
Basic Methodology

Non-Newtonian liquids are used in numerous microfluidics applications, including microscale viscosity and rheology measurements, amplification and sequencing of DNA, fundamental investigations of elastic flows, and development of fluidic memory and control devices. Although these applications span a wide range of flow conditions and non-Newtonian fluid properties, similar experimental methods are used. In this section we summarize some of the experimental considerations for driving non-Newtonian flows, controlling the nature of these flows through the device geometry, and characterizing the non-Newtonian flow behavior.

Methods available to control non-Newtonian flows are the same as for Newtonian flows, including pressure-driven flows via syringe pumps, capillary driven flows, and electrokinetic flows. These methods and others are covered in more detail in other entries. In many cases the behavior of polymer solutions subject to a driving force is similar to that of the corresponding Newtonian solvent as long as the characteristic strain rate remains below the coil-stretch transition, or $\mathrm{De} < \frac{1}{2}$. Above this critical value, shear thinning and elasticity are important.

Pressure-driven flow is one of the most common methods of driving non-Newtonian flows. Below the coil-stretch transition, a polymer solution in a straight microchannel behaves as a Newtonian liquid, exhibiting a parabolic velocity profile $u(x, y)$ and a pressure gradient $\Delta \mathrm{p}$ along the channel axis that is linearly proportional to the volumetric flow rate Q and the total viscosity of the solution $\eta = \eta_\mathrm{s} + \eta_\mathrm{p}$, given by Eq. (2). In a channel with rectangular cross-section, this pressure drop–flow rate relationship is given by

$$\frac{\Delta \mathrm{p}}{L} \cong \frac{12\eta Q}{wh^3}\left[1 - 6\left(\frac{2}{\pi}\right)^5 \frac{h}{w}\right]^{-1} \tag{8}$$

where L is the length of the channel segment, w is the width of the channel, and h is the depth of the microchannel [3]. The approximate expression given here is valid when $h/w < 0.7$. In a pressure-driven flow, the shear rate varies across the channel, with the maximum shear rate occurring at the channel walls. Thus, the dimensionless shear rate is approximately

$$\mathrm{De} = \lambda \dot{\gamma}_\mathrm{w} = \lambda \left.\frac{\partial u}{\partial y}\right|_\mathrm{wall} \approx \frac{6\lambda Q}{wh^2} \tag{9}$$

where y is the dimension across the channel depth (the smallest dimension).

When $\mathrm{De} > \frac{1}{2}$, shear thinning and elasticity influence the velocity and pressure distributions. For example, in a shear thinning liquid described by Eq. (3), the wall shear rate is modified by the exponent n such that

$$\dot{\gamma}_\mathrm{w} = \frac{6Q}{wh^2}\left(\frac{2}{3} + \frac{1}{3n}\right) \tag{10}$$

and the pressure drop for a given volumetric flow rate is modified by the viscosity index m,

$$\frac{\Delta \mathrm{p}}{L} = \frac{2m}{h}\left[\frac{6Q}{wh^2}\left(\frac{2}{3} + \frac{1}{3n}\right)\right]^n \tag{11}$$

In general, an appropriate stress-strain constitutive relationship is needed in order to predict the velocity profile, stress distribution, and pressure drop for a given non-Newtonian liquid [1].

Geometric features such as contractions and expansions can lead to pronounced non-Newtonian flow responses. For example, in a planar contraction with a ratio $\beta = w/w_\mathrm{c}$ of the upstream and downstream channel widths w and w_c, the fluid along the centerline accelerates into the contraction, leading to a significant elongational flow component. The strain rate within the contraction can be estimated by $\dot{\varepsilon}_\mathrm{c} \approx 2Q/w_\mathrm{c}^2 h$. In reality, the local strain rate reaches values several times larger than the characteristic value $\dot{\varepsilon}_\mathrm{c}$ within the contraction [10]. Elastic stresses generated by the predominantly elongational flow through the contraction lead to a pressure drop exceeding the Newtonian value.

In addition to De, which characterizes the role of elasticity in the non-Newtonian flow response, the Reynolds number Re describing the relative magnitudes of inertia and viscous stresses remains an important parameter in contraction flows,

$$\mathrm{Re} = \frac{\rho \bar{V}_{\mathrm{c}} D_{\mathrm{h}}}{\eta} = \frac{2\rho Q}{\eta\left(w_{\mathrm{c}}+h\right)} \tag{12}$$

where $\bar{V}_{\mathrm{c}}$ is the average velocity in the contraction, ρ is the density of the liquid, and D_{h} is the hydraulic diameter of the contraction, $D_{\mathrm{h}} = 2w_{\mathrm{c}}h/\left(w_{\mathrm{c}}+h\right)$. Since both Re and De are linearly dependent on the flow rate Q, these two parameters do not vary independently in experiments. Thus, as elastic effects become more important with increasing De, inertial effects also become more important since Re is also increasing. The ratio of the two dimensionless parameters is the Elasticity number, El,

$$\mathrm{El} = \frac{\mathrm{De}}{\mathrm{Re}} = \frac{\lambda\eta\left(w_{\mathrm{c}}+h\right)}{\rho w_{\mathrm{c}}^{2} h} \tag{13}$$

Note that El depends only on fluid properties and device geometry, and its magnitude describes the rate at which Re changes with De [10].

Electric fields can also be used to drive flows of aqueous polymer solutions, and since most water-soluble polymers carry some charge, it is possible to drive both electrophoretic and electro-osmotic motions. At low field strengths, electrophoretic motions of DNA molecules in electric field gradients can be analyzed exactly analogously to hydrodynamic motions [8]. In addition, some disadvantages of microscale pressure-driven flows can be avoided by using electric fields, including the large shearing components that inevitably accompany such flows, and device failure due to large applied pressures. By placing electrodes at strategic locations within the microfluidic device, one can achieve purely elongational stretching of DNA molecules in the absence of shearing, with an equivalent stretching rate $\dot{\varepsilon}_{\mathrm{EL}}$ and $\mathrm{De}_{\mathrm{EL}} = \lambda\dot{\varepsilon}_{\mathrm{EL}}$.

In all of these approaches to driving non-Newtonian flows in microfluidic devices, the geometry of the device itself plays a key role in determining the nature of the resulting flow. In pressure-driven flow, a straight channel results in pure shearing flow, while a contraction generates a significant elongational component in addition to strong shearing. Stretching flows are accomplished in several other microfluidic geometries including opposing flows in a cross-slot geometry [6], and a hyperbolic converging channel used in conjunction with electric fields [8]. More complex geometries have been designed specifically to create a range of flow types (Eq. (7)) [4, 5]. Microfluidic lithographic fabrication methods offer a significant advantage in these efforts since it is possible to design arbitrarily complex patterns. On the other hand, lithographic fabrication methods are limited to planar patterns, and a given device typically has a uniform depth throughout. In this sense, microfluidic geometries are sometimes more complicated than desired, since the cross-section of the device is rectangular and the aspect ratio of the cross-section varies throughout the device. The complex geometries in most microfluidic devices render interpretation of experiments using simple theories difficult, especially when nonlinear behavior such as non-Newtonian rheology is involved. Many recent studies have employed complementary numerical computations, experiments, and theoretical arguments to aid in the design and analysis of devices.

Finally, measurement and visualization methods are needed in order to analyze and utilize non-Newtonian microfluidic flows. Transparent materials such as glass and PDMS enable a host of optical techniques to be used. Many of these have been used to analyze non-Newtonian flows in microfluidic devices, most notably micro-PIV and related particle imaging techniques, and flow visualization using fluorescent dyes. Pressure taps have also been integrated to measure the non-Newtonian flow response simultaneous to flow visualization [9, 10].

An important visualization technique in non-Newtonian microfluidic flows is single molecule imaging of DNA via fluorescent labeling. The dynamics of bacteriophage DNA have been examined in numerous flow studies, in which DNA chains ranging in length from $2-140\,\mu\mathrm{m}$ have been stained with a fluorescent dye. DNA types that have been imaged include T2, T4, T7, λ-phage, and *E. Coli* DNA, and fluorescent dyes that have been used typically come from the YOYO family [7]. The large size of these molecules permits visualization using a fluorescence microscope with a high NA objective; an intensified CCD camera is needed in order to image individual molecules. At high salt concentrations in aqueous buffer solution, DNA molecules have a persistence length of $l_{\mathrm{p}} \approx 50\,\mathrm{nm}$, and are therefore flexible at these lengths. Using these techniques, the dynamics of DNA molecules have been visualized in a wide range of conditions including microscale hydrodynamic flows [6, 7] and electric field gradients [8].

Key Research Findings

Non-Newtonian effects are important in numerous microfluidics applications. In some cases, microfluidic devices have been designed specifically to characterize the molecular properties and the response of a non-Newtonian liquid in a flow. Other applications involve the use of polymer molecules for specific functions, such as gene amplification and sequencing, in which the non-Newtonian behavior may also play an important role. Still others have used non-Newtonian effects to design functional microfluidic elements. We highlight a few examples here.

Numerous microscale devices and techniques have been developed to characterize the flow behavior of polymer solutions. The principal motivation for this broad class of techniques is to enable characterization of tiny liquid volumes for which samples are costly or difficult to obtain in large quantities. These microfluidic "rheometers" fall into three categories, organized in order of increasing De: devices to measure intrinsic viscosity, shear-rate dependent viscosity, and non-Newtonian behavior for a range of flow types.

At low shear rates $\mathrm{De} < \frac{1}{2}$, polymer chains do not stretch in a flow, but they modify the viscosity according to Eq. (2). Thus, by controlling either the pressure gradient or the volumetric flow rate in a straight microchannel, it is possible to deduce the absolute viscosity of the liquid flowing in that channel using Eq. (8). Furthermore, Eq. (2) shows that the total viscosity of a polymer solution increases relative to the solvent viscosity and the solute concentration. By successively decreasing the concentration of a solute and measuring incremental changes in the viscosity relative to η_s, one can extrapolate the value of intrinsic viscosity $[\eta]$ as the limit of the ratio $\eta_\mathrm{p}/c\eta_\mathrm{s}$ at infinite dilution $c \to 0$. Lee and Tripathi recently reported on a microfluidic network that successively dilutes a sample by mixing two streams, one containing a polymer solution and the other containing a dyed stream of the base solvent [2]. By applying a known pressure at the inlet of each stream and analyzing the flow rate distribution within the network using an electric circuit analogy, the authors show that the ratio of flow rates entering the mixed stream is related to the concentration of polymer in that stream, allowing the authors to measure the fluorescence intensity of the dye and infer the concentration. The device yields intrinsic viscosity measurements for polymer solutions with volumes as small as 3 μL, opening the possibility to characterize high value molecules of biological and pharmaceutical interest, and eliminating the need for manual dilutions that are typical of standard $[\eta]$ measurements.

The flow of a liquid in a microcapillary can also be used to characterize the shear-rate dependent viscosity for larger De values. Srivastava and Burns have reported on a device that draws a liquid droplet into a microchannel via capillary filling [3]. Due to the changing radius of the entering droplet, the pressure gradient within the channel changes with time, and therefore the filling rate and the length of the filled region of the capillary also vary with time and with the viscosity of the liquid. The authors monitored the filling length with time, and used Eqs. (10) and (11) to deduce the viscosity of the liquid as a function of the changing shear rate during the experiment. A reference channel allows the device to self-calibrate, and the results agree well with measurements from a conventional rheometer. The approach taken in this example is also useful because the method of sample loading circumvents the usual "world-to-chip" interface problem faced in many microfluidic devices.

Pressure-driven flows in straight microchannels with uniform cross-section are purely shearing flows ($\xi = 0$ in Eq. (7)). Thus, although the micro-viscometers described in the previous two examples will provide useful information about molecular conformation (through $[\eta]$) and shear flow behavior, they cannot yield information about a liquid's response to any flow that contains elongational components, encompassing many complex microfluidic geometries. Two recent microfluidic devices have been designed to address this need; both devices mimic a conventional, bulk-scale device called a *four roll mill* in which it is possible to generate a wide range of flow types $-1 \le \xi \le +1$. In one microfluidic analog, six channels meet in a cross configuration at a junction [4]. Two pairs of channels are positioned opposite each other with asymmetric baffles in between to offset the opposing flows. The remaining two channels are exit channels oriented perpendicular to the inlet pairs. By adjusting the ratio of the volumetric flow rates entering through the inlet channel pairs, one can vary the flow type parameter from a maximum of $\xi = +1$ to a minimum near $\xi \approx -1$. In this device it is not possible to achieve purely rotational flow. An alternate design reported by Lee et al. offers a similar concept, with opposing flows meeting at a central stagnation region, but in this case both incoming and outgoing channels contain *symmetric* baffles [5]. In this case, varying the flow rate ratio spans the complete range of flow types, including pure rotational flow $\xi = -1$. The performance of both devices is sensitive to the aspect ratio of the channels, requiring validation of the concept using flow visualization experiments and numerical computations. The first device has been used to investigate complex flows of wormlike micelle solutions, but in general neither device has been extensively validated against data from conventional devices.

The previous examples show that various microfluidic geometries can be used to successfully measure the viscoelastic properties of polymer solutions. Together with some of the advantages highlighted above, microfluidic devices offer the benefit that the devices are closed systems with no free surfaces, placing few limitations on the range of fluid viscosities that can be used, beyond pressure limitations on the device materials. On the other hand, there are also potential disadvantages. Most notably, the large surface areas lead to unavoidable shearing effects, which are difficult to de-couple when interpreting the response to elongational or mixed flows. In this vein, shearing within the inlet regions of a device will lead to 'pre-conditioning' of the polymer chain conformations prior to entering the region of interest. Memory of past deformation history can dramatically alter a fluid's response to a flow, which can be either advantageous or detrimental depending on the application.

The ability to fluorescently tag individual DNA molecules and visualize their dynamics in these flows can considerably enhance the information we obtain from these flows. Numerous single molecule visualization experiments have already led to significant advancements in our understanding of polymer chain dynamics in viscous flows. In addition, these experiments have recently been combined with Brownian dynamics simulations, which simulate the motion of bead-rod chains in viscous flows and can quantitatively predict the chain conformation for given flow conditions. This powerful combination has allowed for the validation of detailed molecular scale physics, as well as the development of new physical insights. These conclusions are described in a recent review [7]; we summarize a few of the salient conclusions here.

Arguably the most important new concept to result from single molecule visualization experiments is that of "molecular individualism". In a set of groundbreaking experiments, Perkins, Smith, and Chu placed DNA molecules in a variety of flow conditions and tracked the dynamics of the polymer chains individually. Their observations confirmed several assumptions that had formed the basis for polymer dynamics theories in the absence of the ability to directly measure the chain conformation (although many other measurements supported these hypotheses). Among these, one study observed the dynamics of DNA molecules in dilute solution as they passed through the predominantly elongational flow in a microfluidic cross-slot geometry [6]. The authors collected measurements of the elongation of many individual DNA molecules, and noted several distinct conformation types including folded, kinked, and dumbbell-like configurations. An important observation from these measurements is that the configuration realized by an individual chain is highly sensitive to its initial configuration. This sensitivity to the initial configuration, dubbed 'molecular individualism', leads to highly heterogeneous conformation 'trajectories' as the chains stretch in a flow. Molecular individualism also leads to the idea that 'pre-conditioning' the polymer chains prior to stretching can result in a different flow response. For example, Brownian dynamics simulations have shown that exposing the polymer solution to shearing prior to stretching leads to fewer kinked and folded conformations among the stretched chains. Other studies have shown that in mixed flows, the elongational strain determines the amount of stretching, but the rate of stretching is much slower in mixed flows than in purely elongational flows [7].

Statistics computed from individual measurements form the link between single molecule observations and bulk flow measurements. In the study of Perkins et al. described above, the statistics indicate that the distribution of chain sizes is Gaussian during the majority of stretching; however, when the chains approach full stretch, the statistical distribution becomes highly non-Gaussian. This observation is essential to the development of stress-strain constitutive relationships for polymer solutions. It also helps explain such important observations as 'stress-conformation hysteresis'. Microfluidic devices incorporating non-Newtonian flow have played a central role in developing these conclusions [7].

A novel method for gene sequencing builds upon the ideas developed from single molecule experiments. The idea is to sequence individual DNA strands by directly detecting each base pair along the backbone [8]. To implement this concept, the DNA strand must be fully elongated. While this can be accomplished by exposing the molecules to an elongational flow, the sensitivity of the stretching profile to the initial chain conformation and the degree of shearing in the flow renders hydrodynamic methods impractical. Instead, it has been noted that electric field gradients can efficiently stretch DNA molecules using the charge along the backbone, as we described earlier. Randall and Doyle have presented a method to use electrophoretic motions of DNA in electric field gradients to stretch long DNA strands [8]. In particular, electric fields can be used to achieve pure stretching in the absence of uncontrolled shear flows, such as those that occur in hydrodynamic flows due to the no-slip condition at the walls. Randall and Doyle present a two-step microfluidic process that is designed to control molecular individualism by pre-conditioning the molecular conformation using a gel matrix to pre-stretch the molecules upstream, and then using electric field gradients to further stretch the molecules inside a hyperbolic contraction downstream. The authors show that this method is an efficient alternative to hydrodynamics for achieving continuous stretching of long strands of DNA.

Many microfluidic geometries are not as simple as those described above, and the *mixed* flow type within complex geometries can lead to other interesting flow behaviors, especially at elevated De values. For example, contraction flows of highly elastic non-Newtonian fluids can be unstable due to the interaction of elastic stresses with streamline curvature in the vortices upstream of the contraction. The upstream vortices grow relative to the New-



Non-Newtonian Fluids in Microfluidics, Figure 3 Deborah number – flow type phase diagram depicting the range of flow conditions utilized in each of the examples discussed

tonian case as De increases. At high enough flow rates, the vortex structure becomes unstable and begins to fluctuate, contributing to the measured overall pressure drop. As described earlier, De and Re do not vary independently in these flows (see Eqs. (12) and (13)), and their ratio contains a geometric length scale, suggesting that microscale contractions can be useful in accessing new regions of the De–Re phase space. Recently, Rodd and McKinley utilized this control over the geometric length scale to perform fundamental studies of viscoelastic contraction flows, measuring the pressure drop and the vortex lengths as functions of De, mapping the steady flow patterns as a function of De and Re, and characterizing the onset of inertio-elastic flow transitions [10]. These nonlinearities and instabilities have also been utilized to design functional microfluidic components. For example, as elastic instabilities develop and grow at larger De values, the flow becomes chaotic and has the ability to enhance mixing (see ▶ chaotic mixing based on viscoelasticity). In addition, the nonlinearity inherent in viscoelastic contraction flows has led to the design of microfluidic memory and control devices, including a 'fluidic diode' in which flux is significantly easier in one direction, and a bistable 'flip-flop' which utilizes an elastic instability to modulate the direction of flow at a junction [9].

Based on the examples described, it is clear that at least two essential factors determine the nature of a microscale non-Newtonian flow: the dimensionless strain rate, or De, and the device geometry or the flow type. The utility of each device relies on the ability to operate within a particular range of De and ξ values. Fig. 3 shows a schematic diagram of the De–ξ phase space for non-Newtonian flows, indicating the region of interest for the applications described.

Future Directions for Research

Non-Newtonian flows will remain important in microfluidic applications as long as there is the need to transport and characterize long chain molecules such as DNA and proteins. In fact, increasingly longer strands of DNA are becoming common in gene sequencing and amplification. Thus the development of new ideas for manipulating and characterizing those molecules will be essential to the success of future microfluidic devices. In addition, an understanding of the non-Newtonian behavior in microfluidic devices can be helpful in optimizing the performance of newly developed assays incorporating large macromolecules and particles. Most of the applications highlighted here are just in their beginning stages, and future research will inevitably focus on further development, validation, and uses for these techniques.

Cross References

- ► Capillary Filling
- ► Chaotic Mixing Based on Viscoelasticity
- ► Electrophoresis
- ► Fluorescent Labeling
- ► Lab-on-a-Chip Devices for Particle and Cell Separation
- ► Microscale Flow Visualization
- ► Non-Newtonian Fluids in Microchannel
- ► PCR Lab-on-Chip Devices
- ► Polymer Synthesis within Microfluidic Reactors
- ► Pressure-Driven Single Phase Liquid Flows
- ► Viscoelasticity

References

1. Larson RG (2000) Structure and Rheology of Complex Liquids. Oxford Univ Press, New York
2. Lee J, Tripathi A (2005) Intrinsic viscosity of polymers and biopolymers measured by microchip. Anal Chem 77:7137–7147
3. Srivastava N, Burns MA (2006) Analysis of non-Newtonian liquids using a microfluidic capillary viscometer. Anal Chem 78:1690–1696
4. Hudson SD, Phelan FR, Handler MD, Cabral JT, Migler KB, Amis EJ (2004) Microfluidic analog of the four-roll mill. Appl Phys Lett 85:335–337
5. Lee JS, Dylla-Spears R, Teclemariam NP, Muller SJ (2007) Microfluidic four-roll mill for all flow types. Appl Phys Lett 90:074103
6. Perkins TT, Smith DE, Chu S (1997) Single Polymer Dynamics in an Elongational Flow. Science 276:2016–2021
7. Shaqfeh ESG (2005) The dynamics of single-molecule DNA in flow. J Non-Newtonian Fluid Mech 130:1–28
8. Randall GC, Schultz KM, Doyle PS (2006) Methods to electrophoretically stretch DNA: microcontractions, gels, and hybrid gel-microcontraction devices. Lab Chip 6:516–525
9. Groisman A, Enzelberger M, Quake SR (2003) Microfluidic memory and control devices. Science 300:955–958
10. Rodd LE, Scott TP, Boger DV, Cooper-White JJ, McKinley GH (2005) The inertio-elastic planar entry flow of low-viscosity elastic fluids in micro-fabricated geometries. J Non-Newtonian Fluid Mech 129:1–22

Nucleation

Definition

Initiation of any material growth process where atoms cluster together to provide the starting point for further growth. The nucleation process is governed by the energetics of atomics clusters.

Cross References

- ► Bubble Dynamics in Microchannels
- ► Fabrication of Self-Assembled Catalytic Nanostructures

Nucleation and Growth

Synonyms

Deposition; Precipitation; Crystallizaiton

Definition

A process of nanoparticle generation. Raw materials for nanoparticles (monomers) transform to make embryos, forming under which can grow to particles. Here, embryos and nuclei can be distinguished by its thermodynamic stability. Embryos have smaller size than the nucleus and thermodynamically unstable. The nuclei are said to be thermodynamically stable and grow into larger particles.

Cross References

- ► Nanoparticle Synthesis in Microreactor

Nucleic Acid Detection

- ► SNP on Chip – Micro- and Nanofluidics for Single Nucleotide Polymorphism Discrimination

Nucleus

- ► Kernel Function

Number-Average Molecular Weight

Synonyms

Mn

Definition

It is determined by measuring the molecular weight of *n* polymer molecules, summing the weights, and dividing by *n*.

Cross References

- ► Polymer Synthesis within Microfluidic Reactor

Numerical Discretization

- ► Discretization

Numerical Simulation

- ► Lattice Poisson–Boltzmann Method, Analysis of Electroosmotic Microfludics
- ► Micro- and Nanoscale Gas Fluidics

Numerical Solution of Boltzmann Equation

RAMESH AGARWAL[1], FELIX G. CHEREMISIN[2],
SUBRATA ROY[3]
[1] Aerospace Research and Education Center (AeREC) and Aerospace Engineering Program,
Washington University, St. Louis, MO, USA
[2] Russian Academy of Science, Moscow, Russia
[3] University of Florida, Gainesville, FL, USA
rka@me.wustl.edu, cherem@ocas.ru, roy@ufl.edu

Synonyms

Wang-Chang–Uhlenbeck equation; Generalized Boltzmann equation; Flow simulations in transitional and rarefied regimes

Definition

The Boltzmann equation describes the behavior of gas flows in non-equilibrium due to molecular motion. It is applicable for all mean free paths λ between the molecules, that is, for all Knudsen numbers Kn ($=\lambda/L$, where L is a characteristic dimension in the flow). Thus it can be employed to calculate the flow fields in a variety of applications ranging from hypersonic flow past a space shuttle to flow in microdevices, where all the flow regimes – continuum ($\mathrm{Kn} \to 0$), transitional ($\mathrm{Kn} \sim O(1)$) and rarefied ($\mathrm{Kn} \gg 1$) – may be encountered. The classical Boltzmann equation (CBE) describes the flow of monatomic gases (such as argon and helium) in translational non-equilibrium. The behavior of polyatomic gases (such as nitrogen and oxygen) is described by the generalized Boltzmann equation (GBE) or Wang-Chang–Uhlenbeck equation (WC–UE) [1], wherein the internal (rotational and vibrational) and translational degrees of freedom are considered in the framework of quantum and classical mechanics respectively. The molecular motion in the Boltzmann equation is described by a distribution function f which describes both the motion of the molecules and their collisions. The motion of the molecules is described by a convective differential operator while the molecular collisions result in an integral in molecular velocity space. Thus the Boltzmann equation is an integrodifferential equation whose numerical solution becomes quite a difficult task. One of the most widely used methods for the numerical solution of the Boltzmann equation is due to Cheremisin and his colleagues at the Russian Academy of Science in Moscow [2]. In this method the convective operator is discretized by an explicit scheme and the collision integral is solved by the method of discrete ordinates. A two-step method for time integration is employed that sequentially includes the convective step and the collision step.

Overview

In principle, the Boltzmann equation describes the flow at all Knudsen numbers Kn. For very small values of Kn (say < 0.01), the flow approaches the continuum regime, while for very large values of Kn (say > 10), the flow can be considered free molecular. When $\mathrm{Kn} = O(1)$, the flow is in the continuum transition regime. In the continuum regime, Navier–Stokes equations can accurately predict the flow field, while for $\mathrm{Kn} > 1$, the direct simulation Monte Carlo (DSMC) method [3] can be successfully employed. However in a variety of applications ranging from hypersonic flow past a space shuttle to flow in microdevices, part of the flow field may be in the transition regime. In the transition regime, both the Navier–Stokes equations and the DSMC method have significant limitations. Navier–Stokes equations are no longer accurate because of significant departure from equilibrium and the DSMC method becomes computationally prohibitive because of the large number of particles required for accurate simulations. A number of alternative approaches have been proposed and investigated in the literature such as the Burnett equations, Grad's moment equations or Eu's equations. These equations collectively are known as the extended hydrodynamics (EHD) equations. However, the progress has been limited and furthermore the accuracy of the EHD equations remains questionable because of the asymptotic nature of the Chapman–Enskog expansion (e. g. for the Burnett equations), the issues related to regularization and the difficulty in imposing the exact kinetic boundary conditions on the surface of the body.

Physically, gas flows in the transition regime, where Kn is O(1), are characterized by the formation of narrow, highly non-equilibrium zones (Knudsen layers) of thickness of the order of the molecular mean free path λ; the flow structure is then determined by the fast kinetic processes. Moreover, in the case of unsteady flows, an initial Knudsen time interval is of the order $\tau_0 = \lambda/v$, where v is the molecular velocity. Thus, the Knudsen layer can be computed accurately only by directly solving the Boltzmann equation.

For calculating the non-equilibrium flow of polyatomic gases, the DSMC method is currently the most widely used technique. In the DSMC approach, one usually employs some empirical models [4], which very much resemble a BGK type relaxation model with a constant relaxation time. There are only a few attempts due to Koura [5] and Erofeev [6], for example, which employ the so called *trajectory calculations*, where a realistic modeling of inelastic collisions with translational–rotational (T–R) transfer of energy is made. These computations require enormous CPU time. For vibrational excitations, no trajectory calculations with the DSMC method have been attempted to date. The physical reality is such that the vibrational term becomes important at much higher temperature than the rotational term. For the N_2 molecule the quanta of vibrational temperature is 3340 K and the quanta of rotational temperature is 2.89 K; the corresponding quanta for the O_2 molecule are 2230 and 2.1 K respectively. Therefore, rotational energy levels are important at all temperatures, but the vibrational energy levels are important only at high temperatures. Thus, each vibration energy level splits into a high number of rotational energy levels. The characteristic relaxation times for T–T, T–R, and T–V transfer of energy are in the proportion of about $1:5:100$ (or several thousands). A good physical assumption is that the translational and rotational energy are in thermodynamic equilibrium during the vibrational relaxation process.

Taking into account the above observations, let us consider hypersonic flow at different Knudsen numbers. If $\mathrm{Kn} > 1$, then no internal energies need to be taken into account, except the reactions at the boundaries. If $0.1 < \mathrm{Kn} < 1$, only the rotational levels play a role. For $\mathrm{Kn} < 0.01$, in the majority of the flow field the rotational and translational energies can be considered in equilibrium, but the vibrational relaxation continues. What can therefore be expected in the case of a shock wave (SW) at high Mach number? At the beginning, the SW structure will be formed by T–T and R–T transfers and the structure should be the same as in a gas having no vibrational levels. This SW structure with a characteristic length of about 10 mean free paths will be followed by a large zone of the size of several hundreds of mean free paths formed by the vibrational excitation. Therefore, the computation of the SW structure including the vibrational excitation becomes much more difficult than that with only T–R exchange. The computations with both the rotational and vibrational energy levels will include $N_{\mathrm{total}} = N_{\mathrm{r}} \times N_{\mathrm{v}}$ levels ($N_{\mathrm{r}} =$ number of rotational levels and $N_{\mathrm{v}} =$ number of vibrational levels) which are equivalent to a gas with N_{total} components. These computations thus require significant computational resources. It is therefore important to reduce the numbers N_{r} and N_{v} for efficient calculations without sacrificing the accuracy. Further increase in the efficiency can be obtained by exploiting the big difference between the rotational and vibrational characteristic times. As mentioned before, vibrational degrees of freedom become important when the flow is in rotational–translational equilibrium. Therefore, under such conditions, $N_{\mathrm{total}} = N_{\mathrm{v}}$. Further efficiency can be achieved by using the simplified molecular potentials, for example the inverse power potential and simple R–T cross-sections.

The solution of the GBE at high Mach numbers requires both large memory and CPU time. Following Cheremisin's work on a monatomic gas [2], one can employ a large time step in velocity space (of the order of the mean thermal velocity) ahead of the SW in the GBE code. It is also possible to use fewer levels (6 to 10) in the rotational spectrum to reduce both the memory and CPU requirements as described by Agarwal et al. [7]. Another source of large CPU time in the currently used time-explicit algorithm for solution of the Boltzmann equation is the requirement of a very small time step which results from the condition that the distribution function remains positive after the relaxation stage. For example, for a monatomic gas, at Mach 20, the time step is of the order of 0.001 of the mean free path time. In order to overcome this problem, two strategies can be employed: (a) use a filter that excludes the negligibly small contributions to the collision integral and (b) modify the algorithm to a mixed explicit–implicit scheme to increase the time step by at least a factor of 10. All these improvements result in an accurate and efficient GBE solver for computing the flow field of a diatomic gas at high Mach numbers including the rotational and vibrational excitations.

Basic Methodology

It should be noted that the GBE [8] replaces the classical WC–UE for the case when energy levels are degenerate. In its mathematical form, the GBE is similar to WC–UE and differs from the latter by a factor related to the statistical weights of the levels. Thus, the GBE gives the equilibrium spectrum different from WC–UE. The GBE has the form

$$\frac{\partial f_i}{\partial t} + \xi \frac{\partial f_i}{\partial \boldsymbol{x}} = R_i \,. \tag{1}$$

The collision operator is given by

$$R_i = \sum_{jkl} \int_{-\infty}^{\infty} \int_{0}^{2\pi} \int_{0}^{b_m} \left(f_k f_l \omega_{ij}^{kl} - f_i f_j \right) P_{ij}^{kl} g b \,\mathrm{d}b \,\mathrm{d}\varphi \,\mathrm{d}\xi_j \,. \tag{2}$$

Here f_i is the distribution function for the energy level i, P_{ij}^{kl} is the probability of the transfer from levels i, j to levels k, l, and the factor $\omega_{ij}^{kl} = (q_k q_l)/(q_i q_j)$ (q_i being the degeneracy of the energy level). For simple levels, the GBE changes to the WC–UE; therefore it can also be considered as a more general form of the latter. In [8] the GBE was obtained directly from WC–UE by grouping the q_i single levels that have the same energy and form a degenerate level.

Let us consider molecular nitrogen having the Lennard–Jones potential (6–12), given in Ferziger and Kaper [9], with the depth of the energy hole $\varepsilon = 91\,\mathrm{K}$, degeneracy of rotational level $q_i = 2i + 1$, $i = 0, 1, \ldots \infty$, and the rotational energy of the level $e_{ri} = \varepsilon_0 i(i+1)$, $\varepsilon_0 = 2.9\,\mathrm{K}$. The molecular interaction during the collision consists of two phases. In the first phase, the molecules interact in an elastic manner according to the molecular potential. This stage determines the deviation angle of the relative velocity. In the second stage, the modulus of the relative velocity changes according to the energy conservation equation. For the transition probabilities P_{ij}^{kl} we apply the formulas given in [7] that are obtained by fitting the experimental data of molecular dynamics simulations of interactions of rigid rotors that model N_2 molecules:

$$P_{ij}^{kl} = P_0 \omega_{ij}^{kl} \left[\alpha_0 \exp\left(-\Delta_1 - \Delta_2 - \Delta_3 - \Delta_4 \right) + \frac{1}{\alpha_0} \exp\left(-\Delta_3 - \Delta_4 \right) \right],$$

where

$$\Delta_1 = \frac{|\Delta e_1 + \Delta e_2|}{e_{tr0}} \,, \qquad \Delta_2 = 2\frac{|\Delta e_2 - \Delta e_1|}{e_{\mathrm{tot}}} \,,$$

$$\Delta_3 = 4\frac{|\Delta e_1|}{(e_{tr0} + e_{ri})} \,, \qquad \Delta_4 = 4\frac{|\Delta e_2|}{\left(e_{tr0} + e_{rj}\right)} \,,$$

$$\Delta e_1 = e_{ri} - e_{rk} \,, \qquad \Delta e_2 = e_{rj} - e_{rl} \,,$$

$$\alpha_0 = 0.4\frac{e_{\mathrm{tot}}}{e_{tr0}} \,, \qquad e_{tr0} = \frac{mg^2}{4} \,,$$

$$e_{\mathrm{tot}} = e_{tr0} + e_{ri} + e_{rj} \,.$$

The energy conservation law in a collision selects virtual collisions with nonzero probability. From the equation

$$\frac{mg_{ij}^2}{4} + e_{ri} + e_{rj} = \frac{mg_{kl}^2}{4} + e_{rk} + e_{rl}$$

it can be shown that $P_{ij}^{kl} > 0$, if $g_{kl}^2 \geq 0$, otherwise $P_{ij}^{kl} = 0$. The elastic collision is a particular case of the collision. The probabilities obey the normalization condition $\sum_{k,l} P_{ij}^{kl} = 1$. The kinetic equation (1) is solved by the splitting scheme described by Cheremisin [2]. At a time step $\tau < \tau_0$, where τ_0 is a mean intercollision time, Eq. (1) is replaced by the sequence of equations

$$\text{(a)} \quad \frac{\partial f_i}{\partial t} + \xi \frac{\partial f_i}{\partial \boldsymbol{x}} = 0 \,, \qquad \text{(b)} \quad \frac{\partial f_i}{\partial t} = R_i \,.$$

The collision operator R_i is evaluated at the uniform grid S_0 in the velocity space by the conservative projection method proposed in [2].

Sample Results on Computation of Shock Structure

Some sample results on the computation of shock structure in nitrogen in rotational and vibrational non-equilibrium are presented here in two parts: (a) the computations are presented for shock structure in nitrogen including the rotational degrees of freedom up to Mach 15 by solving the complete WC–UE with a number of energy levels, and (b) the computations are presented for shock structure in nitrogen with both rotational and vibrational degrees of freedom by solving the complete WC–UE for V–T relaxations and employing the two-level kinetic model for R–T relaxations. Some of the details of this two-level kinetic model for R–T relaxations are not given here but can be obtained from Morse [10]. The model reproduces the results obtained by the complete WC–UE.

(a) The SW structure is formed as a final stage of the evolution of discontinuity in the initial distribution function. The problem is considered for the interval $-L_1 \leq x \leq L_2$ with the discontinuity at $x = 0$. The initial distribution function on both sides of the discontinuity is described by the velocities and spectral levels. It has the form

$$f_i^{1,2}(\xi, x) = n^{1,2} \left[\frac{m}{2\pi T^{1,2}} \right]^{\frac{3}{2}} \left[-\frac{m\left(\xi - u^{1,2}\right)^2}{2T^{1,2}} \right] \times \frac{2i+1}{Q_r} \exp\left(-\frac{e_{ri}}{T^{1,2}} \right)$$

where Q_r denotes the statistical sum. Parameters $(n, T, u)^{1,2}$ are defined by the Rankine–Hugoniot relations with $\gamma = 7/5$. At the boundary the initial distribution function is kept constant.



Numerical Solution of Boltzmann Equation, Figure 1 Shock wave structure in nitrogen for $M = 15$; n = density, T = translational temperature, Txx = longitudinal translational temperature, Trot = rotational temperature (normalized)



Numerical Solution of Boltzmann Equation, Figure 2 Shock wave structure in nitrogen for $M = 10$; n = computed density, n, experiment = experimental density, T = translational temperature, Txx = longitudinal translational temperature, Trot = rotational temperature (normalized)

For moderate Mach numbers, the SW structure in nitrogen can be computed with real values of the spectral energy gap ε_0, but for the hypersonic case the needed number of levels becomes too high (up to 50 – 70 levels) and therefore the computations become very time consuming. To facilitate this problem it is possible to increase this energy gap and thereby reduce the number of levels. By conducting numerical experiments at Mach 4, it was determined that this increase in spectral energy gap does not influence the results of calculations in any significant way. Figure 1 shows an example of hypersonic SW structure in nitrogen at Mach 15, computed with 16 levels instead of nearly 70 “natural” levels. These types of calculations compare well with the experiments of Alsmeyer [11] for density n for reported Mach numbers up to 10. Figure 2 shows the comparison for density distribution at Mach 10 between the computation and experimental data; excellent agreement is obtained.



Numerical Solution of Boltzmann Equation, Figure 3 Shock wave structure in a monatomic gas for $M = 25$; n = density, T = translational temperature, Txx = longitudinal translational temperature (normalized)

Figure 3 shows the hypersonic SW structure in a monatomic gas at $M = 25$. It should be noted that for this case, the temperature behind the SW increases about 200 times, which makes the computation very difficult; it required an important improvement to the algorithm.

(b) In this part we consider the gas with both rotational and vibrational degrees of freedom. The interaction potential is the Lennard–Jones potential with parameters of nitrogen taken at room temperature of 300 K. The vibrational spectrum corresponds to nitrogen with energy gap of 3340 K. For the rotational spectrum the energy quantum was increased against the actual (which is equal to 2.9 K) for reducing the number of the levels as described before in part (a). The probabilities of R–T transfers are taken from the data of mathematical simulation by Beylich [8]. The probabilities of V–T transfers are generally accepted to be much smaller than those of the R–T transfers and are in the range of 0.005 – 0.001 of the elastic collision probability. As mentioned above, V–T transfers are computed using WC–UE and the R–T transfers are computed using the two-level kinetic model to simplify the computations. Computations are performed at Mach 6 and 10.



Numerical Solution of Boltzmann Equation, Figure 4 Shock wave structure in nitrogen at $M = 6$; $n =$ density, $T =$ translational temperature, Tvib = vibrational temperature, Trot = rotational temperature, Txx = longitudinal translational temperature



Numerical Solution of Boltzmann Equation, Figure 5 Shock wave structure in nitrogen at $M = 10$; $n =$ density, $T =$ translational temperature, Tvib = vibrational temperature, Trot = rotational temperature, Txx = longitudinal translational temperature

In Figs. 4 and 5, the density, total translational, parallel translational, vibrational and rotational temperatures are shown. It is important to note that the vibrational temperature does not reach the equilibrium state with translational and rotational temperatures. This is due to the large energy quantum of the vibrational spectrum. The deviation from the equilibrium diminishes when Mach number increases. The SW structure is characterized by two phases. In the first phase, the elastic and R–T collisions are essential and the influence of V–T transfers is negligible. The translational temperature here rises above the equilibrium value. The rotational and translational temperatures reach the equilibrium at the end of this stage. At the second stage the gas energy goes to the vibrational degrees of freedom and the above indicated temperatures decrease. At Mach 6, the vibrational spectrum consists of four levels which are sufficient to cover the entire energy range. At Mach 10, the number of needed levels is eight. In Figs. 4 and 5, a part of the x-axes is shown. The computations were made for $x = (-120, 250)$. The deviation of the final vibrational temperature from the equilibrium T–R temperatures decreases when the Mach number increases and thus the temperature behind the SW increases.

Key Research Findings

For computing the non-equilibrium flow fields of polyatomic gases in all flow regimes ranging from continuum to transitional to rarefied, the WC–UE or GBE can be successfully solved numerically to account for both the RT and VT energy transfers in very high Mach number flows. The biggest challenge is the computational efficiency for high Mach number flows using the complete GBE or WC–UE including both the RT and VT energy transfers. This issue has been addressed by reducing the number of energy levels for RT relaxations by increasing the ground state energy quantum (e. g. for Mach 15 flow, we have demonstrated that it is possible to reduce the number of levels from 70 to 16), by coarsening the grid in the velocity space without compromising the accuracy, and by treating the convective operator implicitly.

In addition, a newly developed BGK type 2-level model for R–T energy transfers (2LRT) can be employed to reproduce the calculations of the complete WC–UE; however 2LRT is 20 times faster. Thus the computations including both the R–T and V–T relaxations can be performed efficiently using the 2LRT since the number of vibrational energy levels required is usually four to six even at high Mach numbers. For example, at Mach 15, the complete solution of the WC–UE will require total number of levels $= N_r \times N_v = 70 \times 6 = 420$. With 2LRT, we require only 12.

Furthermore, it is important to note that the quantum of rotational energy for diatomic gases such as nitrogen and oxygen is much smaller than that of vibrational energy; therefore accounting for the rotational spectra is important for all Mach numbers for flows with Kn below 0.3 or so. The influence of vibrational energy should be taken into account for high Mach numbers and much smaller Kn. For Kn > 0.3, the CBE can be applied.

Future Directions for Research

The basic methodology presented here should be extended to a mixture of reactive gases. In addition, several improvements can be made for increasing the efficiency of the computations:

- implicit treatment of the convective operator,
- efficient treatment of collision integral in velocity space by employing the conservative projection method,
- increasing the ground state energy quantum of rotational energy to reduce the number of energy levels required at high Mach numbers, and
- including the adaptive meshing and parallelization in the Boltzmann solver.

Cross References

- ► Lattice Boltzmann Method (LBM)
- ► Molecular Dynamics Simulation Method
- ► Monte Carlo Method
- ► Multiscale Modeling and Numerical Simulations

References

1. Cheremisin FG (2002) Solution of the Wang Chang–Uhlenbeck Master Equation. Doklady Phys 47:872–875
2. Cheremisin FG (2004) Solution of the Boltzmann Kinetic Equation for High Speed Flows of a Rarefied Gas. In: Proceedings of the 24th international symposium on rarefied gas dynamics, Bari, Italy, 10–16 July 2004
3. Bird GA (1994) Molecular Gas Dynamics and the Direct Simulation of Gas Flows. Oxford Science Publications, New York
4. Koura K (1994) A Set of Model Cross-Sections for the Monte Carlo Simulation of Rarefied Real Gases: Atom-Diatom Collisions. Phys Fluid 6:3473–3486
5. Koura K (1997) Monte Carlo Direct Simulation of Rotational Relaxation of Diatomic Molecules Using Classical Trajectory Calculations: Nitrogen Shock Wave. Phys Fluid 9:3543–3549
6. Erofeev AI (2002) Study of a shock Wave Structure in Nitrogen on the Basis of Trajectory Calculations of Molecular Interactions. Fluid Dyn 6:134–147
7. Agarwal RK, Chen R, Cheremisin FG (2007) Computation of Hypersonic Shock Wave Flows of Diatomic Gases Using the Generalized Boltzmann Equation. AIAA Paper 2007–4541 presented at the 39th AIAA Thermophysics Conference, Miami, FL, 25–28 June 2007
8. Beylich AA (2000) An Interlaced System for Nitrogen Gas. In: Proceedings of CECAM Workshop, ENS de Lyon
9. Ferziger JH, Kaper HJ (1972) Mathematical Theory of Transport Processes in Gases. North Holland, Amsterdam–London
10. Morse TF (1964) Kinetic Model for Gases with Internal Degrees of Freedom. Phys Fluids 6:159
11. Alsmeyer H (1976) Density profiles in Argon and Nitrogen Shock Waves Measured by the Absorption of an Electron Beam. J Fluid Mech 74:497–513

Numerical Stability

► Stability

Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking

ALI JAFARI, NASSER ASHGRIZ
Department of Mechanical and Industrial Engineering,
University of Toronto, Toronto, ON, Canada
ashgriz@mie.utoronto.ca

Synonyms

Volume tracking; Surface tracking; Surface capturing; Interfacial flow modelling

Definition

Numerical techniques for free surface flows refer to methods for solving multiphase flows of liquids and gases with sharp moving and deforming interfaces. The solution of these types of flows is complex since the boundary between the two phases is not known a priori and it is part of the solution. In addition, the problem usually involves fluid flows with very large density, viscosity and velocity ratios. This makes the solution of the governing partial differential equations (PDEs) very difficult. Several numerical techniques have been developed to tackle this complex fluid flow. They can be categorized based on the type of flow modeling (Eulerian, Lagrangian or mixed), type of interface modeling (capturing or tracking), type of flow–interface coupling (integrated or segregated) and type of spatial discretization (meshless, finite difference, finite volume, finite element or others).

Overview

Free surface flows and interfaces between two or more immiscible fluids or phases are observed in many natural and industrial processes at macro- and microscales. Different numerical techniques are developed to simulate these flows. However, due to the complexity of the problem, each technique is tailored to a particular category of flows. Finite element (FE), finite volume (FV) and finite difference (FD) methods are all potentially applicable to generalized Navier–Stokes equations. However, they have to be coupled with a technique to track moving fluid boundaries and interfaces. The difficulty in tackling interfacial flows is inherently related to the complexity of interface topology and the fact that the interface location is unknown.

There are two main categories of interface solvers. The first category of methods involve mesh motion and deformation while the second group are based on fixed grids. In the moving mesh methods, the grid points move according to the local flow characteristics. In most cases where all grid points are moved, the method is Lagrangian; otherwise, it is a mixed Lagrangian–Eulerian approach. These include methods such as FE-based Lagrangian [1], interface fitting (or boundary-fitted coordinate) [2] and boundary integral [3] approaches. In these methods, the grid points near the interface essentially play the role of marker points. Thus, these techniques are confronted with difficulties when applied to large surface deformations, surface breaking and merging.

Interface fitting methods, Fig. 1a, are efficient and accurate in the study of shaping processes of viscous materials. However, these methods rapidly become inappropriate, indeed impossible, to apply with less viscous materials that undergo large deformations. Mesh regenerations are necessary when mesh cells and elements become highly skewed, to prevent computational failures. This can make the interface fitting scheme and other moving mesh techniques become very complicated and inefficient.

The fixed grid methods, on contrast, operate in the pure Eulerian and, sometimes, combined Lagrangian–Eulerian framework. The main distinction between moving mesh and fixed mesh lies in the fact that fixed mesh methods use an additional agent such as a Lagrangian marker or indicator function to follow the interface motion instead of grid points used by moving mesh methods. The fixed grid methods are divided into three main categories: interface capturing (Fig. 1b), interface tracking (Fig. 1c) and combined interface capturing–interface tracking techniques. Examples of interface capturing methods include marker and cell (MAC) [4], volume of fluid (VOF) [5, 6], level set (LS) [7], and diffuse interface (DI) (or phase field) [8] methods. The most widely used interface tracking method is Glimm's front tracking method [9]. The notable combined techniques which inherit from both interface capturing and interface tracking methods are Tryggvason's front tracking [10], sharp interface (SI) [11], immersed boundary (IB) [12] and immersed interface (II) [13] methods.

Techniques based on interface tracking and interface capturing avoid the grid-related problems associated with interface fitting methods by employing a grid which is fixed and by defining the location of the liquid and gas regions relative to the fixed grid. This practice requires an enlargement of the computational domain to encompass the entire container, since the free surface can potentially occupy any position within the fixed grid. In general, interface capturing methods can handle complex interfacial regions more easily, but interface tracking methods give a more accurate description of the free surface because of their Lagrangian nature. In interface tracking methods, the position of the free surface is described in a direct way; either by specifying a set of marker points located on the free surface [9] or by introducing a height function which explicitly describes the free surface position [14]. Furthermore, in interface tracking schemes, implementation of the surface tension force is straightforward given the location and curvature of the free surface. The limitation of these methods, unlike interface capturing methods, is their inability to cope naturally with folding or rupturing interfaces.

In the interface capturing techniques, the interface motion can be reproduced using different approaches. In MAC, hundreds of massless marker particles are added to the fluid. These particles are then advected in Lagrangian sense using the average of Eulerian velocities in their vicinity. In the VOF method, the use of volume fractions to mark the fluid regions is adopted because of its efficiency and simplicity and the natural way in which complex interfaces can be treated as internal moving boundaries. The volume fractions are convected through the flow domain by solving a scalar convection equation. In the level set method, a smooth distance function is used as the indicator function for the interface. A similar approach is taken in the diffuse interface method, by devising an equation which governs the continuity of mass concentration. The methods of using volume fractions, level sets or mass concentration are robust enough to handle the breakup and coalescence of fluid masses.

The advantage of LS and DI techniques over the VOF method is that their indicator functions are smooth, rather than discontinuous, and are easier to solve. Another advantage of the LS and DI methods over the MAC method is that these two techniques do not suffer from the lack of divisibility that discrete particles exhibit. There are highly accurate numerical schemes that can be applied to the level set equation. The disadvantage of level set method, however, is that the level set needs to be reset periodically which is not strictly mass conservative. The DI method models interfacial forces as continuum forces by smoothing interface discontinuities and forces over thin but numerically resolvable layers. This smoothing allows use of conventional numerical approximations, sometimes even central differencing, of interface kinematics on fixed grids with acceptable accuracy. This is because the DI method relies on the physical mechanisms on which it is based, rather than special numerical schemes to capture the interface.

Given the shortcoming of different interface solution techniques such as interface tracking and capturing methods and considering their strengths, progress has been made by combining different methods and taking advantage of the best features of each technique while removing or alleviating their drawbacks. A class of promising techniques is the combined Eulerian–Lagrangian meth-



Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 1 Different interfacial flow solution methodologies: (**a**) interface fitting; (**b**) interface capturing; (**c**) interface tracking [15]

ods which have the potential to deliver both accuracy and efficiency. This class of methods combines some features of the Eulerian and Lagrangian approaches. The interface is tracked explicitly as curves (or surfaces in three dimensions). The computations are performed on fixed meshes whose topology is independent of that of the interface. One example of this type of method is the immersed boundary technique used for a range of multi-fluid problems [10, 11] and for fluid–structure interaction problems. While explicitly tracking the interface, this method transmits the information regarding the discontinuity across the interface to the grid in much the same way as purely Eulerian methods, i. e. by casting the surface forces into a body force term in the governing equations. Therefore the solution reverts to a single-fluid approach, i. e. the solver does not see a discontinuity at the location of the interface, but experiences distributed forces and material properties in the vicinity of the interface. On the other hand, the cut-cell treatment [11] proceeds to reconstruct the domain on either side of the interface with attention to the immersed boundary and its geometry overlying the grid. Phases are treated separately and no smearing of the interface takes place at the formulation level.

In the following sections, first, different formulations of interfacial flows are presented. Then, different interface solution techniques are presented with the details of each method to the extent possible.

Basic Methodology

Fluid Flow Formulations

Let us consider an arbitrary control volume Ω with boundary $\partial\Omega$ containing a portion of the two fluids. Both fluids divide the volume into two sub-volumes Ω_1 and Ω_2 by the interface Γ. The flow equations can be written in two different forms: two-fluid and single-fluid formulations.

Two-Fluid Formulation

The two-fluid formulation consists of solving the governing equations in both phases independently and then matching the interfacial boundary conditions at the interface, which usually requires an iterative algorithm. This approach keeps the interface as a discontinuity, consistent with the continuum mechanics concept. For each phase, we can write the following momentum equation along with the incompressibility constraint:

$$\frac{\mathrm{D}(\rho_i \boldsymbol{u}_i)}{\mathrm{D}t} = \nabla \cdot \boldsymbol{\Pi}_i + \rho_i \boldsymbol{g}$$
$$\nabla \cdot \boldsymbol{u}_i = 0 \quad \boldsymbol{x} \in \Omega_i\,, \quad i = 1, 2 \tag{1}$$

where $\mathrm{D}/\mathrm{D}t$ is the material derivative $\partial/\partial t + \boldsymbol{u}_i \cdot \nabla$. The subscript i denotes fluids 1 and 2 respectively. The stress tensor is defined as

$$\Pi_i = -p_i \boldsymbol{I} + \mu_i \big(\nabla \boldsymbol{u}_i + (\nabla \boldsymbol{u}_i)^T\big) \tag{2}$$

where ρ and μ are density and viscosity respectively. The last term in Eq. (1) is the body force due to gravity and buoyancy effects. The fluid interface Γ is impermeable and assuming no mass transfer between the two fluids yields a continuous velocity condition at the interface:

$$\boldsymbol{u}_1 = \boldsymbol{u}_2 \quad \text{for} \quad x \in \Gamma\,. \tag{3}$$

The jump in normal stresses along the fluid interface is balanced with the surface tension. Neglecting the variations of the surface tension coefficient, σ, gives the following Laplace–Young boundary condition for momentum conservation at the interface:

$$\boldsymbol{\Pi}_1 - \boldsymbol{\Pi}_2 = \sigma\kappa\boldsymbol{n} \quad \text{for} \quad x \in \Gamma \tag{4}$$

where σ is surface tension coefficient and $\boldsymbol{n}$ is the unit normal vector along the interface pointing outwards from fluid 2 into fluid 1. The curvature κ of the interface is given as $-\nabla \cdot \boldsymbol{n}$.

Single-Fluid Formulation

The two-fluid formulation is in general demanding in computational operations and complex to implement. A more popular method is the single-fluid formulation of interfacial flows. In the single-fluid approach, one set of equations are solved in the whole domain making use of appropriate physical properties of each phase. The conservation of total momentum for the body of fluid in control volume Ω can be written as

$$\int_{\Omega} \frac{\mathrm{D}(\rho \boldsymbol{u})}{\mathrm{D}t}\,\mathrm{d}x = \int_{\Omega} \nabla \cdot \boldsymbol{\Pi}\,\mathrm{d}x + \int_{\Gamma} \sigma \kappa \boldsymbol{n}\,\mathrm{d}s + \int_{\Omega} \rho \boldsymbol{g}\,\mathrm{d}x\,. \tag{5}$$

It is assumed that the velocity field is continuous across the interface and the interface boundary conditions are implicitly contained within the equation of motion.

An important aspect of the surface tension is that it creates a jump in pressure across a curved interface. The pressure jump is discontinuous and located only at the interface. This singularity creates difficulties when deriving a continuum formulation of the momentum equation. The interfacial conditions should be embedded in the field equations as source terms. Once the equations are discretized in a finite-thickness interfacial zone, within which the flow properties change smoothly. It is therefore necessary to create a continuum surface force equal to the surface tension at the interface, or in a transitional region, and zero elsewhere.

Thus, the surface integral term in Eq. (5) could be rewritten into an appropriate volume integral:

$$\int_{\Omega} \sigma \kappa \delta(\chi) \nabla \chi\,\mathrm{d}x \tag{6}$$

where $\delta(\chi)$ is a one-dimensional Dirac delta function which is equal to 1 at the interface and 0 elsewhere. After replacing the surface integral with the obtained volume integral, the final form of unsteady Navier–Stokes equations for a system consisting of two incompressible phases is

$$\frac{\partial(\rho \boldsymbol{u})}{\partial t} + \nabla \cdot (\rho \boldsymbol{u}\boldsymbol{u}) = \nabla \cdot \boldsymbol{\Pi} + \sigma \kappa \delta(\chi) \nabla \chi + \rho \boldsymbol{g} \tag{7}$$

with the incompressibility constraint

$$\nabla \cdot \boldsymbol{u} = 0 \tag{8}$$

The single-fluid approach has been undertaken utilizing Eulerian methods such as the VOF, level set, and mixed Eulerian–Lagrangian methods [10, 11].

Interface Advection Equation for Single-Fluid Formulation

For most interface capturing schemes, which use the single-fluid formulation, an additional equation is solved to obtain the interface evolution and topology. This equation governs the advection of a variable that can be attributed to the interface. The equation of interface motion is as follows:

$$\frac{\partial \chi}{\partial t} + \boldsymbol{u} \cdot \nabla \chi = 0 \tag{9}$$

where χ is an indicator (or color) function which represents the location of interface. The scalar χ is defined differently in different interface capturing techniques. For example, χ is a volume fraction in the VOF volume tracking method, a distance function in the level set method or a Heaviside (step) function in the front tracking method.

The normal vector and curvature are computed from the indicator function using the following formulas:

$$\boldsymbol{n} = \frac{\nabla \chi}{|\nabla \chi|} \quad \kappa = -\nabla \cdot \boldsymbol{n}\,. \tag{10}$$

The physical properties, such as density and viscosity, used in the single-fluid approach are dependent on the value of χ in the cells throughout the computational domain. For example, if χ is a normalized color function such as volume fraction in the VOF method which changes between 0 and 1 throughout the domain, the following formulas determine the density and viscosity:

$$\rho = \rho_2 + (\rho_1 - \rho_2)\chi \tag{11}$$

$$\mu = \mu_2 + (\mu_1 - \mu_2)\chi \tag{12}$$

where subscripts 1 and 2 refer to the first and second fluids, respectively.

Interface Solution Methodologies

Moving and Deforming Mesh Methods

FE-Based Lagrangian Methods While FD- and FV-based techniques have been commonly used to simulate large surface deformations including the breakup and merging of liquids, the FE-based techniques have been more common in simulating less complicated surface deformations. FE performs on either fixed or deforming spatial meshes (see Fig. 2a). Deforming meshes are more popular and are divided into three sub-categories. The first is based on a three-stage iterative cycle by guessing the location of the free surface, solving the governing equations and updating the free surface. Iterations are repeated until the difference between the two successively updated free surface locations becomes less than some desired convergence tolerance. The second approach eliminates the iterations by introducing the position of the nodes on the free surface as a degree of freedom. The third technique is the height flux (HF) method. In this technique, neither iterations are involved for locating the free surface nor is one degree of freedom added to the set of the unknowns. The free surface is found by using the volume of fluid inside sub-volumes which are updated at any time step using the velocity field.

As a sample simulation using the Lagrangian FE method, Fig. 3 shows the deformation of a droplet after impaction on a flat substrate simulated by Fukai et al. [1]. The deformation of the grid as the droplet spreads can be observed. For low to moderate interface deformations, this method gives accurate results and sometimes is even more efficient than interface capturing simulations with high grid resolutions since in FE-based methods, the region near interface can be adapted locally and reduce the number of cells required.

Interface Fitting (Boundary-Fitted Coordinate) Method In the interface fitting, or boundary-fitted method (Fig. 1a), the interface is tracked by attaching it to a mesh surface which is forced to move with the interface. This can be considered a Lagrangian mesh method. The motion of the free surface is accounted for by a coordinate transformation which maps the moving, body-fitted coordinate system in physical space to a uniformly spaced coordinate system in computational space. If the free surface becomes highly distorted, a new mesh may have to be generated in order to prevent both grid singularities and highly skewed grid point distributions.

For the low-deformation bubble simulations where the boundary-fitted method is most widely used, it is assumed that Reynolds number ($\mathrm{Re} = \rho U D / \mu$) is low, the gas flow inside bubbles is neglected and a constant gas pressure assumed. The following boundary conditions are applied at the interface:

- velocity continuity,
- zero tangential stress, and
- balance of normal stress (Π) contributions by pressure, viscous and capillary forces.

The interface position is tracked by introducing a curvilinear interface-fitted non-orthogonal coordinate system. By means of a coordinate transformation, the physical domain is converted to a computational domain with known boundaries that are coordinate isolines. A boundary-fitted grid is generated around the deformed interface at each iteration by a pair of Poisson equations associated with spacing control functions.

The major difficulty arising in free surface flow computation is that the interface location is unknown together with the velocity and pressure fields. Therefore, one has to obtain the physical velocity boundary conditions and the interface position from the boundary conditions.

The following iterative procedure is used in boundary fitted method:

1. Choose an initial state (bubble shape, velocity and pressure fields) with desired values of Reynolds and Weber ($\mathrm{We} = \rho U^2 D / \sigma$) numbers.
2. Compute a curvilinear coordinate interface-fitted grid by carrying out some iterations on the mapping equations.
3. Calculate the velocity boundary conditions from the velocity continuity and tangential stress.
4. Solve Navier–Stokes equations using the fractional steps method.
5. Check the normal stress condition: if not satisfied, displace each interfacial point proportionally to the current normal stress excess Π^n; a new interface position X^{n+1} is then defined at each iteration (Fig. 4).
6. Continue the iterative process from step 2 until boundary conditions and incompressibility condition are satisfied.

The interface position correction at step 5 is given by

$$k_\Pi \Pi^n \boldsymbol{n}^n \tag{13}$$

where k_Π is a constant coefficient, and Π^n and $\boldsymbol{n}^n$ are respectively the current normal stress excess and interface normal vector at iteration n. The iterative process is stopped when

$$\Pi^n \leqslant \varepsilon_\Pi \tag{14}$$

with $\varepsilon_\Pi = 10^{-2}$. The value of k_Π depends on the Weber number and varies between $k_\Pi = 10^{-1}$ (for small Weber numbers) and $k_\Pi = 10^{-3}$ (for large Weber numbers). Conservation of the bubble volume is controlled at each iteration after the interface position correction step (step 5) in order to avoid accumulation of numerical errors and to ensure the convergence of the whole procedure.

This method is best suited and gives very accurate results for relatively simple geometries especially those encountered in two-dimensional and axisymmetric problems. However, application of the boundary-fitted method to complex fully three-dimensional problems with unsteady deforming phase boundaries is very rare [17].



Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 2 Numerical methods for the fluid flow with moving free surface. Moving grids: (**a**) Lagrangian FE method. Fixed grids: (**b**) MAC method and (**c**) VOF method [16]



Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 3 Impact of a droplet on a substrate at two different time instances using Lagrangian FE method [1]

Boundary Integral (BI) Method The low Reynolds number approximation of the Navier–Stokes equations (also known as Stokes equations) is an acceptable model for a number of interfacial flow problems. For instance, the typical example of drop coalescence also belongs to this case. A boundary integral method [3] arises from a reformulation of the Stokes equations in terms of boundary integral expressions and the subsequent numerical solution of the integral equations.

The main advantage of the boundary integral methods, compared with other methods (e. g. FD, FE), is that for a number of multiphase flow problems its implementation involves integration on the interfaces only. Thus, discretization is required only for the interfaces, which allows for higher accuracy and performance, especially in three-dimensional simulations. An important feature of the mathematical model used in the BI method is that the velocity at a given time instant depends only on the position of the interfaces at that time instant.



Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 4 Definition of the new interface location [2]

For a system of two incompressible Newtonian fluids separated by an immiscible interface, and neglecting inertial forces, the two-fluid system of Eq. (1) can be simplified to

$$\begin{aligned} &\nabla \cdot \boldsymbol{\Pi}_i = 0 \,, \\ &\nabla \cdot \boldsymbol{u}_i = 0 \quad x \in \Omega_i \,, \quad i = 1, 2 \end{aligned} \tag{15}$$

where $\boldsymbol{\Pi}_i = -p_i \boldsymbol{I} + \mu_i (\nabla \boldsymbol{u}_i + (\nabla \boldsymbol{u}_i)^T)$ is the stress tensor. The boundary conditions at the interface $S = \Omega_0 \bigcap \Omega_1$ are the stress balance boundary condition and continuity of the velocity across the interface,

$$(\Pi_1(\boldsymbol{x}) - \Pi_2(\boldsymbol{x})) \cdot \boldsymbol{n}(\boldsymbol{x}) = f(\boldsymbol{x}) \boldsymbol{n}(\boldsymbol{x}) \,, \quad \boldsymbol{u}_1(\boldsymbol{x}) = \boldsymbol{u}_2(\boldsymbol{x}) \tag{16}$$

where $\boldsymbol{n}(\boldsymbol{x})$ is the unit vector normal to S. The present formulation is limited to interfacial forces, such as capillary effects, that are normal to the interfaces:

$$f(\boldsymbol{x}) = 2\sigma\kappa(\boldsymbol{x}) \tag{17}$$

where $k(\boldsymbol{x}) = 0.5(1/R^1 + 1/R^2)$ is the mean curvature of the interface, and R^1 and R^2 are the main radii of the curvature.

The velocity at infinity is prescribed via a boundary condition,

$$\boldsymbol{u}_\infty(\boldsymbol{x}) = \boldsymbol{L}\cdot\boldsymbol{x}, \quad ||\boldsymbol{x}|| = \infty \tag{18}$$

where $\boldsymbol{L}$ specifies the type of linear flow.

The evolution of the interface $S(\boldsymbol{x}, t)$ is given by the kinematic condition

$$\frac{\mathrm{d}\boldsymbol{x}}{\mathrm{d}t} = \boldsymbol{u}(\boldsymbol{x}, t) + \boldsymbol{w}(\boldsymbol{x}, t), \quad \boldsymbol{x} \in S \tag{19}$$

where $\boldsymbol{w}$ can be an arbitrary velocity, tangential to S.

For a given position of the interfaces S the solution of the mathematical model (Eqs. (15)–(17)) for the velocity $\boldsymbol{u}(\boldsymbol{x}_0)$ at a given point $\boldsymbol{x}_0$ can be obtained by means of the boundary integral formulation. The equations are nondimensionalized and, for simplicity, the same notations for the dimensionless velocity, pressure, space and time variables are used as those for the corresponding dimensional variables from the previous equations.

$$\begin{aligned}\boldsymbol{u}(\boldsymbol{x}_0) = {} & \frac{2}{\lambda+1}\boldsymbol{u}_\infty(\boldsymbol{x}_0) \\ & - \frac{2}{\lambda+1}\frac{1}{8\pi}\int_S f(\boldsymbol{x})\boldsymbol{G}(\boldsymbol{x}_0, \boldsymbol{x})\cdot\boldsymbol{n}(\boldsymbol{x})\,\mathrm{d}s(\boldsymbol{x}) \\ & - \frac{\lambda-1}{\lambda+1}\frac{1}{4\pi}\int_S \boldsymbol{u}(\boldsymbol{x})\cdot\boldsymbol{T}(\boldsymbol{x}_0, \boldsymbol{x})\cdot\boldsymbol{n}(\boldsymbol{x})\,\mathrm{d}s(\boldsymbol{x})\end{aligned} \tag{20}$$

where the integration is over the total interfacial area $S = \bigcup_i S^i$. Here, λ is the non-dimensional viscosity. Tensors $\mathbf{G}$ and $\mathbf{T}$ are the Stokeslet and stresslet, respectively:

$$\mathbf{G}(\boldsymbol{x}_0, \boldsymbol{x}) = \frac{\boldsymbol{I}}{r} + \frac{\hat{\boldsymbol{x}}\hat{\boldsymbol{x}}}{r^3}, \quad \mathbf{T}(\boldsymbol{x}_0, \boldsymbol{x}) = \frac{-6\hat{\boldsymbol{x}}\hat{\boldsymbol{x}}\hat{\boldsymbol{x}}}{r^5} \tag{21}$$

where $\hat{\boldsymbol{x}} = \boldsymbol{x} - \boldsymbol{x}_0$, $r = |\hat{\boldsymbol{x}}|$.

The main advantage of a boundary integral method is that it involves integration only on the interfaces. The main problem, however, regarding the numerical implementation of Eq. (20) is due to the singularities of the kernels $\mathbf{G}$ and $\mathbf{T}$ at $\boldsymbol{x} = \boldsymbol{x}_0$, which is described in detail elsewhere [3]. Among the numerical methods for interfacial flow problems the boundary integral method seems to be one of the most appropriate for problems involving interfaces in close approach. Such situations are typical for most of the practically important multiphase flows including drop deformation and drop-to-drop interaction. Well-known examples are neck formation and its thinning during breakup as well as film formation and drainage during drop coalescence. A simulation of these processes requires a good resolution and accuracy in the neck and film regions. However, the main difficulty for the implementation of a boundary integral method is due to the singularity of the free-space Green's kernels and sensitivity of the method to numerical instabilities. Another disadvantage of this method is that the topological changes do not occur naturally, rather by algorithm intervention.

Interface Capturing

Marker and Cell (MAC) Method The first method capable of modeling gas–liquid flows, separated by a moving interface, was the MAC of Harlow and Welch [4]. In the MAC method, as shown in Fig. 2b, the massless markers are used to define the location and track the movement of free surface. This is in fact a combination of a Eulerian solution of the basic flow field, with Lagrangian tracking of marker particles. The computational cycle in the MAC method consists of the advancement of discrete field variables from an initial time t_0 to the subsequent time $t_0 + \Delta t$ by accomplishing the steps below. The computation starts with a predictor–corrector algorithm for the determination of velocity field at $t_0 + \Delta t$. In the predictor stage of the solution algorithm, the pressure is replaced by an arbitrary pseudo-pressure β (which in most cases is set equal to zero at full cells), and tentative velocities are then calculated. A pseudo-pressure boundary condition is applied in surface cells to satisfy the normal stress condition. Since pressure has been ignored in the full cells, the tentative velocity field does not satisfy the incompressible continuity equation. The deviation from incompressibility is used to calculate a pressure potential field ψ, which then is used to correct the velocity field. In the final steps, the velocity boundary conditions are calculated, the new location of free surface is determined by tracking the markers and the velocity boundary conditions associated with the new fluid cells are assigned (Fig. 5).

The MAC method, which allows arbitrary free surface flows to be simulated, is widely used and can be readily extended to three dimensions. Its drawback lies in the fact that it is computationally demanding to trace a large number of particles, especially in three-dimensional simulations. In addition, it may result in some regions void of par-



Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 5 Free surface and velocity distribution in MAC family of interface tracking schemes. The circles represent surface markers, while continuous and dotted lines show the old and new free surface topology. $u(i,j)$ is a new fluid cell velocity [18]



Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 6 Variable arrangement for staggered grid according to the MAC method [4]

ticles because the density of particles is finite. The impact of the MAC method is much beyond its interface capturing scheme. The staggered mesh layout (Fig. 6) and other features of MAC have become a standard model for many other Eulerian codes (even numerical techniques involving mono-phase flows).

Volume of Fluid (VOF) Technique In the VOF method [5, 6], free surface is represented on fixed grids using fractional fluid volume in a cell. Each rectangle in Fig. 2c denotes a unit cell. The fractional volume-of-fluid, C, is defined such that it is equal to unity at any point occupied by the heavier fluid and zero elsewhere. As the free surface moves, the fractional volume of fluid of each cell is updated. In a numerical sense, every cell is classified into three categories according to the value of C (see Fig. 2c). If a cell is completely filled with the first (heavier) fluid, the fractional volume of fluid of the cell is unity ($C = 1$). If a cell is filled with the second (lighter) fluid, its volume of fluid is zero ($C = 0$). A cell is considered to be on the free surface when the values of C lie between 0 and 1 ($0 < C < 1$). Discontinuity in C propagates according to the following transport equation [5, 6]:

$$\frac{\partial C}{\partial t} + \boldsymbol{u} \cdot \nabla C = 0 \,. \tag{22}$$

By solving Eq. (22), distribution of C is obtained and thus free surface location can be identified. In a physical sense, the equation implies mass conservation of one phase in the mixture. Numerically, this equation is characterized as a hyperbolic or pure convection equation.

The formulation of the VOF model requires that the convection and diffusion fluxes through the control volume faces be computed and balanced with source terms within the cell itself. The interface will be approximately reconstructed in each cell by a proper interpolating formulation, since interface information is lost when the interface is represented by a volume fraction field. The application of Eq. (22) to the interface cells is not trivial and requires certain knowledge of the interface shape. The problem of reconstructing an interface by using the volume fraction field data (updated or given at the start) has generated a multitude of approaches and methods. The geometric piecewise linear interface calculation (PLIC) scheme is commonly employed because of its accuracy and applicability for complex flows, compared to other methods such as the donor–acceptor, Euler explicit and implicit schemes. An interface is viewed as comprised of line segments. This is acceptable when the grid system is fine enough. Inside of each cell, this line segment determines uniquely what the volume fraction inside that cell is. However, the reverse correlation is not unique, since more than one location of the interface may determine the same volume fraction in the cell. One has to take into account a group of neighboring cells in order to reconstruct the interface accurately.

A VOF geometric reconstruction scheme is divided into two parts: a reconstruction step and a propagation step. The key part of the reconstruction step is the determination of the orientation of the segment. This is equivalent to the determination of the unit normal vector $\boldsymbol{n}$ to the segment. Then, the normal vector $\boldsymbol{n}_{i,j}$ and the volume fraction $C_{i,j}$ uniquely determine a straight line. Once the interface has been reconstructed, its motion by the underlying flow field must be modeled by a suitable algorithm.

In the PLIC method, the interface is approximated by a straight line of appropriate inclination in each cell. A typical reconstruction of the interface with a straight line in cell (i,j), which yields an unambiguous solution, is perpendicular to an interface normal vector $\boldsymbol{n}_{i,j}$ and delimits a fluid volume matching the given $C_{i,j}$ for the cell. A unit vector $\boldsymbol{n}$ is determined from the immediate neighboring cells based on a stencil $C_{i,j}$ of nine cells in two dimensions. The normal vector $\boldsymbol{n}_{i,j}$ is thus a function of $C_{i,j}$, $\boldsymbol{n}_{i,j} = \nabla C_{i,j}$. Initially, a cell-corner value of the normal vector $\boldsymbol{n}_{i,j}$ is computed. For a uniform grid, an example at $(i+1/2,\ j+1/2)$ in two dimensions is as follows:

$$n_{x,i+\frac{1}{2},j+\frac{1}{2}} = \frac{1}{2h}(C_{i+1,j} - C_{i,j} + C_{i+1,j+1} - C_{i,j+1}) \tag{23}$$

$$n_{y,i+\frac{1}{2},j+\frac{1}{2}} = \frac{1}{2h}(C_{i,j+1} - C_{i,j} + C_{i+1,j+1} - C_{i+1,j}) \tag{24}$$

where $h = \Delta x = \Delta y$ is the computational cell size. Similar relations are used in other interface capturing schemes such as level set or diffuse interface method to calculate the interface normal vector from the proper indicator function. The required cell-centered values are given by averaging

$$\begin{aligned} \boldsymbol{n}_{i,j} = \frac{1}{4}(&\boldsymbol{n}_{i+\frac{1}{2},j-\frac{1}{2}} + \boldsymbol{n}_{i-\frac{1}{2},j-\frac{1}{2}} \\ &+ \boldsymbol{n}_{i+\frac{1}{2},j+\frac{1}{2}} + \boldsymbol{n}_{i-\frac{1}{2},j+\frac{1}{2}})\,. \end{aligned} \tag{25}$$

The most general equation for a straight line on a Cartesian mesh with normal $\boldsymbol{n}_{i,j}$ is

$$n_x x + n_y y = \alpha\,. \tag{26}$$

The normal vector $\boldsymbol{n}_{i,j}$ is defined by the vector gradient of $C_{i,j}$, which can be derived from different finite difference approximations which directly influence the accuracy of algorithms. These include Green–Gauss, volume-average, least-squares, minimization principle and Young's gradients. It is noted that a wide, symmetric stencil for $\boldsymbol{n}_{i,j}$ is necessary for a reasonable estimation of the interface orientation.



Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 7 Definitions of wet-out fraction for the k-th face of cell (i,j), $C_{\Gamma k}$

Geometrical VOF Advection Algorithm In order to trace the free surface location on a fixed mesh using a volume flux-based scheme, fluid volume fluxes through every cell boundary should be calculated. To handle the time derivative in Eq. (22), explicit and implicit time integration can be adopted. Generally, implicit integration gives a solution with higher accuracy, but requires more complex and time-consuming algorithm. In the explicit integration, in contrast, values at the new time step are updated from those at the old time step using the known flow field. In most studies, explicit integration is adopted due to its simplicity in updating the free surface location. After the divergence theorem is applied and the time integration is performed, Eq. (22) is reduced to

$$C_{i,j}^{n+1} = C_{i,j}^{n} + \frac{\Delta t}{V_{i,j}}\left[-\sum_k (C_{\Gamma k}\boldsymbol{u}\cdot\boldsymbol{n})\,A_k\right] \tag{27}$$

where the subscripts (i,j) and k represent the cell and the face numbers, respectively; $C_{i,j}^{n+1}$ and $C_{i,j}^{n}$ denote the values of C in the (i,j) cell at the new and the old time steps; Δt is the size of time increment; $V_{i,j}$ is the volume of the cell and A_k is the area of its k-th face; and $\boldsymbol{u}$ and $\boldsymbol{n}$ are the velocity and the unit outward normal vectors at the k-th face, respectively. From Eq. (27), it can be stated that the change in fluid volume in a cell during a given time interval is equal to the net fluid volume flux through every cell boundary. Here, $C_{\Gamma k}$ represents the *actual fractional volume-of-fluid* at the k-th face of the cell during a given time increment. Also, it can be interpreted as the wet-out fraction at a cell boundary, which indicates to what extent the cell boundary is wetted by the fluid (see Fig 7). In two dimensions, it can be expressed as $C_{\Gamma k} = A_f^{\text{wet}}/A_{\text{f}}$.

In general, $C_{\Gamma k}$ in Eq. (27) is dependent upon the free surface orientation and the value of f in the cell as well as the size of time increment Δt. However, due to the explicit nature of the time integration illustrated here, dependency of $C_{\Gamma k}$ on Δt becomes out of question. As a result, $C_{\Gamma k}$ is a function of the free surface orientation (or normal vector $\boldsymbol{n}$) and $C_{i,j}$ so that

$$C_{\Gamma k} = C_{\Gamma k}(\boldsymbol{n}, C_{i,j}) \tag{28}$$

The relations between $C_{\Gamma k}$ and volume fraction and normal vector components for three-dimensional interfaces can be found in Jafari et al. [19]. In the VOF-PLIC method, the fluxes are calculated using geometric approaches.

VOF Advection Based on High-resolution Difference Schemes It becomes complicated to use a geometric line reconstruction scheme on unstructured grids and more difficulty is encountered in extending it to three-dimensional calculations. To circumvent this limitation in VOF methods, a class of high resolution difference schemes is utilized, instead of geometric calculations, to capture the interface motion. Using standard convection schemes, the advection operator will lead to significant smearing of the interface (an effect of upwind scheme) or unbounded values of volume fraction (a result of using central difference schemes). A variety of compressive advection schemes have been devised to minimize the diffusion and promote boundedness. The compressiveness is often obtained by using a controlled downwinding of the fluxes. Controlled downwinding schemes have compressive characteristics which depend upon the time step, and therefore require small time steps to achieve sharp interfaces even for steady-state free surface flows.

One of the most widely used difference-based VOF schemes is the high-resolution interface-capturing scheme (HRIC) [21]. It is a normalized variable diagram (NVD) scheme based on a nonlinear blending of the bounded downwind (BD) and upwind differencing (UD) schemes, with the aim of combining the compressive property of the BD scheme with the stability of the UD scheme.

The normalized cell value of volume fraction $\tilde{C}_c$ which is used to find the normalized face value $\tilde{C}_f$ for face f is defined as follows:

$$\tilde{C}_c = \frac{C_D - C_U}{C_A - C_U} \tag{29}$$

where U, D, and A represent upwind, donor and acceptor cells respectively. The normalized functional relationships of the BD and UD schemes are given by



Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 8 Interface and volume fraction distribution in neighboring cells [20]

$$\tilde{C}_f^{BD} = \begin{cases} 2\tilde{C}_c & 0 < \tilde{C}_c \leqslant 0.5 \\ 1 & 0.5 < \tilde{C}_c \leqslant 1 \\ \tilde{C}_c & \text{otherwise} \end{cases} \tag{30}$$

$$\tilde{C}_f^{UD} = \tilde{C}_c \tag{31}$$

The functional relationship of the HRIC scheme is also function of the angle θ between the normal to the interface and the normal to the cell face (Fig. 8). For an interface aligned with the cell face ($\theta = 0$) the bounded downwind scheme is used, while for an interface perpendicular to the cell face the upwind scheme is used. For an interface with θ between these two limits, $f(\theta)$ is chosen to be $\sqrt{\cos\theta}$ and the blending formula is given by

$$\tilde{C}_f = \tilde{C}_f^{BD}\sqrt{\cos\theta} + \tilde{C}_f^{UD}(1 - \sqrt{\cos\theta}) \tag{32}$$

where

$$\cos\theta = \frac{\nabla \boldsymbol{C} \cdot \boldsymbol{d}}{|\nabla \boldsymbol{C}|\,|\boldsymbol{d}|} \tag{33}$$

and $\boldsymbol{d}$ is a vector connecting cell centers adjacent to the face f. With this formulation, Eq. (32), the blending of the upwind and downwind schemes is dynamic and accounts for the spatial distribution of the C field.

The face volume fraction is now obtained from the normalized value computed above as follows:

$$C_f = \tilde{C}_f(C_A - C_U) + C_U\,. \tag{34}$$

The use of high-resolution schemes in interfacial flow calculations is promising, but existing schemes are still too diffusive for the capturing of sharp interfaces. Implementation in multiple dimensions is also restricted to the technique of operator splitting. A generalization for implementation on unstructured meshes is still required.

Surface Tension Calculation in VOF Method Modeling interfacial tension effects is important because it is a potentially large force which is concentrated on the interface. There are two different approaches to modeling surface tension forces. The first one is continuum surface force (CSF) defined as

$$F^{\mathrm{st}} = -\sigma\kappa \boldsymbol{n}\delta_{\mathrm{s}} = \sigma\nabla\cdot\left(\frac{\nabla C}{|\nabla C|}\right)\frac{\nabla C}{[C]} \tag{35}$$

where the normal vector and curvature are calculated from Eq. (10). The delta function is approximated as $\delta_{\mathrm{s}} = |\nabla C|/[C]$ and $[C] = C_1 - C_2$ is the difference between maximum and minimum values of C.

The second approach is the continuous surface stress (CSS) model where the surface force is expressed as the divergence of a surface tension tensor:

$$\begin{aligned} \mathbf{T} &= -\sigma(\boldsymbol{I} - \boldsymbol{n}\otimes\boldsymbol{n})\,|\nabla C|\,, \\ F^{\mathrm{st}} &= -\nabla\cdot\mathbf{T} = \sigma\nabla\cdot\left(|\nabla C|\boldsymbol{I} - \frac{\nabla C\otimes\nabla C}{|\nabla C|}\right) \end{aligned} \tag{36}$$

An advantage of the CSS model is that it does not explicitly contain the curvature term since curvatures calculated from the VOF method are less accurate than those calculated from other methods such level set. This is because curvature evaluation in effect requires the second derivative of the discontinuous volume fraction field. Therefore, care must be taken in order to avoid errors in curvature calculations.

Since the movement of free surface is accomplished by solving Eq. (22) in the VOF method, instead of deforming the mesh as in the Lagrangian method or tracing marker particles as in the MAC method, an overall solution algorithm becomes simple and efficient. Combined with advantages of fixed grids which can accommodate complex geometry, the VOF method is adaptable to any existing CFD codes regardless of the solution methods such as FD, FV or FE. For this reason, the VOF-based methods have been used extensively in the simulation of general free surface flow problems. There are several extended or modified versions of the VOF method [22]. If mass conservation is a design constraint, geometrically based algorithms tend to result rather than simpler algebraically based techniques. Geometrically based algorithms, on the other hand, tend to exhibit *numerical surface tension* when interface features are not resolved [23].

The basic idea behind the VOF method is to discretize the equations for conservation of volume in either conservative flux or equivalent form resulting in near-perfect volume conservation except for small over and under shoots. The main disadvantage of the VOF method, however, is that it suffers from the numerical errors typical of Eulerian schemes such as the level set method. The imposition of a volume preservation constraint does not eliminate these errors, but instead changes their symptoms replacing mass loss with inaccurate mass motion leading to small pieces of fluid non-physically being ejected as flotsam or jetsam, artificial surface tension forces that cause parasitic currents and an inability to calculate accurately geometric information such as normal vector and curvature. Due to this deficiency, most VOF methods are not well suited for surface tension-driven flows unless some improvements are made [19].

Level Set (LS) Method In the level set method, the interface between the two phases is represented by a continuous scalar function $\phi(\boldsymbol{x}, t)$, which is set to zero at the interface, is positive on one side and negative on the other. This way both phases are identified, and the location of the physical interface is associated with the surface $\phi = 0$. The function ϕ is called the level set function and is typically defined as the signed distance to the interface; i. e. $\phi = -d(\boldsymbol{x}, t)$ on one side of the interface and $\phi = +d(\boldsymbol{x}, t)$ on the other, where $d(\boldsymbol{x}, t)$ is the shortest distance from the point $\boldsymbol{x}$ to the interface.

When the interface is advected by the flow, the evolution of the level set function is given by

$$\frac{\partial\phi}{\partial t} + \boldsymbol{u}\cdot\nabla\phi = 0 \tag{37}$$

The level set Eq. (37) moves the interface along its normal vector field with the normal speed $v^n = \boldsymbol{u}\cdot\boldsymbol{n}$. Note that any tangential component will have no effect on the position of the front. Using the normal vector $\boldsymbol{n}$ given as $\nabla\phi/|\nabla\phi|$ we can rewrite Eq. (37) as

$$\frac{\partial\phi}{\partial t} + v^n\,|\nabla\phi| = 0 \tag{38}$$

This is called the *Hamilton–Jacobi* formulation and yields the motion of the front $\Gamma(t)$ with normal velocity v^n on the zero level set, $\phi = 0$.

In the level set formulation, the density and viscosity are typically interpolated across the interface as follows:

$$\rho(\boldsymbol{x}, t) = \rho_2 + (\rho_1 - \rho_2)H_\varepsilon(\phi(\boldsymbol{x}, t)) \tag{39}$$

$$\mu(\boldsymbol{x}, t) = \mu_2 + (\mu_1 - \mu_2)H_\varepsilon(\phi(\boldsymbol{x}, t)) \tag{40}$$

where subscripts 1 and 2 denote the values corresponding, respectively, to the two different phases. Here, $H_\varepsilon(\phi)$ is



Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 9 Effect of re-initialization for two merging bubbles. Left columns show the interface and right columns show contours of the level set function ϕ. (**a**) Initial configuration; (**b**) just before merging (time step $n = 100$) with no re-initialization; (**c**) just before merging ($n = 100$) with re-initialization back to a distance function [24]

a smoothed Heaviside function, which is defined as

$$H_\varepsilon(\phi) = \begin{cases} 0 & \text{if } \phi < -\varepsilon \\ \frac{(\phi+\varepsilon)}{(2\varepsilon)} + \frac{\sin(\frac{\pi\phi}{\varepsilon})}{(2\pi)} & \text{if } |\phi| \leqslant \varepsilon \\ 1 & \text{if } \phi > \varepsilon \end{cases} \tag{41}$$

where ε is a small parameter of the order of the size of a mesh cell close to the interface. By using the smoothed Heaviside function, one effectively assigns the interface a fixed finite thickness of 2ε, over which the phase properties are interpolated. Hence, the value of ε can be considered to be the half-thickness of the numerical interface.

The level set function will not necessarily remain a distance function as the front propagates. For large time computations this distortion will give a non-uniform thickness of the interface causing a randomness in the distance over which fluid properties change and surface tension forces are distributed.

There are basically two reasons for this distortion. Standard differencing schemes introduce numerical diffusion to the initial distance function. This problem can be reduced by using higher order numerical methods. The second reason is that the flow field is very rarely of that character so that the level set function ϕ would be kept as a distance function. For example, the maximum and minimum values of the level set function will remain the same throughout the computations. For two merging interfaces (e. g. two bubbles) this will cause a steep gradient and an impenetrable sheet between the two merging interfaces (see Fig. 9). It is therefore necessary to reinitiate the distance function after each time step.

Re-Initialization Procedure Maintaining ϕ as a distance function becomes important for providing a uniform thickness at the interface with a fixed width in time and to avoid steep gradients. It is also essential that the level set function is re-initialized to a distance function without changing its zero level set. An iterative procedure is used to maintain ϕ as a distance function. Their re-initialization procedure is based on solving the following partial differential equation to steady-state solution at each time step:

$$\frac{\partial d}{\partial \tau} = sign(\phi)(1 - |\nabla d|) \tag{42}$$

with initial condition

$$d(\boldsymbol{x}, 0) = \phi(\boldsymbol{x}, t)\,, \tag{43}$$

where τ is an artificial time. It has also been proposed to use a smooth sign function in order to eliminate numerical oscillations,

$$sign_\varepsilon(\phi) = \frac{\phi}{\sqrt{\phi^2 + \varepsilon^2}}\,. \tag{44}$$

The steady-state solution of Eq. (42) is a distance function and, since $sign(\phi = 0) = 0$, the zero level set of $d(\boldsymbol{x}, \tau)$ and $\phi(\boldsymbol{x}, t)$ are the same. When the steady-state solution of Eq. (42) is obtained at $\tau = \tau_\mathrm{s}$, we simply replace $\phi(\boldsymbol{x}, t)$ by $d(\boldsymbol{x}, \tau_\mathrm{s})$.

Surface Tension Solution in Level Set (LS) Methods As for the discontinuous Heaviside function there will be numerical difficulties with discretization of the singular Dirac delta function. This function is therefore smoothed over the interface thickness and commonly defined as

$$\delta_\varepsilon(\phi) = \frac{\partial H_\varepsilon(\phi)}{\partial \phi} \tag{45}$$

or

$$\delta_\varepsilon(\phi) = \begin{cases} \frac{1}{(2\varepsilon)}\left[1 + \cos\left(\frac{\pi\phi}{\varepsilon}\right)\right] & \text{if } |\phi| \leqslant \varepsilon \\ 0 & \text{otherwise.} \end{cases} \tag{46}$$

Introducing the regularized delta function δ_ε into Eq. (6) smears out the surface tension force across the interface. The level set formulation of Eq. (6) takes the form

$$F^{\mathrm{st}} = -\sigma\nabla\cdot\left(\frac{\nabla\phi}{|\nabla\phi|}\right)\delta_\varepsilon(\phi)\nabla\phi\,, \tag{47}$$

where we have expressed the curvature in terms of ϕ. This is similar to the widely used continuum surface force (CSF) model.

Diffuse Interface (Phase Field) Method The diffuse interface (DI) model, also known as partial miscibility or phase field method, is based on the idea that a fluid–fluid interface has a finite thickness over which various thermodynamic variables change continuously. The concept was first used by van der Waals in 1893 to explain why equilibrium interfaces have surface tension and, hence, the DI method is endowed with capillarity. The thickness of the interface is closely related to the finite range of molecular interactions. The finite interaction range is represented by a non-local effect in the free energy: the local free energy density not only depends on the local composition but also on the composition of the immediate environment. By using a mean-field approximation, the non-local effect in the free energy is represented by the dependence on the local composition gradients rather than on the non-local composition. This free energy determines both the interfacial thickness and the surface tension that now appears in the equations of motion as a distributed stress over the interfacial region. The position and the shape of the interface is a part of the solution that is continuous throughout the system but may have large variations in the interfacial region of the governing equations of DI. Originally designed to model the initial stages of spinodal decomposition, the DI approach has recently been used to model a wide range of hydrodynamic and interfacial phenomena.

The following Cahn–Hilliard equation governs the continuity of mass concentration:

$$\frac{\partial C}{\partial t} + \boldsymbol{u} \cdot \nabla C = \nabla \cdot (M(C) \nabla \xi) \tag{48}$$

$$\xi = F'(C) - \varepsilon^2 \Delta C \tag{49}$$

where $M(C) = C(1 - C)$ is the mobility and $F(C) = 1/4C^2(1 - C)^2$ denotes Helmholtz free energy, and ε is the interface thickness which is a measure of gradient energy. This equation can be solved using ordinary difference schemes and it is an advantage of the DI method.

Surface Tension Simulation in Diffuse Interface Method Similar to surface tension modeling in the VOF method, both CSF and CSS methods are applicable, with minor adjustments, to the diffuse interface method. The CSF method is as follows:

$$F^{\mathrm{st}} = -\alpha\sigma\varepsilon\nabla \cdot \left(\frac{\nabla C}{|\nabla C|}\right) |\nabla C| \ \nabla C \tag{50}$$

The CSS formulation of surface tension force is given as

$$F^{\mathrm{st}} = \alpha\sigma\varepsilon\nabla \cdot \left(|\nabla C|^2 \boldsymbol{I} - \nabla C \otimes \nabla C\right) \tag{51}$$

Here, α is constant and has the value of $6\sqrt{2}$.

The diffuse interface method is rapidly developing into a reliable technique for investigation of multiphase and interfacial flows. Its advantages are automatic handling of topological changes, the possibility of easy implementation of physical phenomena and its applicability for treating multiphase flows involving more than two phases, miscible and immiscible [25].

Interface Tracking Methods

Glimm's Front Tracking Method In Glimm's front tracking method [9], the discrete representation of the flow is based on a composite grid that consists of a spatial grid representing the flow field in the bulk fluid, together with a lower dimension grid that represents the fronts. Figure 1c shows a two-dimensional schematic of a time step snapshot of such a grid. The front is represented by a piecewise linear curve, the sections of which are called bonds. In contrast to the spatial grid, which is fixed in time (i. e. Eulerian), the fronts move according to the dynamics of the wave fronts that they represent. A single time step is divided into two processes: the propagation of the fronts and the updating of the solution on the spatial grid.

Front tracking has several features in common with the arbitrary Lagrangian Eulerian (ALE) family of methods in which the solution grid is adapted to the flow. ALE methods are based on a moving mesh formulation of the flow equations where the mesh motion is chosen to maintain desirable features of both the Lagrangian (fluid following) or Eulerian (fixed grid) formulations. Front tracking is a special case where adaptivity is used on a lower dimensional manifold corresponding to wave fronts.

Two key features are exploited by the tracking. When the orientation and position of a front is known, one can locally rotate into a coordinate system that is aligned with the wave front so that the normal and tangential directions to the front are grid lines in the local coordinate system. Such a grid substantially improves the quality of the solution near the front.

A tracked interface is a collection of geometric objects describing the location of a set of fronts at a given time. They consist of discrete representations of points, curves and surfaces. A curve is a connected oriented piecewise linear list of bonds, which are connectors between adjacent points. A surface is a connected oriented piecewise linear collection of triangles, which are in turn connectors between three adjacent points. Both bonds and triangles are linking objects in the sense that they contain pointers to their neighbors. Each bond points to both the previous and following bonds that share its endpoints. It is assumed that a valid interface is non-intersecting in the interior of the surfaces and curves. Thus curves may only intersect along nodes or surfaces along curves. Front intersections produced during propagation correspond to wave interactions and require special treatment to resolve the interaction and untangle the interface.

This technique has been extensively developed by Glimm and collaborators. Details can be found in Glimm et al. [9]. Front tracking is accurate in locating interfaces. However, it is difficult to implement and simulation of rupturing and merging interfaces is not automatically done and needs algorithm intervention.



Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 10 Illustration of the cell–interface intersection in the sharp interface method. Trapezoidal cells are formed near the interface [27]

Combined Interface Capturing–Interface Tracking Methods

Tryggvason's Hybrid Method Although this method is also called front tracking, it is a hybrid between interface capturing and interface tracking techniques. A stationary regular grid is used for the fluid flow, but the interface is tracked by a separate grid of lower dimension, similar to Glimm's method. This grid is usually called the front. However, unlike interface tracking method of Glimm [9] where each phase is treated separately, Tryggvason's method follows front capturing methods and treats all phases by a single set of governing equations throughout the whole flow field [10]. Interfacial source terms such as surface tension are computed on the front and transferred to the fixed grid. Advection of fluid properties such as density is done by following the motion of the front.

Although the front tracking method has been successfully applied to different interfacial flows, there are problems associated with these kinds of interface tracking methods. The main drawback is that the marker points will be non-uniformly distributed as the interface evolves. Also, relatively high computer storage is needed to maintain the interface continuous and smooth. The need to provide element connectivity for a moving, adaptive surface mesh significantly complicates three-dimensional interface tracking. To alleviate this problem, Shin and Juric [26] developed a method which automatically provides for element addition/deletion and topology change.

Sharp Interface Method The sharp interface (SI) method [27] employs a combined Eulerian–Lagrangian strategy. It uses the finite volume method and solves two sets of governing equations instead of using the single set of governing equations for the entire domain of all phases/materials. This enables the method to handle large property (such as density) ratios across the interface with relative ease. The interface is sharp with almost no numerical smearing. In SI method, interfacial constraints are imposed as the distinct boundary conditions, instead of being incorporated through source terms in the governing equations. The cubic B-spline curve fitting method is employed to represent the interface.

An illustration of the cell and interface intersection treated in the sharp interface method is depicted in Fig. 10. It is noted that the small fragments of cut-cells are absorbed into the neighboring cells in the same phase to form larger, trapezoid cells. The interface, represented by suitable geometric representations based on massless markers, intersects with the underlying, fixed Cartesian grid. A compact interpolation method near the interface is adopted to retain second-order accuracy and conservation property. The SI is accurate in capturing interface evolution. However, it is in general demanding in computational operations and complex to implement.

Immersed Boundary (IB) and Immersed Interface (II) Techniques The immersed boundary technique [28] is a combined Eulerian–Lagrangian method in the sense that the flow is solved using a Eulerian approach on a fixed Cartesian mesh, and the interface is represented by a discrete set of points and advected in a Lagrangian way. In this method, a single set of conservation equations valid for both phases is solved. The interface conditions are incorporated into the governing field equation as source terms using the continuum surface force (CSF) method [22]. As a result, the interface is considered to be of small nonzero thickness within which the values of the properties change smoothly. The immersed boundary method tracks the interface explicitly instead of reconstructing it as a posteriori measure. Furthermore, the fluid properties are not advected but prescribed based on the known interface position, therefore keeping the transitional zone on both parts of the interface constant and avoiding any numerical diffusion. This method is suitable for solving bubble and drop dynamics that often encounter large deformation, as has been proved in the existing literature.

In the immersed boundary method, the information between the moving interface and the field variables is exchanged through interpolation. Since the locations of the marker points in general do not coincide with the underlying grid points employed to solve the field equations, the velocity of the field equation, defined according to the Cartesian grid system, is interpolated to obtain the marker velocity. Furthermore, the interfacial force acting on the marker points is spread to the nearby grid points. The concept is illustrated in Fig. 11b. The interpolations are performed via a discrete Dirac delta function taken in this study as Eq. (46) where the interface half-thickness of $\varepsilon = 2h$ with h as grid size is used.

Interface Tracking in Immersed Boundary Method The immersed boundary or interface denoted by $C(t)$ (a curve in two dimensions or a surface in three dimensions), see Fig. 11a, is represented by K markers of coordinates $\boldsymbol{x}_k(s)$ with $k = 1, 2, \ldots, K$. The markers are uniformly distributed along $C(t)$ at some fraction of the grid spacing, $0.5h < ds < 1.5h$. The interface is parameterized as a function of the arclength s by fitting quadratic polynomials $\boldsymbol{x}_k(s) = \boldsymbol{a}_k s^2 + \boldsymbol{b}_k s + \boldsymbol{c}_k$ through three consecutive marker points of coordinates $\boldsymbol{x}_{k-1}, \boldsymbol{x}_k, \boldsymbol{x}_{k+1}$.

The II method [29] is similar to the IB technique with some differences. The IB method uses a set of discrete delta functions to spread the entire singular force exerted by the immersed boundary to the nearby fluid grid points. However, the II method instead incorporates part of this force into jump conditions for the pressure, avoiding discrete dipole terms that adversely affect the accuracy near the immersed boundary.

Hybrid Techniques

There are a number of hybrid techniques which integrate different methodologies. These include (a) coupled level set–volume of fluid (CLSVOF) which combines mass conserving properties with accurate normal and curvature calculation of level set, (b) particle level set which uses particles to enhance mass conservation, (c) mixed markers and volume of fluid with which one obtains a smooth motion of the interface, typical of the marker approach, with a good volume conservation, as in standard VOF methods and (d) hybrid immersed interface–level set which, instead of tracking the interface explicitly, captures the interface similar to level set method (purely Eulerian technique). There are a number of other hybrid techniques which have been less widely used.

Other Methods

There are other methods which are used in some studies of multiphase and interfacial flows. These include particle-based methods and also techniques that do not rely on Navier–Stokes equations for flow solution.

Particle-based methods are roughly divided into two main categories: those that use particles in conjunction with a grid, namely particle-in-cell (PIC) methods; and those that are massless, such as smoothed particle hydrodynamics (SPH). The most striking feature of particle-based methods is their ease of implementation. They are essentially as easy to implement on three-dimensional unstructured meshes as on two-dimensional structured meshes. However, they are very demanding in terms of memory and processing power that has caused their limited use in interfacial flows so far.

There are methods which are not based on Navier–Stokes equations. These include molecular dynamics (MD) and lattice Boltzmann (LB) methods applied to two-phase flows. A MD study of any physical phenomenon attempts to simulate the real behavior of nature by identifying each molecule and following its motion in time through the basic laws of classical mechanics. The system behavior and temporal evolution of its thermodynamic and transport properties are, therefore, nothing more than the cumulative result of individual molecular motion. The simulation of macroscopic multiphase flow phenomena such as droplet evaporation using MD is not yet possible due to the prohibitively large computational requirements both in terms of CPU time and memory. However, a system involving a submicrometer droplet is small enough to successfully apply MD. Consolini et al. [30] studied evaporation of submicrometer droplets in a gaseous surrounding using MD.

The LB method [31] is a relatively new computational method for fluid dynamics. It is based on the foundations of kinetic theory and involves the solution of a kinetic equation, a simplified form of the Boltzmann equation.

This equation describes the evolution of the distribution of the population of particles whose collective behavior reproduces fluid behavior. The distribution of the popu-


h
h
C
ds
Fluid 2
marker points
ñ
Fluid
Ω
a
Circle of radius 2h around marker point X
h
X
Marker points on interface
b

Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking, Figure 11 Immersed boundary method: (**a**) computational domain composed of two immiscible fluids; (**b**) grid points considered for the interface velocity around the marker *X* [12]

lation of particles is modified by the movement and collisions of the particles simulated on a lattice. This lattice restricts the movement and interaction of particles to selected discrete directions such that in the continuum, i. e. longer length and time scales, the collective behavior of the particle populations corresponds to the dynamics of fluid flow described by the Navier–Stokes equations. In contrast to the conventional computational methods for fluid dynamics, which solve macroscopic equations, the LB method effectively simulates macroscopic fluid flow by solving the kinetic equations at the mesoscopic level. This modeling of physics at a smaller scale relative to the macroscopic scale enables it to naturally incorporate physical properties needed to compute complex flows. In the case of multiphase flows, phase segregation and interfacial dynamics can be simulated by incorporating appropriate intermolecular attraction forces or by employing concepts based on the free-energy approach. LB-based methods do not track interfaces, but can maintain sharp interfaces without any artificial treatments. Also, the LB method is accurate for the mass conservation of each component of the fluid. Recently, Inamuro et al. developed a LB method which is applicable to real interfacial flows with density ratios as high as 1000 [32].

Key Research Findings

Despite advances in moving and deforming mesh methods, it remains the case that these methods are useful primarily when the interface topology is straightforward. Effects such as splashing, breaking and colliding remain difficult challenges.

Eulerian methods perform well for a variety of moving boundary problems. However, in these problems, particularly when surface forces are to be included in the flow calculations, the interface is diffused and occupies a few grid cells in practical calculations. This is undesirable in many problems both from an accuracy as well as physical realizability/modeling standpoint.

In the Lagrangian methods, the grid adapts to the interface and hence grid rearrangement and motion terms have to be incorporated. When the interface begins to distort, the grid needs to be regenerated each time. The resulting grid on which the field variables are computed may be skewed and unevenly distributed, thus influencing the accuracy of the field solver. The Eulerian methods have an advantage in this regard since the computations are performed on a fixed grid, hence obviating the need for grid rearrangement. In these methods, mergers and fragmentations are taken care of automatically, merely by updating the values of the phase fraction. However, when the interface is arbitrarily shaped, improved resolution in desired regions is difficult to obtain due to smearing of information, unless complicated local refinements are adopted [33].

As also mentioned by Prosperetti and Tryggvason [17], no method can be regarded as the best technique for handling interfacial flows. This is because each method is tailored for a certain range of flows and it depends on the level of detail that is expected from the numerical simulations.

Future Directions for Research

It is predicted that in the short term, the well-known interface simulation techniques such as VOF and level set will continue to dominate interfacial flow investigations. The algorithmic improvements of these methods are still being made. However, newer techniques which combine Eulerian and Lagrangian features, such as sharp interface and particle level set methods, seem to be the more promising ones. They are conceptually based on a more rigorous flow solution paradigm. Although the new combined methods have not been extensively tested for real flow problems, they show promise in handling interface motions accurately. They still need more developments regarding efficiency and feasibility to solve three-dimensional complex interface motion, breakup and merging.

Turning attention to multiphase micro- and nanoflows, the interface simulation techniques are used to simulate different phenomena encountered in micro- and nanofluidic devices. These include liquid dispensing, handling, breakup into droplets and merging, compound droplet and bubble encapsulation and, finally, formation of slug bubbly flows. In some cases where thin ligaments are formed, such as film formation on the surface or necking of microjets and microdroplets upon breakup, the adaptive grid methods become important to implement into the interface simulation technique. In cases where heat transfer or phase change is involved, the proper form of energy equation should be added to the system of flow equations and coupled accordingly.

Since in most microfluidic applications wall effects are important, development of accurate contact angle handling techniques is vital. Care should be given on implementation and coupling of flow, heat transfer and electric effects. For example in electro-wetting processes, the voltage and temperature dependence of contact angle should be taken into account in the numerical model. Since micro- and nanoscale devices may have complex shapes, development of proper numerical methods, which can handle such geometries, seems inevitable. In these devices, and also in devices with moving components such as micro-dispensing devices, the free surface may interact with the structure. In such cases, a method that can treat fluid–structure interaction with free surface flows is desirable. For simulation of three-phase interfacial microflows, such as formation of double emulsion and compound bubbles, appropriate interface solvers which account for the third phase are necessary to be developed.

Cross References

- ► Finite Volume and Finite Difference Methods for Modeling and Simulation
- ► Boundary Element Method and its Application to the Modelling of MEMS Devices
- ► Immersed Boundary Method
- ► Lattice Boltzmann Method (LBM)
- ► Meshless Methods
- ► Molecular Dynamics Simulation Method
- ► Non-Continuous Approaches
- ► Pressure-Driven Two Phase Flows
- ► Surface Tension Driven Flow
- ► Wetting and Spreading
- ► Electrokinetic Two Phase Flows

References

1. Fukai J, Zhao Z, Poulikakos D, Megaridis CM, Miyatake O (1993) Modeling of the deformation of a liquid droplet impinging on a flat surface. Phys Fluid A 5(11):2588–2599
2. Raymond F, Rosant JM (2000) A numerical and experimental study of the terminal velocity and shape of bubbles in viscous liquids. Chem Eng Sci 55:943–955
3. Pozrikidis C (1992) Boundary-Integral and Singularity Methods for Linearized Viscous Flow. Cambridge Univ Press, Cambridge
4. Harlow FH, Welsh JE (1965) Numerical calculation of time dependent viscous incompressible flow with a free surface. Phys Fluid 8:2182–2189
5. Hirt CW, Nicholls BD (1981) Volume of fluid (VOF) method for the dynamics of free boundaries. J Comput Phys 39:201–225
6. Ashgriz N, Poo JY (1991) FLAIR: flux line-segment advection and interface reconstruction. J Comput Phys 93(2):449–468
7. Osher S, Fedkiw RP (2001) Level set methods. J Comput Phys 169:463–502
8. Anderson DM, McFadden GB, Wheeler AA (1998) Diffuse-interface methods in fluid mechanics. Ann Rev Fluid Mech 30:139–165
9. Glimm J, Grove JW, Li XL, Shyue KM, Zhang Q, Zeng Y (1998) Three-dimensional front tracking. SIAM J Sci Comput 19:703–727
10. Tryggvason G, Bunner B, Esmaeeli A, Juric D, Al-Rawahi N, Tauber W, Han J, Nas S, Jan YJ (2001) A front tracking method for the computations of multiphase flow. J Comput Phys 169:708–759
11. Udaykumar HS, Mittal R, Shyy W (1999) Computation of solid-liquid phase fronts in the sharp interface limit on fixed grids. J Comput Phys 153:535–574
12. Francois M, Shyy W (2003) Computations of drop dynamics with the immersed boundary method, part 1: numerical algorithm and buoyancy-induced effect. Numer Heat Transf B 44:101–118
13. Lee L, Leveque RJ (2003) An immersed interface method for incompressible Navier-Stokes equations. SIAM J Sci Comput 25:832–856
14. Veldman AEP (1979) Liquid sloshing under low-g conditions: mathematical model and basic numerical method. NLR Report TR 79057 U, National Aerospace Laboratory, The Netherlands
15. Zhao Y, Tan HH, Zhang B (2002) A high-resolution characteristics-based implicit dual time-stepping VOF method for free surface flow simulation on unstructured grids. J Comput Phys 183:233–273
16. Kim MS, Lee W (2003) A new VOF-based numerical scheme for the simulation of fluid flow with free surface. Part I: new free surface-tracking algorithm and its verification. Int J Num Methods Fluid 42:765–790
17. Prosperetti A, Tryggvason G (2003) Appendix 3: report of study group on computational physics. Int J Multiph Flow 29:1089–1099
18. Chen S, Johnson DB, Raad PE (1995) Velocity boundary conditions for the simulation of free surface fluid flow. J Comput Phys 116:262–276
19. Jafari A, Shirani E, Ashgriz N (2007) An improved three-dimensional model for interface pressure calculation in free-surface flows. Int J Comput Fluid Dyn 21(2):87–97

20. Darwish M, Moukalled F (2006) Convective schemes for capturing interfaces of free-surface flows on unstructured grid. Numer Heat Transf B 49:19–42
21. Muzaferija S, Peric M, Sames P, Schellin P (1998) A two-fluid Navier-Stokes solver to simulate water entry. Proceedings of Twenty-Second Symposium on Naval Hydrodynamics, Washington, DC
22. Scardovelli R, Zaleski S (1999) Direct numerical simulation of free-surface and interfacial flow. Ann Rev Fluid Mech 31:567–603
23. Kothe DB (1997) Perspective on Eulerian finite volume methods for incompressible interfacial flows. LANL Report LA-UR-97-3559, Los Alamos National Lab., Albuquerque, NM
24. Berthelsen PA (2002) A short introduction to the level set method and incompressible Two-Phase Flow: A Computational Approach, NTNU Report, Norway
25. Kim J (2005) A continuous surface tension force formulation for diffuse-interface models, J Comput Phys 204:784–804
26. Shin S, Juric D (2002) Modeling three-dimensional multiphase flow using a level contour reconstruction method for front tracking without connectivity. J Comput Phys 180:427–470
27. Ye T, Shyy W, Tai CF, Chung JN (2004) Assessment of sharp- and continous-interface methods for drop in static equilibrium. Comp Fluid 33:917–926
28. Peskin CS (1977) Numerical analysis of blood flow in the heart. J Comput Phys 25:220–252
29. Li Z (1997) Immersed interface methods for moving interface problems. Numer Alg 14:269–293
30. Consolini L, Aggarwal SK, Murad S (2003) A molecular dynamics simulation of droplet evaporation. Int J Heat Mass Transf 46:3179–3188
31. Succi S (2001) The Lattice Boltzmann Equation for Fluid Dynamics and Beyond. Clarendon, Oxford, UK
32. Inamuro T, Ogata T, Tajima S, Konishi N (2004) A lattice Boltzmann method for incompressible two-phase flows with large density differences. J Comput Phys 198:628–644
33. Shyy W, Francois M, Udaykumar HS (2001) Cartesian and Curvilinear Grid Methods for Multi-domain, Moving Boundary Problems. In: Debit M et al (eds) 13th Int. Conf. on Domain Decomposition Meth. CIMNE, Barcelona

Ohmic Heating

- ► Joule Heating and Chip Materials
- ► Joule Heating in Electrokinetic Flow: Theoretical Models

Ohnesorge Number

Definition

To account for the liquid viscosity in droplet formation, the appropriate nondimensional number is the *Ohnesorge number* which represents the ratio of internal viscosity dissipation to the surface tension energy. The *Ohnesorge number* may be written in terms of the square root of the ►Weber number divided by the Reynolds number. The *Ohnesorge number* is sometimes also referred to as stability number, viscosity number, Laplace number, or Z number. It is independent on the velocity and therefore only adequate to describe droplet ejection in conjunction with the *Weber number*.

The lower the *Ohnesorge number* the weaker are the friction losses due to viscous forces. This means that most of the inserted energy converts into surface tension energy, i. e. a droplet can be formed. The higher the *Ohnesorge number* the more dominant is the internal viscous dissipation. This means that most of the inserted energy converts into internal viscous dissipation, i. e. that a droplet formation is critical or even impossible.

Cross References

- ► DNA Micro-arrays
- ► Droplet and Bubble Formation in Microchannels
- ► Electrokinetic Dispensing
- ► Piezoelectric Microdispenser

On-Chip Cell Culture

- ► Cell Culture (2D and 3D) on Chip

On-Chip Cell Lysis

ARPITA BHATTACHARYYA[1],
CATHERINE M. KLAPPERICH[2]
[1] Biomedical Engineering Department, Boston University, Boston, MA, USA
[2] Biomedical and Manufacturing Engineering Departments, Boston University, Boston, MA, USA
abhatta@bu.edu, catherin@bu.edu

Synonyms

Cell disruption; Permeabilization of cells

Definition

Cell lysis is the process of releasing intercellular biological molecules into the extracellular milieu by disrupting the cellular membrane. On-chip cell lysis is the process of lysing a cellular sample on a biochip.

Overview

On-chip cell lysis is a crucial component of integrated micro total analysis systems (μTAS). In order to perform biochemical analysis of intercellular molecules (i. e. proteins, lipids and nucleic acids), the cells at first have to be disrupted releasing the biomolecules from inside the cell. The molecules of interest can then be separated or purified from the cell lysate using affinity purification, charge- and size-based separation, filtration, precipitation etc. The process of on-chip cell lysis followed by extraction of the desired biomolecules is collectively referred to as on-chip sample preparation.

Several approaches have proven useful in releasing biomolecules from inside a cell. The most commonly used techniques are

- chemical lysis or permeabilization of the cells,
- physical disruption of the cell wall and cell membrane.

The most commonly used chemical lysis methods include the use of detergents (such as Triton-X, sodium dodecyl sulphate (SDS) etc.), and chaotropic agents (such as guanidinium thiocyanate (GuSCN), guanidine hydrochloride (GuHCL), ethanol, etc.).

Detergent-based lysis is the easiest and mildest form of cell lysis. Detergents disrupt the lipid bilayer surrounding cells by solubilizing proteins and disrupting lipid-protein interactions. Salts, chelating agents (e. g. EDTA) and reducing agents (e. g. dithiothreitol (DTT)) can be added for more efficient lysis. Detergents are comprised of a polar hydrophilic head and a non-polar hydrophobic tail. The nature of the head group is used to categorize the detergent as either ionic (cationic or anionic), non-ionic or zwitterionic. Non-ionic detergents (such as the Triton-X series) and zwitterionic detergents (such as CHAPS) are less denaturing than ionic detergents and retain native protein functions. Ionic detergents (such as sodium dodecyl sulphate (SDS)) are strong solubilizing agents and tend to denature proteins.

Chaotropes are strong protein denaturants and induce cell permeabilization by weakening the hydrophobic interactions of the membrane. In case of bacterial cells, chaotropic agents also inhibit the assembly of cross-linked peptidoglycans in the cell wall. Another common method of disrupting bacterial cell walls is enzymatic digestion using lysozyme, which hydrolyzes the polysaccharide component of the cell wall.

For microchip-based chemical treatments, optimal lysis depends on mixing of the lysis agent with the cell sample. Due to laminar flow in microfluidic channels, mixing occurs solely due to diffusion, which limits the exposure of individual cells to the lysis agent. To enhance the cell lysis efficiency, microfluidic mixing mechanisms can be introduced on the chip. Toner et al. have successfully demonstrated a continuous flow microfluidic system where lysis is achieved by flanking the cell suspension on both sides by the chemical reagent (Sethu et al. [1]). Bhattacharyya and Klapperich demonstrated continuous lysis by mixing chaotropic buffer (GuSCN) and cell suspension in serpentine mixing channel with sharp turns that enhances diffusive mixing (Bhattacharyya and Klapperich, [2]). Lee et al. presented a novel method of chemical cell lysis on-chip using hydroxide ions that porate the cell membrane and cause cell lysis (Di Carlo et al. [3]). A combination of one or more lysis methods may produce optimal lysis in some cases. Bau et al. demonstrated a microfluidic cassette where lysis of gram-positive bacteria was achieved by incubation of the bacteria sample with a solution containing detergents and lysozme, followed by incubation in chaotropic buffer (GuHCl) and proteinase K (Wang et al. [4]).

In addition to these various chemical treatment methods, a number of physical methods of cell disruption can be used in a chip-based system. These physical methods include osmotic shock, which occurs when cells are suspended in a hypotonic solution; shearing and fracturing of cells walls and membranes using microfabricated needles or spherical particles (beads); application of an electric field that causes electroporation; ultrasonication of the cell sample; and thermal lysis.

Lee et al. implemented a mechanical lysis device in which cells were lysed using a microfluidic filter with nanostructured barbs which they refer to as *nano-knives* (Di Carlo et al. [3]). Madou et al. demonstrated disruption of mammalian, bacterial and yeast cells on a microfluidic compact disc platform using spherical beads in a lysis chamber (Kim et al. [6]). Klapperich et al. demonstrated lysis of bacteria using carbon nanotubes embedded in a porous polymer monolith within a microfluidic channel (Klapperich et al. [7]). Jensen et al. demonstrated the electrolysis of human carcinoma cells in a micro-electroporation device to release the subcellular materials. They also demonstrated using simple circuit models that electrical lysis is selective towards plasma membrane and leaves organelle membranes undamaged (Lu et al. [8]). Lysis of white blood cells and murine clonal cells by electroporation in a continuous flow microfluidic device has also been demonstrated (Ramadan et al. [9]). Ultrasonication is frequently used for cell lysis. Ultrasonication is particular advantageous for lysing bacterial or fungal spores. Northrop, et al. performed ultrasonic lysis of bacterial spores trapped in a microfilter. However, in this application the ultrasonic horn was not incorporated in the microfluidic device due to its large size (Taylor et al. [10]). Northrop et al. went on to successfully implement ultrasonication lysis of epithelial and sperm cells on a microfluidic cartridge with an integrated sonication module (Devitt et al. [11]). Grodzinski et al. demonstrated thermal lysis of trapped E. coli cells using embedded heaters (Liu et al. [12]). A single step thermal cell lysis and PCR amplification of E. coli in a microreactor has also been presented (Ke et al. [13]).

The choice of cell lysis method depends to a large extent on sample type. Mammalian cells, bacteria and yeast all have different requirements for lysis depending on the presence or absence of a cell wall. In some cases, a combination of chemical and mechanical disruption may yield best results. Another important factor in the choice of lysis method is the sample size of cells to be disrupted. If only a very small volume of sample is available, care must be taken to reduce loss and avoid cross-contamination. Consideration should also be given to the compatibility of the chosen method with downstream applications.

Cross References

► Biosample Preparation Lab-on-a-Chip Devices

References

1. Sethu P, Anahtar M, Moldawer LL, Tompkins RG, Toner M (2004) Continuous flow microfluidic device for rapid erythrocyte lysis. Anal Chem 76:6247–6253
2. Bhattacharyya A, Klapperich CM (2005) Polymeric microfluidic device for on-chip cell lysis and extraction of nucleic acids from biological samples. Proc 9th Int Conf Miniaturized Syst Chem Life Sci Boston pp 1167–1169
3. Di Carlo D, Ionescu-Zanetti C, Zhang Y, Hung P, Lee LP (2005) On-chip cell lysis by local hydroxide generation. Lab chip 5:171–178
4. Wang J, Mauk MG, Chen Z, Bau HH (2005) A disposable microfluidic device for cell lysis and DNA isolation. Proc 9th Int Conf Miniaturized Syst Chem Life Sci Boston pp 289–291
5. Di Carlo D, Jeong HK, Lee LP (2003) Reagentless mechanical cell lysis by nanoscale barbs in microchannels for sample preparation. Lab Chip 4:516–522
6. Kim J, Hee Jang S, Jia G, Zoval JV, Da Silva NA, Madou MJ (2004) Cell lysis on a microfluidic CD (compact disc). Lab Chip 4:516–522
7. Klapperich CM, Kaufman JD, Kulinski MD, Altman DH (2007) Method for bacterial lysis. Pending. USSN 60/921,404
8. Lu H, Schmidt MA, Jensen MF (2005) A microfluidic electroporation device for cell lysis. Lab Chip 5:23–29
9. Ramadan Q, Samper V, Poenar D, Liang Z, Yu C, Lim TM (2005) Simultaneous cell lysis and bead trapping in a continuous flow microfluidic device. Sens Actuators B 113:944–955
10. Taylor MT, Belgrader P, Furman BJ, Pourahmadi F, Kovacs GT, Northrop MA (2001) Lysing bacterial spores by sonication through a flexible interface in a microfluidic system. Anal Chem 73:492–496
11. Devitt AJ, Aflatooni N, Vinas M, Loh N, Pourahmadi F, Yuan R, Northrop MA (2005) Differential extraction of male and female DNA in an automated microfluidic device. Proc 9th Int Conf Miniaturized Syst Chem Life Sci Boston pp 7–9
12. Liu RH, Yang J, Lenigk R, Bonanno J, Grodzinski P (2004) Self-contained, fully integrated biochip for sample preparation, polymerase chain reaction amplification and DNA microarray detection. Anal Chem 76:1824–1831
13. Ke C, Kelleher AM, Berney H, Sheehan M, Mathewson A (2007) Single step cell lysis/PCR detection of Escherichia coli in an independently controllable silicon microreactor. Sens Actuators B 120:538–544

On-Chip Detection

► On-Chip Micro-Optical Detection

On-Chip Detection Using Optical Fibers

LONNIE J. LUCAS, JEONG-YEOL YOON
Department of Agricultural & Biosystems Engineering,
The University of Arizona, Tucson, AZ, USA
jyyoon@email.arizona.edu

Synonyms

Fiber optics; Lab-on-a-Chip; Micro total analysis system (μTAS)

Definition

Using optical fibers to perform detection *on-chip* is an excellent example of two completely different technologies merging together to produce a synergistic result. In this entry, *on-chip* refers to a Lab-on-a-Chip (LOC) or micro total analysis system (μTAS). The optical fiber or fibre is a thin, transparent strand, usually made of glass or plastic, for transmitting light. Optical fibers integrated with an LOC, may be used to detect particles, chemicals, biomaterials, or other analytes, typically in an aqueous medium. The fibers are used to deliver source light to the chip and to collect emitted light from the sample located in the detection zone of the chip.

Overview

The phenomenon of total internal reflection confines light in one material surrounded by another material of lower refractive index. In the 1840's, physicists showed that light could be guided along jets of water for fountain displays. Later, inventors realized that bent quartz rods could carry light, and patented them as dental illuminators and lighted tongue depressors. During the 1920's, Baird and Hansell patented arrays of glass rods for transmitting television images. These early fibers were *bare*, with total internal reflection at a glass–air interface. Later, fibers were coated with *cladding* of lower refractive index to protect the surface and reduce light leakage [1].

By 1960, fibers had reached signal attenuation of about one decibel per meter, much too high for communication distances. In 1970, Corning Inc. produced fibers with attenuation below 20 dB/km and Bell Laboratories produced the first semiconductor diode laser. In the 1980's, carriers built telephone systems of single-mode fiber with 1300 nm sources. Those technologies spread to other communication platforms and remain the standard for most fiber optic systems today [2].

By the mid 1990's, the need for portable chemical and/or biological detection systems has emerged, as later rein-



On-Chip Detection Using Optical Fibers, Figure 1 Embedded fiber device with source and detection fibers adjacent to microchannel (top). Etched fiber placed into an insertion guide (bottom left). Embedded fibers located within 5μm of the fluid channel (bottom right)

forced by research supports for portable biochemical warfare agent detection systems (e. g. U.S. DARPA, Defense Advanced Research Projects Agency) [3].

Initially, fiber ends were conjugated with biomolecule sensing layers and dipped into test tubes while reactions occurred and were monitored with photomultiplier tubes (PMTs). These types of devices are called fiber optic biosensors (FOB) and are not performed *on-chip*. Many experiments and devices were developed throughout the 1990's using FOB techniques [4].

In the early 2000's, researchers began to incorporate fiber optics with the LOC for doing *on-chip* detection. The number of publications involving on-chip detection using optical fibers has been growing exponentially each year [5].

This entry reviews the basic fabrication methods for various LOCs using optical fibers. A description of fiber optics technology used with LOC applications is discussed. Light sources, detectors, filters and lenses are also discussed.

Basic Methodology

Similar to any bench-scale optical detections, there are multiple measurement modes commonly used with optical fibers, including fluorescence (excite at a certain wavelength and detect the emission at a longer wavelength); colorimetry (color detection); Raman (inelastic scattering detection of a laser); luminescence (light generation at low temperature). Also, changes in intensity, spectral shifts, time-domain parameters (fluorescence decay time), as well as polarization (with appropriate polarization-preserving fiber bundles and configuration) can all be used with optical fiber detections.

The approaches for integrating fiber optics with Lab-on-a-Chip devices can be grouped according to fiber location and are classified as: embedded fibers, proximity fibers, or wetted fibers. Table 1 provides a summary of the characteristics of embedded fiber sensors. Tables 2



On-Chip Detection Using Optical Fibers, Figure 2 Proximity fiber device with source and detection fibers above and below the detection zone on the chip (top). Example of a commercial fiber with jacketing, color coding and connectors (bottom)

and 3 lists the key parameters for proximity and wetted fiber sensors. Each of these three unique *on-chip* fiber optic sensor configurations will be described in the following.

Embedded Fibers

The most common configuration for performing on-chip detection has been the embedded fiber type of device as listed in Table 1. A typical setup, shown in Fig. 1, includes a light source and fiber for delivery, exit fiber connected to a detection system, microfluidic channel, and liquid delivery components. The fibers are usually embedded in chip materials consisting of polydimethylsiloxane (PDMS), SU-8 epoxy, polymethyl methacrylate (PMMA) or glass [3].

An *insertion guide* is used to accurately locate an etched optical fiber. Fiber distal ends are chemically etched to reduce the diameter by removing fiber cladding for easier insertion into the LOC. The plastic or rubber jacket of optical fiber should be moved before this etching. One of the keys to fabrication involves accurately setting the distance from the fiber channel to the microfluidic channel shown in Fig. 1.

Proximity Fibers

The next most popular configuration for performing on-chip detection uses optical fibers in close proximity to the detection zone as summarized in Table 2 and shown in Fig. 2. The input fiber and the receiving fiber tips are usually within 1 mm of the chip surface. In some cases, lenses and filters are used to focus and/or collect the light. Other system components such as light sources, detectors, and computers are the same as those used with the embedded fiber devices.

There are many commercial fiber types, jacketing options, and connectors which can be used such as the example shown in Fig. 2. Fiber accessories and fixtures allow one to easily connect fibers, and integrate them into experimental set-ups. Bulk fibers and fiber assembly-making kits and components are also readily available.

The main advantage of the proximity fiber detection system is that fabrication is much easier due to the fact that the fibers are not connected directly into the chip. This greatly simplifies the chip fabrication process. One disadvantage is that it is more difficult to achieve the maximum intensity of light entering and exiting the detection zone because the fiber tips are further away from the chip. Lenses and filters

On-Chip Detection Using Optical Fibers, Table 1 Embedded fiber types of on-chip detectors (to be continued)

Principal Investigator (Country)	Journal Year	Vol. Page	Fiber Type	Source Light	Lens	Detected Light	Detector	Filters	Fluid Channel ($h \times w$), μm	Motive Force	Chip Mat'l	Analyte	LOD	Application
A. Llobera (Germany)	Lab Chip 2005	5: 506	multimode fiber core 230 μm/ clad 250 μm material: silica	blue LED $\lambda = 460$ nm	biconvex	absorbance	spectrometer	none	100 × 230	syringe pump	PDMS	fluorescein methylorange	mM range for both	pH measurement
A. Wolff (Denmark)	Lab Chip 2004	4: 372	multimode fiber core 70 μm/ clad 100 μm material: silica	red laser $\lambda = 633$ nm	elliptical	forward light scattering	PMT	none	100 × 600	syringe pump	SU-8 and PDMS	polystyrene microspheres	50 – 65 beads per second	flow cytometry
D. Li (Canada)	Instrum Sci Technol 2005	33: 597	multimode fiber #1 core 50 μm/ clad 125 μm multimode fiber #2 core 100 μm/ clad 125 μm material: silica	red laser diode $\lambda = 640$ nm	none	transmitted light	Si PIN photodiode	none	80 × 80	syringe pump	PDMS and glass	polystyrene microspheres	10 μm particles	flow cytometry
G.M. Whitesides (United States)	Anal Chem 2001	73: 4491	multimode fiber core 100 μm, clad 140 μm *NA* = 0.29 material: silica	blue LED $\lambda = 470$ nm	none	fluorescence	micro-avalanche photodiode	dichroic	50 × 100	electrokinetic	PDMS	fluorescein	25 nM	spectro-fluorometry; spectrophotometry
G.-B. Lee (Taiwan)	Sens Actuators A 2003	107: 125	multimode fiber #1 core 63 μm, clad 100 μm single mode fiber #2 core 9 μm, clad 100 μm material: silica	red laser $\lambda = 633$ nm mercury vapor λ = spectral	none	fluorescence	PMT	band-pass	50 × 70	syringe pump	soda lime glass	Rhodamine B + Cy3; FITC-labeled polypeptides	multimode fiber = 10^{-7} M singlemode fiber = 10^{-6} M	capillary electrophoresis
G.-B. Lee (Taiwan)	Anal Chim Acta 2004	507: 163	singlemode fiber core 9 μm, clad 100 μm material: silica	red laser $\lambda = 633$ nm	10*x* objective	transmitted light	avalanche photodiode	none	40 × 80	electrokinetic	soda lime glass	polystyrene microspheres; red blood cells	10 μm particles	flow cytometry
G.-B. Lee (Taiwan)	Biosens Bioelectron 2004	20: 83	multimode fiber core 50 μm, clad 125 μm material: silica	mercury vapor λ = spectral	none	fluorescence	PMT	band-pass	50 × 100	electrokinetic	soda lime glass	X-174 DNA marker; Rhodamine B + Cy3	none reported	capillary electrophoresis
H.-P. Loock (Canada)	Proc SPIE 2005	5969: 1	singlemode fiber core 9 μm, clad 125 μm *NA* = 0.13 material: silica	laser diode $\lambda = 810$ nm	convex fiber	phase shift	InGaAs photodiode	none	100 × 360	syringe pump	glass	cyanine dye ADS805WS	240 nM	capillary electrophoresis
J. Hubner (Denmark)	Rev Sci Instrum 2001	72: 229	singlemode fiber core 9 μm, clad 125 μm *NA* = 0.12 material: silica	deuterium halogen λ = spectral	none	fluorescence	PMT	band-pass filters	50 × 500	syringe pump	silicon wafer	fluorescein; bodipy 650X	fluorescein 250 pM; bodipy 100 nM	spectro-fluorometry; spectrophotometry

Principal Investigator (Country)	Journal Year	Vol. Page	Fiber Type	Source Light	Lens	Detected Light	Detector	Filters	Fluid Channel $(h \times w)$, μm	Motive Force	Chip Mat'l	Analyte	LOD	Application
L.J. Golonka (Poland)	Int J Appl Ceram Technol 2006	3: 150	multimode fiber core 63 μm, clad 125 μm material: quartz	blue-green LED $\lambda = 502$ nm	none	transmitted light	photodiode	band-pass filters	125×125	peristaltic pump	low-temperature cofired ceramic (LTCC)	dye (Ponceau IV)	10 μg/ml	spectro-fluorometry; spectrophotometry
L.J. Golonka (Poland)	Sens Actuators B 2005	111-112: 396	multimode fiber core 63 μm, clad 125 μm material: silica	red LED $\lambda = 630$ nm	none	transmitted light	PMT	none	125×125	peristaltic pump	low-temperature cofired ceramic (LTCC)	fluorescein; creatinine $Cu(NH_3)_4$	none reported	spectro-fluorometry; spectrophotometry
S. Bargiel (Poland)	Sens Actuators A 2004	115: 245	multimode fiber #1 core 63 μm, clad 125 μm material: silica multimode fiber #2 core 750 μm clad 850 μm material: PMMA	blue LED $\lambda = 490nm$	none	fluorescence	spectrometer	none	200×500	peristaltic pump	silicon wafer & glass	fluorescein + erythrosine; phosphate	0 – 0.2 mg/ml of fluorescein + erythrosine; 0.2 – 1.6 g/ml phosphate	spectro-fluorometry; spectrophotometry
S.A. Soper (United States)	Lab Chip 2002	2: 88	singlemode fiber #1 core 8 μm, clad 125 μm multimode fiber #2 core 40 μm, clad 125 μm material: silica	red laser diode $\lambda = 750nm$	none	fluorescence	avalanche photodiode	band-pass filters	20×80	electrokine	PMMA	near-IR dye; NN382 fluorescence; intercalating dye TOPRO-5	1.4×10^{-20} *moles*	capillary electrophoresis
T. Fujii (Japan)	Lab Chip 2003	3: 40	multimode fiber core 105 μm, clad 125 μm $NA = 0.22$ material: silica	incandescent tungsten $\lambda =$ spectral	PDMS 2D lenses	fluorescence	CCD camera	band-pass filters	50×130	syringe pump	PDMS on glass	FITC-labelled albumin	170 mM FITC solution	spectro-fluorometry; spectrophotometry
Z. Cui (United Kingdom)	Biomed Microdevices 2005	7: 323	multimode fiber core 63 μm, clad 125 μm material: silica	green LED $\lambda = 568$ nm	none	absorption	Si PIN photodiode	none	150×250	syringe pump	SU-8 and PDMS	lactate	50 mg/l	spectro-photometry

On-Chip Detection Using Optical Fibers, Table 2 Proximity fiber types of on-chip detectors

Principal Investigator (Country)	Journal Year	Vol. Page	Fiber Type	Source Light	Lens	Detected Light	Detector	Filters	Fluid Channel ($h \times w$), μm	Motive Force	Chip Mat'l	Analyte	LOD	Application
J.-Y. Yoon (United States)	Biosens Bioelectron 2007	22: 2216	multimode fiber core 400 μm, clad 500 μm $NA = 0.22$ material: silica	blue LED $\lambda = 470nm$ red laser diode $\lambda = 635nm$	none	forward light scattering	mini-spectrometer	none	150×150	syringe pump	PDMS on glass	anti-PR3 vasculitis marker	50 ng/mL	immunoassay
A. Okubo (Japan)	Anal Sci 2004	20: 209	multimode fiber core 800 μm, clad 1000 μm material: silica	xenon arc $\lambda =$ UV spectrum	10x objective	fluorescence	PMT	none	50×500	syringe pump	PDMS	sulfite and nitrite	sulfite 10^{-6}M; nitrate 10^{-7}M	spectro-fluorometry; spectrophotometry
D. Li (Canada)	Biosens Bioelectron 2006	21: 2006	multimode fiber core 200 μm, clad 350 μm material: silica	red laser diode $\lambda = 640nm$	none	fluorescence	Si PIN photodiode	filter cube dichroic; band-pass	20×100	electrokine	PDMS	Escherichia coli 0157:H7	0.3 ng/μL	immunoassay
H. Mihara (Japan)	Mol Biosyst 2005	1: 363	multimode fiber core 1000 μm, clad 1200 μm material: PMMA	quartz halogen $\lambda =$ spectral	none	reflectivity	Si PIN photodiode	none	1000×1000	syringe pump	glass	calmodulin (CaM) as model protein	30 nM	immunoassay
J. N. McMullin (Canada)	Appl Photon Technol 2003	6: 114	multimode fiber core 1000 μm, clad 1200 μm $NA = 0.50$ material: PMMA	green LED $\lambda = 570nm$ red laser diode $\lambda = 640nm$	ball lens	fluorescence	PMT	band-pass filters	150×150	syringe pump	glass	fluorescent polystyrene microspheres	15 μm spheres	flow cytometry
J. N. McMullin (Canada)	Rev Sci Instrum 2003	74: 4145	multimode fiber core 1000 μm, clad 1200 μm $NA = 0.50$ material: PMMA	red laser diode $\lambda = 700nm$	ball lens	fluorescence	PMT	band-pass filters	20×50	syringe pump	glass	fluorescent polystyrene microspheres	15 μm spheres	flow cytometry
R. Bruce (United States)	Biosens Bioelectron 2006	21: 1893	fiber array width: 50 mm $NA = 0.66$ material: silica	mercury vapor $\lambda =$ spectral red laser diode $\lambda = 640nm$	none	fluorescence	PMT	dichroic filters	not reported	syringe pump	glass	Circulating tumor cells	10^{-6}M to 10^{-7}M	immunoassay
S. M. Cramer (United States)	J Chromatogr A 2004	1044: 277	multimode fiber core 600 μm, clad 630 μm $NA = 0.22$ material: silica	deuterium halogen $\lambda =$ spectral	10x objective	absorbance	CCD array	none	40×150	peristaltic pump	quartz	three peptides (Trp–Ala, Leu–Trp and Trp–Trp); thiourea	thiourea 167 μM	electro-chromatography; spectrophotometry

On-Chip Detection Using Optical Fibers, Table 3 Wetted fiber types of on-chip detectors

Principal Investigator (Country)	Journal Year	Vol. Page	Fiber Type	Source Light	Detector	Filters	Fluid Channel $(h \times w)$, µm	Motive Force	Chip Mat'l	Analyte	LOD	Application
R. Irawan (Singapore)	Lab Chip 2006	6: 1095	multimode fiber #1 core 1000 µm, clad 1010 µm material: PMMA multimode fiber #2 core 600 µm, clad 750 µm material: silica	blue LED $\lambda = 470 nm$	mini-PMT	band-pass	100×210	syringe pump	acrylic	fluorescein	0.005 mg/L	spectro-fluorometry; spectrophotometry
A. Dybko (Poland)	Analyst 2003	128: 523	multimode fiber core 1000 µm, clad 1200 µm material: PMMA	red LED $\lambda = 630 nm$	spectrometer	none	1000×1000	peristaltic pump	PDMS	saccharose	none reported	refractometry; spectro-photometry
A. Dybko (Poland)	Proc SPIE 2003	5576: 314	multimode fiber core 1000 µm, clad 1200 µm material: PMMA	blue LED $\lambda = 470 nm$ red LED $\lambda = 640 nm$	spectrometer	none	1000×1000	peristaltic pump	PDMS	erythrosine; saccharose; bromothymol blue	none reported	refractometry; spectro-photometry
A. Dybko (Poland)	Sens Actuators B 2005	107: 184	multimode fiber core 1000 µm, clad 1200 µm material: PMMA	blue LED $\lambda = 470 nm$ red LED $\lambda = 640 nm$	spectrometer	none	1000×1000	peristaltic pump	PDMS	glucose; fluorescein	none reported	refractometry; spectrophotometry; spectro-fluorometry
D. Walt (United States)	Anal Chem 2005	77: 5583	fiber array 50,000 fibers diameter: 1 mm material: silica	xenon arc $\lambda = $ UV spectrum	CCD camera	dichroic	1000×1000	syringe pump	PMMA	Bacillus thuringiensis Kurstaki (BTK), biowarfare agent simulant.	10 aM	immunoassay



On-Chip Detection Using Optical Fibers, Figure 3 Wetted optical fiber device with the end of a fiber inserted directly into the analyte flow stream

are sometimes used to compensate for this light traveling distance issue.

Wetted Fibers

Table 3 lists another type of on-chip detection that is performed using *wetted* optical fibers. In this case, the ends of the fibers are inserted directly into the analyte flow stream as shown in Fig.3. Prior to insertion, an indicating layer of biomolecules must be immobilized as sensing elements on the fiber tips as shown in Fig. 4. The ends of the fibers are first decladded and polished, followed by incubation in a labeled antibody/protein solution. Fluorophore labeling is the most common, but chromophore or Raman reporter can also be used. This produces a sensing region on the surface of the fiber. This fluorescent indicating layer responds to the presence of analyte by changing its optical properties. The change in the indicator's properties affects the light which is transmitted back through the fiber to a detector. The change in intensity or spectral properties of the returning light correlates with analyte concentration. Similar to any optical immunoassays, labels (e. g. fluorophore) can be located not only on the fibers but within solution and/or other biomolecules (thus sandwich assay configuration). Competitive binding assay or various other assay formats are all possible in wetted fiber configuration. Wetted fiber optic sensors are created using either a single fiber or a fiber array bundle. A fiber array bundle may contain thousands of individually clad fibers, each $3-10\,\mu$m in diameter. An imaging fiber bundle is able to transmit light signals and images concurrently, while a single-core fiber can carry light, but not images.

Fiber Optics Technology

An optical fiber is simply a very thin piece of glass or plastic which acts as a pipe, through which light can pass. The light that is passed down the fiber can be turned on and off to transmit digital information, or changed in amplitude, frequency, or phase to transmit analog information. This is an important distinction, since telecommunication fibers are based in digital applications while sensor fibers are based in analog applications. On-chip bioreactions emit analog signals, not digital. This is one reason why signal attenuation is a lesser issue for sensor applications than with telecommunications.

Digital signals are sent as square waves, with high frequency components. The bandwidth of a fiber is set by the maximum frequencies it can handle. In sensor applications (analog), high frequencies are generally not an issue except when fluorescence decay time is of interest; and thus, signal attenuation due to bandwidth is typically not an issue. Also, signal attenuation over hundreds of kilometers (dB/km), which is a key parameter for telecommunications, is not a factor for LOC fiber optic sensors which usually travel less than a few meters.

Signal flow direction in fiber optics consists of simplex or duplex methods as illustrated in Fig. 5. The simplex method allows data to flow in one direction only. This is the common case where one fiber is used to transmit the light source while another fiber is used to receive and send the emitted signal to a detector. The duplex method allows simultaneous flow of information in both directions. When detection is performed using wetted optical fibers, it is usually done using the duplex method, where light delivery


Cladding
Analyte
Fluid
Channel
Etched Core
Bio-Probes
Flow

On-Chip Detection Using Optical Fibers, Figure 4 An indicating layer of biomolecules are immobilized as sensing elements on the fiber tips. Here an antibody-antigen immunoassay is shown


Light
Source
Data Flow one direction only
Detector
Simplex system
Light
Source
Data Flow both directions
Detector
Duplex system

On-Chip Detection Using Optical Fibers, Figure 5 The simplex fiber arrangement is normally used for embedded and proximity fibers (top). The duplex setup is used with wetted fiber optic devices (bottom)

and detection both occur simultaneously in opposite directions. There is no problem using the same fiber for sending and receiving light waves. The larger core diameters of multimode fibers are capable of handling thousands of light modes without interference.

The optical region of the spectrum where fiber optic devices operate is from 300 nm to 2 μm wavelengths. The wavelengths used in fiber optic systems are matched to the particular characteristics of the system. Plastic fibers operate best at visible wavelengths, non-silica glass fibers are designed to operate at infrared wavelengths, and special grades of doped silica are used in the near-ultraviolet region. Most optical fibers use silica glass, which is most transparent to light in the near-infrared region from 700 – 1600 nm.

Most LOC devices require detection in the UV-VIS spectrum for biomaterial applications. These wavelengths require quartz or doped silica core fibers, since glass and



On-Chip Detection Using Optical Fibers, Figure 6 Cross section of a typical multimode, step index fiber. Some LOC detection devices employ fibers with cores up to 1mm in diameter

plastic will not transmit very efficiently below 400 nm. Doped silica fibers with high hydroxyl (−OH) content for UV-VIS, or low hydroxyl (−OH) content for VIS-NIR are often used in biosensor fibers. When working in the UV wavelengths, the cladding of the fiber must be chosen such that it will not fluoresce and create noise. The cladding material also affects the light-acceptance angle of the fiber.

Construction of an optical fiber begins with a tube of glass consisting of a number of layers of concentric rings as shown in Fig. 6. Each ring of glass has a different refractive index. Total internal reflection (TIR) is required to send light down the center of these concentric glass tubes. To achieve TIR, the outer glass rings must have a lower refractive index than the inner glass core in which the light is traveling. The core (50 μm) and cladding (125 μm) diameters shown are typical of the fibers used in some LOC devices. TIR should be achieved for successful use of optical fibers, and there exist maximum allowable bending and strain (both extension and compression) as well as maximum/minimum operating temperatures. The ultimate tensile strength of glass is also of important interest.

Numerical aperture refers to the maximum angle of light allowed into the fiber tip. For light to travel down a fiber, it must enter and reflect off the cladding at greater than the critical angle. Due to refractive changes in the direction of light as it enters the fiber core, there is a limit to the angle at which light can enter the core and propagate down the optic fiber. Any light striking the cladding at greater than the critical angle will penetrate the cladding and leak out as illustrated in Fig. 7 (top).

For light entering within the cone in Fig. 7 (bottom), all the rays will strike the cladding at less than the critical angle and transmit down the fiber. This is referred to as the acceptance cone and the half angle (θ) of this cone is referred to as the acceptance angle. The value of the acceptance angle depends on the refractive indices of the core, cladding, and air. A light ray entering the core at an angle greater than (θ) will disperse into the cladding. The term used to specify the light collecting ability of a fiber is the numerical aperture (NA). NA is the sine of the acceptance angle θ, that is: $\mathrm{NA} = \sin 11.5° = 0.20$ for the example shown.

Optical fibers with high NAs will accept more light than fibers with low NAs. High NA fibers must be used when weaker light sources such as LEDs are used. Low NA fibers generally require more expensive light sources, such as lasers, to achieve sufficient intensity for high quality transmission.

Modal dispersion is a phenomenon which affects the clarity of light transmission. A fiber with a large diameter and high NA will have a large number of modes (rays of light) operating along its length. Optical fibers are classified according to the number of rays of light that can be carried down the fiber simultaneously. This is referred to



On-Chip Detection Using Optical Fibers, Figure 7 Light rays striking the core at less than the critical angle will penetrate the cladding and leak out (top). Light entering within the acceptance cone will strike the cladding at greater than the critical angle and transmit down the fiber (bottom)

as the *mode of operation* of the fiber. A mode of light is simply a single light ray. The higher the mode of an optical fiber, the more rays of light that can travel down the core. It is possible for a fiber to carry as many as several thousand modes or as few as only one.

An omnidirectional light source (i. e. one that radiates light rays equally in all directions) such as an LED, emits several thousand rays of light in a single pulse. Because an LED injects a broad beam angle into the core, each mode of light travels at a different angle as it propagates down the fiber, and will travel different total distances over the length of the fiber. Therefore, it takes different lengths of time for each light ray to travel from one end of the fiber to the other. The light source will launch all modes into the fiber at exactly the same time, and the signal will appear at the beginning of the fiber as a short sharp pulse. By the time the light reaches the end of the fiber, it will spread out and appear as an elongated pulse. This is referred to as *modal dispersion*. Modal dispersion increases with higher NA, while the bandwidth of a fiber decreases with higher NA.

A specific number of modes are allowed to propagate down the length of a fiber. When the core and cladding each have a constant refractive index across their cross sections, but the core refractive index is different than the cladding refraction index, then they behave like an optical waveguide. This is referred to as *step index* and in this fiber type, only a specific number of modes can propagate.

As the diameter and the NA decrease, so do the number of modes that can propagate down the fiber. The decrease in modes is affected more by reduction in diameter than by reduction in NA. As the diameter decreases to the wavelength of light, then only one mode will travel down the fiber. This state is referred to as *single mode* propagation or a *single mode* fiber.

Multimode fibers generally refer to fibers with a core diameter of 50 μm or more. Because of their large diameter, multiple modes of light are able to travel down the core. The wider diameter of the multimode fibers makes them suitable for use with LED light sources. This normally produces a lower cost system than single mode fibers, which have a small diameter and require the use of lasers. However, allowing multiple modes of light to travel down a fiber may cause modal dispersion. The good news is that the short optical fiber lengths in most LOC systems make problems with modal dispersion unlikely.

Step and graded index fibers differ in the gradients of their refractive indices. A step index fiber has a glass core of constant cross-sectional refractive index, surrounded by a cladding of a different but constant cross-sectional refractive index. Because of this sudden change in the refractive index, light will reflect off the core/cladding interface and transverse its way down the core. The refractive index of the core (N_1) is typically 1.48 while the cladding is 1.46 (N_2). The acceptance angle (θ_a) is typically near 14°. Step index fibers used in telecommunications exhibit modal dispersion which limits their transmission bandwidth and speed. However, step index fibers are often used in chip sensor applications, where fiber lengths and data rates are much lower than in communication applications.

Graded index (GRIN) multimode fiber has a core with a gradually changing cross-sectional refractive index. The highest refractive index is in the core center and then gradually reduces, as it moves to the outer edge of the core. Because of this gradually changing refractive index, the light rays refract (rather than reflect as in step index fibers) as they move through the core, and produce sinusoidal light wave patterns in the fiber. The practical effect of this curved refractive index profile is that light rays that are traveling further from the center axis of the core will have further to travel, but are traveling through the lowest refractive index and will therefore be traveling the fastest (Snell's law). Light rays that are traveling near the center of the core are moving the shortest distance but going through the highest refractive index and therefore traveling the slowest. The result is that all the rays tend to arrive at the end of the core at the same time, which means that modal dispersion is greatly reduced in graded index fibers.

Single-mode fibers are used to reduce the number of modes traveling down a fiber and therefore reduce modal dispersion. A single-mode fiber is basically a step index fiber with a very small core diameter, generally $8-9\,\mu$m. To reduce the number of modes, the fiber is constructed with very little difference between the refractive indices of the core and the cladding. As the difference between the refractive indices of the core and cladding decrease, the critical angle increases. Therefore, only light approaching at a very large angle of incidence is internally reflected and all other rays will dissipate into the cladding. Because of this, only a single mode of light is able to traverse down the fiber (i. e. the fundamental mode).

When using a single-mode fiber, light must be precisely aimed down the center of the core, or light will be lost to the cladding. With only the fundamental mode traveling down the fiber, there can theoretically be no modal dispersion in single-mode fiber. The signals input at one end of the fiber appear at the output of the fiber with exactly the same shape. As optical biosensors move toward single molecule detection, single-mode fibers may be required.

Alignment of fibers is a major concern with all on-chip detection using optical fibers. There are many issues involved in aligning fibers and connecting fibers. The main concern when connecting two optical devices together is *attenuation*, the fraction of optical power lost in the connection process. Attenuation is the sum of the losses from a number of factors including: misalignment of fibers, differing core diameters, numerical aperture differences, reflection from fiber ends, spacing between the ends of the fibers, fiber tip end finish and cleanliness, and bends in the fibers. Theoretical analysis of the losses caused by these factors is complicated by the fact that the distribution of power across the face of a fiber is usually unknown and varies according to the type and length of fiber, method of excitation, etc.

Plastic fibers such as PMMA have also been used successfully with both communications and sensor applications. Plastic fibers are, however, limited to step index, multimode construction. Because of the nature of plastics, the fabrication process produces a core and cladding with significantly different refractive indices. Most plastic fibers have a core refractive index of 1.50 and a 1.40 cladding refractive index. A typical NA is 0.50, which represents an acceptance angle of 30° (an acceptance cone of 60°) for plastic fibers, which allows them to collect a great deal of light.

There are several other advantages associated with using plastic fibers. First, they are more robust than glass fibers. They can sustain significantly more shock, pressure and stress than glass fibers. Second, they are far more flexible, easier to handle and to terminate than glass fibers. Finally, they are generally cheaper than glass.

However, plastic also some disadvantages. Plastic fibers have a much higher attenuation than glass and can only be used over very short distances. Plastic has an optimum operating wavelength of 650 nm, which may not match the sensor application. Plastic fibers also have very limited operating bandwidth. Another issue for some sensor applications is that plastics are limited to much lower temperatures than glass fibers.

Light Sources

The light-emitting diode (LED) is a semiconductor device that emits incoherent, narrow-spectrum light. The color of the emitted light depends on the semiconducting material used, and can be near-ultraviolet, visible or infrared.

The laser light is monochromatic, i. e., consisting of a single wavelength or color, and emitted in a coherent beam, contrary to common light source.

A laser diode is a laser where the active medium is a semiconductor similar to that found in a light-emitting diode. Laser diodes are used in devices for optical storage, laser pointers, and fiber optics.

The quartz halogen lamp contains a tungsten filament surrounded by a halogen gas such as iodine or bromine. Halogen lamps can be run at higher temperatures, allowing for higher luminous efficacy, apparent brightness, and whiter color temperature. Because the lamp must be very hot to create this reaction, the halogen lamp's envelope must be made of quartz.

The deuterium halogen lamp is a low pressure gas discharge light source often used in spectroscopy when a full spectrum source of illumination in the ultraviolet region is needed. The origin of the continuum ultraviolet radiation extends from around 160 nm to 400 nm.

A mercury-vapor lamp is a gas discharge lamp which uses mercury in an excited state to produce light. They also offer a very long lifetime, as well as intense lighting. Like fluorescent lamps, mercury vapor lamps usually require a starter which is usually contained within the mercury vapor lamp itself.

Xenon arc lamp uses ionized xenon gas to produce a bright white light that closely mimics natural daylight. Xe lamp, however, have a significant amount of spectral fine structure in many parts of the spectrum, as this is one factor to consider when choosing between a halogen and a Xe source. The white, continuous light generated with this arc is of daylight quality and all movie projectors in theaters employ these lamps.

The incandescent tungsten lamp is a source of light that works by passing an electric current through a thin filament, heating it and causing it to emit light. This is the typical light bulb for home use.

Light Detectors

Photomultiplier tubes (PMTs) are extremely sensitive detectors of light in the ultraviolet, visible and near infrared. These detectors multiply the signal produced by incident light by as much as 10^8, from which single photons can be resolved. The PMT benefits from a combination of high gain, low noise, high frequency response and large area of collection.

The photodiode is a semiconductor diode that functions as a photodetector. Photodiodes are packaged with either a window or optical fiber connection, in order to let in the light to the sensitive part of the device. They may also be used without a window to detect vacuum UV or X-rays.

Avalanche photodiodes (APDs) are photodetectors that can be regarded as the semiconductor analog to photomultipliers.

Si PIN photodiodes feature low capacitance, which enables them to deliver a wide bandwidth with only a low bias voltage, making them ideal for high-speed photometry as well as optical communications. Some PIN diodes have a mini-lens, which increases fiber coupling efficiency and enhanced sensitivity for violet laser detection.

The spectrometer measures light over a specific range of wavelengths, from gamma- and X-rays into the far infrared. The variable measured is most often the light's intensity but could also, for instance, be the polarization state. Spectrometers are used for producing spectral lines and measuring wavelengths and intensities.

The charge-coupled device (CCD) detector array is an image sensor, consisting of an integrated circuit containing an array of linked or coupled capacitors sensitive to light. CCDs are used in digital photography, astronomy, photometry, optical and UV spectroscopy and other high speed techniques.

The complementary metal-oxide-semiconductor (CMOS) detector array is another type of an image sensor. Although less sensitive than the CCD array, it is increasingly used in sensor and Lab-on-a-Chip applications due to: much lower power consumption, much lower cost, easier compatibility with digital electronics, and the fact that for many Lab-on-a-Chip applications the background levels are sufficiently high that the higher sensitivity of the CCD does not confer a significant advantage.

Optical Filters

An optical filter is a device which selectively transmits light having certain properties (often, a range of wavelengths), while blocking the remainder. Filters are commonly used in many optical instruments including LOC sensors.

A *longpass (LP) filter* is a colored glass filter that attenuates shorter wavelengths and transmits longer wavelengths over the active range of the target spectrum. In fluorescence, longpass filters are frequently utilized in dichroic mirrors and barrier (emission) filters.

A *shortpass (SP) filter* is a colored glass filter that attenuates longer wavelengths and transmits shorter wavelengths over the active range of the target spectrum. In fluorescence, shortpass filters are often employed in dichromatic mirrors and excitation filters.

A *band-pass filter* is a device that passes frequencies within a certain range and rejects (attenuates) frequencies outside that range. The filter does not attenuate all frequencies outside the desired frequency range completely. This is known as filter roll-off, and is usually expressed in dB of attenuation per octave of frequency.

A *dichroic filter* is a very-accurate color filter used to selectively pass light of a small range of colors while reflecting other colors. By comparison, dichroic mirrors and dichroic reflectors are characterized by the colors of light that they reflect rather than the colors they pass. Because unwanted wavelengths are reflected rather than absorbed, dichroic filters don't absorb much energy during operation and so don't become nearly as hot as the equivalent conventional filter.

Filter wheels and *filter cubes* usually contain four or more individual filters which can be rotated into position. Since all filters are the same thickness, no refocusing is required when changing filters. Filter wheels and cubes are designed to closely and rigidly couple to CCD cameras or other optical equipment.

Applications of On-Chip Detection Using Optical Fibers

Nearly all of the published studies in on-chip detection using optical fibers were conducted after the year 2000. Most of the work to date has been performed at universities in North America (Canada and United States), Europe (Denmark, Germany, Poland and United Kingdom), and East Asia (Japan, Singapore and Taiwan).

Fiber Types

There have been three main types of optical fibers used for on-chip detection as listed in Tables 1–3. The vast majority of researchers have chosen multimode fibers made from fused silica (glass).

Most of the embedded fiber devices (Table 1) contain small diameter (50 – 100 μm) multimode fibers. Many researchers further reduce the size of the fiber by acid etching to remove much of the cladding. For example, when starting with a 63 μm core and 125 μm cladding, the fiber may be acid etched to reduce the cladding size to perhaps 70 μm. This facilitates assembly of the fibers into the micro dimensions of the device. Several embedded fiber devices have been made from the singlemode type (9 μm core), but it has been challenging to deliver or gather sufficient amounts of light while being limited to a single mode and low NA. Lee et al. were able to obtain an order of magnitude lower LOD by using multimode fibers compared to singlemode (Table 1, 5th row) [6].

One advantage of using a proximity type fiber arrangement (Table 2) is that a much larger diameter multimode fibers can be used. Most of these chips are based on fiber cores from 400 μm to 1000 μm. The silica fibers usually have NAs of 0.22, while plastic fiber NAs of 0.50 are common. The proximity fibers can gather more light, but there is a greater distance between the analyte and the fiber which reduces the signal strength.

The wetted fiber types listed in Table 3 have been based on multimode fibers or fiber array bundles. In Fig. 4, the large diameter (1000 μm) multimode cores are acid etched or stretched to create a sharp probe tip. In either case, the fiber surface is treated for binding proteins or other molecular probes. Walt et al. [7] (Table 3, 5th row) developed a chip using a wetted fiber optical array of thousands of individual fibers in a coherent bundle. By etching the core at the fiber bundle's tip, an array of microwells was created and loaded with microspheres. The microspheres are coated with various sensing materials such as antibodies. Resulting changes in fluorescence intensity correspond to analyte concentration.

Lighting and Detection

The most common light source for all applications has been the blue LED (470 nm) and red LED (635 nm), generally used with multimode fibers. Lasers are used with singlemode fibers because the small core requires more intense power. For spectrophotometry, devices utilize full spectral light sources such as mercury vapor, halogen, or tungsten lamps. This allows detection of light absorbance or transmission over the spectrum.

Lenses are sometimes used to focus both source and detected light. Concave, convex, bi-convex and other converging lenses have been used. Loock et al. [8] formed a convex lens directly onto the ends of the fibers (Table 1, 8th row). Fujii et al. [9] fabricated lenses into the chip PDMS structure (Table 1, 14th row). In some cases, filters are also used to sharpen the signal. The most popular filters are the band-pass and dichroic variety.

Chip Fabrication

The chips themselves are most commonly made from SU-8 molds and polydimethylsiloxane (PDMS) which is a silicon-based organic polymer. It is optically clear, inert, and non-toxic, which makes it well suited for Lab-on-a-Chip applications. Other glasses, silicon wafers, and acrylics have also been used. Recently, Golonka et al. have used low-temperature cofired ceramic (LTCC) technology to produce electrical, optical, and fluidics within an LOC structure (Table 1, 10th and 11th rows) [10, 11].

The microfluidic channels in these LOC systems are typically 100 μm depth and width. The liquids are moved with syringe pumps, peristaltic pumps, or some type of electrokinetic method. The syringe pump generally provides a low cost, yet accurate solution.

Analyte Detection

Much of the early work in this area was done for flow cytometry applications using embedded or proximity fiber systems. These devices typically measured the counts and velocities of microspheres in liquids. These systems are able to detect 10 μm spheres at a rate of 65 particles per second (Table 1, 2nd row) [12].

Another application involves capillary electrophoresis (CE) used to separate ionic species based on their size-to-charge ratio in microchannels filled with electrolytes. Various dyes have been used such as Rhodamine B, Cy3, and Topro-5 to detect biomolecules and DNA. LOD's of 100 – 200 nM have been reported (Table 1, 5th, 8th and 13th rows) [6, 9, 13].

The most popular applications have been in the areas of spectrophotometry and/or spectrofluorometry involving the measurement of light intensity as a function of wavelength. These devices have been used to measure chemical concentrations, amino acids, and fluorescent species down to an LOD of 25 nM (Table 1, 4th row) [14].

Most recently, researchers have begun using these chips to conduct immunoassays. An immunoassay is a test that measures the level of a substance in a bio-sample, typically serum or urine, using the specific binding reaction of an antibody or antibodies to its antigen. LOC's have been used to detect protein markers for vasculitis and cancer (Table 2, 1st and 7th rows) [15, 16] at LOD's in the 100 nM range. They have also been used to detect *E. coli* and BTK-a biowarfare agent simulant (Table 3, 5th row) [7].

Future Directions for Research

Lab-on-a-Chip detection using optical fibers will be guided by two major driving forces: molecular analysis and molecular biology, and microelectronics and optical telecommunications. Most Lab-on-a-Chip technologies to date have focused primarily on molecular analysis by miniaturizing capillary electrophoresis (CE), chromatography, flow cytometry, and sensing conditions such as pH, ionic strength, and concentrations of analytes. Currently in the U.S., biodefense funding from DOD and DARPA are driving much of the LOC academic research in universities. These defense programs tend to focus on detection and immunoassays for bioterror prevention. The recent emphasis on high-throughput sequencing for genomics and proteomics has also begun to use microfluidics devices. Current commercial development, in the meantime, is driven to a much greater extent by the real need (and real market for) in vitro diagnostics and drug discovery tools. While the manufacturing technologies being developed in microelectronics will continue to pace the fabrication of microelectromechanical systems (MEMS) in the future [3].

Fiber optics technology has always been dominated by the telecommunications markets and this will certainly continue. Fibers will continue to increase in speed and bandwidth by using new methods such as dense wavelength-division multiplexing (DWDM). Future fibers will be even more pure, and conduct light and images with more clarity. Recent growth in the sensors industry has spawned several new companies which focus strictly on fibers for optical detection. While the communications industry has focused on longer IR wavelengths, the sensor fiber optics companies will work on improving light transmission down into the UV range for biodetection.

Embedded fiber optics will continue to be successful only as microfabrication methods are simplified and commercialized. The original hope of microfluidics was that photolithography and associated technologies that had been so successful in silicon microelectronics, and in microelectromechanical systems (MEMS), would be directly applicable to microfluidics. Some of the earliest work in fluidic microsystems did, in fact, use silicon and glass, but these materials have largely been displaced by plastics. For analyses of biological samples in water, devices fabricated in glass and silicon are usually inappropriate. Silicon, in particular, is expensive, and opaque to visible and ultraviolet light, and cannot be used with optical methods of detection. It is easier to fabricate the components required for microanalytical systems in elastomers than in rigid materials but these methods have not been commercialized. Exciting future research areas will involve embedding light sources and micro-detectors directly into the chip.

Proximity fiber optics should continue to grow in popularity as light sources and detectors become smaller and portable. Companies are now producing low cost LEDs, lasers, and spectrometers that make it relatively easy to set-up on-chip detection devices. These systems will require better and lower cost lenses, filters, light sources and detectors especially in the near-UV wavelengths. Again, this is because almost all research to date has focused on the IR wavelengths used for telecommunications and the internet. Future work in proximity fiber optics will focus on lowering signal-to-noise ratios and increasing the sensitivity of distinguishing different wavelengths.

Wetted fibers on-chip have only recently been attempted and shows great promise. Like embedded fibers, the wetted fibers require very sophisticated microfabrication techniques. Microfluidics has seen the rapid development of new methods of fabrication, and of components such as microchannels that serve as pipes, and other structures that form valves, mixers, and pumps that are essential elements of microchemical 'factories' on a chip. Wetted fibers will require easier ways of inserting and removing the fibers from the chip as well as simpler methods of preparing the fiber tips with biomolecules for detection.

An LOC system must have a number of generic components: a method of introducing reagents and samples; methods for moving these fluids around on the chip, and for combining and mixing them; and various other items such as detectors for most microanalytical work, as well as components for purification of products for systems used in synthesis. The field has, so far, centered on demonstrating concepts for these components. In the future there will be sufficient methods of fabrication, and a range of components which will make it possible to apply microfluidic systems to the resolution of problems rather than simply to the demonstration of principles [3].

Cross References

- ► Flow Cytometer Lab-on-Chip Devices
- ► Spectrophotometric Analysis
- ► Capillary Electrochromatography
- ► Spectrofluorometry
- ► Immunoassay
- ► Capillary Electrophoresis

References

1. Bailey D, Wright E (2003) Practical Fiber Optics. Elsevier, Burlington
2. Shotwell RA (ed) (1997) An Introduction to Fiber Optics. Prentice Hall, Englewood Cliffs
3. Whitesides GM (2006) The origins and the future of microfluidics. Nature 442(27):368–373
4. Grattan KTV, Sun T (2000) Fiber Optic Sensor Technology: Introduction. In: Grattan KTV, Meggitt BT (eds) (2000) Optical Fiber Sensor Technology. Kluwer Academic, Dordrecht
5. Zhang ZY, Grattan KTV (1998) Commercial activity in optical fiber sensors. In: Grattan KTV, Meggitt BT (eds) (1998) Optical Fiber Sensor Technology. Kluwer Academic, Dordrecht, pp 257–306
6. Lin CH, Lee GB, Chen SH, Chang GL (2003) Micro capillary electrophoresis chips integrated with buried SU-8/SOG optical waveguides for bio-analytical applications. Sens Actuators A 107:125–131
7. Bowden M, Song L, Walt DR (2005) Development of a microfluidic plattform with an optical imaging microarray capable of attomolar target DNA detection. Anal Chem 77:5583–5588
8. Treflak NR, Barnes J, Rask F, Courtney DG, Walford R, Li R, Oleschuk RD, Loock HP (2005) Absorption measurements in microfluidic devices using ring-down spectroscopy. Proc SPIE 5969:59690O
9. Camou S, Fujita H, Fujii T (2003) PDMS 2D optical lens integrated with microfluidic channels: principle and characterization. Lab Chip 3:40-45
10. Golonka LJ, Zawada T, Radojewski J, Roguszczak H, Stefanow M (2006) LTCC microfluidic system. Int J Appl Ceram Technol 3:150–156
11. Golonka LJ, Roguszczak H, Zawada T, Radojewski J, Grabowska I, Chudy M, Dybko A, Brzozka Z, Stadnik D (2005) LTCC based microfluidic system with optical detection. Sens Actuators B 111–112:396–402
12. Wang Z, El-Ali J, Engelund M, Gotsaed T, Perch-Nielsen IR, Morgensen KB, Snakenborg D, Kutter JP, Wolf A (2004) Measurements of scattered light on a microchip flow cytometer with integrated polymer based optical elements. Lab Chip 4:372–377
13. Qi S, Liu X, Ford S, Barrows J, Thomas G, Kelly K, McCandless A, Lian K, Goettert J, Soper SA (2002) Microfluidic devices fabricated in poly(methylmethacrylate) using hot-embossing with integrated sampling capillary and fiber optics for flourescence detection. Lab Chip 2:88–95
14. Chabinyc ML, Chiu DT, McDonald JC, Stroock AD, Christian JF, Karger AM, Whitesides GM (2001) An integrated fluorescence detection system in poly(dimethylsiloxane) for microfluidic applications. Anal Chem 73:4491–4498
15. Lucas LJ, Han JH, Chesler N, Yoon JY (2007) Latex immunoagglutination assay for a vasculitis marker in a microfluidic device using static light scattering detection. Biosens Bioelectron 22:2216–2222
16. Hsieh HB, Marrinucci D, Bethel K, Curry DN, Humphrey M, Krivacic RT, Kroener J, Kroener L, Ladanyi A, Lazarus N, Kuhn P, Bruce RH, Nieva J (2006) High speed detection of circulating tumor cells. Biosens Bioelectron 21:1893–1899

On-Chip Electrospray

LESLIE YEO, JAMES FRIEND
Micro/Nanophysics Research Laboratory
Department of Mechanical Engineering, Monash
University, Clayton, VIC, Australia
leslie.yeo@eng.monash.edu.au

Synonyms

Electrospray ionization-mass spectrometry (ESI-MS); Electrospray mass spectrometry; Electrospray emitter on-chip; Chip electrospray mass spectrometry

Definition

Electrospraying utilizes an applied electric field to generate micron or nanometer sized aerosol drops. If DC fields are employed, the emitted drops carry a net charge which allows electrosprays to function as ionization sources, in particular, for mass spectrometry. With electrospray ionization (ESI), interfacing between microfluidic separation technology such as on-chip high performance liquid chromatography (HPLC) and capillary electrochromatography (CEC) with mass spectrometry (MS) is now realizable.

Overview

The concept of employing electrostatic charging to atomize a liquid source was first observed by John Zeleny in



On-Chip Electrospray, Figure 1 Taylor cone formation at the tip of a 100 μm capillary across which a 3 kV DC voltage is applied. A slender jet issues from the tip of the Taylor cone as a result of Rayleigh fission, subsequently breaking up to form aerosol droplets

1914. If the liquid is flowing through a metal capillary, the surface of which is raised to a potential with respect to a grounded source placed a small distance away, the electric field acts to stretch and deform the liquid meniscus at the capillary tip. The fluid physics under the influence of an electric field in such circumstances was described by Sir Geoffrey Ingram Taylor in 1964, who observed the meniscus to deform into a sharp cone with a specific half angle of 49.3° for highly conducting liquids. This Taylor cone, depicted in Fig. 1, arises due to the separation of electrical charges within the liquid or ambient phase to form a thin polarized layer of counter-ions near the meniscus interface; these counter-ions then drift towards the tip of the meniscus by tangential electromigration.

The counter-ion accumulation at the tip then creates a Coulombic repulsion force which causes the tip to disintegrate into a thin jet that emanates from meniscus when the surface tension force holding the drop together is exceeded, as shown in Fig. 1. This jet subsequently breaks up due to hydrodynamic or Coulombic instabilities to form a spray of small liquid drops. As the accumulated charge at the tip is transferred from the meniscus tip to the jet and subsequently to the drops, each individual drop carries a net charge. Since the size of the ejected drop shrinks during its flight due to evaporation, the repulsive force builds up due to the increase in the charge density. Coulombic fission then occurs once again when the Rayleigh limit

$$q > 64\pi^2 \varepsilon_{\mathrm{m}} a^3 \gamma \,, \tag{1}$$

is reached. In Eq. (1), q is the charge, ε_{m} the permittivity of the surrounding medium, a the drop diameter and γ the surface tension. The drop disintegrates to produce even smaller droplets, which themselves undergo similar disintegration cycles, as depicted in Fig. 2; this Rayleigh instability fission cascade eventually leads to charged drops with dimensions down to 10 nm orders.

The ability of the electrospray to produce very small, monodispersed charged drops then naturally lends itself as a powerful soft ionization technique for the mass spectrometry of large, complex and non-volatile biomacromolecules (e. g., DNA, peptides and proteins) which are otherwise denatured by other ionization techniques. Electrospray ionization (ESI) also has several advantages over matrix-assisted laser desorption/ionization (MALDI), which is another soft ionization technique. The use of lasers requires fine tuning of optical properties in order to ensure quality and reproducibility in the results; signals are dependent on the laser wavelength, pulse energy, time between pulses and impact angle, amongst others. Moreover, the inorganic salts in proteins can interfere with the ionization and hence elaborate sample preparation to remove these components is a vital step in MALDI. The small size of the laser spot compared to the sample also requires multiple laser pulses targeted at different sample regions in order to obtain a statistical average of the local concentration within the sample, which is further complicated by inhomogeneity due to partitioning of the analyte molecules as a result of non-uniform solvent evaporation. Sample dispensing onto MALDI target plates also requires the integration of complex components such as piezoelectric microdispensers or centrifugal delivery systems.

ESI was first proposed by Malcolm Dole in 1968 who noticed that the Coulombic fission cascade would eventually lead to sufficiently small drops which contained a single solute molecule that retained some of the drop charge such that a fully desolvated gas phase ion would ultimately be left once all the solvent evaporates, this mechanism being known as the charge residue model (CRM). These efforts were, however, largely unsuccessful practically due to the use of an ion-drift spectrometer to which the electrospray was interfaced. It was John Fenn, then at Yale University, who later developed a practical method for electrospray ionization mass spectrometry (ESI-MS) that allowed the identification and structure analysis of biomacromolecules of virtually unlimited molecular weights to an accuracy of 0.01% by averaging



On-Chip Electrospray, Figure 2 Schematic illustration of the Coulombic fission process occurring during DC electrospraying giving rise to successively smaller charged drops

over the signals generated by the multiple ions which are associated with the high mass-to-charge ratios of large, complex molecules [1]. In recognition of this significant contribution and its impact on genomic, proteomic and drug discovery research, Fenn was awarded the Nobel Prize in Chemistry in 2002. It should however be noted that the term *electrospray ionization* is somewhat misleading as the process is not akin to electron ionization in which electroneutral molecules are converted into ions. Instead, the electrospray essentially allows the transfer of analytes, already ionized in the liquid phase, into the gas phase [2]. Nevertheless, we will retain the term due to its widespread use in the literature.

The recent progress in micro/nanofabrication technology as well as microfluidics has spurred efforts to interface chip-based separation devices with electrospray ionization mass spectrometers. As frontiers in the ability to miniaturize the mass analyzers are being extended further, an integrated field portable microdevice that couples both on-chip separation (e. g., capillary electrophoresis, capillary electrochromatography and high-performance liquid chromatography) and analytical technology with an electrospray interface to produce a complete tool, which is both reliable and can be easily replicated, is increasingly realizable. Such a device would be extremely attractive for in-situ analysis in environmental, chemical or biological monitoring and remediation, offering the advantage of reduced analyte quantities and separation times, higher flow rate capabilities, low cost, increased precision and repeatability. At the time of writing, an ESI-MS microdevice for high performance liquid chromatography known as the HPLC-chip which is marketed by Agilent Technologies is commercially available. The HPLC-chip integrates the HPLC column with a sample enrichment column and an electrospray tip, which can then be mounted onto a mass spectrometer.

Basic Methodology

A review of DC electrospraying is given by Grace & Marijnissen [3]. It should be noted that the use of high frequency ($> 10\,\mathrm{kHz}$) AC electric fields gives rise to completely different drop dynamics and characteristics [4], the most important distinction perhaps being the larger $1-10\,\mu\mathrm{m}$ drops generated which are electroneutral. For the purposes of on-chip electrospray devices for analyte separation and detection, we will focus on the use of DC electrospraying henceforth as the AC electrospray has only recently been discovered and hence the use of AC fields for various applications and devices is currently work-in-progress (see, for example, [5]).

The most stable DC electrospray mode required for ionization is the cone-jet mode [3] described above and depicted in Fig. 1. The appearance of this characteristic conical meniscus and its stability has therefore been generally, and more likely than not, universally, adopted as the benchmark criterion for stable electrospray ionization. This stability is most commonly disrupted intermittently by gas bubbles aggregating into large slugs, thus temporarily causing cessation in the spraying. Once the slug is released, the spraying resumes. The formation of gas bubbles is a common problem in DC electrokinetics as a result of electrolytic reactions occurring to balance the charge induced by the applied voltage at the metal capillary, leading to a reduction in throughput and hence stable electrospray disruption due to the enormous capillary pressures. Joule heating and the generation of ionic contaminant as a result of Faradaic reactions at the electrodes are also additional problems accompanying the use of large DC voltages. Alternatively, stable electrospraying can also be disrupted by stray electric fields, mechanical perturbations (e. g., vibration) or flow variation.

The critical voltage V_c required for stable electrospraying can be estimated through a balance between the capillary stress, of order γ/R, where $R \sim 10^{-3} - 10^{-4}$ m is the principal curvature of the meniscus, of the same order as the radial capillary dimension, and the electric stress $\varepsilon_1 V^2/d^2$, where ε_1 is the liquid permittivity, V the applied voltage and d the electrode separation:

$$\frac{V_\mathrm{c}}{d} \sim \sqrt{\frac{\gamma}{\varepsilon_1 R}} \quad . \tag{2}$$

Typically, $\gamma \sim 10^{-2}\,\mathrm{kg/s^2}$, $d \sim 10^{-2}\,\mathrm{m}$ and $\varepsilon_\mathrm{l} \sim 10^{-10}\,\mathrm{C^2/(Jm)}$, thus suggesting that extremely large critical fields in excess of 1 kV are required.

Taylor, by considering a static balance between capillary and electric stresses, showed the existence of a conical meniscus with a half angle of 49.3° at equilibrium for a perfectly conducting liquid. In this limit, the meniscus behaves as a constant potential body and hence the field is external to the drop; the field lines intersect the interface orthogonally. The normal gas phase electric field E_n then scales as $1/\sqrt{R}$, and hence the normal electric stress $p_\mathrm{E} \sim E_\mathrm{n}^2$ scales as $1/R$. At every point R along the interface, the normal electric stress exactly balances the azimuthal capillary pressure $p_\mathrm{C} \sim \gamma/R$. This exact balance and absence of a specific length scale, is responsible for the formation of a static Taylor cone [6].

The perfectly conducting limit was later relaxed to allow for the effect of finite liquid conductivity [7]. In these cases in which the liquid meniscus is assumed to be sufficiently slender such that the longwave approximation can be assumed, the field that arises is predominantly in the liquid phase, tangential to the interface. Nevertheless, this tangential liquid phase electric field E_t also scales as $1/\sqrt{R}$ and thus an exact balance between the normal electric stress $p_\mathrm{E} \sim E_\mathrm{t}^2$ and the capillary stress $p_\mathrm{C} \sim \gamma/R$ again yields a stable equilibrium cone-like meniscus. The cone angle, however, depends crucially on the liquid to gas permittivity ratio $\varepsilon_\mathrm{l}/\varepsilon_\mathrm{m}$, wherein the Taylor angle is recovered in the perfectly conducting limit as $\varepsilon_\mathrm{l}/\varepsilon_\mathrm{m} \to \infty$ [6].

An alternative ionization mechanism to Dole's charge residue model (CRM) above has been proposed, in part to account for the inadequacy of CRM to account for the excess of analyte molecules over the observed charges in the electrospray flux. The CRM predicts that the relative number of drops for each species is proportional to the species relative concentration. The difficulty lies conceptually in the unlikely possibility for the successive drop subdivisions during the disintegration process to end up with the observation that all the daughter drops contained only a single analyte molecule for each of the ionizable species, especially in the presence of strong evaporation currents. Even if this were possible, a spectral peak for each species would always be obtained, which is not true. The alternative model, in contrast, proposes that the singly charged or multiply charged gas phase ions are generated by the evaporation of small, highly charged liquid drops of the analyte species [8].

On-Chip ESI-MS Interfacing

Progress in the development of on-chip electrospray interfaces for mass spectrometry has grown exponentially over the past two decades. Whilst there are many different designs and methods proposed, it is possible to summarize these developments in general into three broad categories based on the nature of the electrospray emitter type employed: Blunt edge, transfer capillary attachment, and, emitter tip. Early developmental work employed the blunt edge configuration. However, there appeared to be a subsequent parallel divergence thereafter, in which either the transfer capillary or the emitter tip interfaces were employed. Most of the recent on-chip electrospray interface designs therefore fall generally into either of these two latter categories.

On-chip ESI-MS devices were initially fabricated onto quartz or silica substrates. In addition to problems due to the hydrophobicity (discussed below), fabrication on glass is relatively labor-intensive. The shapes and dimensions available for patterning on glass are also limited. Silicon has also been commonly used because of its amenability to fabricating relatively small high aspect ratio features such as needle tip structures. In addition, semiconductor processing techniques such as deep reactive ion etching (DRIE) can be carried out for mass production of silicon chips [9]. However, silicon being semi-conducting has the disadvantage of current leakage.

Recently, the use of polymer-based substrates such as parylene, poly(dimethylsiloxane) or PDMS, polycarbonate (PC), polyimide (PI), poly(methylmethacrylate) or PMMA, poly(ethylene terephthalate) or PET, amongst others, has become increasingly attractive due to the availability of a wide range of plastics at low costs and the relatively simple and rapid microfabrication (rapid prototyping) techniques involved. The flexibility, superior optical properties and the ability to bond readily to glass after exposure to plasma of some plastics also make these materials attractive. Plastics, and glass for that matter, however, often have to be treated with hydrophobic surfactants to eliminate wetting and capillary ballooning at emitter tips. Other methods to avoid emitter tip wetting are discussed in the next section.

Electrospray tips from SU-8 photoepoxy have also been fabricated. Nevertheless, solvent resistance of polymer-based substrates is a critical issue, with poor resistance resulting in the swelling and distortion of the channels. A comparison between the performance of fused silica, parylene and borosilicate glass is discussed in Licklider et al. [10].

Blunt Edge Orifice

The first miniaturized on-chip electrosprays consisted of a planar glass microchip with 60 µm wide and 10 µm deep etched channels [11]. The open-end channel exit


mass spectrometer
sampling orifice
glass microchip with
parallel channels
sample dellvery
ESI electrodes
...
x-y-z-stage
high voltage power supply

On-Chip Electrospray, Figure 3 Schematic diagram representing the multichannel ESI-MS chip device in Xue et al. [12]. Each channel was connected to two reservoirs for sample injection and delivery. A syringe pump attached to the second reservoir of each channel was used to deliver the sample through the channels and electrodes were placed in one of each two buffer reservoirs to provide the electrical contact with the solution. The electrospray orifices consisted of the blunt edges of the open-ended channels. Reprinted with permission from [12]


Capillary (20um IDx 90um OD)
Stainles Steel Capillary
ESI voltage
Air
pressure
To MS
IONSpec
HiResESI FTICR
ESI tip
PMMA
Microchip
Capillary (20um IDx 90um OD)
fused silica capillary
(20 μm id, 60 μm od)
microchannel
(60 μm od)
microchannel
(20 μm od)

On-Chip Electrospray, Figure 4 On-chip ESI-MS device employing a fused silica transfer capillary. The electrical contact was established through a stainless steel capillary connected to the silica capillary using a poly(tetrafluoroethylene) sleeve. Another fused silica capillary connected to the other end of the stainless steel capillary was used as the electrospray emitter, as shown by the enlargement in the bottom image. Reprinted with permission from [16]


syringe for
spray liquid replacement
glass microdevice
sample
I
waste
BGE
II
III
liquid junktion
power supply
resistor
gas intake
restrictor
ESI capillary with tip
MS samling
orifice
ESI chamber
vacuum meter
seperation
channel
ESI tip
Liquid junktion
sample
waste
1 cm
I
II
III
electrospray
capillary
BGE
liquid junktion

On-Chip Electrospray, Figure 5 Schematic diagram (top) and image (bottom) of the ESI-MS device involving a transfer capillary and a subatmospheric liquid junction. Reprinted with permission from [17]

functioned as the electrospray orifice from which a Taylor cone was observed, thus avoiding the necessity of a dedicated electrospray tip. The coning and spraying is still possible as the electric field intensity at the exposed liquid surface was sufficiently high, above the critical value estimate given by Eq. (2). The blunt edge functioning as the electrospray orifice was formed by either breaking off the scored chip or by cutting the chip using a dicing saw. A similar but parallel multichannel electrospray microchip (Fig. 3) for increased throughput was also developed [12].

Whilst the blunt edge configuration is simple to fabricate, there were several challenges associated with such a design. The low currents associated with electrospraying are insufficient to generate electroosmotic flow (EOF) and hence required the flow to be pressure-driven. The absence of flow regulation however resulted in meniscus ballooning at the orifice which disrupted the electrospray stability and led to the formation of a dead volume; this dead volume introduces hydrodynamic dispersion and hence band broadening of the sample, reducing the efficacy of the separation. Even with application of ancillary electric potentials to drive the flow electroosmotically, the low EOF flow rate made regulation difficult. The electrical connection to the electrospray tip, established by insertion of a metal wire into the sample reservoir, also introduced flow perturbations which aggravated the problem of the lack of flow regulation.

In addition, the ballooning problem was intensified by the hydrophilic glass substrate. This was overcome by surface modification or applying a hydrophobic coating around the edges of the exit end. Nevertheless, this was only a partial remedy as it was possible that the corona discharge affected the chemical stability of the coating [13]. Alternatively, it is possible to bond a porous poly(tetrafluoroethylene) or PTFE membrane at the edge of the microchannel exit acting as the electrospray orifice. The hydrophobic membrane acts to constrain lateral dispersion of the liquid emanating from the orifice. The hydrophobic surface of such a membrane being consistently hydrophobic and hence the hydrophobicity can be easily controlled [14].

The ballooning problem was also addressed by attaching a pneumatic nebulizer and introducing an ancillary liquid (e. g., acetonitrile, methanol or 2-propanol) sheath flow downstream prior to the electrospray exit [15]. This was carried out by coupling an integrated nebulizer to a subatmospheric liquid junction. The role of the nebulizer gas (e. g., nitrogen) is four-fold, directly removing the ballooning meniscus and hence minimizing the dead volume, controlling the flow rate of the ancillary sheath flow, aiding in the evaporation of the electrosprayed drops, and, providing cooling to the sheath flow at high currents. The role of the sheath flow is two-fold, providing an electrical connection and reducing the ballooning effect and hence dead volume by constraining the flow of the sample. Sheath flow interfaces also enjoy the advantage of wide flexibility in analyte solution selection and enhanced reliability. However, a major drawback of sheath flows is the dilution of the sample and the introduction of background noise from the ancillary flow, both of which compromise the detection sensitivity. The position at which the nebulizer channel merges with the separation channel is however crucial. If this is too far from the exit, the gas pressure results in a back flow whereas non-merger of the channels will result in the failure of the gas flow to disperse the liquid at the exit [15].

Subsequent developments in the on-chip electrospray then involved using either a transfer capillary or a microfabricated emitter tip as a dedicated electrospray orifice in order to more efficiently address these problems.

Capillary Transfer Attachment

A transfer capillary to which a high voltage is applied can be attached to the edge of a microchannel to act as the electrospray interface. This allows the orifice to be smaller in dimension than that of the blunt edge, thus increasing the stability and hence the performance of the electrospray. In addition, the use of transfer capillaries, the majority constructed from quartz or fused silica, simplifies the construction of the device. Since the capillary is external to the microchannel and chip device, the ESI can be optimized externally. The transfer capillary can also be attached to different chip devices, extending its lifetime and eliminating contamination [13]. An example of the transfer capillary is shown in Fig. 4 in which a long 20 cm fused silica capillary affixed tightly with epoxy to one end to the microchannel was connected to a stainless steel capillary at its free end with a PTFE tube, which in turn, was connected using the PTFE tubing to an electrospray tip pulled from a fused silica capillary [16].



On-Chip Electrospray, Figure 6 Scanning electron microscopy images of an out-of-plane needle electrospray emitter tip fabricated at the bottom side of a liquid chamber etched into a silicon wafer. The view from the bottom is depicted in image (**a**) showing the 10 μm diameter needle protruding from the underside of the substrate. The view from the top of the substrate is depicted in image (**b**) showing the 600 μm liquid chamber. Reprinted with permission from [9]

The capillary attachment setup is, however, difficult to control and does not produce good reproducibility. To circumvent these issues, the transfer capillary can also incorporate the sheath flow and liquid junction components discussed above (Fig. 5) to provide the electrical connection, reduce the dead volume as well as to act as a buffer zone such that the separation is not affected by the nebulizer gas flow. Transfer capillaries however require time-consuming alignment and end-to-end butting; poor alignment reintroduces more dead volume instead, resulting in a reduction in the detection sensitivity and separation efficiency. Another deficiency associated with transfer capillary devices is the clogging of the capillary due to contaminants.



On-Chip Electrospray, Figure 7 Scanning electron microscopy image (**a**) and schematic plan and side views (**b**) of the nib-like in-plane electrospray emitter tip fabricated in SU-8 epoxy using double exposure lithography [21]. Reprinted with permission from [21]

Sheathless interfaces have also been developed to eliminate the dilution effect. To achieve a stable electrospray in the absence of nebulizer flow, the capillary tip is often tapered to provide a reduced orifice size. Electrical connection is provided either by applying a conductive coating (e. g., gold, carbon black or a conductive polymer) to the capillary tip, insertion of a wire electrode through a small opening drilled in the capillary wall or with an additional stainless steel capillary connected via a sleeve tubing shown in Fig. 4 [16]. The conductive layer coating is susceptible to damage due to corona discharge and deterioration due to friction. Moreover, these connections suffer the disadvantage of bubble generation due to electrolytic reactions at the electrode, which could disrupt the spraying and suppress the output signal. To avoid this, a Nafion® housing design was employed in a novel sheathless interface device which provides an escape route to relieve the flow of undesirable electrolytic products [18]. Nafion® is a conducting polymer which acts as a charge-selective salt bridge, thus permitting current penetration through the Nafion® membrane, which in itself has negligible polarization due to the small operating current. The external housing of the electrodes thus permits any gas bubbles to escape through the vent. In this same work, an efficient electroosmotic pump is also integrated into the device using silica monoliths, thus enhancing the stability of the electrospray.

Emitter Tips

Direct electrospraying via emitter tips, also known as nanoelectrospray or nanospray tips, were developed almost as a parallel technique to the transfer capillary interface in an attempt to address the problems associated with direct electrospraying using a blunt edge. The use of emitter tips has the advantage of parallelization in which multiple arrays of emitter tips (over 100 in number) can be fabricated very cheaply and attached onto a microchip, which makes them amenable to high throughput delivery [19]. In general, the development of such tips has taken two routes, namely, out-of-plane tips and in-plane tips. Early work on these emitter tips were almost always out-of-plane, in which the main flow direction and hence emitter is in a direction perpendicular to the device substrate. The first emitter tips comprised of a needle tip, about 50 µm at the large end and 5 µm at the emitting end, blunt cut to about 2 cm in length and glued on to the underside of the substrate at a drilled opening where it meets the bottom of the microchannel [20]. The next generation devices consisted of an integrated nozzle fabricated at the bottom of a liquid chamber, as shown in Fig. 6 [9]. Electrical connection was obtained through the use of a conductive coating or a conducting emitter. In another design, an array of 30 µm holes was machined into the substrate by laser ablation to function as emitters; the inherent taper of low demagnification factor laser etching processes naturally gives rise to conical orifices [19]. The surfaces of these holes were treated to increase the hydrophobicity.

In-plane emitter tips in which the tips are embedded at the end of the microchannel at the edge of the chip devices have been heralded mainly by recent advances in microfabrication technology by which low cost disposable chips are now close to reality. The smaller dimensions of these emitter tip devices were observed to produce more stable electrosprays over longer times. These emitter tip devices consist of an open capillary slot, connected at one end of the chip to a reservoir, which tapers in diameter at the emitting end to form a nib-like structure resembling that of a calligraphic pen, as illustrated in Fig. 7 [21]. This tapered tip is intentionally designed to minimize liquid spreading and to reduce the characteristic orifice length scale and hence the critical voltage required, as stipulated by Eq. (2). In this design, a platinum wire is inserted into the nib to establish the electrical connectivity and sample delivery was achieved using capillary infusion. A drawback of this design, however, is that a large reservoir is required due to evaporation from the open channel. A star-shaped chip device containing eight arms, each with a similar open channel and tip for sequential analysis via rotation of the chip has been built [22]. Other tip designs, e. g., groove structures, triangular tips, point tips and enclosed SU-8 tips have also been proposed. To reduce contamination, the insertion of a triangular parylene sheet between a bottom substrate and a top substrate incorporating the channel and tip has been suggested to confine the liquid at the outlet.

Future Directions for Research

Although a commercially on-chip device for ESI-MS is now available, there still remains several design problems related to enhancing electrospray stability, ionization efficiency, detection sensitivity, separation efficiency, speed, accuracy and spectra quality that need to be addressed. In addition, efforts need to be concentrated to minimize and eliminate sample loss and cross-contamination. Despite significant progress, there is still some way to go before a robust, optimized, cost-effective, high-throughput microdevice providing flexibility for coupling to different MS configurations can be realized. Whilst the high duty cycle of MALDI-MS enables large number of samples deposited on a single target plate, high throughput can only be achieved on chip based ESI-MS devices through the use of multiple channels or emitter tip arrays (see previous section), which themselves are limited by the allotted chip substrate area. The use of high voltage DC electric fields is also a critical safety issue for portable field deployment of miniaturized consumer devices. A possibility around this is to explore the feasibility of employing high frequency AC electric fields [4, 5].

Perhaps the main challenge, however, is the sequential or simultaneous handling of multiple streams (multiplexing) and the integration of multistep processes to allow analyte separation and detection onto a single microchip device [23]. Miniaturization and integration of the mass spectrometer onto the microchip is one goal; some advances have been achieved in scaling down ion trap and quadrupole mass analyzers although the complexity of the tandem mass spectrometer poses a significant challenge for its reduction to a chip-based system. The other goal is upstream miniaturization and complete integration of various other processes such as flow-through sampling, and, sample preparation and enrichment. Such a total analysis microsystem would require complete compatibility and connectivity between the various microfluidic components.

Cross References

- ► Interfacial Electrokinetic Flow
- ► Lab-on-Chip Devices for Chemical Analysis
- ► Lab-on-Chip Devices for Protein Analysis
- ► Mass Spectrometry
- ► Mass Spectrometry on-Chip Devices

References

1. Fenn JB, Mann M, Meng CK, Wong SF, Whitehouse CM (1989) Electrospray ionization for mass spectrometry of large biomolecules. Science 246:64–71
2. Gaskell SJ (1997) Electrospray: Principles and practice. J Mass Spectrom 32:677–688
3. Grace JM, Marijnissen JCM (1994) A review of liquid atomization by electrical means. J Aerosol Sci 25:1005–1019
4. Yeo LY, Lastochkin D, Wang S-C, Chang H-C (2004) A new ac electrospray mechanism by Maxwell-Wagner polarization and capillary resonance. Phys Rev Lett 92:133902
5. Yeo LY, Gagnon Z, Chang H-C (2005) AC electrospray biomaterials synthesis. Biomaterials 26:6122–6128
6. Yeo LY, Chang H-C (2006) High frequency AC electrosprays: Mechanisms and applications. Advances in Fluid Mechanics VI, Skiathos, Greece. WIT Press, Southampton
7. Stone HA, Lister JR, Brenner MP (1999) Drops with conical ends in electric and magnetic fields. Proc R Soc Lond A 455:329–347
8. Thomson BA, Iribarne JV (1979) Field induced ion evaporation from liquid surfaces at atmospheric pressure. J Chem Phys 71:4451–4463
9. Schultz GA, Corso TN, Prosse SJ, Zhang S (2000) A fully integrated monolithic microchip electrospray device for mass spectrometry. Anal Chem 72:4058–4063
10. Licklider L, Wang X-Q, Desai A, Tai Y-C, Lee TD (2000) A micromachined chip-based electrospray source for mass spectrometry. Anal Chem 72:367–375
11. Ramsey RS, Ramsey JM (1997) Generating electrospray from microchip devices using electroosmotic pumping. Anal Chem 69:1174–1178
12. Xue Q, Foret F, Dunayevskiy YM, Zavracky PM, McGruer NE, Karger BL (1997) Multichannel microchip electrospray mass spectrometry. Anal Chem 69:426–430
13. Sung W-C, Makamba H, Chen S-H (2005) Chip-based microfluidic devices coupled with electrospray ionization-mass spectrometry. Electrophoresis 26:1783–1791
14. Wang Y-X, Cooper JW, Lee CS, DeVoe DL (2004) Efficient electrospray ionization from polymer microchannels using integrated hydrophobic membranes. Lab Chip 4:363–367

15. Zhang B, Liu H, Karger BL, Foret F (1999) Microfabricated devices for capillary electrophoresis–electrospray mass spectrometry. Anal Chem 71:3258–3264
16. Meng Z, Qi S, Soper SA, Limbach PA (2001) Interfacing a polymer-based micromachined device to a nanoelectrospray ionization Fourier transform ion cyclotron resonance mass spectrometer. Anal Chem 73:1286–1291
17. Zhang B, Foret F, Karger BL (2000) A microdevice with integrated liquid junction for facile peptide and protein analysis by capillary electrophoresis/electrospray mass spectrometry. Anal Chem 72:1015–1022
18. Wang P, Chen Z, Chang H-C (2006) A new electro-osmotic pump based on silica monoliths. Sens Actuat B 113:500–509
19. Tang K, Lin Y, Matson DW, Kim T, Smith RD (2001) Generation of multiple electrosprays using microfabricated emitter arrays for improved mass spectrometric sensitivity. Anal Chem 73:1658–1663
20. Lazar IM, Ramsey RS, Sundberg S, Ramsey JM (1999) Subattomole-sensitivity microchip nanoelectrospray source with time-of-flight mass spectrometry detection. Anal Chem 71:3627–3631
21. Arscott S, Le Gac S, Druon C, Tabourier P, Rolando C (2004) A planar on-chip micro-nib interface for NanoESI-MS microfluidic applications. J Micromech Microeng 14:310–316
22. Yuan C-H, Shiea J (2001) Sequential electrospray analysis using sharp-tip channels fabricated on plastic chip. Anal Chem 73:1080–1083
23. Oleschuk RD, Jed Harrison D (2000) Analytical devices for mass spectrometry. Trends in Anal Chem 19:379–388

On-Chip Free-Flow Magnetophoresis

► Magnetophoresis

On-Chip Laboratory

► Lab-on-a-Chip Devices for Chemical Analysis

On Chip Light Confiners

► On Chip Waveguides

On Chip Light Guiding

► On Chip Waveguides

On Chip Light Propagator

► On Chip Waveguides

On-Chip Micro-Optical Detection

Holger Schmidt
University of California, Santa Cruz, CA, USA
hschmidt@soe.ucsc.edu

Synonyms

On-chip detection

Definition

On-chip micro-optical detection describes the collection of optical signals created in a micro- or nanofluidic device on the same chip. The wavelengths of the optical signals to be detected are typically in the visible or near-infrared part of the spectrum ranging from 0.4 to 2 µm. This sets the length scale for the detection elements and results in the use of micro-optical methods for on-chip detection. The detection process is an integral part of a fully integrated Lab-on-a-Chip and has to be optimized in the context of the entire chip. In this chapter, we will survey the most common approaches to on-chip micro-optical detection in the context of the complete integrated microfluidic system.

Overview

A large number of microfluidic devices with applications in analytical chemistry, biology, and biomedicine rely at least in part on optical methods for sample analysis. At the same time, the overarching goal for building microfluidic systems is to create miniaturized, portable, and self-contained Labs-on-a-Chip that perform all desired functions in as small a volume as possible. If optical analysis is to be part of the fluidic system, all optical components should be miniaturized as well. This situation is schematically depicted in Fig. 1a that shows the components of a Lab-on-a-Chip with focus on the optical parts. In general terms, light has to be brought in contact with liquid sample material. To this end, the outputs of light and fluid sources are guided via optical waveguides and fluidic channels, respectively, to an interaction region denoted by “I” where the sample analyte creates a characteristic optical signal, typically fluorescence, scattering, or absorption. This optical signal needs to be recorded by the detector, and to this end may pass additional functional optical elements such as filters, beam splitters, or gratings. Fig. 1b shows a recent example for an optofluidic chip that incorporates all these elements in a single device, resulting in almost complete integration [1]. In the remainder of this article, we will first give a brief overview of the optical components preceding the detector stage before focusing on proposed and currently implemented solutions for incorporating the detector with the microfluidic system to create a true optofluidic Lab-on-a-Chip.

Basic Methodology

Integrated Light Source

Due to the generally small amount of sample volume, optical analysis methods in microfluidic systems require only moderate to low amounts of optical power in the range from microwatts to milliwatts. These power levels can easily be achieved by incoherent sources such as light emitting diodes (LEDs). Coherent radiation as produced by a laser has, however, numerous advantages such as high spectral purity and long coherence lengths so that most studies are carried out with laser sources. The main challenge has been that the electronic properties of silicon cause it to be an extremely poor light emitter and preclude the realization of an electrically pumped laser built on a pure silicon platform. There are several ways around this limitation. Either a more efficient semiconductor material, typically alloys from III-V systems such as GaAs or InP or organic dyes that emit light in the desired wavelength range are used. Dye lasers have the advantage that they do not require a silicon-based substrate and that advanced laser structures such as single wavelength distributed feedback (DFB) lasers can be built [1, 2]. Current limitations to this technology include the need for an off-chip optical pump source for exciting the dye molecules and the additional fluidic infrastructure required to control the laser dye.



On-Chip Micro-Optical Detection, Figure 1 (**a**) Schematic layout of optical components in a fully integrated Lab-on-a-Chip (I: interaction region of light with fluidic sample material). (**b**) Photograph of state-of-the-art optofluidic chip with on-chip micro-optical detection (after [1])

Optofluidic Architectures

Once light is generated at the source location on the chip it needs to be guided to the interaction volume to excite the particles of interest. This light transport occurs in optical waveguides and leads to two fundamentally different approaches to the optofluidic device architecture. Light can be guided using conventional index guiding based on total internal reflection from the material surrounding the waveguide core. In this case, it interacts with the fluid either via the evanescent component of the light field that extends into the liquid surrounding the waveguide, or the waveguides are intersected by the fluidic channels and light is recollected after passing the liquid. This approach is represented in Fig. 2a which shows a layered optofluidic device in which microfluidic controls, microfluidic channels, and optical structures (sources, waveguides, sensors) are vertically separated from each other [3]. This architecture is particularly suited for hybrid material approaches where the optical layer is made of different materials (e. g. silicon based) than the fluidic layers (e. g. polymer based). In the second approach, both light and liquids are guided through the same physical fluidic channels. This appears difficult to achieve at first because the low refractive index of typical analyte liquids (around 1.3 to 1.4) precludes the use of conventional index guiding as used in silica fibers. In the context of chip-based integration, two methods to solve this problem have recently been developed. Liquid-core/liquid-cladding (L^2) waveguides are based on flowing two non-mixing liquids through the same channel. If the index of the innermost liquid is higher than that of the cladding liquid, regular index guiding is possible over millimeters of length [4] and additional functionalities such as optical switching can be added. Alternatively, light can be confined in the low-index liquid using dielectric multilayer confinement based on the antiresonant reflecting optical waveguide (ARROW) principle. In this case, light that is refracted out of the liquid is efficiently reflected back into the core by several layers of dielectric materials of appropriate thickness, typically silicon nitride (SiN) and oxide (SiO_2). This principle has been implemented on silicon platforms using wafer bonding for channels with $\sim 150\,\mu m$ diameter [5], and monolithic fabrication for channels with



On-Chip Micro-Optical Detection, Figure 2 (**a**) Three-layer architecture of optofluidic chip with separate fluidic and optical layers (after [3]). (**b**) Planar optofluidic architecture with integrated liquid-core ARROW waveguides (after [7]). Fluid and light (indicated by arrows) are guided through the central channel connecting fluidic reservoirs. Solid-core waveguides interface to the edges of the chip

5 – 15 μm diameter [6]. It has also been shown that the latter approach can be extended to designing 2D networks of hollow and solid core waveguides that allow for fully planar optical beam geometries as the light can be coupled in and out of the fluidic channels in different locations [7]. This scheme is shown schematically in Fig. 2b.

Integrated Optical Elements

When considering the on-chip optical detection process in a microfluidic device, it is not sufficient to consider the detector region alone. Most optical detection methods, in particular the most popular fluorescence detection schemes, require isolation of a weak generated signal from a much stronger excitation beam. In bulk systems, this separation is accomplished in the wavelength domain because the exciting and generated signals have different wavelengths. The most common wavelength selective optical elements are spectrometers, dichroic mirrors, and band-pass interference filters. If efficient on-chip detection is to occur, these elements need to be transferred to the optofluidic chip or alternative solutions need to be found.

The most versatile and sophisticated wavelength selective element is a spectrometer, and substantial efforts to develop integrated microspectrometers on a chip have been made [8]. A key figure of merit for the performance of a spectrometer is the spectral resolution $R = \lambda/\Delta\lambda$ which is defined as the ratio of wavelength λ and the 3 dB power bandwidth $\Delta\lambda$. High-performance grating spectrometers can reach spectral resolutions up to 10^6. Spectrometers work by spatially separating different wavelengths via the combination of a dispersive element and subsequent propagation. Several approaches have been taken to implement this concept on a chip. These include metal gratings and Fabry–Perot resonators as dispersive elements. Fabrication is done with MEMS-based silicon bulk micromachining which can cause compatibility problems for an optofluidic chip. All of these approaches suffer from the short separation path length on a small chip and no spectral resolutions higher than R∼15 have been achieved [8].

Perhaps a more promising approach for pre-detection signal conditioning is to emulate an interference filter on a chip. These filters are used to pass only fluorescence signals over a few to tens of nanometers while rejecting the excitation spectrum. Interference filters are characterized by the ratio of transmitted power at the excitation and detection wavelengths which is typically on the order of 10^5. It has been shown that the ARROW waveguide based optofluidic platform discussed above can be used as an interference filter [7]. The waveguiding efficiency of these structures depends both on wavelength and thickness of the dielectric cladding layers. If properly designed, the hollow channels in Fig. 2b can be designed to guide light efficiently at the detection wavelength while being extremely lossy at the excitation wavelength. This principle allows for implementation of the filter function without adding additional fabrication steps or chip area. Narrow-band wavelength transmission and subsequent separation can also be achieved with interference based integrated elements including microrings or Mach–Zehnder interferometers. There, the challenges lie mainly in minimizing optical losses that occur in curved structures.

Finally, an entirely different, filterless approach can be taken. In this case, the entire optical signal reaches the detector. Its wavelength dependence is recovered by applying different control voltages to the photodetector that result in different detection depths of the detector material [9]. The spectrum can then be reconstructed because the penetration of the optical signal into the detector is wavelength dependent. This approach has been implemented using standard 5 μm CMOS technology and was verified using DNA solution with SYBR-Green labeling. It may have limited use when a large dynamic range is required, i. e. when the excitation and generated signal differ strongly in intensity as is the case when low concentrations of analyte are to be detected.

Integrated Micro-Optical Detection

The optical detection process consists of turning light into an electrical signal that can be recorded, amplified, and stored for further processing and analysis. This signal conversion is carried out via the photoelectric effect in which photons generate mobile charge carriers, i. e. an electrical current. In bulk detection systems, this can be done using photomultiplier tubes (PMTs) or semiconductor photodetectors. In a PMT, the photons impinge on a metal cathode to release electrons that are subsequently amplified in a high voltage cascade. In a photodiode, light incident on a semiconductor transfers electrons to a different electronic state, creating both a positive (hole) and negative (electron) charge in the process that can contribute to electrical current. If this generation process occurs inside or in the vicinity of a p/n-junction – semiconductor regions that have mostly free holes/electrons, respectively – the generated electrons and holes are separated in an applied electric field and can be detected as a photocurrent. Both photodiodes and PMTs can be extremely sensitive and reach the single photon detection limit. Semiconductor detectors with this sensitivity are called avalanche photodetectors (APDs) that include an amplification process similar to PMTs after creation of the initial electron-hole pairs.

Semiconductor photodiodes are the natural choice for building an optofluidic device with integrated on-chip detection. The immediate consequence is that the chip has to be either entirely semiconductor based or be a hybrid system with soft material fluidic components and a solid-state detection layer as shown in Fig. 2a. The detectable wavelength range is determined by the semiconductor material properties. Silicon absorbs light with wavelengths shorter than 1.1 µm and is therefore a good choice for detection in the visible and near-infrared. Longer wavelengths, in particular 1.55 µm, can be reached using different absorbing layers such as InGaAs.

The main challenges for an on-chip detection system are to guide the light to the active detector area, couple as much light as possible into the detector, and find a system fabrication process that is compatible with producing the required photosensitive p/n junctions.

Figure 3 shows different approaches that have been taken to create the optical signal in on-chip semiconductor photodiodes. Common to all of these is the principle of coupling light from the waveguides (these could be any of the types discussed above) into a detector region that consists of different materials. All of these methods were first demonstrated in solid-state integrated optical devices without fluidic components. Fig. 3a shows lateral coupling, which is perhaps the most intuitive approach as the optical signal symbolized by the black arrows remains in the same plane during the coupling process. This concept was implemented using SiON waveguides and laterally structured p-i-n photodiodes yielding light coupling efficiencies on the order of 85% [10].



On-Chip Micro-Optical Detection, Figure 3 Overview of different approaches to on-chip micro-optical detection (details see text, WG: waveguide, C: cladding)

All other methods shown in Fig. 3 utilize vertical coupling and require a way to efficiently scatter light from the waveguide into an underlying photodiode. This scattering process is cumulative and the coupling efficiency increases with the length of the detector region. In Fig. 3b, the waveguide cladding is gradually tapered until being completely absent over the detector region. Without the cladding, the waveguide becomes leaky and light is scattered into the bottom detector. In Fig. 3c, the scattering process is accomplished by a surface grating, otherwise the principle is similar to Fig. 3b. Figs. 3d and 3e are examples for variations of the ARROW waveguiding principle described earlier to accomplish efficient coupling. In Fig. 3d, the thin gray dielectric layer that ensures light confinement in the guiding region is removed over the detector and the waveguide becomes leaky. Radiation is lost quickly through the bottom interface and collected by the detector. In Fig. 3e, the thickness of the ARROW confinement layer is altered above the detector. As mentioned earlier, the ARROW guiding effect depends on the layer thickness and can vary from being highly reflective (waveguiding) to highly transmissive (leaky).

The coupling efficiencies κ of approaches 3b, 3d, and 3e can be expressed analytically as

$$\kappa = 2.17\left(\frac{\lambda}{d_C}\right)^3\left[n_C\sqrt{n_S^2 - n_C^2}\right]^{-0.5}$$

[dB · λ/m] (tapered waveguide, Fig. 3b)

$$\kappa = 0.643\left(\frac{\lambda}{d_C}\right)^3\left[n_C\sqrt{n_S^2 - n_C^2}\right]^{-0.5}$$

[dB · λ/m] (ARROW 1, Fig. 3d)

$$\kappa = 0.879\left(\frac{\lambda}{d_C}\right)^3\left[n_C\sqrt{n_S^2 - n_C^2}\right]^{-0.5}$$

[dB · λ/m] (ARROW 2, Fig. 3e),

where λ is the optical wavelength, d_C is the effective waveguide core thickness, and n_C and n_S are the refractive indices of the core and substrate layers, respectively.

Typical values for the radiation loss for all three structures are in the range of 10 dB/cm for a 5 μm thick waveguide (index 1.46) coupled to silicon (index 3.85) and several hundreds dB/cm for a 1 μm thick core. It should be emphasized that the coupling efficiency can be substantially increased by adding an antireflection layer on top of the detector that ensures efficient transmission of the scattered light into the high index silicon detection region. Experimentally, coupling efficiencies of 85% within a detector length of only 300 μm have been observed [11].

Key Research Findings

The recent development of a Lab-on-a-Chip with integrated optical detection described by Balslev et al. illustrates the combination of the individual optical and fluidic components described in the previous sections and represents the state of the art for on-chip micro-optical detection in a larger fluidic system [1]. An image of the fluidic device was already presented in Fig. 1b. It is built on a p-type silicon substrate which also contains the electrical detection layer (photodiode). Light is guided in SU-8 waveguides surrounded by SiO_2 and PMMA resist cladding layers. Sealing of the channels is provided by a borofloat glass layer on top. The device also contains a fluidic dye laser with external optical pumping, and a fluid mixer. The sample analyte is contained in a cuvette that is horizontally intersected by the SU-8 waveguides. Coupling to the photodetector is accomplished by removing the SiO_2 layer above the detector, corresponding to the tapered waveguide configuration of Fig. 3b. The photodiodes are 50 μm wide and 2 mm long and optimized for detection at 600 nm with a 1 μm deep p/n junction. They exhibit good detection characteristics with a noise equivalent power (NEP) of 7×10^{-13} W (10 Hz bandwidth) and a sensitivity of 0.39 A/W at 580 nm. The device was used for an absorption measurement on xylenol orange dye, and sensitivity to different dye concentrations was demonstrated qualitatively. Note that due to the lack of a wavelength sensitive optical element, fluorescence detection is not feasible on this chip. Such an element could be added using the techniques discussed above, e. g. a microring or Mach–Zehnder interferometer section. Also, up to now no avalanche photodiodes have been integrated on a chip. These would be required for detection on the single molecule level. This work shows that while a fully integrated optofluidic Lab-on-a-Chip has not become reality yet, this goal is now within reach. In particular, the addition of on-chip micro-optical detection represents a key step along this way.

Future Directions for Research

The large payoff for developing completely self-contained micro- or optofluidic Labs-on-a-Chip will continue to drive future research on the optical components of the system, and new developments are bound to occur in all aspects. Integration of both the light source and detector on the chip will represent major breakthroughs along this road. Research on sources will focus on electrically pumped emitters that eliminate the need for off-chip optical pumps. Electrically pumped fluidic DFB lasers, silicon lasers or bonded light emitting diodes are all candidates for suitable sources. Fully planar optical approaches based on ARROW waveguides also hold a lot of promise as single molecule detection sensitivity on a chip has already been demonstrated [6], and the concept can be extended to adding wavelength filtering and efficient detector coupling with little additional effort. Future developments in the area of on-chip micro-optical detection will likely occur in incorporating ultrasensitive avalanche photodetectors (APD) and the required circuitry on the chip [12]. This requires the use of solid-state-only or hybrid silicon-plastic chip architectures and will allow for single molecule sensitivity on a fully self-contained chip. It was discussed that for most applications – in particular fluorescence detection and Raman spectroscopy – additional optical elements such as filters with high extinction ratio must be integrated on the chip along with the detector element itself to produce a useful signal. Finally, more developments on the back-end of the detection process in the areas of on-chip signal processing and data analysis using elaborate CMOS-based circuitry can be expected.

Cross References

- ► Detection using Confocal Microscopy
- ► Fluorescence Measurements
- ► Lab-on-a-Chip (General Philosophy)

- ► On-Chip Waveguide
- ► Optofluidics – Applications

References

1. Balslev S, Jorgensen AM, Bilenberg B, Morgensen KB, Snakenborg D, Geschke O, Kutter JP, Kristensen A (2006) Lab-on-a-chip with integrated optical transducers. Lab Chip 6:213–217
2. Li ZY, Zhang ZY, Emery T, Scherer A, Psaltis D (2006) Single mode optofluidic distributed feedback dye laser. Opt Express 14:696–701
3. Psaltis D, Quake SR, Yang C (2006) Developing optofluidic technology through the fusion of microfluidics and optics. Nature 442:381–386
4. Wolfe DB et al (2004) Dynamic control of liquid-core/liquid-cladding optical waveguides. PNAS 34:12434–12438
5. Campopiano S, Bernini R, Zeni L, Sarro PM (2004) Microfluidic sensor based on integrated optical hollow waveguide. Opt Lett 29:1894–1896
6. Yin D, Barber JP, Deamer DW, Hawkins AR, Schmidt H (2006) Single molecule sensitivity using planar integrated optics on a chip. Opt Lett 31:2136–2138
7. Schmidt H, Yin D, Barber JP, Hawkins AR (2005) Hollow-core waveguides and 2D waveguide arrays for integrated optics of gases and liquids. IEEE J Selected Top Quantum Elect 11:519–527
8. Wolfenbuttel RF (2004) State-of-the-art in integrated optical microspectrometers. IEEE Trans Inst Meas 53:197–202
9. Maruyama Y, Sawada K, Takao H, Ishida M (2006) A novel filterless fluorescence detection sensor for DNA analysis. IEEE Trans Elect Dev 53:553–558
10. Wunderlich S, Schmidt JP, Muller J (1992) Integration of SiON waveguides and photodiodes on silicon substrates. Appl Opt 31(21):4186–4189
11. Baba T, Kokubun Y (1990) High efficiency light coupling from antiresonant reflecting optical waveguide to integrated photodetector using an antireflective layer. Appl Opt 29(18):2781–2792
12. Niclass C, Rochas A, Besse PA, Popovic R, Charbon E (2006) A 4µs integration time imager based on CMOS single photon avalanche diode technology. Sens Actuators A 130–131:273–281

On Chip Waveguides

IAN PAPAUTSKY, ANDREA PAIS
Department of Electrical and Computer Engineering,
University of Cincinnati, Cincinnati, OH, USA
Ian.Papautsky@uc.edu

Synonyms

Integrated waveguides; Buried channel waveguides; On chip light guiding; On chip light propagator; Integrated light guiding; Integrated light propagator; Integrated light confiners; On chip light confiners

Definition

An *optical waveguide* is a structure that guides light waves. It traditionally consists of an inner core layer, a dielectric material with high permittivity and thus high refractive index, and an outer cladding layer, a material with lower refractive index than the core. Such a structure guides optical waves by total internal reflection. Waveguides that are integrated with microfluidic/Lab-on-a-Chip devices for the purpose of delivering excitation light and/or transmitting signal light to a detector are called *on-chip waveguides*.

Overview

A critical component for almost any miniaturized analytical device is perhaps the detection system. Among the possible detection methods and principles, optical detection is the most common in modern bio/chemical analysis. In particular, fluorescence is the most frequently used optical detection method in microfluidic systems. Fluorescence occurs when a fluorophore or quantum dot relaxes to its ground state after being excited. In biotechnology applications, for example, fluorophores or quantum dots can be used to label antibodies which tag molecules of interest in order to visualize their presence. Traditionally, this approach includes bulk optical equipment such as light sources, lenses, and microscope objectives, and requires precise mechanical alignment.

Waveguides can be integrated on-chip with microfluidic systems to improve optical detection. The general advantages of integrating waveguides on-chip are that microfluidic channels and optical elements can be aligned during fabrication, and that very compact devices can be created when light sources and detectors are integrated on-chip.

Waveguide Fundamentals

The key principle behind the waveguiding function of an optical waveguide is the phenomenon of *total internal reflection* [1, 2]. A light wave incident on an interface between two materials will refract and reflect, as schematically shown in Fig 1. Such behavior is described by Snell's law:

$$n_1 \sin\theta_1 = n_2 \sin\theta_2 \tag{1}$$

where θ are input and output angles with respect to the normal plane, and n are refractive indices of the two materials. Refractive index is a material property, defined by the ratio between the velocities of light traveling in vacuum and in the material. The refractive index of a solid material, a liquid, or a gas would thus be always greater than 1. Different



On Chip Waveguides, Figure 1 Behavior of a light wave incident on an interface with (**a**) $n_1 < n_2$ and (**b**) $n_1 > n_2$.

wavelengths of light travel at different speeds through the same material, thus index of refraction of a given material is dependant on the wavelength.

Eq. 1 offers insight into the properties of optical waveguides. When the reflected angle equals 90° (i. e., $\theta_2 = \frac{\pi}{2}$), $\sin\theta_2 = 1$, and Snell's law can be rewritten as:

$$\sin\theta_1 = \frac{n_2}{n_1} \tag{2}$$

Since the sin of a non-imaginary angle can never be greater than 1, the incidence medium must have a greater index of refraction than the transmission medium (i. e., $n_1 > n_2$) and

$$\theta_1 = \sin^{-1}\left(\frac{n_2}{n_1}\right) \tag{3}$$

At this incidence angle, there is no longer any light transmitted though the interface and the output light would travel along the interface boundary itself. However, if the medium of incidence has a lower refractive index than the transmission medium (i. e., $n_2 > n_1$), there is refraction (external reflection). In other words, *total internal reflection* occurs when $n_1 > n_2$.



On Chip Waveguides, Figure 2 Total internal reflection of light in a waveguide ($n_1 > n_2$). Light entering the waveguide core within the acceptance cone is guided, while light entering at a steep angle results in coupling losses

For waveguiding, the index of refraction of the core material must be grater than the index of refraction of the cladding material (Fig. 2) [1, 2]. Total internal reflection confines light in the optical waveguide core. The angle in Eq. 3 is called the angle of total internal reflection or the interface's *critical angle*. For visible light traveling from glass into air (or vacuum), the critical angle is approximately 41.5°. The critical angle for diamond is about 24.4°, which means that light is much more likely to be internally reflected within a diamond (diamonds for jewelry are cut to take advantage of this, achieving high total reflection of entering light).

A light beam propagating in waveguide core (internally) reflects off the core-cladding interface at an angle greater than the critical angle. A nearfield standing wave (called *evanescent wave*) propagates along the boundary and decays exponentially with increasing distance from the interface. Thus, as light is conducted along an on-chip waveguide, the transverse energy field extends past the waveguide core boundaries into the surrounding cladding layer.

Critical angle at the core-cladding interface at the front surface of a waveguide is the *acceptance angle*. If angle of the input light is larger than the acceptance angle, the incident light will not be totally internally reflected and will enter the cladding, causing losses (termed *coupling losses*). If the angle of the incident light is less than the acceptance angle, the light is guided.

The condition for total internal reflection at the core-cladding interface (Fig. 2) is given by:

$$n_1 \sin\left(\frac{\pi}{2} - \phi\right) \geq n_2 \tag{4}$$

Since the angle ϕ is related to the incident angle θ by equation

$$\sin\theta = n_1 \sin\phi \leq \sqrt{n_1^2 - n_2^2} \tag{5}$$

critical condition for total internal reflection is that:

$$\theta \leq \sin^{-1}\left(\sqrt{n_1^2 - n_2^2}\right) \equiv \theta_{\max} \qquad (6)$$

where $\theta_{\max}$ denotes the maximum light acceptance angle of the waveguide and is known as the numerical aperture (NA). The acceptance angle can then be approximated by

$$\theta_{\max} \approx \sqrt{n_1^2 - n_2^2} \qquad (7)$$

A typical refractive index difference between the core and cladding is on the order of 0.01 or greater.

Depending on the various possible patters of propagating or standing electromagnetic fields, optical waveguides are either *single-mode* or *multi-mode* [1, 2]. Each mode is characterized by its frequency, effective refractive index, polarization, power distribution, electric field strength, and magnetic field strength. A single mode waveguide has a narrow core, typically less than 20 µm in critical dimension. As its name suggests, it has only one mode of transmission. Single mode waveguides carry higher bandwidth than multi mode waveguides but require a light source with a narrow spectral width. Using a small core and single light-wave reduces signal attenuation and distortions from overlapping light pulses and increases transmission speeds. A multi mode waveguide has a core at least 50 µm in critical dimension (100 µm is typical). Since it has higher numerical aperture, it can support more than one propagation mode. Light waves are dispersed into numerous paths, or modes, as they travel through the waveguide's core.

In optical communications, long-distance transmissions are accomplished over cylindrical dielectric waveguides (optical fibers). For on-chip integration with planar microfluidic devices, *planar optical waveguides* in the form of films or strips are required. Planar waveguides confine light in one dimension and propagate it in any direction parallel to the surface. Such waveguides can be produced by simply depositing a thin film with a higher refractive index than the substrate, trapping light inside this film.

The boundary between the waveguide core and cladding may either be abrupt or gradual. Waveguides where the refractive index changes sharply or in discrete steps are called *step-index (SI)* optical waveguides, whereas those with a gradual transition in the refractive index are called *graded-index (GI)* optical waveguides. Figure 3a shows a typical three-layer SI planar waveguide formed by depositing a think layer of material with a higher refractive index on a substrate with a lower index. The third layer is either air or an additional lower-index cladding layer. Planar waveguides trap light in the direction of the film thickness, but allow light to spread in horizontally. To facilitate integration with microfluidic devices, 3D optical waveguides (or optical channel waveguides, Fig. 3b) that trap light in both vertical and transverse directions have been fabricated. Although waveguides come in various forms and with a variety of functions, optical waveguides that are uniform in the direction of propagation are the most basic type. Thus, the following discussion will be limited to optical waveguides in which material properties do not change in the direction of propagation.



On Chip Waveguides, Figure 3 Structures of (**a**) planar and (**b**) channel waveguides

Transmission Losses in Waveguides

Transmission loss (or attenuation) is an important characteristic of a waveguide. To measure *attenuation*, a cut back test is performed [1, 2]. Laser light is coupled into one end of a waveguide, and the other end is cut flat (e. g., with a razor blade) to allow light to exit directly to the photodetector. The waveguide length is progressively reduced (cut) and for each time the corresponding light intensity measurements are taken. Attenuation is then calculated as:

$$A = -10 \log\left(\frac{P_{\text{out}}}{P_{\text{in}}}\right) \qquad (8)$$

where A is the attenuation in dB, P_{in} is the power injected into the waveguide, and P_{out} is the power measured by the photodetector. Attenuation level of 3 dB means roughly half the power ($P_{\text{out}}/P_{\text{in}}$ approximately equal to a ratio of 1/1.995).

One of the main causes of attenuation is absorption of energy (or photons). Absorption is caused by atomic defects which result when the waveguide is exposed to radiation, *extrinsic* absorption by impurity atoms, and *intrinsic* absorption by constituent atoms of the material [1, 2]. The dominant mechanism is extrinsic absorption, primarily by metallic ions (iron, cobalt, etc.) and OH^- ions. In early glass optic fibers, transmission distance was primarily limited by absorption by OH^- ions. These ions were introduced in the material from the presence of water or water vapor during the manufacture process. Attenuation caused by this ion is greatest at 1400 nm, 950 nm, and 725 nm, leaving *windows* for transmission between these wavelengths. Today, the vapor phase axial deposition (VAD) manufacturing method tremendously reduces the OH^- concentration in fibers. However, for waveguides microfabricated on-chip, high OH^- content can still be problematic.

Losses in modern glass optic fibers are caused by ultraviolet absorption, infrared absorption, and scattering [1, 2]. The scattering losses, modeled by Rayleigh scattering, are caused by the interaction of the light wave with the constituent molecules which are on the order of the light wavelength. Rayleigh scattering loss is $1/\lambda^4$, so it can be reduced by increasing the wavelength. On the other hand, infrared absorption losses tend to increase with λ, and are usually the greatest at wavelengths above 1.5 µm.

Imperfections in the surface of the waveguide can also cause losses. Imperfections with dimensions of several wavelengths cause perturbation in the field, leading to coupling to higher order modes which do not have the desired transmission characteristics, and also causes power loss. Losses in modern commercial optic fibers can be kept down to as little as 0.01 dB/km, but for microfabricated waveguides losses in the order of 1 – 10 dB/cm for polymer and 0.1 – 1 dB/cm for glass cores are more common.

Basic Methodology

Overview

Generally, the motivation for integration of waveguides in microfluidic devices is to improve the detection, either by focusing the light in the channel to increase the excitation power for fluorescence measurements or by increasing the optical path length for absorbance detection. Further advantages are that optical and fluidic elements can be aligned during fabrication, reducing the number of interfaces and minimizing coupling losses, and that array of elements for multi-point/multi-analyte detection can be easily produced. In addition, on-chip waveguides can enable very compact devices when integrated with light sources and photodetectors.



On Chip Waveguides, Figure 4 Schematic illustrating typical placement of on-chip optical waveguides in a microfluidic system

On-chip optical waveguides are placed within the microfluidic system such that the waveguide is either perpendicular or alongside microchannels. In a typical setup, illustrated in Fig. 4, light from a light source (e. g., laser or Hg arc lamp) is coupled to on-chip (integrated) waveguides via optical fiber. After light traverses the microchannel, it is transmitted by another optical fiber to a photodetector.

Alternatively, microfluidic systems can be designed to take advantage of the evanescent field by immobilizing analyte-sensitive fluorescent dye on the surface of the on-chip waveguide. In this configuration, the evanescent energy field excites the dye molecules resulting in fluorescence emission, and this emitted energy is superimposed on the transmitted light signal. Thus, the emitted signal from the waveguide contains components of the residual excitation signal and the fluorescent emission. Using filtering, chemical effects on the immobilized dye resulting in a change in fluorescent emission intensity and output spectra can allow determination of specific interactions occurring on the waveguide surface. For the evanescent waveguide sensor to operate effectively, the waveguide must confine the light by total internal reflection while allowing transmission of a substantial portion (at least 80% for short waveguide structures) of the light at both excitation and emission frequencies [3].

On-chip waveguides can be fabricated from different types of core materials. Traditionally glass has been a popular choice, but recently polymers have gained popularity



On Chip Waveguides, Figure 5 Process flow for farbciation of glass core waveguides

due to lower costs and excellent transmittance characteristics [4]. Furthermore, polymeric waveguides can now be easily integrated with microfluidic devices, which are now commonly made in polymers.

Glass core waveguides

Glass (or silica) is very well suited as a core material because of its high optical transparency, the stability of silica glass, and its chemical robustness. Silica can be thermally grown on a silicon wafer or deposited by plasma enhanced chemical vapor deposition (PECVD) from the gas phase onto the silicon wafer. Deposition rates of 160 nm/min are typical for high quality films. Figure 5 illustrates a typical process flow. To form waveguides, a bottom cladding layer consisting of pure silica glass is first deposited on top of the substrate. A core layer is then deposited on top if the bottom cladding layer. To achieve light guiding by total internal reflection, the index of the core layer is adjusted to be 1.0 – 1.5 % higher than the surrounding cladding layers. This is achieved by doping the core layer with germanium and nitrogen during PECVD deposition. The core layer is patterned using photolithography and reaction ion etching (RIE). The entire structure is then covered by a cladding layer consisting of pure silica glass. Once waveguides have been fabricated, microchannels are fabricated by etching trenches in glass and bonding with another wafer. Most of such on-chip glass waveguides are single mode, with core thicknesses of 5 – 10 μm and cladding layer thickness of approximately 10 – 20 μm.

Polymer Core Waveguides

A common and simple approach to creating cladding around a polymer core is to sandwich it between two substrates. These substrates form cladding on top and bottom surfaces of the waveguide. Side cladding layers are formed by microchannels filled with air. This approach, schematically illustrated in Fig. 6, can be used to fabricate on-chip waveguides in a variety of polymers.

For a photosensitive polymer, the core is fabricated first directly on a cladding substrate. The second substrate is bonded directly on top of the polymer core (Fig 6a). The cladding is then formed by glass substrates on top and bottom, and air on both left and right sides of the waveguide. Photosensitive epoxy SU-8 (Microchem Corp.) has been growing in popularity as a core material for on-chip waveguides due to simplicity of fabrication. To fabricate waveguide core, SU-8 ($n = 1.59$ at $\lambda = 633$ nm) is simply spin-coated to a desired thickness and photolithographically patterned. Using this approach, single mode or multimode waveguides single to hundreds of micrometers in width and height can be fabricated, limited in height by SU-8 layer thickness and in width by photomask design. SU-8 waveguides, like many polymer waveguides, exhibit higher losses than those fabricated from glass. Nevertheless, unlike in optical waveguides for telecommunications, higher losses are not as problematic in on-chip waveguides for microfluidic Lab-on-a-Chip (LOC) sensing due to their short length.

For a non-photosensitive polymer, such as polydimethylsiloxane (PDMS, Sylgard 184, Dow Corning), a master is first fabricated in SU-8 by photolithography or in silicon by deep reactive ion etching (DRIE) (Fig. 6b). PDMS ($n = 1.41$ at $\lambda = 633$ nm) is then cast to form the core, followed by bonding of a cladding layer. The polymer structure is removed from the SU-8 master, and a second cladding layer is bonded. The resulting structure is schematically illustrated in Fig. 6c.

PDMS has many advantages over other core materials like SU-8 and glass. In addition to low cost, it has a very high light transmittance (> 95%) over a large frequency


Substrate
Photopattern
Substrate
Cladding
Substrate
Cladding
Air
Cladding
Cladding
b
Waveguide core
Polymer
Substrate
Photopattern
Substrate/cladding
Air
Cladding
Cladding
a
Waveguide core
glass or polymer
(n < 1.41)
Air
(n = 1.0)
PDMS
(n = 1.41)
Air
(n = 1.0)
glass or polymer
(n < 1.41)
c

On Chip Waveguides, Figure 6 Fabrication of polymer core waveguides using (**a**) photosensitive and (**b**) non-photosensitive materials. (**c**) Resulting waveguide cross-section structure

range. It is also biocompatible, robust, and has a rapid and repeatable mold fabrication process [5]. Even though SU-8 optical sensors designed for biochemical applications have been demonstrated successfully, the need for simpler and more biocompatible materials makes PDMS superior [6]. PDMS devices can be fabricated using soft lithography techniques [5], which do not require the use of a clean room.

Similar to glass core waveguides discussed earlier, buried waveguides can also be fabricated in polymers (Fig. 7). In this case, two different polymers with appropriate refractive indexes must be used. For example, an on-chip waveguide can be fabricated using a SU-8 core and PDMS cladding ($n_{\mathrm{SU-8}} = 1.59$ vs. $n_{\mathrm{PDMS}} = 1.41$ at $\lambda = 633$ nm). Alternatively, if using the same polymer for both core and cladding, differences in refractive index must be induced. For instance, curing PDMS at room temperature yields a slightly lower refractive index than curing at 150 °C ($n_{150\,°\mathrm{C}} = 1.47$ vs. $n_{25\,°\mathrm{C}} = 1.45$ at $\lambda = 460$ nm) [7].

Liquid Core Waveguides

As an alternative to the traditional buried channel waveguides, liquid core waveguides can be formed using microfluidic channels. In this case, microfluidic channel walls serve as cladding. By flowing liquid of higher refractive index than the microchannel material, light can be guided within the core. Liquid waveguides can also be composed of a liquid core and a liquid cladding (L^2 waveguides) [8, 9]. By selecting the inner core liquid to be of higher refractive index than the refractive index of



On Chip Waveguides, Figure 7 Fabrication of polymer core waveguides using two polymer materials

the surrounding media, light can be confined to the inner core. In these waveguides, the direction of light propagation can be easily altered by altering the differential flow rates for the liquids to steer the inner core liquid.

Key Research Findings

Mogensen et al. reported microfluidic devices for capillary electrophoresis (CE) and electrochromatography (CEC) with glass on-chip waveguides for optical detection [10]. The devices were fabricated from silicon substrates by DRIE and subsequent oxidation to form optical and microfluidic structures. Figure 8 illustrates the CEC device and shows a cross-section of an optical waveguide fabricated by oxidizing a thin lane of silicon, leaving a 22 μm wide stripe of pure SiO_2. The two air channels on both sides of the SiO_2 core constitute the lower refractive index regions of the waveguide. The depth of the air channels was ∼100 μm, which was also the depth of the microfluidic network. PDMS was used as the top cladding layer of the waveguide, due to its low refractive index and the need to seal the microfluidic channels. Light was not confined in the bottom part of the waveguide, which is a limitation of this approach (although the bottom footprint of the waveguide is small compared to the rest of the structure). Figure 8c shows the measured transmission losses for the waveguide. The propagation loss increased from about 0.2 dB/cm at 800 nm to about 0.8 dB/cm at 250 nm, which was attributed to surface scattering at the glass-air interface due to the waveguide sidewall roughness [10]. This kind of wavelength dependence is expected, since scattering generally is more pronounced at shorter wavelengths [1].

Polymers have been gaining popularity in on-chip waveguide fabrication as core and cladding materials. The use of polymers for on-chip waveguides often makes fabrication of a polymer microfluidic system substantially simpler, as both microfluidic and optical components can be fabricated in a single step. For example, Fleger et al. [11] developed a polymer microfluidic chip for capillary electrophoresis with multimode polymer waveguides for optical analytical applications. The microchannels 50 μm in width and 60 μm in depth were fabricated in polymethylmethacrylate (PMMA) using hot embossing. The on-chip waveguides were formed by fabricating 80 μm wide and 60 μm deep waveguide channels in the PMMA substrate (at the time of the microfluidic channel fabrication) and filling them with core material (NOA72, Norland Optical). NOA72 is a highly transparent UV curing adhesive, with low viscosity and good wetting of PMMA. The refractive index of NOA72 is $n = 1.56$ and is suitable as a core material inside PMMA ($n = 1.49$) cladding. Figure 9 shows top view and cross-section of the microfluidic channel and polymer waveguides. The transmission spectrum measured with a cooled photomultiplier (Fig. 9c) proves the suitability of the devices for optical detection in the range 440–800 nm, with a propagation loss of only 1 dB/cm [11].

Fleger et al. [12] also described a PDMS microfluidic chip for capillary electrophoresis with integrated waveguides for optical detection (Fig. 10). The waveguide core was composed of a special formulation of polysiloxane ($n = 1.43$ at $\lambda = 633$ nm). The waveguide cladding was formed by PDMS ($n = 1.41$ at $\lambda = 633$ nm) and air. Dimensions of the microfluidic channel and the waveguide channels were $70 \times 70\ \mu m^2$; distance between the microfluidic channel and the waveguides was 50 μm. Optical loss in the whole system at $\lambda = 633$ nm was approximately 1.27 dB, which included propagation loss in the 25 mm waveguides and coupling losses between the waveguides and the microfluidic channel.

Buried on-chip waveguides using the same polymer for both core and cladding can also be fabricated. Chang-Yen et al. demonstrated a method of fabricating a monolithic PDMS waveguide system using soft lithography [7]. An SU-8 master was first prepared to define waveguide core, and PDMS was cast and allowed to flow into the pattern. The excess PDMS that did not fill the SU-8 pattern was carefully removed using a razor blade. PDMS was cured



On Chip Waveguides, Figure 8 Microfluidic CEC device with on-chip waveguides for optical detection. (**a**) Scanning electron micrograph of the detection region. (**b**) SiO_2 stripe that forms the on-chip waveguide. (**c**) Propagation loss between 200 and 860 nm. From [10]



On Chip Waveguides, Figure 9 PMMA capillary electrophoresis chip with on-chip waveguides for optical detection. (**a**) Top view of the optical detection site illustrating the microfluidic channel and polymer waveguides (additional two waveguides were added for designed for specialized fluorescence measurements). (**b**) Cross-section of the microfluidic channel and polymer waveguides. (**c**) Attenuation spectrum of on-chip polymer waveguides, which includes propagation losses due to coupling between the waveguides and the microfluidic channel. From [11]

at 150 °C for 60 min, which yielded the waveguide core with $n = 1.47$ at $\lambda = 460$ nm. The baked layer was then cooled to room temperature and more PDMS was poured over it. The entire wafer was allowed to cure at room temperature to a refractive index of 1.45 (at $\lambda = 460$ nm), forming the cladding layer. A change of 0.02 in refractive index was sufficient for waveguiding. The cutback procedure was used to measure the attenuation of the waveguide demonstrated a loss of approximately 0.40 dB/cm at $\lambda = 460$ nm [7].



On Chip Waveguides, Figure 10 (**a**) PDMS capillary electrophoresis chip with on-chip waveguides. (**b**) Top view of the optical detection site, illustrating the microfluidic channel and waveguides. (**c**) On-chip waveguide cross-section. From [12]

Alternatively, photosensitive epoxy SU-8 can be used as both the core and cladding layer. The refractive index of SU-8 can be reduced by mixing it with at least 2.7% (by weight) liquid aliphatic epoxy resin DER 353TM from Dow Plastics [13]. The SU-8/aliphatic resin mixture was measured to have $n = 1.590$ at $\lambda = 633$ nm, as opposed to $n = 1.595$ for the un-modified SU-8. The aromatic groups from the aliphatic resin are absorbed in the SU-8 polymeric mesh, inhibiting high cross-linking of the SU-8. Therefore, the refractive index of the blend was lower than the pure SU-8 epoxy. The fabrication process consisted of three successive photolithographic steps to deposit sub-cladding (lower RI), core (higher RI) and top-cladding (lower RI) layers. Both cladding layers had microfluidic channels patterned in them.

Future Directions for Research

Fabrication of waveguides on-chip is important in microfluidic devices, since optical detection is used for many applications. While microfluidics has made it possible to integrate many fluidic casts on a single chip, most optical components such as light sources and sensors remain off-chip. On-chip waveguides provide an interface between these off-chip optical components and on-chip microfluidics. With the drive towards portable microfluidic systems for point-of-care diagnostics or on-site analysis, it is highly desirable to integrate these components on-chip with minimal coupling and transmission losses. This becomes especially important as limits of detection of miniaturized analytical systems improve and analyte concentrations decrease, resulting in ever smaller optical signals.

Cross References

- ► Evanescent-Wave Sensing
- ► Fluorescence Measurements
- ► Microfluidic Optical Devices
- ► Micromolding
- ► On-Chip Micro-Optical Detection
- ► Thick Resist Lithography
- ► Soft Photolithography

References

1. Saleh BEA, Teich MC (1991) Fundamentals of Photonics. Wiley, New York
2. Kasap SO (2001) Optoelectronics and Photonics: Principles and Practices. Prentice Hall, Old Tappan, NJ
3. Chang-Yen DA, Gale BK (2003) An integrated optical oxygen sensor fabricated using rapid-prototyping techniques. Lab Chip 3:297–301
4. Ma H, Jen AKY, Dalton LR (2002) Polymer-based optical waveguides: materials, processing and devices. Adv Mater 14:1339–1365
5. Sia SK, Whitesides GM (2003) Electrophoresis 24:3563–3576
6. Mogensen KB, El-Ali J, Wolff A, Cutter JP (2003) Integration of polymer waveguides for optical detection in microfabricated chemical analysis systems. Appl Opt 42:4072–4079
7. Chang-Yen DA, Gale BK (2005) A monolithic PDMS waveguide system fabricated using soft-lithography techniques. J Lightwave Technol 23:2088–2093

8. Psaltis D, Quake SR, Yang C (2006) Developing optofluidic technology through the fusion of microfluidics and optics. Nature 442:381–386
9. Wolfe DB, Conroy RS, Garstecki P, Mayers BT, Fischbach MA, Paul KE, Prentiss M, Whitesides GM (2004) Dynamic control of liquid-core/liquid-cladding optical waveguides. PNAS 101:12434–12438
10. Mogensen KB, Eriksson F, Gustafsson O, Nikolajsen RPH, Kutter JP (2004) Pure-silica optical waveguides, fiber couplers, and high-aspect ratio submicrometer channels for electrokinetic separation devices. Electrophoresis 25:3788–3795
11. Fleger M, Siepe D, Neyer A (2004) Microfabricated polymer analysis chip for optical detection. Proc Nanobiotechnol 151:159–161
12. Fleger M, Neyer A (2006) PDMS microfluidic chip with integrated waveguides for optical detection. Microelec Eng 83:1291–1293
13. Ruano-Lopez JM, Aguirregabiria M, Tijero M, Arroyo MT, Elizalde J, Berganzo J, Aranburu I, Blanco FJ, Mayora K (2005) A new SU-8 process to integrate buried waveguides and sealed microchannels for a Lab-on-a-Chip. Sens Actuators B 114:542–551

Optical Coherence Imaging

► Optical Coherence Tomography and Optical Doppler Tomography

Optical Coherence Tomography and Optical Doppler Tomography

ZHONGPING CHEN
Department of Biomedical Engineering, University of California, Irvine, CA, USA
z2chen@uci.edu

Synonyms

Optical Doppler tomography (ODT); Doppler OCT; Optical coherence imaging; Optical Doppler velocimetry

Definition

Optical coherence tomography (OCT) is an interferometric, non-invasive, non-contact optical tomographic imaging modality based on coherence-domain optical technology [1–6]. OCT uses the short coherence length of a broadband light source to perform cross-sectional imaging with micrometer-scale axial and lateral resolutions. Optical Doppler tomography (ODT), also named Doppler OCT, combines the Doppler principle with OCT to obtain simultaneously high resolution tomographic images of structure and flow velocity of scattering samples [7, 8].

Overview and Basic Methodology

Optical Coherence Tomography

OCT is a recently developed interferometric imaging modality that uses short coherence length of broadband light sources to perform micrometer-scale, cross-sectional imaging of biological tissue and other sample. Variations in sample scattering due to inhomogeneities in the optical index of refraction provide imaging contrast. OCT is analogous to ultrasound imaging except that it uses light instead of sound wave. The short coherence length of the broadband light source makes it possible to achieve spatial resolution one or two orders of magnitude better than what can be achieved with ultrasound. OCT was initially developed for imaging biological tissue for medical applications [2]. Since then, OCT has been used for imaging and quantifying biomaterials, microchannels, and nanostructures [3, 5, 8].

There are two basic implementations of OCT, time domain OCT (TD-OCT) and Fourier domain OCT (FD-OCT). TD-OCT is based on a Michelson interferometer with a broadband light source (Fig. 1). Light from a broadband partial coherent source is incident on the beam splitter and splits equally between reference and target arms of the interferometer. Light backscattered from the turbid sample recombines with light reflected from the reference arm and forms interference fringes. High axial spatial resolution is possible because interference fringes are observed only when the pathlength differences between the sample arm and reference arm are within the coherence length of the source. Axial scans are performed by scanning the reference arm, and lateral scans are performed by scanning the sample beam. A two-dimensional, cross-sectional image is formed by performing an axial scan followed by a lateral scan. Axial resolution is determined by the coherence length of the source, and lateral resolution is determined by the numerical aperture of the focusing lens [1–6].

Fourier domain OCT measures interference fringes in the spectral separated domain either by a spectrometer with a high speed line-scan camera (Fig. 2) or a swept laser source based system that uses a single detector [3, 6, 8]. Modulation of the interference fringe intensity in the spectral domain is used to determine the location of all scattering objects along the beam propagation direction by a Fourier transformation without scanning of the reference arm. FD-OCT has the advantages of high sensitivity and fast imaging speed. The significant increase in imaging speed and sensitivity of FD-OCT makes it possible to acquire three-dimensional OCT images with high spatial resolution.

An example of OCT applications in microfluidics is the investigation of Laminar dispersion in a serpentine


Broadband Partially Coherent Source
Phase Modulator
Optical Delay Line
Reference Arm
Axial Scan
A/D Converter & Digital Signal Processing
2x2 coupler
Sample Arm
Lateral Scan
Photodiode
Sample

Optical Coherence Tomography and Optical Doppler Tomography, Figure 1 Schematic of a time domain OCT system consisting of a fiber-based Michelson interferometer with a partially coherent light source


Broadband Partially Coherent Source
Reference Arm
Reference Mirror
Optical spectrometer
2x2 coupler
Sample Arm
Lateral Scan
CCD or linear array detector
Signal processing and display
Sample

Optical Coherence Tomography and Optical Doppler Tomography, Figure 2 Schematic of a spectrometer based Fourier domain OCT system


Water/Particle Mixture
Water/Particle Mixture
4.5 mm
R: 1.7 mm
y
x
z
Y
Y
6 mm
Fluids out
Z

Optical Coherence Tomography and Optical Doppler Tomography, Figure 3 Picture and schematic of a meandering square micro-channel made of cyclo-olefin copolymer. It has a Y branch at the beginning and the dimension of cross-section between confluence and outlet is 600 μm × 600 μm. The radius of curvature *R* is 1.7 mm. The red dotted line indicates area of interest



Optical Coherence Tomography and Optical Doppler Tomography, Figure 4 OCT images of transient two-fluid mixing in a meandering square micro-channel as shown in Fig. 3. Initially, the entire channel was filled with a particle/water mixture, and the dual syringe pump (one with the particle/water mixture, and the other with water only) was turned off. As soon as the pump was turned on with a programmed flow rate, OCT images were acquired at 1 frame per second. When the initial mixing was stabilized and reached a dynamic steady state, the pump was turned off again. At the dynamic steady state, sedimentation was observed macroscopically. Stratification between the water and particle/water mixture was developed, and a clear interface was observed in the transverse plane. Secondary flow at the dynamic steady state is clearly visible. Finally, the concentration reached a static steady state where scattering particles occupied the lower half cross-section which resulted from sedimentation

microchannel with a Y-shape inlet (Fig. 3). Transient two-fluid mixing in microfluidic devices can be clearly observed (Fig. 4) [9].

Optical Doppler Tomography

ODT combines the Doppler principle with OCT to obtain high-resolution tomographic images of static and moving constituents simultaneously in scattering samples [5, 8, 10, 11]. When light backscattered from a moving particle interferes with the reference beam, a Doppler frequency shift f_D occurs in the interference fringe:

$$f_D = \frac{1}{2\pi}(\boldsymbol{k}_s - \boldsymbol{k}_i) \bullet \boldsymbol{v}\,, \tag{1}$$

where $\boldsymbol{k}_i$ and $\boldsymbol{k}_s$ are wave vectors of incoming and scattered light, respectively, and $\boldsymbol{v}$ is the velocity vector of the moving particle (Fig. 5). Since ODT measures the backscattered light, assuming the angle between flow and sampling beam is θ, the Doppler shift equation is simplified to:

$$f_D = \frac{2V\cos\theta}{\lambda_0}\,, \tag{2}$$

where λ_0 is the vacuum center wavelength of the light source. Therefore, measurement of Doppler shift of the backscattered light allows quantification of flow velocity of scattering particles.



Optical Coherence Tomography and Optical Doppler Tomography, Figure 5 Schematic of flow direction and probe beam angle in ODT

The optical system of ODT is similar to that of OCT. The primary difference is in signal processing. The first two-dimensional in vivo ODT imaging was reported using the spectrogram method [10, 11]. The spectrogram method uses a short time fast Fourier transformation or wavelet transformation to determine the power spectrum of the measured fringe signal [10, 11]. Although spectrogram methods allow simultaneous imaging of in vivo tissue structure and flow velocity, the velocity sensitivity is limited for high-speed imaging. Phase-resolved Doppler OCT was developed to overcome these limitations [12]. This method uses the phase change between sequential A-line scans for velocity image reconstruction [8, 12]. Phase-resolved Doppler OCT decouples spatial resolution and velocity sensitivity in flow images and increases imaging speed by more than two orders of magnitude without compromising spatial resolution and velocity sensitivity [8, 12]. In phase resolved ODT, the phase information of the fringe signal can be determined from the complex analytical signal $\tilde{\Gamma}(t)$, which is determined through analytic continuation of the measured interference fringe function, $\Gamma(t)$, using a Hilbert transformation [8]:

$$\tilde{\Gamma}(t) = \Gamma(t) + \frac{\mathrm{i}}{\pi} P \int_{-\infty}^{\infty} \frac{\Gamma(\tau)}{\tau - t} \mathrm{d}\tau = A(t)\mathrm{e}^{\mathrm{i}\phi(t)}\,, \tag{3}$$

where P denotes the Cauchy principle value, i is the complex number, and $A(t)$ and $\phi(t)$ are amplitude and phase term of $\tilde{\Gamma}(t)$, respectively. Because the interference signal $\Gamma(t)$ is quasi-monochromatic, the complex analytical signal can be determined by:

$$\tilde{\Gamma}(t) = 2 \int_0^{\infty} \int_0^{\tau} \Gamma\left(t'\right) \exp\left(-2\pi \mathrm{i} \nu t'\right) \mathrm{d}t' \exp\left(2\pi \mathrm{i} \nu t\right) \mathrm{d}\boldsymbol{\nu}\,, \tag{4}$$

where τ is the time duration of the fringe signal in each axial scan.

The Doppler frequency shift f_n at nth pixel in the axial direction can be determined from the average phase shift between sequential A-scans. This can be accomplished by calculating the phase change of sequential scans from the individual analytical fringe signal [8]:

$$\begin{aligned} f_n &= \frac{\Delta\phi}{2\pi T} \\ &= \frac{1}{2\pi T} \sum_{m=(n-1)M}^{nM} \sum_{j=1}^{N} \left[\tan^{-1}\left(\frac{\operatorname{Im}\tilde{\Gamma}_{j+1}(t_m)}{\operatorname{Re}\tilde{\Gamma}_{j+1}(t_m)} \right) \right. \\ &\qquad \left. - \tan^{-1}\left(\frac{\operatorname{Im}\tilde{\Gamma}_{j}(t_m)}{\operatorname{Re}\tilde{\Gamma}_{j}(t_m)} \right) \right]. \end{aligned} \tag{5}$$

Alternatively, the phase change can also be calculated by the cross-correlation method [8]:

$$f_n = \frac{1}{2\pi T} \tan^{-1}\left(\frac{\operatorname{Im}\left[\sum\limits_{m=(n-1)M}^{nM} \sum\limits_{j=1}^{N} \tilde{\Gamma}_j(t_m)\tilde{\Gamma}^*_{j+1}(t_m) \right]}{\operatorname{Re}\left[\sum\limits_{m=(n-1)M}^{nM} \sum\limits_{j=1}^{N} \tilde{\Gamma}_j(t_m)\tilde{\Gamma}^*_{j+1}(t_m) \right]} \right). \tag{6}$$

where $\tilde{\Gamma}_j(t_m)$ and $\tilde{\Gamma}^*_j(t_m)$ are the complex signals at axial time t_m corresponding to the jth A-scan and its respective conjugate; $\tilde{\Gamma}_{j+1}(t_m)$ and $\tilde{\Gamma}^*_{j+1}(t_m)$ are the complex signals at axial time t_m corresponding to the next A-scan and its respective conjugate; M is an even number that denotes the window size in the axial direction for each pixel; N is the number of sequential scans used to calculate the cross correlation; and T is the time duration between A-scans. Because T is much longer than the pixel time window within each scan used in the spectrogram method, high velocity sensitivity can be achieved.

In addition to the local velocity information, the standard deviation of the Doppler spectrum gives the variance of local velocity and can be determined from the measured analytical fringe signal [8]:

$$\begin{aligned} \sigma^2 &= \frac{1}{(2\pi T)^2} \\ &\times \left(1 - \frac{\left| \sum\limits_{m=(n-1)M}^{nM} \sum\limits_{j=1}^{N} \tilde{\Gamma}_j(t_m)\tilde{\Gamma}^*_{j+1}(t_m) \right|}{\frac{1}{2} \sum\limits_{m=(n-1)M}^{nM} \sum\limits_{j=1}^{N} \left[\tilde{\Gamma}_j(t_m)\tilde{\Gamma}^*_j(t_m) + \tilde{\Gamma}_{j+1}(t_m)\tilde{\Gamma}^*_{j+1}(t_m) \right]} \right), \end{aligned} \tag{7}$$

The σ value depends on the flow velocity distribution. Variations in flow velocity will broaden the Doppler frequency spectrum and result in a large σ value. Thus, the Doppler variance image can be an indicator of flow variations and can be used to study flow turbulences. In addition, standard deviation imaging can also be used to determine the transverse flow velocity [8].

The significant increase in velocity sensitivity of phase resolved ODT makes it possible to image in vivo tissue microcirculation. Recently, the development of FD-OCT has significantly increased imaging speed and sensitivity. Combination of FD-OCT with the phase-resolved method has been demonstrated by a number of groups [8]. Because the dynamic range of the phase-resolved ODT depends on the speed of the line scans, Fourier domain ODT has an advantage over the time domain method in terms of imaging speed and velocity dynamic range [8].

ODT can provide cross-sectional imaging of channel geometry and flow velocity simultaneously. It has been used to measure osmotic mobility, quantify size of the scattering particle, and study flow dynamics of microfluidic devices of different materials, geometry, junction, and surface treatment [8, 13]. ODT has also been used to image and quantify two-phase flow and flow mixing [8, 9, 14, 15]. An example of ODT applications to simultaneously image and quantify the secondary flow and mixing pattern in microchannels is shown in Fig. 6 [15]. Aqueous suspension of polystyrene beads with a diameter of 0.2 μm and concentration of 20.5 mg/cc was injected into both inlets of the Y branch device of a meandering microchannel with a square cross section as shown in Fig. 3. The probe beam of the FD-ODT was adjusted to be approximately perpendicular to the plane of the microchannel (x-y plane). Because primary flow is in the x-y plane and the probe beam is in the z direction, ODT is not sensitive to the primary flow in such a probe configuration. Consequently, only the secondary flow will contribute to the Doppler signal. The z-component of the secondary flow velocity $V_z(x, y, z)$ was imaged and quantified with FD-ODT. Fig. 6i–m shows cross-sectional mapping of secondary flow velocity $V_z(x, z)$ in the x-z plane at different y positions as indicated. The velocity field at x-z plane shows a pair of counter rotating vortices. Since the curvature is alternating, the rotational direction of the vortices is also alternating as shown by comparing Fig. 6i–m. Figure 6n–p shows cross sectional mapping of secondary flow velocity $V_z(x, y)$ at different z positions. Alternating flow direction of the secondary flow at different depth in the x-y plane can be clearly visualized. The inset in Fig. 6o is a cross-sectional mapping of secondary flow velocity $V_z(y, z)$ in the y-z plane at the center of the channel as indicated by the white line. The velocity field at the y-z plane shows a pair of counter rotating vortices. This result clearly demonstrates that ODT can be used to image and quantify secondary flow [15].



Optical Coherence Tomography and Optical Doppler Tomography, Figure 6 ODT images of secondary flow in a meandering square micro-channel as shown in Fig. 3. The measured z components of the flow velocity $V_Z(x, y, z)$ in the area of interest was projected into different cross-sectional planes, where the z axis is perpendicular to the micro channel plane (x-y plane) and along the direction of the ODT probe beam. (**i**)–(**m**): cross-sectional mapping of secondary flow velocity $V_Z(x, z)$ at different y positions. (**n**)–(**p**): cross-sectional mapping of secondary flow velocity $V_Z(x, y)$ at different z positions (depth). Inset (**o**) is a cross-sectional mapping of secondary flow velocity $V_Z(y, z)$ at the center of the channel as indicated by the white line

Future Directions for Research

OCT and ODT are rapidly developing technologies with many potential applications for imaging and quantifying microfluidic flow dynamics in BioMEMS devices. New developments in all components of an OCT/ODT system, including light sources, detection electronics, and phase resolved processing algorithms can further increase imaging speed and sensitivity. Given its non-invasive and non-contact nature and exceptionally high spatial resolution and velocity sensitivity, OCT/ODT will be a powerful metrology tool for investigating complex flow dynamics in various bioMEMS devices that involve microfluidics.

Cross References

- ► Micro-PIV-Based Diffusometry
- ► AC Electro-Osmotic Flow
- ► Active Mixer
- ► Velocity Sensor

References

1. Huang D et al (1991) Optical Coherence Tomography. Science 254(5035):1178–1181
2. Bouma BE, Tearney GJ (2002) Handbook of Optical Coherence Tomography. Dekker, New York
3. Fercher AF, Hizenberger CK (2002) Optical Coherence Tomography. In: Wolf E (ed) Progress in Optics. Elsevier, p 215
4. Chen Z (2003) Functional optical coherence tomgoraphy. In: Hwang NHC, Woo SLY (eds) Frontiers in Biomedical Engineering. Kluwer Academic/Plenum, New York, pp 345–364
5. Chen Z (2004) Tomography and Optical Imaging. In: Guenther BD (ed) Encyclopedia of Modern Optics. Elsevier, New York
6. Brezinski ME (2006) Optical Coherence Tomography. Elsevier, New York
7. Chen Z et al (1997) Optical Doppler tomographic imaging of fluid flow velocity in highly scattering media. Opt Lett 22:64–66
8. Chen Z (2004) Optical Doppler tomography. In: Tuchin VV (ed) Coherent-Domain Optical Methods for Biomedical Diagnostics, Environmental and Material Science. Kluwer Academic, Boston, pp 315–340
9. Ahn YC et al (2005) Investigation of laminar dispersion with optical coherence tomography and optical Doppler tomography. Opt Express 13:8164–8171
10. Chen Z et al (1997) Noninvasive Imaging of in vivo blood flow velocity using optical Doppler tomography. Opt Lett 22:1119–1121
11. Izatt JA et al (1997) In vivo bidirectional color Doppler flow imaging of picoliter blood volumes using optical coherence tomography. Opt Lett 22:1439–1441
12. Zhao Y et al (2000) Phase-resolved optical coherence tomography and optical Doppler tomography for imaging blood flow in human skin with fast scanning speed and high velocity sensitivity. Opt Lett 25:114–116
13. Wang RK (2004) High-resolution visualization of fluid dynamics with Doppler optical coherence tomography. Meas Sci Technol 15:725–733
14. Ahn YC, Jung W, Chen Z (2006) Tubid two-phase slog flow in a microtube simultaneous visualizaion of structure and velocity field. Appl Phys Lett 89:064109
15. Ahn YC, Jung W, Chen Z (2008) Optical sectioning for microfluidics: secondary flow and mixing in a meandering microchannel. Lab Chip 8:125–133

Optical Doppler Tomography (ODT)

- ► Optical Coherence Tomography and Optical Doppler Tomography

Optical Doppler Velocimetry

- ► Optical Coherence Tomography and Optical Doppler Tomography

Optical Lithography

- ► Photolithography
- ► Photo Patterned

Optical Narrow Passband Filter

- ► Fabry-Perot Optical Filter

Optical Trapping

- ► Optofluidics: Optics Enabling Fluidics

Optical Traps

- ► Optical Tweezers for Manipulating Cells and Particles

Optical Tweezers for Manipulating Cells and Particles

Aloke Kumar, Andrew H. Ewing,
Steven T. Wereley
Department of Mechanical Engineering,
Purdue University, West Lafayette, IN, USA
wereley@purdue.edu

Synonyms

Optical traps

Definition

Optical tweezing is the stable three-dimensional trapping of dielectric substances by the creation of strong light intensity gradients such as by focusing a laser beam to a diffraction-limited spot. Although originally created using counter-propagating laser beams, most optical tweezers today use a single beam of laser light which is focused to a diffraction-limited spot, the spot being the trapping zone.

Overview

Optical trapping refers to the manipulation of extremely small objects using forces generated by light. The field was pioneered by Arthur Ashkin in the 1970s at Bell Labs. His groundbreaking work demonstrated that forces generated by light could capture micrometer-sized particles in a stable three-dimensional trap. Although Ashkin in his early work used counter-propagating laser beams to capture such miniature particles, present day optical traps generally employ only single laser beams. What exactly causes particles to get ‘caught’ in laser beams depends on the size of the particle, and different theories have been developed to explain the existence of trapping forces according to particle sizes. Diverse mechanisms for the phenomenon exist because of the extremely wide range of particle sizes that have been captured. Atoms, macromolecules, micrometer-sized beads and entire cells, such as viruses, have been shown to be capable of being optically trapped. The mechanisms not only depend on the particle size but also on the wavelength of laser used.

Optical trapping in all cases requires a gradient to be present across the cross-section of the light beam and wavelength control is often necessary in case of biological particles. Lasers, which are strongly monochromatic light sources with a Gaussian intensity profile across the cross-section, are ideal candidates for such purposes. The trapping of micrometer-sized particles is explained with regards to forces arising from the change in momentum of light passing through particles. The momentum change requires a force to be exerted on particles and these forces have transverse (radial) components which confine a particle to a domain. In normal circumstances such forces would be too small to be of any significance but they become increasingly important at lower length scales. These forces are usually in the piconewton range and are large enough for small particles to cause a change in their motion. Also, such a net non-zero transverse trapping force on a particle exists only for a gradient-based light source.

Application of this technology has been extremely wide and varied. The 1997 Nobel Prize in Physics was awarded to scientists who developed methods to cool and trap atoms with laser light. Researchers have used such traps/tweezers to manipulate a whole gamut of particles. The advantages laser tweezers offer over most other confining methods is the non-invasive nature and that the particles only need to have a different refractive index compared to the surroundings for the trap to work. Non-invasiveness can be a critical factor when dealing with biological particles where remote-execution is desirable.

Basic Methodology

Theoretical Principles

To trap a particle in three dimensions with a single beam requires the spatial variation of the light to satisfy two important conditions. The first requirement is that an intensity gradient in the direction perpendicular to the opti-



Optical Tweezers for Manipulating Cells and Particles, Figure 1 On the left-hand side the radial gradient force is illustrated for a particle near the axis of a Gaussian beam. The right-hand side depicts the axial gradient force acting on a particle near the focus of a divergent beam. Red lines represent the gradient forces while blue and green lines represent the forces due to refracting and reflecting rays, respectively

cal axis be present in the beam. This radial intensity gradient is responsible for trapping in the radial direction of the beam and is inherent in most laser systems. Figure 1 shows how a ray of high intensity from the core of a beam contributes a greater degree to the trapping force than a ray of low intensity. In practice, a TEM_{00} mode laser beam is used because of the Gaussian intensity gradient present in such a laser beam. The radial stiffness of the trap depends primarily on the magnitude of the radial intensity gradient. The second condition required for three-dimensional, single-beam trapping is that the laser must be tightly focused, or highly divergent, in the region where trapping is desired. A divergent beam has an intensity gradient in the direction of the optical axis due to the variation in the cross-sectional area of the beam. Trapping in the axial direction can occur near the focus of a divergent beam due to this form of spatial variation, as shown in Fig. 1. Focusing a beam to create an axial intensity gradient large enough to trap particles is easily achieved using an objective lens of high numerical aperture (NA).

Gradient Forces: Mie and Rayleigh Regimes

Optical gradient forces are the fundamental physical phenomena responsible for optical tweezers. There exist two separate theories which accurately describe the origin of the optical gradient forces for two different physical extremes. These two physical extremes, known as the Mie and Rayleigh regimes, refer to the magnitude of the wavelength of the trapping laser with respect to the characteristic size of the particle being trapped. The Mie regime assumes wavelength of the impinging laser beam, λ, is much smaller than the size of the particle, s, so that a geometric approximation of the optics and Newton's third law of motion are all that is required for a quantitative description of the gradient forces. Photons from the laser beam undergo a change in direction when they are refracted or reflected, which constitutes a change in the momentum of the photons. From Newton's third law, the material causing this direction change experiences an equal and opposite change of momentum, which manifests itself in the form of an external force acting on the material, as seen in Fig. 1. Certain rays of light will contribute disproportionately to this external force compared to others in the presence of a spatial intensity gradient. Depending on their intensity and direction before and after interacting with the specimen, each ray will contribute to the external force to a varying degree. The sum of the forces applied by each photon being scattered or transmitted by the specimen is the gradient force which acts as a potential well to trap the specimen. The differential force contribution of a ray, $\mathrm{d}F$, is given by Eq. (1), where n_1 is the refractive index of the surrounding medium and c is the speed of light in a vacuum [1]:

$$\mathrm{d}F = \frac{n_1 R\,(I \cdot \mathrm{d}A)}{c} \tag{1}$$

In Eq. (1), I and A are the intensity and area of the incident ray, respectively, and R is either the reflectance or the transmittance of the ray in question depending on whether the ray is being reflected or transmitted as it interacts with the trapped object. In Eq. (2), the gradient force, F_{∇}, is found by integrating $\mathrm{d}F$ over the surface of the specimen [1]:

$$F_{\nabla} = \int_{s} \mathrm{d}F \tag{2}$$

This method is particularly useful – when implemented numerically for computing the gradient force for bodies of arbitrary shape.

The other physical extreme for which an accurate theoretical treatment exists is known as the Rayleigh regime. Here the size of the specimen is assumed to be much smaller than the wavelength of light; therefore geometric approximations are no longer adequate for describing the behavior of light. Calculation of trapping forces in the Rayleigh regime requires an electrodynamics approach to calculate the optical forces. This approach assumes the gradient force arises from the fact that a dipole in an inhomogeneous electric field experiences a force in the direction of the field gradient. In optical tweezers, the laser induces a fluctuating dipole in a dielectric particle which interacts with the inhomogeneous electric field within the beam. In the presence of an electric field gradient, a dielectric particle with dipole moment, $\boldsymbol{p}$, will experience a force given by

$$\boldsymbol{F} = (\boldsymbol{p} \cdot \nabla)\boldsymbol{E} \tag{3}$$

This is done by treating the particle as a point dipole and using Maxwell's equations to solve for the electric field within the beam. It is convenient to analyze the trapping force in terms of two separate components: the scattering force, F_{scat}, and the gradient force, F_{∇}. The scattering force arises due to absorption and re-radiation by the dipole, whereas the gradient force arises due to the interaction between the induced dipole and the electric field. The dipole moment can be calculated by

$$\boldsymbol{p} = 4\pi n_2^2 \varepsilon_0 a^3 \left(\frac{m^2-1}{m^2+2}\right)\boldsymbol{E} \tag{4}$$

where $m = n_1/n_2$ is the ratio of refractive indices. The electric field vector for the lowest order Gaussian beam approximation is

$$\begin{aligned}\boldsymbol{E} = E_0 &\frac{ikw_0^2}{ikw_0^2 + 2z}\exp(-ikz)\\ &\cdot \exp\left[-i\frac{2kz(x^2+y^2)}{(kw_0^2)^2 + 4z^2}\right]\\ &\cdot \exp\left[\frac{(kw_0)^2(x^2+y^2)}{(kw_0^2)^2 + 4z^2}\right]\end{aligned} \tag{5}$$

where k is the wave number and w_0 is the minimum radius of the beam. The gradient force acting on the dielectric particle is found by substituting Eqs. (4) and (5) into Eq. (3), which yields

$$F_{\text{grad}} = 4\pi n_2^2 \varepsilon_0 a^3 \left(\frac{m^2-1}{m^2+2}\right)\tfrac{1}{2}\nabla E^2 \tag{6}$$

where a is the radius of the trapped sphere [2]. The scattering component of the optical forces must be calculated in order to find the total trapping force. The scattering force, F_{scat}, is equal to the energy density of the electromagnetic wave impinging on the scattering cross section, C_{scat}, of the sphere. The scattering force and cross-section are found using Eqs. (7) and (8) [2]:

$$F_{\text{scat}} = \left(\frac{n_2}{c}\right) C_{\text{scat}} I(x,y,z) \tag{7}$$

$$C_{\text{scat}} = \tfrac{8}{3}\pi (ka)^4 a^2 \left(\frac{m^2-1}{m^2+2}\right)^2 \tag{8}$$

The total trapping force acting on the trapped sphere is the sum of the trapping and scattering forces:

$$F_{\text{total}} = F_{\text{grad}} + F_{\text{scat}} \tag{9}$$

The theoretical treatments described above are very accurate for the extreme cases to which they apply. Unfortunately, most practical cases fall in the intermediate regime where the wavelength of the incident light is roughly the same size as the trapped particle. This intermediate case requires more complex theoretical models and is currently an area of interest for researchers.

Experimental Principles

As discussed earlier, single optical traps are characterized by a single laser beam focused to a high diffraction-limited spot using a high-magnification lens. The lens usually is the objective lens of a microscope, which serves to integrate the imaging and trapping systems. The imaging can serve as a data acquisition system, a monitoring system and a positioning device which helps focus the trap onto the region of interest. As stated before, optical traps have become an important tool for very diverse activities and as such have undergone numerous modifications to suit those diverse activities. The simplest form of optical trap consists of the following optical components.

Laser

The laser is the basic and most important component of the trapping system. Lasers are perhaps the most easily available sources of highly collimated, high-energy and monochromatic light beams. Also the transverse intensity gradient provides the necessary means to capture micro/nanoparticles. Being such an important component of the setup, the laser needs to be selected properly, the selection being based on a number of factors. These factors are usually output beam shape, beam astigmatism, power and wavelength. The most important requirement is that the output beam should be single mode (Gaussian TEM$_{00}$ mode). This ensures that the beam is focused, by the objective lens, to the smallest beam diameter thus producing the



Optical Tweezers for Manipulating Cells and Particles, Figure 2 A typical experimental setup for optical trapping. The lenses on the rail focus the beam onto a diffraction-limited spot and the epi-fluorescent cube filters the unwanted part of the spectrum and hence enhances image quality

most efficient trap. Beam astigmatism also prevents convergence of the laser beam to a small spot and hence needs to be eliminated if present before the laser is deployed. The maximum power of the laser and the final output power determine the maximum attainable strength/stiffness for the laser trap. The required wattage is usually calculated allowing for the losses and taking into account the actual power required for trapping an object. The actual trapping power required might not be easy to calculate and in many cases a review of existing literature should give an order of magnitude estimate. A laser power of the order of 20 – 100 mW is usually sufficient for many basic trapping experiments. The wavelength is another important parameter when it comes to trapping biological specimens. For non-living objects any part of the spectrum works fine but the visible region is usually preferred due to the relative ease in aligning the various other optical components. There is a broad consensus that when dealing with biological elements infrared lasers should be used. The primary concern behind using a laser with an emission peak in the visible spectrum is possible "opticution" (death by light). Such opticution was first observed by Ashkin [3] when working with viruses and bacteria. Even if low-power lasers are used for trapping purposes, very high energy levels are developed due to focusing of the laser beam, and high absorption of the laser wavelength by biological specimens might lead to their extermination. There is a wide consensus that lasers in the infrared region are far less damaging to live biological specimens and the current choice of laser is the neodymium:yttrium-aluminium-garnet (Nd:YAG) laser and its close cousins [4, 5]. This is because of the low absorption of radiation of the infrared part of the spectrum by biological species in general, and wavelengths between 750 and 1000 nm are usually recommended. Nd:YAGs, although a popular choice, are more expensive compared to diode-pumped solid-state lasers. However usage of any infrared laser does not guarantee prevention of opticution and laser wavelength should be determined after a thorough literature survey.

Most of the lasers employed for trapping purposes are continuous-wave (CW) lasers but femtosecond lasers have also been shown to be effective for trapping purposes. Diode lasers are usually inexpensive but the beam quality usually necessitates correcting optics which adds to the cost and makes the optical train more complex. The output beam in the case of diode lasers is elliptical and also astigmatic. Symmetry can be restored by correcting with an anamorphic prism. Spatial filtering by pinholes or single-mode optical fibers can also achieve the same goal albeit with large losses.

Objective

The objective lens is another important component of the system and its use is primarily to focus the laser beam to a diffraction-limited spot. The objective lens is an influencing parameter with regard to the final trap stiffness and depends on its numerical aperture (NA) and transmittance. The NA is usually a measure of the light-gathering ability of a system and hence higher NA lenses are preferred. The lenses should be chosen so as to minimize the refractive index mismatch between the immersion medium and the trapping medium. Some of the higher NA lenses are oil-immersed while water-immersed lenses are also available. As aberrations have a degrading effect on the trap quality, the choice of objective lenses should be made judiciously [4]. In many trap setups the objective serves a dual purpose of trapping and viewing the particles.

Microscope

Inverted and upright microscopes have both been used for trapping purposes and usually integration with the trapping optics is straightforward. Single-beam trapping integrated with confocal microscopy has also been achieved. The microscope also serves as the imaging system which might be achieved visually or using a video-based system. Eyepieces can be used to view the sample or the light might be redirected by a dichroic to a CCD camera. Care has to be taken that the laser light is filtered out before it reaches either the eyepiece or the camera. Highly focused laser beams pose a serious hazard to the observer and hence should be removed using appropriate optical filters. Microscopes also enable different imaging techniques such as differential interference contrast and epi-fluorescence. Figure 2 shows such an arrangement where an epi-fluorescent cube has been deployed for imaging. Like most other designs, it focuses a suitably expanded and shaped laser beam through a high-NA microscope objective. The laser beam is focused by an optical train to a diffraction-limited spot which is also the location for trapping particles. The optical path consists of lenses, directing mirrors and a filter cube, which is set up to specifically enable fluorescent imaging with a setup based on an inverted microscope. Bechhoefer and Wilson [6] and Smith et al. [7] discuss in detail the various practical and theoretical aspects involved in setting up a laser trap. The sample is held on an XYZ translational stage that serves to laterally displace the sample. The sample is illuminated using a halogen lamp placed directly above the sample, which can serve to provide the excitation frequency of the fluorescent microparticles. Finally, the image from the microscope is fed directly to a camera sensor. The microscope (not shown) is represented by the cube and XYZ stage.

Lenses and Other Trapping Optics

Lenses are required to expand the initial laser beam so that it totally fills the back aperture of the objective lens. Beam expanders can either be bought or constructed for specific use, by using individual lenses. The latter allows for the flexibility of a variable output if three lenses are used. Mirrors help to steer the beam. Other optics might be required depending on the specific task. Position detection might be achieved by a variety of techniques with each having its own merits and demerits. An exhaustive treatment of the same can be found in [4].

Key Research Findings

Since their invention, optical tweezers have proved themselves to be very powerful interdisciplinary tools. Today they are used extensively in biophysics, as they serve as delicate tools to manipulate and study single molecules of DNA [8, 9]. Optically trapped beads have been successfully used to measure local elasticities and viscosities, for example inside cells. Ashkin [5] provides an overview of the diverse uses of optical traps as an important tool in the important areas of research. Isolation and detection of sparse cells; concentration of cells from dilute suspensions; separation of cells according to specific properties; and trapping and positioning of individual cells for characterization are the key areas of research due to their possible impact. The non-invasive nature of particle manipulation being a key requirement, forces like hydrodynamic, optical, ultrasonic and electromagnetic have been employed for such purposes. Successful examples of the use of these optical forces for biological applications are determination of motility forces, 3-dimensional multi-gene detection and non-invasive optical sectioning of tissues [10] amongst many others.

Future Directions of Research

An optical trap behaves, at its simplest approximation, like a spring. The further a particle travels from the center of an optical trap, the greater the force it feels back to the center of the trap. Single optical traps make use of the Gaussian intensity profile in a laser to trap particles. Such traps are characterized by linear stiffness constants and hence the resulting potential well has a parabolic profile. Such systems are hence not suitable for creating arbitrary trap geometries. Fortunately recent technological advancements in holographic optical trapping have made possible generation of trap geometry based on individual preference and necessity. Optical tweezers implemented by SLMs are usually computer controllable which bestows upon them the important quality of being easily repeatable. The computer-driven liquid–crystal spatial light modulators create holograms, which correspond to various arrays of traps that can be designed, calculated and optimized on a computer. The traps can be controlled and reconfigured by writing these holograms on an SLM in real time. SLM optical traps have the advantage that they can switch traps independently. Such trapping systems show a lot of promise for future applications because of their many advantages over single optical traps.

Cross References

- ► AC Dielectrophoresis Lab-on-Chip Devices
- ► Dielectrophoretic Motion of Particles and Cells
- ► DC-Dielectrophoresis Lab-on-Chip Devices
- ► Dielectrophoresis

References

1. Gauthier RC (1995) Ray Optics model and numerical computations for the radiation pressure micromotor. Appl Phys Lett 67(16):2269–2271
2. Harada H, Asakura T (1996) Radiation forces on a dielectric sphere in the Rayleigh scattering regime. Opt Comm 124(5–6):529–541
3. Ashkin A (1970) Acceleration and Trapping of Particles by Radiation Pressure. Phys Rev Lett 24(4):156
4. Neuman KC, Block SM (2004) Optical trapping. Rev Sci Instrum 75(9):2787–2809
5. Ashkin A (1997) Optical trapping and manipulation of neutral particles using lasers. Proc Natl Acad Sci USA 94(10):4853–4860
6. Bechhoefer J, Wilson S (2002) Faster, cheaper, safer optical tweezers for the undergraduate laboratory. Am J Phys 70(4):393–400

7. Smith SP, Bhalotra SR, Brody AL, Brown BL (1999) Inexpensive optical tweezers for undergraduate laboratories. Am J Phys 67(1):26–35
8. Kurachi M, Hoshi M, Tashiro H (1995) Buckling of a single microtubule by optical trapping forces: Direct measurement of microtubule rigidity. Cell Motil Cytoskeleton 30(3):221–228
9. Felgner H, Frank R, Schliwa M (1996) Flexural rigidity of microtubules measured with the use of optical tweezers. J Cell Sci 109:509–516
10. Konig K (2000) Laser tweezers and multiphoton microscopes in life sciences. Histochem Cell Biol 114:79–92

Optofluidics – Applications

SUDEEP MANDAL, DAVID ERICKSON
Sibley School of Mechanical and Aerospace Engineering,
Cornell University, Ithaca, NY, USA
sm445@cornell.edu, de54@cornell.edu

Synonyms

Photofluidics

Definition

Optofluidics is the marriage of optics, optoelectronics and nanophotonics with fluidics. Such integration represents a new approach for dynamic manipulation of optical properties at length scales both greater than and smaller than the wavelength of light with applications ranging from reconfigurable photonic circuits to fluidically adaptable optics to high sensitivity bio-detection and analysis currently under development. In this article we present a comprehensive review of some of the emerging applications and technologies for optofluidics.

Overview

The capabilities in terms of fluidic control, mixing, miniaturization and optical property tuning afforded by micro-, nano- and electro-fluidics provides an ideal platform upon which to build versatile optofluidic devices. In this article we provide a general overview of some of the emerging applications of optofluidic technology. Providing a comprehensive overview of all the research in this field is outside the scope of this review. Rather we will provide a number of representative examples of the state of the art.

Basic Methodology

The basic methodology behind optofluidics is described in detail in the ►optofluidics – fluidics enabling optics, ►optofluidics – optics enabling fluidics and ►optofluidics – fabrication and integration techniques. Here we focus primarily on providing an overview of the some of the recent applications for optofluidics and refer readers to those articles for more detailed information.

Key Research Findings

Optofluidic Particle and Cell Sorting Techniques

The discovery that laser radiation could transfer its momentum to microscopic particles and thus be used to manipulate them led to many innovative applications. Optical tweezing was a direct consequence of this and has been vastly refined over the years. Recently there have been various advanced implementation of such techniques to achieve optical control and sorting of particles into advanced and highly integrated microfluidic systems. These techniques range from traditional optical trapping (see a recent review by Grier [1]), to massively parallel handling of particles and cells using electro-optic tweezers, rotational manipulation of components based on form birefringence, to optical force based cell sorting. The advantage of these optical approaches lies in their ability to provide remote operation and handle individual particles directly as opposed to indirect manipulation of the surrounding flow field (as with electrokinetic and pressure driven effects).

Active Sorting

As an example of a direct device integration, Wang et al. [2] developed an optical force based cell sorting technique whereby radiation pressure was used to direct rare cells into separate streams following a green florescent protein (GFP) detection event. A schematic of the operating procedure for this device is shown in Fig. 1. The mixture of cells was made to flow through a microfluidic channel and was aligned into a narrow stream using hydrodynamic focusing. The initial alignment was such that these cells would flow into the waste outlet. Prior to this the cells were made to first pass through an interrogation region. If fluorescence was detected, indicating the presence of a target cell, the optical switch was activated and a focused laser spot was used to deflect the target cell laterally. This lateral displacement of the target cell caused it to follow a streamline which would carry it into the collection outlet. Sorting speeds as high as 200 cells per second were achieved.

Passive Sorting

Though very complex optical manipulations have been demonstrated in literature, the majority of these imple-



Optofluidics – Applications, Figure 1 Layout of the microfluidic sorting junction and the optical switch for the optofluidic cell sorter described by Wang et al. [2]. After being aligned to the center of the channel by flow focusing, cells are analyzed and then switched based on their detected fluorescence. Target cells are directed by the laser to the collection output while all other cells flow to the waste output. Figure and Caption reprinted with permission from Wang et al. [2]

mentations tend to be *binary*. This means that they rely on either the ability to trap or not trap a particle based on whether the conditions for trapping stability are met. Recently however a number of works have extended these ideas to exploit the dependence of this trapping potential on the particle properties, enabling much more advanced and subtle operations. As an example, Macdonald et al. [3] demonstrated an optical lattice technique where particles of different sizes were sorted into different streams depending on their strength of repulsion to regions of high optical intensity. The method relies upon the principle of a periodic optical gradient that is designed to deterministically guide smaller particles. The field is designed to temporarily trap small particles, while using hydrodynamic force to push particles out of the trapped state into an adjacent trapping location in the field. Careful planning of the periodicity of the field leads to a deterministic motion of smaller particles in a specified direction, while larger particles continue nearly unimpeded.

Optical Chromatography

In a series of papers, Imasaka and coworkers [4] provided the initial foundations for optically driven separation techniques, which they termed optical chromatography. The advantage of this technique lies in that it is the most sensitive technique known to date for separation of particles based on their size. Table 1 below compares various bio-analytical separation techniques, the operating principles behind the techniques and the dependence of the separation velocity on the particle radius a.
Work in this area has recently been extended by Terray et al. [5] who have recently integrated this into a microfluidic device format for pathogen detection, demonstrating very precise separation between very closely related bacteria *Bacillus anthracis* and *Bacillus thuringiensis* and millimeter scale separation. In their work a loosely focused laser beam propagates in a direction opposite to the fluid flow in the Poly(dimethysiloxane) (PDMS) channel. As a result of the difference in the optical forces on the cells they come to rest at different points along the length of the channel. At present however, such systems are practically limited by the fundamentals of the free-space optics on which they rely. Specifically, the light-particle interaction length is limited by either the focal depth or the spot size of the objective lens.

Evanescent Field Based Particle Trapping and Manipulation

Waveguide based optical structures serve to confine light within solid structures from the visible to the IR spectrum. A waveguide relies upon the principles of total internal reflection to confine light within the solid waveguide structure. Such confinement separates optical energy into guided modes and evanescent modes. While the guided modes represent the confined optical energy in the waveguide, the evanescent modes represent leaked optical energy, which exhibits an exponential decay as the distance from the waveguide surface increases. A waveguide trap/propulsion device is designed such that the evanescent mode interacts with particles to generate scattering/absorption and gradient forces which pull the particle towards the waveguide. There have been some experimental works of waveguide based particle propulsion. Gaugiran et al. [6] published a paper based on silicon nitride waveguide and demonstrated the trapping and propulsion of biological cells along these waveguides. The paper also presents the use of a finite-element analysis as a means of predicting the optical forces for a dielectric particle interacting with a waveguide. The difficulty with these waveguide techniques is that one is limited to interaction with

Optofluidics – Applications, Table 1 Comparison of Bioanalytical Separation Techniques

Technique	Operating Principle	Separation Velocity
Optical	Scattering and adsorption force dependence on particle size and refractive index. Driving force is intensity of EM field, $V_{op} \propto I$.	$V_{op} \propto a^5$ $V_{op} \propto (\varepsilon_p - \varepsilon_m)^2$
Electrophoresis	Differences in species charge to drag ratio represented by electrophoretic mobility. Driving force is electric field, $V_{ep} \propto E$.	$V_{ep} \propto \zeta \neq f(a)$ * (thin EDL) $V_{ep} \propto 1/a$ * (thick EDL)
Dielectrophoresis	Lorenz force dependence on particle size and polarizability. Driving force is the gradient of E^2, $V_{dep} \propto \nabla(E^2)$.	$V_{dep} \propto a^2$ $V_{dep} \propto (\varepsilon_p - \varepsilon_m)$
Centrifugation and Sedimentation	Differences in density. Driving force is gravitational or centrifugal acceleration field, $V_{cent} \propto g$.	$V_{cent} \propto (\rho_p - \rho_m)a^2 \approx a$
Size Exclusion Chromatography	Size dependence on permeability through packed column. Typically pressure is used as driving force, $V_{SEC} \propto \Delta P$.	$V_{SEC} \propto -\log(a^3)$ **

* For free solution electrophoresis. Gel based electrophoresis results in a non-linear drag which can increase the dependence of V_{ep} on a.
** Approximate, based on assumption of proportionality between hydrodynamic volume and molecular weight.

the evanescent mode which tend to be much weaker than direct interactions with the mode.

Optoelectronic Tweezers

As an alternate approach Chiou et al. [7] recently demonstrated massively parallel manipulation of single cells and microparticles using optical images. This was achieved by high resolution patterning of electric fields by projection of an optical image on a photoconductive surface. In these optoelectronic tweezers (OET), high resolution dielectrophoretic electrodes were patterned optically which enabled single cell manipulations and sorting. By varying the frequency of the AC signal applied between the two electrodes, one can switch between negative dielectrophoresis (DEP) and positive DEP regimes. Since the images used to pattern the electrodes are generated on a computer they can be dynamically modified in real-time. Thus this technique allows for highly parallel cell manipulations, sorting and trapping. The only limitation with this technique is that the resolution of the images that are projected on the photoconducting surface is fundamentally limited because of diffraction. As a result manipulation, with submicron resolution is not possible, though this is well below the precision required for cell based manipulations.

Optofluidic Imaging Techniques

At present one of the significant hindrances towards the development of fully portable, stand alone Lab-on-Chip devices, is the reliance on macroscale infrastructure such as pumps, power sources and most importantly external optics. To tackle the latter of these, Heng et al. [8] have developed an integrated optofluidic microscope (OFM) which integrates a high resolution imager, in the form of a slanted nanohole array, directly into a microfluidic network. Figure 2 provides an overview of the operating procedure for the OFM. The target object is made to flow through the microfluidic channel at a constant velocity using either electrokinetic control or pressure driven flow and confined to the center of the imager through upstream focusing. In the arrangement the imager consists of a slanted nanohole array defined in an opaque layer (typically aluminum) which spans the width of the channel. As is shown in the current arrangement the device is epi-illuminated and the transmission through the holes is monitored as the target flows over the imager. For the length of time the target flows over each individual well the transmission is reduced. Given that the flow rate is known the transmission traces can be used to reconstruct an image of the target. This technique enables the correct shape and size of the target to be extracted which should be sufficient for high speed phenotyping.

Using an entirely different approach, Kuiper and Hendriks [9] demonstrated a variable-focus liquid lens that has immense potential for application in miniature cameras and other optical devices. The lens consists of the meniscus between two immiscible liquids. In their experiment the two liquids were oil and water. By changing the curvature of this meniscus one can change the focal length of this liquid lens. To achieve this change in curvature they used the technique of electrowetting. Electrowetting refers to the phenomena of changing the interfacial contact angle between an electrolyte and solid through application of an applied potential difference. By varying this applied potential difference, the curvature of the fluidic lens could be continuously varied from convex to concave thereby adjusting the focal length of the lens.



Optofluidics – Applications, Figure 2 **(a)** Architecture of the optofluidic microscope (OFM); set of three arrows: illumination; single arrow: flow direction. **(b)** Photograph of the OFM prototype compared with a U.S. quarter. The actual nanoaperture array is 600 mm long. **(c)** The top view of the OFM; a denotes the isolated aperture; b denotes the corresponding aperture, as explained in the text. **(d)** Photograph of the orientation of the aperture array with respect to the channel. **(e)** Experimental scheme for the OFM prototype. **(f)** Transmission time traces from aperture α and β associated with the transition of a C. elegans. Figure and Caption reprinted by permission from Heng et al. [8]



Optofluidics – Applications, Figure 3 SEM images of hollow-core ARROWs with rectangular and arch-shaped cross sections. Figure and Caption reprinted with permission from Yin et al. [11]

Optofluidic Lasers

Another limitation of existing Lab-on-Chip devices is the inability to encorperate active optical components directly into the same inexpensive structure that contains the microfluidic components. As a result of the widespread adoption of PDMS as a material of choice for microfluidic systems, there has been a large thrust towards creating structures which can be easily cast into the soft elastomer fluidics and provide this more advanced functionality. One such example was presented by Li et al. [10] who demonstrated an optofluidic dye laser. In their implementation, a solution of Rhodamine 6G lasing dye in a Methanol, Ethylene Glycol solution is introduced into a microfluidic channel. The refractive index of the solution ($n = 1.42$) is slightly higher than that of PDMS (1.406) at visible wavelengths so that the dye solution and PDMS act as the core and the cladding of an optical waveguide respectively. To provide the feedback mechanism, a Bragg grating is fabricated on the sidewall of the channel. Tunable laser output can be obtained by either changing the index of the dye solution or mechanically varying the grating period. In this work, lasing was demonstrated around the 585 nm point. Such lasers would be of great interest for on-chip spectroscopy and cell sorting applications.

Liquid Core Waveguides

Liquid core waveguides are of great importance in the field of optofluidics since they allow the optical and fluidic structures to be fundamentally intertwined. Recently Yin et al. [11] have demonstrated such a liquid core waveguide which works on the principle of antiresonant reflecting optical waveguides (ARROW), see Fig. 3. ARROW waveguides with solid cores have been used for semiconductor lasers and other applications in the past. The technique uses multiple layers of materials of precise thicknesses as cladding such that an antiresonant Fabry–Perot reflector is created causing the light at the design wavelength to reflect back into the core. Silicon nitride and silicon dioxide are used as the cladding layers because of their compatibility with microfabrication techniques and the potential for integration with silicon-based electronics. The cladding layers are deposited over a sacrificial layer that is later etched away to create a rectangular shaped hollow core. This hollow core can be filled with liquids or gases and has shown exceptional promise for low level, single molecule detection in fluidic systems. The architecture is also amenable to massively parallel integration by creating numerous waveguides on the same chip.

Another approach towards creating liquid core waveguides was demonstrated by Wolfe et al. [12]. They managed to manipulate light in waveguides comprising of a liquid core and a liquid cladding. These waveguides are dynamic and can be reconfigured and adapted in a continuous manner which is a big advantage over solid-state waveguides. The liquids are introduced into a microfluidic channel in such a manner so that the higher refractive index core liquid is sandwiched between two sheaths of the lower refractive index cladding fluid. Thus the light is guided via total internal reflection within the liquid core. Since the flow is laminar the liquid-liquid interface is optically smooth resulting in low optical losses. By varying the rate of flow and the fluid compositions the characteristics of these optical systems can be tuned.

Future Directions for Research

The technologies we have described above represent, in our opinion, those which show the most promise for future commercial development. Of what we have described here liquid lenses (such as that described by Kuiper and Hendriks liquid lenses [9]) are likely the closest to being mass produced and broadly commercially available. Though less well developed at present the other optofluidic imaging techniques may also serve to solve some of the fundamental downsizing challenges (those related to imaging) which have to date largely prevented the demonstration of a truly portable Lab-on-Chip. The inherent advantages of optical chromatography coupled with the very large size of the bio-analytical separations market seem to suggest that this could hold commercial potential in the near future.

Cross References

- ► Optofluidics – Optics Enabling Fluidics
- ► Optofluidics – Fluidics Enabling Optics
- ► Optofluidics – Fabrication and Integration Techniques

References

1. Grier DG (2003) A revolution in optical manipulation. Nature 424(6950):810–816
2. Wang MM, Tu E, Raymond DE, Yang JM, Zhang HC, Hagen N, Dees B, Mercer EM, Forster AH, Kariv I, Marchand PJ, Butler WF (2005) Microfluidic sorting of mammalian cells by optical force switching. Nature Biotechnology 23(1):83–87
3. MacDonald MP, Spalding GC, Dholakia K (2003) Microfluidic sorting in an optical lattice. Nature 426(6965):421–424
4. Imasaka T (1998) Optical chromatography. A new tool for separation of particles. Analusis 26(5):M53–M55
5. Terray A, Arnold J, Hart SJ (2005) Enhanced optical chromatography in a PDMS microfluidic system. Opt Express 13(25):10406–10415
6. Gaugiran S, Getin S, Fedeli JM, Colas G, Fuchs A, Chatelain F, Derouard J (2005) Optical manipulation of microparticles and cells on silicon nitride waveguides. Opt Express 13(18):6956–6963
7. Chiou PY, Ohta AT, Wu MC (2005) Massively parallel manipulation of single cells and microparticles using optical images. Nature 436(7049):370–372
8. Heng X, Erickson D, Baugh LR, Yaqoob Z, Sternberg PW, Psaltis D, Yang CH (2006) Optofluidic microscopy - a method for implementing a high resolution optical microscope on a chip. Lab on a Chip 6(10):1274–1276
9. Kuiper S, Hendriks BHW (2004) Variable-focus liquid lens for miniature cameras. Appl Phys Lett 85(7):1128–1130
10. Li ZY, Zhang ZY, Emery T, Scherer A, Psaltis D (2006) Single mode optofluidic distributed feedback dye laser. Opt Express 14(2):696–701
11. Yin DL, Schmidt H, Barber JP, Lunt EJ, Hawkins AR (2005) Optical characterization of arch-shaped ARROW waveguides with liquid cores. Opt Express 13(26):10564–10570
12. Wolfe DB, Conroy RS, Garstecki P, Mayers BT, Fischbach MA, Paul KE, Prentiss M, Whitesides GM (2004) Dynamic control of liquid-core/liquid-cladding optical waveguides. Proceedings of the National Academy of Sciences of the United States of America 101(34):12434–12438

Optofluidics – Fluidics Enabling Optics

David Erickson
Cornell UniversitySibley School of Mechanical
Engineering, Ithaca, NY, USA
de54@cornell.edu

Synonyms

Photofluidics

Definition

Optofluidics is the marriage of optics, optoelectronics and nanophotonics with fluidics. Such integration represents a new approach to the dynamic manipulation of optical properties at length scales both greater than and smaller than the wavelength of light. Broadly speaking optofluidic devices can be split into two distinct classifications: optics enabling fluids and fluids enabling optics, the latter of which is the focus of this article.

Chemical and Physical Principles

The concept behind optical devices which incorporate liquids as a fundamental part of the optical structure can be traced at least as far back as the 18th century where rotating pools of mercury were proposed as a simple technique to create smooth spherical mirrors for use in reflecting telescopes. Modern microfluidics has enabled the development of a present day equivalent of such devices, the development of which we now refer to as Optofluidics. As will be described below, the capabilities in terms of fluidic control, mixing, miniaturization and optical property tuning afforded by micro-, nano- and electro-fluidics combined with soft lithography based fabrication provides an ideal platform upon which to build such devices.

Broadly speaking optofluidic devices can be classified into two distinct categories: *Optics enabling Fluidics* and *Fluidics enabling Optics*. As mentioned above in this article we focus on the latter of these two and refer readers to the ►optofluidics – optics enabling fluidics article within this encyclopedia for more detail. In this article we begin by describing the core fluid dynamics which describe the transport of fluids and behavior of interfaces in optofluidic devices. In the key research findings section we describe in detail the core advantages and applications of optofluidic devices (specifically looking at adaptive optics, biosensor and thermal stabilization). Following that provide a detailed example of the application of optofluidics to the tuning of photonic crystal circuits at the 200 nm scale.

The Fluid Dynamics of Optofluidic Devices

In the broadest sense, optofluidics involves the manipulation of the optical properties of a system using fluidics and conversely the manipulation of fluidic properties of a system with optics. It is thus is inherently concerned with both the optical and thermophysical properties of the fluid and the dynamics of how both the optical and flow fields change in response to external stimuli. In this section we will provide a brief overview of some of the fluids of particular interest in optofluidics and some of their important optical and thermophysical properties. The following subsection will provide a brief overview of the relevant microfluid dynamics with a focus on the issues of relevance to optofluidics.

Optofluids

Table 1 provides an overview of a small sampling of liquids of the relevant properties for a few common optofluidic liquids. Note that this represents a non-comprehensive list, other parameters of particular interest include: fluid–fluid surface tension, fluid–solid surface energy, contact angle, fluid–solid electroosmotic mobility, compatibility with soft elastomers (or other materials of interest), and numerous others.

Optofluid Dynamics

On length scales relevant to optofluidic devices (between 10 nm and 5 mm), fluid flow and species transport can be accomplished using numerous different techniques, a few of which include: traditional pressure driven flow, electrokinetic transport, buoancy, magnetohydrodynamics, capillarity, electrowetting and thermocapillarity (see Stone et al. [1] for a comprehensive overview). In general all flows can be classified as either body force driven (as in the former four of those listed above) and surface force driven (as in the latter three). Although examples exist to the contrary in general body force driven flows have been more successfully exploited in confined channel geometries, whereas free surface techniques are more popular for discrete droplet techniques. It is important to note that this statement is a general trend and by no means a rule (as capillarity, electrowetting and thermal manipulation of surface forces have all been used in channel driven geometries).

In either case fluid motion is governed by the momentum (Navier-Stokes) Eq. (1a) and continuity equations Eq. (1b) shown below,

$$\rho\left(\frac{\partial \boldsymbol{v}}{\partial t}+\boldsymbol{v}\cdot\nabla\boldsymbol{v}\right)=-\nabla p+\eta\nabla^2\boldsymbol{v}+f\,, \tag{1a}$$

$$\nabla\cdot\boldsymbol{v}=0\,, \tag{1b}$$

where $\boldsymbol{v}$, t, p, η, and ρ are velocity, time, pressure, viscosity and density respectively and f represents an applied body force. Though it is beyond the scope of this paper to provide a comprehensive review of the equations for all transport mechanisms mentioned above we will provide

Optofluidics – Fluidics Enabling Optics, Table 1 Some fluids used in optofluidic devices*

	Optical Properties			Thermophysical Properties		
Fluid	**Refractive index, n**	**Temperature derivative, dn/dT $(10^{-4}\,1/K)$**	**Non-linear refractive index, $\gamma\,(10^{-20}\,m^2/W)$**	**Viscosity, $\eta\,(mPas)$**	**Density, $\rho\,(kg/m^3)$**	**Thermal conductivity, $k\,(W/mK)$**
Water, H_20	1.33299	−0.8	2.7^b	0.890	997.05	0.6071
Heavy Water, D_20	1.32828	–	6.4^c	–	1104.4	–
Methanol, CH_40	1.33118	-4.68^a	4.7^b	0.544	787.2	0.200
5.03M Aqueous $CaCl_2$	1.4420	–	–	8.997	1395.7	–
Ethylene glycol, $C_2H_60_2$	1.4318	-3.06^a	–	16.1	959.8	0.256
Carbon disulfide, CS_2	1.6319	−8.00	$310–360^b$	0.35 2	1255.6	0.149

* Except where indicated properties are given at room temperature conditions and measured at 590 nm. ^{a} = measurement reported at 600 nm, ^{b} = measurement reported between 530 nm and 532 nm, ^{c} = measurement reported at 1060 nm

a brief overview of some of those mechanisms which may be most appropriate for optofluidics.

Pressure driven flow, for which f is zero in Eq. (1a), tends to be the simplest transport mechanism to implement and is accomplished by applying a mechanical pressure difference between an inlet and an outlet port. For the simplest case of pressure driven flow in a microchannel with low aspect ratio it can be shown that the average velocity in the channel is described by Eq. (2) below,

$$v_{\text{ave}} = \frac{h^2}{12\eta}\nabla P\,, \tag{2}$$

where h is the channel height. The geometric dependence of velocity shown in Eq. (2) represents the most significant weakness of pressure driven fluidics in that as one approaches the nanoscale the flow velocity either becomes debilitatingly small or the required pressure exceedingly high.

Alternatively a different transport mechanism can be used which does not exhibit such a fundamental limitation. In electrokinetic transport results from the interaction of an externally applied electric field, $\nabla\phi$, with the net charge density ρ_e, in the electrical double layer (the body force term in Eq. (1a) becomes $f = \rho_e\nabla\phi$). The electrical double layer is a very thin region of non-zero net charge density near the interface (in this case a solid–liquid interface) and is generally the result of surface adsorption of a charged species and the resulting rearrangement of the local free ions in solution so as to maintain overall electroneutrality. In general it can be shown that for electroosmotic flow in a channel with uniform properties Eq. (1a) reduces to a flat velocity profile (as opposed to the parabolic velocity profile associated with pressure driven flow) whose velocity is described by that below,

$$v_{\text{ave}} = \frac{\varepsilon_w\varepsilon_o\zeta}{\eta}\nabla\phi = \mu_{eo}\nabla\phi \tag{3}$$

where μ_{eo} is the electroosmotic mobility and ε_o and ε_w are the dielectric permittivity of a vacuum and the local relative dielectric permittivity (or dielectric constant) of the liquid respectively. In general μ_{eo} is of the order 10^{-4} cm^2/Vs and flow velocities on the order of 1 mm/s are achievable with applied potential fields of 1000 V/cm. The advantage of electrokinetic flow are that the flow velocity does not scale with channel height (outside the limit of double layer overlap and then only weakly until the extreme cases) and thus is more appropriate for nanoscale fluidics. The most significant disadvantage is that μ_{eo} is highly sensitive to the conditions at the solid liquid interface and is thus only applicable to a limited class of fluids, typically aqueous based solution. Even within this class μ_{eo} is strongly dependent with on ionic concentration and becomes exceedingly small in the high molarity (i. e. high refractive index) solutions listed in Table 1. Electrokinetics in high molarity solutions also tends to have other difficulties such as joule heating. The coupling of these effects complicates the use of electrokinetics for optofluidic devices.

As mentioned above, the other class of fluidic manipulation of particular interest in optofluidic applications are surface force driven techniques. In such techniques fluidic motion is induced applying an external perturbation to the equilibrium conditions at the interface between two phases. The normal stress conditions at the interface between two phases is described by Eq. (4) [2].

$$(p - \tau_{nn})_a - (p - \tau_{nn})_b = \sigma\left(\frac{1}{R_1} + \frac{1}{R_2}\right) \tag{4}$$

where the subscripts a and b represent the two phases τ_{nn} is the stress normal to the interface, σ is the surface tension and R_1 and R_2 are the principal radii of curvature. The applied perturbation, which most commonly is either electrically (i. e. electrowetting), thermally or chemically



Optofluidics – Fluidics Enabling Optics, Figure 1 Nanoscale Optofluidic Integration. Multilayer soft lithography is used to fluidically address and tune photonic structures at the nanoscale. (**a**) shows schematic of multi-layer soft-lithography coupling with nanophotonics. (**b**) SEM image of nanoscale precision fluidic addressability in a photonic crystal

based, induces a local change in either the surface tension or curvature (often observed as a change in the solid–fluid contact angle) which, from Eq. (4), in turn results in a pressure gradient and subsequent motion within at least one of the phases. While such techniques have proven extremely successful for both optical and Lab-on-Chip type devices, the activation energy required to overcome surface roughness tends to limit such effects to relatively large droplet sizes.

Key Research Findings

As mentioned above the focus of this section is to describe some of the core applications for optofluidic devices.

Optofluidics for Adaptive Optics

A key factor for high performance adaptive optical system is the capability to dynamically control either the physical layout or the refractive indices of the optical components. Recent advancements in optical MEMS technology [3] has provided significant functionality and flexibility to the former of these (e. g. optical switching and reconfigurable mirror arrays). Traditional techniques for manipulating the refractive index through the application of electric, acoustic or mechanical strain fields are limited in this respect by the achievable $\Delta n/n$, as is shown in Table 2. Optofluidics offers an order of magnitude jump in this quantity allowing for the development of an entirely new class of adaptive optical system in which, when combined with soft lithography based nanofluidics, the index of refraction can in principal be arbitrarily reconfigured at scales significantly smaller than the wavelength of light. At present modulation speeds for such tuning can be in the millisecond range but are ultimately limited by the viscous nature of the process and the mechanical actuation techniques that are popularly used. Alternative transport mechanisms such as electrokinetics (discussed in the following section) could be used to reduce the time response even further, though likely not to the scale required for high speed optical switching applications.

Optofluidics – Fluidics Enabling Optics, Table 2 Comparison of optofluidics with traditional optical tuning techniques

Technology	$O(\Delta n/n)$	Time response (s)
Optofluidics	**1**	$\mathbf{10^{-3}}$
Liquid crystal	0.1	10^{-3}
Injection current	0.02	10^{-9}
Temperature	0.02	1
Photorefractive	0.001	10^{-1}–10^{-5}
Electrooptic (10 kV/cm)	0.002	10^{-12}
Photoelastic/ Acoustooptic (10 W)	0.0001	10^{-6}–10^{-7}

Optofluidic Biosensors

The integration of microfluidics with optical detection techniques has been a field of active interest for several years (see Prasad [4] for an overview of optical biosensors and Erickson and Li [5] for an overview of integrated microfluidic devices). In addition to traditional florescence based detection, techniques relying on the incorporation of planar waveguides, evanescent wave fields or surface plasmons are particularly suitable for integration with microfluidics. While such techniques have proven exceptionally successful, a particularly fruitful path for future research in optofluidics is in the development of resonant cavity sensors. Such sensors can take advantage of the extremely high quality factor to mode volume ratios (Q/V) achieved in nanophotonic structures to perform single or few molecule sensing. The challenges here will be to not only develop techniques for delivering, attracting or concentrating bioentities into the resonant cavities, but being able to perform highly specific detection as well.

Optofluidics for Thermal Stabilization

The incorporation of liquids directly into the optical structure also has inherent advantages in terms of temperature stabilization. In general the heat transfer coefficient (which is the proportionality constant between heat rejection and surface temperature) for systems immersed in air ranges from 10 W/m^{2}K to 100 W/m^{2}K, depending strongly on the geometry and flow velocity. As a result of the higher density, specific heat capacity and thermal conductivity of water immersed systems, heat transfer coefficients typically range from 500 W/m^{2}K to 10,000 W/m^{2}K thus representing at least an order of magnitude decrease in the temperature rise for a given heat rejection requirement. It is important to note that while this represents a general rule for global heat transfer, more detailed modeling is required to accurately predict the local heat transfer enhancement.

Examples of Application

Since the emergence of optofluidics as a distinct field around 2002, a number of prominent examples of the fusion of these technologies have been developed including: liquid crystal infused photonic crystal lasers, fluid-fluid waveguides and florescent light sources, polarization independent fluidic switches, microfluidically tuned optical fibers and interferometers, and electrowetting based adaptable fluidic lenses and electronic paper. Rather than providing a cursory overview of these different devices in the limited space available here, we choose to focus on our recent work on nanofluidically tunable photonic crystal circuits [6] as a representative example. Readers looking for broader detail should consult the article within this encyclopedia entitled ► optofluidics – fabrication and integration or the recently published work by Psaltis et al. [7]. As mentioned above and shown in Table 2, at present techniques for local refractive index modulation in photonic structures are limited to the exploitation of relatively weak non-linearities, where $\Delta n/n$ on the order of 10^{-3} or lower. The consequence of this is that they require long interaction lengths, high operational power, or the incorporation of resonant elements to enhance the effect. The advantage of these techniques is that they can be, in general, applied locally to single devices (a necessity for device integration). Alternative techniques such as mechanical deformation, thermooptics, liquid crystal infusion and liquid-fluid infusion (amongst others) offer much higher effective $\Delta n/n$. At present, however, these methods rely on globally modifying the refractive index of the entire device. Thus whereas local tunability over small interaction lengths requires the high $\Delta n/n$ afforded by these



Optofluidics – Fluidics Enabling Optics, Figure 2 TE-like transmission through photonic crystal with aligned nanochannel. (**a**) Shift in transmitted power spectrum when aligned nanochannel filled with H_20 ($n = 1.33$) and 5M $CaCl_2$ ($n = 1.44$) (**b**) Dynamic switching at $a/\lambda = 0.291$ (shown as *red line* in (**a**)) (**c**) Rendition of the switching process global approaches, the ability to perform such manipulations with the sub-micron scale precision required for advanced photonic devices remains elusive. The development of such a technique could enable the creation of a new class of ultra-compact adaptable photonic circuits.

Nanofluidics provides a solution that enables both localized control and high refractive index modulation. As a first step in the development of two dimensional reconfigurable photonic circuits, here we demonstrate the nanofluidic addressing and tuning of individual defects within planar photonic crystals. Photonic crystals are attractive for controlling optical propagation by introducing pre-engineered defects into an otherwise regular lattice to create spectral filters, tight bend waveguides, resonant cavities and highly efficient lasers. Figure 1 outlines our approach which follows a three level nanoscale optofluidic integration architecture approach comprising of:

1. a nanophotonic level. Fabricated in silicon on insulator with the appropriate device structure.
2. a ►nanofluidic level, which serves to deliver fluids directly into the photonic structure and
3. a microfluidics control engine that performs all the major fluidic manipulations.

Assembly of the structure is performed by first defining the nanofluidic layer in positive relief on SOI and then defining the microfluidic structure on the same device using standard photolithography. At the same time a microscale valve layer is also defined in positive relief using photolithography on a separate silicon wafer. The two layers are then cast in PDMS, aligned and bonded together using standard multilayer soft lithography techniques [8]. The assembled fluidic structure is then aligned and bonded (through plasma oxidation) to the photonics layer. Using this structure fluids with different linear and non-linear optical properties can be infused directly into the nanophotonic structure with excellent precision and without significant leaking as shown in Fig. 1.

Figure 2 shows the normalized quasi-TE mode transmission through the photonic crystal with a fluidically modulated waveguide for DI ($n = 1.33$) water and 5M $CaCl_2$ ($n = 1.44$). The results show a shift in the peak transmission of the guided mode from $a/\lambda = 0.291$ to $a/\lambda = 0.289$ (corresponding to $\lambda = 1491$ nm and 1502 nm respectively) when the lower index liquid is displaced by the higher index salt solution. The high $\Delta n/n$ afforded by nanofluidic modulation demonstrated here enables consistently high contrast over a relatively wide range of wavelengths. Increasing the $\Delta n/n$ of the switching solutions would provide a greater shift in the peak transmission of the guided mode, however it would not provide for a much higher extinction ratio. Dynamic modulation of the transmitted power is demonstrated in Fig. 2 at $a/\lambda = 0.291$ by fluidically switching between the DI water and $CaCl_2$ solutions. For reasons described above, the modulation speed is inherently limited by the use of pressure driven flow. While the length of the nanochannels could be reduced the most fundamental limitation on the speed of such device is the nanochannel width section which is fixed by the lattice constant of the photonic crystal. Alternative fluidic transport mechanisms such as electroosmotic flow are mentioned above as a possibility, however here the low electroosmotic mobility of the $CaCl_2$ solution made such an approach not feasible.

Cross References

- ► Optofluidics – Optics Enabling Fluidics
- ► Optofluidics – Fabrication and Integration

References

1. Stone HA, Stroock AD, Ajdari A (2004) Engineering flows in small devices: Microfluidics toward a lab-on-a-chip. Ann Rev Fluid Mech 36:381–411
2. Panton R (1996) Incompressible Flow. John Wiley & Sons, New York
3. Lin LY, Goldstein EL (2002) Opportunities and challenges for MEMS in lightwave communications. IEEE J Selec Topics Quantum Electron 8(1):163–172
4. Prasad P (2004) Nanophotonics. Hoboken, John Wiley and Sons, Inc, New Jersey
5. Erickson D, Li DQ (2004) Integrated microfluidic devices. Anal Chimica Acta 507(1):11–26
6. Erickson D, Rockwood T, Emery T, Scherer A, Psaltis D (2006) Nanofluidic tuning of photonic crystal circuits. Opt Lett 31(1):59–61
7. Psaltis D, Quake SR, Yang CH (2006) Developing optofluidic technology through the fusion of microfluidics and optics. Nature 442(7101):381–386
8. Unger MA, Chou HP, Thorsen T, Scherer A, Quake SR (2000) Monolithic microfabricated valves and pumps by multilayer soft lithography. Science 288(5463):113–116

Optofluidics: Optics Enabling Fluidics

Allen Yang, David Erickson
Cornell UniversitySibley School of Mechanical Engineering, Ithaca, NY, USA
ay38@cornell.edu, de54@cornell.edu

Synonyms

Photofluidics; Waveguide trapping; Waveguide propulsion; Radiation pressure; Optical trapping

Definition

In the broadest sense, Optofluidics involves the manipulation of the local optical properties of a system using fluids and flow behavior and, conversely, the manipulation of fluids and particles within a flow through optical forces. The latter is inherently concerned with both the optical and thermophysical properties of the fluid and the dynamics of how both the electromagnetic and flow fields change in response to external stimuli. Optical forces used to manipulate fluid and particle behavior can arise either from focused beams in free space or from guided light confined to defined planar structures though total internal reflection. This emerging field of study is currently focused on the understanding of the fundamental coupling between optical dynamics and hydrodynamics, and developing methods to exploit the unique advantages optically derived forces have for micro and nanoscale systems.

Chemical and Physical Principles

The idea of using optical forces for particle manipulation was pioneered by Arthur Ashkin [1] in 1970, when he detailed the scattering and gradient force effects for small particles in the presence of optical energy. Since then, the field has developed to include many other methods to confine and move particles/fluids through the use of optical energy. The first experiments conducted using optical traps dealt with the manipulation of spherical beads within a stagnant liquid and the characterization of the forces observed acting on particles due to the presence of a focused laser beam [2]. With the development of microfluidics, experiments and studies of flow behavior could be conducted on scales similar to those on which optical phenomena occur. Thus, it becomes possible to study systems where coupled fluid and optical dynamics become important. The end goal is to develop nanoscale systems where optics can be exploited as a fundamental transport mechanism.

Free-space optical manipulation techniques in microfluidic systems have recently generated a significant amount of interest. Classically the advantage of these optical approaches lies in their ability to provide remote operation and handle individual particles directly as opposed to indirect manipulation of the surrounding flow field. The precision with which particles can be transported and separated with these optical techniques makes them particularly useful for bio-medical analysis devices. While extremely flexible and relatively easy to implement (see the section on ► optofluidics – applications and ► optofluidics – techniques for fabrication and integration), these systems are ultimately limited by the fundamentals of the free-space optics. Specifically, the light-particle interaction length is limited by either the focal depth or the spot size of the objective lens to usually a few hundred microns, as shown in Fig. 1. Using a more loosely focused lens with a larger spot size can increase the interaction length to as much as a millimeter. The intensity however scales with the square of the beam radius and as such relatively large optical power is required to perform manipulations over even these relatively small length scales.



Optofluidics: Optics Enabling Fluidics, Figure 1 Comparison between optical energy concentration for (**a**) free space and (**b**) a dielectric waveguide. WG = waveguide, n = refractive index

A waveguide relies upon the principles of total internal reflection to confine light within the solid waveguide structure [3]. Though the light is confined to propagate in a single direction, an exponentially decaying component of the optical mode, known as the evanescent field, extends outside the waveguide. The degree of this extension depends on the refractive index contrast between the waveguide and the surrounding media, however is generally on the order of a few 100 nm for visible and near infrared light. The optical gradient in the evanescent field partially polarizes the particle near the waveguide, resulting in an extremely strong gradient force. This serves to attract the particle to the waveguide surface, where the electric field strength is highest. Waveguides for visible light can be fabricated from many types of materials and in different forms. For infrared light, silicon is a better material due to its relatively high transparency in the 1550 nm range and well defined fabrication methods. Planar waveguides are of unique interest for optofluidics for the relatively simple methods for incorporating both microfluidic and optical elements on the same chip.

Optical Forces

There are three types of forces associated with electromagnetic fields, the scattering and absorption forces which account for radiation pressure, and the gradient trapping force. The scattering and absorption propagation forces can be physically described as the momentum transfer associated with the scattering and absorption of a photon from an incident electromagnetic source. For a dielectric particle, these forces can be described as an electromagnetic stress using the Maxwell stress tensor [4]:

$$\boldsymbol{F}_{\mathrm{EM}} = \oint_S \left(\langle \mathbf{T}_{\mathrm{EM}} \rangle \cdot \boldsymbol{n} \right) \mathrm{d}S \tag{1}$$

$$\mathbf{T}_{\mathrm{EM}} = \varepsilon\varepsilon_0 \boldsymbol{E}\boldsymbol{E} + \mu_0 \boldsymbol{H}\boldsymbol{H} - \frac{1}{2}\left(\varepsilon\varepsilon_0 \boldsymbol{E}\cdot\boldsymbol{E} + \mu_0 \boldsymbol{H}\cdot\boldsymbol{H}\right)\mathbf{I} \tag{2}$$

where $\boldsymbol{T}_{\mathrm{M}}$ represents the Maxwell stress tensor and $\boldsymbol{n}$ is the surface normal vector, $\boldsymbol{E}$ and $\boldsymbol{B}$ are the instantaneous electric and magnetic fields respectively, $\mathbf{I}$ is the identity tensor, ε_0 and μ_0 are the electric permittivity and magnetic permeability in vacuum and ε is the dielectric constant of the surrounding medium. It can be shown that the time averaged stress tensor then becomes,

$$\begin{aligned}\langle \mathbf{T}_{\mathrm{EM}} \rangle = \frac{1}{2}\,\mathrm{Re}\Big[&\varepsilon\varepsilon_0 \boldsymbol{E}(r)\boldsymbol{E}^*(r) + \mu_0 \boldsymbol{H}(r)\boldsymbol{H}^*(r) \\ &-\frac{1}{2}\left(\varepsilon\varepsilon_0 \left|\boldsymbol{E}(r)\right|^2 + \mu_0 \left|\boldsymbol{H}(r)\right|^2\right)\mathbf{I}\Big]\end{aligned} \tag{3}$$

where $\boldsymbol{E}^*$ and $\boldsymbol{H}^*$ represent complex conjugates. In Eq. (1) the integration is performed in a surface which encloses the particle of interest and returns the total electromagnetic force on the particle, including scattering, absorption and gradient forces. The latter of these physically results from the temporary polarization of a dielectric particle by the electric field. The instantaneous interaction of the dipole with a non-uniform electric field results in a force directed towards the high-intensity regions of the electric field.

Analytical Simplification: As mentioned above, the mechanism for propulsion in the proposed system is based on the summation of the scattering and absorption forces applied to a particle trapped, expressed most generally through Eq. (1) through Eq. (3) above. We can simplify these equations significantly by considering the case of a Rayleigh particle, as described by Svoboda and Block [7] (amongst others). For such a case we can derive analytical expressions for these forces given by Eq. (4a) and (4b) respectively,

$$F_{\mathrm{scat}} = \frac{8\pi^3 I_0 \alpha^2 \varepsilon_{\mathrm{m}}}{3c\lambda^4} \tag{4a}$$

$$F_{\mathrm{abs}} = \frac{2\pi\varepsilon_{\mathrm{m}} I_0}{c\lambda} Im(\alpha) \tag{4b}$$

where $\alpha = 3V(\varepsilon - \varepsilon_{\mathrm{m}})/(\varepsilon + 2\varepsilon_{\mathrm{m}})$, V is the particle volume, c and λ are the speed and wavelength of light, ε_{p} and ε_{m} are the dielectric constants of the particle and material and I_0 is the incident intensity.

Fluid Mechanics

The details of fluid mechanics on the micro- and nanoscales are well described throughout this encyclopedia and thus to minimize duplication here we will focus primarily on introducing the governing equations relevant to the remainder of our discussion. As is well known fluid motion is governed by the momentum Eq. (5) and continuity equations Eq. (6) shown below [8],

$$\rho\left(\frac{\partial \boldsymbol{v}}{\partial t} + \boldsymbol{v}\cdot\nabla\boldsymbol{v}\right) = -\nabla p + \eta\nabla^2\boldsymbol{v} + f\,, \tag{5}$$

$$\nabla\cdot\boldsymbol{v} = 0\,, \tag{6}$$

where v, t, p, η, and ρ are velocity, time, pressure, viscosity and density respectively and f represents an applied body force. Flow in channels with the low Reynolds number regime (which is almost exclusively the case in nanometer and micrometer scale confined geometries) is dominated by the diffusive transport terms, leading to the Stokes equation:

$$\nabla p = \eta\nabla^2\boldsymbol{v} + f \tag{7}$$

In optofluidic transport we are typically concerned with the interaction of the flow field with the transported species and thus the hydrodynamic quantity of interest is typically the total flow force on the particle. This is described by the integral of the normal component of the total stress tensor, $\mathbf{T}_{\mathrm{f}}$, around the particle boundary given by,

$$\boldsymbol{F}_{\mathrm{FLOW}} = \oint_s \left(\mathbf{T}_{\mathrm{f}}\cdot\boldsymbol{n}\right)\mathrm{d}S \tag{8a}$$

$$\boldsymbol{F}_{\mathrm{FLOW}} = \oint_s \left([p\boldsymbol{I} + \eta\nabla\boldsymbol{v}]\cdot\boldsymbol{n}\right)\mathrm{d}S \tag{8b}$$

where ***n*** is the surface normal. In the absence of any interaction with the confining geometry (which is commonly the case for free space optofluidics, but rarely the case for planar or waveguide based optofluidics) an analytical solution to Eqs. (8a) and (8b) is available in the form of Stokes drag law:

$$F_{\text{stokes}} = 6\pi\eta a U_0 \tag{9}$$

where U_0 is the particle velocity. Note that variants on Eq. (9) have been derived to account for the added influence of the channel side walls on the viscous drag (Faxen's law).

Key Research Findings

In this section we split recent research findings into two sections. In the first of these we will present a series of calculations illustrating the potential velocities achievable through optofluidic propulsion. In the second section we will discuss the trapping stability of a particle in an evanescent field subject to a cross flow.

Propagation Velocity

When this particle interacts with an optical field, a certain percentage of the photons which flow through the system are either scattered (radiated in a random direction) or absorbed when they contact the particle. Each of these photons has a momentum given by Planck's constant multiplied by the frequency, $h\nu$. These scattering and absorption events result in momentum transfer to the particle and a net forward velocity which is proportional to intensity and impeded by fluid drag. By equating the scattering and absorption forces exerted by a Gaussian optical front, Eqs. (4a) and (4b) on a Rayleigh (i. e., sub wavelength) particle with Stokes drag, Eq. (9) we obtain,

$$U_0 = \frac{\varepsilon_{\text{m}} I_0}{6ac\eta}\left(\frac{8\pi^2\alpha^2}{3\lambda^4} + \frac{2I\,m(\alpha)}{\lambda}\right), \tag{10}$$

In Eq. (10) the first term in brackets represents the scattering force and the second the absorption.

Figure 2 shows the computed propagation velocities from Eq. (10) for a (a) silica nano-particle ($\varepsilon_{\text{p}} = 2.4$), which is weakly absorbing, and (b) a gold nanoparticle, which is strongly absorbing ($\varepsilon_{\text{p}} = -80 + 10\text{i}$). From this figure it is apparent that at moderate optical powers, relatively high velocities are possible even at relatively long wavelengths (the scattering velocity scales with $1/\lambda^4$). Note that in the caption of Fig. 2 we refer to the peak intensity used to calculate the above ($0.8\,\text{W}/\mu\text{m}^2$) as being equivalent to 100 mW of power in a 200 nm by 600 nm silicon waveguide. For this comparison we have assumed an optimized system such that the peak in optical intensity occurs directly at the interface between the waveguide and surrounding medium (a technique developed by Ng et al. [9]). This comparison also ignores the influence of the surface on the drag force (see above) and this Eq. (10) is likely to overestimate the actual propulsive velocity for the waveguide system. This result however is accurate for the free space system and can provide some estimates of the expected performance for waveguide based propulsion. Also note that the absorption component of



Optofluidics: Optics Enabling Fluidics, Figure 2 Propagation velocity estimates for Silica (**a**) and Gold Nanoparticles (**b**) on a Silicon Waveguide. U_{abs} and U_{scat} represent the absorption and scattering components of Eq. (10) and U_0 is the summation of the two. Velocities are for calculated for a peak intensity of $0.8\,\text{W}/\mu\text{m}^2$ at 1550 nm. This is approximately equivalent to that obtainable for 100 mW of power in a 200 nm by 600 nm silicon waveguide shown in Fig. 3



Optofluidics: Optics Enabling Fluidics, Figure 3 Optofluidic architecture for waveguide based transport (**a**) diagram of fluid/electro-magnetic coupling at waveguide interface. (**b**) Cross Section of guided mode with arrows showing surface normal electromagnetic forces (Simulation is 3D). (**c**) Cross section image of the magnitude of fluid velocity along with calculated streamlines

velocity for the silica particle results from the imaginary component of the dielectric constant of water at 1550 nm. For smaller absorping particles, such as gold, the scattering force becomes less significant below 100 nm and the absorption forces begin to dominate.

As mentioned above, in a waveguide system, the optical intensity (power/area) is governed by the geometry cross section of the waveguide which can be much smaller than the diffraction limit for a tightly focused free space spot (these calculations are done for the 200 nm tall waveguide shown in Fig. 3 which compares with the diffraction limited spot size which is on the order of 620 nm diameter). As such much lower optical power is required. At the same time the index contrast confines the energy over an indefinite spatial length. As this waveguide is made smaller the intensity increases and with it the net velocity. As such smaller devices have the potential for faster transport, which could impact emerging nanofluidic devices.

Particle Trapping in an Evanescent Field

Although estimates can be made regarding the propagation velocity of a particle once it has been trapped, one of the key questions which must be addressed in order for this to be a translated into a useful technology is the strength of the Lorenz trapping force compared with Brownian motion and the presence of a cross flow. We have examined this here by performing a series of numerical simulations that examine the waveguide/dielectric particle geometry shown in Fig. 3 subject to a pressure driven cross flow. As can be seen in Fig. 3b, the evanescent mode extends outside the waveguide decaying exponentially into the surrounding medium with a portion of it interacting with the particle. For the electromagnetic simulations, Maxwell's equations were solved for the electric and magnetic fields in the waveguide, and the forces on a spherical glass particle were evaluated using Eq. (1). Continuity of the electromagnetic equations are maintained for all internal boundaries, while the surrounding boundaries allow the flux of scattered light, as would be expected in a unbounded fluid medium. The inlet and outlet boundary conditions use the numerical solution from an eigenvalue solver used to determine the guided and evanescent mode profiles.

Simulation results for a glass bead of varying size were evaluated at different positions along the surface of the waveguide. The magnitude of the trapping force on a particle is determined largely by the size and position of the particle relevant to the evanescent field. As seen in Fig. 4,



Optofluidics: Optics Enabling Fluidics, Figure 4 Electromagnetic force on a particle as a function of position. Gradient force calculated for 600 and 400 nm spherical glass particles on a silicon waveguide. A critical maximum in the trapping force is observed for positions ~ 175 nm from the center of the waveguide

for a 600 and 400 nm glass bead, the strongest forces are 200 nm from the center of the waveguide. Note that the forces are directed towards the center of the waveguide, the region of highest intensity (as seen in Fig. 3b). The reason the maximum force does not correspond to the edge of the waveguide surface results from the size of the particle relative to the evanescent field and the radius of curvature of the particle. Smaller particles, and thus those which have a larger radius of curvature have a sharper peaks compared to larger particles. Additionally, the hydrodynamic force as a function of particle position can be considered. In the region from $x = 150$ to $x = 300$, where the critical trapping region would be, the hydrodynamic force on the particle remains constant with respect to position.

Simulations were conducted to determine the relationships describing the electromagnetic and hydrodynamic forces acting on a single sphere in the waveguide geometry. For particles ranging in size from 50 – 600 nm in diameter, the forces in the trapping direction acting on the particle were evaluated. Shown in Fig. 5, the gradient forces at the stable point with respect to size exhibit a near-linear relationship for particle sizes larger than 200 nm. This arises from the positioning of the particle at the edge of the waveguide, thus allowing large portions of the surface area of the particle to sample lower field intensities (in the region beyond the waveguide edge) relative to areas near the waveguide surface, creating a large gradient in the surface force profile. On the other hand, the hydrodynamic force exhibits a non-integer power-law relationship. In the standard stokes drag scenario, the hydrodynamic drag on a particle has a linear relationship with respect to size, but this is in the presence of a uniform velocity field. In the presence of a parabolic flow profile, along with a waveguide geometry that serves to disturb the flow field, it is highly probable that a higher order relation exists in this case.



Optofluidics: Optics Enabling Fluidics, Figure 5 Gradient and Hydrodynamic Forces. Forces plotted for glass particle sizes from 50 to 1000 nm. Forces evaluated at edge of waveguide, as illustrated in Fig. 3

Examples of Application

Please see experimental application article ► optofluidics – fluidics enabling optics which details the use of direct and indirect optical forces in the manipulation of particles for a variety of applications.

Cross References

► Optofluidics - Fluidics Enabling Optics

References

1. Ashkin A (1970) Acceleration and Trapping of Particles by Radiation Pressure. Phys Rev Lett 24(4):156
2. Svoboda K, Block SM (1994) Biological Applications of Optical Forces. Ann Rev Biophys Biomol Struc 23:247–285
3. Saleh DEA, Teich MC (1991) Fundamentals of photonics. Wiley, New York
4. Jackson JD (1975) Classical electrodynamics. Wiley, New York
5. Melcher JR (1981) Continuum electromechanics. MIT Press, Cambridge
6. Gaugiran S, Getin S, Fedeli JM, Colas G, Fuchs A, Chatelain F, Derouard J (2005) Optical manipulation of microparticles and cells on silicon nitride waveguides. Opt Exp 13(18):6956–6963
7. Svoboda K, Block SM (1994) Optical Trapping of Metallic Rayleigh Particles. Opt Lett 19(13):930–932

8. Panton RL (2005) Incompressible Flow. Wiley, New York
9. Ng LN, Luf BJ, Zervas MN, Wilkinson JS (2000) Forces on a Rayleigh particle in the cover region of a planar waveguide. J Lightwave Technol 18(3):388–400

Optofluidics – Techniques for Fabrication and Integration

ROMAN AKHMECHET, DAVID ERICKSON
Sibley School of Mechanical Engineering,
Cornell University, Ithaca, NY, USA
ra224@cornell.edu, de54@cornell.edu

Synonyms

Photofluidic devices

Definition

Optofluidic devices integrate within themselves elements of microfluidics, optics, and electronics. Although methods for fabricating each of the components separately are reasonably well known, difficult challenges exist in developing architectures that enable the integration of all these functionalities onto a single device. Though approaches differ from device to device, the goal is to make fabrication as easy and affordable as possible. In this article we present an overview of the fabrication technologies and integration architectures for optofluidic devices. We will also discuss these techniques in the context of a sampling of the state of the art from the literature.

Overview

Choosing an appropriate fabrication process and integration architecture for optofluidic devices requires the designer to consider a number of different issues ranging from: material restrictions (e. g. optical transparency range, electrical insulation and compatibility with various fluids and functionalization chemistry), desired feature sizes (e. g. are features required on the same scale as the wavelength of light), power consumption, and of course cost (e. g. smaller feature sizes require more elaborate fabrication techniques and more careful handling and treatment of substrates increasing device cost). While these issues have been exhaustively examined independently within the electronics, optics/photonics and fluidics fields, it is unclear what the optimal device structure will be for optofluidics. For example it is reasonably well accepted that for disposable microfluidic devices, polymeric materials and fabrication techniques (such as elastomeric devices fabricated through soft lithography or hard plastic devices fabricated using embossing techniques) are likely to yield the most commercially viable products. This trend towards simplicity conflicts with the complex multilayer lithography and etching techniques commonly used in the electronics and integrated photonics industries. As such it is unclear whether the most fruitful path will be to develop a single fabrication technology that enables the incorporation of each of these elements or whether integration architectures should be developed which enable us to combine, for example, polymeric micro- and nanofluidic structures with silicon photonic devices.

The goal of this article will be to largely explore this question. In the “Basic Methodology” section below we will provide a brief overview of existing fabrication techniques, focusing on those of relevance to optical devices and microfluidics, followed by a discussion on integration techniques. To properly address integration methodology, several examples of optofluidic devices are presented in the “Key Research” section with their challenges and the advantages of techniques that were chosen.

Basic Methodology

As discussed above in this section we will begin by providing a brief review of fabrication techniques for optical and fluidic devices (we focus on these two here as they constitute the most fundamental aspects, electronics will be covered incidentally, but not directly). We will focus primarily on the different sets of tools required and, to a lesser extent, materials required for each. As will be described, the tools are closely interconnected with materials from which the components are made, as well as the sizes of features that are to be included in the optofluidic device.

Techniques for Optical Component Fabrication

Fabrication Procedures

The optical elements of optofluidic devices include such components as waveguides, photonic crystals, optical resonators and active components such as lasers. The order of magnitude of feature size for these elements can range from roughly the scale of the wavelength of light – hundreds of nanometers, to tens of microns or larger. For these smaller features (commonly required in single mode waveguides and photonic crystals for example) techniques such as electron-beam lithography (e-beam) or focused ion beam (FIB) are appropriate. Briefly for e-beam, a focused beam of high energy electrons is used to expose an e-beam resist which can subsequently be developed and the system etched so as to create features of sizes as small as tens of nanometers. Electron beam processes are well developed for silicon on insulator (SOI) type devices and represent a good choice for fabrication of optical waveguides that include smooth bends or circular resonators. In focused ion-beam lithography, samples are bombarded with ions so as to directly etch features into the substrate. An important difference in FIB is that it has a much lower scattering, but a higher chance to damage sensitive electronics though similar feature sizes are available. The ultimate limitation of both e-beam and FIB fabrication procedures is that they are serial in nature and thus while suitable for device prototyping, they are not particularly useful for mass production. Photolithography, on the other hand, allows for much more parallel fabrication once an exposure mask is fabricated. There is a great variety of positive and negative photoresists available to achieve different feature heights. Though only cost effective for mass produced runs, state of the art fabrication lines can now reach feature sizes on the order of 100 nm and below.

Materials

The range of available active and passive optical materials is much too extensive to be described in detail and thus we will focus on the handful which are of broadest interest to optofluidics and separate them into those which are usable in the infrared and visible spectra. Within the former of these silicon specifically, silicon on insulator, tends to be the material of choice, primarily due to the well developed fabrication procedures, simplicity of integration with electronics and high refractive index. The underlying oxide layer serves to isolate the optical components but also as a convenient surface for biochemical functionalization. While generally compatible with most fluids, the conductivity of silicon can lead to some difficulties with electrically driven flow mechanisms such as electrokinetics.

A much more diverse set of materials is available within the visible regime for creating optical elements compatible with fluidics. In most cases devices are fabricated on either a glass or hard plastic base to facilitate photolithography steps and device handling; however techniques borrowed from the flexible optoelectronics communities are becoming more popular. For optical components, silicon nitrides are relatively popular due to the relatively high achievable refractive indices. Commonly however polymeric materials such as SU-8, PMMA and more recently PDMS are preferred due to the relatively easy fabrication procedures (SU-8 devices for example require only simple photolithography and developing steps, whereas silicon nitride devices require more complex etching steps) and slightly higher than glass refractive indices. Though often used to create multimode waveguides for delivering excitation light or capturing emitted light, because the index difference between these polymers and aqueous liquids, it is usually possible to create single mode devices without too much difficulty.

As mentioned above materials processing varies strongly from material to material as well. There are other numerous types or dry and wet etching that work for these different materials, each with its own unique characteristics. For example, reactive ion etches can create well defined, high aspect ratio features with straight, smooth sidewalls in numerous materials, but typically require much more handling and equipment. Wet etches are much simpler but less precise techniques that compatible with both silicon and glass materials. Because etching is time dependent, is it important to properly time the process to achieve appropriate depths. In chemical etching the materials can be layered, so that when the chemical reaches the next layer the process will stop.

In order to create micron scale mirrors or electrical functionality, evaporation of metals such as gold, chrome, titanium and silver are used [1]. The two types of vapor deposition are thermal evaporation, which works by physically boiling material, and sputtering, which includes ion bombardment. Although sputtering works on a much larger variety of materials, it is slower and more expensive than evaporation and, thus, should be used when precision counts or choice of material requires it.

Techniques for Fluidic Component Fabrication

At the onset of modern microfluidics in the early 1990's glasses, quartz and silicon were the materials of choice for microfabrication, primarily due to the well established wet etching and lithography based micromachining techniques developed by the electronics and semiconductor industries. Though silicon based devices found a variety of niche markets, particularly those that benefit from its high thermal conductivity, its high electrical conductivity proved to be a problem for the high voltages required for on-chip electrokinetic transport (as mentioned above). As such the first chips for electrokinetic processes such as capillary electrophoresis were typically constructed from glass which also offered good optical qualities, well defined surface chemistries and a high electroosmotic mobility (i. e. it supports a high ζ-potential). In general however high quality glass is reasonably expensive, at $\$ 4000/\mathrm{m}^2$, and fabrication is very expensive, largely due to the costs associated with establishment and maintenance of clean room facilities. Additionally, usable structures must be thermally bonded to a cover plate made from a similar material at temperatures over 400°C, which precludes the possibility of incorporating a biological agent in to the chip prior to sealing.

As a result of these difficulties with traditional microfabrication materials and techniques, there has been a recent trust to manufacture microfluidic systems and biochips from low-cost polymeric materials such as poly(dimethsiloxane) (PDMS), poly(methylmethacrylate) (PMMA) and others. The primary attractiveness of these materials is that they tend to involve simpler and significantly less expensive manufacturing techniques (e. g. casting, injection and replica molding, or hot embossing), however they are also amenable to surface modification and the wide variety of physiochemical properties allows the matching of specific polymers to particular applications. While the development of these systems has reduced the time from idea to chip from weeks to days, and the per unit cost by a similar ratio, the low thermal conductivities inherent in these materials (0.18 W/mK for PDMS which is an order of magnitude lower than that of glass) retards the rejection of internally generated heat during electroosmosis (Joule heating).

Though there are many microfabrication processes for manufacturing microfluidic systems in soft polymers and hard plastics, one of the most promising is the Soft Lithography and Rapid Prototyping of Masters process developed by Professor Whitesides' group at Harvard University [2]. Through this process complex microfluidic systems can be manufactured in soft elastomer substrates (primarily PDMS) very rapidly and at a fraction of the cost or traditional glass manufacturing. After the initial investment in processing equipment, this technique can reduce the cost per custom microchannel system to several dollars per unit and reduce the lag time from several weeks (or months as outlined above) to 2 or 3 days. Briefly the process consists of producing positive, reusable, masters of the desired microfluidic design on a glass or silicon substrate, by first spin coating a film of photoresist onto the substrate, hardening it through a baking procedure, expositing it to UV light through a transparency mask containing the channel pattern, inducing cross linking of the polymers through a second bake procedure, then dissolving the unexposed portion of the film in a developer solution. PDMS replica molds of the channel design are then prepared by pouring the uncured liquid elastomer over the master and allowing it to cure in a vacuum oven. This yields a negative cast of the microchannel pattern in the PDMS slab. To form the enclosed, sealed chip the PDMS cast is typically plasma treated, aligned, and then placed in direct contact with either a glass substrate or another PDMS slab. Both the lithography mask and the final master can be reused multiple times with PDMS casting to mass-fabricate fluidic layers.

A slight extension of the above involves the use of glass or silicon as mask materials in various soft lithography techniques which can be used in fabrication of fluidic components as well as optical ones. Features as small as 30 nm can be achieved. An example is micro-transfer molding where a mold is filled with a polymer and is pushed against a substrate. The polymer is then cured forming structures on the substrate after the mold is removed. These structures of rectangular cross section can be used as waveguides in optical layers, or walls of microfluidic channels. The main disadvantage of soft lithography is its accuracy limit from thermal deformations.

Photolithography is probably the most widely used technique for making simple microfluidic devices or masters for embossing and casting of polymer devices. A combination of appropriate photoresist and an appropriate developer are needed to fabricate positive or negative relief fluidic channels. Despite its relatively low resolution achievable with photolithography, it is very convenient for channels with features sizes on the order of 2–5 μm or larger. For smaller features e-beam or FIB techniques (see above) are more commonly used. Currently there is a development to move away from placing a physical mask in proximity of the substrate with photoresist and instead use photomask created by a system of high resolution lenses. This will allow photolithography to work on non-planar surfaces.

Sealing of fluidic components to optical/electrical devices can be an issue, particularly when using pressure driven flow. High temperature bonding processes are often undesirable as they can damage electrical/optical devices or any biological functionalization which may be pre-deposited inside devices. Similarly bonding of hard fluidics (glass, silicon) to irregular surfaces is notoriously difficult. Fortunately, the technology has progressed in a direction such that a number of "optofluidically compatible" material systems have been developed. An example is wide use of PDMS because it is easy to bond with glass, silicon or other PDMS layers. Commonly air or oxygen plasmas are used to activate the bonding surface and expose the free oxygen in PDMS. Temperature treatments, such as baking or hot plates, rely on diffusion processes to bond materials. Similarly for PDMS under moderate temperatures, the polymer chains inside the two layers can inter-diffuse between themselves strengthening the bond.

Key Research Findings

Given the well developed fabrication techniques describe above, the key research directions on the fabrication side are focused on developing the techniques which integrate the optical and fluidic layers. Though this will be discussed below in the context of a series of case studies we will also try to provide some global insight in each case. When it comes to choosing appropriate techniques and materials to fabricate these devices, it is important to make decisions based not only on equipment availability, but also on cost. Some of the devices presented below are successful because of their simplicity and cost efficiency. Here we focus on techniques for enabling the fusion of optical and fluidic layers, generally made from different materials, without deforming any of the components and preserving the function of the multilayer device.

Optofluidic Attenuator

The first device we will consider is the optical attenuator presented by Lin Zhu et al. [3]. The device is comprised of two layers, which can be used to reduce the power level of an optical signal in a waveguide. Thus, the two layers are an optical layer that contains straight waveguides with cladding, and a fluidic layer. An opening was made in the top cladding of the waveguides which is filled with a fluid from the fluidic channel on top of it. By changing the refractive index of the fluid occupying the cladding opening, it is possible to change the output power from the waveguides.

The optical layer is manufactured by first thermally growing silicon oxide on a silicon wafer to serve as the lower cladding, and then defining waveguides photolithographically in SU-8. Another photosensitive material serves as the top cladding with an opening defined by a second photolithography process. The fluidic channel is made from PDMS that is cast over a negative resist master fabricated by standard photolithography. To ensure the bonding of PDMS to the top cladding of the optical layer, the device is treated with high power oxygen plasma for 30 s and then baked for an additional 8 h. Experimental results included power output depending on the refractive index of the fluid in the channel and are in agreement with numerical simulations.

The fabrication is based mostly on soft photolithography, which is easy to facilitate and is very cost efficient. The device itself is simple to operate and reproduce. The materials used are completely inert, which is important when using chemically reactive fluids. The sizes of features make what is commonly a complex part of the fabrication process – alignment – relatively simple. Attenuation of optical signals is very sensitive to refractive indexes of the cladding materials. Thus, the main challenge in designing such a device is to allow for fabrication processes which will not only work with materials whose properties are well known, but also guarantee those properties remain relatively constant throughout the sampled volume.

Integration of Nanofluidics with Photonic crystals

A different type of optofluidic device was presented by Erickson et al. [4] and comprised of a silicon photonic crystal integrated with soft-lithography nanofluidics. A photonic crystal is a regular periodic array of varying dielectric constant that exhibits a bandgap (a range of wavelengths which cannot propagate within the structure). In the case of a silicon photonic crystal where the periodicity comprises of a series of nanoholes etched into the base silicon, the output power from the crystal and the range of the bandgap will vary depending on the refractive index of the fluids occupying the wells. The goal of the device developed in this paper was to address individual features within the photonic crystal.

This device consists of three layers: a photonic crystal layer, a nanofluidic delivery layer to deliver proper fluid into the photonic crystal structure, and a microfluidic control level to perform required fluidic manipulations. Photonic crystals have features on the order of a 100 nm and thus require electron-beam lithography for definition. The structure can then be dry etched in silicon-on-insulator substrate. In this case the nanofluidic level (which required similar feature sizes to those in the photonic crystal) was also fabricated in positive relief using e-beam lithography and the microfluidic structures (which had features closer to 10 μm) were superimposed using photolithography. Control fluidic layers were fabricated with standard soft lithography. In order to ensure that at least one channel is delivery layer is aligned with a photonic crystal, the spacing between the photonic structure is constantly varied. Immediately before the assembly of different layers, the whole device was exposed to a short duration air plasma treatment in order to aid with sealing. Figure 1 shows an overview of the device fabrication and integration techniques.

The incorporation of a multilayer microfluidic structure in this device allows for precise control of fluid delivery to the crystal. Thus, experiments require less fluid by volume and can steady state results faster (important for future sensing applications). Further integration with electric components can allow for electrokinetic trapping and other fluidic or sample manipulations. Compared to the previously discussed attenuator, this device requires a number of additional fabrication steps, including bonding between different types of materials, but it achieves versatility beyond its primary function. The final device allows for sub-wavelength usability. It is useful for very localized (sub-wavelength) control and modulation with high refractive indexes, but requires nanoscale flows, which take relatively long time to process.


E-Beam defined pattern
SOI Wafer
Develop Resist
Dry etch to define photonic structure
E-Beam defined pattern
Develop Resist
Dry etch to define nano-fluidics
Photolithography to add microfluidics
Cast and cure PDMS
Photolithography to define valves
Cast and cure PDMS
Remove PDMS
Control Layer
Micro/Nanofluidics Layer
Photonics Layer

Optofluidics – Techniques for Fabrication and Integration, Figure 1 Nanoscale optofluidic integration. Sample fabrication procedure for combining micro- and nanofluidics with nanophotonic structures

Label Free Biosensor

The above two devices functionally integrate optics and fluidics on the micro- and nano-scales respectively however the often cited goal of these optofluidic devices is the integration of binding reactions for biomolecular detection. An example of such a device is the label-free biochemical sensor based on a Mach–Zehnder interferometer developed by Blanco et al. [5]. A biosample occupies a chamber on one arm of the interferometer formed by a multilayer process. A waveguide in the chamber has an evanescent field which extends from it and the speed at which light passes through the waveguide arm depends on the refractive index shift caused by the presence or absence of a binding event at the waveguide surface.

The device is fabricated by bonding two separately prepared parts with multiple layers each. One part includes the interferometer with a waveguide as part of one arm. They are fabricated using photolithography on a silicon wafer. The waveguide surface has to be sufficiently pure in order for the evanescent field to interact with the fluid. Since photolithography usually leaves contaminants on the surface, the waveguide was treated with oxygen plasma. The other part consists of two temporary layers to allow for easy lift off and pealing, and an SU-8 layer on which the inlet and outlet holes are photo-patterned and developed. All of the layers of this part are transparent, so as to facilitate alignment. The materials are dehydrated on a hot plate to ensure good adhesion of the two parts.

Since the device is based on a Mach–Zehnder interferometer, the second arm is used to lower or eliminate external perturbations such as temperature fluctuations. This allows for higher accuracy and detection of smaller concentrations. The adhesion of different layers was good enough to sustain fluid pressure of up to 500 kPa. Several additional integration steps and choice of materials were made in order to satisfy this requirement. In general, this sensing mechanism is used to allow compatibility with complementary metal-oxide semiconductors (CMOS). This property, together with compactness of the device, makes it attractive for further integration with MEMs into a complete lab-on-chip device.

Integration of Fluidics and Semiconductor Lasers

The ultimate degree of optofluidic integration involves the integration of fluidics, passive and active optics, and electronics into a single device. The device presented by Cran-

McGreehin et al. [6] is an example of a device that uses electrical current to create light with wavelength of about 1290 nm. The light is trapped in waveguides and is used to optically move and trap particles in a microfluidic channel. This device can also be used for simultaneous particle detection and manipulation thought scattering and absorption forces. Such integration of microfluidics and semiconductor lasers is not done in distinct components as above. Rather a device is etched and covered with other materials to achieve proper shapes and properties in each part of the device.

The light is emitted from electrically excited layers of quantum dots. The active layer is covered with thermally grown conductive cladding on top and bottom. In order to allow waveguiding, ridges are photo-defined and etched with specific dimensions to support only the zero-order mode. To isolate adjacent waveguides, a layer of SU-8 is added and heated to reflow from the top of the ridges and harden between them. The top electrode for the electrical component is then deposited with an electron beam evaporator through a lift-off mask. The fluidic channel is etched separately to be deeper than the space between the ridges in order to accommodate larger particles. Because it is essential to isolate the pn junction from the fluid, the ridges and the contacts are covered with another layer of SU-8 polymer. This layer is also used to photo-define the walls of the channel. The last step is to deposit a thin metallic layer on the bottom of the channel to prevent particle adhesion. In order to operate, the device requires a relatively large heat sink due to heat generation from electrical currents.

This device allows for exploration of how semiconductor lasers interact with different materials. The experimental data is the power drop when the particle blocks a pair of oppositely positioned lasers. The device itself contains a large variety of fabrication techniques and materials and has a large range of applications. The advantage of this device is the ability to simultaneously manipulate and detect single particles using optical functionality. It is also likely the most prominent example of integration of different components, including electronic ones, directly into the fluidic layer instead of fabrication of different layers followed by their bonding to each other. The advantage of including so much "infrastructure" right on the device (e. g. having optical pressure generated within the microchip as opposed to using an external laser) is largely related to the idea of developing portable devices.

Future Directions for Research

What has inspired initial research in microfluidics is similarly driving the research into optofluidics today. The goal is to make smaller features going from micro- to nano-scales in order to fill the gap between top-down and the bottom-up fabrication techniques [7]. Because most devices consist of multiple planar layers, there is motivation to develop 3-D fabrication or assembly methods for both optical and electrical components. The ultimate goal is an easy and simple technique which works well with a variety of materials and on different scales. The most successful devices up to date rely on fundamental principles of both optics and fluidics in order to avoid as many of components as possible, leaving those devices only with essentials to carry out their functions.

Cross References

- ► Optofluidics – Fluidics enabling optics
- ► Optofluidics – Optics enabling fluidics
- ► Optofluidics – Applications

References

1. Vezenov D, Mayers B, Conroy R, Whitesides G, Snee P, Chan Y, Nocera D, Bawendi M (2005) A low-threshold, high-efficiency microfluidic waveguide laser. J Am Chem Soc 127(25):8952–8953
2. Xia Y, Whitesides G (1998) Soft lithography. Annu Rev Mater Sci 28:153–84
3. Zhu L, Huang Y, Yariv A (2005) Integrated microfluidic variable optical attenuator, Opt Express 13(24):9916–9921
4. Erickson D, Rockwood T, Emery T, Scherer A, Psaltis D (2006) Nanofluidic tuning of photonic crystal circuits. Opt Lett 31(1):59–61
5. Blanco F, Agirregabiria M, Berganzo J, Mayora K, Elizalde J, Calle A, Dominguez C, Lechuga L (2006) Microfluidic-optical integrated CMOS compatible devices for label-free biochemical sensing, J Micromech Microeng (16):1006–1016
6. Cran-McGreehin S, Dholakia K, Krauss T (2006) Monolithic integration of microfluidic channels and semiconductor lasers. Opt Express 14(17):7723–7729
7. Madou M (2002) Fundamentals of microfabrication. CRC, Boca Raton

Ordinary Least Square

► Least Square

Organ Fabrication

► Microfluidic Devices in Tissue Engineering

Organic Material

► Polymer

Organ or Tissue Augmentation

► Microfluidic Devices in Tissue Engineering

Orthorhombic Crystal

► Perovskite

Over/Under/Perfectly-Expanded Nozzle Flow

Definition

A comparison of the theoretical exit pressure for an isentropic nozzle with the level of the ambient back-pressure. For isentropic exit pressures below the ambient, the flow is 'over-expanded'; for isentropic exit pressures exceeding the ambient value, the flow is 'under-expanded' ; when the pressures are matched, the flow is 'perfectly expanded'.

Oxidation/Reduction

► Amperometric Techniques

Oxidation (of Silicon)

Che-Hsin Lin
Department of Mechanical and Electromechanical Engineering, National Sun Yat-sen University,
Kaohsiung, Taiwan
chehsin@mail.nsysu.edu.tw

Synonyms

Thermal oxidation; Oxide growth; Oxide deposition; Silicon dioxide growth

Definition

Oxidation of silicon to create a silicon dioxide layer on the silicon surface can be done either by the thermal growth methods or the undesired native growth process. The process is an adding procedure which adds oxygen to react with silicon to form silicon dioxide on the silicon surface. The process consumes silicon during the oxidation procedure. In general, the oxide layer can be grown either by wet or dry oxidation processes in a furnace at a temperature of 750 – 1100 °C. The reaction can be expressed as: $Si_{(s)} + O_{2(g)} \rightarrow SiO_{2(s)}$.

Overview

Silicon dioxide is a form of pure glass with a melting temperature of 1730 °C which is similar to fused silica. It exhibits excellent dielectric properties and has a good adhesion to silicon such that silicon dioxide is ideal to be used as a dielectric or barrier layer. Silicon dioxide is also very useful in the MEMS and semiconductor industry due to its excellent material properties. A grown oxide layer is conformal on the silicon surface, which makes it an ideal surface coating or passivation layer for MEMS structures. The electric resistivity is up to 1×10^{20} Ω. cm and the energy band gap is around 9 eV. A well-grown silicon oxide layer can sustain a high electric field of up to 10^9 V/m without breakdown [1]. Further more, the ease of formation and its excellent interface with the underlying silicon material make it the most popular thin film in VLSI technology. Essentially, silicon is reactive to oxygen at room temperature such that most silicon exists in the form of silicon dioxide like quartz sand in nature. In this regard, oxidation of silicon occurs immediately to form amorphous silicon dioxide film by exposing a silicon surface to oxygen in atmospheric environment. Silicon dioxide is a dense material that fully covers the silicon wafer to prevent the inner silicon from further oxidation. The thickness of this native oxide will reach to an upper limit of about 40 Å even over a long period of time. The native oxide layer grown from air is not uniform and is usually considered a contaminant in semiconductor processing. This native oxide can be simply removed in seconds using dilute HF solution.

Alternatively, a thermally grown oxide layer is thickness-controllable and has various applications in the semiconductor industry. The thickness ranges for thermal oxide layers may vary, depending on the particular application. For example, the thickness for an oxide capacitor dielectric is as thin as several angstroms but the thickness of a field oxide layer can be up to several micrometers. Since the grown oxide layer will fully cover the silicon surface to prevent it from further oxidation, it is common to elevate the temperature to drive the oxidant molecules to diffuse across the formed oxide layer to continue the oxidation process. In general, an oven or a furnace with high-purity oxygen supplied is usually adopted for the oxidation process. The oxidant can be either pure oxygen gas or water vapor. If the growth procedure occurs with dry oxygen, then the oxidation process is called *dry oxidation*. If the oxygen is introduced to the reaction chamber with water vapor, then the oxidation process is known as *wet oxidation*. The reaction mechanism of these two oxidation approaches is different such that the growth rate and the grown film quality of these two approaches are also different. In general, the wet oxidation process is faster than the dry oxidation process but the density of the grown oxide layer obtained is lower when using the wet oxidation process. Higher temperature will significantly increase the growth rate of the oxide layer. The equipment for performing the oxidation processes, a mathematical model for evaluating the growth rate and a well-known pattern of bird's beak effect in local oxidation of silicon (LOCOS) process are described in this entry.

Basic Methodology

Oxidation Modeling

Silicon dioxide is usually grown by consuming silicon during oxidation process at high temperature from 750 to 1100 °C. Figure 1 shows the basic process for the oxidation of silicon. For successive oxidation, oxidants must diffuse across the formed oxide layer then react with silicon at the SiO_2/Si interface. The chemical reactions for both dry and wet oxidation processes can be described as follows:

$$\text{Dry: } Si_{(s)} + O_{2(g)} \rightarrow SiO_{2(s)}$$

$$\text{Wet: } Si_{(s)} + 2H_2O_{(g)} \rightarrow SiO_{2(s)} + 2H_{2(g)}$$

Apparently, silicon is consumed to form silicon dioxide in both the dry or wet oxidation process. The thickness of the silicon consumed is around 0.44 of the total oxide thickness. This value can be simply calculated using the following equation:

$$\frac{t_{Si}}{t_{SiO_2}} = \frac{V_{Si/mole}}{V_{SiO_2/mole}} = \frac{M_{Si}/\rho_{Si}}{M_{SiO_2}/\rho_{SiO_2}} = \frac{28.09(g/mole)/2.33(g/cm^3)}{60.08(g/mole)/2.21(g/cm^3)} \approx 0.44$$

where t is the thickness, V is the volume, M is the molecular weight and ρ is the material density. The growth rate of oxide depends on the parameters for the oxidation process such as temperature, gas pressure, oxidizing condition (wet or dry), silicon crystal orientation and the dopant concentration in silicon. The model for oxide growth on silicon was first described by Deal and Grove in 1965 [2]. The Deal–Grove model describes two growth stages of the linear stage and the parabolic stage during oxidation. Figure 2 illustrates the one-dimensional model for the oxidant flux from the gas phase to the silicon surface during thermal oxidation. Three first-order equations describing the three series parts of the sample fluxes, i. e., F_1, F_2 and F_3, in the one-dimensional model are presented in Eqs. (1)–(3), where F_1 is the gas transport flux in number of molecules



Oxidation (of Silicon), Figure 1 The basic process for the oxidation of silicon



Oxidation (of Silicon), Figure 2 Flux model for oxidant diffusion from the gas phase to silicon surface during thermal oxidation

per square centimeter per second, F_2 is the diffusion flux through the oxide layer and can be expressed using Fick's first law and F_3 is the reaction flux at the SiO_2/Si interface:

$$F_1 = h_G(C_G - C_S) \tag{1}$$

$$F_2 = -D\frac{\partial C}{\partial x} = D(\frac{C_0 - C_i}{x_0}) \tag{2}$$

$$F_3 = k_s C_i \tag{3}$$

where h_G is the mass transfer coefficient (molecules per cm^2 s), C_G is the concentration of oxidant, C_S is the concentration at the surface, D is the oxidant diffusivity in the oxide (cm^2/s), C_0 and C_i are the concentrations at the two interfaces, x_0 is the oxide thickness and k_s is the reaction rate constant (cm/s). The concentration of the oxidant just inside the oxide surface C_0 and C_S can be related using

Henry's law:

$$C_0 = \mathrm{H}P_\mathrm{S} \tag{4}$$

where H is Henry's constant and P_S is the partial pressure of oxidant at the surface. From the ideal gas law, $PV = NkT$, Eq. (4) can be expressed as

$$C_0 = \mathrm{H} \times kT\left(\frac{N_\mathrm{S}}{V}\right) = \mathrm{H}(kTC_\mathrm{S}) \tag{5}$$

where the subscript s denotes at surface. Rearranging Eq. (5) will give

$$C_\mathrm{S} = \frac{C_0}{\mathrm{H}kT} \tag{6}$$

where k is the Boltzmann constant (1.38×10^{-23} J/K) and T is the temperature in K. C^* is defined to be the oxidant concentration in the oxide that would be in equilibrium with the bulk gas pressure P_G, which is known:

$$C^* = \mathrm{H}P_\mathrm{G} = \mathrm{H}(kTC_\mathrm{G})$$

$$\text{then } C_\mathrm{G} = \frac{C^*}{\mathrm{H}kT} \tag{7}$$

Substitution of Eqs. (6) and (7) into Eq. (1), leads to the result that

$$\begin{aligned} F_1 &= h_\mathrm{G}\left(\frac{C^*}{\mathrm{H}kT} - \frac{C_0}{\mathrm{H}kT}\right) \\ &\equiv \frac{h_\mathrm{G}}{\mathrm{H}kT}\left(C^* - C_0\right) \equiv h\left(C^* - C_0\right) \end{aligned} \tag{8}$$

where $h = h_\mathrm{G}/\mathrm{H}kT$, which is a large value because experimental results show that wide changes in gas flow rates in oxidation furnaces, changes in the spacing between wafers on the carrier in the furnace and changes in the wafer orientation make little difference to oxidation rates. Under steady-state conditions, mass must balance such that the three flux equations representing the oxidation process must be equal. Thus $F_1 = F_2 = F_3$. Solving the two unknowns C_i and C_0 from the two equations of $F_1 = F_2$ and $F_2 = F_3$, then we have

$$C_i = \frac{C^*}{1 + \frac{k_\mathrm{s}}{h} + \frac{k_\mathrm{s}x_\mathrm{ox}}{D}} \tag{9}$$

$$C_0 = C^*\left(1 + \frac{K_\mathrm{s}x_\mathrm{ox}}{D}\right) \tag{10}$$

Substitution of Eq. (9) into Eq. (3) leads to

$$F(= F_1 = F_2 = F_3) = \frac{k_\mathrm{s} \cdot C^*}{1 + \frac{k_\mathrm{s}}{h} + \frac{k_\mathrm{s}x_\mathrm{ox}}{D}} \tag{11}$$

Let M be the number of molecules of the oxidant in a unit volume of the oxide. The rate of the thickness change of the oxide layer with time is then given by oxidizing flux divided by the number of molecules M of the oxidizing species (O_2 or H_2O) that are incorporated into a unit volume of the resulting oxide:

$$\frac{\mathrm{d}x_\mathrm{ox}}{\mathrm{d}t} = \frac{F}{M} = \frac{k_\mathrm{x} \cdot C^*}{M\left(1 + \frac{k_\mathrm{s}}{h} + \frac{k_\mathrm{s}x_\mathrm{ox}}{D}\right)} \tag{12}$$

where $M = 2.2 \times 10^{22}\ O_2/\mathrm{cm}^3$ for the dry oxidation process and $M = 4.4 \times 10^{22}\ H_2O/\mathrm{cm}^3$ for the wet oxidation process. Note that $M = \text{density}/(\text{Avogadro's number} \times \text{molecular weight of } SiO_2)$. Take the boundary condition of $x_\mathrm{ox} = x_i$ at $t = 0$. The oxide growth kinetics can be obtained by integrating Eq. (12) from an initial oxide thickness x_i to a final thickness x_ox. The result is described as

$$\frac{x_\mathrm{ox}^2}{B} + \frac{x_\mathrm{ox}}{B/A} = (t + \tau) \tag{13}$$

where

$$A = 2D\left(\frac{1}{k_\mathrm{s}} + \frac{1}{h}\right), \quad B = \frac{2DC_\mathrm{A}}{M} \quad \text{and } \tau = \frac{x_i^2 + Ax_i}{B}$$

The terms B and B/A can be referred to as the parabolic and linear rate constants for describing the oxide growth kinetics. The physical meanings of the rate constants B and B/A are the oxidant diffusion and interface reaction rate, respectively. The corresponding values for B and B/A for dry and wet oxidation of ⟨111⟩ silicon are plotted in Fig. 3. For ⟨100⟩ silicon, these values should be divided by 1.68. These expressions are better fit for the cases of a very



Oxidation (of Silicon), Figure 3 Plot of B and B/A versus temperature for dry and wet thermal oxidation of ⟨111⟩ silicon thin oxide layer and in dry O_2 conditions. Solving Eq. (13) leads to the relationship between the oxide thickness and the growth time:

$$x_{\mathrm{ox}} = \frac{A}{2}\left\{\sqrt{1 + \left[\frac{t+\tau}{A^2/4B}\right]} - 1\right\} \qquad (14)$$

Considering two limiting cases of $t \to 0$ (small x_{ox}) and $t \to \infty$ (large x_{ox}), we have the following expressions corresponding to Eq. (14):

$$x_{\mathrm{ox}} \to \frac{B}{A}t \text{ when } t \to 0$$

and

$$x_{\mathrm{ox}} \to \sqrt{Bt} \text{ when } t \to 0$$

It is clear that the thickness of the grown oxide layer varies linearly with time at the initial stage of oxidation. In this stage, the oxide growth rate is controlled by the reaction occurring at the SiO_2/Si interface and is called the *reaction rate-controlled region*. The linear stage of oxide growth is valid up to about 150 Å of oxide thickness [3]. The growth of the oxide layer slows down after the linear stage because the oxidant must diffuse across a longer distance to reach the interface where the oxidation reaction occurs. The equation generates the shape of a parabola such that it is called the parabolic stage. In the parabolic stage, the growth rate of oxide is controlled by the mass transportation of the oxidant and is called the *diffusion-controlled region*. Figure 4 illustrates the general curve for both the linear and parabolic stages for dry oxidation at 1100 °C [4]. It is noted that the linear stage is only at the very beginning of the thermal oxidation process.

In practical applications, it is not necessary to calculate the thickness of the grown oxide layer using the kinetic model described above. Users can simply obtain the approximate thickness from a chart which plots the oxide thickness for oxidation versus temperature and time, as an example shown in Fig. 5. Another simple way to estimate the thickness of the grown oxide layer is to use the well-developed simulator available on the internet [5]. In addition, the dopant concentration in silicon is also a factor that influences the growth rate of oxide. Here also a minor parameter which may affect the oxide growth rate is doping during the oxidation process. In general, heavily doped silicon oxidizes at a faster rate than a lightly doped substrate. In the parabolic stage, boron doping will oxidize faster than phosphorus. However, the growth rate shows little difference in the linear rate constant between boron and phosphorus doping [6].



Oxidation (of Silicon), Figure 4 Linear and parabolic stages for dry oxidation process at 1100 °C



Oxidation (of Silicon), Figure 5 The thickness of a grown oxide layer for different temperature and time

In summary, the growth of thermal oxide follows a linear growth stage up to about 150 Å, followed by a slower parabolic growth stage. The chemical reaction for the thermal oxidation of silicon consumes silicon and oxidant and the growth rate of the oxide layer is faster when using wet oxidation. Factors including dopant concentration, crystal orientation, pressure and temperature may affect the oxide growth rate during oxidation.

LOCOS Process

The abbreviation LOCOS stands for *local oxidation of silicon*, in which selective areas on a wafer are oxidized for electrical insulation purposes in semiconductor technology. This process is used for isolating two adjacent devices with a feature size of greater than 0.25 μm.



Oxidation (of Silicon), Figure 6 (**a**–**d**) Schematic of a typical LOCOS formation process. (**e**) SEM image of a LOCOS structure. Note that the silicon nitride layer on the right-hand side was stripped and a polysilicon layer has been deposited on top of the structure to provide better contrast in the image. (Image courtesy of J. Bravman, Stanford University.)

Figure 6 presents a simplified schematic for the LOCOS process. A deposited silicon nitride layer is patterned and etched to expose the selective area for the oxidation process. The patterned Si_3N_4 layer serves as the oxidation barrier (Fig. 6a–c). There is a slight lateral growth of the oxide beneath the nitride oxidation barrier because the oxidants move in all directions when diffusing through the grown oxide. Since the oxidation is an adding procedure and the grown oxide is thicker than any silicon consumed, the oxide grown beneath the nitride layer serves to push up the nitride edge (Fig. 6d). The LOCOS process results in a non-planar Si/SiO_2 interface between the nitride oxidation barrier and oxidized regions. This phenomenon is known as the *bird's beak effect* due to its shape. The bird's beak effect is an undesired by-product of LOCOS processes since it increases the area required for building a semiconductor device. Figure 6e illustrates a SEM image showing the cross-section of a LOCOS process, the bird's beak shape being clearly observed in the image.

Furnace Equipment and Oxidation Processes

Furnace equipment serves as a workhorse in thermal processing and is among the simplest type of processing equipment in the semiconductor industry. The equipment is conceptually constituted of an oven capable of temperatures from 600 to 1200 °C and a simple gas distribution system capable of introducing the oxygen or water molecule oxidants. Since the growth rate of the oxide layer is highly dependent on the temperature, precise temperature control is essential for oxidation furnaces. Modern furnaces are easy to handle up to several hundred 8 in. wafers, with a temperature uniformity of ±0.5 °C [7]. There are three basic types of furnace, horizontal furnace, vertical furnace and rapid thermal processor (RTP), used for thermal processing. Figure 7 shows two images of a conventional horizontal furnace and a RTP chamber. Simple construction and ease of maintenance are the major advantages of the horizontal furnaces such that they are popular in academic institutes and industries which require only small production volumes. The horizontal furnace is so named because of the horizontal position of the quartz tube where wafers are located and heated. This furnace was largely replaced in the early 1990s by the vertical furnace in the semiconductor industry, mainly because the vertical construction is easier to automate, has improved operator safety and reduces particular contaminations [8]. Oxidation processes operated in the horizontal and vertical furnaces are batch processes, which are capable of processing large quantities of wafers (tens to 200 wafers) in one process cycle. The furnace process is considered a hot-wall procedure such that it requires more thermal budget for heating the furnace.

Figure 8 illustrates schematically the setup of a typical oxidation furnace which shows the conceptual configurations for both the dry and wet oxidation processes. The main body of the system is a quartz process tube surrounded by a resistance heating element which can be controlled to produce multiple heating zones. It is common to form three to seven symmetric hot zones over the process tube. The temperature zones thus formed facilitate control of the furnace tube to attain a flat zone near the middle of the tube where the thermal oxidation takes place. The outer zones are designed to help compensate for heat losses out of the ends of the tube. The wafers are normally loaded into the furnace on quartz *boats* which hold 10–50 wafers in parallel. The boats are carried into the center section of the hot zones by the operator or the loading system. The wafers are normally loaded at a moderate temperature (600 – 800 °C) in order to prevent crystallographic defects caused by large thermal gradients across the wafers; thermal budget for this process can be saved as well. Nowa-



Horizontal diffusion furnace
Photo courtesy of NOEL Technologies

RTP Chamber
Photo courtesy of Applied Materials, Inc

Oxidation (of Silicon), Figure 7 Images of a conventional horizontal furnace (left) and a RTP chamber (right)


silicon wafer
wafer boat
To exhaust
Process tube
resistance heaters
MFC
HCl
O_2
N_2
N_2
heated
gas line
water
water
bubble
heater
O_2
heater
Reactor
H_2
Boiler/Bubbler system
Flush system
Pyrogenic system
Dry oxidation
Wet oxidation

Oxidation (of Silicon), Figure 8 Schematic for the conceptual construction of an oxidation furnace

days, these furnaces are most commonly operated at atmospheric pressure. However, if necessary, one is able to increase the tube pressure to increase the growth rate of oxide film.

Dry Oxidation

The furnace structure for the dry oxidation process is simple and straightforward. Usually, high-purity oxygen gas is used to oxidize silicon. Nitrogen gas in the oxidation system is used as the process gas during system idle, temperature ramping, wafer loading steps and chamber purging, because nitrogen does not react with silicon at the processing temperature. In dry oxidation, the process gas is usually introduced into the furnace with a trace amount of hydrogen chloride gas. The existence of chloride ions during oxidation is very important because chloride ions react with the mobile metallic ions, such as sodium ions, to form immobile chloride compounds. The undesired oxide charge occurring at the Si/SiO_2 interface can be neutralized by the use of HCl gas. In addition, the existence of hydrogen chloride will also allow some chlorine atoms to be integrated into the oxide film and bind with silicon at the silicon–oxide interface. This process minimizes the number of dangling bonds and improves IC device reliability. Another important advantage of adding chloride ions to the thermal oxidation process is that they tend to increase the oxidation growth rate by about $10-15\%$ [9]. However, the concentration of chlorine ions should not be high (usually $< 3\%$); otherwise the electric properties (e. g., bias voltage) of the electronic device would become unstable. Instead of using toxic and corrosive HCl gas, chlorine compounds such as dichloroethylene (DCE) or trichloroethylene (TCE) can be used to introduce the chlorine ions into the process tube [10]. Oxide films grown by dry oxidation have better quality than films grown by wet oxidation. Therefore, high-quality thin oxide layers such as gate oxide, screen oxide or pad oxide are usually grown using the dry oxidation process.

Wet Oxidation

The wet oxidation process uses water molecules instead of dry oxygen as the oxygen source to oxidize silicon. As a matter of fact, water molecules contact the silicon furnace in a normal wet oxidation process. Water molecules dissociate at high temperature and form hydroxide (HO) prior to reaching the silicon surface. Hydroxide has faster diffusion mobility in silicon dioxide than pure O_2, which explains why wet oxidation has a higher growth rate than dry oxidation. Wet oxidation is used to form thick oxides such as the LOCOS oxide, masking oxide and field oxide. As shown in Fig. 7, several systems have been used to deliver water vapor into the process tube. The boiler system is the simplest setup which vaporizes ultra-pure water then drives the water vapor in to the process tube via heated gas lines. However, it is difficult to have precise control of the vapor flow with this method. In addition, the water in the boiler is not *fresh* after a long boiling procedure and contaminants may be dissolved in the water. A modified setup is called a bubbler system which flows nitrogen gas into a hot water bath to generate wet nitrogen bubbles and carry vapor into the process tube. This scheme is the most commonly adopted in academic fields due to its simple structure and more precise flow control than a boiler system. The flush system is an alternative choice for introducing water vapor in to the process tube. This system uses small water droplets on a quartz hot plate, which vaporizes the water. The vaporized steam is then carried in to the process tube by flowing oxygen gas. However, this method has the problem that the steam generation is not a steady process. In order to have better control of the vapor flow rate, a pyrogenic system called *Dryox* was developed, which burns hydrogen gas to generate water vapor right at the inlet port of the process tube. The vapor flow can be precisely controlled since no liquid and vapor handling is required in this system. However, it needs extreme care to handle this process since hydrogen gas is flammable and explosive. The pyrogenic reaction is operated at a temperature of about 400 °C at which hydrogen automatically reacts with oxygen and forms water vapor. The typical mixing molar ratio for hydrogen and oxygen is $1.8:1$ to $1.9:1$, in order to completely consume the hydrogen gas [9]. Otherwise, hydrogen can accumulate inside the process tube and cause an explosion. A burn box and a scrubber system for exhaust gas treatment are necessary for operating a pyrogenic system.

Rapid Thermal Process (RTP)

The rapid thermal process (RTP) is a method which heats a single wafer to a temperature range of $400-1300\,°C$ in a very short time under atmospheric conditions or at low pressure. This process is usually referred to as rapid thermal oxidation (RTO). The RTP has a gas handling system, an optical pyrometer for fast temperature measurement and a computer for controlling process operation. In order to achieve this fast heating process, a tungsten halogen lamp array located nearly at the top and bottom of the wafer is used as the radiant heating source. The temperature ramp up and down in a furnace is typically about $20\,°C/min$ or less. Alternatively, the RTP can incorporate a fast-heating system which provides ramp-up rates up to $250\,°C/min$. In order to keep the temperature uniformity across the reaction surface, the RTP usually treats a single wafer at a time. The wafer-to-wafer uniformity of a RTP system is also better than that of a conventional furnace system. The silicon wafers are heated by selectively absorbing radiation from the lamps, which produce short-wavelength radiation. The energy from the lamps is mainly absorbed by the silicon but not the chamber wall such that the RTP is considered as a cold-wall process. In this manner, heat-generated contaminants from the chamber wall can be reduced. The RTP also uses less thermal budget than a furnace system but the throughout is an issue. More importantly, the oxidation process achieved using the RTP can minimize dopant movement in wafers due to the shorter process time. This advantage makes the RTP ideal for processes like the barrier-layer formation and the oxide reflow process.

Future Directions for Research

Oxidation processes have been studied for more than 50 years and they still attract lots of interests from researchers who are working in this area. For example, in order to prevent gate leakage and dielectric breakdown, growth of thinner and denser dielectric layers with high dielectric constant for gate structures is an ongoing trend. The RTP will play a more important role in the semiconductor process since it offers better process control, less thermal budget, less processing time and better wafer-to-wafer uniformity. The RTP incorporated with on-line film monitoring, rapid thermal annealing and even rapid thermal chemical vapor deposition (RTCVD) processes has shown its potential for fabricating high-quality thin films with various material choices. Finally, an automation system to handle the multi-function RTP system is essential for improving the throughput of this system.

Cross References

► Rapid Thermal Oxidation (RTO)

References

1. DiMaria DJ, Arnold D, Cartier E (1992) Degradation and breakdown of silicon dioxide films on silicon. Appl Phys Lett 61:2329–2331
2. Deal BE, Grove AS (1965) General relationship for the thermal oxidation of silicon. J Appl Phys 36:3770–3778
3. Ganem JJ, Battistig G, Rigo S, Trimaille I (1993) A Study of the Initial Stages of the Oxidation of Silicon Using O_{18} and RTP. Appl Surf Sci 65/66:647–653
4. Quirk M, Serda J (2001) Semiconductor manufacturing technology. Prentice-Hall, Inc., New Jersey
5. http://www.lelandstanfordjunior.com/oxcalcfaq.html
6. Choi SS, Numan MZ, Chu WK, Irene EA (1987) Anomalous oxidation rate of silicon implanted with very high doses of arsenic. Appl Phys Lett 51:1001–1003
7. Plummer JD, Deal MD, Griffin PB (2000) Silicon VLSI technology: Fundamentals, Practice and Modeling. Prentice-Hall, New Jersey
8. Singer P (1997) Furnaces evolving to meet diverse thermal processing needs. Semiconduct Int 20:84–88
9. Xiao H (2001) Introduction to semiconductor manufacturing technology. Prentice-Hall, New Jersey
10. Higashitani M, Hikazutani K (1997) Semiconductor device manufacturing method including dry oxidation, US Patent 5,637,528

Oxide Deposition

► Oxidation (of Silicon)

Oxide Growth

► Oxidation (of Silicon)

Oxides

► Non-Metallic Inorganic Materials

Packaging (and Wire Bonding)

MU CHIAO
Department of Mechanical Engineering,
University of British Columbia, Vancouver,
British Columbia, Canada
muchiao@mech.ubc.ca

Synonyms

Electronic packaging; IC packaging; MEMS packaging

Definition

Packaging provides electrical or mechanical access to microdevices from the outside world. Packaging also provides protection to microdevices from being damaged by the elements, such as dust, moisture and chemicals from the environment.

Wire bonding is a technology that connects microdevices to the outside world electrically using small metal wires.

Overview

Historically, packaging technology was developed by the integrated circuit (IC) industry. When semiconductor microdevices such as transistors are fabricated on a semiconductor wafer, electrical signals can only be accessed through many micrometer-sized metal lines and contacts using specialized equipment such as a probe station, equipped with an optical microscope and micromanipulators with fine tungsten needles. In order to provide low cost, general access to the microdevices, semiconductor wafers are first diced into small chips (or dies) and small metal wires are used to connect the metal contacts to a *carrier case*. The carrier case has millimeter-sized pins that can be accessed using standard circuit boards.

In IC packaging, the carrier case also provides a moisture barrier. Often, failure in a microdevice is the contact between the metal wires and the metal contacts on the substrate due to moisture-induced corrosion. For microelectromechanical system (MEMS) devices, moisture presents more of a threat than for conventional IC devices [1]. Many micromechanical MEMS components (such as a microcantilever beam) are positioned a few micrometers from the substrate. Moisture condensing on the surface of the substrate will pull down the MEMS devices due to surface tension. The micromechanical component will no longer be functional.

For microfluidic devices, packaging not only provides electrical access to the metal electrodes in the microchannels, but also provides mechanical access. Small tubing is used to connect the fluid ports on the microfluidic device to syringe pumps or other external devices.

Wire bonding is a technology that uses small gold or aluminum wires with a diameter around 20 to 50 μm to build electrical connections to the MEMS/IC devices. The wires are fed through a small aperture on the tip of an ultrasound actuator (or horn). The tip presses the wire to the metal contact surface on the device substrate. Ultrasound energy is applied to vibrate the tip, making the wire rub against the metal contact surface. The vibration-induced friction can (1) create a clean interface between the wire and the metal surface and (2) provide thermal energy that bonds the wire to the metal surface.

Basic Methodology

DIP (Dual In-Line Package)

DIP technology uses moisture-resistant plastic compounds to encapsulate MEMS/IC devices [2]. As shown in Fig. 1a (Courtesy of Shinko Electric Industries Co. Ltd), the two row of pins commonly seen in IC devices that extended out from the plastic body are used for electronic connections, hence the term *dual in-line*.

After IC devices are manufactured on a substrate wafer, a dicing saw is used to break the wafers into smaller chips. The chips are then bonded to a metal frame (called a lead frame) using epoxy. The lead frame is often made of $\mathrm{Cu-Ni-Fe}$ alloys with a thermal expansion coefficient matched with that of the silicon substrate as well as of the plastic compound. Wire bonding is used to connect con-



Packaging (and Wire Bonding), Figure 1 (**a**) Cross-section of a DIP package; (**b**) exploded view of a QFP package

tact pads on the device to the lead frame. The device (and the lead frame) is then put into a mold. The plastic compound, with a thermal expansion coefficient matched with silicon, is molded around the device/lead frame to form a protective case.

Many other variations of DIP technology are readily available, such as SH-DIP (shrink DIP), SIP (single in-line package), SOP (small out-package) and QFP (quad flat pack, as shown in Fig. 1b (Courtesy of Shinko Electric Industries Co. Ltd)). The basic techniques are the same as DIP but the variants provide different form factors and different arrangement of the pins.

Wafer Bonding

MEMS devices need to be separated from the substrate using a wafer dicing machine before they can be packaged. However, unlike IC devices, water used in the dicing operation will destroy micromechanical components. Moreover, DIP technology cannot be used since the molding process will also destroy the micromechanical part of the MEMS devices.

The wafer bonding technique has been used to encapsulate MEMS devices before the dicing process. Wafers (silicon or glass) with recessed microcavities are used to bond to the MEMS device wafer. The microcavity provides a protection cap to the micromechanical component. The hermetic sealing between the bonded wafers will prevent water (during dicing operation) from coming into the cavity. It will also delay moisture diffusion from the environment into the cavity. Furthermore, the strength of the sealing will need to be high enough to sustain the subsequent molding in a DIP process.



Packaging (and Wire Bonding), Figure 2 Ultrasound horn for wire bonding

Anodic Bonding

Anodic bonding has been widely used to form a pressure reference chamber in silicon pressure sensors. Borosilicate glass wafers with a thermal expansion coefficient matched with silicon are often used to bond with silicon wafers using a strong electric field and high temperature. The glass wafer is first chemically etched or sand blasted to form small cavities. Each cavity will accommodate one or more MEMS devices. The glass wafer is made contact with a silicon surface on a hot plate at 400 °C. An electric field is applied between the glass and the silicon such that sodium ions drift away from the glass–silicon interface.



Packaging (and Wire Bonding), Figure 3 Flip-chip technology for electric interconnection

Dissolved oxygen in the glass moves towards the glass–silicon interface and forms silicon dioxide that bonds the silicon surface and glass wafer (also silicon dioxide).

Silicon–Silicon Wafer Bonding

A clean and polished silicon wafer can be bonded to another silicon wafer at room temperature [3]. Two bonding mechanisms exists: (1) hydrophilic silicon surfaces will allow hydrogen bonds to form between two wafers with thin silicon dioxide layers and (2) hydrophobic silicon surfaces will allow van der Waals interactions between two clean silicon surfaces. Thermal annealing at high temperature ($> 1000\,^\circ$C) is then required to permanently bond the silicon wafers.

Wafer Bonding with Intermediate Layers

Wafers can be bonded using intermediate layers such as metals to form hermetic seals. Polymers, in general, do not provide water-tight sealing, and are hence less important in the field of MEMS packaging. Soft metals such as indium can be bonded with silicon with a gold passivation [4]. Aluminum has been used to bond with silicon dioxide [5] and silicon nitride [6] to form hermetic seals.

Fluid Interconnects for Microfluidic Devices

In Lab-on-a-Chip applications, not only electrical, but also mechanical access (fluids) needs to be realized to the outside world. Flexible tubing such as polyimide tubes is often used to connect the small opening in microfluidic chips [7]. The sealing between the tube and the device opening has to be leak-tight. Most methods involve the use of placing a tube into the small fluid access via and sealants, such as polysiloxane [14] or polydimethylsiloxane [8], are then poured in to form seals. However, the sealants must not clog the tubing.

Many fluid interconnect techniques have been demonstrated to address the issues with the blocking of the tubing as a result of sealant application. These methods include the use of polymer membranes that prevent the seal from clogging [9] and the use of thermal shrink plastic tubing [10]. The published methods have been demonstrated in research and academic settings; much is still needed to be done for industry-relevant scale [15].

Electrical Interconnection

Wire bonding has been used in IC packaging for many years. Ultrasound energy is used to bond small metal wires on the metal pads on silicon wafers. As shown in Fig. 2a (Courtesy of Dr. I.W. Qin, Advanced Packaging, PennWell, Inc.), an ultrasound horn has a small opening at its tip. A small metal wire is fed through the opening, as shown in Fig. 2b (Courtesy of Dr. I.W. Qin, Advanced Packaging, PennWell, Inc.). The horn then makes contact with the surface and bonds the wire to the surface using ultrasound energy. The pitch size is often determined by the precision of the ultrasound horn placement, the size of the ultrasound horn and the size of the metal wires. As IC and MEMS I/O densities increase, it is becoming more and more challenging for wire bonding technology to meet the need of high-density I/O.

Other electric interconnection techniques such as wafer bumping and *flip-chip* bonding have emerged [11]. As shown in Fig. 3 (Courtesy of Amkor Technology, Inc.), small metal balls (Ag/Sn or Sn/Pb) are directly electroplated on the metal pads of the device chip. The chips are then "flipped over" and bonded to a printed circuit board (PCB) or a substrate with prefabricated metal connections. An epoxy underfill is then used to fill the space between the chip and the PCB. A plastic compound is then molded over the chip for protection.

Packaging Reliability and Testing

A major characteristic of a MEMS or IC package is reliability. One often asked question is "how long will the device be operational"? From a packaging perspective, the protection and electrical/mechanical interconnection must withstand the elements. For example, for an accelerometer, the moisture from the environment must be stopped or delayed by the packaging seal so that the accelerometer sitting in the package will function properly. Furthermore, the temperature cycling often seen in automotive applications may raise concerns over the electric interconnection. The metal-to-metal contacts may form intermetallic compounds that are thermally mismatched with the surroundings and cracks will form when the package goes through temperature cycling. The metal contact resistance will then increase and eventually form an open circuit.

Many testing methods are available to evaluate the reliability of an IC/MEMS package. For example, if the dominant failure mode of a MEMS device is water condensation in the package, *autoclave* tests are available to test the reliability of the devices [1]. In an autoclave test, pressurized water is used to fill bonding imperfections and small crevasses that may exist in a package to accelerate the device failure.

Key Research Findings

In recent years, low-cost, localized "welding" has demonstrated reliability and possibilities for packaging of MEMS devices [5, 12]. One of the emphases has been on vacuum packaging for MEMS resonators and gyroscopes for high quality factor performance in a vacuum. Vacuum packaging for MEMS resonators using aluminum-to-silicon nitride bonding was shown to maintain the vacuum level in a harsh environment (130°C, 2.7 atm and 100% relative humidity) for a long period of time [6]. A specialized metallization process was also demonstrated to produce a vacuum package [13].

Future Directions for Research

Due to the diversity of MEMS devices, MEMS packaging methodology is device and application dependent. Compromise solutions between cost, reliability and process compatibility need to be considered.

Cross References

- ► Anodic Bonding
- ► Micromolding
- ► Techniques for Transferring Samples to Chips
- ► Wafer Bonding

References

1. Chiao M, Lin L (2004) Sealing Technologies. In: Hsu TR (ed) MEMS Packaging. IEE, Stevenage, Herts., UK
2. Kamath SM, Tummala RR (2001) Fundamentals of Single Chip Packaging. In: Tummala RR (ed) Fundamentals of Microsystems Packaging. McGraw-Hill, Boston
3. Tong QY, Gosele U (1999) Semiconductor wafer bonding: sciences and technology. Wiley, New York
4. Cheng YT, Lin L, Najafi K (2000) Localized silicon fusion and eutectic bonding for MEMS fabrication and packaging. J Microelectromec Syst 9(1):3–8
5. Cheng YT, Hsu WT, Najafi K, Nguyen CTC, Lin L (2002) Vacuum packaging technology using localized aluminum/silicon-to-glass bonding. J Microelectromec Syst 11(5):556–565
6. Chiao M, Lin L (2006) Device-Level Hermetic Packaging of Microresonators by RTP Aluminum-to-Nitride Bonding. J Microelectromec Syst 15(3):515–522
7. Puntambekar A, Ahn CH (2002) Self-aligning microfluidic interconnects for glass- and plastic-based microfluidic systems. J Micromech Microeng 12:35–40
8. Li S, Chen S (2003) Polydimethylsioxane fluidic interconnects for microfluidic systems. IEEE Trans Adv Packag 26(3):242–247
9. Tsai JH, Lin LW (2001) Micro-macro fluidic interconnectors with an integrated polymer sealant. J Micromech Microeng 11:577–581
10. Tingrui P, Baldi A, Ziaie B (2006) A reworkable adhesive-free interconnection technology for microfluidic systems. J Microelectromec Syst 15(1):267–272
11. Al-Sarawi SF, Abbott D, Franzon PD (1998) A review of 3-D packaging technology. IEEE Trans Compon Packag Manuf Technol, Part B: Adv Packag 21(1):2–14
12. Lin L (2000) MEMS post-packaging by localized heating and bonding. IEEE Trans Adv Packag 23(4):608–616
13. Stark BH, Najafi K (2004) A low-temperature thin-film electroplated metal vacuum package. J Microelectromec Syst 13(2):147–157
14. Gonzalez C, Collins SD, Smith RL (1998) Fluidic interconnects for modular assembly of chemical microsystems. Sens Actuators B 49:40–45
15. Han KH, Frazier AB, (2005) Reliability aspects of packaging and integration technology for microfluidic systems. IEEE Trans Device Mater Reliab 5(3):452–457

Parallelization

Definition

Simultaneous implementation of several chemical/biological analyses in an on-chip format generally from a single reagent source.

Cross References

- ► Surface-Directed Capillary Flow Systems

Parallel (Stratified) Flow

Definition

Stratified flow is that multiphase flow where the phases flow along each other in distinct strata or layers.

Cross References

► Pressure-driven Two Phase Flows

Partial Differential Equations (PDEs)

Definition

A partial differential equation (PDE) is a relation involving an unknown function of several independent variables and its partial derivatives with respect to those variables. Partial differential equations are used to formulate and solve problems that involve unknown functions of several variables, such as the propagation of sound or heat, electrostatics, electrodynamics, fluid flow, elasticity, or more generally any process that is distributed in space, or distributed in space and time. (Definition taken from wikipedia: http://en.wikipedia.org/wiki/Partial_differential_equation)

Particle Dynamics Simulation

► Molecular Dynamics Simulation Method

Particle Image Thermometry

Definition

Particle Image Thermometry (PIT) is a method to determine two dimensional temperature fields of fluids. The particles carry the temperature information and are seeded into the fluid. Thermochromic Liquid Crystals (TLCs) are often used for that.

Particle Image Velocimetry (PIV)

Definition

PIV is used to estimate two-dimensional velocity fields of fluid flows. The fluid is seeded with ►tracer particles (able to follow the flow) whose motion gives information about the motion of the fluid. Therefore two images taken at two times are divided into ►interrogation areas. The interrogation areas belonging together are correlated (image processing algorithm) which leads to a pixel displacement. With the time interval between the capture of the two pictures, the pixel displacement, and the pixel length the velocity of the considered interrogation area can be calculated.

Particle Manipulation

► Bead Based Microfluidic Platforms

Particle Manipulation Using Ultrasonic Fields

Nick R. Harris[1], Martyn Hill[2]
[1] School of Electronics and Computer Science, University of Southampton, Highfield, Southampton, UK
[2] School of Engineering Sciences, University of Southampton, Highfield, Southampton, UK
nrh@ecs.soton.ac.uk

Synonyms

Ultrasonic separation; Ultrasonic concentration; Ultrasonic particle manipulation; Acoustic separation

Definition

Ultrasonic fields, particularly standing waves or pseudo standing waves, can be used to manipulate particles within fluids. Typically particles in aqueous media will move to pressure nodes of the field, which can be planes, lines or points, depending on the standing wave geometry. By control of the standing wave patterns, it is possible to agglomerate particles, separate particles from the medium, wash particles from one fluid to another or fractionate populations of particles. In this article, techniques that have been used in microfluidic applications will be discussed, although many of the techniques can also be used at the macro scale.

Overview

It has been known for many years that acoustic standing waves can influence the behaviour of particles in either a liquid or gaseous medium. This effect relies on acoustic radiation forces that act on particles and other acoustic discontinuities (such as second phase fluids) within an ultrasonic field [1]. These forces are generally larger



Particle Manipulation Using Ultrasonic Fields, Figure 1 Movement of particles within an ultrasonic standing wave (USW). (**a**) Before a standing wave is generated, particles are evenly distributed throughout the fluid (**b**) a standing wave is excited by driving a transducer at a thickness resonance of the fluid layer, generating a pressure node in the centre of the fluid layer (dotted grey lines). A net force profile is established as per the solid line (in the direction of the arrows) (**c**) particles aggregate at the pressure node, driven by the force



Particle Manipulation Using Ultrasonic Fields, Figure 2 Enhanced sedimentation. Particles within an ultrasonic field (left) are agglomerated by the field (centre) and then tend to sediment under gravity (right)

in an ultrasonic standing wave (USW) than in a progressive wave and so it is mainly standing waves that are used for particle manipulation. The magnitude of this force is dependent upon the distance from the node of the standing wave and causes particles to move to the nodal plane. Use in microfluidic systems concentrates on active dimensions comparable with an acoustic wavelength. Acoustic frequencies of a few megahertz have wavelengths of the order of a few hundred micrometres. For example, a 3MHz acoustic wave in water has a wavelength of 500 µm. Many of the devices to be discussed here actually use subwavelength active dimensions and so it can be seen that ultrasonic waves of this order of frequency are compatible with the dimensional scale typically used in microfluidic systems. Consider the system represented in Fig. 1, in which particles within a fluid are bounded by an ultrasonic transducer and a reflective boundary. If the transducer is driven so as to excite a resonance frequency of the cavity (in this case, a half wavelength mode as shown by the pressure profile) a standing wave will be set up, with associated pressure maxima and minima. Particles will, in general, be transported towards pressure nodes within the field, by radiation forces. Figure 1b shows the relative magnitude and direction of the force across the depth of the chamber. The arrows show the net force direction, and the black curve gives an indication of relative magnitude. The dotted curve shows the acoustic pressure profile (in this case a half wavelength) with a resulting node in the centre of the fluid layer.

The magnitude of the force seen by the particles is dependent on

- the radius of the particle
- the energy density in the standing wave
- the distance of the particles from the nodal plane
- the acoustic contrast factor of the particles.

This last factor is a function of the differences in mass density and compressibility of the fluid and the particle.

By considering these factors, it can be seen that particles can be either all concentrated in one place, or by making use of the different size of particle populations and a competing force such as viscous drag, fractionated by size. It is also possible, by making use of acoustic contrast factor variations to fractionate similar sized populations.

Basic Methodology

Particle Concentration or Filtration

An obvious application of this technique is in a particle concentration or filtration system. There are two main approaches adopted

- Particle agglomeration
- Flow through separation.

In a particle agglomeration system (see [2]), devices are typically operated in a vertical direction (see Fig. 2). Particles are driven to the standing wave nodes by the acoustic radiation forces, and start to form agglomerates. Agglomerates form due to secondary radiation forces (see *key research findings*). As agglomerates grow, the relative importance of gravitational forces over viscous drag forces grows until the clumps of particles are able to sediment under gravity. Alternatively, once particles have been



Particle Manipulation Using Ultrasonic Fields, Figure 3 Flow through concentration based on technique described by Hawkes and Coakley [3]



Particle Manipulation Using Ultrasonic Fields, Figure 4 Particle Washing by forcing particles from one medium to another under laminar flow conditions

trapped, the field can be removed and the particle agglomerate falls.

Although as described, this technique has obvious application in batch processing, it can be modified to work as a flow-through device.

Flow-through systems are used in a continuous mode of operation in which a mix of fluid and particles is pumped through the device and the ultrasonic standing wave field concentrates the particles into a nodal plane. In this way a barrier-free filter is created.

This allows concentrated particles to be drawn off from the centre of the flow and clarified fluid to be drawn from either the upper or lower outlet, or from both as shown in Fig. 3. In this configuration, a mixture of particles and fluid are input from the left and flow through the device. In the main chamber an acoustic field concentrates the particles into a nodal plane in the centre. Clear fluid is then drawn out through the top and bottom outlets while the concentrated particles are allowed to proceed to the third exit.

This approach relies on the particles remaining at the centre of the channel due to the ordered nature of the highly laminar flow in a microchannel. The device developed by Hawkes and Coakley [3] was fabricated using traditional techniques and a microfabricated device has been developed using channels that are wet etched into silicon and Pyrex layers anodically bonded together [4].

An alternative technique that sorts particles into discrete patterns within a microchamber has been used by Neild et al. [5]. In the devices used by this group, acoustic energy is coupled into a fluid by first exciting flexural waves in a glass plate that bounds the fluid. Changing the excitation frequency, and in some cases using different transducers to excite the plate, allows particles to be aligned and manipulated within the fluid. Work described in reference [5] uses the acoustic pattern to align particles prior to further manipulation by a mechanical microgripper.

While most work has used planar resonators, it is also possible to manipulate particles in alternative geometries such as cylindrical tubes [6].

Particle Washing

Applications have also been developed whereby particles can be driven acoustically from one fluid to another, making use of the laminar flow inherent in microfluidic systems. This precludes turbulent mixing, and so fluids can be in physical contact with minimal mixing. Figure 4 shows the principle. A fluid with particles in is fed in through fluid 1 inlet, and the acoustic force drives the particles from fluid 1 to fluid 2. Fluid 2 can then be withdrawn from outlet 2 with the particles. The ability to wash cells and particles and to move them from one medium to another is a critical element of many forms of analysis and hence an important component of a Lab-on-a-Chip toolbox.

A microfabricated device that works in a manner similar to that shown in Fig. 4 has been developed by Peterson et al. [7]. Three inlet and three outlet channels feed a single parallel sided channel anisotropically wet etched into a silicon substrate. This channel is excited at its half-wave resonance by a transducer mounted in the plane of the silicon, perpendicular to the axis of the standing wave. Similar devices have been used by the same group for a number of applications, including the separation of lipids from blood (in which the lipids move to the pressure antinode and the red cells to the pressure node) and fractionation of different size beads.

Biosensor Performance Enhancement

Ultrasonic particle manipulation can also be used to enhance biosensor performance, by using the ultrasound to drive the particles of interest to the biosensor surface. In this implementation (Fig. 5), a resonant reflector layer is used to generate a pressure node at a boundary, (effectively creating a quarter wave resonance within the fluid layer), rather than in the centre of the chamber, as previously described.

Such a device was demonstrated by Martin et al [8], who forced spores in a 135 μm deep chamber on to an antibody



Particle Manipulation Using Ultrasonic Fields, Figure 5 Enhancing biosensor performance based on technique of Martin et al [8]

coated surface and increased the capture of those spores by a factor of 70 when compared with the same system without ultrasonic actuation. This has the potential to overcome the diffusion limit on detection in microfluidic biosensor systems and significantly increase sensor sensitivity.

Fractionation

A further illustration of the use of ultrasonic fields is shown in Fig. 6. This demonstrates the principle of particle fractionation using acoustics. Different sized particles of the same material will experience different magnitudes of force within the same field. Thus larger particles, experiencing a larger force, will move more rapidly to the nodal plane. As long as the lateral flow is balanced against the vertical particle movement, the population of particles will be fractionated as shown. If the residence time in the field is too long though, all the particles will end up at the nodal plane.

Again, a quarter wave structure is used here to spread the particles across the width of the chamber, and the pressure profile is shown in the diagram. This requires the whole particle population to be input at the bottom of the channel, requiring some pre-conditioning of the particle distribution before the particles are introduced to this device, as the particles are driven from bottom to top in this case.

Key Research Findings

Calculation of Radiation Forces within the Fluid Layer

For a more detailed description of the background, including key references, see Gröschl's 1998 paper [1]. King provided the first comprehensive calculation of acoustic radiation forces on a small particle within a standing wave in 1934. This theory was developed for rigid spheres in an inviscid fluid and predicts that particles will move toward either the node or antinode of the field depending on the ratio of the fluid and particle densities. When the ratio of the incompressible particle density to the fluid density is



Particle Manipulation Using Ultrasonic Fields, Figure 6 Fractionation of particles, making use of the net larger force on larger particles

less than 0.4, the acoustic force will act towards the pressure antinode. If the density ratio is above 0.4 (which is the general case for real particles) the acoustic radiation force will act towards the pressure node of the standing wave. King's predictions have been shown to be in good agreement with experimental results for solid spheres suspended in a gas, but are subject to significant errors for spheres which are not rigid in comparison to the fluid medium, which is the case of bubbles within a resonant field.

In the light of this, King's theory was extended by Yosioka and Kawasima to allow for compressible spheres in 1955. They demonstrated that the time-averaged acoustic radiation force on a spherical particle of radius a, at position x within a one dimensional standing wave of acoustic energy density ε is:

$$F(x) = 4\pi k \varepsilon a^3 \Phi(\beta\rho) \sin(2kx) \tag{1}$$

The *acoustic contrast factor*, $\Phi(\beta\rho)$ is given by:

$$\Phi(\beta\rho) = \frac{\rho_p + \frac{2}{3}(\rho_p - \rho_f)}{2\rho_p + \rho_f} - \frac{\beta_p}{3\beta_f} \tag{2}$$

where β and ρ are the compressibility and the mass density of the fluid and the particle, indicated by subscripts f and p respectively. The wave number, k is equal to $2\pi/\lambda$ where λ is the wavelength of the standing wave.

For most applications of interest, including cells in aqueous solution, the acoustic force will act towards the pressure node, however in the case of bubbles that are smaller than resonant size, and certain two-phase fluid mixtures, the bubble, or second phase fluid, will experience an acoustic force acting towards the pressure antinode.

Particle Positions Under Gravity and Other Forces Yosioka and Kawasima also considered the direction in which an acoustic force will act on a particle in suspension. The equilibrium position of a particle within the field will be determined by the resolution of this acoustic force and any other forces acting on the particle. Typically this would be gravity, although it applies to any force. In the case of a planar resonant field in which the positive x-axis points vertically upwards, the particle will be in equilibrium when:

$$3k\varepsilon\Phi(\beta\rho)\sin(2kx) = (\rho_p + \rho_f)g \tag{3}$$

The equilibrium position, for this case (in which the particle is small compared to the acoustic wavelength) is independent of the size of the particle, but dependent upon the acoustic contrast factor and the strength and frequency of the ultrasonic field. This offers a means of characterizing the acoustic field, the pressure amplitude of which is often difficult to determine in microsystems, by balancing acoustic and gravitational forces on an acoustically levitated particle. Particles that are not neutrally buoyant will have a minimum acoustic energy density required to hold the particle against buoyancy forces.

In many applications, including the manipulation of biological cells, particles are close to neutrally buoyant and the equilibrium position given by Eq. 3 will be very close to the pressure node. However for heavy particles, or for bubbles, this buoyancy offset may be significant.

Lateral Forces Real standing wave fields do not only exhibit pressure variations along the axis of the standing wave. They also have variations in the lateral directions leading particles to move not just to the axial pressure nodes, but also to particular points within those energy nodal planes. The practical effect of this is that instead of having a homogeneous layer of particles, the layer can organise itself into stripes, or striations, or other patterns. These inhomogeneities in the field may be caused by a number of phenomena including a decrease in acoustic energy towards the edges of axial fields, near field effects [9] due to geometric interference patterns, multidimensional acoustic modes within the enclosure, the coupling of structural (for example bending) modes into the fluid or inhomogeneity of the ultrasonic source.

In some cases these lateral variations provide a desirable feature of the device operation, particularly in systems designed to trap particles, while in others, the variations are not desirable and may be detrimental to the device performance, such as flow through concentrators. In real devices lateral forces may well exist due to a combination of the above causes. The magnitude and distribution of the lateral forces within resonators has been measured and shown to compare well with calculations using Gorkov's formulation for radiation forces (described by Gröschl in [1]).

Secondary Radiation Forces In addition to the axial and lateral radiation forces attributable to the primary acoustic field, secondary acoustic forces are produced between particles themselves. These particle-particle interactions, known as Bjerknes forces, aid the formation of aggregates within a standing wave, but such effects are negligible until the particles are in close proximity.

Some Practical Considerations

The Influence of Particles on the Field Resonant chambers for particle manipulation (including microfluidic chambers) are designed to provide specific acoustic characteristics. However, the chambers must work when filled with a fluid-particle mix which will have acoustic characteristics that differ from the particle-free fluid. Many applications will need to work over a range of particle concentrations that will modify the acoustic field. In cases where the particles are very different acoustically from the fluid medium, agglomerations can cause localized breakdown of the acoustic field resulting in a disruption of the ordered collection of particles at the pressure nodes.

Temperature Changes The temperature of an acoustic resonator will typically rise during use due to energy dissipation in the transducer and acoustic absorption within the layers of the resonator. The temperature rise will depend on the input power, the size of the resonator, the transducer material, and the material characteristics of the resonator layers. Hence there are significant differences in the thermal behaviour of resonators reported in the literature, with, for example, Hawkes and Coakley [3] reporting less than 1 K temperature increase in micro-scale chambers, while at the other extreme, Doblhoffdier et al. [2] required an integrated cooling circuit to avoid significant temperature rises in their rather larger chamber designed for the retention of mammalian cells.

Cell Viability Many of the uses envisaged for USW manipulation of particles are based upon manipulation of biological cells and so cell viability after treatment with ultrasound becomes an important issue. This has been reported on by several studies which have found that viability is maintained. For example Doblhoffdier et al. [2] suspended mammalian cells in a large resonator at different power levels and reported no significant loss in viability.

Hultström et al. [10] trapped cells in a 260 μm deep microfluidic chamber constructed from glass and PDMS. It was demonstrated that cell viability was not significantly impeded by 75 min exposure to a 0.85 MPa 3 MHz USW field. Indeed, tests on the cells following exposure suggested that the exposure to ultrasound enhanced the cells' ability to proliferate. The same group has demonstrated the ability of ultrasound traps to enhance bioanalysis in a number of different microchambers and has constructed microdevices that integrate ultrasonic and dielectrophoretic manipulation.

Future Directions for Research

Radiation forces as generated by low MHz ultrasonic standing waves offer a method of manipulating particles in a fluid, with particular application at the microscale. This gives tremendous potential for trapping and manipulating larger particles and groups of particles, perhaps prior to finer manipulation from other techniques. In addition, the evidence that ultrasound can manipulate and control the position of cells without adversely affecting cell viability suggest that ultrasonic standing waves hold significant potential in the manipulation of biological cells. The field is still relatively immature and requires work on the characterisation and optimisation of chambers and defining the scale limits of manipulation in practical devices.

Cross References

- ► Acoustic Streaming
- ► Acoustics Based Biosensors
- ► Biosample Preparation Lab-on-a-Chip Devices
- ► Cavitation in Microdomains
- ► Cell Sorting
- ► Lab-on-chip Devices for Particle and Cell Separation
- ► Piezo/PZT in Microfluidics

References

1. Gröschl M (1998) Ultrasonic separation of suspended particles – Part I: Fundamentals. Acustica 84(3):432–447
2. Doblhoffdier O, Gaida T, Katinger H, Burger W, Groschl M, Benes E (1994) A Novel Ultrasonic Resonance Field Device for the Retention of Animal-Cells. Biotechnol Progress 10(4):428–432
3. Hawkes JJ, Coakley WT (2001) Force field particle filter, combining ultrasound standing waves and laminar flow. Sens Actuators B Chem 75(3):213–222
4. Harris NR, Hill M, Beeby SP, Shen Y, White NM, Hawkes JJ, Coakley WT (2003) A Silicon Microfluidic Ultrasonic Separator. Sens Actuators B 95(1-3):425–434
5. Neild A, Oberti S, Beyeler F, Dual J, Nelson BJ (2006) A micro-particle positioning technique combining an ultrasonic manipulator and a microgripper. J Micromech Microeng 16(8):1562–1570
6. Goddard G, Kaduchak G (2005) Ultrasonic particle concentration in a line-driven cylindrical tube. J Acoust Soc Am 117(6):3440–3447
7. Petersson F, Nilsson A, Jonsson H, Laurell T (2005) Carrier medium exchange through ultrasonic particle switching in microfluidic channels. Anal Chem 77(5):1216–1221
8. Martin SP, Townsend RJ, Kuznetsova LA, Borthwick KAJ, Hill M, McDonnell MB, Coakley WT (2005) Spore and microparticle capture on an immunosensor surface in an ultrasound standing wave system. Bio-sens Bioelectron 21(5):758–767
9. Lilliehorn T, Simu U, Nilsson M, Almqvist M, Stepinski T, Laurell T, Nilsson J, Johansson S (2005) Trapping of microparticles in the near field of an ultrasonic transducer. Ultrasonics 43(5):293–303
10. Hultström J, Manneberg O, Dopf K, Hertz HM, Brismar H, Wiklund M (2006) Proliferation and viability of adherent cells manipulated by standing-wave ultrasound in a microfluidic chip. Ultrasound Med Biol 33:175–181

Particle Methods

► Meshless Methods

Passive Micromixers

CHIA-YEN LEE[1], CHE-HSIN LIN[2], LUNG-MING FU[3]
[1] Department of Mechanical and Automation Engineering, Da-Yeh University, Chung-Hua, Taiwan, ROC
[2] Department of Mechanical and Electromechanical Engineering, National Sun Yat-sen University, Kaohsiung, Taiwan, ROC
[3] Department of Materials Engineering, National Pingtung University of Science and Technology, Pingtung, Taiwan, ROC
loudyfu@mail.npust.edu.tw

Synonyms

Microfluidic mixer; Micromixing chip; Micromixer; Passive mixer

Definition

A passive micromixer is one of the microfluidic devices. It utilizes no energy input except the mechanism (pressure head) used to drive the fluid flow at a constant rate. Due to the dominating laminar flow on the microscale, mixing in passive micromixers relies mainly on chaotic advection realized by manipulating the laminar flow in microchannels or molecular diffusion with increasing the contact surface and time between the different fluid flows.

Overview

Microfluidic devices have had a considerable impact in the fields of biomedical diagnostics and drug development, and are extensively applied throughout the food and chemical industries. The very small scale of the flow channels in microfluidic systems increases the surface to volume ratio, and is therefore advantageous for many applications. However, the characteristic Reynolds number ($\mathrm{Re} = l\rho v/\eta$) of liquid flows in such microchannels is very small. For example, the Reynolds number in a typical water-based microfluidic system with a channel width of 100 μm, a liquid flow rate of 1 mm/s, a fluid density of 1 g/cm^3 and a viscosity of 0.001 N s/m^2 is of the order of 0.1. In such low Reynolds number regimes, turbulent mixing does not take place, and hence species mixing occurs primarily as a result of diffusion, which is an inherently slow process. Consequently, the aim of microfluidic mixing schemes is to enhance the mixing efficiency such that a thorough mixing performance can be achieved within shorter mixing channels, thus reducing the characteristic size of microfluidic devices. Furthermore, developing efficient mixing schemes is essential to increase the throughput of microfluidic systems in general and to realize the concept of micro-total-analysis systems and Lab-on-a-Chip systems in particular.

In micromixers, two operating parameters are of importance: the Reynolds number Re and the Péclet number Pe. The Reynolds number, given by

$$\mathrm{Re} = VL_h/\upsilon \qquad (1)$$

represents the ratio of momentum to viscous friction, where V is the average flow velocity, L_h is the hydraulic diameter and υ is the kinematic viscosity. A turbulent flow can be indicated by a high Reynolds number above a critical value (around 2300 on the macroscale). In most cases of microfluidics, a laminar flow can be expected with a low Reynolds number. The Péclet number, given by

$$\mathrm{Pe} = VL/D \qquad (2)$$

represents the ratio of the mass transport due to convection and that of diffusion, where L is the mixing path and D is the diffusion coefficient. Convection is dominant at higher Péclet numbers.

The theory reported on mixing began with Einstein's investigation of Brownian movements [1]. The common mixing methods are the generation of chaotic advection and turbulence. Fluid motions vary irregularly so that quantities such as pressure and velocity show a random variation in space and time. The random movement quickly disperses the mixed components. Chaotic advection can be generated by stirring the flow, which is very effective for low Reynolds numbers. The concepts of splitting, stretching, folding and breaking up play an important role in the mixing quality.

In contrast to the passive mixing schemes presented above, in which the microchannel configuration is specifically designed to increase either the contact area or the contact time (or both) of the multiple species, active mixing schemes improve the mixing performance by applying external forces to the sample flow in order to accelerate the diffusion process. Typically, active schemes are implemented by incorporating some form of mechanical transducer within the microfluidic device using microfabrication techniques. It has been shown that microfluidic mixers which use embedded ultrasonic transducers to generate acoustic waves to stir the samples are capable of achieving a high mixing performance. However, the acoustic vibrations also generate considerable heat, which is undesirable since it may lead to unwanted reactions between the samples. Various microfluidic devices with embedded microelectrodes designed to mix the sample fluids dielectrophoretically have been presented. It has also been shown that the use of embedded electrode pairs to change the surface energy of the microchannel walls provides an efficient means of enhancing species mixing by inducing local instabilities in the flow stream. Compared to other active mixing schemes, the use of embedded electrode pairs has the advantage that moving components are not required, and hence the resulting microfluidic devices are not only cheaper, but also more reliable.

Besides chaotic advection, molecular diffusion is another important form of mass transfer in passive micromixers. In such scales where the flow is strictly laminar, the mixing is entirely ensured by molecular diffusion between layers of different concentrations. Consequently, when the thickness of each fluid layer is larger than the characteristic diffusion length, an effective and rapid mixing is difficult to achieve. The diffusion length is often approximated by $\sqrt{D}t$, where t is the residence time of the species. To overcome the limitations by integrating particular designs of microchannels on the basis of different fluidic mechanisms, the most common approach is based on increasing the contact surface between the different fluids and decreasing the diffusion path between them. In general, passive micromixers can be categorized as lamination, chaotic advection and special designs, based on the arrangement of the mixed phases.

Basic Methodology

Theory of Lamination

Mixing in general follows a two-step sequence. The first is segmentation where a heterogeneous mixture of substantially homogeneous flows of the two fluids is formed by convection; the second is interdiffusion of molecules between nearby flows. Segmentation procedures, well known from the macroscopic world, such as stirring or creation of turbulent flow, cannot be scaled down to microsystems with dimensions so small that Reynolds numbers exceeding 2000 (the limit for turbulent flow) are not feasible.

Perfect lamination can be obtained in a flow with a sufficiently low Reynolds number provided that the channel system guiding the fluid is designed in such a way that the pressure gradients in the flow channels will force the two fluids to laminate. Figure 1 shows a generic channel arrangement laid out in a free three-dimensional space. When considering symmetry it is obvious that a perfect lamination and a split into two channels is obtained. Depending on the flow direction, either horizontal (Fig. 1a) or vertical (Fig. 1b) lamination will be the result [2].

A detailed theoretical description of flow and diffusion phenomena in the laminar regime is very useful during design and testing of mixers for microsystems. The fully developed velocity profile for laminar flow in a straight channel of rectangular cross-section of dimensions $W \times H$ is easily found by numerical methods. For channels having width (W) significantly larger than height (H) the velocity profile turns out to be very close to parabolic in the direction of the short dimension and almost similar to H from the channel walls. This is also expected intuitively, as the distance to the nearest walls is the only physically important parameter for laminar flow. In Ref. [2], it was found that the peak velocity (v_{peak}) in the middle of the channel is related to the average velocity (v_{average}) (as calculated from the volume flow rate) as

$$v_{\text{peak}} = \frac{3}{2}\left(\frac{1}{1-0.62H/W}\right)V_{\text{average}} \tag{3}$$

within 1.5% when $W \geq 3H$.

When solving the diffusion problem for a laminated structure, it is useful to consider Fourier expansion of the initial concentration profile, as it is well known that the time evolution of the concentration profile is given by the time evolution of each of the Fourier components. Each Fourier component κ decays exponentially during the diffusion process with a time constant τ_k given by

$$\tau_k = (2\pi)^{-2}\frac{L_k^2}{D} \tag{4}$$

where L_k is the *wavelength* of the Fourier component and D is the diffusivity.

This explains concisely what is also expected from quantitative arguments that a 2^n-layer structure can mix 4^{n-1} times faster than a 2-layer structure, as the wavelength of the Fourier component of longest wavelength and thus slowest decay rate scales with the layer thickness [2].



Passive Micromixers, Figure 1 A generic two-input two-output mixer including lamination and splitting shown in free three-dimensional space. (**a**) Horizontal lamination and (**b**) vertical lamination [2]

Meanwhile, the Fourier argument makes a small but important detail of mixing by lamination very clear: The lamination has to be symmetric, i. e. the top- and bottommost layer should be of only half thickness compared to the other layers. Otherwise, i. e. if the lamination is asymmetric, the Fourier expansion of the initial profile will contain a component with a wavelength twice the channel dimension, no matter how thin the laminated layers are. The component will sooner or later become dominant because of its slow decay, and only a minor benefit is obtained by lamination. The qualitative counterpart of this argument is that, unless the outermost layers are of half thickness, half of their content of the diffusing species has to be distributed over all of the inner layers before full mixing is achieved. When being of only half thickness, they are balanced by their neighboring layer as are all the other layers.

However, a simple cascade of two-input two-output mixers results in an asymmetric lamination. Symmetric lamination can be obtained with a modification of the first mixer into a three-input two-output mixer which builds up a $(H/4, H/2, H/4)$ type of laminate. This initial mixer can be followed by as many regular two-input two-output mixers as desired for the particular application.

Micromixers Based on Lamination

In miniature flow systems with Reynolds numbers varying from 2 to 100, flow structures can be artificially induced which assist in flow segmentation through inertia effects. Wu et al. [3] presented an analytical model of diffusive mixing in microchannels. The dimensionless analysis generalizes the solution for different channel sizes and different diffusion coefficents by varying the Peciet numbers. It could be seen that the nonlinear model described well the diffusive mixing process in the microchannels and the mixing performance was improved with lower Peciet numbers due to the stronger diffusion effect. Another lamination micromixer using inertia forces was reported in the literature, involving a coaxial mixer containing an inner core liquid stream with a low flow rate and an outer flow stream with a higher flow rate.

Jacobson et al. [4] proposed micromixers for electrokinetically driven parallel and serial mixing. To simplify the voltage control hardware, electrokinetic mixing is effected using a single voltage source with the channels dimensioned to perform the desired voltage division. In addition, the number of fluid reservoirs is reduced by terminating multiple buffer, sample or analysis channels in single reservoirs. The parallel micromixer (Fig. 2a) was designed with a series of independent T-intersections, and the serial micromixer (Fig. 2b) was based on an array of cross intersections and sample shunting. The parallel micromixer has the advantages that each set of channels is independent of the others. Consequently, a failure in one set of channels does not affect the operation of the others. The dynamic range of the serial micromixer is larger especially if the sample shunting is carried out with additional cross intersection added to the channel manifold beyond the fifth cross intersection. Wong et al. [5] presented a micro T-mixer fabricated on a silicon substrate and bonded to a Pyrex glass plate (Fig. 3). The experimental results revealed that a mixing channel with a hydraulic diameter of 67 μm and an applied pressure of 5.5 bar were sufficient to result in complete species mixing in less than 1 ms following the initial contact between the two species flows with Reynolds numbers of 400 – 500.

Micromixers Based on Intersecting Channels

Micromixers with intersecting channels can be used to split, rearrange and combine component streams in order to enhance their mixing. He et al. [6] proposed a picoliter-volume mixer (Fig. 4) with intersecting channels of various lengths and a bimodal width distribution. In the proposed design, all of the channels running parallel to the flow direction had a width of 5 μm, while those intersecting the parallel channel network had a width of 27 μm and were aligned at an angle of 45°. The microchannels were designed such that the two species streams merged into one larger stream and then flowed together along a mixing channel of length 300 μm. The results showed that this configuration enabled a complete species mixing within a distance of 200 μm, representing a considerable



Passive Micromixers, Figure 2 (**a**) Schematic of the microchip for parallel electrokinetic mixing. (**b**) Schematic of the microchip for serial electrokinetic mixing [4]



Passive Micromixers, Figure 3 (**a**) The front face of the micro T-mixer test chip. (**b**) The back face of the micro T-mixer [5]



Passive Micromixers, Figure 4 Photomicrograph of a microfabricated mixer. The small image in the lower left corner is the SEM of the mixer. This mixer is about 100 by 200 μm wide and 10 μm in depth. Effect of mixing is evaluated by bringing in two fluids from channels A and B, and flowing to D. Channel C is not used in this work [6]

improvement compared to the mixing distance of 3000 μm required to fully mix the two streams in a conventional straight channel. Melin et al. [7] presented a micromixer in which a constantly changing, time-dependent flow pattern was created within a two-sample liquid plug as the plug passed through a planar mixer chamber. It was shown that the micromixer created a larger mass transfer within the liquid plug than that achieved in many of the passive devices presented previously. The proposed mixing chamber comprised a main meandering channel with perforated walls, which formed connecting channels between parallel segments of the main meandering channel. In the mixing process, two discrete liquid samples are fed into the mixing chamber in a laminar manner. When the liquid wets one side of the first perforated wall segment, it enters the perforation, but is prevented from exiting by surface tension effects. However, as the bulk of the liquid proceeds to the next main channel segment, the other side of the perforated wall becomes wetted. As a result, the liquid/air interface at the exit of the perforation is replaced by a liquid/liquid interface, and hence the liquid flows freely through the perforation. The same phenomenon is repeated in each of the main channel segments as the liquid flows progressively through the mixing chamber. The resulting constantly changing flow lines within the liquid plug cause a self-folding effect within the plug which yields a significant improvement in the mixing performance.

Micromixers Based on Zigzag Channels

Mengeaud et al. [8] presented a 100 μm wide zigzag microchannel integrating a "Y" inlet junction (Fig. 5). The effect of the periodic step value (s) on the mixing efficiency was investigated in a series of experimental trials. The results indicated that for $\mathrm{Re} = 0.26$, the mixing efficiency increased from 65% to 83.8% when the geometry ratio was increased from 1 to 8. For low values of s/w, the number of angles increases, resulting in an increase in the effective width and a reduction in the effective length. For low Reynolds number flows, it was found that the most efficient zigzag configuration, corresponding to $s = 800\,\mu\mathrm{m}$, gave a mixing efficiency of 83.8%. For $\mathrm{Re} = 267$, the mixing efficiency increased rapidly to 98.6% as the geometry ratio was increased to 4, but reduced slightly to 88.1% as the geometry ratio was further increased, thus indicating the existence of an optimal zigzag geometry. After the research, the zigzag passive micromixer showed a modified Tesla structure. The species streams flowed close to the angled surface as a result of the Coanda effect, and this effect was used to guide the fluid streams such that they collided with one another. Mixing cells in opposite directions were then used to repeat the transverse dispersion caused by the flow impact. In the micromixer, one of the fluids was divided into two sub-streams and one of these two sub-streams was then merged with the second fluid stream from the main channel in the micromixer. The two streams were then



Passive Micromixers, Figure 5 Different geometries of a microchannel. (**a**) $s/w = 1$, (**b**) $s/w = 2$, (**c**) $s/w = 4$, (**d**) $s/w = 8$, (**e**) $s/w \to 0$, and (**f**) $s/w \to \infty$ [8]

mixed with the second sub-stream, resulting in a strong impact around the sub-channel of the micromixer.

Micromixers Based on Three-Dimensional Serpentine Structures

The three-dimensional serpentine micromixer was designed to induce a chaotic mixing effect. It was found that the mixing efficiency of the serpentine microchannel was twice that obtained in a conventional straight microchannel. Liu et al. [9] fabricated a three-dimensional serpentine micromixer (Fig. 6) featuring a "C"-shaped repeating unit designed to induce chaotic advection. Mixing in the serpentine channel relies on the flow field being sufficiently three-dimensional, with secondary flows stretching and folding the fluid, greatly increasing the interfacial area across which diffusion occurs. The results showed that for flows with a Reynolds number of 70, the mixing efficiency in the serpentine channel was 16 times better than that in a conventional straight channel and 1.6 times better than that in a zigzag channel.



Passive Micromixers, Figure 6 (**a**) Schematic of the three-dimensional serpentine channel. "Viewing windows" in the channel are labeled 1–10. (**b**) Schematic of zigzag channel. (**c**) Schematic of straight channel [9]

Micromixers Based on Embedded Barrier

Based on the combination of multilamination and chaotic advection effects, Kim et al. [10] developed barrier embedded micromixers for pressure-driven flow in which chaotic flow was induced by applying periodic perturbations to the velocity field via periodically inserted barriers along the upper surface and helical-type flow structures were induced by slanted grooves on the lower surface of the microchannel. Observations using a confocal microscope revealed cross-sectional mixing behaviors in several locations of the micromixer. The proposed design was validated experimentally at a flow rate corresponding to a Reynolds number of 2.28 (corresponding to $\mathrm{Pe} = 1.24 \times 10^4$ with a Rhodamine diffusivity of $2.8 \times 10^{-10}\ \mathrm{m}^2\ \mathrm{s}^{-1}$). Laser scanning around the entrance zone of the micromixer identified a bright image only in the half-zone containing Rhodamine. Bright images



Passive Micromixers, Figure 7 Three-dimensional twisting flow in a channel with obliquely oriented ridges on one wall. (**a**) Schematic of channel with ridges. (**b**) Optical micrograph showing a top view of a red stream and a green stream flowing on either side of a clear stream in the channel. (**c**) Fluorescent confocal micrographs of vertical cross-sections of a microchannel such as in (**a**) [11]

were also observed at the no-barrier zone in the first half-cycle, thus confirming the cross-sectional rotating flow effect induced by the slanted grooves. When the streams entered the barrier zone in the next half-cycle, laser scanning showed that the flow was rotated yet further. The experimental results confirmed that the barrier embedded micromixer yielded an excellent species mixing within a short channel length.

Micromixers Based on Slanted Well

Stroock et al. [11] presented chaotic mixers (Fig. 7) designed to mix streams of steady pressure-driven flows in microchannels at low Reynolds numbers. The authors considered two different microchannel designs, namely one channel with straight ridges on one wall and a second channel with a staggered herringbone pattern on one wall. The mixing performances of the two microchannels were compared with that of a smooth microchannel. In the evaluation experiments, cross-sectional images taken at the same distance (3 cm) from the junction were acquired and the mixing efficiency was assessed by computing the standard deviation σ of the fluorescence intensity in the confocal images as a function of the distance along the mixing channel length, Δy. The deviation maintained a constant value of approximately 0.5, indicating a poor mixing performance. The results revealed that the micromixer with straight ridges on one microchannel wall yielded a poor mixing performance. The standard deviation profile for a low Pe number was approximately 0, which signifies an almost complete mixing. Others investigated the effects of the asymmetry index p and depth ratio α of the groove on the mixing performance of a staggered herringbone mixer with patterned grooves. Since the two vortices within the mixing channel are determined by the asymmetry index p, vortices with dissimilar scales were shown to provide a better mixing performance than two equally sized vortices. Furthermore, the results showed that the intensity of the vertical fluid motions at the side edges of the grooves increased with increasing groove depth α, resulting in a significant improvement in the mixing effect.

Micromixers Based on Twisted Channels

In twisted microchannel applications, the micromixer featured is a three-dimensional structure of twisted microchannels designed to induce a chaotic mixing effect within the fluid streams. The twisted microchannels were designed such that the angle of the channels' lower surfaces alternated in each longitudinal subsection of the mixing channel. The fluid flow sways from side to side as it travels along the microchannel, resulting in a chaotic advection effect. Park et al. [12] presented a breakup method based on passive rotation for enhancing the mixing efficiency of micromixers. The proposed method not only actively generated interfaces between the mixing species, but also enhanced the diffusion process at the interface. The micromixer actually incorporated two separate mixing regions, namely one region with short segments of length 200 μm and a second region with long segments of length 400 μm (Fig. 8). The results showed that this design caused a rotation of the fluids flowing through the channel. It was found that the fluids were mixed well and their interface was distorted at high Reynolds numbers. Conversely, at low Reynolds numbers, the fluids were hardly mixed and the interface was not distorted, i. e. only the respective positions of the two fluid streams were changed.

Key Research Findings

Grooved Staggered Herringbone Micromixers

Grooved staggered herringbone micromixers are based on the original design proposed by Aubin et al. [13] and have an off-centered herringbone pattern on the lower surface of the microchannel, which creates a transverse velocity component in the flow field. Such mixers have several mixing cycles, where each cycle comprises two sequential regions of grooves, i. e. two half-cycles. The direction of asymmetry of the herringbone pattern switches with respect to the centerline of the microchannel every half cycle. In order to improve the mixing efficiency, the depth of the grooves in staggered herringbone micromixers should be specified



Passive Micromixers, Figure 8 Schematic diagrams of (**a**) one mixer segment and (**b**) flows in the microchannel recirculating along the walls. (**c**) Schematic of mixer 1. (**d**) Optical micrograph of mixer 1: top, micromixer composed of short mixer segments; bottom, micromixer composed of long mixer segments [12]

as 30% of the channel height. This promotes both spatial homogenization and a reduction of the striation thickness without increasing the pressure drop across the mixer.

Surface Chemistry Technology in Microchannels

In microfluidic systems, very high pressure gradients are generally required to drive and manipulate the fluid flow. Due to the small characteristic scale of the microchannels in typical microfluidic devices, surface forces dominate, and high friction effects are generated. Conventionally, microchannels are fabricated using silicon dioxide. Silicon dioxide surfaces are typically negatively charged due to their deprotonated silanol groups ($\equiv$Si–O$^-$). When these surfaces come in to contact with a solution containing ions, the positive ions are attracted to the surface, forming an important layer and a diffuse layer on the surface. If an electrical field is then applied, the positive ion diffuse layer moves in the direction of the applied field. The movement of the diffuse layer drags the bulk fluid into motion via momentum coupling, resulting in the so-called electro-osmotic flow (EOF) phenomenon [14].

Future Directions for Research

Mixing in electro-osmotic flow is generally diffusion-dominated. However, it has been shown that the introduction of electrically charged surface heterogeneities enhances the mixing efficiency by creating localized flow circulation regions. By selectively patterning positively charged molecules on a negatively charged channel wall, flow vortices can be induced as a result of the differences in electrostatic potential between the homogeneous and heterogeneous surfaces. It has been shown that these localized flow vortices can be exploited to yield a significant improvement in the mixing performance in a variety of microchannel configurations, including in-line, staggered, serpentine, herringbone and diagonal arrays [15]. In their numerical investigations, the authors specified the patch length and spacing parameters in such a way as to maintain a constant ratio of the heterogeneous-to-homogeneous surface areas over a channel length of 1.8 mm. The results revealed that the nonsymmetrical heterogeneous patterns, namely the staggered and diagonal patterns, generated a better mixing performance than either the symmetrical herringbone pattern or the in-line arrangement. With a theoretical mixing efficiency of 96%, the staggered configuration provided the best mixing performance, outperforming the diagonal, herringbone and serpentine configurations by 8%, 31% and 36%, respectively. Furthermore, compared to the homogeneous case, the staggered configuration provided a 61% improvement in the mixing efficiency. The use of heterogeneous surface charge patches to manipulate electrokinetic flows provides a simple, low-cost solution to mixing problems in Lab-on-a-chip systems, and is therefore likely to receive increasing attention in future studies.

Cross References

- ► Microfluidic Mixing
- ► Fundamentals of Diffusion in Microfluidic Systems
- ► Passive Micromixer

References

1. Einstein A (1956) Investigations on the theory of the Brownian movements. New York, Dover
2. Branebjerg J, Gravesen P, Krog JP, Nielsen CR (1996) Fast mixing by lamination. In: Proc IEEE MEMS'96, pp 441–446
3. Wu Z, Nguyen NT, Huang X (2004) Nonlinear diffusive mixing in microchannels: theory and experiments. J Micromech Microeng 14:604–611
4. Jacobson SC, McKnight TE, Ramsey JM (1999) Microfluidic devices for electrokinetically driven parallel and serial mixing. Anal Chem 71:4455–4459
5. Wong SH, Ward MCL, Wharton CW (2004) Micro T-mixer as rapid mixing micromixer. Sens Actuators B 100:359–379
6. He B, Burke BJ, Zhang X, Zhang R, Regnier FE (2001) A picoliter-volume mixer for microfluidic analytical systems. Anal Chem 73(9):1942–1947
7. Melin J, Gimenez G, Roxhed N, van der Wijngaart W, Stemme G (2004) A fast passive and planar liquid sample micromixer. Lab Chip 4:214–219
8. Mengeaud V, Josserand J, Girault HH (2002) Mixing processes in a zigzag microchannel: finite element simulations and optical study. Anal Chem 174(16):4279–4286
9. Liu RH, Stremler MA, Sharp KV, Olsen MG, Santiago JG, Adrian RJ, Aref H, Beebe DJ (2000) Passive mixing in a three-dimensional serpentine microchannel. J Microelectromech Sys 9(2):190–197
10. Kim DS, Lee SW, Kwon TH, Lee SS (2004) A barrier embedded chaotic micromixer. J Micromech Microeng 14:798–805
11. Stroock AD, Dertinger SKW, Ajdari A, Mezić I, Stone HA, Whitesides GM (2002) Chaotic mixer for microchannels. Science 295:647–651
12. Park SJ, Kim JK, Park J, Chung S, Chung C, Chang JK (2004) Rapid three-dimensional passive rotation micromixer using the breakup process. J Micromech Microeng 14:6–14
13. Aubin J, Fletcher DF, Xuereb C (2005) Design of micromixers using CFD modelling. Chem Eng Sci 60:2503–2516
14. Zeng S, Chen CH, Mikkelsen J, Santiago JG (2000) Fabrication and characterization of electrokinetic micro pumps. Proc. of 7th International Conference on Thermal and Thermomechanical Phenomenon in Electronic Systems 2:31–36
15. Biddiss E, Erickson D, Li D (2004) Heterogeneous surface charge enhanced micromixing for electrokinetic flows. Anal Chem 76(11):3208–3213

Passive Mixer

► Passive Micromixers

Patch Clamp Measurements On-Chip

Hui Yan, Hongkai Wu
Department of Chemistry, Hong Kong University
of Science and Technologyi, Hong Kong, China
chhkwu@ust.hk

Synonyms

Patch clamp technique; Voltage clamp; Patch voltage clamp technique; Cell-attached (single-channel) voltage clamp

Definition

Ion channels, like molecular pores that open and close in response to stimuli, allow electrically charged atoms – such as sodium, potassium and calcium ions – to pass in and out of a cell through the cell's outer membrane by opening and closing like tiny gates. The *patch clamp technique*, a dominant technique providing valuable information for ion channels, including their electrophysiological properties, molecular structures and the mechanism of drug action in cellular electrophysiology with high resolution, involves the fabrication of a pipette with a micrometer-sized tip which is filled with a conducting solution and the tip gentle suction directed towards the cell membrane with a micromanipulator in order to form a gigaseal between the pipette tip and the cell membrane. A *gigaseal* is a tight seal between the membrane and pipette rim with a resistance in the range of gigaohms (10^9 Ω).

Overview

The patch clamp technique, as a dominant technique, provides valuable information for ion channels, including their electrophysiological properties, molecular structures and the mechanism of drug action in cellular electrophysiology with high resolution. The rationale for using *patch pipettes* and the principles of patch clamp recording, including the information provided, are elaborated in detail first to understand the mechanism of the technique. The advantages and disadvantages of four configurations of this technique, i. e. on-cell patch clamp, whole cell patch clamp, inside-out patch clamp and outside-out patch clamp, are then described in the following. Two different methods for preparation of pipette on-chip and patch clamp device on-chip fabrication and electrophysiology recordings are given to provide reference for the reader. There are some simple but perspicuous figures presented to allow an easier grasp of the patch clamp technique. Finally, the key research findings about this technique are summarized and future directions for research are proposed.

Ion channels provide pores for the passive diffusion of ions across biological membranes. They are often highly selective for a particular ionic species, leading to a classification into sodium (Na^+), potassium (K^+), calcium (Ca^{2+}), chloride (Cl^-) and unspecific cation channels. The direc-



Patch Clamp Measurements On-Chip, Figure 1 Patch clamp technique and an amended equivalent circuit

tion of net ion transport, which is associated with an electric current, depends on the electrochemical gradient (established by interplay of active pumps, co-transporters and ion channels) for the relevant ionic species. Channels occur not only in the external (plasma) membrane, but also in membranes of intracellular organelles. Ion channels are essential for many of the cell's functions, such as impulse conduction in the nervous system or pace-making in the cardiac system, and their dysfunction is pivotal in many diseases. The list of human diseases known to be associated with defects in ion channels has grown considerably during the past few years. Hence, there is a great interest in ion channels not only from academia to understand the biophysics of their function but also from the biotechnology and pharmaceutical industries to develop drugs that modulate ion channels to correct any malfunction.

Several methods are available today to test candidate ion channel active drugs (ICADs): electrophysiology (patch clamp), binding assays, radioactive flux assays, membrane potential-sensitive fluorescent dyes, ion-sensitive dyes and voltage sensing based on fluorescence resonant energy transfer (FRET).

Giving an unsurpassed information content and having high sensitivity, the patch clamp technique, developed by Erwin Neher and Bert Sakmann at the Max Planck Institute, Germany (they were awarded the Nobel Prize in Medicine for this discovery; see Fig. 1), is a powerful tool for studying the electrophysiological properties of biological membranes. It is mainly used to detect currents that pass a patch of cell membrane. This *patch* can be a large one, as large as almost the whole cell membrane; or a small one, so small as to contain only several or even one ion channel. *Clamp* mainly refers to fixing the voltage across the membrane, i. e. membrane potential, at a constant level, or at different levels stepwise, under which conditions transmembrane currents are measured (i. e. voltage clamp mode). Also, the patch clamp technique can sometimes be used to observe the membrane potential when a constant current (usually zero), on which sometimes a squarewave current is superposed, is injected into the cell (i. e. current clamp mode). And furthermore, with this technique cell secretion ions can also be studied by measuring the capacitance of the cell membrane (C_{m}), which, used as an indicator of the area of cell membrane, may change during cell secret ion.

Basic Methodology

Mechanism

Rationale for Using Patch Pipettes

A basic limitation for any current measurement, disregarding instrumentation noise, is the Johnson or thermal noise of the signal source, which for a simple resistor is given by

$$\sigma_n = \sqrt{4kT\Delta f/R}$$

where σ_n is the root-mean-square deviation of the current, k the Boltzmann constant, T the absolute temperature, Δf the measurement bandwidth and R the resistance. From this equation, it is clear that the internal resistance of a signal source (or, more generally, the complex impedance) should be very high for low-noise current recording. Specifically, to record a current of 1 pA at a bandwidth of 1 kHz with 10% accuracy, the internal resistance of the signal source should be about 2 GΩ or higher. We now know that the input resistances of small cells can be as high as that. But in the early 1970s the conventional microelectrode techniques required large cells for reliable current measurements, and these typically had input resistances in the range 100 kΩ to 50 MΩ. Thus, it seemed impossible to reach the required resolution with standard techniques and standard preparations. What was required was a smaller signal source.

It was clear that they should be good tools for single-channel measurements, if only the *pipette-to-membrane seal* could be made good enough. The impedance of the patch itself should be higher than required, even for a patch as large as 10 μm in diameter. An incomplete seal, however, is "seen" by the measuring amplifier in parallel to the patch, and its noise is superimposed onto the patch signal.

Principles of Patch Clamp Recording

As is known, there is a resting potential (RP) across the membrane of most cells, and based on it action potentials (AP) or local responses can occur. All these electric phenomena involve specific states or activities of different ion channels and pump proteins in the membrane. The commonly cited explanation can be found in any textbook of general physiology, so we only present an amended equivalent circuit (Fig. 1) for a membrane patch, which is useful for understanding various electric phenomena that occur in the cell membrane.

This circuit includes multiple branches but only two nodes. Channels for different ions are equivalent to voltage sources, whose electromotive forces are equal to their respective equilibrium potentials determined by the Nernst formula, and whose internal resistances depend on the permeability of the membrane for, and the diffusion coefficients as well as the concentrations of, respective ions, etc. The ion pumps can be represented by corresponding current sources, all of which can be summed up forming one current source as shown in Fig. 1. If there exist transporters in the membrane, they can be electrically modeled (omitted in Fig. 1) in the same way as pumps. The capacitor represents the effect of the lipid bilayer of the membrane together with the extracellular solution (or the bath solution under artificial conditions) and intracellular solution. All these branches are arranged in parallel.

If no external circuit acts on the membrane, and the membrane potential is constant or changes very slowly, its value can be given by the node voltage formula:

$$\begin{aligned} V_{\mathrm{m}} &= \frac{E_{\mathrm{K}} g_{\mathrm{K}} + E_{\mathrm{Na}} g_{\mathrm{Na}} + E_{\mathrm{Ca}} g_{\mathrm{Ca}} + E_{\mathrm{Cl}} g_{\mathrm{Cl}} - I_{s-\mathrm{pump}}}{g_{\mathrm{K}} + g_{\mathrm{Na}} + g_{\mathrm{Ca}} + g_{\mathrm{Cl}}} \\ &= \frac{\sum E_j g_j - I_{s-\mathrm{pump}}}{\sum g_j} \end{aligned}$$

Incidentally, if g_{K} is much larger than the conductance for other ions, and the contribution of the net pump current to V_{m} is small enough to be omitted, which is the case for most cells at rest, it can be seen that RP = $V_{\mathrm{m}} \approx E_{\mathrm{K}}$.

If the state of a certain kind of ion channel changes, there generally occurs a change in more than one channel current, accompanied by a change in the membrane potential, i. e. hyper- or hypo-charge of the membrane capacitance.

What interests us most is what ion channels mediate a certain cellular electric activity caused by a certain factor such as alteration in V_{m} or a chemical (ligand) stimulus. Some ion channels are voltage dependent, that is, their permeability changes with the alteration of V_{m}. By holding and changing V_{m} artificially to measure the currents through these channels we can get the details of their voltage-dependent characteristics. On the other hand, many channels such as ligand gated ion channels and G-protein coupled ion channels are chemical dependent, and also respond to V_{m} alteration passively (i. e. voltage independent: the response current is linear with V_{m} alteration with the permeability or conductance of the ion channel remaining constant) or even actively (i. e. voltage dependent as explained above). Under normal circumstances, the activity of these channels caused by a chemical is accompanied by the change in membrane potential. To distinguish between the effect of a chemical and that of V_{m} alteration, it is necessary to fix V_{m} at a constant level to remove the influence of the V_{m} alteration, or at different levels stepwise to observe the amplitude and configuration of the channel current traces for analyzing its ionic mechanisms. The following is a further discussion using some concise and explicit formulae.

V_m is set at a constant level. Once V_{m} is set constant, the capacitive current is zero. This means that the current recorded via the recording pipette equals the transmembrane current (current carried by ions flowing through channels and ions transported by pumps); or briefly speaking, the current recorded is the transmembrane current.

In this case, the current via each kind of ion channel can be expressed as

$$I_j = (V_{\mathrm{m}} - E_j) g_j$$

And the active current caused by the activity of this kind of channel is

$$\Delta I_j = (V_{\mathrm{m}} - E_j) \Delta g_j$$

The whole transmembrane current (including that carried by ion pump s) is

$$I = \sum (V_{\mathrm{m}} - E_i) g_j + \sum I_{s-\mathrm{pump}}$$

and the whole active transmembrane current is

$$\Delta I = \sum (V_{\mathrm{m}} - E_j) \Delta g_j + \sum \Delta I_{s-\mathrm{pump}}$$

It is clear that the term $\Sigma(V_m - E_j)\Delta g_j$ represents the current response caused by the activity of ion channels, and the term $\Sigma \Delta I_{s-\text{pump}}$, by the activity of ion pumps.

V_m is set dynamically from one definite level to another. If V_m clamped jumps from an initial level to a new one, that is, an artificially controlled step voltage $g\Delta V_m$ occurs across the cell membrane, and it causes the activity of some ion channels, the transmembrane current will change from $\Sigma(V_m - E_j)g_j$ to $\Sigma(V_m + \Delta V_m - E_j)(g_j + \Delta g_j)$ (pump currents are omitted here for simplifying the discussion), and the alteration of the transmembrane current will be

$$\Delta I = \sum \Delta V_m g_j + \sum (V_m + \Delta V_m - E_j)(\Delta g_j)$$

The term $\Sigma \Delta V_m g_j$ is the linear transmembrane current change caused by the step voltage, i. e. the passive current response. It can be removed using leak subtraction function for a better observation of the current change caused by the activity of ion channels, i. e. the active current response, which is represented by the term $\Sigma(V_m + \Delta V_m - E_j)(\Delta g_j)$.

Based on the above important concept, the reversal potential V_{rev} is easily accessible. It generally refers to the membrane potential at which the active current response to a kind of stimulus disappears, and beyond which it reappears but flows in the opposite direction. So, let $\Sigma(V_m - E_j)\Delta g_j$ be zero in case (1), or let $\Sigma(V_m + \Delta V_m - E_j)(\Delta g_j)$ be zero in case (2), and we arrive at: $V_{\text{rev}} = (\Sigma E_j \Delta g_j)/(\Sigma \Delta g_j)$ (pump currents are omitted, and note that V_{rev} refers to V_m in case (1) and to $V_m + g\Delta V_m$ in case (2)). This is a general formula for discussing reversal potential, and it is helpful in exploring the mechanism underlying a current response that has been observed.

Four Configurations

Figure 2 shows the four configurations of patch clamp technique. They are discussed as following.


Cell-attached recording
Recording pipette
Mild suction
Tight contact between pipette and membrane
Whole-cell recording
Strong pulse of suction
Cytoplasm is cotinuous with pipette interior
Inside-out recording
Expose to air
Cytoplasmic domain accessible
Outside-out recording
Retract pipette
Ends of membrane anneal
Extracellular domain accessible

Patch Clamp Measurements On-Chip, Figure 2 Four configurations of patch clamp

On-Cell Patch Clamp

A cell-attached (single-channel) voltage clamp is a form of patch clamp when the voltage of only a small part of the cell is controlled allowing current flowing through individual ion channels to be distinguished.

This technique is based on a very simple idea. A pipette with a very small opening is used to make tight contact with a tiny area, or patch, of neuronal membrane. After the application of a small amount of suction to the back of the pipette, the seal between pipette and membrane becomes so tight that no ions can flow between the pipette and the membrane. Thus, all the ions that flow when a single ion channel opens must flow into the pipette. The resulting electrical current, though small, can be measured with an ultrasensitive electronic amplifier connected to the pipette. Based on the geometry involved, this arrangement usually is called the cell-attached patch clamp recording method.

As with the conventional voltage clamp method, the patch clamp method allows experimental control of the membrane potential to characterize the voltage dependence of membrane currents.

Whole Cell Patch Clamp

A whole cell voltage clamp is a form of patch clamp where electrical access is gained to the whole of the cell (usually



Patch Clamp Measurements On-Chip, Figure 3 Multi-pipette tip on-chip fabrication

by disrupting the membrane underneath the pipette by suction), allowing the electrical activity of the whole cell to be measured.

If the membrane patch within the pipette is disrupted by briefly applying strong suction, the interior of the pipette becomes continuous with the cytoplasm of the cell. This arrangement allows measurements of electrical potentials and currents from the entire cell and is therefore called the whole cell recording method. The whole cell configuration also allows diffusional exchange between the pipette and the cytoplasm, producing a convenient way to inject substances into the interior of a *patched* cell.

This is a powerful technique for studying ionic currents at the level of the whole cell membrane.



Patch Clamp Measurements On-Chip, Figure 4 The steps in fabricating a silicon substrate for use as a planar patch clamp. Circles (2 μm diameter) were defined in a photoresist (white layer) using optical lithography and then etched to a depth of 20–40 μm using deep reactive ion etching. The SU-8 resist was then stripped off with an acid bath and the wafer was inverted for back-side processing. A 1 mm diameter well, centered on the 2 μm pore, was defined using optical lithography. Deep reactive ion etching was used to etch the 1 mm well to a depth such that a small pore was formed connecting the base of the well to the other side of the wafer. A 0.5–1 μm thick SiO_2 film was then deposited over the surface of the entire wafer (using PECVD). This film electrically isolates the front side of the wafer from the back and reduced the pore diameter to 1.5–1.8 μm. The deposition conditions could be varied to deposit thicker oxides and thereby reduce pore diameters as small as 0.7 μm

Inside-Out Patch Clamp

Once a tight seal has formed between the membrane and the pipette, small pieces of membrane can be pulled away from the cell without disrupting the seal; this yields a preparation that is free of the complications imposed by the rest of the cell. Simply retracting a pipette that is in the cell-attached configuration causes a small vesicle of membrane to remain attached to the pipette. By exposing the tip of the pipette to air, the vesicle opens to yield a small patch of membrane with its (former) intracellular surface exposed. This arrangement is called the inside-out patch recording configuration.

This is a true single-channel patch clamp mode allowing the measurement of single-channel currents with the



Patch Clamp Measurements On-Chip, Figure 5 Assembly of the patch clamp device. (**a**) Aligning and sealing the processed silicon chip (grey wafer) between an upper and lower chamber (yellow and blue) electrically isolates one side of the chip from the other (except through the pore in he silicon), and enables independent experimental manipulation of each side. The top and bottom chambers are composed of cured PDMS (yellow) coupled to machined polycarbonate (light blue) supports. The bottom polycarbonate support interfaces the lower PDMS vertical channel to a syringe which is used to apply negative pressure. (**b**) Except for the area immediately surrounding the pore on the topside and the 1 mm well on the underside of the chip, the entire top and bottom surfaces of the silicon wafer were stamped with SU-8 photoresist (green) to enable sealing to the PDMS layers and reduce the chip capacitance to as low as 15 pF. (**c**) A single RIN m5F cell is drawn onto the pore (black spot) following suction. A few seconds after landing on the pore, an individual cell tends to center itself over the pore. This image is of a chip that was recycled after being previously used to patch clamp a cell

added benefit of making it possible to change the medium to which the intracellular surface of the membrane is exposed. Thus, the inside-out configuration is particularly valuable when studying the influence of intracellular molecules on ion channel function, like calcium or ATP.

Outside-Out Patch Clamp

If the pipette is retracted while it is in the whole cell configuration, a membrane patch is produced that has its extracellular surface exposed. This arrangement is called the outside-out recording configuration.

This is a true single-channel recording mode. The patch can be superfused on the extracellular side with solutions containing materials such as neurotransmitters, agonists like GABA or glutamate to activate receptor channels in the patch. This range of possible configurations makes the patch clamp method an unusually versatile technique for studies of ion channel function.

Examples of Patch Clamp On-Chip Design and Fabrication

Multi-Pipette Tip On-Chip Fabrication Based on Polydimethylsiloxane (PDMS)

To scale up fabrication of the planar PDMS, as a typical example, a 4×4 on-chip array described in literature is given here.

The 4×4 array of 400 μm deep, self-terminated pits spaced 1 mm apart was anisotropically etched in a silicon wafer. The strategy was to use the precision of silicon micromachining to create a master structure e with good ordering that would define a shape similar to the tip of a glass micropipette in a thin sheet of molded PDMS. That shape was then transferred through two PDMS molding steps into an array of pyramids in polyurethane (see Fig. 3). An important step in forming the PDMS in step 4 of the figure was the treatment of the first PDMS mold so that the two PDMS layers could be separated. The final PDMS electrode partition was formed by pouring freshly prepared PDMS onto the polyurethane mold and then capping the polyurethane pyramids with a glass slide (step 6). The contact between the tip of the polyurethane pyramid and the glass slide excluded the PDMS to form small apertures. The size and shape of the aperture depended on the amount of contact with the glass slide. The authors chose polyurethane because it deforms sufficiently when contacting the glass slide to make holes 4 – 20 μm in size.

For patch clamp measurements the PDMS planar electrode array was plasma-oxidized then mounted in the recording system shown in Fig. 6. To electrically isolate each electrode, the partition was sealed onto the chamber bottom over an array of openings that each contained an Ag–AgCl wire and suction tubing. The Ag–AgCl wire was connected to the multiplexer chip mounted on the circuit board under the chamber. The multiplexer then connected to the input of the amplifier. The tubing connected to a suction manifold that permitted individual or global suction.

The electrode resistance values were measured to confirm that the electrodes were electrically isolated and that the apertures were open. Fig. 6 shows a *macro-patch* recording obtained when a devitellinized oocyte, expressing Shaker potassium channels, was dropped onto an aperture. The ionic currents carried by a population of ~ 80 Shaker channels were measured in response to positive step changes in membrane potential. The overall success rate for forming a gigaseal on a xenopus oocyte using a planar PDMS patch electrode was 13% (10 out of 75). This is lower than the ~ 40 % success rate for the conventional patch electrodes with or without PDMS coating and surface treatment.

In general, a planar electrode has many advantages over the conventional patch pipette electrode. First, the planar electrode can be easily scaled to an array of electrodes to permit multi-cell or multi-site measurements. Second, the planar electrode has the potential for integrating microfluidic lines that would permit exchange of the electrode solution, something rarely achieved with a micropipette. The amplifier electronics can also be integrated into the substrate of the electrode for improved noise performance. Third, a planar electrode can be mounted over a fluorescence microscope to simultaneously record electrical and optical signals.

Also, micromolding a planar electrode from PDMS has advantages over the other microfabricated planar electrodes under development. First, the fabrication is simple and economical so that the electrodes are disposable, therefore eliminating the difficult step of cleaning the device. Second, microfluidic lines can be micromolded in the same structure or added by bonding PDMS layers. Third, PDMS is optically transparent so that alignment to underlying components can be done visually. The transparency of the material may also be advantageous when integrating an optical recording system. Fourth, the PDMS surface can be chemically modified to facilitate seal formation.

However, the probe nature of the conventional patch pipette still has its advantages. Most importantly, it can penetrate the top layers of tissue to permit patch clamp measurement on a cell within a tissue. Second, the electrode can be pulled away from a cell to make an *excised patch* recording, useful for applying modifying agents to the patch of membrane. Third, the pipette can be moved quickly between lines of solution flow for quick changes in modifying agents. Integrated microfluidics may negate the need for these last two points but more complicated micromachining may be required to fabricate planar patch electrodes that can penetrate tissue.

The need to plasma-treat the PDMS surface just before use may be a disadvantage of the planar electrode. This would add a plasma system to the required equipment for patch clamp experiments. However, the planar electrodes do not require use of the high-quality optical microscope and micromanipulators currently required for patch clamp recording. In addition, conventional patch pipettes commonly require several processing steps before use including heat polishing and coating.

Patch Clamp Device On-Chip Fabrication

As another typical example, a method for silicon chip-based patch clamp electrodes integrated with PDMS microfluidics is given in the following.

Silicon Chip Microfabrication. Up to 80 silicon chips to be used for patch clamping experiments were parallel fabricated in a single sequence of steps (Fig. 4) using stand-alone processing tools. Patterns for pores were defined using a photoresist in concert with a custom-designed mask and a mask aligner (operating with 365 and 405 nm radiation lines and in constant power mode). The patterns were developed to etch out the pores using a plasmatherm deep reactive ion-etching system. In the region surrounding the pore, the silicon wafer was thinned to about $20-40\,\mu$m for the micropores ($1.5-2\,\mu$m diameter) and $10-20\,\mu$m for the nanopores ($0.7-1\,\mu$m diameter). Each wafer was fabricated with a small array of usable pores. In the following, only one device was used for any given experiment, and so the chips were diced into 8×8 mm sections, each containing a single pore. The chips were acid cleaned, rinsed using copious amounts of $18\,\mathrm{M}\Omega$ H_2O and dried under flowing nitrogen. The chips were then coated with a $0.5-1.0\,\mu$m thick insulating film of SiO_2 using plasma-enhanced chemical vapor deposition (PECVD). The top side of the chip was exposed for $20-40$ min and the bottom side was exposed for $10-20$ min. This procedure shrunk the pore diameters by about $0.4\,\mu$m. For the nanopores, the oxide was deposited at lower pressure. Deposition at lower pressure was necessary in order to increase the oxide density, deposit a thicker layer of SiO_2, and to conserve the circular symmetry of the nanopores. At this point, the tip fabrication process was essentially complete. *PDMS Microfluidic Fabrication.* Fluidic platforms for both the front and back sides of the wafer were prepared from micromolded PDMS. For most measurements, the chambers simply allowed for separate chemical access to the front and back sides of the micropore. The minimum microfluidic channel widths were $100\,\mu$m and the typical channel heights were $100\,\mu$m. A mold master was photolithographically patterned into a spin-coated film of photoresist on silicon as described in the literature. The microfluidic channels that were used for cell focusing consisted of two layers of micromolded PDMS that formed one final microchannel network component. The bottom layer of the PDMS microchannel network defined the focusing channels which interfaced the silicon substrate, and the top layer interfaced the focusing channel to larger channels that had inlet and outlet ports. Modified syringe needles were pierced through the top layer to connect the input and output ports with Teflon tubing for the introduction and extraction of cells and solutions. The focusing channel was designed to allow for optical access to the micropore region when the syringes were in place.

Device Assembly. The molded PDMS fluidic chambers were pressure bonded to the silicon chips (Figs. 5a,b). This chemically isolated one side of the pore from the other, thereby creating a device that enabled independent experimental control of each side of the pore (or membrane sealed over the pore). To prevent electrical leak around the silicon chip, SU-8-5 photoresist was applied around the edges of the surface of the chip with a cotton swab (Fig. 5b) or by transferring the SU-8-5 with a PDMS stamp, and then cured. This coating not only permitted a quick, greaseless method for sealing the chip surface to the PDMS surfaces of the experimental cell-chip chamber (Fig. 5a), but it also reduced the chip capacitance. Chip capacitance values as small as 15 pF were achieved when the stamping technique was utilized. However, for the devices that were integrated with PDMS microchannels, little or no SU-8 resist was applied, since the PDMS channels themselves prevented solution leak around the silicon chip and minimized stray capacitance. In order to recycle the same batch of chips several times, the SU-8 resist and oxide layers were sequentially stripped away using standard oxidizing solutions. First, an oxidizing clean (2:1 concentrated H_2SO_4:H_2O_2 (30 %)) was used to remove the SU-8-5 resist. Next, the oxide was stripped using a buffered oxide etching (BOE) solution. The oxide layer was then re-deposited using PECVD.

Electrophysiology recordings. To record currents from sealed cells, the silicon chip assembly was used as a chamber for a voltage clamp setup (Fig. 6). Each half of the chamber (top and bottom) was connected to the electrodes of a headstage. The top chamber was connected to the input of the patch clamp amplifier and the bottom chamber was connected either to either the ground or the command voltage depending on the amplifier used.

The silicon chip device, coupled to a voltage clamp setup was prepared for cells by adding external and internal solution to the top and bottom chamber, respectively. An amount of 50 μl of cell solution (about 5×10^4 cells) was introduced into the top chamber with a syringe that had a 2 cm piece of Teflon tubing on its tip. The cells were tracked by viewing the top surface of the chip with a microscope and by monitoring the electrical resistance across the pore. Once the cells covered 20 – 30 % of the chip surface, gentle suction was applied from the bottom chamber side. The progress and quality of the seal of a cell over the pore was monitored visually through the microscope and by measuring the capacitance and resistance across the pore. Once the seal reached maximum resistance, the suction was released and electrophysiological recordings from the cell were made.

Key Research Findings

The inherent complexity of the technique limits its uses in high-throughput screening for drug discovery and drug safety. To meet high-throughput screening requirements, many efforts have been made to improve the patch clamp system. Planar patch clamp electrodes, scalable and easy to use, have been fabricated using silicon oxide-coated nitride membranes, deep reactive ion etched silicon holes coated with PECVD oxide, polyimide films, track-etched quartz, silicon oxide nozzles, glass substrates and oxygen



Patch Clamp Measurements On-Chip, Figure 6 Planar PDMS patch electrode array recording of Shaker potassium channel currents. (**a**) Schematic of planar patch electrode array recording system. The 400 mm thick, oxidized PDMS partition is sealed onto the chamber bottom with vacuum grease. The chamber bottom contains an array of openings, each containing tubing and an Ag–AgCl wire. The tubing connects to a suction manifold and the Ag–AgCl wire connects to a multiplexer chip on the circuit board under the chamber bottom. The multiplexer connects each contact to the amplifier electronics. Another Ag–AgCl wire in the bath solution connects to the ground of the amplifier. Bath solution is exchanged through solution lines into and out of the bath chamber. A devitellinized oocyte is dropped onto the aperture to make a patch clamp recording. (**b**) Current traces recorded from a xenopus oocyte expressing inactivation-removed Shaker potassium channels. Each trace represents a step change in membrane potential from rest, 80 mV. Voltage steps are to 50, 20, 40 and 60 mV, as noted, before returning to 80 mV. Leakage currents were subtracted from the raw data by a P/4 protocol (Penner, 1995).

plasma-treated PDMS. Microfluidics have also been integrated with patch clamp systems using PDMS or glass. Those devices have made possible fast fluid exchange for single electrodes.

Some patch clamp setups with more advantages have been developed to be used more easily. For example, a lateral-based patch clamp setup is compatible with high-resolution microscopy (with a working distance in the $100-300\,\mu$m range). The idea is to trap a cell onto a lateral microchannel in a manner which makes it easier in terms of fabrication and fluidic integration. Niels Fertig has made use of state-of-the-art microstructuring techniques to define three-dimensional micro-openings in planar substrates, with the geometry of an inverted patch clamp pipette tip.

Future Directions for Research

The on-chip-based patch clamp technique broadens the possibilities of ion channel analysis by transferring the classic patch clamp principle onto a microstructured chip format. The planar patch clamp technique enables the automation and parallelization of ion channel measurements. This is an example of the beneficial integration of microtechnological processes in the field of cellular electrophysiology. The chip-based patch clamp technique not only improves ease of use as well as throughput capability compared to conventional patch clamping, but also opens new experimental possibilities for the biophysical characterization of ion channels such as intracellular perfusion or optical accessibility of the chips for combined optical and electrical recordings from ion channels. The automated and parallel patch clamp methods should be further developed in the near future for academia and industry.

Cross References

► Ion Channel

References

1. Neher E (1991) Ion channels for communication between and within cells. Nobel Lect 9 1991:10–25
2. Sakmann B (1992) Elementary steps in synaptic transmission revealed by currents through single ion channels. Nobel Lect 9 1992:31–59
3. Hübner CA, Jentsch TJ (2002) Ion channel diseases. Hum Mol Genet 11:2435–2445
4. Wood C, Williams C, Waldron GJ (2004) Patch clamping by numbers. Drug Discov Today 9:434–441
5. Pantoja R, Nagarah JM, Starace DM, Melosh NA, Blunck R, Bezanilla F, Heath JR (2004) Silicon chip-based patch-clamp electrodes integrated with PDMS microfluidics. Biosens Bioelectron 20:509–517
6. Klemic KG, Klemic JF, Reed MA, Sigworth FJ (2002) Micromolded PDMS planar electrode allows patch clamp electrical recordings from cells. Biosensors and Bioelectronics 17:597–604
7. Fertig N, Blick RH, Behrends JC (2002) Whole Cell Patch Clamp Recording Performed on a Planar Glass Chip. Biophys J 82:3056–3062
8. Li X, Klemic KG, Reed MA, Sigworth FJ (2006) Microfluidic System for Planar Patch Clamp Electrode Arrays. Nano Lett 6:815–819
9. Brüggemann A, Stoelzle S, George M, Behrends JC, Fertig N (2006) Microchip technology for automated and parallel patch-clamp recording. Small 2:840–846
10. Lau AY, Hung PJ, Wu AR, Lee LP (2006) Open-access microfluidic patch-clamp array with raised lateral cell trapping sites. Lab on a Chip 6:1510–1515

Patch Clamp Technique

► Patch Clamp Measurements On-Chip

Patch Voltage Clamp Technique

► Patch Clamp Measurements On-Chip

PCR Lab-on-Chip Devices

MICHAEL KÖHLER
Stiftungslehrstuhl der Deutschen Bundesstiftung Umwelt,
Institut für Physik, Technische Universität Ilmenau,
Ilmenau, Germany
michael.koehler@tu-ilmenau.de

Synonyms

Microthermocyclers; Chip thermocyclers

Definition

PCR Lab-on-Chip devices are microfluidic instruments for the biochemical amplification of DNA by thermocycling using the polymerase chain reaction at the microscale.

Overview

PCR Lab-on-Chip devices are miniaturized fluidic systems for fast DNA amplification. The polymerase chain reaction (PCR) is a molecular biological technique for addressing and exponentially amplifying a DNA fragment. The PCR process is based on temperature cycles with an enzymatic amplification step. It works without the use of a living cell. For PCR, a liquid mixture of an analyte



PCR Lab-on-Chip Devices, Figure 1 Temperature protocol for PCR with repeated thermal addressing of process steps; nominal and real temperature tracks (double-strand separation, primer annealing, primer extension)

containing DNA with an amplification buffer solution containing nucleoside triphosphates (building units for DNA synthesis), primers (starter molecules), catalyst (the enzyme polymerase) and some additives is applied. The exponential increase of concentration of the sequence of interest is due to the doubling during each temperature cycle. The synthesis of a daughter strand of DNA on a mother single strand (template) occurs by template-directed condensation of nucleotides. The primers are applied for addressing a selected sequence part of DNA template molecules from the analyte sample carrying the genetic information of interest. Very small amounts of interesting DNA are required. Under optimized conditions, a single template DNA molecule is sufficient for starting the process. DNA fragments up to about 10,000 base pairs can be amplified by PCR.

The addressed sequence is identically replicated to a large extent during the thermocycling process. The miniaturization by transferring the technology from classic block thermocyclers into Lab-on-Chip devices is associated with a miniaturization of sample and with a large reduction of process time. In addition, Lab-on-Chip PCR allows the integration of sample preparation and post-amplification treatments including labelling and/or separation in order to realize a completely automated process chain in a miniaturized system. DNA microanalysis systems can be built, in which the micro PCR is the key operation for getting the molecular information carrier in a concentration suited for convenient signal readout.

Amplification of DNA by Lab-on-Chip PCR is mainly used for genotyping. In connection with a reverse transcription process using RNA-dependent DNA polymerase, this technique can also be applied for the characterization of RNA, in particular for the identification and measurement of messenger RNA. As a result, the Lab-on-Chip PCR devices can be also applied for gene expression studies.

The application of PCR chip devices is connected with several important advantages with respect to conventional systems:

- low sample volumes
- very fast process steps
- low power consumption, suited for point-of-care diagnostics
- well reproducible temperature protocols
- processing of larger sample series under the same conditions
- low space requirements of devices
- integration of functions like reverse transcription process (for gene expression studies), on-line measurement of double-strand DNA concentration or real-time measurement by multi-sensor arrangements.

Hence, miniaturized PCR devices are very interesting for a broader application of PCR in laboratories as well as for point-of-care diagnostics, screenings or investigations for food safety and environmental protection.

Basic Methodology

The basic technique is the PCR invented by K. Mullis in 1983. This technique allows one to replicate DNA identically without any living cell. The PCR has developed



PCR Lab-on-Chip Devices, Figure 2 Principal molecular processes of PCR during thermocycling

into a common technique used in medical and biological research and diagnostics as well as in forensic, archaeological and other investigations. It is the key method for sequencing of genes, for the diagnosis of hereditary diseases, for paternity testing and for molecular identification of infectious microorganisms.

The PCR technique succeeds by the use of the DNA-dependent DNA polymerase from bacteria living in hot sources (taq-polymerase). This enzyme is able to elongate primers (oligonucleotide starter molecules) in a complementary pattern to a template DNA single strand at a temperature of about 70 °C. This high temperature is necessary in order to create a temperature-controlled three-step process. The whole process includes the following steps:

1. the initialization step for denaturation of DNA double strand into two single strands at about 95 °C by thermal disruption of the hydrogen bonds between the complementary bases in the double strand;
2. the addressing of a short well-known sequence pattern by base-pairing of primers (*primer annealing*) at suitable temperatures in the range between about 45 and 65 °C depending on primer length, AT/CG ratio and desired selectivity; and
3. the elongation of the primers with the complementary order of nucleotides by the synthesis of the new DNA strand by the enzymatic activity of the taq-polymerase (*primer extension*).

Two suitable primers are applied in order to generate both new complementary single strands of a selected DNA sequence in the replication during one temperature cycle. The repeated application of temperature (Fig. 1) cycles leads to a fast increase of the concentration of the selected DNA sequence by doubling the DNA in each cycle (Fig. 2). As a result, the selected sequence can be amplified by a factor of about 1000 in 10 temperature cycles, by a factor of about 1 million in about 20 temperature cycles and about 1 billion in 30 temperature cycles. This amplification is high enough for all characterization techniques like fluorescence detection, electrophoretic characterization, sequencing or chip hybridization. PCR bridges the gap between the molecular diversity in living nature using small numbers of key molecules and the analytical tools of chemistry and sensorics (Fig. 3).

Classic PCR is performed in Eppendorf tubes, microtiterplates or similar repositories by conventional thermocyclers with thermostatted blocks. The typical time required


10^20
classical synthesis
number of equal molecules
conventional analytical chemistry
HTS & CC
Biochips
(PCR)
living nature
1
1
10^6
number of chemical species

PCR Lab-on-Chip Devices, Figure 3 Schematic of PCR as gap bridging technology between the biomolecular and chemical worlds: number of molecular species (types) and number of molecules of the same type in chemical and biological systems



PCR Lab-on-Chip Devices, Figure 4 Example of a silicon chip thermocycler (IPHT Jena, Germany): microlithographically patterned thin-film transducers at the back side (above), liquid chambers and air chambers for heat transfer control at the front side (below)

is in the range of about 90 min up to about 3 h. Faster working thermocyclers need powerful heaters as well as coolers in order to realize high heating and cooling rates.

The temperature control can be realized by alternating mechanical contact to heating/cooling plates, by fluidic switching between heating and cooling liquids or by Joule heating using thick-film or thin-film microheaters. The latter method is frequently combined with passive cooling by heat conduction or convective cooling. In several chip devices, microheaters and thermal microsensors are prepared in close proximity in order to realize efficient feedback loops in electrical heating.

Despite the high amplification factor, the volumes can be small that have to be operated in thermocycling for PCR. So, DNA amplification can be done with volumes in the lower µl or in the nl range. The reduction of sample volume gives the possibility to apply chip devices or other miniaturized systems for the PCR. The reduction of size allows a crucial enhancement of heating and cooling rate and at the same time a reduction of power consumption. Power reduction and process rate enhancement become possible due to the lowering of parasitic heat capacitances and by efficient transfer of heat inside the system. So, miniaturized PCR devices can work at high process speed with low power requirement. Therefore, they are particularly applicable for hand-held devices, mobile analytical systems and microautomated systems.

Microtechnology offers two different strategies for Lab-on-a-Chip PCR. The first is the stationary concept. This concept corresponds to the classic thermocycler. The core element is a miniaturized chamber for PCR liquid equipped with heaters and temperature sensors (Fig. 4). Fast PCR is realized by fast heating and cooling the whole system. The maximum process rate is mainly determined by the ratio of heating and cooling power to the heat capacity of chamber and sample. The second strategy is based on a microflow-through concept. The device contains a long microchannel, which is conducted in meanders through three temperature zones (Fig. 5). Thus, the three regions of the device remain at constant temperature, and the temperature cycling is realized by changing contact of the liquid with the three different temperature zones. The maximum process rate is mainly determined by the heat capacity of the streaming liquid itself and by the heat conduc-



PCR Lab-on-Chip Devices, Figure 5 Principle of construction of a flow-through chip thermocycler

tivity between sample and walls. In principle, the time for single temperature cycles can be reduced down to a few seconds. The whole PCR process with 20 – 40 cycles can be done in time scales between a few minutes and about half an hour.

The acceleration of the PCR process is a very important advantage of PCR Lab-on-a-Chip systems. A second advantage is in the possibility to integrate further functions into the microdevice. Thus, steps of sample preparation as well as separation and detection supporting process steps can be integrated. In this way, miniaturized DNA analysis systems are constructed, in which the Lab-on-Chip amplification by PCR is the central process.

Key Research Findings

The motivation for miniaturization of PCR was driven by several factors. First, PCR should be made faster in order to get results more quickly. Second, larger sets of samples should be processed. Third, DNA-based diagnostics should be evolved from a laboratory technique requiring experienced specialists to an automated on-site diagnostic method operated after brief instructions by anybody. Finally, the amplification by PCR should be integrated in a diagnostic chain (μ-TAS concept) and implemented in a miniaturized transportable system. The power consumption of the thermocycling process should be as low as possible.

The simplest way for meeting the requirements mentioned above and realizing micro-PCR on-a-Chip consists in a transfer of the conventional PCR technique into a microchamber chip. Therefore, microchambers for liquid volumes between a few μl and several hundred nl were etched anisotropically in silicon wafers. A lithographically micropatterned metallic thin-film system at the backside of the wafer was applied in order to control temperature by Joules heating and thermoresistive temperature measurement. Metal film thicknesses of about 1 μm or several hundred nm were sufficient for achieving all temperatures necessary for PCR. The bottom membrane of the chamber carrying the metal transducers was built by the residual silicon thickness after time-controlled chamber etching. The high heat conductivity of the material guaranteed a fast heat transfer between the thin-film transducers and the liquid.

The cooling steps of PCR could be realized by direct contact of the bottom membrane with a cooling element (e.g. a Peltier cooler) or by indirect cooling using the passive heat transfer from the silicon chamber to ambient. For the second method, the fine tuning between temperature homogeneity in the core region of the PCR chamber and temperature gradients between core region (with PCR chamber) and the outer frame region of the microsystems were of particular importance. The problem was solved by the definition of spatially restricted areas *(heat conduction beams)* for passive heat transfer between core and frame by etching holes into the silicon. Optimized chips supplied high temperature homogeneity in the core region of PCR chips and heating and cooling rates of 40 – 80 K/s. Cycle times could be downscaled to a few seconds. The time required for the whole PCR process could be reduced down to 30 – 10min.

An important advantage of microchamber chips, beside the good dynamics, is the flexibility. Temperature/time protocols can easily be adapted and varied. Thus, this technique is useful for the development and optimization of protocols.

Microtiterplates (MTPs) are the most commonly used chamber arrays for PCR. The open chambers have to be covered by oil or sealed by membranes in order to suppress evaporation of water during the process. A fast working PCR in arrays can be realized, if small chamber volumes are applied and the wall thickness of the plate material is thin enough for fast heat transfer. Such chamber arrays can be prepared by in situ forming of array plates by means of a thermostatted block suitable as metal master. A further miniaturization of chamber volumes is possible by using nanotiterplates (NTPs). Microlithography allows the preparation of chambers in the lower μl range as well as over the whole nl and pl range. There are technologies for preparation in silicon as well as in glass. Polymer carriers are made in many cases by replication from microstructured silicon or glass master chips. A wide spectrum of materials is available for NTPs. The thermostatting can be realized by the conventional incorporation of the sealed NTPs in metal block devices or by integration of thermal transducers in the carrier systems. The application of micropatterned thin-film heaters



PCR Lab-on-Chip Devices, Figure 6 Micro-flow-through PCR in tube arrangements: (**a**) spiral-like arrangement (two-dimensional), (**b**) helical arrangement (three-dimensional)

and thin-film sensors for direct thermostatting of NTPs is compatible with well-established microsystem technologies using glass and silicon substrates. It is more difficult in the case of polymer materials. The high conductivity of silicon is responsible for the attractiveness of using these materials for all processes connected with fast temperature changes. Silicon carriers are of particular interest for NTPs used in PCR. The comparatively high affinity of silicon against proteins is a disadvantage and demands special surface covering or chemical surface modifications (see below).

The power consumption for heating and cooling of samples can be reduced if the temperatures in the device are kept constant in three different regions and the sample is moved between these three regions. This movement can be operated at the surface of a thermostatting chip, for example by electrostatic manipulation or by surface acoustic waves (SAWs). Therefore fluidic transport paths (hydrophilic areas) are defined lithographically in a hydrophobic environment on a piezoactive substrate like lithium niobate. The excitation of SAWs is realized by microlithographically prepared thin-film electrodes. SAW systems are of particular interest due to the fast manipulation and the very efficient mixing processes, which can be applied also for sample preparation. The small volumes of droplets make the evaporation of water a serious problem. This can be overcome to a certain extent by oil covering.

The evaporation of solvent can be avoided completely if closed microchannels are used for a micro-PCR with moving of samples between different temperature zones. The simplest variant consists of a flow-through PCR realized in a tube, which is conducted repeatedly through the three temperature zones. There are two principal geometries for the arrangement of tubes. In one variant the tube is coiled in one plane like a spiral (Fig. 6a). This geometry can be easily realized. But, this arrangement suffers from increasing or decreasing residence times in all three temperature zones due to the changing diameter of the tube loops. The alternative is a three-dimensional, helical arrangement of the tube. In this geometry, the conditions at all temperature cycles can be kept equal (Fig. 6b).

A certain disadvantage of using tubes is the low heat conductivity of polymer tube materials and the comparatively high thicknesses of tube walls. This leads to low temperature gradients. As a result, the outside temperature must be adapted to the flow rate-dependent heat required inside the tube and the heat transfer conditions in the tube wall.

The principle of flow-through PCR can further be miniaturized and optimized with respect to heat transfer conditions by realizing flow-through chip thermocyclers. These are devices for flow-through PCR on silicon, glass or polymer chips. The use of silicon (high thermal conductivity) and glass (low heat conductivity) in one device allows convenient control of temperatures in the three process zones by choosing a suitable local heat capacity and heat exchange conditions. In analogy to chip chamber cyclers, etched holes in silicon support the thermal separation of temperature zones, and thin-film resistors are applied for heating and electroresistive temperature measurements.

DNA amplification can occur either in a continuous flow mode or in a serial flow mode. In the continuous flow mode, a template is mixed continuously with the PCR mix and transported through the flow thermocycler. This mode is well suited for preparing amplificates of a certain DNA sequence in constant quality. In contrast to continuous amplification, most PCR applications are found in analytics. Therefore, the enhancement of throughput of samples in one analytical system is the deciding parameter. In principle, series of template-containing samples can be applied in a certain clock pulse in a flow-through system. But, the subsequent injection of different samples in



PCR Lab-on-Chip Devices, Figure 7 Schematic of integration of PCR in a μ-TAS arrangement with sample pre-treatment and separation/detection unit

continuous flow leads to strong cross-talk effects due to the fluidic dispersion which is caused by the laminar flow behaviour in the microtubes and microchannels. This fluidic cross-talk is particularly critical due to the exponential character of the amplification process during PCR.

A crucial improvement of sample separation in serial processing can be achieved by the application of a segmented flow in the micro-PCR. The separation of aqueous fluid segments containing the PCR mix and the different templates by immiscible organic liquids converts the laminar flow to a plug flow. If the inner surface of the wall is hydrophobic, the chemical cross-talk between fluid segments can be suppressed completely. Thus, the segmentation of flow improves the transport behaviour as well as inhibiting effects of the wall. In addition, the plug flow guarantees constant residence times for all samples and all volume parts of one sample in all temperature regions and in all cycles. The segmented flow principle can be applied for both microtube PCR and on-chip PCR.

Serial PCR using flow segments allows comparatively high sample frequencies. The generation of segments can occur up to frequencies of some tens per second. Reconsidering a certain redundancy (several segments of the same sample), it is possible to process in the order of 10^4 samples per hour. This high throughput power of serial flow micro-PCR makes this technique interesting for screening procedures with well-standardized protocols. The fixed definition of temperature protocols is necessary because the length of capillaries or tubes in the different temperature zones is fixed. Changing of flow rate leads only to a proportional change in all temperature zones. The ratio of residence times is fixed by the design of the flow-through device. So, flow-through thermocyclers are much more efficient than chamber thermocyclers, but less flexible. Flow-through PCR is therefore preferably applied for well-defined analytical problems with high numbers of analogue samples.

A big additional advantage of flow-through processes in comparison with stationary processes consists in the possibility of implementation of process chains (Fig. 7). In this way, complete microanalytical systems can be designed. They can include sample pre-treatment like cell separation, cell lysis or chemical separation. Reverse transcription processes can be directly connected on-chip with the DNA amplification by thermocycling (RT-PCR). The analytical chain can also include post-amplification steps like fluorescence labelling, separation by capillary electrophoresis or hybridization on DNA chips.

Chemical compatibility is a particularly important problem for Lab-on-Chip PCR devices. The taq-polymerase possesses a certain surface affinity due to their amphiphilic character. In addition, the low start concentrations of DNA for amplification are critical if the molecules are adsorbed at wall surfaces. The molecule–surface interactions are particularly critical due to the high surface-to-volume ratios in chip devices. The suppression of undesired adsorption demands inert materials. Polymers like polypropylene or polytetrafluoroethylene are much better suited than glass or silicon. The OH groups at the surface of native glass, silicon or silicon dioxide surfaces are mainly responsible for disturbing adsorption. The affinity of surfaces against the biomolecules can be suppressed by surface treatments. Therefore, alkylsilanization (by alkyltrichlorsilanes or alkyltrimethoxysilanes for example) is particularly suited. The surface properties change during the exposure of walls against cell suspensions and PCR solutions. Certain rinsing, cleaning and resilanization protocols are applied in order to achieve a high reproducibility in the case of reused Lab-on-Chip PCR systems.

Micro-flow-through PCR has been investigated in the last few years for several biological and medical applications. They relate to the identification of DNA in different research experiments, for genotyping of microorganisms, in particular the identification of pathogens, as well as for genotyping of tissue material, gene expression studies using a preceding reverse transcription step for conversion of messenger-RNA into DNA and for adaptation and development studies of insect embryos.

Future Directions of Research

Further research for Lab-on-Chip PCR devices is focused on four main topics: the improvement of the performance of the amplification process, the integration of new functions in PCR-based analytical chip devices, the integration of PCR in microautomated diagnostic systems and the extension of PCR-based nucleic acid microdiagnostics to new applications.

The improvement of heat transfer by optimized channel and wall geometries and the choice of best-suited materials contribute to the enhancement of process speed and to a better control of selectivity. Adapted selectivity can be achieved by realizing well-defined temperature proto-



PCR Lab-on-Chip Devices, Figure 8 Process scheme for use of Lab-on-Chip PCR for expression diagnostics in drug screening

cols for the primer annealing step. Therefore, steep cooling and heating ramps are of interest. Special material combinations and the adaptation of manufacturing technologies are under investigation for the improvement of speed and surface compatibility.

Sample throughput is particularly important for screening processes with large numbers of samples. Low-cost DNA diagnostic tools are necessary for biomedical screenings in order to identify genotype-determined health risks in the human population. They are also of interest for screenings for dangerous microbial genotypes. Despite biomedical, environmental and agricultural screenings, high sample throughput is also required for pharma screenings. Here, expression studies depending on drug concentrations and drug combinations demand low-cost solutions including fast RT-PCR (Fig. 8). Highly parallelized systems and in particular fast working serial PCR systems are of interest for such pharma screenings.

The specific fields of recent and future applications of rapid flow-through chip PCR demand the development of PCR-based chip devices with additional integrated functions for sample pre-treatment, on-line sensing, process control and real-time measurement, for referencing and reproducibility tests. Therefore, further efforts for integration of transducers as well as additional fluid manipulation functions are required.

Process speed, sample throughput as well as selectivity could be improved by ultra-miniaturization of Lab-on-Chip PCR. In nature, DNA amplification takes place in reaction volumes (cells) down to the sub-micrometre level. This corresponds to volumes in the sub-femtolitre range. In principle, the PCR process could be downscaled to this region. Recently, most PCR Lab-on-hip devices are working with sample volumes in the sub-μl and in the nl range. By ultra-miniaturization, these volumes could be reduced by factors of between 10^{-3} and 10^{-7}. Therefore, special strategies of liquid handling and, in particular, microencapsulation techniques, vesicle techniques or ultra-miniaturized segmented flow techniques are necessary.

The very different possibilities of using information from nucleic acids for health care, drug development, environmental control, product and process safety, food control, control of trade and transport and so on demand cost-efficient special solutions with microsystems for DNA or RNA analysis. So, further research will address a wide spectrum of different special diagnostic solutions integrating Lab-on-Chip PCR. The questions of universality, reusability, safety and recyclability will become important, in future, like the questions of costs, operability, robustness and reliability.

Cross References

- ► Droplet-Based Lab-on-Chip Devices
- ► Lab-on-Chip Devices for Biodefense Applications
- ► Microfluidics for Bio- and Chemical Reactions
- ► Microsegmented Flow

References

1. Auroux PA, Koc Y, DeMello A, Manz A, Day PJR (2004) Miniaturised nucleic acid analysis. Lab Chip 4:534–546
2. Curcio M, Roeraade J (2003) Continuous segmented-flow polymerase chain reaction for high-throuput miniaturized DNA amplification. Anal Chem 75:1
3. Easley CJ, Karlinsey JM, Landers P (2006) On-chip pressure injection for integration of infrared-mediated DNA amplification with electrophoretic separation. Lab Chip 6:601–610
4. Fukuba T, Yamamoto T, Naganuma T, Fujii T (2004) Microfabricated flow-through device for DNA amplification – towards in situ gene analysis. Chem Eng J 101:151–156
5. Guttenberg Z, Müller H, Habermüller H, Geisbaurer A, Pipper J, Felbel J, Kielpinski M, Scriba J, Wixforth A (2005) Planar chip device for PCR and hybridization with surface acoustic wave pump. Lab Chip 5:308–317
6. Kopp MU, DeMello AJ, Manz A (1998) Chemical amplification: Continous-flow PCR on chip. Science 280:1046–1048
7. Lee JG, Cheong KH, Huh N, Choi JW, Ko Ch (2006) Microchip-based one step DNA extraction and real-time PCR in one chamber for rapid pathogen identification. Lab Chip 6:886–895
8. Liu CN, Toriello NM, Mathies RA (2006) Multichannel PCR-CE microdevice for genetic analysis. Anal Chem 78:5474–5479
9. Mullis KB, Ferré F, Gibbs RA (1994) The polymerase chain reaction, Birkhäuser, Boston
10. Poser S, Schulz T, Dillner U, Baier V, Köhler JM, Schimkat D, Mayer G, Siebert A (1997) Temperature controlled chip reactor for rapid PCR. Sens Actuators A 62:672
11. Schneegaß I, Köhler JM (2001) Flow-through polymerase chain reactions in chip thermocyclers. Rev Mol Biotechnol 82: 101–121

12. Wilding P, Shoffner MA, Kricka LJ (1994) Clin Chem 40:1815
13. Wooley AT, Hadley D, Landre P, DeMello AJ, Mathies RA, Northrup MA (1996) Anal Chem 68:4081

Peclet Number

Definition

Peclet number is a dimensionless number relating the rate of advection of a flow to its rate of thermal diffusion.

Cross References

- ► Polymer Synthesis within Microfluidic Reactor
- ► Microfluidics for Bio- and Chemical Reactions

Peltier Effect

Synonyms

Thermoelectric effect

Definition

The Peltier effect occurs when an electric current passes through two different connected materials (metals or semiconductors) and thereby generates a temperature difference across the materials.

Perfect Slip

- ► Boundary Slip of Liquids

Peristalsis

Definition

Peristalsis is transport in a flexible duct via traveling contraction waves. Peristalsis is the process by which material is moved through anatomical passages, for example of the digestive tract, by the contraction of smooth muscle in rhythmic waves. In biological systems, peristalsis moves liquids or solids. Micropumps based on the principle of peristalsis have been designed to move liquids and gases.

Cross References

- ► Linear Peristaltic Pumps
- ► Peristaltic Pumps
- ► Rotary Peristaltic Pumps

Peristaltic Pumps

JORDAN M. BERG[1], TIM DALLAS[2]
[1] Nano Tech Center & Department of Mechanical Engineering, Texas Tech University, Lubbock, TX, USA
[2] Nano Tech Center & Department of Electrical & Computer Engineering, Texas Tech University, Lubbock, TX, USA
jordan.berg@ttu.edu

Synonyms

Flexible member pump; Membrane pump; Diaphragm pump; Valveless pumps

Definition

Peristaltic pumps are mechanical displacement pumps that induce flow in a fluid-filled, flexible-walled conduit through ►peristalsis – transport due to traveling contraction waves. While macroscale peristaltic pumps appear in a variety of configurations, micropumps based on this principle almost exclusively use the sequenced contraction and expansion of a small number of discrete actuators – typically three – placed along the fluid channel.

Overview

Peristaltic pumps emulate the biological process of peristalsis, in which material is moved through the esophagus or other anatomical passage by the contraction of smooth muscle in rhythmic waves. Figure 1 is a schematic of a typical ►rotary peristaltic pump, as implemented at the macroscale, in which a set of revolving contact elements creates a traveling compression wave in a section of a flexible tube. Figure 2 is a schematic of a macroscale implementation of a ►linear peristaltic pump, in which a number of translating piston actuators cyclically compress a flexible tube. In either case, a moving boundary displaces fluid and induces a flow, placing peristaltic pumps in the class of positive-displacement pumps. Increasing the tube diameter or the pumping cycle frequency increases the flow rate. A major attraction of macroscale peristaltic pumps is cleanliness. The fluid is completely isolated from the pump components since it never leaves the tube. Furthermore, it is a simple matter to change the tubing to avoid cross-contamination between fluids, and the tubing material may be tailored to ensure compatibility with a particular application. The pumping action is relatively gentle, making peristaltic pumps suitable for reactive liquids or cell suspensions. Also, the pumps may be self-



Peristaltic Pumps, Figure 1 A typical macroscale rotary peristaltic pump design. A set of rotating contact elements cyclically compresses a flexible tube. The elements may roll or slide along the tube; the number of contact elements may also vary. The fluid never leaves the tube, protecting the fluid from contamination by the pump elements, and the pump elements from corrosion or abrasion by aggressive fluids. The tube itself is easily replaced. Tube size and composition may be adjusted to accommodate different fluids, or to change the flow rate. Changing the rotation rate Ω changes the flow rate; changing the sign of Ω reverses the flow direction

priming due to the low-pressure region created behind the moving constriction, and the flow direction can be easily reversed. At the macroscale, use of rotary peristaltic pumps is widespread, while linear peristaltic pumps are found mainly in niche applications, such as intravenous drug delivery.

Cleanliness considerations do not translate to the microscale, nor does the notion of interchangeable components. Therefore, use of peristaltic micropumps must be justified for other reasons. Self-priming and bidirectionality remain appealing features, but perhaps the main benefit is simplicity of design. Any mechanism providing volume change in a chamber or channel is a candidate actuator for a peristaltic pump. For example, a typical active microvalve involves a membrane that can be forced against a seal to close, or pulled away from the seal to open [1, 12]. Two or more active microvalves can be arranged in sequence and actuated with the appropriate phasing to create a linear peristaltic micropump. The principles of peristaltic pumping apply to liquid or gas, and micropumps for both have been demonstrated. The ease with which an actuator can be transformed into a pump accounts for the wide variety of linear peristaltic micropumps that have been reported, including an early micromachined silicon and glass version by Smits (as reviewed in [3, 12], or see the original paper referenced therein).



Peristaltic Pumps, Figure 2 A typical macroscale linear peristaltic pump design. A set of translating actuators cyclically compresses a flexible tube. The number of actuators may vary. Features of macroscale rotating peristaltic pumps also apply to microscale linear peristaltic pumps. Linear peristaltic pumps are used in applications such as drug delivery, when accurate flow rate control is needed

In this article we refer to an actuator as *closed* when the associated chamber or channel volume is minimized, and as *open* when that volume is maximized. The volume in the closed position is called the ►dead volume, and the difference between the volume in the open position and the dead volume is the ►stroke volume. The ►stroke volume divided by the dead volume is the ►compression ratio. Compression ratio is particularly important when pumping gases, since the amount of gas ejected from the actuator is reduced by the compressibility of the fluid. In pure liquids this effect is much less, but compression ratio plays an important role in determining how severely bubbles impact a particular pump. In classifying micropumps, a distinction is sometimes made between ►integrated actuators – fabricated along with the other components of the microfluidic system – and ►external actuators – fabricated separately and attached later. It is common to see peristaltic micropumps of either kind.

While a linear pump can easily be built up from two or more basic actuation units, microscale rotary mechanisms face significant fabrication challenges. Accordingly, rotary peristaltic micropumps have seen very limited implementation. While several rotary mechanical micropumps are described in the literature (see the summaries in [1], [3] and [12], for example), to our knowledge there is only one example in the literature of a true rotary peristaltic micropump; Kim et al. (Sensors and Actuators A 128:43–51, 2006) use a silicone membrane for the deformable channel surface, and a rotating ferrofluid plug driven by an external magnet for actuation. Also notable is a miniature rotary peristaltic pump by Bar-Cohen and Chang (*Smart Structures and Materials 2000: Active Materials:*

Behaviors and Mechanics, *Proceedings of SPIE 3992, 2000*) that employs a traveling flexural wave in a piezoelectric ring. Reflecting their dominance in the literature, the subsequent discussion will consider only linear peristaltic micropumps, which for brevity are henceforth referred to simply as peristaltic micropumps. Most reported microscale implementations approximate continuous peristaltic action using two or more (most commonly three) discrete collapsible chambers. A notable exception, and one which does not fit well into the analysis scheme presented here, is the colloidal peristaltic pump presented in [15]. There a large number (approximately twelve) of 3 μm colloidal silica particles are oscillated sinusoidally in a 6 μm deep polydimethylsiloxane (PDMS) channel using external actuation by optical trapping with a scanned 532 nm laser. Flow rate on the order of 1 nl/h are induced in an aqueous solution by the resulting traveling wave. Peristaltic actuation through movable suspended particles is, to our knowledge, unique to [15]. The remainder of this paper focuses on the much more common case of discrete collapsible chambers.

Peristaltic pumps have found wide application in microfluidic systems based on PDMS, due to their ease of fabrication and versatility in operation. PDMS is a popular material for microfluidics for several reasons. Compared to traditional semiconductor industry fabrication schemes, both the materials and processing tools are inexpensive. PDMS is biocompatible, resistant to many chemicals, and transparent to wavelengths of light useful in chemical and biochemical analysis. Figure 3 shows a typical actuator design, similar to that first reported in [4], with the fluid channels formed between a thin PDMS layer and a glass, silicon, or PDMS substrate, and actuator channels formed at right angles to the fluid channels in a thicker PDMS layer, bonded to the planar side of the fluid layer. We refer to the area of the fluid channel under an actuator channel as a pump chamber, even though it is geometrically identical to the rest of the channel. The actuator channels are inflated from an external pressure source to close the pump chamber; when the pressure is removed the natural elasticity of the PDMS restores the channel to its original shape. As suggested by the figure, due to the low modulus of elasticity of PDMS, the pump chambers may be designed to collapse completely when closed, allowing them to act either in concert for pumping, or in isolation as pure valves.

In a peristaltic pump, the volume of fluid displaced by the individual actuators is rectified, that is, directed in the desired direction of flow, solely by the phasing of multiple actuators. Other types of displacement pumps rectify flow differently. A passive check-valve pump uses two passive, one-way check valves incorporating moving flaps or other components. One such valve at the pump inlet permits fluid to enter the chamber as the pump chamber expands, but prevents it from leaving as the chamber contracts. Likewise, a passive check valve at the outlet prevents backflow on the expansion stroke, but permits fluid to exit the chamber on the contraction stroke. Valveless rectification pumps are similar, but use flow diodes instead of mechanical check valves. Flow diodes are diffuser/nozzle structures or so-called Tesla valves that have no moving parts, but exhibit a preferential flow direction due to their geometry. More detail on passive check-valve or valveless rectifier pumps may be found in [1], [3] or [12]. Since these require only a single actuator, versus two or more for peristaltic pumps, they are natural design alternatives. Reasons to prefer a peristaltic design include ease of integration onto the microchip, with no special fabrication steps or external connections. For example, [13] presents an electrostatically-actuated peristaltic micropump suitable for incorporation into a micro-total analytical system (μTAS) with no additional special considerations. Peristaltic pumps avoid the more complex microfabrication typically required for passive check valves, and the susceptibility of such valves to fouling by particles or bubbles. Valveless rectifiers are simple to fabricate, and not prone to fouling, but may have a larger footprint than peristaltic designs. Finally, peristaltic pumps may be used to generate forward or reverse flow by modifying the actuator phasing, while bidirectional versions of the other two options are difficult to realize. Some guides to peristaltic pump design advise adding series passive check valves to aid in rectification if the application allows [1], though this reduces to some extent the operational and fabrication benefits that peristaltic designs offer over check-valve designs.

In many peristaltic micropump implementations identical actuators provide both stroke displacement and flow valving. However, these functions may also be divided between actuators of different design. One analysis reported in the literature treats a large stroke displacement actuator with a low flow resistance, flanked by active valves with small stroke displacement [5]. While similar in concept to a passive check-valve diaphragm pump, the valving actuators in this case are actively opened and closed by external commands, and flow direction is determined by the phasing of these commands with regard to actuation of the central diaphragm. Hence, this design may properly be classified as a peristaltic pump.

Due to a combination of surface tension and viscosity effects, the pressure drop per unit length along a channel with characteristic length l (radius or hydraulic diameter) scales unfavorably (as $1/l^3$ or $1/l^2$, depending on the analysis). Thus mechanical pumps must generate extremely high pressures to maintain flow rates as channel diameters shrink. For this reason, it is widely accepted that mechanical pumping mechanisms, including peristaltic pumps, are not suitable for very small channels. Nguyen and Wereley survey the literature, and, using water as a working fluid, give 10 μl/min as the flow rate below which nonmechanical pumping principles are preferred [1]. However, that boundary is somewhat arbitrary, as demonstrated by flow rate of 0.14 μl/min reported in [4] for pneumatically-actuated peristaltic pumping of water in PDMS channels, the flow rate of 1.7 nl/min for electrostatically-actuated peristaltic pumping of ethanol in parylene channels [13], and the flow rate of 1 nl/h reported in [15] for optically-actuated peristaltic pumping by colloidal particles suspended in an aqueous solution.

Basic Methodology

A linear peristaltic micropump consists of two or more actuators arranged along a channel, and driven in a particular sequence. Important parameters that quantify pump performance are the maximum flow rate, denoted here by Q^*, the maximum pressure that can be generated between the pump inlet and outlet (called the ►pump head), denoted here by p^*, and the efficiency with which the pump converts external power into flow power, denoted here by η. Given a particular actuator, or set of available actuators, pump design consists of selecting the number of actuators, the actuation sequence, and the frequency of actuation. Important information about the individual actuators includes the stroke volume, V, the dead volume, V_0, the flow resistance in open and closed configurations, R_o and R_c, respectively, the maximum pressure the actuator can generate, p^*_act, called the ►closing pressure, the minimum time required for the actuator to either open or close completely, T_min (the minimum time to open and the minimum time to close are typically different; here T_min would be the larger of the two) and the energy or power required to operate an actuator. Almost any mechanical transducer can be used as an actuator in a peristaltic micropump, making generalizations about pump performance difficult. For example, the response time of a thermopneumatic actuator may be dominated by heat transfer out of the actuator, while that of a piezoelectric actuator is primarily determined by material stiffness and membrane geometry. As another example, a thermal actuator may require continual power to remain in the closed position, while – once closed – an electrostatic or pneumatic actuator may be held closed with little or no additional power consumption.



Peristaltic Pumps, Figure 3 A typical pump chamber in a multilayer PDMS implementation (similar to those of [4]). The chamber is open by default, as shown in (**a**). Inflating the actuation channel with compressed air closes the chamber, as shown in (**b**). PDMS layer 1 defines the fluid channels (sometimes called the working channel), while PDMS layer 2 defines the actuation channels. In both cases casting or spinning PDMS on a negative mold creates the channel structures. The molds are defined photolithographically, with standard positive resists used for thin channels (on the order of a micrometer) and negative resists such as SU8 used for thicker channels (up to one millimeter). The patterned side of the fluid layer is bonded to a glass, silicon, or PDMS substrate, and the patterned side of the actuation layer is bonded in turn to the planar side of the fluid layer. For convenience, we refer to the area of the fluid channel under the actuation channel as the pump chamber, even though it is otherwise indistinguishable from the rest of the channel. Baking the fluid layer mold at high temperature after the pattern is developed causes the photoresist to *reflow*, yielding rounded corners in the fluid channels. These rounded corners reduce leakage when the chamber is closed

In this article we focus on those considerations that are common to all peristaltic pump designs. This rules out detailed physical analysis. However, some broad assumptions about actuator and system characteristics allow rough comparisons for pump design purposes. We begin by assuming ideal actuators, with infinite flow resistance in the closed position and zero dead volume. The first property allows easier accounting of the movement of fluid, the second allows issues related to fluid compressibility to be ignored.

The first step in this simplified analysis is estimating the volume of fluid transported in a complete pumping cycle. To do this, we apply the following rules:

1. When an actuator closes, the fluid within is completely expelled.
2. When an actuator opens, it completely fills with fluid.
3. If an actuator remains closed during a step in the sequence, no fluid may pass across it.
4. If, in a single step, some actuators open while others close, and there is a path for fluid to flow between them, then fluid is transferred from the latter to the former.



Peristaltic Pumps, Figure 4 A three-step, three-actuator pumping sequences, used in numerous pumps, including thermopneumatic pumps by Grosjean and Tai (see the reference in [1]) and Jeong, et al. [9]. The stroke volume is designated V. Chambers 1, 2, and 3 are abbreviated $C1$, $C2$, and $C3$. At every step two chambers are closed, reducing leakage. Note that Grosjean and Tai use a similar looking figure to define the pump sequence, but in their paper the raised level indicates actuation, which corresponds to *closing* the chamber

5. If an actuator opens or closes with no closed actuators between it and either the inlet or the outlet, the transfer of fluid is made equally from or to both sides. Once the fluid volume is computed, the flow rate flows from the actuation frequency. Maximum head is taken to be the maximum pressure exerted by an actuator (though this is not often known), and efficiency is estimated from the actuation sequence. Often, an estimate of flow rate is all that is desired. It must be noted that these estimates are very coarse, with for examples, errors of a factor of two reported, and attributed to unmodeled valve leakage [6].

Simplified Sequence Analysis

As an illustration of the simplified analysis, consider the three-step cycle shown in Fig. 4 for a pump consisting of three identical ideal actuators with stroke volume V. At the start of the cycle, no fluid has yet been transferred. In step 2, chamber $C1$ opens while chamber $C3$ closes. By rules 1 and 2, $C1$ must fill with volume V while $C2$ expels volume V. Since the intervening chamber $C2$ is closed, by rule 3 $C1$ must take volume V from the inlet, while $C3$ must expel volume V to the outlet. In step 3 $C1$ closes while $C2$ opens. By rule 4, since there is an open path between them, this transfers volume V from $C1$ to $C2$. Likewise the return to step 1, which completes the cycle, transfers volume V from $C2$ to $C3$. We conclude that, ideally, volume V is pumped per complete three-step cycle. At the final step the net fluid volume increase at the outlet must equal the net decrease at the input. This is a useful check that the analysis was done correctly.



Peristaltic Pumps, Figure 5 A six-step, three-actuator pumping sequences proposed in the literature [6]. At step 1 all chambers are open, allowing backflow which will reduce the net flow rate

Maximum Flow Rate

If each step requires time T, the pumping rate is $V/3T$. The maximum flow rate Q^* then corresponds to the minimum cycle time, $T_{\min}$: $Q^* = V/3T_{\min}$.

Maximum Head

In step 2, $C3$ is emptied to the outlet. If the outlet pressure is greater than p^*_{act}, the maximum pressure the actuator can provide, the chamber will be unable to close. Thus, the maximum head can be approximated as the closing pressure, $p^* = p^*_{\mathrm{act}}$.

Efficiency

Fluid power is the product of flow rate by head. In an ideal ►positive displacement pump, flow rate is independent of head. Therefore, the maximum fluid power is approximately $P^* = p^*Q = p^*_{\mathrm{act}}V/3T$. One actuator closes at each step, and two actuators must be held closed at each step. If energy E_{act} is required to close an actuator, and power P_{act} is required to hold it closed, we see that each cycle requires total energy $3E_{\mathrm{act}} + 6P_{\mathrm{act}}T$ (we assume no energy is required to open an actuator). The total power consumed per cycle is $(E_{\mathrm{act}}/T) + 2P_{\mathrm{act}}$, and the maximum efficiency is $\eta = p^*_{\mathrm{act}}V/(3E_{\mathrm{act}} + 6P_{\mathrm{act}}T)$.

Experiments suggest that a linear relation between flow rate and pump head may be a more appropriate model [5]. In that case, the maximum fluid power is given by $P^* = p^*Q^*/4$.

Design Comparison

To illustrate the use of the simplified analysis in design, we compare the actuation sequence analyzed above to a six-step three-chamber sequence also reported in the literature [6], and shown in Fig. 5. The analysis is similar to the three-step sequence, except for steps 1 and 6, where an actuator closes with no closed actuators between it and either the inlet or the outlet. By rule 5, the expelled fluid is divided evenly between the inlet and the outlet. Two considerations make application of the simplified model more problematic in this case. The first is the all-actuators-open configuration in step 1. If there is significant head across the pump, this may produce an unmodeled backflow. The second is the assumption mentioned above, that the flow splits evenly in step 1 and 6. If the external system flow resistances as seen from the input and output are different, or if there is significant head, the split will *not* be even. These issues aside, we find that a volume $2V$ is pumped in each six-step cycle.

If each step requires time T, the pumping rate is $2V/6T$, or $V/3T$. The maximum flow rate is $Q^* = V/3T_{\mathrm{min}}$. This is the same as for the three-step sequence.

In steps 2, 3, and 4 chambers are emptied to the outlet. The maximum head can again be approximated as the closing pressure.

The maximum fluid power is approximately $P^* = p^*Q = p^*_{\mathrm{act}}V/3T$. In each cycle, energy $3E_{\mathrm{act}}$ is required for actuator closings, and energy $9P_{\mathrm{act}}T$ is needed to hold actuators closed, for a total cycle power requirement $(E_{\mathrm{act}}/2T) + (2P_{\mathrm{act}}/3)$. The maximum efficiency is $\eta = 2p^*_{\mathrm{act}}V/(3E_{\mathrm{act}} + 9P_{\mathrm{act}}T)$.

To the level of modeling accuracy applied, the two designs have the same maximum flow rate and maximum head. The six-step sequence is more power efficient, but there are unanswered questions about how well this design will perform, particularly if there is significant backpressure. If power usage is more important than maximum head, the six-step design may be preferable, but further investigation will be required. If efficiency is not important, the three-step sequence should be chosen for its higher resistance to backflow. An advantage of the six-step sequence is that only one chamber is actuated per step. This makes the sequence insensitive to asymmetries in opening versus closing actuators. For example, if the actuators close ten times faster than they open, fluid may not transfer smoothly between chambers in the sequence of Fig. 4, but instead may leak out of the chamber. Avoiding this risk by adding intermediate steps, as for example, in the five-step sequence used by Smits [2] will reduce the maximum flow rate, and make the sequence of Fig. 5 more attractive.



Peristaltic Pumps, Figure 6 Pumping sequences for two-actuator peristaltic pumps [7]. Sequence A has at least one actuator closed at all times. Sequence B has a higher maximum flow rate, but may have problems with backflow under high head conditions

Most reported peristaltic micropump designs use three actuators. A few use more, but typically not more than five. Since the actuators take up potentially valuable space, and require connections for power and switching, it is desirable in many applications to use the minimal possible number. Some authors have stated that three chambers are the fewest possible for peristaltic pumping. However, the sequences shown in Fig. 6 have been shown to provide peristaltic pumping using only two chambers [7].

Diagrams like Figs. 4–6 are easy to grasp visually, but a more compact description of pumping sequences is also useful. One method used in the literature (for example, in [8]) is to indicate an actuated (closed) chamber by a 1 and an un-actuated (open) chamber by a 0. Thus the sequence in Fig. 4 is written {110, 011, 101}, that of Fig. 5 becomes {000, 100, 110, 111, 011, 001}, and those of Fig. 6 A and B are {01, 10, 00} and {00, 10, 11, 01}, respectively. The five-step sequence used by Smits [2] is, following the convention of 1 for closed, 0 for open, {011, 001, 101, 100, 110}. (This sequence does involve an actuator closing simultaneously with another opening, but they are separated by a closed chamber.) Some care is required in using this notation, since some mechanisms close when actuated (e. g. thermopneumatic), while others open (e. g. piezoelectric).

Dynamic Modeling

Leaks, backpressure, and actuator dynamics all influence the performance of peristaltic pumps. Leaks and backpressure effects will alter the distribution of fluid as actuators open and close. The dynamics of the actuators determines the maximum actuation rate, which in turn limits the maximum flow rate. These effects can be incorporated into lumped-parameter models for analysis and simulation. We do not pursue this further in this article, but refer the reader to the literature. One general approach is presented in [5]. Also relevant for further study are [6], [13] and [14], which present dynamic models for pneumatic and electrostatic pumps, respectively. All of these works are applied to liquid pumps. For gas pumps, or robustness to bubbles, compressibility becomes a factor. Some considerations of micropumps for compressible fluids may be found in [1]. Finite-element analysis of individual chambers can also be used to obtain detailed predictions of pump dynamic performance.

Key Research Findings

Fabrication Materials and Actuator Types

Peristaltic pumps have been demonstrated in all materials common for microfluidic applications, using a variety of physical principles. Space constraints prevent a comprehensive listing, but [1], [3], and [12] provide good overviews. Summarizing here just the main fabrication materials, the operating principle, and the working fluid, these include for silicon and/or glass devices, piezoelectric, thermopneumatic, and electrostatic actuators pumping water. For PDMS devices only pneumatic pumping of water is reported. For plastic or mixed-type devices, electrostatic, thermopneumatic, and pneumatic actuators are reported, pumping water and air. A novel traveling wave pump implemented using optically-actuated colloidal silica spheres is reported in [15]. Recently, Husband et al. (Microelectronic Engineering 73–74:858–863, 2004) report a piezoelectric silicon-glass device pumping water and air, Pan et al. (Proceedings of the 26th Annual International IEEE EMBS Conference, 2004) report a magnetically driven PDMS pump for water, and Jeong et al. report a thermopneumatic PDMS pump for water [9]. Electrostatic pumps implemented in parylene for integration with μTAS devices are reported in [13].

Reducing Device Complexity

Peristaltic pumps already offer simpler fabrication than passive check-valve pumps. Even the simplest actuators, however, require at least two patterned layers, as, for example, in the PDMS device of Fig. 3. However peristaltic pumping was recently demonstrated in a device with a single patterned layer of PDMS on an un-patterned glass or PDMS substrate [10]. The single patterned layer incorporates both pneumatic actuation lines and the water-filled working channels. Rather than press on the fluid channel from above, the actuation lines in this device squeeze the working channel from the sides. While these actuators provide enough stroke and increased resistance for pumping, cell sorting, and mixing, in their closed configuration they are still quite leaky, and do not completely seal the channel. However, the elimination of the second layer, along with the associated alignment and bonding tasks, should yield a significant reduction in device cost.

Reducing Number of Off-Chip Connections

Each actuator in a peristaltic pump is an active element, requiring switching and power. In applications such as Lab-on-a-Chip, the number of required off-chip connections can become very large. As mentioned above, one means for doing this is by using two actuators instead of three [7]. The proliferation of pumps and valves is a particular problem in pneumatically actuated pumps that require external valving. An innovative approach to ameliorating this problem is described in [11] for pneumatically actuated pumps fabricated in PDMS. Here, a single pneumatic actuation channel has a serpentine shape, crossing over the straight channel containing the working fluid at multiple intersections. The phasing of the actuation is provided by the natural delay associated with the propagating inflation zone in the serpentine channel. In this way the equivalent of a three-, five-, or seven-actuator peristaltic pump is realized using a single actuator line.

Multifunction Components

The individual actuators in a peristaltic pump can also serve as individual valves. Additional flexibility in integrating peristaltic pumps into large microfluidic systems can be gained from providing components with multiple functions. An example of this is the rotary mixer described in [8], which can serve as an effective dynamic micromixer, or as a peristaltic pump, depending on the actuation pattern of the individual valves.

Future Directions for Research

Progress in peristaltic pump design has paralleled the advancement of microfluidics as a field. As new materials and applications have been developed, peristaltic pump designs have soon followed. This trend seems likely to continue.

Peristaltic pumps are commonly used in PDMS-based systems. As those systems have attracted increasing amounts of research effort, due to their biocompatibility and demonstrated success in manipulation of cells, genetic material, and proteins, new innovations in PDMS-based pumps have followed. Progress has been made in reducing the need for external connections, but improvement would be welcome in the area of fully integrated pumps of reasonable cost and low complexity.

Cross References

- ► Electromagnetic Valves
- ► Electrostatic Valves
- ► Magnetic Pumps
- ► Membrane Actuation for Micropumps
- ► Microactuators
- ► Microfluidic Mixing
- ► Piezoelectric Valves
- ► Piezo/PZT in Microfluidics
- ► Pneumatic Valves
- ► Soft Photolithography
- ► Thermomechanical Valves
- ► Thermopneumatic Valves
- ► Water Management in Micro DMFCs

References

1. Nguyen NT, Wereley ST (2002) Fundamentals and Applications of Microfluidics. Artech House, Boston
2. Smits JG (1990) Piezoelectric Micropump with 3 Valves Working Peristaltically. Sens Actuators A Phys 21(1–3):203–206
3. Laser DJ, Santiago JG (2004) A review of micropumps. J Micromech Microeng 14:R35–R64
4. Unger MA, Chou HP, Thorsen T, Scherer A, Quake SR (2000) Monolithic Microfabricated Valves and Pumps by Multilayer Soft Lithography. Sci 288:113–116
5. Goldschmidtböing F, Doll A, Heinrichs M, Woias P, Schrag HJ, Hopt UT (2005) A generic analytical model for micro-diaphragm pumps with active valves. J Micromech Microeng 15:673–683
6. Goulpeau J, Trouchet D, Ajdari A, Tabeling P (2005) Experimental study and modeling of polydimethylsiloxane peristaltic micropumps. J Appl Phys 98(044914):1–9
7. Berg J, Anderson RC, Anaya M, Lahlouh B, Dallas T, Holtz M (2003) A Two-Stage Discrete Peristaltic Micropump. Sens Actuators A 104:6–10
8. Chou HP, Unger MA, Quake SR (2001) A Microfabricated Rotary Pump. Bioméd Microdevices 3:323–330
9. Jeong OC, Park SW, Yang SS, Pak JJ (2005) Fabrication of a Peristaltic PDMS Micropump. Sens Actuators A 123–124:453–458
10. Sundararajan N, Kim D, Berlin AA (2005) Microfluidic operations using deformable polymer membranes fabricated by single layer soft lithography. Lab Chip 5:350–354
11. Wang CH, Lee GB (2006) Pneumatically driven peristaltic micropumps utilizing serpentine-shape channels. J Micromech Microeng 16:341–348
12. Nguyen NT, Huang X, Chuan TK (2002) MEMS-Micropumps: A Review. J Fluids Eng 124:384–392
13. Xie J, Shih J, Lin Q, Yang B, Tai YC (2004) Surface Micromachined Electrostatically Actuated Micro Peristaltic Pump. Lab Chip 4:495–500
14. Lin Q, Yang B, Xie J, Tai YC (2007) Dynamic Simulation of a Peristaltic Micropump Considering Coupled Fluid Flow and Structural Motion. J Micromech Microeng 17:220–228
15. Terray A, Oakey J, Marr DWM (2002) Microfluidic Control Using Colloidal Devices. Sci 296:1841–1844

Permeabilization of Cells

► On-Chip Cell Lysis

Perovskite

Synonyms

Calcium titanium oxide; Orthorhombic crystal

Definition

Defines calcium titanium oxide in particular and generally all crystalline materials that exhibit a crystal structure similar to it, as with the crystalline structure of PZT.

Phase-Change Heat Transfer in Microchannels

► Condensation in Microchannels

Phase Field Method

► Interface Capturing Schemes for Free-Surface Flows

Phase Separation Kinetics

► Demixing

Phase Shift

► Frequency Response

pH Control Device

► pH-Sensitive Hydrogel

Phenol Extraction

► Lab-on-a-Chip Devices for Sample Extractions

Phenotypic Assay

► Cell Assays

Phenotypic Screening in Microfluidic Devices/on-Chip

► Cell Assays in Microfluidics

Phosphorescence

Definition

Phosphorescence is the emission of light from triplet-excited states, whereby one set of electron spins is unpaired. This means that electrons in the excited orbital have the same spin as the ground state electrons. Therefore, transition to ground state is not possible and emission rates are slow (in the region of $10^3 - 10^1\ s^{-1}$. Phosphorescent life-times have durations in the millisecond range. Following exposure to light, phosphorescent substances glow for several minutes as the excited phosphors return to the ground state very slowly.

Cross References

► Fluorescent Labeling

Photo-Activated Nonintrusive Tracking of Molecular Motion

► Visualization Based on Molecular Tagging Methods

Photobleached Fluorescence

► Visualization Based on Molecular Tagging Methods

Photobleaching

Synonyms

Photochemical decomposition; Photochemical degradation

Definition

Photobleaching is the decrease of the emitted fluorescence intensity by the excited fluorophores as a result of the decay of dye molecules due to their prolonged exposure to high-intensity incident light.

Cross References

► Fluorescent Thermometry
► Fluorescence Labeling

Photochemical Decomposition

► Photobleaching

Photochemical Degradation

► Photobleaching

Photofluidic Devices

► Optofluidics – Techniques for Fabrication and Integration

Photofluidics

► Optofluidics – Applications
► Optofluidics – Fluidics Enabling Optics
► Optofluidics: Optics Enabling Fluidics

Photolithography

Mauris De Silva
Bascom Palmer Eye Institute, University of Miami,
Miami, FL, USA
mdesilva@med.miami.edu

Synonyms

Optical lithography; Microlithography; Nanolithography

Definition

Photolithography is a process mainly used but not limited to manufacturing integrated circuits, and involves the photographic transfer of a desired pattern to a surface for further processing (e. g. etching).

Overview

Photolithography is the most popular method among various forms of lithography when transferring patterns from a mask (reticle) onto a surface of a substrate. Photolithography is widely used in the integrated circuit (IC) industry. However, it has other potential important applications such as developing methods for controlling the position of cells on a substrate or micropatterning of cells that has many bioengineering applications including the design of biosensors that can be used for drug and toxicity sensing devices and environmental monitoring devices, tissue engineering applications, and basic biology studies.
Photolithography is widely used in the semiconductor industry to perform a series of successive patterning on a given substrate to achieve an electronically functioning product. Although, this pattering method is limited to planar surfaces, it can provide accurate patterning feature sizes at the submicrometer level.

Basic Methodology

Photolithography is comprised of sequential process steps that are schematically summarized in Fig. 1. The process begins by choosing or preparing a substrate for the photolithography process. The ideal substrate should be dehydrated before any application of photoresist. This dehydration is usually done by a baking step called *dehydration bake* to remove adsorbed water from the substrate, usually a silicon wafer. Thereafter, the dehydrated substrate is spin coated with a photoresist adhesion promoter using a spinner. Usually, hexamethyldisilazane (HMDS) is used for this step, which is called priming. Then, the primed substrate is spin coated placing excess amount of a photoresist, a photosensitive material. The photoresist will be spread uniformly on the surface of the substrate by centrifugal force. This process is one of the most important parts of the process, as the quality of the pattern transfer depends on effective spin coating of photoresist material. The most important requirements of spin coating are having a known uniform thickness of the photoresist material throughout the substrate, and this should be optimized for different substrate–photoresist combinations to determine the appropriate amount of photoresist and spinning velocity to use during the spin coating step. The thickness of photoresist may be varied according to the spinning speed and the viscosity of the photoresist-containing fluid. Usually, photoresist vendors provide information on how thickness may vary according to the spinning velocity of a given photoresist. The photoresist-coated substrates are subjected to a prebaking



Photolithography, Figure 1 (**a**) The top image shows the deposition of photoresist on a dehydrated and then primed wafer. The image below shows the coated wafer with uniform layer of photoresist. (**b**) The photoresist-coated wafer is exposed to UV light with an intact mask. (**c**) The pattern is developed by rinsing the substrate in a developing solution or using a spray developer. This process will remove the unwanted photoresist and leaves the pattern on the surface of the substrate.

step or soft baking step before being exposed to UV light with an intact stencil called a *photomask*. This prebaking step is usually done at 80 − 110 °C for 5 to 10 min depending on the thickness of the photoresist layer. This step will enhance the adhesion of the photoresist to the substrate by removal of the solvent in the photoresist and any built in stresses.

The exposure can then be conducted using an aligner. An aligner is comprised of a light source including any reflecting and/or refracting optics needed for collecting, collimating, filtering, and focusing the light onto the mask with the desired image. The most common aligners are contact printers and projection printers. In the contact printer approach the mask is held against the photoresist; in the projection printing method a set of lenses (projector/objective) is placed between the mask and the wafer to refocus light onto the photoresist. After exposure, the pattern is developed by rinsing the substrate in a developing solution or using a spray developer. This process will remove the unwanted photoresist and leaves the pattern on the surface of the substrate. This is also a very important step as it is very temperature sensitive, and will affect control and maintenance of line widths of the pattern, resist contrast, and resist profiles. There are two types of pattern transfer: positive and negative. In the positive form, the photoresist pattern on the substrate is the positive image of the mask pattern; in the negative form, the image of the photoresist pattern is the inverse image of the photomask pattern.

After developing, the substrate is subjected to a hard baking process to harden the photoresist. The hardening of the photoresist is done as the patterned substrates may be used for further processing such as plasma etching or ion implantation. Once all the processing is complete, any remaining/developed photoresist can be removed using a commercially available organic photoresist stripping solvent. This substrate can be used for further patterning by starting another photolithography step.

Future Directions for Research

The future directions for research in photolithography will be in improving minimum feature size. The variables that involve improving minimum feature size include photoresist, mask, and exposing wavelength. Thus, one can think that the future improvement in photolithography will depend on improving resist types, and designing better mask-refining technology and better laser technology.

Cross References

- ► Cell Patterning on Chip
- ► Photo Patterned
- ► Photoresist SU-8
- ► Photoresist Reflow

References

1. Campbell SA (2001) The Science and Engineering of Microelectronic Fabrication. Oxford Univ Press, New York
2. Madou MJ (2002) Fundamentals of Microfabrication: The Science of miniaturization. CRC, Boca Raton

Photoluminescence

- ► Fluorescent Thermometry

Photomask

Definition

A plate of opaque material that has been patterned with transparent regions.

Cross References

- ► Sputtering for Film Deposition

Photometer

KENJI YASUDA
Department of Biomedical Information,
Division of Biosystems Institute of Biomaterials and
Bioengineering, Tokyo Medical and Dental University,
Tokyo, Japan
yasuda.bmi@tmd.ac.jp

Synonyms

Photometry; Illuminance; Irradiance; Scattered light intensity; Absorption; Spectroscopy; Spectrophotometer

Definition

The instrument used to measure illuminance or irradiance of light. It is the general term covering instruments for detecting scattered light intensity, absorption, fluorescence applied in the field of photometry. Spectroscopic techniques using photometer can probe the change of energy, frequency, wavelength and intensity of light caused by the interaction with matter. Most photometers are based on a photoresistor, photodiode, or photomultiplier tubes for photon observation. Either exhibits a change in electrical properties when exposed to light, which can be detected with a suitable electronic circuit.

Photometer, Table 1 Symbols, SI units and abbreviations used in photometer

Quantity	Symbol	SI unit	Abbreviation
Luminous energy	Q_v	lumen second	lms
Luminous flux	F	lumen (= cdsr)	lm
Luminous intensity	I_v	candela (= lm/sr)	cd
Luminance	L_v	candela per square metre	cd/m^2
Illuminance	E_v	lux (= lm/m^2)	lx
Luminous emittance	M_v	lux (= lm/m^2)	lx
Luminous efficacy		lumen per watt	lm/W
Radiant energy	Q	joule	J
Radiant flux	Φ	watt	W
Radiant intensity	I	watt per steradian	Wsr^{-1}
Radiance	L	watt per steradian per square metre	$Wsr^{-1}m^{-2}$
Irradiance	E	watt per square metre	Wm^{-2}
Radiant exitance / Radiant emittance	M	watt per square metre	Wm^{-2}
Spectral radiance	L_λ or L_ν	watt per steradian per metre^3 or watt per steradian per square metre per hertz	$Wsr^{-1}m^{-3}$ or $Wsr^{-1}m^{-2}Hz^{-1}$
Spectral irradiance	E_λ or E_ν	watt per metre^3 or watt per square metre per hertz	Wm^{-3} or $Wm^{-2}Hz^{-1}$
Radiant energy	Q	joule	J

Photometer, Table 2 Comparison of two photodetectors: photodiodes and photomultipliers

Advantages of photodiodes	Advantages of photomultipliers
• Excellent linearity of output current as a function of incident light • Spectral response from 190 nm to 1100 nm (silicon), longer wavelengths with other semiconductor materials • Low noise • Ruggedized to mechanical stress • Low cost • Compact and light weight • Long lifetime • High quantum efficiency • No high voltage required	• Large area • Flexible internal gain • Higher overall sensitivity • Photon counting is possible

Overview

The interaction of electromagnetic radiation with matter is essentially a quantum phenomenon and is dependent on the properties of the radiation and on the appropriate structural parts of the material involved. As the origin of the radiation is due to energy changes within the matter itself, an understanding of the properties of electromagnetic radiation and its interaction with matter leads to a recognition of the variety of types of spectrum, and consequently spectroscopic techniques, and their application to the solution of biological problems. Photometry is the science of measurement of light, historically, in terms of its perceived brightness to the human eye. It is distinct from radiometry, which is the science of measurement of light in terms of absolute power; rather, in photometry, the radiant power at each wavelength is weighted by the luminosity function that models human brightness sensitivity. Thus many different units of measure are used for photometric measurements and sometimes that can't be converted from radiometry. For example, in photometric quantities, every wavelength is weighted according to how visible it is, while radiometric quantities use unweighted absolute power. Because the eye responds much more strongly to green light than to red, a green source will have higher luminous flux than a red source with the same radiant flux would. Light outside the visible spectrum does not contribute to photometric quantities at all, so for example a 1000 W space heater may put out a great deal of radiant flux (1000 W, in fact), but as a light source it puts out very few lumens (because most of the energy is in the infrared, leaving only a dim red glow in the visible). Watts (radiant flux) and lumens (luminous flux) illustrates the distinction between radiometric and photometric units. The watt is a unit of power. As power is not a measure of the amount of light output, power is only a rough guide to light output. In contrast, the lumen is the photometric unit of light output. The lumen is defined as amount of light given into one steradian by a point source of one candela strength; while the candela, a base SI unit, is defined as the luminous intensity of a source of monochromatic radiation, of frequency 540 THz, and a radiant intensity of $1/683\,\mathrm{Wsr}^{-1}$. (540 THz corresponds to about 555 nm, the wavelength, in the green, to which the human eye is most sensitive. The number 1/683 was chosen to make the candela about equal to the standard candle, the unit which it superseded). Combining these definitions, we see that 1/683 W of 555 nm green light provides one lumen. The definition tells us that 1 W of pure green 555 nm light is equal to 683 lm. It should be noted that it does not say anything about other wavelengths. Because lumens are photometric units, their relationship to watts depends on the wavelength according to how visible the wavelength is. Infrared and ultraviolet radiation, for example, are invisible and do not count. That means one watt of infrared radiation is worth zero lumens.

In photometry, illuminance is the total luminous flux incident on a surface, per unit area. It is a measure of the intensity of the incident light, wavelength-weighted by the luminosity function to correlate with human brightness perception. Similarly, luminous emittance is the luminous flux per unit area emitted from a surface. Luminous emittance is also known as luminous exitance. In SI derived units, these are both measured in lux (lx) or lumens per square metre (cdsrm^{-2}). In the CGS system, the unit of illuminance is the phot. One phot is equal to 10,000 lx. Illuminance was formerly often called brightness, but this leads to confusion with other uses of the word.

Irradiance is a radiometry term for the power of electromagnetic radiation at a surface, per unit area, which is used when the electromagnetic radiation is incident on the surface. The SI unit for this quantity is watts per square meter ($\mathrm{W/m}^2$), which is sometimes called intensity. This quantity characterizes the total amount of radiation present, at all frequencies. It is also common to consider each frequency in the spectrum separately. When this is done for radiation incident on a surface, it is called spectral irradiance, and has SI units $\mathrm{W/m}^3$, or commonly $\mathrm{Wm}^{-2}\mathrm{nm}^{-1}$.

Basic Methodology

Photometric Measurements

Photometric measurement is based on photodetectors, devices that produce an electric signal when exposed to light. Simple applications of this technology include switching luminaries on and off based on ambient light conditions, and light meters, used to measure the total amount of light incident on a point. More complex forms of photometric measurement are used for detecting scattered light intensity, absorption, fluorescence.

Light Scattering

Light scattering is one of the two major physical processes that contribute to the visible appearance of most objects, the other being absorption. Major forms of elastic light scattering (involving negligible energy transfer) are Rayleigh scattering and Mie scattering. Inelastic light scattering effects include Brillouin scattering, Raman scattering. Light scattering can also give color to some objects, usually shades of blue, but resonant light scattering in nanoparticles can produce different highly saturated and vibrant hues, especially when surface plasmon resonance is involved. At values of the ratio of particle diameter to wavelength more than about 10, the laws of geometric optics are mostly sufficient to describe the interaction of light with the particle, and at this point the interaction is not usually described as scattering. For modeling of scattering in cases where the Rayleigh and Mie models do not apply such as irregularly shaped particles, there are many numerical methods that can be used. The most common are finite-element methods which solve Maxwell's equations to find the distribution of the scattered electromagnetic field.

Rayleigh Scattering

Rayleigh scattering is a process in which light is scattered by a small spherical volume of variant refractive index, such as a particle, bubble, droplet, or even a density fluctuation. This effect was first modeled successfully by Lord Rayleigh, from whom it gets its name. In order for Rayleigh's model to apply, the sphere must be much smaller in diameter than the wavelength (λ) of the scattered wave; typically the upper limit is taken to be about 1/10 the wavelength. In this size regime, the exact shape of the scattering center is usually not very significant and can often be treated as a sphere of equivalent volume. The inherent scattering that radiation undergoes passing through matter is due to microscopic density fluctuations as the molecules in matter move around, which are normally small enough in scale for Rayleigh's model to apply. This scattering mechanism is the primary cause of the blue color of the Earth's sky on a clear day, as the shorter blue wavelengths of sunlight passing overhead are more strongly scattered than the longer red wavelengths according to Rayleigh's famous $1/\lambda^4$ relation. Along with absorption, such scattering is a major cause of the attenuation of radiation by the atmosphere. The degree of scattering varies as a function of the ratio of the particle diameter to the wavelength of the radiation, along with many other factors including polarization, angle, and coherence.

Mie Scattering

For larger diameters, the problem of electromagnetic scattering by spheres was first solved by Gustav Mie, and scattering by spheres larger than the Rayleigh range is therefore usually known as Mie scattering. In the Mie regime, the shape of the scattering center becomes much more significant and the theory only applies well to spheres and, with some modification, spheroids and ellipsoids. Closed-form solutions for scattering by certain other simple shapes exist, but no general closed-form solution is known for arbitrary shapes.

Raman Scattering

Raman scattering is the inelastic scattering of a photon. When light is scattered from an atom or molecule, most photons are elastically scattered (Rayleigh scattering). The scattered photons have the same energy (frequency) and, therefore, wavelength, as the incident photons. However, a small fraction of scattered light (approximately 1 in 1000 photons) is scattered from excitations with optical frequencies different from, and usually lower than, the frequency of the incident photons. Raman scattering can occur with a change in vibrational, rotational or electronic energy of a molecule. Raman spectroscopy employs the Raman effect for material analysis. The frequency of light scattered from a molecule is changed based on the structural characteristics of the molecular bonds. A monochromatic light source (laser) is required for sufficient illumination, and a spectrogram of the scattered light then shows the deviations caused by state changes in the molecule.

Doppler Shift

Electromagnetic radiation scattered by moving scattering centers does undergo a Doppler shift, which can be detected and used to measure the velocity of the scattering center/s in forms of techniques such as radar. Both Mie and Rayleigh scattering are considered elastic scattering processes, in which the energy (and thus wavelength and frequency) of the light is not substantially changed. However, this shift involves a slight change in energy.



Photometer, Figure 1 Photomultipliers are constructed from a glass vacuum tube which houses a photocathode, several dynodes, and an anode. Incident photons strike the photocathode material which is present as a thin deposit on the entry window of the device, with electrons being produced as a consequence of the photoelectric effect. These electrons are directed by the focusing electrode towards the electron multiplier, where electrons are multiplied by the process of secondary emission

Absorption (Electromagnetic Radiation)

Absorption is the process by which the energy of a photon is taken up by another entity, for example, by an atom whose valence electrons make transition between two electronic energy levels. The photon is destroyed in the process. The absorbed energy may be re-emitted as radiant energy or transformed into heat energy. The absorption of light during wave propagation is often called attenuation. The absorbance of an object quantifies how much light is absorbed by it. This may be related to other properties of the object through the Beer-Lambert law. For most substances, the amount of absorption varies with the wavelength of the light, leading to the appearance of color in pigments that absorb some wavelengths but not others. For example, an object that absorbs blue, green and yellow light will appear red when viewed under white light. More precise measurements at many wavelengths allow the identification of a substance via absorption spectroscopy.

Fluorescent Measurement

Fluorescent measurement uses the luminescence of fluorescence that is mostly found as an optical phenomenon in cold bodies, in which the molecular absorption of a photon triggers the emission of another photon with a longer wavelength. The energy difference between the absorbed and emitted photons ends up as molecular vibrations or heat. Usually the absorbed photon is in the ultraviolet range, and the emitted light is in the visible range, but this depends on the absorbance curve and Stokes shift of the particular fluorophore. The fluorescence quantum yield gives the efficiency of the fluorescence process. It is defined as the ratio of the number of photons emitted to the number of photons absorbed. The maximum fluorescence quantum yield is 1.0 (100%); every photon absorbed results in a photon emitted. Compounds with quantum yields of 0.10 are still considered quite fluorescent. The fluorescence lifetime is an instance of exponential decay. Thus, it is similar to a first-order chemical reaction in which the first-order rate constant is the sum of all of the rates (a parallel kinetic model). Thus, the lifetime is related to the facility of the relaxation pathway. If the rate of spontaneous emission, or any of the other rates are fast the lifetime is short (for commonly used fluorescent compounds typical excited state decay times for fluorescent compounds that emit photons with energies from the UV to near infrared are within the range of 0.5 to 20 ns). The fluorescence lifetime is an important parameter for practical applications of fluorescence such as fluorescence resonance energy transfer. There are several rules that deal with fluorescence.

Photodetectors

Photoresistor

A photoresistor is an electronic component whose resistance decreases with increasing incident light intensity. It can also be referred to as a light-dependent resistor (LDR), photoconductor, or photocell. A photoresistor is made of a high-resistance semiconductor. If light falling on the device is of high enough frequency, photons absorbed by the semiconductor give bound electrons enough energy to jump into the conduction band. The resulting free electron (and its hole partner) conduct electricity, thereby lowering resistance. A photoelectric device can be either intrinsic or extrinsic. An intrinsic semiconductor has its own charge carriers and is not an efficient semiconductor, e. g. silicon. In intrinsic devices, the only available electrons are in the valence band, and hence the photon must have enough energy to excite the electron across the entire bandgap. Extrinsic devices have impurities added, which have a ground state energy closer to the conduction band – since the electrons don't have as far to jump, lower energy photons (i. e. longer wavelengths and lower frequencies) are sufficient to trigger the device. If a sample of silicon has some of its atoms replaced by phosphorus atoms(impurities), there will be extra electrons available for conduction. This is an example of an extrinsic semiconductor.



Photometer, Figure 2 DNA microarrays. The probes are complementary fragment oligonucleotides, of target DNA or mRNA are spotted onto the microarray surface. This type of array is typically hybridized with target cDNAs that are labeled with fluorophores. The samples are amplified by PCR and hybridized to the microarray, and then scanned in a microarray scanner to visualize fluorescence of the fluorophores on the chip. Absolute levels of gene expression cannot be determined, but relative differences in expression among different spots can be estimated when we used the two-color array, each color represents two different samples

Photodiode

A photodiode is a semiconductor diode that functions as a photodetector. Photodiodes are packaged with either a window or optical fibre connection, in order to let in the light to the sensitive part of the device. They may also be used without a window to detect vacuum UV or X-rays. A phototransistor is in essence nothing more than a bipolar transistor that is encased in a transparent case so that light can reach the *base-collector junction*. The phototransistor works like a photodiode, but with a much higher responsivity for light, because the electrons that are generated by photons in the base-collector junction are injected into the base, and this current is then amplified by the transistor operation. However, a phototransistor has a slower response time than a photodiode. A photodiode is usually a p-n junction structure. When a photon of sufficient energy strikes the diode, it excites an electron thereby creating a mobile electron and a positively charged electron hole. If the absorption occurs in the junction's depletion region, or one diffusion length away from it, these carriers are swept from the junction by the built-in field of the depletion region, producing a photocurrent. Photodiodes can be used under either zero bias (*photovoltaic mode*) or reverse bias (*photoconductive mode*). In zero bias, light falling on the diode causes a current across the device, leading to forward bias which in turn induces *dark current* in the opposite direction to the photocurrent. This is called the photovoltaic effect, and is the basis for solar cells – in fact, a solar cell is just a large number of big photodiodes. Reverse bias induces only little current (known as saturation or back current) along its direction. But a more important effect of reverse bias is widening of the depletion layer (therefore expanding the reaction volume) and strengthening the photocurrent. Circuits based on this effect are more sensitive to light than ones based on the photovoltaic effect and also tend to have lower capacitance, which improves the speed of their time response. On the other hand, the photovoltaic mode tends to exhibit less electronic noise.

Photomultiplier Tubes (Photomultipliers, PMT)

Photomultiplier tubes are extremely sensitive detectors of light in the ultraviolet, visible and near infrared. These detectors multiply the signal produced by incident light by as much as 10^8, from which single photons can be resolved. Avalanche photodiodes have replaced photomultipliers in some applications, but photomultipliers are still used in most cases. The electron multiplier consists of a number of electrodes, called dynodes. Each dynode is held at a more positive voltage than the previous one. The electrons leave the photocathode, having the energy of the incoming photon (minus the work function of the photocathode). As they move towards the first dynode they are accelerated by the electric field and arrive with much greater energy. On striking the first dynode, more low energy electrons are emitted and these, in turn, are accelerated toward the second dynode. The geometry of the dynode chain is such that a cascade occurs with an ever-increasing number of electrons being produced at each stage. Finally the anode is reached where the accumulation of charge results in a sharp current pulse indicating the arrival of a photon at the photocathode.

Avalanche Photodiodes (APDs)

Avalanche photodiodes (APDs) are photodetectors that can be regarded as the semiconductor analog to photomultipliers. By applying a high reverse bias voltage (typically 100-200 V in silicon), APDs show an internal current gain effect (around 100) due to impact ionization (avalanche effect). However, some silicon APDs employ alternative doping and beveling techniques compared to traditional APDs that allow greater voltage to be applied (> 1500 V) before breakdown is reached and hence a greater operating gain (> 1000). In general, the higher the reverse voltage the higher the gain. Since APD gain varies strongly with the applied reverse bias and temperature, it is necessary to control the reverse voltage in order to keep a stable gain. Avalanche photodiodes therefore are more sensitive compared to other semiconductor photodiodes. If very high gain is needed (10^5 to 10^6), certain APDs can be operated with a reverse voltage above the APD's breakdown voltage. In this case, the APD needs to have its signal current limited and quickly diminished. Active and passive current quenching techniques have been used for this purpose. APDs that operate in this high-gain regime are in Geiger mode. This mode is particularly useful for single photon detection provided that the dark count event rate is sufficiently low.



Photometer, Figure 3 Fluorescence-activated cell-sorting (FACS). The cell suspension is entrained in the center of a narrow, rapidly flowing stream of buffer liquid. The flow is arranged so that there is a large separation between cells relative to their diameter. A vibrating mechanism of actuator causes the stream of cells to break into individual droplets. The system is adjusted so that there is a low probability of more than one cell being in a microdroplet. Just before the stream breaks into microdroplets the flow passes through a fluorescence measuring station where the fluorescent character of interest of each cell is measured. An electrical charging ring is placed just at the point where the stream breaks into droplets. A charge is placed on the ring based on the immediately prior fluorescence intensity measurement and the opposite charge is trapped on the droplet as it breaks from the stream. The charged droplets then fall through an electrostatic deflection system that diverts droplets into containers based upon their charge. In some systems the charge is applied directly to the stream and the droplet breaking off retains charge of the same sign as the stream. The stream is then returned to neutral after the droplet breaks off

Key Research Findings

Biochemical and Medical Measurements

There is a wide range of applications for photometer in biochemistry and medicine. Especially, in micro/nano fluidics field, fluorescent chemical groups can be attached with small amount of biological molecules by a chemical reaction, and the fluorescence of the attached tag enables very sensitive detection of the molecule by fluorescent photodetector.

DNA Microarray

A DNA microarray (*gene* chip, DNA chip, or gene array) is a collection of microscopic DNA spots, commonly representing single genes, arrayed on a solid surface by covalent attachment to chemically suitable matrices. DNA arrays are different from other types of microarray only in that they either measure DNA or use DNA as part of its detection system. Qualitative or quantitative measurements with DNA microarrays utilize the selective nature of DNA-DNA or DNA-RNA hybridization under high-stringency conditions and fluorophore-based photodetection. DNA arrays are commonly used for expression profiling, i. e., monitoring expression levels of thousands of genes simultaneously, or for comparative genomic hybridization. Applications of these arrays include mRNA or gene expression profiling, comparative genomic hybridization (Array CGH), SNP detection arrays, and Chromatin immunoprecipitation (chIP) studies.

Fluorescent-Activated Cell Sorting (FACS)

Fluorescence-activated cell-sorting (FACS) is a specialised type of flow cytometry. It provides a method for sorting a heterogenous mixture of biological cells into two or more containers, one cell at a time, based upon the specific light scattering and fluorescent characteristics of each cell within microdroplet. It is a useful scientific instrument as it provides fast, objective and quantitative recording of fluorescent signals from individual cells as well as physical separation of cells of particular interest. The acronym FACS is trademarked and owned by Becton Dickinson although it is used within the scientific community as a general term.

Future Directions for Research

Photometer is important for identifying the materials in micro- and nano-scale flow, especially when the channel size is small and the flow speed is high. Although photometer itself does not have spatial resolution, the development of nanofluidics for single molecule detection should be desirable to develop new experimental methods and applications for single molecule based applications.

Cross References

- ► Bioprinting on Chip
- ► Infrared Imaging and Mapping for Biosensors
- ► Biosensors Using Laser
- ► Cell Sorting
- ► DNA Microarray
- ► Flow Cytometer Lab-on-Chip Devices
- ► Fluorescence
- ► Microfluidic Optical Devices
- ► SNP on Chip

References

1. Bohren CF, Huffman DR (1983) Absorption and Scattering of Light by Small Particles. Wiley, Hoboken
2. Stover JC (1995) Optical Scattering: Measurement and Analysis. SPIE Optical Engineering Press
3. Schena M, Shalon D, Davis RW, Brown PO (1995) Quantitative monitoring of gene expression patterns with a complementary DNA microarray. Science 270(5235):467
4. Wei C, Li J, Bumgarner RE (2004) Sample size for detecting differentially expressed genes in microarray experiments. BMC Genomics 5:87
5. Shapiro HM (2003) Practical Flow Cytometry. Wiley, Hoboken

Photometry

► Photometer

Photo Patterned

Synonyms

Lithography; Optical lithography

Definition

Photo patterned is a process used in IC and microfabrication to selectively remove parts of a thin film (photoresist). It uses light to transfer a geometric pattern from a photomask to a light-sensitive chemical on the substrate. A series of chemical treatments then engraves the exposure pattern into the material underneath the photoresist.

Cross References

- ► Bulk Micromachining
- ► Photolithography

Photopatterned Materials

► Stationary Phases in Microchannels

Photoresist Reflow

Definition

Photoresist reflow refers to a unique method to generate the photoresist patterns with hemispheric cross-section using heating effect of photoresist for 3-D microstructure fabrications. The 3-D structures are formed by heating up the photoresist to a certain high temperature after the photoresist is patterned by the conventional lithography. When the temperature is higher than the glass transition temperature of the photoresist, the photoresist begins to melt

and reflow. Due to the surface tension of the liquid resist and the surface property of the substrate, the resist always tends to form a convex shape on top of the substrate.
This is an effective way to form convex lens, cylinder type channels or round tops of the structures as the replica molds for MEMS applications.

Cross References

- ► Fabrication of 3-D Microfluidic Structures
- ► Photolithography
- ► Soft Photolithography
- ► Photoresist SU-8
- ► Photoresist Reflow
- ► Thick Resist Lithography

Photoresist SU-8

Definition

The photoresist SU-8 is an epoxy-based photosensitive polymer that losses its resistance to chemical etching when exposed to ultra-violet radiation. It is used especially in the transference of a structure pattern to a substrate. It offers properties such as high mechanical strength, good adhesion on many different substrate materials and biocompatibility. The fabrication of SU-8 structures is a low-cost process and ultra-violet lithography semiconductor compatible.

Cross References

- ► Lab-on-a-Chip Device for Chemical Analysis
- ► Microfabrication Techniques
- ► Photolithography
- ► Photoresist SU-8
- ► Photoresist Reflow
- ► Wafer Bonding

Photoresponsive Hydrogels

- ► Photosensitive Hydrogels

Photosensitive Hydrogels

Shu Yang
Materials Science and Engineering, University
of Pennsylvania, Philadelphia, PA, USA
shuyang@seas.upenn.edu

Synonyms

Photoresponsive hydrogels; Photoswitchable hydrogels

Definition

A hydrogel is defined as a network of hydrophilic polymer chains that is able to swell and retain large amounts of water. The crosslinks can be produced by chemical reactions to form covalent bonds, or physical interactions, such as hydrogen bonding, van der Waals force and polymer entanglement. Hydrogels can absorb over 99% water in their three-dimensional swollen network. Hydrogels possess a degree of flexibility very similar to natural tissue, due to their significant water content. Responsive hydrogels can reversibly change volume in response to a slight change of external stimulus, including pH, temperature, electric field, ionic strength, salt type, solvent, external stress or light. Photoresponsive is defined as a light-induced reversible change of chemical structures and physical properties.

Chemical and Physical Principles

Definition of Photochromism

Photochromism is the process of light-induced reversible color changes in a medium or more generally of their absorption spectra [1]. Photochromic compounds can exist in two different states, A and B, whose relative concentration depends on the wavelength of the incident light. The thermodynamically stable form A is transformed by irradiation into form B. The back reaction can occur either photochemically or thermally:

$$A \underset{h\nu_2 \text{ or } \Delta}{\overset{h\nu_1}{\rightleftharpoons}} B \tag{1}$$

Photochromic molecules, or light-sensitive chromophores, are chemical species having photochromic properties. Examples of photochromic molecules and photochromic processes are summerized in Table 1.

Chemical Processes Involved In Photochromism

Pericyclic reactions Cycloadditions are found in spiropyrans, spirooxazines, chromenes, hexa-1, 3, 5-triene, diheteroarylethenes, cyclohexa-1, 3-diene and spirodihydroindolizines systems.

Cis–trans isomerizations *Cis–trans* isomerizations occur in stilbenes, azobenzene, azines, thioindigoids, as well as some biological receptors.

Intramolecular hydrogen transfer Intramolecular hydrogen transfer is found in anils, benzylpyridines, tri-azoles, oxazoles, metal dithizonates and perimidinespirohexadienones.

Intramolecular group transfers Intramolecular group transfers are found in polycyclic quinones (periaryloxyparaquinones).

Dissociation processes Heterolytic bond cleavages occur in triarylmethanes and related systems.

When incorporating a small amount of photochromic molecules into a hydrogel matrix, either through chemical coupling or physical impregnation, a molecular level conformational change often leads to a macromolecular structural change and then macroscopic change of shape due to swelling and contraction in the hydrogel. Such a photoresponse has many advantages over other stimulation methods because:

- light is readily available;
- the amount of energy conversion can be carefully controlled by the wavelength, intensity of the exciting light, choice of chromophores and choromphore–polymer interactions;
- use of lasers offers high spatial resolution (up to nanometers), large areas and volumes, and fast speed; and
- it produces no waste during the photochemical process.

Key Research Findings

Hydrogels, which are crosslinked polymer networks surrounded with aqueous solution, are *intelligent* soft materials. In response to external stimuli, such as pH, temperature, light, electric potential, chemical agents and biological agents, polymer chains and water molecules will associate or dissociate, resulting in swelling and shrinking respectively, with a change of volume up to several hundred percent and a change of shape of the polymer.

In 1986, Irie and Kungwatchakun reported a synthesis of photosensitive gels by incorporating photosensitive molecules (1 – 4 mol%), such as leucocyanide and leucohydroxide, into the gel network [2]. These gels underwent volume changes upon irradiation; however, no phase transition was observed. In 1990, a photoinduced phase transition was first reported in thermoresponsive *N*-isopropylacrylamide (PNIPAAm) gels, by copolymerizing light-sensitive bis(4-(dimethylamino)phenyl)(4-vinylphenyl)methyl leucocyanide into the gel network [3]. In the absence of light the gels are neutral and undergo a sharp, yet continuous volume change. Upon irradiation by ultraviolet light, the neutral triphenylmethane leuco derivatives are dissociated into triphenylmethyl cations, creating internal osmotic pressure that induces swelling of the gels, showing a discontinuous volume phase transition. This transition process is slow since it depends on the photochemical ionization and subsequent recombination of ions.

Later, a much faster process (response time of the order of milliseconds) was reported. This was achieved by impregnating light-absorbing chromophores, trisodium salt of copper chlorophyllin, into PNIPAAm gels and illuminating with visible light [4, 5]. In this case, the phase transition was induced by local heating of polymer networks. According to the Flory–Huggins mean field theory, at equilibrium with zero osmotic pressure, the gel temperature, T, increases monotonically with the network density, ϕ:

$$T = T_{\mathrm{gel}}(\phi) \tag{2}$$

When illuminated by light, the chromophore absorbs the light and subsequently dissipates heat locally, inducing an increase in the local temperature. The temperature increment is proportional to the incident light intensity and the concentration of chromophore, and therefore also to the network density ϕ. Thus

$$T = T_0 + \alpha I_0 \phi \tag{3}$$

where T_0 is the ambient temperature, I_0 is the illuminating light intensity and α is a constant related to the heat capacity of the gel. Therefore

$$T_0 = T_{\mathrm{gel}}(\phi) - \alpha I_0 \phi \tag{4}$$

The term $\alpha I_0 \phi$ describes the ability of the system to undergo a local volume phase transition upon illumination of light. When the gel is in thermal equilibrium at a fixed gel temperature T, ϕ increase discontinuously with the increase of light intensity, I_0, beyond a threshold value. When I_0 is decreased, ϕ decreases discontinuously and the gel does not exhibit hysteresis as a function of I_0.

Because the increase of local temperature is the result of a balance between absorption of light and heat dissipation, the swelling and shrinking process of the gel in response to light is much faster compared to the response to ionization and ion migration, which requires collective diffusion of the gel network.

When introducing a small amount of ionic charge either through addition of salt or copolymerization of charged monomers in the light-sensitive gels mentioned above, the phase transition temperature was found also to be a function of pH. In ionic gels, the phase transitions are governed by the extent of hydrophobic interactions or the degree of hydrogen bonding induced between the polymer chains. The temperature and/or visible light intensity determine the extent of hydrophobic interactions, whereas pH affects the degree of hydrogen bonding. In the absence of external

Photosensitive Hydrogels, Table 1 Examples of photochromic molecules and photochromic processes

Photochromic molecules	Photochromic reactions
Spiropyrans	 CH3 CH3 N R O NO2 hν (UV) △ or hν (Vis) closed form open form -O +
Spirooxazines	 CH3 CH3 N R O hν (UV) △ or hν (Vis) closed form open form
Acridizinium cations	 2 N + hν (>300 nm) hν (254nm)
Fulgides and fulgimides	 O X hν1 hν2 open form closed form X = O (fulgides) X = NR (fulgimides)
Azobenzene and derivatives	 N hν (UV) △ or hν (Vis) trans cis
Anils and related compounds (hydrogen transfer)	
Polycyclic quinones (periaryloxyquinones)	 O hν (UV) △ or hν (Vis)
Triphenylmethane leuco derivatives	

stimulus, the ionic gel exhibits a large hysteresis between the collapsed and swollen states, which is indicative of the existence of two free energy minima. It would, therefore, be possible to control the phase behavior by manipulation of other external factors in addition to visible light.

According to the principle of kinetics of gels, the time needed for swelling and shrinking of a gel is dependent on the diffusion of water in and out of the hydrogel, which is proportional to the square of the characteristic linear dimension of a gel, l^2. It is expected that response time will be decreased to microseconds and nanoseconds if we can shrink the gel size to the submicrometer scale. This also means we need to perturb the environment extremely fast. Using a laser T-jump, a switching time of the order of $\sim$100 ns was observed in individual PNIPAAm nanogels [6].

Another common approach to prepare light-sensitive hydrogels is to covalently couple chromophores either in the polymer side chains or in the main chains [7, 8]. The chromophores undergo crosslinking through photodimerization or *trans–cis* isomerization, which brings about a change of the dipole moment or structure, the dissociation of the chromophore into ions, or change of hydrophilicity of the polymer, thus varying the shape and volume phase transition of the hydrogel network.

Photocrosslinking linear PNIPAAm with photodimerizable chromophores, such as stilbene, stilbazolium and acridizinium cations, has been studied [8]. The reversible photodimerization reactions allow for dynamic tuning of the crosslinking density of the gel network, which in turn influences the phase transition temperature and swelling ratio. The introduction of the chromophores could affect the hydrophobic nature of the polymer. Compared to stilbene and stilbazolium, the positive charge in acridizinium cations compensates the hydrophobicity of aromatic groups, resulting in a smaller decrease of the critical transition temperature of PNIPAAm, $-2.7\,°\mathrm{C}$ vs. $-11.0\,°\mathrm{C}$ in the stilbazolium photopolymer, and a higher photoreversibility. A complete reversion to monomer will be impossible if the monomer absorption is higher than that of dimers at the irradiation wavelength.

A conformational change of a hydrogel can be induced by photoisomerization of a chromophore group, such as azobenzene and spiropyran. For azobenzene and derivates, the thermodynamically more stable *trans* form is converted into the metastable *cis* isomer by UV light irradiation, and the *cis* isomer can return to the *trans* form by visible light irradiation or thermally in the dark. A spiropyran group is known to undergo photoisomerization from its neutral, *closed* spiro form (colorless and nonpolar) to the *open* merocyanine form (highly polar and zwitterionic) under UV light irradiation, which isomerizes back to the spiro form under visible light irradiation or thermally in the dark [8]. The formation of zwitterionic merocyanines can be further exploited to bind with charged molecules to manipulate the phase transition of hydrogels. Kinetics study suggests that photoisomerization is dependent on solvent, polymer composition and the free volume distribution around the chromophore. A bulky substituent in the polymer chains seems to slow down the *trans–cis* isomerization but increases the thermal recovery rate (the *cis–trans* isomerization). Typically, it requires hundreds of seconds up to minutes of photoirradiation to induce reversible swelling and shrinkage of hydrogels using this approach.

Examples of Application

Because of their interesting properties, such as swellability in water, hydrophilicity, biocompatibility and lack of toxicity, hydrogels have been widely used in biological and biomedical applications. In response to an environmental stimulus, responsive hydrogels undergo various types of volume phase transition, which converts chemical potential energy into mechanical force. Thus, responsive hydrogels have been used in microfluidic devices such as actuators, pumps and valves, artificial muscles, controlled delivery, sensors and separation. Responsiveness to light and the potentially fast response time provide an additional opportunity to design microfluidic devices that can be triggered without disturbing the system. One could design a submicrometer optical switch on a gel surface, and control an on/off nature by focusing the light in a local area of the gel, generating features analogous to *memory* or *display*. When photoresponsive polymers are grafted onto a porous membrane, reversible UV or visible light irradiation induces a change of the polymer solubility in water, leading to photoregulating permeability and mass transport through the membrane [8].

Cross References

- ► pH-sensitive Hydrogel
- ► Photolithography
- ► Photoresist SU-8
- ► Photoresist Reflow
- ► Thermosensitive Hydrogel
- ► Soft Photolithography

References

1. Bouas-Laurent H, Dürr H (2001) Organic Photochromism. Pure Appl Chem 73:639–665
2. Irie M, Kunwatchakun D (1986) Photoresponsive Polymers. 8. Reversible Photostimulated Dilation of Polyacrylamide Gels

Having Triphenylmethane Leuco Derivatives. Macromolecules 19:2476–2480

3. Mamada A, Tanaka T, Kungwatchakun D, Irie M (1990) Photoinduced Phase-Transition of Gels. Macromolecules 23:1517–1519
4. Suzuki A, Tanaka T (1990) Phase-Transition in Polymer Gels Induced by Visible-Light. Nature 346:345–347
5. Suzuki A, Ishii T, Maruyama Y (1996) Optical switching in polymer gels. J Appl Phys 80:131–136
6. Reese CE, Mikhonin AV, Kamenjicki M, Tikhonov A, Asher SA (2004) Nanogel nanosecond photonic crystal optical switching. J Am Chem Soc 126:1493–1496
7. Chung DJ, Ito Y, Imanishi Y (1994) Preparation of Porous Membranes Grafted with Poly (spiropyran-containing methacrylate) and Photocontrol of Permeability. J Appl Polym Sci 51:2027–2033
8. Kuckling D, Ivanova IG, Adler HJP, Wolff T (2002) Photochemical switching of hydrogel film properties. Polymer 43:1813–1820

Photoswitchable Hydrogels

► Photosensitive Hydrogels

Photothermal Effect

► Thermal Lensing, Detection

pH-Sensitive Hydrogel

Dominic S. Peterson
Chemistry Division, Los Alamos National Laboratory,
Los Alamos, NM, USA
DominicP@lanl.gov

Synonyms

pH control device; pH-sensitive valve; pH sensor; Valve

Definition

A pH-sensitive hydrogel is a gel structure that is sensitive to changes in pH. Most commonly, the hydrogel will swell or contract in response to a change in the local chemical environment. Hydrogels can be made using in situ polymerization techniques, which makes it very useful in incorporating them into microfluidic systems. These pH-sensitive hydrogels have applications in forming valves that are sensitive to a change in pH or in systems that can release a compound when the pH is changed, and in pH sensors.



pH-Sensitive Hydrogel, Figure 1 Schematic representation of the reproducible swelling that occurs in a pH-sensitive hydrogel

Overview

A pH-sensitive hydrogel consists of a gel structure which varies with a change in the pH of the system. The basis of a pH-sensitive hydrogel is a structure that swells or contracts depending on the pH of the solution (Fig. 1). The use of a hydrogel structure allows these devices to be easily fabricated within a microfluidic system. Placing these devices in a microfluidic device enables flow control to be accomplished by changing the pH of the solution that is being pumped through the system. Alternatively, a series of these hydrogels make it possible to sort solutions according to pH by placing two different hydrogels sensitive to either basic or acidic solutions into a microfluidic system, or by using a hydrogel to regulate the pH of solutions flowing out of a mixing hydrogel.

Basic Methodology

Hydrogels are polymer structures that contain a high water content. Because they contain a large amount of water, their physical configuration can change in response to the local chemical environment [1]. In particular, hydrogels undergo a change in volume in response to chemical or physical stimuli. Hydrogels that change their structure in response to temperature have been widely studied [2]. Hydrogels can also change in response to chemical conditions. The chemical environment that is often able to induce this type of volume change in a hydrogel is the pH of the system. In this type of a system the swelling of the hydrogel is produced from an ion-driven effect. How fast the gel expands is therefore dependent on the diffusion of ions into and out of the gel. Furthermore, swelling of the gel is an equilibration effect, and will be limited by how fast a steady state can be reached within the gel.

The ability to change in response to pH has been applied to two general applications. The first is as a valve. Because the volume of the hydrogel changes, a valve can be fabricated in which a hydrogel expands to plug a channel under one set of conditions and contracts to allow flow under another set of conditions. The other application that hydrogels have been applied to is as pH detectors. This approach involves allowing a hydrogel to swell with a change in pH and to detect and measure the swelling of the hydrogel.

One of the great challenges in microfluidics is in preparing functional devices within a microfluidic system. Often, it is necessary to fabricate a functional device within a microfluidic system. Hydrogels are very useful in microfluidic systems because they can be either fabricated in bulk or they can be fabricated in situ. The in situ fabrication approach is particularly important in microfluidics because it greatly simplifies the fabrication of complex devices compared to more traditional methods of fabrication, which are usually based on semiconductor fabrication technology. The in situ synthesis of a hydrogel is usually performed using monomers that are somewhat hydrophilic, such a acrylic acid (AA), or 2-hydroxyethyl methacrylate (HEMA). A hydrophilic monomer allows water to penetrate the hydrogel, and therefore enables the polymer to swell and contract. The crosslinking monomer (such as ethylene glycol dimethacrylate, DGDMA) allows the polymer to retain its cohesiveness with swelling. The amount of crosslinker used affects many parameters in the resulting hydrogel such as how much it can swell, how much water can permeate the gel and the pore structure of the polymer. The actual polymerization step requires an initiator. The use of a photoinitiated monomer enables the hydrogel to be patterned into a specific portion of the microfluidic channel. The fabrication methods for placing a hydrogel into a microfluidic channel are critical in enabling their use in these applications.

Key Research Findings

There are two major areas that pH-sensitive hydrogels are used for in microfluidics. The first of these applications is as a valve. A hydrogel has the ability to change volume. When they expand, the hydrogel has the effect of closing off a channel. When the hydrogel contracts, the channel is opened. An early example of this approach involved introducing a pH-sensitive hydrogel into a microfluidic system in order to regulate the pH in the system [3]. This study utilized a circular chamber with a pH-sensitive hydrogel and included inlet channels that had solutions at a pH of 2 and 12. The outlet of the system was regulated at a pH of 7 by the action of the hydrogel. This study found that the geometry of the hydrogel has a strong effect on the regulation of the outlet pH. When a circular hydrogel is used the outlet pH was observed to oscillate; however, the use of a star-shaped hydrogel greatly reduced the oscillation. Another study fabricated two pH-sensitive hydrogels in a "V" shape in order to mimic a biomimetic valve such as those found in the veins [4]. This valve arrangement has the effect that flow through the valve is enabled in the forward direction, but is restricted in the reverse direction, effectively acting as a check valve. Furthermore, flow regulation is enhanced because the pressure drop across the valve is constant across a wide range of flow rates ($0.4-1.8\,\text{ml/min}$). This ability to have the same pressure drop across the valve is due to the elasticity of the hydrogel; it enables the hydrogel to act as a pressure regulator in the microfluidic system, while the pH sensitivity enables the valve to be activated and deactivated depending on the solution being used. In another study a pH-sensitive hydrogel sphere was used as the actuating element in a microfluidic valve [5]. This approach involved placing the pH-sensitive hydrogel microsphere in a chamber. The swelling microsphere contacts a thick-centered membrane. This contact causes the membrane to close the valve. This approach allows the valve to be activated without the hydrogel being present in the main microfluidic channel, and the activation of the valve can be performed independently of the solvent in the microfluidic channel. This is because the hydrogel microsphere is in a channel separate from the main channel, and the two channels are isolated from one another via the membrane. The primary drawback is that this approach requires a more complex fabrication process to incorporate the valve into the microfluidic system.

In addition to pH-sensitive hydrogels being used as valves in microfluidic devices, they have also been used as a method to determine the pH of a solution in a microfluidic device. The pH of the solution in a microfluidic system can be very important in performing functions on a solution, such a protein digestion or a synthetic step. However, detection of the pH in a microfluidic channel can be very difficult due to the small volumes involved in these channels. One approach involved incorporating a pH-sensitive dye within a hydrogel [6]. The synthesis of the hydrogel with the pH-sensitive dye is relatively simple because the hydrogel is simply synthesized with the dye incorporated within the polymer gel structure. The pH of the system can then be determined by the color of the dye. Using UV-visible spectroscopy enables very specific determination of the dye state. The primary limitation on the time required to determine the pH is the diffusion of within the hydrogel. Another approach that has been demonstrated to measure the pH in a microfluidic channel involves a hydrogel actuating a piezoresistive device [7]. This approach involves fabrication of a pH-sensitive hydrogel in contact with a bending plate. This plate then actuates a piezoresistor, the electrical signal of which is then read to give an indication of the pH in the microfluidic device. While the piezoresistor makes fabrication of these systems more complex, it has the advantage of enabling rapid and precise electronic indication of the pH of the system.

A key parameter that has been studied for pH-sensitive hydrogels is their mechanical properties [8]. This is very important because the macromolecular properties will determine how the gel performs in the system. For instance, the mechanical properties in a valve will determine how well it can seal a channel, and can also affect how fast the valve can close. A wide variety of experimental techniques have been developed to characterize the mechanical properties of microgels, particularly the tensile strength [9]. In these studies it was found that the mechanical properties are dependent on the extent of equilibrium swelling as well as the polymerization conditions used to produce the gel. The mechanical properties can be controlled by adjusting the amount of crosslinker that is used in the hydrogel composition. The ability to control the mechanical properties of a pH-sensitive hydrogel will be critical in applying these components into specific microfluidic applications.

Future Directions for Research

While there have been a number of devices demonstrated for pH-sensitive hydrogels, there is a great deal of development work that can still be done. In particular pH-sensitive hydrogels need to be demonstrated in more robust environments, and their reliability and longevity need to be explored. The use of these systems in more robust situations will enable them to be explored in more complex microfluidic systems. In particular, devices will need to be made that can incorporate multiple valves in order to enable complex flow paths to be constructed. While this may be accomplished utilizing pH-sensitive hydrogels, it may be advantageous to incorporate valves in the system that are actuated via different approaches. This may further enable complex systems to be fabricated. The synthesis of pH-sensitive hydrogels will also need to become more refined to enable them to be placed into these more complex systems. Part of this development will include refining the synthetic methods to produce hydrogels with the desired mechanical, physical and chemical properties. In developing hydrogels with specific chemical properties there are two possible approaches. The first is to incorporate specific chemical functionalities into the polymerization mixture of which the hydrogel is made. The other approach is to coat or react a specific chemical functionality on the surface [10]. The ability to control the chemistry will enable these devices to be used with a wide variety of solutions and may improve their versatility.

Cross References

- ► Capillary Force Valves
- ► Electrochemical Valves
- ► Electromagnetic Valves
- ► Microfluidic Sample Manipulation
- ► Photosensitive Hydrogels
- ► Sol–Gel Technique
- ► Thermosensitive Hydrogel

References

1. Eddington DT, Beebe DJ (2004) Flow control with hydrogels. Adv Drug Deliv Rev 56:199–210
2. Gariepy ER, Leroux JC (2004) In situ-forming hydrogels – review of temperature-sensitive systems. Eur J Pharm Biopharm 58:409–426
3. Eddington DT, Liu RH, Moore JS, Beebe DJ (2001) An organic self-regulating microfluidic system. Lab Chip 1:96–99
4. Yu Q, Bauer JM, Moore JS (2001) Responsive biomimetic hydrogel valve for microfluidics. Appl Phys Lett 78:2589–2591
5. Park JY, Oh HJ, Kim DJ, Baek JY, Lee SH (2006) A polymeric microfluidic valve employing a pH-responsive hydrogel microsphere as an actuating source. J Micromec Microeng 16:656–663
6. Moorthy J, Beebe DJ (2002) A hydrogel readout for autonomous detection of ions in microchannels. Lab Chip 2:76–80
7. Trinh QT, Gerlach G, Sorber J, Arndt KF (2006) Hydrogel-based piezoresistive pH sensors: Design, simulation and output chararcteristics. Sens Actuators B 117:17–26
8. Johnson BD, Beebe DJ, Crone WC (2004) Effects of swelling on the mechanical propertis of a pH-sensitive hydrogel for use in microfluidic devices. Mater Sci Eng C 24:575–581
9. Johnson BD, Bauer JM, Niedermaier DJ, Crone WC, Beebe DJ (2004) Experimental techniques for mechanical characterization of hydrogels at the microscale. Experim Mech 44:21–28
10. Kraft ML, Moore JS (2003) n-Alkyl fatty acid modified microgels: ton permeation as a function of chain length. Langmuir 19:910–915

pH-Sensitive Valve

► pH-Sensitive Hydrogel

pH Sensor

► pH-Sensitive Hydrogel

Physical-Chemical Etching

► Anisotropic Etching

Physical Domain

Synonyms

Physical region

Definition

This refers to the actual spatial domain under consideration. In computational methods, this is replaced by a computational domain using a simplified geometry and boundary conditions.

Cross References

- ► Meshless Methods
- ► Volume and Finite Difference Method for Modeling and Simulation

Physical Etching

► Sputter Etching

Physical Region

► Physical Domain

Physical Vapor Deposition

► Sputtering for Film Deposition

Picoliter Flow Calibration

ZHANHUA SILBER-LI
LNM, Institute of Mechanics, Chinese Academy of
Sciences, Beijing, China
lili@imech.ac.cn

Synonyms

pL; Flow rate

Definition

Flow rate is defined as the volumes or masses of fluids flowing through a special area in unit time. The standard unit of flow rate is m^3/s. Picoliter (pL) is a unit of volume, $1\,\mathrm{pL} = 10^{-15}\,\mathrm{m}^3$ and transfers to other units as: $1\,\mathrm{pL} = 10^{-3}\,\mathrm{nL} = 10^{-6}\,\mu\mathrm{L} = 10^{-9}\,\mathrm{mL} = 10^{-12}\,\mathrm{L}$. An example describes the volume of a picoliter: a droplet with a diameter of 20 µm has a volume of about 4.2 pL.

Overview

Classic flow rate measurement tools are mass flowmeter, electromagnetic flowmeter, rotameter and turbine flowmeter, their measurement ranges being normally larger than $10^{-7}\,\mathrm{m}^3/\mathrm{s}$ (0.1 mL/s). But in microscale flows, the range of flow rate is usually $10^{-7} - 10^{-12}\,\mathrm{m}^3/\mathrm{s}$, in other words, $10^2\,\mu\mathrm{L/s}$–1 nL/s. In nanoscale flows, the flow rate is from 10^{-15} to $10^{-18}\,\mathrm{m}^3/\mathrm{s}$ (1 pL/s–1 fL/s). So the measurement and calibration methods will be different for micro- or nanoscale flows, compared to classic macroscale flows.

Colin [1] has reviewed some measurement methods in microscale flow, including the weighing method, thermal method, wave reflection method, acoustic vibration method, and so on. Here two common methods, the weighing and displacement methods, are introduced. In the weighing method [2], the total mass M of fluids flowing out within a time Δt are measured, and the flow rate is calculated as:

$$Q_\mathrm{g} = \frac{M}{\Delta t} \tag{1}$$

The uncertainty of this method is directly proportion to the accuracies of balance and stopwatch. If a balance with an accuracy of within ±0.001 g is used to measure a kind of flow whose range is larger than 1 µL/s, the measurement accuracy is about ±1%.

The displacement method [1, 3] is another kind of indirect method, which calculates flow rate by measuring the displacement L of a fluid in a capillary tube with a diameter D and interval Δt:

$$Q_\mathrm{m} = \frac{\pi D^2 L}{4\Delta t} \tag{2}$$

Because flow rate Q_m is proportion to the second power of diameter D, the uncertainty of flow rate is mainly related to the accuracy of D. The measuring precision of the diameter of capillary tubes using a toolmaker's microscope is ±0.01 mm, so the uncertainty can reach ±2%, for a flow rate range of 1 – 100 nL/s.

For saving samples, reducing cross-contamination and operating fluids with smaller volume in microfluidic devices, designers hope that the dimensions of channels or tubes are as small as possible. When the characteristic dimension of channels decreases to the nanoscale, picoliter-scale flow will occur. De Heij et al. [4] designed a nozzle array of 50 µm diameter, which can produce

100 – 700 pL discrete droplets. Ahmed and Jones [5] controlled dielectrophoretic (DEP) force, capillary force and inertial force by an electrophoresis method, and produced discrete droplets on the substrate of a channel, whose volumes were smaller than 10 pL. He et al. [6] drove water flow through a nozzle of diameter 1.7 µm by electric pulse, and formed 8 – 14 pL water droplets in an oil environment making use of Rayleigh instability. Ellson [7] used focused acoustic energy to spray droplets from the surface of fluids, whose volumes are about 0.1 pL–1 µL. Karnik et al. [8] controlled protein to transmit in nano- and microchannels under the effect of an electrostatic field, the dimension of the channel being 1 – 100 nm, equivalent to the Debye length. The height of the channel cross-section was just 30 nm, so this device can be used to control picoliter-scale flow of protein solution.

From these literature reports we can see that pL flows have been achieved and applied in sampling devices of biology chips, in micro- or nanochannels and two-phase flows, so the measurement and calibration of pL volume fluid flow have great importance attached to them.

Basic Methodology

The methods that are usually used to calibrate ultra small-volume fluids are the static weighing method, comparing method, flow velocity measurement method, and so on. The study of picoliter flows has just begun, so the perfect calibration methods have not been formed yet. This section will review partial methods to produce pL flow, their measurement accuracy and the relevant calibration methods. A fuller coverage is not possible because of space limitations.

Visual Inspection Measurement

As shown in the literatures, pL flows always present as droplet form. So it is important to pay attention to measuring the volume of droplets in pL flow measurement. The common methods are calculating volume by the size of the microvial or microchannel in which droplets are formed, or measuring droplet diameters from their images and calculating volume by the ball volume formula:

$$V_{\mathrm{d}} = \frac{4}{3}\pi R^3 = \frac{1}{6}\pi D^3 \tag{3}$$

Here, the radius R or diameter D are measured from images captured by a microscope, with a calibrated microruler.

De Heij et al. [4] designed a nozzle array to produce continuous droplets. The diameter of the nozzle is 50 µm.



Picoliter Flow Calibration, Figure 1 The droplet volume measured with stroboscope camera [4]



Picoliter Flow Calibration, Figure 2 Side view of a DEP-driven finger emerging from a sessile droplet using parallel co-planar electrode (top) and the cross-sectional (view A–A) [5]

A digital stroboscope (Visit Video Stroboskop MOCRON-RT) was used to record the spraying process of droplets, and then the image processing software was used to calculate the diameter (Fig. 1). The accuracy of image measurement is ±5%. They have measured droplets from 0.1 to 0.7 nL, and the measurement accuracy is ±0.1 pL.

Ellson et al. [7] used the method of focused acoustic energy to eject a pL droplet from a nanoliter-scale well, the droplet diameter being also measured by a digital stroboscope. In their experiment, 20 pL droplets were ejected from 20 nL liquids. The accuracy of liquid volume measurement is determined by the accuracy of image measurement. They used a precisely calibrated micrometer to measure the image size, the accuracy being estimated as about ±5 µm based on the image resolution. The minimum volume of experimental droplets is 20 pL, and the measurement accuracy is ±0.1 pL. Thousands of droplets were produced continuously, and the whole fluid volume divided by the number of droplets calibrated the average volume.

Ahmed et al. [5] proposed a method to produce discrete pL droplets on substrate by an electrophoresis method. A finger will be formed when water is driven by electrophoresis force above an electrode (Fig. 2). The key parameter dominating capillary instability is the Bond number, which is expressed by $\mathrm{Bo} = \rho g R^2 \gamma$, which presents the relation between hydrostatic pressure $\rho g R$ and Laplace pressure


Cathodic Deposition
Auxillary/ pseudoreference electrode
Working Electrode
Microcavity with drop of Ag⁺ solution
Ag⁰ deposited on TNB electrode
Linear Sweep Voltammetry, Anodic stripping of Ag°
Ag⁰ oxidatively removed from TNB electrode

Picoliter Flow Calibration, Figure 3 Schematic diagram of the electrode and the procedure for small volume measurement using anodic stripping voltammetry [9]

γ/R. If the electrical potential is taken out for $\mathrm{Bo} < 10^{-3}$, the capillary force will dominate, and the finger will be broken to form droplets. The front part of the finger is assumed to form a hemispherical shape droplet, whose diameter is about $D = 2w + g$, where w is the width of the electrode and g is the interspace between the electrodes. The volume of the hemispherical droplet can be calculated by reference to formula (3).

Ahmed et al. used a camera to record the droplet forming process at 500 frames/s, 6 continuous frames being used to calculate the extending length of the finger, and compared to the estimated value of droplet diameter. In the experiment, the average volume of 30 droplets is 40 pL. If the size of the microelectrodes decreases further, 10 pL volume droplets would be obtained. The minimum measurable volume is of the order of 10 pL, and the accuracy is about ±5 pL, but the volume measured by this method has not been calibrated.

In the methods discussed above, fluid volumes were measured by visual inspection, so other methods are needed for fluids which cannot be inspected directly or which flow in opaque channels.

Electrical Measurement

Coulometric Method

Vandaveer et al. [9] proposed anodic stripping voltammetry to measure fluids with ultra-small volume. The advantages of this method are avoiding optical detecting devices, fast and easy and suitable for irregular shapes of fluid flows.

A microvial with electrodes in the wall is used in this method. The volume of fluids can be calculated by exhaustive reduction of current under the effect of continuous changed voltage (Fig. 3). Recessed microdisk (RMD) electrode, tubular nanoband (TNB) electrode and reference electrodes were installed on the bottom, sidewall and top of the microvial, respectively. Soluble metal species were added into the sample fluids, and then they were deposited on the electrodes on the sidewall driven by voltage. After that, the deposited metal species were removed under a voltage of -0.6 to 1 V. Droplets volumes can be measured indirectly by the quantity of electricity integrated from the relation between removed current and voltage of reference electrodes, the formula being expressed as [9]:

$$V_{\mathrm{s}} = \frac{Q}{nFC^{*}} \tag{4}$$

where Q is the total Coulomb value integrated from the anodic removed curve, n is the moles of electrons transferred per mole of metal ions, F is the Faraday constant ($F = 96{,}485\ \mathrm{C/mol}$) and C^{*} is the initial concentration of metallic ions in solution.

Electrodes are installed on the wall of the microvial, and as a result the minimum size of the microvial is 8 μm in height and 13 μm in diameter; in other words, 1 pL measurable volume. The accuracy of this method is 1.49 nL ± 20 pL. It is easier for smaller volume fluids to dissipate and deposit, so this method is better for measuring fluid volumes below 1 nL. Also, because the method is coulometric, calibration curves are not required [9].

Impedance Method

Hjelt et al. [10] proposed an integrated, noninvasive method to measure sub-nanoliter volume droplets. Microelectrodes were integrated on the bottom of a reactor and covered with a layer of SiN. According to the impedance characteristic between electrodes, the size of droplet can be obtained. The volumes of the reactor fabricated in the experiment are 60–40 pL. The relation between liquid volumes and electrodes voltages was calibrated, and the accuracy of voltage measurement was ±5%, and the resolution of volume measurement could be up to 1 pL. To calibrate the measurement results of the impedance method, the authors used a fluorescence microscope to inspect the liquid volume inside the reactor, and they concluded an accuracy could be achieved of ±5%. The minimum measuring volume in the experiment is 30 pL, and the measurement accuracy is ±1.5 pL.

Optical Measurement

Markov et al. [11] measured the velocity of the flow in an electrophoresis chip by backscatter interferometry (Fig. 4). An infrared laser with a shutter was used to heat the fluid periodically in an upstream position, and a bicell was used as a position-sensitive device in the detecting section. The



Picoliter Flow Calibration, Figure 4 Diagram of backscatter interferometry for fluid flow measurement [11]

changes of refractive index of fluids as a function of temperature were converted to electrical signals, and these signals had the same frequency as that of the heating laser, but with different phase. The phase difference between the shutter signal and the bicell signal was used to calculate the time interval Δt during which fluids flowed from the heating section to detecting section. Then the velocity can be calculated. The authors also calibrated the relations between the flow rate and the phase difference.

Experiments were carried out in a 200 μm channel, with a measurement accuracy of $0.833 - 1.66\,\text{nL/s} \pm 0.127\,\text{nL/s}$, but the velocity measurement results were not calibrated.

Key Research Findings

Several methods to obtain and measure pL fluid volumes have been reviewed: visual inspection measurement, electrical measurement and optical measurement. Visual inspection measurement captures a droplet image by microscope or stroboscope, and measures the size of the droplet in the image to calculate its volume. The minimum volume of droplets can reach 10 pL, with a measurement accuracy of ±0.1 pL. Coulometric and impedance methods were introduced as electrical measurements, which measure the quantity of electricity or impedance of fluids to calculate the droplet volume. The minimum volume of droplets measurable with these methods is 30 pL, with ±1 pL accuracy. Finally, optical measurement, especially the backscatter interferometric method, was introduced. This method measures the difference of light phase to calculate the velocity of a fluid, and then calculates the volume. Flow rates from 0.833 to $1.66\,\text{nL/s}$ were measured in experiments and the accuracy was $\pm 0.127\,\text{nL/s}$.

Obviously, visual inspection measurement is the easiest method with the highest accuracy to date. The impedance method also uses it for calibration [10].

For calibration, if the cumulative volume of liquid is larger than 1 μL, the volume weighing method is suggested. But for calibration of single droplet volume, the visual inspection method is simpler.

Future Directions for Research

In principle, calibration methods of ultra small-volume droplets include static weighing method, comparing to standard volume and calibration by high-accuracy velocity measurement. Traditional optical devices, microscopes, stroboscopes, etc., are still the main measurement method for pL fluid volume calibration, and the accuracy is about 0.1 pL. Novel measurement techniques are needed for calibration of sub-picoliter fluid volume.

Cross References

- ► Fluid Metering
- ► Droplet Dispensing
- ► Nanoscale Flow Visualization

References

1. Colin S (2004) Microfluidique. Hermes Science Publications, French 393
2. Sharp KV, Adrian RJ (2004) Transition from laminar to turbulent flow in liquid filled microtubes. Exp Fluids 36:741–747
3. Cui HH, Silber-Li ZH, Zhu SN (2004) Flow characteristics of liquids in microtube driven by high pressure. Phys Fluids 16:1813–1810
4. De Heij B, Steinert C, Sandmaier H, Zengerle R (2003), A tuneable and highly-parallel picolitre-dispeser based on direct liquid displacement. Sens Actuators A 103:88–92
5. Ahmed R, Jones TB (2006) Dispensing picoliter droplets on substrates using dielectrophoresis. J Electrostatics 64:543–549
6. He MY, Kuo JS, Chiu DT (2005) Electro-generation of single femtoliter- and picoliter-volume aqueous droplets in microfluidic systems. Appl Phys Lett 87, 031916
7. Ellson R (2002) Picoliter:enabling precise transfer of nanoliter and picoliter volumes. DDT, 7(5):S32–34
8. Karnik R, Castelino K, Majumdar A (2006) Field-effect control of protein transport in a nanofluidic transistor circuit. Appl Phys Lett 88, 123114
9. Vandaveer WR, Fritsch I (2002) Measurement of ultra-small volumes using anodic stripping voltammetry. Anal Chem 74:3575–3578
10. Hjelt KT, van den Doel R, Lubking W, Vellekoop MJ (2000) High-resolution liquid volume detection in sub-nanoliter reactors. Sens Actuators 83:61–66
11. Markov DA, Dotson S, Wood S, Bornhop DJ (2004) Noninvasive fluid flow measurements in microfluidic channels with backscatter interferometry. Electrophoresis 25:3805–3809

Piezoelectric

Definition

Coupling phenomenon between mechanical strain and stress, and the electric field strength and displacement in a material. Requires a polarization that remains within a material in the absence of the application of an external field, in turn requiring a non-enantiomorphic polar symmetry in the composition of the material.

Cross References

- ► Non-Centrosymmetric
- ► Ferroelectric
- ► Acoustics Based Biosensors

Piezoelectric Drop-on-Demand

► Piezoelectric Microdispenser

Piezoelectric Ink Jet

► Piezoelectric Microdispenser

Piezoelectric Materials for Microfluidics

JAMES FRIEND, LESLIE YEO
Micro/Nanophysics Research Laboratory, Monash University, Clayton, VIC, Australia
james.friend@eng.monash.edu.au

Synonyms

Lead zirconate titanate; PZT; Zinc oxide; Quartz; AlN; Electroactive materials; Electromechanically coupled materials; Artificial muscle materials; Electrets

Definition

Piezoelectricity means *squeeze* or *pressure* electricity, from the Greek *pieze* which means to press or squeeze. The casual definition of piezoelectric materials is that they develop an electric charge differential along an axis of ►piezoelectric polarization if placed under appropriate mechanical strain, called the ►direct piezoelectric effect, and deform if an electric field is applied along the same axis of polarization, the converse piezoelectric effect. The electric field to mechanical strain coupling occurs when the positive and negative charge of the individual ions within the material do not displace symmetrically upon the application of an external strain. Strictly speaking, piezoelectric materials exhibit electric polarization upon the application of a stress and vice versa. Often the casual and strict definitions are the same, though confusion may arise with the casual definition. All piezoelectric materials are ►anisotropic, and there are useful examples of piezoelectric materials that are single crystals, polycrystalline ceramics, and polymers. Many of the known piezoelectric materials have at one time or another been used as sensors or actuators in microfluidics, for which their rapid response and large force transmission have been beneficial, though researchers have had to learn to overcome small strains, thermal losses, aging, and difficulties in fabrication, especially in process compatibility.

Overview

Piezoelectric materials offer the ability to directly transform (transduct) from electrical to mechanical energy and vice versa, convenient for microtechnology in sensing and actuation; a material is said to be piezoelectric if an applied stress generates an electric field within, and vice versa. They may be used to provide static and dynamic deformation at frequencies up to several gigahertz, depending on the motion to be induced, the scale of the device, and the material used. Compared to other methods of power transduction, including electrostatic, electrostrictive, magnetostrictive, and electromagnetic means, piezoelectric transduction typically provides large forces at small strain rates ($< 1\%$ strain typically) for actuation, and relatively large voltages and small currents for sensing. Piezoelectricity is usually treated as a linear interaction between mechanical and electrical phenomena, though this assumption is generally invalid for high-power applications or in materials with either large losses or large deformations (polymers). The ►hysteresis in such conditions is the deviation from linear transduction. This is different than the typically weak ►electrostrictive [2] behaviour of many insulating materials which exhibit a strain proportional to the square of the applied field, though some materials, like ►relaxor ferroelectrics are exceptions. Single crystal materials are usually naturally polarized, implying they may be used without additional treatment, while polycrystalline and polymeric materials must be polarized with either an applied electric field or an applied strain prior to use.

Recognition of the piezoelectric effect has been known since ancient times [6]. Theophrastus noted in 314 BC the attraction of small pieces of straw and wood to tourmaline after heating, but recognition of the presence of an electrostatic field causing the attraction had to wait for the nineteenth century, along with a name provided by Brewster in 1824: ►pyroelectricity. All pyroelectric materials are piezoelectric; Jacques and Pierre Curie studied piezoelectric materials in the 1880's and were able to describe many of the characteristics of the phenomena used in applications today. Once synthetic quartz and high-performance materials like barium titanate, lead zirconate titanate and subsequent variations became available in the 1950's and 60's, a wide variety of applications beyond sonar became feasible.

Many of the piezoelectric materials used for applications are single crystals or polycrystalline matrices of single-crystal grains. Overall, crystalline media may be organized into thirty-two crystal classes or point groups based on their symmetry; the names of some of these groups are commonly known; triclinic, orthorhombic, cubic, and isotropic are especially well-known. ▶Hermann–Mauguin notation [1] is often used to precisely describe the properties of these materials. For example, triclinic materials are represented with either a 1 or –1, depending on whether or not the material has ▶inversion symmetry, respectively. Of these thirty-two crystal classes, twenty-one possess no centre of symmetry; they are said to be ▶non-centrosymmetric or to lack inversion symmetry, and all but one of these classes are piezoelectric. The exception is class 432, which has other symmetries which negate the non-centrosymmetric nature of the crystal structure. The remaining crystal classes which are piezoelectric are 1, 2, m, 222, mm2, 23, 3, 3m, 32, 4, –4, 422, 4mm, –42m, –43m, 6, –6, 622, 6mm, and –62m.

Out of these twenty piezoelectric classes, ten also lack symmetric characteristics along a particular axis, and are therefore able to retain a natural ionic charge separation in the crystalline structure along that axis—a ▶spontaneous polarization—that forms an electric dipole which remains even without an externally applied electric field. This is in contrast to all insulating or dielectric materials which polarize to form such dipoles only with an externally applied field. These crystal groups are *pyroelectric*, including 1, 2, m, mm2, 3, 3m, 4, 4mm, 6, and 6mm. A crystal belonging to one of these crystal groups that has a polarization that may be reversed through the application of an external electric field is said to be ▶ferroelectric. A distinct characteristic of ferroelectric materials, in the strictest definition, is the presence of hysteresis. All ferroelectric materials are both piezoelectric and pyroelectric. Lead zirconium titanate (PZT or $\mathrm{Pb_xZr_{(1-x)}O_3}$) is one of the most important ferroelectric materials, class 6mm, though PZT is only found in polycrystalline form as a ▶perovskite $\mathrm{ABO_3}$.

Most piezoelectric materials tend to be quite capacitive. The pyroelectric nature of all polarized piezoelectric materials can cause the development of significant charging across the material due to thermal expansion coupled to the direct piezoelectric effect causing a charge displacement from the thermal strain; voltages of 1 kV are not unheard of in PZT after a temperature change of 50 °C, and caution is warranted in any application. However, a piezoelectric material will lose its spontaneous polarization if its temperature is raised above the ▶Curie temperature, near the temperature of maximum dielectric constant, the ▶Curie–Weiss temperature. Since the mechanical and electrical behavior are coupled, a change in boundary conditions in one domain will change the behavior of the material in the other domain. By leaving a polarized piezoelectric element open-circuited, the mechanical stiffness of the material will be higher, called stress stiffening. Similarly, mechanically clamping a piezoelectric element will tend to increase the impedance.

With polycrystalline and amorphous *piezoelectric* materials, a spontaneous polarization can rarely be obtained as a consequence of the natural ordering within the material during fabrication. Some form of applied strain or electric field is necessary to polarize the material before use. A common sensor material, polydivinylfluoride (PVDF), is stretched to polarize it, while standard PZT must have a large ($> 10\,\mathrm{kV/cm}$) electric field applied to it to order the electric Weiss domains, or groups of dipoles, in the general direction of the applied field. It is a common misconception that polarization of these materials implies the dipole polarization is rotated to be aligned with the electric field or that the atomic structure itself is realigned within the material. In reality, the atomic structure is essentially fixed, preventing such rotation or realignment. Once polarized, the material can be said to be a member of the pseudocrystal group ∞ mm, and is often represented as a 6 mm material. Generally, the domains are randomly oriented beforehand.

At times, particularly with amorphous materials, the term *electret* is used instead of *piezoelectric* to describe a material; the term was introduced as an electric counterpart to the magnet, defined as all materials that are able to retain at least a quasi-permanent electric polarization within, and perhaps trap charge on the surface (or within in a porous material). Polytetrafluorethylene (PTFE) is a powerful electret material. The critical difference among the terms is that electrets retain polarization in thermodynamic *non*equilibrium, pyroelectric materials retain polarization in equilibrium, ferroelectrics permit the equilibrium polarization to be reversed along the polarization axis, and piezoelectric materials may or may not have any polarization at all.

Basic Methodology

Modeling Linear Piezoelectricity

Equations for structural dynamics within the solid material, along with the standard equations for electrostatics, are sufficient to model most piezoelectric materials and their applications. The full electromagnetic equations are


T
Mechanical Stress
S
Mechanical Strain
E
Electric Field Strength
D
Electric Field Displacement or Flux Density
g
$= \frac{\text{field}}{\text{appl. stress}} = \frac{\text{strain}}{\text{applied charge / electrode area}}$
Piezoelectric Field to Stress Coupling
h
$= \frac{\text{field}}{\text{appl. strain}} = \frac{\text{stress}}{\text{applied charge / electrode area}}$
Piezoelectric Field to Strain Coupling
e
$= \frac{\text{stress}}{\text{applied field}} = \frac{\text{short circuit charge / electrode area}}{\text{applied strain}}$
Piezoelectric Stress to Field Coupling
d
$= \frac{\text{strain}}{\text{applied field}} = \frac{\text{short circuit charge / electrode area}}{\text{applied stress}}$
Piezoelectric Strain to Field Coupling
Constant Electric Field (Short Circuit)
Constant Stress (Free)
s^E
Compliance
c^E
Stiffness
β^T
Inverse Permittivity
ε^T
Permittivity
Constant Electric Displacement (Open Circuit)
Constant Strain (Clamped)
s^D
Compliance
c^D
Stiffness
β^S
Inverse Permittivity
ε^S
Permittivity
k_i
$i = \begin{cases} P & \text{— Planar} \\ 33 \text{ or } t & \text{— Thickness} \\ 15 & \text{— Shear} \\ 31 & \text{— Transverse} \end{cases}$
Electromechanical Coupling Factor
K^S
Relative Dielectric Constant
K^T
$= \frac{\varepsilon^T}{\varepsilon^0} = \frac{\varepsilon^T}{8.85 \times 10^{-5}\,\text{F/m}}$
Relative Dielectric Constant

Piezoelectric Materials for Microfluidics, Figure 1 Variables used in linear piezoelectric material analysis

unnecessary since the mechanical motion propagates at $\sim 10^3$ m/s, several orders of magnitude less than the electric field, permitting the so-called *quasistatic* assumption. For the same reason, magnetic fields are typically weak and may be safely ignored. Still, equations to describe the electrical and mechanical behaviour are needed in addition to the constitutive equations for the material.

Using Auld's notation [1], the full tensor form of the linear constitutive equations with the strain and charge displacement as dependent on the stress and applied field may be written as

$$\mathbf{T} = \mathbf{c}^E : \mathbf{S} - \tilde{\mathbf{e}} \cdot \mathbf{E}$$

$$\mathbf{D} = \mathbf{e} : \mathbf{S} + \tilde{\boldsymbol{\varepsilon}}^S \cdot \mathbf{E} \qquad (1)$$

where the terms are defined with units in Figs. 1 and 2 (using contracted notation to be described later). The tilde ($\sim$) is a transpose while the single and double dots represent an inner product across one and two dimensions


Mechanical
s
D — Compliance measured with electrodes open circuited
11
Related to stress in 1 dir. (strain for stiffness, c)
Related to strain in 1 dir. (stress for stiffness, c)
T
1
Indicates stress is in 1 dir.
c
E — Stiffness measured with electrodes short circuited
36
Related to strain in 3 dir. (stress for compliance, s)
Related to shear stress around 3 dir. (strain for compliance, s)
S
6
Indicates strain about 3 dir.
Piezoelectric
d
31
Electrodes to support this field are perpendicular to the 3 dir.
Piezoelectrically induced strain or the applied stress is in the 1 direction
h
15
Electrodes to detect this field are perpendicular to the 1 dir.
The applied strain or the piezoelectrically induced stress is in shear about the 2 direction
g
31
Electrodes to detect this field are perpendicular to the 3 dir.
The applied stress or the piezoelectrically induced strain is in the 1 direction
e
15
Electrodes to support this field are perpendicular to the 1 dir.
Piezoelectrically induced stress or the applied strain is in shear around the 2 dir.
Electric
ε
S — Permittivity measured with material fixed (clamped)
11
Charge displacement in 1 dir.
Electric field in 1 dir.
E
1
Indicates field is in 1 dir.
β
T — Inverse permittivity measured with material free
33
Electric field in 3 dir.
Charge displacement in 3 dir.
D
3
Indicates charge displacement is in 3 dir.
Units

Variable	Name	Derived Units (MKS)	Fundamental Units
c	*Stiffness*	Pa	kg / m • s^2
s	*Compliance*	1 / Pa	m • s^2 / kg
T	*Stress*	Pa	kg / m • s^2
S	*Strain*	—	—
d	*Piezo. Strain Coefficient*	m / V *or* C / N	C • s^2 / kg • m
g	*Piezo. Voltage Coefficient*	m • V / N *or* N • m / C	m^2 / C
e	*Piezo. Stress Coefficient*	C / m^2	C / m^2
h	*Piezo. Stiffness Coefficient*	V / m	kg • m / C • s^2
ε	*Permittivity*	F / m	C^2 • s^2 / kg • m^3
β	*Inverse Permittivity*	m / F	kg • m^3 / C^2 • s^2
D	*Electric Charge Displacement*	F • V / m	C / m^2
E	*Electric Field Strength*	V / m	kg • m / C • s^2
K	*Relative Dielectric Constant* (ε/ε$_0$)	—	(ε$_0$ = 8.85 x 10^{-5} F / m)
k	*Electromechanical Coupling Factor*	—	—

Piezoelectric Materials for Microfluidics, Figure 2 Description of subscripts used in piezoelectric analysis

of the adjacent tensors, respectively. In piezoelectric materials analysis, the contravariant basis vectors are typically Cartesian, therefore orthonormal and so the covariant basis is not needed. Upon choosing a coordinate system, an indicial notation may be adopted [14],

$$T_{ij} = c^E_{ijkl} S_{kl} + e_{mij} E_m$$

$$D_i = e_{ijk} S_{jk} + \varepsilon^S_{ik} E_k \,, \tag{2}$$

where summation is assumed across repeated subscripts in products of terms, i. e., k and l in $c^E_{ijkl} S_{kl}$; all of the subscripts range from 1 to 3. The strain S_{ij} is given by astrain-displacement relationship $S_{ij} = \frac{1}{2}\left(u_{i,j} + u_{j,i}\right)$ where the comma in the subscript represents a spatial derivative ($u_{i,j} = \partial u_i / \partial x_j$). The momentum equation is $T_{ij,i} + f_i = \rho \ddot{u}_j$ where $\ddot{u} = \partial^2 u_j / \partial t^2$ and f_i represents a body force. The time-dependent electric field, E_i, and charge displacement, D_i, may be related through the polarization and permeability equation $D_i = \varepsilon_0 E_i + P_i$ where P_i is the polarization. A scalar potential φ may be defined to represent the electric field, $E_i = \varphi_{,i}$, while the charge displacement is *spatially* constant along a particular direction, $D_{i,i} = 0$.

A piezoelectric Poynting energy flux akin to those defined for nonpiezoelectric acoustic waves and electromagnetic waves is given by $-\left(T_{ij}\dot{u}_j - \varphi \dot{D}_j\right)$.

In attempting to use these equations to solve problems, a complete and consistent set of electromechanical boundary conditions are needed. Tiersten [13] provides such a derivation, though solution of anything beyond simple problems requires computation. Fortunately, the mechanical and electrical boundary conditions are usually separable; $u_i = u_i^*$ or $n_i T_{ij} = n_i T_{ij}^*$, and $n_i D_i = n_i D_i^*$ or $\varphi = \varphi^*$. The starred terms represent constants, time-varying values, or values defined within another media adjacent to the piezoelectric material. The outward vector normal to the boundary surface is given by n_i.

Even in the most anisotropic of materials substantial symmetry exists in Eq. (2), permitting contraction of the subscripts [4] and giving a simpler form for the constitutive equation;

$$\begin{aligned} T_p &= c_{pq}^E S_q + e_{mp} E_m \\ D_n &= e_{nr} S_r + \varepsilon_{nm}^S E_m\,, \end{aligned} \tag{3}$$

where p, q, and r range from 1 to 6, while m and n range from 1 to 3. There is *not* a one-to-one correspondence between the two representations in Eqs. (2) and (3). For example, the strain S_{ij} is $S_p = 2^{|\mathrm{sgn}(i-j)|}$. For this reason and the confusion that can arise in defining the momentum and strain-displacement equations, one must use care in solving problems with the contracted notation. The value of p in terms of i, j varies notoriously between authors, but the IEEE standard [4] is the most commonly accepted version; here $p = \frac{1}{2}(i+j)(1-|\mathrm{sgn}(i-j)|) + |\mathrm{sgn}(i-j)|(9-i-j)$ for i, j = 1,2,3; here the vertical bars $|\cdot|$ represent an absolute value while $\mathrm{sgn}(\cdot)$ is the *signum*, zero when x is zero and the sign of x otherwise.

Most solutions found by solving the complete set of piezoelectric material equations are very simple approximations. Computation, typically using finite element analysis software, is often necessary for practical cases. The ability to handle piezoelectric materials in commercially available finite element analysis software varies, though ANSYS (ANSYS Inc., Canonsburg, PA, USA) and COMSOL (COMSOL Inc., Burlington, MA, USA) are two well-known packages with decent implementations. However, a one-dimensional model of the piezoelectric material behavior offers many of the salient features without the complexity.

Piezoelectricity in One Dimension: Transducer Equations

If we assume a longitudinal plane wave propagates along the z-axis—assumed to be a principal axis of the material—the only non-zero displacement will also be along the z- or 3-axis, $u = u(z,t)$ and the strain will be $S_{33} = \partial u / \partial z$. Further, assuming the applied electric field is only along the 3-axis, $E_3 = E$ while $E_1 = E_2 = 0$, we may find the resulting constitutive equations from substitution into Eq. (2), closely following the approach used by Dieulesaint and Royer [3]:

$$\begin{aligned} T_{ij} &= c_{ij33}^E S_{33} + e_{3ij} E_3 \\ D_i &= e_{i33} S_{33} + \varepsilon_{i3}^S E_3 \end{aligned}\,, \tag{4}$$

where i must be equal to j. If we set $i = j = 1$, the motion would be transverse to the applied field (setting i and j to 2 would give the same result), while if $i = j = 3$, the motion is parallel. Taking the latter option with Eq. (4),

$$\begin{aligned} T_{33} &= c_{3333}^E S_{33} + e_{333} E_3 \\ D_3 &= e_{i33} S_{33} + \varepsilon_{33}^S E_3 \end{aligned} \;\rightarrow\; \begin{aligned} T &= c^E S + eE \\ D &= eS + \varepsilon^S E \end{aligned}\,, \tag{5}$$

where we discard the subscripts here and subsequently. The electric field, E, may be eliminated from Eq. (5):

$$T = \left(c^E + \frac{e^2}{\varepsilon^S}\right)\frac{\partial u}{\partial z} - \frac{e}{\varepsilon^S} D, \tag{6}$$

giving

$$\frac{\partial T}{\partial t} = \left(c^E + \frac{e^2}{\varepsilon^S}\right)\frac{\partial^2 u}{\partial z \partial t} - \frac{e}{\varepsilon^S}\frac{\partial D}{\partial t} \tag{7}$$

if we take a time derivative. The quantity $\left(c^E + \frac{e^2}{\varepsilon^S}\right) \equiv c^D$; this relation is also true for the tensor form, and indicates the relationship between the constant-field stiffness c^E and the constant field displacment c^D. There are relations between all of the coefficients as described later. The current passing through the piezoelectric element is given by $I = \int \frac{\partial D}{\partial t}\, dA$ where A is the cross-sectional area perpendicular to the z-axis. Since the wave is planar, $\frac{\partial D}{\partial t}$ is a constant across the cross-sectional area A, so $\frac{\partial D}{\partial t} = I/A$, and Eq. (7) simplifies to

$$\frac{\partial T}{\partial t} = c^D \frac{\partial^2 u}{\partial z \partial t} - \frac{eI}{\varepsilon^S A}\,. \tag{8}$$

Differentiating Eq. (8) with respect to z,

$$\frac{\partial^2 T}{\partial t \partial z} = c^D \frac{\partial^3 u}{\partial z^2 \partial t} = c^D \frac{\partial^2 v}{\partial z^2}\,, \tag{9}$$

noting $I = I(t)$ alone, and $v = \partial u/\partial t$. From the momentum equation, if the body force $f = 0$,

$$\frac{\partial T}{\partial z} = \rho \frac{\partial^2 u}{\partial t^2} \implies \frac{\partial^2 T}{\partial z \partial t} = c^D \frac{\partial^2 v}{\partial z^2} = \rho \frac{\partial^2 v}{\partial t^2}, \tag{10}$$

The latter part of Eq. (10), $c^D \partial^2 v/\partial z^2 = \rho\, \partial^2 v/\partial t^2$, may be solved as a wave equation:

$$v(x, t) = \mathrm{e}^{\jmath \omega t} \left(V_1\, \mathrm{e}^{-\jmath k z} + V_2\, \mathrm{e}^{\jmath k z} \right). \tag{11}$$

where the circular frequency-wavenumber ratio is related to the material properties by $\omega/k = \sqrt{c^D/\rho}$ and $\jmath = \sqrt{-1}$; the first and second parts of the solution in Eq. (11) are waves traveling in the positive and negative z-directions, respectively.

An acoustic impedance may be defined as $Z = T/v = \sqrt{c^D \rho}$ —the latter term found by substituting Eq. (11) into Eq. (10)—and used to describe the stress wave propagation by substitution of Eq. (11) into Eq. (8) and integrating,

$$\begin{aligned} T &= \mathrm{e}^{\jmath \omega t} \\ &\left[\frac{k c^D}{\omega} \left(-V_1\, \mathrm{e}^{-\jmath k z} + V_2\, \mathrm{e}^{\jmath k z} \right) + \jmath \frac{e I_0}{\omega \varepsilon^S A} \right]. \end{aligned} \tag{12}$$

Notice that the wave is *electroelastic*, with a propagating electric field wave in addition to the elastic behavior, and that $I = I_0\, \mathrm{e}^{\jmath \omega t}$.

The relationship between the mechanical and electrical behavior may now be determined using the stress and particle velocity fields for a piezoelectric element of homogeneous composition, finite thickness t, and constant cross-sectional area A as shown in Fig. 3. Note the polarization of the material indicated by the arrow adjacent to P. The stress T, when expressed on the faces of the piezoelectric element normal to the z-axis, becomes the force delivered by the element:

$$\begin{aligned} F_1 &= AT|_{z=z_1} = \mathrm{e}^{\jmath \omega t} \\ &\cdot \left[\frac{A k c^D}{\omega} \left(-V_1\, \mathrm{e}^{-\jmath k z_1} + V_2\, \mathrm{e}^{\jmath k z_1} \right) + \jmath \frac{e I_0}{\omega \varepsilon^S A} \right], \\ F_2 &= AT|_{z=z_2} = \mathrm{e}^{\jmath \omega t} \\ &\cdot \left[\frac{A k c^D}{\omega} \left(-V_1\, \mathrm{e}^{-\jmath k z_2} + V_2\, \mathrm{e}^{\jmath k z_2} \right) + \jmath \frac{e I_0}{\omega \varepsilon^S A} \right]. \end{aligned} \tag{13}$$

The velocities on the faces $z = z_1$ and $z = z_2$ are given by

$$\begin{aligned} v_1 &= -v|_{z=z_1} \\ &= -\mathrm{e}^{\jmath \omega t} \left(V_1\, \mathrm{e}^{-\jmath k z_1} + V_2\, \mathrm{e}^{\jmath k z_1} \right), \\ v_2 &= v|_{z=z_2} \\ &= \mathrm{e}^{\jmath \omega t} \left(V_1\, \mathrm{e}^{-\jmath k z_2} + V_2\, \mathrm{e}^{\jmath k z_2} \right) \end{aligned}. \tag{14}$$

Using Eq. (14), it is possible to eliminate V_1 and V_2 from the force Eq. (13);

$$\begin{aligned} V_1\, \mathrm{e}^{\jmath \omega t} &= -\frac{v_1\, \mathrm{e}^{\jmath k z_2} + v_2\, \mathrm{e}^{\jmath k z_1}}{2\jmath \sin kd} \\ V_2\, \mathrm{e}^{\jmath \omega t} &= \frac{v_1\, \mathrm{e}^{-\jmath k z_2} + v_2\, \mathrm{e}^{-\jmath k z_1}}{2\jmath \sin kd} \end{aligned}, \tag{15}$$

where $d = z_2 - z_1$, giving

$$\begin{aligned} F_1 &= \frac{k c^D A}{\jmath \omega} \left[\frac{v_1}{\tan kd} + \frac{v_2}{\sin kd} \right] + \jmath \frac{e I_0}{\omega \varepsilon^S} \\ F_2 &= \frac{k c^D A}{\jmath \omega} \left[\frac{v_1}{\sin kd} + \frac{v_2}{\tan kd} \right] + \jmath \frac{e I_0}{\omega \varepsilon^S} \end{aligned} \tag{16}$$

making use of several trignometric identities.

From the field displacement equation in Eq. (5), the applied voltage V is given by

$$\begin{aligned} V &= \int_{z_1}^{z_2} E\, dz \\ &= \int_{z_1}^{z_2} \left(-\frac{e}{\varepsilon^S} S + \frac{D}{\varepsilon^S} \right) dz \\ &= -\frac{e}{\varepsilon^S} u|_{z=z_1}^{z_2} + \frac{1}{\varepsilon^S} \int_{z_1}^{z_2} D\, dz \\ &= \frac{e}{\varepsilon^S} \left(u|_{z=z_1} - u|_{z=z_2} \right) + \frac{I_0 d}{\jmath A \omega \varepsilon^S} \end{aligned} \tag{17}$$

since $D = (1/A) \int I_0\, \mathrm{d}A = I_0/(\jmath \omega A)$, implying $\int_{z_1}^{z_2} D\, \mathrm{d}z = I_0 d/(\jmath \omega A)$. Since $u = -\jmath \omega v$ and the *static* or *shunt capacitance* is $C_0 = \frac{\varepsilon^S A}{d}$,

$$V = -\jmath \left[\frac{\omega e}{\varepsilon^S} (v_1 - v_2) + \frac{I_0}{\omega C_0} \right], \tag{18}$$

forming the third of three equations which may be combined to give a matrix relationship between the input voltage and current and the output forces and velocities on the



Piezoelectric Materials for Microfluidics, Figure 3 Schematic of a piezoelectric element to illustrate the process of analysis

faces of the piezoelectric element:

$$\begin{bmatrix} F_1 \\ F_2 \\ V \end{bmatrix} = -\jmath \begin{bmatrix} \frac{\zeta}{\tan kd} & \frac{\zeta}{\sin kd} & -\frac{e}{\omega\varepsilon^S} \\ \frac{\zeta}{\sin kd} & \frac{\zeta}{\tan kd} & -\frac{e}{\omega\varepsilon^S} \\ \frac{\omega e}{\varepsilon^S} & -\frac{\omega e}{\varepsilon^S} & \frac{1}{\omega C_0} \end{bmatrix} \begin{bmatrix} v_1 \\ v_2 \\ I \end{bmatrix} \tag{19}$$

if $\zeta \equiv \frac{kc^D A}{\omega}$ as the mechanical impedance, with units of mass/time. Notice that

- The output forces F_1 and F_2 are linearly proportional to the input current I and piezoelectric stress coefficient e, and inversely proportional to the permittivity ε^S and circular frequency ω.
- The change in velocity across the element $v_1 - v_2$ is linearly proportional to the input voltage V and permittivity ε^S, and inversely proportional to the circular frequency ω and piezoelectric stress coefficient e.

Approximating Transducer Behavior with Equivalent Circuit Equations

From the expression in Eq. (19) most forms of equivalent circuit models of piezoelectric elements may be found. The Van Dyke circuit [14] is the simplest, using discrete electrical components combined to approximate the piezoelectric element's behavior. I tis used to represent the electrical impedance about one resonance of a freely suspended piezoelectric element, using a shunt capacitor in parallel with an inductor, resistor, and capacitor placed in series to represent the *motional* or resonance behavior of the element. A multivibrator Van Dyke model may be formed by adding additional motional legs, each representing another resonance. Since it lacks any explicit treatment of the output force and velocity, it is not especially useful beyond electrical characterization (see Smits' method below). Other circuit models incorporate the mechanical behavior, and the most prevalent of these are the *Mason* [14] and Krimholtz–Leedom–Matthaei [7] (KLM) circuits.

The Mason equivalent circuit may be derived directly from Eq. (19). It is sometimes called a *transmission-line* circuit model since the transcendental terms in the matrix appear in the same way when modeling power transmission lines. Most importantly, the circuit represents more than one resonance with these transcendental terms. Consider first an element that does not have piezoelectricity, implying the piezoelectric stress coefficient $e = 0$. The force-velocity relationships in the nonpiezoelectric element would then be

$$F_i = \frac{v_1 + v_2}{\jmath \sin kd}\zeta + (\jmath\zeta \tan kd/2)\, v_i \tag{20}$$

for $i = 1, 2$. This relates the force and velocity on one face of the nonpiezoelectric element to the other face. For an element that is piezoelectric, $e \neq 0$, and we can use the third equation in Eq. (19) to determine the actual force due to the applied voltage by substitution in the top two equations.

Piezoelectric Coefficient Relations

Typically, a piezoelectric material's properties are measured through a series of experiments on a set of samples, and these measurements give results easily substituted into the matrix representations of the material. Unfortunately, very few of the components within each of the matrices are defined with the measured data, but the remaining data may be calculated using relations between the coefficients. At times, not enough data are provided to do this; for whatever reason, the data set is incomplete. This problem is especially common with piezoelectric material manufacturers. Further complicating the problem, companies sometimes provide redundant data that are inconsistent—calculated results from some of the provided data does not match the rest of the data that are provided.

The simplest relationship between the electrical property tensors is the inverse relationship between the permittivity, $\boldsymbol{\varepsilon}$, and the inverse permittivity, $\boldsymbol{\beta}$. The equations are

$$\boldsymbol{\beta}^S = \boldsymbol{\varepsilon}^{S^{-1}} \qquad \text{and} \qquad \boldsymbol{\beta}^T = \boldsymbol{\varepsilon}^{T^{-1}}. \tag{21}$$

Other relations transform the matrix representation of the permittivity or inverse permittivity from one set of boundary conditions (either fixed stress or fixed strain) to the other; for the permittivity,

$$\boldsymbol{\varepsilon}^S = \boldsymbol{\varepsilon}^T - \mathbf{d}\,\mathbf{c}^E\tilde{\mathbf{d}} = \boldsymbol{\varepsilon}^T - \mathbf{e}\,\mathbf{s}^E\,\tilde{\mathbf{e}}, \tag{22}$$

and for the inverse permittivity,

$$\boldsymbol{\beta}^S = \boldsymbol{\beta}^T + \mathbf{h}\,\mathbf{s}^D\,\tilde{\mathbf{h}} \;=\; \boldsymbol{\beta}^T + \mathbf{g}\,\mathbf{c}^D\,\tilde{\mathbf{g}} \tag{23}$$

Again, there is a simple inverse relationship between the mechanical coefficient matrices, namely, the stiffness, **c** and the compliance, **s**;

$$\mathbf{c}^E = \mathbf{s}^{E^{-1}} \quad \text{and} \quad \mathbf{c}^D = \mathbf{s}^{D^{-1}}. \tag{24}$$

The boundary conditions on the mechanical property matrices may be changed with the following transformations:

$$\mathbf{c}^D = \mathbf{c}^E + \tilde{\mathbf{e}}\,\boldsymbol{\beta}^S\,\mathbf{e} \;=\; \mathbf{c}^E + \tilde{\mathbf{h}}\,\boldsymbol{\varepsilon}^S\,\mathbf{h}, \tag{25}$$

for the stiffness, and

$$\mathbf{s}^D = \mathbf{s}^E + \tilde{\mathbf{g}}\,\boldsymbol{\varepsilon}^T\,\mathbf{g} \;=\; \mathbf{s}^E + \tilde{\mathbf{d}}\,\boldsymbol{\beta}^T\,\mathbf{d}, \tag{26}$$

for the compliance.

Unfortunately, there are no inverse relations between the piezoelectric coefficients. But, there are a wide collection of equations that describe one piezoelectric quantity in terms of the others. The following is a complete list of these equations:

$$\mathbf{d} = \boldsymbol{\varepsilon}^T\mathbf{g} = \mathbf{e}\mathbf{s}^E, \tag{27}$$

$$\mathbf{g} = \boldsymbol{\beta}^T\mathbf{d} = \mathbf{h}\mathbf{s}^D, \tag{28}$$

$$\mathbf{h} = \boldsymbol{\beta}^S\mathbf{e} = \mathbf{g}\mathbf{c}^D, \tag{29}$$

and

$$\mathbf{e} = \boldsymbol{\varepsilon}^S\,\mathbf{h} \;=\; \mathbf{d}\,\mathbf{c}^E. \tag{30}$$

Through substitution between these equations, many more relations between the variables can be expressed. Written differently, the relations are clearer. In the following equation, the dots within the parentheses represent where the variable at the top of each column would be placed to form the equation for the variable on the left side of each row:

$$\begin{array}{ccccc}
 & \mathbf{d} & \mathbf{g} & \mathbf{h} & \mathbf{e} \\
\mathbf{d} = & (\cdot) & \boldsymbol{\varepsilon}^T(\cdot) & \boldsymbol{\varepsilon}^T\,(\cdot)\,\mathbf{s}^E & (\cdot)\,\mathbf{s}^E \\
\mathbf{g} = & \boldsymbol{\beta}^T\,(\cdot) & (\cdot) & (\cdot)\mathbf{s}^D & \boldsymbol{\beta}^S\,(\cdot)\,\mathbf{s}^D. \\
\mathbf{h} = & \boldsymbol{\beta}^S\,(\cdot)\,\mathbf{c}^E & (\cdot)\,\mathbf{c}^D & (\cdot) & \boldsymbol{\beta}^S\,(\cdot) \\
\mathbf{e} = & (\cdot)\,\mathbf{c}^E & \boldsymbol{\varepsilon}^S\,(\cdot)\,\mathbf{c}^D & \boldsymbol{\varepsilon}^S\,(\cdot) & (\cdot)
\end{array} \tag{31}$$

Experiment and Use

Physically measuring the coefficients of a piezoelectric material can be pursued in several different ways. Two of the most popular are the IEEE method [14] and Smits' technique [11]. Smits' technique has the advantage in that it requires fewer samples to be made by eliminating the radial resonator shape, especially important when considering the time necessary to make, machine, electrode, pole, and test piezoelectric material. Further, Smits' method uses exact equations in the calculation of the material constants, makes possible the calculation of loss data at the same time, and the electric and mechanical constants are measured at the same frequency unlike the IEEE method.

The technique is iterative, but the iteration process is strongly convergent. To determine all of the coefficients of a given piezoelectric material, four different geometries must be used. Each of these geometries encourage a particular vibration mode shape which reduce the number of material coefficients that are participating in the motion to a reasonable number. Named after the desired mode shape, the *thickness/shear* resonator, the *length expansion* resonator with perpendicular field, the *thickness expansion* plate resonator, and the *length expansion* resonator with parallel field provide different material constants when using Smits' technique on each of them. Convergence criteria and proof are provided in Smits' paper [11], but he claims that convergence to the correct values is usually achieved in eight iterations.

Manufacturing Methods

There are numerous ways to manufacture piezoelectric materials, roughly divided into crystal-growth methods for the single crystal media and a collection of techniques for polycrystalline piezoelectric media. The most obvious and troublesome difference in fabricating piezoelectric materials is the presence of lead in lead-based polycrystalline piezoelectrics like PZT; the lead is present in solid solution and tends to leach from the ceramic during sintering unless a source of lead is provided to maintain equilibrium. For all piezoelectric materials that exhibit remnant polarization, charging effects can be a problem during processing, enough to cause arcing and device failure or substrate cracking.

Among the crystal-growth techniques, the Czochralski (CZ) crystal growth technique is most common, particularly for lithium niobate, lithium tantalate, barium gallium orthophosphate (BGO), langasite, There are other techniques, and this is an active area of research. The development of single-crystal high-strain relaxor ferroelectrics like lead manganese niobate-lead titanate (PMN-PT) [8] using the high-temperature flux technique is a notable example of another approach.

For ceramic materials, there are many approaches available to a researcher for fabrication, including the simple pellet press, tape casting, screen printing, sputter deposition (especially PZT and ZnO), sol-gel techniques for thin films, pulsed-laser deposition, and the hygrothermal technique [10] for deposition of quality PZT onto titanium.

Key Research Findings

During World War II, the discovery of PZT was a fortuitous and remarkable improvement on the state of the art in piezoelectric materials engineering. Since then, modest improvements in performance of piezoelectric materials have been made, with the discovery of single-crystal high-strain PMN-PT materials [8] an important milestone. In the past few years, however, methods for studying and manipulating the structure of ceramics on the scale of the unit cell and lower—the grain structure, the ferroelectric domains, and the structure of the unit cells themselves—have appeared [5]. These techniques are especially well-suited for improving the quality of piezoelectric materials; a recent potassium-sodium niobate/lithium tantalate/lithium antimonate ceramic has a piezoelectric performance equivalent to PZT while eliminating toxic lead [12]. Further, given the need to fabricate ► thin-film devices with features measured in nanometers in conjunction with micro- and nanofluidics, an understanding of the nature of polarization and ferroelectric domain growth in materials compatible with fabrication at these scales is vital. The applications for this technology span many disciplines: nonvolatile memory for computer technology, sensors and sensors for medical and biological diagnostics and actuators and microwave devices for consumer applications [9].

Future Directions for Research

The development of characterization and fabrication methods approaching the unit-cell size of known piezoelectric materials has reenergized the area of piezoelectric materials research in the past few years. By tailoring the structure of piezoelectric materials to maximize the polarizability, strength, and maximum strain, major advances are just beginning to appear. Work on applying the replete knowledge of bulk piezoelectric materials to thin-film materials research remains incomplete, from fabrication of PMN-PT to lead-free ceramics at small scales.

Looking beyond ceramic materials to electrets, polymer and elastomeric piezoelectric materials, and so-called electroactive materials, a wide-open field of research in high-strain piezoelectric materials is appearing. Using the same technology to manipulate the chemical and physical structures of complex ionic or nanotube-imbibed polymers, strains of well over 50 % have been obtained in this new class of material, many examples of which are biocompatible. Improvements in reliability, tolerance of extreme ambient conditions, and modeling are important areas that remain to be considered.

Cross References

► Piezoelectric Microdispenser

References

1. Auld BA (1989) Acoustic fields and waves in solids, vol. 1. Krieger, Malabar
2. Bellaiche L, Vanderbilt D (1999) Intrinsic piezoelectric response in perovskite alloys: PMN-PT versus PZT. Phys Rev Lett 83(7):1347–1350
3. Dieulesaint E, Royer D (2000) Elastic Waves in Solids II. Springer, Berlin
4. Hearmon RFS (1956) The elastic constants of anisotropic materials II. Adv Phys 5(19):323–382
5. Hong S, Woo J, Shin H, Jeon J, Pak Y, Colla E, Setter N, Kim E, No K (2006) Principle of ferroelectric domain imaging using atomic force microscope. J Appl Phys 89(2):1377–1386
6. Lang SB (1999) History of pyroelectricity: from ancient greece to space missions. Ferroelectrics 230(1):401
7. Leedom D, Krimholtz R, Matthaei G (1971) Equivalent Circuits for Transducers Having Arbitrary Even-Or Odd-Symmetry Piezoelectric Excitation. IEEE Trans Son Ultrason 18(3):128–141
8. Park S, Shrout T (1997) Ultrahigh strain and piezoelectric behavior in relaxor based ferroelectric single crystals. J Appl Phys 82:1804
9. Setter N, Damjanovic D, Eng L, Fox G, Gevorgian S, Hong S, Kingon A, Kohlstedt H, Park N, Stephenson G et al (2006) Ferroelectric thin films: Review of materials, properties, and applications. J Appl Phys 100(5):51606–51606
10. Shimomura K, Tsurumi T, Ohba Y, Daimon M (1991) Preparation of lead zirconate titanate thin film by hydrothermal method. Jpn J Appl Phys 30(9B):2174–2177
11. Smits J (1976) Iterative Method for Accurate Determination of the Real and Imaginary Parts of the Materials Coefficients of Piezoelectric Ceramics. IEEE Trans Son Ultrason 23(6):393–401
12. Takao H, Tani T, Nonoyama T, Takatori K, Homma T, Nagaya T, Nakamura M (2004) Lead-free piezoceramics. Nature 432:84–87
13. Tiersten HF (1967) Hamilton's principle for linear piezoelectric media. Proc IEEE 55(8):1523–1524
14. Warner AW, Berlincourt D, Meitzler AH, Tiersten HF, Coquin GA, Welsh IFS (1988) IEEE standard on piezoelectricity (ANSI/IEEE standard 176-1987). Technical report, The Institute of Electrical and Electronics Engineers, Inc.

Piezoelectric Microdispenser

JAMES FRIEND, LESLIE YEO
james.friend@eng.monash.edu.au,
leslie.yeo@eng.monash.edu.au

Synonyms

Piezoelectric ink jet; Piezoelectric drop-on-demand; Droplet generator; Piezoelectric micro/nanoliter droplet dispenser

Definition

A fluid-filled chamber that has one or more exit orifices (nozzles) through which the fluid is driven by piezoelectric material causing either a rapid increase in pressure within the fluid or an acceleration of the orifice with respect to the fluid body. Additional fluid is provided through an inlet orifice by external pressure or through a suction mechanism designed into the microdispenser. The fluid, once forced through the nozzles, forms one or more droplets through an instability mechanism – main and perhaps ►satellite droplets – that propagate away from the nozzle, usually at a speed several times the diameter of the droplet per second at speeds up to 10 m/s. The droplets characteristically have a diameter of the same order as the nozzle diameter, usually 1 to 100 μm, and have a volume of several picoliters to nanoliters as they form over a period of about 100 μs. To deliver the fluidic pressure wave required to form the droplets, a pulse or tailored electric drive signal must be provided to the piezoelectric material at a voltage of 5 to 200 V.

Overview

The ►piezoelectric microdispenser, closely related to ►piezoelectric ink-jet printing, a specific application of the microdispenser traditionally for consumer printing, encompasses three separate operating schemes depending on the intended application. A single ►droplet on demand may be delivered by a dispenser through either impulse excitation of the piezoelectric element or continuous vibration of the nozzle with short-term contact onto an application surface. Continuous droplet generation may be obtained through formation of a long-term Rayleigh instability of the fluid surface at the nozzle. ►Fluid jetting is another method to form fibers or droplets, the latter through subsequent breakup of the jet after it has left the microdispenser's exit nozzle due to Rayleigh or Kelvin–Hemholtz instabilities. Another less common method, ►free-surface atomization, makes use of sessile droplets or relatively large fluid volumes placed on the surface of an ultrasonically vibrating structure which induces breakup through an as-yet poorly understood combination of Rayleigh instability and ►cavitation mechanisms.

Piezoelectric microdispensers have existed since the 1950's, though their use increased dramatically with a need for inexpensive printing from the early 1980's, an application shared with thermoelectric (bubble) microdispensers. Generally, piezoelectric microdispensers offer superior flexibility, simplicity, and scalability compared to other known droplet-forming technologies. However, the use of piezoelectric materials causes problems, particularly in the use of lead zirconate titanate (PZT) and its higher-performance doped variants, which are not generally compatible with standard micromachining processes. As a consequence, scaling down dispensers that make use of PZT is difficult. Though other piezoelectric materials have been used over the years, including quartz, aluminum nitride, and zinc oxide, PZT is favored for its large ►electromechanical coupling and relatively large ►piezoelectric strain coefficients. The generation of a sufficient electric field in the piezoelectric materials, particularly for pulsed drop-on-demand dispensers, can require high voltages not directly compatible with integrated-circuit voltages (5 or 12 V). The placement, diameter, and configuration of the inlet and outlet orifices is critical to obtain suitable droplet formation from input strain pulses along the boundary of the fluid chamber, and microdispenser design is a challenge met through a combination of approximate analytical methods, computational modeling, and experimental development, using many versions of a design to discover the one most suitable for the application. Over the years, different operating schemes have been considered for piezoelectric microdispensers, and current technology [1] is essentially a refinement of the spectrum of configurations available over 25 years ago [2].

Regardless, a majority of the systems operate through direct squeezing of the fluid volume present within the dispenser, and as a consequence the volume of fluid ejected from the dispenser at the nozzle is a linear function of the applied voltage, that is, once the stability of the fluid ►meniscus present across the nozzle is overcome. This is in contrast to the generation of jets and droplets via ►acoustic streaming, which would result in an ejected fluid volume proportional to the square of the applied voltage. Applying low voltage signals to the piezoelectric element will result in a deformation of the meniscus, and as the applied voltage is increased, the deformation grows until the meniscus becomes unstable.

If the capillary wavelength is approximately the same size or larger than the nozzle diameter, the formed droplet diameter will be related to the nozzle diameter, and will increase with an increase in the applied voltage. At a certain threshold voltage, more than one droplet will form from the extension and breakaway of the meniscus. Typically, each of the extra droplets – a ►satellite drop – is smaller in size than the primary droplet, but as the voltage continues to increase, these droplets tend to increase in number and volume. There may be yet another transi-



Piezoelectric Microdispenser, Figure 1 Equivalent circuit modeling of (**a**) planar, thickness-polarized, thickness-vibrating piezoelectric transducers using (**b**) a simple lumped-element Van Dyke model and (**c**) a more complex transmission-line model. A model of a piezoelectric microdispenser (**d**) may be formed by connecting the output terminals to the equivalent circuit model of the remaining components (**e**)

tion to chaotic droplet and stream generation as the voltage continues to increase, and cavitation within the chamber or at the nozzle may also occur.

However, if the capillary wavelength is much less than the diameter of the nozzle, the droplet diameter will instead be related to the capillary wavelength: the droplets form from crest instabilities on the free surface of the fluid. The droplet dimensions for this arrangement follow similar trends as the voltage is increased. Using this technique, it is possible to generate droplets less than 1 μm in diameter through the use of frequencies beyond 10 MHz generated from ►surface acoustic wave devices.

This review considers the variety of device designs for piezoelectric microdispensers, methods to model their overall behavior, in addition to the characteristics of atomization mechanisms available for dispensing droplets using piezoelectric materials.

Basic Methodology

Device modeling

Equivalent circuit models have been used to represent piezoelectric material behavior for many years, but are not without limitations. The most common representation for a piezoelectric material, as recommended by the IRE/IEEE standards on piezoelectricity, is the Van Dyke model as described in detail in ►piezoelectric materials in microfluidics, with a capacitor, resistor, and inductor in series representing a single resonance, or motional component of the piezoelectric element, all set in parallel with a second capacitor, representing the ►shunt capacitance. Additional resonances may be included by placing additional capacitor-resistor-inductor sets in parallel, but therein lies some of the limitations of equivalent circuit modeling: accurate determination of the equivalent circuit components requires either a physical prototype or an accurate computational model to provide the data. Further, assuming the loss mechanisms are isolated to a single resistance in the motional component per resonance may lead to error in predicting both the system response and the resonance frequencies. Computational models using finite-element analysis or the like require similar physical data, and so a physical prototype becomes absolutely necessary in the prediction of microdispenser behavior.

Additional matters to consider in using piezoelectric materials that require a physical prototype include the aging of the piezoelectric material and the temperature change during operation. Over time, the resonance frequency and static capacitance will change in an exponential fashion; most of the aging will occur in the first two months, but the subsequent aging can be important in circuit and resonant chamber design. As an electric field is applied to a piezoelectric element, the element will heat due to electromechanical losses in the material. The heating can be significant for soft piezoelectric materials, and can affect the resonance frequencies and capacitance for both hard and soft piezoelectric media.

Equivalent circuit modeling is a useful and commonly applied analysis approach for designing piezoelectric microdispenser systems. The method has limited accuracy, and the ►lumped analysis approach requires the wavelength of the input signal to be larger than any characteristic length within the device. In a microdispenser with an internal cavity, for example, the ►Hemholtz resonance of the orifice, nozzle, and cavity structure should be far higher than the frequency of excitation of the device used to perform the dispensing. The time required to transmit a change in the applied electric field on the piezoelectric element to a change in the meniscus shape at the nozzle is therefore negligible. Using ►transmission-line models of the piezoelectric element, fluid chamber, and other components in the microdispenser permit analysis without the wavelength limitation [3], and provide the ability to analyze the approximate interaction between multiple resonances in the complete system.

In this situation the coupling coefficient of the piezoelectric material is especially important. Though there are many specific forms of the coupling coefficient, an effective coupling coefficient may be used for a transducer operating near a particular resonance;

$$k_{\mathrm{eff}} = \sqrt{\frac{\text{mechanical energy stored}}{\text{electrical energy input}}} = \sqrt{1 - \frac{f_{\mathrm{r}}^2}{f_{\mathrm{a}}^2}}$$

where f_{r} is the resonance frequency and f_{a} is the antiresonance frequency (►resonance and antiresonance frequency) associated with the vibration mode that dominates the motion induced by the applied voltage signal, if one such mode can be assumed to exist. The mechanical energy stored in the piezoelectric device may then be used to perform work on the fluid meniscus, and in this way the amount of energy applied to form a droplet for a microdispenser as a fraction of the input electrical energy may be estimated once one knows the resonance and antiresonance frequencies. The resonance and antiresonance frequencies are typically near the frequencies of minimum and maximum impedance, respectively, for a specific resonance.

Choosing a thickness-polarized, thickness-vibrating piezoelectric element as an example, we can define the applied voltage V, current i, dimensions b, h, and l, and the output force and velocity F and $\dot{u}$; the cross-sectional area bounded by b and l can be defined by A; here it is assumed this area is electroded on the top and bottom faces of the element and that b and l are much greater than h. Treating it as a collection of discrete circuit elements as shown in Fig. 1b, the Van Dyke circuit, allows the analysis of one resonance within the isolated element. Most piezoelectric materials are capacitive insulators, and the ►shunt capacitance $C_{\mathrm{S}} = bl/\beta_{33}^{S}h$ is the constant capacitance present across the element. The additional branch in the circuit represents the specific resonance being analyzed, the motional branch with inductance L, resistance R, and capacitance C. Many impedance analyzers provide this circuit as a means to model the electrical behavior of the piezoelectric element. The coupling coefficient for this specific arrangement is $k_{\mathrm{T}} = \sqrt{h_{33}^{S}\varepsilon_{33}^{S}/c_{33}^{S}}$. Unfortunately, the model only accounts for one resonance and provides no information on the output force F and velocity $\dot{u}$. By treating the element as a transmission-line impedance Z_{P} as shown in Fig. 1c, one can incorporate an arbitrary number of resonances, where $C_{\mathrm{M}} = -h_{33}^{S}bl/\beta_{33}^{S}h$ and $Z_{\mathrm{P}} = \frac{k}{j\omega}\frac{\omega h/c}{\tan(\omega h/c)}$ where $c = \sqrt{c_{33}^{D}/\rho}$ is the longitudinal wave velocity for an open-circuit element. The resonances appear when $(\tan \omega h/c)$ goes to infinity. The quantities h_{33}, β_{33}, e_{33}, and c_{33} represent the piezoelectric field to strain coupling, permittivity, inverse permittivity, and material stiffness along the thickness direction in this model. The S superscript on these quantities represents constant strain (clamped) values, and the D represents constant electric field displacement (open-circuit) values. By connecting the output of the piezoelectric element, or port, to a microfluidics structure (see Fig. 1d) with nozzle, chamber, inlet and compliant structure, a microdispenser can be formed. A simple representation of this situation can be modeled as a collection of RLC resistance-induction-capacitance branches in Fig. 1e connected to the output of the piezoelectric element represented by the open terminals on the right in Fig. 1c. Note the inclusion of RLC sets for the device, inlet, device, and nozzle, each treating a specific resonance of the component. Transmission-line impedances could be used for these components as well to handle multiple resonances. There is an additional capacitor for the meniscus to take into account the formation of capillary waves; the charging of the capacitor is tied to the appearance of the capillary waves and can suggest whether a droplet will be formed as a consequence of an input signal V. The values of the resistance, inductance and capacitance may be related back to the dimensions and configuration of the microdispenser as shown by Berger and Recktenwald [3].

Generation

Modeling of piezoelectric microdispensers provides useful information on the potential for further optimization and insights into the operating mechanism underlying their behavior. However, the reliable formation of stable, monodisperse droplets from a device generally requires a tedious process of trial-and-error design of the driving scheme, fluid, nozzle, chamber, and inlet. Many factors affect the behavior of microdispensers, only a few of which can be incorporated into a mathematical model of the overall device at present. Most of the difficulty is associated with the behavior of the fluid at the exit nozzle. Generally, if the fluid to be dispensed has a low viscosity of about 1 – 50 cS, is slightly hydrophobic, and does not contain particles greater than 10% of the diameter of the nozzle, droplet generation becomes a function of the design of the microdispenser alone [4].

The generation of droplets can be divided into three schemes depending on the form of the fluid leaving the orifice. Individual droplets may be formed on demand through discrete signals applied to the microdispenser, droplets may be formed continuously, with a short transition to and from steady droplet formation upon the application and removal of the driving signal from the microdispenser, or jets of fluid can be generated from a microdispenser, which may later break up into droplets as the jet interacts with the environment. A comparison of a characteristic length of the fluid leaving the microdispenser with the nozzle meniscus size provides another way to categorize the generation mechanism of a device. If the characteristic length – droplet diameter, for example – and the meniscus diameter are similar, the characteristic length is typically controlled by the meniscus size. If, however, the characteristic length is significantly smaller than the meniscus size, the characteristic length is controlled instead by the instability mechanism that generated it.

Droplets from Nozzles

Piezoelectric microdispensers that generate droplets of a size defined by the nozzle diameter function either through the interaction of a pressure wave induced in the fluid with the meniscus located at the nozzle, or a rapid acceleration of the meniscus. Either way, a column of fluid is pushed from the nozzle into the surrounding atmosphere. If the column reaches a sufficient length before being drawn back into the nozzle after passage of the pressure wave (πd_{noz} as predicted by Rayleigh [5], where d_{noz} is the nozzle diameter), the free surface will become unstable and pinch off, forming at least one droplet; the droplet diameter he predicted as a consequence of this process, $d_{\mathrm{Rayleigh}} = 1.89 d_{\mathrm{noz}}$, represents an upper bound for the actual droplet diameter. This instability mechanism is not the free-surface Rayleigh instability as commonly understood and described later.

Lee and Lal [6] summarize the work of Lord Rayleigh, Weber, Sterling and many others quite well, and consultation of references in their work provides an introduction to the literature. Rayleigh's result represents the upper bound since it ignores the drag on the column and droplet from the surrounding atmosphere, and subsequent research considered these factors in the analysis. Through the inclusion of a drag model, the droplet size prediction can be made to be more accurate. Consider the column of fluid pushed from the nozzle, and treat the velocity of the column as U, the fluid's density, surface tension, and dynamic viscosity as ρ, σ, and μ, respectively, and the ambient atmosphere's density as $\hat{\rho}$. The ▶ Weber number of the ambient atmosphere and ▶ Ohnesorge number of the fluid may then be defined as

$$\hat{\mathrm{We}} = \frac{\hat{\rho} U^2 d_{\mathrm{noz}}}{\sigma} \tag{1}$$

$$\text{and } \mathrm{Z} = \frac{\mu}{\sqrt{\rho \sigma d_{\mathrm{noz}}}} \,. \tag{2}$$

Typically, the Weber and Ohnesorge numbers are dimensionless measures of the relative strength of the inertia to the surface tension in a fluid, and the viscosity to the surface tension of a fluid, respectively. Here the Weber number is modified (with a hat, $\hat{\mathrm{We}}$) to consider the inertia of the surrounding atmosphere in comparison to the surface tension of the fluid extending from the nozzle.

As the fluid column extends from the nozzle, the instability of the free surface is exhibited across several length scales, represented by a collection of solutions of Sterling's equation of motion describing the instability. One of these solutions grows in amplitude more rapidly than the others, which caused Sterling to assume that it would come to dominate the droplet formation process. The selected solution describes the maximum column length that can be obtained without actually causing sufficient surface instability to form a droplet. It further describes the diameter of the droplet formed as a consequence of the instability once the fluid column surpasses that maximum length. The wavelength of the instability as it forms a droplet may be written as $\lambda = \pi d_{\mathrm{noz}} \hat{\vartheta}$, where

$$\hat{\vartheta} = \sqrt{2(1+3\mathrm{Z})}\, \mathrm{e}^{-0.035 \hat{\mathrm{We}}} \tag{3}$$

represents the reciprocal non-dimensional wavenumber of the most rapidly growing disturbance. For water being ejected from a 10 μm diameter nozzle at $U = 1$ m/s, the modified Weber number is $\hat{\mathrm{We}} = 1.81 \times 10^{-4}$, the Ohnesorge number is $\mathrm{Z} = 0.0373$, and so $\hat{\vartheta} = 1.49$ and the wavelength of the instability is $\lambda = 46.9$ μm. The diameter of the droplet may be taken as one-half the instability wavelength, $d = 23.4$ μm, because one-half of the wavelength forms the droplet while the other half forms the neck region that separates the droplet from the remaining portion of the fluid column. The fluid's density, surface tension, and dynamic viscosity were treated as $\rho = 1002\,\mathrm{kg/m^3}$, $\sigma = 0.072$ N/m, and $\mu = 1.002 \times 10^{-3}\,\mathrm{kg/(m-s)}$, respectively, and the ambient atmosphere's density was set at $\hat{\rho} = 1.3\,\mathrm{kg/m^3}$.

The formation of additional droplets – ▶ satellite droplets – in addition to the desired or primary droplet for each extension of the fluid column induced by an applied pressure wave or acceleration of the nozzle is a troublesome problem with microdispensers. Dong, et al., in a thorough work [7], examined the formation of the primary and satellite droplets and suggested a criteria for avoiding the formation of satellite droplets. As the primary droplet forms from the liquid column extending from the nozzle, a fluid thread may form from the neck. In some cases, this fluid thread may become quite long in comparison to the nozzle diameter, the ratio of which could be defined as $l_{\mathrm{b}}/d_{\mathrm{noz}}$. If the fluid thread length is larger than a limiting value l_{b}^{*}, the thread will break up into satellite droplets. There is the possibility that the satellite droplets will merge with the primary droplet if the relative velocities are in the correct direction and large enough to induce recombination.

In any case, the limiting value of the fluid thread length may be written as

$$l_{\mathrm{b}}^{*} = d_{\mathrm{noz}} \left(\frac{(C_2 - C_1)a}{2\alpha_{\mathrm{max}}^{*}} + 1 \right) , \tag{4}$$

where

$$\alpha_{\mathrm{max}}^{*} = \sqrt{\frac{2\vartheta^2 - 2 + 9Z^2}{4\vartheta^4}} \tag{5}$$

is a term related solely to the nozzle and fluid characteristics; $\vartheta = \sqrt{2(1+3Z)}$ here, an approximation similar to Dong, et al., in line with Sterling's analysis given by Eq. (3) with the omission of the Weber-related air drag term. The nondimensional constants C_1 and C_2 are related to the pinch-off time of the liquid thread from the nozzle and primary droplet, respectively, while a represents another nondimensional constant that relates the speed of the wave disturbance along the periphery of the fluid column to the speed of the retreating fluid column back towards the nozzle after the formation of the droplet and fluid thread stretching between the column and droplet. Dong, et al., claim the product $(C_2 - C_1)a$ is between 0.9 and 1.1 for their experiments with water and glycerin compounds ejected into air. For the water/air system considered in this section, the limiting fluid thread length is $l_{\mathrm{b}}^{*} = 22.8\ \mu\mathrm{m}$ if $(C_2 - C_1)a$ is 0.9. Experimental visualization would be necessary to determine the actual fluid thread length. Dong, et al., suggest that the most effective method to eliminate satellite droplet formation is an increase in the fluid viscosity which would increase the Ohnesorge number and reduce $\alpha_{\mathrm{max}}^{*}$.

Most piezoelectric microdispensers use the single-droplet nozzle ejection mechanism to form droplets. Through careful design, droplets may be rapidly ejected one after another from the meniscus at frequencies of up to 10 kHz, though there are limitations from refill speed, cavitation, bubble ingestion from the nozzle into the fluid chamber, and satellite droplet formation. Generally the piezoelectric material is not a limitation in droplet delivery speed unless soft PZT is used, which has a larger electromechanical transduction loss and is susceptible to heating at operating frequencies above 1 kHz.

Jetting from nozzles in piezoelectric microdispensers is also possible, usually through a combination of constant applied pressure on the fluid with a lesser modulation of the pressure using the piezoelectric element. The modulation introduces an instability in the jet traveling out of the orifice which is amplified to cause the breakup of the jet into droplets through the interaction of the jet with the ambient environment; this instability mechanism is known as the ▶ Kelvin–Helmholtz instability and requires the jet to be moving at several meters per second in air to cause droplet formation [8]. Secondary breakup of the droplets into finer droplets may then occur via the Rayleigh–Taylor mechanism described later, though the conditions under which this can happen do not typically occur on the scales of most piezoelectric microdispensers.

Droplets from Free Surfaces

It is also possible to dispense microdroplets from free surfaces, either formed on a sessile droplet or along the meniscus formed at a nozzle. In the latter case, the critical difference with the previous section is that the primary droplet formed from the nozzle is much smaller than the diameter of the nozzle, eliminating the direct influence of the nozzle's size on the size of the droplet. The study of the formation of droplets from free surfaces has a long and controversial history, which has been suggested to be due to either capillary wave breakup, cavitation, cavitation-induced capillary waves which subsequently break up to form droplets, or even cavitation-screened capillary wave breakup, where a cavitation layer beneath the surface acts to suppress atomization. It is likely that over the wide range of operating frequencies and configurations available each of these physical mechanisms is possible, but for microdispensing fluids, capillary wave breakup appears to be the most likely mechanism [9]. Even so, the complexity of the analysis and nonlinear behavior [10] should not be underestimated in considering the use of free surfaces.

In 1950 Taylor studied the formation of sinusoidal waves on the free surface of a fluid in air undergoing acceleration perpendicular to the free surface and in the direction of the force of gravity, and almost a century prior Rayleigh considered the formation of similar waves if the denser fluid was placed above the free surface; both illustrate a similar mechanism that has come to be described by the Rayleigh–Taylor instability. Curiously, the instability will appear between the interfaces of other phases of media, including even solid-solid interfaces, and the form of the equations that describe the instability will remain essentially the same [11]. The formation of droplets from capillary waves may be described by the Rayleigh–Taylor instability.

Loosely following Piriz, et al. [11], if $\xi = \xi(x,t)$ represents the transverse displacement of the inviscid fluid surface where x is the position coordinate along the fluid interface[1], $\ddot{\xi} = A_T \kappa g \xi$ is the equation of motion of the surface if we ignore surface tension and let the ▶Atwood number be $A_T = \rho_2 - \rho_1/\rho_2 + \rho_1$, $\rho_2 > \rho_1$, where ρ_2 is the density of the fluid above the interface, and g and κ be the gravitational acceleration ($9.8065\,\mathrm{m/s^2}$) and the perturbation wave number, respectively. This can be integrated to give the exponential growth of the interface amplitude at a rate of $\sqrt{A_T \kappa g}$. The wavenumber is related here to the frequency of the applied oscillation through $\kappa = f/c$, where f is the frequency of the applied oscillation and c is the bulk sound speed within the fluid carrying the acoustic energy to the interface. If we place the dense fluid beneath the interface so that now ρ_2 is the density of the fluid below the interface, and incorporate surface tension, dynamic viscosity, and the acceleration of the fluid interface $\ddot{\psi}(t)$ in the direction of the gravity force g, the equation of the transverse displacement of the surface $\xi(t)$ becomes

$$\ddot{\xi} + \left[A_T \kappa \left(g - \ddot{\psi}(t)\right) + \sigma/\rho_1\right] \xi + 2\frac{\mu_1 + \mu_2}{\rho_1 + \rho_2} \rho_2 \kappa^2 \dot{\xi} = 0 . \tag{6}$$

Lamb recognized in 1932 that the surface tension acts to stabilize disturbances with wavenumbers greater than the cutoff value of

$$\kappa_C = \sqrt{\frac{g(\rho_1 + \rho_2)}{\sigma}} .$$

Above this value, oscillations induced on the free surface are stable, while below this value, it is possible to induce instability on the surface and form droplets. Viscosity cannot prevent the instability, but it does increase the acceleration $\ddot{\psi}(t)$ necessary to cause the instability to appear. In the equation of motion (6), acceleration due to gravity, g, also acts to stabilize the interface. There are different ways to destabilize the surface, the simplest of which is to $\ddot{\psi}(t)$ to a constant value above $g + \sigma/(\rho_1 A_T \kappa)$, forming a gravity wave. Other ways include harmonic excitation with $\ddot{\psi}(t) = \Psi\, e^{i 2\pi F t}$ where $i = \sqrt{-1}$, Ψ is the amplitude, and F is the frequency of excitation. Lang [9] found the diameter of the droplets formed from the free surface closely follows Kelvin's equation for the capillary wavelength,

$$\lambda = \sqrt[3]{\frac{2\pi\sigma}{\rho f^2}} , \tag{7}$$

where f represents the frequency of the most easily excited capillary waves on the free surface. Based on experimental results, it has been shown that the frequency of the capillary waves is one-half the excitation frequency F if it is assumed to be harmonic, and Lang showed that the droplet diameter is 0.34 times the capillary wavelength based on experimental results across a wide range of frequencies:

$$d = 0.34 \sqrt[3]{\frac{8\pi\sigma}{\rho f^2}} .$$

Similar to the droplet breakup model in the previous section, many different vibration modes may be excited on the surface by the acceleration $\ddot{\psi}(t)$, but the one represented by λ in equation is assumed to dominate in the generation of droplets. This assumption is valid at powers just sufficient to cause the generation of droplets, but as the amplitude Ψ is further increased, other modes may become large enough to form droplets, increasing the droplet size distribution and the complexity of analysis.

Impulsive excitation may also be used to form droplets from a free surface in this way. Continuous wave excitation can provide very monodisperse distributions of droplets with diameters much less than the characteristic size of the free surface [12], but impulsive excitation has also been used with success in commercial applications by Xerox [4]. A critical part of their success has been in finding ways to form a single droplet from the surface per excitation pulse; typical free surface droplet generators form n droplets where $n = (1/2)\pi(d_{\mathrm{surf}}/\lambda)^2$, d_{surf} is the diameter of the free surface, and λ is the capillary wavelength. Impulsive excitation has the advantage of offering droplet-on-demand operation at the expense of requiring thorough analysis of the free surface to ensure reliable formation of individual droplets.

Jetting from the free surface may also be obtained, and droplets could be formed from these jets through secondary breakup mechanisms if the Ohsenorge number is less than about 0.1 and the Weber number is above 5. The conditions necessary to obtain free-surface jetting from piezoelectric microdispensers are fairly challenging; even though there are examples of high-frequency free-surface

---

[1] A 2-D assumption is implicit here, as it is throughout most literature on instability calculations.



Piezoelectric Microdispenser, Figure 2 The capillary tube microdispenser, viewed from the side (**a**) and top (**b**), with a variation (**c**) by Lee and Lal [6]. Though almost unrecognizable after years of refinement and adoption of a parallel layout scheme, the Konica-Minolta device (**d**) is also a capillary tube microdispenser

jetting [13], they at present remain little more than curiosities.

Droplet Motion After Ejection

Once formed, most piezoelectrically-dispensed droplets have a drag force proportional to their velocity. In contrast to the viscous drag force on macroscopic objects,

$$F_{\text{Viscous Drag}} = \tfrac{1}{2}\rho C_{\text{d}} A v^2 \,, \tag{8}$$

which scales with the square of the velocity of the object relative to the surrounding fluid, the drag force due to Stokes' law scales linearly with velocity:

$$F_{\text{Stokes}} = 6\pi\eta r v\,; \tag{9}$$

$r, v, A, C_{\text{d}}, \rho$, and η are the drop's radius, velocity, and cross-sectional area, the coefficient of drag, and the surrounding fluid's density and viscosity, respectively. The viscous drag scales inversely to the square of the diameter of the droplet, and so is negligible in air for droplets less than about 25 µm in diameter. The most common figure of merit used in choosing the appropriate drag force is the ► Reynolds number.

For droplets in air less than about 5 µm in diameter, the actual drag force is even lower, since the surrounding air is not a continuum at these scales. Millikan's resistance factor (or ► Cunningham's correction) multiplies the terms on the right-hand side of equation (9) to form the corrected drag force

$$F'_{\text{Stokes}} = 6\pi\eta r v\left[1 + \left(\frac{0.130\,\mu\text{m}}{d}\right) \times \left(1.252 + 0.399\,\text{e}^{-1.100d/0.130\mu\text{m}}\right)\right] \tag{10}$$

A 10 µm diameter droplet moving at 1 m/s in air would have 14.1 pN, 1.72 nN, and 2.00 nN of force on it from viscous drag, uncorrected Stokes' drag, and Cunningham-corrected Stokes' drag, respectively. More importantly, the deceleration of a 10 µm diameter water droplet moving at 1 m/s would be 3820 m/s^2 due to the Cunningham-corrected Stokes drag calculated from

$$\dot{v} = \text{F}'_{\text{Stokes}} \Big/ \left(\frac{\pi}{6}\rho d^3\right) \tag{11}$$

where the term in parentheses is the droplet mass. The deceleration decreases rapidly as the droplet slows; the velocity is an exponential function of time. Under gravity, the terminal velocity can be found by setting the drag force equal to the force of gravity, though this is far less than the ejection velocities for most dispenser systems; for example, a 10 µm droplet has a terminal velocity of only 3 mm/s.

In addition to the correction on the drag force from the noncontiguous surrounding fluid, there is also an randomizing effect on the droplets' motion due to the interaction with the environment: ► Brownian motion. This motion can cause error in droplet placement or



Piezoelectric Microdispenser, Figure 3 The side-shooter design as conceived by Kyser and his associates at Silonics in the 1970's (**a**), and a modern version by Brother (**b**) using planar micromachining technology. Note the dramatic increase in nozzles and the more detailed cross-sectional design. The chamber cross-section in the Kyser design is rectangular

agglomeration of droplets in continuous droplet formation or atomization systems. The mean displacement of a droplet, δ, due to Brownian interaction over time t is a function of the temperature T, ►Boltzmann's constant $k = 1.38065 \times 10^{-23}$ J/K, and drag force, F_{Drag}, which is a choice between Eqs. (8) through (10) suited to the diameter of the droplet under consideration,

$$\delta = \sqrt{\frac{2kTt}{F_{\mathrm{Drag}}}}\,. \tag{12}$$

For a 5 μm droplet, the average displacement after one second at 20 °C is about 2.66 μm, over half the droplet's radius, using Eq. (10) for the drag force.

Key Research Findings

The devices resulting from the combination of piezoelectric materials and fluidic microstructures to provide dispensing of small amounts of liquid fall into several distinct categories based on their construction. Most common of these is the capillary tube drop-on-demand system, shown in Fig. 2, first developed by Zoltan at Clevite in the early 1970's, and commonly called the Gould or Bogy device. Many variations on this design exist due to the simplicity of the configuration and ease in forming the micropipette tips from which droplets may be dispensed; one can even manufacture their own capillary tube microdispenser for very little cost [4]. Fig. 2a illustrates the typical form of this device, though there have been many variations in the shape of the piezoelectric element used, as shown with the top views in Fig. 2b and c; the latter from Lee and Lal [6], and an interesting variation (see Fig. 2d) from Percin and Khuri-Yakub [14]. Through mass production and microfabrication techniques, the concept has been refined to the form shown in Fig. 2e by Konica-Minolta [15]. The device functions either by squeezing the fluid or accelerating the meniscus through actuation of the piezoelectric material; in most devices both mechanisms are in part responsible for the ejection of droplets. Note even in the Konica-Minolta device the piezoelectric material is a simple shape that may be constructed from machining bulk pieces of PZT. Another design that has been used for microdispensers is the so-called side-shooter design originally developed by Kyser and others in the late 1970's, as illustrated in Fig. 3 in its original configuration, and a modern configuration by Brother making use of planar micromachining technology. A relatively unique version of droplet generation from a free surface is focused acoustic beam ejection by Elrod, et al., at Xerox PARC in the early 1990's [4] illustrated in Fig. 4; it represents a refined version yet lower-frequency ver-



Piezoelectric Microdispenser, Figure 4 Focused acoustic beam ejection technology by Elrod and associates at Xerox PARC. Using a piezoelectric element with electrodes immersed in a thin layer of fluid below a nozzle (**a**), an electrical impulse will induce an acoustic wave that, when interacting with the meniscus, forms a capillary wave that ejects a single droplet (**b**). The form of the electrode (**c**) and the driving signal are two of the features of the design that must be carefully designed

sion of the surface acoustic wave atomizer by Shiokawa et al. [13].

Future Directions for Research

Recently, many new piezoelectric materials have appeared as a consequence of the ability to observe and tailor crystal, polycrystalline, and polymer structures on the nanoscale. Indeed the evolution of high-performance piezoelectric materials like PMN-PT, polypyrrole, IPMC, and other electroactive polymers promise to usher in a new generation of materials that offer advantages over PZT for dispensing applications. Meanwhile, compatibility problems in the fabrication of silicon, PZT, and other standard micromachining materials are being solved, offering the ability to apply PZT in ways not currently possible.

In analysis, most microdispensing work assumes the working fluid is Newtonian, while many fluids that are useful for dispensing in the printing, biomedical and microfabrication industries are strongly non-Newtonian. A return to the fundamentals is in order to revisit the use of these fluids in forming droplets. Improved computational algorithms capable of dealing with the free surfaces and multiple physical phenomena of piezoelectric media, structural deformation, and nonlinear acoustic wave propagation will be central to this effort. As the excitation frequencies and power per unit volume are increased, the incorporation of cavitation models will also be beneficial.

Cross References

- ► Acoustic Streaming
- ► Biosample Preparation Lab-on-a-Chip Devices
- ► Cavitation in Microdomains
- ► Control of Microfluidics
- ► Droplet Based Lab-on-Chip Devices
- ► Droplet Dispensing
- ► Membrane Actuation for Micropumps
- ► Microactuators
- ► Microneedles – Applications & Devices
- ► Supersonic Micro-Nozzles
- ► Piezo/PZT in Microfluidics
- ► Ultrasonic Pumps

References

1. Burgold J et al (2005) Evolution and operating experiences with different drop-on-demand systems. Macromol Rapid Commun 26(4):265–280
2. Wehl WR (1989) Ink-jet printing: the present state of the art. CompEuro'89, VLSI and Computer Peripherals. VLSI and Microelectronic Applications in Intelligent Peripherals and their Interconnection Networks, Proceedings 2, p 2
3. Berger SS, Recktenwald G (2003) Development of an Improved Model for Piezo-Electric Driven Ink Jets. In: NIP19: International Conference on Digital Printing Technologies. The Society for Imaging Science and Technology, New Orleans
4. Lee ER (2003) Microdrop Generation. In: Lyshevski SE (ed) Nano- and Microscience, Engineering Technology and Medicine Series. CRC Press, New York, p 252
5. Rayleigh L (1878) On the instability of jets. Proc London Math Soc 10:4–13
6. Lee CH, Lal A (2004) Single microdroplet ejection using an ultrasonic longitudinal mode with a PZT/tapered glass capillary. Ultrasonics, Ferroelectrics and Frequency Control, IEEE Trans 51(11):1514–1522
7. Dong H, Carr WW, Morris JF (2006) An experimental study of drop-on-demand drop formation. Phys Fluids 18(7):072102

8. Tanner FX (2004) Development and Validation of a Cascade Atomization and Drop Breakup Model for High-Velocity Dense Sprays. Atomization Sprays 14(3):211–242
9. Lang RJ (1962) Ultrasonic Atomization of Liquids. J Acoust Soc Am 34:6
10. Shi WT, Goodridge CL, Lathrop DP (1997) Beraking waves: bifurcations leading to a singular wave state. Phys Rev E 56(4):4157–4161
11. Piriz AR et al (2005) Rayleigh-Taylor instability in elastic solids. Phys Rev E 72(056313):1–10
12. Forde G, Friend J, Williamson T (2006) Straightforward biodegradable nanoparticle generation through megahertz-order ultrasonic atomization. Appl Phys Lett 89:064105
13. Shiokawa S et al (1989) Liquid streaming and droplet formation caused by leaky Rayleigh waves. In: IEEE Ultrasonics Symposium. IEEE, Montreal
14. Percin G, Khuri-Yakub BT (2003) Piezoelectric droplet ejector for ink-jet printing of fluids and solid particles. Rev Sci Instrum 74(2):1120–1127
15. Okuno T (2006) Inkjet Print Head and Manufacturing Method Thereof, U.S.P. Office. 2006, Konica Minolta Holdings, Ltd.: United States, US2006/0017778, p 21

Piezoelectric Micro/Nanoliter Droplet Dispenser

► Piezoelectric Microdispenser

Piezoelectric Pumps

► Piezoelectric Valves

Piezoelectric Valves

JAMES FRIEND, LESLIE YEO
MicroNanophysics Research Laboratory, Monash University, Clayton, VIC, Australia
james.friend@eng.monash.edu.au,
leslie.yeo@eng.monash.edu.au

Synonyms

Microvalve; Piezoelectric pumps; No-moving-part valves

Definition

Structures that regulate the flow of fluids using piezoelectric materials, either composed of active regulation through deflection of a structure to block or allow passage of the fluid using electrically-driven piezoelectric elements, or as a piezoelectric pump in combination with mechanical or passive diffuser valves.

Overview

Active piezoelectric valves offer a unique combination of large closing forces – hundreds to thousands of newtons – against fluid loads and small displacements measured in the tens of microns. Such valves may be designed to close or open upon the application of an electric field to the piezoelectric material, and offer flow rates from nearly arbitrarily low amounts to tens of liters per minute for gases, water, and similar fluids [1]. Given the limited strain, 0.1% or less, available from typical high-performance piezoelectric ceramic materials, a majority of the research and development effort has been in amplifying this strain to permit efficient valving action. Flap or cantilever valves seated across an orifice actuated as a piezoelectric ► bimorph or ► unimorph or ball or grooved structures seated against an orifice and moved using a large-displacement ► linear multilayer piezoelectric actuator is typical of this approach.

Passive piezoelectric valves function in an entirely different manner, though they also make use of piezoelectric bimorph or unimorph structures. Forming one side of a small fluid chamber, or ► Helmholtz cavity, the piezoelectric element can excite chamber resonances when driven at appropriate frequencies via an oscillatory electric field, usually from 10 Hz to 100 kHz depending on the device dimensions and fluid. With two or more orifices connecting the chamber to the outside, fluid may be passed into and out of the chamber; by using orifices with different shapes the flow direction may be regulated without requiring a mechanical blockage of the flow [2] or moving parts. Though these configurations are effective as pumps [3], they also can serve as valves for applications where some leakage is tolerable, or where ball or flap valves may be used as passive mechanical restrictions on the orifices to augment the sealing action and improve performance.

Cross References

► Piezoelectric Microdispenser
► Piezoelectric Materials for Microfluidics

References

1. Oh K, Ahn C (2006) A review of microvalves. J Micromech Microeng 16:13–39
2. Izzo I, Accoto D, Menciassi A, Schmitt L, Dario P (2007) Modeling and experimental validation of a piezoelectric micropump with novel no-moving-part valves. Sens Actuators A 133(1):128–140
3. Laser D, Santiago J (2004) A review of micropumps. J Micromech Microeng 14(6):35–64

pL

► Picoliter Flow Calibration

Planar Laser-Induced Fluorescence

► Laser-Induced Fluorescence (LIF)

Plasma Bonding

► Plasma in Microchannel

Plasma Chromatography

► Miniaturized Ion Mobility Spectrometry

Plasma Etching

CHEN-KUEI CHUNG
Department of Mechanical Engineering, National Cheng Kung University, Tainan City, Taiwan (R.O.C.)
ckchung@mail.ncku.edu.tw

Synonyms

Advanced silicon etching (ASE); DRIE (Deep Reactive Ion Etching); High aspect ratio Si etching

Definition

Plasma etching is the removal process of materials performed using a plasma, which involves the physical, chemical and mixed etching mechanisms. Ion-enhanced ►chemical etching, i. e., a reactive radical dominated etching process with ion assistance, is used in microelectronics and MEMS fabrication. ICP (inductively coupled plasma) etching is the etching process using a high-density plasma generated by the inductive coupling of RF power through an antenna, which is widely used in Si micromachining for high aspect ratio and deep microstructure fabrication. DRIE (deep ►reactive ion etching) is another term for ►ICP etching due to the deep or high aspect ratio microstructure fabricated by RIE principles, which is also called high aspect ratio Si etching or Advanced Silicon Etching (ASE™, a trademark for this technology of the company Surface Technology Systems, STS).

Overview

Etching is used in microelectronic processing and MEMS for pattern transfer during fabrication of devices. The pattern transferred is defined using lithographic techniques by UV exposure on a photoresist through a mask. The photoresist material often loses adhesion in solutions during wet etching processes. Therefore, the pattern dimensions can vary and there can be a lack of control of line width. The process also etches laterally at approximately the vertical rate during wet chemical etching downward into the film and loses the etching directionality. So, wet etching in many semiconductor processes has been replaced by plasma-assisted etching [1, 2]. The driving force of plasma-based etching technology in semiconductor manufacturing is primarily due to the achievement of ►etch directionality and the ability for true pattern transfer from lithographically defined photoresist patterns into underlying layers. The isotropy, undercutting and adhesion problems encountered in wet ►chemical etching can be overcome by anisotropic dry plasma etching; other advantages are its cleanliness and compatibility with automation and vacuum processing technologies. Plasma etching is performed using a discharge gas formed by reactive radicals, ions and electrons to create ion sputtering or reactive radical species that react with surfaces with or without ion assistance to form volatile compounds. The physically sputtered or chemically reacted products evaporate from the surface and proceed to etch the film or substrate. When plasma etching is used, adhesion is no longer a major problem, undercutting can be controlled by varying the plasma chemistry and parameters, and directional or anisotropic profiles can thus be achieved.



Plasma Etching, Figure 1 Three types of plasma etching of a film on a substrate under a mask: (**a**) isotropic etching, (**b**) sloped wall via etch and (**c**) vertical wall (anisotropic etching)



Plasma Etching, Figure 2 Four types of reaction mechanism during plasma etching: (**a**) sputter etching, a purely physical process, (**b**) chemical etching, or chemical volatilization, a purely chemical process, (**c**) ion-enhanced energetic, i. e., ion-enhanced chemical, etching, a combination of physical and chemical processes and (**d**) ion-enhanced inhibitor, i. e., inhibitor ion-enhanced chemical, etching, also a combination of physical and chemical processes but that involves an inhibitor that passivates the surfaces that are not exposed to ion bombardment. The last two types (**c**) and (**d**) are related to reactive ion etching (RIE)

The ►etch directionality in plasma etching is due to directed energy input to an etching reaction at a surface and can be accomplished by radical atoms, electrons, photons or ion bombardment of a surface exposed to a chemical etchant. It can be obtained by controlling the interaction between the plasma physical and chemical mechanisms to achieve the required etching profiles using a suitable reactor and adjusting the plasma parameters. Figure 1 shows three types of plasma-etched profiles of films on a substrate under a mask: isotropic etching, sloped wall via etch and vertical wall (anisotropic etching) [2]. Anisotropic etching occurs when it proceeds much faster in one direction as compared to other directions. The directionality, or anisotropy, is defined by the ratio of vertical to lateral etching rate. The degree of isotropic etching, IE, can be defined in Fig. 1a by equation (1) [2]:

$$\mathrm{IE} = \frac{d_\mathrm{l}}{d_\mathrm{v}} = \frac{V_\mathrm{l}}{V_\mathrm{v}} \tag{1}$$

where d_l is the amount of undercutting due to the lateral etching in rate of V_l, and d_v is the amount of the etched thickness of film due to the vertical etching in rate of V_v. So, the degree of anisotropic etching, AE, is correspondingly given by

$$\mathrm{AE} = 1 - \mathrm{IE} = 1 - \frac{V_\mathrm{l}}{V_\mathrm{v}} \tag{2}$$

In addition to isotropic and/or anisotropic behavior, another important etching characteristic is the ►etch selectivity. Etch selectivity between two materials is defined as the ratio between their etching rates at identical plasma conditions. High selectivity is usually preferred in etching and is related to a high etching rate ratio between chemically different materials or between the etched and the underlying layer. In addition, high selectivity is required between the substrate and etching mask or between different substrate materials.

Also, a plasma etching process should satisfy a number of requirements, including [2]:

- high etching anisotropy for the desired etching profile
- high etching selectivity
- high etching rate
- good uniformity of etching across wafer surface
- minimal material damage
- smooth surface without residues after etching.

Since plasma etching is related to the reactant activated by input energy to active radicals, electrons and ions, it occurs through the following steps for physical or chemical processing [2]:

1. Active species are formed in the plasma from nonreactive gases.
2. The active species formed in the plasma adsorb on the surface of the substrate and react with the surface to form volatile products.
3. The volatile products with a high vapor pressure leave the surface at the substrate temperature and are pumped out with the effluents of the plasma.

The reaction during plasma etching can be categorized into four types of mechanism [2, 3] as illustrated in Fig. 2.

(a) ►Sputter etching, a purely physical process caused by surface bombardment with high-energy ions, leading to anisotropic etching; also with poor selectivity, high surface damage, and low etching rates.

(b) ►Chemical etching, or chemical volatilization, caused by neutral species generated in the plasma, which react with the etched layer to form volatile compounds.



Plasma Etching, Figure 3 High aspect ratio silicon trenches with nearly vertical sidewall profile obtained by inductively coupled plasma (ICP) etching: (**a**) SEM micrograph, (**b**) RIE lag and (**c**) aspect ratio dependent etching phenomena

Chemical etching is typically isotropic and is characterized by high etch rates, usually good ▶etch selectivity, and low substrate damage.

(c) Ion-enhanced energetic, i. e., ion-enhanced chemical, etching, a combination of physical and chemical processes in which the chemical reactions at the surface of the processed sample are enhanced by ion bombardment, enabling one to achieve material selective etch anisotropy.

(d) Ion-enhanced inhibitor, i. e., inhibitor ion enhanced, chemical etching, also a combination of physical and chemical processes but that involves an inhibitor that passivates the surfaces that are not exposed to ion bombardment. It is used in the sidewall passivation process for anisotropic etching.

The last two types, types (c) and (d), are related to ▶reactive ion etching (RIE).

Plasma chemical etching is generally performed under low ion bombardment and chemical reactions with plasma species under conditions at which the physical effects are negligible and is usually an isotropic etching process. The pressure used in plasma chemical etching is relatively high, greater than 0.2 torr, often about 1 torr [2, 3]. If a parallel plate reactor is used, the substrates are placed on the ground electrode at a low potential relative to the plasma and the ion bombardment on the substrates is very weak. It is also performed in barrel reactors often with an etch tunnel to limit the discharge to a region outside the substrates. The substrates interact only with plasma species diffusing out of the plasma and are only chemically etched by atoms and radicals. RIE is generally performed in a parallel plate reactor. The substrates are placed on an electrode, which is capacitively coupled to a generator, usually operated 13.56 MHz. The pressure used in RIE is intermediate in the range 0.01 – 0.2 torr. The problem is the increase of ion bombardment damage with increasing substrate bias as high RF power is required for a high etching rate. To solve the surface damage problem in RIE, a high-density low-pressure (HDLP) system has been developed with the substrates placed out of the high density plasma region. The plasma diffuses downstream to the substrates biased at low power for etching. The benefits of HDLP are high etching rate with low damage, high selectivity and good directionality control for high anisotropy. Electron cyclotron resonance (ECR) and ICP are the two popular excitation techniques for generating HDLP plasma. In MEMS, ▶ICP etching is a very powerful tool for the fabrication of deep and high aspect ratio (HAR) Si microstructures. It will be discussed in detail in the following sections. The common applications of plasma/reactive ion etching in Si technology are listed in Table 1.

Many materials, e. g., single/poly-Si, SiN_x, SiO_x, glass, metals, slicides and polymers, can be etched by plasma-assisted etching to get anisotropic profiles by changing the etching chemistry. A large variety of fluorine-, chlorine-, bromine- and oxygen-based etching plasmas with a few gas additives, e. g., H_2, Ar and He, are used in the semiconductor industry as listed in Table 2 [1–3]. A process recipe involving the specific etching gas mixture and operation parameters is generally based on a large amount of empirical evidence obtained for a particular etching application rather than a real fundamental understanding of the relevant plasma chemistry. In practice, etching is performed by selecting a typical etching recipe and adjusting using a certain basic understanding of plasma physics and chemistry for process improvement.

Basic Methodology

Anisotropic etching is desired in the fabrication of numerous devices, especially the high aspect ratio microstructure (HARM) for MEMS applications. Many phenomena become pronounced in HARM etching compared to the low aspect ratio features ($< 3:1$), e. g., ►RIE lag, ►aspect ratio dependent etching (ARDE), bowing (barreling) of sidewalls, faceting, profile shape dependence, mirotrenching and notching (footing). These effects result from several mechanisms as follows [4]:

- angular dispersion of ions and neutrals as etchants due to collisions within the plasma sheath;
- ion and etchant transport within the feature onto the sidewalls;
- depletion of the reactant as microscopic loading under conditions of high probability at the surface;
- charging of feature sidewalls, as local charging of substrate surface or microstructure sidewalls deflects ions and prevents them from reaching the bottom surface to be etched;
- etching yield dependency upon the angle of incidence;
- deposition of material produced in the discharge within the feature; and
- redeposition of material released by ion-induced etching and reaction of the neutrals on the sidewalls to form passivation layers.

In order to obtain HARM with plasma-assisted etching, the significant issue is to reduce the lateral etching rate by controlling the ratio of ion flux to radical flux and sidewall passivation through the precursor gases and process parameters. Ion-assisted reactions at the bottom surface lead to highly anisotropic etching with the assistance of sidewall passivation or reduction of lateral reactive radical reactions. The key factors for controlling the microscopic etch uniformity in HAR etching are the selection of reactant chemistry, process conditions and the transport behavior of reactant to the surface and product away from the surface. Kassing and Rangelow [4] reported two main etching strategies for reducing the adverse effects listed above: controlled formation of sidewall-inhibitor films, and ►reactive ion etching at low substrate temperatures. Also, Laermer and Schilp [5] used alternating etching and passivation steps in the Si etching process, known as Bosch patented technology, which has become the main technique in the fabrication of Si HARM devices. Based on the Bosch technology, Surface Technology Systems (STS) continues promoting the *ASE* process in equipment design and process enhancement [6], which has been widely used in many universities, research institutes and industries. Figures 3a–c show an SEM micrograph, feature-dependent ►RIE lag and ARDE phenomena of HAR Si trenches with nearly vertical sidewall profile, respectively [7]. The structure was obtained using the *ASE* process with an STS Multiplex ICP system. The feature sizes of trenches from the fourth to the ninth trenches from the left side are between 2.2 μm and 5.5 μm. The etch rates measured range from 1.82 μm/min to 2.58 μm/min while the aspect ratios obtained are from 33.1 to 18.7. The larger the trench size, the higher the etching rate, and the lower the aspect ratio.

In the following, the STS Multiplex ICP system and *ASE* process, etching performance and chemistry, end point detection and experiment will be introduced for anisotropic plasma etching.

Plasma Etching, Table 1 Common applications of plasma/►reactive ion etching in silicon technology

Application	Etch step
Device formation	Polysilicon/polycide gate; sidewall; storage node; emitter contact
Isolation	Deep trench; shallow trench or recessed oxide
Interconnection	Contacts; metal; interlevel vias
Other	Multilayer resist definition; resist strip; backside strip; planarization

STS Multiplex ICP Etching System and ASE Process

Figure 4 shows schematically the STS Multiplex ►ICP etching system. The source plasma is generated by an inductively coupled coil supplied by a $1-3$ kW 13.56 MHz RF generator. Another 13.56 MHz generator is used to power the platen electrode which allows independent control of the bias potential of the wafer relative to the source plasma. The wafer temperature is maintained at typically less than 80 °C through temperature-controlled, pressurized helium supplied to the back of the wafer. Wafers may be either mechanically or electrostatically clamped to the platen electrode. Typical base pressures are in the 10^{-7} torr range. The system is equipped with an automatic pressure control valve which can operate in one of two modes. In fixed automatic pressure control (APC) mode, the APC position remains constant and the chamber pressure is a function of gas flows and RF powers. In automatic APC mode, the APC valve adjusts to maintain the chamber pressure at a constant value. The tool has been developed to produce excellent

Plasma Etching, Table 2 Materials and reactive gases used for plasma/reactive ion etching in Si technology

Material	Reactive chemistry	Remarks
Si	CF_4/O_2, SF_6, NF_3 Cl_2, BCl_3, CCl_4 HBr, CF_3Br	Anisotropic; difficult Directional; good SiO_2 selectivity Directional
Oxide	CF_4/H_2, CHF_3/C_2F_6, CHF_3/CO_2	Etching selectivity to Si
Nitride	CF_4, CHF_3, SF_6, NF_3	Characteristics intermediate to Si, SiO_2
$TiSi_2$	CCl_2F_2, CCl_4	Control of oxygen impurities
WSi_2	CF_4/O_2, SF_6	
W	CF_4/O_2, SF_6	
Al	Cl_2, BCl_3, CCl_4, $SiCl_4$	Removal of native oxide
Al(Cu)	Cl_2, BCl_3, CCl_4, $SiCl_4$	Cu removal, removal of native oxide
Polymers	O_2, O_2/CF_4	

repeatability from cycle to cycle for the switched *ASE* process.

The ASE process uses sequentially alternating etching and passivation steps based on Bosch technology for anisotropic Si etching with feature sizes ranging from submicrometer to several millimeters. SF_6 and C_4F_8 are the primary gases used for etching and passivation purposes, respectively. O_2 is generally added to SF_6 in the etching step for prolonging the turbo pump life with reduction of sulfide coating on turbo blades [6] and for reducing the bowing profile at high bias with the enhancement of sidewall passivation [8]. The STS *ASE* procedure is shown schematically in Figures 5a–c: (a) passivation step after one cycle, (b) the etching step after one cycle, i. e., the second etching, and (c) profile after four cycles. Fig. 5d shows a cross-sectional SEM micrograph of the etched holes with scalloped surface due to the cycling *ASE* process. The etching and passivation mechanism can be explained with the following Eqs.:

$$C_4F_8 + e^- \to CF_x^+ + CF_x^{\cdot} + F^{\cdot} + e^- \qquad (3)$$

$$\begin{aligned} nCF_x^{\cdot} &\to nCF_{2(ads)} \text{ (on surface)} \\ &\to nCF_{2(f)} \quad \text{(polymeric passivation film)} \end{aligned} \qquad (4)$$

$$SF_6 + e^- \to S_xF_y^+ + S_xF_y^{\cdot} + F^{\cdot} + e^- \qquad (5)$$

$$\begin{aligned} nCF_{2(f)} + F^{\cdot} &\xrightarrow{\text{ion energy}} CF_{x(ads)} \\ &\to CF_{x(g)} \text{ (passivation film removed)} \end{aligned} \qquad (6)$$

$$Si + F^{\cdot} \to Si - nF \qquad (7)$$

$$Si - nF \xrightarrow{\text{ion energy}} SiF_{x(ads)} \qquad (8)$$

$$SiF_{x(ads)} \to SiF_{4(g)} \text{ (final Si etched product)} \qquad (9)$$


Gas Inlet
Weighted Clamp (optional)
Ceramic Process Chamber
13.56 MHz RF Matching unit
Plasma Chamber
Process Height
Samples Holder
MESC Compatible IIsolation valve
Temperature Controlled Bellow Sealed Electrode
13.56 MHz RF Matching unit
Helium Cooling Gas Inlet
pump

Plasma Etching, Figure 4 Schematic diagram of the STS Multiplex ICP etching system

The ionization and dissociation of C_4F_8 plasma deposits a nCF_2 or $(C_xF_y)_n$ polymeric passivating film on the sidewalls and the base of the features (Eqs. (3) and (4)). This polymer, $nCF_{2(f)}$, is preferentially removed from the base of features by the directional ion bombardment energy during the following etching cycle to expose Si for spontaneous etching (Eqs. (5) and (6)). The sidewalls remain protected by the polymer which receives no ion bombardment and subsequently no ▶chemical etching either. SF_6 gas supplies fluorine radicals (Eq. (5)) for spontaneous isotropic etching of exposed Si (Eqs. (7)–(9)). Si is mainly etched by the fluorine radicals ($F^{\cdot}$) and assisted by ion bombardment. The ion bombardment only serves to remove polymer from the base of the features. Then the passivation and etching steps are repeated for Si etching. The balance between etching and passivation determines the final process results and can be controlled by a wide variation of process parameters, e. g., the cycle time, flow rate, coil power, platen power and pressure in the etch-


CF⁺x
nCFx*
nCFx*
CF⁺x
nCFx*
Mask
Silicon
Sidewall polymeric passivation (nCF2)
a
SF⁺x
CFx*
F*
F*
SiFx*
Mask
SF⁺x
F*
F*
Sidewall polymeric passivation (nCF2)
b
Mask
Silicon
Sidewall polymeric passivation (nCF2)
c
22 um
22 um
Distance = 32.5μm
d

Plasma Etching, Figure 5 Schematic diagram of the STS *ASE* procedure: (**a**) passivation step after one cycle, (**b**) the etching step after one cycle, i. e., the second etching, (**c**) profile after four cycles and (**d**) cross-sectional SEM micrograph of the etched holes with scalloped surface

Plasma Etching, Table 3 Typical characteristics of Si etching using the STS *ASE* process [3, 6]

SF_6 flow	30 – 150 sccm
C_4F_8 flow	20 – 100 sccm
Etch cycle	5 – 15 s
Deposition cycle	5 – 12 s
Pressure	0.25 – 10 Pa
Temperature	20 – 80 °C
Etching rate	1.5 – 4 μm/min
Aspect ratio	$>$ 20 : 1
Etch depth capability	10 – 800 μm (/through wafer)
Sidewall angle	$90° \pm 2°$
Selectivity to photoresist	50 – 100
Selectivity to SiO_2	100 – 200

ing and passivation step, as well as the substrate temperature and the distance from the source plasma. Table 3 lists the typical characteristics of Si etching using the STS *ASE* process [3, 6].

Figures 6a–d show cross-sectional SEM micrographs of etched profiles in different geometry [7]: (a) high aspect ratio microstructure of holes with the same nominal diameter of 1.5 μm and nearly the same etching depth of 69.5 μm, (b) through-wafer etching of 525 μm thick Si holes with a diameter of 200 μm, (c) rectangular and circular donut trenches with constant width or radius of 5 μm and (d) trenches with feature length from 100 to 500 μm at constant width of 5 – 10 μm, respectively. Compared to Fig. 3 with the larger feature width for the deeper etching depth, the larger continuous feature area also leads to the deeper etching depth. The rectangular donut has a larger area than the circular donut, which leads to the higher etching rate or depth. In addition, the etching depth of trenches is nearly the same as the feature width is fixed. But the etching depth varies as the feature width is changed. The feature width of pattern geometry is a dominating factor affecting the ►RIE lag in ►ICP etching while secondary factors are feature area, shape as well as length-to-width ratio. Etching rates of rectangular trenches are sensitive to width while the ring trenches are sensitive to both width and area. Process parameters can be adjusted to control RIE lag magnitude.

Etching Performance and Chemistry

The performance of anisotropy etching can be evaluated from the etching rate, selectivity, profile (directionality), loading effect, ►RIE lag, ►aspect ratio dependent etching (ARDE) and uniformity. Besides the design of equipment configuration, it is related to the process condition, pattern geometry and reactant chemistry. In general, there is a compromise between the etching rate, selectivity and profile. The higher the etching rate, the better the throughput. Etching rate can be enhanced by high plasma power, substrate bias, process pressure and gas flow and a reduced total etching area. But the high ion energy from high bias,


a
b
c
d
WD20.5mm 15.0kV x100 500um
WD26.1mm 15.0kV x600 50um
WD26.6mm 15.0kV x400 100um

Plasma Etching, Figure 6 Cross-sectional SEM micrographs of: (**a**) high aspect ratio microstructure of holes with the same nominal diameter of 1.5 μm and nearly the same etching depth of 69.5 μm, (**b**) through-wafer etching of 525 μ m thick Si holes with a diameter of 200 μm, (**c**) rectangular and circular donut trenches with constant width or radius of 5 μm and (**d**) trenches with feature length from 100 to 500 μm at constant width of 5 – 10 μm

which is increased with RIE power or independently controlled in ICP, leads to low selectivity and surface damage. Good selectivity, profile control and uniformity are more easily obtained at lower etching rate and shallower depth. In HARM with high etching rate, ▶RIE lag and ARDE will become pronounced, thus reducing the uniformity. The larger the feature size, the higher the etching rate while the higher the aspect ratio, the lower the etching rate. Most isotropic etchants, e. g., SF_6 gases, exhibit a loading effect which can be reduced to some extent by using large-volume reactors and be eliminated as etchant loss, i. e., surface reaction instead of diffusion mechanism, dominates the etching behavior [1, 2]. The high ion energy for HAR features will result in bowing of the profile due to the scattering of ions at high pressure, which can be eliminated by enhanced sidewall passivation with the addition of O_2 in the etching gas [8]. In the ASE process [6], the primary dominant factors for etching rate enhancement are increase of etching step time, decrease of passivation step time and decrease of passivation gas flow. Increasing plasma power, etching step pressure and platen power also increase the etching rate. In order to create a vertical sidewall angle, the process parameters may be adjusted by increasing passivation gas flow, substrate bias, substrate temperature and etching gas flow. The reverse adjustment is made to obtain sloped or tapered sidewall profile for a wafer-level package. To reduce the scallop size for a smooth profile, it can be controlled by decreasing the etching step time, increasing the deposition step time and decreasing the etching gas flow. The patented *Parameter Ramping* has been developed to continually adjust the key parameters in ASE to meet the requirements for good profile in HARM etching [6].

As listed in Table 2, a large variety of fluorine-, chlorine-, bromine- and oxygen-based etching plasmas are used in the Si semiconductor industry. Etching of Si can be accom-


25.34um
26.92um
27.72um
29.70um
S3-1LESC
ICP#0989 E-LULE30%
SE 16:43 000014 WD28.1mm 15.0kV x500 100um
a
40.39um
37.62um
35.24um
34.45um
S3-1LESC
ICP#0987 E-LULE75%
SE 16:25 000014 WD27.5mm 15.0kV x500 100um
b
41.58um
41.58um
41.58um
ICP 15min APC 70%
SE 000020 WD24.5mm 15.0kV x500 100um
c
80
ICP#873 APC70% const area 100x100um
SE WD26.6mm 15.0kV x150 200um
d

Plasma Etching, Figure 7 Cross-sectional SEM micrographs of etched donut trenches with constant area at pressures: (**a**) APC 30% and (**b**) APC 75% for $\pi \times 52.5^2 \mu m^2$, (**c**) APC 70% for $\pi \times 105^2 \mu m^2$ and (**d**) APC 70% for the etched rectangular trenches with constant area of $100 \times 100\ \mu m^2$, in which the width varies from 10 to 100 μm while length varies from 1000 to 100 μm

plished using F-, Cl- and Br-based chemistries and the etch products include volatile SiF_4 and $SiCl_4$. The etching of Si can be carried out in a CF_4 or SiF_6 plasma with negligible ion bombardment of the Si substrate [1]. The correspondence of Si etch rate and atomic fluorine emission is as a function of the RF power through the intensity variation of the 704 nm atomic fluorine-related optical emission. Reactive F atoms are directly involved with Si etching. The gas phase density influences the etching rate in simple CF_4 or SiF_6 plasmas and a large undercut occurs in F-based plasma etching due to the isotropic chemical etch. The directionality in SiF_6 plasma etching can be improved by cooling the substrate to a temperature of −110 to −120 °C, as cryogenic etching enables one to get near vertical profiles [1]. The spontaneous ►chemical etching reactions are suppressed at *cryogenic* temperatures. The etching at the bottom of the feature dominated by ion-assisted etching reactions is not affected at low substrate temperature while the vertical etching rate increases with decreasing temperature, attributed to condensation of etchant for high density. The drawbacks of Si etching at cryogenic temperature are the cracking of resist mask, the increase of surface contamination (leading to black Si) and the increase of equipment complexity. A hard mask, e. g., oxide or metal, is needed in cryogenic etching. Anisotropic Si etching can also be obtained by Cl- and Br-based plasmas at room temperature. Si and oxide passivation are not spontaneously etched by chlorine and bromine atoms for directionality improvement. The size of the halogen relative to the Si atom plays an important role in the spontaneous etching. The spontaneous etching of Si exposed to large Cl atoms is absent compared to small F atoms for isotropic profiles. Although Cl- and Br-based plasma chemistries may achieve highly anisotropic structures, the shallow depth (< 20 μm) obtained limits the potential for MEMS applications. Modified F-based plasmas for Si etching by sequentially switching etching and passivation gases, i. e., Bosch technology, demonstrate anisotropic etching for high aspect ratio microstructure and through-wafer at room temperature. It has become the main method in Si etching as described in the previous sections.

End Point Detection (EPD)

The most direct need for plasma diagnostic techniques results from the determination of the etch end point for a given process. In addition, plasma diagnostic techniques are used for process monitoring and provide information on the types of species present in a plasma etching, the concentration and the energy content. Laser interferometry (or reflectance) and optical emission spectroscopy (OES) are two commonly used techniques for EPD and require only an appropriate optical window attached to the chamber. They are easily implemented to obtain information about etching plasmas [1].

Laser Interferometry (Reflectance)

This technique measures the laser light reflected from the surface of a wafer being etched. For transparent films, e. g., SiO_2, an oscillation is observed for the reflected laser light intensity due to interference of the reflected light from surfaces of both the film and the substrate. The spacing between adjacent maxima (or minima) is $\delta d = \lambda/2n$, where λ is the wavelength of the laser light and n is the refractive index of the transparent layer. Etch rates can be examined in real time. For nontransparent films, e. g., metals, one measures the change in reflectivity before and after complete removal of the metallic film. For patterned wafers without an etch stop layer, we determine the depth of the etched pattern in situ through the used pattern as a diffraction grating. There are two principal drawbacks of these techniques. Firstly, they usually require a special test site especially as the features being etched, e. g., contact holes into a SiO_2 film, are too small for measurements. Secondly, the obtained EPD information is only for one specific area on the wafer, and not suitable for batch processing.

Optical Emission Spectroscopy (OES)

OES is the most widely used techniques for etch end point detection. The change in emission from a characteristic species is observed as etching of a film is completed. Either the decrease in emission of a suitable etch product species or the increase in etchant species at the end of the etching process is monitored. By measuring the wavelengths and intensities of the emitted spectral lines, one can identify the end points both in research laboratories and in manufacturing for production control. Some important electronic materials and common optical emission lines of etching gases used for EPD are listed in Table 4. The OES technique is limited to the monitoring if light-emitting species and the emission intensities are not always directly related to the concentration of the species in the plasma. The sensitivity of this technique depends on how much etchant is consumed or how much film material is etched per unit. If the etch rate is too slow or the size of the etched pattern too small, e. g., contact hole etching into SiO_2 layers, this technique may not be suitable for EPD.

Experimental

Si wafers are initially cleaned in a solution of $H_2SO_4 : H_2O_2$ at 3 : 1 ratio. Thick resist or thermal oxide SiO_2 are used as ICP etch mask of Si. Standard lithography and RIE are used to transfer the photo mask pattern to thick resist or oxide mask. Si deep etching is performed using the *ASE* process in an STS Multiplex ICP system. The etching and passivation gases are ($SF_6 + O_2$) and C_4F_8, respectively, and are switched during the process. Three major kinds of patterns of constant length, constant width and constant area with different feature sizes of 2 to 100 µm are divided to understand the dominating factor of geometry for ►RIE lag in ►ICP etching. Process pressure is adjusted by auto pressure control (APC) from 30% to 75% to understand the process pressure effect on RIE lag. The plasma source is generated by a 600 – 800 W 13.56 MHz RF generator

Plasma Etching, Table 4 Common optical emission lines of etching gases used for EPD [1]

Material	Etchant gas	Emitting species	Wavelength (nm)
Si	CF_4/O_2, SF_6	F (etchant)	704
	CF_4/O_2, SF_6	SiF (product)	440, 777
	Cl_2, CCl_4	SiCl (product)	287
SiO_2	CHF_3	CO (product)	484
Si_3N_4	CF_4/O_2	N_2 (product)	337
	CF_4/O_2	CN (product)	387
	CF_4/O_2	N (product)	674
W	CF_4/O_2	F (product)	704
Al	Cl_2, BCl_3, CCl_4	Al (product)	391, 394, 396
	Cl_2, BCl_3, CCl_4	AlCl (product)	261
Resist	O_2	O (etchant)	777, 843
	O_2	CO (product)	484
	O_2	OH (product)	309
	O_2	H (product)	656



Plasma Etching, Figure 8 SEM images of (**a**) an electroplated Ni mold, (**b**) hot embossed PMMA replica and (**c**) PMMA adhesive bonding in ICP LIGA

and biased by a 10 – 15 W 13.56 MHz RF generator at the platen during the etching step. The wafer is electrostatically clamped and cooled by backside helium flow. Scanning electron microscopy (SEM) is used to examine the etching result after the *ASE* process.

Key Research Findings

Fabrication of Deep/HAR Si Microstructure with High Etching Rate and Good Uniformity to Large Diameter Wafers (Up to 200 mm)

For the requirements of full-scale commercial production, Si DRIE for MEMS applications and advanced packaging are needed for high etching rate with excellent uniformity. The wafer size up to 200 mm is expected and important for high throughput and yield for a cost-effective end product. In mid-2005, STS [6] introduced a new generation of Si etch system, known as Pegasus, for the above purposes. Pegasus employs a revolutionary new de-coupled ICP source design by enhancing both the throughput and the yield to reduce the cost per die.

In conventional plasma processing with the *center-high* spatial profile of both ions and neutral radicals, the density profile variation of the ions will usually be more extreme than for the radicals, leading to large uniformity deviation. Two new de-coupled plasma sources are patented technologies of STS for ramping and SOI modules. They offer the following benefits:

- To reduce the volume of the plasma source for more efficient breakdown of the precursor gas due to the higher power density delivered from the RF power supply.
- To adjust the geometry and volume of the plasma source region to match the silicon's loading characteristics for the ions and neutral radicals diffusing down to the wafer with the desired profiles to obtain high etch uniformity.
- To alter the balance between numbers of ions and neutral radicals reaching the wafer to control selectivity to mask and/or ion damage to feature profiles.

With the appropriate magnitude of parameter values during an etching and precise control of notching at the surface of Si to the insulator, a high etch rate with good uniformity can be achieved. For example, Si etch rates of more than 30 μm/min can be achieved at a more realistic exposed area of around 10% and exceeding 50 μm/min for a 1% exposed area have been observed using the Pegasus source with the *ASE* process. Yield is optimized by improving absolute etch depth uniformity and by reducing trench tilting artifacts observed with conventional ICP plasma sources. The very high etch rate uniformity and feature profile control is relevant for up to 200 mm wafers.

Inverse RIE Lag and Lag Elimination

A ►RIE lag phenomenon occurs in many patterns and becomes more severe at smaller feature width and higher etching depth. In general, the smaller the feature size, the



Plasma Etching, Figure 9 SEM micrographs of (**a**) plane-view nozzle array with circuit layout and (**b**) cross-section of one nozzle for a high-resolution inkjet head application

lower the etching rate and the more obvious is the RIE lag. Experimental results reveal that the primary dominating factor is feature width and a secondary factor is feature area together with length-to-width ratio. Chung [7] reported the effect of geometrical pattern and process parameters on the transition between RIE lag, inverse RIE lag and eliminated RIE lag. Figures 7a and b show SEM micrographs of etching donut trench structure with constant area of $\pi \times 52.5^2 \mu m^2$ at a pressure of APC 30% (20 mtorr (etching)/10 mtorr (passivation)) and APC 75% (54 mtorr (etch)/32 mtorr (passivation)) for 30 min, respectively. The RIE lag exists at low pressure of APC 30% while an inverse RIE lag appears at high pressure of APC 75%. The inverse RIE lag means the higher etching rate occurs at smaller feature width. It implies that other mechanism exists in Si DRIE with respect to previous reports [4, 9]. The possible new reaction mechanism is C_xF_y radical dissociated from C_4F_8 passivation gas playing an important role to affect the etching rate ratio of different feature sizes. The formation and removal of C_4F_8 passivation film impedes the increase of etching depth while the arrival of SF_6 etching gas enhances the etching processing. As the pressure increases, the increasing C_xF_y radical density for the formation of passivation film and reducing S_xF_y ion density to remove passivation film at the bottom will delay longer the start of etching of Si surface at the bottom in a large feature than a small one. The etching rate is enhanced more for small width than for large width. This will lead to the reduction of RIE lag. If the pressure is much higher, inverse RIE lag occurs. Since RIE lag and inverse RIE lag have been achieved, we could find an optimum condition at a pressure of APC 70% to obtain the RIE lag-eliminated feature as shown in Fig. 7c and d, respectively, for donut trenches with constant area of $\pi \times 105^2 \mu m^2$ and rectangular trenches with constant area of $100 \times 100 \mu m^2$.

SOI MEMS and Other Microstructures Using Pure Isotropic Etching or in Combination with Anisotropic Etching

Silicon-on-insulator (SOI) MEMS has the advantages of RIE lag elimination and enabling multilevel HARM for optical MEMS applications. Milanovic [10] reported multilevel beam SOI–MEMS fabrication and its applications to optical scanners. The multilevel beam was fabricated by 4-mask DRIE: two for front-side and two for back-side etching to high degree of freedom motion (both upward and downward vertical pistoning motions as well as bi-directional rotation). One problem of notching or footing will occur at the bottom of Si on oxide due to charging effect. Docker et al. [11] used the notching effect as lateral etching for the fabrication of suspended MEMS structure in one dry single-step process. Mita et al. [12] used DRIE SOI and contour lithography methods for fabrication of nanometer-to millimeter-scale coexisting microsystems. Marty et al. [13] reported that three-dimensional Si structure for Fresnel lens or staircase structure can be fabricated by pure SF_6 isotropic etching in RIE lag condition. In a combination of isotropic and anisotropic etching, a single crystal reactive etching and metalization (SCREAM)-like process has been demonstrated for a suspended Si MEMS structure without the need for an SOI wafer. Other multistep structures from isotropic and anisotropic etching can be fabricated for applications in the photonics and microfluids.

ICP LIGA-Like Process and Nanoimprinting

ICP LIGA-like process is a process to duplicate deep polymer microstructure for applications in microfluid or micro-devices at low cost and easy fabrication compared to the X-ray LIGA process. Figures 8a–c show SEM micrographs of an electroplated Ni mold, hot embossed poly(methyl methacrylate) (PMMA) replica and PMMA adhesive bonding, respectively, in ICP LIGA after Si DRIE process. The PMMA channel width is about 300 μm and the depth nearly 285 μm with vertical sidewall profile without any distortion. It indicates that a cheap plastic chip can be obtained for microfluidic applications using the ICP LIGA process. With the development of nanoimprinting, it requires Si or quartz stamps in a nanoscale pattern for nanolithography pattern transfer. ►ICP etching has been used for the manufacture of Si stamps used to pattern the resist in hot embossing or in different etching chemistry for the transparent quartz stamps used in UV light curing the resist [6].

Examples of Applications

Many examples of applications have been reported in the STS Innovations magazine issues 1 – 3 since April 2006 [6]. They include MEMS inertial and pressure sensors, Si springs for luxury wristwatch components, optical switches and resonators for communication, microphones for portable electronic equipment, advanced packages (system-in-package), and inkjet channels and nozzles. For example, Figs. 9a and b show SEM micrographs of a plane-view nozzle array with circuit layout and cross-section of one nozzle, respectively, for high-resolution inkjet head application. It combines the fabrication of backside wet anisotropic etching and front-side dry DRIE etching. The nominal nozzle diameter is 10 μm with vertical profile as well as scallop rings due to the *ASE* switching process. The emerging nanoscale etching has been applied in photonic crystals, magnetic nanostructures (magnetoresistive random access memory, MRAM), high-Q MEMS resonators, sub-micrometer pilar array or HAR structures made of Si for bioanalysis and lab-on-a-chip, microchannels and inkwells for dip pen nanolithography, and Si or quartz stamps for nanoimprint lithography.

Future Directions for Research

ICP is an important technology for micro- and nanoscale patterning processes. High etch rate, high aspect ratio and anisotropic, good profile control, high uniformity and RIE lag elimination are important issues in the development of MEMS and nanotechnology devices. In MEMS fabrication, it is steadily moving from the development and pilot stages to full-scale production. In nanofabrication, it is promising to enable nanometer–micrometer–millimeter multiscale structures in device design and application. In combining isotropic and anisotropic etching, different promising HARM or three-dimensional structures may be realized for the application of Si-MEMS or SOI MEMS. ICP technology will be required in many applications including MEMS inertial and pressure sensors, optical switches and resonators for communication, inkjet channels and nozzles for high-resolution printheads, microphones for portable electronic equipment, advanced packages, and so on.

Cross References

- ► Anisotropic Etching
- ► Dry Chemical Etch
- ► ICP Etching
- ► Isotropic Etching
- ► Laser Ablation
- ► Laser Based Micromachining
- ► LIGA Like Techniques
- ► Plasma in Microchannel
- ► Reactive Ion Etching (RIE)
- ► Silicon Micromachining

References

1. Oehrlein GS (1990) Reactive Ion Etching. In: Rossnagel SM, Cuomo JJ, Westwood WD (ed) Handbook of plasma processing technology. Noyes, Berkshire
2. Grill A (1994) Plasma Assisted Etching. In: Cold plasma materials fabrication: from fundamentals to applications. Wiley/IEEE, Hoboken
3. Madou M (2002) Pattern Transfer with Dry Etching Techniques. In: Fundamentals of Microfabrication, 2nd ed. CRC, Boca Raton
4. Kassing R, Rangelow IW (1996) Etching process for High Aspect ratio Micro Systems Technology (HARMST). Microsyst Technol 3:20–27
5. Laermer F, Schilp A (1994) Method of Anisotropically Etching Silicon. German Patent DE4241045 1996; USA Patent 5501893, 1996
6. http://www.stsystems.com/; STS Innovations news, issues 1–3, April, July and September, 2006
7. Chung CK (2004) Geometrical pattern effect on silicon deep etching by an inductively coupled plasma system. J Micromech Microeng 14:656–662
8. Chung CK, Lu HC, Jaw TH (2000) High aspect ratio silicon trench fabrication by inductively coupled plasma. Microsyst Technol 6:106–108
9. Jansen H, de Boer M, Wiegerink R, Tas N, Smulders E, Neagu C, Elwenspoek M (1997) RIE lag in high aspect ratio trench etching of silicon. Microelectron Eng 35:45–50
10. Milanovic V (2004) Multilevel Beam SOI-MEMS Fabrication and Applications. J Microelectromech Syst 13(1):19–30
11. Docker PT, Kinnell PK, Ward MCL (2004) Development of the one-step DRIE dry process for unconstrained fabrication of releASEd MEMS devices. J Micromech Microeng 14:941–944
12. Mita Y, Kubota M, Harada T, Marty F, Saadany B, Bourouina T, Shibata T (2006) Contour lithography methods for DRIE fabrication of nanometre-millimetre-scale coexisting microsystems. J Micromech Microeng 16:S135–S141
13. Marty F, Rousseau L, Saadany B, Mercier B, Français O, Mita Y, Bourouina T (2005) Advanced etching of silicon based on deep reactive ion etching for silicon high aspect ratio microstructures and three-dimensional micro- and nanostructures. Microelectron J 36:673–677

Plasma in Microchannel

KHANH DANG[1,2], DAVID W. G. MORRISON[1,2],
UTKAN DEMIRCI[1,2], ALI KHADEMHOSSEINI[1,2]
[1] Harvard-MIT Division of Health Sciences
and Technology, Massachusetts Institute of Technology,
Cambridge, MA, USA
[2] Center for Biomedical Engineering, Department
of Medicine, Brigham and Women's Hospital,
Harvard Medical School, Boston, MA, USA
alik@mit.edu

Synonyms

Microchannel glow discharge; Microchannel surface modification; Microchannel surface sterilization; Plasma bonding

Definition

Gas plasma, a fourth state of matter, is a neutral composition of ions, electrons, radicals, and photons that is synthesized by applying energy to a gas at atmospheric pressure or within a vacuum. Gas plasma can be used to enhance the functionality of microdevices for various biological and chemical applications. The effects of plasma in microchannels are regulated by parameters such as the type of gas, power intensity, chamber pressure and duration of the treatment.

Overview

Microchannels that range in diameter from tens to hundreds of microns have emerged as potentially powerful tools for a variety of biomedical applications. They can be used to minimize sample volume and reduce costs, as well as to increase throughput and analysis sensitivity. Since microfluidic devices operate at small length scales, their functionality is greatly dependent on their surface properties, which vary depending on the type of material that is used to fabricate the channel and the subsequent surface modifications.

Microchannels have traditionally been fabricated from commonly used materials from the semiconductor industry, such as silicon. Silicon offers many advantages for microchannel fabrication, such as standardized fabrication procedures and easy integration with electronics. Despite these merits, silicon is opaque and brittle and cannot be used for fabricating transparent microfluidic devices that require light based sensors. To overcome these difficulties, glass microfluidic channels have also been developed, however, the fabrication of these devices, similar to those of silicon microchannels is time consuming, expensive and requires the use of a clean room facility. As a result, polymeric microchannels have recently emerged as potentially valuable alternatives. Polymers that have previously been investigated for microchannels include: polycarbonate (PC), polystyrene (PS), poly(dimethylsiloxane) (PDMS) and poly(methylmethacrylate) (PMMA). One of the main advantages of using polymeric materials to make microchannels is that they can be fabricated from soft lithographic techniques such as micromolding. Furthermore, the ability to tailor the mechanical and optical properties of polymers can be used to fabricate microchannels with a wide range of properties. Despite the great advancements in the materials used to fabricate microchannels, the surface properties of these channels often require additional modifications based on the specific needs of the device. Thus, approaches to activate microchannel surfaces have been of great interest in fully realizing the potential of these techniques.

During the 1920s and 1930s, Dr. Irving Langmuir proposed the term *plasma* while he was studying the physical properties of gases and the balance of charges between ions and electrons. Commonly considered as the fourth state of matter, basic gas phase plasma contains a neutrally charged mixture of negative and positive ions, photons, electrons and radicals that are produced by applying energy to a gas at low pressure (from 10^{-6} to 10^{-4} bar). In this process, the temperature of plasma electrons is extremely high (on the order of 10^4 K), however, the plasma gas remains close to ambient temperature. This is because plasma components found at higher temperatures (such as the sun) are made of equilibrium (thermal) plasmas while low-pressure gas plasmas are non-equilibrium (non-thermal) type. Plasma is formed by the exposure of free electrons to an external energy source that increases the kinetic energy, resulting in the formation of radicals and ions. These excited molecules then form photoemissions, ions and free radicals due to a loss of excess energy from the plasma. The energy released from these chemical species is capable of breaking covalent bonds and altering the surface chemistry of many materials.

The bombardment of a surface with reactive chemical species can be used to drastically change its surface properties and create functional surfaces within microchannels. Traditionally, corona discharge and oxygen plasma treatment have been used. Corona discharge is the formation of sparks at the tip of a wire created by electromagnetic fields that result in the ionization of nearby molecules at low temperatures and pressures. Corona discharge can be used to oxidize a surface near the tip of the wire. Although widely used in various industrial processes, a negative aspect of corona discharge is its tendency to modify the surface non-uniformly. To overcome this limitation, surface plasma treatment can be used. Plasma treatment of microchannel surfaces is particularly attractive, as it does not require the tedious placement of a wire inside microscale channels. In addition, plasma treatment of a surface is faster and more reproducible compared to corona discharge.

The reaction between the plasma and a surface is highly complex and comprised of numerous and simultaneous chemical reactions [1]. Upon the initial application of energy, the gas molecules, such as oxygen, are converted to various unstable intermediates that can react with the surface. Some of the initiation mechanisms between plasma



Plasma in Microchannel, Figure 1 Schematic of the oxygen plasma treatment of a PDMS substrate

(which may include oxygen radicals) with a surface are shown below:

$$RH + O\bullet \;\rightarrow\; \begin{array}{l} R\bullet + H\bullet + O_2 \\ R_1\bullet + R_2O\bullet \\ R\bullet + OH\bullet \end{array}$$

These radical species then induce chain scission, radical transfer, oxidation and disproportionation to generate functional surface groups such as hydroxyl and carboxyl moieties (Fig. 1). For some materials, such as PDMS, these activated surfaces can be bonded to fabricate channels, as shown in Fig. 2. Plasma treatment of microchannels can also be used to control surface properties by incorporating reactive molecules or by increasing the hydrophilicity of the surfaces that eases the flow of fluids and minimizes the formation of bubbles.

In addition to adding surface functional groups, plasma can be used to remove organic contaminants and sterilize surfaces. In this process, plasma radicals break the covalent bonds and oxidize the surface contaminants, which are then cleared by the vacuum. Here, we will outline the basic methodology of gas plasma modification in microchannels, including theory, experimental methods, pertinent process parameters and characterization methods. Additionally, key research findings will be discussed.

Basic Methodology

In this section we will outline the basic methodology of the plasma treatment process. First, the theory behind plasma treatment will be presented. Following this, experimental protocol outlining the treatment process, pertinent parameters and their relevance will be discussed. Finally, surface analysis methods for plasma treated surfaces will be described, such as X-ray photoelectron spectroscopy (XPS), atomic force microscopy (AFM), and contact angle measuring tools.

Theory

To establish an analytical framework of plasma formation and initiation, thermodynamic models have been developed. For example, for low pressures and high frequencies that generate plasma gases at ambient temperatures the power required to generate plasma can be determined from molecular collision analysis. In this model, the reactive species within the plasma process are created from inelastic collisions between electrons and ground-state atoms [2], where electrons have energy, u, given by

$$u = \frac{(mw^2)}{2}$$

where w is the electron velocity and m is the electron mass. The excitation rate coefficient, C_j, of a particular species is then given by

$$C_j = \left(\frac{2}{m}\right)^{\frac{1}{2}} \int_0^\infty \sigma_j(u) F_0(u) u du$$

where $\sigma_j(u)$ is the particular process cross-section and F_0 is the electron energy distribution function. Nearly all processes at this level that are important possess energy threshold, u_j, where

$$\sigma_j(u) \equiv 0, \quad u \leq u_j$$

There is also a dependence of the number density $\dot{n}_j$ of species j produced per second in the plasma from ground state molecules (of number density Ncm^{-3}) on the electron density n, where

$$\dot{n}_j = C_j N n.$$

The applied electromagnetic field (where frequency $f = \omega/2\pi$) and the plasma has a power balance that is expressed by

$$P_a = \xi n V,$$

where the power absorbed is P_a, the volume of plasma is V and the average power absorbed per electron is ξ. ξ also refers to the power necessary to sustain an electron–ion pair in the plasma.

Experimental

To plasma treat a surface, samples are initially placed within a plasma vacuum chamber. Gas plasma is then generated using various energy sources such as alternating current (AC), radio frequencies (RF) or microwaves (MW) (Fig. 3). For example, in apparatuses that use RF, two electrodes apply energy in the form of magnetic and electric fields to a gas at low pressure ($\sim 266-800$ mbar) inside the vacuum. The application of appropriate amount of energy to the gas discharge results in the formation of a neutral gas plasma. During this process, a characteristic glow is emitted from the apparatus indicating the plasma state of the gas.

Parameters

There are a number of parameters that affect the surface modification during the plasma treatment process. These parameters can be separated into internal process parameters, which are dependent on the plasma, and external process parameters, which are external to the plasma but within the system. Examples of internal parameters include the type and the degree of dissociation of the gas and the residence time of the active species in the vacuum chamber. Examples of the external parameters include, but are not limited to, the substrate material, amount of time that the material is exposed to the plasma, gas pressure, energy frequency, power and substrate temperature. It is important to note that the internal parameters of the plasma are indirectly controlled by the external process parameters. Figure 4 depicts the relations among several parameters. This entry will discuss how the type of gas, exposure time, gas pressure and power affect the plasma initiated surface modifications and the resulting bonding strengths of substrates.

The type of gas is a key parameter in any plasma surface modification process. Plasma treatments using inert gases, such as argon, have been shown to increase the hydrophobicity of oxygen-containing polymers without adding detectable chemical species to the surface. These properties are a result of the degradation and rearrangement of molecules on the surface of the polymer. Degradation is caused by an increase in the kinetic energy in the plasma treatment chamber when inert plasmas are present. This increased energy breaks molecular bonds on the surface, which result in the degradation of the impurities on the surface of the substrate. Rearrangement of chemical species occurs as a result of cracks that are introduced onto the surface of the substrate. These cracks enable molecules from beneath to rearrange with molecules present on the surface. This is indicated by a decrease in the oxygen/carbon ratio within the treated surface, possibly resulting from loss of CO or CO_2. In contrast, plasma treatment by using reactive gases results in the direct conjugation of the reactive molecule on the surface. For example, in the case of oxygen plasmas, hydroxyl and carboxyl functional groups are formed on the surface and can react with each other between two treated surfaces through a dehydration reaction to produce covalent linkages that result in bonding of two substrates.

The exposure time of the plasma to the surface can greatly affect its surface properties. For example, the bonding of PDMS to PDMS for the fabrication of microchannels has been shown to be time dependent (Table 1). If the substrate is not adequately treated with plasma then there will not be enough functional groups present to achieve bonding. If the substrate exposure exceeds an optimal time. Then there will be excessive oxidation of the PDMS surface and the formation, which leads to the formation of a brittle layer of silica. Thus, prolonged plasma treatment results in polymer reorganization on the substrate surface that causes decreased bonding strength due to induced hydrophobic properties.

It has also been determined that the internal pressure of the treatment chamber has a significant impact on the surface properties of treated substrates (Table 1). When the internal pressure is high, the mean free distance between molecular collisions within the plasma is significantly reduced. For example, for PDMS substrates the upper pressure region is characterized as greater than approximately 0.1 mbar. The molecules within this condensed plasma increasingly interact with the polymer surface molecules, resulting in increased bonding strength. Conversely, if the pressure within the chamber is too low (i. e. less than approximately 0.1 mbar) there is reduced interaction between the plasma and the surface and the bond strength is not optimized.

Finally, power variation has also been shown to affect the surface properties of the substrate (Table 1). In the case of PDMS at low power settings, plasma electron speeds are reduced and there is less interaction between the radicals in the plasma and the substrate. This minimizes the formation of functional groups on the surface. Conversely, extreme voltages result in reduced bonding strengths because of the formation of Si–O–Si groups on the PDMS surface. The dissociation energy of these specific bonds is larger than the dissociation energy of the Si–C bonds in the backbone of the polymer, therefore causing substrate degradation and less functional group formation for PDMS-PDMS bonding. At optimal power levels the number of functional groups present on the surface of the substrate is high enough to encourage bonding but low enough to not affect the siloxane backbone of the PDMS.


A. Perform photolithography to create master
Si
master
B. Pour PDMS over master; cure at 70°C for 1 hour
PDMS
Si
C. Peel PDMS from master
PDMS
OH OH OH
•••O–Si–O–Si–O–Si–O•••
CH_3 CH_3 CH_3
D. Plasma treat PDMS
Plasma
Plasma Chamber
PDMS
E. Seal against a flat surface
PDMS
microchannel

Plasma in Microchannel, Figure 2 Schematic of the process used to fabricate microchannels through a plasma induced bonding process

Plasma in Microchannel, Table 1 Comparison of the bonding results with RIE process parameters for bonding of plasma treated surfaces. Bonding 1 metric based on permanently bonded area after immediate contact (no bonding = 0 ~ whole area bonded = 10). Bonding 2 metric based on permanently bonded area when 3 days have passed after immediate contact. Adapted from [11]

#	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21
Power (W)	70						200						300						400		500
Pressure (mTorr)	65		120		180		65		120		180		65		120		180		120		160
Time (sec)	10	40	10	40	10	40	10	40	10	40	10	40	10	40	10	40	10	40	10	40	20
Bonding 1 (max=10)	10	6	10	9	10	9	10	6	10	7	10	3	4	0	3	0	3	0	2	0	0
Bonding 2 (max=10)	10	10	10	10	10	10	10	8	10	8	10	8	4	0	3	0	3	0	2	0	0

Evaluation of Plasma Treated Surfaces

Surface chemical composition, structure and functional properties can be characterized by various techniques, such as XPS, AFM, and contact angle measurements. XPS measures the short range of photoelectrons leaving the surface. The sensitivity ($\sim 1-10\,\text{nm}$) is semi-quantitative and detects chemical bonding information at the surface. Composition depth profiles, known as XPS spectra, can be generated from this method. Conversely, AFM utilizes a nanoscale probe to characterize surfaces and produce 3D surface profiles. AFM can determine the surface roughness and elastic modulus through phase imaging and nanoindentations, respectively. In addition to analyzing the surface of substrates, cross-sections can be imaged by using AFM to picture the stiffer surface layer and determine thickness. Furthermore, contact angle analysis can also be used to study surface wetting behavior. Contact angle measuring devices measure the angle of a liquid–vapor interface with a solid surface to assess surface hydrophilicity. Water droplets on hydrophilic substrates spread out and have relatively low contact angle measurements. Conversely, they maintain a more spherical shape on hydrophobic substrates, thereby producing higher contact angle measure-



Plasma in Microchannel, Figure 3 Schematic of a radio frequency plasma treatment chamber

ments. Common contact angle analysis methods include drop–bubble, reflective light and interference microscopy.

Key Research Findings

Various research findings on the effects of plasma treatment on microchannels have reported improved surface characteristics within microfluidic channels. Researchers have also been able to adapt plasma treatment technologies to develop novel applications in the field of engineering. Furthermore, applications of plasma in microchannels include the development of on-chip light sources and the fabrication of micropatterns and gradients for cell adhesion studies.

Hydrophobic Recovery and Bonding Enhancement Techniques

As previously mentioned, surface properties of a substrate can be tailored by applying various plasma treatments. The stability of plasma treatment is dependant on the material properties. For instance, for PDMS, oxygen plasma treated surfaces regain their hydrophobicity over time. This may be due to

- surface silanol groups reorienting into the bulk;
- movement of free PDMS chains from the bulk phase to the surface through cracks in the Si–O–Si structure;
- silanol groups at the surface condensing;
- volatile oxygen or other species escaping into the atmosphere;
- changes in the surface roughness [4].

Conversely, other explanations suggest hydrophobic recovery can be described in two distinct phases: adsorption of atmospheric contaminants and surface reorganization. Within the first few hours, the initial phase of adsorption of atmospheric contaminants begins. These atmospheric species react with the surface moieties that were introduced during treatment and reduce their functionality. In the case of PDMS, surface reorganization begins when siloxane groups from the backbone of the polymer migrate through cracks created during surface modification and reorganize to yield the original properties of the polymer. Similarly to hydrophilicity, bonding characteristics are also dependent on time (Table 2). It has been shown that the adsorption of contaminants and surface reorganization also has an adverse effect on the bonding properties of PDMS.

To increase the stability of a surface treated substrate a variety of approaches have been developed. For example, different plasma gases can be applied to reduce the amount of surface reorganization. Specifically, nitrogen treated surfaces maintain their hydrophilicity longer than oxygen plasma treated surfaces. Also, to maintain stable hydrophilic PDMS it is possible to fabricate C-F bonds or react poly(HEMA) bonds on PDMS microchannel surfaces [6].

Enhancing Microchannel Functionality

Plasma treatment of microchannels can be useful for improving the functionality of microdevices. For example, previous studies have shown that PDMS microchannels can be made hydrophilic by the addition of silane molecules with polar head groups [7]. In this process (3-mercaptopropyl)trimethoxysilane (3-MPS) was absorbed to PDMS to increase the hydrophilic properties of microchannels. Additionally, plasma polymerization has been used to induce in the long-term hydrophilic surface modification by covalently bonding a polymer layer to the surface. Barbier et al. [8] describe a method based on plasma polymerization modification with acrylic

Plasma in Microchannel, Table 2 Aging of activated PDMS surfaces. Bonding metric is based on permanently bonded area after aging the activated surfaces (no bonding = 0 ~ whole area bonded = 10). Adapted from [11]

#	1	2	3	4	5	6	7	8	9
Power (W)					70				
Pressure (mTorr)					75				
Etch Time (sec)					10				
Aging (min)	2	3	5	7	10	15	20	25	30
Bonding 1 (max=10)	10	10	10	10	10	10	6	7	8


Substrate
•Material
•Dimension
•Morphology
•Quantity
•Temperature
•Potential
Reactor
•Gas leading system
•Inner wall
•Electrode
•Material
•Configuration
•Temperature
Gas Flow
•Carrier gases
•Pressure, flow (total/partial)
•Gas background
Energy Input
•Frequency
•Power density
•Duration
Plasma
•Type and degree of dissociation of the gases
•Live time and residence time of active species
•Ion bombardment and radiation
Parameters

Plasma in Microchannel, Figure 4 External parameters that influence the quality of surface plasma treatment

acid coatings. First, argon plasma pretreatment was used to activate trace oxygen molecules in the chamber, which partially oxidize the top layer of the substrate. This step crosslinked the surface to reduce ablation of silicon during deposition as well as limits the movement of siloxane chains for hydrophobic recovery. Secondly, plasma with acrylic acid was deposited onto the pretreated PDMS. Finally, helium plasma treatment was used to crosslink the deposited polymer film to reinforce the cohesion. This process provides a homogeneous stable hydrophilic polymer layer for robust applications within microfluidics and nanofluidics.

Applications

Applications of plasma in microchannels include the development of chromatography detectors and on-chip light sources. Evju et al. [9] describe the creation of microdischarges or microplasmas by direct current within microfluidic channels on polystyrene. The three different gases tested included helium (He), water-saturated helium (H_2O/He), and hexafluoroethane (C_2F_6/He). These gases were released through a microchannel and ignited at atmospheric pressure. The treatments were completed in several seconds to reduce heat formation. XPS confirmed that oxygen and fluorine on the surfaces contributed to hydrophilic and hydrophobic regions, respectively.

Complex biomolecular micropatterns and microgradients have also been synthesized with the use of plasma treated surfaces, with possible future applications in tissue engineering, biosensors, and immunoassays. Various methodologies, such as microcontact printing and micromolding, have been used to create micropatterns where wettability was controlled through selective plasma treatment. These micropatterns are made up of many ligands and cell types for spatial control and cellular organization. This organization can induce cell–cell signaling and recreate the hierarchy lost in standard in vitro methods to produce more tissue-like structures. These advances are critical in understanding biology and enabling improved tissue culture and tissue engineering techniques.

An application of plasma treated surfaces has also been shown in microcontact printing, where elastomeric stamps are *inked* with chemical species and ligands, which can then be patterned onto different surfaces. Langowski et al. [10] have shown that by applying oxygen plasma to the original *stamp* there is a reduction in low-molecular-weight silicon containing fragments transferred to PMMA substrates. The effect of the treatment increased ligand bioactivity, cell function and proliferation due to reduced contamination from the initial untreated substrate. This finding allows for proper modification for applications desiring the removal of low-molecular-weigh silicon fragments, especially for biological applications.

Microgradient textures within microchannels have also been synthesized by utilizing plasma treatments. By having gradients of ligands, microchannels enable visualization of the effects on cell behavior, such as differentiation, migration and adhesion. Because of the quick and inexpensive nature of soft lithographic techniques and plasma treatments, biological applications can be done more cost effectively and in a faster manner.

Future Directions for Research

Plasma treatment of microfluidic surfaces can be used to improve microdevice functionality, to build devices through bonding processes and to activate and sterilize surfaces. Future directions for this technology include improved modeling of techniques with respect to parameter and surface plasma interaction. The development of refined experimental methods, theoretical models, and experimental studies is required to have more control over plasma treatment within microchannels.

Cross References

- ► Plasma Treatment Physics
- ► Plasma Etching
- ► AFM
- ► Bioprinting on a Chip
- ► Cell Adhesion and Detachment
- ► Control of Microfluidics
- ► Wetting and Spreading

References

1. Wu S (1982) Polymer Interface and Adhesion. Dekker, New York
2. Liston EM, Martinu L, Wertheimer MR (1997) Plasma surface modification of polymers for improved adhesion: a critical review. Plasma Surface Modification of Polymers: Relevance to Adhesion. VSP Boston
3. Makamba H et al (2003) Surface modification of poly(dimethylsiloxane) microchannels. Electrophoresis 24(21):3607–3619
4. Fritz JL, Owen MJ (1995) Hydrophobic recovery of polydimethylsiloxane after exposure to corona discharge. J Adhesion 54:33–45
5. Jo BH et al (2000) Three-Dimensional Micro-Channel Fabrication in Polydimethylsiloxane (PDMS) Elastomer. J Microelectromech Syst 9(1):76–81
6. Bodas D, Khan-Malek C (2006) Formation of more stable hydrophilic surfaces of PDMS by plasma and chemical treatments. Microelectron Eng 83:1277–1279
7. Pisignano D et al (2004) Rapid Soft Lithography by Bottom-Up Enhanced Capillarity. Langmuir 20(12):4802–4804
8. Barbier V et al (2006) Stable Modification of PDMS Surface Properties by Plasma Polymerization: Application to the Formation of Double Emulsions in Microfluidic Systems. Langmuir 22(12):5230–5232
9. Evju JK et al (2004) Atmospheric pressure microplasmas for modifying sealed microfluidic devices. Appl Phys Lett 84(10):1668–1670
10. Langowski BA, Uhrich KE (2005) Oxygen plasma-treatment effects on Si transfer. Langmuir 21(14):6366–6372
11. BH J, Van Lerberghe LM (2000) Three-Dimensional Micro-Channel Fabrication in Polydimethylsiloxane (PDMS) Elastomer. J Microelectromech Syst 9(1):76–81

Plasma Oxidation

Definition

The treatment of a surface with a plasma containing oxygen generally performed using a vacuum chamber and an RF discharge.

Cross References

- ► Sputtering for Film Deposition

Plasma Treatment of Nanoparticles for Nanofluids

YOUNG JO KIM[1], QINGSONG YU[1,2], HONGBIN MA[2]
[1] Department of Chemical Engineering,
Center for Surface Science and Plasma Technology,
University of Missouri-Columbia, Columbia, MO, USA
[2] Department of Mechanical & Aerospace Engineering,
University of Missouri-Columbia, Columbia, MO, USA
yuq@missouri.edu

Synonyms

Diamond nanoparticles; Nanofluids; Thermal conductivity

Definition

Plasma treatment refers to the surface modification processes of materials using non-equilibrium gas plasmas. Non-equilibrium plasmas with a low degree of ionization, so-called cold plasmas or low-temperature plasmas, are mainly composed of electrons, ions, free radicals, and electronically excited atomic and molecular species. These highly reactive plasma species interact non-thermally with material surfaces, and can react with and bond to various substrate surfaces, or combine together to form an ultra thin layer of plasma coating, and consequently alter the surface chemistry and surface properties. The plasma treated nanoparticles with desired surface functionalities can strongly interact with liquid molecules and thus better disperse into the base fluid to form stable suspension.

Overview

Plasma Treatment

Non-equilibrium plasmas, i. e., low-temperature plasmas, which can be easily created by electrical discharges under reduced pressures (e. g., 10 mtorr to 10 torr), are composed of electronically excited atomic, molecular, ionic and free radical species. Depending on the plasma chemistry or gas



Plasma Treatment of Nanoparticles for Nanofluids, Figure 1 Plasma treatment effects on materials surfaces

composition, these highly reactive plasma species react with, clean, and etch surface materials, bond to various substrates, or combine to form a nanoscale thin layer of plasma coating, and consequently alter the surface characteristics. Figure 1 schematically illustrates the plasma-surface interaction results when a material substrate is exposed to low-temperature plasmas. Such plasma-surface interactions are limited to only the material surface without affecting bulk properties of the substrate materials. Since the gas phase is close to room temperature, low-temperature plasmas are suitable and very efficient in surface modification of various materials such as metals, polymers, and ceramics. Plasma treatments with and/or without deposition are currently being widely used in surface modification of various materials for improving adhesion, wettability, printability, corrosion resistance, surface etching or cleaning, and biocompatibility etc. [1–6].

Plasma treatment for material surface modification can be achieved using either simple gas plasmas without deposition or organic vapor plasmas to deposit an ultra-thin layer of plasma coatings on the surfaces. Plasma treatment possesses many unique advantageous features in surface modification of materials. Among these are:

1. plasma treatment processes are usually reliable, reproducible, non-line-of-sight, and applicable to different sample geometries;
2. plasma deposition creates an ultra-thin (in nano-scale) film coating, which are conformal, chemically inert and robust, corrosion-resistant, and strongly bonded to various substrates including both organic and inorganic materials;
3. plasma treatment is relatively inexpensive, easily operated, dry and rapid;
4. plasma treatment can tailor the surface with desired functionalities and properties through simply adjusting the plasma chemistry.

These advantageous features have been demonstrated in the continuous operation of plasma deposition and plasma etching processes in semiconductor manufacturing industry.

Recently, low-temperature plasma treatment has been explored for surface modification of various nanosized materials [7–13]. Surface functionalization of carbon nanotubes (CNTs) using plasma treatment was recently attempted by several research groups. Oxygen plasmas generated at both radiofrequency (RF) and microwave (MW) were used to treat CNTs [7, 8]. It was found that acidic groups were implemented to the CNT surfaces with improved surface wettability. Several other studies [9, 10, 13] reported the surface modification of both CNTs and nanoparticles using plasma treatment. With a simple fluidized-bed plasma apparatus, plasma coatings of 2 nm from pyrrole and 15 nm from acrylic acid were able to be uniformly deposited on 10 – 150 nm Al_2O_3 and 50 nm ZnO nanoparticle surfaces respectively [11]. It was also reported that uniform plasma coating with 1 – 3 nm thickness was achieved on carbon nanotubes with inner diameter of 20 nm [12].

Plasma treatment of nanoparticles for nanofluids can be obtained by plasma treatment using low-temperature plasmas. The diamond nanoparticle surfaces, for example, can be modified by the low-temperature plasmas of methane



Plasma Treatment of Nanoparticles for Nanofluids, Figure 2 Schematic diagram of the magnetically assisted fluidized bed plasma reactor system

and oxygen mixtures, which can improve their dispersion characteristics including dispersibility and suspension stability in water for nanofluid. Plasma treatment of diamond nanoparticles with selected plasma chemistry imparted various functional groups on the particle surfaces and tailored the surface energy to the required levels. Plasma coated nanoparticles with desired surface functionalities, e. g., polar and/or charged groups, can strongly interact with water molecules and thus better disperse into water to form stable suspension through mechanism of *electrostatic repulsion* or *steric repulsion*, or combination of both.



Plasma Treatment of Nanoparticles for Nanofluids, Figure 3 Pictorial view of the plasma reactor system

Nanofluids

Nanofluids, a concept developed by Choi at Argonne National Laboratory [14], is a new class of heat transfer fluids that are composed of suspended nano-sized metallic or nonmetallic solid particles in liquid media. Nanofluids when properly prepared display significantly enhanced heat transfer capacities relative to those of traditional heat transfer fluids. From the practical application viewpoint, the most critical concerns are the agglomeration and poor suspension stability of the metallic or non-metallic nanoparticles in a given fluid medium.

For most fine powders including nanoparticles, strong interparticle attractions tend to stick the particles into agglomerates, which make the independent dispersion of the powders difficult and, more importantly, deteriorates the final property including the thermal conductivity, viscosity, suspension stability, reliability and reproducibility. There is a great difference of density between metallic particles and fluids. As a result, the stability of the suspension of metallic particles in liquid media is usually poor, especially with the relatively high-density and large-size particles. The agglomerates of particles have a great tendency to precipitate and thus further worsen the suspension stability. The particle precipitation will not only decreases the heat transfer capacity of the nanofluids but also adversely limits the application of nanofluids in practical devices. The consequence of the agglomerate precipitation may cause clog issues of the nanofluids-based devices in which the fluids need to flow through mini and/or microchannels.

One approach to achieve the homogeneous dispersion and stable suspension of fine particles is using various dispersing agents (or surfactants) to stabilize the particle suspension via a steric and/or electrostatic repulsion [15]. It is well known that, however, the synthesis of stable dispersion of nanosized inorganic materials in liquid requires amounts of stabilizers several orders of magnitude higher than the available space on the surface of nanoparticles can accommodate [16]. The presence of excess amount of stabilizers could significantly alter the fluids characteristics, such as viscosity and thermal conductivity, and could be a big concern in the practical application of the fluids. In contrast, plasma treatment of nanoparticles provides a new promising approach in producing well-dispersed and stably suspended heat transfer nanofluids via fabrication of surface-functionalized nanoparticles without using dispersing agents (or surfactants).

Basic Methodology

Plasma Treatment

A magnetically-assisted fluidized bed plasma reactor, which is schematically shown in Fig. 2 and pictorially shown in Fig. 3, can be used to treat diamond nanoparticles (average size of 50 nm). The reactor shown in Fig. 3 is a long cylinder with an inside diameter of 2.54 cm and a length of 15.24 cm. The plasma reactor is pumped down to a base pressure less than 3 mtorr. Then, methane and oxygen mixture at various ratios is used as the plasma fuel and introduced into the reactor to a preset pressure for plasma treatment. Methane and oxygen gases both have a purity of 99.997%. The flow rates of the methane and oxygen were controlled and adjusted using needle valves. The gas pressure in the reactor was monitored using a Baratron (MKS instruments, Inc.). A radio-frequency plasma source (RFX-600, Advanced Energy Industries, Inc.) was used to ignite the plasmas for plasma treatment of the nanoparticles.

Surface Energy and Polar Interactions of Nanoparticles

The surface energy of diamond nanoparticles can be measured and calculated through Lifshitz–van der Waals/acid-base (LW-AB) approach by surface contact angle measurements using three different liquids with known surface tensions, including HPLC grade water, acetone, and hexane. The surface contact angles of the untreated and plasma treated diamond nanoparticles were determined using sessile drop contact angle measurements with a VCA 2500XE system (Advanced Surface Technologies, Inc., Billerica, MD). Before each measurement, the diamond nanoparticles were sticking to a glass slide with a piece of double-layer tape, and then pressed and smoothened using another glass slide under ~ 1.0 kg weight. For surface contact angle measurement, a sessile droplet of 0.4 μl liquid was placed on the smoothened nanoparticle surfaces to obtain an optical image of the liquid droplet. The computer user manually traced the arc that was created by the droplet and a computer program was used to calculate the contact angles of liquid on the nanoparticle surfaces. Six measurements for each sample were performed and the average number was reported in this study. The experimental error for the static contact angle measurement was within ±2.0 degree from the average value.

Plasma treatment of diamond nanoparticles can functionalize the nanopartcicles' surfaces with polar groups that have improved interactions with water molecules and thus strong affinity to water medium. Lifshitz–van der Waals/acid-base (LW-AB) approach can be used to quantify the contributions of these plasma-induced polar groups to surface energy increase of the plasma treated nanoparticles. As described by Van Oss et al. [17], the total surface energy of nanoparticle, which combined both Lifshitz–van der Waals and Lewis acid-base (LW-AB) interactions, can be expressed by following expression:

$$\gamma = \gamma^{\mathrm{LW}} + \gamma^{\mathrm{AB}} \tag{1}$$

In other words, the total potential energy of nanoparticle-liquid interactions is the sum of a Lifshitz–van der Waals interaction (γ^{LW}), which means the surface free energy (dipole–dipole and dipole-induced dipole interaction), and Lewis acid-base interaction (γ^{AB}). The Lewis acid-base interaction (γ^{AB}) for the component i is simply calculated by the geometric mean of electron acceptor (γ^{+}) and donor (γ^{-}):

$$\gamma^{\mathrm{AB}} = 2\sqrt{\gamma^{+}\gamma^{-}} \tag{2}$$

In order to calculate the surface energy of nanoparticles from our experimentally measured surface contact angle data, Young–Dupre equation can be used:

$$(1+\cos\theta)\gamma_L = 2\left(\sqrt{\gamma_S^{\mathrm{LW}}\gamma_L^{\mathrm{LW}}} + \sqrt{\gamma_S^{+}\gamma_L^{-}} + \sqrt{\gamma_S^{-}\gamma_L^{+}}\right) \qquad (3)$$

By measuring the contact angle (θ) of the diamond nanoparticles with three different liquids including at least two polar solvent with known γ_L^{LW}, γ_L^{+}, and γ_L^{-} values, the γ_S^{LW}, γ_S^{+} and γ_S^{-} of the untreated and plasma treated diamond nanoparticles were determined.

Fourier Transform Infrared Spectra (Ftir)

FTIR measurements can be used to identify and semi-quantitatively verify the surface functionalities/polar groups on diamond nanoparticles' surface induced by plasma treatment. Nicolet 6700 FT-IR Spectrometer (Thermo Scientific Inc.) was used to take Fourier Transform Infrared Spectra (FTIR) of the untreated and plasma treated diamond nanoparticles. Well-ground mixtures of nanoparticle and KBr powders (IR grade) were kept in an oven and baked at 200 °C for 48 h to get rid of moisture before performing the FTIR measurements.

Thermal Conductivity Measurement

The transient hot-wire method can be used to measure the thermal conductivity of nanofluids in this study [18]. As schematically shown in Fig. 4, the transient hot-wire measurement system contains a DC power supply, the wheatstone bridge, a data acquisition system, a nanofluid container, and a computer system to analyze the measurement data. The wheatstone bridge was constructed to determine the change of resistance. The input voltage of 5 V was supplied by an Agilent E3645A DC power supply and the output voltage was measured by a National Instruments SCXI-1000 DAQ. This data acquisition system was also used to measure the temperature of the liquid during the measurement. Each dataset was collected at a rate of 500 points per second. The relation between the output voltage and the resistance of the platinum wire is given by following Eq. (4):

$$R_{\mathrm{Pt}} = R_2\frac{\left(\frac{V_{\mathrm{OUT}}}{V_{\mathrm{IN}}} + \frac{R_3}{R_1+R_3}\right)}{\left(1-\frac{V_{\mathrm{OUT}}}{V_{\mathrm{IN}}} - \frac{R_3}{R_1+R_3}\right)} \qquad (4)$$



Plasma Treatment of Nanoparticles for Nanofluids, Figure 4 Schematics of the transient hot wire system for thermal conductivity measurement

Using the linear relation between resistance and temperature, Eq. (5) is derived.

$$T = \frac{1}{\alpha}\left(\frac{R_{\mathrm{Pt,T}}}{R_{\mathrm{Pt,T=0}}} - 1\right) \qquad (5)$$

where α is

$$\alpha = \frac{\partial \frac{R_{\mathrm{Pt}}}{R_{\mathrm{Pt,T=0}}}}{\partial T} \qquad (6)$$

Finally, thermal conductivity (k) can be found from the following liner heat source model:

$$k = \frac{q}{4\pi(T_2 - T_1)}\ln\left(\frac{t_2}{t_1}\right) \qquad (7)$$

In order to eliminate the effect of convection of the nanofluid, time interval in Eq. (7) must be within the region where thermal conduction is dominant.

The rectangular nanofluid container was designed so that the wire was at least 10 cm long and would contain about 100 ml of fluid. The fluid container was constructed out of 1.49 cm thick Plexiglas. A 1.27 cm diameter hole was drilled through the container wall in each end. A 0.0254 mm diameter pure platinum wire was attached to 12 gage copper wire. The copper wire was crimped onto each end of the platinum wire at a spacing of 10 cm. The connections between platinum and copper wires were soldered to ensure a good contact and the two copper wires were inserted into the fluid container through two rubber stoppers. The copper portion that would be in contact with



Plasma Treatment of Nanoparticles for Nanofluids, Figure 5 Calibration curve for thermal conductivity measurements of nanofluids



Plasma Treatment of Nanoparticles for Nanofluids, Figure 6 Contact angle change of diamond nanoparticles with plasma treatment time. Plasma treatment conditions were: 60 mtorr pressure, 4 W RF power

the test fluid was covered with Omegabond "100" epoxy to eliminate galvanic corrosion. A T type thermocouple was also placed in the fluid so that the temperature of the fluid could be monitored. The temperature measurements using this thermocouple gave reading with an error of $\pm 1\,^{\circ}\mathrm{C}$. To relate the resistance of the wire to temperature, the resistance of the platinum wire over a range of temperatures should be known. Therefore, HPLC grade water of varying temperatures was placed into the container and the resistances of the platinum wire and the temperature of the water were measured.

The thermal conductivity measurement of nanofluids was conducted with the fluid without any vibration. Each test was conducted at ambient condition and the data were collected for 131 s. After repeated trials it was found that the variable resistor should be balanced slightly above the known resistance of the platinum wire. Once the bridge is properly balanced the variation of voltage with time was measured and recorded. The measured thermal conductivity data was calibrated using three kinds of fluids, which was HPLC grade water, ethylene glycol and toluene. Figure 5 shows the calibration curve obtained by recording the thermal conductivity of those liquids measured. The calibration curve gave a linear calibration equation of $\lambda_{\mathrm{ref}} = \boldsymbol{a} + \boldsymbol{b}\lambda_{\mathrm{acc}}$, with $\boldsymbol{a}$ and $\boldsymbol{b}$ were 0.098 and 1.265. All the measured thermal conductivity data of nanofluids was corrected using this calibration equation.

Key Research Findings

Surface Energy of the Plasma Treated Nanoparticles

Figure 6 shows that the water surface contact angle change of plasma treated diamond nanoparticles with plasma treatment time under different plasma conditions. It can be seen that the untreated diamond nanoparticles had a water surface contact angle of 99°. In contrast, plasma treatment significantly reduced the water surface contact angle to less than 30°, which indicated very hydrophilic surfaces with increased surface energy. Using Lifshitz–van der Waals/acid-base (LW-AB) approach, Table 1 summarized the surface energy data analysis results contributed from Lifshitz–van der Waals interaction (γ^{LW}) and Lewis acid-base interaction (γ^{AB}). Evidenced from the data shown in Table 1, the significant surface energy increase of the plasma treated diamond nanoparticles resulted from the contributions from enhanced Lewis acid-base interaction (γ^{AB}), which includes γ_S^{+} and γ_S^{-}, the surface energies contributed from electron acceptors and the electron donors, respectively. This indicates that increased amount of polar functionalities on plasma treated diamond nanoparticles.

Fourier Transform Infrared Spectra

FTIR measurements were used to determine the surface functionalities induced by plasma treatment. Figure 7 presents the FT-IR spectra of untreated, plasma-treated diamond nanoparticles in plasma gas mixtures of methane and oxygen with ratios of 1 : 1 and 1 : 2. The band at $1630\,\mathrm{cm}^{-1}$ is associated with the vibrations of $\mathrm{C=C}$ bonds which is corresponding to the characteristic of diamond. A wide band with its maximum at $3400\,\mathrm{cm}^{-1}$ in the IR spectrum is due to the vibration of OH groups. The peak at $1725\,\mathrm{cm}^{-1}$ is attributed by the vibration of $\mathrm{C=O}$ bonds in weak-acid carbonyl. The increased peak

Plasma Treatment of Nanoparticles for Nanofluids, Table 1 The contact angle (θ) and its suface energy of untreated and treated ($CH_4 : O_2 = 1 : 1$, 60 mtorr, 4 W RF power) diamond nanoparticles. Surface energy of each solvent is $\gamma_l^+ = 71.99$, $\gamma_l^- = 23.46$, $\gamma_l^{LW} = 17.89$. γ_S^+ and γ_S^- are the surface energies contributed from electron acceptors and the electron donors, respectively. γ^{LW} represents Lifshitz–van der Waals interaction and γ^{AB} represents Lewis acid-base interaction

Plasma gases	Plasma time	Contact angle (cos θ)			Surface energy (mN/m)				
		Water	Acetone	Hexane	γ_S^+	γ_S^-	γ_S^{LW}	γ_S^{AB}	γ_S^{Total}
Untreated		−0.156	0.044	0.019	12.82	6.39	4.64	18.10	22.74
$CH_4 : O_2 = 1 : 1$	15 min	0.729	0.820	0.175	53.80	19.43	6.17	64.66	70.83
$CH_4 : O_2 = 1 : 1$	30 min	0.853	0.886	0.559	61.79	20.86	10.87	71.80	82.67
$CH_4 : O_2 = 1 : 1$	60 min	0.884	0.927	0.643	63.88	21.78	12.07	74.60	86.67

Plasma Treatment of Nanoparticles for Nanofluids, Table 2 FTIR peak ratios for untreated and plasma treated diamond nanoparticles. Plasma treatment conditions were: 60 mtorr pressure, 4 W RF power, 60 min treatment time

FTIR peaks	$C=O/C=C$	$OH/C=C$
(a) Untreated	0.07	2.37
(b) Plasma treated ($CH_4 : O_2 = 1 : 1$)	0.56	3.59
(c) Plasma treated ($CH_4 : O_2 = 1 : 2$)	0.82	4.01

intensity at 1725 and 3400 cm^{-1} indicates the incorporation of $C=O$ and $-OH$ polar functionalities on plasma treated nanoparticles' surfaces. Table 2 summarizes the peak area comparison of $C=O$ and $-OH$ relative to $C=C$ peaks to semi-quantitatively determine the polar groups on plasma treated nanoparticle surfaces, because the amount of $C=C$ group should be constant before and after the plasma treatment. From the Table 2, it is shown that, in comparison with the untreated control, the ratios of $C=O/C=C$ and $-OH/C=C$ groups for plasma treated diamond nanoparticles were significantly increased.

Thermal Conductivities of the Resulting Nanofluids

Effect of Oxygen/Methane (O_2/CH_4) Ratio in Plasma Gas Mixture

The untreated and plasma treated diamond nanoparticles were dispersed into HPLC grade water with the aid of mechanical agitation using a magnetic stirrer. We have reported that plasma treated diamond nanoparticles showed enhanced dispersibility and improved suspension stability in water as compared with the untreated controls [19]. After settled for one hour, the nanofluids thus prepared were characterized using the transient hot wire system shown in Fig. 4. Figure 8 shows the thermal conductivities of the nanofluids prepared using plasma treated nanoparticles with varying oxygen addition in plasma gas mixtures of methane and oxygen. When O_2/CH_4 ratio increased from 1 : 4 to 1 : 1 in the plasma gas mixture, the plasma treated nanoparticles gave increasing thermal conductivities of the resulting nanofluids with more oxygen addition. Further increasing the oxygen amount above 50% ($O_2/CH_4 = 1 : 1$), however, the thermal conductivity of the resulting nanofluids with the plasma treated nanoparticles started to decrease.



Plasma Treatment of Nanoparticles for Nanofluids, Figure 7 FTIR spectra of untreated and plasma treated diamond nanoparticles. Plasma treatment conditions were: 60 mtorr pressure, 4 W RF power, 60 min treatment time

The thermal conductivity dependence of the resulting nanofluids on O_2/CH_4 ratios in plasma gas mixture shown in Fig. 8 is consistent with the water surface contact angle results shown in Fig. 6. 1 : 1 ratio of O_2/CH_4 gave the lowest water contact angles for the plasma treated diamond nanoparticles as compared with lower or higher O_2/CH_4 ratios. The lower water surface contact angle suggested higher amount of polar functionalities were introduced onto diamond nanoparticles' surfaces through



Plasma Treatment of Nanoparticles for Nanofluids, Figure 8 The effects of O_2/CH_4 ratio used for plasma treatment on thermal conductivity of the resulting nanofluids with addition of 0.15 Vol.% plasma treated diamond nanoparticles into water. The thermal conductivities were measured after 1.0 hour settling time. Plasma treatment conditions were: 60 mtorr pressure, 4 W RF power, 60 min treatment time



Plasma Treatment of Nanoparticles for Nanofluids, Figure 9 Plasma treatment time effects on thermal conductivity of the resulting nanofluids with addition of 0.15 Vol.% plasma treated diamond nanoparticles into water. The thermal conductivities were measured after 1.0 h settling time. Plasma treatment conditions were: 60 mtorr pressure, 4 W RF power, 1 : 1 ratio of CH_4 : O_2

plasma treatment. As a result, a better dispersion of the nanoparticles in water medium was achieved and so was the thermal conductivity of the resulting nanofluids. It is believed that plasma treatment using higher amount of oxygen addition over 1 : 1 ratio of O_2/CH_4 could very likely result in a pronounced surface etching effect and etch the surface polar surface functionalities away.

Effect of Plasma Treatment Time

The water surface contact angle measurement and thermal conductivity measurement showed that plasma treatment of diamond nanoparticles with 1 : 1 ratio of O_2/CH_4 gave rise to the best surface wettability and the highest thermal conductivity of the resulting nanofluids. Using plasma gas mixture with a fixed O_2/CH_4 ratio of 1 : 1, therefore, effects of plasma treatment time on thermal conductivities of the resulting nanofluids were examined. In Fig. 9, the effective thermal conductivities of the resulting nanofluids at both 20 °C and 50 °C were plotted against the plasma treatment time for diamond nanopaticle treatment using plasma gas mixture of $O_2/CH_4 = 1:1$. With plasma treatment time varied from 15 to 120 min, plasma treatment of diamond nanoparticles for 60 min gave a nanofluids with the maximum thermal conductivity at both temperatures. The results in Fig. 9 are also consistent with the water surface contact angle measurement results shown in Fig. 6. The thermal conductivity decrease using plasma treatment time longer than 60 min could be due to the over treatment effects often observed in plasma treatment processes.

Stability of the Resulting Nanofluids

We have recently reported that plasma treatment of diamond nanoparticles significantly improved their suspension stability in water [19]. After 45 day sediment test, the nanofluids using plasma treated diamond nanoparticles didn't give any phase separation, while the nanofluids using untreated controls showed clear phase separation of water. In this study, the settling time dependence of the nanofluid thermal conductivity was monitored and the data are shown in Fig. 10. It can be seen that the nanofluids using untreated nanoparticles showed a decreasing trend with settling time. After 120 h settling, the effective thermal conductivity reached to ~ 1.0, i. e., the same as pure water. In contrast, the nanofluids prepared using plasma treated diamond nanoparticles showed very little change in the effective thermal conductivity with settling time.

From Fig. 10, it was noted that, with the same amount nanopartcile addition of 0.15 Vol.%, nanofluids using plasma treated nanoparticles gave much higher thermal conductivity than that using untreated nanoparticles. It was usually observed that the thermal conductivity of nanofluids is proportional to the volume fraction of nanoparticles added in base liquid media [20]. Results shown in this study suggest that plasma treatment of diamond nanoparticles could well disperse the nanoparticles in water and thus increase the thermal conductivity of the resulting nanofluids. It is suspected that the enhanced interfacial interactions between nanopaticles – base water fluids due to introduction of polar surface functionalities by plasma treat-



Plasma Treatment of Nanoparticles for Nanofluids, Figure 10 Thermal conductivity change of the resulting nanofluids (with 0.15 Vol.% diamond nanoparticle addition in water) with settling time. Plasma treatment conditions were: 60 mtorr pressure, 4 W RF power, 60 min treatment time, 1 : 1 ratio of CH_4 : O_2

ment could be another important factor contributed to the thermal conductivity increase of the resulting nanofluids.

Future Directions for Research

Plasma treatment provides a new approach to functionalize nanoparticle surface for heat-transfer nanofluid preparation without using stabilizing agents. More experimental investigation is very necessary to optimize the plasma treatment process in term of plasma chemistry, plasma operating conditions, and proper plasma apparatus design. As pointed out in this paper, besides nanoparticle concentration, the enhanced interfacial interactions between nanopaticles – base fluids could be another important factor that contributed to the thermal conductivity increase observed in heat-transfer nanofluids. A detailed characterization of the nanofluids with the aid of theoretical simulations will help us to understand the fundamental mechanisms for the observed heat-transfer enhancement.

Cross References

- ► Plasma Surface Modification
- ► Surface Tension Measurements
- ► Surface Conductivity Measurement

References

1. Shohet JL (1991) Plasma-Aided Manufacturing. IEEE Transf Plasma Sci 19:725–733
2. Yasuda HK (2005) Luminous chemical vapor deposition and interface engineering. Dekker, New York
3. Yu QS, Deffeyes J, Yasuda HK (2002) Corrosion protection of ion vapor deposition (IVD) Al-coated Al alloys by low-temperature plasma interface engineering: Part III: DC Cathodic Polymerization in a Closed Reactor System. Prog Org Coat 44:37–47
4. Yu QS, Reddy CM, Moffitt CE, Wieliczka DM, Johnson R, Deffeyes J, Yasuda HK (2001) Improved Corrosion Protection of Al Alloys by System Approach Interface Engineering: Part IV – Spray Primer Coated Al Alloys. Corrosion 57:802–814
5. Chu PK, Chen JY, Wang LP, Huang N (2002) Plasma-surface modification of biomaterials. Mater Sci Eng R36:143–206
6. d'Agostino R (1990) Plasma Deposition, Treatment, and Etching og polymers. Academic Press, Boston
7. Bubert H, Haiber S, Brandl W, Marginean G, Heintze M, Bruser V (2003) Characterization of the uppermost layer of plasma-treated carbon nanotubes, Diamond and Related Materials 12(3–7):811–815
8. Chirila V, Marginean G, Brandl W (2005) Effect of the oxygen plasma treatment parameters on the carbon nanotube surface properties Sur Coat Techn 200:548–551
9. Khare BN, Wilhite P, Quinn RC, Chen B, Schingler RH, Tran B, Imanaka H, So CR, Bauschlicher CW Jr, Meyyappan M (2004) Functionalization of Carbon Nanotubes by Ammonia Glow-Discharge: Experiments and Modeling. J Phys Chem B 108(24):8166–8172
10. Khare BN, Wilhite P, Meyyappan M (2004) The fluorination of single wall carbon nanotubes using microwave plasma. Nanotechnology 15(11):1650–1654
11. Shi D, He P, Lian J, Wang L, van Ooij WJ (2002) Plasma deposition and characterization of acrylic acid thin film on ZnO nanoparticles. J Mater Res 17(10):2555–2560
12. Shi D, Lian J, He P, Wang LM, van Ooij WJ, Schulz M, Liu Y, Mast DB (2002) Plasma deposition of ultrathin polymer films on carbon nanotubes. Appl Phys Lett 81(27):5216–5218
13. Shi D, Wang SX, van Ooij WJ, Wang LM, Zhao JG, Yu Z (2001) Uniform deposition of ultrathin polymer films on the surfaces of Al_2O_3 nanoparticles by a plasma treatment. Appl Phys Lett 78(9):1243–1245
14. Choi US (1995) Enhancing thermal conductivity of fluids with nanoparticlers. In: Siginer DA, Wang HP (ed) Developments and Applications of Non-Newtonian Flows. FED-Vol. 231/Mid-Vol. 66, ASME, New York
15. Toshima N (2003) Metal nanoparticles for catalysis. In: Liz-Marzan LM, Kamat PV (ed) Nanoscale materials. Kluwer Academic, Boston
16. Hilgendroff M, Giersig M (2003) Assemblies of magnetic particles – Synthesis and production. In: Liz-Marzan LM, Kamat PV (eds) Nanoscale materials. Kluwer Academic, Boston
17. van Oss CJ (2003) Long-range and short-range mechanisms of hydrophobic attraction and hydrophilic repulsion in specific and aspecific interactions. J Mol Recognit 16:177–190
18. Corey W (2006) Experimental Investigation of Nanofluid Oscillating Heat Pipes. M.S. thesis, University of Missouri, Columbia
19. Yu QS, Kim YJ, Ma HB (2006) Plasma treatment of diamond nanoparticles for dispersion improvement in water. Appl Phys Lett 88:231503/1–3
20. Xie H, Lee H, Youn W, Choi M (2003) Nanofluids containing multiwalled carbon nanotubes and their enhanced thermal conductivities. J Appl Phys 94:4967–4971

Plastic

► Polymer

Plasticity

► Viscosity

Platinum Resistance Thermometer

► Resistance Temperature Detectors

Plug Flow

► Taylor Flow in Microchannels

Pneumatic Valves

DANIEL IRIMIA
Massachusetts General Hospital, Harvard Medical
School, Boston, VA, USA
dirimia@partners.org

Synonyms

Elastomeric valve

Definition

Mechanical structure designed to control the flow of fluids in one channel through changes in pressure in a second channel from which it is separated by a membrane or equivalent structure.

Overview

Pneumatic valves rely on the deformation of a membrane, or other thin structure, by pressure, with the end result of altering the flow of a fluid in a channel. The size of the pneumatic valves is usually comparable to the size of the channels they control and consequently these valves are easy to integrate in the overall design of the microfluidic chips. Although several designs have been proposed over time, using different materials, the most successful valves in terms of applications have been the valves using elastomeric materials. Elastomeric materials are easily deformable, and are already widely used for microfluidic applications, making them ideal for developing pneumatic valves.

In the simplest design, the deformation of a circular membrane under uniform pressure on one side can be described by the following equation:

$$\Delta x = \Delta P \frac{3r^4}{16t^3} \cdot \frac{(1-\nu^2)}{E}$$

where Δx is the deformation of the membrane at its center, ΔP is the pressure difference on the two sides of the membrane, E and ν are characteristics of the membrane material (the Young modulus and the Poisson's ratio, respectively), and r and t are dimensional characteristics of the membrane (the radius and the thickness of the circular membrane, respectively). Although for more complicated shapes of the membrane the dependence of deformation to actuation pressure has to be calculated numerically using specialized software, the formula for the circular membrane already suggests a very important impact from the valve dimensions on valve functionality.

Basic Methodology

Pneumatic valves are fabricated using standard microfabrication and assembly technologies. The membrane of the valve can be one uniform film of elastomeric material, or can have microchannels already imprinted on one side (see ► microfabrication techniques). The actuation chamber is usually in a separate layer, either elastomer or a rigid material. The layer including the controlled microchannel, the membrane, and the layer containing the actuation chamber are then bonded together using standard techniques (e. g. oxygen plasma for elastomer and glass layers see ► microfluidic assembly and microfabrication techniques). The decision for the precise design and integration of pneumatic devices into the manufacturing of microfluidic devices is usually based on several criteria, each of which may have different weight in different applications. The first criterion is usually the compatibility of the technologies for the valve with the rest of the manufacturing. Some valve require the use of positive resist and overflow at higher temperature, other require glass etching, and some can be manufactured using only negative epoxy resist (SU8). Most of the pneumatic valves require the precise aligning and bonding of two layers of elastomeric material. The second criterion is the nature of the fluid to be handled. While most of the elastomeric materials are compatible with water solutions, only few materials could handle solvents and more aggressive chemicals. The third criterion is the number and size of the valves on one device. Smaller valve size is possible when controlling single rounded channels, while larger valves could incorpo-



Pneumatic Valves, Figure 1 Schematics of pneumatic valves. (a) Pneumatic valve using the compression of a rounded channel in the network layer. (b) A bulging membrane can be used to control flow in a rounded channel. (c) Negative pressure can deform a membrane and open communication in a network layer. (d) A microstructured membrane could be used to control flow in a complex network layer. (e) In a single layer valve the control channels are placed on the side of the network layer

rate more features or control multiple channels at the same time. Finally, valves that are normally closed or normally open have been described, and the choice depends on the functionality and actuation pressure available for operating the valves.

Key Research Findings

Several approaches have been described for the practical implementation of the pneumatic valves in microfluidic systems. In general, the control and network channels (Fig. 1) are placed in different layers and the membrane structure performing the actuation is in between the layers. Both higher pressure (Fig. 1a,b,e) and vacuum (Fig. 1c,d) have been use to control the fluid in the network layer. In the case of vaccum-actuated valves, the membrane could seal channels in the network layer in the absence of the actuation pressure, only by elasticity of the membrane pressing against the valve seat (Fig. 1c,d).

While smaller aspect ratios of the network layer usually lead to smaller dead volumes for the valves (Fig. 1), various designs that allow the control of higher aspect ratios has been described, especially for applications that require the transport of larger cells or particles (Fig. 1b-e). Pneumatic valves with rounded (Fig. 1a–c) as well as rectangular (Fig. 1d–e) channels in the network layer have been implemented. The control layer could be above or bellow the network layer (Fig. 1a–d), and at least in one implementation the control and network channels were implemented at the same level (Fig. 1 e). Hierarchical arrangements of pneumatic valves in microfluidic devices, where some microscale valves are used to control the operation of other microscale valves, have been demonstrated as a way to reduce the number of control lines and increase the sophistication of actuation patterns.

For most of the designs, the membrane is relatively flat and feature-less and in some implementations it can be different material from the control and network layer materials (Fig. 1c). However, the addition of microstructures to the valve membrane (Fig. 1d) has been demonstrated to result in higher degree of complexity of the functionality that can be achieved using pneumatic actuation.

Future Directions for Research

There are two main challenges for the development of applications using pneumatic valves. The first one has to do with the choice of materials for the valve. Although elastomeric materials are very good for prototyping, scaling up and reducing the fabrication costs would require the use of polymeric materials. Either these new materials would have to have comparable mechanical properties with the current elastomers, or different designs would have to be imagined. The second challenge is related to the control system and pressure generation that is usually off chip. Integrating these on the chip or at least standardizing and miniaturizing these would be needed for compact, reliable miniaturized devices.

Cross References

- ► Capillary Force Valves
- ► Control of Microfluidics
- ► Digital Microfluidics
- ► Electrochemical Valves
- ► Electromagnetic Valves
- ► Electrostatic Valves
- ► Fabrication of 3D Microfluidic Structures

- ► Volume and Finite Difference Method for Modeling and Simulation
- ► Fluid Metering
- ► Lab-on-a-chip (General Philosophy)
- ► Lab-on-chip Devices for Particle and Cell Separation
- ► Membrane Actuation for Micropumps
- ► Microactuators
- ► Microfluidic Assembly
- ► Microfluidic Circuits
- ► Peristaltic pumps
- ► Piezoelectric Valves
- ► Thermopnuematic Valves
- ► Water Management in Micro DMFCs

References

1. Grover WH, Skelley AM, Liu CN, Lagally ET, Mathies RA (2003) Monolithic membrane valves and diaphragm pumps for practical large-scale integration into glass microfluidic devices. Sensors Actuators B 89(3):315–323
2. Hosokawa K, Maeda R (2000) A pneumatically-actuated three-way microvalve fabricated with polydimethylsiloxane using the membrane transfer technique. J Micromech Microeng 10(3):415–420
3. Irimia D, Toner M (2006) Cell handling using microstructured membranes. Lab Chip 6(3):345–52
4. Li N, Hsu CH, Folch A (2005) Parallel mixing of photolithographically defined nanoliter volumes using elastomeric microvalve arrays. Electrophoresis 26(19):3758–3764
5. Studer V, Hang G, Pandolfi A, Ortiz M, Anderson WF, Quake SR (2004) Scaling properties of a low-actuation pressure microfluidic valve. J Appl Phys 95(1):393–398
6. Sundararajan N, Kim DS, Berlin AA (2005) Microfluidic operations using deformable polymer membranes fabricated by single layer soft lithography. Lab Chip 5(3):350–354
7. Unger MA, Chou HP, Thorsen T, Scherer A, Quake SR (2000) Monolithic microfabricated valves and pumps by multilayer soft lithography. Science 288(5463):113–116

Poiseuille Coefficient

Definition

Poiseuille coefficient determines a gas flow induced by a pressure gradient.

Cross References

- ► Gas Flow in Nanochannels
- ► Micro- and Nanoscale Gas Dynamics

Poiseuille Single Phase Gas Flows

- ► Pressure-Driven Single Phase Gas Flows

Polyclonal

Definition

Polyclonal antibodies are antibodies that are derived from several different t B-cell lines. The selections of antibody molecules bind to different parts of the antigen, with different binding affinities. Within a polyclonal sample, some of the antibodies will be specific for the antigen with which the animal was immunised. The rest of the antibodies have been obtained from meetings with other foreign antigens that the animal has been exposed to through its life time.

Poly(dimethylsiloxane) (PDMS)

Definition

PDMS is popular polymer in the microfluidics community; often used for rapid fabrication of microchannel structures. PDMS is optically-transparent and is generally considered to be inert, non-toxic and non-flammable. PDMS is formed by mixing a *base* with a *curing agent* (typically mixed in a 10 : 1 ratio, but this can vary depending on the desired stiffness of the resultant polymer) and curing in a vacuum-oven for several hours. Cured PDMS will form a reversible-bond with various surfaces (glass microscope slides, for example). Irreversible sealing can be achieved by exposing the PDMS to oxygen plasma prior to bonding.

Cross References

- ► Temperature Effects on the Zeta Potential

Polydispersity

Synonyms

Polydispersity index; Mw/Mn

Definition

The distribution of molecular weights in a given polymer sample.

Cross References

- ► Polymer Synthesis within Microfluidic Reactor

Polydispersity Index

► Polydispersity

Polyelectrolyte

Definition

A species (for example, a colloidal particle or a flexible chain) that is partially ionizable when placed in solution. The polyelectrolyte dissociates into a macroion and counterions.

Cross References

► Electrokinetic Flow and Ion Transport in Nanochannels
► Electrophoresis

Polyelectrolyte Patterning Technique

► Surface-Charge Patterning Techniques

Polymer

Synonyms

Plastic; Organic material

Definition

A polymer is a material composed of large macromolecules. These macromolecules are formed by chains of hundreds or thousands of connected (polymerized) monomer molecules. The three main classes of polymers are thermoplastics, elastomers and thermosets. They differ in the degree of cross-linking of their macromolecules – from no cross-linking (thermoplastics) to moderate cross-linking (elastomers, rubbers) to high cross-linking (thermosets). Thermoplastics commonly used in microfluidics include materials like polymethylmethacrylate (PMMA), polycarbonate (PC), polyethylene terephthalate (PET) or cyclic olefin copolymers (COC). Silicones (like polydimethylsiloxane, PDMS) are a typical class of elastomers. Thermosets include photoresist materials like SU-8 and others.

Cross References

► Glass-Polymer-Bonding

Polymer Casting

► Micromolding

Polymer Electrolyte Membrane Fuel Cells

► Microstructured Hydrogen Fuel Cells

Polymerization Reaction in Microreactor

► Polymer Synthesis within Microfluidic Reactor

Polymer Monoliths

► Stationary Phases in Microchannels

Polymer Replication

► Micromolding (Injection and Compression Molding)

Polymer Solutions

► Non-Newtonian Fluids in Microfluidics

Polymer Synthesis within Microfluidic Reactor

MASAYA MIYAZAKI[1,2], HIDEAKI MAEDA[2,3]
[1] Nanotechnology Research Institute, National Institute of Advanced Industrial Science and Technology (AIST), Tosu, Japan
[2] Department of Molecular and Material Science, Interdisciplinary Graduate School of Engineering Sciences, Kyushu University, Kasuga, Japan
[3] CREST, Japan Science and Technology Agency (JST), Kawaguchi, Japan
m.miyazaki@aist.go.jp, maeda-h@aist.go.jp

Synonyms

Synthesis of polymer molecules using microfluidics; Microfluidic reactor for polymer synthesis; Polymerization reaction in microreactor

Definition

Polymer synthesis requires strict control of reaction conditions such as temperature, reaction time, and mixing of reagents. Microfluidic reaction systems enable efficient mixing and rapid heat exchange. Moreover, a laminar stream in a microfluidic channel enables control of the resulting shape of a molecule. These features of microfluidic reaction systems are suitable for polymer synthesis.

Overview

Reactions involved in chemical polymerization should be highly controlled because polymer properties such as ►average molecular weight, molecular weight distribution, and size and shape of particles strongly affect the functions of polymer materials. When using polymers of less well known functions, the molecular weight or size and shape should be carefully selected, and the molecular weight or size distribution should be controlled to be as narrow as possible. Such requirements could be satisfied by utilizing microfluidic systems. Microfluidic reaction systems have several distinctive features. One of the unique features is the ability to control molecular weight distribution and simple control of the molecular weight of linear polymers. In addition, microfluidic systems enable efficient emulsification with controlled size and shape. Present-day investigations on polymer materials are directed towards the development of novel functional substances by using high-throughput and combinatorial synthesis methods. The microdevices developed for this purpose should be simple, controllable, and capable of continuous combinatorial synthesis process with high-throughput screening systems for polymer material libraries. Moreover, there is a requirement for accelerated multi-parameter optimization of reaction conditions. In this article, efforts towards the development of microreactors for linear polymer synthesis and preparation of complicated polymer particles are summarized.

Synthesis of Linear Polymers in Microfluidic Reactor

Microreaction systems involve microreaction apparatuses that enable high controllability of chemical reactions. Such controllability results from efficient heat transfer, mass transport, and/or a larger surface/interface area. Recent studies have shown the potential benefits of using microfluidic reactors for various chemical reactions. Reactions using micromixing devices give better results than batchwise reactions. This is because a micromixer enables rapid mixing and therefore yields excellent controllability of rapid reactions.

Application of microreaction technology for linear polymer syntheses was initially performed by several researchers, but the field is still in its infancy. Most of the work utilized a combination of micromixing and reaction parts.

The most popular polymerization method is ►radical polymerization. Wu et al. performed radical polymerization by using a chip-type microreactor [1]. The system is composed of a microstirrer mixer connected to a microchannel reaction part. The molecular mass of the polymer produced is governed by the flow rate or polymerization time. The monomer conversion agrees well with the bulk reaction kinetics reported in the literature. The reactor is convenient and inexpensive to manufacture, with a versatile design that can be reconfigured and prototyped in less than a day. The radical polymerization technique was also applied for ►block copolymerization of poly[(ethylene oxide)-*block*-(2-hydroxypropyl methacrylate)] [2]. A series of well-controlled polymerizations was carried out at different pumping rates or reaction times with a constant ratio of monomer to initiator. The stoichiometry of the reactants was also adjusted by varying relative flow rates to change the reactant concentrations. Another example of radical polymerization in a microreactor was described by Iwasaki and Yoshida, who reported a microreactor consisting of commercially available micromixers (T-shape, 500 μm internal diameter) connected with capillary tubes (500 μm internal diameter) [3]. Thermal decomposition of 2,2-azobis(isobutylronitrile) (AIBN) was examined first and subsequent polymerizations of butyl acrylate (BA), benzyl methacrylate (BMA), methyl methacrylate (MMA), vinyl benzoate (VBz), and styrene (St) were performed. The microreactor was quite effective in controlling the molecular weight distribution for highly exothermic reactions (BA, BMA, and MMA) but not so effective for less thermic polymerizations (VBz and St).

Cationic polymerization was performed in a microreaction system consisting of two micromixers connected by microcapillaries [4]. A method that used irreversible generation and accumulation of highly reactive cations in the absence of nucleophile was applied for polymerization. The molecular weight distribution was controlled by extremely fast micromixing, and the resulting polymer could be used for follow-up reactions.

The benefit of microreaction systems is not limited to cationic or radical polymerization. Amino acid polymerization using α-amino acid *N*-carboxyanhydride (NCA) yielded better molecular weight distribution when performed in a microreactor [5]. Also, the average molecular weight could be controlled by changing the flow rates.

Synthesis of dendric molecules has also been performed. Chang and coworkers synthesized ethylenediamine-cored polyamidoamine (PAMAM) dendrimer using an interdigital micromixer [6]. Using this method, synthesis of generation two through generation five PAMAM dendrimer was confirmed by microchip capillary zone electrophoresis. Furthermore, the synthesized polyamide dendron was deposited onto a functionalized glass surface through the formation of amide bonds using a facile coupling procedure via a microreactor. The dendron deposition process involved two major steps: functionalization of the native glass surface using 3-aminopropyl triethoxysilane, and coupling of the synthesized polyamide dendron with the aminosilanized surface.

Compared with conventional synthesis methods, the microreactor provides better yield and selectivity, and a considerably faster synthesis rate. Nanostructured polyamide G1 dendron thin films could be deposited in minutes using an impinging flux from this microreactor.

Not only have efforts been focused on the synthesis of linear or branched polymer molecules, but theoretical studies have also been performed. Serra et al. conducted numerical simulations of free radical polymerization in microfluidic devices [7]. Three microfluidic devices were modeled: two interdigital multilamination micromixers with a long and short focusing section, respectively, and a simple T-junction followed by a microtube reactor together considered as a bilamination micromixer with a large focusing section. The simulations showed that in spite of the heat released by the polymerization reaction, the thermal transfer in such microfluidic devices was high enough to ensure isothermal conditions. Moreover, for low radial ►Peclet number, microfluidic devices with a large focusing section could achieve better control over the polymerization than a laboratory-scale reactor as the ►polydispersity index obtained was very close to the theoretical limiting value. Serra et al. [7] concluded that the reactive medium cannot be fully homogenized by the diffusion transport before leaving the system resulting in a high polydispersity index and a loss in the control of polymerization as the characteristic dimension of the microfluidic device increases, i. e. for high radial ►Péclet number.

Complicated Polymer Particle Synthesis

There is an increasing demand for polymer particles by industry, particularly for painting formulations and drug delivery applications. A microfluidic reaction system provides superior controllability of fluid because the flow forms simple laminar streams. Thus, efforts have been exerted on polymer particle synthesis using microfluidics because of the unique capacity to generate microdroplets with very narrow size distributions. Polymer particles by simple emulsification have been widely studied and well summarized in other entries. Here, we focus on polymer synthesis by complicated emulsification. Nie et al. reported a novel approach to continuous and scalable production of core–shell droplets and polymer capsules in microfluidic devices [8]. They used laminar flow of three immiscible liquids, aqueous SDS, monomer, and silicon oil, in a microfluidic system. The described method is also useful for the synthesis of polymer particles with nonspherical shapes. They used capillary instability-driven break-up of a liquid jet formed by two immiscible fluids. Precise control of emulsification of each liquid allowed production of highly monodispersed core–shell droplets with a predetermined diameter of cores and thickness of shells. They also achieved control over the number of cores per droplet and the location of cores in a droplet. The authors carried out fast throughput photopolymerization of the monomeric shells and obtained polymer particles with various shapes and morphologies, including spheres, truncated spheres, hemispheres, and single and multicore capsules. Photolithography was also applied for the synthesis of polymer particles. Dendukuri et al. reported a one-phase method using a T-junction microchannel to create solid disk- and plug-shaped particles (Fig. 1) [9]. Snap-off at the junction yielded plugs containing Norland optical adhesive (NOA) 60, a photopolymerizable resin. When an ultraviolet (UV) beam was shone on the plug in the narrow channel, a plug structure was captured, but if the plug was allowed to expand laterally and then polymerized, a disk was formed. Because of the small dimensions of the plugs and disks, the photopolymerization occurred in less than 1 s, using only 3 $\mathrm{J\,cm^{-2}}$ of energy. They also developed an evolutionally advanced microfluidic system by combining the advantages of microscope projection photolithography and microfluidics to continuously form morphologically complex or multifunctional particles down to the colloidal length scale (Fig. 2) [10]. Exploiting the inhibition of free radical polymerization of diacrylate monomers near polydimethylsiloxane (PDMS) surfaces, they were able to repeatedly pattern and flow rows of particles in less than 0.1 s, affording a throughput of near 100 particles per second using the simplest of device designs. Polymerization was also carried out across laminar, co-flowing streams to generate ►Janus particles, which are chemically biphasic particles. They synthesized a Janus polymer by using co-flowing laminar streams of monomer, one of which contained a rhodamine-labeled crosslinker, and forming particles across this interface. The relative proportions of Janus particles could be easily tuned. This new high-throughput technique offers unprecedented control over particle size, shape, and anisotropy.



Polymer Synthesis within Microfluidic Reactor, Figure 1 (**a**)–(**e**) Scanning electron microscopy images of polymer microbeads obtained by polymerizing TPGDA in droplets obtained in regimes A, B, C, D, respectively, after removing a SO core. Inset: cross-section of the core–shell particle. (**f**) Cross-section of a polyTPGDA particle with three cores obtained by polymerizing core–shell droplets with three cores. The particle is embedded in epoxy glue. Scale bar is 40 μm. Reproduced from [9]



Polymer Synthesis within Microfluidic Reactor, Figure 2 Scanning electron microscope images of particles. Microparticles formed using a ×20 objective (except (**d**), which was formed using a ×40 objective) were washed before being observed. The scale bar in all of the figures is 10 μm. (**a**)–(**c**) Flat polygonal structures that were formed in a 20 μm high channel. (**d**) A colloidal cuboid that was formed in a 9.6 μm high channel. (**e**), (**f**) High-aspect-ratio structures with different cross-sections that were formed in a 38 μm high channel. (**g**)–(**i**) Curved particles that were all formed in a 20 μm high channel. The inset shows the transparency mask feature that was used to make the corresponding particle. Reproduced from [10]



Polymer Synthesis within Microfluidic Reactor, Figure 3 Mechanism of NCA polymerization initiated by a base such as tertiary amine. Reproduced from [5]

Basic Methodology

Basically, a microreaction system for polymerization reaction consists of a microfluidic device for mixing or droplet formation followed by microchannels as reaction parts. In this article, linear amino acid polymerization reaction is used as a basic example of polymer synthesis using microfluidic devices. Amino acid polymer was synthesized using the NCA method. This reaction is an anion ring-opening reaction which consists of two stages (Fig. 3): initiation by tertiary amine, and propagation of the polymer chain. The initiation and NCA anion attack are known to be relatively fast reactions. It is assumed that these steps are important in controlling polymerization of NCA. However, control of polymerization would be difficult in conventional batchwise systems due to the tendency to locally generate concentration gradients of the reagents. As a remedy, strict reaction control of a microreaction system can be employed to synthesize biopolymers.

Preparation of Microreaction Device

Generally, mixing is extremely important in chemical reactions. When using microreactors for chemical reactions, micromixers are often incorporated in the microreactor for effective mixing. Mixing of the monomer and base principally depends on diffusion through the interface of the two solutions. A multilayered micromixer increases the interface area of two fluids and shortens the diffusion length, resulting in an increase in the mixing efficiency of reactants. Also, a characteristic feature of this mixer is that mixing efficiency increases with a decrease in flow rate. In order to gain long residence time required for polymerizations, low flow rate should be used in the microfluidic system; therefore, a multilayered micromixer was employed for NCA polymerizations in a microfluidic system.

Figure 4 shows the setup of a microreaction system. The micromixer was attached to a PTFE microtube (length = 500 cm) and served as a polymer-propagating region. The volume of fluid channel of the micromixer was 4.4 μl, and the total inner product volume of this microreactor corresponded to 250 μl. In the microreactor setup, monomer and initiator solutions were each charged into a 1 ml Hamilton gastight syringe. The solutions were supplied to the microreactor using a syringe pump with a parallel syringe holder, which enable identical pumping rates so that the final mixed solution would have a constant reagent concentration.

Polymerization Reaction

Polymerizations were performed in DMF and initiated by triethylamine. Both solutions of monomer and base were separately introduced into the microreactor (Fig. 4) using a syringe pump. The resulting mixture was heated at



Polymer Synthesis within Microfluidic Reactor, Figure 4 Microreaction system used in this study. The system consists of a PDMS micromixer and PTFE microtubes. Two syringes containing reagents were coupled on the PDMS micromixer by PTFE microtubes (diameter = 250 μm, 10 cm). The PDMS micromixer was attached to a PTFE microtube (diameter = 250 μm, 500 cm) and served as a reaction region. The mixer and reaction region were kept at 30 °C in a water bath. Reproduced from [5]

100 °C for termination, then deprotection of the side-chain protective group was performed using HBr in AcOH. The sample was analyzed by gel filtration chromatography after dialysis against water to remove HBr. Figure 5 shows the gel filtration chromatography data for the poly(Lys) produced using the microreactor at different flow rates. The molecular weights of the respective samples regularly increased with a decrease in flow rates, that is, as a consequence of the increase in time required for polymerization to occur. It was found that the molecular mass of the polymer produced using the microreactor is simply governed by the flow (pumping) rate. Also, polymers produced by the microreaction showed narrower molecular weight distribution than that of macroscale reaction in homo- and copolymers (Fig. 6).

Key Research Findings

Many polymers with interesting functionalities have been developed and applied in various fields. At present, a rapid and combinatorial synthesis system with highly controllable polymerization reaction is much required. However, it is generally difficult to control polymerization reactions in conventional batchwise systems. Synthesis of polymer molecules using a microreactor enables strict control of chemical reactions which serves as a model of polymer synthesis. The performance of a microreaction system for polymerization was compared with that of a conventional batchwise system by analyzing the properties of the obtained polymers. In linear polymer products, the M_w/M_n values of the polymers synthesized by the batchwise system obviously increased with increasing concentration of monomer. In contrast, the M_w/M_n values in the microfluidic system remained low with high monomer concentrations [5]. It was demonstrated that the microreactor provided high controllability of polymerization even at concentrations that produced poor control of molecular weight distribution in the case of the batch reaction. The controllability of molecular weight distribution is governed by several factors. The first factor is the mixing efficiency of reactants. In the batchwise system, an increase in reagent concentration tends to decrease the mixing efficiency of reagents, and leads to generation of local concentration gradients of the reagents. In addition, the viscosity rise observed for highly concentrated monomer solutions will cause a decrease in the efficiency of mixing based on turbulent flow in the batchwise system. Consequently, it is assumed that such a decrease in mixing efficiency induces a broadening of the molecular weight distribution. In contrast, it is hypothesized that effective mixing of reactants by the attached micromixer in the microfluidic system enables high control of molecular weight distribution. Not only was linear polymer synthesis performed in the microfluidic reactor, but also synthesis of dendrimer molecules. Although still in their infancy, microfluidic systems open the use of microreactors for branched polymers. Overall, the usefulness of microreactors in controlling the reaction of linear and branched polymer synthesis has been demonstrated. For polymer particle synthesis, microfluidic reaction systems show several



Polymer Synthesis within Microfluidic Reactor, Figure 5 Gel filtration chromatography analysis of poly(Lys) produced by the microreactor. The polymerizations were conducted with 0.1 M monomer and 0.01 M initiator for 1, 5, 10, and 100 min of reaction times corresponding to 250, 50, 25, and 2.5 μl/min flow rates, respectively. Reproduced from [5]



Polymer Synthesis within Microfluidic Reactor, Figure 6 Comparisons of polymer properties in batchwise (circle) and microfluidic (triangle) systems at various monomer concentrations. (**a**) ►number average molecular weight (M_n) and (**b**) polydispersity (M_w/M_n) of the obtained polymers against concentrations of NCA. Polymerizations were carried out for 200 min. Reproduced from [5]

advantages over the conventional reaction systems. These benefits arise from the small dimensions of microdevices which provide predictable thermal and mass transportation properties and unique control over the fluid structure. Enhanced transport characteristics of microreactors allow more precise synthesis of polymers compared to traditional batch reactors. Perhaps most importantly, extreme fluid controllability in a laminar flow system enables synthesis of particles with unique shapes not accessible by other methods. Core–shell type polymers and nonspherical polymers were prepared by controlling the fluidic behavior in microchannels. Also, solid, hollow, and multicored asymmetric and irregularly shaped polymer microparticles as well as membranes and fibers can all be produced with microfluidic devices. These particles are generally monodispersed, and the sizes may be tuned from a few micrometers to hundreds of micrometers, depending on the specific device geometry and flow parameters. The design of fluidic systems therefore becomes quite important. Numerical simulation is useful in designing microreaction devices. Likewise, reproducibility of these particles is quite high when performing the reaction using the same microreaction apparatus because of the simple operation of the reactor and strict control of the reaction conditions provided by the system. The reaction does not require special techniques as in batchwise synthesis. This feature is quite advantageous for production of polymer particles by numbering-up. Utilizing the principle of shape control by fluidic behavior, the elegant technique was applied to control the shape of polymers. Microscope projection photolithographic synthesis of particles is a novel particle formation method [8, 9]. This method enables continuous-flow synthesis of particles with complicated shapes. Polymerization was also carried out across laminar, co-flowing streams to generate Janus particles containing different chemistries, whose relative proportions could be easily tuned. This new high-throughput technique offers unprecedented control over particle size, shape, and anisotropy.

To summarize, polymer synthesis in microfluidic reactors, although in its initial stage, holds a promising future. Many efforts are now in progress in many laboratories to develop generally applicable microreactors for polymer synthesis.

Future Directions for Research

Microreactors will represent an indispensable tool for synthesizing polymers with controlled properties. Microreaction in microfluidic systems will find its way in the shift from conventional batchwise reaction to microreaction strategy. In future, microfluidic devices will find broad applications particularly in linear polymer production aimed at obtaining polymers of desired average molecular weight with narrower molecular weight distribution. In addition, the prospect of making novel polymer particles with unique shapes can be realized by microreaction system via control of specific device geometry and flow parameters. The process of rapid prototyping and the emergence of simple, homemade devices that take only minutes or hours to construct have enabled many groups to explore this exciting field. More and more applications of microfluidic reaction systems for polymer synthesis are required to develop a generally applicable microreactor for polymerization reactions. In addition to simple reactions, an aspect of polymer synthesis that may offer great research opportunity is synthesis of novel particles with unique shapes, and thus the development of microscope projection photolithography will be necessary. In addition, theoretical studies such as numerical simulations are also required to obtain a generally applicable microreactor. Matching of experimental achievements and theoretical studies may accelerate development of microreactors for polymerization reactions. Still, this field is in its initial stage and has much room for development.

Cross References

- ► Droplet Based Lab-on-Chip Devices
- ► Lab-on-a-Chip Devices for Chemical Analysis
- ► Microfluidics for Bio- and Chemical Reactions
- ► Droplet Microreactors

References

1. Wu T, Mei Y, Cabral JT, Xu C, Beers KL (2004) A new synthetic method for controlled polymerization using a microfluidic system. J Am Chem Soc 126:9880–9881
2. Wu T, Mei Y, Michelle Byrd HC, Beers KL (2005) Block copolymer PEO-*b*-PHPMA synthesis using controlled radical polymerization on a chip. Macromol Rapid Commun 26:1037–1042
3. Iwasaki T, Yoshida J (2005) Free radical polymerization in microreactors. Significant improvement in molecular weight distribution control. Macromolecules 38:1159–1163
4. Nagaki A, Kawamura K, Suga S, Ando T, Sawamoto M, Yoshida J (2004) Cation pool-initiated controlled/living polymerization using microsystems. J Am Chem Soc 126:14702–14703
5. Honda T, Miyazaki M, Nakamura H, Maeda H (2005) Controllable polymerization of *N*-carboxyanhydride in a microreaction system. Lab Chip 5:812–818
6. Abhinkar A, Tennico Y, Liu SH, Rundel JT, Tseng T, Remcho VT, Paul BK, Chang CH (2006) High Rate Convergent Synthesis and Deposition of Polyamide Dendrimers using a Continuous-Flow Microreactor. Chem Eng Technol 30:334–340
7. Serra C, Sary N, Schlatter G, Hadziioannnou G, Hessel V (2005) Numerical simulation of polymerization in interdigital multilamination micromixers. Lab Chip 5:966–973
8. Nie Z, Xu S, Seo M, Lewis PC, Kumacheva E (2005) Polymer particles with various shapes and morphologies produced in continuous microfluidic reactors. J Am Chem Soc 127:8058–8063
9. Dendukuri D, Tsoi K, Hatton TA, Doyle PS (2005) Controlled synthesis of nonspherical microparticles using microfluidics. Langmuir 21:2113–2116
10. Dendukuri D, Pregibon DC, Collins J, Hatton TA, Doyle PS (2006) Continuous-flow lithography for high-throuput microparticle synthesis. Nat Mater 5:365–369

Poor Man's LIGA

► LIGA-Like Techniques

Porous Electrodes

► Three-Dimensional Electrodes

Port Resonance

► Hemholtz Resonance

Positive Displacement Pump

Synonyms

Flexible member pump; Membrane pump; Diaphragm pump

Definition

In a *positive displacement pump* fluid is displaced by a moving boundary. Ideally, this displacement is independent of backpressure, up to the maximum pump head.

Cross References

- ► Compression Ratio
- ► Dead Volume
- ► Electromagnetic Valves
- ► Electrostatic Valves
- ► Magnetic Pumps
- ► Membrane Actuation for Micropumps
- ► Microactuators
- ► Peristaltic Pumps
- ► Piezoelectric Valves
- ► Pneumatic Valves
- ► Stroke Volume
- ► Thermomechanical Valves
- ► Thermopneumatic Valves

Positive Pressure or Suction (Vacuum) Pressure

Definition

Positive pressure or suction (vacuum) pressure is used to generate a pressure difference to the reservoir on chips and drives the sample solution into the microfluidic systems on chip.

Cross References

► Techniques for Transferring Samples to Chips

Potassium Hydroxide (KOH) Etching

► Anisotropic Etching

Powder Blasting

Zheng Cui
Rutherford Appleton Laboratory, Didcot, Oxfordshire, UK
z.cui@rl.ac.uk

Synonyms

Sand blasting; Micropowder blasting

Definition

Powder blasting is a micromachining technique which uses a high-velocity air jet containing microparticles to impinge on and erode material from a surface.

Overview

Sand blasting is a traditional mechanical processing technique which can be found in a mechanical workshop. Sand blasting has been used commonly for removing rusty surface, dry paints or contaminants from a metal work piece. From the mid-1990s, sand blasting was used to machine large arrays of holes in glass panels for large-area flat panel display devices. Thousands of holes could be machined in the glass at once, which was highly efficient and low cost [1]. Sand blasting was introduced as a microstructuring technique in early 2000, with the name of powder blasting because much smaller particles were used [2]. The principle of power blasting micromachining is that when a powder particle indents the surface of a brittle material such as glass or silicon it generates cracks and a plastic zone around the impact point. There are two types of cracks: lateral and radial. The lateral cracks play a major role in the erosion process because they can reach the surface and remove upper material zone. The radial cracks have no significant contribution in the erosion process, but they weaken the material. The length of such cracks depends on a few parameters like the substrate's Young's modulus and hardness and the indentation volume. These parameters then depend on the kinetic energy of the particle and its shape. Powder blasting has the following features [3]:

- It is only suitable for machining brittle materials, such as glass, silicon and ceramics; it is not suitable for ductile materials, such as metals and polymers. Ductile materials can serve as masking material in powder blasting machining.
- The mask materials for powder blasting are required not only to be ductile but also thick enough. Because high-speed particles inevitably consume the masking layer, even though at a lower rate, when the masking layer reaches a certain thinness the particles with high kinetic energy can penetrate through the mask and damage the work piece surface. The best way of making the mask is to pattern it directly on the work piece surface. For example, a copper layer is deposited by electroplating on the substrate surface and then photolithographically patterned. The selectivity of powder blasting Pyrex glass to copper is 65:1 [4]. Some rubber-like polymers, which are also photon sensitive, can also be used as masking materials.



Powder Blasting, Figure 1 Typical etch profile of powder blasting in glass

- Powder blasting is a pure mechanical processing technique. The particle beam from a nozzle is always of the highest speed in the centre, as a result of which the etched profile always has a sloped sidewall. Figure 1 shows typical structure profiles etched by powder blasting [4].
- The resolution of powder blasting is normally above 50 μm. This is mainly attributed to the particle sizes which are around 30 μm. The resolution may increase if smaller particles are used. However, the kinetic energy of particles also reduces for smaller sized particles.
- The roughness of an eroded surface produced by high-speed powder is around the micrometre scale, which is related to the size of the particles.

Powder blasting is not a high-tech machining method. It is for this reason that the technique is less expensive. Powder blasting is particularly useful for making patterns in glass. For micromachining of glass there are no other better techniques apart from wet etching by HF acid. It is well known that HF acid is a hazardous chemical and wet etching by HF is isotropic. Powder blasting is a much better suited


Powder
Vibrating feeder
Air feed <6 bar
Box
Nozzle
Substrate
X-Y movement
Cyclone Ventilation
Pressurized air mixture 1-5 Bar
Average particle size: 3 - 30 micron
Nozzle
Nozzle
Al_2O_3
$V_{particle}$ = 80-200 m/s
mask
Roughness: 0.7 - 2.5 micon
Target

Powder Blasting, Figure 2 Schematic representation of a powder blasting system

method to process glass materials. The structures encountered in microfluidic and biochip systems are normally above a few tens of micrometres, which can be adequately resolved by powder blasting machining [5]. For drilling holes in glass chips, the conventional method is mechanical drilling with a diamond bit. Mechanical drilling can produce chippings on the edge and it becomes extremely difficult to drill thin glass. Powder blasting can machine a large number of holes in glass at once and the quality of the holes is much better than that produced by mechanical drilling.

Basic Methodology

A schematic representation of a powder blasting system is shown in Fig. 2. The microparticles used for powder blasting are not sands, but Al_2O_3 or SiC particles in the size range $20 - 30\,\mu m$. These are injected from a vibrating feeder into a pressured air flow stream. The pressured particle jet flows through a nozzle and impinge at high velocity normal to the surface of a work piece. The velocity at which the particles impinge on a solid surface is in the range $80 - 200\,m/s$. These particles with high kinetic energy can crack and erode the solid surface locally, with etching rate of a few tens to a few hundreds of micrometers per minute, and in extreme cases can be as high as 1 mm/min [2]. The etching rate is directly proportional to the air pressure and the gap distance between the nozzle and surface of the work piece. However, the etching rate becomes saturated when the air pressure is too high and the speed of the air stream approaches the speed of sound. An array of nozzles can be used to etch a large area of surface. The substrate to be blasted is normally mounted on a rotating table, while the nozzle array is fixed. By rotating the table, uniform erosion over a large area of substrate or a number of substrates can be achieved. While the powder jet impinges the substrate, a cyclone ventilation system collects the powders and reuses them. Although small particles can improve the surface roughness of powder blasting, particles smaller than 5 μm cannot be recycled, which is another reason for not using too small powder particles. After powder blasting and removal of the masking layer, the etched surface can be washed clean by water.

There are no commercial powder blasting systems available because there is not such a market. Only a few places worldwide have utilised this technique. There are companies that can make custom designed powder blasting systems. They only make to order. However, there are some companies, such as Micronit in the Netherlands, which provide powder blast micromachining services.

Key Research Findings

Much of the research in powder blasting has been focused on improving resolution and selectivity of masking materials. Currently the resolution of powder blasting is above 50 μm. This is mainly attributed to the particle sizes which are around 30 μm. Using smaller particles can improve resolution and give smaller pattern dimensions. However, there is a limit to the particle size that can be used for powder blasting. As mentioned earlier, there is the sound barrier which limits the velocity of microparticles not to exceed 335 m/s. There is also a threshold kinetic energy above which a particle can crack an eroding material. For powder blasting of soda lime glass with alumina (Al_2O_3) particles, the threshold energy is 25 nJ, from which the minimum size of alumina particles can be estimated to be 6 μm in order to acquire the threshold kinetic energy at the speed of sound [6]. For safety reasons 10 μm alumina particles were used with a velocity of 156 m/s, which helped to achieve a minimum feature size of 30 μm in soda lime glass. However, smaller particles resulted in much less efficiency. Experimental comparison demonstrated that a 10 μm particle is 50 times less efficient than a 30 μm particle in powder blasting. The etch rate is also limited by the mask feature size. The smaller the mask feature size compared to the particle size, the lower the etch rate.

Various photosensitive polymers, as well as metal films, have been used as masking materials. In general, depending on their erosion behaviour, materials can be divided into two classes: one class comprising all materials showing maximum erosion rate at normal impact of particles, and the other class of materials having a maximum erosion rate at a glancing impact angle. Glass belongs to the first class of materials, while metals belong to the second class. Due to their high erosion resistance at normal impact, metals therefore have been used as a masking material. Metallic contact masks can be made by laser ablation or electroplating using a photoresist as a mould. Recent development has shown that elastomers such as polydimethylsiloxane (PDMS) can be used as masking materials [6]. A PDMS mask can be made by casting into a patterned SU-8 mould. The PDMS mask has selectivity of 5000:1 to soda lime glass in powder blasting [7].

Future Directions for Research

Powder blasting as an alterative technique has been increasingly adopted for making microstructures in glass, ceramics or graphite, which are not easy to make by other techniques. Future research will be aimed at improving etching efficiency and resolution by trying out different masking materials or parameters of microparticles and air jet flow.

Cross References

► Plasma Etching

References

1. Ligthart HJ, Slikkerveer PJ (1996) Glass and glass machining in ZEUS panels, Philips J Res 50:475–499
2. Belloy E, Thurre S, Walckiers E, Sayah A, Gijs MAM (2000) The introduction of powder blasting for sensor and microsystem applications. Sensor Actuator 84:330–337
3. Cui Z (2006) Micro-Nanofabrication Technologies and applications. Springer-Verlag
4. Wensink H, Jansen HV, Berenschot JW, Elwenspoek MC (2000) Mask materials for powder blasting. J Micromech Microeng 10:175–180
5. Schlautmann S, Wensink H, Schasfoort R, Elwenspoek M, van den Berg A (2001) Powder-blasting technology as an alternative tool for microfabrication of capillary electrophoresis chips with integrated conductivity sensors. J Micromech Microeng 11:386–389
6. Pawlowski A-G, Sayah A, Gijs MAM (2005) Precision Poly-(Dimethyl Siloxane) Masking Technology for High-Resolution Powder Blasting. J Microelectromech Syst 14(3):619–624

7. Sayah A, Parashar VK, Pawlowski A-G, Gijs MAM (2005) Elastomer mask for powder blasting microfabrication, Sensor Actuator A 125:84–90

Power MEMS

► Micro Energy Conversion Devices

Precipitate

Definition

A phase change which results in the formation of a collection of a material. For example, solid precipitate can be formed in a liquid phase solution as a result of a chemical reaction or a supersaturation condition in the solution.

Cross References

► Fabrication of Self-Assembled Catalytic Nanostructures

Precipitation

► Nucleation and Growth

Precursor Materials

Synonyms

Predecessor material

Definition

A substance that, following a reaction, becomes an intrinsic part of a product chemical. The material must be stable at room temperatures. During CVD process, the precursor material is vaporised. The precursor gas is transported to the surface where it undergoes a chemical reaction to produce the desired thin film.

Cross References

► Chemical Vapor Deposition for Film Deposition
► Plasma-Treatment Physics

Predecessor Material

► Precursor Materials

Preparatory Separation

► Biosample Preparation by Lab-on-a-Chip Devices

Pressure

Synonyms

Absolute pressure; Gage pressure; Differential pressure

Definition

The absolute pressure is referenced to total vacuum (no gas molecule present in a defined volume). The gage pressure is the difference between absolute pressure and atmospheric pressure. The differential pressure is the difference between a measured pressure and a reference pressure. Pressures are measured in Pascal (N/m^2) according to the international standards system (SI). Further commonly used units include bar, Torr (millimeters of mercury column), pounds per square inch and others.

Cross References

► Glass-Polymer-Bonding
► Wall Shear Stress

Pressure-Driven Flow

Definition

Flow driving principle used to create fluid flows through microfluidic channels. By applying pressure at the inlet the fluid is pumped through the channel. The fluid velocity near the walls approaches zero and a parabolic velocity profile is produced within the channel.

Pressure-Driven Single Phase Gas Flows

Stéphane Colin
National Institute of Applied Sciences of Toulouse
(INSAT), Toulouse Cedex 4, France
stephane.colin@insa-toulouse.fr

Synonyms

Poiseuille single phase gas flows

Definition

A pressure-driven gas flow is generated by applying a pressure difference between the inlet and the outlet of a fluidic system, for example a channel. Due to very small hydraulic diameters, pressure-driven gas flows in microchannels are laminar. Gas microflows are distinct from gas macroflows by rarefaction effects which appear as soon as the mean free path of the molecules is no longer negligible compared with the hydraulic diameter of the microchannel. For such rarefied flows, the classic Poiseuille model is no longer valid, and other models should be used, according to the rarefaction level, which is quantified by the Knudsen number.

Overview

Rarefaction Effects and Gas Flow Regimes

Usually, the regime of gas flow in a macrochannel refers to viscous and compressibility effects, respectively quantified by the Reynolds number Re and the Mach number Ma. For low Reynolds numbers (typically for $\mathrm{Re} < 2000$), the flow is laminar and it becomes turbulent for higher values of Re. For $\mathrm{Ma} < 1$, the flow is subsonic and for $\mathrm{Ma} > 1$, it is supersonic. Generally, if $\mathrm{Ma} > 0.3$, compressibility effects should be taken into account.

On the other hand, for gas microflows, the main micro-effect that results from shrinking down the devices size is rarefaction. Actually, there is a strong – although not complete – analogy between microflows and low pressure flows. Rarefaction, which implies a local thermodynamic disequilibrium, occurs as soon as the mean free path of the gas molecules is no longer negligible compared with a characteristic length of the system.

Thus, it is convenient to differentiate the flow regimes in function of the Knudsen number

$$\mathrm{Kn} = \frac{\lambda}{L}, \tag{1}$$

ratio of the mean free path of the molecules λ over this characteristic length L, and the following classification is usually accepted:

- For $\mathrm{Kn} < 10^{-3}$, the flow is a *continuum flow* **(C)** and it is accurately modeled by the compressible Navier–Stokes equations with classical no-slip boundary conditions.
- For $10^{-3} < \mathrm{Kn} < 10^{-1}$, the flow is a *slip flow* **(S)** and the Navier–Stokes equations remain applicable, provided a velocity slip and a temperature jump are taken into account at the walls. These new boundary conditions point out that rarefaction effects become sensitive at the wall first.


L (µm)
10^2
10^0
10^{-2}
Air at standard conditions
Continuum Flow (C)
Slip Flow (S)
Transition Flow (T)
Free Molecular Flow (M)
DSMC or lattice Boltzmann
Burnett equations with slip B.C.
QGD or QHD equations with 1st-order slip B.C.
or
Navier -Stokes equations with 2nd -order slip B.C.
Navier-Stokes equations with 1st-order slip B.C.
Navier-Stokes equations with no-slip B.C.
Euler equations
Kn
0
10^{-3}
10^{-1}
10

Pressure-Driven Single Phase Gas Flows, Figure 1 Gas flow regimes and main models according to the Knudsen number

- For $10^{-1} < \mathrm{Kn} < 10$, the flow is a *transition flow* **(T)** and the continuum approach of the Navier–Stokes equations is no longer valid. However, the intermolecular collisions are not yet negligible and should be taken into account.
- For $\mathrm{Kn} > 10$, the flow is a *free molecular flow* **(M)** and the occurrence of intermolecular collisions is negligible compared with the one of collisions between the gas molecules and the walls.

The limits of these different regimes are only indicative and could vary from one case to another, partly because the choice of the characteristic length L is rarely unique. For flows in microchannels, L is generally the hydraulic diameter or the depth of the channel. In complex geometrical configurations, it could be preferable to define L from local gradients (for example of the density ρ: $L = 1/|\nabla\rho/\rho|$) rather than from simple geometrical considerations [1]; the Knudsen number based on this characteristic length is the so-called local rarefaction number. The upper axis of Fig. 1 locates these different regimes for air in standard conditions, as a function of a characteristic length, for example a microchannel hydraulic diameter. The lower axis shows the corresponding values of the Knudsen number.

Mean Free Path and Knudsen Number Calculation

Calculating the mean free path requires assumptions about intermolecular collisions. First, the gas is assumed to be a dilute gas, i. e. a gas for which the mean molecular diameter of the molecules is small compared with the mean molecular spacing. This condition is verified with a good precision for all usual gases under standard pressure and temperature conditions. It involves binary collisions between molecules and the mean free path may be expressed as $\lambda = c'/\nu = \sqrt{8RT/\pi}/\nu$, ratio of the mean thermal velocity c' to the collision rate ν. The mean thermal velocity depends on the temperature T and on the specific gas constant R.

For classic collision models, based on an inverse power law (IPL) interaction scheme which only takes into account the repulsion part of the force between two molecules, the expression of ν leads to the general form of the mean free path:

$$\lambda = \frac{k_2 \mu}{\rho \sqrt{RT}} \,. \tag{2}$$

The mean free path is a function of the temperature T, the density ρ and the dynamic viscosity μ of the gas which itself depends on the temperature as

$$\mu_{(T)} = \mu_{0(T_0)} \left(\frac{T}{T_0} \right)^{\omega} , \tag{3}$$

T_0 being a reference temperature for which the viscosity μ_0 is known.

The values of the dimensionless parameters k_2 and ω for the most classic collision models are given in Table 1. The Maxwell Molecules (MM) model assumes a linear relationship between viscosity and temperature, although for the Hard Sphere (HS) model, the viscosity is proportional to the square root of the temperature. These models could be roughly considered as limits for the real behavior of gases, and the Variable Hard Sphere (VHS) model proposed by Bird [2] is much more accurate. Another sophistication has been proposed by Koura and Matsumoto who developed the Variable Soft Sphere (VSS) model, which introduces via an adjustment parameter α limited corrections – less than 3% – to the evaluation of the mean free path deduced from the VHS model, assuming soft collisions between the molecules. For $\alpha = 1$, the VSS model reduces to the VHS model.

Experimentally deduced values of ω and α are available for different gases (Table 2).

Ideal Gas Assumption

For a dilute gas in thermodynamic equilibrium, the classic ideal gas equation of state

$$p = \rho RT = n k_B T \tag{4}$$

is valid. If the thermodynamic equilibrium is not verified, Eq. (4) remains valid, providing the thermodynamic temperature T is replaced with the translational kinetic temperature T_{tr}, which measures the mean translational kinetic energy of the molecules. Here, p is the pressure and $\rho = mn$ is the density, $k_B = R'/N = (M/N)(R'/M) = mR = 1.381 \times 10^{-23}\,\mathrm{J\,K^{-1}}$ is the Boltzmann constant, $R' = 8.315\,\mathrm{J\,mol^{-1}\,K^{-1}}$ being the universal gas constant, $N = 6.022 \times 10^{23}\,\mathrm{mol^{-1}}$ the Avogadro's number and M the molecular weight.

Pressure-Driven Single Phase Gas Flows, Table 1 Mean free path and dynamic viscosity for classic IPL collision models

Model	$\mu \propto T^{\omega}$	$\lambda = k_2 \frac{\mu}{\rho\sqrt{RT}}$
	ω	k_2
Maxwell Molecules (MM)	1	$\sqrt{2/\pi} \approx 0.798$
Hard Spheres (HS)	$\frac{1}{2}$	$\frac{16}{5\sqrt{2\pi}} \approx 1.277$ (sometimes proposed as $\sqrt{\pi/2} \approx 1.253$)
Variable Hard Spheres (VHS)	$\omega = \frac{\eta+3}{2(\eta-1)}$	$\frac{2(7-2\omega)(5-2\omega)}{15\sqrt{2\pi}}$
Variable Soft Spheres (VSS)	$\omega = \frac{\eta+3}{2(\eta-1)}$	$\frac{4\alpha(7-2\omega)(5-2\omega)}{5(\alpha+1)(\alpha+2)\sqrt{2\pi}}$

As a consequence, for an ideal gas and an IPL collision model, the Knudsen number can be written as

$$\mathrm{Kn} = \frac{k_2 \mu_{(T)} \sqrt{RT}}{pL} \,, \tag{5}$$

with the value of k_2 given in Table 1.

Modeling Gas Flow in Microchannels

It can be shown from Eq. (5) that for an ideal gas and an IPL collision model,

$$\mathrm{Re} = k_2 \sqrt{\gamma}\, \mathrm{Ma}/\mathrm{Kn} \,, \tag{6}$$

since $\mathrm{Re} = \rho u L/\mu$ and $\mathrm{Ma} = u/\sqrt{\gamma RT}$, noting γ the ratio of the specific heats of the gas. As k_2 is of the order of unity (Table 1), the result is that for subsonic microflows, viscous effects are predominant and the flows are laminar.

It can be seen from Fig. 1 that gas flows in micron size channels are typically relevant to the slip flow regime, at any rate for usual pressure and temperature conditions. For lower sizes, i. e. for Knudsen numbers higher than 10^{-1}, the slip flow regime could remain valid, provided that classical velocity slip and temperature jump boundary conditions are modified (taking into account higher order terms as explained below) and/or that Navier–Stokes equations are extended to more general sets of conservation equations, such as the Quasi-Gasodynamic (QGD), the Quasi-Hydrodynamic (QHD) or the Burnett equations [3].

However, for Knudsen numbers higher than unity, as it could be the case in nanochannels (▶ gas flow in nanochannels) or in low-pressure flows in microchannels,

Pressure-Driven Single Phase Gas Flows, Table 2 Molecular weight and dynamic viscosity under standard conditions ($p_0 = 101{,}325\,\text{Pa}$ and $T_0 = 273.15\,\text{K}$) estimated from a VHS or a VSS model (data from Bird [2]) with corresponding values of ω and α

Gas	$M \cdot 10^3$ (kg mol^{-1})	$\mu_0 \cdot 10^7$ (N s m^{-2})	ω	α
sea level air	28.97	171.9	0.77	–
Ar	39.948	211.7	0.81	1.40
CH_4	16.043	102.4	0.84	1.60
Cl_2	70.905	123.3	1.01	–
CO	28.010	163.5	0.73	1.49
CO_2	44.010	138.0	0.93	1.61
H_2	2.0159	84.5	0.67	1.35
HCl	36.461	132.8	1.00	1.59
He	4.0026	186.5	0.66	1.26
Kr	83.80	232.8	0.80	1.32
N_2	28.013	165.6	0.74	1.36
N_2O	44.013	135.1	0.94	–
Ne	20.180	297.5	0.66	1.31
NH_3	17.031	92.3	1.10	–
NO	30.006	177.4	0.79	–
O_2	31.999	191.9	0.77	1.40
SO_2	64.065	116.4	1.05	–
Xe	131.29	210.7	0.85	1.44

the continuum approach is not longer valid, and molecular methods such as the Direct Simulation Monte Carlo – DSMC – (▶ Monte Carlo method) or the Lattice Boltzmann methods (▶ Lattice Boltzmann method) should be used.

Basic Methodology

For moderate pressure levels, and Knudsen numbers up to 0.5 or so, pressure-driven gas microflows can be modeled with the compressible Navier–Stokes equations, slip velocity and temperature jump boundary conditions, considering the gas as an ideal gas.

Compressible Navier–Stokes Equations

The compressible Navier–Stokes equations are the governing conservation laws for mass, momentum and energy. These laws are written assuming that the fluid is Newtonian and follows the Fourier law of diffusion, so that the stress tensor is a linear function of the velocity gradients and the heat flux vector is proportional to the temperature gradient. Adding Stokes' hypothesis, which expresses that the changes of volume do not involve viscosity, the compressible Navier–Stokes equations may be written as:

$$\frac{\partial \rho}{\partial t} + \nabla \cdot (\rho \boldsymbol{u}) = 0 \quad (7)$$

$$\frac{\partial (\rho \boldsymbol{u})}{\partial t} + \nabla \cdot \left(\rho \boldsymbol{u} \otimes \boldsymbol{u} - \mu \left[\nabla \otimes \boldsymbol{u} + (\nabla \otimes \boldsymbol{u})^{\mathrm{T}} - \frac{2}{3} (\nabla \cdot \boldsymbol{u})\, \mathbf{I} \right] \right) + \nabla p = \boldsymbol{f} \quad (8)$$

$$\frac{\partial E}{\partial t} + \nabla \cdot \left((E + p)\, \boldsymbol{u} - \mu \left[\nabla \otimes \boldsymbol{u} + (\nabla \otimes \boldsymbol{u})^{\mathrm{T}} - \frac{2}{3} (\nabla \cdot \boldsymbol{u})\, \mathbf{I} \right] \cdot \boldsymbol{u} - k \nabla T \right) = \boldsymbol{f} \cdot \boldsymbol{u} \quad (9)$$

where $\boldsymbol{u}$ is the velocity vector, $\mathbf{I}$ the unit tensor, t the time and k the thermal conductivity. The total energy per unit volume $E = \rho(e + \boldsymbol{u} \cdot \boldsymbol{u}/2)$ is a function of the internal specific energy e that may be written $e = p/[\rho(\gamma - 1)]$ for an ideal gas.

The external volume forces $\boldsymbol{f}$ (gravitational forces, magnetic forces, etc.) are generally negligible in gas flow. It is even more the case in gas microflows, since the volume over surface ratio decreases with the characteristic length L and consequently, in microscale geometries, volume effects may be neglected when compared to surface effects.

Knudsen Layer

The Knudsen layer plays a fundamental role in the slip flow regime. This thin layer, between one and two molecular mean free paths in thickness, is a region of local non-equilibrium which is observed in any gas flow near a surface. In non rarefied flows, the Knudsen layer is too thin for having any significant influence, but in the slip flow regime, it should be taken into account.

Although the Navier–Stokes equations are not valid in the Knudsen layer, due to a nonlinear stress/strain-rate behavior in this small layer [4], their use with appropriate boundary velocity slip and temperature jump conditions proved to be accurate for predicting mass flow rates [5] (▶ methods for flow rate measurements) and velocity profiles out of the Knudsen layer. Classically, the real flow is not simulated within the Knudsen layer, but the influence of the Knudsen layer on the flow outside this non-equilibrium layer is taken into account, replacing the no-slip condition at the wall with a slip-flow condition. For that purpose, a fictitious slip velocity u_{slip} is introduced (Fig. 2). Real slip at the wall, $u_{\text{gas}} - u_{\text{wall}}$, is due to the fact that gas molecules very close to the wall have actually a mean



Pressure-Driven Single Phase Gas Flows, Figure 2 Gas flow regimes and main models according to the Knudsen number

tangential momentum partly due to the non zero momentum of molecules coming from the flow and to the momentum of the molecules reflected by the wall. These reflected molecules keep all their tangential momentum if the reflection is specular, loose all their tangential momentum if the reflection is diffuse or more generally keep only a part of it.

Velocity Slip in the Slip-Flow Regime

The classic slip-flow condition, deduced from a momentum balance at the wall, was first proposed by Maxwell and is generally presented in the form

$$u_{\text{slip}} = \frac{2-\sigma}{\sigma}\lambda \left.\frac{\partial u_s}{\partial n}\right|_w + \frac{3}{4}\frac{\mu}{\rho T}\left.\frac{\partial T}{\partial s}\right|_w . \qquad (10)$$

In this equation, σ is the tangential momentum accommodation coefficient, equal to unity for perfectly diffuse molecular reflection and zero for purely specular reflection. In Maxwell's model, u_{slip} overestimates the real velocity at the wall but leads to a rather good prediction of the velocity out of the Knudsen layer, as represented in Fig. 2. After non-dimensionalization with the characteristic length L, a reference velocity u_0 and a reference temperature T_0, Eq. (10) is written as follows:

$$u^*_{\text{slip}} = \frac{2-\sigma}{\sigma}\text{Kn}\left.\frac{\partial u^*_s}{\partial n^*}\right|_w + \frac{3}{4\gamma k_2^2}\frac{\text{Kn}^2\text{Re}_0}{\text{Ma}_0^2}\left.\frac{\partial T^*}{\partial s^*}\right|_w , \qquad (11)$$

with $u^*_s = u_s/u_0$, $T^* = T/T_0$, $n^* = n/L$ and $s^* = s/L$. Note that this non-dimensionalization is valid only if the reference lengths are the same in the s and n directions, which is generally not the case for a flow in a microchannel. In that case, it is preferable to keep the dimensional form of Eq. (10). The second term on the right-hand side, which is proportional to the square of the Knudsen number, involves the Reynolds number $\text{Re}_0 = \rho u_0 L/\mu$ and the Mach number $\text{Ma}_0 = u_0/\sqrt{\gamma R T_0}$ defined at the reference conditions. This second term is associated with the thermal creep, or transpiration phenomenon. It shows that a flow can be induced by the sole presence of a tangential temperature gradient, without any pressure gradient. In that case, the gas experiences a slip velocity and moves from the colder toward the warmer region. This can also result in a pressure variation inside a microchannel only submitted to tangential temperature gradients. Given that we consider here pressure driven flows, we assume that there is no thermal creep and that the only cause of flow is a pressure gradient. As a consequence, the first-order slip flow boundary condition is written

$$u^*_{\text{slip}} = \beta_u \frac{2-\sigma}{\sigma}\text{Kn}\left.\frac{\partial u^*_s}{\partial n^*}\right|_w = A_1 \text{Kn}\left.\frac{\partial u^*_s}{\partial n^*}\right|_w . \qquad (12)$$

A corrective coefficient β_u has been calculated by different authors [6] who have shown that a better prediction of the flow out of the Knudsen layer would be obtained with this corrective coefficient slightly different from unity, unlike as initially proposed by Maxwell. Its value depends on the collision model: for example, $\beta_u = 1.11$ for a HS model [7]. Equation (12) is called first-order slip boundary condition, because it involves the Knudsen number ($\vartheta(\text{Kn})$) and the first derivative $(\partial u^*_s/\partial n^*)_w$.

For $\text{Kn} > 0.1$, experimental [5] or numerical studies with the DSMC method show significant deviations with models based on first-order boundary conditions. Therefore, since 1947, several authors have proposed second-order boundary conditions, hoping to extend the validity of the slip flow regime to higher Knudsen numbers. Second-order boundary conditions take more or less complicated forms, which are difficult to group together in a sole equation. Actually, according to the assumptions, the second-order terms ($\vartheta(\text{Kn}^2)$) may be dependent of σ [8, 9] or involve streamwise second derivatives $(\partial^2 u^*/\partial s^{*2})_w$, in addition to spanwise second derivatives $(\partial^2 u^*/\partial n^{*2})_w$ [10]. For a developed flow between plane plates or in a circular microtube, the tangential second derivatives are zero and one may compare most of the second-order models that take the generic form

$$u^*_{\text{slip}} = A_1 \text{Kn}\frac{\partial u^*_s}{\partial n^*} + A_2 \text{Kn}^2 \frac{\partial^2 u^*_s}{\partial n^{*2}} . \qquad (13)$$

Pressure-Driven Single Phase Gas Flows, Table 3 Coefficients of some second-order boundary conditions proposed in the literature, for $\sigma = 1$

Author, Year	A_1	A_2
Maxwell, 1879	1	0
Schamberg, 1947	1	$-5\pi/12$
Chapman and Cowling, 1952	≈ 1	$\approx 1/2$
Deissler, 1964	1	$-9/8$
Cercignani, 1964	1.1466	-0.9756
Hsia and Domoto, 1983	1	$-1/2$
Mitsuya, 1993	1	$-2/9$
Karniadakis and Beskok, 2002	1	1/2
Hadjiconstantinou, 2003	1.11	-0.61

In the particular case of a fully diffuse reflection ($\sigma = 1$), some A_1 and A_2 coefficients proposed in the literature are compared in Table 3. We note significant differences, essentially for the second-order term. Recent experimental flow rate data and molecular numerical simulations show that the second order coefficient A_2 should be negative, which corresponds to a slip velocity higher than that predicted by a first-order slip boundary condition.

Pressure Driven Isothermal Flows in Microchannels

We consider here the flow of an ideal gas through different microchannels in the slip-flow regime. The flow is steady, isothermal and the volume forces are neglected. The flow is also assumed to be locally fully developed: the velocity profile in a section is the same as the one obtained for a fully developed incompressible flow, but the density is recalculated in each cross-section and depends on the pressure and the temperature via the equation of state (4). This assumption is no longer valid if the Mach number is greater than 0.3. The main kinds of sections of interest are the rectangular and the circular sections. Microchannels with rectangular cross-sections are easily etched in silicon wafers, for example by reactive ion etching (RIE) or by deep reactive ion etching (DRIE). If the aspect ratio of the section is small enough, the flow may be considered as a plane flow between parallel plates and the modeling is much simpler. Gas flows in circular microtubes are also frequently encountered, for example in chromatography applications. Fused silica microtubes are proposed by different suppliers with a variety of internal diameters, from one micrometer to hundreds of micrometers. Due to their low cost, they are an interesting solution as connecting lines for a number of microfluidics devices or prototypes.



Pressure-Driven Single Phase Gas Flows, Figure 3 Different microchannel sections; **a** plane channel limited by parallel plates ($b \gg h$), **b** circular duct, **c** rectangular channel

The streamwise coordinate is z and the cross-section is in the (x, y) plane. The different considered sections are represented in Fig. 3.

Two different Knudsen numbers are usually defined for microchannel flows:

$$\mathrm{Kn} = \frac{\lambda}{D_\mathrm{H}} = \frac{\lambda}{4A/P} \tag{14}$$

is defined from the hydraulic diameter D_H as a reference length. The section area is noted A and the wetted perimeter is noted P. On the other hand,

$$\mathrm{Kn}' = \frac{\lambda}{L_\mathrm{min}} \tag{15}$$

is defined from the minimal representative length of the section.

Key Research Findings

Pressure Driven Flows Between Parallel Plates

In the case of a plane flow (Fig. 3a), $h/b \to 0$ and the velocity only depends on the transverse coordinate y. With the previous assumptions, the momentum Eq. (8) reduces to

$$\frac{\mathrm{d}^2 u_z}{\mathrm{d}y^2} = \frac{1}{\mu}\frac{\mathrm{d}p}{\mathrm{d}z}\,. \tag{16}$$

The first-order boundary condition (12) for a fixed wall and an isothermal flow is $u_s|_w = A_1\lambda\,(\partial u_s/\partial n)_w$, i. e. for a flow between parallel plates:

$$u_z|_{y=h} = -A_1\lambda\left.\frac{\partial u_z}{\partial y}\right|_{y=h}\,, \tag{17}$$

to be associated with the condition of symmetry (cf. Fig. 3)

$$\left.\frac{\mathrm{d}u_z}{\mathrm{d}y}\right|_{y=0} = 0\,. \tag{18}$$

The solution of this set of equations is

$$u_z = \frac{1}{\mu}\frac{\mathrm{d}p}{\mathrm{d}z}\left(\frac{y^2-h^2}{2} - A_1\lambda h\right)\,. \tag{19}$$

In a dimensionless form, the velocity distribution can be written as

$$u_z^* = 1 - y^{*2} + 8A_1\mathrm{Kn} = 1 - y^{*2} + 4A_1\mathrm{Kn}'\,, \tag{20}$$

where $y^* = y/h$, $u_z^* = u_z/u_{z0}$ and $u_{z0} = u_{z\,(y=0,\mathrm{Kn}=0)} = -\left(h^2/[2\mu]\right)\left(\mathrm{d}p/\mathrm{d}z\right)$ represents the velocity at the center of the section when rarefaction is not taken into account.

The integration of the velocity distribution given by Eq. (20) over the cross-section leads to the mean velocity

$$\overline{u_z^*} = \frac{1}{2}\int_{-1}^{1} u_z^*\,\mathrm{d}y^* = \frac{\overline{u_z}}{u_{z0}} = \frac{2}{3} + 8A_1\mathrm{Kn} = \frac{2}{3} + 4A_1\mathrm{Kn}'\,. \tag{21}$$

Considering a long microchannel of length l with a pressure p_i at the inlet and a pressure p_o at the outlet and neglecting the entrance effects, we can deduce from Eq. (21) the mass flow rate $\dot{m} = \rho\overline{u_z}A = p\overline{u_z}A/(RT)$, which is independent of z. According to Eq. (5), the quantity (Knp) is constant for an isothermal flow and it can be written as a function of the outlet conditions: $\mathrm{Kn}p = \mathrm{Kn}_\mathrm{o}p_\mathrm{o}$. Therefore, the integration of Eq. (21) yields

$$\int_{p_i}^{p_\mathrm{o}}\left(\frac{2}{3}p + 8A_1\mathrm{Kn}_\mathrm{o}p_\mathrm{o}\right)\mathrm{d}p = -\frac{2\mu\dot{m}RTl}{h^2A}\,, \tag{22}$$

which leads to

$$\dot{m}_{\mathrm{NS1,plan}} = \frac{2bh^3p_\mathrm{o}^2}{\mu RTl}\left[\frac{\Pi^2-1}{3} + 8A_1\mathrm{Kn}_\mathrm{o}\,(\Pi-1)\right]\,, \tag{23}$$

where $\Pi = p_i/p_\mathrm{o}$ is the ratio of the inlet over outlet pressures and Kn_o is the outlet Knudsen number. The subscript NS1 refers to the Navier–Stokes equations with first-order slip boundary conditions. In a dimensionless form that compares the actual mass flow rate $\dot{m}$ with the mass flow rate $\dot{m}_{ns}$ obtained from a no-slip hypothesis, Eq. (23) becomes:

$$\begin{aligned}\dot{m}^*_{\mathrm{NS1,plan}} = \frac{\dot{m}_{\mathrm{NS1,plan}}}{\dot{m}_{ns,\mathrm{plan}}} &= 1 + 24A_1\frac{\mathrm{Kn}_\mathrm{o}}{\Pi+1}\\ &= 1 + 12A_1\frac{\mathrm{Kn}'_\mathrm{o}}{\Pi+1}\,.\end{aligned} \tag{24}$$

The pressure distribution along the z-axis can be found by expressing the conservation of mass flow rate through the channel, notably between any section defined by z and the outlet section:

$$\begin{aligned}\dot{m}_{\mathrm{NS1,plan}} = &\frac{2bh^3p_\mathrm{o}^2}{\mu RT\,(l-z)}\\ &\times\left[\frac{(p/p_\mathrm{o})^2-1}{3} + 8A_1\mathrm{Kn}_\mathrm{o}\,(p/p_\mathrm{o}-1)\right]\,.\end{aligned} \tag{25}$$

Equation (25) shows that the pressure $p^* = p/p_\mathrm{o}$ is the solution of the polynomial

$$p^{*2} + \alpha_1 p^* + \alpha_2 + \alpha_3 z^* = 0\,, \tag{26}$$

where $z^* = z/l$ and $\alpha_1 = 24A_1\mathrm{Kn}_\mathrm{o}$, $\alpha_2 = -\Pi(\Pi+\alpha_1)$, $\alpha_3 = (\Pi-1)(\Pi+1+\alpha_1)$.

The solution of Eq. (26) is plotted in Fig. 4, for an inlet over outlet pressure ratio $\Pi = 2$. This figure shows that rarefaction and compressibility have opposite effects on the pressure distribution. Rarefaction effects (characterized by Kn) reduce the curvature in pressure distribution due to compressibility effects (characterized by Ma).

Therefore, the previous model can be improved to remain accurate for higher Knudsen numbers. For this purpose,



Pressure-Driven Single Phase Gas Flows, Figure 4 Pressure distribution along a plane microchannel, for $\Pi = 2$.
(△): incompressible flow; (□): $\mathrm{Kn_o} = 0$; (+): $\mathrm{Kn_o} = 0.05$; (◯): $\mathrm{Kn_o} = 0.1$

second-order – $\vartheta(\mathrm{Kn}^2)$ – models, based on second-order boundary conditions, may be used.

It is easy to verify that the mass flow rate is consequently corrected as:

$$\begin{aligned}\dot{m}^*_{\mathrm{NS2,plan}} &= \frac{\dot{m}_{\mathrm{NS2,plan}}}{\dot{m}_{ns,\mathrm{plan}}} \\ &= 1 + 24A_1 \frac{\mathrm{Kn_o}}{\Pi + 1} - 96A_2 \mathrm{Kn}_\mathrm{o}^2 \frac{\ln \Pi}{\Pi^2 - 1} \\ &= 1 + 12A_1 \frac{\mathrm{Kn}'_\mathrm{o}}{\Pi + 1} - 24A_2 \mathrm{Kn}'^{\,2}_\mathrm{o} \frac{\ln \Pi}{\Pi^2 - 1} \,. \qquad (27)\end{aligned}$$

Pressure Driven Flows in Circular Microtubes

With the same general assumptions than in the previous section, the momentum Eq. (8) in polar coordinates reduces to

$$\frac{1}{r}\frac{\mathrm{d}}{\mathrm{d}r}\left(r\frac{\mathrm{d}u_z}{\mathrm{d}r}\right) = \frac{1}{\mu}\frac{\mathrm{d}p}{\mathrm{d}z} \,. \qquad (28)$$

The first-order boundary condition (12) for a non-moving wall and an isothermal flow is now (cf. Fig. 3b):

$$u_z|_{r=D/2} = -A_1\lambda \left.\frac{\partial u_z}{\partial r}\right|_{r=D/2} , \qquad (29)$$

which leads to the dimensionless velocity profile

$$u^*_z = 1 - r^{*2} + 4A_1\mathrm{Kn} \qquad (30)$$

where the Knudsen number $\mathrm{Kn} = \lambda/D_\mathrm{H} = \lambda/D = \mathrm{Kn}' = \lambda/L_\mathrm{min}$ is defined from a characteristic length $L = D$. Here, $r^* = 2r/D$ and $u^*_z = u_z/u_{z0}$ with $u_{z0} = -\left(D^2/[16\mu]\right)(\mathrm{d}p/\mathrm{d}z)$. The integration of the velocity within a section and along the microtube leads to

$$\dot{m}_{\mathrm{NS1,circ}} = \frac{\pi D^2 p_\mathrm{o}^2}{16\mu RTl}\left[\frac{\Pi^2 - 1}{4} + 4A_1\mathrm{Kn_o}(\Pi - 1)\right] \qquad (31)$$

for a long microtube, neglecting entrance effects and

$$\dot{m}^*_{\mathrm{NS1,circ}} = \frac{\dot{m}_{\mathrm{NS1,circ}}}{\dot{m}_{ns,\mathrm{circ}}} = 1 + 16A_1\frac{\mathrm{Kn_o}}{\Pi + 1} \,. \qquad (32)$$

The pressure distribution $p^* = p/p_\mathrm{o}$ along the microtube is the solution of the polynomial

$$p^{*2} + \beta_1 p^* + \beta_2 + \beta_3 z^* = 0 \,, \qquad (33)$$

where $\beta_1 = 16A_1\mathrm{Kn_o}$, $\beta_3 = (\Pi - 1)(\Pi + 1 + \beta_1)$ and $\beta_2 = -1 - \beta_1 - \beta_3$, which qualitatively leads to the same conclusions as for a plane flow.

The first-order solution can easily be extended to second-order boundary conditions, following the same reasoning as in the previous section. We find

$$\begin{aligned}\dot{m}^*_{\mathrm{NS2,circ}} &= \frac{\dot{m}_{\mathrm{NS2,circ}}}{\dot{m}_{ns,\mathrm{circ}}} \\ &= 1 + 16A_1\frac{\mathrm{Kn_o}}{\Pi + 1} - 32A_2\frac{\mathrm{Kn}_\mathrm{o}^2 \ln \Pi}{\Pi^2 - 1} \,. \qquad (34)\end{aligned}$$

Pressure Driven Flows in Rectangular Microchannels

A rectangular section is characterized by its aspect ratio $a^* = h/b$, with $0 < a^* \leq 1$, assuming $h \leq b$ (Fig. 3c). Actually, calculation of the mass flow rate in a rectangular microchannel using the plane flow solution (24) or (27) is inaccurate as soon as the aspect ratio of the section a^* is higher than 10^{-2}, due to non-negligible friction on the side walls of equations $x = \pm b$. Typically, the overestimation $[(\dot{m}_\mathrm{plan} - \dot{m}_\mathrm{rect})/\dot{m}_\mathrm{rect}]_{\mathrm{NS2}}$ is about 0.5% for an aspect ratio $a^* = 0.01$, it rises to 5.3% for an aspect ratio $a^* = 0.1$ and reaches 112% for a square cross-section for which $a^* = 1$! As a consequence, a real 3D model is required. With the general assumptions of previous sections, the momentum equation takes the dimensionless form

$$a^{*2}\frac{\mathrm{d}^2 u^*_z}{\mathrm{d}x^{*2}} + \frac{\mathrm{d}^2 u^*_z}{\mathrm{d}y^{*2}} = -1 \,, \qquad (35)$$

with $x^* = x/b$, $y^* = y/h$ and $u^*_z = -\mu u_z/(h^2(\mathrm{d}p/\mathrm{d}z))$.

The first-order boundary conditions are

$$u_z^*\big|_{y^*=1} = -2A_1\mathrm{Kn}' \left.\frac{\partial u_z^*}{\partial y^*}\right|_{y^*=1} , \tag{36}$$

$$u_z^*\big|_{x^*=1} = -2a^*A_1\mathrm{Kn}' \left.\frac{\partial u_z^*}{\partial x^*}\right|_{x^*=1} , \tag{37}$$

with $\mathrm{Kn}' = \lambda/(2h)$ and the conditions of symmetry are $\left(\mathrm{d}u_z^*/\mathrm{d}y^*\right)_{y^*=0} = 0$ and $(\mathrm{d}u_z^*/\mathrm{d}x^*)_{x^*=0} = 0$. The solution of Eqs. (35) to (37), compatible with the conditions of symmetry can be written as

$$u_z^* = -\sum_{i=1}^{\infty} \Psi_i\left(x^*\right)\cos\left(\delta_i y^*\right) , \tag{38}$$

where the eigenvalues δ_i must verify

$$\delta_i \tan\delta_i = \frac{A_1}{2\mathrm{Kn}'} \tag{39}$$

in order to be compatible with the boundary condition (36) without leading to a trivial velocity solution. The x^* dependent Ψ_i functions are found by expanding the right-hand side of Eq. (35), i. e. unity, in terms of the orthogonal functions $\cos\left(\delta_i y^*\right)$:

$$\begin{aligned} -1 &= -\sum_{i=1}^{\infty} \frac{2\sin\delta_i}{\delta_i + \sin\delta_i\cos\delta_i}\cos\left(\delta_i y^*\right) \\ &= -\sum_{i=1}^{\infty} \Omega_i \cos\left(\delta_i y^*\right) . \end{aligned} \tag{40}$$

Therefore, to verify the momentum Eq. (35), the functions Ψ_i must obey

$$\frac{d^2\Psi_i}{dx^{*2}} - \left(\frac{\delta_i}{a^*}\right)^2 \Psi_i - \frac{\Omega_i}{a^{*2}} = 0 . \tag{41}$$

The solution of Eq. (41), with the boundary and symmetry conditions and using Eq. (39), is

$$\Psi_i = -\frac{\Omega_i}{\alpha_i^2}\left(1 - \frac{\cosh\left(\frac{\alpha_i x^*}{a^*}\right)}{\cosh\left(\frac{\alpha_i}{a^*}\right) + 2A_1\mathrm{Kn}'\alpha_i\sinh\left(\frac{\alpha_i}{a^*}\right)}\right) . \tag{42}$$

Consequently, the velocity distribution is given by Eq. (38), where Ψ_i and δ_i are obtained from Eqs. (40) and (42). This solution is given as a function of a Knudsen number $\mathrm{Kn}' = \lambda/(2h)$ based on the channel depth, but it can also be expressed as a function of the Knudsen number $\mathrm{Kn} = \lambda/D_\mathrm{H}$ based on the hydraulic diameter, using the relation $2\mathrm{Kn} = \mathrm{Kn}'\left(1 + a^*\right)$.

The solution of the problem with Deissler [10] second-order boundary conditions is detailed in [3]. These boundary conditions may be written in a dimensionless form as

$$\begin{aligned} u_z^*\big|_{y^*=1} &= -2A_1\mathrm{Kn}' \left.\frac{\partial u_z^*}{\partial y^*}\right|_{y^*=1} \\ &\quad - \frac{9}{4}\mathrm{Kn}'^2\left(\left.\frac{\partial^2 u_z^*}{\partial y^{*2}}\right|_{y^*=1} - 1\right) \end{aligned} \tag{43}$$

and

$$\begin{aligned} u_z^*\big|_{x^*=1} &= -2A_1a^*\mathrm{Kn}' \left.\frac{\partial u_z^*}{\partial x^*}\right|_{x^*=1} \\ &\quad - \frac{9}{4}\mathrm{Kn}'^2\left(a^{*2}\left.\frac{\partial^2 u_z^*}{\partial x^{*2}}\right|_{x^*=1} - 1\right) . \end{aligned} \tag{44}$$

for a locally fully developed flow in a rectangular section. A semi-analytical solution for the mass flow is found as [3]:

$$\dot{m}_{\mathrm{NS2,rect}} = -\frac{4ph^4}{a^*RT\mu}\frac{\mathrm{d}p}{\mathrm{d}z}\left[a_1 + a_2\mathrm{Kn}' + a_3\mathrm{Kn}'^2\right] . \tag{45}$$

Values of a_1, a_2 and a_3 coefficients are given in Table 4, for different aspect ratios and values of A_1.

Temperature Jump and Heat Transfer

As for the velocity, it can be shown that the temperature experiences a jump at the wall, which can be written

$$\begin{aligned} T^* - T^*_\mathrm{wall} &= \beta_T\frac{2-\sigma_T}{\sigma_T}\frac{2\gamma}{\gamma+1}\frac{\mathrm{Kn}}{\mathrm{Pr}}\left.\frac{\partial T^*}{\partial n^*}\right|_w \\ &= B_1\frac{2\gamma}{\gamma+1}\frac{\mathrm{Kn}}{\mathrm{Pr}}\left.\frac{\partial T^*}{\partial n^*}\right|_w , \end{aligned} \tag{46}$$

where Pr is the Prandtl number and σ_T is the energy accommodation coefficient; β_T is a corrective coefficient introduced by Cercignani to improve the original formula proposed by Smoluchowski. This temperature jump must be taken into account as well as the velocity slip if the flow is not isothermal and if heat transfer is considered (► convective heat transfer in microchannels). For example, for a hydrodynamically and thermally developed flow in a plane microchannel (Fig. 3a) with a lower adiabatic

Pressure-Driven Single Phase Gas Flows, Table 4 Values of a_1, a_2 and a_3 coefficients for different values of A_1 and a^*, for Deissler second-order boundary conditions

a^* A_1	3.0000	2.3333	1.8571	1.5000	1.2222	1.0000
0 $a_1 = 0.33333$	$a_2 = 6.0000$ $a_3 = 4.5000$	$a_2 = 4.6667$ $a_3 = 4.5000$	$a_2 = 3.7143$ $a_3 = 4.5000$	$a_2 = 3.0000$ $a_3 = 4.5000$	$a_2 = 2.4444$ $a_3 = 4.5000$	$a_2 = 2.0000$ $a_3 = 4.5000$
0.01 $a_1 = 0.33123$	$a_2 = 5.9694$ $a_3 = 4.4528$	$a_2 = 4.6459$ $a_3 = 4.4542$	$a_2 = 3.7007$ $a_3 = 4.4548$	$a_2 = 2.9917$ $a_3 = 4.4550$	$a_2 = 2.4405$ $a_3 = 4.4549$	$a_2 = 1.9993$ $a_3 = 4.4549$
0.025 $a_1 = 0.32808$	$a_2 = 5.9228$ $a_3 = 4.3840$	$a_2 = 4.6141$ $a_3 = 4.3875$	$a_2 = 3.6797$ $a_3 = 4.3887$	$a_2 = 2.9788$ $a_3 = 4.3895$	$a_2 = 2.4337$ $a_3 = 4.3896$	$a_2 = 1.9977$ $a_3 = 4.3892$
0.05 $a_1 = 0.32283$	$a_2 = 5.8420$ $a_3 = 4.2761$	$a_2 = 4.5591$ $a_3 = 4.2813$	$a_2 = 3.6423$ $a_3 = 4.2843$	$a_2 = 2.9547$ $a_3 = 4.2858$	$a_2 = 2.4201$ $a_3 = 4.2858$	$a_2 = 1.9925$ $a_3 = 4.2853$
0.1 $a_1 = 0.31233$	$a_2 = 5.6774$ $a_3 = 4.0697$	$a_2 = 4.4431$ $a_3 = 4.0832$	$a_2 = 3.5613$ $a_3 = 4.0906$	$a_2 = 2.9000$ $a_3 = 4.0943$	$a_2 = 2.3860$ $a_3 = 4.0952$	$a_2 = 1.9751$ $a_3 = 4.0944$
0.25 $a_1 = 0.28081$	$a_2 = 5.1332$ $a_3 = 3.6073$	$a_2 = 4.0464$ $a_3 = 3.6287$	$a_2 = 3.2675$ $a_3 = 3.6449$	$a_2 = 2.6823$ $a_3 = 3.6560$	$a_2 = 2.2267$ $a_3 = 3.6626$	$a_2 = 1.8626$ $a_3 = 3.6647$
0.5 $a_1 = 0.22868$	$a_2 = 4.2443$ $a_3 = 3.3489$	$a_2 = 3.3519$ $a_3 = 3.3588$	$a_2 = 2.7120$ $a_3 = 3.3708$	$a_2 = 2.2289$ $a_3 = 3.3856$	$a_2 = 1.8487$ $a_3 = 3.4048$	$a_2 = 1.5395$ $a_3 = 3.4292$
1 $a_1 = 0.14058$	$a_2 = 3.1207$ $a_3 = 3.3104$	$a_2 = 2.4552$ $a_3 = 3.3176$	$a_2 = 1.9782$ $a_3 = 3.3287$	$a_2 = 1.6187$ $a_3 = 3.3438$	$a_2 = 1.3364$ $a_3 = 3.3644$	$a_2 = 1.1077$ $a_3 = 3.3908$

wall and an upper wall with constant heat flux, the Nusselt number Nu can be calculated and is given by

$$\mathrm{Nu}^{-1} = \frac{\varsigma^*}{4} + \frac{26 + 147\xi^* + 210\xi^{*2}}{140\,(1 + 3\xi^*)^2}\,, \tag{47}$$

where $\xi^* = 4A_1\mathrm{Kn}$ and $\varsigma^* = (8\gamma)/(\gamma + 1)B_1(\mathrm{Kn}/\mathrm{Pr})$ are the dimensionless slip and temperature jump coefficients. This Nusselt number reduces to the classic value 70/13 when $\mathrm{Kn} = 0$.

Future Directions for Research

Theoretical knowledge on pressure-driven gas microflows is currently well advanced, especially in the slip-flow regime. However, there is yet a need for accurate experimental data, both for steady or unsteady gas microflows, with or without heat transfer. For example, in order to definitely validate the choice of the best boundary conditions in the slip flow regime, we need to isolate the influence of the accommodation coefficients, as it remains an open issue. Relationships between their values, the nature of the substrate and the micro fabrication processes involved are currently not available. There are also few data about flows of gas mixtures in microchannels.

Cross References

- ► Micro-PIV-Based Diffusometry
- ► Convective Heat Transfer in Microchannels
- ► Gas Flow in Nanochannels
- ► Lattice Boltzmann Method (LBM)
- ► Methods for Flow Rate Measurement
- ► Micro and Nanoscale Gas Dynamics
- ► Molecular Dynamics Simulation Method
- ► Monte Carlo Method
- ► Single Phase Gaseous Flow

References

1. Gad-el-Hak M (1999) The fluid mechanics of microdevices – The Freeman Scholar Lecture. J Fluid Eng 121:5–33
2. Bird GA (1998) Molecular gas dynamics and the direct simulation of gas flows. Clarendon Press, Oxford
3. Kandlikar SG, Garimella S, Li D, Colin S and King MR (2006) Heat Transfer and Fluid Flow in Minichannels and Microchannels. Elsevier, Oxford
4. Lockerby DA, Reese JM, Gallis MA (2005) Capturing the Knudsen layer in continuum-fluid models of nonequilibrium gas flows. AIAA J 43(6):1391–1393
5. Colin S, Lalonde P, Caen R (2004) Validation of a second-order slip flow model in rectangular microchannels. Heat Transf Eng 25(3):23–30
6. Cercignani C, Illner R, Pulvirenti M (1994) The mathematical theory of dilute gases. Springer-Verlag, New York
7. Hadjiconstantinou NG (2003) Comment on Cercignani's second-order slip coefficient. Phys Fluids 15(8):2352–2354
8. Chapman S, Cowling TG (1952) The mathematical theory of non-uniform gases. University Press, Cambridge
9. Karniadakis GE, Beskok A (2002) Microflows: fundamentals and simulation. Springer-Verlag, New York, pp 340
10. Deissler RG (1964) An analysis of second-order slip flow and temperature-jump boundary conditions for rarefied gases. Int J Heat Mass Transf 7:681–694

Pressure-Driven Single Phase Liquid Flows

GIAN LUCA MORINI
DIENCA, Università di Bologna, Bologna, Italy
gianluca.morini@mail.ing.unibo.it

Definition

The forced mass movement of single phase liquids through microchannels with a hydraulic diameter less than 1 mm induced by a pressure gradient imposed at the ends of the microchannel is called pressure-driven single phase liquid flow.

Overview

Investigation of the flow phenomena in pipes and channels is the most important subject of hydraulics. In the middle of the nineteenth century an exact solution of the hydrodynamic equations was derived for the flow of a fluid through straight tubes of circular cross-section by Hagen [1] and Poiseuille [2] independently. It is interesting to highlight that the original experimental work of Poiseuille was conducted by testing water through glass capillary tubes having an internal diameter down to 15 µm. This work can be considered the first experimental test of pressure-driven single phase liquid flows in microchannels.

Basic Methodology

The behavior of isothermal pressure-driven single phase fluid flows in microchannels can be studied by determining the velocity distribution in the fluid region with the aid of the mass conservation principle (*continuity equation*) and the equations of conservation of fluid momentum [3]:

$$\begin{aligned} -\frac{1}{\rho}\frac{\mathrm{D}\rho}{\mathrm{D}t} &= \nabla \cdot \boldsymbol{v} \\ \rho\frac{\mathrm{D}\boldsymbol{v}}{\mathrm{D}t} &= -\nabla p + \rho \boldsymbol{g} - \nabla \cdot \boldsymbol{\tau} \end{aligned} \tag{1}$$

in which $\boldsymbol{v}$ is the velocity vector, ρ is the fluid density, t is the time, p is the pressure, D/Dt is the total derivative and $\boldsymbol{\tau}$ is the viscous tensor.

In Table 1 the components of the viscous tensor for Newtonian fluids are reported for Cartesian, cylindrical and spherical coordinates.

Pressure-Driven Single Phase Liquid Flows, Table 1 Components of the viscous tensor for Cartesian, cylindrical and spherical coordinates

Cartesian coordinates (x, y, z)	$\tau_{xx} = -\mu\left[2\frac{\partial v_x}{\partial x} - \frac{2}{3}(\nabla \cdot \boldsymbol{v})\right]$
	$\tau_{yy} = -\mu\left[2\frac{\partial v_y}{\partial y} - \frac{2}{3}(\nabla \cdot \boldsymbol{v})\right]$
	$\tau_{zz} = -\mu\left[2\frac{\partial v_z}{\partial z} - \frac{2}{3}(\nabla \cdot \boldsymbol{v})\right]$
	$\tau_{xy} = \tau_{yx} = -\mu\left[\frac{\partial v_x}{\partial y} + \frac{\partial v_y}{\partial x}\right]$
	$\tau_{yz} = \tau_{zy} = -\mu\left[\frac{\partial v_y}{\partial z} + \frac{\partial v_z}{\partial y}\right]$
	$\tau_{zx} = \tau_{xz} = -\mu\left[\frac{\partial v_z}{\partial x} + \frac{\partial v_x}{\partial z}\right]$
Cylindrical Coordinates (r, θ, z)	$\tau_{rr} = -\mu\left[2\frac{\partial v_r}{\partial r} - \frac{2}{3}(\nabla \cdot \boldsymbol{v})\right]$
	$\tau_{\theta\theta} = -\mu\left[2\left(\frac{1}{r}\frac{\partial v_\theta}{\partial \theta} + \frac{v_r}{r}\right) - \frac{2}{3}(\nabla \cdot \boldsymbol{v})\right]$
	$\tau_{zz} = -\mu\left[2\frac{\partial v_z}{\partial z} - \frac{2}{3}(\nabla \cdot \boldsymbol{v})\right]$
	$\tau_{r\theta} = \tau_{\theta r} = -\mu\left[r\frac{\partial}{\partial y}\left(\frac{v_\theta}{r}\right) + \frac{1}{r}\frac{\partial v_r}{\partial \theta}\right]$
	$\tau_{\theta z} = \tau_{z\theta} = -\mu\left[\frac{\partial v_\theta}{\partial z} + \frac{1}{r}\frac{\partial v_z}{\partial \theta}\right]$
	$\tau_{zr} = \tau_{rz} = -\mu\left[\frac{\partial v_z}{\partial r} + \frac{\partial v_r}{\partial z}\right]$
Spherical coordinates (r, θ, ϕ)	$\tau_{rr} = -\mu\left[\frac{\partial v_r}{\partial r} - \frac{2}{3}(\nabla \cdot \boldsymbol{v})\right]$
	$\tau_{\theta\theta} = -\mu\left[2\left(\frac{1}{r}\frac{\partial v_\theta}{\partial \theta} + \frac{v_r}{r}\right) - \frac{2}{3}(\nabla \cdot \boldsymbol{v})\right]$
	$\tau_{\phi\phi} = -\mu \begin{array}{l}\left[2\left(\frac{1}{r\sin\theta}\frac{\partial v_\phi}{\partial \phi} + \frac{v_r}{r} + \frac{v_\theta \cot\theta}{r}\right)\right. \\ \left. -\frac{2}{3}(\nabla \cdot \boldsymbol{v})\right]\end{array}$
	$\tau_{r\theta} = \tau_{\theta r} = -\mu\left[r\frac{\partial}{\partial y}\left(\frac{v_\theta}{r}\right) + \frac{1}{r}\frac{\partial v_r}{\partial \theta}\right]$
	$\tau_{\theta\phi} = \tau_{\phi\theta} = -\mu\left[\frac{\sin\theta}{r}\frac{\partial}{\partial \theta}\left(\frac{v_\phi}{\sin\theta}\right) + \frac{1}{r\sin\theta}\frac{\partial v_\theta}{\partial \phi}\right]$
	$\tau_{\phi r} = \tau_{r\phi} = -\mu\left[\frac{1}{r\sin\theta}\frac{\partial v_r}{\partial \phi} + r\frac{\partial}{\partial r}\left(\frac{v_\phi}{r}\right)\right]$

In order to solve the continuity and momentum balance equations (Eq. (1)) the following *constitutive laws* have to be taken into account:

$$\begin{cases} \rho = \rho(p, T) \\ \mu = \mu(p, T) \end{cases} \tag{2}$$

If the flow is isothermal, Eqs. (1) and (2) allow the calculation of the pressure field and of the velocity vector (p, $\boldsymbol{v}$) in the fluid region.

It is possible to demonstrate that, for Newtonian fluids with constant viscosity μ, the following equality is satisfied:

$$(\nabla \cdot \boldsymbol{\tau})_i = -\mu\left[\nabla^2 v_i + \frac{1}{3}\frac{\partial}{\partial i}(\nabla \cdot \boldsymbol{v})\right] \tag{3}$$

where $i = x, y, z$ for Cartesian coordinates.

Combining Eq. (3) and the momentum equation one obtains

$$\rho \frac{\mathrm{D}\boldsymbol{v}}{\mathrm{D}t} = -\nabla p + \rho \boldsymbol{g} + \mu \left[\nabla^2 \boldsymbol{v} + \frac{1}{3} \nabla \left(\nabla \cdot \boldsymbol{v} \right) \right] \tag{4}$$

This version of the momentum equation is known as the *Navier–Stokes equation.*

For an incompressible ($\rho = \text{const}$) and Newtonian fluid with constant viscosity ($\mu = \text{const}$) the continuity and the momentum balance equations can be written as follows:

$$\nabla \cdot \boldsymbol{v} = 0$$

$$\rho \frac{\mathrm{D}\boldsymbol{v}}{\mathrm{D}t} = -\nabla p + \rho \boldsymbol{g} + \mu \nabla^2 \boldsymbol{v} \tag{5}$$

The momentum balance equation can be simplified in the case of very slow fluid motion. In this case the total derivative of the velocity and the acceleration due to the gravity can be neglected in the *Navier–Stokes equation*:

$$\mu \nabla^2 \boldsymbol{v} = \nabla p \tag{6}$$

Equation (6) applies to the analysis of fluid behavior in tribology and microchannel flows: this kind of flow is called *Stokes flow*. In this case, the velocities are free of macroscopic fluctuations at any point in the flow field and the flow is defined as *laminar*.

For a laminar flow through a straight microchannel the fluid particles move in definite paths called streamlines and there are no components of fluid velocity normal to the duct axis. The projection of Eq. (6) along the axial direction (z) gives

$$\mu \nabla^2 v_z = \frac{\mathrm{d}p}{\mathrm{d}z} \tag{7}$$

Equations (6) and (7) are valid only far from the inlet section of the microchannel (see ►developing flows and ►entrance region) where the velocity profile can be considered hydrodynamically fully developed. Laminar flow is designated as hydrodynamically fully developed when the fluid velocity distribution at a cross-section is of an invariant form independent of the axial distance z.

Laminar Regime

Let us consider a liquid flowing through a straight microchannel having an axially unchanging and uniform cross-section with an area equal to Ω and the perimeter equal to Γ. It is possible to define the *hydraulic diameter* of the microchannel as follows:

$$D_\mathrm{h} = \frac{4\Omega}{\Gamma} \tag{8}$$

and the *mean fluid velocity* as the integrated average axial velocity over the flow area Ω:

$$W = \frac{1}{\Omega} \int\limits_{\Omega} v_z d\Omega = \frac{\dot{m}}{\rho \Omega} \tag{9}$$

in which the link with measurable quantities, like the mass flow rate, is highlighted.

It is suitable to introduce the dimensionless quantities

$$\Omega^* = \frac{\Omega}{D_\mathrm{h}^2}; \quad \Gamma^* = \frac{\Gamma}{D_\mathrm{h}}; \quad \nabla^* = D_\mathrm{h} \nabla;$$

$$V_z = \frac{v_z}{W}; \quad c_1 = -\frac{D_\mathrm{h}^2}{\mu W} \frac{\mathrm{d}p}{\mathrm{d}z} \tag{10}$$

Consequently, the dimensionless momentum balance equation is readily obtained in the following form:

$$\nabla^{*2} V_z + c_1 = 0 \tag{11}$$

In order to characterize a liquid flow through microchannels under an imposed pressure gradient Eq. (11) can be used together with the appropriate boundary condition that, for Newtonian liquids, is the no-slip boundary condition at the walls:

$$V_z|_{\Gamma^*} = 0 \tag{12}$$

For a Newtonian liquid flow, this assumption is justified if the microchannel has a hydraulic diameter larger than 1 μm. In fact, for liquids the typical mean free path λ of molecules under ambient conditions is 0.1 – 1 nm. Since the fluid velocity tends to evidence a slip at the microchannel walls for Knudsen numbers, defined as $\mathrm{Kn} = \lambda / D_\mathrm{h}$, larger than 0.001, the no-slip boundary condition has to be abandoned only when the hydraulic diameter of the microchannel becomes less than 1 μm.

On the contrary, for non-Newtonian liquids, like polymer solutions and surfactants, a slip velocity at the walls can be observed even for microchannels having a hydraulic diameter greater than 1 μm.

The solution of Eqs. (11) and (12) yields the velocity distribution inside the microchannel in the laminar regime for fully developed flow. The analytical solution of this differential problem is available only for very simple geometries.

From the velocity distribution obtained by the solution of Eqs. (11) and (12) it is possible to calculate the value assumed by the main flow parameters which can be useful during the design stage of a microfluidic device:

- the *ratio between the maximum and the mean value of the velocity* (V_max):

$$V_{\max} = \frac{v_{z,\max}}{W} \tag{13}$$

- the asymptotic value of the *momentum flux correction factor* K_d defined as:

$$K_\mathrm{d} = \frac{1}{\Omega^*}\int\limits_{\Omega^*} V_z^2 \,\mathrm{d}\Omega^* \tag{14}$$

- the asymptotic *kinetic energy correction factor* K_e defined as:

$$K_\mathrm{e} = \frac{1}{\Omega^*}\int\limits_{\Omega^*} V_z^3 \,\mathrm{d}\Omega^* \tag{15}$$

- the asymptotic *incremental pressure drop number* $K(\infty)$:

$$K(\infty) = \frac{2}{\Omega^*}\int\limits_{\Omega^*} \left[\left(V_z^3 - V_z^2\right)\right] \mathrm{d}\Omega^* = 2\left(K_\mathrm{e} - K_\mathrm{d}\right) \tag{16}$$

- the *Poiseuille number* defined as the product of the Fanning friction factor for fully developed flow (f) and the Reynolds number ($\mathrm{Re} = \rho W D_\mathrm{h}/\mu$):

$$(f\mathrm{Re})_\mathrm{fd} = -\frac{1}{2\Omega^*}\int\limits_{\Gamma^*} \left.\frac{\partial V_z}{\partial n^*}\right|_{\Gamma^*} \mathrm{d}\Gamma^* = \frac{c_1}{2} \tag{17}$$

  where n^* is the normal direction to the walls.

For Newtonian laminar flows these parameters depend on the geometry of the microchannel cross-section only.

Circular Cross-Section

For a channel with a circular cross-section it is possible to demonstrate that the velocity distribution, written in dimensionless form, is

$$V_z(r^*) = 2(1 - 4r^{*2}) \tag{18}$$

in which r^* is the dimensionless radius defined as r/D_h with D_h being the inner diameter.

In Table 2 the values assumed by $V_{\max}$, K_d, K_e, $K(\infty)$ and $f\mathrm{Re}_\mathrm{fd}$ are quoted for this geometry.

Elliptical Cross-Section

Microtubes with elliptical cross-section in which fully developed laminar flow occurs are geometrically characterized by the value of the aspect ratio β defined as ratio between the minor (h) and the major (a) axes (see Fig. 1).

Pressure-Driven Single Phase Liquid Flows, Table 2 Analytical laminar fully developed values of $V_{\max}$, K_d, K_e, $K(\infty)$ and of the Poiseuille number ($f\mathrm{Re}_\mathrm{fd}$) for circular microtubes

$V_{\max}$	K_d	K_e	$K(\infty)$	$f\mathrm{Re}_\mathrm{fd}$
2	4/3	2	4/3	16



Pressure-Driven Single Phase Liquid Flows, Figure 1 Schematic of the elliptical cross-section and of the Cartesian coordinate system

The fully developed laminar velocity profile is

$$V_z(x^*, y^*) = 8\left(\frac{1}{4} - x^{*2} - y^{*2}\right) \tag{19}$$

in which x^* and y^* are dimensionless coordinates defined as x/a and y/h respectively and the Cartesian coordinate system has its origin at the center of the channel (see Fig. 1).

It is possible to demonstrate by using Eq. (19) that $V_{\max}$, K_d, K_e and $K(\infty)$ assume the same values as those for circular cross-section (see Table 2) for any β.

The fully developed Poiseuille number can be calculated analytically by means of the following relation:

$$f\mathrm{Re}_\mathrm{fd} = 2\pi^2\left(1 + \beta^2\right)\left[\frac{1}{E(1 - \beta^2)}\right]^2 \tag{20}$$

where E denotes the complete elliptical integral of the second kind.

In Table 3 the value of the fully developed Poiseuille number is quoted as a function of the aspect ratio β of the elliptical cross-section.

Concentric Annular Cross-Section

The solution of Eq. (11) with the no-slip boundary condition (Eq. (12)) through an annular channel with an inner radius equal to r_i and an outer radius equal to r_o (see Fig. 2) can be written as follows:

$$V_z(r^*) = \frac{2}{\left[1 + \beta^2 - 2r_\mathrm{m}^{*2}\right]}\left(1 - r^{*2} + 2r_\mathrm{m}^{*2}\ln(r^*)\right) \tag{21}$$

in which β is the aspect ratio of the annuli defined as $r_\mathrm{i}/r_\mathrm{o}$, r^* is the dimensionless radius defined as r/r_o and r^*_m is given by

$$r^*_\mathrm{m} = \left[\frac{1-\beta^2}{2\ln\left(\frac{1}{\beta}\right)}\right]^{\frac{1}{2}} \tag{22}$$

and designates the dimensionless radius corresponding to the maximum value of the velocity.



Pressure-Driven Single Phase Liquid Flows, Figure 2 Schematic of the annular cross-section

Pressure-Driven Single Phase Liquid Flows, Table 3 Analytical laminar fully developed values of V_max, K_d, K_e, $K(\infty)$ and of the Poiseuille number ($f\mathrm{Re}_\mathrm{fd}$) for elliptical microtubes as a function of the aspect ratio β

β	$f\mathrm{Re}_\mathrm{fd}$
1	16
0.9	16.022
0.8	16.098
0.75	16.161
0.7	16.244
2/3	16.311
0.6	16.479
0.5	16.823
0.4	17.294
1/3	17.681
0.3	17.896
0.25	18.24
0.2	18.602
1/6	18.847
1/7	19.02
1/8	19.146
1/9	19.241
1/10	19.314
1/16	19.536
1/20	19.598



Pressure-Driven Single Phase Liquid Flows, Figure 3 Schematic of the rectangular cross-section with the Cartesian coordinate system used in (**a**) Eq. (25) and (**b**) Eq. (28)

For this geometry a closed form solution for V_max and the Poiseuille number is known:

$$\begin{aligned}
V_\mathrm{max} &= 2\frac{\left(1-r^{*2}_\mathrm{m}+2r^{*2}_\mathrm{m}\ln(r^*_\mathrm{m})\right)}{1+\beta^2-2r^{*2}_\mathrm{m}} \\
f_\mathrm{i}\mathrm{Re}_\mathrm{fd} &= 16\frac{(1-\beta)}{\beta\left(1+\beta^2-2r^{*2}_\mathrm{m}\right)}\left(r^{*2}_\mathrm{m}-\beta^2\right) \\
f_\mathrm{o}\mathrm{Re}_\mathrm{fd} &= 16\frac{(1-\beta)}{\left(1+\beta^2-2r^{*2}_\mathrm{m}\right)}\left(1-r^{*2}_\mathrm{m}\right) \\
f\mathrm{Re}_\mathrm{fd} &= \frac{16}{\left(1+\beta^2-2r^{*2}_\mathrm{m}\right)}\left(1-r^{*2}_\mathrm{m}\right)
\end{aligned} \tag{23}$$

where f_i and f_o designate the Fanning friction factors at the inner and outer walls respectively and $f\mathrm{Re}_\mathrm{fd}$ is the perimeter average Poiseuille number:

$$f\mathrm{Re}_\mathrm{fd} = \frac{\beta f_\mathrm{i}\mathrm{Re}+\beta f_\mathrm{o}\mathrm{Re}}{1+\beta} \tag{24}$$

In Table 4 the value assumed by V_max, K_d, K_e and $f\mathrm{Re}_\mathrm{fd}$ are quoted for this geometry as a function of the aspect ratio β. It is evident that, the circular geometry can be considered as the limit case for $\beta = 0$ and the parallel plate geometry for $\beta = 1$.

Rectangular Cross-Section

For a rectangular channel with an aspect ratio $\beta = h/a$ (see Fig. 3a), for which a Cartesian system of coordinates x, y, z is assumed, with its origin in the left bottom corner of the inlet rectangular cross-section (y along the side with length h and z perpendicular to the cross-section), the analytical solution of Eqs. (11) and (12) gives the following velocity distribution:

$$\begin{aligned}
V_z(x^*, y^*) = &\sum_{n=1,\mathrm{odd}}^{\infty}\ \sum_{m=1,\mathrm{odd}}^{\infty} v_{n,m}\sin\left(n\pi\frac{2\beta}{1+\beta}x^*\right) \\
&\times\sin\left(m\pi\frac{2}{1+\beta}y^*\right)
\end{aligned} \tag{25}$$

Pressure-Driven Single Phase Liquid Flows, Table 4 Analytical laminar fully developed values of r_{m}^*, $V_{\max}$, K_{d}, K_{e}, and of the inner, outer and average Poiseuille number ($f\mathrm{Re}_{\mathrm{fd}}$) for annular microtubes as a function of the aspect ratio β

β	r_{m}^*	$V_{\max}$	K_{d}	K_{e}	$f_{\mathrm{i}}\mathrm{Re}$	$f_{\mathrm{o}}\mathrm{Re}$	$f\mathrm{Re}_{\mathrm{fd}}$
0.0001	0.233	1.767	1.298	1.863	9742.834	16.973	17.945
0.001	0.269	1.725	1.287	1.823	1352.776	17.337	18.671
0.01	0.329	1.661	1.266	1.753	219.426	18.034	20.028
0.05	0.408	1.598	1.243	1.675	74.459	18.923	21.567
0.1	0.464	1.567	1.230	1.634	50.886	19.489	22.343
0.15	0.508	1.549	1.222	1.610	42.027	19.904	22.790
0.2	0.546	1.537	1.217	1.594	37.264	20.253	23.088
0.3	0.615	1.522	1.210	1.573	32.166	20.850	23.461
0.4	0.677	1.513	1.206	1.561	29.437	21.375	23.678
0.5	0.736	1.508	1.204	1.555	27.719	21.859	23.813
0.6	0.791	1.504	1.202	1.549	26.529	22.318	23.897
0.75	0.872	1.501	1.200	1.546	25.295	22.971	23.967
0.8	0.898	1.501	1.200	1.544	24.978	23.182	23.980
0.9	0.950	1.500	1.200	1.543	24.440	23.596	23.996

in which the series coefficients $v_{n,m}$ are defined as

$$v_{n,m} = \frac{\pi^2}{4mn\left(\beta^2 n^2 + m^2\right)} \frac{1}{\sum\limits_{i=1,\mathrm{odd}}^{\infty} \sum\limits_{j=1,\mathrm{odd}}^{\infty} \frac{1}{i^2 j^2 \left(\beta^2 i^2 + j^2\right)}} \tag{26}$$

and x^* and y^* are the dimensionless coordinates defined as x/D_{h} and y/D_{h} respectively.

It is easy to demonstrate that for a rectangular cross-section the hydraulic diameter D_{h}, the aspect ratio β and the length of the sides (a, h) are correlated:

$$a = \frac{1+\beta}{2\beta} D_{\mathrm{h}}; \quad h = \frac{1+\beta}{2} D_{\mathrm{h}} \tag{27}$$

Since Eq. (25) involves considerable computational complexity, a simple approximation in the following form, validated for $\beta \le 0.5$, can be suggested:

$$V_z(x^*, y^*) = \left(\frac{w+1}{w}\right)\left(\frac{k+1}{k}\right)\left[1 - \left(\frac{4}{1+\beta} y^*\right)^w\right] \times \left[1 - \left(\frac{4\beta}{1+\beta} x^*\right)^k\right] \tag{28}$$

but in this case the origin of the Cartesian system of coordinates x, y, z is assumed at the center of the cross-section ($a/2$, $h/2$) (see Fig. 3b).

The exponents w and k can be calculated by means of the following empirical correlations:

$$k = 1.7 + 0.5\beta^{-1.4}$$
$$w = \begin{cases} 2 & \text{for } \beta \le \frac{1}{3} \\ 2 + 0.3\left(\beta - \frac{1}{3}\right) & \text{for } \beta > \frac{1}{3} \end{cases} \tag{29}$$

In Table 5 the values assumed by $V_{\max}$, K_{d}, K_{e}, $K(\infty)$ and $f\mathrm{Re}_{\mathrm{fd}}$ are quoted for this geometry as a function of the microchannel aspect ratio β. It is evident that, owing to the symmetry of the cross-section, for microchannels having β greater than 1, one can use $1/\beta$ in order to calculate the integral parameters from Table 5.

Parallel Plates

Very shallow rectangular microchannels with $h \ll a$ (or, for symmetry, in the case that $h \gg a$) are characterized by low values of the aspect ratio ($\beta = 0$); in this case the rectangular microchannel can be modeled as two parallel plates. It is possible to demonstrate that for parallel plates with a plate spacing equal to h, the fully developed laminar velocity profile can be written as follows:

$$V_z(y^*) = \frac{3}{2}\left[1 - 16\left(y^*\right)^2\right] \tag{30}$$

in which y^* is the dimensionless coordinate defined as y/D_{h} with $D_{\mathrm{h}} = 2h$, as obtained by Eq. (27) for $\beta = 0$. As depicted in Fig. 4, in this case the origin of the Cartesian coordinate system is assumed as placed at the center of the channel.

Pressure-Driven Single Phase Liquid Flows, Table 5 Laminar fully developed values of $V_{\max}$, K_{d}, K_{e}, $K(\infty)$ and of the Poiseuille number ($f\mathrm{Re}_{\mathrm{fd}}$) for rectangular microchannels as a function of the aspect ratio β

β	$V_{\max}$	K_{d}	K_{e}	$K(\infty)$	$f\mathrm{Re}$
0	1.500	1.200	1.543	0.686	24.000
0.01	1.510	1.204	1.554	0.7	23.677
0.05	1.549	1.218	1.599	0.762	22.477
0.1	1.601	1.237	1.656	0.838	21.169
0.2	1.715	1.271	1.770	0.998	19.071
0.3	1.829	1.303	1.878	1.15	17.512
0.4	1.924	1.328	1.969	1.282	16.368
0.5	1.992	1.347	2.039	1.384	15.548
0.6	2.038	1.361	2.088	1.454	14.980
0.7	2.067	1.370	2.121	1.502	14.605
0.8	2.085	1.375	2.141	1.532	14.378
0.9	2.094	1.378	2.151	1.546	14.261
1	2.096	1.379	2.154	1.55	14.227



Pressure-Driven Single Phase Liquid Flows, Figure 4 Schematic of the parallel plate cross-section with its Cartesian coordinate system

The values assumed by $V_{\max}$, K_{d}, K_{e}, $K(\infty)$ and $f\mathrm{Re}_{\mathrm{fd}}$ are given in Table 5 for $\beta = 0$.

Triangular Channels

The fully developed laminar velocity profile for isosceles triangular ducts (see Fig. 5a) can be in general determined by solving numerically Eq. (11) with Eq. (12). Shah and London [4] reported the following approximate closed-form solution for the velocity profile for isosceles triangular channels:

$$V_z(x^*, y^*) = \frac{3(B+2)}{(B-2)}\left[4y^{*2} - x^{*2}\right]\left[x^{*B-2} - 1\right]$$
$$B = \left[4 + \frac{5}{2}\left(\frac{1}{\tan^2\phi} - 1\right)\right]^{\frac{1}{2}} \qquad (31)$$



Pressure-Driven Single Phase Liquid Flows, Figure 5 Schematic of (**a**) the isosceles triangular cross-section and (**b**) an equilateral triangular microchannel with rounded corners

where x^* and y^* are dimensionless coordinates defined as x/a and y/h (see Fig. 5a). For the isosceles triangular ducts the hydraulic diameter can be calculated by means of the following equation:

$$D_{\mathrm{h}} = \frac{a\sin\phi}{1+\sin\phi} = \frac{h\cos\phi}{1+\sin\phi} \qquad (32)$$

It can be demonstrated that the maximum value of the velocity occurs at $y^* = 0$ (for the symmetry) and

$$x^*_{\mathrm{m}} = \sqrt[B-2]{\frac{2}{B}} \qquad (33)$$

The fully developed Poiseuille number can be calculated by means of the following equation:

$$f\mathrm{Re}_{\mathrm{fd}} = \frac{12(B+2)(1-\tan^2\phi)}{(B-2)\left[\tan^2\phi + (1+\tan^2\phi)^{\frac{1}{2}}\right]^2} \qquad (34)$$

The numerical results obtained by Shah and London [4] for $V_{\max}$, K_{d}, K_{e}, $K(\infty)$ and $f\mathrm{Re}_{\mathrm{fd}}$ for this geometry are quoted in Table 6.

Because the manufacturing processes employed sometimes produces microchannels of triangular cross-section with one, two or three rounded corners instead of sharp corners, in Table 7 the numerical results obtained by Shah and London [4] for an equilateral triangular microchannel with rounded corners in terms of $V_{\max}$,K_{d}, K_{e}, $K(\infty)$ and $f\mathrm{Re}_{\mathrm{fd}}$ are quoted. The radius of each rounded corner is considered as $a/3$, as shown in Fig. 5b, with $2a$ as the side length of the base triangle.

Trapezoidal Channels

It is well known that with a photolithographic-based process one can obtain microchannels having a cross-section fixed by the orientation of the wafer crystal planes; for example, the microchannels etched in ⟨100⟩ silicon using

Pressure-Driven Single Phase Liquid Flows, Table 6 Laminar fully developed values of x_m^*, V_{max}, K_d, K_e and of the Poiseuille number ($f\mathrm{Re}_{fd}$) for isosceles triangular microchannels as a function of the apex angle ϕ or the aspect ratio a/h

a/h	ϕ	V_{max}	x_m*	K_d	K_e	$f\mathrm{Re}_{fd}$
8.003	3.58	2.593	0.896	1.545	2.805	12.352
5.715	5.00	2.521	0.871	1.526	2.731	12.474
4.000	7.13	2.442	0.839	1.505	2.64	12.636
2.836	10.00	2.368	0.805	1.482	2.546	12.822
2.000	14.04	2.302	0.766	1.459	2.454	13.026
1.866	15.00	2.29	0.758	1.455	2.438	13.065
1.500	18.44	2.259	0.732	1.443	2.392	13.181
1.374	20.00	2.249	0.722	1.439	2.377	13.222
1.072	25.00	2.228	0.692	1.431	2.347	13.307
1.003	26.50	2.225	0.684	1.43	2.342	13.321
0.866	30.00	2.222	0.667	1.429	2.338	13.333
0.750	33.69	2.225	0.650	1.43	2.342	13.321
0.714	35.00	2.227	0.645	1.431	2.345	13.311
0.596	40.00	2.241	0.626	1.436	2.366	13.248
0.500	45.00	2.264	0.608	1.445	2.4	13.153
0.289	60.00	2.38	0.565	1.489	2.571	12.744
0.251	63.34	2.416	0.559	1.499	2.617	12.622
0.134	75.00	2.587	0.530	1.543	2.815	12.226
0.125	75.97	2.605	0.527	1.548	2.835	12.196

Pressure-Driven Single Phase Liquid Flows, Table 7 Laminar fully developed values of V_{max}, K_d, K_e and of the Poiseuille number ($f\mathrm{Re}_{fd}$) for equilateral triangular microchannels with one, two, three rounded corners

	V_{max}	K_d	K_e	$f\mathrm{Re}_{fd}$
No rounded corners	2.222	1.429	2.338	13.333
One rounded corner	2.172	1.406	2.254	14.057
Two rounded corners	2.115	1.379	2.163	14.899
Three rounded corners	2.064	1.353	2.074	15.993



Pressure-Driven Single Phase Liquid Flows, Figure 6 (**a**) KOH-etched trapezoidal cross-section and (**b**) KOH-etched double-trapezoidal cross-section

a KOH solution have a trapezoidal cross-section with an apex angle of 54.74° imposed by the crystallographic morphology of the ⟨100⟩ silicon. By gluing together two KOH-etched trapezoidal silicon microchannels one can obtain microchannels having a double-trapezoidal cross-section (see Fig. 6). These cross-sectional geometries are investigated in this section.

Only numerical solutions of Eq. (11) have appeared in the open literature for this kind of geometry.

In Tables 8 and 9 the numerical results for KOH-etched trapezoidal and KOH-etched double trapezoidal microchannels respectively in terms of V_{max}, K_d, K_e, $K(\infty)$ and $f\mathrm{Re}_{fd}$ are given.

Two different definitions of the aspect ratio are used in the literature for trapezoidal channels ($\beta = h/a$ or $\gamma = h/b$ with reference to the symbols quoted in Fig. 6a). In Table 8, both β and γ are quoted in order to simplify the use of the data. For a ⟨100⟩ silicon microchannel the aspect ratio β cannot exceed the value of $\tan(\phi)/2$ (equal to 0.707 for $\phi = 54.74°$) corresponding to the degeneration of the channel cross-section to the triangular geometry ($\gamma = \infty$). The aspect ratio β of a double-trapezoidal channel is defined as the ratio between the height (h) and the maximum width (a); β can assume all the values between 0, the parallel plate configuration, and 1.414, the rhombic configuration.

Comparison Among Microchannel Cross-Sections

The data illustrated in the above sections can be used in order to minimize the pressure drop in a microfluidic

Pressure-Driven Single Phase Liquid Flows, Table 8 Laminar fully developed values of $V_{\max}$, K_d, K_e, $K(\infty)$ and of the Poiseuille number ($f\mathrm{Re}_{fd}$) for KOH-etched trapezoidal microchannels as a function of the aspect ratio $\beta = h/a$ or $\gamma = h/b$

γ	β	$V_{\max}$	K_d	K_e	$K(\infty)$	$f\mathrm{Re}_{fd}$
0	0.000	1.5	1.2	1.543	0.686	24
0.01	0.010	1.511	1.205	1.556	0.702	23.597
0.0277	0.027	1.530	1.212	1.580	0.736	22.931
0.05	0.047	1.555	1.222	1.610	0.776	22.174
0.1	0.088	1.610	1.243	1.674	0.862	20.737
0.2	0.156	1.719	1.279	1.793	1.028	18.650
0.3	0.211	1.822	1.310	1.897	1.174	17.244
0.4	0.255	1.908	1.334	1.984	1.300	16.263
0.5	0.293	1.976	1.354	2.054	1.400	15.565
0.6	0.325	2.027	1.368	2.108	1.480	15.060
0.7	0.352	2.065	1.379	2.150	1.542	14.690
0.8	0.375	2.094	1.388	2.182	1.588	14.417
0.9	0.396	2.116	1.394	2.207	1.626	14.215
1	0.414	2.132	1.399	2.225	1.652	14.063
1/0.9	0.432	2.146	1.403	2.241	1.676	13.940
1.25	0.452	2.158	1.407	2.254	1.694	13.832
1/0.7	0.473	2.168	1.410	2.266	1.712	13.745
1/0.6	0.497	2.177	1.412	2.275	1.726	13.685
2	0.522	2.183	1.414	2.282	1.736	13.654
2.5	0.551	2.189	1.415	2.287	1.744	13.654
1/0.3	0.583	2.196	1.417	2.294	1.754	13.679
5	0.620	2.206	1.420	2.307	1.774	13.694
10	0.660	2.219	1.426	2.330	1.808	13.622
∞	0.707	2.228	1.431	2.346	1.830	13.308

device with microchannels. In Fig. 7 a comparison among rectangular, KOH-etched trapezoidal microchannels and KOH-etched double-trapezoidal microchannels in terms of friction factor as a function of the aspect ratio β is shown. It is evident that, for a fixed value of the aspect ratio, the trapezoidal geometry allows the achievement of lower friction factors than the other cross-sections. The differences among the cross-sections in terms of friction factors decrease when the aspect ratio decreases.

A fifth-order polynomial approximation for calculating $f\mathrm{Re}_{fd}$, K_d and K_e as a function of the channel aspect ratio (β) is given with the aim of offering a very simple but accurate tool for technicians and designers involved in microfluidic applications:

$$f\mathrm{Re}_{fd} \text{ or } K_d \text{ or } K_e = \sum_{n=0}^{5} g_i \beta^n \qquad (35)$$

The values of the constants g_i are listed in Table 10 for microchannels having rectangular, trapezoidal and double-trapezoidal cross-sections;, the maximum relative differ-



Pressure-Driven Single Phase Liquid Flows, Figure 7 Laminar fully developed Poiseuille number for KOH-etched trapezoidal microchannels, KOH-etched double-trapezoidal microchannels and rectangular microchannels as a function of the aspect ratio

Pressure-Driven Single Phase Liquid Flows, Table 9 Laminar fully developed values of V_{max}, K_d, K_e, $K(\infty)$ and of the Poiseuille number ($f\text{Re}_{fd}$) for KOH-etched double-trapezoidal microchannels as a function of the aspect ratio β

β	V_{max}	K_d	K_e	$K(\infty)$	$f\text{Re}_{fd}$
0	1.500	1.200	1.543	0.686	24.000
0.02	1.518	1.207	1.563	0.712	23.459
0.1	1.598	1.233	1.648	0.830	21.507
0.2	1.717	1.267	1.758	0.982	19.501
0.4	1.931	1.321	1.950	1.258	16.746
0.5	1.989	1.337	2.007	1.340	15.923
0.6	2.019	1.346	2.039	1.386	15.403
0.7	2.030	1.350	2.053	1.406	15.126
0.8	2.033	1.351	2.057	1.412	15.027
0.9	2.036	1.351	2.060	1.418	15.043
1	2.044	1.353	2.068	1.430	15.111
1.2	2.083	1.369	2.123	1.508	15.081
1.3	2.106	1.381	2.164	1.566	14.785
1.414	2.119	1.388	2.188	1.600	14.055

ence Δ quoted in Table 10 is positive when Eq. (35) gives values greater than the rigorous calculation.

Laminar-to-Turbulent Transition

The laminar regime in a channel holds until the Reynolds number reaches a critical value above which the laminar motion becomes unstable and a transition to a turbulent flow will generally occur. It has been demonstrated experimentally that for a microchannel the critical value of the Reynolds number depends on the entrance conditions, on the cross-section geometry and on the wall roughness. The effect of the roughness on the laminar-to-turbulent transition is very important and it can be evidenced by observing Fig. 8 in which the experimental values of the Poiseuille number (fRe) are shown as a function of the Reynolds number for two microtubes made in stainless steel and in fused silica. The stainless steel microtube has an internal diameter of 133 μm and a relative roughness (e/D) equal to 3%, while the tube made in fused silica is characterized by an internal diameter equal to 100 μm and a relative roughness equal to 0.1%. The agreement with the Poiseuille law is confirmed for low values of the Reynolds number ($\text{Re} < 1600$). The stainless steel microtube exhibits an earlier deviation from the Poiseuille law at Re equal to 1600. On the contrary, for the smoother microtube in fused silica the Poiseuille law holds up to Re equal to 2300. In general, for smooth microtubes the critical Reynolds number is about 2000 – 2300, in agreement with the behavior of macrotubes. On the contrary, for rough microtubes it can be concluded that higher relative roughness tends to anticipate the transition and thus decreases the value of the critical Reynolds number down to 1700 – 1800.



Pressure-Driven Single Phase Liquid Flows, Figure 8 Effect of the relative roughness on the laminar-to-turbulent transition in a microtube

Turbulent Regime

For Reynolds numbers larger than the critical Reynolds number the flow becomes turbulent and the fluid velocity at a point can be defined as the mean value of the velocity at this point with respect to time by taking a time interval t_0 larger than the typical time of one turbulent fluctuation and shorter than the typical time of pressure variations. Since mass and momentum must be conserved in turbulent as well as in laminar flow, the conservation equations (Eq. (1)) hold equally for turbulent flow, provided the velocities and pressures in these equations are interpreted as instantaneous velocities and pressures of the turbulent field. From a practical standpoint such equations are of little value because there is no interest in knowing the complete and complex history of instantaneous velocities and pressures but only their time-mean values that can be measured and observed (see also ►turbulence in microchannels). In microchannels with hydraulic diameters less than 500 μm the maximum value that the Reynolds number can assume drops to between 10,000 and 30,000. In fact, in order to reach these values of the Reynolds number a very large pressure difference has to be imposed at the ends of the microchannels. For this reason, the analysis of the turbulence in microchannels is bounded to Reynolds numbers less than 30,000.

Circular Cross-Section

The time-mean value of the dimensionless velocity $\langle V_z \rangle$ can be written in fully developed turbulent flow in a micro-

Pressure-Driven Single Phase Liquid Flows, Table 10 Polynomial coefficients appearing in Eq. (35) for rectangular, KOH-etched trapezoidal and double-trapezoidal silicon microchannels

Rectangular microchannel $0 < \beta < 1$							
	g_0	g_1	g_2	g_3	g_4	g_5	Δ (%)
$f\mathrm{Re}_{\mathrm{fd}}$	24	−32.5272	46.7208	−40.8288	22.9536	−6.0888	0.06
K_{d}	1.2	0.3563	0.1532	−0.8946	0.7953	−0.2312	0.05
K_{e}	1.543	1.0376	1.1632	−3.8892	3.1821	−0.8831	0.10
KOH-etched trapezoidal microchannel $0 < \beta < 0.707$							
	g_0	g_1	g_2	G_3	g_4	g_5	Δ (%)
$f\mathrm{Re}_{\mathrm{fd}}$	24	−42.267	64.272	−118.42	242.12	−178.79	−0.14
K_{d}	1.2	0.3962	0.9808	−1.4388	−2.5004	3.3655	−0.27
K_{e}	1.543	1.1296	3.7251	−2.6799	−14.585	15.496	−0.68
KOH-etched double-trapezoidal microchannel $0 < \beta < 1.414$							
	g_0	g_1	g_2	g_3	g_4	g_5	Δ (%)
$f\mathrm{Re}_{\mathrm{fd}}$	24	−27.471	26.117	−6.6351	−0.2956	−0.5974	0.05
K_{d}	1.2	0.2833	0.5441	−1.7965	1.5499	−0.4277	−0.1
K_{e}	1.543	0.8343	2.3859	−6.9184	5.8104	−1.5876	−0.25

tube as follows:

$$\langle V_z \rangle = \left(1 - 2r^*\right)^{\frac{1}{m}}$$

$$m = \begin{cases} 6 & 4000 < \mathrm{Re} < 110{,}000 \\ 7 & 110{,}000 \leq \mathrm{Re} < 3{,}200{,}000 \\ 10 & \mathrm{Re} > 3{,}200{,}000 \end{cases} \tag{36}$$

in which the following dimensionless quantities are used:

$$\langle V_z \rangle = \frac{\langle v_z \rangle}{\langle W \rangle}; \quad r^* = \frac{r}{D} \tag{37}$$

The ratio $\langle V_{\max} \rangle$ can be computed by using the following equation:

$$\langle V_{\max} \rangle = \frac{\langle v_{z,\max} \rangle}{\langle W \rangle} = \frac{(m+1)(2m+1)}{2m^2} \tag{38}$$

Parallel Plate Cross-Section

For shallow rectangular microchannels, having a low value of the aspect ratio β, the rectangular cross-section can be modeled as a parallel plate geometry (see Fig. 4). In this case one obtains that the velocity distribution for fully developed turbulent flows becomes the following:

$$\frac{\langle v_z \rangle}{v^*} = \frac{1}{k}\left[\ln\left(1 - \sqrt{4y^*}\right) + \sqrt{4y^*}\right] + \frac{\langle v_{z,\max} \rangle}{v^*}$$
$$\left(0 \leq y^* \leq \frac{1}{4}\right) \tag{39}$$

in which $y^* = y/D_{\mathrm{h}}$ with $D_{\mathrm{h}} = 2h$, ($\boldsymbol{\tau}_0$ is the wall shear stress) and $k = 0.36$.

Friction Factor

For Newtonian fluids, the Fanning friction factor f is defined in terms of the wall shear stress as

$$f = \frac{\boldsymbol{\tau}_0}{\frac{\rho W^2}{2}} \tag{40}$$

For turbulent fully developed flow ($\mathrm{Re} > 10{,}000$) in a *smooth* microtube, the Fanning friction factor can be calculated from the *Karman–Nikuradse relation*:

$$\frac{1}{\sqrt{4f_{\mathrm{fd}}}} = -0.8 + 0.87\ln\left(\mathrm{Re}\sqrt{4f_{\mathrm{fd}}}\right) \tag{41}$$

In the range $5000 < \mathrm{Re} < 30{,}000$, in which in general microtubes could work, the *Blasius equation* may be used instead of Eq. (41) for smooth tubes:

$$f_{\mathrm{fd}} = \frac{0.079}{\mathrm{Re}^{0.25}} \tag{42}$$

In *rough* microtubes, like metallic microtubes, the effect of the inner roughness e on the friction factor cannot be neglected and the friction factor can be calculated by using the *Colebrook correlation*:

$$\frac{1}{\sqrt{4f_{\mathrm{fd}}}} = -2.0\log\left[\frac{\frac{e}{D_{\mathrm{h}}}}{3.7} + \frac{2.51}{\mathrm{Re}\sqrt{4f_{\mathrm{fd}}}}\right] \tag{43}$$



Pressure-Driven Single Phase Liquid Flows, Figure 9 Model for pressure drop analysis of multiple microchannel systems

Since the *Colebrook correlation* is awkward to use, an approximate explicit relation for the friction factor was published by *Haaland*:

$$\frac{1}{\sqrt{4f_{\mathrm{fd}}}} = -1.8 \log\left[\left(\frac{\frac{e}{D_{\mathrm{h}}}}{3.7}\right)^{1.11} + \frac{6.9}{\mathrm{Re}}\right] \tag{44}$$

This relation gives values within 2% of the *Colebrook correlation*.

Typical values of the relative roughness defined as the ratio e/D_{h} in microchannels vary between 0.0001 (glass microtubes) and 0.1 (stainless steel microtubes).

Pressure Drop Calculation

Pressure drop evaluation for flow through both single-microchannel and multiple-microchannel systems is very important in the design of microfluidic devices.

The model for the pressure drop analysis is depicted in Fig. 9 in which multiple microchannels with an abrupt entrance and exit are shown. The equations to be presented in this section apply to this model and are not restricted to a particular geometry of the microchannel cross-section. They are applicable to single-microchannel flow by reducing the appropriate terms. The general relation for flow-stream pressure drop calculations is the following:

$$\Delta p = \frac{\rho_1 W_1^2}{2}\left[\left(K_{\mathrm{c}} + 1 - \sigma^2\right) + 2\left(\frac{\rho_1}{\rho_2} - 1\right) + 4f\frac{L}{D_{\mathrm{h}}}\frac{\rho_1}{\rho} - \left(1 - \sigma^2 - K_{\mathrm{ex}}\right)\frac{\rho_1}{\rho_2}\right] \tag{45}$$

in which L is the microchannel length, W_1 is the average velocity defined by Eq. (9) and based on the minimum free flow area, σ is the free flow/frontal area ratio ($\sigma = 1$ for a single microchannel), K_{c} and K_{ex} represent entrance and exit loss coefficients and ρ is given by

$$\frac{1}{\rho} = \frac{1}{L}\int_0^L \frac{1}{\rho}\,\mathrm{d}z \tag{46}$$

The terms involved in Eq. (45) in order to calculate the total pressure drop represent:

- the entrance effects (see ▶developing flow and ▶entrance region);
- the flow acceleration effect for a compressible fluid;
- the usual friction pressure drop;
- the exit effects.

In order to investigate only the entrance pressure drop Eq. (45) can be reduced as follows:

$$\Delta p_{\mathrm{inlet}} = \frac{\rho_1 W_1^2}{2}\left(1 - \sigma^2\right) + K_{\mathrm{c}}\frac{\rho_1 W_1^2}{2} \tag{47}$$

in which the first term is the pressure drop which would occur due to a change in the cross-section alone, without friction, and the second term represents the loss due to irreversible free expansion that follows the abrupt contraction. The irreversible component of the pressure drop is contained in the abrupt contraction or entrance coefficient K_{c}.

The exit pressure rise is similarly broken into two parts:

$$\Delta p_{\mathrm{exit}} = \frac{\rho_1 W_1^2}{2}\left(1 - \sigma^2\right) - K_{\mathrm{ex}}\frac{\rho_1 W_1^2}{2} \tag{48}$$

The first is the pressure rise which occurs due to the area change alone, without friction, and is identical to the corresponding term in the entrance pressure drop. The second term is the pressure loss associated with the irreversible free expansion following an abrupt expansion and this term in the present case subtracts from the other.

The values of K_{c} and K_{ex} have been established analytically for a number of simple entrance and exit geometries and are quoted in many textbooks [9]. These coefficients have been evaluated on the assumption of essentially uniform velocity in the manifolds linked to the microchannels but by considering a fully established velocity profile in the microchannels (that means $L \gg D_{\mathrm{h}}$). These assumptions can be considered verified for long microchannels for which $L > 100D_{\mathrm{h}}$.

In applying the data related to the values of K_{c} and K_{ex} it should be remembered that these coefficients already include the pressure change associated with change in velocity profile.

Thus the friction factor used in Eq. (45) to evaluate the overall pressure drop should be defined on the basis of the mean wall shear stress after the entrance region and not on the basis of the overall pressure drop.

For liquids for which the incompressible model holds Eq. (45) can be simplified as follows:

$$\Delta p = \frac{\rho_1 W_1^2}{2}\left[K_c + 4f\frac{L}{D_h} + K_{ex}\right] \quad (49)$$

where f is the friction factor based on the mean wall shear stress after the entrance region.

For long microchannels for which $L \gg D_h$ (this condition is very common in microchannels) one can use the fully developed value of the friction factor in the calculation of the pressure drop:

$$\Delta p = \frac{\rho_1 W_1^2}{2}\left[K_c + 4f\mathrm{Re}_{fd}\frac{L}{\mathrm{Re}D_h} + K_{ex}\right] \quad (50)$$

To eliminate the uncertainties caused by estimation of minor losses (K_{ex}, K_c) many authors have suggested performing tests with microchannels of different lengths; in this manner it is possible to even out the inlet and outlet minor losses by subtracting the pressure drop of the shorter tube from that of the longer one for a fixed value of the average Reynolds number. By following this method, the value of the friction factor would be calculated as follows:

$$f_{fd} = \frac{\rho}{2\mu^2}\left(\frac{\Delta p(L_1) - \Delta p(L_2)}{L_1 - L_2}\right)\frac{D_h^3}{\mathrm{Re}^2} \quad (51)$$

where L_1 and L_2 are the lengths of the longer and shorter tube respectively.

It is important to observe that this method is in general valid for liquid flows in microchannels but becomes unsuitable for gaseous flows when the effects of compressibility are strong, as the values of the minor losses at the inlet and at the outlet, even for a fixed average value of the Reynolds number, can be very different.

When the initial velocity profile is uniform and there are no abrupt contraction ($K_c = 0$) and expansion ($K_{ex} = 0$) one can take into account the effects of momentum change in the entrance region by using $K(\infty)$ which includes the increased wall shear in the entrance region but separates out the downstream fully developed flow pressure drop due to wall shear to give

$$\Delta p = \frac{\rho_1 W_1^2}{2}\left[4f\mathrm{Re}_{fd}\frac{L}{\mathrm{Re}D_h} + K(\infty)\right] \quad (52)$$

Experimental Results

As mentioned above, the first experimental work in which water through glass microtubes with an inner diameter down to 15 μm was tested was due to Poiseuille in 1840 [2]. The experimental data obtained by Poiseuille were used to state the famous *Poiseuille law* for laminar flows through circular tubes, according to which for Stokes flows the product of the friction factor times the Reynolds number is a constant (equal to 16 for circular tubes) that depends on the cross-section geometry only.

On the contrary, as evidenced in [10], many experimental works published in the last decade seem to be partially in disagreement with the conventional theory and if these results are used in order to establish the validity of the conventional theory for microchannels in laminar and turbulent regime the answer obtained is not unequivocal. In fact, some authors found that the predictions of the conventional theory agree with the experimental results on the friction factor; however, for the same range of hydraulic diameters, some other authors found the opposite result.

It is possible to sum up the main results quoted in the open literature on the friction factor in microchannels highlighting the peculiarities, proposed by different authors, with respect to the conventional macrochannels:

- the friction factor for laminar fully developed flow is found to be smaller or larger than the conventional value;
- the Poiseuille number for laminar fully developed flow depends on the Reynolds number;
- the fully developed turbulent friction factor seems to be in disagreement with the *Blasius equation* for smooth microchannels and with the *Colebrook correlation* for rough microchannels;
- the friction factor depends on the material of the microchannel walls (metals, semi-conductors and so on) and/or on the test liquid (polar fluid or not), thus evidencing the importance of electro-osmotic phenomena at microscales;
- the friction factor depends on the relative roughness of the walls of the microchannels also in the laminar regime.

However, from a chronological analysis of the experimental results of the literature it is possible to extrapolate how the deviations of the behavior of fluid flow through microchannels from that through large-sized channels are decreasing. This fact can be explained by taking into account the dramatic improvement of the techniques of microfabrication with the consequent reduction of the issues of surface roughness of the microchannels and a more appropriate control of the channel cross-sections; for this reason the results of the older studies may not provide useful comparisons. Another possible explanation of the decrease of the observed deviations is related to the increase of the reliability/accuracy of the more recent experimental data quoted in literature. This seems to be confirmed by the increasing number of experimental results on the friction factor of the last few years, which confirm the success of conventional correlations in predicting pressure drop for Newtonian liquids in microchannels having inner hydraulic diameters down to 10 µm.

Future Directions for Research

The analysis of the behavior of single phase Newtonian liquid flow through microchannels in laminar and turbulent regime evidenced that the conventional theory validated for large channels holds for hydraulic diameters down to 10 µm. Further investigations are required for non-Newtonian flows, like polymer solutions and surfactants, for which slip velocity at the walls has been observed even for microchannels having a hydraulic diameter greater than 1 µm. In addition, an accurate analysis of the critical Reynolds numbers for which the laminar-to-turbulent transition occurs in microchannels of different cross-sectional geometry (for Newtonian and non-Newtonian liquids) could be important to improve the understanding of the rules of the development of turbulence at the microscale.

Cross References

▶ Entrance Region
▶ Developing Flow
▶ Pressure-Driven Single Phase Gas Flows
▶ Turbulence in Microchannels

References

1. Hagen G (1839) On the Motion of Water in Narrow Cylindrical Tubes. Pogg Ann 46:423
2. Poiseuille JM (1840) Recherches expérimentales sur le mouvement des liquides dans les tubes de très petits diamètres. C R Hebd Acad Sci 11:961–967, 11:1041–1048
3. Bird RB, Stewart WE, Lighfoot EN (1960) Transport Phenomena. Wiley, New York
4. Shah RK, London A (1978) Laminar Flow Forced Convection in Ducts. Adv Heat Transf 14(1):477
5. Jones OC (1976) An Improvement in the Calculation of Turbulent Friction Factor in Rectangular Ducts. Trans ASME J Fluid Eng 98:173–181
6. Obot NT (1988) Determination of Incompressible Flow Friction in Smooth Circular and Noncircular Passages. A Generalized Approach Including Validation of the Century Old Hydraulic Diameter Concept. Trans ASME J Fluid Eng 110:431–440
7. Idelchick IE (1986) Handbook of Hydraulic Resistance, Chap 2. Begell, Redding
8. Celata GP, Cumo M, Guglielmi M, Zummo G (2000) Experimental Investigation of Hydraulic and Single Phase Heat Transfer in 0.130 mm Capillary Tube. Proc Int Conf Heat Transf Transport Phenomena Microscale: 108–113
9. Rohsenow WM, Hartnett JP (1973) Handbook of Heat Transfer, Chap 7. McGraw Hill, New York
10. Morini GL (2004) Single-phase Convective Heat Transfer in Microchannels: a Review of Experimental Results, Int J Therm Sci 43:631–651

Pressure-Driven Two Phase Flows

LINGLING SHUI, JAN C. T. EIJKEL,
ALBERT VAN DEN BERG
BIOS, Lab-on-a-Chip Group, MESA+ Institute
for Nanotechnology, Enschede, Netherlands
L.shui@ewi.utwente.nl

Synonyms

Two-phase flow driven by pressure

Definition

Pressure-driven ▶ two phase flows are flows of two immiscible fluids in the same micro- or nanofluidic conduit driven by a pressure gradient. The fluids can be of different chemical compositions – liquid/liquid, or in different physical states – gas/liquid.

Overview and Theory

In the past decade, micro- and nanofluidics has been studied in great detail because of the increasing availability of methods for fabricating complicated flow configurations and measuring transport phenomena on the micro and nanoscales. The micro- and nanofluidic channel systems with integrated pumps, valves, and detectors, are known as ▶ Lab-on-a-Chip (LOC) or ▶ micro total analysis system (µTAS) [1]. Ideally, each process – e. g., sampling, sample pretreatment, reaction, separation, detection and analysis in an analytical system – is realized on one integrated device. Fluid mechanics studies in these processes therefore are indispensable for the design and fabrication of LOC and µTAS.

Fluids that are of interest in nature, biotechnology and chemistry, are rarely simple single-phase fluids. Most compartmental chemistry, interfacial phenomena and applications employ two-phase flows. It is therefore not surprising that recently a surge of interest has arisen in two-phase microfluidic manipulation.

Compared to single-phase flow systems, when discussing two-phase flow in micro- and nanosystems, there are many questions that arise even in a simple configuration. When two phases flow in the same conduit or channel, the flow patterns change between droplet-base flows and stratified flows depending on the physicochemical properties of fluids and channel surfaces. At the same time, in two-phase flow systems, several flow phenomena, such as film flow, corner flow and slip flow play increasingly important roles with reduction of the dimensions. Both advantages and disadvantages originate from the reduction in dimension and the coexistence of two phases. In all these phenomena, the fluid manipulation is no doubt the most important factor.

Manipulating fluids in a two-phase flow system is much more complicated than in single-phase systems. Fluid flows can be actuated spontaneously, non-mechanically or mechanically. The most frequently used flow actuation method, till now, is still pressure-driven pumps due to their availability and versatility. Especially, for a two-phase flow system, the naturally existing inhomogeneity makes other methods much more difficult to be applied. Electroosmosis for instance, resulting from the force exerted on a space-charge region in the liquid by an electric field, will not work if the conductivity continuum in the fluid is interrupted by an entrapped dielectric liquid droplet or gas bubble.

Fluid flow in channels of constant cross-sectional shape can be simply described by Poiseuille's law:

$$Q = \int v_i \, \mathrm{d}A \approx \frac{\Delta P}{R_{\mathrm{hy}}} \tag{1}$$

where Q ($\mathrm{m^3\,s^{-1}}$) is the volume flow rate, v_i ($\mathrm{m\,s^{-1}}$) is the flow velocity at the position i, A ($\mathrm{m^2}$) is the area of cross section. The hydrodynamic resistance, R_{hy}, can be approximately expressed as:

$$R_{\mathrm{hy}} \approx \eta l C^2 A^{-3} \tag{2}$$

where η (Pa s) is the fluid viscosity, l (m) is the channel length, and C (m) is the perimeter of the cross section. ΔP (Pa) is the pressure difference between two ends of the fluid, which is the total pressure acting on the fluids. It is the sum of externally applied pressure ($P_{\mathrm{ex.}}$) and the internal (capillary) pressure ($P_{\mathrm{cap.}}$):

$$\Delta P = P_{\mathrm{ex.}} \mp P_{\mathrm{cap.}} \tag{3}$$

If there is a positive capillary pressure in a channel, the externally applied pressure has to exceed it to pump fluid, and inversely fluid can be automatically imbibed in a microchannel if there exists a negative capillary pressure (capillary action). Therefore, pressure-driven flows can be manipulated not only by externally applied pressure but also by the internally generated capillary pressure.

The dynamical response of two-phase flows can be commonly characterized successfully in terms of the dimensionless numbers [2]. Table 1 lists some force-related dimensionless numbers. These dimensionless numbers demonstrate competing phenomena of forces: buoyancy, gravitational, inertial, viscous and interfacial forces. The Grashof number (buoyancy to viscous forces), the Bond number (gravitational to interfacial forces) and the Reynolds number (inertial to viscous forces) scale with the third, the second and the first power of flow dimensions, respectively. The relative importance of the different forces that act on fluids therefore dramatically changes on downscaling. With downscaling, the buoyancy, gravitational and inertial forces become less and less important and viscous and interfacial forces become more and more predominant. In micro-systems, the relative importance of forces, calculated for a water/oxygen two-phase flow, is given by the following order: buoyancy forces < inertial forces < gravitational forces < viscous forces < interfacial forces.

Of these dimensionless numbers, the Reynolds number is the most frequently used number to describe microfluidics. It expresses the ratio of inertial forces to viscous forces:

$$\mathrm{Re} = \frac{\rho v L}{\eta} \tag{4}$$

where ρ ($\mathrm{kg\,cm^{-3}}$) is the effective density, v ($\mathrm{m\,s^{-1}}$) is the average flow velocity, L (m) is the characteristic flow dimension, and η (Pa s) is the effective viscosity. In a straight channel, the value of $\mathrm{Re} \approx 10^3$ is accepted as a limit for the transition from a laminar flow to a turbulent flow. In a straight micro- or nanochannel with diameters between 100 nm and 100 μm, where $\eta(\mathrm{H_2O}) = 1.025 \times 10^{-3}$ Pa s, $\rho(\mathrm{H_2O}) = 10^3\ \mathrm{kg\,m^{-3}}$ and $v = 1\ \mathrm{mm\,s^{-1}}$, the calculated Reynolds number lies between 10^{-1} and 10^{-4}. For a gas, oxygen for instance, $\eta(\mathrm{O_2}) = 20.317 \times 10^{-6}$ Pa s and $\rho(\mathrm{O_2}) = 1.429\ \mathrm{kg\,m^{-3}}$, the Reynolds number at these channel dimensions ranges from 10^{-5} to 10^{-2}. Therefore, inertial forces are over-

Pressure-Driven Two Phase Flows, Table 1 Important force-related dimensionless numbers in two-phase microfluidics and scaling with device dimension L

Dimensionless number	Definition	Equation	Scaling	Value*
Grashof	$\frac{\text{Buoyancy}}{\text{Viscous}}$	$\frac{L^3\rho^2 g\beta\Delta T}{\eta^2}$	3	10^{-4}
Bond	$\frac{\text{Gravitational}}{\text{Interfacial}}$	$\frac{(\rho-\rho_{\mathrm{f}})gL^2}{G\sigma}$	2	10^{-5}
Reynolds	$\frac{\text{Inertial}}{\text{Viscous}}$	$\frac{\rho v L}{\eta}$	1	10^{-1}
Capillary	$\frac{\text{Viscous}}{\text{Interfacial}}$	$\frac{\eta v}{G\sigma}$	0	10^{-4}

* For a water-oxygen two-phase flow: $T = 20°$, $\eta(\mathrm{O_2}) = 20.317 \times 10^{-6}$ Pa s, $\eta(\mathrm{H_2O}) = 1.025 \times 10^{-3}$ Pa s, $\sigma(\mathrm{H_2O}) = 72.8\ \mathrm{mN\,m^{-1}}$, $\rho(\mathrm{H_2O}) = 10^3\ \mathrm{kg\,m^{-3}}$, $\rho(\mathrm{O_2}) = 1.429\ \mathrm{kg\,m^{-3}}$, θ(water and glass) $\approx 50°$, β(water at 20 °C) $= 0.00021\ °\mathrm{C}^{-1}$ assuming that $L = 10\ \mu\mathrm{m}$, $v = 1\ \mathrm{cm\,s^{-1}}$ and $g_{\mathrm{c}} = 1$

L – channel dimension, ρ – fluid density, g – gravity acceleration constant, β – coefficient of expansion, ΔT – temperature difference, η – fluid viscosity, ρ_{f} – surrounding fluid density, f – subscript of density, G – geometrical constant, σ – interfacial force, v – flow velocity whelmed by viscous forces in microfluidic devices. Laminar flows are thus expected in micro- and nanochannels for both gas and liquid, and not turbulent or random flows. The forces acting on two-phase fluids can be divided into tangential and normal components. On the micro- and nanoscales, as shown in Table 1, a pair of competitive forces – the viscous force and the interfacial force – become dominant. The viscous forces mainly act tangential to the interface elongating it, whereas the interfacial forces act normal to the interface inducing droplet or bubble formation (minimizing the interfacial area). The capillary number is the ratio of these two competitive forces, and can be expressed as:

$$\mathrm{Ca} = \frac{\eta v}{G\sigma} \tag{5}$$

where η (Pa s) is the viscosity of continuous phase, G is a geometrical constant, and σ (N m^{-1}) is the interfacial tension. The capillary number is independent of flow dimensions, and can be controlled by the properties of fluids and channels and the interactions between them. It is the most useful dimensionless number to describe two-phase microfluidic flow phenomena including flow formation, sizing, coalescing, mixing and splitting.

Keeping in mind that two-phase flows include both liquid-liquid systems, and gas-liquid systems, the different behavior of a gas and liquid must be emphasized before discussing two-phase flows. The average distance between molecules in a gas phase is one order of magnitude higher than the diameter of its molecules, while it approaches the molecular diameter in a liquid phase. Therefore, in some microdevices the gas is compressed when the pressure strongly changes. The Mach number Ma is a dynamic measure of fluid compressibility, and is defined as the ratio of flow velocity (v) to sound speed (a):

$$\mathrm{Ma} = \frac{v}{a} \tag{6}$$

The flow of a compressible fluid like air can be treated as incompressible if the local Mach number is less than 0.3. Ma is very small in microfluidic systems due to the low flow velocity. Compression however might still occur in the case of density gradients, for instance by high local pressure changes, wall heating or cooling. In that case, equations for compressible flow must be applied [3]

Basic Methodology

Channel Geometries

Two-phase flows can be easily generated by combining flow of different phases in certain channel geometries. The basic channel configurations used to generate multiphase flows are T, Y or cross junctions (Fig. 1).

Pumping by Externally Applied Pressure

In micro- and nanofluidic devices, a pressure is normally externally applied by syringe pumps or vacuum pumps. The pressure difference, generated at two ends of fluids, pushes or pulls fluid to move, and the resulting volume flow rate is expressed by Eq. (1).

The advantage of syringe or vacuum pumping is its versatility. It can be applied to drive all kinds of fluids (gas, liquid or gas-liquid two-phase fluids), and theoretically, it can also be used on all scales as long as the pressure is high enough to overcome the flow resistance. However, the hydrodynamic resistance in a channel is proportional to flow distance and inversely proportional to the fourth power of the channel size, and therefore, very high pressure is necessary to drive flows in smaller channels. For example, without capillary pressure, calculated from Eq. (1), to have water flow with 1 cm s^{-1}, in a 10 μm diameter channel of 1 mm length 10^3 Pa is needed, however, 10^7 Pa has to be applied for the same flow in a 100 nm diameter channel.

Syringe pumping and vacuum pumping remain predominant in microfluidic flows. Fluid flows driven by capillarity become more efficient on downscaling due to its favorable scaling behavior.

Pumping by Capillary Pressure

A hydrophilic liquid, water for instance, *pulls* itself into or through a hydrophilic micro- or nanochannel by capillary action which is induced by interfacial tensions (Fig. 2a). The capillarity-induced pressure pulling the liquid along the channel (Fig. 2a and 2b) is expressed by Young–Laplace's equation:

$$P_{\mathrm{cap.}} = G\sigma_{\mathrm{lg}} \cos\theta d^{-1} \tag{7}$$

where G is a geometrical constant, d (m) is the characteristic diameter, σ_{lg} (N m^{-1}) is the liquid-gas interfacial tension, and θ (degree) is the contact angle which is set up when a liquid droplet contacts both a solid and a gas (or a solid and a second immiscible liquid) (Fig. 2c and 2d). The liquid curvature of the droplet is caused by the differences among interfacial tensions. The force balance is described by Young's equation:

$$\sigma_{\mathrm{sg}} = \sigma_{\mathrm{sl}} + \sigma_{\mathrm{lg}} \cos\theta \tag{8}$$

where σ_{sg} and σ_{sl} (N m^{-1}) indicate the interfacial tensions of solid-gas and solid-liquid, respectively. Fluids,


T- junction
Y-junction
Cross-junction
a
b
c

Pressure-Driven Two Phase Flows, Figure 1 Configurations for two-phase flows: (**a**) T-junction, (**b**) Y-junction and (**c**) Cross-junction


a
b
σlg
σsg
θ
σsl
Hydrophilic Surface
c
σlg
σsg
θ
σsl
Hydrophobic Surface
d

Pressure-Driven Two Phase Flows, Figure 2 Water (**a**) in a hydrophilic channel, (**b**) in a hydrophobic channel, (**c**) on a hydrophilic surface and (**d**) on a hydrophobic surface.


Flow direction
R
r
Geometrical variance
a
hydrophobic
hydrophilic
Surface modification
b
Surfactant
Surface modification
c
σ2
σ12
σ1
Fluid juxtaposition
Δσ = σ1 + σ12 - σ2
d

Pressure-Driven Two Phase Flows, Figure 3 Capillary pressure induced by (**a**) Geometrical variance, (**b**) Surface modification (solid), (**c**) Surface modification (liquid), (**d**) Fluid juxtaposition (bi-slug)


+ + + + + + +
+ + + + + +++
Low E-field
High E-field
Electrically
a
Hot
Cold
Thermally
b
Light
Optically
c
X
Y
Chemically
d

Pressure-Driven Two Phase Flows, Figure 4 Interfacial forces modulated (**a**) Electrically, (**b**) Thermally, (**c**) Optically and (**d**) Chemically

therefore, can be spontaneously propelled by a capillarity-induced pressure gradient.

In a channel, the motion of a fluid segment can result from the capillarity-induced pressure difference between the front and a rear of the fluid column. Such a pressure difference (ΔP) is described by:

$$\Delta P = P_{\text{cap.2}} - P_{\text{cap.1}} = G\sigma_{\text{lg}}\left(\frac{\cos\theta_2}{d_2} - \frac{\cos\theta_1}{d_1}\right) \tag{9}$$

According to the equation, the pressure difference can be obtained by changing the channel diameter (d), the interfacial tension (σ) or the contact angle (θ). Therefore, self-propelling slugs can be realized by careful design, material selection, microfabrication, and surface control and processing. For example, a slug will move from the wide part to the narrow part when the channel diameter changes (Fig. 3a). The movement can also be realized by using different channel materials (Fig. 3b) or fluids (Fig. 3c) with different interfacial energy. Similar phenomena happen for two or more juxtaposed phases (Fig. 3d). The motion can even be inverted by juxtaposing a liquid of low surface tension.

Furthermore, interfacial tensions can be tuned electrically (Fig. 4a), thermally (Fig. 4b), optically (Fig. 4c), chemically (Fig. 4d), or by combinations of them such as optic-electrically.

Flow Phenomena

Flow patterns

Two-phase flow in microfluidic systems is broadly categorized into ► segmented (droplet-based) flow and ► parallel (stratified) flow architectures. Gas-liquid two-phase flows in microchannels have been studied in detail for heat-exchanger applications. Between segmented flows and stratified flows there can be several other flow patterns – bubbly flow, ring flow, lump flow and annular flow (Fig. 5a) [4]. The flow of immiscible liquids has been successfully manipulated to study chemical reactions and for biotechnology purposes. The two-phase microchannel flows change from the droplet-based flows to stratified flows depending on the flow rate and fluid composition, in a manner ultimately dependent on the capillary number (Eq. (5), Fig. 5b) [5].

Immiscible gas-liquid and liquid-liquid mixtures form droplet-based flows over a wide range of flow conditions and channel dimensions without additional control due to interfacial forces. Vice versa, two immiscible streams would flow alongside one-another if there were no interfacial forces between them. Theoretically, a stable elongated interface between two phases only occurs when tangential forces (viscous shear forces) are equal to or greater than normal forces (interfacial forces), i.e, at higher capillary number. Figure 5c shows a typical example of a two-phase flow transition according to the capillary number [6]. Two streams of water are added to a carrier liquid in a cross configuration. The two streams of water coalesce to form a big droplet-based flow at extremely small Ca (~ 0.0004). By increasing Ca, alternating droplet-based flow is generated with decreased droplet size. Droplet size (R) in a two-phase flow depends on the channel size (h) and the capillary number: $R \sim h/\text{Ca}$ [7]. Finally, stratified flow is obtained for $\text{Ca} > 0.15$ at a water fraction of 0.2.

Based on the definition of the capillary number, the two-phase flow patterns in microchannels can be influenced by interfacial forces (σ), fluid viscosity (η), flow velocity (v) and geometric features (G). The interfacial forces can be modulated by adding surfactants, surface coating and patterning techniques, but also by electrical, thermal or optical modulations of the interfacial tensions (see previous section). The fluid viscosity will be changed by changing temperature or adding polymers. The flow velocity is mainly tuned by actuation forces and geometrical tailoring. The geometric features include designing smart geometries and adding microtextures inside micro- and nanofluidic devices.

When two immiscible phases come into contact at a junction, an approximately parabolic flow profile can be obtained for a two-phase stratified flow in a common pressure-driven microfluidic system. On the other hand, in a droplet-based flow, stimulated by the shear between the stationary fluid at the channel wall and the slug axis, there exists internal recirculation in both continuous and dispersed phases [8]. Complex flow patterns may appear under different conditions, depending on the forces acting on the fluids.

Whether a stable two-phase flow can be obtained in a fluidic system depends on both fluid dynamic conditions and surface chemistries. The aim is to open the way to control the flow and to achieve versatility and reproducibility in on-chip flow management. The design will require smart network topologies and interplay of multiple physical and chemical effects.

Slip Flow

Traditional *non-slip* assumptions have been doubted for a long time in microfluidic systems. Recently, the results from molecular dynamics simulations and experiments on micro- and nanoscales strongly indicate the existence of slip flow. Theoretically, fluids will slip when the attraction between fluids molecules is stronger than the wall/fluid molecule attraction. The amount of slip is described as the slip length which is the notional distance inside the surface at which the velocity equals to zero (Fig. 6a).

Molecular dynamics (MD) simulations have shown that slip can occur only when a critical surface shear stress is reached, and that there exists a general relationship (linear or nonlinear given by different results) between the slip length and the local shear rate at a solid surface. Significant slip has been experimentally demonstrated by driving different fluids through micro- and nanochannels. Slip length depends on the interactional parameters between solid and fluid: shear stress, wetting properties, fluid properties (e. g., viscosity and density) and interfacial roughness.

Different fluids have different interactions with each other or with solid surfaces. The fluid/fluid intermolecular interactions can be stronger or weaker than those of fluid/solid surfaces. Therefore, in two-phase flows, boundary conditions are much more complicated. As diagnostic techniques improve our ability to probe the fluid surface at the molecular scale, it is expected that slip flows can be investigated by direct measurement of fluid velocity or the movement of contact lines.

Film Flow

When droplet-based multiphase flow is considered, there are two possible configurations. In the first, a drop forms a distinct contact line with the walls of the channel. In the other, a drop is separated from the boundaries by a thin wetting film. Because of the affinity of fluids and surfaces,



Pressure-Driven Two Phase Flows, Figure 5 (**a**) Phase diagram of a gas-liquid two-phase flow. Reprinted from [4] with permission of Elsevier. (**b**) Phase diagram of a liquid-liquid two-phase flow. Reprinted from [5] with permission of the American Physical Society. (**c**) Two-phase flow patterns transition according to the capillary number. (a) is the schematic illustration of the experimental setup, (b)–(k) are the microphotographs of the observed flow patterns as Ca and wf (water fraction) are varied. Reprinted from [6] with permission of the American Chemical Society

hydrophilic fluids prefer to flow along hydrophilic channel surfaces, and hydrophobic fluids like to flow along hydrophobic surfaces. As hydrophilic liquids are imbibed into hydrophilic channels by capillary force, hydrophobic fluids flow into hydrophobic channels much more easily. When fluid slugs flow forward in a channel, the trail left by the previous slug act as a lubricant for the following one (Fig. 6b). The film thickness can be theoretically calculated from the ratio of the loss of the fluid volume to the surface area traveled by the fluid. The thickness of a lubricating film experimentally depends on viscosity of neighboring slugs, fluid velocities and surface properties. Viscosity causes the deposition while capillary forces oppose the formation of a film. The film thickness (h_∞) deposited behind a wetting meniscus is therefore a function of Ca. At $10^{-5} < \mathrm{Ca} < 10^{-2}$ it can be expressed by: [9]

$$h_\infty = nR\mathrm{Ca}^{2/3} \tag{10}$$

where n is a prefactor determined by fluid properties, and R is the channel radius. Although the thickness decreases with flow dimension, the percentage of film flow will still increase with downscaling due to both the decrease of fluid amount and the increase of specific interfacial areas. The greater the capillary number, the larger the film thickness according to Eq. (10), which allows more liquid flow through the film. A stable thin liquid film between the tube wall and gas slugs can appear at high velocities on carefully treated clean surfaces, and vice versa, so that thin films can be decreased in thickness or eliminated by sur-



Pressure-Driven Two Phase Flows, Figure 6 Schematics of (**a**) No-slip flow and slip flow. (**b**) Film flow: (1) and (2) are immiscible fluids. (**c**) Corner flow in a rectangular channel



Pressure-Driven Two Phase Flows, Figure 7 Schematic applications of (**a**) Droplet-based flow and (**b**) Stratified flow.

face modification of the channel walls by changing the wetting properties.

Corner Flow

As we know, liquid surface tension is prone to minimize the liquid surface area to minimize the surface energy. Most of the channels fabricated on the micro- or nanoscale possess rectangular or slit-like cross sections. To satisfy the contact angle wetting condition the fluid will curve along the perimeter of the interface, thus minimizing interfacial area, and achieving a lower energy state (Fig. 6c). The polymorphism of the wetting liquid depends on two parameters: the channel geometry, and the interaction between substrate materials and liquids. The corner flow velocity is influenced by a flow resistance coefficient and geometric factors: the corner half-angle and the contact angle [10].

In a two-phase flow system, the different affinity of the two fluids for the wall makes one fluid preferentially flow along corners due to the capillarity. As the number of the polygon sides decreases and the corners sharpen, the cross-sectional area of fluids held in corners increases, and corner flow becomes more important. Therefore, corner flow must be considered carefully in such processes as evaporation and drying of micro- and nanochannels with small angular polygonal cross sections.

Key Research Findings

Applications

Two-phase systems are more complex than their single-phase counterparts, but are ubiquitous in process applications. Both the immiscible individual fluids separated by interfaces and the interfaces themselves provide us with mediums that are very suitable to study microreactions and interfacial phenomena.

Droplet-based Flows

Immiscible gas-liquid and liquid-liquid mixtures form droplet-based flows over a wide range of flow conditions and microchannel dimensions without additional control. There are several advantages for droplet-based flows to be applied in different fields. Specific interfacial areas as large as $9000-50{,}000\,\mathrm{m}^{-1}$ have been obtained by decreasing channel dimensions and droplet (bubble) sizes down to $50\,\mu\mathrm{m}$, which is 100 times larger than generally obtained in macroscopic channels. Thermal and mass transfer is therefore rapid due to the large specific interfacial area and consequently small molecular diffusion distance. Moreover, the process controllability is wide in droplet-based flows. The size, the number, and the composition of droplets can be controlled at each step of the process. By varying the initial composition of droplets, one can assess its effect on reaction yield and kinetics, providing a useful operational research tool for laboratories. Furthermore, in a droplet-based multiphase flow, droplets are separated from channel walls by a thin layer of immiscible (carrier) fluid, therefore the internal compositions of the droplets can not change due to contact with the channel walls, and the internal recirculation inside the droplets makes components mix efficiently in a very short time. This supplies us with more flexibility to employ each droplet as a separate microreactor.

Droplet-based two-phase flows offer controlled picoliter or femtoliter volumes of droplets (Fig. 7a) which are almost ideal chemical reactors and therefore have been utilized in emulsification and encapsulation, microreaction, synthesis, mixing, and bioassay [7].

Stratified Flows

In a multiphase stratified flow, the interfaces between immiscible fluids have several characteristics. Firstly, the specific interfacial area can be very large just as droplet-based flow. It can for example be about 10,000 m^{-1} in a microchannel compared with only 100 m^{-1} for conventional reactors used in chemical processes. Secondly, the mass transfer coefficient can be very high because of the small transfer distance and high specific interfacial area. It is more than 100 times larger than that achieved in typical industrial gas-liquid reactors. Thirdly, the interfaces of a stratified microchannel flow can be treated as nano-spaces. Simulation results show that the width of the interfaces of a stratified flow is in nanometers, and that diffusion-based mixing occurs at the interface. The interface width can be experimentally adjusted by adding surfactants. Finally, reactants only contact and react with each other at the interface. Therefore, the interfaces supply us with mediums to study interfacial phenomena, diffusion-controlled interfacial reactions and extraction.

The ideal 2D "nano-reactors" of the interfaces between immiscible fluids in stratified flows (Fig. 7b) have been used for chemical synthesis, triphase hydrogenation and biological enzymatic degradation, for extraction and separation, and for kinetic studies.

Future Directions for Research

Two-phase flows for a long time have been propelled by externally applied pressure, due to the inhomogeneity of two confined phases in the same system. High external pressure is needed to maintain flow in small devices due to the hydrodynamic resistance which increases with downscaling. This makes syringe pumping and vacuum pumping less suitable at smaller length scales. However, the capillarity-induced flow shows its importance at small flow dimensions. The capillary pressure is induced by interfacial forces which increase with downscaling. Moreover, more and more means have been found to modulate different interfacial forces of gas-liquid, gas-solid, liquid-liquid and liquid-solid. As device size decreases, the capillary pressure-driven flow therefore gains importance and may increasingly be used for systems where externally applied pressure would have to be extremely high.

Cross References

- ► Pressure-driven Flow
- ► Pressure-based Sample Injection
- ► Two-phase Flow

References

1. van den Berg A, Lammerink TSJ (1998) Micro total analysis systems: Microfluidic aspects, integration concept and applications. Springer, Berlin
2. Stone HA, Stroock AD, Ajdari A (2004) Engineering flows in small devices: Microfluidics toward a lab-on-a-chip. Ann Rev Fluid Mech 36:381–411
3. Karniadakis GAB, Aluru N (2005) Microflows and Nanoflows. Springer, New York
4. Serizawa A, Feng Z, Kawara Z (2002) Two-phase flow in microchannels. Exp Therm Fluid Sci 26(6-7):703-717
5. Dreyfus R, Tabeling P, Willaime H (2003) Ordered and disordered patterns in two-phase flows in microchannels. Phys Rev Lett 90(14):1445051–1445054
6. Zheng B, Tice JD, Ismagilov RF (2004) Formation of droplets in microfluidic channels alternating composition and applications to indexing of concentrations in droplet-based assays. Anal Chem 76(17):4977–4982
7. Squires TM, Quake SR (2005) Microfluidics: Fluid physics at the nanoliter scale. Rev Mod Phys 77(2):977–1026
8. Song H, Tice JD, Ismagilov RF (2003) A microfluidic system for controlling reaction networks in time. Angew Chem Int Ed 42(7):768–772
9. Bico J, Quere D (2002) Self-propelling slugs. J Fluid Mech 467:101–127
10. Weislogel MM, Lichter S (1998) Capillary flow in an interior corner. J Fluid Mech 373:349–378

Pressure Drop in Microchannels

► Turbulence in Microchannels

Pressure Injection

Definition

Pressure injection is another important technique for transferring sample to microfluidic chips.

Cross References

► Techniques for Transferring Samples to Chips

Pressure Measurements, Methods

BARBAROS CETIN, DONGQING LI
Department of Mechanical Engineering, Vanderbilt University, Nashville, TN, USA
barbaros.cetin@vanderbilt.edu

Synonyms

Pressure sensors

Definition

Experimentation and novel measurement techniques are crucial for the further development of microfluidic devices. Pressure is one of the basic parameters involved in microfluidic experiments. However, it is not realistic to apply conventional pressure measurement techniques to microsystems, since the characteristic dimensions of these measurement instruments are already comparable to those of the microdevices used. Therefore, novel pressure methods are needed for pressure measurement on the microscale.

Overview

It is not practical to measure pressures inside microchannels and nanochannels by use of conventional sensors, since it is very difficult or impossible to implement these sensors in microsystems without disturbing the flow field. Therefore, some novel methods are required for pressure measurement on the microscale.

The common practice for measuring the pressure drop along a microchannel is to use pressure transducers in the inlet and exit reservoirs, which gives overall information about the pressure rather than the pressure distribution along the channel. This approach is used in many studies related to fluid flow in microchannels [1–4].

Sekimori et al. [5] have developed a pressure sensor for use in Lab-on-a-Chip (LOC) devices. It has an embedded miniaturized structure and high chemical resistance, and causes no interference in the microflow during the measurement. This pressure sensor element has a volume of 1 mm^3 and was fabricated by using MEMS technology. The pressure sensor element was installed in an LOC without any dead volume or disturbance to the microflow, and the pressure inside the microchannel was measured (see Fig. 1).

Wu et al. [6] proposed the use of single-walled carbon nanotubes (SWNTs) as nanoscale electromechanical pressure sensors. These authors demonstrated computationally a reversible pressure-induced shape transition in armchair SWNTs, which in turn induced a reversible electrical transition from metal to semiconductor. They also discussed the potential long lifetime of this pressure sensor due to the excellent mechanical durability of carbon nanotubes.

Li and Chou [7, 8] proposed the use of SWNTs as mechanical sensors to measure also mass, strain, and temperature, as well as pressure. The principle of sensing was based on the shift of the resonant frequency of a carbon nanotube resonator when it is subjected to changes in attached mass, external loading, or temperature. Li and Chou discussed the feasibility of such a sensor, with the aid of computer simulation using atomistic modeling together with molecular structural mechanics. They concluded that the sensing capability of this nanoscale sensor was superior to that of current microsensors, and that the sensitivity could be further enhanced by using smaller-sized carbon nanotubes.



Pressure Measurements, Methods, Figure 1 Installation of the pressure sensor to a microchip. Reprinted from [5] with permission from Dr. Kitamori

Kim and Daniel [9] have recently suggested the use of atomic force microscopy (AFM) for measuring pressure profiles in micro/nanochannels. The method is based on measurement of the deflection of a thin plate over the channel surface by topographic imaging of the plate using AFM. Kim and Daniel verified this measurement technique numerically with artificially generated topographic data. Since the topographic imaging takes quite a long time, this technique is only applicable to steady-state processes. Moreover, special attention needs to be paid to providing vibration-free surroundings, since vibrations transmitted via the fluid can cause noise in the data, leading to loss of accuracy.

Matsuda et al. [10] have proposed the use of a pressure-sensitive paint (PSP) technique, which is based on the interaction of atoms or molecules with photons, to measure the pressure inside micro/nanochannels. This technique is limited to gaseous flow, and has drawbacks for high-pressure and low-speed applications. Moreover, the surface where the pressure is to be measured must be visible to the detector. The temperature sensitivity of the PSP technique must also be considered during the calibration.

In conclusion, although several techniques have been suggested by many researchers, the development of measurement techniques for use on the microscale is a challenging topic, and this topic seems likely to remain open-ended in the near future.

Cross References

- ► Nanofluidics in Carbon Nanotubes
- ► Control of Microfluidics

► Fluidic Nanosensors
► Velocity Sensors

References

1. Qu W, Mala GM, Li D (2000) Pressure-driven water flows in trapezoidal silicon microchannels. Int J Heat Mass Transf 43:353–364
2. Qu W, Mala GM, Li D (2000) Heat transfer for water flow in trapezoidal silicon microchannels. Int J Heat Mass Transf 43:3925–3936
3. Ren L, Li D, Qu W (2001) Interfacial electrokinetic effects on liquid flow in microchannels. Int J Heat Mass Transf 44:3125–3134
4. Ren L, Li D, Qu W (2001) Electro-viscous effects on liquid flow in microchannels. J Colloid Interface Sci 233:12–22
5. Sekimori Y, Yoshida Y, Kitamori T (2004) Pressure sensor for micro chemical system on a chip. Sens Proc IEEE 1:516–519
6. Wu J, Zang J, Larade B, Guo H, Gong G, Liu F (2004) Computional design of carbon nanotube electromechanical pressure sensors. Phys Rev B 69(15):153406-1–153406-4
7. Li C, Chou T-W (2006) Atomistic modeling of carbon nanotube-based mechanical sensors. J Intel Mater Syst Struct 17:247–254
8. Li C, Chou T-W (2004) Strain and pressure sensing using single-walled carbon nanotubes. Nanotechnology 15:1493–1496
9. Kim SK, Daniel IM (2006) Pressure measurement technique in nano- and micro-channels using atomic force microscopy. Invers Prob Sci Eng 14(7):701–709
10. Matsuda Y, Mori H, Niimi T, Uenishi H, Hirako M (2007) Development of pressure sensitive molecular film applicable to pressure measurement for high Knudsen number flow. Exp Fluid 42:543–550

Pressure Sensors

► Pressure Measurements, Methods

Pressure Wave

► Shockwaves in Microchannels

Primitive Model

Synonyms

Element model

Definition

Primitive model is a single Differential–Algebraic Equation (DAE) derived from basic conservation laws in different domains describing the dynamic response of a constituent element (e.g., capacitors, inductors, resistors, channels, etc.) in a complex system.

Cross References

► Model Order Reduction (MOR)

Probe Microscopy

► Scanning Probe Microscopy

Programmed Cell Death

► Microfluidics for Studies of Apoptosis

Proper Orthogonal Decomposition (POD) Based MOR

Synonyms

Karhunen–Loève (K–L) expansion; Karhunen–Loève (K–L) decomposition; Karhunen–Loève (K–L) approach

Definition

Proper Orthogonal Decomposition is a technique that extracts the orthogonal basis function spanning the reduced subspace using an ensemble of data from experiments or numerical simulation of the original full systems.

Cross References

► Model Order Reduction (MOR)

Protein Adsorption

► Biomolecular Adsorption in Microfluidics

Protein Array

► Biochip
► Bioprinting on Chip

Protein Array and Cell Array

► Microarray

Protein Chip

► Lab-on-Chip Devices for Protein Analysis
► Protein Microarrays

Protein Microarrays

Steven Wong, Samuel K. Kassegne
MEMS Research Laboratory
Department of Mechanical Engineering
College of Engineering,
San Diego State University, San Diego, CA, USA
kassegne@mail.sdsu.edu

Synonyms

Microarrays; Protein chip

Definition

Protein microarrays are small chips made of glass, plastic or silicon that enable the study of protein–protein, protein–antibody and protein–drug interactions in a miniaturized, automated fashion.

Overview

Protein microarrays are chips made of glass, plastic or silicon spotted with an array of known antibodies or peptides onto which a biological sample of immobilized proteins is applied and binding determined (Fig. 1). These microarrays are used for identifying interactions between molecules fixed onto the surface (i. e. antibodies) and proteins in a solution. In a single experiment, these microarrays enable the simultaneous analysis of thousands of molecular parameters [1]. Typical applications of protein microarrays include determining protein–protein, enzyme–substrate, antibody–protein and drug–protein interactions, and determination of protein expression levels. In general, protein microarrays are classified under two broad categories: *analytical protein microarrays* for identifying the contents of an analyte and *functional protein microarrays* for studying the interaction between the protein of interest and other molecules [2]. Analytical protein microarrays often have microfluidic channels where a solution containing the proteins being investigated is pumped into a flow cell containing the microarrays. These types of protein microarrays are mainly used for basic molecular biology research, disease marker identification, toxicological response profiling and pharmaceutical target screening [3]. In contrast, functional protein microarrays have the proteins being investigated attached to the chip itself.

Protein microarrays are very similar to DNA microarrays; however, they are much more difficult to design [4]. DNA is an unstructured linear polymer that hybridizes due to information contained in the nucleic acid sequence. Proteins, however, are much more complex and possess a wide degree of secondary, tertiary and quaternary structures. In addition, protein function is highly dependant on protein structure. As a consequence, protein microarrays must be synthesized in a way that prevents denaturing of the molecule. Maintaining proteins in buffers at appropriate temperatures and pH is crucial in preserving protein shape. In manufacturing protein microarrays several sources of proteins and peptide have been arrayed onto a solid support including synthetic peptides, recombinant proteins, monoclonal antibodies and polyclonal antibodies. Out of these sources, antibody microarrays have been the most developed due to their good biochemical stability.

Basic Methodology

The design and fabrication of a protein microarray parallels that of a DNA microarray. Using a solid support that exhibits low non-specific binding is quite important in the design of a protein microarray. As shown in Fig. 1, typically glass and in some cases silicon and polymer are used as the support for protein microarrays. To increase signal-to-noise ratios, coating with nitrocellulose polymers can be used [4]. Some of the common protein microarray fabrication methods include robotic contact printing, ink-jetting, piezoelectric spotting and photolithography. A microfluidics system for automated sample incubation with arrays on glass slides and washing has also been developed.

In terms of attachment chemistry, covalent bond formation between the protein and the glass slide or affinity interactions are exploited as the means of attaching a protein to the solid support. In the covalent bond formation method, random regions of the protein are used as linkages to bind to the solid support resulting in different sides of the protein being exposed for probing interactions. In the affinity interaction method, the proteins to be plated are expressed as recombinant His-tagged proteins. The tagging of the protein enables the uniform placement of the protein onto the solid support, which can result in a more uniform signal. However, it has been suggested that the tag can artificially enhance some protein–protein interactions. Tagging both N- and C-terminals and comparing the results can resolve this problem.

Several companies have explored different means of attaching an array of proteins onto a solid surface. Schlei-



Protein Microarrays, Figure 1 A protein microarray with capture agents spotted on a chip surface. Typically glass and in some cases silicon and polymer are used as the support. Robotic contact printing is often used for spotting the agents on the surface. A microfluidics system for automated sample incubation with arrays on glass slides and washing is included. The analytes of interest are retained by selective binding to the capture agents. Specific binding is monitored by fluorescence or mass spectroscopy.

cher & Schuell and the Pall Corporation have used nitrocellulose-coated FAST and Vivid slides using simple random adsorption. The sensitivity for their antibody microarray has been reported in the range of 1 pg/mL. Xenopore, NoAb, BioDiscoveries, Microsurfaces and TeleChem International have products with surface-reactive groups that can minimize protein denaturation. Perkin Elmer and Biocept have commercially available glass slides coated with a hydrogel that increases the protein loading capacity.

Protein Microarray Applications

Protein microarrays find several uses such as in gene expression, detection of signal transduction, genome mismatch scanning, inflammation, cancer, cell cycle, DNA replication, oxidative stress, hormone action, apoptosis, neurodegenerative disease, infectious disease and cytoskeleton [4]. In broad terms, protein microarrays have found unique and superior advantage in the following areas: expression profiling, protein-protein interactions, drug discovery, and diagnostics.

- *Expression Profiling.* This is one of the main application areas for protein microarrays. The microarrays essentially help in identifying proteins in a sample or mixture. This requires good binding specificity and good binding affinity. In other words, the interactions between antibody and protein must be very specific and strong. Today, this is not done quantitatively, rather qualitatively. As a result, we get a relative difference in expression rather than a quantitative amount. This difficulty in quantifying binding efficiency accurately is due to high non-specific binding such as antibodies binding to proteins at varying degrees. Typically, quantification is done with standard calibration curves on the array for calibration.
- *Protein–protein interactions.* This is another area of protein microarray applications where proteins come to contact with other elements in the cell by binding interactions. These interactions influence the behavior of those elements with which they come in contact (i. e. signal transduction). Studying protein–protein interactions allows deeper understanding of the functionality of cells. Protein microarrays offer a means of directly studying these interactions, unlike DNA microarrays which are indirect in that – for protein expression – extrapolation of genetic sequencing or gene expression is used.
- *Drug discovery.* Drugs are often small molecules and interact with proteins. These proteins become activated or repressed due to the drug–protein interaction. Microarrays are being used to gain more understanding of cross reactivity and toxicity due to a given drug–protein interaction. Microarrays can be used as a means to optimize drug targets and avoid toxicity or side effects from activation of unwanted receptors.
- *Diagnostics.* Two diagnostic formats are generally available. One involves antigens printed onto the microarray with the purpose of identifying antibodies in patients. The other format involves antibodies printed onto the microarray with the intent of identifying proteins expressed as a result of genetic defects or disease.

Major Protein Microarrays in the Market

Many microarrays are available on the market, one of which is Clonetech's AB Microarray 500 [5]. This microarray is comprised of over 500 antibodies immobilized onto a glass surface at a high density. This device allows for direct comparison of protein expression in two biological samples. The device uses a fluorescence-based analysis which determines the relative measure of protein abundance in one sample compared to another. The device is typically used as a screening tool to identify proteins involved in physiological or pathological processes. For example, it can be used to detect proteins involved in signal transduction, cell-cycle regulation and apoptosis. Applications range from toxicity testing, to disease investigation and drug discovery [5].

Several companies are involved in developing protein microarrays for expression profiling and diagnostics. Examples include Zyomyx (Hayward, CA), Axcell Biosciences (Newtown, PA), BioSite (San Diego, CA), LumiCyte (Fremont, CA), Phylos (Lexington, MA) and ProteinOne (Bethesda, MD). Other players in the protein microarray market include BD Biosciences and Invitrogen who actually have leading positions in the market. Other chips on the market address the need for probing for a specific group of proteins rather than a diverse range. Zyomyx (Hayward, CA), for example, has developed a chip specific for human cytokines.

Key Findings and Future Directions for Research

Significant research and product development efforts in protein microarrays are being carried out in the following key areas: development of capture agents, surface attachment chemistry, and better detection methods.

- *Development of capture agents.* Monoclonal antibodies take a long time to develop and are labor intensive. Among some of the ongoing research in improving capture agents is the use of phage display methods that can be used to isolate high-affinity binding agents against protein targets [6]. Phage display is a system in which a protein is displayed on the surface of a phage as a fusion with one of the coat proteins of the virus.
- *Surface substrates and attachment.* The quality of data obtained from protein microarray experiments is severely affected by the nature of the surface substrate and attachment chemistry [7]. The immobilization of biotinylated proteins onto streptavidin surfaces has been demonstrated to lead to an increase in sensitivity over random attachment in a microarray assay. Poly(ethylene glycol) derivates used as coatings have also proved successful in increasing sensitivity.
- *Detection methods.* There are several detection methods currently under development. These include laser scanning, ELISA, phosphorimaging, atomic force microscopy, nanoparticles and rolling circle amplification. Currently, research efforts continue in improving detecting binding events. One promising area is the use of sandwich immunoassay with labeled detection antibodies. For ELISA-based assays that have certain restrictions, a highly sensitive detection strategy that uses rolling circle amplification (RCA) has been introduced [8].

Cross References

- ► Protein Microarrays
- ► DNA Microarray
- ► Lab-on-a-Chip (General Philosophy)
- ► Lab-on-Chip Devices for Protein Analysis

References

1. Zhu H, Bilgin M, Bangham R, Hall D, Casamayor A, Bertone P, Lan N, Jansen R, Bidlingmaier S, Houfek T et al (2001) Global analysis of protein activities using proteome chips. Science 293:2101–2105
2. Twyman RM (2004) Principles of Proteomics. BIOS Scientific Publishers, Oxon
3. LaBaer J, Ramachandran N (2005) Protein microarrays as tools for functional proteomics. In: Cravatt BT, Kodadek T (eds) Current Opinion in Chemical Biology, vol 9. Proteomics and Genomics pp 14–19
4. Schena M (ed) (2005) Protein Microarrays. Jones and Bartlett, Sudbury ISBN 0-7637-3127-7
5. Clontech http://www.clontech.com Accessed Oct 2006
6. Sheets MD, Amersdorfer P, Finnern R, Sargent P, Lindquist E, Schier R, Hemingsen G, Wong C, Gerhart JC, Marks JD, Lindqvist E (1998) Efficient construction of a large nonimmune phage antibody library: the production of high-affinity human single-chain antibodies to protein antigens. Proc Natl Acad Sci USA 95:6157–6162
7. Sydor JR, Nock S (2003) Protein expression profiling arrays: tools for the multiplexed high-throughput analysis of proteins. Proteome Sci 1:3
8. Lizardi PM, Huang X, Zhu Z, Bray-Ward P, Thomas DC, Ward DC (1998) Mutation detection and single-molecule counting using isothermal rolling-circle amplification. Nat Genet 19:225–232

Protein Profiling

► Lab-on-Chip Devices for Protein Analysis

Proteolysis

Synonyms

Enzymatic or chemical digestion

Definition

Proteolysis is the process of cleaving protein molecules into smaller pieces (peptides) via chemical or enzymatic reactions. Living systems carry out proteolysis to obtain amino acids from protein substrates or as part of the construction of new proteins. In proteomic analyses, it is often necessary to perform proteolysis in order to facilitate identification of a protein of interest, as digest peptides form a characteristic “fingerprint” of the parent protein.

Cross References

- ► Lab-on-Chip Devices for Protein Analysis
- ► Liquid Chromatography
- ► Mass Spectrometry
- ► Microfluidic Bioreactors
- ► Proteomics in Microfluidic Devices

Proteomics

► Lab-on-Chip Devices for Protein Analysis

Proteomics in Microfluidic Devices

Elizabeth M. Miller[2], Sergio Freire[1],
Aaron R. Wheeler[1]
[1] Department of Chemistry, University of Toronto,
Toronto, ON, Canada
[2] Terrence Donnelly Centre for Cellular and
Biomolecular Research, University of Toronto,
Toronto, ON, Canada
awheeler@chem.utoronto.ca

Definition

Proteomics is the study of the collection of proteins (the proteome) expressed in a given system. The field of proteomics can be divided into three subtypes:

- *profiling* – identification and quantification of the proteins in a sample and drawing comparisons between samples,
- *functional* – the study of the behavior of specific proteins, and
- *structural* – the study of protein folding and the complexes it forms.

Microfluidics is characterized by devices that contain channels or features with dimensions measured in microns, and are capable of transporting and analyzing sample volumes in the nanoliter range.

Overview

Proteomics is a field that first gained prominence in the mid 1990s. The sheer number of proteins as well as the number of variations that comprise the proteome presents a huge challenge for analysis. Serum protein concentrations can vary by several orders of magnitude, and often a single disease will affect both high- and low-abundance proteins to varying degrees. In addition to basic protein structures and sequences, a vast array of post-translational modifications exists that significantly impacts the functionality, structure, and activity of the native proteins. The primary applications of microfluidics in proteomics have been in the profiling and functional subtypes – structural proteomics has not yet been extensively studied on the microscale.

Profiling proteomics is used to identify all of the proteins in a sample or to compare changes in protein expression between several samples. Due to the complexity of the proteome, accurate analysis requires a great deal of sample processing, including proteolytic digestion, followed by multidimensional separations and mass spectrometry. Separations and mass spectrometry are be covered in other chapters of the *Encyclopedia* ► lab-on-chip devices for protein analysis, ► chromatographic chip devices, ► interfaces between microfluidics and mass spectrometry, but chemical processing for profiling proteomics will be discussed here. Readers are encouraged to see Friere and Wheeler [1] for a comprehensive discussion of proteome profiling in microfluidics.

The study of functional proteomics on the microscale comprises an assortment of assays to identify functional groups on proteins and evaluate binding events to determine functional properties of proteins. Functional proteomics is exploited in *enzyme assays* and *immunoassays* to characterize the behavior of a protein within a biological system.

There are a number of ways in which enzymatic studies contribute to the understanding of the proteome. Enzymes are commonly used in proteomics to investigate analytes that are difficult to measure by conventional means. Quantitation of small molecules with enzymatic methods provides insight into the concentration and activity of the proteins associated with those molecules. A great variety of these enzymatic assays have been carried out in microfluidic devices. Another function of enzymatic assays is in kinetics; measurements of properties of enzymes such as the Michaelis–Menten constant (the concentration of substrate when the reaction rate is half the maximum rate) and the turnover number (the number of moles of substrate that are converted to product per catalytic site per unit time) are vital to understanding the mechanics of the proteome, and are used to characterize of the effects of known drugs and discover new ones.

The immunoassay is another widely used technique that has been applied to a diverse set of proteomic applications, including the identification and quantization of protein markers for diagnosis of diseases where laboratory facilities are not readily available. Immunoassays can be designed to detect very small amounts of antigens and to measure the concentrations quite accurately; in addition, further information about the disease markers, such as the existence of structural changes and posttranslational modifications, can be elucidated. Since immunoassays typically comprise a number of repetitive steps and require expensive reagents, they are a ripe target for adaptation to the microscale format, where sample sizes, reagent quantities, and analysis times are all greatly reduced.

Basic Methodology

The methods used in microscale proteomics applications can be divided into two categories, related to the features of microfluidic devices, and the nature of the analyses and assays themselves.

Features of Microfabricated Proteomic Devices

In proteomics applications, the most important features of microfluidic systems are related to delivery of fluid reagents, immobilization of proteins, mixing and reactions, and geometric microarrays.

Movement of Fluids

A critical decision for any microfluidic system is how to generate and control the flow of fluid. The most common methods rely on external pumps or electrokinetic flow. Conventional pumps are too large for pumping ~nL volumes of solutions, requiring splitters to isolate a fraction of the pressure to apply to the device. Smaller pumps such as syringe pumps are used frequently, but can be difficult to interface with microchannels in a device. Another common option is using electroosmotic (or electrokinetic) flow (EOF) to move analytes through a chip. This method is advantageous because it doesn't require any pressure to be applied on the sometimes fragile chips, it can move fluids at fast rates (exceeding 33 mL/min), and electrodes can easily be integrated into the chip itself. The magnitude of EOF is a function of the density of charge on microchannel walls (or on the surface of packed media); thus, careful consideration must be made in determining the materials used to fabricate devices. If materials without adequate charge density are used (or if the native EOF is too weak or strong), there are a number of coatings that can be used tune the direction and magnitude of EOF (►electroosmotic flow). Electrokinetic effects can also be used to separate the constituents of solutions; however, this can be one of its biggest disadvantages. Any fluid pumped by this method will have its components at least partially separated from one another, creating an inherent bias in any injected sample plug, and flow rates will vary due to protein adsorption on the interior of the chip or with Joule heating in the device. A final disadvantage is that all solutions must contain buffer ions in a particular concentration range, which is not convenient for all applications.

There are several less common alternatives for controlling fluid flow in microchannels. ►Digital microfluidics (DMF) is an alternative fluid handling method that is beginning to be used in proteomic applications. In DMF, discrete droplets are manipulated on a surface (rather than as streams in enclosed channels) via electrowetting and/or dielectrophoretic forces generated when an electrical potential is sequentially applied to electrodes in an array. This technique can be used with a wide variety of different fluids and can be applied to some aspects of sample preparation and purification. Hydrodynamic pumping, in which flow is driven by siphoning from one fluid reservoir to another, is an option for driving flow that does not introduce a sampling bias. It can, however, be difficult to control; consistency and fine-tuning of flow rate are problematic. Centrifugal pressure flow is another attractive option for fluid movement in protein studies, as it is insensitive to pH, ionic strength, and other characteristics of the fluid that may need to be varied for different assays. Centrifugal pumping is also relatively unaffected by the deposition of analytes onto channel walls (unlike EOF, DMF, etc.); however, it typically relies on single-use valves and therefore flow can only be driven one-time, and in one direction.

Immobilized Proteins

There are two basic formats in which assays are incorporated in microfluidic devices: homogeneous, or solution-based, assays, and heterogeneous, or surface-based, assays. Both approaches significantly reduce sample and reagent consumption relative to their macroscale counterparts, but heterogeneous assays are emerging as the dominant method for proteomics, as they can be adapted to many different types of interactions (Fig. 1a–f) [2].

Heterogeneous assays require proteins or other substrates to be immobilized on surfaces, which allows for conservation and repeated use of the immobilized bed, as well as facilitating the analysis of a sample without need for a separate concentration or mixing step. Also, the binding event or interaction between analytes is not restricted by equilibrium conditions or adequate mixing/diffusion of reagents. Finally, immobilization makes it easier to incorporate more than one reaction-zone in a device, increasing the number of analyzes that can be performed on a sample and taking greater advantage of the benefits of a microfluidic system. Several properties are required for useful surface-immobilized proteins, including: the sur-


Antigen-antibody
a
b
Protein-protein
c
Aptamers
d
K +ADP
K +ATP
Enzyme-subtrate
SP SP S
e
Receptor-ligand
f
Attachment mechanisms
+ + + / / /
Electrostatic/ Hydrophobic interaction
Physical Entrapment
CHO
covalent binding
Biorecognition (oriented)
g Simplified represention not dawn in scale

Drug Discovery Today

Proteomics in Microfluidic Devices, Figure 1 (**a**)–(**f**) Several heterogeneous protein assay formats (reprinted from [2]). A variety of protein binding events can be studied, ranging from antibody/antigen to protein/protein to enzyme/substrate interactions. (**g**) Strategies for the immobilization of proteins on solid supports (reprinted from [4])

face must have a high binding capacity for the capture protein, the immobilized protein must retain its biological activity, the protein must be spatially accessible, and there must be a low level of *non*specific interactions between proteins in solution and the coated surface.

In microfabricated devices, protein immobilization is most often carried out on glass or silicon supports, using a wide variety of surface chemistries [3]. The most common methods for attachment of proteins to surfaces are depicted in Fig. 1g [4], ranging from simple (e. g., adsorption of proteins via electrostatic or hydrophobic interactions with the surface, entrapment in immobilized polymers, etc.) to more sophisticated techniques, relying on covalent bonding and biological recognition (e. g., biotin/streptavidin). In general, the most robust immobilized protein beds are formed by covalent attachment. One popular method requires two steps: a first layer is formed by silane chemistry such that the surface presents a reactive group (e. g., epoxy, amino, thiol, etc.), and a second layer (e. g., the protein to be immobilized or a linker molecule) is covalently attached via the immobilized reactive groups. Other strategies include covalent attachment to functionalized polymer coatings on the interior of the device or linkage to the free end of a self-assembled monolayer (SAM) on a gold surface. Most of these methods result in incomplete coating of the surface, and some reactive groups are left vulnerable to interaction with target proteins during analysis; this phenomenon is called non-specific interaction, and can negatively impact assay performance. A number of strategies exist for blocking surfaces to prevent nonspecific binding of analytes, most of which involve coatings of polymers (e. g., polyethylene glycol) or proteins (e. g., albumin or casein) that will not interact with the sample. However, even with these precautions, interactions between analytes and the surface of the device are very difficult to eliminate.

Mixers and Microreactors

In contrast to heterogeneous assays, in homogeneous assays, solutions of an enzyme and a substrate or an *antibody* and antigen are combined in a channel to evaluate the enzyme kinetics or properties of inhibitors, or measure the amount of displaced antigen, which requires thorough mixing. In low Reynold's Number microfluidic channels, turbulent mixing is not possible, and diffusive mixing dominates. Diffusive mixing is a reasonable technique for small molecules; however, enzymes and other large molecules diffuse much too slowly for adequate mixing in many proteomic applications. A number of passive mixing schemes in microfluidic systems have been developed – for example, a network of interconnecting channels of varying lengths and widths is capable of mixing solutions being pumped by electroosmotic flow, while patterned surface grooves enable mixing in a pressure-flow device.

One solution to the challenges of mixing proteins in microfluidic systems is to immobilize proteins in *microreactors* [5]. These systems typically consist of chambers of enzymes immobilized on beads, micropillars [6], or porous polymer monoliths [7] (Fig. 2a–b). Such systems have large surface area-to-volume ratios, which minimizes diffusion time for reactions with solution-phase reagents. Microreactors can be used either for the conversion of an analyte to another form that is more easily detected, or for direct studies of the properties of enzymes and substrates. One of the most common uses is for the digestion of proteins for proteome profiling, but such systems can also be used for the removal of amino acid residues from peptides or proteins or for enzyme kinetic studies.

Microarrays

Biological microarrays are two-dimensional arrangements of immobilized spots of molecules on a surface. When a microarray is exposed to a solution containing unknown analytes bearing an appropriate label, analytes binding to particular spots on the surface can be rapidly identified. DNA microarrays were introduced in the late 1990s, and have become a widely used tool for high-throughput genomic analysis; however the development of similar tools for proteome analysis has been hampered by the diverse properties of proteins. For example, all DNA molecules inherently possess specific capture properties through complementary base-pairing; proteins do not have such a universal property. Additionally, protein capture *ligand*s tend to be more delicate in structure and function than the relatively robust DNA molecule. Finally, small amounts of DNA can be detected quite easily using amplification techniques such as the polymerase chain reaction (PCR); no such amplification technique exists for proteins.


Enzyme film
Micropillar
10 μm
1 μm
a
b
sample of serum containing antibodies
BSA
serailly diluted antibody solutions
antigen-presenting membrane
overall ~ 6 cm
1mm
mixer
Δy = 4mm
200 μm
μDN
area of antigen-antibodyinteractions
stripes presenting different antigens
Area for antibody-antigen interaction
+ control
serial dilutions
- control
c

Proteomics in Microfluidic Devices, Figure 2 (**a**) An enzymatic microreactor containing micropillars that have been coated with trypsin for protein digestion. Reprinted from [6]. (**b**) Porous monolith microreactors of various pore sizes. Pore size is determined by the ratio of monomer to porogen (solvent) during polymerization. Reprinted from [7]. (**c**) A microdilution network (μDN) for the quantitation of multiple antigens. The device uses a series of T-intersections to sequentially dilute a serum sample. Herringbone patterned areas are used as mixers in the dilution channels. Several antibodies have been deposited on a membrane using a microfluidic network, and the membrane is incorporated in the bottom of the μDN device. Reprinted from [12]

Despite these disadvantages, the promise of multiplexed detection of analytes has made protein microarrays a popular research topic in microfluidic implementations of proteomic analyses.

The immobilized spots used in protein microarrays may contain protein molecules, or smaller molecules such as inhibitors or ligands with which a protein in solution may interact. Very small spots are advantageous in that higher detection throughput can be achieved with minimal amounts of printed material and sample. Spots are typically deposited either by contact methods, such as printing arrayers that use needles to deposit droplets directly on the surface, or by non-contact methods, including the use of capillaries or ink jet dispensers to deposit droplets with nanoliter-picoliter volumes.

An alternative to microarrays is the use of arrays of multiple parallel channels. Typically, such structures are used to carry out a number of duplicate assays on one or more samples, to perform a serial dilution of a single sample for quantitation of a given protein, or to detect multiple targets in a single sample. In the latter case, an array of channels may be used in conjunction with a printed array of spots or bands – the channel network is used for fluid delivery to the printed array (Fig. 2c).

Analyses and Assays

Microfluidic devices are used in a variety of profiling and functional proteomics applications; the goal in much of this work is to reduce sample and reagent consumption and increase throughput. The primary application in profiling proteomics is in the preparation of protein samples for separations and mass spectrometry, while the major functional proteomics tools are enzymatic and immunological assays.

Sample Preparation for Profiling Proteomics

The identification of unknown proteins often requires that they be digested (or divided) into a group of constitutive peptides, which are interrogated by mass spectrometry. Comparing the masses of the peptides to genomic databases enables absolute identification by means of peptide mass fingerprinting (PMF). Proteins are digested by exposure to proteolytic enzymes (e. g., trypsin), or other lytic reagents (e. g., cyanogen bromide, CNBr); this is often part of a multistep process requiring 12 – 18 h, including mixing the sample with buffer and denaturant, mixing and incubating the sample with reducing agent to reduce disulfide bonds, mixing and incubating the sample with alkylating agent to prevent disulfide bonds from reforming, and finally, mixing and incubating with lytic reagent. This process is extremely tedious and time-consuming, making it an attractive application for microfluidics.

Several device configurations have been used for proteomic processing in microfluidic devices, including open channels, immobilized beads, and other solid phase media. Open-channel devices for tryptic digestion and reduction of disulfides in proteins are capable of achieving complete tryptic digestion in timeframes ranging from 15 min to 5 s. Immobilized beads increase the surface-to-volume ratio further; for example, a bed of trypsin-modified beads immobilized in a microfluidic chamber can be used very effectively for *proteolysis* of relatively large volumes of flowing sample. An alternative method for increasing the surface area-to-volume ratio in microfluidic devices is to use trypsin-modified monoliths, formed from polymer plugs cured in situ, or from membranes sandwiched between channels. Trypsin and other enzymes can also be copolymerized within hydrogel microstructures – the hydrogel is a biocompatible matrix that reduces the likelihood of damage to the enzyme during and after immobilization.

Microfluidics is promising for developing tools with integrated chemical processing of proteomic analytes, by virtue of fast reaction kinetics. Sample purification and concentration can be carried out on the microscale by methods such as solid phase extraction on hydrophobic surfaces ►lab-on-chip devices for sample extraction or affinity chromatography ►chromatographic chip devices. Immunoassays on magnetic beads have been used not just for detection of antigens (described below), but also as a purification method for the isolation of a target for mass spectrometry. However, to our knowledge, there have been no reports of implementing a fully integrated process, including stepwise reduction, alkylation, and digestion. Microfluidic tools for chemical processing will likely not be widely adopted until this critical benchmark is achieved.

Enzymatic Assays

Traditionally, enzymatic assays are performed in microtitre plates (plastic trays containing arrays of isolated wells), where an enzyme and its substrate are mixed in an individual well, and the substrate turnover is measured to determine the activity of the enzyme. Microfabricated devices that can perform enzymatic studies without interference between individual elements are highly desirable, as the macroscale method consumes a great deal of enzyme. There are three basic applications of enzymatic assays in proteomic studies:

1. small molecule detection or sensing via an enzymatic reaction,
2. studies of enzyme–substrate, protein–ligand, and protein–protein interactions, and
3. kinetic studies.

The first type of enzyme application in microfluidics is chemical sensing. Sensors can be constructed in cases where an enzyme turns over a particular small-molecule substrate to produce a product quantifiable by fluorescence, chemiluminescence, absorbance spectroscopy, or electrochemical detectors. In cases where the substrate is not detectable itself, an enzymatic product can often be coupled to another enzyme that produces a detectable product. For example, there are a wide variety of small molecules (such as nutrients, amino acids, and sugars) that can be coupled to the chemiluminescent reaction of luminol and peroxide in the presence of horseradish peroxidase. These enzyme-substrate assays were the first to be adapted to microfluidic devices – a great number of small-molecule sensors have been developed based on microfluidic channels with electroosmotic or hydrodynamic flow, and pre-loaded microfluidic cartridges containing nanoliter volumes of reagents have shown great promise as a replacement for 96-well plates for high-throughput screening [8].

The second type of enzyme application in microfluidics is protein interaction studies. In order to study interactions between enzymes and substrates, peptides, or other proteins, an alternative to microtitre plates is the microarray. These arrays are very often used in conjunction with microfluidic sample and reagent delivery systems; alternatively, microchannels can be used to deposit spots in an array. By immobilizing substrates or inhibitors on the array, it is possible to screen large numbers of molecules for their relative abilities to bind a particular enzyme. This is typically accomplished by tagging the enzyme with a fluorescent molecule and using the intensity of the array spots to determine the amount of enzyme bound (Fig. 3a). This is a promising approach for the identification of protein drug targets, or for the evaluation of compound libraries in drug discovery. Peptide fragments of proteins of interest have great potential as capture ligands, as they are easy to synthesize, stable, and able to mimic proteins. However, small molecules such as peptides are difficult to immobilize on a surface such that they are still accessible to the sample. Peptide fragments are also not as specific as complete proteins; for some applications, it is preferable to immobilize an entire protein to characterize its interactions with other proteins or enzymes of interest. Sample delivery to the elements of an array via microfluidics enables hundreds of different analyses to be performed on a single sample while reducing the size of that sample from microliter volumes to nanoliters.

A third type of enzyme application in microfluidics is kinetic studies, which may be carried out in either homogeneous or heterogeneous format. In homogeneous assays, adequate mixing of the enzyme, substrate, and any inhibitors that are being studied is crucial – this is done either via the merging of reagent streams at a T- or Y-shaped junction between channels or by means of a microfabricated mixer to ensure complete homogenization. A microfluidic mixer is advantageous – it ensures complete mixing of the enzyme and substrate and a smaller quantity of enzyme is consumed. Electrophoretically-mediated microanalysis, or EMMA, uses electrokinetic forces as the pumping method, which has the added benefit of separating product from substrate as the analysis proceeds. EMMA was first developed in capillary electrophoresis systems, but was readily adapted to microchannel setups [9]. Since a chip disperses Joule heat much more efficiently than a capillary does, the analysis can be run at higher potentials, increasing the speed of measurement. In most cases, a modified substrate is used that is converted to a fluorescent, chemiluminescent, or colored product by the enzyme, and optical methods are used to calculate factors such as the turnover number and Michaelis constant. Kinetic assays have also been carried out in centrifugal flow microfluidic devices [10], which are applicable for a wide variety of biological samples, including whole blood, plasma, and urine, that are incompatible with electroosmotic flow systems. Centrifugal devices are also easily adapted to perform multiple analyses on a single plastic device, reducing the costs of manufacturing. However, fresh enzyme is required for each determination, making enzyme recovery difficult. Heterogeneous enzyme microreactors eliminate the need for recovery



Proteomics in Microfluidic Devices, Figure 3 Detection of binding of a protein analyte in a heterogeneous (**a**) or homogeneous (**b**) assay. In (**a**), the fluorescence intensity of spots on an array reflects the amount of the target protein in the sample solution. Different analytes are tagged with molecules that fluoresce at different wavelengths to simplify identification. In (**b**), the tetanus toxin-C-fragment (TTC) is fluorescently labeled and separated from the antibody-TTC complex in an electrophoretic channel for quantification. Reprinted from [11] steps and dead time during the measurement. Microfluidic devices containing immobilized enzymes enable the study of kinetics with excellent enzyme recovery and decreased reagent consumption, increasing the overall efficiency of the method and greatly decreasing waste.

Immunoassays

Like enzymatic assays, immunoassays are conventionally implemented in microtitre wells, but they are even more easily adapted to the microscale. Homogeneous immunoassays are typically employed for the study of small molecules, while heterogeneous immunoassays are preferred for large-molecule detection.

A homogeneous assay is carried out by combining an antigenic sample and an antibody by means of electrokinetic flow in a microchannel. After the antigen binds the antibody, the complex can be separated from the remaining free antibody via electrophoresis to determine the amount of antigen present in the sample (Fig. 3b) [11]. On a microfluidic chip, this analysis can easily be multiplexed – a different assay can be performed in different channels on the same sample.

There are two common forms of heterogeneous assays used to detect and quantify disease markers: the direct-labeling method, in which the proteins in a sample are labeled with a detectable tag and isolated from a complex sample by means of a bed of immobilized antibodies, and the indirect-labeling method, in which two antibodies are used for each marker. Sandwich-type immunoassays, such as the enzyme-linked immunosorbent assay (ELISA), require two antibodies: an immobilized antibody used to capture a molecule of interest – a protein, a virus, or a small molecule (e. g., a hormone, pharmaceutical, or environmental pollutant) – and a second antibody in solution that is conjugated to a detectable tag. Immunoassays have also been carried out with detection via surface plasmon resonance microscopy, atomic force microscopy, and electrochemical sensors, eliminating the need for a detectable label. These assays are very useful because the antibody-antigen binding that must occur at each step is highly specific and thus has built-in redundancy – they are very sensitive and capable of quantitation of changes in concentration with a dynamic range of up to 2 – 3 orders of magnitude. As for enzymatic assays, microfluidic channels can be used either to deposit the first antibody onto a surface for immobilization or to direct the sample over the immobilized antibody (concentrating the antigen on the surface in the process) and any subsequent reagents – in some cases, microfluidic systems have been used for both purposes [12]. While basic immunoassays are well-suited for determining the presence of a given molecule in a sample and sometimes the quantity, they do not provide any other information about the target molecule. In recent work, immunoassays have been adapted to provide structural and post-translational modification information on marker proteins, however, these assays have not yet been widely applied to microfluidic devices and are still primarily performed in microtitre wells.

Key Research Findings

In the first report of on-chip proteolytic processing, Gottschlich et al. used open-channel devices for tryptic digestion and reduction of disulfides in proteins, which enabled complete processing in 15 min. More recently, Huang et al. [13] and Liu et al. [14] used surface adsorbed trypsin in channels to enable complete digestion in less than 5 s. In an alternative strategy, Yue et al. used a bed of trypsin-modified agarose beads immobilized in a weir in a glass microfluidic device to digest β-casein [15]. Peterson et al. used the related heterogeneous technique of forming methacrylate plugs cured in situ to increase the surface area-to-volume ratio to achieve tryptic digestion of myoglobin in $\sim$11 s [16]. Sakai-Kato et al. developed similar methods using trypsin immobilized in a sol-gel matrix [17]. Gao et al. reported using a trypsin-modified polyvinylidiene fluoride (PVDF) membrane in a PDMS microfluidic chip, enabling protein digestion in 3 – 10 min [18]. Each of these methods represents a vast improvement over conventional macroscale proteolysis, which typically requires hours-days. One promising approach for sample purification during processing is the use of digital microfluidics to remove hydrophilic impurities from proteomic samples [19].

Hadd et al. performed the first homogeneous assays to determine enzyme kinetics in a microfluidic chip – these assays relied on diffusional mixing of β-galactosidase and resorufin β-D-galactopyranoside (RBG) within a channel electrophoresis system [9]. This assay successfully characterized the kinetics of the enzyme, and reduced reagent consumption by four orders of magnitude over conventional assay methods. The same assay was later modified by Burke et al. by including a passive microfluidic mixer, resulting in a characterization of enzyme kinetics that more closely agreed with that obtained via conventional methods [20]. Puckett et al. developed a centrifugal microfluidic system in which homogeneous protein-ligand binding assays were performed to detect and characterize the binding interaction between phenothiazine antidepressants and calmodulin, a calcium-binding protein known to interact with this class of drugs [21]. This system utilized pre-measured aliquots of reagents,



Proteomics in Microfluidic Devices, Figure 4 (**a**) Use of hydrodynamic flow to create a microfluidic stream and direct it to specific areas of a larger channel. (**b**) The flow system is used to deposit biotinylated fluorescein in a grid pattern. The direction of flow during deposition is indicated by arrows. (**c**) Quantitation of C-reactive protein (CRP) in whole blood. Samples of blood were spiked with CRP and the microstream directed across a surface coated with anti-CRP before exposure with a Cy3-labeled secondary antibody. Reprinted from [24] under open access agreement with BioMed Central.

increasing the speed and reproducibility of the analysis for high-throughput applications. In an effort to integrate multiple analyses on one device, Wang et al. incorporated two homogeneous assays into one microfluidic channel: an enzymatic assay for glucose and an immunoassay for insulin [22]. Electrokinetic effects were used for both fluid movement and separation of the components before detection. Through the use of pre- and post-column reactors and an electrophoretic separation of analytes, two independent measurements were made in the same space.

Perhaps the greatest area of interest in microfluidics for proteomics applications is in multiplexed, heterogeneous assays. Kim et al. used microfluidic PDMS channels to pattern sol–gels on polyvinylacetate-coated glass slides under conditions mild enough to retain protein activity [23]. The use of a microfluidic channel system generated a well-defined, intricate pattern of immobilized protein that simplified data collection. Jiang et al. patterned antigens on a membrane via a microfluidic network, and then positioned the membrane under a microdilution network to carry out serially-diluted immunoassays to detect multiple antigens on the patterned surface (Fig. 2c) [12]. This fluidic network enables the simultaneous quantitation of several molecules that vary widely in concentration – a major challenge in proteomics – in a single submicroliter sample. Brevig et al. developed a hydrodynamic microfluidic system that uses two streams of fluid to focus a sample and perform parallel immunoassays to quantitate levels of C-reactive protein, a well-known marker of inflammation (Fig. 4) [24]. As this method effectively creates a microscale stream within a larger chamber, it conserves sample but can also be carried out on whole blood without risk of clogging very small channels. In recent years, a great number of biochips have been made commercially available that use networks of microfluidic channels to perform analyses of over 100 different proteins using only 0.1 µL of whole blood [25]. These chips are capable of separating plasma from blood cells, and then directing the plasma sample across an ELISA array – the heterogeneous array format and simplified sample prep are advantageous in terms of both speed of analysis and reduced sample consumption. This is very promising, as the cleanup of whole blood is a major bottleneck to the use of microfluidics in medical applications.

Future Directions for Research

The future of miniaturization in proteomic applications lies in achieving greater sophistication of devices. A variety of arrays have been used to investigate post-translational modifications such as phosphorylation and glycosylation, and it is only a matter of time before these are incorporated into microfluidic systems. Factors such as antibody synthesis currently limit the range of proteins that can be incorporated on an array, and devices that are capable of simultaneous quantitation of a protein and the study of its post-translational modifications, activity, etc., are not yet fully realized. Enzymatic microreactors are evolving in directions that will enable rapid screening of enzyme inhibitors for pharmaceutical purposes, industrial-scale synthesis, and environmental applications such as conversion of used grease to diesel fuel. Tools such as biochips mark the beginning of a shift from central laboratory to point-of-care testing, one of the hallmark aims of microfluidic technology. Together, these innovations will enable the development of a true total analytical system capable of greatly increasing the efficiency and throughput of any number of diagnostic, prognostic, and industrial processes.

Cross References

- ► Biosample Preparation Lab-on-a-Chip Devices
- ► Chromatographic Chip Devices
- ► Digital Microfluidics
- ► DNA Micro-arrays
- ► Interfaces between Microfluidics and Mass Spectrometry
- ► Lab-on-Chip Devices for Immunoassay
- ► Lab-on-Chip Devices for Protein Analysis
- ► Lab-on-Chip Devices for Sample Extraction
- ► Microfluidic Bioreactors
- ► Droplet Microreactors

References

1. Friere SLS, Wheeler AR (2006) Proteome-on-a-chip: Mirage or the Horizon? Lab Chip 6(11):1415–1423
2. Templin MF, Stoll D, Schrenk M, Traub PC, Vohringer CF, Joos TO (2002) Protein microarray technology. Drug Discovery Today 7(15):815–822
3. Peterson DS (2005) Solid supports for micro analytical systems. Lab on a Chip 5(2):132–139
4. Cretich M, Damin F, Pirri G, Chiari M (2006) Protein and peptide arrays: Recent trends and new directions. Biomol Eng 23(2–3):77–88
5. Urban PL, Goodall DM, Bruce NC (2006) Enzymatic microreactors in chemical analysis and kinetic studies. Biotechnol Adv 24(1):42–57
6. Kato M, Inuzuka K, Sakai-Kato K, Toyo'oka T (2005) Monolithic bioreactor immobilizing trypsin for high-throughput analysis. Anal Chem 77(6):1813–1818
7. Hayashi K, Iwasaki Y, Kurita R, Sunagawa K, Niwa O, Tate A (2005) The highly sensitive detection of catecholamines using a microfluidic device integrated with an enzyme-modified pre-reactor for interferent elimination and an interdigitated array electrode. J Electroanal Chem 579(2):215–222
8. Linder V, Sia SK, Whitesides GM (2005) Reagent-loaded cartridges for valveless and automated fluid delivery in microfluidic devices. Anal Chem 77(1):64–71
9. Hadd AG, Raymond DE, Halliwell JW, Jacobson SC, Ramsey JM (1997) Microchip Device for Performing Enzyme Assays. Anal Chem 69(17):3407–3412
10. Duffy DC, Gillis HL, Lin J, Sheppard NF, Jr., Kellogg GJ (1999) Microfabricated Centrifugal Microfluidic Systems: Characterization and Multiple Enzymatic Assays. Anal Chem 71(20):4669–4678
11. Herr AE, Throckmorton DJ, Davenport AA, Singh AK (2005) On-chip native gel electrophoresis-based immunoassays for tetanus antibody and toxin. Anal Chem 77(2):585–590
12. Jiang X, Ng JMK, Stroock AD, Dertinger SKW, Whitesides GM (2003) A Miniaturized, Parallel, Serially Diluted Immunoassay for Analyzing Multiple Antigens. J Am Chem Soc 125(18):5294–5295
13. Huang JX, Mehrens D, Wiese R, Lee S, Tam SW, Daniel S, Gilmore J, Shi M, Lashkari D (2001) High-throughput genomic and proteomic analysis using microarray technology. Clin Chem 47(10):1912–1916
14. Liu Y, Lu H, Zhong W, Song P, Kong J, Yang P, Girault HH, Liu B (2006) Multilayer-Assembled Microchip for Enzyme Immobilization as Reactor Toward Low-Level Protein Identification. Anal Chem 78(3):801–808
15. Lin Y, Timchalk CA, Matson DW, Wu H, Thrall KD (2001) Integrated microfluidics/electrochemical sensor system for monitoring of environmental exposures to lead and chlorophenols. Biomed Microdevices 3(4):331–338
16. Peterson DS, Rohr T, Svec F, Frechet JMJ (2002) Enzymatic microreactor-on-a-chip: Protein mapping using trypsin immobilized on porous polymer monoliths molded in channels of microfluidic devices. Anal Chem 74(16):4081–4088
17. Sakai-Kato K, Kato M, Toyo'oka T (2004) Screening of inhibitors of uridine diphosphate glucuronosyltransferase with a miniaturized on-line drug-metabolism system. J Chromatogr A 1051(1–2):261–266
18. Nie S, Han M, Gao X (2001) Lab-on-a-bead: Optically encoded microspheres for massively parallel analysis of genes and proteins. Abstracts of Papers, 221st ACS National Meeting, San Diego, CA, United States, April 1-5, IEC-019
19. Wheeler AR, Bird CA, Loo JA, Garrell RL, Loo RRO, Kim CJ, Moon H (2005) Digital microfluidics with in-line sample purification for proteomics analyses with MALDI-MS. Anal Chem 77(2):534–540
20. Burke BJ, Regnier FE (2003) Stopped-Flow Enzyme Assays on a Chip Using a Microfabricated Mixer. Anal Chem 75(8):1786–1791

21. Puckett LG, Dikici E, Lai S, Madou MJ, Bachas L, Daunert S (2004) Investigation into the Applicability of the Centrifugal Microfluidics Platform for the Development of Protein-Ligand Binding Assays Incorporating Enhanced Green Fluorescent Protein as a Fluorescent Reporter. Anal Chem 76:7263–7268
22. Wang J, Ibanez A, Prakash CM (2003) On-chip integration of enzyme and immunoassays: Simultaneous measurements of insulin and glucose. J Am Chem Soc 125(28):8444–8445
23. Kim Y-D, Park CB, Clark DS (2001) Stable Sol-Gel Microstructured and Microfluidic Networks for Protein Patterning. Biotech Bioeng 73(5):331–337
24. Brevig T, Kruhne U, Kahn RA, Ahl T, Beyer M, Pedersen LH (2003) Hydrodynamic guiding for addressing subsets of immobilized cells and molecules in microfluidic systems. BMC Biotechnology 3(10)
25. Dupuy AM, Lehmann S, Cristol JP (2005) Protein biochip systems for the clinical laboratory. Clin Chem Lab Med 43(12):1291–1302

Proton Exchange Membrane Fuel Cells

► Microstructured Hydrogen Fuel Cells

PRT

► Resistance Temperature Detectors

Pump Head

Synonyms

Backpressure; Differential pressure; Head pressure

Definition

Pump head is the pressure rise from pump inlet to pump outlet. The *characteristic curve* of a pump relates pump head to flow rate. The pump head at which the flow rate is zero is called the *shut-off head* or *maximum head*.

Cross References

► Magnetic Pumps
► Membrane Actuation for Micropumps
► Peristaltic Pumps
► Positive Displacement Pump

Pyroelectric

► Pyroelectric Flow Sensors

Pyroelectric Flow Sensors

HUI YAN, HONGKAI WU
Department of Chemistry, Tsinghua University, Beijing,
P. R. China
hkwu@mail.tsinghua.edu.cn

Synonyms

Pyroelectric sensors; Pyroelectric; Thermal flow sensors

Definition

A *pyroelectric* is substance that generates an electrical charge during a temperature change. The *pyroelectric coefficient* is the measured change in the polarization with a variation in the temperature in a single-domain pyroelectric material. *Pyroelectric sensors*, in principle, work as thermal transducers. The pyroelectric sensing element converts a non-quantified thermal flux into an output measurable quantity like charge, voltage or current.

Overview

Pyroelectric Effect

The pyroelectric coefficient (p) of a material under constant stress and electric field is defined by the following expression:

$$p = \left(\frac{\partial P}{\partial T}\right)_{E,\sigma} \tag{1}$$

where P is the polarization, T the temperature, E the electric field and σ ghe elastic stress.

Pyroelectrics can be classified into two main categories:

- non-pyroelectric pyroelectrics, those whose polarization cannot be switched by an application of external electric field (such as some semiconductors and biological materials); and
- pyroelectric pyroelectrics, those whose polarization is obtained by poling and also can be switched by an electric field.

The pyroelectric effect of pyroelectric pyroelectrics usually exists below a certain transition temperature called the *Curie point*, T_c, in proper pyroelectrics and is more temperature dependent than that of the non-pyroelectric pyroelectrics.

Primary and Secondary Pyroelectric Effects

Thermodynamic analysis of the pyroelectric effect yields the expression

$$P_i^{\sigma} = P_i^{\varepsilon} + d_{ijk}^{T} c_{jklm}^{T,E} \alpha_{lm}^{\sigma} \tag{2}$$

where P_i^{σ} is the total pyroelectric effect measured at constant stress, and P_i^{ε}, the pyroelectric effect at constant strain ε, is called the primary effect. The second term of Eq. (2) is the contribution caused by thermal deformation of the crystal and is known as the secondary pyroelectric effect. Parameters d, c and σ are the piezoelectric, elastic stiffness and thermal expansion coefficients of the crystal, respectively.

In pyroelectric ferroelectrics, generally, the primary effect is large and negative because the spontaneous polarization decreases with increasing temperature. The secondary effect is considerably smaller and may have either sign depending on the values of the constants. And so the experimentally observed pyroelectric coefficients are dominated by the primary effect and are negative in pyroelectric crystals. But in non-ferroelectric pyroelectric crystals there is no simple way to predict the sign and the magnitude of their coefficients. In practice the total pyroelectric effect can be measured and, also, the secondary effect calculated from the constants d, σ and c.

Pyroelectric Currents

Pyroelectric currents are proportional to the time derivative of the temperature and, in case of infrared (IR) detectors, to the changes of IR radiation. In order to assess stationary IR sources as well, a chopper is used to modulate the IR radiation. Signals thus exhibit a well-defined angular chopping frequency ω. The smallest detectable temperature change is limited to the temperature fluctuation of the detector system, the electronics or the intrinsic noise current j_n of the pyroelectric element, given here for a thin film by the expression

$$j_\mathrm{n} = \sqrt{\frac{A}{t} 4KT(\sigma + \omega\varepsilon_\mathrm{r}\varepsilon_0 \tan\delta \Delta f)} \qquad (3)$$

where σ is the leakage conductivity of the pyroelectric thin film (in bulk detectors, the parallel resistor); ω the angular frequency; $\tan\delta$ the loss tangent; Δf the frequency bandwidth; A the surface; and t the thickness of the element.

The crossover frequency $\omega_\mathrm{el} = \sigma/\varepsilon_\mathrm{r}\varepsilon_0 \tan\delta$ between resistor-type noise and dielectric noise is typically $0.1 - 10$Hz. At typical modulation frequencies of 30 Hz, the dielectric noise dominates. The figure of merit of dielectric and pyroelectric material parameters for an optimal detectivity can thus be formulated as

$$F_D = \frac{p}{\sqrt{\varepsilon_0\varepsilon_\mathrm{r} \tan\delta}} \qquad (4)$$

Essential Materials

Pyroelectrics in Materials with Perovskite Structure

Perovskite oxides have the structural formula ABO in which A may be some large cation, such as Ba^{2+} or Pb^{2+}, and B may be some medium size cation, such as Ti^{4+} or Zr^{4+}. These cations are located in cages formed by the network of the oxygen anions. There is an abundance of perovskites, natural (minerals) and synthetic ones, because of a large number of cations having sizes that can fit into the oxygen cages. Pyroelectric perovskites are a sub-group in the perovskite family.

Lead Zirconate Titanate (PZT)

Because of its high piezoelectric constants, PZT is the most widely used pyroelectric ceramic in sensor applications. PZT is a solid solution of lead titanate and lead zirconate. The substitution of a small fraction (~1 %) of the PZT cations by other cations can improve the properties. This method is always used to produce PZT that is optimized for different applications. Doping by cations of lower valence, e. g. Fe^{3+} replacing Ti^{4+}, Zr^{4+} and/or Na^+ for Pb^{2+}, results in oxygen vacancies that stabilize the domain walls. PZT ceramics with dopants of lower valence (acceptors) are very useful for underwater applications and also for high-power and high-voltage applications. Doping with a higher valence than the substituted cations (donors), e. g., Nb^{5+} for Ti^{4+}/Zr^{4+} and/or La^{3+} for Pb^{2+}, increases the concentration of lead vacancies, enhancing the mobility of domain walls. These materials are used for medical transducers and for sensitive pressure sensors. PZT ceramics for pyroelectric applications are rich in titanium. The compositions rich in titanium (e. g., zirconium titanium) have a high pyroelectric coefficient and low permittivity, giving good pyroelectric figure of merit. Additionally, their coercive field is high, reducing the risk of depolarization during use and making this composition useful also in the form of thin films.

Relaxors and Relaxor Pyroelectrics

A large number of lead-containing perovskites, called relaxors, show anomalous characteristics typified by a strong frequency dispersion of the permittivity. Examples are lead magnesium niobate ($PbMg_{1/3}Nb_{2/3}O_3$ or PMN) and lead zinc niobate ($PbZn_{1/3}Nb_{2/3}O_3$ or PZN). These materials have many useful advantages:

- very high permittivity over a wide temperature range,
- large electrostrictive strain and
- strong pyroelectric response under a DC bias field. Solid solutions of relaxors and normal pyroelectrics, which are the subject of much interest, are called relaxor pyroelectrics, such as $PMN-PbTiO_3$ and $PZN-PbTiO_3$.

Layer Perovskites

A large number of pyroelectrics crystallize in the so-called layer perovskite phases. These phases are made of layers of perovskites separated by other layers; a typical example is bismuth oxide. Many pyroelectric layer perovskites have a high T_c, making them interesting for high-temperature piezoelectric applications. In addition, many of them are lead free. A prototype material is bismuth titanate ($Bi_4Ti_3O_{12}$).

Lithium-niobate and Lithium-tantalate

Lithium-niobate (LN) and lithium-tantalate (LT) are uniaxial pyroelectrics, having trigonal structure, with spontaneous polarization arising from asymmetrical displacement of lithium relative to the other ions. These materials' T_c values are 1210 and 620 °C, respectively. They are always produced commercially in single-crystal forms. Both are much used for surface acoustic wave devices (e. g., high-frequency filters), while LT is used for pyroelectric detection due to its large pyroelectric coefficient and low permittivity.

Pyroelectric Polymers

Pyroelectricity is also found in polymers. Polyvinylidenfluoride (PVDF, $(CH_2CF_2)_n$) is used for sensor applications that can benefit from a large sensor area. The pyroelectric polymers have low pyroelectric coefficients d and high coefficients because of the low permittivity. The polymers are light and then have good acoustic impedance matching to water, to organic and biological matter.

Dimensional and Microstructural Aspects of Pyroelectric Materials

Pyroelectric sensors utilize a wide range of material forms: crystals, bulk ceramics, thick layers and thin films. Noteworthy among new compositions with improved performance is the class of relaxor pyroelectrics. Many novel pyroelectric sensors utilize thin and thick films. Bulk pyroelectric ceramics for room temperature, and pyroelectric sensors, are widely available. New compositions with higher permittivity are available now.

Poling of Pyroelectric Materials

After the manufacturing, pyroelectric materials usually do not possess pyroelectric properties, since the pyroelectric domains are randomly oriented. The poling process consists of the application of a DC electric field to align the domains. A remanent polarization persists after the removal of the field and the material is pyroelectrically active. Poling is usually done at elevated temperatures (see below) using fields larger than the coercive field. During use of pyroelectric materials, care should be taken to avoid depolarization under high temperatures, electric fields or stresses.

In summary, pyroelectric materials have found applications in a wide range of fields. For device applications and the convenience of application engineers, several figures of merit criteria are defined. Most of these can be calculated using the thermal, electrical and optical characteristics of the materials available in the literature and various handbooks on the physical constants of materials.

Pyroelectric Flow Sensors

Pyroelectric flow sensors are a kind of thermal flow sensor. They can be classified according to the thermal transfer mechanism, i. e., calorimetric- or boundary-layer-type flow meters and here the latter will be introduced.

Thermal mass-flow meters directly measure the mass-flow rate utilizing the thermal transfer process between a heated element and the flowing mass. According to the thermal transfer mechanism, they can be classified as calorimetric- or boundary-layer-type flow meters. Calorimetric flow meters utilize the simple principle that as the mass flows through the device, power has to maintain the temperature of the incoming mass at a known level. By measuring the supplied power P and the temperature above ambient, ΔT, the mass-flow rate $\dot{M}$ can be calculated as the expression

$$\dot{M} = \frac{1}{c_{pg}} \frac{P}{\Delta T} \tag{5}$$

where c_{pg} is the specific heat of the mass at constant pressure. A typical example of calorimetric flow meters consist of a thin-walled capillary with a heater wire wound around its center. The wire resistor serves both to heat the center section and to provide a measure of the temperature, since the resistance of the heater wire is a function of temperature. Because the capillary has a very small diameter, the mass absorbs heat from the wall and quickly reaches the wall temperature. As the mass follows, additional power has to be supplied to compensate for the energy carried away by the mass. The mass-flow rate may be measured by keeping either the power or the elevated temperature constant.

Another type of capillary flow meter is shown in Fig. 1. A central heater (H) is wound about a thin walled capillary tube. Two resistive sensor elements are mounted on the capillary symmetrically, one upstream (S_1) and the other downstream (S_2) of the heater to monitor the temperature



Pyroelectric Flow Sensors, Figure 1 A capillary flow meter with external heater and transducers is depicted at the top with the corresponding temperature profile along the capillary for zero (upper) and nonzero (lower) gas flow

as depicted in the upper portion of Fig. 1. The difference in temperature between the two sensors

$$\Delta T_{21} = \Delta T\,(\mathrm{S}_2) - \Delta T\,(\mathrm{S}_1) \tag{6}$$

is used to determine the flow rate. In the absence of flow, the temperature profile in the capillary is symmetric with $\Delta T_{21} = 0$ as shown in Fig. 1. As mass flows, heat is transferred from the wall to the moving fluid at the upstream position, thereby lowering $\Delta T(\mathrm{S}_1)$. At the downstream electrode, energy is injected into the wall at S_2 by the heated flowing fluid, thereby increasing the temperature $\Delta T(\mathrm{S}_2)$. The net effect is an asymmetric temperature profile in the tube causing $\Delta T_{21} \neq 0$, as indicated at the bottom of Fig. 1. This differential measurement has the advantage of being directional and providing a zero signal at zero flow.

Basic Methodology

Methods for Determination of Pyroelectric Coefficients

There are several methods for measurement of pyroelectric coefficients, but most can be grouped into two kinds. The objective in the first case is to directly measure the pyroelectric current and at the same time change the temperature. In the second method measurements of polarization or charge can be estimated either by the integration of pyroelectric current during the continuous heating of the sample or recording the hysteresis loop at various temperatures by the Sawyer–Tower technique.

In the first approach the changing temperature can be generated by chopping the incoming radiation source or AC heating (known as the Chynoweth technique) of the sample and the pyroelectric response current i can be expressed as follows:

$$i = \frac{p\eta W T_{\mathrm{r}}}{Ct}$$

where η is the power absorbed by the sample, T_{r} is a transfer function depending on the thermal circuit of the sample and the chopping or modulation frequency, t is the thickness of the sample and C is the thermal capacity of the sample. Often a thin layer of highly absorbing material is applied on the sample in order to achieve $\eta = 1$.

The pyroelectric current $i(T)$ at a temperature T can also be measured by uniformly heating or cooling the sample at a constant rate (generally, 1 to 4 °C/min) and the pyroelectric coefficient, p, can be calculated using the following expression (Byer–Roundy technique):

$$i(T) = \frac{Ap}{(\Delta T/\Delta t)^{-1}}$$

where A is the electroded area of the sample and $\Delta T/\Delta t$ is the heating or cooling rate of the sample. Here, the charge release (in either of the two cases mentioned earlier) at a discrete temperature is determined and the pyroelectric coefficient is obtained graphically or by differentiation.

Methods for Thin-Film Deposition

Thin-film deposition techniques such as sol–gel method, hydrothermal route, sputtering, metalorganic chemical vapor deposition (MOCVD) and pulsed laser deposition have been developed and are being adapted in commercial devices. Table 1 lists some advantages and disadvantages of different film deposition techniques. Three major kinds are sol–gel, physical vapor deposition and chemical vapor deposition. In wet methods, the sol–gel technique uses fine powder in gel forming a liquid-like mixture of metal oxides and organic salts to grow transparent ceramic films. It is low energy consuming process at lower crystalline temperature and allows better control of chemistry by mixing of precursors in the liquid state at the molecular level. Most electroactive ceramics and polymers are amenable to this technique. Physical vapor deposition requires vacuum and uses DC or RF magnetron sputtering and pulse laser deposition to provide high quality, uniformity and stability but low deposition rates of materials. Chemical vapor deposition, i. e., MOCVD, on the other hand, uses volatile chemical precursors, which are vaporized on heated substrates. It is proving suitable for conformational deposition of high-quality three-dimensional structures on bottom electrodes and is characterized by high deposition rates.

Pyroelectric Flow Sensors, Table 1 The advantages and disadvantages of different film deposition techniques

	Deposition technique	Advantages	Disadvantages
1	Sol–gel	Lower crystallization temperature, lower cost, better control of mixing of precursors, quickly produce new materials	Lack of phase and composition control, morphology, reproducibility
2	Physical vapor deposition (i) DC sputtering (ii) Pulsed laser deposition (iii) MBE	Compatibility with IC processing Uniformity and scalability, high quality Rapid sampling of materials, quickly produce new materials Composition control, precise atomic layering, extreme flexibility and scalability	High equipment cost Low deposition rate, high point defect concentration Lack of uniformity, high residual stresses Expensive development stage
3	Chemical vapor deposition	High deposition rate, good stoichiometry control, low point defect concentration, high conformity and scalability	Low precursor stability, expensive

Properties to be Considered of an Appropriate Material

While the pyroelectric, dielectric and thermal properties of pyroelectric materials are clearly fundamental in determining the basic performance of a device, there are many other properties to be considered when making a selection of an appropriate material. These are the following:

- Electrical resistivity. The circuit in Fig. 2 shows a resistor R_G connected across the active element. This serves three functions. First, it fixes the electrical time constant τ_E of the device. Second, it allows the gate leakage current of the FET to bias its operating point. If there was no bias resistor here, the FET amplifier would not be stable and would take a long time to settle. Third, it determines the voltage responsivity.
- Piezoelectric properties. At first sight it seems surprising that piezoelectric properties are important in pyroelectric devices. However, all pyroelectric detectors used in a high-vibration or acoustically noisy environment will produce a piezoelectric microphonic noise signal, mostly through flexure, which can be very significant if steps are not taken to suppress it.
- Manufacturability. The ability to make the selected material in a large area at low cost is a very important consideration. Pyroelectric ceramics have an important advantage here over some of the single-crystal materials that are available, as a consequence of their relative ease of manufacture using a range of techniques and their stability during other subsequent manufacturing processes.

Examples for Sensor Design and Fabrication

Many studies had demonstrated that pyroelectric anemometers based on single-crystal $LiTaO_3$ have a very wide range and the promise of interesting response characteristics. The following example was well characterized by a conjugate gas-flow–heat-flow model.

A 200 μm thick, 30 mm diameter, Z-cut, single-crystal $LiTaO_3$ wafer, unpolished on both sides, was used to fabricate the pyroelectric flow sensor. The wafer was first degreased by immersing in trichloroethane, acetone and isopropyl alcohol for 10 min each and then it was rinsed in deionized (DI) water and blown dry with nitrogen. After cleaning, nichrome (NiCr) and gold films were sequentially deposited on the front surface of the wafer. This was done in a cryo-pumped electron-beam evaporator at a pressure of about 10^{-5} Pa without breaking vacuum between the NiCr and Au evaporations. The last step minimized contamination of the devices.

Two masks were prepared to define the nichrome and gold patterns. Using standard photolithography, the Au leads and contact patterns were formed in a photoresist layer. The residual gold was removed with a solution of $4\,\mathrm{g}\ KI : 1\,\mathrm{g}\ I_2 : 40\,\mathrm{mL}\ H_2O$. The $KI - I_2$ solution was chosen because it etches the gold film but not the NiCr. The photoresist was then removed using photoresist stripper and rinsed in DI water.

After cleaning and processing, the NiCr pattern was formed in the photoresist by aligning a suitable mask to the Au pattern on the wafer. The NiCr on the wafer was etched using a solution of $310\,\mathrm{g}\ (NH_4)_2Ce(NO_3)_6 : 1970\,\mathrm{mL}\ H_2O : 120\,\mathrm{mL}\ HNO_3$. With the completion of the front side patterning, a 200 nm thick NiCr film was evaporated onto the backside of the wafer. The wafer was then sliced into chips.

The two-electrode element, 3.8 mm × 3.8 mm × 0.2 mm in size, is shown in Fig. 3. The device was mounted on a ceramic carrier with one end of the heater connected to the NiCr common on the other side of the $LiTaO_3$ chip. The assembled unit was then inserted into a standard


Electrode
(Area A, Emissivity η)
Incident radiation
(Power W(t))
Polar axis element
d
CE
iP
RG
CA
RL
Vs
VD
0V
Thermal Conductance (G_T)

Pyroelectric Flow Sensors, Figure 2 Schematic diagram of a pyroelectric detector element


Eletrode
Heater
Eletrode
Eletrodes
Heater
Eletrodes
1
2
3'
2'
1'
1
2
3
IPFS
CPFS
RPFS
a
b
c
NiCr heater
Au pad
NiCr eletrode
LiTaO3

Pyroelectric Flow Sensors, Figure 3 Layer of (**a**) a two-electrode element pyroelectric flow sensor and (**b**) a six-electrode one and (**c**) the equivalent circuit of the pyroelectric electrode

1/4′ Union Tee. For completeness, the equivalent circuit of the pyroelectric flow sensors electrode is shown in Fig. 3. A schematic diagram of the measurement system is shown in Fig. 4. The basic component consists of a function generator that produces the heater current and a computer-controlled two-phase analog lock-in amplifier.

Other parts of the electronic measuring system consisted of a function generator to supply a sinusoidal driving voltage to the heater of the sensor, a buffer, a signal conditioner for the output from the sensor, a two-phase lock-amplifier and a computer. The signals from the two electrodes of the sensor are sent directly to a buffer. The buffer section transforms the high impedance of the sensor signal into a low-impedance signal, which is sent to a signal conditioner through a seven-line cable. Because of the extremely high resistance, R_{PA}, of the sensor chip, the loading by the electronics produces a voltage output signal across the input resistance of the buffer amplifier.

Key Research Findings

Modification of Pyroelectric Materials

As we know, there are many kinds of pyroelectric materials, but all of them have some advantages and disadvan-



Pyroelectric Flow Sensors, Figure 4 Diagram of the measurement system

tages. For example, as a perovskite-type pyroelectric compound desirable for pyroelectric infrared detectors because of its relatively large pyroelectric coefficient and spontaneous polarization, PT has poor mechanical properties due to its large tetragonal strain which makes poling of PT materials difficult. Much attention has been focused on the modification of PT by doping with the purpose of obtaining improved mechanical and electrical properties. The incorporation of off-valent (La^{3+}, Sm^{3+}, Nd^{3+}, Gd^{3+}) and isovalent ions (Ca^{2+}, Ba^{2+}, Sr^{2+}) into PT ceramics is reported to enhance the pyroelectric properties. Substitution of these ions results in the reduction of lattice anisotropy leading to hard and dense ceramics with high mechanical strength. From the standpoint of thermal responsivity, the performance of a pyroelectric detector is enhanced when it is in the form of a thin film. In recent device applications, it has become increasingly necessary to consider the improvement of these films in their performance in addition to the large component area and connection to many circuit elements. Recently, calcium- and lanthanum-doped lead titanate (PCT and PLT) thin films have been studied due to their possible use in optical waveguides, infrared sensors, dynamic random access memories and non-volatile memories. Thin-film optical devices are especially attractive because of their potential for monolithic integration. In addition, thin films offer the potential for increased speeds, reduced operating voltages and enhanced efficiency.

In order to improve mechanical properties for different applications, many pyroelectric polymer composites have been prepared, such as $BaTiO_3$–PVC composites, $(Bi_{0.5}Na_{0.5})_{0.94}Ba_{0.06}TiO_3$/P(VDF-TrFE), 65PMN-35PT/P(VDF-TrFE) and DTGS:PVDF.

Preparation of Thin Films

The use of bulk pyroelectrics in pyroelectric devices inevitably leads to a situation where the material must be cut, lapped and polished to make a thin, thermally sensitive layer. If an array of detectors is required for a thermal goal, this must be metallized on both faces, processed photolithographically and bonded to a silicon read-out circuit to yield a complete hybrid array. Clearly, it would be desirable if the material could be deposited as a thin film, to remove the requirement for lapping and polishing, if possible directly onto a complete wafer of chips, where it could be processed to yield an array of thin, thermally isolated structures. Fortunately, many techniques have been researched for pyroelectric thin-film deposition, mainly for applications to non-volatile memories. These include chemical solution deposition (CSD), metalorganic deposition (MOD), RF magnetron sputtering, pulsed laser ablation (PLD) and metalorganic chemical vapor deposition (MOCVD).

Pyroelectric flow sensors and chips

Pyroelectric sensors have recently been increasingly employed for sensing purposes. Excellent piezoelectric and pyroelectric properties of pyroelectric materials, combined with design flexibility and miniaturization offered by thin-film geometry and also developments in micro- and nanoscale fluids technologies have generated great interest in pyroelectric thin films. The multisensing chip utilizes the pyroelectric effect in the following sensing devices: gas-flow sensor infrared detector arrays, chemical reaction sensors and charge-coupled device imagers. A multipurpose integrated sensor chip that responds simultaneously to several different physical and chemical variables has been fabricated.

Also, multifunctional pyroelectric flow sensors have also appeared. As we know, any change in the temperature induces charges on the surface of the material, inducing an electric field, which generates transverse strain and bending deformation (see Fig. 3). A typical example is used for flow sensor and valving purposes.

Future Directions for Research

During recent years, the study of micro- and nanoscale fluids has shown significant opportunities for high detectivity of elementary devices with small size. For pyroelectric flow sensors, it is highly desirable to develop theoretical models, experimental methods for pyroelectric element preparation and sensor fabrication, and higher sensitivity with excellent mechanical properties.

Cross References

- ► Ferroelectric
- ► Pyroelectricity
- ► Piezoelectric Valves

References

1. Damjanovic D, Muralt P, Setter N (2001) Pyroelectric sensors. IEEE Sens J 1(3):191–206
2. Lee MH, Guo R, Bhalla AS (1998) Pyroelectric sensors. J Electroceramics 2(4):229–242
3. Whatmore RW (2004) Pyroelectric arrays: ceramics and thin films. J Electroceramics 13:139–147
4. Chang DH, Yoon YS (2002) Response analysis of multilayer pyroelectric structures. Integr Pyroelectrics 49:275–283
5. Hsieh HY, Zemel JN (1995) Pyroelectric anemometry: frequency, geometry and gas dependence. Sens Actuators A 49:133–140
6. Hsieh HY, Bau HH, Zemel JN (1995) Pyroelectric anemometry: theory of operation. Sens Actuators A 49:125–132
7. Hsieh HY, Spetz A, Zemel JN (1995) Pyroelectric anemometry: vector and swirl measurements. Sens Actuators A 49:141–147
8. Duggirala R, Son IS, Lal A (2003) A pyroelectric-piezoelectric valve for integrated microfluidics. Transducers'03, International Conference on Solid-State Sensors, Actuators and Microsystems, Digest of Technical Papers, 12th, Boston, MA, United States, 8–12 June, vol 2, pp 1554–1557
9. Goel M (2004) Recent developments in electroceramics: MEMS applications for energy and environment. Ceram Int 30:1147–1154
10. Chopra S, Sharma S, Goel TC, Chatterje R, Mendiratta RG (2006) Comparison of Ca-doped and La-doped PT films for pyroelectric sensors. Comput Mater Sci 37:134–140

Pyroelectricity

Definition

Describes the phenomenon of materials that generate an electric field across them due to a change in their temperature. All pyroelectric materials are piezoelectric.

Pyroelectric Sensors

► Pyroelectric Flow Sensors

PZT

► Piezoelectric Materials for Microfluidics

Q-Dots

► Semiconductor Nanoparticles

Quadrupole Filter

Synonyms

Electrostatic quadrupole; Quadrupole mass spectrometer

Definition

A mass filter that separates ions according to their trajectories in a two-dimensional hyperbolic electrostatic field with DC and radiofrequency AC components. Ions with stable trajectories transit the filter, while other ions discharge on the electrodes. Unlike a quadrupole ion trap, the quadrupole filter operates continuously.

Cross References

► Mass Spectrometry

Quadrupole Ion Trap

Synonyms

Ion trap mass spectrometer

Definition

A mass filter that separates ions according to their trajectories in a three-dimensional hyperbolic electrostatic field with DC and radiofrequency AC components. Unlike a quadrupole filter, the ion trap does not operate continuously, but on batches of ions that are trapped, stored and then detected in sequence.

Cross References

► Mass Spectrometry

Quadrupole Mass Spectrometer

► Quadrupole Filter

Quantum Box

► Quantum Dot

Quantum Dot

CHAN HEE CHON, DONGQING LI
Department of Mechanical Engineering, Vanderbilt University, Nashville, TN, USA
Chanhee.chon@vanderbilt.edu

Synonyms

Quantum box; Artificial atom

Definition

A quantum dot is a semiconductor nanoparticle that confines the motion of electrons and holes in three spatial directions.

Overview

Quantum confinement is defined as the space where the motions of electrons and holes in a semiconductor are restricted in one or more dimensions. This quantum confinement occurs when the size of semiconductor crystallites is smaller than the bulk exciton Bohr radius. Quantum wells, quantum wires, and quantum dots are confined in one, two, and three dimensions, respectively [1, 2]. The confinement can be created due to electrostatic potentials, the presence of an interface between different semiconductor materials, and the presence of a semiconductor surface. A valence band and a conduction band are separated by an energy range known as the band gap (E_g). These amounts



Quantum Dot, Figure 1 Schematics and image of quantum confinement and semiconductor size: (**a**) energy level of high-energy conduction band and low-energy valence band; (**b**) band gap energy increase by decreasing nanoparticle sizes; (**c**) quantum dots of cadmium sulfide in solution fluoresce brightly under ultraviolet light [3]

of energy will be absorbed in order to promote an electron from the valence band to the conduction band and emitted when the electron relaxes directly from the conduction band back to the valence band. By changing the size of the semiconductor nanoparticles the energy width of the band gap can be altered and the optical and electrical responses of these particles are changed (Fig. 1).

A quantum dot containing electrons can be compared to an atom because both have a discrete energy spectrum and bind a small number of electrons. However, a quantum dot different from an atom can be engineered by controlling the geometrical size and shape and the strength of the confinement potential [4].

A quantum dot confines more electrons and holes than those of the bulk semiconductor material. This causes a blue-shift of the interband absorption and a quantum dot of the same material can emit different color light depending on its size [5]. A smaller quantum dot emits shorter wavelength light (bluer) while a larger quantum dot emits longer (redder) wavelength light because of the band gap energy (E_g) levels (Fig. 1a), which determine the fluoresced light. This band gap energy is inversely proportional to the square of the size of the quantum dot. Consequently, a larger quantum dot has more energy and a closer energy band (Fig. 1b). This allows the quantum dot to absorb photons containing less energy, which is closer to red light (Fig. 1c).

The size of a quantum dot is important for the tunable light emission characteristic. A small quantum dot, such as a colloidal semiconductor nanocrystal, can be as small as 2 to 10 nm [6]. A self-assembled quantum dot is typically between 10 and 50 nm in size [7]. A quantum dot defined by lithographically patterned gate electrodes or by etching on two-dimensional electron gases in semiconductor heterostructures can have lateral dimensions exceeding 100 nm [8].

Quantum dots have many promising applications in diode lasers [9], QD-LED for computer displays [10], quantum computing [11], solar cells [12], and biological applications such as medical imaging and disease detection [13].

Cross References

- ► Evanescent Wave Microscopy
- ► Flow Cytometer Lab-on-Chip Devices
- ► Fluorescence Measurements
- ► Fluorescent Labeling
- ► Fluorescent Thermometry
- ► Nanoscale Flow Visualization
- ► Detection Using Confocal Microscope
- ► Detection Using Fluorescence Microscope
- ► Semiconductor Nanoparticles

References

1. Brus LE (1984) Electron–Electron and Electron–Hole Interactions in Small Semiconductor Crystallites: The Size Dependence of the Lowest Excited Electronic State. J Chem Phys 80:4403–4409
2. Norris DJ, Sacra A, Murray CB, Bawendi MG (1994) Measurement of the Size Dependent Hole Spectrum in CdSe Quantum Dots. Phys Rev Lett 72:2612–2615
3. Frankel F (2007) No Small Matter. http://www.nisenet.org/publicbeta/gallery/slideshow001/index.php. Accessed 26 Nov 2007
4. Shiraishi K, Tamura H, Takayanagi H (2001) Design of a Semiconductor Ferromagnet in a Quantum-Dot Artificial Crystal. Appl Phys Lett 78:3702–3704
5. Canham LT (1990) Silicon Quantum Wire Array Fabrication by Electrochemical and Chemical Dissolution of Wafers. Appl Phys Lett 57:1046–1048
6. Murray CB, Norris DJ, Bawendi MG (1993) Synthesis and Characterization of Nearly Monodisperse CdE (E = Sulfur, Selenium, Tellurium) Semiconductor Nanocrystallites. J Am Chem Soc 115:8706–8715
7. Petroff P, Lorke A, Imamoglu A (2001) Epitaxially Self-Assembled Quantum Dots. Phys Today 54:46–51
8. Scherer A, Craighead HG (1986) Fabrication of Small Laterally Patterned Multiple Quantum Wells. Appl Phys Lett 49:1284–1286
9. Zhukov AE et al (1999) Continuous-Wave Operation of Long-Wavelength Quantum-Dot Diode Laser on a GaAs Substrate. Photonics IEEE Tech Lett 11:1345–1347

10. Coe S, Woo WK, Bawendi M, Bulovic V (2002) Electroluminescence from single monolayers of nanocrystals in molecular organic devices. Nature 420:800–803
11. DiVincenzo DP (1995) Quantum Computation. Science 270:255–261
12. Schaller RD, Klimov VI (2004) High Efficiency Carrier Multiplication in PbSe Nanocrystals: Implications for Solar Energy Conversion. Phys Rev Lett 92:186601
13. Michalet X et al (2005) Quantum Dots for Live Cells, in Vivo Imaging, and Diagnostics. Science 307:538–544.

Quantum-Dot Quantum Well (QDQW Nanoparticles)

► Composite Nanoparticles

Quantum Efficiency

Synonyms

Fluorescence efficiency; Quantum yield

Definition

Quantum efficiency is a parameter that is used to quantify the efficiency of the fluorescence emission of a fluorescent dye. For a fluorophore that is excited to its first excited state, the quantum efficiency represents the fractional rate of emission of photons via fluorescence.

Cross References

► Fluorescent Thermometry
► Lab-on-a-Chip Device for Chemical Analysis

Quantum Yield

► Quantum Efficiency

Quartz

► Piezoelectric Materials for Microfluidics

Radiation Pressure

- ► Optofluidics: Optics Enabling Fluidics
- ► Transport of Droplets by Acoustics

Radical Polymerization

Definition

A type of polymerization in which the reactive center of a polymer chain consists of a radical.

Cross References

- ► Polymer Synthesis within Microfluidic Reactor

Radiofrequency (RF) Sputtering

Definition

Thin-film deposition technique which uses a radio frequency (e. g. 13.56 MHz) to create a plasma consisting of ions of a process gas (Ar in the case of this investigation). These ions are accelerated into a target material to remove atoms of the material, which are then deposited onto a substrate to form a thin film.

Cross References

- ► Fabrication of Self-Assembled Catalytic Nanostructures

Radius of Curvature

Definition

Radius of a theoretical circle (or sphere in three dimensions) that can fit a meniscus of interest. This radius is used to approximate the pressure drop associated to capillary flow.

Cross References

- ► Surface-Directed Capillary Flow Systems

Random Method

- ► Monte Carlo Method

Rarefaction Parameter

Definition

Rarefaction parameter is the ratio of a typical size of gas flow a to the equivalent mean free path ℓ, i. e. $\delta = a/\ell$.

Cross References

- ► Gas Flow in Nanochannels
- ► Heat Transfer in Microchannel Flows
- ► Supersonic Micro-Nozzles
- ► Micro- and Nanoscale Gas Dynamics

Rarefied Flow

Definition

Conditions under which the characteristic length scale for a flow approaches the mean free path of the gas molecules; this flow regime bridges the continuum regime and the gas kinetics regime.

Rarefied Gas Dynamics

Definition

Rarefied Gas Dynamics is a scientific field which aims at describing gas flows on the basis of the kinetic Boltzmann equation considering the whole range of the gas rarefaction covering the free molecular, transitional and hydrodynamic regimes.

Cross References

- ► Gas Flow in Nanochannels
- ► Heat Transfer in Microchannel Flows
- ► Supersonic Micro-Nozzles
- ► Micro- and Nanoscale Gas Dynamics
- ► Lattice Poisson-Boltzmann Method, Analysis of Electroosmotic Microfluidics

Rayleigh Flow

Definition

An idealized steady, I-D compressible duct flow in which heat transfer may occur. The flow is regarded as frictionless and perfect gas behavior with constant specific heat is assumed.

Cross References

- ► Supersonic Micro-Nozzles

Rayleigh Instability

Definition

Taking a force balance between the surface tension along the surface of a fluid and the normal stresses across it, the Rayleigh instability will describe the tendency of a fluid stream to break up into droplets. It is not the same as the Rayleigh-Taylor instability, and not to be confused with Kevin-Helmholtz instabilities.

Cross References

- ► Piezoelectric Microdispenser
- ► Kelvin–Helmholtz Instability
- ► Rayleigh–Taylor Instability
- ► Jetting
- ► Free-Surface Atomization

Rayleigh–Taylor Instability

Definition

Describes the formation of irregularities along an interface, typically fluid-fluid, as it is accelerated in a direction perpendicular to the interface. The phenomenon occurs in microfluidics in the atomization of sessile droplets. It is not the same as the Rayleigh instability (► Rayleigh–Taylor instability), and should not be confused with the ► Kevin–Hemholtz instability.

Cross References

- ► Piezoelectric Microdispenser

Reacting Electrokinetic Flow

- ► Electrokinetic Transport with Biochemical Reactions

Reaction Condition Control

Synonyms

Temperature control; Concentration control; Reaction time control

Definition

Controlling reaction conditions such as temperature, concentration of chemicals, and reaction time. To obtain well defined products, it is often necessary to control these reaction conditions precisely and uniformly.

Reaction Time Control

- ► Reaction Condition Control

Reactive Ion Etching (RIE)

SAMI FRANSSILA, LAURI SAINIEMI
Helsinki University of Technology, Helsinki, Finland
sami.franssila@tkk.fi, lauri.sainiemi@tkk.fi

Definition

Reactive ion etching (RIE) is a plasma process where radiofrequency (RF) discharge-excited species (radicals, ions) etch substrate or thin films in a low-pressure chamber. RIE is a synergistic process between chemically active species and energetic ion bombardment. RIE is faster than either pure physical ion bombardment or spontaneous chemical etching. Because ion bombardment is directional, RIE has anisotropic character, with reduced lateral etch rate and vertical (or nearly vertical) sidewalls. RIE is essential when narrow lines or channels are needed, or when high aspect ratio structures need to be fabricated. RIE of silicon is independent of crystal planes, and therefore any shape can be fabricated, unlike anisotropic wet etching. Deep reactive ion etching (DRIE) is an extension of RIE that enables high-rate etching of deep structures.

Overview

Etching has traditionally been divided into wet and dry etching, according to etchant phase. In the case of wet etching, the etch reaction results in soluble products; in the case of dry etching, in volatile etch products:

Solid + gaseous etchant → volatile products

$\mathrm{Si(s)} + 2\mathrm{XeF_2(g)} \rightarrow \mathrm{SiF_4(g)} + 2\mathrm{Xe(g)}$

$\mathrm{W(s)} + \mathrm{SF_6(g)} + \mathrm{O_2(g)} \rightarrow \mathrm{WF_6(g)} + \mathrm{SO_2(g)}$

Etch gases are thus selected on product volatility considerations. Halogens F, Cl and Br are the most widely used etch species, coming from SF_6, CF_4, CHF_3, C_4F_8, Cl_2, BCl_3, $SiCl_4$, HBr. Typical etch products include SiF_4, $SiCl_4$, NF_3, WF_6, $AlCl_3$ [1–3]. Non-volatile etch products like AlF_3 or $CuCl_2$ cause problems in the form of residues, micromasking, roughness and non-uniformity.

Other gases used in RIE include oxygen, hydrogen, argon, helium and nitrogen. These have roles in modifying plasma chemistry and physics, heat transfer and surface chemistry. Oxyhalides typically form WO_xF_y type etch products, and CO_2 and H_2O are generated as photoresist mask is etched.

Additive gases are also important for anisotropy mechanism: for instance deposition of SiO_xF_y film is essential for sidewall passivation in silicon etching in SF_6/O_2 plasmas. Similarly, CHF_3 and C_4F_8 etch gases lead to deposition of $(CF_2)_n$ type fluoropolymer films, which passivate sidewalls and minimize lateral etching. Etch rate and anisotropy are manifestations of balancing properly etching and deposition reactions.



Reactive Ion Etching (RIE), Figure 1 RIE etched sidewall profiles (from left to right): vertical (SEM and schematic); positively sloped; negatively sloped (retrograde); bowing (barrelling); isotropic



Reactive Ion Etching (RIE), Figure 2 Bottom of etched structures: trenching; faceting; spearheading, rounding; notching (footing) at insulator interface

Etched profiles are depicted in Fig. 1. Perfectly vertical walls are possible, but both positively and negatively sloped and bowing and isotropic profiles can be found. The bottoms of reactive ion etched structures exhibit similarly a wide variety of shapes (Fig. 2): trenching, faceting, spearheading and rounding. At insulator etch stop layers notching (footing) effects can take place.

Ion beam etching (IBE; also known as ion milling) relies on energetic (argon) ions and differs thus from RIE. Chemically active species are absent in ion beam etching, and etch product volatility is not an issue. IBE rates are very low compared to RIE, only 20 – 100 nm/min. Reactive ion beam etching (RIBE) uses reactive ions, e. g. fluorine or chlorine, but the etching mechanism is dominated by physical bombardment at low pressures.

The term dry etching is sometimes used as a synonym for RIE, but there are also processes which are dry etching without ions or plasmas. The XeF_2 example cited above is a case of spontaneous chemical reaction that proceeds without plasma activation.

Basic Methodology

For many materials there is the choice of both wet and RIE processes. Silicon, silicon dioxide, aluminum, tungsten (and other refractory metals) and glass/quartz can be etched by either method. Silicon and its compounds can be etched in both fluorine or chlorine plasmas, with SiF_4 or $SiCl_4$ as the main reaction products, but because of tighter safety requirements chlorine gas is less popular [4]. In integrated circuit fabrication Cl_2 (and HBr) source gases are used routinely in silicon etching because they offer better anisotropy and higher oxide selectivity than fluorine gases. DRIE of silicon using Cl_2 gas is limited because the etch rate is very slow compared with that of fluorine gases, even by a factor of ten. Another drawback is the need for thick metallic masks (e. g. several micrometers thick electroplated nickel). The advantages of Cl_2 plasmas are in smaller RIE lag (see below) and smaller mask undercut.

Silicon nitride is etched in CF_4- or SF_6-based plasmas. The process is fairly straightforward and the main considerations are the etch rate ratios (selectivities) needed. It is impossible to achieve selectivity against silicon in CF_4 and SF_6 plasmas, but nitride-to-oxide selectivity is ca. 2:1 to 10:1. If selectivity between nitride and silicon is needed, plasmas based on CHF_3, C_2F_6 or C_4F_8 are employed. Nitride-to-silicon selectivities can be in the range 5:1 to 50:1. Oxide etching is carried out with these same plasmas. Nitride etch rate is roughly half of oxide etch rate in the same plasma.

Diamond, silicon carbide, titanium carbide and gallium nitride are materials that do not have wet etch processes, but RIE processes do exist. For some materials neither RIE nor wet processes exist and then IBE can be used to pattern them, or else molding or deposition together with polishing can be used for patterning. Platinum and gold (and other noble metals) can be wet and dry etched, but both processes are difficult since the aggressive etch conditions are damaging the resist mask. These materials are often patterned by lift-off rather than by etching.

Releasing structures by isotropic undercut etching in wet solutions is prone to stiction when capillary force exceeds the mechanical spring force of a cantilever, beam or a plate, leading to contact. Dry release techniques avoid stiction by avoiding liquid-phase processing. Dry release methods include vapor etching (HF; oxide sacrificial layer), plasmaless dry etching (XeF_2; silicon sacrificial layer) and isotropic plasmas (SF_6; silicon sacrificial layer).

In RIE the details of thin-film structure or doping can usually be neglected and for instance PECVD nitride and LPCVD nitride are etched at roughly the same rate, and in silicon etching no doping dependence needs to be accounted for.

Equipment

RIE equipment is usually parallel plate reactors in which both plasma and DC bias voltage are created using one capacitively coupled plasma (CCP) source [5]. The wafers are placed on top of the electrode which is typically in direct contact with plasma glow (Fig. 3). This ensures a reasonable etch rate but the controllability of etching is difficult. A major downside of this type of reactor is that the wafers are exposed to heavy ion bombardment because plasma generation and bias voltage are coupled. The etch rate of silicon is typically 0.1 – 1 μm/min and selectivity against the photoresist mask is usually below 5:1. Anisotropy is based on the directionality of ion bombardment and aspect ratios are usually limited to 2:1.

The difference between RIE and DRIE is not unambiguously defined. The division can be made according to etch rate, selectivity, aspect ratio capability or reactor type. DRIE reactors are typically equipped with two RF power generators instead of one (Fig. 3). An inductively coupled plasma (ICP) source generates plasma that has 1 – 2 orders of magnitude higher plasma density than RIE, which roughly translates to 1 – 2 orders of magnitude higher etch rate. In DRIE reactors the wafer is clamped on the bottom electrode of the CCP power source, which is not in direct contact with the plasma. Bias voltage is controlled separately by the second capacitively coupled source. This arrangement allows low bias voltages and therefore much higher selectivities can be achieved. In DRIE selectivity of photoresist mask is 10:1 to 100:1 vs. 1:1 to 10:1 in RIE.

The parameters available for process optimization include:

- etch gas selection
- RF power (coil power in ICP)
- bias voltage (CCP power in ICP)
- pressure
- flow rate
- temperature

The key process outcomes of a (D)RIE process are:

- etch rate
- anisotropy/sidewall angle
- mask selectivity
- substrate selectivity
- etched surface quality
- throughput

A rough order of magnitude estimate of etch rates is as follows: 100 nm/min for simple research reactors; 1 μm/min for production tools and 10 – 50 μm/min for silicon DRIE reactors. Exact values depend on particular reactor design, RF power source and other hardware factors. Silicon etch rate is much faster than oxide or polymer etch rate in the same reactor. More extensive passivation translates to reduced etch rate but also reduced undercut and more vertical sidewalls.

In most DRIE processes aspect ratios of 20:1 can be quite easily achieved. Directionality of ion bombardment is also better in DRIE reactors because wafers are not in direct contact with plasma and process pressure is also lower (typically 10 – 50 mTorr in DRIE). Low process pressure creates high requirements for vacuum pumps because, in order to achieve high etch rates, high gas flows are essential. Temperature of the wafer can be controlled between −150 and +450 °C. Systems with wafer cooling can utilize higher RF power to increase etch rate while keeping photoresist erosion to a minimum.



Reactive Ion Etching (RIE), Figure 3 Capacitively coupled RIE reactor (left); inductively coupled DRIE reactor (right)



Reactive Ion Etching (RIE), Figure 4 Micromasking from aluminum mask

Mask Selection (Selectivity, Mask Material Effects, Removal)

Photoresist is used as a mask practically whenever it is possible because it is the fastest and the simplest way to create patterns. However, its fairly low selectivity in RIE limits the etch depth. Both elevated and cryogenic temperatures are detrimental to photoresists. During conventional RIE process temperature of the wafer increases because of the heavy ion bombardment and photoresist may burn. At cryogenic temperatures photoresists suffer from cracking.

When high selectivity or wider temperature range is needed hard masks such as silicon dioxide, metals and metal oxides are utilized. The most obvious downside of the hard masks is the increase in process complexity. Deposition of the hard mask material might include high-temperature processes and the non-idealities in hard mask etching process degrade the quality of final structures. The most common hard mask material is silicon dioxide (SiO_2). In conventional RIE silicon to oxide selectivity is 10:1 to 100:1 and in DRIE 100:1 and higher. Metals and metal oxides have usually higher selectivities than SiO_2, but they may create new problems, like generation of microroughness (Fig. 4).

In order to avoid photoresist deposition over severe topography, a peeling mask (nested mask) can be used: two mask patterns are fabricated on a starting surface, using a suitable combination of mask materials, e. g. oxide-resist or oxide-nitride. After the first DRIE step, one of the mask materials is selectively removed (oxygen plasma ashing of resist mask; or HF etching of oxide mask), exposing more etchable area, while the non-etchable mask still protects selected areas. The second DRIE step etches both newly opened area and continues deeper in the original areas (Fig. 5).

Hard masks can be patterned by both wet and dry etching, and in the first approximation they are identical. However, if accurate dimensional control is required and hard mask etch selectivity is not very high, the etch profile of a wet etched hard mask can influence the size and shape of the feature. The thin wedges resulting from wet etching are quickly eroded by plasma, and the edge of the hard mask recedes, widening the trench (or narrowing a ridge). With vertical walled plasma etched hard masks this is not an issue. Redeposition of etched material on the mask sidewalls can lead to dimensional changes, however (Fig. 6).

Key Research Findings

Silicon DRIE

By far the two most popular DRIE techniques are the Bosch [6] and cryogenic processes [7].

Bosch Process

The Bosch process was developed and patented by Franz Lärmer and Andrea Schilp in 1994. Because of



Reactive Ion Etching (RIE), Figure 5 Nested (peeling) mask: (**a**) mask layers patterned; (**b**) after first RIE step; (**c**) after peeling the top mask and second RIE step. Bottom mask, e. g. SiO_2; top mask, resist



Reactive Ion Etching (RIE), Figure 6 Non-idealities in width control (left to right): redeposition on mask; bowing at trench top; hard mask erosion and trench widening

the nature of the process it is also frequently called the *switched process* and *time domain multiplexed process*. The principle of the Bosch process is shown in Fig. 7. It is based on alternating etch and passivation steps. The etching gas is sulphur hexafluoride (SF_6) that creates fluorine radicals in high-density plasma. After the etch step a thin fluorocarbon film is deposited from cyclic octofluorocyclobutane (c-C_4F_8). This film passivates the surface and prevents etching. At the beginning of the next etch step the fluorocarbon film is removed from horizontal surfaces but sidewalls remain passivated. The SF_6 etch step is not fully anisotropic but the polymer is etched preferentially from the horizontal surfaces due to ion bombardment and the sidewalls remain protected. The repetition of etching and passivation steps results in vertical sidewalls. The microstructure of the etched sidewall, however, shows scalloping (undulation) because of the pulsed nature of the process [8]. The etching and passivation pulse times are typically 5 – 15 s. Etch rate, anisotropy, selectivity and scalloping (sidewall undulation) are all influenced by the duration and overlap of the etch and passivation pulses.

Cryogenic Process

Cryogenic RIE etching was first introduced in 1988 [9]. It was noticed that by cooling the wafer during the RIE the rate of chemical reactions on the sidewalls could be reduced dramatically, leading to improved anisotropy. Selectivity between silicon and masking material is also improved at cryogenic temperatures. The reason for reduced chemical reactions on sidewalls is the silicon oxyfluoride (SiO_xF_y) layer that forms during cryogenic etching process in SF_6/O_2 plasma [10]. Fluorine has very low adsorption coefficient to passivating SiO_xF_y wich therefore inhibits lateral etching. Etching can proceed downwards because ion bombardment removes the passivating layer from horizontal surfaces. Cryo-etched pillars and holes are shown in Fig. 8. Low temperature also reduces spontaneous reactions of free radicals according to the Arrhenius rate law, which also improves anisotropy. Still, the main reason for enhanced anisotropy is the passivating SiO_xF_y layer.

High etch rate in SF_6/O_2 plasma is due to high concentration of fluorine radicals. Oxygen controls the quality of the passivating layer. It is the most important parameter when optimizing the sidewall tapers. If the O_2 content is too low, an isotropic profile results. Too high an oxygen flow leads to overpassivation and formation of so-called black silicon which consists of silicon micrograss.

DRIE Reactor Requirements

The Bosch and cryogenic processes utilize similar DRIE reactors but both processes have their own special requirements [11]. The Switched nature of Bosch-process calls for high speed mass flow controllers, or fast acting valves and buffer tanks. Short step times also necessitate gas line design to minimize delays. In order to reduce the polymer deposition on the chamber walls and pumping lines they should be heated as deposition of fluorocarbon polymer to unwanted surfaces creates particle contamination. In the Bosch process the ratio between the ions and free radicals is important. If relative ion concentration is too high the profile control is lost. By placing the wafer far enough from the plasma glow it is possible to create sufficient ratio



Reactive Ion Etching (RIE), Figure 7 (**a**) Bosch process schematic: repetition of etch and deposit pulses. SEM images of etched structures: (**b**) scalloping of the sidewall; (**c**) perfectly vertical profile

of free radical to ions because of short decay time of ions. Without an ICP source it is impossible to create adequate ratio of free radicals to ions.

In the cryogenic process the temperature of the wafer plays an important role. Accurate wafer temperature control during the process is also essential because the wafer temperature directly affects etch profiles. Cryogenic cooling of the wafer stage is done using liquid nitrogen. The wafer is mechanically or electrostatically clamped on the cooled stage and helium pressure is applied on the backside of the wafer. Because of the high thermal conductivity of the helium, heat transfer from the stage to the wafer is improved. Clamping must be tight to prevent helium leaks to the chamber. Leaks compromise not only the temperature control of the wafer, but also the plasma conditions. In principle a cryogenic process can be operated using a CCP source only, but the etch rate and the selectivity would be considerably lower.

DRIE Special Features

The benefits of the Bosch process are its accurate profile control in high aspect ratio structures and its high etch rate [12]. Etch rates up to 50 μm/min have been reported in special cases, with 10 – 20 μm/min to be considered as more typical production etch rates.

The Bosch process results in scalloping sidewalls due to the pulsed process. This limits its applications in optics, and some fluidic devices are also sensitive to sidewall roughness. The amplitude of scalloping can be minimized by shortening the pulse lengths, and this minimizes the amplitude as well, and 20 nm can be obtained. However, etch rate will be sacrificed. Scallops can also be treated after etching by thermal oxidation or wet etch smoothing.

A notching effect (or footing effect) [13] is seen when high-density plasma etching reaches an insulator surface, e. g. SOI buried oxide or oxide on the backside of the wafer in through-wafer etching (Fig. 2). Charging of the interface leads to ion deflection and ion-enhanced sideways etching at the insulator–silicon interface. This can be minimized by running the end point step in RIE mode (low-density plasma) as opposed to high-density plasma mode, and minimized by having only a single feature size which minimizes overetch time. Reactor design can also help: pulsed CCP power, or low frequency (kHz) power give the electrode time to discharge, thus minimizing the notching effect, but unfortunately affecting sidewall quality. Notching has also been utilized as a release step: joining of two lateral etch fronts acts as a dry release method without the isotropic character of SF_6 plasma release.

With the cryogenic process, sidewalls of the etched structures are smooth, but the etch rate of silicon is some-



a

b

Reactive Ion Etching (RIE), Figure 8 Cryo-DRIE etched pillars and holes

what lower than in the Bosch process. Because the thickness of the passivation layer is only ca. 10 nm little ion bombardment is needed to remove it from horizontal surfaces. Therefore applied bias voltage can be very low and extremely high selectivities can be reached. A downside of the cryogenic temperature is that not all photoresists can stand it: they shatter like glass. Thick photoresists are especially prone to cracking. Therefore hard masks such as silicon dioxide must often be employed. Another characteristic feature of the cryogenic process is the possibility to create crystallographic-dependent etch results. Crystallographic dependence appears only at the bottom of the trench (Fig. 2) and it is possible only when using extremely low temperatures and low RF powers.

DRIE Processes for Other Materials

Glasses can be etched by SF_6, CHF_3 or C_4F_8 gases in DRIE but the process is more difficult than with silicon [14]. Silicon–oxygen bonds are stronger than silicon–silicon bonds, and higher power is needed to etch glass with DRIE. Fused silica which is pure SiO_2 can be etched more easily than Pyrex glass which has metal oxides. Increased ion bombardment (and thus power) is needed to prevent residues from metal oxides. This high power leads to problems with masking layers. For shallow etching thin silicon films (PECVD, LPCVD) are suitable as etch masks, but for deep etching thick (electroplated) metals, silicon wafers or thick photoresists (SU-8) must be used. Selectivities of 10 : 1 are typical for both metal and silicon masks.

Etch rates of Pyrex are typically in the range 1 µm/min, which is considerably lower than that of silicon. Aspect ratios of 10 : 1 are demanding, and sidewall angle is positively tapered because of extensive mask erosion. Even though 88° sidewall angles have been reported, 80° is more typical, and the sidewall angle is more feature size (anodically bonded or shadow masks) dependent than in the case of silicon DRIE. Increasing sidewall roughness is an additional factor limiting higher etch rates.

Polymers can be etched by oxygen plasmas using silicon, metal and oxide masks. Etch rates of a few µm/min have been demonstrated with 20 : 1 aspect ratios. A Bosch process for polymer etching involves an O_2 etch step followed by a C_4F_8 passivation step.

SiC is typically etched in high-density SF_6 plasma that results in etch rate of ~ 300 nm/min. A benefit of low reactivity of SiC is that no sidewall passivation is needed to enhance anisotropy. A downside is that heavy ion bombardment (platen power 50 – 100 W) enhances also mask material etch rate and selectivity becomes a problem. Therefore hard masks such as nickel, indium tin oxide and aluminm are used in SiC etching. Because of sputtering and redeposition of mask material etched surfaces are often rough.

(D)RIE Process Limitations and Problems

Practical (D)RIE processes exhibit a number of limitations regarding etch rate, etchable area, feature size and shape, all of which become more prominent for high aspect ratio structures. Also the sidewall profile non-idealities are discussed.

Loading effect [15] refers to etch rate dependence on etchable area. Loading effect has its roots in reactant supply and consumption balance. When etchable area is small, etch gas flow can supply enough reactive specie,



Reactive Ion Etching (RIE), Figure 9 RIE lag: etched depth depends on feature size



Reactive Ion Etching (RIE), Figure 10 Elimination of RIE lag: DRIE of single sized mosaic subpatterns combined with sidewall removal by TMAH wet etching

but with higher etchable area a deficiency of reactants may develop. Higher gas flow will compensate this but it may be undesirable to increase flow rate for other reasons. Loading phenomenon exhibits itself in various ways: in batch reactors rate depends on the number of wafers in the reactor; in a single-wafer reactor it depends on chip design. On the microscale loading manifests itself between dense and isolated structures. Etchable area also influences etch uniformity: for the Bosch process 1.5% uniformity over a 150 mm wafer has been reported, at 20% loading, with deterioration for higher loads, especially at the edges.

RIE lag refers to the common observation that smaller features are shallower than larger features (Fig. 9). This effect manifests itself in high aspect ratio (> 1:1) structures only. Aspect ratio-dependent etching (ARDE) is a similar but not identical effect: etch rate decelerates for longer etching times (i. e. when aspect ratios increase). ARDE occurs for all line widths, and many different etch times are needed to check it, while RIE lag can be seen from one wafer. Reactions (both etching and deposition) are affected as gas transport and ion bombardment change in high aspect ratio structures. At very high aspect ratios, etching of passivation layers also changes.

Combination of RIE lag and wet etching of sidewalls can be utilized either to eliminate RIE lag or to create multidepth microstructures in a single etch step [17]. This necessitates that the larger patterns are redrawn on the mask as a mosaic of smaller structures. If all mosaic elements are the same size, RIE lag is eliminated (Fig. 10); if they are different in size, multiple etched depths are obtained.

The shape of the etchable feature affects etch rate [18]. Holes of 5 μm diameter are etched more slowly than trenches 5 μm wide. This is again related to reactant transport inside the microstructures. Making narrow structures side-by-side with large features, e. g. a pillar filter and a liquid reservoir, or sniffer holes in a microreactor, results in larger areas being deeper than the small ones.

(D)RIE Applications in Microfluidics

In this section RIE applications in fluidics are discussed. Especially, benefits and drawbacks of silicon DRIE processes are highlighted, and special capabilities of DRIE emphasized.

Silicon DRIE is independent of silicon crystal structure, and this enables fabrication of all possible shapes, in contrast to wet chemical anisotropic etching which is limited by silicon crystal planes. In microfluidics this shape freedom has implications for flow profiles, as significantly channel cross-sections can be kept constant on turns, or widened or narrowed. Various microreactors, separation systems, mixers, fuel atomizers and micropower combustion systems make use of meandering, radial or spiralling channels enabled by DRIE. Constrictions of various sorts, converging–diverging structures are essential for example in microthrusters, capillary valves and nozzle-diffuser micropumps. They can be etched easily by DRIE. All sorts of nozzles, emitters and orifices can be optimized for performance when DRIE is used, while wet etched structures are limited in shape. Filters with narrow pass gaps can be made by DRIE (also by bonding and sacrificial layer techniques) but not by wet etching.

DRIE is essential in fabrication of small features. DRIE is capable of reproducing accurately practically any features that have been defined by lithography. Fluid dynamics studies of microflows utilize DRIE for making accurately dimensioned microchannels and orifices. Membrane structures with small holes are useful in many drug delivery, fuel cell and cell probing applications. In a patch clamp application submicrometre apertures have been etched in 20 μm thick silicon membrane. In catalysis studies a small DRIE fabricated capillary leak into a mass spectrometer enabled increased sensitivity and fast response times. Integration of microreactor and mass spectrometer also minimized dead volumes.

DRIE enables high aspect ratio structures. Holes, trenches and pillars with 10:1 to 20:1 aspect ratios can be fabricated, and experimental structures with 40:1 and even higher have been demonstrated. These high aspect ratio structures are limited by RIE lag, however. Applications for high aspect ratio structures include various trapping devices. Depending on feature size, either micro- or nanobeads are trapped, or macromolecules like DNA. For pillars, aspect ratios in excess of 50:1 have been demonstrated: 300 nm feature size, 15 μm structure height.

Random nanopillars can also be utilized in chemical microsystems. Intensity of desorption/ionization on silicon mass spectrometry (DIOS-MS) is dependent on surface area. At first DIOS plate material was porous silicon, but it has been shown that using nanopillars instead of porous silicon, signal intensity can be increased.

Combining DRIE and anisotropic wet etching can produce unique structures. For example, ⟨111⟩ silicon cannot be etched by the standard KOH, TMAH or EDP etchants, but if an initial trench has been etched by DRIE, fast etching crystal planes are exposed, and wet etching can proceed. If this is combined with spacer structures to protect sidewalls and another DRIE step, ⟨111⟩ free-standing silicon structures can be made.

Combination of DRIE and isotropic plasma etching can be used to create channels inside silicon. After the DRIE step, a sidewall passivation step is performed, and etching is then continued with an isotropic etchant. Anisotropic SF_6/O_2 DRIE recipe can quite easily be tailored to be isotropic by for example raising the pressure and eliminating the oxygen. Similarly, isotropic SF_6 plasma release etch can be used to fabricate free-standing silicon structures.

DRIE in combination with electrochemical etching of silicon enhances shape freedom in electrochemical etching. If anisotropic wet etching is used to create the initial pits for electrochemical etching, the usual limitations of crystal plane dependence manifests itself, while by using DRIE complex shapes like circular or curving can be made.

DRIE of silicon is a major method for making masters for polydimethylsiloxane (PDMS) casting and hot embossing. Alternative techniques include silicon wet etching and SU-8 thick photoresist. Silicon offers more durable material properties, but the master fabrication is more tedious. DRIE excels over wet etching because of shape freedom and sidewall profile engineering possibilities, but suffers from inferior surface quality. DRIE process has to be optimized for slightly positively sloping sidewall profile in order to facilitate de-embossing/release. The quality of optimized silicon masters is good, as applications in optofluidic chips demonstrate: PDMS fluidics and optics can be replicated from silicon masters with excellent performance [19].

An DRIE reactor can be used as a CVD-like deposition tool by changing process parameters and gases [20]. An important example is the deposition of $(CF_2)_n$ from CHF_3 or C_4F_8 source gases. This is the basis of anisotropy in the Bosch process but such films have been used in their own right in microfluidics to render surfaces hydrophobic. Patterning on these films can be done by oxygen plasma with standard photoresist masking and acetone resist stripping as Teflon-like films are chemically very tolerant. Alternatively, lift-off techniques or shadow mask techniques with oxygen plasma can be used.

Future Directions for Research

RIE and DRIE are workhorses of micromachining, and they are being applied to an increasing variety of structures. In developing (D)RIE processes, a number of issues have to be dealt with simultaneously: etch rate, mask etch rate, sidewall angle and profile, the various process limitations and process integration issues. There is a need for more robust processes that are insensitive to design changes, and allow small and large areas to be etched with the same rate, sidewall angle and surface roughness. Through-wafer etching still poses challenges, both as regards rate and aspect ratio and process integration. Very high aspect ratio structures still need design-specific optimization. The same challenges apply to other materials even more than to silicon.

Cross References

- ► Fabrication of 3D Microfluidic Structures
- ► Bulk Micromachining
- ► Silicon Micromachining
- ► Laser Based Micromachining
- ► Plasma Etching

References

1. Williams KR, Muller RS (1996) Etch rates for micromachining processes. J MEMS 5:256–269
2. Williams KR, Gupta K, Wasilik M (2003) Etch rates for micromachining processes – Part II. J MEMS 12:761–778

3. Franssila S (2004) Introduction to Microfabrication. Wiley, Chichester
4. Tian WC, Weigold JW, Pang SW (2000) Comparison of Cl_2 and F-based dry etching for high aspect ratio Si microstructures etched with an inductively coupled plasma source. J Vac Sci Tech B18:1890
5. Elwenspoek M, Jansen H (1998) Silicon micromachining. Cambridge University Press, Cambridge
6. Lärmer F, Urban A (2003) Challenges, developments and applications of deep silicon reactive ion etching. Microelectronic Eng 67–68:349
7. Murakami K, Wakabayashi Y, Minami K, Esashi M (1993) Cryogenic dry etching for high aspect ratio microstructures. Proc IEEE Microelectromech Syst Conf, Fort Lauderdale, Feb 1993
8. Ayon A et al (1999) Characterization of a time multiplexed inductively coupled plasma etcher. J Electrochem Soc 146:339
9. Tachi S, Kazunori K, Okudaira S (1988) Low-temperature reactive ion etching and microwave plasma etching of silicon. Appl Phys Lett 52:616
10. de Boer MJ, Gardeniers JGE, Jansen HV, Smulders E, Gilde MJ, Roelofs G, Sasserath JN, Elwenspoek M (2002) Guidelines for etching silicon MEMS structures using fluorine high-density plasmas at cryogenic temperatures. J MEMS 11(4):385–401
11. Walker MJ (2001) Comparison of Bosch and cryogenic processes for patterning high aspect ratio features in silicon. Proc SPIE 4407:89–99
12. Marty F et al (2005) Advanced etching of silicon based on deep reactive ion etching for silicon high aspect ratio microstructures and three-dimensional micro- and nanostructures. Microelectronics J 36:673–677
13. Hwang GS, Giapis KP (1997) On the origin of the notching effect during etching in uniform high density plasmas. J Vac Sci Technol B15:70
14. Akashi T, Yoshimura Y (2006) Deep reactive ion etching of borosilicate glass using an anodically bonded silicon wafer as an etch mask. J Micromech Microeng 16:1051
15. Mogab CJ (1977) The loading effect in plasma etching. J Electrochem Soc 124:1262
16. Gottscho RA et al (1992) Microscopic uniformity in plasma etching. J Vac Sci Tech B10:2133–2147
17. Kiihamäki J, Kattelus H, Karttunen J, Franssila S (2000) Depth and profile control in plasma etched MEMS structures. Sens Actuators 82:234–238
18. Kiihamäki J, Franssila S (1999) Pattern shape effects and artefacts in deep silicon etching. J Vac Sci Technol A17:2280
19. Seo J, Lee LP (2004) Disposable integrated microfluidics with self-aligned planar microlenses. Sens Actuators B99:615–622
20. Andersson H, van der Wijngaart HW, Griss P, Niklaus F, Stemme G (2001) Hydrophobic valves of plasma deposited octafluorobutane in DRIE channels. Sens Actuators B75:136–141

Reflective Index

Definition

Materials with a high reflective index reflect a huge amount of the striking light. They appear glittery.

Regular Least Square

► Least Square

Relative Roughness

Definition

Ratio of roughness to the channel hydraulic diameter.

Relaxation

► Viscoelasticity

Relaxation Time of the Viscoelastic Fluid

Definition

Relaxation time is the characteristic time in which a system relaxes under certain changes in external conditions. Here, it refers to the characteristic time required for the polymer coil to relax from a deformed state to its equilibrium configuration. It is a key parameter for characterizing a viscoelastic fluid.

Cross References

- ► Turbulence in Microchannels
- ► Viscoelasticity
- ► Non-Newtonian Fluids in Microchannel
- ► Non-Newtonian Fluids in Microfluidics

Relaxor Ferroelectrics

Definition

A specific type of electrostrictive material with large electrostrictive coupling coefficients, and important for applications that require high relative permittivities (i. e., supercapacitors) of 20,000 – 35,000, and actuator applications in particular. Single crystal PMN-PT is a popular composition in this class of material.

Cross References

- ► Electrostrictive

Replica Molding

► Micromolding

Reptation Tube

Definition

A model of the steric constraints provided by a gel during DNA electrophoresis. The DNA is assumed to move by curvilinear motion along the tube axis.

Cross References

► Electrophoresis

Residual Stress

Definition

Residual stresses are stresses that remain after the original cause of the stresses (external forces, heat gradient) has been removed. Residual stresses occur for a variety of reasons, including inelastic deformations and heat treatment.

Resistance Temperature Detectors

Chris Dames
Department of Mechanical Engineering, University of California, Riverside, CA, USA
cdames@engr.ucr.edu

Synonyms

RTD; Platinum resistance thermometer; PRT; SPRT; IPRT

Definition

A resistance temperature detector (*RTD*) is a device to measure temperature by relating it to changes in the electrical resistance of a metallic sensing element. The resistance of a typical RTD increases by about 0.3% to 0.4% of its room temperature value for every degree Kelvin of temperature increase. With care, RTDs can achieve accuracies of better than 0.1 K at temperatures ranging from about 14 K to over 900 °C.

Overview

Resistance temperature detectors (*RTD*s) are widely used for general purpose temperature measurements as well as high-accuracy metrology and research applications such as MEMS and microfluidics[1–6]. The key concept is the fact that the electrical resistance of a pure metal increases almost linearly with temperature over a broad range of temperature. The underlying physical reason for the temperature dependence is the scattering of electrons by lattice vibrations (phonons), which vibrate with larger amplitudes at higher temperatures. For example, the resistance of platinum, the most common RTD material, is shown in Fig. 1a from −200 °C to 600 °C. To use an RTD, the resistance of the metallic sensing element is measured and then its temperature is calculated from a known calibration relation. The most important property of an RTD is its ► temperature coefficient of resistance (TCR), often denoted by α. The TCR is defined as the relative change in resistance per unit change in temperature:

$$\alpha(T) \equiv \frac{1}{R}\frac{dR}{dT}\,, \tag{1}$$

where R is the resistance and T is the temperature. A larger TCR results in a more sensitive RTD. For industrial and standards-grade platinum RTDs, the TCR is approximately 0.0039 K^{-1} near room temperature, although this value can be significantly reduced in microfabricated platinum RTDs due to their different microstructures (Fig. 1b). RTDs are traditionally made of loosely wound platinum wire encapsulated in a ceramic, glass, or metallic housing. RTDs are also made from laser-trimmed films of platinum on a ceramic substrate. These chip-style RTDs are cheaper and smaller than the wire-wound variety and offer a faster response time, but historically they have been slightly less accurate and at greater risk of degraded accuracy due to thermal expansion mismatch and impurity contamination from the underlying substrate. Nickel, copper, and tungsten are less widely used for commercial RTDs. In MEMS and microfluidic devices, it is common to microfabricate small metallic RTDs out of a wide variety of metals, including platinum, nickel, copper, and gold.

Typical Applications

RTDs are used in a great variety of applications. At one extreme, carefully-designed platinum RTDs are used in the very definition of temperature between 13.8033 K and 961.78 °C [2], because of their potential for extreme stability and accuracy (uncertainties of better than ±1 mK). At a more practical level, commercial RTDs are widely used for industrial and research applications from 14 K to around 600 – 700 °C, with typical absolute accuracies of around ±0.15 K to ±2 K uncalibrated, or ±0.1 K or better after calibration. Bare platinum RTDs also have a long and illustrious history as velocity sensors for fluid flow, a technique known as hot-wire anemometry. More recently, special RTD configurations have also been developed to measure the thermal properties of fluids and solids [7–9].



Resistance Temperature Detectors, Figure 1 (**a**) The normalized resistance of an industrial platinum resistance thermometer (IPRT or RTD) as a function of temperature. This curve was calculated using the Callendar-Van Dusen equation with the IEC standard coefficients, Eqs. (2a), (2b) and (3). (**b**) The normalized resistance of representative home-built platinum RTDs (points) as compared to the standard curve given in (Fig. 1a) (solid line). The circles are measurements of an unannealed platinum wire of 2 mil (51 μm) diameter. The squares are measurements of a microfabricated platinum line on a substrate, deposited by e-beam evaporation and patterned with a lift-off technique. Although the data for the wire RTD are fairly close to the standard curve, the data for the microfabricated RTD have a very different slope, highlighting the necessity of calibration

RTDs Compared to Other Temperature Sensors

For general-purpose temperature measurements with the convenience of electronic readout, the three most common technologies are RTDs, thermistors, and thermocouples. Thermistors are close cousins to RTDs because both depend on the temperature dependence of the electrical resistance of the sensor. However, thermistors are based on semiconducting films such as oxides of cobalt, manganese, and nickel. The TCR of typical thermistors at room temperature is around $-0.03\,\mathrm{K}^{-1}$ to $-0.05\,\mathrm{K}^{-1}$, which is of opposite sign and about 10 times larger in magnitude compared to RTDs, making thermistors significantly more sensitive than RTDs. However, thermistors have an inconveniently nonlinear relationship between temperature and resistance (roughly following an Arrhenius-type trend $R \propto \exp(-\theta/T)$, where θ is a constant) and they can be somewhat less uniform in manufacturing and less stable in use compared to RTDs. Thermocouples are formed at the junction between two dissimilar metal wires, and exploit the Seebeck effect which gives an open circuit voltage that can be related to the temperature at the junction. Thermocouples are inexpensive, offer measurements at a small point, are more tolerant of vibrations and high temperatures compared to RTDs, and may be more convenient because of their direct voltage readout. However, compared to RTDs, thermocouples are less accurate, are subject to spurious signals from intermediate metals and temperature drifts elsewhere in the circuit, and are less well-suited to microfabrication.

Basic Methodology

Typical RTD Materials

An ideal material for use as an RTD sensing element would have the following properties:

- Linear $R(T)$ relationship over a broad temperature range.
- Moderate resistivity for ease of resistance measurement ($10-1000\ \Omega$ is a good value).
- High TCR for good sensitivity.
- Minimal thermal expansion; or thermal expansion matched to its substrate.
- Chemically stable and inert in oxidizing, reducing, and corrosive environments.
- Mechanically strong.
- Good solderability for making junctions.
- Commercially available as wires and films with highly reproducible properties.
- Able to be deposited by evaporation and/or sputtering for microfabrication applications.
- Low cost.

The material that comes closest to satisfying these diverse requirements is platinum, which is justifiably the most common RTD material. One noteworthy weakness of platinum is that it is unstable in reducing environments, and so performs best when there is some oxygen in the surrounding ambient. Other common RTD materials include copper, nickel, and gold, although in principle almost any metal can be used. Although some RTDs are also made out of alloys, such as platinum and rhodium, in general alloys are less well-suited to RTDs because alloy scattering of electrons is not as temperature-sensitive as phonon scattering.

Types of Sensing Elements

RTD sensing elements are available in a wide range of packages for various applications. The sensors can be roughly grouped into the following three categories:

Standard Platinum Resistance Thermometers (SPRTs)

Standard platinum resistance thermometers (SPRTs) are the most accurate and most delicate RTDs in existence. Their applications are largely limited to standards laboratories and other applications requiring temperature accuracies of 1 mK or better. SPRTs are the primary interpolation instrument in the very definition of temperature in the International Temperature Scale of 1990 (ITS-90) from 13.8033 K (the triple point of hydrogen) to 961.78 °C (the freezing point of silver) [2]. An SPRT can therefore cover the vast majority of practical temperatures, although extra care is required above about 400 – 500 °C due to risks of contamination, defect generation, and other materials issues [6]. SPRT sensing elements are typically made of platinum wire of diameters from 10 to 100 μm, gently wound on an insulating support such as mica or quartz. The wire and support are housed in an insulating sheath and may be packed loosely with electrical insulation for additional mechanical support. Electrical connections are always of the 4-wire variety to eliminate the influence of lead resistances. These instruments are very sensitive to shock and vibrations, which can plastically deform the platinum sensing element and alter its calibration.

Industrial Platinum Resistance Thermometers (IPRTs)

For the vast majority of applications, the extreme accuracy of SPRTs cannot justify their high cost, large size, and fragile construction. Instead, manufacturers offer a wide selection of industrial platinum resistance thermometers (IPRTs), which are smaller, far more robust, and only slightly less accurate than SPRTs. They can be either wire-wound or made of thin films evaporated on a substrate, and are most commonly provided with 100 Ω resistance at 0 °C. Various package styles are available, including cylinders, washers, and glue-on chips.

Microfabricated RTDs

Standard commercial RTDs (that is, IPRTs) are typically at least several millimeters in size, which is much larger than would be desired for many applications in MEMS and microfluidics. For these applications there is a clear need for integrated temperature sensors that are smaller than commercial sensors. Microfabricated metallic RTDs are the most common solution to this challenge, although microfabricated thermocouples and thermistors (e. g. doped silicon) have also been used. Micron-sized metallic RTDs are easily patterned using standard microfabrication techniques such as wet or dry etching, liftoff, or electrodeposition. Although platinum is probably still the preferred material for microfabricated RTDs, other metals (e. g. Au, Ni, Cu) are also widely used. For simplicity it is common practice to pattern a microfabricated RTD in the same mask step as other metallization required in the microdevice, thus eliminating the need for a separate deposition and lithography step. An important consideration for microfabricated RTDs is that the properties of the deposited metal can differ significantly from the properties of bulk metals. Microfabricated metals often have more defects and grain boundaries than the wires used most macro-scale RTDs. This leads to increased resistivity in the microfabricated metals, and more importantly to a reduced temperature sensitivity. It is not unusual for the TCR of a microfabricated metal to be tens of percent lower than a well-annealed bulk sample (Fig. 1b). Thus, calibration is essential for microfabricated RTDs, and the literature values of TCR for the bulk metal should be considered only as an upper bound.

Describing the Relationship Between Temperature and Resistance

Depending on the application, the relationship between resistance and temperature will be determined using one of two approaches: a standardized $R(T)$ curve, or a calibration by the end user.

Standardized Curves Relating Temperature to Resistance

For general purpose temperature measurements the user will generally select a commercial platinum RTD (that is, an IPRT) which conforms to existing codes and standards for the relationship between temperature and resistance. Several different standards govern the performance of IPRTs. By far the most widely used is the International Electrotechnical Commission (IEC) standard 60751, which is essentially equivalent to the Deutsches Institut für Normung (DIN) standard 43760 and the American Society for Testing and Materials (ASTM) standard E1137. The uncertainty tolerances on commercial RTD elements are commonly specified as Class A or Class B. As seen from the expressions in Table 1, the uncertainty is minimum at $t = 0\,°\mathrm{C}$ and increases linearly with the absolute value of t, where we have followed the usual convention in this field that t denotes temperature in degrees Celsius. Thus, an uncalibrated Class A RTD at 100 °C has an uncertainty of ±0.35 °C. The IEC tolerance specifications of Table 1 apply to as-received IPRTs without any calibration, and the uncertainty can be improved to ±0.1 °C or better over all temperatures after calibration.

Manufacturers also sometimes specify RTD tolerances with fractions such as *1/10 Class B*, or *1/10 DIN*. These RTDs have reduced uncertainty at 0 °C but are still subject to the same temperature dependence of the uncertainty given in Table 1 for either Class A or Class B. For example, the tolerance formula for *1/10 Class B* is $\pm(0.03 + 0.005\,|t|)\,°C$.

The IEC/DIN standards are based on platinum with some level of impurities such that the $R(T)$ relationship follows a standard curve known as the European curve (described in more detail below). This curve is also designated by its resistance at 0 °C and 100 °C, such that the quantity $\left[R\,(100\,°\mathrm{C}) - R\,(0\,°\mathrm{C})\right] / \left[(100\,°\mathrm{C}) \times R\,(0\,°\mathrm{C})\right]$ is approximately $0.00385\,\mathrm{K}^{-1}$, which is also known as the European Fundamental Interval. Therefore these RTDs are also known as *385* or *0.00385* type RTDs. Note that although this quantity $0.00385\,\mathrm{K}^{-1}$ is also sometimes known as *alpha* and denoted α, it is only approximately equal to the average value of the TCR (as defined in Eq. 1) over this temperature range. Less commonly, IPRTs with higher purity platinum are also available with a value of $0.00392\,\mathrm{K}^{-1}$ for the quantity $\left[R\,(100\,°\mathrm{C}) - R\,(0\,°\mathrm{C})\right] / \left[(100\,°\mathrm{C}) \times R\,(0\,°\mathrm{C})\right]$. This is also known as the American Fundamental Interval or American curve, even though most IPRTs available in the United States now follow the European curve. IPRTs are most commonly available with 3-wire or *Siemens* connections as described below, although 2-wire and 4-wire connections are also available.

Commercial platinum RTDs are almost always described by the following $R(t)$ relationship, known as the Callendar-Van Dusen equation:

$$R(t) = R(0\,°\mathrm{C})\left[1 + At + Bt^2 + C\left(t - 100\,°\mathrm{C}\right)t^3\right], \quad -200\,°\mathrm{C} < t < 0\,°\mathrm{C} \tag{2a}$$

$$R(t) = R(0\,°\mathrm{C})\left[1 + At + Bt^2\right], \quad 0\,°\mathrm{C} \leqslant t < 850\,°\mathrm{C} \tag{2b}$$

where t is the temperature in degrees Celsius. For the large majority of IPRTs which conform to the IEC/DIN standards, the Callendar-Van Dusen constants are assigned the values

$$A = 3.9083 \times 10^{-3}\left[°\mathrm{C}^{-1}\right], \tag{3a}$$

$$B = -5.775 \times 10^{-7}\left[°\mathrm{C}^{-2}\right], \tag{3b}$$

$$C = -4.183 \times 10^{-12}\left[°\mathrm{C}^{-4}\right], \tag{3c}$$

It is often necessary to invert the Callendar-Van Dusen equation to express t as a function of R. For the high temperature range ($t \geqslant 0\,°\mathrm{C}$), the quadratic Eq. (2b) is readily solved for $t(R)$ in closed form:

$$t(R) = \frac{-A \pm \sqrt{A^2 - 4B\left(1 - R(t)/R(0\,°\mathrm{C})\right)}}{2B}, \quad 0\,°\mathrm{C} \leqslant t < 850\,°\mathrm{C} \tag{4}$$

while below 0 °C numerical or iterative solutions may be preferred. Many commercial meters are available to convert directly from resistance to temperature using these equations with the standard coefficients. However, users should be aware that slightly different values of the coefficients may be provided by an RTD manufacturer, or determined by a user after careful calibration. In particular, RTDs are still commercially available that follow the *American curve* (0.00392-type), and should be used with different values of the Callendar-Van Dusen constants. If one of these 0.00392-type RTDs is mistakenly used with the IEC/DIN standard coefficients given above (0.00385-type), the calculated temperature will be correct at 0 °C, but will be in error by about 3 K at −200 and 200 °C, with errors increasing to nearly 10 K at 600 °C.

Calibration

Because microfabricated metals generally have more defects and grain boundaries than the metals used in commercial RTDs, they will have different $R(t)$ relationships, making it essential to calibrate microfabricated RTDs prior to use. There are many approaches to calibration depending on the desired accuracy. For many MEMS and microfluidics applications it will be satisfactory to calibrate the RTD against a second thermometer with trusted temperature readings. In these calibrations it is important

Resistance Temperature Detectors, Table 1 Temperature accuracy of industrial platinum resistance thermometers (IPRTs) according to the most common standard, which is known variously as IEC, DIN, ASTM, 0.00385-type, and/or the European curve. Note that t is the temperature in degrees Celsius

	Class A	Class B
Temperature Range	$-200\,°\mathrm{C} < t < 650\,°\mathrm{C}$	$-200\,°\mathrm{C} < t < 850\,°\mathrm{C}$
Formula for Temperature Uncertainty	$\pm(0.15 + 0.002\,\lvert t\rvert)\,°\mathrm{C}$	$\pm(0.3 + 0.005\,\lvert t\rvert)\,°\mathrm{C}$
Uncertainty at −100 °C	±0.35 °C	±0.8 °C
Uncertainty at 0 °C	±0.15 °C	±0.3 °C
Uncertainty at 100 °C	±0.35 °C	±0.8 °C
Uncertainty at 500 °C	±1.15 °C	±2.8 °C

that the standard thermometer and RTD to be calibrated are subject to the same temperature. Thus it is important to minimize conduction heat transfer through any leads or supports which will alter the local temperature at the sensing element. Convection and radiation may also be concerns. Calibrations are generally performed in an oven, cryostat, vacuum chamber, or well-stirred bath, often with both RTD and standard thermometer in intimate thermal contact with a common substrate of high thermal conductivity. For example, a copper block may have two holes bored into it to accommodate the RTD and standard thermometer. The practice of taping or gluing the two thermometers to the surface of a substrate which is then placed on a hot plate can result in significant errors, because of the large thermal resistance between thermometer and substrate and potential for large heat transfer along the thermometer leads and supports. For a chip or wafer with microfabricated RTDs, it may be acceptable to firmly attach the wafer to a larger, thermally conducting substrate which is fitted with a standard thermometer in good thermal contact.

The goal of calibration is to obtain data for the temperature-dependent resistance of the RTD being calibrated. This is often done by measuring the RTD resistance at several fixed points, for example at 20, 30, …, 100 °C. It is not unusual for the experimental apparatus used for the calibration to take a long time (from tens of minutes to an hour or more) to reach stable thermal equilibrium at each intermediate temperature. As an alternative calibration procedure, it is sometimes more efficient to slowly sweep the temperature between the minimum and maximum temperatures of interest. In this case the temperature and resistance should both be recorded periodically, or even continuously. If both thermometers are in good thermal contact and the sweep rate is slow enough, the lag in temperature between the two thermometers will be negligible. This can be confirmed by repeating the sweep in the opposite direction and verifying that there is negligible hysterisis in the plot of resistance versus temperature.

After obtaining the calibration data for resistance as a function of temperature at various known temperatures, it is convenient to fit this data with a continuous function for ease of future use. In many cases a linear approximation will be adequate:

$$R(t) = R(0\,°\mathrm{C})\,[1 + c_1 t] \tag{5}$$

where again t is the temperature in degrees Celsius, and $R\ (0\,°\mathrm{C})$ and c_1 are fitting constants determined by the calibration. For example, over the range from 25 °C to 75 °C, a linear approximation for a commercial RTD introduces less than 0.1 °C of error. For improved accuracy a parabolic fit may be used by introducing a third fitting constant c_2:

$$R(t) = R(0\,°\mathrm{C})\left[1 + c_1 t + c_2 t^2\right] \tag{6}$$

This is the same form as the high-temperature Callendar-Van Dusen equation given in Eq. (2b), but in general the constants c_1 and c_2 will be different from A and B. A parabolic fit with the form of Eq. (6) should be adequate for microfabricated metallic RTDs over temperature ranges spanning several hundred degrees. (Recall that *semiconducting* resistance elements are known as thermistors, which are beyond the scope of this article and would be better described by an Arrhenius-type $R(T)$ behavior.)

Measurement Considerations

To achieve a typical accuracy of ±0.1 °C around room temperature with an RTD, the resistance of the sensing element must be measured with accuracies of a few hundredths of one percent. Thus, for typical RTDs with resistances in the range of 10 – 100 Ω, the resistance measurement must have an accuracy of tens of milliohms or even better. This level of accuracy is readily achieved with commercial RTD readers, standard laboratory multimeters, and bridge circuits, each of which is described later. Regardless of the measurement technology, several additional issues must be considered for a quality measurement:

Lead resistances are unlikely to be negligible compared to the required resistance accuracy. For some simple RTDs, two-wire measurements may still be satisfactory, but most commercial RTDs use a 3-wire connection, and for the utmost in accuracy a 4-wire approach should always be used.

Thermoelectric effects occur whenever more than one type of metal is used in the measurement circuit, which includes the sensing element, the leads, and the readout instrumentation. The typical Seebeck coefficient between different metals is around $10\,\mu\mathrm{V/K}$ or more, and it is not unusual for temperature to vary by $5-10\,°\mathrm{C}$ between different parts of an apparatus even for room-temperature measurements. Thus thermoelectric effects can be expected to contribute voltages of $100\,\mu\mathrm{V}$ or more if no precautions are taken, which may lead to errors of $\pm 1\,°\mathrm{C}$ when measuring the RTD temperature around 300 K, and potentially much worse away from 300 K. The first guideline to minimize thermoelectric errors is to minimize the number of junctions between dissimilar metals. When such junctions are necessary, they should be designed as pairs that occur at the same temperature (ideally in a region close to room temperature). For example, if copper leads are connected to a platinum RTD, the two (or 3 or 4) copper-platinum junctions should be placed nearby to each other and thermally anchored to the same common temperature. Thermoelectric voltage errors typically vary slowly with time and are insensitive to the magnitude and direction of the test current. Therefore one effective technique to minimize the impact of thermoelectric voltages in DC measurements is to use a current-reversal method, whereby the true RTD resistance can be estimated from the average of the apparent resistances recorded with both forward and reverse currents. AC measurements are also very good at minimizing thermoelectric errors as well as many other types of noise, and are typically conducted at a few hundred Hertz where inductive and capacitive effects can be neglected.

Self-heating effects occur because the finite measurement current inevitably causes some joule heating (I^2R) within the temperature sensing element. This heating will cause the temperature of the sensing element to rise slightly above that of the surroundings, especially if large sensing currents are used. The heating can be minimized by reducing the sensing current, but this will also reduce the voltage signal thereby increasing the uncertainty in the resistance measurement. As a compromise, common test currents are around 1 mA. It is worth noting that a 1 mA test current through a typical $100\,\Omega$ RTD at room temperature results in a voltage sensitivity of approximately $400\,\mu\mathrm{V/K}$, which is about 10 times more sensitive than the common type K thermocouple ($\approx 40\,\mu\mathrm{V/K}$). Self-heating errors can also be minimized by ensuring good thermal contact between the sensing element and the fluid or solid being measured. In many cases the strength of this thermal coupling between the sensing element and the fluid can be estimated and expressed as a thermal conductance, G, with units of W/K, in which case the self-heating temperature error is given by

$$\Delta T_{\text{self-heating}} = I^2R/G \tag{7}$$

where I is the test current and R is the electrical resistance of the sensing region. This simple relationship also provides a means to experimentally estimate the thermal conductance G and ensure that self-heating effects are negligible. For a constant temperature of the surroundings, the sensor resistance can be measured with several different test currents. The resistance is then plotted against the square of the test current(Fig. 2), and is expected to follow the relationship

$$R(T, I) \approx R_0 + \alpha R_0^2 I^2/G \tag{8}$$

where $R_0(T)$ is the actual resistance of the sensor at the temperature T of the surroundings. This resistance R_0 is sometimes known as the *cold-wire* resistance (as opposed to the *hot-wire* resistance used in anemometry). The slope of resistance versus the square of the current gives the thermal conductance:

$$G = \frac{\alpha R_0^2}{\mathrm{d}R\big/\mathrm{d}\left(I^2\right)} \tag{9}$$

which is useful for estimating the magnitude of the self-heating errors.

Strain gauge effects are an important concern whenever the RTD element is subject to mechanical stress or strain. This can be due to shock, vibration, or damage during handling or operation, or mismatched coefficients of thermal expansion between the RTD and its substrate if they are tightly bonded. For modern commercial RTDs this is not usually an issue.

Non-uniform temperature profiles in the RTD sensing element can occur due to self-heating effects, temperature gradients within the fluid being measured, or thermal losses through the leads and supports of the sensor. Because any such temperature nonuniformities are typically well within the temperature range over which the $R(T)$ relation can be approximated as linear, and the sensing elements have a uniform cross section, it is easily shown that the measured resistance corresponds to the *average* temperature of the sensing element.



Resistance Temperature Detectors, Figure 2 Representative data to illustrate self-heating effects in an RTD. The true value of the RTD resistance at this temperature is 54.194 Ω. Test currents of around 1 mA cause small self-heating errors of less than 0.1 K. Larger test currents of around 5 mA cause significant self-heating errors of 1.5 K or more. The slope of the curve is related to the thermal coupling *G* between the sensing element and the fluid or solid being measured

Measurement Hardware

Commercial Temperature Readers

For commercial platinum RTDs that follow the IEC/DIN (0.00385-type) standard, the most convenient method to determine temperature is to use a commercial temperature reader which automatically measures resistance and converts it to temperature by using the standardized Callendar-Van Dusen coefficients given in Eq.(3). Some of the more sophisticated readers are also capable of handling non-standard curves or lookup tables as provided by the RTD manufacturer or determined by a user calibration. Commercial RTDs are used in 2, 3, or 4-wire configurations. The 2-wire configuration is the simplest but is subject to errors from the finite lead resistances. The 3-wire configuration (*Siemens-type*) is the most common, and can remove the effect of lead resistance as long as all 3 leads are identical (Fig. 3a). The 4-wire configuration is used whenever the utmost in accuracy is required (better than around 0.01 °C.

Direct Measurement with a Digital Multimeter or Lock-in Amplifier

In many cases a commercial temperature reader may not be desirable or available, especially for microfabricated RTDs which do not conform to the IEC/DIN standard. In this case it is common to use a digital multimeter to monitor resistance. Four-wire operation is essential to avoid the effect of lead resistances (Fig. 3b). Widely-available benchtop multimeters typically measure 100 Ω resistances with better than ±0.02 % accuracy, and a test current of 1 mA which is appropriate for typical RTD measurements. At room temperature this resistance uncertainty corresponds to a temperature accuracy of approximately ±0.05 °C, which is adequate for many applications. For increased accuracy a nanovoltmeter can be used along with a stable current source, leading to a typical resistance uncertainties of ±0.005% which corresponds to a temperature accuracy of around ±0.015 °C at room temperature. Thermoelectric effects are likely to be important in these measurements, and should be checked by the current reversal method mentioned above. If AC methods are chosen then a sinusoidal current source should be combined with a lock-in amplifier to ensure the best accuracy. Typical lock-in amplifiers can have voltage accuracies better than one part in 10^4, corresponding to a temperature accuracy of around ±0.03 °C at room temperature.

Because voltage sources are much more common than current sources, especially for AC measurements, experimentalists will sometimes place a *ballast resistor* in series with a voltage source in order to approximate a current source [7]. Furthermore the current is sometimes estimated from the ratio of the source voltage to the total resistance of the circuit, as measured separately at a baseline condition. This practice is generally acceptable as long as the ballast resistor is very stable (ideally TCR = 0) and much larger in magnitude than the RTD element being studied. However, if the RTD resistance is *not* negligibly small compared to the total circuit resistance, the temperature-induced voltage changes across the RTD will be smaller than the analysis assumes, leading the experimenter to underestimate the temperature changes. In this situation a simple correction factor can be applied for improved accuracy [7].

Bridges

Bridge arrangements were the standard approach for all RTD measurements circuits prior to the development of highly-accurate digital electronics, and are still used at standards laboratories to achieve the utmost extremes of accuracy. Carefully-made DC and AC bridges can have accuracies of better than 1 part in 10^7, which for a typical platinum RTD at room temperature corresponds to a temperature uncertainty of a few tens of micro-Kelvin. Although a classical Wheatstone bridge can be used in a 2-wire arrangement (Fig. 3c), in practice a 3-wire or 4-wire arrangement is always used in order to compensate for the effects of lead resistances. The 3-wire arrangement



Resistance Temperature Detectors, Figure 3 Several methods for measuring the resistance of an RTD sensing element. (**a**) The 3-wire connection which is most widely used in commercial RTDs. (**b**) A 4-wire arrangement for use with a digital multimeter or lock-in amplifier. (**c**) 2-wire arrangement in a classical Wheatstone bridge, which is subject to errors due to the lead resistances. (**d**) An improved bridge using the Siemens arrangement, a common 3-wire connection where the lead resistances cancel (as long as the leads have the same resistance). (**e**) A half-bridge with two differential amplifiers [8]. The standard resistor is chosen to have nearly the same resistance as the RTD sensing element, resulting in reduced common-mode background voltage for the same RTD signal

is also known as the Siemens arrangement and is shown in Fig. 3d. To the extent that all 3 wires have the same resistance, the unknown lead resistance cancels out at the balance condition. However, because the lead resistances are never truly identical, there is always some residual uncertainty which limits the accuracy of this arrangement to around ±0.01 °C. For the utmost in accuracy, 4-wire arrangements such as the Mueller bridge are used.

It may sometimes be worthwhile to use a half-bridge in combination with simple operational amplifier (op-amp) circuit, as shown in Fig. 3e. The standard (or *series*) resistor should have a very low TCR and its value is chosen and/or adjusted to be close to the value of the RTD resistance at some baseline temperature. The two differential amplifiers remove most of the common-mode background voltage, allowing the output voltage to be dominated only by the *changes* in the RTD voltage due to temperature. This can improve the measurement accuracy by making better use of the available dynamic range of the multimeter or lock-in amplifier and by making the measurement much less sensitive to fluctuations in the current source. A multiplying digital-to-analog converter element (not shown) can also be incorporated to allow computer control of the adjustments of the standard resistor [8].

Key Research Findings

RTDs already have a long history for both industrial and standards-grade thermometry [2–6]. Over the last century the key enabling results have included: the ability to fabricate low-stress platinum sensing elements that are mechanically supported yet free to expand and contract with temperature changes; the evolution of accurate potentiometers and ratio transformers; the evolution of standards such as IEC 60751 which allow industrial RTDs to be interchanged without calibration; and the development of relatively low-cost, highly-accurate digital instrumentation for sourcing current and measuring voltage, with typical accuracies of ±0.005% to ±0.02%.

Future Directions for Research

The state of the art in thermometry research is generally reported at the International Temperature Symposia, with conference proceedings published by the American Institute of Physics [1]. For metrology applications at standards laboratories, an important research direction for platinum RTDs is to extend the upper temperature limit at which the RTDs can be used. For example, the International Temperature Scale of 1968 (ITS-68) only used platinum RTDs up to 630.74 °C, while requiring a Pt-PtRh thermocouple above this temperature. But subsequent research improved the stability and accuracy of platinum RTDs so that they are now used in ITS-90 up to 961.78 °C. It is likely that research will continue to extend the high-temperature limits of platinum RTDs. Applied research continues to improve the accuracy and reliability of thin-film RTDs, making them a good compact, low-cost alternative to the more traditional wire-wound RTDs.

Finally, there is considerable interest in using what are essentially self-heated RTDs as tools to measure thermal properties. Referring back to Eq.(9) and Fig. 2, it is possible to evaluate the thermal conductance G between an RTD and its environment by studying the RTD's resistance as a function of current. For many situations the thermal conductance can be directly related to one or two thermal properties of the surrounding environment. For example, this concept is used in the hot-wire method of measuring the thermal conductivity of a fluid, whereby a long insulated platinum filament is immersed in a fluid and subject to varying electrical currents. The higher the thermal conductivity of the fluid, the smaller the temperature rise of the wire for a given amount of heat dissipation. In many cases additional information can be extracted by studying the response over a range of frequencies. Related methods can be used to study fluid velocity (hot-wire anemometry) and the thermal conductivity and/or specific heat of wires, fluids, and semi-infinite solids both with and without thin films [7–9].

Cross References

- ► Methods for Temperature Measurements
- ► Temperature Control in Microfluidic Systems
- ► Temperature Sensitive Resistor
- ► Thermoelectric Flow Sensors
- ► Thermoresistive Flow Sensors
- ► Contact Temperature Sensors

References

1. Ripple DC (ed) (2003) Temperature: Its Measurement and Control in Science and Industry, Vol. 7. Eighth International Temperature Symposium 21-24 Oct 2002, Chicago, Illinois, AIP Conference Proceedings, Vol. 684, American Institute of Physics, New York
2. Preston-Thomas H (1990) The International Temperature Scale of 1990 (ITS-90). Metrologia 27:3–10 (see also corrections detailed in Metrologia 27:107)
3. McGee TD (1988) Principles and methods of temperature measurement. Wiley, New York
4. Schooley JF (1986) Thermometry. CRC Press, Boca Raton
5. Quinn TJ (1990) Temperature. 2nd edn., Academic Press, London
6. Bentley RE (ed) (1998) Handbook of temperature measurement. Springer, New York
7. Dames C, Chen G (2005) 1ω, 2ω, and 3ω methods for measurements of thermal properties. Rev Sci Instrum 76(12):124902-1–124902-14
8. Cahill DG (1990) Thermal conductivity measurement from 30 to 750 K: the 3ω method. Rev Sci Instrum 61(2):802–808
9. Birge NO, Nagel SR (1987) Wide-frequency specific heat spectrometer. Rev Sci Instrum 58(8):1464–1470

Resistance Thermometers

Definition

A resistance thermometer uses the temperature dependency of the electric resistance of the used material. Therefore a well defined and very low current is applied onto the sensor by measuring the voltage simultaneously. For precise measurements pure platinum is often used since the temperature coefficient is almost constant and the variations of the electric resistance are higher than for alloys. When semiconductors are used, much higher temperature coefficients and therewith higher sensitivity can be obtained; these thermometers are called thermistors.

Cross References

- ► Resistance Temperature Detectors

Resistive Heating

- ► Joule Heating in Electrokinetic Flow: Theoretical Models

Resonance and Antiresonance Frequencies

Definition

The resonance and antiresonance frequencies are associated with the frequencies of minimum and maximum impedance for a particular resonance phenomenon, respectively. A continuous structure, like a cantilever beam, may have many resonance and antiresonance frequencies alternating in an ordered fashion with respect to frequency.

Cross References

- ► Piezoelectric Microdispenser

Reynolds Number

Definition

A characteristic dimensionless number that determines the nature of fluid flow in a given set up.

Cross References

- ► Electrokinetic Flow and Ion Transport in Nanochannels

RGB

Definition

Red, Green and Blue cubic color model. The RGB Values are used in an additive way to describe a color. The color ratio varies from 0 % to 100 %. White is determined by 100 % of the three values.

Rheological Fluid Flow in Microchannels

► Non-Newtonian Fluids in Microchannel

Rheology

► Non-Newtonian Fluids in Microfluidics

Rheometer

Synonyms

Viscometer

Definition

Rheometer is an instrument that measures both the stress and deformation history of a material for the derivation of the viscosity and the viscoelastic properties of materials.

Cross References

► Chaotic Mixing Based on Viscoelasticity
► Non-Newtonian Fluids in Microchannel
► Non-Newtonian Fluids in Microfluidics

RIE Lag

Synonyms

Feature size dependent etching

Definition

RIE lag is the phenomenon of the etching rate related to the feature size. The larger the feature size, the higher the etching rate. As the larger feature size results in the lower etching rate, it is called inverse RIE lag.

Cross References

► Aspect Ratio Dependent Etching
► Anisotropic Etching
► Reactive Ion Etching (RIE)
► Plasma Etching

Rosensweig Instability

► Interfacial Instability

Rotary Peristaltic Pump

Definition

Rotary peristaltic pumps transport fluid through a flexible duct using traveling contraction waves. In a typical rotary peristaltic pump, revolving contact elements close off sections of flexible tube, defining moving volumes of fluid. Because a moving boundary displaces fluid and induces the flow, rotary peristaltic pumps are an example of positive-displacement pumps.

Cross References

► Linear Peristaltic Pumps
► Peristalsis
► Peristaltic Pumps

Rotating Channel Flow

► Centrifugal Microfluidics

Rough Channels

► Roughness Effect on Microscale Transport

Roughness

Definition

Surface irregularity or surface features on the channel walls.

Roughness Effect on Microscale Transport

SATISH G. KANDLIKAR
Department of Mechanical Engineering,
Rochester Institute of Technology, Rochester, NY, USA
sgkeme@rit.edu

Synonyms

Rough channels; Surface features to enhance transport

Definition

►Roughness on the surface of a channel wall directly affects the transport processes at the wall. In fluid mechanics applications, roughness is generally defined in terms of the average roughness parameter *Ra*, which represents the average height of the roughness elements on a surface. Newer parameters are being proposed to capture the roughness effects on fluid flow. Recent experimental evidence indicates that the roughness affects laminar flow and transition to turbulence. Roughness effects become especially important in microfluidics as the roughness features offer a unique opportunity to control the level of transport processes occurring at the wall.

Overview

Our understanding of ►roughness effects on fluid flow at macroscale is largely derived from the experimental data obtained by Nikuradse [1] in 1933. He used sand grain coated pipes of 25 to 5486 mm diameter tubes coated with sand grains in his experiments. The sand grains were coated on the inside of the tube in a monolayer, separated by some unknown distance from each other, with the help of a coating of Japanese lacquer. The diameter of the sand grains was used as the roughness parameter ε, and the ►relative roughness was defined as the ratio ε/D, where D is the root diameter of the pipe. The widely used Moody [2] diagram depicts the effect of Reynolds number and relative roughness ε/D on the friction factor. The relative roughness varied from 0 to 0.05, or 5%, and the Reynolds number ranged from 600 to 10^6. Based on his data, Nikuradse concluded that there is no effect of roughness in the laminar range under the experimental conditions employed in his experiments.

Nikuradse's conclusion on the roughness effect in the laminar region was disputed by Kandlikar [3]. It was shown that the experimental uncertainty in Nikuradse's data was of the same order as the pressure drop measurements between the two adjacent pressure taps. Experiments conducted [4] clearly show a roughness effect on friction factor and transition Reynolds number. A comprehensive summary of the research in this field is given by [4] and [5].

In the microfluidic application, since the flow channel size is small, it is possible to achieve high values of relative roughness with only a modest size rough roughness. For example, in a 200 μm channel, a roughness of 5 μm results in a relative roughness of 2.5%. Relatively large relative roughnesses, on the order of 10%, can be easily fabricated using the microfabrication techniques. Since the Reynolds numbers in the microchannels are generally low, a clear understanding of the roughness effects in laminar and transition regions becomes important.

Basic Methodology

The roughness effects on the transport processes are not well understood. Our current knowledge is mainly based on the experimental data available in the literature. In recent literature, the flow over roughness elements is also being investigated using CFD simulation. Some models are also being considered by incorporating an effective viscosity and slip velocity at the wall. But these formulations are still in very preliminary stages.

Key Research Findings

The effect of roughness on incompressible fluid flow was studied extensively by a number of investigators, with the experimental work of Nikuradse [1] being one of the most noteworthy. He clearly established that the roughness affected the friction factor using turbulent flows in circular channels. Moody [2] presented these results in his well-known Moody diagram. The relative roughness was defined as the diameter of the sand grains used by Nikuradse to make the roughened pipes. The relative roughness was defined as the ratio of the sand grain diameter to the pipe internal diameter without the sand grains, or the root diameter of a rough pipe.

Two key features in the Moody diagram were discussed further by Kandlikar et al. [4]. Firstly, the fully developed rough turbulent flow region at higher Reynolds numbers is seen to be dependent on the relative roughness. As the relative roughness increases, the friction factor increases for a given Reynolds number. Secondly, the laminar region was represented as being unaffected by the wall roughness. A new hydraulic diameter $D_{\mathrm{h,cf}}$ was introduced based on the ►constricted flow dimensions. For a circular pipe with wall roughness ε, the constricted flow diameter is



Roughness Effect on Microscale Transport, Figure 1 Variation of transition Reynolds number with relative roughness based on constricted flow diameter, Kandlikar et al. [4]



Roughness Effect on Microscale Transport, Figure 2 (**a**) Fully developed friction factor versus Reynolds number for water flow, $D_\mathrm{h} = 953\ \mu\mathrm{m}$ and $\varepsilon/D_\mathrm{h} = 0.0735$, adapted from [4]. (**b**) Fully developed friction factor versus Reynolds number, both based on constricted flow diameter for water flow, $D_\mathrm{h} = 953\ \mu\mathrm{m}$ and $\varepsilon/D_\mathrm{h} = 0.0735$; $D_\mathrm{h,cf} = 684\ \mu\mathrm{m}$ and $\varepsilon/D_\mathrm{h,cf} = 0.1108$, adapted from [4]

defined as:

$$D_{\mathrm{h,cf}} = D - 2\varepsilon \tag{1}$$

Moody diagram is replotted using the new constricted flow diameter in defining the friction factor as well as the Reynolds number. The resulting plot is shown in Fig. 1. It should be noted that all the lines in the fully rough turbulent region for $\varepsilon/D_{\mathrm{h,cf}} > 0.03$ collapse on a single line with $f_{\mathrm{Darcy,cf}} = 0.042$. This introduces a significant simplification and also provides some insight into the roughness effect on the turbulent flows at high $\varepsilon/D_{\mathrm{h,cf}}$ values. Another fact that is introduced in the modified plot shown in Fig. 1 is that the laminar region was represented by a line similar to that in the original Moody diagram, but was modified to include the constriction effect:

$$f_{\mathrm{cf}} = \frac{\mathrm{Po}}{\mathrm{Re}_{\mathrm{cf}}} \tag{2}$$

Where f_{cf} and $\mathrm{Re}_{\mathrm{cf}}$ are constriction based friction factor and Reynolds number respectively, and Po is the Poiseuille number specific to the cross-sectional geometry of the channel, 16 for circular pipes, 14.23 for a square channel and 24 for flow between two parallel plates.

Since Nikuradse's data in the laminar region was obtained with a high degree of uncertainty, the original Moody plot



Roughness Effect on Microscale Transport, Figure 3 Roughness parameters for application in fluid flow [4]

erroneously indicates that a relationship of $f = \text{Po}/\text{Re}$, with both f and Re based on the root diameter of the pipe. Extensive experiments conducted by [4, 6] show the validity of the constricted diameter approach as indicated by Eq. (2). Figures 2a and 2b show the plots of the experimental data for water in an artificially roughened rectangular channel with sawtooth ridges. The use of the conventional base channel dimensions in Fig. 2a clearly underpredicts the friction factor significantly, while using the same data with the constricted flow parameters shows excellent agreement with the experimental data.

Roughness representation: A set of three parameters are proposed to represent the roughness compatible with the constricted flow parameters discussed in the earlier sections: Maximum Profile Peak Height (*Rp*), Mean Spacing of Profile Irregularities (*RSm*), and the Floor Distance to Mean Line (*Fp*), as shown in Fig. 3. Two of these parameters (*Rp* and *RSm*) are defined in the ASME B46.1-2002 and the other (*Fp*) is proposed by Kandlikar et al. (2005)

Maximum Profile Peak Height (*Rp*): The distance between the highest point of the profile and the mean line within the evaluation length. The mean line represents the conventional average roughness value (*Ra*).

Mean Spacing of Profile Irregularities (*RSm*): Consists of the mean value of the spacing between profile irregularities within the evaluation length. The irregularities of interest are the peaks, so this is equivalent to the Pitch.

$$RSm = \frac{1}{n}\sum_{i=1}^{n} Sm_i \qquad (3)$$

Floor Distance to Mean Line (*Fp*). Consists of the distance between the main profile mean line (determined by *Ra*) and the floor profile mean line. The floor profile is the portion of the main profile that lies below the main profile mean line.

From the above parameters, the equivalent roughness ε can be estimated by the following relationship:

$$\varepsilon = Rp + Fp \qquad (4)$$

Future Directions for Research

The concept of constricted flow diameter is seen to be applicable in the laminar and turbulent flows as illustrated in the above sections. The effect of different roughness structure is also important and needs to be investigated further. The roughness parameter ε defined by Eq. 4 is proposed for replacing the conventional average roughness parameter *Ra*. Further work to validate this concept is currently under way [6]. Experiments with biological application are also being conducted and indicate a need for further investigation in this field [7]. Numerical simulation of the flow with rough walls is also being pursued [8–10]. In future, a close tie-in between the numerical simulations and experimental work is expected. The size and shape of the roughness structure and its effect on the flow can be effectively used to create the desired transport effect at the wall, such as enhanced mixing, localized mass transport enhancement or more effective heat transfer surfaces.

Cross References

- ► Developing Flows
- ► Microfluidic Micing
- ► Pressure Drive Single Phase Liquid Flows
- ► Turbulence in Microchannels
- ► Transition to Turbulence in Microchannels

References

1. Nikuradse J (1933) Strömungsgesetze in rauhen Rohren. VDI-Forschungsheft 361, Beilage zu “Forschung auf dem Gebiete des Ingenieurwesens”, Ausgabe B, Band 4; English Translation: Laws of Flow in Rough Pipes. NACA Tech Mem 1292, 1937
2. Moody LF (1944) Friction Factors for Pipe Flow. ASME Trans 66:671–683
3. Kandlikar SG (2005) Roughness Effects at Microscale – Reassessing Nikuradse’s Experiments on Liquid Flow in Rough Tubes. Bull Polish Acad Sci Tech Sci 53(4):343–349

4. Kandlikar SG, Schmitt D, Carrano AL, Taylor JB (2005) Characterization of surface roughness effects on pressure drop in single-phase flow in minichannels. Phys Fluids 17(10):100606
5. Kandlikar SG, Garimella S, Li D, Colin S, King MR (2005) Flow Boiling in Microchannels and Minichannels. In: Heat Transfer and Fluid Flow in Minichannels in Minichannels and Microchannels. Elsevier, London
6. Brackbill TP, Kandlikar SG (2007) Effect of sawtooth roughness on pressure drop and turbulent transition in microchannels. Heat Transf Eng 28(8-9):662–669
7. Kim YM, Kim WS, Lee SH, Baek JY (2005) Effects of surface roughness on the flow characteristics in PDMS microchannel 3rd IEEE/EMBS Special Topic Conference on Microtechnology in Medicine and Biology, 292–295
8. Rawool AS, Mitra SK, Kandlikar SG (2006) Numerical simulation of flow through microchannels with designed roughnes Microfluid Nanofluid 2(3):215–221
9. Croce G, D'Agaro P (2005) Numerical simulation of roughness effect on microchannel heat transfer and pressure drop in laminar flow. J Phys D: Appl Phys 38(10):1518–1530
10. Baviere R, Gamrat G, Favre-Marinet M, Le Person S (2006) Modeling of laminar flows in rough-wall microchannel. J Fluids Eng, Trans ASME 128(4):734–741

RTD

► Resistance Temperature Detectors

Rutherford Backscattering Spectrometry (RBS)

Definition

Material characterization technique which uses a high-energy beam of He ions to determine the chemical and physical properties of a material. The beam is directed at a sample and the ions which scatter from the sample are collected by a detector. This technique can give both composition and crystallographic information on a material.

Cross References

► Fabrication of Self-Assembled Catalytic Nanostructures

Sample Handling

► Microfluidic Sample Manipulation

Sample Pre-Fractionation

► Biosample Preparation by Lab-on-a-Chip Devices

Sample Preparation

► Microfluidic Sample Manipulation

Sample Purification

► Lab-on-a-Chip Devices for Sample Extractions

Sample Purification Using Magnetic Particles

JUN KEUN CHANG
NanoEnTek Inc. & Digital Bio Technology Co., Inc.,
Seoul, Korea
jkchang@digital-bio.com

Synonyms

MACS (magnetic-activated cell sorting)

Definition

Isolation of specific content from a cocktail using paramagnetic particles in a magnetic field.

Overview

Under a certain magnetic field, a magnetic particle is forced to move depending on its susceptibility and volume [1]. The magnetic force [2] is

- paramagnetic particle:

$$F_{\mathrm{M}} = \frac{\chi V}{\mu_0} B \nabla B \tag{1}$$

- superparamagnetic particle (saturation of field in the case of a relatively small particle, in general less than 100 nm in diameter):

$$F_{\mathrm{M}} = m_{\mathrm{s}} \nabla B \tag{2}$$

where the magnetic field (B) is $\mu_0(H + M)$ and the magnetization (M) is the product of a dimensionless magnetic susceptibility (χ_{m}) and a uniform external field (H_{app}). The strength of the magnetic source is expressed by the magnetic moment (μ_0 and m_{s}, respectively, in Eqs. (1) and (2)). The consideration of magnetic property is critical to perform sample purification using magnetic particles.

Magnetic sample purification is conducted by binding magnetic particles on a specific content such as DNA, protein, bacteria or cells in an equivalent contents pool. By applying magnetic particles, a target material which has no magnetic property can be controlled under the magnetic field.

There are three methods in sample purification using magnetic particles [3].

The positive method is to label magnetic particles only with the target molecule. The target molecule is isolated from the others by magnetic force balance under the field. After the isolation process, magnetic particles should be removed from target molecules to reduce the interference during post-processes such as cell culture and gene work. To remove the possibility of this interference clearly, the negative method is used. All other molecules except the target molecule are conjugated with magnetic particles using each specific binding partner. The purifying efficiency of the two methods is reported as 60–90%. The depletion method, which removes partial unwanted contents but not all from a cocktail in a single step, is also used. The sequential depletion shows 99.9% purifying efficiency in general.

Cross References

- ► Lab-on-Chip Devices for Particle and Cell Separation
- ► Magnetic Field Based Lab-on-Chip Devices

References

1. Tondra M, Granger M, Fuerst R, Porter M, Nordman C, Taylor J, Akou S (2001) Design of integrated microfluidic device for sorting magnetic beadsin biological assays. IEEE Transaction Magn 37:2621–2623
2. Inglis DW, Riehn R, Sturm JC, Austin RH (2006) Microfluidic high gradient magnetic cell separation. J Appl Phys 99 08K101-1-3
3. Safarik I, Safarikova M (1999) Use of Magnetic techniques for the isolation of cells. J Chromatograp B, 722:33–53

Sample Transport

- ► Microfluidic Sample Manipulation

Sampling

- ► Transferring Samples to Chips, Techniques

Sampling Unit

Synonyms

Fluidic multiplexer; Fluidic sequencing circuits

Definition

A fluidic device performing spatio/temporal conversion of fluid flows in response to a control signal. It allows only one of the inlet fluid flows at a time to progress to the outlet.

Essential part of sampling units is an array of microfluidic valves. There are many advantages in using for the purpose the no-moving-part valves, but their property of the flow paths not being separated by a solid partition requires a somewhat sophisticated design, with the fluid purity ensured by guard flows. Sampling units find an application in microfluidic systems for combinatorial chemistry, where they deliver a sample at a time from several test reactors allowed to flow to the composition analysis connected to the sampling unit outlet.

Cross References

- ► Microfluidic Systems for Combinatorial Chemistry
- ► Guard Flows

Sand Blasting

- ► Powder Blasting

Satellite Droplets

Definition

Droplets about one or more main droplets that are of a smaller size.

Cross References

- ► Piezoelectric Microdispenser

Saturated Flow Boiling

Definition

Boiling process at the wall while the mean bulk enthalpy of flow is at or above the saturation enthalpy corresponding to the local pressure.

Cross References

- ► Bubble Dynamics in Microchannels

Scanning Electron Microscopy (SEM)

Definition

Material characterization technique where electrons emitted from a filament (typically tungsten) interact with a material to create secondary electrons. These electrons are collected in a detector and used to create an image of the material. The resolution of this technique approaches hundreds of angstroms and thus shows a material's grain structure.

Cross References

- ► Fabrication of Self-Assembled Catalytic Nanostructures

Scanning Probe Measurement

- ► Scanning Probe Microscopy

Scanning Probe Microscopy

DAVID LEE BUTLER
School of Mechanical & Aerospace Engineering,
Nanyang Technological University, Singapore, Singapore
mdlbutler@ntu.edu.sg

Synonyms

Scanning probe measurement; Probe microscopy

Definition

Scanning Probe Microscopy (SPM) is the branch of microscopy concerned with the formation of images of a surface using a physical probe that scans the specimen.

Overview

Scanning probe microscopy originated with the invention of the scanning tunneling microscope (STM) in 1981 by Gerd Binning and Heinrich Rohrer (Nobel Prize for Physics in 1986). The STM relies on the principle of electrons *tunneling* through the gap between a sharpened tip and the sample in a vacuum. For tunneling to take place, both the sample and the tip must be conductors or semiconductors, STMs cannot image insulated materials.

To understand how atomic resolution can be achieved, it is necessary to consider the electronic structure of a metal as illustrated in Fig. 1. The electrons of the metal occupy all the available energy levels up to the energy E_F known as the *Fermi* energy (at this level they precisely compensate the positive charge of the metal ions). For an electron to be able to exit the metal, an additional amount of energy of Φ above the Fermi energy is required. This brings the electron up to the vacuum level, at which point it is free to move away from the metal. The energy Φ is known as the *work function* of the metal.

To allow the electrons to tunnel through the vacuum, a second conductive object needs to be placed a small distance d away from the first. When an electrical voltage V is applied between the specimen and tip, a net electrical current (known as the tunneling current) flows. The current depends on the tip-surface distance d, the voltage V and on the height of the barrier Φ. The relationship is given by Eq. (1).

$$I(d) = \text{constant} \times \text{eV} \exp\left(-2\frac{\sqrt{2m\Phi}}{\text{h}}d\right) \qquad (1)$$

The other quantities in Eq. (1) are the electron charge and mass e and m, and Planck's constant h. Eq. (1) shows that the tunneling current obeys Ohm's law (i. e., $I \propto V$). It also depends exponentially on the distance d. For a typical work function value of 4 electronVolts (eV), the tunneling current reduces by a factor of 10 for every 0.1 nm increase in d. Considering a typical atomic diameter to be 0.3 nm the tunneling current would change by a factor of 1000 over this range.



Scanning Probe Microscopy, Figure 1 Schematic illustrating the tunnel phenomena. (**a**) In a metal, the energy levels of the electrons are filled up to a particular energy known as the Fermi energy E_F. In order for electrons to leave the metal and travel to the other body (in this case specimen and tip), an additional amount of energy known as the work function is required. (**b**) If the distance d between the specimen and tip is small enough, electrons can 'tunnel' through the vacuum barrier and with an applied voltage between the specimen and tip, a tunneling current is achieved

The most common and possible most versatile SPM is the Atomic Force Microscope (AFM). The AFM relies on the principle of the atomic forces exerted between two objects as they are brought close to each other (Fig. 2). At a distance of tens to hundreds of angstroms, the interatomic forces are attractive (predominantly due to long-range van der Waals forces). On approaching the surface to a distance of a few angstroms the force becomes repulsive. To observe this phenomenon, a sharp tip of a few µm in length with a diameter of less than 100 µm is used to probe the surface. The tip is located at the free end of a cantilever (typically 100 to 200 µm in length). The forces between the tip and the sample cause the cantilever to bend or deflect and this movement is measured by a detector. Unlike the STM, the AFM is not restricted to only conducting material.

In comparison with other microscopy techniques such as optical microscopy or scanning electron microscopy, SPM offers a number of advantages in terms of resolution and magnification. However, due to image acquisition by raster scanning, the measurement is slower and the maximum image size is generally smaller as well. Table 1 list some of the more common applications for SPMs.

In addition to the STM and AFM, the SPM family has expanded to include a whole array of instruments for detecting various probe-surface interactions. Figure 3 shows a comparison of the measurement scale of scanning probe microscopes in relation to other types of microscopy.

Basic Methodology

A generalized scanning probe microscope is shown in Fig. 4. The sample is typically mounted on a piezoelectric scanner which allows precise movement in the x-, y- and z-directions. The image is generated by the sample moving under the probe (or vice versa depending on instrument configuration) in a raster pattern. Typical scan step sizes range from a few angstroms to hundreds of nanometres with scan areas ranging from a couple of nanometres to around 50 µm depending on the instrumentation.

Scanning Probe Microscopy, Table 1 Areas of Application for the Scanning Probe Microscopes

Mineral surface morphology
Metal surfaces (roughness)
Microfabrication techniques
Optical and compact discs
Ceramic surface structures
Lipid monolayers (as Langmuir–Blodgett films)
Different layered substances on solids
Self-assembly structures at interfaces
Solid surfaces
Langmuir–Blodgett films
Thin-film technology
Interactions at surfaces of ion beams/laser damage
Nanoetching and lithography, nanotechnology
Semiconductors
Catalyses
Surface adsorption (metals, minerals)
Surface manipulation by STM/AFM
Friction force microscope (FFM)
Polymers
Biopolymers (peptides, proteins, DNA, cells, virus)
Vaccines
Microsensors



Scanning Probe Microscopy, Figure 2 The variation in inter-atomic forces in relation to separation distance



Scanning Probe Microscopy, Figure 3 Lateral and vertical measurement ranges of various microscopes


System to detect vertical position of tip
Feedback system to control vertical position of probe
Probe Tip
Coarse positioning system to bring probe close to sample
A piezoelectric scanner to move sample (or tip) in a raster pattern
Computer system to control measurement & analyse data

Scanning Probe Microscopy, Figure 4 Schematic of a generalised Scanning Probe Microscope

Depending on what physical phenomena is being measured, the probe will either maintain contact with the surface or remain a fixed distance above the surface. This height control is maintained by a feedback system which inputs and amplifies the tunneling current (low voltage) and drives the piezo scanning tube (high voltage). The shielding and layout of the feedback control is critical to the performance of the system as a whole.

Scanning Tunneling Microscopy

The STM typically employs a probe, made of tungsten (W) or platinum–iridium (Pt–Ir) alloy to scan the surface at a distance of 5 to 10 angstroms. The magnitude of resolution achievable is in the range of a fraction of 1 angstrom. This is highly dependable on the size and shape of the probe tip which will determine the lateral resolution.

The STM has a number of very real limitations. The instrument probes the electron cloud structure of the surface with great precision however, this reveals nothing about other important sample properties. As only the electronic structure is observed, information such as distinguishing between different elemental atoms within a compound is not achievable.

Atomic Force Microscopy

Limitations in the STM and its inability to investigate non-conducting surfaces led to the development of the AFM. Based on similar principles to the STM, the AFM can operate on both conducting and non-conducting surfaces.

A cantilever scans the surface and the deflection of the cantilever is detected by the reflection of a laser beam. The cantilever is typically made of Si_3N_4 of approximately 200 μm in length and with a spring constant of between 0.2 and 40 N/m. In many AFM instruments deflections in the cantilever are measured optically by bouncing a laser off the top of the cantilever, minute changes (as small as 10 angstroms) in the light path can be measured using a photodiode array. An alternative detection technique involves the incorporation of a piezoresistive element into the cantilever which generates a small voltage when deflected.

As the AFM relies on actual contact to sense the sample surface (as opposed to current flow for the STM), it can be used on biological molecules, organic materials, polymers, ceramics and insulating materials like diamond or glass.

Once the AFM has detected the cantilever deflection, it can generate the topographic data by operating one of two modes – *constant height* or *constant force*. In constant height mode, the spatial variation of the cantilever deflection can be used directly to generate the surface data as the scanner height is fixed as it scans. In constant-force mode, the deflection of the cantilever can be used as input to the feedback circuit so that the scanner is moved up or down vertically in order to keep the deflection constant. In general, the AFM operates under a constant force mode.

For the cantilever, the two most important characteristics which will affect its performance are the spring constant and the resonant frequency. The spring constant for the cantilever is normally measured directly. For a beam with a rectangular cross section loaded at one end, the spring constant is given by Eq. (2).

$$k_{\text{spring}} = E_{\text{Y}} w_{\text{width}} / 4(\text{t}_{\text{thickness}} / l_{\text{length}})^3 \tag{2}$$

Where k_{spring} is the spring constant, E_{Y} is the Young's modulus and w_{width}, $t_{\text{thickness}}$ and l_{length} are the respective beam width, thickness and length. The resonant frequency of the cantilever will be dependant on which measurement mode or AFM variation is employed (these will be discussed in the proceeding sections) and whether a stiff or flexible cantilever is desirable. The formula for determining the resonant frequency is given by Eq. (3) where m is the mass of the cantilever.

$$\text{resonant frequency} = \frac{1}{2\pi}\sqrt{\frac{k_{\text{spring}}}{m}} \tag{3}$$

The AFM has three common modes or regions of operation; these are contact, intermittent contact and non-contact and are shown in Fig. 2.

Contact Mode

In contact AFM mode (also known as repulsive mode), the AFM tip makes soft physical contact with the sample. As the scanner traces the tip across the surface, the contact force causes the cantilever to bend to accommodate changes in topography. From Fig. 2 it can be seen that the slope on the left side of the graph is relatively steep suggesting the force increases significantly for a very small movement towards the surface. In other words, when the cantilever pushes the tip against the surface, the cantilever will bend rather than forcing the tip against the sample.

In addition to the repulsive force between the tip and sample, two other forces are generally present during contact AFM measurement. These are a capillary force exerted by the thin water layer often present in an ambient environment and the force exerted by the cantilever itself. The capillary force arises when water adheres itself to the tip and creates a strong adhesive force (about 10^{-8} N) that holds the tip in contact with the surface. The force exerted by the cantilever on the surface can be likened to that of a compressed spring with the magnitude and force direction dependent on the spring constant. However, as long as the tip is in contact with the surface the capillary force should remain constant. The magnitude of the total force exerted on the sample varies from 10^{-8} N to the typical operating range of 10^{-7} N to 10^{-6} N.

Non-Contact AFM

Non-contact AFM is one of several vibrating cantilever techniques in which an AFM cantilever is vibrated near the surface of a sample. Tip-sample spacing is in the order of tens to hundreds of angstroms.

Non-contact AFM is desirable where little or no contact between the tip and sample is required. The total force between the tip and sample is relatively low at about 10^{-12} N which makes it advantageous for studying soft or elastic samples. As no contact is made, there are no tip contamination issues to consider.

Cantilever selection differs from that for contact mode as they are required to be stiffer to prevent being pulled into the sample surface.

In non-contact mode, the system vibrates a stiff cantilever near its resonant frequency (typically 100 to 400 kHz) with an amplitude in the range of ten to several hundred angstroms. Any change in resonant frequency or vibration amplitude as the tip nears the surface can be detected. The sensitivity of this technique allows sub-angstrom vertical resolution to be achieved.

Intermittent Contact

Intermittent Contact AFM is similar to the non-contact AFM mode except that the vibrating cantilever is brought closer to the sample so that at the maximum amplitude it makes slight contact with the surface (i. e., 'taps' the surface). The intermittent contact region is shown on Fig. 2. As with non-contact measurement, the change in cantilever oscillation amplitude is in response to variation in tip-to-sample spacing.

In some cases, intermittent contact is preferred as it is less likely to damage the sample than contact mode as it eliminates lateral forces (i. e., friction or drag) between the tip and sample. Compared to non-contact measurement, intermittent contact is more effective for imaging larger scan areas that may include greater surface topographic variation. In recent years, intermittent contact AFM has become a popular tool for cell biologists as it can measure hydrated biological samples- overcoming the adhesive forces of the water by vibrating at a sufficiently high frequency.



Scanning Probe Microscopy, Figure 5 The basic components of an Atomic Force Microscope showing the stationary sample configuration with the tip mounted on the scanning tube

Calibration

Due to the measurement range that SPMs work in, calibration is an essential procedure which needs to be carried out on a regular basis. The calibration of STM and AFM in the x–y direction is carried out using a standard of regular and known structure such as Highly Oriented Pyrolytic Graphite or a grid. The real challenge has been calibration in the vertical direction. Currently used procedures are based on calibration standards consisting of gold samples with one layer steps of gold, lipid layer deposited on a Langmuir-Blodgett film or macromolecules with known dimensions.

Other Types of SPM

Magnetic Force Microscopy

Magnetic Force Microscopy (MFM) images the spatial variation of magnetic forces on a sample surface. The tip is coated with a thin film of ferromagnetic material. To obtain the necessary surface topographic and magnetic information, a two-pass measurement approach is used. The first measurement pass obtains the topographic data by either contact or intermittent contact mode while the second pass uses the non-contact mode to detect changes in the resonant frequency of the cantilever induced by the magnetic fields influence on the tip.

Lateral Force Microscopy

Lateral Force Microscopy (LFM) measures the lateral deflections in the cantilever that are present from forces on the cantilever parallel to the plane of the sample surface. Lateral deflections of the cantilever are normally attributable to changes in surface friction or changes in slope. The LFM has been used to image variation in surface friction which can arise from inhomogeneity in the surface material.

Force Modulation Microscopy

A further extension to AFM imaging is that of Force Modulation Microscopy (FMM) which characterises the sample's mechanical properties while simultaneously obtaining the surface topographic information.

In FMM mode, the AFM tip is scanned in contact with the sample while a constant cantilever deflection is maintained by the feedback system. In addition, a periodic signal is applied to either the sample or the tip. Any variation in the amplitude of cantilever modulation that results from the applied signal can be attributed to a change in the elastic properties of the sample.

Electrostatic Force Microscopy

Electrostatic Force Microscopy (EFM) works on the same two-pass measurement technique as MFM. Rather than measure the magnetic force, in EFM a voltage is applied between the tip and the surface. Any deflection in the cantilever can be attributed to locally charged domains on the sample surface. EFM can be used to map electrostatic fields in electronic devices when switched on and off in a technique known as voltage probing.

Scanning Probe Microscopy, Table 2 Members of the Scanning Probe Microscopy Family

AFM	Atomic Force Microscopy
EFM	Electrostatic Force Microscopy
FMM	Force Modulation Microscopy
KPFM	Kelvin Probe Force Microscopy
LSTM	Laser Tunneling Microscope
MRFM	Magnetic Resonance Force Microscopy
NSOM	Near-Field Scanning Optical Microscopy
SICM	Scanning Ion Conductance Microscopy
SECM	Scanning Electrochemical Microscopy
SCM	Scanning Capacitance Microscopy
SNM	Scanning Noise Microscopy
SPotM	Scanning Potentiometry Microscopy
SSRM	Scanning Spreading Resistance Microscopy
STAP	Scanning Tunneling Atom Probe
SThM	Scanning Thermal Microscopy
STM	Scanning Tunneling Microscopy
SVM	Scanning Voltage Microscopy

Scanning Thermal Microscopy

The scanning probe based thermal microscope (SThM) gives information about the temperature distributions and allows for quantitative determination of the local thermal conductivity in a sample. A resistive probe is employed which both captures the topographic information as well as the temperature/thermal conductivity profile with a resolution of a few milliKelvin. Table 2 provides a list of the more established members of the scanning probe microscope family.

Future Directions for Research

Research in SPMs appears to follow two distinct directions; one as a characterisation instrument and the other as a nanomanipulation instrument. In terms of characterisation, it has found use in many areas as described in Table 1 however, there are demands on the performance of these instruments to allow them to measure larger, rougher samples with greater speed. This has led to new developments in cantilever design as well control systems which is envisaged to continue to satisfy new areas of application.

As a tool for nanotechnology, the STM has been well publicised in its ability to 'push' or manipulate atoms into specific locations to create nanopatterns. However, this is a relatively slow process and would not be commercially viable. A more feasible approach has been undertaken using the AFM to create nanolithographic patterns by using the tip to remove material from a surface and create the desired pattern.

Cross References

- ▶ Biosensors Using Atomic Force Microscopes
- ▶ Dip-Pen Nano Lithography
- ▶ Enzyme Nanolithography
- ▶ Roughness Effect on Microscale Transport
- ▶ Scanning Electron Microscopy (SEM)
- ▶ Surface Roughness Measurement
- ▶ Surface Modification

References

1. Samori P (2006) Scanning Probe Microscopies Beyond Imaging: Manipulation of Molecules and Nanostructures. Wiley-VCH, Weinheim
2. Foster A, Hofer W (2006) Scanning Probe Microscopy: Atomic Scale Engineering by Forces and Currents. Springer, New York
3. Morita S, Wiesendanger R, Meyer E (2002) Noncontact Atomic Force Microscopy. Springer, Berlin

Scattered Light Intensity

▶ Photometer

Segmented (Droplet-Based) Flow

Definition

Segmented flow (or droplet-based flow) means multiphase flow where the individual phases are divided in consecutive segments.

Cross References

▶ Pressure-driven Two Phase Flows

Segmented Flow

▶ Taylor Flow in Microchannels

Selective Silicon Etching

▶ Silicon Micromachining

Self-Assembled Monolayer

Definition

A two-dimensional single layer of molecules induced to spontaneously order upon a surface via covalent bonding at an interface.

Cross References

- ► Surface-Directed Capillary Flow Systems

Self-Assembly

Definition

Growth method whereby atoms naturally group together into structures due to energy considerations that may form shapes such as nanorods and quantum dots.

Cross References

- ► Fabrication of Self-Assembled Catalytic Nanostructures

Self-Assembly Fabrication

Zhemin Wu, Dongqing Li
Department of Mechanical Engineering, Vanderbilt University, Nashville, TN, USA
zhemin.wu@vanderbilt.edu

Synonyms

Molecular self-assembly fabrication

Definition

Self-assembly refers to the fundamental principle which generates autonomous organization of components into structural patterns or well-defined structure without external instructions or human interventions. Molecular self-assembly is the spontaneous organization of molecules under thermodynamic equilibrium conditions into stable, structurally well-defined aggregates joined by a number of noncovalent bonds (Whitesides et al. [1]).

Overview

As a fundamental natural principle, self-assembly exists everywhere at all scales from molecules to galaxies. Self-assembly describes the spontaneous association of numerous individual entities into a structural organization without external interventions. It is defined as reversible processes in which pre-existing parts or disordered components of a preexisting system form structures of patterns. Molecular self-assembly is the most well-studied subfield, which refers to the spontaneous organization of molecules under thermodynamic equilibrium conditions into stable, structurally well-defined arrangements through noncovalent interactions such as hydrogen bonds, ionic bonds, hydrophobic interactions, van der Waals interactions and water-mediated hydrogen bonds [1–4].

There are two major types of self-assembly, static and dynamic [5]. Static self-assembly describes the process that the ordered state occurs when the system is in equilibrium and does not dissipate energy. One special example of static self-assembly is the formation of atomic, ionic and molecular crystals [6–8]. In dynamic self-assembly, the process occurs only if the system is dissipating energy. The patterns formed in oscillating chemical reactions are simple examples [9, 10].

In recent years, self-assembly was successfully applied in micrometer scale structures. Self-assembled monolayer (SAM) [11] is the representative example of self-assembly microfabrication, in which surfaces consist of a single layer of molecules on a substrate. SAMs can be prepared simply by adding a solution of the desired molecule onto the substrate surface and washing off the excess. The technique was utilized on the metal substrates with PDMS stamps to form the combined system for controlling of crystal nucleation [12]. Another example involves a fluidic technique based on patterned hydrophobic SAMs and capillary forces to self-assemble micro fabricated silicon blocks onto silicon and quartz substrates [13].

Cross References

- ► Hydrophilic/Hydrophobic Patterning
- ► Materials used in Microfluidic Devices
- ► Methods for Surface Modification
- ► Microfabrication Techniques
- ► Self-assembled Monolayers
- ► Silicon Micromachining
- ► Surface Modification

References

1. Whitesides GM, Mathias JP, Seto CT (1991) Molecular self-assembly and nanochemistry: a chemical strategy for the synthesis of nanostructures. Science, 254:1312
2. Lehn JM (1993) Supramolecular chemistry. Science 260:1762–1763
3. Ball P (1994) Polymers made to measure. Nature 367:323
4. Zhang S (2003) Fabrication of novel biomaterials through molecular self-assembly. Nature Biotechnol 21:1171
5. Whitesides GM, Grzybowski B (2002) Self-assembly at all scales. Science 295:2418

6. Philip D, Stoddart JF (1996) Self-Assembly in Natural and Unnatural Systems. Angew Chem Int Ed 35:1155
7. Desiraju GR (1989) Crystal Engineering: The Design of Organic Solids. Elsevier, New York
8. Isaacs L, Chin DN, Bowden N, Xia Y, Whitesides GM (1999) Self-assembling systems on scales from nanometers to millimeters: design and discovery. In: Reinhoudt DN (ed) Supramolecular Technology, pp 1–46. Wiley, New York
9. Jakubith S, Rotermund HH, Engel W, von Oertzen A, Ertl G (1990) Spatiotemporal concentration patterns in a surface reaction: Propagating and standing waves, rotating spirals, and turbulence. Phys Rev Lett 65:3013–3016
10. Hess B (2000) Periodic patterns in biology. Naturwissenschaften 87:199–211
11. Kumar A, Abbott NA, Kim E, Biebuyck HA, Whitesides GM (1995) Patterned Self-Assembled Monolayers and Meso-Scale Phenomena. Acc Chem Res 28:219–226
12. Aizenberg J, Black AJ, Whitesides GM (1999) Control of crystal nucleation by patterned self-assembled monolayers. Nature 398:495
13. Srinivasan U, Liepmann D, Howe RT (2001) Microstructure to substrate self-assembly using capillary forces. J Microelectromech Syst 10:17

Self-Diffusion

► Fundamentals of Diffusion in Microfluidic Systems

Semiconductor Nanocrystals

► Semiconductor Nanoparticles

Semiconductor Nanoparticles

Synonyms

Semiconductor Nanocrystals; Q-Dots

Definition

Nanoparticles of semiconductor materials. Many of them absorb light whose energy is larger than their band gap energy and emit fluorescence whose energy corresponds to their band gap. Their band gap can be tuned according to their diameter, composition, and structure, and consequently fluorescence can also be tuned by these properties. Due to their stability and arbitrarity in excitation wave length, they are expected to be used as fluorescence tag for bio materials.

Cross References

► Fluorescence Measurements
► Fluorescent Labelling
► Quantum dots

Sensing and Actuation

► Control of Micro-Fluidics

Serpentine Microchannel Flow

► Curved Microchannel Flow

SERS

Definition

Surface-enhanced Raman scattering

Cross References

► Biosensors Using Surface-Enhanced Raman Scattering

SERS-Based Biosensors

► Biosensors Using Surface-Enhanced Raman Scattering

Shear

► Viscoelasticity

Shear-Driven Flow

Definition

The shear-driven technique is an alternative flow driving principle for the creation of fluidic flows through micro- and nanochannels. It is created when two flat surfaces are translated relative to each other resulting in a movement of the fluid in between the two surfaces. The fluid flow is characterized by a linear flow profile and is independent of the channel size.

Shear-Driven Micro- and Nanofluidics

Kris Pappaert, David Clicq, Veronika Fekete, Gert Desmet
Transport Modeling & (Bio)analytical Separation Science Group (TMAS^2), Vrije Universiteit Brussel, Brussel, Belgium
kris.pappaert@gmail.com

Definition

The shear-driven technique is an alternative flow driving principle for the creation of fluidic flows through micro- and nanochannels. It is created when two flat surfaces are translated relative to each other resulting in a movement of the fluid in between the two surfaces. The fluid flow is characterized by a linear flow profile and is independent of the channel size.

Overview

During the last decade, miniaturization has been a major issue in analytical and bio-analytical chemistry. Microsystems have generated a considerable activity at economic and scientific levels and their importance in our everyday life is expected to increase considerably over the next few years. The drive towards miniaturization follows from an ever increasing demand (from such fields as organic (polymer) synthesis, medical diagnostics and therapeutics, genomics, etc.) for analytical tools capable of identifying and quantifying all compounds within small sample volumes. Furthermore, methods should generate more precise results, higher sensitivity and this in the fastest possible way. An efficient handling of minimal sample consumption can become possible by miniaturizing the analysis systems. Miniaturized fluidic systems can have several applications, such as amplification, digestion, and analysis of deoxyribonucleic acid (DNA) sequences or the separation and analysis of single defective cells in order to diagnose specific diseases at early stages. With the completion of the Human Genome Project, the analysis of gene and protein functions creates a huge demand for advanced biotechnological systems. These systems can only be realized using miniaturized fluid handling systems, which allow the rapid and efficient analysis of structures and functions with minimal sample volume. Due to this increasing demand, microfluidics has rapidly turned into an interdisciplinary research field equally including physics, chemistry, materials science and engineering.

The generation of a stable and controllable fluid flow in microfluidic devices is a major issue and a lot of research work has been put into optimizing the flow driving methods. Not only conventional methods (derived from macroscopic applications) like pressure-driven and ►electro-osmotic flows have been scaled down, but also novel methods like ►shear-driven flows (SDF) have been introduced. There are several problems associated with the conventional flow driving methods: ►pressure-driven flows suffer from pressure drop limitations, while electro-osmotic flows suffer from Joule heating, fluctuations of flow velocity and double-layer overlap [1]. Therefore other approaches to evade these problems and limitations have been proposed (centrifugal forces, magneto-hydrodynamic forces, etc.).

The shear-driven fluidic approach is based on a radical modification of the fluidic channel concept. This recently developed technique for the transport of fluids in ultra-thin channels based on the SDF [2] relies on a very basic hydrodynamic effect: the viscous drag. This effect is present in every fluid flow, be it a liquid or a gas flow. In pressure-driven flows, the viscous drag manifests itself in an undesirable manner, as the stationary column and particle surfaces tend to slow down the fluid flow. In SDF, the viscous drag effect is turned into an asset. By conceiving channels with a moving wall element, this part of the channel wall no longer acts as a flow resistance but instead provides a net source of impulse, dragging along the fluid through the channel without the need to apply a pressure- or voltage gradient.

Instead of considering channels which are hermetically sealed along their longitudinal axis, the channels are axially split into two separate surfaces (Fig. 1a). While one of the surfaces is kept stationary, the other one is translated or rotated past the first. A large number of different channel layouts can be used to put this principle into practice. In the "Basic methodology" section the more practical side of this technology is described in more detail.

Pure hydrodynamic considerations [3] easily allow showing that, when the flat wall element is moved (Fig. 1b) relative to the element carrying the open channel, a flow is obtained which does not generate any pressure drop or pressure build up. The flow rate is only determined by the velocity of the moving wall element. As is taught in nearly every basic hydrodynamics course, the axial velocity in a laminar flow between two flat plates displays a perfectly linear profile, going from $u = 0$ near the stationary wall to $u = u_{\mathrm{wall}}$ near the moving wall [4]. As the viscous drag effect sustains this so-called shear-driven flow (SDF) at literally each point of the channel axis, the flow is generated without any pressure-drop or pressure build-up. This also implies that none of the fluid will leak through the axial split, which in turn implies that the use of axially split channels, forming the basis of the SDF concept, does not pose any sealing problem. It can be shown [3]


Fluid outlet
Upper surface containing spacer supports
3 fluidic microchannels
Fluid inlet
Relative direction of the surface movement
a
Upper stationary surface
$u = 0$
$u_{av} = \frac{1}{u_{wall}}$
u_{wall}
Lower moving surface
b

Shear-Driven Micro- and Nanofluidics, Figure 1 Figure showing the basic concept of a shear-driven flow apparatus. (**a**) The upper wall is kept stationary while the lower wall moves (driven by a linear translating stage) at a constant velocity. In this way the fluid in the channel is flown through the channel. The dimensions of width, length, and thickness are not to scale. (**b**) This shear-driven flow technique results in a linear flow profile inside the microchannel with an average fluid velocity that is half the velocity of the moving wall

that in a channel with a flat rectangular cross-section (width $w \gg$ thickness d), if neglecting the small regions (width of order d) near the side walls, a flow with a substantially linear radial velocity profile (Fig. 1b) is established, with the mean fluid velocity (u_{m}) given by:

$$u_{\mathrm{m}} = \frac{1}{2} u_{\mathrm{wall}} \tag{1}$$

wherein u_{wall} is the velocity of the moving wall.

Since the factor 2 in Eq 1 can also be considered as a geometrical factor, representing the ratio of the moving channel wall surface to the total channel wall surface, it should be noted that Eq 1 only holds in a channel with a flat-rectangular cross-section, wide enough to neglect the surface of the side-walls. It also shows that the SDF method intrinsically is an open-tubular technique: the moving wall cannot be used to generate a significant flow through a packed bed, as the stationary surface area in a packed bed is typically orders of magnitude larger than the surface area of the moving wall ever could be.

The striking difference between Eq 1 and the pressure-driven case that follows from Poiseuille's pressure drop law:

$$\Delta P = \frac{u_{\mathrm{m}} \psi \eta L}{\mathrm{d}^2} \tag{2}$$

is that the fluid velocity is totally independent of the channel diameter (*d*) and the channel length (*L*), implying that the SDF concept offers an intrinsic possibility to get around Poiseuille's pressure drop limitation on *d* and *L*. The fact that neither the length and/or the thickness of the channels, nor the physical properties of the fluid influence the fluid velocity is one of the most interesting properties of shear-driven flows. The SDF concept also retains all the beneficial characteristics of pressure-driven systems (same choice of stationary- and mobile-phase composition, same ruggedness and same possibility to perform temperature and solvent gradient programming, etc.).

The advantage with respect to the electro-osmotic flow is that SDF does not rely on the generation of an electrical double layer but is purely controlled by mechanical means, allowing for much larger fluid velocities, and as the established velocity field is independent of the nature of the fluid (3), the system also offers a perfect flow rate controllability and repeatability.

It should be noted that, with the basic principle described above, a large number of column shape variants for SDF can be conceived. The use of spiral- or helical shaped channels to increase the path length is such an example.

In our group, this type of flow principle has been researched extensively and one of the most important applications is situated in the field of chromatographic separations [5]. For chromatographic purposes, SDF creates the possibility to use longer and thinner separation channels without any theoretical restriction on the fluid velocity. Other advantages are the perfect predictability, reproducibility of the established flow rates and the selection of the solvent or buffer composition solely on the basis of its ability to maximize selectivity or detection [6]. Shear-driven ▶chromatography therefore leads to a high separation efficiency and numerous experimental set-ups have been used to demonstrate the theoretical expected gain.

SDF has also proven to be a successful technique when it comes too enhancing the ▶DNA hybridization on ▶DNA-microarrays. The DNA microarray technology is a recently developed technique that can be used to study gene expression, mutation detection or genome analysis and allows the analysis of hundreds of thousands of genes or complete genomes in parallel. The power and universality of DNA microarrays as experimental tools are derived from the exquisite specificity and affinity of complementary base-pairing of the nucleic acids (the hybridization process). During the pas decade DNA microarrays have become an important biological tool for obtaining high-throughput genetic information in studies of human disease states, toxicological research and gene expression profiling. However, this technique still suffers from a number of inherent shortcomings such as lack of uniformity and slow hybridization speed. The main cause for these shortcomings is the fact that the hybridization process on the microarrays is governed by the slow diffusion process of the target molecules towards their complementary probes. Using the SDF technique this slow diffusion process could be circumvented by transporting small target volumes over the microarray surface, hence enhancing the hybridization rate and sensitivity of the hybridization process

The flexibility of the SDF fluid transport system in nano- and micrometer thin channels enables to exploit numerous other possible applications, especially if a high degree of spatial confinement or an increase in the diffusion transport rates is required. Vankrunkelsven et al. used the SDF system for the size separation of macromolecules and micro-particles in nano- and micrometer deep channels using micro-steps [7] (Fig. 2). The separation of 0.5 and 1.0 µm carboxylated polysterene beads; mixtures of *Staphylococcus aureus* and *Saccharomyces cerevisiae*; and mixtures of *Saccharomyces cerevisiae* and *Escherichia coli* cells in a micro- or nanochannel that is only slightly larger than the molecules themselves and is narrowed in a stepped structure.

Basic Methodology

Shear-Driven Chromatography (SDC)

As it already has been described in the overview, SDC is based on two well-polished surfaces, slid one at the top of the other generating a fluid flow thanks to the viscous drag. For chromatographic purposes, like in reverse phase-HPLC (RP-HPLC) (▶high performance liquid chromatography (HPLC)), the sample solution (present in the mobile phase) needs to flow over a separation surface (the stationary phase) that can adsorb or absorb the sample molecules that need to be separated. The smallest (stationary) plate carries the stationary phase, whilst the longer (moving) plate should either be inert or have an opposite hydrophobicity. Thus far the majority of the conducted separation experiments have been carried out with monolayer coatings of C8 and C18. Given the sub-micron channel heights, these monolayer coatings already provide a sufficient retention capacity to separate a 4 component



Shear-Driven Micro- and Nanofluidics, Figure 2 Compilation of a series of captured CCD-images (20× magnification) of a micro-step separation experiment of a mixture of 0.5 µm and 1.0 µm polystyrene beads (**a-c**) ($u_{\text{wall}} = 100$ mm/s) and a mixture of *E. coli* and *S. cerevisiae* cells (**d-f**) ($u_{\text{wall}} = 10$ mm/s, pure PBS). The channel depth changes respectively from 3.3 µm to 0.7 µm (a-c) and from 5.2 µm to 1.6 µm (d-f) at the micro-machined step, indicated by the white dashed line. The relation between the apparent size of the particles and cells does not correspond to the actual size ratio, due to the disproportionately stronger fluorescence of the larger particles and cells (reproduced from [7])

coumarin dye mixture in the first few mm of a C8-coated nano-channel. The stationary plate also contains an etched rectangular nanochannel. These channels are prepared by Deep ▶reactive ion etching (RIE) using a state of the art etching machine: the AMS 100 SE (Adixen, France).

During the separation, the stationary channel is placed on top of a well polished fused silica plate (Photox Optical Systems, Sheffield, UK). This plate can be translated along the channel direction while the channel is kept in a fixed position (Fig. 3a). The velocity of the moving channel part is controlled using an automatic translation stage. This translation stage is held in the microscope table. The epi-fluorescence microscope is equipped with an Hg-vapour lamp and a UV-1 filter cube set that allows to excite the components at the right wavelength and to detect the emitted fluorescent light (Fig. 3b). The passage of the excitation and emission light is ensured via the moving bottom part made of fused silica. The SDC channels are positioned above the objective lens of the microscope. The emitted fluorescent light is taped by a ▶charge coupled device (CCD) camera.

The actual injection method is semi-automated and consists basically of five successive steps. In the first step, the inlet of the channel is cleaned and all liquid present in front of the channel is removed. In the second step, a small drop of the sample mixture is deposited in front of the channel inlet. During the third step, the moving wall is rapidly displaced over a given prescribed distance depending on the injection volume. This movement forces the sample deposited in front of the inlet into the channel. During the fourth step, the non-entered sample is aspirated and replaced by pure buffer solution. When this is completed, the motion of the translation stage is restarted to perform the actual separation run (step 5). Apart from the second step, everything is automated. Using a computer controlled vacuum switch (needed in steps 1 and 4) and a syringe pump (needed in step 4), the entire injection process is currently completed in a couple of seconds [3].

The efficiency of chromatographic separations can be determined by calculating the plate heights. For the SDC system the theoretical plate height (HETP) can be calculated using Eq 3.

$$HETP = 2 \times \frac{D_\text{m}}{u_\text{m}} + \frac{2}{30} \times \frac{1 + 7k' + 16k'^2}{(1+k')^2} \times u_\text{m} \times \frac{d^2}{D_\text{m}} + \frac{2}{3} \times \frac{k'}{(1+k')^2} \times u_\text{m} \times \frac{\delta^2}{D_s} \tag{3}$$



Shear-Driven Micro- and Nanofluidics, Figure 3 (**a**) This figure shows the employed mechanical set-up. The stationary phase is deposited on the bottom surface of a rectangular nanochannel [1]. The channel is placed on top of a well polished fused silica plate [3] which is moved along the channel direction while the channel is kept in a fixed position by a home-made holder [2]. (**b**) The main part of the detection set-up is an inverted epi-fluorescence microscope equipped with a Hg-vapour lamp (**a**) and a UV-1 filter cube set (**b**) to excite the four coumarin dyes (**c**) at the right wavelength (375 nm) The detection system consists of the two detectors, A CCD camera and a PMT device (**d-e**). The organization of the employed flow principle is represented, as well as the orientation and direction of the light paths of the employed fluorescence detection scheme. The passage of the excitation and emission light is ensured via the moving bottom part made of fused silica (**f**)

The plate height is calculated using the molecular diffusion coefficient of the mobile phase (D_m), the mean fluid velocity (u_m), the retention factor (k'), the channel depth (d), the molecular diffusion coefficient of the stationary phase (D_s) and the stationary phase thickness (δ). In general higher plate heights will lead to more efficient separations or the possibility to perform more complex separations.

Shear-Driven Hybridization (SDH)

The system used to perform shear-driven hybridization (SDH) on microarrays consists of a circular microchamber (diameter= 2 cm) etched in the center of a round, flatly polished (flatness= $\lambda/4$ at $\lambda = 512$ nm) borosilicate glass wafer (Radiometer Nederland, The Netherlands) with thickness 6 mm and diameter 5 cm [9]. This wafer was subsequently clamped in a home-built, hybridization device (Fig. 4). The wafer is rotated with an automated rotation stage equipped with a stepper motor (M-060, Physik Instrumente, Karlsruhe, Germany), and controlled with NetMove420-software (Physik Instrumente, Karlsruhe, Germany). The circular PVC holding cup surrounding the glass wafer makes it possible to control the temperature using a Julabo$^{\text{ő}}$ F32-MD Heating (and Refrigerated) Circulator (JD Instruments Inc., Houston, TX, USA), set at T= 42 °C during all the experiments.



Shear-Driven Micro- and Nanofluidics, Figure 4 Bird's eye view schematic of the rotating micro-chamber hybridization set-up, showing the rotation stage (1) and the stainless holding shaft (2). The PVC-cup (3) is used for temperature control. The etched glass consists of an outer etched ring (4) made to limit the contact area between the rotating bottom substrate and the microarray slide surface, and the microchamber (5). Finally the microarray slide (6) seals the entire system



Shear-Driven Micro- and Nanofluidics, Figure 5 Compilation of a series of subsequent CCD-camera images of the separation of a mixture of four coumarin dyes (C440, C450, C460 and C480) injected at a concentration of 10^{-4} M in a channel with $d = 280$ nm

To carry out the hybridization experiments, a freshly spotted microarray slide was gently deposited (spotted surface facing downwards) on the top surface of the glass wafer. A volume of 10 μL was applied in the 3.7 μm deep micro-chamber with diameter 2.0 cm. During the rotation of the glass wafer, the microarray slide was kept stationary and a pressure of 1 bar was used to push the microarray substrate and the microchamber against each other. For other hybridization experiments (coverslip and Slidepro) the standard hybridization procedures of the MicroArray Facility Lab (www.microarray.be) were followed. For the coverslip hybridization 30 μl sample was used to hybridize the microarray slide for an overnight (16 h) period in an incubator at 42 °C. Hybridizations using the Slidepro-system (GE Heatlhcare) are performed in independently temperature-controlled chambers, allowing customized process parameters to be used for each slide. Up to 210 μl can be injected into each chamber.

All hybridization experiments were conducted using conventional microarray procedures and made use of the VIB_Mouse_21K_II chip (MicroArray Facility, Leuven, Belgium). As array elements, mouse spleen and heart total RNA was used (BD Biosciences Clontech, Palo Alto, CA, USA). All different cDNA strands were obtained by PCR amplification and were arrayed on Amersham type 7 star slides (Amersham Biosciences, Buckinghamshire, UK) using a commercial Generation III Array Spotter (Amersham Biosciences, Buckinghamshire, UK). The array elements were all spotted at a concentration of 200 ng/μL. The spots (diameter 100 μm and spaced 20 – 30 μm apart), situated in the circular spotted area were grouped in 2 × 5 different blocks of 21 × 44 spots.

Prior to each experiment the arrays were slightly dampened and UV-crosslinked at 50 mJ followed by a prehybridization in 2xSSPE/0.2%SDS at 26 °C for 30 minutes. After hybridization the slides were washed

3 times for 10 minutes in respectively 1xSSC/0.2%SDS, 0.1xSSC/0.2%SDS and 0.1xSSC/0.2%SDS at 56 °C and 1 time for 1 minute in 0.1xSSC at room temperature. The slides were then scanned at 532 nm using a commercial Array Scanner Generation III (Amersham Biosciences, Buckinghamshire, UK). Image analysis was done using Array Vision 7.0-software (Imaging Research, ON, Canada) and Spotfire 8-software (Spotfire Inc., Somerville, MA, USA).

All experiments were started from 5 µg testis total RNA and 5 µg lung total RNA per sample. This was first amplified by T7-in vitro transcription and 5 µg aRNA was used for every labeling reaction. After labeling with ►Cy3/Cy5-dye, both samples were mixed and for every experiment, identical amounts of sample, i.e. 5, 20 or 40 pmol Cy3/Cy5-dye were applied. The cDNA was further dissolved in a solution containing 50% formamide, 25% buffer, 15% Mouse COT and 7.5% polydT35. This cDNA-mixture was then respectively denatured at 96 °C for 3 minutes, set on ice for 2 minutes, heated to 42 °C for 5 minutes, centrifuged at $\omega = 12.000$ rpm for another 5 minutes and subsequently held on ice before applying it on the microarray slide.

Key Research Findings

Shear-Driven Chromatography (SDC)

In our lab the use of the shear-driven technology to perform chromatographic separation has been investigated since 1999, and the results obtained thus far are remarkable. Yet there is still room for improvement. Especially the enhancement of the detection system and the automation of the injection procedure have been the two main focus points. They are considered as the Achilles' heel of this technique. It has already been proven that a separations of four coumarin dyes is possible in less than 2 s. Figure 5 shows such a separation of a mixture of four coumarin dyes (C440, C450, C460 and C480) in a 300 nm deep channel in 1.8 sec. The velocity of the moving wall is 2 mm/s (i. e., far below the optimal flow velocity which is situated around 10 mm/s) in order to be compatible with the scan rate of the Charge-Coupled Device (CCD) camera. About 2000 plate numbers per second can be achieved. This offers the possibility to yield over 10,000 plates per centimeter in a few seconds. A separation at 8 mm far from the inlet of the channel does not yield unfortunately the hoped 8000 plates per second but 4000. The reason of the drop in efficiency is explained by the channel irregularities and the use of 10 times more concentrated solutions to allow detecting far from the injection region.

Detection Enhancement

The observation that the SDC technique couldn't reach the theoretical predicted efficiency, led us to find a way to enhance the detection system. A very simple idea about locally deepened channels was investigated. By creating a small but 10 to 30 times deeper region (►detection groove, Figure 6a) in the channel structure near to the exit a 10 to 30 times more intense fluorescent signal can be expected. The groove accumulates the fluid passing in the channel and instead of detecting in the 300 nm deep region of the nanochannel, the detection occurs in a small but much deeper region enabling an enhanced detection. An experimental study was carried out in order to proof the efficiency of the detection grooves. A 4.75 µm deep and 4 µm wide detection groove, running perpendicular to the mean flow direction, was etched (Fig. 6a). This resulted in a 5-fold lower detection limit in a 300 nanometer deep nano-channel. This 5-fold gain in S/N-ratio is however about three times lower than the theoretically expected gain, based on the ratio of the channel depth outside and inside the groove. Measurements performed under stationary conditions indicated that this underachievement is due to scattering light losses. The plate number loss accompanying the passage of the peaks through the detection groove in a 1 cm long and 300 nm deep channels coated with a retentive layer would be of order of 20%.

The separation experiments with the detection groove were however still insufficient for more qualitative studies. This can be attributed to the semi-manual injection procedure that is not reproducible enough. The standard variation of three consecutive injections can vary from 1 up to 50% mainly due to the manual handling in this injection procedure.

Fully Automated Injection System

To tackle the injection problems a new automated injection system was tested (Fig. 6b). An ►injection slit etched by Bosch avoids any formation of asymmetric shaped plugs, which typically occurs during loading of the sample in wide channels. The slit is connected to a vacuum system and syringes for the supply of the analyte and the mobile phase. A CFD simulation was first performed to compare different injection well shapes and configurations in order to account for less profitable configurations.

The main problems related to the semi-automated injection method (the definition of plugs is highly dependent on the dicing quality of the substrate, the method is slow which gives rise to peak broadening by diffusion, reproducibility is bad because of uncontrolled dilution and manual handling and no gradient in the mobile phase composi-



Shear-Driven Micro- and Nanofluidics, Figure 6 (**a**) Schematically overview of the detection groove structure. In the nanochannel structure (1–2) a deeper groove (3) is etched to enhance the detection. With this type of groove (with a depth of 4.75 μm, see side view) a 5 fold decrease in the detection limit could be obtained. (**b**) Outline of the automated injection system. (**a**) The supply channels in the PMMA connect to a cavity above the injection micro-well. (**b**) Wyko (optical profilometry) scan of the backside of the etched well, showing the position of the injection slit in the channel, together with the non-etched channel spacer regions (1, 2) delimiting the lateral extent of the channel and the non-etched region (3) preventing the mobile phase that is present in front of the channel to enter the channel. The flow direction is indicated by the arrows

tion can be created) could be resolved by this new method. It would hence allow performing complex separations.

It was experimentally shown that a good reproducibility occurred both for the peak width as for the sample concentration (standard deviations are max. 4 and 8%, respectively), where as the plug concentration was 80% of the original sample concentration. It was also observed that with the current setup the lower limit of the peak width was 122 μm. This is a consequence of the fact that peak width originating from convection becomes negligible to the contribution of diffusion during filling and flushing. This automated and closed system paves the way for further functionalities in shear driven chromatography, i. e. gradient elution and parallelization.

Shear-Driven Hybridization (SDH)

A second important application of the shear-driven technology based on the microarray technique has been investigated as well in our group. Earlier reports show that the most ideal flow principle for hybridization on the microarrays is an intermitting flow mode where the fluid is kept stationary for a certain period, followed by a short movement of the fluid. The stationary period is necessary to allow the target molecules to form hybrids with their complementary probes, while the short fluid pulses are necessary to refresh the target mixture above the microarray spots.

A further evaluation of the efficiency of the SDH system consisted of a series of hybridizations with complex target samples (mouse spleen and heart) on slides containing more than 21,000 cDNA fragments. In order to compare SDH with other types of hybridization approaches all experiments started from the same amount of genetic material (i. e. 40 pmol Cy3/Cy5- labeled cDNA) (Table 1). As the amount of labeled sample was kept the same for all experiments, SDH had an immediate advantage as the sample concentration is increased from 3 to 21 fold compared to the conventional coverslip and Slide Pro, respectively. A comparison of these three types of hybridization systems (Table 1) showed that, compared to the results with an automated slide processor (SlidePro, GE Heatlhcare), the relative intensity of the spots increased with a factor 2 for the coverslip hybridization and with a factor 4 for the shear-driven hybridization. Furthermore the total number of spots that could be flagged as being hybridized rose from 67% with the Slidepro system and 80% under the coverslip to 87% with the SDH system. This significant rise in the number of spots points to the great potential of SDH as it will be possible to detect a larger number of hybridized spots with the same amount of sample, or detect the same amount of spots with a smaller sample consumption. An even better gain could be obtained by making the shear driven hybridization last longer than two hours. All experiments with the SDH system lasted two hours while the SlidePro and coverslip hybridizations lasted for 16 hours.

Shear-Driven Micro- and Nanofluidics, Table 1 Comparison of hybridization conditions on the shear-driven rotating micro-chamber system, the diffusion-driven coverslip system and the SlidePro (GE healthcare) for a mouse heart and spleen total RNA sample on the VIB_Mouse_5KI microarray chip

	Shear-driven hybridization-system	Diffusion under cover-slip	SlidePro automated hybridization
Amount incorporated Cy3/Cy5 (in pmol)	40	40	40
Sample Volume (in µL)	10	30	210
Sample Concentration (in pmol Cy3/ µL)	3.00	1.00	0.14
Hybridization Time (h)	2	16	16
Surface Micro-chamber (in mm^2)	314	1000	1000
Hybridized spots	87%	80%	67%
Relative Intensity	396%	189%	100%

Figure 7 shows images of experiments identical to the ones from table 1. It was clear from these images that the overall intensity of the spots was much greater for the SDH system than for the coverslip and SlidePro hybridization. For this series (Fig. 7a) of experiments the SlidePro hybridization was conducted with a total amount of 40 pmol incorporated Cy3/Cy5 dyes while the SDH and coverslip hybridizations were performed with only 20 pmol incorporated Cy3/Cy5 dyes. It is even possible to drop the concentration even further to 5 pmol incorporated Cy3/Cy5 dyes in the sample (Fig. 7b) and still be able to get good results with the SDH system, compared to SlidePro, where almost no hybridization occurred.

This report shows how a working prototype for microarray hybridizations based on the shear-driven technology has been developed and tested. The key factor for the success of the SDH method was the combination of the mixing, circumvented the slow molecular diffusion, and the reduction of sample volume generated more concentrated samples and higher final intensity values of the microarray spots. The concentration was indeed found a major factor on the effect of convection to reach higher signals intensities.

Future Directions for Research

The investigations into the fundaments of the shear-driven technique and the different applications (SDC, SDH, . . .) is still ongoing. Fundamentally different types of spacer walls are being tested in order reduce the channel depth under the 100 nm boundary. Until now 100 nm has been the limit of the shear-driven fluidics. Other channel designs and etching techniques are now being used to reduce even



Shear-Driven Micro- and Nanofluidics, Figure 7 A series of different hybridization experiments done with 20 pmol (coverslip and SDH) and 40 pmol (SlidePro) of incorporated Cy3/Cy5 dyes (**a**) and with 5 pmol of incorporated Cy3/Cy5 dyes (**b**). All experiments were done with mouse heart (Cy3) versus spleen (Cy5) total RNA sample on the VIB_Mouse_21KII microarray chip further the channel depths in order to reach sub 100 nm nanofluidic flows. Also the development towards infinite moving wall elements and high-throughput formats are being studied.

For SDC applications, apart from detection enhancement and the automation of the injection system, much effort is put into the development of novel stationary phases and the application of gradient elutions.

Currently a novel SDH prototype is being developed to enable a 100% coverage of the microarray slide, where our current prototype covers only 30% of the microarray slide. In order to use shear driven convection on standard microarray slides, the prototype needs to be redesigned from a rotating to a lateral movement or change the standard microarray slides to microarrays on round disks.

Cross References

- ► Electroosmotic Flow (DC)
- ► DNA-Microarrays
- ► Pressure-Driven Flow
- ► Reactive Ion Etching (RIE)

References

1. Bhuiyan LB, Outhwaite CW, Levine S (1979) Chem Phys Letters 66:321
2. Desmet G, Baron GV (2000) Anal. Chem. 72:2160
3. Schlichting H (1958) Boundary Layer Theory. Mc-Graw Hill, London
4. Desmet G, Baron GV (1999) J Chromatogr A 855:57–70
5. Desmet G, Vervoort N, Clicq D, Baron GV (2001) J Chromatogr A 924:111
6. Clicq D, Pappaert K, Vankrunkelsven S, Vervoort N, Baron GV, Desmet G (2004) Anal Chem 76(23):430A–438A
7. Vankrunkelsven S, Clicq D, Pappaert K, Baron GV, Desmet G (2004) Anal Chem 76:3005–3011
8. Clicq D, Pappaert K, Vankrunkelsven S, Vervoort N, Baron GV, Desmet G (2004) Anal Chem 76(23):430A–438A
9. Vanderhoeven J, Pappaert K, Dutta B, van Hummelen P, Desmet G (2005) Anal Chem 77:4474–4480

Shear Flows

Definition

Fluid motion that is characterized by velocity gradients.

Shear Stress

► Wall Shear Stress

Shear Stress Sensors

PRADIPTA KUMAR PANIGRAHI
Department of Mechanical Engineering, IIT Kanpur,
Kanpur, India
panig@iitk.ac.in

Definition

Fluid flow past a surface or boundary leads to surface forces acting on it. These surface forces depend on the rate at which fluid is strained by the velocity field. A stress tensor with nine components is used to describe the surface forces on a fluid element. The tangential component of the surface forces with respect to the boundary is known as shear stress. The nature or origin of shear stress depends on the nature of flow, i. e., laminar or turbulent. The stress components for a laminar flow are functions of the viscosity of the fluid and are known as viscous stresses. The turbulent flow has additional contributions known as Reynolds stresses due to velocity fluctuation, i. e., the stresses of a laminar flow are increased by additional stresses known as apparent or Reynolds stresses. Hence, the total shear stresses for a turbulent flow are the sum of viscous stresses and apparent stresses. In a turbulent flow, the apparent stresses may outweigh the viscous components.

Overview

The ► wall shear stress is an essential quantity of interest in a wall-bounded flow. The time averaged value of wall shear stress can be used to determine the skin friction drag acting on the body by the fluid flow. The time-resolved behavior of surface shear stress indicates the unsteady flow structures responsible for individual momentum transfer events and turbulence activities. The instantaneous shear stress values at distributed locations on the surface can be used to feedback control the turbulence events inside a boundary layer. Shear stress measurement also helps in assessment and control of power consumption rate and therefore is an important quantity of interest in various industrial applications.

The importance of shear stress measurement is even more crucial for small-scale devices, i. e., MEMS applications, due to their higher surface to volume ratio. There have been many efforts in literature for successful shear stress measurements. The success of these efforts primarily relies on the complexity of the flow, the nature of solid boundaries and limitations of the measurement techniques. The other drawback of shear stress measurements is its smaller magnitude, i. e., the estimated value of shear stress of a typical car moving at 100 km/hour is about 1 Pa. Hence, highly sensitive shear stress measuring devices are required for successful measurements of surface shear stress and it is essential to have proper understanding of the various noise sources that can effect shear stress measurements.

Shear stress sensors provide qualitative information about the flow field, i. e., separation, transition, reattachment, etc., and proper calibration of shear stress sensors is required for quantitative measurement/information. Hence, this review concentrates on: principle of operation, noise sources and calibration of various shear stress sensors. The spatial and temporal resolution requirements for turbulent flow applications and the benefit of MEMS sensors are also discussed.

Requirements for Turbulent Flow

Turbulence is characterized by the existence of numerous length and time scales. The time scale is a measure of the fact that at a given point in a turbulent flow field, distinct patterns get repeated regularly in time. Similarly, distinct patterns may be repeated in space at a given instant and the size of the patterns are known as length scales. Different length scales and time scales have been defined for characterization of turbulent flow field. The smallest eddy of turbulent flow is expressed by the Kolmogorov length (l) and time scale (τ) which is uniquely determined by dissipation (ε) and kinematic viscosity (ν):

$$l = \left(\frac{\upsilon^3}{\varepsilon}\right)^{\frac{1}{4}} \tag{1}$$

$$\tau = \left(\frac{\nu}{\varepsilon}\right)^{\frac{1}{2}} \tag{2}$$

Using the inviscid assumption for calculation of the dissipation rate, the non-dimensional length scale and time scale respectively reduce to

$$\frac{l}{l_\mathrm{S}} = (\mathrm{Re})^{-\frac{3}{4}} \tag{3}$$

$$\frac{\tau}{l_\mathrm{S}} u = (\mathrm{Re})^{-\frac{1}{2}} \tag{4}$$

Here, l_S is the characteristic length of the inertial sublayer, u is the characteristic velocity of the eddy and Re is the Reynolds number (ul_S/ν). Equations (3) and (4) indicate that with an increase in Reynolds number, the length and time scales of eddies decrease. To spatially resolve the small eddies, sensors that are of same size as the Kolmogorov length scale for that particular flow are needed. Hence, smaller sensors are required as the Reynolds number is increased. For a flat plate boundary layer with momentum thickness Reynolds number equal to 4000, the Kolmogorov length scale is of the order of 50 μm. A large-dimension sensor integrates the fluctuation due to small eddies over its spatial extension. Therefore, when measuring fluctuating quantities, small eddies are counted as mean flow and the fluctuating energy is lost. This leads to lower estimated value of turbulence intensity. The other important issue is the spacing between the sensors, which is primarily determined by the spacing between the coherent structures present in the flow. For the turbulent wall boundary layer, the spacing between the sensors needs to be less than the distance between the low-speed streaks, i. e., the near-wall region coherent structures.

Basic Methodology

Classification

Various shear stress measurement techniques have been proposed in the literature. Some of the principal measurement techniques are: Stanton tube, Preston tube, electrochemical technique, velocity measurements, thermal method, floating element sensors, sublayer fence, oil-film interferometry and shear stress sensitive liquid crystal.

The Stanton tube is a rectangular shaped pitot tube located very close to the boundary wall and the mean velocity measured from this pitot tube pressure difference is directly related to the shear stress. The Preston tube is similar to the concept of the Stanton tube using a pitot static tube close to the surface and the difference between the stagnation pressure at the center of the tube from the static pressure is related to the shear stress. The electrochemical or mass transfer probe is flush mounted with the wall and the concentration at the wall element is maintained constant. The measurement of mass transfer rate between the fluid and the wall element is used for determination of the wall shear stress. One of the limitations of the mass transfer probe is that at very high flow rates, the mass transfer rate becomes large and it may not be possible to maintain the wall concentration constant. A detailed discussion on the above three techniques can be found in Hanratty and Campbell [1]. These shear stress measurement techniques are not ideal MEMS-based techniques.

Benefits of MEMS-Based Sensors

MEMS-based shear stress sensors offer many advantages over traditional shear stress sensors. These are:

- MEMS-based shear stress sensors can meet the spatial and temporal requirement of turbulent flow due to their small size.

- MEMS-based sensors have low thermal inertia leading to higher dynamic response.
- MEMS-based sensors are less intrusive compared to the traditional sensors due to their small size and therefore do not effect the flow significantly.
- The energy consumption is low for MEMS-based sensors.
- MEMS-based sensors are ideal for distributed measurements and control, as a large number of sensors can be fabricated on the same chip in a cost-effective manner.

Due to numerous benefits of MEMS-based shear stress sensors, the following shear stress measurement techniques having great promise for future MEMS applications are discussed in the following sections: velocity measurements, thermal sensors, floating element sensors, sublayer fence, oil-film interferometry and shear stress-sensitive liquid crystal.

Velocity Measurements

Velocity measurements close to the wall or the velocity profile measurement in the near-wall region can be used to determine the wall shear stress. Clauser proposed an approach for shear stress measurement of turbulent flow [1]. Here, the mean velocity measurements away from the wall are used with the assumption that the mean velocity ($\bar{U}$) varies with the logarithmic distance from the wall (y), i. e.,

$$\frac{\mathrm{d}\bar{U}}{\mathrm{d}y} = \frac{u^*}{\kappa y} \tag{5}$$

where $u^* = (\tau_\mathrm{w}/\rho)^{1/2}$ is the friction velocity and κ is the von Karman constant. The slope of a semi-logarithmic plot between $\bar{U}$ and y gives u^*/κ and therefore τ_w. The difficulty in this approach is the validity of the logarithmic region assumption and the value of the von Karman constant, which is approximated to be equal to 0.40. For flows with large pressure gradient, a well-defined logarithmic layer does not exist. If the wall is flat and in equilibrium situation Clauser proposed a relationship as

$$\frac{\bar{U}}{u^*} = f\left(\frac{yu^*}{\nu}, \Delta\right) \tag{6}$$

where $\Delta = |\mathrm{d}P/\mathrm{d}x|\left(\nu/u^*\tau_\mathrm{w}\right)$ and $\mathrm{d}P/\mathrm{d}x$ is the pressure gradient. Comparison of measured variation of mean velocity with distance from the wall gives the wall shear stress τ_w.

The Spalding formula represents a good fit to the velocity profile in a turbulent boundary layer, i. e., from the wall to the end of the log region, thus including both the linear sub-layer and the logarithmic region. The Spalding formula is given by

$$y^+ = \frac{yu^*}{\nu} = u^+ + \frac{1}{E}\left[e^{-\kappa u^+} - 1 - \kappa u^+ - \frac{(\kappa u^+)^2}{2} - \frac{(\kappa u^+)^3}{6} - \frac{(\kappa u^+)^4}{24}\right] \tag{7}$$

where $u^+ = u/u^*$ and E is a constant equal to 8.6. An iterative procedure is carried out for curve fitting the experimental velocity profile to the Spalding formula and the shear stress is determined from the best fit. The Spalding formula represents the mean velocity profile in a turbulent boundary layer at all pressure gradients and until about $y^+ = 200$.

Optical techniques, i. e., laser Doppler velocimetry (LDV), particle image velocimetry (PIV) and holographic PIV, have matured as successful non-intrusive velocity measurement techniques for large-scale applications. Panigrahi et al. [2] obtained the shear stress from PIV measurements by assuming the validity of law of the wall for turbulent flow. In recent years, the µ-PIV has matured as a successful velocity measurement technique for MEMS applications [3]. The PIV techniques provide instantaneous velocity field information. The spatial and temporal resolution of PIV can be controlled with proper selection of lighting source, i. e., laser, imaging system, i. e., camera and frame grabber, and optical arrangements/components. The continuous development of this hardware in near future is expected to result in very high spatial and temporal resolution velocity measurements. Therefore the µ-PIV and µ-holographic PIV techniques will develop as high-resolution indirect instantaneous shear stress measurement techniques in the near future.

Thermal Sensors

The operational principle of a thermal sensor is based on the relationship between the heat transfer from the sensor exposed to the flowing fluid and the shear stress. For the heat transfer to take place the sensor element temperature must differ from the temperature of the flowing medium, i. e., the sensor is raised to a temperature above the medium temperature. The thermal sensor forms one of the resistances of a Wheatstone bridge circuit (see Fig. 1a). The resistance of the thermal sensor is given by

$$R = R_0\left(1 + \alpha\,(T - T_0)\right) \tag{8}$$

where R is the sensor resistance at temperature T and R_0 is the sensor resistance at reference temperature (T_0); T is the temperature of the sensor and α is the temperature



Shear Stress Sensors, Figure 1 (**a**) Schematic of a hot wire sensor connected to a Wheatstone bridge circuit and (**b**) schematic of a flush-mounted thermal shear stress sensor

coefficient of resistance. The heat transfer rate depends on the nature of fluid flow past the sensor leading to drop in temperature of the sensor. The drop in sensor temperature affects the sensor resistance leading to imbalance of the Wheatstone bridge circuit. The relationship between the bridge circuit imbalances and the heat transfer can be obtained from two approaches: deflection method and null method. In the deflection method, the change in bridge balance due to the input signal is measured. In the null method, an electronic feedback is used to keep the bridge balanced. The null method is usually preferred due to better frequency response. For the electronic feedback, there are three possible modes of operation:

- *Constant current mode* (CC). Here the current through the sensor is kept constant and the change in current needed to maintain its constant value is related to the flow signal, i. e., shear stress.
- *Constant voltage mode* (CV). Here the voltage across the sensor is kept constant and the change needed to keep the voltage constant is related to the shear stress.
- *Constant temperature mode* (CT). Here the temperature of the sensor is kept constant and the voltage or current change needed to keep the temperature constant represents the wall shear stress.

The thermal sensors for shear stress measurements can have two principal modes of variation: elevated hot wire probe and surface-mounted hot wire probe. The principle of operation of these two types of thermal shear stress sensors is discussed in the following sections.

Elevated Hot Wire Probe

In the elevated hot wire approach, the hot wire is mounted a small distance away from the wall. The velocity increases linearly with the wall distance in the near-wall region of both laminar and turbulent flow. For turbulent flow, this assumption is valid for the instantaneous velocity profile up to the wall normal location $y^{+}(yu^{*}/\nu) < 5$. The linear relationship between the shear stress (τ_{w}) and the velocity u at distance y from the wall is given as

$$\tau_{\mathrm{w}} = \frac{\rho \nu u}{y} \tag{9}$$

The true velocity in the near-wall region determined from the hot wire calibrated in the free stream is affected due to the heat conduction in the near-wall region. Therefore, the velocity obtained from the hot wire needs to be corrected based on the empirical relationship. The substitution of this corrected velocity in Eq. (9) provides the wall shear stress. The sensitivity of this approach depends on the wall distance, i. e., there is an optimal wall distance at which the hot wire sensitivity is optimal. In addition to that, the hot wire should be located inside the inertial sublayer to satisfy the basic assumption essential for the shear stress measurement.

Surface-Mounted Hot Wire Sensor

Figure 1b shows a schematic of a flush-mounted thermal shear stress sensor. The sensor element is either positioned


Viscous boundary layer
Flow
δ_v
Thermal boundary layers
δ_T
Q_{f2}
Q_{f1}
Q_{f2}
y
x
Wall boundary
Q_s
$T_w = T$
$T_w = T_\infty + \Delta T$
Effective length

Shear Stress Sensors, Figure 2 The flow and heat transfer mechanism of a flush-mounted thermal shear stress sensor


Flow
Photodiode
X
W_t
Tether
W_e
Floating element
X
L_t
L_e
L_t
a
Incident light
Flow
Floating-element shuttter
n-type Si
Gap
photodiodes
p-type Si susbtrate
X – X
b

Shear Stress Sensors, Figure 3 Schematic of a floating element shear stress sensor: (**a**) top view and (**b**) cross-sectional view

on the top of a substrate or on a thin diaphragm above a vacuum cavity. As the thermal shear stress sensor is flush mounted along the surface of the wall, this technique is considered as non-intrusive with negligible disturbance to the mean flow. The ohmic heating (Q_{ohmic}) due to the current flow through the sensor element transfers heat to both fluid (Q_{fluid}) and the substrate ($Q_{\text{substrate}}$), i. e.,

$$Q_{\text{ohmic}} = Q_{\text{fluid}} + Q_{\text{substrate}} \tag{10}$$

Figure 2 shows the heat transfer mechanism from a surface-mounted thermal sensor. The total heat transfer to the fluid from the thermal sensor (Q_{ohmic}) has two components, i. e., the heat transfer to the fluid (Q_{fluid}) and the heat lost to the substrate ($Q_{\text{substrate}}$). The heat transfer to the fluid has two parts, i. e., direct heat transfer from the sensor element (Q_{f1}) and the indirect heat transfer from the substrate heated by the conduction of heat from the sensor to the substrate (Q_{f2}). The heat transferred to the fluid via the substrate affects the temperature distribution near the sensor. This affects the net heat transfer rate from the sensor element and limits the performance of thermal shear stress measurement. The effective length of the thermal sensor is higher than the size of the sensor element thus limiting the spatial resolution of shear stress measurement. Therefore, effective thermal isolation between the sensor element and substrate is an important issue for optimum performance, fabrication and packaging of thermal shear stress sensors. For thermal isolation, the resistor of the sensor sits on the top of a diaphragm above a vacuum cavity (see Fig. 2). The presence of the vacuum cavity and thin diaphragm reduces the convective and conductive heat transfer to the substrate. Better insulation improves the thermal sensitivity of the sensor, i. e., higher temperature rise ($T - T_0$) of the thermal sensor is achieved for a particular power input (P).

In experimental aerodynamics, the surface hot wire probe has proved to be the most successful standard measurement technique to determine the laminar-to-turbulent flow transition, local separation and shear stress fluctuations. The flush-mounted thermal shear stress sensor is one of the most successful techniques for shear stress measurement and is available in various forms, i. e., sensor skin, etc. [4], due to the rapid development of MEMS manufacturing processes. The quantitative determination of shear stress depends on the proper calibration with a reference method. The calibration issues are described in a later section.

Floating Element Sensors

Direct measurement of tangential force exerted by the fluid on the sensor element is possible using floating element shear stress sensors. Therefore, the floating element-based shear stress sensor is classified as a direct measurement device. A schematic of a floating element shear stress sensor is shown in Fig. 3. The floating element is connected to the substrate by four tether elements. The movement of the floating element due to the surface force, i. e., shear stress acting on it, is sensed by suitable transducer and is related to the shear stress. The movement of the floating element can be inferred using the capacitive, piezo-resistive and optical detection schemes. The axial compression and expansion of the tethers due to the imposed shear stress cause a change in piezo-resistive effect for piezo-resistive sensing element. The change in resistance is a measure of the shear stress magnitude and direction. In the capacitive scheme, the sensor element displacement leads to change in the capacitance value. In the photodiode-based scheme, photodiodes are integrated below the floating element at its leading and trailing edge. A coherent light source illuminates the sensor element from above. The differential photocurrent generated due to the movement of the floating element is related to its displacement (see Fig. 3).

No assumption regarding the flow field is required for the floating shear stress sensor. The displacement (δ) of the floating element sensor as a function of shear stress (τ_w) can be derived from Euler–Bernoulli beam theory as

$$\delta = \tau_\mathrm{w} \frac{L_\mathrm{e} W_\mathrm{e}}{4Et} \left(\frac{L_\mathrm{t}}{W_\mathrm{t}} \right)^3 \left(1 + 2\frac{2L_\mathrm{t} W_\mathrm{t}}{L_\mathrm{e} W_\mathrm{e}} \right) \tag{11}$$

where L_t is the tether length; W_t is the tether width; E is the elastic modulus of the tether; t is the floating element thickness; L_e is the length of the floating element; W_e is the width of the floating element; and g is the recessed gap of the floating element (see Fig. 3). Equation (11) indicates a linear relationship between the displacement of the floating element and the shear stress. The above linear relationship has been verified from the static calibration results of floating element sensors. The flow under the floating element and the pressure gradient acting on its lip introduce error to the measurement of skin friction. This relationship between the effective shear stress (τ_eff) and the actual shear stress (τ_w) is given by [5]

$$\tau_\mathrm{eff} = \left(1 + \frac{g}{h} + \frac{2t}{h} \right) \tau_\mathrm{w} \tag{12}$$

where h is the channel height of the wind tunnel used for calibration. The second and third term of the above equation relate to the effect of gap height and pressure gradient on the measurement error respectively. Equation (12) indicates the benefit of MEMS-based shear stress sensors, as both gap height and the floating element thickness can be maintained at a very small value ($\sim 1\,\mu$m) leading to considerable reduction in errors. In addition, the MEMS-based sensor element results in high spatial resolution and higher frequency bandwidth due to lower effective size and mass respectively. Due to the rapid advancement of MEMS-based fabrication techniques, it is also possible to place pairs of sensors in close proximity at right angles to each other for detection of both streamwise and spanwise shear stress.

The capacitive and piezo-resistive sensing-based floating element sensors may show sensitivity to electromagnetic interference due to the impedance of the electronics elements used for detection. The size of the floating element, the misalignment and gaps around the floating element, pressure gradient, sensitivity to acceleration, vibration and thermal expansion are some of the general drawbacks of floating element sensors. The availability of MEMS fabrication techniques has enhanced the capability of floating element sensors.

MEMS Skin Friction Fence

The generic skin friction fence and its principle has been explained by Hanratty and Campbell [1]. Recently, Schober et al. [6] developed a MEMS-based skin friction fence (see Fig. 4a). The surface fence is a fence protruding from the wall. There is a slot below the surface fence with support at both ends. Two pairs of piezo-resistors are located at both ends of the fence. These piezo-resistors are connected to a Wheatstone bridge circuit. The voltage output of the Wheatstone bridge circuit is related to the strain acting on the fence. The strain due to the deflection of the fence is directly related to the pressure difference across the fence. Hence the voltage output is indirectly related to the shear stress acting on the fence. The surface fence should remain inside the viscous sublayer ($y^+ < 5$). However, there is no requirement on the validity of the law of



a

b

Shear Stress Sensors, Figure 4 Schematic of (**a**) MEMS skin friction fence and (**b**) its calibration curve between the bridge voltage (U_B) and the shear stress (τ_W)

the wall for the turbulent boundary layer. The pressure difference between the front and back of the fence is related to the shear stress, i. e.,

$$\Delta P = A\tau_w + B\tau_w^2 \tag{13}$$

where A and B are constants. From Eq. (13), the measured voltage (V_{br}) from the Wheatstone bridge circuit can be related to the shear stress as

$$V_{br} = A_{br}\tau_w + B_{br}\tau_w^2 \tag{14}$$

where A_{br} and B_{br} are the constants to be obtained from the calibration. Figure 4b shows the calibration curve between the bridge voltage and the shear stress of a micro-fence inside a zero pressure gradient turbulent boundary layer. It may be observed that the sensitivity of the micro-fence is higher at higher shear stress.

Optical Sensors

The optical-based shear stress sensor can be classified into two categories based on the measurement principle: oil-film interferometry and shear sensitive liquid crystal. These techniques are discussed in the following sections.

Oil-Film Interferometry

The oil film technique is a direct method for skin friction measurement based on the movement of interference fringes of a thin film. In this method, an oil film is applied to the smooth solid wall, which spreads out by the flow into a thin layer whose thickness is of the order of 1 µm. The thickness of the oil film is dependent on the shear force acting upon it. Interferometry is used to measure the thickness of the oil film. Monochromatic light of wavelength λ from a light source is incident on the film at an angle θ (Fig. 5a). The light partially gets reflected from the oil/air interface. The remainder of the light passes through the film and reflects from the solid surface and travels back through the oil film. These two beams interfere constructively and destructively with each other in the image plane depending on the phase difference between the two leading to formation of bright and dark bands known as interference fringes.

The local height of the oil film can be obtained from the fringe patterns. The height of the oil film at the kth black fringe is given by

$$h_k = h_0 + k\Delta h\ ;\ k = 0, 1, 2, \ldots \tag{15}$$

where h_0 is the height of the zeroth black fringe at the film edge, i. e., at $k = 0$, and Δh is the difference in height between two consecutive fringes given by

$$\Delta h = \frac{\lambda}{2\left(n^2 - \sin^2\alpha\right)^{1/2}} \tag{16}$$

Here, n is the refractive index of oil and λ is the wavelength of light. A general oil-film interferometry experimental setup is shown in Fig. 5b. Here, the light from preferably a He – Ne laser (wavelength = 632.8 nm) or sodium lamp (wavelength = 589 nm) is incident on the thin oil film through a beam splitter. A camera collects the reflected light from the oil film and a portion of the incident light from the beam splitter against a black background. The motion of the interference fringes is collected by imaging through the camera.

For oil-film interferometry, it is assumed that the oil film is so thin that it does not influence the flow above it and is driven by the skin friction distribution of the flow. Using a control volume analysis of the thin oil film with its height



Shear Stress Sensors, Figure 5 Schematic showing (**a**) fringe formation for oil height measurement and (**b**) an experimental setup using oil film interferometry

h in wall normal (y) direction as a function of streamwise (x) and spanwise (z) coordinate and assuming the shear stress contribution to be dominant compared to the pressure gradient and surface tension force, the governing equation for the thin oil-film flow is

$$\frac{\partial h}{\partial t} + \frac{\partial}{\partial x}\left(\frac{\tau_{w,x} h^2}{2\mu}\right) + \frac{\partial}{\partial z}\left(\frac{\tau_{w,z} h^2}{2\mu}\right) = 0 \tag{17}$$

Using the distribution of oil film height from interferometry measurements and the integration of equation (16) the skin friction can be determined. The benefit of oil-film interferometry is that no calibration is required for measurement of shear stress and the basic analytical expression is used. It can be used for three-dimensional flow situations and provides both magnitude and direction of shear stress. The disadvantage is that it does not possess any temporal resolution and therefore cannot be used for fluctuating skin friction measurements.

Liquid Crystal Sensors

Liquid crystal is a phase of matter that exists between the liquid and solid phase. It exhibits optical properties similar to a solid crystalline material. The molecular arrangement of a liquid crystal is a function of either temperature or shear stress. When the molecular arrangement is sensitive to temperature, the liquid crystal coating can be used for temperature measurement and when the molecular arrangement is sensitive to shear stress, the liquid crystal can be used for shear stress measurement.

Shear sensitive liquid crystal coatings applied to a solid surface consist of helical aggregates of long planar molecules arranged in layers parallel to the coated surface. This molecular arrangement is affected by the application of shear stress on the thin film of liquid crystal. Each layer of molecules is rotated relative to the layer above and below it due to the application of shear stress. The incident light on the coating surface selectively scatters at a wavelength proportional to the pitch of the helix. The local pitch of the helical structure is altered due to application of shear stress relative to the no shear state. The liquid crystal selectively scatters the incident white light as a three-dimensional spectrum in color space depending on the molecular arrangement. The color change observed at a particular direction by the imaging device is a function of both shear stress vector magnitude and direction (see Fig. 6a). The shear vectors with components directed away from the observer exhibits color change responses of the liquid crystal depending on the shear magnitude and direction. At any surface point, maximum color change occurs when the shear stress vector is aligned and directed away from the observer. The location with shear stress directed to the observer exhibits no color change response. The above behavior of the shear sensitive liquid crystal is used for determination of the shear stress magnitude and direction.

A sample experimental setup for the application of shear sensitive liquid crystal is shown in Fig. 6b similar to the one proposed by Fujisawa et al. [7]. The off-axis angles of the camera and the light source with respect to the horizontal are α and β respectively. Two cameras are situated on opposite sides of the axis with an off-axis angle δ. As the color images are acquired at an oblique angle to the test surface, it is important to convert the images at oblique angle to the normal observation angle by using a geometrical transformation technique. The two color cameras



Shear Stress Sensors, Figure 6 Schematic showing (**a**) the principle of shear sensitive liquid crystal and (**b**) the experimental setup for shear stress measurement using shear sensitive liquid crystal



Shear Stress Sensors, Figure 7 (**a**) The relative hue (H_R) versus the shear stress angle (γ) for different shear stress magnitude (τ_w). (**b**) The relative hue (H_R) versus the shear stress angle (γ) for two cameras (left, $\delta = -30°$; right, $\delta = 30°$) at a particular shear stress magnitude

are synchronized with the lighting source. The test section can be rotated leading to variation of the shear stress angle (γ) for calibration. There are different color formats, i. e., RGB, HIS, for quantitative representation of color. The hue has been observed to be the best indicator for expressing the change in color. It can be calculated from

$$H = \left[\pi/2 - \tan^{-1}\left(\frac{2R-G-B}{\sqrt{3(G-B)}}\right) + \pi\right] \Big/ 2\pi;\ G > B \tag{18}$$

The color change of the liquid crystal depends on the illumination and observation angle with respect to the liquid crystal coating surface. Therefore, the calibration of the liquid crystal is carried out by the relative hue ($H_R = H_\tau - H_{\text{no}-\tau}$), where H_τ is the hue value of the liquid crystal with applied shear stress and $H_{\text{no}-\tau}$ is the hue value of the liquid crystal without applied shear stress. The hue value for a particular shear stress magnitude and direction depends on the camera and lighting angle. Therefore, two separate calibration curves for two cameras in stereo arrangement can be used to determine the two unknowns, i. e., the shear stress magnitude and direction. Figure 7a shows the calibration curve between the relative hue (H_R) and the shear stress angle (γ) at different shear stress amplitudes (τ_w) for a particular camera and lighting angle. Figure 7b shows the relative hue (H_R) versus the shear stress angle (γ) for two different cameras (left and right). For quantitative determination of the shear stress, the two cameras and lighting source are set at optimum off-axis (δ), observation (α) and illumination (β) angles respectively. The calibration curve between the relative hue of both the cameras (left and right), i. e., $H_{\text{R-left}}(\tau_w, \gamma)$ and $H_{\text{R-right}}(\tau_w, \gamma)$ with respect to the shear stress magnitude (τ_w) and direction (γ) is established during the calibration process. The determination of shear stress magnitude and direction for an actual measurement is carried out by an iterative process. Initially, the shear stress magnitude (τ_w) and direction (γ) are assumed. The corresponding hue values for both left and right cameras are determined from the calibration curve. The measured hue value for both left and right cameras $\left(H_{\mathrm{R-left-M}}(\tau,\ \gamma) \text{ and } H_{\mathrm{R-right-M}}\right)\ (\tau,\ \gamma)$ are compared with the calibrated hue values. The iteration is carried out, i. e., the shear stress magnitude (τ_{w}) and direction (γ) are changed, until the error (E) between the calibrated hue and actual hue value for both left and right cameras is minimized close to a zero value.

$$E = \left(H_{\mathrm{R-left}}(\tau,\gamma) - H_{\mathrm{R-left-M}}(\tau,\gamma)\right)^2 + \left(H_{\mathrm{R-right}}(\tau,\gamma) - H_{\mathrm{R-right-M}}(\tau,\gamma)\right)^2 \qquad (19)$$

Calibration Procedure

Calibration is one of the important issues for quantitative determination of the shear stress vector from measurement. The suitability of the shear stress sensor for a particular application is based on the complexity of the calibration procedure. The calibration of thermal-based shear stress sensors and the calibration setup required is described below. Similar setup can be used for calibration of other types of shear stress sensors. The calibration process is categorized as static and dynamic.

Static Calibration

The heat transfer rate from a flush-mounted shear stress tensor depends on the near-wall flow, i. e., the magnitude of the velocity gradient. For a laminar two-dimensional thermal boundary layer developing over the heated sensor with an approaching linear velocity profile (Fig. 2) and negligible free convection effect the heat loss from the thermal element can be derived from the thermal boundary layer equation as

$$\frac{q}{\Delta T} = \frac{I^2 R}{\Delta T} = 0.807 \frac{C_{\mathrm{p}}^{1/3}\, k^{2/3}}{L^{1/3}\, \mu^{1/3}} (\rho \tau_{\mathrm{w}})^{1/3} \qquad (20)$$

where ρ is the density; k is the thermal conductivity; C_{p} is the specific heat; L is the length of heating element; T is the temperature; μ is the viscosity of the fluid; and τ_{w} is the shear stress. Equation (19) for the ohmic heating of the thermal sensor can be written as

$$\frac{I^2 R}{\Delta T} = A (\rho \tau_{\mathrm{w}})^{1/3} + B \qquad (21)$$

where I is the heating current and R is the resistance of the sensor. The term B represents the heat loss from the substrate and depending on the design can be more than the heat loss to the fluid, i. e., the first term of the above equation. The term A is a weak function of temperature. The length of the sensor calculated from the experimentally determined value of A is more than the actual sensor length due to the heat transfer to the fluid from both substrate and the sensor (see Fig. 2). The forced convection heat transfer assumption is limited by the effective length of the sensor. It is also difficult to satisfy the thermal boundary layer to be within the linear velocity profile. Hence, for a turbulent flow the above equation is modified as

$$\frac{I^2 R}{\Delta T} = A_{\mathrm{T}} (\rho \bar{\tau}_{\mathrm{w}})^{1/n} + B_{\mathrm{T}} \qquad (22)$$

Here, the constants A_{T}, B_{T} and n should be determined empirically from the calibration procedure. If the resistance of the heating element is held constant and the voltage (E) / current (I) is measured, than the above equation can be rearranged as

$$\tau_{\mathrm{w}} = \left(A_{\mathrm{T,New}}\, E^2 + B_{\mathrm{T,New}}\right)^n \qquad (23)$$

Equation (23) between shear stress and the voltage can also be represented as a polynomial function as

$$\tau_{\mathrm{w}} = C_0 + C_1 E + C_2 E^2 + \ldots + C_n E^n \qquad (24)$$

One possible experimental arrangement for shear stress calibration is a rotational rig consisting of a rotational disc above a bottom stationary disc (see Fig. 8a). The gap size (δ) between the discs is very small (0.3 mm to 0.45 mm) to maintain a small Reynolds number ($\mathrm{Re}_{\mathrm{s}} = \omega\delta^2/\nu \ll 5$), where ω is the rotating disc angular velocity. For small Reynolds number, the tangential shear stress can be derived as

$$\tau = \mu(\omega r/\delta)\left[1.0 + (1/1050)\mathrm{Re}_{\mathrm{s}}^2 + O(\mathrm{Re}_{\mathrm{s}}^4)\right] \qquad (25)$$

During calibration, the shear stress sensor is mounted on the stationary plate at various radial positions with different gap size and rotational speed to achieve wide range of shear stress values for static calibration.

Another possible setup for the static calibration uses a wind tunnel (Fig. 8b). The wind tunnel test section should be sufficiently long to establish fully developed flow. The width over height ratio of the test section also needs to be high, i. e., greater than 30, for the flow to be two dimensional. The shear stress values (τ_{w}) for this configuration is related to the local pressure gradient as

$$\frac{\mathrm{d}P}{\mathrm{d}x} = -\frac{\tau_w}{h} \qquad (26)$$

Here, P is the local pressure, x is the streamwise coordinate and h is the half height of the channel. The pressure gradient can be measured by mounting pressure taps along the channel before and after the shear stress sensor location.


Timer belt
To DC motor
Bearing
Flywheel
Marginally-elevated Hot-wire probe
Top rotating disk
Stationary bottom disk
Micrometer screw gauge adjustable supports
a
L
h
Flow
Shear Stress Sensor
w
b

Shear Stress Sensors, Figure 8 Schematic of a static calibration apparatus: (**a**) using a rotating disc and (**b**) long, high aspect ratio smooth channel flow



Shear Stress Sensors, Figure 9 Static calibration curve: (**a**) the bridge output (E) versus shear stress (τ_W) and (**b**) the input power versus (shear stress)$^{1/3}$ of a thermal shear stress sensor



Shear Stress Sensors, Figure 10 The schematic of a dynamic calibration apparatus for the shear stress sensor

Figure 9a shows one representative calibration curve between the Wheatstone bridge output (E) and the shear stress (τ_w) of the shear stress sensor operating in constant temperature mode. The same calibration curve have been re-plotted in Figure 9b using the heating power ($P = E^2/R$) divided by the temperature difference (ΔT) with respect to shear stress to one-third (0.33) power. A linear variation as expected from Eq. (21) is clearly observed. The laminar value of the exponent (0.33) may change due to the restriction by the experimental condition during calibration, i. e., wall presence, mounting location and size of the sensor element. Hence, the exponent value around 0.4 in contrast to the laminar value of 0.33 has been observed in many investigations.

Dynamic Calibration

The shear stress sensor for turbulent flow needs to accurately capture the complete turbulent fluctuation spectrum. Therefore, the shear stress sensor should possess a large bandwidth with flat and minimum frequency–phase relationship. For direct measurement, i. e., floating point sensors, the resonant frequency of the floating element and the fluidic damping determines the usable bandwidth. For the thermal sensor, the thermal inertia of the sensor element and the frequency-dependent heat conduction to the substrate influence the usable bandwidth. It is complicated to analytically predict the frequency response of the thermal sensor. Therefore, dynamic calibration is essential to characterize the frequency response of the sensor.

The Stokes-layer excitation in a cylindrical duct is one of the effective techniques for dynamic calibration of shear stress sensors [8]. The flow inside the duct is driven by an oscillating pressure gradient generated by loud speaker (see Fig. 10). The loud speaker driven by an amplifier generates an acoustic wave. The amplifier receives sinusoidal input from a function generator. The microphone and shear stress sensor are mounted at opposite locations of the tube. The data acquisition system records the signal from the microphone and shear stress sensor.

The solution of the compressible momentum equation provides the relationship between the shear stress and the pressure gradient and the excitation frequency as

$$\tau(z,t) = -\frac{p' e^{j(2\pi f t - kz)}}{c} \sqrt{\frac{j2\pi f \mu}{\rho}} \frac{I_1\left(R\sqrt{j2\pi f/\nu}\right)}{I_0\left(R\sqrt{j2\pi f/\nu}\right)} \quad (27)$$

Here, p' is the magnitude of pressure fluctuation; c is the speed of sound; f is the frequency of acoustic wave; $k = 2\pi f/c$ is the wave number; z is the axial direction; μ is the fluid viscosity; ρ is the density; R is the radius of tube; ν is the kinematic viscosity; and I is the Bessel function. The frequency response function $H(f)$ from Eq. (27) is used to determine the frequency response of the shear stress sensor as

$$H(f) = \frac{V(f)}{\tau(f)} \frac{\delta\tau}{\delta V} \quad (28)$$

Here, $V(f)$ is the sensor voltage, $\tau(f)$ is the shear stress calculated from Eq. (27) as a function of the pressure fluctuation magnitude and $\delta\tau/\delta V$ is the static sensitivity from the static calibration of the shear stress sensor. For an ideal sensor the static and dynamic sensitivity should be equal leading to a normalized frequency transfer function $(H(f))$ of 0 dB at all measurable frequencies.

Uncertainty and Noise

For proper design and practical implementation of shear stress measurement procedure, it is important to be aware of different sources of noise and uncertainty during the measurement. When using shear stress sensor based on MEMS technology, all circuit elements are located on the substrate surface. Hence, the electronics is one of the primary sources for drift or noise during shear stress measurement. The other important contribution to noise is physical sources, i. e., during low flow velocity situations the free convection effect disturbs the signal. The packaging and mounting of the sensor element can generate offset signals which may change in time due to the change in heat dissipation of the sensor element. This influences the frequency response of the shear stress sensor. The MEMS-based shear stress sensor can have the following noise sources: thermal or white noise, shot noise, flicker noise and photon noise. The thermal noise is the movement of electrons due to the finite temperature difference leading to noise in the output voltage or current. Shot noise is due to the flow of charge carriers past different potential barrier sources in the electronic circuits. Flicker noise or $1/f$ noise is the low-frequency noise due to flow of charge carriers in discontinuous medium, i. e., resistors, transistors, thin films, etc. Photon noise is due to the fluctuation in the number of quanta or power reaching the photodiode or CCD element. Photon noise is strongly temperature dependent and can be reduced by effective cooling.

Future Directions for Research

Shear stress measurement plays an important role for characterization and control of both macro- and microscale flows. There are various existing techniques suitable for either steady state or instantaneous nature of the flow. The rapid development of MEMS manufacturing technology has immensely contributed to improvement in spatial and temporal resolution of shear stress sensors. Therefore, turbulent flow control has become feasible for many practical applications. However, the calibration and implementation issues of shear stress measurements are not completely established. Therefore, the implementation procedure for shear stress measurement is problem specific and requires complete understanding of the measurement principle. The existing shear stress measurement technologies have not been implemented over a wide range of microscale flow problems. Therefore, future research should concentrate on critical issues relevant to shear stress measurement in various microflow applications. This will contribute towards development of matured shear stress measurement techniques.

Cross References

- ► Flow Rate Measurements
- ► Turbulent Structures

References

1. Hanratty TJ, Campbell JA (1996) Chapter 9: Measurement of wall shear stress. In: Goldstein RJ (ed) Fluid Mechanics Measurements, 2nd edn. CRC. Taylor and Francis, Washington
2. Panigrahi PK, Schroeder A, Kompenhans J (2005) PIV investigation of flow behind surface mounted permeable ribs. Exp Fluids 40:277–300
3. Nguyen N, Wereley ST (2006) Fundamentals and Applications of Microfluidics. Artech House, Norwood/London
4. Xu Y, Jiang F, Newbern S, Huang A, Ho CM (2003) Flexible shear-stress sensor skin and its application to unmanned aerial vehicles. Sens Actuators A 105:321–329
5. Naughton JW, Sheplak M (2002) Modern developments in shear-stress measurement. Progr Aerosp Sci 38:515–570
6. Schober M, Obermeier S, Pirskawetz S, Fernholz HH (2004) A MEMS skin-friction sensor for time resolved measurements in separated flows. Exp Fluids 36:593–599
7. Fujisawa N, Aoyama A, Kosaka S (2003) Measurement of shear stress distribution over a surface by liquid-crystal coating. Meas Sci Technol 14:1655–1661
8. Sheplak M, Padmanabhan A, Schmidt MA, Breuer KS (2001) Dynamic calibration of a shear-stress sensor using Stokes-layer excitation. AIAA J 39(5):819–823
9. Fernholz HH, Janke G, Schober M, Wagner PM, Warnack D (1996) New developments and applications of skin-friction measuring techniques. Meas Sci Technol 7:1396–1409
10. Löfdahl L, Gad-el-Hak M (1999) MEMS-based pressure and shear stress sensors for turbulent flows. Meas Sci Technol 10:665–686

Shockwave

Definition

Large amplitude, non-linear pressure wave produced in supersonic field or flow. The fluid passing through this discontinuity undergoes a finite decrease in velocity accompanied by a marked increase in pressure, density, temperature and entropy.

Cross References

- ► Shock Wave in Microchannel

Shockwaves in Microchannels

FLORIN IANCU, NORBERT MÜLLER
Michigan State University, East Lansing, MI, USA
ihuin@egr.msu.edu

Synonyms

Pressure wave; Micro-shock tube

Definition

► Shockwaves are large-amplitude, nonlinear pressure waves produced in a supersonic field or flow. The fluid passing through this discontinuity undergoes a finite decrease in velocity accompanied by a marked increase in pressure, density, temperature and entropy.

Although the concept of ► microchannel has been in the field literature for some time now, a clear definition of it has not yet been enunciated. However, it is the general understanding that any channel that has a characteristic dimension is between 1 μm and 1 mm is considered to be a ► microchannel. Most of the microchannels discussed in the literature are manufactured through microfabrication techniques, but not exclusively.

Overview

Since new and more complex microfabrication techniques became available, scientists have been trying to replicate at the microscale technologically more advanced systems and devices that have been available only at the large scale so far. During this process, it has been discovered that the laws of fluid mechanics and fluid dynamics do not necessarily scale linearly with the geometric dimensions. Although in the last ten years many questions have been answered regarding the behavior of fluid flow at the microscale, some phenomena still remain unclear. Among them is the phenomenon of ► shockwave propagation and compressibility effects inside a ► microchannel.

By its nature, the shockwave phenomenon happens in the microscale domain since the shockwave normal width is equal to a few mean free paths (less than a micrometer).

Basic Methodology

Estimates of pressure drops can be made using the traditional theory and correlations. However, accurate prediction of pressure drops in microchannels for non-slip flows is not possible [1]. For better prediction many models have been proposed [2]. Shockwave phenomena in microchannels have been investigated analytically, numerically, and experimental work is under way.



Shockwaves in Microchannels, Figure 1 One-dimensional model of a microchannel: (**a**) with shock traveling in the direction opposite to the flow; (**b**) with shock traveling in the direction of the flow

Knudsen Number

The ► Knudsen number Kn, defined as the ratio between the mean free path of the molecules and the characteristic length of the system, is often used to establish the domain level of the phenomenon and limits in the model application ranges. For Kn $\gg$ 1 the usual continuum modeling is valid. Satisfactory prediction of experimental results can be obtained until Kn $= 0.3$, but the question is raised as to whether it is possible to further extend the continuum modeling accounting more correctly for surface phenomena like the reflection law, and the Knudsen layer, or whether the validity limit of the continuum approach is reached here [3].

Analytical Modeling

A one-dimensional mathematical model based on basic physical background has been created to investigate the efficiency of shockwave compression in microchannels. The model considers the entropy produced by a single normal shockwave that runs through the channel and by the wall friction due to the gas flow through the channel. Entry losses are also taken into consideration. Only heat transfer is neglected, following a recent study [4] that shows no significant effect of heat transfer on the compression efficiency in silicon microchannels.

Focusing on the phenomenon occurring inside a single channel, the normal shockwave is modeled by gas dynamics for one-dimensional flow [5]. The model has been presented with air as working fluid modeled as an ideal gas, and a friction coefficient that varies along the channel as a function of gas-dynamic conditions. The microchannel geometric characteristics are length ($2L$) and hydraulic diameter (D_H, equal to 4 times the area divided by the perimeter of a section), shown in Fig. 1a. The model relates the efficiency of the compression process to the velocity, pressure, and temperature of the gas at the entrance of the channel (station 1: u_1, p_1, T_1), the pressure ratio across the shock Π_S, the friction coefficient f, and channel dimensions. In Fig. 1a, a shockwave is shown that moves in the opposite direction to the flow and is positioned in the middle of the channel. It can be shown that a snapshot evaluation at the mid position is a good representation of the overall results and does not affect the accuracy of the model. Friction is considered along the lengths L before and after the shock. The frictional effect is modeled as shear stress at the wall acting on a fluid with uniform properties over the cross-section.

One-Dimensional Flow with Friction

Using equations of one-dimensional compressible flow with friction, and knowing the conditions at station 1, the conditions at station 2, just before the arrival of the shockwave, can be obtained. Temperature and velocity at station 1 determine the speed of sound (Eq. (1)) and the Mach number (Eq. (2)):

$$a = \sqrt{\gamma \cdot R \cdot T} \tag{1}$$

$$\mathrm{M} = \frac{u}{a} \tag{2}$$

The Mach number at station 2 is found, by using the sonic condition as it would develop due to friction, from the state in station 1 through station 2, at the virtual distance from station 1 denoted with L_1^* (Eq. (3)), as can be derived from the momentum equation, expressing the shear stress in terms of friction coefficient and integrating between station 1 and the point where $\mathrm{M} = 1$ [5]:

$$L_1^* = \frac{D}{4 \cdot f}\left[\frac{1-\mathrm{M}_1^2}{\gamma \cdot \mathrm{M}_1^2} + \frac{\gamma+1}{2 \cdot \gamma} \cdot \ln\left(\frac{(\gamma+1)\cdot \mathrm{M}_1^2}{2+(\gamma-1)\cdot \mathrm{M}_1^2}\right)\right] \tag{3}$$

The classical theory of laminar flow relates the friction coefficient to be proportional to the Reynolds number:

$$f = \frac{64}{\mathrm{Re}} \tag{4}$$

The Reynolds number is dependent on density ρ, viscosity μ, velocity u, and hydraulic diameter (Eq. (5)):

$$\mathrm{Re} = \frac{\rho \cdot u \cdot D_H}{\mu} \tag{5}$$

Since the same sonic condition develops from the flow in station 1 and 2, the difference between the two virtual distances to sonic condition equals the distance L between both station 1 and 2:

$$L = L_1^* - L_2^* \tag{6}$$

Applying Eq. (3) to station 2 and substituting L_2^* from the Eq. (6), Eq. (3) can be solved for Mach number M_2. Pressure and temperature at station 2 then can be calculated with the continuity equation in adiabatic conditions, Eqs. (7) and (8), knowing M_2 and all conditions at station 1:

$$p_2 = p_1 \cdot \frac{\mathrm{M}_1}{\mathrm{M}_2} \cdot \sqrt{\frac{2+(\gamma-1)\cdot \mathrm{M}_1^2}{2+(\gamma-1)\cdot \mathrm{M}_2^2}} \tag{7}$$

$$T_2 = T_1 \cdot \frac{2+(\gamma-1)\cdot \mathrm{M}_1^2}{2+(\gamma-1)\cdot \mathrm{M}_2^2} \tag{8}$$

Jump Conditions Across a Moving Shock

Knowing T_2, the speed of sound a_2 (Eq. (1)) and then flow velocity u_2 can be calculated. Assuming that the distance between stations 2 and 3 is negligible, and knowing the pressure ratio across the shock $\Pi_S = p_3/p_2$, conditions at station 3 can be obtained by the normal shock relations (Eqs. (9) and (10)):

$$T_3 = T_2 \cdot \Pi_S \cdot \left(\frac{\frac{\gamma+1}{\gamma-1} + \Pi_S}{1 + \frac{\gamma+1}{\gamma-1} \cdot \Pi_S}\right) \tag{9}$$

From the three basic Euler equations, the Mach number of the shockwave, M_S, can be found:

$$\mathrm{M}_S = \sqrt{\frac{\gamma+1}{2\gamma} \cdot (\Pi_S - 1) + 1} \tag{10}$$

Further, the induced velocity of the flow behind the wave u_p can be calculated:

$$u_p = \frac{a_2}{\gamma} \cdot (\Pi_S - 1) \cdot \sqrt{\frac{\frac{2\gamma}{\gamma+1}}{\frac{\gamma-1}{\gamma+1} + \Pi_S}} \tag{11}$$

The velocity of the flow at station 3 is a vector sum of the initial velocity of the flow and the velocity induced by the moving shockwave:

$$\boldsymbol{u}_3 = \boldsymbol{u}_2 + \boldsymbol{u}_p \tag{12}$$

From station 3 to station 4, the same algorithm is applied as for the flow traveling from station 1 to station 2.

Since this is an unsteady process the total properties behind the shock at station 3 are different from the ones in front of the shock (station 2). The total pressure is calculated using the known properties of the induced mass motion instead of being directly calculated from the equation of state.

The isentropic efficiency of the compression process is defined as temperature difference for an isentropic process versus a real process:

$$\eta_C = \frac{\Delta T_S}{\Delta T} = \frac{\left(\frac{p_4}{p_1}\right)^{\frac{\gamma_{\mathrm{air}}-1}{\gamma_{\mathrm{air}}}} - 1}{\frac{T_4}{T_1} - 1} \tag{13}$$

Analytical Results

The model described has been applied to compressible air flow with Reynolds numbers in the range of 500 to 1500. These values were obtained using Eq. (5) that is also valid for shockwave propagation in a narrow channel [2]. Further, based on the analysis of gas flow characteristics in silicon microchannels [6], the friction coefficient f has been found to be approximately 0.04 for a Reynolds number of 500, while for Reynolds numbers greater than 1000, the friction coefficient becomes less than 0.005.

A variable friction coefficient is introduced dependent on Reynolds number and therefore indirectly dependent on viscosity and temperature. Using Eq. (13), the efficiency results for various entry temperatures and shock strengths have been calculated. For the reason that for a laminar flow at microscale the friction coefficient does not depend linearly on the Reynolds number [6], a second set of efficiencies for the same range of inlet temperatures has been presented using the experimentally obtained dependence of the friction coefficient on the Reynolds number. Both sets of efficiency results are represented in Fig. 2. The efficiencies obtained with the experimentally determined friction coefficient are about 10% higher than those obtained using the theoretical friction coefficient. For each pressure ratio across the shock, an optimum entry temperature can be found that results in the highest shockwave compression efficiency. Another observation that can be made is that the values of efficiency vary only a little with entry temperature, justifying the use of a constant friction coefficient determined for the inlet temperature. This effect is caused by the competing effects of the temperature in Eq. (3): higher temperature leads to lower Mach number for the same inlet velocity, but lower Reynolds number, thus higher friction coefficient. While the length/diameter ratio is an important parameter in shock tube design, its effect on the shock compression efficiency is not very significant over a wider range. However, at lower pressure ratios its effect is more considerable. For a shock strength $\Pi_S = 1.8$ the variation is only 3.3% for a diameter from $D_H = 30\,\mu m$ up to $100\,\mu m$ and a 1 mm channel length. Efficiency results are plotted in Fig. 3. The left graphs present the results versus length/diameter ratio with shock pressure ratio as parameter, while the graph on the right side is like a side view with the length/diameter ratio as parameter. On the right side the solid line connects the optimum pressure ratios for maximum efficiency for each length/diameter ratio. While in the application of the above described procedure the influence of heat transfer has been found negligible, under the presumption that shockwave motion at low Reynolds numbers is governed by convection as well as viscosity, another one-dimensional model that utilizes the Reynolds analogy for heat and momentum transfer could be applied to the phenomenon of shock and detonation attenuation in narrow channels [7].

Numerical Modeling and Simulation

Numerical Model

With the goal of simulating as best as possible the real-life conditions in a wave rotor channel (Fig. 4), a two-dimensional numerical model has been presented [8]. The channel modeled is 1 mm long and 76 µm wide and has a larger inlet duct (port) and opens into a larger outlet port. The mesh size in channels and inlet and outlet ports has been based on the results of a grid sensitivity study. A tetrahedral mesh is used with a 2 µm cell size for the channel and paved 10 µm cells for the inflow and outflow ports that sequence the flow through the channel. Air treated as a compressible ideal gas is used for modeling the flow.

Computational Fluid Dynamics (CFD) Results

The data trend of the above presented analytical study has been verified by computational fluid dynamics (CFD) analysis. Moreover, some microscale-specific effects could be seen: for the initial part of the process, the pressure drop is confined over a short distance (between stations 2 and 3 in Fig. 5a); as the shockwave travels further from the left to the right, the pressure gradient dissipates more and more continuously over a longer range. Instead of a well-defined shockwave, a set of compression waves can then be seen distributed over more than a half of the length of the channel (Fig. 5b). This effect has already been noted in experiments with microscale shock tubes [9], originating from the stronger influence of the viscous forces at low Reynolds numbers. In the den-



Shockwaves in Microchannels, Figure 2 Efficiency of shockwave compression process as a function of entry temperature for different shock strengths, and for a shock traveling in the opposite direction to the flow. Results obtained with analytical one-dimensional code



Shockwaves in Microchannels, Figure 3 Efficiency of shockwave compression process as function of microchannel length/diameter ratio for different shock strengths, and for a shock traveling in the direction of the flow. Results obtained with analytical one-dimensional code

sity contour plot (Fig. 6), the existence of the boundary layer can be seen clearly, behind the shockwave as soon as it has traveled about 20% of the channel length. Many more CFD simulations at the microscale exist and the numerical reproduction of the behavior of pressure-driven flows in microchannels has been obtained often [2, 10]. Some discrepancies have been found between numerical solutions of the Navier–Stokes equations and experimental data obtained in viscosity-dominated shock tube investigations. It was noticed that even using fine grid cells of a few micrometers, the solution of the Navier–Stokes equations still does not match experimental data of shockwave reflection transition over a wedge [2]. It has been pointed out that the solution of shockwave motion at low Reynolds numbers requires the finding of a two-dimensional unsteady solution of the Navier–Stokes equations and doubts are raised that the inclusion of transport phenomena as perturbations to a simple shock-tube flow would be adequate for a reliable flow description.

Numerical simulation might become a more efficient and economic way to analyze shock and flow phenomena at the microscale [2]. However, there is still a great need of experimental results to verify and support all the theoret-



Shockwaves in Microchannels, Figure 4 (**a**) Active components of conventional axial wave rotor. (**b**) Radial ultra-micro-wave rotor used to enhance a microfabricated gas turbine



Shockwaves in Microchannels, Figure 5 Static pressure inside a microchannel at two different time steps. Time = 1 is when a pressure wave reached the end of the channel. Flow moving from left to right

ical assumptions made in CFD and to establish reliable numerical models and schemes [2, 10].

Experimental Approach

Although the accuracy of present experiments is still not high enough to fully validate numerical models and solution schemes [2], more experimental investigations are needed in order to better understand the physics of shockwaves at the microscale. A good experiment will focus on trying to visualize the shock front, but a difficult task, besides obtaining good clarity, is recording the images. Although the geometric dimensions are scaled down, the shock velocities remain in the same high range; thus, the duration of shock travel is of the order of a microsecond for a channel length of 1 mm.

Despite the behavior of shockwave motion in large shock tubes at relatively high Reynolds numbers being extensively investigated in the 1950s and 1960s [2], little work has been done for low Reynolds number flows, especially at small scales. The experimental investigation of shock propagation in microchannels could provide valuable validation information on viscosity-dominated compressible flows. Two-dimensionality of the flow in channels is favorable for any validation effort. However, no shock visualization in microchannels has been published. Nevertheless, using the



Shockwaves in Microchannels, Figure 6 Density contours inside a microchannel. Time = 1 is when a pressure wave reached the end of the channel. Flow moving from left to right

Schlieren method for flow visualization to record the shock propagation has been successful down to a channel size of 3 mm × 3 mm cross-section and 42 mm length [11]. Investigations for microchannels are under way.

Single-Channel Experiment

Shockwave Visualization on 3 mm Wide Channels

At the University of Tokyo, the Schlieren method and a high-speed camera have been used for capturing images of the flow of a traveling shockwave in channels of 3 mm × 3 mm cross-section and 42 mm and 168 mm length. The channels were closed at one end and high-pressure air (250 kPa) was supplied at the other end by means of rotating ports. The effect of the transient opening was neglected during preliminary calculations and it was observed that it does not affect the shock propagation during the experimental investigations. Shockwave propagation speed has been reported as 300–400 m/s in both tubes. Interestingly, no boundary layer effects on the shock propagation or shockwave dissipation were observed. The wall friction effect seemed not to play an important role in the shockwave behavior [11].

Microchannel Experiments in Preparation for 90–720 μm Wide Channels

At Michigan State University a single-channel experiment has been developed to investigate the wave phenomenon. A set of similar channels have been designed in order to obtain more information on what the characteristic dimension is at which the shockwave behavior starts to deviate from macroscale theory. The channels have the same length/width ratio and same height; the length and width are varied (90 × 750 μm^2, 180 × 1500 μm^2, 360 × 3000 μm^2, 720 × 6000 μm^2), while the height is uniformly 360 mm. The channels are etched in a silicon wafer and closed on top with glass. The access ports are etched on the bottom side of the silicon wafer. Figure 7 shows photos of the silicon/glass microfabricated die. On the top side, the channels and the flow plenums can be observed, and on the bottom side, the access holes and the alignment marks can be seen. The quality of the geometry resulting from the microfabrication technique is impressive: even the smallest channel (90 μm in width) has crisp edges and a well-defined shape. Figure 8 shows SEM images of the four channels. In a first experiment with these micro-shock tubes, the channels are connected via access ports to stainless steel tubing (1.02 mm outer diameter) to a nitrogen supply tank. A quick release valve releases the nitrogen through the microchannel. Since the silicon wafer surface is highly reflective, reflection laser interferometry is used to capture the passing of the shockwave.

Microchannel Experiments in Preparation for 10 μm

A similar experiment is currently being designed at Sherbrooke University [12]. The goal is to build and test a true shock tube with two cavities filled with gases at different pressures, divided by a breakable membrane. The aspect ratio of the channel is 100 and a pressure ratio of 2 is planned for a Reynolds number of 100. These conditions could be achieved in a 5 mm diameter/500 mm long tube



Shockwaves in Microchannels, Figure 7 Silicon microchannels: (**a**) top view; (**b**) bottom view



Shockwaves in Microchannels, Figure 8 Different size channels visualized with SEM: (**a**) 90 μm and 180 μm wide channels; (**b**) 360 μm and 720 μm wide channels

with pressures of 1 mbar and 2 mbar, respectively. But the low pressures typically exclude the possibility for flow visualization or measurement. Therefore a more favorable solution is planned that will create the same hydrodynamic flow, using a micro-shock tube with a hydraulic diameter of 10 μm, operating at pressures close to atmospheric conditions.

The tube is created with a squared cross-section, 10 μm wide. The driver and driven section have equal lengths. The driver and driven sections are separated by a membrane, and the test section is pre-filled with the test gas during fabrication. The top side of the tube is made of a plate comprising direct-sensing piezoelectric gauges, used for timing the arrival of pressure waves.

Key Research Findings

Microscale Flow Phenomena

The overall conclusion is that while the currently available experimental data suggest the presence of microscale phenomena, they do not unequivocally identify the effects [1, 13]. In general it is found that the boundary layer effects are dominant at and below the microscale resulting in rarefaction effects in gaseous flow. However, the no-slip boundary condition appears to hold true less and less with smaller scale. The slip flow effect is seen to result in less frictional pressure drop than the continuum model predicts. Further it is widely pointed out that sudden increases in pressure (due to a shockwave) dissipate gradually when propagating through a microchannel due to high hydraulic resistance.

Compressibility and Rarefaction Effect

With the dominant occurrence of boundary layer effects in microchannel flow, in gaseous flows considerable decrease in density is observed with increasing flow length due to viscous dissipation [14]. This is also referred to as the rarefaction effect. Compressibility and rarefaction effects have been studied in three-dimensional gas flow with Reynolds number varying from 0.0001 to 1.2 and pressure ratio varying from 1.5 to 5.0, with the Knudsen number varying from 0.001 to 0.06 [3]. It has been found that the



Shockwaves in Microchannels, Figure 9 Non-slip versus slip-flow wall velocity

pressure drop for compressible flows exhibits an unusual nonlinear behavior as compared to that for incompressible flows. Especially at high pressure ratio (or Reynolds number) the compressibility effect becomes dominant although the Mach number may still be very small. So typically Knudsen number increases from inlet to outlet for compressible microchannel flow.

Isothermal Effect

At the microscale the time scales associated with heat loss mechanisms reduce dramatically. However, the characteristic time scales for heat release, governed by the deflagration process, remain fairly independent of scale [9]. In long, non-insulated microchannels, an isothermal flow assumption has been found accurate for Mach numbers $\mathrm{M} \ll 1/\sqrt{\gamma}$, where γ is the specific heat ratio [14]. Values of laminar Nusselt number increase with the cross-sectional aspect ratio and the surface roughness [15].

Slip Flow

With scale in particular, changes in fluid–surface interactions, such as the wetting ability of the fluid, can affect the ability of the fluid to exchange momentum with the surface at the atomic scale, resulting in a slip velocity v_{slip} at the solid wall as shown in Fig. 9 [16]. The slip length y_{Slip} gives the imaginary location behind the wall where non-slip condition with zero flow speed $v = 0$ would be found. Slip flow has been reported for both liquid and gaseous flow. Especially at $\mathrm{Kn} < 0.1$, the effect of slip flow has been seen resulting in reduced pressure loss gradient and hence increased mass flow rate. Deviations from Poiseuille flow predictions are not related to turbulence when Re is too low but to deviations from the no-slip boundary conditions. Increase in the mass flow for given inlet and outlet pressures for microchannel flows has been based on a perturbation expansion of the Navier–Stokes equations with a first-order correction of wall slip [14]. More factors regarding non-continuum effect, compressibility effect, and surface effects are presented in [17].

Friction Factor

Discrepancy between the conventional theory and the microchannel measurements of friction factor f in gaseous flow has been attributed to compressibility [6]. In general it appears that $f\mathrm{Re}$ for compressible slip flow is less than that for the incompressible case [3]. In a comprehensive study of results of microscale single-phase internal flows [1], it has been found that the only definitive conclusion that can be reached from the currently available data is that gaseous slip flow data indicate an approximate 60% reduction in f compared to macroscale theory at the same Re (while for laminar non-slip water flow f appears to be approximately 20% higher than the theoretical predictions). The finding for compressible slip flow seems to be supported by a simple analytical correlation with the factor $c \approx 0.6 \pm 0.05$ [3]:

$$\frac{(f\mathrm{Re})_{\mathrm{slip}}}{(f\mathrm{Re})_{\mathrm{non-slip}}} = \frac{D_{\mathrm{h}}}{D_{\mathrm{h}} + c} \tag{14}$$

The currently available experimental data for other types of flows are inconclusive, as they appear both above and below the theoretical predictions (although data for each researcher are consistently either greater or less than theoretical values). In part, these differences may be attributed to roughness of the channels, to lack of well-controlled surface structures, and to uncertainty in the determination of channel dimensions. Some researchers estimate the entrance effects in determining the microchannel friction factor, while, much better, the measurements should be taken within the microchannel near the channel entrance and exit. Further, preliminarily it has been concluded that, regarding non-slip microchannel flows, f appears to increase with surface roughness and this effect seems to intensify with higher surface roughness.

For $\mathrm{Re} < 700$, global pressure drop has been shown to be proportional to Re. For $\mathrm{Re} > 700$, it deviates from the linear relationship with the deviation dependent on Re. Also it has been found that f increases with the cross-sectional aspect ratio and the surface roughness [15].

Critical Reynolds Number

There is an ongoing debate regarding the critical Reynolds number R_{cr} for microfluidics at which the transition from laminar to turbulent flow starts. The determination of R_{cr} depends very much on the method used. R_{cr} varies widely from 300 to 2200 with it being mostly between 1500 and 1800 [1, 13].

Entry Lengths and Boundary Layers

It is the case that most flow investigations at the microscale happen in the laminar flow regime with developing boundary layer (combined entry lengths). As for macroscale cases, the velocity entry length L_E is often simply calculated by

$$\frac{L_E}{D_h} \approx 0.06\text{Re} \tag{15}$$

However, also larger factors of 0.08 and 0.09 [9] have been found for microchannels. The thermal entry length L_T may be calculated by

$$\frac{L_T}{D_h} \approx 0.05\text{RePr} \tag{16}$$

where Pr is the Prandtl number, a measure of diffusivity.

When investigating the boundary layer thicknesses, the Euler equations lead to specific solutions. The thermal boundary layer thickness is

$$\delta_T(x) = 3.6\sqrt{\frac{\alpha x}{u_\infty}} \tag{17}$$

where x is the coordinate along the channel and u_∞ is the velocity of the free stream.

The Reynolds analogy between the flow field and the thermal field provides the relation between the velocity and thermal boundary layer thickness:

$$\frac{\delta_T}{\delta} = 0.975\sqrt[3]{\text{Pr}} \tag{18}$$

Shockwave Phenomena at the Microscale

Dominant viscous and wall effects appear to influence considerably shockwave behavior at the microscale. Sudden increase in pressure (due to a shockwave) vanishes gradually in time due to hydraulic resistance [18]. So, it has been observed that, subsequent to the arrival of the shocks, the pressure increases continuously which is not conventional shock tube behavior [8, 9]. Also the decaying amplitudes of the shocks indicate that dissipation plays an important role. Therefore when waves are generated and propagated into ducts of small dimensions, diffusive transport phenomena, commonly ignored at conventional scales, can no longer be neglected. Viscous stresses at the boundaries lead to the deformation of the wave fronts, and heat conduction with the wall no longer allows the flow to remain adiabatic; at certain scales, molecular diffusion and adsorption may also lead to important effects.

It has been reported that for a given wave Mach number at small scales, the resulting particle velocities are lower but the pressures are higher [9]. Also, it has been shown that at small scales, the weak wave solution is no longer sonic and isentropic but is isothermal and can be subsonic.

Further, a model has been introduced that predicts via molecular diffusion phenomena an isothermal bow at small scales and that the minimum wave velocity can be subsonic. A parameterization of the shear stresses and heat flux at the wall has led to new jump conditions [9].

Experiments with a miniature shock tube using low pressures to simulate the effects of small scale have shown qualitative agreement with the proposed model. The effects of scale are even more pronounced than what has been predicted by the model. Experimental and numerical investigations for incident shock Mach number of $M = 1.2$ have shown significant viscous effects for channel heights below 4 mm even at atmospheric pressure. That shockwaves propagate more slowly at low pressures in a narrow channel has been confirmed, but they may propagate faster than in a wide channel because compression waves initiated from the entrance of the channel can strengthen the shockwave [2].

Micro-Shockwave Applications

Micro-Wave Rotors

The wave rotor is a pressure exchanger that uses the concept of direct energy transfer between fluids by waves. A basic wave rotor consists of a rotating drum with straight channels arranged around its axis. The drum lies between two end plates, each of which has a few ports or manifolds controlling the fluid flow through the channels. Figure 4 presents a schematic axial wave rotor drum and its end plates and inclusion in a microfabricated gas turbine. In the process of recent turbomachinery miniaturization it has been shown that a decrease of the overall thermal efficiency and output, and increase of losses are severe. While the wave rotor efficiency is based on the efficiency of the shockwave compression inside each channel, the influence of external losses can be minimal since the wave rotor itself is the only moving part and its rotation is only for the flow control. External losses are leakage, windage, friction in the bearings of the rotor, and if microfabricated losses due to sharp bends in the flow path to the rotor since rounded corners are difficult to obtain in the direction of etching. While all these losses also occur in turbomachinery, they can be lower in a wave rotor, since the compression process is only controlled but not determined by the rotational speed of the rotor. Therefore high efficiency can be obtained even at relative low rotational speed and relatively low flow speed, which implies less frictional losses as it becomes very important at small scale. It has been shown numerically that while the efficiency of a conventional radial compressor drops to about 50% when scaled down to millimeter size, the efficiency of shockwave compression has values around 70%. Two effects support this favorable outcome: shockwave entropy production is independent of scale and wave rotors can work with relatively low flow speeds (while the compression is realized by shockwaves that travel at much higher speed than the flow speed).

The results of the previously described analysis show that the efficiency depends not only on pressure gain across the shockwave traveling through the wave rotor channel, but also on the friction coefficient for the channel geometry. According to the model, shorter wave rotor channels with larger diameter allow a higher compression efficiency of the wave rotor. The temperature at which the compression process is initiated also has a considerable influence: higher temperatures yield higher efficiencies. Analytical and numerical results suggest that a shockwave compression efficiency of 70–80% can be achieved in the channels. If the inlet temperature is high enough (about 1500 K), the efficiency is predicted to be even higher, up to 90%. Moreover, the wave rotor, due to its geometry, is ideal for microfabrication processes. Its mainly two-dimensional shape is easy to construct at the microscale, where most of the fabrication techniques rely on etching and deposition [4].

Shock Tube as Vaccine Delivery System

An unique form of powder delivery system, a biolistic system, has been developed [19]. This novel technology accelerates microparticles by a gas flow behind a traveling shockwave, so that they can attain sufficient momentum to penetrate the skin and thus achieve a pharmacological effect. One of the most recent developments is a mouse biolistic system, used in immunological studies. These studies require powdered vaccine to be delivered into the epidermis of the mouse with a narrow and highly controllable velocity distribution and a uniform spatial distribution. The preliminary results demonstrate the overall capability of a newly designed supersonic nozzle to deliver the particles to the skin targets with a more uniform velocity and spatial distribution. CFD has been utilized to characterize the complete operation of a prototype mouse biolistic system.

Micronozzles

The Mach number near the downstream position of a micronozzle's throat is lower than that in a conventional nozzle. In the divergent region of the micronozzle, there is a supersonic area instead of the shockwave that usually occurs in conventional-scale nozzles. Results of numerical simulations also show that the position of the sonic point moves away from the throat towards the outlet with a decrease in the size of the nozzle. This particular behavior is attributed to the higher viscous dissipation in micronozzles as compared to that in conventional-scale nozzles [20].

Future Directions for Research

Recent medical and industrial applications of shockwaves necessitate a better understanding of shockwave motion at low Reynolds numbers: for example, shock motion in very small tubes ($r < 1$ mm) and micrometer-size particles moving at a supersonic speed [2]. Along with this comes a clear need for additional experimental investigations over a wider Re range using microchannels with well-characterized dimensions and surface roughness and well-designed experimental methods in order to understand microscale single-phase internal fluid flow [1]. To enhance the accuracy, flow visualization may focus on a local region instead of the whole test section, and more sensitive and precise pressure transducers for measuring weak shockwaves at low initial pressures are necessary [2]. Wave rotors are a promising technology that uses unsteady waves in an instant self-cooled dynamic pressure exchange between fluids. For high-pressure, high-temperature topping cycles, it results in an engine overall pressure ratio and temperature increase which in turn generates higher efficiency and lower specific fuel consumption. Further applications are pressure wave-driven pumps. Most advanced embodiments are wave discs engines that do not need any other rotating parts beside the wave disc self. They appear to be superior in simplicity and power density [21].

Cross References

- ► Micro and Nanoscale Gas Dynamics
- ► Microscale Flow Visualization
- ► Supersonic Micro-Nozzels
- ► Microturbines
- ► Micro-wave rotor
- ► Pressure-Driven Single Phase Gas Flows

References

1. Papautsky I, Ameel T, Frazier AB (2001) A Review of Laminar Single-Phase Flow in Microchannels. ASME International Mechanical Engineering Congress and Exposition, New York
2. Sun M, Ogawa T, Takayama K (2001) Shock Propagation in Narrow Channels. ISSW23, Fort Worth, Texas
3. Jain V, Lin CX (2006) Numerical Modeling of Three-Dimensional Compressible Gas Flow in Microchannels. J Micromech Microeng 16:292–302
4. Iancu F (2005) Integration of a Wave Rotor to an Ultra-Micro Gas Turbine (UμGT). Michigan State University, East Lansing

5. Anderson JD (2003) Modern Compressible Flow With Historical Perspective. McGraw-Hill, New York
6. Ying-Tao D, Zhao-Hui Y, Meng-Yu S (2002) Gas Flow Characteristics in Straight Silicon Microchannels. Chin Phys 11(9):869–875
7. Thomas GO, Brown CJ, Teodorczyk A (2000) Shock and Detonation Attenuation in Narrow Channels. Experiments in Fluids. Springer, Berlin
8. Iancu F, Müller M (2006) Efficiency of Shock Wave Compression in a Microchannel. J Microfluid Nanofluid 2:50–63
9. Brouillette M (2003) Shock Waves at Micro Scale. Shock Waves 13:3–12
10. Colin S (2005) Rarefaction and Compressibility Effects on Steady and Transient Gas Flows in Microchannels. J Microfluid Nanofluid 1:268–279
11. Okamoto K, Nagashima T, Yamaguchi K (2006) Propagating Shock Waves in a Narrow Tube from the Viewpoint of Ultra Micro Wave Rotor Design in 11th International Symposium on Unsteady Aerodynamics, Aeroacoustics and Aeroelasticity of Turbomachines, 4–8 Sept 2006, Moscow, Russia, pp 421–433
12. Mirshekari G, Brouillette M (2006) Towards a Microfabricated Shock Tube. In: 25th International Symposium on Shock Waves. Bangalore, India
13. Hetsroni G, Mosyak A, Pogrebnyak E, Yarin LP (2005) Fluid Flow in Micro-channels. Int J Heat Mass Transf 48:1982–1998
14. Arkilic EB, Schmidt MA, Breuer KS (1997) Gaseous Slip Flow in Long Microchannels. J Microelectromech Syst 6(2):167–178
15. Hao PF, He F, Zhu KQ (2005) Flow Characteristics in a Trapezoidal Silicon Microchannel. J Micromech Microeng 15:1362–1368
16. Choi CH, Westin JA, Breuer KS (2003) Apparent Slip Flows in Hydrophilic and Hydrophobic Microchannels. Phys Fluids 15(10):2897–2902
17. Takuto A, Soo KM, Hiroshi I, Kenjiro S (2000) An Experimental Investigation of Gaseous Flow Characteristics in Microchannels. In: International Conference on Heat Transfer and Transport Phenomena in Microscale, Banff, Canada
18. De Bruyker D, Puers R (2001) Experimental Characterization of the Reference Channel of a Differential Pressure Sensor Using Pressure Shock Waves. J Micromech Microeng 11:390–396
19. Liu Y, Truong NK, Kendall MAF (2004) Numerical Studies of Contoured Shock Tube for Murine Powdered Vaccine Delivery System. In: 15th Australasian Fluid Mechanics Conference, Sydney, Australia
20. Hao PF, Ying-Tao D, Zhao-Hui Y, He F (2005) Size Effect on Gas Flow in Micro Nozzles. J Micromech Microeng 15:2069–2073
21. Piechna J (2006) Feasibility Study of the Wave Disk Micro-Engine Operation. J Micromech Microeng 16:S270–S281

Shunt Capacitance

Synonyms

Low-frequency capacitance; DC capacitance

Definition

The capacitance associated with the low-frequency response of a system all the way down to direct current (DC).

Cross References

► Piezoelectric Microdispenser

Signal Attenuation

► Frequency Response

Silicon Dioxide Growth

► Oxidation (of Silicon)

Silicon Etching

► Anisotropic Etching
► Silicon Micromachining

Silicon Micromachining

JIANMIN MIAO
Micromachines Centre, School of Mechanical
and Aerospace Engineering, Nanyang Technological
University, Singapore, Singapore
mjmmiao@ntu.edu.sg

Synonyms

Anisotropic silicon etching; Deep reactive ion silicon etching; Electrochemical etching; Isotropic silicon etching; Selective silicon etching; Silicon etching; Surface micromachining

Definition

Silicon micromachining concerns a process that involves the removal of silicon materials using wet chemical or dry plasma process in order to create 3-D silicon or non-silicon microstructures for making functional devices such as micro-sensors, micro-actuators, biochips, etc.

Overview

Silicon is a well-known single crystalline semiconductor material, which is widely used in integrated circuits (ICs). Silicon possesses excellent mechanical properties, which surpass stainless steel in yield strength and hardness with good mechanical stability. Silicon also has a high piezoresistance effect, whose resistivity changes when mechanical loads or stresses are applied to it. This makes silicon a good candidate for various mechanical sensor applications. By combining micromachining technologies, its outstanding properties have made silicon a successful material not only for integrated circuits, but also for Micro-Electro-Mechanical Systems (MEMS), micro-fluidic components, optical devices, and other applications.

In general, silicon micromachining technologies can be classified as follows: wet bulk-micromachining, reactive ion etching (RIE), deep reactive ion etching (DRIE), surface micromachining, and laser micromachining. During the micromachining process, only the surface area, which will be etched away, is exposed to the etchants, such as wet chemicals or gases, while the rest of the silicon surface is protected by the so-called etching masking layer.

Silicon has a diamond cubic crystal structure. The Miller indices of the main crystallographic planes of silicon are (100), (110) and (111), respectively. In the wet bulk-micromachining, there are two silicon etching methods: isotropic (direction-independent) and anisotropic (direction-dependent) etching. Wet chemical etching solutions are used in this bulk silicon micromachining technology.

In the reactive ion etching, silicon is isotropically etched in plasma gases. Its silicon etch rate is relatively low and orientation-independent.

The deep reactive ion etching technology, also called Bosch process, uses the concept of alternate etch and passivation steps to achieve high aspect ratio (depth to width ratio of microchannel) silicon deep micromachining. In this process, silicon can be deeply micromachined, even through the whole wafer of few hundreds micrometers with aspect ratio as high as 30 to 1, without considering the wafer orientation.

Basic Methodology

Wet Silicon Bulk-Micromachining

This micromachining technique has been used for more than two decades and is the most popular fabrication technology for sensors such as pressure sensors and accelerometers [1]. In this bulk-micromachining, chemical etching solutions are used to shape the microstructures by the removal of a large amount of single crystalline silicon substrate. Thin films, acting either as etching mask materials or microstructure materials, are deposited/grown and patterned on the silicon substrate. KOH (Potassium Hydroxide), EDP (Ethylenediamine Pyrocatechol) or TMAH (Tetramethyl Ammonium Hydroxide) are commonly used as chemical etching solution for anisotropic micromachining of silicon materials, while the NHA ($HF-HNO_3-CH_3COOH$) solution performs the isotropic etching of silicon wafers. Thin films, such as SiO_2 and Si_3N_4 with a thickness ranging from few tens nanometers to few micrometers, are the common materials serving as etching mask layers, which can also be used as structure materials for sensors or actuators after silicon bulk-micromachining. The dielectric materials, SiO_2 and Si_3N_4, can be deposited either by low pressure chemical vapor deposition (LPCVD) or plasma-enhanced chemical vapor deposition (PECVD). Additionally, SiO_2 thin film can be also grown by thermal oxidation on the silicon substrate.



Silicon Micromachining, Figure 1 Schematic of cross sectional view of isotropically etched silicon microchannels using wet chemical etchants of NHA

Isotropic etchants etch in all crystallographic directions at the same rate; they usually are acidic, such as NHA, and lead to rounded isotropic features in single crystalline silicon as shown in Fig. 1. The basic chemical reaction equation is described as follows:

$$\begin{aligned} &Si + HNO_3 + 6HF \\ &\rightarrow H_2SiF_6 + HNO_2 + H_2O + H_2 \text{ (bubbles)} \end{aligned}$$

The etch rate can be as high as $5\,\mu m\,min^{-1}$ at room temperature, and is very temperature-dependent. At 50°C, the etch rate is increased to about $50\,\mu m\,min^{-1}$ [2].

Anisotropic etchants shape desired microstructures in single crystalline silicon material by etching much faster in one direction than the others. ► Anisotropic etching results in geometric shapes bounded by the slowest etching and perfectly defined crystallographic planes. By using KOH chemical etching solution, the etch rate in the <100> orientation is much higher than that in the <111> direction, up to 400:1. If holes, membranes, groove-type microchannels, pits, etc., have to be etched in silicon, then wafers are taken with surface orientation (100) and (110), depending on the required shape of the etched structures. Figure 2 shows some etch shapes in these two wafers. Parts of the wafers are covered with an etch mask, and the exposed areas are etched. For wafers of <100> surface orientation, etching proceeds along (100) planes, which intersects the surface along the mask edges. If the mask opening is a square with a side that is small compared to the etching depth, then a pyramidal pit is formed, which is defined by four (111) planes, i. e. it will virtually stop. The angle between the <100> and <111> directions is 54.74 degrees.



Silicon Micromachining, Figure 2 Schematic of cross sectional view of anisotropically etched microchannels (**a**) in (100) silicon, (**b**) in (110) and (**c**) of 3-D aerial view of anisotropically etched microchannels in (100) silicon using wet chemical etchants of KOH, EDP or TMAH

In <110> wafers, the (111) planes are vertical, and deep trenches with high aspect ratio can be etched since silicon in the <111> direction will not be etched.

The commonly used anisotropic etchants are KOH, EDP and TMAH. KOH added with water is the most popular silicon anisotropic etchant. At 80 °C with 50 wt% KOH, the etch rate of (100) silicon can achieve 1.4 μm min^{-1} with smooth silicon etching surface. The etching selectivity between (100) and (111) silicon is up to 400:1. However, the etching selectivity between Si and SiO_2 is not very good in KOH, as it etches SiO_2 too fast. So, SiO_2 is not a good choice as etching mask of silicon in KOH. The best candidate as etching mask is Si_3N_4. One disadvantage of KOH is its incompatibility with IC fabrication processes. Therefore, for MEMS with integrated circuits, the IC fabricated steps will be processed first and followed by the wet bulk-micromachining in KOH to create MEMS microstructures.

EDP etching solution doesn't contain sodium or potassium and therefore, it is IC compatible. EDP has also very high etching selectivity of 5000:1 between Si and SiO_2, which is a good etching mask for silicon etching. The etch rate can reach 1 μm min^{-1} in EDP, however its etching selectivity of 35 to 1 between (100) and (111) silicon is relatively low. Furthermore, EDP contains pyrocatechol, which is described as a corrosive toxic.



Silicon Micromachining, Figure 3 Schematic of cross sectional view of highly boron-doped silicon (**a**) cantilever, and (**b**) membrane. The anisotropic etching stops at the highly boron-doped (100) silicon layer by using wet chemical etchants of KOH, EDP or TMAH

TMAH is more compatible with CMOS IC processes than KOH and also neither toxic nor harmful. The etch rate of (100) silicon in TMAH can achieve about 0.7 μm min^{-1}, but its etching selectivity of (100)/(111) silicon is quite low, which is between 12.5 and 50.

For some applications, especially for the microfluidic devices, the etched surface quality of micromachined microchannels is very important. In general, isotropic etching generates smooth etched surface. However, anisotropic etchants leave rough etched surface. A highly concentrated KOH is preferred to obtain a smooth surface. In some cases, a post polishing process after KOH etching can be adopted by using slight isotropic etching to obtain a smooth surface.

If silicon is highly doped, particularly with boron, then silicon will be etched very slowly by the previously mentioned wet chemical etchants such as KOH, EDP or TMAH. One can use ion-implanting or diffusing boron into silicon to form a thin etch-stop layer. Since non highly-doped silicon will be etched very fast, this thin etch-stop layer will stay as a free-standing membrane, bridge or cantilever, depending on its shape patterning, as illustrated in Fig. 3. Such dopant-dependent selective etching techniques have led to the development of pressure sensors, accelerometers and microphones [3] with great commercial success.

The most appropriate technique to make low-doped, single crystalline silicon membrane-type microstructures with



Silicon Micromachining, Figure 4 Schematic drawing of experimental set-up for electrochemical etching of p-type (100) silicon. The etching stops at p-type and n-type silicon interface



Silicon Micromachining, Figure 5 Schematic drawing of a typical reactive ion etching (RIE) system

well-controlled dimension and thickness is the electrochemical etch-stop on a diffusion or an epitaxial layer as shown in Fig. 4. In this silicon micromachining technique, a positive voltage is applied to one n-type side of a p-n junction of a wafer in an etch bath of a strong alkaline solution such as EDP or KOH. A platinum cathode is connected to the negative voltage and immersed in the etching solution. The etching proceeds as normal wet chemical etching until the exposed side of the p-n junction is completely etched away, which means that the etching stops exactly on the n-type silicon layer to release the diaphragm. In this case, only a low-doped layer is sufficient for the etch stop. Compared to the heavily-doped layer produced by purely chemical etching, silicon membranes micromachined by the electrochemical etching have much less mechanical stress.

Reactive Ion Etching of Silicon

In microelectronic fabrication processes, plasma etching is used to create the patterns of silicon-based thin films (silicon dioxide, silicon nitride, polysilicon). This etch process is performed in the vacuum chamber. By adding etch gases excited by radio frequency (RF) power, plasma is generated in the chamber, where silicon wafers are located. The exposed silicon surface is reacted with plasma gases and then removed layer by layer by this so-called reactive ion etching (RIE) technique. The schematic diagram of the RIE system is illustrated in Fig. 5. Since there is no wet chemical etching solution to be involved, this process is also called dry etching process. Assisted by the energetic plasma ions, fluorine gases, such as SF_6, CHF_3 and CF_4, are the etching gases for silicon-based thin films of SiO_2, Si_3N_4 and polysilicon, which are to be removed or patterned to form the desired shapes of microstructures.

By adding small amount of O_2 gas, the etch rate can be accelerated. In general, in this approach, the etch rate is relatively small, and in the range of few nanometers to tens nanometers per minute. The RIE process is not applicable for bulk material micromachining and therefore, it is suitable only to etch thin films with thickness of few micrometers. However, RIE is a suitable process to etch shallow microchannels in silicon substrate with good etch depth control.

Silicon Surface Micromachining

In this technique, thin layers, such as polycrystalline silicon, SiO_2 and Si_3N_4, will be deposited on the silicon wafer, which serves as a supporting substrate and may contain integrated circuits. The silicon substrate is protected by the etch-resistant film, for example thermal silicon dioxide or LPCVD silicon nitride, grown or deposited on the silicon substrate. A sacrificial layer of low temperature oxide (LTO), phosphosilicate glass (PSG) or borophosphosilicate glass (BPSG) is then deposited and followed by the deposition of LPCVD polysilicon, which is used as microstructures, typically for comb-drive structures, and normally patterned by RIE or DRIE technology [4].

In this approach, the bulk silicon substrate is not etched away, but only the sacrificial layer between the silicon substrate and the polysilicon microstructures is removed by lateral under-etching using the selective wet etchant of HF or BOE. Such etching solutions do not have any etching effect on the polysilicon film. Figure 6 illustrates the process steps to fabricate a polysilicon cantilever.

The surface micromachining technique is a CMOS-compatible process and has some advantages over the bulk-micromachining one. The most popular microstructure is the so-called comb-drive structures as shown in Fig. 7. Several commercially available sensors with integrated circuit on chip have been developed by using


Polysilicon
SiO_2
Silicon substrate
a
Polysilicon cantilever
Silicon substrate
b

Silicon Micromachining, Figure 6 Fabrication steps of a polysilicon cantilever using surface micromachining. (**a**) Deposition of SiO_2 on silicon substrate, followed by polysilicon, whose shape is etched by DRIE or RIE, and (**b**) generation of polysilicon cantilever after removal of the sacrificial SiO_2


Movable beam electrode
Movable seismic
Tether
Anchor
Fixed electrode
Displacement

Silicon Micromachining, Figure 7 Schematic plan view of a MEMS device with comb drive structure

this technique such as accelerometers, gyroscopes, microphones, etc.

Instead of deposition of different thin films, silicon-on-insulator (SOI) micromachining may surpass the poly-Si surface micromachining technology for fabricating high performance devices. Figure 8 shows the process steps to fabricate a comb drive structure using SOI wafer. The single crystalline silicon device layer, whose thickness ranges from few to 100 μm, can be obtained by epi-silicon or fusion-bonding on a thin SiO_2 insulating layer. The top silicon device layer can be micromachined by RIE for thin layer and then followed by wet sacrificial etching of the buried SiO_2 layer by BOE for the structure release. Microstructures made from these single crystalline Si layers result in more reproducible and reliable sensors and other MEMS devices. Figure 9 presents a fabricated comb drive structure based on SOI surface micromachining.


Silicon device structure
SiO_2
Silicon substrate

Silicon Micromachining, Figure 8 Illustration of the comb-drive structure in SOI (silicon-on-insulator) wafer fabricated using surface micromachining


SE 20-Sep-01 20.0kV x350 100um

Silicon Micromachining, Figure 9 Scanning electron microscope (SEM) photograph of comb-drive structure in SOI (silicon-on-insulator) wafer fabricated using DRIE and surface micromachining

Deep Reactive Ion Etching of Silicon

Microchannels and holes can be micromachined using wet chemical etching. However, as geometries of micro-device components get smaller, the requirement to etch silicon microchannels with vertical profile becomes important. An increase in aspect ratio for microstructures (for example microchannel) is desirable because more devices can be made from the same size of silicon substrate, and also lead to enhanced device characteristics.



Silicon Micromachining, Figure 10 Illustrations of deep reactive ion etching process by time-multiplexing scheme. (**a**) Silicon is isotropically etched using SF_6 etching gas, (**b**) Polymer is deposited on the trench sidewall and bottom using C_4F_8, (**c**) At the beginning of following etch cycle, the bottom polymer is removed by etching gas ions, (**d**) In the remaining etching cycle, silicon is then further isotropically etched using SF_6 etching gas, forming the scallop sidewall



Silicon Micromachining, Figure 11 Scanning electron microscope (SEM) photograph illustrating high aspect ratio and vertical silicon trenches etched by DRIE



Silicon Micromachining, Figure 12 Scanning electron microscope (SEM) photograph illustrating the DRIE etched silicon with sidewall scallops of 50 nm

Laermer and Schilp of Robert Bosch GmbH originally invented a fluorine-based chemistry process [5], which maintains verticality (anisotropy), by using the concept of alternate etch and passivation steps, which is also called the time-multiplexed deep etching (TMDE) [6].

The TMDE technique utilizes an etching cycle flowing only SF_6 (steps b and d in Fig. 10), which is similar to the normal reactive ion etching process, and then switching to a sidewall passivating cycle using only C_4F_8 (step c in Fig. 10). During the subsequent etching cycle, the passivating film is preferentially removed only from the bottom of the trenches due to vertical ion bombardment, while preventing etching of the sidewalls, which are covered by the passivating layer.

To achieve a high etch rate, a high power inductively coupled plasma (ICP) source is used in the DRIE system. The etch rate can now reach up to $50\,\mu\mathrm{m\,min}^{-1}$. The etching process is carried out at room temperature. Photoresist and SiO_2 can be used as etch mask with silicon etching selectivity up to 150:1 and 400:1, respectively. Compared to the wet chemical micromachining of silicon, the DRIE process is direction-independent. Any planar shapes of microstructures can be created while the wet anisotropic etching can only etch rectangle holes on (100) plane.

Key Research Findings

The aspect ratio of the microtrenches is defined as the ratio of the trench depth to the trench width. DRIE can easily reach an aspect ratio of 30. With special recipe and high plasma power, the highest aspect ratio can reach as high as 100 [7]. The smallest feature size is dependent of the patterning capability. Using the normal optical lithogra-



Silicon Micromachining, Figure 13 Scanning electron microscope (SEM) photographs and atomic force microscope (AFM) measurement results showing the improved surface roughness of DRIE etched silicon sidewall by thermal oxidation process, (**a**) after DRIE, (**b**) after thermal oxidation, and (**c**) after removal of oxide layer

phy, 2 μm high aspect ratio silicon beams can be deeply micromachined with almost vertical angle as shown in Fig. 11. Associated with the DRIE process, the etch rate is feature-size dependent, which leads to the RIE-lag effect. Smaller feature size results in a lower etch rate. Due to the nature of the time-multiplexing of etch-passivation process, rough wave-shaped features (called scallops) appear on the etched sidewall. The roughness is about 50 nm as observed in Fig. 12. However, if the etch depth is more than 200 μm, the sidewall is much rougher due to the micromasking effect of the passivation layer of polymer. The rough sidewall surface can be smoothed by the thermal oxidation and oxide removal as indicated in Fig. 13.

Silicon material is not bio-compatible. The microchannels, which are micromachined by DRIE, RIE or wet chemical etching, can be coated with silicon oxide by the thermal oxidation process as shown in Fig. 14. For bio-chip applications [8], using silicon is not a cost-effective solution. However, one can use micromachined silicon structures as micro-molds for the polymer, PDMS or silicone replications. In this case, the sidewall of the small trenches needs to be coated with a special thin layer for easy demolding of microstructures [9].



Silicon Micromachining, Figure 14 Cross sectional scanning electron microscope (SEM) of silicon microbeams coated with thermally grown SiO_2

Future Directions for Research

Silicon micromachining technology is important in the fabrication of micro- and nanofluidic chips, MEMS/NEMS and other miniaturized devices [10]. Deep reactive ion etching opens new research opportunities for high aspect ratio silicon-based micro- and nanostructures for various applications. The etch rate needs to be increased to reduce the process time and costs. Further study should be focused on smoothing rough sidewalls of DRIE etched silicon microchannels in order to reduce the fluidic resistance. Ultra high aspect ratio micromachining technology needs to be further developed to fabricate silicon nanostructures. Furthermore, a new challenge will be on how to use surface micromachining, which is a compatible process with integrated circuits, for the integrated micro- and nanofluidic applications.

Cross References

- ▶ Anisotropic Etching
- ▶ Anodic Bonding
- ▶ Bulk Micromachining
- ▶ Fabrication of 3-D Microfluidic Structures
- ▶ Heat Transfer in Microchannel Flows
- ▶ Isotropic Etching
- ▶ Lab-on-a-Chip (General Philosophy)
- ▶ Laser Based Micromachining
- ▶ Magnetic Pumps
- ▶ Mechanical Nanosensors
- ▶ Membrane Actuation for Micropumps
- ▶ MEMS-Based Biosensor
- ▶ Microactuators
- ▶ Microfabrication Techniques
- ▶ Microfilters
- ▶ Micromolding
- ▶ Microneedles – Applications & Devices
- ▶ Supersonic Micro-Nozzles
- ▶ Nanochannel Fabrication
- ▶ NEMS-Based Biosensors
- ▶ Oxidation (of Silicon)
- ▶ Photolithography
- ▶ Plasma Etching
- ▶ Powder Blasting
- ▶ Reactive Ion Etching (RIE)
- ▶ Wafer Bonding

References

1. Petersen KE (1982) Silicon as a Mechanical Material. Proc IEEE 70:420–457
2. Schwartz B, Robbins H (1961) Chemical Etching of Silicon-III: A Temperature Study in the Acid System. J Electrochemical Soc 108:365–372
3. Sessler GM (1996) Silicon Microphones. J Audio Eng Soc 44:16–22
4. Howe RT, Muller RS (1982) Polycrystalline Silicon Micromechanical Beams. Spring Meeting of the Electrochemical Society, Montreal 184–185
5. Laemer F, Schilp A (1996) Method of Anisotropically Etching Silicon Robert Bosch GmbH: U.S. Patent 5,501,893.
6. Ayón A, Braff R, Lin CC, Sawin HH, Schmidt MA (1999) Characterization of a Time Multiplexed Inductively Coupled Plasma Etcher. J Electrochemical Soc 146(1):339–349
7. Marty F, Saadany B, Bourouina T, Mita Y, Shibata T (2005) High Aspect Ratio Nano-structures (HARNS) for Photonic MEMS Based on Vertical DBR Architecture. Digest of Technical Papers – International Conference on Solid State Sensors and Actuators and Microsystems Transducers '05, Seoul 1 384-387
8. Chen PJ, Shih CY, Tai YC (2006) Design, fabrication and characterization of monolithic embedded parylene microchannels in silicon substrate. Lab Chip 6:803–810
9. Gao J, Yeo LP, Chan-Park MB, Miao J, Yan Y, Sun J, Lam YC, Yue CY (2006) Anti-stick post-passivation of high aspect ratio silicon molds fabricated by deep reactive ion etching. J Microelectromech Syst 15:84–93
10. Madou MJ (2002) Fundamentals of Microfabrication: The Science of Miniaturization. CRC Press LLC, Boca Raton

Simulating Migration of Polymer Chains, Methods

GREG WALKER
Department of Mechanical Engineering, Vanderbilt University, Nashville, TN, USA
greg.walker@vanderbilt.edu

Synonyms

Macromolecular transport; Active particle flows; Brownian dynamics

Definitions

Polymer chains are long flexible molecules usually associated with organic molecules such as DNA. Their transport is important to many medical screening applications and can be described using Monte Carlo or molecular dynamics approaches.

Overview

The motion of large molecules in microfluidic flows is important because the trajectories of particles in shear flows do not always follow the local flow field. Therefore, a knowledge of the fluid dynamics is not sufficient to completely describe the motion of the particles. When a suspended particle does not track the flow, the particle is said to be active as opposed to passive. The dynamics of active particles are particularly interesting in microfluidic devices because the molecules of polymer chains can approach – and even exceed – the characteristic lengths of the device. Consequently, the deviations between the particle/molecular motion and the fluid motion can be significant.

While active particle dynamics can address the motion of any suspended particle in a fluid, microfluidic researchers are usually interested in polymer chains because these structures in general do not follow the fluid flow, have a high degree of flexibility, and model important biological subsystems such as DNA and many types of proteins. If we want to track or manipulate different polymer chains in a microfluidic system, we need to understand their dynamics relative to the fluid flow. However, not only will the bulk motion deviate from what the fluid is doing, but also their conformation or shape can change, which alters the transport properties. In other words, as polymer chains travel in a fluid system, the inherent flexibility of the chains allow them to bunch up, stretch out or tumble in the flow. As the shape of the chain changes, the fluid forces imposed on the chain will also change. As a result, the motion of a flexible chain will vary even if the flow field remains constant. For microfluidic systems designed to sequence or hybridize DNA, for example, the conformation can be as important as the trajectory of bulk motion of the molecule.

Basic Methodology

The adjective *macromolecular* is often used to describe transport of molecules in systems as opposed to transport within a molecule. This distinction can be important because some of the same methods can be used to treat both systems. Depending on the size of the system, two general methods could be used to describe molecular motion in a fluid.

1. Molecular dynamics is a fundamental approach that requires only the knowledge of forces between individual atoms. This approach is useful only for the smallest microfluidic systems because modern computational architectures can only handle a few million atoms and a single nanoliter of water contains over 10^{16} atoms.
2. Brownian dynamics approximates a molecule as a structure with limited degrees of freedom and with continuum forces. This approach is useful for multiscale simulations, which are characteristic of the vast majority of microfluidic systems. With this approach we no longer have to simulate each individual atom, but approximate the force due to a large group of atoms.

Molecular Dynamics

Molecular motion can theoretically be described using molecular dynamics. In this context, molecular dynamics describes the motion of a molecule in a fluid by accurately characterizing the force between any two atoms in the system including the molecules of the surrounding fluid. All forces in the system are summed and Newton's law is applied to each atom to deduce its individual motion. The motion of the molecule is deduced from the motion of its constituent atoms. Because of its fundamental nature, a molecular dynamics approach is often considered ab initio or "from first principles", meaning that there are virtually no fitting parameters required to obtain a physical solution. Nevertheless, the force between atoms, or ►inter-atomic potential, arises from a variety of chemical interactions (Van der Walls' force, chemical bonding, electrostatic) and in general, is difficult to characterize. (Discussion of the different potential fields and their application is beyond the scope of this article, but it should be noted that inter-atomic potentials often contain approximations and non-physical fitting parameters, so the ab initio designation is not always appropriate.)

Applications for molecular dynamics in microfluidic systems include, for example, protein folding in solution, transport of amino acids in ion channels, and locally driven electro-osmotic flows with rigid particles. However, these applications do not involve the bulk motion of a fluid and are extremely small, specialized systems. In general, the systems that microfluidic researchers consider are multi-scale in that they require knowledge of the bulk fluid motion, far-field boundary conditions, interactions with other molecules, walls and fluid structures, and other experimental conditions. Consequently, the molecular dynamics approach is rarely feasible or even necessary for multi-scale systems. Instead, researchers and analysts rely on ►coarse-graining techniques to reduce the degrees of freedom, where tractable solutions are more accessible.

Coarse-Grained Models

By coarse-graining, the molecular system is discretized and treated as a bead/spring system or bead/rod system. In the case of the bead/spring system, the molecule is treated as a series of beads with mass and size connected by springs. In the case of the bead/rod model, the molecule is treated a series of massless beads connected by rigid rods. The bead/spring system is simpler, but can allow the molecule to cross, which is unphysical, and is susceptible to computationally unstable solutions. The bead/rod model is mathematically and computationally more difficult, but the motion is often more realistic. In either case, the discretization or the number of beads used to model the chain is somewhat arbitrary but is chosen so that the behavior of the chain in a flow matches observations of the motion of actual chains. In the case of DNA, each base pair could be treated as a bead, but even this level of coarse-graining is usually far too fine to yield reasonable computational times and unnecessary to achieve accurate results. Instead, most simulations use anywhere from 5 to 20 sections depending on the complexity of the flow and resulting motion of the molecule that needs to be captured. Besides the reduction in the problem size, another advantage of coarse-graining is that the forces on the beads or rods can be described by continuum mechanics instead of requiring inter-atomic potentials. The forces common to most simulations include the following.

Drag

Drag forces arise from the difference between a bead or rod's velocity $\dot{\boldsymbol{r}}_i$ and the local velocity field of the fluid $\boldsymbol{u}_i$, with the difference scaled by the drag coefficient ζ, giving $F_D = -\zeta(\dot{\boldsymbol{r}}_i, -\boldsymbol{u}_i)$.
The drag coefficient depends on the size of the bead. In the case of rods, the local flow field may not be uniform across the rod, which gives rise to moments on the object as well. Because the motion of a rod involves an additional angular acceleration, the computations are often more involved.

Internal

The internal forces for coarse-grained models can be considered elastic (bead/spring) or rigid (bead/rod). Regardless of the method, the force connecting adjacent beads does not represent inter-atomic forces, but merely constricts the distance between adjacent beads. In general, the effect of a shear flow is to stretch the molecule, so an attractive force is applied to keep the molecule intact. For the spring-like model, several non-linear forms of for the attractive force have been proposed. For more information about the types and physical basis for the mathematical form of these forces, the reader is referred to [1, 2]. Although the rigid model (bead-rod chains) introduces an added level of complexity due to constraints on the motion, the results obtained using the bead-rod model are more accurate for a fewer number of beads. Furthermore, for more complex situations such as electric field induced motion and obstacle navigation, the bead/rod formalism is often considered more robust.

Electrostatic

A myriad of conditions could give rise to non-uniform charge distributions in the fluid. For example, electroosmotic flows or solutions of electrolytes are often used to manipulate microfluidic flows. In these situations, the macromolecule may be subject to Coulomb forces. There is no general expression to account for these forces, but they will depend on the location and strength of the charge distribution in the fluid as well as along the molecule.

Image

The force of the wall is modeled as a steep potential near a physical barrier. The force is called an image potential because the magnitude is derived from a phantom particle that is placed on the perpendicular to the wall and the particle near the wall. The phantom particle is exactly the same as the particle being repulsed, and the repulsive force is the force between two neighboring particles (instead of the wall). This approach allows one to consider variations in forces that arise from the particles without having to treat the wall differently.

Brownian

All other forces are essentially continuum forces, i. e. they would be present for a large-scale strand of beads and are not specific to molecules. The Brownian force, on the other hand, is only present for very small objects. This force is the result of individual atoms and other molecules in the flow bumping into the macromolecule to change its conformation. In the continuum limit, enough momentum exchange occurs in all directions so that the net force is zero. For small objects, the net force is some non-zero randomly oriented force that goes to zero over long times. However, in some non-equilibrium situations such as near walls, the Brownian force can be non-uniform.

Hydrodynamic

Objects in the wake regions of other objects are known to experience different flow characteristics compared to the bulk motion of fluid. Therefore, some beads in a macromolecule do not sample the bulk fluid, but a modified version of the bulk fluid because of the proximity of other beads in the flow. A great deal of research has gone into developing techniques and approximations to attempt to include this effect with varying degrees of success. The difficulty lies in the attempt to invent a general solution to a problem that is dependent on geometry, discretization of the molecule and flow characteristics. Discussion of these details are beyond the scope of this article. Instead the reader is referred to [3].

Other External

Many other forces could conceivably be important in macromolecule flows. For example,

1. magnetic forces could arise when dealing with magnetized particles in conjunction with macromolecules, which is often done in drug delivery and targeting.
2. Gravitational forces may be important if transport occurs in a centrifuge.
3. Many experiments also track macromolecules with fluorescent dyes. If the dye molecule is of the order of the transported molecule, then the dye can introduce additional drag.
4. Hybridization of DNA can provide a force at the ends of the macromolecules that tether the molecule to a surface.
5. Van der Waals forces can arise between polar objects.

Once the forces acting on the molecule are known, two approaches can be used to solve for the dynamics behavior of the particles. Boltzmann-based models (also called Fokker–Planck systems) can predict average quantities through calculation of a distribution function.

$$\begin{aligned}\frac{\partial f}{\partial t} &= \sum_i \left(m_1^{-1} p_1 \frac{\partial f}{\partial r_i} + F_j \frac{\partial f}{\partial p_i} \right) \\ &= \sum_i \sum_j \frac{\partial}{\partial p_i} \zeta_{ij} \left(m_j^{-1} p_j f + kT \frac{\partial f}{\partial p_j} \right) .\end{aligned} \tag{1}$$

Moments of f result in an average displacement field. This approach has largely been supplanted by non-averaging techniques because of molecular individualism [3]. In other words, instead of calculating average displacements, the behavior of individual molecules are of more interest in modern macromolecule transport.

To determine specific molecular motions, the Langevin approach is relatively straightforward and involves integrating Newton's second law,

$$\sum_i F_{ij} = m_j \boldsymbol{a}_j = m_j \frac{\mathrm{d}^2 x_j}{\mathrm{d}t^2} , \tag{2}$$

over time to calculate the displacement (motion) of each bead. In equation 1, i indexes each force acting on a bead and j indexes the beads in the simulation. Tractable solutions to this motion are only possible when time is discretized into tiny steps. Over each time step, the forces and acceleration are assumed constant. The integration scheme varies with the discretization of the molecule and type and magnitude of the forcing functions that are present. However, most generally applicable schemes are second-order accurate and involve some leap-frog technique where velocities are calculated at the half-time step.

The two primary difficulties are including the Brownian force and the hydrodynamic interactions because these two forces are not independent of the solution resulting in a non-linear system of equations. If we assume that the momentum relaxation is much faster than the position relaxation of the Brownian particles, then the resulting equations can be simplified with a diffusion tensor that represents the influence of the Brownian force on average displacement [1].

$$\langle \Delta r_i \rangle = \sum_j \left(\frac{\partial \mathrm{D}_{ij}^0}{\partial r_j} + \frac{\mathrm{D}_{ij}^0}{kT} F_j^0 \right) t , \tag{3}$$

where the summation index spans the particles in three-dimensional space. In the foregoing expression, time is assumed to be greater than the momentum relaxation, i. e. $t \gg \tau^0 = m\mathrm{D}/kT$. The Oseen tensor is often used for D_{ij} [2], but appropriate expression of this diffusion component is the subject of a great deal of research.

The prediction of molecular motion is only as good as the effective forces that act between beads or rods. In the case of rigid rods connected by rotating joints, Kramer's bead chain rod system is the prevailing model. In this approach, the total length of the polymer is fixed, which may not be physically realistic in many cases. Yet, this model prevents the molecular strand from crossing itself, which is also physically unrealistic. The displacement of the beads is usually predicted from an optimization using the inter-bead distance as an internal constraint. For the bead-spring models, several different forms of inter-bead potentials have been used. The simplest model has a linear spring between each bead. This model tends to allow too much displacement, so an inverse Langevin model is used to stiffen the spring for larger displacements, which can be approximated as

$$F_j = \frac{G r_i}{1 - (\frac{r}{r_0})^2} \tag{4}$$

where G is the spring constant and r_0 is the relaxed molecule length. For DNA molecules, a worm-like chain model has proven remarkably successful, which has several forms that can be useful.

Key Research Findings

Research in macromolecular transport using Brownian dynamics is either fundamental in that a parameterized class of fluid flow conditions is considered, or a particular experiment is modeled with well-known geometric and fluid conditions.

In the study of molecular transport and conformation in simple flows, results suggest that the motion is not very simple. Many polymers have fairly complex shapes when in a quiescent fluid. They can be coiled, straight, curved or a combination of different shapes as seen in Fig 1. This tendency is important when discussing transport in a ▶ shear flow. Both simulations and experiments produce molecular shapes described as coils, dumbbell, linked, half dumbbell, straight and folded, all in a single longitudinal shear flow. Moreover, for varying flow parameters, the shape can transition between the different forms, and the transition is unpredictable. Similarly, in linear shear flows, the motion can be characterized as longitudinal (perpendicular to the shear direction), tumbling, or globular. Transition between flows can occur without changing flow parameters. The transition rate, however, is usually governed by the strength of the shear.



Simulating Migration of Polymer Chains, Methods, Figure 1 Conformation of a 30-bead chain in a linear shear flow at different times. The chain shown will exhibit a periodic tumbling motion if observed for long periods of time

These results suggest that control of a single polymer chain in a flow is difficult because of the unpredictability of any specific molecule. However, we are usually interested in the motion of a large number of molecules in a micro-fluidic system. Therefore, statistics are collected on a single molecule given a variety of initial conditions, for example. Then predictions about the average behavior of certain types of molecules in certain types of flows can be made.

The non-dimensional Weissenberg number ($\mathrm{Wi} = \dot{\gamma}\lambda$) is defined as the product of fluid strain rate ($\dot{\gamma}$) and the longest relaxation time of the polymer chain (λ). This number provides an approximation to the ratio of ability of the flow to stretch the polymer chain divided by the tendency of the chain to resist stretching. For large Wi, the flow generally results in stretching of the molecule; for small Wi, the molecule's conformation is dominated by Brownian motion.

Other studies of polymer transport focus on how long molecules behave in a complex flow in the presence of obstacles. For example, one group has examined how DNA migrates through a field of posts where the strands straddle the obstacle. Simulations of this type are useful to help predict the resident time of DNA in a particular region. This might be important to researchers who are using micro-fluidic chambers to produce chemical reactions with DNA, for example.

Future Directions for Research

Two research direction emerge from existing studies and needs in the community. (1) Fundamental studies focus on the physics governing the relationship between the forces acting on the beads. (2) Applied studies focus on how molecules behave in different systems.

In terms of fundamental studies, modeling of polymer chains is still in its infancy. Although there are plenty of instances where experiments and simulation converge, there is no general purpose, all-encompassing simulation approach that works universally. The primary difficulty arises from resolving the relative strengths of each force acting on the molecule. In isolation, each force can be described mathematically with a good deal of rigor. However, the relative magnitude of each force relies on difficult to characterize free parameters. Therefore, simulations still rely on experiments to provide data for accurate simulations. A first-principles simulation is simply not possible yet. Consequently, much of the current research is devoted to refining the force models to include more physics in simulations.

In terms of applied studies, different configurations are constantly being addressed to help analyze specific experimental studies and to help provide ranges for the free parameters associated with the forces.

To address both of these concerns, the following areas are suggested as immediate research areas where substantial contributions can be made.

Complex Flows

Most fundamental simulations examine simple flow situations such as elongation and linear shear flows. These flows appear in many micro-fluidic structures, and include a wide range of effects that molecules might experience. In addition, the flow solution is simple and can be reliably produced in the lab. Therefore, there is continued need to investigate these configurations. However, these simple flows do not represent all situations seen in modern micro-fluidic devices. For example, stagnation point flow into a stationary wall, flow around corners and flow mixing are all complex phenomena that affect polymer chain transport and conformation.

Overlap Models

Although the bead spring model appears adequate for many situations, more complex flows can cause interaction of a molecule with itself. For bead-spring models, this can be treated by introducing strong, short-range potentials. Because of the large gradients, however, simulations are prone to exaggerated motion when non-adjacent beads approach each other. The bead-rod model attempts to account for the interaction by preventing the coarse-grained model of the chain from crossing itself. This approach can be relatively complex and a universally agreed upon approach has not been established.

Wall Interaction

Typically a wall is modeled with an image potential. In this case, a virtual particle that is located at the mirror location to the real particle provides an interaction potential. As such there is often an artificial buffer that prevents the bead from contacting the wall and migration away from surfaces is possible. Even though these interaction potentials have a short range, they can be strong to prevent beads from penetrating walls. As a result, time stepping becomes crucial, and too large of a time step can result in physically unrealistic motion. New methods to treat this artifact are needed to provide transport in confined channels.

DNA Hybridization

In the case of DNA transport, the researcher is often interested in hybridization, which is a reaction that changes the characteristics of the chain or causes additional forces. Motion in the presence of interaction particles is complex and has not received much attention.

Cross References

- ► AC Electro-Osmotic Flow
- ► Brownian Motion and Diffusion
- ► Dielectrophoretic Motion of Particles and Cells
- ► Dissipative Particle Dynamics
- ► Electrokinetic Flow and Ion Transport in Nanochannels
- ► Electroosmotic Flow (DC)
- ► Multiscale Modeling and Numerical Simulations
- ► Molecular Dynamics Simulation Method
- ► Polymer Synthesis Within Microfluidic Reactor
- ► Van der Waals Interaction Forces

References

1. Ermak DL, McCammon JA (1978) Brownian dynamics with hydrodynamics interactions. J Chem Phys 69(4):1352–1360
2. Yamakawa H (1971) Modern Theory of Polymer Solutions. Harper and Row, New York
3. de Gennes PG (1997) Polymer Physics: Molecular Individualism. Science 276(5321):1999–2000
4. Marko JF, Siggia ED (1995) Stretching DNA. Macromol 28(26):8759–8770
5. Hur JS, Shaqfeh ESG, Babcock HB, Chu S (2002) Dynamics and Configurational Fluctuations of single DNA Molecules in Linear Mixed Flows. Phys Rev E 66(011915)
6. Schroeder CM, Shaqfeh ESG, Chu S (2004) Effect of Hydrodynamic Interactions on DNA Dynamics in Extensional Flow: Simulation and Single Molecule Experiment. Macromolecules 37:9242–9256

Single Cell Analysis in Microfluidic Devices

LUC CHARON[2], AARON R. WHEELER[1], LOTHAR LILGE[2]
[1] Department of Chemistry, University of Toronto, Toronto, ON, Canada
[2] Department of Medical Biophysics, University of Toronto, Toronto, ON, Canada
awheeler@chem.utoronto.ca

Synonyms

Analysis of individual cell contents

Definition

►Chemical cytometry is a class of highly sensitive analytical techniques for the analysis of the chemical contents of single cells. These techniques enable the detection and identification of cell constituents including oligonucleotides, small molecules, and proteins, as well as providing means to monitor the effects of biochemical and enzymatic reactions.

►Capillary electrophoresis is an analytical technique used to separate chemicals in solution as a function of their charge and size. Samples are injected into a capillary, a high electric field is applied, and the analytes migrate to the end of the column, where they are detected.

Overview

The cell is a complex biochemical factory, capable of proliferation, differentiation and communication. The cell also interacts with its microenvironment, comprised of other cells, tissue matrix and interstitial vascular, lymphatic and non-biological compartments. Yet most of what is known about the correlation between behavior, function and genotype of biological cells comes from *average* measurements of cell populations. While useful, these studies are unfortunately incapable of assessing the response and interaction of individual cells within a heterogeneous population. As an illustration, a recent study [1] of hormone-induced maturation of unfertilized eggs (oocytes) as a function of enzyme activation was evaluated both based on populations and individual cells. The population data suggested a *graded* relationship between the hormone (progesterone) concentration and enzyme activation while the single cell data revealed a sharp *all-or-nothing* switch. The single cell analysis approach can in fact provide not only complementary information but rather reveal the actual functional interaction of biomolecules thus assisting in understanding complex biological systems on the cellular and tissue structural basis. This kind of biological insight is required to understand complex systems such as tissues, organs and even complete organisms. While it is obvious that this type of work is useful, single cell studies are much more complicated and time-consuming than their population counterparts; in fact, single cell analyses push the boundaries of conventional techniques.

Several single cell analysis techniques have been developed, which may be classified in terms of information content (# of elements capable of being studied simultaneously) and throughput (# of cells studied in a given time) – this is illustrated in Fig. 1. The simplest and most widely used forms of single cell analysis are fluorescence microscopy and flow cytometry. In microscopy, fluorescence from small molecule reporters, immunochemical labels, or transfected fluorescent proteins within cells is observed with subcellular localization. While this technique enables the measurement of time-dependent changes in response to stimuli of individual cells as well as cell-cell interaction studies, it is an inherently low-throughput method if used with high magnification. Conversely, flow cytometry is a high-throughput technique that can be used to analyze up to several tens of thousands of cells per second but is limited in the type of assays for which it can be used and does not provide subcellular resolution. Multiple wavelength analysis schemes have been developed, but the number of parameters which can be measured simultaneously is intrinsically limited by the finite spectral bandwidth of the detectors and the increasing complexity of using multiple fluorophores, excitation sources, and/or detectors. These two techniques therefore are classified in the region of low information content space in Fig. 1.

In order to achieve a more comprehensive analysis of individual cells, methods that incorporate chemical separations have been developed to increase the number of parameters capable of being studied simultaneously. These techniques, termed *chemical cytometry* by Dovichi and coworkers [2] are used to detect and identify various components of single cells such as oligonucleotides, small molecules and proteins, as well as to monitor enzyme activity. Capillary electrophoresis (CE), laser-induced fluorescence (LIF), and electrochemistry are the tools which are used in chemical cytometry; this chapter deals with capillary electrophoresis implemented in microfluidic devices.



Single Cell Analysis in Microfluidic Devices, Figure 1 Chart comparing single cell bioanalytical techniques in terms of information content and throughput

CE-based chemical cytometry can be used to evaluate many cell constituents simultaneously, and is thus, as shown in Fig. 1, categorized as a high information content technique. This comes at a cost, however, as the cell injection schemes and use of a single capillary makes the technique extremely low-throughput. Ideally, the contents of hundreds of cells could be individually analyzed for statistical evaluation of the heterogeneity of a population; in practice, however, the arduous and time-consuming nature of chemical cytometry typically limits it to a few cells (i. e., < 10) per analysis.

In recent years, microfluidics has become a popular technology for applications in the life sciences. The continued development of new microfabrication techniques has permitted the integration and scaling down of several bioanalytical procedures into a single device, from which emerged the concept of Lab-on-a-Chip or micro total analysis system (μTAS). Microfluidic devices have several advantages over conventional bioanalytical techniques: low reagent and power consumption, low cost, and the potential for mass production and massively parallel scale analysis. As illustrated in Fig. 1, the application of microfluidics to chemical cytometry may result in a solution to the low-throughput problem of capillary-based chemical cytometry techniques, forming a new class of methods with high-throughput and information content. Several good reviews have been recently published covering the potential of microfluidics for applications involving cells [3, 4]. Microfluidics has been applied to microscopy, flow cytometry, and chemical cytometry, among others. As microscopy and flow cytometry are discussed in detail in other chapters in the *Encylopedia* (► flow cytometer lab-on-chip devices, ► detection using confocal microscopy), we focus here on chemical cytometry. In what follows, we discuss the state-of-the-field and challenges remaining to be solved in the areas of fabrication, cell selection/transportation, cell lysis/treatment, and analysis, from the standpoint of microfluidic method development for high-throughput chemical cytometry.

Basic Methodology

Fabrication Considerations

There are many well-established microfabrication techniques which can be used to construct microfluidic devices (► microfabrication techniques). Each has strengths and weaknesses, but the choice of fabrication technique ultimately depends on cost, availability of the facility, and most importantly, on compatibility with the desired application. This is especially important for chemical cytometry, where the fabrication process must be versatile enough to form devices capable of implementing the many necessary functions. Key considerations for fabrication of chemical cytometry include material, integration, and macro-to-micro interface.

Material

The materials used for the fabrication of most microfluidic chips include glass, silicon, quartz, and plastics (► materials used in microfluidic devices) In addition to cost and optical, electrical and physical properties, careful consideration must be given to the surface chemistry of the material (► methods for surface modifications). In fact, surface chemistry plays a major role in chemical cytometry, as protein adsorption to the channel walls can degrade the separation performance and make the electroosmotic flow unreproducible.

Integration of Multiple Components

The functionality and versatility of microfluidic devices for chemical cytometry requires the combination of several cell manipulation, processing, and analysis steps. These techniques, discussed in detail in the next section, rely on device components such as microstructures, optical windows, electrodes, embedded waveguides, and valves and pumps; each of which must be miniaturized and integrated on a single microfluidic platform (please refer to the following chapters ► fabrication of 3D microfluidic structures, ► on-chip waveguide, ► pneumatic valves, ► thermomechanical valves, ► thermopneumatic valves). Integrating multiple components on a single device dramatically increases the complexity of the final product and introduces compatibility problems in the various integrated functions. For example, surfaces designed to promote or prevent cell adhesion (for cell manipulation) are often different than surfaces best suited for electrophoretic separations. These engineering challenges are a bottleneck in the development of multifunctional microfluidic devices and must be addressed for the development of high-throughput chemical cytometry.

Macro-to-Micro Interface

A key concern for all microfluidic devices is the macro-to-micro interface. The complexity of the interface depends on the number of integrated functions (see ► packaging (including wire bonding)).

Cell Manipulation and Transportation

One of the most critical steps in single cell analysis is selection of predetermined individual cells and transportation through the device (► techniques for manipulating cells, ► microfluidic sample manipulation). The manipulation and transport techniques used for chemical cytometry should be multiplexed, have the potential for automation, and, depending on the assay, should have minimal biological or chemical impact on the cell(s) to be transported. Techniques fitting this description include cell sorting and integrated flow cytometry (► cell sorting, optophoresis for cell sorting, ► flow cytometer lab-on-chip devices). Several micromanipulation techniques based on mechanical, electrical and optical means have been developed for cell-based assays in microfluidic devices.

Mechanical Manipulation

While micromanipulators and micropipettes are routinely used for in vitro fertilization studies, they are bulky, suffer from low throughput and are not amenable to integration with a sealed microfluidic device. Other mechanical manipulation techniques include microfilters, dams, and *sandbag* structures. We note that these techniques are often used to capture, dock or sort many cells simultaneously without specificity and thus are limited in their use for single cell analysis where selecting a particular cell is a key goal.

Electrical Manipulation

The electric charge or polarity of cells (and cell contents) may also be used for manipulation and transportation within microfluidic devices. In contrast to mechanical methods, the use of electric field based approaches such as electrokinetics and dielectrophoresis are well-suited for microfluidics as they permit flexibility, controllability, automation and high-throughput capability. We note, however, that these kinds of techniques can produce undesired biological stress such as protein migration and clustering within the cells and in high fields, cells may even lyse (i. e., die). For more information, please refer to the following *Encyclopedia* chapters: ► dielectrophoretic motions of particles and cells, ► electrokinetic motion of cells and non-conductive particles, ► AC dielectrophoresis Lab-on-a-Chip devices.

Optical Manipulation

Optical micromanipulation techniques use lasers to apply piconewton forces on micron sized particles, and have been demonstrated to be useful for cell transportation in microchannels. One of the most popular optical techniques is ► optical *trapping* (or optical/laser tweezers), which is implemented by focusing a laser to a diffraction-limited spot by a high numerical aperture (N.A.) microscope objective. Although optical trapping can be used to select particular cells accurately, its slow translational speeds ($20-30\,\mu$m/sec) [5] makes it a low-throughput cell manipulation technique. We note that some have used diffractive optical elements (DOEs) and spatial light modulators to create multiple *optical traps* simultaneously, thus improving throughput [6]. These techniques are described further in ► optical tweezers for manipulating cells and particles. Another alternative in optical manipulation is laser-guided direct writing, in which a weakly collimated or converging beam pushes cells to desired locations [7]. This technique has been used to transport cells at 88 μm/s over several millimeters. A similar transportation technique was developed using evanescent waves from integrated waveguides to manipulate micron size particles [8]. While these two techniques suffer from lack of cell selectivity, they could potentially be automated to increase throughput in chemical cytometry by strategically positioning the integrated waveguides within the microfluidic device.

Cell Lysis/Treatment

In conventional population cell-based assays, sample preparation involves several steps, including lysis, filtration of non-solubilized cellular material, labeling of the analytes of interest, and sample purification. However, to prevent dilution of the extremely small samples in single cell analysis, filtration and purification are not typically integrated in chemical cytometry methods. This section briefly describes the various cell lysis techniques which have been implemented in microfluidics; for more detail, please see ► on-chip cell lysis.

In CE-based chemical cytometry, the quality of the information is ultimately determined by the manner in which the cells are lysed and their contents injected into the capillary. The technique employed to perform this task must be carefully designed to enable high quality, reproducible electrophoretic separations. Dilution of the contents of the cell prior to application of the electric field must be reduced to maximize sensitivity and resolution of the separated analytes. Lysis should occur in a manner such that the biochemical contents of the cell are not altered, for example, by the activity of proteases that are usually kept partitioned away from free cellular proteins. The technique must also address capillary clogging issues which result from the presence of insoluble cell debris. Finally, the lysis technique must be able to function in parallel for high-throughput applications. There are three categories of cell lysis techniques: electrical, mechanical and chemical lysis.

Electrical Lysis

When a large electric field is applied across a cell, the transmembrane potential is disrupted and pores are formed on the surface of the membrane. This phenomenon is called ► electroporation and is often used for gene transfection. As conventionally implemented, the process is reversible, and when the electric field is terminated, the pores close. The phenomenon can also be used to cause permanent disruption of the membrane, effectively lysing the cell. There have been several reports on the use of electrical lysis techniques in microfluidic devices [9–11]. Of particular interest, fast lysis of individual cells (~ 33 ms) by electrical pulses for chemical cytometry was demonstrated in a microfluidic platform [12]. These extremely rapid lysis methods which minimize unwanted effects of slow lysis (that may bias the results) make these techniques favorable for protein analysis when compared to chemical lysis techniques. One drawback of electrical lysis is that much of the cell membrane, subcellular structures and the nucleus may remain intact and thus can clog the channe or adhere to the surface, affecting the separation and limiting the capacity for re-use.

Mechanical Lysis

Typical lysis techniques based on mechanical forces such as sonication and bead milling are not amenable for integration in a microfluidic device; however, in recent work, cells were lysed in microchannels by mechanical shearing on nanostructured filter-like *nano-knives* [13]. This method had the additional advantage of aiding subsequent analysis steps by filtering out cellular debris thus preventing clogging and sample fouling.

Chemical Lysis

The most common macro-scale cell lysis methods make use of chemical agents; as a result, several research groups have used similar techniques to lyse cells in microfluidic devices [14–16]. While detergents such as sodium dodecyl sulfate (SDS) permit a greater number of proteins to be analyzed due to the capacity to solubilize membrane proteins and lipids, chemical lysis reaction times are relatively slow (tens of seconds). Therefore, this technique may not be ideal for applications in which desired biological events take place on time scales of seconds or less (e. g., metabolite concentrations can change by a factor of 10 within 1 s [17]) or when diffusion of the cellular content within the microfluidic chip structure can not be suppressed.

Analysis

While an array of analytical techniques has been developed to study various aspects of cells (please see ▶ cell assays in microfluidics), this chapter is focused on chemical cytometry. As mentioned above, chemical cytometry refers to methods in which intracellular constituents of a single cell are analyzed by means of a chemical separation. Such methods typically employ capillary electrophoresis for separations, combined with laser induced fluorescence (LIF) or amperometry for detection. We refer readers to other chapters for detailed descriptions of other methods used to evaluate contents of cells (▶ patch–clamp measurements on-chip, ▶ mass spectrometry on chip device).

In capillary-based chemical cytometry, a cell is injected into a capillary, where it is lysed, and then its contents are separated by electrophoresis. The separating contents are detected at or near the end of the capillary, as the analytes migrate past the detection zone. Microfluidic devices are well-suited to replace capillaries for chemical cytometry. The channel dimensions ($5-100\,\mu$m) and planar geometry allow for very efficient dissipation of Joule heat produced from large electric field gradients. The capacity to apply high fields (e. g., $500-1000$ V/cm) dramatically reduces separation time and minimizes band diffusion. Most importantly, the small channel dimensions can handle injection volumes ranging from nanoliters to hundreds of femtoliters [18], and thus results in minimal dilution of sample.

The level of expression of protein species within a single cell ranges between several millions to under 10 copies, requiring that extremely sensitive detection techniques be employed. LIF is particularly well suited for this task as it is capable of achieving mass concentration detection limits of a few tens of molecules and even single-molecule detection [19]. Amperometry has also been used frequently due to its high sensitivity. A more detailed look at these two techniques can be found elsewhere (▶ fluorescence measurements, ▶ amperometric techniques).

Key Research Findings

Over the past few years, several groups have attempted to integrate all of the critical processes for chemical cytometry on a single mirofluidic plattform. Various combinations of cell manipulation, cell lysis, and analysis strategies were used to obtain high content information with the goal of maintaining analysis in a high-throughput format. Some methods were optimized for analysis of small molecules and proteins, while others were developed for genetic assays, evaluating DNA or RNA content.

Protein or Small Molecule Analysis

Fang and coworkers [9] developed a glass microfluidic chemical cytometry device with a simple cross-shaped channel design. Derivatized glutathione (GSH) in single human erythrocyte cells was separated and detected by LIF. Cells were transported from the reservoir to the T-junction by hydrodynamic flow, which was controlled by adjusting the amount of liquid in the four reservoirs; fine positioning was performed by applying a series of voltages to *dock* the cell. Once positioned, each cell was electrokinetically lysed. This technique yielded a throughput of approximately 15 cells/h.

Hellmich et al. [20] designed a PDMS device comprising a cross-junction integrated with other micro-scale features as shown in Fig. 2a. GFP-transfected insect cells were selected and transported to the intersection using optical tweezers. After positioning, the cells were lysed with SDS; the microstructures acted as a physical cell trap, preventing the cell from moving away during the process. After each cell was lysed, fluorescently labeled contents (amino acids and proteins) were separated by electrophoresis and detected with LIF.

McClain et al. [12] also developed a microfluidic device that integrated cell handling, lysis and electrophoresis, as shown in Fig. 2b. The device was evaluated with T-cells loaded with fluorogenic dyes which were separated and detected by LIF. Cell transport and lysis were accomplished using electric fields. In order to reduce Joule heating, lysis was effected by superimposing AC fields on the DC fields used for separations. This technique enabled separation to be maintained throughout the process; lysis was completed within 33 ms and a throughput of $7-12$ cells/min was achieved with a separation efficiency ranging from 2300 to 4000 theoretical plates.

As an alternative to using AC fields, to prevent excessive Joule heating, Wang et al. [21] designed a microfluidic device with channels having variable cross-sections which modulated the local electric field strengths. Chinese hamster ovary cells labeled with calcein AM were used to



Single Cell Analysis in Microfluidic Devices, Figure 2 (**a**) PDMS single-cell microfluidic device with T-junction and integrated cell trap, formed from micron-sized posts. The cell is transported with optical tweezers (OT) to the intersection, followed by the delivery of the surfactant, SDS, to lyse the cell. (Image reproduced from [20].) (**b**) Design for high-throughput chemical cytometry; this method uses a combination of AC and DC electric fields for cell lysis and electrophoresis. (Image reproduced from [12])

test the device. The cells were driven to the T-junction by hydrodynamic flow generated by a syringe pump. Once at the junction, the cells were lysed and the contents were separated by electrophoresis and detected.

To increase throughput and eliminate sample cross-contamination, which is common when analyzing cells sequentially, Munce et al. [22] developed a microfluidic device with four parallel CE channels. Calcein-labeled acute myloid leukemia cells were selected and transported with optical tweezers to injector structures at the entrance of each channel, as shown in Fig. 3a. Once loaded, the cells were lysed by the combined action of an applied electric field and the reduction in channel cross-section (Fig. 3b). The injector design also enabled stepwise lysis of the cell, shown in Fig. 3c, where only the cyctoplasmic material (containing calcein AM in green) was injected into the capillary while the nucleus (stained blue with Hoechst 33342) remained in the injector structure. This selective lysis is especially useful to separate the cytoplasm from the nucleus and finally the membrane particularly if protein signalling is the focus of the application. The injector structures also prevented extracellular debris from entering the channels. Once loaded in the capillary, the analytes were separated and detected with LIF. The throughput was estimated to be 24 cells/h; however, this could be increased with additional separation channels.

Wu et al. [23] designed a PDMS microfluidic device for chemical cytometry, consisting of integrated valves which formed a reaction chamber and a picopipette for reagent delivery. The system, depicted in Fig. 4a, allows for individual cells to first be isolated in a closed chamber, and then be combined with an aliquot of lysis and fluoresecent derivatization reagents, delivered by the picopipette. After lysis and derivatization, the valves are opened and voltage is applied to separate the derivatized amino acids. Figure 4b shows an electropherogram collected from a single Jurkat T cell compared to one generated from a population of cells with off-column lysis and derivatization. With the pneumatic valves, 70-picoliter reaction chamber, and



Single Cell Analysis in Microfluidic Devices, Figure 3 (**a**) Four parallel laser-etched injector structures in PMMA. (**b**) Sequence of fluorescent images of two calcein-labeled AML cells being lysed and injected into 2 separation channels. (**c**) Stepwise lysis of an AML cell. The cytoplasmic material (labeled in green) is loaded into the electrophoresis channel while the nucleus (labeled in blue) remains in the injector structure. (Images reproduced from [22])

picopipette, this device simultaneously addresses the problems of fluid control and reagent delivery without affecting sample dilution. This system could also be implemented in parallel to increase throughput.

As an alternative to LIF, Xia et al. [24] used amperometry to detect the contents of single wheat callus cells. In this work, cells were transported electrokinetically to a double T-junction, and docked, after which they were lysed by a DC electric field. Ascorbic acid and other analytes were separated by electrophoresis and detected by means of an amperometric detector.

DNA Analysis

A study of doxorubicin-induced apoptosis (programmed cell death) in individual cardiomyoctes was performed using a microfluidic device created by Horky and coworkers [25]. Apoptotic DNA fragments from individual cells were electrophoretically separated and detected by LIF. The device consisted of a simple cross channel design; cells were injected into the device and transported by pressure-driven flow by application of a vacuum. Cell lysis was achieved by activating an electric field across the T-junction, which was filled with a 2% solution of linear polyacrylamide.

Quake and coworkers [16] developed a PDMS microfluidic device (shown in Fig. 4c) for nucleic acid purification from a small number of bacterial or mammalian cells. This multilayer device contained fluidic channels and a system of membrane-actuated pneumatic valves and pumps, which enabled precise control of buffers, lysis agents and cell solution, and also allowed for parallel processing. Bacterial cells, dilution buffer and lysis buffer are first introduced into the chip and then transferred into the rotary mixer. Once mixed, the lysate is flushed over a DNA affinity column and drained. The DNA is recovered from the chip with an elution buffer for further analysis. We note that this is the only microfluidic chemical cytometry device to use a separation method other than solution-phase electrophoresis (i. e., solid phase extraction).

Future Directions for Research

This chapter has outlined the challenges inherent in chemical cytometry, i. e., the separation and detection of the contents of a single cell. Microfluidics is a promising technology in the goal of developing high-throughput chemical cytometry techniques, which require robust and repeatable means for cell transportation, lysis and analysis applied in parallel (or very rapidly in series). The current methods have established proof-of-principle; however, much work remains to be done, especially related to scaling up for parallel analysis.


A
Close valve fill cell suspension
Open valve isolate one coil and dose valve
Meter SDS half open valve: fill SDS and lyse cell
Cell
PBS
SDS
Single cell lyaate
Derivatized cell content
Running buffer
Meter and 1 NDA: allow reaction to occur
Close valves; fill buffer; open valves; apply high voltages
B
1
2
3
4
5
6
7
8
100 µm

a


Flourescence Intensity
Ser. Asn
Gln
Gly
Ala
Met
Tyr
Cell debris
Arg
Phe
Ile
Trp
NDA
Single cell
Multiple cells

b


a
Lysis buffer
Dilution buffer
Naked bacterial cells
Beads
b
Dilution buffer
Cells
lysis buffer
c
Cell lysis
d
Wash buffer
DNA on beads
Waste
e
Elution buffer
Purified genomic DNA
f
4. Vertical ctl
7. Mixer ctl1
8.
9.
Buffer
Cell in
12. Bead trap ctl
Bead in
1. Lysis out
2. Wash ctl
13. Wash ctl
14. Collection ctl
Collection, c1
Lysis in
Wash in
c2
Buffer in
Waste
c3
11. Bead vtf ctl
3. Elute ctl
5. Horiz ctl
6. Dead end ctl
10. Loop exit ctl

c

Single Cell Analysis in Microfluidic Devices, Figure 4 (**a**) 70-picoliter reaction chamber chemical for cytometry comprising a 3-state valve, a 2-state valve and a picopipette. The sequence illustrates the isolation and lysis of a single cell, as well as fluorescent derivatization of amino acids in the lysate. (**b**) Electropherogram collected from a single Jurkat T cell (solid line) generated in the microfludidic reaction chamber compared to one generated from a population of cells with off-column derivatization (doted line). (Images in (a) and (b) reproduced from [23].) (**c**) Multilayered PDMS microfluidic device with integrated pneumatic valves and pumps. The sequence illustrates the steps for cell isolation, lysis in a rotary mixer, and DNA purification and harvesting. (Image reproduced from [16]) ◄

Cross References

- Flow Cytometer Lab-on-Chip Devices
- Detection Using Confocal Microscopy
- Microfabrication Techniques
- Materials Used in Microfluidic Devices
- Methods for Surface Modifications
- Fabrication of 3D Microfluidic Structures
- On-Chip Waveguide
- Pneumatic Valves
- Thermomechanical Valves
- Thermopneumatic Vavles
- Packaging (Including Wire Bonding)
- Techniques for Manipulating Cells
- Microfluidic Sample Manipulation
- Cell Sorting
- Dielectrophoretic Motions of Particles and Cells
- Electrokinetic Motion of Cells and Non-Conductive Particles
- AC Dielectrophoresis Lab-on-a-Chip Devices
- Optical Tweezers for Manipulating Cells and Particles
- On-Chip Cell Lysis
- Cell Assays in Microfluidics
- Patch-Clamp Measurements On-Chip
- Mass Spectrometry On Chip Devices
- Fluorescence Measurements
- Amperometric Techniques
- Chemical Cytometry

References

1. Ferrell JE, Machleder EM (1998) The Biochemical Basis of an All-or-None Cell Fate Switch in Xenopus Oocytes. Science 280:895–898
2. Dovichi NJ, Hu S (2003) Chemical cytometry. Curr Opin Chem Bio 7:603–608
3. El-Ali J, Sorger PK, Jensen KF (2006) Cells on chips. Nature 442:403–411
4. Yi CQ, Li CW, Ji SL, Yang MS (2006) Microfluidics technology for manipulation and analysis of biological cells. Anal Chim Acta 560:1–23
5. Grover SC, Skirtach AG, Gauthier RC, Grover CP (2001) Automated single-cell sorting system based on optical trapping. J Biomed Opt 6:14–22
6. Ferrari E, Emiliani V, Cojoc D, Garbin V, Zahid M, Durieux C, Coppey-Moisan M, Di Fabrizio E (2005) Biological samples micro-manipulation by means of optical tweezers. Microelectron Eng 78–79:575–581
7. Odde DJ, Renn MJ (2000) Laser-guided direct writing of living cells. Biotechnol Bioeng 67:312–318
8. Gaugiran S, Getin S, Fedeli JM, Colas G, Fuchs A, Chatelain F, Derouard J (2005) Optical manipulation of microparticles and cells on silicon nitride waveguides. Opt Express 13:6956–6963
9. Gao J, Yin XF, Fang ZL (2004) Integration of single cell injection, cell lysis, separation and detection of intracellular constituents on a microfluidic chip. Lab Chip 4:47–52
10. Lee SW, Tai YC (1999) A micro cell lysis device. Sens Actuatores A 73:74–79
11. Lu H, Schmidt MA, Jensen KF (2005) A microfluidic electroporation device for cell lysis. Lab Chip 5:23–29
12. McClain MA, Culbertson CT, Jacobson SC, Allbritton NL, Sims CE, Ramsey JM (2003) Microfluidic devices for the high-throughput chemical analysis of cells. Anal Chem 75:5646–5655
13. Di Carlo D, Jeong KH, Lee LP (2003) Reagentless mechanical cell lysis by nanoscale barbs in microchannels for sample preparation. Lab Chip 3:287–291
14. Irimia D, Tompkins RG, Toner M (2004) Single-cell chemical lysis in picoliter-scale closed volumes using a microfabricated device. Anal Chem 76:6137–6143
15. Wheeler AR, Throndset W, Whelan RJ, Leach AM, Zare RN, Liau YH, Farrell K, Manger I, Daridon A (2003) Microfluidic Device for Single Cell Analysis. Anal Chem 75:3581–3586
16. Hong JW, Studer V, Hang G, Anderson WF, Quake SR (2004) A nanoliter-scale nucleic acid processor with parallel architecture. Nat Biotechno 22:435–439
17. Berridge MJ (1993) Inositol Trisphosphate and Calcium Signaling. Nature 361:315–325
18. Swanek FD, Ferris SS, Ewing AG (1997) Capillary Electrophoresis for the Analysis of Single Cells. In: Electrochemical, Mass Spectrometric and Radiochemical Detection Handbook of Capillary Electrophoresis, pp 495–521
19. Johnson ME, Landers JP (2004) Fundamentals and practice for ultrasensitive laser-induced fluorescence detection in microanalytical systems. Electrophoresis 25:3513–3527
20. Hellmich W, Pelargus C, Leffhalm K, Ros A, Anselmetti D (2005) Single cell manipulation, analytics, and label-free protein detection in microfluidic devices for systems nanobiology. Electrophoresis 26:3689–3696
21. Wang HY, Lu C (2006) Electroporation of mammalian cells in a microfluidic channel with geometric variation. Anal Chem 78:5158–5164
22. Munce NR, Li JZ, Herman PR, Lilge L (2004) Microfabricated system for parallel single-cell capillary electrophoresis. Anal Chem 76:4983–4989
23. Wu HK, Wheeler A, Zare RN (2004) Chemical cytometry on a picoliter-scale integrated microfluidic chip. P Natl Acad Sci USA 101:12809–12813
24. Xia FQ, Jin WR, Yin XF, Fang ZL (2005) Single-cell analysis by electrochemical detection with a microfluidic device. J Chromatogr A 1063:227–233
25. Kleparnik K, Horky M (2003) Detection of DNA fragmentation in a single apoptotic cardiomyocyte by electrophoresis on a microfluidic device. Electrophoresis 24:3778–3783

Single Cell Impedance Spectroscopy

► Impedance Measurements of Cells

Single Crystal

Definition

Description of the ordered nature of the atoms in a material. In a single-crystal material, there is only one atomic structure of the crystal.

Cross References

► Fabrication of Self-Assembled Catalytic Nanostructures

Single-Phase Convective Flows in Microchannels

► Convective Heat Transfer in Microchannels

Single-Phase Forced Convection in Microchannels

► Convective Heat Transfer in Microchannels

Single-Phase Gaseous Flow

Yildiz Bayazitoglu
Rice University, Houston, TX, USA
bayaz@rice.edu

Synonyms

Gaseous flow; Slip boundary; Transition flow; Molecular flow

Definition

When gases are at low pressures, or are flowing in small geometries, the interaction of the gas molecules with the wall becomes as frequent as intermolecular collisions. This type of flow is known as rarefied gas flow. Typically, macrochannel boundary conditions, gas velocity and temperature that are applied to fluid flow and heat transfer equations are equivalent to the corresponding wall values. In contrast, these conditions do not hold for rarefied gas flow in microchannels. The Knudsen number (Kn) is used to represent the rarefaction effects. It is the ratio of the molecular mean free path to the characteristic dimension of the flow (i. e., the channel hydraulic diameter). The mean free path is defined as the average distance traveled by a molecule before colliding with another molecule. As Kn takes higher values, due to a higher molecular mean free path by reduced pressure or a smaller flow dimension, rarefaction effects become more significant. Kn is an important parameter to explain the surface effects in gaseous flows in microchannels in determining the pressure drop and the heat transfer coefficient. The continuum flow assumption will only be valid when $\mathrm{Kn} < 10^{-3}$. As Kn increases, the flow enters the slip flow regime ($10^{-3} < \mathrm{Kn} < 10^{-1}$), transition flow regime ($10^{-1} < \mathrm{Kn} < 10$) and eventually the free-molecular flow regime ($\mathrm{Kn} > 10$). These four regimes are illustrated in Fig. 1.



Single-Phase Gaseous Flow, Figure 1 Flow regimes identified by the Knudsen number

Overview

Gaseous flow in micro- and minichannels has been extensively investigated, and it is very important in microdevice development and design. Although several contradictory results have been published related to pressure drop and heat transfer coefficients, a few experiments were also performed to verify the theoretical results and some arguments are also made to explain those discrepancies.

Continuum Regime

The velocity, density, pressure and other properties of a fluid are all defined at every point in space and time and the solutions of fluid flow in the continuum regime are obtained by using the Navier–Stokes equations. For incompressible flow with constant properties we have the following.

Conservation of mass:

$$\frac{\partial \rho}{\partial t} + \nabla \cdot (\rho \boldsymbol{v}) = 0 \tag{1}$$

Conservation of linear momentum:

$$\rho \left(\frac{\partial \boldsymbol{v}}{\partial t} + \boldsymbol{v} \cdot \nabla \boldsymbol{v} \right) = \rho g - \nabla p + \mu \nabla^2 v \tag{2}$$

Conservation of energy:

$$\rho c \left(\frac{\partial T}{\partial t} + \boldsymbol{v} \cdot \nabla T \right) = k \nabla^2 T + \Phi \tag{3}$$

where $\boldsymbol{v}, t, p, T, \mu, k, c, g$ and ρ are velocity, time, pressure, temperature, viscosity, thermal conductivity, specific heat, gravity and density respectively.

The fluid velocity and temperature in this regime are equivalent to the corresponding wall conditions. The boundary layer approximations for a two-dimensional fluid flow in Cartesian coordinates (x, y) are given as

$$u \gg v \,, \qquad \frac{\partial u}{\partial y} \gg \frac{\partial u}{\partial x}, \frac{\partial v}{\partial x}, \frac{\partial v}{\partial y} \tag{4a}$$

$$\frac{\partial T}{\partial y} \gg \frac{\partial T}{\partial x} \tag{4b}$$

The Nusselt number (Nu) for laminar, fully developed flow is constant and independent of the Reynolds number (Re), the Prandtl number (Pr) and the axial location of the channel.

Slip Flow Regime

The current standing on the study of gaseous slip flow in microchannels stipulates that, although the continuum assumption is no longer valid within the slip region, Navier–Stokes equations are still applicable with some boundary modifications. The continuum model will apply at the core of the flow and a modified molecular/continuum boundary condition at the boundaries. That is, the Navier–Stokes equations are applicable except in the layer next to the surface. The commonly used slip boundary conditions are called Maxwellian boundary conditions. Since they are first order in accuracy, other extended boundary conditions are proposed in [1]. In the Knudsen layer, the layer one mean free path away from the boundary, the Maxwellian velocity slip boundary condition approximates the true gas velocity at the boundary by the velocity that the molecules would have if a linear velocity gradient existed, as shown in Fig. 2. In other words, the magnitude of the slip is calculated from the velocity gradient evaluated at $y = \lambda$.

The first-order approximation to the velocity slip within the Knudsen layer is given by

$$u_{\mathrm{s}} = \frac{2 - F_{\mathrm{m}}}{F_{\mathrm{m}}} \lambda \frac{\mathrm{d}u}{\mathrm{d}y} \tag{5}$$



Single-Phase Gaseous Flow, Figure 2 Schematic of the first-order slip velocity approximation

Another characteristic of rarefied gas flow is that there is a finite difference between the fluid temperature at the wall and the wall temperature. The temperature jump is first proposed to be

$$T_{\mathrm{s}} - T_{\mathrm{w}} = c_{\mathrm{jump}} \frac{\partial T}{\partial y} \tag{6}$$

The thermal accommodation coefficient is defined as

$$F_{\mathrm{T}} = \frac{Q_{\mathrm{i}} - Q_{\mathrm{r}}}{Q_{\mathrm{i}} - Q_{\mathrm{w}}}$$

where Q_{i} is the energy of the impinging stream, Q_{r} is the energy carried by the reflected molecules and Q_{w} is the energy of the molecules leaving the surface at the wall temperature. F_{T} can be defined as the fraction of molecules reflected by the wall that accommodated their energy to the wall temperature. Let us assume that the temperature of the approaching molecules is T_{s}. The energy difference of these molecules can be written as the summation of the kinetic energy, internal energy and contribution of the incoming molecules to the conduction minus the energy of the outgoing molecules at the wall temperature as

$$Q_{\mathrm{i}} - Q_{\mathrm{w}} = \frac{c_{\mathrm{v}} \left(T_{\mathrm{s}} - T_{\mathrm{w}} \right) (\gamma + 1) P}{2\sqrt{2\pi R T}} + \frac{1}{2} k \frac{\partial T}{\partial y} \tag{7}$$

where $R = c_{\mathrm{p}} - c_{\mathrm{v}}$ and $\gamma = c_{\mathrm{p}} / c_{\mathrm{v}}$.

The net energy carried to the surface, $Q_{\mathrm{i}} - Q_{\mathrm{r}}$, is equal to the heat flux at the wall

$$Q_{\mathrm{i}} - Q_{\mathrm{r}} = k \frac{\partial T}{\partial y} \,. \tag{8}$$

Therefore the temperature jump in Eq. (7) is derived to be [2]

$$T_{\mathrm{s}} - T_{\mathrm{w}} = \frac{2 - F_T}{F_T} \frac{2\gamma}{\gamma + 1} \frac{\lambda}{\mathrm{Pr}} \frac{\partial T}{\partial y} \tag{9}$$

Equation (9) gives the first-order approximation to the temperature jump, and it is assumed that the temperature gradient at the wall is the same as that at $y = \lambda$. The same approach is applied to obtain the second-order velocity slip equation [1]. This results in

$$\theta_{\mathrm{s}} - \theta_{\mathrm{w}} = \frac{2 - F_T}{F_T} \frac{2\gamma}{\gamma + 1} \frac{\mathrm{Kn}}{\mathrm{Pr}\,(1 - a\mathrm{Kn})} \left(\frac{\partial \theta}{\partial \eta} \right)_0 \tag{10}$$

where $\theta = T/T_{\mathrm{reference}}$ and a is a variable.

The gaseous flow heat transfer problem in the slip flow region is solved both analytically and numerically. Larrode et al. [2] solved the problem for micro-circular tubes with constant wall temperatures. Beskok et al. [3] presented computational results in the slip flow region for Knudsen number less than 0.3. Yu and Ameel [4] studied laminar, fully developed slip flow forced convection heat transfer in rectangular microchannels by applying a modified generalized integral transform. The compressibility effects in the slip flow were included in [5, 6] and the results agreed with previous experimental results. It was found that compressibility is significant for high Re and rarefaction is significant for low Re. Exact, analytical solutions for flows in circular, rectangular and parallel plate microchannels were given by Tunc and Bayazitoglu [7, 8]. The neglected frictional heating effects in low-velocity gaseous flows of macrochannel flows are found to be significant for microchannel flows. Bayazitoglu and Kakac [9] reviewed the flow regimes, and Bayazitoglu et al. [10] reviewed mathematical solutions to gaseous slip flows.

Slip Flow Nusselt Number for Different Geometries

The steady-state heat convection between two parallel plates and in circular, rectangular and annular channels with uniform heat flux and uniform temperature boundary conditions including the viscous heat generation for thermally developing and fully developed conditions are solved. Both constant wall temperature and constant heat flux boundary conditions are considered. The velocity and the temperature distributions are derived from the momentum and energy equations by using the proper slip flow boundary conditions. To have a better understanding of the viscous heating effects, the following parameter to combine the effects of the Brinkman number (Br) and the Graetz number (Gz) is used:

$$\frac{\mathrm{Br}}{\mathrm{Gz}} = \frac{\nu u_{\mathrm{m}}}{c_{\mathrm{p}}\,(T_0 - T_{\mathrm{s}})} \frac{L}{D^2} \tag{11}$$

Using the integral transform method, Yu and Ameel [4] solved for Nu for flow in a rectangular microchannel subject to the constant temperature and slip flow boundary conditions. They did not include viscous dissipation in the work, but they included variable thermal accommodation coefficients. Similar to [7], they concluded that Kn, Pr, aspect ratio, velocity slip and temperature jump can all cause Nu to deviate from the conventional value. Overall it is found that the heat transfer coefficient is strongly influenced by variation of Kn.

Transition and Free-Molecular Flow Regime

As the flow enters the transition flow regime and continues into the free-molecular flow regime, Kn becomes significant enough that the molecular approach has to be utilized. Thus, the Boltzmann equation

$$\frac{\partial f}{\partial t} + v_i \frac{\partial f}{\partial x_i} + F_i \frac{\partial f}{\partial \xi_i} = Q\,(f,f) \tag{12}$$

should be considered to fulfill the atomic level of studies of the gaseous flows in the transition regime. The Boltzmann equation denotes v_i as the velocity, F_i as the forcing function and f as the particle velocity distribution function in space, while $Q(f,f)$ describes the intermolecular collisions. The density can be obtained by integrating f over time and space. The integration of the product of the density and the velocity will provide the mass velocity. The Maxwellian distribution is the simplest distribution as it is the zeroth-order approximation of the Boltzmann equation.

The Boltzmann equation is solved by the particulate methods, molecular dynamics (MD), the direct simulation Monte Carlo (DSMC) method or by deriving higher order fluid dynamics approximations beyond Navier–Stokes, which are the Burnett equations. The Burnett equation

$$f = f^{(0)} + \mathrm{Kn} f^{(1)} + \mathrm{Kn} f^{(2)} + \cdots \tag{13}$$

is the first three terms of the Champan–Enskog equation. The simplified Boltzmann equation can be solved using the lattice Boltzmann method (LBM) for the distributed function on a regular lattice. Being a deterministic approach, the MD method simulation may require a very large domain for gaseous flows while the DSMC is a stochastic approach and is simulated more efficiently for gaseous flows. When $\mathrm{Kn} = 0.06 - 1.1$, the flow is called transition flow and the continuum assumption becomes invalid; the DSMC method also requires a large number of particles, which makes it expensive in terms of computational time and memory requirements.

Another mechanism that may affect the velocity profile in a microchannel is thermal creep. It is a molecular transport phenomenon that occurs when two isopressure containers at different temperatures are connected by a channel whose diameter is close to the gaseous mean free path. Under this condition, gaseous molecules start to flow from the cooler container to the hotter container. Thus, a positive temperature gradient along the flow direction tends to increase the mass flow rate while a negative temperature gradient tends to reduce the mass flow rate. The inclusion of the thermal creep effect in the slip boundary condition is given in by the following formula:

$$u_s = \frac{2 - F_m}{F_m} \mathrm{Kn} \frac{\partial u}{\partial \eta} + \frac{3}{2\pi} (\gamma - 1) \, \mathrm{Kn}^2 \mathrm{Re} \frac{\partial \theta}{\partial \zeta} \qquad (14)$$

The large surface-to-volume ratio in microchannels tends to enhance several factors that are neglected in macroscale flow and heat transfer, such as surface friction, compressibility, surface roughness, viscosity, channel surface geometry, surface electrostatic charges, axial wall heat conduction and measurement errors. Certainly more experimental measurements would be necessary to resolve the various discrepancies.

Cross References

- ► Gas Flow in Nanochannels
- ► Heat Transfer in Microchannel Flows
- ► Lattice Boltzmann Method (LBM)
- ► Microchannel
- ► Molecular Dynamics

References

1. Bayazitoglu Y, Tunc G (2002) Extended Slip Boundary Conditions for Microscale Heat Transfer. AIAA J Thermophys Heat Transf 16(3):472–475
2. Larrode FE, Housiadas C, Drossinos Y (2000) Slip Flow Heat Transfer in Circular Tubes, Int J Heat Mass Transf 43:2669–2680
3. Beskok A, Karniadakis GE, Trimmer W, (1996) Rarefaction and compressibility effects in gas microflows. J Fluid Eng 118:448–456
4. Yu SP, Ameel TA (2001) Slip-flow heat transfer in rectangular microchannels. Int J Heat Mass Transf 44(22):4225–4235
5. Asako Y, Pi T, Turner SE, Faghri M (2003) Effect of compressibility on gaseous flows in micro-channels. Int J Heat Mass Transf 46:3041–3050
6. Chen CS (2004) Numerical method for predicting three-dimensional steady compressible flow in long microchannels. J Micromech Microeng 14:1091–1100
7. Tunc G, Bayazitoglu Y (2001) Heat Transfer in Microtubes with Viscous Dissipation. Int J Heat Mass Transf 44:2395–2403
8. Tunc G, Bayazitoglu Y (2002) Heat Transfer in Rectangular Microchannels. Int J Heat Mass Transf 45:765–773
9. Bayazitoglu Y, Kakac S (2005) Flow regimes in microchannel single-phase gaseous fluid flow. In: Kakac S, Vasiliev L, Bayazitoglu Y, Yener Y (eds) Microscale Heat Transfer – Fundamentals and Applications. Kluwer Academic, Amsterdam
10. Bayazitoglu Y, Tunc G, Wilson K, Tjahjono I (2005) Convective Heat Transfer for Single-Phase Gases in Microchannel Slip Flow: Analytical Solutions. In: Kakac S, Vasiliev L, Bayazitoglu Y, Yener Y (eds) Microscale Heat Transfer – Fundamentals and Applications. Kluwer Academic, Amsterdam

Slip Boundary

► Single-Phase Gaseous Flow

Slip Flow Regime

► Gas Flow in Nanochannels

Slip Velocity

Definition

Non-zero velocity of a fluid at a solid-fluid interface in situations when the no-slip boundary condition is not necessarily applicable. Generally not well characterized or understood for microfluidic devices.

Cross References

- ► Surface-Directed Capillary Flow Systems

Slope Method

► Electrical Current Monitoring Methods

Slug Flow

► Taylor Flow in Microchannels

Smart Skin

► Flexible Shear Stress Sensor

Smoluchowski Equation

Definition

The Smoluchowski equation is used to relate average flow (v_{av}) velocity to electric field strength (E_z) in electroosmotic flows. Under the conditions of a thin double layer or a large channel height (i. e a plug-like or constant velocity profile), it can be expressed as follows:

$$v_{av} = \frac{(\varepsilon_0 \varepsilon_r)\zeta}{\mu} E_z \, , \qquad (1)$$

where ε_0 and ε_r are the electrical permittivity of a vacuum and the relative dielectric constant, respectively. Zeta potential is represented by ζ, and μ is the solution viscosity. The proportionality constant $(\varepsilon\zeta/\mu)$ is often referred to as the electroosmotic mobility.

Cross References

- ► Temperature Effects on the Zeta Potential

Smoothing Function

- ► Kernel Function

SNP on Chip – Micro- and Nanofluidics for Single Nucleotide Polymorphism Discrimination

David Erickson
Sibley School of Mechanical and Aerospace Engineering,
Cornell University, Ithaca, NY, USA
de54@cornell.edu

Synonyms

Nucleic acid detection

Definition

Single Nucleotide Polymorphisms (SNPs) are single base pair differences in individuals where the less common variant occurs in only a small portion of the total population. Detection of these SNPs is proving to be a useful technique for the diagnosis of a variety of genetic diseases and disorders. In this article microfluidics based techniques for SNP discrimination are explored.

Overview

Single Nucleotide Polymorphisms

Single Nucleotide Polymorphisms (SNPs) are single base pair differences in DNA amongst individuals where the less common variant occurs in at least 1% of the total population [1]. The decoding of the human genome has given us access to more than 3 million SNPs (roughly 1 every 100 – 300 bases) and opened up exciting new capabilities for associating individual SNPs, haplotypes and linkage disequilibrium with disease states and pharmacological responses. The first of these associations represents the simplest of cases, where the SNP alleles are the actual sequence variants that result in differences in gene function (by inducing sequence errors in the expressed protein or the exons it contains) or regulation (as a result of the SNP occurring within a promoter region). In general however the vast majority of SNPs fall into one of the latter two categories in that they do not contribute directly to disease states, but can serve as genetic markers that can be used to find functional SNPs as a result of associations between the two. In such cases many SNPs (in exons, introns and other non coding regions) may all be associated with a disease state or phenotype though only a single one may have a direct effect.

To make good use of SNPs for finding genes related to disease and studying their function, for genotyping them in many individuals, for finding their frequencies in pooled samples and for discerning haplotypes, better and cheaper technological methods are needed for discovering SNPs. At present the technology is not yet cheap enough for studies that would genotype thousands of individuals for hundreds of thousands of SNPs across the genome in order to see which variants are most closely associated with a disease phenotype [2]. The purpose of this article will be to introduce some of the ways micro- and nanofluidic technology is making progress towards addressing this issue. The first *Basic Methodology* section will introduce some of the existing chip based techniques for interrogating SNPs with a focus on surface phase hybridization techniques as being the most commercially viable. The *Key Research Directions* section will then describe how these techniques are being implements in microfluidic formats. In the final section a discussion regarding how these technologies can or should be extended to handle future analytical needs will be provided.

Basic Methodology

Techniques for SNP Screening

All allele-specific SNP discrimination techniques suitable for high throughput genetic analysis can be categorized as either being either primer extension, oligonucleotide ligation, invasive cleavage or hybridization based [3]. There are numerous variants on the primer extension technique however all are based on the ability of DNA polymerase to incorporate specific deoxyribonucleotides that are complementary to the sequence of the template DNA [4]. An entire class of techniques based on electrophoretic separation have also been developed and include: heteroduplex analysis (HA), single-strand conformation polymorphism (SSCP), denaturing gradient gel electrophoresis (DGGE), temperature gradient gel electrophoresis (TGGE), allele-specific PCR amplification and ligase chain reaction/ligase detection reaction (LCR/LDR).

Of all these, the technique that has shown the most commercial promise has been surface phase DNA microarray technologies, involving large-scale DNA sequence detection based on hybridization between complementary DNA sequences on a solid support. In recent years a number of DNA microarray and DNA chip type devices have been developed and commercialized (examples include LabCard by ACLARA Bio Sciences, GeneChip by Affymetrix, NanoChip by Nanogen). Such devices enable parallel DNA or RNA analysis to be carried out in a format that typically includes some functional microfluidic technology which serves to increase the rate at which targets are delivered to the region of interest (either by increasing the probability of target-surface collisions through physical confinement near the probesite or direct electro-active attraction). Though broadly useful to study a number of different target: probe binding systems, such chips are commonly used gene expression analysis or Single Nucleotide Polymorphism (SNP) discrimination applications.

Such high throughput DNA microarray technologies can simplify SNP analysis, but most methods require several hours for hybridization (due to diffusion-limited reaction kinetics) and complicated washing steps demanding strict temperature and buffer salt-content control. In addition, microarray hybridization and washing manipulation is conducted on centimeter-scale glass substrates thereby requiring that large quantities of DNA target sample be used. While numerous techniques have been identified for amplifying the signal, recently even to the point where SNP identification can be performed without the need for target amplification (via PCR), such processes require complex and, often, expensive labeling steps. The main difficulty with such devices however relates to the infrastructure/sensitivity tradeoff whereby either a large expensive tabletop optical apparatus (often con focal) is used to perform ultra-sensitive detection or a smaller footprint (though still relatively large) laser scanner is used to perform much more rapid analysis however the detection sensitivity is significantly lower. Such post-reaction scanning systems typically also lack the ability to monitor reaction kinetics. Based on these limitations the requirements outlined in Fig. 1 are proposed as requirements for next generation SNP discrimination techniques. These conditions will be revisited in the *Future Directions* section of this article.

Key Research Findings

As mentioned above, this section will review the state of the art in microfluidics based SNP discrimination with the goal of providing as broad of an overview of the existing technology as possible. As this review by necessity is somewhat cursory, it will be followed up with a more detailed description of a particular *electrokinetically based* on-chip SNP discrimination technique. The overall thrust of this section will be to determine to what degree exiting microfluidic technology can be used to address the next generation needs described in Fig. 1.

Next generation SNP discrimination techniques should…

1. Have high throughput capabilities, enabling multiplexing of both interrogated SNPs and (less importantly) patient samples on the same device.
2. Minimize the total amount of time and handling required to perform a multiplexed reaction.
3. Enable either disposability or reusability functionality.
4. Be sufficiently sensitive to so as to work with raw, unamplified samples.

SNP on Chip – Micro- and Nanofluidics for Single Nucleotide Polymorphism Discrimination, Figure 1 Requirements for next generation Single Nucleotide Polymorphism Screening Technologies. A technique which meets the above requirements is required to perform the large scale population screening studies

State of the Art in Integrated Microfluidic Devices for Single Nucleotide Polymorphism Discrimination

As described throughout this encyclopedia, microfluidic (Lab-on-a-Chip) technologies enable processing small liquid volumes in a rapid and controlled manner which has proven especially useful for analysis in life sciences. In the early 2000's several researcher groups began to investigate the integration of multiple microfluidic-based technologies into single microscale platforms with the goal of developing integrated technologies for performing nucleic acid analysis. Designs included paramagnetic or glass bead based devices, poly(methylmethacrylate) (PMMA) chips exploiting universal zip code arrays and polycarbonate (PC) chips designed to be credit card sized all of which proved successful in accelerating and automating detection of hybridization events (see Erickson and Li [5] for a more comprehensive review of these devices).

Commonly, a necessity for obtaining maximum discrimination between fully matched target: probe complexes



SNP on Chip – Micro- and Nanofluidics for Single Nucleotide Polymorphism Discrimination, Figure 2 Integrated Microfluidic Devices for (**a**) Parallel Polymerase Chain Reaction and (**b**) DNA hybridization (from [5])

and those containing a single-base base pair mismatch in a microfluidic chip is accurate control of the thermal conditions at the reaction site (whether it be in solution or at a surface). This has been largely accomplished through the integration of external heaters and thermal sensors (e. g. RTDs) on chip thereby adding an additional level of device complexity to that required for simple hybridization detection. Figure 2 illustrates recently developed devices for PCR (Fig. 2a) and surface phase DNA hybridization (Fig. 2b) which incorporate such functionality. PCR amplification was one of the first on-chip applications which required this type of control. In what were some of the first prominent examples Kopp, deMello and Manz [6] used a copper heating block for continuous-flow PCR in a microfluidic channel, while others such as Lao et al. [7] used high thermal conductivity silicon-based devices to achieve precise temperature control and rapid cooling in cycling based device. As for devices specifically devices for SNP detection, Buch et al. [8] reported a TGGE method based on the presence of a controllable temperature gradient on a polymer microfluidic chip. Platforms for high-throughput on-chip temperature gradient assays were also developed by Mao et al. [9] who demonstrated discrimination of fully complementary DNA strands from those containing a single T–G or C–A mismatch. This was also done using SYBR Green I intercalating dye and was reported for parallel and combinatorial measurements. As described above these devices required the incorporation of temperature control units, external heaters and thermal sensors on the microfluidic chips making it possible to control and rapidly change the temperature in order to produce spatial temperature gradients. In a recent work, Blazej et al. [10] developed what they terms a *microfabricated bioprocessor* which integrated all three steps involved in Sanger sequencing (namely thermal cycling, sample purification, and capillary electrophoresis). Using this device they demonstrated a 99% read accuracy over 556 bases. The device presented in that work represents one of the most integrated microfluidic systems developed at time of publication incorporating such elements as pneumatic microvalves and electrokinetic flow control elements and low dispersion turns in addition to thermal control and monitoring elements. Of note is that in the majority of these devices, hydrodynamic pumping techniques have been relied upon for performing the majority of the primary transport operations (the exception of course being those which rely on an electrophoresis step).

Electrokinetically Based Single Nucleotide Polymorphism Discrimination

On the length scales relevant to microfluidic devices, fluid flow and species transport can be accomplished using numerous different techniques, a few of which include: traditional pressure driven (pneumatic) flow, electrokinetic transport, buoancy, magnetohydrodynamics, capillarity, electrowetting and thermocapillarity (see Stone et al. [11] for a comprehensive overview). While electrokinetic means can greatly simplify species transport in microfluidic systems (see the section ►electroosmotic flow), an effect commonly considered a significant drawback is the internal heat generation caused by current flow through the buffer solution. To maintain uniform and controlled system temperatures required for SNP discrimination, devices must have the ability to rapidly reject this heat to the surroundings. This problem is enhanced as a result of the recent shift towards low cost polymeric microfluidic systems (which will be discussed in greater detail in the final section) fabricated from such low thermal conductivity polymeric materials as poly(dimethsiloxane) (PDMS) and poly(methylmethacrylate) (PMMA) as opposed to tra-



SNP on Chip – Micro- and Nanofluidics for Single Nucleotide Polymorphism Discrimination, Figure 3 Electrokinetically based SNP discrimination technique (**a**) Schematic describing electrokinetically based SNP discrimination technique applying an electrokinetic driving potential allows for precise manipulation of the thermal (through Joule heating), shear (through electroosmotic flow) and electrical (through electrophoresis) forces enabling the SNP to be discriminated. (**b**) H-type channel structure probesite layout for electrokinetically-based single nucleotide polymorphism discrimination. Four regions were robotically spotted onto the chip each with 8 individual probesites shown as SMN1 and SMN2 in the figure. For the purposes of this work the same probes were used for each spot in the individual regions for DNA hybridization chip. Input ports labeled as (1) sample port, (2) waste port, (3) buffer port and (4) auxiliary port. (**c**) Optimal discrimination for both SMN1A and SMN2A target. Data points show ratio of average intensity over the matched probesite to the average intensity of the mismatched probesite. Peak represents point where ratio of match intensity to mismatch intensity is greatest

ditional materials such as glass or silicon. The primary attractiveness of these materials is that they tend to involve simpler and significantly less expensive manufacturing techniques while still being amenable to surface modification and probe functionalization. The low thermal conductivities inherent in these materials (0.18 W/mK for PDMS which is an order of magnitude lower than that of glass) retards the rejection of internally generated heat during electroosmosis.

As mentioned above we have recently developed a novel on-chip electrokinetically-based microfluidic technique for SNP discrimination (see Erickson et al. [12] for details). The traditional advantages in terms of flow and sample handling afforded by electrokinetic transport described in the electroosmotic flow section of the article were extended to include thermal control through on-line manipulation of the Joule heating conditions. Precise control of the thermal, shear and electrical conditions at the probe sites were shown to enable discrimination of single-base-mismatch SNP sample targets on the chip by exploiting differences in denaturation energetics. This technique is expanded on in this article as it uniquely demonstrates how detailed understanding of fluid dynamics and thermal transport on the micro- and nanoscales can be exploited to control reaction specificity without the need for incorporating additional device functionality.

A schematic of the discrimination technique is shown in Fig. 3. As can be seen under standard conditions (or at low applied voltage) both the fully matched hybrid and that with a single base pair mismatch remain hybridized making discrimination difficult. Applying an electrokinetic driving potential allows for manipulation of the thermal (through Joule heating), shear (through electroosmotic flow) and electrical (through electrophoresis) forces above the microarray. To demonstrate the clinical utility of the technique, the detection of single base pair mutations in the survival motor neuron gene, associated with the childhood disease Spinal Muscular Atrophy, was performed. Specifically the technique was applied to the detection of the common C→T mutation in the SMN1 gene resulting in what is known as SMN2 (and is found in all SMA patients). Such mutations lead to the loss of alpha-motor neurons and subsequently the wasting of voluntary muscles.

To determine the optimal conditions for SNP discrimination, a series of incrementally increasing voltages were applied during the discrimination step, ranging from 100 V/cm to 600 V/cm within the hybridization array. Figure 3c compares the florescence intensity of the matched probe sites with that of the mismatched probe sites for both SMN1A and SMN2A targets. While the intensity ratios remained constant at lower voltages, a clear optimum in the discrimination existed for each different target:probe complex, at 460 V/cm and 525 V/cm, respectively. The difference in the optimal potential gradient between these two cases can be attributed to the slightly larger change in the thermodynamic stability associated with the SMN1A:SMN2 hybrid.

Future Directions for Research

In the preceding two sections an overview of microfluidics based SNP discrimination technology has been presented and thus when defining future directions for research it makes sense to compare these devices with each of the needs as expressed in Fig. 1. Continuing the theme from above here we focus more on technology development rather than clinical applications (for more details on the latter of these readers are referred to Motsinger et al. [13].

The first condition for next generation technology outlined in Fig. 1 relates to the development of highly multiplexed devices that enable simultaneous screening of multiple samples against multiple SNPs. While most of the surface phase binding based chips described above have generally targeted a small number of specific SNPs for demonstrative purposes, the extension to the kind of parallelity used in microarray formats is relatively easy. This is as a result of the numerous microfluidic technologies have been developed for dispersing samples over relatively large interrogation areas and the well developed detection/scoring infrastructure. Devices which rely on what have classically been more serial technologies (e. g. capillary electrophoresis) can have many analytical advantages over binding assays (such as enabling Sanger-type sequencing as discussed above) but are likely to face parallelity roadblocks in the future unless more cost-effective multiplexing technologies can be developed.

The second requirement for next generation technologies pertains to minimizing the time and handling required to perform a complete assay. Great advances have been made along these lines in the past 2 – 3 years largely thanks to the development of multi-layer soft lithography [14]. This technology has enabled the incorporation of pneumatic pumps, valves and other flow control elements on chip with relative ease. Given that, much of the effort in the field is therefore directed towards pushing the analytical technology upstream towards processing real patient samples or at least minimizing the number of manual processing steps. Almost inevitably however incorporation of additional on-chip functionality increases the final cost-per-chip and thus a trade off has to be made between how much manual processing the customer is willing to tolerate in order to keep total device costs down. In a research environment, where tests are likely to be conducted by a technician or graduate student with a relatively sophisticated level of expertise, this tolerance level is likely to be relatively high. For point of care applications the requirements are much more stringent.

The third condition relates to disposability or reusability of devices. In general disposability is so ingrained in the medical community that even if washing technologies were developed to the point that the potential for cross contamination could be effectively eliminated, it seems unlikely that reusable devices are likely to have a significant commercial impact. As alluded to above this suggests that development efforts should be focused on polymer devices, where device fabrication can be done using relatively simple and inexpensive casting or hot embossing techniques. This simplification of the fabrication steps tends to conflict with the requirements mentioned above for the basic thermal control (that facilitates SNP discrimination) let alone some of the desired additional upstream functionality. Since fabrication technology is reasonably well developed, research directed towards the development of techniques that can perform the desired analytical operations without the need for additional on-chip functionality (such as the electrokinetic SNP discrimination technique described above) is certainly warranted.

Most of the existing technologies discussed above require some sort of upstream PCR amplification step to bring the target concentration up to detectable levels. This step requires additional time, more functionality to be incorporated onto a chip and limits the degree of multiplexing. For the reasons discussed above therefore it would be desirable if this step could be eliminated in favor of sensor systems which have sufficient sensitivity and specificity to detect relatively minute quantities of a target in its unamplified state. Achieving this task in a multiplexed format requires research that takes an overall systems view of device development looking at the coupling of sensitivity, specificity, transport and repeatability in the context of a whole device, as opposed to a component view as is commonly done at present.

Cross References

► DNA hybridization

References

1. Brooks L (2003) Single Nucleotide Polymorphisms. In: Kwok P (ed) SNPs: Why do we care? Humana Press, Totowa, NJ
2. Risch N, Merikangas K (1996) The future of genetic studies of complex human diseases. Science 273(5281):1516–1517
3. Kwok PY (2001) Methods for genotyping single nucleotide polymorphisms. Annu Rev Genomics Hum Genet 2:235–258
4. Sobrino B, Brion M, Carracedo A (2005) SNPs in forensic genetics: a review on SNP typing methodologies. Forensic Sci Int 154(2–3):181–194
5. Erickson D, Li DQ (2004) Integrated microfluidic devices. Anal Chim Acta 507(1):11–26
6. Kopp MU, de Mello AJ, Manz A (1998) Chemical amplification: Continuous-flow PCR on a chip. Science 280(5366):1046–1048
7. Lao AIK, Lee TMH, Hsing IM, Ip NY (2000) Precise temperature control of microfluidic chamber for gas and liquid phase reactions. Sens Actuators Phys 84(1–2):11–17
8. Buch JS, Kimball C, Rosenberger F, Highsmith WE, DeVoe DL, Lee CS (2004) DNA mutation detection in a polymer microfluidic network using temperature gradient gel electrophoresis. Anal Chem 76(4):874–881
9. Mao HB, Holden MA, You M, Cremer PS (2002) Reusable platforms for high-throughput on-chip temperature gradient assays. Anal Chem 74(19):5071–5075
10. Blazej RG, Kumaresan P, Mathies RA (2006) Microfabricated bioprocessor for integrated nanoliter-scale Sanger DNA sequencing. Proc Natl Acad Sci USA 103(19):7240–7245
11. Stone HA, Stroock AD, Ajdari A (2004) Engineering flows in small devices: Microfluidics toward a lab-on-a-chip. Annu Rev Fluid Mech 36:381–411
12. Erickson D, Liu XZ, Venditti R, Li DQ, Krull UJ (2005) Electrokinetically based approach for single-nucleotide polymorphism discrimination using a microfluidic device. Anal Chem 77(13):4000–4007
13. Motsinger AA, D Ritchie M, Dobrin SE (2006) Clinical applications of whole-genome association studies: future applications at the bedside. Expert Rev Mol Diagn 6(4):551–565
14. Unger MA, Chou HP, Thorsen T, Scherer A, Quake SR (2000) Monolithic microfabricated valves and pumps by multilayer soft lithography. Science 288(5463):113–116

Soda-Lime Glass

Synonyms

Sodium glass; Sodium silicate glass

Definition

Soda-lime glass is the kind of glass which is most widely used for various purposes. Soda-lime glass is a multicomponent mixture of SiO2 (72.8%), Na_2O (13.7%), CaO (8.8%), MgO (4.0%) and small amounts of Fe_2O_3 (0.12%) and Al_2O_3 (0.1%). Adding sodium carbonate lowers the melting point of the glass, thus lowering the energy required to heat it, but also making it soluble in water. Calcium carbonate or calcium oxide are added to counter this.

Cross References

► Bulk Micromachining

Sodium Glass

► Soda-Lime Glass

Sodium Silicate Glass

► Soda-Lime Glass

Sol–Gel Technique

Dominic S. Peterson
Chemistry Division, Los Alamos National Laboratory,
Los Alamos, NM, USA
DominicP@lanl.gov

Definition

The sol–gel synthetic technique is used to fabricate a porous structure composed of transition metal alkoxides. These structures most commonly utilize a siloxane (Si – O) to form the backbone structure. The synthesis of these sol–gels involves a hydrolysis of a silicone monomer followed by the condensation of the silica into a porous structure with a 3-dimensional networked structure. The physical structures of these sol–gels can be tailored to produce structures with a wide range of useful properties and the chemical surface chemistry can be modified to produce various surface interactions.

Overview

Sol–gel chemistry is a versatile tool that can be used to produce organic and inorganic hybrid materials that have properties that can be difficult to obtain from only inorganic or organic synthetic approaches. The synthetic approach involves the polycondensation of sol–gel active molecules to form a macromolecular network structure.



Sol–Gel Technique, Figure 1 Hydrolysis of tetramethyl ortho silicate to silanol

Basic Methodology

The synthesis of a sol–gel follows three primary steps [1]. First, the transition metal monomers are hydrolyzed to form a tetrahydroxy alkoxide. Because most sol–gels are formed from silica monomers the remainder of the discussion will focus on silica sol–gels. The hydrolysis step for silica sol–gels typically involves the use of either tetramethyl ortho silicate (TMOS) or tetraethyl ortho silicate (TEOS). The side product of the reaction is the corresponding alcohol (Fig. 1).

Once the tetrahydroxy silane has been formed, the silica will condense to form larger silica molecules and oligiomers (Fig. 2). This formation of the sol (or small colloidal silica particles) can be controlled to produce particles that have a particular size or size distribution.

Once the sol has been formed, they will cross-link to form a gel structure. This formation of a gel from the sol gives the materials the name sol–gel (Fig. 3). This crosslinking is achieved through a poly-condensation step. This step is the same as the condensation step, except that is results in a structure that is highly crosslinked. The size and amount of cross linking is dependant on the pH of the system and also the presence (and amount of) any other alkyl groups in the silica monomers ($-\mathrm{Si}-\mathrm{OR}$). It should also be noted that a wide range of chemical functionalities can be incorporated into the eventual sol–gel by the use of monomers that have useful alkyl groups incorporated into the structure. Alternatively, it is possible to modify the sol–gel after it has been formed by the condensation of a functional silane onto the sol–gel surface.

The relative rates of reaction between the hydrolysis, condensation, and polycondensation directly affect the type and quality of sol–gel produced. For instance, in base catalyzed sol–gel synthesis, the rate of the hydrolysis reaction is much slower than the polycondensation step, which tends to form a polymeric structure that is highly branched with relatively large particles. In contrast, in acid-catalyzed sol–gel synthesis the rate of the hydrolysis reaction is much faster than the polycondensation step, which favors the formation of linear polymers. This also tends to form much smaller particles that the gel is composed of, which results in materials with much higher porosities and higher surface areas than is formed with sol–gels formed in base-catalyzed reactions. Therefore acid-catalyzed synthesis tends to produce materials that have properties that are preferable for microfluidic applications.

Another process that is essential to the properties of the sol–gel produced is aging. When the gel that is formed is maintained in liquid its structure and properties continue to change after the gel has been formed. There are three processes that continue to change the properties of the sol–gel during aging. These include polycondensation, syneresis, and coarsening. Polycondensation reactions continue to occur within the gel as long as silanol groups are close enough to one another to react with one another. This continues to increase the connectivity within the gel network. Syneresis is the shrinkage of the gel and the expulsion of liquid from the pores of the gel. This shrinkage is attributed to the formation of new bridging siloxane bonds through condensation, which causes the gel to contract. The amount of shrinkage will increase with higher concentrations of silica in the gel and at higher temperatures. Coarsening is the decrease in surface area through dissolution and reprecipitation of dissolved material within the gel network. Due to the solution microenvironment, this precipitation of material is irreversible. The overall aging process is affected by several parameters including time, pH, temperature, and inclusion of organic solvents in the gel system. Through the control of the aging process it is possible to produce sol–gels with specific porous structure including the particular surface area that is needed for specific applications.

The preparation of sol–gels is a simple and straightforward process. Because the precursor sol has a low viscosity, it



Sol–Gel Technique, Figure 2 Condensation of two silanols into a dimer



Sol–Gel Technique, Figure 3 Schematic of conversion of the sol into a gel structure

is easy to place it into any mold (including a microfluidic channel) and then form the gel. The primary limitation on the mold is that it needs to avoid adhesion of the sol solution, and it must not lead to the formation of bubbles during filling or during the gelation process.

Key Research Findings

In the past decade there has been intense interest in the use of sol–gels for use in microfluidic and nanofluidic applications. The most widespread use of sol–gels in microfluidic systems has been for capillary electrochromatography (CEC). CEC is a separation technique in which an electrical potential is applied across a capillary (containing a packing material) and the ionic functionalities generates bulk flow through the capillary through electroosmosis. The separation of non-ionic analytes can then be achieved as the analytes will partition between the mobile phase and the packing stationary phase. Sol–gels have provided an excellent method to make CEC columns, as they are simple to prepare within the capillary and they easily crosslink with the silica surfaces of the capillary, thus immobilizing them. Furthermore, in addition to using functionalized silica monomers in the preparation of a CEC sol–gel column, it is also possible to modify the silica surface with functionalized siloxanes. This enables the column to have higher thermal and solvent stability. The sol–gel process for preparing CEC columns enables the surface chemistry to be controlled and the selectivity of the column to separate different compounds can be adjusted for specific applications.

There are two types of preparation that are used to make CEC columns [2]. The first approach involves fully filling the capillary with the sol–gel solution. This method produces a sol–gel that fully fills the capillary, and thus produces the maximum amount of surface area for separation processes. However, fully filling the column with a sol–gel leads to a higher rate of bubble formation under the high voltage conditions utilized for CEC separations. The preparation of filled CEC sol–gel columns involves pre-treating the capillary, preparing the sol and filling the capillary with the sol-solution. After this, the gel step is performed and the sol–gel is formed in situ. After the sol–gel is formed there is typically a rinsing step that is used to remove un-reacted sol and to fill the column with a solution that is more suitable for electrophoretic operations. The other approach to sol–gel columns is the preparation of open tubular columns in which the sol–gel is coated on the interior surface of the capillary. The greatest difficulty in preparing open tubular is in preparing sol–gel coatings which are relatively thick, stable, reliable, and reproducible. There have been many examples of sol–gel CEC columns, and they have been shown to enable separations that have high efficiency and are quite reproducible.

The preparation of open tubular CEC sol–gel columns first involves the pre-treatment of the capillary and the preparation of the sol. The gel step for open tubular columns is allowed to proceed for only a short period of time (i. e. 20 min). This short time allows the gel to begin to form, typically silanol containing groups will began to react with other silanols in the immediate vicinity. This includes the sol reacting with the silanol groups at the surface of the silica capillary. When the non-reacted sol is rinsed out of the capillary all of the sol–gel that is not covalently attached to the wall of the capillary will be rinsed out. This will leave a layer of the sol–gel on the interior of the capillary.

While the use of sol–gels in capillaries has been extensive, their use in microchannels on chips has been more limited, due to the difficulty of fabricating sol–gels within the chip materials. The primary difficulty is in preparing the sol–gel in the region of the chip that it is needed, while excluding it from the areas where it is not needed. One method that has been introduced to fabricate the sol–gel in a particular area of a chip is to use a photoinitiation step to cause the gelation to form in a specific area [3]. This process first involves preparing a sol from a siloxane containing an organic monomer, such as a methacrylate. Once the sol had been prepared it was placed into a UV transparent capillary or chip. The organic functionalities on the sol was then reacted utilizing a UV active initiator under a UV lamp, which causes the sol to become crosslinked through the organic functional linker. Because this reaction is activated using light it is possible to cause the sol to polymerize only in a specific region of interest. The unreacted sol is then rinsed out of the channel. This approach allows the sol–gel to be placed into a very specific portion of the chip or capillary with no residual sol–gel remaining in other portions of the channel. The primary disadvantage to this approach is that it requires that the sol–gel that is fabricated be imparted with very specific organic functionalities in order to enable the photopolymerization step to proceed with high efficiency.

Another approach that has been used to introduce a sol–gel functionality into a microchip has been to either imbed the sol–gel into the microchip or to coat a microchip channel with a sol–gel. The method to imbed sol–gel functionality into a chip involved to preparing a PDMS chip with silica nanoparticles homogeneously distributed throughout the PDMS [4]. This approach produced a chip that was more hydrophilic than normal PDMS. In addition, when these chips were used for capillary electrophoresis analysis, the electroosmotic flow was much higher than in other PDMS chips.

Another application to which sol–gels have been applied is in assays involving various biocatalytic reactions. It has been demonstrated several times that proteins can be easily immobilized within a sol–gel and then used for a variety of applications. Once the proteins are incorporated into the sol–gel structure they still retain their enzymatic activity. This enables a wide array of enzymatic reactors to be prepared including oxidases, lipases, and proteases. Enzymes and even whole cells can be incorporated into the gels to enable flow-through reactors to be simply constructed. The incorporation of proteins into a sol–gels can also be combined with CEC separations to enable the separation of enantiomers.

Sol–gels with encapsulated enzymes have been demonstrated for high throughput screening of catalytic activity [5]. This involved fabricating an array of sol–gel microstructures on a glass slide. This was accomplished by using a PDMS template and then synthesizing the sol–gel with the active enzyme on top of the glass slide. The enzyme kinetics of the encapsulated proteins can then be studied in detail by changing the concentrations of substrate and inhibitor and using different temperatures. This enables rapid detailed analysis of the behavior of the enzyme. The activity of the immobilized enzyme was similar to the free enzyme, which demonstrates that the activity is maintained even in the sol–gel matrix. Each microwell requires only 50 μg of enzyme. These assays have been demonstrated with dozens of enzymes, which further demonstrates the robustness of the method.

In addition to microwell bioreactors for screening of enzymatic activity, enzymes have also been encapsulated into sol–gels for flow-through systems. For instance, trypsin has been fabricated into a sol–gel on a microchip to form a device that performs both digestion and separation on the same device [6]. Because of the proteolytic activity of the trypsin, proteins that are passed through the device are digested into consistuent peptide fragments. The amount of trypsin that was incorporated into the sol–gel was varied between 0.1% and 10% depending on the size of the analyte that needed to be digested and thus the amount of activity that was needed to adequately digest the sample. For sample introduction the driving force for introducing the analyte to the bioreactor was electroosmotic flow. Once the protein was digested it was then separated using the same electrophoretic forces that are used to introduce the protein to the bioreactor. Because the protein will be digested into fragments of different sizes, the different fragments (which are charged) will migrate at different speeds and be separated in the microchip. The overall time that was required for the digestion of the protein and the subsequent separation is much faster than other methods have been.

Protein encapsulation has also been used to prepare sol–gel columns for CEC separations [7]. This involved incorporating a proteins that has a chiral center such as bovine serum albumin or ovomucoid. Because these proteins have a chiral center it is possible to use the hybrid protein/sol–gel column to separate enantiomers. In these separations, the amount of protein that was encapsulated was critically important in resolving the enantiomers, and protein concentrations generally needed to be above 5%. Even at these levels, the total amount of protein loaded was in the range of tens of micrograms.

Pre-concentration of analytes is another application that sol–gel materials have been applied to. Pre-concentration steps are critical in microfluidic analytical systems because the small volumes used require that the concentration be relatively high to allow analytes to be detected. The pre-concentration step typically involves loading the analyte onto the sol–gel in one solvent or solution. The analytes are later released from the sol–gel utilizing another solvent in which the analyte is more soluble than the sol–gel. A wide variety of functional interactions can be utilized to pre-concentrate an analyte. These can include ion-exchange, hydrophobic, and hydrophilic interactions. One major difficulty of these types of pre-concentrators is that it is very difficult to change solvents from one to the other in a microfluidic system. Also, the loading and release solvents must be miscible, which limits the solvents that may be used for pre-concentration operations. An example of sol–gels being used for pre-concentration is in the enrichment of DNA [8]. This process involves first adsorption of the DNA onto the silica in the presence of a salt. The containments are then washed off using an alcohol/water solution, and finally the DNA is eluted utilizing a buffer solution. The DNA that is eluted is suitable for further PCR amplification, which adds to the utility of the process.

Sol–gels can also be used for more than one application at the same time. For instance, it has been shown that a sol–gel column can be produced that enables both pre-concentration and separation of amino acids [9]. The column was prepared with a quaternary ammonium functionality, which gives the sol–gel a positive charge. This unique functionality in the sol–gel enabled amino acids to be preconcentrated and separated on the column with high enrichment and efficiency. Furthermore, the use of a positively charged surface for the silica surface enables the electroosmotic flow to be reversed to that which is normally observed in silica capillaries. This enables specialized separations to be performed on the sol–gel CEC column compared to that which would be normally achievable.

Future Directions for Research

Sol–gel technology is a very mature technique with a wide variety of methods that are known and are widely used. However, there are many opportunities that still exist to expand the sol–gel technique to microfluidic applications. One of the most important areas of future research involve developing microfluidic systems that incorporate multiple functionalities. For instance, a device for proteomic determinations may involve a sol–gel bioreactor to digest proteins, a sol–gel pre-concentrator to enrich the peptide fragments, and a CEC separation phase to separate the peptides prior to detection. Incorporating multiple functionalities will require several additional difficulties to be overcome. In addition to placing the sol–gel in a specific portion of a microchip it will be necessary to prepare multiple columns on a chip without adversely affecting the structure or functionality of the other sol–gel devices on the chip. This may be accomplished by using multiple interconnected channels and placing each sol–gel into its channel individually. It may also require some careful selection of the sol–gels to be prepared so that the preparation can be achieved while not disturbing the other devices. The other area that is ripe for further research is to utilize sol–gels for other functional devices in microfluidics. This could involve making electrokinetic pumps from sol–gels, which would involve fabricating sol–gels with high ionic loading so that a current can be used to cause the sol–gel to act as a pump with no moving parts. It has been demonstrated that a variety of biological proteins can be easily encapsulated into sol–gels. This should be expanded so that other functionalities can be included in microfluidic devices. Other pre-concentration approaches could also be fabricated using sol–gels. Pre-concentration will be a critically important step in microfluidics since the concentrations required for detection is relatively large. It should be possible to make pre-concentrators that would release the anaytes in response to other stimuli, such as heat or light, which would simplify the injection of the analytes into the system.

Cross References

- ► Bead-Based Microfluidic Platform
- ► Capillary Filling
- ► Chromatographic Chip Devices
- ► Electrokinetic Flow in Porous Media
- ► Lab-on-Chip Devices for Chemical Analysis
- ► Lab-on-Chip Devices for Separation Based Detection
- ► Liquid Chromatography
- ► Microfluidic Systems for High-Throughput Screening
- ► Stationary Phases in Microchannels

References

1. Hench LL (1998) Sol–Gel Silica. Noyes Publications, Westwood
2. Malik A (2002) Advances in sol–gel based columns for capillary electrochromatography: Sol–gel open-tubular columns. Electrophoresis 23:3973–3992

3. Dulay MT, Quirino JP, Bennett BD, Kato M, Zare RN (2001) Photopolymerized Sol–Gel Monoliths for Capillary Electrochromatography. Anal Chem 73:3921–3926
4. Roman GT, Hiaus T, Bass KJ, Seelhammer TG, Culbertson CT (2005) Sol–Gel Modified Poly(dimethylsiloxane) Microfluidic Devices with High Electroosmotic Mobilities and Hydrophilic Channel Wall Characteristics. Anal Chem 77:1414–1422
5. Park CB, Clark DS (2002) Sol–gel encapsulated enzyme arrays for high-throughput screening of biocatalytic activity. Biotechnol Bioeng 78:229–235
6. Kato KS, Kato M, Toyo'Oka T (2003) Creation of an On-Chip Enzyme Reactor by Encapsulating Trypsin in Sol–Gel on a Plastic Microchip. Anal Chem 75:388–293
7. Kato M, Kumiko SK, Matsumoto N, Toyo'oka T (2002) A Protein-Encapsulation Technique by the Sol–Gel Method for the Preparation of Monolithic Columns for Capillary Electrochromatography. Anal Chem 74:1915–1921
8. Wolfe KA, Breadmore MC, Ferrance JP, Power ME, Conroy JF, Norris PM, Landers JP (2002) Toward a microchip-based solid-phase extraction method for isolation of nucleic acids. Electrophoresis 23:727–733
9. Li W, Fries DF, Alli A, Malik A (2004) Positively Charged Sol–Gel Coatings for On-Line Preconcentration of Amino Acids in Capillary Electrophoresis. Anal Chem 76:218–227

Solid Phase Extraction

► Lab-on-a-Chip Devices for Sample Extractions

Solutal Marangoni

► Marangoni Convection

Solution Reservoirs on Chips

Definition

The solution reservoirs on chips are small vials connected to the ends of the microchannels and can store buffer or sample solutions.

Cross References

► Techniques for Transferring Samples to Chips

Soret

Definition

The *Soret coefficient* is the ratio of the thermal diffusion coefficient and the normal diffusion coefficient; it is a measure for the degree of separation of the species in ► thermophoresis.

Soret Effect

► Thermophoresis

Space Charge

Synonyms

Non-equilibrium diffuse charge; Non-equilibrium electrical double layer

Definition

Space charge refers to the extended diffuse charge in an electric double layer, which is passing a super-limiting current.

Cross References

► Electrical Double Layers
► Electroosmosis of the Second Kind
► Electrophoresis of the Second Kind
► Nonlinear Electrokinetic Phenomena
► Super-Limiting Current

Specific Impulse

Definition

The impulse delivered by a propulsion system per unit of propellant consumed; the quantity can be described either per unit mass or unit weight of propellant. It is a measure of the efficiency of the propulsion system.

Spectral Analysis

► Spectral Methods
► Spectrophotometric Analysis

Spectral Approximation

► Spectral Methods

Spectral Methods

SANGMO KANG, YONG KWEON SUH
Mechanical Engineering, Dong-A University, Busan, Republic of Korea
kangsm@dau.ac.kr

Synonyms

Spectral analysis; Spectral approximation

Definition

Spectral methods are a class of techniques used in applied mathematics and scientific computing to numerically solve certain differential equations using the method of weighted residuals. In spectral methods, the solution is approximated as an expansion in terms of spectral basis functions. Here, the basis functions are infinitely differentiable *global* (non-local) functions defined over a whole domain, e.g. trigonometric functions, Chebyshev polynomials, Legendre polynomials and so on, making the spectral methods different from the finite-element and finite-difference methods. Spectral methods have an excellent property of very high spatial accuracy for well-behaved problems and, thus, they are appropriate for the numerical simulation of accurately predicting flows with a broad range of dynamically significant scales of motion.

Overview

Spectral methods are used to numerically solve boundary value, eigen-value and time-dependent problems and these methods involve a completely different approach from finite-element and finite-difference methods. In spectral methods, instead of representing a function by its values at grid points, one would approximate the function by a series expansion in terms of spectral basis functions as follows (in the case of one-dimensional problem):

$$u(x) \approx u_N(x) = \sum_{n=0}^{N} a_n \phi_n(x)\,, \tag{1}$$

where $u(x)$ and $u_N(x)$ denote respectively a function and its approximation, and $\phi_n(x)$ and a_n respectively the nth basis function and its corresponding coefficient. N is the degree of the series expansion. The basis functions are infinitely differentiable non-local functions defined over a whole domain. In addition, they should have a lot of appropriate properties, such as easy computation, rapid convergence and completeness (A basis set is said to be *complete* for a given class of functions if all the functions within the class can be represented to arbitrary high accuracy as a sum of a sufficiently large number of basis functions) [1]. The typical examples are the trigonometric functions and Chebyshev and Legendre polynomials. The trigonometric functions, or Fourier series, are used for the periodic boundary conditions, whereas the Chebyshev and Legendre polynomials are used for the Dirichlet conditions. It means that the coefficient, a_n, influences the function, $u_N(x)$, and its derivative, $\mathrm{d}u_N(x)/\mathrm{d}x$, over a whole domain and, thus, spectral methods are completely *global*. Note that finite-element and finite-difference methods are local because the function value at a grid point has influence only near that point.

When the spectral series (1) is substituted into the differential equation

$$Lu(x) \equiv f(x)\,, \tag{2}$$

where L is the differential operator, the result is the so-called residual function defined as;

$$R(x; a_0, a_1, \ldots, a_N) \equiv Lu_N(x) - f(x)\,. \tag{3}$$

Since the residual function, $R(x; a_n)$, is identically equal to zero for the exact solution, the ultimate goal in spectral methods is to choose the spectral coefficients, a_n $(n = 0, 1, \ldots, N)$, so that the residual function is minimized. The different kinds of spectral methods differ mainly in the minimization strategies.

The basis functions, $\phi_n(x)(n = 0, 1, \ldots, N)$, should be already determined such that each of them satisfies the corresponding boundary condition. Here, the application of the *method of weighted residuals* [2] determines the coefficients, a_n, by imposing the $(N + 1)$ conditions

$$(w_i, R\,[x; a_0, a_1, \ldots, a_N]) = 0\,, \quad i = 0, 1, \ldots, N \tag{4}$$

for some suitable test functions, $w_i(x)$. The inner product for any two functions, $u(x)$ and $v(x)$, is defined as

$$(u, v) \equiv \int_\Omega \rho(x) u(x) v(x)\,\mathrm{d}x \tag{5}$$

for a given non-negative weight function, $\rho(x)$, where Ω denotes the whole domain.

There are two basic types of spectral methods: *pseudospectral* methods and *Galerkin* methods. In pseudospectral methods, or spectral collocation methods, the test function is given as

$$w_i(x) \equiv \delta(x - x_i)\,, \tag{6}$$

where x_i is each collocation point and $\delta(x)$ the Dirac delta-function (1 for $x = 0$ and 0 otherwise). The substitution of Eq. (6) into Eq. (4) results in the algebraic equations

$$R(x_i; a_0, a_1, \ldots, a_N) = Lu_N(x_i) - f(x_i) = 0\,, \quad i = 0, 1, \ldots, N \tag{7}$$

at the collocation points.

In the Galerkin method, on the other hand, the test function is given as

$$w_i(x) \equiv \phi_i(x) \,. \tag{8}$$

This choice of test function is successful because any well-chosen set of basis functions would have all the properties desired by weighting functions, including linear independence and completeness. The main difference between pseudospectral and Galerkin methods is as follows. In pseudospectral methods, some of the calculations are carried out in terms of the spectral coefficients, a_n, and some in terms of the values of $u(x)$ at certain grid points, whereas, in Galerkin methods, all the computations are carried out in terms of the spectral coefficients, a_n.

Micro and nanoflows involve a relatively broad range of dynamically significant scales of motion. Thus, highly accurate numerical methods are required for exactly capturing these dynamics. High spatial accuracy is achieved by spectral methods, which thus may be very effective in simulating micro and nanoflows. However, most micro and nanoflows involve complex wall-bounded geometries, that is the flow geometry is complex or particular regions need to be resolved. Note that spectral methods cannot be readily applied to such cases without any special treatment.

Spectral domain-decomposition methods are suggested as an efficient way of resolving the limitation of conventional spectral methods. The basic idea behind the methods is to partition the whole domain into several subdomains, and then to simultaneously solve the differential equations in each subdomain and appropriate matching conditions on each interface. These methods have very attractive features, such as rapid convergence, geometric flexibility, and suitability to parallel implementation. Thus, they are appropriate when particular regions need to be resolved or when flows in complex geometries are to be simulated.

In general, two classes of spectral domain-decomposition methods have been proposed in the literature: *patching* methods and *variational* methods. The difference is in the way how the interface conditions are imposed. To solve second-order partial differential equations as an example, the interface condition is typically enforced by requiring that the solution and its first normal derivative be continuous on each interface. In patching methods, the continuity conditions on each interface are discretized by enforcing them at selected points, and thus are satisfied exactly by any approximation. In variational methods, on the other hand, the continuity conditions are enforced implicitly or variationally with differential equations at all points, including all the subdomains and interfaces.

Patching methods are based on spectral collocation methods first developed by Orzag [4]. They are useful in exploiting the efficiency of spectral collocation methods. On the other hand, the spectral element methods first developed by Patera [5] are a kind of variational methods. These methods are a high-order weighted residual technique that combines the accuracy and rapid convergence of spectral methods with the generality and geometric flexibility of finite-element methods.

Basic Methodology

Pseudospectral and Galerkin Methods

In order to simply explain the basic principle behind spectral methods, consider one-dimensional linear Helmholtz equation as an example:

$$Lu(x) = -\frac{\mathrm{d}^2u(x)}{\mathrm{d}x^2} + \lambda u(x) = f(x) \quad \text{in } \Omega \,, \tag{9}$$

where λ is a non-negative constant. The same basic principle can be readily extended to more complex differential equations and more-dimensional problems.

The function, $u(x)$, in Eq. (9) can be approximately written as a series expansion in terms of spectral basis functions, $\phi_n(x)$, as in Eq. (1). When the spectral series (1) is substituted into Eq. (9), the resultant residual function can be written as

$$\begin{aligned} R(x; a_0, a_1, \ldots, a_N) &= Lu_N(x) - f(x) \\ &= \left(-\frac{\mathrm{d}^2u_N}{\mathrm{d}x^2} + \lambda u_N\right) - f \,. \end{aligned} \tag{10}$$

Since the residual is zero if $u_N(x)$ is the exact solution of Eq. (9), it follows that the goal of all numerical methods is to choose the undetermined coefficients, a_n, so as to make $R(x; a_n)$ as small as possible. The different kinds of spectral methods differ mainly in the minimization strategies. There are two basic types of spectral methods: pseudospectral methods and Galerkin methods.

In pseudospectral methods, the following $(N+1)$ algebraic equations are derived from Eq. (7):

$$\begin{aligned} &R(x_i; a_0, a_1, \ldots, a_N) = Lu_N(x_i) - f(x_i) \\ &= \left(-\frac{\mathrm{d}^2u_N(x_i)}{\mathrm{d}x^2} + \lambda u_N(x_i)\right) - f(x_i) = 0 \,, \\ &i = 0, 1, \ldots, N \,. \end{aligned} \tag{11}$$

In other words, pseudospectral methods define the 'minimization' of the residuals as 'zero at a set of $(N+1)$ collocation points, x_i'.

In the special case where the differential operator, L, is linear, Eq. (11) converts the differential Eq. (9) into the following linear matrix problem:

$$\bar{L}\bar{a} = \bar{f}\,, \tag{12}$$

where the elements of the matrices are

$$\begin{aligned} \bar{L})_{in} &= L[\phi_n(x_i)] = \left(-\frac{\mathrm{d}^2\phi_n(x_i)}{\mathrm{d}x^2} + \lambda\phi_n(x_i)\right), \\ \bar{a})_n &= a_n\,, \\ \bar{f})_i &= f(x_i)\,. \end{aligned} \tag{13}$$

Thus the inth element of the matrix, $\bar{L})_{in}$, is the approximate value of the differential operator, L, of the nth basis function (where n is the column index) evaluated at the ith collocation point (where i is the row index). If L is a nonlinear operator, on the other hand, then the algebraic Eqs. (11) are nonlinear, too. In such a case, they should be solved by iteration methods such as the Newton–Raphson method.

The alternatives to pseudospectral methods are Galerkin methods. Galerkin methods distribute the residual so that the expansion of the residual function as a series of the basis functions, $\phi_n(x)$, contains no component with respect to the test function, $\phi_i(x)$ $(i = 0, 1, \dots, N)$. The combination of Eqs. (4) and (8) gives the following $(N+1)$ algebraic equations:

$$\begin{aligned} &(\phi_i, R\,[x; a_0, a_1, \dots, a_N]) \\ &\quad = \int_\Omega \rho(x)\phi_i(x)\left(-\frac{\mathrm{d}^2u_N(x)}{\mathrm{d}x^2} + \lambda u_N(x) - f(x)\right)\mathrm{d}x \\ &\quad = 0\,, \\ &\quad i = 0, 1, \dots, N\,. \end{aligned} \tag{14}$$

In the special case where L is a linear operator, Galerkin methods give the linear matrix problem

$$\tilde{L}\tilde{a} = \tilde{f}\,, \tag{15}$$

where the elements of the matrices are

$$\begin{aligned} \tilde{L})_{in} &= (\phi_i, L\phi_n) \\ &= \int_\Omega \rho(x)\phi_i(x)\left(-\frac{\mathrm{d}^2\phi_n(x)}{\mathrm{d}x^2} + \lambda\phi_n(x)\right)\mathrm{d}x\,, \\ \tilde{a})_n &= a_n\,, \\ \tilde{f})_i &= (\phi_i, f) = \int_\Omega \rho(x)\phi_i(x)f(x)\,\mathrm{d}x\,. \end{aligned} \tag{16}$$

In some cases, the orthogonality of the spectral basis-function set may be important because the coefficients of the expansion of an arbitrary function, $u(x)$, in terms of an orthogonal basis function set are given as

$$u(x) = \sum_{n=0}^{\infty} u_n(x)\phi_n(x)\,, \quad u_n = (u, \phi_n)/(\phi_n, \phi_n)\,. \tag{17}$$

If L is a nonlinear operator, then the algebraic Eqs. (14) are nonlinear, too.

Pseudospectral and Galerkin methods are very different in appearance. However, pseudospectral methods are efficient only if the collocation points are distributed so that the residual is not merely zero at the collocation points themselves but also very small everywhere in between. It turns out that, for all the canonical basis sets, the optimum choice of collocation points is to employ the Gaussian quadrature points which are used to evaluate the integral inner product associated with the basis set [1, 3]. From this, one could show that Galerkin and pseudospectral methods are equivalent if the integrals are evaluated by $(N+1)$-point Gaussian quadrature.

To summarize, pseudospectral algorithms are easier to program. On the other hand, Galerkin methods are more accurate for small N and are easier to understand and manipulate for theoretical purposes such as perturbation theory. Perhaps Galerkin methods are more robust for difficult problems. For numerical purposes, however, there is not much to choose between them [1].

Choice of Basis Function Set (Fourier Series and Chebyshev Polynomials)

When the solution has spatially periodic boundary conditions, one uses the following Fourier series as a basis function set:

$$u(x) = a_0 + \sum_{n=1}^{\infty} a_n \cos(nx) + \sum_{n=1}^{\infty} b_n \sin(nx)\,,$$
$$x \in [-\pi, \pi]\,,$$
$$a_0 = \frac{1}{2\pi} \int_{-\pi}^{\pi} u(x)\,\mathrm{d}x\,, \tag{18}$$
$$a_n = \frac{1}{\pi} \int_{-\pi}^{\pi} u(x) \cos(nx)\,\mathrm{d}x\,,$$
$$b_n = \frac{1}{\pi} \int_{-\pi}^{\pi} u(x) \sin(nx)\,\mathrm{d}x\,.$$

Since each Fourier term is individually periodic with a period 2π, the solution, $u(x)$, automatically satisfies the periodic conditions, independent of the spectral coefficients, a_n and b_n.

On the other hand, if the domain is finite, but the function is not periodic, for example $u(\pm 1) = 0$, the Chebyshev polynomials are best. The Chebyshev polynomials of degree n are defined as

$$T_n(x) = \cos[n \arccos(x)]\,. \tag{19}$$

It can also be calculated directly via the following three-term recurrence relation:

$$\begin{aligned} T_0(x) &\equiv 1\,,\\ T_1(x) &\equiv x\,,\\ T_{n+1}(x) &= 2xT_n(x) - T_{n-1}(x), \quad n \geq 1\,. \end{aligned} \tag{20}$$

To impose the Dirichlet boundary conditions, $u(\pm 1) = 0$, one defines the spectral basis functions to be linear combinations of the Chebyshev polynomials, which vanish at the boundaries, such as

$$\begin{aligned} \phi_{2n}(x) &= T_{2n}(x) - 1\,,\\ \phi_{2n+1}(x) &= T_{2n+1}(x) - x\,, \quad n = 1, 2, \ldots \end{aligned} \tag{21}$$

The fact that $\phi_n(\pm 1) = 0$ for each n follows from the trigonometric definition of the Chebyshev polynomials, which implies $T_n(\pm 1) = (\pm 1)^n$.

There are many exceptions: the basis set can be generally determined by the flow geometry and boundary conditions. Therefore, the interested readers may refer to the literature for more details.

Spectral Domain-Decomposition Methods

Most of spectral methods have been developed paying attention to simple geometries and, thus, one would suffer from many difficulties in applying them to more complex geometries. Recently, there have been a number of developments on the use of spectral schemes in more complex geometries, for example the advent of spectral domain-decomposition methods. The basic idea behind these methods is to partition the whole domain into several subdomains, and then to simultaneously solve differential equations in each subdomain and appropriate matching conditions on each interface. In general, two classes of spectral domain-decomposition methods have been proposed in the literature: patching methods and variational methods.

In order to simply explain the basic principle of patching and variational methods, consider one-dimensional linear Helmholtz equation subject to zero Dirichlet boundary condition as follows:

$$Lu(x) = -\frac{\mathrm{d}^2 u(x)}{\mathrm{d}x^2} + \lambda u(x) = f(x) \qquad \text{in } \Omega \tag{22}$$
$$u(x) = 0 \qquad \text{on } \partial\Omega \tag{23}$$

where $\partial\Omega$ is the boundary of the whole domain.

Patching Methods

Patching methods [1, 3], first developed by Orzag [4], are useful in exploiting the efficiency of spectral collocation methods. Suppose that the whole domain, Ω, is decomposed into M subdomains, Ω_s $(s = 1, \ldots, M)$. N_s denotes the degree of polynomials used to approximate $u(x)$ in the sth subdomain, and $N \equiv N_1 + N_2 + \ldots + N_M$ is the total number of degrees of plynomials in the whole domain. The numerical solution is denoted by $u^N(x)$, while $u_s(x)$ indicates the *restriction* of the numerical solution to the sth subdomain.

In patching methods, the Helmholtz equation and the corresponding boundary condition are satisfied in each subdomain as follows:

$$\begin{aligned} Lu_s(x_i^s) - f(x_i^s) = \left(-\frac{\mathrm{d}^2 u_s(x_i^s)}{\mathrm{d}x^2} + \lambda u_s(x_i^s)\right)&\\ - f(x_i^s) = 0 \quad \text{in } \Omega_s\,,&\\ i = 0, 1, \ldots, N_s\,, \quad s = 1, 2, \ldots, M& \end{aligned} \tag{24}$$
$$u_s = 0 \quad \text{on } \partial\Omega \cap \Omega_s\,. \tag{25}$$

On the other hand, the solution and its first normal derivative should be continuous across the interface:

$$u_s = u_{s+1} \qquad \text{on } \Gamma_s\,, \tag{26}$$

$$\frac{\mathrm{d}u_s}{\mathrm{d}x} = \frac{\mathrm{d}u_{s+1}}{\mathrm{d}x} \qquad \text{on } \Gamma_s\,, \tag{27}$$

where Γ_s $[s = 1, 2, \ldots, (M-1)]$ denotes the interface between two adjacent subdomains, $\Gamma_s = \Omega_s \cap \Omega_{s+1}$. If the order of a certain differential equation is d (≥ 2), the solution and all the normal derivatives less than d should be continuous across the interface.

To summarize, in patching methods, the algebraic equations (24) are solved, together with the boundary condition (25), in each subdomain and simultaneously the interface matching conditions (26) and (27) are satisfied on each interface. The same principle can be readily extended to more-dimensional problems.

Variational Methods

Variational methods [3] are a class of high-order weighted residual techniques that combines the high spatial accuracy and rapid convergence of spectral methods with the generality and geometric flexibility of finite-element methods. Consider a variational method on Ω for one-dimensional Helmholtz Eq. (22). A variational formulation of this problem is that $u(x)$ should be the solution to

$$\int_\Omega \left(-\frac{\mathrm{d}^2 u(x)}{\mathrm{d}x^2} + \lambda u(x) \right) \phi_i(x)\,\mathrm{d}x = \int_\Omega f(x)\phi_i(x)\,\mathrm{d}x\,. \tag{28}$$

Equation (28) can be converted into another form, using integration-by-parts and zero natural boundary condition:

$$\int_\Omega \left(\frac{\mathrm{d}u(x)}{\mathrm{d}x}\frac{\mathrm{d}\phi_i(x)}{\mathrm{d}x} + \lambda u(x)\phi_i(x) \right) \mathrm{d}x = \int_\Omega f(x)\phi_i(x)\,\mathrm{d}x\,, \tag{29}$$

where $\phi_i(x)$ is the trial (or test) function which vanishes on $\partial\Omega$ and which is integrable over Ω together with its first derivative. In addition, it is a continuous function of piecewise polynomials defined on the decomposition of the whole domain, Ω. The solution to the Eq. (29) is approximated by a function $u^N(x)$ satisfying

$$\sum_{s=1}^{M} \int_{\Omega_s} \left(\frac{\mathrm{d}u_s^N}{\mathrm{d}x}\frac{\mathrm{d}\phi_i}{\mathrm{d}x} + \lambda u_s^N \phi_i \right) \mathrm{d}x = \sum_{s=1}^{M} \langle f, \phi_i \rangle_s\,. \tag{30}$$

For each s, $\langle f, \phi_i \rangle_s$ is a convenient approximation of the integral, $\int_{\Omega_s} f\phi_i\,\mathrm{d}x$. Equation (30) is a variational formulation with trial and test functions which are continuous across the interface (element boundary).

Key Research Findings

Since micro and nanoflows involve very low Reynolds numbers, the convection effects may be neglected in simple geometries. However, in complex geometries with abrupt turns the effects are substantial [6] and, thus, more accurate and efficient numerical schemes such as spectral methods may be necessary in handling such flows. Up to now, there have been a vast number of numerical studies on micro and nanofluidics. Therefore, few conspicuous numerical studies using spectral methods have been performed, except Karniadakis' research group.

Karniadakis and Beskok [6] developed a code μ*Flow* with implementation of spectral element methods. They employed both the Navier–Stokes (incompressible and compressible) and energy equations in order to compute the relative effects of compressibility and rarefaction in gas micro flow simulations. In addition, they also considered the velocity slip, temperature jump, and thermal creeping boundary conditions in the code μ*Flow*. The spatial discretization of μ*Flow* was based on spectral element methods, which are similar to the *hp* version of finite-element methods. A typical mesh for simulation of flow in a rough micro channel with different types of roughness is shown in Fig. 1. The two-dimensional domain is broken up into elements, similar to finite elements, but each element employs high-order interpolants based on Legendre polynomials. The N points that determine the interpolant correspond to the maxima locations of the Legendre polynomials and the end-points. For smooth solutions, the spatial discretization error decays exponentially to zero (spectral or p-convergence). This means that if we dou-



Spectral Methods, Figure 1 A typical mesh in a rough micro channel for the spectral element method [6] ble N, the error would decay by two orders of magnitude. This is a much faster decay than in standard second-order methods which yield an error reduction by a factor of only four. In MEMS simulations, spectral element methods can be used efficiently by exploiting the dual path of convergence allowed by the method. For example, in regions of geometric complexity, a finite element-like discretization (low N and small size elements) can be employed, whereas in regions of homogeneous geometry with steep gradients, a spectral-like discretization (high N and large size elements) can be employed. In particular, the boundary conditions for MEMS flows, either for gases (Knudsen effects) or liquids (electrokinetic effects), can be resolved very accurately.

Future Directions for Research

Spectral methods have been a promising tool for simulating micro and nanoflows as well as macro flows because they have excellent properties of high spatial accuracy and rapid convergence. Therefore, they can capture a broad range of dynamically significant scales of motion very effectively.

Up to now, a vast number of studies on micro and nanofluidics have been performed based on the theoretical, numerical and experimental approaches. For the numerical analysis, however, finite-volume or finite-difference schemes have been mostly used. In the future, spectral methods will contribute more to the studies on micro and nanoflucids that require numerical methods with high spatial accuracy, for example electrokinetic and capillary effects.

Cross References

- ► Finite Volume and Finite Difference Methods for Modeling and Simulation

References

1. Boyd JP (2001) Chebyshev and Fourier Spectral Methods. Dover, New York
2. Finlayson BA (1973) The Method of Weighted Residuals and Variational Principles. Academic, New York
3. Canuto C, Hussaini MY, Quarteroni A, Zang TA (1988) Spectral Methods in Fluid Dynamics. Springer, Berlin
4. Orszag SA (1980) Spectral methods for problems in complex geometries. J Comput Phys 37:70–92
5. Patera A (1984) The spectral element method for fluid dynamics: laminar flow in a channel expansion. J Comput Phys 54:468–488
6. Karniadakis GE, Beskok A (2002) Micro flows: fundamentals in simulation. Springer, New York

Spectral Response

- ► Spectral Responsivity

Spectral Responsivity

Synonyms

Spectral response

Definition

The spectral responsivity refers to the electrical signal generated by a photodetector when irradiated with a known radiant flux of a specific wavelength.

Cross References

- ► Lab-on-a-Chip Device for Chemical Analysis

Spectrophotometer

- ► Photometer

Spectrophotometric Analysis

Synonyms

Spectrophotometry; Spectrophotometric measurement; Spectral analysis

Definition

The spectrophotometric analysis is the study of the interaction of electromagnetic radiation with chemical compounds. This analytical technique can be used to determine the structure of a new compound, identify a specific compound, determine the activity of a specific enzyme and determine the concentration and/or amount of a particular compound in body fluids samples. It is the one of the most commonly used analytical techniques for body fluids analysis in clinical diagnosis.

Spectrophotometric analysis by optical absorption is based on the absorption of electromagnetic radiation that is proportional to the amount of the element, ion, compound or molecule being analyzed in the sample. Absorbance detection is covered under a separate title.

Cross References

- ► Lab-on-a-Chip Devices for Chemical Analysis
- ► Lab-on-Chip Devices for Protein Analysis

Spectrophotometric Measurement

► Spectrophotometric Analysis

Spectrophotometry

► Spectrophotometric Analysis

Spectroscopy

► Photometer

Speed of Sound

Definition

The speed at which an infinitesimal pressure perturbation propagates in a quiescent medium.

Cross References

► Supersonic Micro-Nozzles

Spinning-Disk Confocal Microscopy

► Confocal Microscopy, Detection

Spinodal Decomposition

► Demixing

Spiral Microchannel Flow

► Curved Microchannel Flow

Spontaneous Electrowetting

► Electrowetting, Applications

Spontaneous Polarization

Definition

A polarization that exists within a material in the absence of the application of an external field. Requires non-enantiomorphic polar symmetry. Usually used in the context of electric fields and electrical polarization. Materials that exhibit spontaneous polarization and are piezoelectric are able to retain a ionic polarization and therefore said to be ferroelectric.

Cross References

► Non-Centrosymmetric
► Ferroelectric
► Piezoelectric

SPR

► Surface Plasmon Resonance Sensors

SPRT

► Resistance Temperature Detectors

Sputter Etching

Synonyms

Physical etching

Definition

A purely physical process caused by surface bombardment with high-energy ions, anisotropic etching; also with poor selectivity, high surface damage, and low etching rates.

Cross References

► Anisotropic Etching
► Isotropic Etching
► Reactive Ion Etching (RIE)
► Plasma Etching
► Silicon Micromachining

Sputtering for Film Deposition

Alexander Iles, Nicole Pamme
Department of Chemistry, The University of Hull,
Hull, UK
n.pamme@hull.ac.uk

Synonyms

Physical vapor deposition; Cathode sputtering; Impact evaporation

Definition

The verb *to sputter* originates from *sputare* (latin, to emit saliva with noise). Sputtering is the ejection of atoms from a surface following bombardment by suitably energetic atomic particles. Typically, these bombarding particles are ions generated by an electrical discharge in a low pressure gas. This process can be utilized as a thin film deposition technique by allowing atoms sputtered from a target to impinge on a substrate. The process is widely used to deposit films less than one micrometer thick for microelectronic component fabrication, the formation of optical coatings and the production of decorative parts.

Overview

The process of sputtering was first reported by W. R. Grove in 1852. He observed the formation of metallic deposits on the inner wall of a glass discharge tube during an investigation into the electrical conductivity of gases using direct current (DC) glow discharges. This observation has led to the development of an extremely versatile thin film deposition technique that is utilized in numerous different fields. A vast range of different materials can be deposited using sputtering, including: pure metals, alloys, semiconductors and insulators. The deposition process can also be used for the formation of films with novel properties in terms of stoichiometry and crystalline orientation. In addition to deposition, sputtering can also be used for etching, surface cleaning and for surface layer analysis.

Sputtering has been used for many years to produce the chromium coated ▶photomasks that are often used in the production of glass microdevices. Recently, sputtering has become a common technique for the deposition of thin films in microfluidic and nanofluidic devices. For most applications, it is used as a convenient means for the production of patterned electrodes. However, as will be shown below, sputtering can be used to achieve far more than this. In the not so distant future it is likely that the enormous versatility of this technique will be exploited for the fabrication of miniaturized fluidic devices with greatly enhanced functionality that would be difficult or impossible to produce by other means.

The sputtering process is governed by a range of different parameters. These parameters can be manipulated to alter the properties of the deposited film. In DC sputtering systems, the maximum energy (E) of the atoms ejected from the target is determined by the applied voltage. Accelerating a singly charged ion through a potential difference of 1 V imparts a kinetic energy of 1 eV to the ion. For a given voltage atoms are sputtered from the target with a broad distribution of energies. The sputtered atoms impinge on the substrate with maximal energies that are typically 100 times greater than those achieved during film deposition by evaporation. The applied voltage also governs a parameter called the ▶sputter yield (S), which is the number of target atoms removed divided by the number of incident ions. For applied voltages below a certain threshold value, the ions have insufficient energy to overcome the surface binding energy (U_0) of the target material and so atoms are not ejected. This threshold level usually occurs between 0 and 100 eV. For ion energies between 100 eV and 1000 eV, atoms are ejected from the target and the *sputter yield* increases with increasing applied voltage. For ion energies within this range, the *sputter yield* can be estimated by assuming energy transfer occurs by binary collisions:

$$S = \frac{3\alpha}{4\pi^2} \cdot \frac{4m_\mathrm{i} \cdot m_\mathrm{t}}{(m_\mathrm{i} + m_\mathrm{t})^2} \cdot \frac{E}{U_0} \tag{1}$$

where m_i and m_t are the masses of the incident ion and the target atom, respectively; α is a function of the ratio $m_\mathrm{t}/m_\mathrm{i}$. This increases from 0.17 for $m_\mathrm{t}/m_\mathrm{i} = 0.1$ to 0.28 for $m_\mathrm{t}/m_\mathrm{i} = 1$ to 1.4 for $m_\mathrm{t}/m_\mathrm{i} = 10$.

For ion energies greater than 1000 eV, the probability of ions being implanted into the surface of the target becomes significant. The *sputter yield* no longer increases linearly with increasing ion energy. Eventually, the *sputter yield* becomes almost constant and at very high energies it begins to fall as ▶ion implantation becomes the dominant process. As a consequence of this, in DC systems, applied voltages between 100 V and 1000 V are most widely used for the sputter deposition of thin films.

The rate of sputtering is determined primarily by the sputter current density. For most systems, this is generally between 0.1 and 10 mA/cm^2. Increasing the current density increases the rate of deposition. However, a faster rate of arrival of material on the surface of the substrate means that there is less time for the occurrence of processes such as surface diffusion and agglomeration on existing growth sites or nucleation with other growth sites.

The rate of sputtering and the properties of the deposited film are also significantly influenced by the sputter gas type and pressure. In most instances, it is not desirable for the sputter gas to react with the target and so noble gases tend to be used. Xenon and Krypton have larger atomic masses than Argon and generally give higher *sputter yields*. However, Argon is most often used as it is cheaper and more readily available.

The gas pressure dictates the average distance the sputtered atoms travel before they interact with gas atoms. This is called the mean free path (λ) and it is inversely proportional to the gas pressure. A short mean free path means that the sputtered atoms will be subjected to many collisions with gas atoms before being deposited on the substrate. This can affect the porosity of the deposited film and also its crystallinity and surface morphology. Hence, it is often desirable to sputter at low pressure, so that λ is as large as possible. For simple DC gas discharge systems (Fig. 1), relatively high pressures are used, typically 30 to 120 mTorr. This is because it is difficult to maintain the gas discharge at lower pressures. DC ▶ magnetron systems (Fig. 2) can be operated at lower pressures (10^{-5} to 10^{-3} Torr) since the magnetic fields around the target increase the number of collisions between electrons and neutral sputter gas atoms. Sometimes, a reactive gas such as oxygen or nitrogen is added to the sputter gas, so that oxide or nitride films can be deposited.

Not surprisingly, different target materials sputter at different rates. Periodicity is observed when *sputter yields* are plotted against target atomic number. This is related to the surface binding energy (U_0) of the target materials. For the transition metals, *sputter yields* increase between Ti and Cu; then decrease sharply. *Sputter yields* increase again between Zr and Ag before decreasing to another minimum at Hf. Yields increase once more, reaching another maximum at Au. Hence, Cu, Ag and Au are the transition metals that sputter most readily. The orientation and crystal structure of the target relative to the incident sputter ions can also affect the *sputter yield* and the angular distribution of sputtered atoms. *Sputter yields* tend to increase with increasing angle of incidence reaching a maximum between 60° and 80° from the target normal. For larger angles of incidence, the *sputter yield* decreases rapidly. At the optimal angle of incidence, the target atoms are sputtered predominantly in the forward direction with the maximum of their distribution occurring between 10 and 30° from the target normal. If the target is made of a monocrystalline material, then the angular dependence and *sputter yield* will vary according to the orientation of the crystallographic planes relative to the angle of incidence. This is because the surface binding energy (U_0) varies slightly in accordance with the ▶ anisotropy of the crystal structure.

Different metals sputter at different rates. However, when an alloy target is sputtered, the deposited film develops the same composition as the target material, as long as the target temperature is below that required for thermal diffusion. This is because the faster ejection of one element leads to the enrichment of the target's surface with elements that have lower sputter rates. Hence, differences in sputter rates are counteracted and the deposited film obtains the same stoichiometry as the target.

DC systems cannot be used to sputter insulating targets. This is because an electrical discharge in such a system would result in the charging up of the target. Therefore, radio frequency (RF) excitation is used to sputter insulating targets. RF excitation reverses the surface polarity of the target typically at a rate of 13 MHz, and this prevents the target from becoming charged.

The distance between the target and the substrate dictates the mean number of collisions that occur once the sputtered atoms leave the target and travel through the sputter gas to the substrate. Varying this distance can influence the porosity, crystallinity and surface morphology of the deposited film.

Film adhesion is strongly dependent on the cleanliness of the substrate, the chemical nature of the substrate relative to the film and the surface morphology of the substrate. Surface contaminants may increase or decrease adhesion, depending on how they influence the adsorption energy of the deposited material. Often it is desirable to have a very clean surface and so sputter cleaning of the substrate is performed prior to film deposition. Certain metals do not adhere well to substrates such as glass. Adhesion can be improved by increasing the kinetic energy of the incident atoms or by increasing the number of nucleation sites on the substrate. Alternatively, an adhesion layer could be applied to the substrate prior to deposition. For example, chromium is frequently used as an adhesion layer for the deposition of gold onto glass.

During sputtering, the substrate is bombarded by a wide range of species. Some of these species are charged. Hence the properties of the deposited film can be influenced by applying a ▶ bias voltage to the substrate. This is typically between ±100 V and it is used to repel or attract electrons or ions. Substrate biasing can exert a great influence on the physical and electrical properties of the deposited film, including: dielectric constant, porosity, surface morphology, hardness and etch resistance. The polarity and magnitude of the optimal *bias voltage* will depend on the target and substrate materials and the desired properties of the deposited film.

As with most vacuum deposition techniques, film growth on the substrate occurs according to the sequence: atom arrival and physical adsorption, migration on the surface



Sputtering for Film Deposition, Figure 1 Schematic of a DC sputtering system



Sputtering for Film Deposition, Figure 2 Schematic of a DC *magnetron*; a magnetic field is generated by an assembly of magnets beneath the target. This lead to the confinement of electrons in the immediate vicinity of the target

Sputtering for Film Deposition, Table 1 Advantages and Disadvantages for film deposition using sputtering.

Advantages of Sputtering	Disadvantages of Sputtering
– no melting of target material required – deposited film has same stoichiometry as target material – sputtering does not require evaporation, can sputter materials with high evaporation temperature – versatility (type of materials, instrumental parameters) – formation of novel materials possible – long target lifetime – simple DC systems can be built easily from primitive materials	– vacuum required – many variables to optimize, complexity to produce high quality films – dedicated instruments are expensive and require cleanroom facilities – contamination (increased porosity, pinholes, gas incorporation into film) – often slower than other methods

or re-evaporation, formation of atom pairs, nucleation of islands, island growth, coalescence and finally continuous film formation. Clearly, the temperature and crystallinity of the substrate will have a significant effect on the growth behavior of the film. Higher substrate temperatures impart higher mobilities to the atoms on the surface. This leads to larger grain sizes and smoother films. Hence, in many sputtering systems, the substrate is placed on a heated stage. However, the sputtering process itself can lead to significant substrate heating. Excessive heating is undesirable and so substrate cooling may be necessary. The use of polycrystalline substrates will generally lead to the formation of a polycrystalline film. However, if a monocrystalline substrate is used at a suitable temperature, then it is possible to form an ►epitaxial film. Substrates may also be chosen with specific crystallographic orientations so that deposited films acquire particular orientations.

The advantages and disadvantages of sputtering for film deposition are summarized in Table 1.

Basic Methodology

The simplest of sputtering systems is the DC gas discharge diode as shown in Fig. 1. This apparatus consists of a vacuum chamber containing two planar electrodes. One electrode is the cathode, to which the target is connected. This is usually water cooled to prevent it from over-heating. The substrate to be sputtered is placed onto the other electrode, which forms the anode. This may also be water cooled if necessary.

Prior to sputtering, the chamber is evacuated to remove as much oxygen and moisture as is possible. The level of vacuum that is achieved will depend on the effectiveness of the pumping system and the desired quality of the



Sputtering for Film Deposition, Figure 3 The principle of a radio frequency (RF) sputtering system

sputtered film. For high quality film production, the pre-sputtering vacuum should be in the region of 10^{-7} Torr. Once this has been achieved, sputter gas (typically Argon) is admitted to the chamber to raise the pressure to between 30 and 120 mTorr. A high voltage is applied to the electrodes and an electrical gas discharge is initiated. Generally, a constant current power supply is used so that the sputter current can be adequately controlled. The spacing between the target and the substrate is usually set at about 10 cm and the sputter current is adjusted to deposit a film at a suitable rate. Deposition rates are usually between 10 and 200 nm per minute, although this will vary significantly depending on the target material.

The main advantage of DC diode sputtering systems is that they can be extremely simple and can be constructed at low cost using readily available components [1] However, the quality of the films deposited with such systems is relatively poor. This is mainly due to the high operating pressure that must be used to maintain the electrical discharge. A widely used technique to lower the sputter gas pressure is to utilize magnetic fields to confine the electrical discharge to the region around the target (Fig. 2). Sputtering systems that utilize assemblies of magnets around the target are referred to as DC *magnetrons*. With these systems, the sputter gas pressure can be as low as 10^{-5} Torr and very high quality films can be produced at deposition rates that match those obtained by ►evaporation deposition techniques.

Unfortunately it is difficult to use DC systems and DC *magnetron* systems to sputter magnetic materials or insulators. For such targets, it is more common to use radiofrequency (RF) excitation to ionize the gas in the sputtering chamber (Fig. 3). A circuit is employed to match the ►impedance of the power supply to the *impedance* of the sputtering chamber. A blocking capacitor is placed in series with the target so that it is negatively biased during excitation. The sputter gas pressure is typically 1 mTorr. RF sputtering systems can also be fitted with magnet assemblies; such systems are referred to as RF ►magnetrons. A major disadvantage of RF sputtering is that substrate heating is more problematic than with DC *magnetron* systems.

Generally, sputtering systems are fitted with a shutter so that the target can be sputter cleaned before deposition. Other refinements include facilities for substrate biasing and for substrate sputter cleaning. Some sputtering systems are fitted with multiple targets so that different materials can be sputtered simultaneously or sequentially without breaking the vacuum.

For micro- and nanofluidic devices, sputtering is usually performed after channel fabrication. Areas that do not require sputter coating are masked off using a lift-off layer. This could be a specially fabricated photoresist layer, or it could just be the chromium mask left over from the channel etching step. The structured substrate is placed into the sputtering chamber where it is sputtered with the desired material. Then it is removed and the lift-off layer dissolved, leaving sputtered material in the appropriate areas. Subsequently the structure is bonded to a sealing layer so that the channel structure is enclosed.

Key Research Findings

Sputtering is a standard process in materials science and it has required fairly minor adaptation for its use in fluidic device fabrication. Hence, few papers specifically deal with sputtering for microfluidics, most authors mention sputtering as a technique employed in a rather brief manner. A non-exhaustive overview of different sputtering applications is given in Table 2. Many more metals, alloys, semiconductors and insulators can be sputtered than are listed in this table; however, they are beyond the scope of this article.

Sputtering is an excellent method for producing photolithographic mask blanks and for fabricating integrated electrodes, heating elements, sensors and catalysts. Sputtering can also be used to deposit sacrificial layers for nanochannel fabrication or for channel surface treatment

Sputtering for Film Deposition, Table 2 Selected examples of sputtering as used for the fabrication of mircrofluidic and nanofluidic devices. (n.s. = not specified)

Metal	Substrate	Adhesion Layer	Layer thickness	Application	Reference
Pt	silicon	Ti	20 nm Ti, 20 nm Pt	catalysis	[2]
	Pyrex glass	Ti	20 nm Ti, 200 nm Pt	microelectrodes, *impedance* sensor	[3]
	PDMS	Ti	30 nm Ti, 320 nm Pt	microelectrodes	[4]
Au	glass	Ti	50 nm Ti and Au	thiol binding, SPR sensor	[5]
	borofloat glass	Cr, Ti	100 nm Au	temperature sensor	[6]
	PMMA	none	40 nm Au	current collector	[7]
Al	Pyrex	none	300 nm	microheater	[8]
	Pyrex	none	200 nm	heater and electrodes	[9]
	Polymer	none	100 nm	masking layer	[10]
Cr	fused silica	none	1 μm	masking layer	[11]
Ta	glass	n.s.	n.s.	to enable *anodic bonding*	[12]
Pt, Pd, Ru	glass	Cr	n.s.	catalysis	[1]
$Tb_{40}Fe_{60}$, $Fe_{50}Co_{50}$	Silicon and Molybdenum	none	(7 nm, 9 nm) × 100	GMR sensors	[13]
SLBTLO on Pt	glass	Cr	30 nm Cr, 120 nm Pt, 100 nm sensing layer	pH sensing electrodes	[14]
ITO and Ag	Pyrex glass	none	100 nm	microheater	[15]
TiNi	Silicon	none	3 μm	micropump, shape memory effect	[16]
C (graphite)	Silicon	none	1 – 7 μm	*diamond like carbon (DLC)* films as microchannel material	[17]

and modification. In addition to this, when microstructures are subjected to scanning electron microscopy (SEM) analysis, sputtering is often used to deposit a conducting layer prior to examination to prevent the structure from charging up when it is exposed to the electron beam.

Chromium is the most widely sputtered material for ► photomask fabrication. It sputters easily and it adheres well to glass. This high level of adhesion can be attributed to its ability to form a metal suboxide interface layer on glass. The exposed surface of the chromium is often oxidized to reduce its reflectivity. Aluminium is also sometimes used as a mask material, although it is more difficult to sputter and is has a higher reflectivity than oxidized Cr. This can be problematic for *photomask* applications.

On-chip electrodes have been fabricated from a number of metals including Al, Pt, Au, Indium Tin oxide (ITO)-Ag and Cu. Sometimes these electrodes have been used as low thermal mass integrated heating elements. The great versatility of sputtering is ideal for the creation of integrated on-chip sensors. These sensors range from simple thermocouples to pH sensors and even to multilayer oxide materials for giant magneto-resistance (GMR) sensors.

Sputtering has been used to incorporate a number of catalytic metals into microreactor devices. Examples include: Pt, Zr, Mo, Pd, Ru, Rh or alloys such as Pt-Ru. It is a convenient fabrication technique, although some researchers argue that the active surface area of the deposited catalyst is unsatisfactory. For many metals this problem can be overcome by sputtering using an oxygen-rich sputter gas rather than Ar alone. This produces a porous oxide deposit with a high surface area that can be reduced back to the metallic form after bonding. Alternatively, the catalytic metal can be co-sputtered with aluminium. The aluminium acts as an adhesion promoter and also forms an intermetallic oxide with the metal catalyst when the device is bonded. This method creates a robust and highly active catalyst.

Channel surface passification or modification can also be performed using sputtering. Examples include the deposition of SiO_2, SiC or even ► diamond like carbon (DLC). In addition to this, sputter deposited Ta has been used to promote ► anodic bonding for device fabrication.

Many sputtered metals do not adhere particularly well to typical device substrate materials such as silicon, glass and polymers. For example, noble metals such as Au can only rely on van der Waal's forces for adhesion and these forces are relatively weak. Metals such as Cr, Al and Ti readily form a suboxide interface layer on glass and so they are often used as adhesion layers.

There is extensive knowledge of sputtering on Si and glass substrates that is available from the microelectronics and the electro-optics industries. Far less is known about sputtering onto more delicate substrates such as the polymers used for fluidic chip fabrication. Polymers are much more sensitive than glass and silicon to high temperatures and to being bombarded by charged particles and atoms. Conditions must be carefully optimized and the polymer substrate may even have to be protected by a layer of aluminium deposited by evaporation prior to sputtering. Great care must be taken when sputtering onto flexible polymers such as polydimethylsiloxane (PDMS), since bending may lead to cracking of the deposited film. This can be avoided by placing the polymer substrate onto a glass wafer or another rigid material. The adhesion of certain films to PDMS can be problematic. It has been found that ► plasma oxidation is sometimes helpful in improving film adhesion.

Sputtering is usually undertaken before the fluidic device is bonded and it is necessary to ensure that the deposited film does not interfere with the ► chip bonding process. This can be done by using a lift-off layer in the regions that must be clear of sputtered material. *Chip bonding* can have detrimental effects on the deposited film and this must be taken into account, especially where the device must be heated to a high temperature. After bonding, it is generally the case that catalysts deposited by sputtering must be activated before they can be used. This is often achieved by heating under a reducing atmosphere.

Future Directions for Research

Relatively few researchers in the field of micro- and nanofluidics have investigated the application of sputtering to their work. Hence, the potential of sputtering in device fabrication has been far from fully explored. In the future it is highly likely that sputtering techniques will play an important role in blurring the distinctions between electronic and fluidic devices. This will be driven by the desire to produce ever more sophisticated integrated devices with pumps, valves, electrodes, sensors, amplifiers and processors all placed on a single chip. The immense versatility of sputtering will lead to its use in the fabrication of devices with novel, nanostructured, multi-component materials. An infinite variety of composite nanomaterials can be deposited using sputtering. These materials can be engineered by: sputter etching of surfaces, sputtering using reactive sputter gases, sputtering with multi-component targets (in combination or alternately to produce layers), by using angular dependence sputtering and by using oriented crystal substrates. Such materials will have extremely interesting catalytic and magneto-electro-optical properties and they will be utilized in many different areas of fluidics research. As can be seen from this brief introductory article, the combination of sputtering with micro- and nanofluidics is at a relatively primitive stage of development. Far more remains to be discovered.

Cross References

- ► Anisotropy
- ► Anodic Bonding
- ► Bias Voltage
- ► Chip Bonding
- ► Diamond Like Carbon (DLC)
- ► Epitaxial
- ► Evaporation Deposition
- ► Impedance
- ► Ion Implantation
- ► Magnetron
- ► Photomask
- ► Plasma Oxidation
- ► Sputter Yield
- ► Torr

References

1. Iles A, Wootton RCR, Habgood M, et al (2005) Proceedings of microTAS Conference. In: K. Jensen (ed) Kluwer Academic Publishers
2. Cui TH, Fang J, Zheng AP, et al. (2000) Sensors and Actuators B-Chemical 71:228–231
3. Hong JG, Yoon DS, Kim SK, et al (2005) Lab on a Chip 5:270–279
4. Al Mamun NH, Dutta P (2006) J Microlithograp Microfab Microsys 5
5. Kurita R, Yokota Y, Sato Y, et al (2006) Anal Chem 78:5525–5531
6. Easley CJ, Legendre LA, Roper MG, et al (2005) Anal Chem 77:1038–1045
7. Chan SH, Nguyen NT, Xia ZT, et al (2005) J Micromech Microeng 15:231–236
8. Östman P, Marttila SJ, Kotiaho T, et al (2004) Anal Chem 76:6659–6664
9. Shin WC, Besser RS (2006) J Micromech Microeng 16:731–741
10. Holland A, Cher C, Rosengarten G, et al (2006) Smart Mat Struct 15:S104–S111
11. Steingoetter I, Fouckhardt H (2005) J Micromech Microeng 15:2130–2135
12. Kawamura Y, Ogura N, Yahata T, et al (2005) J Chem Eng Japan 38:854–858
13. Ludwig A, Quandt E (2000) J App Phys 87:4691–4695
14. Lin CF, Lee GB, Wang CH, et al (2006) Biosens Bioelectr 21:1468–1475
15. Yen TH, Shoji M, Takemura F, et al (2006) Intern J Heat Mass Transfer 49:3884–3894

16. Benard WL, Kahn H, Heuer AH, et al (1998) J Microelectromech Syst 7:245–251
17. Mousinho AP, Mansano RD, Massi M, et al (2003) Diamond Related Materials 12:1041–1044
18. Wasa K, Hayakawa S (1992) Handbook of Sputter Deposition Technology, Principles, Technology and Applications. Noyes Publications, New Jersey
19. Stuart RV (1983) Vacuum Technology, Thin Films and Sputtering – An Introduction. Academic Press, New York

Sputter Yield

Definition

The number of sputtered atoms from a given target per incident ion.

Cross References

► Sputtering for Film Deposition

Stability

Synonyms

Numerical stability

Definition

Stability is a desirable property of dynamic systems in general and numerical algorithms in particular. The precise definition of stability depends on the context, but it is generally related to the accuracy of the algorithm. It is sometimes observed that different ways of doing a single calculation yield different results as they have different levels of numerical stability. A numerical algorithm is called robust if it has good numerical stability.

In the context of ►Numerical Solution of Boltzmann Equationnumerical solution of partial differential equations, stability ensures that round-off and other errors in the calculation are not amplified to cause the calculation to blow up. An algorithm for solving an evolutionary (e. g., a time-dependent) ►partial differential equation is stable if the numerical solution at a fixed time remains bounded as the time step-size goes to zero. An important theorem in mathematics, the so-called Lax equivalence theorem, states that an algorithm converges if it is consistent and stable.

Cross References

► Meshless Methods
► Volume and Finite Difference Method for Modeling and Simulation

Stack Actuator

► Multilayer Piezoelectric Actuator

Stagnation Conditions

Definition

For a compressible flow, this is the thermodynamic state that would exist if a flow were brought to rest isentropically. In practice, this would correspond to the thermodynamic state of a very low-speed flow entering the nozzle inlet from an upstream combustion chamber or a pressurized reservoir. For this reason, stagnation conditions are also sometimes referred to as ’chamber’ or ’reservoir’ conditions.

Cross References

► Supersonic Micro-Nozzles

Standard Deviation

Definition

The standard deviation describes the statistical spread of a bunch of random values to their arithmetic mean. It can be calculated with the root mean square of the values from their arithmetical mean.

Static Electrowetting

► Electrowetting, Applications

Stationary Phases in Microchannels

Anup K. Singh
Sandia National Laboratories, Livermore, CA, USA
aksingh@sandia.gov

Synonyms

Photopatterned materials; Cast-in-place polymeric media; In situ polymerized materials; Polymer monoliths; Cross-linked gels; Hydrogels

Definition

A stationary phase is a solid material, thin film, or gel that remains motionless relative to the flow of buffer, ions, or current in a microchannel during michrochip chromatography, electrochromatography, or electrophoresis.

Overview

Chromatographic separations frequently rely upon interactions between analytes in a flowing liquid or gas stream (or *mobile phase*), and a solid surface which remains motionless. In traditional forms of chromatography, the motionless solid surface, or *stationary phase*, might be porous particles of a polar material like silica (a *normal phase* chromatographic support), hydrophobically modified or coated silica (a *reversed phase* chromatographic support), or a thin polysiloxane film on the inner lumen of a capillary (for capillary gas chromatography).

These common forms of stationary phase are sometimes employed for miniaturized versions of chromatographic separations on microfluidic devices, although achieving uniform packing of porous particles in a planar chip can be difficult, typically requiring some form of on-chip frit. Furthermore, localizing particles to a single portion of a multifunctional device is challenging, requiring some form of on-chip valving or other strategy to isolate the chromatography column from the rest of the chip.

An alternative strategy which is sometimes employed is to fabricate a polymeric stationary phase *in situ*, often combined with photopatterning to localize the stationary phase in a particular region of the chip. As an example, phase separation polymerization using a variety of acrylate monomers, along with a photointiator, crosslinker, and porogenic solvent, can be used to define porous polymer monoliths within microchannels. In this approach, the monomers are initially soluble in the porogenic solvent, but as polymerization proceeds, the growing chains have decreased solubility, and eventually phase-separate or precipitate. Surface properties and pore size can be tailored by choice of monomer and solvent, with possibilities for hydrophobic, polar, or charged surfaces, and microscale or nanoscale pores. Polymerization can be initiated by flood illumination through a photomask, or using shaped laser light to localize monoliths to certain regions of the chip, with well-defined boundaries. Porous polymer monoliths created in this fashion have been used for on-chip liquid chromatography and electrochromatography of proteins, peptides, and other biomolecules, and are suitable for interfacing with mass spectrometry.

The term *stationary phase* can also be applied to a variety of crosslinked gels or hydrogels that can be fabricated within microchannels to act as sieving media for electrophoresis. Polyacrylamide gel is a typical stationary phase for electrophoretic separations, and has been used for sieving separations of native proteins and immunocomplexes, SDS-denatured proteins, and single- and double-stranded DNA. Sieving electrophoresis, particularly for DNA, is also frequently performed using semi-dilute solutions of non-crosslinked polymers. Crosslinked gels, like porous polymer monoliths, can be photpatterned *in situ* and localized to certain regions of the device with good spatial resolution, which can be an important advantage in complex, integrated microfluidic devices.

Cross References

► Liquid Chromatography
► Electrophoresis
► Photopatterning

References

1. Fintschenko Y, Kirby BJ, Hasselbrink EF, Singh AK, Shepodd TJ (2003) In: Svec F, Tennikova TB, Deyl Z (eds) Monolithic Materials: Preparation, Properties and Applications. Elsevier, Amsterdam, pp. 659-686
2. Ro KW, Nayalk R, Knapp DR (2006) Electrophoresis 27:3547–3558
3. Throckmorton DJ, Shepodd TJ, Singh AK (2002) Anal Chem 74:784–789
4. Herr AE, Hatch AV, Throckmorton DJ, Tran HM, Brennan JS, Giannobile WV, Singh AK (2007) Proceedings of the National Academy of Sciences of the United States of America 104:5268–5273

Statistical Sampling Method

► Monte Carlo Method

Steady Streaming

► Acoustic Streaming

Stem Cell Isolation

► Microfluidics for Stem Cell Therapy

Stem Cell Reprogramming

► Microfluidics for Stem Cell Therapy

Stem Cell Tissue Engineering

► Microfluidics for Stem Cell Therapy

Stereolithography

► Microsterolithography

Stokes Approximation

Definition

A simplifying approximation often made in fluid mechanics where the terms arising due to the inertia of fluid elements is neglected. This is justified if the Reynolds number is small, a situation that arises for example in the slow flow of viscous liquids such as when pouring honey over toast.

Cross References

Cross References

► Electrokinetic Flow and Ion Transport in Nanochannels

Stokes Shift

Definition

For fluorescent molecules that are illuminated by incident light, the shift in wavelength of the fluoresced light relative to the absorption wavelength is referred to as Stokes shift.

Cross References

► Fluorescent Thermometry

Stotz–Wien Effect

Synonyms

Nonlinear electrophoresis; Field-dependent electrophoretic mobility

Definition

The Stotz–Wien effect refers to dependence of the electrophoretic mobility of a charged polarizable particle on the field strength due to induced-charge electro-osmotic flow.

Cross References

► Aperiodic Electrophoresis
► Electrical Double Layers
► Electrokinetic Motion of Heterogeneous Particles
► Electrokinetic Motion of Polarizable Particles
► Electroosmotic Flow (DC)
► AC Electro-Osmotic Flow
► Electrophoresis
► Induced-Charge Electro-Osmosis
► Induced-Charge Electrophoresis
► Nonlinear Electrokinetic Phenomena

Streaming Current

Definition

A forced ionic liquid flow generated by a pressure gradient in a microchannel induces an electrostatic field whereas the current induced by the displacement of the heterogeneous charges in the flow is called the streaming current.

Cross References

► Streaming Current and Electroviscosity

Streaming Current and Electroviscosity

DAVID BRUTIN
IUSTI Laboratory, Poytech'Marseille, Marseille, France
david.brutin@polytech.univ-mrs.fr

Synonym

Electroviscous effects

Definition

A forced ionic liquid flow generated by a pressure gradient in a microchannel induces an electrostatic field, and the current induced by the displacement of the heterogeneous charges in the flow is called the ►streaming current. Due to the electric neutrality of the fluid inside the microchannel, a conduction current, I_C, appears to equilibrate the ►streaming current, I_S. The physical and electrical properties of the fluid such as density, viscosity, electrical conductivity and permeability are influenced by concentrations of cations and anions. A forced ionic liquid flow with a surface potential induces a charge accumulation near the surface. Due to the concentration of charges the fluid viscosity near the surface is modified locally. This phenomenon of a change in apparent viscosity due to the



Streaming Current and Electroviscosity, Figure 1 Hydration and ionization of a fused silica surface by H_2O

presence of charges in an electrical field with a Lorentz force is also called ►electroviscosity.

Chemical and Physical Principles

Calculation of Streaming Current

►Streaming current and ►electroviscosity can only appear with an ionic fluid and a microchannel with a nonconductive inner surface such as fused silica. The surface charging mechanism with a liquid can have several origins [1]. One is the ionization and dissociation of a chemical group and another is ion adsorption, also called ion binding, on a surface which has a low charge or no charge initially. Whatever the wall charging mechanism, the final surface charge must be equilibrated by opposite sign charges accumulated in the fluid near the surface. The capacity of the wall to store charges is a function of its dielectric permittivity. For the purpose of this entry, the surface material is assumed to be fused silica (SiO_2). Water molecules hydrate the silica surface to create groups on the surface (Fig. 1). The physical mechanisms involved are the protonation and de-protonation of the SiO groups after hydration. The mechanism depends on the H^+ concentration given by the pH:

$$\mathrm{Si-O^- + H^+ \longleftrightarrow Si-OH}\,, \tag{1a}$$

$$\mathrm{Si-OH + H^+ \longleftrightarrow Si-OH_2^+}\,. \tag{1b}$$

If a pressure gradient is imposed on the fluid, a flow which contains charges appears and thus generates an electrostatic field due to the charge displacement. The electrostatic potential that is derived from this field is called the streaming potential. Without a pressure gradient, the fluid can be moved using an electrical field; hence an electro-osmotic flow appears. The fluid velocity profile which develops without the electric double layer (EDL) effect is parabolic; the velocity at the center of the microtube is maximum and null on the microtube surface. The charges in the fluid of opposite sign to that of the surface accumulate near the silica surface (SiO_2) and thus are transported at a lower speed than other charges far from the surface. These ion concentration laws are obtained by solving the Poisson–Boltzmann (PB) equation. Due to this differential transport phenomenon, an electric disequilibrium appears between the entrance and exit of the microtube in order to keep the total charge density constant. A current called a conduction current appears to counter the transport of charges by the fluid (streaming current). Without surface charges, no charge gradient appears in the cross-section; thus neither a streaming nor a conductive current appears. Considering that the Lorentz force (Eq. (2a)) applies on each charge, the balance between positive and negative charge is null at the center of the microtube and thus the resulting force is null. However, this disequilibrium induces a non-zero Lorentz force which has a maximum near the surface. This force decreases far from the surface as the excess charge density $\varrho(r)$ decreases. The fluid potential $\phi(r,z)$, written according to Eq. (2b), is a superposition of two potentials: the surface one $\psi(r)$ due to the EDL on the r-axis and the streaming one on the z-axis due to the differential transport phenomena of charges in the streaming field E_Z.

$$\boldsymbol{F}(r) = \varrho(r)E_Z\boldsymbol{e}_Z \tag{2a}$$

$$\phi(r,z) = \phi_0(r,z) - E_Z * z + \psi(r) \tag{2b}$$

$$E_Z = -\frac{\partial\phi(r,z)}{\partial z} \tag{2c}$$

The surface potential generates the charge gradient along the radius of the microtube according to an exponential law, whereas the streaming field induces a potential gradient along the microtube on the z-axis. As soon as ions are positioned radially, the pressure gradient induces a displacement on z. The total Lorentz force is thus on z. Its orientation is always in the direction of the flow. This phenomenon, in opposition to the fluid flow, occurs whatever the surface charge sign, as presented below:

- If the surface is negatively charged, positive charges are attracted near the surface of the microtube and thus a leak of these charges appears in the diffusive layer. The conduction current which characterizes the electron displacement is directed from the microtube


Microduct exit
EDL
EDL
EDL
EDL
F(r)
F(r)
F(r)
F(r)
L
L
solution electrically neutral
solution electrically neutral
Streaming current
Conduction current
Conduction current
Streaming current
E_Z
E_Z
0
0
Microduct entrance
Flow direction (pressure gradient)
Flow direction (pressure gradient)

Streaming Current and Electroviscosity, Figure 2 Fluid charge distributions, electrostatic field orientations, force orientations and intensities for positive and negative surface charges

entrance to the exit in the direction opposite to that of the electrical field. The local force $F(r)$ which is based on the excess charge density (here positive charges: $+$e) is applied on a field E_Z oriented following $-\boldsymbol{e}_Z$ (from the exit to the entrance). $F(r)$ is therefore oriented along $-\boldsymbol{e}_Z$ and acts in opposition to the flow.

- If the surface is positively charged, negative charges are attracted near the surface of the microtube and thus a leak of these charges appears in the diffusive layer. The conduction current which characterizes the electron displacement is in the direction opposite to that of the electrical field from the microtube exit to the entrance. The local force $F(r)$ which is based on the excess charge density (here negative charges: $-$e) is applied on a field E_Z oriented along $\boldsymbol{e}_Z$ (from the entrance to the exit). $F(r)$ is therefore oriented parallel to $-\boldsymbol{e}_Z$ and also acts in the direction opposite to that of the flow.

The formulation used in this entry is based on the EDL theory detailed by Israelachvili [1]. The surface potential used for further calculations is denoted by ψ_0. The compact layer near the surface has a thickness of only a few atoms (about 1 nm) whereas the diffusive layer can reach 1 µm. The interfacial potential between these layers is called the zeta potential (ζ). In further computations we assume $\zeta \sim \psi_0$. Assuming a negatively charged surface, which is the case corresponding to our material, positive charges are attracted to the surface and there is a leak of negative charges. To calculate the local density of ions and co-ions, we need to make the chemical potential (μ_C)

balance on each species using the equations given below, where z is the ion valence, k_B the Boltzmann constant, T the average fluid temperature and e the proton charge:

$$\mu_C^i = ze\psi + k_B T \log n^i \,, \tag{3a}$$

$$n^i(r) = n_0 \exp\left(-i\frac{ze\Psi(r)}{k_B T}\right) . \tag{3b}$$

Considering that this potential is conserved, the chemical potential can be written for a radius and at the microtube center where the electrostatic potential is null: $\psi_{r=0} = 0$ where the fluid charge density is the bulk density (n_0). The ion concentration is given by

$$\varrho(r) = [n^+(r) - n^-(r)]ze \,, \tag{4a}$$

$$\varrho(r) = -2n_0 ze \sinh \frac{ze\Psi(r)}{k_B T} . \tag{4b}$$

where n^+ and n^- are respectively the positive and negative ion concentrations. The excess charge density is expressed as a function of the electrostatic potential.

The Poisson equation gives the relationship between the electrostatic potential $\psi(r)$ and the charge density $\varrho(r)$. In a circular geometry, the relation is

$$\frac{1}{r}\frac{\mathrm{d}}{\mathrm{d}r}\left(r\frac{\mathrm{d}\Psi(r)}{\mathrm{d}r}\right) = -\frac{4\pi}{\varepsilon\varepsilon_0}\varrho(r) \,, \tag{5a}$$

$$\frac{1}{\bar{r}}\frac{\mathrm{d}}{\mathrm{d}\bar{r}}\left(\bar{r}\frac{\mathrm{d}\bar{\Psi}(\bar{r})}{\mathrm{d}\bar{r}}\right) = -\frac{4\pi n_0 e^2 R^2}{\varepsilon\varepsilon_0 k_B T}\bar{\rho}(\bar{r}) . \tag{5b}$$

For further calculations we define nondimensional parameters such as $\bar{r}$, $\bar{\varrho}(\bar{r})$, $\bar{\Psi}(\bar{r})$:

$$\bar{r} = \frac{r}{R} \,, \tag{6a}$$

$$\bar{\varrho} = \frac{\varrho}{n_0 e} \,, \tag{6b}$$

$$\bar{\Psi} = \frac{e\Psi}{k_B T} \tag{6c}$$

$$\bar{\rho}(\bar{r}) = -2\sinh\bar{\Psi}(\bar{r}) \tag{7}$$

When Eq. (7) is included in Eq. (5b), the PB equation is obtained. κ is the electrokinetic length (usually called the Debye–Hückel length). The definition of δ depends on the geometry studied because whatever the geometry $\kappa = \delta R$ constitutes the right term of the equation before $\sinh(\bar{\Psi}(\bar{r}))$. In the literature, δ in planar geometry differs slightly from δ in circular geometry: $\delta_{\text{circ}} = \sqrt{4\pi}\,\delta_{\text{plan}}$. The boundary conditions for this nonlinear ordinary differential equation of second order are given below:

$$\frac{1}{\bar{r}}\frac{\mathrm{d}}{\mathrm{d}\bar{r}}\left(\bar{r}\frac{\mathrm{d}\bar{\Psi}(\bar{r})}{\mathrm{d}\bar{r}}\right) = \kappa^2 \sinh\bar{\Psi}(\bar{r}) \,, \tag{8a}$$

$$\kappa = \delta R = \sqrt{\frac{8\pi n_0 z^2 e^2}{\varepsilon\varepsilon_0 k_B T}}R \,, \tag{8b}$$

$$\bar{r} = 0 \quad \Rightarrow \quad \frac{\mathrm{d}\bar{\Psi}(\bar{r})}{\mathrm{d}r} = 0 \,, \tag{8c}$$

$$\bar{r} = 1 \quad \Rightarrow \quad \bar{\Psi}(1) = \bar{\psi}_0 = \frac{e\psi_0}{k_B T} . \tag{8d}$$

The surface potential is related to the surface charge density through the charge balance, also known as the Grahame equation:

$$\sum_i \varrho_{0i} = \sum_i \varrho_{\infty i} + \frac{\sigma^2}{2\varepsilon\varepsilon_0 kT} \tag{9}$$

where σ is the charge density in Cm^{-2}. ϱ is the volumic density of charges in m^{-3}. Physically, the surface charge is constant for a given fluid while the surface potential is thereby a function of the charge fluid density. The glass–water surface potential is negative [2]. This is due to the $\mathrm{H_3O^+}$ ion adsorption from the water dissociation. The authors performed measurements for glass surfaces with KCl solutions and show for a 3×10^{-3} M solution a surface charge of $-0.8\,\mu\mathrm{C\,cm^{-2}}$. For a higher pH of, say, 8.5, the measured surface charge reaches $-1.75\,\mu\mathrm{C\,cm^{-2}}$.

For example, with a 1 : 1 electrolytic solution ($z = 1$) with a concentration varying from 10^{-4} to $1\,\mathrm{mol\,l^{-1}}$ and a low surface charge of $0.2\,\mu\mathrm{C\,cm^{-2}}$, we obtain the relation between the surface charge and the surface potential function of the ion concentrations (C):

$$\sigma = \sqrt{8\varepsilon\varepsilon_0 k_B T\left(1000\left[\frac{C}{2}\right]\right)N_a}\,\sinh\frac{e\psi_0}{2k_B T} \tag{10}$$

where N_a is the Avogadro number, ε the relative fluid permittivity and ε_0 the absolute fluid permittivity.

To solve the PB equation we consider two zones in the microtube. Thus the hyperbolic sinus function is dissociated into two functions:

$$\bar{\Psi}(\bar{r}) \ll 1 \quad \Rightarrow \quad \sinh\left(\bar{\Psi}(\bar{r})\right) \approx \bar{\Psi}(\bar{r}) \,, \tag{11a}$$

$$\bar{\Psi}(\bar{r}) \gg 1 \quad \Rightarrow \quad \sinh\left(\bar{\Psi}(\bar{r})\right) \approx \frac{1}{2}e^{\bar{\Psi}(\bar{r})} . \tag{11b}$$

Equation (11a) is used for the central zone of the microtube for low potentials ($\psi_0 < 25\,\mathrm{mV}$ or $\bar{\Psi}(1) < 1$) whereas Eq. (11b) is used for the zone near the surface with high surface potentials ($\psi_0 > 25\,\mathrm{mV}$ or $\bar{\Psi}(1) > 1$).

Thus we build a potential function consisting of two branches matched at $\bar{r} = \beta$. Both functions are written $\bar{\Psi}_1(\bar{r})$ for $\bar{r} < \beta$ and $\bar{\Psi}_2(\bar{r})$ for $\bar{r} > \beta$. The matching condition is required for the function and their first derivate equality at $\bar{r} = \beta$. The boundary conditions for the potential function are given below:

$$\left[\frac{\mathrm{d}\bar{\Psi}_1(\bar{r})}{\mathrm{d}\bar{r}}\right]_{\bar{r}=\beta} = \left[\frac{\mathrm{d}\bar{\Psi}_2(\bar{r})}{\mathrm{d}\bar{r}}\right]_{\bar{r}=\beta} \tag{12a}$$

$$\bar{\Psi}_1(\beta) = \bar{\Psi}_2(\beta) \tag{12b}$$

$$\bar{r} = 0 \quad \Rightarrow \quad \frac{\mathrm{d}\bar{\Psi}_1(\bar{r})}{\mathrm{d}\bar{r}} = 0 \tag{12c}$$

$$\bar{r} = 1 \quad \Rightarrow \quad \bar{\Psi}_2(1) = \bar{\psi}_0 \tag{12d}$$

The continuity condition on the first derivative is used to access β which cannot be obtained analytically. At this stage it is necessary to solve the problem using a mathematical solver. The method for the solution of the ordinary differential equation is given by Levine et al. [3].

The momentum balance equation is applied for our situation with a volumic force due to the heterogeneous presence of charge excess. The geometry considered is a one-dimensional circular one with an incompressible liquid flow on the z-axis:

$$\frac{\mu}{r}\frac{\mathrm{d}}{\mathrm{d}r}\left(r\frac{\mathrm{d}U_\mathrm{Z}(r)}{\mathrm{d}r}\right) - \frac{\mathrm{d}P}{\mathrm{d}z} + F_\mathrm{Z} = 0 \tag{13}$$

For the sake of simplicity we use the following notations. F_Z is expressed as a function of the excess charge density ($\varrho(r)$) and E_Z is the electrostatic field given by $E_Z = E_S/L$, where E_S is the electrical field:

$$P_\mathrm{Z} = \frac{\mathrm{d}P}{\mathrm{d}z} \tag{14a}$$

$$F_\mathrm{Z} = E_\mathrm{Z}\varrho(r) \tag{14b}$$

$$\bar{U} = \frac{U_\mathrm{Z}}{U_0} \tag{14c}$$

Thus we obtain the following ordinary differential equation to solve

$$\frac{1}{\bar{r}}\frac{\mathrm{d}}{\mathrm{d}\bar{r}}\left(\bar{r}\frac{\mathrm{d}\bar{U}(\bar{r})}{\mathrm{d}\bar{r}}\right) + K_1 - \frac{K_2\bar{E}_\mathrm{S}}{\kappa^2}\frac{1}{\bar{r}}\frac{\mathrm{d}}{\mathrm{d}\bar{r}}\left(\bar{r}\frac{\mathrm{d}\bar{\Psi}(\bar{r})}{\mathrm{d}\bar{r}}\right) = 0 \tag{15a}$$

where K_1, K_2 and E_S are defined as

$$K_1 = \frac{P_\mathrm{Z}R^2}{\mu U_0} \tag{15b}$$

$$K_2 = \frac{2n_0 e\xi R^2}{\mu U_0 L} \tag{15c}$$

$$\bar{E}_\mathrm{S} = \frac{E_\mathrm{S}}{\xi} \tag{15d}$$

K_1 is the classical force ratio between pressure and the viscous forces. With a difference of one coefficient, K_1 is the classical definition of the Poiseuille number.

Without the presence of the EDL, it is possible to relate K_1 to the wall shear stress by creating a force balance on the perimeter of the microtube. Thus we obtain the relation between the classical Poiseuille number (Po) and K_1 which is $K_1 = \mathrm{Po}/8$. With the EDL, an additional term must be accounted for. This is the first space integration of the EDL force in the cross-section:

$$P_\mathrm{Z} = \frac{4\tau_W}{D} \tag{16}$$

Equation (15a) is transformed into

$$\frac{1}{\bar{r}}\frac{\mathrm{d}}{\mathrm{d}\bar{r}}\left(\bar{r}\frac{\mathrm{d}}{\mathrm{d}\bar{r}}\left(\bar{U} - \frac{K_2\bar{E}_\mathrm{S}}{\kappa^2}\bar{\Psi}\right)\right) + K_1 = 0 \tag{17a}$$

then spatially integrated twice to obtain $\bar{U}(\bar{r})$ given by

$$\bar{U}(r) = \frac{K_1}{4}(1 - r^2) - \frac{K_2\bar{\xi}\bar{E}_\mathrm{S}}{\kappa^2}\left(1 - \frac{\bar{\Psi}(r)}{\bar{\xi}}\right) \tag{17b}$$

The velocity profile is a function of the electrostatic potential function. For information, the reference velocity profile is given by

$$\bar{U}_\mathrm{ref}(\bar{r}) = 2(1 - \bar{r}^2) \tag{17c}$$

and will be used in the following sections for comparison. The electrostatic potential is solved as a function of $\bar{r}$ for both differential Eqs. (18a) and (18b) in the two separated zones:

$$\frac{1}{\bar{r}}\frac{\mathrm{d}}{\mathrm{d}\bar{r}}\left(\bar{r}\frac{\mathrm{d}\bar{\Psi}_1(\bar{r})}{\mathrm{d}\bar{r}}\right) = \kappa^2\bar{\Psi}_1(\bar{r}) \quad \forall\bar{r} \in [0, \beta] \tag{18a}$$

$$\frac{1}{\bar{r}}\frac{\mathrm{d}}{\mathrm{d}\bar{r}}\left(\bar{r}\frac{\mathrm{d}\bar{\Psi}_2(\bar{r})}{\mathrm{d}\bar{r}}\right) = \frac{\kappa^2}{2}e^{\bar{\Psi}_2(\bar{r})} \quad \forall\bar{r} \in [\beta, 1] \tag{18b}$$

The solution of Eq. (18a) can easily be obtained and is given below, where Bessel I_0 is the modified Bessel function of the first kind zero order:

$$\bar{\Psi}_1(\bar{r}) = \frac{\text{Bessel}\, I_0(\kappa\bar{r})}{\text{Bessel}\, I_0(\beta\kappa)} \tag{19}$$

The validity range for the integration of Eq. (18a) is the microtube cross-section ($\bar{r} \in [0, 1]$) and thus we obtain the solution for the assumption of low potentials (< 25 mV). This solution is called LP for 'low potentials':

$$\bar{\Psi}(\bar{r})_{\text{LP}} = \bar{\psi}_0 \frac{\text{Bessel}\; I_0(\kappa\bar{r})}{\text{Bessel}\; I_0(\kappa)} \tag{20}$$

It will be compared with the full solution for high potentials (HP) in the following sections.

According Levine et al. [3] in the case $P < 0$ the solution of Eq. (18b) is given by

$$\bar{\Psi}_2(\bar{r}) = \ln\left(\frac{-P}{\kappa^2\bar{r}^2\cos^2(Q + \frac{1}{2}\sqrt{-P}\ln\bar{r})}\right) \tag{21a}$$

where

$$P = \left[2 + \beta\kappa\frac{\text{Bessel}\; I(1, \beta\kappa)}{\text{Bessel}\; I(0, \beta\kappa)}\right]^2 - e^1\beta^2\kappa^2 \tag{21b}$$

and

$$Q = \cos^{-1}\left(\sqrt{\frac{-P}{e^{\psi_0}\kappa^2}}\right) \tag{21c}$$

The electrostatic potential variation is solved for both zones as defined by

$$\bar{\Psi}(\bar{r})_{\text{HP}} = \begin{cases} \bar{\Psi}_1(\bar{r}) = \dfrac{\text{Bessel}\; I_0(\kappa\bar{r})}{\text{Bessel}\; I_0(\beta\kappa)} \\ \qquad \text{if } \bar{r} \in [0, \beta] \\ \bar{\Psi}_2(\bar{r}) = \ln\left(\dfrac{-P}{\kappa^2\bar{r}^2\cos^2(Q + \frac{1}{2}\sqrt{-P}\ln\bar{r})}\right) \\ \qquad \text{if } \bar{r} \in [\beta, 1] \end{cases} \tag{22}$$

Thus it is possible to obtain the velocity profile as given by

$$\bar{U}(\bar{r})_{\text{HP}} = \begin{cases} \bar{U}_1(\bar{r}) = \dfrac{K_1}{4}(1 - \bar{r}^2) \\ \qquad - \dfrac{K_2\bar{\psi}^2\bar{E}_{\text{S}}}{\kappa^2}\left(1 - \dfrac{\bar{\Psi}_1(\bar{r})}{\bar{\psi}_0}\right) \\ \qquad \text{if } \bar{r} \in [0, \beta] \\ \bar{U}_2(\bar{r}) = \dfrac{K_1}{4}(1 - \bar{r}^2) \\ \qquad - \dfrac{K_2\bar{\psi}^2\bar{E}_{\text{S}}}{\kappa^2}\left(1 - \dfrac{\bar{\Psi}_2(\bar{r})}{\bar{\psi}_0}\right) \\ \qquad \text{if } \bar{r} \in [\beta, 1] \end{cases} \tag{23}$$

Now we need to determine $\bar{E}_{\text{S}}$ from the electrical charge balance inside the microtube.

A forced ionic liquid flow generated by a pressure gradient induces an electrostatic field E_{S}. The current induced by the charge displacement in the flow is called the electrostatic current I_{S}; its expression is

$$I_{\text{S}} = 2\pi\int_0^R U(r)\varrho(r)r\,\mathrm{d}r \tag{24a}$$

After a classical nondimensioning of the governing equations on $U(r)$ and $\varrho(r)$, the expression of $\bar{I}_{\text{S}}$ is

$$\bar{I}_{\text{S}} = \frac{I_{\text{S}}}{U_0R^2n_0e} = -4\pi\int_0^1 \bar{U}(\bar{r})\bar{\Psi}(\bar{r})\bar{r}\,\mathrm{d}\bar{r} \tag{24b}$$

Applying the electric neutrality of the fluid inside the microtube, a conduction current (I_{C}) occurs in order to equilibrate the streaming current due to the charge displacement. The following equation gives the expression of the conduction current:

$$\begin{aligned} I_{\text{C}} &= \int_0^R 2\pi rme[n_+(r) + n_-(r)]\frac{E_{\text{S}}}{L}\,\mathrm{d}r \\ &= \frac{E_{\text{S}}\lambda_0}{L}\int_0^R 2\pi r\cosh\bar{\Psi}(r)\,\mathrm{d}r \end{aligned} \tag{25}$$

where λ_0 is the electrical fluid conductivity which can be calculated using

$$\lambda_0 = \text{F}^2\sum z_i^2\nu_i c_i \tag{26}$$

where ν_i is the ion mobility, c_i is the ion concentration, z_i is the charge and F is the Faraday constant.

Using a nondimensional form with Eq. (27c), we obtain Eq. (27a) where Σ_1 is a pure numerical integration:

$$\bar{I}_{\mathrm{C}} = \frac{I_{\mathrm{C}}}{\lambda_0 R \psi_0} = 2\pi \bar{E}_{\mathrm{S}} \bar{L} \Sigma_1 \tag{27a}$$

$$\Sigma_1 = \int_0^1 \bar{r} \cosh \bar{\Psi}(\bar{r})\, \mathrm{d}\bar{r} \tag{27b}$$

$$\bar{L} = \frac{L}{R} \tag{27c}$$

Using Eq. (28), the balance is written for both currents:

$$I_{\mathrm{S}} + I_{\mathrm{C}} = 0 \tag{28}$$

Thus we obtain $\bar{E}_{\mathrm{S}}$ which is given by

$$\bar{E}_{\mathrm{S}} = 2\frac{K_3}{\Sigma_1} \int_0^1 \bar{r} \bar{U}(\bar{r}) \bar{\Psi}(\bar{r})\, \mathrm{d}\bar{r} = \frac{K_1 \Sigma_3}{\frac{2\Sigma_1}{K_3} + \frac{4K_2 \bar{\psi}_0 \Sigma_4}{\kappa^2}} \tag{29}$$

where K_3 is given by

$$K_3 = \frac{n_0 e L U_0}{\lambda_0 \psi_0} \tag{30}$$

and

$$\Sigma_3 = \int_0^1 \bar{r}(1 - \bar{r}^2) \bar{\Psi}(\bar{r}) \tag{31}$$

$$\Sigma_4 = \int_0^1 \bar{r} \left(1 - \frac{\bar{\Psi}(\bar{r})}{\bar{\psi}_0}\right) \bar{\Psi}(\bar{r}) \tag{32}$$

Using the nondimensional electrostatic potential expression in the velocity profile expression, we obtain the Poiseuille number expression. K_3 is the nondimensional ratio between the convection current and the conduction current.

Electroviscosity

Theory

The net effect of the charge forces close to the wall is a diminished flow in the main flow axis. The fluid appears to exhibit an enhanced viscosity if its flow rate is compared with the flow without the EDL effects. This increase in apparent viscosity of a fluid is the ▶electroviscous effect [4–6].

To calculate ▶electroviscosity, we first define the volumic flow rate using

$$Q_{\mathrm{V}} = \int_0^R U(r) 2\pi r\, \mathrm{d}r \tag{33}$$

To use the previous results of the fluid velocity profile, we require a nondimensional form of the volumic flow rate:

$$Q_{\mathrm{V}} = 2\pi R^2 U_0 \int_0^1 \bar{r} \bar{U}(\bar{r})\, \mathrm{d}\bar{r} \tag{34}$$

The expression of the fluid velocity has already been calculated in the previous section (Eq. (23)). For calculation purposes, we use the following writing simplification ($i = 1$ if $\bar{r} < \beta$, $i = 2$ if $\bar{r} > \beta$):

$$\bar{U}_i(\bar{r}) = \frac{K_1}{4}(1 - \bar{r}^2) - \frac{K_2 \bar{\psi}_0 \bar{E}_{\mathrm{S}}}{\kappa^2} \left(1 - \frac{\bar{\Psi}_i(\bar{r})}{\bar{\psi}_0}\right) \tag{35}$$

By replacing the fluid velocity expression, we extract the expression of the volumic flow rate:

$$Q_{\mathrm{V}} = 2\pi R^2 U_0 \left[\frac{K_1}{24} - \frac{K_2 \bar{\psi}_0 \bar{E}_{\mathrm{S}}}{\kappa^2} \int_0^1 \bar{r} \left(1 - \frac{\bar{\Psi}_i(\bar{r})}{\bar{\psi}_0}\right)\right] \tag{36}$$

The expressions of K_1 and K_2 (Eqs. (15b) and (15c)) are introduced into Eq. (36) to reveal the fluid viscosity:

$$Q_{\mathrm{V}} = \frac{\pi R^4}{12\mu} P_{\mathrm{Z}} - \frac{4\pi R^4 n_0 e \xi \bar{\psi}_0 \bar{E}_{\mathrm{S}}}{\mu L \kappa^2} \int_0^1 \bar{r} \left(1 - \frac{\bar{\Psi}_i(\bar{r})}{\bar{\psi}_0}\right) \tag{37}$$

The apparent fluid viscosity (μ_{a}) can be deduced by assuming the classical relation between volumic flow rate and pressure drop:

$$Q_{\mathrm{V}} = \frac{\pi R^4}{12\mu_{\mathrm{a}}} P_{\mathrm{Z}} \tag{38}$$

$$\frac{\mu_{\mathrm{a}}}{\mu} = \frac{1}{1 - \frac{32\bar{E}_{\mathrm{S}}(\bar{\psi}_0)^2 \varepsilon\varepsilon_0}{\pi R^2 P_Z L} \int_0^1 \bar{r} \left(1 - \frac{\bar{\Psi}_i(\bar{r})}{\bar{\psi}_0}\right)} \tag{39}$$

Volumic flow rates which are identical are identified and enable us to find the ▶electroviscosity.

Equation (39) gives the ▶electroviscosity in a microtube with an inner charged surface at the potential ψ_0. The reduced forward volumic flow rate observed experimentally is interpreted as an increased apparent viscosity. Using the expressions of K_1, K_2, E_{S} and K_3 (respectively Eqs. (15b), (15c), (29) and (30)) it is possible to evidence that μ_{a}/μ is a function of neither the average fluid velocity (U_0) nor the pressure gradient (P_Z) but only a function of the microtube diameter and the electrokinetic parameters.

The case of two parallel plates has been studied by Mala et al. [6] and will not be presented here. The ▶electroviscosity equation obtained differs slightly from Eq. (39) due to the geometry.



Streaming Current and Electroviscosity, Figure 3 Electroviscosity as a function of microtube radius for a pure deionized water flow with an electrical surface potential of 57 mV



Streaming Current and Electroviscosity, Figure 4 Electroviscosity as a function of fluid ionic concentration in a microtube with a diameter of 1 μm and an electrical surface potential of 40 mV

Example

Let us consider a capillary tube with a radius ranging from 1 to 24 μm, which corresponds to commercial fused silica microtubes used in gas chromatography. The fluid is pure deionized water with a total ionic concentration of 2×10^{-7} M and consequently an electrical conductivity of 4.1×10^{-7} S m^{-1}. The inner capillary surface is slightly charged at 50 μC m^{-2}, with a 1 : 1 electrolytic solution ($z = 1$). We obtain the relation between the surface charge and the surface potential function of the ion concentrations with Eq. (10). The surface potential (ψ_0) which is calculated by deduction is 57 mV.

Figure 3 presents the variation of the ►electroviscosity for a fluid flow of pure deionized water in a microtube with a radius ranging from 1 to 24 μm. The increase in ►electroviscosity in a microtube is not perceptible for diameters above 15 μm. Below 15 μm the increase becomes perceptible with a maximum of 25% for a microtube with a diameter of 2 μm. The model previously described and the mathematical assumptions are correct since the radius of the microtube is greater than the electrokinetic distance, which is about 1 μm for pure water. Experiments with microtubes smaller than the electrokinetic distance have not as yet been reported in the literature.

Figure 4 presents the variation of the ►electroviscosity for a KCl solution with an ionic concentration ranging from 3×10^{-7} to 10^{-5} M. As the ionic concentration increases, the electrokinetic distance ($1/\delta$) decreases according to Eq. (8b). The surface potential is constant at 40 mV and the diameter of the microtube is 1 μm. The largest electrokinetic distance is about 0.2 μm for the lowest ionic concentration based on two kinds of ions: K^+ and Cl^- for a total number charge (n_0). The ►electroviscosity is almost the classical fluid viscosity for solution concentrations higher than 10^{-5} M. For lower concentrations up to 3×10^{-7} M the apparent viscosity increases to reach +50% for a 3×10^{-7} M concentration, which is close to the ion concentration of pure water (total ion concentration of 2×10^{-7} M with H_3O^+ and OH^-).

Key Research Findings

The experimentally observed differences in the literature for fluid flow in microchannels can have many explanations. Some deviations can be rapidly explained by the use of microducts which have not been well calibrated. The four main effects proposed to explain these observed deviations are: the micropolar fluids theory, electrokinetic effects, heat viscosity dissipation and the wall continuity condition. Among all these effects electrokinetic flow has been more widely investigated in the literature; ion interaction with water is of great importance in biological and chemical applications for MEMS technology.

Electroviscous effects on fluid flow for ionic fluids in microchannels have been evidenced over the last decade experimentally [7–9] and are still a subject of widespread theoretical research [4, 10]. Ren et al. [5] found experimentally significant electroviscous effects for dilute solutions flowing through microchannels with hydraulic diameters of 14.1, 28.2 and 40.5 μm. They elaborated a model for a microchannel between two plates which considers the deficit of counterions and the surplus of co-ions outside the EDL. They obtain a nonzero electrical potential gradient and a net charge density near the middle plane of the microchannel. The highest fluid velocity and the transport of the net charge at the center of the microchannel result in a higher streaming potential.

Cross References

- ▶ Electroosmotic Flow (DC)
- ▶ AC Electro-Osmotic Flow
- ▶ Electrokinetic/Hydrodynamic Flow Instability
- ▶ Nonlinear Electrokinetic Phenomena
- ▶ Surface Conductivity Measurement
- ▶ Temperature Effects on the Zeta Potential
- ▶ Zeta Potential Measurement

References

1. Israelachvili JN (1991) Intermolecular and Surface Forces. Academic Press, London
2. Schweiss R, Welzel PB, Werner C, Knoll W (2001) Interfacial charge of organic thin films characterized by streaming potential and streaming current measurements. Colloids Surf 195:97–102
3. Levine S, Marriott JR, Neale G, Epstein N (1975) Theory of electrokinetic flow in fine cylindrical capillaries at high zeta-potentials. J Colloid Interface Sci 52(1):136–149
4. Bowen WR, Jenner F (1995) Electroviscous effects in charged capillaries. J Colloid Interface Sci 173:388–395
5. Ren CL, Li D (2004) Electroviscous effects on pressure-driven flow of dilute electrolyte solutions in small microchannels. J Colloid Inferface Sci 274:319–330
6. Mala GM, Li D, Dale JD (1997) Heat transfer and fluid flow in microchannels. Int J Heat Mass Transf 40(13):3079–3088
7. Ren L, Qu W, Li D (2001) Interfacial electrokinetic effects on liquid flow in microchannels. Int J Heat Mass Transf 44:3125–3134
8. Brutin D, Topin F, Tadrist L (2003) A transient method for the liquid laminar flow friction factor in microtubes. AIChE J – Fluid Mech Transp Phenom 49(11):2759–2767
9. Brutin D, Tadrist L (2003) Experimental friction factor of a liquid flow in microtubes. Phys Fluids 15(3):653–661
10. Vainshtein P, Gutfinger C (2002) On electroviscous effects in microchannels. J Micromech Microeng 12(2):252–256

Streaming Dielectrophoresis

- ▶ DC Dielectrophoresis in Lab-on-a-Chip Devices

Stroke

Synonyms

Throw

Definition

In an actuator that produces linear translation, *stroke* refers to the maximum amplitude of the motion.

Cross References

- ▶ Membrane Actuation for Micropumps
- ▶ Microactuators
- ▶ Peristaltic Pumps
- ▶ Positive Displacement Pump

Stroke Volume

Definition

In a positive displacement pump a moving boundary changes the volume of a pump chamber. The *stroke volume* is the difference between the maximum and minimum chamber volumes.

Cross References

- ▶ Compression Ratio
- ▶ Dead Volume
- ▶ Electromagnetic Valves
- ▶ Electrostatic Valves
- ▶ Magnetic Pumps
- ▶ Membrane Actuation for Micropumps
- ▶ Microactuators
- ▶ Peristaltic Pumps
- ▶ Piezoelectric Valves
- ▶ Pneumatic Valves
- ▶ Positive Displacement Pump
- ▶ Thermomechanical Valves
- ▶ Thermopneumatic Valves

Subcooled Flow Boiling

Definition

Boiling process at the wall while the mean bulk enthalpy of flow is below the saturation enthalpy corresponding to the local pressure.

Cross References

- ▶ Bubble Dynamics in Microchannels

Subdynamic Regime

Definition

Laminar fluid flow regime in which inertial effects become negligible compared with frictional damping.

This regime exists at very low values of the Reynolds number, usually below $\mathrm{Re} \simeq 10$. In the true subdynamic regime the character of the flow ceases to depend on the Reynolds number, the flowfield becomes self-similar. Microfluidic devices are rarely if at all employed in the subsonic regime – usually the inertial effects remain noticeable in them. The regime, however, served as a useful reference asymptotic state.

Superfast Electrophoresis

- ► Electrophoresis of the Second Kind

Super-Limiting Current

Definition

A super-limiting current in an electrolyte is an ionic current large enough to exceed diffusion limitation, which depletes the bulk salt concentration and leads to the formation of extended space charge.

Cross References

- ► Electrical Double Layers
- ► Electroosmosis of the Second Kind
- ► Electrophoresis of the Second Kind
- ► Nonlinear Electrokinetic Phenomena
- ► Space Charge

Superparamagnetism

Definition

Superparamagnetism characterizes materials that have susceptibility typical of ferromagnetism and a reversible magnetization like paramagnetic matter.

Cross References

- ► Magnetic Field-Based Lab-on-Chip Devices

Supersonic Micro-Nozzles

William F. Louisos, Darren L. Hitt
Mechanical Engineering Program, School of Engineering,
University of Vermont, Burlington, VT, USA
darren.hitt@uvm.edu

Synonyms

MEMS-nozzle; Microthruster; MEMS-thruster

Definition

The fundamental purpose of any nozzle is the acceleration of a flow field via the conversion of available pressure and/or internal energy into kinetic energy. For compressible fluids (gases), it is possible accelerate to the flow from subsonic to sonic speeds – and ultimately supersonic speeds – with sufficiently high inlet pressure ratios. Supersonic nozzles typically consist of three distinct regions: a subsonic converging portion at the inlet, followed by a 'throat' where the cross-sectional area is minimum, and finally a supersonic diverging section ('expander'). Micronozzles are uniquely defined by their small length scales (throat diameters typically below 100 μm) and the low Reynolds numbers of the flow ($\text{Re} < 1000$).

Overview

Perhaps the most frequent engineering application of nozzles is in propulsion systems for aircraft or spacecraft; however, other important applications exist as well (e. g., spray nozzles and fluid atomization). Initial acceleration of a flow at subsonic speeds occurs in the convergent section and, for sufficiently high pressure ratios and nozzle area contraction, it is possible to accelerate a flow to sonic conditions at the nozzle throat. The addition of a divergent section downstream of the throat enables further acceleration of the flow through supersonic expansion (i. e., a *de Laval* nozzle). It is the ability of the convergent–divergent nozzle to fully and efficiently extract pressure/internal energy from a low speed inlet flow and produce supersonic exit velocities that make it such a vital component in high-speed aerospace propulsion. In the present article, we shall restrict our focus to supersonic nozzle behavior within the context of propulsion physics and engineering.

In most aerospace propulsion applications, the combination of high speeds and moderate-to-large length scales result in very high Reynolds numbers – sufficiently large that viscous effects can be largely ignored and inviscid analyses employed as a first approximation. However, the importance of viscous effects in supersonic flows is emerging in light of recent trends within the aerospace community linked to the design of next-generation miniaturized spacecraft. Most commonly known as 'nano-sats' (The names 'micro-sats' and more recently 'pico-sats' are also used, and to a certain degree, they can be regarded as interchangeable with nano-sat. At present there exists no formalism to distinguish the specific mass range that defines a micro/nano/pico-sat other than being successfully smaller than each other), these spacecraft will feature masses < 20 kg and be capable of operating in distributed networks ('formation flying') and performing mission objectives not currently achievable with traditional satellite architectures. Over the past decade, numerous and diverse micropropulsion initiatives for nano-sats have been undertaken by governments, industry, and academia throughout the world. The various approaches, all of which tend to have their unique benefits, have included both liquid/solid chemical propellants and electric propulsion concepts; many of these options require supersonic micro-nozzles as an integral part of the design. For the interested reader, a comprehensive survey of current micropropulsion concepts is given by Mueller [1].

As a result of the dramatically reduced size, nano-sats require miniaturized propulsion systems to provide the extremely low levels of thrust/impulse necessary for orbital maneuvering and precise station-keeping. With the characteristic length scales being considered for these new propulsion systems being on the order of microns to millimeters, the corresponding Reynolds numbers within the supersonic nozzles are $\mathrm{Re} \sim 10^2 - 10^3$ and hence viscous effects can no longer be ignored. The scenario of low Reynolds number, supersonic flow represents a *very unusual flow regime*, and one that has not been extensively examined in the fluid dynamics literature. In this regime, there is the usual thermo-fluidic complexity of a supersonic flow superimposed with subsonic viscous boundary layers extending from solid surfaces. At these low Reynolds numbers the viscous layer can occupy a sizable fraction of the divergent nozzle cross-section and, as a consequence, substantially impact the performance of the nozzle (e. g. thrust production). Aside from viscous forces, other important effects such as heat transfer and flow rarefaction may also be present on the micro-scale. The former becomes a concern as the thermal mass of the flow is reduced and the surface area-to-volume ratio increases on the micro-scale. The latter introduces additional complications since gas kinetic (non-continuum) effects begin to emerge as the characteristic length scales begin to approach molecular mean free paths.

In this article, we provide an overview of the various engineering issues and challenges surrounding the modeling, design and fabrication of micro-propulsion systems and supersonic micro-nozzles in particular. From this, it is our hope and intent that the reader will develop an appreciation for the unique aspects of supersonic nozzle behavior on the micro-scale.

Basic Methodology

Design Considerations and Specifications

Micro-Electro-Mechanical Systems (MEMS) techniques offer great potential in satisfying future mission requirements for the next generation of small scale spacecraft being designed by the aerospace community. Owing to the substantially reduced size, nano-sats have unique propulsion requirements, including extremely low thrust levels and/or extremely low minimum impulse requirements for orbital maneuvers and attitude control. Nanosatellites will be launched from Earth in a consolidated manner via a single rocket. Once in orbit, they will be subsequently deployed and operate in a distributed network performing simultaneous, multi-point observations and communication. The Magnetospheric Constellation (MagCon) is an example of one mission currently being designed by the NASA Goddard Space Flight Center (GSFC) that will utilize the unique characteristics of nano-satellites to monitor the Earth's magnetosphere. This type of space mission is not feasible with traditional satellite architectures. Nano-satellite technology demands highly accurate and extremely precise control of the spacecraft to maintain pattern formation. The primary method of attitude control is spin axis precession. In order to correct for perturbations such as solar radiation pressure or gravitational non-uniformities, the propulsion system must operate by firing low thrust, precise, and controlled impulse 'bits'. As a result of the spacecraft's reduced size and mass, the ability to perform spin axis precession and very small station-keeping maneuvers will require the development of radically new propulsion systems.

Supersonic Micro-Nozzles, Table 1 Design parameters for the NASA/GSFC MEMS-based monopropellant supersonic micro-nozzle.

Design Parameter	Value/Range
Target Thrust Level	10 – 500 μN
Maximum Specific Impulse	180 sec
Specific Impulse Efficiency	80%
Steady State Inlet Pressure	250 kPa
Mass Flow Rate	$\sim$ 0.015 kg/sec
Throat Area	9000 $\mu\mathrm{m}^2$
Expansion Ratio	6.22
Inlet Mach No.	0.05
Exit Mach No.	2.5 – 3.0
Reynolds Number	$<$ 1000
Impulse Bit	1 – 100 μN sec

As an illustrative example, NASA/GSFC has designed a prototype monopropellant micro-thruster, shown in Fig. 1, for the purpose of nano-satellite attitude control and station keeping maneuvers [2]. The supersonic micro-nozzle has been outlined in the figure for clarity. A listing of target design specifications for this prototype is given in Table 1. The NASA/GSFC prototype is based on catalytic decomposition of a liquid monopropellant; specifically hydrogen peroxide H_2O_2 or hydrazine N_2H_4. Chemical-based propulsion schemes, on the whole, are attractive in several regards: they feature relatively high energy densities and efficiencies; the propellants can be stored at low pressures thus alleviating leakage concerns; and they offer the ability to throttle and control the rate of thrust production via transient operation.

Quasi-1D Flow Approximation and Analysis

A supersonic micro-nozzle consists of a micro-machined channel with a varying cross-sectional area $A(x)$, where the $+x$-direction coincides with the flow direction within the channel. Under the 'quasi-one-dimensional' (quasi-1D) flow approximation, all flow variables are assumed to vary only with the streamwise position x (and time if the flow field is unsteady). Variations across a given cross-section are considered negligible. Such an approximation is valid provided that the *rate of area variation* $\mathrm{d}A/\mathrm{d}x$ *is sufficiently small*. The quasi-1D model is, of course, only an approximation of an actual 3D flow; however, it greatly simplifies analyses and often yields surprisingly good results in predicting basic nozzle behavior. An overview of the quasi-1D nozzle model and its limitations can be found in most gas dynamics references (e. g., [3]).



Supersonic Micro-Nozzles, Figure 1 (Top) A photograph of the NASA/GSFC MEMS-based micro-thruster etched into a silicon wafer and placed on top of a US penny for purposes of scale. (Bottom) A Scanning Electron Microscopy (SEM) image of the NASA/GSFC micro-thruster with the converging-diverging supersonic micro-nozzle outlined for clarity. See [2] for details

The governing equations for the flow are obtained by one-dimensional approximations of conservation laws for mass, momentum and energy. Often the additional assumptions of inviscid, adiabatic flow are invoked and, as a consequence, the flow is regarded as isentropic throughout. From the conservation laws, one may derive an important relation between the cross-sectional area, the velocity and the local Mach number:

$$\frac{\mathrm{d}A}{A} = \left(\mathrm{M}^2 - 1\right) \frac{\mathrm{d}u}{u} \tag{1}$$

Here $\mathrm{M} = u/a$ is the Mach number and a is the isentropic speed of sound defined by

$$a^2 = \gamma RT \tag{2}$$

where T is the static temperature, R is the gas constant, and $\gamma = C_\mathrm{p}/C_\mathrm{v}$ is the ratio of the specific heats.

The area-velocity relation provides important insight regarding the behavior of a quasi-1D compressible flow in a channel of varying cross section. It states that for a subsonic flow ($\mathrm{M} < 1$) to increase velocity, a decrease in cross-sectional area is required. This is an intuitive and familiar result similar to incompressible flow theory. In contrast, acceleration of a supersonic flow ($\mathrm{M} > 1$), requires an increase in area: a counter-intuitive result when viewed from an incompressible flow perspective. This relation also indicates that sonic velocity ($\mathrm{M} = 1$) can only occur at a nozzle throat where the area is a minimum. It thus follows for a gas to expand from subsonic to supersonic velocities, it must flow through a convergent–divergent channel arrangement.

An alternative and extremely useful form of the area-velocity relation (1) can be derived for isentropic flow which relates the local Mach number to the local area,

$$\left(\frac{A}{A_*}\right)^2 = \frac{1}{\mathrm{M}^2}\left[\frac{2}{\gamma+1}\left(1 + \frac{\gamma-1}{2}\mathrm{M}^2\right)\right]^{\frac{\gamma+1}{\gamma-1}} \tag{3}$$

where A_* is the area of the nozzle throat where sonic conditions exist. For a prescribed nozzle profile $A(x)$, this 'area-Mach relation' yields the corresponding variation in the Mach number along flow direction. Further, for isentropic flow, it can be shown that the local thermodynamic properties (T, p, ρ) may be uniquely determined by the local Mach number according to the following:

$$\frac{T_0}{T} = 1 + \frac{\gamma - 1}{2}\mathrm{M}^2 \tag{4}$$

$$\frac{p_0}{p} = \left(1 + \frac{\gamma - 1}{2}\mathrm{M}^2\right)^{\frac{\gamma}{\gamma-1}} \tag{5}$$

$$\frac{\rho_0}{\rho} = \left(1 + \frac{\gamma - 1}{2}\mathrm{M}^2\right)^{\frac{1}{\gamma-1}} \tag{6}$$

Here, the subscript “0” indicates the stagnation conditions ($\mathrm{M} \to 0$) corresponding to a specific flow state. In practice, these are the conditions of the gaseous products of chemical decomposition or combustion that exist upstream of the nozzle inlet and, therefore, may be regarded as known states for the purposes of the nozzle modeling.

In summary, for a prescribed nozzle profile $A(x)$ and inlet conditions, the area-Mach relation (3) and isentropic flow relations (4)–(6) are sufficient to completely determine the nozzle flow field under the quasi-1D model.

Thrust and Impulse

The ultimate deliverable for a supersonic nozzle in a propulsion application is the production of thrust and impulse. A control volume analysis of the nozzle indicates that the thrust produced at any moment in time can be approximated by the exit conditions according to

$$\boldsymbol{F} = \int_{A_{\mathrm{exit}}} \rho \boldsymbol{u}\,(\boldsymbol{u} \cdot \boldsymbol{n})\,\mathrm{d}A \approx \dot{m}\boldsymbol{V}_{\mathrm{exit}} \tag{7}$$

where $\dot{m} = \rho_{\mathrm{exit}} V_{\mathrm{exit}} A_{\mathrm{exit}}$ is the mass flow rate through the nozzle and $\boldsymbol{V}_{\mathrm{exit}}$ is the average velocity at the nozzle exit plane. For transient operation, the total impulse during a single firing cycle of the thruster is given by

$$\boldsymbol{I} = \int_0^{t_{\mathrm{b}}} \boldsymbol{F}\,\mathrm{d}t \tag{8}$$

where t_{b} is the total burn time or thrust duration of a single micro-nozzle firing. Under the quasi-1D approximation, all force generated is necessarily in the axial direction (i. e., thrust). In actual 2D or 3D flows, this will generally not be the case and there will be performance reductions resulting from transverse velocity components at the exit. Thus, exit flow alignment is yet another consideration that is part of the overall supersonic nozzle design.

Continuum vs. Rarefied Flows

The preceding discussion has implicitly assumed that the flow conditions are such that the continuum assumption remains valid within the micro-nozzle. The usual metric cited in arguing for (or against) the continuum assumption is the *Knudsen number* Kn, defined by $\mathrm{Kn} = \Lambda/L$ where Λ is the mean free path of the fluid particle and L is a characteristic length scale. For converging-diverging nozzles the throat dimension is commonly chosen as the characteristic length scale. An alternative version of the Knudsen number which is of particular use in investigating supersonic flows is given by

$$\mathrm{Kn} = \sqrt{\frac{\gamma\pi}{2}}\frac{\mathrm{M}}{\mathrm{Re}}\,.$$

While $\mathrm{Kn} \to 0$ is the formal requirement for a continuum flow, in practical terms gas flows for which Kn remains below a threshold value can be safely regarded as being within a continuum regime. The exact value of Kn at which rarefaction effects begin to appear remains a matter of some controversy and generally depends upon the specifics of the flow under consideration; however, $\mathrm{Kn} \sim 0.01 - 0.1$ is a representative range of values. At these and higher Kn numbers, the breakdown in the continuum assumption is first manifested at the boundaries with the appearance of velocity and (if applicable) thermal ‘slip’ wherein a discontinuity occurs between the flow and the solid boundary where they interact. Mathematically, these modified boundary conditions take the form:

$$u_{\mathrm{slip}} = \mathrm{Kn}\frac{\partial u}{\partial n} \qquad T - T_{\mathrm{wall}} = \mathrm{Kn}\frac{\partial T}{\partial n}$$

The flow within a typical converging/diverging supersonic micro-nozzle – and its plume – may span a wide range of Knudsen numbers encompassing continuum flow, highly rarefied flows and all intermediate states in between. A key determinant, however, rests with the value of the ambient back-pressure at the nozzle exit. For cases where there is very low back-pressures (e. g., low Earth orbit or space) a significant portion of the flow field may be influenced by rarefaction effects. Conversely, at more modest back-pressures (e. g., atmospheric operation) it may be that the flow field can safely be regarded as remaining within the continuum regime.

In most high-altitude or space applications, the nozzle flow will be under-expanded and the external plume will experience the greatest flow rarefaction. Depending on the circumstances, the rarefaction can be quite severe, extending beyond the slip regime and bordering on the free molecular regime. In such cases, modeling efforts require the use of gas kinetic schemes such as Direct Simulation Monte Carlo (DSMC) or even Molecular Dynamics (MD). The discussion of these methods are beyond the scope of this article and the interested reader is encouraged to refer to the classic monograph by G. Bird [4]. It is important to note that, for supersonic flow, the level of accuracy required in the modeling of the plume region is really a 'matter of interest'. For example, if the interest lies in the chemical signatures of exhaust plumes or perhaps the interaction of the plume with a spacecraft's solid surfaces, then flow rarefaction cannot be ignored. On the other hand, if thrust production by the nozzle is the key item of interest, then the specifics of the supersonic plume are of no real import.

It is possible that the supersonic portion of the micro-nozzle may also experience some degree of rarefaction, depending on the specifics of the flow. However, the extent of the rarefaction is usually minor and, if needed, can be reasonably managed by augmenting a continuum model with slip boundary conditions to yield more precise estimates of thrust production.

Micro-Nozzle Geometry

Area Ratios and Physical Nozzle Dimensions

The driving constraint of a micro-nozzle design is the target thrust level, which is determined by the nozzle exit conditions (velocity, thermodynamic state, and area) as given by Eq. (7). It is important to note that there is not a unique flow state for a specific thrust, and thus other design constraints or conditions must be imposed in order to determine a specific solution. Such considerations might include: the ambient back-pressure at the nozzle exit, the maximum allowable size of the nozzle, or the maximum mass flow rate $\dot{m}$ that the system can deliver. For micro-nozzles that are components of miniaturized propulsion systems, size may be the overriding concern and hence the exit area may provide the necessary additional constraint. Once the desired nozzle exit conditions have been identified, the nozzle area expansion ratio (A/A_*) is fixed by the area-Mach relation (3); moreover, the values of all the remaining thermodynamic variables (T/T_0, p/p_0, ρ/ρ_0) are fixed by the isentropic flow relations (4)–(6). Note that the state of the gaseous products of decomposition or combustion upstream of the nozzle inlet establishes the stagnation values T_0, p_0, and ρ_0.

As an illustrative example, the NASA/GSFC micro-nozzle described in [2] is designed to produce a thrust level in the range of 10 – 500 μN. This prototype featured a throat dimension of 90 μm and an exit area expansion ratio $A_{\text{exit}}/A_* \sim 6$ which produce an exit Mach number of ~ 3.4.

Nozzle Profile and 3D Effects

The idealized nozzle profile $A(x)$ is one which provides the required area expansion ratios for supersonic flow and, concurrently, aligns the flow in the axial direction at the nozzle exit. This flow alignment minimizes losses in thrust production associated with unwanted transverse velocity components. The traditional 'bell-shape' contoured nozzle accomplishes this task while maintaining isentropic flow conditions throughout the nozzle. Note that the profile of the isentropic bell nozzle cannot be obtained by quasi-1D theory. Rather, it is determined through the solution of expansion and compression wave propagation in the supersonic portion of the nozzle – typically this is done using the method of characteristics (e. g., [3]). While a bell-shape profile may be the ideal case, linear nozzles are also commonly used in thruster propulsion systems. A linear nozzle features a supersonic section with a fixed expansion rate $\mathrm{d}A/\mathrm{d}x$ characterized by a divergence angle θ. Linear nozzle designs are attractive primarily for their geometric simplicity and the associated advantages in the fabrication process. This has proven to be an important consideration for micro-scale fabrication of nozzles over the past decade; however, microfabrication techniques continue to improve and the likely future trend will be a return to the more efficient bell-shape nozzles.

Regardless of the profile, one key difference between micro-nozzles and their macro-scale counterparts is their inherent 3D nature. Owing to the method of microfabrication (see below) the nozzles are ducts with rectangular cross-sections. Conversely, all macro-scale nozzles are conical in nature and thus the flows are 2D aximsymmetric. The 3D nature of the flow can have substantial effects on the supersonic nozzle performance on the micro-scale.

Microfabrication Techniques

Many MEMS-based micro-nozzles are created from 2D planar patterns which are transferred to a substrate material (typically Si) via a photolithographic masking process. The nozzle is fabricated within the substrate by selectively removing the substrate material from unmasked regions; commonly this is accomplished via reactive ion etching (RIE) or 'deep' reactive ion etching techniques. Whereas the RIE method is acceptable for etching depths on the order of 10 μm, the DRIE method enables etching depths in excess of 100 μm. Chemical wet etching is also possible, but is becoming less common because of its inherent limitations compared to RIE techniques. An alternative approach, and one which is becoming more widely available, is the use of 'focused ion beams' (FIB) to mill out the pattern on the substrate. Regardless of the method, high precision is required in the fabrication process to ensure proper geometry is produced, including smooth nozzle walls. The nozzle is typically sealed by bonding a cover surface (e. g., Pyrex to provide optical access) to the substrate. Often anodic bonding is used to produce a permanent bond which can withstand a wide range of operating temperatures. To date, there has been little effort experimentally to provide for thermal insulation of the nozzle within the substrate. This may be an important area for future work given the potential significance of heat transfer during nozzle operation, as will be described later.

Key Research Findings

Steady Flow

Much of the current research is focused on examining the interaction of viscous forces and nozzle geometry in an effort to better understand and quantify performance characteristics. The majority of the research literature has dealt with 2D steady-state flow conditions. Given the experimental challenges associated with micro-scale supersonic flow interrogation, virtually all analyses have been computational in nature. While some experimental works have also been reported, most of these have reported only thrust measurements without corresponding flow field data.

Within the aerospace literature, Bayt and Breuer [5] were among the first to examine micro-nozzle flow and to identify the key role that viscous effects can play. In short, the low Reynolds numbers of these flows permit the growth of relatively thick viscous layers within the nozzle expander – these layers can occupy a significant portion of the nozzle exit, effectively restricting the flow and reducing thrust production. In an effort to mitigate the growth of viscous layers, propulsion researchers have considered increasing the expansion angle of the diverging section of the nozzle; however, as will be shown, doing so introduces geometric losses linked to increased non-axial exit velocity components.

The results that to follow are based on numerical simulations of the operation of the NASA/GSFC microthruster system described in [2]. While the data is somewhat case specific, the findings and issues that arise are germane to most micro-scale nozzles. Numerical models of monopropellant based supersonic flows have been developed for varying micro-nozzle geometries including linear and bell shaped expander sections. For the linear micro-nozzles, which will be of primary focus, expander half-angles have been examined within the range of $\theta = 10° - 50°$ (Fig. 2). For the present analysis, adiabatic nozzle walls are assumed. The supersonic flow field is characterized by Reynolds numbers typically less than 1000.



Supersonic Micro-Nozzles, Figure 2 Performance results for the NASA/GSFC supersonic microthruster nozzle with decomposed H_2O_2 and decomposed N_2H_4 as the working monopropellants. Thrust production, as shown on the left axis, has been normalized by the theoretical quasi-1D inviscid value. The percentage of the micro-nozzle exit plane occupied by the viscous subsonic layer is also shown on the right axis for both monopropellants of interest. Results are shown for expander half-angles ranging from 10° to 50°. Note that the expander angle exhibiting the maximum thrust production does not directly coincide with the minimum subsonic layer thickness. This is a direct result of the competing effects of viscous forces and micro-nozzle geometry. The optimum expander angle is the result of this trade-off

Referring to Fig. 2, a rapid and drastic reduction in thrust output is observed as the expander half-angle is increased above 30°. This is a direct consequence of expander geometry. For large expander angles, the flow follows the walls in the expander and thus a sizeable component of the velocity vector exits the nozzle in the transverse direction. This results in a significant reduction of axial momentum flux and a corresponding decline in thruster performance.

For small expander angles, transverse velocity components due to expander geometry are reduced, but at the expense of increased nozzle length in order to maintain the desired area expansion ratio. As the expander angle is decreased below 30°, viscous forces acting over the lengthened expander section begin to dominate nozzle performance. The subsonic layer acts to restrict the flow and reduce the effective exit area. Because the viscous boundary layer at the exit plane is subsonic, the ambient back-pressure conditions can communicate with the flow upstream within the nozzle expander near the walls. As a result, the flow inside the expander will respond in order to match ambient backpressure. The flow exiting the micro-nozzle is inherently underexpanded in a space environment and, as such, premature flow turning occurs via an expansion fan originating within the nozzle. Thus, a portion of the exit momentum is vectored into the transverse direction which results in a further reduction in micro-nozzle performance. These factors combine to represent a performance trade-off between viscous and geometric effects as described further in Louisos and Hitt [6].

To provide additional insight into the nature of the viscous effects, the subsonic boundary layer in the nozzle expander can be examined. Fig. 3 shows the viscous subsonic boundary layer in the 30° expander half-angle for both decomposed H_2O_2 and decomposed N_2H_4. Forming at the throat, the viscous subsonic layer grows as the axial distance progresses towards the exit. The subsonic layer thickness also scales with the fluid viscosity, as is evident for the two different monopropellants shown in Fig. 3. The steady-state subsonic layer thickness at the nozzle exit has been quantified as a function of expander half-angle in Fig. 2. As the expander angle is decreased, the subsonic layer grows to occupy a larger percentage of the nozzle exit area, up to 15% for decomposed H_2O_2 and up to 8.5% for decomposed N_2H_4. For cases of smaller expansion angles, the corresponding length of the expander increases allowing the subsonic layer to grow as the flow moves further downstream. This scenario is directly responsible for the reduction in performance of the micro-nozzle at small divergence angles. For larger expander angles, the subsonic layer thickness again increases proportionally. Here the flow is forced to turn sharply at the throat as it enters the micro-nozzle expander section. The high speed bulk flow is unable to turn efficiently and a thick subsonic layer results near the wall boundary. However, owing to the low Reynolds number regime, no flow separation is observed.

It is clear that the interplay between viscous effects and micro-nozzle geometry is complex and must be fully understood for the efficient design of high-performance MEMS-based nozzles. In summary, with the flow conditions specified for the micro-thruster nozzle, trade-offs between the size of the subsonic layer and geometric losses due to non-axial flow components result in an optimal linear expander half-angle of approximately 30° with decomposed H_2O_2 as the monopropellant. This value is significantly larger (2×) than half-angles of around 15° typically used in macro-scale conical thrusters [7]. While the N_2H_4 monopropellant thruster does not exhibit a distinct maximum thrust output corresponding to an optimal geometry, it is clear that the most effective half-angle is in the range of 25° and less.

Transient Flow

Supersonic micro-nozzles are intended to provide station keeping and attitude control for nano-sats. This is accomplished through the application of discrete impulse 'bits' resulting from the transient firing of the micro-thruster. The ability to precisely predict and control the impulse bit delivered during a firing is evidently of great importance from an operations standpoint. The thruster firing for a chemical-based system essentially involves three phases: start-up, a period of steady-state operation, and finally a shut-down sequence. Currently, typical micro-valve actuation of the propellant flow is on the order of milliseconds. Because of viscous effects on the micro-scale, the use of inviscid theory in determining flow actuation and micro-nozzle performance can lead to innaccurate predictions. This may be present in the form of 'residual' thrust and impulse resulting from the viscous impact on nozzle response. There has been little in the literature on transient operations. Here we describe results for a simulated firing of the NASA/GSFC micro-nozzle prototype.



Supersonic Micro-Nozzles, Figure 3 Visualization of the viscous subsonic boundary layer in the 30° half-angle micro-nozzle expander section as shown by Mach contours < 1.0 for both decomposed H_2O_2 (top) and decomposed N_2H_4 (bottom) at an inlet to exit pressure ratio of 10 : 1 across the micro-nozzle. Note that the size of the H_2O_2 subsonic layer is larger compared to the N_2H_4 subsonic layer owing to the fact that decomposed H_2O_2 has approximately a 38% greater viscosity over the operating temperature range within the micro-nozzle

Transient micro-nozzle simulations have been performed with divergence half angles ranging from $10-50^\circ$ with decomposed H_2O_2 as the gas.

For a typical microthruster firing, the micro-valve is initially closed and there is no flow through the nozzle. As the valve opens, a pressure gradient is established across the nozzle and the corresponding mass flow through the nozzle begins to generate thrust. Initially the pressure ratio is small and the flow at the exit is over-expanded and thus free boundary shock reflection is observed in the exhaust plume. With elapsed time the micro-valve continues to open and the pressure gradient across the nozzle increases as does thrust production. The size of the exhaust plume increases in tandem. As the micro-valve opens to its maximum position the flow transitions from over-expanded through perfectly-expanded and finally to under-expanded flow at steady-state; at this point a sizable expansion fan develops at the nozzle exit. This sequence is then repeated, in reverse order, during the shut-down process of the micro-nozzle duty cycle. The flow field evolution at selected time steps is shown in Fig. 4. A single typical thruster firing, which includes start-up, steady-state, and shut-down occurs on the order of a few milliseconds.

Numerical simulations of transient micro-nozzle flows have shown a lag in thrust production and performance response during the start-up sequence of the duty cycle [8]. For the reduced pressure gradient across the nozzle during start-up, viscous effects dominate and the flow throughout the entire expander section is subsonic. As the pressure gradient increases with time, the flow locally attains supersonic velocities in a region extending downstream from the throat, but then decelerates to subsonic speeds by the nozzle exit. This is seen in Fig. 5 which shows the extent of the viscous subsonic layer in the expander section at various times during the start-up process. As the micro-valve continues to open and larger pressure gradients are established, the flow is able to overcome viscous forces and establish wide-spread supersonic conditions in the expander section.

A finite time 'lag' is observed during the start-up which results from viscous effects. The lag in thrust production during start-up is most pronounced in the 10° and 50° expander half-angles owing to the fact that these geometries feature for the largest subsonic layers. It is interesting to note that the flow does *not* exhibit a lag in response to micro-valve closure during the shut-down sequence of the micro-nozzle [8]. Owing to the fact that viscous effects tend to reduce flow through frictional forces, the shut-down process is in fact facilitated by the existence of the subsonic layer. As the pressure ratio across the micro-nozzle is reduced during shut-down, the subsonic layer grows into the bulk of the flow field and thus promotes the reduction of thrust output. In this sense, viscous forces aid the shut-down sequence through dissipation.



Supersonic Micro-Nozzles, Figure 4 The evolution in time of the micro-nozzle flow field as shown by Mach number contours for the 30° expander half-angle during transient operation of the microthruster. As the pressure ratio across the micro-nozzle increases during start-up, the exhaust plume grows in size and the flow transitions from over-expanded through perfectly expanded flow to under-expanded conditions. A typical microthruster firing is on the order of milli-seconds and the simulation depicted here has a total actuation time of 1.7 ms. The results normalized by the actuation time are characterized as follows; (**a**) $t^* = 0.16$ over-expanded start-up, (**b**) $t^* = 0.176$ over-expanded start-up, (**c**) $t^* = 0.188$ perfectly expanded start-up flow, (**d**) $t^* = 0.206$ under-expanded start-up, (**e**) $t^* = 0.5$ steady-state under-expanded, and (**f**) $t^* = 0.82$ over-expanded shut-down flow. As expected, free boundary shock reflection occurs in the case of over-expanded flow while an expansion fan can be seen near the exit of the micro-nozzle for under-expanded flow

The transient results can be summarized by examining the total impulse over one duty cycle for a single micro-nozzle



Supersonic Micro-Nozzles, Figure 5 Shown in the figure are transient sonic lines ($M = 1$) which indicate the maximum extent of the viscous subsonic layers from the micro-nozzle wall during the start-up sequence of the micro-nozzle. The time t has been normalized by the total actuation cycle time of 1.7 ms. Note that for $t < 0.082$ the flow is initially supersonic in the vicinity of the throat before viscous forces impede the flow and thus cause it to revert back to entirely subsonic conditions at the nozzle exit



Supersonic Micro-Nozzles, Figure 6 A plot of the total impulse generated during a single actuation cycle for a range of expander half-angles as compared to quasi-one-dimensional inviscid theory. Maximum total impulse occurs at a micro-nozzle half-angle of 30°. For expander half-angles $< 30°$, viscous effects are responsible for the reduction in performance while at larger expander angles, performance decreases as a result of significant transverse velocity components at the micro-nozzle exit. The bell contoured expander here initially has a 30° half-angle in the vicinity of the throat and the contoured walls align the flow along the nozzle axis. As anticipated, the contoured expander outperforms the linear nozzle owing to the straightening of the flow and lack of transverse velocity associated with the bell profile

firing. The results are shown in Fig. 6; also shown are the results from quasi-1D inviscid theory for comparison purposes. As expected, the total impulse from the simulations is less than that predicted by inviscid theory – this difference can be directly attributed to the integrated effect of viscous and geometrical losses incurred during the transient process. The 'optimal' angle for a linear micro-nozzle in the transient case is seen to be the same as for the steady-state operation.

Heat Transfer Effects

Micro-nozzles are typically fabricated into much larger, thermally-conducting substrates. In an operational setting, these substrates will be thermally linked with the remainder of the spacecraft and will experience major temperature variations over a single orbit due to alternating day/night conditions. It is thus expected that significant heat transfer is possible between the micro-nozzle and the substrate and, in turn, may impact the flow. As a first approximation, one may argue that the substrate can be regarded as a thermal sink (or source) of constant temperature for the nozzle flow. This argument is based on a comparison of the relative thermal masses of the flow and a typical substrate; indeed, a lumped capacitance analysis of the NASA/GSFC micro-nozzle indicates that only a 5% temperature increase would be realized within the substrate under a typical firing sequence involving a 'cold' nozzle.

From a modeling perspective, then, a reasonable first-approximation of heat transfer effects is the imposition of isothermal boundary conditions on the micro-nozzle walls. The particular wall temperature would reflect the thermal state of the spacecraft as a whole based on its orbital location with respect to the Sun. To demonstrate the effect of heat transfer, we present findings obtained from numerical simulations of the NASA/GSFC linear micro-nozzle for expansion angles of 15° and 30° and isothermal wall temperatures ranging from 50 K to 1000 K. The thrust production (normalized with respect to quasi-1D inviscid theory) as a function of isothermal wall temperature is shown in Fig. 7. For comparison, the adiabatic results are also given. Cases with heat loss are seen to outperform comparable simulations with adiabatic walls. From a performance standpoint, as the wall temperature is increased the thrust output decreases and the subsonic layer grows non-linearly. A large subsonic layer has already been shown to greatly reduce micro-nozzle performance.

The observed effects of heat transfer on the flow in micro-nozzles is readily explained as follows. From compressible *Rayleigh flow* it is known that removing heat from a supersonic flow acts to accelerate the flow. At steady-state, the bulk of the flow in the micro-nozzle expander is super-



Supersonic Micro-Nozzles, Figure 7 Steady-state micro-nozzle performance including heat transfer through an isothermal wall. A reduced wall temperature is used to model heat losses from the flow field into the silicon micro-nozzle substrate acting as a thermal sink. As heat is removed from the expander, the supersonic flow is further accelerated, subsonic layer size is reduced, and performance as measured by thrust output increases. Note that the adiabatic results nearly coincide with the 900 K isothermal wall values as indicated

sonic and thus heat transfer acts to further accelerate the supersonic flow. Concurrently, as the flow is cooled, the exit density ρ increases. The overall effect is an increase in thrust. Heat extraction from the flow into the substrate increases performance from the subsonic layer point of view as well. For low nozzle wall temperatures, the local sonic velocity is diminished and the near-wall Mach number increases. This phenomena is the force driving the reduction in subsonic layer size for micro-nozzle flows with heat removal. In fact, with sufficient heat extraction from the flow, the subsonic layer can be reduced to the point where the competing effects of viscous forces and nozzle geometry cause the optimum expander half-angle to be shifted from 30° to a more traditional expander half-angle of 15°. This is demonstrated in Fig. 7 for isothermal wall temperatures less than ~ 700 K.

Non-Continuum Effects

Alexeenko et al. [9, 10] have performed non-continuum Direct Simulation Monte Carlo (DSMC) analyses of milli-/micro-nozzle flows in order to examine the influence of rarefaction effects on performance. The DSMC method is a statistical approach to the solution of the Boltzmann equation, the governing equation for rarefied gasdynamics. Their work has found that for Knudsen numbers of $\mathrm{Kn} \sim 0.1$, gas-surface interactions have a strong influence on the flow in both the converging and diverging sections of the nozzle. Owing to the fabrication process of MEMS devices, the surfaces have a significant degree of roughness at the molecular scale and thus result in inelastic diffusive collisons of a molecule with the surface. As such, a large portion of the flow remains subsonic along the nozzle expander walls. This causes an overall reduced Mach number at the nozzle exit and decreased thrust production. Comparisons have also been made between predicted velocity fields obtained by DSMC and Navier–Stokes continuum models for a supersonic converging-diverging micro-nozzle [9]. It was observed that the two solutions exhibit strong agreement within the micro-nozzle and that differences between the two methods were confined to the vicinity of the exhaust plume, specifically the corners of the nozzle exit. This is due to the rapid expansion of the gas and high flow rarefaction that is difficult to capture by continuum methods. Minor differences were reported in the size of the subsonic layers in the expander section owing to the difference in the wall boundary conditions (i. e., no-slip vs. slip). However, comparison of the velocity distributions along the nozzle centerline region shows only a small difference between the two methods.

Rarefied analyses of thermal coupling between the micro-nozzle with the surrounding substrate have also been reported [10]. In this work, steady low Reynolds number gas flows were again modeled by the DSMC approach and the substrate transient thermal response was governed by the heat conduction equation. It was shown that propulsive efficiencies of the micro-nozzle decreased with higher nozzle wall temperatures and vice versa. These results are in agreement with the continuum-based heat transfer results previously discussed.

Future Directions for Research

We close this article with a brief discussion concerning future research opportunities and needs for supersonic micro-nozzle flow within the context of micro-propulsion applications. In some instances preliminary work has been reported in various forms within the aerospace literature, however comprehensive and detailed studies have not yet appeared.

Conjugate Heat Transfer in Prototype Devices

As described previously, heat transfer from the micro-nozzle to its surroundings can have a significant impact on the supersonic flow within. Most of the studies to date, however, have been based on models featuring simplified and somewhat artificial thermal boundary conditions rather than a full conjugate heat transfer analysis with the domain surrounding the micro-nozzle. This shortcoming is a consequence of incomplete knowledge of actual nano-sat propulsion system configurations, geometries and operating conditions. As experimental prototype nanosats and propulsion systems begin to appear in greater numbers – and the design configurations and typical operating conditions start to take shape – more detailed heat transfer analyses will be warranted. Indeed, the solution of the conjugate heat transfer problem will be an important part in future design optimization process for supersonic micro-nozzles.

Three-Dimensional Geometric Effects

Much of the modeling efforts to date have focused on 2D planar geometries, owing largely to the 2D nature of patterning associated MEMS-based fabrication procedures. To a lesser degree, 2D modeling has also been invoked as a simplification to reduce computational resources required for numerical simulations. In reality, MEMS-based supersonic nozzles will have rectangular cross sections as a result of reactive ion etching or milling performed in the fabrication process. Further, the depth dimension may be substantially smaller than the nozzle width at the exit plane. One could posit that viscous boundary layer growth from the upper and lower boundaries of the nozzle will be of equal, if not greater, significance than the boundary layers studied in the 2D simulations. The presence of the upper and the lower boundaries also provides substantial, additional surface areas for heat loss from the nozzle flow and thus the consequences may well be more severe than those previously discussed in 2D models. In all, it is clear that there is a very real need for the pursuit of 3D models for the supersonic micro-nozzle flow. It is, however, also important to note that the additional computational resources required for full 3D simulations will be significant, particularly in cases of transient flows and flows with rarefaction.

Multiphase Flow

One unique aspect of supersonic micro-nozzles is the potential for the occurrence of multiphase flow, particularly in the expansion section. There are two primary mechanisms by which a liquid phase could be present within the flow. The first scenario would involve sufficiently high levels of heat loss through the nozzle walls resulting in gas condensation near the solid boundaries; this situation would most likely occur in the supersonic expansion section of the nozzle. The probable impact of condensation would be a reduction in thrust and micro-nozzle performance. A second scenario involves a multi-phase inlet that could be the result, for example, of incomplete chemical decomposition (catalysis) of a monopropellant or incomplete combustion of bipropellants upstream of the nozzle (e. g., Hitt et al. [2]). Such problems could arise in chemical monopropulsion, for example, over time with degradation/fouling of catalysts in micro-reactors. In this case, the multiphase subsonic flow would likely affect the critical conditions required for sonic conditions to occur at the nozzle throat. Regardless of the particular scenario, there is a definite need for modeling efforts in this area – be it analytical, computational or both – to provide predictive capabilities for micro-nozzles under these multiphasic conditions.

Rarefaction Effects for Realistic Gases

Much of the micro-nozzle literature dealing with rarefied flows has focused on so-called ‘cold gas’ propulsion mechanisms. A cold-gas system features a single, inert gas (typically N_2) as a propellant and, consequently, offers a great modeling simplification for gas kinetic simulations utilizing DSMC or MD approaches. The fact that all molecules are identical within the flow simplifies the treatment of molecular collisions; in contrast, for multi-gas flows the treatment of collisions between molecules of different sizes and number densities becomes considerably more complicated. In practice, many propulsion schemes feature gas mixtures (e. g., decomposed H_2O_2 or decomposed N_2H_4 monopropellant schemes) and as such, there remains a significant void in the micro-nozzle literature concerning the effects of flow rarefaction in these cases.

Cross References

- ► Microfabrication Techniques
- ► Microrockets
- ► Reactive Ion Etching (RIE)

References

1. Mueller J (2000) Thruster options for microspacecraft: a review and evaluation of the state-of-the art and emerging technologies. In: Micci M, Ketsdever A (eds) Micropropulsion for Small Spacecraft – Progress in Astronautics and Aeronautics, vol 187. AIAA, Reston, VA
2. Hitt DL, Zakrzwski CM, Thomas MK (2001) MEMS-Based Satellite Micropropulsion Via Catalyzed Hydrogen Peroxide Decomposition. J Smart Mater Struct 10:1163–1175
3. Anderson JD (2003) Modern Compressible Flow with Historical Perspective, 3rd edn. McGraw–Hill, Boston, MA
4. Bird GA (1994) Molecular Gas Dynamics and the Direct Simulation of Gas Flows. Oxford University Press, Oxford
5. Bayt RL, Breuer KS (2001) System design and performance of hot and cold supersonic micro-jets. AIAA Paper 2001–0721
6. Louisos WF, Hitt DL (2005) Optimal Expander Angle for Viscous Supersonic Flow in 2-D Micro-Nozzles. AIAA Paper 2005–5032

7. Humble RW, Henry GN, Larson WJ (1995) Space Propulsion Analysis and Design. McGraw–Hill, New York
8. Louisos WF, Hitt DL (2006) Viscous Effects in Supersonic Micro-Nozzle Flows: Transient Analysis. AIAA Paper 2006–2874
9. Alexeenko AA, Levin DA, Gimelshein SF, Collins RJ (2002) Numerical Modeling of Axisymmetric and Three-Dimensional Flows in Microelectromechanical systems. AIAA J 40(5):897–904
10. Alexeenko AA, Levin DA, Fedosov DA, Gimelshein SF (2005) Performance Analysis of Microthrusters Based on Coupled Thermal-Fluid Modeling and Simulation. J Propuls Power 21(1):95–101

Surface Acoustic Waves

- ► Flow by Surface Acoustic Waves
- ► Transport of Droplets by Acoustics

Surface Capturing

- ► Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking

Surface Change

- ► Surface Modification, Methods

Surface-Charge Patterning Techniques

Winky L. W. Hau
IMTEK, University of Freiburg, Freiburg, Germany
winky.hau@imtek.de

Synonyms

Surface chemistry technique; Polyelectrolyte patterning technique; Electro-osmosis with patterned surface charge

Definition

The surface-charge patterning technique is a surface chemistry process to make both positively charged and negatively charged patterns on a glass/silicon dioxide surface.

Overview

In microfluidic systems, liquid flow control is very challenging because of the large flow resistance. As such, electro-osmotic flow (EOF), a surface-driven flow phenomenon, is an alternative to pressure-driven flow (PDF), in order to overcome the flow resistance problem. Since the velocity of EOF depends on the surface charge of the channel wall, the surface-charge patterning technique has thus been developed to control liquid flow in a very confined space.



Surface-Charge Patterning Techniques, Figure 1 (**a**) Schematic chemical structure of a glass (or silicon dioxide) surface. (**b**) Glass surface carries negative charges in contact with aqueous solution

Surface Chemistry

Glass (or silicon dioxide) naturally carries negative charges on its surface. When a glass surface is in contact with an aqueous solution, ionization occurs in the surface chemical group [1], leaving the chemical group with negative charges (Fig. 1). However, the surface charge density of such a natural process is low.

The surface-charge patterning technique can be considered as a two-step process. Firstly, the negative charges on the glass surface are enhanced by chemical processing with alkali and acid. The purpose is not only to make a negatively charged surface but also to prepare for the second step. In the second step, part of the glass surface, i. e. the pre-designed pattern, is masked by a very thin polymer coating or polymer structure. Then the whole glass surface is submerged in or flooded with a positively charged polymer solution called a polyelectrolyte. Owing to the glass surface and the polyelectrolyte having opposite charges, the polyelectrolyte is bound to the glass surface by electrostatic force, forming a thin polymer coating of the order of nanometers in thickness, as illustrated in Fig. 2. This binding process is termed an electrostatic self-assembly (ESA) process [2].

The positively charged patterning process in the second step can be accomplished by soft-lithography or photolithography. There exist several variations in soft-lithography but the principles are the same – to mask the pre-designed pattern on the glass surface [3, 4]. To illustrate the general idea, one soft-lithography technique which makes use of molding is presented, followed by a discussion of the photolithography technique.



Surface-Charge Patterning Techniques, Figure 2 Electrostatic self-assembly (ESA) process. (**a**) A glass substrate with negative charges on its surface is submerged in a positively charged polymer solution. (**b**) The polymer binds to the glass surface due to electrostatic attraction



Surface-Charge Patterning Techniques, Figure 3 Schematics of the setup for micromolding that creates polymer surface-charge pattern on a glass surface

Soft-Lithography with Micromolding

The mold used is made of a thin polydimethylsiloxane (PDMS) membrane attached to a rigid plate of glass as shown in Fig. 3 [4]. The plate has holes to introduce the polymer solution and to connect to vacuum. The valve to vacuum is closed while the polymer solution is applied at several inlets. The ESA process takes place on the glass surface when the capillaries are filled with the polymer solution. Finally, the vacuum is released and the mold is removed. As a result, a polymer which has the same pattern as the mold is obtained.

Photolithography with Lift-Off

Photolithography is a standard patterning technique in the fabrication process of integrated circuits (ICs) in the semiconductor industry. In fact, many silicon-based microfluidic devices are fabricated by photolithography. Photolithography is combined with the lift-off technique to make surface-charge patterns [5]. A photoresist (PR), a UV-curable polymer used in photolithography, is patterned on a glass substrate which is submerged in a polymer solution, as shown in Fig. 4a. The ESA process takes place (Fig. 4b). The unnecessary polymer is lifted off by removing the PR underneath. Finally, a pre-designed pattern containing both positive and negative charges is obtained.

Application in Microfluidics

The surface-charge patterning technique combined with EOF is, in principle, able to create numerous flow patterns



Surface-Charge Patterning Techniques, Figure 4 Schematics of surface-charge patterning by the photolithography method. (**a**) A glass substrate with patterned photoresist is submerged in a polymer solution. (**b**) ESA takes place. (**c**) The unnecessary polymer is lifted off by removing the photoresist underneath, leaving the desired surface-charge pattern



Surface-Charge Patterning Techniques, Figure 5 (**a**) Schematic plan view of longitudinal (i. e. parallel to the electric field set up by the electrodes at both ends) surface-charge patterns in a microchannel which generates bi-directional shear flow. (**b**) A cross-section A–A' of the microchannel showing symmetric patterns on top and bottom of the channel walls



Surface-Charge Patterning Techniques, Figure 6 (**a**) Schematic plan view of transverse (i. e. perpendicular to the electric field set up by the electrodes at both ends) surface charge patterns in a microchannel which generates out-of-plane vortices. (**b**) A cross-section B–B' of the microchannel showing asymmetric patterns on top and bottom of the channel walls



Surface-Charge Patterning Techniques, Figure 7 (**a**) Schematic plan view of chessboard-like surface charge patterns in a microchannel which generates in-plane vortices. (**b**) A cross-section C–C' of the microchannel showing symmetric patterns on top and bottom of the channel walls

at the microscale. In experiments, several simple flow patterns have been demonstrated, namely bi-directional shear flow (Fig. 5) [5, 6], out-of-plane vortex (Fig. 6) [6, 7] and in-plane vortex (Fig. 7) [8]. These basic flows are studied so that more complex flows can be understood and designed. A promising application is continuous mixing between two liquids or particle-laden liquids because liquid flow at the microscale is always laminar which does not favor mixing. It has already been demonstrated that the mixing efficiency can be significantly enhanced by EOF in a surface-charge patterned microchannel [9, 10].

Cross References

- ▶ Electroosmotic Flow (DC)
- ▶ AC Electro-Osmotic Flow
- ▶ Liquid–Liquid Stratified Flow in Microchannels
- ▶ Photolithography
- ▶ Photoresist SU-8
- ▶ Photoresist Reflow
- ▶ Self-Assembly Fabrication

References

1. Hunter RJ (2001) Foundations of Colloid Science. Oxford Univ Press, New York
2. Whitesides GM, Grzybowski B (2002) Self-Assembly at All Scales. Science 295(5564):2418
3. Liu Y, Fanguy JC, Bledsoe JM, Henry CS (2000) Dynamic Coating Using Polyelectrolyte Multilayers for Chemical Control of Electroosmotic Flow in Capillary Electrophoresis Microchips. Anal Chem 72(24):5939–5944
4. Jeon NL, Choi IS, Xu B, Whitesides GM (1999) Large-Area Patterning by Vacuum-Assisted Micromolding, Adv Mater 11(11):946–950
5. Hau WLW, Trau DW, Sucher NJ, Wong M, Zohar Y (2003) Surface-chemistry technology for microfluidics, J Micromech Microeng 13:272–278

6. Stroock AD, Weck M, Chiu DT, Huck WTS, Kenis PJA, Ismagilov RF, Whitesides GM (2000) Patterning Electro-osmotic Flow with Patterned Surface Charge, Phys Rev Lett 84(15):3314–3317
7. Hau WLW, Trau DW, Sucher NJ, Wong M, Zohar Y (2002) Micro flow patterns on demand using surface-chemistry technology. In: Proceeding of MEMS 2002, Las Vegas, NV, 20–24 Jan 2002
8. Lee LM, Hau WLW, Lee YK, Zohar (2006) In-plane vortex flow in microchannels generated by electroosmosis with patterned surface charge. J Micromech Microeng 16(1):17–26
9. Biddiss E, Erickson D, Li D (2004) Heterogeneous Surface Charge Enhanced Micromixing for Electrokinetic Flows. Anal Chem 76:3208–3213
10. Hau WLW, Leung PK, Lee LM, Lee YK, Zohar Y (2005) Electrokinetically-Driven Micro Mixer with a Novel Surface-Charge Pattern. In: Proc IEEE Robio 2005, Hong Kong, Macau, 29 Jun–3 Jul 2005

Surface Chemistry Technique

- ► Surface-Charge Patterning Techniques

Surface Conductance

- ► Surface Conductivity
- ► Surface Conductivity Measurement

Surface Conductivity

Synonyms

Surface conductance; Surface electric conductance

Definition

The surface conduction is the excess electric conduction tangential to a charged surface, and originates from the excess counterions' concentrations in the electrical double layer region near the solid-liquid interface. The corresponding electric conductivity is called the surface conductivity, λ_S, that is considered as the electric conductivity of a sheet of material of negligible thickness, with a unit $\Omega^{-1}m^{-1}$. Specific surface conductivity values are of the order $10^{-9} \sim 10^{-8}$ for water in glass capillaries.

Cross References

- ► Electrical Double Layers
- ► Zeta Potential Measurements
- ► Electroosmotic Flow (DC)
- ► Streaming Current and Electroviscosity
- ► Surface Conductivity Measurement

Surface Conductivity Measurement

DONGQING LI
Department of Mechanical Engineering,
Vanderbilt University, Nashville, TN, USA
dongqing.li@vanderbilt.edu

Synonyms

Surface conductance; Surface electric conductance

Definition

The surface conduction is the excess electric conduction tangential to a charged surface, and originates from the excess counterions' concentrations in the electrical double layer region near the solid-liquid interface. The corresponding electric conductivity is called the ►surface conductivity, λ_S, that is considered as the electric conductivity of a sheet of material of negligible thickness, with a unit $\Omega^{-1}m^{-1}$. Specific surface conductivity values are of the order $10^{-9} \sim 10^{-8}$ for water in glass capillaries.

Overview

Generally, surface conductivity usually is referred to the electrical conductivity through a thin liquid layer near the solid-liquid interface where there is a net charge accumulation due to the charged solid-liquid interface. Zeta potential is considered as an electrokinetic potential at the shear plane near a solid-liquid interface where the liquid velocity is zero. The zeta potential and the surface conductivity are very important interfacial electrokinetic properties to a huge number of natural phenomena, such as electrode kinetics, electrocatalysis, corrosion, adsorption, crystal growth, colloid stability and flow characteristics of colloidal suspensions and electrolyte solutions through porous media and microchannels. In electro-osmotic flow or pressure-driven flow through fine capillary tubes, the zeta potential and the surface conduction will critically influence the velocity or flow rate. In many cases, knowing the surface conductivity is a must in order to evaluate the zeta potential and other electrokinetic properties correctly. Measurement of the surface conductivity, therefore, is important in the studies of electrokinetic phenomena. Two methods to measure the surface conductivity, one involving pressure-driven flow, and the other electroosmotic flow, will be reviewed in this entry.

It is well-known that most solid surfaces carry electrostatic charges, i. e. an electrical surface potential. If the liquid contains a certain amount of ions (for instance, an electrolyte solution or a liquid with impurities), the electrostatic charges on the solid surface will attract the counterions in the liquid. The rearrangement of the charges on the solid surface and the balancing charges in the liquid is called the electrical double layer (EDL) [1–3]. Immediately next to the solid surface, there is a layer of ions which are strongly attracted to the solid surface and are immobile. This layer is called the compact layer, normally about several Angstroms thick. From the compact layer to the uniform bulk liquid, the net charge density gradually reduces to zero. Ions in this region are affected less by the electrostatic interaction and are mobile. This region is called the diffuse layer of the EDL. The thickness of the diffuse layer is dependent on the bulk ionic concentration and electrical properties of the liquid, usually ranging from several nanometers for high ionic concentration solutions up to several microns for pure water and pure organic liquids. The boundary between the compact layer and the diffuse layer is usually referred to as the shear plane. The electrical potential at the solid-liquid surface is difficult to measure directly. The electrical potential at the shear plane is called the zeta potential, ς, and can be measured experimentally [1–3]. In practice, the zeta potential is used as an approximation to the potential at the solid-liquid interface. The ion and electrical potential distributions in the electrical double layer can be determined by solving the Poisson–Boltzmann equation [1–3]. According to the theory of electrostatics, the relationship between the electrical potential ψ and the local net charge density per unit volume ρ_e at any point in the solution is described by the Poisson equation:

$$\nabla^2\psi = -\frac{\rho_\mathrm{e}}{\varepsilon} \tag{1}$$

where ε is the dielectric constant of the solution. Assuming the equilibrium Boltzmann distribution equation is applicable, which implies uniform dielectric constant, the number concentration of the type-i ion in a symmetric electrolyte solution is of the form

$$n_\mathrm{i} = n_\mathrm{io}\exp\left(-\frac{z_\mathrm{i}e\psi}{k_\mathrm{B}T}\right) \tag{2}$$

where n_io and z_i are the bulk ionic concentration and the valence of type-i ions, respectively, e is the charge of a proton, k_B is the Boltzmann constant, and T is the absolute temperature. The net volume charge density ρ_e is proportional to the concentration difference between symmetric cations and anions, via.

$$\rho_\mathrm{e} = ze(n_+ - n_-) = -2zen_\mathrm{o}\sinh\left(\frac{ze\psi}{k_\mathrm{B}T}\right) \tag{3}$$

Substituting Eq. (3) into the Poisson equation leads to the well-known Poisson–Boltzmann equation.

$$\nabla^2\psi = \frac{2zen_\mathrm{o}}{\varepsilon}\sinh\left(\frac{ze\psi}{k_\mathrm{B}T}\right) \tag{4}$$

When a liquid is forced through a capillary under an applied hydrostatic pressure, the ions in the diffuse layer (mobile part) of the EDL are carried towards the downstream end, resulting in an electrical current in the pressure-driven flow direction. This current due to the transport of charges by the liquid flow is called the streaming current. Corresponding to this streaming current, there is an electrokinetic potential called the streaming potential. This flow induced streaming potential is a potential difference that builds up along the capillary. This streaming potential acts to drive the ions in the diffuse layer of the EDL to move in the direction opposite to the streaming current, i. e., opposite to the pressure-driven flow direction. The action of the streaming potential will generate an electrical current called the conduction current. The conduction current will produce a liquid flow in the opposite direction to the pressure driven flow. The overall result is a reduced flow rate in the pressure drop direction.

The zeta potential can be determined from the measured pressure drop and the measured streaming potential along a single capillary tube. In absence of an applied electric field, when a liquid is forced through a channel under hydrostatic pressure, the excess counter-ions in the diffuse layer of the EDL are carried by the liquid to flow to the downstream, forming an electrical current, i. e., the streaming current. The streaming current is given by

$$I_\mathrm{s} = \int_{A_\mathrm{c}} v\rho_\mathrm{e}\,\mathrm{d}A_\mathrm{c} \tag{5}$$

where A_c is the cross-section of the capillary, v is the local velocity of the liquid, and ρ_e is the local net charge density. For a liquid flowing through a cylindrical capillary tube of radius R at a steady state, the liquid local velocity $v(r)$ is given by the solution of the Poiseuille equation:

$$v(r) = \frac{\Delta P\left(R^2 - r^2\right)}{4\eta L} \tag{6}$$

where r is the radial variable measured from the central of the capillary, ΔP is the pressure drop along the capillary, η is the viscosity of the liquid, and L is the length of the capillary. The local net charge density $\rho_\mathrm{e}(r)$ in Eq. (5) can be replaced by the Poisson equation, Eq. (1). Realizing that local net charge density $\rho_\mathrm{e}(r)$ is not zero only in the EDL, i. e., only in a thin region near the channel wall, and that the EDL potential at the channel wall is approximated to be the zeta potential ς, one can show that the streaming current is given by:

$$I_s = -\frac{\varepsilon\varsigma}{\eta}\pi R^2 \frac{\Delta P}{L} \tag{7}$$

As explained above, the streaming potential generates a conduction current in the reversed direction. For a cylindrical capillary, the conduction current is given by:

$$I_c = \frac{\pi R^2 \lambda_b E_s}{L} \tag{8}$$

where λ_b is the bulk liquid electrical conductivity, and E_s is the streaming potential. At a steady state, the net electrical current should be zero, i.e., $I_s + I_c = 0$. Using this condition, one obtains the following:

$$\frac{E_s}{\Delta P} = \frac{\varepsilon\varsigma}{\eta\lambda_b} \tag{9}$$

As seen from Eq. (9), by measuring the streaming potential and the pressure drop, and knowing the liquid properties, the zeta potential can be determined.

Generally, for a given solid-liquid system at a given temperature, the zeta potential is considered as a constant, this is because the nature of the material, its surface charge, and the nature and the concentration of the electrolyte determine the electrokinetic potential. However, early studies found that zeta potential determined from Eq. (9) depends on the size of the capillary tubes for the same solid material (the capillary wall) and the same liquid (with the same electrolyte concentration). This problem was solved later by considering the surface conduction, i.e., the electrical conduction through a thin layer at solid-liquid interface. Generally, the surface conduction is the excess conduction tangential to a charged surface, and originates from the excess counterions' concentrations in the EDL region near the solid-liquid interface [4]. Particularly in the cases of low bulk ionic concentrations, the surface conduction will have a significant contribution to the total conduction current through the capillary tube. Usually, the surface conductivity, λ_s, is considered as the conductivity of a sheet of material of negligible thickness, with a unit $\Omega^{-1}\text{m}^{-1}$. Specific surface conductivity values are of the order $10^{-9} \sim 10^{-8}\Omega^{-1}\text{m}^{-1}$ for water in glass capillaries. The surface conductivity is expected to have a significant effect on the zeta potential in capillaries smaller than 1 mm in diameter at concentrations below 1×10^{-3} M.

Briggs [5] suggested a simple procedure to correct Eq. (9). This method requires the measurement of the actual electrical resistance of the liquid in the capillary, R_{exp}, and the comparison of this value with calculated electrical resistance at high concentration, R_{cal}, where the surface conduction is expected to be negligible. The modified Eq. (9) becomes:

$$\frac{E_s}{\Delta P} = \frac{\varepsilon\varsigma}{\eta\lambda_b}\frac{R_{\text{exp}}}{R_{\text{cal}}} \tag{10}$$

Briggs' method does not give explicit information on surface conduction. Two modern methods of determining the zeta potential and the surface conductivity will be summarized below.

Basic Methodology

Streaming Potential Method

Theory

Rutgers [6] was first to rigorously consider the *surface conductance* effect on the zeta potential and solved the problem of zeta potential dependence on capillary size. By considering the *surface conductance*, the conduction current for a cylindrical capillary is given by:

$$I_c = \frac{\pi R^2 E_s \lambda_b}{L} + \frac{2\pi R E_s \lambda_s}{L} \tag{11}$$

In the above equation, the first term accounts for the conduction through bulk liquid, and the second term accounts for the surface conduction. Using Eq. (7) and Eq. (11), and the steady state condition, $I_s + I_c = 0$, we have:

$$\frac{E_s}{\Delta P} = \frac{\varepsilon\varsigma}{\eta(\lambda_b + 2\lambda_s/R)} \tag{12}$$

Realize $\varepsilon = \varepsilon_r\varepsilon_0$, where ε_r and ε_0 are the dielectric constant of the liquid and the permittivity of vacuum, respectively, the above equation can be rearranged into the following form:

$$\frac{\varepsilon_r\varepsilon_0\Delta P}{\eta\lambda_b E_s} = \frac{1}{\varsigma} + \left(\frac{2\lambda_s}{\varsigma\lambda_b}\right)\frac{1}{R} \tag{13}$$

For a given solid-liquid system, ε_r, η, λ_b, and ζ are constant. Equation (13) clearly shows that the term $\varepsilon_r\varepsilon_0\Delta P/\eta\lambda_b E_s$ is a linear function of $1/R$. If we plot $\varepsilon_r\varepsilon_0\Delta P/\eta\lambda_b E_s$ vs. $1/R$, as shown in Fig. 1, the intersection of the line given by Eq. (13) with the vertical axis is $1/\varsigma$, and the slope of this line is $(2\lambda_s/\varsigma\lambda_b)$. This implies that if one measures the pressure drop and the streaming potential of the same solid (capillary wall)-liquid system for different capillary radii, and plot the data according to Eq. (13), the zeta potential ζ and the surface conductivity λ_s can be determined from the intercept and the slope of the line.



Surface Conductivity Measurement, Figure 1 The linear relationship of $\varepsilon_r\varepsilon_0\Delta P/\eta\lambda_b E_s$ versus $1/h$ for a slit capillary (or $1/R$ for a cylindrical capillary) by using Eq. (14) (or Eq. (13)) to determine the Zeta potential and the surface conductivity by the streaming potential method

In additional to cylindrical capillary tubes, another type of capillary with a simple cross-section shape is the slit capillary, i. e., a channel formed between two parallel plates. For an electrolyte solution flowing through a slit capillary, it can be shown that, in analogy to Eq. (13),

$$\frac{\varepsilon_r\varepsilon_0\Delta P}{\eta\lambda_b E_s} = \frac{1}{\varsigma} + \left(\frac{2\lambda_s}{\varsigma\lambda_b}\right)\frac{1}{h} \tag{14}$$

where h is the height of the slit channel.

Experimental

The key in the streaming potential method is to measure the streaming potential and pressure drop of the same solid-liquid system for different capillary radii. Figure 2 illustrates an experimental setup for such measurements [3, 7]. The capillary used in the test may be a single capillary tube or a bundle of capillary tubes of the same dimensions, or a slit channel formed between two parallel plates. The capillary tube is placed in a two-part symmetrical Plexiglas assembly to form a test cell as shown in Fig. 2. For a given capillary tube and a given electrolyte solution, the precision pump is set to maintain a constant flow rate. The pressure drop across the capillary tube is monitored and recorded by a differential pressure transducer (±0.5% FS accuracy, Validyne Eng. Corp.) and a computer data acquisition system. The flow was considered to have reached a steady state when the readings of the pressure drop do not change any more. Such a constant pressure drop value corresponds to the ΔP in Eq. (13) or (14). At this steady state, two electrodes (e. g., Ag/AgCl electrodes, Sensortechnik Meinsberg GmbH) and a high resistance electrometer (Keithley Instruments Inc.) are used to measure the streaming potential. The streaming potential measured at this steady state corresponds to the E_s in Eq. (13) or (14). It should be emphasized that such a streaming potential measurement should not last more than 60 or 100 s (depending on the electrolyte concentration and the flow rate) to avoid the polarization of the electrodes. In addition to the problem of electrode polarization, it should also be noted that there are no two identical electrodes due to the material and the manufacturing process. Therefore, in order to obtain more reliable and repeatable results, under the same flow rate, the flow is switched in an opposite direction after the previous streaming potential measurement. When the flow reaches the steady state again, the above described pressure drop and streaming potential measurement are repeated. Usually, for one flow rate, the operation described above should be repeated several times to ensure the repeatability and good average values of the pressure drop and the streaming potential. It is recommended to repeat the above measurements for several different flow rates.



Surface Conductivity Measurement, Figure 2 Schematic of an experimental setup used for measurements of the streaming potential and the pressure across a capillary tube or a microchannel

As explained previously, in order to determine the zeta potential and the surface conductivity by using Eq. (13) or (14), one must measure the pressure drop and the streaming potential of the same solid-liquid pair for different capillary sizes. Therefore, the above-described measurements should be conducted for cylindrical capillary tubes with different radii or slit channels with different heights. Finally, by plotting $\varepsilon_r\varepsilon_0\Delta P/\eta\lambda_b E_s$ vs. $1/R$ (or $1/h$) as illustrated in Fig. 1, one can determine the zeta potential and the surface conductivity from the intercept and the slope of the best-fitted line to the experimental data points.

As an example, the results of glass surface-NaCl solution systems are re-plotted here [7] in Figs. 3 and 4. The measurements were done by using a slit channel formed by



Surface Conductivity Measurement, Figure 3 Experimental data for glass surface with (**a**) De-ionized Ultra-filtered water, and (**b**) 10^{-3} M aqueous NaCl solution

two parallel glass plates separated by two strips of a plastic shim of uniform thickness [7]. In Fig. 3, each data point represents an average value of several measurements as described above for the same channel height. For a given channel height the three data points represent the measurements for three different flow rates. Figure 4 shows the measured zeta potential and the surface conductivity as functions of the NaCl concentration. This method can also be used to study the effects of temperature, pH, different electrolytes and surfactants on zeta potential and surface conductivity.

It should be pointed out that Eq. (13) or (14) is derived on the basis of Eq. (6) (or the equivalent form for a slit channel), the solution of the classical Poiseuille equation. The Poiseuille equation, however, does not consider any EDL or electrokinetic (e. g., electro-viscous) effect on the liquid flow. For small capillaries, the electro-viscous effects on flow may be significant and have to be considered [3]. The Eq. (13) or (14) is no longer valid for small capillaries and may cause a significant error when used to evaluate the zeta potential and the surface conductivity [10]. Since the electro-viscous effect on flow is negligible for flow through a capillary with a hydraulic diameter larger than 50 μm, it is recommended that above-described method should be used with capillary tubes of a hydraulic diameter larger than 50 μm.



Surface Conductivity Measurement, Figure 4 Variation of the bulk conductivity and the surface conductivity with NaCl concentration

Electro-Osmosis Current Method

Within the diffuse layer of the EDL, the local net charge density, ρ_e, is not zero. If an electric field is applied such that it is tangential to the EDL, an electrical body force is exerted on the ions in the diffuse layer of the EDL. The ions will move under the influence of the applied electrical field to form a conduction current, pulling the liquid with them and resulting in an electro-osmotic flow. The liquid movement is carried through to the rest (beyond the EDL region) of the liquid in the channel by viscous force. This electrokinetic process is called electro-osmosis. The effect of the electrical force to generate the flow is dependent on the local net charge density within the liquid, which in turn is dependent on the electric double layer field and hence the zeta potential, ζ. On the other hand, the surface conduction will influence the bulk liquid's share of the applied electrical field and hence will influence the electro-osmotic flow. Therefore, electro-osmosis also depends on both the zeta potential and the surface conductivity. The following will describe a method of determining both the zeta potential and the surface conductivity by measuring the electrical current in electro-osmotic flow through a capillary [8–10].

Zeta potential

Consider an electro-osmotic flow of an aqueous solution in a cylindrical capillary tube with a radius R as a fully-developed, one-dimensional flow at steady state. The momentum equation for such a case is given by [3]

$$-\eta \frac{1}{r}\frac{\mathrm{d}}{\mathrm{d}r}\left(r\frac{\mathrm{d}u}{\mathrm{d}r}\right) = E_x \rho_\mathrm{e} \tag{15a}$$

Where r is the radial variable. The corresponding boundary conditions are:

$$r = 0: \quad \frac{\mathrm{d}u}{\mathrm{d}r} = 0; \qquad r = R: \quad u = 0 \tag{15b}$$

where u is the liquid velocity, η is the viscosity, E_x is the applied electrical potential gradient, and ρ_e is the local net charge density. In order to solve the above flow equation, the local net charge density $\rho_\mathrm{e}(r)$ must be known. The local net charge density $\rho_\mathrm{e}(r)$ can be determined by the Boltzmann equation:

$$\rho_\mathrm{e}(r) = ze(n_+ - n_-) = -2zen_0 \sinh\left(\frac{ze\psi(r)}{k_\mathrm{B}T}\right) \tag{3}$$

The EDL potential $\psi(r)$ can be determined by the solving the well-known Poisson–Boltzmann equation for cylindrical capillary:

$$\frac{1}{r}\frac{\mathrm{d}}{\mathrm{d}r}\left(r\frac{\mathrm{d}\psi}{\mathrm{d}r}\right) = \frac{2zen_0}{\varepsilon_\mathrm{r}\varepsilon_0}\sinh\left(\frac{ze\psi}{k_\mathrm{B}T}\right) \tag{16a}$$

with the following boundary conditions:

$$r = 0: \quad \psi = 0; \qquad r = R: \quad \psi = \varsigma \tag{16b}$$

Once the EDL potential $\psi(r)$ is known, the local net charge density $\rho_\mathrm{e}(r)$ is determined according to Eq. (3). Finally, the equation of motion, Eq. (15a), can be solved numerically to find the velocity $u(r)$. The average velocity can then be determined as follows:

$$u_\mathrm{av} = \frac{1}{A_\mathrm{cross}}\int_0^R u(r)\,\mathrm{d}A_\mathrm{cross} = \frac{2}{R^2}\int_0^R u(r)\cdot r\cdot \mathrm{d}r \tag{17}$$

where A_cross is the cross-section area of the capillary tube. It should be realized from the above procedure that the velocity $u(r)$ and hence the average velocity u_av are implicit functions of the zeta potential, ζ (in the boundary condition, Eq. (16b)). If the average velocity can be measured directly, the zeta potential ζ can be determined by solving Eq. (17) by using an iterative technique. In this process, an initial guessing value of the zeta potential, ζ_guess, may be obtained by invoking the Debye–Huckel approximation, as described below.

The Debye–Huckel approximation assumes that the value of ψ is small ($\psi \leq 25\,\mathrm{mV}$) or the following approximation can be made:

$$\sinh\frac{ze\psi}{k_\mathrm{B}T} \approx \frac{ze\psi}{k_\mathrm{B}T} \tag{18}$$

If the above approximation can be made, the following exact solutions for the local net charge density distribution and the velocity profile can be obtained analytically:

$$\rho_\mathrm{DH}(r) = \zeta\frac{I_0(\kappa r)}{I_0(\kappa R)} \tag{19}$$

$$u_\mathrm{DH}(r) = \frac{\varepsilon_\mathrm{r}\varepsilon_0 E_x \zeta}{\eta}\left(1 - \frac{I_0(\kappa r)}{I_0(\kappa R)}\right) \tag{20}$$

where I_0 is the zero-order modified Bessel function of the first kind; and κ is the so-called Debye–Huckel parameter, defined by:

$$\kappa = \left(\frac{2z^2e^2n_0}{\varepsilon_\mathrm{r}\varepsilon_0 k_\mathrm{B}T}\right)^{1/2} \tag{21}$$

As shown in Eq. (17), the average velocity can be found by integrating the local velocity over the cross-section area of the capillary tube. Thus, with the Debye–Huckel assumption, ζ_DH can be expressed as an explicit function of the radius through the average velocity equation, such that if the average velocity is known, then the initial guess for the zeta potential ζ can be determined as

$$\varsigma_\mathrm{guess} = \varsigma_\mathrm{DH} = \frac{u_\mathrm{av}R^2\eta}{2\varepsilon\varepsilon_0 E_x}\left[\int_0^R r\left(1 - \frac{I_0(\kappa r)}{I_0(\kappa R)}\right)dr\right]^{-1} \tag{22}$$

Using this ζ_DH value as the initial guess for ζ_guess in Eq. (17) to calculate u_av, and comparing the result to the known (measured) value of u_av, a new ζ_guess is obtained. This procedure can be continued until the calculated and the known values of u_av converge.

Evaluation of the Specific Surface Conductivity

When considering the transport of an electrolyte solution, one must consider the motion of mobile ionic species in addition to the considerations of traditional fluid mechanics. The transport of ions in a capillary results in an electrical current. In electro-osmotic flow, the total current is a result of three physical processes:

1. the bulk conductivity of the electrolyte solution, resulting in a conduction current, $I_{\text{cond,bulk}}$;
2. the surface conductivity, resulting in a secondary conduction current, $I_{\text{cond,surf}}$; and,
3. the electro-osmotic flow, resulting in a convection current, I_{conv}.

Generally, the convection current is several orders of magnitude smaller than the other two components of the current. Neglecting the contribution of I_{conv} results in the following equation for the total current, I_{total}:

$$\begin{aligned} I_{\text{total}} &= I_{\text{cond,bulk}} + I_{\text{cond,surf}} \\ &= \lambda_{\text{b}} A_{\text{cross}} \boldsymbol{E} + L_{\text{surface}} \lambda_{\text{s}} \boldsymbol{E} \end{aligned} \tag{23}$$

For the case of a cylindrical capillary with an electrical field $\boldsymbol{E}$ applied in the axial direction only, I_{total} is given by:

$$I_{\text{total}} = \pi R^2 \lambda_{\text{b}} E_{\text{x}} + 2\pi R \lambda_{\text{s}} E_{\text{x}} \tag{24}$$

In general, the surface conductivity λ_{s} is unknown. Since the radius of the capillary tube, R, and the bulk liquid conductivity, λ_{b}, can be measured accurately, they can be treated as known, and E_{x} is applied electrical field strength and is known. Since the total current I_{total} can be measured, the above equation can be rearranged to solve for the surface conductivity, λ_{s}, such that:

$$\lambda_{\text{s}} = \frac{I_{\text{total}} - \lambda_{\text{b}} \pi R^2 E_{\text{x}}}{2\pi R E_{\text{x}}} \tag{25}$$

As seen from Eq. (25), by measuring the total current during a steady electro-osmotic flow, the bulk conductivity, the applied electrical field and the capillary size, the surface conductivity can be determined. Generally, this is a relatively simple method with a reasonable accuracy.

The above equation should be modified to account for the changes in ionic concentration within the double layer near the wall. The variation in ionic concentration is accounted for in the conduction current component by using the following equation:

$$I_{\text{cond,bulk}} = \int_A \lambda_{\text{b}} E_{\text{x}} \cosh \psi(r) \, \mathrm{d}A \tag{26}$$

Thus, Eq. (25) becomes:

$$\lambda_{\text{s}} = \frac{I_{\text{total}} - \int_A \lambda_{\text{b}} E_{\text{x}} \cosh \psi(r) \, \mathrm{d}A}{2\pi R E_{\text{x}}} \tag{27}$$

If ζ is known, the electrical field potential $\psi(r)$ can be determined by solving the Poisson–Boltzmann equation. The surface conductivity λ_{s}, therefore, can be determined by using the measured I_{total} and Eq. (27).

Experimental

The experimental set-up [8, 9] shown in Fig 5a can be used to measure the average velocity by monitoring the current in electro-osmosis. In the experiment, the reservoir 2 will be filled with an electrolyte solution at a desired concentration. The capillary tube and reservoir 1 will be filled with the same electrolyte solution at a concentration lower than the concentration in reservoir 2. For example, the capillary tube and reservoir 1 are filled with an electrolyte solution at a concentration that is 95% of the concentration in reservoir 2. Immediately after connecting the two reservoirs by the capillary tube, a voltage difference between the two reservoirs is applied by setting reservoir 1 at ground potential and reservoir 2 to a high voltage power supply unit (CZE1000R, Spellman, NY) via Platinum electrodes.

The applied electrical field results in an electro-osmotic flow in the capillary tube. During electro-osmosis, the higher-concentration electrolyte solution from reservoir 2 gradually displaces the lower-concentration electrolyte solution in the capillary tube (it can the opposite way depending on the polarity of the applied electrical field). As a result, the overall electrical resistance of the liquid and hence the current in the capillary tube changes, as illustrated in Fig. 5a. An L-DAS8 data acquisition chip (Kiefley) was used to record the voltage (kV) and current (μA) as a function of time (s). Once the lower-concentration solution in the tube is completely replaced by the higher-concentration solution from reservoir 2, the current will reach a maximum and constant value. The measured time for the current to reach such a plateau value is the time required for the solution from reservoir to travel through the entire capillary tube. The average velocity of the liquid flow can then be calculated by using:

$$u_{\text{av,exp}} = \frac{L}{\Delta t} \tag{28}$$

where L is the length of the capillary and Δt is the time required for the higher-concentration electrolyte solution to completely displace the lower-concentration electrolyte solution from the capillary tube.


Pt electrode
Capillary
Pt electrode
HV power source
C = 95%
C = 100%
Reservoir 1
Reservoir 2
Fluid Resistance C = 95% to C = 100%
Fluid Resistance C = 95%
Fluid Resistance C = 100%
Surface Resistance
a
Pt electrode
Capillary
Pt electrode
HV power source
C = 100%
C = 100%
Reservoir 1
Reservoir 2
Fluid Resistance C = 100%
Fluid Resistance C = 100%
Fluid Resistance C = 100%
Surface Resistance
b

Surface Conductivity Measurement, Figure 5 Schematic diagram illustrating experimental set-up and varying resistances (**a**) for measuring the current variation and the complete displacement time of a two-concentration system; (**b**) for measuring the total current of a single concentration system

For the purpose of evaluating the specific surface conductivity, a second set of measurements using a similar setup [8, 9], as shown in Fig. 5b, may be used to measure the total current, I_{total} during electro-osmosis. In these cases, reservoir 1, reservoir 2 and the capillary tube will be filled with an electrolyte solution of the same concentration.

Key Research Findings

Generally, the value of specific surface conductivity depends on the molecules of the solid surface, the surface charge, and the electrokinetic properties of the liquid (e. g., type of ions, valance, the ionic concentration, pH). Typical values of specific surface conductivity are of the order $10^{-9} \sim 10^{-8}$ for water in glass capillaries.

The electroosmotic current method described in the above sections was used to evaluate the zeta potential and the surface conductivity for Polyamide coated silica capillary tubes with KCl solutions [8]. In the experiments, polyamide coated silica capillary tubes of various diameters (Polymicro Technologies Inc., Phoenix, AZ) were cut to 10 cm. lengths and connected to the reservoirs. The electrolyte solution was prepared by using KCl (Anachemia Science, Quebec) and deionized ultra filtered (DIUF) water (Fisher Scientific, Ontario). The amount of KCl was measured by using a precision scale (Mettler). The bulk liquid conductivity of the prepared solutions was measured using a high precision conductivity meter (Mettler Toledo). In the experiments, each measurement was repeated at least three times for a given set of conditions. All experiments were conducted at room temperature (22 °C).



Surface Conductivity Measurement, Figure 6 A typical result of current versus time for Set-up A. For the specific case of: capillary diameter $D = 100\,\mu\text{m}$, $E_x = 3500\,\text{V}/10\,\text{cm}$. KCl concentration in Reservoir 1 is $C_{95\%} = 0.95 \times 10^{-4}$ M. KCl concentration in Reservoir 2 is $C_{100\%} = 10^{-4}$ M



Surface Conductivity Measurement, Figure 7 Specific surface conductivity, λ_S versus the applied voltage and the capillary diameter, for a 10 cm long capillary tube, for: (**a**) $C = 10^{-4}$ M KCl; (**b**) $C = 10^{-3}$ M KCl

Figure 6 shows a typical variation of current versus time for a KCl solution with a 100 μm diameter silica glass capillary and an applied electrical field of 350 V/cm. The concentration in reservoir 2 is $C_{100\%} = 10^{-4}$ M, and the concentration in reservoir 1 is $C_{95\%} = 0.95 \times 10^{-4}$ M . Linear regression was used to smooth the experimental data and determine Δt. The current increases with time as the higher concentration ($C_{100\%}$) electrolyte solution displaces the lower concentration ($C_{95\%}$) electrolyte solution in the capillary. The increase in current continues until the capillary is completely filled with the $C_{100\%}$ electrolyte solution, at which time the current reaches a steady value, which continues until the applied voltage is removed.

The average velocity of the liquid during electro-osmosis is determined by Eq. (28). Using the measured average velocity data, the method described earlier can be used to calculate the zeta potential ζ. The measured total current for single-concentration systems is required to determine the specific surface conductivity λ_s according to Eq. (25). In a more rigorous treatment, using the measured total current and the determined zeta potential, the specific surface conductivity λ_s can be calculated by using Eq. (27). Figs. 7a and b are plots of λ_s versus the applied voltage and the capillary size for the two KCl concentrations, $C = 10^{-3}$ M and $C = 10^{-4}$ M, respectively. From the results, there is clearly a relationship between the size of the capillary and the specific surface conductivity. Comparing the λ_s values between Fig. 7a and b, λ_s appears to have no significant dependence on the ionic concentration. This may be understood as the K^+ and Cl^- are not the potential determining ions in this system and are not adsorbed on the solid surface.

Future Directions for Research

Surface conductance is important in micro- and nano-scale flow and transport processes, especially when the channel size is small and the ionic concentration of the bulk solutions (bulk liquid conductivity) is low. More experimental data of surface conductivity are needed for various liquid-microchannel systems. With the rapid development of nanofluidics, it is highly desirable to develop new theoretical models, experimental methods and the experimental data for surface conductance of nanochannels.

Cross References

► Electrical Double Layers
► Zeta Potential Measurements
► Electroosmotic Flow (DC)
► Streaming Current and Electroviscosity
► Surface Conductivity

References

1. Hunter RJ (1981) Charge and Potential distribution at Interfaces. In: Hunter RJ Zeta Potential in Colloid Science: Principle and Applications. Academic, London, pp 11–55
2. Lyklema J (1995) Electric Double Layers. In: Lyklema J Solid-Liquid Interfaces. Fundamentals of Interface and Colloid Science, vol 2. Academic, London, pp 3.2–3.232
3. Li D (2004) Electrokinetics in Microfluidics. Academic, London
4. Lyklema J (1995) Electrokinetics and Related Phenomena. In: Lyklema J Solid-Liquid Interfaces. Fundamentals of Interface and Colloid Science, vol 2. Academic, London, pp 4.31–4.36
5. Briggs DK (1928) The determination of the ζ-potential on cellulose – A method. J Phys Chem 32:641
6. Rutgers AJ (1940) Streaming potentials and surface conductance. Trans Faraday Soc 36:69
7. Gu Y, Li D (2000) The Zeta Potential of Glass Surface in Contact with Aqueous Solutions. J Colloid Interface Sci 226:328–339
8. Arulanandam S, Li D (2000) Evaluation of Zeta Potential and Surface Conductance by Measuring Electro-Osmotic Current. J Colloid Interface Sci 225:421–428

9. Ren L, Escobedo C, Li D (2002) A New Method of Evaluating the Average Electro-Osmotic Velocity in Microchannels. J Colloid Interface Sci 250:238–242
10. Sze A, Erickson D, Ren L, Li D (2003) Zeta-Potential Measurement Using Smoluchowski Equation and the Slope of Current-Time Relationship in Electroosmotic Flow. J Colloid Interface Sci 261:402–410

Further Reading

- Hunter RJ (1981) Charge and Potential distribution at Interfaces. In: Hunter RJ Zeta Potential in Colloid Science: Principle and Applications. Academic, London, pp 11–55
- Lyklema J (1995) Electric Double layers. In: Lyklema J (ed) Solid-Liquid Interfaces. Fundamentals of Interface and Colloid Science, vol 2. Academic, London, pp 3.2–3.232

Surface-Directed Capillary Flow Systems

MICHAEL J. SWICKRATH[1], J. ADIN MANN[1],
GARY E. WNEK[2]
[1] Department of Chemical Engineering, Case Western Reserve University, Cleveland, OH, USA
[2] Department of Macromolecular Science and Engineering, Case Western Reserve University, Cleveland, OH, USA
michael.swickrath@case.edu

Synonyms

Surface tension-confined confined microfluidics; Wetting on structured substrates; Capillary-based microfluidics; Hydrophobic/hydrophilic microfluidics

Definition

Generating surface tension gradients such as Marangoni stresses or discontinuities in surface energy, either through ►chemical patterning or ►topographical manipulation, facilitates the control of wettability of fluids upon that surface. Surface-directed microfluidics is the exploitation of this phenomenon to encourage fluid transport through capillary interactions upon a surface-modified platform. Consequently, the need for extraneous pumping components is eliminated. These techniques demonstrate a great capacity to automate fluid transport providing alternative manufacturing methods for microfluidic platform development.

Overview

The field of microfluidics promises the capacity to automate sophisticated laboratory analyses into a diminutive platform that can be implemented by a user with minimal analytical experience. Often an analogy is drawn towards the integrated circuit revolution which facilitated the automation of large-scale computation. Similarly, a great deal of optimism exists that microfluidics may have such an impact on chemistry, biology and medicine, resulting in a drastic decrease in the amount of expensive reagent or invasive fluid samples required while enabling higher degrees of throughput and ►parallelization.

Such microfluidic devices have been successfully developed. However, many microfluidic devices require multiple components to implement fluid transport. This article describes alternative platform design to mitigate the aforementioned problems resulting in a fully-autonomous micro-device capable of promoting capillary flow. An example of commercial microfluidic device exploiting capillarity includes the OneTouch® testing strip developed by LifeScan, Inc. The test strip imbibes micro-volumes of blood which is introduced to a blood glucose meter facilitating fast and accurate results. The autonomous nature of this inexpensive microfluidic device is very attractive with regard to point-of-care diagnostics. Furthermore, many more novel platform configurations and fabrication methods are currently being investigated resulting in stand-alone microfluidic systems. Specifically, spontaneous ►surface-directed capillary pumping of fluids with appropriate surface tension and viscosity is enabled by patterning energetic discontinuities or topographical features upon a surface.

However, before *surface-directed microfluidics* can be employed towards solving problems in chemistry, biology and medicine, a thorough understanding of the underlying physics must be established. This task becomes non-trivial as fluidic miniaturization results in dramatic changes to the fundamental physics manifested at small length scales. For example, mass transport within microfluidic devices is a challenge as viscous effects dominate at small length scales rather than inertial effects [1]. Consequently, utilizing scaling arguments through dimensional analysis, the nonlinear terms in the Navier-Stokes equations can be neglected in most microfluidic systems. Although the lack of inertia at small length scales seems to indicate analysis of microfluidic platforms is straightforward, quite the opposite is true. Other non-linear phenomena that may not be as familiar at the macro scale become apparent as surface area to volume ratios increase [1]. In particular, surface ►curvature and three-phase boundaries must be taken into account making the analysis of *surface-directed* flows substantially more difficult.

With regard to *surface-directed microfluidics*, patterning discontinuities in surface energetics results in deformation of the solid-liquid contact line. Such deformations can either promote or impede capillary break-up. Consequently, discontinuous energetics serves as a mechanism to harness for autonomous fluid transport. Furthermore, other implications arise as a result of the capacity to manipulate interfacial *curvature* at the microscale. As the surface area to volume ratio experienced within microfluidic devices is rather substantial, the overall shape and stability of boundaries and interfaces can be dramatically affected by minute amounts of surface or fluid contaminants. Accordingly, *surface-directed microfluidic* devices warrant proper surface cleaning protocols, storage procedures and reagent preparation to ensure reproducible and reliable device function. Moreover, since reagents may necessarily contain surface-active components, adsorption dynamics may be an important factor in capillary pumping.

The breadth of this article seeks to address a review of fabrication techniques, characterization and analysis of microfluidic devices implementing the *surface-directed* approach. Furthermore, key research findings will be explicated along with aspects of this approach requiring future investigation. As a result, the methodology to implement the *surface-directed* approach will be established along with a suitable record of pertinent literature regarding this novel technique. However, before doing so, a brief diversion into the treatment of fluid physics for systems exhibiting high surface area to volume ratios may lend much insight in developing a robust understanding and appreciation of capillary-driven microfluidic flow.

Surface-Directed Capillary Physics

As previously mentioned, the analysis of microfluidic systems can be rather difficult for a variety of reasons. The direct implementation of the Navier-Stokes equations toward *surface-directed microfluidic* systems requires careful attention when considering the advection of the free surface and the associated curvature of this surface. Consequently, sophisticated computational fluid dynamics software packages are required for a comprehensive three-dimensional analysis of the fluid transport within *surface-directed microfluidic* devices. However, a time-consuming comprehensive analysis may be beyond the requirements of designing and manufacturing functional surface-directed microfluidic platforms. Consequently, empirical approximations and scaling arguments are commonly used in the characterization of microfluidics physics.

One common approach to treating capillary microfluidic phenomena entails equating the fluid volumetric flowrate to a ratio of pressure drop per resistance, R, in a fluid channel as developed by Washburn circa 1921 [2] where A_{cs} represents cross-sectional area of a fluid duct (assumed to be constant) and x represents the time-dependent location of the ▶ meniscus position.

$$A_{\mathrm{cs}}\frac{\mathrm{d}x}{\mathrm{d}t} = \frac{\Delta P}{R} \tag{1}$$

Considering capillary dynamics, the pressure drop term is often described by the Laplace equation, $\Delta P = 2\gamma H$, where γ represents liquid surface tension and H represents the mean *curvature* of the liquid-gas interface associated with all curves, C_i, passing through the surface. Furthermore, the character of a sufficiently smooth surface is through the invariant from differential geometry, the principal curvature of each curve, k_i. The the radii of curvature are the inverse of each principal curvature, $k_i = 1/r_i$. Considering the maximum and minimum ▶ radii of curvature at a point on a three-dimensional surface, the mean *curvature* can be calculated explicitly (see appendix for more thorough derivation of the mean *curvature* parameter).

$$H = \frac{1}{2}\left(\frac{1}{r_1} + \frac{1}{r_2}\right) \tag{2}$$

Curvature is usually assumed to follow geometries that can be fit to a circle (or sphere in the three-dimensional case) in the Laplace equation; this is not typically the case but usually results in a decent approximation. Further, for straight paths, r_2 can be considered as infinite and approximations can be made for r_1 [3].

$$r_1 = \frac{h}{2\cos\theta_{\mathrm{I}}} \tag{3}$$

In Eq. (3), θ_{I} indicates the contact angle at the three-phase interface.

Moreover, resistance terms exist for common geometries such as rectangular ducts [4].

$$R_{\mathrm{D}} = \frac{12\mu x}{wh^3}\left[1 - \frac{h}{w}\left(\frac{192}{\pi^5}\sum_{n=0,1,2}^{\infty}\frac{\tanh\frac{2n+1\pi w}{2h}}{(2n+1)^5}\right)\right]^{-1} \tag{4}$$

Here w represents channel width, h represents channel height and μ represents the viscosity of the fluid. In the case where $w \gg h$, the bracketed term can be neglected while maintaining sufficient accuracy through the approximation.

By substituting Eq. (3) into Eq. (2) and subsequently utilizing modified Eq. (2) and Eq. (4) with the general Washburn equation, one finds that capillary dynamics tend to follow

Eq. (5) with a general geometry-dependent characteristic length scale, L [1].

$$x \sim \left(\frac{\gamma L \cos\theta}{\mu} t \right)^{1/2} \tag{5}$$

Consequently, the time-dependent fluid front position in a *surface-directed microfluidic* device tends to be dependent on system geometry, intrinsic fluid properties, fluid-substrate interactions and the square root of time. This dependency has been derived theoretically and observed for a number of capillary-driven microfluidic systems such as the ▶ v-groove geometry [5, 6]. Noting that the ratio γ/μ is a characteristic capillary velocity, U_c, enables the rearrangement $x \sim (U_c L \cos\theta t)^{1/2}$. This relation perhaps leads to a more tangible description of fluid specific capillary transport.

Outside of the capillary dynamics approach, scaling arguments and dimensionless analysis can provide valuable insight into fluid physics on the micro-/nanoliter scale. An exhaustive review of these approaches has been conducted for a variety of microfluidic techniques [1]. However, for this article, we will strictly consider scaling metrics and dimensionless numbers pertinent to the *surface-directed* approach.

First, we will consider perhaps the most often applied dimensionless number toward fluid transport, the Reynolds number. The Reynolds number is a measure of inertial to viscous forces [1] and is dependent upon fluid density ρ, and viscosity μ, as well as characteristic velocity U and the characteristic length scale L which can be written as follows.

$$\mathrm{Re} \equiv \frac{\rho L U}{\mu} \tag{6}$$

Characteristic length scales chosen depend on system geometry. For example, diameter is commonly chosen for cylindrical systems while the hydraulic diameter, $D_A = 4A/P$, may be chosen for Cartesian geometries (such as a microfluidic duct) in which A denotes cross-sectional area and P is the perimeter of the cross-section. As mentioned earlier, the lack of turbulence in microfluidic devices indicates inertial effects are minimal. Consequently, viscous forces dominate. Reynolds numbers characteristic of microfluidic devices are generally on the order of $O(10^{-6})$ to $O(10)$ [1]. Furthermore, the transient time required to achieve this laminar flow goes according to $\tau \sim \rho L^2/\mu$. Consequently, one can see that flow in microfluidic devices tends to be rather devoid of turbulence.

Another relevant number in the analysis of microfluidic devices in general is the Péclet number; which yields the ratio of convective transport to diffusive transport where D represents the diffusion constant of a molecule within a particular fluid.

$$\mathrm{Pe} \equiv \frac{U}{D/L} \tag{7}$$

As already indicated, flow is laminar in microfluidic devices which results in great difficulty in attaining adequate mixing for chemical reaction processes. Scales for the general time ($\tau \sim w^2/D$) and length ($z \sim Uw^2/D$) to achieve mixing in a low Péclet number devices are known considering a channel of width w [1].

An additional dimensionless number particularly important to *surface-directed microfluidics* is the capillary number utilized to measure viscous to interfacial forces.

$$\mathrm{Ca} \equiv \frac{U}{\gamma/\mu} \tag{8}$$

Surface forces tend to be inherently important for capillary-driven microfluidic devices as surface area to volume ratios are rather high and surface tension-induced interfacial *curvature* is significant enough to promote capillary wicking. For chemically patterned devices depending on hydrophobic/hydrophilic confinement in particular, the capillary number must be sufficiently low (i. e. $\mathrm{Ca} \ll 1$) in order to maintain fluid confinement within intricate geometry implying $\Delta P \leqslant \gamma/w$ [1].

The above analyses lend insight into the behavior of fluids within *surface-directed microfluidic* devices. Now that an intuitive framework of the fluid physics within microfluidic platforms has been established, the contemplation of successful platform fabrication techniques and their associated applications is worthy of consideration.

Basic Methodology

Several approaches exist to manufacture *surface-directed microfluidic* platforms. Examples of relevance to this article include the *chemical patterning* of regions exhibiting drastic and abrupt disparity in surface energies and the manipulation of surface topography to influence mean *curvature*. Furthermore, some alternative techniques will be discussed as potential applications to *surface-directed microfluidics* such as thermal actuation and passive gate fabrication with coatings that enable contact angle mediation via photochemical reactions or the presence of water.

Chemical Patterning

The concept of *chemical patterning* generally involves the deposition of hydrophobic ‘curbs’ upon an otherwise hydrophilic substrate. Consequently, capillarity can be exploited to promote autonomous fluid transport eliminating the requirement to integrate pumping equipment into the microfluidic platform.

Initial investigations focused on the relationship between fluid morphology and surface energy. Gau et al. investigated the shape instability that liquids undergo when an appropriate amount of liquid is adsorbed on a hydrophobic surface patterned with hydrophilic microstripes [7]. Hydrophilic stripes were deposited via thermal vapor deposition of MgF_2 (stripe thickness $\sim 20\,\text{nm}$) upon hydrophobic silicone rubber or thiolated gold substrates. The patterned surface was then exposed to sufficiently humid air and cooled to force the condensation of liquid upon the surface. The results indicate that initially, water adsorbs forming a structure with a cylindrical cross-section; however, when an adequate amount of water is adsorbed, instability can occur resulting in bulge formation. This instability is quite different from the classical Rayleigh instability; rather it is a bifurcation in two different morphologies of constant mean *curvature* [7]. A linear stability analysis indicates that the cylinder is locally stable so long as the wavelength of the shape deformation λ, exceeds a critical value λ_c, based upon the hydrophilic path width a and advancing contact angle θ.

$$\lambda_c = \left[\frac{\frac{\pi}{2}}{\theta^2 - \left(\frac{\pi}{2}\right)^2}\right]^{1/2} \frac{\theta}{\sin\theta} a \qquad (9)$$

Consequently, Gau suggests that it is in fact feasible to build two-dimensional microfluidic devices through *chemical patterning* techniques.



Surface-Directed Capillary Flow Systems, Figure 1 *Surface-directed microfluidic* device fabricated via sol gel processing (**a**) with a demonstration of the configuration of device and (**b**) the implementation of the device with colored fluid for visualization [9]. (**c**) Computational fluid dynamic representation of the fluid front of a device fabricated with a patterned bottom substrate and indiscriminately hydrophobic top substrate. (**d**) The implementation of the device with an unpatterned top substrate [11]

These results were also independently confirmed by other groups [8]. Darhuber et al. developed disparities in hydrophilicity on a [001]-oriented p-type doped silicon wafers coated with a ► self-assembled monolayer of octadecyl-trichlorosilane (OTS). In all of the studies [7, 8], the experimental results were found to be in good agreement with theoretically determined surface morphology through the ► surface evolver software package. The surface evolver software package is an interactive tool to study the equilibrium surface shapes of liquids subject to surface tensions and other energies under various constraints. The surface evolver evolves the surface toward minimal energy by a gradient descent method. The surface evolver software package is a powerful tool for the theoretical investigation of static surface structures of *surface-directed microfluidics* enabling the determination of surface curvature and quantification of the Laplace pressure. Most often, gravity can be neglected in the surface evolver analysis as indicated by the low Bond number experienced in microfluidic devices (i. e. $\text{Bo} \ll 1$). Specifically, the Bond number is a measure of body forces (i. e. gravity) per surface forces (i. e. capillarity) where $\Delta\rho$ indicates the change in density across a surface, g is the gravitational constant, L is a characteristic length of the capillary cross-section and γ is the surface tension of the fluid.

$$\mathrm{Bo} \equiv \frac{\Delta \rho g L^2}{\gamma} \tag{10}$$

These findings were later extended towards the development of autonomous microfluidic platforms employing *surface-directed* fluid transport. Several studies indicate that microfluidic platforms can be manufactured by chemically patterning substrates in combination with correspondingly patterned (or in some cases unpatterned) lids in a parallel plate arrangement [9–11]. Figure 1 demonstrates the approach utilized to develop such devices. Figures 1a and b demonstrate the configuration of a device fabricated with hydrophobic commodity polymers patterned on both bottom and top substrates with a hydrophilic silica sol gel material [9]. Figure 1c exhibits the fluid front, determined through computational fluid dynamics, of a device (Fig. 1d) where the bottom substrate is composed of a hydrophilic borosilicate wafer patterned with hydrophobic plasma-polymerized hexafluoropropene barriers developed photolithographically. The top substrate in Figs. 1c and d is indiscriminately hydrophobic.

Results from the development of these parallel plate *surface-directed microfluidic* have resulted in optimal device geometry recommendations. The optimal aspect ratio, defined as width per height of the device, has been determined through free energy considerations [3]. To ensure spontaneous capillary flow, the aspect ratio must follow Eq. (11) which indicates that the height of the device b, must always be less than the width of the device a, and the capacity to promote fluid flow is subject to the magnitude of the advancing contact angle of the hydrophilic path. The development of Eq. (11) follows arguments based upon the ►Laplace pressure drop associated with interfacial *curvature* [3].

$$\frac{b}{a} \leqslant \cos\theta \tag{11}$$

Consequently, as the advancing contact angle increases towards the 90° limit for spontaneous flow, the capacity of the device to promote capillary flow diminishes drastically.

Furthermore, devices have been developed demonstrating reactions and passive valves with *self assembled monolayers* of OTS via either multi-stream laminar flow or photolithography [9, 10]. The pressure sensitive valves were demonstrated with silane solutions and water with trace amounts rhodamine-B for visualization purposes. The maximum pressure experienced based on capillarity was determined for these devices dependent upon device geometry, liquid surface tension γ and the advancing contact angle for the non-polar hydrophobic region θ_N [9, 10].

$$\Delta P_\mathrm{MAX} = \frac{2\gamma}{b} \sin\left(\theta_\mathrm{N} - \frac{\pi}{2}\right) \tag{12}$$

Furthermore, an application requiring a large interfacial surface area is demonstrated with an acidified gas and phosphate buffer neutralization in the presence of indicator. This investigation also presents conditions for critical width and curve radius that fluid can make under spontaneous flow conditions [10]. Furthermore, through energy minimization considerations, Lam et al. independently derive and demonstrate Eq. (11) is in excellent agreement between theoretical and experimental results [9]. Consequently, Eq. (11) can be derived through an alternative but equally valid approach.

An additional method regarding the fabrication of *surface-directed microfluidic* devices entails chemically pattering plasma polymerized hexafluoropropene coating photolithographically upon a hydrophilic borosilicate wafer [11]. Consequently, such a drastic differential in wettability is established that only one patterned substrate is required and can be coupled with a hydrophobic top substrate. The advantage of this approach is that it eliminates the tedious necessity for proper alignment for top and bottom substrates. The investigators of this approach present a theoretical model to predict fluid front position versus time based upon a conservation of momentum approach and discuss the similarities between their model and an analogous model derived for cylindrical capillaries.

$$\frac{\mathrm{d}^2\left(x^2\right)}{\mathrm{d}t^2} + \frac{12\mu}{\rho a^2}\frac{\mathrm{d}\left(x^2\right)}{\mathrm{d}t} + \frac{2\gamma\left[2a - b\left(\cos\theta_1 + \cos\theta_2\right)\right]}{\rho a b} = 0 \tag{13}$$

In this relation, x denotes the fluid front position as a function of time t, system architecture a and b, and intrinsic material properties including contact angles of the fluid upon the hydrophilic and hydrophobic materials θ_1 and θ_2, respectively. The solution to this second order ordinary differential equation with respect to *meniscus* position squared can be solved relatively easy through numerical techniques. The solution determined by the investigators of this approach is in excellent agreement with experimental results [11]. Furthermore, the investigators demonstrated that confluent monolayers of cells could be cultured in their apparatus and proteins could be selectively adsorbed upon the device surface [11]. Consequently, the *surface-directed* approach may be advantageous for applications requiring uninhibited gas exchange such as tissue engineering.

Lastly, the *surface-directed* approach is not without limitations. Due to the inherent simplicity associated with these devices, flow control and mixing become an issue. Moreover, paths with bifurcations pose a challenge to flow control as fluid does not discriminate between paths to flow across. Specifically, preferentially controlling which path a particular fluid travels across is difficult, at best. In addition, flow within microfluidic devices tends to be laminar rendering turbulent mixing is difficult to achieve, at best [1]. However, one may be able to overcome this predicament by strategically patterning resistance upon the device surface although this has yet to be employed within a two-dimensional chemically patterned platform.

Although much work still exists before chemically patterned devices provide novel solutions to problems in chemistry, biology and medicine, many of the reports discussed are encouraging regarding the capacity of *surface-directed microfluidic* devices to support autonomous chemical processes.

Topographical Manipulation

An alternative paradigm to facilitating capillary wicking via the *surface-directed* technique includes deliberately manipulating the topography of a device to control interfacial *curvature*. This approach to *surface-directed microfluidics* generally exploits the fact that capillary-based flow can occur where the corners meet as a consequence of the diminishing *radius of curvature* at the intersection [12]. However, for this flow to occur spontaneously, the Concus-Finn condition must be fulfilled considering the advancing contact angle θ, as well as the corner half-angle α [13].

$$\theta < \frac{\pi}{2} - \alpha \tag{14}$$

This technique has been rigorously studied for the determination of equilibrated liquid morphology on structured surfaces such as rectangular channels and in *v-grooves* [5, 6]. In the case of rectangular channels, a map has been constructed enabling the a priori determination of ultimate liquid morphology based upon the contact angle of the substrate and aspect ratio of the duct cross-section [14]. Figure 2 illustrates this morphological dependency on fluid properties and system architecture. The associated syntax addresses features characteristic of each morphological regime. Results were calculated theoretically with the surface evolver software package and were found to be in good agreement with experimental results investigated through AFM [14].

Furthermore, the *v-groove* morphology has been thoroughly investigated and relations for capillary dynamics have been developed [5, 6]. Several alcohols with γ/μ ratios ranging from 46 – 970 cm/s were studied in grooves of varying geometry machined into a copper substrate. Figure 3a illustrates the groove geometry while Fig. 3b demonstrates the experimental platform used to conduct the studies [5, 6]. Two models were developed characterizing the capillary dynamics. The first model considers a hydrodynamic approach where the driving force is a result of pressure drop across a curved interface. The second model depends strictly upon the total interfacial energy change while neglecting the shape of the curved interface. In both cases, flow was demonstrated to always follow a relation of the following form where $K(\alpha, \theta)$ is a geometric parameter dependent on system geometry and contact angle.

$$x = K(\alpha, \theta)\, h_0 \frac{\gamma}{\mu} t^{1/2} \tag{15}$$

The results of these analyses demonstrate that the three-phase contact line location follows the square root of time. Coumarin fluorescent dye was utilized in small quantities to develop sufficient contrast of the three-phase line under UV irradiation for the comparison of experimental data to the models. The investigators of this approach conclude that exhaustive solutions to the capillary flow model can be realized; however, approximations via Eq. (15) can be employed for sufficiently accurate predictive models [5, 6].

As demonstrated through the referenced literature, *topographical manipulation* provides the capacity to induce capillary wicking through interfacial *curvature* modulation. As a result, one can exploit techniques such as photolithography, chemical etching and even three-dimensional machining to produce features promoting *curvature* management. Consequently, the approach of *topographical manipulation* is yet another straightforward but viable technique to produce *surface-directed* fluid transport.

Flow Modulation Techniques

As already established in previous sections, the *surface-directed* approach to microfluidic system fabrication produces autonomously functioning devices with little rigor associated regarding implementation. This is a direct implication of the fact that the driving force for flow exploits capillary interactions producing spontaneous capillary flow. However, an unwanted artifact resulting from the inherent simplicity of these devices is that flow modu-



Surface-Directed Capillary Flow Systems, Figure 2 Demonstration of equilibrated liquid structure based on system geometry and advancing contact angle. Characteristic features include droplet (D), filament (F), pinned-wedges (pW) and corner-wedges (cW). The $+/-$ signs indicate whether the ►Laplace pressure associated with each morphology is positive or negative, respectively [14]



Surface-Directed Capillary Flow Systems, Figure 3 Illustration of *v-groove* experiments (**a**) with the demonstration of system architecture and (**b**) the experimental platform utilized in the study [6]

lation is particularly difficult. This drawback is especially hindering for systems requiring the controlled introduction and the selective guidance of fluids across intricate geometry. This section intends to introduce several techniques that have been or could be employed to guide fluids in specific directions.

One such mechanism to control flow directionality or rate includes manipulating ►thermocapillary shear stresses at the liquid air interface upon a substrate with a temperature gradient to facilitate fluid transport [15]. This technique has been demonstrated through patterning a SiO_2 wafer with hydrophobic strips of octadecyltrichlorosilane and coupling this substrate with a heater array to induce temperature gradients [15]. The driving force for such thermocapillary induced flow is through local heating that can reduce the liquid surface tension producing *thermocapillary shear stress* [15].

$$\tilde{\tau} \cdot \hat{n} = \nabla\gamma = \frac{\partial\gamma}{\partial T}\nabla T \qquad (16)$$

For liquids, $\partial\gamma/\partial T$ is essentially temperature independent indicating that the driving force is ∇T. This affect induces fluid transit from warmer areas to cooler areas of a substrate. Figure 4 demonstrates the capacity to control fluid progression utilizing this technique. As demonstrated, fluid can be directionally guided down required pathways and even across 90° angles. Furthermore, models have been developed with a lubrication equation approach and found to be in good agreement with the experimental results [15].

Other techniques provide the potential to produce wettability modulation upon chemically patterned substrates. For example, ▶contraphilic polyurethane materials exist exhibiting an 83° contact angle when dry but a 108° contact angle in the presence of water [16]. The proposed mechanism is that amide inter/intramolecular hydrogen bonding occurs in the dry and moderately hydrophilic state while surface-confined amide-water hydrogen bonding releases semifluorinated groups yielding a more hydrophobic surface when wet [16]. This mechanism has been found to be reversible and could potentially serve as method to design passive gates between aqueous and nonaqueous solutions. This material could also be utilized to selectively pattern regions to impede fluid flowrate.

Another example of a coating technique presenting a feasible solution to developing wettability modulation includes employing light sensitive compounds such as spiropyrans. These photoisomerizable compounds can undergo an 11 – 14° reversible decrease in contact angle when light is switched from the visible region to ultraviolet [17]. This photocapillary modulation technique could be utilized to control the *Laplace pressure*, and therefore the flowrate, in a microfluidic channel coated with spiropyran compounds. Consequently, the field of flow modulation in *surface-directed microfluidics* is currently wide-open for investigation. Novel flow control methods are a necessity before integrating complex reaction processes into an on-chip format.

Key Research Findings

As demonstrated within this review, the *surface-directed microfluidics* approach offers a simple method for fabrication and implementation of micro-analytical systems. This burgeoning field offers great opportunity to resolve problems associated with more complicated microfluidic systems. Though this approach is rather new, several findings have already been established which may be of particular importance to investigators initiating research in this field. From a fluid physics perspective, rigorous solutions to the Navier–Stokes equations are not immediately realizable as a consequence of the poor understanding of ▶slip velocities associated with boundary conditions in microfluidic systems. However, alternative approaches towards developing dynamic flow models indicate *meniscus* position progresses according to the square root of time and is dependent upon fluid/substrate properties and system geometry as demonstrated in Eq. (5). Interestingly, Mann et al. [5, 6] found that a dynamic contact angle was not required to fit their experimental data to theoretical predictions. Furthermore, *surface-directed microfluidic* platforms can adequately be characterized as exhibiting low Reynolds, Péclet, capillary and Bond number flow. Subsequently, flow in *surface-directed* devices tends to be rather laminar with transport being dominated by diffusion with surface forces out-competing body forces such as gravity, respectively.

Chemical patterning and *topographical manipulation* techniques have successfully produced autonomous devices for fluid transport. In some cases, reaction processes have been integrated within these devices. However, this field is ripe with opportunity regarding the implementation of *surface-directed* platforms towards developing platforms that conduct reactive and diagnostic analyses. Preliminary diversion into theory has provided some relations that can be utilized for intelligent device optimization; however, a great deal of investigation needs to be addressed before a comprehensive understanding of device function is established.

Surface-directed microfluidic devices are inherently simple. Consequently, flow modulation is a concern. Methods have been employed to gain more control over flow such as mechanical actuation and thermocapillary induction. Moreover, material coatings provide the potential for the development of flowrate impediment and passive gate introduction through contraphilism or light-mediation.

Future Directions for Research

The *surface-directed microfluidics* approach presents a manufacturing methodology involving minimal rigor. Furthermore, *surface-directed* devices are devoid of extraneous mechanical/electrical components which can lead to component malfunction and overall device failure. As a consequence of the inherent simplicity of *surface-directed microfluidic* devices, implementation of the platform is straightforward and requires limited analytical experience. However, before wide-scale deployment of *surface-directed microfluidic* devices can be realized, a more comprehensive understanding of the underlying physics needs to be conducted. Certain phenomena play a larger role in fluid physics as liquid samples approach the nanoliter scale. For example, long-ranged inter-molecular interactions, thermal fluctuations such as capillary waves and the influence of the molecular structure of the fluid all inherit a greater capacity to affect fluid physics as surface area to volume ratios decrease. To realize greater degrees of *parallelization* and high-throughput, a better theoretical framework is a necessity regarding microfluidics as a whole encompassing the



Surface-Directed Capillary Flow Systems, Figure 4 (**a**)–(**e**) Thermal induced division of a drop of dodecane on a selectively wetting strip 1000 μm wide (elapsed time = 8.5 s). (**f**)–(**i**) Dodecane drop propelled through a 1000 μm wide intersection (elapsed time = 104 s). (**j**)–(**l**) Dodecane drop thermally guided across a 90° angle in a 1000 μm wide intersection (elapsed time = 164 s) [15]

surface-directed technique. Lastly, fluid sample pretreatment techniques are of great consideration to ensure reproducible and reliable function of devices as only minimal amounts of contaminants are required to influence capillary dynamics in *surface-directed* devices. A comprehensive literature review exists as a basis for microfluidic sample pretreatment [18]; however, these findings need to be extended to the *surface-directed* approach to enhance platform reliability. Addressing such concerns may expedite the application of the *surface-directed microfluidics* towards current problems in chemistry, biology and medicine.

Cross References

- ► Capillary Filling
- ► Capillary Force Valves
- ► Methods for Surface Modification
- ► Surface Tension Driven Flow
- ► Thermal Capillary
- ► Thermocapillary Pumping
- ► Wetting and Spreading

Appendix

Considering a Monge surface of area A_o in Cartesian coordinates, $\xi\,(t,x,y)$, the change in free energy required to curve this surface with respect to a flat surface with a reference free energy, Ω_0, at a constant composition and temperature is as follows.

$$\Omega - \Omega_0 = \int_{A_o} [p]\,\xi\,(t,x,y)\sqrt{a}\,\mathrm{d}x\,\mathrm{d}y + \int_{A_o} \sqrt{a}\,\mathrm{d}x\,\mathrm{d}y \quad \text{(a)}$$

Where $[p]$ is the pressure drop (ΔP) across the interface and the a is a geometrical parameter.

$$a = \sqrt{1 + \left(\frac{\partial \xi}{\partial x}\right)^2 + \left(\frac{\partial \xi}{\partial y}\right)^2} \quad \text{(b)}$$

Considering that the surface $\xi\,(t,x,y)$ is arbitrary and the associated derivatives are small, the free energy function is simplified.

$$\Omega - \Omega_0 = \int_{A_o} [p]\,\xi\,\mathrm{d}x\,\mathrm{d}y + \int_{A_o} \gamma \left[1 + \frac{1}{2}\left(\frac{\partial \xi}{\partial x}\right)^2 + \frac{1}{2}\left(\frac{\partial \xi}{\partial y}\right)^2\right] \mathrm{d}x\,\mathrm{d}y \quad \text{(c)}$$

Let δ be the variational operator and consider that $\xi\,(t,x,y)$ and the derivatives of $\xi\,(t,x,y)$ are equal to zero on the boundary, ∂A_o, over which the variation function is determined. Moreover, it is implicitly assumed that $\delta\,[p] = 0$

and $\delta\gamma = 0$.

$$\delta\Omega = \int_{A_o} [p]\,\delta\xi\,\mathrm{d}x\,\mathrm{d}y + \int_{A_o} \gamma \left[\frac{\partial \xi}{\partial x}\frac{\partial \delta\xi}{\partial x} + \frac{\partial \xi}{\partial y}\frac{\partial \delta\xi}{\partial y} \right] \mathrm{d}x\,\mathrm{d}y \tag{d}$$

Utilizing integration by parts on the second integral further simplifies the variation in free energy.

$$\delta\Omega = \int_{A_o} [p]\,\delta\xi\,\mathrm{d}x\,\mathrm{d}y - \int_{A_o} \gamma \left[\frac{\partial^2 \xi}{\partial x^2} + \frac{\partial^2 \xi}{\partial y^2} \right] \delta\xi\,\mathrm{d}x\,\mathrm{d}y \tag{e}$$

Because A_o is arbitrary and $\delta\xi$ is small, but an otherwise arbitrary variation, an explicit pressure drop dependence becomes apparent.

$$0 = [p] - \gamma \left[\frac{\partial^2 \xi}{\partial x^2} + \frac{\partial^2 \xi}{\partial y^2} \right] \tag{f}$$

Furthermore, in comparison with the Laplace pressure, $\Delta P = 2\gamma H$, the mean curvature of the Monge surface can be reconstructed leading directly to the result in Eq. (2).

References

1. Squires TM, Quake SR (2005) Microfluidics: Physics at the nanoliter scale. Rev Mod Phys 77:977–1026
2. Washburn EW (1921) The dynamics of capillary flow. Phys Rev 17(3):273–283
3. Zhao B, Moore JS, Beebe DJ (2001) Surface-directed liquid flow inside microchannels. Science 291:1023–1026
4. Constantinescu VN (1995) Steady Parallel Flow of Incompressible Fluids. In: Ling FF (ed) Laminar Viscous Flow. Springer, New York, p 123
5. Mann JA, Romero L, Rye RR, Yost FG (1995) Flow of simple liquids down narrow v-grooves. Phys Rev E 52(4):3967–3972
6. Rye RR, Mann JA, Yost FG (1996) The flow of liquids in surface grooves. Langmuir 12:555–565
7. Gau H, Herminghaus S, Lenz P, Lipowsky R (1999) Liquid morphologies on structured surfaces: from microchannels to microchips. Science 283:46–49
8. Darhuber A, Troian SM, Reisner WW (2001) Dynamics of capillary spreading along hydrophilic microstripes. Phys Rev E 64(3):031603(1–8) http://prola.aps.org/abstract/PRE/v64/i3/e031603
9. Lam P, Wynne KJ, Wnek GE (2002) Surface-tension confined microfluidics. Langmuir 18:948–951
10. Zhao B, Moore JS, Beebe DJ (2002) Principles of surface-directed flow in microfluidics channels. Anal Chem 74:4259–4268
11. Bouaidat S, Hansen O, Bruus H, Berendsen C, Bau-Madsen NK, Thomsen P, Wolff A, Jonsmann J (2005) Surface-directed capillary system; Theory, experiments and applications. Lab Chip 5:827–836
12. Boys CV (1959) Soap Bubbles. Dover, New York
13. Concus P, Finn R (1969) On the behavior of a capillary surface in a wedge. Proc Natl Acad Sci USA 63:292–299
14. Seemann R, Brinkmann M, Kramer EJ, Lange FF, Lipowsky R (2004) Wetting morphologies at microstructured surfaces. Proc Natl Acad Sci 102(6):1848–1852
15. Darhuber AA, Valentino JP, Davis JM, Troian SM, Wagner S (2003) Microfluidic actuation by modulation of surface stresses. App Phys Lett 82(4):657–659
16. Makal U, Wynne KJ (2005) Water induced hydrophobic surface. Langmuir 21:3742–3745
17. Rosario R, Gust D, Garcia AA, Hayes M, Taraci JL, Clement T, Dailey JW, Picraux ST (2004) Lotus effect amplifies light-induced contact angle switching. J Phys Chem B 108:12640–12642
18. Lichtenberg J, de Rooij NF, Verpoorte E (2002) Sample pretreatment of microfabricated devices. Talanta 56:233–266

Surface Electric Conductance

► Surface Conductivity
► Surface Conductivity Measurement

Surface Enhanced Raman Scattering (SERS)

Definition

►SERS is a highly sensitive optical detection technique in which lasers are used to excite vibrational transitions in a molecule adsorbed on a metal nanoparticle surface. As a result of large optical fields, the Raman cross section for a molecule on a surface is enhanced by factors of $10 \times 10^6 - 10 \times 10^{10}$.

Cross References

► Biosensors Using Surface-Enhanced Raman Scattering

Surface Evolver

Definition

An interactive tool to study the equilibrium surface shapes of liquids subject to surface tensions and other energies under various constraints by evolving the surface toward a minimal energy state by a gradient descent method.

Cross References

► Surface-Directed Capillary Flow Systems

Surface Features to Enhance Transport

► Roughness Effect on Microscale Transport

Surface Forces

► Disjoining Pressure

Surface Lipid Translocation

► Microfluidics for Studies of Apoptosis

Surface Micromachining

► Silicon Micromachining

Surface Modification, Methods

SUSHANTA K. MITRA, AURO ASHISH SAHA
Department of Mechanical Engineering, Indian Institute of Technology Bombay, Mumbai, India
skmitra@me.iitb.ac.in

Synonyms

Surface change; Surface transformation; Surface treatment

Definition

Surface chemistry is of great importance in micro/nanofluidic devices, especially in the case of miniaturized and integrated systems, owing to the high surface-area-to-volume ratio. Surface properties play a vital role in a number of microfluidic devices through hydrophobic and electrostatic interactions. Protein and cell adhesion at surfaces can occur because of hydrophobic and electrostatic interactions, which is undesirable in bioanalytical applications. Control of surface properties is thus an indispensable prerequisite in microfluidic systems. The approach generally adopted is to modify the surface chemistry of the device to make it more useful for various applications.

Overview

Microfluidic devices have been fabricated from a wide range of materials, such as silicon, fused silica, borosilicate glass, elastomers (poly(dimethylsiloxane) (PDMS)), resins (SU-8), and thermoplastics (poly(methylmethacrylate) (PMMA), polystyrene, polycarbonate (PC), cyclic olefin copolymer, and poly(ethylene terephthalate glycol) (PETG)). The fabrication of glass- or silicon-based devices relies on established technologies such as those of microelectronics and is often considered to be time-consuming and very expensive. Glass, in particular fused silica, is a very attractive material for microfluidic chips owing to its excellent optical properties, good insulating properties, and inertness towards a variety of different solvents. Although silicones have been used mostly as soft-tissue substitutes, serious problems have occurred when silicone devices have been implanted for a long time [1]. In contrast, microfluidic devices fabricated from polymer materials have simpler manufacturing procedures and are cheaper. Furthermore, channels with high aspect ratios are much easier to produce from polymer materials than from glass, which is often advantageous for optical detection.

The surfaces of devices often exhibit different wettability characteristics, depending on the manufacturing approach adopted. Surface modification techniques can be used to alter the wettability behavior of microfluidic devices. This difference in wettability can be used to control the flow rate in devices. There are many other benefits of hydrophilic surface treatments, including the ability to increase adhesion and capillary effects [2]. Irrespective of the material used in the device, the primary requirement that a material needs to fulfill is biocompatibility in various applications. Therefore it is also necessary to use surface modification techniques to render materials biocompatible. It is believed that future devices of increasing sophistication will often require programmable surface properties, including control of the spatial distribution of charge and polarity [3].

Conventional polymers do not always possess the combination of desired bulk and surface properties for a specific application. The polymer materials used for microfluidic devices are innately hydrophobic, low-surface-energy materials and thus do not adhere well to other materials brought into contact with them. This necessitates their surface modification/treatment to render them adhesive. This has prompted the development of a variety of polymer modification techniques, with the aim of developing new materials from known and commercially available polymers that have desirable bulk properties (elasticity, thermal stability, permeability, etc.), in conjunction with newly tailored surface properties (adhesion, biocompatibility, optical reflectivity, etc.).

Currently, the methods used for surface modification of polymers are dynamic coating and permanent surface modification [4]. Dynamic coating is considered to be the easiest way to perform surface modification. In this



Surface Modification, Methods, Figure 1 Surface modification with 3-aminopropyltrimethoxysilane

coating process, surface-active coating materials or surface modifiers are introduced into the buffer, which is then forced through the channel at a constant speed. The coating materials are strongly adsorbed onto the channel surface via physical interactions. Permanent surface modification involves specific chemical reactions which permanently modify the chemical composition of the surface by the application of high-energy sources such as radiation, flames, coronas, plasmas, electron beams, and ion beams to activate the surface before chemical bonding.

For silicon-based microdevices, most of the surface modification approaches rely on silanization chemistry (Fig. 1), where the silanol groups on the surface are derivatized using various silanes. Silica surfaces must typically be coated to effect permanent changes in their properties [3]. A wide variety of techniques have also been developed around surface functionalization using self-assembling monolayers (SAMs) for coatings on silicon surfaces. Monolayers have been deposited on silica surfaces, primarily using chemicals consisting of a hydrocarbon backbone terminating in a polyfunctional alkoxysilyl moiety. Hydrolysis and condensation of these alkoxy groups attaches the hydrocarbon backbone to the silica surface via a siloxane bond. SAMs have been patterned using UV lithography, microcontact printing, scanned-probe lithography, and electron beam lithography. Polymers including polyethylene glycol, polyacrylamide, and hydroxypropylcellulose have been grafted onto silica surfaces using, primarily, methacrylate-terminated intermediates. Successful polymer films prevent both electrostatic and hydrophobic attractions at the wall by presenting an uncharged polar surface to the fluid [3]. Surface modification of silicon-based devices with polyethylene glycol (PEG) can be performed by physical adsorption, covalent immobilization such as grafting and chemical coupling, or gas phase treatment (plasma treatment or deposition) [5]. Although surface modification efforts have proved successful, however, they do not guarantee conformal coating and long-term stability. As in the case of modified PDMS, the surfaces have shown to slowly recover their original hydrophobicity. It is known that an oxidized PDMS surface recovers its hydrophobicity.

Dynamic coating appears to be especially attractive for plastic microchips, as established surface chemistry such as silanization is often not applicable to polymeric materials. Permanent coatings are often regarded as the most effective way to perform surface modification in order to reduce analyte–wall interactions and to modify electroosmotic flow (EOF). Permanent surface modification is, however, often more laborious in the production process and might, accordingly, be less attractive for disposable devices. Dynamic coating methods are applied not only to control EOF and reduce analyte adsorption but also to make a hydrophobic surface more compatible with a hydrophilic separation medium.

Basic Methodology

The chemical modification of the surfaces of polymers is of increasing importance in many diverse aspects of modern technology, with applications which include solid-phase chemical synthesis related to drug discovery, chemical catalysis, biocompatible medical implants and prostheses, diagnostic devices, and surface-modified fabrics, amongst many others. In biological analysis, it is necessary to make polymer surface properties meet requirements regarding wettability, biocompatibility, and nonspecific adsorption [6]. Introducing biological samples, such as plasma or whole blood, into microsystems needs far more consideration of surface modification compared with working with buffer samples of adjusted pH containing cells in the form of polymeric beads. Blood–material contact most often initiates surface-mediated reactions that lead to cell activation and blood clotting.

A wide array of surface modification techniques, ranging from simple to sophisticated, wet to dry, and vacuum to nonvacuum, are available for a host of polymeric materials. They include plasma surface treatment; laser surface treatment; corona, flame, UV, ozone, UV/ozone, photochemical, photografting, chemical-grafting, and chemical methods of surface modification; and modification of polyamide surfaces by microorganisms [7].

The surface modification of PDMS is often found to be difficult because the material is inert. Polymer surface modification is required for applications such as biomedical assays, microfuel cells, and lipid-based immunoassay chips. Many surface modifications have been made to PDMS for electrophoretic separation, but new modifications are being made for emerging applications such as heterogeneous immunoassays and cell-based bioassays. These new modification techniques are powerful because they impart biospecificity to the microchannel surfaces and reduce protein adsorption [8]. To decrease the hydrophobicity of PDMS, low-pressure oxygen plasma, UV/ozone, indirect corona, or oxygen-rich butane gas flame treatment is often used to activate the surface and render it hydrophilic. Oxygen plasmas have been the most popular of these techniques. During plasma treatment, the surface of PDMS is subjected to high-energy species, including electrons, photons, ions, and radicals. The surface is oxidized owing to exposure to the plasma and it becomes oxygen-rich and carbon-lean. However, the surface of oxidized PDMS recovers its hydrophobicity after oxidation in a very short time. The recovery in hydrophobicity is caused by the migration of PDMS chains to the surface. It is believed that continuous storage of oxidized PDMS in water stabilizes electroosmotic flow. High-energy treatments make the surface hydrophilic and thus able to support electroosmotic flow; they also helps in the binding of molded PDMS to flat PDMS or other substrates. However, it should be noted that permanent surface modification techniques cannot be directly applied to rigid polymeric materials, owing to the more challenging microfabrication procedures required for those materials.

Some commercially available protein-inert polymers commonly used in microfluidic applications, all of which require permanent surface modification, are polyacrylamide, poly(N-hydroxyethylacrylamide), poly(N,N′-dimethylacrylamide) (PDMA), polyvinylpyrrolidone (PVP), poly(vinyl alcohol) (PVA), hydroxyethylcellulose (HEC), and hydroxypropylmethylcellulose (HPMC). To permanently attach protein-resistant materials to the channel surface, high-energy sources, special chemistries, or even strong physical adsorption have been employed to introduce reactive functionalities. After activation, protein-resistant polymers can be anchored via UV-initiated free-radical polymerization. Polymeric materials usually do not have good solvent and heat resistance compared with inorganic materials, and hence it is necessary to take precautions during surface treatment to avoid serious damage to the microstructure or alteration of the physical properties of the bulk material.

One successful method for PDMS surface modification is ultraviolet polymer grafting. In this method, PDMS is immersed in an aqueous solution of $NaIO_4$, benzyl alcohol, and a monomer (acrylic acid, acrylamide, dimethyl acrylamide, hydroxyethyl acrylamide, or PEG-monomethoxyacrylate) under uniform exposure to a 200 W mercury lamp. $NaIO_4$ scavenges oxygen in the polymerizing mixture, and benzyl alcohol facilitates chain transfer during polymerization. The graft density increases with the irradiation time and also with the concentration of benzyl alcohol. When individual polymers are compared, the highest graft density is achieved with polyacrylamide, whereas the lowest is obtained with poly(PEG-monomethoxyacrylate) [9].

One of the earliest methods for modification of a PMMA surface for medical applications is based on chemical conversion of the wall rather than on addition of a new layer [9]. The conversion of PMMA consists of reesterification of PMMA with polyfunctional hydroxyl compounds, such as ethylene glycol, glycerol, mannitol, or saccharose. First, the PMMA surface is covered with ethylene glycol or another polyalcohol, which is allowed to diffuse inside the polymer body. Then the surface is treated with hot sulfuric acid to perform reesterification and replace the methanol in PMMA with ethylene glycol. After neutralization with sodium bicarbonate, a hydrophilic, transparent layer is formed on the surface of the PMMA.

Polycarbonate is a thermoplastic material used in many applications, including microchips. The aromatic rings in the polycarbonate structure offer a relatively easy way to modify the PC surface by a direct sulfonation reaction. After cleaning with isopropyl alcohol, the polycarbonate surface is modified by reaction with sulfur trioxide at 50°C for 10 min. Then it is rinsed with water and dried in a stream of nitrogen. The sulfonated PC has shown improvement in both surface wettability and electroosmotic mobility. As an alternative to coating the PC surface forming the wall, UV and excimer laser (at a wavelength of 248 nm) treatment of the PC surface have also been used for surface modification. PETG is another plastic material used for the preparation of microchips. Its surface can be modified easily by NaOH treatment, resulting in ester hydrolysis and the appearance of carboxylic groups on the surface.

Dynamic wall coatings for surface modification can be applied to glass substrates owing to the presence of silanol groups on the channel surface. PDMA can be used simultaneously as a sieving matrix and a wall coating for a glass microchip. Several other polymers, including PEG, PVP, HEC, and epoxy poly(dimethyl acrylamide), are applicable as coatings on a glass chip. Several dynamic coatings can be applied to PDMS chips to make the channel surface more hydrophilic. An n-dodecyl-b-D-maltoside

(DDM) coating minimizes protein adsorption on PDMS surfaces [10]. DDM is an alkyl polyglucoside, which belongs to a family of very mild nonionic surfactants. It adsorbs strongly on hydrophobic surfaces and forms a monolayer. This monolayer coverage causes the surface to become hydrophilic and nonionic, thus reducing the interaction between the protein and the surface. Several dynamic coatings have been tried for modifying PMMA surfaces [9] of microchip channels used with 1-aminopyrene-3,6,8-trisulfonate-labeled oligosaccharides. However, low-molecular-weight compounds, including monoethylamine, diethylamine, and triethylamine, and surfactants, such as sodium dodecyl sulfate, cetyltrimethylammonium bromide, and dodecyltrimethylammmonium chloride, do not adequately suppress the adsorption of analytes on the channel wall. A significant improvement is observed when hydrophilic neutral polymers, including PEG, HEC, HPMC, and methylcellulose are applied to PMMA walls.

The surface properties of many materials may be tailored, for example for adhesion promotion, nonstick properties, or chemical activation, by coating with silanes. From a general point of view, silanization of hydroxyl-terminated substrates is an effective and frequently used procedure for modification of the chemical and physical properties of a substrate, as well as for covalent immobilization of a variety of compounds. Surfaces bearing oxides are well known to be of potential interest for chemical modification with silanes. Silane coatings serve in a number of applications such as protective coatings and adhesion promoters on metal surfaces, adhesives in industrial paints, selectively binding surfaces for tethering biological molecules in biosensor and DNA chip design, scanning probe microscopy (SPM) studies of biomolecules, and chemical force microscopy studies (where they serve as probe-functionalizing agents). Silanes have also been grafted onto plastic and elastomeric microchannels. Silanes have the general formula $RSiX_3$, where R is an organofunctional group, selected according to the desired surface properties, and X is a hydrolyzable group, typically an alkoxy group, which is capable of reacting with the substrate. The silanes are normally hydrolyzed at some stage in the coating process, allowing interaction with the substrate via either hydrogen bonds or covalent bonds.

The surfaces of glasses contain silanol groups. The presence of silanol groups on the surface of a glass microchip makes reaction with silanol the first choice for modification of glass surfaces. In one approach, after the channels have been flushed with NaOH, the channels are first filled with γ-methacryloxypropyltrimethoxysilane in diluted acetic acid and/or acetonitrile for an hour. In a second step, an aqueous solution of acrylamide together with ammonium persulfate and 1,2-bis-(dimethylamino)ethane (TEMED) is then pumped into the channels and polymerized at room temperature. The channels are then flushed with water and dried under vacuum. In another approach, channels in borofloat glass chips are coated with thermally immobilized PVA. A 1% aqueous solution of PVA is repeatedly pumped into the channels, and then the channels are emptied by a nitrogen flow. The chip is flushed with a nitrogen flow at 70°C for 60 min, followed by heating at 160°C for 10 min without any flow.

Chemical modification of microchip surfaces with SAMs has been used to prevent or minimize the deposition of proteins on channels. SAMs are ordered molecular assemblies that are formed spontaneously by the adsorption of a surfactant with a specific affinity of its headgroup to a substrate. Immersing an oxidized silicon wafer in a solution of an organosilicon derivative forms the SAM. The formation of a compact monolayer results in a drastic reduction of the surface wettability.

Measurement Techniques

In order to understand the behavior of surfaces after surface modification, it is essential to examine their surface composition and structure in detail. A large number of techniques are available, and it is often desirable to combine several of these methods. The techniques used to monitor surface properties include scanning electron microscopy (SEM), optical profilometry, atomic force microscopy (AFM), X-ray photoelectron spectroscopy (XPS), infrared (IR) spectroscopy, imaging ellipsometry, and water contact angle measurements.

SEM is a tool for measuring surface topography and morphology. SEM functions by focusing and scanning a relatively high-energy electron beam (usually 15 – 30 keV) on a electrically conducting specimen. The measurement of nonconducting samples is difficult owing to charging effects. Often, the sample preparation step introduces difficulties. Transmission electron microscopy (TEM) or scanning transmission electron microscopy (STEM) can also be employed in surface characterization.

Optical profilometry equipment is used for the measurement of surface texture, which includes features such as roughness, waviness, and lay. The methods of measurement available can be further classified into contact and noncontact methods, and three-dimensional (area) and two-dimensional (profile) procedures.

AFM is a tool for measuring surface topography on a nanometric scale. The principle is similar to that of contact profilometry with a nanometric tip. AFM has made significant contributions to biomaterials research in areas dealing with structure, properties, dynamics, and manipulation. Interface phenomena such as protein adsorption, conformational changes, and subsequent interactions with cellular components can be observed with AFM. Study of the mechanisms of these phenomena can help in explaining why a particular surface treatment may exhibit performance superior to another.

The X-ray photoelectron spectroscopy (XPS) technique is used to identify chemical species on the surfaces of materials. XPS uses a monochromatic, low-energy X-ray beam. The interaction between the incident beam and the atoms of the material causes emission of photoelectrons from within a few micrometers of the surface. The kinetic energy of the electrons is measured and provides information about the nature and environment of the atoms in the surface.

Infrared-based techniques are used to identify molecules on the surface. IR radiation is used to excite vibrational modes in molecules in the gas phase or adsorbed on a surface. The transmitted or reflected IR spectrum can be analyzed in a spectrometer. Considerable improvement in the sensitivity can be achieved by use of Fourier transform infrared (FTIR) spectroscopy. Attenuated total reflection (the ATR-FTIR method) inside a crystal (Germanium) of high refractive index can be used to further enhance the surface sensitivity (using the evanescent field).

Ellipsometry is a nondestructive, label-free optical method for determining film thicknesses and optical properties. Imaging ellipsometry combines the power of ellipsometry with microscopy, and has an *x*-*y*-resolution of approximately 1 μm. It measures the change in the polarization state of light reflected off the surface of the film. Fast ellipsometry methods, both single-wavelength and multiwavelength, have been used for monitoring film growth in situ, allowing the precise control of film deposition processes.

The contact angles and surface tension are connected via Young's equation, based on the thermodynamic energy balance at a fluid/solid/fluid interface. At any point on the perimeter of a liquid drop on a solid surface, three surface tension components (solid–liquid, solid–vapor, and liquid–vapor) are balanced and control the wetting behavior. Both static and dynamic (advancing/receding) measurements can be performed.

Key Research Findings

Surface modification using vapor-phase deposition is very promising for some biomedical nanodevices and has advantages over liquid-phase deposition, since the vapor phase has the ability to permeate more efficiently into silicon nanochannels. A vapor-phase deposition system described by Bhushan et al. [11] used conformal fluorosilane self-assembled monolayer films on silicon and PDMS surfaces. Different perfluorosilane films were deposited onto three different substrates: piranha-cleaned silicon, oxygen-plasma-treated silicon, and oxygen-plasma-treated PDMS. The films were characterized by means of a contact angle analyzer for hydrophobicity, an ellipsometer for film thickness, and an atomic force microscope for surface roughness. The surfaces modified by the fluorosilane films consistently exhibited dramatically higher water contact angles and lower adhesive forces than did the unmodified silicon surfaces.

A pulsed UV excimer laser [4] has been used to modify the surface chemistry and surface charge of a previously imprinted microchannel in PMMA, without changing the physical dimensions of the channel. This surface modification technique was used to reduce the band-broadening effects that occur owing to electrokinetic flow in bends. The electroosmotic mobility was shown to increase by an average of 4% with UV-modified surfaces compared with nonmodified surfaces without any change in the channel morphology. UV exposure was demonstrated to spatially modify the surface charge and to create the desired electrokinetic flow profiles, without the use of wall coatings or the need to change the channel dimensions.

PDMS surface modification using graft polymerization of 2-hydroxyethyl methacrylate (HEMA) induced by a CO_2 pulsed laser was demonstrated by Khorasani et al. [1]. The CO_2 pulsed laser generated radicals on the PDMS surface, which react with oxygen to form hydrogen peroxide through hydrogen abstraction from the PDMS chains. The PDMS surface was then graft polymerized with the water-soluble HEMA monomer by thermal cleavage of hydroperoxide groups. In vitro assays showed that the addition of poly(HEMA) to hydrophobic PDMS provided a suitable surface for reducing platelet adhesion and allowed activation of the surface, unlike the unmodified sample. It was also observed that the laser-treated samples without any graft polymerization become almost superhydrophobic, with a contact angle of 170°. It was shown that these superhydrophobic PDMS films had higher blood compatibility than the hydrophilic PDMS and the untreated PDMS.

Photopatterned surface modification has been demonstrated by Kirby et al. [3], for the purpose of arbitrary control of the surface charge and hydrophobicity of silica-based microfluidic structures. The microchannels were globally coated with an acrylate-terminated SAM followed by localized polymerization of polyacrylamide, resulting in photopatterning of the surface charge and polarity. The photopatterning technique enabled the researchers to pattern isolated regions in the device. The performance of the coating was evaluated by performing zeta potential measurements, cell adhesion studies, and micellar electrokinetic chromatography (MEKC) separation. The tests indicated a reduction in cell adhesion and wall charge. The coatings showed good stability under biological pH conditions, but degraded under extreme pH conditions. It was also shown that the SAM coating protocol had only a marginal effect on the electrokinetic performance of silica microchannels.

PEG chains have been added to polymer substrates as a means of minimizing nonspecific protein adsorption, because of their low interfacial energy, nonadhesive properties, and high mobility. A simple method for the deposition of brush-like PEG chains on PMMA microfluidic channel surfaces was reported by Bi et al. [6]. A copolymer of butyl methacrylate (BMA) and poly(ethylene glycol) methyl ether methacrylate (PEGMA) was synthesized to deposit a dense PEG molecular, brush-like coating on the PMMA microchannel surfaces via the anchoring effect of the hydrophobic BMA units. The addition of hydrophilic PEG chains to microchip surfaces overcomes the limitations caused by the hydrophobicity of PMMA. The modified microchannel surfaces showed good wettability, low nonspecific adsorption, and better biocompatibility, and enhanced the electroosmotic mobility compared with the mobility in the native state. The modified surface also showed excellent blood compatibility, with low protein and platelet adhesion.

Recently, a new method has been developed to modify the hydrophobic and hydrophilic nature of silicon surfaces by the use of 5-(4-Hydroxyphenyl)-10,15,20-tetra(p-tolyl)porphyrin self-assembled monolayers [12]. The bare SiO_2 substrate exhibited a contact angle of $33 \pm 2°$, showing the hydrophilic nature of the surface. In the presence of a hydroxyphenylporphyrin SAM, the contact angle was found to increase to up to $75 \pm 3°$, indicating the hydrophobic nature of the surface due to the formation of a self-assembled monolayer on the SiO_2 surface. Hydrophilic surface modification of PDMS using an atmospheric plasma has recently been reported by Hong et al. [2]. PDMS stamps were shown, by measurement of the water contact angle and XPS and AFM analysis, to exhibit surface hydrophilicity after the plasma treatment.

The hydrophilic stability of surface-modified PDMS was described by Bodas et al. [13]. Three different modification processes, namely conventional oxygen plasma treatment, two-step modification using $O_2 + C_2F_6$, and chemical modification using HEMA, were considered in the study. All of the surfaces were characterized using static contact angle measurements and ATR-FTIR spectroscopy. Oxygen plasma modification resulted in hydrophilic stability for about 2 days. The hydrophobic recovery in this case was due to the migration of low-molecular-weight species from the surface to the bulk of PDMS. HEMA modified PDMS showed the lowest contact angle and retained its hydrophilicity for over 10 days. The wettability in this case was attributed to carbonyl groups. The $(O_2 + C_2F_6)$-modified PDMS did not show a much lower contact angle, but its hydrophilic stability was much higher than that of the O_2-plasma-treated sample. This high stability was attributed to stable, hydrophilic CF groups on the surface.

Future Directions for Research

Surface treatments and surface interactions are the challenges ahead for the research community in relation to the development of advanced, sophisticated microfluidic devices. Surface modification techniques need to be optimized for various applications, and particularly for disposable microfluidic devices. PDMS will be a popular material for future microfluidic devices, and some issues associated with most of the currently employed treatments, such as the hydrophobic recovery of PDMS surfaces, need to be adequately addressed.

Cross References

- ► Hydrophilic/Hydrophobic Patterning
- ► Plasma Treatment of Nanoparticles for Nanofluids

References

1. Khorasani MT, Mirzadeh H, Sammes PG (1999) Laser surface modification of polymers to improve biocompatibility: HEMA grafted PDMS, in vitro assay – III. Radiat Phys Chem 55:685–689
2. Hong SM, Kim SH, Kim JH, Hyang HI (2006) Hydrophilic surface modification of PDMS using atmospheric RF plasma. J Phys: Conf Ser 34:656–661
3. Kirby BJ, Wheeler AR, Zare RN, Fruetel JA, Shepodd TJ (2003) Programmable modification of cell adhesion and zeta potential in silica microchips. Lab Chip 3:5–10
4. Johnson TJ, Ross D, Gaitan M, Locascio LE (2001) Laser modification of preformed polymer microchannels: application to reduce band broadening around turns subject to electrokinetic flow. Anal Chem 73:3656–3661
5. Kim P, Jeong HE, Khademhosseini A, Suh KY (2006) Fabrication of non biofouling polyethylene glycol micro and nanochannels by ultraviolet assisted irreversible sealing. Lab Chip 6:1432–1437
6. Bi H, Meng S, Li Y, Guo K, Chen Y, Kong J, Yang P, Zhong W, Liu B (2006) Deposition of PEG onto PMMA microchannel surface to minimize nonspecific adsorption. Lab Chip 6:769–775
7. Mittal KL (1996) Polymer surface modification: relevance to adhesion. VSP, Netherlands

8. Makamba H, Kim JH, Lim K, Park N, Hahn JH (2003) Surface modification of poly(dimethylsiloxane) microchannels. Electrophoresis 24:3607–3619
9. Dolnik V (2004) Wall coating for capillary electrophoresis on microchips. Electrophoresis 25:3589–3601
10. Huang B, Wu H, Kim S, Zare RN (2005) Coating of poly(dimethylsiloxane) with n-dodecyl-β-D-maltoside to minimize nonspecific protein adsorption. Lab Chip 5:1005–1007
11. Bhushan B, Hansford D, Lee KK (2006) Surface modification of silicon and polydimethylsiloxane surfaces with vapor-phase-deposited ultrathin fluorosilane films for biomedical nanodevices. J Vac Sci Technol A 24(4):1197–1202
12. Nayak K, Kulkarni PD, Deepu A, Sitaraman VR, Punidha S, Saha AA, Ravikanth M, Mitra SK, Mukherji S, Rao VR (2007) Patterned microfluidic channels using self-assembled hydroxyphenyl porphyrin monolayer. Proceedings of 7th IEEE International Conference on Nanotechnology (in press)
13. Bodas D, Malek CK (2006) Formation of more stable hydrophilic surfaces of PDMS by plasma and chemical treatments. Microelectron Eng 83:1277–1279

Surface Plasmon Resonance Sensors

DAVID ERICKSON
Sibley School of Mechanical and Aerospace Engineering,
Cornell University, Ithaca, New York, USA
de54@cornell.edu

Synonyms

SPR

Definition

Surface plasmons are electromagnetic waves that occur at metal/dielectric interfaces. The conditions for exciting these optical modes are extremely sensitive to the dielectric environment very near this interface. As a result, surface plasmon resonance (SPR) is one of the most commonly exploited label free optical biosensing techniques in use today.

Overview

This article introduces the essentials of surface plasmon resonance biosensing. The *Basic Methodology* section focuses on describing the experimental techniques involved and some of the advantages and disadvantages of the various implementations that are in common use today. In the *Key Research Findings* and *Future Directions for Research* sections, the limitations of the current state of the art in SPR biosensing will be discussed in the context of future analytical needs and the promise of other unlabeled biosensing technologies. For more detailed information, readers are referred to some of the recent reviews of the subject by Homola et al. [1].

Basic Methodology

In this section we introduce the most popular surface plasmon resonance biosensing architectures in use today. In each case the operating principle has been outlined and whenever possible the advantages and disadvantage of the given approach have been discussed both in the context of the competing SPR architectures an other biosensing techniques.

Angular Surface Plasmon Resonance Biosensing

The attenuated total reflection surface plasmon resonance (ATR–SPR), approach using the Kertschmann geometry shown in Fig. 1a, represents the most common SPR configuration in use today. In this arrangement, transversely polarized light is incident on a metal/dielectric interface through a coupling prism. Under most conditions the incident light is nearly completely reflected from the surface and very little loss in optical power is observed at the detector (PMT in Fig. 1a. At a particular angle of incidence, θ_{sp}, a momentum matching condition exists and a certain amount of the incident energy is coupled into a surface plasmon mode resulting in a reduction in the reflected power. The incident angle for this plasmon excitation is described by Eq. (1) below,

$$\sin\theta_{\mathrm{sp}} = \frac{1}{n_{\mathrm{p}}}\sqrt{\frac{\varepsilon_{\mathrm{m}}(\lambda)\varepsilon_{\mathrm{s}}}{\varepsilon_{\mathrm{m}}(\lambda)+\varepsilon_{\mathrm{s}}}} \tag{1}$$

where n_{p} is the refractive index of the prism, $\varepsilon_{\mathrm{m}}(\lambda)$ is the dielectric constant of the metal film which varies as a function of the excitation wavelength, λ, and ε_{s} which represents the dielectric constant of the sensing layer (see the inset in Fig. 1a for details of the geometric arrangement). At fixed wavelength, ε_{m} is constant and thus from Eq. (1) it is apparent that θ_{sp} is only a function of the dielectric constant in the sensing region. The plasmon wave decays exponentially into the sensing layer over a spatial distance on the order of a few hundred nanometers and thus only the near field of the sensing region is probed. In the cases of interest here, this metal/dielectric interface consists of a thin metal film deposited either directly on the prism surface or on a microscope slide that is refractive index matched to the prism. Gold is most often used as it is inert to the atmosphere, can be modified by appropriate surface chemistry to provide active sites for bonding of organic molecules, and exhibits a pronounced surface plasmon effect in the visible and near infrared regions of the electromagnetic spectrum. A subtle variation on the above geom-



Surface Plasmon Resonance Sensors, Figure 1 Variations on Surface Plasmon Resonance Detection (**a**) Angular SPR (**b**) Spectral SPR and (**c**) Nanoparticle or Local SPR. Details on each of the above techniques is provided in the text

etry uses a grating coupler to excite a plasmon wave at the interface [2].

In a typical biosensing experiment, the metal layer is functionalized with a series of biorecognition agents (referred to as probes herein) specific to a solution phase target of interest. The addition of these probes to the surface increases the average dielectric constant in the near field of the sensing layer and a change in θ_{sp} is observed. Following functionalization a solution which may or may not contain targets specific to the immobilized biorecognition agents is introduced to the surface (for most commercial systems this is done using some form of microfluidic delivery system). Should the solution contain the compliment to the surface probe, a positive binding event will occur and the average dielectric constant in the sensing layer will further increase and another shift in θ_{sp} will be observed.

ATR–SPR has numerous inherent properties that have made it one of the most popular biosensing techniques in use today. The primary advantage is that it represents a *label free* technique in that since the transduction signal is based on changes in local refractive index, the targets do not require tagging (e. g., a florescent label). Because measurements of θ_{sp} can be made dynamically quantitative information on the reaction kinetics, such as the bioaffinity constants, can also be obtained. In addition ATR–SPR also exhibits extremely high sensitivity compared with other biosensing techniques. Most systems have angular resolutions on the order of 10^{-4} degrees and bound mass sensitivities on the order of $\mathrm{ng/cm^2}$ (nanograms per square centimeter) which correspond to average near field refractive index changes on the order of $\Delta n = 10^{-5}$. As a specific example, for many nucleic acid based biomolecular recognition systems an adsorbed mass on the order of $700\,\mathrm{ng/cm^2}$ is required for an SPR shift of 1 degree. A significant disadvantage of SPR, however is that this sensitivity is strongly dependent on the spatial distance of the added mass from the sensor surface. Since the plasmon decays exponentially into the solution phase, bound mass which is farther away from the surface has an increasingly lesser effect on the average refractive index and results in a smaller shift in the SPR angle. This represents a significant limitation on the types of systems which can be investigated through SPR.

Figure 2 demonstrates the use of the angular SPR method for the detection of cancer antigens in human sera as performed in Campagnolo et al. [3]. In this case the patient sera is being screened for the presence of antibodies specific to the NY–ESO–1 which is a cancer/testis antigen expressed in a number of malignant neoplasms (see the above reference for more details). In these experiments a nickel-nitrilotriacedtic (Ni–NTA) surface chemistry is applied to the gold sensor surface to serve as the immobilization chemistry. When His-tagged NY–ESO–1 antigen is flown over the functionalized surface, a change in the SPR angle, $\Delta\theta_{sp}$, on the order of 1.15° is observed. Introduction of the antigen is done through a simple microfluidic flow cell. Note that this is quantified in the figure axis in units of PU or *Pixel Units* which are equivalent to a change of 0.0038° in the SPR angle. After washing with the run buffer $\Delta\theta_{sp}$ reduces to 0.15° (∼





Surface Plasmon Resonance Sensors, Figure 2 SPR sensorgram for the interaction of surface-immobilized His-tagged NY–ESO–1 with (**a**) a serum sample (labeled A) which contains the anti–NY–ESO–1 antibody and (**b**) a serum sample (labeled D) which contains the anti–NY–CO–38 antibody. Both serum samples were dilute 1 : 15 in PBS buffer. Triangles indicate the injection of analyte; inverted triangles indicate the injection of running buffer. Figure and caption reprinted with permission from Campagnolo et al. [3]

40 PU) suggesting that some non-specifically absorbed tumor antigen has been removed from the surface, leaving only the chemically immobilized probes. When Sample A (Fig. 2a) is then flown over the surface, a significant increase in the SPR angle is observed indicating the presence of binding between the immobilized antigen and its compliment and suggesting anti-NY–ESO–1 activity within the patient sample. When Sample D (Fig. 2b) is flown over the surface only a slight change in $\Delta\theta_{sp}$ is observed (due to non-specific adsorption) indicating that the sample does not contain any anti-NY–ESO–1 activity.

Spectral Surface Plasmon Resonance Biosensing

A variation on the above approach, termed spectral SPR (e. g., Otsuki et al. [4]), exploits the wavelength dependence of ε_m to interrogate the surface plasmon coupling conditions. This resonant wavelength condition can be determined from Eq. (1) given a knowledge of the incident angle θ_{sp} and the $\varepsilon_m(\lambda)$ relationship. The apparatus is similar to the angular approach described earlier, the only significant difference being that the experiment is conducted at fixed incident angle and a tunable excitation source is used to sweep over the wavelengths of interest as illustrated in Fig. 1b. Alternatively a broadband excitation source could be used and the spectrum of the reflected light is recorded. Analogous to the angular SPR case, by monitoring the change in the resonant wavelength with time, information on the reaction kinetics and bioaffinity constants can also be obtained.

The spectral technique has two advantages over the traditional angular approach: a simplification of the experimental apparatus for multiplexed SPR imaging and increased inherent sensitivity. As described by Otsuki et al. [4], the spectral approach lends itself to imaging based data collection techniques which are more amenable to high throughput screening applications (this is expanded on in the *Key Research Finding* findings section of this article). The latter of these relates to the relatively weak dependence of ε_m on wavelength as outlined in detail by Homola et al. [5]. Despite these advantages, the angular SPR approach is generally preferred to the spectral approach due to added expense of the tunable illumination source or the added complication of extracting the reflected spectrum.

Local Surface Plasmon Resonance Biosensing

As an alternative to the traditional SPR biosensing approaches, local SPR (LSPR) has recently been developed for surface phase geometries. LSPR surfaces comprise of dielectric substrate with arrays of sub-wavelength scale metallic nanoparticle, nanostructure or nanohole features. Localized surface plasmon resonances occur when light is absorbed or scattered by oscillating electric dipoles within those nanostructures. These standing oscillations represent a slightly different mechanism from the propagating surface plasmon polaritons associated with the architectures discussed above, though the term *plasmon resonance* is commonly used to refer to both. When illuminated these surface arrays exhibit a characteristic change in the transmitted or reflected power at a specific resonant wavelength that is strongly dependent on the local dielectric environment. As such binding events are detected by observing the change in this resonant wavelength using a similar technique to the spectral SPR technique described above. Though the specifics are dependent on the geometric properties of the nanostructure, the relationship between the change in the resonant wavelength and the dielectric constant of the surrounding medium is often reported to be close to linearly proportional to the change in refractive index. The well cited characterization study by Haes et al. [6] provides details of the experimental apparatus and a nanosphere lithography technique



Surface Plasmon Resonance Sensors, Figure 3 (**a**) Schematic of a typical optical configuration and the fluidic connections employed with a transmission mode LSPR device. (**b**) Schematic and images illustrating the architecture of the microfluidic chip with embedded nanohole arrays at relevant centimeter-, micrometer-, and nanometer-length scales. Figure and caption reprinted from De Leebeeck et al. [8]

for surface preparation and functionalization. The sensitivity limits reported in some of the earlier works using this approach were much lower than those for traditional SPR however recently Dahlin et al. [7] described a technique for improving the instrumentation and data analysis techniques for this architecture in the end reporting limits of detection on the order of $100\,\mathrm{pg/cm^2}$. One of the major strengths of the LSPR techniques is that the excitation angle can be normal or near normal to the surface, significantly simplifying the overall setup and facilitating extension to large area two dimensional multiplexing.

As an implementation example of this technique consider the system shown in Fig. 3 which shows a schematic of the optofluidic integration architecture used to couple the microfluidic delivery system with a nanohole array as presented by De Leebeeck et al. [8] . In this case the nanohole array was fabricated in a 100 nm thick gold film on a transparent glass substrate using a focused ion beam milling technique, enabling the creation of feature sizes on the order of 150 nm as shown in Fig. 3b. The plasmonic resonance of each array is governed by the spatial periodicity of the holes. In this experiment, a grouping of nanohole based arrays of varying periodicity constitutes an array of unique SPR sensors. Such a platform could facilitate both a spatial and spectral multiplexed format. The microfluidic chip is fabricated in PDMS using soft lithography and then reversibly bonded to the gold substrate. As shown in Fig. 3a, optical interrogation of the system is accomplished by shining a broadband halogen light source from above and coupling the transmitted light into a fiber spectrometer. In Fig. 4a the transmission spectra obtained with the device through an array of holes with 550 nm periodicity for solutions of varying refractive index are shown. As can be seen the increased refractive index caused by the introduction of the sugar solution cases a red-shift of the transmission spectrum particularly at the ~ 625 nm peak. This is better quantified in Fig. 4b which plots the shift in peak transmission through a 450 nm periodicity nanohole array (which showed three transmission peaks at 604 nm, 644 nm and 674 nm) as a function of the refractive index of the glucose solution. The sensitivity of this device is reported as 333 nm per refractive index unit, or RIU [8].

Solution Phase Nanoparticle LSPR

The final example to consider here is solution phase colloidal nanoparticle LSPR. Such systems comprise of metallic particles (typically spherical, but elongated rods have also been used) dispersed in solution. As with the surface phase LSPR techniques, the nanoparticles are functionalized with a bio-recognition element specific to a target of interest. A sample is then added to the nanoparti-



Surface Plasmon Resonance Sensors, Figure 4 Sample sensitivity measurements using solutions of different refractive indices made using the nanohole SPR device shown in Fig. 2. Transmission spectra were obtained through a 450 nm periodicity array for the cases of pure water, sucrose solutions with increasing refractive index, and again for water. (**a**) Sample transmission spectra plotted together. (**b**) The relative redshift in peak wavelength for three SPR peaks (at wavelengths 606, 644, and 674 nm) exhibited by the array as a function of refractive index. Figure and caption reprinted from De Leebeeck et al. [8]

cle solution and the presence of a positive binding event results in a shift in the measured adsorption peak (for measurements done in transmission mode). Solution phase SPR methods have several advantages over surface phase techniques. The most significant of these being the relative ease with which an assay and be prepared and detection feedback received. Since the assay is carried out in solution, the additional effort required to immobilizing the particles or fabricate structures on the surface directly is not required. With regards to feedback, since the wavelength shifts can, in principle, be quite large it is sometimes possible to detect the presence of a binding event with relatively inexpensive spectrographic equipment (in some cases the shift can even be observed by eye). An additional advantage is that time required for solution phase targets to diffuse to its complementary probe is significantly lower (i. e. the diffusion timescale for a target to reach the nearest nanoparticle is much lower than that required to reach the surface) and therefore the overall reaction time is reduced. The most significant disadvantages of solution phase approach is that multiplexing is a challenge, typically only one reaction can be monitored at a time, and that in general relatively large amounts of target are required in order to ensure relatively uniform binding on all nanoparticles.

The theory which ties the observed macroscopic observation of plasmons to electromagnetics involves an expansion of the involved electromagnetic fields into a series of partial waves to obtain,

$$\sigma_{\text{ext}} = \frac{2\pi}{|k|^2} \sum_{L=1}^{\infty} (2L+1) \times \text{Re}(a_L + b_L) \tag{2a}$$

$$\sigma_{\text{scat}} = \frac{2\pi}{|k|^2} \sum_{L=1}^{\infty} (2L+1) \times (|a_L|^2 + |b_L|^2) \tag{2b}$$

where σ_{ext} and σ_{scat} are the extinction and scattering coefficients respectively, k is the wavenumber and a_L and b_L are the coefficients relating a series of Ricatti–Bessel functions involving particle size, medium refractive index, radius and complex dielectric constant of the particle (see Link and El-Sayed [9] for more details). For smaller particles when the dipole oscillations are dominant, Eq. (2a) can be simplified to,

$$\sigma_{\text{ext}} = \frac{9\omega}{c} \varepsilon_{\text{s}}^{3/2} V \left[\frac{\varepsilon_2}{(\varepsilon_1 + 2\varepsilon_{\text{s}})^2 + (\varepsilon_2)^2} \right] \tag{3}$$

where ω is the angular frequency, ε_{s} is the dielectric constant of the sensing medium, V is the volume, and ε_1 and ε_2 are the real and imaginary components of the dielectric constant of the particle (i. e., $\varepsilon_{\text{particle}} = \varepsilon_1 + i\varepsilon_2$) which are typically functions of ω. Given that ε_2 typically shows a much weaker dependence on ω than ε_1, a maximum in the extinction coefficient occurs when the magnitude of the real part of the dielectric constant of the particle (which is negative for a metal) is double that of the surrounding media.

Future Directions for Research

Though numerous label free refractive index based optical biosensor technologies exist, SPR has evolved as likely the most popular technique for monitoring surface phase binding reactions largely due to its relatively good inherent sensitivity and ease of implementation/use. Since challenges related to reaction specificity and non-specific adsorption are general to all optical biosensors, they will not be discussed in detail here (this is not meant to diminish their importance). Rather we focus here on listing some of the challenges and limitations of the technology itself and outline some of the general trends of current research.

The high sensitivity of many other optical detection technologies relates to the relatively large interaction lengths of the incident excitation field with the sample. As such a large number of binding events are required in order to induce a relatively small overall change in refractive index and rare target identification therefore becomes significantly more difficult. This is to say that while they are very sensitive to bulk measures such as refractive index, the absolute mass sensitivity can be quite poor. In ATR–SPR the reaction site can in principal be as small as the propagation distance of the plasmon wave, which is typically on the order of 20 μm. As reported above most ATR–SPR systems operate with refractive index resolutions on the order of $\Delta n = 10^{-5}$, though values on the order of $\Delta n = 10^{-8}$ have been reported, and limits of detection on the order of ng/cm^2. Given the plasmon propagation distance value listed above a crude estimate for the bulk mass limit of detection for ATR–SPR can be calculated as being on the order of 10 attograms (10×10^{-15} g). The LSPR technologies discussed were largely developed as an attempt to improve on this value since the optical energy is concentrated over a smaller spatial distance, thereby significantly reducing the probed surface area. As such the presence of significantly fewer binding events can have a larger effect on the effective refractive index and by extension the resonance shift. Using single silver nanoparticle Riboh et al. [10] demonstrated wavelengths shifts on the order of 38 nm for adsorption of ∼ 100 antibiotin molecules. Extrapolating then it can be argued that, assuming a molecular mass of 150 kDa for antibiotin, the total mass per particle is on the order of 20 zeptograms (2×10^{-17} g). Although the technology for optically probing these ultrasmall systems is reasonably well developed, practical implementation of such low mass limit of detection systems, implies an ability independently functionalize each nanostructure (or at least a small number of them) with different capture agents. One potential way to do this is to increase the spatial distance between nanotructures to the resolution achievable with traditional spotting techniques and then applying a functionalization chemistry specific to the metallic structures and not the base substrate. Increasing this spatial distance however increases the total surface area over which the sample must be delivered. This poses significant reagent delivery techniques in order to ensure that all targets from a sample have the opportunity to be interrogated by each probe site. With traditional transport mechanisms such as diffusive transport or simple microfluidic architectures, the probability of a collision between a given solution phase target and surface bound probe is exceedingly small (for practical time limits). Developing an integrated system which can address this challenge represents a significant challenge.

One limitation of existing SPR devices has been the degree to which the assays could be multiplexed (i. e., with SPR typically only a few reactions are monitored at a time, compared with microarrays where thousands of binding reactions can be monitored in parallel). Relatively recently a number of Commercial SPR biosensor developers have introduced multiplexed versions of their existing platforms (e. g., the Spreeta from Texas Instruments and FlexChip from BIACORE) based on SPR imaging techniques. Of those that which contains the highest degree of parallelity is the FlexCHIP platform. This chip uses a grating coupling mechanisms and a mechanical scanning technique to image as many as 400 reactions over the course of 3 hours (which is still orders of magnitude lower than microarray based assays). In these multiplexed systems however the sensitivity is reduced to that available from a standard microarray (see Usui-Aoki et al. [11]). As such there remains a significant need for the development of platforms which can maintain the extreme sensitivity available from SPR while pushing the limits of parallelity into the 1000 s or tens of 1000 s of binding reactions.

Cross References

► Optofluidics–Applications

References

1. Homola J, Yee SS, Gauglitz G (1999) Surface plasmon resonance sensors: review. Sens Actuators B 54(1–2):3–15
2. Unfricht DW, Colpitts SL, Fernandez SM, Lynes MA (2005) Grating-coupled surface plasmon resonance: A cell and protein microarray platform. Proteomics 5(17):4432–4442
3. Campagnolo C, Meyers KJ, Ryan T, Atkinson RC, Chen YT, Scanlan MJ, Ritter G, Old LJ, Batt CA (2004) Real-Time, label-free monitorine, of tumor antigen and serum antibody interactions. J Biochem Biophys Meth 61(3):283–298
4. Otsuki S, Tamada K, Wakida S (2005) Wavelength-scanning surface plasmon resonance imaging. Appl Opt 44(17):3468–3472
5. Homola J, Koudela I, Yee SS (1999) Surface plasmon resonance sensors based on diffraction gratings and prism couplers: sensitivity comparison. Sens Actuators B 54(1–2):16–24
6. Haes AJ, Van Duyne RP (2002) A nanoscale optical biosensor: Sensitivity and selectivity of an approach based on the localized surface plasmon resonance spectroscopy of triangular silver nanoparticles. J Am Chem Soc 124(35):10596–10604

7. Dahlin AB, Tegenfeldt JO, Hook F (2006) Improving the instrumental resolution of sensors based on localized surface plasmon resonance. Anal Chem 78(13):4416–4423
8. De Leebeeck A, Kumar LKS, de lange V, Sinton D, Gordon R, Brolo AG (2007) On-Chip Surface-Based Detection with Nanohole Arrays. Anal Chem 79(11):4094–4100
9. Link S, El-Sayed MA (2000) Shape and size dependence of radiative, non-radiative and photothermal properties of gold nanocrystals. Int Rev Phys Chem 19(3):409–453
10. Riboh JC, Haes AJ, McFarland AD, Yonzon CR, Van Duyne RP (2003) A nanoscale optical biosensor: Real-time immunoassay in physiological buffer enabled by improved nanoparticle adhesion. J Phys Chem B 107(8):1772–1780
11. Usui-Aoki K, Shimada K, Nagano M, Kawai M, Koga H (2005) A novel approach to protein expression profiling using antibody microarrays combined with surface plasmon resonance technology. Proteomics 5(9):2396–2401

Surface Potential

► Measuring Zeta Potential, Methods
► Zeta Potential Measurement

Surface Roughness Measurement

David Lee Butler
School of Mechanical & Aerospace Engineering,
Nanyang Technological University, Singapore, Singapore
mdlbutler@ntu.edu.sg

Synonyms

Surface topography; Surface texture

Definition

Surface roughness measurement is the measurement of the small-scale variations in the height of a physical surface. This is in contrast to larger scale variations such as form and waviness which are typically part of the geometry of the surface.

Overview

In recent years the importance of surface texture has gained attention in many fields. In particular the surface roughness is an important factor in determining the satisfactory performance of a workpiece in areas as diverse as tribology, surface coatings, microfluidics and biocompatibility.

Surface roughness measurement can be characterized using either quantitative or qualitative methods. Qualitative techniques include optical appearance such as the reflectivity of a surface or the strength of the machining lay as well as dragging a thumbnail across the surface as a crude tactile sensor. Quantitative analysis has evolved from simple two-dimensional profilometry to more advanced three-dimensional area analysis where information regarding surface structure can be easily obtained.

The two-dimensional quantitative approach has been in existence since the early 1930s when the need to better understand the manufacturing process necessitated the desire to characterize the surface. More recently, with the advances in computing and data storage, three-dimensional quantitative analysis has gained popularity. Three-dimensional measurement is more suited for non-contact measurement techniques due to the speed of data acquisition.

Basic Methodology

In order to quantify a surface profile, it is essential to remove the unnecessary wavelength components as well as establish a datum from which the parameters can be calculated.

Cut-Off and Filtering

Typically, a surface consists of many wavelengths all superimposed on each other. The wavelengths are generally classified into three groups, form, waviness and roughness, with the last mentioned being the shortest wavelengths and the first mentioned being the longest. To separate the waviness and form from the roughness, a cut-off filter is employed. Depending on which information is to be retained it is possible to select from high- or low-pass filters as well as a band-pass filter which extracts surface data within a specified bandwidth. The selection of cut-off length is laid down in international standards [1, 2].

A number of filter types have been used over the years, each having its own unique frequency response. The oldest standard filter is the 2RC filter and consists of two sets of a resistor and capacitor in series; however, it is subject to large errors when the surface profile direction changes abruptly. It has now been replaced with digital filters which no longer have to rely on physical components. The most common digital filters are the phase-correct 2RC filter and the Gaussian filter – the latter applies a weighting function to the surface data to establish the profile mean line.

Once the surface data have been filtered and the mean line (or plane in the case of three-dimensional measurements) has been determined it is possible to quantify the surface features. Figure 1 shows a ground surface separated into the roughness and waviness components after applying a Gaussian filter and a 0.8 mm cut-off length.


Alpha = 124° Beta = 33°
µm
5.18 µm
3 mm
3 mm
5
4.8
4.6
4.4
4.2
4
3.8
3.6
3.4
3.2
3
2.8
2.6
2.4
2.2
2
1.8
1.6
1.4
1.2
1
0.8
0.6
0.4
0.2
0
Roughness
Waviness
Alpha = 30° Beta = 50°
µm
5.21 µm
2.10 mm
2.10 mm
5
4.5
4
3.5
3
2.5
2
1.5
1
0.5
0
Alpha = 62° Beta = 48°
µm
0.767 µm
2.10 mm
2.10 mm
0.7
0.6
0.5
0.4
0.3
0.2
0.1
0

Surface Roughness Measurement, Figure 1 A ground surface being separated into its respective roughness and waviness components after application of a Gaussian filter and a 0.8 mm cut-off length, note the loss of area due to the filtering window


Z
Ra
X
Measurement Length (L)

Surface Roughness Measurement, Figure 2 The graphical definition of R_a where the absolute height variations from the mean line are summed

The oldest and most commonly used surface parameter is the average roughness (R_a) which is also known as arithmetic average (AA) and centre line average (CLA) and more mathematically as the arithmetical mean deviation of the profile. The average roughness is the area between the roughness profile and its mean line, or the integral of the absolute value of the roughness profile height over the evaluation length, as shown in Fig. 2 and defined in Eq. (1):

$$R_a = \frac{1}{L} \int_0^L \left| Z(x) \right| dx \tag{1}$$

However, the main limitation of R_a is that it provides no information about the surface shape; for example, a surface with a regular triangular wave profile could have the same R_a value as a random surface. Over the years, a considerable array of parameters has been developed to provide greater insight into the surface and its function. These parameters are typically grouped depending on what surface attribute they are concerned with such as height or spatial features or a combination of both (hybrid). An additional group which is derived from the amplitude distribution function of the profile provides information regarding the surface shape and its sharpness.

Table 1 provides a list of some of the more commonly used surface parameters with the appropriate standards as reference. The *R* prefix is used for parameters based on the roughness component of the surface while *P* refers to the original unfiltered profile and *W* is the waviness component.

For areal parameters, the main difference is that the reference datum is based on a mean plane and all parameters are calculated from that. The prefix *S* is used to denote these parameters and to distinguish them from the *R*, *P* and *W* prefixes used for profile measurement. A number of the areal parameters are direct three-dimensional equivalents of their profile counterparts such as $S_q(R_q)$ and $S_{ku}(R_{ku})$ while others take advantage of the structural information available to determine the texture direction of the surface and the strength of the surface lay.

Although the application of a single parameter for surface roughness can be used to indicate a change in a manufacturing process, it is not sufficiently discriminating to pinpoint where the changes in the process have occurred. Using an array of simple parameters rather than just one may still not provide the level of discrimination required. With the development of random process analysis, new capabilities arose with the use of autocorrelation and power spectra functions. These are functions rather than numbers such as the average roughness (R_a) of the profile and so can reveal more of the underlying statistics of the surface. The autocorrelation function is particularly useful for looking at random surfaces and the power spectrum is more useful for looking at periodic surfaces. The autocorrelation function is obtained by simply plotting the correlation coefficient between the surface profile and the same profile shifted in space by a set amount. The power spectrum is the Fourier transform of this.

Instrumentation

The earliest ways of measuring surfaces were by using the thumbnail as a tactile sensor or the eyes. Both techniques are highly effective but are completely subjective. Demand for quantitative results led to the development of two distinct branches of instrumentation, one following the tactile approach the other mimicking the eyes.

Both techniques evolved to measure different surface features. Optical methods looked for lateral structure, namely spatial information, whereas contact methods examined heights in the plane perpendicular to the surface. More recently, optical techniques have been developed which can provide height information as well. A more general form of categorization would be to classify the instruments as either contact or non-contact. The lateral and vertical resolutions of the various contact and non-contact techniques are shown in Fig. 3.



Surface Roughness Measurement, Figure 3 Lateral and vertical measurement ranges of various microscopes



Surface Roughness Measurement, Figure 4 Schematic of an inductance transducer-based stylus

Contact Instruments

The contact method involves the dragging of a diamond stylus whose tip dimension is such that it can penetrate the detailed geometry of the surface. The stylus is mounted onto an arm with a transducer at the other end as shown in Fig. 4. Any change in height of the stylus due to the surface features corresponds to a change in the signal detected and amplified by the transducer and the subsequent electronics. The most common type of transducer is based on the inductance principle and offers a large range-to-resolution as well as being of robust construction.

The main limitation of the stylus approach is the need for contact to be made between the probe and the surface which deems it unsuitable for soft materials and where contamination may be an issue. The actual tip dimensions

Surface Roughness Measurement, Table 1 Common 2D surface parameters

Parameter	Name	Standards	Related
	Height Parameters		
Ra	Roughness average (Ra)	1, 2	Pa, Wa
Rq	Root mean square (RMS) roughness	1, 2	Pq, Wq
Rt	Maximum height of the profile	1, 2	Pt, Wt
Rpm	Average maximum profile peak height	1	
Rz	Average maximum height of the profile	1, 2	Pz, Wz, Rtm
Rc	Mean height of profile irregularities	2	Pc, Wc
Rz(iso)	Roughness height	2	
Wt, W	Waviness weight	1, 2	Rt, Pt
	Spacing Parameters		
Sm, RSm	Mean spacing of profile irregularities	1, 2	PSm, WSm
Pc	Peak count (peak density)	1	
HSC	High spot count		
	Hybrid Parameters		
Δa	Average absolute slope	1, 2	PΔa, WΔa
Δq	Root mean square (RMS) slope	1, 2	PΔq, WΔq
	Amplitude Distribution Function Parameters		
Rsk, Sk	Skewness	1, 2	Psk, Wsk
Rku	Kurtosis	1, 2	Pku, Wku

also act as mechanical filter removing features smaller than the tip radius from the measurements.

Non-Contact Instrumentation

A wide range of techniques can be used to capture the surface roughness of a component using non-contact methods. Some of the more common instruments used to capture topographic data include confocal microscopy, laser triangulation, focus detection and optical interferometry. A relatively recent branch of microscopy known as scanning probe microscopy (SPM) yields over 20 other instruments which are defined based on what probe–surface interaction they are monitoring. The SPM family is described in more detail elsewhere in this book and will be briefly mentioned in this article.

Confocal Laser Scanning Microscopy

Confocal laser scanning microscopy is a valuable tool for obtaining high-resolution surface images as well as enabling three-dimensional reconstruction of the surface. In contrast to a conventional optical microscope which floods the entire specimen with light, confocal microscopy relies on point illumination. A pinhole in an optically conjugate plane in front of the detector ensures that out-of-focus information is eliminated and thus only light within the focal plane is detected resulting in a much higher quality image. As only one point is illuminated at a time in confocal microscopy, two- or three-dimensional imaging requires scanning over a regular raster (i. e. a rectangular pattern of parallel scanning lines) in the specimen. The thickness of the focal plane is defined mostly by the square of the numerical aperture of the objective lens, and also by the optical properties of the specimen and the ambient index of refraction. This technique has found widespread use for biological and semiconductor applications.

Focus Detection System

The optical focus system or optical profilometer system is based on the dynamic focusing principle of a confocal microscope. These systems work on the detection of the focus position of reflected light from the surface. Any change in the focus position of the light relates to a change in the surface height and by refocusing the lens it is possible to determine the height value. It is widely used in applications where surface damage is an issue for concern.

Optical Interferometry

Optical interferometers work on the principle of exposing the surface to be characterized to monochromatic or white light and observing the interference fringes produced using an optical flat tilted through a small angle. The fringe patterns are produced by splitting the light beam and the interference patterns are produced due to interference between reflections from the tilted optical flat and the surface to be measured. The fringe patterns are analyzed by a computer program incorporating the appropriate algorithms to give an unfiltered representation of the surface. The data may be statistically processed and filtered to provide parametric values.

Laser Triangulation

The principle of laser triangulation is essentially the measurement of range by location of three points forming a triangle. A laser spot is focused onto the sample surface, and as the surface height changes, the position of the reflected beam onto a position-sensitive detector is also shifted. This shift in the reflected beam can, using the triangulation principle, be related back to the surface height deviation.

As with most optical-based systems, a number of limitations exist which include the need for the specimen to possess some degree of reflectivity, a limitation on the maximum surface slope which can be detected and the effect of surface color change on the fidelity of the data.

Scanning Probe Microscopy

Scanning probe microscopy is a branch of microscopy that forms images using a physical probe that scans the surface of the specimen. An image is obtained by mechanically moving the probe in a raster scan of the specimen, line by line, and recording the interaction between the probe and the surface as a function of the position. A wide range of interactions can be observed depending on which phenomenon is being observed; they include atomic force, tunnel current, magnetic force and electrostatic force.

Future Directions for Research

Current research in surface roughness measurement is directed at both the hardware and the software. Established filtering techniques such as Gaussian filtering do not satisfy all applications and research is currently being undertaken to develop filters based on the wavelet principle. Instrumentation is currently being developed to overcome the limitations of current contact and non-contact techniques such as, for example, measuring the sidewalls of a microchannel. This has led to the development of more specialized probes which can sense topographic changes in more than one direction at the same time.

Cross References

- ► Roughness Effect on Microscale Transport
- ► Scanning Electron Microscopy (SEM)
- ► Surface Modification
- ► Scanning Probe Microscopy

References

1. B46.1 (2002) Surface Texture, Surface Roughness, Waviness and Lay, ASME, USA
2. ISO 4287 (1997) Geometrical Product Specifications (GPS) – Surface texture: Profile method – Terms, definitions and surface texture parameters
3. Whitehouse DJ (1994) Handbook of Surface Metrology. Taylor Francis, Institute of Physics Publishing, London

Surface Tension, Capillarity and Contact Angle

KAMRAN MOHSENI
Department of Aerospace Engineering Sciences,
University of Colorado, Boulder, CO, USA
mohseni@colorado.edu

Overview

Surface tension is important in daily life and many engineering applications. Surface tension plays a major role in many applications such as washing and cleaning procedures, in lubricants such as those used in automobiles and cosmetics, and the formation of rain drops. It is even the phenomenon that allows the water-strider to walk on water. This introductory review presents some of the basic concepts associated with surface tension and capillarity. First, we consider the mechanical and thermodynamic definition of surface tension. This is followed by capillarity, contact angle, governing interface equations, relevant nondimensional numbers with surface tension effects, capillarity rise, temperature and surfactant effects of surface tension, and dynamic contact angles. Techniques for measuring surface tension and contact angle then follow. Controlling the wettability of a surface is then presented in order to create surfaces with superhydrophobic properties. Example applications of surface tension and capillarity are briefly presented at the end.

Chemical and Physical Principles

Surface Tension

Surface tension, often represented by σ or γ, is a property of liquids arising from an imbalance in molecular cohesive forces at the surface of the liquid (see Fig. 1). The attractive forces between molecules of a liquid are often stronger than forces between the liquid molecules and the surrounding gas or another immiscible liquid. In the bulk of a liquid each molecule is pulled equally, on average,



Surface Tension, Capillarity and Contact Angle, Figure 1 Adhesive and cohesive forces on molecules of a liquid close to an interface and away from it



Surface Tension, Capillarity and Contact Angle, Figure 2 Surface tension can be considered as the work required for creating a unit surface area. In this case, the work is equal to $\gamma \delta S$ for a force equal to γl and moving a distance dx. The increment in surface area is $\delta S = l\, dx$

in all directions by neighboring liquid molecules, resulting in a net zero force. However, the situation is different at the surface of the liquid where the liquid molecules are pulled more effectively by other liquid molecules, resulting in a net inward force. As a result of higher molecular attraction between the molecules of the same liquid than the attraction to molecules of another fluid, the surface of the liquid tends to contract inward. This net inward force can be mechanically modeled by assuming an apparent elastic surface under tension. In this case, the force per unit length along the interface between the two immiscible fluids is called surface tension. Surface tension can also be interpreted as the storage of energy at the surface of a liquid: energy per unit area. Therefore, γ is the work required to create a unit area of interface (see Fig. 2). This is a more thermodynamic definition for surface tension. In this case, in order to increase the surface area of a liquid by δS, an amount of work equal to $\gamma \delta S$ is required. The SI units for surface tension are N/m (force per length) or J/m^2 (energy per area).

Water at 20° has a surface tension of 72.9 mN/m in contact with air compared with 35 mN/m for SAE 30 oil and 486.5 mN/m for mercury. Surface tension values of common liquids are listed in Table 1.

Surface Tension, Capillarity and Contact Angle, Table 1 Surface tension values for some common liquids at 20 °C

Interface	Surface tension (mN/m)
Water–air	72.9
Mercury–air	486.5
Methanol–air	22.5
Ethanol–air	22.4
Benzene–air	28.9
Water–Mercury	415
SAE 30 oil–air	35
Soap solution–air	25
Glycerin–air	63
Blood–air	58



Surface Tension, Capillarity and Contact Angle, Figure 3 A droplet on a hydrophobic surface. The static contact angle, θ_0, is set by the balance of surface tension forces in the horizontal direction

Contact Point and Line

The line that delimits the wetted portion of a surface by a liquid is called the contact line. In two-dimensional flows the contact line reduces to a point (see Fig. 3). For a static droplet, the angle of the interface between the liquid and the solid surface is called the static contact angle θ.

Capillarity

Capillary actions or capillarity is a scientific topic concerning the equilibrium shape of interfaces in contact with a solid wall; in particular, in thin tubes or capillaries. For instance, for water in a thin glass tube, the strong hydrogen-bonding interactions between the water molecules and air at the surface of the glass causes the water to climb up in the tube. These new intermolecular interactions must balance the gravity and the weight of the water column. As a result, since the weight of water in a narrow tube is less than that in a thicker one, the water will climb higher in a narrow tube. The curved free surface of the liquid in a capillary is called the meniscus.

Capillary action has major biological and engineering implications. For example, capillary actions are responsible for providing nutrients and oxygen and removing wastes and carbon dioxide from cells wherever blood flow is available. It is also the mechanism which distributes water and nutrients from plant roots to plant tissue.

Hydrophobic and Hydrophilic Surfaces

The strength of the capillary effect can be quantified by the contact angle. The rise or fall of a liquid in a small-diameter tube inserted into a liquid pool can be determined by the value of the contact angle. The contact angle for water in a glass tube is less than 90° (wetting the wall) and is more than 90° for mercury in a glass tube. In general, a nonwettable surface where the contact angle is greater than 90° is termed hydrophobic. Conversely, a contact angle less than 90° characterizes a wettable or hydrophilic surface. Surfaces with contact angles greater than 150° are called superhydrophobic. This is sometimes referred to as the "lotus effect" after the self-cleaning property of lotus plants. Water droplets roll off the leaves and cannot make them wet.

Key Research Findings

Young's Equation

The contact angle, as seen in Fig. 3, is set by the balance of surface tension forces in the horizontal direction

$$\gamma_{\mathrm{LG}} \cos\theta = \gamma_{\mathrm{SG}} - \gamma_{\mathrm{SL}} \,. \tag{1}$$

This is known as Young's equation where γ_{LG}, γ_{SG}, and γ_{SL} are the surface tension between the liquid and gas, solid and gas, and solid and liquid respectively. Young's angle is a result of thermodynamic equilibrium of the free energy at the contact point. This equation was derived by Young in 1805 shortly before its independent publication by Laplace. The same equation was also derived by Gibbs in 1906 through an energy minimization approach. By using Young's equation one can define a wetting coefficient k as

$$k = \frac{\gamma_{\mathrm{SG}} - \gamma_{\mathrm{SL}}}{\gamma_{\mathrm{LG}}} = \cos\theta \,. \tag{2}$$

Note that k has a value between 1 and -1. For hydrophilic surfaces $0 < k < 1$ or equivalently $0 < \theta < \pi/2$ and the solid is said to be wetted by the liquid. For hydrophobic surfaces $-1 < k < 0$ or $\pi/2 < \theta < \pi$ and the solid is not wetted by the liquid.

Young–Laplace Equation

A curved interface is an indicator of a pressure jump across the interface with higher pressure on the concave side. This can be easily seen in the case of a spherical droplet or bubble. For example consider the free body diagram of a droplet with radius R cut in half, as depicted in Fig. 4. The uniform surface tension along the circumference of the droplet is balanced by the pressure acting on the projected area πR^2. The balance of forces in the horizontal direction results in $(2\pi R)\gamma = (\pi R^2)\Delta P$, or $\Delta P = P_\mathrm{i} - P_\mathrm{o} = 2\gamma/R$ where P_i and P_o are the equilibrium pressure inside and outside of the droplet, respectively. In the case of a bubble, one obtains $\Delta P = P_\mathrm{i} - P_\mathrm{o} = 4\gamma/R$ since there are two layers of surface tensions: one in contact with the outside gas and one in contact with the gas inside the bubble. This simple relation can be extended to any surface with a mean curvature $\kappa = 1/R_1 + 1/R_2$, where R_1 and R_2 are the principal radii of curvature. The resulting equation is known as the Young–Laplace equation

$$\Delta P = \kappa\gamma \,. \tag{3}$$

In the absence of viscous forces, this equation provides a relationship for the change in pressure across a curved interface. It should be noted that pressure jumps across a fluid interface can only sustain normal stress jumps, they do not result in a tangential stress jump. Therefore, tangential surface stresses can only be balanced by viscous stresses associated with fluid motion. Consequently, in the absence of other effects, it is not possible to have a static system in the presence of surface tension gradient. A flow induced by a gradient in the surface tension is called Marangoni flow.

Nondimensional Numbers

Surface tension is a dominant force for liquid handling and actuation at microscales. Surface tension forces scale with a characteristic length scale L as compared with body forces (e. g. gravity) that scale as L^3, and pressure forces that scale as L^2. As a result, modifications of surface tension and other methods with similar scalings are much more effective for microdroplet transport than simple pressure-driven flow.

Consider a fluidic system with surface tension effects. The characteristic scales for length and velocity are L and U. The physical parameters are density ρ, viscosity ν, gravity g, and surface tension γ. By using the Buckingham Π theorem one can obtain three independent nondimensional groups from these six variables. An option for a set of three



Surface Tension, Capillarity and Contact Angle, Figure 4 Free body diagram of forces on a droplet cut in half

independent nondimensional numbers is

$$\mathrm{Re}=\frac{UL}{\nu}=\frac{\text{inertial forces}}{\text{viscous forces}} \tag{4}$$

$$\mathrm{Bo}=\frac{\rho g L^2}{\gamma}=\frac{\text{gravitational forces}}{\text{surface tension forces}} \tag{5}$$

$$\mathrm{Ca}=\frac{\rho \nu U}{\gamma}=\frac{\text{viscous forces}}{\text{surface tension forces}} \tag{6}$$

where Re is the Reynolds number, Bo is the Bond number, and Ca is the capillary number. The Reynolds number expresses the relative magnitude of inertial forces in the system to viscous forces. Transitions from laminar to turbulent flows are characterized by the Reynolds number. The Bond number is a measure of gravitational forces compared to surface tension forces, while the capillary number determines the ratio of viscous forces to surface tension forces.

Two other relevant nondimensional numbers can be defined as

$$\mathrm{We}=\mathrm{Ca}\times\mathrm{Re}=\frac{\rho U^2 L}{\gamma}=\frac{\text{inertial forces}}{\text{surface tension forces}} \tag{7}$$

$$\mathrm{Fr}=\frac{\mathrm{We}}{\mathrm{Bo}}=\frac{U^2}{gL}=\frac{\text{inertial forces}}{\text{gravitational forces}} \tag{8}$$

The Weber number, We, represents an index of the inertial forces to surface tension forces and it is important in analyzing thin films and the formation of bubbles and droplets. The Bond number is often used when considering static surface tension effects, while the Weber number is more relevant in unsteady and moving systems. The Froude number, Fr, compares inertial and gravitational forces. Note that all the nondimensional numbers involving surface tension are boundary-related phenomena and they enter the governing equations through boundary conditions. On the other hand, the Reynolds number is directly introduced through the Navier–Stokes equations.



Surface Tension, Capillarity and Contact Angle, Figure 5 Capillary rise in a tube. The weight of the liquid column is supported by the vertical component of surface tension forces on the tube wall

Capillary Rise

The rise or fall of a liquid interface in a capillary can be easily calculated by writing the balance of forces on a cylindrical column of height H (see Fig. 5). The water at the bottom of the tube, leveled with the free surface of the liquid, is at atmospheric pressure. The hydrostatic pressure drop just below the meniscus is balanced by the vertical component of surface tension at the wall. Therefore, $2\pi R\gamma\cos\theta=\rho g(\pi R^2 H)$. Hence, the capillary rise is given by

$$H=\frac{2\gamma}{\rho g R}\cos\theta=2\frac{\delta_c^2}{R}\cos\theta \tag{9}$$

where $\delta_c=\sqrt{\gamma/\rho g}$ is the capillary length. For nonwetting liquids $\theta>90°$ which results in a negative H. The capillary length also express the characteristic length of a meniscus; it is determined by the interplay between the Laplace and the hydrostatic pressure across an interface.

Surface Tension Variation

Surface tension values can be affected by temperature change, addition of impurities or surfactants, and, to a lesser extent, by variation in pressure and surface curvature.

Considering that surface tension is the result of cohesive forces between molecules of the same liquid, it would not be surprising to observe that by increasing the temperature (in an other words, by increasing the random kinetic energy of the liquid molecules), the surface tension is decreased. In fact, at the critical temperature, this kinetic energy is enough to break all the cohesive bonds between the liquid molecules and separate the molecules to form a gas.

The surface tension of many liquids decreases, almost linearly, with increasing temperature. In other words, the quantity $\mathrm{d}\gamma/\mathrm{d}T$ is negative and almost constant for most pure materials. A well-known relation is the Eötvös rule

$$\gamma = V^{-2/3} k (T_\mathrm{c} - T) \tag{10}$$

where V is the molar volume, k is a constant equal to $2.1\,\mathrm{erg/K}$ for most liquids, and T_c is the critical temperature. Another relationship suggested by van der Waals and further developed by Guggenheim is

$$\frac{\gamma}{\gamma_0} = \left(1 - \frac{T}{T_\mathrm{c}}\right)^n \tag{11}$$

where n is a constant equal to 11/9 for most organic liquids but may be closer to unity for most metals, and γ_0 is another constant that depends on the liquid under consideration. Note that in both equations the surface tension approaches zero at the critical temperature.

The surface tension of a material can also be greatly affected by the presence of impurities, particularly surfactants. Surfactants are surface-active agents that contain hydrophilic polar groups on their heads and hydrophobic groups on their tails. As a result, they are soluble in both water and organic solvents. In general, surfactants reduce the surface tension of a liquid. For example, surface tension of water can be greatly reduced by addition of soap or other detergents. This is used in washing processes in order to enable the liquid to penetrate cavities between fibers for more effective washing. Solutes, depending on their structure, can have different effects on surface tension. For example, sugar has no effect on surface tension of water, while inorganic salts increase surface tension, and alcohols decrease it. Surfactants will only decrease surface tension to a set limit and after that they will have no more effect. This can be explained as follows. The equilibrium value of surface tension can be decreased as the number of surfactant molecules accumulating at the surface increases. This process continues until the surface is completely covered by surfactant molecules. At this point, if the surfactant concentration is further increased the extra surfactant molecules will accumulate within the solution and form aggregates; what are called micelles. The concentration of the surfactant at which the surface is completely occupied by surfactant molecules is called the critical micelle formation concentration.

Dynamic Contact Angles

If a droplet is not in static equilibrium, the contact line might move; so too the dynamic contact angles. Figure 6 shows dynamic contact angles for a droplet moving on a inclined plate. Depending on the direction of the liquid movement, different contact angles may be observed. The contact angle measured when the contact line is in movement by wetting the solid is called the advancing contact angle, θ_A. On the other hand, the contact angle observed when the liquid is withdrawn over a pre-wetted surface is called the receding contact angle, θ_R. The advancing contact angle is always larger than or equal to the receding contact angle.

If the contact angle is a function of the speed of the contact line relative to the solid surface, one needs to consider viscous stress forces among other effects. In fact, the viscous stresses show singular behavior at the contact line [1]. The concept of contact line is a continuum concept. This concept breaks down near the surface and one requires molecular considerations in the vicinity of the contact line.

The difference between the advancing (maximum) and receding (minimum) contact angles is called the contact angle hysteresis. Hysteresis can be used to characterize surface heterogeneity, mobility, and roughness. If the sur-



Surface Tension, Capillarity and Contact Angle, Figure 6 A droplet rolling down on an inclined surface. The advancing and receding contact angles are depicted



Surface Tension, Capillarity and Contact Angle, Figure 7 Surface tension measurement. (**a**) Du Nouy ring method. (**b**) Wilhelmy plate method

face is not homogeneous, some regions might present a barrier to the movement of the contact line (pinning the contact line) and can be manifested in regions with different contact angles from the surrounding area.

Surface roughness can also generate contact angle hysteresis by actual microscopic variations in the slope of the surface.

Techniques for Measuring Contact Angle and Surface/Interfacial Tension

Correct analysis of capillary and wetting problems requires accurate knowledge of surface tension values and contact angles. In this section we will provide a brief review of methods for measuring surface tension and contact angles. The basic methods for measuring these quantities can be divided into two categories: methods for measuring dynamic quantities and methods for measuring geometrical quantities. Another classification for measuring contact angles of nonporous solids is goniometry and tensiometry. In the goniometry method, the shape of a sessile drop on a solid substrate is analyzed. In the tensiometry method, the interaction forces between a solid in contact with the test liquid are measured.

The Du Nouy Ring Method A ring with perimeter L is immersed in to a liquid and then lifted up. The maximum pull exerted on the ring by the surface tension forces is measured (see Fig. 7a). At the maximum pull the force vector will be exactly parallel to the direction of motion and the contact angle will be zero. The surface tension is then calculated from $\gamma = F_\mathrm{m}/L$, where F_m is the maximum force during the lift off. A correction for the weight of the volume of liquid lifted beneath the ring could significantly improve the accuracy of this method.

The Wilhelmy Method This is a technique that can be used for both surface/interfacial tension and contact angle measurements (Fig. 7b). To measure the surface tension, a plate with known perimeter P is attached to a balance. The plate is brought into contact with the test liquid and the force due to wetting is measured. The upward force of the surface tension must be equal to the weight of the meniscus measured by the balance. This results in $F = \gamma P \cos\theta$. This equation provides a method to measure the vertical component of surface tension. However, this provides one equation with two parameters: γ and θ. By intensive cleaning or by roughening a platinum plate one could achieve an almost zero contact angle. This results in a single measurement for calculating the surface tension. If the surface tension is known, one can employ the same equation to calculate the contact angle in the same fashion.

Capillary Rise Method In this approach a capillary tube is immersed into the liquid. The surface tension is calculated by measuring the liquid height in the capillary tube via Eq. (9). The capillary rise is also a measure of the vertical component of surface tension.

Tilted Plate Method This is a method for measuring contact angle. In this approach, a plate is immersed in the test liquid until the liquid meniscus becomes horizontal at the point of contact. The contact angle is then equal to the angle of the plate. A tilted plate can also be used for measuring dynamic contact angles. In this case, a plate with a sessile drop on top is slowly tilted until the drop begins to move. At this time, the uphill angle will be the receding contact angle and the downhill angle will be the advancing contact angle. The measurement should be done immediately before the actual droplet motion in order to avoid dynamic effects.

Pendant or Sessile Drop Method The surface tension can be easily measured by analyzing the shape of a drop. This is often done by optical means. Assuming that the drop is axially symmetric and in equilibrium (no viscous and inertial effects) the only effective forces are gravity and surface or interfacial forces. In this case, the Young–Laplace equation relates the shape of the droplet to the pressure jump across the interface. Surface tension is, then, measured by fitting the drop shape to the Young–Laplace equation. Either a pendant or a sessile drop can be used for surface tension measurement. The pendant drop approach is often more accurate than the sessile drop approach since it is easier to satisfy the axisymmetric assumption. Similar techniques can be used for measuring surface tension in a bubble.

Drop Weight Method The drop weight, or Tate's, method is yet another technique for determining surface tension. This approach relies on dripping of a liquid in a gas from a capillary and measuring the combined volumes of the primary and satellite drops that are formed. In this case one can write Tate's law for the weight of the drop

$$\rho g V = 2\pi R \gamma \tag{12}$$

where ρ is liquid density, g is the gravitational acceleration, V is the volume of the drop, and R is the drop radius. By measuring the drop volume and radius one can calculate the surface tension.

Bubble Pressure or Drop Weight Method In this approach, surface tension is calculated from the measurement of pressure inside the bubble or from the weight of the drop when it detaches from an orifice. The gas bubble can be introduced into a liquid through a capillary with known radius. The maximum pressure p_m during this process is recorded and used to calculate the surface tension. At the maximum pressure, the gas bubble radius is the same as the capillary with the gas bubble forming an exact hemisphere. If the hydrostatic pressure is p_0, and the inner radius of the capillary is R, the surface tension is calculated from the equation

$$\gamma = \frac{p_\mathrm{m} - p_0}{2} R \tag{13}$$

After the maximum pressure measurement, the bubble radius increases while the pressure drops. The bubble finally detaches from the capillary and rises to the surface.

Superhydrophobicity

Controlling the wettability of a surface is crucial in many industrial applications. Surfaces with water contact angles above 150° are called superhydrophobic. Such surfaces are important because they could have anti-contamination, anti-sticking, and self-cleaning properties. In nature, superhydrophobic surfaces are observed in lotus leaves, cicada orni wings, and water-strider legs. Water droplets easily roll off such surfaces at a small sliding angle and hereby remove contaminants from the surface.

The high contact angle in superhydrophobic surfaces is often called the apparent contact angle since it does not represent the actual contact angle value of the droplet on a flat surface. The superhydrophobic surfaces are usually covered with micro- or nanoscale roughness. As depicted in Fig. 8 the water can penetrate the gap between the spikes on a surface (Wenzel state) or stay in a suspended state above the spikes (Cassie–Baxter state). In either case a higher contact angle is observed than that observed on a flat surface. In the case where the liquid does not enter the roughness, a drop is supported on a patchwork of solid and gas, which leads to very high contact angles. Furthermore, the gas trapped below the drop homogenizes the solid surface and results in very low contact angle hysteresis. Superhydrophobic windshields are nowadays used for better visibility during rain conditions. The water-repellent coated glass enables windshields to shed rain without the need for windshield wipers. If the spatial scale of the roughness is small compared to the wavelength of light the texture does not affect the optical transparency of the windshield.



Surface Tension, Capillarity and Contact Angle, Figure 8 Effect of surface structures on wetting behavior. (**a**) Wenzel's model where the liquid penetrates between the structures. (**b**) Cassie–Baxter model where water does not wet the surface between the structures

In the Wenzel model, the apparent contact angle θ_W is obtained by correcting the Young's contact angle θ with a roughness correction factor r

$$\cos\theta_\mathrm{W} = r \frac{\gamma_\mathrm{SG} - \gamma_\mathrm{SL}}{\gamma_\mathrm{LG}} \,. \tag{14}$$

The roughness factor is defined by the actual surface area divided by the projected surface area. Therefore, for a rough surface $r > 1$. Following Wenzel's equation, surface roughness results in enhancing both hydrophobicity and hydrophilicity depending on the nature of the corresponding flat surface. Therefore, for a truly hydrophobic surface $\theta_\mathrm{W} > \theta > 90°$ and for a truly hydrophilic surface $\theta_\mathrm{W} < \theta < 90°$. For surface roughness factors greater than 1.7, the droplet will have a hard time to wet all the grooves and the system switches from a Wenzel model to a Cassie–Baxter model. In this case, the droplet is suspended on top of the grooves, where the gas is trapped. The apparent contact angle can be calculated from Cassie's law for a liquid on a composite surface

$$\cos\theta_\mathrm{C} = f_1 \cos\theta_1 + f_2 \cos\theta_2 \tag{15}$$

where θ_1 is the Young contact angle for component 1 with surface fraction f_1 and θ_2 is the Young contact angle for component 2 with surface fraction f_2. Note that $f_1 + f_2 = 1$. For a two-component system consisting of an air component with a contact angle of 180° the equation is reduced to

$$\cos\theta_C = f(\cos\theta + 1) - 1 \quad (16)$$

after dropping the second index. This equation implies that it is possible to create surfaces with very large apparent contact angles if the surface has small f and large true contact angle θ. The lotus effect is based on this principle. Note that for a given surface with a true contact angle θ, the apparent contact angle in the Cassie–Baxter model is a function of f only.

Examples of Applications

Some of the industrial applications of surface/interfacial tension and capillarity are: in soil mechanics where the penetration of liquids into porous rocks are considered; in anti-fog, anti-frost, or anti-stain treatment of glass for enhanced visibility in harsh environments; in the chemical industry for uniform spreading of paints, insecticides, ink, and coloring ingredients; in the construction industry for waterproofing of concrete; and in creating fuel spray in internal combustion engines. In the life sciences, locomotion of insects on water surfaces; the rise of sap in plants; adhesion of parasites on wet surfaces; and wetting of eye (an eye is normally wet while the cornea is by nature hydrophobic). Surface tension is also a dominant force at the microscale. To this end, surface tension and its manipulation play a major role in most microfluidic and Lab-on-a-Chip devices. Capillarity is a significant part of capillary liquid chromatography, capillarity electrophoresis, and flow cytometry. Micropipettes work based on the same principle. Surface tension also plays a significant role in applications where the formation of jets and drops are considered.

Further Reading

Some general references for surface and interfacial phenomenon are the books by Adamson and Gast [2] and Hiemenz and Rajagopalan [3]. An interesting scientific background to molecular and macroscopic properties of soap films and bubbles is provided in [4]. The fluid dynamics, heat transfer, and mass transfer of single bubbles, drops, and particles are covered in [5].

References

1. de Gennes PG (1985) Wetting: Statistics and dynamics. Rev Mod Phys 57(3):827–863
2. Adamson AW, Gast AP (1997) Physical Chemistry of Surfaces, 7th edn. Wiley, New York
3. Hiemenz PC, Rajagopalan R (1997) Principles of Colloid and Surface Chemistry, 3rd edn. Dekker, New York
4. Isenberg C (1992) The science of soap films and soap bubbles. Dover, New York
5. Clift R, Grace JR, Weber ME (2005) Bubbles, drops, and particles. Dover, New York

Surface Tension-Confined Confined Microfluidics

► Surface-Directed Capillary Flow Systems

Surface Tension Driven Filling

► Capillary Filling

Surface Tension Driven Flow

SUMAN CHAKRABORTY
Department of Mechanical Engineering, Indian Institute of Technology, Kharagpur, India
suman@mech.iitkgp.ernet.in

Synonyms

Capillary flow; Wetting phenomenon

Definition

Surface tension driven flow concerns the actuation and control of fluid dynamic transport through a manipulation of the surface tension forces. The manipulation, in principle, can be hydrodynamic, thermal, chemical, electrical or optical in nature. It is also important to mention here that there must be a free surface or a liquid–fluid interface in order to have a surface tension driven flow

Surface tension (γ) is a force per unit length that acts along the interfaces of immiscible phases. For illustration, one may refer to the instance of a liquid–gas interface, the molecules located on which experience a net cohesive force that is directed towards the bulk of the liquid and away from the interface, because of the denser molecular packing in the liquid phase than in the gas phase and a consequent stronger intermolecular force of attraction offered by the liquid molecules. Thus, the interface appears to be in a kind of tension. The interface also must possess necessary energy that overcomes the net attractive force towards the liquid side and allow the interface to sustain. This energy per unit interfacial area is also known as the surface energy.

Overview

It is well known that as the length scale of a system is reduced, surface tension effects become progressively more important, as compared to the other forces that are conventionally dominant over macroscopic length scales. This is primarily because of the fact that the surface tension force scales down only linearly with the length scales whereas most other forces scale down with higher powers of the same. Thus, surface tension, which is a negligibly weak force in the macro domain, may eventually become a dominant force in the micro and nano domains.

From a fluid mechanics viewpoint, the presence of an interface creates a jump in pressure. To appreciate the underlying physical picture from a fundamental viewpoint, let us begin with the thermodynamic description of a liquid droplet in terms of its free energy, as

$$E = \sum_{i \neq j} A_{ij}\gamma_{ij} - \lambda \forall \tag{1}$$

where $\forall$ is the droplet volume and λ is a Lagrange multiplier to enforce a constant volume constraint (physically, λ is equal to the pressure drop across the liquid–vapour interface, thermodynamically consistent with the definition of free energy of a system). Here A_{ij} is the interfacial area that demarcates the phases i and j, with the corresponding surface energy being designated as γ_{ij}. In this article, the subscripts 'l', 's' and 'v' will be employed to represent the liquid, solid and vapour phases, respectively. It can also be noted that if A_{ls} is increased by some amount, A_{sv} is decreased by the same amount. The evaluation of free energy of the droplet, in accordance with Eq. (1), can be best illustrated through the example of a spherical droplet with an equilibrium contact angle θ (refer to Fig. 1 of the article on ► electrocapillary), for which one can write: $A_{\text{sl}} = \pi R^2 \sin^2\theta$, $A_{\text{lv}} = 2\pi R^2(1-\cos\theta)$, $\forall = \pi R^3\left(\frac{2}{3} - \frac{3}{4}\cos\theta + \frac{\cos 3\theta}{12}\right)$. Thus, for a spherical droplet

$$E = \underbrace{\pi R^2 \sin^2\theta\,(\gamma_{\text{ls}} - \gamma_{\text{sv}}) + \gamma_{\text{lv}} 2\pi R^2(1-\cos\theta)}_{\text{f}} - \lambda \left\{ \underbrace{\pi R^3\left(\frac{2}{3} - \frac{3}{4}\cos\theta + \frac{\cos 3\theta}{12}\right)}_{\text{g}} - k \right\} \tag{2}$$

where k is the volume of the droplet. For minimization of E, one must have $\partial E/\partial\theta = 0$ and

$$\frac{\partial E}{\partial R} = 0\,, \quad \text{which implies}$$

$$\frac{\partial f}{\partial \theta}\frac{\partial g}{\partial R} = \frac{\partial f}{\partial R}\frac{\partial g}{\partial \theta}\,. \tag{3}$$

Performing the necessary algebra and simplifying, it follows from Eqs. (3) and (4) that

$$\cos\theta = \frac{\gamma_{\text{sv}} - \gamma_{\text{sl}}}{\gamma_{\text{lv}}}\,. \tag{4}$$

When $0 \leqslant \theta \leqslant 90°$, the liquid is termed as partially wetting, or equivalently, the solid substrate is characterized as hydrophilic. When $\theta > 90°$, the liquid is non-wetting and the substrate is termed as hydrophobic. The case $\theta = 0$, a very special one, represents a theoretically complete wetting. Equation (4), also known as the 'Young's Law', can be interpreted as a balance between the horizontal components of all the forces that act on the 3-phase contact line (refer to Fig. 2 of the article on ► electrocapillary). The vertical component of this resultant force, on the other hand, is balanced by the normal stress in the rigid solid substrate. Further, substituting the value of $\cos\theta$ from Eq. (4), one may calculate a value of the parameter $\lambda(=\Delta p)$, as

$$\Delta p = \frac{\partial f/\partial\theta}{\partial g/\partial\theta} = \frac{2\gamma_{\text{lv}}}{R}\,. \tag{5}$$

For a droplet of a more general shape, Eq. (5) can be generalized as

$$\Delta p = \gamma_{\text{lv}}\left(\frac{1}{r_1} + \frac{1}{r_2}\right)\,, \tag{6}$$

where r_1 and r_2 are the two principal radii of the curvature of the droplet surface. It is important to note here that the Eqs. (4) and (6) are the two necessary conditions for equilibrium but not sufficient, since in addition, the second variation of E must also be positive for a minimization of the same. In fact, in presence of complex surfaces, certain morphologies may, indeed, result in unstable droplets, even though the necessary conditions of equilibrium are satisfied.

The celebrated Young's equation, as described by (4), is somewhat restricted in nature in a strict sense, since it neglects the bulk internal forces within the droplet that might generate due to gravity, electric field etc. In an effort to generalize the underlying mathematical description, one may note that, for equilibrium of a spherical droplet

$$\mathrm{d}E(R,\theta) = 0\,, \tag{7}$$

which implies

$$\frac{\partial E}{\partial R}\mathrm{d}R + \frac{\partial E}{\partial \theta}\mathrm{d}\theta = 0\,. \tag{7a}$$

Further, since $\forall = \pi R^3\left(\frac{2}{3} - \frac{3}{4}\cos\theta + \frac{\cos 3\theta}{12}\right)$, the condition of $\mathrm{d}\forall = 0$ implies that

$$\mathrm{d}R - Rf_1(\theta)\,\mathrm{d}\theta = 0\,, \tag{8}$$

where

$$f_1(\theta) = \frac{-2\cos^2\frac{\theta}{2}\cot\frac{\theta}{2}}{2+\cot\theta}\,. \tag{8a}$$

Substituting Eq. (8a) in Eq. (7a), one finally gets

$$\frac{\partial E}{\partial R}Rf_1(\theta) + \frac{\partial E}{\partial \theta} = 0\,. \tag{9}$$

Incorporating the effects of gravitational potential energy in the expression for E, one can write

$$E = \underbrace{R^2\left[2\pi\gamma_{\mathrm{lv}}(1-\cos\theta) + \pi\sin^2\theta(\gamma_{\mathrm{ls}} - \gamma_{\mathrm{sv}})\right]}_{\text{contribution from interfacial terms}} + \underbrace{R^4\frac{2\pi}{3}\rho g(3+\cos\theta)\sin^6\left(\frac{\theta}{2}\right)}_{\text{contribution from gravity}}\,. \tag{10}$$

Utilizing the above expression for E in Eq. (9), one can arrive at a more generalized form of the Young equation incorporating gravity effects, as

$$\cos\theta - \frac{\gamma_{\mathrm{sv}} - \gamma_{\mathrm{sl}}}{\gamma_{\mathrm{lv}}} - \frac{\rho g R^2}{\gamma_{\mathrm{lv}}}\left[\frac{\cos\frac{\theta}{3} - \cos 2\theta}{12} - \frac{1}{4}\right] = 0\,. \tag{11}$$

From Eq. (11), following two important observations may be carefully noted:

1. With gravity effects, θ depends on R, unlike the case without gravity.
2. If $\rho g R^2/\gamma_{\mathrm{lv}}$ is small, gravity effects can safely be neglected. This ratio is known as the Bond number (Bo), which essentially compares the square of the system length scale (R) with the square of a characteristic length scale, l_{s}, that depicts the relative contributions of surface tension and gravity influences, as $l_{\mathrm{s}} = \gamma_{\mathrm{lv}}/\rho g$. For Bo $\leqslant 10^{-3}$, gravity effects can safely be neglected, as appropriate to many of the micro-scale transport processes.

The preliminary understanding of pressure jump across a static meniscus with constant surface tension effects (refer to Eq. 6) can be more fundamentally extended to write a generalized expression for the interfacial condition on a mobile phase boundary, as [1]

$$\left[p^{(2)} - p^{(1)} + \gamma\left(\frac{1}{r_1} + \frac{1}{r_2}\right)\right]n_i = \left[\mu^{(2)}\left(\frac{\partial u_i^{(2)}}{\partial x_k} + \frac{\partial u_k^{(2)}}{\partial x_i}\right) - \mu^{(1)}\left(\frac{\partial u_i^{(1)}}{\partial x_k} + \frac{\partial u_k^{(1)}}{\partial x_i}\right)\right] \times n_k - \frac{\partial\gamma}{\partial x_i} \tag{12}$$

where $p^{(1,2)}$, $\mu^{(1,2)}$, $u_i^{(1,2)}$, $u_k^{(1,2)}$ are the pressures, viscosities and velocity components, respectively, in phases 1 and 2, $n_i\ (i = 1,2,3)$ are the components of the unit vector normal to the interfaces and directed into the interior of phase 1, and a summation over the repeated index, k, is assumed. To account for the effects of surface-active elements (surfactants), right hand side of Eq. (12) may be provided with phenomenological source terms of the form

$$-\mu_{\mathrm{s}}\delta_{ik}\frac{\partial^2 u_k^{(s)}}{\partial x_i \partial x_k} \tag{13}$$

where δ_{ik} is the Kronecker delta, $u_k^{(s)}$ are the components of surface motion velocity and μ_{s} is the so-called surface viscosity (a phenomenological constant), which characterizes the dynamical elasticity of the insoluble surface film. In a strict sense, Eq. (13) accounts for the energy dissipation in the surface layer due to irreversibilities associated with the viscous motion of adsorbed particles on the surfaces.

Basic Methodology

Marangoni Effects and Thermocapillary Motion

Fundamental principles associated with surface tension driven flows rely on the motion induced by the variation of surface tension from point to point on a mobile phase boundary, giving rise to tangential strains on the same. According to the boundary condition given by Eq. (12), the presence of tangential strains at the interface is accompanied by fluid motion. Fluid motion induced by the tangential gradients of surface tension is classically known as the Marangoni effect. As an illustration specific to microflow actuations with the aid of thermally-activated surface tension gradients, we consider the steady thermocapillary migration of a gas bubble [2] of fixed volume in a tube of radius a, filled with a liquid of viscosity μ, surface tension γ, density ρ, thermal diffusivity α and temperature coefficient of surface tension $\gamma_{\mathrm{T}} = -\mathrm{d}\gamma/\mathrm{d}T$. Viscosity and the conductivity of the gas are neglected in comparison to those of the liquid and the length of the bubble is taken to be much larger than the radius of the tube. The temperature gradient imposed on the tube wall is a constant, say β. The variation of interfacial tension as a function of temperature generates a thermocapillary shear stress, inducing the bubble motion at a steady speed towards the hotter region. The liquid is taken to be perfectly wetting. A thin layer of liquid separates the bubble from the tube wall. The three important non-dimensional numbers charecterizing the bubble motion are the Bond number ($\mathrm{Bo} = \rho g a^2/\gamma$), Péclet number ($\mathrm{Pe} = \mathrm{Re}.\mathrm{Pr}$, where Re is the Reynolds number and Pr is the Prandtl number) and capillary number ($\mathrm{Ca} = \mu u_\mathrm{b}/\gamma$), where u_b is the characteristic axial speed of the bubble. For the mathematical analysis, all these non-dimensional numbers are taken to be small. A small Bond number implies that the gravity effects are negligible and the bubble is symmetrically located within the tube. A small Péclet number implies that the advective in the temperature variations are negligible. For small Ca, one can subdivide the flow around the bubble in five different regimes, namely, (I) a section parallel to the wall with constant film thickness (say, b), (II, III) two sections of constant curvature hemispherical caps in the front and in the back, which are connected to the constant film-thickness region through two transient regions at the two ends (IV, V) over which the curvature smoothly varies from zero to a constant value. A small Reynolds number ($\mathrm{Re} = \rho_\mathrm{a} u_\mathrm{b} a/\mu$) assumption allows one to use a lubricating film assumption in the transition regions. With small Capillary numbers, it is also implicit that there are no significant fluid dynamic forces in the regions near the hemispherical caps (since surface tension forces dominate over viscous forces, which in turn dominate over inertia forces for low Reynolds numbers). For the section of the bubble parallel to the wall (section I), one can obtain the maximum velocity at the edge of the thin film of thickness b, analogous to the situation of a shear-driven Couette flow, as

$$U_\mathrm{T} = \frac{\gamma_\mathrm{T} \beta b}{\mu} \tag{14}$$

where the shear stress, τ, is balanced by the Marangoni stress due to temperature gradient (i. e., $\partial\gamma/\partial x = (\partial\gamma/\partial T)(\partial T/\partial x) = -\gamma_\mathrm{T}\beta$). The velocity U_T, however, is unknown, since the film thickness (b) is not known a-priori. In the transition region, the governing equations of fluid flow, in a reference frame fixed with the bubble, can be written as

$$\frac{\partial^2 u}{\partial y^2} = \frac{1}{\mu}\frac{\partial p}{\partial x} \tag{15}$$

subject to the following boundary conditions:

$$u = -U_\mathrm{b} \text{ at } y = 0 \text{ and } \tau = \mu\frac{\partial u}{\partial y} = -\gamma_\mathrm{T}\beta \text{ at } y = h(x) \tag{15a}$$

where u is the liquid velocity in the moving reference frame, x is the axial direction of motion, y is the transverse direction and $h(x)$ is the film thickness. A solution for Eq. (15) can be obtained as

$$u(x, y) = \frac{1}{2\mu}\frac{\partial p}{\partial x}y^2 + \frac{1}{\mu}\left(\frac{\partial\gamma}{\partial x} - \frac{\partial p}{\partial x}h\right)y - U_\mathrm{b}\,. \tag{16}$$

The pressure gradient is related to γ by setting right hand side of Eq. (12) to zero and substituting the expressions of radii of curvature in terms of the geometrical parameters of the surface profile (noting that $\frac{1}{R_1} = \frac{\mathrm{d}^2 h}{\mathrm{d}x^2} / \left[1 + \left(\frac{\mathrm{d}h}{\mathrm{d}x}\right)^2\right]^{\frac{3}{2}}$, where the denominator can be neglected relative to the numerator for small curvature, and $R_2 \to \infty$), one obtains

$$\frac{\partial p}{\partial x} = -\gamma\frac{\mathrm{d}^3 h}{\mathrm{d}x^3}\,. \tag{17}$$

The differential equation for the free surface location can be derived by noting that the flux across any cross section needs to be a constant, which mathematically implies $\int_b^{h(x)} u(x, y)\,\mathrm{d}y = 0$, in the moving reference frame. Also noting that $\frac{\partial p}{\partial x} = 0$ at $y = b$, one can utilize Eq. (16) and (17) to evaluate the above integral and obtain

$$\frac{\gamma}{3\mu}h^3\frac{\mathrm{d}^3 h}{\mathrm{d}x^3} - \frac{\gamma_\mathrm{T}\beta}{2\mu}\left(h^2 - b^2\right) - U_\mathrm{b}(h - b) = 0\,. \tag{18}$$

It is interesting to note that Eq. (18) explicitly takes care of the fact that $h \to b$ when the film becomes flat, or in other words, it takes care of an asymptotic matching of the solution in the constant film-thickness region. For an asymptotic matching with the hemispherical cap, one may use a new set of dimensionless coordinates (refer to Fig. 1)



Surface Tension Driven Flow, Figure 1 Dimensionless coordinates for the description of thermocapillary flow around a liquid–vapour meniscus such that $\eta = h/b$, $\zeta = x/b\,(3\mathrm{Ca})^{-\frac{1}{3}}$. These rescalings cast Eq. (18) in a modified Landau–Levich form, as

$$\eta^3 \frac{\mathrm{d}^3\eta}{\mathrm{d}\zeta^3} - \frac{U^*}{2}\left(\eta^2 - 1\right) - (\eta - 1) = 0 \tag{19}$$

where $U^* = U_\mathrm{T}/U_\mathrm{b} = \gamma_\mathrm{T}\beta b/\mu U_\mathrm{b}$, which is an unknown parameter. However, given a value of U^*, it is possible to integrate Eq. (19) numerically, with specified sets of initial conditions. When η is very close to unity, Eq. (19) can be linearized to obtain

$$\frac{\mathrm{d}^3\eta}{\mathrm{d}\zeta^3} = \left(1 + U^*\right)(\eta - 1) \tag{20}$$

which has the following general solution [2]:

$$\begin{aligned}\eta &= 1 + A\exp\left(\left(1 + U^*\right)\zeta\right)\\ &\quad + B\exp\left(-\frac{1}{2}\left(1 + U^*\right)\zeta\right)\cos\left(\frac{\sqrt{3}}{2}\left(1 + U^*\right)\zeta\right)\\ &\quad + C\exp\left(-\frac{1}{2}\left(1 + U^*\right)\zeta\right)\sin\left(\frac{\sqrt{3}}{2}\left(1 + U^*\right)\zeta\right)\end{aligned} \tag{21}$$

where A, B and C are constants of integration. The asymptotic behaviour of the solution as $\eta \to \infty$ can be used by applying the perturbation theory over Eq. (21) to yield [2]

$$\begin{aligned}\eta &= \frac{1}{2}C_0\zeta^2 + C_1\zeta + C_2 - \frac{U^*}{C_0}\left(\zeta\ln|\zeta| - \zeta\right)\\ &\quad + \frac{U^{*2}}{2C_0^3}\ln^2|\zeta| + \left(\frac{U^{*3}}{2C_0^3} - \frac{C_1U^*}{C_0^2}\right)\ln|\zeta|\\ &\quad + O\left(\frac{\ln^2|\zeta|}{\zeta}\right).\end{aligned} \tag{22}$$

The coefficients C_0, C_1 and C_2 are determined from the numerical solution for large values of ζ. The constant C_0 (related to the curvature of the end caps) can be determined as the limiting value of the second derivative for large η. When $U^* = 0$, the asymptotic form simplifies to $C_0 = 0.643$ [2]. In general, C_0 is a monotonically increasing function of U^*, as can be obtained numerically. Another matching condition can be obtained by noting that the mean curvature of the caps equals $2/a$ for the leading order approximation for small Ca, which implies

$$h_\mathrm{xx} \approx \frac{1}{a}, \text{ or } \frac{(3\mathrm{Ca})^{\frac{2}{3}}}{b}\eta_{\zeta\zeta} \approx \frac{1}{a}. \tag{23}$$

From the above considerations, one gets

$$\eta_{\zeta\zeta} \approx \frac{b}{a(3\mathrm{Ca})^{\frac{2}{3}}}, \text{ or } C_0\left(U^*\right) \approx \frac{b}{a(3\mathrm{Ca})^{\frac{2}{3}}}. \tag{24}$$

Further, from the considerations of global mass balance, one may note that the rate of volume of fluid pumped by the Marangoni stress, Q_1, must be same as the rate of volume displaced by the moving bubble, Q_2. Since $b \ll a$, one can neglect $O(b/a)$ terms and approximate Q_1 as

$$Q_1 = 2\pi\int\limits_{a-b}^{a} U_T(a - r)r\,\mathrm{d}r \approx \frac{-\pi\gamma_T\beta a}{\mu}\frac{b^2}{a^2}. \tag{25}$$

Similarly,

$$Q_2 = \pi U_b(a - b)^2 \approx \pi U_b a^2. \tag{26}$$

Since $Q_1 = -Q_2$, one may write

$$\mathrm{Ca} = \frac{\mu U_b}{\gamma} = \frac{\gamma_T\beta a}{\gamma}\frac{b^2}{a^2}. \tag{27}$$

Equation (27) can be used with Eq. (24) to express $C_0(U^*)$ as a sole function of b/a, in the asymptotic matching condition. With $C_0(U^*)$ already being obtained numerically, the ratio of b/a can therefore be obtained from Eq. (24), for a given value of $\Delta\gamma^* = \Delta\gamma/\gamma = \gamma_\mathrm{T}\beta a/\gamma$ (which is the ratio of the thermocapillary force to the mean surface tension force). The numerical results can be fitted with the following power law expression [2]:

$$\frac{b}{a} = 13.591\Delta\gamma^{*^2} \tag{28a}$$

and

$$\mathrm{Ca} = 184.715\Delta\gamma^{*^5}. \tag{28b}$$

One can observe from Eq. (28b) that higher temperature gradients may cause the bubble to move faster. The solutions presented above, however, are rather approximate and are valid for vanishingly small Capillary numbers only.

Electrocapillary Flow

Similar to the thermocapillarity (where temperature gradient creates the driving surface tension force), one can also exploit the effects of electrocapillarity or electrowetting, in which electric potentials can be employed to alter the surface tension and thereby cause a fluid motion. Compared to the thermocapillary flows, electrocapillary flows are much more energy efficient, with a much faster speed of operation (speeds more than 100 mm/s have been successfully achieved by electrowetting action, in contrast to a typical speed of only about 1 mm/s in thermocapillary flows). The electrocapillary principles are all based on the fact that the surface tension occurs to be a strong function of the electrical potential acting across an interface. As a consequence, the apparent contact angle, θ, gets modified from its value at zero voltage, θ_0, in the following form:

$$\cos\theta = \cos\theta_0 + \frac{cV^2}{2\gamma_{\mathrm{lv}}} \tag{29}$$

where c is the capacitance of the interface per unit area and V is the interface potential. Based on this fundamental principle, one can design various flow actuating mechanisms such as continuous electrowetting (employing liquid metal droplets in a filler liquid and exploiting the electric double layer potential to alter the liquid/liquid interfacial tension), electrowetting (employing liquid droplets in a vapour medium and exploiting the electric double layer potential to alter the solid/liquid interfacial tension), and electrowetting on dielectrics (employing liquid droplets in a vapour medium and exploiting the potential across a dielectric layer to alter the liquid/liquid interfacial tension), the details of which are outlined in the article on ► electrocapillary. It is important to note here that Eq. (29) can be obtained as a generalization of the Young's equation, by noting that there is an additional electrostatic contribution (E_{el}) to the free energy, which, for the case of electrowetting on dielectrics as an example, can be written as

$$E_{\mathrm{el}} = -\frac{1}{2}\frac{\varepsilon_{\mathrm{d}}}{d}V^2 A_{\mathrm{sl}} \tag{30}$$

where ε_{d} is the permittivity of the dielectric layer and d is its thickness. For a spherical droplet, $A_{\mathrm{sl}} = \pi R^2 \sin^2\theta$. Thus, the total interfacial energy for this case is given as

$$E(R,\theta) = R^2\left[\pi \sin^2\theta\,(\gamma_{\mathrm{ls}} - \gamma_{\mathrm{sv}}) - \frac{\varepsilon_{\mathrm{d}}V^2}{2d} + 2\pi\gamma_{\mathrm{lv}}(1-\cos\theta)\right]. \tag{31}$$

Minimizing $E(R,\theta)$ for a constant droplet volume, one can arrive at the Young-Lippman equation:

$$\cos\theta = \frac{\gamma_{\mathrm{sv}} - \gamma_{\mathrm{sl}}}{\gamma_{\mathrm{lv}}} - \frac{\varepsilon_{\mathrm{d}}V^2}{2\gamma_{\mathrm{lv}}d}. \tag{32}$$

It is important to note here that although fairly general, the above analysis is not strictly valid for apolar liquids (for example, silicone oil at the top of a conducting solid substrate). In such cases, the droplet may be modeled as an insulator with a permittivity of ε_{l}. The electrical energy stored in that case can be estimated as $1/2\varepsilon_{\mathrm{l}}R^3(V/R)^2 a_{\mathrm{de}}(\theta)$, where $a_{\mathrm{de}}(\theta)$is a shape factor, which cannot be computed analytically, but can be numerically fitted as [3]

$$a_{\mathrm{de}}(\theta) \approx 0.0592 + 0.0012\theta + 0.0022\tan(1.71-\theta). \tag{33}$$

In this situation, a generalized Young equation can be arrived at by applying the energy minimization principle, to obtain

$$\cos\theta - \frac{\gamma_{\mathrm{sv}} - \gamma_{\mathrm{sl}}}{\gamma_{\mathrm{lv}}} + \frac{\varepsilon_{\mathrm{l}}V^2}{2\gamma_{\mathrm{lv}}R}\,\frac{2+\cos\theta}{2\pi\sin\theta} \times \left[a_{\mathrm{de}}(\theta) f_1(\theta) + \frac{da_{\mathrm{de}}}{d\theta}\right] = 0. \tag{33a}$$

Solutal Gradient Originated Surface Tension Driven Flow

Other than due to the imposed gradients of temperature and electrical potential, surface tension gradients can spontaneously originate as a consequence of droplet splitting or coalescence, mixing of samples or chemical reactions. Typically, surface tension gradients generated during the contact of dissimilar liquids are much larger than those obtained as a consequence of thermocapillary variations. Deposition of biological liquids containing surface active elements onto a liquid film with higher γ_{lv} generates Marangoni stresses, which can cause rapid thinning and rupture of films. For an interface containing surface-active molecules, the surface tension is likely to vary with the local concentration, giving rise to a tangential stress, τ, as

$$\tau = \nabla_{\mathrm{s}}\gamma_{\mathrm{lv}} = \left(\frac{d\gamma_{\mathrm{lv}}}{d\Gamma}\right)\nabla_{\mathrm{s}}\Gamma \tag{34}$$

where $\Gamma(\boldsymbol{x},t)$ is the surfactant surface-concentration, which is governed by the following advection-diffusion equation:

$$\frac{\partial\Gamma}{\partial t} + \nabla_{\mathrm{s}} \bullet (\Gamma\boldsymbol{u}_{\mathrm{s}}) + \Gamma\,(\nabla_{\mathrm{s}} \bullet \boldsymbol{n})\,(\boldsymbol{u} \bullet \boldsymbol{n}) = D_{\mathrm{s}}\nabla_{\mathrm{s}}^2\Gamma. \tag{35}$$

The flux of the surfactant depends on the tangential component of the surface velocity, $\boldsymbol{u}_{\mathrm{s}} = \left(\underline{\underline{I}} - \boldsymbol{nn}\right).\boldsymbol{u}$, the mean curvature of the interface, $\nabla_{\mathrm{s}} \bullet \boldsymbol{n}$, and the surfactant surface diffusion coefficient, D_{s}. Soluble surfactants require the specification of the interfacial adsorption/desorption kinetics relating the surface concentration, Γ, to the bulk concentration, C, for which the governing transport equation is as

$$\frac{\partial C}{\partial t} + \boldsymbol{u} \bullet \nabla C = D_{\mathrm{B}} \nabla^2 C \tag{36}$$

where D_{B} refers to the bulk diffusion coefficient. Further, for thin film flows on a flat substrate, the variation of liquid thickness is determined from the following equation:

$$\frac{\partial h}{\partial t} - \nabla \bullet \left(\frac{h^3}{3\mu} \nabla p - \frac{h^2}{2\mu} \nabla \gamma_{\mathrm{lv}} \right) = 0\,. \tag{37}$$

Equations (35), (36) and (37) can be combined together to depict the dependence of the surface tension on the surfactant concentration and the surface velocity, $\boldsymbol{u}_{\mathrm{s}} = (h \nabla \gamma_{\mathrm{lv}} / \mu) - h^2 \nabla p / (2\mu)$.

Capillary Spreading

Another variant of the surface tension driven flow that is of potential interest to the microfluidics research community is the capillary spreading phenomenon. Of particular interest can be the spreading of liquids on rough homogeneous substrates or on heterogeneous substrates with hydrophobic and hydrophilic stripes. For smooth homogeneous substrates, the radial advancement of a liquid of volume ∀ has been observed by Tanner [4] as

$$r\,(t) \sim \left(\frac{\gamma}{\mu} \forall^3 t \right)^{\frac{1}{10}} \tag{38}$$

which shows a rather weak dependence on time. However, careful analysis has revealed that a thin precursor film advances at a rate proportional to $\sqrt{t}$, following standard diffusion dynamics.

To illustrate the flow behaviour during capillary spreading in non-smooth surfaces, one may refer to the classical example of liquid spreading in V-shaped microgrooves (see Fig. 2 for the geometrical features of the cross section of the groove). For low Capillary number, the pressure drop across the groove is given by

$$\Delta p = p(x) - p(0) = -\frac{\gamma}{R(x)} \tag{39}$$

where $1/R(x) = \sin(\alpha - \theta) \tan \alpha / h(x,t)$. Following a quasi one-dimensional analysis, the flow rate can be obtained as [5]

$$Q = -\frac{h^4(x,t)}{\mu} \Gamma(\theta, \alpha) \frac{\partial p}{\partial x} \tag{40}$$



Surface Tension Driven Flow, Figure 2 Geometrical features pertinent to the liquid spreading in a V-microgroove

where

$$\Gamma(\theta, \alpha) \approx \Gamma(\alpha, \alpha) \left[\frac{h_{\mathrm{c}}(\theta, \alpha)}{h_0} \right]^3 \left[\frac{\overset{\frown}{A}(\theta, \alpha)}{\cot \alpha} \right]^{\frac{1}{2}} . \tag{40a}$$

In Eq. (40a), h_{c} is the height of the fluid at the middle of the groove, and is given by

$$h_{\mathrm{c}}(\theta, \alpha) = h_0 \left[1 + \cot \alpha \frac{\cos(\alpha - \theta) - 1}{\sin(\alpha - \theta)} \right] . \tag{40b}$$

The parameter $\Gamma(\alpha, \alpha)$ can be analytically approximated as

$$\Gamma(\alpha, \alpha) \approx \frac{1}{6} \frac{\cot^3 \alpha + 3.4 \cot^4 \alpha + \cot^5 \alpha}{1 + 3.4 \cot \alpha + 4 \cot^2 \alpha + 3.4 \cot^3 \alpha + \cot^4 \alpha} . \tag{40c}$$

Also, the function $\overset{\frown}{A}(\theta, \alpha)$ in Eq. (40a) is related to the cross sectional area $A(x,t)$ of the liquid inside the groove, as

$$A(x,t) = h^2(x,t) \overset{\frown}{A}(\theta(x,t), \alpha) \tag{40d}$$

where

$$\overset{\frown}{A}(\theta, \alpha) = \frac{\sin^2(\alpha - \theta) \tan \alpha - (\alpha - \theta) + \sin(\alpha - \theta) \cos(\alpha - \theta)}{\tan^2 \alpha \sin^2(\alpha - \theta)} . \tag{40e}$$

The evolution of the height of the liquid inside the groove is derived from the continuity and the momentum conservation equation as

$$\frac{\partial h^2(x,t)}{\partial t} = \frac{D}{h_0}\frac{\partial}{\partial x}\left[h^2(x,t)\frac{\partial h(x,t)}{\partial x}\right] \tag{41}$$

where D is the diffusion coefficient, given by

$$D = \frac{\gamma h_0}{\mu\kappa(\theta_0,\alpha)}\,. \tag{41a}$$

In Eq. (41a)

$$\kappa(\theta_0,\alpha) = \frac{\Gamma(\theta_0,\alpha)\sin(\alpha-\theta_0)\tan\alpha}{(\theta_0,\alpha)}\,. \tag{41b}$$

It is interesting to note here that the value of D is positive if $\alpha > \theta_0$, which is equivalent to having a concave free surface. For $\alpha < \theta_0$, on the other hand, no capillary wicking takes place. Equation (41) has been solved in the literature [5] under various conditions. In the simple case of $h(0,t) = h_0$, a similarity solution can be attempted with $h(x,t) = h_0\phi(\eta)$, where $\eta = x/\sqrt{Dt}$. An approximate solution, in that case, can be obtained as

$$\phi(\eta) = -\frac{1}{2}\eta_0(\eta-\eta_0) - \frac{1}{2}(\eta-\eta_0)^2 - \frac{1}{108\eta_0}(\eta-\eta_0)^3 + \dots \tag{42}$$

where η_0 is the location where the solution goes to zero and stays at zero. A major physical consequence of the above analysis is that the diffusion dynamics dominate for the capillary filling of microgrooves, and the leading edge (spreading front) propagates as

$$x_0(t) = \eta_0(\theta_0,\alpha)\sqrt{Dt}\,. \tag{43}$$

Thus, spreading increases with the depth of the groove, since $D \propto h_0$. The similarity solution also implies that free surface of the liquid spreading remains self-similar downstream.

By following an approach analogous to the above, Darhuber et al. [6] studied the dynamics of capillary spreading along hydrophobic microstripes. The smooth surface was processed chemically to create narrow hydrophilic stripes on a hydrophobic background. The equation governing the self-similar solutions, in that case, can be described as

$$\frac{\mathrm{d}}{\mathrm{d}\eta}\left(\phi^3\frac{\mathrm{d}\phi}{\mathrm{d}\eta}\right) + \frac{\eta}{2}\frac{\mathrm{d}\phi}{\mathrm{d}\eta} = 0 \tag{44}$$

where the similarity variables are defined similarly as before. An approximate solution in this case is given by

$$\phi(\eta) \approx \left(1 - \frac{\eta}{\eta_0}\right)^{\frac{1}{3}} \tag{45}$$

where $\eta_0 \approx 0.87$. Thus, the spreading front advances as $x(t) \propto \sqrt{Dt}$, where $D = 64\gamma h_0^3/35\mu w^2$, w being the width of the microstripe. The average streamwise speed, $\bar{u}$, scales as $\bar{u} \sim \gamma w^4/\mu x$.

Surface Tension Driven Flow in Microchannels

Surface tension driven flows not only take place in open conduits such as microgrooves, but are also quite common in capillary tubes and microchannels. In a generic form, one can write the equation of motion describing the capillary advancement as

$$\frac{\mathrm{d}}{\mathrm{d}t}(MV_\mathrm{c}) = \sum F \tag{46}$$

where M is the fluid mass being transported, V_c is the velocity of its centre of mass and $\sum F = F_{\text{surface tension}} + F_{\text{viscous}} + F_{\text{gravity}}$. To illustrate the use of the above equation in simple forms, one may consider the viscous, incompressible and Newtonian flow against the direction of gravity along a long cylindrical capillary of radius r. For this case, one may first assume that $M = \rho\pi r^2 z$, $V_\mathrm{c} = \dot{z}$, $F_{\text{surface tension}} = 2\pi r\gamma\cos\theta$, $F_{\text{viscous}} = -8\pi\mu z\dot{z}$(assuming fully developed flow) and $F_{\text{gravity}} = -\rho g z$, where z is axial displacement of the capillary front. This leads to the following equation of capillary motion

$$\rho[z\ddot{z} + \dot{z}^2] = \frac{2}{r}\gamma\cos\theta - \frac{8}{r^2}\mu z\dot{z} - \rho g z\,. \tag{47}$$

Equation (47) suffers from a fundamental drawback that as $t \to 0$, $M \to 0$ (since $z \to 0$), giving rise to an ill-posed problem with infinite initial acceleration. This ambiguity can be physically resolved by referring to the equation of continuity, based on which it can be inferred that in the onset of the capillary rise, the liquid present in the dipped portion of the capillary and the bulk reservoir to which it is connected also starts moving at the same time. This additional mass of fluid inducted into the motion initially is known as the added mass, m_0. This added mass can be approximated by executing a potential flow analysis for an incoming spherical liquid element of radius r that moves with a velocity $\dot{z}$. Executing this analysis, one can obtain, for a cylindrical tube [7],

$$m_0 \approx \frac{3\rho\pi r^3}{8}\,. \tag{48}$$

The above is equivalent to the introduction of an additional term in the left hand side of Eq. (56), in the form $3\rho r\ddot{z}/8$, which eliminates the prediction of an unrealistic initial burst as $t \to 0^+$.

Equation (47), with the modifications introduced by Eq. (48) physically represents a rather simplified situation. In reality, a number of other complicating factors may be present, resulting in further modifications in the equation of capillary advancement. For example, the capillary walls can adsorb surfactants from the bulk solution, leading to a continuous variation in the surface tension coefficient. The adsorption of the surfactant, Γ_{lv}, can lead to an axial gradient of surface tension, following the Gibbs equation:

$$\gamma = \gamma_0 - \bar{R}T \int_{C=0}^{C(z,t)} \Gamma_{\mathrm{lv}} d\ln C \tag{49}$$

where C is the surface concentration of the surfactant. Phenomenologically, one may carry out an approximate analysis by posing an exponentially decaying time-dependence of the second term appearing in Eq. (49), such that

$$\gamma = \gamma_0 - \Delta\gamma\phi_{\mathrm{B}}(t) \tag{50}$$

where

$$\Delta\gamma = \gamma_0 - \gamma_\infty\,, \quad \phi_{\mathrm{B}}(t) = 1 - \exp(-\beta t)\,. \tag{50a}$$

Here γ_0 is the initial surface tension, γ_∞ is the equilibrium surface tension and β is a relaxation constant. This effect can be introduced in Eq. (47) by first differentiating the same with respect to time, neglecting the terms containing the products $\dot{z}\ddot{z}$ and $z\dddot{z}$ in the quasi-steady limit, to set

$$-\frac{2\beta\Delta\gamma\cos\theta}{r}\exp(-\beta t) = \frac{8\mu}{r^2}[\dot{z}^2 + z\ddot{z}] + \rho g\dot{z}\,. \tag{51}$$

Typical numerical solutions of Eq. (51), following Zhumud et al. [8], are presented in Fig. 3. A maximum occurs in the characteristic displacement curves only when the surface tension relaxation is not as fast as compared to the capillary filling. More simplistic scaling estimates in the capillary rise phenomenon can readily be obtained by noting that within certain limits, the capillary rise represents a quasi-steady process, in which the amount of surfactant adsorbed to the solid/liquid interface per unit time is equal to that transported to the liquid/vapour interface by diffusion, which implies

$$2\pi r\Gamma_{\mathrm{sl}}^m dz \sim \pi r^2 D\frac{C_{\mathrm{b}}}{\sqrt{Dt}}\mathrm{d}t \tag{52}$$



Surface Tension Driven Flow, Figure 3 Simulated capillary rise dynamics for aqueous solutions of surfactants. In the figure, $\alpha = \rho g r^2/8\eta z_{t\to\infty}$. For obtaining the plots, following data are taken: $r = 10^{-4}$ m, $\eta = 10^{-3}$ Pa, $\rho = 10^3$ kg/m^3, $\theta = 0$, $\alpha = 8.3 \times 10^{-2}$ s^{-1}

where Γ_{sl}^m is the adsorption capacity of the monolayer per unit area and C_{b} is the bulk concentration of the surfactant. From Eq. (52), one can obtain

$$z(t) \sim \frac{rC_{\mathrm{b}}}{\Gamma_{\mathrm{sl}}^m}\sqrt{Dt} \tag{53}$$

which physically implies the condition of a diffusion-limited capillary advancement.

The real physical picture of surface tension driven capillary motion appears to be much more complicated than what is depicted by Eq. (47). First of all, the viscous resistance terms need to be modeled more carefully. In reality, as the fluid enters the microchannel, the flow passes through a short entrance region, followed by a fully developed region. A third region, namely the meniscus traction region, also comes into play, because of the influence of the free surface of the meniscus on the flow. This can alter the velocity profiles significantly, and the predicted drag force can appear to be significantly different from that obtained from the considerations of a fully developed Poiseullian velocity profile. These effects have recently been taken into account for analyzing the surfacetension driven flow of blood in microfluidic channels. Details of the underlying physical principles to model the modified viscous drag are presented in the article on ►capillary filling, and are not repeated here for the sake of brevity. Another interesting and important consideration is the modeling of the dynamic evolution of an apparent contact angle, which can effectively represent a gross manifestation of the sub-continuum picture close to the interfaces that cannot be directly resolved in the system-level calculations. It needs to be noted in this context that the capillarity effect within the microchannel essentially implies that a fluid–fluid interface and the fluid–solid interface intersect to form a common line of contact, or a tri-junction. In order to model such moving contact lines appropriately, one needs to first qualitatively assess the physical phenomena influencing the capillarity. In this regard, it has been experimentally shown that points on the interfacial lines arrive at the contact line within a finite time span. Therefore, one must pose an effective slip law that relieves a force singularity condition by ensuring that a finite force is necessary to move the contact lines of a fluid, irrespective of the no-slip boundary conditions classically being applied at the channel walls. In order to mathematically ensure this effect, one needs to pose a condition on the contact angle θ, as a function of velocity of the contact line. In a physical sense, this departure of contact angle from its static equilibrium value is mainly due to viscous bending of the interface near the contact lines. Although exact mathematical quantification of the dynamic evolution of this contact angle may be somewhat involved, experimental studies have revealed that the apparent dynamic contact angle, θ_a, that the liquid forms with the solid surface is closely described by a universal scaling relationship at low speeds, known sometimes as Tanner's law, which can be mathematically stated as

$$\theta_\mathrm{a} \sim \mathrm{Ca}^{\frac{1}{3}} \tag{54}$$

where $\mathrm{Ca} = \mu u/\gamma$ is the capillary number, and u is velocity of the contact line. However, in order to quantify the proportionality constant, one must resolve the asymptotic behavior of the thin liquid film in vicinity of the microchannel wall. This thin film region can further be divided into two parts, namely, (a) a lubricating film region followed by (b) a precursor film region as one moves along the direction of wetting. In the precursor film region, one expects the interfacial length scales to approach molecular scales, as intermolecular forces become important. Behind the lubricating film, on the other hand, the length scales are quite large (of the order of r), and a potential challenge remains in devising a quantitative expression for dynamic evolution of θ_a by asymptotic matching from solutions to these regions of widely different length scales. For analysis of the same, one may assume negligible gravitational effects (typically characterized by a low Bond number, $\mathrm{Bo} = \rho g r^2/\gamma$), and viscosity of the gas phase negligible in comparison to that of the liquid phase so that dynamics of the two phases are essentially decoupled. In that situation, the domain of interest can be divided into two regions, namely

- the outer region where the lateral and vertical length scales are both O(1) and
- the inner lubrication region in which the lateral and vertical length scales are $\mathrm{O}(\mathrm{Ca}^{\frac{1}{3}})$ and $\mathrm{O}(\mathrm{Ca}^{\frac{2}{3}})$, respectively, as capillary and viscous forces balance.

Further division of the inner region may be necessary when the intermolecular forces become important at very thin films. In the lubricating film region, this effect can be incorporated by invoking an extra term of the same dimension as that of pressure in the overall force balance, which can be described as $A/6\pi z^3$, z being the film thickness. This term is known as the ▶disjoining pressure. The parameter A is called the Hamaker's constant (for a further detailing, see the next sub-section), which is negative for wetting fluids. It is important to note here that one needs to be extremely careful in introducing intermolecular forces into a continuum model such as the Navier–Stokes equation. In particular, the surface tension force, which is due to intermolecular forces between the gas and liquid phases, cannot be considered separately from the Van der Waals forces between the gas and the solid phases for very thin films. If one introduces a molecular length scale R_m as $R_\mathrm{m} = (|A|/6\pi\gamma)^{\frac{1}{2}}$, or its dimensionless counterpart $\lambda = R_\mathrm{m}/r$; the above-mentioned model for lubricating film is valid if its film thickness is much larger than R_m, i.e., $\mathrm{Ca}^{\frac{2}{3}} \gg \lambda$. Since R_m is typically of the order of a few Angstroms, while a typically capillary radius is of the order of 10^{-1} mm, the lower bound on Ca is of the order of 10^{-4}. Beyond this lower bound, the continuum model remains valid for the lubricating film. At relatively larger Ca, the intermolecular forces would turn out to be less effective, so that dependence of Tanner's law on λ becomes progressively weaker. For a significantly large Ca, the meniscus speed may exceed the wetting speed and the meniscus may reverse its curvature as the contact angle passes through 90° . However, the foregoing analysis assumes that such situations do not occur, and accordingly, it remains valid for $\theta < 90°$. An asymptotic matching may accordingly be done between the outer region and the precursor film through the lubricating film at the inner region. At the front of this region, however, intermolecular forces and a vanishingly small film (spread by fast wetting) stipulate a hyperbolic decay of the film thickness towards zero. Accordingly, a universal relationship for dynamic evolution of the contact angle can be obtained as [9]

$$|\tan\theta_\mathrm{a}| = 7.48\mathrm{Ca}^{1/3} - 3.28\lambda^{0.04}\mathrm{Ca}^{0.293} \tag{55}$$

It can be noted here that λ is typically of the order of 10^{-8} for wetting fluids flowing through a microcapillary channel having hydraulic radius of the order of 1 mm. Physically, for very low values of Ca, the corresponding correction term appearing in Eq. (55) may become important, where intermolecular forces come significantly into play and $\tan\theta_a$ diverges slightly away from the asymptotic behavior characterized by Eq. (54) towards lower values. Mathematically, Eq. (55) has been derived from a matched asymptotic analysis that matches a static outer region to the precursor adhering the wall, through an intermediate lubricating film. The problem, hence, is characterized by three length scales, namely, the capillary radius, film thickness and molecular length scale (λ). This interconnection is captured by Eq. (55), and the outcome is very much analogous to the slip model obtained by Hoffman [10], which gives the variation of θ_a as a function of slip length as:

$$g(\theta_a) = g(\theta_a(0)) + \mathrm{Ca}\ln\left(\frac{k}{l_s}\right) \tag{56}$$

where the slip length scale is given by: $l_s \sim l_d/\mathrm{Ca}$, l_d being of the order of wall roughness and k being a slip-model dependent constant. Exact for of $g(\theta_a)$ is available in Hoffman [10], which is as

$$g(\theta_a) = \int\limits_0^{\theta} d\phi\,[f(\phi)]^{-1} \tag{57}$$

where

$$f(\phi) = \frac{2\sin\phi(A+B+C)}{D+E} \tag{57a}$$

where

$$A = q^2\left(\phi^2 - \sin^2\phi\right),$$
$$B = 2q\left[\phi(\pi-\phi) + \sin^2\phi\right],$$
$$C = (\pi-\phi)^2 - \sin^2\phi,$$
$$D = q\left(\phi^2 - \sin^2\phi\right)[(\pi-\phi) + \sin\phi\cos\phi],$$
$$E = (\phi - \sin\phi\cos\phi)\left[(\pi-\phi)^2 - \sin^2\phi\right].$$

In Eq. (57a), q is the ratio of viscosity of the liquid and the vapour. Typical values of the factor k, as reported in the literature [10], can be of the order of 10^{-1} to 10.

Molecular Level Modeling of Wetting Phenomena

The mathematical descriptions outlined in most of our preceding discussions represents a continuum-based picture of the wetting phenomenon and the consequent surface tension driven flow. However, from a more fundamental perspective, these are strongly influenced by the underlying molecular picture; more precisely, through the intermolecular interaction potentials (adhesion and cohesion). One may quantify the net effect of the interaction potentials on the wetting behaviour by considering a liquid film of thickness l on a solid substrate. For strong solid–liquid adhesive interactions, the system can lower its free energy by increasing the distance between the solid–liquid and the liquid–vapour interfaces. This leads to a net repulsion force per unit area between the solid–liquid and the liquid–vapour interfaces, which is called the disjoing pressure, $\Pi(l)$. The disjoing pressure can be related to the effective interface potential, $V(l)$ as per the following relationship:

$$\Pi(l) = -\frac{\mathrm{d}V(l)}{\mathrm{d}l}. \tag{58}$$

The excess free energy of the liquid film, accordingly, can be estimated as

$$E_s(l) = \gamma_{lv} + \gamma_{sl} + V(l). \tag{59}$$

A fundamental estimate of the excess free energy of the liquid film can be provided by the density functional theory, which is based directly on the microscopically specified molecular interactions. In its simplest form, the free energy functional, E_s, can be represented as [11]

$$\begin{aligned} E_S = {} & \underbrace{E_{hc}\left(\{\rho(\mathbf{r})\}, T\right)}_{\text{hard core interactions}} \\ & + \frac{1}{2}\int \underbrace{d^3r d^3r' \tilde{w}\left(\left|\mathbf{r}-\mathbf{r}'\right|\right)\left(\rho(\mathbf{r})\rho(\mathbf{r}') - \rho_b^2\right)}_{\text{long range particle-particle interactions}} \\ & + \int \underbrace{d^3rU(\mathbf{r})\rho(\mathbf{r})}_{\text{particle-wall interactions}} \end{aligned} \tag{60}$$

where $\tilde{w}\left(\left|\mathbf{r}-\mathbf{r}'\right|\right)$ is the long-ranged part of the particle-particle interaction potential in the liquid phase, ρ_b is the particle-density far from the wall, and $U(\mathbf{r})$ is the interaction potential of a fluid particle with the wall particles. The density profile, $\rho(\mathbf{r})$ can be found by minimizing Eq. (60). Despite being quite straight forward in principle, a execution of this task, however, is rather difficult, owing to the slow decay of parts of the interaction potential. Because of such practical constraints, quantitative predictions based on numerical solutions of the full density functional theory has been rather limited, except for wetting behaviour of simple atoms or molecules (e. g. He) on simple substrates (e. g. Cs) at zero temperature [12]. However, for He, quantum effects also need to be taken into account while formulating the density functional, which takes the following form [12]:

$$E_{\mathrm{S}} = \frac{\hbar^2}{2m} \int \underbrace{\mathrm{d}^3 r \left\{ \nabla \left[\rho^{\frac{1}{2}} \right] (\mathbf{r}) \right\}^2}_{\text{quantum kinetic energy}} + \int \underbrace{d^3 r U(\mathbf{r})\, \rho(\mathbf{r})}_{\text{particle-wall interactions}} + \underbrace{H_{\mathrm{NL}}}_{\text{short range correlations in the liquid}} \tag{61}$$

where the non-local Hamiltonian, H_{NL}, is given by

$$H_{\mathrm{NL}} = \frac{1}{2} \int d^3 r d^3 r' \rho(\mathbf{r})\, \rho(\mathbf{r}')\, \tilde{w}\left(|\mathbf{r} - \mathbf{r}'|\right) + \frac{c}{2} \int d^3 r \rho(\mathbf{r}) \left[\bar{\rho}(\mathbf{r})\right]^{1+\gamma} . \tag{61a}$$

Phenomenologically, H_{NL} accounts for short-range interactions and correlations between the He atoms, and involves a spatially-averaged density, $\bar{\rho}$. One major limitation of expression (61), however, is that it is restricted to $T = 0$, so that it cannot predict the wetting temperature. For wetting of quantum liquids, an alternative approach was introduced by Cheng et al. [12]. As per this consideration, under the assumptions of a sharp interface bounding the wetting layer, the surface free energy of the substrate can be approximated as

$$\gamma_{\mathrm{sl}} = \gamma_{\mathrm{sv}} + \tilde{\gamma}_{\mathrm{sl}} + \rho_{\mathrm{b}} \int_{z_{\min}}^{\infty} U(z) dz \tag{62}$$

where $\tilde{\gamma}_{\mathrm{sl}}$ is the cost of making the liquid density vanish at the substrate, and is taken to be equal to γ_{lv}. This simple model also assumes the liquid density in the film to be same as the bulk liquid density. The potential is taken as follows:

$$U(z) = \frac{4C_3^3}{27D^2 z^9} - \frac{C_3}{z^3} \tag{63}$$

where C_3 gives the amplitude of the van der Waals interaction between one particle and the substrate, and D is the well-depth of the substrate-adsorbate interaction potential. In addition, if $z_{\min}$ is taken to be the minimum of $V(l)$, the wetting transition temperature can be calculated by solving

$$\left(C_3 D^2\right)^{\frac{1}{3}} = \frac{3.33\gamma(T)}{\rho_{\mathrm{l}} - \rho_{\mathrm{v}}} . \tag{64}$$

It is important to note here that for wetting phenomena, an important contribution to the disjoining pressure arises from the van der Waals interaction ($w(r) \propto 1/r^6$), which includes dipole-dipole, dipole-induced dipole and induced dipole-induced dipole interactions. Performing a volume integral over all the molecules present in the two half-spaces bounding the film, one finds a decay of the form $\Pi(l) \approx A/(6\pi l^3)$, where A is known as the Hamaker constant, which physically gives the amplitude of the interaction. Fundamentally, the Hamaker constant can be calculated in terms of the dielectric properties of the three phases. For example, one can employ a simple approximation by first considering the contribution due to dipolar interactions, given by the zero-frequency permittivities of the respective phases, as [13]

$$A_{\nu=0} = -\frac{3}{4} k_{\mathrm{B}} T \frac{(\varepsilon_1 - \varepsilon_3)(\varepsilon_2 - \varepsilon_3)}{(\varepsilon_1 + \varepsilon_3)(\varepsilon_2 + \varepsilon_3)} \tag{65}$$

where 1(solid) and 2(vapour) denote the phases in the two half-spaces and 3(liquid) is the intermediate phase. For non-zero frequencies, on the other hand, the contribution comes from the relative refractive indices of the three phases, as

$$A_{\nu>0} = -\frac{3h\nu_{\mathrm{UV}}}{16\sqrt{2\left(n_1^2 + n_3^2\right)\left(n_2^2 + n_3^2\right)}} \frac{\left(n_1^2 - n_3^3\right)\left(n_2^2 + n_3^2\right)}{\sqrt{\left(n_1^2 + n_3^2\right) + \sqrt{\left(n_2^2 + n_3^2\right)}}} \tag{66}$$

where h is the Planck's constant and ν_{UV} ($\approx 2 \times 10^6$ Hz) is the UV frequency for which the relative refractive indices of the phases become identical (close to unity). In practice, the Hamaker constant is the sum of the two contributions given by Eqs. (65) and (66). Equaion (65) retains the $1/l^2$ dependence for all distances. However, Eq. (66) is subject to retardations, since interactions between dipoles travel only at the speed of light. It also follows from Eq. (66) that for two identical phases1 and 2 separated by a dissimilar phase 3, the net effect is an attractive van der Waals interaction ($A < 0$) between the two interfaces. In typical situations involving surface tension driven flows, the nature of the contribution given by Eq. (66) is dominated by the relative refractive index difference between the liquid and the solid, since the refractive index of the vapour would generally be close to unity. If the liquid has a refractive index between that of the solid and the vapour, then $A > 0$ and the formation of the wetting layer is preferred (because of an effective repulsion between the interfaces).

A close inter-connection between the molecular and the continuum theories of surface tension driven phenomena can be provided by the equilibrium spreading coefficient, $S = \gamma_{\mathrm{sv}} - \gamma_{\mathrm{sl}} - \gamma_{\mathrm{lv}}$, which physically represents the surface free energy difference between partial and complete wetting. When S is negative, it becomes unfavourable to replace the solid-vapour interface by two others, as pertinent to the partial wetting state. The phenomenological theory of Cahn [14] gives an explicit way to calculate the value of S, from molecular considerations. As per this theory, the surface free energy functional is given as

$$E_{\mathrm{s}} = \underbrace{\phi(\rho_{\mathrm{s}})}_{\text{wall interaction}} + \int_0^{\infty} \underbrace{\left[\omega(\rho) + c^2/4 \left(\frac{\mathrm{d}\rho(z)}{\mathrm{d}z}\right)^2\right]}_{\text{liquid–vapour interaction}} \mathrm{d}z \tag{67}$$

where ω is the grand potential per unit volume, $\rho(z)$ is the density profile as a function of the distance z from the solid surface and $\rho_{\mathrm{s}} = \rho(0)$ is the value of density at the substrate. In principle, Eq. (67) intends to represent a similar physical behaviour as that depicted by Eq. (60), except for the fact that long-ranged interactions are not included in Eq. (67). The wall-interaction term in Eq. (67) is usually expanded to the second order, as

$$\phi(\rho_{\mathrm{s}}) = -h_1 \rho_{\mathrm{s}} - g\rho_{\mathrm{s}}^2/2 \tag{67a}$$

where the parameters h_1 and g are referred to as the short-range surface field and the surface enhancement field, respectively. The parameter h_1 describes the preference of the substrate for either the liquid or the vapour, and can be taken proportional to the difference between the substrate–liquid and substrate–vapour interfacial tensions. If $h_1 > 0$, the liquid is preferred at the wall, whereas for $h_1 < 0$, the vapour is preferred. The parameter g (usually a small negative number) is a measure of the 'missing' liquid–liquid interactions due to the fact that a liquid molecule near the wall has a small number of liquid neighbours than the bulk. The grand potential in Eq. (67) can be estimated by employing the classical Landau expansion around the critical point (in units of $k_{\mathrm{B}}T$), in the form of

$$\omega = a_2\rho^2 + a_4\rho^4 \,. \tag{67b}$$

Based on this, the spreading coefficient, S, can be calculated explicitly, as

$$S = c\rho_0/12 \left(\left[\kappa^2 + 4(1+\chi)\right]^{\frac{3}{2}} - \left[\kappa^2 + 4(1-\chi)\right]^{\frac{3}{2}}\right) + 3\chi\kappa/4 - 4c\rho_0^3/3 \tag{68}$$

where $\pm\rho_0$ are the bulk densities, $\chi = h_1/c\rho_0^2$ and $\kappa = g/c\rho_0$.

Key Research Findings

Numerous applications of surface tension driven microflows have been presented in the recent literature. Jun and Kim [15] demonstrated the pumping of fluids in microchannels using the movement of a single or multiple vapor bubbles The pumping mechanism required no micromechanical moving components for actuation, and essentially operated by utilizing an asymmetric heating that creates a variation in vapor pressure and surface tension due to the heater-induced temperature gradient along the channel. A heat and mass transfer analysis was performed to model the pumping mechanism and to estimate the pumping capability of the device. Experimental results were also presented to establish the proposition. Chakraborty and Som [16] theoretically determined the rate of heat transfer in a thin evaporating liquid film flowing along the walls of a microchannel under the combined action of surface tension and gravity. Analytical solutions of conservation equations, in both liquid and vapour phases, were obtained in their study. Lee and Kim [17] demonstrated the first microelectromechanical systems (MEMS) device that adopts surface tension as the driving force, by driving a liquid-metal droplet in an electrolyte-filled capillary, by locally modifying the surface tension with electric potential. Certain key issues in practical implementation were identified and investigated, including the problems of material compatibility, electrode polarization, and electrolysis, as well as the micromachining process. Based on these understandings, they demonstrated a liquid micromotor in the form of an electrolyte and liquid-metal droplets rotating along a microchannel loop. Smooth and wear-free rotation of the liquid system was shown at a speed of approximately 40 mm/s, with a driving voltage of only 2.8 V and a little power consumption (10 – 100 W). Chakraborty [18] investigated the breakup of viscous liquid droplets on surface tension modulation during micro-welding metal transfer. This study was motivated by the fact that viscous jets of a molten metal ready to be transferred into the arc welding pools are inherently unstable. From this study, a variation of the time required for droplet formation was obtained as a function of the surface tension modulation, corresponding to different instability modes. Chan and Yang [19] presented theoretical and experimental studies of the surface-tension-driven, two-immiscible liquid–liquid displacement in a horizontal capillary. A one-dimensional mathematical model was developed to describe the capillary displacement of a fixed liquid column by another liquid that continuously flows into the capillary by surface tension. Experiments for a water column displaced by silicon oil were carried out to examine the underling dynamics in practice. It was found that a faster and longer displacement was achieved for a shorter water column in a larger capillary. Their theoretical predictions agreed well with the experimental results. In a recent study, Chakraborty [20] devised a novel mathematical approach to analyze the surface tension driven flow of blood from a droplet into a microcapillary channel. Special attention was devoted to estimate the effects of variable hydraulic resistance over different flow regimes, influence of suspended RBC particulates on the non-Newtonian flow characteristics and implications of a dynamically-evolving contact angle. These studies have subsequently been extended for capillary transport in presence of electroosmotic effects [21]. There have also been other recent applications on modeling of surface tension driven microflows (for details, please refer to the articles on ► electrocapillary, ► capillary filling and ► droplet dynamics in microchannels), elucidating comprehensive applications of the underlying theory.

Future Directions For Research

Future research in the modeling of surface tension driven flows can be directed towards the development of integrated multi-scale models that can more effectively represent the sub-continuum (essentially, molecular level) level transport features in the framework of continuum based descriptions of the surface tension aided microfluidic transport.

Cross References

- ► Applications Based on Electrowetting
- ► Boundary Slip of Liquids
- ► Bubble Dynamics in Microchannels
- ► Capillary Filling
- ► Chaotic Flow
- ► Compute Mixing Efficiency
- ► Digital Microfluidics
- ► Droplet and Bubble Formation in Microchannels
- ► Droplet Based Lab-on-Chip Devices
- ► Droplet Despensing
- ► Droplet Dynamics in Microchannels
- ► Droplet Evaporation
- ► Droplet Microreactors
- ► Electrocapillary
- ► Electrowetting and Droplets
- ► Transport of Droplets by Acoustics
- ► Transport of Droplets by Thermal Capillarity
- ► Wetting and Spreading

References

1. Levich VG, Krylov VS (1969) Surface-tension-driven phenomena. Ann Rev Fluid Mech 1:293–316
2. Mazouchi A, Homsy GM (2000) Thermocapillary migration of long bubbles in cylindrical capillary tubes. Phys Fluids 12:542–549
3. Shapiro B, Moon H, Garrel RL, Kim C-J (2003) Equilibrium behaviour of sessile drops under surface tension: applied electric fields and material variations. J Appl Phys 93:5794–5811
4. Tanner LH (1979) The spreading of silicone oil drops on horizontal surfaces. J Phys D 12:1473–1484
5. Romero LA, Yost FG (1996) Flow in an open channel capillary. J Fluid Mech 322:109–129
6. Darhuber AA, Troian SM, Reisner WW (2001) Dynamics of capillary spreading along hydrophobic microstripes. Phys Rev E 64(1–8):031603
7. Yih CH (1995) Kinetic-energy mass, momentum mass, and drift mass in steady irrotational subsonic flow. J Fluid Mech 297:29–36
8. Zhumud BV, Tiberg F, Hallstensson K (2000) Dynamics of capillary rise. J Colloid Interface Sci 228:263–269
9. Kalliadasis S, Chang HC (1994) Apparent dynamic contact-angle of an advancing gas-liquid meniscus. Phys Fluids 6:16–23
10. Hoffman RL (1975) A study of the advancing interface I. Interface shape in liquid–gas systems. J Colloid Interface Sci 50:228–235
11. Schick M (1990) Liquids at Interfaces. In: Charvolin JJ, Zinn-Justin J (eds) Liquids at Interfaces, Les Houches Session XLVIII. Elsevier, Amsterdam, pp 415–497
12. Cheng E, Cole M, Dupont-Roc J, Saam W (1993) Novel wetting behaviour in quantum fluids. Rev Mod Phys 65:557–567
13. Israelachvili J (1992) Intermolecular & Surface Forces. Academic, London
14. Cahn J (1977) Critical-point wetting. J Chem Phys 66:3667–3672
15. Jun JK, Kim CJ (1998) Valveless pumping using traversing vapour bubbles in microchannels. J Appl Phys 83:5658–5664
16. Chakraborty S, Som SK (2005) Heat Transfer in an evaporating thin liquid film moving slowly along the walls of an inclined microchannel. Int J Heat Mass Transf 48:2801–2805
17. Lee J, Kim CJ (2000) Surface-tension-driven microactuation based on continuous electrowetting. J Microelectromech Syst 9:171–180
18. Chakraborty S (2005) Analytical investigations on break up of viscous liquid droplets on surface tension modulation during welding metal transfer. Appl Phys Lett 86(1–3):174104
19. Chan WK, Yang C (2005) Surface-tension-driven liquid–liquid displacement in a capillary. J Micromech Microeng 15:1722–1728
20. Chakraborty S (2005) Dynamics of capillary flow of blood into a microfluidic channel. Lab Chip 5:421–430
21. Chakraborty S (2007) Electroosmotically driven capillary transport of typical non-Newtonian bio-fluids in rectangular microchannels. Anal Chim Acta 605:175–184

Surface Texture

► Surface Roughness Measurement

Surface Topography

► Surface Roughness Measurement

Surface Tracking

► Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking

Surface Transformation

► Surface Modification, Methods

Surface Treatment

► Surface Modification, Methods

Suspensions

► Non-Newtonian Fluids in Microfluidics

Switching Etching

► ICP Etching

Synthesis of Biological Molecules in Microfluidics

► Biomolecular Synthesis in Microfluids

Synthesis of Polymer Molecules Using Microfluidics

► Polymer Synthesis within Microfluidic Reactor

Synthetic Jet

► Microsynthetic Jets

Tandem MS

► Mass Spectrometry

Taylor–Aris Dispersion

► Hydrodynamic Dispersion

Taylor Bubble Flow

► Taylor Flow in Microchannels

Taylor Dispersion

► Hydrodynamic Dispersion

Taylor Flow

► Microsegmented Flow

Taylor Flow in Microchannels

PANAGIOTA ANGELI, ASTERIOS GAVRIILIDIS
Department of Chemical Engineering, University College London, London, UK
p.angeli@ucl.ac.uk, a.gavriilidis@ucl.ac.uk

Synonyms

Taylor bubble flow; Bubble train flow; Segmented flow; Slug flow; Plug flow; Elongated bubble flow; Intermittent flow

Definition

Taylor flow is a type of gas–liquid flow pattern that consists of elongated bubbles with equivalent diameter usually many times that of the channel diameter, separated by liquid slugs (Fig. 1). The bubbles adopt a characteristic capsular shape and can either completely or nearly completely fill the channel cross-section where at most a thin liquid film separates them from the channel wall.

Chemical and Physical Principles

Definition of Small Channels

Taylor flow is a dominant pattern during gas–liquid flow in small channels. Channels are generally considered to be small when the surface tension forces dominate the gravitational forces. A measure of the relative importance of the two forces is given by the Bond or Eötvös number (both names are invariably used in the literature)

$$\text{Bo or Eö} = \frac{(\rho_g - \rho) g d^2}{\gamma} \tag{1}$$

where ρ_g and ρ are the gas and liquid densities, respectively, g is the gravitational acceleration, d is the tube diameter and γ is the surface tension. Investigators have suggested different values of the Bo or Eö number below which channels can be considered small, ranging from 0.88 to $(2\pi)^2$. Bretherton [1] has observed that a Taylor bubble no longer rises spontaneously in a water-filled capillary under the effect of gravity for Bo < 3.37 and this value can also be used to define small channels.



Taylor Flow in Microchannels, Figure 1 Gas–liquid Taylor flow

Flow Patterns

In small channels a number of flow patterns can be observed and the same terminology and classifications as in large channels are commonly used. Because of the dominance of the surface tension forces stratified flow is rarely observed in small channels. In general, bubble flow appears at low gas flowrates. As the gas flowrate increases Taylor bubbles form. With further increase in the gas flowrate annular flow appears with the liquid forming an annulus which wets the wall. At high gas and liquid flowrates, churn flow occurs where there is a liquid film at the wall and the gas flow in the center is interrupted by the frequent appearance of frothy bubbles and slugs.

As the dimensions of the channel reduce, Taylor and annular flows dominate, while patterns specific to small channels appear (such as ring, liquid lump, Yakitori and rivulet flows). These can be considered to be variations of the Taylor and annular regimes. For a review of gas–liquid flow patterns in microchannels see Ghiaasiaan and Abdel-Khalik [2].

Key Research Findings

Flow Patterns in Liquid Slugs

Qualitative sketches of the flow streamlines in the liquid slug ahead of the bubble have been presented by Taylor [3] (see Fig. 2). These were related to the Capillary number, Ca ($\mathrm{Ca} = \mu U_\mathrm{b}/\gamma$, where μ is the liquid viscosity and U_b is the bubble velocity) and to the dimensionless number m, that gives the relative velocity between the bubble and the liquid

$$m = \frac{U_\mathrm{b} - U_\mathrm{ls}}{U_\mathrm{b}} \qquad (2)$$

where U_ls is the average liquid slug velocity. At high values of Ca, for $m > 0.5$, complete bypass flow was suggested with a single stagnation point at the bubble front. At low values of Ca, for $m < 0.5$ two possible reversal flow patterns were envisaged, one featuring a stagnation ring around the bubble cap (Fig. 2b) and the other featuring a single stagnation point at the bubble cap tip and a second one inside the liquid slug (Fig. 2c).

Although patterns 2a and 2b have been confirmed experimentally and theoretically by many investigators, pattern 2c was observed for the first time in numerical studies [4]. For no inertia and high Ca, a single stagnation point on the bubble tip was seen. As Ca decreased, there was a transition and vortices started to appear at $\mathrm{Ca} = 0.69$, as suggested by pattern 2c. A stagnation ring finally developed at $\mathrm{Ca} = 0.60$ (pattern 2b). The small range of Ca values, $0.60 < \mathrm{Ca} < 0.69$, within which pattern 2c appeared would explain why it had not been observed experimentally before. At the back of the bubble, it was found [5] that as Ca increases from 0.60 to 0.69 the vortex breaks into two regions, a swirl and a recirculating flow separated by a stagnation point, whose sizes diminish as Ca increases.



Taylor Flow in Microchannels, Figure 2 Streamlines in the liquid slug in front of the Taylor bubble [3]

The analytical model developed by Thulasidas et al. [6], which is suitable for bubble train flow, showed that the transition to complete bypass (pattern 2a) occurs in horizontal flow at $\mathrm{Ca} = 0.7$, in upward flow at $\mathrm{Ca} = 0.5$ and in downward flow at $\mathrm{Ca} = 0.6$.

Film Thickness and Bubble Shape

The flow of a long bubble in a capillary is a classical problem in fluid mechanics. Bubbles have been used as tracers in capillaries filled with liquid in order to determine liquid velocity. This application led to the discovery that when a wetting viscous liquid is displaced by a gas bubble in a capillary a liquid film is deposited on the wall. Initial experimental findings that the thickness of the film was proportional to $\mathrm{Ca}^{1/2}$ were confirmed and extended to $\mathrm{Ca} = 10^{-1}$ [3]. In his pioneering approach, Bretherton [1] assumed creeping flow in the liquid and used lubrication theory for the region of the film between the end of the spherical bubble cap and the flat film behind it to calculate the thickness of the film, the pressure drop and the shape of the bubble. The Taylor bubble was taken to be inviscid with spherical caps. From this analysis it was found that the thickness of the film can be obtained from $\delta/d = 0.66\,\mathrm{Ca}^{2/3}$. This finding should be valid for low values of Ca. Surprisingly, however, the experiments agreed better with the theory for $\mathrm{Ca} > 10^{-3}$, while at lower Ca, where the theory should hold exactly, the thickness of the film was substantially larger than the theoretical values. This discrepancy was later attributed to the presence of surface-active contaminants that are absorbed at the interface. Ratulowski and Chang [7] argued that surface contamination can be correctly assessed only if the surface tension is allowed to vary along the interface. A model was developed that included surfactant transportation at both the interface and in the bulk liquid and showed that an increase in the thickness of the film occurs if the surfactant transport in the bulk is mass transfer limited.

For higher values of Ca ($\mathrm{Ca} > 5 \times 10^{-3}$), numerical studies are required to obtain the shape of the bubble and the thickness of the film. A number of numerical solutions to the problem have been suggested, which also validate Bretherton's approach at very low values of Ca. As the front profile and the thickness of the film of a long Taylor bubble with sufficient separation between the bubbles can be approximated by that of an infinitely long bubble, many early studies, considered semi-infinite bubbles.

In later studies the effect of inertia at increased Reynolds numbers ($\mathrm{Re} = \rho U r/\mu$, where r is the channel radius) was considered. Giavedoni and Saita carried out extensive numerical simulations and analyzed the front [4] of a Taylor bubble for $10^{-5} < \mathrm{Ca} < 10$, $\mathrm{Re} < 70$, and the back [5] of a Taylor bubble for $10^{-3} < \mathrm{Ca} < 1.5$, $\mathrm{Re} < 70$. Because of the development of a constant film thickness it is possible to study the front and rear parts of the bubble independently. The influence of increasing Re on film thickness was found to be weakly non-monotonic where an initial decrease was followed by an increase (see Fig. 3). Later studies at even higher Re confirmed the trend of increasing thickness of the film as Re increased further. For $\mathrm{Ca} < 0.01$, however, inertial forces do not have an effect on film thickness.

Experimentally determined film thickness correlations have been listed by Edvinsson and Irandoust [8]. Based on scaling arguments in a semi-infinite bubble, a correlation was suggested [9] for the film thickness in the visco-capillary regime (where the thickness of the film depends only on Ca) that agreed well with Taylor's data and at very small Ca with Bretherton's model. After fitting it against experimental data the correlation became

$$\frac{\delta}{d} = \frac{0.66\,\mathrm{Ca}^{2/3}}{1 + 2.5\left(1.34\,\mathrm{Ca}^{2/3}\right)} \tag{3}$$



Taylor Flow in Microchannels, Figure 3 Thickness of the film over the half-channel size (h_∞) against Reynolds number for plane flow (dashed lines) and axisymmetric flow (solid lines). Dotted lines represent situations that may not be feasible in practice [4]

At $\mathrm{Ca} > 10^{-3}$ inertial effects become important (visco-inertial regime) and the film thickness becomes larger than the one obtained by Eq. (3). Interestingly, this difference increases as the diameter of the tube increases. In the inertial regime [9]

$$\frac{\delta}{d} \propto \frac{\mathrm{Ca}^{2/3}}{\left(1 + \mathrm{Ca}^{2/3} - \mathrm{We}\right)} \tag{4}$$

The Weber number, We, is defined as $\mathrm{We} = \rho U_\mathrm{b}^2 (r-h)/\gamma$, where h is the thickness of the film deposited on the wall. The simulations by Giavedoni and Saita showed that the bubble front tended to adopt the shape of an arc of a circle for decreasing values of Ca. Undulations, which increased with Re, appeared at the back of the bubble. The size of the undulations depended on both Ca and Re and for $\mathrm{Ca} > 0.5$ no undulations were observed. For all the values of Re that were tested the rear of the meniscus was convex at first, became flat as Ca increased and then adopted a concave shape, while as Re increased the change from flat to concave shape appeared at lower values of Ca. The interface at the back of the bubble close to the meniscus tip is an almost perfect hemisphere for $\mathrm{Ca} < 10^{-3}$.

Thulasidas et al. [6] found experimentally that the thickness of the film was almost the same in horizontal and downward flows but was twice as much in upward flows.

Bubble Velocity

Because of the film between the bubble and the wall, the bubble and liquid velocities are not the same. The bubble velocity, U_b, is given by the drift flux model

$$U_\mathrm{b} = CU_\mathrm{ls} + U_0 \tag{5}$$

where C is an experimentally determined coefficient and U_0 is the bubble rise velocity in a stagnant liquid. For very small capillaries the bubble rise velocity is very small or zero (see also the definition of small channels given above). The bubble motion is often characterized by the dimensionless number m (see Eq. (2)). For low values of Ca, $m = 1.0\,\mathrm{Ca}^{1/2}$ which was found to be valid for $\mathrm{Ca} < 10^{-1}$ [3].

Bretherton's [1] analytical approach resulted in the following expression:

$$m = 1.29\,(3\,\mathrm{Ca})^{2/3} \tag{6}$$

Thulasidas et al. [6] compared their and all other available experimental data on relative bubble velocity, m, with the literature correlations. There was a considerable scattering of the experimental data at the lower values of Ca, particularly for $\mathrm{Ca} < 10^{-2}$, while Bretherton's correlation was found to underpredict all the data. The results showed that m reached a limiting value of 0.58 at large values of Ca.

The more recent literature on bubble velocity has been reviewed by Akbar and Ghiaasiaan [10]. They observed that their data and those of others were well predicted by the following correlation, valid for $2 \times 10^{-4} < \mathrm{Ca} < 0.39$:

$$\frac{U_\mathrm{b}}{U_\mathrm{m}} = \frac{1}{1 - 0.61\,\mathrm{Ca}^{0.33}} \tag{7}$$

where U_m is the mixture velocity calculated from the overall gas and liquid flowrates divided by the area of the tube.

Bubble and Slug Length

Various characteristics in Taylor flow (such as pressure drop and mass transfer rate) depend on the bubble and slug sizes. Thulasidas et al. [6] developed a hydrodynamic analytical model for a unit cell (i. e., a bubble and a slug) that allowed the length ratio of bubble to unit cell to be calculated when the superficial gas and liquid velocities, calculated by dividing gas and liquid flowrates, respectively, with the channel cross sectional area, are known. The absolute lengths depend on the dynamics during two-phase contact made at the inlet. Thus, inlet geometry is expected to affect slug and bubble length.

Kreutzer [11] suggested a correlation for the slug length, L_s, based on experimental data in a 200 cpsi monolith reactor

$$\frac{L_\mathrm{S}}{d} = \frac{\varepsilon_\mathrm{l}}{-0.00141 - 1.556\,\varepsilon_\mathrm{l}^2 \ln(\varepsilon_\mathrm{l})} \tag{8}$$

where ε_l is the liquid volume fraction.

Akbar and Ghiaasiaan [10] conducted computational fluid dynamics simulations to model a unit cell (one bubble and two half-liquid slugs) in a capillary of 1 mm diameter. Their numerical results, as well as experimental data from previous investigators, were predicted well by the following equation:

$$\frac{U_\mathrm{m}^{-0.33}}{\sqrt{L_\mathrm{S}}} = 142.6\,\varepsilon_\mathrm{g}^{0.56} \left(\frac{d}{L_\mathrm{UC}}\right)^{0.42} \mathrm{Re}_\mathrm{g}^{-0.252} \tag{9}$$

where U_m is the mixture velocity, L_UC is the unit cell length, η_g is the gas volume fraction and Re_g is the gas-based Reynolds number, $\mathrm{Re}_\mathrm{g} = \rho_\mathrm{g} U_\mathrm{sg} d / \mu_\mathrm{g}$, ρ_g and μ_g are the gas density and viscosity and U_sg is the gas superficial velocity.

Extensive numerical simulations on the formation and channel flow of Taylor bubbles have also been conducted by Qian and Lawal [12] for gas and liquid superficial velocities from 0.01 to 0.25 m/s in a 1 mm capillary, for $0.09 < \varepsilon_\mathrm{g} < 0.91$, $15 < \mathrm{Re} < 1500$, $0.000278 < \mathrm{Ca} < 0.01$. The inlet configuration was varied either by bringing the two separate fluids into the channel through a T-junction or by premixing them. Interestingly, premixing resulted in shorter bubble or slug lengths. The T-inlet orientation and channel sizes, as well as the gas and liquid superficial velocities, affected the lengths. On the other hand, surface tension had only a slight effect while liquid viscosity had almost no influence. Their set of 148 data was correlated to within 10% by the following equation:

$$\frac{L_\mathrm{UC}}{d} = 1.637\,\varepsilon_\mathrm{g}^{-0.893} (1 - \varepsilon_\mathrm{g})^{-1.05} \mathrm{Re}^{-0.075} \mathrm{Ca}^{-0.0687} \tag{10}$$

Bubble and slug lengths can be obtained by multiplying Eq. (10) with the respective phase volume fractions.

Systematic experimental investigations on the effect of the inlet configuration on the bubble size have been carried out by Amador et al. [13]. T- and Y-junctions with different inlet channel dimensions and fluid joining angles were used as well as a co-flow configuration with the gas in the middle and the liquid in the annulus around it. Three bubble formation mechanisms were identified. In some cases bubble pairing was also observed at the inlet. The bubble length was found to depend mainly on the ratio of the gas to liquid superficial velocities. The size of the gas inlet affected the bubble size but the size of the liquid inlet or the angles at which the fluids joined only had a small effect. The importance of the gas and liquid flowrates on the size of the bubbles formed in a T-junction, was confirmed by Garstecki et al. [14]. Based on scaling arguments they derived the following expression:

$$L_B/w = 1 - \alpha(Q_g/Q_l) \tag{11}$$

where L_B is the bubble length, w is the main channel width, α is a fitting parameter of order 1, Q_l and Q_g are the liquid and gas flowrates.

Pressure Drop

Bretherton's analysis also provided an expression for the pressure drop over the entire length of the bubble

$$\Delta P = 7.16\,(3\,\mathrm{Ca})^{2/3}\frac{\gamma}{d} \tag{12}$$

From numerical simulations Kreutzer [11] derived the pressure drop in a unit cell comprised of a bubble and a slug. At low values of Ca the numerical results were slightly higher than Bretherton's predictions. Simulations indicated that the pressure drop increases with increasing Re and decreasing Ca, while with increasing Ca the effect of inertia on the pressure drop reduces. The extra pressure drop caused by the bubble could be estimated by subtracting the contribution of the liquid flow in the slug from the overall pressure drop. It was found that this extra pressure drop was almost equal to the difference in the interfacial pressure between the tips of the bubble at low Re while at high Re the dramatic increase in the pressure drop over the interface was not reflected in the overall unit cell pressure drop. A strong dependence of the pressure drop on the slug length was found experimentally. Assuming that the overall pressure drop consisted of the pressure drop in the slugs plus a Laplace pressure term caused by the bubbles, the following correlation was suggested for the friction factor, f, in capillaries during Taylor flow. The equation is valid for $2\times10^{-3} < \mathrm{Ca} < 4\times10^{-2}$ and $100 < \mathrm{Re} < 900$:

$$f = \frac{16}{\mathrm{Re}}\left[1 + \alpha_1\frac{d}{L_S}\left(\frac{\mathrm{Re}}{\mathrm{Ca}}\right)^{\frac{1}{3}}\right] \tag{13}$$

where α_1 was found from the numerical simulations to be 0.07, while a value of 0.17 fitted the experimental data better. The difference was attributed to the presence of impurities. The following equation was proposed for low values of Re:

$$f = \frac{16}{\mathrm{Re}}\left[1 + \frac{d}{L_S}\frac{0.465}{\mathrm{Ca}^{\frac{1}{3}}}\right] \tag{14}$$

The pressure drop is then found from $\Delta P/L = 2f\rho U_m^2\varepsilon_l/d$, where L is the channel length.

Non-Circular Channels

In contrast to circular channels there is less information available on Taylor flow in non-circular channels and most of the information that is available refers to square channels. In square channels at $\mathrm{Ca} < 0.1$ the bubble is not axisymmetric and flattens out against the tube walls leaving liquid regions in the corners which are joined by thin flat films at the sides of the channels. As Ca increases the bubble becomes axisymmetric and for high values of Ca the bubble radius reaches an asymptotic minimum value, approximately equal to 0.68 times the square channel half-width [15]. A stagnation ring forms at the bubble surface at low values of Ca, but for $\mathrm{Ca} > 0.54$ the liquid completely bypasses the bubble. In upward and downward flows complete bypass occurs at $\mathrm{Ca} = 0.5$ and $\mathrm{Ca} = 0.57$, respectively [6]. Differences were also observed in the thickness of the film and in m between the upward and downward directions. The bubble relative velocity asymptotically approached a limiting value of $m = 0.6$ at high values of Ca in both the upward and downward flows.

Examples of Applications

One of the first applications of Taylor bubbles was in flow measurements where the bubbles acted as tracers to determine the velocity of the liquid in the capillaries. Later, however, it was recognized that the presence of the film between the bubble and the wall makes the bubble velocity different from the liquid one.

Applications of Taylor flow in microchannels stem mainly from the good mass transfer characteristics in this flow regime. In Taylor flow the bulk liquid is separated by the gas bubbles which significantly reduces axial mixing between the liquid slugs. The liquid recirculation within the slugs for the range of Ca encountered in small channels (see Fig. 2) also improves the radial mass/heat transfer. Fast multiphase reactions that can be mass transfer limited can benefit from improved radial mixing. In fact, much of the information on Taylor flow originates from the investigation and characterization of monolithic reactors where the two fluid phases are introduced into the reactor as froth flow and pass through catalyst-coated channels in a Taylor flow pattern. The performance of operations such as liquid chromatography within tubes with absorbing walls and tubular dialysers can be improved if Taylor bubbles are introduced in the single-phase flow because they reduce backmixing. Even microfiltration efficiencies have been found to improve when Taylor bubbles have been introduced in the liquid medium. This improvement has been attributed to pressure pulsations caused by the alternating passage of slugs and bubbles.

In the past, the low axial mixing properties of Taylor flow were used in automated analyzers, to avoid cross-talking between successive samples. The same concept applies to high throughput screening where Taylor bubbles facilitate the sequential passage of different reactants/samples through a microchannel reactor/analyzer. The enhanced heat and mass transfer rates that are possible in microchannels can enable a kinetically controlled operating regime to be established that would allow evaluation of reaction kinetics.

Investigations on Taylor flow in non-circular channels originated from flows in porous materials, for instance in enhanced oil recovery. They are also relevant to microstructured reactors and to the many monolithic systems which in many cases have non-circular reaction channels.

Cross References

- ► Bubble Dynamics in Microchannels
- ► Pressure Driven Two-Phase Flows

References

1. Bretherton FP (1961) The motion of long bubbles in tubes. J Fluid Mech 10:166–188
2. Ghiaasiaan SM, Abdel-Khalik SI (2001) Two-phase flow in microchannels. Adv Heat Transf 34:145–254
3. Taylor GI (1961) Deposition of a viscous fluid on the wall of a tube. J Fluid Mech 10:161–165
4. Giavedoni MD, Saita FA (1997) The axisymmetric and plane case of a gas phase steadily displacing a Newtonian liquid – A simultaneous solution to the governing equations. Phys Fluid 9(8):2420–2428
5. Giavedoni MD, Saita FA (1999) The rear meniscus of a long bubble steadily displacing a Newtonian liquid in a capillary tube. Phys Fluid 11(4):786–794
6. Thulasidas TC, Abraham MA, Cerro RL (1995) Bubble train flow in capillaries of circular and square cross section. Chem Eng Sci 50(2):183–199
7. Ratulowski J, Chang HC (1990) Marangoni effects of trace impurities on the motion of long gas bubbles in capillaries. J Fluid Mech 210:303–328
8. Edvinsson RK, Irandoust S (1996) Finite-element analysis of Taylor flow. AIChE J 42(7):1815–1823
9. Aussilous P, Quére D (2000) Quick deposition of a fluid on the wall of a tube. Phys Fluid 12(10):2367–2371
10. Akbar MK, Ghiaasiaan SM (2006) Simulation of Taylor flow in capillaries based on the volume-of-fluid technique. Ind Eng Chem Res 45:5396–5403
11. Kreutzer MT (2003) Hydrodynamics of Taylor flow in capillarties and monolith reactors. PhD Thesis, Technical University of Delft, Delft
12. Qian D, Lawal A (2006) Numerical study on gas and liquid slugs for Taylor flow in a T-junction microchannel. Chem Eng Sci 61:7609–7625
13. Amador C, Salman W, Sanguanpiyapan S, Gavriilidis A, Angeli P (2004) Effect of gas/liquid inlet conditions on slug length in Taylor flow. Proceedings 5th International Conference on Multiphase Flow (CD-ROM), Japan
14. Garstecki P, Fuerstman MJ, Stone HA, Whitesides GM (2006) Formation of droplets and bubbles in a microfluidic T-junction – scaling and mechanism of break-up. Lab Chip 6:437–446
15. Kolb WB, Cerro RL (1993) The motion of long bubbles in tubes of square cross-section. Phys Fluid 5(7):1549–1557

TCR

► Temperature Coefficient of Resistance

Temperature Coefficient of Resistance

Synonyms

TCR

Definition

The relative change in the resistance of a substance per unit change in temperature. The units of TCR are K^{-1}, sometimes expressed as %/K.

Temperature Control

- ► Reaction Condition Control
- ► Temperature Gradient Generation and Control

Temperature Control in Microfluidic Systems

CHAN HEE CHON, DONGQING LI
Department of Mechanical Engineering,
Vanderbilt University, Nashville, TN, USA
Chanhee.chon@vanderbilt.edu,
dongqing.li@vanderbilt.edu

Synonyms

Temperature control system in microfluidic chips; Integrated temperature control in microfluidic systems; Microfluidic system control modules; Thermal control in microfluidic modules

Definition

Temperature control in microfluidic systems is a way to control the temperature of fluids such as water, chemicals, and biofluids in microfluidic systems or devices by using direct/indirect heating or cooling techniques. The characteristics of the temperature control in microfluidic systems are very small control volume, shorter period of control time, small size of control areas/mass, and small size of control devices.



Temperature Control in Microfluidic Systems, Figure 1 Contact external heating methods for microfluidic devices: (**a**) heat exchanger heater [1], (**b**) Peltier thermoelectric heater [2], and (**c**) thin resistive heater [3]



Temperature Control in Microfluidic Systems, Figure 2 Infrared non-contact external heating methods for microfluidic devices [4]

Overview

Due to smaller sample volumes and larger surface-to-volume ratios, the thermal control of microfluidic systems shows many advantages such as small amount of energy, simpler control system, and shorter control time. Precise control and rapid thermal control are also required in certain processes such as the polymerase chain reaction (PCR).

These temperature control techniques for microfluidic devices can be divided into two categories: external temperature control and internal temperature control. External temperature control systems control temperature by using external heating and cooling elements such as a heater and fan and a thermoelectric heater–cooler. Internal temperature control systems achieve heating and cooling with a thermal system embedded in microchannels.

External Heating Technique

The external heating technique relies on heating working fluids in a microchannel with separated heating elements. This is also divided into two types by heat transfer methods: contact and noncontact.



Temperature Control in Microfluidic Systems, Figure 3 Internal heating methods for microfluidic devices: (**a**) micromachined reactor [5], (**b**) Joule heating heater [6], (**c**) endothermic/exothermic heater [7]

In contact-type heating (Fig. 1) one clamps or glues heating elements on the surfaces of channels or containers which contain working fluids and heat is transferred into the fluids by conduction from the heating elements. Heat exchanging [1] by contacting the microsystem to the passively heated or cooled surfaces is widely used to control temperature. However, it is too bulky and limits are involved in integrating a microsystem. The Peltier thermoelectric heater–cooler system [2] is an example of this heating technique. The Peltier heater–cooler is a small solid-state device that functions as a heat pump. It is a sandwich formed by two ceramic plates with an array of small bismuth telluride cubes in between. When a DC current is applied, heat is moved from one side of the device to the other – where it must be removed with a heat sink. The cold side is commonly used to cool an electronic device. If the current is reversed, the device becomes a heater. Another example of contact-type heating involves temperature control by resistive heating elements [3]. Heat is generated when electricity flows in the high-resistance material as in an electric heater.

Noncontact-type heating allows heat transfer by noncontacting methods to fluids such as radiative and ultrasonic heating. Infrared temperature control [4] is a noncontact heating technique, which uses the infrared excitation of a vibration band of water combined with a high-power halogen light bulb and an optical filter (Fig. 2).

Internal Heating Technique

The internal heating technique incorporates heating elements in microfluidic devices to control temperature of fluids. A widely used technique is direct fabrication of a heater or reactor [5] inside of a microchannel or chamber. This requires a microfabricating process to manufacture


Layout component side
Layout inner layer
Prepreg
Internal heat sink
Prepreg
Layout inner layer on carrier
Layout solder side
Coolant channel
a
Reservoir
Reservoir feed line
Vapor line
Evaporator capillary pump
Condenser
Liquid line
b
Microjet
Orifice plate
Fan
Adhesive tape
Baffle plate
Air Flow
Cold plate
Processor
Motherboard
Aluminium back plate
Baffle
c
Air blowing
d

Temperature Control in Microfluidic Systems, Figure 4 Cooling methods for microelectronic or integrated electronic circuits/chips: (**a**) integrated microcooling with microchannels etched on the back of chips [8], (**b**) microcapillary pumped loop cooling [11], (**c**) microjet cooling [12], and (**d**) microfin array cooling [13]

the microheater system to fit in the microscaled container. In electrokinetically driven microflow, naturally generated Joule heating in the channel is used to control the temperature of fluids [6].

Guijt et al. [7] suggested an on-chip heating and cooling technique by using endothermic or exothermic processes in a microchannel to cool or heat solutions within an adjacent sample channel. Chemical or physical processes of solutions in a channel such as evaporation of acetone and exothermic dissolution of H_2O_4 in water are used to cool and heat an adjacent channel (Fig. 3).

Cooling

Currently the most popular cooling method is the externally controlled passive cooling technique using traditional convection heat transfer and heat exchanging techniques such as fins [1], a fan [3], and compressed air for microfluidic device cooling. Integrated cooling techniques for microfluidic devices are very limited such as the Peltier thermoelectric cooler [2] and endothermic cooler [7] mentioned above.

There are several techniques (Fig. 4) for heat removal for microelectronics or integrated circuits or chips not involving microfluidic devices. These techniques may be possible to apply for microfluidic system cooling in the near future. Integrated microcooling flowing water through microchannels etched on the backs or sides of electronic chips is used for heat dissipation in high energy generating electronic components [8]. High-efficiency evaporative heat transfer is applied for heat dissipation of electronic devices: thermosiphons [9], heat pipe cooling [10], and capillary pumped loops [11]. Air-based microelectromechanical devices such as air microjets [12] and microfin arrays [13] also effectively remove heat from microelectronic devices.

Cross References

- ► Electronics Cooling
- ► Heat Transfer in Microchannel Flows
- ► Joule Heating in Electrokinetic Flow: Theoretical Methods
- ► Joule Heating vs. Chip Materials

- ► Methods for Temperature Measurements
- ► Micro Heat Pipes
- ► Microscale Energy Conversion Devices
- ► PCR Lab-on-Chip Devices
- ► Temperature Gradient Generation and Control

References

1. Kopp MU, deMello AJ, Manz A (1998) Chemical amplification: Continuous-flow PCR on a chip. Sci 280:1046–1048
2. Khandurian J, McKnight E, Jacobson SC, Waters LC, Foote RS, Ramsey JM (2000) Integrated system for rapid PCR-based DNA analysis in microfluidic device. Anal Chem 72:2995–3000
3. Xiang Q, Xu B, Fu R, Li D (2005) Real Time PCR on Disposable PDMS Chip with a Miniaturized Thermal Cycler. Biomed Microdevices 7:273–279
4. Roper MG, Easley CJ, Legendre LA, Humphrey JAC, Landers JP (2007) Infrared temperature control system for a completely noncontact polymerase chain reaction in microfluidic chips. Anal Chem 79:1294–1300
5. Srinivasan R, Hsing IM, Berger PE, Jensen KF, Firebaugh SL, Schmidt MA, Harold MP, Lerou JJ, Ryley JF (1997) Micromachined reactors for catalytic partial oxidation reactions. AIChEJ 43:3059–3069
6. de Mello AJ, Habgood M, Lancaster NL, Welton T, Woodtton RCR (2004) Precise temperature control in microfluidic devices using Joule heating of ionic liquids. Lab Chip 4:417–419
7. Guijt RM, Dodge A, van Dedem GWK, de Rooij NF, Verpoorte E (2003) Chemical and physical processes for integrated temperature control in microfluidic devices. Lab Chip 3:1–4
8. Schutze J, Ilgen H, Fahrner WR (2001) An integrated micro cooling system for electronic circuits. IEEE Tran Ind Electron 48:281–285
9. Murthy SS, Joshi YK, Nakayama W (2000) Single chamber compact thermosyphons with micro-fabricated components. InterSociety Conf Thermal Pheonemena 321–327
10. Xie H, Ali A, Bhatia R (1998) The use of heat pipes in personal computers. InterSociety Conf Thermal Pheonemena 442–448
11. Pettigrew K, Kirshberg J, Yerkes K, Trebotich D, Liepmann D (2001) Performance of a MEMS based micro capillary pumped loop for chip-level temperature control. IEEE Int Conf MEMS 427–430
12. Campbell JS, Black WZ, Hartley JG (1998) Thermal management of a laptop computer with synthetic air microjets. InterSociety Conf Thermal Pheonemena 43–50
13. Go JS, Kim SJ, Lim G, Yun H, Lee J, Song I, Pak E (2001) Heat transfer enhancement using flow-induced vibration of a microfin array. Sens Actuators A 90:232–239

Temperature Control System in Microfluidic Chips

- ► Temperature Control in Microfluidic Systems

Temperature Effects on the Zeta Potential

ROBERTO VENDITTI
Department of Mechanical and Industrial Engineering,
University of Toronto, Toronto, ON, Canada
roberto.venditti@gmail.com

Definition

The ►zeta potential (ζ) depends on the surface charge that appears at the interface of a liquid:solid pair when the two are brought into direct contact. The zeta potential represents the electrical potential generated as a consequence of this electrical surface charge. The zeta potential is normally treated as being invariant with respect to temperature, but recent experiments have suggested that this is not always accurate. It is important to have a precise estimate of ζ because calculation of ►electroosmotic flow velocity in a microchannel (using the ►Smoluchowski equation) depends directly upon this value.

Overview

When a solid surface is in contact with an aqueous solution, a thin region of nonzero net charge density forms near the interface. The arrangement of the charges at the solid–liquid interface and the balancing counterions in the liquid is usually referred to as the electrical double layer (EDL). There is a thin layer of counterions immediately next to the charged solid surface, called the compact layer. The counterions in the compact layer are immobile due to strong electrostatic attraction. Counterions outside the compact layer are mobile. This part of the EDL is called the diffuse layer. The zeta (ζ) potential is the electrostatic potential at the boundary dividing the compact layer and the diffuse layer [2].

Application of an external electric field along a microchannel exerts a force on the EDL which can be used to drive fluid motion. This method is commonly referred to as electroosmotic flow (EOF). EOF is one of the most popular methods used to induce fluid motion in microfluidic systems (the other being pressure-driven) because it has many advantages, particularly by way of offering precise control over liquid motions.

When measured at elevated temperatures, experimentally-observed EOF velocities of liquids in microchannels are sometimes considerably higher than those predicted analytically using the *Smoluchowski equation* [1, 2],

$$U_{\mathrm{av}} = \left(\frac{\varepsilon_r \varepsilon_0 \zeta}{\mu}\right) E_z \qquad (1)$$



Temperature Effects on the Zeta Potential, Figure 1 Average electroosmotic flow velocity in a 300 μm × 8 μm PDMS : Glass microchannel filled with 10 mM KCl solution under an applied electric field, E_Z, of 15,900 V/m: (◇) experimentally measured velocity, (□) velocity calculated by Eq. 1, with temperature dependence of viscosity and permittivity considered (but not zeta potential) and (△) velocity calculated by Eq. 1, with no temperature dependencies taken into account

where U_{av} is the average channel velocity, μ, ε and ζ are viscosity, permittivity and zeta potential parameters, respectively, and E_z is the applied electric field strength. This equation is used to calculate the fluid velocity in channels driven by electric fields (i. e. ►electroosmotic flow). Adjusting viscosity and permittivity for temperature improves prediction, but can still be insufficient in some cases. An example of this is shown in Fig. 1, and will be explained in more detail shortly.

It has been demonstrated that the difference between measured and calculated EOF velocities can be adequately explained by treating the zeta potential as a temperature-dependent variable [3]. The particular relationship between ζ and temperature varies depending on the combination of buffer solution and microchannel material being used; in some cases there is a strong dependence, while in others the effect is negligible. Treating the zeta potential as a temperature-dependent variable is a relatively new idea in the field of microfluidics; the traditional approach has been to consider ζ constant over all temperatures [4]. It is important to emphasize that this is not a trivial matter; failure to account for the temperature dependence of ζ has been shown to under-predict EOF velocities by as much as 30% at the sort of elevated temperatures ($\sim 90\,^{\circ}\mathrm{C}$) that are not at all unusual in microfluidic environments (Fig. 1) [3].

The previously-described situation where in-channel fluid temperatures encountered are significantly above ambient conditions is surprisingly common in microfluidic systems. In particular, ►Joule heating effects can produce elevated temperatures in typical microfluidic channels [4]. The Joule heating phenomenon occurs in electrokinetically-driven microfluidic systems. It describes the heat generated as a result of a liquid's inherent resistance to having an electrical current passed through it. Because EOF is generated using electrical fields, current is always present and Joule heating is inevitable. In some cases the resulting elevated temperatures resulting may be sufficient to change the zeta potential to an extent whereby the effect cannot be ignored. In such cases, ζ should be taken as a temperature-dependent variable. The mathematical function used to describe this relationship should be based upon experimentally-derived results, such as those presented in [3].

The publication authored by Venditti et al. [3] describes the results of an experimental investigation that attempts to characterize the influence of temperature on the zeta potential. The work describes the experimental procedure required to measure and classify the relationship between

ζ and temperature for a given liquid : substrate pair. It investigates this relationship for a number of buffer solutions commonly used in the microfluidics community. The influence of buffer concentration on the ζ-temperature curve is investigated. Results are given for both glass and ►poly(dimethylsiloxane) (PDMS) substrates. The consequential effect on calculated EOF velocity is studied and shown to be significant in some cases but negligible in others.

Revil et al. [5] explain that the influence of temperature on the zeta potential is a result of changes in silanol equilibrium, adsorption equilibria, and diffuse double-layer thickness. Their analysis and data is geared towards the geophysical community, but the linear profiles they show describing change in zeta potential with temperature is consistent with [3]. A linear zeta potential-temperature profile is again reported in a more recent paper by Revil et al. [6].

A useful analysis of the effect of temperature on zeta potentials is given by Reppert and Morgan [7]. Their treatment is centred around an analysis of temperature-dependent streaming potentials, which concludes that temperature can have a significant impact on zeta potential. It can be difficult to establish how the data they offered might be applicable in a microfluidic setting, for the same reason that their work is tailored to the geophysical community.

For a thorough review of this topic, see the paper presented by Kirby and Hasselbrink Jr. [8]. This work punctuates the fact that temperature variations can have a significant impact on the zeta potential.

Owing to the vast number of buffer solutions used by the microfluidic community, there are many situations where a researcher might find it impossible to find specific information about the ζ-temperature relationship of the particular reagent being used. In such a case, it is advisable to perform a separate test to evaluate the temperature properties of the solution being used before making any assumptions about whether-or-not the zeta potential can be taken as a constant. The procedure for such an experiment is described in ►Zeta Potential Measurements section to follow.

Basic Methodology

Zeta Potential Measurements

The suggested experimental setup (Fig. 2) and procedure used for zeta potential measurements is identical to that used for the time-interval current-monitoring method of Huang et al. [9]. The procedure used for measuring ζ can be described briefly as follows:

The microchannel and one reservoir are initially filled with the solution to be tested. The other reservoir is filled with a diluted version of the same buffer solution (∼ 95% concentration) and a voltage is applied across the channel. Under the applied electric field, the lower concentration solution gradually replaces the higher-concentration solution. This results in a linearly-decreasing electrical current that ends in a flat plateau (which represents the instant the lower concentration buffer completely fills the microchannel). A schematic illustration of the process is shown in Fig. 3.

The electrical current is arrived at by measuring the voltage drop across a resistor positioned in series with the microchannel as a function of time. The time interval (Δt)



Temperature Effects on the Zeta Potential, Figure 2 Schematic diagram of experimental setup. Microchannel chip placed directly on hotplate surface and Platinum electrodes inserted vertically into reservoirs. Voltage drop measured across a resistor in series with the microchannel was used to calculate current flow in the electrical circuit



Temperature Effects on the Zeta Potential, Figure 3 Schematic diagram of the current-monitoring method used to measure zeta potential (ζ). As time increases, a higher-concentration buffer displaces a lower-concentration version of the same buffer solution. Consequently, the electrical current passing through the channel increases. ζ can be calculated by using the time required for the displacement process (the sloped portion of the current-time curve) in the Smoluchowski equation required for the displacement process is measured and used to calculate the average fluid velocity, U_{av}, according to the relationship

$$U_{\mathrm{av}} = \frac{L}{\Delta t}\,, \tag{2}$$

where L is the total length of the channel. In turn, this average velocity is used in the ►Smoluchowski equation (Eq. 1), allowing for the calculation of zeta potential by direct substitution.

A possible concern lies in determining the time interval of the displacement process. Depending on the current-time curve obtained, it can be difficult to assess the exact starting and ending points of the fluid-displacement time interval. Any error introduced into this value will affect the calculated EOF velocity (Eq. 2) and ultimately influence the calculated value of ζ (Eq. 1). Care should be taken to minimize this error by using sufficiently long displacement periods (as controlled by the applied voltage) that the reading error (typically ~ 0.5 s) represents an acceptably small portion of total experimental time.

Provided buffer concentrations are sufficiently low, parameters of permittivity and viscosity can be taken to be the same as for pure water [10]. After obtaining the current-time curve, the experiment is run again in the reverse direction. This complete process should be repeated at least once, which provides a total of four separate curves for each data point. Having repeatable results helps minimize the influence of inability to precisely evaluate the start and end points of the displacement curve.

An alternative method that can be used to calculate the value of ζ uses the slope of the current-time curve instead of its duration, as described in [2]. This method can be more accurate then the previously-described option because it avoids needing to take measurement from the beginning and ending regions of the plot. Unfortunately, it requires an accurate measurement of the buffer conductivity which can be inconvenient to obtain for the small volumes used in microfluidic systems.

To allow for temperature-dependent measurements, the fluid temperature in the microchannel must be controlled precisely. One possible method for this is to position the microchannel atop a hotplate that can be used to set and maintain precise channel temperatures. The temperature setting is increased after each experimental run and the procedure is repeated once the hot plate is allowed to reach steady-state. The solution in both reservoirs should be replaced between runs to eliminate any effects of electrochemical changes and concentration increases (due to evaporation).

Special attention must be given to the sizing of the critical elements of the experiment. In particular the resistor value should be carefully-selected to provide a measurable voltage drop for the current draw of the system in use. Using Ohm's law, a 500 kΩ resistor would provide a 1 V signal for every 2 μA of current passing through the circuit. This scenario is typically sufficient for relatively high concentration solutions (~ 1 mM) in moderately-sized microchannels ($D_{\mathrm{h}} \sim 15\,\mu$m). If solution concentration is lowered, or channel size is reduced, resistors of higher value might be required (such as 1 V per 0.5 μA) because the net current through the circuit is smaller.

Caution should also be exercised when deciding upon the channel dimensions to be used for measurement. Larger channels result in a higher electrical current that can be measured more-easily, but the higher current implies that the effect of Joule heating is enhanced. This may lead to a less stable measurement condition. Typically the smallest channel that still provides a voltage that is measurable with available equipment should be used.

Selection of the electric field to be used for experimental measurements also requires some care. In general, the voltage to be used should adhere to three experimental concerns:

- Resultant current should be sufficiently high as to be measured reliably
- but also, resultant current should be sufficiently low that no Joule heating effects are observed (i. e. electrical current stable over a span of at least 60 s).
- Experimental time interval should be long enough that reading error does not adversely effect interpretation of experimental results (typically ~ 30 s displacement time is required).

Running the experiment consecutively in opposite directions helps to eliminate any possible influence of pressure-driven flow. This ensures that measured velocity is due to the driving force of the electric field only and results in a more accurate calculation of the zeta potential. Other steps to be taken to minimize pressure-driven effects include meticulously leveling of the channel prior to experimentation, careful balancing of reservoir heights, and use of small channel heights (resulting in increased flow resistance). Large reservoirs should be used such that any change in fluid elevation caused by fluid flow during experimentation is miniscule.

Key Research Findings

From the perspective of a researcher wanting to implement temperature dependence of ζ into calculations of EOF, specific mathematical relationships are most important. For this purpose, Table 1 [3] summarizes ζ-Temperature

Temperature Effects on the Zeta Potential, Table 1 Summary of measured zeta potential results

Solution		Concentration	$\zeta(30\,°C)$ [mV]	$\zeta = \zeta(T)$[mV, °C]
KCl	(a)	0.1 mM	– 108.2	– 0.06 T – 107.4
	(b)	1 mM	– 92.6	– 0.44 T – 78.2
	(c)		(– 78.2)	(– 0.20 T – 72.8)
	(d)	10 mM	– 56.4	– 0.48 T – 43.8
	(e)		(– 38.4)	(– 0.09 T – 35.5)
1X TBE	(f)	89 mM Tris, 89 mM Boric Acid, 2 mM EDTA	– 52.4	– 0.35 T – 40.0
1X TE	(g)	10 mM Tris, 1 mM EDTA	– 68.2	– 0.01 T – 67.9
$Na_2CO_3/NaHCO_3$	(h)	10 mM	– 92.9	+ 0.02 T – 93.1

Bracketed entries denote PDMS:PDMS microchannels. All other entries represent PDMS:Glass.



Temperature Effects on the Zeta Potential, Figure 4 Zeta potential measurements as a function of liquid temperature for a number of commonly-used solutions: (◇) 10 mM KCl, (□) 1X TBE, (△) 1X TE , and (○) 10 mM $Na_2CO_3/NaHCO_3$. All values are for PDMS:Glass microchannels and are normalized to the zeta potential measured at 30°C

relationships for a number of solutions that are commonly used by the microfluidics community. The tabulated data compares the temperature dependence for a number of different solutions, including three different concentrations of KCl. Also considered is the influence of the substrate material on the temperature dependence. Both glass and PDMS are examined, as both are highly-relevant to modern microfluidic applications. The data shown in Tab. 1 represents linear fits to experimental data, and are labeled on the other figures shown in this section. Bracketed entries denote PDMS : PDMS microchannels. All other entries represent PDMS : Glass.

Most of the figures present zeta potential values normalized to the value obtained at 30°C. This relative treatment makes it easier to directly compare solution curves that might otherwise be widely separated because of significant differences in the absolute zeta potential values. Error bars were obtained by considering that the greatest source of experimental uncertainty was present in the measurement of the time interval required for one fluid to displace the other during the current-monitoring procedure. It has been estimated that the time interval can be accurately measured within 1.0 s (i. e. ±0.5 s). Accordingly, this information was used to calculate the range of possible zeta potential values and is reflected in the error bars shown on the figures displaying experimental results.

At this point, Fig. 1 merits further discussion. The experimental curve (◇) displays velocity data obtained by sub-



Temperature Effects on the Zeta Potential, Figure 5 Zeta potential measurements as a function of liquid temperature for a various concentrations of KCl solution: (◇) 10 mM KCl,(□) 1 mM KCl , and (△) 0.1 mM. All values are for PDMS : Glass microchannels and are normalized to the zeta potential measured at 30°C

stituting measured displacement time and channel length into Eq. 2. This particular data set shows values measured for a 10 mM KCl solution in a 300 μm × 8 μm PDMS : Glass microchannel under an applied electric field, E_Z, of 15,900 V/m. If no temperature effects are considered on any of the parameters used to calculate channel velocity (Eq. 1), the curve (△) is obtained. As expected, this plot demonstrates no dependence on temperature; it is clearly inadequate for describing the actually observed temperature-dependent velocity (◇). The next level of refinement to this is to make corrections for the known temperature dependence of the viscosity [10] [kg/m − s] (Eq. 3) and relative permittivity [10] (Eq. 4) parameters (temperatures expressed in Kelvin).

$$\mu = 2.761 \times 10^{-6} e^{\frac{1713}{T}} \tag{3}$$

and

$$\varepsilon = 305.7 e^{\frac{-T}{219}} , \tag{4}$$

This plot is represented by the squares (□) in Fig. 1 (note that the value of the zeta potential is held constant at its room-temperature value). This treatment still fails to accurately predict the EOF velocity in the microchannel. For example, at 90°C the EOF velocity predicted by this approach would be 1.5 mm/s, while the actual velocity is 2.2 mm/s; a 32% underestimation! This plot makes it clear that in some cases the typical approach for velocity estimation is insufficient. Since the zeta potential is the only unaltered variable in the ►Smoluchowski equation (Eq. 1), it is assumed that the discrepancy is owing to inaccuracy in this variable. In these cases the zeta potential should be taken to be a temperature-dependant variable rather than a constant.

Following below are results describing the temperature variation of ζ under a number of different circumstances. Specifically, the effect of temperature on the zeta potential of different solutions is considered. Also described is the influence of buffer concentration and the effect that the substrate material may have on the relationship. The temperatures considered vary between 30°C and 90°C. This range was selected because it is believed to encompass the breadth of temperatures that one would expect to encounter in a microfluidic setting. Testing at increments of 10°C allowed for the capture of sufficient detail to provide meaningful conclusions,

Buffer Comparison

Figure 4 shows the results from a series of tests conducted to determine whether-or-not temperature had any influence on the zeta potential values of solutions considered important to the microfluidics community. It is surprising to note that the zeta potential of some solu-



Temperature Effects on the Zeta Potential, Figure 6 Zeta potential measurements as a function of liquid temperature for KCl solution in microchannels of either Glass substrate: (◇) 1 mM, (△) 10 mM, or PDMS substrate: (☐) 1 mM, (○) 10 mM

tions is strongly-dependent upon the temperature, while others demonstrate almost no temperature influence. For this reason proper care must be exercised when assuming a constant zeta potential over a relatively large temperature span.

Concentration Effects

The concentration of the solution is also known to influence the temperature dependence of the zeta potential. Consider the following test concentrations of KCl solution: 10 mM, 1 mM, and 0.1 mM. The zeta potential of each of these solutions was measured over the range 30°C to 90°C and the temperature response was noted. The results of the concentration effect analysis are shown in Fig. 5. Results obtained clearly indicate that the zeta potential of higher concentrations (e. g., 10 mM, 1 mM) of KCl solution exhibit a strong dependence on temperature, while the low concentration (e. g., 0.1 mM) KCl shows almost no dependence. Specifically, over the same temperature span ($30-90°$C) the magnitude of the zeta potential increases by 53% in the 10 mM KCl case, 33% in the 1.0 mM case, and almost no change is seen in the 0.1 mM case. Furthermore, the results demonstrate (Table 1) that the magnitude of the zeta potential decreases as the solution concentration increases. This is consistent with the findings of other studies [1, 2, 6]. It seems that the zeta potentials of the systems with lower ionic concentration solutions are less affected by the temperature change than their higher ionic concentration counterparts.

Substrate Effects (Glass vs. PDMS)

The results presented herein are geared towards researchers using PDMS-based microfluidic chips. These devices are fabricated with either a glass or PDMS substrate. It is important to understand the influence that changing the channel substrate material has on the $\zeta-$temperature phenomenon. Results illustrate a marked difference between the two substrate materials for different concentration KCl solutions (Fig. 6).

The observed trend for each substrate material is similar. For both substrates tested the magnitude of the zeta potential increased with solution temperature. Interestingly, the rate of change of zeta potential with temperature in the 10 mM case was much lower for the PDMS substrate than for the glass substrate. This was not seen in the 1 mM case, where the curve slope was similar for both substrates. Additionally, the magnitude of the zeta potential value was lower in the PDMS : PDMS than in the PDMS : Glass channels for both solution concentrations tested (-38.4 mV vs. -56.4 mV, and -78.2 mV vs. -92.6 mV for 10 mM and 1 mM KCl at 30°C, respectively). This result agrees with the trend observed by other groups [8] under similar conditions.

Future Directions for Research

Relatively little work has been done to characterize the effect of temperature on the zeta potential. There is much research that must still be done before we have a complete understanding of this phenomenon. The most immediate need is to conduct ζ-temperature characterization experiments for more buffers (different solutions at varying concentrations). This data will allow researchers to account for this effect in any required EOF calculations. Also required is testing in other materials used to form microchannels; silica capillaries, etched-glass, PMMA and other materials used in the microfluidics community.

A research topic of ever-increasing value is to test this effect at the nanoscale. It would be interesting to know if this phenomenon still exists in nanofluidic environments. If it does, particular relationships should be characterized and quantified.

Ultimately, the most important work still remaining is to offer a proper explanation of the phenomenon itself. Why does the zeta potential vary with temperature in some solutions, but not all? We should be able to predict which buffers will have a temperature dependent zeta potential and which will not vary. A theoretical relationship would prove most useful in avoiding the onerous task of compiling and tabulating a vast array of data covering all of the scenarios that a researcher in this field might encounter.

Cross References

- ► Electrical Current-Monitoring Methods
- ► Electrical Double Layers
- ► Electrokinetic Flow and Ion Transport in Nanochannels
- ► Electroosmotic Flow (DC)
- ► Joule Heating in Electokinetic Flow: Theoretical Models
- ► Joule Heating vs. Chip Materials
- ► Methods for Measuring Zeta Potential
- ► Zeta-Potential
- ► Zeta Potential Measurement

References

1. Hunter RJ (1981) Zeta potential in colloid science: principles and applications. Academic, New York
2. Sze A, Erickson D, Ren L, Li D (2003) Zeta-potential measurement using the smoluchowski equation and the slope of the current-time relationship in electroosmotic flow. J Colloid Interf Sci 261:402–410
3. Venditti R, Xuan X, Li D (2006) Experimental characterization of the temperature dependence of zeta potential and its effects on electroosmotic flow velocity in microchannels. Microfluid Nanofluid 2:493–499
4. Erickson D, Sinton D, Li D (2003) Joule heating and heat transfer in poly(dimethylsiloxane) Microfluidic Systems. Lab Chip 3:141–149
5. Revil A, Pezard PA, Glover PWJ (1999) Streaming potentials in porous media 1. Theory of the zeta potential. J Geophys Res 104(B9):20021–20031
6. Revil A, Hermitte D, Spangenberg E, Cochémé JJ (2002) Electrical properties of zeolitized volcaniclastic materials. J Geophys Res 107(B8):2168
7. Reppert PM, Morgan FD (2003) Temperature-dependent streaming potentials: 1. Theory. J Geophys Res 108(B11 ECV3):1–12
8. Kirby BJ, Hasselbrink Jr. EF (2004) Zeta potential of microfluidic substrates: 1. Theory, experimental techniques, and effects on separations. Electrophoresis 25:187–202 and references cited therein
9. Huang X, Gordon MJ, Zare RN (1988) Current-monitoring method for measuring the electroosmotic flow rate in capillary zone electrophoresis. Anal Chem 60:1837–1838
10. Knox JH, McCormack KA (1994) Temperature effects in capillary electrophoresis. 1. Internal capillary temperature and effect upon performance. Chromatographia 38:207–214

Temperature Gradient Focusing

GONGYUE TANG, CHUN YANG
School of Mechanical and Aerospace Engineering,
Nanyang Technological University, Singapore, Singapore
mcyang@ntu.edu.sg

Synonyms

Thermal gradient focusing

Definition

Temperature gradient focusing was first reported by Ross and Locascio [1]. In principle, with an appropriate buffer having a temperature-dependent ionic conductivity, the application of a temperature gradient creates a gradient in both the electric field and electrophoretic velocities. Charged species can be stationary and concentrated at a unique point where the sum of the bulk and electrophoretic velocities is equal to zero. This means that different species, with differing electrophoretic mobilities, can be focused at spatially distinct points along microchannels or capillaries.

Overview

Separation of charged species can be achieved using capillary electrophoresis (CE), a process that utilizes the different electrical mobilities of dielectric particles/macromolecules under an applied electric field. Due to low reagent and sample consumption and high efficiency, CE has become an effective method for the sep-



Temperature Gradient Focusing, Figure 1 Schematic illustration of temperature gradient focusing in a microchannel. The microchannel is heated at one end and cooled at the other, producing a temperature gradient in the middle. The sample solute velocity u_T is the summation of two opposite velocities: the electrophoretic velocity, u_{ep} and the bulk liquid velocity, u_B. As both u_{ep} and u are a function of temperature, there exists a unique point along the channel where the sample solute velocity u_T is equal to zero. The sample solute will then move from both directions toward their respective zero-velocity points where the solutes are focused/concentrated

aration of biologically or chemically charged components, such as DNA sequencing in genetic engineering [2].

However, a typical CE-based separation suffers from relatively poor detection limits, particularly when coupled with UV absorbance detection. Consequently, CE has not been widely adopted for the analysis of drug molecules in biological fluids such as serum or urine in which the drug and its metabolites are usually at much lower concentrations than in a laboratory preparation [3, 4]. To address these problems, novel methods are needed to either improve the detection technology or increase the concentration of the sample prior to detection. For CE involving extremely short optical path lengths, the detection technology has been already pushed to its limit, thus methods of concentrating the sample prior to detection appear to be more promising [5].

Although sample extraction methods are often used to preconcentrate samples before analysis by CE, these methods increase analysis time and cost. Transient stacking, sweeping, or isotachophoresis techniques can also be used in conjunction with CE to improve the detection limits. With these types of methods, the sample is concentrated by causing the sample plug to move across a boundary between two buffers with different compositions in a capillary or microchannel. The two buffer compositions are chosen such that the analytes of interest will move more slowly through one buffer than the other. As the sample plug moves from the fast side of the boundary to the slow side, it is compressed and thus concentrated. Concentration enhancements of the order of 100 – 1000-fold are typical [6]. However, these methods are not universally applicable and often require sample pretreatment or extraction to produce a sufficiently clean sample for stacking.

Temperature gradient focusing (TGF) is a newly developed technique for spatially focusing and separating ionic analytes in microchannels or capillaries. With this method, a controlled flow of buffer is applied to the capillary to counterbalance the electrophoretic motion of the analytes. The basic mechanism of TGF is illustrated in Fig. 1. In this case, by applying a temperature gradient along the capillary filled with a buffer with a temperature-dependent ionic conductivity, a nonuniform electric field along the capillary is created. Consequently, the local flow velocity can be adjusted such that the total velocity, u_T (i. e., electrophoretic velocity, u_{ep} + bulk velocity, u) of an analyte is equal to zero at a unique point along the channel. Analytes will then move inward from both directions toward their respective zero-velocity points where the analytes are focused/concentrated.

The major limitation of microchip CE is that it requires long channels for high resolution separations, and long channels are difficult to fit into the small area of a microfluidic chip without introducing dispersion that degrades the resolution. High-resolution TGF does not require long channels; the separation presented in this study only needs relatively short capillaries (about 20 mm in length), with the separation occurring in only 4 mm of the column (a large proportion of the capillary length is required for attachment to the sample and waste reservoirs). High-resolution microfluidic chip-based TGF separations could conceivably be performed in microchannels that are only a few millimeters long, some of which could easily fit into a small, planar chip format [7].

The temperature gradient required for TGF can either be an externally applied temperature gradient or can be generated by Joule heating due to the applied electric field that also drives the focusing [1]. We will emphasize the latter. It is well known that Joule heating results from the inevitable volumetric heating when an electric field is applied across a conducting medium such as an electrolyte. Such heat would lead to an increase in the buffer temperature and develop temperature gradients in the buffer solution along both radial and axial directions of the microchannel [8]. In the following section we will present a comprehensive numerical model that describes the Joule heating-induced TGF.

Basic Methodology

To address the problems in TGF assosciated with Joule heating, computer-aided numerical simulation is needed to solve the coupled governing equations which will be presented below.

Transport of Charged Solutes

As mentioned earlier, the TGF technique is mainly used for electrophoretic concentration and separation of the solutes, and thus the transport of the charged solutes needs to be modeled. For ease of analysis, it is assumed that there is no adsorption of sample solutes onto the capillary wall and no interaction between the sample solutes and the electrolyte components. In addition, in the vast majority of microfluidic applications, the buffer concentration is many times (100 or more) higher than that of the sample solutes, and hence, the transport equation of the charged solutes can be formulated as [9]

$$\frac{\partial C_{\mathrm{s}}}{\partial t} + \left(\boldsymbol{u} + \boldsymbol{u}_{\mathrm{ep}}\right) \cdot \nabla C_{\mathrm{s}} = \nabla \cdot \left[D_{\mathrm{s}}(T) \nabla C_{\mathrm{s}}\right] \tag{1}$$

where $\boldsymbol{u}$ is the bulk liquid velocity (i. e., electroosmotic flow (EOF) velocity of the buffer solution) and will be described in the next section. C_{s} is the solute concentration and $D_{\mathrm{s}}(T)$ is the temperature-dependent mass diffusivity of the solutes, given by

$$D_{\mathrm{s}}(T) = D_{\mathrm{s}0} f_{\mathrm{D}}(T) \tag{2}$$

where $D_{\mathrm{s}0}$ is the diffusion coefficient of the solutes at room temperature, and $f_{\mathrm{D}}(T)$ is a function accounting for the temperature dependence of the diffusion coefficient of the sample solutes. The electrophoretic velocity of the solutes $\boldsymbol{u}_{\mathrm{ep}}$ can be expressed as

$$\boldsymbol{u}_{\mathrm{ep}} = \mu_{\mathrm{ep}}(-\nabla \phi) \tag{2a}$$

where ϕ is the applied electrical field potential. μ_{ep} is the electrophoretic mobility of the solutes, and can be written as

$$\mu_{\mathrm{ep}} = \mu_{\mathrm{ep}0} f_{\mathrm{ep}}(T) \tag{2b}$$

where $\mu_{\mathrm{ep}0}$ is the electrophoretic mobility of the solutes at room temperature and $f_{\mathrm{ep}}(T)$ is a function accounting for the temperature dependence of the electrophoretic mobility of the solutes.

Flow Field

Since the TGF utilizes the counterbalancing bulk buffer flow (i. e., EOF) and electrophoretic motion, the flow field should be formulated. Considering the buffer solution to be a Newtonian fluid of uniform and homogeneous composition, the laminar, incompressible flow is governed by the Navier–Stokes equation

$$\rho \left(\frac{\partial \boldsymbol{u}}{\partial t} + \boldsymbol{u} \cdot \nabla \boldsymbol{u} \right) = -\nabla p + \nabla \cdot \left[\mu\,(T)\, \nabla \boldsymbol{u}\right] - \rho_{\mathrm{e}} \nabla \Phi \tag{3a}$$

$$\nabla \cdot \boldsymbol{u} = 0 \tag{3b}$$

where $\mu(T)$ is the buffer viscosity, and its dependence on temperature is expressed by $\mu(T) = 2.761 \times 10^{-6} \exp(1713/T)$. ρ and p are the solution density and hydrodynamic pressure, respectively. From Eq. (3a), it can be seen that the evaluation of the momentum equation requires a description of the net charge density, ρ_{e}, and the total electrical potential, Φ. It is assumed that Φ can be decoupled as the summation of the electrical double layer potential, ψ, and the applied electric potential, ϕ, as expressed in Eq. (4)

$$\Phi = \phi + \psi \tag{4}$$

Electrical Double Layer Potential

When a solid surface is in contact with an electrolyte, the surface usually becomes charged. Due to electrostatic interactions, both anions and cations are preferentially redistributed near the charged surface, leading to the formation of an electric double layer (EDL). According to the theory of electrostatics, the EDL potential distribution, ψ is governed by the Poisson equation, written as [9]

$$\nabla \cdot \left[\varepsilon(T) \nabla \psi\right] = -\frac{\rho_{\mathrm{e}}}{\varepsilon_0} \tag{5}$$

where $\varepsilon(T)$ is the dielectric permittivity of the electrolyte, and its dependence on the temperature is given by $\varepsilon(T) = 305.7 \exp\left(-T/219\right)$ [10]. ε_0 is the permittivity of a vacuum.

For a symmetric electrolyte (i. e., both co-ions and counter-ions have the same charge valence, $|\sigma_+| = |\sigma_-| = \sigma$), its ionic concentration distributions for both anions and cations are assumed to follow the Boltzmann distributions [9], and hence the local charge density,ρ_{e}, is given by

$$\rho_{\mathrm{e}} = \sigma e \left(n_+ - n_-\right) = -2\sigma e n_0 \sinh\left(\frac{\sigma e \psi}{k_{\mathrm{B}} T}\right) \tag{6}$$

e is the fundamental charge, T is the absolute temperature, k_{b} is the Boltzmann constant, and n_0 is the ionic number concentration in the bulk electrolyte solution.

Combining Eqs. (5) and (6), we obtain the well-known Poisson–Boltzmann equation expressed as [9]

$$\nabla \cdot \left[\varepsilon(T) \nabla \psi\right] = \frac{2 n_0 \sigma\, e}{\varepsilon_0} \sinh\left(\frac{\sigma e \psi}{k_{\mathrm{b}} T}\right) \tag{7}$$

Applied Electrical Potential

According to Probstein [9], the distribution of the applied electric potential, ϕ is governed by the Laplace equation which is derived on the basis of the law of conservation of current and is written as

$$\nabla \cdot \left[\lambda(T)\nabla\phi\right] = 0 \tag{8}$$

where $\lambda(T)$ is the temperature-dependent electrical conductivity of the electrolyte, and is given by [10].

$$\lambda(T) = \lambda_{+}(T)\,\eta_{+} + \lambda_{-}(T)\,\eta_{-} \tag{9a}$$

$$\lambda_{+}(T) = \lambda_{+0} f_{\lambda+}(T) \tag{9b}$$

$$\lambda_{-}(T) = \lambda_{-0} f_{\lambda-}(T) \tag{9c}$$

Here $[\lambda_{+}(T)$ and $\lambda_{-}(T)]$ and $[\lambda_{+0}$ and $\lambda_{-0}]$ are the ionic conductivity of the cations and anions of the electrolyte at temperature T and room temperature, respectively. $f_{\lambda+}(T)$ and $f_{\lambda-}(T)$ are functions accounting for the temperature dependence of the ionic conductivity of the cations and anions, respectively. η_{+} and η_{-} denote the mole concentration of the cations and anions of the electrolyte, respectively.

Joule Heating-Induced Temperature Field

The Joule heating-induced temperature field is governed by the energy equation expressed as

$$\rho c_{\mathrm{p}}\left(\frac{\partial T}{\partial t} + \boldsymbol{u}\cdot\nabla T\right) = k_{\mathrm{l}}\nabla^{2}T + \lambda(T)\,(\nabla\phi)^{2} \tag{10}$$

where c_{p} and k_{l} are the specific heat and thermal conductivity of the buffer solution, respectively.

In addition, a conjugate heat transfer problem has to be solved to simultaneously account for the heat transfer in the solid channel wall, which is governed by the heat conduction equation expressed as

$$\rho_{\mathrm{s}} c_{\mathrm{ps}}\left(\frac{\partial T}{\partial t}\right) = k_{\mathrm{s}}\nabla^{2}T \tag{11}$$

where c_{ps}, ρ_{s}, and k_{s} are the specific heat, density, and thermal conductivity of the microchannel wall, respectively.

Initial and Boundary Conditions

At the initial time, the microchannel is filled with an electrolyte which has the same solute concentration and temperature as the electrolyte in the inlet reservoir. The fluid is assumed to be initially stationary.

A high voltage is then imposed at the inlet reservoir, and the outlet reservoir is grounded. Due to electroosmosis, the electrolyte carrying the solutes of a given concentration is continuously injected from the inlet reservoir at room temperature, and the heated electrolyte is streamed from the microchannel to the outlet reservoir.

At all channel wall surfaces, the no-slip boundary condition is applied to the velocity field (the Navier–Stokes equation), the fixed zeta-potential boundary condition is imposed on the EDL potential field (the Poisson–Boltzmann equation), and the insulation boundary condition is assigned to the applied electric field (the Laplace equation), and the no-mass penetration condition is specified for the solute mass concentration field (the mass transport equation). In addition, the third-kind boundary condition (i. e., the natural convection heat transfer with the surrounding air) is applied to the temperature field at all the outside surfaces of the fabricated channels to simultaneously solve the energy equation for the buffer solution together with the conjugated heat conduction equation for the channel wall.

Key Research Findings

In this section, numerical simulations of the Joule heating-induced temperature field and the sample solute concentration distributions in a microchannel structure with a step change in cross-section (see Fig. 2) will be presented. Because the total current passing through a dielectric channel is constant, the current density in the narrow channel is higher than that in the wide channel. As shown in Eq. (10), the Joule heating is proportional to the second power of the current density, so more heat is generated in the narrow channel. Consequently, the temperature in the narrow channel is higher than that in the wide channel, resulting in the formation of a sharp temperature gradient at the junction. The variations in the



Temperature Gradient Focusing, Figure 2 Schematic diagram of the microchannel with a step change in cross-section



Temperature Gradient Focusing, Figure 3 Temperature variation along the centerline of the microchannel



Temperature Gradient Focusing, Figure 4 Temperature gradient variation along the centerline of the microchannel

temperature and temperature gradient along the centerline of the microchannel with a step change in cross-section are shown in Figs. 3 and 4, respectively. The microchannel is made of Polydimethylsiloxane (PDMS) sealed with another PDMS sheet. The parameters used in the simulation are similar to those reported by Ross and Locascio [1], and they are the chip dimensions ($W_1 = 7\,\text{mm}$, $L = 17\,\text{mm}$, $L_1 = 4\,\text{mm}$, $H_1 = H_2 = 2\,\text{mm}$) and the cross-sections for the narrow channel ($40\,\mu\text{m} \times 30\,\mu\text{m}$) and the wide channel ($300\,\mu\text{m} \times 30\,\mu\text{m}$) (see Fig. 2). The buffer solution is 20 mM NaHCO_3 electrolyte, the average electric field strength is $E_0 = 1000\,\text{V/cm}$, and the air natural-convection cooling mode is selected (i. e., the convection heat transfer coefficient $h = 10\,\text{W/m}^2\text{K}$). Table 1 provides the expressions for the temperature-dependent functions of the solute mass diffusivity ($f_D(T)$), solute electrophoretic mobility ($f_{ep}(T)$), and buffer electrical conductivity ($f_{\lambda+}(T)$ and $f_{\lambda-}(T)$). The numerical predictions presented in Figs. 3 and 4 are consistent with the experimental data [1]. Experimentally, it was recorded that the temperature spanned the range $23-39\,°\text{C}$ (at room temperature 22 °C, with a maximum gradient of 150 °C/mm. While the numerical simulations show that the temperature varies in the range $28-43\,°\text{C}$ (the room temperature in the simulation is set at 25 °C), with a maximum gradient of 140 °C/mm. Both the initial and injected sample solute concentrations are 8 μM.

Figure 5 shows the simulated sample solute concentration contours at sequential time of 0 s, 40 s, 90 s, 140 s and 190 s after the electric field has been imposed. Figure 6 displays the quantitative results of the sample solute concentrations varying along the microchannel centerline. As shown in Figs. 5 and 6, the simulations provide reasonable predictions which are consistent with the experimental results [1]. Figure 6 also shows that 190 s after the electric field has been applied, the peak of the sample concentration at the channel centerline reaches $2.8 \times 10^{-3}\,\text{M}$ which is 350-fold the initial and injected sample concentrations. A similar value was reported by Ross and Locascio [1].

Future Directions for Research

Concentration/separation of sample solutes is one of most important functions in micro- and nanofluidic systems. TGF has proved to be a promising technique that can achieve concentration and separation in microfluidic devices. However, so far very limited experimental and theoretical investigations have been reported. Experimentally, it is highly desirable to develop various microfluidic structures that can be utilized by the TGF technique to concentrate different samples. Furthermore, more

Temperature Gradient Focusing, Table 1 Expressions for the temperature-dependent functions of the solute mass diffusivity ($f_D(T)$), solute electrophoretic mobility ($f_{ep}(T)$), and buffer electrical conductivity ($f_{\lambda+}(T)$ and $f_{\lambda-}(T)$)

Properties	Expression	Function
$D_S(T)$	$D_S(T) = D_{S0} f_D(T)$	$f_D(T) = [1 + 0.02(T - T_0)]$
μ_{ep}	$\mu_{ep} = \mu_{ep0} f_{ep}(T)$	$f_{ep}(T) = [1 + 0.04(T - T_0)]$
$\lambda_\pm(T)$	$\lambda_\pm(T) = \lambda_{\pm 0} f_{\lambda\pm}(T)$	$f_{\lambda\pm}(T) = [1 + 0.02(T - T_0)]$



Temperature Gradient Focusing, Figure 5 Sample solute concentration contours near the junction of the narrow and wide microchannels at various times: (**a**) 0 s, (**b**) 40 s, (**c**) 90 s, (**d**) 140 s, and (**e**) 190 s



Temperature Gradient Focusing, Figure 6 Distributions of the sample solute concentration along the centerline of the microchannel at various times

experiments should be carried out to characterize the thermo-electrical properties of buffers and samples so as to obtain the temperature-dependent electroosmotic mobility and electrophoretic mobility, as well as buffer conductivity, viscosity and dielectric permittivity for each individual sample and buffer solution. In addition, the development of reliable, accurate, high-resolution, experimental techniques for measuring flow, temperature and sample solute concentration fields in microfluidic channels is needed. Theoretically, the model development of TGF is still in its infancy. The models presented in this study assume the dilute solute sample and linear mass flux–driving forces correlations. However, when the concentrations of the sample solute and the buffer solution are comparable, the aforementioned assumptions break down. Moreover, the channel wall zeta-potential in this situation may become nonconstant. More comprehensive models should be developed to incorporate the solute–buffer and solute–channel wall interactions as well as the heterogeneous distribution of the channel zeta-potentials.

Recent years have seen significant academic interest in nanofluidics. Fundamental research has reached a feverish level. However, no information is available on the demonstration of the TGF in nanofluidic channel structures.

Cross References

- ► Concentration Gradient Generation and Control
- ► Electrothermal Effects
- ► Temperature Control in Microfluidic Systems
- ► Joule Heating in Electrokinetic Flow: Theoretical Methods
- ► Temperature Gradient Generation and Control

References

1. Ross D, Locascio LE (2002) Microfluidic temperature gradient focusing. Anal Chem 74 11:2556–2564
2. Jorgenson JW (1987) Capillary zone electrophoresis: New directions in electrophoretic methods. ACS Symposium Ser 335, Washington DC

3. Scriba GKE (2003) Pharmaceutical and biomedical applications of chiral capillary electrophoresis and capillary electrochromatography: An update. Electrophoresis 24(15):2409–2421
4. Bonato PS (2003) Recent advances in the determination of enantiomeric drugs and their metabolites in biological fluids by capillary electrophoresis-mediated microanalysis. Electrophoresis 24(22–23):4078–4094
5. Ghosal S, Horek J (2005) Mathematical model describing gradient focusing methods for trace analytes. Anal Chem 77(16):5380–5384
6. Urbánek M, Křivánková L, Boček P (2003) Stacking phenomena in electromigration: From basic principles to practical procedures. Electrophoresis 24(3):466–485
7. Balss KM, Vreeland WN, Phinney KW, Ross D (2004) Simultaneous concentration and separation of enantiomers with chiral temperature gradient focusing. Anal Chem 76(24):7243–7249
8. Tang GY, Yan DG, Yang C, Gong HQ, Chai JC, Lam YC (2006) Assessment of Joule heating and its effects on electroosmotic flow and electrophoretic transport of solutes in microfluidic channels. Electrophoresis 27(3):628–639
9. Probstein RF (1994) Physiochemical Hydrodynamics: An Introduction. Wiley, New York
10. Weast R, Astle MJ, Beyer WH (1986) CRC Handbook of Chemistry and Physics. CRC, Boca Raton

Temperature Gradient Generation and Control

BARBAROS CETIN, DONGQING LI
Department of Mechanical Engineering,
Vanderbilt University, Nashville, TN, USA
barbaros.cetin@vanderbilt.edu

Synonyms

Temperature control

Definition

In today's microfluidic technology, electrokinetic transport is used to perform many chemical and biological analyses in Lab-on-Chip devices, such as clinical diagnoses, DNA scanning, cell manipulation, cell patterning, and molecular detection. Due to the presence of an electrical potential gradient in electrokinetic transport, Joule heating is a ubiquitous phenomenon which may lead to an increase in the overall temperature and to temperature gradients in the transverse and longitudinal directions inside the channels. These generated temperature gradients and their control are crucial for the performance of the devices.

Overview

Simply, a temperature gradient can be generated by means of two temperature reservoirs at different temperatures at the inlet and the exit of a microchannel. However, in electrokinetic transport, Joule heating results in heat generation which can also result in temperature gradient generation in the longitudinal and transverse directions inside the microchannels due to

- the effect of the temperature reservoirs at the inlet and the exit of the channel (thermal end effects);
- the different thermal boundary conditions at the channel wall (thermostatted and thermostatted region along the channel wall);
- the cross-sectional area change along the channel; and
- the flow of two parallel streams having different molar concentrations.

These temperature gradients also affect the electrical field, flow field, and concentration field via temperature-dependent electrical conductivity, viscosity, and diffusivity. Large temperature gradients inside channels may cause band broadening and dispersion that leads to inefficient and low-quality separation for separation processes [1]. Effective dissipation of the heat generated by Joule heating is critical for reproducible and efficient separations in electrokinetically driven separation systems. These temperature gradients can also be useful for some applications such as isoelectric focusing (IEF) [2–4] and temperature gradient focusing (TGF) [5, 6]. Therefore, generation and control of the temperature generation inside the Lab-on-Chip are very important to enhance and optimize the performance of the device.

Xuan and Li [7] developed an analytical model to study Joule heating effects on electrokinetic transportation in capillary electrophoresis with thermal end effects by considering the temperature-dependent fluid viscosity and electrical conductivity. They derived closed formulas for steady-state temperature field, applied electrical potential field, pressure field, velocity field, and transient concentration field which provide fundamental understanding of effects of the temperature gradients on transport of heat, electricity, momentum, and mass species in capillary electrophoresis. They showed that Joule heating enhances the transport of samples which can provide a reduction in the analysis time for capillary electrophoretic separations. Despite the time reduction benefit, they also showed that Joule heating and thermal end effects increase the sample dispersion which leads to a lower separation efficiency. Xuan and coworkers [8, 9] also studied the same effects with temperature-dependent fluid properties, both numerically [8] and experimentally [9]. They used a caged-fluorescent dye-based visualization technique to measure the EOF velocity profile, and a fluorescence-based thermometry technique to measure the temperature profile inside the channel. They observed concave and convex velocity profiles due to distortion of the plug-like profile because of the induced pressure gradients resulting from the axial temperature gradient.

Non-uniform cooling across the length of the channels can be experienced by some thermostatted portion of the channel either by

1. forced convection of the channel or
2. cooling of the channel by optical infrastructure in the detection region.

This non-uniform dissipation also results in temperature gradients inside the channel. Xuan and Li [10] studied case (1.) and Sinton et al. [11] studied case (2.) for a microcapillary.

Temperature gradients along the channel can also be used to focus different species inside the microchannel. IEF and TGF are the two methods that use this concept for focusing. Temperature generation along the channel is achieved both by using two reservoirs at different temperatures [4, 5] and by using Joule heating by means of the variable cross-sectional area along the channel [2, 3, 5, 6]. Using two parallel flow streams with different molar concentrations also results in non-uniform Joule heating and hence a temperature gradient in the transverse direction as well as the longitudinal direction. Cetin and Li [12] studied the effect of these two streams on the temperature field inside a microchannel for the potential use of this gradient in cell manipulation.

Cross References

- ► Temperature Control in Microfluidic Systems
- ► Methods for Temperature Measurements

References

1. Li D (2004) Electrokinetics in Microfluidics. Elsevier Academic Press, Amsterdam
2. Pawliszyn J, Wu J (1993) Ampholyte-free isoelectric focusing of proteins in cone-shaped capillaries. J Microcol 5:397
3. Fang XH, Adams M, Pawliszyn J (1999) A model of thermally generated pH gradients in tapered capillaries. Analyst 124:335
4. Lochmuller CH, Breiner SJ, Ronsick CS (1989) Open-channel isoelectric focusing in thermally engerdered pH gradients. J Chromatography 480:293
5. Ross D, Locascio LE (2002) Microfluidic temperature gradient focusing. Anal Chem 74:2556
6. Kim SM, Sommer GJ, Burns MA, Hasselbrink EF (2006) Low-power concentration and seperation using temperature gradient focusing via Joule heating. Anal Chem 78:8028
7. Xuan X, Li D (2005) Analytical study of Joule heating effects on electrokinetic transportation in capillary electrophoresis. J Chromatography A 1064:227
8. Xuan X, Sinton D, Li D (2004) Thermal end effects on electroosmotic flow in a capillary. Int J Heat Mass Transf 47:3145
9. Xuan X, Xu B, Sinton D, Li D (2004) Electroosmotic flow with Joule heating effects. Lab Chip 4:230
10. Xuan X, Li D (2005) Electrophoresis 26:166
11. Sinton D, Xuan X, Li D (2004) Thermally induced velocity gradients in electroosmotic microchannel flows: the cooling influence of optical infrastructure. Exp Fluid 37:872
12. Cetin B, Li D (2007) Modeling and Simulation of 2D, electroosmotic flow (EOF) in a slit channel with Joule heating effect. Proc 16th Natl Conf Therm Sci, Kayseri, Turkiye 30 May–2 June 2007

Temperature Measurement, Methods

VINAY K. NATRAJAN, KENNETH T. CHRISTENSEN
Department of Mechanical Science and Engineering,
University of Illinois, Urbana, IL, USA
ktc@uiuc.edu

Synonyms

Thermometry

Definition

Thermometry is the determination of a medium's temperature as inferred from properties of a probe whose characteristics are highly dependent on temperature.

Overview

There exists a growing demand for the development of advanced diagnostics for high-precision temperature measurements at the microscale. This demand is driven by the ever-increasing use of complex microfluidic devices such as micro-total analysis systems (μ-TAS) and μ-heat exchangers. Lab-on-a-Chip devices, which integrate multiple complex laboratory functions onto a single chip-sized substrate, often require precise temperature control to maximize the productivity of chemical operations like mixing, reactions and separations. Such control becomes especially critical when electrokinetic pumping is used for driving flow through these devices, as the current flowing through the buffer solution can result in significant internal heat generation, a phenomenon known as Joule heating. Since most microfluidic-based MEMS devices utilize very high heat and mass transfer rates, a thorough understanding of their thermal transport characteristics is paramount for optimizing their design for increased performance and reliability.

Several methods exist for measurement of fluid and/or surface temperature at both the macro- and micro-scale; however, the appropriate choice of methodology is tightly coupled to the specific application under consideration. Further, the capabilities of many techniques that are commonly implemented at the macroscale are greatly challenged in microscale applications where one wishes to not only resolve the local temperature but also *temperature gradients*. Therefore, any technique employed in this regard must not only have satisfactory spatial resolution but also excellent temporal response since dissipation of thermal gradients at the microscale occurs over extremely short time scales owing to high heat-transfer rates and large surface area-to-volume ratios. As such, obtaining accurate measurements of fluid temperature at the microscale is still a topic of intense research interest.

Until recently, temperature measurements in microfluidic systems were limited to measures of bulk fluid temperature at the inlet and outlet of microfluidic sections or simply measurement of the substrate temperature. With regard to local temperature measurements, thermocouple probes provide highly accurate measures of fluid and/or substrate temperature with excellent temporal response. However, thermocouples can often be physically intrusive and generally suffer from poor spatial resolution since most probes have a characteristic size of several microns or more. Alternatively, microfluidic devices can be fabricated with integrated microscale resistance temperature detectors (RTDs's) embedded in the substrate with spatial extents on the order of a few microns [13]. Micro-RTDs overcome the intrusiveness issues of thermocouples; however, their fabrication can be quite complex and RTDs still suffer from poor spatial resolution which limits their ability to resolve local thermal gradients. Further, while RTDs are convenient for monitoring surface temperature, they do not provide a direct measure of fluid temperature.

While local measures of temperature may suffice for some applications, many others require a detailed description of the spatial and/or temporal variations of temperature on a surface or in a fluid. ► Infrared thermography, for example, involves the imaging of the electromagnetic energy radiated by a surface in a specific infrared band which can be directly related to the surface temperature. However, while infrared thermography yields the spatial distribution of temperature on a surface, it does not provide a measure of fluid temperature In contrast, both thermochromic liquid crystals (TLCs) and ► fluorescent thermometry (a specific application of the more general laser-induced fluorescence (LIF) technique) can provide excellent measures of fluid temperature fields. Thermochromic liquid crystals are organic molecules that behave as a liquid but maintain a crystal-like arrangement akin to a solid. For a certain class of TLCs, the molecules align in a helical pattern that reflects a preferred wavelength when under white-light illumination. Since the pitch of the helical arrangement has strong temperature dependence, the wavelength of the reflected light provides a measure of temperature. Therefore, imaging of the light reflected by a suspension of TLCs in a fluid or a surface coating of TLCs can provide a measure of temperature over a given field of view. In fluorescent thermometry, a fluorescent dye whose ► fluorescence intensity is a strong function of temperature is dissolved in a fluid of interest or is coated on a surface of interest. The fluorescent dye is illuminated with incident light which excites the molecules to fluoresce at a different wavelength and this fluoresced light is recorded by a CCD camera. For many dyes, the intensity of the fluoresced light is a strong function of temperature. Therefore, imaging of the fluorescence, in concert with an a priori calibration of the fluorescence intensity with temperature, provides a measure of the temperature over the field of view. Finally, fluid temperature can be inferred by measuring the Brownian diffusion of sub-micron particles suspended in a fluid of interest since this diffusion process is known to be strongly correlated with temperature. While suitable for assessing fluid temperature, measures of Brownian motion cannot provide an estimate of surface temperature since the technique relies upon the free motion of particles suspended in a fluid.

All of the aforementioned methods certainly have many advantages and disadvantages, particularly when implemented at the microscale. Each of these methods is described in detail below and select applications of these methods at the microscale are highlighted.

Basic Methodology

Contact Temperature Sensors

Principle and Implementation

► Contact temperature sensors represent a class of probes used to infer the temperature of a medium through the thermal equilibrium attained between the sensor and the medium when in contact. In particular, changes in the medium temperature yields a corresponding variation of the sensor resistance or output voltage that can be used to infer the temperature difference via an a priori calibration of the sensor output with temperature.

Of the variety of contact sensors that exist for measurement of temperature, thermocouples are amongst the more commonly implemented probes. Temperature measurement by thermocouple is based on the principle that the contact potential generated when two dissimilar metals are in contact varies with temperature. Therefore, by measuring the difference in the contact potential of a measurement junction that forms the probe tip, relative to that of the reference junction, the temperature difference between the junctions is obtained. Thermocouples can be manufactured from many different combinations of metals, depending on the working temperature range, chemical sensitivity of the probe and desired sensitivity and accuracy. In general, the use of thermocouples is preferred over other contact sensors because of their relatively short response times and low cost. However, the temperature sensitivity of thermocouples can be quite low ($\sim 50\,\mu\mathrm{V}/^\circ\mathrm{C}$ or less) and their accuracy is limited to approximately $\pm 0.5\,^\circ\mathrm{C}$. Further, the spatial resolution of the measurement domain is inherently limited by the physical dimensions of the probe tip that forms the measurement junction, with most thermocouple probes having a characteristic dimension of several microns or more. Therefore, the use of thermocouples for measurements of temperature at the microscale can be quite restrictive.

Resistance temperature detectors (RTDs) are contact-type temperature sensors that are based on the principle that the electrical resistance of metals increases with temperature. Therefore, RTDs are also commonly referred to as positive-temperature-coefficient sensors. Resistance temperature detector elements are typically manufactured from platinum because of the linear variation of its resistance with temperature, high stability and chemical inertness, while nickel and copper represent lower-cost alternatives. In general, while RTDs have a smaller working-temperature range than thermocouples, their increased stability and higher sensitivity ($\sim 0.35\,\mathrm{mV}/^\circ\mathrm{C}$) provide more accurate measurements of temperature (typically $\pm 0.05 - 0.1\,^\circ\mathrm{C}$). In contrast, RTDs have longer response times than thermocouples, which often renders them unsuitable for instantaneous measurements of temperature fluctuations occurring over short time intervals.

Finally, thermistors represent another class of commonly-implemented contact temperature sensors. As the name suggests, thermistors are thermally-sensitive resistors that are manufactured using semiconductor materials or transition metal oxides. The basic principle of their operation is similar to that of an RTD in that the temperature of a medium is estimated via variations in the resistance of the sensing element with temperature. However, unlike RTDs, thermistors are negative-temperature-coefficient sensors and their resistance varies inversely with temperature, often in a non-linear fashion. Although their pronounced non-linearity limits the working temperature range to within $100\,^\circ\mathrm{C}$, thermistors are known to have high temperature sensitivities ($\sim 10\,\mathrm{mV}/^\circ\mathrm{C}$), short response times and provide highly accurate temperature measurements (typically $\pm 0.02 - 0.05\,^\circ\mathrm{C}$).

Infrared Thermography

Principle

►Infrared (IR) thermography is a non-intrusive, two-dimensional technique for the whole-field measurement of surface temperature. An infrared scanning radiometer (IRSR) detects the electromagnetic energy radiated in the IR spectral band by the surface of interest and converts it into an electronic signal. For an object whose surface temperature is T, the monochromatic radiation of intensity E_λ emitted by the surface can be written using Planck's law as

$$E_\lambda = \frac{\epsilon_\lambda C_1}{\lambda^5 (\mathrm{e}^{C_2/\lambda T} - 1)}, \tag{1}$$

where C_1 and C_2 are the first and second radiation constants, respectively, λ is the wavelength of the radiation being considered and ϵ_λ is the spectral emissivity coefficient that acts as a correction factor to account for radiation from a real surface ($\epsilon_\lambda = 1$ for a blackbody). Integrating Planck's law over the entire spectrum, from $\lambda = 0$ to $\lambda = \infty$, yields the Stefan–Boltzmann law for the total radiation intensity, E, given by

$$E = \epsilon \sigma T^4, \tag{2}$$

where σ is the Stefan–Boltzmann constant.

In general, most IRSR's are tuned to detect the radiation in a limited bandwidth of the IR spectrum and are therefore classified as long-wave (LW) radiometers or short-wave (SW) radiometers depending upon which window in the IR band is to be detected. For such cases, the radiation intensities detected by the radiometers represent intensity values integrated over the given spectral bandwidth. Temperature is then determined from these intensity values using appropriately modified forms of Eqs. (1) and (2).

Implementation

The two basic components of an IRSR are the optics that form the sensing system and the IR detector. Typically, the characteristics of the optics used in IR systems depends upon whether the incoming radiation is detected in the SW or the LW windows. For the case where the incoming SW infrared radiation is scanned, the radiometer utilizes silicon optics with a coating that has a transmittance peak at a radiation wavelength of about $5\,\mu\mathrm{m}$. Additionally, the detector is manufactured from indium-antimonide and gives a spectral response between $3.5\,\mu\mathrm{m}$ and $5.6\,\mu\mathrm{m}$. Further, a broad-band coating of the SW optics can be used to enhance the relative response of the scanner by shifting the lower limit of the SW window down to $2\,\mu\mathrm{m}$. The use of such a broad-band coating may be favorable for applications such as determining the temperature of semi-transparent objects that makes use of spectral filtering, although these systems are more susceptible to atmospheric losses. On the other hand, radiometers used in the

LW band employ germanium optics that have a peak transmission at 10 μm. The detectors used for LW radiometers are typically manufactured from mercury-cadmium-telluride and give a spectral response between 8 and 12 μm in the far infrared. While the choice of the appropriate spectral-band radiometer depends on several factors, systems operating in the LW region are generally used for higher-accuracy measurements due to relatively low atmospheric absorption. However, SW systems are preferred when the surfaces have higher emissivity factors in the SW window.

The IR detector is a transducer that converts the incoming IR radiation into an electronic signal. The most commonly used detectors are photonic detectors, where the release of electrons is directly governed by photon absorption. While photonic detectors have a very short response time (on the order of microseconds), they suffer from poor spectral response and often require cooling to temperatures well below the ambient to allow for rapid scanning, higher temperature sensitivities and lower noise levels. For most practical applications, the overall performance of an IR imaging system is evaluated using its thermal sensitivity, scan speed, image resolution and the dynamic range of the measurements that can be achieved. Typical operating temperature ranges of IRSRs span from −20 to 800 °C, and can be extended to 2000 °C using appropriate filters (the reader is referred to [1] for the specifications of commercially available IRSRs).

Thermochromic Liquid Crystals

Principle

Thermochromic liquid crystals (TLCs) represent collections of long-chain organic molecules, like cholesterol derivatives, that exhibit liquid characteristics while maintaining a crystal-like order akin to a solid. Of interest from a thermometry point of view is the fact that the optical properties of TLCs strongly depend upon temperature. In particular, the wavelength of light reflected by a TLC is highly correlated with its phase (solid, liquid or intermediate) which is in turn dependent upon its temperature. At low temperatures, TLCs exist in a solid-like crystalline phase and eventually transition through intermediate phases to an isotropic liquid phase with increasing temperature. Two intermediate phases typically exist: the smectic and nematic phases. The smectic phase is achieved by heating the solid, causing the molecules to attain a layered order with their long axes oriented in a preferred direction. Upon further heating, the nematic phase is achieved wherein the layering is destroyed but the preferred orientation remains intact. In this phase, the molecules become asymmetric about their long axis, meaning they can rotate slightly with respect to one another. In this *chiral* state, the nematic phase takes the form of a helical structure wherein its pitch, p, selectively reflects white light with a wavelength on the order of p and transmits all other wavelengths. Further, the pitch of the helical structure is strongly dependent upon temperature. Therefore, the temperature of TLCs can be inferred from the hue of the light that they preferentially reflect when exposed to a white-light source.

Thermochromic liquid crystals in their raw form can provide a nearly continuous coating on a surface or a nearly continuous distribution in a solvent, meaning that the spatial resolution of the measurement is likely governed by the imaging system. Unfortunately, TLCs in this form are prone to degradation due to chemical contamination and exposure to ultraviolet (UV) and oxygen. To alleviate such issues, TLCs are typically manufactured in micro-encapsulated forms wherein the TLCs are encased within polymer shells to form discrete particles ranging in size from approximately one micron to nearly a millimeter. The polymer shell shields the TLC from contamination and most degradation issues; however, the spatial resolution of the measurement will likely be limited by the size of the encapsulated TLC particles. In addition, the thickness of the shell can distort the color reflected by a TLC and variations in shell thickness from particle to particle can produce additional variations in a given experiment. Therefore, the thickness of the polymer shell must be minimized to reduce these adverse influences.

Implementation

The experimental setup for measuring temperature via TLCs is rather simple. In a typical experiment, TLCs are either coated on a surface of interest or suspended in a liquid of interest. A white-light source is employed to illuminate a measurement region and the light reflected by the TLCs is recorded by a color CCD camera. The choice in TLCs is quite dependent upon the temperature range one wishes to resolve because the temperature range over which a TLCs reflectivity varies is a direct function of its specific chemical composition. Since it is important to maintain good contrast in recording the light reflected by the TLCs, it is common for the surface upon which the TLCs are coated or the region behind suspended TLCs to be painted black. Once a color image is acquired, the hue of the reflected light must be related to temperature. However, while this hue is strongly dependent upon temperature through the pitch of the TLC helical structure, it is also tied to other experimental parameters. In particular, the wavelength of the reflected light from a TLC is also dependent upon the angle from which the reflected light



Temperature Measurement, Methods, Figure 1 A schematic illustrating the interaction of TLCs with incident light (Adapted from [2])

is viewed as well as the angle and spectral composition of the incident light. Figure 1 illustrates the interaction of incident light with a repeating TLC helical structure. As discussed in [2], a path difference exists between the light reflected by consecutive helical structures given by

$$\overline{AC} - \overline{AB} = \frac{p}{2\cos\theta}(1+\cos 2\theta) = p\cos\theta, \tag{3}$$

where θ represents the angle of the incident and reflected light (they are assumed equal for simplicity). Constructive interference will occur when

$$n\lambda = p\cos\theta, \tag{4}$$

where n is a positive integer and λ represents the reflected wavelength. Therefore, the wavelength of the reflected light is dependent upon both the pitch of the helical structure and θ. A careful calibration of the TLCs hue as a function of temperature must be performed to account for these effects. Such a calibration is achieved by placing the TLCs within an environment wherein the temperature of the TLC is known and can be precisely controlled. Images of the light reflected by the TLCs are then acquired at distinct temperature intervals from which a calibration curve relating hue to temperature can be constructed. However, given the strong dependence of the hue on both the viewing angle as well as the characteristics of the incident light, it is strongly recommended that this calibration be performed in situ to properly account for such variabilities.

While TLCs can be quite sensitive to very small temperature variations, the temperature range over which TLCs reflect from red to blue can be quite narrow, typically on the order of 1 K or less. Coupled with a typical temperature uncertainty of 0.1 K, the relative measurement error using TLCs can be larger than 10%. Further TLCs have several drawbacks for use in micro- and nano-scale devices. First, the lower bound on the size of micro-encapsulated TLCs of a few microns can limit their use in microfluidic devices of comparable size when in suspension since they would likely promote blockage. Further, the lower bound in size inherently limits the spatial resolution of the temperature measurement to a few microns. Therefore, TLCs can often be inadequate for resolving strong temperature gradients that can exist in microscale devices.

Fluorescent Thermometry

Principle

►Fluorescence refers to the process by which a fluorophore returns to its ground state through the emission of energy after absorbing a photon of a given energy. During this process, a portion of this energy is lost by the molecule before the emission occurs as it transitions between energy states, meaning that the emission is of a longer wavelength than the energy it initially absorbed. This shift in wavelength of the fluoresced light relative to the absorption wavelength is known as Stokes shift. While the emission of fluoresced light represents one possible path for the molecule to transition back to the ground state, there exist other non-radiative processes by which an excited molecule can return to its ground state. As such, the efficiency of the fluorescence emission by a dye is often quantified by its quantum efficiency

$$\phi = \frac{k_\mathrm{r}}{k_\mathrm{r} + k_\mathrm{nr}}, \tag{5}$$

where k_r is the rate of emission of photons via fluorescence and k_nr represents the rate at which non-radiative relaxation to the ground state occurs. One key difficulty in exploiting fluorescence to infer temperature is that the fluorophore can sustain significant and irreversible decay of its quantum efficiency due to these non-radiative processes. In particular, repeated exposure to high-intensity incident light increases the probability of this photobleaching effect.

For a dye of concentration C (kg m^{-3}) illuminated with an incident light flux of intensity I_0 (W m^{-3}), the fluorescence energy emitted per unit volume, I (W m^{-3}), is

$$I = I_0 C\phi\epsilon, \tag{6}$$

where ϵ (m^2 kg^{-1}) is the absorption coefficient of the dye. Variations in I with temperature are predominantly attributable to a dye's quantum efficiency, ϕ, which displays some degree of temperature dependence for most organic dyes. While this temperature sensitivity is small for most dyes (typically a fraction of a percent per K), there are other dyes that exhibit significantly stronger temperature dependence, like Rhodhamine B (2.3% K^{-1}). In contrast, ϵ has a very weak temperature dependence, usually of the order of 0.05% K^{-1}. Therefore, by employing a dye whose quantum efficiency is highly-sensitive to temperature variations, the temperature distribution in a fluid or on a surface can be inferred from intensity variations in the light fluoresced by the dye.

Single-Dye Fluorescence Temperature measurement using a single fluorescent dye is the simplest adaptation of fluorescent thermometry at the microscale. If the intensity of the illuminating light flux, I_0, is assumed constant in both space and time, then the ratio of the emitted fluorescence intensity measured at a temperature T to that measured at a reference temperature T_{ref} for a fixed dye concentration is given by the ratio of the quantum efficiencies of the fluorescent dye at these temperatures:

$$\frac{I}{I_{\mathrm{ref}}} = \frac{\phi(T)}{\phi(T_{\mathrm{ref}})} = f(T). \tag{7}$$

Therefore, assuming that the variation of the ratio of quantum efficiencies, or equivalently the ratio of the emitted fluorescence intensities, has been properly calibrated as a function of temperature, an estimate of the unknown temperature distribution is arrived at by comparing its fluorescence intensity to that given by the calibration. The spatial resolution of this measurement is defined by the imaging optics while the temporal resolution is defined either by the framing rate of the imaging camera or by the illumination time of the incident light.

Two-Dye Fluorescence As outlined above, the fluorescence intensity measured by single-dye fluorescence depends solely on temperature *only* if the dye concentration and the incident light flux are constant. While maintaining a constant dye concentration is quite simple, sustaining a constant incident light flux is much more difficult since all illumination sources exhibit some degree of spatial and/or temporal variability in their intensity. As such, the measured fluorescence intensity not only embodies temperature variations through ϕ, but also variations in the illuminating intensity through I_0. Therefore, the accuracy of temperature measurements via single-dye fluorescence is strongly dependent on the stability and homogeneity of the illuminating light source. To alleviate such issues, a two-dye methodology has been developed to improve the accuracy of macroscale fluorescent thermometry. In this technique, spatial and/or temporal intensity variations within the illuminating light source are accounted for via a second fluorescent dye whose quantum efficiency exhibits little, or no, temperature dependence. Therefore, while the intensity of the fluoresced light from the temperature-dependent dye embodies both variations in temperature and illuminating intensity, any variations in the fluorescence intensity of the temperature-insensitive dye are directly attributable to variations in the illuminating intensity. As such, one can account for variable illumination intensity by simultaneously imaging the fluoresced light from each dye with separate CCD cameras and normalizing the fluorescence intensity of the emission from the temperature-sensitive dye by that of the temperature-insensitive dye.

Implementation

A schematic of the imaging configuration used for the measurement of temperature via single- and two-dye fluorescence is presented in Fig. 2. Light from an illumination source, like an Nd:YAG laser, Argon-ion laser or a mercury arc lamp, is directed through an epi-fluorescent filter cube and through a microscope objective lens to excite the fluorescent dye molecules in the microfluidic device. The filter cube allows the relatively weak fluorescent signal to pass to a CCD camera while simultaneously blocking the intense illumination wavelength. Given the relatively weak fluorescent signal from the dye, the CCD camera employed must have very low noise levels and a high sensitivity to the emitted wavelength in order to maximize the signal-to-noise ratio of the measurement. In the case of two-dye fluorescence, the emissions of the two dyes must be imaged separately. Such separation is achieved by adding a second camera and additional spectral filters to the aforementioned single-dye optical arrangement (these additions are identified by the dashed bounding box in Fig. 2). In this optical arrangement, both dyes must have similar excitation wavelengths since the same illumination source is typically used to simultaneously excite both dyes. However, the dyes must have different emission spectra so that they can be effectively separated using low- and high-pass spectral filters just upstream of the cameras.

The exact temperature dependence of the chosen dye(s) must be known before the measured intensity fields for single- and two-dye fluorescence can be faithfully converted to temperature fields. This calibration is accomplished by isolating a fixed amount of each chosen dye at known concentration in a well-insulated reservoir whose temperature is both known and precisely controlled. One then maintains the dye solution at a known temperature, begins illuminating the dye solution and acquires an ensemble of images of the light fluoresced by the dye using the same optical configuration outlined above (Fig. 2). The temperature of the dye is then varied slightly and a new ensemble of images is acquired at this new temperature. This procedure is repeated until image ensembles have been acquired at several known temperatures over the range expected in a given experiment. This procedure allows one to construct a calibration curve of intensity ratio (or equivalently quantum-efficiency ratio) versus


CCD Camera β
Longpass filter
Additional Optics for a two-color µLIFsystem
Shortpass filter
Epifluorescent Filter Cube
CCD Camera α
Epifluorescent Filter Cube
Illumination Source (Nd: Yag laser/ mercury lamp)
Objective Lens
Test Section

Temperature Measurement, Methods, Figure 2 Representative schematic of the optical configuration for microscale ►fluorescence thermometry. The dashed box outlines the additional optics required for a two-dye fluorescence imaging

temperature. In the context of two-dye fluorescence, the calibration methodology is identical except that one must now assess the temperature dependence of both dyes.

Thermometry via Measures of Brownian Motion

Principle

►Brownian motion refers to the random thermal diffusion of a particle immersed in a fluid of interest due to continual collisions between the particle and the fluid molecules that are in continual, random motion. Such an effect is increasingly prevalent as the characteristic length scale of the particle decreases, meaning micron-size, or smaller, particles immersed in an otherwise quiescent fluid will display measurable diffusion owing to Brownian motion. Einstein [3] was the first to quantify the intensity of this diffusion for a spherical particle subjected to Stokes drag law in terms of the mean-square distance of diffusion defined as

$$\langle r^2 \rangle = 6D\Delta t, \qquad (8)$$

where Δt is a time interval much larger than the particle response time and D is the diffusion coefficient given by

$$D = \frac{\kappa T}{6\pi \mu d_p}, \qquad (9)$$

where κ is the Boltzmann's constant, T is the fluid temperature, μ is the dynamic viscosity of the fluid and d_p is the particle diameter. Combining Eqs. (8) and (9) gives

$$\langle r^2 \rangle \propto (T\mu^{-1})d_p^{-1}. \qquad (10)$$

Therefore, the mean-square diffusion is proportional to the thermodynamic state of the fluid through $T\mu^{-1}$ and inversely proportional to the particle size. For fixed d_p, the mean-square diffusion is entirely defined by the thermal character of the fluid through $T\mu^{-1}$ whose temperature dependence is a function of the phase of the fluid. For a liquid, an increase in T will yield a commensurate decrease in μ, meaning that $T\mu^{-1}$ will always increase with increasing temperature. On the other hand, an increase in temperature of a gas enhances the viscosity μ, meaning that the temperature dependence of $T\mu^{-1}$ is a strong function of the specific properties of the fluid. Nevertheless, while Brownian motion can severely limit the accuracy of particle-based methods for inferring the bulk motion of a fluid at the microscale when sub-micron particles are employed (as is sometimes done in the microscopic particle image velocimetry technique), it can be used quite adeptly to infer the *thermal* character of the fluid.

Implementation

In order to determine the temperature of a fluid via Brownian motion of suspended, sub-micron particles, one must estimate the displacement of the particles owing to this random effect. There are many established methodologies for achieving such estimates, including methods for tracking the motion of single particles (particle-tracking velocimetry) as well as techniques for tracking small groups of particles (particle-image velocimetry, PIV). In both cases, the position of a particle or a group of particles must be documented at two or more times. Tracking of sub-micron particles at the microscale can be accomplished using an epi-fluorescent microscope in concert with an appropriate illumination source and a low-noise CCD camera, very much akin to the experimental arrangement used in single-dye fluorescent thermometry (Fig. 2). It is advantageous to employ fluorescently-labeled particles in conjunction with a filter just upstream of the camera that blocks the illumination wavelength and passes the light fluoresced by the particles. This experimental arrangement ensures optimal signal-to-noise ratios of the particle images. An image of the particle positions in a plane of interest in the fluid is then acquired at some time t_1 followed by a subsequent image at $t_1 + \Delta t$. The time interval, Δt, must be chosen carefully, as an underestimation of Δt will limit the diffusion of the particles while overestimation can average away the Brownian diffusion effects and can also compromise the fidelity of the tracking algorithm due to loss of particle images due to out-of-plane motion. Once time-delayed images of the particle positions are acquired, the motion of individual particles can then be assessed (particle tracking) or the motion of groups of particles in pre-defined subareas of the field of view can be tracked using statistical methods (as is done in the microscopic PIV method). Specific applications of these methodologies are presented in section *Thermometry via Measures of Brownian motion*.

Key Research Findings

Resistance Temperature Detectors

In general, most contact temperature sensors are designed to provide single-point temperature measurements, although whole-field temperature measurements may be obtained using spatially-distributed arrays of these sensors. While such measurements are fairly simple to conduct at the macroscale, performing similar measurements at the microscale can often be quite complex for several reasons. Typically, most commercially available contact sensors have probe tips whose diameters are at least of the order of a few hundred microns. This size severely constrains the maximum spatial resolution of the measurements that can be attained. Additionally, since the characteristic sizes of these sensors are of the order of the physical dimensions of the microfluidic devices under investigation, these sensors can often be physically intrusive to the flow. Further, limitations on the in-house fabrication technology of microscale temperature sensors not only limits the minimum physical dimension of the sensing element that can be fabricated but can also severely restrict the choice of sensor material. As such, these limitations affect the sensitivity and the accuracy of microscale temperature sensors in comparison to their macroscale counterparts. In particular, while micro-RTDs and micro-thermistors have shown reasonable promise as contact sensors at the microscale, these limitations have stalled development of micro-thermocouples. Watanabe et al. [12] developed a preliminary micro-thermocouple probe for the measurement of cellular thermal responses. The probe was fabricated by thermally tapering a Pyrex glass tube to produce a micropipette tip of diameter 1 μm where a 50 nm thick layer of nickel was deposited. An insulating film of diamond-like carbon (DLC) was then deposited over the nickel layer. Constantan was chosen as the second alloy to form the thermocouple junction and was deposited at the micropipette tip by ion-sputtering following the removal of a small segment of the DLC coating by focused-ion-beam etching. Although the micro-thermocouple fabricated in this manner was in its preliminary stages of validation, the authors noted that the quality of the junction at the probe tip and the decreased signal-to-noise ratio due to the higher thermal conductivity of the culture solution limited the effective sensitivity of the micro-thermocouple probe. Ryu et al. [11] report the development of a micro-hotwire sensor to monitor the position and speed of advancing liquid fronts in microfluidic channels. A thin film of gold was embedded along the length of the microfluidic channel and used as the sensing element. The resistance of the sensing element as a function of temperature was calibrated and confirmed to be linear. The local fluid temperature was then assessed using this calibration information, from which the speed and position of the advancing liquid front were also determined. The temperature coefficient of the sensing element was measured to be $0.0024\,°\mathrm{C}^{-1}$ and its thermal response time was estimated as 4 ms.

A micro-thermistor sensor array was used by Wu et al. [13] to characterize a microscale heat exchanger that utilized a series of impinging jets exiting from micronozzles. The temperature sensor chip consisted of 64 thermistor-type polysilicon sensors, each of which were 4 μm × 4 μm in dimension and were spaced 500 μm apart from one-another to form an 8×8 array in a 4 mm × 4 mm area at the center of the device. The sensors had a nominal resistance of 20 kΩ at room temperature and a temperature resolution of 0.1 °C. A polysilicon heater having a nominal resistance of 55 Ω was fabricated on the backside of the sensor chip in a manner similar to that utilized to fabricate the micro-thermistor array. Using this experimental setup, Wu et al. [13] showed that a 500 μm jet placed 750 μm above the heated surface cooled the chip from over 70 °C to nearly 35 °C.

Infrared Thermography

In order to obtain quantitative measurements of temperature using IR thermography, an accurate characterization of the IR system performance and its calibration must be performed prior to conducting the actual experiment. Some of the common sources of error in IR thermography include variability in the surface emissivity of the object, inaccurate mapping of the image coordinates back to the physical coordinates of the object, losses due to radiation and use of external supplementary optics. Additionally, radiation from the background can also introduce large uncertainties in the measurement of surface temperatures. This latter issue is exacerbated at the microscale where the uncertainties due to background radiation can severely limit the resolution of the measure-



Temperature Measurement, Methods, Figure 3 (**a**) Schematic of the experimental setup used for the IR temperature measurement of a capillary by [5]. (**b**) Variation of the average Nusselt number as a function of Reynolds number (Adapted from [5])

ments. The issue of obtaining accurate surface temperature measurements at the microscale using IR thermography was addressed by Hestroni et al. [5], wherein IR measurements of temperature in a 1.5 mm heated capillary are reported. Hestroni et al. [5] compensated for the background radiation by maintaining the background temperature as close to the measured temperature of the capillary surface as possible via a thermostat (Fig. 3a). A SW radiometer system with a noise-equivalent-temperature-difference of less than 0.07 K at 30 °C and an uncertainty level of 0.1 °C was utilized. Figure 3b presents the variation of average Nusselt number (Nu) with the Reynolds number (Re) of the water flow through the capillary. These results revealed heat-transfer coefficients considerably lower than that predicted theoretically for laminar flow in the range $10 < \text{Re} < 100$ through larger-diameter tubes.

Thermochromic Liquid Crystals

Höhmann and Stephan [6] utilized TLCs to study the thermal characteristics of an evaporating liquid meniscus in a capillary-driven heat-transfer device. Of particular interest were the heat-transfer characteristics in a microregion where the liquid–vapor interface approaches the boundary. Höhmann and Stephan [6] constructed a model evaporator wall consisting of a thin layer of non-encapsulated TLCs painted on a plexiglass surface followed by a thin layer of black paint. An electrically-heated metal foil was then placed upon the black surface and the evaporating meniscus was allowed to form along the foil surface. This experimental setup allowed a direct measure of the surface temperature below the evaporating meniscus by illuminating the TLCs with white light through the plexiglass and recording the light reflected by the TLCs with a three-chip CCD camera over a field of view of 640 × 480 µm. Use of a three-chip CCD camera allowed separate recording of the red, blue and green components of the reflected light. The authors performed a calibration in situ by maintaining a constant surface temperature, independently confirmed using thermocouple sensors at the surface, and acquiring images of the light reflected by the TLCs. This procedure was repeated for temperatures over the range of interest to calibrate the hue of the light reflected by the TLCs with temperature. Figure 4a presents an idealized schematic of the narrowing liquid–vapor interface of an evaporating meniscus and Fig. 4b presents the measured surface-temperature profile beneath the meniscus. The rapid temperature decrease characteristic of the microregion (approximately 50 µm in length) is clearly resolved in the measurement.

Fluorescent Thermometry

Temperature measurement at the microscale by single-dye fluorescence was first accomplished by Ross et al. [10] using RhB as the temperature-dependent fluorescent dye and a mercury arc lamp for illumination. Ross et al. [10] conducted measurements of fluid temperature distributions resulting from Joule heating in a microfluidic circuit (schematic presented in Fig. 5a) due to electrokinetic pumping. Figures 5b–5f present a time series of fluid temperature fields acquired by Ross et al. [10] through a constriction in the microfluidic circuit. These temperature fields clearly highlight the drastic rise in fluid temperature that can occur in the presence of electrokinetic pumping. A spatial resolution of 1 µm and a temporal resolution of 33 ms were reported, yielding temperature uncertain-



Temperature Measurement, Methods, Figure 4 (**a**) Schematic of the liquid–vapor interface characteristic of an evaporating meniscus. (**b**) Temperature profile along the surface beneath the evaporating meniscus measured with TLCs (Adapted from [6])

ties in the range 2.4 – 3.5 °C with no spatial or temporal averaging. Improved measurement uncertainties (as low as 0.03 °C) were achieved but at a significant cost in spatial and/or temporal resolution. This single-dye methodology was also employed by Erickson et al. [4] to examine Joule heating and heat transfer in electrokinetically-driven flows at the junctions of PDMS and PDMS/glass microfluidic devices. The temperature fields obtained with RhB excited by a mercury illumination source were found to agree with complementary numerical simulations to within ±3 °C. They also reported a repeatability of approximately ±2 °C and a noise level of ±1 °C. Improved noise levels were achieved by applying a Wiener-type filter to their raw image data.

Thermometry via Measures of Brownian Motion

As noted earlier, inferring fluid temperature from the Brownian motion of sub-micron particles suspended in the fluid requires an accurate estimate of the displacement of the particles over a fixed time interval, Δt. Hohreiter et al. [7] used the microscopic PIV technique to estimate the diffusion of groups of particles in pre-defined subareas of the acquired images. In its standard implementation, PIV utilizes time-delayed images of tracer particles to infer the bulk motion of a fluid by correlating subareas of the time-delayed images together. This correlation yields a peak corresponding to the average displacement of the particles in the subarea over the time interval Δt. A displacement vector (or alternatively a velocity vector when the displacement vector is divided by Δt) is then placed at the center of the subarea and the process is repeated throughout the field of view, yielding a velocity field representative of the bulk fluid motion. It is important to note that the spatial resolution of this measurement is exactly defined by the linear dimensions of the chosen subarea. Olsen and Adrian [8] noted that implementing the PIV technique at the microscale with sub-micron particles yields a broadening of the displacement peak computed from the cross-correlation of the time-delayed subareas. Hohreiter et al. [7] exploited this behavior by deriving an expression that relates changes in the cross-sectional area of the correlation peak to $\langle r^2 \rangle$ (the mean-square distance of diffusion due to Brownian motion) and hence the temperature. Hohreiter et al. [7] used this methodology to determine the temperature of a quiescent fluid from the Brownian motion of 700 nm particles suspended in water. Figure 6a presents fluid temperature inferred from the broadening of the correlation peak determined by micro-PIV analysis versus the fluid temperature measured independently with a thermocouple. The average uncertainty is reported as ±3 °C, with the uncertainty increasing slightly with temperature. It should also be noted that since the overall motion of the suspended particles is tracked via the micro-PIV process, this methodology gives one the capability of simultaneously determining *both* the bulk motion as well as the temperature of the fluid when the fluid is in motion. Simultaneous velocity and temperature measurements are particularly important when convective heat-transfer effects are substantial. Park et al. [9] present an alternate methodology for inferring temperature from particle diffusion that involves tracking the three-dimensional motion of *individual* particles using optical serial sectioning microscopy (OSSM). The OSSM technique utilizes a standard epi-fluorescent imaging setup to capture the diffraction patterns of suspended particles from which their positions in a three-dimensional space can be determined (discussion of the OSSM technique is beyond the subject of this contribution; the reader is referred to Park et al. [9] for further details). Therefore, acquisition of time-delayed images of the diffraction patterns of suspended particles enables the



Temperature Measurement, Methods, Figure 5 (**a**) Schematic of a microfluidic circuit through which flow is driven by electrokinetic pumping. (**b**)–(**f**) Temperature fields through a constriction in the microfluidic circuit acquired 0.2, 0.4, 0.6, 1.4 and 3.8 s after the driving voltage was switched on (Adapted from [10])



Temperature Measurement, Methods, Figure 6 (**a**) Fluid temperature determined by micro-PIV assessment of Brownian motion versus the actual fluid temperature measured by a thermocouple (Adapted from [7]). (**b**) Mean-square diffusion distances assessed from OSSM tracking on individual particles as a function of temperature (Adapted from [9])

three-dimensional tracking of their motion, specifically their Brownian motion when the fluid is otherwise quiescent. Figure 6b presents $\langle r^2 \rangle$ as a function of temperature for particles tracked using the OSSM technique as reported by Park et al. [9]. The authors tracked the particle motion in one, two and three dimensions and compared the measured diffusion of the particles to theoretical estimates with deviations of 5.54%, 4.26% and 3.19% reported for the one-, two- and three-dimensional measurements.

Future Directions for Research

It is important to note that most of the community's effort in the area of microscale thermometry has focused on adapting established macroscale methods for implementation at the microscale. While significant progress has been made in this regard, the accuracy of these techniques generally suffers when extended to the microscale. In the area of contact sensors, significant work remains in reducing their physical dimensions to a much less intrusive size. Even with such progress, contact sensors will always suffer from the fact that they only yield a local measure of temperature in isolation and can be highly complex when one fabricates arrays to assess spatial distributions of temperature. In contrast, methods like IR thermometry, TLCs and fluorescent thermometry overcome many of the disadvantages of contact sensors because they are ideally suited for measuring spatial distributions of temperature. Still, the accuracy of these methodologies is severely compromised at the microscale compared to their macroscale implementations due to various limitations outlined herein.

It is likely that the research community will need to consider the development of thermometry methods that are specifically tailored to the micro- and nano-scales. One such example is the development of methods relying on the Brownian motion of sub-micron particles to infer fluid temperature. While the current accuracy of this method is still comparable to most adapted macroscale methods, this technique is unique in that it relies upon a defining characteristic of particle motion at these smaller spatial scales. Another promising methodology that is specifically tailored to micro- and nano-scale systems involves the use of ►quantum dots (nanometer-scale semiconductors) as thermal markers. Quantum dots behave similarly to fluorescent dyes in that they can be excited with an illumination source to fluoresce light with rather large Stokes shifts and their fluorescence intensity is strongly dependent upon temperature. In contrast to most dyes, however, quantum dots have exceptional quantum yields (providing a significant improvement in the signal-to-noise ratio) and they do not suffer from photobleaching effects, meaning that their viability as thermal markers is not compromised by continued exposure to illuminating light.

Cross References

- ► Fluorescence Measurements
- ► Fluorescent Labeling
- ► Liquid Crystal Technique for Measuring Temperature
- ► Methods for Temperature Measurements
- ► Quantum Dots
- ► Resistance Temperature Detectors
- ► Thermocouples

References

1. Carlomagno GM, de Luca L (1989) Infrared thermography in heat transfer. In: Handbook of Flow Visualization Hemisphere, London 531–553
2. Collings PJ, Hird M (1997) Introduction to Liquid Crystals. Taylor and Francis, Oxford
3. Einstein A (1956) Investigations on the Theory of the Brownian Movement. Dover, New York
4. Erickson D, Sinton D, Li D (2003) Joule heating and heat transgfer in poly(dimethylsiloxane) microfluidic systems. Lab Chip 2:141–149
5. Hestroni G, Gurevich M, Mosyak A, Rozenblit R (2003) Surface temperature measurement of a heated capillary tube by means of an infrared technique. Meas Sci Technol 14:807–814
6. Höhmann C, Stephan P (2002) Microscale temperature measurement at an evaporating liquid meniscus. Exp Thermal Fluid Sci 26:157–162
7. Hohreiter V, Wereley ST, Olsen MG, Chung JN (2002) Cross-correlation analysis for temperature measurement. Meas Sci Technol 13:1072–1078
8. Olsen MG, Adrian RJ (2000) Brownian motion and correlation in particle image velocimetry. Optics Laser Technol 32:621–627
9. Park JS, Choi CK, Kihm KD (2005) Temperature measurement for a nanoparticle suspension by detecting the brownian motion using optical serial sectioning microscopy (OSSM). Meas Sci Technol, 16:1418–1429
10. Ross D, Gaitan M, Locascio LE (2001) Temperature measurement in microfluidic systems using a temperature-dependent fluorescent dye. Anal Chem 73:4117–4123
11. Ryu KS, Shaikh K, Goluch E, Liu C (2006) Two-terminal longitudinal hotwire sensor for monitoring the position and speed of advancing liquid fronts in microfluidic channels. Appl Phys Lett 88:104104
12. Watanabe MS, Kakuta N, Mabuchi K, Yamada Y (2005) Micro-thermocouple probe for measurement of cellular thermal responses. In: Proceedings of IEEE-EMBS 27th Annual International Conference 1–4
13. Wu S, Mui J, Tai YC, Ho CM (1999) Micro heat exchanger by using MEMS impinging jets. Proc IEEE MEMS 171–176

Temperature Measurement Using Fluorescence

- ► Fluorescent Thermometry

Temperature Probes

- ► Contact Temperature Sensors

Temperature-Sensitive Hydrogels

HEIKO VAN DER LINDEN, JERRY WESTERWEEL
Laboratory for Aero- and Hydrodynamics
Faculty of Mechanical, Maritime and Materials
Engineering, TU Delft, Delft, Netherlands
heiko.vanderlinden@tudelft.nl

Synonyms

Thermosensitive hydrogels; Thermally-sensitive hydrogels; Intelligent gels

Definition

Temperature-sensitive hydrogels, which are part of the family of stimulus-sensitive hydrogels, consist of water-filled polymer networks (i. e., gels) that display a temperature-dependent degree of swelling. Temperature-sensitive hydrogels are of interest to microactuation purposes for a number of reasons [1]: their volumetric size changes are large compared to other microactuation principles, hydrogels are soft and resilient, temperature-sensitive hydrogel actuators are operated at conveniently low temperatures and the hydrogel polymer networks can be microfabricated using standard photolithography.

Temperature-sensitive hydrogels can either display a positive temperature response, meaning that the gel material swells with increasing temperature, or a negative temperature response, meaning that the gel material shrinks with increasing temperature.

Chemical and Physical Principles

The amount of swelling of hydrogels is a function of two opposing forces. On one side water molecules moving into the hydrogel cause a swelling force, due to molecular interactions with the polymer molecules in the hydrogel. On the other side, the elastic elongation of the coiled-up polymer molecules in the polymer network results in an *elastic retractive force* opposing the swelling force in the hydrogel.

When water is added to a dry, hydrophilic polymer network (xerogel), a swelling hydrogel is formed. During the swelling process, the swelling forces dominate and the elastic retractive force gradually increases with progressive swelling. When the hydrogel is swollen to a degree that the elastic retractive forces have the same magnitude as the swelling forces, the hydrogel reaches equilibrium swelling. If the conditions of the hydrogel are kept stable, the volume of the hydrogel will remain constant indefinitely.

Stimulus-sensitive hydrogels have the unique property that an external physical parameter, e. g., temperature, pH or ionic strength, has an effect on the swelling forces inside the hydrogel. When the magnitude of the physical parameter is changed, the swelling force increases or decreases. As a result the hydrogel changes its degree of swelling to equilibrate the new swelling force with the elastic retractive force.

The thermal behavior of temperature-sensitive hydrogels is a direct result of the thermosensitivity of the molecular interactions between the polymer network inside the hydrogel and the aqueous solution in and around the hydrogel. In the case of a hydrogel made of poly-[N-isopropylacrylamide] (a hydrogel with a negative temperature response), the efficiency of hydrogen bond formation between the polymer and water molecules decreases at higher temperatures. At temperatures below 22 °C water molecules can form hydrogen bonds efficiently with the amide group in the polymer side chains. As a result of the efficient hydrogen bonding, water molecules move into the polymer network, resulting in the swelling of the hydrogel material. When the temperature of the hydrogel is increased to 42 °C, gradually the hydrogen bonding efficiency decreases to a minimum. This process decreases the interaction energy of the polymer network with water molecules and water moves out of the hydrogel. Macroscopically this process is visible as the shrinking of the hydrogel. Physically the temperature-dependent swelling of temperature-sensitive hydrogels can be expressed through temperature-dependent changes in osmotic pressure differences between the hydrogel and its surrounding solution. A temperature increase results in a reversal in osmotic pressure difference and water exits the hydrogel resulting in shrinking. A temperature decrease results in an increase in osmotic pressure difference and the water enters the hydrogel resulting in swelling.

The temperature-dependent swelling behavior of these hydrogels can be represented in a graph by plotting a dimensional property of the hydrogel (e. g., the thickness or diameter of a hydrogel disc) as a function of the temperature stimulus. The resultant graph for poly-[N-isopropylacrylamide] is shown in Fig. 2.

The polymer network of temperature-sensitive hydrogels is made up of smaller repeating units called monomers. In addition to monomers, so-called crosslinker groups are present in the polymer network. The crosslinker groups form connections between different strands of polymer inside the polymer network. As a result a single giant polymer molecule is formed which is incapable of dissolving.

A commonly used monomer for the fabrication of temperature-sensitive hydrogels is N-isopropylacrylamide. This



Temperature-Sensitive Hydrogels, Figure 1 Graphical representation of the reversible swelling and shrinking of temperature-sensitive hydrogels. In the swollen state the polymer molecules in the hydrogel are strongly hydrated. The water molecules force the polymer molecules into a swollen state. In the shrunken state, the polymer molecules are attracted to each other due to the elastic retractive force (arrows), resulting in the expulsion of the water molecules



Temperature-Sensitive Hydrogels, Figure 2 Typical temperature response of a temperature-sensitive hydrogel disc made of poly-[N-isopropyl acrylamide]

monomer has the special property that it displays lower critical solution temperature (LCST) behavior and its solubility is a function of temperature. When the temperature of an aqueous N-isopropylacrylamide solution is increased above the LCST, the monomer will crystallize out of the solution. In a temperature-sensitive hydrogel this behavior is visible in the shrinking response of the hydrogel at temperatures above the LCST.

To polymerize NIPAAm into its polymer network (polyNIPAAm), free radicals are needed to initiate the polymerization reaction. Commonly these free radicals are obtained from chemical compounds called initiators. These initiators generate free radicals due to homolytic bond scission inside the initiator molecule. The bond scission can be induced by temperature or light. These initiators are called thermal initiators and photoinitiators respectively.

The swelling force of a temperature-sensitive hydrogel is a strong function of the hydrophilicity of the side groups in the polymer network. If the polymer network contains highly hydrophilic side groups, the resulting hydrogel will swell more compared to a hydrogel with less hydrophilic side groups. Similarly, the side group hydrophilicity has an effect on the LCST of the temperature-sensitive hydrogel. The composition of the polymer network can be modified by incorporating hydrophobic or hydrophilic comonomers into the polymer network chains. When hydrophobic comonomers are incorporated, the LCST of the hydrogel will move to lower temperature regions. When hydrophilic comonomers are incorporated the opposite effect occurs. Using this method, the temperature region where a temperature-sensitive hydrogel actuator responds can be shifted to higher or lower temperatures [2]. Hence, the response of these actuators can be tailored for a specific need in an application.

Stimulus-sensitive hydrogels, such as pH-sensitive and temperature-sensitive hydrogels can be microfabricated efficiently by photopolymerization [2, 3]. This convenient process allows the use of standard microphotolithography technology (i. e., a mask aligner and photomasks) for the accurate positioning and dimensioning of stimulus-sensitive hydrogel microactuators.

A solution containing the precursors of the hydrogel network (i. e., monomers and crosslinking compounds) and a photoinitiator is deposited onto the substrate where the hydrogels should be fabricated. Using a photomask, selective areas of the precursor solution are irradiated for a sufficient time to allow the polymerization reaction to occur and a polymer network to be formed. After the photopolymerization reaction, the unreacted chemicals are dissolved, by washing the substrate in a suitable solvent. Normally within the period of 10 to 100 s, large numbers of hydrogel actuators can be fabricated with accurately defined dimensions and positions.

Examples of Application

The main focus of research on temperature-sensitive hydrogels as microactuators in microfluidic devices has been on microvalves. Hydrogel actuators have a distinct advantage for microvalve applications since they are very soft and encapsulate dust particles encountered in microfluidic flows. Normally these particles could result in the loss of function of conventional *hard* actuators when these particles get trapped in the actuator. Furthermore, temperature-sensitive hydrogel actuators are controlled by relatively small temperature changes close to ambient temperature (i. e., around 10 K to 20 K). As a result large heating powers are not necessary to control microvalves made out of these materials. Thus affording the possibility of using battery power to control the microvalves. In contrast, most conventional microactuators e. g., piezo or thermal actuators use high voltages or high power to operate.

Stimulus-sensitive hydrogel actuators display a large volume change during swelling and shrinking. Typically this volume change is around 100% to 800% for pH-sensitive hydrogels and 100% to 400% for temperature-sensitive hydrogels. Therefore a small stimulus-sensitive hydrogel actuator can be used to generate a large displacement in a microfluidic device.

Two kinds of temperature-sensitive hydrogel microvalves have been shown in the literature. The first kind of microvalve uses a monolithic piece of hydrogel, which swells and shrinks as a function of temperature to open or close a microchannel. An example of such a microvalve was shown by Yu et al. [4]. Actuation times are relatively short at 3.5 to 5 s and a holding pressure of 1.38 MPa was reported.

A second kind of temperature-sensitive hydrogel microvalve is based on the grafting of thin layers of poly-[N-isopropylacrylamide] on the surface of glass capillaries [5]. The contact angle, and thus the free surface energy, in such a treated capillary is a strong function of the temperature. By changing the temperature of the capillary, the flow of water could be controlled reversibly. The holding pressure of this kind of valve is in the range of 10 MPa.

Future Directions of Research

Because temperature-sensitive hydrogels are still a relatively new material to the field of microfluidics, their full potential in actuation applications has not been reached. It is expected that novel applications will be found where hydrogels replace standard actuators, e. g. electromagnets, but this will only be in cases where the actuation mechanism can be realized in the aqueous environment needed by the hydrogels. Additionally mechanical properties of the temperature-sensitive hydrogel materials have not been thoroughly investigated for microfluidic applications. Therefore it is necessary to both further optimize the characteristics of the actuator material and to come up with a set of design rules to allow the efficient design of temperature-sensitive hydrogel driven microfluidic applications.

Another direction of research could be the use of temperature-sensitive hydrogel thin films to allow fluid control in nanofluidics. Below the LCST these layers will be hydrophilic and above the LCST significantly more hydrophobic. It should be possible to make intelligent hydrophobic patch valves that are switched by temperature.

Cross References

- ► pH-Sensitive Hydrogel
- ► Photosensitive Hydrogels

References

1. van der Linden HJ, Herber S, Olthuis W, Bergveld P (2003) Stimulus-sensitive hydrogels and their applications in chemical (micro)analysis. Analyst 128:325–331
2. van der Linden HJ, Olthuis W, Bergveld P (2004) An efficient method for the fabrication of temperature-sensitive hydrogel microactuators. Lab Chip 6:619–624
3. Beebe DJ, Moore JS, Bauer JM, Yu Q, Liu RH, Devadoss C, Jo B-H (2000) Functional hydrogel structures for autonomous flow control inside microfluidic channels. Nature 404:588–590
4. Yu C, Mutlu S, Selvaganapathy P, Mastrangelo CH, Svec F, Frechet JMJ (2003) Flow control valves for analytical microfluidic chips without mechanical parts based on thermally responsive monolithic polymers. Anal Chem 75:1958–1961
5. Idota N, Kikuchi A, Kobayashi J, Sakai K, Okano T (2005) Microfluidic valves comprising nanolayered thermoresponsive polymer-grafted capillaries Adv Mat 17:2723–2727

Temperature Sensitive Resistor

Synonyms

Hot wire; Hot film

Definition

A temperature sensitive resistor has a high enough temperature coefficient of resistance, indicating variation of electrical resistivity with temperature. A temperature sensitive resistor used for the measurement of fluid flow generally takes the form of either hot wire or hot film. When cooled by the surrounding fluid, its electrical resistance would decrease which reflects the flow rate of the fluid.

Cross References

- ► Integrated Microfluidic Systems for Medical Diagnostics
- ► Heat Transfer in Microchannel Flows
- ► Temperature Control in Microfluidic Systems
- ► Resistance Temperature Detectors
- ► Thermocapacitive Flow Sensor
- ► Thermoelectric Flow Sensors
- ► Thermoresistive Flow Sensors
- ► Liquid Crystal Technique for Measuring Temperature
- ► Methods for Temperature Measurements

Temperature Sensors

► Contact Temperature Sensors

Temporal Averaging

Definition

Temporal averaging is an arithmetical averaging of local similar signals at different point of times. It has the background to increase the quality of the measurement signal and decrease the measurement noise. Using temporal averaging in image processing, several pictures (captured within a time period) are averaged. This causes a loss of temporal resolution.

Terminal Velocity

Definition

Peak velocity of an object in a fluid due to gravity force on the object.

Cross References

- ► Piezoelectric Microdispenser

Test

► Assay

Thermal Anemometer

Synonyms

Micro hot-wire anemometer

Definition

A thermal anemometer typically consists of a heater and one or more surrounding temperature sensors relative to the flow direction. The heater usually works when its self Joule heating is maintained constant. Any fluid flow through the heater will cause a shift in its temperature and thus resistance. By measuring the temperature profile around the heater, the flow rate and direction of the fluid flow can be identified.

Cross References

- ► Fluid Metering
- ► Methods for Flow Rate Measurements
- ► Micro-and Nanoscale Gas Dynamics
- ► Gas Flow in Nanochannels

► Joule Heating vs. Chip Materials
► Thermoresistive Flow Sensors

Thermal Bonding

► Thermal Fusion Bonding

Thermal Bubbles

Ping Cheng[1], Yi-Kuen Lee[2], Peigang Deng[3]
[1] School of Mechanical & Power Engineering,
Shanghai Jiaotong University, Shanghai, China
[2] Department of Mechanical Engineering,
Hong Kong University of Science and Technology,
Hong Kong, China
[3] MEMS Department, China Resources Semiconductor
(HK) Co., Ltd., Hong Kong, China
pingcheng@sjtu.edu.cn

Synonyms

Vapor bubbles

Definition

Thermal bubbles are those bubbles generated by heating in a liquid when its temperature exceeds its nucleation temperature.

Overview

In recent years, advances in microelectronic fabrication technology have led to many vapor-bubble actuators, such as thermal inkjet printheads, vapor-bubble micropumps, vapor-bubble perturbators and DNA microarrayers. In all of these microelectromechanical devices, microbubble(s) are generated on a microheater under pulse heating with pulse widths ranging from microseconds to milliseconds.

Thermal Inkjet Printheads

The thermal inkjet printhead is perhaps one of the most successful microelectromechanical systems (MEMS) products to date. The inkjet printhead uses microheaters (about 20 × 20 μm^2 to 40 × 40 μm^2 in size) under a train of electrical pulses of several microseconds (μs) to periodically generate microbubbles. The microbubble will expel a small droplet of ink through a nozzle at a high frequency to a specified position on a paper to compose the text and graphics. The quality of the printing depends on the thermal properties of the ink, the size of the droplets and droplet velocity, which is closely related to microbubble generation. There are three types of thermal inkjet printheads according to the direction of the ink ejection relative to the direction of vapor-bubble growth. These are: the top-shooter (also called the roof-shooter) with two directions being the same, which has been used in Hewlett-Packard's products [1]; the side-shooter, with the two directions being at right angles to each other, has been used in Canon printers [2]; and the back-shooter, with a droplet being ejected in the opposite direction to bubble growth, was first patented by Bhaskar and Leban [3].

Many improved designs of the top-shooter, side-shooter, and back-shooter types of thermal inkjet printheads have recently been proposed. Lee et al. [4] fabricated a monolithic thermal inkjet printhead, which employed the top-shooter firing mode as shown in Fig. 1. The heater had an area of 40 × 40 μm^2. The nozzles, with a diameter of 50 μm, had a resolution of 300 dpi and a nozzle-to-nozzle pitch of 170 μm. Ink ejection up to the operating frequency of 11 kHz with an average ink dot diameter of about 110 μm was achieved under current pulses of 0.3 A and 5 μs.

Baek et al. [5] have adopted two concepts to improve the nozzle density in the top-shooter design. First, the heater was placed on the sidewall of the ink inlet (see Fig. 2) and thus, the area taken by the heater could be minimized. Second, the manifold, the inlet, pressure chamber, and the nozzle were arranged in a line vertically with respect to the substrate. The nozzle density was improved in this new design although it was not easy to fabricate using MEMS technology.

Tseng et al. [6] have introduced a modified back-shooter design, featuring two heaters with different sizes (see Fig. 3). When a current pulse passed through these two heaters connected in series, the smaller heater generated a bubble faster because of higher power dissipation. The bubble formed under the smaller heater, which can work as a virtual chamber neck, blocking the liquid passage as the larger heater started to generate its own bubble.



Thermal Bubbles, Figure 1 Cross-sectional view of the monolithic "top-shooter" inkjet printhead [4]



Thermal Bubbles, Figure 2 A “side-shooter” inkjet printhead [5]



Thermal Bubbles, Figure 3 An improved design of a “back-shooter” thermal inject printhead with two unequally sized heaters. From Tseng et al. [6]

Expansion of the second bubble pushed the ink ejection. As the two bubbles grew and eventually merged, the tail of the ejected droplet was cut off, preventing the formation of a long tail. The operation frequency of the droplet ejection with a 10 μm dimaeter nozzle was around 35 kHz.

Vapor-Bubble Pumps

Geng et al. [7] have designed a novel pumping device based on the periodic generation and collapse of a single vapor-bubble in a tube. The device consisted of two stainless steel tubes with two different diameters (508 μm and 1067 μm, respectively). A divergent passage was connected from the smaller tube to the larger tubes (see Fig. 4). Pulse heating was applied at the narrow end of the divergent channel, where a vapor bubble was periodically generated and collapsed. Because of the difference in the curvature of the bubble at the narrow tube and the large tube, a capillary force was created that drove the bubble toward the larger tube according to the Young–Laplace equation. At a pulse-heating period of 100 – 1000 ms (i. e., a frequency in the range 10 – 1 Hz), the device could develop a head of a few centimeters of water with flow rates in the range of 100 μl/min.

Jun et al. [8] have used the growth and collapse of a single or multiple vapor bubble(s) to displace fluids in microchannels. The pumping action was provided by asymmetric heating along the microchannels that created a variation in vapor pressure and surface tension due to the heater-induced temperature gradient. A pumping device, consisting of a microchannel with a hydraulic diameter of 3.4 μm and 726 μm in length, was fabricated in a silicon wafer. Three heaters were turned on and off sequentially (Fig. 5) to actuate the movement of vapor bubble(s). It was found that the pulse width (in the range 0.25 – 1 s) and power input (in the range 18 – 26 V) determined whether the micropump could operate in single or multiple bubble mode. Experimental results showed that pumping of isopropanol at velocities as high as 160 μm/s with a pressure head of approximately 800 Pa was achieved.

Thermal Bubble Perturbators

Lin [9] has fabricated a polysilicon microheater with nonuniform width ($10 \times 3 \times 0.5\,\mu\text{m}^3$ and $5 \times 2 \times 0.5\,\mu\text{m}^3$) to generate single microbubbles. This nonuniform microheater can induce highly localized heat source, which can generate a single microbubble periodically at the narrow part of the heater under pulse heating. Using a nonuni-



Thermal Bubbles, Figure 4 Sketch of a microbubble pump, from Geng et al. [7]



Thermal Bubbles, Figure 5 Vapor-bubble pumps for fluid displacement: (**a**) single bubble; (**b**) multiple bubbles [8]

form width microheater (with the slim part having dimensions of $10 \times 3\,\mu\text{m}^2$) under pulse heating in the millisecond range, Deng et al. [10, 11] investigated bubble growth and collapse on the microheater immersed in water as an actuator for mixing and for DNA hybridization enhancement. It was found that when single bubble was generated by pulse heating with the pulse width in the millisecond ranges, the growth and collapse of the bubble was asymmetric, leading to a net perturbation of the local fluid motion [10]. A comparison of molecular beacon-based hybridization assays with and without microbubble agitation revealed that the hybridization time could be effectively shortened by 33% with 10 cycles of microbubble agitation from a 2 × 1 bubble actuator array, and by 43% with 10 cycles of microbubble agitation from a 2 × 2 bubble actuator array [11].



Thermal Bubbles, Figure 6 Schematic diagram of experimental setup [10, 12]

Basic Methodology

The experimental setup for the investigation of microbubble generation and its subsequent dynamics on a microheater under pulse heating is presented in Fig. 6, which shows a test section, a high-speed CCD camera, a microscope, a pulse generation system and a DC power supply. The test section consisted of a nonuniform width platinum microheater submerged in DI water, and the pulse generation system consisted of a control circuit and a switching transistor. Through the microscope and the CCD camera, with its recording process synchronized with the heating process, thermal bubble growth and collapse processes were observed. The platinum microheater was also used as a resistive temperature sensor, and the surface temperature of the microheater versus time was recorded. The temperature inflection point of the surface temperature variation curve can be identified as the nucleation temperature [12].

Key Research Findings

Microbubble Growth and Collapse on a Microfilm Heater

Effects of Pulse Width on Growth and Collapse Periods

The effect of pulse width (in the range 0.015 – 5.0 ms) on the bubble growth and collapse on a nonuniform



Thermal Bubbles, Figure 7 Effects of pulse width on bubble growth and collapse on a $3 \times 10\,\mu m^2$ microheater at 28.2 mW immersed in DI water [10]


0.5 ms
2.5 ms
2 ms
200 ms

Thermal Bubbles, Figure 8 Microbubble growth and collapse on a microheater at a pulse width of 1.66 ms and a power input of 28.2 mW [10]

width microheater (with the slim part having dimensions of $10 \times 3\,\mu m^2$) at a power input of 28.2 mW immersed in water is presented in Fig. 7. It is shown that the diameter of the bubble undergoes a rapid, initial growth period and after reaching a maximum value, it suddenly drops and then the bubble begins to collapse slowly as a result of the condensation process. For the short pulse widths (e. g., in the range 0.015 – 0.18 ms), a single bubble was barely observable on the surface of the microheater and the growth and collapse of the bubble was almost symmetric. When the duration of the heating pulse was in the millisecond range (0.85 – 5 ms), bubble growth and collapse periods became asymmetric with respect to time.

Asymmetric Growth and Collapse Periods and Perturbation Area

Figure 8 shows time-lapse micrographs about the asymmetric bubble growth and collapse periods on the slim part of the microheater ($10 \times 3\,\mu m^2$) at a pulse width of 1.66 ms under a power input of 28.2 mW [10]. It is shown that the bubble grew during the period 0 – 2 ms and then collapsed in the period 2 – 200 ms. The maximum size of the bubble was about 9.2 μm, which was comparable to the larger dimension of the narrow part of the microheater. To investigate the perturbation area, submicron particles (0.96 μm in diameter) were placed in the DI water near the microheater to trace the movement of the fluid, and the movement of the particles was recorded by a high-speed CCD. At such a pulse width and power input, it was found that the asymmetric growth and collapse periods of the bubble led to a perturbation area of fluid that bwas about six times greater than the maximum diameter of the bubble [10].

Effects of Heater Size on Boiling Patterns

Table 1 lists the sizes of different submicron and micron heaters fabricated by Deng et al. [13] for the investigation of heater size effects on bubble shape, boiling patterns and their growth and collapse periods. A series of tests were carried out for submicron and micron heaters immersed in water at 298 K (room temperature) under a 1.66 ms pulse width. It was found that there was a critical feature size for the heater, 10 μm, for this pulse width. The boiling patterns on heaters with a feature size below or above this critical value were quite different, and they can be classified into two groups as shown in Fig. 9. A single spherical bubble was generated periodically with Group I heaters (a)–(f) with width of the slim part of the heater less than or equal to 10 μm, and an oblate vapor blanket was generated periodically with Group II heaters (g)–(k). The fact that the shape of the bubble and boiling pattern depend on the slim part of the heater can be explained as follows: after the incidence of boiling, the water–vapor interface will try to form a spherical bubble within the thin superheated liquid due to the surface tension effect, which is the dominant force at the microscale level. The spherical vapor bubble stops growing near the outer edge of the thin superheated region because of its contact with the cooled

Thermal Bubbles, Table 1 Dimension of various submicron and micron heaters [13]; The length and width are measured at the slim part of the microheater

Heater ID	Length (μm, ±2%)	Width (μm, ±3%)
(a)	0.5	0.5
(b)	1	0.5
(c)	2	1
(d)	10	3
(e)	10	5
(f)	20	10
(g)	30	10
(h)	30	15
(i)	90	30
(j)	150	50
(k)	200	70



Thermal Bubbles, Figure 9 Map of boiling patterns for various sizes of microheaters [13]



Thermal Bubbles, Figure 10 Semi-logarithmic plot of bubble diameter versus time for spherical bubble growth and collapse on submicron heaters and micron-heaters at a pulse width of 1.66 ms [13]

liquid. When the heater has exceeded a certain critical length, the growth of the spherical bubble cannot fit within the thin superheated region, and it grows within the thin superheated region as an elongated bubble on the heater. Because of the larger area of the elongated bubble that is exposed to the outer cooled fluid, the condensation effect is much stronger than the spherical bubble and so it collapses immediately.

Single Spherical Bubble A semi-logarithmic plot of the diameter of spherical bubble as a function of time for the Group I heaters is shown in Fig. 10, which was obtained by using a digital image processing program. The variations in the bubble diameter with time were very similar to each other and a clear bubble growth and collapse process were recorded. In all cases, the spherical bubble growth period was comparable to the width of the heating pulse (1.66 ms). After reaching its maximum size, the bubble began to collapse on the heater surface, and the collapse period, which could last for 10 – 450 ms, was longer than the growth period. The maximum bubble diameter was comparable to the size of the microheater due to the highly localized heating resulting in a superheated zone on the microheater. The bubble lifetime decreased with the heater size due to the shrinking of the superheated zone. Figure 11a shows the growth and collapse of the bubble on a submicron heater having an area of $1 \times 0.5\ \mu\text{m}^2$ at a pulse heating power of 1.3 mW and a heat flux of $112.4\ \text{MW/m}^2$. Figure 11b shows the growth and collapse of the microbubble on a microheater having an area of $10 \times 5\ \mu\text{m}^2$ at a pulse heating power of 38.5 mW and a heat flux of $85.2\ \text{MW/m}^2$. Note that in each of these photos, there is a bright circle at the middle of the spherical bubble, indicating a curved spherical vapor–liquid interface.

Film Boiling Oblate vapor blanket or film boiling was found on the surface of the Group II heaters (g)–(k) with the slim part of the heater greater than 10 μm. Figures 12a and 12b show that boiling patterns on the heaters having an area of $150 \times 50\ \mu\text{m}^2$ and $200 \times 70\ \mu\text{m}^2$, respectively. No single spherical bubble was observed. Instead, an oblate vapor blanket was formed on the heater surface, and it disappeared almost immediately after the pulse heating stopped at 1.66 ms. The light intensity of the vapor layer on the surface of heaters of Group II was fairly uniform, indicating a relatively planar vapor–liquid interface.



Thermal Bubbles, Figure 11 Spherical bubble generated in water under 1.66 ms pulse heating: (**a**) on submicron heater (1 × 0.5 μm^2) at pulse heating power of 1.3 mW and heat flux at 112.4 MW/m^2; (**b**) on a microheater (10 × 5 μm^2) at 38.5 mW at heat flux of 85.2 MW/m^2 [13]



Thermal Bubbles, Figure 12 Oblate vapor blanket on the heater surface (**a**) on a microheater (90 × 30 μm^2) at pulse heating power of 808.2 mW and at a heat flux of 46.3 MW/m^2; (**b**) on a micron heater (200 × 70 μm^2) [13]

Onset of Bubble Nucleation

Effect of Heater Size on Nucleation Temperature and Nucleation Time

Deng et al. [13] experimentally investigated the effects of the size of the heater on the temperature variations of microheaters at a specific pulse width τ of 1.66 ms. The inflection point and temperature discontinuity point of the temporal variations of the surface temperature of the submicron heaters and microheaters were identified as the respective nucleation temperatures. The nucleation temperature and nucleation time for various heaters are presented in Fig. 13. The horizontal axis of this figure is in terms of the featured size of the heater, L_c, which is defined as the square root of the area of the slim part of the heater, i. e., $L_c = (L \times W)^{1/2}$ with W and L being the width and the length of the microheater, respectively. It is shown that the nucleation temperature increases while the nucleation time decreases as L_c decreases. This is because the rate of temperature increase of the heater decreases with the size of the heater.

Microbubble Growth and Collapse and Nucleation Temperature in DNA Solutions

Bubble Growth and Collapse in DNA Solutions

It is known that the viscosity of the single-stranded DNA (ssDNA) solution increases with its concentration [14]. It was found that the overall bubble lifetime in ssDNA solutions decreased distinctly with the increase in the ssDNA concentration [14].

Figure 14 shows the variation of bubble diameter immediately after pulse heating is imposed for the concentrations of 0 μg/μl, 0.1 μg/μl, 1 μg/μl, 6.4 μg/μl, and 10 μg/μl



Thermal Bubbles, Figure 13 Effects of heater size on nucleation temperature and nucleation time at $\tau = 1.66$ ms [13]



Thermal Bubbles, Figure 15 Effects of concentration on the nucleation temperature and time [12]

ssDNA solutions, respectively [14]. In this figure, the time is normalized by the heating pulse width (1.66 ms) and the bubble diameter is normalized by the characteristic size of the microheater L_c. It is shown that the maximum bubble diameter decreases with the increase of the ssDNA concentration. For both DI water and 0.4 µg/µl ssDNA solution, the largest bubbles were recorded 2 ms after the start of the heating process, implying that the bubble kept on growing even though the heating pulse stopped at 1.66 ms, due to the inertia effect. For the case of 1 µg/µl, the maximum-size bubble was recorded at 1.5 ms, implying that the bubble stopped growing at almost the end of the heating pulse. For high concentrations of 6.4 µg/µl and 10 µg/µl, however, the largest bubbles were both recorded at 0.5 ms, indicating that the bubble growth process was much shorter than that at moderate concentrations, and the bubble stopped growing even though the heater was still operating. From this graph, it can be concluded that high concentrations of the DNA macromolecules in a solution can effectively retard the bubble growth by increasing the dissipation of the kinetic energy of the bubbles. As a result, both the bubble growth period and the recorded maximum bubble diameter are distinctively reduced at high DNA concentrations. For medium and low concentrations (1 µg/µl and 0.4 µg/µl, respectively), the bubble growth period is comparable to the heating pulse width.



Thermal Bubbles, Figure 14 Variation of microbubble diameter in ssDNA solutions: (**a**) bubble diameter versus time; (**b**) close-up view of bubble initial growth period [11]

Nucleation Temperature and Nucleation Time in DNA Solutions

The effects of DNA concentration on nucleation temperature and nucleation time are presented in Fig. 15. It is shown that the nucleation temperature increases with DNA concentration. This is because higher nucleation work is required for higher DNA concentrations, leading to higher nucleation temperatures. On the other hand, nucleation time decreases with the increases of the DNA concentration. This is because higher power inputs are required for bubble nucleation in higher DNA concentration, resulting in a faster heating rate and therefore a shorter nucleation time.

Future Directions for Research

Although extensive efforts have been focused on fundamental and applied research on microbubble actuators, the demand for high-speed, high-quality printing will be one of the main drivers of the development of the next generation of inkjet printheads using MEMS technology [15]. In comparison with the other inkjets, such as the piezoelectric type, the bubble actuator-based inkjet has the advantages of a simple fabrication process and high compatibility with the CMOS process. The applications of bubble actuators to microfluidics based biotechnology, such as DNA microarrayer, microcell manipulator/sorter and micro-oligonucleotide synthesizer, are in the early stage of research, and more studies on the behavior of bubble actuators using different biofluids will be needed for design and fabrication of these devices.

Cross References

- ► Bubble Growth and Collapse
- ► Micro Heat Pipes
- ► Nucleation Temperature

References

1. Nielsen NJ (1985) History of the inkjet printhead development – preventing hydraulic crosstalk. Hewlett-Packard J 36:4–10
2. Kobayashi H, Koumura N, Ohno S (1981) Canon Kabushiki Kaisha liquid recording medium. US Patent 4,243,994
3. Bhaskar EV, Leban MA (1989) Integrated thermal inkjet printhead and method of manufacture. US Patent 4,847,630
4. Lee JD, Yoon JB, Kim JK, Chung HJ, Lee CS, Lee HD, Lee HJ, Kim CK, Han CH (1999) A thermal inkjet printhead with monolithically fabricated nozzle plate and self-aligned ink feed hole. J Microelectromech Syst 8:229–236
5. Baek SS, Choi BY, Oh YS (2004) Design of a high-density thermal inkjet using heat transfer from CVD diamond. J Micromech Microeng 14:750–760
6. Tseng FG, Kim CJ, Ho CM (2002) A high-resolution high-frequency monolithic top-shooting microinjector free of satellite drops. Part I. Concept, design, and model. J Microelectromech Syst 11:427–436
7. Geng X, Yuan H, Oguz HN, Prosperetti A (2001) Bubble-based micro pump for electrically conducting liquids. J Micromech Microeng 11:270–276
8. Jun TK, Jin C, Kim CJ (1998) Valveless pumping using traversing vapor bubbles in microchannels. J Appl Phys 83:5658–5664
9. Lin L (1998) Microscale thermal bubble formation: thermophysical phenomena and applications. Microscale Thermophys Eng 2:52–59
10. Deng PG, Lee YK, Cheng P (2003) The growth and collapse of a micro-bubble under pulse heating. Int J Heat Mass Transf 46:4041–4050
11. Deng PG, Lee YK, Cheng P (2006) Two-dimensional micro-bubble actuator array to enhance the efficiency of molecular beacon DNA micro-biosensors. Biosens Bioelectron 21:1443–1450
12. Deng PG, Lee YK, Cheng P (2005) Measurements of micro bubble nucleation temperature in DNA solutions. J Micromech Microeng 15:564–574
13. Deng PG, Lee YK, Cheng P (2006) An experimental study of heater size effect on micro bubble generation. Int J Heat Mass Transf 49:2535–2544
14. Deng PG, Lee YK, Cheng P (2004) Micro bubble dynamics in DNA solutions. J Micromech Microeng 14:693–701
15. Petersen K (2005) A new age for MEMS. 13th International Conference on Solid-State Sensors, Acuators and Microsystems (IEEE Transducers), Seoul, Korea, pp 1–4
16. Okamoto T, Suzuki T, Yamamoto N (2000) Microarray fabrication with covalent attachment of DNA using bubble jet technology. Nat Biotech 18:438–441

Thermal Capacitive Flow Sensor

- ► Thermocapacitive Flow Sensor

Thermal Conductivity

- ► Plasma Treatment of Nanoparticles for Nanofluids

Thermal Control in Microfluidic Modules

- ► Temperature Control in Microfluidic Systems

Thermal Creep Coefficient

Definition

Thermal creep coefficient determines a gas flow induced by a temperature gradient.

Cross References

- ► Gas Flow in Nanochannels
- ► Micro- and Nanoscale Gas Dynamics

Thermal Diffusion

- ► Thermophoresis

Thermal Flow Sensors

- ► Micro/Nano Anemometers
- ► Micro- and Nanoscale Anemometry: Implication for Biomedical Applications
- ► Pyroelectric Flow Sensors
- ► Thermoelectric Flow Sensors

Thermal Fusion Bonding

Synonyms

Fusion bonding; Thermal bonding; Hot press bonding

Definition

Thermal fusion bonding is a process which fuses more than one material or substrate via a thermal cycle. The temperature for performing this process is usually a bit higher than the glass transient temperature (T_g) of the material.

Cross References

- ► Bulk Micromachining
- ► Thermal Fusion Bonding

Thermal Gradient Focusing

- ► Temperature Gradient Focusing

Thermal Lens Effect

- ► Thermal Lensing, Detection

Thermal Lensing, Detection

Kazuma Mawatari[1], Takehiko Kitamori[2]
[1] Microchemistry Group, Kanagawa Academy of Science and Technology (KAST), Kanagawa, Japan
[2] Department of Applied Chemistry
School of Engineering, The University of Tokyo,
Tokyo, Japan
kmawatari@world.odn.ne.jp,
kitamori@icl.t.u-tokyo.ac.jp

Synonyms

Photothermal effect; Thermal lens effect

Definition

Thermal lensing (TL) is one example of a photothermal phenomenon. When an excitation laser is focused into a non-fluorescent sample in a microchannel, the sample absorbs the excitation laser and releases the light energy as heat following non-radiative relaxation. The heat generation induces a temperature distribution which is similar to a Gaussian profile due to the Gaussian intensity distribution of the excitation laser and heat diffusion. Generally, a temperature increase in a liquid decreases the refractive index, and a refractive index distribution working as a concave lens is formed around the focus. This concave lens is a thermally-induced lens and the phenomenon is known as *thermal lensing*. A thermal lens microscope (TLM) utilizes TL effects for ultrasensitive detection of non-fluorescent molecules in microchannels. The TLM features high sensitivity comparable to that obtained by a fluorescence method and, because there are so many more non-fluorescent molecules, much wider applicability. TLM has been successfully applied to various analytical and chemical synthesis applications on microchips combined with general micro-integration methods by micro-unit operations (MUOs) and continuous flow chemical processing (CFCP).

Overview

The basic principle of TLM is illustrated in Fig. 1 [1]. In a TLM, two laser beams are utilized: an excitation laser beam and a probe laser beam. The wavelength of the former is tuned to the light absorption band of the sample and that of the latter is adjusted to avoid the absorption band. The excitation laser is tightly focused into the sample. The diameter of the beam waist is usually around 1 µm. The sample absorbs the excitation beam, and heat is released to the solvent around the molecule, increasing temperature of the solution. The light absorption is linearly dependent on the light intensity distribution which is a Gaussian distribution, and the resultant temperature distribution is sim-



Thermal Lensing, Detection, Figure 1 Basic principle of TLM



Thermal Lensing, Detection, Figure 2 Illustration of sensitive TL detection by focal length difference Δz: $\Delta z = 0$ (left) and $\Delta z \cong z_C$ (right)

ilar to the intensity distribution. The strength of the lens at thermal equilibrium is expressed as,

$$\frac{1}{f} = \frac{P\varepsilon Cl\,(\mathrm{d}n/\mathrm{d}T)}{\pi J\kappa\omega_0^2} \tag{1}$$

where f is the focal length of the thermal lens near the optical axis, J is the Joule coefficient, κ is the thermal conductivity of the medium (usually solvent in dilute solutions), ω_0 is the radius of the beam waist, P is the power of the excitation beam, ε is the molar absorption coefficient of the sample, C is the concentration of the sample, l is the optical path length of the cell (usually the depth of the cell if the change of the waist ω is ignored) and $\mathrm{d}n/\mathrm{d}T$ is the first derivative of the refractive index, n, of the medium by temperature, T.

For detection of the TL effect, a probe beam is coaxially introduced into the objective lens and focused on the sample. The radius of the spot is also calculated from Eq. (1). When the excitation beam is focused on the sample and the TL effect is induced, the optical path of the probe beam is changed. The change in the optical path is detected by measuring the probe beam intensity through a pinhole. For dilute solutions, the intensity change ΔI is proportional to $1/f$ in Eq. (1) and is defined as a thermal lens signal. The sign of ΔI depends on the TL effect on the probe beam, which is either converging or diverging, and is determined by the relative focal positions of the probe and excitation beams. When the focus of the probe beam is closer to the



Thermal Lensing, Detection, Figure 3 Signal recovery by intensity modulation of the excitation beam (upper) and synchronous detection of the same frequency component by a lock-in amplifier (bottom)


Solution B
Solution A
Shake
Phase contact
Extraction
Phase separation
Solution A
Solution B
Microchannel
a
Phase
Operations and channel structures
L/L
Phase contact
Phase separation
Extraction
Mixing & reaction
Counter flow contact
G/L
Phase contact
Phase separation
Adsorption
Reaction
Concentration
Bubble separation
Condensation
Distillation
L/S
Adsorp. or reac.
Membrane sep.
Others
Heating
Cell culture
b

Thermal Lensing, Detection, Figure 4 Realization of micro-unit operations (MUOs): (**a**) example of solvent extraction and (**b**) MUOs developed for various phases

objective lens than that of the excitation beam, the probe beam diverges.

As shown in Eq. (1), the sensitivity of the TL signal depends on chemical and physical properties of the solution. For the chemical properties, the enhancement factor $(\mathrm{d}n/\mathrm{d}T)/\kappa$ is very important. Usually, organic solvents are favorable due to higher $\mathrm{d}n/\mathrm{d}T$ and smaller κ [1]. Water shows the lowest enhancement factor. For example, carbon tetrachloride has an approximately 40 times greater enhancement factor than water.

For the physical properties, the enhancement factor $P/\pi\omega_0^2$ is important. Tightly focusing the excitation beam leads to a strong TL effect; however, it also leads to a large divergence of the excitation beam due to light diffraction and the effective length of the TL contributing to the signal decreases. The detection depth should be experimentally determined.

The most important point to realize sensitive TLM is a focal length difference between the excitation beam and probe beam as shown in Fig. 2. When the focal lengths of the two beams are the same, the probe beam is focused at the center of the TL. In this case, the optical path of the probe beam is not changed, and the signal intensity becomes almost zero. An adequate focal length difference Δz is necessary for realizing optimum sensitivity. The optimum Δz is estimated by

$$\Delta z \cong \sqrt{3} z_{\mathrm{c,pr}} \qquad (2)$$


Continuous flow chemical processing (CFCP)
~ example of wet analysis~
Water phase
Sample (Co²⁺)
Contamination (Cu²⁺)
Chelating reagent
Organic phase
Complex
①
②
③
④
Reaction & Extraction
MUOs : ① Mix & Reaction
② 2-phase flow formation
③ Extraction
④ Phase separation
Washing & Detection
MUOs : ⑤ 3-phase flow formation
⑥ Decomposition
⑦ Extraction & removal
⑧ Extraction & removal
⑨ TLM detection
HCl
Contamination (Cu²⁺)
TLM
⑤
⑥
⑦
⑧
⑨
NaOH
Chelating reagent
Integration on a chip

Thermal Lensing, Detection, Figure 5 Concept of continuous flow chemical processing (CFCP) and TLM detection for general micro-integration: an example of wet analysis on a microchip


Excitation laser
Light chopper
Beam expander
Beam expander
Probe laser
Focus adjustment
Objective lens
Microchip
Stage
Objective lens
Pinhole
Photodiode
Filter
Pre-amplifier
Recorder
Reference signal
Lock-in amplifier
Recovered TL signal

Thermal Lensing, Detection, Figure 6 A typical TLM system



Thermal Lensing, Detection, Figure 7 a) Desktop-sized TLM and b) palmtop-sized TLM

where $z_{c,pr}$ is a confocal distance of the probe beam. However, Eq. (2) assumes that $z_{c,pr}$ is much larger than the TL thickness which is investigated based on Eq. (2). The exact value should be determined by measuring the dependence of the TL intensity onΔz.

Next, the signal processing to recover TL signals from large thermal noises is illustrated because the TL effect is very weak; typically the largest value of ΔT is 10^{-3} degrees and Δn is less than 10^{-7}. The former value is as small as the thermal fluctuation and easily affected by environmental temperature change. In order to recover the true TL signal, the intensity of the excitation beam is modulated at a certain frequency and the synchronous signal of frequency in the probe beam intensity change is detected by a lock-in amplifier. The lock-in amplifier works as an ultra-narrow band pass filter. A typical waveform is illustrated in Fig. 3. Finally, the concept of a general micro-integration method and coupling with the TLM are illustrated. In the 1990's, most microchip-based analytical systems were concerned with genome or protein analysis by electrophoresis with fluorescence detection. However, many other analytical and synthesis applications were expected in general chemistry, organic synthesis, combinatorial chemistry, physical chemistry, and biochemistry that involve complicated chemical processes, organic solvents, neutral species, and non-fluorescent detection. For this purpose, we first realized conventional unit operations on microchips as micro-unit operations (MUOs) utilizing multiphase laminar flow as shown in Fig. 4. These MUOs were connected by continuous flow chemical processing (CFCP) to form a multiphase laminar flow network (Fig. 5), and TLM was utilized for detection of non-fluorescent molecules. These concepts have opened various analytical and chemical synthesis applications on microchips with wide applicable and sensitive TLM detection.



Thermal Lensing, Detection, Figure 8 Performance of TLM for ultrasensitive detection of molecules. The sample was lead(II)-porphyrine complex solution

Basic Methodology

A typical TLM system is illustrated in Fig. 6. The output of the excitation beam is intensity-modulated by a light



Thermal Lensing, Detection, Figure 9 Single cell imaging by scanning TLM. Cytochrome C was directly measured by scanning the laser beams with a 1 µm increment

chopper. The excitation beam is expanded by a beam-expander to adjust the beam size to the size of the input pupil of an objective lens. Then, the excitation beam is introduced into a microscope through a dichroic mirror and a prism. The probe beam is also expanded by a beam-expander. The distance between the two lenses in the beam expander is adjusted to control the divergence of the probe bam and focal length difference Δz. Then, the probe beam is reflected by the dichroic mirror and introduced into the microscope coaxially with the excitation beam. The objective lens of the microscope focuses the excitation and probe beams into a sample on a microchip. The TL effect is induced in the sample, and the probe beam is converged or diverged due to the TL effect depending on the focal position as described in the previous section. The two transmitted beams are collimated by another objective lens and reflected by a mirror and focused by a third lens. The excitation beam is removed by a filter, and only the probe beam is focused onto the pinhole and collected by a photodiode. The photodiode converts the light intensity of the probe beam to an electronic signal which is amplified by a pre-amplifier. Then, the amplified signal is fed into a lock-in amplifier. The lock-in amplifier extracts synchronous signals in the large background, and the amplitude and phase are measured as TL signals. Available wavelengths range from deep-UV to IR regions.

Desktop- and palmtop-sized TLMs are commercially available (Fig. 7) [2]. In the palm-top TLM, laser-diodes are utilized as excitation and probe beams, and these beams are introduced to a microchannel via a light mixer and a single-mode optical fiber. The palm-top TLM can also be integrated into a system. For example, an allergy analysis system with the palmtop-sized TLM has been reported.

Key Research Findings

Realization of TL detection under a microscope allows ultrasensitive detection of non-fluorescence molecules. An example of dye solution detection in a microchannel is illustrated in Fig. 8 [3]. The microchannel was 150 µm wide and 100 µm deep. The solvent used was benzene and the molar absorption coefficient of the porphyrine complex was $3.2 \times 10^4\ \mathrm{M}^{-1}\mathrm{cm}^{-1}$. The expected value was cal-

Thermal Lensing, Detection, Table 1 Example applications utilizing TLM and microchips [6]

	Analyte	Method
Environmental analysis	Co^{2+}, Cr^{6+}, Fe^{2+}, K^{+}, Na^{+}, Ni^{2+}, PO_4^{2-}, Pesticides, etc.	Solvent extraction
	NH_4, HCHO	Gas/liquid absorption and colorimetric reaction
Clinical diagnosis	s-IgA, INF-.γ, BNP, IgE, CRP, CEA, 17-estradiol, AFP, Amphetamines, Sedatives, Antibiotics, etc.	Immunoassay
	Glucose, HDL, LDL, Albumin, GOT, GPT, ALP, GA , etc.	Enzyme reaction
Bioanalysis	Fe^{2+}, Ascorbic acid, H_2O_2,	Flow injection analysis
	Cytochrome C, TNBS (on a cell)	Direct detection
	NO (released from a cell)	Enzyme reaction
	ApoA1 (released from a cell)	Immunoassay
	DNA, Amino acids	Direct detection
	Arachidonic acid	Direct detection
Food analysis	Prion peptides	Immunoassay
Other	Individual nanoparticles (gold, silver)	Direct detection
	UO_2^{2+}	Solvent extraction
	Dye molecules	Direct detection

culated by multiplying the concentration and the detection volume (7 fL). The signal intensity showed good linear dependence on the expected value. The lower limit of detection was estimated to be 0.32 molecules from the conditions of a signal-to-noise ratio (S/N) of 2 and a signal-to-background ratio (S/B) of 0.1 for an averaging time of several seconds. In comparison with spectrophotometry, more than six orders higher sensitivity in the absolute molecular number is achieved. This ultrahigh sensitivity with wide applications for non-fluorescent molecules holds the promise of a powerful tool for various microchip-based analytical or chemical synthesis applications.

TLM can also be utilized for imaging by scanning the laser beams. Figure 9 shows the direct imaging of a single neuron cell by measuring Cytochrome C for monitoring an apoptosis process [4]. In situ imaging of a single cell with almost 1 µm spatial resolution was successfully realized [5]. Many other applications such as in situ immunoassay on biological cells or membranes have also been reported [5].

A summary of example TLM applications coupled with MUOs developed and CFCP is made in

Future Directions for Research

In a previous section, just one example of ultrasensitive concentration determination of non-fluorescent molecules was given. However, the area of micro- and nano-fluidics is rapidly expanding and high degrees of functionality are desired for detection methods.

For these purposes, various functional TLMs have already been realized. For example, sensitive chiral recognition by circular-dichroism TLM (CD-TLM) was reported for synthesis and analysis of drugs on microchips [6]. Other reports have described an electrochemical TLM [7], flow sensing TLM, UV TLM [8], and TLM spectrometer [9].

As important functions for science and technology in micro- and nano-fluidics, three functions are highly desired: individual molecule detection as the ultimate sensitivity, fast (real-time) imaging, and femtosecond time-resolved measurement for investigating molecular dynamics in a nano-space.

The design method of these functional TLMs is also important. The TL effect is usually very complex in the micro- and nano-space and its basic science is still an important issue. Development of a theoretical analysis tool which combines fluidics and optics is desired for this purpose.

Cross References

- ► Lab-on-Chip Devices for Immunoassay
- ► Lab-on-Chip (General Philosophy)
- ► Devices for Sample Extraction

References

1. Bialkowski SE (1996) Photothermal Spectroscopy Methods for Chemical Analysis. Wiley, New York
2. Web site of Institute Microchemical Technology Co., Ltd. http://www.i-mt.co.jp/
3. Tokeshi M, Uchida M, Hibara A, Sawada T, Kitamori T (2001) Determination of subyoctomole amounts of nonfluorescent

molecules using a thermal lens microscope: Subsingle molecule determination. Anal Chem 73:2112

4. Tamaki E, Sato K, Tokeshi M, Sato K, Aihara M, Kitamori T (2002) Single-cell analysis by a scanning thermal lens microscope with a microchip: Direct monitoring of cytochrome c distribution during apoptosis process. Anal Chem 74:1560
5. Kitamori T, Tokeshi M, Sato K, Hibara A (2004) Thermal lens microscopy and microchip chemistry. Anal Chem 76:52A
6. Yamauchi M, Mawatari K, Hibara A, Tokeshi M, Kitamori T (2006) Circular-dichroism thermal lens microscope for sensitive chiral analysis on microchip. Anal Chem 78:2646
7. Kim H-B, Hagino T, Sasaki N, Watanabe N, Kitamori T (2005) Spectrochemical detection using thermal lens microscopy with a glass-substrate microelectrode-microchannel chip. J Electroanal Chem 577:47
8. Hiki S, Mawatari K, Hibara A, Tokeshi M, Kitamori T (2006) UV-excitation thermal lens microscope for non-labeled and ultrasensitive detection of non-fluorescent molecules. Anal Chem 78:2859
9. Tamaki E, Hibara A, Tokeshi M, Kitamori T (2005) Tunable thermal lens spectrometry utilizing microchannel-assisted thermal lens spectrometry. Lab Chip 5:129

Thermally Actuated Mechanical Valves

► Thermomechanical Valves

Thermally Driven Mechanical Valves

► Thermomechanical Valves

Thermally-Sensitive Hydrogels

► Temperature-Sensitive Hydrogels

Thermal Marangoni Effect

► Thermocapillarity

Thermal Mechanical Valves

► Thermomechanical Valves

Thermal Oxidation

► Oxidation (of Silicon)

Thermal Pumping

► Thermocapillary Pumping

Thermal Slip Coefficient

Definition

Thermal slip coefficient determines the tangential velocity of gas near a solid surface due to a longitudinal gradient of surface temperature.

Cross References

► Gas Flow in Nanochannels
► Micro- and Nanoscale Gas Dynamics

Thermistors

► Contact Temperature Sensors

Thermocapacitive Flow Sensor

HONG JIANG[1], GUIREN WANG[2]
[1] GraceFlow Technology, Columbia, SC, USA
[2] Department of Mechanical Engineering, University of South Carolina, Columbia, SC, USA
ajiangca2@yahoo.com, wanggu@engr.sc.edu

Synonyms

Thermal capacitive flow sensor

Definition

The thermocapacitive flow sensor is a velocimeter used to measure the rate of fluid flow. In a thermocapacitive flow sensor, there is a heater and sensing capacitor, which has a dielectric material with a temperature-dependent dielectric constant. The heater is located close to the capacitor. If electric power is supplied to the heater, it causes the temperature of the capacitor to rise. The dielectric constant of the capacitor increases with temperature, resulting in an increase in the capacitance. When the fluid flows through the capacitor, the temperature of the capacitor will decrease due to the convective heat transfer from the capacitor to the fluid. Thus the capacitance will also be reduced. Through measuring the capacitive value, the flow velocity can be obtained by a calibration relationship between the flow rate and the capacitance.

Overview

Fluid flow is important not only in almost all engineering fields, but also in micro- and nanofluidic chips. Flow measurements are required to: increase our understanding of the physicochemical mechanisms of processes; improve the designs of the devices; and enhance the corresponding function of the devices. The measurement of the flow velocity is important in fluid mechanics. There are many conventional advanced velocimetries in fluid mechanics: hot-wire anemometry (HWA), laser Doppler velocimetry (LDV) and particle image velocimetry (PIV) [1]. These methods have been applied in microfluidics to measure the flow velocity in microchannels [2–4]. For microfluidics, there are several other methods to measure flow velocity, these have been reviewed elsewhere [5].

Thermal flow sensors based on convective heat transfer are usually used to measure the flow rate, since a heater can easily be realized by applying electric power to a electric resistor. For instance, HWA, one of the most widely used velocimetries, is a thermal flow sensor.

All thermal flow sensors are based on the convective heat transfer between a flowing fluid and a sensing solid element. Figure 1 shows a simplified case of convective heat transfer which explains the thermal flow sensing principle. A heater heats a solid sensor, which faces the flowing fluid. When power is supplied to the heater, the sensor temperature increases to T_s. As the fluid flows through the solid sensor, there will be a convective heat transfer from the sensor to the fluid. If Q is the heat transfer rate, A_h is the interface area perpendicular to the direction of heat flow between the sensor and the fluid. T_s and T_f are the temperature of the sensor surface and fluid, respectively. The heat transfer can then be described as

$$Q = \mathrm{Nu}\, A_\mathrm{h}\, (T_\mathrm{s} - T_\mathrm{f}) \tag{1}$$

where Nu $(= \alpha_\mathrm{c} L / k_\mathrm{d})$ denotes the Nusselt number, α_c is the convective heat transfer coefficient, L represents the characteristic length for the heat transfer, and k_d is the thermal conductivity of the fluid. Nu normally depends on the flow and material properties and can be described as

$$\mathrm{Nu} = f\nu\, (\mathrm{Re}, \mathrm{Pr}) \ , \tag{2}$$



Thermocapacitive Flow Sensor, Figure 1 Simplified case of convective heat transfer

from Eq. (1) and Eq. (2):

$$T_\mathrm{s} = \frac{Q}{f\nu\, (\mathrm{Re}, \mathrm{Pr})\, A_h} + T_f = \frac{Q}{f\nu\, (uL/\mu, \mathrm{Pr})\, A_h} + T_f \tag{3}$$

where Re $(= uL/\nu)$ is the Reynolds number and Pr $(= c_\mathrm{p}\mu / k_\mathrm{c})$ denotes the Prandtl number. u, ν, μ, c_p, and k_c are the flow velocity, kinematic viscosity, dynamic viscosity, specific heat, and thermal conductivity of the fluid, respectively [6]. The relationship between Nu and u depends generally on flow (e. g., laminar, turbulent), the geometry of the sensor, the position and the orientation of the sensor to the flow. Nu(Re, Pr) does not have a universal formula. When constant power is applied to the heater, it will cause the temperature T_s to rise. However, when the fluid passes through the sensor, the convective flow will reduce T_s. The higher the flow velocity, the lower the value of T_s. If the fluid temperature, composition, and pressure are constant, the only variable that affects the convective heat transfer or T_s is the flow velocity u. The heater can be an electric resistant. Thus, the flow velocity can be determined by measuring the temperature T_s directly or other variables that are, in turn, related to T_s.

A thermal flow sensor typically consists of a heater and one or more temperature sensors. The heater can operate at either constant heating power or at a constant heating temperature. In thermal microflow sensors, the flow rate is evaluated by measuring the heating power, the temperature of the heater or fluid, and the time of flight of a heat pulse [7].

There are three types of thermal flow sensors that combine the evaluation methods and heater modes: hot-wire (hot-film), calorimetric, and time-of-flight.

- Hot-wire (hot-film) sensors measure the effect of the flowing fluid on a hot body. At a constant heat power, the forced convection causes a decrease in the temperature of the heater.
- Calorimetric sensors measure the asymmetry of a temperature profile round the heater, which is modulated by the fluid flow.
- Time-of-flight type sensors measure the time that it takes for a heat pulse to move a known distance.

In principle, any temperature-dependent property of a solid-state material could be used for temperature measurement. Each of the sensor types can be further categorized, according to their thermal sensing principle as: thermoresistive, thermoelectronic, pyroelectic, thermophilic elements, microresonator structures, or thermocapacitive [7].

In this essay, we focus on the thermocapacitive flow sensor. The advantages of the thermocapacitive flow sensor are: its low cost arising from batch fabrication; on-chip electronic signal-conditioning circuitry for enhanced performance; low power consumption; low noise due to the metal oxide semiconductor (MOS); and reduced dimensions. Its disadvantages include the fact that it has difficulty measuring velocity distribution in flow fields due to the relatively poor spatial resolution. There are also difficulties with using the thermocapacitive flow sensor in liquids, due to electrical insulation, and in electrokinetic flows, as it could interfere with the flow.

Basic Methodology

The thermocapacitive flow sensor is based on a dielectric material with a temperature-dependent dielectric constant. The sensing module is a capacitor. If the electric power is supplied to a heater that is close to the capacitor, the temperature of the capacitor will increase, causing an increase in the dielectric constant, and thus, an increase in the capacitance of the capacitor. When a fluid flows through the capacitor and if its temperature is lower than that of the capacitor, the temperature of the capacitor will decreases due to the convective heat transfer between the fluid and the capacitor. The temperature of the dielectric material of the capacitor will decrease, resulting in a decrease in the capacity. The higher the flow velocity, the lower the capacity. Therefore there is a relationship between the flow velocity and the capacitance. Like the HWA, with a calibration relationship between the flow velocity and the capacitance, the flow velocity can be calculated by measuring the capacity of the capacitor.

The measurement of flow rate is one of main subjects in experimental fluid mechanics. However, the thermocapacitive flow sensor may have electronic and semiconductor components, such as a capacitor, an n-channel MOS transistor, an oscillation circuit, and microfabrication. Therefore, the thermocapacitive flow sensor is a multidisciplinary tool and some of its electronic and semiconductor components need to be explained.

Components

Capacitor

A parallel-plate capacitor consists of two closely spaced conductive plates. A nonconductive material is termed a dielectric. When the space between the two plates is occupied by a dielectric material, the capacitance is increased by a factor κ that is characteristic of the dielectric and is known as the dielectric constant or dielectric coefficient [8].

$$C = \kappa C_0 = \kappa \left(\frac{A}{d} \right) \qquad (4)$$

where C_0 is the original capacitance, A represents the area of the plates, and d is the distance between the surfaces of the two plates. The capacitance C depends on the dielectric constant and the geometrical configuration, but is independent of the voltage on it. Since the dielectric constant κ is dependent on the temperature and frequency, the capacitance C is also a function of the temperature.

N-Channel MOS

Figure 2 illustrates the MOS structure that consists of a semiconductor substrate layer, a middle oxide layer and a top metal layer which acts as the control gate. Most transistors are MOS field-effect transistors (MOSFETs) and the metal gate has mostly been replaced by a polysilicon gate. Although the term insulated gate field effect transistor (IGFET) is sometimes preferred, we will continue to use the term MOS, because it is used in the relevant publication [9]. There are three terminals: D (drain), S (source), and G (gate) in a MOSFET.

The MOS is a voltage sensitive device and operates as the positive gate voltage. This positive potential on the gate causes a polarization of the charges within the oxide insulator as illustrated in Fig. 2. The positive charges (holes) are aligned along the inner surface of the oxide. Consequently, these positive charges attract the negative charges (electrons) from the p-substrate to the area of the oxide. When more electrons are attracted into the n-channel region under the gate oxide than there are holes in the n-channel, that is when the gate voltage is higher than the threshold voltage, the n-channel is created to bridge the two n^+ regions. n^+ regions are so-called in order to emphasize the very large n impurity. If a positive drain voltage is now applied between the D and S terminals, n-channel electrons provide a conducting path between the two n^+ sections and current flows between the source and drain.

A floating gate MOS has one more layer than a MOS. This layer is called the floating gate. It is situated between the control gate and the semiconductor substrate and is surrounded by the oxide insulator (see Fig. 3).

The Sensing Capacitor Module

The sensing module is a capacitor, which has a dielectric layer, whose dielectric constant increases with temperature. In practice the capacitor module can be fabricated


n-channel
Drain D
Oxide
Metal
Gate G
n+
p
Semiconductor Substrate
V_{DS}
Source S
n+
V_{GS}
a
G
D
S
V_{GS}
V_{DS}
b

Thermocapacitive Flow Sensor, Figure 2 n-channel MOS structure and wiring. (**a**) n-channel MOS structure; (**b**) diagram showing how the MOS is wired to obtain the current between source and drain

using a MOS-compatible process combined with ethylenediamine pyrocathechol (EDP) groove etching [9, 10] as shown in Fig. 4. The capacitor module consists of multilayers, such as molybdenum for the control gate, a dielectric material Ta_2O_5 [9] or $SrTiO_3$ [10], a polysilicon floating gate, and an oxide insulator. A heating resistor, that can be an electrical resistance, is also included in this module.

Measuring Variables

The sensor operation is based on convective cooling by fluid flow of the sensing capacitor, which is initially heated by a polysilicon microheater which is in close proximity to it. Two variables have been used to measure the flow rate: voltage [9] and oscillation frequency [10].


Control Gate
G
Floating Gate
Oxide$_1$
Oxide$_2$
S
D
n+
n+
p Substrate

Thermocapacitive Flow Sensor, Figure 3 Structure of a floating gate MOS


Molybdenum Control gate
Ta_2O_5 or $SrTiO_3$ Dielectric Material
Polysilicon Heating Resistor
Polysilicon Floating Gate
Oxide Insulator
Silicon p+ Substrate

Thermocapacitive Flow Sensor, Figure 4 Sensing capacitor module

MOS Amplified Voltage Output

A schematic of the sensor circuit is shown in Fig. 5 [9]. The sensing capacitor module with a dielectric material (such as Ta_2O_5 or $SrTiO_3$) and a n-channel MOS transistor M_1 together constitute a floating-gate MOS transistor. C is the coupling capacitor between the control gate and the floating gate. For purposes of thermal isolation, the capacitor C and the heating resistor can be located on a cantilever structure, which can be fabricated by bulk micromachining in EDP. The rest of the floating gate MOS was located on the substrate area to avoid heat transfer from the heating element.

The sensor works in the current saturation region where the drain current I_d is nearly independent of the drain–source voltage V_{DS}. The saturation drain current of the floating gate MOS transistor is governed by the following equation in simplified form [9]:

$$I_\mathrm{d} = \frac{K}{2}\left(\frac{C}{C_\mathrm{T}}V_i + W_\mathrm{B}V_\mathrm{B} - W_\mathrm{s}V_\mathrm{s} - W_\mathrm{T}V_\mathrm{th}\right)^2 \tag{5a}$$

Using Eq. (4),

$$I_\mathrm{d} = \frac{K}{2}\left(\frac{\kappa C_0}{C_\mathrm{T}}V_i + W_\mathrm{B}V_\mathrm{B} - W_\mathrm{s}V_\mathrm{s} - W_\mathrm{T}V_\mathrm{th}\right)^2 \tag{5b}$$

where I_d is the drain current, W_B, W_s, and W_T are the coupling ratios which relate to the input voltage V_i, substrate potential V_B, source potential V_s and threshold voltage V_th, respectively. C_T is the total capacitance associated with the floating-gate including C. K is the transistor transconductance which relates an output quantity (drain current) to an input quantity (gate–source voltage).

By differentiating I_d with respect to κ, where the coupling ratios are a function of C directly, we obtain the expression

$$\frac{\mathrm{d}I_\mathrm{d}}{\mathrm{d}\kappa} = \frac{2I_\mathrm{d}C_0}{C_\mathrm{T}}\left(\sqrt{\frac{I_\mathrm{d}^*}{I_\mathrm{d}}} - 1\right), \tag{6}$$

$$V_0 = V_\mathrm{cc} - R_\mathrm{d}I_\mathrm{d} \tag{7}$$

where I_d^* is the drain current in the MOS transistor if the control gate voltage V_i is applied directly in the floating gate and V_0 is the output voltage. Since there is a voltage drop on the capacitor, the control gate voltage is higher than the floating gate voltage. Therefore I_d^* is larger than I_d and $\mathrm{d}I_\mathrm{d}/\mathrm{d}\kappa$ is positive. As a result, I_d increases with the dielectric constant κ.



Thermocapacitive Flow Sensor, Figure 5 Circuit schematic of flow sensor measuring capacitor voltage



Thermocapacitive Flow Sensor, Figure 6 Circuit of oscillator 555 timer IC chip coupled with sensing capacitor

When power is applied to the heater, the rise in temperature causes the dielectric constant κ in the capacitor to increase, then the drain current increases. When fluid flows through the capacitor convective cooling reduces the temperature, causing κ to decrease, so that the drain current decreases. Therefore the change in the drain current or the output voltage is a measurement of the velocity of the fluid flow.

Frequency Modulated Output

When the sensing capacitor is externally connected to a 555 timer IC chip to form an oscillation circuit as shown in Fig. 6, the oscillation frequency can be used to measure the flow velocity [10]. Here, both inputs of trigger and threshold in 555 timer are connected together. The response of the output voltage V_0 to the input voltage V_c on the capacitor is illustrated in Fig. 7.

The lower threshold (V_TL) and the upper threshold (V_TH) of the 555 timer are internally set at $V_\mathrm{cc}/3$ and $2V_\mathrm{cc}/3$, respectively. When power is first applied to the circuit, there is no charge in the sensing capacitor and the output V_0 is set high to V_cc, since the capacitor voltage V_c is below the lower threshold. The sensing capacitor then starts charging through resistors R_1 and R_2 until V_TH is reached, which causes the timer to reset and the output V_0 to reduce to a low level. This turns on the internal discharge transistor, which discharges the sensing capacitor through R_2. When V_c reaches V_TL, the 555 timer output goes high again and the discharge transistor is turned off. The operation is now cyclic, with the sensing capacitor voltage V_c oscillating between $V_\mathrm{cc}/3$ and $2V_\mathrm{cc}/3$.



Thermocapacitive Flow Sensor, Figure 7 Response of output voltage V_0 to sensing capacitor voltage V_C. (**a**) Sensing capacitor voltage V_C as input; (**b**) output voltage V_0 from 555 timer

The time interval for charging the capacitor is [10]

$$t_1 = 0.693\,(R_1 + R_2)\,C\,. \tag{8}$$

The time interval for discharging the capacitor is

$$t_2 = 0.693 R_2 C\,. \tag{9}$$

The total period of the oscillation is

$$\begin{aligned} T = t_1 + t_2 &= 0.693\,(R_1 + 2R_2)\,C \\ &= 0.693\kappa\,(R_1 + 2R_2)\,C_0 \end{aligned} \tag{10}$$

and the oscillation frequency is

$$f = \frac{1}{0.693\kappa\,(R_1 + 2R_2)\,C_0}\,. \tag{11}$$

Clearly, the period of oscillation T is proportional to the dielectric constant κ. Because of the positive temperature coefficient of the dielectric constant, there is a proportional increase in the oscillation period, due to the increase in the temperature of the capacitor, when power is applied to the heater. With fluid flowing, the convective cooling of the sensing capacitor surface would reduce its dielectric constant κ again and cause the period to decrease. Hence, the change in the oscillation period or frequency is a measurement of the fluid flow velocity.

Fabrication

The function of the thermocapacitive flow sensor strongly depends on the sensing material and the quality of its fabrication. Two dielectric materials have so far been used for the sensing capacitor: Ta_2O_5 and $SrTiO_3$. The more sensitive the dielectric constant to the temperature, the higher the sensitivity of the sensor for measuring the flow rate. The dielectric constant temperature coefficients of Ta_2O_5 and $SrTiO_3$ are 375 ppm/°C and 2000 ppm/°C, respectively [9, 10]. Therefore the latter is more temperature-sensitive than the former.

The microcapacitor module can be fabricated using microfabrication technology. The MOS process and a slightly modified MOS process followed by the groove-etching technique in EDP have been applied for the microcapacitor module [9, 10]. In order to increase the sensitivity of the sensor, the leakage current, which is the current flowing through the capacitor when a DC voltage is applied to the capacitor, should be kept as low as possible. The leakage current depends on the fabrication process. For instance, when oxygen is used as the sputtering gas for the deposition of the dielectric layer during the fabrication, the leakage current is more than four orders smaller than that when argon is used [10]. The leakage current can be at least six orders smaller than the sensing capacitor charging and discharging current.

If the capacitor module (the capacitor and heater) is thermally isolated from the rest of the active device, the sensitivity can be increased. If the module is built on a cantilever, the thermal isolation can be enhanced. The thermal isolation of the heater element from the rest of the active device can be tested by measuring the MOS transistor current–voltage characteristics and the threshold voltage, with and without power to the heater element. The smaller the difference, the better the thermal isolation.

Key Research Findings

Since the capacitance of the capacitor depends on the dielectric constant, which in turn is related to temperature, Fig. 8 shows the relationship between the normalized capacitance and the temperature for the sensing capacitor, where the capacitance increases with the temperature due to the heating from the heater.

Although capacitance can be used as a measurable variable for flow velocity measurement, in practice, voltage is easier to measure. With the MOS, the voltage signal can be amplified to increase the sensitivity. The relation between the voltage and the flow velocity is shown in Fig. 9. The voltage increases with the flow velocity, since the higher the velocity, the lower the dielectric constant of the capacitor. Since the current I_d decreases with the reduction of the dielectric constant in Eq. (3), the output voltage, based on Eq. (4), will increase.

For the frequency modulated output, the relationship between the oscillating frequency from the timer and flow



Thermocapacitive Flow Sensor, Figure 8 Normalized capacitance of O_2-sputtered $SrTiO_3$ capacitor as a function of temperature. Reproduced from Sens Actuators A with permission of Elsevier



Thermocapacitive Flow Sensor, Figure 9 Relationship between output voltage and gas flow velocity for heater power at 45 mW and 57 mW, respectively. Reproduced from IEEE Electron Device Letters with permission of IEEE



Thermocapacitive Flow Sensor, Figure 10 Relationship between oscillation frequency and gas flow velocity for heater power 150 mW and 250 mW, respectively for both theoretical modeling and experimental measurement. Reproduced from Sens Actuators A with permission from Elsevier

velocity is shown in Fig. 10. The frequency increases with the flow velocity, due to the decrease in the capacitance with the reduction in temperature. At low velocity, the frequency increases linearly with the flow velocity and saturates at a relatively high flow velocity, as shown in Fig. 10. This trend is consistent with theoretical modeling [11], whose result is also shown in Fig. 10.

Figures 9 and 10 show that the sensitivity of the thermocapacitive flow sensor decreases as the flow velocity increases, similar to the case in the HWA and Laser-Induced Fluorescence Photobleaching Anemometer [12]. However, the sensitivity of the thermocapacitive flow sensor increases with heating power, as the higher power will cause a higher temperature difference between the capacitor and fluid, and the change in the flow velocity will cause a larger variation in the temperature, which will cause a larger signal. The sensitivity can be increased by using a large dielectric constant temperature coefficient and a small capacitor.

The response time, which is inversely proportional to the oscillation frequency, determines how fast a sensor can measure the flow velocity, or the frequency band. The higher the heating power, the larger the response time. This is because the higher heating power will generate a larger capacitance, which in turn, will increase the response time. Such a relationship is shown in Fig. 11, where the frequency decreases as the heater power increases.

In practice, a calibration between flow velocity and measuring variables is required before measuring an unknown flow velocity. When calibrating, the fluid temperature, composition, and density should be the same as those to be measured and the fluids are expected to be incompressible.



Thermocapacitive Flow Sensor, Figure 11 Oscillation frequency as a function of heater power without gas flow. Reproduced from Sens Actuators A with permission from Elsevier

Future Directions for Research

To date, the thermocapacitive flow sensor has only been demonstrated in the semiconductor field for measuring the gas flow rate. Many microfluidic chips and most BioMEMS chips work with a liquid medium. Possible future work includes applications of the thermocapasitive flow sensor in a liquid medium, where electrical insulation would be required.

Cross References

- ► Velocity Sensors
- ► Thermocapacitive Flow Sensor
- ► Thermoelectric Flow Sensors
- ► Thermoresistive Flow Sensors
- ► Pyroelectric Flow Sensors

References

1. Jensen KD (2004) Flow measurements. J Braz Soc Mech Sci Eng 26:400–419
2. Liu C, Huang JB, Zhu Z, Jiang F, Tung S, Tai YC, Ho CM (1999) A micromachined flow shear-stress sensor based on thermal transfer principles. J Microelectromech Syst 8:90–99
3. Tieu AK, Mackenzie MR, Li EB (1995) Measurements in microscopic flow with a solid-state LDA. Exp Fluids 19:293–294
4. Santiago JG, Wereley ST, Meinhart CD, Beebe DJ, Adrian RJ (1998) A particle image velocimetry system for microfluidics. Exp Fluids 25:316–319
5. Devasenathipathy S, Santiago JG (2003) Electrokinetic flow diagnostics. In: Breuer KS (ed) Micro- and Nano-scale Diagnostic Techniques. Springer, New York, pp 121–165
6. Kreith F (1965) Principles of Heat Transfer, 2nd edn. International Text Book Company, Scranton
7. Kallio P, Kuncova J (2004) Microfluidics. Tekes Technology Review 158
8. Del Toro V (1986) Electrical Engineering Fundamentals, 2nd edn. Prentice Hall, Englewood Cliffs
9. Lin KM, Kwok CY, Huang RS (1996) An integrated thermocapacitive type MOS flow sensor. IEEE Electron Device Lett 17:247–249
10. Kwok CY, Lin KM, Huang RS (1996) A silicon thermocapacitive flow sensor with frequency modulated output. Sens Actuators A 57:35–39
11. Wachutka G, Lenggenhager R, Moser D, Baltes H (1991) Analytical 2D-model of CMOS micromachined gas flow sensors. In: Proceedings of 1991 International Conference on Solid-state Sensors and Actuators, San Francisco, pp 22–25
12. Wang GR (2005) Laser-induced fluorescence photobleaching anemometer for microfluidic devices. Lab Chip 5:450–456

Thermocapillarity

CHARLES N. BAROUD
LadHyX and Departement de Mécanique, Ecole
Polytechnique, Palaiseau, France
baroud@ladhyx.polytechnique.fr

Synonyms

Thermocapillary effect; Marangoni effect; Thermal Marangoni effect

Definition

The dependence of surface tension on temperature can lead to the existence of a surface stress imbalance when a liquid interface is subject to variations in temperature. These stresses then lead to fluid motion along the interface. In the low Reynolds number situations typical of microfluidics, this motion along the interface rapidly leads to motion in the bulk of the fluid.

Thermocapillarity, Table 1 Surface tension of water from freezing to boiling

Temperature (°C)	Surface tension (mN m^{-1})
0	75.6
10	75.2
20	72.9
30	71.2
40	69.6
50	68.0
60	66.2
70	64.5
80	62.7
90	60.8
100	58.9

Chemical and Physical Principles

The surface tension between a liquid and another immiscible fluid (liquid or gas) accounts for the free energy associated with the creation of a free surface. It has units of energy per unit area, usually taken as $\mathrm{mJ/cm^2}$. The units can also be expressed as a force per unit length, in $\mathrm{mN/m}$, which accounts for the notion that surface tension is indeed a tension that pulls in the direction tangential to the surface.

Statistical mechanics considerations predict that the surface tension (γ) displays a linear dependence on temperature (T),

$$\frac{\mathrm{d}\gamma}{\mathrm{d}T} = \gamma T < 0\,, \tag{1}$$

where T is a constant, usually negative. Table 1, adapted from [1], provides the values of the surface tension γ for a water–air interface as a function of temperature. This table shows that the surface tension has a linear evolution with temperature, starting at a finite value and ending at a lower but also finite value. Note that the drop of surface tension to zero at the critical point of boiling corresponds to a discontinuity in the value of γ.

Table 2 is adapted from [2] and provides the values of γ and γT for some commonly used liquids in microfluidics.

Thermocapillary Convection: The Bénard–Marangoni Problem

Consider now a liquid layer with a free surface. If this layer is submitted to local variations of temperature, it follows that the surface tension will also vary which will lead in turn to an imbalance in the surface tension. This uneven pulling on the interface can be expressed as a production of surface stresses and may be written as

$$\sigma = \gamma T \nabla_{\|} T\,, \tag{2}$$

where σ is the local surface stress and $\nabla_{\|}$ denotes the gradient along the interface. This surface stress must be compensated by a flow from the region with low surface tension to the region with high surface tension. Since motion along the interface must be accompanied by motion in the bulk in order to conserve the fluid volume, the thermocapillary phenomenon leads to convective motion in the bulk of the heated fluid.

The early experiments by Bénard (1900), which have been reproduced many times since [3], beautifully demonstrate the presence of thermocapillary flow. The setup consists of a cell which is partially filled with a thin layer of liquid and submitted to a temperature gradient perpendicular to the liquid–air interface, as shown in Fig. 1. If we imagine that the layer of liquid has a small initial undulation, it is reasonable to think that the region close to the upper plate (region (a)) is cooler than the region which is close to the lower plate (region (b)). This leads to a decrease in the surface tension of region (b) compared to region (a), which in turn leads to a flow along the surface from (b) to (a). By conservation of mass, this surface flow must lead to recirculation rolls in the bulk, as seen by the arrows in Fig. 1.

Two scaling laws about thermocapillarity are worth noting. First, it should be noted that the numerical values of γT are relatively small and lead to modest changes in surface tension for large variations in temperature. For this reason, thermocapillary effects are often masked in large-scale systems by bulk phenomena, with the notable exception of microgravity situations. One can show for instance that thermocapillary (Bénard–Marangoni) convection is the dominant convection mechanism only for liquid layers shallower than a few millimeters. For thicker layers of liquid, buoyancy effects grow rapidly and dominate the convective motion.

This corresponds to the often-cited notion of surface phenomena becoming dominant over bulk phenomena at small scales. It may be stated more generally by dimensional arguments: the surface area decreases as the square

Thermocapillarity, Table 2 Values of surface tension, at a temperature $T = 20\,°\mathrm{C}$, and its dependence on temperature for some commonly used liquids in microfluidics

Liquid	Surface tension γ ($\mathrm{mN\,m^{-1}}$)	γT ($\mathrm{mN\,m^{-1}K^{-1}}$)
Water	72.88	– 0.138
Ethanol	22.75	– 0.086
n-Octane	21.80	– 0.10
Benzene	28.88	– 0.13
Perfluoromethyl cyclohexane (C_7F_{14})	15.70	– 0.10



Thermocapillarity, Figure 1 Bénard–Marangoni experiment, demonstrating flow generated on the surface and in the bulk of a thin layer of liquid of the typical length scale L, while the volume decreases as L^3. As the scale L of the problem decreases, this implies that the bulk phenomena will decrease faster than the surface phenomena and be dominated by them.

The second scaling law concerns the magnitude of the surface stresses. Note that the stresses caused by the variations in temperature (Eq. (2)) do not depend on the value of the temperature but rather on its spatial gradient. This means that the stresses σ may be strong even for modest changes in temperature, if the scale over which they vary is small enough. Microfluidic scales therefore favor surface stresses due to the variations in temperature.

The above two scaling laws both imply that thermocapillary effects may become a dominant driving mechanism for microfluidics. They have led researchers to explore using thermocapillarity to manipulate fluids in microfluidic situations.

The Solutal Marangoni Effect

Surface tension variations can also be produced by adding surfactants on the interface. These surface active materials (e. g. soap) typically consist of a hydrophilic head group and a hydrophobic tail. Therefore, the presence of surfactants in solution is energetically unfavorable and one gains in free energy if the molecules align along the free surface, which is the equilibrium situation. The creation of a layer of surfactant molecules on the interface then lowers the surface tension of the system.

In transient situations, e. g. in the presence of an external flow or during the formation of droplets, the surface density of the surfactant molecules may be inhomogeneous, which again leads to an imbalance in surface tension, similarly to the thermal case. However, in contrast with the thermal case, the relationship between surface tension and surfactant surface concentration (Γ) is highly nonlinear. A classical model for this dependence states that

$$\gamma = \gamma_0 + RT\Gamma_\infty \ln\left(1 - \frac{\Gamma}{\Gamma_\infty}\right) , \tag{3}$$

which predicts a steep decrease in surface tension as the surface concentration approaches a finite value, Γ_∞. The value of Γ_∞ is determined by the finite space occupied by the surfactant molecules, which sets an upper bound on the surface concentration. See the entry on ▶ Marangoni Convection for a more detailed discussion of this topic.

Key Research Findings

Microfluidic applications of thermocapillarity have centered around the use of temperature gradients to manipulate small quantities of fluid. Young et al. [4], in a pioneering use of thermocapillarity, applied a vertical downward temperature gradient to stabilize the position of a gas bubble against buoyancy. In their experiment [4], the air bubble was subjected to differential heating between its upper and lower sides, as shown in Fig. 2. The flow along the surface, from the hot to the cool side, induces a flow of the external fluid around the bubble in the same direction. The bubble, in reaction to this flow, feels a force which pushes it in the opposite direction. It is as if the bubble were swimming up the temperature gradient.

Experimentally, Young et al. [4] showed that air bubbles a few tens of microns in size could thus be suspended in water between the two cylinders of a machinist's micrometer. The maximum force produced, calculated by balancing the buoyancy force, was of the order of 1 μN.

When gravity can be neglected, which is often the case in microfluidics, the main question that has interested researchers has been that of the velocity of propagation of a drop or a fluid layer for a given temperature gra-



Thermocapillarity, Figure 2 Thermocapillary flow induced by a vertical temperature gradient has been shown to counter the bubble rise due to gravity



Thermocapillarity, Figure 3 A plug of wetting liquid subjected to a temperature gradient, will experience a preasure gradient pushing it towards the hot side

dient. This velocity is given by a balance between the Marangoni stresses and the viscosity. Two categories of such flows can be distinguished. First, when the fluid is in direct contact with a solid substrate, the contact angle between the wall and the substrate imposes a local pressure drop across the interface, through the Young–Laplace law. Therefore the motion of the fluid is associated with a change in the contact angle as well as the change in surface tension. Second, when the fluid is not in contact with the solid, the change in surface tension is associated with a flow of the external fluid, which in turn imposes surface stresses on the drop, as in the experiments of Young et al. [4].

Fluid in Contact with a Solid Substrate

When the drop is in contact with a solid wall, the simplest case is a liquid plug inside a microchannel, shown schematically in Fig. 2. In this figure, we consider a two-dimensional plug of wetting fluid inside a tube. The pressure outside the plug is assumed to be equilibrated at P_0. Inside the plug, there is a pressure jump due to the Young–Laplace pressure, which states that the pressure P_1 is lower than P_0 by an amount γ_1/R where the radius of curvature R may be considered equal to half of the channel size for a wetting fluid. By the same token, the pressure P_2 may be written as $P_0 - \gamma_2/R$. Since the interface at 1 is considered to be cooler than that at 2 and the surface tension drops with increasing temperature, we find that $P_1 > P_2$ and therefore the plug travels towards the hot side.

This first-order analysis accounts for the direction of travel in the channel but does not yield the speed of propagation. The latter is given by a balance between the surface tension deficit and the viscous effects, both in the bulk and at the advancing and receding interfaces. Furthermore, a complete treatment of the problem must also account for the recirculation inside the drop which acts to transport heat from the hot to the cold sides. However, Sammarco and Burns [5] have found experimentally that plug propagation velocities scale linearly with the applied temperature drop for a variety of liquids.

In the case of an open substrate, meaning that only one wall is in contact with the fluid, the initial observation is that a semi-infinite film of liquid subject to a temperature gradient will spread towards the cooler side of the substrate. This can be understood by referring back to Fig. 1 and noting that fluid is pulled towards the cool region, since the surface tension is higher there. A lubrication analysis yields a speed that is proportional to the thermocapillary stress (σ) and to the layer height (h), and inversely proportional to the fluid viscosity (μ).

However, it should be noted that the motion of the film is also associated with a change in its height and the formation of a rim around the advancing interface. This rim was shown to become unstable and to lead to the formation of a fingering pattern with a wavelength (λ) which scales as $h(3\mathrm{Ca})^{1/3}$, where (h) is the film thickness and $\mathrm{Ca} = \gamma U/\mu$ is the capillary number (U being the advance velocity). It can be shown that the film is stable if the width of the layer is smaller than λ.

The case of an isolated droplet on a solid substrate is more significant for microfluidic applications, where one is typically interested in manipulating small volumes of fluid. The analysis of the drop motion is complicated by several factors compared to the continuous film. First, the freedom to change both the front and rear contact angles can act to move the drop either to the hot or to the cold side. More significantly for experiments, the quality of the surface and the wetting properties play a major role. Experiments on isolated drops require that the drop of fluid partially wets the surface, i. e. yielding a finite contact angle when placed in contact with the solid, in order to avoid the spreading of a film of liquid on the surface. However, surfaces with a finite contact angle tend to exhibit a large amount of hysteresis, which implies that the motion of the drop will be characterized by a stop-start motion unless great care is taken with the cleanliness and smoothness of the surface. Most significantly, contact angle hysteresis leads to the existence of a minimum droplet radius for motion, for a given thermocapillary stress. Above this critical value, the propagation speed increases linearly with the radius and the thermal gradient. A detailed discussion may be found in [6].

Finally, it should be noted that contact angle hysteresis may be reduced by bathing the liquid drop in another liquid. Experiments have shown that a drop of water, immersed in oil, will show a very small amount of hysteresis and may be displaced through localized laser heating [7].

Fluid in Suspension away from Walls

The second case is that of a drop of liquid away from any solid walls. In this case, the solid cannot be used to support the production of stresses and the presence of any thermocapillary stress produces a flow in the drop and in the surrounding fluid. This situation also produces a net force on the drop but this situation has been studied much less than that of wall contact. Homsy and his collaborators [8] have studied the migration of a long bubble in a polygonal tube under the effect of a temperature gradient. Although there is always a lubrication film which isolates the bubble from the solid walls, the fluid flow is strongly influenced by the presence of the tube, contrary to the case studied by Young et al. [4]. This allows the modelling to focus on the lubrication film between the bubble and the tube walls and the bubble velocity being computed by conservation of mass. Again, the bubble migration velocity is found to scale linearly with the imposed temperature gradient.

The modelling of an isolated drop involves the calculation of the complete flowfield around the drop in order to determine the forces acting on it. A series of recent papers by Subramanian (and collaborators) [9] have addressed the complete calculations of flow around drops in an infinite medium, taking into account the heat transport, for different ranges in the dimensionless parameters. Solutions for semi-confined geometries, such as those generally encountered in microfluidics, remain generally unavailable although recent work is heading in this direction.

Finally, it should be noted that most experiments with drops involve the presence of surfactants which serve to stabilize droplets and aid in their formation. However, surfactant dynamics and their solubility also vary with temperature. Since the effect of surfactant adsorption can be more dramatic than that of temperature, the surfactant dynamics can greatly modify the effect of temperature gradients. This is the subject of current research.

Examples of Applications

In addition to the transport of fluid, the mixing of the fluid contained inside a droplet is also a major challenge in microfluidics. The flow induced by the thermocapillary forcing has been proposed as a way to mix the contents. This was demonstrated by combining thermocapillary forcing with surface patterning in order to force a liquid layer to flow in an oblique direction with respect to the temperature gradient. The resulting motion of the liquid created recirculation zones which efficiently mix the fluid [6]. Other studies have been undertaken on an isolated drop which is pushed in a carrier fluid. Mixing is achieved in the drop if its motion leads to a breaking of the barriers to mixing, e. g. through a complex cyclical motion. Finally, merging the drops in order to produce chemical reactions by using thermocapillarity has been demonstrated. Droplets in microfluidics are difficult to merge due to the presence of a thin film which becomes harder to displace the thinner it is. This film, known as a lubrication film, prevents drops from approaching each other sufficiently to merge. However, the flow produced by thermocapillary motion has been shown to reduce this film, inducing rapid merging of the drops [10].

Cross References

- ▶ Digital Microfluidics
- ▶ Droplet Based Lab-on-Chip Devices
- ▶ Droplet Dynamics in Microchannel
- ▶ Droplet Evaporation
- ▶ Electrocapillary
- ▶ Electrowetting
- ▶ Marangoni Convection
- ▶ Interfacial Instability
- ▶ Surface Tension Driven Flow
- ▶ Surface Tension, Capillarity and Contact Angle
- ▶ Transport of Droplets by Thermal Capillarity

References

1. Lide DR (2005) CRC Handbook of Chemistry and Physics, 86th edn. CRC, Boca Raton
2. Adamson AW, Gast AP (1997) Physical Chemistry of Surfaces, 6th edn. Wiley, New York
3. Schatz MF, Neitzel GP (2001) Experiments on thermocapillary instabilities. Annu Rev Fluid Mech 33:93–127
4. Young NO, Goldstein JS, Block MJ (1959) The motion of bubbles in a vertical temperature gradient. J Fluid Mech 6:350–356
5. Sammarco TS, Burns MA (1999) Thermocapillary pumping of discrete drops in microfabricated analysis devices. AICHE J 45:350–356
6. Darhuber AA, Troian SM (2005) Principles of microfluidic actuation by modulation of surface stresses. Annu Rev Fluid Mech 37:425–455
7. Kotz KT, Noble KA, Faris GW (2004) Optical microfluidics. Appl Phys Lett 85:2658–2660
8. Lajeunesse E, Homsy GM (2003) Thermocapillary migration of long bubbles in polygonal tubes. II. Experiments. Phys Fluid 15:308–314
9. Barton KD, Subramanian RS (1989) The migration of liquid-drops in a vertical temperature-gradient. J Colloid Interface Sci 133:211–222
10. Baroud CN, Saint Vincent MR, Delville JP (2007) An optical toolbox for total control of droplet microfluidics. Lab Chip 7:1029–1033

Thermocapillary Actuation

▶ Transport of Droplets by Thermal Capillarity

Thermocapillary Convection

► Marangoni Convection

Thermocapillary Effect

► Thermocapillarity

Thermocapillary Pumping

ZHENJUN JIAO, NAM-TRUNG NGUYEN
School of Mechanical and Aerospace Engineering,
Nanyang Technological University, Singapore, Singapore
mntnguyen@ntu.edu.sg

Synonyms

Microplug transport; Microdroplet transport; Thermal pumping; Multiphase pumping

Definition

Thermocapillary pumping (TCP) is a pumping concept based on thermocapillary forces, where a liquid droplet moves through a microchannel or on a planar surface. A temperature gradient leads to a difference of the surface stresses across a liquid droplet and propels it into a cooler region.

Overview

According to the above definition, thermocapillary pumping concept requires an interface between dissimilar continua such as a gas/liquid interface. The molecules of a liquid attract each other due to intermolecular forces. While the molecules inside the bulk liquid experience attractive forces from all directions, the liquid molecules at the gas/liquid interface have neighboring liquid molecules only on the side facing the bulk liquid. The attractive force tends to pull the molecules at the surface into the interior. Thus, the liquid molecules at the interface will rearrange for the minimum surface energy or for the minimum number of molecules at the interface, which also means a minimum surface area. So in the three phase situation, three interfacial forces cause three-phase (solid/liquid/gas) surface tensions. The resultant force caused by these three interfacial forces will decide the final state of a liquid drop. Surface tension σ is considered as the energy required for increasing the surface area of a liquid by a unit area. Surface tension has a unit of $\mathrm{J/m^2}$. Surface tension values of silicone oil in glass capillary are for instance on the order of 10^{-2} to $10^{-1}\ \mathrm{J/m^2}$. The surface tension of a liquid depends on the temperature. At a higher temperature, the attracting force and subsequently the surface tension decrease. For a small temperature range, we can assume a linear relation between surface tension and temperature:

$$\sigma_{\mathrm{lg}}(T) = \sigma_{\mathrm{lg0}} - \gamma (T - T_0) \tag{1}$$

Where σ_{lg} is the surface tension of the gas–liquid interface, γ is a constant, T is the actual temperature, and σ_{lg0} is the surface tension at the reference temperature T_0. The temperature dependency of surface tension is the fundamental concept of thermocapillary pumping.

Thermocapillary pumping offers a simple mechanism for moving drops of liquid within micro-scale channels. The advantage of TCP is its ability to locally control the movement of a single liquid drop rather than a continuous liquid stream. Furthermore, since TCP relies on simple interface heating, devices incorporating TCP can be easily constructed. These advantages make TCP a promising candidate for microfabricated chemical or biological analysis devices that require precisely defined sample volumes and that strive for a simple method for achieving system integration. The above researches have showed us the basic theoretical knowledge of TCP in different aspects which proves that the feasibility of producing TCP [1].

Basic Methodology

The actuation force for a droplet can be achieved by creating a temperature gradient along the direction of the droplet movement. The temperature difference between the two ends of the droplet can cause the different surface tensions, which will finally produce a net force to propel the liquid droplet. Volkoviski first observed that a liquid film tends to spread away from the hotter side of a substrate [2]. Hershey later observed a similar effect, where spatial variation in the film height is determined by the temperature distribution along a thin film [3]. Ludviksson and Lightfoot [4] observed the spontaneous spreading of thin, non volatile films on a vertical wettable substrate subject to a linear temperature change.

Brochard was the first to formulate a theory on the movement of a liquid droplet on a solid with a horizontal thermal gradient [5]. In his paper, reasons of the migration of the droplet under the temperature gradient were determined as the non-uniform surface tension and the different spreading coefficients S which depends on the distance x. The spreading coefficient is negative ($S<0$) for partial wetting. The advancing velocity of the droplet is determined as:

$$v = C\frac{h_0}{\eta}\left[\frac{\partial}{\partial x}(\sigma_{\mathrm{lg}} - \sigma_{\mathrm{sl}}) + \frac{\partial}{\partial x}(\sigma_{\mathrm{sg}} - \sigma_{\mathrm{sl}})\frac{\mathrm{d}T}{\mathrm{d}x} + \frac{1}{2}\frac{\partial\sigma}{\partial T}\frac{\mathrm{d}T}{\mathrm{d}x}\right] \tag{2}$$

Where h_0 is the thickness of the droplet at the center, σ_{lg}, σ_{sl} and σ_{sg} are the surface tension of the liquid/gas, solid/liquid and solid/gas interfaces, respectively.

Key Research Findings

Brzoska et al. experimentally investigated displacement of liquid droplets in a temperature gradient [6]. This work focused on the different radii of the droplets. The results showed that a droplet only moves if its radius is above a critical radius R_c. The critical radius strongly depends on the contact angle hysteresis, but not on the fluid viscosity. For small liquid droplets and radii above R_c, the velocity of the droplet is proportional to the temperature gradient and inversely proportional to the viscosity η. Ford and Nadim determined the velocity and pressure fields within the droplet which is modeled as an infinitely long strip of finite width and arbitrary height profile under the uniform temperature gradient. And the boundary condition in the vicinity of contact line was highlighted [7].

Sammarco and Burns studied thermocapillary pumping of discrete droplets in micro fabricated analysis devices [8]. The major factor limits the pumping velocity is the contact angle hysteresis. Contact angle hysteresis reduces the temperature induced driving force of TCP, thereby introducing a minimum temperature difference requirement for drop movement. This minimum temperature difference is a function of the hysteresis parameter $(1 - \cos\theta_A / \cos\theta_R)$, where θ_A and θ_R are the contact angles at the advancing and the receding edges of the droplet. The greater the degree of hysteresis, the higher the minimum temperature difference needed to initiate droplet movement. When contact angle hysteresis becomes so large that the droplet may boil before moving. Surface treatment can help to reduce the contact angle hysteresis. Further, converging microchannels can offset the hysteresis and the externally applied pressure. Figure 1 shows a set up for measuring the contact angles of receding and advancing ends. Using the low-pressure air source and submerged in liquid, from the Yong–Laplace equation the contact angle can be determined as:

$$\theta_{A,R} = \frac{1}{\cos\left[d\,(p - \rho g h)\,d/(G\sigma)\right]} \tag{3}$$

while σ is the liquid surface tension, d is the channel diameter and G is a constant specific to channel geometry (G=4 for circular, G=2 for slit-like, and G=2(1 + height/width) for rectangular cross sections).

Besides liquid droplets, bubbles can also be pumped in microfabricated channels. Mazouchi and Homsy investigated the migration of a long bubble in a tube with a prescribed axial temperature gradient [9]. The resulting thermocapillary force moves the bubble toward the hotter region, which is opposite to the liquid droplets. The work focused on the determination the bubble velocity. A simplified model was used. The model ignores the gravity in the horizontal tube, the viscosity and the thermal conductivity of the gas. At small Reynolds numbers and capillary numbers, a theory based on the lubrication approximation and matched expansions was presented to determine the shape and speed of the bubble. The assumption of small capillary numbers and long bubbles allows the division of the domain into five regions depicted in Fig. 2. The long cylindrical region of constant film thickness is connected to two constant curvature caps through two transition regions.



Thermocapillary Pumping, Figure 1 Experimental setup for measuring the receding (**a**) and advancing (**b**) contact angle in a microchannel



Thermocapillary Pumping, Figure 2 Section of a bubble in a horizontal tube. Five regions are shown: the constant film thickness region (1), two capillary static's regions (3, 5), and two transition regions (2, 4)

Darhuber et al. demonstrated active manipulation of nanoliter droplets on the surface of a glass or silicon substrate by combining chemical surface patterning with electronically addressable microheater arrays [10]. Hydrophilic lanes determine the possible routes for liquid migration, while the activation of a specific heater determines the trajectories. The induced temperature gradients spatially modulate the liquid surface tension by thermocapillary effect; thereby take over the control of the direction, timing, and flow rate of continuous streams or discrete drops. Temperature maps can be programmed to move, split, trap, and mix microscale volumes without mechanically moving parts. Figure 3 shows an example of droplet splitting using thermocapillary forces. The method of fluidic actuation allows direct accessibility to liquid samples for handling and diagnostic purposes and provides an attractive model for the thermocapillary pump.

Yarin et al. studied the movement of liquid droplets consisting of *n*-decane, *n*-undecane, *n*-dodecane, and *n*-hexadecane on a partially wettable cylindrical fiber [11]. When the temperature gradient was created along the fiber, the droplets began to move along the fiber toward the cold region according to the phenomenon related to the thermocapillary motion. Their theoretical results and experimental data agree reasonably well with their theories. The model of the droplet motion reveals its potential importance for a number of applications, particularly for draining filters that coalesces liquid droplets from a gas stream.



Thermocapillary Pumping, Figure 3 Splitting of a droplet using thermocapillary force. When the heater is turned on, the induced temperature gradient causes the droplet to move away from the heater. As result, the droplet is split at its center

Glockner and Naterer reported a new method of cyclic flow control with an external heat source is developed for thermocapillary pumping of a microdroplet in a closed microchannel [12]. The pumping concept involves a stationary cyclic heat source embedded within an adjoining silicon substrate. Lab on a chip based on thermocapillary pumping can be realized with this concept. The internal and external motions of micro-droplet are examined numerically using the finite-volume method and analytically using slug-flow approximation. The solution of the full Navier–Stokes and energy equations within the droplet were considered. Additionally, temperature boundary conditions for a stationary heat source are applied at the interface between the substrate and its surroundings, rather than along the microchannel wall.

Burns and Masterangelo reported microfabricated structures for integrated DNA analysis based on photolithography silicon micromachining [13]. The thermocapillary pump was able to move discrete nanoliter drops through enclosed channels using only local heating. The same actuation concept can accurately mix, measure, and divide drops by simple electronic control of the heater. In addition, they have constructed thermal-cycling chambers, gel electrophoresis channels, and radio labeled DNA detectors that are compatible with the fabrication process. Since all of the components are made by conventional photolithographic techniques, they can be integrated into a more complex system.

DeBar and Liepmann reported a silicon-based TCP with integrated microheaters [14]. The devices were operated at a variety of heater settings to evaluate their performance over a range of flow rates and pressures. A minimum energy of 140 mW was required from the central heater to generate and maintain the vapor bubble, and the flow rate increased with input energy. The efficiency of the device increased with flow rate, since the overhead to create and maintain the bubble (140 mW) dwarfs the energy expended to generate the temperature gradient (15 – 50 mW). The devices generated a maximum pressure head of 44 Pa, and a maximum flow rate of 9.3 nL/s.

Future Directions for Research

Despites its simplicity in implementation, thermocapillary pumping was not fully exploited in microfluidics research community. Thermocapillary may have a big impact in droplet-based digital microfluidics. Besides droplet transport, thermocapillary force can be used for other droplet manipulation functions such as splitting, merging and dispensing. More research results in this direction can be expected in the near future.

Cross References

► Droplet Dynamics in Microchannels

References

1. Darhuber AA, Troian SM (2005) Principles of microfluidic actuation by modulation of surface stresses. Annu Rev Fluid Mech 37:425–455
2. Volkoviski V (1935) Sur les tourbillons en festons. Compt Rend Acad Sci Paris 200:285–87
3. Hershey AV (1939) Ridges in a liquid surface due to the temperature dependence of surface tension. Phys Rev 56:204
4. Ludviksson V, Lightfoot EN (1971) Dynamics of thin liquid films in the presence of surface- tension gradients. AIChE J 17:1166–1173
5. Brochard F (1989) Motions of droplets on solid surfaces induced by chemical or thermal gradients. Langmuir 5:432–438
6. Brzoska JB, Brochard-Wyart F, Rondelez F (1993) Motions of droplets on hydrophobic model surfaces induced by thermal gradients. Langmuir 9:2220–2224
7. Ford ML, Nadim A (1994) Thermocapillary migration of an attached drop on a solid surface. Phys Fluid 6:3183–3185
8. Sammarco TS, Burns MA (1999) Thermocapillary pumping of discrete drops in microfabricated analysis devices. J AIChE 45:350–366
9. Mazouchi A, Homsy GM (2000) Thermocapillary migration of long bubbles in cylindrical capillary tubes. Phys Fluid 12:542–549
10. Darhuber AA, Valentino JP, Davis JM, Troian SM, Wagner S (2003) Microfluidic actuation by modulation of surface stresses. App Phys Lett 82:657–679
11. Yarin AL, Liu W, Reneker DH (2002) Motion of droplets along thin fibers with temperature gradient. J Appl Phys 91:4751
12. Glockner PS, Naterer GF (2005) Thermocapillary control of microfluidic transport with a stationary cyclic heat source. J Micromech Microeng 15:2216–2229
13. Burns MA, Mastrangelo CH (1996) Microfabricated structures for integrated DNA analysis. Proc Natl Acad Sci 93:5556–5561
14. DeBar MJ, Liepmann D (2002) Fabrication and performance testing of a steady thermocapillary pump with no moving parts. In: Proceedings of the IEEE Micro Electro Mechanical Systems (MEMS 2002), pp 109–112

Thermocapillary Shear Stress

Definition

Shear stress induced by a temperature gradient resulting in directional fluid transport from high to low temperature.

Cross References

► Surface-Directed Capillary Flow Systems

Thermochromic Liquid Crystals

► Liquid Crystal Technique for Measuring Temperature

Thermocouples

Definition

A thermocouple is a measuring device consisting of two different metals or semiconductors, commonly performed as wires, which are connected in one point. Because of the Seebeck-effect an electrical voltage can be measured between the two metals as long as the junction and the free ends of the wires have different temperature levels. The voltage is almost linear with the temperature difference and lies for metals in the range of some micro-volts per Kelvin.

Cross References

► Contact Temperature Sensors
► Thermoelectric Flow Sensors

Thermodiffusion

► Thermophoresis

Thermoelectric Effect

► Peltier Effect

Thermoelectric Flow Sensors

NORBERT KOCKMANN
Laboratory for Design of Microsystems
Department of Microsystems Engineering – IMTEK,
Albert-Ludwig University of Freiburg, Freiburg, Germany
kockmann@imtek.de

Synonyms

Thermoelements; Thermal flow sensors

Definition

Thermoelectric flow sensors indirectly measure the velocity of gases and liquids close to the wall and the volume flow rate in a microchannel. Electrical heating, thermoelectric temperature sensing, appropriate calibration, and



Thermoelectric Flow Sensors, Figure 1 Setup of a thermoelectric flow sensor in a channel consisting of a heater and two temperature sensors upstream and downstream of the heater, method A; *left*: conductive heat transfer with symmetric temperature profile; *right*: convective heat transfer with higher temperature at sensor 2

sensor control are essential for fast, reliable and sensitive measurement.

Overview

Flow measurement using thermoelectric devices and sensors implies the use of heat transfer and temperature measurements in microchannels to determine the near-wall velocity. With appropriate calibration procedures, the mean flow velocity or mass flow rate can be determined by measurements of the local wall temperature. Thermoelectric temperature probes and sensors, also known as thermocouples, rely on the Seebeck effect, where a temperature difference between two metal contacts induces a voltage drop which can be measured. An electrical resistance heater introduces a heat flux into the fluid flow. The temperature is measured either directly at the heater, in its vicinity, or at the wall downstream of the heater. Often, the upstream mean temperature of the fluid flow is also measured to provide a comparison. Thermoelectric flow rate measurement is one of commonest, and for laminar flow one of the most accurate, reliable, and cost-effective measuring techniques.

Basic Methodology

The flow sensor consists mainly of the heating element and temperature sensors, which measure the temperature of the heater or of the fluid before and after the heater. The streaming fluid is mainly heated by resistance heaters. The temperature can be measured either by electrical resistance sensors or by thermocouples. This essay concentrates on the latter method for thermoelectric flow sensors.

Thermoelectric temperature measurement has been established for more than a century, and the sensing devices, including thermocouples, have been miniaturized from the start. Van Herwaarden and Sarro [1] presented thermoelectric flow sensors, which were then adopted in the textbook by Middelhoek and Audet [2]. The basic measuring principle was not changed but was modified and improved by the choice of different materials, geometry, and device design. The basic sensor setup can be classified into two different techniques or methods. In method A, heating of the fluid imposes a temperature profile in the channel or near-wall flow (see Fig. 1), which is measured at certain positions by thermocouples. In method B, fluid flow cools the heater, the temperature or electrical power of which is measured (see Fig. 2). Besides the integral heater temperature, the local temperatures of a heated area can be measured, which allows a direction-sensitive velocimetry (see Fig. 3).

In method A, the temperature downstream of the heater is taken to determine the mean flow velocity in the vicinity of the heater. The general setup is shown in Fig. 1. The geometric setup of the heater and sensors determines the measurement of the fluid flow.

The temperature profile in the microchannel without fluid flow is nearly symmetric, and both sensors are detecting a similar temperature. The fluid flow shifts the temperature profile downwards, and the sensor located downstream measures a higher temperature; the sensor located upstream measures the temperature of the incoming fluid. The temperature distribution has been simulated by Ashauer et al. [3].



Thermoelectric Flow Sensors, Figure 2 Thermoelectric flow sensor consisting of an electrical heater on a thin membrane with parallel meandering thermoelectric sensors, two thermopiles with 15 thermoelements [4]



Thermoelectric Flow Sensors, Figure 3 Two-axis flow measurement from convective cooling of the sensor device with connected temperature sensors and direct heating of the membrane, acc. van Oudheusden [7]

The geometric setup of a fabricated device in thin film technology (see Fig. 2) is an example of method B. The heating structure with the adjacent meandering thermopiles to measure the temperature is located on a thin membrane to reduce the heat losses to the wall material. The thermocouples are arranged in a pile (series switching) to increase the sensitivity of the sensor used to measure the temperature difference between the heater and the substrate. A good example of the microstructure device has been given by Buchner et al. [4] (see Fig. 2).

A different scheme with a periodic heater/sensor setup was proposed by Al khalfioui et al. [5] with a more detailed flow measurement. This system is more complex and the effort required to measure the physical domain is correspondingly greater.

Measurement of the flow by a heated membrane with connected thermocouples has been proposed by van Oudheusden [6, 7]. The schematic setup is shown in Fig. 3. Comparing the four measured temperatures allows not only measuring the flow near the wall, but can also determine the angle of attack of the main direction of flow. More details of the analysis have been given by van Oudheusden [7]. The sensor contacts also serve as mechanical hinges and guarantee a good thermal insulation for the heated membrane.

For commercial flow sensors, the in-line setup according to method A with one heater and two sensors, one upstream and one downstream, is the most important and has been commercially realized by sensor suppliers.

Key Research Findings

General Setup

The geometric setup has been explained in the section on basic methodology. The general requirements of the signal processing are now described. The domain of the mechanical signal to be measured is determined by the flow and the velocity profile near the wall and the heating/sensing device. The flow-induced heat transfer (convection) and the parallel heat conduction in the sensor wall/substrate interface determine the measured temperature. Comparison of two or more temperatures indicates the flow and can be transferred into a flow rate, thus giving the complete flow situation. The temperature is measured as a voltage between the hot and cold ends of the thermocouple [6]. With this setup, three complex domains are combined: fluid flow, heat transfer, and thermoelectric energy and signal conversion.

In the following, we will start with the fluid flow and convective heat transfer, followed by the temperature measurement and will then characterize the entire device.

Heat Transfer and Fluid Flow

The electrical power dissipated in the heater spreads into the flowing fluid and the wall or substrate supporting the heater and sensors. In a steady-state situation, the energy balance of the heater/sensor expresses the correlation between the electrical heating power P and the heat dissipated into the substrate Q_S and into the fluid Q_f

$$P = Q_\mathrm{S} + Q_\mathrm{f} = G_\mathrm{S}\,(T_\mathrm{H} - T_\mathrm{S}) + G_\mathrm{f}\,(T_\mathrm{H} - T_\mathrm{f}) \qquad (1)$$

where T_H, T_S, and T_f are the temperature of the heater, the substrate, and the bulk fluid, respectively. The coefficients G_S and G_f indicate the thermal conductivity of the substrate and the convection by the flowing fluid, respectively. Due to the small temperature differences, radiation heat transfer can be neglected in most cases. The flow measurement relies on the variance of G_f with the flow and is measured, for example, by the temperature difference induced by a given electrical power.

As already mentioned, the flow rate can be determined by measuring the temperature of either the heater (method B) or the fluid downstream of the heater (method A). In both cases, the temperature of the fluid upstream of the heater must be known or must be set to the ambient temperature. First, we focus on measuring the fluid temperature downstream of the heater according to method A.

The wall heat transfer from the heater determines the energy used for heating the fluid and increasing its temperature. The location of the temperature sensor influences the measurement and should not be too far downstream from the heater. If the inflowing fluid has the same temperature as the sensor substrate, T_S, and the sensors measure the mean temperature of the fluid, the energy dissipation into the fluid is determined by

$$Q_\mathrm{f} = \dot{m}\,c_\mathrm{p}\,(T_\mathrm{S} - T_\mathrm{f}) \qquad (2)$$

where the mass flow rate $\dot{m} = \rho_\mathrm{f} A_\mathrm{C}\, u$ and c_p is the heat capacity of the fluid. The density of the fluid ρ_f and the channel cross-section A_C should be known in order to obtain the correct sensing. The mean flow velocity u is determined with the heater power and the measured temperature difference

$$P = Q_S + \rho_f \, c_p \, A_C \, (T_S - T_f) \; u \tag{3}$$

where the heat dissipation into the substrate Q_S has to be estimated. The measurement of the fluid temperature downstream is not very accurate, so the fabricated sensor always has to be calibrated.

Convective cooling of an electrical heater and measuring its temperature according to method B avoids some sources of error, like measuring the heated fluid temperature or the unknown amount of heat dissipated into the substrate. For this reason, many sensors are located on a thin membrane or are fabricated on polymers or on other thermal insulations. This minimizes the parasitic heat loss and increases the sensor's accuracy. The convective heat transfer into the fluid Q_f is determined by the heat transfer coefficient α_W at the wall and by the temperature difference.

$$\frac{Q_f}{A_H} = q_f = \alpha_W \, (T_H - T_f) \tag{4}$$

The cooling heat transfer of the electrical heater can be treated like cooling a plate on one side in surface flow. Here, the influence of the surrounding channel walls is neglected for simplicity. With the help of the boundary layer theory, the wall heat transfer is described by the dimensionless heat transfer coefficient, the local Nusselt number Nu [7]

$$\mathrm{Nu} = \frac{\alpha \, x}{\lambda_f} = 0.332 \, \mathrm{Pr}^{\frac{1}{3}} \mathrm{Re}^{\frac{1}{2}} \tag{5}$$

which has the dimensionless fluid properties (Prandtl number) $\mathrm{Pr} = \lambda_f / \rho_f \, c_{p,f}$ and dimensionless flow conditions (local Reynolds number) $\mathrm{Re} = u\,x/\nu$. For the entire length of the heater, l_H, the overall Nu_L number has been given by Welty et al. [8].

$$\mathrm{Nu}_L = \frac{\alpha \, l_H}{\lambda_f} = 0.664 \, \mathrm{Pr}^{\frac{1}{3}} \mathrm{Re}^{\frac{1}{2}} \tag{6}$$

Both equations are valid for laminar flow with $\mathrm{Re} = u\,x/\nu < 2 \times 10^5$. The correlation between the flow velocity and the dissipation power and measured temperature difference is given by

$$\begin{aligned} \frac{Q_f}{A_H} &= \frac{\mathrm{Nu}\,\lambda_f}{l_H} \, (T_H - T_f) \\ &= 0.664 \, \lambda_f \, \mathrm{Pr}^{\frac{1}{3}} \left(\frac{u}{l_H \, \nu} \right)^{\frac{1}{2}} (T_H - T_f) \end{aligned} \tag{7}$$

where the length coordinate x replaces the heater length, l_H. Arranging the above equations the correlation of the electrical heating power with the flow velocity gives the following equation:

$$\begin{aligned} P = {} & G_S \, (T_H - T_S) \\ & + 0.664 \, \lambda_f \, A_H \, \mathrm{Pr}^{\frac{1}{3}} \left(\frac{u}{l_H \, \nu} \right)^{\frac{1}{2}} \cdot (T_H - T_f) \end{aligned} \tag{8}$$

The detailed analysis of the correlation needs many parameters such as: the heat conductivity of the substrate, the correct fluid properties, and the correct geometry of the sensor. For practical applications, the correlation between the electrical power, the measured temperature difference, and the flow velocity can be reduced to

$$P = \left(c_1 + c_2 \sqrt{u} \right) \, \Delta T \tag{9}$$

for laminar flow with $\Delta T = T_H - T_f$ [9]. Both coefficients can be determined by calibration measurements and should not vary with time or flow velocity. However, the fluid properties have to be calibrated to obtain the correct measurements. The operation of the device with different measuring modes is described in the section about the design, fabrication, and operation of the devices.

Temperature Measurement by Thermoelectric Effect

Due to their compactness and standard fabrication technology, the temperature in thermal flow sensors is often measured by thermocouples, which rely on the thermoelectric effect. The thermoelectric effect describes the coupling between the electrical and thermal currents, especially the occurrence of an electrical voltage due to a temperature difference between two material contacts, known as the Seebeck effect. In reverse, an electrical current can produce a heat flux or a cooling of a material contact, known as the Peltier effect. A third effect, the Thomson effect, is also connected with thermoelectricity where an electric current flowing in a temperature gradient can absorb or release heat from or to the ambient [10, 11]. The relation between the first two effects can be described by methods of irreversible thermodynamics and the linear transport theory of Onsager in vector form.

$$\begin{bmatrix} q_{el} \\ q_{th/T} \end{bmatrix} = \begin{bmatrix} \sigma_{el} & L_S \\ L_P & L_q \end{bmatrix} \begin{bmatrix} \Delta U \\ \Delta T \end{bmatrix} \tag{10}$$

The electrical current density q_{el} and the thermal entropy flux q_{th}/T are linked to the driving forces, the temperature gradient ΔT and the potential gradient ΔU with linear coefficients: σ_{el} as the electrical conductivity, L_q for the heat transfer, L_{S} for the Seebeck effect, and L_{P} for the Peltier effect.

Solving the first equation for ΔU and substituting the result into the second equation yields

$$-\Delta U = \frac{q_{\mathrm{el}}}{\sigma_{\mathrm{el}}} + \frac{L_{\mathrm{S}}}{\sigma_{\mathrm{el}}} \Delta T \tag{11}$$

$$q_{\mathrm{th}} = T \frac{L_{\mathrm{P}}}{\sigma_{\mathrm{el}}} q_{\mathrm{el}} + T \left(\frac{L_{\mathrm{S}}\, L_{\mathrm{P}}}{\sigma_{\mathrm{el}}} - L_{\mathrm{q}} \right) \Delta T \tag{12}$$

The matrix in Eq. (10) is symmetrical according to the Onsager reciprocity law [11], which means $L_{\mathrm{S}} = L_{\mathrm{P}}$. The linear coefficients can be identified with known material properties

$$\rho_{\mathrm{el}} = \frac{1}{\sigma_{\mathrm{el}}} \tag{13}$$

$$\lambda_{\mathrm{th}} = -T \left(\frac{L_{\mathrm{S}}\, L_{\mathrm{P}}}{\sigma_{\mathrm{el}}} - L_{\mathrm{q}} \right) = -T \left(\frac{2\, L_{\mathrm{S}}}{\sigma_{\mathrm{el}}} - L_{\mathrm{q}} \right) \tag{14}$$

$$\alpha_{\mathrm{ab}} = \frac{L_{\mathrm{S}}}{\sigma_{\mathrm{el}}} \tag{15}$$

$$\pi_{\mathrm{ab}} = T \frac{L_{\mathrm{P}}}{\sigma_{\mathrm{el}}} \tag{16}$$

The thermoelectric temperature measurement employs the Seebeck effect, the voltage between two material pair contacts on a different temperature level without the flow of electrical current ($Q_{\mathrm{el}} = 0$). The Seebeck effect can also be described by the correlation

$$\Delta U = (\alpha_{\mathrm{a}} - \alpha_{\mathrm{b}})\ \Delta T = \alpha_{\mathrm{ab}}\, \Delta T \tag{17}$$

where α_{ab} is the Seebeck coefficient for the material pair $\mathrm{a} - \mathrm{b}$. The Seebeck coefficient depends on the pair of materials. Certain applications, like sensing or energy conversion, demand certain parameter combinations like heat or electrical conductivity or temperature linearity. For temperature measurement, standardized elements and pairs of materials are used which have good linearity of the material properties, reproducibility, and long-term stability.

A summary of the common standardized thermocouples is given in Table 1. Besides the thermoelectric properties of the Seebeck coefficient, the thermal and electrical conductivities are important for the sensitivity and time response of the thermoelectric flow sensor.

The materials of standardized thermocouples are rarely used in microfabrication, which relies to a large part on CMOS technology. Table 2 lists the metals commonly used in microfabrication. Van Herwaarden [1] and Rowe [11] have also given a summary of microthermocouple materials. Often, the thermoelectric pairs of materials are used for energy conversion from heat to electricity with the help of thermoelectric generators. Here, the so-called figure-of-merit, Z, gives an indication of a good energy conversion and is given by

$$Z = \frac{\alpha_{\mathrm{ab}}^2}{\left(\sqrt{\lambda_{\mathrm{a}}\, \rho_{\mathrm{a}}} + \sqrt{\lambda_{\mathrm{b}}\, \rho_{\mathrm{b}}}\right)^2} = \frac{\alpha_{\mathrm{ab}}^2\, \sigma_{\mathrm{a}}}{\lambda_{\mathrm{a}}} \tag{18}$$

The second part of Eq. (18) is often used to characterize the thermoelectric activity of a single material α. This parameter may help to identify sensitive pairs of materials for thermoelectric temperature measurement.

Due to its use in microelectronics, silicon is by far the most common and best understood semiconductor material. It is cheap and a large variety of fabrication processes are available. Consequently, silicon has become a common material for thermoelectric sensors. The material properties of silicon depend heavily on the doping concentration and type as well as on the fabrication process [9].

A comparison of the values in Tables 3 and 4 gives remarkable differences between the bulk material and the deposited film material. Baltes et al. [9] have given the properties of n- and p-doped silicon together with the fabrication process, which also differs over a wide range. The doping concentration determines the thermoelectric properties of silicon over a wide range [12, 13]. For practical

Thermoelectric Flow Sensors, Table 1 Some commercially available thermocouples for temperature measurement (IC 584-1)

Material	Type	Seebeck coefficient (μV/K)	Operating range (°C)
Fe/CuNi	J	51	−200 – 760
NiCr/AlNi	K	41	−200 – 1260
PtRh/Pt	R	6	0 – 1480
Cu/CuNi	T	41	−200 – 370

Thermoelectric Flow Sensors, Table 2 Properties of some metals used in microfabrication at room temperature

Material	Seebeck coefficient α (μV/K)	Thermal conductivity λ (W/mK)	Electrical resistivity ρ (10^{-9} Ωm)
Aluminum (Al)	−1.66	237	26.5
Chromium (Cr)	21.8	93.9	125.0
Copper (Cu)	1.83	401.0	16.78
Titanium (Ti)	9.1	21.9	420.0
Gold (Au)	1.94	318.0	21.14

Thermoelectric Flow Sensors, Table 3 Thermoelectric properties of bulk material

Material	Seebeck coefficient α (µV/K)	Thermal conductivity λ (W/mK)	Electrical conductivity σ (10^4 1/Ωm)
p-$Bi_{0.5}Sb_{1.5}Te_3$	218	0.59	4.0
Bi_2Te_3	210	2.0	7.7
Sb_2Te_3	124	1.3	13.5
Bi	−65	8.3	83
Sb	36	24	238
PbTe	−200	3.5	13.0
Si (n-type)	−450	145	2.9

Thermoelectric Flow Sensors, Table 4 Thermoelectric properties of thin films [9] and other sources

Material	Seebeck coefficient α (µV/K)	Thermal conductivity λ (W/mK)	Electrical conductivity σ (10^4 1/Ωm)
p-$Bi_{0.5}Sb_{1.5}Te_3$	230	1.05	5.8
p-$Bi_{0.87}Sb_{0.13}$	−100	3.1	14.0
Bi	−65	5.2	28.5
Sb	35	13	100.0
PbTe	−170	2.5	5.0
Si (n-poly)	−108 to −520	16 – 29	0.2
Si (p-poly)	190 – 330	19 – 20	n.a.

applications it is very important to characterize the fabrication process and the relevant outcome and to ensure the reproducibility of the properties of the material.

Design, Fabrication, and Operation of Devices

Not only the single sensor components like heater or sensor, but also the interplay of the parts, their integration and the entire device are important for the performance of the sensor. Table 5 gives the general relationship between the film and bulk properties of the sensor and the sensing characteristics.

The more generalized parameters of the thermal conductance, G, and the temperature conductivity, C, are a function of the sensor geometry and the heat and temperature diffusivity. The device parameters and characteristics are determined by the properties such as the thermal conductivity or the Seebeck coefficient of the thermoelectric materials as well as the geometric setup and fabrication method. The main sensor signal output is determined by the number of thermocouples n, the Seebeck coefficient, and the measured or applied temperature differences. With a higher temperature difference, the signal increases with the heat loss. Hence, the sensitivity of the sensor depends mainly on the properties of the thermocouple, and the thermal conductance of the fluid and the substrate. For gas flow measurement and high temperature differences, the emissivities of the heater, thermocouple, and substrate have to be considered.

The necessary power for a clear and noise-free signal can be determined from the noise of the electrical conductivities and the sensitivity of the sensor. The inverse ratio gives the detectivity of the sensor. The time constant of the sensor, which determines the response time to flow changes or the start-up time of the sensor, is a function of the thermal diffusivity of the heater, thermocouple(s), and the substrate, as well as the thermal conductance of the entire device.

In summary, a high Seebeck coefficient and high electric conductivity of the sensor as well as low thermal conductance of the sensor and the substrate provide a sensitive, low energy-consuming sensor with a fast response time. Hence, the figure-of-merit (Eq. (18)) of a thermoelectric flow sensor is a good indicator of quality. However, the heater and sensor are often fabricated in thin-film technology on membranes, glass, or polymer substrates. The material combinations of the devices must also guarantee low thermal stress due to the expansion of heating and

Thermoelectric Flow Sensors, Table 5 Relationship between sensor parameters and film/substrate properties for sensors with n thermocouples, acc. Baltes et al. [14]

Film properties		Sensor parameters
Seebeck coefficient α		Thermoelectric voltage, signal
Thermal conductivity λ		$U = n\left(\alpha_a - \alpha_b\right)\,\Delta T$
Electrical conductivity σ		
Figure of merit $Z = \frac{\alpha_{ab}^2 \sigma_a}{\lambda_a}$		Sensitivity
Emissivity ε		$S = \frac{n(\alpha_a - \alpha_b)}{G(n,\lambda,\varepsilon,\lambda_s,\varepsilon_s)}$
Density ρ		Noise equivalent power
Heat capacity c_p		$\mathrm{NEP} \propto \frac{(R(\sigma))^{1/2}}{S}$
Thermal diffusivity $a = \frac{\lambda}{\rho\, c_p}$	$\Rightarrow$	
Substrate properties		Detectivity
Thermal conductivity λ_s		$\mathrm{D}^* \propto \frac{S(F)^{1/2}}{(R(\sigma))^{1/2}}$
Emissivity ε_s		
Density ρ_s		
Heat capacity $c_{p,s}$		Time constant
Thermal diffusivity $a = \frac{\lambda_s}{\rho_s\, c_{p,s}}$		$\tau = \frac{C(a,a_s)}{G(n,\lambda,\varepsilon,\lambda_s,\varepsilon_s)}$

Thermoelectric Flow Sensors, Table 6 Material properties for device design, thermal expansion behavior [15]

Material	Specified electrical resistance ρ, 20 °C ($\mu\Omega$cm)	Specified thermal expansion, 0 – 100 °C 10^{-6} (1/K)	Heat conductivity λ_S, 0 – 100 °C (W/mK)
Gold	2.2	14.1	318
Platinum	10.58	9	71.6
Titanium	54	8.9	21.9
Polyimide		30 – 60	0.1 – 0.35
PTFE		100 – 160	0.25
PSU		50 – 60	0.26 – 0.28
PMMA		70 – 77	0.17 – 0.19
Quartz		0.5	1.4 – 1.9
Glass ceramics		13	1.5

cooling. Table 6 gives the thermal and electrical properties of some sensor materials.

Besides the properties and the geometrical setup, the operating mode of the sensor device is important for the application and sensitivity. The heater can be operated in two modes [16]: with constant electrical power or at a constant controlled temperature. With constant electrical heating power, the measurement of the temperature difference ΔT is appropriate for low liquid flow rates or gas flow. No temperature control is necessary for the heater. The heater cannot be overheated when an error occurs. Measuring the heater temperature T_H is suitable for liquid flow rates, but the fluid temperature has to be known. With a constant heater temperature, the measurement of the temperature difference ΔT can detect very low liquid flow rates and gas flow. Measuring the heating power is applicable for medium liquid flow rates. Due to the fast signal response, this mode can also be used to investigate the flow behavior. During to the longer operating time, thermal drift of the sensor or time drift of the thermocouple may occur and should be controlled by the routine calibration procedures.

The electrical insulation of the heater and the sensors is not critical when designing gas flow sensors, but has to be considered for liquid flows. In many cases, insulating layers, like metals oxide or polymer films, are deposited on the surface of the electrical conducting layers. Many thermoelectric flow sensor devices have been designed and fabricated for investigation and research purposes, but some are already commercially available. An overview of the existing devices has been given by Dittmann [15], but does not claim to be complete (see Table 7).

Dittmann's [15] estimation of the costs may serve as a reference point. In the fast developing area of sensor technology, costs can change rapidly. Future improvements in fabrication technology and new emerging markets may change the price level of existing sensors or produce new types of thermoelectric flow sensors.

Future Directions for Research

The most important requirements for successful sensors are accuracy, good reliability, and long-term operability at an acceptable price. Many applications may require standard sensors, but tailor-made solutions and integrated devices in Lab-on-a-Chip or microprocess technology application are also urgently needed. A standardization

Thermoelectric Flow Sensors, Table 7 Overview of existing devices [15]

Company, Institute, Sensor	FZK-IMT AMANDA sensor	HSG-IMIT flow sensor	Bosch MFM6	Leister Mflow 20	Sensirion ASF1400	MKS M20	Bronkhorst LiquiFlow L1
Fluids	liquid/gas	liquid/gas	gas	gas	(liquid) gas	gas	liquid
Flow rate (min)	0.1 sccm	0.1 sccm	6 l/min	0.01 sccm	0.01 sccm	0.01 sccm	
Gas Liquid	0.1 µl/min	0.16 µl/min			nl range		1.6 µl/min
Response time	2.5 ms	1 – 3ms	7 ms	>1 ms	150 ms	500 ms	1 – 2s
Temperature difference							
Gas	45 °C	–	150 – 180 °C	–	–	90 – 110 °C	
Liquid	6 °C						>1 °C
Dynamics	1:100	1:100	1:100	1:100	1:40 000	1:100	1:50
Fabrication	AMANDA polymers	silicon	silicon	silicon	silicon	conventional	conventional

of sensing elements and entire devices will help developers and users in many areas. Besides the typical materials, which might already be standardized, like thermocouples or heater materials, the standardization of typical geometries of the heater/sensors and the sensor setup would be very helpful for future developments and applications. The integration of sensing elements into various materials like metals, polymers, glass, or ceramics is very important for the wide application of the flow sensors in chemical or thermally challenging environments. An intelligent three-dimensional setup of the heater and the sensors elements may help to achieve more accurate measurements. For long-term application, an automated calibration procedure is desirable and will give a user-friendly sensor.

Cross References

- ► Chemical Vapor Deposition for Film Deposition
- ► Developing Flows
- ► Electrothermal Effects
- ► Fluid Metering
- ► Heat Transfer in Microchannels Flow
- ► Methods for Flow Rate Measurements
- ► Measurements for Temperature Measurements
- ► Resistance Temperature Detectors
- ► Thermocouples
- ► Thermoresistive Flow Sensors

References

1. van Herwaarden A, Sarro P (1986) Thermal sensors based on the Seebeck effect. Sens Actuators 10:321–346
2. Middelhoek S, Audet SA (1994) Silicon Sensors. Department of Electrical Engineering, Technical University of Delft
3. Ashauer M, Glosch H, Hedrich F, Hey N, Sandmaier H, Lang W (1999) Thermal flow sensors for liquids and gases based on combinations of two principles. Sens Actuators A 73:7–13
4. Buchner R, Sosna C, Maiwald M, Benecke W, Lang W (2006) A high-temperature thermopile fabrication process for thermal flow sensors. Sens Actuators A 130:262–266
5. Al khalfioui M, Michez A, Giani A, Boyer A, Foucaran A (2003) Anemometer based on Seebeck effect. Sens Actuators A 107:36–41
6. van Oudheusden B (1992) Silicon thermal flow sensors. Sens Actuators A 30:5–26
7. van Oudheusden B (1991) The thermal modelling of a flow sensor based on differential convective heat transfer. Sens Actuators A 29:93–106
8. Welty JR, Wicks CE, Wilson RE (1984) Fundamentals of Momentum, Heat, and Mass Transfer, 3rd edn. Wiley, New York
9. Baltes H, Paul O, Brand O (1998) Micromachined thermally based CMOS microsensors. In: Proceedings IEEE86 8:1660–1678
10. Nolas G, Sharp J, Goldsmit H (2001) Thermoelectrics - Basic Principles and New Material Developments. Springer, Berlin, Heidelberg
11. Rowe D (2006) Thermoelectrics Handbook – Macro to Nano. CRC, Boca Raton, Florida
12. Menz W, Mohr J, Paul O (2005) Mikrosystemtechnik für Ingenieure. Wiley-VCH, Weinheim
13. von Arx M (1998) Thermal properties of CMOS thin films. PhD Thesis, ETH, Zürich
14. Baltes H, Moser D, Völklein F (1994) Thermoelectric Mocrosensors and Microsystems. Chap. 2 in Bau H, DeRooij NF, Kloeck B (Eds), Sensors – A Comprehensive Survey. Vol. 7: Mechanical Sensors, VCH, Weinheim, 14–55
15. Dittmann DM (2001) Durchflusssensoren aus Kunststoff für sehr kleine Volumenströme auf der Basis des AMANDA-Verfahrens. Forschungszentrum Karlsruhe, Wissenschaftliche Berichte FZKA 6710
16. Gerlach G, Dötzel W (1997) Grundlagen der Mikrosystemtechnik. Hanser, Munich

Thermoelements

► Thermoelectric Flow Sensors

Thermoforming

► Micromolding

Thermomechanical Valves

LIN GUI, CAROLYN REN
Department of Mechanical and Mechatronics
Engineering, University of Waterloo, Waterloo,
ON, Canada
c3ren@mecheng1.uwaterloo.ca

Synonyms

Thermal mechanical valves; Thermally actuated mechanical valves; Thermally driven mechanical valves

Definition

A thermomechanical valve is a device that regulates fluid flow (either gas flow, liquid flow or slurry flow) by using an actuator which deforms under different temperatures to open, close, or partially obstruct various channels.

Overview

Since Kilby, the 2000 Nobel Prize winner, proposed the first integrated circuit in 1958, microfabrication has been a very attractive topic in a wide range of research fields. In the late 1970s, influenced by the development of microfabrication technology, microelectromechanical

Thermomechanical Valves, Table 1 Materials for the microvalves

	Thermal expansion microvalves		Bimetallic microvalves	Thermally driven SMA microvalves
	Thermal expansion buckling microvalves	SCE microvalves		
Materials	Si, Ni, etc.	Water, paraffin, etc.	PMMA-polymide, $Si-Ni$, $Si-Au$, $Al-Si$, SiO_2-Al, etc.	$Ni-Ti$, $Ni-Ti-Pd$, $Ni-Ti-Cu$, etc.

systems (MEMS) began to flourish in every mechanical field and about 10 years later largely drove the development of microfluidic chips. A typical microfluidic chip is a piece of glass or plastic plate with a network of microchannels, electrodes, and electrical circuits integrated onto it to perform a series of chemical or biomedical diagnoses and analyzes such as: DNA separation, enzymatic analysis, bacterial diagnosis etc. Normally, the volume of liquid that a microfluidic chip deals with is in the range of a nanoliter to a picoliter. The small volume requirement together with other advantages benefiting from miniaturization, such as short analysis time, high throughput, and minimized Joule heating, make such small-scale devices more competitive than their traditional counterparts. There are several commonly used methods to manipulate the liquid in a microfluidic chip including both mechanical and nonmechanical approaches, such as electrokinetic, magnetic, and electrochemical methods. Different approaches will lead to the development of different microvalves, which can be categorized as active or passive valves. Under each of the above category, microvalves can be further classified into mechanical or nonmechanical valves. Typical examples of active mechanical microvalves include, but not limited to, magnetic valves, electric valves, thermal valves, and piezoelectric valves. Active nonmechanical microvalves include phase change valves, bistable valves, and electrochemical valves, etc. Here we will focus on the introduction to thermomechanical microvalves including both active and passive valves, which use heat to conduct mechanical actions.

Generally, the chemical and physical properties of most engineering materials vary with temperature. The only difference lies in the degree to which the property changes with temperature. Among all the properties, the material shape change with temperature has mostly been used for the development of thermomechanical microvalves. The detailed mechanisms of thermomechanical microvalves will be discussed below. Briefly, the deformation of the material shape causes an actuation force, which can be used to induce mechanical actions through actuators. The thermomechanical microactuator is the major component of a thermomechanical microvalve through which thermal energy is converted into mechanical stress. The induced mechanical stress causes the deformation of the material shape of the actuator to close or open a channel. There are two main mechanisms for a thermomechanical actuator to convert thermal energy into mechanical stress: thermal expansion and the shape memory effect. Thermal expansion means that the size of a piece of material expands when its temperature increases and the shape memory effect describes a phenomenon that a piece of material memorizes its original shape and tends to return to it when heated. To control the switch between open and closed, a heater or a cooler is usually also involved in a thermomechanical microvalve. According to the way that the thermal control affects the shape of the microactuator, thermomechanical microvalves can be roughly divided into three categories: thermal expansion microvalves, bimetallic microvalves, and shape memory alloy (SMA) microvalves.

Basic Methodology

Different thermomechanical microvalves use different mechanisms to control the valve although all of them are based on the deformation of the material due to thermal expansion. For example, a thermal expansion microvalve utilizes the thermal expansion of a single material to open or close the flow, a bimetallic microvalve utilizes the thermal expansion difference between two materials which are bond together to open or close the flow, and a thermally driven SMA microvalve utilizes the shape memory effect (a sample of SMA has the capability to regain its original geometry by itself during heating (one-way effect)) to open or close the flow. The detailed methodologies for each category are summarized below.

Thermal Expansion Microvalves

Thermal Expansion

For most materials, when heated, the average amplitude of the atom's vibration within it increases, which increases the distance between the atoms thus causing the material to expand. Early developed thermomechanical microvalves, including bimetallic microvalves, were primarily based on this principle. In contrast to bimetallic microvalves, only one single-layered beam or membrane is usually involved in a thermal expansion microvalve. Generally, two coefficients are used to depict the thermal expansion in a piece of material: the linear thermal expansion coefficient, α, and the volumetric thermal expansion coefficient, β. These two coefficients relate the change in temperature to the change in the linear and volumetric dimensions of the material, respectively, and are defined as

$$\alpha = \frac{1}{L}\frac{\partial L}{\partial T}\,, \tag{1}$$

$$\beta = \frac{1}{V}\frac{\partial V}{\partial T}\,, \tag{2}$$

where L and V are the length and the volume of the material, respectively, and T is the absolute temperature. For ideal isotropic materials, the linear thermal expansion coefficient is one-third of the volumetric thermal expansion coefficient, i. e., $\alpha = (\beta/3)\,\beta$. For most materials, both coefficients are positive, for example, they expand when heated. Assuming that the linear thermal expansion coefficient is independent of the temperature, the length of the material under zero compressive stress can be simply given as

$$L = L_0\left[1 + \alpha\,(T - T_0)\right], \tag{3}$$

where L_0 is the length of the material at a temperature, T_0.

Beam Buckling

If fixed at its two ends, a straight beam will bend when heated due to thermal expansion. This inflection is usually utilized to design a thermal expansion microvalve actuator and the degree to which the material inflects when heated is key to the valve design. Lin et al. [1] have developed a theoretical model to investigate the buckling under electrothermal buckling conditions. Figure 1a shows a schematic diagram of such a microbeam. The deflection at the center of the beam can be given as

$$h_{\max} = 4\zeta\sqrt{\frac{I}{(\alpha\Delta T - \varepsilon)\,A_c}}\,, \tag{4}$$

where A_c represents the cross-sectional area, I is the inertia moment of the beam, T is the average temperature, ε is the strain of the beam, and ζ is a function of the maximum deflection angle, $\theta_{\max}$, which occurs at one-fourth of the total length, given by

$$\zeta = \sin\frac{\theta_{\max}}{2}\,. \tag{5}$$

There are two important parameters involved in the evaluation of the beam buckling, which are the critical load, P_{cr}, and the critical temperature, T_{cr}. The critical load is the force at which the beam will buckle, given by

$$P_{cr} = \frac{4\pi^2 EI}{L^2}\,, \tag{6}$$

where E is the Young's modulus. If no stress and external pressure differences are loaded on the beam at the temperature, T_0, considering a constant linear thermal expansion coefficient, the theoretical critical temperature for the beam to buckle can be given as

$$T_{cr} = \frac{4\pi^2 I}{\Delta\alpha A_c L^2} + T_0\,, \tag{7}$$

where $\Delta\alpha$ is the difference in the thermal expansion coefficient between the beam and the substrate. Investigations on thermal buckling of eccentric clamped–clamped beams can be found elsewhere [2].

Membrane Buckling

Similar to beam buckling, membrane buckling is another important mechanism for thermal expansion microvalves. To investigate the bending of a membrane when heat is added to it, Fig. 1b illustrates the principle of the thermal buckling of a square membrane. Considering a uniform compression condition cross the membrane (i. e., the compressive stress is constant, $S_x = S_y = S$), the membrane buckles transversally without any additional external load when the compressive stress gradually increases with temperature and exceeds the critical stress, S_{cr}. The critical stress is defined as

$$S_{cr} = 4.38\frac{\delta^2}{l^2}\frac{E}{1-\nu^2}\,, \tag{8}$$

where l and δ are the length (or the width for a square membrane) and the thickness of the membrane, respectively, and ν is Poisson's ratio. After that, a higher temperature will give rise to a larger buckling amplitude. The following equation shows the transversal displacement of the buckled membrane:

$$h(x,y) = \frac{h_{\max}}{4}\left(1 + \cos\frac{2\pi}{l}x\right)\left(1 + \cos\frac{2\pi}{l}y\right), \tag{9}$$

where $h_{\max} = h\,(0,0)$, is the deflection at the center of the membrane. If no initial deflection is loaded and only the



Thermomechanical Valves, Figure 1 (**a**) Schematic diagram of a straight, clamped–clamped beam after buckling; (**b**) illustration of the thermal buckling of a square membrane

first-order buckling of the membrane is considered, $h_{\max}$ can be obtained as

$$h_{\max} = \begin{cases} 0\,, & S \leq S_{\mathrm{cr}} \\ \pm 2.298\delta\sqrt{\dfrac{S}{S_{\mathrm{cr}}} - 1}\,, & S \geq S_{\mathrm{cr}}\,. \end{cases} \tag{10}$$

If no stress and external pressure are loaded on the membrane at the temperature, T_0, considering a constant linear thermal expansion coefficient, the theoretical critical temperature for the membrane to buckle can be given as

$$T_{\mathrm{cr}} = 4.38\frac{\delta^2}{l^2\left(1-\nu^2\right)\Delta\alpha} + T_0\,, \tag{11}$$

where $\Delta\alpha$ is the difference in the thermal expansion coefficient between the membrane and the substrate.

Sealed Capsule Expansion Microvalves

In 1987, Zdeblick and Angell [3] first proposed the concept of the sealed capsule expansion (SCE) valve, which utilized the thermal expansion of a trapped liquid to actuate the valve, instead of the buckling of a beam or membrane. Later, a family of sealed capsule expansion valves trademarked as the *FluistorTM* was developed by Redwood Microsystems. Generally, in a SCE microvalve, there is a small cavity with trapped liquid which has a low boiling point and/or a high expansion coefficient. When the liquid is heated, it expands and closes the valve. When it is cooled, it shrinks and opens the valve.

The cavity can be made of silicon, quartz, or glass substrates or any other appropriate materials. Because of the convenience of silicon micromachining techniques, silicon is commonly used to fabricate the cavity and flexible membrane. Normally a thin-film heating resistor is integrated onto one inner side of the cavity, with a flexible diaphragm wall sealing the opposite inner side of the small cavity. When an electrical current is passed through the resistor, the trapped fluid is heated to evaporate and expand. The expansion causes the flexible wall to flex outward. This outward flex movement is then used to close or open the flow. A SCE microactuator can function as a normally opened microvalve, which opens the channel in its normal de-energized state. At a normal temperature, the flexible wall is in its shrinking stage, which gives a gap between the valve seat and the flexible wall. The valve is in its open stage with the fluid moving through the gap. When the trapped liquid is heated, due to its thermal expansion, the outward-flexing wall comes into contact with the nearby valve seat. Thus the fluid flow is cut off between the input channel and the output channel through the port. A high power can be applied to speed up the closure. Because the cooling is slower than the heating for most thermally driven valves, the following opening is much slower and depends on the thermal conduction and convection in the valves.

Bimetallic Microvalves

Bimetallic Strip

A bimetallic strip was the earliest bimetallic valve structure and was invented by the eighteenth century British clockmaker John Harrison for his third marine timekeeper (H3) to compensate for the error caused by temperature. A bimetallic strip consists of two strips of different metals which have different thermal expansion coefficients. As shown in Fig. 2a, if two strips are bonded together throughout their length, due to the different degrees of thermal expansion between the two metals, the bimetallic strip will bend to the side with a lower thermal expansion coefficient when heated and to the other side when cooled down. The sideways displacement of the bimetallic strip is much larger than the lengthways change in either of the two metal strips. Thus, a temperature change is converted into a sideways mechanical displacement, which can be used to regulate the flow. For two layers of different thickness, as shown in Fig. 2a, the sideways displacement can be given as

$$h = \frac{3L^2\,(\alpha_2 - \alpha_1)\,\Delta T\,(\delta_1 + \delta_2)}{\delta_2^2 K_1}\,, \tag{12}$$

where

$$K_1 = 4 + 6\frac{\delta_1}{\delta_2} + 4\left(\frac{\delta_1}{\delta_2}\right)^2 + \frac{E_1}{E_2}\left(\frac{\delta_1}{\delta_2}\right)^3 + \frac{E_2}{E_1}\frac{\delta_2}{\delta_1}$$

and the subscript, i, represents the ith strip. If the thicknesses of the two layers are equal, i. e., $\delta = \delta_1 = \delta_2$, the sideways displacement can be simplified as

$$h \approx \frac{6L^2\,(\alpha_2 - \alpha_1)\,\Delta T E_1 E_2}{\delta\left(E_1^2 + E_2^2 + 14 E_1 E_2\right)}\,. \tag{13}$$

Neglecting the difference between E_1 and E_2, the displacement can be further simplified as

$$h \approx \frac{3}{8\delta}\,(\alpha_2 - \alpha_1)\,\Delta T L^2\,. \tag{14}$$



Thermomechanical Valves, Figure 2 (**a**) Cross-section of a bimetallic strip; (**b**) schematic of a circular annular bimetallic membrane

Bimetallic Membrane

In addition to bimetallic strips, bimetallic membranes are also commonly used in a microvalve actuator. Figure 2b shows the schematic of a circular annular bimetallic membrane. Similar to a bimetallic strip, a bimetallic membrane consists of two layers of different metal materials which have different thermal expansion coefficients. When heated, due to their different thermal expansions, the center of the membrane bulges vertically to the side with a higher thermal expansion coefficient. As shown in Fig. 2b, for a circular annular bimetallic membrane, if the outer edge is fixed by a wall and the inner edge is guided in the vertical direction by a boss, the displacement at the inner edge can be given as

$$h \approx \frac{3\,(\alpha_2 - \alpha_1)\,\Delta T\,(\delta_1 + \delta_2)\,(1 + \nu_a K_3/K_2)\,a^2 b^2 \ln\frac{a}{b}}{\delta_2^2 K_4\left(a^2 - b^2\right)}\,, \tag{15}$$

where

$$K_2 = 1 + \frac{E_2\delta_2^3\left(1-\nu_1^2\right)}{E_1\delta_1^3\left(1-\nu_2^2\right)} + \frac{3\left(1-\nu_1^2\right)(1+\delta_2/\delta_1)^2(1+E_1\delta_1/E_2\delta_2)}{(1+E_1\delta_1/E_2\delta_2)^2-(\nu_1+\nu_2E_1\delta_1/E_2\delta_2)^2}, \tag{16}$$

$$K_3 = 1 + \frac{\nu_2E_2\delta_2^3\left(1-\nu_1^2\right)}{\nu_1E_1\delta_1^3\left(1-\nu_2^2\right)} + \frac{3\left(1-\nu_1^2\right)(1+\delta_2/\delta_1)^2(1+\nu_2E_1\delta_1/\nu_1E_2\delta_2)}{(1+E_1\delta_1/E_2\delta_2)^2-(\nu_1+\nu_2E_1\delta_1/E_2\delta_2)^2}, \tag{17}$$

$$K_4 = 4 + 6\frac{\delta_1}{\delta_2} + 4\left(\frac{\delta_1}{\delta_2}\right)^2 + \frac{E_1\delta_1^3(1-\nu_2)}{E_2\delta_2^3(1-\nu_1)} + \frac{E_2\delta_2(1-\nu_1)}{E_1\delta_1(1-\nu_2)}, \tag{18}$$

where a and b are the outer and inner radius of the membrane, respectively. Considering $\delta = \delta_1 = \delta_2$, $E_1 = E_2$, and $\nu = \nu_1 = \nu_2$, the displacement can be simplified as follows:

$$h = \frac{3}{8\delta}(\alpha_2-\alpha_1)\Delta T(1+\nu)\frac{a^2b^2}{a^2-b^2}\ln\frac{a}{b}. \tag{19}$$

Further numerical and experimental studies on the thermal behavior of other more complex bimetallic membranes can be found elsewhere [4].

Thermally Driven SMA Microvalves

The SMA, known as the memory metal or smart wire, was first discovered in an Ag – Cd alloy in 1932. Due to a crystalline transformation between a high temperature austenite phase and a low temperature martensite phase, when materials with this shape memory property are subject to deformation, they are able to return to their *memorized* original shape after being heated to a temperature above their transformation temperatures. It was not until the early 1960s that SMAs showed their real importance when the Ni – Ti SMA was discovered by Buehler et al. [5]. Compared with other SMAs, Ni – Ti alloys can give a much larger deformation under the same conditions, have good chemical resistance and biocompatibility, and possess superior mechanical properties such as long fatigue life and relatively high ductility. Because of the large deformation occurring under a temperature variation, a SMA is an ideal material for a microactuator, especially for a microvalve.

Shape Memory Effects

In fact, not only alloys have shape memory properties, some polymers, ceramics and even biological systems also possess such properties. For example, bacteriophages can use the shape memory mechanism to enter into host cells. However, to date, only SMAs are widely used in microvalve fabrication. We will focus on the introduction of SMA microvalves.

Different from most normal materials, besides the shape changes resulted from elastic, plastic or thermal contributions, the SMA has three additional shape changes: a one-way effect shape change, a two-way effect shape change, and a pseudoelasticity shape change [6].

- One-way effect: the effect that the material remembers to return to its original shape when heated, but the material needs external loads to make it deform. This thermally driven deformation cycle is the basis for most SMA microvalves.
- Two-way effect: the effect that the material remembers two different shapes: one at low temperatures, and the other at high temperatures. In this situation, external loads are not necessary (intrinsic two-way effect). Normally, a SMA *remembers* its high-temperature shape and immediately *forgets* the low-temperature shape upon heating to recover the high-temperature shape. However, it can be *trained to remember* to leave some reminders of the deformed low-temperature condition in the high-temperature phase.
- Pseudoelasticity: the effect that the material does not need temperature variation to change its shape. It acts like a spring: expanding when added with a load and receding when released from an external load.

Key Research Findings

There have been too many studies and findings on thermomechanical microvalues to list all of them here. Some key research findings about the above-mentioned three categories of thermomechanical microvalves are briefly discussed here.

Thermal Expansion Microvalves

Thermal Expansion Buckling Microvalves

Figure 3 shows a basic setup of a normally closed thermal expansion microvalve. The main valve components usually include a valve seat, a valve membrane, a thin film polysilicon heater, an upper housing, and a lower housing. Generally, a thin film heater is used to heat the valve membrane. When the membrane is heated, the membrane begins to bulge allowing the flow to pass. A well-designed microvalve can possess a response time of about 10 – 20 ms, which is quite fast for a thermally driven microvalve. Most thermomechanical microvalves are active valves which use external thermal control to change the stage of the valve. A possible passive thermal buckling valve has been proposed [2] as shown in Fig. 4a. In contrast to active valves, passive valves utilize the properties of the fluid itself to control the stage of the valve. As shown in Fig. 4a, a clamped eccentric nickel beam is fabricated over a slot through the substrate. When the temperature is low, the gap between the beam and the seat is small, allowing a small mass of liquid to flow through it. But, if the temperature is high, the beam buckles, allowing a larger flow rate. These eccentric microbeams can potentially be used in the future for thermally adaptive microvalves which can self-regulate the flow. Figure 4b shows possible applications of these thermally adaptive microvalves. It illustrates the schematic of a MEMS skin-cooling scheme which is similar in nature to the biological phenomenon of perspiration. When the temperature increases, the thermally adaptive microvalve can increase the flow of local cooling fluid, hence automatically enhancing the cooling strength. With this adaptive cooling strategy, the temperature of the surface can be well controlled under a spatially and temporally varying heating load.



Thermomechanical Valves, Figure 4 A passive thermal buckling valve. (**a**) Photograph of eccentric micro nickel beams; (**b**) application of the valve in MEMS adaptive cooling scheme for both a single device (upper) and an array of devices (bottom)



Thermomechanical Valves, Figure 3 A typical normally closed thermal expansion microvalve

SCE Microvalves

Figure 5a shows a schematic of a normally closed SCE microvalve which has been commercialized as the FluistorTM Microvalve of NC-105 by Redwood Microsystems. Different from the normally opened SCE microvalve, this microvalve has a fulcrum point on the flexible diaphragm. In its de-energized state, the body of the actuator falls down on the off-center orifice on the right and closes the flow. When heated, the trapped fluid expands to cause the flexible diaphragm to lever the body of the actuator away from the orifice and allow the flow to pass through. The Fluistor TM NC-105 has been reported to have a leak


Trapped fluid
Glass
Silicon
Glass
Closed (cold)
Flow
a
Open (hot)
CS2591 10-97
b

Thermomechanical Valves, Figure 5 (**a**) Schematic of normally closed sealed capsule microvalve action; (**b**) Fluistor™ NC-1500-T by Redwood Microsystem


Circular Reservoir
Gap Height
Outlet Hole
Valve Seat
Channel
Reservoir
Heater
Paraffin Actuator
Substrate
Inlet Hole
a
Circular Reservoir
Parylene-C Channel
Outlet Hole
Paraffin Actuator
200 um
b
Channel
Cr/Au Heater
Paraffin Actuator
Electrode
Circular Reservoir
c

Thermomechanical Valves, Figure 6 A paraffin actuated microvalve described in the text. (**a**) Schematic of the cross-section of the microvalve; (**b**) microscope photograph of the microvalve from the top; (**c**) microscope photograph of the microvalve from the bottom

rate of no less than 0.006 ml/min of helium, which is acceptable in many applications. This valve cannot be used to control corrosive fluids, because it uses the flexible diaphragm to directly seal the valve and a very limited range of materials can be used to fabricate the diaphragm. This has since been improved by avoiding the use of the flexible membrane to directly seal the device. Figure 5b shows a typical Redwood Microsystems NC-1500-T normally closed valve, which works at an ambient temperature range of 0 – 55 °C and opens the flow at approximately 56 °C.

Besides the thermal expansion of the fluid and the volumetric expansion of the liquid–gas phase change, the expansion of the solid–liquid phase change can also be used in a SCE valve to actuate the action. Figure 6 shows the microvalve that Carlen and Mastrangelo proposed in 1999 [7]. This SCE microvalve is a normally opened SCE microvalve in which it uses the expansion of the solid–liquid phase change of the paraffin to actuate the switch. Figure 6a shows the schematic cross-section of the microvalve. Because paraffin has a large volumetric expansion upon melting, paraffin melts and expands 10 – 30 % when heated to 65 – 150 °C, and thus causes the flexible membrane to deflect vertically about 3 μm in 20 ms with a power requirement of less than 50 mW. The outward-flexing membrane will then come into good con-



Thermomechanical Valves, Figure 7 Schematic of a normally closed thermal bimorph-actuated valve



Thermomechanical Valves, Figure 8 Schematic of a bimetallically actuated three-way valve

tact with the outlet hole above and cut off the flow. Figures 6b and 6c show, respectively, the top and bottom view of the SCE microvalve.

Bimetallic Microvalves

Classical Bimetallic Microvalves

In 1991, Jerman proposed a new microactuator based on a bimetallic membrane [8], which was later used to fabricate a normally opened microvalve and a normally closed microvalve. As shown in Fig. 7, a circular annular Al – Si bimetallic membrane with a central boss is used in the microvalve. The bimetallic diaphragm consists of a 5 μm-thick diaphragm of aluminum and a lower 8 μm-thick silicon diaphragm with embedded diffused resistors. In its de-energized state, the central boss seals the valve seat (400 μm × 80 μm) and thus closes the flow. When energized, the resistors heat the Al – Si bimetallic diaphragm making the central boss move up, thus allowing the flow. The displacement of the boss can be changed by altering the electrical power and the temperature of the diaphragm, which can be used to control the flow rate of the valve. The leakage rate of this valve is approximately 0.03 ml/min of nitrogen at a 34.5 kPa input pressure. This microvalve works well under the temperature range of −20 to +85 °C. The response time is about 150 ms, which is quite rapid for a thermally driven microvalve.

Figure 8 shows a similar bimetallic microvalve which was fabricated by Messner et al. [9]. In contrast to the microvalve shown in Fig. 7, it has another port (port 2) which is always open at the edge of the membrane. When the microvalve is de-energized, the center boss seals port 1 thus letting port 2 connect with port 3. When the boss is lifted by the thermally driven metallic membrane, port 1



Thermomechanical Valves, Figure 9 A four-leg bimetallic membrane microvalve



Thermomechanical Valves, Figure 10 A $Si-Ni$ bimorph actuated microvalve with thermal isolation comb regions. (**a**) Thermal isolation comb regions; (**b**) photograph of the microvalve

is released and port 3 is sealed. Port 2 is connected with port 1. This 3-way microvalve is designed to control a differential pressure of 1000 kPa allowing a maximum flow rate of 800 ml/min for dry air at 600 kPa. The electrical power is about 1 W. It works properly in an ambient temperature range of 0 – 50 °C.

Power-Saving Bimetallic Microvalves

To minimize the thermal conduction loss from the membrane, Wang et al. [10] have proposed a new microvalve using a four-leg bimetallic *membrane*. Figure 9 shows their microvalve. In contrast to other bimetallic membrane microvalves, this microvalve has a four-leg $Ni-Si$ bimetallic membrane at the center instead of an annular one. With less conjunction to the substrate this tapered-leg membrane largely decreases the thermal conduction loss, and thus significantly saves on the power required to actuate the valve. It has been reported that the power requirement of this design is 5.3 times less than that of the older design.

Tomonari et al. [11] have used thermal isolation comb regions to minimize the thermal conduction loss from the membrane in their microvalve. As shown in Fig. 10a, they used a $Si-Ni$ bimorph as the microactuator. They fabricated thermal isolation comb regions on either side of the silicon bimorph by etching Si and filling the structure with polyimide resin. Because of the low heat conductivity of the polyimide resin, this structure can effectively protect from heat loss. Figure 10b shows their microvalve.

Other Attempts to Switch the Flow Using Bimetallic Structures

Many other attempts to switch the flow using bimetallic structures have been made. Walters et al. [12]. introduced gate microvalves (cross-flow microvalve or X-microvalve) in 1998. In a gate microvalve, the valve gate moves perpendicular to the flow and static pneumatic force. Figure 11 shows the bimorph-actuated gate microvalves reported by Haasl et al. [13]. The shortcoming of these microvalves is that leakage is unavoidable in the closed state because the limited actuation energy in microsystems does not allow friction between sliding structures.

In 1992, Doring proposed using the bimetallic microcantilever structure to direct a fluid jet. Later, on the basis of this idea, Trah et al. [14] fabricated a micromachined normally closed valve using an $Al-Si$ cantilever, as shown in Fig. 12. When the cantilever is in its de-energized state, the cantilever is slightly bent upwards and directs the fluid to the room above the membrane. Thus, the pressure in the upper room is a little larger than that in the lower room. The pressure difference presses the boss down to the valve seat and seals the valve. When the cantilever is heated and thus bends downwards, the fluid jet also deflects downwards and flows into the lower room to lift up the boss. Thus, the valve opens. The size of the valve is 14.5 mm × 8.5 mm × 1.43 mm. The valve was designed to control a flow rate of 75 ml/min at time constants of about 0.5 ms.

Thermally Driven SMA Microvalves

Microvalves Using Sputtered SMA Thin Films or Rolled Sheets

Thin films and rolled sheets are the most widely used format in microvalve fabrication. Usually a SMA microvalve consists of an upper and a lower housing integrated with a valve seat and fluidic connections, a membrane, a spacer, and a SMA microactuator. The deformation actuated by the SMA thin film pushes or pulls the spacer to seal or open the valve seat, thus to close or allow the liquid to flow through the valve seat.


Gate
z
y
x
Bimorph actuator
Orifice channel
Bimorph actuator
Gate
z
y
x
Air flow
Orifice channel
Air flow
Orifice channel
Bimorph
z
y
x
y
x
Top view
w_{Act}
w_{Gt}
l_{Act}
t_{ChW}
w_{Ch}
l_{Act}
w_{Act}
t_{Gt}
l_{Lk}
l_{Ch}
t_{ChW}
w_{Ch}
$w_{Act}/2$
w_{Gt}
w_{Ch}
t_{ChW}
l_{Ch}
l_{Act}
closed
z
x
Side view
open
h_{Act}
h_{Gt}
l_{Lk}
h_{Ch}
t_{Gt}
l_{Ch}
h_{Act}
h_{Ch}
h_{Gt}
w_{Gt}
h_{Act}
h_{Gt}
h_{Ch}
l_{Lk}
t_{Gt}
Air flow
Bimorph actuator
Gate
Orifice channel
Air flow
Air flow
Bimorph actuator
Orifice channel
Air flow
Bimorph actuator
Orifice channel
Gate
flow

Thermomechanical Valves, Figure 11 Bimetallically actuated gate microvalves

The method of using SMA films to fabricate microvalves can be traced back to Busch and Johnson [15] who successfully fabricated a $Ni-Ti$ film using sputter deposition and crystallization processing techniques and also suggested some microvalve and micromirror structures. Because a $Ni-Ti$ thin film can generate 10 J per cubic centimeter per cycle, it can be used as a heating resistor, which can largely simplify the structure because it avoids the use of additional heaters. They later developed a normally closed SMA microvalve where a $Be-Cu$ spring was used to push a sapphire ball against the silicon over the spacer to close the flow orifice in a de-energized state, as shown in Fig. 13. A thin $Ni-Ti$ SMA film is deposited onto a silicon substrate and is cut into the shape of microribbon by using the photolithography and selective etching techniques. When heated, the $Ni-Ti$ microribbons return to the original undeflected state to move the silicon back from the orifice and thus open the microvalve.

There have been further developments in microvalves using sputtered SMA thin films. The major research efforts have been concentrated on the optimization of the SMA film shape through the simulation of the stress distribution in the film. Figure 14 shows a stress-optimized SMA microdevice designed by Skrobanek et al. [16]. The goal of this practice is to ensure that the stress values in the thin film should be sufficiently high to provide large work outputs, and low enough to avoid fatigue effects. Ikuta et al. [17] have fabricated fluid-driven chips containing multiple pumps and switching valves for the biochemical IC family. The switching valve that they fabricated was driven by a SMA film. Figure 15 shows the operating principle of their switching valve. In contrast to normal valves, this valve has two outlets instead of one. Due



Thermomechanical Valves, Figure 12 Schematic and principle of a hydraulic actuated microvalve



Thermomechanical Valves, Figure 13 SMA microvalve

to the lever action of the silicon rubber, when the SMA actuator pushes the spacer down to seal the right outlet 2, it opens the left outlet 1 automatically. The switching time in the active (heating) phase is 0.5 s and the response time of the opposite way in the passive (cooling) phase is about 2 s. Different Ni – Ti – x alloys were also tried to fabricate such microvalves. The use of Ni – Ti – Pd alloys provides a higher ambient temperature application, and Ni – Ti – Cu alloys provide a higher recoverable stress as compared to Ni – Ti alloys.

Microvalves Using SMA Wires

Micropinch Valves Using SMA Wires SMA wire is commonly used in micropinch valves. A micropinch valve usually consists of a soft tube and a SMA wire. The SMA wire pinches the tube to close the flow and releases it to open the flow. The first pinch valve using a SMA wire was used in an implantable drug delivery system [18]. A 120 μm-diameter Ni – Ti wire was used to pinch down a silicone rubber tube with an inner diameter of 0.6 mm and an outer diameter of 1 mm. This value is operated with a pressure difference of 200 kPa and can open in less than 1 s with a power consumption of 120 mW.



Thermomechanical Valves, Figure 14 Stress-optimized microdevice

Later, more normally closed pinch valves were developed. Figure 16 shows another normally closed pinch valve developed by Pemble and Towe [19]. The valve consists of an actuator and silicon tubing. The actuator consists of a 152 μm-diameter Ni – Ti contraction wire in tension with a 584 μm-diameter Ni – Ti superelastic wire. One end of the actuator is fixed to a flat surface using epoxy. In the de-energized state, the actuator tightens the tube and makes it deform to block the flow. When the contraction wire is electrified, Joule heating causes the superelastic cantilever to bend upward. This upward deflection relieves pinch pressure on the tubing thereby allowing the flow. In this pinch valve, the outer diameter of the silicone tubing is 1.2 mm and the inner diameter is 0.64 mm. It operates with a pressure difference of 20.7 kPa and a flowrate of up to 48 ml/min at a current of 420 mA. The valve can be opened in less than 1 s and then closed in less than 2.5 s. The calculated power dissipation has been reported to be 398 mW.

Figure 17 shows a relatively economical micropinch valve fabricated by Piccini and Towe [20]. The system consists of a microbore silicone tube, a Ni – Ti SMA wire, a miniaturized synthetic ruby ball and a thermocouple. All of the components are off-the-shelf components. As shown in Fig. 17, the ruby ball blocks the tubing in a nor-



Thermomechanical Valves, Figure 15 Schematic of a SMA switching valve



Thermomechanical Valves, Figure 16 SMA pinch valve. (**a**) Schematic of the valve; (**b**) photograph of the valve

mal state. When electrified, due to Joule heating, the SMA wire stretches the microbore silicone tubing away from the ruby ball and the gap between them allows the flow. This microvalve has been reported to have a response time of 2.5 s with a power pulse of 213 mW.

Other Microvalves Using SMA Wires Figure 18 shows another type of gate microvalve using SMA wires [21]. A paddle suspended from a silicon beam is placed on the valve seat. In its de-energized state, the hole in the paddle fits in with the valve seat and allows the flow. When electrified, the SMA wire is heated by Joule heating and bends to push the paddle aside from the valve seat and closes the inlet opening. When the SMA wire cools down, the paddle is pushed back by the silicon beam to allow the flow again.

Future Directions for Research

Various thermomechanical microvalves have been developed with the development of MEMS fabrication technology. Thermomechanical microvalves work by converting thermal energy into mechanical deformation. Compared with other microvalves, such as magnetic microvalves, electrostatic microvalves, and piezoelectric microvalves, thermally driven microvalves have their own advantages such as simplicity of fabrication, controllable deflection (by adjusting the input power), and a relatively large actuation force.

However, thermally driven microvalves also have their drawbacks. First, they have a relatively long response time. Second, because heat dissipation is unavoidable, more attention must be paid when designing a microvalve. In most circumstances, heat dissipation in a thermally driven microvalve is a trade-off. For example, a small heat dissipation helps to obtain a high heating rate to open the valve; while at the same time it also means a low cooling rate to close it. Third, the performance of a thermally driven microvalve is largely affected by the ambient temperature. A thermally driven microvalve usually works within a relatively small temperature range. Fourth, compared to the heating process, the cooling process is relatively difficult to achieve. The cooling process is always the bottleneck in reducing the response time of a thermally driven microvalve. Generally speaking, the response time of a thermally driven microvalve is of the order of a second. Fifth, sometimes due to the large power consumption, a thermally driven microvalve is not appropriate when the energy consumption is limited. Sixth, thermal expansion may cause loosening to the support which may introduce some leakage problems. Seventh, the closing time may not be the same as the opening time. Finally, heating of the fluid may not be appropriate in some MEMS applications because it may introduce some local boiling on the electrode.



Thermomechanical Valves, Figure 17 SMA pinch microvalve in: (**a**) de-energized close state; (**b**) actuated open state



Thermomechanical Valves, Figure 18 A gate microvalve acuated by a SMA wire at (**a**) open position; (**b**) closed position

Overcoming the shortcomings of the thermomechanical microvalves listed above will be the main tasks for future studies in this area. The development of new materials and exploring new methods to make thermomechanical microvalves will also be promising directions.

Cross References

- ► Thermal Expansion

References

1. Lin L, Chiao C, Luo JJ, Sun TP (1996) Electro, thermal and elastic characterizations of suspended micro beams. The Second International Workshop on Thermal Investigations of ICs and Microstructures, Budapest, pp 219–223
2. McCarthy M, Tiliakos N, Modi V, Frechette LG (2007) Thermal buckling of eccentric microfabricated nickel beams as temperature regulated nonlinear actuators for flow control. Sens Actuators A 34(1):37–46
3. Zdeblick MJ, Angell JB (1987) A microminiature electro-fluidic valve. Proceeedings of the 4th International Conference on Solid-state Sensors and Actuators, pp 827–829
4. Hsu CP, Hsu WY (2000) A two-way membrane-type micro-actuator with continuous deflections. J Micromech Microeng 10:387–394
5. Buehler WJ, Gilfrich JV, Wiley RC (1963) Effect of low temperature phase changes on the mechanical properties of alloy near composition Ti – Ni. J Appl Phys 34:1475
6. Kohl M (2004) Shape Memory Microactuators. Springer, Heidelberg
7. Carlen ET, Mastrangelo CH (2000) Paraffin actuated surface micromachined valves, Micro Electro Mechanical Systems, 2000, MEMS 2000, the Thirteenth Annual International Conference, pp 381–385
8. Jerman JH (1991) Semiconductor microactuator. US Patent 5,069,419, Dec 1991
9. Messner S, Muller M, Burger V, Schaible J, Sandmaier H, Zengerle R (1998) Micro Electro Mechanical Systems, MEMS 98, Proc Eleventh Annual International Workshop, pp 25–29
10. Wang TK, Barth P, Alley R, Baker J, Yates D, Field L, Gordon G, Beatty C, Tully L (1999) Production-ready silicon microvalve. Proc SPIE 3876, pp 227–237
11. Tomonari S, Yoshida H, Kamakura M, Yoshida K, Kawahito K, Saitoh M, Kawada H, Juodkazis S, Misawa H (2003) Efficient microvalve driven by a Si – Ni bimorph. Jpn Soc Appl Phys 42:4593–4597
12. Walters M, Dhuler V, Mahadevan R, Cowen A, Wood R, Hill E, Kao I (1998) A silicon micromachined gate valve. Presented at the 1998 Solid-state Sensors and Actuators Symposium
13. Haasl S, Braun S, Ridgeway AS, Sadoon S (2006) Out-of-plane knife-gate microvalves for controlling large gas flows. J Microelectromec Syst 15:1281–1288
14. Trah HP, Baumann H, Doring C, Goebel H, Grauer T, Mettner M (1993) Micromachined valve with hydraulically actuated membrane subsequent to a thermoelectrically controlled bimorph cantilever. Sens Actuators A 39:169–176
15. Busch JD, Johnson AD (1990) Shape-memory properties in Ni – Ti sputter deposited film. J Appl Phys 68:6224–6228
16. Skrobanek KD, Kohl M, Miyazaki S (1997) Stress-optimised shape memory devices for use in microvalves. J Phys IV 7:597–602
17. Ikuta K, Hasegawa T, Adachi T, Maruo S (2000) Fluid drive chips containing multiple pumps and switching valves for Biochemical IC Family. Proceedings of the IEEE Thirteenth Annual International Conference on Micro Electro Mechanical Systems, pp 739–744
18. Reynaerts D, Peirs J, Brussel H (1997) An implantable drug-delivery system based on shape memory alloy micro-actuation. Sens Actuators A 61:455–462
19. Pemble CM, Towe BC (1999) A miniature shape memory alloy pinch valve. Sens Actuators 77:145–148
20. Piccini ME, Towe BC (2006) A shape memory alloy microvalve with flow sensing. Sens Actuators A 128:344–349

21. Buttgenbach S, Butefisch S, Leester-Schadel M, Wogersien A (2001) Shape memory microactuators. Microsyst Techn 7:165–170

Thermometry

► Temperature Measurement, Methods

Thermophoresis

PETER GEELHOED[1], JERRY WESTERWEEL[1],
SIGNE KJELSTRUP[2], DICK BEDEAUX[2]
[1] Laboratory for Aero- & Hydrodynamics,
Delft University of Technology, Delft, Netherlands
[2] Department of Chemistry, Norwegian University of
Science and Technology, Trondheim, Norway
p.f.geelhoed@tudelft.nl, j.westerweel@tudelft.nl

Synonyms

Thermodiffusion; Thermal diffusion; Soret effect; Ludwig–Soret effect

Definitions

Thermophoresis is defined as the migration of a colloidal particle or large molecule in a solution in response to a macroscopic temperature gradient. The inverse effect, i. e., the formation of a temperature gradient as the result of the mixing of different molecular species, is referred to as the *Dufour effect*. The ►Soret coefficient is defined as the ratio of the thermal diffusion coefficient and the normal diffusion coefficient; it is a measure for the degree of separation of the species. These concepts are the same as for a molecular mixture.

Physical Principles

A colloidal particle or large molecule can be driven to move in a gas or a liquid by the application of a non-uniform temperature field. The mass flow rate $\boldsymbol{J}_\mathrm{m}$ of a species or of colloidal particles as the result of a thermal gradient ∇T in a fluid is given in, e. g. [1]:

$$\boldsymbol{J}_\mathrm{m} = -\rho D \nabla c - \rho D_\mathrm{T} c(1-c)\nabla T\,, \tag{1}$$

where ρ is the fluid density, D the diffusion coefficient, D_T the thermal diffusion coefficient, and c the species or particle concentration in terms of mass fraction. The first term on the right hand side is the Fick diffusion law, while the second term describes the migration due to the thermal gradient.

In a stationary state the mass flux vanishes (i. e., $\boldsymbol{J}_\mathrm{m} = 0$), and the Soret coefficient $\mathrm{S_T}$ is given by [5]:

$$S_\mathrm{T} \equiv \frac{D_\mathrm{T}}{D} = -\frac{1}{c\,(1-c)}\frac{\nabla c}{\nabla T}\,. \tag{2}$$

Hence, the effectiveness of the separation is given by the Soret coefficient, while the rate of separation is determined by the diffusivity. In general the thermal diffusion coefficient D_T is a function of temperature and concentration, which complicates the description of thermophoresis.

Thermophoresis as defined above occurs in liquids. For molecular mixtures of gases there is a sound theoretical description [5], but a theory has not been formulated satisfactorily for liquids.

Key Research Findings

For gases thermophoresis can be described using Chapman–Enskog theory [5], assuming a Maxwell–Boltzmann distribution for the velocity of the molecules, with corrections. This approach is only valid when the relative temperature change over the molecular free path is small. Using Onsager's theorem the transport equation can be derived from the entropy production, which is described by De Groot [5].

For liquids there does not yet exist a satisfactory theoretical description, despite more than 150 years of research since the first description of thermophoresis by Ludwig [6] and Soret [7]. Theoretical descriptions fail to predict correct values of the Soret coefficient, and sometimes even fail to predict the correct sign. Hence, thermophoresis remains an area of active research, both on a theoretical and practical level. Below follows an overview of approaches applicable to large molecules or colloidal particles in suspension.

Thermophoresis of a Particle with a Thin Diffusive Layer

Ruckenstein [8] proposed that thermophoresis, diffusiophoresis and electrophoresis can be described as the result of a variation of the surface tension (due to a variation in the surface potential; see Fig. 1), so that the motion of a particle is analogous to the Marangoni effect, i. e.:

$$U_\mathrm{T} = -\frac{\varepsilon\varsigma^2}{32\pi\eta}\frac{\mathrm{d}\ln T}{\mathrm{d}z} \equiv -\frac{\ell}{\eta}\frac{\mathrm{d}\gamma}{\mathrm{d}T}\frac{\mathrm{d}T}{\mathrm{d}z}\,, \tag{3}$$

where $\ell = \chi^{-1}$ is the Debye length (i. e., the thickness of the diffusive layer), η the dynamic viscosity of the fluid, ς the surface potential, and $\gamma = \gamma_0 - \frac{1}{8\pi}\varepsilon\chi\varsigma^2$ is the interfacial tension (where the second term on the right is related to the total free energy of formation of the diffusive layer) [8].

Thermophoresis, Table 1 Diffusivity and Soret coefficients for different binary liquid mixtures

species	solvent	D [$\times 10^{-12}$ m^2/s]	S_T [K^{-1}]	Ref.
ethanol	water	1280	0.0056	[1]
DNA(27 bp)	water	36	0.013	[2]
DNA (5.6 kbp)	water	3.4	0.14	[2]
30 nm latex particles	water	15	$\sim$2	[3]
490 nm polystyrene particle	water	0.9	$\sim$0.5	[4]



Thermophoresis, Figure 1 The thermophoretic motion of a small particle in a temperature gradient as the result of interfacial tension due to the diffusive layer around the particle; see Ruckenstein [8]

Hydrodynamic Models

Brenner [9] proposes a different description of fluid dynamics. He proposes that $\nabla \boldsymbol{v}$ in Newton's rheological law should not be based on the mass based velocity of the fluid, but on its 'volume velocity.' This is a controversial idea. The adapted Navier–Stokes equations provide a hydrodynamic description of thermophoresis and thermal creep. Bedeaux et al. [13] describe how this alternative approach of the transport equations can be validated experimentally by means of thermophoresis.

It would go too far to derive the complete set of equations here so we suffice with the thermophoretic velocity given by Brenner [9]. The thermophoretic velocity U of a sphere is:

$$U = -\frac{\alpha\beta}{1 + k_p/2k} \nabla T \,, \tag{4}$$

where α is the thermal diffusivity, β the thermal expansion, and k and k_p the thermal conductivity of the solvent and particle respectively.

Solvent Particle Interactions

The entropy of particle solvent interactions plays an important role in thermophoresis. The description by [5] of thermophoresis in gases is based on entropy. In complex fluids the entropy of the interaction between molecules or particles and solvent leads to thermophoretic motion. Schimpf & Semenov [10] consider the slip flow caused by a local pressure gradient set up by the temperature dependent properties of the particle and solvent. They find the same thermal expansion proportionality factor as Brenner [9] who does not consider these interactions.

Change of Sign of Soret Coefficient

The Soret coefficient is not a constant; it may vary due to changes in concentration or temperature. A positive Soret coefficient means a thermophobic particle. The Soret coefficient can change sign as a function of concentration [1] or temperature [3] (see Fig. 2). The inversion temperature for latex particles, which only have electrostatic interactions with water, lies close to the maximum density of the solvent at 4 °C. Iacopini et al. [3] conclude based on empirical findings that the thermal expansivity is the major factor in thermophoresis. They claim that this effect can be added to the Soret coefficient caused by the entropy production of particle solvent interactions. The similarity between the results of Brenner [9] and Schimpf & Semenov [10] suggests that this may be valid. For molecular mixtures, Haase [14], Kempers [15] and Rousseau et al. [16], have given important contributions.



Thermophoresis, Figure 2 Inversion of the Soret coefficient. Left: Soret coefficient measurement of water ethanol mixtures, compiled from results obtained by different groups, which shows an inversion of the Soret coefficient for increasing ethanol weight fraction (from Wiegand [1]). Right: Soret coefficient measurement of latex particles (circles) and pMD31 DNA (squares), which shows an inversion of the Soret coefficient with decreasing temperature (from Iacopini et al. [3])



Thermophoresis, Figure 3 Thermophoresis of particles in a microchannel. The top wall has a higher temperature and repulses the particles for thermophobic particles (i. e., a positive Soret coefficient). An exponential concentration profile is established at the channel outlet

Examples of Application

Thermophoresis is applied in industry for the separation of (large) molecules or small particles from their solvent in so-called *thermal field flow fractioning* (TFFF) [11]. A down-scaled version of this process to microscopic scales demonstrated thermophoretic separation on microscopic scales [4, 12]. The advantage of using the very small confinement in a microfluidic device is that the separation times can be reduced, so that thermophoretic separation can be used. Braun & Libchaber [2] use a combination of thermophoresis and convection to concentrate DNA samples. The disadvantage of this approach is that it is a batch process.

As an example we estimate the timescales required to continuously separate a species in a microchannel (see Fig. 3). Consider a two-dimensional channel, e. g., a fluid between two parallel plates separated by a distance h. For low concentrations (i. e., $c \ll 1$) one finds the following stationary solution (i. e., $\boldsymbol{J}_\mathrm{m} = 0$) for the concentration:

$$c = c_0 \exp\big[- S_\mathrm{T}(T - T_0)\big] \tag{5}$$

where c_0 and T_0 are a reference concentration and temperature respectively. The effectiveness of the separation is essentially given by the Soret coefficient. The time scale τ to reach the steady state is given by:

$$\tau = \frac{h^2}{\pi^2 D} \,. \tag{6}$$

For a colloidal particle with a diameter d that is suspended in a fluid with a dynamic viscosity η, the diffusion constant is given by:

$$D = \frac{kT}{3\pi \eta d} \,, \tag{7}$$

where k is the Boltzmann constant ($k = 1.38 \times 10^{-23}$ J/K). A typical particle diffusion coefficient is $D \sim 0.9 \times 10^{-12}$ m^2/s (e. g., $T \sim 300$ K, $\eta \sim 10^{-3}$Pa s, $d \sim 490$ nm). For a micro-channel (with a typical channel width of $h \sim 10 - 100$ µm) the time scale τ is typically of the order of $10 - 10^3$ seconds. This means that one has to use long microchannels in combination with low flow rates to establish a high separation ratio.

Another advantage of implementing thermophoretic separation at a microscopic scale is that one can reach very large temperature gradients without applying large temperature differences. For example, a 5 K temperature difference over a 50 µm channel implies a temperature gradient of $\sim 10^5\,\mathrm{K/m}$, while the absolute variation of temperature is limited. This is beneficial in the case of biological samples (cells, proteins, DNA) where large variations in temperature can disintegrate the samples. However, the difficulty lies in establishing and maintaining a temperature difference in a microfluidic device, which is complicated by the high conductivity and small dimensions at small scales. A design of a microfluidic device for thermophoretic separation is given by Geelhoed et al. [4].

Cross References

- ► Diffusiophoresis
- ► Electrophoresis

References

1. Wiegand S (2004) Thermal diffusion in liquid mixtures and polymer solutions. J Phys Condens Mat 16:357–379
2. Braun D, Libchaber A (2002) Trapping of DNA by thermophoretic depletion and convection. Phys Rev Lett 89:188103
3. Iacopini S, Rusconi R, Piazza R (2006) The macromolecular tourist. Eur Phys J E 19:59–67
4. Geelhoed PF, Lindken R, Westerweel J (2006) Thermophoretic separation in microfluidics. Chem Eng Res Des 84:370–373
5. de Groot SR (1951) Thermodynamics of Irreversible Processes. NHCP, Amsterdam
6. Ludwig C (1856) Sitz. ber. Akad. Wiss. Wien. Math-Nat wiss Kl 20:539 (cited in Wiegand [1])
7. Soret C Arch (1879) Geneve 3. 48 (cited in Wiegand [1])
8. Ruckenstein E (1981) Can phoretic motions be treated as interfacial tension gradient driven phenomena? J Colloid Interf Sci 83:77–81
9. Brenner H (2005) Navier-Stokes revisited. Physica A 349:60–132
10. Semenov S, Schimpf M (2004) Thermophoresis of dissolved molecules and polymers: Consideration of the temperature-induced macroscopic pressure gradient. Phys Rev E 69:011201
11. Kowalkowski T, Buszewski B, Cantado C, Dondi F (2006) Field-flow fractionation: theory, techniques, applications and the challenges. Cr Rev Anal Chem 36:129–135
12. Edwards TL, Gale BK, Frazier AB (2002) A microfabricated thermal field-flow fractionation system. Anal Chem 74:1211–1216
13. Bedeaux D, Kjelstrup S, Öttinger HC (2006) On a possible difference between the barycentric velocity and the velocity that gives translational momentum in fluids. Physica A 371:177–187
14. Haase R (1990) Thermodynamics of Irreversible Processes. Dover, London
15. Kempers LJTM (2001) A comprehensive thermodynamic theory of the Soret effect in a multicomponent gas, liquid or solid. J Chem Phys 115:6330–6341
16. Rousseau B, Nieto-Draghi C, Bonet Avalos J (2004) The role of the molecular association in the change of the sign of the Soret coefficient in aqueous mixtures Europhy. Lett 67:976–982

Thermopneumatic Membrane Valve

► Thermopneumatic Valve

Thermopneumatic Valve

EUI-HYEOK YANG
Department of Mechanical Engineering, Stevens Institute of Technology, Hoboken, NJ, USA
eyang@stevens.edu

Synonyms

Thermopneumatic membrane valve

Definition

A thermopneumatic valve is a type of micromachined active valve operated by the volumetric thermal expansion of a heated gas or heated liquid in a sealed chamber [1].

Overview

The rapid development of new methods of fabrication and microfluidic components enables the desired control and manipulation of small amounts of fluids. The microvalves in microelectromechanical systems (MEMS) are essential elements of a micro total analysis system. Typically, there are two types of microvalve: one is the passive valve the operation of which is dependent upon its surrounding pressure conditions; the other is the active valve, which can be controlled actively. Active valves are categorized in three major ways: initial working state, control pattern, and actuation principle. Each microvalve has advantages and disadvantages from the viewpoint of power consumption, integration method, response time, operation frequency and voltage, fabrication process, and actuation efficiency. Among the various types of microvalves, thermopneumatic actuation provides a large achievable volume stroke and simple fabrication process relative to other actuation methods for microvalves [1].

A thermopneumatic valve typically consists of a moveable valve diaphragm, a valve seat, and a resistive heater in a sealed cavity. While electrical power is applied to the resistive heater, the initial volume of gas in the sealed chamber expands. Using the volumetric change of the heated gas in the cavity, the diaphragm structure is deformed and subsequently blocks the fluidic path. Heated effluents (in liquid form) can also be used for thermopneumatic actuation using the phase transition to gas [2, 3]. A thermopneumatic microvalve can be fabricated with rigid materials such as silicon, metal, and glass. The silicon-based valve devices often face issues such as reliability (cycles or time to failure), wear/tear, residual stress, and high production cost. The residual stress is one of the major issues in MEMS devices. As shown in Fig. 1 [4], a corrugated structure can be used for minimizing the process-dependent residual stress of boron-doped silicon film [5]. Its effectiveness is verified experimentally through comparison between the static deflection characteristics of flat and corrugated diaphragms (Fig. 2) [4]. The development of the soft-lithography process [6, 7] allows the rapid prototyping of microfluidics devices. Elastomers possess outstanding mechanical and optical properties, which can provide effective solutions to overcome the limitations of silicon-based microvalves. By choosing elastomers as valve materials, several issues such as valve efficiency, capacity, power consumption, response time, leakage, closing force, biocompatibility, and biochemical compatibility can be addressed. These can also allow the large-format integration of thermopneumatic microvalves with a thin PDMS membrane [8]. For more reliable operation of thermopneumatic microvalves, Parylene C (i. e. gas-impermeable layer) can be deposited on PDMS (i. e. non-porous rubbery elastomer with high gas permeability).



Thermopneumatic Valve, Figure 1 Thermopneumatic actuator consisting of a corrugated p+ silicon diaphragm as the residual stress relaxation structure and a microheater for thermopneumatic actuation [4]



Thermopneumatic Valve, Figure 2 Time response of the static deflection of thermopneumatic actuators with a corrugated and a flat diaphragm [4]

Cross References

- ► Thermopneumatic Pump

References

1. Oh KW, Ahn CH (2006) A review of microvalves. J Micromech Microeng 16:R13–R39
2. Yang X, Grosjean C, Tai YC, Ho CM (1998) A MEMS Thermopneumatic Silicone Rubber Membrane Valve. Sens Actuators A 64:101–105
3. Sim WY, Yoon HJ, Jeong OC, Yang SS (2003) A phase-change Type Micropump with Aluminum Flap Valves. J Micromech Microeng 13(2):286–294
4. Jeong OC, Yang SS (2000) Fabrication of a Thermopneumatic Microactuator with a Corrugated p+ Silicon Diaphragm, Sens Actuators A 80(1):62–67
5. Yang EH, Yang SS, Yoo SH (1995) A Technique for Quantitative Determination of the Profile of the Residual Stress along the Depth of *p*+ Silicon Films, Appl Phys Lett 67(7):912–914
6. Unger MA, Chou H, Thorsen T, Scherer A, Quake SR (2000) Monolithic Microfabricated Valves and Pumps by Multilayer Soft Lithography. Science 288:113–116
7. McDonald JC, Whitesides GM (2002) Poly(dimethylsiloxane) as a Material for Fabricating Microfluidic Devices. Acc Chem Res 35(7):491–499
8. Baechi D, Buser R, Dual J (2002) A High Density Microchannel Network with Integrated Valves and Photodiodes. Sens Actuators A 95:77–83

Thermoresistive Flow Sensors

JING LIU
Cryogenic Lab, Technical Institute of Physics
and Chemistry, Chinese Academy of Sciences,
Beijing, China
jliu@cl.cryo.ac.cn

Synonyms

Hot wire; Hot film

Definition

A *thermoresistive flow sensor* refers to the flow measurement element based on monitoring the thermal states of an electrically heated sensor whose dependence on the heat loss represents the flow rates of the surrounding fluid. The thermoresistivity of a sensor reflects its variation in electrical resistivity with temperature. A sensor element should usually have a sufficiently high temperature coefficient of resistance (TCR). Typical sensor materials are platinum, nickel, or polysilicon with a specific TCR in the order $\sim 10^{-3}$ °C. The highest measured resolution for the latest thermoresistive flow sensors has reached the order of $\sim$ nl/min.

Overview

Most commonly used microflow sensors are based on thermal principles [1]. Owing to its superior simplicity, which allows it to be integrated in a MEMS device, the thermoresistive flow sensor has been widely adopted in a variety of practical situations such as: biomedical and home applications, environmental monitoring, process control, microanalysis systems etc. [2, 3]. The dependence on the heat loss between a fine wire or thin film, which serves as the sensor, and the surrounding fluid has traditionally been among the most accepted methods for measuring fluid flow [4]. A thermoresistive flow sensor refers to the flow measurement element based on monitoring the thermal states of an electrically heated sensor immersed in or besides the flowing fluid medium such as a gas or liquid [5]. It usually works when the other physical properties of the fluid such as temperature, composition, density, and pressure are constant, therefore the only variable which affects the heat transfer of the sensor is the flow rate.

A microthermoresistive flow sensor can be composed of a variety of combinations of heat sources and temperature sensors. It typically consists of a heater and one or more temperature sensors [1, 6]. Up to now, thermistor principles, geometries, and sensor materials have been found in a wide variety of combinations from CMOS compatible thermocouples to thermistors with different material compositions and geometries, from bridge structures to membranes [6]. The fluid (a gas or liquid) can either flow over the entire chip or over a controlled area of the chip through an integrated microchannel [2]. The flow rate is estimated by measuring the heating power, heater temperature, fluid temperature, and the time-of-flight of a heat pulse.

The electrical resistance of a thermoresistive flow sensor can be calibrated as a change in the temperature. A linear relation between them is usually adopted, i. e.

$$R(T) = R\left(T_0\right)\left[1 + \alpha\left(T - T_0\right)\right] \tag{1}$$

where $R(T)$ is the sensor resistance at operating temperature T; $R(T_0)$ is the sensor resistance at the reference temperature T_0; α is the temperature coefficient of resistance, which includes the effects of lead and wire resistance change and may depend on a reference temperature. When an electrical current I_0 is applied on a thermoresistive flow sensor and its self-Joule heating is maintained at a constant level, any fluid flow through the sensor will cause a shift in its temperature and thus resistance R, respectively. As a result, a decrease in the voltage V $(= I_0 R)$ of the sensor will be detected. The aim of the thermoresistive flow sensor is to evaluate such changes caused by variations of the flow rate alone.

The most typical electrical circuits for control and evaluation of a thermoresistive flow sensor are based on the well-known Wheatstone bridge using either the constant-current or the constant-temperature mode, respectively [4]. In a constant-current circuit (see Fig. 1a), resistors R_3 and R_4 at the two arms are much larger than the sensor resistor R_1. Therefore, the electrical current through R_1 is essentially independent of the changes in the sensor resistor R_1. Any flow in the channel cools the hot wire, decreases its resistance as given by Eq. (1), and unbalances the bridge, which then produces an output voltage V. The voltage V is generally small and must be amplified before it is recorded [4]. The values of the TCR α for R_1 and the variable resistor R_2 should be equal in order to eliminate any signal errors due to changes in the ambient temperature. The values of TCR for R_3 and R_4 should also be equal.

A constant-temperature Wheatstone bridge is shown in Fig. 1b. The circuit bridge is balanced in advance under noflow conditions using the variable resistor R_2. Therefore with the flow of the fluid, the hot wire or film is cooled and its resistance decreases and unbalances the bridge. A differential amplifier would then balance the bridge with a feedback voltage [4]. Such electrical output correlates directly with the flow rate.

Traditionally the thermoresistive flow sensor appears as a wire or film embedded inside the flow field. In a microfluidics-related measurement, the microthermal sensor is usually mounted in the wall of a microchannel to avoid disturbing the flow and thus accurately measure the fluid. Due to the highly confined geometry, a complicated MEMS technique has to be adopted for the fabrication of the thermoresistive flow sensor. At present, most of the commercially available sensors are usually inadequate for precise flow control in microfluidics because of their limited sensitivity, large size, high dead volume, and difficulties in interfacing with microfluidic devices [7]. Miniaturization of a sensor in micro- or nanoflow is therefore a necessity, since only a small size will allow for a precise, local and high transient resolution in temperature measure-



Thermoresistive Flow Sensors, Figure 1 Wheatstone bridge circuit for control and evaluation of hot-wire or hot-film sensor: (**a**) constant-current bridge; (**b**) constant-temperature bridge. Modified from [3]

ment, power reduction, and integration with devices [6]. Overall, the microthermoresistive flow sensor relies heavily on miniaturization and innovation of different well-established thermal macroflow sensing principles. There are three main types of thermal flow sensor which combine the evaluation methods and heater modes: hot-wire (hot-film), calorimetric, and time-of-flight [1]. Each of these sensors types can be further categorized according to their thermal sensing principle as: thermoresistive, thermocapacitive, thermoelectric, thermoelectronic, or pyroelectic. Only the thermoresistive flow sensor will be illustrated in this essay. To interpret the mechanisms of using such sensors to measure the flow parameters, typical principles, and practical design of the device will be considered. Some fundamental issues which will require further investigation are noted.

Basic Methodology

Principle

The operating modes for the microthermoresistive flow sensor are similar to their conventional bulk ones. For traditional research applications, cylindrical sensors which take the form of either a fine wire (typical diameters of $1-15\,\mu$m) or a cylindrical film (typical diameters of $25-150\,\mu$m) are the most common. The wire sensor is mainly used for clean air or gas measurement due to its fragility, while hot-film sensors can be used in both liquid and contaminated-gas environments [4]. A major difference between a microthermoresistive flow sensor and its traditional counterpart is that, the former has to be made using micro- or nanofabrication technologies such as bulk micromachining, surface micromachining, epimicromachining, and LIGA-techniques, etc. These new sensors have been able to measure very small flows in the nanoliter and microliter ranges. Depending on the location of the heating and sensing elements, the flow sensors can be either intrusive (lying in the fluid), or nonintrusive (located outside the flow). The intrusive type has many limitations such as disturbing the fluid, easy corrosion or damage, and difficulty in integrating with the channel [4]. Thus, it is more common for nonintrusive thermal sensors to be used in micro- or nanofluidics. The sensors are often embedded in the wall of a microchannel for flow measurement.

The three existing types of thermoresistive flow sensor are generally classified as hot-film, calorimetric, and time-of-flight type, respectively. The basic operating principle of a hot-film flow sensor is based on microconvective heat transfer from a heated thin-film sensing element (also called a heater) to a liquid flowing inside a microchannel [7]. When the sensor (heater) is subjected to a constant current heating, forced convection by the flow causes a decrease in the heater temperature. The flow rate of the fluid can be identified by detecting the effect of the flowing fluid to the sensor. Figure 2a illustrates the geometric design of such an MEMS flow sensor and its operating principle. Here, the heater is built on the wall of the microchannel. By detecting the sensor temperature, one can obtain the liquid flow rate using a precalibrated experimental curve for temperature versus flow rate (see Fig. 2b). In terms of the calorimetric principle, a widely used microthermoresistive flow sensor is the ►thermal anemometer, which typically consists of a middle heater with an upstream and downstream temperature sensors, relative to the flow direction [2]. Such a calorimetric sensor is based on measuring the asymmetry temperature profile around the heater, modulated by the fluid flow [1, 8]. The schematic representation of a calorimetric device and the temperature distribution in the flow direction are shown in Fig. 3. The MEMS flow sensor consists of three electrical resistors which are mounted directly onto the substrate at the bottom of the fluidic channels. The heating element is located in the middle of the flow channel and is symmetrically encircled by two sensor elements. This symmetric arrangement makes the sensor insensitive to fluctuations in the ambient temperature and enables the flow direction to be detected. The resulting temperature gradient is detected by the two ►temperature sensitive resistors. At zero flow rate, no convection exists in the channel and the heat generated will be transmitted by diffusion. As



Thermoresistive Flow Sensors, Figure 2 Principle for a single hot-wire or hot-film sensor to measure microchannel flow. (**a**) Sensor configuration; (**b**) Sensor temperature



Thermoresistive Flow Sensors, Figure 3 Schematic diagram for calorimetric principle: (**a**) flow microsensors: (**b**) temperature distribution for flow measurements. Modified from [7]

the temperature distribution surrounding the heater is symmetric, no temperature difference is detectable (see Fig. 3). The diffusion can be split into two contributions: the diffusion through the substrate, and that into the fluid via the upstream and downstream directions. Due to heat dissipation, the temperature change is reduced, and may be lower than the detection limit [9]. An increase in the flow velocity shifts the temperature maximum into the direction of the flow. The flow measurement is therefore achieved by the temperature difference between the downstream and upstream sensor microfilaments, whose correlation with the flow rate can also be precalibrated.

The flow measurement principle for the time-of-flight sensor is illustrated in Fig. 4. In this method, the time taken for a heat pulse to pass over a known distance is recorded. The heat pulse generated by an electrical pulse applied to the heater microfilm travels due to the fluid flow and is detected by a sensor microfilm [8, 10]. The time between the heat pulse generation and its detection can then be used for flow estimation (Fig. 4b).

In each of the above thermoresistive flow sensors, the sensor elements are powered by an electrical current like that shown in Fig. 1. The electrical components used for the heater can operate either in a constant heating temperature or in a constant heating current mode depending on whether or not a feedback loop circuit is adopted [1, 2, 5]. The former usually has a fast response. In order to detect the differential voltage, a specific test circuit needs to be manufactured on the device in advance.

Sensitivity of Thermoresistive Flow Sensor

The highest flow measurement resolution for a thermoresistive flow sensor has been in the order of nano- or microliters. To illustrate the basic method of characterizing the sensitivity of a thermoresistive flow sensor, we consider here only a single sensor element for a Lab-on-Chip application, i. e., the hot-film case. For a single thermoresistive element, it utilizes a miniaturized adaption of the anemometric principle. The combination of an established detection principle with the benefits of microtechnology has resulted in a sensor with very high sensitivity [9].

Electrically, the flow-induced output voltage change for the circuit such as shown in Fig. 1a can be written as [7]

$$\Delta V = I_0\left[R(T) - R(T_0)\right] = V_0 \alpha \Delta T \tag{2}$$

where I_0 is the constant current, $V_0 = I_0 R(T_0)$, $\Delta T = T - T_0$.

If the sensitivity (S_V) of a sensor is defined as the ratio between the changes in the sensor output voltage and flow



Thermoresistive Flow Sensors, Figure 4 Flow measurement by time of-flight principle. (**a**) Sensor configuration; (**b**) Sensor signal. Modified from [7, 9]

rate (Q), i. e., $S_V = \Delta V/\Delta Q$, one has

$$S_V = V_0\alpha\frac{\Delta T}{\Delta Q} = V_0\alpha S_T \tag{3}$$

where $S_T = \Delta T/\Delta Q$, represents the temperature–flow ratio, and is related to the sensor structure design and fluid properties. The sensitivity can be assessed in an average sense by the slope of a straight line fitted to the measurement data. In the microflow measurement, if the temperature variation of the sensor is recorded, the flow rate of the fluid can then be estimated through curve fitting.

Further, S_V may involve an original bias voltage that is not related to the sensor design. Thus, it is more appropriate to normalize the sensitivity by the initial bias signal and define the relative sensitivity as [7]

$$S_{V/V_0} = \frac{\Delta V/V_0}{\Delta Q} = \alpha\frac{\Delta T}{\Delta Q} = \alpha S_T \tag{4}$$

As indicated by Eq. (4), the relative sensitivity is proportional to both the TCR and S_T. It should be noted that the former is related to the sensing material properties and the latter to the sensor configuration design. This suggests that a better resolution can be achieved through an improvement of these two factors.

System Level Modeling

Modeling the electrical, thermal, and fluidic behavior of a microfluidic flow sensor and its surrounding structures will provide comprehensive information on many of the physical and dynamic behaviors of the thermoresistive flow sensors located within microfluidic environments [2]. An accurate device model and simulation offer the designer many advantages such as: reducing the time needed for the development cycle and providing the possibility for device optimization through software instead of iterations on physical devices. This, in turn, helps to reduce the end cost of the device. Here, we will focus on the thermal and fluidic modeling. The electrical effect of the sensor will be attributed to a lumped heat source term which appears in the thermal fluidic models.



Thermoresistive Flow Sensors, Figure 5 Side view geometry for a typical calorimetric flow sensor with a middle heater and upstream and downstream temperature sensor. Modified from [2]

Simulation on a flow sensor with its integrated control and signal processing electronics has to simultaneously take into consideration several different domains including the electrical (circuit electronics), heat transfer (thermal phenomena), and fluid flow [2].

As shown in Fig. 5 for the three-dimensional structure of a typical ►thermal anemometer, different types of heat transfer occur in and around the microchip structure [2]. Based on the model developed previously [2], a complete modeling of the thermal state of the flow sensors can be obtained as follows.

Clearly, conduction occurs in the SiO_2 layer, insulating the three flow sensor elements, the flow sensor elements themselves, and the bottom silicon substrate wall of the microchannel. The equations for characterizing the thermal state of these elements can thus be expressed as, respectively, [2]

$$\text{for SiO}_2\text{ layer:}\quad k_{\mathrm{SiO_2}}\nabla\cdot(\nabla T) = (\rho c)_{\mathrm{SiO_2}}\frac{\partial T}{\partial t} \tag{5}$$

$$\text{for heater:}\quad k_{\mathrm{p}}\nabla\cdot(\nabla T) + \dot{q}_{\mathrm{heat}} = (\rho c)_{\mathrm{p}}\frac{\partial T}{\partial t} \tag{6}$$

$$\text{for sensors:}\quad k_{\mathrm{sens}}\nabla\cdot(\nabla T) + \dot{q}_{\mathrm{sens}} = (\rho c)_{\mathrm{sens}}\frac{\partial T}{\partial t} \tag{7}$$

$$\text{for silicon substrate:} \quad k_{\mathrm{Si}} \nabla \cdot (\nabla T) = (\rho c)_{\mathrm{Si}} \frac{\partial T}{\partial t} \tag{8}$$

where $k_{\mathrm{SiO_2}}$, k_{p}, k_{sens}, and k_{Si} are the thermal conductivities of the $\mathrm{SiO_2}$ layer, polysilicon heater, sensor, and silicon substrate, respectively; $\dot{q}_{\mathrm{heat}}$ and $\dot{q}_{\mathrm{sens}}$ are the Joule heating rates at which energy is generated per unit volume of medium for the electrical heater and sensor, respectively; ρ and c are the density and specific heat for each of the solid materials, respectively.

Forced convection occurs in the microchannel where the liquid flowing through the microchannel carries heat away from the heater location. The liquid flowing through the microchannel is governed by the Navier–Stokes equations. By assuming that the flow includes viscous dissipation, the flow equations can be reduced to

$$k_{\mathrm{f}} \nabla \cdot (\nabla T) + \mu \left(\frac{\partial u}{\partial y} \right)^2 = \rho c_{\mathrm{p}} \left[\frac{\partial T}{\partial t} + u(y) \frac{\partial T}{\partial x} \right];$$

$$u(y) = 4 u_{\max} \left[\frac{y}{d} - \left(\frac{y}{d} \right)^2 \right] \tag{9}$$

where k_{f}, ρ, c_{p}, and μ are the thermal conductivity, density, specific heat, and viscosity of the fluid, respectively; u is the velocity of the fluid and $u_{\max}$ is the velocity of flow at the center line of the microchannel; d is the gap distance of a microchannel with a rectangular cross-section.

At the top surface of the $\mathrm{SiO_2}$ layer in the device, natural convection and radiation occur due to heat being conducted to the surface of the device from the sensor heater. The boundary equation there can thus be formulated by equating the conduction of heat through and the effective convection on the top surface, i. e.

$$-k_{\mathrm{SiO_2}} \frac{\partial T}{\partial y} = h \left(T - T_\infty \right) \tag{9}$$

where h is heat transfer coefficient which has included the convection effect and radiation on the device surface, and T_∞ is the temperature in the free stream flow.

A constant temperature is assumed at the entrance of the microchannel bearing in mind that this site is exposed to the ambient temperature, i. e.

$$T\,(x = 0) = T\,(x = L) = T_\infty \tag{10}$$

where L is the length of the microchannel.

To obtain the above equations in a closed form, a series of continuum equations still need to be established. At the interfaces between the heater, sensor, and the surrounding solid material, there is a continuum equation which characterizes the heat conduction at the two sides. A convective heat transfer equation similar to Eq. (9) should be used for the interfaces between a solid surface and the surrounding flowing fluid.

A complete simulation of the above coupled equations and boundary conditions would help to give a complete picture of the detailed working process of the thermoresistive flow sensor including the electrical, thermal, and fluidic phenomena [2]. It would also provide a useful way to optimize the geometry and material of the whole fluidic device.

Device Fabrication

Realization of a flow sensor depends on its specific application. Overall, the spatial and transient resolution and the compatibility of the sensor within the desired device are of major concern [6]. In addition, the protection of the fluids and components demands a reduction in the thermal crossover from the flow sensor. The microflow sensors are usually automatically integrated with the microchannel during the fabrication process. The sensing element should be a resistor that has a resistance with high temperature sensitivity [2, 4, 9]. The heater of the sensor is often fabricated from a platinum or polysilicon resistor and acts as a microheater while the upstream and downstream temperature sensors are made from either polysilicon resistors or thermopiles. Such materials have excellent chemical resistance, biocompatibility, and high TCR [9].

The fabrication of a flow sensor includes making the microchannel and integrated sensor elements. Taking the fabrication of a single heater sensor in a suspended microchannel as an example, the general process involves the following basic sequences (Fig. 6) [7]: Fig. 6a: silicon wafer is often used as substrate. Its surface can be deposited with a thin silicon nitride layer as electrical insulation. A sacrificial PSG layer is then deposited and patterned on top of silicon nitride to define the microchannel geometry. Fig. 6b: Following the above procedure, another silicon nitride layer is deposited above the PSG surface to act as the top wall of the microchannel. After etching the PSG by HF, a microchannel can be formed. Fig. 6c: A polycrystalline silicon layer is deposited on the silicon nitride as the sensor, and then doped by B^+ ion implantation to improve its performance. This is followed by an annealing process. After that the polysilicon is patterned by plasma dry etching to define the sensor geometry. Fig. 6d: The sensors are sealed by uniformly depositing a thin silicon nitride layer. The inlet and outlet are then opened by KOH. Subsequently, contact opening and Al metallization will form connections between the macroworld and the sensing element. Finally, thermal iso-



Thermoresistive Flow Sensors, Figure 6 Main process steps for fabrication of MEMS flow sensors. Modified from [6]

lation of the channel is achieved by removing the silicon directly underneath the channel using gas-phase isotropic etching by BrF_3 or XeF_2. In this way, an integrated thermoresistive flow sensor with a microchannel is made. In a practical design, the structure, material and configuration, even the fabrication approaches (see Fig. 6) are subject to change depending on various specific demands.

Key Research Findings

Material matching is a critical issue when making a high quality sensor system. For example, Ni and Pt thin films have often been used as temperature sensing elements on GaAs substrate because of their high temperature coefficients and compatibility with GaAs-based devices and related IC processing steps [11]. But when deposited directly on GaAs, both films exhibit high chemical reactivity and interdiffusion effects on the GaAs interface mainly at elevated temperatures, which can lead to the degradation of their electrical and thermal properties. In order to suppress the interfacial interactions, a thin diffusion barrier layer has to be formed on the GaAs surface before the deposition of the Pt and Ni [11].

Several factors determine the measurement resolution of the microflow sensor [11]. First, the sensitivity of the sensor depends on the heater's TCR. Adoption of an appropriate doping concentration of the polysilicon thin film would improve the measurement resolution. For example, a slightly doped heater increases its resistance and hence reduces inaccuracies arising from the resistance of the leads and wires. Second, *thermoresistive flow sensors* require extremely good thermal isolation to avoid heat conduction in the wall. For the channel in direct contact with the substrate, the heat loss from the heater to the substrate may considerably reduce the sensor's sensitivity to the fluid flow. As a remedy, the microchannel can be suspended from the substrate to improve the thermal isolation. In this way, a flow rate measurement resolution in the nanoliter per minute range is possible [11]. On the other hand, it is also useful to insert a thermal insulation between the substrate and the fluidic channel. Further, to assure a fast response and low power consumption, free-standing microfilms with reduced dimensions and good thermal isolation are also very helpful. They are usually implemented using surface micromachining [8]. Such devices can be applied to both gas and liquid flow measurements and permit dynamical operation with complex heating and possible evaluation of the fluid flow parameters.

The maximum temperature measurement resolution depends on the spatial position of the sensor elements with reference to the distance between the heater and the sensor which can also be optimized. Computational modeling and simulation can provide a predictive capability and the means of evaluating the performance of a new design before hardware fabrication. The effect of varying the geometries of sensors and channel can be tested numerically, with different aspect ratios between them. Further, most fluid properties, which determine the heat transfer process, depend on the working temperature. It should be noted that, some changes to the fluid due to heating may not always be easily compensated. Therefore, accurate thermal flow sensors require both flow calibration and calibration for temperature compensation [4].

Future Directions for Research

Except for the normal microsize sensor devices, which have already been strenuously tested, much smaller *thermoresistive flow sensors* are in urgent need of investigation. However, this may involve a series of new challenges. With the decrease in the flow channel and sensor, conventional flow and heat transport theories may not be valid to explain the phenomena, due to the multiple physical effects that are involved. Currently, there is still a strong lack of fundamental knowledge on such issues. In particular, the coupled momentum, electrical and heat transfer phenomena in the basic components of the flow sensor and the surrounding fluid and solid components are not well understood. It is possible that if the size becomes smaller, the flow and heat transfer, electrical field, and even mechanical properties such as the expansion effect in such devices may tend to behave differently compared to the behavior of their bulk objects. For example, the inertial force tends to be quite small and the surface effects, the electrical double layer, which were unimportant in the bulk device, will play a dominating role. Friction, electrostatic forces, and viscous effects due to the microfluid and channel may become increasingly important as the devices become smaller. Further, whether or not the specific fluid, usually a biosample, will follow the behavior of Newtonian fluids needs to be clarified experimentally. Additionally, with multispecies such as biological samples or chemical compounds in the micro- or nanofluidics, the thermoresistive flow sensor may encounter difficulty in realizing a high measurement solution and good repeatability. Multiparameter detection in micro- or nanoflows is thus a big challenge.

Overall, a large number of variables determine the measurement resolution of a thermoresistive flow sensor. Among the effects which influence the measurement, sensor material characteristics and liquid flow mode, the channel property, the flow quality, multicomponents, liquid properties and geometry of microchannels all need to be addressed. Previous investigations have provided quite substantial experimental data on the thermoresistive flow sensor. Future study can choose to follow some of the existing technical routes by carefully evaluating the size effects. Clearly, a complete modeling of the various domains in the flow sensor and incorporating the electrical, thermal and fluidic effects into the model are also worth investigating.

Cross References

- ► Control of Microfluidics
- ► Digital Microfluidics
- ► Flow in Channels with 3D Elements
- ► Fluid Metering
- ► Fluidic Nanosensors
- ► Heat Transfer in Microchannel Flows
- ► Temperature Control in Microfluidic Systems
- ► Implication for Biomedical Applications
- ► Methods for Flow Rate Measurements
- ► Micro- and Nano-Scale Anemometry: Implication for Biomedical Applications
- ► Microfluidic Circuits
- ► Temperature Sensitive Resistor
- ► Thermal Anemometer
- ► Thermoresistive Flow Sensors

References

1. Kallio P, Kuncova J (2004) Microfluidics. Tekes Technol Rev 158/2004:1–33
2. Rasmussena A, Mavriplisa C, Zaghloula ME, Mikulchenkob O, Mayaram K (2001) Simulation and optimization of a microfluidic flow sensor. Sens Actuators A 88:121
3. Xu Y, Chiu CW, Jiang F, Lin Q, Tai YC (2005) A MEMS multisensor chip for flow sensing. Sens Actuators A 121:253
4. Nguyen NT (1999) Thermal mass flow sensor. In: Webster JG (ed) Mechanical Variables Measurement: Solid, Fluid, and Thermal. CRC Press, Boca Raton, Florida
5. Cheremisinoff NP, Cheremisinoff PN (1988) Flow Measurement for Engineers and Scientists, pp 76–113. Dekker, New York
6. Ernst H, Jachimowicz A, Urban GA (2002) High resolution flow characterization in Bio-MEMS. Sens Actuators A 100:54
7. Wu SY, Lin Q, Yuen Y, Tai YC (2001) MEMS flow sensors for nano-fluidic applications. Sens Actuators A 89:152
8. Rodriguesa RJ, Furlan R (2003) Design of microsensor for gases and liquids flow measurements. Microelectron J 34:709
9. Schöler L, Lange B, Seibel K, Schäfer H, Walder M, Friedrich N, Ehrhardt D, Schönfeld F, Zech G, Böhm M (2005) Monolithically integrated micro flow sensor for lab-on-chip applications. Microelectron Eng 164:78–79
10. Rodrigues RJ, Furlan R (2002) Development of a time-of-flight flow microsensor. In: Proceedings of 17th Symposium on Microelectronics Technology and Devices
11. Lalinský T, Držík M, Jakovenko J, Husák M (2005) GaAs thermally based MEMS devices: fabrication techniques, characterization and modeling. In: Leondes CT (ed) MEMS/NEMS Handbook: Techniques and Applications, vol 3. Springer, New York

Thermosensitive Hydrogels

► Temperature-Sensitive Hydrogels

Thick Film Lithography

► Thick Resist Lithography

Thick-Film Piezoelectric Actuation

► Membrane Actuation for Micropumps

Thick Resist Lithography

Clifford L. Henderson
School of Chemical & Biomolecular Engineering,
Georgia Institute of Technology, Atlanta, USA
cliff.henderson@chbe.gatech.edu

Synonyms

Thick film lithography

Definition

Thick film lithography refers to the processes used to make thick films of photoresist, i. e. typically “thick film” is used to refer to films that 5 to 100’s of μm (μ) thick, and subsequently produce relief patterns in those films. The *photoresist* is a radiation sensitive material that is applied to a substrate surface, exposed to radiation to create a physiochemical change in the exposed regions, and washed in a developer solution to produce the desired physical relief patterns.

Overview

Lithography in the most general sense refers to methods used for printing on a smooth surface. It has its origins in methods used to print text and artwork onto paper or other suitable materials in the late 1700’s. In the context of microfabrication and microsystems today (e. g. integrated circuits, microelectronic devices, microelectromechanical systems, and microfluidic devices), it refers to the processes used to form relief patterns in the photoresist films that are subsequently used in the layer-by-layer fabrication sequences of such micro-scale devices. It is also commonly referred to as microlithography or nanolithography depending on the size scale of features that are being printed. There are many specific types of lithographic processes. It is common to classify them by either:

- the type of external stimuli used to impart pattern definition in the resist (e.g exposure to ultraviolet light, exposure to an electron beam, exposure to x-rays, mechanical force using a mold or template, etc.)
- the type of photoresist being used (e. g. positive tone resist, negative tone resist, diazonapthoquinone-novolac resist, chemically amplified resist, single layer resist, bilayer resist, etc.), or
- the photoresist film thickness range being used (i. e. generally divided into thin film lithography and thick film lithography).

This discussion will be limited to those lithography methods that utilize the application of external radiation (i. e. optical exposure, e-beam exposure, or x-ray exposure) and will not include imprint lithography techniques such as hot embossing. Thick film lithography is generally used to refer to lithographic processes that utilize photoresist film thicknesses greater than 5μ in thickness.

The steps in a basic lithography process are shown schematically in Fig. 1. The first step in the process generally involves cleaning the surface of the substrate on which the lithography is to be performed, and may also involve the application of a surface priming agent. A wide variety of both wet chemical and dry plasma methods for cleaning the substrate surface may be employed. If surface priming of the substrate is performed, it can be done using both vapor phase and liquid phase exposure of the surface to an appropriate priming agent. Surface priming is generally done to improve the adhesion between the photoresist film and the substrate surface so as to prevent problems such as difficulty in wetting the substrate surface during spin coating of the photoresist or delamination of the photoresist film during further processing such as aqueous development. One of the most commonly used surface priming agents for spin coating resists is hexamethyldisilazane (HMDS) which reacts when applied to a surface containing hydroxyl groups (i. e. such as the silanol groups present on native oxide coated silicon wafers) to produce an essentially methyl terminated surface. The organic non-polar nature of this methyl terminated surface generally improves compatability between the surface and the photoresist, which is also typically an organic material of moderate polarity.

Once the substrate surface has been prepared, the photoresist film is applied. Application of the photoresist can be performed using several different methods, with dry film transfer, casting and in -situ polymerization, and spin coating being the most common methods. In dry film transfer, a pre-made solid photoresist film is laminated onto the substrate surface. This type of photoresist film deposition method is relatively common in thick film lithography since spin coating of thick uniform films can be difficult and thick photoresist films respond well to such film transfer methods. Spin coating is the other most common film deposition method and involves depositing the photoresist from solution, i. e. the photoresist solids are dissolved into an organic casting solvent, onto the substrate and subsequently spinning the substrate at moderate to high speeds. The spinning action spreads the solution into a uniform film and also serves to dry the film into a solid form. In cases where the film is spin coated onto the substrate, it is common to then heat the substrate and film in



Thick Resist Lithography, Figure 1 Schematic of the basic lithography process. First a resist film is coated onto the substrate of interest that may contain either films to be etched or films that can be used to deposit other materials by techniques such as plating. The resist film is exposed pattern-wise to radiation which results in a physiochemical change in the exposed resist that changes the solubility of the exposed resist in a developing solvent. Treatment of the resist with a developing solvent then leads to either removal of the exposed resist in the case of positive tone photoresists or removal of the unexposed resist in the case of negative tone photoresists

what is referred to as a post-apply bake (PAB). The purpose of this baking step is to further dry the film by evaporating remaining casting solvent in the photoresist film. After application of the film, the next step is to expose the film in a pattern-wise manner to produce a latent chemical image in the film in the shape of the desired final pattern. Depending on the specific type of resist and the type of radiation exposure source used, the type of physiochemical change in the resist film that ultimately leads to development of the desired relief image can vary quite widely. The most common types of thick film lithography are:

- positive tone imaging using ultraviolet exposure of *diazonaphthoquinone-novolac resists*,
- negative tone imaging using ultraviolet or x-ray exposure of cross-linking resists such as *SU-8*, and
- x-ray exposure of positive tone resists such as *poly(methyl methacrylate)* or PMMA. Further attention will be paid to each of these in the following section.

Basic Methodology

Positive Tone Thick Film Lithography using DNQ-Novolac Resists and UV Exposure

In a positive tone resist, the areas that are exposed to the radiation develop away into solvent faster than unexposed areas, resulting in a positive tone image of the mask. The majority of commercial, positive tone, non-chemically amplified resists used today are variations on the well-known, two component, diazonaphthoquinone-novolac resist. (5) Novolac is a name generally given to acid catalyzed phenol-formaldehyde condensation polymers of the type shown in Fig. 2.

Novolac polymers are soluble in a variety of common organic solvents. Resist films are typically cast from organic solutions (propylene glycol monomethyl ether acetate, or PGMEA, is a common solvent) to form isotropic, glassy, thin films. These polymers are also soluble in aqueous alkaline solutions due to the presence of the acidic phenolic functionalities on the polymer backbone. It is this base solubility that is exploited in the development process. In order to print a relief image in a photoresist it must be possible to modify the dissolution rate of the resist upon exposure to radiation. It is not the novolac polymer in DNQ-novolac resists that is sensitive to radiation. Instead, it is the second component of the resist, the diazonaphthoquinone (DNQ), that is responsible for the ability of the resist to change its dissolution behavior upon exposure to radiation. DNQ is often referred to as the photoactive compound (PAC) or sensitizer in the resist, since it is the component which responds to radiation exposure. Thus, the role of the novolac polymer in these resists is to provide the desired physical characteristics of the material, such as good film forming properties and etch resistance to plasma processing, while the DNQ allows the resist to be imaged. Figure. 3 shows a schematic view of the basic mechanism responsible for the function of DNQ-novolac photoresists.



Thick Resist Lithography, Figure 2 Example of the structure of a novolac resin and the commercial production route for the polymer that is typically accomplished via the acid catalyzed polymerization of cresols with formaldehyde



Thick Resist Lithography, Figure 3 Schematic picture of the mechanism by which DNQ-novolac resists function. Addition of DNQ inhibitor (I) to novolac polymer (N) results in a dramatic reduction in the dissolution rate of the polymer in aqueous alkaline developer solutions. Exposure of the DNQ-novolac resist mixture causes a chemical reaction converts the diazonaphthoquinone to a carboxylic acid photoproduct (P), and the presence of this carboxylic acid product in the exposed resist either does not dramatically retard or may in fact accelerate the dissolution of the polymer in aqueous alkaline developers. This differentiation in dissolution rate of the resist upon exposure allows for the formation of relief images in the photoresist after development

The addition of diazonapthoquinones to novolac films leads to a reduction in the dissolution rate of the polymer film in aqueous base relative to the dissolution rate of the pure polymer. This difference in rate can be as large as several orders of magnitude. Diazonaphthoquinone is therefore termed a “dissolution inhibitor” due to its ability to retard the dissolution rate of the novolac film. As shown above, DNQ undergoes a series of reactions upon exposure to radiation to form a carboxylic acid product. This carboxylic acid, unlike the hydrophobic DNQ, is soluble in aqueous base and its presence in the polymer film does not retard the dissolution rate in aqueous base. In fact, the presence of the carboxylic acid often serves to increase the dissolution rate of the novolac several orders of magnitude relative to the pure novolac polymer. It is this change in the dissolution rate of the novolac film due to the reaction of the diazonaphthoquinone with light that allows for the formation of relief images in the resist film. One advantage of DNQ-novolac resists for use in thick film UV lithography is that the resist material becomes more transparent to ultraviolet light, referred to as “bleaching” of the resist, as it is exposed. This bleaching phenomena allows thick resist films to be exposed and developed to produce high aspect ratio patterns relatively easily.

In forming thick resist films using DNQ-novolac resist solutions, solutions containing a high solids content of relatively high molecular weight resist polymers are typically used to provide high solution viscosities that make such thick film formation possible. In general, the relationship between film thickness formed after spin coating (*t*), spin speed (Ω), polymer concentration (*C*, typically in grams polymer/ 100 mL of solution), and resist polymer molecular weight ([η], as measured by intrinsic viscosity in this case) can be expressed as follows:

$$t = K\frac{C^{\beta}[\eta]^{\gamma}}{\omega^{\alpha}} \tag{1}$$

where K is an overall proportionality constant and *a, b,* and *g* are constants, all of which depend on the particular resist, substrate, and resist processing system used. Once a few experimental data points are collected, for example on the effect of spin speed on resist thickness, Eq. (1) can in general be used to develop a master equation for a resist coating application that can allow for specific resist thickness targets to be achieved. Before applying the resist, the substrate is generally cleaned and may be surface primed as mentioned earlier. In addition, in the case of UV exposure a so-called *anti-reflection coating* (ARC) may also be applied to the substrate. The purpose of such an ARC is to minimize surface reflections during UV exposure of the resist that can lead to undesired exposure variations in the resist, such as the formation of standing waves, that lead to degraded lithographic performance (e. g. the formation of scalloped sidewalls in developed relief images).

Exposure of DNQ-novolac resists is typically done using either I-line 365 nm, G-line 436 nm, or broadband (~ 350–450 nm) ultraviolet exposure using mercury lamp-based exposure tools. A variety of different types of exposure tools including contact, proximity, and projection exposure tools are used to perform the pattern-wise exposure of such materials. The maximum feature resolution of such exposure tools depends on the tool type, with projection exposure tools exhibiting the highest resolution and proximity tools exhibiting the lowest resolutions. Typical ultraviolet exposure doses for DNQ-novolac resists are on the order of several hundred mJ/cm^2 to several thousand mJ/cm^2 depending on the resist thickness, wavelength used, and formulation. After exposure, DNQ-novolac resists may be subjected to a post-exposure bake (PEB) that is designed to eliminate any significant gradients in DNQ concentration normal to the substrate surface. Such gradients are common in thinner film exposures using near monochromatic exposure sources since standing waves can form in the film during exposure that lead to a sinusoidal-looking concentration profile though the thickness of the resist film. Such oscillating concentration profiles make development of high quality features difficult and lead to scalloped edges in final resist relied profiles. Finally, the resist film is either immersed or sprayed with an aqueous alkaline developer to remove the exposed regions of the resist. Both inorganic alkaline developers (e. g. based on potassium hydroxide or KOH) and organic alkaline developers (e. g. tetramethyl ammonium hydroxide or TMAH) can be used for DNQ-novolac resists.

Positive Tone Thick Film Lithography Using X-ray Exposure

X-ray exposure of samples to fabricate thick film resist structures has developed into an important technique for microfabrication of a wide variety of devices. The use of x-rays to expose thick film resist samples is advantageous for a variety of reasons including:

- a simple printing scheme such as shadow masking (i. e. proximity or contact printing) can be used while still producing high aspect ratio structures with relatively straight sidewalls and
- x-rays have the ability to penetrate and expose the resist film with good uniformity throughout the depth of very thick film samples leading to more uniform structures.

The use of such x-ray exposure techniques is the basis for the so-called *X-ray* LIGA process. LIGA is the German acronym for lithography (LI thographie), Electroplating (G alvanoformung), and Molding (Abformung), which is a microfabrication process that was developed in the late 1970's and early 1980's by a team at the Forschungszentrum Karlsruhe. It was developed to allow the manufacturing of very high aspect ratio parts, in this case nozzles for uranium separation, with lateral precision below one micron. The basic original process involves five key steps steps:

- use of x-ray exposure to produce a high aspect ratio resist structure that can serve as a mold for electroplating,
- electroplating into the resist mold to form a metal master part attached to the substrate,
- removal of the resist layer,
- manufacture of a mold from the metal master part, and
- reproduction of copies of the metal master part by injection molding or other techniques.

Since its invention, this type of LIGA process, and many other variations on it, have been used for fabricating a wide variety of *microelectromechanical systems* (MEMS) and other microdevices.

The original resist used for the LIGA process was thick films of poly(methyl methacrylate) (i. e. PMMA). Because spin coating the very thick layers desired in the original work was not a practical way to obtain thick homogeneous resist films, other alternatives were developed for producing the desired resist layers that were hundreds of microns to millimeters thick. The maximum film thickness reported when spin coating PMMA has been on the order of 150 μ. One technique developed for producing the thick PMMA films desired is the so-called "film casting" process in which:

- PMMA polymer is dissolved in methyl methacrylate monomer to form a very viscous mixture,

- a polymerization initiator and potentially cross-linkers and adhesion modifying compounds are added to the mix,
- the liquid is poured onto the substrate, put into a press configuration where a plate is placed on top of the liquid film and pressed down onto spacer shims located between the substrate and plate (i. e. to control the final film thickness),and
- the material is cured by heating the material or exposing it to ultraviolet light.

One problem with this casting method is the shrinkage that occurs as a result of the polymerization which makes film thickness control somewhat challenging and creates residual stress build-up in the polymer film. This residual stress build-up can be very problematic and can lead to crazing and delamination of the film from the substrate. In order to minimize such problems, very high molecular weight polymers are desired with preference to somewhat networked materials formed through the use of cross-linking agents (e. g. multi-functional acrylate monomers). Furthermore, post-cure annealing steps in which the film and substrate are heated above the glass transition of the polymer can help to reduce residual stress. Another set of techniques that have been used to generate very thick PMMA films involves the lamination of a pre-formed PMMA sheet onto the substrate. In one version of such a process, commonly referred to as a "glueing process", a thin layer ($\sim < 10$ thick) of the polymer-monomer mixture used for the film casting process is spread onto the substrate and the pre-formed PMMA sheet is pressed onto this layer which acts as a glue to stick and bond the sheet to the substrate. The glue layer is then cured to produce a secure bond of the sheet to the substrate. Studies of this technique have shown that the residual stress built up in the glue layer is much lower than that of the film casting technique since the amount of material cured is much smaller. In one final variation of this sheet bonding process, a thin ($\sim 1-2\,\mu$ thick) PMMA layer is first deposited onto the substrate via a method such as spin casting. After the film is cast, a small amount of a good solvent for PMMA is sprayed onto the film and the pre-formed PMMA sheet is pressed onto this solvent rich layer. The presence of solvent results in a melting and fusion of the sheet to the cast film and the process is complete in a few hours as the solvent dries from the thick film.

Upon exposure to x-rays, PMMA undergoes a variety of complex reactions. However, the dominant effect is chain-scission of the polymer which reduces its molecular weight. Figure. 4 shows the effect of x-ray dose on molecular weight for PMMA possessing a relatively high initial molecular weight (i. e. 10^6 g/mol) It is this reduction of molecular weight of the polymer in the exposed areas that is responsible for the increased dissolution rate of the exposed PMMA in developing solvent. As can be seen, there is a point of diminishing returns in terms of using higher exposure energies. This is because as the polymer molecular weight decreases, the chance for cross-linking reactions in the PMMA increases, leading to the fact that at very high doses an equilibrium between chain scission and cross-linking reactions occurs that results in no further change in polymer molecular weight. After exposure, the irradiated regions of the polymer must be selectively remove using a solvent without attacking the unexposed regions. Special multi-component solvent mixtures are commonly used for the development. One example of a solvent developer that has been widely used is a mixture consisting of 20 vol% tetrahydro-1,4-oxazine, 5 vol% 2-aminoethanol, 60 vol% 2-(2-butoxyethoxy)ethanol, and 15 vol% deionized water. The molecular weight cut-off that the developer can dissolve can be adjusted by slight compositional changes to the developer or by simply adjusting the developer temperature. Increasing the developer temperature enables the dissolution of high molecular weight polymer, but temperatures above ~45 °C should be avoided as even very high molecular weight polymer is swollen or dissolved above these temperatures.



Thick Resist Lithography, Figure 4 Example of the effect of x-ray irradiation on the molecular weight of an initially high molecular weight poly(methyl methacrylate) sample

Although PMMA is well known for its ability to produce extremely high resolution patterns, it is also known for its relatively low radiation sensitivity. This results in the use of very high radiation doses to pattern the material. Furthermore, in thick resist layers, the absorption of energy by the material can not be ignored and leads to a variation in the energy deposited as a function of depth into the resist film. There is a minimum energy that must be deposited in the bottom of the resist film, otherwise the polymer at the bottom of the film will not undergo sufficient chain scission to develop cleanly and will leave a residue. Likewise, there is a maximum amount of energy that can be deposited into the top of the resist film without resulting in foaming of the resist due to the release of gaseous byproducts during the chain scission process. As a result of these issues, the exposure conditions for PMMA in x-ray thick film lithography must be carefully considered and must take into account the limits for energy deposited into the top and bottom of the resist film.

Negative Tone Thick Film Lithography Using UV and X-ray Exposure of Cross-linking Resists

In the two previous examples, different physiochemical mechanisms were employed to increase the solubility of the exposed resist in developer that led to positive tone image formation. Negative tone imaging can also be performed by invoking physiochemical changes in the resist upon radiation exposure that leads to a decrease in the solubility of the exposed resist in developing solvent. The most popular method for producing such negative tone materials is the use of radiation induced cross-linking reactions in a polymer matrix. Cross-linking of the polymer in general to a reduction of the solubility of the polymer in developing solvent, in a manner that is exactly opposite to that used in x-ray lithography of PMMA. One of the most popular resists for negative tone thick film lithography is SU-8. SU-8 consists basically of a phenolic oligomer that has been functionalized with epoxide groups mixed with a photoacid generator (e. g. an onium salt such as triphenyl sulfonium hexafluoroantimonate). Upon exposure to radiation, the photoacid generator compound produces a strong acid and this acid in turn initiates polymerization of the epoxide groups on the oligomers. This results in heavy cross-linking of the film and a dramatic reduction in its solubility. In addition to providing a mechanism for patterning the resist, the use of the cross-linking reaction produces a very mechanically robust polymer that is often used to directly form structures that are used as a part of the final device being constructed and not simply as a temporary resist mask for other processes such as plating.

Key Research Findings

X-ray based thick film lithography is still the best technique for producing very high aspect ratio structures with little or no variation in part dimensions along the axis normal to the substrate. This ability to produce such high aspect ratio structures with excellent dimensional tolerancing is a result of the very small x-ray wavelength combined with the ability to produce very well collimated x-ray beams using synchrotron sources. Parts that are hundreds of microns to millimeters in thickness with lateral feature resolution well below one micron can easily be formed. However, access to a synchrotron source is required for such x-ray techniques which makes the method impractical for most laboratories or companies. As an alternative, thick film lithography using UV exposure has progressed to the point where it is the dominant over x-ray techniques for MEMS and other thick film fabrication needs. Both positive and negative tone resists are used in such methods, with negative tone materials offering the advantage that they generally have superior mechanical properties that can allow for their permanent use in device structures.

Future Directions for Research

Thick film lithography at this point is a relatively mature technology. While techniques such as x-ray lithography can produce very high aspect ratio structures in very thick resist films, the use of such x-ray techniques is limited by extreme expense of the synchrotron sources needed to produce the well collimated x-ray beams required for such lithography processes. Therefore, work continues to develop much cheaper alternatives based on the use of ultraviolet exposure using both positive and negative tone resists that can produce high aspect ratio structures with high feature resolutions. Such UV exposure methods are now used in so-called UV LIGA in a manner that is analogous to the x-ray LIGA methods discussed earlier. In addition, modern MEMS devices rely on the ability to fabricate released structures, i. e. ones where some part of the device is not in contact with the substrate or some other part of the device. Various sacrificial techniques have been developed in conjunction with thick film lithography to produce these released structures. Development of materials and techniques for the direct use of the resist material as a sacrificial material continues to be of interest. In one example, sacrificial resists based on polynorbornenes and polycarbonates have been developed that can be used for thick film lithography, used to template the deposition of additional materials via plating or other techniques, and finally removed as a sacrificial material by simply heating the resist to a moderate temperature that is capable of transforming the polymer into gaseous products. Using such materials and techniques, microchannels and microfluidic devices have been fabricated with very complex designs in a manner that is compatible with both other microelectronic and MEMS fabrication techniques.

Cross References

- ► Photoresist SU-8
- ► Photoresist Reflow

- ► Photolithography
- ► SU-8
- ► LIGA
- ► Microelectromechanical System (MEMS)

References

1. Friedrich CR, Warrinton R, Bacher W, Bauer W, Coane PJ, Gottert J, Haneman T, Haubelt J, Heckele M, Knitter R, Mohr J, Piotter V, Ritzhaupt-Kleissl H-J, Ruprecht R (1997) High Aspect Ratio Processing, In: Choudhury PR (ed) Handbook of Microlithogr, Micromachining Microfabr, vol 2: Micromachining and Microfabr. SPIE Optical Eng Press, Bellingham, Washington
2. Thompson LF (1994) An Introduction to Lithography. In: Thompson LF, Willson CG, Bowden MJ (ed) Introduction to Microlithogr Second Edition. American Chem Society, Washington DC
3. Willson CG (1994) Organic Resist Materials. In: Thompson LF, Willson CG, Bowden MJ (ed) Introd to Microlithogr Second Edition. American Chem Society, Washington DC
4. Thompson LF (1994) Resist Processing. In: Thompson LF, Willson CG, Bowden MJ (ed) Introd to Microlithography Second Edition. American Chem Society, Washington DC
5. Dammel RR (1993) Diazonaphthoquinone-based Resists. SPIE Optical Engin Press, Bellingham, Washington

Thin-Film Actuation

- ► Membrane Actuation for Micropumps

Three-Dimensional Electrodes

Shelley D. Minteer
Department of Chemistry, Saint Louis University, St. Louis, Missouri, USA
minteers@slu.edu

Synonyms

3D electrodes; Flow-through electrodes; Porous electrodes

Definition

Three-dimensional electrodes are non-planar electrodes that typically improve the transport of redox species to the electrode surface increasing current density. Some 3-D electrodes are solid, but others are porous or flow-through electrodes whose effective surface area is greater then the geometric surface area on the device.

Overview

One of the common challenges of high sensitivity electrochemical analysis and high power density electrochemical power sources is the need for fabrication of three-dimensional electrodes. Historically, three-dimensional electrodes have been the focus of battery technology for decades and flow-based macroscale three-dimensional electrodes have been used for electrosynthesis [1], electrowining [2], photocatalytic reactors [3], and different types of chemical analysis [4, 5]. The electrodes were fabricated from a number of high surface area and high porosity materials like reticulated vitreous carbon (RVC). Over the last few years, scientists have developed microscale three-dimensional electrodes and have started employing them in microfluidic and nanofluidic devices. These microscale three-dimensional electrodes show promise for improving sensitivity of Lab-on-a-Chip devices and improving control in cell sorting and manipulation.

Basic Methodology

The main principle of employing microscale three-dimensional electrodes is to increase the effective surface area of the electrode to increase current, because amperometric and voltammetric current (i) or electrochemical flux is directly proportional to true electrode area (A).

$$i \propto A$$

Electrochemical current, typically referred to as faradaic current, is a measurement of reaction rate, so the more surface area for reaction, the more product that will be formed and the higher the current. This is illustrated in Fig. 1, which shows the effect of the increase in surface area (via a 3-D electrode) on the number of reactions (turnovers) that can occur at a given point in time. Frequently, the factor by which the current is increased is referred to as the roughness factor, which is the


O
R
O
R
R
O
R
O
R
O
R
O
R
R
Flat (2-D) comb electrodes structure
3-D comb electrodes structure
a
b
Anode
Cathode
R: Reduced species
O: Oxidized species

Three-Dimensional Electrodes, Figure 1 Comparison between flat and 3-D electrodes [13], Reproduced with permission from each of the publishers ratio of the true electrode area to the geometric electrode area, but the concept of the roughness factor gets more complicated with flow-through electrode geometries. However, over the last few years, other purposes for 3-D electrodes have emerged. 3-D electrodes are also useful in the field of dielectrophoresis and electrohydrodynamics.

Dielectrophoresis is sometimes confused with electrophoresis and electroosmosis, but electrophoresis and electroosmosis involve the movement of charged species in a high electric field, but dielectrophoresis is the flow phenomenon by which neutral species can be transported by inducing a spatially non-uniform electric field. There are two types of dielectrophoresis: positive dielectrophoresis and negative dielectrophoresis. In positive dielectrophoresis, sub-micron species move toward high electric field regions, wherein negative dielectrophoresis results in sub-micron species moving toward low electric field regions. Dielectrophoresis is particularly helpful in separating sub-micron species (which cannot easily be separated with traditional filters) and allowing for the deliver of sub-micron species to specific areas of the microchip. It is important to note that all particles can experience dielectrophoretic forces, but the strength of the force predicts the observed dielectrophoretic effect. The strength of the force is dependent on the size and shape of the particle, the electric field gradient, dielectric constant of the solution, and dielectric constant of the particle in the solution. 3-D electrodes allow for a better method for extending the electric field within the solution for improved 3-D control through the solution reservoir and can be designed to have better local control over the dielectrophoretic movement [6].

The final use of 3-D microelectrodes is electrohydrodynamics. Electrohydrodynamic fluid flow is similar to magnetohydrodynamics, but instead is developed by applying a high frequency electric traveling wave, which induces net fluid flow by exerting a force on the charges in the bulk liquid. It is advantageous compared to magnetohydrodyanics or even mechanical pumping, because it is pulseless (continuous) and capable of controllable deliver of very small amounts of fluid, as well as requiring low voltages (around 10V) [7]. Miniaturization of the electrohydrodynamic pump has the advantages of providing the opportunity for bi-directional flow and the ability to more quickly turn the flow on and off.

Key Research Findings

Carbon MEMS (C-MEMS)

Interdigitated arrays of carbon electrodes can be fabricated from pyrolyzing photoresist, as shown in Fig. 2. These electrodes are formed by fabricating a prepatterned photoresist structure using photolithography. The photolithographic process involves coating a surface (typically a silicon wafer) with an organic photoresist (i. e. SU-8) and then exposing the photoresist to UV light through a mask that will define the size, shape, and placement of the carbon electrodes. Then, the photoresist is developed, so that the only remaining structures on the substrate are the UV-crosslinked photoresist structures. The substrate is then pyrolyzed at high temperature ($> 900\,^{\circ}\mathrm{C}$) to form the 3-D carbon electrodes. These electrodes have similar properties to glassy carbon, but with lower oxygen content. They are particularly useful for 3-D electrodes, because they can be fabricated with high aspect ratios (up to 20:1), to tall structures can be fabricated easily and reproducibly. These pyrolyzed photoresist 3-D electrodes have applications in batteries, but they are also applicative to microchip bioanalysis systems. Fischer et al. have used pyrolyzed photoresist to make 3-D electrodes for dual amperometric detection for microchip electrophoresis [8]. However, it is important to note that many electrodes for microchip electrophoresis are 3-D electrodes and can be fabricated from a number of sources including carbon-based screen printing inks, precious metal-based screenprinting inks, carbon fibers, electroplating of metallic electrodes, vapor deposition of metallic electrodes, etc. The choice of material is



Three-Dimensional Electrodes, Figure 2 Array of carbon microelectrodes produced by pyrolizing photoresist [14], Reproduced with permission from each of the publishers usually a function of the properties of the analyte being measured and the type of microchip being fabricated. In theory, these same increased surface area electrodes can be used for micro- flow injection analysis and other amperometric biochips. For instance, micromolded screen printing inks can be used to study the release of catecholamines from PC12 cells [9]. Beyond employing 3-D electrodes for electrochemical detection, Park et al. have used the pyrolyzed photoresist 3-D electrodes for dielectrophoretic separation of carbon nanofibers from canola oil, cell sorting (separation of living and dead cells, cancer cells and leukocytes from blood, and even one type of bacteria from another), and engine oil filtering for sub 10 micron particles [6].

Other Fabrication Methods

Although there are a wide variety of methods for fabricating 3-D electrodes, they can be simply characterized as top-down approaches or bottom-up approaches. The top-down approaches typically involve ablating or etching a large structure down to a 3-D micro or nanostructure. This is frequently done to form micro- and nanoscale electrode tips, but is not as frequent in microfluidic and nanofluidic devices as compared to electrodes for scanning electrochemical microscopy (SECM) and other static solution electrochemical devices. Most 3-D electrodes in microfluidic and nanofluidic devices are fabricated from a bottom-up approach (like the C-MEMS discussed above). This can be done for metallic electrodes by sputter coating or vapor depositing metal structures on substrate surfaces (frequently with the help of an adhesion layer, depending on the substrate surface) or by electrodeposition/electroplating through a template. However, there are other fabrication methods including screen printing 3-D electrodes and micromolding with screen printing inks. The process of screenprinting conductive inks is a well developed technology and can be used for fast mass-production of electrodes, but micromolding is a relatively new technology develop by Martin et al. [10] by which a PDMS microfluidic mold is used and the mold is placed over the substrate. Screen printing ink is pulled through the mold and then the mold/ink/substrate are cured and the mold is removed. The result is 3-D carbon electrode with similar properties to a screenprinted 3-D electrode that can be used for amperometric or voltammetric detection and can easily be coupled to microchip electrophoresis. These types of electrodes can also be used in microfluidic biofuel cells, because the micromolding technique can be used to deposit both the electrode and the enzyme immobilization membrane for entrapping the enzyme at the surface of the electrode.

Microfluidic Chambers for Studying Cellular Responses to Electrical Stimulation

In electrochemistry, we normally define 4 types of electrode designs: a single electrode, a dual electrode, an electrode array, and an individually addressable electrode array. The single electrode is used for simple amperometric and voltammetric detection or as the anode or cathode in a battery or fuel cell. The single electrode can be used in either a 2-electrode or 3-electrode electrochemical cell. The 2-electrode electrochemical cell is the typical battery design with a single electrode and a counter electrode, which we can consider a cathode and an anode. The 3-electrode electochemical cell contains the single electrode (frequently referred to as the working electrode or sensing electrode), a counter electrode for completing the circuit, and a reference electrode in a feedback circuit to ensure the proper applied potential. The dual electrode system is used for dual detection systems in either a 3-electrode or 4-electrode electrochemical cell. The 3-electrode cell contains the two working electrodes and a single counter electrode, whereas the 4-electrode cell contains the dual working electrodes, a counter electrode, and a reference electrode.

Electrode arrays are different from single electrodes, because frequently the electrodes are so close together that the electric field and concentration gradient at one electrode can affect the other electrode. There are two types of electrode arrays: a simple electrode array and an individually addressable electrode array. The simple electrode array contains a series of small micro- or nano-scale electrodes that are all connected together (similar to a group of electrodes wired in series), so that the potential (voltage) that is applied is the same for all electrodes. This type of electrode is used to increase the current density of system, but is not helpful for dielectrophoresis or 3-D detection or stimulation, whereas a individually addressable electrode array has a group of electrodes, but a different potential (voltage) can be applied to each electrode and the current can be measured for just that electrode. The individually addressable electrode array is a relatively new technology, but is crucially important in detection schemes for complex systems and the ability to control transport on the microscale.

Three-dimensional microelectrode arrays can also be used for stimulation of cell versus separation or detection. Klauke et al. developed a microchip device for studying cellular responses to electrical stimulation of myocytes. A polydimethylsiloxane (PDMS)-based microchip was fabricated that include an array of three-dimensional gold microelectrodes for stimulation of mycotes cultured on the surface of the chamber. Measurement of action potential,



Three-Dimensional Electrodes, Figure 3 Schematic of biochip for dielectrophoresis-based cell separation and trapping [15], Reproduced with permission from each of the publishers

intracellular calcium concentration and cell shortening can be performed in-situ within this device [11].

3-D Electrodes for Cell Manipulation

Three-dimensional electrodes on microchip devices have also been used for cell manipulation via dielectrophoresis. Dielectrophoresis can be used to move neutral particles (like cells) by inducing a spatially non-uniform electric field, which will either force the particle to low or high potentials. Microchips have been fabricated with 102,400 addressable electrodes of 20 micron x 20 micron [12]. A schematic of the microchip is shown in Fig. 3. Varying potentials were applied to the electrode to move cells and trap them into regions for optical detection [12]. This is off particular interest for single cell detection and also for the separation of different types of cell (cancer vs. normal, etc.). However, this type of device requires a complicated individually addressable electrode array instead of just an electrode array, because the non-uniform electrode fields must be controlled precisely to move the cell to the proper place on the chip and then to trap the cell. This particular technology and the control circuitry allowed for the software controlled movement of 10,000 living cells simultaneously [12], which is a significant advancement in both the capacity of the chip, but also the logic, circuitry, and software to be able to handle the increased capacity.

Future Directions for Research

These type of 3-D electrodes on microchips could also be used for a wider variety of biomethods, including electroporation, drug delivery, and electrostimulated cell culturing. 3-D electrodes will also have applicability in laminar flow-based fuel cells and biofuel cells due to the increase in roughness factor. 3-D electrode for dielectrophoresis also have applicability to nanoliter or sub-nanoliter liquid dispensing.

Cross References

- ► AC Dielectrophoresis Lab-on-Chip Devices
- ► Amperometric Techniques
- ► Electrokinetic Motion of Cells and Nonpolarizable Particles
- ► DC Dielectrophoresis Lab-on-Chip Devices
- ► Dielectrophoresis
- ► Dielectrophoretic Motion of Particles and Cells
- ► Droplet Dispensing
- ► Electrochemical Techniques
- ► Electrophoresis
- ► Microfluidic Fuel Cells
- ► Photoresist SU-8
- ► Photoresist Reflow
- ► Techniques for Manipulating Cells

References

1. Chai D, Genders D, Weinberg N, Zappi G, Bernasconi E, Lee J, Roletto J, Sogli L, Walker D, Martin C, Menon V, Zelenay P, Zhang H (2002) Ceftibuten: Development of a commercial process based on cephalosporin C. Part IV. Pilot-plant scale electrochemical reduction of 3-acetoxymethyl-7(R)-glutaroylaminoceph-3-em-4-carboxylic acid 1(S)-oxide. Organic Process Res Dev 6: 178–183
2. Reyes Cruz V, Oropeza MT, Gonzalez I, Ponce-de-Leon C (2002) Electrochemical recovery of silver from cyanide leaching solutions. J Appl Electrochem 32: 473–479
3. An T, Zhang W, Xiao X, Sheng G, Fu J, Zhu X (2004) Photoelectrocatalytic degradation of quinoline with a novel three-dimensional electrode packed bed catalytic reactor. J Photochem and Photobio A 161: 233–242
4. Armalis S, Kubiliene E (2000) Stripping potentiometry signal enhancement using mercury film-coated reticulated vitreous carbon working electrode. Analy Chim Acta 423: 287–291
5. Price A, Bartley S, Male S, Cooley G (1999) A novel approach to utility scale energy storage. Power Eng J 13: 122–129
6. Park BY, Madou MJ (2005) 3-D electrode designs for flow-through dielectrophoretic systems. Electrophoresis 26: 3745–3757
7. Felten M, Geggier P, Jager M, Duschl C (2006) Controlling electrohydrodynamic pumping in microchannels through defined temperature fields. Phys Fluid 18: 051707–1 - 051707–4
8. Fischer DJ, Vandaveer WR, Grigsby RJ, Lunte SM (2005) Pyrolyzed photoresist carbon electrodes for microchip electrophoresis with dual-electrode amperometric detection. Electroanal 17: 1153– 1159
9. Li MW, Spence DM, Martin RS (2005) A microchip-based system for immobilizing PC12 cells and amperometrically detecting catecholamines released after stimulation with calcium. Electroanal 17: 1171–1180

10. Kovarik ML, Torrence NJ, Spence DM, Martin RS (2004) Fabrication of carbon microelectrodes with a micromolding technique and their use in microchip-based flow analyses. Analyst 129: 400–405
11. Klauke N, Smith GL, Cooper JM (2003) Stimulation of isolated ventricular myocytes within an open architecture microarray. IEEE Transact Biomed Eng 52: 531–538
12. Manaresi N, Romani A, Medoro G, Altomare L, Leonardi A, Tartagni M, Guerrieri R (2003) A CMOS chip for individual cell manipulation and detection. IEEE J Solid-State Circuits 38: 2297–2305
13. Honda N, Inaba M, Katagiri T, Shoji S, Sato H, Homma T, Osaka T, Saito M, Mizuno J, Wada Y (2005) High efficiency electrochemical immunosensors using 3D comb electrodes. Biosens Bioelectronics 20 2306–2309
14. Chemical Reviews 2004 104 4463–4492
15. Manaresi N, Romani A, Medoro G, Altomare L, Leonardi A, Tartagni M, Guerrieri R (2003) A CMOS chip for individual cell manipulation and detection. IEEE J Solid-State Circuits 38 2297–2305

Three-Dimensional Patterning

► Fabrication of 3D Microfluidic Structures

Threshold Filter

Definition

With a threshold filter binary images can be created. A threshold of a defined intensity value is set and all pixel intensity values above this threshold are 1 while the others are 0. If only pixel values are set to 0 whose original intensity value is smaller than the threshold, a ►background subtraction can be done. This is often done to divide objects from background.

Throat

Definition

This is the location of the minimum cross-sectional area in the converging/diverging nozzle where sonic flow conditions exist (unity Mach number).

Cross References

► Supersonic Micro-Nozzles

Throw

► Stroke

Time-Dependent Density Functional Theory (TDFT)

► Dynamic Density Functional Theory (DDFT)

Time-of-Flight Filter

Synonyms

Time-of-flight mass spectrometer; TOF-MS

Definition

A mass filter that separates ions according to their time of flight through a fixed distance, following their acceleration through a common potential. Requires a pulsed ion source, fast electronics and sufficient flight path for ion separation.

Cross References

► Mass Spectrometry

Time of Flight Ion Mobility Spectrometry

► Miniaturized Ion Mobility Spectrometry

Time-of-Flight Mass Spectrometer

► Time-of-Flight Filter

Time-Gated Fluorescence Detection

Synonyms

Fluorescence detection

Definition

Time-gated fluorescence detection is used to monitor the fluorescence of a sample as a function of time after excitation by a flash or pulse of light. Steady-state intensity measurements of emitted fluorescence are taken over a period of time following pulsed excitation. Time resolution is optically gated, whereby a short laser pulse acts as a gate for the detection of emitted fluorescence and only fluorescence that arrives at the detector at the same time as the gate pulse is collected. In time-gated detection systems, the detector is turned on after excitation and the fluorescence intensity generated is integrated. This method is useful for long lifetime probes.

Cross References

- ► Biosensors Using Laser
- ► Fluorescent Labeling

Time-Multiplexed Deep Etching

Synonyms

Time-multiplexed plasma etching

Definition

Time-multiplexed deep etching (TMDE) is a special deep reactive ion etching (DRIE) process, and has been commonly applied in inductively coupled plasma (ICP) etching system for anisotropic etching and 3-D microstructure fabrication.

In TMDE, the process conducts the cycling of etching and passivation steps. In each cycle, plasma processing gases are flowed independently one at a time during operation which is known as the Bosch process patented by Robert Bosch GmbH of Germany in the mid-1990s. The etching step forms a shallow isotropic trench in a substrate (typically silicon). The passivation step forms a protective film on all surfaces of the substrate. In the subsequent etching step, ion bombardment promotes the preferential removal of the passivation film on the horizontal surface and further attack the substrate chemically and physically, allowing the profile to evolve in a highly anisotropic structure. In a typical configuration,SF_6 is the etching gas andC_4F_8 is the deposition gas for sidewall passivation. In TMDE processing, gas flow rates, etching durations and working powers in each step can be varied to produce designed 3-D microtructures with the well-controlled sidewall profiles.

Cross References

- ► Fabrication of 3-D Microfluidic Structures
- ► Microfabrication Techniques
- ► Plasma Etching
- ► Reactive Ion Etching (RIE)

Time-Multiplexed Plasma Etching

- ► Time-Multiplexed Deep Etching

TIRF

Synonyms

Total Internal Reflection Fluorescence (Microscopy); TIRM; TIRFM

Definition

Total internal reflection fluorescence microscopy (TIRFM), or simply TIRF, is the application of fluorescence imaging to evanescent wave microscopy. The material of interest is tagged with fluorescent material that emits light at wavelengths greater than the excitation photons from the evanescent field, which additionally improves the detectability of the evanescent wave microscopy technique.

Cross References

- ► Evanescent Wave Illumination
- ► Evanescent Wave Microscopy
- ► Fluorescence Measurements
- ► Fluorescence Labeling
- ► Quantum Dots

TIRFM

- ► Evanescent Wave Illumination
- ► Evanescent Wave Microscopy
- ► TIRF

TIRM

- ► Evanescent Wave Illumination
- ► Evanescent Wave Microscopy
- ► TIRF

TIRV

- ► Total Internal Reflection Velocimetry

T-Junction

- ► Flow Bifurcation in Microchannel

TLCs

- ► Liquid Crystal Technique for Measuring Temperature

TOF-MS

- ► Time-of-Flight Filter

Topographical Manipulation

Definition

Three-dimensional management of the landscape of a microfluidic platform utilized to influence curvature to induce capillary flow.

Cross References

- ► Surface-Directed Capillary Flow Systems

Torr

Definition

A unit of pressure, 1 Torr = 133.322 Pa.

Cross References

- ► Sputtering for Film Deposition

Total Internal Reflection Fluorescence (Microscopy)

- ► Evanescent Wave Illumination
- ► Evanescent Wave Microscopy
- ► TIRF

Total Internal Reflection Velocimetry

Synonyms

TIRV

Definition

Total internal reflection velocimetry combines evanescent wave microscopy with established mirco- and nano-scale velocimetry techniques. Particle image velocimetry or particle tracking velocimetry are used to infer fluid velocities from tracer particle displacements in two or three dimensions within the penetration depth of the evanescent field.

Cross References

- ► Micro-PIV-Based Diffusometry
- ► Brownian Motion and Diffusion
- ► Brownian Motion
- ► Evanescent Wave Microscopy
- ► Quantum Dots

Tracers

Definition

Tracers for flow visualization (PIT/► PIV measurement technique) are used as particles and seeded into fluids. It is important that the tracers are able to follow the flow properly. Smaller particles follow the flow very good but offer worse reflective properties than bigger particles. For PIT TLCs are used as tracer particles. They show indirectly the temperature of the flow within a certain temperature range.

Transesterification

Synonyms

Definition

Transesterification is the process of exchanging the alkoxy group of an ester compound by another alcohol.

Cross References

- ► Biomolecular Synthesis in Microfluidics
- ► Lab-on-a-Chip Devices for Chemical Analysis
- ► Microfluidics for Bio- and Chemical Reactions

Transferring Samples to Chips, Techniques

Gang Chen, Xiaohong Chen
School of Pharmacy, Fudan University, Shanghai, China

Synonyms

Sampling; Microfluidic chip; World-to-chip interface

Definition

Techniques for transferring samples to microfluidic chips are of crucial importance because they open the microchip to the macroworld. ►Sample introduction is the beginning of the process of microfluidic analysis on chips. Various techniques for transferring samples in the form of liquid, gas or aerosol to an on-chip liquid environment have been reported for biochemical and environmental analysis.

Overview

Microsystems based on microfluidic chips, are of considerable recent interest owing to their high degree of integration, portability, minimal solvent/reagent consumption, high performance and speed. The dramatic downscaling and integration of chemical assays hold considerable promise for faster and simpler on-site monitoring and decentralized clinical testing and make these analytical microsystems particularly attractive for biological, environmental, and industrial analysis. As with other analysis systems, techniques for transferring samples to microfluidic chips are one of the most important steps for microfluidic analysis on chips. Sample introduction is an important component of these systems and is an essential process for making chip electrophoresis a widely applicable analytical technique. A major obstacle to the realization of such real-life applications has been the introduction of the sample into such microchip devices.

Samples are usually introduced into a microfluidic chip via ►solution reservoirs on chips that are simply storage units for the reagents and samples used within the manifold. Several types of reservoirs have been reported as fabrication techniques have progressed. Effenhauser et al. [1] have developed a simple method that has been commonly used. A blank glass plate (typically 1 mm in depth) was thermally bonded onto the etched chip containing the microstructure, in order to seal the system. Holes were then drilled into this top plate to provide access points to the microchannels. Plastic pipette tips were inserted into these holes to act as reservoirs and to hold the electrodes.

Transferring samples to chips requires the introduction of a reproducible sample into a flowing carrier stream of a manifold without any disturbance to the carrier stream. The system is more versatile if the reproducible volume range that can be introduced is wider. An ideal sample-induction system performs this as a convenient and fast operation so as to provide a high sampling rate. Conventional flow-injection analysis (FIA) injectors (e. g., rotary/slide valve injectors) cannot be used successfully in a microfluidic environment because of the demands of injecting very small volumes. However, some methods for transferring samples based on electrokinetic mobility (electrophoretic mobility or electroosmotic flow), miniaturized valves and hydrodynamic pressure methods employed in micro-FIA system have been adapted to be compatible with the microchip system. Many of the sample-transfer techniques used in the microfluidic chip system were initially adapted from techniques employed in conventional FIA and capillary electrophoresis (CE). Various techniques for transferring samples in the form of liquid, gas or aerosol to an on-chip liquid environment have been reported for biochemical and environmental analysis within the last decade.

Basic Methodology

Samples were usually transferred to the microfluidic system by electrokinetic injection and ►pressure injection. ►Electrokinetic sample introduction is most commonly used for transferring samples to chips. This can be attributed to factors such as the simplicity in achieving electroosmotic flow (EOF), i. e., no moving parts and minimal backpressure effects. The EOF in the microchannel acts as a pump and can easily be controlled by outside high voltages. The two commonly employed injection modes for microfluidic chips are time-based and discrete volume-based injection. In the case of the time-based (or gated injection), the amount of sample introduced into the carrier stream can be controlled by adjusting the injection time.

Figure 1 illustrates the time-based floating injection. The running buffer (Fig. 1b) and unused (Fig. 1c) reservoirs were filled with running buffer solution, while the sample reservoir (Fig. 1a) was filled with a sample mixture. The detection reservoir (Fig. 1d) was filled with the running buffer solution. A high voltage was applied to the sample reservoir to facilitate the filling of the injection channel, while the detection reservoir was grounded and all the other reservoirs remained floating. The sample solution was loaded into the separation channel by applying an injection voltage to the sample reservoir for several seconds, while the detection reservoir was grounded and other



Transferring Samples to Chips, Techniques, Figure 1 Operation processes of time-based floating injection. (**a**) sample reservoir, (**b**) running buffer reservoir, (**c**) unused reservoir, (**d**) detection reservoir reservoirs floated. The separation was usually performed by applying a separation voltage to the running buffer reservoir (Fig. 1b) with the detection reservoir grounded and other reservoirs floating. This technique is characterized by ease of control and variation of injected volume and is suitable for continuous and sequential injection for on-line measurements. This approach to sample introduction may suffer from uncontrolled dispersion, resulting in irreproducible injection volumes. The electrokinetic biasing of the sample is another major problem of this method. The injected sample may not be representative of the whole sample. Time-based injections involve applying an electric field to move the sample continuously at a known flow rate, for a given period of time into the reaction or separation channels.

The volume-based sample introduction can be further classified into floating and pinched modes. The volume-based floating injection method applies a high voltage across the sample line only, leaving all the other channels and reservoirs floating. The high voltage is applied to the sample channel (ac) (see Figs. 2a – 2c) to pump the sample solution by EOF to fill the intersections. However, no voltage is applied between reservoirs (b) and (d) so that leakage and migration of the sample solution into the separation channel during injection will occur, resulting in uncontrollable injection volumes. This floating sample introduction technique is quite simple since it only requires one high voltage. When the sample zone passes across the intersection, the sample will migrate toward both (b) and (d) due to the diffusion and eddy effects. Separation can be carried out by switching the electric field to run in the direction of (b) and (d). The sample plug in the intersection will move towards (d) and is separated in the separation channel. To prevent leakage and diffusion of the sample solution, a *pinched* injection method has been developed while an electric field is applied to every channel within the microfluidic chip system. Typically, an electric field (ac) is applied across the sample channel as shown in Fig. 2d, thus moving the sample to fill the intersection. Meanwhile, a lower positive potential will be applied to all the other reservoirs to keep the sample solutions pinched so as to reduce, or preferably eliminate, leakage from the sample into the side channels (see Fig. 2d). And then, the electric field is re-directed so that (d) in Fig. 2d is grounded, with all the other channels positive relative to (d) in Fig. 2d for separation. Jacobson et al. [2] have demonstrated that an improvement in RSD values from 2.7% to 1.7% for a 90-pl injection volume could be obtained using the pinched method compared to that achieved using the floating method. The much higher reproducibility of pinched injection than time-based injection and the minimization of the diffusion/leakage at the intersections offer great promise for microfluidic chips.

Pressure injection is another important technique for transferring samples to microfluidic chips. ►Positive pressure or suction (vacuum) pressure is used to generate a pressure difference to the reservoir on the chips and drives the sample solution into the microchannel. The main advantage of pressure injection over the electrokinetic injection mentioned above is the lack of electric discrimination resulting from the different ion mobilities. But it is unsuitable for gel-filled capillaries. Due to the low dimensions of the micochannels in chips, pumping mechanisms usually lead to high backpressure and the conventional parabolic flow, resulting in band broadening and the dilution of the sample. The amount of sample transferred to the chips has to be calculated, considering the sample viscosity, injection time, and pressure differential. The precision of the injection is difficult to control because the atmospheric conditions and elevation affect the pressure differences and the amount of samples being transferred.

Samples are usually manually loaded into the sample reservoir using standard pipettors and their replacement requires extensive washing. Such manual or automated sample removal limits the sampling rate and is incompatible with the high performance of microchip devices.



Transferring Samples to Chips, Techniques, Figure 2 Operation processes of (**a–c**) volume-based floating injection and (**d**) pinched injection: (**a**) sample reservoir, (**b**) running buffer reservoir, (**c**) unused reservoir, (**d**) detection reservoir

Efficient assays of real-world samples will require the incorporation of a continuous sampling capability (from the external environment) or rapid sampling of multiple discrete samples. Such ability to continuously introduce real samples into micrometer channels would make *Lab-on-a-Chip* devices compatible with real-life applications. Despite various approaches proposed recently for transferring samples to microchips, the "world-to-chip" interface remains a major barrier for real-life applications of microchip devices.

Key Research Findings

Fang et al. [3] have developed a high-throughput continuous sample-transfer interface for microfluidic chip-based capillary electrophoresis systems. A world-to-chip interface has been fabricated based on a novel flow-through sampling reservoir with a guided overflow design. The flow-through reservoir was fabricated on a glass microchip of crossed-channel design used for CE separations. The 20-µl sample reservoir was produced from a plastic pipette tip and fixed at one end of the sampling channel. Sample change was performed by pumping samples, sandwiched between air segments, through the flow-through reservoir, introduced from an access hole on the bottom side of the chip. A filter paper wrapped tightly around the reservoir guided the overflowing sample solution into a plastic trough surrounding the reservoir and then to waste. The feasibility and performance of the novel system was demonstrated by the determination of arginine, glycine, phenylalanine, and glutamic acid, by continuously introducing a train of different samples through the system without electrical interruption. Maximum throughputs of 80/h were achieved with <4.1 % carryover and precisions of 1.5% for arginine and 2.6 % RSD for glycine ($n = 11$) when employing a separation channel of 4 cm (2-cm effective separation length) and a separation voltage of 1.4 kV. The sampling system was tested by continuous monitoring of the derivatization of amino acids over a period of 4 h, involving 166 analytical cycles. There was an outstanding overall precision of 4.8 % RSD ($n = 166$).

Solignac and Gijs [4] have presented a simple capillary electrophoresis microsystem in which the sample is injected hydrodynamically using a pressure pulse. This approach can transfer a sample solution without electric bias, in contrast to a classical electrokinetic injection, in which the magnitude of the electric field in the sample reservoir in combination with variations in electrophoretic mobility can lead to a biased injection. The sample can be loaded using a well controlled and variable pressure pulse (0.1 – 1.0 s) generated by the mechanical actuation of a flexible membrane placed on the sample reservoir of the chip. A fluorescein/calcein-containing borate-tris-hydroxymethylaminoethane (TRIS) sample solution has been taken as a model system for CE analysis. The separation results using pressure pulse injection clearly demonstrate the advantages of this approach. In addition to the reduced bias due to the absence of an electrode in the sample well, this method allows the injection of variable plug volumes by simply changing the pulse length. Figure 3 is a schematic diagram of the cylindrical reservoir used for the pulsed pressure injection. It is identical to a reservoir used with electrodes for electrokinetic pumping, but contains no electrode and is covered by a PDMS membrane that is applied on the top of the reservoir after filling it, but is not firmly bonded to it. This membrane is mechanically actuated with an electromagnet fixed on a linear translation stage. The actuator exerts a mechanical deformation of the membrane (as illustrated in Fig. 3), and provokes a momentary pressure rise within the reservoir. The PDMS membrane provides a good seal with the sample reservoir under pressure. When the membrane is deflected, the pressurized air pushes the liquid in the injection channel. The injection involves small quantities of liquid. The volume flushed into the injection channel is below 0.2 µl, as compared to the 36-µl sample reservoir volume. The pressure is released when the actuator returns to its initial position (after a variable time of 0.1 – 1.0 s) using the backforce of a spring. They purposely used a flexible membrane to avoid or strongly reduce "backsucking" from the injection channel.

Most of the sample-transfer methods for microfluidic chips described above have been used to either inject discrete samples into a separation lane on a microchip or perform repeated injections of a single sample. Between



Transferring Samples to Chips, Techniques, Figure 3 Schematic view of the mechanical actuation of the PDMS membrane on the sample reservoir for a pressure pulse injection. (Reproduced with permission from [4])



Transferring Samples to Chips, Techniques, Figure 4 A novel flow-through sampling design for continuous sampling on an electrophoresis-based microchip, in which electrical voltages are applied to the electrophoretic channels to control sample loading for separation and detection as well as to inhibit sample leakage. (Reproduced with permission from [5])

analyses of different samples, the reservoirs and channels have often been washed manually and new samples have been placed in the sample reservoirs. This has hindered the realization of high throughput even when very fast separations are achieved on microchips. An attempt must be made to match the amount of time it takes to load the samples into the chip with the high-efficiency characteristic of these microchip devices. Various methods have been developed to transfer samples from the macroworld to a microchip in order to improve the separation throughput and achieve continuous analysis. Chen et al. [5] have proposed a method for the operation of a flow-through sampling chip and its application for immuno-separation, as well as its integration with a wash/elution bed for protein purification, concentration, and detection. This novel device used hydrodynamic pressure to drive the sample flow, and a gating voltage was applied to the electrophoretic channel on the microchip to control the sample loading for the separation and to inhibit sample leakage. Figure 4 illustrates the voltage-switching scheme for this sampling microchip. A high positive voltage, regarded as the gating voltage, was applied to reservoir E while reservoirs D and F were grounded (Fig. 4 (a)). Under this voltage scheme, the inlet flow was split at the first intersection and then directed to reservoir D through the second intersection. For sample loading (Fig. 4 (b)), reservoirs D–F were floating for a specified period that determined the amount of sample transferred to the separation channel. For sample separation (Fig. 4 (c)), reservoirs D and F were immediately grounded and the separation voltage was applied to reservoir E to initiate the electrophoretic separation. Use of this device requires optimization of the gating voltage as a function of the hydrodynamic flow rate. The function of the flow-through sampling microchip has been demonstrated by separation of Cy5-labeled bovine serum albumin (Cy5-BSA) and its antibody complex.

Wang et al. [6] have fabricated a novel dual-injection electrophoretic poly(methylmethacrylate) (PMMA) microchip. It consists of two crosses on both sides of the chip and one separation channel. Anions and cations can be injected electrokinetically from both crosses to the separation channel and then be simultaneously separated and detected. A movable contactless conductivity detector was put along the separation channel between the two crosses to detect the ions. The feasibility, utility, and advantage of this new system has been demonstrated by injecting, separating, and detecting ammonium, methyl ammonium, sodium, chloride, nitrate, and perchlorate (six ionic explosives) simultaneously. This versatile chip can also be used to separate anions or cations alone. The simultaneous detection of anionic and cationic explosives and nerve agent degradation products by the newly designed chip has also been demonstrated. The attractive properties of the dual-injection chip will find a wide range of other applications in the life sciences, environmental analysis, etc. Figure 5 shows the electropherograms for a mixture solution containing 2 mM ammonium (a), 1 mM methyl ammonium (b), 1 mM sodium (c), 1 mM chloride (d), 1 mM nitrate (e), and 1 mM perchlorate (f) introduced by cathodic injection (A), anodic injection (B), and dual injection (C). As shown in Fig. 5C, six ions were baseline separated by the dual-injection chip after the simultaneous injection. Electropherograms A and B correspond to the detection of the anions alone (via cathodic injection) and of the cations alone (via anodic injection), respectively. In this case, the injection method was changed from the dual-injection described above. It can be seen that the profiles of the single-injection electropherograms of the anions and cations, shown in Fig. 5 (A and B, respectively), are comparable to the corresponding peaks in the combined dual cathodic/anodic injection response (C). Such a microchip layout is therefore very versatile as it offers three operation modes (i. e., anode, cathode, and dual detection corresponding to measurements of the cations, anions, and both, respectively). The change between these modes can be carried out by simply switching the high voltages.

Chen et al. [7] have developed a new CE system based on a PMMA electrophoretic microchip with an easy sample-introduction interface. One side of the PMMA chip was sharpened to fabricate a sharp inlet tip, allowing rapid and reproducible sample introduction into CE microchip devices coupled to contactless conductivity detection. The new microfluidic interface relies on the use of a sharp sample-inlet tip placed alternately in the sample and buffer vials. This design facilitates the electrokinetic introduction of discrete samples directly into the separation microchannel without the use of injection crosses and allows rapid replacement of different samples. One side of the microchip was cut to leave a separation channel (Fig. 6 (see (d)). The hole (b) near the detection point could accommodate the pipette tip (k), allowing the solution connection between the separation channel (d) and the buffer reservoir (j). A 0.8-mm diameter hole (e) was drilled beside the sharp tip to accommodate the Pt high-voltage electrode (f). Figure 6c shows a photograph of the final PMMA microchip with a sharp inlet tip. The sample solution was introduced into the channel by applying the desired potential between the *sample* vial (i) and the buffer reservoir (j) for 2 s. Subsequently, the inlet tip (Fig. 6 (see (h)) was immersed into the running buffer vial (Fig. 6 (see (g)) and the separation voltage was applied between points (g) and (j) in Fig. 6. The high voltage was commonly applied for 2 s after placing the inlet tip in the sample or buffer vials and was disconnected for 3 s before removing the tip from the corresponding vial. The high voltage was disconnected during sample or running buffer change. The solutions in the vials (Fig. 6 (see (g) and (i)) were retained by the surface tension although the orientation of the vial mouths was horizontal. The new sharp-chip design facilitates the analysis of multiple discrete samples through a simplified electrokinetic introduction of highly reproducible sample zones (Fig. 6). Such introduction is carried out directly in the separation channel (without an injection cross) by alternate placement of the inlet tip in vials containing the sample or buffer solutions. This sample introduction results in the insertion of highly reproducible sample plugs and allows rapid replacement of different samples with no apparent carry carry-over because PMMA is hydrophobic. In the case of high concentration samples, the unwanted sample carry-over can be minimized by immersing the inlet tip (Fig. 6 (see (h)) in



Transferring Samples to Chips, Techniques, Figure 5 Electropherograms for a mixture solution containing 2 mM ammonium (a), 1 mM methyl ammonium (b), 1 mM sodium (c), 1 mM chloride (d), 1 mM nitrate (e), and 1 mM perchlorate (f) introduced by cathodic injection (A), anodic injection (B), and dual injection (C). Operation conditions: separation voltage, +1000 V; injection voltage, +500 V; injection time, 1s; running buffer, 20 mM MES-20 mM His (pH 6.1); sinus waveform with frequency of 200 kHz and a peak-to-peak voltage of 10 V. (Reproduced with permission from [6])



Transferring Samples to Chips, Techniques, Figure 6 (**a**) Top, and (**b**) side view of a PMMA electrophoresis microchip with a sharp-tip inlet (h) and a movable electrode system (c) for the contactless conductivity detection and (**c**) a photograph of the final PMMA microchip with a sharp inlet tip. (a) PMMA chip, (b) hole linked to the buffer solution, (c) movable electrode system, (d) separation channel, (e) hole for the high-voltage power electrode, (f) platinum wire high-voltage electrode, (g) buffer vial, (h) sharp inlet tip, (i) sample solutions vial, (j) buffer reservoir, (k) pipette tip for buffer reservoir, (l) buffer solution. (Reproduced with permission from [6])



Transferring Samples to Chips, Techniques, Figure 7 Electropherograms for a mixtures containing 1mM potassium (a), 1mM sodium (b), and 1mM lithium (c) at the separation of voltages of (A) +500, (B) +1000, (C) +1500, (D) +2000, and (E) +2500V. Also shown (in the inset) are the resulting plots of the dependence of the plate numbers (*N*) of (c) and the resolution (*R*) between (a) and (b) upon the separation voltage. Operation conditions: injection voltage, +1000V; injection time, 2s; running buffer, 20mM boric acid-20mM TRIS (pH 8.0); sinus waveform with a frequency of 200kHz and a peak-to-peak voltage of 5V; electrode distance, 0.8mm; electrode width, 0.8mm. (Reproduced with permission from [6])

a cleaning vial containing the running buffer for 1 – 2 s before placing the tip in the buffer vial (Fig. 6 (see (g)) for the electrophoretic separation. Figure 7 shows the electropherograms for a mixtures containing 1 mM potassium (a), 1 mM sodium (b), and 1 mM lithium (c) at the separation of voltages of (A) +500, (B) +1000, (C) +1500, (D) +2000, and (E) +2500 V by using the sharp tip microchip. As expected, increasing the separation voltage from +500 to +2500 V (A-E) dramatically decreases the migration time, from 99.6 to 21.1 s, from 140.4 to 29.1 s, and from 174.5 to 36.2 s for potassium (a), sodium (b), and lithium (c), respectively. The inset of Fig. 7 shows the effects of the separation voltage upon the plate number (N/m^{-1}) of lithium (c) and the resolution (R) between potassium (a) and sodium (b). The plots for both N and R versus the separation voltage have the similar profiles. Upon raising the separation voltage between +1000 and +2500 V, N and R increase to the maximum values of 44,814 m^{-1} and 2.6 (at +1500) and decrease gradually to 28,005 m^{-1} and 1.8, respectively. Despite the higher separation voltage, flat baselines and low noise levels are maintained even at high separation voltages. Such behavior indicates an effective isolation from the high separation voltage.

Takabayashi et al. [8] have described the development of a microchip for the detection of nitrogen dioxide (NO_2, a gaseous chemical pollutant) in air. A quartz glass microchip has been fabricated for handling the following three functions: gas absorption, chemical reaction, and fluorescence detection. Channels constructed in the microchip were covered with porous glass plates, allowing nitrogen dioxide to penetrate into the triethanolamine (TEA) flowing within the microchannel beneath. The nitrogen dioxide was then mixed with TEA and reacted with a fluorescence reagent in the chemical reaction chamber in the microchip. The reacted solution was then allowed to flow into the fluorescence detection area to be excited by an ultraviolet light-emitting diode, and the fluorescence was detected using a photomultiplier tube. Preliminary studies with standardized test solutions revealed quantitative measurements of nitrite ion (NO_2^-), which corresponded to atmospheric nitrogen dioxide in the range of 10 – 80 ppb.

Kobayashi et al. [9] have developed an efficient system for tri-phase reactions using a microchannel reactor. They conducted hydrogenation reactions that proceeded smoothly to afford the desired products quantitatively within 2 min for a variety of substrates. The hydrogen gas was transferred to the microfluidic channel by pressure and was allowed to interact with the liquid substrates and the solid catalyst. They could achieve an effective interaction between hydrogen, substrates, and a palladium catalyst using the extremely large interfacial areas and the short path required for molecular diffusion in the very narrow channel space. This concept could be extended to other multiphase reactions that use gas-phase reagents such as oxygen and carbon dioxide.

Recently, a glass microimpinger on microchip for gas phase sampling of hydrogen cyanide has been designed and fabricated by Tipple et al. [10]. A microimpinger consisting of a gas sample inlet, gas delivery arms, and an extraction reservoir was fabricated using standard glass microfabrication techniques to extract dilute hydrogen cyanide vapor from a gas delivery system using a basic aqueous trapping buffer. A Teflon membrane was used to contain the liquid sample in the extraction reservoir. The extraction efficiency for sampling the hydrogen cyanide was monitored by forming a fluorescent cyanide isoindole in the reaction of cyanide with naphthalene-2,3-dicarboxaldehyde and taurine. It has been demonstrated that a microfabricated and miniaturized glass impinger could be used as a gas-sampling device on a Lab-on-a-Chip platform. This glass microimpinger relies on the vacuum sampling of gaseous analytes through an extraction solution, much like a traditional impinger. The feasibility and operability of this microimpinger was characterized with regards to hydrogen cyanide vapor sampling. Figure 8 shows the top and side views of the glass microimpinger design. The width and length of the arms extending from the gas sample inlet into the extraction reservoir (Fig. 8 (b)) were 250 μm and 3.5 mm, respectively. These channels were 20 μm deep. The length and width of the gas sample inlet were 6.2 and 3.1 mm, respectively. The small squares shown in the gas sample inlet (353 × 353 μm^2) were intentionally placed in this region to both aid in the further mixing of the diluted cyanide vapor and to provide structural stability to the region during the bonding process. The diameter of the extraction reservoir was 2.10 mm. This diameter and the thickness of the cover plate (5.5 mm) created a reservoir with a total volume of approximately 20 μl.



Transferring Samples to Chips, Techniques, Figure 8 Schematic illustration of the glass microimpinger used in these studies. The upper drawing shows a top view layout of: (a) the gas sample inlet, (b) the impinger arms, and (c) the extraction reservoir. The lower drawing shows the side view and the placement of: (d) the Teflon membrane, and the tubing connections (e) for the vacuum pump, and (f) from the gas delivery system. (Reproduced with permission from [10])

Future Directions for Research

Techniques for transferring samples to microchips play a key role in the microchip-based system. Future directions for sample introduction will focus on the automation of the sample transfer to the microchips, the development of the world-to-chip interface for real-life applications, the integration of the sample pre-treatment unit and sample-introduction interfaces, the direct introduction of ► gaseous samples, and various designs for sample introduction. With the rapid development of microfluidic chips, it is highly desirable to develop new theoretical models, experimental methods, and new experimental devices for transferring samples to chips.

Cross References

- ► Active Mixer
- ► Biosample Preparation Lab-on-a-Chip Devices
- ► Control of Microfluidics
- ► Electrokinetic Sample Injection
- ► Lab-on-Chip Devices for Sample Extraction

- ► Microfluidic Sample Manipulation
- ► Pressure-based Sample Injection
- ► Sample Introduction

References

1. Effenhauser CS, Manz A, Widmer HM (1993) Glass chips for high-speed capillary electrophoresis separations with submicrometer plate heights. Anal Chem 65:2637–2642
2. Jacobson SC, Hergenroder R, Koutny LB, Warmack RJ, Ramsey JM (1994) Effects of injection schemes and column geometry on the performance of microchip electrophoresis devices. Anal Chem 66:1107–1113
3. Fang Q, Xu GM, Fang ZL (2002) A high-throughput continuous sample introduction interface for microfluidic chip-based capillary electrophoresis systems. Anal Chem 74:1223–1231
4. Solignac D, Gijs MAM (2003) Pressure pulse injection: a powerful alternative to electrokinetic sample loading in electrophoresis microchips. Anal Chem 75:1652–1657
5. Chen SH, Y LH, Wang LY, Lin CC, Lee GB (2002) Flow-through sampling for electrophoresis-based microchips and their applications for protein analysis. Anal Chem 74:5146–5153
6. Wang J, Chen G, Muck A, Collins GE (2003) Electrophoretic microchip with dual-opposite injection for simultaneous measurements of anions and cations. Electrophoresis 24:3728–3734
7. Chen Y, Yang PY, Li JH, Chen D, Chen G (2006) Electrophoresis microchips with sharp inlet tips, for contactless conductivity detection, fabricated by in-situ surface polymerization. Anal Bioanal Chem 384:683–691
8. Takabayashi Y, Uemoto M, Aoki K, Odake T, Korenaga T (2006) Development and optimization of a lab-on-a-chip device for the measurement of trace nitrogen dioxide gas in the atmosphere. Analyst 131:573–578
9. Kobayashi J, Mori Y, Okamoto K, Akiyama R, Ueno M, Kitamori T, Kobayashi S (2004) A microfluidic device for conducting gas–liquid–olid hydrogenation reactions. Science 304:1305–1308
10. Tipple CA, Smith M, Collins GE (2005) Development of a microfabricated impinger for on-chip gas phase sampling. Ana Chim Acta 551:9–14

Transitional Microchannels

Cross References

► Boiling and Evaporation in Microchannels

Transitional Nanochannels

Definition

Channels with the smallest passage dimension D between 1 μm and 0.1 μm.

Cross References

► Boiling and Evaporation in Microchannels

Transitional Regime

► Gas Flow in Nanochannels

Transition Flow

► Single-Phase Gaseous Flow

Transition in Microchannels

► Turbulence in Microchannels

Transition to Turbulence in Microchannels

SATISH G. KANDLIKAR
Mechanical Engineering Department, Rochester Institute of Technology, Rochester, NY, USA
sgkeme@rit.edu

Synonyms

Laminar to turbulent flow transition; Critical Reynolds number

Definition

Transition from laminar to turbulent flow is identified by a departure from the laminar flow velocity profile, and the presence of time-varying velocity component in the flow, especially near the wall. The wall shear stress becomes higher following the departure from the laminar flow. The transition occurs over a range of Reynolds number, and is dependent on the local wall and flow conditions. Microchannels are defined as channels with the minimum channel dimension in the range from 1 – 200 μm [1].

Overview

Transition to turbulence is the result of localized flow instabilities. As the Reynolds number increases, these instabilities are set in at the wall. The instabilities are also created as a result of the wall roughness or specific structural features present on the wall, such as grooves, ridges and other roughness elements. At Reynolds numbers below the transition value, the instabilities generated are overcome by the flow inertia, and the *relaminarization* process causes the flow to revert back to laminar flow [2]. At higher Reynolds numbers, the instabilities near the wall are propagated into the flow and transition to turbulent flow occurs. The transition has been linked to the Reynolds number based on the average shear stress Re_τ, [3]:

$$\mathrm{Re}_\tau = \frac{H/2}{\upsilon}\sqrt{\frac{\tau_{\mathrm{w,av}}}{\rho}} > 40 - 60 \qquad (1)$$

Where H is the channel height (the smaller dimension in a rectangular channel), $\tau_{\mathrm{w,av}}$ the average wall shear stress, υ the kinematic viscosity, and ρ the density of the fluid. In internal flows, the laminar to turbulent transition in abrupt entrance rectangular ducts was found to occur at a transition Reynolds number $\mathrm{Re}_\mathrm{t} = 2200$ for an aspect ratio $\alpha_\mathrm{c} = 1$ (square ducts), to $\mathrm{Re}_\mathrm{t} = 2500$ for flow between parallel planes with $\alpha_\mathrm{c} = 0$ [4]. For intermediate channel aspect ratios, a linear interpolation is recommended. For circular tubes, $\mathrm{Re}_\mathrm{t} = 2300$ is suggested. These transition Reynolds number values are obtained from experimental observations in smooth channels in macroscale applications of 3 mm or larger hydraulic diameters. Their applicability to microchannel flows is still an open question.

Basic Methodology

The transition to turbulence is generally identified by conducting experiments to measure local pressure variation along the length of a tube and estimating the local friction factor value. The local friction factor is then used as an indicator of the type of the flow. Transition from laminar to turbulent flow is identified by noting the departure from the laminar flow friction factor values. As the transition sets in, the friction factor increases above the laminar flow value. Care needs to be taken in ascertaining that the entrance region effects are accounted for properly.

Key Research Findings

Although a number of researchers in 1990s have suggested that the transition to turbulence occurs at lower Reynolds numbers, some of the recent experiments conducted under careful conditions [5–7] have shown that for smooth microchannels, the transition Reynolds number remains the same as for the macroscale channels.

The transitions observed at lower Reynolds numbers are due to the presence of roughness on the wall surface. In order to study the effect of roughness on transition to turbulence, a systematic experimental study was conducted by Kandlikar et al. [7]. A test fixture was developed with 10 mm wide channels, and an adjustable gap to allow for different channel sizes. The two side walls were removable, and different surface features could be machined on them. For smooth channels, the transition was noted to occur between $\mathrm{Re}_\mathrm{t} = 2300$ and $\mathrm{Re}_\mathrm{t} = 2500$.



Transition to Turbulence in Microchannels, Figure 1 Geometry of a rough rectangular channel

Different roughness features were introduced by machining ridges onto the walls. As the relative roughness ($=\varepsilon/\mathrm{D}_{\mathrm{h,cf}}$) increased, the transition was observed to occur at lower Reynolds numbers. The hydraulic diameter $\mathrm{D}_{\mathrm{h,cf}}$ was based on the constricted flow dimensions (representing the free flow area in the channel). Thus for a rectangular channel, shown in Fig. 1, with the long walls having a roughness height of ε, the constricted channel height b_{cf} is expressed in terms of the maximum height of the channel from the base of one wall to the base of the other wall, b, by the following equation:

$$b_{\mathrm{cf}} = b - 2\varepsilon \qquad (2)$$

Figure 2 shows the variation of the transition Reynolds number as a function of $\varepsilon/\mathrm{D}_{\mathrm{h,cf}}$. It is observed that for $\varepsilon/\mathrm{D}_{\mathrm{h,cf}} = 0.1$, or 10%, the transition Reynolds number is estimated to be as low 700 [7, 10].

The representation of surface roughness itself is an important subject. Taylor et al. [8] provide a detailed descrip-



Transition to Turbulence in Microchannels, Figure 2 Variation of transition Reynolds number with relative roughness based on constricted flow diameter, adapted from [7, 10] tion of various roughness parameters used to represent the roughness of a surface forming the walls of a channel. The traditional roughness parameter Ra was shown to be inadequate as two surfaces with very different surface features, such as ridge heights and pitches, may yield the same Ra, but their fluid flow performance is entirely different. Further details of the specific roughness parameter can be found in [8] and [9].

Future Directions for Research

Since the channel dimensions in a microchannels are less than 200 μm, a roughness height of only several micrometers results in a relative roughness that is sufficient to cause a departure from the flow in smooth channels. The turbulent flow may be desirable in microchannels to enhance the transport processes, such as heat transfer or mass transfer at the wall. It is therefore possible to design microchannels that can effectively use the higher thermal performance characteristics in the turbulent flow. It is essential to keep a watch on the resulting pressure drop. In general, suitable header design will be able to provide a pressure drop that is within an allowable limit.

Mixing in microchannels in another major application where the transition to turbulent flows can be utilized for enhanced mixing possible in turbulent flows. The roughness elements then act to destabilize the flow and induce local instabilities. The localized transition to turbulence will enhance the mixing, and relaminarization process downstream will provide the laminar flow with its lower friction factor and associated lower pressure drop penalties.

Cross References

- ► Developing Flows
- ► Microfluidic Mixing
- ► Pressure Driven Single Phase Liquid Flows
- ► Roughness Effect on Microscale Transport
- ► Turbulence in Microchannels

References

1. Kandlikar SG, Grande WJ (2003) Evolution of Microchannel Flow Passages – Thermohydraulic Performance and Fabrication Technology. Heat Transf Eng 24(1):3–17
2. Narasimha R, Sreenivasan KR (1979) Relaminarization of Fluid Flows. Advances App Mech 19:221–309
3. Mikic BB, Kapat J, Ratnathicam J (1992) Transition to Turbulence in Systems with Eddy Promoters: Implication for the Question of Transition. Phys Fluids A 4(8):1854–1855
4. Hartnett JP, Koh JCY, McComas ST (1962) A Comparison of Predicted and Measured Friction Factors for Turbulent Flow Through Rectangular Ducts. J Heat Transf 84:82–88
5. Baviere R, Ayela F, Le Person S, Favre-Marinet M (2004) An Experimental Study of Water Flow in Smooth and Rough Rectangular Microchannels, Paper No. ICMM2004-2338, Second International Conference on Microchannels and Minichannels. Rochester, NY, USA pp 221–228
6. Bucci A, Celata GP, Cumo M, Serra E, Zummo G (2004) Water single-phase fluid flow and heat transfer in capillary tubes. Paper No. ICMM2004-2406, Second International Conference on Microchannels and Minichannels, Rochester, NY, USA, pp 221–228
7. Kandlikar SG, Schmitt D, Carrano AL, Taylor JB (2005) Characterization of Surface Roughness Effects on Pressure Drop in Single-phase Flow in Minichannels. Phys Fluids 17(10):100606
8. Taylor JB, Carrano AL, Kandlikar SG (2006) Characterization of the effect of surface roughness and texture on fluid flow – past, present and future. Int J Therm Sciences 45(10):962–968
9. Kandlikar SG, Garimella S, Li D, Colin S, King MR (2005) Flow Boiling in Microchannels and Minichannels. In: Heat Transfer and Fluid Flow in Minichannels and Microchannels. Elsevier, London
10. Brackbill TP, Kandlikar SG (2007) Effect of Sawtooth Roughness on Pressure Drop and Turbulent Transition in Microchannels. To appear in Heat Transf Eng

Translocation of Phosphatidylserine

► Microfluidics for Studies of Apoptosis

Transmission-Line Model

Synonyms

Continuous model; Distributed parameter model

Definition

Models arising from the transmission of energy along a finite distance, traditionally associated with electrical transmission cables, but applicable to energy transfer through materials via acoustics, electromagnetics, or electromechanical means.

Cross References

► Piezoelectric Microdispenser

Transmittance

Definition

Transmission is the term used to describe the process by which incident radiant flux leaves a surface or medium from a side other than the incident side, usually the opposite one. The transmittance is the ratio of the radiant flux after it has traversed a surface or medium to its incident flux, often expressed in percentage.

Cross References

► Lab-on-a-Chip Device for Chemical Analysis

Transport of Droplets by Acoustics

ALI NADIM, JAMES D. STERLING
Keck Graduate Institute, Claremont, CA, USA
nadim@kgi.edu

Synonyms

Acoustic droplet ejection; Acoustic levitation of droplets; Droplet transport by surface acoustic waves; Radiation pressure; Surface acoustic waves; Acoustic particle concentration; Droplet manipulation; Drop on demand

Definition

Transport of droplets by acoustics refers to the use of acoustic or ultrasonic waves in fluids or on solid surfaces to generate, manipulate, position or transport liquid droplets, ranging from picoliters to microliters in volume, surrounded by a gas or immiscible liquid phase and/or attached to a solid surface.

Overview

Acoustic waves in liquids can give rise to so-called radiation pressure forces that can in turn drive acoustic streaming flows, deform fluid–fluid interfaces to generate droplets, or exert levitation forces on suspended drops or particles. This contribution reviews three technologically relevant examples of these effects: acoustic droplet ejection, droplet transport along a solid surface using surface acoustic waves, and acoustic levitation of droplets.

Acoustic droplet ejection refers to the process whereby a focused acoustic beam directed toward a liquid–air interface can cause the ejection of discrete droplets of the liquid. Use of surface acoustic waves (SAW) on a solid upon which sessile droplets are attached can cause the migration of those droplets along the solid surface. Finally, standing acoustic waves in flow channels can be used to exert levitation forces on suspended droplets or particles in the channel, causing them to concentrate along a line, which can be applied to sheathless focusing in flow cytometry.

In order to understand the physical underpinnings of the above processes and to be able to model them mathematically, we begin by providing an overview of the relevant concepts from fluid dynamics and acoustics. This is followed by a separate discussion of each of the above applications.

Basic Methodology

In this section, the equations governing acoustic waves in fluids and surface waves in solids are described and concepts from nonlinear acoustics such as radiation pressure and acoustic streaming are reviewed in order to provide an appropriate framework for modeling and simulation of droplet transport by acoustics.

Governing Equations

The equations that govern acoustic waves in an ideal (inviscid) fluid consist of the conservation of mass and linear momentum equations

$$\frac{\partial \rho}{\partial t} + \nabla \cdot (\rho \boldsymbol{v}) = 0\,, \tag{1}$$

$$\frac{\partial (\rho \boldsymbol{v})}{\partial t} + \nabla \cdot (\rho \boldsymbol{v}\boldsymbol{v}) = -\nabla p\,, \tag{2}$$

in which $\rho(\boldsymbol{x},t)$, $p(\boldsymbol{x},t)$ and $\boldsymbol{v}(\boldsymbol{x},t)$ are the density, pressure and velocity fields, respectively, t is time and $\boldsymbol{x}$ is the position vector. In addition, an equation of state (EOS) that relates the pressure and density fields is needed. Since it is usually the case that the fluid remains isentropic during small-amplitude sound propagation, an adiabatic equation of state is generally assumed, in the form [1]:

$$p - p_0 = Q_0 \left[\left(\frac{\rho}{\rho_0} \right)^{\gamma} - 1 \right], \tag{3}$$

where p_0 and ρ_0 are the base pressure and density, respectively, $Q_0 = \rho_0 c_0^2/\gamma$ and c_0 is the small-signal speed of sound. In an ideal gas, γ is the ratio of the constant-pressure to constant-volume specific heat capacities and $c_0 = \sqrt{\gamma p_0/\rho_0}$, for which Eq. (3) reduces to $p/p_0 = (\rho/\rho_0)^{\gamma}$. For liquids, γ is an empirical parameter and Eq. (3) is known as the Tait equation. For water, $\gamma \approx 7$ and $Q_0 \approx 3000$ bars [1].

Linear Acoustics

Linearization of Eqs. (1)–(3) can be effected by writing the density, pressure and velocity fields as:

$$\rho - \rho_0 = \rho_1 + \rho_2 + \cdots \tag{4}$$

$$p - p_0 = p_1 + p_2 + \cdots \tag{5}$$

$$\boldsymbol{v} = \boldsymbol{v}_1 + \boldsymbol{v}_2 + \cdots \tag{6}$$

in which quantities with subscript ‘1’ are the leading-order perturbations from the base state (referred to as the ‘acoustic’ fields), with quantities having subscript ‘2’ or higher being successively smaller. Note that it is assumed that the fluid in the base state is quiescent, so the leading term in the velocity field is due to the linear acoustic signal.

Substitution of expansions (4)–(6) into the governing conservation equations and the EOS and retention of leading terms results in the equations of linear acoustics in the form:

$$\frac{\partial \rho_1}{\partial t} + \rho_0 \nabla \cdot \boldsymbol{v}_1 = 0\,, \tag{7}$$

$$\rho_0 \frac{\partial \boldsymbol{v}_1}{\partial t} + \nabla p_1 = \boldsymbol{0}\,, \tag{8}$$

$$p_1 = c_0^2 \rho_1\,. \tag{9}$$

Upon taking the partial time derivative of Eq. (7), subtracting the divergence of Eq. (8) from the result and making use of the linearized equation of state (9), the acoustic pressure field is seen to satisfy the linear wave equation:

$$\frac{\partial^2 p_1}{\partial t^2} = c_0^2 \nabla^2 p_1\,. \tag{10}$$

Indeed, the same equation is also satisfied by the density field ρ_1, the velocity field $\boldsymbol{v}_1$ and the velocity potential ϕ_1. The latter may be introduced by noting that for irrotational flows where $\nabla \times \boldsymbol{v} = \boldsymbol{0}$, the velocity derives from a potential: $\boldsymbol{v} = \nabla\phi$.

In the framework of linear acoustics, one can also derive an equation for conservation of *acoustic energy* which involves quadratic terms in the primary acoustic disturbances. That equation is given by [2]:

$$\frac{\partial w}{\partial t} + \nabla \cdot \boldsymbol{I} = 0\,, \tag{11}$$

where the acoustic energy density w and the acoustic intensity vector $\boldsymbol{I}$ are given by

$$w = \frac{p_1^2}{2\rho_0 c_0^2} + \frac{\rho_0 \boldsymbol{v}_1^2}{2}\,, \qquad \boldsymbol{I} = p_1 \boldsymbol{v}_1\,, \tag{12}$$

in which $\boldsymbol{v}_1^2 = \boldsymbol{v}_1 \cdot \boldsymbol{v}_1$.

Plane Waves

Starting with the equations of linear acoustics, useful relationships among the variables can be obtained for the case of so-called plane waves [2] propagating in infinite space in a particular direction. If the unit vector in the direction of plane wave propagation is denoted by $\hat{\boldsymbol{n}}$, with the acoustic pressure field of the plane wave given by

$$p_1(\boldsymbol{x}, t) = f(t - \hat{\boldsymbol{n}} \cdot \boldsymbol{x}/c_0)\,, \tag{13}$$

the acoustic velocity and density fields would then be given by [2]:

$$\boldsymbol{v}_1 = \hat{\boldsymbol{n}} \frac{p_1}{\rho_0 c_0}\,, \qquad \rho_1 = \frac{p_1}{c_0^2}\,. \tag{14}$$

Note that f can be an arbitrary function of its scalar argument and the above would satisfy the equations of linear acoustics. For instance, for propagation along the x-direction in a Cartesian coordinate system, right-going pressure waves of the form $p_1 = f(x - c_0 t)$ produce a velocity of the form $\boldsymbol{v}_1 = \hat{\boldsymbol{i}}\, p_1/(\rho_0 c_0)$, whereas left-going pressure waves of the form $p_1 = g(x + c_0 t)$ lead to the velocity $\boldsymbol{v}_1 = -\hat{\boldsymbol{i}} p_1/(\rho_0 c_0)$. Here, $\hat{\boldsymbol{i}}$ is the unit vector in the increasing x direction. This becomes an important distinction when the problem of reflection and transmission of a wave across an interface between two media is considered. It is also seen that the product of fluid density and sound speed, $\rho_0 c_0$, provides the proportionality between pressure and speed. This combination occurs frequently in acoustics and is known as the *acoustic impedance*.

The acoustic energy density and intensity vector for a plane wave are given by

$$w = \rho_0 \boldsymbol{v}_1^2 = \frac{p_1^2}{\rho_0 c_0^2}\,, \qquad \boldsymbol{I} = \hat{\boldsymbol{n}} \frac{p_1^2}{\rho_0 c_0} = \hat{\boldsymbol{n}}\, c_0 w\,. \tag{15}$$

Radiation Pressure

Acoustic waves in fluids are often characterized by time-periodic oscillations of a given radian frequency $\omega = 2\pi f$ (with f the frequency in cycles per unit time) at any given point in space. As such, time-averages over one period of the oscillation $T = 2\pi/\omega = f^{-1}$ of linear quantities are zero, whereas averages of quadratic quantities over time produce non-zero means. Denoting the time-average over one period by $\langle\cdot\rangle$ and applying this operator to the original momentum conservation equation (2) yields [1]:

T

$$\nabla \cdot \Pi = \boldsymbol{0}\,, \tag{16}$$

where Π is the acoustic radiation stress tensor

$$\Pi = -\langle p\rangle\, \boldsymbol{\delta} - \langle \rho \boldsymbol{v}\boldsymbol{v}\rangle \approx -\langle p - p_0\rangle\, \boldsymbol{\delta} - \rho_0 \langle \boldsymbol{v}\boldsymbol{v}\rangle\,. \tag{17}$$

To arrive at these results, we have noted that the time-average of the leading partial time-derivative in Eq. (2) is zero and that, since the velocity field is already a first-order quantity (with the base state being one of zero flow), the acoustic stress is correct to second order as written on the far right-hand side of Eq. (17). Here, $\boldsymbol{\delta}$

denotes the unit isotropic tensor of rank two whose components in a Cartesian system are given by the Kronecker delta symbol δ_{ij}. That is, in component form, $\Pi_{ij} = -\langle p - p_0 \rangle \delta_{ij} - \rho_0 \langle v_i v_j \rangle$.

The quantity $\langle p - p_0 \rangle$ in Eq. (17) is the *mean excess pressure* and in general, it is nonzero for finite amplitude waves. It is also an *Eulerian* quantity since the time-averaging is being performed at a fixed position in space. Wang and Lee [1] provide a succinct derivation for the value of this Eulerian mean excess pressure, correct to second order but expressed in terms of first-order quantities, in the form:

$$\left\langle p^{\mathrm{E}} - p \right\rangle = \frac{1}{2\rho_0 c_0^2} \left\langle p_1^2 \right\rangle - \frac{1}{2} \rho_0 \left\langle v_1^2 \right\rangle + C$$

$$= \langle V \rangle - \langle K \rangle + C \,. \tag{18}$$

The superscript 'E' is affixed to pressure as a reminder of its Eulerian nature, and $\langle V \rangle = \left\langle p_1^2 \right\rangle / 2\rho_0 c_0^2$ and $\langle K \rangle = \rho_0 \left\langle v_1^2 \right\rangle / 2$ are the time-averaged potential and kinetic energy densities, respectively. Constant C is independent of both space and time; in linear acoustics it is zero, but at second order, it is sometimes needed to satisfy a constraint such as constancy of total mass or the condition of having no perturbation at infinity.

One can also calculate a *Lagrangian* mean excess pressure by time-averaging the pressure of a material fluid particle which oscillates in space during the passage of the acoustic wave. That pressure, designated by superscript 'L', can be shown to take the form [1]:

$$\left\langle p^{\mathrm{L}} - p \right\rangle = \langle V \rangle + \langle K \rangle + C = \langle w \rangle + C \,, \tag{19}$$

where the acoustic energy density w is defined in Eq. (12).



Transport of Droplets by Acoustics, Figure 1 Schematic representation of launching of plane waves in a fluid by small-amplitude traveling flexural waves on a wall. The flexural wave speed c_{W} must be supersonic with respect to the speed of sound c_0 in the fluid for such plane waves to be generated. If the flexural wave is subsonic, the disturbance dies out exponentially with y

Wang and Lee [1] define the so-called Langevin and Rayleigh radiation pressures, respectively, as the mean excess pressures that either depend upon the sound wave only (i. e., with $C = 0$), or on the sound wave together with a constraint which determines the constant C that contributes to the pressure. The concept of the radiation pressure enables the calculation of forces acting upon material surfaces, such as an interface between two fluids or the surface of a particle or a drop in a sound field. Strictly speaking, one should use the acoustic radiation stress tensor Π to calculate such forces. However, in many situations, such as when the surface is rigid or when the velocity at a surface is normal to that surface, it is convenient to use the radiation pressure rather than the full stress.

Sound Radiated by Traveling Flexural Waves

Following Pierce [2] and referring to Fig. 1, consider an infinite plane wall situated at $y = 0$, the region above which (i. e., $y > 0$) is occupied by a fluid with sound speed c_0. Suppose that the wall is undergoing small-amplitude transverse vibrations in the form of a traveling wave that propagates in the positive x-direction, parallel to the wall. In other words, suppose the normal displacement of points on the wall to be of the form $\eta(x, t) = \eta(t - x/c_{\mathrm{W}})$, where c_{W} is the speed of the flexural wave along the wall. The normal velocity of points on the wall is thus given by $v_{\mathrm{W}}(t - x/c_{\mathrm{W}}) = \partial\eta/\partial t$. We consider the limit when $|v_{\mathrm{W}}| \ll c_0$.

The nature of the acoustic disturbance generated in the fluid depends critically upon whether the flexural wave speed is subsonic ($c_{\mathrm{W}} < c_0$) or supersonic ($c_{\mathrm{W}} > c_0$) with respect to the sound speed in the fluid. In the subsonic case, the disturbance in the fluid (generated by constant-frequency excitation of the wall) dies out exponentially with distance y from the surface. On the other hand, when the flexural waves are supersonic relative to the fluid sound speed, plane waves are launched in the fluid at some angle relative with the wall or the vertical. To see this, consider a plane pressure wave in the fluid that propagates in the direction of a unit normal $\hat{\boldsymbol{n}}$. The pressure field for such a wave is taken to be of the form given by Eq. (13), $p_1(\boldsymbol{x}, t) = f(t - \hat{\boldsymbol{n}} \cdot \boldsymbol{x}/c_0)$, satisfying the linear wave equation. The fluid velocity field is therefore given by Eq. (14). Let θ denote the angle between the direction of propagation $\hat{\boldsymbol{n}}$ and the y-axis, as identified in Fig. 1, so that unit vector $\hat{\boldsymbol{n}}$ can be expressed as $\hat{\boldsymbol{n}} = \sin(\theta)\hat{\boldsymbol{i}} + \cos(\theta)\hat{\boldsymbol{j}}$, with $\hat{\boldsymbol{i}}$ and $\hat{\boldsymbol{j}}$ the unit vectors parallel to the x- and y-axes. The y-component of the fluid velocity at the wall is thus given by $\hat{\boldsymbol{j}} \cdot \boldsymbol{v}_1 \Big|_{y=0} = \cos(\theta)(\rho_0 c_0)^{-1} f(t - \sin(\theta)x/c_0)$. This must match the wall velocity that is given by $v_{\mathrm{W}}(t - x/c_{\mathrm{W}})$. One thus finds the relationships:

$$\sin(\theta) = \frac{c_0}{c_\mathrm{w}}\,, \quad f(t) = \frac{\rho_0 c_0}{\cos(\theta)} \boldsymbol{v}_\mathrm{w}(t)\,, \tag{20}$$

valid in the supersonic regime $c_\mathrm{w} > c_0$. That is, the sine of the propagation angle of the plane waves relative to the vertical direction is given by the ratio of the fluid sound speed to the speed of the flexural waves, and the amplitude and functional form of the pressure of the plane waves in the fluid are determined by the functional form of the transverse velocity of the material points on the wall.

The intensity vector of the radiated plane wave in the fluid, which is a measure of the acoustic energy flux carried by the waves, is given by

$$\boldsymbol{I} = \hat{\boldsymbol{n}} \frac{\rho_0 c_0}{\cos^2(\theta)} \left[\boldsymbol{v}_\mathrm{w}(t - \hat{\boldsymbol{n}} \cdot \boldsymbol{x}/c_0)\right]^2 . \tag{21}$$

Note that if c_w decreases toward c_0, θ tends to $\frac{\pi}{2}$ and the direction of propagation becomes parallel to the wall. In that limit, $\cos(\theta) \to 0$ and the radiated acoustic power tends to infinity. This limit cannot be realized because generation of such acoustic waves in the fluid will rapidly deplete the vibrational energy of any such flexural waves [2].

Key Research Findings

We now apply the fundamental concepts outlined above to three specific examples that are relevant to the topic of droplet transport by acoustics; namely, acoustic droplet ejection, droplet transport along a solid surface using surface acoustic waves, and acoustic levitation of droplets.

Acoustic Droplet Ejection

When a focused acoustic beam is directed toward a liquid–air interface from the liquid side, it can cause the ejection of discrete droplets of the liquid that can then be captured by or deposited onto other surfaces. This is shown schematically in Fig. 2. This acoustic droplet ejection (ADE) method and multiple patents based thereupon are the technological basis for the company Labcyte Inc. (Sunnyvale, CA) which uses it for dispensing and liquid handling directed at high-throughput applications [4]. A variety of liquid solvents, containing DNA, proteins, or live cells can be dispensed without loss of activity, at varying volumes ranging from picoliters to microliters.

To model this process, it is instructive to consider first the reflection of a plane wave from a fluid-fluid interface at normal incidence. To this end, we follow a procedure similar to Lighthill [3] who treats the general problem of transmission of waves through junctions. Suppose the interface between the fluids is located at $x = 0$, with the fluid on the left having properties ρ_0 and c_0, while the one on the right has properties $\hat{\boldsymbol{\rho}}_0$ and $\hat{\boldsymbol{c}}_0$. We will affix a caret to quantities that pertain to the fluid on the right. Consider an incident (i. e., right-going) pressure wave in the left fluid given by $p_{1i} = f(t - x/c_0)$. The reflected wave will be a left-going wave of the form $p_{1r} = g(t + x/c_0)$, with the total pressure wave in fluid 1 being the sum of the incident and reflected waves: $p_1 = f(t - x/c_0) + g(t + x/c_0)$. The transmitted wave in the right fluid will be a right-going wave given by $\hat{\boldsymbol{p}}_1 = h(t - x/\hat{c}_0)$. Using the plane-wave relations, the x-velocities in the two fluids are then given by $v_1 = (\rho_0 c_0)^{-1}[f(t - x/c_0) - g(t + x/c_0)]$ and $\hat{\boldsymbol{v}}_1 = (\hat{\boldsymbol{\rho}}_0 \hat{\boldsymbol{c}}_0)^{-1} h(t - x/\hat{\boldsymbol{c}}_0)$. On equating the pressure and velocities at the interface $x = 0$ we find:

$$f(t) + g(t) = h(t) \tag{22}$$

$$(\rho_0 c_0)^{-1}[f(t) - g(t)] = (\hat{\boldsymbol{\rho}}_0 \hat{\boldsymbol{c}}_0)^{-1} h(t)\,. \tag{23}$$

Equations (22) and (23) can be solved for the waveforms of the reflected and transmitted waves, $g(t)$ and $h(t)$, in terms of the waveform of the incident wave $f(t)$ and the ratio $Z = \hat{\boldsymbol{\rho}}_0 \hat{\boldsymbol{c}}_0 / \rho_0 c_0$ of the impedances of the two fluids. The result is that:

$$g(t) = \frac{Z-1}{Z+1} f(t)\,, \quad h(t) = \frac{2Z}{Z+1} f(t)\,. \tag{24}$$

Lighthill [3] points out that for plane wave transmission in channels and tubes, one should actually account for the cross-sectional area change at junctions as well. That is, rather than equating the velocities of the two fluids at junctions, the volumetric flow rates should be equated. For infinite plane waves, our treatment is accurate. If the two fluids have equal impedances so that $Z = 1$, there is no reflected wave ($g(t) = 0$) and the transmitted wave is identical to the incident wave ($h(t) = f(t)$). On the other hand, if the impedance in the right fluid is much less than that



Transport of Droplets by Acoustics, Figure 2 Acoustic droplet ejection of the left fluid, so that $Z \approx 0$, there will be no transmitted wave ($h(t) \approx 0$) and the reflected waveform is given by $g(t) \approx -f(t)$. This corresponds to the case of waves in water reflecting from a water–air interface, since air has a much lower density and sound-speed (and therefore impedance) than water. Such an interface is often referred to as a pressure–release surface [2] since the pressure at such a perfectly-reflecting interface turns out to be zero.

Now suppose that the incident wave is actually of the form

$$p_{1i} = \mathrm{Re}\left\{A\, e^{i(kx-\omega t)}\right\}, \tag{25}$$

corresponding to a sinusoidal wave of radian frequency ω and wavenumber k (or wavelength $\lambda = 2\pi/k$), with complex amplitude A. Note that the wavenumber and frequency are related by $\omega/k = c_0$. Here Re denotes the real part of its complex argument. Upon incidence on a pressure-release surface, the reflected wave is thus given by

$$p_{1r} = -\,\mathrm{Re}\left\{A e^{i(-kx-\omega t)}\right\}, \tag{26}$$

which, when added to the incident wave, produces a standing wave of the form:

$$p_1 = 2|A|\cos(\omega t)\sin(kx)\,, \tag{27}$$

to within an arbitrary shift of the time axis. The corresponding density and velocity fields are then given by

$$\rho_1 = \frac{2|A|}{c_0^2}\cos(\omega t)\sin(kx)\,, \tag{28}$$

$$\boldsymbol{v}_1 = \frac{-2|A|}{\rho_0 c_0}\sin(\omega t)\cos(kx)\hat{\boldsymbol{i}}\,, \tag{29}$$

and the time-averaged acoustic energy density turns out to be

$$\langle w\rangle = \frac{|A|^2}{\rho_0 c_0^2}\,. \tag{30}$$

The Langevin radiation pressure on the interface, given by Eq. (19) with $C = 0$, is therefore also given by

$$\left\langle p^{\mathrm{L}} - p_0\right\rangle = \frac{|A|^2}{\rho_0 c_0^2}\,. \tag{31}$$

Wang and Lee [1] provide the corresponding results for a plane wave incident on an interface separating fluids whose impedance ratio is Z, as defined above. The difference in the Lagrangian mean excess pressure across the interface is then

$$\left\langle p^{\mathrm{L}} - \hat{p}^{\mathrm{L}}\right\rangle = \frac{|A|^2}{\rho_0 c_0^2}\frac{(1+Z^2-2nZ)}{(1+Z)^2}\,. \tag{32}$$

Here $n = c_0/\hat{c}_0$ is the ratio of the wave speeds in the two media. They also provide more general expressions for the case of sound *beams* (rather than plane waves) that are approximated by a one-term Fourier–Bessel series, having both a radial and an axial wave number. The radiation pressure difference (32) at the interface is said to explain the *acoustic fountain* effect where the directed sound beam creates a liquid jet.

Starting with the radiation pressure of a focused acoustic beam at an interface, Elrod et al. [5] have used useful scaling arguments to characterize the acoustic droplet ejection process as a function of pulse energy and frequency. Their model of the ejection considers an initial expulsion of a roughly cylindrical volume of fluid (as depicted on the right side of Fig. 2) due to the impulse (or momentum) imparted to the interface by the focused acoustic beam. The beam is assumed to be on for a time T which is long compared to the period of the wave, $1/f$, but short compared to the time-scale for the dynamics of the liquid. Focused beams are characterized by the diameter D of the focal spot and axial length L which measures the depth of focus. For an acoustic lens with an F-number of roughly unity, both D and L scale with the wavelength $\lambda = c_0/f$ of the sound wave. Not surprisingly, the diameter of the drop that is finally ejected also scales linearly with the wavelength λ or the reciprocal of the frequency: $D \propto c_0/f$. These same length scales D and L are used to estimate the volume of the cylinder of fluid that is expelled. The volume therefore scales with the cube of the wavelength, or $(c_0/f)^3$. The impulse M delivered to that volume is proportional to the product of the radiation pressure, given by Eq. (31), with the cross-sectional area of the beam, and the time-duration of the pulse, T:

$$M \propto \frac{|A|^2 T\lambda^2}{\rho_0 c_0^2} = \langle w\rangle\, T\lambda^2 = \frac{\left\langle \hat{\boldsymbol{n}}\cdot\boldsymbol{I}\right\rangle T\lambda^2}{c_0} \propto \frac{E}{c_0}\,. \tag{33}$$

Here, as in [5], we have identified the incident energy pulse E as the product of the acoustic intensity (see Eq. (15)) with the pulse duration and cross-sectional area. This represents the total energy delivered by the beam while it is on. Equating the impulse to the initial momentum of the ejected cylinder, one finds the scaling for the initial velocity

$$U_{\text{init}} \propto \frac{M}{\rho_0 \lambda^3} \propto \frac{Ef^3}{\rho_0 c_0^4}\,. \tag{34}$$

The initial velocity of the jet appears to scale linearly with the total pulse energy and with the third power of the acoustic frequency.

As the liquid column is ejected with the above initial velocity due to the impulse delivered by the sound beam, it is continually acted upon by the surface tension σ of the liquid which pulls it downward toward the main liquid bath with a force given by the product of σ with the circumference of the circular cross section of the cylinder $\pi D \propto \lambda$ (see Fig. 2). This constant force decelerates the column until it comes to rest at time

$$t_{\text{rise}} \propto \frac{Ef}{c_0^2 \sigma}\,, \tag{35}$$

having reached the height

$$h_{\text{rise}} \propto \frac{E^2 f^4}{\rho_0 c_0^6 \sigma}\,. \tag{36}$$

Whether or not a drop can pinch off during this time depends upon the time-scale for the growth of Rayleigh-Plateau instability on a liquid column, which is given by

$$t_{\text{RP}} \propto \left(\frac{\rho_0 \lambda^3}{\sigma}\right)^{\frac{1}{2}} = \left(\frac{\rho_0 c_0^3}{\sigma f^3}\right)^{\frac{1}{2}}, \tag{37}$$

exhibiting a frequency dependence of $f^{-3/2}$. If the pinch-off time is less than the rise time, a drop can be ejected from the column due to the development of the Rayleigh instability before it returns to the main liquid bath below by the pulling action of surface tension.

Elrod et al. [5] have provided most of the above scaling laws, but have not made use of the fact that a threshold energy for droplet ejection can be obtained by requiring that

$$t_{\text{RP}} < t_{\text{rise}}\,, \tag{38}$$

so that the drop pinch-off due to Rayleigh-Plateau instability can occur prior to the column returning to the bath. The threshold energy is thus found to be:

$$E > \frac{\rho_0^{\frac{1}{2}} c_0^{\frac{7}{2}} \sigma^{\frac{1}{2}}}{f^{\frac{5}{2}}}\,. \tag{39}$$

The $f^{-5/2}$ frequency dependence is consistent with experimental observations reported in [5] for which a least-squares fit provides a dependence of the form $f^{-2.3\pm0.2}$. Typical magnitudes for water droplet ejection using a 5 MHz focused beam include a drop of approximately one wavelength in diameter ($\lambda \approx 300\,\mu$m) and a threshold energy in the range of tens of microjoules [5]. Interestingly, most of the energy in the wave is reflected as the interfacial and kinetic energies of the resulting drop are in the nanojoule range [5]. The characteristic time (37) for the Rayleigh instability to lead to droplet pinch-off is hundreds of microseconds, whereas the acoustic pulse used to generated the droplet lasts approximately 20 microseconds, in accordance with the view that the effect of the acoustic beam can be modeled as delivering an initial impulse to the liquid.

A more recent study of droplet ejection from small micromachined nozzles is provided in [6]. The acoustic droplet ejection method has found applications in photoresist deposition and matrix-assisted laser desorption ionization (MALDI) analysis [4], among others.

Droplet Transport by Surface Acoustic Waves

A recent application of acoustics to droplet transport has been through the use of surface acoustic waves (SAW) to move sessile droplets attached to a solid surface [7–9]. The physical basis for this process has been described in simple terms as follows. When a SAW propagating along a surface encounters a liquid drop, as depicted in Fig. 3, by the mechanism described earlier where flexural waves on a solid launch acoustic waves in the surrounding fluid, they launch plane waves at an angle given by Eq. (20) on the side of the liquid drop that they first encounter. The SAW and the corresponding acoustic waves that they generate in the drop diminish rapidly as one moves away from the leading edge of the drop. The acoustic field thus generated within the drop produces a radiation pressure distribution on the drop interface that tends to deform the drop and modify the contact angles at the leading and trailing edges of the drop. Also, mediated by an effect known as acoustic streaming, an internal flow field is generated within the



Transport of Droplets by Acoustics, Figure 3 Droplet transport by surface acoustic waves drop that leads to its translational motion parallel to the direction of the original SAW. Typical droplet volumes that are actuated by this effect are tens of nanoliters, although smaller volumes (tens of picoliters) can be left behind on appropriately patterned surfaces as the larger drops move along.

In references [7–9] that describe this phenomenon, the SAW is generated on a piezoelectric substrate with interdigital gold transducers. Typical values of the SAW frequencies and wavelengths are in 100 s of MHz and 10 s of μm, respectively, with the surface wave velocity c_w in the range $3000-4000\,\mathrm{m/s}$. The amplitude of the waves is said to be in the nanometer range. An order of magnitude analysis can be used to estimate characteristic values of the wave amplitudes that can be established in the droplet. Using an SAW velocity of $c_\mathrm{w} = 3000\,\mathrm{m/s}$ and frequency of $f = 100\,\mathrm{MHz}$ provides an SAW wavelength of 30 microns. If we take the amplitude of the wave to be $\varepsilon = 1$ nanometer, the amplitude of the plane pressure waves that get launched in the liquid is estimated to be

$$\frac{2\pi f \varepsilon \rho_0 c_0}{\sqrt{1-(c_0/c_\mathrm{w})^2}} \approx 10^6\,\mathrm{Pa}$$

or about 10 atmospheres. The energy density w of such waves (cf. Eqs. (12) and (15)) is approximately $500\,\mathrm{J/m^3}$ or 500 Pa, however. Based on Eq. (19), this is also the approximate magnitude of the radiation pressure that would act upon the droplet interface.

Although a detailed analysis of the flow field within the sessile drops has not been carried out, the coupling between the SAW and the liquid via the oblique plane waves that are launched in the liquid is thought to give rise to acoustic streaming within the droplets or other bulk liquids that are in contact with the solid surface [7–9]. Acoustic streaming refers to nonzero time-averaged bulk flows that result in fluids under the influence of primarily time-periodic acoustic waves [10]. Since time-periodic quantities arising form linear acoustic disturbances have a zero mean, acoustic streaming, like the radiation pressure effect, is based upon nonzero averages of quadratically nonlinear terms. One also needs to include viscous effects in the description. Thus, the divergence of the viscous stress, $\nabla \cdot \tau$, is first added to the right-hand side of the conservation of momentum equation (2). Here, $\tau = \mu[\frac{1}{2}(\nabla \boldsymbol{v} + \nabla \boldsymbol{v}^\dagger) - \frac{1}{3}\boldsymbol{\delta}(\nabla \cdot \boldsymbol{v})] + \kappa \boldsymbol{\delta}(\nabla \cdot \boldsymbol{v})$, with μ the shear viscosity of the fluid and κ its dilatational or bulk viscosity. Upon time-averaging the resulting momentum equation and ignoring the dilatational terms that contain $\nabla \cdot \boldsymbol{v}$, one obtains the analog of Stokes equations for the time-averaged quantities, but with an effective body force term, in the form [10]:

$$\nabla \langle p \rangle - \mu \nabla^2 \langle \boldsymbol{v} \rangle = F_e \,. \tag{40}$$

Since acoustic fields p_1 and $\boldsymbol{v}_1$ generally have zero time-averages, the averaged quantities appearing in Eq. (40) could be regarded as being the averages of p_2 and $\boldsymbol{v}_2$ in the series expansions (5) and (6). The effective force, however, involves averages of quadratically nonlinear terms in the first-order quantities, namely

$$F_e = -\nabla \cdot \langle \rho \boldsymbol{v}\boldsymbol{v} \rangle \approx -\nabla \cdot \langle \rho_0 \boldsymbol{v}_1 \boldsymbol{v}_1 \rangle \,. \tag{41}$$

Thus, to analyze acoustic streaming, one must first solve the equations of linear acoustics to obtain the first-order fields. This is followed by the calculation of the effective body force (41) and the solution of the Stokes equation (40) for the time-averaged streaming flow, driven by the effective force. Guttenberg et al. [7] have carried out such an analysis to investigate pumping in a capillary gap driven by SAW.

Acoustic Levitation

In a standing pressure wave characterized by time-periodic acoustic pressure and velocity fields $p_1(\boldsymbol{x}, t)$ and $\boldsymbol{v}_1(\boldsymbol{x}, t)$, consider a spherical droplet of radius R (small compared to the acoustic wavelength) to be located at a given position in space. Upon calculating the scattered acoustic field in the vicinity of the droplet and the resulting radiation pressure acting on its interface, a net force is found to be acting on the drop, obtained via integration of the product of the radiation pressure and the inward-pointing unit normal vector on the entire drop surface. A convenient way to express this acoustic levitation force, F, is in terms of the negative gradient of a potential energy function U, i. e., $F = -\nabla U$, with the potential energy field given by

$$U = 2\pi R^3 \left[\frac{g_1}{3\rho_0 c_0^2} \left\langle p_1^2 \right\rangle - \frac{g_2 \rho_0}{2} \langle \boldsymbol{v}_1 \cdot \boldsymbol{v}_1 \rangle \right] . \tag{42}$$

This result, which is due to Gor'kov (1962), is reviewed in [1] and [11]. The angular brackets denote the time-averages of their arguments at a fixed position in space and dimensionless functions g_1 and g_2 are related to the ratios of the properties of the droplet phase and those of the external fluid. In particular, with $\Lambda = \hat{\boldsymbol{\rho}}_0/\rho_0$ and $\Sigma = \hat{\boldsymbol{c}}_0/c_0$ respectively representing the density ratio and sound speed ratio of the droplet phase (identified with a caret) to the external fluid, these functions are given by

$$g_1 = 1 - \frac{1}{\Lambda \Sigma^2} \tag{43}$$

$$g_2 = \frac{2(\Lambda - 1)}{2\Lambda + 1}\,. \tag{44}$$

For instance, if in the absence of the droplet, there exists a standing pressure wave of the form: $p_1 = A\sin(kz)$ $\cos(\omega t)$, for which a pressure node is located at $z = 0$, when the droplet center is located at $z = Z$, it experiences the force:

$$F_z(Z) = -\frac{\pi A^2 kR^3}{\rho_0 c_0^2}\left[\frac{g_1}{3} + \frac{g_2}{2}\right]\sin(2kZ)\,. \tag{45}$$

This force can drive the droplet toward the nodes or the antinodes of the standing wave, depending upon the sign of the factor $g_1/3 + g_2/2$ which in turn depends on the properties of the two fluids. When that factor is positive, the droplets move toward the nodes.

As an application of this effect, a number of recent papers [12–14] have demonstrated and analyzed the potential for concentrating aerosol droplets in cylindrical cavities and for sheathless focusing of particles in a flow cell for subsequent interrogation and sorting. The concentrators are constructed from piezoelectric materials or consist of flow cells that are gel-coupled to piezoelectric transducers and driven at or near resonance modes. Slight modifications to the cavity geometry have been found to have significant impact on the precise positioning of the particles or droplets. The modeling efforts in this area generally require determination of the radiation potential U for the given channel/cavity geometry and investigating the effects of symmetry-breaking changes to the geometry on the radiation potential in order to predict the degree of localization of the particles. The application to sheathless focusing [13] is particularly promising for the development of Lab-on-Chip flow cytometry systems.

Future Directions for Research

There are a number of open problems that can be treated using the modeling principles that have been summarized above. For instance, in the problem of transport of sessile droplets by surface acoustic waves, a detailed understanding of the internal flow within the droplet has not yet emerged. Nor are there simple scaling laws that design engineers can use to predict the speed of droplet motion as a function of the surface wave characteristics and droplet size and physical properties. In acoustic droplet ejection, one can anticipate more detailed computational studies of the droplet pinch-off process using boundary integral methods, initiated in [5], and more sophisticated numerical techniques for multiphase flow systems with interfaces, e. g., the level-set method [15]. The same techniques can also be applied to the problem of acoustic levitation of droplets in order to gain a better understanding of the deformed shapes of levitated droplets [16] or their shape mode oscillations.

Cross References

- ▶ Acoustic Streaming
- ▶ Boundary Element Method and its Application to the Modelling of MEMS Devices
- ▶ Digital Microfluidics
- ▶ Droplet Based Lab-on-Chip Devices
- ▶ Droplet Dispensing
- ▶ Flow Cytometer Lab-on-Chip Devices
- ▶ Flows Driven by Surface Acoustic Waves
- ▶ Interface Capturing Schemes for Free-Surface Flows
- ▶ Interface Tracking Schemes for Free-Surface Flows
- ▶ Interfacial Instability
- ▶ Microfluidic Mixing
- ▶ Supersonic Micro-Nozzles
- ▶ Piezoelectric Microdispenser
- ▶ Surface Tension, Capillarity and Contact Angle
- ▶ Ultrasonic Machining
- ▶ Ultrasonic Pumps

References

1. Wang TG, Lee CP (1998) Radiation Pressure and Acoustic Levitation. In: Hamilton MF, Blackstock DT (eds) Nonlinear Acoustics. Academic, San Diego, pp 177–205
2. Pierce AD (1989) Acoustics: An Introduction to Its Physical Principles and Applications. Acoustical Society of America, Woodbury
3. Lighthill J (1978) Waves in Fluids. Cambridge University Press, Cambridge
4. Papen R, Ellson RN, Olechno J (2004) Sound Effects. Am Lab 36(24):26–30
5. Elrod SA, Hadimioglu B, Khuri-Yakub BT, Rawson EG, Richley E, Quate CF, Mansour NN, Lundgren TS (1989) Nozzleless Droplet Formation with Focused Acoustic Beams. J Appl Phys 65:3441–3447
6. Meacham JM, Varady MJ, Degertekin FL, Fedorov AG (2005) Droplet Formation and Ejection from a Micromachined Ultrasonic Droplet Generator: Visualization and Scaling. Phys Fluids 17:100605
7. Guttenberg Z, Rathgeber A, Keller S, Radler JO, Wixforth A, Kostur M, Schindler M, Talkner P (2004) Flow Profiling of a Surface-Acoustic-Wave Nanopump. Phys Rev E 70:056311
8. Strobl CJ, von Guttenberg Z, Wixforth A (2004) Nano- and Pico-Dispensing of Fluids on Planar Substrates Using SAW. IEEE Trans Ultrasonics Ferroel Freq Control 51:1432–1436
9. Wixforth A, Strobl C, Gauer C, Toegl A, Scriba J, von Guttenberg Z (2004) Acoustic Manipulation of Small Droplets. Anal Bioanal Chem 379:982–991
10. Nyborg WL (1998) Acoustic Streaming. In: Hamilton MF, Blackstock DT (eds) Nonlinear Acoustics. Academic, San Diego, pp 177–205

11. Marston PL, Thiessen DB (2004) Manipulation of Fluid Objects with Acoustic Radiation Pressure. Ann NY Acad Sci 1027:414–434
12. Kaduchak G, Sinha DN, Lizon D (2002) Novel Cylindrical, Air-Coupled Acoustic Levitation/Concentration Devices. Rev Sci Instr 73:1332–1336
13. Goddard G, Martin JC, Graves SW, Kaduchak G (2006) Ultrasonic Particle-Concentration for Sheathless Focusing of Particles for Analysis in a Flow Cytometer. Cytometry Part A 69:66–74
14. Kogan S, Kaduchak G, Sinha DN (2004) Acoustic Concentration of Particles in Piezoelectric Tubes: Theoretical Modeling of the Effect of Cavity Shape and Symmetry Breaking. J Acoust Soc Am 116:1967–1974
15. Zheng XM, Lowengrub J, Anderson A, Cristini V (2005) Adaptive Unstructured Volume Remeshing, II: Application to Two- and Three-dimensional Level-Set Simulations of Multiphase Flow. J Comput Phys 208:626–650
16. Yarin AL, Pfaffenlehner M, Tropea C (1998) On the Acoustic Levitation of Droplets. J Fluid Mech 356:65–91

Transport of Droplets by Thermal Capillarity

NAM-TRUNG NGUYEN, ZHENJUN JIAO,
XIAOYANG HUANG
School of Mechanical and Aerospace Engineering,
Nanyang Technological University, Singapore, Singapore
mntnguyen@ntu.edu.sg

Synonyms

Thermocapillary actuation

Definition

Transport of droplets by thermal capillarity is an actuation concept utilizing thermocapillary forces. A temperature gradient across a liquid droplet leads to a difference in surface tensions at both ends of the droplet. The surface tension difference drives the liquid droplet toward the cooler place.

Overview

Droplet-based microfluidics promises a number of applications for chemical analysis and synthesis. Generally, droplet transport can be achieved by manipulating a droplet's surface tension. Electrowetting or electrocapillarity is a common method for transport, where electrostatic force changes the contact angles and propels a droplet. Thermocapillarity utilizes the temperature dependency of interfacial tension for transporting a droplet. Temperature field on a solid substrate generated by heaters leads to a temperature gradient across a droplet and consequently a surface tension difference across the two ends of the droplet. The imbalance of surface tension makes the droplet move toward a cooler place. Transport of droplets by thermal capillarity is a coupled problem between heat transfer in a solid substrate and the surface tension-driven motion based on Newton's second law.

Basic Methodology

Transport of a Liquid Droplet in a Transient Temperature Field

Figure 1 shows a basic model of the motion of a liquid droplet inside a capillary and under a transient temperature field. At a relatively low heater temperature, the heat radiation can be neglected. The energy equation for heat transport in the capillary wall can be formulated with heat conduction and free convection as

$$\frac{\mathrm{d}T}{\mathrm{d}t} = \alpha \frac{\mathrm{d}^2 T}{\mathrm{d}x^2} - \frac{2hR_\mathrm{o}}{\rho c\left(R_\mathrm{o}^2 - R_\mathrm{i}^2\right)} T \tag{1}$$

where T is the temperature difference between the capillary temperature and the ambient temperature, and α, ρ and c are the thermal diffusivity, the density and the specific heat capacity of the capillary material. R_o and R_i are the outer and inner radii of the capillary as depicted in Fig. 1. The transient boundary conditions of the temperature field are

$$t = 0: \quad T(x) = 0$$

$$t > 0: \quad \begin{cases} x = 0\,, & \left.\dfrac{\mathrm{d}T}{\mathrm{d}x}\right|_{x=0} = -\dfrac{q''}{k} \\ x = L_\mathrm{c}\,, & T = 0 \end{cases}$$

where L_c, q'', k, R_o and R_i are the length of the capillary, the heat flux, the heat conductivity of the capillary's material and the outer and the inner radii of the capillary, respectively. Using the dimensionless variables

$$T^* = \frac{T}{q'' L_\mathrm{c} k}\,, \quad x^* = \frac{x}{L_\mathrm{c}}\,, \quad t^* = \frac{t}{L_\mathrm{c}^2 \alpha}$$

and the dimensionless parameter

$$\beta = \sqrt{\frac{2hR_o L_\mathrm{c}^2}{k\left(R_\mathrm{o}^2 - R_\mathrm{i}^2\right)}}$$

leads to the dimensionless form of Eq. (1):

$$\frac{\partial T^*}{\partial t^*} = \frac{\partial^2 T^*}{\partial x^{*2}} - \beta T^* \tag{2}$$



Transport of Droplets by Thermal Capillarity, Figure 1 Model of thermocapillary effect of a liquid droplet in a transient temperature field

as well as the dimensionless boundary conditions:

$$t^* = 0: \quad T^*\left(x^*\right) = 0$$

$$t^* > 0: \quad \begin{cases} x^* = 0\,, & \dfrac{\partial T^*}{\partial x^*} = -1 \\ x^* = 1\,, & T^* = 0 \end{cases}$$

Using separation of variables and Fourier series transformation, the solution of the partial differential Eq. (2) is

$$\begin{aligned} T^* = {} & \frac{1}{\beta}\left[\frac{\sinh(\beta)}{\cosh(\beta)}\cosh\left(\beta x^*\right) - \sinh\left(\beta x^*\right)\right] \\ & + \sum_{n=1}^{\infty} D_n \exp\left\{-\left[\left(n-\tfrac{1}{2}\right)^2 \pi^2 + \beta^2\right] t^*\right\} \\ & \times \cos\left[\left(n-\tfrac{1}{2}\right)\pi x^*\right] \end{aligned}$$

$$\begin{aligned} \frac{\partial T^*}{\partial x^*} = {} & \left[\frac{\sinh(\beta)}{\cosh(\beta)}\sinh\left(\beta x^*\right) - \cosh\left(\beta x^*\right)\right] \\ & - \sum_{n=1}^{\infty}\left(n-\tfrac{1}{2}\right) D_n \\ & \times \exp\left\{-\left[\left(n-\tfrac{1}{2}\right)^2 \pi^2 + \beta^2\right] t^*\right\} \\ & \times \sin\left[(n-\frac{1}{2})\pi x^*\right] \end{aligned}$$

$$\begin{aligned} D_n = {} & 2\int_0^1 \left\{-\frac{1}{\beta}\left[\frac{\sinh(\beta)}{\cosh(\beta)}\cosh\left(\beta x^*\right) - \sinh\left(\beta x^*\right)\right]\right\} \\ & \times \cos\left[\left(n-\frac{1}{2}\right)\pi x^*\right] \mathrm{d}x^* \end{aligned} \tag{3}$$

Figure 2 depicts the analytical transient behavior of the dimensionless temperature distribution along the capillary. The circles represent the position of the droplet in this space–time coordinate system. The liquid droplet is predicted to accelerate first and then slow down when it moves out of the temperature field.

The surface tension is a function of the temperature, which in turn is a function of the position x if a weak thermal interaction between the droplet and the capillary can be assumed:

$$\sigma_{\mathrm{lg}}(T) = f\left[T(x)\right] = g(x) = \sigma_{\mathrm{lg}}(x) \tag{4}$$

The simplest model for the friction between the liquid droplet and the capillary wall is the Hagen–Poiseuille model:

$$\frac{\mathrm{d}p}{\mathrm{d}x} = \frac{8\mu}{R^2}\frac{\mathrm{d}x}{\mathrm{d}t}$$

where $R = R_{\mathrm{i}}$ is the radius of the droplet and μ is the dynamic viscosity of the liquid. The governing equation for the movement of the liquid drop is

$$\begin{aligned} \rho\pi R_{\mathrm{o}}^2 L\frac{\mathrm{d}u}{\mathrm{d}t} = {} & -8\pi\mu L u + 2\pi R_{\mathrm{o}}\left[\sigma_{\mathrm{lg}}(x)\cos\theta_{\mathrm{r}}\right. \\ & \left. - \sigma_{\mathrm{lg}}(x+L)\cos\theta_{\mathrm{a}}\right] = 0 \end{aligned} \tag{5}$$

where L, θ_{r} and θ_{a} are the length and the contact angles at the receding and advancing ends of the liquid droplet,



Transport of Droplets by Thermal Capillarity, Figure 2 Graphical representation of the dimensionless transient temperature distribution along the capillary. The circles are the corresponding droplet position in this field

T



Transport of Droplets by Thermal Capillarity, Figure 3 Position and velocity of the droplet versus time

respectively. Introducing the velocity $u = \mathrm{d}x/\mathrm{d}t$, rearranging Eq. (5) and introducing the kinetic viscosity $\nu = \mu/\rho$, the governing equation of the droplet's motion is

$$\frac{\mathrm{d}u}{\mathrm{d}t} + \frac{8\nu}{R^2}u + \frac{2}{\rho RL}\left[\sigma_{\mathrm{lg}}(x+L)\cos\theta_{\mathrm{a}} - \sigma_{\mathrm{lg}}(x)\cos\theta_{\mathrm{r}}\right] = 0 \tag{6}$$

For a small temperature range, the surface tension can be assumed as a linear function of the temperature:

$$\sigma_{\mathrm{lg}}(T) = \sigma_{\mathrm{lg}0} - \gamma\,(T - T_0)$$

Finally, the velocity of the droplet is determined as

$$u = \frac{B}{A}\left[1 - \exp(-At)\right] \tag{7}$$

with

$$A = \frac{8\nu}{R_{\mathrm{o}}^2}$$

$$B = \frac{2}{\rho R^0 L}\left[\sigma_{\mathrm{lg}}(x+L)\cos\theta_{\mathrm{a}} - \sigma_{\mathrm{lg}}(x)\cos\theta_{\mathrm{r}}\right]$$

Because $L \ll L_{\mathrm{c}}$, the same contact angles at the two ends of the droplet can be assumed. Normalizing the spatial variable, the time and the velocity by L_{c}, L_{c}^2/α and α/L_{c}, respectively, results in the dimensionless velocity:

$$\begin{aligned} u^* &= \frac{B^*}{A^*}\left[1 - e^{-A^*t^*}\right] \\ A^* &= \frac{8\nu}{R_{\mathrm{o}}^{*2}\alpha} \\ B^* &= \frac{2L^3q''}{\rho R_{\mathrm{o}}^* k\alpha^2}\gamma\cos(\theta)\frac{\mathrm{d}T^*}{\mathrm{d}x^*} \end{aligned} \tag{8}$$

where the asterisk denotes the dimensionless variables. Note that the above dimensionless velocity is the ratio between the droplet velocity and the characteristic spreading velocity of heat in the capillary. Figure 3 shows the position and velocity of the droplet versus time with different liquid viscosities. From the analytical results, it is clear that liquids with lower viscosities can travel much further than those with higher viscosities. As expected from the results of the temperature field, the liquid droplet first accelerates, and then slows down. The acceleration period is determined by A^* in Eq. (8) or the ratio between the kinematic viscosity (momentum diffusivity) of the liquid and the thermal diffusivity of the capillary material. The stabilizing period is determined by B^* or the heat transfer in the capillary wall as modeled in Eq. (8). The less viscous droplet will initially accelerate faster and reach a higher velocity. The velocity then decreases until



Transport of Droplets by Thermal Capillarity, Figure 4 Model of thermocapillary effect of a liquid droplet in a periodic temperature field

the droplet stops when it moves out of the temperature field. A smaller dimensionless capillary radius R_o^* leads to a higher value of B^* , and consequently to a higher velocity.

Transport of a Liquid Droplet in a Periodic Temperature Field

Figure 4 shows a model of a liquid droplet inside a capillary and under a periodic temperature field. At a relatively low heater temperature, heat radiation can be neglected. The energy equation for heat transport in the capillary wall formulated with heat conduction and free convection remains the same as in the case of a transient temperature field (Eq. (1)), but the periodic boundary conditions are now

$$\left.\frac{\mathrm{d}T}{\mathrm{d}x}\right|_{x=0} = -\frac{q_1''}{k} = -\frac{q''}{k} f_1(t)$$

$$\left.\frac{\mathrm{d}T}{\mathrm{d}x}\right|_{x=L} = -\frac{q_2''}{k} = -\frac{q''}{k} f_2(t)$$

The functions f_1 and f_2 are depicted in Fig. 4. We can also introduce the dimensionless variables

$$T^* = T\frac{k}{q''L_c}, \quad t^* = \frac{t}{T_h}, \quad x^* = \frac{x}{L_c}$$

Eq. (1) then has the dimensionless form

$$\eta \frac{\mathrm{d}T^*}{\mathrm{d}t^*} = \frac{\mathrm{d}^2T^*}{\mathrm{d}x^*2} - \beta^2 T^* \tag{9}$$

with

$$\eta = \frac{L_c^2}{\alpha T_h}$$

$$\beta = \sqrt{\frac{2hL_c^2 R_o}{\alpha\rho c\left(R_o^2 - R_i^2\right)}}$$

and the dimensionless boundary conditions

$$\left.\frac{\mathrm{d}T^*}{\mathrm{d}x^*}\right|_{x^*=0} = -f_1\left(t^*\right)$$

$$\left.\frac{\mathrm{d}T^*}{\mathrm{d}x^*}\right|_{x^*=1} = f_2\left(t^*\right)$$

The dimensionless temperature field can then be determined as

$$T^* = \sum_{n=-\infty}^{\infty}\left\{\frac{F_{2n}\mathrm{e}^{\lambda_n} - F_{1n}}{\lambda_n\left(\mathrm{e}^{2\lambda_n}-1\right)} e^{\lambda_n x^*} + \left[\frac{F_{2n}\mathrm{e}^{\lambda_n} - F_{1n}}{\lambda_n\left(\mathrm{e}^{2\lambda_n}-1\right)} - \frac{F_{1n}}{\lambda_n}\right] e^{-\lambda_n x^*}\right\} e^{\mathrm{i}2\pi n t^*}$$

$$T(x,t) = \frac{q''L_c}{k}\operatorname{Re}\left(T^*\right) \tag{10}$$



Transport of Droplets by Thermal Capillarity, Figure 5 Graphical representation of the dimensionless periodic temperature distribution along the capillary. The circles are the corresponding droplet position in this field

where Re represents the real part of a complex number and

$$n = 0 \quad \begin{cases} F_{10} = \int_0^1 f_1\left(t^*\right) \mathrm{d}t^* = -0.5 \\ F_{20} = -F_{10} \end{cases}$$

$$n \neq 0 \quad \begin{cases} F_{1n} = \dfrac{\mathrm{i}}{2\pi n}\left[1 - (-1)^n\right] \\ F_{2n} = F_{1n} \end{cases}$$

Figure 5 depicts the three-dimensional dimensionless temperature difference. Because of the relatively large thermal capacitance of the capillary, a longer heating period T_h results in a better temperature gradient. If the period is too short, both heaters will contribute to an almost uniform temperature distribution.

The motion of the liquid droplet under this periodic temperature field can be obtained in the same manner as previously in the transient case. According to the result, the damping force acting on the droplet is proportional to its viscosity. The higher the viscosity, the smaller is the maximum peak-to-peak traveling distance. A low-viscosity droplet responds quickly to the change of the temperature gradient and causes an initial overshoot in velocity. At a higher viscosity, the response is damped and the velocity curve will have a typical exponential form. Figure 6 depicts the typical dynamic behavior of a droplet at different viscosities.

Key Research Findings

Droplet Motion in a Transient Temperature Field

Figure 7 depicts the measurement results of position and velocity of droplets with different viscosities. The experimental results agree relatively well with the theoretical results shown in Fig. 3. The droplet first accelerates in a short time, but most of the distance is traveled in this period. Initially, the temperature at the heater rises quickly, but temperature spreading along the capillary needs more time. Thus, the initial acceleration is controlled by the heat flux, while the later motion depends on the spreading process of the temperature. During this process, the liquid droplet moves to the cooler region because of the initially high velocity. In this region, the temperature gradient decreases significantly leading to a slowing down of the motion.

Periodic Fields

Figure 8 shows the experimental results of the droplet position and velocity in a periodic temperature field at different switching frequencies. In this case, the experimental results agree relatively well with the theoretical prediction in Fig. 6. Based on both experimental and theoretical data, the dynamic behavior of the droplet is determined by a number of parameters such as viscosity, drop length and switching frequency. In general, the droplet motion can follow the temperature change at low switching frequencies. However, the maximum traveling distance decreases at higher frequencies.



Transport of Droplets by Thermal Capillarity, Figure 6 Position and velocity of the droplet versus time at different viscosities



Transport of Droplets by Thermal Capillarity, Figure 7 Measured position versus time and velocity versus position of a droplet in a transient field with different viscosities

A lower liquid viscosity causes a larger traveling distance.

Future Directions for Research

Thermal capillarity is suitable for manipulating liquid droplets in microchannels. Thermocapillary pumps work with the same concept. Theoretical and experimental results show that the droplet motion can be controlled by viscosity, droplet length and the temperature field itself. Using more heaters in an array will allow a more complex droplet motion. In the models presented here the same contact angles at receding and advancing ends were



Transport of Droplets by Thermal Capillarity, Figure 8 Measured position and velocity of the droplet at different switching frequencies

assumed. But this is not the case in reality. The contact angles depend on the temperature and the droplet velocity, which directly affect the motion. Consideration of thermal expansion of the liquid, heat transfer inside the droplet and the capillary wall thickness may lead to further interesting findings.

Cross References

- ► Thermocapillarity
- ► Thermocapillary Pumping

References

1. Nguyen NT, Huang XY (2005) Thermocapillary effect of a liquid droplet in transient temperature field. Jpn J Appl Phys 44:1139–1142
2. Nguyen NT, Huang XY (2005) Erratum: Thermocapillary effect of a liquid droplet in transient temperature fields. Jpn J Appl Phys 45:6058
3. Jiao Z, Nguyen NT, Huang XY, Ang YZ (2006) Reciprocating thermocapillary droplet motion in an externally heated capillary. Microfluid Nanofluid 3:39–46

Transverse Electrophoresis

► Electrokinetic Motion of Heterogeneous Particles

Trapping Dielectrophoresis

► DC Dielectrophoresis in Lab-on-a-Chip Devices

Traveling-Wave Electro-Osmosis

► AC Electro-Osmotic Flow

Traveling-Wave Pump

Definition

A device for fluidic rectification using a series of nozzles located along a channel for issuing short *puffs* of flow which travel through the channel.

In fluidic pumps, the supplied alternating fluid flow is converted into a mostly one-way (and ideally non-return) output flow. One possibility how to do it is generating a series of travelling waves in a channel by alternating outflows and suction in a series of nozzles arranged along a channel. Each travelling wave drags along another fluid which does not necessarily enter the nozzles. In a more sophisticated versions, the outflow from the nozzles utilizes the Coanda effect of flow attachment to a curved wall.

Cross References

- ► Valve-Less Rectification Pumps
- ► Fluidic Pumping
- ► Fluidic Rectification

Turbulence

- ► Chaotic Flows

Turbulence Control (Microflap, Microballoon, Microsynthetic Jet)

Pradipta Kumar Panigrahi
Department of Mechanical Engineering, IIT Kanpur,
Kanpur, UP, India
panig@iitk.ac.in

Synonyms

Flow control; Turbulent shear stress; Mixing enhancement

Definition

A flow field is broadly classified as laminar or turbulent. Pressure, velocity and temperature information are used to characterize a flow field. In turbulent flows, these flow variables are random functions of space and time. The coherent and random flow structures/vortices and interactions between them influence the overall behavior of the turbulent flow field. The location of the wall surface, Reynolds number, Mach number, buoyancy force due to temperature and concentration gradients etc. influence the turbulent flow field characteristics. The nature of flow field also depends on the convective or absolute instability mechanism leading to turbulent flow.

The flow control is a mechanism by which the flow field is manipulated to obtain required behavior in comparison to the natural uncontrolled case. The flow control is broadly classified as: (a) passive control, where no auxiliary power source is required and (b) active control, where there is expenditure of energy. In passive control, parameters like geometry, compliance, temperature and porosity etc. are varied. Boundary oscillation, acoustic waves, blowing, suction etc. are used for active control. The active control schemes use actuators for manipulating the flow behavior. The size of these actuators depends on the nature of the flow. When the Reynolds number is increased, the required size of the actuator is reduced. The availability of MEMS fabrication technique has contributed towards small scale actuators development.

Overview

The industrial applications of turbulent flow control, the design requirements of actuators and the various classification schemes of actuators are discussed in the following sections.

Industrial Applications

The turbulent flow control finds application in various industrial applications: drag reduction, lift enhancement, mixing and or heat transfer enhancement, flow induced noise suppression etc. Reduction in drag of aircraft and underwater body leads to reduced fuel cost and volume. Enhanced heat transfer is desired for heat exchangers and electronic packaging while enhanced mixing is desired in combustors. The reduction in boundary layer noise due to pressure fluctuations helps in operation of under water sonar. To achieve these end results, the flow control techniques aim to control either the transition (delay or advance) or separation (suppression or enhancement) in a wall bounded flow. For an example, when the boundary layer is turbulent on an aircraft wing, the resistance to separation is enhanced and more lift can be attained by operating at higher angle of attack. On the other hand, the skin friction drag for a laminar boundary layer is smaller than that of turbulent boundary layer and therefore the delay in transition leads to lower skin friction drag and flow induced noise.

Implementation Strategy

The turbulent flow control can be implemented through different control schemes [1]. They are: predetermined open-loop control, reactive feed forward open loop control and reactive feedback closed loop control. The physical arrangement of sensors and actuators depend on the nature of control schemes and flow characteristics. The criteria for selection of appropriate actuators have been discussed in next section. It should be noted that the actuators require parasitic power supply for its operation. This fact should be taken into consideration for overall performance analysis of actuators.

Turbulent flow control schemes assume the significant role played by coherent large scale structures or vortices. These structures are responsible for more than 50% turbulence productions. The growth of large coherent structures leads to mixing enhancement. Similarly, the annihilation of large scale structures to small scale structures lead to lower drag. These coherent structures are generated or amplified due to the flow instability and gets convected from the upstream to the downstream locations. The boundary conditions imposed by the actuators located in-between the upstream



Turbulence Control (Microflap, Microballoon, Microsynthetic Jet), Figure 1 A schematic of flow control arrangement

and downstream locations modify the approaching turbulent structures. One possible turbulent flow control implementation scheme is shown in Fig. 1. The physical system on which the flow control scheme is implemented can be subdivided into three subsystems: (a) flow sensors, which characterize the upstream coherent structures, (b) actuators, which modify the wall boundary conditions experienced by the approaching coherent structures and (c) control sensors, which establishes the coherent structures evolution between upstream and downstream locations and the effect of actuations.

The control sensors are used for verification of control objectives. When, the objective is to reduce drag, the control signal is the shear stress. Similarly, for reduction of pressure fluctuations, the control sensors provide the rms value of pressure fluctuations. For implementation of the control scheme, the relationship/transfer function between the upstream sensors and control sensors is established. Similarly, the transfer function between the actuator properties and the control sensors is obtained. These two transfer functions are used to obtain the actuator state for optimal control.

Actuator Requirements

Due to chaotic nature, the turbulent flow is high dimensional in nature. Therefore, the implementation of turbulent flow control schemes for practical applications is challenging. However, the form and structures in a turbulent flow can be diagnosed and control of turbulent flow is realizable by suitable actuation. It is difficult to specify the requirement of an ideal actuator for turbulent flow control. The ideal characteristics of an actuator for turbulent flow control can be described based on the following guidelines.

- Turbulent flow is quite sensitive to the surface roughness. The actuator should not introduce additional roughness to the surface of the device. It should not have parasitic effect on the flow when the actuator is switched off.
- The frequency to be introduced by the actuators should match with the spatial and temporal frequencies present in the turbulent flow. The high Reynolds number flow has spatial and temporal frequency of the order of microns and kHz respectively. Therefore, MEMS based actuators are ideal for turbulent flow control due to their smaller physical dimension and lower inertia.
- Strength is the other requirement of actuator for maintaining the integrity against the load from the fluid forces.
- During implementation of distributed control with multiple actuators for optimal turbulent flow control, the behavior of the actuators should be uniform for all actuators.

The earlier flow control studies using blowing and suction have shown that the velocity due to the movement of the actuator should be of the order of friction velocity u_τ. For blowing based flow control, the flow blows through the boundary layer when the jet velocity is higher and the control is not effective for boundary layer control. The other observation is that when the size of the actuator is higher than the turbulent length scale ($l = \nu/u_\tau$, where ν is the kinematic viscosity and u_τ is the friction velocity), the surface roughness effect becomes predominant. The size of the actuator is usually about ten times the characteristics turbulent length scale. The operating frequency of the actuator is set based on two criteria:

- The actuator frequency is matched with the instability frequency of the flow and this approach is traditionally successful for separation control;
- The actuator frequency is set higher than the unstable frequency of the flow and the frequency content from the actuator is damped.

Here the actuator acts like a constant flux source without any fluctuations content. This mode acts on the main flow and is effective in turbulent boundary layer control for drag reduction.

Actuator Classification

The actuators can be broadly classified based on their principle of operation as: thermal actuators, electro hydrodynamic actuators, magneto hydrodynamic actuators, momentum injection actuators and moving surface actuators.

Thermal actuators are surface mounted electrical resistor, which injects heat into the near wall flow. The heating of the working fluid influences the instability of the flow in different ways depending on whether the working field is gas or liquid. The injected heat reduces the fluid density when the working fluid is gas leading to generation of buoyant force. When the working fluid is liquid, there is a decrease in fluid viscosity due to increase in temperature influencing the generation of Tollmien–Schlichting waves. The drawback of these actuators is the low frequency response due to the parasitic heat loss to the solid on which it is mounted and high power consumption.

For an electrically conducting fluid (water or ionized gas), the electrical field can induce motions due to the movement of charged ions or the body forces can be generated due to the interactions between magnetic and electric fields. These options are used in electro hydrodynamic and magneto hydrodynamic actuators. The drawbacks of these actuators are the high voltage requirement and significant loss due to the thermal effect. The micro-fabrication procedure of these types of actuators is not yet established.

The momentum injection actuators act like a source of momentum to the flow. One popular approach in this category is blowing. The other popular actuator in this category which does not require any fluid supply is the synthetic jet. The moving surface actuators provide motion of the wall beneath the flow. These actuators inject momentum to the flow by modification of the surface boundary condition. They introduce localized boundary layer disturbances. Flap actuator and balloon actuator belong to the moving surface actuators. The fabrication procedure of microsynthetic jet, microballoon and microflap actuators is established in literature. The practical applications of these actuators have been demonstrated. The present study discusses the details of these three actuators i. e. microsynthetic jet, microballoon and microflap. Other special MEMS based actuators are electrokinetic actuator, microbubble actuator, microvalve actuator and micropolymer actuator.

Basic Methodology

The physical configuration and the micro-fabrication procedure of microsynthetic jet, microballoon and microflap actuators are discussed in this section.

Micro Synthetic Jet

Configuration

The schematic of synthetic jet is shown in Fig. 2. It consists of a cavity open to the flow through a slit or orifice. The bottom wall of the cavity is driven by a moving surface, which can be either a piston or a vibrating membrane. The vibration of the membrane can be achieved using electrostatic actuation, piezo-ceramic material and differential thermal expansion of the electrode material with silicon layer underneath. When the membrane or piston moves inward of the cavity, fluid is pushed out of the cavity and when the membrane or piston moves back, the fluid is sucked into the cavity. The nature of flow through the slit opening depends on; (a) the frequency of membrane oscillation, (b) the amplitude of the membrane displacement, (c) the size of the orifice and (d) the geometry of the orifice. When the movement of the membrane or piston is small the flow through the slit is reversible during ingestion and expulsion phase. Above an amplitude threshold, the flow through the slit generates acoustic or pressure wave similar to a loud speaker. With subsequent increase in the membrane or piston displacement above a threshold, the outflow separates at the exit corner and a vortex ring moving away from the orifice is formed (see Fig. 2). The jet flow from the orifice draws fluid from the adjacent surroundings contrary to the uniform inward flow during the ingestion phase. Hence, the jet provides a net point source of momentum to the flow. The synthetic jet has zero net mass flux contrary to a normal jet. It imparts a net momentum to the flow without adding any net mass to the system. There is no need of reservoir or piping system for the operation of a synthetic jet. Temporal frequency of the order of 4 kHz can be achieved for a microsynthetic jet. The spatial resolution of the microsynthetic jet depends on the orifice diameter which is of the order of 500 μm. However, the combination of the oscillating membrane size and the substrate increase the overall dimension of the microsynthetic jet limiting the capability of distributed control using multiple actuators.



Turbulence Control (Microflap, Microballoon, Microsynthetic Jet), Figure 2 Schematic of synthetic actuator with (top) ingestion and (bottom) expulsion phase



Turbulence Control (Microflap, Microballoon, Microsynthetic Jet), Figure 3 A possible fabrication procedure of μ-synthetic Jet

Fabrication

A possible procedure for synthetic jet fabrication has been shown in Fig. 3. The first step in the fabrication process is the wet etching of the silicon wafer using KOH to form a cavity. The cavity is filled with electroplated Nickel in the second step. A polyimide membrane is deposited over the silicon wafer using spin coating in the third step. The back side of the silicon substrate is etched using KOH to obtain the orifice hole. The orifice hole extends till the filled Nickel inside the cavity and the Nickel material is also etched away. The piezo-ceramic material is deposited on top of the membrane for actuation. In case of electrostatic based actuation, aluminum electrode is deposited on the membrane. The disadvantage of the KOH based wet etching is the limited possible control over the size and shape of the orifice. To have superior control on the dimensional and shape accuracy, dry reactive etching is preferable.

Micro Balloon

Configuration

The schematic of a micro-balloon actuator is shown in Fig. 4.

This consists of Silicone rubber with manifold underneath for pressurized air actuation. The actuation takes place by the deformed shape of the silicone rubber, which is a function of the actuator pressure. The compression and decompression is achieved by a solenoid valve with external compressed air supply. Each microballoon consists of about 120 μm thick silicon membrane over two/three holes on a silicone chip. The bottom of Fig. 4 shows the shape and deflection of a balloon actuator at two different pressure levels. The advantage of these actuators is that they can support very large force (> 100 mN) and actuation length (> 1 mm). A micro-balloon can be operated for about 11,000 cycles of inflation and deflation and is robust against harsh environment. The disadvantage of micro-balloon actuators is the low-step response. The other disadvantage is the plastic deformation of the membrane due to stretching at high load. The actuation can be based on micro coil, piezoelectric, electrostatic and electromagnetic principle.

Fabrication

A possible fabrication procedure of the micro-balloon actuator has been shown in Fig. 5. In first step of the fabrication, silicon nitride is deposited using LPCVD (Low Pressure Chemical Vapor Deposition) technique at both sides of the silicon wafer. The back side of the wafer is patterned using reactive ion etching. In the second step, the cavities are etched using KOH based wet etching procedure. In the third step, Parylene-C is deposited on the front side and patterned using oxygen plasma. Parylene-C is used here to act as an intermediate layer between the silicon rubber and the sacrificial materials during the fabrication process. This is required as the sacrificial materials as oxide, silicon, photo-resist and etchants are incompatible with silicone membrane. Before removing the photoresist, the front side of the wafer is roughened using SF_6/O_2 plasma. The photo-resist is removed and silicone rubber is spin coated on the front side of the wafer in the fourth step. In the fifth step, silcone nitride and Parylene-C are removed from the back side of the wafer using SF_6/O_2 plasma followed by O_2 plasma etching. In the last step, pressurized compressed air is sent through the cavity to release the membrane.

Micro Flap

Configuration

The schematic of flap actuator is shown in Fig. 6. The actuator surface is supported at one end as cantilever support and the actuation takes place due to the external applied force at the other end. The disadvantage of micro coil, piezoelectric and electrostatic actuation is the large voltage requirement. Thus, the devices heat up leading to increase in temperature of the substrate with parasitic heat loss to the fluid. Magnetic



Turbulence Control (Microflap, Microballoon, Microsynthetic Jet), Figure 4 (**a**) Schematic of a balloon actuator and (**b**) the picture of a deformed balloon actuator at two different pressure levels



Turbulence Control (Microflap, Microballoon, Microsynthetic Jet), Figure 5 Fabrication procedure of a micro balloon actuator

actuation can achieve large force (order of hundreds μN) and large displacement (tens-hundreds of μm). The actuator consists of suspended magnetic piece supported by cantilever beams. The benefit of magnetic actuation is that magnetic field can be applied externally without any required electrical connections for voltage supply.

Silicon, silicon nitride, silicon elastomer and polymer etc. have been used as flap/membrane materials in literature One mode of operation is the application of current through the coil over electromagnet consisting of thin film coil with current passing through it. The other mode of operation is using a flap fabricated from a permanent magnet (permalloy) and actuated by an external magnetic field. During the rest mode, no magnetic field is applied and the membrane is flushed with the wall. When external magnetic field is applied by using either a permanent magnet or electro magnet, the flaps on the membrane surface are magnetized and a torque is generated due to the interaction between the internal and external magnetic field (see Fig. 6, bottom). The application of torque on the cantilever leads to deflection of the membrane/flap. The strength of the external magnetic field controls the deflection of the flap membrane. The frequency of the voltage supply to the electromagnet can be controlled for dynamic actuation.

Fabrication

The fabrication procedure of a magnetic flap actuator is shown in Fig. 7. The details on the fabrication procedure can be found in Liu et al. [4]. In the first step, phosphosilicate glass sacrificial thin film is deposited on top of the silicon substrate. This thin film is patterned to form mesas on which the actuator will be deposited. The mesas help in



Turbulence Control (Microflap, Microballoon, Microsynthetic Jet), Figure 6 Schematic of a magnetic flap actuator

limiting the possible undercut during the etching process. The photoresist layer is removed and the wafer is annealed in nitrogen at 1000°C for one hour. Subsequently, a layer of LPCVD polycrystalline silicon is coated on which thin phosphosilicate glass layer is deposited for doping purpose. Annealing at 950°C in nitrogen for one hour is carried out next for stress relieving and doping. Conductive seed layer (200 Å thick cromium and 1800 Å thick copper) is thermally evaporated in step 2. The permalloy (80% nickel and 20% iron) piece is electroplated in the third step. During electroplating, the wafer is affixed to the cathode and a pure Ni piece acts as anode. An external magnet is applied with the field lines being parallel to the wafer substrate. This establishes the easy axis of the permalloy parallel to the length of the cantilever beams. In step 4, the photoresist material is removed. The exposed seed layer material is than etched away. For etching copper, etchant (water : acetic acid : hydrogen peroxide) is used. For cromium etching, etchant (water : HCL = 10 : 1) is used. In the final fifth step, HF etching is used for about 20 minutes to release the actuators. The sacrificial layer is removed by etching and there is little effect on polysilicon. The permalloy sustains no structural and chemical damage.

Key Research Findings

The operational characteristics and salient examples of microsynthetic jet, microballoon and microflap applications have been discussed in the following sections.

Micro Synthetic Jet Characteristics

Different non-dimensional numbers and their critical value characterize the operation of a microsynthetic jet. Reynolds number and Stokes number are used to describe the viscous and unsteady effects respectively. The Reynolds number (Re) is defined based on the maximum jet velocity, U at the exit of the orifice and orifice diameter (d) as (see Fig. 2):

$$\mathrm{Re} = \frac{Ud}{\nu} \tag{1}$$

where, ν is the kinematic viscosity of the fluid. When the jet Reynolds number is less than a critical value of about 50, the flow is reversible. For this case, the flow is identical during suction and blowing phase. When the Reynolds number exceeds the critical Reynolds number, the jet separates from the orifice edge. The Stokes number (Stk) is



Turbulence Control (Microflap, Microballoon, Microsynthetic Jet), Figure 7 Fabrication procedure of a magnetic flap actuator

defined as:

$$\mathrm{Stk} = \sqrt{\frac{\omega d^2}{\nu}} = \sqrt{\frac{d^2}{\delta_\mathrm{v}^2}} \tag{2}$$

where, ω is the oscillation frequency of membrane and δ_v is the thickness of the unsteady boundary layer. Stokes number is the ratio between the orifice diameter and the thickness of the boundary layer at the exit of the orifice. When Stk is large, the viscous effect is not significant. When Stk is small, the viscous effect dominates and the exit velocity from the orifice reduces. This phenomenon is known as *viscous choking*. The increase in orifice size minimizes the viscous effect; but there is a simultaneous reduction in the exit velocity due to large flow area. Hence, a compromise solution is essential for the design of the micro-synthetic jet. The ratio between the square of the Stokes number and Reynolds number is known as Strouhal number (St):

$$\mathrm{St} = \frac{\omega d}{U} \tag{3}$$

The high value of Strouhal number indicates that the number of membrane cycle is higher than the frequency of fluid element passage through the orifice. The low Strouhal number value indicates similar actuation cycle of the actuator and the fluid element. Low Strouhal number indicates higher strength of the jet with low viscous losses. The *stroke ratio* which is defined as the ratio of the expelled stroke (L) to the diameter of the orifice (d) is also used to characterize the vortex ring formation of a synthetic jet. At higher stroke ratio (L/d), the vortex ring formed is disconnected from the trailing jet and at lower stroke ratio only single vortex ring is formed. The transition between these two cases is known as *formation number* and is usually within the range of 3.6 – 4.5.

The stroke ratio $L/d = U/(\omega d)$ is equal to the inverse of the Strouhal number. However, the limitation of stroke ratio definition is the assumption of slug-velocity profile. Holman et al. [2] discussed the formation criteria of synthetic jet based on both numerical simulation and experiment. They observed that vortex ring needs to withstand the suction velocity during ingestion stroke which is a function of the vortex strength. From dimensional reasoning, they proposed the following criterion for jet formation:

$$\frac{\mathrm{Re}}{\mathrm{Stk}^2} = \frac{1}{\mathrm{St}} > K \tag{4}$$

The above equation indicates that vortex escapes when the Strouhal number is less than a critical value. The constant K is a function of orifice geometry, the aspect ratio of the orifice, the shape of the exit edge i. e. sharp or rounded. The constant (K) is approximately equal to 1.0 and 0.16 for two-dimensional and axisymmetric synthetic jet respectively. Figure 8 shows the vorticity distribution during the ingestion and expulsion phase of a synthetic jet. The no-jet case corresponds to the K value less than 1.0 and the jet formation case corresponds to K value greater than 1.0 for a two-dimensional synthetic jet. For the jet formation case, the separated vortex ring is not dragged into the cavity during the ingestion stroke leading to a net momentum transport to the flow. Figure 8 compares the Reynolds number versus Stokes number relationship between the jet and no-jet formation case from both experimental and theoretical data (Holman et al. [2]). The small discrepancy between



Turbulence Control (Microflap, Microballoon, Microsynthetic Jet), Figure 8 (**a**) Vorticity plots for synthetic Jet during no formation (top) and formation (bottom) cases. (**b**) Reynolds number ($U_0 d/\gamma$) versus Stokes number ($\sqrt{\omega} d^2/\gamma$) of synthetic Jet, for no and formation cases

the two is attributed to the orifice geometry or curvature effect.

Lee et al. [8] presented the effectiveness of micro-synthetic jet for modification of turbulent boundary layer under adverse gradient. They showed significant mixing enhancement of the boundary layer when the forcing frequency is closer to the natural instability frequency. The boundary layer modification is more sensitive to forcing frequency compared to the forcing amplitude. The near wall mean velocity and turbulence intensity are significantly enhanced due to the operation of the synthetic jet. The synthetic jet needs to have sufficient velocity output and strong longitudinal vortices for effective flow control.

Micro Balloon Characteristics

The deflection of a micro balloon actuator depends on the actuation air pressure. Figure 9 shows the deflection versus pressure relationship of a silicone based balloon actuator. It shows the direct relationship between the applied pressure and the deflection. The plastic deformation of the balloon and the effect due to cyclic variation is used to decide the operating range of the micro balloon. Tung et al. [6] investigated the compressible flow separation control of a three-dimensional wing section using micro-balloon actuators. A glass plenum was used for supply of compressed air to the balloons. An initial pressure was applied for overcoming the stiction of the diaphragm to the substrate. The balloon deflection of about 1.2 mm was obtained during the testing experiment. The actuation pressure was varied between 4.5 to 7.5 psig depending on the Mach number of the flow. The micro-balloon actuator was shown to be successful in control of separation characteristics. A large pressure recovery was observed during the activation of the micro-balloon actuator. However, the shear stress sensors showed reduction in lift to drag ratio due to the micro-balloon actuation indicating the necessity of proper optimization of control technique. The micro-balloon was shown to be robust demonstrating its ability for high speed flow control applications.



Turbulence Control (Microflap, Microballoon, Microsynthetic Jet), Figure 9 Deflection versus actuation pressure of a balloon actuator

Micro Flap Characteristics

Liu et al. [4] investigated the effect of micro-flap actuator on a delta wing airfoil. The flap was 400 μm long and 100 μm wide. The calibration of the flap actuator was carried out in still air. An electromagnet was used to provide uniform external magnetic field. The magnetic field intensity was measured using Gauss meter. The angular displacement with respect to the magnetic field intensity is shown in Fig. 10. Large angular deflections (about 60 deg) and vertical deflections (about 1 – 2 mm) was demonstrated. It shows the asymptotic variation of flap displacement angle with respect to the magnetic filed



Turbulence Control (Microflap, Microballoon, Microsynthetic Jet), Figure 10 Angular displacement versus magnetic field strength of a flap actuator

intensity. Arrays of flaps positioned near the leading edge of delta wing showed generation of rolling moment by flap actuation. The effect of actuator location on the rolling moment of the delta wing was investigated from the force balance. Clear effect on rolling moment as a function of the actuator location was observed. The flow visualization images showed the vortical structures generated by the actuator.

Future Directions for Research

The micro actuators have shown success in various flow control applications. The detailed criteria for characterization of successful synthetic jet formation are evolving. There are limited data on the synthetic jet formation constant as function of the geometric parameters of the synthetic jet. The universality of jet formation constant needs to be verified for variety of synthetic jet geometries. The size, strength and trajectory of the vortices from synthetic jet need to be characterized from more detailed measurements and analysis. The effect of multiple synthetic jets, the pitch between neighbouring jets and the relative phase difference need to be investigated with respect to the nature of control vortices formation. The efficacies of flap actuators have been demonstrated in axisymmetric jet control and delta wing manoeuvring applications. The micro balloon actuators have shown its receptiveness to boundary layer control over delta wing with limited success on drag reduction. The integration and implementation of appropriate electronics with the micro actuator have not received adequate attention. The integration of microelectronics and micro-actuators with optimal control strategy will improve the performance of turbulent flow control applications. The uniformity in characterization and fabrication procedure of the micro actuators will facilitate their widespread research and industrial applications in future. The efficacy of these micro actuators for micro fluidics applications needs to be further explored.

Cross References

- ► Shear Stress Sensors
- ► Flow Structures
- ► Fabrication of 3D Microfluidic Structures

References

1. Gad-el-Hak M (2000) Flow Control, Passive, Active and Reactive Flow Management. Cambridge Univ Press, Cambridge
2. Holman R, Utturkar Y, Mittal R, Smith BL, Cattafesta L (2005) Formation criterion for synthetic jets. AIAA J 43:2110–2116
3. Huang A, Lew J, Xu Y, Tai YC, Ho CM (2004) Microsensors and actuators for microfluidic control. IEEE Sens J 4:494–502
4. Liu C, Tsao T, Lee GB, Leu TS, Yong WY, Tai YC, Ho CM (1999) Out-of-plane magnetic actuators with electroplated permalloy for fluid dynamics control. Sens Actuators 78:190–197
5. Khoo M, Liu C (2001) Micro magnetic silicone elastomer membrane actuator. Sens Actuators 89:259–266
6. Tung S, Maines B, Jiang F, Tsao T (2004) Development of a MEMS-based control system for compressible flow separation. J Microelectromech Syst 13:91–99
7. Rathnasingham R, Breuer K (2003) Active control of turbulent boundary layers. J Fluid Mech 495:209–233
8. Lee C, Hong G, Ha QP, Mallinson SG (2003) A piezoelectrically actuated micro synthetic jet for active flow control. Sens Actuators A108:168–174

Turbulence in Microchannels

MICHAEL G. OLSEN
Department of Mechanical Engineering,
Iowa State University, Ames, IA, USA
mgolsen@iastate.edu

Synonyms

Transition in microchannels; Friction factor in microchannels; Pressure drop in microchannels

Definition

Fluid flows can be generally described as being either laminar or turbulent. As opposed to laminar flows, in which the fluid moves in smooth layers (or laminae), turbulent flows are characterized by chaotic motion of fluid elements and seemingly random fluctuations in instantaneous velocities. One result of the chaotic fluid motion in turbulent flows is a tremendous increase in heat and mass transfer compared to laminar flows.

Overview

The governing equations for viscous fluid flow are conservation of mass (or continuity) and the Navier–Stokes equations (conservation of momentum or Newton's Second Law applied to a fluid). For steady-state, incompressible flow, these equations can be written as

$$\nabla \cdot \boldsymbol{u} = 0 \tag{1}$$

$$\rho \left(\boldsymbol{u} \cdot \nabla\right) \boldsymbol{u} = -\nabla p + \mu \nabla^2 \boldsymbol{u} \tag{2}$$

where $\boldsymbol{u}$ is the velocity, ρ is the fluid density, p is the pressure, and μ is the fluid viscosity. By introducing a characteristic length, L, a characteristic velocity, U, and a characteristic pressure, p_0, Eqs. (1) and (2) can be rendered dimensionless, resulting in

$$\nabla \cdot \boldsymbol{u}^* = 0 \tag{3}$$

$$\rho^* \left(\boldsymbol{u}^* \cdot \nabla\right) \boldsymbol{u}^* = -\mathrm{Eu} \nabla p^* + \frac{1}{\mathrm{Re}} \nabla^2 \boldsymbol{u}^* \tag{4}$$

where $()^*$ indicates a dimensionless quantity, $\mathrm{Eu} = p_0/(\rho U^2)$ is the Euler number, and $\mathrm{Re} = (\rho U L)/\mu$ is the Reynolds number.

The Reynolds number is the most important dimensionless parameter in fluid dynamics. Physically, the Reynolds number represents the ratio of inertial forces to viscous forces, and thus quantifies the effects of viscosity in the flow. In a pipe or channel flow, the characteristic velocity is typically taken as the mean velocity, and the characteristic length is typically taken as the pipe diameter or channel width.

In turbulent flows, Re is important because it can be used to determine when the flow transitions from laminar to turbulent flow and also when the flow achieves a fully turbulent state. For macroscale pipe and channel flows, transition to turbulence can occur in the range $1800 < \mathrm{Re} < 2300$, depending of flow conditions, and the flow becomes fully turbulent at a Reynolds number of approximately 4000. As will be shown later in this chapter, whether flows in microchannels agree with this macroscale behavior has long been a topic of debate, as some researchers have reported transitional Reynolds numbers in microchannel flows far lower than the $1800-2300$ reported for macroscale flows. However, recent studies using newly developed experimental techniques and also careful reexamination of the results of some of the earlier studies strongly suggest that microchannel flows do indeed exhibit transitional behavior similar to that observed in macroscale flows.

In designing systems involving pipes or channels, one important consideration is the pressure drop due to fluid friction for a pipe or channel, as this determines the pumping power required to force fluid through the conduit. The pressure drop, Δp, due to fluid friction with the pipe or channel walls can be found using

$$\Delta p = f \rho \frac{\ell}{D_\mathrm{h}} \frac{U^2}{2} \tag{5}$$

where ℓ is the pipe or channel length, D_h is the hydraulic diameter (calculated using $D_\mathrm{h} = \frac{4A}{P_W}$, where A is the cross-sectional area and P_W is the wetted perimeter), U is the mean velocity, and f is the Darcy friction factor. For laminar flow, f is purely a function of the Reynolds number, such that

$$f = \frac{64}{\mathrm{Re}} \tag{6}$$

For turbulent flows, the friction factor is a function of both the Reynolds number and the relative roughness, $\frac{\varepsilon}{D_\mathrm{H}}$, where ε is the root mean square roughness of the pipe or channel walls. For turbulent flows, the friction factor is found experimentally. The experimentally measured values for friction factor as a function of Re and $\frac{\varepsilon}{D_\mathrm{H}}$ are compiled in the Moody chart [1]. Whether the macroscale correlations for friction factor compiled in the Moody chart apply to microchannel flows has also been a point of contention, as numerous researchers have suggested that the behavior of flows in microchannels may deviate from these well established results. However, a close reexamination of previous experimental studies as well as the results of recent experimental investigations suggests that microchannel flows do, indeed, exhibit frictional behavior similar to that observed at the macroscale. This assertion will be addressed in greater detail later in this chapter.

In analyzing turbulent flows, it is often convenient to decompose the instantaneous velocity components and the pressure into mean and fluctuation components, such that

$$u = \langle u \rangle + u', \qquad v = \langle v \rangle + v',$$
$$w = \langle w \rangle + w', \qquad p = \langle p \rangle + p'$$

where $\langle\rangle$ denotes an ensemble average. Introducing these quantities into the Navier–Stokes equations and taking the ensemble average yields the Reynolds-averaged Navier–

Stokes (RANS) equations, which are

$$\begin{aligned}
&\rho\left(\langle u\rangle\frac{d\langle u\rangle}{\mathrm{d}x}+\langle v\rangle\frac{\mathrm{d}\langle u\rangle}{\mathrm{d}y}+\langle w\rangle\frac{\mathrm{d}\langle u\rangle}{\mathrm{d}z}\right)=-\frac{\partial\langle p\rangle}{\partial x}\\
&\quad+\mu\nabla^2\langle u\rangle-\rho\left(\frac{\partial\langle u'u'\rangle}{\partial x}+\frac{\partial\langle u'v'\rangle}{\partial y}+\frac{\partial\langle u'w'\rangle}{\partial z}\right)\\
&\rho\left(\langle u\rangle\frac{\mathrm{d}\langle v\rangle}{\mathrm{d}x}+\langle v\rangle\frac{\mathrm{d}\langle v\rangle}{\mathrm{d}y}+\langle w\rangle\frac{\mathrm{d}\langle v\rangle}{\mathrm{d}z}\right)=-\frac{\partial\langle p\rangle}{\partial y}\\
&\quad+\mu\nabla^2\langle v\rangle-\rho\left(\frac{\partial\langle u'v'\rangle}{\partial x}+\frac{\partial\langle v'v'\rangle}{\partial y}+\frac{\partial\langle v'w'\rangle}{\partial z}\right)\\
&\rho\left(\langle u\rangle\frac{\mathrm{d}\langle w\rangle}{\mathrm{d}x}+\langle v\rangle\frac{\mathrm{d}\langle w\rangle}{\mathrm{d}y}+\langle w\rangle\frac{\mathrm{d}\langle w\rangle}{\mathrm{d}z}\right)=-\frac{\partial\langle p\rangle}{\partial z}\\
&\quad+\mu\nabla^2\langle w\rangle-\rho\left(\frac{\partial\langle u'w'\rangle}{\partial x}+\frac{\partial\langle v'w'\rangle}{\partial y}+\frac{\partial\langle w'w'\rangle}{\partial z}\right)
\end{aligned}\tag{7}$$

The terms of the form $\langle u'_i u'_j\rangle$ are called the Reynolds stresses. The RANS equations do not consist of a closed set of equations (there are more unknowns than equations), so if the RANS equations are to be solved, the Reynolds stress terms must be modeled somehow. Typically, this modeling is based on experimental measurements. The application of models developed for macroscale flows to turbulent microchannel flows is dependent on the Reynolds stresses being similar for both cases. Recent experimental evidence suggests a strong similarity between turbulence statistics measured in turbulent microchannel flows and turbulence statistics measured in turbulent pipe and channel flows. Thus, the evidence suggests that turbulent models and codes developed to study macroscale turbulent pipe and channel flow should be applicable to the study of turbulent microchannel flows.

While the fluctuating velocities in turbulent channel flow may seem to imply random motion in the fluid, in actuality, turbulent channel flows (and turbulent flows in general) do contain underlying structure. One characteristic of turbulent flows is the presence of large- and small-scale turbulent eddies. One way to describe these turbulent structures of the flow is to measure spatial correlations of velocity fluctuations and to define characteristic length scales of the turbulent structures.

The normalized spatial correlation of the fluctuating velocity component u'_i with the fluctuating velocity component u'_j is defined as

$$R_{u'_i u'_j}(\Delta\boldsymbol{x};\boldsymbol{x})=\frac{u'_i(\boldsymbol{x})\,u'_j(\boldsymbol{x}+\Delta\boldsymbol{x})}{\sqrt{\langle u'^2_i(\boldsymbol{x})\rangle}\sqrt{\langle u'^2_j(\boldsymbol{x})\rangle}}$$

Where $\boldsymbol{x}$ is some location in the flowfield, and $\Delta\boldsymbol{x}$ is a displacement vector from location $\boldsymbol{x}$. If the turbulent velocity field was truly random, then $R_{u'_i u'_j}(\Delta\boldsymbol{x};\boldsymbol{x})$ would be equal to zero for all $\Delta\boldsymbol{x}\neq 0$. However, in a turbulent flow, $R_{u'_i u'_j}(\Delta\boldsymbol{x};\boldsymbol{x})$ is not equal to zero, signifying the existence of underlying structure in the turbulent flow. The properties of $R_{u'_i u'_j}(\Delta\boldsymbol{x};\boldsymbol{x})$ can be used to discern some characteristics about this underlying flow structure.

For example, $R_{u'_i u'_j}(\Delta\boldsymbol{x};\boldsymbol{x})$ can be used to define characteristic length scales for the underlying turbulent structures. $R_{u'_i u'_i}(\Delta\boldsymbol{x};\boldsymbol{x})$ has the property of being equal to 1 at $\Delta\boldsymbol{x}=0$ and approaching zero as $\Delta\boldsymbol{x}\to\infty$. The integral length scale for a turbulent flow is defined as

$$L_i=\int_0^\infty R_{u'_i u'_i}(\Delta\boldsymbol{x};\boldsymbol{x})\,\mathrm{d}\Delta\boldsymbol{x}$$

One way to compare the turbulent structures present in microchannel flows with the turbulent structures present in turbulent macroscale pipe and channel flows is to compare the integral length scales for each. As will be shown in the next section, the integral length scales of turbulent microchannel flows agree well with the integral length scales for their macroscale counterparts, suggesting that turbulent microchannel flows and large-scale pipe and channel flows are structurally similar.

In summary, even though the characteristic length scales of turbulent flows in microchannels are several orders of magnitudes smaller than their counterparts in macroscale pipes and channels, experimental evidence suggests the flows are statistically and structurally similar. As such, long established correlations for pressure drop in pipes and channels, and computational tools available for the study of turbulent pipe and channel flows should be equally applicable to turbulent microchannel flows.

Key Research Findings

Transition to Turbulence

In early studies of flow in microchannels, the onset of transition to turbulence was inferred from measurements of bulk properties of the flow, such as pressure drop or heat transfer rate. The behavior of the friction factor or Nusselt number undergoes a drastic change when the flow transitions to turbulence, and thus an observation of such a behavioral change can be indicative of the onset of turbulent flow.

Many of these early studies of flow in microchannels suggested transition to turbulence occurring at lower Reynolds numbers than those observed at the macroscale. For example, Wu and Little [2] measured friction factors and Nusselt numbers of gas flow through etched microchannels with D_H ranging from 45 μm to 83 μm, and their results suggested an early onset of transition occurring at around Re = 350. Similarly, Pent et al. [3] measured the friction factors and Nusselt numbers of flow through stainless steel microchannels of various diameters and aspect ratios and observed behavior consistent with transitional Reynolds numbers ranging from 200 – 700. Evidence of early transition to turbulence was also suggested by other experimental studies, too numerous to list individually here.

One common conclusion of many of these early studies was that the relatively high surface roughness of the microchannels investigated was a major factor in the observed behavior. However, this explanation is unsatisfying because there have also been researchers whose results on transition similarly derived from friction factor and Nusselt number data agreed well with macroscale behavior for microchannels with the same magnitude of relative roughness as the researchers mentioned previously. For example, in experiments on microchannels with hydraulic diameters ranging from 112 μm to 210 μm and aspect ratios from 1.0 to 1.5, Hegab et al. [4] reported transition for Re over 2000. Similarly, Qu and Mudawar [5] found no evidence of early transition in a series of micro heat sink experiments with Reynolds numbers as high as 1672. Transitional Reynolds numbers consistent those at the macroscale have also been observed by numerous other researchers.

In an attempt to clarify the seemingly contradictory results on transition in microchannels presented by various researchers, Hetsroni et al. [6] reexamined the results of previous researchers, with a particular emphasis on determining possible sources of the anamoulous results found in some studies. They determined that the anamoulous results reported by some researchers were due to either improperly defined experiments, heating of the fluid due to viscous dissipation resulting in a change in fluid viscosity, or due to measurement error. After examining the extensive body of experimental studies on transition in microchannels, they concluded that the vast preponderance of evidence reveals that the transitional behavior of flow in microchannels shows no differences with macroscale flow.

The recent development of microscopic particle image velocimetry (microPIV) [7] has provided researchers with the capability of measuring instantaneous velocity fields in microchannels, and hence provided an additional tool for investigating transition in microchannels. Because microPIV can be used to directly observe features of the velocity field in the microchannel, data collected using this technique provide a more direct indication of transition than pressure drop measurements where the transitional behavior must be inferred. In the first study of transition using microPIV, Sharp and Adrian [8] measured velocities in round microtubes with diameters between 50 μm and 247 μm. Using an increase in the root-mean-square velocity fluctuations along the centerline of the microtube as an indication of transition to turbulence, Sharp and Adrian observed transition between $1800 < \mathrm{Re} < 2300$, and thus concluded that early transition did not occur.

Li and Olsen used microPIV to measure velocity fields in microchannels for Reynolds numbers ranging from 272 to close to 3000 in two sets of experiments. In the first set of experiments [9], Li and Olsen measured velocity fields in square cross-section microchannels with hydraulic diameters ranging from 200 μm to 640 μm, and in the second set of experiments [10], they repeated these measurements for microchannels with hydraulic diameters equal to 480 μm and aspect ratios ranging from 0.97 to 5.69. In both sets of experiments, they observed transition in the same range of Reynolds numbers as Sharp and Adrian, indicating transitional behavior in agreement with classical macroscale results.

To summarize, although the transitional behavior of microchannel flows has been a point of significant debate due to conflicting results reported by numerous investigators, a close reexamination of the previous studies and the recent addition of microchannel velocity measurements using microPIV have strongly suggested that microchannel flows exhibit the same transitional behavior as has been observed in macroscale pipes and channels.

Friction Factor in Turbulent Microchannel Flow

Whether the friction factor for flow in microchannels agreed or disagreed with classical macroscale results was also long a point of confusion due to conflicting experimental results. Several of the early studies of flow in microchannels, including those of Wu and Little [2], measured friction factors that were significantly greater than well accepted macroscale results. However, numerous other researchers, including Qu and Mudawar [5] reported good agreement between microscale and macroscale friction factors. The study of Judy et al. [11] is particularly of interest due to its breadth. Judy et al. measured friction pressure drop of fluid flow in microtubes and microchannels with hydraulic diameters between 15 μm and 150 μm for three different fluids (water, methanol, and isopropanol), two different tube materials (and hence two different surface roughnesses), and two different tube cross-sectional geometries (circular and square), and found no significant deviation from macroscale viscous flow theory.

Hetsroni et al. [6] also reexamined previous studies of friction factor in microchannels and drew the same conclusions that they did for transition in microchannels. They found that the anamoulous results reported in some studies could be explained by the same factors that contributed to the observation of anamoulous transitional behavior. Indeed, in the only study performed to date combining both microPIV and extensive pressure drop measurements, Sharp and Adrian [8] found that transition as measured by microPIV agreed well transition as inferred from friction factor data, and also found that their measured friction factors agreed well with macroscale results. As with transition to turbulence, the experimental evidence on friction factors in turbulent microchannel flow shows that microscale flow exhibits the same behavior as macroscale flows.

Turbulence Statistics and Large-Scale Structures

The studies referenced up to this point indicate that the bulk characteristics of turbulent microchannel flow, specifically the onset of transition and the frictional pressure drop, tend to agree well with classical results for macroscale pipe and channel flow. However, the question remains as to whether the microscale turbulence is statistically and structurally similar to turbulence at the macroscale.

The development of microPIV as a microfluidics research tool has made it possible to measure statistical quantities such as velocity fluctuations and Reynolds stresses. Moreover, since microPIV provides instantaneous *velocity field* data, spatial correlations of velocity fluctuations can be measured, yielding insights into the underlying large scale structures in turbulent microchannel flow. However, obtaining reliable microPIV data in turbulent microscale flows is inherently difficult, and thus, to the author's knowledge, at the present time only two research groups have been successful in obtaining *whole-field* turbulence data for turbulent flow in microchannels. The major research findings of these studies are summarized below.

Velocity Fluctuations and Reynolds Stresses

Li and Olsen [9, 10] were the first researchers to measure profiles of velocity fluctuations in turbulent microchannel flow. They measured streamwise and transverse velocity fluctuations and Reynolds shear stresses for a range of Reynolds numbers spanning the laminar through fully-turbulent regime. They found good agreement between their measured fluctuations and Reynolds shear stresses and values reported for macroscale turbulent duct flow.

Natrajan et al. [12] collected velocity fluctuation and Reynolds shear stress data for turbulent flow in round microtubes for Re = 4500 (well within the fully-turbulent flow regime), and compared their experimental results with the results of a direct numerical simulation of turbulent pipe flow at a comparable Reynolds number. The comparison of these results is shown in Fig. 1, with the solid lines representing the DNS results and symbols representing the microPIV results. The agreement for the streamwise velocity fluctuations is nearly exact, while the transverse fluctuations and Reynolds shear stress agree to within 10% with the DNS results (this slight discrepancy in transverse velocity fluctuations is due to limitations in PIV itself and not due to any physical differences between micro- and macro-scale turbulence. See Liu et al. [13] for similar results obtained in comparing macroscale PIV data to DNS results).

Taken as a whole, the studies of Li and Olsen and Natrajan et al. encompass flow in round microtubes, square microchannels, and rectangular microchannels with aspect ratios as high as 5.69. They suggest that, with regards to pointwise turbulent statistics, turbulent flow in microchannels over an array of microchannel geometries agree well with pointwise statistics in similar macroscale geometries.

Large-Scale Structures and Velocity Correlations

The previously mentioned microPIV studies suggest that the turbulence in microchannels is *statistically* similar to flow in macroscale pipes and channels, but it is also important to consider if the microscale flows are *structurally* similar to macroscale flows. One way to determine this is to measure the characteristics of the large-scale turbulent structures in turbulent microchannel flow and compare these to turbulent macroscale flow.

Figure 2 is an instantaneous velocity field in a 536 μm diameter microtube at Re = 4500. Large-scale turbulent eddies are clearly visible throughout the velocity field, and a comparison to a velocity field obtained in a macroscale pipe would show many similarities. However, such comparisons are qualitative only, and a true quantitative comparison can only be made by statistically comparing the large-scale structures, as can be done by calculating spatial correlations and turbulent length scales.

Li and Olsen [14] were the first to perform such calculations. They calculated spatial correlations from ensembles of instantaneous velocities fields for flows in square microchannels and defined turbulent length scales in the streamwise and transverse directions as the distance it takes normalized spatial correlations of streamwise velocity correlations to drop to 0.5. These correlation lengths in the streamwise and transverse directions were called Lx_{uu} and Ly_{uu}, respectively. A comparison of these microchannel correlation lengths normal-



Turbulence in Microchannels, Figure 1 (**a**) Rms velocity fluctuations and (**b**) Reynolds shear stress as measured by microPIV for turbulent flow in a 536 μm diameter glass microtube

Turbulence in Microchannels, Table 1 A comparison of turbulent length scales for turbulent microchannel and macroscale channel flows

Study	Channel Dimension	Re	$2Lx_{uu}$/W	$2Ly_{uu}$/W	Lx_{uu}/Ly_{uu}
Li and Olsen [14]	325 μm	2853	0.38	0.20	1.90
Li and Olsen [14]	490 μm	3489	0.34	0.17	2.00
Li and Olsen [14]	640 μm	3333	0.30	0.16	1.88
Clark [15]	25 mm	3460	0.37	0.20	1.85
Clark [15]	25 mm	8300	0.29	0.16	1.93

ized by microchannel width, W, and correlation lengths for macroscale channels [15] are shown in Table 1. Excellent agreement was observed between the microscale and macroscale results. Natrajan et al. [12] also calculated spatial correlations from their microPIV data for turbulent microtube flow and also found excellent agreement between their results and spatial correlations for turbulent pipe flow.

While at the present time, these two studies are the only measurements of spatial correlations and turbulent length scales for microscale flows, the agreement observed in these measurements compared to large-scale pipe and channel flows suggest that the turbulence in microchannels and microtubes is structurally similar to the turbulence observed in similar macroscale flows.

Summary of Key Research Findings

Although for many years there were some questions about whether turbulent microchannel flows exhibited behavior similar to macroscale flows, recent experiments using new experimental techniques and a reexamination of data collected in previous studies suggest that, at least for microchannels as small as 50 μm in diameter, these questions are unfounded. Turbulent microchannel flow exhibits the same transitional behavior, displays similar frictional loss characteristics, and is statistically and structurally similar to macroscale pipe and channel flow.

Directions of Future Research

The number of studies utilizing microPIV in microchannels has to this point been very limited. Moreover, thus far this small number of studies has been limited to microchannels with hydraulic diameters greater than 200 μm. While these studies strongly suggest that microchannel turbulence is statistically and structurally similar to macroscale pipe and channel turbulence, a truly definitive answer cannot be arrived at until these two studies are supplement by additional studies for smaller hydraulic diameter microchannels.

Moreover, there must be some lower limit of microchannel hydraulic diameter beyond which the fluid behavior begins to deviate from behavior observed at the macroscale. At some point, the characteristic length scale of the flow will become so small that the continuum hypothesis must break down. However, the mean free path of molecules in liquid flows in microchannels is on the order of nanometers, and



Turbulence in Microchannels, Figure 2 An instantaneous velocity field as measured by microPIV for Re = 4500 flow in a 536 μm diameter glass microtube. A convective velocity of 91% of the centerline velocity has been subtracted to help visualize turbulent structures

thus, this lower limit is likely to be significantly smaller than 1 μm. Experiments will have to be performed to determine what this lower limit is, and also to determine the characteristics of flow in this regime.

Cross References

- ► Heat Transfer in Microchannel Flows
- ► Micro-PIV-Based Diffusometry
- ► Pressure Driven Single Phase Gas Flows
- ► Pressure Driven Single Phase Liquid Flows
- ► Transition to Turbulence in Microchannels

References

1. Moody LF (1944) Friction factors for pipe flow. Transactions of the ASME 66:671–684
2. Wu PY, Little WA (1983) Measurement of friction factor for flow of gases in very fine channels used for micro-miniature Joule-Thompson refrigerators, Cryogenics 23:273–277
3. Peng XF, Peterson GP, Wang BX (1994) Frictional flow characteristics of water flowing through rectangular microchannels. Exp Heat Transf 7:249–264
4. Hegab HE, Bari A, Ameel TA (2002) Friction and convection studies of R-134a in microchannels within the transition and turbulent flow regimes. Exp Heat Transf 15:245–259
5. Qu W, Mudawar I (2002) Experimental and numerical study of pressure drop and heat transfer in a single-phase micro-channel heat sink. Int J Heat Mass Transf 45:2549–2565
6. Hetsroni G, Mosyak A, Pogrebnyak E, Yarin LP (2005) Fluid flow in microchannels Int J Heat Mass Transf 48:1982–1998
7. Santiago JG, Wereley ST, Meinhart CD, Beebe DJ, Adrian RJ (1998) A particle image velocimetry system for microfluidics. Exp Fluids 25:316–319
8. Sharp KV, Adrian RJ (2004) Transition from laminar to turbulent flow in liquid filled microtubes. Exp Fluids 36:741–747
9. Li H, Olsen MG (2006) MicroPIV measurements of turbulent flow in square microchannels with hydraulic diameters from 200 μm to 640 μm. Int J Heat Fluid Flow 27:123–134
10. Li H, Olsen MG (2006) Aspect ratio effects on turbulent and transitional flow in rectangular microchannels as measured with microPIV. J Fluids Eng 128:305–315
11. Judy J, Maynes D, Webb BW (2002) Characterization of frictional pressure drop for liquid flows through microchannels. Int J Heat Mass Transf 45:3477–3489
12. Natrajan VK, Yamaguchi E, Christensen KT (2007) Statistical and structural similarities between micro- and macroscale wall turbulence. Microfluid Nanofluid 3:89–100
13. Liu ZC, Adrian RJ, Hanratty TJ (1991) High resolution measurement of turbulent structure in a channel with particle image velocimetry. Exp Fluids 10:301–312
14. Li H, Olsen MG (2006) Examination of large-scale structure in turbulent microchannel flow. Exp Fluids 40:733–743
15. Clark W (1970) Measurement of two-point correlations in a pipe flow using laser anemometer. Ph.D. Thesis. University of Virginia

Turbulent Flows

► Chaotic Flows

Turbulent Shear Stress

► Turbulence Control (Microflap, Microballoon, Microsynthetic Jet)

Two-Faced Particle

► Janus Particle

Two-Fluid Stratified Flow

► Liquid–Liquid Stratified Flow in Microchannels

Two Phase Flow

Definition

Two phase flow is the flow of two immiscible fluids in the same micro- or nanofluidic conduits, the fluids can be of different chemical compositions – liquid/liquid, or in different physical states – gas/liquid.

Cross References

► Pressure-driven Two Phase Flows

Two-Phase Flow Driven by Pressure

► Pressure-Driven Two Phase Flows

Ultra High-Throughput Screening System

► Microfluidic Systems for High-Throughput Screening

Ultrasonic Concentration

► Particle Manipulation Using Ultrasonic Fields

Ultrasonic Machining

ZHEMIN WU, DONGQING LI
Department of Mechanical Engineering, Vanderbilt University, Nashville, TN, USA
zhemin.wu@vanderbilt.edu

Synonyms

Ultrasonic material removal

Definition

Removal of materials using an axially oscillating tool at ultrasonic frequency (about 20,000 Hz) with a fine abrasive of silicon carbide, aluminum oxide, or boron carbide carried by a liquid between tool and work piece.

Overview

Ultrasonic vibrations are used in various engineering applications such as cleaning, welding and machining. Ultrasonic machining (USM) is the removal of materials by abrasive bombardment and crushing in which a soft flat-ended tool is made to vibrate at a frequency of about 20,000 hertz and amplitude of 0.001 – 0.003 inch. During the vibration, bunches of hard abrasive particles are continuously fed into the machining zone, between the tool and the work piece. The particles give either direct action on the surface of work piece or cavitation erosion caused by rapid changes in pressure inside the fluid, resulting in the material removal to form the required structure [1–3]. The dimensions of the work piece are determined by the size of the abrasive particles. Micro-ultrasonic machining (µUSM) can be realized by using submicron particles. The USM process is able to machine any material, but is more efficient on brittle materials. The abrasive particles have to be harder than the work piece material.

Ultrasonic machining is mostly used for producing small details in hard materials such as glass, precious stones, ceramics and composites. Many USM applications are involved in drilling where a tool penetrates into the work piece to produce either a through or blind hole of the required dimensions [4]. By applying fine abrasive grains (0.2 µm diamond particles), the technique was successfully utilized to produce micro holes as small as 5 µm in diameter with 37 µm in depth, in glass and silicon [5]. By combining USM and other machining techniques such as wire electro-discharge grinding (WEDG) and electro-discharge machining (EDM), the fabrication of complete 3D microstructure within one total manufacturing process becomes possible, e. g. a 3D micro center-pin bearing air turbine developed by Sun, et al. [6]. Recently, the technique was further extended to the nanometer scale by using ultrasonic actuation with an Atomic Force Microscope tip, which can induce structural surface and subsurface modifications at Highly Oriented Pyrolytic Graphite and thus facilitate the patterning of nanoscale surface features [7].

There are variations on the basic USM techniques. Rotary ultrasonic machining (RUM) [8, 9] is the technique involving the vibration of a small grinding toll, which is excited and simultaneously rotated. The technique permits increase in machining speed and decrease in machining forces, a useful condition for machining with fragile tools. The same advantages of smaller forces can be obtained by applying ultrasonic vibrations to a surgical tool in various medical applications. Examples include ultrasonic assistance dental cutting, brain tumors removal and artery surgeries [9, 10].

Cross References

► Biosensors Using Atomic Force Microscopes
► Bulk Micromaching

- ► Particle Manipulation Using Ultrasonic Fields
- ► Integrated Micro Devices for Biological Applications
- ► Microfabrication Techniques
- ► Microturbines

References

1. Kainth GS, Nandy A, Singh K (1979) On the mechanics of material removal in ultrasonic machining. Int J Mach Tool Des Res 19:33
2. Nair EV, Ghosh A (1985) A fundamental approach to the study of the mechanics of ultrasonic machining. Int J Prod Res 23:731
3. Soundararajan V, Radakrishnan V (1986) An experimental investigation on the basic mechanisms involved in ultrasonic machining. Int J Mach Tool Des Res 26:307
4. Graff KF (1975) Macrosonics in industry: 5. Ultrasonic machining. Ultrasonics 13:103
5. Egashira K, Masuzawa T (1999) Microultrasonic Machining by the Application of Workpiece Vibration. Ann CIRP 48:131
6. Sun XQ, Masuzawa T, Fujino M (1996) Micro ultrasonic machining and its applications in MEMS. Sens Actuators A 57:159
7. Cuberes MT (2007) Ultrasonic Machining at the Nanometer Scale. J Phys: Conference Series 61:219
8. Komarajah M, Manan MA, Narasimha PR, Victor S (1988) Investigation of surface roughness and accuracy in ultrasonic machining. Precis Eng 10:59
9. McGeough J (2002) Micromaching of Engineering Materials. Marcel Dekker Inc., New York
10. Drobinski G, Brisset D, Philippe F, Kremer D, Laurian C, Montalescot G, Thomas MD (1993) Effects of Ultrasound Energy on Total Peripheral Artery Occlusions: Initial Angiographic and Angioscopic Results. J Interv Cardiol 6:157

Ultrasonic Material Removal

- ► Ultrasonic Machining

Ultrasonic Particle Manipulation

- ► Particle Manipulation Using Ultrasonic Fields

Ultrasonic Pumps

Barbaros Cetin, Dongqing Li
Department of Mechanical Engineering,
Vanderbilt University, Nashville, TN, USA
barbaros.cetin@vanderbilt.edu

Synonyms

Acoustic streaming pumps

Definition

Ultrasonic pumps are pumps that use acoustic streaming to create a fluid motion inside microchannels. Acoustic streaming is the time-averaged flow induced by an ultrasonic wave (periodic pressure oscillation). Attenuation of the acoustic energy (via reflection and other distortion) generates a body force within the fluid and converts acoustic energy into kinetic energy of the fluid [1].

Overview

Ultrasonic pumps are very useful for microscale applications due to their simplicity, robustness and scaling advantages. Moreover, they are insensitive to the chemical state of the fluid and the wall material unlike electroosmotic and magnetic pumps. By using acoustic streaming as a pumping mechanism, noncontact fluid control is achievable since no contact is needed between the acoustic source and the fluid; and no valves are required [2].

Acoustic streaming flow fields depend on acoustic beam characteristics, fluid properties and the presence and the geometry of solid boundaries or particles. Depending on these factors, laminar, transitional or turbulent flow with jets and vortices can be generated. Acoustic streaming is proportional to the sound pressure level of the acoustic beam and the square of the frequency of the acoustic wave [1]. However, excessive heating – since most of the acoustic energy becomes heat – and bubble formation set an upper limit for high intensities [2].

An ultrasonic transducer is an integrated component of acoustic pumps. The transducers that generate ultrasonic energy with megahertz frequency for ultrasonic pumps make use of the piezoelectric (PZT) effect. A PZT layer is the vital component of the ultrasonic transducer and provides the oscillatory motion that ultimately produces the acoustic beam.

Rife et al. [3] developed a fluidic pumping circuit powered by an acoustic frequency of 50 MHz, and generated fluid flow with velocities of the order of mm/s. They used ultrasonic PZT transducers for their pump to generate the acoustic waves. The intensity of the waves was low enough to produce negligible heating; however, even if the heating could be tolerated, dielectric breakdown in the PZT thin film limited the maximum intensity. They also discussed bubble formation, and concluded that for frequencies above a few megahertz, the technique was safe to use for degassed liquids without any cavitation problem.

Nguyen and White [4] presented a numerical study of a flexural plate wave (FPW) micropump. Their simulated device consisted of a channel with a thin PZT membrane, whose thickness was $1-3\,\mu$m attached to a bottom wall. This membrane generated a high-intensity acoustic filed in the vicinity of the fluid inducing the motion of a fast-moving layer near the membrane. They investigated the pumping performance with different parameters such as the wave amplitude, channel height and back pressure. They concluded that micropumps with a height of a few micrometers had a good performance due to their high flow rate and high hydraulic impedance against back pressure.

Cross References

- ► Electrical Pumps
- ► Magnetic Pumps
- ► Thermocapillary Pumping

References

1. Martin SE (2001) Parametric Analysis of Acoustic Streaming Pumps Utilizing Planar Ultrasonic Acoustic Beams. Ms. Thesis, Vanderbilt University
2. Minor KT (2002) Acoustic Streaming Micropumps. Ms. Thesis, Vanderbilt University
3. Rife JC, Bell MI, Horwitz JS, Kabler MN, Auyeung RCY, Kim WJ (2000) Sens Actuators 868:135–140
4. Nguyen NT, White RM (1999) Sens Actuators 77:229–236

Ultrasonic Separation

- ► Particle Manipulation Using Ultrasonic Fields

Unbalanced AC field

Synonyms

Aperiodic AC field

Definition

A periodic alternating-current (AC) electric field is called unbalanced, if its first moment has zero time average ($\langle E\rangle = 0$), but at least one of its higher moments does not (e. g. $\langle E^3\rangle \neq 0$).

Cross References

- ► Aperiodic Electrophoresis
- ► Electrokinetic Motion of Polarizable Particles
- ► Nonlinear Electrokinetic Phenomena

Unimorph

Definition

A structure composed of one active layers and one or more passive layers. Typically the active layers work through either thermal expansion, hygrothermal expansion, or piezoelectric expansion via an externally-applied electrical field. Such devices are asymmetric about their neutral axis, and so may generate axial stretching or contraction along with bending.

Cross References

- ► Bimorph
- ► Piezoelectric Valves

Unit Impulse Function

- ► Dirac Delta Function

Unmanned Rotorcraft

- ► Microrotorcraft

Unmixing

- ► Demixing

UV-LIGA

- ► LIGA-Like Techniques

Valve

► pH-Sensitive Hydrogel

Valveless Pumps

► Peristaltic Pumps

Valve-Less Rectification Pumps

Václav Tesař
Department of Thermodynamics, Institute
of Thermomechanics, Academy of Sciences of the Czech
Republic, Prague, Czech Republic
tesar@it.cas.cz

Synonyms

No-moving-part pumps

Definition

The term, despite its common and frequent use, is actually a misnomer. The fluidic pumps so described in fact do have valves and it is the arrangement and configuration of these valves which is their most interesting aspect. What are absent are the mechanical moving or deformed components in the valves. The valves are there to rectify the alternating flow generated, as in the more conventional pumps, by an actuator performing reciprocating motions and displacing the pumped fluid from the displacement cavity. The actuators are usually driven by an electric input.

In the "valve-less" version, the mechanical blockage of the flow in the *closed* state of the valve is replaced by a dynamic, inertial effect which is to be overcome by the fluid. This never suffices for stopping the flow completely. The rectification – conversion to one-directional movement – is therefore inherently less efficient than with the mechanofluidic counterparts. In microfluidics, there is a distinct continuing trend towards a smaller size and this – together with typically higher viscosity often pumped biological fluids – leads to lower Reynolds numbers. Since one of the interpretations of Reynolds number presents it as the ratio of inertial to viscous friction force acting on a fluid, this trend also contributes to the efficiency being generally indifferent or downright poor. This, however, is not of much significance in most microfluidic applications. The selling point of the "valve-less" pumps is their excellent suitability for micromanufacturing – no need for expensive assembly operations – long life, not endangered by breakage of springs or by moving components getting stuck, and suitability for operation at high working frequencies [1–3, 12].

Basic Methodology

The Grätz Bridge Circuit

Usual present-day pumps in microfluidics are of the simplest configuration corresponding to Fig. 1. The actuator, represented in Fig. 1 symbolically by the traditional crankshaft-connecting rod-piston mechanism, generates the alternating flow, rectified by two one-way valves. During the first half of the cycle, the liquid is sucked into the displacement cavity through the upstream or suction valve. No fluid comes back into the cavity from the output, because the return flow is prevented by the upstream or delivery valve, which is oriented so that in this phase of the cycle it is in its *closed* state. Its state changes into the *open* in the subsequent half of the cycle when it allows the liquid, displaced by the actuator, to flow to the output terminal. Obviously, the output flow is intermittent, available only during one half of each operating period. The output flow pulsation is an obvious disadvantage.

In applications where the pulsation can cause problems – and also in those aiming at a higher efficiency – it is advisable to use, according to Fig. 2, the full-wave, Grätz bridge rectifier. Its name is explained in Fig. 3. It needs to be supplied by two-phase alternating input flow, carried in two channels. Generating it is usually no problem since the to-and-fro motion of the front side of the mechanical actuator


Schematic symbol
for fluidic diode
- direction
of easy flow
Diode
R
Output
flow rate

Valve-Less Rectification Pumps, Figure 1 Schematic representation of a single-action reciprocating pump. The alternating flow, shown symbolically as generated by a piston and crankshaft mechanism, is rectified by two fluidic diode valves. Their schematic symbol is derived from one of the oldest rectifying valve versions with a moving ball


Air
Displacement
vessels
Alternative layouts
of air/liquid motion transfer
Displacement
vessels
LIQUID
Piston
Diaphragm
Gravity
Pumped
liquid
R
Output
flow rate

Valve-Less Rectification Pumps, Figure 2 Schematic representation of the double-acting two-phase reciprocating pump. Two alternating flows, mutually shifted by π radians, are rectified by four fluidic diodes connected into the Grätz full-wave bridge. Also shown is one of the advantages of energy transfer by the alternating flow: the possibility of using different fluids (here gas and liquid) in different parts of the fluidic system

(symbolized in the drawing by the piston) means availability of a motion of the same amplitude with the opposite phase on its reverse side. The second phase may be also used differently, according to Fig. 4, to increase the generated output pressure. This is welcome in situations where the pump has to drive a high-dissipance load.

In the "valve-less" pumps, the mechanofluidic one-way valves are replaced by fluidic diodes. A diode is a device exhibiting different hydrodynamic properties for different directions of the flow. The effect is characterized by diodity – the ratio of dissipances

$$\boldsymbol{D} = \frac{Q_{\text{return}}}{Q_{\text{forward}}}, \tag{1}$$

in the return and forwards flow directions. Diodity is usually evaluated in steady regimes, where it is generally found to increase with Reynolds number

$$\text{Re} = \frac{wd}{\boldsymbol{\nu}}, \tag{2}$$

where w [m/s] is the characteristic velocity, d [m] the characteristic length dimension of the device and $\boldsymbol{\nu}$ [m^2/s] is fluid viscosity. In unsteady regimes, the relation between the inertial and friction forces is different. The former increase in importance with increasing operating frequency f [Hz] of the alternating input flow. This is characteristically chosen higher as the size of the pump



Valve-Less Rectification Pumps, Figure 3 The reason why the Grätz circuit is called a “bridge”: the load with one-way fluid flow is bridging the gap between the two parallel systems of diodes

decreases. Rather than Reynolds number, the proper characterization criterion in these cases is the Stokes number

$$\mathrm{Sk} = \frac{f\,d^2}{\nu}\,. \tag{3}$$

Of the two-terminal fluidic diodes, the highest rectifying effect is offered by ▶ vortex diodes (Figs. 5 and 6). In the *return* flow direction, the flow is opposed by the centrifugal action of rotation in the vortex chamber. The rectification is due to there being essentially no rotation with the central fluid entry into the vortex chamber in the *forward* flow regime. Diodity values as high as about $\boldsymbol{D} = 20$ have been achieved – not, however, with the simple version shown in Fig. 6. This can achieve, depending on its geometry, usually values of about $\boldsymbol{D} = 4$. The versions developed for really high performance are of more complex design, typically with a large number of inlets on the periphery of the vortex chamber, necessary for symmetry of the vortex motion. The inlets and the outlets have to be carefully shaped, the latter as diffusers. Use of vortex diodes in microfluidic pumps is limited by two factors. First, considering the structure of the full-wave bridge in Fig. 5, it is obvious that it is difficult or even impossible to accommodate into the typical planar configuration on a substrate plate the exits leading at right angles from the vortex chamber. Even more problems arise with the complex structure of the inlets in the high-performance versions. The second factor is the relatively poor frequency range. It takes a relatively long time to start up the rotation after the onset of the reverse *closed* state. This counters the modern trend towards operation at a high frequency with small-volume displacement cavities.



Valve-Less Rectification Pumps, Figure 4 The double-acting, two-phase driving does not necessarily mean the use of the Grätz full-wave bridge. As shown here, the two phases may be used in half-bridges connected in series. The pulsation of the output flow is not suppressed, but the rectifier generates a higher output pressure

More suitable for microfabrication, because of their planar layout, are the Tesla diode (Fig. 7) and the various versions of the labyrinth diodes, in particular the one shown in Fig. 9. Experience with the former type, patented in 1920 by the inventor N. Tesla, has been unfortunately somewhat disappointing. An improved version, the Tesser valve, is described in [4]. To improve the effective overall diodity, these devices are usually designed in multi-stage arrangements – the downstream stages in the Tesla diode actually benefiting from the jet-deflection phenomenon of the stage located upstream. The diodity $\boldsymbol{D}$ is, however, rarely larger than 1.2 to 1.6.

Better performance and, because of the short and simple path, high-frequency range are characteristic of the ▶ venturi diode, consisting of a nozzle and a diffuser placed in series. Under various other names [5], it is currently among the most popular among the no-moving-part rectifiers (Figs. 10 and 11). An application of the use of a two-Venturi rectifier circuit in a flow control actuator for gen-



Valve-Less Rectification Pumps, Figure 5 Rectification by vortex diodes – in the double-acting two-phase Grätz full-wave bridge. The advantage is the absence of the moving parts; disadvantages are the slow start-up of diodes and necessity of complex spatial layout



Valve-Less Rectification Pumps, Figure 6 A simple version of the vortex diode. At left is the *closed* state with rotation in the vortex chamber; at right is the easy flow, *open* state with radial forward flow. High-performance diodes have several tangential inlets into the chamber, resulting in symmetric character of the flow – but lead to an even more difficult spatial layout of the rectifier circuit

eration of hybrid synthetic jets [6] is an example of a use of the rectifier circuits other than in simple pumps.

Jet-Type Rectifiers

Rectification based on properties of a fluid jet is a very old technique but used to be mostly applied in devices of little importance, such as aquarium ventilators, coolers or humidifiers, where the dominant requirement was low cost. Sometimes the decisive factor for their use was the fact that inertia of moving parts in mechanofluidic diodes prevents them from operation at the frequency of AC mains (also wear of contacting moving components would be too rapid at this frequency). Typically, descriptions in the literature are missing as the designers (and usually inventors) did not consider the solution of this peripheral problem in the main pumping design task worthy of publication. Probably the first reference in the literature is from 1957, when Dauphinne described in a short note the use of the *loudspeaker wind* for a simple closed-circuit cooling. He used a standard loudspeaker provided with a front plate having a central orifice forming a simple displacement vessel with a nozzle. The flow generated and used for cooling would nowadays be called the *synthetic jet*. Better documented use of the jet-type rectifier – in a pump for moving molten salts – was described by Walkden and co-workers (e. g. [7]). Their rectifier was developed from a standard jet pump (Fig. 12a). A very similar jet-pump rectifier was later tested by the present author [8]. To obtain the full-wave rectification, Walkden provided the jet pump with two primary nozzles in parallel, each supplied with one phase of the alternating two-phase flow. An even more important improvement was replacing the two nozzles by diffusers (Fig. 12b). This led to better efficiency



Valve-Less Rectification Pumps, Figure 7 The Tesla diode, one of the earliest no-moving-part devices. As shown here, it is usually used in a multi-stage layout. Diodity is very much worse than with vortex diodes



Valve-Less Rectification Pumps, Figure 8 A typical example of the labyrinth diode, here built using short conical tubes


Return (inhibited) flow
Forward (easy) flow

Valve-Less Rectification Pumps, Figure 9 Planar labyrinth diode, more suitable for micromanufacturing: again a multi-stage version


Diffuser
- operates as a good nozzle in the reverse flow
Nozzle - does not operate at all as a diffuser in the reverse flow
Wide jet
Narrow jet

Valve-Less Rectification Pumps, Figure 10 Rectification effect in the Venturi (convergent–divergent) diode is based on the larger energetic loss by dissipating kinetic energy of the narrower jet


Suction Venturi
Displacement cavity
Delivery Venturi

Valve-Less Rectification Pumps, Figure 11 Single-action pump with the Venturi diode rectifier. This is currently the most common type of "valve-less" pumps used in microfluidics


Alternating flow
Primary nozzle
Mixing tube
a
Possible second suction inlet
b
Dividing nose
c
d

Valve-Less Rectification Pumps, Figure 12 Survey of the jet-type diodes. (**a**) A standard jet pump may exhibit a reasonable rectification effect. (**b**) The Walkden two-phase full-wave rectifier was developed from a jet pump with two parallel "primary nozzles", actually better performing when shaped as diffusers. (**c**) Tippetts' analysis of the long-nosed symmetric Walkden rectifier found it actually consists of three three-terminal devices. (**d**) The three-terminal Venturi, sometimes known as RFD device


Thermopneumatic actuator
Ohmic heater

Valve-Less Rectification Pumps, Figure 13 A simple single-action pump with the three-terminal Venturi rectifier. Less known than the version from Fig. 11, it can exhibit higher rectification efficiency. The alternating flow is generated by expansion of gas heated electrically by the resistance heater



Valve-Less Rectification Pumps, Figure 14 Operation of the three-terminal Venturi rectifier. Fluid from the suction pipe of the pump enters the rectifier due to the jet-pumping effect of entrainment into the jet, which appears in both flow halves of the operating cycle



Valve-Less Rectification Pumps, Figure 15 The double-action full-wave pump with two three-terminal Venturi rectifiers. Alternating flow is generated by deformation of round diaphragms



Valve-Less Rectification Pumps, Figure 16 The Tippetts version of the double-action pump with the single three-terminal Venturi rectifier and a symmetric jet pump in the opposite vertex of the Grätz bridge


Two 3-terminal Venturi devices with front-to-rear symmetry
T_1
R
T_2
Logical OR
Jet pump with left-to-right symmetry
R

Valve-Less Rectification Pumps, Figure 17 Schematic fluidic circuit diagrams of the two pumps from Fig. 15 (left) and Fig. 16 (right)

due to the absence of flow separation from the walls in the reverse flow direction. Analysis of the Walkden rectifiers led Tippetts [9] to discovering the importance of the three-terminal device shown in Fig. 12d as a member of version C of the variant of Walkden's rectifier shown in Fig. 12 – and the proposal (also in [9]) to use this device alone in a reciprocating jet pump (Fig. 13). The return flow from the load during a part of the cycle was acknowledged as inevitable – and actually made use of by arranging the rectifier device (Fig. 14) so that the jets are formed in both flow directions and the pumped fluid is sucked in from the input inlet due to the entrainment effect of the jets.

Though also using the same two diffusers as the now standard design of Fig. 11, the pump according to Fig. 13, less well known, has more effective rectification. Tippetts himself went on later to extend this principle to the full-wave two-phase operation. He did not follow the more obvious additive layout of Fig. 15, presented also schematically in the left half of Fig. 17. Instead, he placed the rectifier devices into the other vertices of the Grätz bridge, where



Valve-Less Rectification Pumps, Figure 18 Operating principle of the jet-type rectifier with the *forward flow diverting* by the Coanda effect. The original version with a nozzle at the inlet into the displacement cavity [10]

the single direction of the output flow made possible the replacement of the upstream three-terminal device by the symmetric jet-pump OR logical element.



Valve-Less Rectification Pumps, Figure 19 Later improvement of the principle from Fig. 18. Energetic loss associated with inflow into the displacement cavity is reduced by the inlet being shaped as a diffuser. The small angle β (compared with the full 80°in Fig. 14) is made possible by the change of the jet direction due to the Coanda effect attachment to the curved wall

Traveling Wave Pump

Essentially also a jet-type rectification, this is an alternative that features several important improvements [11]. One of them is the use of the Coanda effect attachment to a curved wall. This wall is positioned so that it turns the direction of the forward flow coming from the displacement cavity. The general direction of the main flow through this rectifier is straight and a considerable proportion of the pumped liquid actually continues in the straight direction without ever entering the displacement cavity. A recently tested version (Fig. 22) uses the principle from Fig. 18, with a number of displacement cavities arranged along the channel length. The entrances into the cavities are placed at a streamwise pitch which corresponds to the distance traveled from one displacement cavity to the following one by the attached Coanda jet during one half of the period. As a result of this timing, the outflows from the cavities form a traveling wave passing through the channel. With proper adjustment of operating frequency it is possible to enter the resonant regime in which the efficiency reaches very high values. Little has been done so far with the improved version of Fig. 19, with angular position of the inlets into the displacement cavities ($\beta < \pi$; in fact $\beta < \frac{\pi}{2}$ (Fig. 19) decreasing the hydraulic losses associated with flow direction change.

Other Principles

To round off the list, the peristaltic pumps should be mentioned. They use a multi-phase multi-stage arrangement similar to that of Fig. 20, but in their common form they are based on much less effective rectification elements.

Finally, a useful rectification has been also demonstrated based on temperature dependence of viscosity. Ohmic


Small displacement vessels accomodate only a percentage of pumped fluid

Valve-Less Rectification Pumps, Figure 20 The principle of the traveling-wave pump, two-phase, three-stage rectifier based on the principle from Fig. 19. A substantial proportion of the pumped liquid does not enter the displacement cavities – instead, it is dragged along with the wave



Valve-Less Rectification Pumps, Figure 21 Schematic representation of the working principle (above) and the relation to the Grätz half-bridge principle

heating of the delivery channels synchronized with the flow from the displacement cavity is used with liquids which decrease their viscosity in response to the heating. In a similar design, the electric heating of the liquid is so intense that it leads to boiling – generation of bubbles in the channel resisting the flow by surface tension.

Key Research Findings

Existing designs of microfluidic pumps with operation based on valve-less rectification demonstrate the practical applicability of no-moving-part flow generation and control principles [12]. The absence of moving components makes these pumps attractive for applications stressing the aspects of high reliability, long life and absence of any maintenance. They are also more suitable for micromanufacturing techniques, such as etching, than the pumps with return flow control by mechanical moving components. On the other hand, without the moving components the return flow in the valves is never suppressed completely. As a result, the valve-less pumps are considerably less efficient and therefore suitable for those applications where efficiency of pumping is not of primary importance.

Since the suppression of the return flow in the valve-less pump is based on inertial effects in flowing pumped fluid, the efficiency of the pump decreases with decreasing Reynolds number. This is a serious factor, since the general trend of operating at progressively smaller Reynolds numbers is typical for modern microfluidics [12]. To oppose this effect, it is found useful to employ in a microfluidic system with several circuits, a central pump for driving the flow in all these circuits rather than distributed driving by a separate pump in each circuit. For the central pump, this means a larger size and larger handled flow rates so that the Reynolds number is not so low.



Valve-Less Rectification Pumps, Figure 22 An example of a micropump using the principle from Fig. 18 and generation of the flow wave by alternative suction into the nozzles on both sides of the channel. Nozzles belonging to on phase are on the same side of the channel. Alternating flow is generated by displacement due to volume of a liquid crystal gel exposed to an electrostatic field

Future Directions for Research

The use of the attractive properties of valve-less pumps being limited by the generally poor efficiency, further development concentrates on research aimed at obtaining a higher efficiency of the rectification, especially at low Reynolds number flows. Besides development of new rectification principles with better properties, higher efficiency is obtainable by operating at a higher frequency and therefore higher values of the Stokes number (Eq. (3)). However, this way towards a better performance is not applicable for all operating principles; it is not suitable for those flow mechanisms characterized by long flow paths. From this point of view, it seems advisable to direct future research to the jet-type rectification principles.

Cross References

- ► Electroosmotic Pumps
- ► Fluidic Rectification
- ► Electroosmotic Pumps
- ► Magnetic Pumps
- ► Microfluidic Circuits
- ► Particle Manipulation Using Ultrasonic Fields
- ► Peristaltic Pumps
- ► Piezoelectric Valves
- ► Pneumatic Valves
- ► Pressure-Driven Two-Phase Flows
- ► Rotary Peristaltic Pumps
- ► Thermomechanical Valves
- ► Thermopnuematic Valves
- ► Ultrasonic Pumps

References

1. Zimmerman WBJ (ed) (2006) Microfluidics: History, Theory, and Aplications. CISM courses and lectures No. 466, Springer-Verlag, Wien, New York
2. Laser DJ, Santiago JG (2004) A review of micropumps. J Micromech Microeng 14:R35
3. Nguyen NT, Wereley ST (2006) Fundamentals and Applications of Microfluidics. Chapter 6: Microfluidics for Internal Flow Conrol: Microvalves. Chapter 7: Microfluidics for Internal Flow Control: Micropumps
4. Forster FK, Williams BE (2002) Parametric design of fixed-geometry microvalves – the Tesser valve. In: Proceedings of IMECE. ASME, New Orleans, November 2002
5. Trávníček Z, Tesař V, Wang AB (2005) Enhancement of synthetic jets by means of an integrated valve-less pump. Sens Actuat A (Physical) 125:50
6. Trávníček Z, Vít T, Tesař V (2006) Hybrid synthetic jets as the non-zero-net-mass-flux synthetic jets. Phys Fluid (accepted for publication)
7. Stutely JR, Walkden AJ (1968) Improvements in or relating to pumps. UK Patent 1.132,442, Oct 1968
8. Tesař V (1983) Fluidic Jet-Type Rectifier: Experimental Study of Generated Output Pressure. J Fluid Control / Fluidics Q 14(4):13
9. Tippes JR, Swithenbank J (1974) Fluidic flow control devices and pumping systems. US Patent 4,021,146, 30 Oct 1974
10. Tesař V (1976) Čerpadlo nebo dmychadlo, zejména pro dopravu obtížně čerpatelných tekutin (Pump or blower, particularly for transport of difficult-to-pump fluids). Czechoslovak Certificate of Authorship Nr. 192 082
11. Tesař V (1981) Alternáló légárammal mükodtetett folyadék szivattyu (Fluidic Pump Driven by Alternating Air Flow). In: Proceedings of Pneu-Hidro kollokvium, Gépipari Tudományos egyesület, Györ, Hungary, September 1981
12. Tesař V (2007) Pressure-Driven Microfluidics. Artech House, Boston-London

Van-der-Waals Attraction

Definition

The weak attraction felt by molecules when they are several molecular diameters apart: responsible for condensation and solidification of a gas when the temperature is reduced.

Cross References

- ► Electrokinetic Flow and Ion Transport in Nanochannels

Vapor Bubbles

► Thermal Bubbles

Vaporization

- ► Droplet Evaporation

Velocimetry

Synonyms

Flow profiling

Definition

Velocimetry is the measurement of fluid velocity. In the context of microfluidics and nanofluidics, velocimetry involves the determination of the velocity field in small scale internal flows. Most commonly, velocimetry involves optical tracking of a fluid marker. In such cases the terms flow visualization and velocimetry are used interchangeably. A variety of velocimetry methods have been developed for small scale flows. Visualization based methods can be divided into particle-based techniques, such as micro-particle image velocimetry, and scalar-based techniques, such as molecular tagging. Non-visualization based velocimetry methods have also been developed, such as electrochemical velocimetry where fluid velocity is determined via generation of a redox species.

Cross References

- ► Visualization Based on Molecular Tagging Methods
- ► Microscale Flow Visualization
- ► Micro-PIV-Based Diffusometry
- ► Fluid Metering Methods for Flow Rate Measurements
- ► Flow Rate Measurement, Methods

Velocity Distribution Function

Definition

Velocity distribution function is defined so that the quantity $f(t, \boldsymbol{r}, \boldsymbol{v})\, \mathrm{d}\boldsymbol{r}\, \mathrm{d}\boldsymbol{v}$ is the number of particles in the phase volume $\mathrm{d}\boldsymbol{r}\, \mathrm{d}\boldsymbol{v}$ near the point $(\boldsymbol{r}, \boldsymbol{v})$ at the time t.

Cross References

- ► Gas Flow in Nanochannels
- ► Heat Transfer in Microchannel Flows
- ► Supersonic Micro-Nozzles
- ► Micro- and Nanoscale Gas Dynamics
- ► Lattice Poisson-Boltzmann Method, Analysis of Electroosmotic Microfluidics

Velocity Sensors

Ahmad Yusairi Bani Hashim,
Dharmalingam Sugumar
Faculty of Manufacturing Engineering, Universiti
Teknikal Malaysia Melaka, Melaka, Malaysia
yusairi@utem.edu.my

Synonyms

Flow sensors; Flow meters

Definition

Flow velocity in microchannels can be measured by means of flow sensors. The basic principle of measuring flow velocity is by monitoring the flight time of particles or elements in the moving fluid after heat impulses are injected. The time taken for the particles or elements to move between two predetermined points is called the flight time. In addition, some principles in heat transfer and fluid dynamics are also applied to give precise estimation of flow conditions. Flow velocity is obtainable from flow rate. The flight time unit is second (s), the flow velocity unit is micrometer per second (μm/s) and the flow rate unit is microliter per minute (μl/min). The units for flow velocity and flow rate can sometimes be of nano- and picoscale order of magnitude.

Overview

Fluid (gas, liquid) systems such as natural gas supply or water supply use flow meters, the devices that can be used to estimate the amount of fluid supplied. They are also found in automotive applications in engine control and emission and in fuel flow and consumption, and in biomedical instrumentation [1]. A trend over the last decade has been to develop biochemical sensors that are very small in size. Typical measuring parameters are the temperature, the electrolyte conductivity, the flow rate, the liquid level and the concentration of ions, gases and enzymes. Among these sensors are the flow sensors, the devices that detect physical quantities of fluid flow such as the flow velocity. It was then expected that there were potential applications of these sensors for microanalysis technologies and systems that include analytical chemistry, biotechnology, medicine, environment monitoring, space investigations and industrial process control [2].

A miniature fluid system usually handles transportation of fluids filled with particles and/or biomacromolecules such as protein solution or cell lysate. This system, also called a microfluidic system, works with a flow rate of the order

Velocity Sensors, Table 1 Notations and symbols

Notation	Symbol	Notation	Symbol	Notation	Symbol
Coordinates	x, y, z	Density	ρ	Kinematic viscosity	υ
Velocity components	u, v, w	Stress	τ	Reynolds number	Re
Time	t	Pressure	p	Prandtl number	Pr
Total energy	E_T	Heat flux	Q, q	Heat density	Φ
Nusselt number	Nu	Heat transfer coefficient	α, h	Power	P
Thermal conductivity coefficient	λ, k	Specific heat coefficient	c_p	Volume	V
Temperature	T	Heat conductance	G	Incoming fluid temperature	T_∞

of pl/s to nl/s and where its microchannels have diameters less that a millimeter. Due to the small flow rate required by the system, it depends on micropumping to provide the fluid flow. A micropump, a device that produces a small-scale fluid flow, uses electrical or mechanical stimulus to drive the flow [3]. An example of a pump used in micropumping is the syringe pump. Current trends are to develop microfluidic systems for precise control of gas and liquid flows. The designs typically consist of integrated microfluidic components such as pumps, valves and sensors [4].

Basic Methodology

In this section, the fundamental principles of fluid flow and heat transfer are introduced. Additionally, two representative approaches in flow velocity measurement using pulse modality flow sensors and calorimetric-type gas flow sensors are discussed. There are a number of notations found in the text: Table 1 lists the notations and their respective symbols. Moreover, the articles found in the cross-references list are useful for further understanding of the topics discussed here.

Fluid Flow

In the early 1800s the Navier–Stokes equations were independently derived by G. G. Stokes and M. Navier [5]. These are a set of equations that describe the motion of a fluid. It consists of a time-dependent continuity equation for conservation of mass, three time-dependent conservation of momentum equations and a time-dependent conservation of energy equation. The flow condition can be estimated using these equations.

The continuity equation for conservation of mass where the amount of mass remains constant is

$$\frac{\partial \rho}{\partial t}+\frac{\partial(\rho u)}{\partial x}+\frac{\partial(\rho v)}{\partial y}+\frac{\partial(\rho w)}{\partial z}=0 \tag{1}$$

The following equations give the x, y, z momentums for conservation of momentums respectively where the amount of momentum remains constant:

$$\begin{aligned}&\frac{\partial(\rho u)}{\partial t}+\frac{\partial\left(\rho u^2\right)}{\partial x}+\frac{\partial(\rho u v)}{\partial y}+\frac{\partial(\rho u w)}{\partial z}\\&=-\frac{\partial \rho}{\partial x}+\frac{1}{\mathrm{Re}}\left(\frac{\partial \tau_{\mathrm{xx}}}{\partial x}+\frac{\partial \tau_{\mathrm{xy}}}{\partial y}+\frac{\partial \tau_{\mathrm{xz}}}{\partial z}\right)\end{aligned} \tag{2}$$

$$\begin{aligned}&\frac{\partial(\rho v)}{\partial t}+\frac{\partial(\rho u v)}{\partial x}+\frac{\partial\left(\rho v^2\right)}{\partial y}+\frac{\partial(\rho v w)}{\partial z}\\&=-\frac{\partial \rho}{\partial y}+\frac{1}{\mathrm{Re}}\left(\frac{\partial \tau_{\mathrm{xy}}}{\partial x}+\frac{\partial \tau_{\mathrm{yy}}}{\partial y}+\frac{\partial \tau_{\mathrm{yz}}}{\partial z}\right)\end{aligned} \tag{3}$$

$$\begin{aligned}&\frac{\partial(\rho w)}{\partial t}+\frac{\partial(\rho u w)}{\partial x}+\frac{\partial(\rho v w)}{\partial y}+\frac{\partial\left(\rho w^2\right)}{\partial z}\\&=-\frac{\partial \rho}{\partial z}+\frac{1}{\mathrm{Re}}\left(\frac{\partial \tau_{\mathrm{xz}}}{\partial x}+\frac{\partial \tau_{\mathrm{yz}}}{\partial y}+\frac{\partial \tau_{\mathrm{zz}}}{\partial z}\right)\end{aligned} \tag{4}$$

The energy equation where the amount of energy remains constant is

$$\begin{aligned}&\frac{\partial(E_{\mathrm{T}})}{\partial t}+\frac{\partial(uE_{\mathrm{T}})}{\partial x}+\frac{\partial(vE_{\mathrm{T}})}{\partial y}+\frac{\partial(wE_{\mathrm{T}})}{\partial z}\\&=-\frac{\partial(up)}{\partial x}-\frac{\partial(vp)}{\partial y}-\frac{\partial(wp)}{\partial z}\\&\quad-\frac{1}{\mathrm{Re}\,\mathrm{Pr}}\left(\frac{\partial q_{\mathrm{x}}}{\partial x}+\frac{\partial q_{\mathrm{y}}}{\partial y}+\frac{\partial q_{\mathrm{z}}}{\partial z}\right)\\&\quad+\frac{1}{\mathrm{Re}}\left(\frac{\partial}{\partial x}\left(u\tau_{\mathrm{xx}}+v\tau_{\mathrm{xy}}+w\tau_{\mathrm{xz}}\right)\right.\\&\quad+\frac{\partial}{\partial y}\left(u\tau_{\mathrm{xy}}+v\tau_{\mathrm{yy}}+w\tau_{\mathrm{yz}}\right)\\&\quad\left.+\frac{\partial}{\partial z}\left(u\tau_{\mathrm{xz}}+v\tau_{\mathrm{yz}}+w\tau_{\mathrm{zz}}\right)\right)\end{aligned} \tag{5}$$

Heat Transfer

The passage of thermal energy from a hot to a cold body is called heat transfer in thermal physics. It can occur through conduction, transfer of heat through matter; convection, transfer of heat through moving liquids and gases; and radiation, transfer of heat through electromagnetic radiation emitted from the surface of an object which is due to the object's temperature [6]. However, radiation heat transfer usage in microfluidic flow sensors has not been found. In 1822, Joseph Fourier proposed a conduction process as in Eq. (6); in 1701, Isaac Newton suggested a convective process as in Eq. (7):

$$q = -k\frac{\mathrm{d}T}{\mathrm{d}x} \tag{6}$$

$$q = \bar{h}\left(T_{\mathrm{body}} - T_{\infty}\right) \tag{7}$$

Representative Approaches in Flow Velocity Measurement

The sensor output signal of pulse modality flow sensors is strongly tied to the relationship between sensing element temperature and flow rate as well to the relationship between sensing element resistivity and temperature [7]. Further explanation of its functionality is discussed in the next section. In steady state, the input heat transfer is balanced by power dissipation:

$$P = Q_{\mathrm{conduction}} + Q_{\mathrm{convection}} \tag{8}$$

The amount of heat transferred to the fluid is proportional to the temperature difference between the hot sensing element and the fluid temperature:

$$Q_{\mathrm{convection}} = G_{\mathrm{convection}}\left(T_{\mathrm{s}} - T_{\mathrm{f}}\right) \tag{9}$$

Equation (10) is the surface heat flux per unit area. Considering laminar flow and the decreasing thermal boundary layer with increasing velocity, the heat transfer increases in relation with the flow velocity.

$$Q'_{\mathrm{convection}} = 0.332\lambda\left(T_{\mathrm{s}} - T_{\mathrm{f}}\right)\left(\sqrt[3]{\mathrm{Pr}}\right)\sqrt{\frac{v}{x\upsilon}} \tag{10}$$

Calorimetric-type gas flow sensors analyze the temperature distribution built up in the environment around a central heater element [2]. Further explanation of its functionality is discussed in the next section. Using thermal electric circuits, thermal behavior of the sensor's structure is determined. A number of resistors and capacitors are used in the circuit to function as heat transfer agents. Equation (11) is modeled for convective resistance, and Eq. (12) for thermal capacitance where A is the heater area. The flow velocity can be obtained from Eq. (12).

$$R_{\mathrm{convection}} = \frac{1}{\alpha A} \tag{11}$$

$$R_{\mathrm{capacitance}} = \frac{1}{\rho c_{\mathrm{p}} A v} \tag{12}$$

Key Research Findings

In this section, the operating principles of selected gas velocity sensors and liquid velocity sensors are explained.

Gas Velocity Sensors

Calorimetric Sensors. The calorimetric type of gas flow sensors analyze the temperature distribution built up in the environment around a central heater element [2]. A photograph of a novel calorimetric sensor design is shown in Fig. 1, while Fig. 2 depicts the general idea behind the concept of calorimetric-type gas flow sensors. Figure 2 shows a single channel with two sensing elements, the temperature resistors, attached upstream and downstream of the direction of flow. These elements confirm the direction of flow that can be in two possible directions.

In between the elements is the central heater that heats up the gas as it passes by. This arrangement allows gas velocity to be measured. The thermal conduction, convection and laminar flow condition of the gas are used for gas velocity determination. Figure 3 shows a typical output of this sensor. It depicts the simulated temperature values of the upstream and downstream resistors for different heater temperatures using nitrogen gas. It can be seen that the temperature difference between the upstream and downstream resistors increases with the flow velocity. The sensor is said to be useful in measuring explosive gas mixture concentrations.

C-MOS Compatible Silicon Gas Flow Sensors. The top view of a novel C-MOS compatible silicon gas flow sensor is exhibited in Fig. 4. The dimension (D) is the width of the porous silicon isolation area. Its function is to measure gas flow velocity applying the principle of heat transfer [1]. The sensor is fabricated using porous silicon. It consists of two thermopiles which have two series of aluminum/p-type polysilicon thermocouples. Thermocouples are types of temperature sensor that convert thermal potential difference into electric potential difference [8].

The heater and the thermopiles are placed on a thick porous silicon layer. There are numbered pads on the top surface of the sensor. Input electric current is introduced to the heater through certain pads to generate heat. Another



Velocity Sensors, Figure 1 View of a micromachined sensor structure developed for direction-dependent flow detection. Image taken using a scanning electron microscope [2]


Flow direction
Flow channel
Heat transfer
Central heater
Upstream temperature resistor
Downstream temperature resistor

Velocity Sensors, Figure 2 Schematic of a one-dimensional calorimetric mass flow meter. The inhomogenous temperature distribution developing around the central heater characteristically represents the flow velocity [2]



Velocity Sensors, Figure 3 Simulated gas temperature versus flow velocity at the position of platinum resistors. Nitrogen gas was used in this simulation [2]



Velocity Sensors, Figure 4 Top view of a flow sensor [1]



Velocity Sensors, Figure 5 Thermopile difference as a function of flow velocity [1]

option is through pads that have compensation resistors whose characteristics resemble those of the heater. Figure 5 shows the sensor's typical output. It describes the thermopiles' output voltage difference as a function of gas flow velocity. This output is a result of an experiment where nitrogen gas flow in the range of 0 to 1000 standard cubic centimeters per minute at room temperature was introduced.

Carbon Nanotube (CNT)-based Microelectromechanical Systems (MEMS) Flow Sensors. CNT-based MEMS flow sensors can be used to detect air flow inside a poly(methyl methacrylate) (PMMA) microfluidic chamber [9]. Figure 6 shows the sensor's system prototype. The system applies the principle of heat transfer by electrical current heating, flow resistance dependency and current–voltage characteristics to measure gas flow velocities.



Velocity Sensors, Figure 6 (**a**) Photograph of a flow sensor chip with multi-walled carbon nanotube (MWNT) sensing element; (**b**) optical microscope image showing an array of MWNT sensors inside a PMMA chamber; (**c**) optical microscope image showing two pairs of microelectrodes with CNT bundles; (**d**) scanning electron microscope image showing the formation of MWNTs (∼ 5 µm in length) between gold microelectrodes [9]

Figure 7 exhibits a typical result produced by the sensor. In this experiment, a constant current mode circuit is used to generate heat in the sensor with different overheat ratios. As a result, the thermal heat transfer mechanisms across the sensor affect the flow sensitivity. The air flow is supplied using a vortex micropump, a device that produces fluid flow in microliter and nanoliter volumes [8]. The sensor is claimed to have potential for biocompatible and low-cost sensing applications.



Velocity Sensors, Figure 7 Output voltage variations with different ait flow supplied by an air compressor. Three curves represent three different overheat ratios for the same sensor [9]

Liquid Velocity Sensors

Ion-Sensitive Field-Effect Transistor (ISFET)-based Flow Velocity Sensor. The ISFET-based flow velocity sensor functions as a flow direction and diffusion coefficient detection device [10]. It senses the velocity of liquid through detection of ions. The sensor is shown in Fig. 8. It shows a chemical sensor-actuator system having one ion generator and one detector. The generator–detector pair detects ions that are electrochemically generated. Positive potential applied to the generator electrode results the electrochemical reaction in water solution generating hydrogen ions (H^+). Likewise, hydroxyl ions (OH^-) are generated when a negative potential is applied to the generator electrode. These ions are called the chemical tracers.



Velocity Sensors, Figure 8 Photograph of a flow sensor with a single ISFET placed onto a printed circuit board before encapsulation [10]



Velocity Sensors, Figure 9 Schematic of a sensor. The corresponding electrochemical reactions for H^+ and OH^- ion generation through the electrolysis of water solution are shown



Velocity Sensors, Figure 10 Typical output signal of an ISFET-based flow velocity sensor at different flow rates from 0.1 to 0.6 ml/min (**a**) and determination of the time of flight (**b**). In this experiment, OH^- ions were generated by a constant current of 30 µA to reach a constant sensor signal. The arrows mark the time of the beginning (arrows downwards) and the end of generation (arrows upwards). The time of flight (t_l) is that needed for the generated OH^- ions to reach the ISFET gate region [10]



Velocity Sensors, Figure 11 Image of a milliscale prototype. The dotted circles show the separator (left) and analyzer (right) regions. The prototype was made with two analyzers, one on each arm, but only one was used at a time. Ruler scale is in centimeters [3]



Velocity Sensors, Figure 12 Calibration of a LAPS meter. Lag time was calculated for bovine serum albumin solutions pumped at 10 – 50 µl/min. The lag time was found to be inversely proportional to the flow rate [3]

Figure 9 shows the flow of water solution passing by the ion generator. The ions generated here are then transported until they are detected upon reaching the downstream ISFET. Fluid velocity is measured by the time difference between detection and generation of the ions. The time difference is called the flight time and is inversely proportional to the mean velocity. Knowing the fluid velocity


Physical isolation channel
Metallic electrode on silicon dioxide
Sensing Element
200μm

Velocity Sensors, Figure 13 Scanning electron micrograph of the top of a linear array of three fabricated flow sensors [7]



Velocity Sensors, Figure 14 Theoretical sensor temperature T_S versus fluid (water) velocity U, beginning at temperature T_0 and asymptotically approaching final ambient temperature T_f [7]

given that the relevant dimensions of the channel are also known, the flow rate can be determined as well. ISFET is said to have a fast response so it can be used to measure flow velocity in an operating range of μm/s to m/s. Figure 10 exhibits a typical output signal of an ISFET-based flow velocity sensor. It explains how the time of flight is determined. This output is obtained from an experiment where a constant electrical current of 30 μA is applied that generates hydroxyl ions. The arrow that points downwards marks the beginning of the flight time; where it ends is marked by the arrow pointing upwards.

Lag-After-Pulse-Separation (LAPS) Meter. The LAPS meter is a flow meter that measures flow rates of suspensions laden with protein or other charged macromolecules or particles [3]. The sensor prototype is shown in Fig. 11. The sensor system has a channel that branches into two subchannels. The subchannels merge again to allow the flow to continue. There is a pair of electrodes attached at the main channel (as shown in the left dotted circle in Fig. 11) called the separator. When the separator is not supplied with direct-current voltage the particles will move with the fluid. This produces a uniform flow in the main channel as well as in the two subchannels. However, when a finite-duration pulse of direct-current voltage is applied to the separator, the fluid with particles is forced to flow towards one of the subchannels.

There is also a pair of electrodes attached at each subchannels (as shown in the right dotted circle in Fig. 11) called the analyzer. The time taken for the pulse traveling downstream to reach the analyzer location is related to the inverse of the flow rates. The analyzer monitors particle concentration by measuring electric charge values. The pulse's arrival time at the analyzer is considered only when the electric charge reaches its defined maximum value. Figure 12 shows a typical output of the LAPS meter. It shows a graph where bovine serum albumin solution in deionized water is tested with a flow rate of 10 – 50 μl/min. The lag time is plotted against the inverse flow rate. It is found that the lag time is inversely proportional to the flow rate. Also, the time delay between the event and the detection is inversely proportional to the velocity.

Pulse Modality Flow Sensors. Pulse modality flow sensors measure liquid flow through the integrated channel sidewall using a pulse modality [7]. Figure 13 shows an image of the sensor taken using a scanning electron microscope, a device that produces high-resolution images of a sample surface [8]. It clearly shows the sensing element, the channel and the electrode.

The sensor applies the principle of heat transfer where its output signal is tied to the relationship between sensing element temperature and flow rate, between sensing element resistivity and temperature. Figure 14 shows the relationship between sensing element temperature and flow velocity. This sensor is claimed to produce fast and highly sensitive signals for regulation of microflow in the range 0.01 – 10 ml/min.

Future Directions for Research

Microfluidic velocity sensors are based on very sensitive structures and materials. Their sensor systems are developed using complicated fabrication technology, sophisticated measuring apparatus and at high production cost [10]. These are issues that require immediate attention because their commercialization is problematic. Microfluidic systems will achieve their full potential if micropumping operates at an optimum level where flow rate must be measurable and controllable based on the needs of the system. For an application that delivers protein to a microbioreactor at a precise rate using this miropumping operation then some feedback controls would be necessary to ensure that process disruption did not affect the delivery rate [3]. It is highly desirable for microfluidic systems to have necessary feedback controls to produce accurate flow rates.

Cross References

- ► Developing Flows
- ► Electric Current Monitoring Methods
- ► Fluid Metering
- ► Heat Transfer in Microchannel Flows
- ► MEMS-Based Biosensor
- ► Methods for Flow Rate Measurements

References

1. Kaltsas G, Nassiopoulou AG (1999) Novel C-MOS compatible monolithic silicon gas flow sensor with porous silicon thermal isolation. Sens Act 76:133–138
2. Fürjes P, Légrádi G, Dücsó C, Aszódi A, Bársony I (2004) Thermal characterisation of a direction dependent flow sensor. Sens Act A 115:417–423
3. Sengupta S, Ziaie B, Barocas VH (2004) Lag-after-pulsed-separation microfluidic flowmeter for biomacromolecular solutions. Sens Act B 99:25–29
4. Kohl M, Liu Y, Dittmann D (2004) A polymer-based microfluidic controller. 17th IEEE Int Conf Micro Electro Mechanic Sys :288–291
5. Navier-Stokes Equations: 3-dimensional-unsteady. Glenn Research Center. National Aeronautics and Space Administration. http://www.grc.nasa.gov/WWW/K-12/airplane/nseqs.html
6. Lienhard IV JH, Lienhard V JH (2006) A Heat Transfer Textbook, 3rd ed. Phlogiston Press, Cambridge, Massachusetts
7. Okulan N, Henderson HT, Ahn CH (2000) A pulsed mode micromachined flow sensor with temperature drift compensation. IEEE Transact Electron Devices 47(2):340–347
8. Wikipedia: The Free Encyclopedia. http://en.wikipedia.org/wiki/Microfluidics
9. Fung CKM, Sin MLY, Lei TKF, Chow WWY, Lai KWC, Li WJ (2005) Flow rate measurement inside polymer microfluidic systems using carbon nanotube sensors. Sensors 2005 IEEE Oct-Nov: 541–544
10. Poghossian A, Berndsen L, Schöning MJ (2003) Chemical sensor as physical sensor: ISFET-based flow-velocity, flow-direction and diffusion-coefficient sensor. Sens Act B 95:384–390

Venturi Diode

Definition

A version of a no-moving-part fluidic diode consisting of two series-connected components: a flow contraction upstream and a diffuser immediately downstream.
A successful type of a fluidic diode particularly suited for operation at quite high operating frequencies. Its operation may be explained by considering the difference in the widths or diameters of the issuing jets in the two opposing flow direction. The difference is due to the flow separation from the walls of the contraction which lacks the diffuser property of keeping the flow attached.

Cross References

- ► Fluidic Diodes
- ► Valve-Less Rectification Pumps
- ► Fluidic Rectification

V-Groove

Definition

Groove with a wedge-shaped cross section (i.e. V-shaped) machined into a plate utilized to manipulate the mean curvature of a fluid within the groove.

Cross References

- ► Surface-Directed Capillary Flow Systems

Viscoelastic

- ► Viscoelasticity

Viscoelasticity

HIONG YAP GAN, YEE CHEONG LAM
Division of Manufacturing Engineering School
of Mechanical and Aerospace Engineering, Nanyang
Technological University, Singapore, Singapore
ganh0002@ntu.edu.sg

Synonyms

Non-Newtonian; Viscoelastic; Relaxation;
Shear; Extensional

Definition

Subjected to an applied force, an elastic solid instantaneously deforms. The deformation is fully recovered with the removal of the force. In contrast, the deformation of a viscous fluid increases with time when a force is applied. With the removal of the force, a viscous fluid ceases to deform further, but any prior deformation remains. A viscoelastic material exhibits both elasticity and ▶ viscosity. Subjected to an applied force, it deforms and its deformation increases with time, i. e., it creeps. When the force is removed, only partial deformation is recovered instantaneously. It recovers more, but not all, of its deformation as time progresses. Depending on the time scale of interest, a viscoelastic material could behave solid-like or fluid-like or a combination of both.

Chemical and Physical Principles

Sir Isaac Newton proposed the law of viscosity in 1687 [1]. Subsequently, the analogous supposition, giving the modern form to the Newton hypothesis, was formulated by Navier and then by Stokes. Liquid with flow properties obeying the Newton hypothesis is called a Newton–Stokes liquid, or a Newtonian liquid. In a simple Newtonian shear flow, the shear stress is linearly proportional to the deformation rate,

$$\tau = \mu\dot{\gamma} \qquad (1)$$

where τ is the shear stress and $\dot{\gamma} = \mathrm{d}\gamma/\mathrm{d}t$ is the shear rate or rate of shear deformation. The Newtonian viscosity, μ, is constant for a given temperature and is independent of shear rate or stress. Thus, a plot of shear stress versus shear rate at a given temperature is a straight line with a constant slope.

Another model describing the mechanical properties of materials originated in the seventeen century is Hooke's law for a linear elastic solid [1],

$$\sigma = E\varepsilon \qquad (2)$$

where ε, σ and E are the strain, the stress and the elastic modulus, respectively.

Newton's law is satisfactory for describing the flow of simple liquids and gases with molecular weights less than $M_{\mathrm{wt}} \leq 1000\,\mathrm{g/mol}$ [2]. However, it is not adequate to describe the behaviors of polymer melts and simple liquids with the addition of high molecular weight macromolecules (polymers). For a given temperature, μ is no longer constant but depends on the flow conditions such as the shear rate $\dot{\gamma}(t)$ or the shear stress $\tau(t)$. Any fluid that does not obey the Newtonian relationship is termed as a non-Newtonian fluid.

The first person who paid attention to the effect of *viscoelasticity* was C. A. Coulomb in 1784 [1]. He showed that the damping in torsional oscillations of wires is caused by the viscoelasticity of the materials. Subsequently, it has been shown that fluids can also exhibit viscoelastic behavior, which has now been comprehensively documented over the last three decades. Some excellent references are *Viscoelastic Properties of Polymers* by Ferry [3], *The Dynamics of Polymeric Liquids* by Bird et al. [2] and *Rheological Phenomenon in Focus* by Boger and Walters [4].

Viscoelastic Behavior

Creep-and-recovery and stress relaxation experiments are the simple methods to illustrate viscoelasticity.

Creep and Recovery Tests

When a Newtonian fluid is stretched by a stress at $t = t_0$, as shown in Fig. 1a(1), the strain $\varepsilon(t)$ will increase linearly with time, see Fig. 1a(2). If the stress is removed at $t = t_{\mathrm{s}}$, the strain $\varepsilon(t)$ will remain at the level reached at $t = t_{\mathrm{s}}$, i. e., $\varepsilon(t_{\mathrm{s}})$.

When a Hookean solid is stretched, the strain $\varepsilon(t)$ will instantly increases proportionally to the stress to $\varepsilon(t_0)$, see Fig. 1a(3). $\varepsilon(t)$ will remain constant until the stress is removed at $t = t_{\mathrm{s}}$, at which time all the strain is recovered and $\varepsilon(t_{\mathrm{s}}) = 0$.

For a viscoelastic material under a constant applied stress, the strain $\varepsilon(t)$ shows a delay in response to the applied stress, see Fig. 1a(4). When the load is removed at $t = t_{\mathrm{s}}$ a viscoelastic liquid will recover partially its deformation at t = t_{s} over a period of time. Some deformation remains permanently. In contrast, for a viscoelastic solid, on load removal, the deformation recovery over time is relatively faster, and almost all the deformation may be recovered over a sufficiently long period of time.

Stress Relaxation Test

Figure 1b(1) shows at time $t = t_0$ a material is subjected to a strain step, and with the strain remains at this value for a prolong period of time. For a Newtonian fluid, the stress, $\tau(t)$, will increase suddenly with the sudden and step increase in strain. However, $\tau(t)$ will instantly drops to zero, see Fig. 1b(2). Thus, an immediate and complete stress relaxation occurs.

For a Hookean solid, the stress $\tau(t)$ remains constant after strain step at $t = t_0$, i. e., no stress relaxation occurs.

After the application of a strain step at $t = t_0$, both viscoelastic liquid and solid show a non-linear delay in stress relaxation as a function of their viscoelastic properties, see


Stress (τ)
τ₀
t₀=0
tₛ Time
(1) Constant stress applied over t₀< t <tₛ
a
Strain (γ)
t₀=0
tₛ Time
(2) Ideal viscous liquid response
Strain (γ)
t₀=0
tₛ Time
(3) Ideal elastic solid response
Strain (γ)
VE liquid
VE solid
t₀=0
tₛ Time
(4) Viscoelastic material response
Strain (γ)
γ₀
t₀=0
Time
(1) Constant stress applied, t > t₀
b
Stress (τ)
t₀=0
Time
(2) Ideal viscous liquid response
Stress (τ)
t₀=0
Time
(3) Ideal elastic solid response
Stress (τ)
VE solid
τₑ
VE liquid
t₀=0
Time
(4) Viscoelastic material response
(1) Maxwell liquid model
Stress (τ)
τ₀
t₀=0
tₛ Time
Strain (γ)
τ₀/μ
τ₀/G
τ₀/μ tₛ
t₀=0
tₛ Time
(2) Creep and recovery test
Strain (γ)
γ₀
t₀=0
Time
G₀γ₀
τ(t) = (G₀γ₀) exp (-t / λ)
t₀=0
tₛ Time
(3) Stress relaxation test
c

Viscoelasticity, Figure 1 (**a**) Creep and recovery tests: (1) stress step (2) response of an ideal viscous liquid (3) response of an ideal elastic solid (4) response of two different viscoelastic materials, both are showing delayed recovery of deformation. (**b**) Stress relaxation tests: (1) strain step (2) ideal viscous liquid relaxation curve (3) ideal elastic solid relaxation curve (4) Stress relation curves of two viscoelastic materials, both are showing delayed relaxation. (**c**) (1) Schematic of Maxwell liquid model an its response to (2) creep recovery test and (3) stress relaxation test

Fig. 1b(4). For a viscoelastic liquid, a delayed but complete stress relaxation takes place if the period of observation is sufficiently long. However, for a viscoelastic solid, a delayed and partial stress relaxation takes place even after a long period of observation.

Mathematical Model for Viscoelastic Fluid Behavior

It is rather complex to describe viscoelastic behaviors mathematically. We will only focus here the simple, but representative Maxwell model for viscoelastic liquids. A mechanical analogue of a Maxwell liquid model is obtained by a serial combination of a spring and a dashpot, see Fig. 1c(1). If the individual strain rates of the spring and the dashpot respectively are $\dot{\varepsilon}_{\text{solid}}$ and $\dot{\varepsilon}_{\text{liquid}}$, then the total strain rate $\dot{\varepsilon}$ is given by the sum of these two components:

$$\dot{\varepsilon} = \dot{\varepsilon}_{\text{fluid}} + \dot{\varepsilon}_{\text{solid}}$$

$$\Rightarrow \quad \dot{\varepsilon} = \frac{\tau}{\mu} + \frac{\dot{\tau}}{G} \tag{3}$$

where G is the shear modulus.

Incorporating the Hooke's law of elasticity and Newton's law of viscosity with Eq. (3), the stress-strain relationship can be expressed as

$$\mu\dot{\varepsilon} = \tau + \lambda\dot{\tau} \tag{4}$$

where $\dot{\tau}$ is the time derivative of τ, $\lambda = \mu/G$ is the relaxation time. From Eq.(4), if a constant stress is applied to a Maxwell-model fluid, the strain rate will be constant and the strain will increase indefinitely, the so called creep phenomenon, see Fig 1c(2). If instead, a constant strain is applied to the fluid, the stress will decay as $\exp(-t/\lambda)$, the so called stress relaxation, see Fig. 1c(3). An important feature of the Maxwell model is its predominantly fluid-like response, see Fig. 1c. However, comparing Fig. 1c(2) and 1c(3) to Fig 1a(2) and 1a(4) respectively, it can be observed that the Maxell model is only an approximation to a viscoelastic liquid.

There are other models based on springs and dashpots such as the simple Kelvin–Voigt model for viscoelastic solid and the Burgers model. Reader is referred to [1–5] for details. Other elementary models are the dumbbell, bead-spring representations, network and kinetic theories. However, the most notable limitation of all these models is their restriction to small strain and strain rates [2, 3].

Viscoelastic Fluid Behaviors

Polymeric solutions are inherently viscoelastic due to their long molecular chains. Dilute polymeric solutions will be of interests for microfluidic and nanofluidic applications, due to their ease of implementation. Since the polymer coils in a dilute solution are isolated and independent in their molecular movements, their viscoelastic behavior can be explained by the deformation of the individual coil or molecule in the stream [2, 3]. As a result, the viscoelasticity of polymer solutions is generally attributed to the deformation of polymer chains and the consequent generation of unequal normal stresses.

Steady Shear Flows

For a one-dimensional steady shear flow of a fluid between two planes, the velocities of an infinitesimal element of fluid in the y- and z-directions are zero. The velocity in the x-direction is a function of y only. Note that in addition to the shear stress τ_{yx} (refer to τ subsequently) there are three normal stresses denoted by τ_{xx}, τ_{yy}, τ_{zz} within the sheared fluid. Weissenberg in 1947 [6] was the first to observe that the shearing motion of a viscoelastic fluid gives rise to unequal normal stresses, known as Weissenberg effects. Since the pressure in a non-Newtonian fluid cannot be defined, and as the normal stress differences [2, 3], $\tau_{\mathrm{xx}} - \tau_{\mathrm{yy}} = N_1$ and $\tau_{\mathrm{yy}} - \tau_{\mathrm{zz}} = N_2$, are more readily measured than the individual stresses, it is therefore customary to express N_1 and N_2 together with the shear stress τ as functions of the shear rate $\dot{\gamma}_{\mathrm{yx}}$ to describe the viscoelastic behavior of a material in a simple shear flow.

The first and second normal stress differences N_1 and N_2can be expressed in terms of two coefficients, ψ_1 and ψ_2, defined as follows:

$$\psi_1 = \frac{N_1}{\gamma_{\mathrm{yx}}^2} \quad \text{and} \quad \psi_2 = \frac{N_2}{\gamma_{\mathrm{yx}}^2} \tag{5}$$

It is common that the first normal stress difference N_1 is higher than the shear stress τ. The ratio of N_1 to τ is often taken as a measure of how elastic a liquid is; specifically (N_1/τ) is referred as the recoverable shear.

Elongational Flow

Three main types of elongational flow are uniaxial, biaxial and planar. Although resistance to flow can be referred to loosely as an elongational or extensional viscosity (which further depends upon the type of elongational flow), this parameter generally is not constant.

For simplicity, consider the behavior of an incompressible fluid element which is being elongated at a constant strain rate $\dot{\varepsilon}$ in the x-direction (uniaxial extensional flow). For an incompressible fluid, the volume of the element must remain constant and therefore it must contract in both the y- and z-directions at the rate of $(\dot{\varepsilon}/2)$ for a system symmetrical in these directions. The three components of the velocity vector $\boldsymbol{V_i}$ are given by:

$$\boldsymbol{V_x} = \dot{\varepsilon} x\,, \quad \boldsymbol{V_y} = -\frac{\dot{\varepsilon}}{2} y\,, \quad \boldsymbol{V_z} = -\frac{\dot{\varepsilon}}{2} z \tag{6}$$

The rate of elongation in the x-direction can be written as:

$$\dot{\varepsilon} = \frac{\partial \boldsymbol{V_x}}{\partial x} \tag{7}$$

In uniaxial extension, the elongational viscosity μ_{e} can then be defined as:

$$\mu_{\mathrm{e}} = \frac{\tau_{\mathrm{xx}} - \tau_{\mathrm{yy}}}{\dot{\varepsilon}} \quad \text{or} \quad \frac{\tau_{\mathrm{xx}} - \tau_{\mathrm{zz}}}{\dot{\varepsilon}} \tag{8}$$

The earliest determinations of elongational viscosity were for the simplest case of uniaxial extension or stretching of a fiber or filament of liquid. Trouton [7], and subsequently many other investigators, found that at low strain (or elongation) rates, the elongational viscosity μ_{e} was three times the shear viscosity μ. The ratio μ_{e}/μ is referred to as the Trouton ratio, T_{r}:

$$T_{\mathrm{r}} = \frac{\mu_e}{\mu} = 3 \tag{9}$$

The value of 3 for Trouton ratio refers specifically to the viscosities in shear and elongation for an incompressible Newtonian fluid.

By analogy, the Trouton ratio for a non-Newtonian fluid, for which T_r is not necessary equal to three, can be defined as:

$$T_\mathrm{r} = \frac{\mu_e(\dot{\varepsilon})}{\mu(\dot{\gamma})} \tag{10}$$

Since the Trouton ratio depends on both $\dot{\varepsilon}$ and $\dot{\gamma}$ in Eq. (10), there is some ambiguity in choosing their values. To provide a convenient estimate without this ambiguity, Jones et al. [8] proposed the following definition:

$$T_\mathrm{r} = \frac{\mu_e(\dot{\varepsilon})}{\mu(\sqrt{3}\dot{\varepsilon})} \tag{11}$$

i. e., in the denominator, the shear viscosity is evaluated at $\dot{\gamma} = \sqrt{3}\,\dot{\varepsilon}$. They also suggested that for inelastic isotropic fluids, the Trouton ratio is equal to 3 for all values of $\dot{\varepsilon}$ and $\dot{\gamma}$ and any departure from the value of 3 can be ascribed unambiguously to *viscoelasticity*.

A common behavior of polymeric solutions [9–11] and polymer melts [12] is that the Trouton ratio is greater than three at moderate and higher deformation rate. Their typical behaviors are illustrated in Fig. 2, which show that the Trouton ratio can be a function of both strain and strain rate.

Dimensionless Parameters

The relaxation time (λ), which describes the time required for the polymer coil to relax from a deformed state back to its equilibrium configuration, is a key parameter for characterizing a viscoelastic fluid. For a fluid with large λ, the stresses relax slowly and the elastic effects can be observed even at low deformation rates. A fluid with small λ can also exhibit significant elastic effects provided that the deformation rate is high. Clearly, both the fluid characteristic time (the relaxation time) and the flow characteristic time (e. g. the inverse of the deformation rate) are crucial in determining the viscoelastic response of a viscoelastic liquid. For many polymeric liquids, λ lies between 10^{-3} s for dilute solutions and 10^3 s for concentrated solutions.

The relative importance of elasticity in a flow is often described by the Deborah number, De introduced by Reiner [13]. This number may be interpreted as the ratio of the magnitudes of the elastic forces to that of the viscous forces. It is defined as the ratio of a characteristic time (time scale) of the fluid λ to a characteristic time of the flow system t_flow [2]

$$\mathrm{De} = \frac{\lambda}{t_\mathrm{flow}} \tag{12}$$

The characteristic time of the fluid is often taken to be the largest time constant describing the slowest molecular motions, or else some mean time constant determined by linear viscoelasticity. The characteristic time may also be chosen as a time constant in a constitutive equation. The characteristic time for the flow is usually taken to be the time interval during which a typical fluid element experiences a significant sequence of kinematic events, for example the duration of a characteristic experimental observation. If the flow following a material particle is steady, the characteristic time can be the reciprocal of a characteristic strain rate.



Viscoelasticity, Figure 2 Extensional viscosity curve of polymeric solution and polymer melt. (**a**) Comparison between steady shear and elongation response (**b**) Trouton ratio as a function of total Hencky strain $\varepsilon = \dot{\varepsilon}_0 t$ for polymeric solution

Rheological Measurements

Rheological properties of the same polymeric solution measured in shear and elogational flows can be very different as discussed in earlier section. However, a cursory examination of current textbooks on rheology (e. g. Bird et al. [2], Ferry [3], Tanner [14]) shows that shear rheology dominates and research in extensional rheology is comparatively much more recent. The measurements of the shear properties of polymeric fluids are well established and a number of ► rheometers are available for both melts and dilute polymeric solutions. Lately, more efforts have been directed in measuring the extensional properties of fluids [8, 9, 15–19].

In practice, the steady shear and oscillatory tests are commonly conducted via rotational rheometers, and the extensional test is widely performed in *liquid filament rheometers* or *capillary breakup extensional rheometers* (CaBER).

Rotational Shear Measurements

Steady Shear Flow Curves Steady shear flow generally is a viscosity measurement on materials undergoing steady and continuous shear. A flow curve, viscosity (μ) versus shear rate ($\dot{\gamma}$), across a wide range of shear rate is often used to design pumps and mixing devices. This method is also used to provide flow behavior which indicates the relationship of shear rate to shear stress between suitable limits. A commonly observed feature of polymeric solutions is the shear thinning characteristic, i. e., the decrease of viscosity with increasing shear rate, which can be determined from this technique. This typical flow curve exhibits two Newtonian plateaus – one at low shear and another at high shear regimes. The shear thinning region lies between the two limiting conditions and may extend over a few decades of shear rate.

However, dynamic measurements, such as the oscillatory tests, are preferred in practice over the steady shear measurements for determining the viscoelastic properties of fluids. This is not only because of the difficulty in determining the first normal stress coefficient accurately, the determination of a fluid's viscosity by steady shear measurement is only a partial characterization of a viscoelastic fluid's properties.

Dynamic Oscillatory Experiments The dynamic rheological properties of a polymeric solution can be determined by small-amplitude oscillation tests [2]. In small amplitude oscillatory measurements, a sinusoidally varying shear stress field is imposed on a fluid and the amplitude of the resulting shear strain and phase angle between the imposed stress and the strain is measured. The test is said to be in the *linear viscoelastic* regime if the strain is linearly proportional to the imposed stress and the response is sinusoidal [1, 5].

In practice, dynamic oscillatory measurements are sensitive probes of molecular structure and interactions, for examples in emulsions and dispersions. Oscillatory measurements probe emulsion structure without destroying it. This is accomplished by applying very small sinusoidal displacements or strains to the emulsion at controlled amplitude and frequency. In general, there are two mechanisms for a material to respond to a deformation:

- elastic energy storage (G', known as storage modulus), and
- viscous dissipation (G'', known as loss modulus).

G', which is proportional to the strain in-phase with the stress, provides information about the elasticity of a material. G'', the loss modulus, is proportional to the stress out-of-phase with the displacement. These parameters are termed the elastic and viscous loss moduli, G' & G'' respectively. The values of the respective stresses measured are divided by the appropriate strains, resulting in the respective moduli. The shapes of the curves for G' and G'' versus the test frequency ω for polymeric solutions are described by Ferry [3]. At low frequency, G' and G' are proportional to ω^2 and ω respectively. As frequency increases, the slope of these curves decreases, as illustrated in Fig. 3.

Qualitatively, the stress created by imposing oscillatory strains will be a function of the amplitude of strain, its frequency, and the properties of the polymeric solution. By applying sufficiently small strains, we can minimize the strain dependency from the material response. Thus, the amplitude of strain is no longer an important consideration, resulting in a *linear viscoelastic* response. Small



Viscoelasticity, Figure 3 Dynamic test: frequency oscillation sweep. For viscoelastic fluid of 1 wt% poly (ethylene-oxide)(PEO) in 55 wt% glycerol water. Molecular weight of PEO is 2×10^6 g/mol strain measurements can be important for certain application as they do not adversely affect the structure of the fluid.

These linear viscoelastic dynamic moduli are functions of frequency. For a suspension or an emulsion material at low frequency, elastic stresses relax and viscous stresses dominate with the result that the loss modulus, G'', is higher than the storage modulus, G'. For a dilute solution, G'' is larger than G' over the entire frequency range but they approach each other at higher frequencies as shown in Fig. 3.

The Maxwell relaxation time is commonly evaluated from the first normal stress difference measurement,

$$\lambda_M = \frac{N_1}{2\dot{\gamma}^2\mu_0} \tag{13}$$

However, at zero deformation rate, where the simple fluid theory applies, can be evaluated from the oscillatory data by

$$\lambda_M^0 = \lim_{\dot{\gamma}\to 0} \frac{N_1}{2\dot{\gamma}^2\mu_0} = \lim_{\omega\to 0} \frac{G'}{\omega^2\mu_0} \tag{14}$$

It was shown that for water soluble polymeric solution such as Separan AP30, NP10 and Keltrol with polymer concentration less than approximately 1500, 5000, and 500 ppm, respectively, is independent of polymer concentration [20]. These observations were consistent with the molecular theories such as the Zimm theory, which states that at infinite dilution, the relaxation time is independent of polymer concentration and is given by

$$\lambda_z = 0.423\frac{[\mu]\,\mu_s M_{wt}}{RT} \tag{15}$$

where $[\mu]$ is the intrinsic viscosity [2, 3] and μ_s is the solvent viscosity.

By Cox–Mertz rule, for polymeric solutions at low frequency and shear rate in accordance with the simple fluid theory, the zero shear viscosity can be estimated by [2, 20]

$$\mu_0 = \lim_{\dot{\gamma}\to 0} \mu = \lim_{\omega\to 0} \left|\mu^*\right| = \lim_{\omega\to 0} \left(\frac{G"}{\omega}\right) \tag{16}$$

Key Research Findings

Extensional Rheological Measurement

Elongational or extensional flow of polymeric fluids are experienced in important industry processes, such as food dispersion, paints, adhesives, coating, inkjet printing, enhanced oil recovery, and lubrication. However, extensional properties cannot be determined from shear rheometry experiments.

Filament-stretching has been studied for obtaining extensional properties of polymeric solutions and melts. A comprehensive review of the flow dynamics of filament-stretching is provided by McKinley and Sridhar [9]. Subsequently, *liquid filament rheometers* or *capillary breakup extensional rheometers* (CaBER) has been developed for the characterization of the dynamics of complex fluids undergoing extensional flows.

Technical Aspect of CaBER Measurements

Recently, rheometer for measuring extensional properties is commercially available. It is called the CaBER 1 (the Capillary Breakup Extensional Rheometer). It was designed by the Cambridge Polymer Group and is manufactured by Thermo Haake. The measuring procedure involves the placing of a small quantity of sample fluid between two parallel plates. A fluid filament is formed when the sample fluid is subjected to a rapid extensional step strain, see Fig. 4. The filament evolution as a function of time is dictated by the surface tension and the viscoelastic stresses of the fluid. The surface tension is trying to *pinch off* the filament and the extensional properties of the sample are trying to prevent it. A laser micrometer measures the midpoint diameter of the gradually thinning fluid filament when the upper plate extends to its final position. From the measured data, several elongational rheological properties can be determined such as the extensional viscosity, evolution of the filament diameter as a function of time, the extensional deformation and deformation rate, and the filament break-up time.

In general, the changes of a fluid filament are governed by a balance of forces on the filament. Assuming that a fluid sample is at rest initially, and is subjected to a constant strain rate subsequently. With reference to the mid-diameter (D_{mid}) of the filament and ignoring the very small inertial effects [10], the governing equation can be expressed as

$$\mu_e\dot{\varepsilon}_0 \equiv \langle \tau_{zz} - \tau_{rr} \rangle = \frac{4F_z}{\pi D_{\text{mid}}^2} - \frac{2\rho g V_0}{\pi D_{\text{mid}}^2} - \frac{2\sigma}{D_{\text{mid}}} \tag{17}$$

where ρ and V_0 is the density of the sample fluid and the sample volume respectively. σ is the surface tension of the fluid, which has to be measured separately. g is the gravitational constant. F_z is the tensile force acting on the column ends, and $\langle \tau_{zz} - \tau_{rr} \rangle$ represents the non-Newtonian contribution to the average total normal stress difference over the filament cross section.

Equation (17) is model-dependent and the resulting solution to the differential equation depends on how the polymeric contribution to the stress varies with the rate of deformation. Solutions to this evolution equation have


Final position
Laser measuremant at midpoint of filament
$t = t_0$
$t = t_1$
$t = t_2$
$t = t_3$
$t = t_4$
where, $t_4 > t_3 > t_2 > t_1 > t_0$

Viscoelasticity, Figure 4 Sequence of a CaBER 1 experiment snapshots

Viscoelasticity, Table 1 Evolution of the mid-filament diameter in a fluid filament undergoing capillary-driven breakup. Note: λ_c is the characteristic relaxation time of the sample, t_c is the filament break-up time and μ_S is the Newtonian viscosity of the solvent

Constitutive Model	Growth of Filament	Inferred Parameters
Newtonian Fluid, $\tau = \mu\dot{\gamma}$	$D_{mid}(t) = 0.142(\sigma/\mu_S)(t_c - t)$	t_c, σ/μ_S
Power Law Fluid, $\tau = K\dot{\gamma}^n$	$D_{mid}(t) = 2^{1-n}(0.142)(\sigma/K)(t_c - t)^n$	t_c, $\sigma/K, n$
Upper Convected Maxwell	$D_{mid}(t) = D_0\left(GD_0/\sigma\right)^{1/3}\exp(-t/3\lambda_c)$	λ_c, G/σ

been found for a number of models [17–19] and are summarized in Table 1.

The Apparent Extensional Viscosity

The evolution of filament diameter is driven by the capillary pressure and resisted by the extensional stress in the fluid. Thus, measurements can also be represented in terms of an apparent extensional viscosity, define as

$$\mu_{\text{app}}(\varepsilon) = \langle \tau_{zz} - \tau_{rr} \rangle / \dot{\varepsilon}(t) \tag{18}$$

where under steady elongation flow, the natural-strain or Hencky strain [9] is given by

$$\varepsilon\,(0, t) = \dot{\varepsilon}_0 t = \ln(L(t)/L_0) = -2\ln(D(t)/D_0) \tag{19}$$

Hence, the apparent viscosity can be written as,

$$\mu_{\text{app}}(\varepsilon) = \frac{\frac{2\sigma}{D_{\text{mid}}(t)}}{-\frac{2}{D_{\text{mid}}(t)}\frac{\mathrm{d}D_{\text{mid}}}{\mathrm{d}t}} = \frac{\sigma}{\frac{\mathrm{d}D_{\text{mid}}}{\mathrm{d}t}} \tag{20}$$

Examples of Application

- Inkjet printing cartridge: a micro-entry flow (contraction flow) of a non-Newtonian fluid.
- Micro-injection molding: scaled-down version of injection molding (contraction flow).
- Flow focusing of emulsion: micro-contraction is used to generate emulsion droplet.
- Viscoelastic micro-mixer: elastically induced chaotic flow instabilities through contraction/expansion geometrical configuration in a microchannel.
- Microfluidics rectifier: a channel whose resistance to flow changes based on the direction of the flow.

Cross References

► Chaotic Mixing
► Chaotic Mixing Based on Viscoelasticity
► Droplet Dispensing
► Droplet Microreactors
► Microfluidic Mixing
► Micromolding
► Micromolding (Injection and Compression Molding)
► Non-Newtonian Fluids in Microchannel
► Non-Newtonian Fluids in Microfluidics
► Viscosity

References

1. Malkin AY, Isayev AI (2006) Rheology: Concepts, Methods & Applications. ChenTec, Toronto
2. Bird RB, Armstrong RC, Hassager O (1987) Dynamics of Polymeric Liquids 1. John Wiley & Sons, New York
3. Ferry JD (1980) Viscoelastic Properties of Polymers. John Wiley & Sons, New York
4. Boger DV, Walters K (1993) Rheological Phenomena in Focus. Elsevier, New York
5. Mezger TG (2006) The Rheology Handbook: For Users of Rotational and Oscillatory Rheometers. Vincentz Network, Germany

6. Weissenberg K (1947) A Continuum Theory of Rheological Phenomena. Nature 159:310–311
7. Trouton FT (1906) On the Viscous Traction and its Relation to that of Viscosity. Proc R Soc A77:426–440
8. Jones DM, Walters K, Williams PR (1987) The Extensional Viscosity of Mobile Polymer Solutions. Rheol Acta 26:20–30
9. McKineley GH, Sridhar T (2002) Filament-Stretching Rheometry of Complex Fluids. Annu Rev Fluid Mech 34:375–415
10. Li L, Larson RG, Sridhar T (2000) Brownian Dynamics Simulation of Dilute Polystyrene Solutions. J Rheol 4:291–322
11. Gupta RK, Nguyen DA, Sridhar T (1991) Extensional Viscosity of Dilute Polystyrene Solutions: Effect of Concentration and Molecular Weight. Phys Fluid 12:1296–1318
12. Cogswell FN (1972) Measuring the Extensional Rheology of Polymer Melts. J Rheol 16:383–403
13. Reiner M (1964) The Deborah Number. Phys Today 17:62
14. Tanner RI (2000) Engineering Rheology. Oxford, Clarendon
15. Tirtaatmadja V, Sridhar T (1993) A Filament Stretching Device for Measurement of Extensional Viscosity. J Rheol 37:1081–1102
16. Sridhar T, Tirtaatmadja V, Nguyen DA, Gupta RK (1991) Measurement of Extensional Viscosity of Polymer Solutions. J Non-Newt Fluid Mech 40:271–280
17. Entov VM, Hinch EJ (1997) Effect of a Spectrum of Relaxation Times on the Capillary Thinning of a Filament of Elastic Liquid. J Non-Newt Fluid Mech 72:31–54
18. Bazilevsky AV, Entov VM, Rozhkov AN (1990) Liquid Filament Microrheometer and Some of its Applications. 3rd Eur Rheol Conf, Elsevier
19. McKinley GH, Tripathi A (2000) How to Extract the Newtonian Viscosity from Capillary Breakup Measurements in a Filament Rheometer. J Rheol 44:653–671
20. Tam KC, Tiu C (1996) Water Soluble Polymers (Rheological Properties). Polymeric Materials Encylopedia. CRC Press, Boca Raton

Viscometer

► Rheometer

Viscosity

Synonyms

Compactness; Plasticity

Definition

Viscosity is a measure of the resistance of a fluid to deform under shear stress. It describes a fluid's internal resistance to flow and may be thought of as the friction forces that act within a moving fluid. Viscosity can also be defined as the ratio of the shear stress to the strain rate.

Cross References

- ► Micro- and Nano-Scale Anemometry: Implication for Biomedical Applications
- ► Chaotic Mixing Based on Viscoelasticity
- ► Droplet Dispensing
- ► Microfluidic Mixing
- ► Micromolding
- ► Micromolding (Injection and Compression Molding)
- ► Non-Newtonian Fluids in Microchannel
- ► Non-Newtonian Fluids in Microfluidics
- ► Viscoelasticity

Viscous Dissipation

GIAN LUCA MORINI
Institute of Physics, DIENCA Università di Bologna,
Bologna, Italy
gianluca.morini@mail.ing.unibo.it

Synonyms

Internal friction

Definition

The irreversible process by means of which the work done by a fluid on adjacent layers due to the action of shear forces is transformed into heat is defined as viscous dissipation.

Overview

The equation of continuity and the thermal energy balance on a differential element fixed in a pure flowing fluid can be written as follows:

$$\begin{aligned} -\frac{1}{\rho}\frac{\mathrm{D}\rho}{\mathrm{D}t} &= \nabla\cdot\boldsymbol{v} \\ \rho\frac{\mathrm{D}U}{\mathrm{D}t} &= -\nabla\cdot\boldsymbol{q} - p\,(\nabla\cdot\boldsymbol{v}) - \bar{\boldsymbol{\tau}} : \nabla\boldsymbol{v} \end{aligned} \qquad (1)$$

in which U is the specific internal energy of the fluid, p the pressure, $\boldsymbol{v}$ the velocity vector, $\boldsymbol{q}$ the heat flux, ρ the fluid density, t the time and $\bar{\boldsymbol{\tau}}$ the viscous tensor.

The second term on the right-hand side of Eq. (1) represents the reversible work done by the fluid against the external pressure field; this term is linked to the compressibility of the fluid and is known in the literature as *flow work*. The third term on the right-hand side of Eq. (1) is linked to the work done by the fluid on adjacent layers due to the action of the shear forces; this work is transformed into heat by means of an irreversible process called *viscous dissipation* in the English language literature and as *internal friction* in the Russian literature.

The effect of the viscous dissipation on heat transfer is significant especially for high-velocity flows, highly viscous flows even at moderate velocities, for fluids with a moderate Prandtl number and moderate velocities with small wall-to-fluid temperature difference or with low wall heat fluxes and flowing through microchannels.

Basic Methodology

Since the internal energy of a real fluid can be related to the temperature and to the fluid specific heat by means of the equation

$$\mathrm{d}U = c_\mathrm{V}\,\mathrm{d}T + \left[T\left(\frac{\partial p}{\partial T}\right)_\mathrm{V} - p\right]\mathrm{d}V \tag{2}$$

one can write the total derivative of the internal energy in terms of the fluid temperature as follows:

$$\frac{\mathrm{D}U}{\mathrm{D}t} = \left[T\left(\frac{\partial p}{\partial T}\right)_\mathrm{V} - p\right]\frac{\mathrm{D}V}{\mathrm{D}t} + c_\mathrm{V}\frac{\mathrm{D}T}{\mathrm{D}t} \tag{3}$$

where V is the specific volume of fluid, T is the absolute fluid temperature and c_V is the specific heat at constant volume.

The continuity equation allows one to write the derivative term of the fluid volume in the form

$$\frac{\mathrm{D}V}{\mathrm{D}t} = \frac{\mathrm{D}}{\mathrm{D}t}\left(\frac{1}{\rho}\right) = -\frac{1}{\rho^2}\frac{\mathrm{D}\rho}{\mathrm{D}t} = \frac{1}{\rho}\left(\nabla\cdot\boldsymbol{v}\right) \tag{4}$$

By combining Eq. (4) with Eq. (3) and the thermal energy balance (Eq. (1)), one obtains

$$\rho c_\mathrm{V}\frac{\mathrm{D}T}{\mathrm{D}t} = -\nabla\cdot\boldsymbol{q} - T\left(\frac{\partial p}{\partial T}\right)_\mathrm{V}\left(\nabla\cdot\boldsymbol{v}\right) - \bar{\boldsymbol{\tau}}:\nabla\boldsymbol{v} \tag{5}$$

in which the energy balance is expressed by means of the fluid temperature and the physical properties of the fluid. In Eq. (5) it is evident that the reversible work done against the pressure field is linked to the fluid compressibility. More explicitly, if one considers the definition of the thermal expansion coefficient (β) and of the volume compressibility (χ)

$$\beta = -\frac{1}{\rho}\left(\frac{\partial\rho}{\partial T}\right)_\mathrm{p} \quad \chi = \frac{1}{\rho}\left(\frac{\partial\rho}{\partial p}\right)_\mathrm{T} \tag{6}$$

the thermal energy equation for viscous flows can be written as follows:

$$\begin{aligned}\rho c_\mathrm{V}\frac{\mathrm{D}T}{\mathrm{D}t} &= -\nabla\cdot\boldsymbol{q} - \frac{\beta}{\chi}T\left(\nabla\cdot\boldsymbol{v}\right) - \bar{\boldsymbol{\tau}}:\nabla\boldsymbol{v}\\ &= -\nabla\cdot\boldsymbol{q} + \frac{\beta}{\chi}T\left[\frac{1}{\rho}\frac{\mathrm{D}\rho}{\mathrm{D}t}\right] - \bar{\boldsymbol{\tau}}:\nabla\boldsymbol{v}\end{aligned} \tag{7}$$

By remembering the following relation between the fluid specific heats:

$$c_\mathrm{p} - c_\mathrm{V} = T\left[\left(\frac{\partial V}{\partial T}\right)_\mathrm{p}\frac{\mathrm{d}p}{\mathrm{d}T} + \left(\frac{\partial p}{\partial T}\right)_\mathrm{V}\frac{\mathrm{d}V}{\mathrm{d}T}\right] \tag{8}$$

the thermal energy equation (Eq. (7)) can be expressed in the following alternative form:

$$\rho c_\mathrm{p}\frac{\mathrm{D}T}{\mathrm{D}t} = -\nabla\cdot\boldsymbol{q} + \beta T\frac{\mathrm{D}p}{\mathrm{D}t} - \bar{\boldsymbol{\tau}}:\nabla\boldsymbol{v} \tag{9}$$

in which the fluid specific heat at constant pressure is involved. Equation (9) is the version of the thermal energy quoted in many textbooks [1, 2]. For Fourier fluids the first term on the right-hand side of Eq. (9) can be expressed in terms of temperature gradient by using the Fourier law:

$$-\nabla\cdot\boldsymbol{q} = \nabla\cdot\left(k\nabla T\right) = k\nabla^2 T \tag{10}$$

where the last equality is obtained only for fluids with a constant thermal conductivity.

It is possible to demonstrate that, if the working fluid is Newtonian, the *viscous dissipation* term can be written as follows (i. e. in Cartesian coordinates):

$$\begin{aligned}\bar{\boldsymbol{\tau}}:\nabla\boldsymbol{v} &= -\mu\Phi\\ &= -\mu\left[-\frac{2}{3}\left(\nabla\cdot\boldsymbol{v}\right)^2 + 2\left(\frac{\partial v_x}{\partial x}\right)^2\right.\\ &\quad + 2\left(\frac{\partial v_y}{\partial y}\right)^2 + 2\left(\frac{\partial v_z}{\partial z}\right)^2 + \left(\frac{\partial v_z}{\partial y} + \frac{\partial v_y}{\partial z}\right)^2\\ &\quad \left. + \left(\frac{\partial v_x}{\partial z} + \frac{\partial v_z}{\partial x}\right)^2 + \left(\frac{\partial v_y}{\partial x} + \frac{\partial v_x}{\partial y}\right)^2\right]\end{aligned} \tag{11}$$

Equation (11) provides evidence that viscous heating can be considered as the sum of two terms:

- the rate of viscous dissipation due to the contribution of the density variation; and
- the rate of viscous dissipation for an incompressible fluid (Φ_inc).

$$\bar{\boldsymbol{\tau}} : \nabla \boldsymbol{v} = -\mu\Phi = -\mu\left[-\frac{2}{3}(\nabla\cdot\boldsymbol{v})^2 + \Phi_{\text{inc}}\right] = -\mu\left[-\frac{2}{3}\frac{1}{\rho^2}\left(\frac{\mathrm{D}\rho}{\mathrm{D}t}\right)^2 + \Phi_{\text{inc}}\right] \quad (12)$$

If the fluid density is considered as a function of the pressure and of the temperature ($\rho = \rho(p, T)$), by using the definition of the volume compressibility and of the coefficient of thermal expansion, it is possible to write

$$\frac{\mathrm{d}\rho}{\rho} = -\beta\,\mathrm{d}T + \chi\,\mathrm{d}p \quad (13)$$

For this reason the viscous dissipation term for a real fluid can be written as follows:

$$\bar{\boldsymbol{\tau}} : \nabla \boldsymbol{v} = -\mu\Phi = -\mu\left[-\frac{2}{3}\left(\chi\frac{\mathrm{D}p}{\mathrm{D}t} - \beta\frac{\mathrm{D}T}{\mathrm{D}t}\right)^2 + \Phi_{\text{inc}}\right] \quad (14)$$

Thus, the general expression of the thermal energy equation for a real Newtonian fluid becomes

$$\rho c_{\mathrm{p}}\frac{\mathrm{D}T}{\mathrm{D}t} = -\nabla\cdot\boldsymbol{q} + \beta T\frac{\mathrm{D}p}{\mathrm{D}t} + \mu\left[-\frac{2}{3}\left(\chi\frac{\mathrm{D}p}{\mathrm{D}t} - \beta\frac{\mathrm{D}T}{\mathrm{D}t}\right)^2 + \Phi_{\text{inc}}\right] \quad (15)$$

Table 1 reports the expressions of the viscous dissipation term for an incompressible fluid (Φ_{inc}) with constant properties for different geometry coordinates.

In Table 2 are quoted the values assumed by the volume compressibility and by the coefficient of thermal expansion for a selection of liquids and gases. It is evident that the liquids are in general characterized by very low values of compressibility. On the contrary, it is evident that many liquids have a value of the coefficient of thermal expansion that cannot be considered negligible.

From Eq. (15) it is possible to derive the following particular expressions of the thermal energy equation as a function of the fluid considered:

1. *Ideal gas* ($\beta = 1/T$, $\chi = 1/p$)

$$\rho c_{\mathrm{p}}\frac{\mathrm{D}T}{\mathrm{D}t} = -\nabla\cdot\boldsymbol{q} + \frac{\mathrm{D}p}{\mathrm{D}t} + \mu\left[-\frac{2}{3}\left(\frac{1}{p}\frac{\mathrm{D}p}{\mathrm{D}t} - \frac{1}{T}\frac{\mathrm{D}T}{\mathrm{D}t}\right)^2 + \Phi_{\text{inc}}\right] \quad (16)$$

2. *Incompressible fluid* ($\beta = 0$, $\chi = 0$)

$$\rho c_{\mathrm{p}}\frac{\mathrm{D}T}{\mathrm{D}t} = -\nabla\cdot\boldsymbol{q} + \mu\Phi_{\text{inc}} \quad (17)$$

3. *Real fluid* ($\beta \neq 0$, $\chi = 0$)

$$\rho c_{\mathrm{p}}\frac{\mathrm{D}T}{\mathrm{D}t} = -\nabla\cdot\boldsymbol{q} + \beta T\frac{\mathrm{D}p}{\mathrm{D}t} + \mu\left[-\frac{2}{3}\left(\beta\frac{\mathrm{D}T}{\mathrm{D}t}\right)^2 + \Phi_{\text{inc}}\right] \quad (18)$$

4. *Real fluid* ($\beta = 0$, $\chi \neq 0$)

$$\rho c_{\mathrm{p}}\frac{\mathrm{D}T}{\mathrm{D}t} = -\nabla\cdot\boldsymbol{q} + \mu\left[-\frac{2}{3}\left(\chi\frac{\mathrm{D}p}{\mathrm{D}t}\right)^2 + \Phi_{\text{inc}}\right] \quad (19)$$

As highlighted by Toor [3], observing the typical values of the thermal expansion coefficients and of the volume compressibility of the selection of liquids quoted in Table 2, it is possible to note that in general for liquids small changes in density allow the compressibility contribution to the dissipation function to be neglected so that it is possible to write

$$\Phi \cong \Phi_{\text{inc}} \quad (20)$$

For these reasons the following version of the thermal energy equation can be used with real liquids:

5. *Real liquids* ($\beta \neq 0$, $\chi = 0$)

$$\rho c_{\mathrm{p}}\frac{\mathrm{D}T}{\mathrm{D}t} = -\nabla\cdot\boldsymbol{q} + \beta T\frac{\mathrm{D}p}{\mathrm{D}t} + \mu\Phi_{\text{inc}} \quad (21)$$

This version of the thermal energy can be considered appropriate especially for liquids characterized by large values of the thermal expansion coefficient and subject to large pressure gradients; this can be the case for microchannels in which large pressure drops per unit length are ordinary for low hydraulic diameters.

If the thermal energy equation is used in order to study laminar flow forced convection in microchannels, the expression of the thermal energy equation can be simplified.

In this case, the velocity has only one nonzero component, along the axial direction z, and Eq. (15) can be written as

Viscous Dissipation, Table 1 The expressions of the viscous dissipation term for incompressible fluids with constant properties

Coordinates	Φ_{inc}
Rectangular	$2\left(\frac{\partial v_x}{\partial x}\right)^2+2\left(\frac{\partial v_y}{\partial y}\right)^2+2\left(\frac{\partial v_z}{\partial z}\right)^2+\left(\frac{\partial v_z}{\partial y}+\frac{\partial v_y}{\partial z}\right)^2+\left(\frac{\partial v_x}{\partial z}+\frac{\partial v_z}{\partial x}\right)^2+\left(\frac{\partial v_y}{\partial x}+\frac{\partial v_x}{\partial y}\right)^2$
Cylindrical	$2\left(\frac{\partial v_r}{\partial r}\right)^2+2\left(\frac{1}{r}\left(\frac{\partial v_\theta}{\partial \theta}+v_r\right)\right)^2+2\left(\frac{\partial v_z}{\partial z}\right)^2+\left(\frac{\partial v_\theta}{\partial z}+\frac{1}{r}\frac{\partial v_z}{\partial \theta}\right)^2+\left(\frac{\partial v_z}{\partial r}+\frac{\partial v_r}{\partial z}\right)^2+\left(\frac{1}{r}\frac{\partial v_r}{\partial \theta}+r\frac{\partial (v_\theta/r)}{\partial r}\right)^2$
Spherical	$2\left(\frac{\partial v_r}{\partial r}\right)^2+2\left(\frac{1}{r}\left(\frac{\partial v_\theta}{\partial \theta}+v_r\right)\right)^2+2\left(\frac{1}{r\sin\theta}\frac{\partial v_\phi}{\partial \phi}+\frac{v_r}{r}+\frac{v_\theta\cot\theta}{r}\right)^2+\left(r\frac{\partial (v_\theta/r)}{\partial r}+\frac{1}{r}\frac{\partial v_r}{\partial \theta}\right)^2$ $+\left(\frac{1}{r\sin\theta}\frac{\partial v_r}{\partial \phi}+r\frac{\partial (v_\phi/r)}{\partial r}\right)^2+\left(\frac{\sin\theta}{r}\frac{\partial (v_\phi/\sin\theta)}{\partial \theta}+\frac{1}{r\sin\theta}\frac{\partial v_\theta}{\partial \phi}\right)^2$

follows:

$$\begin{aligned}\rho c_{\text{p}}\left[\frac{\partial T}{\partial t}+v_z\frac{\partial T}{\partial z}\right] &= -\nabla\cdot\boldsymbol{q}+\beta T\left[\frac{\partial p}{\partial t}+v_z\frac{\partial p}{\partial z}\right]\\ &\quad+\mu\left[-\frac{2}{3}\left(\chi\left[\frac{\partial p}{\partial t}+v_z\frac{\partial p}{\partial z}\right]\right.\right.\\ &\quad\left.\left.-\beta\left[\frac{\partial T}{\partial t}+v_z\frac{\partial T}{\partial z}\right]\right)^2+\Phi'_{\text{inc}}\right]\end{aligned} \tag{22}$$

Some time after the flow has started, the time variation of the temperature approaches zero if the boundary conditions are independent of time. Assuming a steady-state axial pressure distribution and a fully developed velocity field inside the microchannel, the energy equation becomes:

Viscous Dissipation, Table 2 Typical values of the volume compressibility and of the coefficient of thermal expansion for a selection of liquids and gases

	χ ($\times 10^{11}$ Pa^{-1})	β ($\times 10^{6}$ K^{-1})
Water	45.9	276
Mercury	3.7	181
Glycerin	21	480
Ethyl alcohol	110	1100
Carbon disulfide	93	1190
Polyethylene	–	751
Acetic acid	–	1024
Ether	–	1638
Engine oil (SAE 50)	–	700
Ethylene glycol	–	650
R134a	–	3130
Ammonia	–	2450

6. *Steady-state laminar flow in microchannels (fully developed velocity):*

$$\begin{aligned}\rho c_{\text{p}} v_z\frac{\partial T}{\partial z} &= -\nabla\cdot\boldsymbol{q}+\beta T v_z\frac{\partial p}{\partial z}\\ &\quad+\mu\left[-\frac{2}{3}\left(\chi v_z\frac{\partial p}{\partial z}-\beta v_z\frac{\partial T}{\partial z}\right)^2+\Phi'_{\text{inc}}\right]\end{aligned}$$

$$\text{(for gases)} \tag{23}$$

$$\begin{aligned}\rho c_{\text{p}} v_z\frac{\partial T}{\partial z} &= -\nabla\cdot\boldsymbol{q}+\beta T v_z\frac{\partial p}{\partial z}\\ &\quad+\mu\Phi'_{\text{inc}} \qquad \text{(for liquids)}\end{aligned} \tag{24}$$

where Φ'_{inc} for incompressible laminar flow is given by

$$\Phi'_{\text{inc}}=\nabla v_z\cdot\nabla v_z \tag{25}$$

For rectangular and circular geometries the complete expression of Φ'_{inc} is reported in Table 3. It is interesting to observe that, for gases for which Eq. (20) holds, Eqs. (23) and (24) coincide.

In Eq. (24), written for liquids in microchannels, the flow work term is conserved in the energy balance because its role, especially in very fine microchannels, can be important since the pressure gradient along the tube is inversely proportional to the square of the hydraulic diameter of the channel:

$$-\frac{\partial p}{\partial z}=2f\,\text{Re}\frac{\mu W}{D_h^2} \tag{26}$$

Viscous Dissipation, Table 3 The expressions of the dissipation function for fully developed incompressible laminar flow

Coordinates	Φ'_{inc}
Rectangular	$\left(\frac{\partial v_z}{\partial y}\right)^2+\left(\frac{\partial v_z}{\partial x}\right)^2$
Cylindrical	$\left(\frac{\partial v_z}{\partial r}\right)^2$

in which f is the Fanning friction factor, Re is the Reynolds number and W is the average fluid velocity.

By considering Eqs. (24) and (25) it is evident that the flow work term and the viscous dissipation term have opposite signs (negative and positive, respectively). This fact underlines that the viscous dissipation plays the role of a distributed heat source inside the fluid; on the contrary the fluid thermal expansion cools the flow like a distributed heat sink. In a tube, since these two effects are locally proportional to $(\partial v_z/\partial r)^2$ and to v_z respectively, the heat sink prevails in the central region of the channel and the heat source dominates in the wall region. The thermal energy generated mainly near the wall region due to the viscous dissipation is absorbed near the channel central region due to the flow work effect.

In general, it is recommended to use Eqs. (23) and (24) in dimensionless form. To this extent, as suggested by Shah and London [4] and Dryden [5], viscous dissipation effects for internal flows can be captured by introducing the Brinkman number:

$$\mathrm{Br} = \frac{\mu W^2}{k \Delta T_{\mathrm{ref}}} \tag{27}$$

in which ΔT_{ref} indicates a characteristic temperature difference for the specific problem considered (i. e. the difference between the wall temperature and the entrance temperature) and k is the fluid thermal conductivity.

For constant axial wall temperature boundary conditions (T boundary conditions) (see ►convective heat transfer in microchannels) the characteristic temperature difference ΔT_{ref} is defined as the difference between the fluid average bulk temperature and the external temperature.

For constant axial heat flux boundary conditions (H1 boundary conditions) the characteristic temperature difference to use in the definition of the Brinkman number is chosen equal to (q_{w}/k), in which q_{w} is the linear heat flux imposed at the walls of the channels.

When Eqs. (10) and (20) hold and the fluid has constant properties, the momentum and the thermal energy equations for steady-state laminar flow in microchannels with a fully developed velocity profile in dimensionless form become

$$\begin{cases} \nabla^{*2} V_z = -p^* \\ V_z \dfrac{\partial \theta}{\partial z^+} = \nabla^{*2}\theta - 2\mathrm{f}\,\mathrm{Re}\,\mathrm{Br}\,(\beta \Delta T_{\mathrm{ref}})\, V_z \theta + \mathrm{Br}\,\Phi'^{*}_{\mathrm{inc}} \end{cases} \tag{28}$$

in which the following dimensionless quantities are introduced:

$$\begin{aligned} z^+ &= \frac{z}{D_h \mathrm{Re}\,\mathrm{Pr}}\,; & \nabla^* &= D_h \nabla\,; \\ V_z &= \frac{v_z}{W}\,; & p^* &= -\frac{D_h^2}{\mu W}\frac{\partial p}{\partial z}\,; \\ \theta &= \frac{T - T_0}{\Delta T_{\mathrm{ref}}}\,; & \Phi'^{*}_{\mathrm{inc}} &= \nabla^* V_z \cdot \nabla^* V_z \end{aligned} \tag{29}$$

Examples of Application

Let us consider the silicon microchannel heat sink shown in Fig. 1; the microchannels obtained by chemical etching on the silicon wafer are in general closed by a Pyrex glass cover bonded to the substrate or by silicon wafer. A liquid flows through the channels; due to the small size of the microchannels the flow is typically laminar. The microchannels have an axially unchanging cross-section with area equal to Ω and a wetted perimeter equal to Γ. A fixed linear power q_{w} is imposed on the top of the silicon substrate while all the other outside walls can be considered as adiabatic. In silicon heat sinks, owing to the high thermal conductivity of the silicon, the temperature gradient in the silicon substrate is very limited and temperature field in the solid is close to isothermal. When a Pyrex cover is used to close the heat sink, three walls of the microchannel work with a constant temperature; on the contrary, the Pyrex side can be considered adiabatic. In general, the ratio between the thermal conductivity of the silicon and of the liquid assumes very high values, and the same occurs for the ratio between the length and the hydraulic diameter of the microchannel. For these reasons the microchannels can be conveniently studied as "long ducts" under a classical H1 thermal boundary condition with three sides having an imposed uniform temperature and one side (the Pyrex side) as adiabatic (*3bc* version; see ►convective heat transfer in microchannels). Conversely, when a silicon cover is used to close the microchannels, all the boundaries can be considered as isothermal; it is possible to use the H1 thermal boundary condition, with four sides having an imposed uniform temperature (*4bc* version; see ►convective heat transfer in microchannels).

For silicon microchannels produced by chemical etching the shape of the channels depends on a variety of factors such as the crystallographic nature of the silicon used. For example, when a KOH anisotropic etching technique is employed in ⟨100⟩ or ⟨110⟩ silicon, the microchannels have a trapezoidal cross-section (with an apex angle of 54.74° imposed by the crystallographic morphology of the silicon) or a rectangular cross-section respectively. In this analysis, KOH-etched microchannels having trapezoidal,



Viscous Dissipation, Figure 1 Schematic of a silicon heat sink



Viscous Dissipation, Figure 2 Rectangular, trapezoidal and double-trapezoidal KOH-etched microchannels

hexagonal (obtained by gluing together two trapezoidal channels) and rectangular cross-sections are considered (see Fig. 2). Each cross-section is characterized by the aspect ratio α defined as the ratio between the height (b) and the minimum width (a) of the channel (see Fig. 2).

By applying Eqs. (28) to model the heat transfer process in the microchannels and considering the flow with constant properties and being thermally and hydrodynamically fully developed, one obtains

$$\begin{cases} \nabla^{*2} V_z = -p^* \\ V_z \dfrac{\partial \theta}{\partial z^+} = \nabla^{*2}\theta + \mathrm{Br}\left[\nabla^* V_z \cdot \nabla^* V_z\right] \end{cases} \tag{30}$$

where the liquid is considered as incompressible ($\beta = 0$) and $\Delta T_{\mathrm{ref}} = q_{\mathrm{w}}/k$ is used in the definition of the dimensionless temperature and the Brinkman number (see ▶ convective heat transfer in microchannels).

Further simplification can be made by considering that in the fully developed thermal region of a heated duct the temperature profile continues to change axially but the "relative temperature shape" of the profile no longer changes. Resorting to the definition of thermally fully developed region for the H1 boundary condition, it is possible to demonstrate (see ▶ viscous heating) that

$$\frac{\partial \theta}{\partial z^+} = \frac{\partial \theta_{\mathrm{b}}}{\partial z^+} = \frac{1}{\Omega^*} + 2\mathrm{Br} f\, \mathrm{Re} \tag{31}$$

where Ω^* is the dimensionless area of the cross-section ($\Omega^* = \Omega / D_{\mathrm{h}}^2$) and θ_{b} is the fluid bulk temperature. The momentum balance equation is solved by using the no-slip boundary condition at the wall which means considering negligible any rarefaction effect. The complete set of boundary conditions is thus

$$\begin{cases} V_z|_{\Gamma} = 0 \qquad \theta|_{\Gamma} = 0 & \text{(4 version)} \\ V_z|_{\Gamma} = 0 \qquad \left.\dfrac{\partial \theta}{\partial n}\right|_{\Gamma_{\mathrm{b}}^*} = 0 \quad \theta|_{\Gamma^* - \Gamma_{\mathrm{b}}^*} = 0 & \text{(3 version)} \end{cases} \tag{32}$$

where Γ_{b}^* is the dimensionless (divided by the hydraulic diameter) length of the adiabatic boundary of the microchannels.

From the dimensionless temperature distribution the value of the fluid bulk temperature can be computed as

$$\theta_{\mathrm{b}} = \frac{1}{\Omega^*} \int_{\Omega^*} V_z \theta \, \mathrm{d}\Omega^* \tag{33}$$

The local Nusselt number along the walls of the microchannels can be calculated as follows:

$$\mathrm{Nu}_{\mathrm{l}} = -\frac{1}{\theta_{\mathrm{b}}} n \cdot \nabla^* \theta \Big|_{w} \tag{34}$$

where n is the versor normal to the wall.

By averaging the local Nusselt number along the heated perimeter one can obtain the thermally fully developed mean Nusselt number:

$$\mathrm{Nu} = \frac{1}{\Gamma_{\mathrm{h}}^*} \int_{\Gamma_{\mathrm{h}}^*} \mathrm{Nu}_{\mathrm{l}} \, \mathrm{d}\Gamma^* = -\frac{1}{\Gamma_{\mathrm{h}}^* T_{\mathrm{b}}} \int_{\Gamma_{\mathrm{h}}^*} n \cdot \nabla T \, \mathrm{d}\Gamma^* = -\frac{1}{\Gamma_{\mathrm{h}}^* T_{\mathrm{b}}} \tag{35}$$

where Γ_{h}^* is the dimensionless heated perimeter ($\Gamma_{\mathrm{h}}^* = \Gamma^*$ (4bc version), $\Gamma_{\mathrm{h}}^* = \Gamma^* - \Gamma_{\mathrm{b}}^*$ (3bc version)).

The numerical solution of the problem defined by Eqs. (31) and (32) has been presented by Morini and Spiga [6]. In Fig. 3 the trends of the local Nusselt number along the perimeter of two trapezoidal microchannels having aspect ratio α equal to 1 (Fig. 3a) and 0.2 (Fig. 3b) with



Viscous Dissipation, Figure 3 Local Nusselt number along the perimeter of two trapezoidal microchannels with four heated sides for (**a**) $\alpha = 1$ and (**b**) $\alpha = 0.2$ as a function of the Brinkman number



Viscous Dissipation, Figure 4 Average fully developed Nusselt number as a function of the Brinkman number for rectangular silicon microchannels with (**a**) three and (**b**) four sides heated

four heated sides are shown as a function of the Brinkman number. It is evident that the convective heat transfer coefficient presents strong variations along the perimeter of the microchannel; in particular, the value of the local Nusselt number approaches zero near the corners of the channels where the fluid tends to be stagnant. When the aspect ratio decreases the longer sides tend to be characterized by a more uniform value of the local convective heat transfer coefficient. Figure 3 provides evidence for the reduction of the local values of the Nusselt numbers when the Brinkman number increases; when the effect of the viscous forces is significant ($\mathrm{Br} > 0.001$) the local Nusselt numbers tend to decrease as an effect of the reduction of the temperature gradients at the walls due to the viscous internal heat production.

The average fully developed Nusselt number for rectangular silicon microchannels is plotted as a function of the Brinkman number in Fig. 4 with three (Fig. 4a) and four (Fig. 4b) sides heated respectively.

Looking at Fig. 4b, it is possible to note that in general the Nusselt number is higher for cross-sections having lower aspect ratios if the viscous dissipation is negligible ($\mathrm{Br} < 0.001$). For large Brinkman numbers this rule is reversed; in fact, for large Brinkman numbers the cross-sections with lower aspect ratios exhibit lower Nusselt numbers.

It is possible to demonstrate analytically [7] that the link between the average Nusselt and Brinkman numbers can be expressed by means of a general relationship for circular and non-circular channels:

$$\overline{\mathrm{Nu}}_{\mathrm{H1}}\,(\mathrm{Br}) = \frac{\overline{\mathrm{Nu}}_{\mathrm{H1}}}{1 + \sigma\,\mathrm{Br}} \tag{36}$$

where $\overline{\mathrm{Nu}}_{\mathrm{H1}}$ is the fully developed value of the Nusselt number when $\mathrm{Br} = 0$ (the values assumed by $\overline{\mathrm{Nu}}_{\mathrm{H1}}$ for the most common microchannel cross-sectional geometries are reported in ►convective heat transfer in microchannels) and σ is a parameter depending on the geometry of the channel cross-section (by means of the aspect ratio α) and on the combination of heated and adiabatic sides of the channel.

In Table 4 the values of σ calculated numerically for rectangular, trapezoidal and double-trapezoidal microchannels having three and four sides heated respectively are listed. Using these data and Eq. (36) it is possible to calculate the value assumed by the fully developed Nusselt number as a function of the Brinkman number in KOH-etched silicon microchannels. For the sake of completeness, it can be useful to remember that for circular microtubes with prescribed wall heat flux, the analytical value of σ is equal to $48\pi/11$ and the fully developed average Nusselt number (Nu_0) is equal to $48/11$.

In order to compare the thermal performances of silicon microheat sinks with rectangular or trapezoidal microchannels it is possible to use the *area goodness factor* defined as follows:

$$\frac{j}{f} = \frac{\mathrm{Nu}\,\mathrm{Pr}^{-1/3}}{f\,\mathrm{Re}} \tag{37}$$

This factor was introduced by Shah and London [4] in order to compare different kinds of heat exchangers. From Eq. (37) it is evident that this factor depends only on the Brinkman number for the fully developed laminar flow of a specified fluid.

Since the dimensionless quantities j and f are independent of the scale of the geometry (D_{h}), the area goodness factor j/f for different microchannels represents the influence of the geometric factors on the pressure losses and the heat transfer.

In Fig. 5 the area goodness factor is shown as a function of the aspect ratio α for rectangular and trapezoidal microchannels with four sides heated. It is evident that the rectangular microchannels give, in general, higher values of the area goodness factor; this fact means that the microheat sinks with rectangular microchannels are more compact than those with trapezoidal microchannels for a fixed value of the heat exchanged because they have a lower flow area.

If the viscous dissipation can be neglected ($\mathrm{Br} \approx 0$), when rectangular microchannels are employed very high (deep) or very low (shallow) values of the aspect ratio ensure high values of the area goodness factor. On the contrary, for trapezoidal microchannels the j/f factor is a maximum for low aspect ratio (shallow microchannels).



Viscous Dissipation, Figure 5 Area goodness factor j/f as a function of the aspect ratio α for rectangular and trapezoidal microchannels with four sides heated



Viscous Dissipation, Figure 6 Area goodness factor j/f as a function of the aspect ratio α for rectangular and trapezoidal microchannels with three sides heated

It is worth noting from Fig. 5 that when α is low the difference between the trapezoidal and rectangular geometry tends to vanish because the cross-section tends to become similar to parallel plates. It is interesting to note that when the Brinkman number increases the area goodness factor reaches the maximum for intermediate values of the aspect ratio; the viscous effects tend to penalize the performances of the microchannel when very shallow and/or very deep. These conclusions are confirmed by Fig. 6 for microchannels with three sides heated. In this case for $\mathrm{Br} = 0$ the j/f factor is a maximum for high values of the aspect ratio when rectangular microchannels are employed. For microheat sinks with trapezoidal microchannels the j/f factor is always lower than for rectangular microchannels but when the aspect ratio decreases this difference tends to vanish. In addition, Fig. 6 highlights that the dependence of the

Viscous Dissipation, Table 4 Coefficients σ for rectangular, trapezoidal and double-trapezoidal KOH-etched microchannels having three or four sides heated

α					
0.05	131.35	136.51		43.98	45.472
0.1	67.98	73.17		23.41	24.863
0.108	–	–	65.46	–	–
0.2	36.57	41.79		13.53	14.866
0.233	–	–	34.04	–	–
0.3	26.39	31.58		10.75	11.844
0.4	21.57	26.68		9.808	10.569
0.5	18.91	23.88		9.605	9.952
0.558	–	–	19.15	–	–
0.6	17.36	22.14		9.75	9.658
0.7	16.42	20.98		10.07	9.52
0.773	–	–	16.62	–	–
0.8	15.89	20.19		10.505	9.476
0.9	15.62	19.62		10.999	9.474
1	15.54	19.22		11.528	9.494
1.042	–	–	15.24	–	–
10/9	15.62	18.9		12.141	9.551
5/4	15.89	18.63		12.935	9.618
1.386	–	–	14.54	–	–
10/7	16.42	18.42		13.971	9.717
5/3	17.36	18.28		15.371	9.848
1.842	–	–	14.30	–	–
2	18.91	18.22		17.353	9.988
2.475	–	–	14.39	–	–
2.5	21.57	18.28		20.357	10.167
3.413	–	–	14.69	–	–
10/3	26.39	18.44		25.449	10.367
5	36.57	18.7		35.817	10.579
7.918	–	–	15.65	–	–
10	67.98	18.99		67.369	10.765
16.078	–	–	16.08	–	–
∞	–	19.15	16.28	–	10.864

j/f factor on the aspect ratio is weak for trapezoidal cross-sections.

Finally, it is important to highlight that the results presented here are valid under the hypothesis of thermophysical properties being independent of temperature. On the contrary the variation with temperature, especially for the fluid viscosity, cannot be ignored in particular for low Reynolds numbers when, for a prescribed wall heat flux, there is a strong temperature rise between the inlet and the outlet of the microchannel. Since the viscosity tends to decrease when the temperature increases, the viscous dissipation effects calculated by using the proposed constant properties model could be overestimated.

Future Directions for Research

The effect of viscous dissipation on convective heat transfer is significant especially for high-velocity flows, highly viscous flows even at moderate velocities, for fluids with a moderate Prandtl number and moderate velocities with small wall-to-fluid temperature difference or with low wall heat fluxes and flowing through microchannels. In this last case, further investigations on the combined effect of the flow work and of the viscous dissipation in microchannels are mandatory by taking into account the temperature variation of the fluid thermophysical properties (especially for the coefficient of thermal expansion and for the viscosity).

Cross References

- ► Viscous Heating
- ► Convective Heat Transfer in Microchannels

References

1. Bird RB, Stewart WE, Lightfoot EN (1960) Transport Phenomena. Wiley, New York
2. Incropera FP, DeWitt DP (1996) Fundamentals of Heat and Mass Transfer. Wiley, New York
3. Toor HL (1956) The Energy Equation for Viscous Flow. Ind Eng Chem 48:922–926
4. Shah RK, London AL (1978) Laminar Flow Forced Convection in Ducts. Adv Heat Transf 14:196
5. Dryden HL, (1936) Aerodynamics of cooling. Aerodyn Theory 6:253
6. Morini GL, Spiga M (2007) The role of the viscous dissipation in heated microchannels. ASME J Heat Transf 129:308–318
7. Morini GL, Spiga M (1999) Nusselt Numbers in Rectangular Ducts with Viscous Dissipation. ASME J Heat Transf 121:1083–1087

Viscous Heating

GIAN LUCA MORINI
DIENCA Università di Bologna, Bologna, Italy
gianluca.morini@mail.ing.unibo.it

Synonyms

Internal friction

Definition

Viscous heating represents the effect of an irreversible process by means of which the work done by a fluid on adjacent layers due to the action of shear forces is transformed into heat.

Overview

In order to study the forced convection of liquids in the laminar regime a common theoretical basis for macro- and microflows can be used; nevertheless, certain effects can be of different importance for microsystems if compared with macrosystems. These effects can be defined as scaling effects with respect to a standard macroanalysis. At the microscale, since different forces have different length dependences, the surface forces (like surface tensions, viscous forces or electrostatic forces) become more important and even dominant as the scale is reduced. Viscous heating, like pressure drop, tends to increase dramatically when the dimensions of microchannels are decreased.

This entry focuses on the role of viscous heating in fluids flowing through microchannels. A criterion will be presented to draw the limit of significance for viscous dissipation effects in microchannel flows. The role of the cross-sectional geometry on viscous dissipation will be highlighted and the minimum Reynolds number for which viscous dissipation effects can no longer be neglected will be calculated as a function of the hydraulic diameter and of the microchannel geometry for different fluids. It will be demonstrated how viscous effects can explain some experimental results on the Poiseuille numbers in microchannels which recently appeared in the open literature.

Basic Methodology

To study laminar flow forced convection in microchannels under the assumptions of steady state axial pressure distribution and fully developed velocity field, the balance of the thermal energy can be written as follows [1] (see ►convective heat transfer in microchannels):

$$\rho c_p v_z \frac{\partial T}{\partial z} = -\nabla \cdot \bar{q} + \beta T v_z \frac{\partial p}{\partial z} + \mu \left[\frac{2}{3} \left(\chi v_z \frac{\partial p}{\partial z} - \beta v_z \frac{\partial T}{\partial z} \right)^2 + \Phi'_{\text{inc}} \right] \quad \text{(for gases)} \qquad (1)$$

$$\rho c_p v_z \frac{\partial T}{\partial z} = -\nabla \cdot \bar{q} + \beta T v_z \frac{\partial p}{\partial z} + \mu \Phi'_{\text{inc}} \quad \text{(for liquids)} \qquad (2)$$

where Φ'_{inc} for incompressible laminar flows is given by

$$\Phi'_{\text{inc}} = \nabla v_z \cdot \nabla v_z \qquad (3)$$

The last term on the right-hand side of Eqs. (1) and (2) represents the work done by the fluid on adjacent layers due to the action of the shear forces (see ►viscous dissipation). This work is entirely transformed into heat by means of an irreversible process and it is responsible for the viscous heating of the fluid.

The integration over the channel cross-section of Eqs. (1) and (2) allows the calculation of the axial distribution of the fluid bulk temperature locally defined as follows:

$$T_b = \frac{1}{W\Omega} \int_{\Omega} v_z T \, \mathrm{d}\Omega \qquad (4)$$

in which Ω indicates the area of the channel cross-section and W is the fluid average velocity.

In this entry the effect of the viscous heating in microchannels is highlighted by means of two examples. First of all, a steady-state liquid flow in the laminar regime through a microchannel with an imposed constant linear heat flux at the walls q'_{w} is considered (H1 boundary condition; see ►convective heat transfer in microchannels). Then, the case of a steady-state liquid flow in the laminar regime through a microchannel with an axially constant outer wall temperature, while the wall heat flux is linearly proportional to the difference between the external temperature and the wall temperature, is considered. This is the case of a microchannel cooled by convection of an external fluid (T3 boundary condition; see ►convective heat transfer in microchannels).

Let us consider the heated microchannel subjected to the H1 boundary condition. By integrating Eq. (2) over the channel cross-sectional area Ω one obtains the following result:

$$D_h^2 \rho c_p W \frac{\mathrm{d}T_b}{\mathrm{d}z} = \frac{q'_{\mathrm{w}}}{\Omega} D_h^2 - 2\mu W^2 f \,\mathrm{Re} \bar{\beta} T_b + 2\mu W^2 f \,\mathrm{Re} \tag{5}$$

where $\bar{\beta}$ is the coefficient of thermal expansion of the fluid calculated at the bulk temperature. The following property of the viscous dissipation term, demonstrated by Morini [2], has been used in order to write Eq. (5):

$$\mu \int_{\Omega} \Phi'_{\mathrm{inc}} \,\mathrm{d}\Omega = 2\mu W^2 f \,\mathrm{Re} \frac{\Omega}{D_h^2} \tag{6}$$

where f is the Fanning friction factor (see ►pressure–driven single-phase liquid flows).

It is interesting to note that, for ideal gases for which $\bar{\beta} = 1/T_b$ the flow work and the viscous dissipation are exactly the same in terms of absolute value and they compensate each to other. For this reason, for ideal gases, the axial variation of the bulk temperature in a channel is independent of viscous heating and flow work even for large values of the Mach number (highly compressible gases).

Equation (6) shows that the viscous dissipation term scales with the internal dimensions of the microchannel. In fact, for a fixed value of the volumetric flow rate ($\dot{V}$) through a microtube with an inner diameter equal to D, the viscous heating generated per unit of length equals the pump power, and it can be written using Eq. (6) as follows:

$$\mu \int_{\Omega} \Phi'_{\mathrm{inc}} \,\mathrm{d}\Omega = \frac{8 f \,\mathrm{Re} \mu \dot{V}^2}{\pi D^4} = \frac{\Delta p \dot{V}}{L} \tag{7}$$

in which Δp is the pressure drop along the microtube and L is the length of the microtube.

By observing Eq. (7) it is evident that the viscous heating and the pressure drop scale with the fourth power of the inner diameter of the channel. This means that viscous heating tends to become very important especially for smaller microchannels.

From the solution of Eq. (5) one can obtain the axial distribution of the bulk temperature along the microchannel. For the H1 boundary condition it is suitable to introduce the following dimensionless quantities (see ►convective heat transfer in microchannels):

$$z^+ = \frac{z}{D_h \mathrm{Re}\,\mathrm{Pr}}; \qquad \Omega^* = \frac{\Omega}{D_h^2}; \qquad \theta_b = k\frac{(T_b - T_{b0})}{q'_{\mathrm{w}}}; \qquad \mathrm{Br} = \frac{\mu W^2}{q'_{\mathrm{w}}} \tag{8}$$

where k is the fluid thermal conductivity and T_{b0} is the value of the bulk temperature at the inlet of the microchannel. Using these dimensionless quantities, Eq. (5) can be written in dimensionless form with the appropriate boundary condition at the entrance:

$$\begin{cases} \dfrac{\mathrm{d}\theta_b}{\mathrm{d}z^+} = \dfrac{1}{\Omega^*} + 2\mathrm{Br} f \,\mathrm{Re}\left[1 - \left(\dfrac{\beta q'_{\mathrm{w}}}{k}\right)\theta_b\right] \\ \theta_b(z^+ = 0) = 0 \end{cases} \tag{9}$$

The analytical solution of this differential problem for a liquid with constant properties is the following:

$$\theta_b(z^+) = \left[\frac{k}{\beta q'_{\mathrm{w}}}\right]\left[1 + \frac{1}{2\Omega^* \mathrm{Br} f \,\mathrm{Re}}\right] \times \left[1 - e^{-2\mathrm{Br} f \,\mathrm{Re}\left(\frac{\beta q'_{\mathrm{w}}}{k}\right) z^+}\right] \tag{10}$$

For an incompressible fluid ($\beta = 0$) the solution of the problem defined by Eq. (9) becomes the following:

$$\theta_b = \frac{1}{\Omega^*} z^+ + 2\mathrm{Br} f \,\mathrm{Re}\, z^+ \tag{11}$$

In the case of a microchannel cooled for convection by an external fluid (T3 boundary condition), the heat flux at the walls can be written as

$$q'_{\mathrm{w}} = -U_{\mathrm{w}} \Gamma \left(T_b - T_{\mathrm{ext}}\right) \tag{12}$$

in which $1/U_w$ is referred to as the wall thermal resistance and Γ the perimeter of the walls.

By combining Eq. (5) with Eq. (12) and introducing the dimensionless quantities

$$z^+ = \frac{z}{D_h \mathrm{Re}\,\mathrm{Pr}}\,; \quad \Omega^* = \frac{\Omega}{D_h^2}\,;$$
$$\Gamma^* = \frac{\Gamma}{D_h}\,; \quad \theta_b = \frac{(T_b - T_{\mathrm{ext}})}{(T_{b0} - T_{\mathrm{ext}})}\,; \tag{13}$$
$$R_w = \frac{k}{U_w D_h}\,; \quad \mathrm{Br} = \frac{\mu W^2}{k\,(T_{b0} - T_{\mathrm{ext}})}$$

where k is the fluid thermal conductivity and R_w is the dimensionless wall thermal resistance, the energy balance equation and its boundary condition in dimensionless form become

$$\begin{cases} \dfrac{\mathrm{d}\theta_b}{\mathrm{d}z^+} = -\dfrac{4}{R_w}\theta_b + 2\mathrm{Br} f\,\mathrm{Re} \\ \qquad \times \left[1 - (T_{b0} - T_{\mathrm{ext}})\,\bar{\beta}\theta_b - T_{\mathrm{ext}}\bar{\beta}\right] \\ \theta_b(z^+ = 0) = 1 \end{cases} \tag{14}$$

The analytical solution of Eq. (14) for a liquid with constant properties is

$$\theta_b(z^+) = \left[1 - \frac{B}{A}\right] e^{-Az^+} + \frac{B}{A}$$
$$\text{with} \quad A = \left[\frac{4}{R_w} + 2\mathrm{Br} f\,\mathrm{Re}\,(T_{b0} - T_{\mathrm{ext}})\,\bar{\beta}\right] \tag{15}$$
$$\text{and} \quad B = 2\mathrm{Br} f\,\mathrm{Re}\left[1 - T_{\mathrm{ext}}\bar{\beta}\right]$$

For an incompressible fluid ($\beta = 0$) the solution of Eq. (14) becomes

$$\theta_b\left(z^+\right) = \left[1 - \frac{\mathrm{Br} f\,\mathrm{Re} R_{\mathrm{w}}}{2}\right] e^{-\frac{4z^+}{R_{\mathrm{w}}}} + \frac{\mathrm{Br} f\,\mathrm{Re} R_{\mathrm{w}}}{2} \tag{16}$$

For an adiabatic microchannel ($R_w = \infty$) in which an incompressible fluid ($\beta = 0$) flows the solution of Eq. (14) becomes

$$\theta_b(z^+) = 2\mathrm{Br} f\,\mathrm{Re}\,z^+ + 1 \tag{17}$$

Examples of Application

The theory developed in the previous section is used to draw the limit of significance of viscous dissipation in heated and adiabatic microchannels.

In particular, in this section a criterion will be stated in order to predict the range of the Brinkman number where the viscous dissipation effect cannot be neglected in the analysis of the fluid flow and heat transfer in microchannels.

Heated Microchannels

If one considers the case of an incompressible liquid flowing through a heated microchannel the axial distribution of the bulk temperature is given by Eq. (11). This equation highlights that the temperature rise along the microchannel is given by two contributions: the heat flux imposed at the walls ($\theta_{b,q}$) and the viscous heating inside the fluid ($\theta_{b,v}$):

$$\theta_b = \frac{1}{\Omega^*} z^+ + 2\mathrm{Br} f\,\mathrm{Re}\,z^+ = \theta_{b,q} + \theta_{b,v} \tag{18}$$

If one considers the ratio between these two contributions, it is possible to demonstrate that this ratio is linked to the Brinkman number and to the Poiseuille number by means of the following relation:

$$\kappa = \frac{\theta_{b,v}}{\theta_{b,q}} = 2\mathrm{Br}\,\Omega^* f\,\mathrm{Re} \tag{19}$$

In order to draw the limit of the significance of the viscous heating in a microchannel, one can impose that this term has to be considered as significant only if this ratio is greater than a fixed value ($\kappa_{\lim} = 1 - 5\%$) [3]; in this manner the following inequality for the Brinkman number can be introduced:

$$\mathrm{Br} > \frac{\kappa_{\lim}}{2\Omega^* f\,\mathrm{Re}} \tag{20}$$

If this inequality holds, the effects of the viscous dissipation cannot be neglected.

For silicon microchannels produced by chemical etching, the shape of the channels depends on a variety of factors such as the crystallographic nature of the silicon used. For example, when an anisotropic KOH etching technique is employed in ⟨100⟩ or ⟨110⟩ silicon, the microchannels have a trapezoidal cross-section (with an apex angle of 54.74° imposed by the crystallographic morphology of the silicon) or a rectangular cross-section respectively. The cross-section is in general characterized by the aspect ratio α defined as the ratio between the height (b) and the minimum width (a) of the channel (see Fig. 1).

For rectangular and trapezoidal channels the dimensionless area of the cross-section is a function of the aspect ratio (α) and of the apex angle (ϕ); it can be expressed as

$$\Omega^* = \frac{\left[1 + \alpha\left(\frac{1}{\tan\phi} + \frac{1}{\sin\phi}\right)\right]^2}{4\alpha^2\left[\frac{1}{\alpha} + \frac{1}{\tan\phi}\right]} \tag{21}$$

In Fig. 2 the maximum value of the Brinkman number for which the viscous dissipation effects can be neglected for



Viscous Heating, Figure 1 Typical cross-section of KOH-etched microchannels



Viscous Heating, Figure 2 Maximum value of the Brinkman number for which viscous dissipation effects can be neglected for trapezoidal ($\phi = 54.74°$) and rectangular ($\phi = 90°$) microchannels as a function of the aspect ratio α

microchannels having trapezoidal ($\phi = 54.74°$) and rectangular ($\phi = 90°$) cross-sections is depicted as a function of the aspect ratio α. A value of κ_{lim} equal to 5% is considered. The results in Fig. 2 show that for shallow microchannels the effects of the viscous dissipation become important for lower Brinkman numbers.



Viscous Heating, Figure 3 Maximum Reynolds numbers for which the effects of viscous dissipation can be neglected in a heated KOH-etched microchannel with imposed wall heat flux q_W

In order to consider the applicability related to microchannels of the proposed criterion, the value of the minimum Reynolds number (linked to the minimum Brinkman number indicated in Eq. (20)) for which κ becomes equal to 5% is computed as a function of the hydraulic diameter for a rectangular microchannel having $\alpha = 3$. In Fig. 3 the minimum Reynolds number is shown for water and isopropanol as working fluids in rectangular and trapezoidal microchannels having an aspect ratio $\alpha = 3$. A constant wall heat flux equal to 90 W/cm^2 is considered. It is evident that the viscous effects are more important for isopropanol than for water because the isopropanol is characterized by a lower value of the specific heat at constant pressure as compared to water; as a consequence, the same viscous heating produces a larger temperature rise in isopropanol than in water. In addition, it is interesting to note that for water the viscous effects have to be considered only for microchannels having a hydraulic diameter less than 100 µm; when the hydraulic diameter decreases the minimum Reynolds number decreases and the viscous effects become important even if the Reynolds numbers are low ($\text{Re} < 500$). In Fig. 3 the role of the cross-sectional shape is highlighted; it can be seen that the viscous effects occur earlier in a rectangular microchannel for a fixed value of the hydraulic diameter and aspect ratio. Figure 3 proves that the viscous effects are typical scaling effects. In fact, they are negligible for high values of the hydraulic diameter but become more important when hydraulic diameters less than 100 – 300 µm are considered.

Adiabatic Microchannels

For an adiabatic microchannel in which an incompressible liquid flows, the axial temperature rise due to viscous heating can be computed by means of Eq. (17). For a microchannel with a length equal to L, the axial temperature gradient results from Eq. (17) in which the definitions reported in Eq. (13) are used:

$$\frac{\partial T_b}{\partial z} \cong \frac{\Delta T_b}{L} \cong 2 \frac{\mu W}{\rho c_p D_h^2} f \,\text{Re} \tag{22}$$

In order to validate this result the experimental data of Celata et al. [4] are used. Celata et al. measured the temperature difference between inlet and outlet of a smooth



Viscous Heating, Figure 4 Gradient of viscous heating ($\Delta T_b/L$) along adiabatic microtubes versus Reynolds number; comparison of measurements (exp) and the theory for incompressible ($\beta = 0$) laminar flows (Eq. (22))

capillary tubes ($f\,\mathrm{Re} = 16$) of fused silica with hydraulic diameters equal to 100, 70 and 50 μm through which water is circulated at different Reynolds numbers in the laminar regime. The comparison between the prediction of Eq. (22) and the experimental data is shown in Fig. 4, and the agreement between the model and the measurements is good. The agreement improves for larger Reynolds numbers and smaller diameters; this fact is due to the smaller temperature rise at lower Reynolds number and larger diameters.

Considering Eq. (22), it is possible to note that, for two different fluids, *c* and *d*, and for a fixed value of the Reynolds number, hydraulic diameter and cross-sectional geometry, the temperature gradient ratio is related to the following ratio of the fluid thermophysical properties:

$$\frac{\left(\frac{\mathrm{d}T_b}{\mathrm{d}z}\right)_c}{\left(\frac{\mathrm{d}T_b}{\mathrm{d}z}\right)_d} = \left(\frac{\nu_c}{\nu_d}\right)^2 \left(\frac{c_{pd}}{c_{pc}}\right) \tag{23}$$

The temperature gradient due to the viscous heating is larger for fluids having a large value of kinematic viscosity and a low value of specific heat. For example, for isopropanol and water this ratio is equal to 13.26 at 298 K; for methanol and water this ratio is equal to 2.32 at 298 K. It is interesting to note that for water and air the ratio quoted in Eq. (23) is equal to 10^3 at 298 K; this means that the effects of viscous dissipation could be very strong for air. However, the influence of the compressibility is very important for gases flowing through microchannels and β cannot be neglected; the gas expansion in the flow direction causes a decrease of the temperature, which contrasts the effects of viscous heating.



Viscous Heating, Figure 5 Reynolds numbers for which the temperature rise due to viscous heating along an adiabatic circular microchannel 5 cm long is equal to 1 K as a function of the hydraulic diameter

It is possible to suggest a criterion to establish when viscous dissipation effects cannot be ignored in an adiabatic microchannel. Considering that for water and isopropanol the dynamic viscosity decreases by about 20 – 25% per 10 K one can assume as reference temperature rise an increase of 1 K of the bulk temperature between the inlet and outlet of a microchannel [2].

When the bulk temperature increase along the microchannel is greater than 1 K the effect of the viscous dissipation cannot be neglected. This means that the following inequality must be satisfied in order to neglect the viscous heating in adiabatic microchannels:

$$\begin{aligned}(T_{be} - T_{b0}) &= (T_{b0} - T_{\mathrm{ext}})\left(\theta_b\left(z_e^+\right) - 1\right)\\ &= 2\frac{Br}{\mathrm{Re}\,\mathrm{Pr}}\frac{L}{D_h} f\,\mathrm{Re}\,(T_{b0} - T_{\mathrm{ext}}) < 1\\ &\text{with}\quad z_e^+ = \frac{L}{D_h \mathrm{Re}\mathrm{Pr}}\end{aligned} \tag{24}$$

where *L* is the microchannel length, T_{be} is the fluid temperature at the exit of the microchannel, θ_b and Br are as defined in Eq. (13).

Equation (24) can be adopted as a criterion to predict the upper limit of significance of viscous dissipation in a microchannel. Equation (24) allows, for a fixed microchannel geometry and hydraulic diameter, the calculation of the values of the Reynolds number for which the temperature rise between inlet and outlet is equal to or greater than 1 K.

Figure 5 shows the Reynolds number for which the temperature rise, between inlet and outlet of a microtube 5 cm long, becomes equal to 1 K as a function of the hydraulic diameter of the microchannel, for both water and isopropanol flows.

Finally, it must be noted that Eq. (17) can be used to determine experimentally the value assumed by the friction factor in an adiabatic microchannel for incompressible liquids:

$$f = \frac{\mathrm{Pr}}{\mathrm{Br}} \frac{D_h}{L} \left(\theta_b(z_e^+) - 1\right) \tag{25}$$

The friction factor can thus be determined without measuring the pressure drop along the microchannel but by means of temperature and flow rate measurements. This kind of measurement is unsuitable when macrochannels are tested. For this reason Eq. (25) can be considered as an example of the role of scaling effects and to suggest new measurement procedures at the microscale. This relation has been used by Celata et al. [4] in order to determine the friction factor in microchannels. In addition, since Eq. (25) is valid only in the laminar regime, one can use it to individuate the laminar-to-turbulent transition in microchannels. This has been experimentally demonstrated by Celata et al. [4] and Rands et al. [5].

Rearranging Eq. (22) and using the following definition of the Eckert number:

$$\mathrm{Ec} = \frac{W^2}{c_p \Delta T_b} \tag{26}$$

it can be demonstrated that for an incompressible liquid through an adiabatic microchannel the following equation holds in the laminar regime:

$$\frac{\mathrm{Re}\, D_h}{\mathrm{Ec}\, L} = 2 f\, \mathrm{Re} \tag{27}$$

Rands et al. [5] experimentally tested this equation for circular microtubes ($f\,\mathrm{Re} = 16$) having diameters ranging between 16.6 and 32.2 μm and with lengths between 1 and 3 cm.

In Fig. 6 the experimental results obtained by Rands et al. [5] are compared with Eq. (27); it is evident that the comparison between Eq. (27) and the experimental results allows one to individuate the laminar-to-turbulent transition in microchannels without the need to use pressure gauges.

Future Directions for Research

The effect of the viscous heating of fluids in microchannels is significant especially for hydraulic diameters less than 200 μm. In this case, further investigations on the combined effect of the flow work and of the viscous dissipation in microchannels are mandatory by taking into account the temperature variation of the fluid thermophysical properties (especially the coefficient of thermal expansion and the viscosity).



Viscous Heating, Figure 6 Comparison between experimental results of Rands et al. [5] and Eq. (27) for incompressible laminar flows

Cross References

- ► Viscous Dissipation
- ► Convective Heat Transfer in Microchannels
- ► Pressure-Driven Single-Phase Liquid Flows
- ► Pressure-Driven Single-Phase Gas Flows

References

1. Bird RB, Stewart WE, Lightfoot EN (1960) Transport Phenomena. Wiley, NY
2. Morini GL (2005) The Viscous Heating in Liquid Flows in Microchannels. Int J Heat Mass Transf 48:3637–3647
3. Morini GL (2006) Scaling effects for liquid flows in microchannels. Heat Transf Eng 27:64–73
4. Celata GP, Morini GL, Marconi V, McPhail S, Zummo G (2006) Using viscous heating to determine the friction factor in microchannels – An experimental validation. Exp Fluid Therm Sci 30(8):725–731
5. Rands C, Webb BW, Maynes D (2006) Characterization of transition to turbulence in microchannels. Int J Heat Mass Transf 49:2924–2930

Viscous Pump

- ► Microfluidic Rotary Pump

Viscous Slip Coefficient

Definition

Viscous slip coefficient determines the tangential velocity of gas near a solid surface due to a normal gradient of this velocity.

Cross References

- ► Gas Flow in Nanochannels
- ► Supersonic Micro-Nozzles
- ► Micro- and Nanoscale Gas Dynamics

Visualization
Based on Molecular Tagging Methods

David Sinton
Department of Mechanical Engineering, University of Victoria, Victoria, BC, Canada
dongqing.li@vanderbilt.edu, dsinton@me.uvic.ca

Synonyms

Flow tagging; Flow profiling; Laser-induced molecular tagging; Laser-induced photochemical anemometry; Photobleached fluorescence; Photo-activated nonintrusive tracking of molecular motion

Definition

In the context of microfluidics and nanofluidics, visualization implies the determination of fluid velocity in small scale internal flows. Visualization requires an optically detectable fluid marker that does not alter the local fluid velocity of interest. A variety of visualization methods have been developed for small scale flows, many of which were derived from methods originally developed for macroscale flows. Molecular tagging describes one class of methods that involve molecules being rendered optically differentiable from the bulk fluid to serve as optically detectable fluid markers. The molecular dimensions of these fluid markers make them well suited to small scale flows. Molecular tagging is commonly achieved by select exposure to light, although the specific photochemical mechanisms vary over the four techniques described here.

Overview

Flow visualization has a long history. A well-known early flow visualization experiment is that of Reynolds in 1883, who studied the transition to turbulence in a pipe flow by observing the transport of an injected dye. Although many flow visualization methods have evolved since, all share a fundamental objective: to alter the fluid such that the fluid transport may be observed, yet not alter the fluid motion. The latter half of this objective is very difficult to achieve in that it requires the method to be totally non-intrusive. Instead, the researcher must either demonstrate that the alterations brought about by the marker are negligible, or be able to model the alterations such that the velocity of the undisturbed flow may be determined.

Visualization has played a central role in the development of the field of microfluidics and associated applications. It is both a natural desire, and highly informative to ‘see’ what is going on inside these small scale systems. The inherent scale of these systems results in significant deviations from macroscale fluid behavior, most notably due to an increase in the role of surface effects and diffusive transport of mass, momentum and energy. Unique micro- and nanoscale transport phenomena present many opportunities for advanced functionality as exploited by the many applications described in this encyclopedia and elsewhere. The scale of these systems, however, also presents some unique challenges with respect to visualization. Most notably, on the microscale the non-intrusive requirement precludes the use of many techniques commonly applied to macroscale flows, such as hot-wire anemometry and the injection of dye by mechanical means. In addition it is not possible to observe the phenomena without the use of a microscope. Several visualization techniques have, however, been successfully applied to microscale flows. Like much of the research in microfluidics and nanofluidics, many proof-of-concept contributions have appeared in the 1990s, and subsequent advancement has been rapid. Most visualization techniques applied to microstructures may be conveniently divided into two categories: particle based methods and scalar based methods [1].

Particle based visualization methods have been well developed for macroscale flows and popular for many years. In these methods, the motion of the bulk fluid is inferred from that of observed marker particles. Different methods of acquiring and analyzing particle transport data have evolved including, briefly, laser Doppler *velocimetry*, particle streak velocimetry, and particle image velocimetry. The latter includes particle tracking velocimetry and pattern matching velocimetry algorithm methodologies. Although not the focus of this entry, these particle based methods have been successfully applied to microscale flows and highly instrumental in microsystem development. Detailed descriptions of these methods are available in this encyclopedia and elsewhere.

In scalar based visualization methods, the motion of the bulk fluid is inferred from the observed velocity of a conserved scalar, quite often a dye. Reynolds' historic work fits in this category as do many other visualization methods developed since. The key distinction between scalar and particle based methods is that particle based methods track individual particles whereas scalar based methods track a tagged solute concentration. In the limit where particle sizes approach molecular dimensions, and/or single molecule tracking is involved, this particle/scalar distinction vanishes. Some studies in this regime are discussed under key research findings and future research sections. Commonly employed molecular tagging methods, however, fall under the classification of scalar based visualization. It is the observed transport of a concentration of *tagged* molecules that provides the basis for the determination of fluid velocity.

A schematic illustrating the generic molecular tagging approach is given in Fig. 1. The microchannel, in this case a circular capillary, initially contains a fluid with uniform optical/fluorescent properties. Molecular tagging is most commonly applied to liquid aqueous flows, however, organic solvents and gases have been used as well. In the first step, a portion of the fluid is differentiated from the bulk fluid, or *tagged*, through an interaction with light, commonly from a laser. The specific photochemical mechanisms that facilitate the molecular tagging vary over the four techniques described here, namely: photobleached fluorescence, photochromic reaction, phosphorescence, and caged fluorescence. For the tagging light source, lasers are often employed to achieve a high intensity, wavelength specific, tightly focused light exposure. With the setup shown in the schematic, the molecules are tagged in a cross-sectional volume by a focused sheet of light oriented perpendicular to the channel (this is a common configuration, although point-based molecular tagging has also been demonstrated). The sheet of tagged molecules is deformed into a bowl shape, characteristic of pressure-driven flow in a circular channel. The second, visualization, step involves imaging the transport of the observed scalar and interpreting the results. The visualization is commonly achieved with a microscope system that delivers/gathers light from the microchannel as illustrated in the figure. The transport of the concentration of tagged molecules is imaged through the microscope onto a CCD camera. The resulting image sequence is then processed and analyzed numerically to determine the fluid velocity.

The channel is filled with an aqueous solution containing caged fluorescent dye (which is non-fluorescent). A cross-sectional *sheet* or *band* of the solution is exposed to a brief, intense pulse of ultraviolet light. This exposure breaks the caging groups in the band of fluid and fluorophores are released. These fluorophores are continuously excited by light from the microscope (blue) and the resulting fluorescent emission (green) is imaged through the microscope onto a CCD camera. An image sequence of the transport of the fluorescent band of dye is then analyzed to determine the bulk liquid velocity in the channel.

Flows in micro- and nanochannels are generally laminar and driven electrokinetically, as in electroosmotic flow, by pressure, or by a combination of the two. The pressure source may be external to the microfluidic network, or internally induced via capillary pressure, valving, or nonuniformities arising from electrokinetic effects. Central to electrokinetic effects is the electrical double layer, or EDL, that results from the non-uniform distribution of electrical charges near phase boundaries. Electrokinetically-driven flow, often called electroosmotic flow, results from the response of liquid ions in the electrical double layer to an axially applied electric field. The electric field may be applied via external electrodes in fluid reservoirs, or through embedded electrodes. The nature of electroosmotic flow is compared to that of pressure-driven flow in the image sequences shown in Fig. 2. The images were obtained using a caged fluorescence molecular tagging method (details described later). The transport of the concentration of tagged molecules illustrates the plug-like velocity profile characteristic of electroosmotic flows in microchannels. The velocity profile appears flat because the flow driving force is generated in the electrical double layer which is typically on the order of 10 nm and thus a very thin layer relative to the diameter of the microchannel on the order of 100 μm. In contrast, the transport of tagged molecules in the pressure driven flow reflects the familiar parabolic velocity profile expected from classical theory. Both pressure-driven and electroosmotic flow present unique challenges and advantages with respect to molecular tagging. The plug-like nature of electroosmotic flows, results in reduced dispersion (or blurring) of the tagged solute. This characteristic of electroosmotic flows has long been exploited in the area of capillary electrophoresis. However, the electrophoretic velocity of the tagged solute (if charged) in response to the applied electric field can bias the measurement of the bulk fluid velocity, and must be taken into account. For pressure-driven flow, electrophoretic effects do not play a role assuming there is no externally applied electric field, and streaming potential is not significant. However, the cross-sectional velocity gradients characteristic of pressure-driven flows result in hydrodynamic dispersion or blurring of the tagged solute resulting in a reduced useful lifetime and reduced resolution, particularly near the channel wall.

The processing and interpretation of a sequence of images documenting the observed transport of a tagged solute involves several considerations. In most cases the desired output is the fluid velocity, exhibiting a spatial resolution



Visualization Based on Molecular Tagging Methods, Figure 1 Schematic illustrating typical molecular tagging methodology as applied to microchannel flow visualization. First, a small cross-stream section of molecules is *tagged* such that they become optically detectable. This step is typically accomplished with intensely focused laser light. Second, the transport of the tagged molecules is recorded, typically using fluorescence video microscopy

as high as possible. Although the fluid velocity is desired, it is the transport of a conserved scalar, the tagged solute concentration that is imaged. This transport, in general, is modeled by the species conservation equation for a dilute solute as follows [2],

$$\frac{\partial c_i}{\partial t} + \boldsymbol{u} \cdot (\nabla c_i) = D_i \nabla^2 c_i + \frac{D_i z_i e}{kT} \nabla \cdot (c_i \nabla \Psi) + R_i \quad (1)$$

where c is the concentration of the tagged solute, $\boldsymbol{u}$ is the bulk fluid velocity, D is the diffusion coefficient, z is the valence charge of the solute, Ψ is the electric potential, R is the rate of generation of the solute, subscript i indicates a quantity specific to the solute species, and other variables/symbols have their usual meanings. For fully developed flow in the x-direction with only an axially applied electric field (i. e., thin electrical double layer limit), Eq. (1) may be recast as,

$$\frac{\partial c_i}{\partial t} + \left(u_x + u_{\text{ph\_}x}\right) \cdot (\nabla c_i) = D_i \nabla^2 c_i + R_i \quad (2)$$

where $u_{\text{ph\_}x}$ indicates the axial velocity of the solute due to electrophoretic response to the applied field. This velocity is given by,

$$u_{\text{ph\_}x} = \frac{D_i z_i e}{kT} \left(-\frac{\partial \Psi}{\partial x} \right) = \nu_{\text{ph}} \left(E_x \right) \quad (3)$$

Essentially, Eqs. (1–3) indicate that in addition to bulk fluid velocity, $\boldsymbol{u}$ (which is the desired output), the imaged concentration is also a product of transport by diffusion and electrophoretic motion, and the rate of generation of the tagged molecules. Thus the visualization problem is somewhat the inverse of the conventional computational modeling problem where the evolution of the concentration field is calculated from a known bulk velocity field. In contrast, the bulk velocity field is calculated from the known evolution of the concentration field when interpreting image sequences for visualization purposes. Methods to perform this calculation are discussed in the next section, following a description of four molecular tagging strategies.

Basic Methodology

The basic methodology behind molecular tagging based visualization is illustrated in Fig. 1. In the first step, a portion of the fluid is differentiated from the bulk fluid, or *tagged*, through an interaction with light. In the second step, the transport of the tagged solute concentration is imaged and interpreted to determine the fluid velocity. Provided below are the details of four molecular tagging approaches, and a description of image processing and interpretation procedures.

Photobleached Fluorescence Tagging

Fluorescence is the process by which molecules that are excited by electromagnetic radiation almost immediately emit a photon. It occurs in molecules termed fluorophores, typically polyaromatic hydrocarbons, in a multi-step process. A photon is absorbed by the fluorophore, elevating it to an excited state for a short period (typically 1 – 10 ns) and then the fluorophore releases a photon. The released photon is of lower energy than the absorbed photon due to energy dissipated in the excited state. This energy loss corresponds to a shift in wavelength between the absorbed and emitted light, termed the Stokes shift, and facilitates the filtering out of all excitation light from fluorescence emission and is the basis for fluorescence microscopy. For example, fluorescein dye molecules have an absorption



Visualization Based on Molecular Tagging Methods, Figure 2 Visualization of electroosmotic flow (**a**), as compared to pressure-driven flow (**b**), using caged-dye based molecular tagging method. The microchannel was circular in cross-section and 200 μm in diameter. Both the plug-like velocity profile characteristic of electroosmotic flows, and the parabolic velocity profile characteristic of pressure-driven flows are apparent. Adapted from [1] with permission



Visualization Based on Molecular Tagging Methods, Figure 3 Photobleached fluorescence based molecular tagging and visualization. A photobleached marker in a microchannel is shown inset of a measured electroosmotic velocity profile. The contrast of the inset image has been adjusted for clarity. (Reprinted from [4])

maximum around $\lambda = 490$ nm and an emission maximum at approximately $\lambda = 513$ nm. Thus if a microfluidic channel is uniformly illuminated with a single-line argon laser at $\lambda = 488$ nm, and a fluorescence microscope filters out all light below $\lambda < 500$ nm, only fluorescent emission from fluorescein molecules will be imaged by the camera. The excited lifetime of fluorescence is too short to facilitate a molecular tagging based visualization strategy (i. e., the flow-wise displacement between excitation and emission would be too small to measure for most flowrates of interest). However, photobleaching of fluorescence does enable molecular tagging based visualization.

Photobleaching of fluorophores is a process by which exposure to excitation light results in chemical alterations rendering the molecule non-fluorescent. Burning out a light bulb is analogous to photobleaching a fluorophore. The rate of photobleaching depends on the photon flux, and photobleaching is typically permanent in aqueous solutions. A common problem in biology experiments, photobleaching can be used to good effect as a molecular tagging strategy. With this tagging method, the fluid is first uniformly seeded with a dilute concentration of fluorescent dye. The molecular tagging step (as shown in Fig. 1) is achieved with a light source close to the absorption maximum of the dye. The intensity and duration of exposure must be sufficient to induce significant local photobleaching. The visualization step involves fluorescence microscopy, where the *tagged* solute is differentiated from the rest of the fluid as it is non-fluorescent. An argon laser is commonly employed in combination with fluorescein dye to achieve the photobleaching [3], however another method employed the reflective optical properties of a gaseous bubble in the microchannel to locally focus flood illumination and achieve local photobleaching without a secondary light source [4]. An image of a photobleached fluorescence tagged flow marker is shown in Fig. 3 along with an electroosmotic velocity profile determined using photobleached fluorescence. The velocity profile exhibits the plug-like shape, characteristic of electroosmotic flows, with resolution extending to 5 μm from each wall.

An advantage of photobleached fluorescence tagging is that visible light and standard, relatively inexpensive, fluorescent dyes can be employed. A disadvantage of this technique is that the signal-to-noise ratio (SNR) that defines image contrast is as much as an order of magnitude [3] lower than caged fluorescence tagging (discussed below). Furthermore, because it is the *unmarked* fluid in the channel that is fluorescing, out-of-plane velocity gradients can occlude the photobleached section. For this reason, photobleached fluorescence tagging is suited more to electroosmotic flows than to pressure-driven flows.

Photochromic Reaction Tagging

Photochromic reactions induce a change in the absorption spectrum of a solution. This change is observed as a change in the colour of a solution. The tagging process can occur on the order of nanoseconds, however, the colour change, typically from clear to blue, can persist for seconds to minutes. Photochromic reaction tagging is induced by exposure of the solution to ultraviolet light. Although some water-soluble photochromic dyes are now available, many photochromic dyes require the use of organic solvents such as kerosene and ethanol, which limit their usefulness in microfluidic applications that primarily involve aqueous solutions. Another disadvantage of this tagging method is that the image is produced by a change in absorbance which is inherently less sensitive than an image produced by emitted light against a black background as is the case in fluorescence and phosphorescence. None the less, this molecular tagging method has been successfully applied both in macroscale flows and microscale flows.

Phosphorescence Tagging

Phosphorescence is the process by which molecules, excited by electromagnetic radiation, become excited to a higher level and emit energy in the form of light as they return to their unexcited state. The central difference between fluorescence and phosphorescence is the length of time between excitation and emission. Phosphorescence emission lifetimes can be as long as several milliseconds ($\sim$ ms), which is much longer than fluorescence ($\sim$ ns), but much shorter than colour changes in photochromic dyes ($\sim$ s). Thus unlike fluorescence, phosphorescent molecules are suitable for molecular tagging applications where the tracer lifetime ($\sim$ ms) is long enough relative to the flow convection timescale to produce a quantifiable displacement. In other words, phosphorescence itself can be used as a molecular tagging mechanism, without an associated bleaching or caging strategy.

A distinct advantage of phosphorescence based molecular tagging is that only a single light source, that required for excitation, is needed to visualize the flow. Typically a UV laser is used. Traditional phosphorescent molecules suffered from O_2 and H_2O quenching during their excited states, however, so-called phosphorescent supramolecules have been developed more recently that resist quenching. These compounds have been applied to both macro- and microscale flows. For microflows, the emission lifetime on the order of milliseconds restricts their applicability to relatively high-speed microflows. In addition, water-soluble phosphorescent supramolecules require a significant concentration of alcohol ($c \sim 100$ mM or higher) in solution to perform effectively. Thus applicability of this method to study electrokinetic phenomena is limited.

Caged Fluorescence Tagging

Caged fluorescent dyes are fluorophores with additional chemical groups that render the fluorophore nonfluorescent. A caged fluorophore may be *uncaged* by exposure to certain wavelengths of light that break the bonds attaching the caging groups. The original fluorophore is recovered through this process, termed photolysis, and may be tracked indefinitely through fluorescence microscopy. With this tagging method, the fluid is first uniformly seeded with a dilute concentration of caged fluorescent dye. A range of caged dyes are available commercially (Invitrogen Corp.). The molecular tagging step (as illustrated in Fig. 1) is achieved with a light source close to the absorption maximum of the caged dye, (which is distinct from the absorption maximum of the fluorophore) normally in the ultraviolet range ($\lambda < 360$). Once uncaged, the fluorophore requires excitation in the appropriate wavelength range, which is on the order of $\lambda = 490$ nm for fluorescein. Standard fluorescence microscopy equipment is typically sufficient to image the uncaged dye transport. The images shown in Fig. 2 were obtained using fluorescence video microscopy following caged dye based molecular tagging. A schematic of the experimental setup employed is given in Fig. 4. In the case shown, circular cross-section capillaries were used in conjunction with optical immersion oil and an oil immersion objective. The immersion system ensures minimal signal loss and prevents optical distortion due to the capillary wall (the latter is not an issue with chip-based microchannels).

The most critical time scale in caged fluorescence based molecular tagging is the time delay between absorption of the photolysis radiation (untagging light exposure), and a significant release of fluorophore. Several studies have investigated this rate of release. Some fluorescence has been detected only 1 μs [5] after photolysis radiation exposure, more significant release on the order of 10 ms, and gradual increase continuing up to 0.5 s. In general, the time delay is a function of the intensity of the untagging light exposure, the concentration of the caged dye, the sensitivity of the detector employed, and likely other factors including the pH and temperature of the solution. In the context of molecular tagging, this time-delayed release has two ramifications: it imposes a limit on the maxi-



Visualization Based on Molecular Tagging Methods, Figure 4 Schematic of typical experimental setup employed for caged-dye based visualization in capillaries. Optical immersion oil setup ensures minimal signal loss and prevents optical distortion at the capillary wall (the latter is not an issue with chip-based microchannels). Adapted from [6] with permission

mum flow velocity measurable over a given displacement, and the rate of generation term, R, in Eq. (1) becomes finite and thus requires consideration in the image processing/interpretation.

Since uncaged fluorescent dye is detectable at relatively low concentrations, this molecular tagging technique is applicable to electrokinetic flows. Applying caged fluorescence based molecular tagging to electrokinetic flows, however, requires knowledge of the electrophoretic velocity of the dye. As shown in Eq. (2), the observed velocity of the tagged solute is in fact a result of the desired bulk fluid velocity, as well as the electrophoretic velocity if the uncaged dye is charged. In the extreme case where the electrophoretic mobility of the tagged solute is equal to the electroosmotic mobility, the tagged solute will remain stationary regardless of bulk fluid motion. In general however, if the microchannel section of interest is straight and of constant cross-section, the electrophoretic dye velocity may be calculated directly from dye property data and boundary conditions. More involved methods have been developed in order to additionally account for Joule heating induced fluid temperature rise on this calculation [6]. It has also been reported that the adsorption of caged dye onto polymer microchannel walls can alter the surface properties, and thus applicability of caged fluorescence based molecular tagging to electrokinetic flows in polymer based microchannels may be limited.

Caged fluorescence tagging is generally limited to small scale visualization experiments as the cost of caged dyes is relatively high (portions on the order of milligrams are commonly valued on the order of hundreds of US dollars). Another consideration is that the signal strength is generally low (depending on uncaging intensity, untagged volume, dye concentration etc.). Despite some disadvantages however, caged dye based molecular tagging has been relatively popular, and successfully applied in a wide variety of microscale flow visualization efforts. Some of these works are highlighted in the key research findings section here, and a detailed listing is provided elsewhere [1].

Determining Velocity from the Image Data

The first step in interpreting the image data is image processing. Image processing is required to both remove any non-uniformities present in the imaging system, and to convert fluorescence or absorbance levels to concentration.

At the minimum this process involves dark-field subtraction and bright-field normalization. Multiple texts on digital image processing are available.

After processing, intensity levels in the image set may be interpreted directly as concentration, and thus the image set forms a sequence of snap-shot solutions to the transport equation described earlier, Eqs. (1–3). The general process of extracting the bulk fluid velocity, $\boldsymbol{u}$, from the species transport equation has been studied extensively and termed Scalar Image Velocimetry (SIV) [7]. A full SIV formulation can be quite involved. For the specific case illustrated in Fig. 1, where a cross-sectional band of molecules are tagged in a straight channel of uniform cross-section, a much simplified SIV technique, such as the one illustrated in Fig. 5, can be effective. In short, the strategy involves choosing axial points of maximum concentration as marker points, and tracking the motion of these marker points over time (i. e., through the image sequence) to determine the cross-stream velocity profile. The axial maximum concentration points are chosen as their axial position is less effected by diffusion and any rate of generation or photobleaching of tagged molecules. As shown in the figure, the axial maximum concentration points form a cross-stream profile at each time-step. The axial displacement of this profile, divided by the time delay between images provides a cross-sectional velocity profile, $\boldsymbol{u}$. Although this method has limitations, it is relatively straightforward to implement computationally and has provided reliable results both for pressure-driven and electroosmotic flows. Some key research findings are summarized in the next section.

Key Research Findings

The limited space available here does not allow for comprehensive review of the multitude of important research contributions, particularly since the late 1990s, in the area of molecular tagging based visualization of small scale flows. For a comprehensive review, the reader is referred to a recent review paper [1] and the references therein. Below, a sampling of some early and influential papers in this area are discussed.

The term molecular tagging velocimetry first became popular in connection to phosphorescence tagging methods [8]. Originally employed in macroscale flow visualization studies [8], so-called phosphorescent supramolecules have since been applied to visualization of relatively fast flows in microtubes.

In 1998, Paul et al. [9] applied caged fluorescence tagging to visualize flows in capillaries. The importance of that contribution is evidenced by a long citation record. This technique has been adapted by several groups, and applied to study flows in microchannel bends, the effect of non-uniform zeta potential, flows in plastic microchannels, Joule heating effects (both on the determination of electrophoretic velocity and on the flow), and many others as described in Ref. [1] and references therein. Shelby and Chiu [5] extended the use of caged fluorescence tagging in microsystems to high speed pressure-driven flows using extremely sensitive single point detection.

Mosier et al. [3] applied photobleached fluorescence tagging to study both electrokinetic and pressure-driven flows in rectangular microchannels. High molecular weight fluorescent conjugates were used to decrease diffusive effects (a diffusion coefficient four orders of magnitude below that of fluorescein). An argon laser was employed to achieve the photobleaching while a fluorescence microscope facilitated the visualization. A niche flow marking technique requiring only flood illumination was later developed using the reflective optical properties of a microchannel-entrapped bubble [4].

Future Directions for Research

The application of molecular tagging based visualization to nanoscale flows is an exciting research direction. The molecular dimensions of these probes make them well suited to these geometries, however, several challenges exist. Most notably, resolving nanoscale features with visible light presents a fundamental challenge due to the inherent wavelength of visible light. Along similar lines it is expected that as nanoscale based flow visualization methods are developed, traditional distinctions between scalar based and particle based methods will vanish. Although nanoscale velocity gradients have not yet been resolved, depth-wise averaging of fluorescence signal over nanoscale depths is one strategy that has been successfully employed recently in nanoscale electrophoresis applications. Another future research avenue is the improvement of molecular tagging probe chemistries and invention of new molecular tagging strategies. A wide variety of probes are produced in response to demand from biological research and molecular probes with improved functionality for visualization purposes may be a useful byproduct of this demand. Lastly, molecular tagging based velocimetry could play an interesting role in the rapidly emerging field of optofluidics, the marriage of optics and fluidics.

Cross References

- ► Micro-PIV-Based Diffusometry
- ► Diffusion
- ► Electrical Current Monitoring Methods



Visualization Based on Molecular Tagging Methods, Figure 5 Compilation illustrating an axial maximum concentration point tracking strategy for determining the bulk fluid velocity from image data. Shown is a much simplified version of general scalar image velocimetry techniques. Adapted from [6] with permission

- ▶ Electroosmotic Flow (DC)
- ▶ Electrophoresis
- ▶ Fluid Metering
- ▶ Fluorescence Measurements
- ▶ Fluorescent Labeling
- ▶ Hydrodynamic Dispersion
- ▶ Methods for Flow Rate Measurements
- ▶ Microscale Flow Visualization
- ▶ Velocimetry

References

1. Sinton D (2004) Microscale Flow Visualization. Microfluid Nanofluid 1:2–21
2. Probstein RF (2003) Physicochemical Hydrodynamics. John Wiley&Sons, NJ
3. Mosier BP, Molho JI, Santiago JG (2002) Photobleaching-fluorescence imaging of microflows. Exp Fluids 33:545–554
4. Sinton D, Erickson D, Li D (2003) Micro-Bubble Lensing Induced Photobleaching (μ-BLIP) with Application to Microflow Visualization. Exp Fluids 35:178–187
5. Shelby JP, Chiu DT (2003) Mapping Fast Flows Over Micrometer-Length Scales Using Flow-Tagging Velocimetry and Single-Molecule Detection. Anal Chem, 75:1387–1392
6. Sinton D, Li D (2003) Electroosmotic Velocity Profiles in Microchannels. Colloids Surf A 222:273–283
7. Dahm WJA, Su LK, Southerland KB (1992) A Scalar Imaging Velocimetry Technique for Fully Resolved Four-dimensional Vector Velocity Field Measurements in Turbulent Flows. Phys Fluid 4(10):2191–2206
8. Gendrich CP, Koochesfahani MM, Nocera DG (1997) Molecular Tagging Velocimetry and Other Novel Applications of a New Phosphorescent Supramolecule. Exp Fluid 23:361–372
9. Paul PH, Garguilo MG, Rakestraw DJ (1998) Imaging of Pressure- and Electrokinetically Driven Flows through Open Capillaries. Anal Chem 70:2459–2467

Voltage Clamp

▶ Patch Clamp Measurements On-Chip

Volume of Fluid (VOF) Method

▶ Interface Capturing Schemes for Free-Surface Flows

Volume Illumination

Definition

Volume illumination is an illumination method for image capturing where the whole volume around the focus plane is illuminated. The illumination axis is the same as the camera axis (one-axis-illumination) or the directions of illumination and camera are similar. Volume illumination and illumination with a ▶ light sheet are used for ▶ PIV and PIT measurements. When illuminating the whole volume, the ► measurement depth is defined by the ► depth of field of the optics. The disadvantage of this illumination method is the high background noise when using it in a suspension.

Volume Tracking

► Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking

Vortex Diode

Definition

A type of a no-moving-part fluidic diode the essential part of which is an axisymmetric chamber with tnagential inlet and axial outlet.

A fluidic diode based on the difference in fluid flow between the situations with fluid entering the chamber tangentially a producing there a rotation and with the fluid entering axially, when the rotation is absent. This type of diodes particularly suited for operation at relatively low operating frequencies. because star-up of the rotation in the chamber takes a considerable time.

Cross References

► Fluidic Diodes
► Valve-Less Rectification Pumps
► Fluidic Rectification

Vortex Pair

► Microsynthetic Jets

Vortex Ring

► Microsynthetic Jets

Vortices

► Chaotic Mixing Based on Viscoelasticity

Wafer Bonding

ZHENG CUI
Rutherford Appleton Laboratory, Oxford, UK
z.cui@rl.ac.uk

Synonyms

Direct bonding; Fusion bonding

Definition

Wafer bonding is a process by which two mirror-polished wafers of any materials adhere to each other at room temperature without the application of any macroscopic gluing layer or external force. The bonding is achieved through van der Waals force. Wafer bonding achieved at room temperature is usually relatively weak compared to metallically, covalently or ionically bonded solids. Therefore, for many applications the room temperature bonded wafers have to undergo a heat treatment to strengthen the bonds across the interface.

Overview

It has long been known that mirror-polished surfaces, when in direct contact, adhere to each other by capillary force, or electrostatic force or van der Waals force. In the absence of liquid or electrical charge at the mirror surfaces, the van der Waals force is the primary force to cause adhesion of two mirror-polished surfaces. The van der Waals force is an extremely short-ranged attractive force between two polar molecules. However, the force can be *long ranged* if there are water molecules participating the process, because the hydrogen atoms in water molecules can bridge with other molecules to form *long-ranged* hydrogen bonds instead of direct bonds between the solid atoms [1]. In the example of silicon wafer bonding, most silicon wafers are covered with a thin native oxide ($\sim 2\,\mathrm{nm}$) or purposely grown thermal oxide which have typically a monolayer or two of water molecules absorbed on OH groups associated with the oxide. At room temperature, silicon wafers may be bonded by relatively weak *hydrogen bridges*. A subsequent heat treatment can turn the weak hydrogen bonds to strong covalent bonds. For a hydrophobic surface where the thin oxide has been removed by dipping into HF, the process is expressed as Eq. (1). For a hydrophilic surface where there is a thin oxide layer, the process is expressed as Eq. (2).

Hydrophobic surface:

$$\mathrm{Si-H+H-Si \Rightarrow Si-Si+H_2} \tag{1}$$

Hydrophilic surface:

$$\mathrm{Si-OH+HO-Si \Rightarrow Si-O-Si+H_2O} \tag{2}$$

In both cases strong covalent bonds are formed after heat treatment. For a hydrophobic surface, the process starts at about 500 °C, while for a hydrophilic surface it is about 120 °C [1]. Typical change of surface energy with heat treatment temperature is shown in Fig. 1. Though they started differently as temperature rises, both hydrophobic and hydrophilic surfaces gain high surface energy at high temperature. The full covalent bond formation is accomplished at temperatures from 800 to 1200 °C. The bonds formed at such temperatures are as strong as those of a crystalline solid.

The first systematic investigation of room temperature adhesion between two optically polished glass plates was done by Lord Rayleigh in 1936. Later, the *anodic bonding* technique was developed for semiconductor wafer bonding with glasses and metals. Direct bonding of silicon wafers was first reported in 1986 [2]. In the same year, silicon wafer bonding with an oxide intermediate layer was also reported, which opened a new route for manufacturing silicon-on-insulator (SOI) wafers [3]. Semiconductor devices built on a SOI substrate were favoured because of their high resistance against the undesirable side effect of radiation-induced electron–hole pairs for application in outer space. The original driving force of *radiation hardness* behind SOI development, however, was dwarfed by



Wafer Bonding, Figure 1 Evolution of surface energy with temperature for hydrophobic and hydrophilic surfaces

its great commercial potential in integrated circuits (IC) manufacturing. ICs built on SOI substrates allow operation at lower voltage and higher packing density, as well as simultaneous use of low and high voltage on one chip. SOI technology has become the mainstream technology for the next generation of ICs [4]. Prior to the advent of silicon direct bonding, SOI wafers were produced by either epitaxial growth of single-crystal silicon on an insulating layer or by the so-called SIMOX process (Separation by IMplanted OXygen), in which high doses of high-energy oxygen ions were implanted into silicon, followed by annealing at a temperature close to the melting point of silicon, resulting in the formation of a buried layer of silicon dioxide below the thin top layer of silicon [5]. The SIMOX technique produces a high density of implantation-induced dislocations in the silicon layer. Both epitaxial growth and SIMOX processes are expensive and of low throughput. Direct silicon wafer bonding has completely changed the way SOI substrates are manufactured.

Another important application of wafer bonding is in microelectromechanical systems or MEMS. Semiconductor wafer bonding is an ideal technique to combine different structures to form functionalised elements in a three-dimensional arrangement. The first application of wafer bonding to build micro-pressure sensors was reported in 1988. Now wafer bonding has been employed in research and production of nearly all types of MEMS, including mechanical, fluidic, power, optical, medical and biological microsystems. Wafer bonding enables combination of silicon with a large variety of dissimilar materials, such as III–V and II–VI compound semiconductors, to build optoelectronic devices. It also enables transfer of MEMS devices onto a fully processed CMOS wafer to realise integration of MEMS with CMOS electronic circuits.

It must be pointed out that direct bonding of silicon wafers is not the only type of wafer bonding, though it represents the largest application of wafer bonding techniques. There are other bonding techniques, apart from *anodic bonding*, that can be considered as wafer bonding, such as eutectic bonding, adhesive bonding and glass frit bonding.

- Eutectic bonding is used when a hermetic or vacuum seal is required, generally for sensors. It uses an intermediate bonding material that forms a eutectic alloy at a specific temperature, such as gold–silicon, gold–tin or lead–silicon. The metal is usually deposited by plating, while the silicon source can be the wafer or chemical vapour deposited. Solid–liquid mixing occurs at temperatures slightly above the eutectic point and high contact force (40 kN) is produced. A hermetic solid seal forms upon cooling.
- Adhesive bonding uses photoresist, spin-on glasses or polymers to deposit a planarising material between two wafers. Such materials can be annealed or UV cured at low temperature to provide a low-stress wafer stack.
- Glass frit bonding uses glass beads (glass frit) suspended in a carrier paste and deposited onto a substrate either in a blanket form or patterned using screen printing. After deposition, the solvents are removed by degassing then heat and pressure are applied to make a hermetic seal.

Although silicon direct bonding has wide applications in MEMS and IC industries, it is not as much used in constructing micro- or nanofluidic systems because of the conductive nature of silicon wafers. Many microfluidic applications require application of an electrical field, such as those utilising *electrophoresis* and *electroosmosis*. For these applications, glass materials are preferred. A glass material permits the use of high voltages, which provides the basis for fast and efficient separation of analytes. Its transparency allows sensitive and invasive optical detection of samples. Microfluidic applications also tend not to use adhesive or intermediate layers in wafer bonding, because they may clog the microchannels or adversely affect the liquid flow patterns.

Basic Methodology

The success of direct wafer bonding is critically dependent on surface properties and conditions, chemical cleaning process and ambient conditions when the initial room temperature bonding is performed. Particles on the bonding surface will adversely affect the bonding. For example, a particle of 1 µm diameter can generate a void with a diameter of 0.5 mm which is 500 times larger the particle itself. Interfacial bubbles are often generated during the heat treatment step, which is not related to particles. Direct wafer bonding used to be a difficult manufacturing technology and sometimes characterised as *black magic* in the past [1]. Now with better understanding of the fundamental physics and chemistry of the bonding process, the technology has matured and been implemented in high-volume production. The direct wafer bonding involves four basic steps:

1. Preparation of bonding surfaces. The surfaces have to be polished mirror-like, with surface roughness less than 1 nm and thickness variation across a 4-inch wafer less than 2 µm. Normal silicon wafers straight out of the box without any processed structures are of the surface quality for direct bonding. However, if the wafer has been processed a thorough clean is necessary to remove any particulate, organic and metallic contaminations. In the meantime, the cleaning process should not degrade the surface smoothness. Hydrogen peroxide-based RCA wet solutions are commonly used for cleaning, which is also the standard cleaning solution in semiconductor manufacturing. There are two steps in cleaning: the first step is to remove any particles and organics using RCA1 ($NH_4OH : H_2O_2 : H_2O = 1 : 1 : 5$) and the second step is to remove any alkali and heavy metal contaminations using RAC2 ($HCl : H_2O_2 : H_2O = 1 : 1 : 6$) [1]. In addition to cleaning, activating the surface is highly desirable. The surface activation is to create a reactive bonding surface, for example to create the abovementioned hydrogen *bridge* bonds, so that the requirement on surface smoothness can be fairly relaxed. Activation makes the surface either hydrophobic or hydrophilic.
2. Room temperature bonding. After cleaning and activation, the two wafer surfaces are brought into contact in air and at room temperature. With a slight press to push out the thin cushion of air between the wafers, bonding occurs at the pressing area and spreads out rapidly over the entire surface within a few seconds. It must be emphasised that this step should be performed in an environment as clean as possible. Even in a *class 1* cleanroom (one 0.5 µm or larger particle in a cubic foot of air), 100% bonding yield cannot be guaranteed because of the risk of particles falling onto the bonding surface. In order to alleviate the stringent requirement on the cleanroom, special apparatus acting as a micro-cleanroom has been developed to reduce the chance of a particle dropping onto the bonding surface [1].
3. Heat treatment. This step is to convert the van der Waals weak bonds to covalent strong bonds at temperatures from 800 up to 1200 °C. Although the initial change of surface energy is different at low temperature for hydrophobic and hydrophilic surfaces, they all form the covalent bonds in the final stage of heat treatment, as shown in Fig. 1. The time of heat treatment depends on the temperature, ranging from hours to days. High temperature requires less time.
4. Wafer thinning. Although this is not a necessary step, many applications require one of the bonded wafers to be thin, from 100 nm to a few micrometres thick. This is an important step for manufacturing SOI wafers, in which the thin single-crystal silicon layer is called the device layer and the supporting silicon wafer called the handle layer. A number of techniques have been developed for wafer thinning, but the most elegant one is the *smart-cut* process [6]. As shown schematically in Fig. 2, it is based on hydrogen implantation prior to bonding. High-energy hydrogen ions implanted deep into the silicon form a buried layer which leads to cracking and splitting from the silicon wafer during heating to about 500 °C. Therefore, after implantation and bonding the top wafer can be separated from the handle wafer by heating, leaving the thin layer of silicon bonded with the handle wafer. Only a slight polishing to the splitting surface is needed to achieve the equivalent surface of a typical silicon wafer. In this way, the split-off wafer can be used again and again, because each bonding-splitting only loses a fraction of the thickness in the wafer. The smart-cut process has now become a mass production technology for manufacturing SOI wafers.

The bonding strength or surface energy after bonding can be measured by a so-called crack-opening method which is shown schematically in Fig. 3. For bonding of identical wafers ($t_{w1} = t_{w2} = t_w$, $E_1 = E_2 = E$), the surface energy per unit area γ can be expressed as [7]

$$\gamma = \frac{3Et_w^3 t_b^2}{32L^4} \qquad (3)$$



Wafer Bonding, Figure 2 Schematic of the *smart-cut* process for manufacturing SOI wafers

where E is the Young's modulus, t_w is the wafer thickness and L is the crack opening length. The surface energy for room temperature bonding is typically around 100 mJ/m^2 for hydrophilic surfaces and around 20 mJ/m^2 for hydrophobic surfaces. It becomes one or two orders of magnitude higher after heat treatment, as indicated in Fig. 1. For good-quality bonding, the bonding strength is that of a normal crystalline structure. Bonding uniformity or defects at bonding interface can be inspected by either infrared imaging or scanning acoustic microscopy.

Bonding of glass is also called fusion bonding. The method is more or less the same as silicon wafer bonding [8]. It requires polished surfaces, cleaning in RCA1 and RCA2 solutions. The cleaned and polished surfaces are brought into contact and heated at the temperature nearly to the melting point of glass for 6 to 8 h. For soda-lime microscope glass slides, the thermal fusion temperature is around 630 °C. For quartz substrates, the temperature can be up to 1000 °C. In most cases, a pressure applied to the bonding pair during the thermal fusion process can help to achieve a good bonding. The bonding strength is about 20 – 30 MPa, close to the strength of bulk material [9].



Wafer Bonding, Figure 3 Schematic of the crack-opening method for measuring bonding strength

Key Research Findings

The key development in wafer bonding in recent years is the low-temperature bonding technique. As mentioned above, the typical annealing temperature in silicon wafer bonding is above 800 °C. However, an increasing number of applications require temperature below 500 °C because integration of MEMS devices with a CMOS wafer has a thermal budget below 450 °C. The key to realising low-temperature wafer bonding is to modify the wafer surface: either to increase the number of hydrogen bonds or to generate new types of chemical bonds. Although some techniques utilising various intermediate layers have been developed to facilitate low-temperature bonding, the most simple and effective method is by surface activation using a plasma process. It has been found that a short plasma treatment of a bonding surface ($\sim$ 30 s) can lower the bonding temperature to 200 – 500 °C. The exact mechanism of plasma activation is not yet fully understood. For oxygen plasma, it may be due to an increase of oxide layer, combined with a higher porosity of the amorphous layer because of ion bombardment, resulting in an increasing incorporation of additional water molecules [10]. However, wafer surfaces treated in argon and nitrogen plasmas can also undergo low-temperature bonding. Recent studies indicated that the activation effect of semiconductor surfaces is mainly caused by electrons and UV radiation instead of ions. The effect of UV radiation is an additional cleaning of the surfaces by cracking of CH compounds and electrons help to generate surface-active sites, causing bonding of more OH groups [10]. Plasma activation can also help to lower the temperature for bonding of dissimilar materials.

Future Directions for Research

Wafer direct bonding has become a key technology in semiconductor manufacturing. It offers the freedom in the design of material combination whether they are amorphous, polycrystalline, of different crystalline orientation or lattice constant. The most successful example is mass manufacturing of SOI wafers, which already has had a profound impact in the integrated circuits industry. Applications of wafer bonding in MEMS and microsystems are increasing and the technique is promised to be the key for three-dimensional integration of device structures and full integration with CMOS-based wafers. Such integration will have a significant impact on micro- and nanofluidics development. While it is a constant pursuing goal to further broaden the application of the wafer bonding technique, some basic studies are needed to better understand the mechanism of plasma activation for low-temperature bonding. Further researches are also needed to understand the physical and chemical processes of wafer bonding for materials other than silicon.

Cross References

- ► Anodic Bonding
- ► Packaging (Including Wire Bonding)

References

1. Tong QY, Gosele U (1999) Semiconductor Wafer Bonding Science and Technology. Wiley, New York
2. Shimbo M, Fukukawa K, Fukusa F, Tanzawa K (1986) Silicon-to-silicon direct bonding method. J Appl Phys 60:2987–2989
3. Lasky JB (1986) Wafer bonding for silicon-on-insulator technology. Appl Phys Lett 48:78–80
4. Iyer SS, Auberton-Herve AJ (eds) (2002) Silicon wafer bonding technology for VLSI and MEMS applications. INSEPCT. the IEE, London
5. Izumi K, Doken M, Ariyoshi H (1978) CMOS devices fabricated on buried SiO2 layers formed by oxygen implantation into silicon. Electron Lett 14:593
6. Bruce M (1995) A new silicon on insulator material technology. Electron Lett 31:1201–1202
7. Gosele U, Tong QY, Schumacher A, Krauter G, Reiche M, Plossi A, Kopperschmidt P, Lee TH, Kim WJ (1999) Wafer bonding for microsystem technologies. Sens Actuator 74:161–168
8. Stjernstrom M, Roeraade J (1998) Method for fabrication of microfluidic systems in glass. J Micromech Microeng 8:33–38
9. Sayah A, Solignac D, Cueni T, Gijs MAM (2000) Development of novel low temperature bonding technologies for microchip chemical analysis applications. Sens Actuator A 84:103–108
10. Reiche M (2006) Semiconductor wafer bonding. Phys Stat Sol A 203(4):747–759

Wall Shear Stress

Synonyms

Shear stress

Definition

Wall shear stress is the tangential drag force produced by horizontal movement of the fluid across the surface. It is a function of the velocity gradient of the fluid near the surface. Its magnitude is directly proportional to fluid flow and viscosity and inversely proportional to the cube of the radius.

Cross References

- ► Micro- and Nano-Scale Anemometry: Implication for Biomedical Applications
- ► Pressure

Wang-Chang–Uhlenbeck Equation

- ► Numerical Solution of Boltzmann Equation

Water Management in Micro DMFCs

CHENG-CHIEH HSIEH
Intel Corporation, Chandler, AZ, USA
cheng-chieh.hsieh@intel.com

Synonyms

Direct Methanol Fuel Cell

Definition

A DMFC (Direct Methanol Fuel Cell) converts the chemical energy stored in liquid methanol to usable electrical energy by a direct electrochemical oxidation-reduction reaction.

Overview

In a DMFC, methanol is directly oxidized on the surface of catalytic electrodes at the anode.

$$\mathrm{CH_3OH_{(l)}} + \mathrm{H_2O_{(l)}} \rightarrow \mathrm{CO_{2(g)}} + 6\mathrm{H}^+ + 6\mathrm{e}^- \qquad (1)$$

The electrons are drawn to an external circuit through conductive backing layers to generate electricity, and the pro-



Water Management in Micro DMFCs, Figure 1 Schematic of a passive micro-scale CO_2 degassing system in a DMFC



Water Management in Micro DMFCs, Figure 2 Water management at the cathode of a DMFC

tons migrate through a humidified solid electrolyte (Proton Exchange Membrane, PEM) and react with oxygen at the cathode.

$$\tfrac{3}{2}O_{2(g)} + 6H^+ + 6e^- \rightarrow 3H_2O_{(l)} \quad (2)$$

Carbon dioxide (CO_2) evolves on the anode surface in the form of gas bubbles, impeding methanol supply to the catalyst surface. Surface treatment with a selective hydrophobic coating on the backing layer is used to assist CO_2 bubble scrubbing [1]. CO_2 bubbles escaping from the catalyst surface accumulate in the internal fuel circulation loop. The resulting two-phase flow drastically increases the flow resistance of the fuel circulation loop and may totally choke the flow path. A passive CO_2 degassing system, consisting of two parallel plates with an array of etched-through holes, is shown in Fig. 1 [2]. The wettability of the surface of the gas separator is modified by a thin layer of hydrophobic coating to facilitate gas bubble removal from the gas-liquid mixture. The coating also prevents fuel leakage through the openings by forming a meniscus at the mouth of the openings inside the system. The maximum sustainable opening diameter ($D_{\max}$) to avoid liquid leakage can be approximated by the well-known Young–Laplace equation.

$$D_{\max} = \frac{4\gamma \cos(180^\circ - \theta)}{P_s - P_0} \quad (3)$$

where γ is the surface tension of the fuel mixture, θ is the contact angle (in degree) of the fuel mixture on the hydrophobic surface, P_s is the system pressure and P_0 is the ambient pressure. The liquid separator, on the other hand, is hydrophilic in order to create an effective passage for the liquid flow.

Water is generated at the cathode. The excessive water may result in flooding, reducing the effective surface area of the cathode available for the reduction reaction and hence, lowering the entire electrochemical reaction rate. The same concept of preferential surface wettability modification used in the passive CO_2 degassing system can be applied to resolve this water management issue. As shown in Fig. 2, a hydrophobic thin film is coated on the area with small openings to allow air (oxygen) "breathing", while the surface of the area with large openings remains hydrophilic to assist water removal from the cathode surface [2]. The water expelled from the cathode through the openings is guided and collected along the hydrophilic surface without cross-covering the area with small. Part of the collected water can then be recycled back to the anode to maintain the electrochemical reaction.

References

1. Scott K, Taama WM, Argyropoulos P (1998) Material Aspects of the Liquid Feed Direct Methanol Fuel Cell. J Appl Electrochem 28:1389–1397
2. Yao SC, Tang X, Hsieh CC, Alyousef Y, Vladimer M, Fedder GK, Amon CH (2006) Micro-Electro-Mechanical-Systems (MEMS)-based Micro-scale Direct Methanol Fuel Cell Development. J Energy 31:636–649

Waveguide Propulsion

► Optofluidics: Optics Enabling Fluidics

Waveguide Trapping

► Optofluidics: Optics Enabling Fluidics

Weak Formulation

Synonyms

Generalized formulation

Definition

A weak formulation is an equation derived from the original (strong) formulation of a physical problem by alleviating the strict differentiability requirements for the unknown function. This is often achieved by lowering the order of partial derivates appearing in the equation for instance using integration-by-parts.

The solution to a weak formulation associated to an ordinary or partial differential equation is called the weak (or generalized) solution. There are many different definitions of weak solution, appropriate for different classes of equations.

Weak solutions are important in engineering because a large number of differential equations which are used to describe real world phenomena do not admit smooth enough solutions. Weak formulations provide a way to solve such problems.

Cross References

- ► Meshless Methods
- ► Volume and Finite Difference Method for Modeling and Simulation

Weber Number

Definition

The dimensionless *Weber number* represents the ratio of disruptive hydrodynamic forces to the stabilizing surface tension force. Hence, the *Weber number* indicates whether the kinetic or the surface tension energy is dominant. For a spherical droplet the *Weber number* can be derived using the kinetic energy compared to the surface energy.

The *Weber number* can be used for two different declarations. On the one hand it describes whether a droplet can leave a nozzle at all due to higher kinetic energy compared to surface energy. On the other hand it can describe whether a droplet has the tendency for splashing when the kinetic energy is released at the impact on a surface.

The higher the *Weber number* the more dominant is the kinetic energy. This means that most of the inserted energy converts into kinetic energy, i. e. an ejected droplet is faster with higher *Weber number*. The lower the *Weber number* the more dominant is the surface tension energy. This means that most of the inserted energy converts into surface tension energy, i. e. a droplet formation is critical or even impossible.

The *Weber number* is the most important dimensionless number characterizing the droplet formation. Therefore, the *Weber number* can be used to distinguish between occurring droplet formation regimes.

Cross References

- ► DNA Micro-arrays
- ► Droplet and Bubble Formation in Microchannels
- ► Electrokinetic Dispensing
- ► Piezoelectric Microdispenser

Weighted Least Square

- ► Least Square

Weights and Measures

- ► Fluid Metering

Wet Chemical Etch

Definition

Wet etching is the process of using liquid reagents of acids, bases or other chemicals to dissolve away unwanted materials such as metals, semiconductor materials or glass.

Cross References

- ► Anisotropic Etching
- ► Bulk Micromachining
- ► Dry Etching
- ► Isotropic Etching
- ► Photolithography
- ► Plasma Etching
- ► Wet Etching

Wet Etching

Definition

Wet etching is a fabrication process of using liquid chemicals or wet etchants (a mixture of acids, base, water and other chemicals) to dissolve the bulk substrate or thin film such as silicon,GaAs,SiC,SiO_2,Si_3N_4 and metals. In microfabrication applications, it is widely used to transfer the designed patterns from an etching mask to the substrate. When the sample is immersed into the etching bath, the etchant only contacts and reacts with the substrate surfaces where are uncovered by the etching mask. The suitable materials for the mask can be polymers or other materials such as photoresist, SU-8,SiO_2 andSi_3N_4, which feature much lower etching rate in the selected etchant in contrast to the substrate material.

Wet etchants fall into two broad categories: isotropic etchants and anisotropic etchants. Isotropic etchants attack the material being etched at the same rate in all directions. Anisotropic etchants attack some single-crystal materials (typically silicon) at different etch rates depending on the crystallographic orientation of the substrate, so there is more control of the shapes being produced.

Wet etching is the most common processing in semiconductor industry and MEMS applications.

Cross References

- ► Fabrication of 3-D Microfluidic Structures
- ► Microfabrication Techniques
- ► Photolithography
- ► Photoresist Reflow
- ► Wet Chemical Etch

Wettability Patterning

- ► Hydrophilic/Hydrophobic Patterning

Wetting Phenomenon

- ► Surface Tension Driven Flow

Wetting and Spreading

Leslie Yeo
Micro/Nanophysics Research Laboratory
Department of Mechanical Engineering, Monash
University, Clayton, VIC, Australia
leslie.yeo@eng.monash.edu.au

Synonyms

Capillarity

Definition

The wettability of a liquid governs how it spreads over a solid substrate or an immiscible liquid phase and is characterized by a contact angle, which is the angle subtended by the liquid/vapor interface and the solid or immiscible liquid surface. Depending on the surface energy of the substrate, two equilibrium situations can occur upon contact of the liquid and the solid. *Complete wetting* corresponds to the situation when the surface energy of the substrate is high and hence the liquid spreads entirely over (or wets) the solid, thereby forming a film in which case the contact angle is zero. *Partial wetting*, on the other hand, relates to the situation when the surface energy of the substrate is low and hence a finite contact angle is obtained in which case the liquid retains its drop shape which is restricted at the solid surface by a contact line where the solid, liquid and vapor phases meet. The governing principle is the minimization of interfacial energy; in the former case, the interfacial contact between the liquid film and the solid substrate minimizes the free energy of the surface.

Overview

Wetting and spreading, the subject of which is a fundamental pillar of colloid and interface science, are fundamental processes which occur in a wide variety of natural and industrial settings. These processes govern the adhesion between two substances and therefore have significant implications in paint, lubrication, coating, printing and fabric technology as well as in enhanced oil recovery. More recently, there has been renewed interest in the relevance of wetting and spreading in biological and microscale environments. The functional design of biomaterials and biological surfaces requires a thorough understanding of the interrelationships of bio-surfaces and bio-environments. The miniaturization of fluid processes, on the other hand, is associated with an increase in the dominance of surface forces over body forces given that the surface area to volume ratio scales as the inverse of the characteristic system dimension. Thus, at microscale dimensions, surface tension and hence wettability (or capillarity) effects are extremely important considerations in the design of microfluidic devices.

Basic Methodology

Surface Tension and Contact Angle

The relationship between surface tension γ and contact angle θ, formally defined as

$$\theta = \cos^{-1}(\boldsymbol{n}_l \boldsymbol{n}_s) , \tag{1}$$

where $\boldsymbol{n}_l$ and $\boldsymbol{n}_s$ are the outward pointing unit normal vectors from the liquid and solid at the three-phase contact line, respectively, was first established by Thomas Young in 1805 through a force balance in the plane of the surface at the contact line (Fig. 1):

$$\gamma_{\mathrm{LV}} \cos\theta = \gamma_{\mathrm{SV}} - \gamma_{\mathrm{SL}} \,, \tag{2}$$

where the subscripts LV, SV and SL denote the liquid-vapor, solid-vapor and solid-liquid phases, respectively. Equation (2) is thus known as *Young's equation*. It should be noted that a force balance also exists in the plane normal to the surface due to the existence of a strain field beneath the contact line to balance the force component $\gamma_{\mathrm{LV}} \sin\theta$. In the case of a liquid lens sitting at the interface of an immiscible liquid, the lens shape is governed by this force balance, the resultant of which is zero (Fig. 2). Equation (2) can also be derived by energy minimization considerations.

The spreading of the drop can be characterized by a spreading coefficient:

$$S = \gamma_{\mathrm{SV}} - \gamma_{\mathrm{SL}} - \gamma_{\mathrm{LV}} \,. \tag{3}$$

If $S \geqslant 0$, complete spreading occurs in which the drop spontaneously forms a liquid film above the solid substrate, as shown in Fig. 3(a), due to a decrease in the free energy. If $S < 0$, $\theta > 0°$ from Eq. (2) and the drop spreads to an equilibrium shape, constrained by the contact line where the three phases meet; if $\theta < 90°$, the surface is said to be *hydrophilic* (Fig. 3(b)) whereas the surface is said to be *hydrophobic* if $\theta > 90°$ (Fig. 3(c)). Strictly speaking, there is no local minimum in the interfacial energy for $S > 0$ and hence the equilibrium contact angle $\cos\theta$ cannot be defined by Eq. (2). The minimum is defined at $S = 0$, which from Eqs. (2) and (3) gives $\cos\theta = 1$ or $\theta = 0°$, corresponding to the complete wetting case.



Wetting and Spreading, Figure 1 Force balance at the three-phase contact line where the solid-liquid and vapor phases meet. The outward unit normals protruding from the solid and liquid at the contact line are shown. The angle θ subtending these unit normal vectors or that subtending the interface between the drop and the solid substrate is known as the contact angle



Wetting and Spreading, Figure 2 Force balance at the contact line of a liquid lens sitting above an immiscible liquid

The contact angle is known as a *static* contact angle when the contact line is stationary with respect to the solid substrate. Young's equation in Eq. (2) is therefore a description of the static contact angle. On the other hand, if the contact line is moving relative to the solid, the contact angle, whether it is advancing or receding, is known as a *dynamic* contact angle. The dynamic contact angle varies with the speed at which the contact line advances (or recedes). The upper theoretical limit of the receding contact line speed is therefore the case of complete wetting where the dynamic contact angle approaches 0°. The opposite completely non-wetting limit can be seen when the bulk of the advancing fluid and hence the drop interface overtakes the contact line and hence entrains the fluid being displaced. An example of this is in gravity driven fronts in which the advancing front of the drop forms a nose which rolls over the contact line, as shown in Fig. 4, in which case the dynamic contact angle would approach 180°; in this case, the entrained fluid is therefore the air surrounding the drop. In the extreme completely non-wetting case $\theta = 180°$, a thin submicroscopic film of the displaced phase is entrained beneath the drop therefore causing the complete disappearance of the contact line.

A point should be made here about superhydrophobic surfaces, over which a drop can translate via two states. In a suspended state, the drop sits atop the apex tips of the rough surface; air is entrained beneath the drop and fills the interstices of the rough surfaces between the apex tips. In this state, it has been shown that the velocity of the drop increases with increasing contact angles. Although this may seem contradictory to the classical view above, it is this author's view that the contact line receding speed remains low but the drop itself slides over the entrained air layer due to bulk convection. The increasing bulk drop velocity with increasing contact angles is attributed to the higher center of mass of the drop [1]. For drops in a collapsed state, wherein the liquid fills the interstices of the rough surface, the drop velocity is reduced dramatically each time the contact line reaches a cavity and a stick-slip motion is therefore observed.


Liquid film
Contact Line
θ
Contact Line
θ
Complete wetting (θ = 0°)
Hydrophilic (θ < 90°)
Hydrophobic (θ > 90°)
a
b
c

Wetting and Spreading, Figure 3 Equilibrium conditions for a liquid drop in contact with a solid substrate. (**a**) Complete wetting. (**b**) Partial wetting: hydrophilic drop. (**c**) Partial wetting: hydrophobic drop



Wetting and Spreading, Figure 4 Schematic depiction of contact angle hysteresis arising when the solid substrate upon which a drop is placed is inclined. At the instance prior to the drop moving down the plane, the contact angle at the advancing front and at the rear are known as the advancing and receding contact angles, respectively



Wetting and Spreading, Figure 5 Contact angle hysteresis arising due to the dependence of the apparent contact angle θ on the contact line velocity U


Advancing contact angle θ_A
Receding contact angle θ_R

Wetting and Spreading, Figure 6 Measurement of the advancing and receding contact angles by incrementally adding or removing liquid through a thin capillary tube. The measurements are taken just prior to motion of the contact line

The boundary between the static and dynamic conditions also gives rise to contact angle hysteresis, in which the static contact angle when the contact line velocity U is zero is not single-valued (as predicted by Eq. (2)), as shown in Fig. 5, which maps out the velocity dependence of the contact angle. The static contact angle at equilibrium θ appears to be dependent on the history of the drop, i. e., on whether it is on the verge of advancing or receding. The observed contact angle at the front just before the inclined drop in Fig. 4 begins to slide is known as the *advancing* contact angle θ_A whereas that at the rear is known as the *receding* contact angle θ_R. Alternatively, the advancing and receding contact angles can be obtained by measuring the contact angle of a sessile drop just prior to motion when liquid is added or removed from a capillary above the drop to drive it to advance or recede, respectively, as illustrated in Fig. 6. The difference in the advancing and receding angles, i. e., $\theta_A - \theta_R$ (typically 10° or larger), is therefore the contact angle hysteresis, and the equilibrium static contact angle takes any intermediate value in between these limits, i. e., $\theta_R \leqslant \theta \leqslant \theta_A$.

Contact angle hysteresis can be attributed to a departure from the conditions of ideality of the solid, namely, surface roughness, chemical inhomogeneities or contamination, or, the presence of solute (polymers or surfactants) deposits on the surface [2]. Figure 7 shows a plan view illustration of the hysteresis mechanism in which the receding contact line of a drop is locally pinned when the drop moves over a localized surface inheterogeneity which is more hydrophilic than the substrate surface. As a result, there is a distortion of the contact line [3]. If the macroscopic force exerted on the contact line is

$$F = \gamma_{LV} \left(\cos\theta' - \cos\theta \right) , \qquad (4)$$



Wetting and Spreading, Figure 7 Plan view illustrating the pinning of the receding contact line due to the presence of a localized surface heterogeneity (represented by the shaded spot) which is more hydrophilic than the substrate. The arrows indicate the direction of the drop motion

where θ' is the contact angle of the drop and θ is the equilibrium contact angle given by Young's equation (Eq. (2)), we note that it is not possible to detach the contact line below a given value of the force and hence the contact line remains pinned for contact angles θ' below that of the equilibrium contact angle θ. In such cases and when evaporation is significant, there arises liquid flow from the bulk of the macroscopic drop in order to replenish the liquid evaporated from the contact line region. If solutes are present in the liquid, these are convected towards the contact line and deposited there, resulting in the formation of concentrated rings along the perimeter of the contact line; an example of this is the ubiquitous coffee-ring stain phenomenon.

A distinction between the *apparent* (or visible) contact angle θ_a and the intrinsic contact angle θ is worthy of mention. The apparent contact angle is a macroscopic extrapolation whereas the intrinsic contact angle is that microscopically subtended from the solid substrate at the contact line, as schematically depicted for a rough surface in Fig. 8. The advancing and receding contact angles due to contact angle hysteresis therefore relate to apparent contact angles. Thus, were the surface ideal, i. e., atomically smooth, clean and homogeneous such that Eq. (2) holds, then the apparent contact angle should coincide with the intrinsic contact angle to describe the equilibrium static contact angle.

Nevertheless, for most practical surfaces, this is not true and hence the intrinsic contact angle is difficult to determine. The surface heterogeneities could very well be the reason why the wetting line moves in a hesitant jerk or shuffling motion, termed as *stick-slip* motion [4]. This could also be attributed to the successive formation and collapse (due to negative disjoining pressure) of the entrained air film beneath the drop. Changes to the apparent contact angle, nevertheless, can be evaluated for rough surfaces. Consider a small displacement of the contact line dx on a rough but chemically homogeneous surface, as shown in Fig. 9(a). The change in the surface energy per unit length along the contact line dE is then



Wetting and Spreading, Figure 8 Schematic depiction of the contact line region on a microscopic level illustrating the distinction between the apparent (macroscopic) contact angle θ_a and the intrinsic (microscopic) contact angle θ due to surface roughness effects on the substrate

$$\mathrm{d}E = (\gamma_{\mathrm{SL}} - \gamma_{\mathrm{SV}})\, r\mathrm{d}x + \gamma_{\mathrm{LV}} \cos\theta^* \mathrm{d}x\,, \tag{5}$$

in which r is the surface roughness (assumed to be much smaller than the macroscopic drop length scale) and θ^* denotes the contact angle on the rough surface ($r > 1$).

At equilibrium, the resultant surface forces at the contact line balance and hence the energy is at its minimum, i. e., $\mathrm{d}E/\mathrm{d}x = 0$. Wenzel's law, derived from this equilibrium condition $\mathrm{d}E/\mathrm{d}x = 0$ together with Eq. (2) (which can be recovered from Eq. (5) for smooth surfaces where, by definition, $r = 1$), then states

$$\cos\theta^* = r\cos\theta\,, \tag{6}$$

wherein θ is the contact angle for smooth surfaces given by Young's equation (Eq. (2)). Since $r > 1$ for rough surfaces, $|\cos\theta^*| > |\cos\theta|$, implying that surface heterogeneities always act to amplify the inherent properties of a surface. In other words, a hydrophilic surface ($\theta < 90°$) will be rendered more hydrophilic ($\theta^* < \theta$) and a hydrophobic surface ($\theta > 90°$) will be rendered more hydrophobic ($\theta^* > \theta$) in the presence of surface roughness.

A similar analysis can be carried out for physically smooth but chemically inhomogeneous surfaces, as depicted in Fig. 9(b), where we allow the surface to comprise of two different materials, each of which is associated with a corresponding contact angle, θ_1 and θ_2. Denoting the fractions along the surface which is composed by each material as f_1 and f_2 (such that $f_1 + f_2 = 1$), assuming f_1 and f_2 are small compared to the area occupied by the entire drop, Eq. (5) now becomes

$$\begin{aligned}\mathrm{d}E &= f_1\,(\gamma_{\mathrm{SL}} - \gamma_{\mathrm{SV}})_1\,\mathrm{d}x + f_2\,(\gamma_{\mathrm{SL}} - \gamma_{\mathrm{SV}})\,2\mathrm{d}x\\ &\quad + \gamma_{\mathrm{LV}}\cos\theta^*\mathrm{d}x\,. \end{aligned} \tag{7}$$

Energy minimization then requires

$$\cos\theta^* = f_1\cos\theta_1 + f_2\cos\theta_2\,, \tag{8}$$

which is known as the Cassie–Baxter law. In this case, the apparent contact angle due to the chemical inhomogeneous surface is the average of the cosines of the contact angles associated with each chemical that the surface is comprised of, and is hence bounded by the two extremes of these contact angles.

Capillarity

The equilibrium drop shape is related to the surface tension of the drop through its curvature. In other words, the tendency for the drop to assume a curved interfacial shape is due to its surface tension. A consequence of this is the existence of a pressure difference across the interface

$$\Delta p = \gamma_{\mathrm{LV}}\kappa\,, \tag{9}$$

with the highest pressure residing on the concave side.

$$\kappa = \frac{1}{R_1} + \frac{1}{R_2}\,, \tag{10}$$

is twice the mean curvature wherein R_1 and R_2 are known as the principal radii of curvature, which is the radii of curvature of the interface along any two orthogonal elements. Equation (9) is known as the *Laplace–Young equation*. For a spherical drop or bubble, $R_1 = R_2 = R$ and hence

$$\Delta p = p_{\mathrm{i}} - p_{\mathrm{e}} = \frac{2\gamma_{\mathrm{LV}}}{R}\,, \tag{11}$$

where p_{i} and p_{e} are the pressures inside and outside the drop or bubble, respectively.

Capillarity is the phenomena that arises due to the existence of a finite (or even zero) contact angle that a liquid makes with the solid substrate. One example is the height-of-rise of a liquid in an open capillary tube, as shown in Fig. 10. The associated liquid motion due to surface tension is known as *capillary flow*. Assuming the meniscus to be approximately hemispherical with constant radius of curvature $R_1 = R_2 = R/\cos\theta$, where $2R$ is the capillary diameter, the pressure variation across the interface from Eq. (11) is then

$$\Delta p = p_{\mathrm{atm}} - p_{\mathrm{liq}} = \frac{2\gamma_{\mathrm{LV}}\cos\theta}{R}\,, \tag{12}$$

where p_{atm} and p_{liq} are the atmospheric and liquid pressures, respectively. Given that at equilibrium, the hydrostatic head of the liquid capillary $p_{\mathrm{liq}} + \rho g H$, where ρ is the liquid density, g the gravitational acceleration and H the equilibrium height of the liquid capillary column, must balance the atmospheric pressure, i. e.,

$$p_{\mathrm{liq}} + \rho g H = p_{\mathrm{atm}}\,, \tag{13}$$

H can then be obtained by substituting Eq. (12):

$$H = \frac{2\gamma_{\mathrm{LV}}\cos\theta}{\rho g R}\,. \tag{14}$$

Equation (14) therefore represents an equilibrium dominant balance between the gravitational and surface tension forces. Thus, given that ρ and $\cos\theta$ are known for a given fluid, the capillary rise can be determined. It is also evident from Eq. (14) that the capillary rise is dependent on the capillary radius. For small capillaries, H can therefore become relatively large. This capillary rise method is therefore very useful and accurate for measuring the surface tension of liquids.

Key Research Findings

Spreading Dynamics

We briefly consider the spreading dynamics of a drop, sufficiently small such that the spreading is not influenced by gravity. We will also assume the substrate to be smooth and homogeneous since surface roughness effects can enhance spreading and even lead to the spontaneous wetting of partially wetting liquids. The interface is also assumed to be



Wetting and Spreading, Figure 9 Contact line region of a drop on a (**a**) physically rough but chemically homogeneous surface, and, (**b**) a physically smooth but chemically inhomogeneous surface consisting of two different surface materials. A small displacement to the contact line $\mathrm{d}x$ is considered in the derivation of Wenzel's law in the case of (**a**) and the Cassie–Baxter law in the case of (**b**)



Wetting and Spreading, Figure 10 Schematic depiction of a capillary height-of-rise experiment

clean such that no surface tension gradients are imposed, which could lead to Marangoni stresses; such effects will be discussed subsequently. The experimentally observed spreading data for complete wetting then appears to follow a simple power law relationship given by

$$R(t) \sim t^n , \tag{15}$$

where R is the radius of the spreading drop and t denotes time. n has been empirically found to lie between 0.1 and 0.14; it's value has been reported to be dependent on the drop volume, temperature and physical properties as well as the humidity of the ambient phase.

There is also a very specific scaling for the macroscopic dynamic contact angle θ. This was first observed by Hoffman [5], who investigated the variation in the contact angle of an advancing meniscus front in a capillary tube subject to different fluid driving velocities, as well as Tanner [6], who observed similar behavior for drops spreading on a horizontal substrate. In both cases, it was observed that for small Ca,

$$\theta \sim \mathrm{Ca}^{\frac{1}{3}} , \tag{16}$$

where

$$\mathrm{Ca} \equiv \frac{\mu U}{\gamma} , \tag{17}$$

is the capillary number with $U(t) = \mathrm{d}R(t)/\mathrm{d}t$ being the speed of the contact line in the above, μ is the viscosity. The universal law given by Eq. (16) has since been corroborated by many investigators.

Kalliadasis and Chang [7] considered the behavior of the asymptotic region between the bulk macroscopic drop and a thin film ahead of the drop in which liquid from the perfectly wetting drop drains into due to the negative disjoining and capillary pressures, as shown in Fig. 11. This thin film, known as the precursor film, has both been observed experimentally [8] and is also used as a convenient means of removing mathematical difficulties near the contact line region where continuum theory breaks down; a discussion of this will be carried out below. In this asymptotic region between the bulk drop, of characteristic length scale L, and the precursor film region, of characteristic length scale $\hat{L}$, viscous and capillary forces dominate.

Thus, assuming the film in this region to be thin such that the lubrication approximation holds, the spreading dynamics of the drop in the limit $\hat{L}/L \ll 1$ and the local quasi-steady limit with respect to a moving coordinate frame translating at a constant dimensionless speed given by Ca, is governed by the Bretherton [9] equation:

$$3\,\mathrm{Ca}\frac{\partial h}{\partial x} = \frac{\partial}{\partial x}\left(h^3\frac{\partial^3 h}{\partial x^3}\right) , \tag{18}$$

where h is the dimensionless film height, scaled by the characteristic height of the macroscopic drop H. In the



Wetting and Spreading, Figure 11 Contact line region of a spreading drop ahead of which a thin front running precursor film exists. The intermediate asymptotic region where viscous and capillary forces dominate is shown. After Kalliadasis and Chang [7]

above, the axial and vertical coordinates, x and z are scaled by L and H, respectively. Kalliadasis and Chang [7] then showed that the film height, upon redimensionalization, assumes the following weak logarithmic behavior as it asymptotes away from the contact line:

$$h \sim -x\,\mathrm{Ca}^{\frac{1}{3}}\left(9\log\frac{\hat{L}}{L}\right)^{\frac{1}{3}} . \tag{19}$$

A dynamic contact angle condition can then be written for the macroscopic spreading drop:

$$\tan\theta \sim -\frac{\partial h}{\partial x} \sim \left(-9\log\frac{\hat{L}}{L}\right)^{\frac{1}{3}}\mathrm{Ca}^{\frac{1}{3}} , \tag{20}$$

showing that the local quasi-steady spreading of a partially or completely wetting liquid drop at constant speed Ca driven by viscous and capillary forces always gives rise to an interfacial shape that scales consistently with the universal law given in Eq. (16). Equation (20) suggests that away from the static equilibrium limit, a partially wetting drop behaves, albeit quite surprisingly, like a complete wetting drop, consistent with the experimental findings for sufficiently large Ca [7].

It is now possible to insert this dynamic contact angle condition back into the spreading relationship in Eq. (15) to obtain an explicit power law for the spreading dynamics of a drop lying on a horizontal substrate [7]. If the drop can be assumed to be thin, then the axisymmetric Laplace–Young equation in the lubrication limit reads

$$\frac{\partial}{\partial r}\left[\frac{1}{r}\frac{\partial}{\partial r}\left(r\frac{\partial h}{\partial r}\right)\right] = 0 . \tag{21}$$

The following boundary conditions apply

$$\frac{\partial h}{\partial r}(r=0) = 0 , \quad h\,(r=R) = 0 , \quad \text{and,}$$
$$\frac{\partial h}{\partial r}(r=R) = -\tan\theta . \tag{22}$$

In addition, we impose conservation of the drop volume V:

$$\int_0^R hr\,\mathrm{d}r = \frac{V}{2\pi} . \tag{23}$$

Integrating Eq. (21) twice subject to the boundary conditions above then yields

$$h\,(r) = \frac{2V}{\pi R^2}\left[1-\left(\frac{r}{R}\right)^2\right] . \tag{24}$$

Substitution of the dynamic contact angle condition in Eq. (20) then gives

$$\frac{\partial h}{\partial r}(r=R) = -\frac{4V}{\pi R^3} = \left(9\log\frac{\hat{L}}{L}\right)^{\frac{1}{3}}\mathrm{Ca}^{\frac{1}{3}} . \tag{25}$$

Since the dimensionless advancing speed of the contact line can be written as $\mathrm{d}R/\mathrm{d}t = 3\,\mathrm{Ca}$, where time is scaled



Wetting and Spreading, Figure 12 Collapse of the poly(dimethylsiloxane) drop spreading data of Ausserré et al. [8] with the dimensional form of the universal law given by integration of Eq. (26), which is denoted by *D*. Reproduced with permission from [8]

by $\mu L/\gamma$ and the radius by $V^{1/3}$, it then follows that

$$\frac{\partial R}{\partial t} = -\frac{512V}{3\log\left(\hat{L}/L\right)R^9}\,, \tag{26}$$

and hence

$$R \sim t^{\frac{1}{10}}\,, \tag{27}$$

consistent with the dynamic spreading law of Eq. (15). The collapse of the experimental data of [8] for the spreading of poly(dimethylsiloxane) drops of various volumes on a silicon substrate is shown in Fig. 12 [7]. On the other hand, for large drops where gravity would play an influence, the drop radius would spread as $R \sim t^{1/8}$ instead.

Stress Singularity

In addition to the challenges in the treatment of free surfaces, dynamic spreading models encounter a significant conceptual difficulty due to the breakdown of continuum hydrodynamics at the contact line when the sharp continuum interface is extrapolated to molecular scales to define the contact angle. At these microscopic scales, such geometric conceptualizations such as an interface and the contact angle becomes ambiguous. Moreover, the enforcement of the slip-free and tangential stress continuity on the smooth solid substrate at the three-phase contact line gives rise to a stress singularity [4]. In other words, a logarithmically infinite force is required to advance the contact line, which is not observed experimentally [10]. This locally unbounded force is not the result of a kinematic incompatibility between the no-slip condition on the substrate and the existence of an advancing drop interface that is impenetrable by both sides of the fluid [11]. Instead, Dussan and Davis [11] suggest that the stress singularity is a dynamic consequence of the multi-valued velocity field at the contact line.

Various models have been proposed to overcome this difficulty. Early models allowed the continuum theory to define the contact angle up to a molecular cut-off. One approach is to allow for a finite slip velocity such that the stress singularity, whilst not removed altogether, becomes a logarithmic singularity that is at least integrable [12, 13]. Another approach that we have discussed above is to assume that a thin precursor film precoats the substrate [14]. Alternatively, given that wetting is driven by molecular forces at the inner region of the contact line, the disjoining pressure arising from long-range intermolecular interactions can be introduced to account for a negative pressure that sucks liquid from the bulk into the precursor film.

Nevertheless, it has been shown that the same asymptotic behavior of the inner region away from the contact line given by the universal solution of Eq. (19) is recovered regardless of which model above is adopted to remove the contact line stress singularity in both partially or completely wetting fluids [15]. In fact, the dimensionless length scale $\hat{L}/L$ can be shown to be equal to the precursor film thickness b, i. e.,

$$\frac{\hat{L}}{L} \sim \frac{b}{H}\,, \tag{28}$$

if the precursor film is adopted, the Hamaker constant α, i. e.,

$$\frac{\hat{L}}{L} \sim \frac{1}{L}\left(\frac{|\alpha|}{6\pi\gamma}\right)^{\frac{1}{2}}\,, \tag{29}$$

if the disjoining pressure is used, and, the slip coefficient $\lambda_{\mathrm{i}} = \lambda h^i$, i. e.,

$$\frac{\hat{L}}{L} \sim \lambda_i^{\frac{1}{(1+i)}}\,, \tag{30}$$

if a slip model is employed; λ is the film thickness dependent slip length, the dependence of which is given by the exponent i $(=0, 1)$ and corresponds to the different slip models historically used [16].

To leading order, the intermolecular forces are shown to be solely determined by the apparent dynamic contact angle and independent of slip. The precursor film is also shown to be reasonable approximation to account for intermolecular effects although both the precursor film and slip



Wetting and Spreading, Figure 13 Schematic depiction of a bubble translating within a long capillary tube

models, while mathematically convenient for handling the problem of stress singularity, do not appear to contribute to the dynamic contact angle condition. In any case, imposing one or the other does not lead to significant error due to the weak dependence of the coefficient $-9\log(\hat{L}/L)$ on the asymptotic behavior of the bulk drop region [15].

Capillary Driven Spreading

We have already observed an example of capillary-driven spreading in the capillary rise experiment described above. Another example of capillarity is that of bubble transport in capillary tubes [9]. Scaling arguments for this problem, illustrated in Fig. 13, are discussed by Chang [17]. To leading order, the pressure drop at the front and rear spherical caps are given by Eq. (11) and thus the axial curvature is $1/R$, where R is the radius of curvature of the bubble cap. In the short intermediate transition region of length L_0 between the spherical cap and annular film regions, the azimuthal curvature gradient, which scales as H_0/R^2L_0 given that the azimuthal curvature is $1/(R-h)$, is negligible compared to the axial curvature gradient, which scales as H_0/L_0^3 since the axial curvature is $\mathrm{d}^2h/\mathrm{d}x^2$ (that $L_0 \ll R$ will be explicitly shown below in Eq. (33)); h is the liquid film thickness with a characteristic length scale in the transition region of H_0 and x is the axial coordinate. Asymptotic matching between the transition and cap regions then gives rise to a balance between the axial and azimuthal curvatures:

$$\frac{H_0}{L_0^2} \sim \frac{1}{R}\,. \tag{31}$$

A balance between viscous and capillary forces requires

$$\frac{\mu U}{H_0^2} \sim \frac{\mathrm{d}p}{\mathrm{d}x} \sim \frac{\gamma}{RL_0}\,, \tag{32}$$

where U is the speed of the bubble. It then follows from Eqs. (31) and (32), with the dimensionless speed Ca defined by Eq. (17), that

$$H_0 \sim R\,\mathrm{Ca}^{\frac{2}{3}}\,,\ \text{and}\,,\quad L_0 \sim R\,\mathrm{Ca}^{\frac{1}{3}}\,, \tag{33}$$

as long as $\mathrm{Ca} \ll 1$.

To render the problem quasi-steady, a moving coordinate frame is adopted such that the bubble translates at speed Ca. In the thin annular film region, application of the lubrication approximation to a balance between viscous and capillary forces then yields the following dimensionless equation for the film thickness h [17]:

$$h^3\frac{\mathrm{d}^3h}{\mathrm{d}x^3} = h - 1\,, \tag{34}$$

where h is scaled by the characteristic height of the film H_0 and x by $H_0(3\,\mathrm{Ca})^{-1/3}$. Equation (29) describes the asymptotic behavior in the transition regions for both the front spherical cap as $x \to \infty$ and the rear spherical cap as $x \to -\infty$. Since a quadratically increasing film height is expected, we allow

$$h = A^{\pm}x^2 + B^{\pm}x + C^{\pm}\,, \tag{35}$$

where A, B and C are constants in which the + subscript denotes that pertaining to the front cap and the − subscript pertains to the rear cap. These can be obtained by numerical integration of Eq. (34) starting from the flat film where $\mathrm{d}h/\mathrm{d}x = \mathrm{d}^2h/\mathrm{d}x^2 = 0$, noting that B can be set to zero by arbitrarily shifting the origin. It is then possible to match the curvature $\mathrm{d}^2h/\mathrm{d}x^2$ of the asymptotic solution in Eq. (35) to the outer spherical cap solutions, which to leading order, are static solutions of the Laplace–Young equation. Chang [17] showed that this leads to

$$\frac{H_0}{R} = 0.643\,(3\,\mathrm{Ca})^{\frac{2}{3}}\ , \tag{36}$$

which is an estimate of the film thickness to leading order. Similar scalings can also be observed in coating flows wherein solid substrates are coated with a thin and uniform liquid film.

Marangoni and Thermocapillary Driven Spreading

In our discussion above, we had assumed that the interface is clean and isothermal. However, surface impurities and non-uniform temperatures can alter the local surface tension, thus giving rise to surface tension gradients that generate additional interfacial stresses, the so-called Marangoni stresses [18]. Marangoni stresses can, in turn, alter the macroscopic spreading behavior significantly and introduce instabilities at the spreading front. Troian et al. [14] have shown that a capillary ridge appears at the advancing front which is the target of viscous instabilities that lead to a fingering phenomenon. Away from the spreading front, instabilities arising from surfactant concentration or thermal non-uniformities can also give rise to dewetting and hence the formation of dry-spots upon rupture of the liquid film [19, 20].

Future Directions for Research

Despite considerable advances in the investigations carried out on wetting and spreading phenomena over several decades, a complete fundamental understanding is still elusive, particularly at the contact line where significant conceptual and mathematical difficulties arise. Although it has been seen above that the weak logarithmic asymptotic behavior in the contact line region suggests that an intimate knowledge of the microscopic conditions is not required to accurately model the macroscopic spreading behavior, the local microscopic wetting behavior may still be important in many physical systems, and particularly so where nanochannel wetting and transport at molecular scales, are concerned. As such, there is a further need to verify and successively refine our current understanding concerning microscopic wetting dynamics.

This is now possible due to advances in computer processing, which has previously limited the scope of molecular dynamics (MD) simulations in microscopically modeling local dynamic wetting behavior. By integrating the laws of motion governing individual molecular particles and taking into account intermolecular interactions, it is possible to resolve the velocity fields which then provide a mechanism for slippage of liquid molecules over the solid. In addition, dynamic contact angle conditions can be inferred and appear to be dependent on the interaction potentials between the liquid and solid molecules. Nevertheless, MD simulations are still confined to small length scales and continue to be limited to short times. As such, it is envisaged that multi-scale spatial and time averaging techniques will allow a unified coupling between continuum and molecular theories to provide a more complete description for modeling wetting behavior. A description of such multiscale models is given in Karniadakis et al. [21]. MD simulations involving equilibrium statistical mechanics or weak deviations from equilibrium (for example, by means of density-functional theories), can therefore replace the disjoining pressure in molecular theories to explicitly account for intermolecular interactions in an intermediary step in asymptotic matching with continuum hydrodynamic models in the long scale limit.

Cross References

- ► Applications Based on Electrowetting
- ► Bubble Dynamics in Microchannel
- ► Capillary Filling
- ► Digital Microfluidics
- ► Droplet and Bubble Formation in Microchannels
- ► Droplet Based Lab-on-a-Chip Devices
- ► Droplet Dispensing
- ► Droplet Dynamics in Microchannel
- ► Electrocapillary
- ► Electrowetting
- ► Electrowetting and Droplets
- ► Interfacial Electrokinetic Flow
- ► Surface Tension Driven Flow
- ► Surface Tension, Capillarity and Contact Angle
- ► Thermal Capillary
- ► Thermocapillary Pumping

References

1. Dupuis A, Yeomans JM (2006) Dynamics of sliding drops on superhydrophobic surfaces. Europhys Lett 75:105–111
2. de Gennes PG (1985) Wetting: statics and dynamics. Rev Modern Phys 57:827–863
3. Nadkarni GD, Garoff S (1992) An investigation of microscopic aspects of contact angle hysteresis: Pinning of the contact line on a single defect. Europhys Lett 20:523–528
4. Huh C, Scriven LE (1971) Hydrodynamic model of steady movement of a solid/liquid/fluid contact line. J Colloid Interface Sci 35:85–101
5. Hoffman RL (1975) A study of the advancing interface. I. Interface shape in liquid–gas systems. J Colloid Interface Sci 50:228–241

6. Tanner LH (1979) The spreading of silicone oil drops on horizontal surfaces. J Phys D: Appl Phys 12:1473–1484
7. Kalliadasis S, Chang H-C (1996) Dynamics of liquid spreading on solid surfaces. Ind Eng Chemistry Res 35:2860–2874
8. Ausserré D, Picard AM, Léger L (1986) Existence and role of the precursor film in the spreading of polymer liquids. Phys Rev Lett 57:2671–2674
9. Bretherton FP (1961) The motion of long bubbles in tubes. J Fluid Mech 10:166–188
10. Kistler SF (1993) Hydrodynamics of wetting. In: Berg JC (ed) Wettability. Marcel-Dekker, New York
11. Dussan V EB, Davis SH (1974) On the motion of a fluid-fluid interface along a solid surface. J Fluid Mech 65:71–96
12. Hocking LM (1977) A moving fluid interface. Part 2. The removal of the force singularity by a slip flow. J Fluid Mech 79:209–229
13. Dussan V EB (1979) On the spreading of liquids on solid surfaces: Static and dynamic contact lines. Ann Rev Fluid Mech 11:371–400
14. Troian SM, Herbolzheimer E, Safran SA, Joanny JF (1989) Fingering instabilities of driven spreading films. Europhys Lett 10:25–30
15. Yeo LY, Chang H-C (2006) Electrowetting films on parallel line electrodes. Phys Rev E 73:011605
16. Haley PJ, Miksis MJ (1991) The effect of the contact line on droplet spreading. J Fluid Mech 223:57–81
17. Chang H-C (2002) Bubble/Drop transport in microchannels. In: Gad-el Hak M (ed) The MEMS Handbook. CRC Press, Boca Raton
18. Edwards DA, Brenner H, Wasan DT (1991) Interfacial transport processes and rheology. Butterworth-Heinemann, London
19. Warner MRE, Craster RV, Matar OK (2002) Dewetting of ultrathin surfactant-covered films. Phys Fluids 14:4040–4054
20. Yeo LY, Craster RV, Matar OK (2003) Marangoni instability of a thin liquid film resting on a locally heated horizontal wall. Phys Rev E 67:056315
21. Karniadakis G, Beskok A, Aluru N (2005) Microflows and Nanoflows. Springer, New York

Wetting on Structured Substrates

► Surface-Directed Capillary Flow Systems

Wien Filter

► Crossed Field Filter

World-to-Chip Interface

► Transferring Samples to Chips, Techniques

X-Ray Diffraction (XRD)

Definition

Material characterization technique used to determine the crystalline quality, chemical composition, and physical properties of a material. A Cu source is used to generate X-rays, which are then scattered off of a sample and collected by a detector. The full-width at half-maximum (FWHM) value of the scattered X-ray beam can be used as a measure of the materials crystalline perfection.

Cross References

► Fabrication of Self-Assembled Catalytic Nanostructures

Zeta-Potential

Definition

The zeta potential ζ is a measure of the electrical charge developed when a solid surface is brought into contact with an aqueous solution. More specifically, when a solid surface is brought into contact with an aqueous solution an electrical charge is generated at the interface. As a result, local free ions in the solution tend to rearrange themselves such that a thin region of non-zero net charge density exists near the interface. The arrangement of the charges at the solid–liquid interface and the balancing counterions in the liquid is usually referred to as the electrical double layer (EDL). There is a thin layer of counterions immediately next to the charged solid surface, called the compact layer. The counterions in the compact layer are immobile due to the strong electrostatic attraction. Counterions outside the compact layer are mobile. This part of the EDL is called the diffuse layer. The zeta potential is the electrostatic potential at the boundary dividing the compact layer and the diffuse layer.

Cross References

- ► Temperature Effects on the Zeta Potential
- ► Measuring Zeta Potential, Methods

Zeta Potential Measurement

Tom Glawdel, Carolyn Ren
Department of Mechanical
and Mechatronics Engineering, University of Waterloo,
Waterloo, ON, Canada
tglawdel@engmail.uwaterloo.ca

Synonyms

Electrokinetic potential; Surface potential

Definition

►Zeta potential is defined as the electrical potential at the shear plane of the electric double layer. Measurement techniques are based on indirect readings obtained during electrokinetic experiments. Typically, the magnitude of the zeta potential varies between $0 - 200$ mV where both negative and positive values are possible depending on the electrochemistry of the solid-liquid interface.

Overview

►Zeta potential refers to the electrokinetic potential at the shear surface of the electric double layer. Along with surface conductance, zeta potential is an important parameter in the study and modeling of a variety of electrokinetic phenomena relevant to microfluidics and Lab-on-a-Chip devices. The zeta potential of a solid-liquid interface depends on a number of factors including the ion concentration, ion valence, pH level and temperature of the solution. For this reason each solid-liquid interface has its own unique zeta potential that must be measured. Zeta potential measurements are based on indirect readings using one of the following electrokinetic phenomena: electro-osmotic flow, electrophoresis and streaming potential. In terms of microfluidics, electro-osmotic and streaming potential techniques are used in the study of microchannels and capillaries while electrophoresis based methods are used to study charged particles such as fluorescent beads, DNA and proteins.

This document is organized in the following manner: first, a brief introduction to the electric double layer and its significance to electrokinetic phenomenon. Second, the principles behind zeta potential measurements based on the three types of electrokinetic phenomenon are discussed, with special attention to the advantages and disadvantages of each method. Finally, a few key research results for each of the methods are presented. The purpose of this entry is to provide the reader with a brief introduction to the fundamentals of zeta potential measurements, for a more detailed description of zeta potential measurements, electric double layer and electrokinetic phenomenon the reader should consult the various texts that discuss these topics in depth [1–4].

Basic Methodology

Electric Double Layer and Zeta Potential

In most cases, when a solid surface comes in contact with an aqueous solution an electric charge develops at the interface. The surface charge influences the nearby ions creating a non-uniform electric charge distribution near the interface known as the electric double layer (EDL) [1–4]. Several mechanisms cause this effect including ionization, ion adsorption and ion dissolution.

The earliest theoretical study on the structure of the EDL was performed by Helmholtz (1879) who proposed that the charged interface is surrounded by two condensed planes of oppositely charged ions. In actual fact, thermal forces tend to spread out the ions creating a diffuse region around the interface. Gouy (1910) and Chapman (1913) independently tackled this problem by applying the kinetic molecular theory to the diffuse region of ions. In their model, the electric potential and charge distributions are described using the well-known Poisson–Boltzman equation of statistical physics. Although the model is based on statistical grounds, it produces accurate results when the surface potential is low or the electrolyte concentration is not too high. The major defect of the Gouy–Chapman model is that the ions are treated as point charges; however, in reality ions have a finite size that limits the distance they can approach a surface. Stern (1924) resolved this issue and proposed a new model that divides the EDL into an inner compact layer and an outer diffuse layer. Inside the compact layer the size of the ions is considered while in the diffuse layer the Gouy–Chapman model is still applied.

As shown in Fig. 1, the Stern layer is approximately one ion radius thick and is defined by the solid surface and the Stern plane. Counterions in the Stern layer experience strong electrostatic forces and are essentially immobilized against the surface. Ions located outside the Stern plane experience a weaker electrostatic attraction and form the mobile diffuse layer of the EDL. The boundary separating these two regions is defined as the shear plane. In the diffuse layer, competing electrostatic and thermal forces creates a non-zero concentration of ions that is a maximum at the surface and decreases gradually with distance until it reaches equilibrium with the bulk concentration. The thickness of the diffuse layer is often characterized by the Debye length λ_d which can vary from several nanometers to micrometers depending on the concentration and properties of the solution.



Zeta Potential Measurement, Figure 1 Schematic representation of the electric double layer using Gouy–Chapman–Stern model [3]

The double layer acts to neutralize the surface charge creating an electrokinetic potential distribution between the interface and the solution. This voltage difference is on the order of millivolts and is refereed to as the surface potential ψ_S. Through the Stern layer the electric potential varies almost linearly to the Stern plane potential ψ_d and then decreases gradually in the diffuse layer until it reaches zero far away from the surface. The electric potential at the shear plane is known as the electrokinetic potential or zeta potential (ζ). Because the zeta potential is located at the fluid flow boundary it is an important parameter for analyzing a variety of electrokinetic phenomenon.

It should be noted that the surface potential and the zeta potential do not always have the same sign [3]. If adsorbed polyvalent or surface active counterions are present the zeta potential may decrease or increase substantially. Thus the zeta potential measurements can not always be extrapolated to determine the surface potential.

In the EDL, the electric potential and net charge density are described by the Poisson–Boltzman equation [1–4].

The Poisson equation describes the electric field within a dielectric medium:

$$\nabla \cdot (\nabla \psi) = \frac{-\rho_\mathrm{e}}{\varepsilon_\mathrm{r}\varepsilon_0} \tag{1}$$

where ε_0 and ε_r are the dielectric permittivity of a vacuum ($\varepsilon_0 = 8.854 \times 10^{-12}\ \mathrm{C/Vm}$) and the relative dielectric permittivity of the solution. The net charge density, ρ_e, is the sum of negative and positive ions ($\rho_\mathrm{e} = \sum_i z_i e n_i$). Assuming that the Boltzmann distribution is valid, the ionic concentration in the EDL is given by:

$$n_i = n_0 \exp\left(\frac{-z_i e \psi}{k_\mathrm{b} T}\right) \tag{2}$$

where n_i is the specific number of the ith ion, n_0 is the number of ions in the bulk solution, z is the valence of the ion, e is the charge of an electron, k_b is Boltzmann's constant and T is the absolute temperature. Combining Eqs. (1, 2) leads to the Poisson–Boltzman equation:

$$\nabla \cdot (\nabla \psi) = \frac{-\sum_i^N z_i e n_0 \exp\left(\frac{-z_i e \psi}{k_\mathrm{b} T}\right)}{\varepsilon_\mathrm{r}\varepsilon_0} \tag{3}$$

For the special case of a symmetric electrolyte solution ($z : z = 1 : 1$) the Poisson–Boltzman equation reduces to:

$$\nabla \cdot (\nabla \psi) = \frac{2 n_0 z e}{\varepsilon_\mathrm{r}\varepsilon_0} \sinh\left(\frac{z e \psi}{k_\mathrm{b} T}\right) \tag{4}$$

Applying the non-dimensionalized parameters ($\Psi = ze\psi/kT,\ X = x/L$) to Eq. (4), yields

$$\nabla \cdot (\nabla \Psi) = \kappa^2 L^2 \sinh(\Psi) \tag{5}$$

where κ is the Debye–Hückel parameter and is given by $\kappa = (2z^2 e^2 n_0/\varepsilon_\mathrm{r}\varepsilon_0 k_\mathrm{b} T)^{1/2}$. As stated previously, the EDL thickness is characterized by the Debye length ($\lambda_\mathrm{d} = 1/\kappa$). For most microfluidic applications involving microchannels the appropriate boundary conditions for solving Eq. (4) are $\psi = \zeta$ at the shear plane and the assumption that $\psi \to 0$ as $x \to \infty$. However, this is not the case for nanochannels where over-lapping boundary layers invalidate the assumption of uniform bulk properties far from the wall. Numerical techniques are usually employed to calculate the electric potential and charge distribution from Eq. (3). Analytical solutions are possible for a few cases where simplified assumptions are justified.

Electrokinetic phenomena arise when the mobile layer of the EDL interacts with an externally applied electric field resulting in relative motion between the solid and liquid phases. There are three types of electrokinetic phenomena relevant to microfluidics: electro-osmotic flow, streaming potential and electrophoresis. In all of these cases, the zeta potential is a key parameter that defines either the fluid flow or particle motion. Since it is not possible to probe the zeta potential directly, measurements are based on indirect readings obtained from electrokinetic experiments. The following discussion focuses on modern methods of measuring the zeta potential using electro-osmotic flow, electrophoresis and streaming potential.

Electro-Osmotic Flow

When an electric field is applied tangentially to the EDL, the mobile ions in the diffuse layer begin to migrate towards the appropriate electrode. Through viscous drag, the motion of the ions causes the surrounding liquid to move generating electro-osmotic flow. The movement also generates an electric current. Since the applied electric field is tangential to the surface, the resulting ion migration does not affect the charge density in the EDL. Thus the body force ($\boldsymbol{F}_\mathrm{b} = \rho_\mathrm{e}\boldsymbol{E}$) experienced by the fluid is limited to the diffuse layer. Note that it is the external field, $\boldsymbol{E}$, that drives the fluid and not the internal field within the EDL. The resulting velocity profile is *plug* like, where the velocity is zero at the wall (no-slip condition) and rises to a uniform velocity in the bulk. Since the EDL thickness is very small (~ 30 nm) compared to microchannel (~ 50 μm), to an observer it appears as if the fluid *slips* by the surface. The velocity at the edge of the EDL is given by the classic Helmholtz-Smoluchowski equation:

$$u_\mathrm{HS} = -\frac{\varepsilon_0\varepsilon_\mathrm{r}\zeta E_x}{\eta} \tag{6}$$

where E_x is the tangential electric field and ζ is the zeta potential. Usually the group of terms, $\varepsilon_0\varepsilon_\mathrm{r}\zeta/\eta$, are combined together into a proportionality constant called the electro-osmotic mobility (μ_eo) of the solid-liquid interface. Since the velocity only varies in the EDL, the total flow rate is approximated by $Q = u_\mathrm{HS} A_\mathrm{c}$, where A_c is the cross-sectional area of the microchannel. Thus it is possible to determine the zeta potential by measuring the fluid velocity or volume flow rate under electro-osmotic flow.

Volume Method

One of the earliest methods for determining the zeta potential was to measure the volumetric flow rate of a liquid transported in a capillary under electro-osmotic flow. This method seems simple in principal; however, the small flow rates typical of electro-osmotic flow (~ nl/min) make it difficult to obtain accurate measurements. Normally the flow rate is determined by following the progression of a meniscus or bubble in an adjoining capillary which in it self produces a variety of errors [2].

Direct Visualization Methods

Several variations of micro flow visualization have been developed for microfluidic applications such as particle-based flow velocimetry and scalar-based flow velocimetry [5]. In terms of the zeta potential measurement, these visualization techniques such as micro-PIV are used to measure the velocity profile and flow rate under electro-osmotic flow. Once the velocity is known the zeta potential can be calculated from Eq. (6). The main advantage of using a flow visualization technique is that the electro-osmotic velocity can be measured directly and in real time. In general, the small amount of particles or dye used has a negligible effect on the electro-osmotic flow being measured. The only significant disadvantage of this technique is that the extent and cost of the hardware may be prohibitive.

Current-Monitoring Methods

Recently a method has been developed to determine the average flow velocity by measuring the electric current in a microchannel under electro-osmotic flow [6, 7]. The experimental set up is shown in Fig. 2, and consists of a microchannel, a high voltage power supply and a data acquisition system. The microchannel and reservoir 2 are initially filled with an electrolyte solution that has a slightly different concentration than reservoir 1 ($c_1 - c_2 = 5\%$). The concentration difference must be small so that the zeta potential and ionic concentrations are nearly uniform throughout the microchannel.

Immediately after the two solutions are in contact, the high voltage power supply is turned on to induce electro-osmotic flow. As the fluid in reservoir 1 displaces the existing fluid in the microchannel the electric current draw changes. Initially the current is constant and then changes linearly until it reaches another plateau once the initial fluid is completely replaced. The time required for the displacement represents the time required for the solution to travel through the channel length, which can be used to determine the average electro-osmotic velocity:

$$u_{\text{ave}} = \frac{L}{\Delta t} \tag{7}$$

where L is the length of the channel and the zeta potential can be calculated from Eq. (6). The major problem associated with this method is the ambiguity surrounding the displacement time. Small current fluctuations and gradual transitions at the beginning and end of the displacement process may cause errors in measuring Δt.



Zeta Potential Measurement, Figure 2 Schematic of the experimental setup for the current-monitoring technique (*a*) and a typical current time plot (*b*) [7]

To solve this problem, an improved method was developed to determine the zeta potential by using the slope of the current-time relationship [7]. The slope of the current-time relationship is given as:

$$\text{slope} = \frac{\Delta I}{\Delta t} \tag{8}$$

Under electro-osmotic flow the current in the channel is composed of three parts: 1. the bulk conductivity current, $I_{\text{cond,bulk}}$, the surface conduction current, $I_{\text{cond,surf}}$, and the convection current created by the fluid motion, $I_{\text{cond,conv}}$. Typically, the convection current is several orders of magnitude smaller than the other currents and is neglected. Therefore, the total current is given as:

$$I_{\text{total}} = I_{\text{cond,bulk}} + I_{\text{cond,surf}} = \lambda_b A_c E_x + \lambda_s P_w E_x \tag{9}$$

where λ_b is the bulk conductivity of the fluid, λ_s is the surface conductivity, A_c is the cross-sectional area of the channel, P_w is the wetted perimeter and E_x is the applied electric field. Substituting Eq. (9) and assuming that $\Delta\lambda_s = 0$, Eq. (8) reduces to:

$$\text{slope} = u_{\text{ave}} \frac{E_x A_c (\lambda_{b2} - \lambda_{b1})}{L} \tag{10}$$

The above expression can then be rearranged to solve for u_{ave} and then substituted into Eq. (6) to calculate the zeta potential. In addition, the surface conductivity can be measured using this method. In this case, the reservoirs are filled with the same fluid and the total current is measured. The surface conductivity is calculated from Eq. (9) assuming that the bulk conductivity is already known.

The disadvantages of the current monitoring technique are that

- the electro-osmotic flow is measured indirectly through the current draw,
- the method assumes constant zeta potential between the two fluids,
- the difference in conductivity must be large enough so that the current change is measurable, and
- there is a lack of spatial and temporal resolution since the zeta potential represents an average value.

The advantage of using this method is in its simplicity, current-time measurements can be performed quickly and with relatively little infrastructure compared to other methods.

It should be noted that there are several additional sources of error for electro-osmotic based measurements. Joule heating must be controlled or temperature fluctuations may cause significant changes in zeta potential, viscosity and other fluid properties. Another source for error is undesired pressure driven flow caused by small head and meniscus (Laplace pressure) differences at the reservoirs. In fact, even modest differences (~ 5 mm of head) can lead to pressure driven flow rates comparable to the electro-osmotic flow being studied. Also electrolysis occurring at the electrodes may create a pH gradient along the channel creating significant errors in the zeta potential measurement. On the other hand, electro-osmotic flow and electro-osmotic pumping are common methods of transporting fluids in microfluidic devices. Therefore, zeta potential measurements based on electro-osmotic flow provide the most accurate representation of on-chip operating conditions.

Electrophoresis

Electrophoresis refers to the movement of a charged surface relative to a stationary liquid. For instances, under an applied electric field a negatively charged particle will migrate towards the positive electrode (anode).


$\upsilon_E - \upsilon_{EO}$
Observed particle velocity (υ_{obs})
υ_E
Velocity
υ_{EO}
Liquid velocity (υ_L)
0
υ_{EO}
$\upsilon_E > |\upsilon_{EO}|$

Zeta Potential Measurement, Figure 3 Stationary level, fluid velocity and particle velocity distribution in an electrophoresis cell [1]

For spherical particles the velocity is given as [1]:

$$u_E = \mu_{ep} \boldsymbol{E} \tag{11}$$

where μ_{ep} is called the electrophoretic mobility of the particle. The electrophoretic mobility is related to the zeta potential through:

$$\mu_{ep} = \frac{2\varepsilon_0 \varepsilon_r \zeta}{3\eta} f_1(\kappa a) \tag{12}$$

where a is the radius of the particle, η is the viscosity of the liquid, κ is the Debye–Hückel parameter and $f_1(\kappa a)$ is a correcting function that depends on the shape of the particle. Therefore the zeta potential can be calculated from Eq. (12) if the electrophoretic mobility is known.

The most popular method of measuring electrophoretic mobility is micro-electrophoresis. In micro-electrophoresis, particles are placed in a closed capillary with electrodes at either end. When an electric field is applied the particles migrate towards the electrode and their velocities are measured. Because the capillary walls are charged the applied electric field will also induce an electro-osmotic flow. However, since the capillary is closed a back pressure creates a net zero flow in the tube (see Fig. 3). The particle velocity is a combination of the electrophoretic motion and the fluid flow. To obtain the true electrophoretic mobility the particles must be tracked along the stationary layer where the fluid velocity is zero.

For a circular capillary the liquid velocity across the tube is given by the electro-osmotic flow and the back pressure flow:

$$u = u_{\mathrm{EO}} + u_{\mathrm{BP}} \tag{13}$$

For a pressure driven flow the velocity profile is given by the solution of the Poiseuille equation ($u_{\mathrm{BP}} = -c(a^2 - r^2)$), where c is a constant. The value of c is determined by realizing that the net flow in the capillary is zero, $c = 2u_{\mathrm{EOF}}/a^2$. The velocity profile is then given by:

$$\frac{u}{u_{\mathrm{EOF}}} = 2\frac{r^2}{a^2} - 1 \tag{14}$$

The stationary level is determined by setting u to zero so that $r_{\mathrm{stat}} = a/\sqrt{2}$. The same procedure repeated for a plane cell results in $y_{\mathrm{stat}} = a(1 - 1/\sqrt{2})$. Since the velocity varies significantly across the capillary, locating the stationary level is critical for obtaining accurate results.

Early methods of measuring the particle velocities involved manually tracking them along a reference grid using a microscope. This process was tedious and not very accurate since only a few particles could be tracked at a time. Modern devices use a variety of measurement techniques to increase the accuracy and throughput of the procedure. Current devices use laser Doppler velocimetry (LDV) and phase analysis light scattering (PALS) to measure particle velocity. New developments focus on suppressing electro-osmotic flow through surface modifications of the capillary or by using oscillating electric fields to take advantage of time scale differences between electrophoresis and electro-osmotic flow. It should be noted that electrophoresis is also used as a method of separating charged particles such as proteins and DNA in a variety of biomedical applications. A few examples include gel electrophoresis, isoelectric focusing and capillary zone electrophoresis.

Streaming Potential

If an electrolyte solution is forced through a microchannel under pressure driven flow, charges in the EDL move downstream resulting in an electric current called the streaming current:

$$\boldsymbol{I}_{\mathrm{s}} = \int_{v} \boldsymbol{u}\rho_{\mathrm{e}}\,\mathrm{d}v \tag{15}$$

where $\boldsymbol{I}_{\mathrm{s}}$ is the streaming current, $\boldsymbol{u}$ is the velocity and ρ_{e} is the net charge density. The accumulation of these charges creates a potential difference across the channel known as the streaming potential. This potential, in turn, drives the conduction current in the opposite direction of the streaming current. The conduction current is the sum of the bulk and surface conduction:

$$\boldsymbol{I}_{\mathrm{c}} = A_{\mathrm{c}}\boldsymbol{E}_{\mathrm{s}}\lambda_{\mathrm{b}} + P_{\mathrm{w}}\boldsymbol{E}_{\mathrm{s}}\lambda_{\mathrm{s}} \tag{16}$$

where $\boldsymbol{I}_{\mathrm{c}}$ is the conduction current, A_{c} is the cross-sectional area, $\vec{E}_{\mathrm{s}}$ is the streaming potential electric field, P_{w} is the wetting perimeter, λ_{b} and λ_{s} are the bulk and surface conductivities, respectively. At steady state, $\boldsymbol{I}_{\mathrm{c}} + \boldsymbol{I}_{\mathrm{s}} = 0$ and the general relationship between the streaming potential and *zeta potential* can be derived as:

$$\frac{\boldsymbol{E}_{\mathrm{s}}}{\Delta P} = \frac{\varepsilon_0\varepsilon_{\mathrm{r}}\zeta}{\eta\,(\lambda_{\mathrm{b}} + f\lambda_{\mathrm{s}})} \tag{17}$$

where ΔP is the pressure difference, f is a shape factor for the channel and is given as the ratio of the wetted perimeter to the cross-sectional area ($f = P_{\mathrm{w}}/A_{\mathrm{c}}$). One can see that Eq. (17) provides a basis for calculating the zeta potential and surface conductance if the pressure drop and streaming potential are measured. By rearranging Eq. (17) a more convenient form of the streaming potential equation appears:

$$\frac{\Delta P\varepsilon_0\varepsilon_{\mathrm{r}}}{\eta\boldsymbol{E}_{\mathrm{s}}\lambda_{\mathrm{b}}} = \frac{1}{\zeta} + \left(\frac{2\lambda_{\mathrm{s}}}{\zeta\lambda_{\mathrm{b}}}\right)f \tag{18}$$

For a physical system λ_{s} and ζ should remain constant. Eq. (18) shows that there is a linear relationship between the streaming potential measurement and the form factor as shown in Fig. 4. The zeta potential is calculated from the intercept and the surface conductivity from the slope. Therefore, unless the surface conduction is neglected at least two measurements are required to determine the zeta potential and surface conductivity. For practical purposes multiple streaming potential experiments are performed for different form factors to increase the accuracy of the measurements.

A typical experimental apparatus consists of a capillary connected to a pump through a pipe network and a series of transducers strategically placed to measure the pressure drop, flow rate, streaming potential and conductivity. The piping network is designed so that the flow direction can be reversed in the microchannel. Particular attention is required in the preparation and assembly of the apparatus. The potential must be measured with a high impedance electrometer so that the streaming current and therefore the flow in the microchannel are not disturbed. Also, it is important to use electrodes that respond reversibly to current flows (eg. Ag/AgCl).


$\frac{\varepsilon_r\varepsilon_0\Delta P_z}{\mu E_s\lambda_b}$ $[\frac{1}{V}]$
0
$\frac{1}{\zeta}$
$\frac{1}{\delta}$ $[\frac{1}{m}]$
$\lambda_s=0$
$\tan\alpha = \frac{2\lambda_s}{\zeta\lambda_b}$ $[\frac{m}{V}]$
α
Least-square linear curve fit
$\lambda_s\neq0$

Zeta Potential Measurement, Figure 4 Plot of the relationship between streaming potential, surface conductance and zeta potential used in the streaming potential method [8]

To prevent the electrodes from polarization streaming potential measurements must not exceed 1 – 2 minutes before the flow should be reversed and measurements taken again. By reversing the flow any errors caused by the asymmetry of the electrode system are also reduced. For a given gap height this procedure should be repeated for several different flow rates. Consequently, in order to obtain an accurate streaming potential plot a number of experiments (~ 20) must be performed.

It is important to emphasize the need to measure the surface conductance as well as the zeta potential. If the surface conductance is neglected in Eq. (18) the zeta potential can be severely underestimated. It should also be noted that the equations derived above neglect electrokinetic effects on the flow by assuming a Poiseuille type flow through the microchannel. In actuality the streaming potential creates a reverse electro-osmotic flow in the channel that decreases the overall flow rate. The decreased velocity creates the appearance of an increased fluid viscosity and is known as the electroviscous effect. Generally this effect is prevalent in microchannels less than 50 μm.

Key Research Findings

Sanders et al. applied the micro-electrophoresis technique to measure the zeta potential of finely ground glass slides as a function of pH [9]. The results show that for glass particles suspended in a 0.1 M NaCl the zeta potential varies from −20 mV for a pH of 3 to −75 mV for a pH of 10 demonstrating the importance of pH on zeta potential. One problem that arises with this method is whether the zeta potential measured using finely crushed particles corresponds to the zeta potential of the uncrushed solid-liquid interface. The act of grinding may alter the zeta potential of the original material and is still a topic of debate.

Oddy and Santiago used micro-PIV techniques to study small particles in AC and DC electro-osmotic flow [10]. Independent measurements of the particle motion in the two fields can be correlated to determine the electrophoretic mobility of the particle and electro-osmotic mobility of the solid-liquid interface. The electrophoretic mobility of the fluorescent polystyrene particles was found to be −3.76 ± 0.05 μm cm/Vs and the zeta potential of the glass/water interface for a pH of 7 was −115 ± 10 mV.

Gu and Li [8] used the streaming potential method to study the effects of surface conductance, pH, ionic concentrations and surfactants on zeta potential using the streaming potential technique. A glass slit microchannel was used as the capillary which has a form factor of $f = 1/\delta$, where δ is the gap height. As an example, the streaming potential plot obtained for deionized ultrafiltered (DIUF) water is shown in Fig. 5. Each data point represents the average of 18 readings for a given flow rate and for each gap height three flow rates were studied. Ideally for a given gap height the results for different flow rates should be almost identical. The discrepancy is attributed to the fact that the measured streaming potential $\boldsymbol{E}_\mathrm{S}$ is not exactly proportional to the pressure drop ΔP as specified in Eq. (18). A least-square linear curve fit of the data determines the zeta potential and surface conduction. In particular, the zeta potential for a glass-water interface was determined to be −62.2 mV and −22.7 mV for an electrolyte solution of 1×10^{-3} M NaCl solution. In addition, for glass/water the zeta potential var-



Zeta Potential Measurement, Figure 5 Experimental data from streaming potential measurements for glass/DIUF water in a slit microchannel [8]



Zeta Potential Measurement, Figure 6 Plot of the electro-osmotic velocity as a function of the applied electric field for two buffers (*a*) 1xTAE and (*b*) 1xTBE. Results for both the direct flow visualization method and the current-monitoring method are shown [6]

ied from −40 mV for a pH of 3 to −80 mV for a pH of 10. Sinton et al. [6] utilized both the direct visualization method and current monitoring technique to measure the zeta potential for two buffer solutions commonly used in biochemistry. The direct method employed caged fluorescent dye that upon exposure to an intense ultraviolet light uncages and fluoresces. The fluorescent dye is then tracked through a series of images that are analyzed to determine the velocity field. Electro-osmotic velocity measurements for the two methods are shown in Fig. 6. The results from both methods are in excellent agreement indicating that the simpler current-monitoring method produces accurate measurements.

Future Directions for Research

Zeta potential is a fundamental parameter for modelling and characterizing electrokinetic flows in a variety of microfluidics and Lab-on-a-Chip devices. Because the zeta potential depends on so many factors (pH, concentration, liquid, surface etc.) more measurements are required for a variety of surface-liquid combinations; particularly, biological and biochemical fluids. Since measurements can vary greatly between methods and experiments, multiple tests should be employed to accurately determine the zeta potential. In addition, measurements performed using multiple techniques can be corroborated which will reduce errors between results. The ultimate goal is to develop an accurate database of zeta potential measurements for various solid-liquid interfaces, however this will most likely require the development of new theoretical models and experimental methods to increase the accuracy and throughput of current devices.

Cross References

- ► Electric Double Layers
- ► Electric Double Layer Interaction
- ► Electroosmotic Flow (DC)
- ► AC Electro-Osmotic Flow
- ► Electrophoresis
- ► Electrical Current Monitoring Methods
- ► Methods for Measuring Zeta
- ► Inter-Atomic Potential
- ► Lennard–Jones Potential
- ► Microscale Flow Visualization
- ► Surface Conductivity Measurement
- ► Electrokinetic Flow and Ion Transport in Nanochannels
- ► Temperature Effects on the Zeta Potential
- ► Measuring Zeta Potential, Methods

References

1. Probstein RF (1994) Physiochemical Hydrodynamics. An Introduction. New York, John Wiley & Sons, Inc.
2. Hunter RJ (1981) Zeta potential in colloid science: principles and applications. Academic Press, London
3. Masiliyah JH (1994) Electrokinetic Transport Phenomena. AOSTRA, Edmonton
4. Hunter RJ (2001) Foundations of Colloid Science. Oxford University Press, Oxford
5. Sinton D (2004) Microscale flow visualization. Microfluid Nanofluid 1:2–21
6. Sinton D, Escobedo C, Ren L, Li D (2002) Direct and Indirect Electro-osmotic Flow Velocity Measurements in Microchannels. J Colloid Interface Sci 254:184–189

7. Sze A, Erickson D, Ren L, Li D (2003) Zeta-Potential Measurement Using Smoluchowski Equation and the Slope of Current-Time Relationship in Electro-osmotic Flow. J Colloid Interface Sci 261, 402-410
8. Gu Y, Li D (2000) The ζ-Potential of Glass Surface in Contact with Aqueous Solutions. J Colloid Interface Sci 226:328–339
9. Sanders RS, Chow RS, Masilyah JH (1995) Deposition of Bitumen and Asphaltene-Stabilizing Emulsions in an Impinging Jet Cell. J Colloid Interface Sci 174:230–245
10. Oddy MH, Santiago JG (2004) A method for determining electrophoretic and electro-osmotic mobilities using AC and DC electric field displacements. J Colloid Interface Sci 269:192–204

Zinc Oxide

► Piezoelectric Materials for Microfluidics

Entry List

Essays are shown in blue

Absolute Pressure 1
Absorption 1
AC Dielectrophoresis Lab-on-Chip Devices 1
AC Electrokinetics 8
AC Electro-Osmosis (ACEO) 8
AC Electro-Osmotic Flow 8
Acoustic Droplet Ejection 14
Acoustic Levitation of Droplets 14
Acoustic Particle Concentration 14
Acoustics Based Biosensors 15
Acoustic Separation 25
Acoustic Streaming 25
Acoustic Streaming Pumps 33
Acoustic Waves 33
AC Pumping of Liquids 33
Active Mixer 33
Active Mixing 38
Active Particle Flows 38
Advanced Silicon Etching (ASE) 38
AFM 39
AFM Biosensors 39
Aggregation of Nanoparticles 39
Aging 39
AlN 39
Amperometric Detection 39
Amperometric Techniques 39
Amphoteric Ion Exchange Membrane 47
Analysis/Design 47
Analysis of Individual Cell Contents 47
Analyte 47
Analytical Method 47
Analytical Modeling 47
Anion 47
Anion Exchange Membrane 47
Anisotropic Etching 47
Anisotropic Silicon Etching 49
Anisotropic Silicon Micromachining 49
Anisotropy 49
ANN 50
Anode 50
Anodic Bonding 50
Anthrax 54
Antibody 55
Antigen 55
Aperiodic AC Field 55
Aperiodic Electrophoresis 55
Apoptosis 55
Apparent Slip 55
ARDE 55
Arnoldi Algorithm 55
Arnoldi-Based Macromodeling 55
Arnoldi-Based Model Order Reduction 55
Artificial Atom 55
Artificial Muscle Materials 56
Artificial Neural Networks 56
Aspect Ratio Dependent Etching 56
Assay 56
Assembly of Nanoparticles Into Controlled Nanostructures 56
Atomic Force Microscope (AFM) 56
Atomistic Computer Simulation 56
Atomistic Deposition 56
Atwood Number 56
Background Subtraction 57
Backpressure 57
Band Broadening 57
Bead Based Assays 57
Bead Based Microfluidic Platforms 57
Behavioral Model 65
Bias Voltage 65
Bifurcating Microchannel 65
Bimorph 65
Biocatalytic Fuel Cell 65
Biochip 65
Biochip Printing 66
Bioengineering 66
Biofuel Cell 66
Biognosis 66
Bioimmobilization 66
Bio-Inspired Design 66
Biological Sensors 66
Biomedical Microdevices 66

Bio-MicroElectroMechanical Systems (BioMEMS) 67
Biomicrofluidics 67
Biomimesis 67
Biomimetics 67
Biomimicry 67
Biomolecular Adsorption in Microfluidics 68
Biomolecular Synthesis in Microfluids 76
Biomolecule Detection 84
Bionics 84
Biophysics 84
Bioprinting on Chip 84
Biorecognition 96
Biosafety 96
Biosample Preparation by Lab-on-a-Chip Devices 96
Biosecurity 106
Biosensor 106
Biosensors Using Atomic Force Microscopes 106
Biosensors Using Infrared Imaging 114
Biosensors Using Lasers 114
Biosensors Using Magnetics 119
Biosensors Using Scanning Force Microscope 120
Biosensors Using Surface-Enhanced Raman Scattering 120
Biotechnology 127
Bioterrorism 127
Biothreat 127
Biotransducer 127
Bipolar Membrane 127
Bistability 127
Blending 128
Block Copolymerization 128
Block Heteropolymerization 128
Blood Analysis 128
Blood–Plasma Separators 128
Boiling and Evaporation in Microchannels 128
Boltzmann Equation 131
Boltzmann's Constant 131
Bonding of Non-Metallic Inorganic Surfaces and Polymers 131
Bosch Process 131
Boundary Condition at Interface 131
Boundary Element Method 131
Boundary Element Method and its Applications to the Modeling of MEMS Devices 132
Boundary Integral Approaches 140
Boundary Slip of Liquids 140
Bragg Diffraction Equation or Bragg's Law 147
Bridging Instability 148
Brownian Diffusion 148
Brownian Dynamics 148
Brownian Motion 148
Brownian Noise 148
Bubble Actuated Microfluidic Switch 148
Bubble Dynamics in Microchannels 161
Bubble Formation 163
Bubble Growth 163
Bubble Jet 163
Bubble Train Flow 163
Bulk Materials 163
Bulk Micromachining 164
Bulk Micromachining of Silicon 173
Buried Channel Waveguides 173
Calcium Titanium Oxide 175
Cantilever 175
Cantilever Biosensors 175
Capacitance Cytometry 175
Capacitance Method 175
Capacitive Sensing 176
Capillarity 176
Capillarity-Driven Stop Valve and Sample Injection Switch 176
Capillary-Based Microfluidics 176
Capillary Electrochromatography 176
Capillary Electrochromatography–Electrospray Ionization–Mass Spectrometry: An Integrated Electrokinetic Analytical Technique 177
Capillary Electrophoresis 185
Capillary Electrophoretic Separation 185
Capillary Filling 185
Capillary Flow 192
Capillary Force Valves 192
Capillary Magnetophoresis 196
Capillary Reactor 196
Capillary Valves 196
Capillary Zone Electrophoresis 196
Caspase Activation 196
Cast-in-Place Polymeric Media 196
Catalyst Testing 196
Cataphoresis 196
Cathode 196
Cathode Sputtering 196
Cation 197
Cation Exchange Membrane 197
Cavitation 197
Cavitation in Microdomains 197
Cavity Resonance 201
C-Axis 201
CCD-Camera 202
CEC 202
CEC–ESI–MS 202
Cell Adhesion 202
Cell Adhesion and Detachment 202
Cell Analysis/Testing in Microfluidic Devices 208

Cell Array 208
Cell Arraying 208
Cell Assays 208
Cell Assays/Analysis/Testing on-Chip 208
Cell Assays in Microfluidics 209
Cell-Attached (Single-Channel) Voltage Clamp 216
Cell Attachment 216
Cell-Based High-Throughput Assays 216
Cell Binding 216
Cell Capture 216
Cell Culture (2D and 3D) on Chip 217
Cell Culture on a Chip 223
Cell Disruption 223
Cell Fractionation 223
Cell Handling 223
Cell Membrane Changes 223
Cell Patterning on Chip 223
Cell Positioning 224
Cell Release 224
Cell Separation 224
Cell Sorting 224
Cell and Tissue Culture 234
Cellular Microenvironments 234
Centrifugal Flow 234
Centrifugal Microfluidics 234
Ceramics 245
Changes of Caspase Activity 245
Chaotic 246
Chaotic Flows 246
Chaotic Mixing Based on Viscoelasticity 248
Charge Coupled Device (CCD) Camera 254
Chemical Bond 254
Chemical Cytometry 254
Chemical Etching 254
Chemical Patterning 255
Chemical Vapor Deposition for Film Deposition 255
Chemical Volatilization 260
Chemiluminescence 260
Chemiphoresis 260
Chip-Based Systems 260
Chip Bonding 260
Chip Electrospray Mass Spectrometry 260
Chip Thermocyclers 260
Chiral Nematic 260
Cholesteric 260
Chromatographic Chip Devices 260
Chromatography 264
Closed-Loop 264
Closing Pressure 264
Clusters 265
CMOS-Camera 265
CMUTs 265
Coarse-Grained Particle Methods 265
Coarse-Graining 265
Co-Ions 265
Cold Light Sources 265
Colloidal Forces 265
Color Cameras 265
Color Temperature 265
Combinatorial Library 265
Combined Pressure-Driven Flow and Electroosmotic Flow 266
Compactness 274
Compact Support 274
Complex Fluids 274
Composite Nanoparticles 274
Compression Molding 274
Compression Ratio 274
Computational Domain 275
Computational Fluid Dynamics (CFD) 275
Computational Region 275
Concentration Control 275
Concentration Gradient Generation and Control 275
Condensation in Microchannels 285
Conductivity Detection 291
Confined Bubble Growth 291
Confocal Microscope 291
Confocal Microscopy, Detection 291
Constricted Flow Dimensions 296
Contact Line 296
Contact Temperature Sensors 296
Continuous Model 296
Contraphilic 296
Control 296
Controlled-Potential Instrumentation 296
Controlled System 297
Control of Micro-Flows 297
Control of Micro-Fluidics 297
Control Theory 304
Control Volume Based Finite Difference Method 304
Control Volume Method 304
Convective Dispersion 304
Convective Heat Transfer in Microchannels 304
Conventional Sized Channels 322
Core-Shell Nanoparticles 322
Counterions 322
Coupling Microfluidic Devices to Mass Spectrometers 322
Covalent Bonding 322
Critical Heat Flux (CHF) 322
Critical Reynolds Number 322
Crossed Field Filter 323
Crossed-Field Mass Spectrometer 323
Crosslinked Gels 323

Crystallizaiton 323
Cunningham's Correction 323
Cunningham Slip Correction 323
Curie Temperature 323
Curie–Weiss Temperature 323
Current Monitoring Method 323
Current Monitoring Technique 323
Curvature 323
Curved Microchannel Flow 324
CVD 329
Cy3/Cy5-Dye 329
Cytometric Bead Immunoassay 329
DC Capacitance 331
DC Dielectrophoresis in Lab-on-a-Chip Devices 331
Dead Volume 334
Debye-Hückel Approximation 334
Debye Layer 334
Debye Length 335
Deep Lithography 335
Deep Reactive-Ion Etching (DRIE) 335
Deep Reactive Ion Silicon Etching 335
Degree of Mixing 335
De Laval Nozzle 335
Delta Function 335
Demixing 335
DEP 348
Deposition 348
Depth of Field 348
Detection Groove 348
Developing Flows 348
Developing Region 349
Device Substrates 349
Diagnostic Biochip 349
Diamond Like Carbon (DLC) 350
Diamond Nanoparticles 350
Diaphragm Actuation 350
Diaphragm Pump 350
Dielectric Spectroscopy 350
Dielectrophoresis 350
Dielectrophoretic Force 357
Dielectrophoretic Motion of Particles and Cells 357
Differential Ion Mobility Spectrometry 364
Differential Pressure 365
Diffuse Double Layer 365
Diffuse Interface Model 365
Diffusion 365
Diffusion-Based Mixing 365
Diffusiophoresis 365
Digital Microfluidics 370
Dip-Pen Nanolithography 375
Dirac Delta Function 379
Direct Bonding 379
Direct Current Dielectrophoresis (DC-DEP) 379
Discrete Element Analysis 379
Discrete Least Square 379
Discrete Method 379
Discretization 379
Disjoining Pressure 380
Dispensing 385
Dispersed Magnetic Nanoparticles 385
Dissipative Particle Dynamics 385
Distributed Parameter Model 391
DLVO Theory 391
DNA Array 391
DNA Chip 391
DNA Extraction 391
DNA Fragmentation 391
DNA Hybridization 391
DNA Ladders 391
DNA Microarrays 391
Doppler OCT 396
DPN 396
DRIE (Deep Reactive Ion Etching) 396
Drop 397
Drop on Demand 397
Droplet 397
Droplet Based Lab-on-Chip Devices 397
Droplet-Based Microreactor 402
Droplet Break Up 402
Droplet on Demand 402
Droplet Dispensing 402
Droplet Dynamics in Microchannels 411
Droplet Ejection 418
Droplet Evaporation 418
Droplet Flow 423
Droplet Formation 423
Droplet Generation 423
Droplet Generator 423
Droplet Injection 423
Droplet Manipulation 423
Droplet Microfluidics 423
Droplet Micromixer 423
Droplet Microreactor 423
Droplet Motion in Microchannels 427
Droplet Release 428
Droplet Tear-Off 428
Droplet Transport by Surface Acoustic Waves 428
Drug Delivery 428
Dry Chemical Etch 428
Dry Etch 428
Duty Cycle 428
Dynamic Density Functional Theory (DDFT) 428
Dynamic Mixing 433
EDL Potential 435

Effective Coupling Coefficient 435
Einstein Relation 435
Elastomeric Valve 435
Electrets 435
Electrical Current Monitoring Methods 435
Electrical Double Layer Potential 444
Electrical Double Layers 444
Electrical Double Layers Interaction 453
Electrical/Electrochemical Impedance 459
Electric Debye Layer 460
Electric Heating 460
Electric Paper-Like Display 460
Electroactive Materials 460
Electrocapillarity 460
Electrocapillary 460
Electrocapillary Effect 469
Electrochemical Detection 469
Electrochemical Etching 469
Electrochemical Techniques 469
Electrochemiluminescence 474
Electro Chemo Luminescence (ECL) 474
Electrodeless Dielectrophoresis 482
3D Electrodes 482
Electroendosmosis 482
Electrogenerated Chemiluminescence 482
Electrohydrodynamic Dispensing 482
Electrohydrodynamic Focusing 482
Electrohydrodynamic Instability 482
Electrohydrodynamic Mixing 482
Electrokinetic Dispensing 482
Electrokinetic/ElectroHydrodynamic Flow Instability 489
Electrokinetic Flow 496
Electrokinetic Flow and Ion Transport in Nanochannels 496
Electrokinetic Flow in Porous Media 506
Electrokinetic Focusing 516
Electrokinetic Injection 516
Electrokinetic Instability 517
Electrokinetic Mobility 517
Electrokinetic Motion 517
Electrokinetic Motion of Cells and Nonpolarizable Particles 517
Electrokinetic Motion of Heterogeneous Particles 518
Electrokinetic Motion of Polarizable Particles 522
Electrokinetic Potential 529
Electrokinetic Sample Dispensing 529
Electrokinetic Sample Injection 529
Electrokinetic Sample Introduction 536
Electrokinetic Transport 536
Electrokinetic Transport with Biochemical Reactions 536
Electrokinetic Two-Phase Flows 547
Electromagnetically Actuated Pumps 554
Electromagnetophoresis 554
Electromechanical Coupling 554
Electromechanically Coupled Materials 554
Electromigration 554
Electronic Packaging 554
Electronic Paper 554
Electroosmosis 560
Electro-Osmosis with Patterned Surface Charge 560
Electroosmosis in Porous Media 560
Electroosmotic Dispensing 560
Electroosmotic Flow 560
Electroosmotic Flow (DC) 560
Electroosmotic Flow (EOF) 567
Electroosmotic Flow over Heterogeneous Surfaces 567
Electroosmotic Flow Over Non-Uniform Surfaces 574
Electroosmotic Flow in Porous Media 574
Electroosmotic Pump 574
Electropermeabilization 580
Electrophoresis 580
Electrophoresis of the Second Kind 588
Electrophoretic Flow 588
Electrophoretic Mobility 588
Electrophoretic Transport in Nanofluidic Channels 588
Electroporation 592
Electrospray Emitter on-Chip 593
Electrospray Ionization 593
Electrospray Ionization-Mass Spectrometry (ESI-MS) 593
Electrospray Mass Spectrometry 593
Electrostatic Bonding 593
Electrostatic Quadrupole 593
Electrostatic Valves 593
Electrostrictive 595
Electrothermal Effects 595
Electrothermal Flow 599
Electroviscosity 599
Electrowetting 600
Electrowetting, Applications 606
Electrowetting on Dielectric (EWOD) 615
Electrowetting and Droplets 615
Electrowetting on Insulator Coated Electrodes (EICE) 620
Electrowetting on Line Electrodes (ELE) 620
Element Connectivity 620
Element Connectivity Matrix 620

Element-Free Methods 620
Element Model 620
Elongated Bubble Flow 620
Encapsulation 620
Endergonic 620
Endothermic 620
Entrance Flows 621
Entrance Region 621
Enzymatic Bioreactor 630
Enzymatic or Chemical Digestion 630
Enzymatic Fuel Cell 630
Enzymatic Nanolithography 630
Enzyme Assay 630
Enzyme-Assisted Nanolithography 630
Enzyme Based Nanolithography 630
Enzyme Nanolithography 630
Enzymes 636
EOP 636
EO Pump 636
Epitaxial 636
Epitaxial Growth 636
Epitaxy 636
Equivalent Mean Free Path 636
ESI 637
Establishing Flows 637
Establishing Region 637
Etch Directionality 637
Etching Rate Ratio 637
Etching Single Crystalline Materials 637
Etch Profile 637
Etch Selectivity 637
Eulerian Streaming 637
Evanescent Field 637
Evanescent Wave 637
Evanescent Wave Illumination 638
Evanescent Wave Microscopy 638
Evaporation Deposition 644
Explosive Boiling in Microchannels 644
Extensional 644
External Actuators 644
Externalization of Phosphatidylserine 644
Fabrication of 3D Microfluidic Channels 645
Fabrication of 3D Microfluidic Structures 645
Fabrication of Self-Assembled Catalytic Nanostructures 656
Fabry-Perot Optical Filter 662
Feature Size Dependent Etching 663
Feedback 663
Ferroelectric 663
Ferrofluids in Microchannels 664
Fiber Optic Cables 669
Fiber Optics 669
Field Assisted Bonding 669
Field Asymmetric Ion Mobility Spectrometry 669
Field-Dependent Electrophoretic Mobility 669
Field-Effect Flow Control 669
Film Coating 669
Filters 669
Finite Volume and Finite Difference Methods for Modeling and Simulation 669
Flexible Member Pump 679
Flexible Shear Stress Sensor 679
Flip of Phosphatidylserine 680
Flow Bifurcation in Microchannel 680
Flow Boiling Instability 687
Flow Boiling in Microchannels 695
Flow Boiling in Narrow Channels 695
Flow in Channels with 3D Elements 695
Flow Control 696
Flow of Coolants in Micro-Conduits 696
Flow Cytometer Lab-on-Chip Devices 696
Flow Field-Effect Transistor 708
Flow Instabilities 708
Flow and Mass Transport Through Rough Microchannels 708
Flow Measurement 708
Flow Meters 708
Flow in Microchannels with 3D Roughness 708
Flow Patterns 708
Flow Profiling 708
Flow Rate 708
Flow Rate Measurements, Methods 708
Flow Sensors 718
Flow Simulations in Transitional and Rarefied Regimes 718
Flow by Surface Acoustic Waves 718
Flow Tagging 719
Flow-Through Electrodes 719
Fluerics 719
Fluid Dispersion 719
Fluidic Amplification and Oscillation 719
Fluidic Diodes 719
Fluidic Logic 720
Fluidic Multiplexer 720
Fluidic Pressure Sensing 720
Fluidic Pumping 720
Fluidic Rectification 720
Fluidic Sequencing Circuits 720
Fluid Metering 720
Fluid Metrology 730
Fluid Particle Model 730
Fluid Quantification 730
Fluorescence 730
Fluorescence Detection 730

Fluorescence Efficiency 730
Fluorescence Lifetime 730
Fluorescence Measurements 731
Fluorescence Microscopy 737
Fluorescence Resonance Energy Transfer (FRET) 737
Fluorescence Visualization 737
Fluorescence Yield 737
Fluorescent Labeling 737
Fluorescent Microscopy 749
Fluorescent Probes 750
Fluorescent Thermometry 750
Fluorescent Visualization 759
Fluorophores 759
Focused Ion Beam Milling (FIB) 760
Force-Based Biosensors 760
Force Biosensors 760
FOV – Field of View 760
Free Boundary Reflection 760
Free-Flow Magnetophoresis 760
Free Molecular Regime 760
Free-Surface Atomization 760
Free Surface Electrohydrodynamics 760
Free Surface Electrokinetics 760
Free Surface Flow 760
Frequency Response 760
Friction Factor in Microchannels 761
Front Capturing 761
Front Tracking 761
Fuel Cell 761
Full-Width Half-Maximum (FWHM) 761
Fundamentals of Diffusion in Microfluidic Systems 761
Fusion Bonding 768
Gage Pressure 769
Gas Chromatography 769
Gaseous Flow 772
Gaseous Samples 772
Gas Flow 772
Gas Flow in Nanochannels 772
Gas–Surface Scattering Kernel 778
Gate in the Cell Wall 778
Gaussian Filter 778
GC 778
Gene Chip 778
Generalized Boltzmann Equation 778
Generalized Formulation 778
Genosensors 778
Glass 779
Glass-Polymer Bonding 779
Glycosidase 789
Glycoside Hydrolase 789
Gravity Wave 789
Gray-Scale Lithography 789
Gray-Tone Lithography 790
Guard Flows 790
HARMST (High Aspect Ratio Micro-Structure Technology) 791
Head Pressure 791
Heat Absorption 791
Heat Capacity 791
Heating Foil 791
Heat Transfer in Microchannel Flow 791
Helical Microchannel Flow 791
Helmholtz Cavity 791
Hemholtz Resonance 791
Hermann–Mauguin Notation 792
Heterogeneous Membrane 792
High Aspect Ratio Si Etching 792
High Performance Liquid Chromatography (HPLC) 792
High Pressure Liquid Chromatography (HPLC) 792
High-Throughput Chemical Testing 792
High-Throughput Screening (HTS) 792
Homogenization 792
Hot Embossing 792
Hot Film 793
Hot Press Bonding 793
Hot Press Molding 793
Hot Wire 793
Hot Wire Anemometer 793
HSV 793
HSV Color Space 793
HSV / Intensity Images 793
Hybrid Bonding 793
Hybrid Simulation 793
Hydrodynamic Dispersion 793
Hydrogels 801
Hydrogen Bond 801
Hydrogen Passivation 802
Hydrophilic/Hydrophobic Patterning 802
Hydrophobic/Hydrophilic Microfluidics 803
Hydrophobic/Hydrophilic Patterning 803
Hysteresis 803
ICEO 805
ICEP 805
IC Packaging 805
ICP Etching 805
Illuminance 805
Imaging for Biosensors/Biochips/Microchips 805
Immersed Boundary Method 805
Immersed Interface Method 808
Immobilized Enzyme Biosensor 808
Immobilized Enzyme Reactor 808

Immobilized Microfluidic Enzyme Reactor (IMER) 808
Immunoassay 808
Immunochemistry 808
Immunodiffusion 808
Impact Evaporation 808
Impedance 808
Impedance Biosensors 809
Impedance Measurements of Cells 809
Impedimetric Biosensors for Nano- and Microfluidics 811
Impulse Bit 823
Induced-Charge Electro-Osmosis 824
Induced-Charge Electrophoresis 824
Infrared Imaging and Mapping for Biosensors 824
Infrared (IR) Mapping 826
Infrared Radiation 826
Infrared Thermography 826
Injection Molding 826
Injection Slit 826
Inkjet 826
Inkjet Print 827
Inkjet Printing 827
Inkjet Printing in Microfabrication 827
In situ Polymerized Materials 827
Insulating Post Dielectrophoresis 827
Insulator-Based Dielectrophoresis (iDEP) 827
Integrated Actuators 827
Integrated Biochips 828
Integrated Light Confiners 828
Integrated Light Guiding 828
Integrated Light Propagator 828
Integrated Microdevices for Biological Applications 828
Integrated Microdevices for Medical Diagnostics 834
Integrated Microfluidic Devices 840
Integrated Nanoliter System 840
Integrated Temperature Control in Microfluidic Systems 840
Integrated Waveguides 840
Intelligent Gels 840
Inter-Atomic Potential 841
Interdigitated Microelectrode 841
Interface Capturing Schemes for Free-Surface Flows 841
Interfaces between Microfluidics and Mass Spectrometry 849
Interface Tracking 854
Interfacial Electrohydrodynamics 854
Interfacial Electrokinetic Flow 854
Interfacial Flow 866
Interfacial Flow Modelling 866
Interfacial Instability 866
Interfacing Lab-on-a-Chip Platforms with Mass Spectrometers Using MALDI and ESI 871
Intermittent Flow 871
Internal Friction 871
Internal Rarefied Gas Flows 872
International Notation 872
Internucleosomal DNA Fragmentation 872
Interrogation Area 872
Intracellular Ca2+ Concentration Changes 872
Intracellular Ca2+ Fluxes 872
Inversion Symmetry 872
Ion Channel 872
Ion Conductance in Nanochannels 873
Ion Counter 873
Ion Detector 873
Ion Exchange Membranes 873
Ion Implantation 876
Ionization Source 876
Ion Mobility 876
Ion Mobility Spectrometer 876
Ion Source 876
Ion Transport 877
Ion Transport in Nanopores 877
Ion Trap Mass Spectrometer 877
IPRT 877
Irradiance 877
Isentropic Flow 877
Isotropic Etching 877
Isotropic Silicon Etching 884
I-STAT 884
Janus Particle 885
Jet Pumping 885
Jetting 885
Jet-Type Rectifier 885
Joule Heating and Chip Materials 886
Joule Heating Effect 896
Joule Heating in Electrokinetic Flow: Theoretical Models 896
Karhunen–Loève (K–L) Approach 905
Karhunen–Loève (K–L) Decomposition 905
Karhunen–Loève (K–L) Expansion 905
Kelvin–Hemholtz Instability 905
Kernel Function 905
Kinetic Boltzmann Equation 905
Kinetics 906
Kinetic Theory of Gases 906
Knoevenagel Condensation 906
Knudsen Number 906
Lab-Cd 907
Lab-on-a-Chip 907

Lab-on-Chip Devices for Biodefense Applications 907
Lab-on-a-Chip Devices for Chemical Analysis 910
Lab-on-Chip Devices for Immunoassays 927
Lab-on-a-Chip Devices for Particle and Cell Separation 930
Lab-on-Chip Devices for Protein Analysis 940
Lab-on-a-Chip Devices for Sample Extractions 948
Lab-on-Chip Devices for Separation-Based Detection 954
Lab-on-a-Chip (General Philosophy) 962
Lab-on-a-Disk 969
Laboratorial Microsystem 969
Laminar Flow 969
Laminar Flow-Based Fuel Cells 969
Laminar to Turbulent Flow Transition 969
Laplace Pressure 969
Laplace Pressure Drop 970
Laser Ablation 970
Laser-Based Biosensors 973
Laser Based Micromachining 973
Laser Doppler Anemometry 980
Laser Doppler Sensor 980
Laser-Induced Fluorescence (LIF) 980
Laser-Induced Molecular Tagging 980
Laser-Induced Photochemical Anemometry 980
Laser Machining 980
Laser Micromachining 981
Laser Scanning Confocal Microscopy (LSCM) 981
Lattice Boltzmann Equation 981
Lattice Boltzmann Method (LBM) 981
Lattice Poisson–Boltzmann Method, Analysis of Electroosmotic Microfludics 985
LC-LIGA (Low-Cost LIGA) 999
Lead Zirconate Titanate 999
Least Square 999
Lennard-Jones Potential 1000
Level Set Method 1000
LIGA 1000
LIGA-Like Techniques 1003
Ligand 1005
Light Sheet 1005
Linear Peristaltic Pump 1005
Liquid Chromatography 1006
Liquid Crystal Technique for Measuring Temperature 1012
Liquid Extraction 1022
Liquid Handling 1022
Liquid–Liquid Electroosmotic Flow 1022
Liquid–Liquid Stratified Flow in Microchannels 1022
Liquid Magnet 1031
Liquid–Solid Electrophoretic Flow 1031
Liquid–Vapor Phase Change 1031
Lithography 1031
Local Filtering 1031
Low-Frequency Capacitance 1032
Low-Pass Filtering 1032
Ludwig–Soret Effect 1032
Luminescence 1032
Luminescent Labels 1032
Lumped Analysis 1032
Lumped Capacitance 1032
Mach Number 1033
Macromodel 1033
Macromolecular Transport 1033
Magnetic-Based Biosensors 1033
Magnetic Biosensors 1033
Magnetic Coils 1033
Magnetic Field-Based Lab-on-Chip Devices 1033
Magnetic Field-Based Microfluidic Devices 1040
Magnetic Fields 1040
Magnetic Filter 1040
Magnetic Fluid 1040
Magnetic Mass Spectrometer 1040
Magnetic Microbeads 1040
Magnetic Pumps 1040
Magnetic Split-Flow Thin Fractionation 1043
Magnetic Susceptibility 1043
Magnetohydrodynamic Pumps 1043
Magnetophoresis 1043
Magnetron 1048
Magnets 1048
MALDI 1048
Manipulating Cells, Techniques 1048
Marangoni Convection 1050
Marangoni Effect 1055
Mass Analyser 1055
Mass Filter 1055
Mass Spectrometer 1056
Mass Spectrometry 1056
Mass Spectrometry on a Chip 1057
Materials Used in Microfluidic Devices 1065
Matrix Assisted Laser Desorption/Ionization 1068
Mean Curvature 1068
Mean Filter 1068
Mean Free Path 1068
Measurement Depth 1068
Measurement Standards 1068
Measuring Zeta Potential, Methods 1068
Mechanical Nanodetectors 1076
Mechanical Nanosensors 1076
Median Filters 1078
Medical Imaging 1078
Membrane Actuation for Micropumps 1078

Membraneless Fuel Cells 1082
Membrane Pump 1082
Membrane Reactor 1082
Memory 1082
Memory Effect 1083
MEMS Actuators 1083
MEMS-Based Biosensor 1083
MEMS Biosensor 1091
MEMS-Nozzle 1091
MEMS Packaging 1091
MEMS-Thruster 1091
Meniscus 1092
Meshfree Methods 1092
Meshless Methods 1092
Mesicopter 1100
Mesomorphic State 1100
Mesoscopic Method 1100
Metalorganic Chemical Vapor Deposition (MOCVD) 1100
MGA 1100
Microactuators 1100
Micro Aerial Vehicles 1103
Microair Vehicle (MAV) 1110
Microarray 1110
Microarray Fabrication 1110
Microbial Fuel Cell 1110
Microbiosensor 1110
Microchannel 1110
Microchannel Flow 1111
Microchannel Glow Discharge 1111
Microchannel Heat Sinks (MCHS) 1111
Microchannel Surface Modification 1111
Microchannel Surface Sterilization 1111
Microchemical Systems 1111
Micro Chemlab 1111
Micro Coolers 1111
Microdialysis 1111
Microdrone 1119
Microdroplet Transport 1119
Micro-Encapsulation 1119
Micro Energy Conversion Devices 1119
Micro Energy Harvesting 1127
Micro Energy Scavenging 1127
Microengines 1127
Microfabricated Coulter Counter 1127
Microfabricated Flow Cytometer 1127
Microfabricated Needles 1128
Microfabrication 1128
3D Microfabrication 1128
Microfabrication of Three-Dimensional Microstructures 1128
Microfilters 1128
Microflaps 1135
Microflow Actuator 1136
Microflow Switch 1136
Microfluidic Analysis System 1136
Microfluidic Assembly 1136
Microfluidic Bioreactors 1147
Microfluidic Cell Culture 1151
Microfluidic Chip 1151
Microfluidic Circuits 1151
Microfluidic Component Assembly 1159
Microfluidic Devices 1159
Microfluidic Devices in Tissue Engineering 1159
Microfluidic Flow Visualization 1169
Microfluidic Fuel Cells 1169
Microfluidic Imaging 1177
Microfluidic Integration 1177
Microfluidic Mixer 1177
Microfluidic Mixing 1177
Microfluidic Optical Devices 1186
Microfluidic Platforms 1187
Microfluidic Reactor for Biomolecular Synthesis 1187
Microfluidic Reactor for Polymer Synthesis 1188
Microfluidic Rotary Pump 1188
Microfluidics 1189
Microfluidic Sample Manipulation 1189
Microfluidics-Based Surface Patterning Tools 1194
Microfluidics for Biochemical and Chemical Reactions 1195
Microfluidics on a CD 1207
Microfluidics and Magnetism 1207
Microfluidics and Nanofluidics 1207
Microfluidics for Stem Cell Therapy 1207
Microfluidics for Studies of Apoptosis 1213
Microfluidic Stem Cell Culture 1220
Microfluidic System Control Modules 1221
Microfluidic Systems 1221
Microfluidic Systems Assembly 1221
Microfluidic Systems for Combinatorial Chemistry 1221
Microfluidic Systems for High-Throughput Screening 1230
Microfluidic Systems Packaging 1243
Microfluidic Systems in Space Science 1243
Micro Fluorescently-Activated Cell Sorting (µFACS) 1244
Micro Fuel Cells 1244
Micro Gas Analyzers 1244
Micro Gas Chromatography 1244
Micro Gas and Liquid Chromatography 1244
Micro Gas Turbine Engines 1244
Micro Gas Turbines 1244

μGC 1244
Microgravity 1244
Micro Heat Engines 1244
Micro-Heat Exchangers 1245
Micro Heat Pipes 1245
Micro Hot-Wire Anemometer 1253
Microhypodermic Needles 1253
Microjets 1253
Micro Laser Doppler Velocimetry (μ-LDV) 1253
Microlayer 1255
Micro-LC 1255
Microlithography 1255
Micromachined Coulter Counter 1255
Micromachined Flow Cytometer 1256
3D Micromachining 1256
Micromixer 1256
Micromixing Chip 1256
Micromolding 1256
Micromolding (Injection and Compression Molding) 1267
Micro/Nano Anemometers 1274
Micro/Nanofluidics 1274
Micro- and Nanoscale Anemometry: Implication for Biomedical Applications 1274
Micro- and Nanoscale Gas Dynamics 1281
Micro- and Nanoscale Gas Fluidics 1287
Microneedles – Applications & Devices 1294
μPEMFC 1300
Micro-PIV-Based Diffusometry 1300
Microplug Transport 1305
Microporous Materials 1306
Microporous Membranes 1306
Micropowder Blasting 1306
Micro Power Generation 1306
Microprojections 1306
Micro Propulsion 1306
Microreaction Technology 1306
Microreactor 1306
Microreactor for Synthesis of Biomolecules 1306
Microrockets 1306
Microrotorcraft 1307
Microscale Cooling Devices 1314
Microscale Flow Visualization 1325
Microscale Needles 1334
Microscopic Lenses 1334
Microsegmented Flow 1335
Micro-Shock Tube 1342
Microslug Flow 1342
Micro Steam Turbines 1342
Microsterolithography 1342
Microstructured Hydrogen Fuel Cells 1351
Microsynthetic Jets 1354
Microsystems 1359
μTAS 1359
Microthermocyclers 1359
Microthrusters 1359
Microtips and Microspikes 1359
Micro Total Analysis System (μTAS) 1359
Microturbines 1359
Microvalve 1368
Micro-Wave Rotor 1368
Millikan’s Resistance Factor 1368
Miniature Heat Pipes 1368
Miniature Heat-Removal Devices 1368
Miniature Unmanned Air Vehicle (UAV) 1368
Miniaturized Analysis Systems 1368
Miniaturized Fluorescence-Activated Cell Sorting Devices 1368
Miniaturized Ion Mobility Spectrometry 1368
Miniaturized Systems 1376
Miniaturized Total Analysis System (μ-TAS) 1376
Minichannels 1376
Mixing Effectiveness 1376
Mixing Efficiency 1376
Mixing Enhancement 1376
Mixing Measures 1376
Mixing Performance 1382
Mixing Quality 1382
MLPA 1382
Mn 1382
Model Kinetic Equation 1382
Model Order Reduction (MOR) 1382
Model Reduction 1391
Molecular Beam Epitaxy (MBE) 1391
Molecular-Continuum Simulation 1391
Molecular Dynamics 1391
Molecular Dynamics Simulation Method 1391
Molecular Flow 1398
Molecular Method 1398
Molecular Modeling 1398
Molecular Self-Assembly Fabrication 1398
Monoclonal 1398
Monostability 1398
Monte Carlo Method 1398
Monte Carlo Simulation Method 1401
Morphotropic Phase Boundary 1401
Motional Branch 1401
Motional Circuit 1401
Motional Leg 1401
Motion of a Deformable Drop in Microchannels 1401
MS 1401
MS/MS 1401
Multi-Channel Micro Liquid Dosing System 1401
Multi-Channel Micro Switch Pumping 1401

Multilayer Piezoelectric Actuator 1401
Multiphase Flows 1402
Multiphase Pumping 1402
Multiplexed Time Etching 1402
Multiscale Modeling 1402
Multiscale Modeling and Numerical Simulations 1402
Mw/Mn 1407
Nanoarrays 1409
Nanobiosensors for Nano- and Microfluidics 1409
Nanocatalyst 1409
Nanochannel Fabrication 1409
Nanochannels 1414
Nanochips 1414
Nanoclusters 1414
Nanocrystals 1414
Nanofluid Flow in Microchannels 1414
Nanofluidic Channels 1414
Nanofluidics 1414
Nanofluidics in Carbon Nanotubes 1414
Nanofluidic Single Molecule Detection 1417
Nanofluidic Single Molecule Sensors 1417
Nanofluidic Systems for Single Molecule Detection 1417
Nanofluids 1422
Nanolithography 1422
Nanometer 1422
Nano-Particle Controllable Assembly 1422
Nanoparticles 1437
Nanoparticle Synthesis in Microreactors 1437
Nanophotonic Characterization in a Microfluidic System 1446
Nanopore Conductance 1446
Nanopore Fabrication 1447
Nanopores 1447
Nanorods 1447
Nanoscale Biosensors 1447
Nanoscale Optofluidic Characterization Techniques 1448
Nanoscale Optofluidic Measurement 1456
Nanosensors 1456
Nanostructures 1456
NEMS-Based Biosensors 1456
Neural Network 1456
Nitrides 1457
No-Moving-Part Pumps 1457
No-Moving-Part Valves 1457
Non-Centrosymmetric 1457
Non-Continuous Approaches 1457
Non-Covalent Bonding 1461
Non-Covalent Forces 1461
Non-Covalent Interactions 1461
Non-Directional Etching 1461
Non-Equilibrium Diffuse Charge 1461
Non-Equilibrium Electrical Double Layer 1461
Nonlinear Electrokinetic Phenomena 1461
Nonlinear Electro-Osmosis 1470
Nonlinear Electrophoresis 1470
Nonlinear Electrophoretic Mobility 1470
Non-Metallic Inorganic Materials 1470
Non-Newtonian 1471
Non-Newtonian Fluid 1471
Non-Newtonian Fluids in Microchannel 1471
Non-Newtonian Fluids in Microfluidics 1480
Nucleation 1488
Nucleation and Growth 1488
Nucleic Acid Detection 1488
Nucleus 1488
Number-Average Molecular Weight 1488
Numerical Discretization 1489
Numerical Simulation 1489
Numerical Solution of Boltzmann Equation 1489
Numerical Stability 1494
Numerical Techniques for Free Surface Flows: Interface Capturing and Interface Tracking 1494
Ohmic Heating 1513
Ohnesorge Number 1513
On-Chip Cell Culture 1513
On-Chip Cell Lysis 1513
On-Chip Detection 1515
On-Chip Detection Using Optical Fibers 1515
On-Chip Electrospray 1530
On-Chip Free-Flow Magnetophoresis 1539
On-Chip Laboratory 1539
On Chip Light Confiners 1539
On Chip Light Guiding 1539
On Chip Light Propagator 1539
On-Chip Micro-Optical Detection 1539
On Chip Waveguides 1544
Optical Coherence Imaging 1553
Optical Coherence Tomography and Optical Doppler Tomography 1553
Optical Doppler Tomography (ODT) 1557
Optical Doppler Velocimetry 1557
Optical Lithography 1558
Optical Narrow Passband Filter 1558
Optical Trapping 1558
Optical Traps 1558
Optical Tweezers for Manipulating Cells and Particles 1558
Optofluidics – Applications 1563
Optofluidics – Fluidics Enabling Optics 1567
Optofluidics: Optics Enabling Fluidics 1572

Optofluidics – Techniques for Fabrication and Integration 1578
Ordinary Least Square 1583
Organ Fabrication 1583
Organic Material 1583
Organ or Tissue Augmentation 1584
Orthorhombic Crystal 1584
Over/Under/Perfectly-Expanded Nozzle Flow 1584
Oxidation/Reduction 1584
Oxidation (of Silicon) 1584
Oxide Deposition 1591
Oxide Growth 1591
Oxides 1591
Packaging (and Wire Bonding) 1593
Parallelization 1596
Parallel (Stratified) Flow 1597
Partial Differential Equations (PDEs) 1597
Particle Dynamics Simulation 1597
Particle Image Thermometry 1597
Particle Image Velocimetry (PIV) 1597
Particle Manipulation 1597
Particle Manipulation Using Ultrasonic Fields 1597
Particle Methods 1602
Passive Micromixers 1602
Passive Mixer 1610
Patch Clamp Measurements On-Chip 1610
Patch Clamp Technique 1618
Patch Voltage Clamp Technique 1618
PCR Lab-on-Chip Devices 1618
Peclet Number 1626
Peltier Effect 1626
Perfect Slip 1626
Peristalsis 1626
Peristaltic Pumps 1626
Permeabilization of Cells 1633
Perovskite 1633
Phase-Change Heat Transfer in Microchannels 1633
Phase Field Method 1633
Phase Separation Kinetics 1633
Phase Shift 1634
pH Control Device 1634
Phenol Extraction 1634
Phenotypic Assay 1634
Phenotypic Screening in Microfluidic Devices/on-Chip 1634
Phosphorescence 1634
Photo-Activated Nonintrusive Tracking of Molecular Motion 1634
Photobleached Fluorescence 1634
Photobleaching 1634
Photochemical Decomposition 1634
Photochemical Degradation 1634
Photofluidic Devices 1634
Photofluidics 1634
Photolithography 1635
Photoluminescence 1636
Photomask 1636
Photometer 1636
Photometry 1642
Photo Patterned 1642
Photopatterned Materials 1642
Photoresist Reflow 1642
Photoresist SU-8 1643
Photoresponsive Hydrogels 1643
Photosensitive Hydrogels 1643
Photoswitchable Hydrogels 1647
Photothermal Effect 1647
pH-Sensitive Hydrogel 1647
pH-Sensitive Valve 1649
pH Sensor 1649
Physical-Chemical Etching 1649
Physical Domain 1650
Physical Etching 1650
Physical Region 1650
Physical Vapor Deposition 1650
Picoliter Flow Calibration 1650
Piezoelectric 1653
Piezoelectric Drop-on-Demand 1654
Piezoelectric Ink Jet 1654
Piezoelectric Materials for Microfluidics 1654
Piezoelectric Microdispenser 1662
Piezoelectric Micro/Nanoliter Droplet Dispenser 1672
Piezoelectric Pumps 1672
Piezoelectric Valves 1672
pL 1672
Planar Laser-Induced Fluorescence 1673
Plasma Bonding 1673
Plasma Chromatography 1673
Plasma Etching 1673
Plasma in Microchannel 1684
Plasma Oxidation 1691
Plasma Treatment of Nanoparticles for Nanofluids 1691
Plastic 1700
Plasticity 1700
Platinum Resistance Thermometer 1700
Plug Flow 1700
Pneumatic Valves 1700
Poiseuille Coefficient 1702
Poiseuille Single Phase Gas Flows 1702
Polyclonal 1702
Poly(dimethylsiloxane) (PDMS) 1702
Polydispersity 1702

Polydispersity Index 1703
Polyelectrolyte 1703
Polyelectrolyte Patterning Technique 1703
Polymer 1703
Polymer Casting 1703
Polymer Electrolyte Membrane Fuel Cells 1703
Polymerization Reaction in Microreactor 1703
Polymer Monoliths 1703
Polymer Replication 1703
Polymer Solutions 1703
Polymer Synthesis within Microfluidic Reactor 1703
Poor Man’s LIGA 1710
Porous Electrodes 1710
Port Resonance 1710
Positive Displacement Pump 1710
Positive Pressure or Suction (Vacuum) Pressure 1710
Potassium Hydroxide (KOH) Etching 1710
Powder Blasting 1711
Power MEMS 1714
Precipitate 1714
Precipitation 1714
Precursor Materials 1714
Predecessor Material 1714
Preparatory Separation 1714
Pressure 1714
Pressure-Driven Flow 1714
Pressure-Driven Single Phase Gas Flows 1714
Pressure-Driven Single Phase Liquid Flows 1724
Pressure-Driven Two Phase Flows 1736
Pressure Drop in Microchannels 1743
Pressure Injection 1743
Pressure Measurements, Methods 1743
Pressure Sensors 1745
Pressure Wave 1745
Primitive Model 1745
Probe Microscopy 1745
Programmed Cell Death 1745
Proper Orthogonal Decomposition (POD) Based MOR 1745
Protein Adsorption 1745
Protein Array 1745
Protein Array and Cell Array 1745
Protein Chip 1746
Protein Microarrays 1746
Protein Profiling 1748
Proteolysis 1748
Proteomics 1749
Proteomics in Microfluidic Devices 1749
Proton Exchange Membrane Fuel Cells 1758
PRT 1758
Pump Head 1758
Pyroelectric 1758
Pyroelectric Flow Sensors 1758
Pyroelectricity 1765
Pyroelectric Sensors 1765
PZT 1765
Q-Dots 1767
Quadrupole Filter 1767
Quadrupole Ion Trap 1767
Quadrupole Mass Spectrometer 1767
Quantum Box 1767
Quantum Dot 1767
Quantum-Dot Quantum Well (QDQW Nanoparticles) 1769
Quantum Efficiency 1769
Quantum Yield 1769
Quartz 1769
Radiation Pressure 1771
Radical Polymerization 1771
Radiofrequency (RF) Sputtering 1771
Radius of Curvature 1771
Random Method 1771
Rarefaction Parameter 1771
Rarefied Flow 1771
Rarefied Gas Dynamics 1771
Rayleigh Flow 1772
Rayleigh Instability 1772
Rayleigh–Taylor Instability 1772
Reacting Electrokinetic Flow 1772
Reaction Condition Control 1772
Reaction Time Control 1772
Reactive Ion Etching (RIE) 1772
Reflective Index 1781
Regular Least Square 1781
Relative Roughness 1781
Relaxation 1781
Relaxation Time of the Viscoelastic Fluid 1781
Relaxor Ferroelectrics 1781
Replica Molding 1781
Reptation Tube 1782
Residual Stress 1782
Resistance Temperature Detectors 1782
Resistance Thermometers 1790
Resistive Heating 1790
Resonance and Antiresonance Frequencies 1790
Reynolds Number 1790
RGB 1791
Rheological Fluid Flow in Microchannels 1791
Rheology 1791
Rheometer 1791
RIE Lag 1791
Rosensweig Instability 1791
Rotary Peristaltic Pump 1791

Rotating Channel Flow 1791
Rough Channels 1791
Roughness 1791
Roughness Effect on Microscale Transport 1792
RTD 1795
Rutherford Backscattering Spectrometry (RBS) 1795
Sample Handling 1797
Sample Pre-Fractionation 1797
Sample Preparation 1797
Sample Purification 1797
Sample Purification Using Magnetic Particles 1797
Sample Transport 1798
Sampling 1798
Sampling Unit 1798
Sand Blasting 1798
Satellite Droplets 1798
Saturated Flow Boiling 1798
Scanning Electron Microscopy (SEM) 1798
Scanning Probe Measurement 1798
Scanning Probe Microscopy 1799
Scattered Light Intensity 1804
Segmented (Droplet-Based) Flow 1804
Segmented Flow 1804
Selective Silicon Etching 1804
Self-Assembled Monolayer 1805
Self-Assembly 1805
Self-Assembly Fabrication 1805
Self-Diffusion 1806
Semiconductor Nanocrystals 1806
Semiconductor Nanoparticles 1806
Sensing and Actuation 1806
Serpentine Microchannel Flow 1806
SERS 1806
SERS-Based Biosensors 1806
Shear 1806
Shear-Driven Flow 1806
Shear-Driven Micro- and Nanofluidics 1807
Shear Flows 1816
Shear Stress 1816
Shear Stress Sensors 1816
Shockwave 1828
Shockwaves in Microchannels 1829
Shunt Capacitance 1839
Signal Attenuation 1839
Silicon Dioxide Growth 1839
Silicon Etching 1839
Silicon Micromachining 1839
Simulating Migration of Polymer Chains, Methods 1846
Single Cell Analysis in Microfluidic Devices 1851
Single Cell Impedance Spectroscopy 1860
Single Crystal 1860
Single-Phase Convective Flows in Microchannels 1860
Single-Phase Forced Convection in Microchannels 1860
Single-Phase Gaseous Flow 1860
Slip Boundary 1863
Slip Flow Regime 1863
Slip Velocity 1863
Slope Method 1863
Slug Flow 1863
Smart Skin 1863
Smoluchowski Equation 1863
Smoothing Function 1864
SNP on Chip – Micro- and Nanofluidics for Single Nucleotide Polymorphism Discrimination 1864
Soda-Lime Glass 1869
Sodium Glass 1869
Sodium Silicate Glass 1869
Sol–Gel Technique 1869
Solid Phase Extraction 1874
Solutal Marangoni 1874
Solution Reservoirs on Chips 1874
Soret 1874
Soret Effect 1874
Space Charge 1874
Specific Impulse 1874
Spectral Analysis 1874
Spectral Approximation 1874
Spectral Methods 1874
Spectral Response 1880
Spectral Responsivity 1880
Spectrophotometer 1880
Spectrophotometric Analysis 1880
Spectrophotometric Measurement 1881
Spectrophotometry 1881
Spectroscopy 1881
Speed of Sound 1881
Spinning-Disk Confocal Microscopy 1881
Spinodal Decomposition 1881
Spiral Microchannel Flow 1881
Spontaneous Electrowetting 1881
Spontaneous Polarization 1881
SPR 1881
SPRT 1881
Sputter Etching 1881
Sputtering for Film Deposition 1882
Sputter Yield 1888
Stability 1888
Stack Actuator 1888
Stagnation Conditions 1888
Standard Deviation 1888
Static Electrowetting 1888

Stationary Phases in Microchannels 1888
Statistical Sampling Method 1889
Steady Streaming 1889
Stem Cell Isolation 1889
Stem Cell Reprogramming 1889
Stem Cell Tissue Engineering 1890
Stereolithography 1890
Stokes Approximation 1890
Stokes Shift 1890
Stotz–Wien Effect 1890
Streaming Current 1890
Streaming Current and Electroviscosity 1890
Streaming Dielectrophoresis 1898
Stroke 1898
Stroke Volume 1898
Subcooled Flow Boiling 1898
Subdynamic Regime 1898
Superfast Electrophoresis 1899
Super-Limiting Current 1899
Superparamagnetism 1899
Supersonic Micro-Nozzles 1899
Surface Acoustic Waves 1910
Surface Capturing 1910
Surface Change 1910
Surface-Charge Patterning Techniques 1910
Surface Chemistry Technique 1913
Surface Conductance 1913
Surface Conductivity 1913
Surface Conductivity Measurement 1913
Surface-Directed Capillary Flow Systems 1922
Surface Electric Conductance 1931
Surface Enhanced Raman Scattering (SERS) 1931
Surface Evolver 1931
Surface Features to Enhance Transport 1932
Surface Forces 1932
Surface Lipid Translocation 1932
Surface Micromachining 1932
Surface Modification, Methods 1932
Surface Plasmon Resonance Sensors 1938
Surface Potential 1944
Surface Roughness Measurement 1944
Surface Tension, Capillarity and Contact Angle 1948
Surface Tension-Confined Confined Microfluidics 1955
Surface Tension Driven Filling 1955
Surface Tension Driven Flow 1955
Surface Texture 1969
Surface Topography 1969
Surface Tracking 1969
Surface Transformation 1969
Surface Treatment 1969
Suspensions 1969
Switching Etching 1969
Synthesis of Biological Molecules in Microfluidics 1969
Synthesis of Polymer Molecules Using Microfluidics 1969
Synthetic Jet 1969
Tandem MS 1971
Taylor–Aris Dispersion 1971
Taylor Bubble Flow 1971
Taylor Dispersion 1971
Taylor Flow 1971
Taylor Flow in Microchannels 1971
TCR 1976
Temperature Coefficient of Resistance 1976
Temperature Control 1976
Temperature Control in Microfluidic Systems 1976
Temperature Control System in Microfluidic Chips 1980
Temperature Effects on the Zeta Potential 1980
Temperature Gradient Focusing 1987
Temperature Gradient Generation and Control 1993
Temperature Measurement, Methods 1994
Temperature Measurement Using Fluorescence 2005
Temperature Probes 2005
Temperature-Sensitive Hydrogels 2006
Temperature Sensitive Resistor 2009
Temperature Sensors 2009
Temporal Averaging 2009
Terminal Velocity 2009
Test 2009
Thermal Anemometer 2009
Thermal Bonding 2010
Thermal Bubbles 2010
Thermal Capacitive Flow Sensor 2017
Thermal Conductivity 2017
Thermal Control in Microfluidic Modules 2017
Thermal Creep Coefficient 2017
Thermal Diffusion 2017
Thermal Flow Sensors 2017
Thermal Fusion Bonding 2018
Thermal Gradient Focusing 2018
Thermal Lens Effect 2018
Thermal Lensing, Detection 2018
Thermally Actuated Mechanical Valves 2025
Thermally Driven Mechanical Valves 2025
Thermally-Sensitive Hydrogels 2025
Thermal Marangoni Effect 2025
Thermal Mechanical Valves 2025
Thermal Oxidation 2025
Thermal Pumping 2025
Thermal Slip Coefficient 2025
Thermistors 2025

Thermocapacitive Flow Sensor 2025
Thermocapillarity 2032
Thermocapillary Actuation 2036
Thermocapillary Convection 2037
Thermocapillary Effect 2037
Thermocapillary Pumping 2037
Thermocapillary Shear Stress 2040
Thermochromic Liquid Crystals 2040
Thermocouples 2040
Thermodiffusion 2040
Thermoelectric Effect 2040
Thermoelectric Flow Sensors 2040
Thermoelements 2047
Thermoforming 2047
Thermomechanical Valves 2047
Thermometry 2061
Thermophoresis 2061
Thermopneumatic Membrane Valve 2064
Thermopneumatic Valve 2064
Thermoresistive Flow Sensors 2065
Thermosensitive Hydrogels 2072
Thick Film Lithography 2072
Thick-Film Piezoelectric Actuation 2072
Thick Resist Lithography 2073
Thin-Film Actuation 2079
Three-Dimensional Electrodes 2079
Three-Dimensional Patterning 2083
Threshold Filter 2083
Throat 2083
Throw 2083
Time-Dependent Density Functional Theory (TDFT) 2083
Time-of-Flight Filter 2083
Time of Flight Ion Mobility Spectrometry 2083
Time-of-Flight Mass Spectrometer 2083
Time-Gated Fluorescence Detection 2083
Time-Multiplexed Deep Etching 2084
Time-Multiplexed Plasma Etching 2084
TIRF 2084
TIRFM 2084
TIRM 2084
TIRV 2084
T-Junction 2084
TLCs 2085
TOF-MS 2085
Topographical Manipulation 2085
Torr 2085
Total Internal Reflection Fluorescence (Microscopy) 2085
Total Internal Reflection Velocimetry 2085
Tracers 2085
Transesterification 2085
Transferring Samples to Chips, Techniques 2085
Transitional Microchannels 2093
Transitional Nanochannels 2093
Transitional Regime 2093
Transition Flow 2093
Transition in Microchannels 2093
Transition to Turbulence in Microchannels 2093
Translocation of Phosphatidylserine 2095
Transmission-Line Model 2095
Transmittance 2095
Transport of Droplets by Acoustics 2096
Transport of Droplets by Thermal Capillarity 2104
Transverse Electrophoresis 2110
Trapping Dielectrophoresis 2110
Traveling-Wave Electro-Osmosis 2110
Traveling-Wave Pump 2110
Turbulence 2111
Turbulence Control (Microflap, Microballoon, Microsynthetic Jet) 2111
Turbulence in Microchannels 2119
Turbulent Flows 2126
Turbulent Shear Stress 2126
Two-Faced Particle 2126
Two-Fluid Stratified Flow 2126
Two Phase Flow 2126
Two-Phase Flow Driven by Pressure 2126
Ultra High-Throughput Screening System 2127
Ultrasonic Concentration 2127
Ultrasonic Machining 2127
Ultrasonic Material Removal 2128
Ultrasonic Particle Manipulation 2128
Ultrasonic Pumps 2128
Ultrasonic Separation 2129
Unbalanced AC field 2129
Unimorph 2129
Unit Impulse Function 2129
Unmanned Rotorcraft 2129
Unmixing 2129
UV-LIGA 2129
Valve 2131
Valveless Pumps 2131
Valve-Less Rectification Pumps 2131
Van-der-Waals Attraction 2139
Vapor Bubbles 2139
Vaporization 2140
Velocimetry 2140
Velocity Distribution Function 2140
Velocity Sensors 2140
Venturi Diode 2147
V-Groove 2147
Viscoelastic 2147
Viscoelasticity 2147

Viscometer 2155
Viscosity 2155
Viscous Dissipation 2155
Viscous Heating 2164
Viscous Pump 2169
Viscous Slip Coefficient 2170
Visualization Based on Molecular Tagging Methods 2170
Voltage Clamp 2177
Volume of Fluid (VOF) Method 2177
Volume Illumination 2177
Volume Tracking 2178
Vortex Diode 2178
Vortex Pair 2178
Vortex Ring 2178
Vortices 2178
Wafer Bonding 2179
Wall Shear Stress 2183
Wang-Chang–Uhlenbeck Equation 2183
Water Management in Micro DMFCs 2183
Waveguide Propulsion 2184
Waveguide Trapping 2184
Weak Formulation 2185
Weber Number 2185
Weighted Least Square 2185
Weights and Measures 2185
Wet Chemical Etch 2185
Wet Etching 2185
Wettability Patterning 2186
Wetting Phenomenon 2186
Wetting and Spreading 2186
Wetting on Structured Substrates 2196
Wien Filter 2196
World-to-Chip Interface 2196
X-Ray Diffraction (XRD) 2197
Zeta-Potential 2199
Zeta Potential Measurement 2199
Zinc Oxide 2207

tler
HANDBOOK OF NANOPHYSICS
ectronics
nd
hotonics

HANDBOOK OF NANOPHYSICS

Nanoelectronics and Nanophotonics



Edited by

Klaus D. Sattler

CRC Press
Taylor & Francis Group

8/4/10 4:30 PM

HANDBOOK OF NANOPHYSICS

6

Handbook of Nanophysics

Handbook of Nanophysics: Principles and Methods

Handbook of Nanophysics: Clusters and Fullerenes

Handbook of Nanophysics: Nanoparticles and Quantum Dots

Handbook of Nanophysics: Nanotubes and Nanowires

Handbook of Nanophysics: Functional Nanomaterials

Handbook of Nanophysics: Nanoelectronics and Nanophotonics

Handbook of Nanophysics: Nanomedicine and Nanorobotics

HANDBOOK OF NANOPHYSICS

6

Nanoelectronics and Nanophotonics

Edited by

Klaus D. Sattler

CRC Press
Taylor & Francis Group
Boca Raton London New York

CRC Press is an imprint of the
Taylor & Francis Group, an **informa** business

MATLAB® is a trademark of The MathWorks, Inc. and is used with permission. The MathWorks does not warrant the accuracy of the text or exercises in this book. This book's use or discussion of MATLAB® software or related products does not constitute endorsement or sponsorship by The MathWorks of a particular pedagogical approach or particular use of the MATLAB® software.

CRC Press
Taylor & Francis Group
6000 Broken Sound Parkway NW, Suite 300
Boca Raton, FL 33487-2742

© 2011 by Taylor and Francis Group, LLC
CRC Press is an imprint of Taylor & Francis Group, an Informa business

No claim to original U.S. Government works

Printed in the United States of America on acid-free paper
10 9 8 7 6 5 4 3 2 1

International Standard Book Number: 978-1-4200-7550-2 (Hardback)

This book contains information obtained from authentic and highly regarded sources. Reasonable efforts have been made to publish reliable data and information, but the author and publisher cannot assume responsibility for the validity of all materials or the consequences of their use. The authors and publishers have attempted to trace the copyright holders of all material reproduced in this publication and apologize to copyright holders if permission to publish in this form has not been obtained. If any copyright material has not been acknowledged please write and let us know so we may rectify in any future reprint.

Except as permitted under U.S. Copyright Law, no part of this book may be reprinted, reproduced, transmitted, or utilized in any form by any electronic, mechanical, or other means, now known or hereafter invented, including photocopying, microfilming, and recording, or in any information storage or retrieval system, without written permission from the publishers.

For permission to photocopy or use material electronically from this work, please access www.copyright.com (http://www.copyright.com/) or contact the Copyright Clearance Center, Inc. (CCC), 222 Rosewood Drive, Danvers, MA 01923, 978-750-8400. CCC is a not-for-profit organization that provides licenses and registration for a variety of users. For organizations that have been granted a photocopy license by the CCC, a separate system of payment has been arranged.

Trademark Notice: Product or corporate names may be trademarks or registered trademarks, and are used only for identification and explanation without intent to infringe.

Library of Congress Cataloging-in-Publication Data

Handbook of nanophysics. Nanoelectronics and nanophotonics / editor, Klaus D. Sattler.
p. cm.
"A CRC title."
Includes bibliographical references and index.
ISBN 978-1-4200-7550-2 (alk. paper)
1. Nanoelectronics--Handbooks, manuals, etc. 2. Nanophotonics--Handbooks, manuals, etc. I. Sattler, Klaus D. II. Title.

TK7874.84.H36 2010
621.381--dc22 2010001108

Visit the Taylor & Francis Web site at
http://www.taylorandfrancis.com

and the CRC Press Web site at
http://www.crcpress.com

Contents

Preface ix
Acknowledgments xi
Editor xiii
Contributors xv

PART I Computing and Nanoelectronic Devices

1 Quantum Computing in Spin Nanosystems **1**-1
Gabriel González and Michael N. Leuenberger

2 Nanomemories Using Self-Organized Quantum Dots **2**-1
Martin Geller, Andreas Marent, and Dieter Bimberg

3 Carbon Nanotube Memory Elements **3**-1
Vincent Meunier and Bobby G. Sumpter

4 Ferromagnetic Islands **4**-1
Arndt Remhof, Andreas Westphalen, and Hartmut Zabel

5 A Single Nano-Dot Embedded in a Plate Capacitor **5**-1
Gilles Micolau and Damien Deleruyelle

6 Nanometer-Sized Ferroelectric Capacitors **6**-1
Nikolay A. Pertsev, Adrian Petraru, and Hermann Kohlstedt

7 Superconducting Weak Links Made of Carbon Nanostructures **7**-1
Vincent Bouchiat

8 Micromagnetic Modeling of Nanoscale Spin Valves **8**-1
Bruno Azzerboni, Giancarlo Consolo, and Giovanni Finocchio

9 Quantum Spin Tunneling in Molecular Nanomagnets **9**-1
Gabriel González and Michael N. Leuenberger

10 Inelastic Electron Transport through Molecular Junctions **10**-1
Natalya A. Zimbovskaya

11 Bridging Biomolecules with Nanoelectronics **11**-1
Kien Wen Sun and Chia-Ching Chang

PART II Nanoscale Transistors

12 Transistor Structures for Nanoelectronics 12-1
Jean-Pierre Colinge and Jim Greer

13 Metal Nanolayer-Base Transistor 13-1
André Avelino Pasa

14 ZnO Nanowire Field-Effect Transistors 14-1
Woong-Ki Hong, Gunho Jo, Sunghoon Song, Jongsun Maeng, and Takhee Lee

15 C_{60} Field Effect Transistors 15-1
Akihiro Hashimoto

16 The Cooper-Pair Transistor 16-1
José Aumentado

PART III Nanolithography

17 Multispacer Patterning: A Technology for the Nano Era 17-1
Gianfranco Cerofolini, Elisabetta Romano, and Paolo Amato

18 Patterning and Ordering with Nanoimprint Lithography 18-1
Zhijun Hu and Alain M. Jonas

19 Nanoelectronics Lithography 19-1
Stephen Knight, Vivek M. Prabhu, John H. Burnett, James Alexander Liddle, Christopher L. Soles, and Alain C. Diebold

20 Extreme Ultraviolet Lithography 20-1
Obert R. Wood II

PART IV Optics of Nanomaterials

21 Cathodoluminescence of Nanomaterials 21-1
Naoki Yamamoto

22 Optical Spectroscopy of Nanomaterials 22-1
Yoshihiko Kanemitsu

23 Nanoscale Excitons and Semiconductor Quantum Dots 23-1
Vanessa M. Huxter, Jun He, and Gregory D. Scholes

24 Optical Properties of Metal Clusters and Nanoparticles 24-1
Emmanuel Cottancin, Michel Broyer, Jean Lermé, and Michel Pellarin

25 Photoluminescence from Silicon Nanostructures 25-1
Amir Sa'ar

26 Polarization-Sensitive Nanowire and Nanorod Optics 26-1
Harry E. Ruda and Alexander Shik

27 Nonlinear Optics with Clusters 27-1
Sabyasachi Sen and Swapan Chakrabarti

28 Second-Harmonic Generation in Metal Nanostructures 28-1
Marco Finazzi, Giulio Cerullo, and Lamberto Duò

29 Nonlinear Optics in Semiconductor Nanostructures **29**-1
Mikhail Erementchouk and Michael N. Leuenberger

30 Light Scattering from Nanofibers **30**-1
Vladimir G. Bordo

31 Biomimetics: Photonic Nanostructures **31**-1
Andrew R. Parker

PART V Nanophotonic Devices

32 Photon Localization at the Nanoscale **32**-1
Kiyoshi Kobayashi

33 Operations in Nanophotonics **33**-1
Suguru Sangu and Kiyoshi Kobayashi

34 System Architectures for Nanophotonics **34**-1
Makoto Naruse

35 Nanophotonics for Device Operation and Fabrication **35**-1
Tadashi Kawazoe and Motoichi Ohtsu

36 Nanophotonic Device Materials **36**-1
Takashi Yatsui and Wataru Nomura

37 Waveguides for Nanophotonics **37**-1
Jan Valenta, Tomáš Ostatnický, and Ivan Pelant

38 Biomolecular Neuronet Devices **38**-1
Grigory E. Adamov and Evgeny P. Grebennikov

PART VI Nanoscale Lasers

39 Nanolasers **39**-1
Marek S. Wartak

40 Quantum Dot Laser **40**-1
Frank Jahnke

41 Mode-Locked Quantum-Dot Lasers **41**-1
Maria A. Cataluna and Edik U. Rafailov

Index **Index**-1

Preface

The *Handbook of Nanophysics* is the first comprehensive reference to consider both fundamental and applied aspects of nanophysics. As a unique feature of this work, we requested contributions to be submitted in a tutorial style, which means that state-of-the-art scientific content is enriched with fundamental equations and illustrations in order to facilitate wider access to the material. In this way, the handbook should be of value to a broad readership, from scientifically interested general readers to students and professionals in materials science, solid-state physics, electrical engineering, mechanical engineering, computer science, chemistry, pharmaceutical science, biotechnology, molecular biology, biomedicine, metallurgy, and environmental engineering.

What Is Nanophysics?

Modern physical methods whose fundamentals are developed in physics laboratories have become critically important in nanoscience. Nanophysics brings together multiple disciplines, using theoretical and experimental methods to determine the physical properties of materials in the nanoscale size range (measured by millionths of a millimeter). Interesting properties include the structural, electronic, optical, and thermal behavior of nanomaterials; electrical and thermal conductivity; the forces between nanoscale objects; and the transition between classical and quantum behavior. Nanophysics has now become an independent branch of physics, simultaneously expanding into many new areas and playing a vital role in fields that were once the domain of engineering, chemical, or life sciences.

This handbook was initiated based on the idea that breakthroughs in nanotechnology require a firm grounding in the principles of nanophysics. It is intended to fulfill a dual purpose. On the one hand, it is designed to give an introduction to established fundamentals in the field of nanophysics. On the other hand, it leads the reader to the most significant recent developments in research. It provides a broad and in-depth coverage of the physics of nanoscale materials and applications. In each chapter, the aim is to offer a didactic treatment of the physics underlying the applications alongside detailed experimental results, rather than focusing on particular applications themselves.

The handbook also encourages communication across borders, aiming to connect scientists with disparate interests to begin interdisciplinary projects and incorporate the theory and methodology of other fields into their work. It is intended for readers from diverse backgrounds, from math and physics to chemistry, biology, and engineering.

The introduction to each chapter should be comprehensible to general readers. However, further reading may require familiarity with basic classical, atomic, and quantum physics. For students, there is no getting around the mathematical background necessary to learn nanophysics. You should know calculus, how to solve ordinary and partial differential equations, and have some exposure to matrices/linear algebra, complex variables, and vectors.

External Review

All chapters were extensively peer reviewed by senior scientists working in nanophysics and related areas of nanoscience. Specialists reviewed the scientific content and nonspecialists ensured that the contributions were at an appropriate technical level. For example, a physicist may have been asked to review a chapter on a biological application and a biochemist to review one on nanoelectronics.

Organization

The *Handbook of Nanophysics* consists of seven books. Chapters in the first four books (*Principles and Methods*, *Clusters and Fullerenes*, *Nanoparticles and Quantum Dots*, and *Nanotubes and Nanowires*) describe theory and methods as well as the fundamental physics of nanoscale materials and structures. Although some topics may appear somewhat specialized, they have been included given their potential to lead to better technologies. The last three books (*Functional Nanomaterials*, *Nanoelectronics and Nanophotonics*, and *Nanomedicine and Nanorobotics*) deal with the technological applications of nanophysics. The chapters are written by authors from various fields of nanoscience in order to encourage new ideas for future fundamental research.

After the first book, which covers the general principles of theory and measurements of nanoscale systems, the organization roughly follows the historical development of nanoscience. *Cluster* scientists pioneered the field in the 1980s, followed by extensive work on *fullerenes*, *nanoparticles*, and *quantum dots* in the 1990s. Research on *nanotubes* and *nanowires* intensified in subsequent years. After much basic research, the interest in applications such as the *functions of nanomaterials* has grown. Many bottom-up and top-down techniques for nanomaterial and nanostructure generation were developed and made possible the development of *nanoelectronics* and *nanophotonics*. In recent years, real applications for *nanomedicine* and *nanorobotics* have been discovered.

MATLAB® is a registered trademark of The MathWorks, Inc. For product information, Please contact:

The MathWorks, Inc.
3 Apple Hill Drive
Natick, MA, 01760-2098 USA
Tel: 508-647-7000
Fax: 508-647-7001
E-mail: info@mathworks.com
Web: www.mathworks.com

Acknowledgments

Many people have contributed to this book. I would like to thank the authors whose research results and ideas are presented here. I am indebted to them for many fruitful and stimulating discussions. I would also like to thank individuals and publishers who have allowed the reproduction of their figures. For their critical reading, suggestions, and constructive criticism, I thank the referees. Many people have shared their expertise and have commented on the manuscript at various stages. I consider myself very fortunate to have been supported by Luna Han, senior editor of the Taylor & Francis Group, in the setup and progress of this work. I am also grateful to Jessica Vakili, Jill Jurgensen, Joette Lynch, and Glenon Butler for their patience and skill with handling technical issues related to publication. Finally, I would like to thank the many unnamed editorial and production staff members of Taylor & Francis for their expert work.

Klaus D. Sattler
Honolulu, Hawaii

Editor

Klaus D. Sattler pursued his undergraduate and master's courses at the University of Karlsruhe in Germany. He received his PhD under the guidance of Professors G. Busch and H.C. Siegmann at the Swiss Federal Institute of Technology (ETH) in Zurich, where he was among the first to study spin-polarized photoelectron emission. In 1976, he began a group for atomic cluster research at the University of Konstanz in Germany, where he built the first source for atomic clusters and led his team to pioneering discoveries such as "magic numbers" and "Coulomb explosion." He was at the University of California, Berkeley, for three years as a Heisenberg Fellow, where he initiated the first studies of atomic clusters on surfaces with a scanning tunneling microscope.

Dr. Sattler accepted a position as professor of physics at the University of Hawaii, Honolulu, in 1988. There, he initiated a research group for nanophysics, which, using scanning probe microscopy, obtained the first atomic-scale images of carbon nanotubes directly confirming the graphene network. In 1994, his group produced the first carbon nanocones. He has also studied the formation of polycyclic aromatic hydrocarbons (PAHs) and nanoparticles in hydrocarbon flames in collaboration with ETH Zurich. Other research has involved the nanopatterning of nanoparticle films, charge density waves on rotated graphene sheets, band gap studies of quantum dots, and graphene foldings. His current work focuses on novel nanomaterials and solar photocatalysis with nanoparticles for the purification of water.

Among his many accomplishments, Dr. Sattler was awarded the prestigious Walter Schottky Prize from the German Physical Society in 1983. At the University of Hawaii, he teaches courses in general physics, solid-state physics, and quantum mechanics.

In his private time, he has worked as a musical director at an avant-garde theater in Zurich, composed music for theatrical plays, and conducted several critically acclaimed musicals. He has also studied the philosophy of Vedanta. He loves to play the piano (classical, rock, and jazz) and enjoys spending time at the ocean, and with his family.

Contributors

Grigory E. Adamov
Open Joint-Stock Company
Central Scientific Research Institute of Technology “Technomash”
Moscow, Russia

Paolo Amato
Numonyx

and

Department of Materials Science
University of Milano-Bicocca
Milano, Italy

José Aumentado
National Institute of Standards and Technology
Boulder, Colorado

Bruno Azzerboni
Department of Matter Physics and Electronic Engineering
Faculty of Engineering
University of Messina
Messina, Italy

Dieter Bimberg
Institut für Festkörperphysik
Technische Universität Berlin
Berlin, Germany

Vladimir G. Bordo
A.M. Prokhorov General Physics Institute
Russian Academy of Sciences
Moscow, Russia

Vincent Bouchiat
Nanosciences Department
Centre National de la Recherche Scientifique
Néel-Institut
Grenoble, France

Michel Broyer
Laboratoire de Spectrométrie Ionique et Moléculaire
Centre National de la Recherche Scientifique
Université de Lyon
Villeurbanne, France

John H. Burnett
Atomic Physics Division
National Institute of Standards and Technology
Gaithersburg, Maryland

Maria A. Cataluna
Division of Electronic Engineering and Physics
School of Engineering, Physics and Mathematics
University of Dundee
Dundee, United Kingdom

Gianfranco Cerofolini
Department of Materials Science
University of Milano-Bicocca
Milano, Italy

Giulio Cerullo
Dipartimento di Fisica
Politecnico di Milano
Milano, Italy

Swapan Chakrabarti
Department of Chemistry
University of Calcutta
Kolkata, West Bengal, India

Chia-Ching Chang
Department of Biological Science and Technology
National Chiao Tung University
Hsinchu, Taiwan

and

Institute of Physics
Academia Sinica
Taipei, Taiwan

Jean-Pierre Colinge
Tyndall National Institute
University College Cork
Cork, Ireland

Giancarlo Consolo
Department of Matter Physics and Electronic Engineering
Faculty of Engineering
University of Messina
Messina, Italy

Emmanuel Cottancin
Laboratoire de Spectrométrie Ionique et Moléculaire
Centre National de la Recherche Scientifique
Université de Lyon
Villeurbanne, France

Damien Deleruyelle
Centre National de la Recherche Scientifique
Institut Matériaux Microélectronique Nanosciences de Provence
Universités d’Aix Marseille
Marseille, France

Alain C. Diebold
College of Nanoscale Science and Engineering
University at Albany
Albany, New York

Lamberto Duò
Dipartimento di Fisica
Politecnico di Milano
Milano, Italy

Mikhail Erementchouk
NanoScience Technology Center

and

Department of Physics
University of Central Florida
Orlando, Florida

Marco Finazzi
Dipartimento di Fisica
Politecnico di Milano
Milano, Italy

Giovanni Finocchio
Department of Matter Physics
and Electronic Engineering
Faculty of Engineering
University of Messina
Messina, Italy

Martin Geller
Experimental Physics

and

Center for Nanointegration
Duisburg-Essen
University of Duisburg-Essen
Duisburg, Germany

Gabriel González
NanoScience Technology Center

and

Department of Physics
University of Central Florida
Orlando, Florida

Evgeny P. Grebennikov
Open Joint-Stock Company
Central Scientific Research Institute
of Technology "Technomash"
Moscow, Russia

Jim Greer
Tyndall National Institute
University College Cork
Cork, Ireland

Akihiro Hashimoto
Department of Electrical and Electronics
Engineering
Graduate School of Engineering
University of Fukui
Fukui, Japan

Jun He
Department of Chemistry
Institute for Optical Sciences

and

Centre for Quantum Information
and Quantum Control
University of Toronto
Toronto, Ontario, Canada

Woong-Ki Hong
Department of Materials Science
and Engineering
Gwangju Institute of Science
and Technology
Gwangju, Korea

Zhijun Hu
Center for Soft Matter Physics
and Interdisciplinary Research
Soochow University
Suzhou, China

Vanessa M. Huxter
Department of Chemistry
Institute for Optical Sciences

and

Centre for Quantum Information
and Quantum Control
University of Toronto
Toronto, Ontario, Canada

Frank Jahnke
Institute for Theoretical Physics
University of Bremen
Bremen, Germany

Gunho Jo
Department of Materials Science
and Engineering
Gwangju Institute of Science
and Technology
Gwangju, Korea

Alain M. Jonas
Institute of Condensed Matter
and Nanosciences
Division of Bio- and Soft Matter
Catholic University of Louvain
Louvain-la-Neuve, Belgium

Yoshihiko Kanemitsu
Institute for Chemical Research
Kyoto University
Uji, Kyoto, Japan

Tadashi Kawazoe
Department of Electrical Engineering
and Information Systems
School of Engineering
The University of Tokyo
Tokyo, Japan

Stephen Knight
Office of Microelectronics Programs
National Institute of Standards
and Technology
Gaithersburg, Maryland

Kiyoshi Kobayashi
Department of Electrical Engineering
and Information Systems
The University of Tokyo
Tokyo, Japan

and

Core Research of Evolutional Science
and Technology
Japan Science and Technology

and

Department of Electrical and Electronic
Engineering
University of Yamanashi
Kofu, Japan

Hermann Kohlstedt
Christian-Albrechts-Universität Zu Kiel
Faculty of Engineering Nanoelectronics
Kiel, Germany

Takhee Lee
Department of Materials Science
and Engineering
Gwangju Institute of Science
and Technology
Gwangju, Korea

Jean Lermé
Laboratoire de Spectrométrie Ionique et Moléculaire
Centre National de la Recherche Scientifique
Université de Lyon
Villeurbanne, France

Michael N. Leuenberger
NanoScience Technology Center

and

Department of Physics
University of Central Florida
Orlando, Florida

James Alexander Liddle
Center for Nanoscale Science and Technology
National Institute of Standards and Technology
Gaithersburg, Maryland

Jongsun Maeng
Department of Materials Science and Engineering
Gwangju Institute of Science and Technology
Gwangju, Korea

Andreas Marent
Institut für Festkörperphysik
Technische Universität Berlin
Berlin, Germany

Vincent Meunier
Oak Ridge National Laboratory
Oak Ridge, Tennessee

Gilles Micolau
Institut Matériaux Microélectronique Nanosciences de Provence
Centre National de la Recherche Scientifique
Universités d'Aix Marseille
Marseille, France

Makoto Naruse
National Institute of Information and Communications Technology
Koganei, Japan

and

Department of Electrical Engineering and Information Systems
School of Engineering
The University of Tokyo
Tokyo, Japan

Wataru Nomura
School of Engineering
The University of Tokyo
Tokyo, Japan

Motoichi Ohtsu
Department of Electrical Engineering and Information Systems
School of Engineering
The University of Tokyo
Tokyo, Japan

Tomáš Ostatnický
Faculty of Mathematics and Physics
Department of Chemical Physics and Optics
Charles University
Prague, Czech Republic

Andrew R. Parker
Department of Zoology
The Natural History Museum
London, United Kingdom

and

School of Biological Science
University of Sydney
Sydney, New South Wales, Australia

André Avelino Pasa
Laboratório de Filmes Finos e Superfícies
Departamento de Física
Universidade Federal de Santa Catarina
Santa Catarina, Brazil

Ivan Pelant
Institute of Physics
Academy of Sciences of the Czech Republic
Prague, Czech Republic

Michel Pellarin
Laboratoire de Spectrométrie Ionique et Moléculaire
Centre National de la Recherche Scientifique
Université de Lyon
Villeurbanne, France

Nikolay A. Pertsev
A.F. Ioffe Physico-Technical Institute
Russian Academy of Sciences
St. Petersburg, Russia

Adrian Petraru
Christian-Albrechts-Universität Zu Kiel
Faculty of Engineering Nanoelectronics
Kiel, Germany

Vivek M. Prabhu
Polymers Division
National Institute of Standards and Technology
Gaithersburg, Maryland

Edik U. Rafailov
Division of Electronic Engineering and Physics
School of Engineering, Physics and Mathematics
University of Dundee
Dundee, United Kingdom

Arndt Remhof
Division of Hydrogen and Energy
Department of Environment, Energy and Mobility
Swiss Federal Laboratories for Materials Testing and Research
Dübendorf, Switzerland

Elisabetta Romano
Department of Materials Science
University of Milano-Bicocca
Milano, Italy

Harry E. Ruda
Centre for Advanced Nanotechnology
University of Toronto
Toronto, Ontario, Canada

Amir Sa'ar
Racah Institute of Physics

and

The Harvey M. Kruger Family Center for Nanoscience and Nanotechnology
The Hebrew University of Jerusalem
Jerusalem, Israel

Suguru Sangu
Device and Module Technology Development Center
Ricoh Company, Ltd.
Yokohama, Japan

Gregory D. Scholes
Department of Chemistry
Institute for Optical Sciences

and

Centre for Quantum Information and Quantum Control
University of Toronto
Toronto, Ontario, Canada

Sabyasachi Sen
Department of Chemistry
JIS College of Engineering
Kolkata, West Bengal, India

Alexander Shik
Centre for Advanced Nanotechnology
University of Toronto
Toronto, Ontario, Canada

Christopher L. Soles
Polymers Division
National Institute of Standards and Technology
Gaithersburg, Maryland

Sunghoon Song
Department of Materials Science and Engineering
Gwangju Institute of Science and Technology
Gwangju, Korea

Bobby G. Sumpter
Oak Ridge National Laboratory
Oak Ridge, Tennessee

Kien Wen Sun
Department of Applied Chemistry
National Chiao Tung University
Hsinchu, Taiwan

Jan Valenta
Faculty of Mathematics and Physics
Department of Chemical Physics and Optics
Charles University
Prague, Czech Republic

Marek S. Wartak
Department of Physics and Computer Science
Wilfrid Laurier University
Waterloo, Ontario, Canada

Andreas Westphalen
Department of Physics and Astronomy
Institute for Condensed Matter Physics
Ruhr-Universität Bochum
Bochum, Germany

Obert R. Wood II
GLOBALFOUNDRIES
Albany, New York

Naoki Yamamoto
Department of Physics
Tokyo Institute of Technology
Tokyo, Japan

Takashi Yatsui
School of Engineering
The University of Tokyo
Tokyo, Japan

Hartmut Zabel
Department of Physics and Astronomy
Institute for Condensed Matter Physics
Ruhr-Universität Bochum
Bochum, Germany

Natalya A. Zimbovskaya
Department of Physics and Electronics
University of Puerto Rico
Humacao, Puerto Rico

and

Institute for Functional Nanomaterials
University of Puerto Rico
San Juan, Puerto Rico

I

Computing and Nanoelectronic Devices

1 **Quantum Computing in Spin Nanosystems** *Gabriel González and Michael N. Leuenberger* **1**-1
Introduction • Qubits and Quantum Logic Gates • Conditions for the Physical Implementation of Quantum Computing • Zeeman Effects • Atom–Light Interaction • Loss–DiVincenzo Proposal • Quantum Computing with Molecular Magnets • Semiconductor Quantum Dots • Single-Photon Faraday Rotation • Concluding Remarks • Acknowledgments • References

2 **Nanomemories Using Self-Organized Quantum Dots** *Martin Geller, Andreas Marent, and Dieter Bimberg*....... **2**-1
Introduction • Conventional Semiconductor Memories • Nonconventional Semiconductor Memories • Semiconductor Nanomemories • A Nanomemory Based on III–V Semiconductor Quantum Dots • Capacitance Spectroscopy • Charge Carrier Storage in Quantum Dots • Write Times in Quantum Dot Memories • Summary and Outlook • Acknowledgments • References

3 **Carbon Nanotube Memory Elements** *Vincent Meunier and Bobby G. Sumpter*... **3**-1
Introduction • CNFET-Based Memory Elements • NEMS-Based Memory • Electromigration CNT-Based Data Storage • General Conclusions • Acknowledgments • References

4 **Ferromagnetic Islands** *Arndt Remhof, Andreas Westphalen, and Hartmut Zabel*.. **4**-1
Introduction • Background • State of the Art • Summary and Discussion • References

5 **A Single Nano-Dot Embedded in a Plate Capacitor** *Gilles Micolau and Damien Deleruyelle*................................ **5**-1
Introduction • Studied Configuration: Geometry and Notations • Metallic Dot • Semiconductor Dot: Theoretical Approach • Finite Element Modeling of a Silicon Quantum Dot • Conclusion • Appendix A: A Numerical Validation of the Semi-Analytical Approach • References

6 **Nanometer-Sized Ferroelectric Capacitors** *Nikolay A. Pertsev, Adrian Petraru, and Hermann Kohlstedt*............ **6**-1
Introduction • Fundamentals of Ferroelectricity • Deposition and Patterning • Characterization of Ferroelectric Films and Capacitors • Physical Phenomena in Ferroelectric Capacitors • Future Perspective • Summary and Outlook • References

7 **Superconducting Weak Links Made of Carbon Nanostructures** *Vincent Bouchiat*... **7**-1
Introduction • Superconducting Transport through a Weak Link • Superconducting Transport in a Carbon Nanotube Weak Link • Nanotube-Based Superconducting Quantum Interferometers • Graphene-Based Superconducting Weak Links • Fullerene-Based Superconducting Weak Links • Concluding Remarks • Acknowledgment • References

8 **Micromagnetic Modeling of Nanoscale Spin Valves** *Bruno Azzerboni, Giancarlo Consolo, and Giovanni Finocchio* **8**-1
Introduction • Background • Computational Micromagnetics of Nanoscale Spin-Valves: State of the Art • Conclusions and Future Perspective • References

9 **Quantum Spin Tunneling in Molecular Nanomagnets** *Gabriel González and Michael N. Leuenberger* **9**-1
Introduction • Spin Tunneling in Molecular Nanomagnets • Phonon-Assisted Spin Tunneling in Mn_{12} Acetate • Interference between Spin Tunneling Paths in Molecular Nanomagnets • Incoherent Zener Tunneling in Fe_8 • Coherent Néel Vector Tunneling in Antiferromagnetic Molecular Wheels • Berry-Phase Blockade in Single-Molecule Magnet Transistors • Concluding Remarks • Acknowledgment • References

10 Inelastic Electron Transport through Molecular Junctions *Natalya A. Zimbovskaya* **10**-1
Introduction • Coherent Transport • Buttiker Model for Inelastic Transport • Vibration-Induced Inelastic Effects • Dissipative Transport • Polaron Effects: Hysteresis, Switching, and Negative Differential Resistance • Molecular Junction Conductance and Long-Range Electron-Transfer Reactions • Concluding Remarks • References

11 Bridging Biomolecules with Nanoelectronics *Kien Wen Sun and Chia-Ching Chang* **11**-1
Introduction and Background • Preparation of Molecular Magnets • Nanostructured Semiconductor Templates: Nanofabrication and Patterning • Self-Assembling Growth of Molecules on the Patterned Templates • Magnetic Properties of Molecular Nanostructures • Conclusion and Future Perspectives • References

1

Quantum Computing in Spin Nanosystems

1.1 Introduction 1-1
1.2 Qubits and Quantum Logic Gates 1-2
1.3 Conditions for the Physical Implementation of Quantum Computing 1-3
1.4 Zeeman Effects 1-3
Weak External Field • Strong External Field
1.5 Atom–Light Interaction 1-4
Jaynes–Cummings Model
1.6 Loss–DiVincenzo Proposal 1-7
RKKY Interaction
1.7 Quantum Computing with Molecular Magnets 1-9
1.8 Semiconductor Quantum Dots 1-12
Classical Faraday Effect • Quantum Faraday Effect
1.9 Single-Photon Faraday Rotation 1-14
Quantifying the EPR Entanglement • Single Photon Faraday Effect and GHZ Quantum Teleportation • Single-Photon Faraday Effect and Quantum Computing
1.10 Concluding Remarks 1-20
Acknowledgments 1-20
References 1-20

Gabriel González
University of Central Florida

Michael N. Leuenberger
University of Central Florida

1.1 Introduction

The history of quantum computers begins with the articles of Richard Feynman who, in 1982, speculated that quantum systems might be able to perform certain tasks more efficiently than would be possible in classical systems (Feynman, 1982). Feynman was the first to propose a direct application of the laws of quantum mechanics to a realization of quantum algorithms. The fundamentals of quantum computing were introduced and developed by several authors after Feynman's idea. A model and a description of a quantum computer as a quantum Turing machine was developed by Deutsch (1985). In 1994, Shor introduced the quantum algorithm for the integer-number factorization and in 1997, Grover proposed the fast quantum search algorithm (Grover, 1997). Later on, Wooters and Zurek proved the noncloning theorem, which puts definite limits on the quantum computations, but Shor's work challenges all that with the quantum error correction code (Shor, 1995). In the last years, the development of quantum computing has grown to enormous practical importance as an interdisciplinary field, which links the elements of physics, mathematics, and computer science. Currently, various physical models of quantum computers are under intensive study. Several types of elementary quantum computing devices have been developed based on atomic, molecular, optical, and semiconductor physics and technologies.

Before contemplating the physical realization of a quantum computer, it is necessary to decide how information is going to be stored within the system and how the system will process that information during a desired computation. In classical computers, the information is typically carried in microelectronic circuits that store information using the charge properties of electrons. Information processing is carried out by manipulating electrical fields within semiconductor materials in such a way as to perform useful computational tasks. Presently it seems that the most promising physical model for quantum computation is based on the electron's spin. A strong research effort toward the implementation of the electron spin as a new information carrier has been the subject of a new form of electronics based on spin called *spintronics*. Experiments that have been conducted on quantum spin dynamics in semiconductor materials demonstrate that electron spins have several characteristics that are promising for quantum computing applications. Electron spin states possess the following advantages: very long relaxation time in the absence of external fields, fairly long decoherence time $\tau_d \approx 1\,\mu s$, and the possibility of easy spin manipulation by an external magnetic field. These characteristics are very promising since longer decoherence times relax constraints on the switching speeds of quantum gates necessary for reliable error correction. Typically quantum gates are required to switch 10^4 times faster than the loss of qubit coherence. Spin coherent transport over lengths as large as $100\,\mu$m have been reported in semiconductors. This makes electron spin a perfect candidate as an information carrier in semiconductors (Adamowski et al., 2005).

The spin of particles exhibiting quantum behavior is specially suitable for the construction of quantum computers. The electron spin states can be used to construct qubits and logic operations in different ways. They can be constructed either directly with the application of a magnetic field or indirectly with the application of symmetry properties of the many-electron wave function (namely by the resulting singlet or triplet spin states). Traditionally, in nanoelectronic devices, the charge of the electrons has been used to carry and transform information, which makes the interaction of spintronic devices with charge-based devices important for compatibility with existing classical computing schemes. Overall, we can say that spin nanosystems are good candidates for the physical implementation of quantum computation.

1.2 Qubits and Quantum Logic Gates

We know that the information stored in a classical computer can take one of the two values, i.e., 0 or 1, with probability 0 or 1 each. Quantum bits or qubits are the quantum mechanical analogue of classical bits. In contrast, the qubit can be defined as a quantum state vector in a two-dimensional Hilbert space. Suppose $|0\rangle, |1\rangle$ forms a basis for the Hilbert space, then the qubit can be expressed as the superposition of the two states as

$$|\psi\rangle = c_0\,|0\rangle + c_1\,|1\rangle, \tag{1.1}$$

where c_0 and c_1 are complex numbers and the modulus squared of each complex number represents the probability to obtain the qubit $|0\rangle$ or $|1\rangle$, respectively. Additionally, they must satisfy the normalization condition $|c_0|^2 + |c_1|^2 = 1$. Contrary to the classical bit, the quantum bit takes on a continuum of values, which are determined by the probability amplitudes given by c_0 and c_1. If we perform a measurement on qubit $|\psi\rangle$, we obtain either outcome $|0\rangle$ with probability $|c_0|^2$ or outcome $|1\rangle$ with probability $|c_1|^2$. However, if the qubit is prepared to be exactly equal to one of the states of the computational basis, i.e., $|\psi\rangle = |0\rangle$ or $|\psi\rangle = |1\rangle$, then we can predict the exact result of the measurement with probability 1. This nondeterministic characteristic between the general state of the qubit and the precise result of the measurement in the basis state plays an essential role in quantum computations. To carry out a quantum computation, we require at least a two-qubit state, i.e., the states of a two-particle quantum system. The two-qubit states can be constructed as tensor products of the basis states $|0\rangle$, $|1\rangle$. The two-qubit basis consists of the states $|00\rangle$, $|01\rangle$, $|10\rangle$, $|11\rangle$, where in the shorthanded notation $|0\rangle \otimes |1\rangle \equiv |01\rangle$, etc. implied. An arbitrary two-qubit state has the form

$$|\Psi\rangle = c_0\,|00\rangle + c_1\,|00\rangle + c_2\,|10\rangle + c_3\,|11\rangle, \tag{1.2}$$

where the normalization condition takes the form $|c_0|^2 + |c_1|^2 + |c_2|^2 + |c_3|^2 = 1$. Another basic characteristic for quantum computing is the so-called *entanglement*. The two quantum two-level systems can become *entangled* by interacting with each other. This means that we cannot fully describe one system independently of the other. For example, suppose that the state $(|01\rangle - |10\rangle)/\sqrt{2}$ gives a complete description of the whole system. Then a measurement over the first subsystem forces the second subsystem into one of the two states $|0\rangle$ or $|1\rangle$. This means that one measurement over one subsystem influences the other, even though it may be arbitrarily far away.

Qubits can be transformed by unitary transformations (observables) $\mathcal{U}$ that play the role of quantum logic gates and which transforms the initial qubit into a final qubit according to

$$|\Psi_f\rangle = \mathcal{U}\,|\Psi_i\rangle. \tag{1.3}$$

Depending on the type of qubit on which they operate, we deal with either a 2 × 2 or a 4 × 4 matrix. For example, the quantum NOT gate is defined as

$$\mathcal{U}_{\text{NOT}} = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}. \tag{1.4}$$

The effect of the quantum logic gate (4) in the one-qubit state given in Equation 1.1 is to exchange the probability amplitudes i.e.,

$$\mathcal{U}_{\text{NOT}} \begin{pmatrix} c_0 \\ c_1 \end{pmatrix} = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix} \begin{pmatrix} c_0 \\ c_1 \end{pmatrix} = \begin{pmatrix} c_1 \\ c_0 \end{pmatrix}. \tag{1.5}$$

An example of an important quantum logic gate that operates on a two-qubit state is the so-called controlled-NOT gate $\mathcal{U}_{\text{CNOT}}$, for which the first qubit is the control qubit and the second qubit is the target qubit. The controlled-NOT gate transforms the two-qubit basis states as follows:

$$\begin{aligned} &\mathcal{U}_{\text{CNOT}}\,|00\rangle = |00\rangle, \quad \mathcal{U}_{\text{CNOT}}\,|01\rangle = |01\rangle, \\ &\mathcal{U}_{\text{CNOT}}\,|10\rangle = |11\rangle, \quad \text{and} \quad \mathcal{U}_{\text{CNOT}}\,|11\rangle = |10\rangle, \end{aligned} \tag{1.6}$$

which means that the CNOT (conditionalNOT) gate changes the second qubit if and only if the first qubit is in state $|1\rangle$. The matrix representation of the CNOT gate is

$$\mathcal{U}_{\text{CNOT}} = \begin{pmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & 1 \\ 0 & 0 & 1 & 0 \end{pmatrix}. \tag{1.7}$$

It has been shown that the set of logic operations, which consists of all the one-qubit gates and the single two-qubit gate $\mathcal{U}_{\text{CNOT}}$ is universal in the sense that all unitary transformations on

N-qubit states can be expressed by different compositions of the set of universal gates (DiVincenzo, 1995).

Using the concepts of superposition and entanglement, we can describe another important characteristic of quantum computation, which is known as *quantum parallelism*. Quantum parallelism is based on the fact that a single unitary transformation can simultaneously operate on all the qubits in the system. In a sense, it can perform several calculations in a single step. In fact, it can be proved that the computing power of a quantum computer scales exponentially with the number of qubits, whereas a classical computer the scale is only linear.

1.3 Conditions for the Physical Implementation of Quantum Computing

The successful implementation of a quantum computer has to satisfy some basic requirements. These are known as the DiVincenzo criteria and can be summarized in the following way (DiVincenzo, 2001).

1. *Physical realizability of the qubits*. We need to find some quantum property of a scalable physical system in which to encode our information so that it lives long enough to enable us to perform computations.
2. *Initial state preparation*. It should be possible to precisely prepare the initial qubit state.
3. *Isolation*. We need a controlled evolution of the qubit; this will require enough isolation of the qubit from the environment to reduce the effects of decoherence.
4. *Gate implementation*. We need to be able to manipulate the states of individual qubits with reasonable precision, as well as to induce interaction between them in a controlled way, so that the implementation of gates is possible. Also, the gate operation time τ_s has to be much shorter than the decoherence time τ_d, so that $\tau/\tau_d \ll r$, where r is the maximum tolerable error rate for quantum error correction schemes to be effective.
5. *Readout*. We must be able to accurately measure the final qubit state.

The conditions listed above put certain limitations on the quantum computing technology. For example, the complete isolation of the qubit with respect to the environment disables the read/write operations. Therefore, some slight interaction of the quantum system and the environment is necessary. On the other hand, this interaction leads to decay and decoherence processes, which reduce the performance of the quantum computer.

In the decay process, the quantum system jumps in a very short time to a new state, releasing part of its energy to the environment. The decay is characterized by the relaxation time, which for the spin states can be very long. Decoherence is a more subtle process because the energy is conserved but the relative phase of the computational basis is changed. As a result of the decoherence the qubit changes as follows:

$$|\psi\rangle = c_0\,|0\rangle + e^{i\theta}c_1\,|1\rangle, \tag{1.8}$$

where the real number θ denotes the relative phase. The appearance of the nonzero relative phase results due to the coupling between the quantum system and the environment and can lead to significant changes in the measurement process. The ratio of the decoherence time to the elementary operation time τ_s, i.e., $R = \tau_d/\tau_s$, is an approximate measure of the number of computation steps performed before the coupling with the environment destroys the qubit. This ratio changes abruptly for different quantum computing schemes. For example, $R = 10^3$ for the electron states in quantum dots, $R = 10^7$ for nuclear spin sates, and $R = 10^{13}$ for trapped ions.

An important factor that should always be kept in mind when constructing quantum computers is the scalability of the device. We should be able to enlarge the physical device to contain many qubits and still fulfill the DiVincenzo requirements described above.

1.4 Zeeman Effects

An external magnetic field superimposed on an atom perturbs its state in a definite way. The Hamiltonian for such an atom may be divided into the operator $\mathcal{H}_0$ for the unperturbed atom and the perturbation operator $\mathcal{H}'$ due to the magnetic field. The external magnetic field $\vec{H}$ causes the vectors $\vec{L}$ and $\vec{S}$ to precess about its direction. We shall examine the two cases where the magnetic field is weak and is strong.

Let us first write down the perturbation operator explicitly. Consider an electron in the simplest possible atom (hydrogen) rotating around the nucleus. The electron orbit can be regarded as a current loop. The current is the charge per unit time past any fixed point on the orbit, therefore

$$j = \frac{e}{T} = \frac{ev}{2\pi r} = \frac{e(p/m_e)}{2\pi r}, \tag{1.9}$$

where p and m_e are the momentum and mass of the electron, respectively. The magnitude of the magnetic moment of the loop is the current times the enclosed area, i.e., $\mu_{orb} = \pi r^2 j$, therefore

$$\vec{\mu}_{orb} = \frac{e}{2m_e}\vec{r}\times\vec{p} = \frac{\mu_B}{\hbar}\vec{L}, \tag{1.10}$$

where we have introduced the Bohr magneton, $\mu_B = e\hbar/2m_e$. We do not have a good semiclassical picture for spin and therefore we can only conclude that the spin magnetic moment is

$$\vec{\mu}_{sp} = g_s\frac{\mu_B}{\hbar}\vec{S}, \tag{1.11}$$

where g_s is called the gyromagnetic factor and its value is approximately equal to 2. Therefore, the total magnetic moment is

$$\vec{\mu} = \frac{\mu_B}{\hbar}(\vec{L} + 2\vec{S}). \tag{1.12}$$

The perturbation energy caused by the magnetic field is given then by

$$\mathcal{H}' = -\vec{\mu} \cdot \vec{H} = \frac{\mu_B}{\hbar}(\vec{J} + \vec{S}), \tag{1.13}$$

where the plus sign resulted because the charge of the electron is $-e$.

1.4.1 Weak External Field

In a hydrogen atom, the electron circles around the proton; but in a system fixed to an electron, the proton circles around the electron and generates an inner magnetic field at the position of the electron given by

$$\vec{H}_{\text{in}} = \frac{\mu_0 e}{4\pi m_p r^3}\vec{L}. \tag{1.14}$$

Equation 1.14 gives the following energy for the electron's spin

$$\mathcal{H}_{\text{so}} = \vec{\mu}_{\text{sp}} \cdot \vec{H}_{\text{in}} = \frac{e^2}{4\pi\epsilon_0 r^3 m^2 c^2}\vec{S} \cdot \vec{L}, \tag{1.15}$$

which is called the spin–orbit interaction. We interpret the spin–orbit interaction as an internal Zeeman effect because it splits the energy levels without an external magnetic field. Let the external field be weak compared with the effective internal field. Since the Larmor frequency is proportional to the magnetic field, the triangle $\vec{L}\,\vec{S}\,\vec{J}$ in Figure 1.1 rotates about $\vec{J}$ considerably faster than the precession around $\vec{H}$. Therefore, the coupling of the vectors $\vec{L}$, $\vec{S}$, and $\vec{J}$ in the triangle is not disrupted.

Let us now find the correction to the energy due to the external magnetic field. Equation 1.13 involves the vectors $\vec{J}$ and $\vec{S}$, if we consider that the z-axis coincides with the direction of the external magnetic field, then, the only projections of these two vectors that contribute to the energy are the ones along the z-axis. Thus, the mean value of $\mathcal{H}'$ is equal to



FIGURE 1.1 Schematic of the spin–orbit coupling.

$$\langle \mathcal{H}' \rangle = \frac{\mu_B H J_z}{\hbar}\left(1 + \frac{\vec{S} \cdot \vec{J}}{J^2}\right), \tag{1.16}$$

and using

$$\frac{\vec{S} \cdot \vec{J}}{J^2} = \frac{j(j+1) + s(s+1) - l(l+1)}{2j(j+1)} = g \tag{1.17}$$

we get

$$\langle \mathcal{H}' \rangle = \mu_B H g m_j \quad \text{for } m_j = -j, -j+1, \ldots, j. \tag{1.18}$$

Thus, the energy levels with a given J are split into as many levels as there are different projections of $\vec{J}$ on the magnetic field, i.e., $2j + 1$. The factor g is called the Landé factor and takes a given value for a given L and S and each corresponding value of J. The Zeeman effect in a weak magnetic field is called anomalous.

1.4.2 Strong External Field

We shall now consider the opposite extreme case, when the external field is strong compared with the internal field, so that the coupling between the vectors $\vec{L}, \vec{S}, \vec{J}$ is disrupted. This can be explained by the fact that $\vec{S}$ precesses twice as fast $\vec{L}$. Then, from the classical analogy, each of the vectors $\vec{S}$ and $\vec{L}$ precesses independently about the magnetic field. For this case, the correction to the energy is given by

$$\langle \mathcal{H}' \rangle = \frac{\mu_B e H}{\hbar}(L_z + 2S_z). \tag{1.19}$$

In Equation 1.19, L_z and S_z are the projections of the orbital angular momentum and spin along the z-axis, respectively, and are given by

$$L_z = \hbar m_l \quad \text{for } m_l = -l, \ldots, l, \quad S_z = \hbar m_s, \quad \text{for } m_s = \pm\frac{1}{2}. \tag{1.20}$$

The projections S_z and L_z are changed by unity, therefore all the levels in Equation 1.19 are equidistant. Of course, certain values of $\langle \mathcal{H}' \rangle$ may be repeated several times if the sum $L_z + 2S_z$ assumes the same value. This Zeeman effect in a strong magnetic field is called the normal Zeeman effect.

1.5 Atom–Light Interaction

Though an atom has infinitely many energy levels, we can have under certain assumptions a two-level atom. These assumptions are (1) the difference of the energy levels approximately matches the energy of the incident photon, (2) the selection rules allow transition of the electrons between the two levels, and (3) all other energy levels are sufficiently detuned in frequency separation with respect to the incoming frequency such that there is no transition to these levels.

Consider that we apply the two-level approximation to a simple atom where the interaction with visible light involves a single electron. The corresponding wave function of the system is

$$|\psi\rangle = c_0\,|0\rangle + c_1\,|1\rangle, \tag{1.21}$$

where $|0\rangle$ ($|1\rangle$) corresponds to the nonexcited (excited) state and the coefficients $c_0(c_1)$ represent the probability amplitude to find the system in either state, respectively. The probability amplitudes satisfy the normalization condition $|c_0|^2 + |c_1|^2 = 1$. The wavelength of visible light, typical for atomic transitions, is about a few thousand times the diameter of an atom. Therefore, there is no significant spatial variation of the electric field across an atom, and $\vec{E}(\vec{r},t) \approx \vec{E}(t)$ can be taken as independent of the position (dipole approximation). Consistent with this long-wavelength approximation is that the magnetic field $\vec{H}$ is approximately zero, i.e., $\vec{H} \approx 0$, so that the interaction energy between the field and the electron of the atom is given by $\mathcal{H}' = -e\vec{r}\cdot\vec{E}$, hence the total Hamiltonian is

$$\mathcal{H} = \mathcal{H}_0 + \mathcal{H}', \tag{1.22}$$

where $\mathcal{H}_0$ represents the unperturbed atom system, i.e., $\mathcal{H}_0\,|0\rangle = \varepsilon_0\,|0\rangle$ and $\mathcal{H}_0\,|1\rangle = \varepsilon_1\,|1\rangle$, where ε_0 and ε_1 are the energy values for the nonexcited and excited states, respectively.

Seeking a solution to the Schrödinger equation

$$\mathcal{H}\,|\psi(t)\rangle = i\hbar\frac{\partial\,|\psi(t)\rangle}{\partial t}, \tag{1.23}$$

in the following form

$$|\psi(t)\rangle = c_0(t)e^{-i\varepsilon_0 t/\hbar}\,|0\rangle + c_1(t)e^{-i\varepsilon_1 t/\hbar}\,|1\rangle, \tag{1.24}$$

we get

$$\mathrm{i}\hbar\frac{c_l(t)}{\mathrm{d}t} = \sum_{k=0,1} c_k(t)\mathrm{e}^{-\mathrm{i}(\varepsilon_k-\varepsilon_l)t/\hbar}\langle l\,|\,\mathcal{H}'\,|\,k\rangle, \quad \text{for } l = 0, 1. \tag{1.25}$$

Representing the light with frequency ν by means of the complex electric field vector E_0 in the form

$$\vec{E}(t) = \frac{1}{2}(\vec{E}_0\mathrm{e}^{-\mathrm{i}\nu t} + \vec{E}_0^{\star}\mathrm{e}^{\mathrm{i}\nu t}), \tag{1.26}$$

and using the fact that the diagonal elements of the interacting Hamiltonian are zero due to the parity of the eigenfunction, i.e., $\langle k\,|\,\mathcal{H}'\,|\,k\rangle = 0$, we end up with the following coupled differential equations

$$\frac{\mathrm{d}c_0(t)}{\mathrm{d}t} = \frac{i}{2\hbar}\left[\vec{E}_0\cdot\langle 0\,|\,\vec{d}\,|1\rangle\mathrm{e}^{-\mathrm{i}(\omega_{10}+\nu)t} + \vec{E}_0^{\star}\cdot\langle 0\,|\,\vec{d}\,|1\rangle\mathrm{e}^{-\mathrm{i}(\omega_{10}-\nu)t}\right]c_1(t), \tag{1.27}$$

$$\frac{\mathrm{d}c_1(t)}{\mathrm{d}t} = \frac{i}{2\hbar}\left[\vec{E}_0^{\star}\cdot\langle 1\,|\,\vec{d}\,|\,0\rangle\mathrm{e}^{\mathrm{i}(\omega_{10}+\nu)t} + \vec{E}_0\cdot\langle 1\,|\,\vec{d}\,|\,0\rangle\mathrm{e}^{\mathrm{i}(\omega_{10}-\nu)t}\right]c_0(t), \tag{1.28}$$

where $\omega_{10} = (\varepsilon_1 - \varepsilon_0)/\hbar$ and $\langle 0|\vec{d}|1\rangle = \langle 1|\vec{d}|0\rangle^{\star} = \langle 0|e\vec{r}|1\rangle$.

For the case when $\nu \approx \omega_{10}$, we can drop the terms containing $\exp[\pm(\omega_{10} + \nu)t]$ in Equation 1.28 since they oscillate rapidly in time and can be neglected with respect to the near resonant terms, i.e., the terms of the form $\exp[\pm(\omega_{10} - \nu)t]$. This approximation is called the rotating wave approximation (RWA), and the coupled differential equations become

$$\begin{aligned}\frac{\mathrm{d}c_0(t)}{\mathrm{d}t} &= \frac{\mathrm{i}\Omega_\mathrm{R}^{\star}}{2}\mathrm{e}^{-\mathrm{i}\Delta t}c_1(t),\\ \frac{\mathrm{d}c_1(t)}{\mathrm{d}t} &= \frac{\mathrm{i}\Omega_\mathrm{R}}{2}\mathrm{e}^{\mathrm{i}\Delta t}\,c_0(t),\end{aligned} \tag{1.29}$$

where

$\Omega_\mathrm{R} = \vec{E}_0\cdot\langle 1|\vec{d}|0\rangle/\hbar$ is known as the Rabi frequency
$\Delta = (\omega_{10} - \nu)$ is the so-called detuning

The general solution for Equation 1.29 for strictly monochromatic fields, i.e., $\Omega_\mathrm{R} = |\Omega_\mathrm{R}|\mathrm{e}^{\mathrm{i}\phi}$ = constant, is given by

$$\begin{aligned}c_0(t) &= \frac{1}{\Omega}(\mu_1\mathrm{e}^{\mathrm{i}\mu_2 t} - \mu_2\mathrm{e}^{\mathrm{i}\mu_1 t}),\\ c_1(t) &= \frac{\mathrm{i}\Omega_\mathrm{R}}{\Omega}\mathrm{e}^{\mathrm{i}\Delta t/2}\sin\left(\frac{\Omega t}{2}\right),\end{aligned} \tag{1.30}$$

where

$$\begin{aligned}\mu_{1,2} &= -\frac{\Delta}{2} \pm \sqrt{\Delta^2 + \Omega_\mathrm{R}^2},\\ \Omega &= \mu_1 - \mu_2 = \sqrt{\Delta^2 + \Omega_\mathrm{R}^2}.\end{aligned} \tag{1.31}$$

Equation 1.31 gives the transition probabilities from the nonexcited to the excited state

$$|c_0(t)|^2 = \left(\frac{\Omega_\mathrm{R}}{\Omega}\right)^2\sin^2\left(\frac{\Omega t}{2}\right), \quad |c_1(t)|^2 = 1 - |c_0(t)|^2, \tag{1.32}$$

which oscillate with frequency Ω (Rabi flopping frequency) between levels ε_0 and ε_1. Any two-level system can be represented by a 2 × 2 matrix Hamiltonian and hence can be expressed in terms of Pauli matrices. For example, choosing the energy zero to be half way between the excited and nonexcited state $|0\rangle$ and $|1\rangle$, we have the following matrix Hamiltonian for this system

$$\mathcal{H}_0 = \frac{\hbar\omega}{2}\begin{pmatrix}1 & 0\\ 0 & -1\end{pmatrix} = \frac{\hbar\omega}{2}\sigma_z, \tag{1.33}$$

where

$\hbar\omega = \varepsilon_1 - \varepsilon_0$

σ_z is a Pauli matrix

Therefore, we can write the total Hamiltonian of the atom–light interaction in the RWA as

$$\mathcal{H} = \frac{\hbar}{2}\begin{pmatrix} \omega & -\Omega_{\mathrm{R}} \mathrm{e}^{\mathrm{i}\Delta t} \\ -\Omega_{\mathrm{R}}^{\star} \mathrm{e}^{-\mathrm{i}\Delta t} & -\omega \end{pmatrix} = \frac{\hbar\omega}{2}\sigma_z - \frac{\hbar}{2}(\Omega_{\mathrm{R}} \mathrm{e}^{\mathrm{i}\Delta t}\sigma_+ + \Omega_{\mathrm{R}}^{\star} \mathrm{e}^{-\mathrm{i}\Delta t}\sigma_-), \tag{1.34}$$

where

$$\sigma_+ = \begin{pmatrix} 0 & 1 \\ 0 & 0 \end{pmatrix} \quad \text{and} \quad \sigma_- = \begin{pmatrix} 0 & 0 \\ 1 & 0 \end{pmatrix}. \tag{1.35}$$

1.5.1 Jaynes–Cummings Model

So far, we have used a semiclassical description of the interaction between a two-level atom and an electric field. A quantum description of the interaction would require a quantization of the radiation field. This description is known as the *Jaynes–Cummings model*. Consider the sourceless electromagnetic field in a cubic cavity of volume $V = L \times L \times L$. Working with the Coulomb gauge for which the vector potential satisfies the requirement

$$\nabla \cdot \vec{A} = 0, \tag{1.36}$$

and, since there are no sources, it satisfies the homogeneous wave equation

$$\nabla^2 \vec{A} - \frac{1}{c^2}\frac{\partial^2 \vec{A}}{\partial t^2} = 0. \tag{1.37}$$

Then the fields are fully specified by the vector potential in the form

$$\vec{E} = -\frac{\partial \vec{A}}{\partial t} \quad \text{and} \quad \vec{B} = \nabla \times \vec{A}. \tag{1.38}$$

We can expand the vector potential in the form

$$\vec{A}(\vec{r}, t) = \frac{1}{\sqrt{\epsilon_0 V}} \sum_{\vec{k}} \left[\vec{A}_{\vec{k}}(t) \mathrm{e}^{\mathrm{i}\vec{k}\cdot\vec{r}} + \vec{A}_{\vec{k}}^{\star}(t) \mathrm{e}^{-\mathrm{i}\vec{k}\cdot\vec{r}} \right]. \tag{1.39}$$

Equation 1.36 implies that $\vec{A}_{\vec{k}}$ and $\vec{A}_{\vec{k}}^{\star}$ are perpendicular to the vector of propagation $\vec{k}$, therefore we can rewrite Equation 1.39 in the following form:

$$\vec{A}(\vec{r}, t) = \frac{1}{\sqrt{\epsilon_0 V}} \sum_{\vec{k}} \left[\vec{\epsilon}_{\vec{k}} A_{\vec{k}}(t) \mathrm{e}^{\mathrm{i}\vec{k}\cdot\vec{r}} + \vec{\epsilon}_{\vec{k}}^{\star} A_{\vec{k}}^{\star}(t) \mathrm{e}^{-\mathrm{i}\vec{k}\cdot\vec{r}} \right], \tag{1.40}$$

where $\vec{\epsilon}_{\vec{k}} = (e_1, e_2)$ is called the polarization vector, which is perpendicular to the direction of propagation and $A_{\vec{k}}(t)$ is a time dependent amplitude that varies harmonically with time, i.e., $\dot{A}_{\vec{k}} = -\mathrm{i}\omega_{\vec{k}} A_{\vec{k}}$, where $\omega_{\vec{k}} = \sqrt{k_x^2 + k_y^2 + k_z^2} = |\vec{k}|c$. Assuming that the field is periodic in space, and the lengths of the periods in three perpendicular directions are equal to the dimensions of the cubic box, then $k_j = 2n_j\pi/L$ for $j = x, y, z$ and n_j are integers of any sign. Using Equation 1.38 we get

$$\vec{E}(\vec{r}, t) = \frac{i}{\sqrt{\epsilon_0 V}} \sum_{\vec{k}} \nu_{\vec{k}} \left[\vec{\epsilon}_{\vec{k}} A_{\vec{k}} \mathrm{e}^{\mathrm{i}\vec{k}\cdot\vec{r}} + \vec{\epsilon}_{\vec{k}}^{\star} A_{\vec{k}}^{\star} \mathrm{e}^{-\mathrm{i}\vec{k}\cdot\vec{r}} \right], \tag{1.41}$$

and

$$\vec{H}(\vec{r}, t) = \frac{i}{\sqrt{\epsilon_0 V}} \sum_{\vec{k}} \left[(\vec{k} \times \vec{\epsilon}_{\vec{k}}) A_{\vec{k}} \mathrm{e}^{\mathrm{i}\vec{r}\cdot\vec{r}} - (\vec{k} \times \vec{\epsilon}_{\vec{k}}^{\star}) A_{\vec{k}}^{\star} \mathrm{e}^{-\mathrm{i}\vec{r}\cdot\vec{r}} \right]. \tag{1.42}$$

The classical Hamiltonian for the field is given by

$$\mathcal{H}_{\mathrm{E-M}} = \frac{\epsilon_0}{2} \int_V \left(|\vec{E}|^2 + c^2 |\vec{H}|^2 \right) \mathrm{d}x\,\mathrm{d}y\,\mathrm{d}z. \tag{1.43}$$

Substituting Equations 1.41 and 1.42 into Equation 1.43 one gets

$$\mathcal{H}_{\mathrm{E-M}} = \sum_{\vec{k}} \omega_{\vec{k}}^2 A_{\vec{k}} A_{\vec{k}}^{\star}. \tag{1.44}$$

If we introduce the variable

$$A_{\vec{k}} = \frac{1}{\sqrt{2}} \left(Q_{\vec{k}} + \mathrm{i}\frac{P_{\vec{k}}}{\omega_{\vec{k}}} \right), \tag{1.45}$$

then Equation 1.44 becomes

$$\mathcal{H}_{\mathrm{E-M}} = \frac{1}{2} \sum_{\vec{k}} (Q_{\vec{k}}^2 \omega_{\vec{k}}^2 + P_{\vec{k}}^2). \tag{1.46}$$

Equation 1.46 corresponds to the sum of independent harmonic oscillators. This suggests that each mode of the field is dynamically equivalent to a mechanical harmonic oscillator. The canonical quantization of the field consists of the substitution of the variables $Q_{\vec{k}}$ and $P_{\vec{k}}$ for operators, which fulfill the commutation relation

$$[Q_{\vec{k}}, P_{\vec{k}'}] = \mathrm{i}\hbar\delta_{\vec{k}\vec{k}'}, \tag{1.47}$$

this means that

$$[A_{\vec{k}}, A_{\vec{k}'}^{\dagger}] = \frac{\hbar}{\omega_{\vec{k}}} \delta_{\vec{k}\vec{k}'}. \tag{1.48}$$

Introducing the creation and annihilation operators

$$a_{\vec{k}} = \sqrt{\frac{\omega_{\vec{k}}}{\hbar}} A_{\vec{k}} \quad \text{and} \quad a_{\vec{k}}^{\dagger} = \sqrt{\frac{\omega_{\vec{k}}}{\hbar}} A_{\vec{k}}^{\dagger}, \tag{1.49}$$

we can write the electromagnetic field Hamiltonian in the form

$$\mathcal{H}_{\text{E-M}} = \sum_{\vec{k}} \left(\hbar\omega_{\vec{k}} a_{\vec{k}} a_{\vec{k}}^{\dagger} + \frac{1}{2}\hbar\omega_{\vec{k}} \right). \tag{1.50}$$

The total Hamiltonian that describes the interaction of an atom with the quantized electromagnetic field can be written in the form

$$\mathcal{H} = \sum_{i} \varepsilon_i \,|i\rangle\langle i| + \sum_{\vec{k}} \hbar\omega_k a_{\vec{k}}^{\dagger} a_{\vec{k}} - \sum_{i,j} \langle i|\vec{d}\,|j\rangle\,|i\rangle\langle j|\cdot\vec{E}, \tag{1.51}$$

where ϵ_i is the energy corresponding to the state $|i\rangle$ of the atom and we have dropped the constant terms corresponding to the zero point energy.

The electric field operator is given by

$$\vec{E} = i\sum_{\vec{k}} \vec{\epsilon}_{\vec{k}} \sqrt{\frac{\hbar\omega_{\vec{k}}}{\epsilon_0 V}} \left[a_{\vec{k}} \mathrm{e}^{\mathrm{i}\vec{k}\cdot\vec{r}} - a_{\vec{k}}^{\dagger} \mathrm{e}^{-\mathrm{i}\vec{k}\cdot\vec{r}} \right]. \tag{1.52}$$

Making the dipole approximation, i.e., $\mathrm{e}^{\mathrm{i}\vec{k}\cdot\vec{r}} \approx 1$, and assuming that we are dealing with a two-level atom, i.e., $i, j = 0, 1$, then we can write Equation 1.51 as

$$\mathcal{H} = \frac{\hbar\omega_{10}}{2}\sigma_z + \sum_{\vec{k}} \hbar\omega_{\vec{k}} a_{\vec{k}}^{\dagger} a_{\vec{k}} + \sum_{\vec{k}} (g_{\vec{k}}^{\star}\sigma_+ - g_{\vec{k}}\sigma_-)(a_{\vec{k}} - a_{\vec{k}}^{\dagger}), \tag{1.53}$$

where $g_{\vec{k}} = i\sqrt{\hbar\omega_k/\epsilon_0 V}\,\vec{d}_{01}\cdot\vec{\epsilon}_{\vec{k}}$. The scalar product between the dipole moment and the polarization vector yields a complex number that can be written as $\vec{d}_{01}\cdot\vec{\epsilon}_{\vec{k}} = |\vec{d}_{01}\cdot\vec{\epsilon}_{\vec{k}}|\,\mathrm{e}^{\mathrm{i}\phi}$. This allows one to choose the phase ϕ in such a way that $g_{\vec{k}} = g_{\vec{k}}^{\star}$. If the atom interacts only with one mode of the electromagnetic field, then we can drop the sum over the vector of propagation to get

$$\mathcal{H} = \frac{\hbar\omega_{10}}{2}\sigma_z + \hbar\omega a_k^{\dagger} a_k + g_k(\sigma_+ - \sigma_-)(a_k - a_k^{\dagger}) = \mathcal{H}_0 + \mathcal{H}'. \tag{1.54}$$

In the interaction picture, i.e., $\mathcal{H}_{\mathrm{I}} = \mathrm{e}^{-\mathrm{i}\mathcal{H}_0 t/\hbar}\,\mathcal{H}\,\mathrm{e}^{\mathrm{i}\mathcal{H}_0 t/\hbar}$, the Hamiltonian of interaction will have the form

$$\begin{aligned} \mathcal{H}_{\mathrm{I}}' = g_k \Big(&\sigma_+ a_k \mathrm{e}^{-\mathrm{i}(\omega_{10}-\omega)t} + \sigma_- a_k^{\dagger}\,\mathrm{e}^{\mathrm{i}(\omega_{10}-\omega)t} - \sigma_+ a_k^{\dagger}\,\mathrm{e}^{\mathrm{i}(\omega_{10}+\omega)t} \\ &- \sigma_- a_k \mathrm{e}^{-\mathrm{i}(\omega_{10}+\omega)t} \Big), \end{aligned} \tag{1.55}$$

using the RWA, i.e., dropping the rapidly oscillating terms containing $\mathrm{e}^{\pm\mathrm{i}(\omega_{10}+\omega)t}$, we end up with

$$\mathcal{H}_{\mathrm{I}} = \frac{\hbar\omega_{10}}{2}\sigma_z + \hbar\omega a_k^{\dagger} a_k + g_k(\sigma_+ a_k \mathrm{e}^{-\mathrm{i}\Delta t} + \sigma_- a_k^{\dagger} \mathrm{e}^{\mathrm{i}\Delta t}), \tag{1.56}$$

where $\Delta = \omega_{10} - \omega$ is the detuning. The Hamiltonian of Equation 1.56 corresponds in the Schrödinger picture to

$$\mathcal{H} = \frac{\hbar\omega_{10}}{2}\sigma_z + \hbar\omega a_k^{\dagger} a_k + g_k(\sigma_+ a_k + \sigma_- a_k^{\dagger}). \tag{1.57}$$

Equation 1.57 is the Jaynes–Cummings model.

1.6 Loss–DiVincenzo Proposal

The first proposals for quantum computing made use of cavity quantum electrodynamics (QED), trapped ions, and nuclear magnetic resonance (NMR). All of these proposals benefit from long decoherence times due to a very weak coupling of the qubits to their environment. The long decoherence times have led to big successes in achieving experimental realizations. A conditional phase (CPHASE) gate was demonstrated early on in cavity QED systems. The two-qubit controlled-NOT gate has been realized in single-ion and two-ion versions. The most remarkable realization of the power of quantum computing to date is the implementation of Shor's algorithm to factor the number 15 in a liquid-state NMR quantum computer to yield the known result 5 and 3. However, these proposals may not be scalable and therefore do not meet the DiVincenzo criteria. The requirement for scalability motivated the Loss–DiVincenzo proposal for a solid state quantum computer based on electron spin qubits (Loss and DiVincenzo, 1998). The spin of an electron in a quantum dot can point up or down with respect to an external magnetic field; these eigenstates, $|\uparrow\rangle$ and $|\downarrow\rangle$, correspond to the two basis states of the qubit. The electron trapped in a quantum dot, which is basically a small electrically defined box that can be filled with electrons, can be defined by metal gate electrodes on top of a semiconductor (GaAs/AlGaAs) heterostructure. At the interface between GaAs and AlGaAs conduction band, electrons accumulate and can only move in the lateral direction. Applying negative voltages to the gates locally depletes this two-dimensional electron gas underneath. The resulting gated quantum dots are very controllable and versatile systems, which can be manipulated and probed electrically. When the size of the dot is comparable to the wavelength of the electrons that occupy it, the system exhibits a discrete energy spectrum, resembling that of an atom.

Initialization of the quantum computer can be achieved by allowing all spins to reach their equilibrium thermodynamic ground state at a low temperature T in an applied magnetic field, so that all the spins will be aligned if the condition $|g\mu_{\mathrm{B}}H| \gg k_{\mathrm{B}}T$ is satisfied (where k_{B} is Boltzmann constant).

To perform single-qubit operations, we can apply a microwave magnetic field on resonance with the Zeeman splitting, i.e., with a frequency $f = \Delta E_Z/h$ (h is Planck's constant). The oscillating magnetic component perpendicular to the static magnetic field H results in a spin nutation. By applying the oscillating field for a fixed duration, a superposition of $|\uparrow\rangle$ and $|\downarrow\rangle$ can be created. This magnetic technique is known as electron spin resonance (ESR). In the Loss–Divincenzo proposal, two-qubit operations can be carried out purely electrically by varying the gate voltages between neighboring dots. When the barrier is high, the spins are decoupled. When the interdot barrier is pulsed low,



FIGURE 1.2 Theoretical proposal by Loss–DiVincenzo for quantum computing using quantum dots and electric gates.

an appreciable overlap develops between the two electron wave functions, resulting in a nonzero Heisenberg exchange coupling J (see Figure 1.2). The Hamiltonian describing this time dependent process is given by

$$\mathcal{H}(t) = J(t)\vec{S}_n \cdot \vec{S}_{n+1}. \tag{1.58}$$

Equation 1.58 is sometimes referred to as the direct interaction.

The evolution of the quantum state is described by the propagator given by $U(t) = \mathcal{T}\exp[-i\int \mathcal{H}(t)\mathrm{d}t/\hbar]$, where $\mathcal{T}$ is the time ordering operator. If the exchange is pulsed on for a time τ_s such that $\int J(t)\mathrm{d}t/\hbar = J_0\tau_s/\hbar = \pi$, the states of the two spins will be exchanged. This is the SWAP operation. Pulsing the exchange for a shorter time $\tau_s/2$ generates the square root of SWAP operation, which can be used in conjunction with single-qubit operator to generate the controlled-NOT gate.

A last crucial ingredient requires a method to read out the state of the spin qubit. This implies measuring the spin orientation of a single electron. Therefore, an indirect spin measurement is proposed. First, the spin orientation of the electron is correlated with its position, via spin to charge conversion. Then an electrometer is used to measure the position of the charge, thereby revealing its spin. In this way, the problem of measuring the spin orientation has been replaced by the much easier measurement of charge.

The Loss–DiVincenzo ideas have influenced an enormous research effort aimed at implementing the different parts of the proposal and has been quickly followed by a series of alternative solid state realizations for trapped atoms in optical lattices that may also be scalable. It should also be stressed that the efforts to create a spin qubit are not purely application driven. If we have the ability to control and read out a single electron spin, we are in a unique position to study the interaction of the spin with its environment. This may lead to a better understanding of decoherence and will also allow us to study the semiconductor environment using the spin as a probe.

1.6.1 RKKY Interaction

The RKKY interaction is a long-range magnetic interaction that involves nearest-neighbor ions as well as magnetic atoms that are further apart; this interaction is sometimes called indirect interaction. The basis of this interaction lies in an exchange interaction, which was proposed by Ruderman and Kittel (1954), and extended by Kasuya (1956) and Yosida (1957), and now known as the RKKY interaction. This interaction refers to an exchange energy written as

$$\mathcal{H}_{\text{exch}} = -J(r)\sum_i \vec{s}_i \cdot \vec{S}, \tag{1.59}$$

where

The exchange parameter $J(r)$ falls off rapidly with distance r between the center of a localized magnetic ion and electron spin

$\vec{s}_i$ is the spin state of a conduction electron

$\vec{S}$ is the spin of a localized magnetic ion

The minus sign in Equation 1.59 is related to the Pauli exclusion principle (lowest energy of electron occupancy). Below some critical magnetic ordering temperature, the itinerant or localized spins may condense into an ordered array, i.e., ferromagnetic or antiferromagnetic. As in the case of atomic scattering, any disorder within this array will cause additional electron scattering. This scattering may be elastic, in which case there is no change in energy or spin-flip, or it may be inelastic, in which case the spin state of the conduction electrons changes. Usually RKKY interaction is of significance only in compounds with a high concentration of the magnetic atom. Thus, localized ions may start to interact indirectly via the conduction electrons.

Now, consider the case in which there exist two localized spins at lattice points $\vec{R}_n$ and $\vec{R}_m$. By the interaction between spin S_{mz} localized at $\vec{R}_m$ and the spin density of conduction electrons polarized by spin S_{nz} localized at $\vec{R}_n$, the following interaction between the spins $\vec{S}_n$ and $\vec{S}_m$ is found:

$$\mathcal{H}_{\text{exch}} = -9\pi\frac{J^2}{\varepsilon_F}\left(\frac{N_e}{N}\right)^2 F\left(2k_F\,|\vec{R}_n - \vec{R}_m|\right)S_{mz}S_{nz}, \tag{1.60}$$

where

$$F(x) = \frac{-x\cos(x) + \sin(x)}{x^4}. \tag{1.61}$$

Recently, the optical RKKY interaction between two spins was introduced as a means to produce an effective exchange interaction (Piermarocchi et al., 2002). Similar to the Loss–DiVincenzo scheme, in this scheme, the two qubits are defined by the excess electrons of semiconductor quantum dots. Instead of using the direct exchange interaction between the two electrons, the exchange interaction is indirectly mediated by the itinerant electrons of virtual excitons that are optically excited in the host material, which can be made of bulk, quantum well, or quantum wire structures. This scheme has the advantage that two-qubit gates can be performed on the femtosecond timescale due to the possibility of using ultrafast laser optics. The Coulomb interaction between the photoexcited itinerant electrons and the localized electrons in the two quantum dots contains direct and indirect terms. While the direct terms give rise to state renormalization of the localized electrons, the exchange terms lead to an effective Heisenberg interaction of the form

$$\mathcal{H}_{\text{ORKKY}} = -J_{12}\mathbf{S}_1 \cdot \mathbf{S}_2 \propto P_{12}\frac{H_C^2 H_X^2}{\delta^3}P_{12}, \tag{1.62}$$

which is calculated in fourth-order perturbation theory using the diagram depicted in Figure 1.3.

P_{12} is the projection operator on the two-spin Hilbert space of the two localized spins. The control Hamiltonian

$$\mathcal{H}_C = \sum_{\mathbf{k},\sigma}\frac{\Omega_{\mathbf{k},\sigma}(t)}{2}\mathrm{e}^{-\mathrm{i}\omega_P\sigma}c^\dagger_{\mathbf{k},-\sigma}h^\dagger_{-\mathbf{k},\sigma} + h.c. \tag{1.63}$$

describes the creation of the virtual excitons by means of an external laser field that is detuned by the energy δ from the continuum states of the host material, or more precisely from the exciton 1s level. $c^\dagger_{\mathbf{k},\sigma}$ and $h^\dagger_{\mathbf{k},\sigma}$ are electron and hole creation operators, respectively. The RKKY interaction between a localized electron in the quantum dot and the itinerant electrons in the host material is given in second quantization by

$$\mathcal{H}_X = -\frac{1}{V}\sum_{\alpha,\alpha',\mathbf{k},\mathbf{k}'} J(\mathbf{k},\mathbf{k}')\mathbf{S}_i \cdot \mathbf{s}_{\alpha,\alpha'}c^\dagger_{\mathbf{k},\alpha}c_{\mathbf{k}',\alpha'}. \tag{1.64}$$

The predicted exchange interaction $J_{12}(\mathbf{R})$ (see Figure 1.2) can be of the order of 1 meV, which is of the same order as the Heisenberg interaction in the Loss–DiVincenzo scheme.


ω_P, $\sigma+$
ω, k_e, $-\frac{1}{2}$
γ'
γ
J_2
$\omega_P - \omega$, k_h, $\frac{3}{2}$
ω, k_c', α
J_1
β'
ω, k_e, $-\frac{1}{2}$
ω_P, $\sigma+$
β

FIGURE 1.3 Effective spin–spin interaction for the localized electrons in the dots 1 and 2 (indicated by dotted lines) induced by a photoexcited electron–hole pair (the solid and dashed lines, respectively). The indices β and γ denote the spin states of the electrons localized in the dots. The photon propagator is depicted by a wavy line. (From Piermarocchi, C. et al., *Phys. Rev. Lett.*, 89, 167402, 2002.)

1.7 Quantum Computing with Molecular Magnets

Shor and Grover demonstrated that a quantum computer can outperform any classical computer in factoring numbers (Shor, 1997) and in searching a database (Grover, 1997) by exploiting the parallelism of quantum mechanics. Recently, the latter has been successfully implemented (Ahn et al., 2000) using Rydberg atoms. Leuenberger and Loss (2001) proposed an implementation of Grover's algorithm using molecular magnets (Friedman et al., 1996; Thomas et al., 1996; Sangregorio et al., 1997; Thiaville and Miltat, 1999; Wernsdorfer et al., 2000); their spin eigenstates make them natural candidates for single-particle systems. It was shown theoretically that molecular magnets can be used to build dense and efficient memory devices based on the Grover algorithm. In particular, one single crystal can serve as a storage unit of a dynamic random access memory device. Fast ESR pulses can be used to decode and read out stored numbers of up to 10^5, with access times as short as 10^{-10} s. This proposal should be feasible using the molecular magnets Fe_8 and Mn_{12}.

Suppose we want to find a phone number in a phone book consisting of $N = 2^n$ entries. Usually it takes $N/2$ queries on average to be successful. Even if the N entries were encoded binary, a classical computer would need approximately $\log_2 N$ queries to find the desired phone number (Grover, 1997). But the computational parallelism provided by the superposition and interference of quantum states enables the Grover algorithm to reduce the search to one single query (Grover, 1997). This query can be implemented in terms of a unitary transformation applied to the single spin of a molecular magnet. Such molecular magnets, forming identical and largely independent units, are embedded in a single crystal so that the ensemble nature of such a crystal provides a natural amplification of the magnetic moment of a single spin. However, for the Grover algorithm to succeed, it is necessary to find ways to generate arbitrary superpositions of spin eigenstates. For spins larger than ½, this turns out to be a highly nontrivial task as spin excitations induced by magnetic dipole transitions in conventional ESR can change the magnetic quantum number m by only ±1. To circumvent such physical limitations, it was proposed to use multifrequency coherent magnetic radiation that allows the controlled generation of arbitrary spin superpositions. In particular, it was shown that by means of advanced ESR techniques, it is possible to coherently populate and manipulate many spin states simultaneously by applying one single pulse of a magnetic a.c. field containing an appropriate number of matched frequencies. This a.c. field creates a nonlinear response of the magnet via multiphoton absorption processes involving particular sequences of σ and π photons, which allows the encoding and, similarly, the decoding of states. Finally, the subsequent read-out of the decoded quantum state can be achieved by means of pulsed ESR techniques. These exploit the nonequidistance of energy levels, which is typical of molecular magnets.

Molecular magnets have the important advantage that they can be grown naturally as single crystals of up to 10–100 μm length containing about 10^{12}–10^{15} (largely) independent units so that only minimal sample preparation is required. The molecular magnets are described by a single-spin Hamiltonian of the form $\mathcal{H}_{\text{spin}} = \mathcal{H}_{\text{a}} + V + \mathcal{H}_{\text{sp}} + \mathcal{H}_{\text{T}}$ (Leuenberger and Loss, 1999, 2000a,b), where $\mathcal{H}_{\text{a}} = -AS_z^2 - BS_z^4$ represents the magnetic anisotropy ($A \gg B > 0$). The Zeeman term $V = g\mu_{\text{B}}\mathbf{H} \cdot \mathbf{S}$ describes the coupling between the external magnetic field $\mathbf{H}$ and the spin $\mathbf{S}$ of length s. The calculational states are given by the $2s + 1$ eigenstates of $\mathcal{H}_{\text{a}} + g\mu_{\text{B}}H_zS_z$ with eigenenergies $\varepsilon_m = -Am^2 - Bm^4 + g\mu_{\text{B}}H_zm$, $-s \le m \le s$. The corresponding classical anisotropy potential energy $E(\theta) = -As\cos^2\theta - Bs\cos^4\theta + g\mu_{\text{B}}H_zs\cos\theta$ is obtained by the substitution $S_z = s\cos\theta$, where θ is the polar spherical angle. We have introduced the notation $m, m' = m - m'$. By applying a bias field H_z such that $g\mu_{\text{B}}H_z > E_{mm'}$, tunneling can be completely suppressed and thus $\mathcal{H}_{\text{T}}$ can be neglected (Leuenberger and Loss, 1999, 2000a,b). For temperatures below 1 K, transitions due to spin–phonon interactions ($\mathcal{H}_{\text{sp}}$) can also be neglected. In this regime, the level lifetime in Fe_8 and Mn_{12} is estimated to be about $\tau_{\text{d}} = 10^{-7}$ s, limited mainly by hyperfine and/or dipolar interactions (Leuenberger and Loss, 2001).

Since the Grover algorithm requires that all the transition probabilites are almost the same, Leuenberger and Loss (2001) and Leuenberger et al. (2003) propose that all the transition amplitudes between the states $|s\rangle$ and $|m\rangle$, $m = 1, 2, \ldots, s-1$, are of the same order in perturbation V. This allows us to use perturbation theory. A different approach uses the magnetic field amplitudes to adjust the appropriate transition amplitudes (Leuenberger et al., 2002). Both methods work only if the energy levels are not equidistant, which is typically the case in molecular magnets owing to anisotropies. In general, if we choose to work with the states $m = m_0, m_0 + 1, \ldots, s-1$, where $m_0 = 1, 2, \ldots, s-1$, we have to go up to nth order in perturbation, where $n = s - m_0$ is the number of computational states used for the Grover search algorithm (see below) to obtain the first nonvanishing contribution. Figure 1.4 shows the transitions for $s = 10$ and $m_0 = 5$. The nth-order transitions correspond to the nonlinear response of the spin system to strong magnetic fields. Thus, a coherent magnetic pulse of duration T is needed with a discrete frequency spectrum $\{\omega_m\}$, say, for Mn_{12} between 20 and 300 GHz and a single low-frequency 0 around 100 MHz.

The low-frequency field $\mathbf{H}_z(t) = H_0(t)\cos(\omega_0 t)\mathbf{e}_z$, applied along the easy-axis, couples to the spin of the molecular magnet through the Hamiltonian

$$V_{\text{low}} = g\mu_{\text{B}}H_0(t)\cos(\omega_0 t)S_z, \tag{1.65}$$



FIGURE 1.4 Feynman diagrams $\mathcal{F}$ that contribute to $S^{(5)}_{m,s}$ for $s = 10$ and $m_0 = 5$ describing transitions (of fifth order in V) in the left well of the spin system (see Figure 1.5). The solid and dotted arrows indicate σ^- and π transitions governed by Equations 1.66 and 1.65, respectively. We note that $S^{(j)}_{m,s} = 0$ for $j < n$, and $S^{(j)}_{m,s} \ll S^{(n)}_{m,s}$ for $j > n$.

where $\hbar\omega_0 \ll \varepsilon_{m_0} - \varepsilon_{m_0+1}$ and $\mathbf{e}_z$ is the unit vector pointing along the z-axis. The π photons of V_{low} supply the necessary energy for the resonance condition (see below). They give rise to virtual transitions with $\Delta m = 0$, that is, they do not transfer any angular momentum (see Figure 1.4). The perturbation Hamiltonian for the high-frequency transitions from $|s\rangle$ to virtual states that are just below $|m\rangle$, $m = m_0, \ldots, s-1$, given by the transverse fields $\mathbf{H}_\perp^-(t) = \sum_{m=m_0}^{s-1} H_m(t)[\cos(\omega_m t + \Phi_m)\mathbf{e}_x - \sin(\omega_m t + \Phi_m)\mathbf{e}_y]$, reads

$$\begin{aligned} V_{\text{high}}(t) &= \sum_{m=m_0}^{s-1} g\mu_{\text{B}}H_m(t)[\cos(\omega_m t + \Phi_m)S_x - \sin(\omega_m t + \Phi_m)S_y] \\ &= \sum_{m=m_0}^{s-1} \frac{g\mu_{\text{B}}H_m(t)}{2}\left[e^{i(\omega_m t + \Phi_m)}S_+ + e^{-i(\omega_m t + \Phi_m)}S_-\right], \end{aligned} \tag{1.66}$$

with phases Φ_m (see below), where we have introduced the unit vectors $\mathbf{e}_x$ and $\mathbf{e}_y$ pointing along the x- and y-axis, respectively. These transverse fields rotate clockwise and thus produce left circularly polarized σ^- photons, which induce only transitions in the left well (see Figure 1.5). In general, absorption (emission) of σ^- photons gives rise to $\Delta m = -1$ ($\Delta m = +1$) transitions, and vice versa in the



FIGURE 1.5 Double-well potential seen by the spin due to magnetic anisotropies in Mn_{12}. Arrows depict transitions between spin eigenstates driven by the external magnetic field **H**.

case of σ^+ photons. Anticlockwise rotating magnetic fields of the form $\mathbf{H}_\perp^+(t) = \sum_{m=m_0}^{s-1} H_m(t)[\cos(\omega_m t + \Phi_m)\mathbf{e}_x + \sin(\omega_m t + \Phi_m)\mathbf{e}_y]$ can be used to induce spin transitions only in the right well (see Figure 1.5). In this way, both wells can be accessed independently.

Next we calculate the quantum amplitudes for the transitions induced by the magnetic a.c. fields (see Figure 1.4) by evaluating the S-matrix perturbatively. The jth-order term of the perturbation series of the S-matrix in powers of the total perturbation Hamiltonian $V(t) = V_{\text{low}}(t) + V_{\text{high}}(t)$ is expressed by

$$S_{m,s}^{(j)} = \left(\frac{1}{i\hbar}\right)^j \prod_{k=1}^{j-1} \int_{-\infty}^{\infty} \mathrm{d}t_k \int_{-\infty}^{\infty} \mathrm{d}t_j \Theta(t_k - t_{k+1})$$
$$\times\, U(\infty,t_1)V(t_1)U(t_1,t_2)V(t_2)\ldots V(t_j)U(t_j,-\infty), \tag{1.67}$$

which corresponds to the sum over all Feynman diagrams $\mathcal{F}$ of order j, and where $U(t, t_0) = \mathrm{e}^{-\mathrm{i}(\mathcal{H}_\mathrm{a} + g\mu_\mathrm{B}\delta H_z)(t-t_0)/\hbar}$ is the free propagator, $\Theta(t)$ is the Heavyside function. The total S-matrix is then given by $S = \sum_{j=0}^{\infty} S^{(j)}$. The high-frequency virtual transition changing m from s to $s - 1$ is induced by the frequency $\omega_{s-1} = \omega_{s-1,s} - (n - 1)\omega_0$. The other high frequencies ω_m, $m = m_0, \ldots, s - 2$, of the high-frequency fields H_m mismatch the level separations by ω_0, that is, $\hbar\omega_m = \varepsilon_m - \varepsilon_{m+1} + \hbar\omega_0$ (see Figure 1.4). As the levels are not equidistant, it is possible to choose the low and high frequencies in such a way that $S_{m,s}^{(j)} = 0$ for $j < n$, in which case the resonance condition is not satisfied, that is, energy is not conserved. In addition, the higher-order amplitudes $|S_{m,s}^{(j)}|$ are negligible compared to $|S_{m,s}^{(j)}|$ for $j > n$. Using rectangular pulse shapes, $H_k(t) = H_k$, if $-T/2 < t < T/2$, and 0 otherwise, for $k = 0$ and $k \geq m_0$, one obtains ($m \geq m_0$)

$$S_{m,s}^{(n)} = \sum_{\mathcal{F}} \Omega_m \frac{2\pi}{i}\left(\frac{g\mu_\mathrm{B}}{2\hbar}\right)^n \frac{\prod_{k=m}^{s-1} H_k \mathrm{e}^{-\mathrm{i}\Phi_k} H_0^{m-m_0} p_{m,s}(\mathcal{F})}{(-1)^{q\mathcal{F}} q\mathcal{F}!\,r_s(\mathcal{F})!\,\omega_0^{n-1}}$$
$$\times\, \delta^{(T)}\left(\omega_{m,s} - \sum_{k=m}^{s-1} \omega_k - (m - m_0)\omega_0\right), \tag{1.68}$$

where $\Omega_m = (m - m_0)!$, is the symmetry factor of the Feynman diagrams $\mathcal{F}$ (see Figure 1.4), $q\mathcal{F} = m - m_0 - r_s(\mathcal{F})$, $p_{m,s}(\mathcal{F}) = \prod_{k=m}^{s} \langle k|S_z|k\rangle^{r_k(\mathcal{F})}$, $r_k(\mathcal{F}) = 0, 1, 2, \ldots, \leq m - m_0$ is the number of π transitions directly above or below the state $|k\rangle$, depending on the particular Feynman diagram $\mathcal{F}$, and $\delta^{(T)}(\omega) = \frac{1}{2\pi}\int_{-T/2}^{+T/2} \mathrm{e}^{\mathrm{i}\omega t}\mathrm{d}t = \sin(\omega T/2)/\pi\omega$ is the delta-function of width $1/T$, ensuring overall energy conservation for $\omega T \gg 1$. The duration T of the magnetic pulses must be shorter than the lifetimes τ_d of the states $|m\rangle$ (see Figure 1.5). In general, the magnetic field amplitudes H_k must be chosen in such a way that perturbation theory is still valid and the transition probabilities are almost equal, which is required by the Grover algorithm. According to Leuenberger and Loss (2001), the amplitudes H_k do not differ too much between each other due to the partial destructive interference of the different transition diagrams shown in Figure 1.5. Leuenberger et al. (2002) show that the transition probabilities can be increased by increasing both the magnetic field amplitudes and the detuning energies under the condition that the magnetic field amplitudes remain smaller than the detuning energies. In this way, both high-multiphoton Rabi oscillation frequencies and small quantum computation times can be attained. This makes both methods (Leuenberger and Loss, 2001; Leuenberger et al., 2002) very robust against decoherence sources.

In order to perform the Grover algorithm, one needs the relative phases φ_m between the transition amplitudes $S_{m,s}^{(n)}$, which is determined by $\Phi_m = \Sigma_{k=s-1}^{m+1}\Phi_k + \varphi_m$, where Φ_m are the relative phases between the magnetic fields $H_m(t)$. In this way, it is possible to read-in and decode the desired phases Φ_m for each state $|m\rangle$. The read-out is performed by standard spectroscopy with pulsed ESR, where the circularly polarized radiation can now be incoherent because only the absorption intensity of only one pulse is needed. We emphasize that the entire Grover algorithm (read-in, decoding, read-out) requires three subsequent pulses each of duration T with $\tau_d > T > \omega_0^{-1} > \omega_m^{-1} > \omega_{m,m\pm1}^{-1}$. This gives a "clock-speed" of about 10 GHz for Mn_{12}, that is, the entire process of read-in, decoding, and read-out can be performed within about 10^{-10} s.

The proposal for implementing Grover's algorithm works not only for molecular magnets but for any electron or nuclear spin system with nonequidistant energy levels, as is shown by Leuenberger et al. (2002) for nuclear spins in GaAs semiconductors. Instead of storing information in the phases of the eigenstates $|m\rangle$ (Leuenberger and Loss, 2001), Leuenberger et al. (2002) use the eigenenergies of $|m\rangle$ in the generalized rotating frame for encoding information. The decoding is performed by bringing the delocalized state $(1/\sqrt{n})\Sigma_m|m\rangle$ into resonance with $|m\rangle$ in the generalized rotating frame. Although such spin systems cannot be scaled arbitrarily, large spin s (the larger a spin becomes, the faster it decoheres and the more classical its behavior will be) systems of given s can be used to great advantage in building dense and highly efficient memory devices.

For a first test of the nonlinear response, one can irradiate the molecular magnet with an a.c. field of frequency $\omega_{s-2,s}/2$, which gives rise to a two-photon absorption and thus to a Rabi oscillation between the states $|s\rangle$ and $|s-2\rangle$. For stronger magnetic fields, it is in principle possible to generate superpositions of Rabi oscillations between the states $|s\rangle$ and $|s-1\rangle$, $|s\rangle$ and $|s-2\rangle$, $|s\rangle$ and $|s-3\rangle$, and so on (see also Leuenberger et al., 2002).

1.8 Semiconductor Quantum Dots

In the following, we mainly focus on quantum dots made of III–V semiconductor compounds with zincblende structure, like GaAs or InAs. The electronic bandstructure of a three-dimensional semiconductor with zincblende structure is illustrated in Figure 1.6. The bands are parabolic close to their extrema, which are all located at the Γ point. The conduction (c) states have orbital s symmetry and are spin degenerate. The valence (v) band consists of three subbands: the heavy-hole (hh), the light-hole (lh), and the split-off (so) band. The v-band states have orbital p symmetry. The bottom of the c band and the top of the v band are split by the band-gap energy E_{gap}. The v-band states with different j ($j=\frac{1}{2}$ for the so-band, $j=\frac{3}{2}$ for the hh and lh band) are split by Δ_{so} in energy due to spin–orbit interaction.

The hh states have the angular momentum projections $J_z = \pm\frac{3}{2}$ and the lh states $J_z = \pm\frac{1}{2}$. For finite electron wavevectors $k \neq 0$, and the hh and lh subbands split into two branches according to the different curvatures of the energy dispersion, which implies different effective masses of heavy and light holes. The v-band states with spin can be written in terms of the orbital angular momentum basis by using the Clebsch–Gordon coefficients which gives us

$$\text{Heavy hole}\begin{Bmatrix} \left|\frac{3}{2},\frac{3}{2}\right\rangle = |1,1\rangle|\uparrow\rangle \\ \left|\frac{3}{2},-\frac{3}{2}\right\rangle = |1,-1\rangle|\downarrow\rangle \end{Bmatrix}, \qquad (1.69)$$

$$\text{Light hole}\begin{Bmatrix} \left|\frac{3}{2},\frac{1}{2}\right\rangle = \frac{1}{\sqrt{3}}|1,1\rangle|\downarrow\rangle + \sqrt{\frac{2}{3}}|1,0\rangle|\uparrow\rangle \\ \left|\frac{3}{2},-\frac{1}{2}\right\rangle = \sqrt{\frac{2}{3}}|1,0\rangle|\downarrow\rangle + \frac{1}{\sqrt{3}}|1,-1\rangle|\uparrow\rangle \end{Bmatrix}, \qquad (1.70)$$



FIGURE 1.6 Electronic band structure in the vicinity of the Γ point for (a) a three-dimensional crystal and (b) a quantum well. The conduction and valence bands are shown as a function of the wavevector.

$$\text{Split off}\begin{Bmatrix} \left|\frac{1}{2},\frac{1}{2}\right\rangle = \frac{1}{\sqrt{3}}\left|1,0\right\rangle\left|\uparrow\right\rangle + \sqrt{\frac{2}{3}}\left|1,1\right\rangle\left|\downarrow\right\rangle \\ \left|\frac{1}{2},-\frac{1}{2}\right\rangle = \sqrt{\frac{2}{3}}\left|1,-1\right\rangle\left|\uparrow\right\rangle + \frac{1}{\sqrt{3}}\left|1,0\right\rangle\left|\downarrow\right\rangle \end{Bmatrix}. \tag{1.71}$$

Quantum confinement along the crystal axis quantizes the wavevector component, consequently the hh and lh states of the lowest subband are split by an energy $\Delta_{\text{hh-lh}}$ at the Γ point. Uniaxial strain in the semiconductor crystal can also lift the degeneracy of the heavy and light holes, and thus define the spin quantization axis. If we have a spherically symmetric quantum dot known as *colloidal quantum dots*, then we can have degeneracy between the heavy and light hole band, i.e., $\Delta_{\text{hh-lh}} = 0$.

Via photon absorption, an electron in a *v*-band state can be excited to a *c*-band state. Such interband transitions are determined by optical selection rules. The source or the optical transition rules are due to spin–orbit interaction. The electron–hole pair created with an interband transition is called an exciton. The electron and hole of an exciton form a bound state due to the Coulomb interaction, similar to that of a hydrogen atom. We refer to the system of two bound excitons as a biexciton.

1.8.1 Classical Faraday Effect

Michael Faraday first observed the effect in 1845 when studying the influence of a magnetic field on plane-polarized light waves. Light waves vibrate in two planes at right angles to one another, and passing ordinary light through certain substances eliminates the vibration in one plane. He discovered that the plane of vibration is rotated when the light path and the direction of the applied magnetic field are parallel. In particular, a linearly polarized wave can be decomposed into right and left circularly polarized waves where each wave propagates with different speeds. The waves can be considered to recombine upon emergence from the medium; however, owing to the difference in propagation speed, they do so with a net phase offset, resulting in a rotation of the angle of linear polarization.

The Faraday effect occurs in many solids, liquids, and gases. The magnitude of the rotation depends upon the strength of the magnetic field, the nature of the transmitting substance, and Verdets constant, which is a property of the transmitting substance, its temperature, and the frequency of light. The relation between the angle of rotation of the polarization and the magnetic field in a diamagnetic material is

$$\beta = \mathcal{V}Hd, \tag{1.72}$$

where

β is the angle of rotation

$\mathcal{V}$ is the Verdet constant for the material

H is the magnitude of the applied magnetic field

d is the length of the path where the light and magnetic field interact (see Figure 1.7)



FIGURE 1.7 The figure shows how the polarization of a linearly polarized beam of light rotates when it goes through a material exposed to an external magnetic field.

A positive Verdet constant corresponds to an anticlockwise rotation when the direction of propagation is parallel to the magnetic field and to a clockwise rotation when the direction of propagation is antiparallel. The Faraday effect is used in spintronics research to study the polarization of electron spins in semiconductors.

1.8.2 Quantum Faraday Effect

The Faraday effect is expected to emerge in low dimensional systems such as semiconductor quantum dots in which the spin states of the electron in the conduction band and the light and heavy hole in the valence band provide a system where different circular polarizations of light couple differently during the process of virtual absorption. The quantum analogue of the Faraday effect does not require an external magnetic field because it is created by selection rules (one circular polarization interacts with the heavy hole band while the other circular polarization interacts with the light hole band) and by the Pauli exclusion principle (the absorption of a right polarized wave is excluded because the allowed transition state between bands have the same spin) (Leuenberger et al., 2005b). In particular, we will be interested in the quantum Faraday effect in a semiconductor colloidal two-level quantum dot system. We can have a two-level system in a colloidal quantum dot where the heavy hole and the light hole bands are degenerate at the Γ point. This two-level system is achieved by the valence and the conduction band under certain assumptions: (1) the split-off band can be ignored since typical split-off energies are around 10^2 meV, thus bringing the energy level out of resonance with the single photon; (2) under the appropriate doping and thermal conditions, it can be assumed that the top of the valence band is filled with four electrons, while there is one excess electron in the conduction band; and (3) the energy of the electromagnetic wave is taken to be slightly below the effective band-gap energy, so that the transition from the top of the valence band to the bottom of the conduction band is the strongest transition by far (Leuenberger, 2006).



$|\frac{1}{2},-\frac{1}{2}\rangle$
$|\frac{1}{2},+\frac{1}{2}\rangle$
σ^+
σ^-
$\sigma^+ . e^{iS_o^{hh}}$
$\sigma^- . e^{iS_o^{lh}}$
σ^+
σ^-
$|\frac{1}{2},-\frac{1}{2}\rangle$
$|\frac{1}{2},+\frac{1}{2}\rangle$
$\sigma^+ . e^{iS_o^{hh}}$
$\sigma^- . e^{iS_o^{lh}}$
(a)
$|\frac{3}{2},-\frac{3}{2}\rangle$
$|\frac{3}{2},-\frac{1}{2}\rangle$
$|\frac{3}{2},+\frac{1}{2}\rangle$
$|\frac{3}{2},+\frac{3}{2}\rangle$
(b)
$|\frac{3}{2},-\frac{3}{2}\rangle$
$|\frac{3}{2},-\frac{1}{2}\rangle$
$|\frac{3}{2},+\frac{1}{2}\rangle$
$|\frac{3}{2},+\frac{3}{2}\rangle$

FIGURE 1.8 The solid circles represent filled states and dashed circles represent empty states. The electron in the conduction band interacts with the right or left circularly polarized electromagnetic wave allowing virtual transitions between the conduction and valence band states. After the interaction, the RCP and LCP electromagnetic wave acquire different phases, which produce the rotation of the incident wave.

Interestingly, the idea of the conditional single-photon Faraday rotation first developed by Leuenberger et al. (2005b) and already patented by the authors has been copied (Hu et al., 2008), which demonstrates the importance of this scheme.

We now turn our focus to the optical selection rules. In Figure 1.8 we show how different circular polarizations of the photon interact with the two-level system. The conduction band state has one electron with spin either up ($|\frac{1}{2},\frac{1}{2}\rangle$) or down ($|\frac{1}{2},-\frac{1}{2}\rangle$). The presence of a spin up (down) electron in the conduction band forces the virtual transitions of the incident electromagnetic wave to couple $|\frac{3}{2},-\frac{3}{2}\rangle$ ($|\frac{3}{2},-\frac{1}{2}\rangle$) or $|\frac{3}{2},\frac{1}{2}\rangle$ ($|\frac{3}{2},\frac{3}{2}\rangle$) heavy hole and light hole states depending if it is a right or left circularly polarized photon. Examination of the coefficients given in Equations 1.69 and 1.70 shows that the matrix elements of the heavy hole band and the matrix element involving the light hole band are different, leading to different phases and causing a change in the refractive index, which induces the Faraday rotation effect. The Faraday rotation is clockwise if the spin is up, and counterclockwise if the spin is down. The complex refractive index ($\tilde{\eta}$) can be calculated as follows:

$$\tilde{\eta}^2 = 1 - \frac{e^2 N}{\epsilon_0 m_e} \sum_{i,j} \frac{f_{ji}}{(\omega^2 - \omega_{ji}^2) + i\gamma\omega}, \tag{1.73}$$

where

$|e|$ is the electron's charge
N is the electron number density
ϵ_0 is the permittivity of free space
m_e is the mass of the electron
ω_{ji} is the transition frequency from the ith state to the jth state
γ is the full-width at half maximum (assumed to be much smaller than the detuning energy)
ω is the frequency of the incident electromagnetic wave
f_{ji} is the oscillator strength given by

$$f_{ji} = \frac{2}{m\hbar\omega_{ji}} |\langle j|(-e)\vec{r}\cdot\vec{E}|i\rangle|^2. \tag{1.74}$$

This quantum Faraday rotation can be used to measure the spin polarization of charge carriers in quantum wells (Kikkawa et al., 1997; Kikkawa and Awschalom, 1998, 1999). Recently, an experiment based on the quantum Faraday rotation was able to measure the spin state of a single excess electron inside a quantum dot (Berezovsky et al., 2006), which is crucial for the read-out of a qubit in a quantum computing scheme (see below).

1.9 Single-Photon Faraday Rotation

The single-photon Faraday effect (SPFE) is similar to the quantum Faraday effect but involves only the nonresonant interaction of a single photon with the quantum dot two-level system and can result in an entanglement of the photon with the spin of the extra electron (Leuenberger et al., 2005b; Leuenberger, 2006). The SPFE can be described by the Jaynes–Cummings Hamiltonian

$$\begin{aligned}\mathcal{H} = {} & \hbar\omega\left(a^\dagger_{\sigma^+}a_{\sigma^+} + a^\dagger_{\sigma^-}a_{\sigma^-}\right) + \hbar\omega_{\text{hh}}\sigma_{\frac{3}{2}v} + \hbar\omega_{\text{hh}}\sigma_{-\frac{3}{2}v} \\ & + \hbar\omega_{\text{lh}}\sigma_{\frac{1}{2}v} + \hbar\omega_{\text{lh}}\sigma_{-\frac{1}{2}v} + \hbar\omega_e\sigma_{\frac{1}{2}c} + \hbar\omega_e\sigma_{-\frac{1}{2}c} + \hbar g_{\frac{3}{2}v,\frac{1}{2}c} \\ & \times\left(a^\dagger_{\sigma^-}\sigma_{\frac{3}{2}v,\frac{1}{2}c} + a_{\sigma^-}\sigma_{\frac{1}{2}c,\frac{3}{2}v} + a^\dagger_{\sigma^+}\sigma_{-\frac{3}{2}v,-\frac{1}{2}c} + a_{\sigma^+}\sigma_{-\frac{1}{2}c,-\frac{3}{2}v}\right) \\ & + \hbar g_{\frac{1}{2}v,\frac{1}{2}c}\left(a^\dagger_{\sigma^-}\sigma_{\frac{1}{2}v,-\frac{1}{2}c} + a_{\sigma^-}\sigma_{-\frac{1}{2}c,\frac{1}{2}v} + a^\dagger_{\sigma^+}\sigma_{-\frac{1}{2}v,-\frac{1}{2}c} + a_{\sigma^+}\sigma_{\frac{1}{2}c,-\frac{1}{2}v}\right).\end{aligned} \tag{1.75}$$

Equation 1.76 describes how the right circularly polarized (σ^+) and left circularly polarized (σ^-) components of a linearly polarized photon field interact with the degenerate quantum dot levels in a cavity. It is assumed that the spin of the excess electron in the conduction band is up ($\uparrow$). The evolution of the system will be given by the state vector

$$|\Psi(t)\rangle = \frac{1}{\sqrt{2}}\Big[C_{\uparrow\mathrm{hh}}(t)|\uparrow,\mathrm{hh}\rangle + C_{\uparrow\sigma^+}(t)|\uparrow,\sigma_z^+\rangle + C_{\uparrow\mathrm{lh}}(t)|\uparrow,\mathrm{lh}\rangle + C_{\uparrow\sigma^-}(t)|\uparrow,\sigma_z^-\rangle\Big], \qquad (1.76)$$

where $|\uparrow,\mathrm{hh}\rangle$ and $|\uparrow,\mathrm{lh}\rangle$ are the states in which the quantum dot is in an excited state with a heavy-hole exciton or a light-hole exciton, and the spin of the excess electron in the conduction band is up. $|\uparrow,\sigma_z^+\rangle$ and $|\uparrow,\sigma_z^-\rangle$ are the states in which the quantum dot is in the ground state with the photon present in the cavity, and the spin of the extra electron in the conduction band is up.

In order to solve for the phase accumulated for RCP and LCP components of the linearly polarized photon during the interaction with the quantum dot in the nanocavity, we must find the time evolution of the probability amplitudes $C_{\uparrow\sigma+}(t)$ and $C_{\uparrow\sigma-}(t)$, respectively. Assuming the following initial conditions, $C_{\uparrow\mathrm{hh}}(0) = 0$, $C_{\uparrow\sigma+}(0) = 1$, $C_{\uparrow\mathrm{lh}}(0) = 0$, and $C_{\uparrow\sigma-}(0) = 1$, then the probability amplitudes of interest are given by (Seigneur et al., 2008)

$$C_{\uparrow\sigma^+}(t) = e^{-i\Delta t/2}\left[\cos\left(\frac{\Omega_{\frac{3}{2}}t}{2}\right) + \frac{i\Delta}{\Omega_{\frac{3}{2}}}\sin\left(\frac{\Omega_{\frac{3}{2}}t}{2}\right)\right] \qquad (1.77)$$

$$C_{\uparrow\sigma^-}(t) = e^{-i\Delta t/2}\left[\cos\left(\frac{\Omega_{\frac{1}{2}}t}{2}\right) + \frac{i\Delta}{\Omega_{\frac{1}{2}}}\sin\left(\frac{\Omega_{\frac{1}{2}}t}{2}\right)\right], \qquad (1.78)$$

where $\Omega^2_{\frac{3}{2}} = \Delta^2 + 4g^2_{\frac{3}{2}v,\frac{1}{2}c}$ and $\Omega^2_{\frac{1}{2}} = \Delta^2 + 4g^2_{\frac{1}{2}v,\frac{1}{2}c}$, with $g_{\frac{3}{2}v,\frac{1}{2}c}$ and $g_{\frac{1}{2}v,\frac{1}{2}c}$ being the coupling strength involving the heavy-hole electron and the light-hole electron, respectively, with $\Delta = \omega - \omega_{\mathrm{ph}}$ being the detuning frequency and $g_{\frac{3}{2}v,\frac{1}{2}c} = \sqrt{3}g_{\frac{1}{2}v,\frac{1}{2}c}$.

Rewriting the complex coefficients given in Equations 1.77 and 1.78 in the form $C_{\uparrow\sigma^+}(t) = |C_{\uparrow\sigma^+}(t)|\exp[iS_0^{\mathrm{hh}}]$ and $C_{\uparrow\sigma^-}(t) = |C_{\uparrow\sigma^-}(t)|\exp[iS_0^{\mathrm{lh}}]$, we obtain an expression for the phase accumulated during the interaction of the right and left circularly polarized component with the heavy-hole and the light-hole band, i.e.,

$$S_0^{\mathrm{hh}} = \tan^{-1}\left[\frac{\Delta}{\Omega_{\frac{3}{2}}}\tan\left(\frac{\Omega_{\frac{3}{2}}t}{2}\right)\right] \quad \text{and} \quad S_0^{\mathrm{lh}} = \tan^{-1}\left[\frac{\Delta}{\Omega_{\frac{1}{2}}}\tan\left(\frac{\Omega_{\frac{1}{2}}t}{2}\right)\right]. \qquad (1.79)$$

To determine the entanglement of the single photon with the electron, we know that the electron–photon state after the interaction reads

$$|\psi_{\mathrm{ep}}^{(1)}\rangle = e^{iS_0^{\mathrm{hh}}}|\psi_{\mathrm{hh}}^{(1)}\rangle + e^{iS_0^{\mathrm{lh}}}|\psi_{\mathrm{lh}}^{(1)}\rangle, \qquad (1.80)$$

where

$$|\psi_{\mathrm{hh}}^{(1)}\rangle = \frac{1}{\sqrt{2}}\left(\alpha|\Uparrow\rangle|\sigma_{(z)}^+\rangle + \beta|\Downarrow\rangle|\sigma_{(z)}^-\rangle\right) \qquad (1.81)$$

represents the photon scattering off a heavy hole, and

$$|\psi_{\mathrm{lh}}^{(1)}\rangle = \frac{1}{\sqrt{2}}\left(\alpha|\Uparrow\rangle|\sigma_{(z)}^-\rangle + \beta|\Downarrow\rangle|\sigma_{(z)}^+\rangle\right) \qquad (1.82)$$

represents the photon scattering off a light hole. Let

$$|\varphi\rangle = \cos\varphi|\leftrightarrow\rangle + \sin\varphi|\updownarrow\rangle \qquad (1.83)$$

be the photon state with linear polarization that is rotated by φ around the z-axis with respect to the state $|\leftrightarrow\rangle$ of linear polarization in x direction. Changing to circular polarization states, Equation 1.83 can be rewritten as

$$\begin{aligned}|\varphi\rangle &= \frac{\cos\varphi}{\sqrt{2}}\left(|\sigma_{(z)}^+\rangle + |\sigma_{(z)}^-\rangle\right) + \frac{\sin\varphi}{i\sqrt{2}}\left(|\sigma_{(z)}^+\rangle - |\sigma_{(z)}^-\rangle\right)\\ &= \frac{1}{\sqrt{2}}\left(e^{-i\varphi}|\sigma_{(z)}^+\rangle + e^{i\varphi}|\sigma_{(z)}^-\rangle\right).\end{aligned} \qquad (1.84)$$

Using the representation of this linear polarization with $\varphi = \pm(S_0^{\mathrm{hh}} - S_0^{\mathrm{lh}})/2 = \pm S_0/2$, we find that Equation 1.10 becomes

$$\begin{aligned}|\psi_{\mathrm{ep}}^{(1)}(T)\rangle &= \alpha|\Uparrow\rangle\left(e^{iS_0^{\mathrm{hh}}}|\sigma_{(z)}^+\rangle + e^{iS_0^{\mathrm{lh}}}|\sigma_{(z)}^-\rangle\right)\Big/\sqrt{2}\\ &\quad + \beta|\Downarrow\rangle\left(e^{iS_0^{\mathrm{lh}}}|\sigma_{(z)}^+\rangle + e^{iS_0^{\mathrm{hh}}}|\sigma_{(z)}^-\rangle\right)\Big/\sqrt{2}\\ &= e^{i\left(S_0^{\mathrm{hh}} + S_0^{\mathrm{lh}}\right)/2}\left(\alpha|\Uparrow\rangle|-S_0/2\rangle + \beta|\Downarrow\rangle|+S_0/2\rangle\right).\end{aligned} \qquad (1.85)$$

From this equation, we draw the conclusion that the accumulated CPHASE shift S_0 corresponds to a single-photon Faraday rotation around the z-axis by the angle $S_0/2$ due to a single spin. Let j be an integer. For $S_0/2 = (2j + 1)\pi/4$, the electron–photon state $|\psi_{\mathrm{ep}}^{(1)}\rangle$ is maximally entangled. If j is even,

$$|\psi_{\mathrm{ep}}^{(1)}\rangle = \alpha|\Uparrow\rangle|\text{⤡}\rangle + \beta|\Downarrow\rangle|\text{⤢}\rangle. \qquad (1.86)$$

If j is odd,

$$|\psi_{\mathrm{ep}}^{(1)}\rangle = \alpha|\Uparrow\rangle|\text{⤢}\rangle + \beta|\Downarrow\rangle|\text{⤡}\rangle. \qquad (1.87)$$



FIGURE 1.9 The conditional Faraday rotation of the linear polarization of the photon depends on the spin state $|\psi_e\rangle = \alpha\,|\uparrow\rangle + \beta\,|\downarrow\rangle$. If the spin state is up (down), the linear polarization turns (counter) clockwise. The photon and the spin get maximally entangled if the Faraday rotation angle is $S_0/2 = \pi/4$. This entanglement between photon polarization and electron spin can be used as an optospintronic link to transfer quantum information from electron spins to photons and back.

For $S_0/2 = 2j\pi/4$, the electron–photon state $|\,\psi_{\text{ep}}^{(1)}\rangle$ is not entangled. If j is even,

$$|\,\psi_{\text{ep}}^{(1)}(T)\rangle = \alpha\,|\uparrow\rangle\,|\leftrightarrow\rangle + \beta\,|\downarrow\rangle\,|\leftrightarrow\rangle. \tag{1.88}$$

If j is odd,

$$|\,\psi_{\text{ep}}^{(1)}(T)\rangle = \alpha\,|\uparrow\rangle\,|\updownarrow\rangle - \beta\,|\downarrow\rangle\,|\updownarrow\rangle. \tag{1.89}$$

This means the entanglement oscillates continually between 0 and 1 if no decoherence is present. The entanglement process between the spin of the electron and the polarization of the photon during the conditional Faraday rotation is visualized in Figure 1.9.

1.9.1 Quantifying the EPR Entanglement

Rewriting Equation 1.85 in the basis states of the linear polarization in x and y directions yields

$$\left|\psi_{\text{ep}}^{(1)}\right\rangle = \alpha\,|\uparrow\rangle\left(\cos\frac{S_0}{2}\,|\leftrightarrow\rangle - \sin\frac{S_0}{2}\,|\updownarrow\rangle\right) + \beta\,|\downarrow\rangle\left(\cos\frac{S_0}{2}\,|\leftrightarrow\rangle + \sin\frac{S_0}{2}\,|\updownarrow\rangle\right). \tag{1.90}$$

The entanglement between the photon and the spin of the excess electron can be calculated by means of the von Neumann entropy (Bennett et al., 1996):

$$E[\psi_{\text{ep}}^{(1)}] = -\mathrm{Tr}_{\text{e}}[\mathrm{Tr}_{\text{p}}\,\rho_{\text{ep}}\log_2(\mathrm{Tr}_{\text{p}}\,\rho_{\text{ep}})] \tag{1.91}$$

or the normalized linear entropy (Silberfarb and Deutsch, 2004)

$$E_{\text{L}}[\psi_{\text{ep}}^{(1)}] = 2[1 - \mathrm{Tr}_{\text{e}}(\mathrm{Tr}_{\text{p}}\,\rho_{\text{ep}})^2]. \tag{1.92}$$

We will use the linear entropy in our calculation. The density matrix is given by

$$\rho_{\text{ep}} = \begin{pmatrix} \rho_{\uparrow\uparrow} & \rho_{\uparrow\downarrow} \\ \rho_{\downarrow\uparrow} & \rho_{\downarrow\downarrow} \end{pmatrix}, \tag{1.93}$$

where

$$\rho_{\uparrow\uparrow} = \begin{pmatrix} |\alpha|^2\cos^2\frac{S_0}{2} & -2|\alpha|^2\sin S_0 \\ -2|\alpha|^2\sin S_0 & |\alpha|^2\sin^2\frac{S_0}{2} \end{pmatrix}, \tag{1.94}$$

$$\rho_{\uparrow\downarrow} = \begin{pmatrix} \alpha\beta^*\cos^2\frac{S_0}{2} & 2\alpha\beta^*\sin S_0 \\ -2\alpha\beta^*\sin S_0 & -\alpha\beta^*\sin^2\frac{S_0}{2} \end{pmatrix}, \tag{1.95}$$

$$\rho_{\downarrow\uparrow} = \begin{pmatrix} \alpha^*\beta\cos^2\frac{S_0}{2} & -2\alpha^*\beta\sin S_0 \\ 2\alpha^*\beta\sin S_0 & -\alpha^*\beta\sin^2\frac{S_0}{2} \end{pmatrix}, \tag{1.96}$$

$$\rho_{\downarrow\downarrow} = \begin{pmatrix} |\beta|^2\cos^2\frac{S_0}{2} & 2|\beta|^2\sin S_0 \\ 2|\beta|^2\sin S_0 & |\beta|^2\sin^2\frac{S_0}{2} \end{pmatrix}, \tag{1.97}$$

and thus by $\rho_{\text{ep}} =$

$$\begin{pmatrix} |\alpha|^2\cos^2\frac{S_0}{2} & -2|\alpha|^2\sin S_0 & \alpha\beta^*\cos^2\frac{S_0}{2} & 2\alpha\beta^*\sin S_0 \\ -2|\alpha|^2\sin S_0 & |\alpha|^2\sin^2\frac{S_0}{2} & -2\alpha\beta^*\sin S_0 & -\alpha\beta^*\sin^2\frac{S_0}{2} \\ \alpha^*\beta\cos^2\frac{S_0}{2} & -2\alpha^*\beta\sin S_0 & |\beta|^2\cos^2\frac{S_0}{2} & 2|\beta|^2\sin S_0 \\ 2\alpha^*\beta\sin S_0 & -\alpha^*\beta\sin^2\frac{S_0}{2} & 2|\beta|^2\sin S_0 & |\beta|^2\sin^2\frac{S_0}{2} \end{pmatrix} \tag{1.98}$$

in the basis $|\uparrow\rangle\,|\leftrightarrow\rangle$; $|\uparrow\rangle\,|\updownarrow\rangle$; $|\downarrow\rangle\,|\leftrightarrow\rangle$; $|\downarrow\rangle\,|\updownarrow\rangle$. Since the measures for entanglement must be independent of the chosen basis, all of the measures involve the trace of ρ_{ep}. Taking the trace over the photon states yields

$$\mathrm{Tr}_{\text{p}}\,\rho_{\text{ep}} = \begin{pmatrix} |\alpha|^2 & \alpha\beta^*\cos S_0 \\ \alpha^*\beta\cos S_0 & |\beta|^2 \end{pmatrix}. \tag{1.99}$$

So we obtain the entanglement

$$E_{\text{L}}[\psi_{\text{ep}}^{(1)}] = 2\left(1 - |\alpha|^4 - |\beta|^4 - 2|\alpha|^2|\beta|^2\cos^2 S_0\right). \tag{1.100}$$

With the parametrization $\alpha = \cos\frac{\eta}{2}e^{-i\chi/2}$, $\beta = \sin\frac{\eta}{2}e^{-i\chi/2}$ we obtain

$$E_{\text{L}}[\psi_{\text{ep}}^{(1)}] = 2\left(1 - \cos^4\frac{\eta}{2} - \sin^4\frac{\eta}{2} - \frac{1}{2}\sin^2\eta\cos^2 S_0\right). \tag{1.101}$$

This result is plotted in Figure 1.10.

1.9.2 Single Photon Faraday Effect and GHZ Quantum Teleportation

The theory of quantum teleportation was first developed by Bennett et al. (1993) and later experimentally verified by Bouwmeester et al. (1997). This scheme relies on EPR pairs,



FIGURE 1.10 Entanglement of the photon with the spin of the excess electron.

i.e., pairs of entangled particles, which can be entangled in, for example, the polarization degree of freedom in the case of photons or the spin degree of freedom in the case of electrons or holes. Leuenberger et al. (2005b) show that all the three particles that take part in the teleportation process are entangled in a so-called Greenberger–Horne–Zeilinger (GHZ) state (Greenberger et al., 1989, 1990).

We will perform now a GHZ teleportation. In this GHZ quantum teleportation, the photon (qubit 2) interacts first with the electron spin of the destination (qubit 3) and then with the electron spin of the origin (qubit 1). We identify qubit 1, 2, and 3 with the qubits used by Bennett et al. (1993). Qubit 1 is with Alice, qubit 2 with Charlie, and qubit 3 with Bob. We start from the state $|\Psi^{(1)}_{\mathrm{pe}'}(t_A)\rangle = |\leftrightarrow\rangle|\leftarrow'\rangle$. After interaction in Bob's microcavity, we obtain

$$
\begin{aligned}
|\Psi^{(1)}_{\mathrm{pe}'}(t_{\mathrm{C}})\rangle &= \frac{1}{\sqrt{2}}\Big(|\sigma_z^{+}\rangle|\uparrow'_y\rangle + |\sigma^{-}_{(z)}\rangle|\downarrow'_y\rangle\Big) \\
&= \frac{1}{\sqrt{2}}(|\nwarrow\!\!\!\searrow\rangle|\swarrow\!\!\!\nearrow\rangle|\downarrow'\rangle). \qquad (1.102)
\end{aligned}
$$

This hybrid photon–spin entangled state corresponds to the shared EPR state of qubit 2 and 3 in the original version of the teleportation (EPR teleportation). Note that there is no way to distinguish between a single-spin or a single-photon Faraday rotation because we do not have any preferred basis defined by α and β. We have not yet used qubit 1 at all. Alice's photon can be stored for as long as it maintains its entanglement with Bob's spin. This step is like the distribution of the EPR pair in EPR teleportation. Instead of performing now a Bell measurement on qubit 1 and 2 to complete the EPR teleportation, we let the photon (qubit 2) interact with Alice's spin (qubit 1), giving rise to a GHZ state in the hybrid spin–photon–spin system. After interaction of the photon in Alice's microcavity, we obtain

$$
\begin{aligned}
|\psi^{(1)}_{\mathrm{epe}'}(t_{\mathrm{C}}+T)\rangle = \frac{1}{\sqrt{2}}\Big[\alpha|\uparrow\rangle\Big(&e^{iS_0^{\mathrm{hh}}}|\sigma^{+}_{(z)}\rangle|\uparrow'_y\rangle \\
&+e^{iS_0^{\mathrm{lh}}}|\sigma^{-}_{(z)}\rangle|\downarrow'_y\rangle\Big) \\
&+\beta|\downarrow\rangle\Big(e^{iS_0^{\mathrm{lh}}}|\sigma^{+}_{(z)}\rangle\Big|\uparrow'_y\Big\rangle \\
&+e^{iS_0^{\mathrm{hh}}}|\sigma^{-}_{(z)}\rangle|\downarrow'_y\rangle\Big)\Big]. \qquad (1.103)
\end{aligned}
$$

Now we change to the S_z representation of Bob's spin and to the linear polarization representation of Charlie's photon, which yields ($t_{\mathrm{C}} = 0$)

$$
\begin{aligned}
|\psi^{(1)}_{\mathrm{epe}'}(T)\rangle = \frac{e^{i\left(S_0^{\mathrm{hh}}+S_0^{\mathrm{lh}}\right)/2}}{\sqrt{2}}\Big(&\alpha|\uparrow\rangle|-S_0/2-\pi/4\rangle|\uparrow'\rangle \\
&+\alpha|\uparrow\rangle|-S_0/2+\pi/4\rangle|\downarrow'\rangle \\
&+\beta|\downarrow\rangle|+S_0/2-\pi/4\rangle|\uparrow'\rangle \\
&+\beta|\downarrow\rangle|+S_0/2+\pi/4\rangle|\downarrow'\rangle. \qquad (1.104)
\end{aligned}
$$

Choosing $S_0 = \pi/2$, we obtain

$$
\begin{aligned}
|\psi^{(1)}_{\mathrm{epe}'}(T)\rangle = \frac{1}{\sqrt{2}}\Big[&|\updownarrow\rangle\Big(-\alpha|\uparrow\rangle|\uparrow'\rangle+\beta|\downarrow\rangle|\downarrow'\rangle\Big) \\
&+|\leftrightarrow\rangle\Big(\alpha|\uparrow\rangle|\downarrow'\rangle+\beta|\downarrow\rangle|\uparrow'\rangle\Big)\Big]. \qquad (1.105)
\end{aligned}
$$

[From this equation, it becomes obvious that we can produce all the four Bell states between qubit 1 (Alice's electron spin) and qubit 3 (Bob's electron spin).] Now we change to the S_x representation of Alice's spin:

$$
\begin{aligned}
|\psi^{(1)}_{\mathrm{epe}'}(T)\rangle = \frac{1}{\sqrt{2}}|\updownarrow\rangle\Big[&|\leftarrow\rangle\Big(-\alpha|\uparrow'\rangle+\beta|\downarrow'\rangle\Big) \\
&+|\rightarrow\rangle\Big(-\alpha|\uparrow'\rangle-\beta|\downarrow'\rangle\Big)\Big] \\
+\frac{1}{\sqrt{2}}|\leftrightarrow\rangle\Big[&|\leftarrow\rangle\Big(\beta|\uparrow'\rangle+\alpha|\downarrow'\rangle\Big) \\
&+|\rightarrow\rangle\Big(\beta|\uparrow'\rangle-\alpha|\downarrow'\rangle\Big)\Big]. \qquad (1.106)
\end{aligned}
$$

The difference between our method and the original version of the teleportation (Bennett et al., 1993) is that we have entangled qubit 2 (the photon) with qubit 1 (Alice's electron spin) by means of the electron–photon interaction, which is not done in the original version. That is why we do not need Bell measurements. So after measuring the photon polarization state (qubit 2) and the spin state of Alice's electron (qubit 1), the spin state of the electron of the destination gets projected onto $-\alpha|\uparrow'\rangle + \beta|\downarrow'\rangle$, $-\alpha|\uparrow'\rangle - \beta|\downarrow'\rangle$, $\beta|\uparrow'\rangle + \alpha|\downarrow'\rangle$, or $\beta|\uparrow'\rangle - \alpha|\downarrow'\rangle$ with equal probability. This corresponds exactly to the outcome of the original version of the teleportation. However, we do not use any Bell measurements.

Let us check what happens if there is no interaction between Charlie's photon and Alice's spin. Then we get

$$|\psi^{(1)}_{\mathrm{epe}'}(T)\rangle = \frac{1}{\sqrt{2}}\Big[|\nwsearrow\rangle\big(\alpha|\uparrow\rangle|\uparrow'\rangle + \beta|\downarrow\rangle|\uparrow'\rangle\big) + |\neswarrow\rangle\big(\alpha|\uparrow\rangle|\downarrow'\rangle + \beta|\downarrow\rangle|\downarrow'\rangle\big)\Big]. \tag{1.107}$$

In this case, we would have to apply a Bell measurement in order to perform the teleportation.

1.9.3 Single-Photon Faraday Effect and Quantum Computing

Recently, the *destructive probabilistic* CNOT gate for all-optical quantum computing proposed by Knill et al. (2001), which relies on postselection by measurements, has been implemented experimentally (O'Brien et al., 2003; Nemoto and Munro, 2004). Based on a proposal by Pittman et al. (2001), experiments have demonstrated that this destructive CNOT gate and a quantum parity check can be combined with a pair of entangled photons to produce a *nondestructive probabilistic* CNOT gate (Pittman et al., 2002a,b, 2003; Gasparoni et al., 2004; Zhao et al., 2005). It has been shown theoretically that deterministic quantum computing with postselection is feasible for quantum systems where the qubits are represented by several degrees of freedom of a single photon (Cerf et al., 1998). An interferometric approach to linear-optical deterministic CNOT gate between the polarization and momentum of a single photonic qubit has recently been demonstrated experimentally (Fiorentino and Wong, 2004). A general scheme to teleport a quantum state through a universal gate has been given by Gottesman and Chuang (1999). This idea gave Raussendorf and Briegel the inspiration to develop the one-way quantum computer (Raussendorf and Briegel, 2001; Raussendorf et al., 2003), which performs quantum computations by measurement-induced teleportation processes on an entangled network of qubits. The name one-way quantum computing refers to the irreversibility of the computations due to the measurement processes.

Leuenberger developed a scheme for fault-tolerant quantum computing with the excess electron spins in quantum dots based on the SPFE (Leuenberger, 2006). This scheme shares a similarity with the one-way quantum computing scheme in the sense that it makes use of measurement processes to perform quantum computations. Both the one-way quantum computing scheme and Leuenberger's scheme are fully deterministic and scalable to an arbitrary number of qubits. However, while the one-way quantum computing scheme is irreversible, Leuenberger's scheme is fully reversible. In addition, the one-way quantum computing scheme needs to maintain the coherence of the whole cluster of qubits and is therefore more sensitive to the environment than single isolated qubits, since in a cluster the decoherence of one qubit leads also to decoherence of neighboring qubits that are entangled to it. Therefore, Leuenberger's scheme is more robust in this respect.



FIGURE 1.11 The nonresonant interaction of a photon with Alices and Bobs quantum dot produces the CPHASE gate required for universal quantum computing. This CPHASE gate applies to the case of the noncoded spins, where each microcavity contains only a single quantum dot with a single excess electron.

We describe now Leuenberger's quantum computing scheme (see Figure 1.11). DiVincenzo showed that the CNOT gate and a single qubit rotation are sufficient for universal quantum computing (DiVincenzo, 1995). In the framework of the conditional Faraday rotation, it is easier to work with the implementation of the CPHASE gate than with the implementation of the CNOT gate. The CPHASE gate

$$u_{\mathrm{CPHASE}} = \begin{pmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ 0 & 0 & 0 & -1 \end{pmatrix} \tag{1.108}$$

is equivalent (similar) to the CNOT gate (see Equation 1.7), i.e., they can be transformed into each other by means of a basis transformation. The CPHASE gate shifts the phase only if both spins point down. Let us define two persons Alice and Bob. Both of them have one photonic crystal, in which n noninteracting quantum dots are embedded. The single excess electrons of Alice's quantum dots are in a general single-spin state $|\psi\rangle_A = \alpha|\uparrow\rangle_A + \beta|\downarrow\rangle_A$, where the quantization axis is the z-axis. Bob's spins are in a general single-spin state $|\psi\rangle_B = \gamma|\uparrow\rangle_B + \delta|\downarrow\rangle_B$. The photons that interact with both Alice's and Bob's quantum dots are initially in a horizontal linear polarization state $|\leftrightarrow\rangle$.

Since there is no need to detect optically the spin states in transverse direction (Leuenberger et al., 2005a), our quantum dots can be nonspherical. So each photon can virtually create only a heavy-hole exciton on each quantum dot (see Figure 1.6). The strong selection rules imply that only a $\sigma^+_{(z)}(\sigma^-_{(z)})$ photon can interact with the quantum dot if the excess electron's spin is up (down). This leads to a conditional Faraday rotation of the linear polarization of the photon depending on the spin state of the quantum dot. The photonic crystal ensures that the photon's propagation direction is always in z-direction, perpendicular to the quantum dot plane.

In Leuenberger's implementation of the CPHASE gate, a single photon interacts sequentially with Alice's and then with Bob's quantum dot. The spin on Alice's quantum dot is prepared in the state $|\psi_A(0)\rangle = \alpha|\uparrow\rangle_A + \beta|\downarrow\rangle_A$. So we start with the electron–photon state $|\psi_{Ap}(0)\rangle = (\alpha|\uparrow\rangle_A + \beta|\downarrow\rangle_A)|\leftrightarrow\rangle$. After the interaction with Alice's quantum dot, the resulting electron–photon state is

$$|\psi_{Ap}(T)\rangle = \left(\alpha|\uparrow\rangle_A|\nwsearrow\rangle + \beta|\downarrow\rangle_A|\neswarrow\rangle\right)/\sqrt{2}, \tag{1.109}$$

which is maximally entangled.

We let the photon interact also with Bob's quantum dot, which yields

$$\begin{aligned}|\psi_{ApB}(2T)\rangle &= |\updownarrow\rangle\left(-\alpha\gamma|\uparrow\rangle_A|\uparrow\rangle_B + \beta\delta|\downarrow\rangle_A|\downarrow\rangle_B\right)\\ &\quad + |\leftrightarrow\rangle\left(\alpha\delta|\uparrow\rangle_A|\downarrow\rangle_B + \beta\gamma|\downarrow\rangle_A|\uparrow\rangle_B\right)\\ &= \frac{1}{\sqrt{2}}\Big[|\nwsearrow\rangle\big(-\alpha\gamma|\uparrow\rangle_A|\uparrow\rangle_B + \beta\delta|\downarrow\rangle_A|\downarrow\rangle_B\\ &\quad + \alpha\delta|\uparrow\rangle_A|\downarrow\rangle_B + \beta\gamma|\downarrow\rangle_A|\uparrow\rangle_B\big)\\ &\quad + |\neswarrow\rangle\big(\alpha\gamma|\uparrow\rangle_A|\uparrow\rangle_B - \beta\delta|\downarrow\rangle_A|\downarrow\rangle_B\\ &\quad + \alpha\delta|\uparrow\rangle_A|\downarrow\rangle_B + \beta\gamma|\downarrow\rangle_A|\uparrow\rangle_B\big)\Big].\end{aligned} \tag{1.110}$$

If the linear polarization of the photon is measured in the ↘ axis, we obtain the two results

$$\begin{aligned}|\psi_{AB}(2T)\rangle &= -\alpha\gamma|\uparrow\rangle_A|\uparrow\rangle_B + \beta\delta|\downarrow\rangle_A|\downarrow\rangle_B\\ &\quad + \alpha\delta|\uparrow\rangle_A|\downarrow\rangle_B + \beta\gamma|\downarrow\rangle_A|\uparrow\rangle_B,\end{aligned} \tag{1.111}$$

$$\begin{aligned}|\psi_{AB}(2T)\rangle &= \alpha\gamma|\uparrow\rangle_A|\uparrow\rangle_B - \beta\delta|\downarrow\rangle_A|\downarrow\rangle_B\\ &\quad + \alpha\delta|\uparrow\rangle_A|\downarrow\rangle_B + \beta\gamma|\downarrow\rangle_A|\uparrow\rangle_B\end{aligned} \tag{1.112}$$

with equal probability, where the CPHASE shift is π if both spins are up or both spins are down, respectively. For deterministic quantum computing, we need to choose either Equation 1.111 or 1.112 to be the correct phase gate. Let us choose Equation 1.112 to be the correct implementation. The measurement of the photon's polarization state must be shared through a classical channel between Alice and Bob, in order for the CPHASE gate to be deterministic. Then Equation 1.111 can be transformed into Equation 1.112 by two local single-qubit phase shifts $\sigma_{A,z}\sigma_{B,z}$ applied to Alice's and Bob's qubit, where σ_z is a Pauli matrix. This scheme for implementing the CPHASE gate is similar to the scheme of quantum teleportation in the sense that the measurement outcome of the photon's polarization needs to be shared between Alice and Bob through a classical channel. This scheme for implementing the CPHASE gate is a generalization of the scheme of quantum teleportation in the sense that it takes not only one local unitary operation but two unitary operations to reconstruct the desired two-qubit state, which makes sense, because we perform a two-qubit manipulation, as opposed to a single qubit manipulation in the case of quantum teleportation.

Thus, we can produce deterministically the CPHASE gate, which is equivalent to the CNOT gate in the basis $\{|\uparrow\rangle_A|\leftarrow\rangle_B, |\uparrow\rangle_A|\rightarrow\rangle_B, |\downarrow\rangle_A|\leftarrow\rangle_B, |\downarrow\rangle_A|\rightarrow\rangle_B\}$, where $|\leftarrow\rangle = (|\uparrow\rangle + |\downarrow\rangle)/\sqrt{2}$ and $|\rightarrow\rangle = (|\uparrow\rangle - |\downarrow\rangle)/\sqrt{2}$ in the S_x representation. This can be proven by writing down the mappings

$$\begin{aligned}|\uparrow\rangle_A|\leftarrow\rangle_B &= \frac{1}{\sqrt{2}}|\uparrow\rangle_A\left(|\uparrow\rangle_B + |\downarrow\rangle_B\right)\\ &\rightarrow \frac{1}{\sqrt{2}}|\uparrow\rangle_A\left(-|\uparrow\rangle_B + |\downarrow\rangle_B\right) = -|\uparrow\rangle_A|\rightarrow\rangle_B,\\ |\uparrow\rangle_A|\rightarrow\rangle_B &= \frac{1}{\sqrt{2}}|\uparrow\rangle_A\left(|\uparrow\rangle_B - |\downarrow\rangle_B\right)\\ &\rightarrow \frac{1}{\sqrt{2}}|\uparrow\rangle_A\left(-|\uparrow\rangle_B - |\downarrow\rangle_B\right) = -|\uparrow\rangle_A|\leftarrow\rangle_B,\\ |\downarrow\rangle_A|\leftarrow\rangle_B &= \frac{1}{\sqrt{2}}|\downarrow\rangle_A\left(|\uparrow\rangle_B + |\downarrow\rangle_B\right)\\ &\rightarrow \frac{1}{\sqrt{2}}|\downarrow\rangle_A\left(|\uparrow\rangle_B + |\downarrow\rangle_B\right) = |\downarrow\rangle_A|\leftarrow\rangle_B,\\ |\downarrow\rangle_A|\rightarrow\rangle_B &= \frac{1}{\sqrt{2}}|\downarrow\rangle_A\left(|\uparrow\rangle_B - |\downarrow\rangle_B\right)\\ &\rightarrow \frac{1}{\sqrt{2}}|\downarrow\rangle_A\left(|\uparrow\rangle_B - |\downarrow\rangle_B\right) = |\downarrow\rangle_A|\rightarrow\rangle_B,\end{aligned} \tag{1.113}$$

corresponding to the CPHASE gate in Equation 1.111, and

$$\begin{aligned}|\uparrow\rangle_A|\leftarrow\rangle_B &= \frac{1}{\sqrt{2}}|\uparrow\rangle_A\left(|\uparrow\rangle_B + |\downarrow\rangle_B\right)\\ &\rightarrow \frac{1}{\sqrt{2}}|\uparrow\rangle_A\left(|\uparrow\rangle_B + |\downarrow\rangle_B\right) = -|\uparrow\rangle_A|\leftarrow\rangle_B,\\ |\uparrow\rangle_A|\rightarrow\rangle_B &= \frac{1}{\sqrt{2}}|\uparrow\rangle_A\left(|\uparrow\rangle_B - |\downarrow\rangle_B\right)\\ &\rightarrow \frac{1}{\sqrt{2}}|\uparrow\rangle_A\left(|\uparrow\rangle_B - |\downarrow\rangle_B\right) = |\uparrow\rangle_A|\rightarrow\rangle_B,\\ |\downarrow\rangle_A|\leftarrow\rangle_B &= \frac{1}{\sqrt{2}}|\downarrow\rangle_A\left(|\uparrow\rangle_B + |\downarrow\rangle_B\right)\\ &\rightarrow \frac{1}{\sqrt{2}}|\downarrow\rangle_A\left(|\uparrow\rangle_B - |\downarrow\rangle_B\right) = |\downarrow\rangle_A|\rightarrow\rangle_B,\\ |\downarrow\rangle_A|\rightarrow\rangle_B &= \frac{1}{\sqrt{2}}|\downarrow\rangle_A\left(|\uparrow\rangle_B - |\downarrow\rangle_B\right)\\ &\rightarrow \frac{1}{\sqrt{2}}|\downarrow\rangle_A\left(|\uparrow\rangle_B + |\downarrow\rangle_B\right) = |\downarrow\rangle_A|\leftarrow\rangle_B,\end{aligned} \tag{1.114}$$

corresponding to the CPHASE gate in Equation 1.112.

For universal quantum computing, the CPHASE gate described above and single-qubit operations are sufficient (Barenco et al., 1995; DiVincenzo, 1995). The single-qubit operations on Alice's and Bob's spins can be implemented by means of the optical Stark effect (Gupta et al., 2001). In contrast to Imamoglu et al.'s two-qubit gate (Imamoglu et al., 1999), which relies on a shared mode volume for the exchange of a single virtual photon between the two qubits, this scheme requires only local mode volumes for each qubit separately and is therefore fully scalable to an arbitrary number of qubits. Since the strong interaction between a quantum dot and a cavity inside a photonic crystal has already been experimentally observed (Yoshie et al., 2004), it would be possible to build a fully scalable quantum network inside a photonic crystal hosting qubits, which can be for example spins of excess electrons in semiconductor quantum dots or N-V center states in diamond.

1.10 Concluding Remarks

Quantum computers have excited many researchers because they would perform a kind of parallel processing that would be extremely effective for certain tasks, such as searching databases and factoring large numbers. Also, quantum computers can be used to simulate or model quantum systems and could bring huge advances in physics, chemistry, and nanotechnology. Recently, diamond has become very attractive for solid state electronics. Pure diamond is an electrical insulator, but on doping, it can become a semiconductor. The particular impurity that researchers are interested in is the nitrogen-vacancy (N-V) center. The N-V center has a number of properties and characteristics that make it very promising to build a quantum computer (Awschalom et al., 2007). The N-V center electrons have a spin state that is extremely stable against environmental disturbances. One of the most exciting aspects of the N-V center is that it exhibits quantum behavior even at room temperature; this characteristic is very important because it makes this kind of systems easy to study and easy to turn into a practical technology. Other important aspects of N-V centers come from the fact that they have weak spin–orbit interaction and dipole–dipole interaction, which make the spin state very stable and it can be used to encode quantum information even at room temperatures. The decoherence time of the N-V center spin is about 1 ms and the operation time is about 10 ns, therefore $R = \tau_d/\tau_s =$ 100,000 operations that can be performed in the millisecond lifetime of the spin quantum system. This rate of decay is well below the threshold and better than any other system of solid-state qubits to date.

Acknowledgments

We acknowledge support from NSF-ECCS 0725514, the DARPA/MTO Young Faculty Award HR0011-08-1-0059, NSF-ECCS 0901784, and AFOSR FA9550-09-1-0450. We would also like to thank Sergio Tafur for his comments on improving the manuscript.

References

Adamowski, J., S. Bednarek, and B. Szafram. Quantum computing with quantum dots. *Schedae Inform.*, 14:95–111, 2005.

Ahn, J., Weinacht, T.C., and P.H. Bucksbaum. Information storage and retrieval through quantum phase. *Science*, 287: 463–465, 2000.

Awschalom, D.D., R. Epstein, and R. Hanson. The diamond age of spintronics. *Sci. Am.*, 297:84–91, 2007.

Barenco, A., D. Deutsch, A. Ekert, and R. Josza. Conditional quantum dynamics and logic gates. *Phys. Rev. Lett.*, 74:4083, 1995.

Bennett, C.H., G. Brassard, C. Crépeau, R. Jozsa, A. Peres, and W.K. Wootters. Teleporting an unknown quantum state via dual classical and Einstein–Podolsky–Rosen channels. *Phys. Rev. Lett.*, 70:1895–1899, 1993.

Bennett, C.H., D.P. DiVincenzo, J.A. Smolin, and W.K. Wootters. Mixed-state entanglement and quantum error correction. *Phys. Rev. A*, 54:3824–3851, 1996.

Berezovsky, J., M.H. Mikkelsen, O. Gywat, N.G. Stoltz, L.A. Coldren, and D.D. Awschalom. Nondestructive optical measurements of a single electron spin in a quantum dot. *Science*, 314:1916, 2006.

Bouwmeester, D., J.-W. Pan, K. Mattle, M. Eibl, H. Weinfurter, and A. Zeilinger. Experimental quantum teleportation. *Nature*, 390:575, 1997.

Cerf, N.J., C. Adami, and P.G. Kwiat. Optical simulation of quantum logic. *Phys. Rev. A*, 57:R1477, 1998.

Deutsch, D. Quantum theory, the Church–Turing principle, and the universal quantum computer. *Proc. R. Soc. Lond. A*, 400:97–117, 1985.

DiVincenzo, D.P. Two-bit quantum gates are universal for quantum computation. *Phys. Rev. A*, 51:1015–1022, 1995.

DiVincenzo, D.P. The physical implementation of quantum computation, in *Scalable Quantum Computers*, S.L. Braunstein and H.K. Lo (eds.), Wiley, Berlin, Germany, 2001.

Feynman, R.P. Simulating physics with computers. *Int. J. Theor. Phys.*, 21:467–488, 1982.

Fiorentino, M. and F.N.C. Wong. Deterministic controlled-not gate for single-photon two-qubit quantum logic. *Phys. Rev. Lett.*, 93:070502, 2004.

Friedman, J.R., M.P. Sarachik, J. Tejada, and R. Ziolo. Macroscopic measurement of resonant magnetization tunneling in high-spin molecules. *Phys. Rev. Lett.*, 76:3830–3833, 1996.

Gasparoni, S., J.-W. Pan, P. Walther, T. Rudolph, and A. Zeilinger. Realization of a photonic controlled-not gate sufficient for quantum computation. *Phys. Rev. Lett.*, 93:020504, 2004.

Gottesman, D. and I.L. Chuang. Demonstrating the viability of universal quantum computation using teleportation and single-qubit operations. *Nature*, 402:390, 1999.

Greenberger, D.M., M.A. Horne, and A. Zeilinger. in *Bell's Theorem, Quantum Theory, and Conceptions of the Universe*. Kluwer, Dordrecht, the Netherlands, p. 73, 1989.

Greenberger, D.M., M.A. Horne, A. Shimony, and A. Zeilinger. Bell theorem without inequalities. *Am. J. Phys.*, 58:1131, 1990.

Grover, L.K. Quantum mechanics helps in searching for a needle in a haystack. *Phys. Rev. Lett.*, 79:325–328, 1997.

Gupta, J.A., R. Knobel, N. Samarth, and D.D. Awschalom. Ultrafast manipulation of electron spin coherence. *Science*, 292:2458, 2001.

Hu, C.Y., A. Young, J.L. O'Brien, W.J. Munro, and J.G. Rarity. Giant optical Faraday rotation induced by a single-electron spin in a quantum dot: Applications to entangling remote spins via a single photon. *Phys. Rev. B*, 78:085307, 2008.

Imamoglu, A., D.D. Awschalom, G. Burkard, D.P. DiVincenzo, D. Loss, M. Sherwin, and A. Small. Quantum information processing using quantum dot spins and cavity QED. *Phys. Rev. Lett.*, 83:4204, 1999.

Kasuya, T. A theory of metallic ferro- and antiferromagnetism on Zener's model, *Prog. Theor. Phys.* 16:45, 1956.

Kikkawa, J.M. and D.D. Awschalom. Resonant spin amplification in n-type gas. *Phys. Rev. Lett.*, 80:4313, 1998.

Kikkawa, J.M. and D.D. Awschalom. Lateral drag of spin coherence in gallium arsenide. *Nature*, 397:139, 1999.

Kikkawa, J.M., I.P. Smorchkova, N. Samarth, and D.D. Awschalom. Room-temperature spin memory in two-dimensional electron gases. *Science*, 277:1284, 1997.

Knill, E., R. Laflamme, and G.J. Milburn. A scheme for efficient quantum computation with linear optics. *Nature*, 409:46, 2001.

Leuenberger, M.N. Fault-tolerant quantum computing with coded spins using the conditional Faraday rotation in quantum dots. *Phys. Rev. B*, 73:075312–8, 2006.

Leuenberger, M.N. and D. Loss. Spin relaxation in Mn12-acetate. *EuroPhys. Lett.*, 46:692–698, 1999.

Leuenberger, M.N. and D. Loss. Spin tunneling and phonon-assisted relaxation in Mn12-acetate. *Phys. Rev. B*, 61:1286–1302, 2000a.

Leuenberger, M.N. and D. Loss. Incoherent Zener tunneling and its application to molecular magnets. *Phys. Rev. B*, 61:12200–12203, 2000b.

Leuenberger, M.N. and D. Loss. Quantum computing in molecular magnets. *Nature*, 410:789–793, 2001.

Leuenberger, M.N., D. Loss, M. Poggio, and D.D. Awschalom. Quantum information processing with large nuclear spins in gas semiconductors. *Phys. Rev. Lett.*, 89:207601–4, 2002.

Leuenberger, M.N., F. Meier, and D. Loss. Quantum spin dynamics in molecular magnets. *Monatshefte Chem.*, 134:217–233, 2003.

Leuenberger, M.N., M.E. Flatté, and D.D. Awschalom. Teleportation of electronic many-qubit states encoded in the electron spin of quantum dots via single photons. *Phys. Rev. Lett.*, 94:107401–4, 2005a.

Leuenberger, M.N., M.E. Flatté, and D.D. Awschalom. Teleportation of electronic many-qubit states encoded in the electron spin of quantum dots via single photons. *Phys. Rev. Lett.*, 94:107401–4, 2005b.

Loss, D. and D.P. DiVincenzo. Quantum computation with quantum dots. *Phys. Rev. A*, 57:120–126, 1998.

Nemoto, K. and W.J. Munro. Nearly deterministic linear optical controlled-not gate. *Phys. Rev. Lett.*, 93:250502, 2004.

O'Brien, J.L., G.J. Pryde, A.G. White, T.C. Ralph, and D. Branning. Demonstration of an all-optical quantum controlled-not gate. *Nature*, 426:264, 2003.

Piermarocchi, C., P. Chen, and L.J. Sham. Optical RKKY interaction between charged semiconductor quantum dots. *Phys. Rev. Lett.*, 89:167402, 2002.

Pittman, T.B., B.C. Jacobs, and J.D. Franson. Probabilistic quantum logic operations using polarizing beam splitters. *Phys. Rev. A*, 64:062311, 2001.

Pittman, T.B., B.C. Jacobs, and J.D. Franson. Demonstration of feed-forward control for linear optics quantum computation. *Phys. Rev. A*, 66:052305, 2002a.

Pittman, T.B., B.C. Jacobs, and J.D. Franson. Demonstration of nondeterministic quantum logic operations using linear optical elements. *Phys. Rev. Lett.*, 88:257902, 2002b.

Pittman, T.B., M.J. Fitch, B.C. Jacobs, and J.D. Franson. Experimental controlled-not logic gate for single photons in the coincidence basis. *Phys. Rev. A*, 68:032316, 2003.

Raussendorf, R. and H.J. Briegel. A one-way quantum computer. *Phys. Rev. Lett.*, 86:5188–5191, 2001.

Raussendorf, R., D.E. Browne, and H.J. Briegel. Measurement-based quantum computation on cluster states. *Phys. Rev. A*, 68:022312, 2003.

Ruderman, M.A. and C. Kittel. Indirect exchange coupling of nuclear magnetic moments by conduction electrons, *Phys. Rev*. 96:99, 1954.

Sangregorio, C., T. Ohm, C. Paulsen, R. Sessoli, and D. Gatteschi. Quantum tunneling of the magnetization in an iron cluster nanomagnet. *Phys. Rev. Lett.*, 78:4645–4648, 1997.

Seigneur, H.P., M.N. Leuenberger, and W.V. Schoenfeld. Single-photon Mach–Zehnder interferometer for quantum networks based on the single-photon Faraday effect. *J. Appl. Phys.*, 104:014307–13, 2008.

Shor, P. Scheme for reducing decoherence in quantum computer memory. *Phys. Rev. A*, 52:2493–2496, 1995.

Shor, P. Polynomial-time algorithms for prime factorization and discrete logarithms on a quantum computer. *SIAM J. Comput.*, 26:1484–1509, 1997.

Silberfarb, A. and I.H. Deutsch. Entanglement generated between a single atom and a laser pulse. *Phys. Rev. A*, 69:042308–8, 2004.

Thiaville, A. and J. Miltat. Small is beautiful. *Science*, 284:1939–1940, 1999.

Thomas, L., F. Lionti, R. Ballou, D. Gatteschi, R. Sessoli, and B. Barbara. Macroscopic quantum tunnelling of magnetization in a single crystal of nanomagnets. *Nature*, 383: 145–147, 1996.

Wernsdorfer, W., R. Sessoli, A. Caneshi, D. Gatteschi, and A. Cornia. Nonadiabatic Landau–Zener tunneling in Fe8 molecular nanomagnets. *EuroPhys. Lett.*, 50:552–558, 2000.

Yoshie, T., A. Scherer, J. Hendrickson, G. Khitrova, H.M. Gibbs, G. Rupper, C. Ell, O.B. Shchekin, and D.G. Deppe. Vacuum Rabi splitting with a single quantum dot in a photonic crystal nanocavity. *Nature*, 432:200, 2004.

Yosida, K. Magnetic properties of Cu-Mn alloys, *Phys. Rev*. 106:893, 1957.

Zhao, Z., A.-N. Zhang, Y.-A. Chen, H. Zhang, J.-F. Du, T. Yang, and J.-W. Pan. Experimental demonstration of a nondestructive controlled-not quantum gate for two independent photon qubits. *Phys. Rev. Lett*., 94:030501, 2005.

2

Nanomemories Using Self-Organized Quantum Dots

2.1 Introduction 2-1
2.2 Conventional Semiconductor Memories 2-2
Dynamic Random Access Memory • Nonvolatile Semiconductor Memories (Flash)
2.3 Nonconventional Semiconductor Memories 2-4
Ferroelectric RAM • Magnetoresistive RAM • Phase-Change RAM
2.4 Semiconductor Nanomemories 2-6
Charge Trap Memories • Single Electron Memories
2.5 A Nanomemory Based on III–V Semiconductor Quantum Dots 2-7
III–V Semiconductor Materials • Self-Organized Quantum Dots • A Memory Cell Based on Self-Organized QDs
2.6 Capacitance Spectroscopy 2-10
Depletion Region • Capacitance Transient Spectroscopy
2.7 Charge Carrier Storage in Quantum Dots 2-16
Carrier Storage in InGaAs/GaAs Quantum Dots • Hole Storage in GaSb/GaAs Quantum Dots • InGaAs/GaAs Quantum Dots with Additional AlGaAs Barrier • Storage Time in Quantum Dots
2.8 Write Times in Quantum Dot Memories 2-21
Hysteresis Measurements • Write Time Measurements
2.9 Summary and Outlook 2-23
Acknowledgments 2-23
References 2-24

Martin Geller
University of Duisburg-Essen

Andreas Marent
Technische Universität Berlin

Dieter Bimberg
Technische Universität Berlin

2.1 Introduction

One of the fundamental achievements of today's information society is providing storage and processing of ever-increasing amounts of data that is based on basic research in physics in combination with fundamental technology developments over the last four decades. As no low-cost universal memory that is suited for all kinds of applications exists, digital data storage is separated mainly into three different lines:

1. The digital versatile disk (DVD) and the compact disk (CD) are nonvolatile storage media based on an *optical* write and read-out process using laser light at wavelengths of 650 and 780 nm, respectively. The newest representative of optical data storage is the Blu-ray disk, using a laser wavelength at 405 nm with a maximum capacity of up to 50 GB disk^{-1}.
2. The hard-disk drive in a personal computer is a nonvolatile mass storage device with a capacity of up to 1000 GB in production year 2008 that uses the *magnetization* of rapidly rotating platters.
3. *Semiconductor* memories are the third line of digital storage media and will be the focus of this chapter with a perspective of future nanomemories.

Semiconductor memories can be divided into two groups: volatile memories, like the dynamic random access memory (DRAM), and nonvolatile memories, the so-called Flash. The DRAM presents the main working memory in a personal computer. Flash memories are found, for example, in mp3 players, cell phones, and memory sticks; in automobiles and microwave ovens; and have started to replace the hard-disk drive in notebooks as well as the DVD and CD as easily portable high-capacity nonvolatile memories. Driven by the increasing demand for such portable electronic applications, where nonvolatile data storage with low power consumption is needed, the market for Flash memories is growing rapidly and is replacing the DRAM as the market driver.

Up to now, the semiconductor memory industry improved the storage density and performance while simultaneously reducing the cost per information bit just by scaling down the feature size. This leads to an exponentially growing number of components on a memory chip as predicted by Moore in 1965 (Moore 1965) known nowadays as "Moore's Law." Contrary to all predictions, Moore's Law has held remarkably well over the last decades. The feature size for Flash memories has reached 45 nm in 2008. The International Roadmap for Semiconductors (ITRS 2008) predicts a further shrinkage down to 14 nm in 2020. The problems encountered during this shrinking process were mainly solved by developing new materials, for example, for isolation and interconnects, and for new types of cell structures. Upon further size reduction, quantum mechanics will dominate at least some of the physical properties. In addition, the amount of technological difficulties to realize such structures increases enormously. Therefore, a considerable effort is devoted to the search for alternative memory technologies that are even based on completely new non-semiconducting materials. Phase change access memories (PCRAMs), magnetic random access memories (MRAMs), and ferroelectric RAM (FeRAMs) are just three alternative memory concepts that are explored for having the potential to replace today's DRAM and/or Flash memory.

One completely different technology is the use of self-organized nanomaterials in future nanoelectronic devices. Especially self-organized quantum dots (QDs) based on III–V materials (e.g., GaAs, InAs, InP, etc.) provide a number of important advantages for new generations of nanomemories. Billions of self-organized QDs can be formed simultaneously and fast in a single technological step, allowing for massive parallel production in a bottom-up approach, and offering an elegant method to create huge ensembles of electronic traps without lithography. They can store just a few or even single charge carriers with a retention time depending on the material combination—potentially up to many years at room temperature. With an area density of up to 10^{11} cm^{-2}, an enormous storage density in the order of 1 TBit per square inch could be possible, if each single QD would represent one information bit and could be addressed individually. The carrier capture process into the QDs is of the order of pico to sub-picoseconds, an important prerequisite for a very fast write time in such memories. The use of self-organized QDs could thus lead to novel nonvolatile memories with high storage density combined with a fast read/write access time.

Using self-organized QDs for future semiconductor memory applications is discussed in this chapter. Section 2.2 gives a brief overview of the main semiconductor memories, DRAM and Flash, while the following Section 2.3 concentrates on three nonconventional memories that may replace Flash or DRAM in the future. Section 2.5 presents an alternative nanomemory concept that is based on III–V materials, especially self-organized QDs. By using capacitance spectroscopy, introduced in Section 2.6, the carrier storage time in different QD systems is studied in Section 2.7 and a storage time of seconds at room temperature is demonstrated. Finally, the chapter will show results on fast write times in QD-based nanomemories in Section 2.8 and will close with a summary and outlook in Section 2.9.

2.2 Conventional Semiconductor Memories

Presently the semiconductor memory industry focuses essentially on two memory types: the DRAM (Mandelman et al. 2002, Waser 2003) and the Flash (Geppert 2003). Both memory concepts have their advantages and disadvantages in speed, endurance, storage time, and cost. A memory concept that adds the advantages of a DRAM to a Flash would combine high storage density, fast read/write access, long data storage time, and good endurance with low production cost. In addition, for portable applications like mobile phones and mp3 players, low power consumption is demanded. This section describes the two conventional semiconductor memories, while Section 2.3 will focus on nonconventional alternatives that have the potential to replace DRAM and/or Flash.

2.2.1 Dynamic Random Access Memory

Since the invention of the DRAM in the late 1960s (Dennard 1968), its cell structure mainly stayed the same, consisting of a transistor and a capacitor (cf. Figure 2.1a). The capacitor stores the information by means of electric charge. The charge state is defined by the voltage level on the capacitor. The stored charge



FIGURE 2.1 (a) Schematic picture of an array of DRAM cells, where the capacitors act as the storage units. Each cell can be addressed individually by a matrix of word- and bit-lines; it is the so-called random-access architecture. (b) Cell layout for a planar DRAM cell.

disappears typically in a few milliseconds mainly due to leakage and recombination currents. A DRAM is volatile and requires periodic "refreshing" of the stored charge. After any read process, the information has to be rewritten into the DRAM cell. A chip on the integrated circuit controls the refresh rewrite process automatically and this continuous read and write operation has led to the name "Dynamic."

Figure 2.1b shows schematically the layout of a simple planar DRAM cell (Sze 2002). The storage capacitor uses the inversion channel region as one plate, the storage gate as the other plate, and the gate oxide as the dielectric. The access transistor is a metal oxide semiconductor field effect transistor (MOSFET) with a source, drain, and a gate contact. The drain contact is connected to the storage capacitor. The source contact is connected to the bit-line and the gate contact to the word-line. Via word- and bit-line, a single cell can be addressed in an organized matrix of DRAM cells (Figure 2.1a). This so-called "random access" provides short access times independent of the location of the data (Waser 2003). For a write/read operation, a voltage pulse is passed through the selected bit- and word-line. Only at the crossing point of a given DRAM cell, the access transistor switches to "open" and the capacitor is charged or discharged for a write or read event, respectively.

DRAM cells provide fast read, write, and erase access times below 20 ns in combination with a very good endurance of more than 10^{15} write/erase cycles. The endurance is defined as the minimum number of possible write/erase operations until the memory cell is destroyed. DRAM memory cells draw power continuously due to the refresh process and the information is lost after switching off the computer. Another disadvantage is the relatively large number of electrons, presently in the order of 10^5, needed to store one information bit, leading additionally to permanent high power consumption. Both, the volatility and the power consumption make DRAMs unsuitable for mobile applications.

The goal to shrink the feature size, based on the assumption of scalability, of a DRAM (Kim et al. 1998) down to 14 nm by 2020 is a major challenge. It is speculated that the leakage currents of the capacitor might inhibit the scalability very soon. A fixed capacitance of the order of 50 pF is needed to maintain a sufficiently high voltage signal during the read-out process. Shrinking the area of the capacitor will decrease its capacitance, the number of stored electrons per DRAM cell, and the amplitude of the read-out signal. Downscaling increases leakage currents due to quantum-mechanical tunneling through thinner dielectrics (Frank et al. 2001). Therefore, there is a search for novel dielectrics.

2.2.2 Nonvolatile Semiconductor Memories (Flash)

Nonvolatile memories (NVMs) can retain their data for typically more than 10 years without power consumption. The most important nonvolatile memory is the Flash-EEPROM (electrically erasable and programmable read-only memory); in short just Flash (Geppert 2003, Lai 2008). A Flash offers the possibility of repeated electrical read, write, and erase processes. The Flash memory market is the fastest growing memory market today, since it is the ideal memory device for portable applications. In a mobile phone, it holds the instructions and data needed to send and receive calls, or stores phone numbers. But not only portable applications are ideal for Flash. In each computer, a Flash chip holds the data on how to boot up. Other electronic products of all types, from microwaves ovens to industrial machines, store their operating instructions in Flash memories.

Flash is based on a floating-gate structure (Pavan et al. 1997, Sze 1999), where the charge carriers are trapped inside a polysilicon floating gate embedded between two SiO_2 barriers (Figure 2.2a). The SiO_2 barriers having a height of ~3.2 eV and an average thickness of 10 nm guarantee a storage time of more than 10 years at room temperature. However, these barriers are also the origin of the two main disadvantages of a Flash cell: a slow write time (in the order of microseconds) and a poor endurance (in the order of 10^6 write/erase cycles).

The write process is realized by means of "hot-electron injection." Here a small voltage is applied between the source contact and the bit-line (drain contact) (cf. Figure 2.2b). The word-line (control gate) is set to a high positive bias of 10–20 V, the MOSFET is set to "open" and the electrons flow though the inversion channel from the source to drain and are, in addition, accelerated in the direction of the floating-gate due to the high electric field in the order of 10^7 V cm^{-1}. These "hot-electrons" have sufficient kinetic energy to reach the floating gate over one of the SiO_2 barriers, but destroy this barrier step by step by



FIGURE 2.2 (a) Schematic band structure of a Flash memory based on Si as matrix material and SiO_2 for the oxide barriers. (b) Schematic cell layout of a floating-gate Flash memory.

Memory	Write	Read	Storage	Electrons	Endurance
DRAM	~10 ns	~10 ns	~ms	>10,000	$>10^{15}$
Flash	µs–ms	~20 ns	>10 years	~1,000	$\sim 10^{6}$

FIGURE 2.3 Comparison of DRAM and Flash.

creating defects leading eventually to leakage. This is the reason for the poor endurance of a Flash memory cell. The slow write time is due to the low probability for energy relaxation of these hot-electrons into the floating gate.

The read-out of the stored information is normally done by measuring the resistance of the two-dimensional electron gas (2DEG) of the MOSFET—the inversion channel. A bias is applied at the gate contact, forming inversion between the source and the drain. Stored electrons in the floating gate reduce the conductivity of the 2DEG and a higher resistance between the source and the drain is measured.

Figure 2.3 compares the main properties of the DRAM and Flash. The Flash memory has already replaced the DRAM as a technology driver for the semiconductor memory industry (Mikolajick et al. 2007) in the year 2003. It is leading in storage density and the main innovations are coming from the Flash industry. The feature size of the Flash has decreased from 1.5 µm in the year 1990 down to 45 nm in the year 2008. Accordingly, the number of electrons decreased from about 10^5 to less than 1000 per information bit (Atwood 2004) (cf. Figure 2.4). A further shrinkage to 14 nm in the year 2020, as predicted, would lead to only 100 electrons per information bit.

Flash memory scaling beyond 32 nm feature size will become more and more difficult, mainly due to the physical limitations (Atwood 2004). For instance, during the hot-electron injection a voltage of about 4.5 V is applied between the source and the drain. Shrinking the gate length while keeping the write voltage fixed at 4.5 V, leads to an increased electric field in the source–drain channel and in the end to a punch-through. Another limitation for future scaling is the capacitive coupling between different floating gates (cross talk) and the scalability of the floating gate. While the number of electrons decreases to about 200 per cell in year 2020, the main charge leakage mechanisms will remain. Dangling bonds and other defects at the Si/SiO$_2$ interface will dramatically decrease the storage time while scaling to smaller cell sizes.



FIGURE 2.4 Electron number per Flash memory cell versus the minimum feature size. The feature size decreases from 1.5 µm in the production year 1990 down to 45 nm in the year 2008. Accordingly, the number of electrons decreased from about 10^5 to less than 1000 per information bit.

2.3 Nonconventional Semiconductor Memories

The increasing number of difficulties and challenges for further scaling of the DRAM and Flash has led to a continuous search for alternative memory concepts. A large variety of proposed concepts using different physical phenomena to store an information bit have been reported (Burr et al. 2008). This section concentrates on three nonconventional memories, which are the most advanced ones (Geppert 2003, Burr et al. 2008): the ferroelectric RAM (FeRAM), the magnetic RAM (MRAM), and the phase-change RAM (PCRAM).

2.3.1 Ferroelectric RAM

The ferroelectric RAM (FeRAM) (Jones et al. 1995, Sheikholeslami and Gulak 2000) has almost the same structure as a DRAM cell, except for the capacitor. The dielectric inside the capacitor of a DRAM is a non-ferroelectric material like silicon dioxide. When the charge is stored on the metal plates of the capacitor, it leaks away into the silicon substrate within a few milliseconds, causing the nonvolatility of a DRAM cell. In a FeRAM, a ferroelectric film such as zirconate titanate, also known as PZT, replays the dielectric of the capacitor. This ferroelectric material has a remnant polarization that occurs when an electric field has been applied. In PZT the center atom is zirconium or titanium which can be moved by an external electric field into two different stable states, representing a “0” or “1” in a ferroelectric memory. One state is near the top face of the PZT cube, the other one is near the bottom face. Even after removal of the external electric field, these stable states store the information for more than 10 years. When an opposite electric field is applied, the dipoles flip to the opposite direction, that is, the zirconium or titanium atoms are switching into the other stable state.

The write operations of a “0” and “1” state in a FeRAM are in principle the same as in a DRAM cell. An electric pulse via a word and a bit-line switches the ferroelectric state of the PZT. To read an information bit, an electrical pulse is applied via the access transistor to the ferroelectric capacitor and a sense amplifier can measure a current pulse. The amplitude depends on the position of the zirconium or titanium atoms in the PZT cube. For instance, if the external electric field from the pulse is pointing in the same direction of the PZT, that is, the atoms are already at the top of the cube and a smaller current pulse is detected than for opposite direction.

Reading the information in a FeRAM cell destroys the data stored in its ferroelectric capacitor. After a read operation, the information has to be rewritten into the FeRAM cell, which is a major disadvantage in comparison to the Flash memory based on a floating-gate structure. However, the FeRAM is nonvolatile having a random read/write access time below 50 ns and an almost unlimited endurance ($>10^{12}$ write/erase cycles).

2.3.2 Magnetoresistive RAM

The magnetoresistive RAM (Gallagher and Parkin 2006, Wolf et al. 2006, Burr et al. 2008) uses the giant magnetoresistance (GMR) effect that was discovered in the late 1980s by the groups of Albert Fert (Baibich et al. 1988) and Peter Grunberg (Binasch et al. 1989). Grunberg and Fert received the Nobel Prize in Physics 2007 for their discovery.

The MRAM is based on a magnetic tunnel junction (MTJ) (see Figure 2.5a), which consists of two magnetic layers separated by a thin insulating layer (like AlOx) with a thickness in the order of 1 nm. One of the ferromagnetic layers has a fixed magnetization, while the other layers can flip its magnetization by an external writing event. The read-out of the information in a MRAM cell works as follows: if the access transistor for a certain cell is turned on, a current is driven through the MTJ and the resistance of the MRAM cell is measured. If the two magnetic moments are parallel, the resistance is low, representing a “0” state. If the moments are antiparallel, the resistance is high, representing a “1” state. The difference between these two values can be up to 70%, therefore, GMR.



(a) Read-out process



(b) Write process

FIGURE 2.5 Schematic picture of the read (a) and write (b) process of an MRAM cell. During read out a current passes through the MTJ. If the magnetization of the two magnetic layers is parallel to each other a low resistance is measured; if the magnetization is antiparallel the resistance is high. The write process is based on current flow through both the bit and digit line. The sum of both currents is strong enough to flip the magnetic domains inside the free magnetic layer to a “1” or “0” state, depending on the current direction inside the lines.

The physical effect that leads to this GMR effect is called tunnel magnetoresistance (TMR). The TMR effect can be understood in terms of spin polarized tunneling of the electrons. The electron spins are polarized inside one magnetic layer and if the spin is conserved during tunneling through the thin insulator layer, an initially spin up electron can only tunnel to a spin up final state. If the magnetic layers have parallel magnetic moments, a higher current is detected than for antiparallel directions.

The write mechanism can be understood by looking at Figure 2.5b. During the write mode, a current is passing through two wires: a bit-line that runs over the MTJ and a digit line that is below. The sum of both currents is strong enough to flip the magnetic domains inside the free magnetic layer to a “1” or “0” state, depending on the current direction. Both magnetic states are stable for more than 10 years; hence, an MRAM is a nonvolatile memory device with a random-access architecture and unlimited endurance. In addition, the write/read time has been demonstrated to be below 50 ns. However, scaling MRAM to smaller feature sizes is a big challenge as the write current has to remain very high (>1 mA), even if the feature size goes below 40 nm. Such large currents in very small devices might damage the structure.

2.3.3 Phase-Change RAM

The architecture of the phase-change RAM (PCRAM)—also called ovonic unified memory (OUM)—is again an array of access transistors that are connected to a word- and a bit-line. The capacitor is now replaced by a phase-change material (Geppert 2003, Burr et al. 2008). The PCRAM uses the large resistance change between a (poly) crystalline and an amorphous state in a chalcogenide glass, which is also used in rewritable CDs and DVDs. The chalcogenides used for this type of memory are alloys containing elements like selenium, tellurium, or antimony (GeSbTe, GeTe, Sb_2Te_3, etc.). The crystalline and amorphous states show a large difference of up to five orders of magnitude in the electrical resistance, representing the binary state “1” for low resistance and the state “0” for high resistance. The read-out can easily be done by a measurement of the resistance of the PCRAM cell.

Besides the chalcogenide, the PCRAM cell consists of a top and a bottom electrode that are connected to the word- and bit-line and a resistive heater below the phase-change material (see Figure 2.6). To switch the state of the cell to the crystalline



FIGURE 2.6 The PCRAM is based on a chalcogenide that can exist in two different states: in the (poly) crystalline state the resistance is low (representing a "1"), while the resistance is high in the amorphous state (representing a "0"). Switching to the amorphous state is done by heating the programmable volume up to its melting point with the resistive heater and cooling down rapidly. To make it crystalline, the heater is switched on for a short time period (~50 ns) to heat the volume above its crystallization temperature.

one, a short write pulse is applied that heats the programmable volume just below its melting point and holds it there for a certain time. This SET operation limits the write speed of the PCRAM because of the required duration to crystallize the phase-change material. The write speed is in the order of tens of nanoseconds (~50 ns), depending on the used material. In the RESET operation, the memory cell is switched to the amorphous "0" state by applying a larger electrical current (~mA) in the order of 100 ns that heats up the phase-change material just above the melting point.

The PCRAM access time is presently longer than for the MRAM. However, the write/erase time improves with scaling, as the active programmable volume is getting smaller and shorter write/erase pulses are sufficient to switch the state of the phase-change material. The read operation shows a very good scaling that gives PCRAM the highest market potential among all nonconventional memory concepts that could replace the Flash memory in the future. A big disadvantage is the endurance of a PCRAM cell (10^7–10^{12}), being above the conventional Flash cell but several orders of magnitude away from the DRAM ($>10^{15}$).

2.4 Semiconductor Nanomemories

The semiconductor memory industry has already entered the "nano-world" years ago and has introduced a feature size of 45 nm in the year 2008. To improve the device performance of a conventional Flash cell, nanomaterials have been used as replacements for the floating gate. For instance, replacing the Si floating gate with Si nanocrystals—Si particles with diameters in the order of 1–10 nm—leads to the advantage that charge leakage from any particular nanocrystal does not discharge the complete floating gate. The ultimate goal would be the usage of only one nanocrystal as one information bit to build a single electron memory.

This section will briefly review semiconductor memories based on charge traps and silicon nanocrystals in Section 2.4.1 and a single electron memory based on silicon QD in Section 2.4.2.

2.4.1 Charge Trap Memories

One of the major drawbacks is the limited number of write/erase cycles of a conventional Flash cell, the poor endurance. This will be a major problem during scaling down the feature size and simultaneously the thickness of the SiO_2 tunneling barrier. A single defect in the tunneling oxide will always destroy the entire Flash cell. The simplest way to improve the endurance of a conventional Flash memory and, hence, to extend the scalability is to replace the floating gate by a charge trapping material, schematically illustrated in Figure 2.7.

A charge trapping memory cell can be realized in different approaches. One possibility is to use a dielectric material that stores the charges in deep traps. Silicon nitride is the most established among such materials and the memory cell is often referred to as oxide–nitride–oxide, short just ONO (Lai 2008). A variation of this type of charge trapping device is the SONOS (silicon–oxide–nitride–oxide–silicon) (White et al. 2000). Figure 2.7a illustrates the floating-gate structure and the SONOS device principle. The thin silicon-nitrite (Si_3N_4) film is the storage unit where a single defect in the oxide layer will not discharge the complete memory cell. In addition, SONOS cells show a reduced cross talk and lower read/write voltages.

A second alternative to create a charge trapping memory is the usage of nanoparticles as the floating gate. The first attempts of such memory devices were made by Lambe and Jaklevic



FIGURE 2.7 (a) Schematic picture of a SONOS nonvolatile charge trapping memory that consists instead of a Si floating gate of an oxide–nitride–oxide (ONO) sandwich. The nitride layer can store charges (electrons or holes) in deep traps. (b) A nanocrystal Flash based on silicon nanoparticles.

(1969) 40 years ago. They used an array of Al droplets—with a diameter in the order of 10 nm—embedded in thin oxide and observed a memory effect in capacitance measurements. Tiwari et al. (1996) embedded Si nanocrystals into a floating-gate structure to improve the Flash concept with nanomaterials. The principle of such memory devices is depicted in Figure 2.7b. The Si nanocrystals are fabricated through spontaneous decomposition during chemical vapor deposition onto the tunneling oxide barrier. These particles have a typical size in the order of about 1–10 nm. Replacing the floating gate with these Si nanocrystals has the advantage that charge leakage through defect inside the oxide layer will not completely discharge the whole memory cell. Thinner tunneling barriers can be used and an improved endurance is observed.

2.4.2 Single Electron Memories

One charge carrier inside a single nanocrystal or QD for one information bit is the ultimate goal for a memory cell. Such devices were realized with a single polysilicon QD embedded into an oxide matrix (Guo et al. 1997). This device showed a storage time of 5 s at room temperature and is schematically depicted in Figure 2.8. It was fabricated by electron beam lithography (EBL) and reactive ion etching (RIE). A source–drain channel with a width between 25 and 120 nm was created onto an oxide layer, followed by a second oxide layer and the polysilicon dot. The dot had a width of about 20 nm and is covered again by silicon oxide and polysilicon as a gate electrode. By an appropriate bias on the control gate, the single dot is charged and discharged at room temperature and the charge state—the read-out of the information—was possible via a resistance measurement of the source–drain channel.

This measurement demonstrates perfectly the possibility of single charge storage and read-out even at room temperature without conductance quantization inside the source–drain channel. However, these structures were fabricated via EBL, which is not suitable for mass production and the storage time is limited to 5 s at 300 K.



FIGURE 2.8 Schematic picture of single electron memory device based on a polysilicon QD above a silicon channel. The silicon channel is connected to a source and drain contact to measure the resistance of the channel. The charge state can be written and erased by the polysilicon control gate. (After Guo, L. et al., *Appl. Phys. Lett.*, 70(7), 850, 1997.)

2.5 A Nanomemory Based on III–V Semiconductor Quantum Dots

In this section, a memory concept based on III–V nanomaterials—self-organized QDs—that has the potential to overcome the drawbacks of the current conventional Flash and DRAM is presented (Geller et al. 2006a). Such a nanomemory cell should provide long storage times (>10 years) and good endurance (>10^{15} write/erase cycles) in combination with even better read/write access time than the DRAM (<10 ns). In addition, an ultimate memory cell should store one information bit by means of as few carriers as possible, let it be electrons or holes, to compete with the ongoing miniaturization in the semiconductor memory industry. With a lateral feature QD size of about 7–20 nm—depending on the material combination and growth conditions—to have a single QD as one information bit is a must for the future. Comparing this QD size with the predicted feature size of conventional Flash presented in Figure 2.4, one expects that the QD memory could be competitive for the next 10 years. A major challenge for such QD-based memory will be to address a single self-organized QD. However, a lot of work has been focused on QD alignment in two-dimensional arrays that would allow addressing a single self-organized QD in the future. An overview on QD alignment can be found in Kiravittaya et al. (2009).

This section concentrates on a brief introduction to III–V semiconductor hetereostructures and self-organized QDs in Sections 2.5.1 and 2.5.2, respectively. The last subsection will focus on a nanomemory concept based on these QDs.

2.5.1 III–V Semiconductor Materials

Metal organic chemical vapor deposition (MOCVD) or molecular beam epitaxy (MBE) are epitaxial growth techniques to deposit different defect-free semiconductor materials with different electronic properties (e.g., band offsets) on each other. Such a semiconductor crystal, made of more than one material, is referred to as a "heterostructure," and the interface between the two materials as "heterojunction." The electronic properties of the entire heterostructure are mainly determined by this heterojunction. Heterostructures pave the way to design devices with tailored optical or electronic properties.

The use of heterojunctions has led to the development of many device families like the double heterostructure (DHS) laser or the hetero-bipolar transistor, both invented in 1963 by Alferov and Kroemer (Alferov and Kazarinov 1963, Kroemer 1963) and honored with the Nobel prize in physics in the year 2000. Alferov built the first DHS semiconductor laser using gallium arsenide (GaAs) and aluminum arsenide (AlAs) in 1969.

By using epitaxial growth techniques, it is also easily possible to create ternary alloys, for instance $Al_xGa_{1-x}As$, which exhibit a bandgap smoothly varying between the binary alloys. Figure 2.9 shows the energy bandgap as a function of lattice constant for different III–V compound semiconductors (points) and their ternary alloys (lines) at zero temperature. The III–V compound



FIGURE 2.9 Energy bandgap as a function of lattice constant for different III–V compound semiconductors (points) and their ternary alloys (lines) at zero temperature. (After Vurgaftman, I. et al. *J. Appl. Phys.*, 89, 5815, 2001.)

semiconductors and their ternary alloys offer a large variety of material combinations in heterostructure devices with the possibility of a controlled band-structure engineering.

For a semiconductor heterostructure, besides the energy bandgap, the relative energetic position of the valence and conduction band at the interface is of central importance: the so-called band alignment. The band alignment and the bandgap control the band offsets in the conduction and valence band. The band offset is simply defined as the discontinuity in the band edges at the interface between the two semiconductors. Figure 2.10 shows the various types of band alignments that can arise for semiconductor heterojunctions: type I, type II staggered, and type II broken-gap. For a type I alignment, the bandgap of the narrower gap semiconductor E_g^2 lies completely within the bandgap of the wider gap E_g^1, shown in Figure 2.10a. This band alignment occurs in a large number of technically important heterojunctions, for example, InAs/GaAs, GaAs/AlGaAs, and GaSb/AlSb. For a type II staggered band alignment, the bandgaps of the two materials show only partial overlap (Figure 2.10b). An example for a type II staggered band alignment is GaSb/GaAs, which plays an important role for memories based on self-organized QDs. A type II broken-gap alignment occurs, when the bandgaps of the two materials do not overlap at all (Figure 2.10c).



FIGURE 2.10 Types of band alignment at a heterojunction consisting of two semiconductors with different bandgap E_g^1 and E_g^2. The conduction and valence band edges have been labeled with E_C and E_V, while the conduction and valence band offsets have the label ΔE_C and ΔE_V, respectively.

2.5.2 Self-Organized Quantum Dots

Self-organized QDs are low-dimensional heterostructures (Bimberg et al. 1998) that confine electrons and/or holes in all three spatial directions. Such a zero-dimensional system exhibits the electronic and optical properties like "artificial" atoms and offers lots of possibilities for new applications, for example, in electronic devices such as field effect transistors (Kim et al. 2000, Koike et al. 2000) as well as in optoelectronic devices such as lasers (Kirstaedter et al. 1994, Heinrichsdorff et al. 2000, Kuntz et al. 2004, Hopfer et al. 2006), detectors (Campbell et al. 1997, Chu et al. 2001), amplifiers (Lämmlin et al. 2006), and single-photon sources (Santori et al. 2002, Lochmann et al. 2006) or memory cells as described in this chapter.

The fabrication of QDs is based on self-organization effects on crystal surfaces first reported by Stranski and Krastanow (1938). On a flat substrate surface, a layer of a material with a different lattice constant is deposited, leading to a strained wetting layer. The strain energy can be reduced by forming small islands from the material of the wetting layer. These small structures with dimensions in the nanometer range can be very regular in size and shape and can confine carriers in all three dimensions (Shchukin et al. 1995, 2003). The term Stranski–Krastanow growth mode (SK-growth) was reintroduced in heteroepitaxy for the formation of islands on an initially two-dimensional layer. The formation of coherent, that is, defect free islands as a result of SK-growth is today exploited to fabricate QDs (Eaglesham and Cerullo 1990, Mo et al. 1990). Self-organized QDs have often a pyramidal or truncated pyramidal shape (Heinrichsdorff et al. 1996, Eisele et al. 1999) with typical base widths and heights in the order of 7–30 nm and 2–5 nm, respectively, depending on the growth conditions and material combinations.

The reduction of the extension of the QDs to values below the de Broglie wavelength leads to charge carrier localization in all three directions and the disappearance of the continuous $E(k)$ dispersion, called band structure. As in a real atom, the resulting energy level structure is discrete. The QD provides a confining potential of finite depth for electrons and/or holes. Figure 2.11 shows schematically two types of QDs: type I QDs (like InAs/GaAs) confine electrons and holes, while a type II QD confines either electrons or holes. The depicted type II GaSb/GaAs QD system has a localization potential for holes only and provides a barrier for the electrons in the conduction band. The localization energy represents the energy difference of the confined electron or hole states with respect to the conduction or valence band edge, equivalent to the binding energy.

The single particle states in self-organized QDs depend on two structural properties: size and shape, and the chemical composition. The influence of the QD geometry on the electron and



FIGURE 2.11 Schematic picture of the electron and hole states in a type I InAs/GaAs (a) and in a type II GaSb/GaAs (b) QD system. A type I QD confines electrons as well as holes, while a type II QD confines either electrons or holes. The depicted type II GaSb/GaAs QD confines only holes and has a potential barrier for electrons in the conduction band.

hole states can be understood in principle from a simple particle-in-a-box model (Grundmann et al. 1995, Stier et al. 1999). For an infinite potential well, the quantum-mechanical solution predicts energy separation and nonzero energy for the lowest level, depending on the size of the box. In contrast, the confining barrier in buried QDs is of finite height, given by the band offsets. Only a finite number of bound states exist, depending on the QD size and shape. As the QD becomes smaller, the separations between the electron and hole levels increase—quantum size effect—and all states are lifted in energy toward the valence/conduction band edge. Below a certain size, no bound electron and/or hole state exists.

Self-organized QDs can trap electrons or holes, storing these charge carriers for a certain time depending on the emission processes involved. Therefore, QDs may store information like a memory cell. Carrier emission limits the storage time in a QD-based memory. Confined charge carriers can escape by the following four mechanisms: thermal activation, tunneling, phonon-assisted tunneling, and optical activation. Phonon-assisted tunneling is a combination process of tunneling and thermal activation. The charge carrier is thermally activated by phonons to a higher energy state E_1 (a real or virtual state) and tunnels subsequent to the conduction or valence band through a barrier. The mechanisms are schematically depicted in Figure 2.12 for electron escape into the conduction band. Whether a charge state and, hence, the information bit is destroyed by one of the emission processes depends on the electric field and the temperature in comparison to the localization energy of the charge carriers E_{Loc}. If the electric field is weak and the thermal energy k_BT is large, the charge carriers will be emitted due to thermal activation. If the electric field is strong and the thermal energy is small in comparison to the localization energy, the charge carriers will be released due to tunneling. Phonon-assisted tunneling will occur for a situation, were the tunneling rate from the state E_1 is equal to the thermal activation rate from the ground state E_0 to the state E_1.



FIGURE 2.12 The possible carrier emission processes in an applied electric field: thermal activation, phonon-assisted tunneling and tunneling are shown for electron escape from a QD ground state into the conduction band. The term E_{Loc} represents the localization energy of the charge carriers in the ground state while E_A is the thermal activation energy for phonon-assisted tunneling.

To understand the limitations in storage time in a nanomemory based on self-organized QDs all above mentioned emission processes have to be taken into account. However, in the storage situation of a memory, the electric field should be sufficiently small such that tunneling and phonon-assisted tunneling can be ruled out and only pure thermal activation is of interest. The average time for a thermally activated emission process from the ground state of the QDs to the band edge (which presents an upper limit for the average storage time of the charge carriers) depends in this situation exponentially on the localization energy of the charge carriers; cf. Equation 2.27 in Section 2.6.2.1. Therefore, III–V material combinations with large band offsets that provide large localization energies are needed to build a nonvolatile nanomemory based on self-organized QDs. After a presentation of the QD-based memory concept, the next sections will concentrate on storage times and localization energies in different III–V self-organized QDs and their suitability for a nonvolatile memory.



(a) Storage and read-out (b) Writing a "1" (c) Erase-writing a "0"

FIGURE 2.13 Schematic illustration of the (a) storage and read-out, (b) write, and (c) erase process in a possible future QD-based nanomemory.

2.5.3 A Memory Cell Based on Self-Organized QDs

Here, a memory concept is presented where the self-organized QDs are embedded in a p–n or p–i–n diode structure (Geller et al. 2006a). The QDs act as storage units, since they can be charged with electrons or holes representing the "0" (uncharged QDs) and "1" (charged QDs) of an information bit. An emission barrier is needed to store a "1" in such a memory concept. The barrier height—which is related to the localization energy of the charge carrier (Figure 2.13a)—can be varied by varying the material and size of the QDs and the material of the surrounding matrix (see Section 2.5.1). If the localization energy is increased, a longer storage time of the charge carriers is expected. Furthermore, a capture barrier is needed to store a "0" (Figure 2.13a). This barrier protects an empty QD cell from unwanted capture of charge carriers. In this concept, the capture barrier is realized by using the band bending of a p–i–n or p–n diode.

The major advantage in using a diode structure is the possibility to tune the height of the barriers by an external bias. Therefore, during the write process (Figure 2.13b), the capture barrier can be eliminated by a positive external bias between the gate and source contact ($V_g > 0$ V) and the charge carriers can directly relax into the QD states. This allows to benefit from another advantage of self-organized QDs: the charge carrier relaxation time into the QD states is in the range of picoseconds at room temperature (Müller et al. 2003, Geller et al. 2006b) (see Section 2.7), enabling very fast write times in a QD-based memory. In addition, a very good endurance of 10^{15} write operations should be feasible. To erase the information, the electric field is increased within the QD layer by a negative external bias between the gate and source ($V_g < 0$ V), such that tunneling of the charge carriers occurs (cf. Figure 2.13c).



FIGURE 2.14 Schematic picture of the layer sequence for a possible QD-based memory. The QDs are located below the p–i–n junction and a 2DEG is placed below the QD layer to detect the charge state.

Figure 2.14 shows schematically the device structure of such a QD-based memory, where the QDs are charged with holes to represent an information bit. The doping sequence of the p- and n-regions would be inverted for electron storage. The distance to the junction is adjusted, such that the QDs are inside the depletion region for zero bias ($V_g = 0$ V in Figure 2.13a). The read-out of the stored information is done by a two-dimensional electron gas (2DEG) for an electron and a two-dimensional hole gas (2DHG) for a hole storage device. The 2DEG or 2DHG is situated 10–50 nm below the QD layer and is filled with charge carriers, provided by the additional n- or p-δ-doping, respectively. Stored charge carriers inside the QDs reduce the conductivity of the 2DEG/2DHG; hence, a higher resistance is measured between the source/drain contacts, in analogy to the read-out in a conventional Flash cell.

2.6 Capacitance Spectroscopy

To elucidate the potential of nanomaterials like self-organized QDs for future memory applications the localization energy and the carrier storage time at room temperature has to be determined for different III–V heterostructures. The first goal is to find a material combination that yields a minimum storage time of milliseconds at 300 K, the benchmark for present DRAM.

The capacitance spectroscopy is a powerful tool to study the energy levels and charge carrier emission times in QDs. It has been widely used for different device geometries, for instance in p–i–n diodes to investigate the tunneling dynamics and localization energies in self-organized InAs/GaAs QDs (Fricke et al. 1996, Luyken et al. 1999) or to probe single-electron levels in QDs that are laterally confined inside a 2DEG (Ashoori et al. 1992, Ashoori 1996).

In this section, capacitance spectroscopy is used to determine storage and emission times as well as localization energies in self-organized QDs. The QDs are embedded in a GaAs matrix nearby an abrupt p–n junction that forms a depletion region. This different capacitance spectroscopy method consists of measurements of the depletion capacitance of a p–n or Schottky diode, it is the "capacitance spectroscopy of a depletion capacitance" (Lang 1974).

2.6.1 Depletion Region

The work function or Fermi energy with respect to the vacuum level of a metal or doped semiconductor differs for different metals or semiconductors having a different doping concentration. If a metal and a semiconductor (or two differently doped semiconductors—a p–n diode) are in electric contact, the free charge carriers are exchanged between the different materials until a thermodynamic equilibrium is reached and the Fermi energy is equal throughout the entire structure. Sometimes only ionized donors and acceptors are present in the vicinity of the interface while all free charge carriers are moved away in the semiconductor (Figure 2.15). The layer depleted from free charge carriers is usually referred to as the "depletion region" (Sze 1985, Blood and Orton 1992). The width of the depletion region depends on the doping concentration and the potential difference between the materials, of which the latter can easily be modified by an externally applied bias.



FIGURE 2.15 Energy band diagram of a depleted metal-semiconductor Schottky contact. The width of the depletion region w depends on the doping concentration in the semiconductor. A build-in voltage V_b is present without external bias due to the band bending of the depletion region.

A metal-semiconductor contact can be described by the Schottky model and is referred to as the "Schottky contact." A junction of a p-doped and n-doped semiconductor is a "p–n junction." Both types of contacts provide a depletion region and they are briefly described in the following.

2.6.1.1 Schottky Contact

A metal-semiconductor contact is usually described in the framework of the Schottky model, which is an acceptable approach to construct the band diagram of the contact (Figure 2.15). Within this model, the barrier height ϕ_b inside the metal is independent or just weakly dependent on the applied external bias.

According to the Schottky model, the energy band diagram is constructed by reference to the vacuum level, defined as the energy of a free electron to rest outside the material. The work function of the metal ϕ_m and the electron affinity of the semiconductor χ_s are defined as the energies required to remove an electron from the Fermi level of the metal or the semiconductor conduction band edge, respectively, to the vacuum level. These properties are assumed constant in a given material and it is further assumed that the vacuum level is continuous across the interface. The Fermi levels in the metal and semiconductor must be equal in thermal equilibrium. These conditions result in a band diagram for the interface as shown in Figure 2.15.

Since the vacuum level is the same at the interface of the metal and the semiconductor, a step between the Fermi level in the metal and the conduction band edge E_C of the semiconductor occurs. This is the barrier height ϕ_b given by*

$$\phi_b = \phi_m - \chi_s - eV_m. \tag{2.1}$$

The band bending in the metal is very small due to the large density of electron states; hence, eV_m can be neglected. Therefore, the Schottky barrier height is usually written as

$$\phi_b = \phi_m - \chi_s. \tag{2.2}$$

For increasing distance from the interface, the conduction band energy decreases. At the end of the depletion region, it has the same value as in the neutral semiconductor with respect to the Fermi level. The resulting band bending is an effect of the removed free charge carriers, leaving behind a distribution of fixed positive charges from ionized donors. The depletion region ends at that position, where the bands become flat and the associated electric field is zero. The width of the depletion region w is determined by the net ionized charge density according to Poisson's equation (see Section 2.6.1.3).

Since the density of states in the metal is much greater than the doping density in the semiconductor, the depletion width in the metal is much smaller. Therefore, it can be assumed that the potential difference across the metal near the contact (V_m) is negligibly small compared to that in the semiconductor (V_s).

---

* For a Schottky barrier, ϕ_m must exceed χ_s otherwise the bands bend in the opposite direction.

The total zero bias band bending of the Schottky contact, also referred to as "build-in potential" or "build-in voltage" V_b can be written as

$$eV_b \approx eV_s = \phi_m - \chi_s - (E_C - E_F) = \phi_b - (E_C - E_F). \tag{2.3}$$

Experimental values for various metal Schottky contacts on GaAs can be found in Myburg et al. (1998).

2.6.1.2 p–n Junction

The band diagram of an abrupt p–n junction, in Figure 2.16, is considered in a similar manner. Again, two rules are used to construct the diagram: (1) the vacuum level is continuous and (2) the Fermi energy is constant across the junction in thermal equilibrium. For the same p- and n-doped semiconductor the electron affinity χ_s is the same on both sides of the junction. Therefore, the band bending is caused entirely by the difference in the Fermi level with respect to the conduction band of the two differently doped materials. From Figure 2.16, using subscripts to denote the n and p side, one obtains for zero external bias

$$(E_C^p - E_F) + \chi_s = eV_b + \chi_s + (E_C^n - E_F), \tag{2.4}$$

hence, the build-in voltage is

$$eV_b = E_g - (E_F - E_V^p) - (E_C^n - E_F), \tag{2.5}$$

where E_g is the energy gap of the semiconductor. The build-in voltage as the total electrostatic potential difference between the p-side and the n-side is temperature-dependent and a function of the fixed donor and acceptor charges of density N_d and N_a (Sze 1985):

$$V_b = \frac{k_B T}{e} \ln\left(\frac{N_a N_d}{n_i^2}\right), \tag{2.6}$$

where n_i is the intrinsic carrier density

$$n_i = \sqrt{N_C N_V} \exp\left(-\frac{E_g}{2k_B T}\right), \tag{2.7}$$

with the effective density of states in the valence N_V and conduction band N_C, respectively. A typical doping density of 10^{17} cm^{-3} yields for GaAs a build-in voltage of 1.3 V at 300 K.

In a p–n junction, depletion regions on each side of the contact exist, where the fixed donor and acceptor charges lead to the band bending. Since the total charge in the p–n diode is zero (charge neutrality), in the depletion approximation (Blood and Orton 1992) of an abrupt depletion layer edge

$$N_a w_p = N_d w_n \tag{2.8}$$

must hold. For similar doping concentrations, the depletion width on the p- and n-side of the semiconductor will be comparable. However, for the purpose of material characterization (such as capacitance experiments) doping concentrations are often chosen such that the depletion region is situated almost entirely on one side of the junction. The depletion region of such an asymmetrical p–n junction resembles the depletion region of a Schottky contact. Such asymmetrical junctions are briefly denoted as p$^+$–n or n$^+$–p junction with $N_a \gg N_d$ or $N_d \gg N_a$, respectively.



FIGURE 2.16 Energy band diagram of a p–n junction.

2.6.1.3 Width of the Depletion Region

The entire band bending across the depletion region is defined by the sum of the build-in voltage of the contact V_b (Equation 2.5 or 2.6), and the applied external bias V_a in reverse direction: $V = V_\mathrm{b} + V_\mathrm{a}$. The width of the depletion region and the electric field can be calculated using Poisson's equation. The electrostatic potential ψ at any point is given by

$$-\frac{\partial^2\psi}{\partial x^2} = \frac{\partial F}{\partial x} = \frac{\rho(x)}{\varepsilon\varepsilon_0}, \tag{2.9}$$

where

F is the electric field

ε_0 is the vacuum permittivity

ε is the dielectric constant of the semiconductor material

If the donors or acceptors are entirely ionized, the charge density ρ is eN_d or eN_a, respectively:

$$-\frac{\partial^2\psi}{\partial x^2} = \frac{eN_\mathrm{d}}{\varepsilon\varepsilon_0} \quad \text{for } 0 \le x \le w_\mathrm{n}. \tag{2.10}$$

For a Schottky contact or an abrupt asymmetric p⁺–n junction, integration of Equation 2.9 yields

$$F(x) = F_0 + \frac{eN_\mathrm{d}x}{\varepsilon\varepsilon_0} \quad \text{for } 0 \le x \le w_\mathrm{n}, \tag{2.11}$$

while $F(x) = 0$ for $x < 0$ and $x > w_\mathrm{n}$. Hence, using the approximation $F(x) = 0$ at the edge of the depletion region, gives the boundary condition for the integration constant:

$$F_0 = -\frac{eN_\mathrm{d}w_\mathrm{n}}{\varepsilon\varepsilon_0}, \tag{2.12}$$

and represents the electric field at the interface $F(0)$, where it has its maximum. Therefore, the electric field F across the depletion region in an n-doped semiconductor with the donor concentration N_d is

$$F(x) = \frac{eN_\mathrm{d}}{\varepsilon\varepsilon_0}(x - w_\mathrm{n}) \quad \text{for } 0 \le x \le w_\mathrm{n}. \tag{2.13}$$

Analogously, the electric field distribution across the depletion region on the p-doped side is

$$F(x) = -\frac{eN_\mathrm{a}}{\varepsilon\varepsilon_0}(x + w_\mathrm{p}) \quad \text{for } -w_\mathrm{p} \le x \le 0. \tag{2.14}$$

The potential distribution across the depletion region for a p⁺–n junction inside the n-doped semiconductor is now obtained by integration of Equation 2.13:

$$\psi(x) = -\int_0^x \frac{eN_\mathrm{d}}{\varepsilon\varepsilon_0}(x - w_\mathrm{n})\,dx = \frac{eN_\mathrm{d}w_\mathrm{n}}{\varepsilon\varepsilon_0}\left(x - \frac{x^2}{2w_\mathrm{n}}\right) + \psi(0), \tag{2.15}$$

with $\psi(0) = 0$ as a reference for the potential distribution. For an asymmetric p⁺–n junction, one notices that the band bending in the present approximation only occurs in the n-doped region of the junction. The contact potential is equal to the total band bending, that means, equal to the build-in voltage plus the external bias $\psi(0) = -V = -(V_\mathrm{b} + V_\mathrm{a})$. Since the potential on the edge of the depletion region is zero, $\psi(w_\mathrm{n}) = 0$, one obtains

$$V = V_\mathrm{b} + V_\mathrm{a} = \frac{eN_\mathrm{d}}{2\varepsilon\varepsilon_0}w_\mathrm{n}^2, \tag{2.16}$$

or the expression for the depletion width

$$w_\mathrm{n} = \sqrt{\frac{2\varepsilon\varepsilon_0}{eN_\mathrm{d}}V}. \tag{2.17}$$

If the p–n junction is symmetric and the depletion region extends into the p- and n-doped semiconductor, Equation 2.16 is modified to

$$V = V_\mathrm{b} + V_\mathrm{a} = \frac{eN_\mathrm{d}}{2\varepsilon\varepsilon_0}w_\mathrm{n}^2 + \frac{eN_\mathrm{a}}{2\varepsilon\varepsilon_0}w_\mathrm{p}^2, \tag{2.18}$$

with the net acceptor doping concentration N_a and the width of the depletion region w_p in the p-doped side. The total depletion width w is given by

$$w = (w_\mathrm{n} + w_\mathrm{p}) = \sqrt{\frac{2\varepsilon\varepsilon_0}{e}\left(\frac{N_\mathrm{a} + N_\mathrm{d}}{N_\mathrm{a}N_\mathrm{d}}\right)V}. \tag{2.19}$$

The assumption of an abrupt depletion layer edge, is the so-called depletion approximation. A more general description of the depletion region can be found in reference Blood and Orton (1992).

2.6.1.4 Depletion Layer Capacitance

The capacitance that arises from the depletion region is the so-called "depletion capacitance." In comparison to a plate capacitor, here, the charge is accumulated inside the depletion region of the p–n diode. The number of ionized donors depends linearly on the width w_n, while again the width is a function of the square root of the voltage (Equations 2.17 and 2.19). Hence, the capacitance does not depend linearly on the voltage and has to be defined differentially for a small bias signal ΔV:

$$C = \lim_{\Delta V \to 0}\frac{\Delta Q}{\Delta V} = \frac{dQ}{dV}. \tag{2.20}$$

Using Equation 2.17, the entire stored charge inside the depletion region of a Schottky diode or an abrupt asymmetric p⁺–n junction with area A is

$$Q = eN_\mathrm{d}A \cdot w_\mathrm{n}(V) = A\sqrt{2e\varepsilon\varepsilon_0 N_\mathrm{d}V}, \tag{2.21}$$


Before bias pulse, $V_a = V_r$
QDs empty
During bias pulse, $V_a = V_p$
QDs filled
After bias pulse, $V_a = V_r$
charge carrier emission
w_n
p+
n
F
Electron energy
E_F
E_C
(a)
(b)
(c)

FIGURE 2.17 DLTS work cycle of a p⁺–n diode with embedded QDs. The upper row schematically shows sketches of the devices for three different bias situations: (a) before, (b) during, and (c) after the bias pulse, respectively. The lower row shows the corresponding band diagrams.

and the capacitance is

$$C(V) = \left|\frac{dQ}{dV}\right|_V = A\sqrt{\frac{\varepsilon\varepsilon_0 e N_d}{2V}} = \frac{\varepsilon\varepsilon_0 A}{w_n}. \tag{2.22}$$

The depletion capacitance resembles the capacitance of a plate capacitor with a distance of w_n between the plates and a dielectric with relative permittivity ε, although the charge is actually stored in the volume rather than on the edges of the space charge region.

2.6.2 Capacitance Transient Spectroscopy

The depletion width depends on the applied voltage and the doping concentration, that is, on the charge stored inside the space charge region. As a consequence, the measured capacitance is sensitive to the carrier population inside deep levels or QDs situated inside the depletion region (Kimerling 1974). Semiconductor QDs can be considered as deep levels (or traps), storing few or single charge carriers for a certain time. Time-resolved capacitance spectroscopy allows investigating the electronic structure of QDs, since the carrier dynamics can be studied in detail.

Historically, time-resolved capacitance spectroscopy was initially used to study and characterize deep levels caused by impurities or defects. In this context it is usually referred to as "deep level transient spectroscopy" (DLTS) or "capacitance transient spectroscopy" (Sah et al. 1970, Lang 1974, Miller et al. 1977, Rhoderick and Williams 1988, Grimmeiss and Ovrén 1981, Blood and Orton 1992). Besides the determination of activation energies and capture cross sections, DLTS also permits to obtain a depth profile of the trap concentration and to investigate the influence of the electric field on the emission process. As QDs act more or less as deep levels, the DLTS has been used successfully to study thermal emission processes, activation energies, and capture cross sections of various QD systems (Anand et al. 1995, 1998, Kapteyn et al. 1999, 2000a,b, Schulz et al. 2004).

2.6.2.1 Measurement Principle

In the following, the DLTS measurement principle will be described for QDs in a p–n or Schottky diode structure. A more detailed description can be found in Blood and Orton (1992).

First, a single layer of QDs with density N_{QD} per area in an n-doped material (with doping concentration N_d) shall be considered. The work cycle of a DLTS experiment of a p⁺–n structure with QDs embedded is depicted in Figure 2.17. The upper row displays schematically the p–n diode while the lower row depicts the corresponding potential distribution of the conduction band.

In an initial step (Figure 2.17a), a reverse bias V_r is chosen such that the depletion region extends well over the QDs. The QDs are completely depleted from charge carriers and the Fermi level is below the QD levels. During the pulse V_p, the depletion region is shorter than the distance of the QD layer from the p–n interface and the QDs are consequently filled with carriers—electrons in Figure 2.17b. The Fermi level is now above the QD states. After switching back to the reverse bias situation (Figure 2.17c), the QDs are again situated inside the depletion region but still filled with electrons. The depletion width is larger for QDs filled with charge carriers, hence, the capacitance after the pulse V_p is smaller and increases again when electrons/holes are emitted due to thermal activation or tunneling emission.* By recording the depletion capacitance as a function of time, transients are observed, which represent the carrier emission

---

* The emission of carriers from QD states is usually slow, whereas the free carriers in the matrix material are considered to follow the change in the external bias instantaneously at the timescale of the experiment.



FIGURE 2.18 DLTS work cycle during a DLTS experiment. The lower part displays the external bias on the device as function of time, the upper part the corresponding capacitance.

processes from the QD states. The pulse sequence during the experiment and the measured capacitance transient is schematically depicted in Figure 2.18.

2.6.2.2 Rate Window and Double-Boxcar Method

The capacitance transient, recorded from a single emission process is usually mono-exponential having the time-constant τ. Hence, the capacitance transient is given by (Blood and Orton 1992)

$$C(t) = C(\infty) - \Delta C_0 \exp\left(-\frac{t}{\tau}\right), \tag{2.23}$$

where

$C(\infty)$ is the steady state capacitance at V_r

ΔC_0 is the entire change in the capacitance $C(t)$ for $t = \infty$ (see Figure 2.18)

The emission time constant can be determined by using Equation 2.23 and plotting the data on a semilogarithmic scale. However, in general, the capacitance transient for deep levels and QDs are multi-exponentials due to the ensemble broadening (Omling et al. 1983) and a linear fit is consequently impossible in most cases.

In order to obtain the emission time constant, the activation energies and capture cross section from multi-exponential transients, the rate window concept is commonly applied. One investigates the contribution to the observed emission process at a chosen reference time constant τ_{ref}. By plotting the boxcar amplitude $C(t_2) - C(t_2)$ for that reference time constant as function of temperature, the relation between temperature and emission rate can be evaluated for a thermal activated process.

In the rate window concept, the selection of the contribution for a chosen reference time constant is done by a simple technique: the DLTS signal at a certain temperature $S(T, t_1, t_2)$ is given by the difference of the capacitance at two times t_1 and t_2 by

$$S(T, t_1, t_2) = C(T, t_2) - C(T, t_1), \tag{2.24}$$

or with Equation 2.23

$$S(T, t_1, t_2) = \Delta C_0 \left[\exp\left(-\frac{t_2}{\tau(T)}\right) - \exp\left(-\frac{t_1}{\tau(T)}\right)\right]. \tag{2.25}$$

The two times t_1 and t_2 define the rate window, which has the reference time constant

$$\tau_{\text{ref}} = \frac{t_2 - t_1}{\ln(t_2/t_1)}. \tag{2.26}$$

Plotting $S(T, t_1, t_2)$ as function of temperature yields the DLTS spectrum, schematically depicted in Figure 2.19. A maximum appears at that temperature, where the emission time constant of the thermally activated process equals almost the applied reference time constant: $\tau(T) = \tau_{\text{ref}}$. A maximum appears only for a thermally activated process, a temperature independent tunneling process leads to a constant DLTS signal (Kapteyn



FIGURE 2.19 The evaluation of capacitance transients (a) for increasing temperature by a rate window, defined by t_1 and t_2, leads to a DLTS plot $[C(t_1) - C(t_2)]$ of a thermally activated emission process (b).



FIGURE 2.20 Work cycle during a charge-selective DLTS experiment (a) before, (b) during, and (c) after the bias pulse, respectively. The filling pulse V_p is chosen, that the emission or capture of approximately one charge carrier per QD is probed.

2001). This relation is also valid for inhomogeneous broadened DLTS spectra of self-organized QDs. The measured emission time constant is the average time constant at the maximum of the Gaussian ensemble distribution (Omling et al. 1983).

The thermal emission rate of the charge carriers, e_{th} is now given by (Lang 1974, Blood and Orton 1992)

$$e_{th} = \gamma T^2 \sigma_\infty \exp\left(-\frac{E_A}{kT}\right), \tag{2.27}$$

where

E_A is the thermal activation energy

σ_∞ is the apparent capture cross section for $T = \infty$

γ is a temperature-independent constant

Knowing the emission time constant $\tau = 1/e_{th}$ for different temperatures enables to derive the thermal activation energy and the capture cross section. For varying τ_{ref} different peak positions T_{max} are obtained. The plot of $\ln(T_{max}^2 \tau_{ref})$ as a function of T_{max}^{-1}, cf. Figure 2.22b, is called an Arrhenius plot and is a linearization of Equation 2.27. The slope yields the activation energy E_A and from the y-axis intersection, the apparent capture cross section σ_∞ at infinite temperature can be obtained.

In order to improve the signal-to-noise ratio (SNR), the capacitance transients near t_1 and t_2 can be averaged over an interval t_{av} (Day et al. 1979). The SNR in this case is found to scale as $\sim\sqrt{t_{av}}$ (Miller et al. 1977), and the reference time constant is in good approximation

$$\tau_{ref} = \frac{t_2 - t_1}{\ln\left((t_2 + (1/2)t_{av})/(t_1 + (1/2)t_{av})\right)}. \tag{2.28}$$

This method to improve the SNR is referred to as "Double-Boxcar" approach.

2.6.2.3 Charge-Selective Deep Level Transient Spectroscopy

As described in the previous section, usually the QDs are completely filled with charge carriers during the pulse bias V_p (Figure 2.17b). Consequently, after the pulse, the emission of many charge carriers from multiply charged QDs is probed. The activation energy of each emitted charge carrier depends on the actual charge state in such conventional DLTS experiments. The DLTS spectrum is broadened due to different emission processes from different QD states having different emission time constants, for instance, nicely observed in DLTS experiments on Ge/Si QDs (Kapteyn et al. 2000b).

In order to study the charge states in more detail, charge-selective DLTS probes the emission of approximately one charge carrier per QD. The principle of this method is schematically illustrated in Figure 2.20. Before the filling pulse, the QDs might be already filled with charge carriers up to the Fermi level. During the filling pulse (Figure 2.20b), the Fermi level is adjusted by the applied pulse bias, such that approximately one carrier per QD will be captured. To probe all QD states from the ground state up to the excited state the pulse bias with respect to the reverse bias is set to a constant height and the reverse bias is decreased step by step. After the bias pulse, the reverse bias is set to the initial condition. Now, the previously captured carrier is emitted again and the emission process of approximately one charge carrier per QD is observed. Narrow peaks appear now in the DLTS spectra, which are due to differently charged QDs (cf. Figure 2.23).

Moreover, even for an energy-broadened ensemble of QDs (normally measured in DLTS experiments) the charge-selective DLTS offers a simple method to probe the emission from many charge carriers in different QDs, all having the same activation energy. Decreasing the reverse bias and keeping the pulse bias height fixed (to ensure the emission of only one charge carrier per QDs) gives the activation energy starting at the ground states of the ensemble to the excited states and finishing at completely charged QDs.

2.7 Charge Carrier Storage in Quantum Dots

In this section, experimental results from capacitance spectroscopy measurements on different QD material systems are presented. This time-resolved method allows to derive thermal activation energies and capture cross sections of electron and hole states in QDs. In addition, the important storage time at room temperature can be quantified and connected to the localization energy of the charge carriers.

2.7.1 Carrier Storage in InGaAs/GaAs Quantum Dots

Emission of electrons and holes from InGaAs/GaAs QDs was observed using conventional DLTS measurements by Kapteyn et al. (1999, 2000a,b). The electron/hole emission from InGaAs/GaAs QDs was studied in more detail by using charge-selective DLTS (Geller et al. 2006d) and time-resolved tunneling capacitance measurements (TRTCM) (Geller et al. 2006c). Two samples H1 and E1 were investigated to study the hole and electron emission, respectively, where the QD layer was incorporated in the slightly p-doped/n-doped (~3 × 10^{16} cm^{-3}) region of a n^+–p or p^+–n diode structure. The QD layer was situated 500 nm/415 nm below the p–n junction for the hole/electron sample. Mesa structures with a diameter of 800 μm and ohmic contacts were formed by employing standard optical lithography. The results of these measurements are presented in Figure 2.21.

It turns out that phonon-assisted tunneling controls the charge-carrier emission process from self-organized QDs in an electric field. The influence of the tunneling part, however, depends strongly on the effective mass and the strength of the electric field. The observed hole ground state activation energy $E_A^{H1} = 120 \pm 10$ meV, hence, underestimates the localization energy. It is the thermal activation part in a phonon-assisted tunneling process: thermal activation into an excited state and subsequent tunneling through the remaining triangular barrier, cf. schematic pictures in Figure 2.21. The true hole localization energy was determined by using the TRTCM method to $E_{loc}^{H1} = 210 \pm 20$ meV.

For the electrons, two contributions to the DLTS signal were observed: a DLTS signal with an activation energy of $E_{A1}^{E1} = 82 \pm 10$ meV that is in good agreement with the theoretically predicted value for the ground/excited state energy splitting (70 meV). In addition, a DLTS signal with a smaller activation energy of $E_{A2}^{E1} = 44 \pm 10$ meV is observed. This value is attributed to the first/second-excited state energy splitting and in satisfactory agreement with the theoretically predicted value of 50 meV. The ground state localization energy was determined by the TRTCM method to $E_{loc}^{E1} = 290 \pm 30$ meV (Geller et al. 2006c).



Thermal activation energy	$E_A^{H1} = 120$ meV	$E_{A1}^{E1} = 82$ meV
		$E_{A2}^{E1} = 44$ meV
Localization energy	$E_{loc}^{H1} = 210$ meV	$E_{loc}^{E1} = 290$ meV
Storage time (300 K)	$t_{Storage}^{H1} = 0.5$ ns	$t_{Storage}^{E1} = 200$ ns

FIGURE 2.21 Summary of the results from the charge-selective DLTS and tunneling emission experiments on self-organized InGaAs/GaAs QDs.

The electron/hole storage time at room temperature can be estimated by using Equation 2.27 and the capture cross section and the localization energy for sample E1/H1, respectively. An average storage time for electrons of about 200 ns and for holes of about 0.5 ns is obtained. This means, InAs QDs embedded in a GaAs matrix do not have a sufficiently long storage time to act as storage units in future nanomemories.

2.7.2 Hole Storage in GaSb/GaAs Quantum Dots

The storage time can be further increased by changing the material of the QDs and/or the surrounding matrix. A larger difference in the energy bandgap than in InGaAs/GaAs is more promising, for example, InAs/AlAs QDs. Moreover, large band discontinuities and, hence, strong hole localization is expected in type II QD heterostructures (Hatami et al. 1998), for example, GaSb/GaAs or InSb/GaAs. Only holes are confined in GaSb/GaAs QDs, while a repulsive potential barrier exists for the electrons in the conduction band. Type II material combinations are therefore very attractive for future memory applications.

Hole storage in and emission from $GaSb_{0.6}As_{0.4}$/GaAs QDs was investigated by DLTS and charge-selective DLTS (Geller et al. 2003). The sample was an n^+–p diode structure containing a single layer of GaSb QDs. An area density of about 3 × 10^{10} cm^{-2}, an average QD height of about 3.5 nm, and an average base width of about 26 nm were determined by structural characterization of uncapped samples grown under identical conditions (Müller-Kirsch et al. 2001). The QD layer was placed 500 nm below the n^+–p junction in a slightly p-doped ($p = 3 \times 10^{16}$ cm^{-3}) GaAs region. Mesa structures with a diameter of 800 μm and ohmic contacts were formed by employing standard optical lithography.

2.7.2.1 Multiple Hole Emission

In Figure 2.22, conventional DLTS measurements of the QD sample for a reverse bias $V_r = 10$ V and a pulse bias $V_p = 4$ V are displayed. The pulse length was 10 ms. For these conditions, the QDs are completely filled during the bias pulse and release all trapped holes after the pulse.

The DLTS spectrum of the QD sample (Figure 2.22a) shows three maxima, in the following denoted by "A," "B," and "C." From an Arrhenius plot, an activation energy $E_A^C = 530 \pm 20$ meV and a capture cross section $\sigma_\infty^C \approx 6 \times 10^{-16}$ cm^2 is obtained for peak C. This signature can be identified as the bulk hole trap H3 in p-type GaAs (Stievenard et al. 1986).

Peaks A and B, observed at temperatures $T = 140$ and 230 K, are obviously related to QD formation. An activation energy of about 600 meV is found for peak B. This relatively high activation energy is comparable to the unstrained GaSb/GaAs valence band offset (Hatami et al. 1995, North et al. 1998) and could be explained by the existence of relaxed GaSb islands in the QD sample.



FIGURE 2.22 (a) DLTS signal of the $GaSb_{0.6}As_{0.4}$/GaAs QD sample, measured at a reverse bias V_r = 10 V and a pulse bias V_p = 4 V with a filling pulse width of 10 ms and a reference time constant τ_{ref} = 62.5 ms. (b) The corresponding Arrhenius plot for peak A, which is related to multiple hole emission from the GaSb QD states. An average activation energy of E_A = 340 meV is obtained.

Peak A in the DLTS spectrum of the QD sample in Figure 2.22a is attributed to the hole emission from the GaSb QD states, where the activation energy of each successively emitted hole depends on the actual charge state. The DLTS peak is broadened as previously observed for multiply charged Ge/Si QDs (Kapteyn et al. 2000b). From a standard Arrhenius plot in Figure 2.22b, an activation energy of E_A = 340 meV is obtained. Consequently, this activation energy of peak A represents only an average value for hole emission from completely charged QDs, where 15 holes from different states with different confinement are involved.

2.7.2.2 Charge-Selective DLTS

In order to study the charge states in more detail, the QD sample was studied using the charge-selective DLTS method. The pulse bias was always set to $V_p = V_r - 0.5$ V, while the reverse bias was increased from 4.5 to 9.5 V. Narrow peaks appear in the DLTS spectra in Figure 2.23. At V_r = 4.5 V the DLTS signal shows a maximum at about 80 K and for increasing reverse bias the DLTS peak shifts to higher temperature. The activation energy increases accordingly from 150 meV at 4.5 V to 450 meV for 9.5 V in Figure 2.24 obtained by standard Arrhenius plots.



FIGURE 2.23 Charge-selective DLTS spectra of hole emission from $GaSb_{0.6}As_{0.4}$/GaAs QDs for a reference time constant of τ_{ref} = 62.5 ms. The reverse bias V_r is increased from 4.5 V up to 9.5 V while the pulse height is fixed at 0.5 V for all spectra. The pulse width is 10 ms and the data is displayed vertically shifted for clarity.

The DLTS spectra for a reverse bias between 4.5 and 9.5 V in Figure 2.23 are attributed to the hole emission from differently charged QDs. All these spectra exhibit a maximum in the temperature range between 80 and 180 K, the range covered by peak A in Figure 2.22a. The maximum activation energy of 450 meV represents the average hole ground state energy of the QD ensemble, that is, the localization energy. The decrease in the activation energy from 450 meV down to 150 meV corresponds to an increase in the average occupation of the QDs, see the schematic insets in Figure 2.23. With increasing amount of charge in the QDs, state filling lowers the thermal activation barrier. The completely charged QDs are filled with 15 holes up to the Fermi level at the valence band edge, where Coulomb charging generates the barrier height.

In order to compare the storage time for $GaSb_{0.6}As_{0.4}$/GaAs with In(Ga)As/GaAs QDs, the observed emission rates were extrapolated to room temperature, using Equation 2.27. A storage time of about 1 μs for localized holes with the ground state energy of 450 meV is estimated, three orders of magnitude longer than the hole storage time in InGaAs/GaAs QDs.

2.7.3 InGaAs/GaAs Quantum Dots with Additional AlGaAs Barrier

Hole storage in InGaAs/GaAs QDs with an additional AlGaAs barrier is presented in this section. The additional AlGaAs barrier increases the activation energies and a longer storage time at room temperature is observed. Two different samples having an AlGaAs barrier with different aluminum content were studied. The first contains an $Al_{0.6}Ga_{0.4}As$, the second an $Al_{0.9}Ga_{0.1}As$ barrier below the QD layer. The activation energy in the latter is increased sufficiently to reach a retention time of seconds at room temperature.



FIGURE 2.24 Dependence of the activation energy E_A on the reverse bias $GaSb_{0.6}As_{0.4}/GaAs$ QDs. For a reverse bias of V_r = 9.5 V hole emission from the QD ground states is probed.

2.7.3.1 Storage Time: Milliseconds at Room Temperature

The first sample is an n^+–p diode structure, grown by MBE. It contains a single layer of InGaAs QDs embedded in slightly p-doped GaAs ($p = 2 \times 10^{15}$ cm^{-3}). The QDs are placed 1500 nm below the p–n junction and an additional undoped $Al_{0.6}Ga_{0.4}As$ barrier of 20 nm thickness is situated 7 nm below the QD layer to increase the hole storage time. Again, mesa structures with a diameter of 800 μm and ohmic contacts were formed.

Figure 2.25a shows the charge-selective DLTS spectra with a reference time constant of 5 ms (Marent et al. 2006). The pulse bias height was fixed to 0.2 V for all spectra ($V_p = V_r - 0.2$ V). For a reverse bias above V_r = 3.2 V no DLTS signal is visible, as the Fermi level is energetically above the QD states and no QD states are occupied. By decreasing the reverse bias the Fermi level reaches the QD ground state at V_r = 3.2 V and a peak in the DLTS spectrum appears at 300 K. This peak is related to thermally activated hole emission from the ground states of the QD ensemble across the AlGaAs barrier, see inset in the upper left corner of Figure 2.25b. A further decrease of the reverse bias leads to QD state-filling and emission from higher QD states is observed. A peak in the DLTS appears at that temperature, where the averaged time constant of the thermally activated emission equals the applied reference time constant, cf. Equation 2.26. Therefore, the peak at 300 K for τ_{ref} = 5 ms (V_r = 3.2 V in Figure 2.25a) represents an average emission time constant (storage time) of 5 ms for hole emission from the QD ground states across the $Al_{0.6}Ga_{0.4}As$ barrier.

The thermal activation energies are shown in Figure 2.25b. The highest value of 560 ± 60 meV at V_r = 3.2 V is related to thermal activation from the hole ground states of the QD ensemble across the AlGaAs barrier. The decrease in the activation energy corresponds to an increase in the average occupation of the QDs. At V_r = 1.4 V the energetic position of the Fermi level is at the valence band edge and no further QD state-filling is possible. As a consequence, between V_r = 1.4 and 0.2 V carrier emission from the valence band edge is probed. The activation energy remains roughly constant with a mean value of 340 meV. This energy represents the energetic height of the $Al_{0.6}Ga_{0.4}As$ barrier.

2.7.3.2 Storage Time: Seconds at Room Temperature

The second sample is also an n^+–p diode structure, grown by MOCVD. It contains a single layer of InGaAs QDs embedded in p-doped GaAs ($p = 3 \times 10^{16}$ cm^{-3}). The QDs are placed 400 nm below the p–n junction and an additional undoped $Al_{0.9}Ga_{0.1}As$ barrier of 20 nm thickness is situated 7 nm below the QD layer.

Figure 2.26a shows the charge-selective DLTS spectra (Marent et al. 2007). The pulse bias height was fixed here to 0.3 V for all spectra ($V_p = V_r - 0.3$ V). At V_r = 5.7 V a peak in the DLTS spectrum appears at 380 K, related to thermally activated hole emission from the ground states of the QD ensemble across the $Al_{0.9}Ga_{0.1}As$ barrier. As mentioned before, the peak at 380 K for τ_{ref} = 5 ms represents an average emission time constant (storage time) of 5 ms for hole emission from the ground states of the QD ensemble across the $Al_{0.9}Ga_{0.1}As$ barrier. To obtain the storage time at room temperature, the capacitance transient recorded at



FIGURE 2.25 Charge-selective DLTS spectra of thermally activated hole emission from InGaAs/GaAs QDs with an additional $Al_{0.6}Ga_{0.4}As$ barrier below the QD layer (a). Spectra below V_r = 1.6 V are divided by a factor from 1.1 up to 5. (b) Dependence of the thermal activation energy on the reverse bias V_r. (Reprinted from Marent, A. et al., *Appl. Phys. Lett.*, 89, 072103, 2006. With permission.)



FIGURE 2.26 Charge-selective DLTS spectra of thermally activated hole emission from InGaAs/GaAs QDs with an additional $Al_{0.9}Ga_{0.1}As$ barrier below the QD layer (a). Dependence of the thermal activation energy on the reverse bias V_r.



FIGURE 2.27 Capacitance transient of hole emission from InGaAs/GaAs QDs with an additional $Al_{0.9}Ga_{0.1}As$ barrier (for a reverse bias of $V_r = 5.7$ V). An average hole storage time of 1.6 s at $T = 300$ K is obtained from a linear fit of the transient on a semilogarithmic scale.

300 K is plotted on a semilogarithmic scale in Figure 2.27. From a linear fit an average hole storage time of 1.6 s at room temperature is determined.

Furthermore, the thermal activation energies are shown in Figure 2.26b. The highest value of 710 ± 40 meV at $V_r = 5.7$ V is related to thermal activation from the hole ground states of the QD ensemble across the $Al_{0.9}Ga_{0.1}As$ barrier. The decrease in the activation energy corresponds again to an increase in the average occupation of the QDs. At $V_r = 3.6$ V, carrier emission from the valence band edge is probed and the activation energy has a value of 520 meV. This energy now represents the energetic height of the $Al_{0.9}Ga_{0.1}As$ barrier.

2.7.4 Storage Time in Quantum Dots

Carrier emission from different QD systems has been studied in order to determine the carrier storage time at room temperature. In addition, the localization energy was obtained by using time-resolved capacitance spectroscopy (DLTS) and related to the hole/electron retention time. The results of the experiments are summarized in Figure 2.28.

An electron/hole localization energy of 290/210 meV, respectively, was obtained for InGaAs QDs embedded in a GaAs matrix. Based on these values the storage time at $T = 300$ K was estimated to ~200 ns for electrons and ~0.5 ns for holes. Furthermore, the more promising type II $GaSb_{0.6}As_{0.4}/GaAs$ has been studied in detail. Ground state activation energy of 450 meV was determined, which accounts for a room temperature emission time in the order of 1 μs. The ground state localization is about twice as large and the retention time at room temperature is about three orders of magnitude longer than in InGaAs/GaAs QDs. Finally, the hole emission from InGaAs/GaAs QDs with an additional AlGaAs barrier was investigated. The activation energy for the QD ground states increases from 210 to 560 meV

Material System	Charge Carrier Type	Localization Energy	Storage Time at 300 K
InAs/GaAs	Hole Electron	210 meV 290 meV	~0.5 ns ~200 ns
Ge/Si	Hole	350 meV	~0.1 μs
$GaSb_{0.6}As_{0.4}/GaAs$	Hole	450 meV	~1 μs
InAs/GaAs with $Al_{0.6}Ga_{0.4}As$ barrier	Hole	560 meV	5 ms
InAs/GaAs with $Al_{0.9}Ga_{0.1}As$ barrier	Hole	710 meV	1.6 s

FIGURE 2.28 Summary of the measured electron/hole storage time (at 300 K) and localization energy for different QD systems.



FIGURE 2.29 Dependence of the hole storage time on the localization energy for a variety of QD systems. The solid line is a fit to the experimentally obtained data (full circles). The open circles are estimated storage times for the labeled material systems according to the calculated localization energies and the fit. (Reprinted from Marent, A. et al., *Appl. Phys. Lett.*, 91, 42109, 2007. With permission.)

for an additional $Al_{0.6}Ga_{0.4}As$ barrier and the hole storage time is in the order of milliseconds. Using an $Al_{0.9}Ga_{0.1}As$ barrier increases the activation energy accordingly from 210 to 710 meV and the hole storage time at room temperature increases by nine orders of magnitude to 1.6 s. This value is already three orders of magnitude longer than today's DRAM refresh time, which is in the millisecond range.

From the experimental results, material combinations can be predicted to obtain a storage time of more than 10 years at room temperature. Figure 2.29 displays the hole storage time in dependence of the localization energy (full circles). The solid line is a fit to the data and corresponds to Equation 2.27. The storage time shows an exponential dependence on the localization energy as predicted by the common rate equation of thermally activated emission. The storage time increases by one order of magnitude for an increase of the localization energy of about 50 meV. From these results, hole localization energies can be estimated, which provide storage times of 24 h or 10 years. These storage times are reached for localization energies of 0.96 and 1.14 eV, respectively.

To find a material system with such large localization energies, the hole localization energies for $GaAs_xSb_{1-x}/GaAs$ and $In_xGa_{1-x}Sb/GaAs$ QDs have been calculated using eight-band k · p theory (Stier et al. 1999, Schliwa et al. 2007). Based on structural characterization of GaSb/GaAs QDs (Müller-Kirsch et al. 2001) the QDs are modeled as truncated pyramids with a base width of 21 nm and a height of 3.9 nm. The results are summarized in Figure 2.30 and plotted in Figure 2.29 as open circles. The localization energy in $GaAs_xSb_{1-x}/GaAs$ QDs increases from 350 meV up to 853 meV for an antimony content of 50% and 100%, respectively. Since the bandgap in III–V materials decreases with increasing lattice constant (Vurgaftman et al. 2001), InSb/GaAs QDs should offer a larger localization energy than GaSb/GaAs. Eight-band k·p calculations for $In_xGa_{1-x}Sb/GaAs$ QDs provide a localization energy of 919 and 996 meV for an indium content of 50% and 100%, respectively. A hole storage time in InSb/GaAs QDs of more than 24 h is predicted (see Figure 2.29). Using an AlAs matrix instead of a GaAs matrix a storage time of more than 10 years can be reached. Since the valence band offset between GaAs and AlAs is about 550 meV (Batey and Wright 1986) the entire hole localization energy in GaSb/AlAs QDs is about 1.4 eV. This value leads to the prediction of an average hole storage time of more than 1 million years at room temperature (see Figure 2.29), orders of magnitude longer than needed for a nonvolatile memory.

2.8 Write Times in Quantum Dot Memories

The carrier capture of electrons/holes from the valence/conduction band into the QD states limits physically the possible write time in a QD-based nanomemory. Normally, carrier capture into QDs is studied by interband absorption optical techniques, like time-resolved photoluminescence (PL) spectroscopy (Heitz et al. 1997, Giorgi et al. 2001). However, such experiments probe the exciton dynamics, that means, the electron–hole capture and relaxation into the QD states is measured simultaneously. A detailed knowledge of either electron or hole capture is of great importance, for future QD-based memory applications as only one sort of charge carriers is stored. Electron or hole capture has been investigated separately, for example, in interband pump and intraband probe experiments of Müller et al. (2003). In addition, the hole capture into $GaSb_{0.6}As_{0.4}/GaAs$ self-organized QDs has been studied (Geller et al. 2008) using DLTS experiments. The investigations demonstrate a fast

Material System	Charge Carrier Type	Localization Energy	Storage Time at 300 K
$GaSb_{0.5}As_{0.5}/GaAs$	Hole	350 meV	0.1 µs
GaSb/GaAs	Hole	853 meV	13 min
$In_{0.5}Ga_{0.5}Sb/GaAs$	Hole	919 meV	4 h
InSb/GaAs	Hole	996 meV	6 days
GaSb/AlAs	Hole	~1.4 eV	$>10^6$ years

FIGURE 2.30 Hole localization energies in different Sb-based QDs calculated by eight-band k.p theory. The storage time is estimated according to the fit of the experimental data in Figure 2.29.

capture and relaxation process in self-organized QDs in the range of picoseconds at room temperature, more than three orders of magnitude faster than the write time in a DRAM cell. This fast carrier capture should enable very fast write times in a QD-based nanomemory (<ns) which are independent of the storage time, possibly up to more than 10 years at room temperature. The QD-based memory concept should therefore allow a nonvolatile semiconductor memory with orders of magnitude faster write times than the present Flash concept.

To confirm the presumption of a fast write time that is independent of the storage time, this section shows the write time measurements for two different QD memory structures containing type I InAs/GaAs and type II $GaSb_{0.6}As_{0.4}$/GaAs QDs—both already described in Section 2.7—where the average storage time at 300 K ranges from nanoseconds (InAs/GaAs QDs) to microseconds ($GaSb_{0.6}As_{0.4}$/GaAs QDs).

2.8.1 Hysteresis Measurements

As already discussed in Section 2.7, where the charge carrier storage time was determined, the read-out of the charge state (which represents the stored information) inside the QDs is done by the measurement of the capacitance of the p–n diode. The capacitance of a diode structure with embedded QDs depends on the number of holes stored inside the depletion region. A larger capacitance corresponds to unoccupied QDs ("0") while a smaller capacitance represents a "1," where the QDs are filled with holes.

A fundamental property of storage devices is the appearance of hysteresis when switching between the two information states. Accordingly, a nanomemory device containing self-organized QDs shows a hysteresis in the capacitance measurement after writing (yielding occupied QDs, a "1" state) and erasing (yielding unoccupied QDs, a "0" state) process. Such a hysteresis measurement is shown in Figure 2.31 for InAs/GaAs QDs (a) and $GaSb_{0.6}As_{0.4}$/GaAs QDs (b). Both memory structures are n-p diodes where holes are stored inside the QDs. The sample description can be found in Section 2.7.1 for the InAs/GaAs QDs and in Section 2.7.2 for the $GaSb_{0.6}As_{0.4}$/GaAs QDs. One hysteresis sweep takes a few seconds; hence, the temperature was reduced down to 15 K for the InAs QDs where the hole storage time is in the order of minutes. Analogously, for the $GaSb_{0.6}As_{0.4}$/GaAs QDs—having hole localization energy twice as high as the InAs/GaAs QDs—a higher temperature of 100 K is already sufficient to obtain hole storage times of several minutes.

Figure 2.31 shows the switching between the two information states by a hysteresis curve of the capacitance for both samples. At the reverse bias of 14 V/16 V (point 1) the charge carriers tunnel out of the QDs (erasing the information). If the reverse bias is now swept from 14 V/16 V to the storage situation at 8.2 V (InAs QDs) or 7.2 V (GaSb QDs), respectively, the QDs are empty and a larger capacitance is observed (point 2). If the bias is swept to 0 V (point 3), the QDs are charged with holes and a smaller capacitance is observed upon sweeping back to the storage situation (point 4). The maximum hysteresis opening is now defined at the storage position as the difference between both capacitance values for a "0" and "1" state. The structures are not yet optimized since the carriers are not stored at zero bias. However, the memory structure can be easily adjusted in the future to yield a storage situation at zero bias, realized by changing the width between the QD layer and the p–n junction.



FIGURE 2.31 Capacitance sweeps of a p–n-diode containing InAs/GaAs (a) and $GaSb_{0.6}As_{0.4}$/GaAs (b) QDs. (Reprinted from Geller, M. et al., *Appl. Phys. Lett.*, 92, 092108, 2008. With permission.)

2.8.2 Write Time Measurements

To study the limit of the write-time, series of write pulses are applied with decreasing pulse widths down to 300 ps. The operation principle is schematically depicted in Figure 2.32. The cycle



FIGURE 2.32 Operation principle for measuring the write time, while the labeled numbers refer to the numbers in Figure 2.31. (Reprinted from Geller, M. et al., *Appl. Phys. Lett.*, 92, 092108, 2008. With permission.)



FIGURE 2.33 Maximum hysteresis opening C_{max} for varying write-pulse width. The InAs QD memory is successfully charged for write-pulses down to 6 ns. Analogously, the information in the GaSb QD memory structure can be written down to 14 ns.

started with a 10 s long erase pulse at $V_r = 14$ V/16 V (point 1). Then the capacitance of the device structure is measured at the storage position (point 2) at 7.2 V (GaSb QDs) and 8.2 V (InAs QDs), respectively. A write pulse of $V_r = 0$ V was applied to the device (point 3) and the capacitance is again measured at the storage situation point 4.

The maximum hysteresis opening C_{max} was plotted versus the write-pulse width in Figure 2.33. The limit of the write time is reached when the QDs are not sufficiently charged anymore. The hysteresis opening C_{max} vanishes and the write time is defined as a drop in C_{max} to 50%. A minimum write time of 6 ns at $T = 15$ K for the InAs QD sample and 14 ns at $T = 100$ K for the GaSb QD sample is obtained, respectively. These values are in the order of the write time in a DRAM cell and are now only limited by the experimental set-up and the parasitic cut-off frequency of the RC low pass of the devices. Additional measurements for different temperatures on the same device showed a temperature-independent write time, for example, the difference between the InAs and GaSb structure is due to these different cut-off frequencies. This assumption is also confirmed by previous measurements (Geller et al. 2006b) of the same structure, where average hole capture and relaxation times were found in the order of picoseconds. Therefore, much faster write times below 1 ns are feasible for improved nanomemory structures having higher external cut-off frequencies.

2.9 Summary and Outlook

The semiconductor memory market is evenly split following two different layout approaches: the DRAM and the Flash. Both memories have their limitations in storage time, write/read/erase time, and endurance and will be facing fundamental physical problems in the near future when the feature size has to go down to 14 nm by the year 2020. Therefore, a large variety of novel concepts using different physical phenomena to store an information bit has been reported. One of the promising options is the use of self-organized nanostructures in future nanoelectronic devices. Especially self-organized QDs based on III–V materials (e.g., GaAs, InAs, InP, etc.) could realize a nonvolatile memory (like Flash) with fast read/write/erase access time (like DRAM). In addition, with an area density of up to 10^{11} cm^{-2}, a storage density in the order of 1 TBit in.$^{-2}$ could be possible, if each single QD—with a lateral feature size of about 10 nm—would represent one information bit and it could be addressed individually.

This chapter showed the potential and advantages of using self-organized QDs in a III–V semiconductor nanomemory concept. The charge carrier storage and emission from different QD systems has been studied in order to determine the carrier storage time at room temperature. Localization energies were determined by using time-resolved capacitance spectroscopy (DLTS) and were related to the hole/electron retention time. A maximum storage time of 1.6 s at room temperature has already been demonstrated in InAs/GaAs QDs with $Al_{0.9}Ga_{0.1}As$ barriers. A storage time of more than 10 years is predicted for hole storage in GaSb/AlAs QDs.

The use of III–V heterostructures enables tuning the band structure to a desired storage time at room temperature while simultaneously getting rid of one of the largest drawback of Si-based Flash memories: the fixed SiO_2 barrier that leads to the poor endurance and a bad write time. A very fast write time below 1 ns independent of the storage time (possibly beyond 10 years) is possible. The physical limitation of the write time in such a QD-based nanomemory is only given by the relaxation time of the charge carriers, known to be in the picosecond range. A write time of 14 ns in $GaSb_{0.6}As_{0.4}$/GaAs QDs and 6 ns for InAs/GaAs QDs has already been achieved. These numbers are now limited by the experimental set-up and the parasitic cut-off frequency of the RC low pass of the devices. Faster write times below 1 ns in combination with a storage time of more than 10 years at room temperature are expected in the future. A fast semiconductor Flash nanomemory—even faster than the present day DRAM—based on III–V self-organized QDs seems to be possible.

Acknowledgments

This work was partly funded by the SANDiE Network of Excellence of the European Commission, Contract No. NMP4-CT-2004-500101; the Nanomat project of the European Commission Growth Program, Contract No. G5RD-CT-00545; and SFB 296 of DFG. We also acknowledge financial support by the QD-Flash project in the framework of ProFIT of the Investitionsbank Berlin (IBB) and the DFG, BI 284/29-1. We want to acknowledge the support of and helpful discussions with Dr. C. Kapteyn, T. Nowozin, and E. Stock. Dr. L. Müller-Kirsch, K. Pötschke, D. Feise, A. P. Vasi'ev, E. S. Semenova, Prof. A. E. Zhukov, and Prof. V. M. Ustinov are acknowledged for providing us with the samples.

References

Alferov, Z. I. and Kazarinov, R. F. 1963. Semiconductor laser with electric pumping. Inventor's certificate no. 181737 [in Russian]. Application no. 950840.

Anand, S., Carlsson, N., Pistol, M.-E. et al. 1995. Deep level transient spectroscopy of InP quantum dots. *Appl. Phys. Lett.* **67**: 3016.

Anand, S., Carlsson, N., Pistol, M.-E. et al. 1998. Electrical characterization of InP/GaInP quantum dots by space charge spectroscopy. *J. Appl. Phys.* **84**: 3747.

Ashoori, R. C. 1996. Electrons in artificial atoms. *Nature* **379**: 413.

Ashoori, R. C., Störmer, H. L., Weiner, J. S. et al. 1992. Single-electron capacitance spectroscopy of discrete quantum levels. *Phys. Rev. Lett.* **68**: 3088.

Atwood, G. 2004. Future directions and challenges for Etox flash memory scaling. *IEEE Trans. Device Mater. Reliab.* **4**: 301.

Baibich, M. N., Broto, J. M., Fert, A. et al. 1988. Giant magnetoresistance of (001)Fe/(001)Cr magnetic superlattices. *Phys. Rev. Lett.* **61**: 2472.

Batey, J. and Wright, S. L. 1986. Energy band alignment in GaAs:(Al,Ga)As heterostructures: The dependence on alloy composition. *J. Appl. Phys.* **59**: 200.

Bimberg, D., Grundmann, M., and Ledentsov, N. N. 1998. *Quantum Dot Heterostructures*. Chichester, U.K.: John Wiley & Sons.

Binasch, G., Grunberg, P., Saurenbach, F. et al. 1989. Enhanced magnetoresistance in layered magnetic-structures with antiferromagnetic interlayer exchange. *Phys. Rev. B* **39**: 4828.

Blood, P. and Orton, J. W. 1992. *The Electrical Characterization of Semiconductors: Majority Carriers and Electron States*. London, U.K.: Academic Press.

Burr, G. W., Kurdi, B. N., Scott, J. C. et al. 2008. Overview of candidate device technologies for storage-class memory. *IBM J. Res. Dev.* **52**: 449.

Campbell, J. C., Huffaker, D. L., Deng, H. et al. 1997. Quantum dot resonant cavity photodiode with operation near 1.3 μm wavelength. *Electron. Lett.* **33**: 1337.

Chu, L., Zrenner, A., Bichler, M. et al. 2001. Quantum-dot infrared photodetector with lateral carrier transport. *Appl. Phys. Lett.* **79**: 2249.

Day, D. S., Tsai, M. Y., Streetman, B. G. et al. 1979. Deep-level-transient spectroscopy: System effects and data analysis. *J. Appl. Phys.* **50**: 5093.

Dennard, R. H. 1968. Field-effect transistor memory. U.S. patent no. 3,387,286.

Eaglesham, D. J. and Cerullo, M. 1990. Dislocation-free Stranski–Krastanow growth of Ge on Si (100). *Phys. Rev. Lett.* **64**: 1943.

Eisele, H., Flebbe, O., Kalka, T. et al. 1999. Cross-sectional scanning-tunneling microscopy of stacked InAs quantum dots. *Appl. Phys. Lett.* **75**: 106.

Frank, D. J., Dennard, R. H., Nowak, E. et al. 2001. Device scaling limits of Si MOSFETs and their application dependencies. *Proc. IEEE* **89**: 259.

Fricke, M., Lorke, A., Kotthaus, J. P. et al. 1996. Shell structure and electron–electron interaction in self-assembled InAs quantum dots. *Europhys. Lett.* **36**: 197.

Gallagher, W. J. and Parkin, S. S. P. 2006. Development of the magnetic tunnel junction MRAM at IBM: From first junctions to a 16-MB MRAM demonstrator chip. *IBM J. Res. Dev.* **50**: 333.

Geller, M., Kapteyn, C., Müller-Kirsch, L. et al. 2003. 450 meV hole localization energy in GaSb/GaAs quantum dots. *Appl. Phys. Lett.* **82**: 2706.

Geller, M., Marent, A., and Bimberg, D. 2006a. Speicherzelle and Verfahren zum Speichern von Daten. German patent application no. 10 2006 059 110.0.

Geller, M., Marent, A., Stock, E. et al. 2006b. Hole capture into self-organized InGaAs quantum dots. *Appl. Phys. Lett.* **89**: 232105.

Geller, M., Stock, E., Kapteyn, C. et al. 2006c. Tunneling emission from self-organized In(Ga)As/GaAs quantum dots observed via time-resolved capacitance measurements. *Phys. Rev. B* **73**: 205331.

Geller, M., Stock, E., Sellin, R. L. et al. 2006d. Direct observation of tunneling emission to determine localization energies in self-organized In(Ga)As quantum dots. *Physica E* **32**: 171.

Geller, M., Marent, A., Nowozin, T. et al. 2008. A write time of 6 ns for quantum dot-based memory structures. *Appl. Phys. Lett.* **92**: 092108.

Geppert, L. 2003. The new indelible memories—It's a three-way race in the multibillion-dollar memory sweepstakes. *IEEE Spectr.* **40**: 48.

Giorgi, M. D., Lingk, C., Plessen, G. V. et al. 2001. Capture and thermal re-emission of carriers in long-wavelength InGaAs/GaAs quantum dots. *Appl. Phys. Lett.* **79**: 3968.

Grimmeiss, H. G. and Ovrén, C. 1981. Fundamentals of junction measurements in the study of deep energy levels in semiconductors. *J. Phys. E: Sci. Instrum.* **14**: 1032.

Grundmann, M., Stier, O., and Bimberg, D. 1995. InAs/GaAs quantum pyramids: Strain distribution, optical phonons and electronic structure. *Phys. Rev. B* **52**: 11969.

Guo, L., Leobandung, E., and Chou, S. Y. 1997. A room-temperature silicon single-electron metal-oxide-semiconductor memory with nanoscale floating-gate and ultranarrow channel. *Appl. Phys. Lett.* **70**(7): 850.

Hatami, F., Grundmann, M., Ledentsov, N. N. et al. 1998. Carrier dynamics in type-II GaSb/GaAs quantum dots. *Phys. Rev. B* **57**: 4635.

Hatami, F., Ledentsov, N. N., Grundmann, M. et al. 1995. Radiative recombination in type-II GaSb/GaAs quantum dots. *Appl. Phys. Lett.* **67**: 656.

Heinrichsdorff, F., Krost, A., Grundmann, M. et al. 1996. Self-organization processes of InGaAs/GaAs quantum dots grown by metalorganic chemical vapor deposition. *Appl. Phys. Lett.* **68**: 3284.

Heinrichsdorff, F., Ribbat, C., Grundmann, M. et al. 2000. High-power quantum-dot lasers at 1100 nm. *Appl. Phys. Lett.* **76**: 556.

Heitz, R., Veit, M., Ledentsov, N. N. et al. 1997. Energy relaxation by multiphonon processes in InAs/GaAs quantum dots. *Phys. Rev. B* **56**: 10435.

Hopfer, F., Mutig, A., Kuntz, M. et al. 2006. Single-mode submonolayer quantum-dot vertical-cavity surface-emitting lasers with high modulation bandwidth. *Appl. Phys. Lett.* **89**: 141106.

ITRS. 2008. International Technology Roadmap for Semiconductors (ITRS) 2007 Edition (2008). Technical report.

Jones, R. E., Maniar, P. D., Moazzami, R. et al. 1995. Ferroelectric non-volatile memories for low-voltage, low-power applications. *Thin Solid Films* **270**: 584.

Kapteyn, C. 2001. *Carrier Emission and Electronic Properties of Self-Organized Semiconductor Quantum Dots*. Berlin, Germany: Mensch & Buch Verlag.

Kapteyn, C. M. A., Heinrichsdorff, F., Stier, O. et al. 1999. Electron escape from InAs quantum dots. *Phys. Rev. B* **60**: 14265.

Kapteyn, C. M. A., Lion, M., Heitz, R. et al. 2000a. Hole and electron emission from InAs quantum dots. *Appl. Phys. Lett.* **76**: 1573.

Kapteyn, C. M. A., Lion, M., Heitz, R. et al. 2000b. Many-particle effects in Ge quantum dots investigated by time-resolved capacitance spectroscopy. *Appl. Phys. Lett.* **77**: 4169.

Kim, K., Hwang, C. G., and Lee, J. G. 1998. DRAM technology perspective for gigabit era. *IEEE Trans. Electron Devices* **45**: 598.

Kim, H., Noda, T., Kawazu, T. et al. 2000. Control of current hysteresis effects in a GaAs/n-AlGaAs quantum trap field effect transistor with embedded InAs quantum dots. *Jpn. J. Appl. Phys.* **39**: 7100.

Kimerling, L. C. 1974. Influence of deep traps on the measurement of free-carrier distributions in semiconductors by junction capacitance techniques. *J. Appl. Phys.* **45**: 1839.

Kiravittaya, S., Rastelli, A., and Schmidt, O. G. 2009. Advanced quantum dot configurations. *Rep. Prog. Phys.* **72**: 046502.

Kirstaedter, N., Ledentsov, N. N., Grundmann, M. et al. 1994. Low threshold, large T_0 injection laser emission from (InGa)As quantum dots. *Electron. Lett.* **30**: 1416.

Koike, K., Saitoh, K., Li, S. et al. 2000. Room-temperature operation of a memory-effect AlGaAs/GaAs heterojunction field-effect transistor with self-assembled InAs nanodots. *Appl. Phys. Lett.* **76**: 1464.

Kroemer, H. 1963. Semiconductor laser with optical pumping. U.S. patent no. 3309553.

Kuntz, M., Fiol, G., Lämmlin, M. et al. 2004. 35 GHz mode-locking of 1.3 μm quantum dot lasers. *Appl. Phys. Lett.* **85**: 843.

Lai, S. K. 2008. Flash memories: Successes and challenges. *IBM J. Res. Dev.* **52**: 529.

Lambe, J. and Jaklevic, R. C. 1969. Charge-quantization studies using a tunnel capacitor. *Phys. Rev. Lett.* **22**: 1371.

Lämmlin, M., Fiol, G., Meuer, C. et al. 2006. Distortion-free optical amplification of 20–80 GHz modelocked laser pulses at 1.3 μm using quantum dots. *Electron. Lett.* **42**: 697.

Lang, D. V. 1974. Deep-level transient spectroscopy: A new method to characterize traps in semiconductors. *J. Appl. Phys.* **45**: 3023.

Lochmann, A., Stock, E., Schulz, O. et al. 2006. Electrically driven single quantum dot polarised single photon emitter. *Electron. Lett.* **42**: 774.

Luyken, R. J., Lorke, A., Govorov, A. O. et al. 1999. The dynamics of tunneling into self-assembled InAs dots. *Appl. Phys. Lett.* **74**: 2486.

Mandelman, J. A., Dennard, R. H., Bronner, G. B. et al. 2002. Challenges and future directions for the scaling of dynamic random-access memory (DRAM). *IBM J. Res. Dev.* **46**: 187.

Marent, A., Geller, M., Bimberg, D. et al. 2006. Carrier storage time of milliseconds at room temperature in self-organized quantum dots. *Appl. Phys. Lett.* **89**: 072103.

Marent, A., Geller, M., Schliwa, A. et al. 2007. 10^6 years extrapolated hole storage time in GaSb/AlAs quantum dots. *Appl. Phys. Lett.* **91**: 42109.

Mikolajick, T., Nagel, N., Riedel, S. et al. 2007. Scaling of non-volatile memories to nanoscale feature sizes. *Mater. Sci.-Pol.* **25**: 33.

Miller, G. L., Lang, D. V., and Kimerling, L. C. 1977. Capacitance transient spectroscopy. *Ann. Rev. Mater. Sci.* **7**: 377.

Mo, Y.-W., Savage, D. E., Swartzentruber, B. S. et al. 1990. Kinetic pathway in Stranski–Krastanov growth of Ge on Si(001). *Phys. Rev. Lett.* **65**: 1020.

Moore, G. E. 1965. Cramming more components onto integrated circuits. *Electronics* **38**: 82.

Müller, T., Schrey, F. F., Strasser, G. et al. 2003. Ultrafast intraband spectroscopy of electron capture and relaxation in InAs/GaAs quantum dots. *Appl. Phys. Lett.* **83**: 3572.

Müller-Kirsch, L., Heitz, R., Pohl, U. W. et al. 2001. Temporal evolution of GaSb/GaAs quantum dot formation. *Appl. Phys. Lett.* **79**: 1027.

Myburg, G., Auret, F. D., Meyer, W. E. et al. 1998. Summary of Schottky barrier height data on epitaxially grown n- and p-GaAs. *Thin Solid Films* **325**: 181.

North, S. M., Briddon, P. R., Cusack, M. A. et al. 1998. Electronic structure of GaSb/GaAs quantum dots. *Phys. Rev. B* **58**: 12601.

Omling, P., Samuelson, L., and Grimmeis, H. G. 1983. Deep level transient spectroscopy evaluation of nonexponential transients in semiconductor alloys. *J. Appl. Phys.* **54**: 5117.

Pavan, P., Bez, R., Olivo, P. et al. 1997. Flash memory cells—An overview. *Proc. IEEE* **85**: 1248.

Rhoderick, E. H. and Williams, R. H. 1988. *Metal Semiconductor Contacts*. Oxford, U.K.: Oxford Science Publications.

Sah, C. T., Forbes, L., Rosier, L. L. et al. 1970. Thermal and optical emission and capture rates and cross sections of electrons and holes at imperfection centers in semiconductors from photo and dark junction current and capacitance experiments. *Solid-State Electron.* **13**: 759.

Santori, C., Fattal, D., Vučković, J. et al. 2002. Indistinguishable photons from a single-photon device. *Nature* **419**: 594.

Schliwa, A., Winkelnkemper, M., and Bimberg, D. 2007. Impact of size, shape, and composition on piezoelectric effects and electronic properties of In(Ga)As/AaAs quantum dots. *Phys. Rev. B* **76**: 205324.

Schulz, S., Schnüll, S., Heyn, C. et al. 2004. Charge-state dependence of InAs quantum-dot emission energies. *Phys. Rev. B* **69**: 195317.

Shchukin, V. A., Ledentsov, N. N., Kopev, P. S. et al. 1995. Spontaneous ordering of arrays of coherent strained islands. *Phys. Rev. Lett.* **75**: 2968.

Shchukin, V. A., Ledentsov, N. N., and Bimberg, D. 2003. *Epitaxy of Nanostructures*. Berlin, Germany: Springer.

Sheikholeslami, A. and Gulak, P. G. 2000. A survey of circuit innovations in ferroelectric random-access memories. *Proc. IEEE* **88**: 667.

Stier, O., Grundmann, M., and Bimberg, D. 1999. Electronic and optical properties of strained quantum dots modeled by 8-band-k.p theory. *Phys. Rev. B* **59**: 5688.

Stievenard, D., Boddaert, X., and Bourgoin, J. 1986. Irradiation-induced defects in p-type GaAs. *Phys. Rev. B* **34**: 4048.

Stranski, I. N. and Krastanow, L. 1938. Zur Theorie der orientierten Ausscheidung von Ionenkristallen aufeinander. *Sitzungsber. Akad. Wiss. Wien, Math.-Naturwiss. K1, Abt. 2B* **146**: 797.

Sze, S. M. 1985. *Semiconductor Devices—Physics and Technology*. New York: John Wiley & Sons.

Sze, S. M. 1999. Evolution of nonvolatile semiconductor memory: From floating-gate concept to single-electron memory cell. In *Future Trends in Microelectronics*, S. Luryi, J. Xu, and A. Zaslavsky (Eds.), p. 291. New York: John Wiley & Sons.

Sze, S. M. 2002. *Semiconductor Devices*. New York: John Wiley & Sons.

Tiwari, S., Rana, F., Hanafi, H. et al. 1996. A silicon nanocrystal based memory. *Appl. Phys. Lett.* **68**: 1377.

Vurgaftman, I., Meyer, J. R., and Ram-Mohan, L. R. 2001. Band parameters for III–V compound semiconductors and their alloys. *J. Appl. Phys.* **89**: 5815.

Waser, R. 2003. *Microelectronics and Information Technology*. Berlin, Germany: Wiley-VCH.

White, M. H., Adams, D. A., and Bu, J. K. 2000. On the go with SONOS. *IEEE Circuits Devices* **16**: 22.

Wolf, S. A., Chtchelkanova, A. Y., and Treger, D. M. 2006. Spintronics—A retrospective and perspective. *IBM J. Res. Dev.* **50**: 101.

3

Carbon Nanotube Memory Elements

3.1 Introduction 3-1
3.2 CNFET-Based Memory Elements 3-2
General Description of a CNFET • FET-Based Memory Elements: Pioneering Works • FET-Based Memory Elements: Further Improvements • FET-Based Memory Elements: Controlling Storage Nodes • FET-Based Memory Elements: Optoelectronic Memory • Redox Active Molecules as Storage Nodes • Two-Terminal Memory Devices • Using Nanotubes as Storage Nodes • Conclusions
3.3 NEMS-Based Memory 3-9
NEMS: Generalities • Carbon Nanotube Crossbars for Nonvolatile Random Access Memory Applications • Nanorelays • Feedback-Controlled Nanocantilevers • Data Storage Based on Vertically Aligned Carbon Nanotubes • Linear Bearing Nanoswitch • Conclusions
3.4 Electromigration CNT-Based Data Storage 3-16
A "Bucky Shuttle" Memory Element • Memory Elements Based on the "Bucky Shuttle" Concept • Conclusions
3.5 General Conclusions 3-18
Acknowledgments 3-18
References 3-19

Vincent Meunier
Oak Ridge National Laboratory

Bobby G. Sumpter
Oak Ridge National Laboratory

3.1 Introduction

An incredibly rapid expansion in the demand of portable consumer electronics ranging from personal computers, cellular phones, MP3 players, digital cameras, PDAs, USB memory sticks to applications in the networking arena continues to drive the pursuit for the development of higher density, faster, more efficient, and economical electronic memory devices (Scott 2004). Currently, most commercially available memory elements consist of dynamic random access memory (DRAM), static random access memory (SRAM), or flash memory (nonvolatile memory). DRAM is considered to be very fast and cheap but its contents are lost when power is switched off (volatility). SRAM is much faster and needs less power but is far more expensive and also suffers from volatility. Flash memory is nonvolatile but currently operates at low write speed and thus has a slow random access. In addition, it is power-hungry and very expensive. In the past, incremental improvements in memory capacity and capability were primarily achieved by the simple scaling of the physical dimensions of the devices. However, the semiconductor industry is quickly reaching the fundamental limits on the miniaturization, encountering, for example, extreme difficulties due to short channel effects in the scaling of metal-oxide-semiconductor field-effect transistor (MOSFET). This difficulty has stimulated an intense growth in research and development in the area of new technologies and materials that can overcome these limitations and deliver unprecedented capabilities for memory storage and access. Some promising new types of memory-storage devices include magnetoresistive RAM (MRAM), ferroelectric RAM (FRAM), phase-change memory (PRAM), and novel high speed–density nonvolatile memory (these are primarily based on carbon nanotubes [CNTs]) (Waser 2003).

CNT-based data-storage devices or memory elements offer high potential for considerable improvements compared to current memory paradigms (Bichoutskaia et al. 2008, Zhang 2006). First, CNTs are considerably smaller than conventional cells, e.g., each nanotube is less than 1/10,000th the width of a human hair, thus allowing an impressive density to be achieved in a modest space. The intrinsic structural, thermal, and mechanical stability of CNTs are expected to confer to these memory devices a very long lifetime while the power requirements for their operation should be considerably less than DRAM. In addition, CNTs are known to be radiation-resistant and nanotube-based memory elements are therefore expected to be robust in numerous types of environments. As such, these novel types of memory elements have recently been touted as a "universal memory" (Bichoutskaia et al. 2008).

In this chapter, we review the developments in memory elements that exploit the properties of CNTs. These nanoscale systems fit into the realm of nanoelectronics and offer exceptional properties and well-characterized structures that have rapidly emerged as a viable route to satisfy the future requirements and needs for data-storage and memory devices. Given the difficulty in the integration of nanoscale systems, such as CNTs, into adequate arrangements for useful structures and devices, and the complexity in the assessment of the properties of the devices, a tremendous effort has been devoted in the past years toward the development of experimental and theoretical methods making it possible to creatively imagine, design, and test new systems for desired and tailored characteristics. In this chapter, we review the different types of CNT-based memory devices, which include memory elements based on CNT field-effect transistors (CNFET) (Section 3.2), nanoelectromechanical systems (NEMS) (Section 3.3), and electromigration (Section 3.4). The fundamental operational principles and characteristics of the different devices and concepts are examined in detail along with a discussion of the current status of experimental fabrication and practical realization.

3.2 CNFET-Based Memory Elements

A number of CNT memory elements have been developed from the functioning principle of CNFETs. The following section will be devoted to a description of a few of them. First, we will expose the basic working principle of the CNFET before showing how CNFETs can be implemented for memory applications.

3.2.1 General Description of a CNFET

Nanotube transistors are among the possible replacements for silicon field-effect transistors (FETs) as bulk-device scaling approaches quantum limits. A CNFET is a device consisting of a single nanotube and three contacts (Figure 3.1a). It has been demonstrated repeatedly in the laboratory to possess characteristics similar to those of conventional silicon FETs. Because nanotubes can be used as either n- or p-type CNFETs, existing complementary metal-oxide-semiconductor (CMOS) design techniques can be utilized for a nanotube-based FET technology. A CNT-based CMOS industry is very appealing, in particular because with their electrical and thermal properties, CNTs can sustain very large current in the billion amperes per square centimeter regime (about three orders of magnitude larger than conventional metallic wires).

The main hurdle facing nanotube-FET technology remains the difficulty of developing scalable manufacturing methods to compete with the well-developed silicon large-scale production.

CNTs can behave as either conductors or as semiconductors, depending on the arrangement of the atoms along the nanotube (Bernholc et al. 2002, Charlier et al. 2007). While about one-third of nanotubes are metals, the bandgap of the semiconducting tubes varies inversely with the tube diameter, making it possible to design a large range of devices and heterostructures. Conversely,



FIGURE 3.1 (a) Schematic cross section of a typical CNFET device. A single CNT of either multiwall- or single-wall-type bridges the gap between two gold electrodes. The silicon substrate is used as back gate. Output and transfer characteristics are shown in (b) and (c), respectively. The current vs. source–drain voltage curves in (b) were measured for gate voltage values of −6, 0, 1, 2, 3, 4, 5, and 6 V. In (c) the current vs. gate voltage are given for 10 different source–drain voltages between 10 and 100. The inset shows that the gate modulates the conductance by five orders of magnitude (for a source–drain voltage of 10 mV). (Reprinted from Martel, R. et al., *Appl. Phys. Lett.*, 73(17), 2447, 1998. With permission.)

conducting nanotubes possess a very low resistance for electron flow (ballistic conductors) because the decoherence length of the nanotube wavefunctions is typically larger than practical nanotube lengths. As long as the nanotube length is shorter than the decoherence length, the resistance will not depend upon the cylinder length. In that case, the only electrical resistance is at the contact points where the electrons enter and leave the tube. As shown below, it is precisely at the interface between the nanotube and the metallic electrodes that the physical processes responsible for the functioning of a nanotube transistor take place.

CNFETs can be fabricated with a structure very similar to silicon FETs. As shown in Figure 3.1a, such a device consists of a single-walled semiconducting nanotube whose ends are attached to two metallic contacts. In the terminology of transistors, the nanotube acts as the channel and the two contacts are the drain and the source, respectively. The device is completed by a gate electrode that is positioned somewhere between the source and the drain. There are a number of possible designs: the nanotube can be positioned above or under the metallic contacts and the gate can be placed as a back or front gate. For a transistor to work properly the semiconductor CNT must be doped. In air, at room temperature, the device behaves as a depletion mode p-FET (the I–V is typical of hole conduction, Figure 3.1b). The transistor action is due to the electric field around the gate modulating the Schottky barrier at the points where the source and drain terminals contact the nanotube. For reasonably short tubes (a few hundred nanometers or less), the effect of the gate voltage on channel resistance is minimal. Experimentally, the first-reported CNFETs were all p-type devices. This is because when exposed to air, nanotubes are p-doped due to the presence of oxygen that shifts the Fermi level at the metal–nanotube interface toward the valence band, leading to a hole-conduction mechanism. When the same device is heated in a vacuum and allowed to outgas, the Fermi level shifts toward the conduction band, which leads to an electron-conduction mechanism, i.e., acts as an n-type FET. Different types of FETs can be obtained depending on chemical doping, leading to p-type, n-type, or even p–n-type (ambipolar) systems.

Here we describe the general functioning of a p-type transistor. An understanding for the n-type systems can be easily obtained by considering electrons as majority carriers. As shown in Figure 3.2, the application of a negative gate voltage increases the number of majority carriers in the channel, thereby leading to an increased current density across the transistor. For positive gate voltage, the current is negligibly small, due to the depletion in the number of holes. At the same time there is no evidence of electron conduction, even at very large positive gate voltages.

While nanotubes show great promise in the mechanical and microelectronic realms, major problems still exist (Bernholc et al. 2002). Assuming the ability to produce large quantities of nanotubes with specific geometries, a separate difficulty lies in actually assembling large quantities of transistors out of them and placing those transistors, along with an interconnect, on a substrate to form a complete circuit. Solutions to these problems are only beginning to surface. With respect to electronics, the biggest difficulty is devising a production method that can provide the same facility for large-scale fabrication as silicon photolithography. This goal appears distant but it continues to be a topic of intense research. With the demonstrated potential payoff for a range of applications, it seems likely that a solution to this problem will eventually be found. Further details on the general aspects of CNFETs can be found in the vast literature published on the topic (e.g., Derycke et al. 2001, 2002, Martel et al. 2001, and Tans et al. 1998). Below we review how CNTs have been implemented for FET-based memory applications.

3.2.2 FET-Based Memory Elements: Pioneering Works

Nonvolatile and volatile memory elements can be designed from the functioning of a CNFET (Wunnicke 2006). The storage media is typically a charge that is stored in the vicinity of the nanotube



FIGURE 3.2 Schematic of the bands in the vicinity of the contacts as a function of the electrostatic gate field for a p-type (a), ambipolar (b), and n-type (c) CNFETs. Annealing the device in vacuum results in a transition from the situation of (a) to that of (c) in case of low doping and (d) for high doping. The transition can be reversed by the introduction of air, clearly showing that the presence of oxygen p-doping of the nanotube. It is clear that the Schottky barrier at the nanotube–metal interface plays a key role. Note also the importance of Fermi-level pinning for the functioning of the device. (Reprinted from Derycke, V. et al., *Appl. Phys. Lett.*, 80(15), 2773, 2002. With permission.)

channel. The charge causes a threshold potential shift (the threshold potential is defined as the potential at which the majority carriers start flowing) of the nanotube FET. Because the nanotube has very high carrier mobility, the information can be stored in a few (as few as one) electrons configuration. The states can be reversibly written and erased. The reading mechanism is performed via a measurement of the source–drain current, while the writing mechanism is completed using a large bias voltage applied to the gate.

A number of groups have obtained convincing results on CNFET-based memory elements. How the information is stored and consequently under which conditions the memory is usable depends on the details of the manufacturing, particularly in the gating material. The first two examples of FET-memory elements were proposed independently by Fuhrer et al. (2002) and Radosavljevic et al. (2002). The functioning of the devices hinges on the operation of a single-electron memory. In this case, the capacitance of the storage node must be small enough so that its Coulomb-charging energy is significantly larger than the thermal energy at the operating temperature, and the readout device must be sensitive enough to detect a single nearby electronic charge. In Fuhrer's device, the charge is reversibly injected and removed from the dielectric (placed between the tube and the gate electrode) by applying a moderate (10 V) bias between the nanotube and the substrate. The nanotube is ideal as a charge-detecting device due to its high carrier mobility, large geometrical capacitance, and its one-dimensional (1D) nature ensuring that local changes in charge affects the global conductance (due to slow screening). In Fuhrer's pioneering work, for instance, discrete charge states corresponding to differences of a single, or at most a few, stored electrons are observed. The device is based on the characteristics of a p-type FET (i.e., it conducts at negative gate voltage and becomes insulating at positive gate voltage) and can be operated at temperatures up to 100 K. Properties relevant to memory operation are demonstrated by the large hysteresis I–V_g curve that is obtained by sweeping the gate voltage V_g between −10 and +10 V. As is shown in Figure 3.3, the threshold voltage is shifted by more than 6 V. The mechanism of charge storage is related to the rearrangement of charges in the dielectric or by the injection or removal of charges from the dielectric through the electrodes or the nanotube. Due to the geometry of the device, the electric field at the surface of the



FIGURE 3.3 (a) Atomic force microscope topographic image of the nanotube device used in Fuhrer et al. (2002). The nanotube extends between the two dark blocks at the top and bottom of the image (i.e., the electrodes). The scale bar represents 1 μm. (b) Drain current as a function of gate voltage at room temperature and a source–drain bias of 500 mV. As the gate voltage is swept from positive to negative and back, a strong hysteresis is observed, as indicated by the arrows denoting the sweep direction. (c) Series of four read–write cycles of the nanotube memory at room temperature. The upper panel shows the drain current at a source–drain bias of 500 mV, while the lower panel shows the gate voltage. The memory state was read at −1 V, and written with pulses of ±8 V. (Reprinted from Fuhrer, M.S. et al., *Nano Lett.*, 2(7), 755, 2002. With permission.)

nanotube is very large, at least large enough to cause the movement of charge in the dielectric (Fuhrer et al. evaluated the field to be comparable to the breakdown field in SiO_2). At these high fields the electrons are easily injected into the dielectric from the nanotube and remain trapped in metastable states until the polarity is reversed.

In Radosavljevic's device, the FET used is based on an n-type transistor (obtained from annealing the nanotube in hydrogen gas). Again, it was shown that CNFETs are extremely sensitive to the presence of individual charges around the channel, largely because of the nanoscale capacitance of the CNTs. A technique known as scanning gate microscopy (SGM) (Freitag et al. 2002, Meunier et al. 2004) was used to study the local transport properties across the channel, revealing the key role of nanotube–metal contacts (Schottky barriers) and also the positions of the possible sites where the electrons are trapped (i.e., where the information is physically stored, the storage nodes). Figure 3.4 shows the reproducible hysteresis loop in the I–V_g curve that becomes larger as the range of V_g is increased, indicating that it originates from avalanche injection into bulk oxide traps. The hysteresis can become so large that the device varies from depletion mode (normally on at $V_g = 0$) and enhancement mode (normally off) behavior. The location and sign of the trapped charge can be determined by examining the directions of the hysteresis loop. After a sweep to positive V_g, the CNFET threshold voltage moves toward more positive gate values, indicating injection of negative charges into oxide traps. To read the memory, a 1 MΩ load resistor is added to create a voltage divider. Read ($V_{in} = 0$) and write ($V_{in} = +20$ or -20 V) are applied to the input terminal (back gate). A logical gate (1 or 0) is defined as $V_{out} = 1$ or 0. To write a "1" to the memory cell, V_{in} is switched rapidly to −20 or +20 V and back to "0," so the CNFET is in the on or off at the read voltage. This memory device was found to be nonvolatile at room temperature and with a bit-storage retention time of at least 16 h. The trap charging time limits the speed of the device and the bit was evaluated to be stored in no more than 2, 70, and 200 e.

In the pioneering works discussed above, it is noteworthy that the storage nodes are not precisely the nanotube itself, but consist of trapping sites in the dielectric layer of the gating material. The functional temperatures, storage density, operating speeds, etc., are very sensitive to the details of the trapping mechanisms. As summarized below, a number of studies have been reported following the seminal studies of Fuhrer and Radosavljevic, where the trapping mechanism was further analyzed and modified.

3.2.3 FET-Based Memory Elements: Further Improvements

Charge-storage stability of up to 12 days at room temperature was reported in a 150 nm long nanotube channel (Cui et al. 2002). The observed conductance decreases for increasing gate



FIGURE 3.4 (a–c) Current vs. gate voltage data obtained in high vacuum for a source–drain voltage of 0.5 mV. The device hysteresis increases steadily with increasing gate voltage due to avalanche charge injection into bulk oxide traps, schematically shown in (d). (e) Demonstration of the CNFET-based nonvolatile molecular memory cell. A series of bits is written into the cell and the cell contents are continuously monitored as a voltage signal (V_{out}) in the circuit shown in the inset. (Reprinted from Radosavljevic, M. et al., *Nano Lett.*, 2(7), 761, 2002. With permission.)

potential, a normal feature of p-type, air-exposed single-wall carbon nanotubes (SWCNTs). The hysteresis loop is obtained by sweeping continuously the gate voltage from −3 to +3 V. This shows two conductance states at $V_g = 0$ differing by more than two orders of magnitude, associated with a threshold voltage of 1.25 V. The method used by Cui et al. is more technologically straightforward compared to the previously reported techniques, as it does not require separating SWCNT bundles into individual SWCNTs during sample preparation. The sample treatment is likely to be responsible for the modified type of trapping centers, compared to earlier similar devices. The heat treatment and exposure to oxygen plasma cause the metallic nanotubes present in the bundle to be preferentially oxidized, leading to increased gate dependence due to the remaining intact semiconducting tubes. In addition, oxidation-related defects are likely to be formed in the remaining amorphous carbon particles on the bundle surface or at the SiO_2 interface. These defects act as charge-storage traps and their close proximity to the surface of the channel accounts for the large threshold voltage shifts.

Another type of charge trapping was presented by Kim et al. (2003). In that case, water molecules were shown to be responsible for the hysteresis properties (i.e., responsible for the threshold potential shift) of the I–V_g curves. The water molecules contributing to the trapping could be located on the nanotube surface or on the SiO_2 close to the tube. Heating under dry conditions significantly reduces the hysteresis. A completely hysteresis-free CNFET was possible by passivation of the device using a polymer coating, clearly indicating that the storage nodes were removed by the treatment. This work also confirms the central role played by surface chemistry on the properties of the device and that truly robust passivation is needed in order to use CNT-based devices in practical electronic devices, unless it is simply used as a detection device (e.g., of humidity).

More recent work of Yang et al. confirmed the role of adsorbed (including water and alcohol) molecules for charge trapping, also showing charge retention of up to 7 days under ambient conditions (Yang et al. 2004).

3.2.4 FET-Based Memory Elements: Controlling Storage Nodes

Soon after the publication of the pioneering works of 2002, a number of groups confirmed that the as-prepared nanotube FETs possessed intrinsic charge-trapping centers that were responsible for the shift in the threshold voltage measured in the hysteresis loop of the I–V_g characteristics. As discussed briefly above, the trapping centers can be defects in the SiO_2, water, or alcohol molecules adsorbed on the tube or the dielectric, or oxidized amorphous carbon. It was soon understood that a better control of the storage medium was required in order to harness the full potential of CNFET-based memory elements.

In 2003, Choi et al. proposed a SWCNT nonvolatile memory device using SiO_2-Si_3N_4-SiO_2 (ONO) layers as the storage node (Choi et al. 2003). In that device, the top gate structure is placed above the ONO layer, which is positioned directly above a few-nanometers-long channel. Charges can tunnel from the CNT surface into the traps present in the ONO layers. The stored charges impose a threshold voltage shift of 60 mV, which is independent of charging time, suggesting that the ONO traps present a quasi-quantized state. The choice of SiO_2-Si_3N_4-SiO_2 is motivated by the fact that it presents a high breakdown voltage, low defect density, and high charge-retention capability (Bachhofer et al. 2001).

Another type of device was demonstrated experimentally in 2005 (Ganguly et al. 2005). In this case, the charge-storage nodes consist of gold nanocrystals placed on the top gate above the nanotube channel. The device was found to have a large memory window with low voltage operations and single-electron-controlled drain currents. The device is based on a Coulomb blockade behavior, in other words on the difficulty of adding supplementary electrons due to the large charging effect of the system with large capacitance and Coulomb repulsion. The Coulomb blockade in the nanocrystals, along with the single-charge sensitivity of the nanotube FET, is suggested to allow for multilevel operations. In this device, the reported retention is rather modest: 6200 s at 10 K and only 800 s at room temperature. Better dielectric and preprocessing should improve these low retention times.

More recently, Sakurai et al. proposed a modified design where the dielectric insulator was made up of a ferroelectric thin film (Sakurai et al. 2006). The experimental results show that the carriers in the CNTs are controlled by the spontaneous polarization of the ferroelectric films. Ferroelectric-gate FETs offer potential advantages as nonvolatile memory elements, such as low power consumption, the capability of high-density integration, and nondestructive readable operation. So far, the use of ferroelectric thin films in conventional Si-based FETs for memory applications has been complicated because of the extreme difficulty of fabricating the ferroelectric/Si structure with good interface properties due to the chemical reaction and interdiffusion of Si and ferroelectrics. It was suggested that this problem could be resolved by inserting an insulating layer between the ferroelectric and the semiconductor layers, but at the cost of increased voltage operation and depolarization field. Another method was to use an oxide semiconductor, such as indium tin oxide. However, even though this system also shows good memory operation, the carrier mobility is much lower than in Si, causing problems that are unacceptable for high-performance nonvolatile memory elements. The use of a semiconducting tube as the conducting channel and a ferroelectric as a gate insulator alleviates all of these problems: the new design allows the carriers in the channel to be controlled by the spontaneous polarization of the ferroelectric film, while keeping the high-conduction characteristics of CNTs. In the demonstrated prototypical device, a 400 nm thick PZT ($PbZr_{0.5}TiO_5O_3$) film was used. The threshold voltage was found to be shifted in the positive direction when V_g was swept from negative to positive bias and was shifted in the negative direction when V_g was swept from positive to negative. This gave a clear hysteresis loop and bistable current values at $V_g = 0$, due to the spontaneous polarization of the electric field (the effects of charge trapping in the dielectric was found to be negligible compared to the effects due to the ferroelectric, at least for small sweeping range of V_g).

3.2.5 FET-Based Memory Elements: Optoelectronic Memory

In all of the CNFET-based memory devices mentioned thus far in this chapter, the information is stored by applying a large enough gate voltage to store or remove the charge in, or from, the traps (for the ferroelectric-based FET, the gate is used to flip the polarization field). In Star's CNFET-memory (p-type) device, the information is still stored as electric charges (Star et al. 2004), however, it differs in that the writing mechanism relies on the use of optical illumination of a photosensitive polymer (which is part of the gate electrode) that converts photons into electric charge stored in the vicinity of the channel. The information is read by measuring the source–drain current, while it is erased (the charge is removed) using a large gate voltage. In other words, this optoelectronic memory is written optically and read and erased electrically. The threshold voltage change compared to the non-illuminated system was measured to be as large as +2 V after optical excitation, suggesting a charge transfer of about 300 electrons per micron in the tube.

3.2.6 Redox Active Molecules as Storage Nodes

In this experimentally built system, the overall configuration and operating principle consists of a nanotube or nanowire FET functionalized with redox active molecules, where an applied gate voltage or source–drain voltage pulse is used to inject net positive or negative charge into the molecular layer (Duan et al. 2002). The oxide layer, on the surface of the channel, serves as a barrier to reduce charge leakage between the molecules and the channel, and thus maintains the charge state of the redox molecules, thereby guaranteeing nonvolatility. The charged redox molecules gate the FET to a logic on state with higher channel conductance or the off state with lower channel conductance. Positive charges in the redox material act just like a positive gate, leading to an accumulation of electrons and an on state in n-type semiconducting nanowire-based FETs. For p-type FETs, the same effect is obtained with negative charges in the redox layer, which cause an increase in majority carrier density, in this case holes, in the channel (Figure 3.5). Mannick et al. also described a similar device, using SWCNTs as channels, where the conductance is switched on or off, guided by chemical reactivity of a CNT in H_2SO_4 (Goldsmith et al. 2007, Mannik et al. 2006).

3.2.7 Two-Terminal Memory Devices

Transistor devices consist of three electrodes: a source, a drain, and a gate terminal. The source and the drain are good metals (Au, Pt, Co, etc.) and the gate terminal is typically made up of a dielectric layer (e.g., SiO_2) sandwiched between the channel and a heavily doped Si-wafer, which is hooked up to the gate battery. The present authors have theoretically proposed a modified version of the FET memory device where the physical gate is replaced by a virtual electrode. The role of the



FIGURE 3.5 Nanowire-based nonvolatile devices. The devices consist of a semiconductor nanowire (NW) configured as a FET with the oxide surface functionalized with redox active molecules. The top-middle inset shows a scanning electron microscope (SEM) image of a device, and the lower circular inset shows a TEM image of an InP NW highlighting the crystalline core and surface oxide. Positive or negative charges are injected into, and stored in, the redox molecules with an applied gate or bias voltage pulse. In an n-type NW, positive charges create an on or logic "1" state, while negative charges produce an off or logic "0" state. (Reprinted from Duan, X.F. et al., *Nano Lett*., 2(5), 487, 2002. With permission.)



FIGURE 3.6 (a) Schematic representation of the typical setup used to probe the information stored in the nonvolatile memory element based on the encapsulation of a donor–acceptor molecule inside a metallic nanotube. In (a) the system is made up a tetrafluorotetracyano-p-quinodimethane molecule encapsulated inside a (10, 10) armchair nanotube. (b) Examples of bistable orientations of the C=C bond of tetracyanoethylene (TCNE) inside a (9, 0) zigzag CNT. (Reprinted from Meunier, V. and Sumpter, B.G., *Nanotechnology*, 18(42), 424032, 2007. With permission.)

gate is filled by a single donor or acceptor molecule embedded inside a metallic nanotube channel (Meunier and Sumpter 2007, Meunier et al. 2007) (Figure 3.6). The resulting device is a two-terminal system where the conduction properties can be turned on and off by modifying the position of the donor (or acceptor) molecule relative to the nanotube inner core. The intrinsic gating effect works for any nanotube-molecule couple, as long as the molecule possess two stable positions corresponding to a different interacting scheme with the nanotube host (bistability). The gating mechanism works as follows: In one orientation, charge transfer between the molecule and the nanotube imposes a suppression of the current. In another orientation, when the interaction is not only purely electrostatic (charge transfer), but also includes significant directional binding, the gating effect is suppressed and current flow is allowed. It was proposed that the molecule's orientation can be modified by imposing a lateral stress to the nanotube, changing the local atomic arrangement around the molecule, which in turn results in its flipping. Other optional writing mechanisms include the use of a magnetic field, optoelectronics, etc. This example underlines the importance of developing a memory device with a well-defined and well-characterized storage node (here the storage node is a single molecule). It is also a memory device that lies at the boundary of FET-type system and NEMS device, as it involves both transistor-like technology and "moving parts," on which NEMS are based, as shown in Section 3.3.

Tour and coworkers proposed a memory element, not based on FET operation, but relying on the conformation of a molecule as the storage media (He et al. 2006). The idea is based on the development of a metal-free silicon-molecule-nanotube test bed for exploring the electrical properties of single molecules that demonstrated a useful hysteresis *I*–*V* loop for memory storage.



FIGURE 3.7 (a) Schematic structure of the HfAlO/CNTs/HfAlO/Si MOS memory structure of Lu and Dai where a nanotube is used as the storage node. (b) High-resolution transmission electron microscopy (HRTEM) image of CNTs embedded in HfAlO control and tunneling layers. (Reprinted from Lu, X.B. and Dai, J.Y., *Appl. Phys. Lett.*, 88(11), 113104-3, 2006. With permission.)

Nonvolatile memory for more than 3 days with cyclability of greater than 1000 read and write–erase operations was obtained for a molecular interface between the Si and SWCNTs consisting of π-conjugated organic molecules. In this case, the hysteresis in the I–V curve resulted from a conductivity change at high-voltage bias. The conduction state could be easily switched from high to low conductivity, by using a +5 V pulse, and makes it possible for the Si-molecule–SWCNT junction to be used as a nonvolatile memory element. The underlying mechanism for the switching was examined and it was concluded that it was not due to a thermoionic process but likely from a tunneling process across the molecule. Akdim and Pachter suggested that the switching in the device may be driven by conformational changes in the molecule upon the application of an electric field and that the nature of the contact at the interface of the SWCNT mat plays an important role in the switching (Akdim and Pachter 2008).

3.2.8 Using Nanotubes as Storage Nodes

Some authors have reported CNFETs, where nanotubes were used as the storage node. Yoneya et al. proposed a 40 K device with a crossed nanotube junction where one of the tubes is used as channel and the other one is used as floating gate (memory-storage node) (Yoneya et al. 2002). In this case it is the large capacitance property of the nanotube that is exploited. The floating gate is charged and discharged using a back gate. The main disadvantage of this approach is the requirement of a low operating temperature. Other reports have focused on room-temperature use of CNTs as storage nodes. Most notably, Lu et al. developed FET-based memory elements (Chakraborty et al. 2008, Lu and Dai 2006) in which the nanotubes are embedded inside the gate oxide in the metal oxide semiconductor structures. The memory structure is made up of an HfAlO/CNTs/HfAlO/Si structure. HfAlO was chosen as the tunneling and control oxides in the memory structures because of its promising performance for high-k gate dielectric applications and floating device applications. The schematic structure of a floating-gate memory device using CNTS as the floating gate is shown in Figure 3.7. The p-type substrate is designed as the current channel and the CNTs are designed to be embedded in the HfAlO film and act as the charge-storage nodes. Excellent long-term charge retention characteristics are expected for the memory structure using CNTs as a floating gate due to their hole-trapping characteristics, as is demonstrated in Lu and Dai's papers. While short-term charge retention was not found to be excellent in their prototype device, the memory window was found to remain at a reasonably large value over the long term.

3.2.9 Conclusions

CNFET-based devices for memory applications have received tremendous interest as is witnessed by the numerous published works outlined above. In all the examples presented, the working principle is that the channel of the transistor consists of a doped semiconducting CNT. For all the examples presented above, with the exception of those shown in Section 3.2.8, the storage node is usually located close to the channel but is not the channel itself, and depends dramatically on the surface chemistry of the dielectric, nanotube, and dielectric–nanotube interface. In those cases, it is the charge injection into the defects or charge traps in the dielectrics or interface responsible for the bistability and the memory properties.

3.3 NEMS-Based Memory

3.3.1 NEMS: Generalities

NEMS are made of electromechanical devices that have critical dimensions from hundreds to few nanometers (Ke and Espinosa 2006a,b). By exploiting nanoscale effects, NEMS offer a number of unique properties, which in some cases can differ significantly from those of the conventional microelectromechanical systems (MEMS). Those properties pave the way to applications such as force sensors, chemical sensors, and ultrahigh frequency resonators. For instance, NEMS operate in the microwave range and have a mechanical quality that allows low-energy dissipation, active mass in the femtogram range, unprecedented sensitivity (forces in the attonewton range, mass up to attograms, heat capacities below yoctocalories), power consumption on the order of 10 attowatts, and high integration levels (Ke and Espinosa 2006a,b). The most interesting properties of NEMS arise from the behavior of the active parts, which is typically in the form of cantilevers or doubly clamped beams with nanoscale dimensions. In NEMS, the charge controls the mechanical motion, and vice versa. The presence of mechanical motion demands that the moving element to possess high-quality mechanical properties, including high strengths, high Young's moduli, and low density. While limitations in strength and flexibility compromise the performance of Si-based NEMS actuators, CNTs are better candidates to realize the full potential of NEMS, in part due to their one-dimensional structure, high aspect ratio, perfect terminated surfaces, and exceptional electronic and mechanical properties. These properties, now complemented by significant advances in growth and manipulation techniques, make CNTs the most promising building blocks for next-generation NEMS (Bernholc et al. 2002, Chakraborty et al. 2007, and Yousif et al. 2008).

A majority of CNT-based NEMS devices exploit the specific propensity of CNTs to respond efficiently to capacitive forces. Capacitive forces can develop between a nanotube and a gate electrode when the presence of a gate potential induces the rearrangement of a net charge on the nanotube's surface, which in turn causes the appearance of a capacitance force between the nanotube and the gate. Because the nanotube is very flexible, the capacitance force bends the nanotube toward the gate electrode. This phenomenon hinges on two key properties of the nanotube: a large capacitance due to its shape and size and its exceptional mechanical flexibility. In addition to capacitance forces, other forces play a role in nanotube-based NEMS: elastic, van der Waals (vdW), and short-range forces. It is the delicate balance between those forces that makes the functioning of nanotube-based NEMS possible. Here we review a few examples of NEMS implementation for memory applications. We will discuss crossbar nonvolatile RAM, nano-relays, feedback-controlled nano-cantilevers, electro-actuated multiwalled nanotubes, linear-bearing nano-switches, and telescoping nanotube devices.

3.3.2 Carbon Nanotube Crossbars for Nonvolatile Random Access Memory Applications

Rueckes et al. proposed one of the most promising applications of CNTs for memory applications (Rueckes et al. 2000). The device exploits a suspended SWCNT crossbar array for both I/O and switchable bistable elements with well-defined on and off states. The crossbar consists of a set of parallel SWCNTs on a substrate and a set of parallel SWCNTs that are suspended on a periodic array of supports (Figure 3.8). The storage node is found at each place where two nanotubes cross. The bistability is obtained from a balance between the elastic energy (corresponding to the bending energy of the tube, having a minimum for a non-bent tube), and the attractive vdW energy (which creates a minimum corresponding to a situation where the upper nanotube is deflected downward into contact with the lower nanotube), as shown qualitatively in Figure 3.9. Since one minimum corresponds to a large vertical distance between the two mutually perpendicular arrays (defined roughly by the height of the supports), it corresponds to a situation where no current can flow between the two wires (this is the off state). At the second minimum (roughly 0.34 nm, the distance between two tubes in a bundle), tunneling current is possible as the tube–tube distance is small enough to allow wave-function overlap between the two tubes. The "bent" geometry therefore corresponds to the on state. The device can be switched between the on and off situation by transiently charging the nanotubes to produce attractive or repulsive electrostatic forces. In the integrated system, electrical contacts are made only at one end of each of the lower and upper sets of the nanoscale wires in the crossbar array, which makes it possible to address many device elements from a limited number of contacts. It was found that there is a wide range of parameters that yield a bistable potential for the proposed device configuration. The robustness of the two states suggests: this architecture is tolerant to variations in the structure. The other important feature of this device is the large difference in resistance between the two states (this is the key property of electron tunneling: the



FIGURE 3.8 NRAM device made from a suspended nanotube device architecture with a three-dimensional view of a suspended crossbar array showing four junctions with two elements in the on state and two elements in the off state. The on state corresponds to nanotubes in contact and the off state to nanotubes separated. The substrate consists of a conducting layer (dark gray) that terminates in a thin dielectric layer (light gray). The lower nanotubes are supported directly on the dielectric film, whereas the upper nanotubes are suspended by periodic inorganic or organic supports (gray blocks). A metal electrode, represented by yellow blocks, contacts each nanotube. (Reprinted from Rueckes, T. et al., *Science*, 289(5476), 94, 2000. With permission.)



FIGURE 3.9 Interaction energies between two SWCNTs (one top and one bottom) in the device shown in Figure 3.8. (a) Mechanical strain in the top nanotube and (b) attractive van der Waals interaction, showing a minimum at the nanotube–nanotube distance of about 0.34 nm. Plot in (c) shows the resulting bi-stable potential well used for storing information. The first minimum is in the on state (contact) and the second minimum is the off state (physical separation). The existence of the energy barrier between the two minima ensures nonvolatility.

tunneling resistance decreases exponentially with the separation), which makes the device operation very reliable. The main drawback of the proposed geometry remains however, that at such small dimensions, the junction gap size imposes significant challenges in the nanofabrication of parallel device arrays.

The concept proposed by Rueckes et al. was further developed by the Nantero company, which has devoted a particular important effort toward integrating nanotube array-based memory devices for practical applications. In an IEEE communication in 2004, Ward and coworkers improved the initial device by proposing a novel technique to overcome the hurdle of manipulating individual nanotube structures at the molecular level (Ward et al. 2004). This technique allows CNT-based NEMS devices to be fabricated directly on existing production CMOS fabrication lines. The approach relies on the deposition and lithographic patterning of a 1–2 nm thick fabric of nanotubes, which retain their molecular-scale electromechanical characteristics, even when patterned with 80 nm feature sizes. Because the nonvolatile memory elements are created in an all-thin-film process, it can be monolithically integrated directly within existing CMOS circuitry to facilitate addressing and readout. The transfer of the NRAM fabrication process to a commercial CMOS foundry is ongoing, and, when commercialized, will be the first actual application of CNTs for their unique electronic properties.

A modified NEMS switch using a suspended CNT was studied by Cha et al. (2005). In that memory element, the device has a triode structure and is designed so that a suspended CNT is mechanically switched to one of two self-aligned electrodes by repulsive electrostatic forces between the tube and the other self-aligned nanotube electrodes. One of the self-aligned electrodes is set as the source electrode and the third is the gate electrode. The nanotube is suspended between the two other electrodes (acting as a drain electrode). As the gate bias increases, the force between the gate and the drain electrode deflects the suspended CNT toward the source electrode and establishes electric contact, which results in current flow between the source and the drain electrodes. The electrical measurements show well defined on and off states that can be changed with the application of the gate voltage.

Dujardin et al. exposed another type of memory device based on suspended nanotubes. In their NEMS, multiwall carbon nanotubes (MWCNTs) are suspended across metallic trenches at an adjustable height above the bottom electrode (Dujardin et al. 2005). When a voltage is applied between the nanotube and the bottom electrode, the nanotube switches between conducting and nonconducting states by physically getting closer or farther from the bottom electrode. The device acts as a very efficient electrical switch and can be improved by surface functionalizing the bottom electrode with a self-assembled monolayer. The nanotube bridge was also experimentally studied by Kang et al. who highlighted the importance of the interatomic interactions between the CNT bridge and the substrate and the damping rate on the operation of the NEM memory device as a nonvolatile memory (Kang et al. 2005).

3.3.3 Nanorelays

CNT nanorelays are three terminal devices made up of a conducting CNT positioned on a terrace on a silicon substrate (Figure 3.10). It is connected to a fixed-source electrode (single clamping) and a gate electrode is placed beneath the nanotube. When a bias is applied to it, charge is induced in the nanotube and the resulting capacitance force established between the gate and the tube triggers the bending of the tube, whose end is brought in closer contact to the drain electrode, thereby closing an electric circuit. This device was first proposed by Kinaret et al. (2003), and later demonstrated experimentally by Lee et al. (2004) and by Axelsson et al. (2005). As in other memory devices, the mechanism hinges on the existence of two stable positions (bistability), corresponding to the on and off states, respectively. The advantage of the device is that it is characterized by a sharp transition between the conducting and the nonconducting states. The large variation in the resistance is due to the exponential dependence of the tunneling resistance on the tube-end–drain distance. The transition occurs at fixed source–drain potential, when the gate voltage is varied. In this case, the tube is bent toward the drain and a large current is established, which subsequently disappears when the tube is moved far from it. Aside from possessing the property of a memory element, this device also allows for the amplification of weak signals superimposed on the gate voltage.

A number of investigations, theoretical and experimental, have been performed to further characterize and optimize the practical applications of the nanorelay for memory purposes. The fundamental property of the nanorelay is reached for a balance of the vdW, adhesive (close range), electrostatic (capacitance), and elastic forces. The so-called *pull-in* voltage (voltage required to bring the tube in contact with the drain) was first studied by Dequesnes et al. for a two-terminal device where the entire substrate acted as the gate electrode (Dequesnes et al. 2002). It was found that vdW forces reduce the pull-in voltage, but do not qualitatively modify the on–off transition. The importance of vdW forces decreases with decreasing tube length and increasing terrace height and tube diameter. The transition is, however, very sensitive to short-range attractive forces, which enhance the tendency of the CNT to remain in contact (*stiction* effect). Stiction makes



FIGURE 3.10 Nanorelay: schematic picture of the model system consisting of a conducting CNT placed on a terraced Si substrate. The terrace height is labeled h, and q denotes the excess charge on the tube. The CNT is connected to a source electrode (S), and the gate (G) and drain (D) electrodes are placed on the substrate beneath the CNT. The displacement x of the nanotube tip is measured toward the substrate. Typical practical lengths are $L \sim 50$–100 nm, $h \sim 5$ nm. (Reprinted from Kinaret, J.M. et al., *Appl. Phys. Lett.*, 82(8), 1287, 2003. With permission.)

the device unusable as it remains stuck in the on position (Jonsson et al. 2004a,b). The effect of the surface forces can be visualized by means of a stability diagram, which reveals the existence and positions of zero net force (local minima) on the cantilever as a function of gate voltage and tube deflection. A typical curve was computed by Jonsson et al. and is reproduced in Figure 3.11. A stability diagram with more than one local equilibrium for a specific voltage results in a hysteretic behavior in the I–V_g characteristics (more than one position of zero net force means that there actually are three such positions, one of which is not stable). The net force is positive to the right of the curve and negative to the left of the curve, so that, when lowering the voltage for a tube in contact with the drain electrode, it will not release until there is no stable position at the surface. The surface forces exacerbate this effect. The stiction problem corresponds to a stable nanotube position at the surface that can no longer be modified by the application of a gate voltage. The stiction problem is a general issue encountered in many nanotube-based devices. The problem of stiction hinders the use of SWNTs (because they are too flexible) as a bistable NEMS switch. MWNT and SWNT bundles are better candidates for bistable switching (Yousif et al. 2008). This problem can be alleviated, for example, by using stiffer (by avoiding total collapse of the tube, e.g., by using MWCNTs) or shorter tubes. It can also be avoided by applying a layer of adsorbates.



FIGURE 3.11 Nanorelay stability diagram with and without surface forces computed with parameters given in Jonsson et al. (2004b). The curve shows the positions of zero net force on the tube (or local minima) as functions of gate voltage (at constant source voltage = 0.01 V) and deflection x (in units of h, see Figure 3.10). The large arrows show the direction of the force on each side of the curves, indicating that one local equilibrium state is unstable. The required voltage for pulling the tube to the surface (*pull-in* voltage) is given by A (~6.73 V). A tube at the surface will not leave the surface until the voltage is lower than the "release voltage," B and C in the figure. Note that A > B, C, which indicates a hysteretic behavior in the current-gate voltage characteristics, a feature significantly enhanced by surface forces. (Reprinted from Jonsson, L.M. et al., *Nanotechnology*, 15(11), 1497, 2004a. With permission.)

Fujita et al. suggested a very different approach with a modified device design. They proposed using a floating gate that is built between a bundle of CNTs and electrically isolated from the input and output electrodes. The bundle of CNTs is, therefore, bent by the electrostatic force between the floating and control gate, thereby allowing the on–off threshold voltage to be controlled by changing the back-gate voltage, similar to silicon MOSFET (Fujita et al. 2007). A consequence of reducing the possibility of stiction is that a higher pull-in voltage is required, and field emission from the end of the tip can be important. Field emission will become important when the effective potential at the tube end is equal or larger to the work function of the nanotube (i.e., about 4.5 V). For a set of design parameters, field emission can be deliberately sought after (noncontact mode). In the contact mode described above, tunneling current passes from the tube to the drain electrode. In the noncontact mode, the device is designed (short tube) in such a way that the tube is never in physical contact with the drain electrodes. In that case, an electron flow is established via a field emission mechanism. The field emission current onsets with a sufficiently large source–drain voltage and then increases nonlinearly as the source–drain voltage (i.e., the applied field) is further increased. The nanotube can be switched very quickly between the on and off states, and the nanorelay operation was evaluated to work in the gigahertz regime (Jonsson et al. 2004a).

3.3.4 Feedback-Controlled Nanocantilevers

A variation of the nanorelay device presented in the previous section was proposed (Ke and Espinosa 2004), as shown in Figure 3.12a. It is made of an MWCNT placed as a cantilever over a micro-fabricated step. A bottom electrode, a resistor, and a power supply complete the device circuit. Compared to the nanorelay, this is a two-terminal device, providing more flexibility in terms of device realization and control. When the applied potential difference between the tube and the bottom electrode exceeds a certain potential, the tube becomes unstable and collapses onto the electrode. The potential that causes the tube to collapse is defined as the pull-in voltage, already encountered above (Dequesnes et al. 2002). Above the pull-in voltage, the electrostatic force becomes larger than the elastic forces and the CNT accelerates toward the electrode. At small nanotube-tip electrode distance (of the order of 0.3–1.0 nm), substantial tunneling current passes between the tip of the tube and the bottom electrode. The main difference with the nanorelay design is the presence of a resistance R placed in the circuit; with the increase in the current, the voltage drop at R increases, which causes a decrease in the effective tube-electrode potential and the tube moves away from the electrode. It follows that the current decreases and a new equilibrium is reached. Without damping in the system, the cantilever would keep on oscillating at high frequency. However, damping is usually present, and the kinetic energy of the CNT dissipates. The tip ends up at a position where the electrostatic force is equal to the



FIGURE 3.12 (a) Schematic of a feedback controlled nanocantilever device. H is the initial step height and Δ is the gap between the deflected tip and bottom conductive substrate. R is the feedback resistor, as explained in the text. (b,c) Characteristic of *pull-in* and *pull-out* processes for a device with $L = 500\,\text{nm}$, $H = 100\,\text{nm}$, and $R = 1\,\text{G}\Omega$. (b) The relation between the gap Δ and the applied voltage U. (c) The relation between the current I in the circuit and the applied voltage U. (Reprinted from Ke, C.H. and Espinosa, H.D., *Appl. Phys. Lett.*, 85(4), 681, 2004. With permission.)

elastic one and a stable tunneling current is established. This is the "lower" equilibrium position for the CNT cantilever. If the applied voltage decreases, the cantilever starts retracting. When the applied potential is lower than the so-called *pull-out* voltage, the CNT leaves the "lower" position and returns back to the upper equilibrium position where the tunneling current significantly decreases and becomes negligibly small. The pull-in and pull-out processes follow a hysteretic loop for the applied voltage and current in the device. The lower and upper positions correspond to the on and off states of the switch, respectively. The lower equilibrium state is very robust, thanks to the existence of the tunneling current and the feedback resistor. (The concept of robustness is related to the value of the ratio of current in on and off states. A ratio of 104 is usually needed for such a device to be considered robust.) Representative characteristics are reproduced in Figure 3.12b. This device has been demonstrated experimentally by Ke and Espinosa (2006a,b) and Ke et al. (2005), showing striking agreement between theoretical prediction and experimental realization. The presence of the resistor allows adjusting the electrostatic field to achieve the second stable equilibrium position. This is an advantage compared to the NRAM system developed by Rueckes et al., since it reduces the constraints in fabricating devices with nanometer gaps between the freestanding CNTs and the substrate, thereby increasing reliability and tolerance to variability in fabrication parameters. The main drawback of this device for memory applications is that the memory becomes volatile; when the applied potential is turned off, the tube retracts back to the upper position and the information stored in the position of the tube is erased.

3.3.5 Data Storage Based on Vertically Aligned Carbon Nanotubes

Another type of memory cell using a nanotube cantilever is based on the work of Kim et al. on nanotweezers (Kim and Lieber 1999). The nanotweezer consists of two vertically aligned MWCNTs that are brought together or separated by the application of a bias potential between them. Motivated by that realization, Jang et al. proposed a memory system that improves the integration density and provides a simple fabrication technique applicable to other types of NEMS (Jang et al. 2005). The device consists of three MWCNTs grown vertically from predefined positions on the electrodes, as shown in Figure 3.13. The first nanotube is electrically connected to the ground and acts as a negative electrode. Positive electrostatic charges build up in the second and the third tubes when they are connected to a positive voltage. The third tube pushes the second tube toward the first tube, because of the forces induced when the positive bias of the third tube increases, while maintaining a constant positive bias on the second one. Above a threshold bias, the second tube makes electrical contact to the first tube, establishing the on state. The balance of the electrostatic, elastic, and vdW forces involved in the device operation determines the threshold bias. If the attractive force between the first and second tube is larger than the repulsive electrostatic forces between them, they remain held together even after the driving bias is removed (otherwise they would return to the original position). Therefore, the system can act as either a volatile or nonvolatile memory element, depending on the design parameters. Note that a two-terminal memory device can be devised using the same principles. In that



FIGURE 3.13 A schematic illustration of the CNT-based electromechanical switch device proposed by Jang et al. (a) Schematic of fabrication process: Three Nb electrodes are patterned by electron-beam lithography, followed by sputtering and lift off. Similarly, Ni catalyst dots were also formed on the predefined locations for the growth of MWCNTs. The MWCNTs were then vertically grown from the Ni catalyst dots. (b) Illustration of CNT-based electromechanical switch action. (c)–(d) SEM image of the actual device: The length and diameter of the MWCNTs are about 2 μm and 70 nm, respectively. The scale bar corresponds to 1 μm. (Reprinted from Jang, J.E. et al., *Appl. Phys. Lett.*, 87(16), 163114-3, 2005. With permission.)

case the "gate" electrode is no longer the third tube but a conventional gate that is used to separate the two tubes from their contact position.

Jang et al. also reported a nanoelectromechanical-switched capacitor structure based on vertically aligned MWCNTs in which the mechanical movement of a nanotube relative to a CNT-based capacitor defines on and off states. The CNTs are grown with controlled dimensions at predefined locations on a silicon substrate in a process that could be made compatible with existing silicon technology, and the vertical orientation allows for a significant decrease in cell area over conventional devices. It was predicted that it should be possible to read data with standard dynamic random-access memory-sensing circuitry. Jang et al.'s simulations suggest that the use of high-*k* dielectrics in the capacitors will increase the capacitance to the level needed for dynamic random-access memory applications (Jang et al. 2008).

3.3.6 Linear Bearing Nanoswitch

This type of memory device exploits the friction properties of MWCNTs. In MWCNTs, the intershell resistance force, or friction for the sliding of one shell inside another, is known to be negligibly small, as small as 10^{-14} N/atom (Cumings and Zettl 2000, Yu et al. 2000). The inner core of an open MWCNT can therefore be expected to move quasi-freely forward and backward along the tube axis, provided that at least one end of the tube is open. Deshpande et al. presented a remarkable application of the low-friction-bearing capabilities of MWCNTs to realize a NEM switch as shown in Figure 3.14 (Deshpande et al. 2006). The switch consists of two open-ended MWCNT segments separated by a nanometer-scale gap. The switching occurs through electrostatically actuated sliding of the inner nanotube shells to close the gap, producing



FIGURE 3.14 CNT linear bearing nanoswitch. Main panel: abrupt rise in conductance upon sweeping of source–drain voltage (open squares) and subsequent latching in the on state (filled squares). Lower-right inset: SEM image of the device after latching showing that the gap has closed. Upper-right inset: schematic cup and cone model of the system. (Reprinted from Deshpande, V.V. et al., *Nano Lett.*, 6(6), 1092, 2006. With permission.)

a conducting on state. For double-walled nanotubes, in particular, a gate voltage was found to restore the insulating off state. The device was shown to act as a nonvolatile memory element capable of several switching cycles. The authors indicate that the nanotubes are straightforward to implement, are self-aligned, and do not require complex fabrication, potentially allowing for scalability. The nanotube-bearing device is fabricated in high yield by using electric breakdown to create gaps in a single freestanding MWCNT device, producing an insulating off state. The device is actuated using electrostatic forces between the two ends of the tube that are connected to external electrodes. The force triggers a linear bearing motion that telescope the inner shells in the two multiwall or double-wall segments, so that they bridge the gap (Forro 2000). This restores electrical contact and produces the on state. Adhesion forces between the tube ends maintain the conductive state. The insulating state is controllably restored using a gate voltage, thereby completing the three-terminal nonvolatile memory devices. The gap is closed for a source–drain voltage around 9 V, leading to a conducting on state. At a large gate voltage (110 V) and small source–drain voltage (10 mV), the device snaps back to the zero conductance state. The explanation for the transition from the on state back to the off state is that the gate voltage imposes a bending stress on the nanotube and acts to break the connection. The use of elementary beam mechanics confirms that the force acting upon the two portions of the nanotube is significantly larger than the adhesion forces, allowing for the gap to be reopened.

The use of the exceptional low friction between individual walls in MWNTs is also the basic property exploited in a number of theoretically proposed structures for nanotube-based memory elements. In the following paragraphs, we will briefly review the work of Maslov (2006) and Kang and Jiang (2007).

Maslov proposed a concept that uses vertically aligned MWCNTs, that is first opened (or "peeled") layer by layer, so that the inner core is able to move along the vertical tube axis. By mounting another dielectric above the nanotube at a specific distance from the tube caps, two stable vdW states for the inner core are created and provide for nonvolatile data storage. The two stable states are (1) when the inner tube is away from the top electrode, stabilized by the interaction with the outer shell (off state, where the circuit is open) and (2) when the inner tube is in contact with the top electrode, stabilized by vdW interaction with the top electrode (on state, where the circuit is closed). The switching between the two states is realized by exploiting the electrostatic force resulting from the positive charging of the top (or bottom) electrode and negative charging of the tube inner core, pulling the core toward (away from) the top electrode. For nonvolatility purposes, it is important that the adhesion force is large enough to maintain the tube position, even when the battery potential is turned off.

Another interesting theoretical proposal using the friction properties of multiwalled systems was made by Kan and Jiang. The conceptual design and operation principle of the MWCNT-based storage are illustrated in Figure 3.15 (Kang and Jiang 2007). The main structural element of the devices is composed of a MWCNT deposited on a metallic electrode. The metallic electrode clamps the outer shell of the multiwall tube, while the inner core of the tube is allowed to freely slide back and forth (both ends of the tube outer-shell are opened). This telescoping device possesses three stable positions, resulting from the balance between the wall–wall interactions and the tube–metal electrode interactions. Two minima correspond to inner tube positions close to the electrode (allowing current to flow between that electrode and the bottom one, attached to the outer core of the tube). A third minimum corresponds to the tube positioned completely inside the outer shell. The movement of the inner core is realized using electrostatic forces induced by the voltage differences between the various electrodes. This leads to reversibility and nonvolatility, provided that the electrode material is carefully chosen (large enough vdW force to ensure contact when bias is turned off, while avoiding stiction where the nanotube cannot be separated



FIGURE 3.15 Electrostatically telescoping nanotube nonvolatile memory device. (a) The initial equilibrium position, (b) the core CNT contacts with the right electrode with V_1 and (c) the core CNT contacts with the left electrode with V_2. (d) Energetic schematics of the telescoping MWCNT-based memory, showing the presence of two local minima (bistability) and an energy barrier between them (nonvolatility). (Reprinted from Kang, J.W. and Jiang, Q., *Nanotechnology*, 18(9), 095705, 2007. With permission.)

from the electrode anymore due to small range forces, as illustrated in Figure 3.15b).

3.3.7 Conclusions

In this section, we have presented the state of the art of fundamental research of the use of CNTs NEMS for memory applications. The CNT-NEMS are particularly interesting because they exploit the two most remarkable properties of CNTs, namely, their electronic and mechanical properties. The viability of CNT-based NEMS switches and their comparison with their CMOS equivalents was recently presented by Yousif et al. (2008). A detailed analysis of performance metrics regarding threshold voltage control, static and dynamic power dissipation, and speed and integration density revealed that apart from packaging and reliability issues (which are the subject of intense current research), nanotube-based switches are competitive in low power, particularly low-standby power, logic, and memory applications.

3.4 Electromigration CNT-Based Data Storage

During the past decade there have been numerous promising concepts developed, based on utilizing ionized endohedral fullerenes and nanotubes as high-density nonvolatile memory elements. In this section the fundamental concepts underlying the operation and development of these types of systems are described and two specific examples are discussed in detail.

3.4.1 A "Bucky Shuttle" Memory Element

One of the earliest concepts for a CNT nonvolatile memory element was based on an ionized fullerene that could be electrically shuttled from one energy state to another inside a larger fullerene or CNT, as shown in Figure 3.16 (Kwon et al. 1999).



FIGURE 3.16 Illustration of the "bucky shuttle" concept as a memory element: (a) Transmission electron micrograph of a synthesized carbon structure showing a fullerene encapsulated inside a short nanotubule. (b) Molecular model depicting the ideal structure. (c) Position-dependent energy of an endohedral K@C_{60}^+ within the structure shown in (b). The results (total energy) were obtained from molecular dynamics simulations without an electric field (solid line) and following the application of a small electric field on the system (dashed line). A schematic of the corresponding C_{60} position and intrinsic state ("bit 0" or "bit 1") is shown on the figure. (d) A schematic of the overall "bucky shuttle" memory element concept that corresponds to a high-density memory board. (Reprinted from Kwon, Y.K. et al., *Phys. Rev. Lett.*, 82(7), 1470, 1999. With permission.)

One advantage of this concept was an appropriate material could be self-assembled from elemental carbon via thermal treatment of diamond power. A unique geometry of a nanotube encapsulating a fullerene, where a small fullerene structure could reside at one of the two ends of a capped nanotube or larger fullerene was experimentally identified (Figure 3.16a), and this structural arrangement became the basis for the original concept of a "bucky shuttle" memory element. In this system the on (bit 1) and off (bit 0) states correspond to the two ends of the nanotube that are local minima in the energy landscape of the endohedral fullerene (Figure 3.16c). The position of the ionized endohedral fullerene (obtained by doping with potassium, e.g., $K^+@C60$) can be manipulated by applying a bias voltage across the ends of the nanotube. The energetics of a switching field of 0.1 V/Å generated by applying a voltage of 1.5 V is shown in Figure 3.16c. With such a small electric field, integrity problems are not expected since graphitic structures are known not to degrade under fields of <3 V/Å. The overall thermal stability and nonvolatility of the system directly depends on the relative depth of the energy minima for the two states. Molecular dynamics simulations were used to explore the functional operation regime for the "bucky shuttle" and also to perform detailed performance analyses. Those calculations successfully demonstrated that information stored would be thermally stable well beyond room temperature, requiring temperatures above 3000 K to be destroyed. In addition, the results indicated that the "bucky shuttle" can be switched between the two states on a very fast timescale, ~10 ps, by applying a small electric field. This operation regime would allow for memory-switching access of close to 0.1 THz, giving a data throughput rate of 10 Gbyte/s in its simplest serial mode. Parallel arrays of the "bucky shuttles" could be envisioned from ordered close-packed nanotube arrays and such an assembly could potentially provide unprecedented memory storage (Figure 3.16d). This ideal system would offer a nonvolatile memory device with a combination of high switching speed and high density.

3.4.2 Memory Elements Based on the "Bucky Shuttle" Concept

While the "bucky shuttle" concept provides a relatively simple mechanism for storing information at the nanoscale, and it is strongly supported by molecular dynamics simulations that have solidified its theoretical operation, a practical measurement of the intrinsic on and off states is not clear. Also, the experimental production, although shown possible using self-assembly, is not able to exclusively produce the required "bucky shuttle" structures and would require novel separation and sorting techniques to facilitate their practical use. These shortcomings stimulated the development of a number of related concepts that have continued to evolve, such as a "nanotube shuttle" employing a transition from single-walled to double-walled nanotube for detection of the "shuttle" position (Kang and Hwang 2004c, 2005a), multi-endo-fullerenes- or peapod-based shuttles (Kang and Hwang 2004c, 2005b), and variations of these including boron nitride nanotubes (Choi et al. 2004, Hwang et al. 2005b), bipolar endo-fullerenes (Hwang et al. 2005a), metallofullerenes (Byun et al. 2004), and ionic fluidic media (Kang and Hwang 2004b). Again, the basic underlying concept relies on the electromigration of an encapsulated architecture(s) from one local energy minimum to another. The "nanotube shuttle," for example (see Figure 3.17), is based on the use of a capped peapod (nanotube with multiple endohedral C_{60}s, see Figure 3.17a), which is subjected to thermal and e-beam treatment (Figure 3.17b) that subsequently causes coalescence of the encapsulated C_{60}s to form an inner tubule. This is a well-known experimental process and one of the primary methods used for producing high-quality double-walled CNTs. The capped double-walled carbon nanotube (DWCNT) is then cut using lithography and etching technology in order to produce two aligned open ends with the inner tubule initially residing within one end (Figure 3.17c through e). The shuttle mechanism allows the inner tubule to move from one tube end across the gap into the other tube (Figure 3.17f). The separation of the two open ends is required in order to have two independent nanotube structures, which is critical for detecting the state that the overall system is in. The separation must be large enough to preempt strong interactions between the two nanotube structures (the two ends need to be independent in order for the electronic structure to allow unique detection) but small enough so as to prevent the shuttling inner tubule from completely escaping. For such an ideal system, the position of the inner tubule could in principle be measured by detecting the electronic structure of one of the ends since it will change from that corresponding to a single-walled to a double-walled nanotube (Lee et al. 2002).

3.4.3 Conclusions

The general "bucky shuttle" concept relies on utilizing the basic principle of electromigration in a two-level system defined by an ionized encapsulated fullerene-based structure. Its operation has been demonstrated to be very efficient (very short switching times) and is in general highly robust in regard to thermal and electrical stability. In addition, the possibility of assembling very high density architectures promises to allow construction of memory elements with high switching speed, high density, and nonvolatile storage of data. Unfortunately, despite the tremendous interest in the fundamentally simple and attractive systems underlying the use of CNT-based electromigration for memory elements, experimental realization has been difficult. This is because of the complexities in practical fabrication of the required structures and for making appropriate electrical contacts with them. As such, these types of systems have remained as conceptual ideas, to date, relying on the proof-of-principles results primarily obtained from classical molecular dynamics simulations.



FIGURE 3.17 A schematic illustration of the design (a–e) and operation of a "nanotube shuttle" memory element (f): (a) a peapod CNT that can be coalesced by e-beams and thermal treatment. (b) the coalesced DWCNT; (c) oxide film growth; (d) Masking and oxide etching; (e) etching of the DWCNT; (f) The van der Waals force (F_{vdW}) and total energy (U_{total}) as a function of the center position of the inter-nanotubule. (Reprinted from Kang, J.W. and Hwang, H.J., *Carbon*, 42, 3018, 2004a. With permission.)

3.5 General Conclusions

At the nanoscale, where electronics is integrated on a lateral scale associated with a minimum feature size significantly smaller than tens of nanometers, a number of new phenomena stemming from quantum effects and confinement dominate the processes governing the electron flow across an active device (Waser 2003). It is when those quantum effects are understood, that new device concepts can be developed and novel mechanisms tuned to desired functionality. For practical applications, the role of fundamental research is to address the question of how a new material can be employed in useful devices. This is particularly important for nanoelectronics and information storage since any technology that has ambitions to compete with conventional approaches must display significant benefits and distinct advantages. As discussed in this chapter, CNTs are among the most cited materials that have been used for prototype nanoelectronics and information-storage devices, a dominant position that originates from their intrinsic structural and electronic properties. It is clear that numerous memory devices based on CNTs have been proposed and successfully demonstrated during the past decade. Many of these devices show tremendous promise for providing enhanced densities, lower power requirements, more efficient read–write processes, and nonvolatility of data. These advantages indicate that CNT-based memory could, in principle, compete with current memory devices such as DRAM. However, cycling stability and data-retention times that are competitive with flash memory has proven to be difficult to achieve. Other critical issues revolve around practical fabrication and the scalability for CNT-based memory devices that can provide the same facility for large-scale fabrication as silicon photolithography. Presently, this goal appears to be in the distant future but it continues to be a topic of intense research. With the demonstrated potential payoff for a range of useful applications, it seems likely that a solution to these problems will eventually be found.

Acknowledgments

This research was sponsored in part by the Laboratory Directed Research and Development Program of Oak Ridge National Laboratory (ORNL), by the Division of Materials Sciences and

Engineering, and by the Center of Nanophase Materials Science, U.S. Department of Energy under Contract No. DEAC05-00OR22725 with UT-Battelle, LLC at ORNL.

References

Akdim, B. and Pachter, R., Switching behavior in pi-conjugated molecules bridging nonmetallic electrodes: A density functional theory study, *Journal of Physical Chemistry C* 112(9), 3170–3174, 2008.

Axelsson, S., Campbell, E. E. B., Jonsson, L. M. et al., Theoretical and experimental investigations of three-terminal carbon nanotube relays, *New Journal of Physics* 7, 245, 2005.

Bachhofer, H., Reisinger, H., Bertagnolli, E., and von Philipsborn, H., Transient conduction in multidielectric silicon-oxide-nitride-oxide semiconductor structures, *Journal of Applied Physics* 89(5), 2791–2800, 2001.

Bernholc, J., Brenner, D., Nardelli, M. B., Meunier, V., and Roland, C., Mechanical and electrical properties of nanotubes, *Annual Review of Materials Research* 32, 347–375, 2002.

Bichoutskaia, E., Popov, A. M., and Lozovik, Y. E., Nanotube-based data storage devices, *Materials Today* 11(6), 38–43, 2008.

Byun, K. R., Kang, J. W., and Hwang, H. J., Nanoscale data storage device of metallofullerene peapods, *Journal of the Korean Physical Society* 45(2), 416–422, 2004.

Cha, S. N., Jang, J. E., Choi, Y. et al., Fabrication of a nanoelectromechanical switch using a suspended carbon nanotube, *Applied Physics Letters* 86(8), 083105-3, 2005.

Chakraborty, R. S., Narasimhan, S., and Bhunia, S., Hybridization of CMOS with CNT-based nano-electromechanical switch for low leakage and robust circuit design, *IEEE Transactions on Circuits and Systems I—Regular Papers* 54(11), 2480–2488, 2007.

Chakraborty, G., Sarkar, C. K., Lu, X. B., and Dai, J. Y., Study of the tunnelling initiated leakage current through the carbon nanotube embedded gate oxide in metal oxide semiconductor structures, *Nanotechnology* 19(25), 255401, 2008.

Charlier, J. C., Blase, X., and Roche, S., Electronic and transport properties of nanotubes, *Reviews of Modern Physics* 79(2), 677–732, 2007.

Choi, W. B., Chae, S., Bae, E. et al., Carbon-nanotube-based nonvolatile memory with oxide-nitride-oxide film and nanoscale channel, *Applied Physics Letters* 82(2), 275–277, 2003.

Choi, W. Y., Kang, J. W., and Hwang, H. J., Bucky shuttle memory system based on boron-nitride nanopeapod, *Physica E—Low-Dimensional Systems & Nanostructures* 23(1–2), 135–140, 2004.

Cui, J. B., Sordan, R., Burghard, M., and Kern, K., Carbon nanotube memory devices of high charge storage stability, *Applied Physics Letters* 81(17), 3260–3262, 2002.

Cumings, J. and Zettl, A., Low-friction nanoscale linear bearing realized from multiwall carbon nanotubes, *Science* 289(5479), 602–604, 2000.

Dequesnes, M., Rotkin, S. V., and Aluru, N. R., Calculation of pull-in voltages for carbon-nanotube-based nanoelectromechanical switches, *Nanotechnology* 13(1), 120–131, 2002.

Derycke, V., Martel, R., Appenzeller, J., and Avouris, P., Carbon nanotube inter- and intramolecular logic gates, *Nano Letters* 1(9), 453–456, 2001.

Derycke, V., Martel, R., Appenzeller, J., and Avouris, P., Controlling doping and carrier injection in carbon nanotube transistors, *Applied Physics Letters* 80(15), 2773–2775, 2002.

Deshpande, V. V., Chiu, H. Y., Postma, H. W. C. et al., Carbon nanotube linear bearing nanoswitches, *Nano Letters* 6(6), 1092–1095, 2006.

Duan, X. F., Huang, Y., and Lieber, C. M., Nonvolatile memory and programmable logic from molecule-gated nanowires, *Nano Letters* 2(5), 487–490, 2002.

Dujardin, E., Derycke, V., Goffman, M. F., Lefevre, R., and Bourgoin, J. P., Self-assembled switches based on electroactuated multiwalled nanotubes, *Applied Physics Letters* 87(19), 193107-3, 2005.

Forro, L., Nanotechnology: Beyond Gedanken experiments, *Science* 289(5479), 560–561, 2000.

Freitag, M., Johnson, A. T., Kalinin, S. V., and Bonnell, D. A., Role of single defects in electronic transport through carbon nanotube field-effect transistors, *Physical Review Letters* 89(21), 216801, 2002.

Fuhrer, M. S., Kim, B. M., Durkop, T., and Brintlinger, T., High-mobility nanotube transistor memory, *Nano Letters* 2(7), 755–759, 2002.

Fujita, S., Nomura, K., Abe, K., and Lee, T. H., 3-d nanoarchitectures with carbon nanotube mechanical switches for future on-chip network beyond CMOS architecture, *IEEE Transactions on Circuits and Systems I—Regular Papers* 54(11), 2472–2479, 2007.

Ganguly, U., Kan, E. C., and Zhang, Y., Carbon nanotube-based nonvolatile memory with charge storage in metal nanocrystals, *Applied Physics Letters* 87(4), 043108-3, 2005.

Goldsmith, B. R., Coroneus, J. G., Khalap, V. R. et al., Conductance-controlled point functionalization of single-walled carbon nanotubes, *Science* 315(5808), 77–81, 2007.

He, J. L., Chen, B., Flatt, A. K. et al., Metal-free silicon-molecule-nanotube testbed and memory device, *Nature Materials* 5(1), 63–68, 2006.

Hwang, H. J., Byun, K. R., Lee, J. Y., and Kang, J. W., A nanoscale field effect data storage of bipolar endo-fullerenes shuttle device, *Current Applied Physics* 5(6), 609–614, 2005a.

Hwang, H. J., Choi, W. Y., and Kang, J. W., Molecular dynamics simulations of nanomemory element based on boron-nitride nanotube-to-peapod transition, *Computational Materials Science* 33(1–3), 317–324, 2005b.

Jang, J. E., Cha, S. N., Choi, Y. et al., Nanoelectromechanical switches with vertically aligned carbon nanotubes, *Applied Physics Letters* 87(16), 163114-3, 2005.

Jang, J. E., Cha, S. N., Choi, Y. J. et al., Nanoscale memory cell based on a nanoelectromechanical switched capacitor, *Nature Nanotechnology* 3(1), 26–30, 2008.

Jonsson, L. M., Axelsson, S., Nord, T., Viefers, S., and Kinaret, J. M., High frequency properties of a CNT-based nanorelay, *Nanotechnology* 15(11), 1497–1502, 2004a.

Jonsson, L. M., Nord, T., Kinaret, J. M., and Viefers, S., Effects of surface forces and phonon dissipation in a three-terminal nanorelay, *Journal of Applied Physics* 96(1), 629–635, 2004b.

Kang, J. W. and Hwang, H. J., Carbon nanotube shuttle' memory device, *Carbon* 42, 3018–3021, 2004a.

Kang, J. W. and Hwang, H. J., Nano-memory-element applications of carbon nanocapsule encapsulating potassium ions: Molecular dynamics study, *Journal of the Korean Physical Society* 44(4), 879–883, 2004b.

Kang, J. W. and Hwang, H. J., Schematics and atomistic simulations of nanomemory element based on carbon tube-to-peapod transition, *Japanese Journal of Applied Physics Part 1—Regular Papers Short Notes & Review Papers* 43(7A), 4447–4452, 2004c.

Kang, J. W. and Hwang, H. J., Carbon nanotube shuttle memory device based on singlewall-to-doublewall carbon nanotube transition, *Computational Materials Science* 33(1–3), 338–345, 2005a.

Kang, J. W. and Hwang, H. J., Schematics and simulations of nanomemory device based on nanopeapods, *Materials Science & Engineering C—Biomimetic and Supramolecular Systems* 25(5–8), 843–847, 2005b.

Kang, J. W. and Jiang, Q., Electrostatically telescoping nanotube nonvolatile memory device, *Nanotechnology* 18(9), 095705, 2007.

Kang, J. W., Lee, J. H., Lee, H. J., and Hwang, H. J., A study on carbon nanotube bridge as a electromechanical memory device, *Physica E: Low-Dimensional Systems and Nanostructures* 27(3), 332–340, 2005.

Ke, C. H. and Espinosa, H. D., Feedback controlled nanocantilever device, *Applied Physics Letters* 85(4), 681–683, 2004.

Ke, C.-H. and Espinosa, H. D., Nanoelectromechanical systems and modeling, in *Handbook of Theoretical and Computational Nanotechnology* American Scientific Publishers, Valencia, CA, 2006a.

Ke, C. H. and Espinosa, H. D., In situ electron microscopy electromechanical characterization of a bistable NEMS device, *Small* 2(12), 1484–1489, 2006b.

Ke, C. H., Pugno, N., Peng, B., and Espinosa, H. D., Experiments and modeling of carbon nanotube-based NEMS devices, *Journal of the Mechanics and Physics of Solids* 53(6), 1314–1333, 2005.

Kim, P. and Lieber, C. M., Nanotube nanotweezers, *Science* 286(5447), 2148–2150, 1999.

Kim, W., Javey, A., Vermesh, O. et al., Hysteresis caused by water molecules in carbon nanotube field-effect transistors, *Nano Letters* 3(2), 193–198, 2003.

Kinaret, J. M., Nord, T., and Viefers, S., A carbon-nanotube-based nanorelay, *Applied Physics Letters* 82(8), 1287–1289, 2003.

Kwon, Y. K., Tomanek, D., and Iijima, S., "Bucky shuttle" memory device: Synthetic approach and molecular dynamics simulations, *Physical Review Letters* 82(7), 1470–1473, 1999.

Lee, J., Kim, H., Kahng, S.-J. et al., Bandgap modulation of carbon nanotubes by encapsulated metallofullerenes, *Nature* 415, 1005–1008, 2002.

Lee, S. W., Lee, D. S., Morjan, R. E. et al., A three-terminal carbon nanorelay, *Nano Letters* 4(10), 2027–2030, 2004.

Lu, X. B. and Dai, J. Y., Memory effects of carbon nanotubes as charge storage nodes for floating gate memory applications, *Applied Physics Letters* 88(11), 113104-3, 2006.

Mannik, J., Goldsmith, B. R., Kane, A., and Collins, P. G., Chemically induced conductance switching in carbon nanotube circuits, *Physical Review Letters* 97(1), 016601, 2006.

Martel, R., Schmidt, T., Shea, H. R., Hertel, T., and Avouris, P., Single- and multi-wall carbon nanotube field-effect transistors, *Applied Physics Letters* 73(17), 2447–2449, 1998.

Martel, R., Derycke, V., Lavoie, C. et al., Ambipolar electrical transport in semiconducting single-wall carbon nanotubes, *Physical Review Letters* 87(25), 256805, 2001.

Maslov, L., Concept of nonvolatile memory based on multiwall carbon nanotubes, *Nanotechnology* 17(10), 2475–2482, 2006.

Meunier, V. and Sumpter, B. G., Tuning the conductance of carbon nanotubes with encapsulated molecules, *Nanotechnology* 18(42), 424032, 2007.

Meunier, V., Kalinin, S. V., Shin, J., Baddorf, A. P., and Harrison, R. J., Quantitative analysis of electronic properties of carbon nanotubes by scanning probe microscopy: From atomic to mesoscopic length scales, *Physical Review Letters* 93(24), 246801, 2004.

Meunier, V., Kalinin, S. V., and Sumpter, B. G., Nonvolatile memory elements based on the intercalation of organic molecules inside carbon nanotubes, *Physical Review Letters* 98(5), 056401, 2007.

Radosavljevic, M., Freitag, M., Thadani, K. V., and Johnson, A. T., Nonvolatile molecular memory elements based on ambipolar nanotube field effect transistors, *Nano Letters* 2(7), 761–764, 2002.

Rueckes, T., Kim, K., Joselevich, E. et al., Carbon nanotube-based nonvolatile random access memory for molecular computing, *Science* 289(5476), 94–97, 2000.

Sakurai, T., Yoshimura, T., Akita, S., Fujimura, N., and Nakayama, Y., Single-wall carbon nanotube field effect transistors with non-volatile memory operation, *Japanese Journal of Applied Physics Part 2—Letters & Express Letters* 45(37–41), L1036–L1038, 2006.

Scott, J. C., Materials science: Is there an immortal memory? *Science* 304(5667), 62–63, 2004.

Star, A., Lu, Y., Bradley, K., and Gruner, G., Nanotube optoelectronic memory devices, *Nano Letters* 4(9), 1587–1591, 2004.

Tans, S. J., Verschueren, A. R. M., and Dekker, C., Room-temperature transistor based on a single carbon nanotube, *Nature* 393(6680), 49–52, 1998.

Ward, J. W., Meinhold, M., Segal, B. M. et al., A nonvolatile nanoelectromechanical memory element utilizing a fabric of carbon nanotubes, in *Non-Volatile Memory Technology Symposium*, Orlando, FL, 2004, pp. 34–38.

Waser, R., *Nanoelectronics and Information Technology: Advanced Electronic Materials and Novel Devices*, Wiley-VCH, Weinheim, Germany, 2003.

Wunnicke, O., Gate capacitance of back-gated nanowire field-effect transistors, *Applied Physics Letters* 89(8), 083102, 2006.

Yang, D. J., Zhang, Q., Wang, S. G., and Zhong, G. F., Memory effects of carbon nanotube-based field effect transistors, *Diamond and Related Materials* 13(11–12), 1967–1970, 2004.

Yoneya, N., Tsukagoshi, K., and Aoyagi, Y., Charge transfer control by gate voltage in crossed nanotube junction, *Applied Physics Letters* 81(12), 2250–2252, 2002.

Yousif, M. Y. A., Lundgren, P., Ghavanini, F., Enoksson, P., and Bengtsson, S., CMOS considerations in nanoelectromechanical carbon nanotube-based switches, *Nanotechnology* 19(28), 285204, 2008.

Yu, M. F., Yakobson, B. I., and Ruoff, R. S., Controlled sliding and pullout of nested shells in individual multiwalled carbon nanotubes, *Journal of Physical Chemistry B* 104(37), 8764–8767, 2000.

Zhang, Y., Carbon nanotube based nonvolatile memory devices, *International Journal of High Speed Electronics and Systems* 16(4), 959–975, 2006.

4

Ferromagnetic Islands

Arndt Remhof
Swiss Federal Laboratories for Materials Testing and Research

Andreas Westphalen
Ruhr-Universität Bochum

Hartmut Zabel
Ruhr-Universität Bochum

4.1 Introduction 4-1
4.2 Background....... 4-1
Ferromagnetism • Ferromagnetic Domains • Hysteresis Loops • Micromagnetic Simulations • Experimental Techniques
4.3 State of the Art 4-5
Sample Preparation • Rectangular and Elliptical Islands • Ferromagnetic Dots • Ferromagnetic Rings • Noncircular Rings • Ferromagnetic Spirals • Magnetostatic Interactions
4.4 Summary and Discussion....... 4-14
References....... 4-14

4.1 Introduction

A ferromagnetic island is a detached piece of ferromagnetic material, supported by a nonmagnetic* substrate. The term *ferromagnetic island* is usually used to describe a prolate object with a thickness of a few nanometers and lateral dimensions of up to a few micrometers. If the geometrical confinement becomes comparable or smaller than the intrinsic magnetic length scales, such as the exchange length, the domain size, or the domain wall thickness, novel magnetic properties and magnetization reversal mechanisms emerge, different from the properties of the respective bulk material. The domain configuration, the reversal mechanism, and the demagnetizing field of ferromagnetic islands can be tailored by their size, their shape, and their chemical composition.

Nanomagnetism is a rapidly growing area in solid-state research and development. There exist several excellent reviews covering the whole field, including preparation and characterization techniques (Dennis et al. 2002, Martín et al. 2003, Adeyeye and Singh 2008). We do not aim to give another comprehensive overview. This chapter is intended to give an introduction to ferromagnetic islands and to illustrate their properties and interactions on some of our own selected recent experimental results. First, we will present an overview of the fundamentals of ferromagnetism, particularly with regard to its impacts on nanostructured materials. Subsequent, examples of selected systems starting from single dots and rectangular-shaped islands to more complex geometries will be discussed. Preparation and characterization techniques are only covered if they are necessary for the understanding of the physical properties. This chapter concludes with an outlook on the future perspectives.

4.2 Background

4.2.1 Ferromagnetism

The discovery of magnetism is one of the oldest cultural achievements in human history. The attraction of iron to loadstone was observed before recorded history began. Magnetism arises from the magnetic dipole moments of atoms and molecules influenced by their symmetry and by the relative orientation of their electron orbits. Depending on the response of substances in an external magnetic field, they are classified as diamagnetic, paramagnetic, ferromagnetic, antiferromagnetic, or ferrimagnetic. The main characteristic of ferromagnetic materials is their permanent magnetization, caused by a natural tendency of the magnetic moments of its atoms or molecules to align under their mutual interactions. The ferromagnetism of the 3d transition metals Fe, Co, and Ni is essentially due to a quantum mechanical phenomenon which has its origin in electrostatics (Heisenberg 1928).

The permanent magnetic moment of a free atom of the 3d transition metals is caused by the uncompensated spin moments of partly filled 3d shells and the related orbital moments. The wave function of the 3d electrons can be separated into an orbital wave function and a spin wave function. Paulis exclusion principle forces the total wave function to be antisymmetric, so that no two electrons may have the same set of quantum numbers in an atom. Parallel alignment of the spins forces the occupation of higher energy levels, allowing for a larger separation of the electrons and a reduction of their Coulomb interaction. The win in Coulomb energy is confronted with an increasing kinetic energy, as some electrons have to occupy higher energy levels for the symmetric spin configuration. Thus, the developing of ferromagnetism depends on which energy term dominates. In the most simple case of a two-electron system, the energy difference between the parallel and the antiparallel spin alignment is expressed by the exchange integral J:

---

* Throughout the text the term "nonmagnetic" will be used to address nonferromagnetic materials.

$$J = 2\int \left(\Psi_1^*(r_1)\Psi_2^*(r_2)V(r_1,r_2)\Psi_2(r_1)\Psi_2(r_2) \right) dr_1 dr_2. \qquad (4.1)$$

where

$V(r_1, r_2)$ denotes the interaction potential

$\Psi_1(r_1)$ and $\Psi_2(r_2)$ are the respective single-particle wave functions

A strong exchange interaction implies a large spatial overlap of the electron wave functions, which cannot be realized if these electrons are strictly localized. At least in the metals Fe, Co, and Ni, conduction electrons of the outer shell are not bound to their atoms, they are free to move and must interact in some way with the electrons at the lattice sites. In these metals the 3d band is overlapped in energy by a much wider 4s band. The bands are filled up to the Fermi level, so that the electrons which each atom contributes to the conduction band are not all from the 4s band, but partly from the 3d band. Therefore, the number of d electrons per atom contributing to the bulk magnetism is not an integral number (Aharoni 2000). In the bulk, the direction of the magnetization vector is defined by the crystalline symmetry. In materials with a large magnetic anisotropy there is a strong coupling between the spin and orbital angular moments within an atom. In addition, the atomic orbitals are generally nonspherical. Because of their shape, the orbits prefer to lie in certain crystallographic directions. The spin–orbit coupling then assures a preferred direction for the magnetization, called the easy direction. To rotate the magnetization away from the easy direction costs energy, the so-called anisotropy energy. The anisotropy energy depends on the lattice structure. In a perfect single crystal, the anisotropy axis is well defined macroscopically, while in a polycrystalline sample the anisotropy axis is still defined locally in each crystallite, but macroscopically it is averaged out due to the random orientation of the crystallites. In ferromagnetic islands the induced anisotropy of the geometrical shape plays a mayor role and will be discussed in more detail in the following sections. Anisotropies may also be induced by the interface to the substrate, the surface, or strains. A more detailed discussion of the relevant energy terms will be given in Section 4.2.4.

4.2.2 Ferromagnetic Domains

Most ferromagnetic materials show no resulting magnetic moment outside the material. The reason for this observation are domain structures (Hubert and Schäfer 1998). The equilibrium magnetization configuration is a result of the competition between the local effects of exchange and anisotropy with the nonlocal effect of the magnetostatic field (in the case without applied magnetic field). Exchange and anisotropy alone would favor a homogeneously magnetized sample with the magnetization along one of the system's easy axes. But this configuration creates a large, long-range dipolar stray field. The energy contained in the field can be reduced thoroughly by separation of the sample into so-called magnetic domains or Weiss regions, in which the magnetization is still orientated along one of the easy axes, and where the demagnetizing fields of the different domains compensate each other. Only at the boundary between the domains, a domain wall is created, where locally some exchange and anisotropy energy is invested. A domain structure is stable if the interplay between magnetic field energy and domain wall energy has reached an optimal value.

Inside a domain the homogeneous magnetization is parallel to an easy axis direction of the magnetic anisotropy. Thus, domain formation leads to a minimization of exchange and anisotropy energy. If an external magnetic field is applied to the sample, it will also bring energy into the system, the so-called Zeeman energy. The Zeeman energy favors domains parallelly aligned to the external field and leads to domain wall moving or rotation of the magnetization. In a soft magnetic material where no anisotropy exists, a continuous magnetic vector field is expected. But also in the absence of anisotropy, regular domain pattern develops due to the shape of the element. The reason for this is the requirement of a minimum demagnetizing field. The following conditions have to be fulfilled: the magnetic vector field has to be free of divergence, the field has to be aligned parallel to the edges and to the surface, and the vector field has to have a constant length. The conditions will be only achieved simultaneously, if line discontinuities are admitted (van den Berg 1986). These discontinuities are replaced by domain walls. Thus, the shape of the sample enforces a regular domain pattern in a magnetic film of no anisotropy. Van den Berg invented a geometrical procedure to construct this equilibrium domain pattern: the basic domain structure is the locus of centers of all circles inside the sample that touch the sample edge at least at two points. The most important result of van den Berg is that in most cases domains will form along the edges (closure domains) in order to minimize the demagnetizing field. Figure 4.1 schematically shows the reduction of the stray field by domain formation with the help of van den Berg's construction. Examples of the domain structure of a three-dimensional Fe island, discussed on the basis of van den Berg's construction, are provided by Hertel et al. (2005).

Inside a domain wall the magnetization changes its direction in numerous small steps (Bloch 1932). The cost of exchange energy for building up a domain wall decreases as the domain wall thickness increases. On the other hand a minimum value for the anisotropy energy is observed in thin domain walls as the magnetization direction inside the wall is different from the easy direction. In the equilibrium state, the domain wall thickness δ_W follows from the balance of the exchange energy J, and the anisotropy energy K_1:

$$\delta_W = \sqrt{\frac{JS^2\pi^2}{K_1 a}} = \pi\sqrt{\frac{A}{K_1}} \qquad (4.2)$$

A is a material constant, the so-called exchange constant, and equals JS^2/a for a simple cubic lattice with lattice constant a.



FIGURE 4.1 Van den Berg's construction on the example of ferromagnetic islands with simple geometric shapes.

The domain wall thickness can vary from a few nanometers in Co, to approximately 30 nm in Fe up to a few micrometers in extreme soft permalloy. If the domain wall thickness exceeds the lateral extension of the island, it will stay as a single domain. Larger islands will develop a domain structure if the gain in field energy overcompensates the domain wall energy. There is also a lower limit for the existence of a stable ferromagnetic single-domain island. As the anisotropy energy of an island scales with the volume of the island, there is a critical volume below which the anisotropy energy becomes comparable to the thermal energy k_BT. Below this *superparamagnetic limit*, the magnetization of the island is subject to thermal fluctuations. For magnetic data storage devices, the superparamagnetic limit marks the smallest possible bit size. A more detailed discussion of the relevant length scales in nanostructures is given by Martín et al. (2003) and Dennis et al. (2002).

4.2.3 Hysteresis Loops

The magnetic response of a ferromagnetic material to an external field is represented by a hysteresis loop in which the magnetization is plotted as a function of the magnetic field strength. The magnetization is a vector. Usually, the component parallel to the applied field (the x-component) is recorded. A hysteresis loop consists of two branches. They are called the ascending and descending branch, as it depicts the magnetization during field increase or field decrease. Generally, both branches do not overlap, i.e., the magnetization is not unambiguously defined on the field strength alone, it also depends on the magnetic history of the sample. The area enclosed by the two branches represents the magnetic energy stored in the system. A hysteresis loop shows three characteristic points: (1) The point where a further increase in magnetic field strength does not result in a further increase of the magnetization is called the saturation field. At this point all domains are aligned with the external field. (2) The persisting magnetization in zero field is called the remanent magnetization or the remanence. (3) The field needed to reduce the magnetization to zero is the coercive field or the coercivity. Coercivities may range from the mOe range for soft magnetic FeNi alloys to several 10 kOe for hard magnetic $SmCo_5$. Figure 4.2 shows two model hysteresis loops for a ferromagnetic island magnetized along the easy axis (left) and along the hard axis (right). The remagnetization along the easy axis usually is dominated by the rapid growth of oppositely oriented domains as soon as the applied field exceeds the nucleation field. In the case of elongated islands often domains nucleate at the two ends of the islands that grow by domain wall movement. The hysteresis loop is therefore characterized by a sudden change of the magnetization close to the coercive field and a high remanence, resulting in a square-shaped hysteresis loop. If on the other hand the field is applied along the hard axis, the remagnetization is realized by a coherent rotation of all the individual spins. The resulting hystereses loop therefore shows a continuous variation of the magnetization and a low remanence.

4.2.4 Micromagnetic Simulations

For the prediction of the expected domain configuration and the time-dependent development of the magnetization, micromagnetic computer simulations are used. A realistic approach for the description of the magnetic behavior of a magnetic material is to ignore the atomic nature of matter, to neglect quantum



FIGURE 4.2 Model hysteresis loops for a single-domain island magnetized along the easy axis (left) and along the hard axis (right).

effects, and to use classical physics in a continuum description. Micromagnetism is the link between the atomistic, quantum mechanical description of the single atom on the one hand and the macroscopic view of a material characterized by the shape of its hysteresis curve on the other hand. Essentially, the magnetization is to be assumed as a continuous vector field $\vec{M}(\vec{r})$; thus, only the local average over the magnetic moments in a certain neighborhood instead of individual spins is taken into account. The history of micromagnetics starts from 1935 with the paper of L. Landau and E. Lifshitz on the structure of a wall between two antiparallel domains (Landau and Lifschitz 1935), and the work of W. F. Brown Jr. around 1940. A detailed treatment of micromagnetism is given by Brown (1963) and Prohl (2001). The energy will be formulated in terms of the continuous magnetization vector field, and this energy will be minimized in order to determine static magnetization structures. Thermodynamically, the system is described by the free energy $F = E - TS$ with the inner energy E of the system. There are several contributions to the inner energy:

- The exchange energy, responsible for the ferromagnetic coupling, is given by

  $$E_{\text{ex}} = -2\sum_{i<j} J_{ij}\vec{S}_i \cdot \vec{S}_j, \tag{4.3}$$

  where
  the coefficients J_{ij} are the exchange integrals
  the coefficients $\vec{S}_i$ are the atomic spins

  Positive J_{ij} lead to ferromagnetic order while negative J_{ij} cause antiferromagnetic order. The exchange energy is short-ranged and involves a summation over the nearest neighbors.
- The magnetostatic or demagnetization energy, which is the potential energy that the magnetic moments experience in their own magnetic field, can be written as

  $$E_{\text{demag}} = -\frac{\mu_0}{2}\int_V \vec{H}_{\text{d}} \cdot \vec{M} dV, \tag{4.4}$$

  where μ_0 is the magnetic constant. The magnetostatic or demagnetizing field, $\vec{H}_{\text{d}}$, is related to the magnetization via $\nabla \cdot \vec{H}_{\text{d}} = -\nabla \cdot \vec{M}$ as Maxwell's equation require that $\nabla \cdot \vec{B} = \mu_0 \nabla \cdot (\vec{H} + \vec{M}) = 0$. In the case of a homogenous magnetized ferromagnetic sample the demagnetizing energy can be expressed as

  $$E_{\text{demag}} = \frac{V}{2}\left(N_{11}M_x^2 + N_{22}M_y^2 + N_{33}M_z^2\right) \tag{4.5}$$

  where N_{ii} are the components of the so-called magnetometric demagnetizing tensor **N**. The components of the tensor are purely determined by the geometry.
- The magnetocrystalline anisotropy originates at the atomic level as discussed in Section 4.2.1. In a system with uniaxial anisotropy along the z direction, the leading energy terms are

  $$E_{\text{mca}} = VK_{u1}\sin^2\theta(1 + \sin^2\theta) \tag{4.6}$$

  where
  θ is the angle between the z direction and the magnetization
  K_{u1} is the anisotropy constant
  V is the volume of the sample

  A large positive anisotropy constant K_{u1} describes an easy axis, and a large negative constant K_{u1} an easy plane, perpendicular to the anisotropy axis. Uniaxial anisotropy occurs in hexagonal crystals such as Co, for example. Cubic anisotropy occurs for example in Fe and Ni, the leading energy terms are

  $$E_{\text{mca}} = VK_1\left(m_x^2 m_y^2 + m_y^2 m_z^2 + m_x^2 m_z^2\right) + VK_2 m_x^2 m_y^2 m_z^2 \tag{4.7}$$

  The anisotropy constants K_1 and K_2 and their ratio determine the easy axis of the system. Typical values for K_1 are in the order of 10^3–10^5 J/m^3. Most work on ferromagnetic islands has been either performed on polycrystalline samples, where the magnetocrystalline anisotropy is averaged out, or on materials with a negligible anisortopy. Therefore, contributions of magnetocrystalline anisotropy are not considered throughout this contribution.
- The surface anisotropy arises from the broken symmetry at the interface between the ferromagnetic and a nonmagnetic material. It can phenomenologically be described by the anisotropy constant K_{S}:

  $$E_{\text{S}} = \frac{1}{d}VK_{\text{S}}\sin^2\theta, \tag{4.8}$$

  where
  d denotes the thickness of the island
  θ denotes the angle between the magnetization and the surface normal

  K_{S} lies typically in the order of 10^{-4} to 10^{-3} J/m^2. The sign of K_{S} defines whether the easy axis is in-plane or out-of-plane. For the ferromagnetic islands discussed in this chapter, the surface anisotropy is negligible compared to the shape anisotropy, forcing in-plane magnetization.
- Finally the Zeeman energy is the energy of the magnetic moments in an external magnetic field H_{a}. It is given by

  $$E_{\text{Zeeman}} = -\mu_0 M_{\text{sat}}\int_V \vec{H}_{\text{a}} \cdot \vec{m} dV, \tag{4.9}$$

As experimentally the applied magnetic field $\vec{H}_a$ is the control variable, it is more adapted to use Gibbs free energy or thermodynamic potential

$$G(T, \vec{H}_a, \vec{M}) = F - \mu_0 \int \vec{H}_a \cdot \vec{M} \, dV. \qquad (4.10)$$

We assume that all experiments are performed at constant temperature, so that the entropy term can be neglected. Of course, it is necessary to take into account that the material constants are temperature-dependent. The system has the thermodynamic tendency to evolve toward the minimum of the potential G when approaching equilibrium. The metastable states of the ferromagnetic system are local minima of the potential G.

4.2.5 Experimental Techniques

To investigate the magnetic domain structure as well as the remagnetization process of micro- and nanostructured materials, a number of experimental techniques are available to the experimenter. On the one hand, magnetic domains can be imaged in real space by various techniques, an overview is given in Ref. Hopster and Oepen (2005): Kerr microscopy (Feldtkeller and Stein 1967), Lorentz microscopy (Chapman et al. 1994), scanning electron microscopy with polarization analysis (SEMPA) (Oepen and Kirschner 1991), scanning transmission x-ray microscopy (STXM) (Fischer et al. 1999), photo emission electron microscopy (PEEM) (Mundschau et al. 1996), spin-polarized low-energy electron microscopy (SPLEEM) (Bauer 1994), or magnetic force microscopy (MFM) (Martin and Wickramasinghe 1987). If real space images are obtained at different external magnetic field values, the hysteresis loop is derived by evaluating the total size of the magnetic domains having a particular direction of the magnetization vector with respect to the applied field. On the other hand, magnetic hysteresis loops can be measured with magneto-optical Kerr effect (MOKE) (Kerr 1877), micro MOKE (Allwood et al. 2003), superconducting quantum interference device (SQUID) magnetometry (Philo 1977), or vibrating sample magnetometry (VSM) (Foner 1959). Micro MOKE is an advanced magnetometry for the analysis of single magnetic nanostructures. In the case of the other techniques, a large number of identical elements are investigated in parallel in order to increase the resolution and accuracy. Therefore, the measured hysteresis loops yield information on the average remagnetization process of all elements and not on a single element. Thus, correlation effects between elements also become visible. The periodicity of an artificially structured array of ferromagnetic islands enables the use of diffraction techniques, such as Bragg-MOKE, where the Kerr effect measurements are performed at the diffraction spots from a lateral structure. Diffraction techniques suppress magnetic contributions of the substrate and contain information about the domain configuration inside the magnetic structures via the magnetic form factor (Remhof et al. 2007). Most experimental techniques can be extended to a vector-magnetometer: by applying a field perpendicular to the direction of measurement, the transverse (the y) component of the magnetization in the ferromagnetic structure can be investigated. From the measurements with the longitudinal and the transverse field orientation, the complete in-plane magnetization vector for the remagnetization can be derived (Westphalen et al. 2007). Using a photoelastic modulator and a digital lock-in amplifier for θ and 2θ response, all three components can be analyzed by measuring different polarizations of the incident beam (Vavassori 2000).

4.3 State of the Art

4.3.1 Sample Preparation

The preparation of sub-micrometer-sized ferromagnetic islands has benefited from the advancements in miniaturization techniques over the last decades. Usually optical lithography is used to define small patterns such as integrated circuits. Lithography, originally meaning “writing with stone,” refers to a printing technique in which the imprint of an original pattern is reproduced on paper. In microtechnology it is used do describe a process, in which the desired pattern is first defined as a template on a mask, that can be transferred to the work piece. In optical lithography this is usually an opaque pattern on a transparent glass plate. An optical system is that used to downsize the pattern by projection onto a substrate coated with a photo-sensitive resist. The great advantage of this method is the high throughput. It is limited by the wavelength of the light and by the refractive power of the optical components. E-beam lithography (EBL) is a direct writing technique, in which the resist is exposed by a focused electron beam. In this case the mask only exists as a design file in the computer. The advantage is the high flexibility and the high resolution as compared to the optical methods. There are two kinds of resist: *positive* and *negative*. In the positive technique, first a resist template is produced by one of the aforementioned lithographic methods. Then the magnetic film is deposited onto the template. In a final chemical lift-off step only those magnetic islands remain, which have direct contact to the substrate or another metal layer. In the negative process a pattern is etched out of a continuous ferromagnetic film. Therefore, the homogeneous film is covered with an etch-resistant resist. After exposure, developing, and dry etching, only those magnetic islands that were exposed to the e-beam and covered with resist remain. Both methods are schematically illustrated in Figure 4.3. Apart from visible and UV light and electrons, other radiations such as x-rays and focused ion beams are well established in micro- and nanolithography. Also self-assembly and nanoimprint technologies are in use to prepare ferromagnetic islands. For a more detailed description of the various lithographic techniques we refer to Waser (2003), Bucknall (2005), and Suzuki and Smith (2005).



FIGURE 4.3 Patterning steps using positive resist (top panel) and negative resist (bottom panel).

4.3.2 Rectangular and Elliptical Islands

The simple geometry of rectangular and elliptical islands, featuring a well-defined and pronounced uniaxial shape anisotropy, is predestined as model systems. Especially in islands composed of materials with little or no crystalline anisotropy or in polycrystalline systems, the shape anisotropy becomes dominant. In elongated islands the shape anisotropy usually forces the easy axis along the major axis, while the hard magnetic axis lies along the minor axis. The strength of the anisotropy is thereby governed by the aspect ratio (Martín et al. 2003).

At remanence small rectangular or elliptic small islands are in a single-domain state with pronounced magnetic poles at the opposite ends of the island. MFM images these magnetic poles as areas of maximum contrast as depicted in the right panel of Figure 4.4. The left panel shows a secondary electron micrograph, recorded by scanning electron microscopy (SEM) of an array of 50 nm thick, 3 μm × 300 nm-sized permalloy islands placed on a square grid of 3 μm × 3 μm on a silicon wafer. While the SEM image shows the topological contrast, the MFM images the strength of the stay field (i.e., the density of the field lines) normal to the sample. Therefore, the poles at the end, where the stray field enters and leaves the island can, respectively, be identified as black and white spots.

Larger islands will decay into domains at remanence. The terms *small* and *larger* depend on the material's properties and the aspect ratio, determining the anisotropy. Last et al. (2004) have investigated polycrystalline permalloy (Py) micro- and nanostructures (thickness: 38 and 50 nm, length: 0.2–60 μm, width: 0.2–30 μm) in order to map the multi-domain to single-domain transition with MFM. They found a single-domain state, if the aspect ratio (length:width) is greater than 20:1; the multi-domain state is visible inside the rectangles with a aspect ratio between 1:1 and 3:1. Between these two cases they observed a transition state with a featureless inner region and fan-type closure domains at both ends of the rectangle. Figure 4.5 also shows that for very small particles, where the geometric extensions approach the domain wall width, smaller aspect ratios are sufficient to obtain a single-domain state. Extreme aspect ratios lead to *ferromagnetic nanowires*. In the case of thin wires the magnetization reversal process is initiated by the nucleation of oppositely oriented domains at the two ends of the wire and the formation of 180° domain walls. During the reversal process these domains grow by domain wall motion, until the walls meet in the middle of the film where they annihilate. Thicker wires show a more complex reversal mechanism, involving perpendicular in-plane domains that fill up the inner part of the wire and 180° as well as 90° domain walls are formed (Hausmanns et al. 2002). The domain walls can be manipulated (Tsoi et al. 2003) and used to perform logic operations (Allwood et al. 2002) and they can be employed for data storage (Parkin et al. 2008).

Returning to the original discussion of rectangular and elliptic islands and their dipolar behavior in remanence, the pronounced stray field of elongated micrometer-sized islands as discussed before are ideal to study the mutual magnetostatic interactions as a function of their separation.



FIGURE 4.4 Micrographs of an array of 50 nm thick, 3 μm × 300 nm-sized permalloy islands placed on a square grid of 3 μm × 3 μm on a silicon wafer. The left panel shows a secondary electron micrograph, the right panel an magnetic force microscopy image.



FIGURE 4.5 (a) Magnetic force microscopy images of Py structures in remanence with (I) low-aspect ratio (m = 2.5, with l = 10 μm, t = 38 nm), (II) medium-aspect ratio (m ≈ 14, l = 20.9 μm, t = 38 nm), and (III) high-aspect ratio (m = 57 (top wire), m = 43 (bottom wire), t = 50 nm). (b) Experimentally observed domain states of Py microstructures and nanostructures for varied length l vs. aspect ratios m. Open squares indicate multidomain states (I), gray squares denote high remanent states (II), and closed squares indicate a single-domain state (III). The black solid line depicts the transition line between multidomain and single-domain configuration from a phenomenological model. The dotted lines are guides to the eye indicating transitions between regions I, II, and III. (Reused from Last, T. et al., *J. Appl. Phys.*, 96, 6706, 2004. With permission.)

4.3.3 Ferromagnetic Dots

For technical applications such as the magnetic data recording, each island has to be addressed individually. Therefore, interactions between the islands have to be avoided. This can be done either by increasing the distances between the islands, or by avoiding strong and extended stray fields. Due to their geometric shape, circular dots and rings of certain aspect ratio exhibit a flux-closed state known as vortex state (Cowburn et al. 1999, Raabe et al. 2000, Shinjo et al. 2000, Fraerman et al. 2002). In this case a curling magnetic structure is established, in which the spin directions only change gradually, minimizing the loss in exchange energy. This configuration suppresses the occurrence of a net in-plane magnetization (zero remanence) without the need to form magnetic domains and to build domain walls. Close to the dot center, the increasing angle between adjacent spins forces them out-of-plane, so that they can align parallel to each other along the plane normal. Therefore, in the center of the vortex a spot of perpendicular magnetization exists, first observed by Shinjo et al. (2000) in circular permalloy dots with diameters ranging from 0.3 to 1 μm and a thickness of 50 nm. MFM images obtained by Shinjo et al. are represented in Figure 4.6.



FIGURE 4.6 MFM image of an array of permalloy dots, 1 μm in diameter and 50 nm thick. (From Shinjo, T. et al., *Science*, 289, 930, 2000. With permission.)

Let us discuss the vortex state in a single permalloy dot of diameter 0.8 μm as an example for micromagnetic simulation, using the OOMMF 1.2a3 software (Donahue and Porter 1999) with a saturation magnetization $M_s = 860 \times 10^3$ A/m, exchange stiffness $A = 13 \times 10^{-12}$ J/m, anisotropy constant $K_1 = 0$, and a damping coefficient $\alpha = 0.5$. Figure 4.7 shows the result of the micromagnetic simulation.

As it is typical for an ideal vortex configuration, the y component of the magnetization is zero. Starting from negative saturation field (1) to point (2) the core of the vortex develops abruptly at the so-called *nucleation field*. In the remanent state (3) the core has moved into the center of the circular dot. This state lowers the system energy by reducing stray fields and hence lowering magnetostatic energy. Increasing the field then deforms the vortex, and its core moves away from the center of the dot to the upper edge (4). Finally it becomes unstable and again abruptly the core vanishes at the *annihilation field* (step in the hysteresis loop between (4) and (5) at approximately 90 Oe). Note that the nucleation and annihilation fields are different. The resulting minor loops are the main characteristics of the vortex state. Also note that the system is degenerate: the vortex may nucleate at the bottom and move to the top, or vice versa nucleate at the top and propagate to the bottom.

The geometrical conditions which favor the occurrence of the vortex state were studied by Cowburn at al. (1999) on the example of Supermalloy ($Ni_{80}Fe_{15}Mo_5$) dots with diameters ranging between 55 and 500 nm and a thickness range between 6 and 15 nm. The larger dots exhibit the remagnetization behavior of a vortex as described above, while the smaller dots show a more square-like hysteresis loop, a high remanence ($M_{rem}/M_{sat} \approx 0.8$) and a small coercive field, as depicted in Figure 4.8. This is characteristic of a uniform single-domain behavior. In agreement with micromagnetic simulations, the critical diameter drops with increasing thickness from 200 nm for 6 nm thick dots to 100 nm for 15 nm thick ones.



FIGURE 4.7 Hysteresis loop for the x (black line) and y component (gray line) of the magnetization, and some selected calculated magnetization profiles.



FIGURE 4.8 Hysteresis loops measured from nanomagnets of diameter d and thickness t: (a) $d = 300\,\text{nm}$, $t = 10\,\text{nm}$; (b) $d = 100\,\text{nm}$, $t = 10\,\text{nm}$. The schematic annotation shows the magnetization within a circular nanomagnet, assuming a field oriented up the page. (Reprinted from Cowburn, R.P. et al., *Phys. Rev. Lett.*, 83, 1042, 1999. With permission.)

The magnetic vortex is characterized by its rotational sense (chirality) which can be either clockwise or anticlockwise and the out-of-plane magnetization of the vortex core (polarity) pointing either upwards or downwards. Combining the chirality and the polarity, four different ground states can be realized. Often MOKE and Hall bar measurements are employed to determine the hysteresis of the magnetization reversal of circular magnetic disks (Cowburn et al. 1999, Rahm et al. 2003). The measured hysteresis has the features characteristic for the reversal process occurring through a vortex state, i.e., a vanishing remanence and closed lobes on either side of the remanence with the nucleation field and the annihilation field. However, these measurements are neither sensitive to the chirality nor to the polarity of magnetic vortices. Using MFM (Raabe et al. 2000, Shinjo et al. 2000), the polarity can be determined but not the chirality, whereas Lorentz microscopy operated in the Fresnel mode is sensitive to the chirality but not to the polarity (Raabe et al. 2000, Schneider et al. 2000).

Longitudinal Bragg MOKE on the other hand is sensitive to the average vortex chirality in a periodic array of magnetic islands. In case of longitudinal MOKE (L-MOKE) the measured variable, i.e., the Kerr rotation θ_{x} is proportional to the component of the magnetization vector $\vec{m} = (m_x, m_y)$ projected onto the intersection between the plane of incidence and the plane of the sample surface: $\theta_x \propto m_x$ (longitudinal component). For patterned samples such as an array of islands, the Kerr angle can be measured not only for the specularly reflected beam but also at the diffraction spots whose pattern represents the Fourier transform of the two-dimensional lattice structure of the real pattern. The Kerr rotation θ_x^{hk} measured for the diffraction orders h and k, corresponds to the magnetic form factor f_x^{hk}, i.e., the Fourier transform of the magnetization distribution within a single element of the array

$$f_x^{hk} \propto \int dS\,\vec{m}_x(\vec{r})\exp\left(i\vec{G}\,\vec{r}\right) \tag{4.11}$$

where

$\vec{G} = 2\pi(h\vec{e}_x + k\vec{e}_y)/a$ is the reciprocal lattice vector of the dot array
a is the periodicity of the dot array
the integral is taken over the area of a single dot

The relation between the magnetic form factor f_x^{hk} and the corresponding Kerr rotation θ_x^{hk} can be expressed as follows:

$$\theta_x^{hk} = c_{hk}(\phi_{\mathrm{i}})\left(a_{hk}\Re\left(f_{\mathrm{m}}\right) + b_{hk}\Im\left(f_{\mathrm{m}}\right)\right) \tag{4.12}$$

where ϕ_i is the angle of incidence,

$$c_{hk}(\phi_i) = \left(h\frac{\lambda}{a} - \sin(\phi_i)\right) \Bigg/ \left(1 - \left(k\frac{\lambda}{a}\right)^2\right). \tag{4.13}$$

and a_{hk} and b_{hk} are coefficients describing the extent of the real and the imaginary contribution, respectively, of the magnetic form factor to the Bragg MOKE signal. They depend on a, ϕ_i, λ, the (magneto-) optical constants of the dots and the substrate, the shape, and the thickness of the dots. With the complete knowledge of all these parameters it is possible to determine the coefficients a_{hk} and b_{hk} (Lee et al. 2008). However, since the computation is rather complicated and cumbersome, they are usually treated here as adjustable parameters.

Grimsditch et al. concluded from Bragg MOKE measurements in the transverse geometry that the vortex chirality manifests itself in the sign of the imaginary part $\Im\left(f_{\mathrm{m}}^{hk}\right)$ (Grimsditch et al. 2002). This effect can also be applied in the longitudinal geometry. It can be shown that for a magnetization reversal process occurring through a vortex state, $\Im\left(f_{\mathrm{m}}^{hk}\right)$ always possesses the global extremum at the zero point of the external magnetic field and vanishes as the sample magnetization approaches the saturation level (Grimsditch et al. 2002, Grimsditch and Vavassori 2004). Hence, this imaginary contribution is expected to give rise to a splitting of the ascending branch and the descending branch of the hysteresis loop. For an array of perfectly circular disks a random distribution of left- and right-handed chiralities is expected. In this case the splitting of the hysteresis at remanence will vanish. Since the extent of the splitting corresponds to the degree of the imbalance between clockwise and anticlockwise vortices in magnetic islands, the Bragg MOKE technique provides a statistical means of measuring the chirality distribution in an array of magnetic islands. For a perfectly circular dot there are equal chances for the occurrence of either rotational senses. The vortex chirality can be controlled by breaking the circular symmetry (Lee et al. 2008). This can be most easily realized by shaping the dot with a flat edge at the top as depicted in Figure 4.9.



FIGURE 4.9 Scanning electron micrograph of a flat dot. (Reused from Lee, M.-S. et al., *J. Appl. Phys.*, 103, 093913, 2008. With permission.)

When a magnetic field is applied in the direction parallel to the flat edge (along the x-axis), the vortex nucleation always starts at the top close to the flat edge with a negative chirality (counterclockwise). With decreasing field strength the core moves down to the bottom perpendicularly to the field direction where it is annihilated. Micromagnetic simulation confirm that along the ascending branch the rotational sense is clockwise, whereas in the descending branch it is counterclockwise in agreement with the experimental observation (Lee et al. 2008).

4.3.4 Ferromagnetic Rings

Within a disk-shaped island, the vortex is only stable for diameters above approximately 100 nm, depending on the thickness of the disk. The vortex state can be stabilized by removing the vortex core in a ring-shaped element. Apart from the low remanent vortex state, which is the ground state of the system, ferromagnetic rings exhibit another, metastable magnetic configuration, the so-called *onion state* (Rothman et al. 2001). The onion state is characterized by the formation of two equally sized domains as shown in Figure 4.10. Due to the shape anisotropy, the magnetization in both domains follows the perimeter of the ring. The onion state allows the majority of the spins to be aligned with the applied magnetic field during the decrease of the magnetization from saturation to zero. Magnetization reversal is achieved by domain wall movement. The domain wall movement starts as soon as the applied reverse field exceeds the pinning strength of the walls. For perfectly symmetric rings, the pinning strength for both walls will be identical and both walls will move synchronous. Consequently, the ring will switch from the onion state to the reverse onion state. In a real system, however, shape irregularities and defects will give rise to differences in the pinning strength, which allows the wall that moves first to annihilate with the second wall, forming the vortex state. Therefore, specific shape irregularities in ferromagnetic rings allow to tailor their reversal behavior, to stabilize the vortex state, and to determine its chirality (Kläui et al. 2001, Vaz et al. 2007).

4.3.5 Noncircular Rings

Closed flux lines in the vortex state or the dipolar onion state are not restricted to circular-shaped objects. They can also be



FIGURE 4.10 Schematic representation of the magnetization of a ring-shaped island. (a) In saturation by an applied field and (b) in remanence.



FIGURE 4.11 From left to right: Scanning electron micrograph of a square ring and sketches of the three different symmetrical ground states: vortex, onion, and horseshoe.

observed in square rings (or closed frames), as displayed in Figure 4.11. The shape anisotropy always forces the magnetization parallel to the sides of the frame. In the vortex state the magnetic moments form a closed ring; no stray field is expected to be observed outside the frame. The onion state consists of magnetically parallel-aligned sides of the frame, resulting in two magnetic poles in the opposite corners of the frames. The last panel of Figure 4.11 depicts a remanent state that is not observed in rings, the so-called *horseshoe state*. This state is formed by two magnetically parallel-aligned sides and by two antiparallel-aligned sites. Consequently two magnetic poles occur on one branch of the frame.

The remanent state is not only determined by the size and shape of the island, it can also be influenced by the direction of the external field during the magnetization reversal process. As long as the external field is applied in-plane, only the onion state is observed in remanence regardless of the azimuthal angle (Vavassori et al. 2003). However, if the field is applied perpendicular to the sample surface, the vortex state is the favorite remanent state. At intermediate angles (around 70°) the horseshoe state coexists with the onion state. MFM images of the different remanent states, together with an indication of the field direction, are presented in Figure 4.12.

Noncircular rings also allow the study of different symmetries. Triangular structures (Westphalen et al. 2006) have a sixfold magnetic shape anisotropy. In contrast to a square ring, where at the same time two sides are orientated in the hard axis direction and the other two sides point in the easy axis direction if the external magnetic field is orientated parallel to these sides, in a triangular ring structure two sides are always in an intermediate position if the third side is orientated parallel to the magnetic field, i.e., in the easy direction. This will lead to a more complex domain structure and to more possibilities for the remagnetization process according to the orientation of the structures to the applied magnetic field. By choosing different sizes for the same structure the shape anisotropy also affects the remagnetization process because it is more pronounced in the small triangular rings. Rings and islands have received most attention, because these elements show a vortex state in remanence which leads to a reduced stray field energy. Such elements can be stacked close together without disturbing each other, unlike elements with dipole character.



FIGURE 4.12 MFM images of square rings recorded in remanence after saturation in an external field. The field direction is indicated below each micrograph.

4.3.6 Ferromagnetic Spirals

Spirals are hybrids between circular islands and magnetic dipoles. In contrast to ring structures a closed magnetic flux configuration cannot be realized in the spirals during the remagnetization process. In fact they act as magnetic dipoles at the rim while the center is screened from the environment. On the other hand, a spiral is from a geometrical point of view a vortex. Therefore, spirals allow to investigate the interplay between a geometric and a magnetic vortex and to answer the question whether the geometry influences the magnetization: does the shape of a spiral lead to a vortex state in the remanent magnetization? In such a case the outer end piece of a long spiral would act as a magnetic monopole, because in the near region of the outer end piece the interaction with the second magnetic pole at the inner end piece could be neglected. The second question addressed by magnetic spirals is whether the core of the spiral is magnetically harder or softer than the outer parts and how the coercivity is affected by stray field interaction between the spirals. By choosing Fe as the material from which the spirals are fabricated a strong domain formation during the magnetization reversal is expected.

In order to address the aforementioned questions various quadratic arrays of polycrystalline Fe spirals (maximum radius = 2.8 μm, linewidth = 100 nm) were realized (Westphalen et al. 2008a). The polycrystallinity of the Fe suppresses the intrinsic magnetocrystalline anisotropy. In the first case (S1) only one spiral is set on the square grid. In a second sample (S2), it consists of two spirals facing each other without any connection while they are connected in the third sample (S3). Micrographs of the resulting pattern are shown in Figure 4.13.



FIGURE 4.13 Scanning electron micrograph images of the four Fe spiral structures used in the experiments. The different spiral structures are named S1, S2, and S3. (Reused from Westphalen, A. et al., *J. Appl. Phys.*, 104, 013906, 2008. With permission.)

The hysteresis loops are similar for all four patterns; however, strong variations occur in the coercive field values. S1 exhibits a coercive field of 240 Oe, while S2 and S3 exhibit coercive fields of 305 and 190 Oe, respectively. It is therefore possible to tailor the coercivity without disturbing the overall magnetization process.

The variations in coercivity are not only due to differences and inhomogeneities in the shape of the spiral structures. Micromagnetic simulations of ideal spiral structures, i.e., spirals without kinks and with constant linewidth, show the same behavior.

One important aspect which is obtained from the micromagnetic simulation is the observation that the remanent state of all spiral patterns is characterized by an onion-like magnetization configuration. The spirals are divided by a horizontal axis parallel to the applied field into an upper and lower part. In each part the magnetization follows the curvature of the spiral forming poles at the horizontal axis. Additionally, micromagnetic simulations of spiral structures with a diameter one order of magnitude smaller than for the ones considered so far still show a preference for the onion state. This behavior is different from closed ring structures, where a vortex state forms spontaneously during the magnetization reversal (Rothman et al. 2001, Castaño et al. 2003, Kläui et al. 2003). In order to generate a magnetic vortex in a spiral structure (geometric vortex), a staggered magnetic field is required that changes orientation after each half turn.

In general the inner parts of the spiral are more stable and switch later than the outer ones. In pattern S2 where the end pieces of two spirals face each other through a small gap, dipolar stray fields stabilize the magnetic configuration and the outer parts switch later than the inner parts. In contrast, joining two spirals by a magnetic bridge in pattern S3 results in a decrease of the coercive field, as this bridge allows domain walls to propagate across. Thus, the boundary condition for the outer pieces of the spiral controls the coercivity. Vice versa, using the same spiral parameters but arranging them in different ways the coercivity can be tailored. In fact the spiral structures have some similarity to the exchange spring heterostructures consisting of magnetically hard and soft materials, one providing the anisotropy and the other the magnetic moment (Fullerton et al. 1999). In comparison, the core of the spiral represents the hard part, whereas the outer tail of the spiral is either soft or can be hardened by interaction.

4.3.7 Magnetostatic Interactions

A key issue in fundamental physics and data storage technology is to understand the remagnetization behavior of submicron-sized magnetic elements and to functionalize their mutual interactions. Recently, the possibility to build logic devices such as AND and NOR gatters on the basis of elongated, dipolar-coupled permalloy (Py) has been demonstrated (Imre et al. 2006). Due to the demagnetizing field of elongated magnetic islands the remanent magnetic state and the reversal mechanism become sensitive to the shape of the elements. In well-ordered artificially structured nanomagnetic dipoles, the interactions arising from the stray field lead to highly correlated systems. In particular, geometric frustration leads to the spin ice state, in which the individual dipoles mimic the frustration of hydrogen ions in frozen water. In the ice structure, two hydrogen atoms are close to the oxygen atoms and two further away. This rule is usually quoted as the "two in–two out" ice rule. Figuratively speaking, the magnetic dipoles on the square lattice obey the spin ice rule, if two spins or magnetic dipoles point into a vertex and two point out. To realize this state, a two-dimensional square lattice of 25 nm thick Py islands (80 nm × 220 nm) was carefully demagnetized and visualized by means of MFM (Wang et al. 2006). The spin ice state is one of many possible magnetic superstructures which may appear in nanomagnetic arrays. Apart from the shape of the elements the symmetry of the superstructure depends on the relative distances between the particles. If the interparticle distance is comparable with or smaller than the length of an element, higher-order magnetostatic contributions become important (Vedmedenko et al. 2005). These contributions might induce additional anisotropy and/or select specific vertex configurations from the manifold of the spin ice symmetries. This, in turn, might influence the magnetization reversal in magnetic arrays.

The open frame system consisting of two perpendicularly crossed stripe arrays is a suitable prototype of interacting islands (Remhof et al. 2008). The open frame system is inherently frustrated. Each vertex where the two sublattices intersect has to accommodate four magnetic poles in close proximity. In the most unfavorable case, four equal magnetic poles meet in a vertex, i.e., the four magnetic moments point all inward or all outward. Energetically more favorable is a configuration in which two moments point inward and two point outward. A situation in which each magnetic pole is surrounded only by opposite poles is impossible. Analogous to the steric frustration of hydrogen ions in frozen water, the geometric frustration of spins in a magnetic material has been denoted as spin ice. The spin ice state is a demagnetized state. It is characterized by a lack of long-range order and by the so-called ice rules which require a minimization of the spin–spin interaction energy when two spins point inward and two spins point outward on each vertex. Model calculations based on the magnetostatic interactions including multipolar contributions clearly show that the spin ice state is indeed the demagnetized ground state of the system. At remanence, however, the samples exhibit a persistent net magnetization, indicative of the existence of a metastable, ordered state. The possible symmetric remanent states are shown schematically in Figure 4.14. The onion state, in which each of the two sublattices is parallel-aligned, has the highest symmetry and the highest magnetization. The resulting net magnetization of the whole array is tilted 45° against the long axes of the individual islands. At each vertex, the magnetization of two adjacent elements from different sublattices point inward, while the two others point outward. In the so-called horseshoe state only one of the two sublattices is parallel-aligned, while the other is antiparallel-ordered. Only the parallel-aligned sublattice contributes to the net magnetization, which consequently aligns with the anisotropy axis of the respective islands. There are two possible configurations in the horseshoe state. In the first one, in the following referred to as horseshoe 1, at each vertex the magnetization of two adjacent elements from different sublattices points inward, while the two others point outward. In the second one, in the following denoted as horseshoe 2, at each vertex the magnetization of three elements points inward (or outward), while only one points outward (inward). Experimentally, mainly the horseshoe 2 state is observed.

The micro-vortex state (Vedmedenko 2007) exhibits no net magnetic moment. In order to realize the micro-vortex state, the chirality of two adjacent vortices has to be antiparallel. Also in this state, the magnetization of two elements point inward and two outward. However, opposite to the aforementioned states, this time the magnetization of the two next nearest elements, i.e., from the same sublattice, points inward, while the two perpendicular elements from the other sublattice point outward, or vice versa. Consequently, the distance between two equal poles is larger than in the onion or the horseshoe state and the distance between two opposite poles is smaller. Thus, this configuration is energetically more favorable than the two arrangements discussed before. The micro-vortex state can be seen as an "ordered" spin ice state. It fulfills the condition of demagnetization and the ice rules.



FIGURE 4.14 Schematic representation of the possible symmetrical (meta-) stable remanent states. On the right a representative square formed of four individual islands is depicted, on the left the long-range order of the respective structure is shown. The circles within the extended structure indicate the vertices.

The onion state can easily be realized experimentally. Applying an external field along the diagonal axis, i.e., under an angle of 45° with respect to the individual stripes, naturally leads to the onion state in remanence. In this case, the external field exhibits a strong component along the easy axis of each Py element, resulting in two magnetic poles in the opposite corners of the frames. For an applied magnetic field pointing along the horizontal stripes (0°), the situation is different. In this case the horizontal stripes are magnetized along the easy axis, while the vertical stripes are magnetized along their hard axis. In remanence, the shape anisotropy of the elongated islands supports the magnetization along the islands. While it is energetically favorable for the magnetization of the horizontal stripes to stay in the field direction, there is no preference for the vertical ones. If the effect of the stray field of the neighboring islands is negligible (i.e., at sufficiently large distances), 50% of the stripes are magnetically oriented north–south, while the other 50% are oriented south–north. For large distances (2 μm), this leads to the coexistence of the onion state together with the horseshoe 2 state (see Figure 4.15 right). For small distances (0.5 μm), the situation is different. Here, both sublattices are magnetically aligned parallel. Obviously, at small distances the stray field stabilizes the onion state irrespective of the direction of the field. At zero distance, i.e., in closed square rings, the onion state has also been observed in remanence. In this case the sample had to be carefully demagnetized to reach the vortex state.

The variation of distances between elongated Py elements without any variation of the particle shape changes the remanent configuration of the whole array. This means that with increasing interparticle distance the relative depth of energy minima corresponding to different configurations changes. For a deeper understanding of the observed phenomena, theoretical calculations are necessary. In the geometrically frustrated crossed bar configuration small distances lead to a quenching of the impressed fourfold anisotropy by the formation of the highly symmetric, long-range ordered onion state. At larger distances one of the sublattice starts to randomize and the onion state coexists with the horseshoe 2 state. The experimental results can be understood on the basis of the magnetostatic energy of the whole system, including higher-order terms. The one-dimensional energy curve displays three minima that can be identified as the micro-vortex state, the onion state, and the



FIGURE 4.15 MFM images of Py dipole arrays on a square lattice, recorded in the remanent state ($H = 0$). The individual elements have separations of 0.42, 0.84, and 2.34 μm (from left to right). The field direction is indicated by the white arrow. In the panel to the right vertices displaying an onion state are highlighted with a black circle, vertices with a horseshoe state are highlighted with a white circle. (Reprinted from Remhof, A. et al., *Phys. Rev. B*, 77, 134409, 2008. With permission.)

horseshoe 2 state. Thereby, the formation of the micro-vortex state as the ground state is separated from the observed onion state by a substantial energy barrier.

Indeed, one of the initially longitudinally magnetized elements have to be completely reversed. Depending on the mechanism (coherent or incoherent magnetization rotation) the magnetization reversal requires an additional energy comparable with that of the magnetostatic coupling. The reversed element should be antiparallel to the applied magnetic field. This makes the magnetization reversal even more energetically expensive. The probability for climbing an energy barrier in the presence of available local minima is close to zero. Thus, it follows from the calculations that for initial 0° saturation of a Py array in the case of small separations, the most probable state is the onion magnetization configuration. However, for large interparticle distances a relevant number (≈30%) of horseshoe 2 states should appear. In remanence the energetically most favorable vortex state is inaccessible because of the large energy barrier of the magnetization reversal. A similar analysis has been performed for initially 45° saturated arrays. The main difference to the previous discussion is that the total energy of the 45° state is lower than that of the 0° configuration. Therefore, the energy minimum for the horseshoe 2 ordering disappears already for the more widely spaced arrays with dominating dipolar interactions. Hence, if an array has been initially magnetized under 45° to its axes the onion state should prevail in wider- as well as in denser-packed arrays. Energetically preferred micro-vortex configuration can be obtained only after a thorough demagnetization of an array. A detailed discussion of the theoretical calculations is given in Vedmedenko and Mikuszeit (2008).

Recently, magnetostatic interactions have also been studied in other frustrated systems. Especially the kagome lattice, a two-dimensional structure composed of corner-sharing triangles and the related honeycomb structure, gained considerable attraction. The kagome lattice and the honeycomb structure intrinsically exhibit a sixfold symmetry; both patterns are schematically represented in Figure 4.16. In the interconnected honeycomb net, three lines meet in each vertex. The ice rules change consequently from two-in–two-out to two-in–one-out or to one-in–two-out. In the magnetic ground state, prepared by careful demagnetization, Qi et al. observed that the magnetization along each connecting element of adopts a single domain, and that the domain walls are constrained within the vertices. Thereby, the ice rules are strictly obeyed. Compared to the square lattices discussed above, where the realization of the artificial spin ice is hindered by large energy barriers, the magnetic honeycomb structure turned out to be an ideal artificial spin ice system (Qi et al. 2008).



FIGURE 4.16 Schematic representation of the honeycomb structure (left) and of a periodic array of islands, placed between the vertices of a kagome lattice (right).

Rectangular islands, placed between the vertices of a kagome lattice, lead to a periodic structure in which the number of nearest neighbors of a lattice point is four as on a square lattice. However, the angles between the connecting lines to the nearest neighbors on the triangular lattice are 60° instead of 90°. Varying the size of the rectangular bars and the interparticle distance the effect of stray field interaction on the magnetization reversal was investigated by (Westphalen et al. 2008b). The islands on the kagome pattern can be subdivided into three sublattices with triangular symmetry. The magnetization reversal depends on the direction of the applied field. Two simple geometric cases may be distinguished: The field may be applied either parallel to one of the sublattices 0° orientation or perpendicular to one sublattice 30° orientation. For the 0° orientation, two reversal processes were observed. In case that the interaction between the net magnetic moments is weak, the particles inclined to the field direction by 60° flip first, followed by the sublattice parallel to the applied field. For stronger interaction at reduced particle distance, the parallel sublattice switches first, followed by the domain process in the inclined bars. Applying a magnetic field in the 30° orientation leads to a strong frustration of the particles with the hard axis orientation. This frustration causes domain formation preferentially in the perpendicular bars.

4.4 Summary and Discussion

The technological progress in the field of magnetoelectronics and the advancement in miniaturization techniques brought topological-ordered nano- and microstructured magnetic thin films in the focus of many research activities (Martín et al. 2003).

Understanding, modeling, and controlling the magnetization reversal of magnetic micro- and nanostructures as a function of shape, aspect ratio, and interparticle separation are of high current interest. Various shapes have been investigated in the past, including stripes, closed and open squares, and circular and elliptic dots.

Even though there exists a large variety of shapes, sizes, and materials, leading to a huge variety of properties, ferromagnetic islands have a few characteristics in common:

- In small ferromagnetic islands, the shape anisotropy dominates the remanent state and the reversal mechanism. Therefore, the geometrical extensions of magnetic structures determine their magnetic properties. Elongated structures tend to form magnetic dipoles, while small aspect ratios favor closed flux states.
- By lateral structuring of originally homogeneous, magnetically isotropic ferromagnetic thin films new anisotropy axes can be impressed in arbitrary directions.
- Micrometer and nanometer-sized ferromagnetic islands exhibit much larger coercive fields than bulk magnets composed of the same material.
- The magnetization reversal is dominated by coherent rotation in hard axis orientation and by domain wall motion in easy axis orientation.
- At small distances, magnetostatic interactions occur, leading to the collective behavior of an array of islands.

In future, the technological advancements of sample preparation will lead to even smaller individual structures and to larger arrays. Three major routes are currently followed. The first one tries to optimize the lithographic techniques by using electromagnetic radiation with smaller wavelength (Bakshi 2008) or by nanoimprint technologies (Chou et al. 1996). The second route involves self-assembly of clusters and surfaces to complex, periodic structures (Boncheva et al. 2005). The third route is the bottom-up technique. In this approach, the ferromagnetic island is built from its atoms. A tip from a scanning tunneling microscope can be used to move individual atoms on a surface, thereby reaching island sizes that will never be accessible with classical lithography (Stroscio and Eigler 1991). Further miniaturization will not only allow to study smaller objects, and bridge the gap between individual atoms, clusters and nano- to micrometer-sized islands, it also leads to a higher definition of the circumference of the island, reducing the often undesired influence of rough edges.

The research on ferromagnetic islands is nowadays embedded in the field of spintronics (Wolf et al. 2001). In the classical electronics the information is carried by the charge of the electrons, while its spin is ignored. In the future, the standard microelectronics will be combined with spin-dependent effects that arise from the interaction between spin of the carrier and the magnetic properties of the material. Therefore, the magnetic properties of ferromagnetic (FM) islands will be joined to other materials such as antiferromagnets (AF), semiconductors (SC), and superconductors (S). For extended films, the mutual interaction within F/AF and F/S heterostructures leading to the exchange bias effect and the superconducting proximity effect have been studied in great detail in the past (Zabel and Bader 2008). Patterning the ferromagnetic layer allows to control its coercivity and its anisotropy. It also allows to tune the size of the islands to the typical length scales of the AF, i.e., its domain size, and to the S, i.e., its coherence length. The exchange bias, for example, stabilizes the magnetization of ferromagnetic islands close to the superparamagnetic limit, fueling the hope of higher storage densities in magnetic recording devices (Skumryev et al. 1991). Ferromagnetic islands play an important role for the preparation of spin-polarized electric currents as the electrical conductivity of the majority spin electrons differs substantially from minority spin, resulting in a spin-polarized electric current. The spin-polarized current may then be transferred into a SC device ballistically via an ohmic contact. However, F/SC contacts involve doping of the semiconductor surface, leading to spin-flip scattering and loss of the spin polarization. Understanding and optimizing spin injection and spin transport are some of the key challenges for the development of truly spintronic devices.

Another degree of freedom are vertical structures, in which the islands are stacked on top of each other, separated by nonmagnetic material. In such a way, one-dimensional spin chains may be realized, in which the islands interact via their magnetostatic fields (Fraerman et al. 2008). It has already been shown, that interacting islands may be used as logic devices (Wang et al. 2006). Research in this area is still at a very early stage and far away from a technical application; the perspective, however, to functionalize the magnetostatic interactions will have stimulating effects on the research worldwide.

References

Adeyeye, A. O. and Singh, N. 2008. Large area patterned magnetic nanostructures. *J. Phys. D: Appl. Phys.* 41: 153001.

Aharoni, A. 2000. *Introduction to the Theory of Ferromagnetism*. Oxford, U.K.: Oxford Science Publications.

Allwood, D. A., Xiong, G., Cooke, M. D. et al. 2002. Submicrometer ferromagnetic NOT gate and shift register. *Science* 296: 2003–2006.

Allwood, D. A., Xiong, G., Cooke, M. D., and Cowburn, R. P. 2003. Magneto-optical Kerr effect analysis of magnetic nanostructures. *J. Phys. D: Appl. Phys.* 36(18): 2175–2182.

Bakshi, V. 2008. *EUV Lithography*, Bellingham, WA: SPIE Publications.

Bauer, E. 1994. Low energy electron microscopy. *Rep. Prog. Phys.* 57: 895–938.

Bloch, F. 1932. Zur Theorie des Austauschproblems und der Remanenzerscheinung der Ferromagnetika. *Z. Phys.* 74 (5–6): 295–335.

Boncheva, M., Andreev, S. A., Mahadevan, L. et al. 2005. Magnetic self-assembly of three-dimensional surfaces from planar sheets. *Proc. Natl. Acad. Sci. USA* 102(11): 3924–3929.

Brown, W. F. 1963. *Micromagnetics*. New York: John Wiley & Sons.

Bucknall, D. G. 2005. *Nanolithography and Patterning Techniques in Microelectronics*. Cambridge, U.K.: Woodhead Publishing in Materials.

Castaño, F. J., Ross, C. A., Frandsen, C. et al. 2003. Metastable states in magnetic nanorings. *Phys. Rev. B* 67(18): 184425.

Chapman, J. N., Johnston, A. B., and Heyderman, L. J. 1994. Coherent Foucault imaging: A method for imaging magnetic domain structures in thin Films. *J. Appl. Phys.* 76(9): 5349–5355.

Chou, S. Y., Krauss, P. R., and Renstrom, P. J. 1996. Imprint lithography with 25-nanometer resolution. *Science* 272: 85–87.

Cowburn, R. P., Koltsov, D. K., Adeyeye, A. O. et al. 1999. Single-domain circular nanomagnets. *Phys. Rev. Lett.* 83(5): 1042–1045.

Dennis, C. L., Borges, R. P., Buda, L. D. et al. 2002. The defining length scales of mesomagnetism: A review. *J. Phys. Condens. Matter* 14: R1175–R1262.

Donahue, M. J. and Porter, D. G. 1999. *OOMMF User's Guide, Version 1.0, Interagency Report NISTIR 6376*. Gaithersburg, MD: National Institute of Standards and Technology.

Feldtkeller, E. and Stein, K. U. 1967. Verbesserte Kerr-Technik zur Beobachtung magnetischer Domänen. *Z. Angew. Phys.* 23: 100–102.

Fischer, P., Eimüller, T., Schütz, G. et al. 1999. Magnetic domain imaging with a transmission X-ray microscope. *J. Magn. Magn. Mater.* 198–199: 624–627.

Foner, S. 1959. Versatile and sensitive vibrating-sample magnetometer. *Rev. Sci. Instrum.* 30(7): 548–557.

Fraerman, A. A., Gusev, S. A., Mazo, L. A. et al. 2002. Rectangular lattices of permalloy nanoparticles: Interplay of single-particle magnetization distribution and interparticle interaction. *Phys. Rev. B* 65(6): 064424.

Fraerman, A. A., Gribkov, B. A., Gusev, S. A. et al. 2008. Magnetic force microscopy of helical states in multilayer nanomagnets. *J. Appl. Phys.* 103(7): 073916.

Fullerton, E. E., Jiang, J. S., and Bader, S. D. 1999. Hard/soft magnetic heterostructures: Model exchange-spring magnets. *J. Magn. Magn. Mater.* 200(1–3): 392–404.

Grimsditch, M. and Vavassori, P. 2004. The diffracted magneto-optic Kerr effect: What does it tell you? *J. Phys. Condens. Matter* 16(9): R275–R294.

Grimsditch, M., Vavassori, P., Novosad, V. et al. 2002. Vortex chirality in an array of ferromagnetic dots. *Phys. Rev. B* 65(17): 172419.

Hausmanns, B., Krome, T. P., Dumpich, G. et al. 2002. Magnetization reversal process in thin Co nanowires. *J. Magn. Magn. Mater.* 240(1–3): 297–300.

Heisenberg, W. 1928. Zur Theorie des Ferromagnetismus. *Z. Physik* 49: 619–636.

Hertel, R., Fruchart, O., Cherifi, S. et al. 2005. Three-dimensional magnetic-flux-closure patterns in mesoscopic Fe islands. *Phys. Rev. B* 72: 214409.

Hopster, H and Oepen, H. P. 2005. *Magnetic Microscopy of Nanostructures*. Berlin Heidelberg: Springer Verlag.

Hubert, A. and Schäfer, R. 1998. *Magnetic Domains, The Analysis of Magnetic Microstructures*. Heidelberg, Germany: Springer Verlag.

Imre, A., Csaba, G., Ji, L. et al. 2006. Majority logic gate for magnetic quantum-dot cellular automata. *Science* 311(5758): 205–208.

Kerr, J. 1877. On the rotation of the plane of polarisation by reflection from the pole of a magnet. *Philos. Mag.* 3: 321–343.

Kläui, M., Rothman, J., Lopez-Diaz, L. et al. 2001. Vortex circulation control in mesoscopic ring magnets. *Appl. Phys. Lett.* 78(21): 3268–3270.

Kläui, M., Vaz, C. A. F., Bland, J. A. C. et al. 2003. Direct observation of spin configurations and classification of switching processes in mesoscopic ferromagnetic rings. *Phys. Rev. B* 68(13): 134426.

Landau, L. and Lifschitz, L. 1935. On the theory of dispersion of magnetic permeability in ferromagnetic bodies. *Physik. Z. Sowjetunion* 8: 153–169.

Last, T., Hacia, S., Wahle, M. et al. 2004. Optimization of nanopatterned permalloy electrodes for a lateral hybrid spin-valve structure. *J. Appl. Phys.* 96(11): 6706–6711.

Lee, M.-S., Westphalen, A., Remhof, A. et al. 2008. Extended longitudinal vector and Bragg magneto-optic Kerr effect for the determination of the chirality distribution in magnetic vortices. *J. Appl. Phys.* 103(9): 093913.

Martin, Y. and Wickramasinghe, H. K. 1987. Magnetic imaging by "force microscopy" with 1000 Å resolution. *Appl. Phys. Lett.* 50(20): 1455–1457.

Martín, J. I., Nogués, J., Liu, K. et al. 2003. Ordered magnetic nanostructures: Fabrication and properties. *J. Magn. Magn. Mater.* 256: 449–501.

Mundschau, M., Romanowicz, J., Wang, J. Y. et al. 1996. Imaging of ferromagnetic domains using photoelectrons: Photoelectron emission microscopy of neodymium-iron-boron ($Nd_2Fe_{14}B$). *J. Vac. Sci. Technol. B* 14(4): 3126–3130.

Oepen, H. and Kirschner, J. 1991. Imaging of magnetic microstructures at surfaces—The scanning electron microscope with spin polarization analysis. *Scanning Microsc.* 5(1): 1–16.

Parkin, S. S. P., Hayashi, M., and Thomas, L. 2008. Magnetic domain-wall racetrack memory. *Science* 320(5873): 190–194.

Philo, J. S. and Fairbank, W. M. 1977. High-sensitivity magnetic susceptometer employing superconducting technology *Rev. Sci. Instrum.* 48: 1529–1536.

Prohl, A. 2001. *Computational Micromagnetism*. Stuttgart, Germany: B. G. Teubner.

Qi, Y., Brintlinger, T., and Cumings, J. 2008. Direct observation of the ice rule in an artificial kagome spin ice. *Phys. Rev. B* 77: 094418.

Raabe, J., Pulwey, R., Sattler, R. et al. 2000. Magnetization pattern of ferromagnetic nanodisks. *J. Appl. Phys*. 88(7): 4437–4439.

Rahm, M., Biberger, J., Umansky, V. et al. 2003. Vortex pinning at individual defects in magnetic nanodisks. *J. Appl. Phys*. 93(10): 7429–7431.

Remhof, A., Westphalen, A., Theis-Bröhl, K. et al. 2007. Magnetization reversal studies of periodic magnetic arrays via scattering methods. In *Springer Series in Materials Science: Magnetic Nanostructures*, B. Aktas, L. Tagirov, and F. Mikailov (eds.), pp. 65–96. Heidelberg, Germany: Springer Verlag.

Remhof, A., Schumann, A., Westphalen, A. et al. 2008. Magnetostatic interactions on a square lattice. *Phys. Rev. B* 77: 134409.

Rothman, J., Kläui, M., Lopez-Diaz, L. et al. 2001. Observation of a Bi-domain state and nucleation free switching in mesoscopic ring magnets. *Phys. Rev. Lett*. 86(6): 1098–1101.

Schneider, M., Hoffmann, H., and Zweck, J. 2000. Lorentz microscopy of circular ferromagnetic permalloy nanodisks. *Appl. Phys. Lett*. 77(18): 2909–2911.

Shinjo, T., Okuno, T., Hassdorf, R. et al. 2000. Magnetic vortex core observation in circular dots of permalloy. *Science* 289(5481): 930–932.

Skumryev, V., Stoyanov, S., Zhang, Y. et al. 1991. Beating the superparamagnetic limit with exchange bias. *Nature (London)* 423: 850–853.

Stroscio, J. A. and Eigler, D. M. 1991. Atomic and molecular manipulation with the scanning tunneling microscope. *Science* 254(5036): 1319–1326.

Suzuki, K. and Smith, B. W. 2005. *Microlithography: Science and Technology*. Boca Raton, FL: CRC Press.

Tsoi, M., Fontana, R. E., and Parkin, S. S. P. 2003. Magnetic domain wall motion triggered by an electric current. *Appl. Phys. Lett*. 83(13): 2617–2619.

van den Berg, H. A. M. 1986. Self-consistent domain theory in soft-ferromagnetic media. II. Basic domain structures in thin-film objects. *J. Appl. Phys*. 60: 1104–1113.

Vavassori, P. 2000. Polarization modulation technique for magneto-optical quantitative vector magnetometry. *Appl. Phys. Lett*. 77(11): 1605–1607.

Vavassori, P., Grimsditch, M., Novosad, V., Metlushko, V., and Ilic, B. 2003. Metastable states during magnetization reversal in square permalloy rings. *Phys. Rev. B* 67(13): 134429.

Vaz, C. A. F., Hayward, T. J., Llandro, J. et al. 2007. Ferromagnetic nanorings. *J. Phys. Condens. Matter* 19(14): 255207.

Vedmedenko, E. Y. 2007. *Competing Interactions and Pattern Formation in Nanoworld*. Weinheim, Germany: Wiley-VHC.

Vedmedenko, E. Y. and Mikuszeit, N. 2008. Multipolar ordering in electro- and magnetostatic coupled nanosystems. *Chem. Phys. Chem*. 9(9): 1222–1240.

Vedmedenko, E. Y., Mikuszeit, N., Oepen, H. P., and Wiesendanger, R. 2005. Multipolar ordering and magnetization reversal in two-dimensional nanomagnet arrays. *Phys. Rev. Lett*. 95: 207202.

Wang, R. F., Nisoli, C., Freitas, R. S. et al. 2006. Artificial spin ice in a geometrically frustrated lattice of nanoscale ferromagnetic islands. *Nature (London)* 439: 303–306.

Waser, R. 2003. *Nanoelectronics and Information Technology*. Weinheim, Germany: Wiley-VCH.

Westphalen, A., Lee, M.-S., Remhof, A., and Zabel, H. 2007. Vector and Bragg magneto-optical Kerr effect for the analysis of nanostructured magnetic arrays. *Rev. Sci. Instrum*. 78(12): 121301.

Westphalen, A., Remhof, A., and Zabel, H. 2008a. Magnetization reversal in nanowires with a spiral shape. *J. Appl. Phys*. 104(1): 013906.

Westphalen, A., Schumann, A., Remhof, A., Zabel, H., Last, T., and Kunze, U. 2006. Magnetization reversal of equilateral Fe triangles. *Phys. Rev. B* 74(10): 104417.

Westphalen, A., Schumann, A., Remhof, A. et al. 2008b. Magnetization reversal of microstructured kagome lattices. *Phys. Rev. B* 77: 174407.

Wolf, S. A., Awschalom, D. D., Buhrman, R. A. et al. 2001. Spintronics: A spin-based electronics vision for the future. *Science* 294(5546): 1488–1495.

Zabel, H. and Bader, S. D. 2008. *Magnetic Heterostructures, Advances and perspectives in Spinstructures and Spintransport*. Heidelberg, Germany: Springer Verlag.

5

A Single Nano-Dot Embedded in a Plate Capacitor

5.1 Introduction 5-1
5.2 Studied Configuration: Geometry and Notations 5-3
5.3 Metallic Dot 5-3
Definitions of Capacitance and Coupling Coefficient • Influence of the Charge • Influence of Polarization • Numerical Implementation • Numerical Results and Comparison with a Classical Approximation • Conclusion
5.4 Semiconductor Dot: Theoretical Approach 5-9
General Considerations on Quantization Effects • Quantum Dot Containing a Single Electron: A Simplified Approach • Addition of a Second Electron in the Dot • Multiple Electrons in the Dot
5.5 Finite Element Modeling of a Silicon Quantum Dot 5-14
Studied Structure and Meshing Strategy • Numerical Results • Comparison with the Metallic Approximation
5.6 Conclusion 5-18
Appendix A: A Numerical Validation of the Semi-Analytical Approach 5-19
Convergence • Numerical Validation with FEM Approach
References 5-21

Gilles Micolau
Universités d'Aix Marseille

Damien Deleruyelle
Universités d'Aix Marseille

5.1 Introduction

Nowadays, nonvolatile memories (NVM) are used on a massive scale in different domains related to personal and industrial applications such as cellular phones, massive computer data storage on mobile support, digital photography, aeronautics, and embedded electronic in automotive applications.

The current NVM technology is based on electric charge storage in silicon-based devices. The scaling of these devices has been predicted by Gordon Moore. In his famous paper published in 1965, he mentions: "…The complexity for minimum component costs as increased at a rate of roughly a factor two per year […] Over the longer term […] there is no reason to believe it [the rate] will not remain nearly constant for at least 10 years" [1].

As a matter of fact, even after 40 years, this prediction is still valid [2]. However, the typical size of memory cells has been so much reduced that a further miniaturization becomes critical (recently, NVM cells have been proposed with 43 nm typical size [technology node]) [3]. Indeed, new phenomena such as quantum or finite size effects and single-electron effects [4–6] challenge the possibility of further reduction.

In the field of industrial and academic research, two major parallel axes are proposed to solve these issues. The first one is based on the use of new materials using singular physical properties (phase changed memory [7], resistive random access memory [8], etc.). These promising approaches are not yet completely mature to replace the well-known traditional devices, studied for at least a half century. The other approach consists in modifying, step by step, the current devices in order to push the scaling limits of silicon-based devices. This chapter is devoted to this second approach.

The essential element of the current NVM is the metal oxide semiconductor transistor (TMOS), which can be seen as a nonlinear valve of electronic current controlled by an external voltage. To simplify, the schematic behavior of the MOS transistor is presented in Figure 5.1. It can be described as follows: the current flowing between the two polarized pads—source and drain—is null when the voltage applied on the control gate is lower than a threshold voltage (V_{T0}). It becomes arbitrarily high when the voltage is equal or greater than V_{T0}. The value of V_{T0} is an intrinsic quantity of the TMOS. The main idea of the NVM is to modulate the value of V_{T0} by storing electric charges, spatially confined in a floating gate located between the control gate and the channel of electronic transport. Injecting negative (resp. positive) charges in the floating gate shifts the value of the threshold voltage to values greater (resp. lower) than V_{T0} as shown in Figure 5.2. Consequently, two different electrical states are possible: the "up" one defined by $V_{Tu} > V_{T0}$ and the "down"



FIGURE 5.1 Schematic behavior of a MOS transistor.



FIGURE 5.2 Schematic behavior of a TMOS with a floating gate.



FIGURE 5.3 Floating nano-dots.

one with $V_{Td} < V_{T0}$. These two states define a level of programmation for the cell. Depending on the technology, the "up" (resp. "down") state is called programmed or erased (resp. erased or programmed) and the cell can store one fundamental memory unit, the well-known *bit*.

Classically, the floating gate is designed with degenerated polysilicon whose electrical behavior is quasi-metallic. It is electrically insulated by oxide layers (silicon oxide for the bottom and a stack of different oxides on its top) designed to maintain the electric charges as long as possible in the floating gate. One major issue in scaling is the reduction of the thickness of the oxides leading to an alteration of the retention ability of the device. Another critical issue is the size reduction of the floating gate. To work properly, the memory cell needs a certain quantity of electric charges—injected in its floating gate. Scaling the floating gate and the surrounding oxides implies using less charges for the programmation of the cell. The repartition of less charges in the volume of a small floating gate makes the discrimination between the two possible states of the cell more difficult (the classical term is "closure of the programming window"). Moreover, another issue is linked to the apparition of traps in the bottom oxide when cycling the memory device. This phenomenon is known as *stress-induced leakage current* (SILC) [9,10]. Because the charges are delocalized in the floating gate, the presence of the unique trap in the bottom dielectric can discharge the entire memory device and lead to the data loss. To tackle these issues, one solution could be to constrain charges in the vicinity of the channel. For accomplishing this goal, the use of nanoscale dots instead of a continuous floating gate has been experimentally and theoretically studied for many years [11–14]. The principle of the configuration is shown in Figure 5.3.

For modeling the electrical characteristics of these devices, such as programming (erasing) or retention, knowledge of the electrostatics and, more generally, the physics of this type of devices is needed. The physical properties of such nanoobjects have been studied for many years, with the help of different innovative techniques such as scanning tunneling microscopy (STM), atomic force microscopy (AFM), transmission electron microscopy (TEM), and so on. A detailed review about nanoclusters can be found in Ref. [15].

The modeling of dynamics phenomenon such as tunneling currents needs an accurate modeling of the electric field in the device. For metallic or quasi-metallic dots, a classical (non-quantum) approach based on equivalent capacitance is efficient and has been even used in the case of large semiconductor islands [16–19]. Theoretically, for small semiconductor dots, solving the electrostatics of the configuration must be achieved by a self-consistent resolution of Poisson and Schrödinger equations as shown in Refs. [20–22]. However, this huge complete resolution can be avoided. First of all, the number of dots involved in the problem has a crucial influence. The electrostatics of a device with numerous dots can be governed by the classical interaction between each dot, even if the typical size of the dot is lower than the typical quantum range. Second, the current typical size of dots does not necessarily imply that the quantum approach is justified. So, many models assume that the dots are metallic and interact as plane capacitors. The validity of this approach has been proved in Ref. [23]. However, it was shown in Ref. [24], in a 2D case and for a single dot arbitrarily shaped, that this approach is no longer valid in the range of aspect ratios encountered in nanodot arrays. To enclose this state of art, in the context of ultrascaled devices, the individual electrical behavior of a dot can become significant in front of the collective behavior of a matrix of dots [6,25].

We aim to model, academically and as precisely as possible, the electric behavior of a single dot embedded in a dielectric oxide. So, we choose a very canonical and academic physical configuration, particularly with the twin aims of

- Determining the critical size of the dot leading to quantum effects
- Comparing the classical approximations with models giving more physical insights

In this chapter, we focused on a single spherical island, electrically charged, embedded in a plane capacitor. In the first part, we propose a rigorous—by this word, we mean that there are no physical approximations—non-quantum model for the electrostatics of a metallic dot and give a semi-analytical expression for its capacitance. In the second part, we propose a quantum approach for a dielectric dot, based on solving the Poisson and Schrödinger equations, with a discrete number of charges in the dot. Finally, results obtained from both approaches are quantitatively confronted to determine in which extent the quantum effects have to be considered.

5.2 Studied Configuration: Geometry and Notations

A spherical dot, of radius a, is embedded in a dielectric medium of relative dielectric permittivity ε_r, located between two infinite conductor planes geometrically supported by two planes Π_1 and Π_2. Each is held at a constant electric potential (V_1 for Π_1, V_2 for Π_2). The spherical dot is initially charged with an electrical charge Q_0, with a process not studied here. We assume that $\Delta V = V_1 - V_2$ and Q_0 are independent. We denote by σ the surface charge density of the dot when metallic and ρ the volumic charge density when dielectric. h is the distance between the two plate electrodes. All distances and notations are defined in Figure 5.4. Any point M in the dielectric medium is characterized by its Cartesian coordinates (x, y, z) and also by the spherical ones (r, θ, ϕ). Because the physics of the configuration is invariant by any rotation along the longitudinal angle ϕ, only the two spherical coordinates $\left(r = OM,\ \theta = \widehat{(\mathbf{e}_z, \mathbf{OM})}\right)$ are required to locate M.

5.3 Metallic Dot

In this section, we assume that the dot is a perfect conductor medium. As a consequence, the potential is constant in the volume of the dot but also floating because it is electrically insulated. We solve the classic electrostatics (non-quantum approach) of the configuration by a rigorous semi-analytical expansion of the potential. By rigorous, we mean that there are no physical approximations in our model. There are only numerical truncations and numerical approximations arising from the implementation. The model is based on the work exposed in Ref. [26] where the author rigorously solves the electrostatics of this problem, with the help of the method of images and the Legendre polynomial expansions. The author gives the solution for the potential in the medium (and discuss its mathematical validity) and the electrostatic force acting on the charged dot. Nevertheless, the evaluation of floating potential is not explicit at all. Starting from this model, we derive a rigorous semi-analytical expression for the capacitance and a very simple expression for the polarization coupling coefficient. The floating potential is therefore directly determined without a recurring iterative process. Then, we validate the numerical implementation and compare results with classical capacitance approximations.



FIGURE 5.4 Configuration of study.

In this section, we first define the physical parameters required for the resolution of the electrostatics. Secondly, we find a semi-analytical expression for the capacitance and the coupling coefficient. Finally, we conclude with the numerical investigations of the model.

5.3.1 Definitions of Capacitance and Coupling Coefficient

Due to the linearity of the electrostatic equations and the unicity of the Poisson equation—with given boundary conditions—the potential, at any point M in the dielectric medium, can be described as the sum of two terms. The first one, denoted by $V^{\mathrm{Q}}(M)$, is the potential created by the dot when charged (with electric charge Q_0) without polarization ($\Delta V = V_1 - V_2 = 0$). The second term, denoted by $V^{\mathrm{po}}(M)$, is the potential created by the polarization between the two electrodes ($\Delta V = V_1 - V_2$) when $Q_0 = 0$. Thus, the electric potential anywhere in the dielectric medium can be written as

$$V(M) = V^{\mathrm{Q}}(M) + V^{\mathrm{po}}(M) \tag{5.1}$$

The computation of the function $V(M)$ involves the resolution of the Poisson equation with three Dirichlet boundary conditions: the potential is constant and imposed on the electrodes (Π_1 and Π_2), is constant, and floating on the dot. The floating potential, denoted by V_{f}, can be split into two parts: v_{f}^{Q}, due to the charge, and $v_{\mathrm{f}}^{\mathrm{po}}$, due to the polarization. It can now be written as

$$V_{\mathrm{f}} - V_2 = v_{\mathrm{f}}^{Q} + v_{\mathrm{f}}^{\mathrm{po}} - V_2 \tag{5.2}$$

Determining V_{f} requires another boundary condition. The charge density over the dot, σ, is linked to the normal derivative of the floating potential (normal component of the electric field):

$$\left(\frac{\partial V}{\partial r}\right)_{r=a} = -\frac{\sigma(\theta)}{\varepsilon_0 \varepsilon_r} \quad \text{and} \quad Q_0 = \int_{\theta=0}^{\pi} \sigma(\theta) 2\pi a^2 \sin\theta \, d\theta \tag{5.3}$$

Classically the capacitance is defined as follows: "…the capacitance of a conductor is the charge of the conductor when it is maintained at unit potential, all others conductors being held at zero potential" [27,28]. We define the capacitance of the dot, C_S, as

$$C_S = \left(\frac{\partial Q_0}{\partial v_{\mathrm{f}}^{Q}}\right)_{\Delta V} = \left(\frac{\partial Q_0}{\partial V_{\mathrm{f}}}\right)_{\Delta V} = \frac{Q_0}{v_{\mathrm{f}}^{Q}} \tag{5.4}$$

The floating potential linearly depends on the total difference of potential ΔV. We define the polarization coupling coefficient α as

$$\alpha = \left(\frac{\partial v_{\mathrm{f}}^{\mathrm{po}}}{\partial \Delta V}\right)_{Q_0} = \left(\frac{\partial V_{\mathrm{f}}}{\partial \Delta V}\right)_{Q_0} = \frac{\Delta V}{v_{\mathrm{f}}^{\mathrm{po}}} \tag{5.5}$$

We thus obtain the classical equation for the floating potential

$$V_{\mathrm{f}} - V_2 = \frac{Q_0}{C_S} + \alpha \Delta V \tag{5.6}$$

This equation still remains valid for any shape of the dot. Nevertheless, a rigorous semi-analytical expression of C_S can just be extracted for the canonical spherical shape. In other cases, computations can be carried out with the help of rigorous models that need numerical methods of discretization of the shape (method of moments, boundaries models, variational computations [24,29]) or by approximated analytical expansions (Rayleigh hypothesis on boundary conditions for instance [30]).

Let us denote by Q_1 (resp. Q_2) the charge supported by the top (resp. bottom) half-part of the dot. We write these quantities with an unique notation $Q_{(1,2)}$. Introducing here the angles $\theta_1 = 0$ (resp. $\theta_2 = \pi/2$), denoted by the unique notation $\theta_{(1,2)}$, we express the partial charges, as we did with Q_0, integrating σ on the top (resp. bottom) part of the dot:

$$Q_{(1,2)} = 2\pi a^2 \int_{\theta_{(1,2)}}^{\theta_{(1,2)}+\pi/2} \sigma(\theta) \sin\theta \, \mathrm{d}\theta \tag{5.7}$$

Deriving the relation (5.7) along v_{f}^Q defines the partial capacitances C_1 and C_2, formalized with the following unique notation $C_{(1,2)}$:

$$C_{(1,2)} = \left(\frac{\partial Q_{(1,2)}}{\partial v_{\mathrm{f}}^Q}\right)_{\Delta V} \tag{5.8}$$

The Chasles relation on the integral over θ leads obviously to the equality $C_1 + C_2 = C_S$.

We can define the ratio $\kappa_{(1,2)}$ between the partial capacitances and the total one:

$$\kappa_{(1,2)} = \frac{C_{(1,2)}}{C_S} = \left(\frac{\partial Q_{(1,2)}}{\partial Q_0}\right)_{\Delta V} \quad \text{and so} \quad \kappa_1 = 1 - \kappa_2 \tag{5.9}$$

As ΔV and Q_0 are independent, the coefficients $\kappa_{(1,2)}$ and α are not equal. Mathematically this property arises from the fact that the partial derivatives do not involve the same constant physical parameters (Q_0 for α and ΔV for κ_2).

The two following sections are dedicated respectively to the semi-analytical expansions of C_S and α.

5.3.2 Influence of the Charge

In this section, we assume that there is no polarization between the electrodes ($V_1 - V_2 = 0$). We focus on the term V^{Q} in the relation (5.1). The boundary conditions for the potential are such as

(Qa) The potential is constant on the dot. This floating potential is denoted by $v_{\mathrm{f}}^Q = V^Q(r = a) = \dfrac{Q_0}{C_S}$.

(Qb) The potential is null everywhere on each plate electrode.

(Qc) The relations (5.3) are still valid.

Because the geometry simultaneously involves plane and spherical structures (electrodes and dot), it is interesting to include the plate boundary conditions in the expansion of the potential. For this, we use the classical method of images. The expansion of the potential is based on the work in Ref. [26] where the author treats the electrostatics of a charged dot rigorously in a nonpolarized plate capacitor. He uses the method of images and the Legendre polynomials expansion. The author arrives at the solution for the potential in the medium (and discuss its mathematical validity) and the electrostatic force acting on the charged dot. Nevertheless, the evaluation of the floating potential is not explicit so that the capacitance cannot be known.

5.3.2.1 Method of Images

The main idea of the method is to find a virtual distribution of charges involving the same boundaries conditions than the initial distribution [28]. Because of the unicity of the solution of the Poisson equation for given boundary conditions, the virtual distribution and the real one generate the same potential in the domain investigated. Here, we build a distribution of charges ensuring that the two planes Π_1 and Π_2 are planes of antisymmetry of the charge distribution. This is done by taking recursively the images of the sphere by the symmetries along the planes Π_1 and Π_2, as done in Refs. [26,31], and described in Figure 5.5. The z-coordinate z_p of the center O_p of the pth image is: $z_p = ph + (-1)^p z_0$, p describing the relative natural integers.



FIGURE 5.5 Coordinates of the images.

We denote by r_p the distance between the point of observation M and the center O_p, and θ_p the oriented angle between the line (O_pM) and vertical axis. To obtain a correctly oriented angle, it is necessary to alternate the sense of the axis $\mathbf{e}_z$ attached to the considerated image. We get so $\theta_p = \left(\widehat{(-1)^p\mathbf{e}_z, \mathbf{O_P M}}\right)$. These variables are shown in Figure 5.5. The classical Pythagore theorem and the definition of the geometric scalar product give the two coupled relations:

$$\begin{cases} r_p^2 = (z_0 - z_p)^2 + r^2 + 2r(z_0 - z_p)\cos\theta \\ \cos\theta_p = (-1)^p \dfrac{r\cos\theta + (z_0 - z_p)}{r_p} \end{cases} \tag{5.10}$$

To simplify the notations, we note for every point located on the surface of the dot $(r = a) : r_p^a(\theta) = (r_p)_{r=a}$ and $c_p^a(\theta) = (\cos\theta_p)_{r=a}$. Derivating the relations (5.10) along the variable r leads to

$$\begin{cases} dr_p^a(\theta) = \left(\dfrac{\partial r_p}{\partial r}\right)_{(r=a)} = \dfrac{a + (z_0 - z_p)\cos\theta}{r_p^a(\theta)} \\ dc_p^a(\theta) = \left(\dfrac{\partial \cos(\theta_p)}{\partial r}\right)_{(r=a)} = (-1)^p \left(\dfrac{\cos\theta}{r_p^a(\theta)} - \dfrac{a\cos\theta + (z_0 - z_p)}{r_p^a(\theta)^2} dr_p^a(\theta)\right) \end{cases} \tag{5.11}$$

5.3.2.2 Semi-Analytical Expression for the Capacitance

Each sphere centered in O_p generates a potential $v_p(M)$ expandable as an infinite set of Legendre polynomials [28]. Because the spheres get the same distribution of charges (or opposite), each sphere generates the same potential v_p (or opposite), vanishing far from its centre. The potential becomes [26,28]

$$v_p(M) = (-1)^p \sum_{l=0}^{+\infty} B_l \left(\frac{a}{r_p}\right)^{l+1} P_l(\cos\theta_p) \tag{5.12}$$

where P_l is the Legendre polynomial of order l and B_l are constant coefficients. The resolution of the electrostatics of the configuration is mathematically equivalent to determining B_l using boundary conditions.

The potential $V^Q(M)$, at every $M(r, \theta)$ in the dielectric medium, is the sum of the contributions of all spheres:

$$\begin{aligned} V^Q(r,\theta) = {} & \sum_{l=0}^{+\infty} B_l \left(\frac{a}{r}\right)^{l+1} P_l(\cos\theta) \\ & + \sum_{p*} (-1)^p \sum_{l=0}^{+\infty} B_l \left(\frac{a}{r_p(\theta)}\right)^{l+1} P_l(\cos\theta_p) \end{aligned} \tag{5.13}$$

where $p*$ denotes the summation over all the non-null relative integers.

The relation (5.13), combined with Equation 5.3, gives the charge of the sphere:

$$\begin{aligned} \frac{Q_0}{2\pi\varepsilon a} = {} & \sqrt{2}B_0 + a\sum_{p*} (-1)^p \sum_{l=0}^{+\infty} B_l \int_{\theta=0}^{\pi} \left[(l+1)\frac{dr_p^a(\theta)}{r_p^a(\theta)} P_l(c_p^a(\theta)) \right. \\ & \left. - \cdots dc_p^a(\theta) P_l^{(1)}(c_p^a(\theta)) \right] \left(\frac{a}{r_p^a(\theta)}\right)^{l+1} \sin\theta \, d\theta \end{aligned} \tag{5.14}$$

Because of the linearity between v_f^Q and Q_0, derivating Equation 5.14 along the floating potential is equivalent to dividing it by v_f^Q. So noting $\dot{B}_l = (B_l/v_f^Q) = (\partial B_l/\partial v_f^Q)$, it becomes

$$\begin{aligned} \frac{C_S}{2\pi\varepsilon a} = {} & \sqrt{2}\dot{B}_0 + a\sum_{p*} (-1)^p \sum_{l=0}^{+\infty} \dot{B}_l \int_{\theta=0}^{\pi} \left[(l+1)\frac{dr_p^a(\theta)}{r_p^a(\theta)} P_l(c_p^a(\theta)) \right. \\ & \left. - \cdots dc_p^a(\theta) P_l^{(1)}(c_p^a(\theta)) \right] \left(\frac{a}{r_p^a(\theta)}\right)^{l+1} \sin\theta \, d\theta \end{aligned} \tag{5.15}$$

Defining the row vector Γ, whom generic kth term Γ_k is

$$\begin{aligned} \Gamma_k = {} & \frac{\delta_{0,k-1}}{\sqrt{2}} + \frac{a}{2\sqrt{2}} \sum_{p*} (-1)^p \int_{\theta=0}^{\pi} \left[k\frac{dr_p^a(\theta)}{r_p^a(\theta)} P_{k-1}(c_p^a(\theta)) \right. \\ & \left. - \cdots dc_p^a(\theta) P_{k-1}^{(1)}(c_p^a(\theta)) \right] \left(\frac{a}{r_p^a(\theta)}\right)^{k} \sin\theta \, d\theta \end{aligned}$$

and defining the column vector $\dot{\mathbf{B}}$, the pth term of which is $\dot{B}_p$, we can write the relation (5.15) as a vector-product:

$$C_S = 4\pi a \boldsymbol{\Gamma} \dot{\mathbf{B}} \tag{5.16}$$

5.3.2.2.1 Expression of B_l Coefficients

The relation (5.13), written at $r = a$ and divided by v_f^Q, gives

$$\sum_{l=0}^{+\infty} \dot{B}_l P_l(\cos\theta) + \sum_{p*} (-1)^p \sum_{l=0}^{+\infty} \dot{B}_l \left(\frac{a}{r_p^a(\theta)}\right)^{l+1} P_l(c_p^a(\theta)) = 1, \quad \forall\theta \tag{5.17}$$

Projecting this relation on all the orders of the Legendre's polynomials (using their orthonormality and the fact that $P_0 = 1/\sqrt{2}$), we obtain the linear system:

$$\mathbb{M}\dot{\mathbf{B}} = \sqrt{2}\mathbf{1}_1$$

where

- $\mathbf{1}_1$ is a column vector whose first coefficient is 1 and the others are zeros
- $\mathbb{M}$ is a square matrix whose generic term M_{km} is

$$M_{km} = \delta_{k-1,m-1} + \sum_{p*} (-1)^p \int_{\theta=0}^{\pi} \left(\frac{a}{r_p^a(\theta)} \right)^m P_{m-1}(c_p^a(\theta)) P_{k-1}(\cos\theta) \sin\theta \, \mathrm{d}\theta \tag{5.18}$$

with $\delta_{k,m}$ the Kronecker symbol.

The coefficients $\dot{B}_l$ are so the unknown variables of a linear well-posed problem. The matrix $\mathbb{M}$ is numerically well-conditioned (its size and its numerical properties are explained in the numerical section of this part). The coefficients $\dot{B}_l$ are given by

$$\dot{\mathbf{B}} = \sqrt{2}\mathbb{M}^{-1}\mathbf{1}_1 \tag{5.19}$$

5.3.2.2.2 *Matricial Expression for the Capacitance*

Hence, the relation (5.16) becomes a simple matrix relation, numerically easy to manipulate:

$$C_S = 4\pi\varepsilon a \boldsymbol{\Gamma} \mathbb{M}^{-1}\mathbf{1}_1 \tag{5.20}$$

5.3.2.2.3 *Corollary: Expression of Partial Capacitances*

Using the relation (5.19) and the row vector $\Gamma^{(1,2)}$ (the superscript (1,2) indicates the part of the dot where we integrate σ) whose generic kth term $\Gamma_k^{(1,2)}$ is

$$\Gamma_k^{(1,2)} = \frac{1}{2}\delta_{0,k-1} + a\frac{1}{\sqrt{2}} \sum_{p*} (-1)^p \int_{\theta=\theta^{(1,2)}}^{\theta^{(1,2)}+\pi/2} \left[k \frac{dr_p^a(\theta)}{r_p^a(\theta)} P_{k-1}(c_p^a(\theta)) \right.$$

$$\left. - \cdots dc_p^a(\theta) P_{k-1}^{(1)}(c_p^a(\theta)) \right] \left(\frac{a}{r_p^a(\theta)} \right)^k \sin\theta \, \mathrm{d}\theta$$

the relation (5.8) becomes matricially

$$C_{(1,2)} = 4\pi\varepsilon a \boldsymbol{\Gamma}^{(\mathbf{1,2})} \mathbb{M}^{-1}\mathbf{1}_1 \tag{5.21}$$

5.3.2.3 Semi-Analytical Expression for the Potential

To finish this section, we rewrite the expression of the potential due to the charge as a matricial product. Using the relations (5.19) and (5.4) and the row vector $\mathbf{G}(r, \theta)$ whose generic term is

$$G_k(r,\theta) = \sqrt{2}\left(\frac{a}{r}\right)^k P_{k-1}(\cos\theta) + \sqrt{2}\sum_{p*}(-1)^p \left(\frac{a}{r_p}\right)^k P_{k-1}(\cos\theta_p)$$

the expression (5.13) for the potential $V^{Q}(M)$ in the dielectric medium becomes

$$V^{Q}(M) = \frac{Q_0}{C_S}\mathbf{G}(r,\theta)\mathbb{M}^{-1}\mathbf{1}_1 \tag{5.22}$$

5.3.3 Influence of Polarization

5.3.3.1 Analytical Expression for the Coupling Coefficient

In this section, we consider that $Q_0 = 0$ and that a polarization, $\Delta V = V_1 - V_2$, is applied between the two plate electrodes. As it is usually done in classical electrodynamics, the potential $V^{\text{po}}(M)$—defined in relation (5.1)—is split into two parts. The first, denoted by v^i, is the potential due to the polarization ΔV in the dielectric medium considered as empty. It is often called "incident" or "primary" potential (classically used in scattering models [30,32]). It is the potential that should exist if the dot was not there. The second part of the potential, denoted by v^{d} is due to the presence of the dot in the polarized medium. Classically this term is called "scattered" potential or "secondary" potential. Then

$$V^{\text{po}}(r,\theta) - V_2 = v^i(r,\theta) + v^{\text{d}}(r,\theta) \tag{5.23}$$

v^i is the potential in a plane capacitor.

$$v^i(r,\theta) = (\lambda_2 + z - z_0)\frac{\Delta V}{h} = (\lambda_2 + r\cos\theta)\frac{\Delta V}{h} \tag{5.24}$$

The boundary conditions satisfied by $V^{\text{po}}(M)$ are the following:

(Pa) $V^{\text{po}}(M) = V_1$ for $z = z_1$ and $V^{\text{po}}(M) = V_2$ for $z = z_2$
(Pb) The potential is floating and constant on the dot: $V^{\text{po}}(a,\theta) - v_{\text{f}}^{\text{po}}\ \forall\theta$
(Pc) Relations (5.3) with $Q_0 = 0$ are still valid

The scattered potential is expandable as a series of Legendre polynomials, for every M located in the same medium [28,30]. That is to say this expansion is valid only in the greatest sphere centered on O that does not cut the electrodes. This particular sphere, denoted by C in Figure 5.4, is tangent to the nearest electrode from the point O. Assuming that the nearest electrode is the bottom one (V_2), the radius of C is $\lambda_2 = a + t_2$. In this sphere ($r \le \lambda_2$), we have

$$v^{\text{d}}(r,\theta) = \sum_{m=0}^{+\infty}\left[U_m\left(\frac{r}{a}\right)^m + W_m\left(\frac{a}{r}\right)^{m+1}\right]P_m(\cos\theta) \tag{5.25}$$

Using the boundary conditions (Pb) and (Pc) on the dot and the orthonormal properties of Legendre's polynomials, it follows that

$$\begin{cases} W_0 = 0 \\ U_0 = \left(v_{\text{f}}^{\text{po}} - V_2 - \lambda_2\dfrac{\Delta V}{h}\right)\sqrt{2} \\ U_m = -W_m - a\dfrac{\Delta V}{h}\sqrt{\dfrac{2}{3}}\delta_{m,1} \quad \forall m \ge 1 \end{cases} \tag{5.26}$$

The condition (Pa), for $\theta = \pi$, gives $U_m = -W_m, \forall m$. At zero-order it comes (with relations (5.26)):

$$v_{\mathrm{f}}^{\mathrm{po}} - V_2 = \frac{\lambda_2}{h}\Delta V \Rightarrow \alpha = \frac{\lambda_2}{h} \tag{5.27}$$

Remark: If the nearest electrode is the electrode 1, *the condition* (*Pa*) *gives* $v_{\mathrm{f}}^{\mathrm{po}} - V_2 = (1-(\lambda_1/h))\Delta V$ *which implies the same result for* α.

Finally, inside the sphere C, v^{d} can be written as

$$v^{\mathrm{d}}(r,\theta) = \frac{a}{h}\Delta V \frac{\lambda_2^3}{\lambda_2^3 - a^3}\left(\left(\frac{a}{\lambda_2}\right)^3 \frac{r}{a} - \left(\frac{a}{r}\right)^2\right)\cos\theta \tag{5.28}$$

5.3.3.2 Semi-Analytical Expression for the Potential in the Dielectric Medium

As a last corollary, the semi-analytical expansion for C_S and the simple expression of α allows us to express the total potential everywhere in the dielectric medium, when ΔV and Q_0 are non null.

To express the potential V^{po} everywhere in the dielectric, we use again the method of images for determining v^{d}. Indeed, v^i already contains the boundary conditions on the planes Π_1 and Π_2. The boundary conditions on v^{d} are $v^{\mathrm{d}}|_{\Pi_1} = v^{\mathrm{d}}|_{\Pi_2} = 0$. So we can expand the potential v^{d} as we did for V^Q in the previous section, with the same notations. Using the conditions (Pa), (Pb), (Pc), and the relation (5.27), we can finally write V^{po} as

$$V^{\mathrm{po}}(M) - V_2 = \frac{\lambda_2}{V}\Delta V \times \mathbf{G}\mathbb{M}^{-1}\mathbf{A}^h \tag{5.29}$$

where $\mathbf{A}^h$ is the column vector of generic term of order k, $A_k^h = -\sqrt{(1/3)}(a/h)\delta_{2,k}$.

Finally using the two relations (5.22) and (5.29), the total potential in the dielectric medium is

$$V(M) - V_2 = \mathbf{G}\mathbb{M}^{-1}\left(\frac{Q_0}{C_S}\mathbf{1}_1 + \frac{\lambda_2}{h}\mathbf{A}^h\right) \tag{5.30}$$

This expression allows one to estimate the distribution of charges on the electrodes, derivating this relation along z, at $z = 0$ and h. This is not the subject of this chapter but a parametric study of this distribution could be interesting to understand the classical approximations of C_S. Moreover, this should allow to obtain immediately the electric field everywhere in the medium. This physical quantity is necessary to model charge transport phenomenon through the dielectric layers.

To conclude this part, let us remind that the semi-analytical relations (5.20) and (5.27) solve the physical parameters of the configuration. As a final corollary, the matricial relation (5.30) gives the electrostatics of the dot.

We notice that this classical approach is invariant by scale change. So, these results can be directly used for larger configurations with the same aspect ratio. We can cite for instance chemical sciences where models of metallic bubbles embedded in dielectric solutions are often used.

5.3.4 Numerical Implementation

The numerical computation of the capacitance is numerically conditioned by the obtaining an invertible matrix $\mathbb{M}$. Numerically, the matrix $\mathbb{M}$ is a square matrix of the typical size 10 × 10. This is not a critical size for classical numeric inversion. Moreover, in practice, the conditioning (ratio between greatest and smallest values) of this matrix is about unity. Hence, the inversion of the matrix $\mathbb{M}$ is not the key point of this numerical implementation. Its quality is conditioned by the double truncation of the expansion of the potential (on the maximum order of polynomials in one hand and on the number of images in the other one). A discussion about the influence of this truncation is presented in Appendix A. Let us say here that the two truncations are independent one of each other, and numerically they are not critical at all for computations. Moreover, the semi-analytical expression was numerically validated by comparing results provided by finite element method (FEM) computations. This validation is also presented in Appendix A. To briefly sum up the conclusions, let us say that FEM may have some accuracy problems and it is clearly slower.

5.3.5 Numerical Results and Comparison with a Classical Approximation

Classically C_S and α are estimated by different physically based approaches using very simple expressions. Nevertheless, the validity of these latest approaches is not always well known. A very classical phenomenological approach is the equivalent capacitances approach (for details, see [24]) that we will briefly expose here.

It is assumed that a coupling capacitance can be defined between the dot and each electrode. Let us denote $C_{\mathrm{C}}^{\mathrm{b}}$ (resp. $C_{\mathrm{C}}^{\mathrm{t}}$) the capacitance between the dot and the bottom (resp. top) electrode. The sum of these two capacitances is equal to C_{C}. We further assume that $C_{\mathrm{C}}^{\mathrm{b}}$ and $C_{\mathrm{C}}^{\mathrm{t}}$ are classical capacitances, as defined for metallic bodies under mutual influence and that the polarization coupling coefficient α is given by the ratio $\beta = (C_{\mathrm{C}}^{\mathrm{t}}/C_{\mathrm{C}})$. The parallel plate approximation (PPA) consists in approximating the capacitances $C_{\mathrm{C}}^{\mathrm{b}}$ and $C_{\mathrm{C}}^{\mathrm{t}}$ by plate capacitances in which surface S is the projected surface of the dot on each electrode and whose thickness $t_{\mathrm{C}}^{\mathrm{b}}$ (resp. $t_{\mathrm{C}}^{\mathrm{u}}$) is the typical distance between the dot and each electrode. This rough approximation is even used to model single-electron effects such as Coulomb blockade [16]. Note that it is possible to use several surfaces and typical distances to calculate this plate capacitances. Here, we choose two different thicknesses for the same configuration ($t_{\mathrm{C}}^{\mathrm{t}} = t_1$ or $t_{\mathrm{C}}^{\mathrm{t}} = t_1 + a = \lambda_1$ to illustrate the capacitances.

1. The thicknesses of the capacitances are the distance between the border of the dot and the electrodes: $t_C^b = t_2$ and $t_C^t = t_1$. This approximation is named PPA(1).

$$C_C^b(1) = \varepsilon\frac{S}{t_2}, \quad C_C^t(1) = \varepsilon\frac{S}{t_1}, \quad C_C(1) = \varepsilon\left(\frac{S}{t_1} + \frac{S}{t_2}\right)$$
$$\text{and} \quad \beta(1) = \frac{t_2}{t_1 + t_2} \tag{5.31}$$

2. The thicknesses of the capacitances are the distance between the center of the dot and the electrodes: $t_C^b = \lambda_2$ and $t_C^t = \lambda_1$. This approximation is named PPA(2).

$$C_C^b(2) = \varepsilon\frac{S}{\lambda_2}, \quad C_C^t(2) = \varepsilon\frac{S}{\lambda_1}, \quad C_C(2) = \varepsilon\left(\frac{S}{\lambda_1} + \frac{S}{\lambda_2}\right)$$
$$\text{and} \quad \beta(2) = \frac{\lambda_2}{\lambda_1 + \lambda_2} \tag{5.32}$$

To compare the validity of these approximations, we compare some results given by PPA and results given by the semi-analytical (SA) method. For a given radius, we compare the evolution of the capacitances and different ratios versus the value of t_2. The numerical values are the following: $a = 2.8$ nm, $t_1 = 12$ nm, $\varepsilon_r = 3.9$, and t_2 is varying from 0.5 to 10.5 nm. For the surface S, we have chosen the surface of the disk of radius a as $S = \pi a^2$.

In Figure 5.6, we plot the evolution of the three capacitances C_S (denoted by SA), $C_C(1)$ and $C_C(2)$, divided by the factor $4\pi\varepsilon a$, versus the ratio t_2/a. We also plot the ratios $C_C(1)/C_S$ and $C_C(2)/C_S$. The behavior given by the approximation (1) is qualitatively correct. Quantitatively, this is not very convincing. Indeed for $t_2/a < 1$, the ratio $C_C(1)/C_S$ is not quite constant. It varies from 0.7 to 0.2. There is no way to fit the values of C_S by $C_C(1)$ just by adjusting the numerical value of S. PPA(2) seems qualitatively and quantitatively more interesting to estimate C_S. For $t_2/a < 1$, the ratio $C_C(2)/C_S$ is varying from 0.12 to 0.14 (a variation about 20%).

For large values of t_2/a, the behavior of PPA(1) and PPA(2) are asymptotically equivalent. The asymptotic limit for $t_2 \gg a$ is $a/(4t_1) \sim 5.83 \times 10^{-2}$ for $C_C(1)/(4\pi\varepsilon a)$ and $a/(4(t_1 + a)) \sim 4.73 \times 10^{-2}$ for $C_C(2)/(4\pi\varepsilon a)$. In the figure, we see the beginning of this asymptotic behavior. Because the limiting value of t_2, in our simulation, is of the same order of t_1, the smallest values seen on the figure are approximatively twice the limiting value. For $t_2/a > 2$, the ratio $C_C(2)/C_S$ remains quite constant, varying from 0.11 to 0.09. The ratio $C_C(1)/C_S$ varies from 0.15 to 0.1.

Finally, in all the range of values of t_2/a presented here, only the PPA(2) allows to approximate C_S with finite relative error. The difficulty consists in finding a numerical value for the surface S that makes PPA match the capacitance.

To end this comparison, the dimensionless coefficients κ_1, $\beta(1)$, and $\beta(2) = \alpha$ are compared. For great values of t_2/a, $\beta(1)$ tends to 1 while $\beta(2)$ tends to 0.5. The limiting value of κ_1 is also 0.5 (because C_2 tends to the capacitance of a single half-sphere). On the other hand, for small t_2/a, the limiting value for $\beta(2)$ is $a/(t_1 + 2a) \sim 0.15$, while $\beta(1)$ tends to 0 and C_1 also to 0 (for small t_2, only C_2 contributes to the value of C_S).

In Figure 5.7, we plot the coefficients κ_1, $\beta(1)$, and $\beta(2)$ versus t_2/a for the same previous configuration. On this figure, it appears that the coefficient $\beta(2)$ underevaluates κ_1 for $t_2/a > 0.25$. The greatest relative difference between κ_1 and $\beta(2)$ is observed for $t_2/a \sim 1$ and is about 30%. For $t_2/a > 3$, the relative difference is lower than 10%. The coefficient $\beta(1)$ is far from κ_1, even in the range $t_2/a \ll 1$.

For values of t_2/a in the range of the unity, neither PPA(1) nor PPA(2) gives an approximation with an accuracy better than 10%. Only PPA(2) could give a good approximation, if we are able to evaluate an optimized value for the surface S.



FIGURE 5.6 Comparison between normalized capacitances obtained by the approximations PPA(1) and PPA (2) and by SA. In the first figure, the capacitances are normalized by the factor $4\pi\varepsilon a$. The second figure represents the ratios C_C/C_S for the two approximations. The capacitances and the ratios are plotted versus the ratio t_2/a, for a fixed radius a and variable t_2.



FIGURE 5.7 Undimensioned coefficients κ_1, $\beta(1)$, $\beta(2)$, and α versus the ratio t_2/a.

5.3.6 Conclusion

We devised a semi-analytical model for the potential and the capacitance of a spherical metallic dot located in a dielectric medium between two metallic planes at fixed potential. From this model, we establish a simple analytical expression for the polarization coupling coefficient. We have derived a semi-analytical formulation for the potential everywhere in the dielectric medium. The validity of our approach has been established by comparison with a variational numerical approach. Finally, we have discussed the validity of classical approximations for the capacitance, particularly when the distance between the border of the dot and the nearest electrode has the same order of magnitude as the radius of the dot.

Three major developments are under study. The first one, developed in the next part of this chapter, consists in using this approach in the quantum model of a dielectric dot. First, it allows to generate an initial evaluation of the floating potential used in iterative resolution of Schrödinger and Poisson systems. Second, the comparison between the classical and quantum approaches determines the critical dimensions leading to a quantum behavior. The second development is to adapt this model for dielectric dots. The method of images remains interesting but the spatial distribution of charges in the dot—even in a non-quantum approach—is a serious node of the resolution. The third point is to use the evaluation of the potential around the dot to model the electric field, first step to a modelization of an electronic transport through the dielectric.

5.4 Semiconductor Dot: Theoretical Approach

5.4.1 General Considerations on Quantization Effects

In the metallic case, the electric charge is distributed on the surface of the dot. On the contrary, in the case of a semiconductor dot, the electric charge is distributed in the volume of the nanocrystal and in the surrounding dielectrics. The resolution of such a configuration in a classical approach needs conditions of continuity of the electric field involving model of macroscopic polarization of the dielectric medium. This approach is classically exposed in different works (for instance, Refs. [28,30]). However, when the dot size falls into the nanometer range, classical electrostatics and semiclassical approaches of charge in semiconductor devices are no longer sufficient to describe the charge density and thus the electrostatic potential inside the nanocrystal. Two arguments favor a quantum approach to correctly describe the problem. First of all, let us consider the De Broglie wavelength, λ_B, that describes the wave–particle duality of any particle of mass m; it is equal to the ratio of Planck constant, h, on the kinetic momentum p. In the case of a free thermal electron of mass m_e, at temperature T, De Broglie wavelength is

$$\lambda_B = \frac{h}{p} = \frac{h}{\sqrt{2kTm_e}}$$

where k is the Boltzmann constant.

At ambient temperature ($T \sim 300\,\text{K}$), λ_B is around 8 nm; this values gives an order of magnitude of the extension of the electronic wavefunction.

In the frame of this work, we will consider semiconductor islands with typical radius around 10 nm, so it becomes a priori necessary to take into account quantum effects to solve the electrostatics of the dot.

Another way to convince ourselves of this latest point is to remind us of some results obtained in the case of an infinite quantum well. Indeed, electrons confined in quantum dots can be roughly compared to the problem of a single particle in an infinite quantum well.

Let us consider an infinite one-dimensional quantum well of width $2a$. Due to the strong confinement of the wavefunction into the well, the only possible solution of Schrödinger equation inside the dot are standing waves with wave number, k_n, equal to

$$k_n = \frac{n\pi}{2a} \tag{5.33}$$

The non-normalized density of probability, $\tilde{\psi}_n(x)$ is given by

$$\tilde{\psi}_n(x) = \sin\left[k_n x - n\frac{\pi}{2}\right] \tag{5.34}$$

From now, the normalized density of probability is denoted by ψ. The normalization is such as the density is unitary.

The energy of the nth bound state, with respect to the bottom of the well, is proportional to the square of the wave number:

$$E_n = \frac{\hbar^2 k_n^2}{2m_e} = \frac{n^2h^2}{32m_e a^2} \tag{5.35}$$



FIGURE 5.8 Schematic representation of an infinite quantum well of width $2a$ and of the three first bound states and their energy.

As an explicative pattern, the eigen wavefunction ψ_n and the level of energy E_n for the three first levels of quantification are plotted simultaneously in Figure 5.8. The evolution of the energy of the first bound state, E_1, is plotted as a function of the dimension of the quantum well in Figure 5.9. If we compare the energy level of the first bound state with the thermal energy, k_BT, we can see that when the quantum well's typical size, a, falls under 2–3 nm, E_1 becomes greater than the thermal energy at ambient temperature (~25.6 meV). From this consideration, we define R_Q the value of the quantum well radius at which the energy shift due to quantum confinement in the dot becomes equal to the thermal energy:

$$R_Q = \frac{nh}{4}\sqrt{\frac{1}{2m_e k_B T}} \tag{5.36}$$

As seen in Figure 5.10, for temperatures ranging from 5 to 300 K, R_Q values are in the 10 nm range, which is the typical size of the quantum dots that we will consider here.



FIGURE 5.9 Evolution of the energy level of the first bound state, E_1, obtained in an infinite well of width $2a$ versus a.



FIGURE 5.10 Evolution of quantum dot radius at which quantization energy becomes greater than thermal energy, R_Q, with temperature.

5.4.2 Quantum Dot Containing a Single Electron: A Simplified Approach

To start with, in this study of the electronic properties of semiconductor dots, we present the main equations describing the behavior of a single electron in the conduction band of a silicon nanocrystal. As explained in the introduction of this section, due to the fact that the De Broglie wavelength is of the same order as the dimension of the nanocrystal, a quantum approach has to be used. Due to the difference in electronic affinity between silicon and silicon oxide, a single silicon dot embedded in a SiO_2 matrix acts as a quantum well for electrons in the conduction band, as shown in Figure 5.11. This system is close to the well-known case of a finite potential well described in many graduate textbooks [33,34]. If analytical expression can be easily found for E_n and $\psi_n(\vec{r})$ in the case of an empty finite or infinite quantum well, it is not the case for a finite quantum well containing several electrons; as a consequence, solving Schrödinger equation is done numerically.

In this chapter, we consider an undoped semiconductor quantum dot embedded in a silicon dioxide matrix. Due to the extremely low concentration of free carriers in intrinsic semiconductor ($n_i \approx 10^{10}$ cm^{-3} for silicon, at 300 K), we assume that there is no free electron in the conduction band of the nanocrystal. Let us make a quick calculation to illustrate this assertion.



FIGURE 5.11 Energy band diagram representing a silicon nanocrystal embedded in a SiO_2 matrix along one direction.

Let us consider a silicon nanocrystal of radius $a = 10\,\text{nm}$, the intrinsic number of electrons N is

$$N = n_i \times \frac{4}{3}\pi a^3 \sim 4\times 10^{-8} \ll 1$$

For the sake of simplicity, we only consider the bound states existing in the conduction band. We neglect any perturbation arising from the valence band and spin degeneracy. Let us note $E_C(\vec{r})$ the spatial density of the potential energy in the conduction band. Considering the above finite quantum well with a single additional free electron in the conduction band, the spatial evolution of probability density, $\psi(\vec{r})$ is described by the Schrödinger equation in stationary regime. If we look at the first electronic states—at low energy—it is possible to consider that the electron behaves as a quasi-free particle in the dot with an isotropic effective mass m^*_{eff} [35] ($m^*_{\text{eff}} \approx 0.26 m_e$ in silicon):

$$\mathbb{H}\psi(\vec{r}) = E\psi(\vec{r}) \tag{5.37}$$

with

$$\mathbb{H} = \frac{\vec{p}^{\,2}}{2m^*_{\text{eff}}} + V_{\text{conf}}(\vec{r}) \tag{5.38}$$

where

- $V_{\text{conf}}(\vec{r})$ is the potential confining the electron evaluated at the point $\vec{r}$ (see Figure 5.11)
- $\vec{p}$ is the kinetic momentum operator (classically equivalent to a Laplacian [33,34])

$V_{\text{conf}}(\vec{r})$ must be evaluated with the help of hypothesis, described in the following, for each configuration.

In the case of a single electron in a quantum well, the potential energy $V_{\text{conf}}(\vec{r})$ is only equal to the conduction band energy value at position $(\vec{r})$, $E_C(\vec{r})$. For convenience, we take the bottom of the conduction band energy in the quantum dot as the energy reference.

As there is no other energy contribution in the Hamiltonian $\mathbb{H}$ due to the presence of other electrons in the conduction band, this problem is the same as the finite quantum well. The only available energy states for the electron, are the same (E_n; ψ_n) than those of the finite well. For the following, we suppose that the wavefunction ψ_n has been properly normalized.

The presence probability $\mathcal{P}(\vec{r})$, of the electron at position $\vec{r}$, is thus equal to

$$\mathcal{P}(\vec{r}) = |\psi_n(\vec{r})|^2 \tag{5.39}$$

Under these conditions, we can built the charge density at any position, $\rho(\vec{r})$, as the product of the electronic charge by the presence probability at $\vec{r}$ (which is also known as the charge density *observable*):

$$\rho(r) = -e \times \mathcal{P}(\vec{r}) = -e \times |\psi_n(\vec{r})|^2 \tag{5.40}$$

where e is the fundamental charge. As described above, charge density depends on the bound state occupied by the electron. Once the wavefunction of the bound state is known, a numerical resolution of the Poisson equation using the above charge density gives the electrostatic potential of the structure and the evolution of the conduction band energy. For our problem, we make the assumption that the electron, without any external perturbation, is on the first available quantum state, i.e., the fundamental bound state at energy E_1 with the normalized presence probability density $\psi_1(\vec{r})$ and solve the Poisson equation to derive the electrostatic potential, $V(\vec{r})$, in the whole structure:

$$\Delta V(\vec{r}) = -\frac{\rho(\vec{r})}{\varepsilon_0 \varepsilon_r} \tag{5.41}$$

where

- ε_r is the relative dielectric permittivity of the material
- Δ is the Laplacian operator

5.4.3 Addition of a Second Electron in the Dot

In this section, we consider the previous system made of a silicon nanocrystal embedded in a SiO_2 matrix containing a single electron on the first bound state. When a second electron is added in the conduction band, the probability density, ψ, rigorously becomes a function of two positions:

$$\psi_n = \psi_n(\vec{r}_1, \vec{r}_2) \tag{5.42}$$

Under these conditions, the Hamiltonian of the system is written as

$$\mathbb{H} = \frac{\vec{p}_1^{\,2}}{2m^*_{\text{eff}}} + \frac{\vec{p}_2^{\,2}}{2m^*_{\text{eff}}} + V_{\text{conf}}(\vec{r}_1) + V_{\text{conf}}(\vec{r}_2) + \frac{q^2}{4\pi\varepsilon_0\varepsilon_r \|\vec{r}_1 - \vec{r}_2\|^2} \tag{5.43}$$

where $\vec{p}_1$ and $\vec{p}_2$ are the kinetic momentum operators of each electron. At this stage, it is very important to notice that an energy term has been added in the Hamiltonian. This term is due to the *Coulombian interaction* of electrons with each other and corresponds to the *electrostatic energy*. Including the interaction term in the Hamiltonian and considering two position variables, solving the problem becomes very heavy, even numerically. Moreover, when we consider further more than two electrons in the nanocrystal, the problem quickly become a N-body problem. For this reason, some approximations are required to be developed further. In the following, we use an approximation that allows to write the wavefunction in a simpler way.

In the Hartree approximation [36], we make the assumption that each electron can be described by an individual wavefunction, respectively $\psi_1(\vec{r})$ and $\psi_2(\vec{r})$, as if they were *independent*. Therefore, the global wavefunction can be written as the product of these individual wavefunctions:

$$\psi(\vec{r}_1,\vec{r}_2)=\psi_1(\vec{r}_1)\times\psi_2(\vec{r}_2) \tag{5.44}$$

In this approximation, we calculate ψ_1 and ψ_2 in such a way that the *total energy* of the system is *minimal*. Moreover the separation of the wavefunction allows to use a *mean field* approximation in which we consider that the electrostatic interaction felt by one electron can be described as if it felt the electrostatic potential induced by the other one(s).

The problem now consists in calculating ψ_1 and ψ_2 by solving individual Schrödinger equations with Hamiltonians $\mathbb{H}_1$ and $\mathbb{H}_2$ with

$$\mathbb{H}_{1,2}\psi_{1,2}(\vec{r}_{1,2})=E_{1,2}\psi_{1,2}(\vec{r}_{1,2}) \tag{5.45}$$

with

$$\mathbb{H}_{1,2}=\frac{\vec{p}_{1,2}^{\,2}}{2m_e}+V_{\text{conf}}(\vec{r}_{1,2})+V_{\text{inter}_{1,2}}(\vec{r}_{1,2}) \tag{5.46}$$

$V_{\text{inter}_{1,2}}(\vec{r}_{1,2})$ is the term of Coulomb interaction defined in relation (5.43).

If we compare this latest equation with the one used for the single-electron case (5.37), V_{inter} has been added to take account of the Coulomb interaction between both electrons. As V_{inter} is the mean electrostatic potential induced by the antagonist electron, it is a solution of the Poisson equation:

$$\Delta V_{\text{inter}_{1,2}}(\vec{r}_{1,2})=-\frac{\rho_{2,1}(\vec{r}_{1,2})}{\varepsilon_0\varepsilon_r} \tag{5.47}$$

where $\rho_{2,1}(\vec{r})$ is given by (5.40)

$$\rho_{2,1}(\vec{r})=-e\times\left|\psi_{2,1}(\vec{r})\right|^2 \tag{5.48}$$

The total energy of the system is equal to the sum of the energy corresponding to the bound states of both electrons *plus* the electrostatic energy arising form the Coulomb interaction between both electrons, E_{inter}:

$$\mathbb{E}_{\text{tot}}=\mathbb{E}_1+\mathbb{E}_2+\mathbb{E}_{\text{inter}} \tag{5.49}$$

with

$$\begin{aligned}\mathbb{E}_{\text{inter}}&=\iiint_{\text{space}}-e\left|\psi_1(\vec{r})\right|^2\times V_{\text{inter}_1}(\vec{r})\cdot d^3\vec{r}\\&=\iiint_{\text{space}}-e\left|\psi_2(\vec{r})\right|^2\times V_{\text{inter}_2}(\vec{r})\cdot d^3\vec{r}\end{aligned} \tag{5.50}$$

From Equations 5.46 to 5.48 it is obvious that this problem can be solved only *self-consistently*; ψ_1 is computed by solving (5.46) using an initial guess for ψ_2. Then, Poisson equation is solved using ρ_1 as charge density and the corresponding potential V_{inter_2} is used in (5.46) to compute ψ_2. This algorithm is iteratively repeated until the total energy $\mathbb{E}_{\text{tot}}$ calculated at the end of each loop converges.

5.4.4 Multiple Electrons in the Dot

In this section, we extend the results presented in the previous section to the case of multiple electrons in the dot with the same methodology. When the quantum dot contains N electrons, Hamiltonian can be derived in a similar way than in the two-electron problem (relation 5.43):

$$\mathbb{H}=\sum_{j=1}^{N}\frac{\vec{p}_j^{\,2}}{2m_{\text{eff}}^{*}}+\sum_{j=1}^{N}V_{\text{conf}}(\vec{r}_j)+\frac{1}{2}\times\sum_{j=1}^{N}\sum_{\substack{i=1\\ i\neq j}}^{N}\frac{q^2}{4\pi\varepsilon_0\varepsilon_r\left\|\vec{r}_j-\vec{r}_i\right\|^2} \tag{5.51}$$

where

$\vec{p}_j$ is the kinetic momentum operator of electron j

V_{conf} is the confining potential

the last term of Equation 5.51 is the interaction potential coming from the electrostatic interaction of the N electrons with each other.

Note that the prefactor 1/2 has been added to avoid to count twice the same interaction.

Rigorously, the solution of the problem is given by solving Schrödinger equation with a N-variable wavefunction:

$$\psi=\psi(\vec{r}_1,\vec{r}_2,\ldots,\vec{r}_N) \tag{5.52}$$

As mentioned in the previous section, solving this N-body problem needs an approximations on the wavefunction. In the Hartree approximation, the wavefunction can be written as the product of N individual *normalized* wavefunction:

$$\psi(\vec{r}_1,\vec{r}_2,\ldots,\vec{r}_N)=\prod_{j=1}^{N}\psi_j(\vec{r}_j) \tag{5.53}$$

each wavefunction can now be associated to an Hamiltonian operator describing the behavior of the jth electron:

$$\mathbb{H}_j\psi_j(\vec{r}_j)=\mathbb{E}_j\psi_j(\vec{r}_j) \tag{5.54}$$

with

$$\mathbb{H}_j=\frac{\vec{p}_j^{\,2}}{2m_{\text{eff}}^{*}}+V_{\text{conf}}(\vec{r}_j)+V_{\text{inter}_j}(\vec{r}_j) \tag{5.55}$$

V_{inter_j} refers to the electrostatic interaction between electron j and the mean potential induced by the $(N-1)$ other electrons.

Assuming that an equivalent charge density, $\rho_j(\vec{r})$ can be defined for each electron:

$$\rho_j(\vec{r}) = -e \times \left|\psi_j(\vec{r})\right|^2 \tag{5.56}$$

the electrostatic interaction potential V_{inter} is solution of the following Poisson equation:

$$\Delta V_{\text{inter}_j}(\vec{r}) = -\sum_{\substack{i=1\\ i\neq j}}^{N} \frac{\rho_i(\vec{r})}{\varepsilon_0\varepsilon_r} \tag{5.57}$$

The total energy of the system is the sum of the individual eigen energies of the electrons *plus* the electrostatic interaction energy:

$$\mathbb{E}_{\text{tot}} = \sum_{i=1}^{N} \mathbb{E}_i + \mathbb{E}_{\text{inter}} \tag{5.58}$$

where

$$\mathbb{E}_{\text{inter}} = -\frac{1}{2}\sum_{i=1}^{N}\sum_{\substack{j=1\\ j\neq i}}^{N}\iiint_{\text{space}} q\left|\psi_i(\vec{r})\right|^2 \times V_{\text{inter}_j}(\vec{r})\cdot \mathrm{d}^3\vec{r} \tag{5.59}$$

To solve the entire problem in the Hartree approximation, it is now necessary to self-consistently solve the set of coupled Equations 5.54 and 5.57 in order to minimize the total energy of the system (5.58).

In this study, electrical results presented in the next section are obtained by using the algorithm presented in Figure 5.12. Starting from an initial assumption for wavefunctions (assuming, for example, an homogenous dilution of the electrons in the quantum dot) and for the potential of the dot (metallic approach or empty dot with coupling polarization), the Poisson equation is solved to determine the interaction potential, V_{inter}. This potential is used in the system Hamiltonian (5.55) as well as the confining potential, V_{conf}, to determine the bound states, i.e., their energies, $\mathbb{E}_j$ and the normalized wavefunctions, ψ_j. This process is repeated for the N electrons and then, the total energy of the system, $\mathbb{E}_{\text{tot}}$ is calculated using Equations 5.58 and 5.59. If the difference of the total energy found at the nth and $(n - 1)$th iteration is smaller than an user-defined value (ε), then the Poisson equation is solved for all electrons in the nanocrystal, otherwise the resolution restarts until this condition is satisfied.

We notice here that the influence of the initial guess on the final solution is very weak when the number of electrons is low. However, it can become critical in the case where the number of electrons becomes of the order of magnitude of 10.


Initial guess: $\psi_j^0(\vec{r})$
$k = 1$
$\tilde{\rho}_j(\vec{r}) = -e \times |\psi_j(\vec{r})|^2$
$\Delta V_{\text{inter}_j}(\vec{r}) = -\sum_{\substack{i=1\\ i\neq j}}^{N} \frac{\tilde{\rho}_j(\vec{r})}{\varepsilon_0\varepsilon_r}$
Poisson resolution
$k \leftarrow k+1$
$-\frac{\vec{p}_j^{\,2}}{2m_{\text{eff}}^*}\psi_j(\vec{r}) + (V_{\text{conf}}(\vec{r}) + V_{\text{inter}_j}(\vec{r}))\cdot\psi_j(\vec{r}) = E_j\cdot\psi_j(\vec{r})$
$n \leftarrow n+1$
$\psi_j(\vec{r})$ E_j
Schrödinger resolution
Yes
$k \le N$
Calculation of E_{tot}
Final poisson resolution
No
$|E_{\text{tot}}^{n-1} - E_{\text{tot}}^{n}| \le \varepsilon$
Yes
$\rho(\vec{r}) = -q \times \sum_{j=1}^{N} |\psi_j(\vec{r})|^2$

FIGURE 5.12 Algorithm used for the self-consistent resolution of Poisson and Schrödinger equations for multiple electrons in a quantum dot.

5.5 Finite Element Modeling of a Silicon Quantum Dot

In this section, we will present some simulation results obtained on a silicon dot by finite element modeling (FEM). For this study, we used COMSOL Multiphysics© [37] to generate the geometry as well as to solve Poisson and Schrödinger equations [38,39]. Firstly, we will present the studied structure and focus on the methodology used to optimize meshing, which is a crucial point in FEM. Then, the simulation results will be presented, in particular, we will see the influence of the dot radius and the number of electrons on the evolution of the electrostatic potential into the nanocrystal. Finally, we will compare the electrical results obtained in the previous chapter on metallic dots with those obtained in a full quantum treatment of the charge in a semiconductor dot.

5.5.1 Studied Structure and Meshing Strategy

The system studied consists in a spherical silicon dot embedded into a dielectric matrix of SiO_2. The notations are recalled in Figure 5.13. In this work, the thickness of the top and bottom oxides (t_1 and t_2) are respectively fixed to 10 and 5 nm, which are typical values used in the semiconductor industry [17].

As shown in Figure 5.14, the device can be reduced to a quarter of structure for plane-symmetry reasons along the (*YZ*) and (*XZ*) planes. This optimization of simulated geometry considerably reduces the computation time that can be advantageously converted into a finer mesh of the structure.

The boundary conditions used for this work are the following:

- Dirichlet conditions on both top and bottom electrodes: electrostatic potential fixed, respectively, to V_1 and V_2
- Symmetry conditions on the symmetry planes of the structure (*YZ*) (*XZ*)
- Neumann conditions (i.e., null electric field) on the external planes of the structures parallel to (*XZ*) and (*YZ*)



FIGURE 5.13 (a) Studied structure for the FEM simulation of the quantum dot containing multiple electrons. (b) 2D schematic view showing the dimensions of the structure.



FIGURE 5.14 Detailed view of the quarter-structure studied in FEM showing some relevant meshing parameters considered during the meshing operation: maximum mesh size in the dot (hmax_dot) and maximum mesh size in the oxide (hmax_ox).

For these simulations, we paid a particular attention to meshing which is a crucial point in FEM simulations. From a practical point of view, each simulation result was validated only after having verified that its result remains unchanged after successive mesh refinements [40]. Meshing the structure described in Figure 5.13 is sensitive to many parameters related to the dot size, oxide thickness and the total width of the structure. In each of these domains (dot or silicon dioxide), many parameters such as maximum (resp. minimum) mesh size as well as maximum (resp. minimum) mesh growth rate can be defined. For the sake of simplicity, we will only focus on two main parameters to see the way to optimize them as well as their impact on the numerical results. The parameters studied here are (see Figure 5.14)

- The maximum mesh size in the oxide: hmax_ox
- The maximum mesh size in the dot: hmax_dot

From a general point of view, meshing optimization consists in finding the best compromise between numerical accuracy and computation time by tuning the relevant meshing parameters. Indeed, for a three-dimensional problem the number of mesh points is N^3 where N is the average number of mesh per dimension. So, reducing the number of mesh in regions that do not need much refinement can drastically increase computation time. The two structures depicted in Figure 5.15 show typical results obtained for a set of value for (hmax_ox; hmax_dot) giving a coarse mesh (Figure 5.15a) and a finer one (Figure 5.15b). The natural trend is to refine mesh as much as possible, like in Figure 5.15b, but sometimes it considerably increases computation time or dramatically leads to numerical instabilities.



FIGURE 5.15 Comparison of the same structure meshed with different parameters: (a) coarse mesh giving fast computations (hmax_ox = 1 nm, hmax_ox = 3 nm) and (b) fine mesh giving a better numerical accuracy but more time consuming (hmax_dot = 0.25 nm, hmax_ox = 2 nm).


Initial value for p_1 and p_2: $(p_1^0; p_2^0)$
Mesh the structure using the set of parameters $(p_1^0; p_2^0)$
Solve the problem and store the solution: S_0
$k \leftarrow 1$
Decrease p_1
ex: $p_1^k \leftarrow 0.5 \times p_1^{k-1}$
Re-mesh the structure using the set of parameters $(p_1^k; p_2^k)$
Solve the problem
p_1 may be too small
increase p_1
ex: $p_1^k \leftarrow 0.75 \times p_1$
No
Convergence?
Yes
Store the solution: S_k
$||S_k - S_{k-1}|| < \varepsilon$?
No
$k \leftarrow k+1$
Yes
Set p_1^k as the best value for p_1

FIGURE 5.16 Algorithm used to mesh the structure.

As a consequence, for each of the two meshing parameters chosen in our study, a systematic study needs to be carried out to determine the best set of values for (hmax_ox; hmax_dot). To this aim, each parameter is separately adjusted, while the value of the other one is fixed, by an iterative study depicted in the algorithm of Figure 5.16. For each value of hmax_ox (resp. hmax_dot), the convergence is tested and the result is compared to the one obtained during the previous iteration. The value of the studied parameter is reduced until the difference between the simulation results obtained at iteration (*k*) and

$(k - 1)$ is lower than a user-fixed value. At this point, it means than reducing again the value of the studied parameter will not increase numerical accuracy anymore. The optimal set of meshing parameters values can be found by repeating this method as many times as the number of meshing parameters. To conclude with this method, let us mention that the factor used to reduce the studied parameter (i.e., 2) as well as the numerical accuracy criterion (i.e., ε) are very structure-dependent and need to be adjusted to the specificity of each problem.

In the typical case studied in this work, the meshing optimization has been performed on structure shown in Figure 5.14 with an applied bias of 5 V between the top and the bottom electrodes. To quantitatively evaluate the impact of the meshing parameters on the simulation results, the energy value of the first bound state in the dot without any electron inside (E_0) is followed when changing the values of hmax_ox and hmax_dot. Obviously, E_0 is obtained by solving Schrödinger equation in the dot after the meshing step. Note that the zero-energy reference has been taken at the bottom electrode. In Figure 5.17a and b, E_0 values are plotted for different values of hmax_ox and hmax_dot. As can be seen in Figure 5.17a and b, the maximum mesh size in the oxide does not seem to have any quantitative influence on E_0 (the total energy scale represented in the graph is below 1 meV). On the contrary, hmax_ox plays a crucial role in the numerical results; reducing its value from 1 × a (i.e., 2.5 nm) to 0.1 × a (i.e., 0.25 nm) changes the value found for E_0 from ≈5 meV. It is very interesting to notice that beyond 0.1 × a, reducing hmax_dot does not significantly change the numerical result obtained for E_0 meaning that an optimum value can be found around 0.1 × a. At this stage, it is useful to have a look at Figure 5.18 showing the exponential increase of the number of degree of freedom in the structure (i.e., number of mesh points) due to the reduction of the maximum mesh size in the nanocrystal; reducing hmax_dot from 0.1 × a to 0.05 × a makes the number of mesh points increases from ~20,000 to ~1 million units.



FIGURE 5.17 Meshing optimization. Evolution of the first self-energy found in the dot versus (a) hmax_ox and (b) hmax_dot. Note that values of are normalized with respect to the dot radius a.



FIGURE 5.18 Number of degree of freedom (DOF) versus normalized maximum mesh size in the dot.

For this work, the criterion chosen to determine the best value for each meshing parameter is that the variation of E_0 should not exceed 0.1 meV between two successive meshing. This criterion corresponds to an arbitrary choice allowing a good accuracy in the energy levels obtained in our problem; in this way, the maximum allowed energy uncertainty remains smaller than the thermal energy at 300 K (~25.6 meV). Using this criterion the value retained for hmax_ox and hmax_dot are, respectively, 3 nm and 0.07 × a.

5.5.2 Numerical Results

Using the algorithm detailed in Figure 5.12 and the structure meshed with the methodology exposed in previous section, Poisson and Schrödinger equations have been solved for an increasing number of electrons in the dot. Figure 5.19a shows the evolution of the charge density in the nanocrystal along the high-symmetry axis. When no external bias is applied, the shape of the charge density is very similar to the wavefunction of the first state in an infinite quantum well. However, when increasing the number of charges in the dot, Coulomb interaction between



FIGURE 5.19 (a) Charge density in the nanocrystal without any external bias ($V_1 - V_2 = 0$ V) and (b) evolution of the charge density in the dot containing 12 electrons for various external biases.

electrons splits the charge density centroid into two peaks situated on each side of the symmetry plan of the dot (see Figure 5.19a for 12 electrons or Figure 5.19b for 1 V). When an external bias is applied on the electrodes, the charge density is moved in a classical way in the direction of the increasing potential, corresponding to expected electrostatic result. As shown in Figure 5.19b, the more the potential difference increases, the more the charge centroid moves toward the edge of the dot.

Then, using the relationship given in (5.58), the total energy of the system has been computed and reported in Figure 5.20. These results are very close to those obtained by other groups on similar structures [20,21]. As a reminder, this energy takes into account the confinement energy of each electron and the Coulomb interaction between all electrons. Let us remark that the increase in the total energy due to the addition of a single electron significantly increases as the dot radius decreases. As an example, adding a sixth electron in a dot already containing five electrons increases the total energy of 500 meV (~$20k_BT$ at 300 K) if the dot radius is 6 nm. This value goes up to 3 eV when the radius is reduced to 1 nm (~$120k_BT$ at 300 K). As explained in Figure 5.10, this result clearly underlines the role played by the quantum effects in nanostructures and the necessity to use a full quantum approach when the dimension of the system studied is in the nanometer range.



FIGURE 5.20 Evolution of the total energy of the system when varying the dot radius and the number of electrons stored in the nanocrystal.

5.5.3 Comparison with the Metallic Approximation

To conclude this study, let us compare the electrical results obtained in the case of a metallic dot with those obtained in a full quantum treatment of the charge density. Here, we will compare the electrostatic potential obtained in both methods. Let us note that, in the metallic case, the electrostatic potential is constant over the entire dot whereas it varies along the dot volume in the semiconductor cases. For ease of comparison, let us define the mean electrostatic potential, V_{mean}, as

$$V_{\text{mean}} = \frac{1}{Q_0} \iiint_{\text{space}} \rho(\vec{r}) \times V(\vec{r}) \mathrm{d}^3\vec{r} \tag{5.60}$$

where Q_0 is the total electronic charge carried by the dot

$$Q_0 = -e \times N_{\text{elec}} \tag{5.61}$$

As defined in Equation 5.60, V_{mean} is nothing else than the mean potential over the whole structure weighted by the charge density.

Figure 5.21 compares the potential of the metallic dot with the mean potential in the semiconductor dot, V_{mean}, for different values of the dot radius, a, and various number of electrons stored in the dot. As it can be seen, there is a small difference between both electrostatic potential values. In each case, the difference observed in the potential is smaller than 200 mV and this difference decreases as the dot radius increase. Even for small dot size, a good agreement can be found when the number of electrons is low; a difference of less than 50 mV is observed when the dot is charged by one or two electrons, whatever the radius is.

This comparison leads to an interesting conclusion regarding the different levels of approximations developed in each approaches. As described in the previous section, the metallic approach gives immediate results thanks to the potential equation once the coupling capacitances between the dot and the electrodes are extracted. On the contrary, the Poisson–Schrödinger solver is an iterative process much more time-consuming but giving a more realistic description of the physical processes occurring inside the nanocrystal. However, both approaches can successfully coexist; we should keep in mind that a Poisson–Schrödinger resolution always start with an initial guess for the Poisson or the Schrödinger problem. Giving the fact that the metallic approach gives electrostatic results quite close to the final solution (see Figure 5.21), the metallic solution can be used as an initial guess for the iterative Poisson–Schrödinger solver to improve the speed of convergence.



FIGURE 5.21 Comparison between the metallic and the quantum approach regarding the calculation of the electrostatic potential of the nanocrystal. No external bias is applied to the structure ($V_1 = V_2 = 0$ V).

5.6 Conclusion

The purpose of this chapter was to study the electrostatic properties of individual nanodots embedded in a dielectric medium in a 3D configuration. To this purpose, various approaches have been developed and compared. The first one, based on a metallic floating nanoconductor, consist in solving the classical electrostatics equation with a rigorous semi-analytical model. As shown in Section 5.1, this method is able to predict the electrostatic potential of the floating conductor from a simple equation involving the coupling capacitance and the total charge carried by the dot. These results were successfully compared with FEM results obtained on the same structure with an excellent agreement. As a corollary, it should also be stated that the results derived from this approach are not sensitive to the length scale of the system and can be applied to structures of greater (or smaller) dimensions unless they have the same aspect ratio.

In the second part of this chapter, the focus is put on semiconductor nanocrystals. In this case, the quantum effects cannot be neglected any more like in the metallic case. Indeed, it has been shown that when the quantum well dimension falls in the nanometer scale, quantum confinement of the carriers in the nanocrystal is expected, even at ambient temperature. In this case, the electrostatic problem has been solved by a self-consistent resolution of Poisson and Schrödinger equations using the Hartree approximation. The approach developed in this work on a 3D structure by FEM gives the evolution of the charge density (and thus the electrostatic potential) in the volume of the structure with more physical insight than the rough metallic approximation. Moreover, the energy distribution of the carrier can be derived from the energy levels found for each bound state. However, as shown in the last part of this chapter, if we only need the mean electrostatic potential of the nanocrystal, the first metallic approach surprisingly gives very accurate results, even for nanocrystal with dimensions as small as few nanometers, whatever the quantity of charges in the dot.

We should keep in mind these last results as a conclusion. Indeed, they demonstrate that even macroscopic approaches can be used efficiently to predict some physical properties in nanostructures. For the typical case of the electrostatics of a semiconductor dot, there is, a priori no need to handle a complex approach based on a Poisson–Schrödinger solver if the only unknown is the electrostatic potential of the nanodot; the simple metallic approach can give accurate and immediate results if the precision required does not exceed few hundreds of millivolts.

However, if quantum transport between the electrodes and the dot, or even inter-dot transport, has to be studied, the knowledge of the energy distribution of the electrons over their bound-states becomes primordial and will need the use of a quantum treatment of the charge. This is the first point of perspective of this work.

The second evolution of this work would consist in taking into account an irregular shape of the dot. Indeed, in the range of sizes of the current nanodot devices, it is expected that the shape of the dot could have a great influence on the electrostatics behavior. Such a study has been yet proposed in Ref. [24] in a 2D case, combining semi-analytical approach and FEM computations. The results suggest that, extended to a 3D case, a spherical approximation could be sufficient for some configurations.

Appendix A: A Numerical Validation of the Semi-Analytical Approach

5.A.1 Convergence

The tests of convergence of the numerical code are done by repeating a numerical simulation and refining precision until the convergence is satisfactory. For the numerical computation of C_S, there are two numerical truncations in relation (5.15). The first one concerns the required value of the maximum order, $L_{\max}$, ensuring the convergence of the series. The value of $L_{\max}$ is physically constrained by the ratio a/λ_2 (the relative size of the dot seen from the plane). In practice, a value of around a few units is enough to ensure convergence (to fix the idea let us say that $L_{\max} \sim 10 \times a/\lambda_2$ gives good results). $L_{\max}$ leads the discretization over θ that appears in the integration. This integration is assured here by a simple Riemann series with a finite step $\delta\theta$. In practice, $\delta\theta \sim \pi(10L_{\max})^{-1}$ is sufficient. The second truncation is about the number of images taken in the summation over p. We denote by P_0 the greatest natural integer taken for the images. The difficulty of evaluating correctly this summation is the fact that the generic term is alternating because of the factor $(-1)^p$. Doing the summation described in the relations (5.15) and (5.18) for $p = \{-P_0, \ldots, -1, 1, \ldots, +P_0\}$ shows that the convergence is very slow. However, a little numerical arrangement allows a reasonable convergence of the series. Doing the same computation with an odd number of images $p = \{-P_0 -1, -P_0, \ldots -1, 1, \ldots P_0\}$ allows a convergence almost twice faster. An instance of this behavior is shown in Figure 5.22. We compare the results for the capacitance C_S versus the greatest order P_0 in the case of a summation over an even number of images and the case of a summation over an odd one. From $P_0 \sim 30$, the "odd" summation gives result that varies on the fourth digit. The "even" summation gives result still varying on the second digit around $P_0 \sim 40$, and still oscillating on the third digit for $P_0 \sim 70$. This difference between the two types of summation can be clearly explained expressing the potential on the electrodes, highlighting the property of symmetry of each term. The required value of P_0 is constrained by the ratio λ_2/h (the relative distance between the border of the dot and the electrodes), but we have to verify *a posteriori* the validity of this truncation, and did not found heuristic law to fix it.



FIGURE 5.22 Behavior of the result for the capacitance versus the greatest order P_0. Slashed and stars, the summation is done for $p^* = \{-57\ldots57\}$. Full and dot, for $p^* = \{-58\ldots57\}$. The configuration is the following: $t_1 = 6\,\text{nm}$, $t_2 = 10\,\text{nm}$, $a = 15\,\text{nm}$. $L_{\max} = 7$.

In Figure 5.23, we plot the result for C_S versus $L_{\max}$ for three different values of P_0. The summation over p^* is made for $p^* = -P_0 -1, \ldots -1, 1, \ldots, P_0$. In the left figure, we see that the influence of P_0 is weak. That is to say that each truncation can be treated separately. In the zoom, in the right side of the figure, we can notice that from $L_{\max} \geq 8$, the result varies only on the fourth significant digit for the both three curves. The curve corresponding to $P_0 = 15$ differs from ~0.3% from the other one corresponding to $P_0 = 75$. The difference between the curve $P_0 = 35$ and $P_0 = 75$ is on the fifth significant digit. In this instance, the dot is particularly big and near from the electrode ($t_1 \sim a/15$ and $2a/h \sim 0.65$). This kind of configuration is the worst case for convergence.

5.A.2 Numerical Validation with FEM Approach

The numerical implementation has been finally validated comparing the results provided by a FEM computation over the same configuration. The capacitance C_S and the coefficient α have been computed for various radius a, keeping t_1 and t_2 constant. The methodology involved for the extraction of C_S and α by FEM calculation is exhaustively described in Ref. [24]. Let us explore this methodology. For each radius, V_f is computed for a given Q_0 and for a given ΔV, by an iterative process stopped on the condition of charge (relation (5.3)). This operation is repeated for each value of Q_0 and ΔV. The linear regressions between Q_0 and V_f (with ΔV constant) and between V_f and ΔV (with Q_0 constant) give, respectively C_S and α. The entire process is repeated for a new radius, giving so the results exposed in Figure 5.24.



FIGURE 5.23 Behavior of the result for the capacitance versus the greatest order $L_{\max}$ for three values of P_0. Slashed and circle, the summation is done for $p^* = \{-76\ldots75\}$. Full, for $p^* = \{-36\ldots35\}$, dotted and square for $p^* = \{-16\ldots15\}$. The configuration is the following: $t_1 = 1\,\text{nm}$, $t_2 = 10\,\text{nm}$, $a = 15\,\text{nm}$. Left-hand side: global representation; right-hand side: zoom for values of $L_{\max} \geq 6$.



FIGURE 5.24 Comparison of FEM results with semi-analytical expression (denoted by SA). Left: Result for total capacitance versus the radius a for two sets of values for t_1 and t_2, right: Comparison of the coefficient α obtained by FEM and the value λ_2/h versus the radius a. For SA, $L_{\max} = 9$ and $P_0 = 80$.

The two configurations are the following:

1. $t_2 = 6\,\text{nm}$, $t_1 = 15\,\text{nm}$, $h = t_1 + t_2 + 2a$. We plot C_S versus a, a varying from 0.5 to 30 nm.
2. $t_2 = 4\,\text{nm}$, $t_1 = 15\,\text{nm}$, $h = t_1 + t_2 + 2a$. We plot C_S versus a, a varying from 0.5 to 30 nm.

In Figure 5.24 are presented the results obtained by the two methods. Concerning C_S, the agreement between the two methods is better than 1% for values of a up to 20 nm and 2% for higher values. This difference for great values of a may be explained by the methodology involved for the extraction of C_S by FEM calculation. For large values of radius the meshing of the structure becomes a critical parameter. Indeed the space has to be meshed far from the dot and meshed very finely near the dot. The FEM computation is based on the conservation of Q_0. For big sphere, the computed floating potential may be not sufficiently constant, because of the meshing problem. As a conclusion for this analysis, let us insist on the point that the two methods are completely different, and such an agreement is not frequent in numerical simulations.

For the coupling coefficient α, the agreement is not as satisfying as the previous comparison. We observe that the greatest difference between λ_2/h and α obtained by FEM is around 10% for configuration (2) and around 5% for configuration (1). The FEM calculation pains to extract α especially for great values of a and small value of t_2. This fact could be enlighted by the asymptotic behavior of the coupling coefficient for great values of a. Whatever the configuration the coefficient $\alpha = \lambda_2/(t_1 + t_2 + 2a)$ tends to the value 0.5, for large radius. This behavior appears earlier more quickly with SA than with FEM.

This instances seems to show that for great values of a ($a > t_2$), FEM may have some problems of accuracy for computing those two parameters.

To finish this appendix, let us say that a typical calculation of C_S by SA takes few seconds, with a non-optimized.

MATLAB®-like code, while the same extraction with FEM could takes several minutes.

References

1. Moore G.E., Cramming more components onto integrated circuits, *Electronics*, 38 (8), 114–117, April 1965.
2. *2007 ITRS ORTC, Public Conference*, Makuhari, Japan, http://www.itrs.net.
3. Noguchi M., Yaegashi T., Koyama H., Morikado M., Ishibashi Y., Ishibashi S., Ino, K., et al., A high-performance multi-level NAND Flash Memory with 43 nm-node floating-gate technology, in: *Proceedings of the International Electron Device Meeting* (*IEDM*), pp. 445–448, Washington, DC, December 10–12, 2007, doi: 10.1109/iedm.2007.4418969.
4. Ishii T., Osabe T., Mine T., Murai F., Yano K., Engineering variations: Towards practical single-electron (few-electron) memory, in: *Technical Digest of IEDM'00*, San Francisco, CA, December 11–13, 2000.
5. Wang H., Takahashi N., Najima H., Inukai T., Saitoh M., Hiramoto T., Effects of dot size and its distribution on electron number control in metal-oxide-semiconductor-field-effect-transistor memories based on silicon nano-crystal floating dots, *Jpn. J. Appl. Phys*., 40, 2038–2040, 2001.
6. Molas G., Deleruyelle D., DeSalvo B., Ghibaudo G., Gely M., Perniola L., et al., Degradation of floating gate reliability by few electron phenomena, *IEEE. Trans. Electron Devices*, 53 (10), 2610–2619, 2006.
7. Redaelli A., Pirovano A., Benvenuti A., Lacaita, A., Threshold switching and phase transition numerical models for change memory simulations, *J. Appl. Phys*., 103, 111101-1–111101-18, 2008.
8. Sawa A., Resistive switching in transition metal oxides, *Mater. Today*, 11 (6), 28–36, June 2008.
9. Naruke K., et al., Stress induced leakage current limiting to scale down EEPROM tunnel oxide thickness, in: *Proceedings of International Electron Device Meeting* (*IEDM*), pp. 424–427, San Francisco, CA, December 11–14, 1988.
10. Bez R., et al., Introduction to flash memory, *Proc. IEEE*, 91 (4), 489–502, 2003.
11. Tiwari S., et al., Volatile and non-volatile memories in silicon with nano-crystal storage, in: *Proceedings of the International Electron Device Meeting* (*IEDM*), pp. 521–524, IEDM 1995, Washington, DC, December 10–13, 1995.
12. De Salvo B., Gerardi C., Lombardo S., Baron T., Perniola L., Mariolle D., Mur P., et al., How far will silicon nanocrystals push the scaling limits of NVMs technologies? in: *Technical Digest of IEDM'03*, Washington, DC, December 8–10, 2003.
13. Muralidhar R., Steimle R.F., Sadd M., Rao R., Swift C.T., Prinz E.J., Yater J., et al., A 6 V embedded 90 nm silicon nanocrystal nonvolatile memory, in: *Technical Digest of IEDM'03*, Washington, DC, December 8–10, 2003.
14. Choi S., Choi H., Kim T.-W., Yang H., Lee T., Jeon S., Kim C., Hwang H., High density silicon nanocrystal embedded in SiN prepared by low energy (<500 eV) SiH_4 plasma immersion ion implantation for non-volatile memory applications, in: *Technical Digest of IEDM'05*, Washington, DC, December 5–7, 2005.
15. Sattler K., *Handbook of Thin Films Materials*, Volume 5: *Nanomaterials and Magnetic Thin Film*, H.S. Nalwa (ed.), Academic Press, New York, Chapter 2, pp. 61–97, 2002, ISBN: 0-12-512913-0.
16. Averin D.V., Korotkov A.N., Likharev K.K., Theory of single-electron charging of quantum wells and dots, *Phys. Rev. B*, 44 (12), 6199–6211, 1991.
17. De Salvo B., Ghibaudo G., Luthereau P., Baron T., Guillaumot B., Reimbold G., Transport mechanisms and charge trapping in thin dielectric/Si nano-crystals structures, *Solid-State Electron*., 45 (8), 1513–1519, 2001.
18. Han K., Kim I., Shin H., Characteristics of P-channel Si nano-crystal memory, *IEEE Trans. Electron Devices*, 48 (5), 874–879, 2001.
19. Busseret C., Ferraton S., Montès L., Zimmermann J., Granular description of charging kinetics in silicon nanocrystals memories, *Solid-State Electron*., 50 (2), 134–141, 2006.
20. Sée J., Dollfus P., Galdin S., Hesto P., Electronic properties of semiconductor quantum dots for coulomb blockade applications, *Physica E*, 21 (2–4), 496–500, 2004.
21. Sée J., Dollfus P., Galdin S., Theoretical investigation of negative differential conductance regime of silicon nanocrystal single-electron devices, *IEEE Trans. Electron Devices*, 53 (5), 1268–1273, 2006.
22. Cordan A.S., Leroy Y., Leriche B., Electrostatic coupling between nanocrystals in a quantum flash memory, *Solid-State Electron*., 50 (2), 205–208, 2006.
23. Ferry D.K., Goodnick S.M., *Transport in Nanostructures*, Section 4.2, p. 226, Cambridge University Press, Cambridge, U.K., 1999, ISBN: 0-521-66365-2.
24. Deleruyelle D., Micolau G., On the electrostatic behavior of floating nanoconductors, *Solid State Electron*., 52 (1), 17–24, 2008.
25. Ganguly U., Narayanan V., Lee C., Hou T., Kan E., Three-dimensional analytical modeling of nanocrystal memory electrostatics, *J. Appl. Phys*., 99, 114516-1–114516-6, 2006.
26. Godin Yu.A., Electrostatic problem of a conducting sphere in the field of a plane capacitor, *Sov. Phys. Tech. Phys*., 33 (6), June 1988 [*Zh. Tech. Fiz*., 58, 1216–1219, June 1988].

27. Pan Y., Chew W.C., Wan, L.X., A fast multipole-method-based calculation of the capacitance matrix for multiple conductors above stratified dielectric media, *IEEE Trans. Microw. Theory Tech.*, 49 (3), March 2001.
28. Jackson J.D., *Classical Electrodynamics*, 3rd edn., pp. 95–144, Wiley, New York, 1998 (Chapter 3), ISBN: 047130932X.
29. Ngakosso E., Saillard M., Vincent P., Electromagnetic diffraction by homogeneous cylinders of the field radiated by a dipole: A rigorous computation, *J. Electromagn. Waves Appl.*, 9, 1189–1205, 1995.
30. Petit R., *Ondes Electromagnétiques*, Masson Publications, 1988.
31. Aqua J.N., *Physique statistique des fluides coulombiens classiques et quantiques au voisinnage d'une paroi*, Thèse Université Paris XI Orsay, décembre 20, 2000, pp. 23–100, partie B.
32. Chew W.C., *Waves and Fields in Inhomogeneous Media*, Van Nostrand Reinhold, New York, 1990.
33. Cohen-Tannoudji C., Diu B., Laloé F., *Mécanique Quantique*, I Editions, Hermann, Paris, 1998, ISBN: 2-7056-6074-7.
34. Messiah A., *Quantum Mechanics*, Dover Publications, Mineola, NY, 1999, ISBN: 978-0486409245.
35. Sze S.M., *Physics of Semiconductor Devices*, John Wiley & Sons, New York, NJ, 1981, ISBN: 0-471-87424-8.
36. Kittel C., *Quantum Theory of Solids*, John Wiley & Sons, New York, 1987, ISBN: 0-471-62412-8.
37. www.comsol.com.
38. Deleruyelle D., Guiraud A., Micolau G., Study of electronic properties of nanocrystals from different point of view: From a simple 2D electrostatic approach to 3D Poisson Schrödinger simulations, in: *Proceedings of 2007 European COMSOL Conference*, Volume 2, pp. 636–641, Grenoble, France, October 23–24, 2007.
39. Deleruyelle D., Guiraud A., Bassani F., Theoretical and experimental investigation of electronic properties of semiconductor quantum-dots for non-volatile memory applications, in: *Proceedings of Nanoscale VI*, p. 146, Berlin, Germany, July 9–11, 2008.
40. Nougier J.P., *Méthodes de calcul numérique, vol. 2: Fonctions, équations aux dérivées*, pp. 206–212, Paris Hermès Science Publications, Paris, 2001 (Chapter 7), ISBN: 2-7462-0279-4.

6

Nanometer-Sized Ferroelectric Capacitors

6.1 Introduction 6-1
6.2 Fundamentals of Ferroelectricity 6-2
6.3 Deposition and Patterning 6-4
General Aspects • Deposition Techniques • Patterning • Current Trends in Deposition and Patterning
6.4 Characterization of Ferroelectric Films and Capacitors 6-8
Rutherford Backscattering Spectrometry • X-Ray Diffraction for Thin-Film Analysis • Ferroelectric Capacitors: *P-E* Hysteresis Loop Measurements • Scanning Probe Techniques: Atomic Force Microscopy and Piezoresponse Force Microscopy
6.5 Physical Phenomena in Ferroelectric Capacitors 6-13
Strain Effect • Depolarizing-Field Effect • Intrinsic Size Effect in Ultrathin Films
6.6 Future Perspective 6-17
6.7 Summary and Outlook 6-19
References 6-19

Nikolay A. Pertsev
A.F. Ioffe Physico-Technical Institute

Adrian Petraru
Christian-Albrechts-Universität Zu Kiel

Hermann Kohlstedt
Christian-Albrechts-Universität Zu Kiel

6.1 Introduction

Ferroelectric materials possess unique dielectric, piezoelectric, pyroelectric, and electro-optic properties, which make them suitable for applications in various microelectronic and micromechanical devices (Lines and Glass 1977). Owing to the sustained trend toward the miniaturization of electronic devices, ferroelectrics are mostly used nowadays in thin-film form (Dawber et al. 2005, Setter et al. 2006). In particular, the switching of spontaneous polarization in a ferroelectric film is employed in low-power and fast nonvolatile random access memories (FeRAMs) produced for smart cards (Scott 2000, Ishiwara and Okuyama 2004, Kohlstedt et al. 2005a). Owing to their high piezoelectric and pyroelectric responses, ferroelectric thin films are promising for applications in various sensors and actuators and as the heart of microelectromechanical systems (MEMS) that combine Si-technology with the latest achievements in micromechanics (Scott 2007).

Numerous experimental and theoretical studies performed during the past decade have demonstrated that the physical properties of ferroelectric thin films may be very different from those of bulk ferroelectrics. When the film thickness or the lateral size of a ferroelectric capacitor (Figure 6.1) is reduced down to the nanoscale range, these properties generally become size-dependent. Therefore, the physics of nanoscale ferroelectrics represents an exciting field of research in solid-state physics with a close link to device applications. Impressive progress made in this field is mainly the result of the following three recent achievements: (1) new theoretical investigations based on the phenomenological Landau theory of phase transitions (Landau et al. 1984) and the abinitio calculations of ferroelectric crystals and thin films; (2) tremendous improvement in the thin-film technology of complex oxides by using sophisticated deposition techniques and pattering; and (3) the advent of advanced analytical tools. The corresponding "research triangle" is sketched in Figure 6.1.

The phenomenological theory of bulk ferroelectrics was founded in the middle of the twentieth century and proved to be very successful in describing the physical properties of these materials (Devonshire 1954, Lines and Glass 1977). However, this mean-field theory, which is usually termed the Landau–Ginzburg–Devonshire theory, cannot be directly applied to thin-film and nanoscale ferroelectrics. The presence of surfaces (interfaces) and considerable lattice strains in these material systems require significant modifications of this thermodynamic theory (Kretschmer and Binder 1979, Pertsev et al. 1998). In particular, Pertsev et al. (1998) have shown that the substrate-induced lattice strains may give rise to new polarization states and phase transitions in epitaxial ferroelectric thin films. Subsequent experimental studies of single-crystalline films grown on dissimilar substrates confirmed many of the theoretical predictions and demonstrated the importance of strain effects in ferroelectric films (Schlom et al. 2007).



FIGURE 6.1 The "research triangle" summarizing the most important developments in the field of ferroelectric thin films and devices. Inside the triangle, a three-dimensional sketch of a ferroelectric capacitor is shown.

In addition to the advanced thermodynamic calculations, the past decade has been distinguished by the breakthrough in the first-principles density-functional theory investigations of ferroelectrics. Such theoretical studies, which do not involve any empirical input, were first performed for the two classical ferroelectrics, $BaTiO_3$ and $PbTiO_3$, and then were extended to other ferroelectric perovskites (Cohen 1992, King-Smith and Vanderbilt 1994, Waghmare and Rabe 1997). The treatment of ferroelectrics was greatly facilitated by the formulation of the correct definition of the electric polarization as a bulk quantity through the Berry-phase formalism of King-Smith and Vanderbilt (1993) and Resta (1994). This result and the related Wannier-function expression (King-Smith and Vanderbilt 1994) make it possible to calculate the spontaneous polarization and its derivatives after finishing the usual total-energy calculations (see the review paper by Dawber et al. (2005)).

Since the current computational limitations strongly restrict the size of material systems that can be directly calculated from first principles, the modeling based on first-principles results plays an important role in the theoretical studies of ferroelectrics as well. In particular, Monte Carlo simulations using an effective Hamiltonian approach make it possible to extend theoretical predictions to finite temperatures (Diéguez et al. 2004, Lai et al. 2005). It should be noted that the accuracy of first-principles calculations is still limited, which is clearly evidenced by the typical underestimation of the unit-cell size by about 1% and a substantial underestimation of the band gap of insulators. Despite these deficiencies and a considerable disparity between the size of systems studied theoretically and that of real devices, the ab initio calculations represent a very powerful tool for investigating bulk and thin-film ferroelectrics. Furthermore, by combining the first-principles results with the phenomenological Landau–Ginzburg–Devonshire theory, it is possible to develop a fruitful approach making use of the strength of both theories (Gerra et al. 2007, Tagantsev et al. 2008).

In parallel to important developments in the theoretical physics of ferroelectrics, we can notice essential improvements in thin-film growth and characterization techniques. Today, these improvements allow an atomic level of control of ferroelectric inorganic materials such as $BaTiO_3$ and $PbZr_xTi_{1-x}O_3$ (PZT) at the interfaces with lattice-matched substrates ($SrTiO_3$, $NdGaO_3$, $DyScO_3$, etc.) and electrodes made of metal oxides ($SrRuO_3$, $LaSr_xMn_{1-x}O_3$, etc.). Molecular beam epitaxy (MBE), a sophisticated method borrowed from semiconductor technology, pulsed laser deposition, and sputtering, is the work horse in the growth of thin-film ferroelectrics. Essential progress in the structural analysis by transmission electron microscopy and the advent of nanoscale scanning probe techniques of ferroelectric thin films led to a considerable progress in the thin-film deposition, as well as in the understanding of ferroelectrics at the nanometer and angstrom scale (Gruverman and Kholkin 2004, Schlom et al. 2007, Jia et al. 2008).

In this chapter, we first briefly discuss the basic physics of ferroelectric materials and then focus on nanoscale ferroelectric capacitors and future prospects in this research area. Because of the length limit, we restrict our discussion to the class of inorganic ferroelectrics and related devices. Readers interested in ferroelectric polymers, ferroelectric liquid crystals, and ferroelectric II–VI mixed compounds are referred to the relevant publications (Weil et al. 1989, Xu 1991).

This chapter is organized in the following way. In Section 6.2, the fundamentals of ferroelectricity are presented. Section 6.3 is devoted to the state-of-the-art deposition and pattering techniques, whereas Section 6.4 describes the various aspects of the structural and electrical characterization of ferroelectric thin films and capacitors. In Section 6.5, the most important physical phenomena occurring in ferroelectric capacitors are discussed. New developments and emerging trends in the field of nanoscale ferroelectric devices are briefly described in Section 6.6.

6.2 Fundamentals of Ferroelectricity

Ferroelectricity was discovered by J. Valasek in Rochelle salt in 1920 (Valasek 1921). The phenomenological definition of ferroelectricity in the textbook by Lines and Class reads: "A crystal is said to be ferroelectric material when it has two or more orientational states in the absence of an electric field. Any two of the orientation states are identical (or enantiomorphous) in crystal structure and differ only in electric polarization vector at null electric field" (Lines and Glass 1977). The crystal symmetry imposes restrictions on the existence of the spontaneous polarization $\mathbf{P}_s$. First, this property is not allowed in the presence of a center of symmetry, which excludes 11 centrosymmetric groups from the total set of 32 crystallographic point groups. Second, only 10 point groups out of the remaining 21 noncentrosymmetric ones posses a polar axis along which the spontaneous polarization may develop. This subset corresponds to *pyroelectric* crystals, where the build-in polarization manifests itself in temperature-induced changes of the total dipole moment of the unit cell. Ferroelectrics represents a subclass of pyroelectric crystals: they are distinguished from other pyroelectric materials by their ability to switch between two or more stable states with different spontaneous polarization under the action of sufficiently strong external electric field. Indeed, this switching field must be lower than the breakdown field of the material.

Currently, about 700 ferroelectric materials are known (Scott 2007), which can be divided into several groups in accordance with the microscopic origin of ferroelectricity and their atomic structure. The most important examples are ferroelectric oxides such as $BaTiO_3$ and $SrBi_2Ta_2O_9$, hydrogen-bonded ferroelectrics (e.g., KH_2PO_4), ferroelectric polymers like poly(vinylidenefluoride), and ferroelectric liquid crystals (Lines and Glass 1977, Xu 1991). There are many industrial applications of ferroelectric materials, ranging from $BaTiO_3$ capacitors to ferroelectric-liquid-crystal displays for flat TV screens.

In this chapter, we focus on ferroelectric oxides with the perovskite structure, i.e., with the crystal structure characteristic of the mineral $CaTiO_3$ found in the Ural Mountains and named "perovskite." The general chemical formula for perovskite oxides is ABO_3, where A and B represent two cations of very different sizes. In the cubic unit cell of a perovskite oxide, the A-type atoms are situated at the cube corners, the B-type atom sits at the cube center, and oxygen atoms are located at the face centers. In Figure 6.2, the unit cell of the perovskite oxide $BaTiO_3$ is shown schematically for the cubic and tetragonal phases. In the high-temperature cubic state, $BaTiO_3$ is indeed paraelectric with a zero dipole moment of the unit cell. Below about 120°C, stress-free bulk crystals of $BaTiO_3$ become ferroelectric owing to a small shift of the Ti^{4+} ion relative to the center of the surrounding oxygen cage, which leads to the appearance of dipole moment and lattice spontaneous polarization. Since the direction of this shift depends on temperature T, $BaTiO_3$ has three different ferroelectric phases: tetragonal ($10°C \leq T \leq 120°C$), orthorhombic ($-71°C \leq T \leq 10°C$), and rhombohedral ($T \leq -71°C$) (Jona and Shirane 1962).

The build-in switchable polarization **P** represents the most important physical characteristic of a ferroelectric material. In the thermodynamic theory of ferroelectrics, the polarization vector **P** is used as an *order parameter* and the additional Gibbs free energy density $\Delta G(\mathbf{P})$ of the ferroelectric phase is expanded in terms of the polarization components P_i ($i = 1, 2, 3$). For a stress-free tetragonal ferroelectric crystal subjected to an electric field **E** parallel to the polar x_3 axis ($P_1 = P_2 = 0$, $P_3 \neq 0$), the Gibbs free energy G_{ferro} can be written as

$$G_{\text{ferro}} = G_{\text{para}} + a_1 P_3^2 + a_{11} P_3^4 + a_{111} P_3^6 + \cdots - P_3 E_3,$$

where a_1, a_{11}, and a_{111} are the dielectric stiffness and higher-order stiffness coefficients of the centrosymmetric paraelectric phase at constant stress. The dielectric stiffness a_1 is given the linear temperature dependence $a_1 = (T - \theta)/(2\varepsilon_0 C)$, where θ and C are the Curie–Weiss temperature and constant and ε_0 is the permittivity of the vacuum. The minimization of $\Delta G(P_3)$ makes it possible to calculate the polarization P_3 of a homogeneously polarized crystal as a function of temperature T and applied field E_3. When the coefficient a_{11} of the fourth-order polarization term is positive, the spontaneous polarization $P_s = P_3$ ($E_3 = 0$) remains zero down to the transition temperature $T_c = \theta$, below which it increases gradually as $P_s \sim \sqrt{\theta - T}$. The energetics of this *second-order* ferroelectric phase transition is described schematically in Figure 6.3b. In contrast, at $a_{11} < 0$ and $a_{111} > 0$, the spontaneous polarization displays a step-like increase up to a value of $P_c = \sqrt{|a_{11}|/2a_{111}}$ at $T_c = \theta + \varepsilon_0 C a_{11}^2/(2a_{111})$. Therefore, a *first-order* ferroelectric phase transition takes place in this situation, as illustrated in Figure 6.3a.

Under an external field directed against the spontaneous polarization, the magnitude of $P_3(E_3)$ first gradually decreases with increasing field intensity E_3. When it reduces down to a certain minimum value P_{min}, the "antiparallel" polarization state becomes unstable. As a result, the polarization switches by 180° into the direction parallel to the applied field. In the case of ferroelectrics with a second-order transition, $P_{\text{min}} = P_s/\sqrt{3}$, and the critical switching field equals $E_{\text{th}} = -(4/3)a_1 P_{\text{min}} \sim (\theta - T)^{3/2}$. The field E_{th} represents the *thermodynamic coercive field* that corresponds to a homogeneous polarization reversal in the whole crystal. The polarization-field curve resulting from the thermodynamic calculations is hysteretic, as shown in Figure 6.4a. The theoretical hysteresis loop is qualitatively similar to the experimental ones, which differ mainly by a gradual polarization



FIGURE 6.2 Schematic representation of the unit cell of $BaTiO_3$ in the paraelectric cubic (a) and ferroelectric tetragonal (b) phases.



FIGURE 6.3 Temperature evolution of the free energy density as a function of polarization shown schematically for ferroelectrics with the first-order (a) and second-order (b) phase transition.



FIGURE 6.4 Theoretical (a) and measured (b) ferroelectric hysteresis loops. The theoretical dependence of the normalized polarization on the normalized applied field corresponds to a homogeneous polarization reversal in the whole crystal. The experimental polarization-voltage loop was measured for the 150 nm thick PZT film.

reversal seen in Figure 6.4b. The measured coercive fields E_c of bulk crystals, however, are typically several orders of magnitude lower than E_{th}, because the polarization switching develops in reality via the nucleation and growth of ferroelectric domains (Lines and Glass 1977).

When the size of a ferroelectric crystal is reduced down to a length scale comparable to the so-called *ferroelectric correlation length*, its physical properties generally become size-dependent. This feature is due to the fact that ferroelectricity is a collective phenomenon resulting from a delicate balance between long-range Coulomb forces (dipole–dipole interactions), which are responsible for the ferroelectric state, and a short-range repulsion favoring the paraelectric state (Lines and Glass 1977). The scaling of physical characteristics such as the remanent mean polarization $P_r = \langle P_3(E_3 = 0)\rangle$ and coercive field E_c is currently in the focus of experimental and theoretical studies in the field of nanometer-sized ferroelectric capacitors. The most important results of these studies will be discussed in Sections 6.4 and 6.5.

6.3 Deposition and Patterning

6.3.1 General Aspects

The deposition of thin films belongs to the heart of today's micro- and nano-electronics. In order to grow thin films with desired properties, several important issues have to be considered. Besides the choice of the deposition method, a number of process parameters are essential, such as the background pressure of the vacuum system, the deposition rate (measured in nm/s), the substrate material and temperature, and the composition of the material source. Furthermore, the process pressure is important, irrespective of the conditions in the chamber, i.e., the state of an ultra-high vacuum or the presence of a noble gas (typically argon) or reactive gases (oxygen or nitrogen). The basic principles of thin-film deposition are described in several textbooks (Chopra 1969, Maissel and Glang 1979, Bunshah 1994). Here we focus on the deposition of complex oxides by means of physical methods.

As already mentioned in the introduction, thin-film deposition techniques for the growth of heteroepitaxial oxides have made tremendous progress recently. The purpose of this section is to give a short overview of the current status of the MBE, pulsed laser deposition (PLD), and sputter deposition (SD). For chemical-based methods, such as metal-organic chemical vapor deposition (MOCVD), atomic layer deposition (ALD), and chemical solution deposition (CSD), we refer the reader to the relevant papers (Oikawa et al. 2004, Kato et al. 2007, Schneller and Waser 2007). We also note that ferroelectric polymers are deposited by either a spin-on technique or the Langmuir-Blodgett method (Ducharme et al. 2002).

Consider a planar ferroelectric capacitor sketched in Figure 6.1. The choice of materials for the substrate, electrodes, and ferroelectric layer strongly depends on the application or the research task. For the epitaxial growth of perovskite ferroelectrics, single-crystalline substrates having small lattice mismatches with these complex oxides are preferable. At present, the commercially available single crystals of $SrTiO_3$ are most popular, although other substrates such as MgO, $KTaO_3$, $GdScO_3$, and $DyScO_3$ have also been successfully employed. When the ferroelectric overlayer is commensurate with a dissimilar thick substrate, it appears to be strained to a certain extent defined by the mismatch in their in-plane lattice parameters. Above some critical thickness, however, these lattice strains start to relax due to the generation of misfit dislocations (see Section 6.4).

As for the electrodes, noble metals such as Pt, Ir (also IrO_2), and Ru are used in most device applications, e.g., in FeRAMs and MEMS (Kohlstedt et al. 2005a). On the contrary, conducting complex oxides were favored so far as electrode materials in the basic research studies of scaling effects. Prominent examples of such electrode materials are $SrRuO_3$, $LaSr_xMn_{1-x}O_3$, and $LaCa_xMn_{1-x}O_3$, which are routinely used in the complex-oxide heterostructures (Eom et al. 1992, Sun 1998). A comparison of the advantages and disadvantages of metal and oxide electrodes shows a delicate trade-off. Let us compare, for instance, Pt and $SrRuO_3$.

On the one hand, the resistivity of a sputtered thin-film Pt at room temperature (~10 μΩ cm) is much smaller than that of even a high-quality $SrRuO_3$ (≈300 μΩ cm). On the other hand, the screening-space-charge capacitance density, which is important for the stabilization of ferroelectricity in ultrathin films (Pertsev and Kohlstedt 2007), is equal to 0.9 F/m^2 for the $SrRuO_3$ electrode and only to 0.4 F/m^2 for the Pt electrode (Pertsev et al. 2007). This feature seems to make $SrRuO_3$ electrodes preferable for nanoscale ferroelectric capacitors. In addition, the electrode surface roughness, crystallographic orientation of the ferroelectric layer grown on a particular electrode, and the quality of the electrode–ferroelectric interface must be taken into account. Currently, conducting complex oxides are preferred for the fabrication of the bottom electrode, whereas the top electrode can be made of Pt or other noble metal as well. In the rest of this section, we focus on entirely complex-oxide heterostructures for ferroelectric capacitors.

6.3.2 Deposition Techniques

6.3.2.1 Molecular Beam Epitaxy

MBE has developed from a simple evaporation technique via the use of ultra-high vacuum (UHV) to avoid disturbances by residual gases and additional incorporation of various effusion (Knudson) cells as material sources. Figure 6.5 schematically shows an MBE system involving several material sources that allow controlled deposition of multi-element compounds. In contrast to the deposition of most semiconductor materials such as GaN, GaAs, and InP, the growth of oxides by MBE requires relatively high partial pressure of oxygen (~10^{-7} mbar) during the deposition. This is necessary to avoid the oxygen deficiency in the final film, which could seriously deteriorate the quality of a ferroelectric capacitor. Partial pumping, the use of reactive oxygen (e.g., ozone), and post-annealing of the films in a high-pressure oxygen atmosphere (several mbar) are used to supply the films with a sufficient amount of oxygen.

Owing to the UHV conditions in the MBE chamber, all UHV surface techniques can be employed. This feature, indeed, constitutes the strength of MBE (Haeni et al. 2000). This tool offers the highest degree of freedom to apply sophisticated in situ analytical techniques to study films during the growth and just after the deposition without breaking the vacuum. Complex MBE systems using low-energy electron microscopy (LEEM) and Auger electron spectroscopy (AES), for example, were developed (Habermeier 2007 and Clayhold et al. 2008). The standard technique currently is the reflection high-energy electron diffraction (RHEED), which allows control of the surface chemistry of the last layer during the deposition. This technique provides an opportunity to fabricate oxide films with a definite termination at the surface (e.g., the BaO or TiO_2 termination in $BaTiO_3$ films). Many groups successfully demonstrated this approach (Logvenov and Bozovic 2008) with similar oxide materials. An obvious research goal now is to find correlations between atomic terminations at ferroelectric–metal interfaces and the electrical properties of capacitors.



FIGURE 6.5 Schematic view of MBE system for the growth of multi-element-compound thin films (a) and a photograph of MBE chamber (b). (From Lettieri, J. et al., *J. Vac. Sci. Technol. A*, 20, 1332, 2002. With permission.)

An additional important feature of MBE is the low energy of deposited species. Indeed, the temperature of the material source in effusion cells or electron-beam evaporators does not exceed 3500 K. Hence, the corresponding thermal energy of the deposited species is about 300 meV. This value is an order of magnitude lower than the energies characterizing pulsed laser deposition and typical sputter deposition. Among available deposition techniques, MBE is the most flexible one with respect to the incorporation of analytical tools and offers the highest degree of atomic layer control. On the other hand, MBE systems are difficult to handle, considerable time is necessary for their maintenance, and, last but not least, special methods are needed to supply complex oxides with a sufficient amount of oxygen. Due to the highly complex machinery, experienced researchers working with MBE systems for years translated the acronym MBE as "many boring evenings."

6.3.2.2 Pulsed Laser Deposition

PLD is a very useful and flexible tool for growing oxide materials (Hubler and Chrisey 1994). A sketch of a PLD system is shown in Figure 6.6. A pulsed laser beam, from a KrF (248 nm) or ArF (193 nm) excimer laser, for example, is focused on a rotating target made of an oxide material (e.g., $BaTiO_3$, PZT, or $SrRuO_3$). The oxygen gas pressure during ablation can be varied from 10^{-7} to 0.5 mbar. Owing to the intense laser beam, a plasma containing energetic ions, electrons, neutral atoms, and molecules is formed. The energy density is in the range of 2–5 J/cm^2 at the target surface. As a result, the energy of the ablated material may reach values well above 10 eV at the substrate surface. The wavelength of the used laser beam may be 248 or 193 nm (at this UV wavelength, the absorption in the oxide target materials is sufficiently large). A repetition rate of several Hz and a pulse length of 25 ns represent typical parameters. Initially, a serious problem of the method was the formation of droplets on the substrate, which can easily deteriorate the device properties. Currently, various methods to reduce this effect are known, e.g., the time-of-flight selection of ablated material. PLD systems are widely used for basic research studies of thin films. The main advantage of this method is that a certain film stoichiometry can be easily achieved by PLD. Many targets (six or more) can be placed on the target carrousel holder. In this way, numerous materials can be deposited without time-consuming rearrangements of the deposition chamber or complicated source exchange procedures, as in the case of MBE or MOCVD.



FIGURE 6.6 Pulsed laser deposition system for the growth of oxide films: PLD setup scheme (a) and a photograph showing the ablation process and the plasma plume (b). (From Schlom, D., Cornell University, Ithaca, NY.)

6.3.2.3 Sputter Deposition

Plasma sputtering is a physical vapor deposition technique that has been known for 150 years since the time when W.R. Grove first observed the sputtering of surface atoms. Different sputtering techniques, such as dc- and rf-sputtering with or without a magnetron arrangement, have been used to grow a variety of materials. Figure 6.7a illustrates the principle of dc-sputtering. A potential of several hundred volts is applied between the target (cathode) and the heater (anode), accelerating positively charged ions toward the target. These accelerated particles sputter off the target material, which finally arrives at the substrate. The discharge is maintained because the accelerated electrons continuously collide with the gas circulating in the chamber and ionize new atoms.

For insulating targets such as ferroelectric ones, the dc-sputtering is not suitable. Insulating targets have to be sputtered using alternating electric fields to generate the plasma. Typically, an rf-frequency of 13.56 MHz is employed. This frequency is not a magic number, rather a frequency that is approved by the government for industrial purposes. A symmetrical arrangement of cathode and anode and the use of a low-frequency alternating field would result in similar sputtering and re-sputtering rates so that the film will not grow. In the case of a high-frequency alternating field, however, light electrons can respond to the field at this frequency, whereas heavy Ar^+ ions see only an average electric field (Kawamura et al. 1999). Moreover, the geometrical asymmetry between small cathodes (target side) and large anodes (heater and chamber) leads to a higher electron concentration at the former, resulting in a self-generated dc bias that accelerates Ar^+ ions toward the target.

The high-pressure sputtering technique of oxide materials was developed by Poppe et al. (1988) and served initially for the



FIGURE 6.7 Schematic representation of the dc-sputtering process showing the electrons, positive plasma ions (light gray), and neutral atoms (dark gray) moving toward cathode or anode (a) and a photograph of a high-pressure sputtering system (b). (From Rodríguez Contreras, J. et al., PhD thesis)

growth of oxide superconductors. A planar on-axis arrangement of the target and substrate is used, as shown in Figure 6.7b. A high sputtering pressure of 2.5–3.5 mbar, corresponding to a mean-free-path $\lambda_{\text{mean free}} = 6 \times 10^{-3}$ cm at 600°C and exceeding largely the pressure of 10^{-2} mbar used for conventional sputtering ($\lambda_{\text{mean free}} = 2$ cm at 600°C), leads to multiple scattering of the negatively charged oxygen ions accelerated toward the substrate. As a result of the thermalization of ions, the re-sputtering of the deposited films, which is caused by negatively charged ions, is negligible. This technique yields excellent thin films due to the low kinetic energy (as in the case of MBE) of sputtered particles.

A disadvantage of the high-pressure sputtering technique could be a low deposition rate of several nanometers per hour, which may lead to interdiffusion at heterogeneous interfaces. To enhance the deposition rate, a low ionization degree of less than 1% of the atoms in the plasma is increased by the use of magnetic fields forcing electrons onto helical paths close to the cathode, which leads to much higher ionization probability. This so-called magnetron sputtering can be employed for high-pressure sputtering (Poppe et al. 1988), as well as for conventional, low-pressure sputtering (Fisher et al. 1994). Sputtering is routinely used as a vapor deposition method for the growth of complex-oxide films.

6.3.3 Patterning

The patterning of oxide heterostructures represents an important step in the fabrication of ferroelectric capacitors with small lateral dimensions ranging from a few micrometers to tens of nanometers. As in many other areas of nanoelectronics, two different approaches exist for the device fabrication. A conventional approach relies on the well-established processes used in the modern semiconductor industry: deposition, lithography, and etching. Using these techniques sequentially, ferroelectric capacitors can be fabricated. It should be emphasized that this fabrication procedure employs the so-called *top-down* approach, where external tools are used to create a nanoscale device out of a larger structure. In contrast, the *bottom-up* approach is based on the self-organization of constituents or their positional assembly necessary for a desired nanodevice. Such techniques recently became very fashionable (Spatz et al. 2000) because they do not require advanced and expensive patterning tools. The bottom-up approach has had considerable success, but improvements are needed to achieve registered arrays of devices, such as those produced by the state-of-the-art complementary metal-oxide-semiconductor (CMOS) technology. In some works, mixed top-down and bottom-up methods were used to produce nanoscale ferroelectric dots and crystals (Kronholz et al. 2006, Szafraniak et al. 2008).

One of the simplest ways to fabricate ferroelectric capacitors is the lift-off technique. The main steps of this technique are shown in Figure 6.8a. First, the bottom electrode and the ferroelectric layer are deposited on a substrate. A subsequent photo-lithographic step defines the area of the capacitor. Next, the top electrode is deposited, for example, by the sputtering of Pt. After a lift-off in acetone, the metal with photoresist underneath is removed and the capacitor is ready for electrical characterization. Because the top interface is subjected to photoresist and chemical developer during this procedure, relatively poor electrical properties (e.g., large leakage) are observed here (Rodríguez et al. 2003a and Rodríguez Contreras 2004). The post-annealing of capacitors at high temperatures and in an oxygen atmosphere was successfully used to improve the electrical properties considerably (Schneller and Waser 2007).

The aforementioned drawback, however, can be avoided using another method, which involves the fabrication steps shown schematically in Figure 6.8b. Here the whole sandwich (bottom



FIGURE 6.8 Patterning of capacitors by lift-off technique (a) and ion beam etching (b). (Reprinted from Rodríguez Contreras, J. et al., *Appl. Phys. Lett.*, 83, 126, 2003a. With permission. American Institute of Physics.)



FIGURE 6.9 Patterning of tunnel junctions with the aid of photolithography and ion beam etching. (From Rodriquez Contreras, J. et al., *Mater. Res. Soc. Symp. Proc.*, 688, C8.10, 2002. With permission.)

electrode/ferroelectric/top electrode) is deposited without breaking the vacuum. Then the capacitor area is defined by a photolithographic process and dry-etching, typically using Ar ion beam milling. Again acetone is employed to remove the photoresist from the top electrode. Although this method delivers better electrical interface properties than the first one, etch residuals at the sidewalls of the mesa can cause short-circuiting along the sidewall from the top electrode to the bottom one. An etch stop right after reaching the top surface of the ferroelectric can avoid this problem in a simple way. Ion-beam etching is the preferred method for the studies of scaling effects, because it results in the smallest degradation at the top electrode–ferroelectric interface.

A more complex procedure should be used to pattern oxide tunnel junctions. As shown in Figure 6.9, three photo-mask steps in total allow the fabrication of tunnel junctions by conventional photolithography and ion-beam etching (Sun 1998). First, the whole layer sequence such as the $SrRuO_3$(20 nm)/$BaTiO_3$(2 nm)/$SrRuO_3$(20 nm) trilayer is deposited in situ. Using a photolithographic step and ion-beam milling, the shape of the bottom electrode is defined. Here the whole trilayer has to be etched down to the substrate. Next, the tunnel junction is defined by the second photo-mask step and an etching down to the bottom electrode. The subsequent deposition of SiO_2 is needed to isolate the surroundings of the mesa. A third photo-mask step and the deposition of the wiring layer complete the fabrication of a tunnel junction. Figure 6.9e shows the top view of the junction layout. The four-point probe arrangement, which avoids electrical artifacts during current-voltage measurements, is essential (Rodríguez et al. 2003b and Rodríguez Contreras 2004).

6.3.4 Current Trends in Deposition and Patterning

The physical vapor deposition methods described above make it possible to grow complex oxides with a high structural quality and a low surface roughness. Further developments in this field involve combinatorial PLD and MBE systems for the fabrication of epitaxial layers with composition gradients and wedge-like films with a thickness varying across the substrate (Nicolaou et al. 2002, Ohtani et al. 2005, Habermeier 2007). This interesting approach helps to reduce run-to-run uncertainties and allows the variation of certain film parameters in a single deposition run while keeping other conditions fixed.

New patterning methods can be developed as well, in particular, a combination of conventional top-down methods and bottom-up techniques. It should be noted that electron beam lithography has been used to produce capacitors with nanoscale dimensions (Szafraniak-Wiza et al. 2008). Focused ion-beam direct-writing techniques already showed their strength, but they suffer from sidewall contaminations at the mesa structure created by etching ions or atoms, e.g., Ga (Hambe et al. 2008).

6.4 Characterization of Ferroelectric Films and Capacitors

6.4.1 Rutherford Backscattering Spectrometry

Rutherford backscattering spectrometry (RBS) is an accurate nondestructive technique for measuring the stoichiometry, layer thickness, quality of interfaces, and crystalline perfection of thin films. RBS offers a quantitative determination of the absolute concentrations of different elements in multi-elemental thin films. A collimated mono-energetic beam of low-mass ions hits the specimen to be analyzed. Typically, He^+ ions with energy of 1.4 MeV are used in RBS experiments. A small fraction of the ions that impinge on the sample is scattered back elastically by the atomic nuclei and are then collected by a detector. The detector determines the energy of the backscattered ions, which provides an RBS energy spectrum. The RBS spectra describe the yield of backscattered particles as a function of their energy. The analysis of RBS spectra is done using modern software. A more detailed description of the technique is given by Chu et al. (1978).

In the so-called random experiments, the ion beam is not aligned with respect to the crystallographic directions of the specimen. The energy distribution of the collected ions provides information on the masses of atoms constituting the sample and on the thicknesses of deposited layers. Information on the sharpness of interfaces between these layers is given by the abruptness of the low-energy edge in the “random” spectrum.

Epitaxial films usually have the same major channeling axis as the substrate. The degree of epitaxy is determined from ion channeling experiments by a ratio of the elemental signals from the film for the channeled and random sample orientations. This ratio is called the “minimum yield,” χ_{min}, and its value provides information on the crystalline perfection of a film. Defects inside the film lead to higher values of χ_{min}.

6.4.2 X-Ray Diffraction for Thin-Film Analysis

X-ray diffraction (XRD) represents a powerful tool for the characterization of thin films. It can be used to determine whether the film grown on a crystalline substrate is amorphous, polycrystalline, or single-crystalline (epitaxial growth). Moreover, this technique makes it possible to determine the film thickness, lattice parameters, and the amount of strain in an epitaxially grown film with a high precision.

In particular, the 2θ scans performed at a fixed glancing incident angle of the incoming x-ray beam (in the range of 0.5°–2°) are suited for the investigations of polycrystalline films, since the spectrum contains only the peaks coming from the XRD of randomly oriented crystallites. (The single-crystal substrate does not contribute to the XRD because the Bragg condition is not satisfied for this angle of incidence.) For (001)-oriented epitaxial films, the normal θ–2θ scans reveal only the (00*l*) reflections. Thus, we can distinguish between an epitaxial film on a crystalline substrate and a polycrystalline one. Moreover, from the 2θ position of these reflections, one can precisely determine the out-of-plane lattice parameter. Once this parameter is measured, the in-plane lattice constants could be determined as well by finding the peak positions of the (*h*0*l*) reflections, for example. For ultrathin films, however, this becomes difficult because of the overlap with substrate peaks. Therefore, the grazing incidence diffraction, which is characterized by a low penetration depth of the incoming x-ray beam, has to be used to measure the in-plane lattice constants of ultrathin films.

The amount of strain in an epitaxial film can be nicely visualized by the reciprocal space maps measured, for example, around an asymmetric (103) reflection. These maps can indicate whether the film is fully strained by the substrate or is partially relaxed owing to the generation of misfit dislocations. Representative reciprocal space maps of strained and relaxed epitaxial $BaTiO_3$ films grown on $SrRuO_3$-covered $SrTiO_3$ substrates are given in Figure 6.10a and b. The out-of-plane and in-plane lattice parameters of $BaTiO_3$ films extracted from such maps are plotted in Figure 6.10c as a function of the film thickness *t* (Petraru et al. 2007). It can be seen that ultrathin films with $t < 30$ nm are commensurate with the substrate, which results in a compressive biaxial in-plane strain and an out-of-plane elongation of the unit cell.

The synchrotron x-ray scattering measurements give additional possibilities for the characterization of ultrathin films (Fong et al. 2005). In particular, it was demonstrated that electrode-free $PbTiO_3$ films grown on $SrTiO_3$ remain ferroelectric for thicknesses down to only 3 unit cells (Fong et al. 2004).

Finally, we note that the film thickness itself can be measured precisely using the x-ray specular reflectivity method based on interference fringes whose spacing is characteristic for this thickness (Fewster 1996). This method can be applied to films with any structure, crystalline or amorphous, but requires a flat surface over the region studied. It was demonstrated to work even



FIGURE 6.10 X-ray reciprocal space maps around the (103) Bragg reflection obtained for fully strained (a) and partially relaxed (b) $BaTiO_3$ films epitaxially grown on $SrRuO_3$-covered $SrTiO_3$. The film lattice parameters are plotted as a function of the film thickness in panel (c). (From Petraru, A. et al., *J. Appl. Phys.*, 101, 114106, 2007. With permission.)



FIGURE 6.11 (a) Interference fringes appearing in an x-ray specular reflectivity scan for the 27 nm thick LaNiO$_3$ film deposited on SrTiO$_3$. The film thickness was calculated from the spacing of these fringes. (b) High-angle finite-size oscillations occurring in the θ–2θ scan around the (001) peak of the BaTiO$_3$ film (7.5 nm thick) grown on SrRuO$_3$-covered SrTiO$_3$. The solid line shows the measured signal, whereas the dots denote the results of simulations.

in the case of ultrathin films with thicknesses down to 24 Å. The amplitude of oscillations depends mainly on the density contrast between the layers, and the number of oscillations correlates with the roughness of the surface and interfaces involved. In the case of rough surfaces, the average intensity of reflectivity decreases rapidly with an increasing 2θ angle (Nevot and Croce 1980). For epitaxial films, high-angle finite-size oscillations occurring in the θ–2θ scans around the (001) peak allow determination of the number of planes involved in the diffraction, and, therefore, of the film thickness (Schuller 1980). Examples of the low- and high-angle finite-size oscillations are given in Figure 6.11.



FIGURE 6.12 Experimental techniques for the measurement of polarization-voltage loops of ferroelectric capacitors: (a) Sawyer-Tower circuit allowing the visualization of ferroelectric hysteresis loops, and (b) an alternative method using a fast current-to-voltage converter, where the loop is obtained via the integration of measured electric current.

6.4.3 Ferroelectric Capacitors: *P-E* Hysteresis Loop Measurements

A ferroelectric capacitor usually displays a polarization-field (*P-E*) hysteresis loop similar to that shown in Figure 6.4b. There are several techniques that are used to measure the *P-E* loops of ferroelectric capacitors. The simplest method employs a circuit proposed by Sawyer and Tower, which is shown schematically in Figure 6.12a. The circuit consists of a fixed capacitor with known capacitance, the test ferroelectric capacitor, an oscilloscope, and a function generator. The method relies on the fact that two capacitors in a series have the same charge. The ac voltage created by the generator and the potential across the standard capacitor are shown on the x- and y-axes of the oscilloscope. The capacitance of the standard capacitor is chosen to be large enough so that the voltage drop across this capacitor is much smaller than the potential difference across the tested ferroelectric capacitor.

Another method uses a fast current-to-voltage converter connected in series with the ferroelectric capacitor (see the circuit shown in Figure 6.12b). In this case, the current-voltage curve is measured as a response of the ferroelectric capacitor to a triangular signal excitation. It is very useful to look at the switching current peaks that appear in this curve in order to distinguish the ferroelectric switching from artifacts, especially in the case of leaky ferroelectric samples. By numerical integration of the current over the time, the classical *P-E* hysteresis loop is obtained, from which the remanent polarization and the coercive field can be determined. The remanent polarization of nanoscale SrRuO$_3$/BaTiO$_3$/SrRuO$_3$ capacitors fabricated on the SrTiO$_3$ substrate is shown in Figure 6.13 as a function of the BaTiO$_3$ thickness t (Petraru et al. 2008). Remarkably, even at t = 3.5 nm, the strained BaTiO$_3$ film



FIGURE 6.13 Thickness dependence of remanent polarization in the SrRuO$_3$/BaTiO$_3$/SrRuO$_3$ ferroelectric capacitors measured at 77 K. (From Petraru, A. et al., *Appl. Phys. Lett.*, 93, 072902, 2008. With permission.)

remains ferroelectric and has a remanent polarization larger than the spontaneous polarization $P_s = 26\,\mu C/cm^2$ of bulk BaTiO$_3$. The coercive field E_c of BaTiO$_3$ capacitors relatively weakly depends on the thickness t (Jo et al. 2006b), which contrasts with a strong increase of E_c (Figure 6.14) in ultrathin PZT capacitors with Pt top electrodes (Pertsev et al. 2003b).

Ferroelectric capacitors are often rather leaky, because thin films, especially at small thicknesses, are not perfect insulators. The conduction here results from the Schottky injection or Fowler–Nordheim tunneling through the interfacial barrier followed by the charge transport across the film via the Poole–Frenkel conduction mechanism, space-charge-limited conduction, or variable range hopping (Dawber et al. 2005). The leakage contribution to the total current can be singled out with the aid of the positive-up negative-down (PUND) pulsed method (Smolenskii et al. 1984). It involves the application of a series of voltage pulses from a function generator and the measurement of the transient current response of a ferroelectric device, which allows the separation of different contributions. As a representative example, we consider the sequence of five train pulses shown in Figure 6.15. The first one (0) is the pre-polarization pulse—it puts the sample into a definite polarization state. The pulse (1) switches the polarization of the sample, and its current response is the sum of the ferroelectric displacement current caused by the switching of spontaneous polarization, the dielectric displacement current, and the leakage current. The pulse (2) has the same polarity but comes after a certain delay time. Therefore, in case of a stable polarization, the current response contains only the components arising from the dielectric response and leakage current. In order to find the switchable polarization (the quantity of primary interest), the current response due to pulse (2) is subtracted from the current created by pulse (1), and the result is numerically integrated over the measuring time. Moreover, this method makes it possible to study the stability of ferroelectric polarization against back-switching. To that end, we can vary the delay time between pulses (1) and (2) and determine the relaxation time of the polarization. A similar analysis can be done for currents resulting from pulses (3) and (4) applied to the capacitor with opposite polarization.

6.4.4 Scanning Probe Techniques: Atomic Force Microscopy and Piezoresponse Force Microscopy

Atomic force microscopy (AFM) is one of the most widely used scanning probe microscopy (SPM) techniques (Garcia and Perez 2002). The primary purpose of an AFM instrument is to quantitatively measure the roughness of various surfaces. The lateral and vertical resolutions are typically about 5 and 0.01 nm, respectively. An atomically sharp tip is scanned over a surface with feedback mechanisms that enable the piezoelectric scanners to maintain the tip at a constant force (to obtain height information) or height (to obtain force information) above the sample surface.

Tips are typically made of Si$_3$N$_4$ or Si and extend down from the end of a cantilever. The AFM head employs an optical



FIGURE 6.14 Coercive field of PZT 52/48 epitaxial films measured at 20 kHz and plotted versus the film thickness t (a) and the inverse of film thickness $1/t$ (b). The straight line in (b) shows a linear fit to the experimental data, whereas the curve in (a) is a guide to the eyes.



FIGURE 6.15 Measurements of switchable ferroelectric polarization by the PUND pulsed method. The excitation signal consists of five pulses denoted by thin lines, and the current response is shown by a thick line. The upper inset demonstrates the switching (1) and nonswitching (2) current responses. The integration of their difference gives the switchable polarization plotted in the lower inset.

detection system, in which the tip is attached to the bottom of a reflective cantilever. A laser diode is focused onto the back of this cantilever. As the tip scans the surface of a sample, the laser beam is deflected by the cantilever into a four-quadrant photodiode. In contact mode, feedback from the photodiode difference signal, through the software control from a computer, enables the tip to maintain either a constant force or a constant height above the sample. In the constant force mode, the piezoelectric transducer monitors real-time height variations. In the constant height mode, the deflection force acting on the tip is recorded. The instrument gives a topographical map of the sample surface by plotting the local sample height versus the horizontal probe tip position. For many soft materials like polymers and biological samples, the operation in contact mode often modifies or destroys the surface. These complications can be avoided using the tapping-mode AFM. In tapping mode, the AFM tip–cantilever assembly oscillates at the sample surface during the scanning. As a result, the tip lightly taps the surface while scanning and only touches the sample at the bottom of each oscillation. This prevents damage of soft specimens and avoids the "pushing" of specimens along the substrate. By using a constant oscillation amplitude, a constant tip–sample distance is maintained until the scan is complete. Tapping-mode AFM can be performed on both wet and dry surfaces.

Scanning probe microscopy techniques also offer several different possibilities for the investigation of domain patterns in crystals. For imaging domain structures in ferroelectrics, piezoresponse force microscopy (PFM) is most widely used nowadays (Figure 6.16). Introduced in 1992 by Güthner and Dransfeld (1992), the PFM method has been developed by several groups to visualize domain structures in ferroelectric thin films. It became a popular tool in the science and technology of ferroelectrics and is considered to be a main instrument for getting information on ferroelectric properties at the nanoscale. Several reviews on the SPM-based methods for the characterization of ferroelectric domains are available in the literature (Gruverman and Kholkin 2004, Kholkin et al. 2007).

Ideally, when a modulation voltage V is applied to a piezoelectric material, the vertical displacement of the probing tip, which is in mechanical contact with the sample, accurately follows the motion of the sample surface resulting from the converse piezoelectric effect. The applied voltage V generates an electric field $\mathbf{E}(\mathbf{r})$ in the ferroelectric film, which creates the lattice strain $\delta u_3 = d_{13}E_1 + d_{23}E_2 + d_{33}E_3$ in the film thickness direction. Here, d_{ij} are the local piezoelectric coefficients of the ferroelectric material, which depend on the polarization orientation. The strain field $\delta u_3(\mathbf{r})$ changes the film thickness at the tip position by an amount δt so that the local piezoresponse signal proportional to $\delta t(V)$ can be recorded. The amplitude of the tip vibration measured by the lock-in technique provides information on the effective piezoelectric coefficient $d_{33}^{\text{eff}} = \delta t / V$. The phase yields information on the polarization direction in a studied ferroelectric domain (Rodriguez et al. 2002). It should be noted that not only the surface electromechanical response but also the electrostatic forces could contribute to the measured signal in the PFM setup, which complicates the analysis of the PFM results. In particular, there exists a nonlocal contribution caused by the capacitive cantilever–sample interaction (Kalinin and Bonnell 2002).

Most PFM measurements are performed in a local-excitation configuration where the modulation voltage is applied between the bottom electrode and conductive SPM tip, which scans the bare surface of the film having no top electrode. In this case, the PFM image has a lateral resolution of about 10 nm (Gruverman et al. 1998). It should be noted that the electric field generated by the SPM tip in such film is highly inhomogeneous, which makes the *quantitative* analysis of the field-induced signal extremely difficult. In other words, PFM measurements on a sample



FIGURE 6.16 PFM setup for simultaneous measurements of the surface topography and the out-of-plane and in-plane piezoelectric responses of a ferroelectric sample. The cantilever deflection caused by the voltage-induced surface displacements is detected by a laser beam reflecting into a four-quadrant photodiode. The vertical and horizontal piezoresponses are determined with the aid of two lock-in amplifiers by demodulating the corresponding signals (a + c) – (b + d) and (a + b) – (c + d), respectively. The instrument is operated in a constant force mode.



FIGURE 6.17 Out-of-plane piezoelectric response of $SrRuO_3/PbZr_{0.2}Ti_{0.8}O_3/SrRuO_3$ capacitors measured by the PFM technique: (a) piezoelectric hysteresis loops obtained for five different film thicknesses, and (b) the piezoelectric coefficient d_{33} as a function of the film thickness. (From Nagarajan, V. et al., *J. Appl. Phys.*, 100, 051609, 2006, With permission.)

without extended top electrodes collect signals from a subsurface layer of unknown thickness that is a function of dielectric permittivity and contact conditions (Gruverman et al. 1998).

Alternatively, a ferroelectric film with a deposited top electrode may be studied at the expense of a lower lateral resolution. By applying a voltage to the SPM tip contacting the top electrode, a submicron variation of piezoelectric properties in PZT capacitors was demonstrated (Christman et al. 2000, Setter et al. 2006). Under these conditions, a homogeneous electric field is generated in a ferroelectric layer, and the electrostatic tip–sample interaction is suppressed. This approach allows the investigations of domain-wall dynamics and polarization reversal mechanisms in ferroelectric capacitors and quantitative studies of the scaling of piezoelectric properties in ultrathin ferroelectric films. In particular, it was found (Nagarajan et al. 2006) that the piezoelectric coefficient d_{33} of epitaxial $PbZr_{0.2}Ti_{0.8}O_3$ films sandwiched between $SrRuO_3$ electrodes decreases rapidly as the thickness is reduced from 20 to 5 nm (see Figure 6.17).

6.5 Physical Phenomena in Ferroelectric Capacitors

There are several physical effects that make the phase states and electric properties of thin-film ferroelectric capacitors different from those of bulk ferroelectrics. First, the ferroelectric film is generally subjected to an in-plane straining and clamping due to the presence of a dissimilar thick substrate. Second, an internal electric field exists in the capacitor, which depends on the electrode material and the film thickness. Third, the scaling of physical properties may result from the short-range interatomic interactions at the film–electrode interfaces. The current status of the theoretical description of these effects in thin films of perovskite ferroelectrics is given below.

6.5.1 Strain Effect

Owing to the electrostrictive coupling between lattice strains and polarization, the mechanical film–substrate interaction may strongly affect the physical properties of ferroelectric thin films (Pertsev et al. 1998). In a film deposited on a dissimilar thick substrate, the in-plane strains u_1, u_2, and u_6 are totally governed by the substrate, whereas the stresses σ_3, σ_4, and σ_5 are usually equal to zero. (We use the Voigt matrix notation and the reference frame with the x_3 axis orthogonal to the film surfaces.) Under such "mixed" mechanical boundary conditions, the equilibrium polarization state corresponds to a minimum of the modified thermodynamic potential $\widetilde{G}$ (Pertsev et al. 1998), but not of the standard elastic Gibbs function G (Haun et al. 1987). In the most important case of a film grown in the (001)-oriented cubic paraelectric phase on a (001)-oriented cubic substrate ($u_1 = u_2 = u_m$, $u_6 = 0$), the stability ranges of different polarization states can be conveniently described with the aid of two-dimensional phase diagrams, where the misfit strain $u_m = (b - a_0)/a_0$ and temperature T are used as two independent parameters (a_0 is the equivalent cubic cell constant of the free standing film and b is the substrate lattice parameter). Such "misfit strain-temperature" diagrams were developed with the aid of thermodynamic calculations for single-domain $BaTiO_3$, $PbTiO_3$, and $Pb(Zr_{1-x}Ti_x)O_3$ (PZT) films (Pertsev et al. 1998, 2003a). Since the substrate-induced strains lower the symmetry of the paraelectric phase from cubic to tetragonal, the film polarization state may be very different from the ferroelectric phases observed in the corresponding bulk material (see Figure 6.18).

At large negative misfit strains, films of perovskite ferroelectrics stabilize in the tetragonal c phase with the spontaneous polarization $\mathbf{P}_s$ orthogonal to the film–substrate interface, whereas at large positive strains the orthorhombic aa phase forms, where $\mathbf{P}_s$ is directed along the in-plane face diagonal of the prototypic cubic cell. At low temperatures, the stability ranges of the c and aa phases are separated by a "monoclinic gap," where the monoclinic r phase with three nonzero polarization components P_i becomes the energetically most favorable state. These predictions of the thermodynamic theory were confirmed by the first-principles calculations (Bungaro and Rabe 2004, Diéguez et al. 2004).

It should be emphasized that the orthorhombic and monoclinic phases do not exist in the bulk $PbTiO_3$ crystals, where only the tetragonal ferroelectric state is stable (Haun et al. 1987). In the case of $BaTiO_3$, the aa phase may be compared with the orthorhombic phase forming in the bulk crystal in the low-temperature range between 10°C and –71°C, whereas the r phase can be regarded as a distorted modification of the rhombohedral phase that exists in a free crystal below –71°C (Jona and Shirane 1962).

The most remarkable manifestation of the strain effect appears in thin films of strontium titanate. In a mechanically free state, bulk $SrTiO_3$ crystals remain paraelectric down to zero absolute temperature despite a strong softening of the transverse optic polar mode near $T = 0\,K$ (Müller and Burkard 1979). The thermodynamic calculations show that this "incipient ferroelectricity" exists in epitaxial $SrTiO_3$ films grown on dissimilar cubic substrates only at small misfit strains ranging from -2×10^{-3} to -2×10^{-4} (Pertsev et al. 2000). Outside this "paraelectric gap," the ferroelectric phase transition takes place in the $SrTiO_3$ film at a finite temperature, which rises rapidly with the increase of the strain magnitude. The predicted phenomenon of strain-induced ferroelectricity was observed experimentally in $SrTiO_3$ films grown on (110)-oriented $DyScO_3$, which were found to display ferroelectric properties at room temperature (Haeni et al. 2004).



FIGURE 6.18 Misfit strain-temperature phase diagrams of single-domain $BaTiO_3$ (a) and $PbTiO_3$ (b) thin films epitaxially grown on (001)-oriented cubic substrates. The second- and first-order phase transitions are shown by thin and thick lines, respectively. (From Pertsev, N.A. et al., *Phys. Rev. Lett.*, 80, 1988, 1998. With permission.)

The strain-induced increase of the temperature T_c, at which the paraelectric to ferroelectric phase transition takes place, is characteristic of all studied perovskite ferroelectrics (Pertsev et al. 1998, 2003a). In addition, the two-dimensional clamping of the film by a thick substrate may change the order of this transition (Pertsev et al. 1998). Strong dependence of T_c on the misfit strain u_m explains the very high transition temperatures observed in epitaxial films grown on dissimilar substrates (Choi et al. 2004, He and Wells 2006).

The magnitude of the spontaneous polarization is also sensitive to the lattice strains. This effect is especially pronounced in ferroelectric films grown on "compressive" substrates ($u_m < 0$), where the polarization $\mathbf{P}_s$ is orthogonal to the film surfaces. For fully strained $BaTiO_3$ films grown on $SrTiO_3$ ($u_m = -2.6\%$), the thermodynamic theory predicts $P_s = 35\,\mu C/cm^2$, which is close to the experimental values of $43–44\,\mu C/cm^2$ (Kim et al. 2005, Petraru et al. 2007). Remarkably, the film polarization exceeds the polarization $P_b = 26\,\mu C/cm^2$ of bulk $BaTiO_3$ significantly. At the same time, the strain sensitivity of polarization in highly polar Pb-based perovskites, where the ferroelectric ionic displacements are already large in the bulk, is relatively low (Lee et al. 2007).

The enhancement of polarization P_s and the decrease of the in-plane permittivity ε_{11} in the strained *c* phase (Koukhar et al. 2001) should lead to a considerable increase of the coercive field E_c in thin films (Pertsev et al. 2003b). From the Landauer model of domain nucleation (Landauer 1957) it follows that $E_c \sim \gamma^{6/5}/\left(\varepsilon_{11}^{1/5} P_s^{3/5}\right)$, where $\gamma \sim P_s^3$ is the domain-wall energy. Hence, the coercive field $E_c \sim P_s^3/\varepsilon_{11}^{1/5}$ of $BaTiO_3$ films grown on $SrTiO_3$ ($\varepsilon_{11} \approx 170$) may be about eight times larger than that of the bulk crystal ($\varepsilon_{11} \approx 3600$). Although it is certainly a very strong increase, the strain effect alone cannot explain the observed drastic difference between the measured coercive fields $E_c \sim 150–300\,kV/cm$ of epitaxial $BaTiO_3$ films (Jo et al. 2006b, Petraru et al. 2007) and the bulk $E_c \sim 1\,kV/cm$.

Finally, it should be noted that ferroelectric properties of epitaxial thin films may strongly depend on the orientation of the crystal lattice with respect to the substrate surface. In particular, the phase states and dielectric properties of single-domain $PbTiO_3$ films with the (111)-orientation of the paraelectric phase were found to be very different from those of the (001)-oriented films (Tagantsev et al. 2002).

6.5.2 Depolarizing-Field Effect

When the polarization charges $\rho = -\text{div}\,\mathbf{P}$ existing at the film surfaces are not perfectly compensated for by other charges, an internal electric field appears in the ferroelectric layer (Figure 6.19). This "depolarizing" field $\mathbf{E}_{\text{dep}}$ may be significant even in short-circuited ferroelectric capacitors with perfect interfaces because the electronic screening length in metals is finite (Guro et al. 1970, Mehta et al. 1973).

For a homogeneously polarized film, the electrostatic calculation gives $E_{\text{dep}} = -P_3/(\varepsilon_0\varepsilon_b + c_i t)$, where P_3 is the equilibrium out-of-plane polarization in the film of thickness t, ε_0 is the permittivity of the vacuum, $\varepsilon_b \sim 10$ is the background dielectric constant of a ferroelectric material (Tagantsev and Gerra 2006), and c_i is the total capacitance of the screening space charge in the electrodes per unit area (Ku and Ullman 1964). When $P_1 = P_2 = 0$ (the *c* phase), the polarization $P_3(t)$ can be calculated from the nonlinear equation of state $\partial\tilde{G}/\partial P_3 = 0$ written for a strained film with an internal field E_{dep}. Since the capacitance c_i affects the polarization only via the product $c_i t$, the dependencies $P_3(t)$ corresponding to different electrode materials can be described by one universal curve $P_3(t_{\text{eff}})$. Here the effective film thickness t_{eff} may be defined as $t_{\text{eff}} = (c_i/c_1)t$, where $c_1 = 1\ F/m^2$.



FIGURE 6.19 Imperfect screening of polarization charges in a ferroelectric capacitor. Distribution of the electrostatic potential φ is shown schematically for the case of dissimilar electrodes kept at a bias voltage compensating for the difference of their work functions. (From Pertsev, N.A. and Kohlstedt, H., *Phys. Rev. Lett.*, 98, 257603, 2007. With permission.)

Figure 6.20 shows the dependencies $P_3(t_{\text{eff}})$ calculated for fully strained PZT 50/50 and $BaTiO_3$ films grown on $SrTiO_3$ (Pertsev and Kohlstedt 2007). It can be seen that the spontaneous polarization decreases in thinner films and vanishes at a critical film thickness t_0. In the case of capacitors with $SrRuO_3$ electrodes ($c_i = 0.444\,F/m^2$), the thickness t_0 is about 2 nm for PZT 50/50 films and about 2.6 nm for $BaTiO_3$ films. However, the size-induced phase transition at t_0, also predicted by the first-principles calculations (Junquera and Ghosez 2003), cannot be observed in reality since at a slightly larger film thickness $t_c < 3\,nm$ the single-domain ferroelectric state becomes unstable and transforms into the 180° polydomain state (Pertsev and Kohlstedt 2007).

The experimental studies of ultrathin $BaTiO_3$ films (Kim et al. 2005, Petraru et al. 2008) showed that the remanent polarization decreases monotonically with decreasing thickness at $t < 30\,nm$, where the misfit strain becomes constant. This behavior is similar to the dependence shown in Figure 6.20, but the thermodynamic theory does not provide a precise quantitative description of the experimental data (Kim et al. 2005, Petraru et al. 2008). The first-principles calculations performed by Junquera and Ghosez (2003) also cannot explain the measured dependence quantitatively (Kim et al. 2005).



FIGURE 6.20 Thickness dependence of the out-of-plane polarization and depolarizing field in ultrathin Pb(Zr$_{0.5}$Ti$_{0.5}$)O$_3$ (a) and BaTiO$_3$ (b) films epitaxially grown on SrTiO$_3$. The misfit strain is taken to be -39×10^{-3} for Pb(Zr$_{0.5}$Ti$_{0.5}$)O$_3$ films and -26×10^{-3} for BaTiO$_3$ films; T = 25°C. The dashed line shows the film thickness below which the single-domain state becomes unstable.

For BaTiO$_3$ capacitors with SrRuO$_3$ electrodes, the depolarizing field E_{dep} has been evaluated experimentally as well and was found to increase dramatically with decreasing film thickness (Kim et al. 2005). Such a strong rise is consistent with the theoretical thickness dependence of E_{dep} shown in Figure 6.20, which was calculated with the account of the polarization variation $P_3(t_{eff})$. The predicted saturation of the depolarizing field and its decrease in ultrathin films, however, were not observed. In this thickness range, the single-domain state becomes unstable (Pertsev and Kohlstedt 2007), and the mean value of the depolarizing field vanishes due to the formation of 180° domain structure.

The presence of a depolarizing field in a capacitor is expected to affect the shape of polarization-voltage (*P-V*) hysteresis loops and the magnitude of coercive fields (Tagantsev and Gerra 2006, Jo et al. 2006a,b). Indeed, a simple calculation shows that imperfect compensation of polarization charges at the interfaces not only reduces the remanent polarization, but also leads to a tilt of the hysteresis loop (Tagantsev and Gerra 2006). The influence of E_{dep} on the magnitude of the coercive field seems to be less pronounced. An accurate electrostatic modeling of the polarization switching on the macroscopic level indicates that E_c reduces with decreasing film thickness, but only when the *P-V* loop is not saturated (Tagantsev and Gerra 2006). In the limit of high amplitudes of the driving field applied to a capacitor, the influence of the depolarizing field on E_c disappears. This feature is explained by the absence of voltage drop across the metal–ferroelectric interface at $E = E_c$, where the macroscopic polarization $P(E)$ goes to zero by definition.

At the same time, Jo et al. (2006a,b) proposed that the depolarizing field may strongly reduce the potential barriers hindering polarization switching in ultrathin films. Such reduction may happen at the early stage of switching, when the macroscopic polarization P is large, but the influence of E_{dep} becomes negligible in a film with $P = 0$. Therefore, it is not clear whether the coercive field changes. It would decrease if the switching develops as an "avalanche" process after the nucleation of a few reversed domains. On the contrary, the change of E_c should be small when the applied field must increase significantly in the course of switching to facilitate further domain nucleation or domain-wall motion.

It should be noted that the nucleation of reversed domains in a perfect bulk crystal is impossible since the activation energy is many orders of magnitude larger than the thermal energy (Landauer's paradox). Jo et al. (2006a) suggested that such "homogeneous" domain nucleation becomes possible in ultrathin ferroelectric films, where the field-dependent activation energy decreases dramatically due to strong depolarizing fields. This conclusion, however, is based on a rough estimate of the activation energy obtained in the approximation of a homogeneous depolarizing field, which is valid for a single-domain film only.

Domain nucleation is evidently easier near crystal surfaces, ferroelectric–electrode interfaces, and lattice defects. Gerra et al. (2005) proposed that the interface coupling between a ferroelectric layer and electrodes changes its sign after the polarization reversal and, therefore, stimulates the switching. According to their model, the surface-stimulated nucleation may reduce the coercive field of BaTiO$_3$ down to a value two orders of magnitude smaller than the thermodynamic coercive field. High local electric fields $E_{loc} \gg E$ created by spikes on the electrodes may also permit the domain formation at small applied fields E. Besides, residual domains probably exist in ferroelectric films, especially in polycrystalline ones. The growth of these domains may play an important role in the polarization switching, as it happens in ferroelectric polymers (Pertsev and Zembilgotov 1991).

6.5.3 Intrinsic Size Effect in Ultrathin Films

Since the unit cells adjacent to the film–electrode interfaces have an atomic environment different from that of the inner cells, the ferroelectric polarization may depend on the film thickness even in the absence of a depolarizing field. This "intrinsic" size effect can be described with the aid of a modified thermodynamic theory based on the concept of extrapolation length (Kretschmer and Binder 1979). In this theory, the total energy of the ferroelectric layer involves an additional surface contribution, and the polarization distribution across the film, in general, is taken to be inhomogeneous.

In the most important case of the (001)-oriented film grown on a compressive substrate ($P_1 = P_2 = 0$, $P_3 \neq 0$), the polarization profile $P_3(x_3)$ can be calculated from the Euler–Lagrange equation (Zembilgotov et. al. 2002). For a film having the same atomic terminations at both surfaces and sandwiched between identical electrodes, the boundary conditions can be written as $\mathrm{d}P_3/\mathrm{d}x_3 = P_b/\delta$ at $x_3 = 0$ and $\mathrm{d}P_3/\mathrm{d}x_3 = -P_b/\delta$ at $x_3 = t$, where P_b is the polarization value at the film boundaries and δ is the extrapolation length. The polarization suppression (enhancement) near the film surfaces is described by positive (negative) values of the extrapolation length. In a weakly conducting ferroelectric, such as $BaTiO_3$ or $PbTiO_3$, the inner polarization charges $\rho = -\mathrm{d}P_3/\mathrm{d}x_3$ are largely compensated by charge carriers so that the associated depolarizing field should be negligible. In this case, the spatial scale of polarization variations is determined by the ferroelectric correlation length $\xi^* = \sqrt{g_{11}/|a_3^*|}$ of a strained film, and the strength of the intrinsic size effect is governed by the ratio $\xi^*/|\delta|$. (Here g_{11} and $a_3^*(u_m)$ are the coefficients of the gradient term and the renormalized second-order polarization term in the free energy expansion, respectively.)

The numerical calculations demonstrate that the polarization suppression in the surface layers reduces the temperature T_c of ferroelectric transition at a given misfit strain u_m. This reduction, however, is significant only in ultrathin films with thicknesses about a few $\xi^*(T = 0)$. Below the transition temperature $T_c(u_m)$, the mean polarization reduces with decreasing film thickness and vanishes at a critical thickness $t_c \approx \xi^*$ (Zembilgotov et al. 2002). Thus, the intrinsic surface effect may lead to a size-induced ferroelectric to paraelectric transformation.

Since the discussed thermodynamic theory is a continuum theory, it is valid only when the characteristic length ξ^* of the polarization variations is larger than the interatomic distances. In the case of a negligible depolarizing field, this condition is satisfied at least near the transition temperature T_c because the coefficient a_3^* goes to zero at this temperature (Pertsev et al. 1998). The situation, however, changes dramatically in a perfectly insulating ferroelectric, where the uncompensated polarization charges $\rho = -\mathrm{div}\,\mathbf{P}$ inside the film create a nonzero depolarizing field (Kretschmer and Binder 1979, Tagantsev et al. 2008). The characteristic length of polarization variations becomes $\xi_d^* = \sqrt{g_{11}/\left|a_3^* + (\varepsilon_0\varepsilon_b)^{-1}\right|}$, which, in contrast to ξ^*, does not increase significantly near T_c. Since $\xi_d^* \sim 0.1\,\mathrm{nm}$ only, the continuum approach based on the concept of extrapolation length cannot be used to describe the surface effect in perfectly insulating perovskite ferroelectrics (Tagantsev et al. 2008).

In the latter case, however, the ferroelectric film may be assumed to be homogeneously polarized in the thickness direction, and the intrinsic size effect can be described with the aid of a phenomenological approach as well (Tagantsev et al. 2008). To that end, the film free energy is written as the sum of the "bulk" and "surface" contributions, each represented by a polynomial in terms of ferroelectric polarization. In general, the surface contribution should involve not only the even-power terms, but also the odd-power terms, because the surface breaks the inversion symmetry of the ferroelectric (Levanyuk and Sigov 1988, Bratkovsky and Levanyuk 2005). However, when the film–electrode interfaces are identical, the linear term vanishes and the surface energy can be approximated by a quadratic polarization term. The coefficient of this term may be evaluated from the comparison of the phenomenological theory with the results of first-principles calculations performed for ultrathin ferroelectric films. For $BaTiO_3$ capacitors with $SrRuO_3$ electrodes, this procedure reveals that the surface energy is positive (Tagantsev et al. 2008), which implies the polarization suppression at the interfaces.

In other metal/ferroelectric/metal heterostructures, however, polarization could be enhanced near the interfaces. Such enhancement was demonstrated by the first-principles-based calculations performed for ultrathin $PbTiO_3$ and $BaTiO_3$ films (Ghosez and Rabe 2000, Lai et al. 2005). The short-range interactions between the film and electrodes must be also taken into account to prove that this effect exists in ferroelectric capacitors as well. The importance of ionic displacements in the boundary layers of $SrRuO_3$ electrodes for the stabilization of ferroelectricity in ultrathin films was revealed by the first-principles investigations (Sai et al. 2005, Gerra et al. 2006).

6.6 Future Perspective

When the thickness of the ferroelectric layer in a biased capacitor becomes as small as a few nanometers, the quantum mechanical electron tunneling across the insulating barrier should become significant (Kohlstedt et al. 2005b, Zhuravlev et al. 2005a). Since the tunnel current exponentially depends on the barrier thickness, the crossover from a capacitor to a *tunnel junction* takes place near some threshold thickness. The presence of spontaneous polarization in a ferroelectric barrier and its piezoelectric properties are expected to make the current-voltage (*I-V*) characteristic of a ferroelectric tunnel junction (FTJ) very different from those of conventional tunnel junctions involving nonpolar dielectrics (Kohlstedt et al. 2005b and Rodríguez Contreras 2004). Theoretically, the junction conductance can change strongly after the polarization reversal in the barrier so that the FTJs are promising for the memory storage with nondestructive readout. For the memory applications, asymmetric FTJs with dissimilar electrodes seem to be preferable since such junctions should exhibit much larger conductance on/off ratios (Kohlstedt et al. 2005b, Zhuravlev et al. 2005a). This feature is due to the fact that here the mean barrier height changes after the polarization reversal by the amount $\Delta\phi \cong eP_3(t)(c_{m2}^{-1} - c_{m1}^{-1})$, where c_{m1} and c_{m2} are the capacitances of two electrodes and e is the electron charge.

The ferroelectric tunnel barrier may also be combined with ferromagnetic electrodes. For such a *multiferroic* tunnel junction (MFTJ), new functionalities may be expected since the tunneling probability becomes different for the spin-up and spin-down electrons owing to the exchange splitting of electronic bands in ferromagnetic electrodes. In particular, Zhuravlev et al. proposed a new spintronic device, where an electric current is injected from a diluted magnetic semiconductor through the ferroelectric barrier to a normal (nonmagnetic) semiconductor (Zhuravlev et al. 2005b). Their theoretical calculations indicated that the switching of ferroelectric polarization in the barrier may change the spin polarization of the injected current markedly, which provides a two-state electrical control of the device performance.

When both electrodes are ferromagnetic, the tunnel current becomes dependent on the mutual orientation of the electrode magnetizations. This phenomenon, which is termed *tunneling magnetoresistance* (TMR), is important for the applications in spin-electronic devices such as magnetic sensors and magnetic random-access memories. Since the TMR ratio depends not only on the properties of ferromagnetic electrodes, but also on the barrier characteristics (Slonczewski 1989), it may be sensitive to the orientation of the ferroelectric polarization in the MFTJ. This supposition was confirmed by the theoretical calculations performed for junctions involving two magnetic semiconductor electrodes (Zhuravlev et al. 2005b). It was shown that, under certain conditions, the MFTJ works as a device that allows the switching of TMR between positive and negative values.

The experimental realization of ferroelectric and multiferroic tunnel junctions, however, is a task with many obstacles because it requires the fabrication of ultrathin films retaining pronounced ferroelectric properties at a thickness of only a few unit cells. Moreover, the ferroelectric state with a nonzero net polarization must be stable at such a small thickness and switchable by a moderate external voltage. In our opinion, reliable FTJs showing resistive switching in the tunneling regime have not been fabricated yet, despite several attempts made in this direction (Rodríguez et al. 2003b, Gajek et al. 2007). The observation of a hysteretic *I-V* curve or resistance jumps after short-voltage pulses alone is not sufficient to prove the existence of an FTJ (Kohlstedt et al. 2008). Hysteretic *I-V* curves were also measured for *non*ferroelectric $LaSr_xMn_{1-x}O_3/SrTiO_3/LaSr_xMn_{1-x}O_3$ tunnel junctions and explained by other effects (Sun 2001). Further experiments are necessary to demonstrate the functioning of FTJs unambiguously.

In case the above challenges will be overcome in the future, a number of new exciting opportunities for technological applications and interesting physical phenomena are anticipated. Figure 6.21 summarizes the variety of novel functional oxide tunnel junctions. Here, the Josephson tunnel junctions with a ferroelectric or multiferroic barrier are included as well. The influence of a ferroic tunnel barrier on the Cooper pair and quasiparticle tunneling might lead to interesting new physics. Besides oxide materials, ferroelectric polymers such as PVDF and P(VDF-TrFE) (Xu 1991, Bune et al. 1998) can be incorporated in low-temperature superconducting Josephson junctions [e.g., Nb/Al-AlO_x-P(VDF-TrFE)/Nb] (Huggins and Gurvitch 1985) and in magnetic tunnel junctions [e.g., Co_xFe_{1-x}/AlO_x-P(VDF-TrFE)/$Ni_{20}Fe_{80}$] (Moodera et al. 1995). In principle, one would expect the appearance of physical effects similar to those



FIGURE 6.21 A "zoo" of novel tunnel junctions involving multifunctional tunnel barriers and electrodes of various types.



FIGURE 6.22 Low-temperature superconducting Josephson junctions (a) and magnetic tunnel junctions (b) with the AlO_x-ferroelectric polymer composite barriers.

described above for entirely oxide tunnel junctions. On the other hand, metallic (Josephson and magnetic) tunnel junctions are more reliable than oxide ones, and, in addition, ultrathin PVDF films are compatible with AlO_x so that composite ferroelectric-oxide barriers can be fabricated. The possible structures of superconducting and magnetic metallic tunnel junctions involving PVDF are shown schematically in Figure 6.22.

In conclusion of this section, it should be noted that in addition to the planar metal/ferroelectric/metal multilayers discussed above, heterostructures of other geometries may be useful for certain applications in nanoelectronics and may even display specific physical properties. Remarkably, one-dimensional structures in the form of ferroelectric nanowires (Urban et al. 2003) and nanotubes with inner and outer electrodes (Alexe et al. 2006) have been successfully fabricated. Ferroelectric quantum dots are of great interest as well, in particular, for electro-optical devices (Ye et al. 2000).

6.7 Summary and Outlook

The overview presented in this chapter demonstrates impressive achievements in the deposition, characterization, and theoretical description of nanoscale ferroelectric films and heterostructures. Remarkably, capacitors involving only a few nanometers of perovskite ferroelectrics were successfully fabricated, displaying a high remanent polarization. Several advanced analytical tools are now available, showing that high structural quality and sharp interfaces can be retained even in nanoscale capacitors. The basic physical effects in ferroelectric thin films, such as the strain and depolarizing-field effects, are already well understood theoretically, and the influence of short-range interactions at the ferroelectric–metal interfaces is intensively studied by first-principles calculations. Thus, all three constituents of the research triangle shown in Figure 6.1 are functioning effectively, which promises new advances in the physics of nanoscale ferroelectrics and their device applications in the near future.

References

Alexe, M., Hesse, D., Schmidt, V. et al. 2006. Ferroelectric nanotubes fabricated using nanowires as positive templates. *Applied Physics Letters* 89: 172907.

Bratkovsky, A. M. and Levanyuk, A. P. 2005. Smearing of phase transition due to a surface effect or a bulk inhomogeneity in ferroelectric nanostructures. *Physical Review Letters* 94: 107601.

Bune, A. V., Fridkin, V. M., Ducharme, S. et al. 1998. Two-dimensional ferroelectric films. *Nature* 391: 874–877.

Bungaro, C. and Rabe, K. M. 2004. Epitaxially strained [001]-$(PbTiO_3)_1(PbZrO_3)_1$ superlattice and $PbTiO_3$ from first principles. *Physical Review B* 69: 184101.

Bunshah, R. F. 1994. *Handbook of Deposition Technologies for Films and Coatings*, Park Ridge, NY: Noyes Publications.

Choi, K. J., Biegalski, M., Li, Y. L. et al. 2004. Enhancement of ferroelectricity in strained $BaTiO_3$ thin films. *Science* 306: 1005–1009.

Chopra, K. L. 1969. *Thin Film Phenomena*, New York: McGraw-Hill.

Christman, J. A., Kim, S. H., Maiwa, H. et al. 2000. Spatial variation of ferroelectric properties in $Pb(Zr_{0.3},Ti_{0.7})O_3$ thin films studied by atomic force microscopy. *Journal of Applied Physics* 87: 8031–8034.

Chu, W., Mayer, J., and Nicolet, M. 1978. *Backscattering Spectrometry*, New York: Academic Press.

Clayhold, J. A., Kerns, B. M., Schroer, M. D. et al. 2008. Combinatorial measurements of Hall effect and resistivity in oxide films. *Review of Scientific Instruments* 73: 033908.

Cohen, R. E. 1992. Origin of ferroelectricity in perovskite oxides. *Nature* 358: 136–138.

Dawber, M., Rabe, K. M., and Scott, J. F. 2005. Physics of thin-film ferroelectric oxides. *Reviews of Modern Physics* 77: 1083–1130.

Devonshire, A. F. 1954. Theory of ferroelectrics. *Advances in Physics* 3: 85–130.

Diéguez, O., Tinte, S., Antons, A. et al. 2004. Ab initio study of the phase diagram of epitaxial $BaTiO_3$. *Physical Review B* 69: 212101.

Ducharme, S., Palto, S. P., Fridkin, V. M., and Blinov, L. M. 2002. Ferroelectric Polymer Langmuir-Blodgett Films. In *Ferroelectric and Dielectric Thin Films*, Vol. 3 of *Handbook of Thin Films Materials*, ed. H. S. Nalwa, San Diego, CA: Academic Press.

Eom, C. B., Cava, R. J., Fleming, R. M. et al. 1992. Single-crystal epitaxial thin films of the isotropic metallic oxides $Sr_{1-x}Ca_xRuO_3$ ($0 < x < 1$). *Science* 258: 1766–1769.

Fewster, P. F. 1996. X-ray analysis of thin films and multilayers. *Reports on Progress in Physics* 59: 1339–1407.

Fisher, O., Triscone, J. M., Fivat, P. et al. 1994. Investigations of coupled $DyBe_2Cu_3O_7$-$(Y_{1-x}Pr_x)$-$Be_2Cu_3O_7$ multilayer structures. *Superconducting Superlattices and Multilayers* 2157: 134–141.

Fong, D. D., Stephenson, G. B., Streiffer, S. K. et al. 2004. Ferroelectricity in ultrathin perovskite films. *Science* 304: 1650–1653.

Fong, D. D., Cionca, C., Yacoby, Y. et al. 2005. Direct structural determination in ultrathin ferroelectric films by analysis of synchrotron x-ray scattering measurements. *Physical Review B* 71: 144112.

Gajek, M., Bibes, M., Fusil, S. et al. 2007. Tunnel junctions with multiferroic barriers. *Nature Materials* 6: 296–302.

Garcia, R. and Perez, R. 2002. Dynamic atomic force microscopy methods. *Surface Science Reports* 47: 197–301.

Gerra, G., Tagantsev, A. K., and Setter, N. 2005. Surface-stimulated nucleation of reverse domains in ferroelectrics. *Physical Review Letters* 94: 107602.

Gerra, G., Tagantsev, A. K., Setter, N. et al. 2006. Ionic polarizability of conductive metal oxides and critical thickness for ferroelectricity in $BaTiO_3$. *Physical Review Letters* 96: 107603.

Gerra, G., Tagantsev, A. K., and Setter, N. 2007. Ferroelectricity in asymmetric metal-ferroelectric-metal heterostructures: A combined first-principles-phenomenological approach. *Physical Review Letters* 98: 207601.

Ghosez, P. and Rabe, K. M. 2000. Microscopic model of ferroelectricity in stress-free $PbTiO_3$ ultrathin films. *Applied Physics Letters* 76: 2767–2769.

Gruverman, A. and Kholkin, A. 2004. Ferroelectric nanodomains. In *Encyclopedia of Nanoscience and Nanotechnology*, ed. H. S. Nalwa, pp. 359–375. Los Angeles, CA: American Scientific Publishers.

Gruverman, A., Auciello, O., and Tokumoto, H. 1998. Imaging and control of domain structures in ferroelectric thin films via scanning force microscopy. *Annual Review of Materials Science* 28: 101–123.

Guro, G. M., Ivanchik, I. I., and Kovtonyuk, N. F. 1970. C-Domain barium titanate crystal in a short-circuited capacitor. *Soviet Physics Solid State* 11: 1574.

Güthner, P. and Dransfeld, K. 1992. Local poling of ferroelectric polymers by scanning force microscopy. *Applied Physics Letters* 61: 1137.

Habermeier, H. U. 2007. Thin films of perovskite-type complex oxides. *Materials Today* 10: 34–43.

Haeni, J. H., Theis, C. D., and Schlom, D. G. 2000. RHEED intensity oscillations for the stoichiometric growth of $SrTiO_3$ thin films by reactive molecular beam epitaxy. *Journal of Electroceramics* 4: 385–391.

Haeni, J. H., Irvin, P., Chang, W. et al. 2004. Room-temperature ferroelectricity in strained $SrTiO_3$. *Nature* 430: 758–761.

Hambe, M., Wicks, S., Gregg, J. M. et al. 2008. Creation of damage-free ferroelectric nanostructures via focused ion beam milling. *Nanotechnology* 19: 175302.

Haun, M. J., Furman, E., Jang, S. J. et al. 1987. Thermodynamic theory of $PbTiO_3$. *Journal of Applied Physics* 62: 3331–3338.

He, F. Z. and Wells, B. O. 2006. Lattice strain in epitaxial $BaTiO_3$ thin films. *Applied Physics Letters* 88: 152908.

Hubler, G. K. and Chrisey, D. B. 1994. *Pulsed Laser Deposition of Thin Films*, New York: John Wiley & Sons, Inc.

Huggins, H. A. and Gurvitch, M. 1985. Preparation and characterization of Nb/Al-oxide/Nb tunnel junctions. *Journal of Applied Physics* 57: 2103–2109.

Ishiwara, H. and Okuyama, M. 2004. *Ferroelectric Random Access Memories: Fundamentals and Applications*, Berlin, Germany: Springer.

Jia, C. L., Mi, S. B., Urban, K. et al. 2008. Atomic-scale study of electric dipoles near charged and uncharged domain walls in ferroelectric films. *Nature Materials* 7: 57–61.

Jo, J. Y., Kim, D. J., Kim, Y. S. et al. 2006a. Polarization switching dynamics governed by the thermodynamic nucleation process in ultrathin ferroelectric films. *Physical Review Letters* 97: 247602.

Jo, J. Y., Kim, Y. S., Noh, T. W. et al. 2006b. Coercive fields in ultrathin $BaTiO_3$ capacitors. *Applied Physics Letters* 89: 232909.

Jona, F. and Shirane, G. 1962. *Ferroelectric Crystals*, New York: MacMillan.

Junquera, J. and Ghosez, P. 2003. Critical thickness for ferroelectricity in perovskite ultrathin films. *Nature* 422: 506–509.

Kalinin, S. V. and Bonnell, D. A. 2002. Imaging mechanism of piezoresponse force microscopy of ferroelectric surfaces. *Physical Review B* 65: 125408.

Kato, Y., Kaneko, Y., Tanaka, H. et al. 2007. Overview and future challenge of ferroelectric random access memory technologies. *Japanese Journal of Applied Physics Part 1—Regular Papers Brief Communications & Review Papers* 46: 2157–2163.

Kawamura, E., Vahedi, V., Lieberman, M. A. et al. 1999. Ion energy distributions in rf sheaths; review, analysis and simulation. *Plasma Sources Science & Technology* 8: R45–R64.

Kholkin, A., Kalinin, S., Roelofs, A. et al. 2007. Review of ferroelectric domain imaging by piezoresponse force microscopy. In *Scanning Probe Microscopy: Electrical and Electromechanical Phenomena at the Nanoscale*, eds. S. Kalinin, and A. Gruverman, pp. 173–214. New York: Springer.

Kim, D. J., Jo, J. Y., Kim, Y. S. et al. 2005a. Polarization relaxation induced by a depolarization field in ultrathin ferroelectric $BaTiO_3$ capacitors. *Physical Review Letters* 95: 7602.

Kim, Y. S., Kim, D. H., Kim, J. D. et al. 2005b. Critical thickness of ultrathin ferroelectric $BaTiO_3$ films. *Applied Physics Letters* 86: 102907.

King-Smith, R. D. and Vanderbilt, D. 1993. Theory of polarization of crystalline solids. *Physical Review B* 47: 1651–1654.

King-Smith, R. D. and Vanderbilt, D. 1994. First-principles investigation of ferroelectricity in perovskite compounds. *Physical Review B* 49: 5828–5844.

Kohlstedt, H., Mustafa, Y., Gerber, A. et al. 2005a. Current status and challenges of ferroelectric memory devices. *Microelectronic Engineering* 80: 296–304.

Kohlstedt, H., Pertsev, N. A., Rodríguez Contreras, J. R. et al. 2005b. Theoretical current-voltage characteristics of ferroelectric tunnel junctions. *Physical Review B* 72: 125341.

Kohlstedt, H., Petraru, A., Szot, K. et al. 2008. Method to distinguish ferroelectric from nonferroelectric origin in case of resistive switching in ferroelectric capacitors. *Applied Physics Letters* 92: 062907.

Koukhar, V. G., Pertsev, N. A., and Waser, R. 2001. Thermodynamic theory of epitaxial ferroelectric thin films with dense domain structures. *Physical Review B* 64: 214103.

Kretschmer, R. and Binder, K. 1979. Surface effects on phase transitions in ferroelectrics and dipolar magnets. *Physical Review B* 20: 1065.

Kronholz, S., Rathgeber, S., Karthauser, S. et al. 2006. Self-assembly of diblock-copolymer micelles for template-based preparation of $PbTiO_3$ nanograins. *Advanced Functional Materials* 16: 2346–2354.

Ku, H. Y. and Ullman, F. G. 1964. Capacitance of thin dielectric structures. *Journal of Applied Physics* 35: 265–267.

Lai, B. K., Kornev, I. A., Bellaiche, L. et al. 2005. Phase diagrams of epitaxial $BaTiO_3$ ultrathin films from first principles. *Applied Physics Letters* 86: 132904.

Landau, L. D., Lifshitz, E. M., and Pitaevskii, L. P. 1984. *Electrodynamics of Continuous Media*, Oxford, NY: Pergamon.

Landauer, R. 1957. Electrostatic considerations in $BaTiO_3$ domain formation during polarization reversal. *Journal of Applied Physics* 28: 227–234.

Lee, H. N., Nakhmanson, S. M., Chisholm, M. F. et al. 2007. Suppressed dependence of polarization on epitaxial strain in highly polar ferroelectrics. *Physical Review Letters* 98: 217602.

Lettieri, J., Haeni, J. H., and Schlom, D. G. 2002. Critical issues in the heteroepitaxial growth of alkaline-earth oxides on silicon. *Journal of Vacuum Science and Technology A* 20: 1332.

Levanyuk, A. P. and Sigov, A. S. 1988. *Defects and Structural Phase Transitions*, Amsterdam, the Netherlands: Gordon and Breach.

Lines, M. E. and Glass, A. M. 1977. *Principles and Applications of Ferroelectrics and Related Materials*, Oxford, NY: Oxford University Press.

Logvenov, G. and Bozovic, I. 2008. Artificial superlattices grown by MBE: Could we design novel superconductors? *Physica C—Superconductivity and Its Applications* 468: 100–104.

Maissel, L. I. and Glang, R. 1979. *Handbook of Thin Film Technology*, New York: McGraw-Hill.

Mehta, R. R., Silverman, B. D., and Jacobs, J. T. 1973. Depolarization fields in thin ferroelectric films. *Journal of Applied Physics* 44: 3379–3385.

Moodera, J. S., Lisa R. K., Wong, T. M., and Meservey, R. 1995. Large magnetoresistance at room temperature in ferromagnetic thin film tunnel junctions. *Physical Review Letters* 74: 3273–3276.

Muller, K. A. and Burkard, H. 1979. $SrTiO_3$—Intrinsic quantum paraelectric below 4 K. *Physical Review B* 19: 3593–3602.

Nagarajan, V., Junquera, J., He, J. Q. et al. 2006. Scaling of structure and electrical properties in ultrathin epitaxial ferroelectric heterostructures. *Journal of Applied Physics* 100: 051609.

Nevot, L. and Croce, P. 1980. Characterization of surfaces by grazing x-ray reflection—Application to study of polishing of some silicate-glasses. *Revue De Physique Appliquee* 15: 761–779.

Nicolaou, K. C., Hanko, R., and Hartwig, W. 2002. *Handbook of Combinatorial Chemistry: Drugs, Catalysts, Materials*, Weinheim, Germany: Wiley-VCH Verlag GmbH.

Ohtani, M., Lippmaa, M., Ohnishi, T. et al. 2005. High throughput oxide lattice engineering by parallel laser molecular-beam epitaxy and concurrent x-ray diffraction. *Review of Scientific Instruments* 76: 062218.

Oikawa, T., Morioka, H., Nagai, A. et al. 2004. Thickness scaling of polycrystalline $Pb(Zr,Ti)O_3$ films down to 35 nm prepared by metalorganic chemical vapor deposition having good ferroelectric properties. *Applied Physics Letters* 85: 1754–1756.

Pertsev, N. A. and Kohlstedt, H. 2007. Elastic stabilization of a single-domain ferroelectric state in nanoscale capacitors and tunnel junctions. *Physical Review Letters* 98: 257603.

Pertsev, N. A. and Zembilgotov, A. G. 1991. Microscopic mechanism of polarization switching in polymer ferroelectrics. *Soviet Physics—Solid State* 33: 165–175.

Pertsev, N. A., Zembilgotov, A. G., and Tagantsev, A. K. 1998. Effect of mechanical boundary conditions on phase diagrams of epitaxial ferroelectric thin films. *Physical Review Letters* 80: 1988–1991.

Pertsev, N. A., Tagantsev, A. K., and Setter, N. 2000. Phase transitions and strain-induced ferroelectricity in $SrTiO_3$ epitaxial thin films. *Physical Review B* 61: R825–828; 2002. Erratum. *Physical Review B* 65: 219901.

Pertsev, N. A., Kukhar, V. G., Kohlstedt, H. et al. 2003a. Phase diagrams and physical properties of single-domain epitaxial $Pb(Zr_{1-x}Ti_x)O_3$ thin films. *Physical Review B* 67: 054107.

Pertsev, N. A., Rodríguez Contreras, J., Kukhar, V. G. et al. 2003b. Coercive field of ultrathin $Pb(Zr_{0.52}Ti_{0.48})O_3$ epitaxial films. *Applied Physics Letters* 83: 3356–3358.

Pertsev, N. A., Dittmann, R., Plonka, R. et al. 2007. Thickness dependence of intrinsic dielectric response and apparent interfacial capacitance in ferroelectric thin films. *Journal of Applied Physics* 101: 074102.

Petraru, A., Pertsev, N. A., Kohlstedt, H. et al. 2007. Polarization and lattice strains in epitaxial $BaTiO_3$ films grown by high-pressure sputtering. *Journal of Applied Physics* 101: 114106.

Petraru, A., Kohlstedt, H., Poppe, U. et al. 2008. Wedgelike ultrathin epitaxial $BaTiO_3$ films for studies of scaling effects in ferroelectrics. *Applied Physics Letters* 93: 072902.

Poppe, U., Schubert, J., Arons, R. R. et al. 1988. Direct production of crystalline superconducting thin-films of $YBa_2Cu_3O_7$ by high-pressure oxygen sputtering. *Solid State Communications* 66: 661–665.

Resta, R. 1994. Macroscopic polarization in crystalline dielectrics—The geometric phase approach. *Reviews of Modern Physics* 66: 899–915.

Rodríguez, B. J., Gruverman, A., Kingon, A. I. et al. 2002. Piezoresponse force microscopy for polarity imaging of GaN. *Applied Physics Letters* 80: 4166–4168.

Rodríquez Contreras, J., Schubert, J., Poppe, U. et al. 2002. Structural and ferroelectric properties of epitaxial $PbZr_{0.52}Ti_{0.48}O_3$ and $BaTiO_3$ thin films prepared on $SrRuO_3$/$SrTiO_3$(100) substrates. *Materials Research Society Symposium Proceedings* 688: C8.10.

Rodríguez Contreras, J. 2004. *Ferroelectric Tunnel Junctions*, Jülich, Germany: Forschungszentrum Jülich GmbH Verlag.

Rodríguez Contreras, J., Kohlstedt, H., Poppe, U. et al. 2003a. Surface treatment effects on the thickness dependence of the remanent polarization of $PbZr_{0.52}Ti_{0.48}O_3$ capacitors. *Applied Physics Letters* 83: 126–128.

Rodríguez Contreras, J., Kohlstedt, H., Poppe, U. et al. 2003b. Resistive switching in metal-ferroelectric-metal junctions. *Applied Physics Letters* 83: 4595–4597.

Sai, N., Kolpak, A. M., and Rappe, A. M. 2005. Ferroelectricity in ultrathin perovskite films. *Physical Review B* 72: 020101(R).

Schlom, D. G., Chen, L. Q., Eom, C. B. et al. 2007. Strain tuning of ferroelectric thin films. *Annual Review of Materials Research* 37: 589–626.

Schneller, T. and Waser, R. 2007. Chemical modifications of $Pb(Zr_{0.3},Ti_{0.7})O_3$ precursor solutions and their influence on the morphological and electrical properties of the resulting thin films. *Journal of Sol-Gel Science and Technology* 42: 337–352.

Schuller, I. K. 1980. New class of layered materials. *Physical Review Letters* 44: 1597–1600.

Scott, J. F. 2000. *Ferroelectric Memories*, Berlin, Germany: Springer.

Scott, J. F. 2007. Applications of modern ferroelectrics. *Science* 315: 954–959.

Setter, N., Damjanovic, D., Eng, L. et al. 2006. Ferroelectric thin films: Review of materials, properties, and applications. *Journal of Applied Physics* 100: 051606.

Slonczewski, J. C. 1989. Conductance and exchange coupling of two ferromagnets separated by a tunneling barrier. *Physical Review B* 39: 6995–7002.

Smolenskii, G. A., Bokov, V. A., Isupov, V. A. et al. 1984. *Ferroelectrics and Related Materials*, New York: Gordon and Breach.

Spatz, J. P., Mossmer, S., Hartmann, C. et al. 2000. Ordered deposition of inorganic clusters from micellar block copolymer films. *Langmuir* 16: 407–415.

Sun, J. Z. 1998. Thin-film trilayer manganate junctions. *Philosophical Transactions of the Royal Society of London Series A—Mathematical Physical and Engineering Sciences* 356: 1693–1711.

Sun, J. Z. 2001. Spin-dependent transport in trilayer junctions of doped manganites. *Physica C—Superconductivity and Its Applications* 350: 215–226.

Szafraniak-Wiza, I., Hesse, D., and Alexe, M. 2008. *Nanosized Ferroelectric Crystals*, Cambridge, U.K.: Woodhead Publishing, Limited.

Tagantsev, A. K. and Gerra, G. 2006. Interface-induced phenomena in polarization response of ferroelectric thin films. *Journal of Applied Physics* 100: 051607.

Tagantsev, A. K., Pertsev, N. A., Muralt, P. et al. 2002. Strain-induced diffuse dielectric anomaly and critical point in perovskite ferroelectric thin films. *Physical Review B* 65: 012104.

Tagantsev, A. K., Gerra, G., and Setter, N. 2008. Short-range and long-range contributions to the size effect in metal-ferroelectric-metal heterostructures. *Physical Review B* 77: 174111.

Urban, J. J., Spanier, J. E., Lian, O. Y. et al. 2003. Single-crystalline barium titanate nanowires. *Advanced Materials* 15: 423–426.

Valasek, J. 1921. Piezo-electric and allied phenomena in Rochelle salt. *Physical Review* 17: 475–481.

Waghmare, U. V. and Rabe, K. M. 1997. Ab initio statistical mechanics of the ferroelectric phase transition in $PbTiO_3$. *Physical Review B* 55: 6161–6173.

Weil, R., Nkum, R., Muranevich, E. et al. 1989. Ferroelectricity in zinc-cadmium telluride. *Physical Review Letters* 62: 2744–2746.

Xu, Y. 1991. *Ferroelectric Materials and Their Applications*, Amsterdam, the Netherlands: North-Holland.

Ye, H., Xu, Y. H., and Mackenzie, J. D. 2000. Semiconducting ferroelectric SbSl quantum dots in organically modified TiO_2 matrix. *Proceedings of SPIE* 3943: 95–101.

Zembilgotov, A. G., Pertsev, N. A., Kohlstedt, H. et al. 2002. Ultrathin epitaxial ferroelectric films grown on compressive substrates: Competition between the surface and strain effects. *Journal of Applied Physics* 91: 2247–2254.

Zhuravlev, M. Y., Jaswal, S. S., Tsymbal, E. Y. et al. 2005b. Ferroelectric switch for spin injection. *Applied Physics Letters* 87: 222114.

Zhuravlev, M. Y., Sabirianov, R. F., Jaswal, S. S. et al. 2005a. Giant electroresistance in ferroelectric tunnel junctions. *Physical Review Letters* 94: 246802.

7

Superconducting Weak Links Made of Carbon Nanostructures

7.1 Introduction 7-1
7.2 Superconducting Transport through a Weak Link 7-2
Density of Electronic States in a Superconductor • Coherent Transport at a Normal/ Superconducting Interface • A Brief Introduction to the Josephson Effect • Normal Electron Transport through an Atomic or Molecular Conductor • Superconducting Transport through Andreev Bound States • Introduction to Low-Dimensional sp^2 Carbon Structures • Gate Control of the Weak Link Transparency
7.3 Superconducting Transport in a Carbon Nanotube Weak Link 7-6
Introduction to Carbon Nanotube Devices • Experimental Realizations of Carbon Nanotube Weak Links • Nanotube Quantum Dot Connected to Superconducting Electrodes • High- Frequency Irradiation of Nanotube Weak Links
7.4 Nanotube-Based Superconducting Quantum Interferometers 7-10
Quantum Interference with Single Nanotube Weak Links • Tunability of the Phase Shift across Nanotube Weak Links • Application of Nanotube Weak Links to Magnetometry • Application of Nanotube Weak Links to Quantum Information
7.5 Graphene-Based Superconducting Weak Links 7-15
Proximity Effect in Graphene Weak Links • Graphene Nanotube Superconducting Quantum Interferometers
7.6 Fullerene-Based Superconducting Weak Links 7-17
Molecular Transistors Made by Electromigration • Implementation of a C60 Superconducting Transistor
7.7 Concluding Remarks 7-18
Acknowledgment 7-18
References 7-18

Vincent Bouchiat
Centre National de la Recherche Scientifique

7.1 Introduction

It has been known since the 1960s (De Gennes and Guyon 1963) that charge carriers emitted from a superconductor can propagate in a non-superconducting medium, provided that the electron wave functions of the two electrons originating from the superconductor (the so-called Cooper pairs) keep their correlation during their diffusion outside the superconductor. This process requires the absence of defects in the propagating medium that break time-reversal symmetry, such as magnetic impurities. These correlated electrons form an evanescent state that “bleeds” from the superconductors into the non-superconducting electrode on mesoscopic distances. The physics of these evanescent states, known as the “superconducting proximity effect” depends on many parameters (the coherence length of the superconductor, the contact barrier at the interface, the temperature, the electron diffusion length, etc.).

It appeared then possible to sever a superconducting electrode with non-superconducting elements (a narrow constriction, a normal metal, a thin insulating barrier, known as “weak links”) while keeping a supercurrent flow. As tunneling processes are known to depend exponentially on the thickness of oxide barriers, controlling the structure and the geometry of weak links down to the atomic scale appears to be of capital importance if one wants to get reproducible devices. Therefore, improving the miniaturization and the crystalline quality of these weak links was clearly identified as a critical issue. Among the possible candidates are sp^2-hybridized carbon nanostructures (i.e., graphenes, carbon nanotubes [CNTs], or fullerenes), which, among other advantages, offer good control of the crystallinity and provide ideal media to control a supercurrent flow. Quantum confinement of electronic states within the carbon nanostructure generates sharp variations of the electronic density of states. Tuning the weak link chemical potential with an electrostatic gate allows to adjust the weak link transparency.

The purpose of this chapter is to propose a basic overview of the principles that govern the physics of these carbon based devices and illustrate them by presenting experimental demonstrations and some applications.

7.2 Superconducting Transport through a Weak Link

7.2.1 Density of Electronic States in a Superconductor

At energies around the chemical potential μ and below the energy gap Δ, a superconductor (noted in the following by the symbol S) only has a single ground state, which depends on a macroscopic phase. In a bulk superconductor, all electrons are in the same quantum state characterized by a global phase φ. The charge carriers are condensed in a bound state of two electrons, the so-called Cooper pair, which has a charge of $-2e$ (Figure 7.1a). The ground state wave function depends on the phase φ and can be written as

$$\Delta \approx \sqrt{n_s}\exp(\mathrm{i}\varphi), \tag{7.1}$$

where n_s is the total number of Cooper pairs.

Δ is the "superconductor order parameter" and specifies the choice for the quantum phase φ. There are no other states present in the interval $[\mu - \Delta, \mu + \Delta]$ because it takes an energy 2Δ to break a Cooper pair. An electron in this energy window cannot be injected in a superconductor alone, generating a "gap" in the transmission of charge carriers at a normal/superconductor metal interface.

7.2.2 Coherent Transport at a Normal/Superconducting Interface

At the interface between a normal metal (N) and a superconductor (S), an electron at the Fermi level can nevertheless be converted into a Cooper pair with zero momentum if a hole (charge $+e$) is reflected with energy $-\varepsilon$ and opposite momentum, conserving the charge, energy, and momentum. The reflected hole acquires an additional phase factor φ, the order parameter phase. This conversion of an electron–hole pair into a Cooper pair is a process known as the Andreev reflection (Figure 7.1b). It dominates the charge transport at low bias through the interface. This Andreev reflection can lead to a supercurrent transport if correlated charge carriers are collected by a second superconductor placed in a series. The process is still effective at the interface between superconducting electrodes and nanoscale constriction, which we will refer to as a "weak link."



FIGURE 7.1 (a) Density of state of a superconducting electrode: all the electrons are in the ground state wave function at the chemical potential μ. (b) Schematics depicting the Andreev reflection. Describing coherent transport at a normal/superconducting interface below the gap. An electron (e) impinging the interface between a normal conductor (N) and a superconductor (S) produces a Cooper pair (CP, oval) in the top superconducting electrode and a retro-reflected hole (h) in the normal conductor. Vertical arrows indicate the spin band occupied by each particle.

7.2.3 A Brief Introduction to the Josephson Effect

The order parameter characterizing the superconducting state varies on a spatial scale equal to $\xi = hv_F/\Delta$, where v_F is the Fermi velocity. The quantity ξ, which is a measure of the size of Cooper pairs, is called the coherence length. At the interface with an insulator, a metal, or a nano-object, the superconducting order parameter $\Delta(\mathbf{r})$ (its wave function) weakens gradually close to the interface on a characteristic scale, which is on the order of ξ.

When two superconductors with phase φ_1 and φ_2 are separated by a weak link (see Figure 7.2), they interact through direct tunneling or by the Andreev reflection process presented in the previous paragraph. This sandwich structure is called a Josephson junction. It is dominated by the interaction energy between the two superconductors. In 1962, Brian Josephson predicted that due to the interaction between the two superconducting condensates in close proximity, a non-superconducting nanostructure can let flow a superconducting current I, the value of which depends on the phase twist between the two condensates (Figure 7.2) (Josephson 1962). For a thin insulating tunnel barrier, he has shown that the current has the following form:

$$I = I_c \sin(\varphi_2 - \varphi_1). \tag{7.2}$$

This surprising prediction (Josephson 1962) was rapidly experimentally confirmed, leading to a new field in superconducting electronics. Until the mid-1990s, such superconducting "weak links" were either made of insulating barriers (the so-called Josephson tunnel junctions, at the origin of all the recent advances in superconducting Qubits), narrow diffusive metallic



FIGURE 7.2 Schematics of a Josephson weak link. In this device, two superconducting electrodes, characterized by their phase φ_1 and φ_2 are separated by a weak link (symbolized by a twisted solid). The superconducting current I flowing through the weak link is a given function f of the "phase twist" i.e., the phase difference $\varphi_1 - \varphi_2$. This current–phase function f exhibits a 2π-periodicity and is highly non linear. It is the main characteristics of a Josephson weak link.

or semiconducting wires, or point contacts inserted between bulk electrodes (Likharev 1979). The first realization of a ballistic weak link with a limited number of conduction channels and controlled at the atomic scale came in 1997, with the measurement transport through gold atomic contacts in close vicinity of superconducting aluminum contacts (Scheer et al. 1997). In the last 5 years, it has been shown that carbon nanostructures can provide another class of weak links of good structural quality, for which strong quantum confinement offers gate tunability.

7.2.4 Normal Electron Transport through an Atomic or Molecular Conductor

At the atomic level, electron transport occurs by hopping through the atomic or molecular orbitals that are quantized in the case of a laterally confined nanostructure. They provide discrete conducting channels for electron transport (Imry and Landauer 1999). At the interface with a nanostructure, these contributions are related to the overlaps between molecular orbitals and the electronic wave functions in the metal. The physics of this quantum transport follows the description of Rolf Landauer from the 1970s, which refers to treating incoming charge carriers as plane waves traveling through "conduction channels" that are the eigen-modes for electronic propagation within the nanostructure. The electronic wave is partially transmitted and reflected at the interface. The theoretical work by Landauer and subsequently confirmed by numerous experiments have shown that the conductance of an electronic mesoscopic conductor is indeed divided into a discrete sum over all conduction channels i placed in parallel:

$$G = \sum_i G_i = \sum_i G_0 T_i = \frac{2e^2}{h} \sum_i T_i. \tag{7.3}$$

Each channel bears a quantized conductance G_0 called the quantum of conductance given by a ratio of two fundamental constants, $G_0 = 2e^2/h = (12.8\,\mathrm{k}\Omega)^{-1}$. In practice, each conduction channel is partially coupled to the modes of the reservoirs. This induces a reduction of the conductance of a dimension-less prefactor T_i with $0 < T_i < 1$. The origin of these reduction factors is essentially of technologic origin and can be optimized by choosing the right interface materials as shown below. Nevertheless, even for a perfectly transmitting interface ($T = 1$), the normal transport through a nanoscale conductor is limited to a resistive transport of $12\,\mathrm{k}\Omega$ per channel, the resistance being localized at the interface between the reservoir and the leads (see Figure 7.8a for an example).

In the case of coupling to superconducting electrodes, the Landauer formula 7.3 is no more valid: it is possible to cancel this contact resistance and obtain a zero-resistance electron flow through an atomic-sized contacts. This simple observation might have important technical consequences in the future of nanoelectronics, for example, to limit heat dissipation in the case of the ultra-high density integration of nanodevices involving few conduction channels.

7.2.5 Superconducting Transport through Andreev Bound States

As shown in Section 7.2.2, the microscopic transfer of charges at a superconducting interface arises by an electron–hole process known as the Andreev reflection. In a weak link, there are two normal/superconducting interfaces back-to-back (S/weak link and weak link/S). The two proximity effects on each side percolate and give rise to a superconducting current flow through the weak link. Furthermore, one has to consider the confinement in the weak link of the electron and holes created by the successive Andreev reflections at the interfaces: the electron and the holes remain spatially and energetically confined (Figure 7.3), thus defining a quantum well. The eigenstates of this well, the so-called Andreev bound states, require constructive interferences to propagate. The electron state, once converted into its hole conjugate, is converted back into the same electron state with the same quantum phase. This defines a quantization condition that depends on the phase difference between the superconductors: they shift the electron–hole Andreev wave function by their phase $\exp(i\varphi)$.

When no scattering occurs between the superconductors, there are two bound states per conductance channel with the energies $E_\pm = \pm\Delta\cos(\phi/2)$. More realistically, in the presence of a finite transmission T_i, their energies become $E_\pm = \pm\Delta\sqrt{1-\sin^2(\phi/2)}$ (Goffman et al. 2000). At low temperatures, only the Andreev-bound state lowest in energy is occupied. The Josephson superconducting currents carried by the different channels add their contribution to each other and for the superconducting current give

$$I = -\frac{\partial \sum_i E_-(\phi, T_i)}{\partial \phi} = \frac{e\Delta}{2\hbar} \sum_i T_i \frac{\sin\phi}{\sqrt{1 - T_i \sin^2(\phi/2)}}. \tag{7.4}$$

This "current-phase" relation, linking the supercurrent I to the phase shift ϕ across the ballistic weak link is a characteristic of Andreev processes and more generally will be the fingerprint of any superconducting weak link (Golubov et al. 2004). From that last formula, one can see that the "critical" current I_c, defined as the maximum supercurrent that can flow through the weak link with a length shorter than the superconducting coherence length, is quantized. Its maximum value is equal to

$$I_c = \frac{Ne\Delta}{\hbar}. \tag{7.5}$$

In the case of a nanodevice that can be modeled by N ballistic conduction channels placed in parallel, the quantum interference of the Andreev electrons bouncing back and forth between the two S/N and N/S serial interfaces at the junction boundaries is also at the origin of resonance currents called "Multiples Andreev reflections" (Klapwijk et al. 1982), which occur at voltages below the superconducting gap Δ (see examples in Figure 7.18). Due to resonating energy conditions they occur at bias



FIGURE 7.3 Top: Schematics depicting superconducting transport through a normal weak link N sandwiched between two superconducting electrodes. An electron is reflected as a hole at the interface with the left superconductor and the hole is reflected back as an electron on the right interface. The net result is a transfer of one Cooper pair through the S/N/S junction. Bottom: Phase dependence of the Andreev bound states energy levels ($\pi=\delta_r-\delta_l$). Left: For a perfectly transmitted channel without scattering potential ($T_i = 1$). Right: For a partially transmitted channel $T_i < 1$. The lower energy state is the only occupied state at low temperature.

voltages corresponding to the sub-harmonics of the superconducting gap ($1/n^*(2\Delta/e)$), where n is an integer. These multiple Andreev Reflections, which position are independent of the weak link density of state but are strongly affected by scattering, will then provide the most convincing experimental signatures of a ballistic weak link.

7.2.6 Introduction to Low-Dimensional sp^2 Carbon Structures

Low-dimensional allotropes based on carbon nanostructures with sp^2-hybridized bonds (Figure 7.4a), such as CNTs, graphenes, and fullerenes, have been extensively studied in the last decade (see appropriate chapters in the Handbook for immediate reference). Their exceptional electronic properties could provide alternative solutions in many fields of electronics including industrial applications for logic. They also behave as ideal media for transmitting superconducting charge carriers for several reasons.

First, they experimentally provide a quasi-perfect crystalline semiconducting lattice on a rather large scale length (typically a fraction of a micron, which corresponds to several thousands of C–C sp^2-hybridized bonds in every direction). Second, the inertness and absence of dangling bonds on the carbon surface solves the problem of surface termination (passivation), which is usually found in almost all other systems including all semiconductors candidates. This allow to make atomically clean edges and boundaries. This important feature enables the fabrication of reliable nanoscale metal/sp^2 carbon contacts with reproducible transparency.

7.2.7 Gate Control of the Weak Link Transparency

As we will detail in the following paragraph, the quantum confinement created by the low dimensionality of carbon nano-objects is at the origin of a sharp dependence of the electron density of states with the chemical potential of the weak link (Figure 7.4a). The resulting Andreev bound states will then be directly affected by this confinement and will create gate-tunable “filters” for the coupling between the two superconducting electrodes (Figure 7.4b). In the superconducting state, a supercurrent will flow if an Andreev bound state is aligned with respect to the Fermi level of the leads as depicted in paragraph 7.2.5. A voltage V_g applied on an electrostatic gate allows for a shift in the chemical potential of the weak link, which is equivalent to translating the confined energy levels (Figure 7.4b) with respect to the Fermi level of the leads. This will in turn tune the maximum superconducting current through the junction, thus implementing a “gate tunable Cooper pair filter.” In the following section, we provide details of the typical cases for the different types of nanocarbon structures considered.



FIGURE 7.4 (a) Crystalline structure of the three low-dimensional phases of sp^2 carbon allotropes (top), and its associated densities of states (bottom). Left: in Graphene, the two dimensional density of states is described by a set of two "Dirac" cones that intersect the Brillouin zone at points K and K'. These cones provide a linear gap-less dispersion curve. Middle: Metallic single-walled carbon nanotube. The periodic boundary conditions generated by the rolled-up graphene sheet generate solutions symbolized by thick black lines. For selected chiral angles and diameter of the nanotube, these lines intersect the K and K' points of the Brillouin zone, leading to metallic nanotubes which behave as perfect 1D channels. Right: C60 and derivated fullerenes. The energy spectrum shows discrete states, whose positions could be derived through molecular orbitals (HMO, left side) or density functional theory (DFT, right side of axis). The molecule shows a gap between the occupied and empty states of about 1 eV. (b) "Semiconducting" representations of the energy levels of a Superconductor/Nano-carbon/Superconductor junctions for two dimensional (left) and zero dimensional (right) weak links. The chemical potential of the weak link can be translated by adjustment of a gate voltage V_g which allows to tune the transmission of the Cooper pairs through the weak link. Left: For a 2D junction (i.e., graphene-based weak links), the transport of Cooper pairs can either be transmitted by the valence or the conduction band, leading to an ambipolar semiconductor-like transmission function. At the charge neutrality point (position where the valence and conduction cones intersect, superconducting transport is minimal and is mediated through evanescent waves. Right: for a quantum dot junction (short nanotube junction or fullerene), superconducting transport occurs when a single electron or single hole energy levels is aligned with the Fermi level of the electrode. Such discrete energy spectrum of the weak link acts as a tunable filter for superconducting transport and leads to a series of peaks in the gate dependence of the maximum superconducting current.

7.3 Superconducting Transport in a Carbon Nanotube Weak Link

7.3.1 Introduction to Carbon Nanotube Devices

CNTs are cylinders of carbon of about one nanometer in diameter and up to several micron in length, which can be seen as a rolled-up sheet of sp^2 carbon “graphene.” Their cylindrical shape and original 1D electronic structure (for a review, see Charlier et al. 2007) constitute the unique experimental realizations of a quasi-perfect 1D electronic system.

Depending on the chiral angle of the crystalline direction with the cylinder axis, CNTs can exhibit either metallic or semiconducting properties. For the sake of simplicity, one assumes in the following that the nanotube is single-walled and is of a metallic variety (Figure 7.4).

In practice, semiconducting nanotubes are so heavily doped by the metal contacting electrodes that they can also behave in a similar fashion.

A metallic single-walled CNT has two channels of conduction electrons available for electron conduction. According to the Landauer Formula (see Equation 7.3), when perfectly connected to a normal state electrode, it has a resistance that equals the fundamental constant called resistance quantum $h/4e^2$ = 6.5 kΩ. Due to the mismatch of the electron orbitals in the nanotube and in the metal electrodes, the transmission is generally not perfect. The result is equivalent to a tunnel barrier at the contact ($T < 1$). This induces a probability of transmission between the electrode and the nanotube that can be less than unity. These two semi-transparent electronic junctions placed in a series are in all means reminiscent to what is occurring for photon beams in a “Fabry–Perot” cavity (Liang et al. 2001) in which a photon is trapped between two semi-reflective mirrors. Such a cavity has internal resonating modes that correspond to stationary waves given by integer multiples of the half-wavelength and the resonating mode width (invert of the so-called finesse of the cavity) increases linearly with the mirror transparency. Similarly, the CNT junction behaves as a “quantum dot” that the gap between levels (normal modes) increases proportionally to $1/L$ where L is the nanotube length. The width of the levels is proportional to the transmission of contacts. For a short nanotube junction, we obtain discrete levels when the nanotube is completely decoupled from the electrodes like the energy level of an isolated molecule (see the case of C60 Figure 7.4a). These levels widen a bit when the quantum dot interacts with contacts. The position of the nanotube levels with respect to the energy level of the contacts can be adjusted by varying the electrostatic voltage applied to a gate electrode. The transmission of electrons is maximal when the energy level of the quantum dot coincides with the contacts. It thus realizes a molecular transistor (Figure 7.9, left) in which junction transparency can be periodically tuned with a voltage applied to the electrostatic gate (Figure 7.6).

7.3.2 Experimental Realizations of Carbon Nanotube Weak Links

Progress in the late 1990s in improving the contact of CNTs to superconducting electrodes showed that such junctions can exhibit superconducting fluctuations that can be gate controlled (Morpurgo et al. 1999) and that they can accommodate a superconducting current (Kasumov et al. 1999). In 2006, it was then shown that such junctions behave as gate-controlled Josephson junctions (Jarillo-Herrero et al. 2006, Jørgensen et al. 2006). During this period, fabrication techniques have been optimized to generate low-resistive contacts at the metal/sp^2 carbon interfaces. They required the use of specific metals for connection such as titanium (Jarillo-Herrero et al. 2006) or palladium (Cleuziou et al. 2006, Javey et al. 2003) that both provide good wetting properties onto the sp^2 carbon layer and minimize the Schottky barrier that could arise from the differences of the electronic work functions at the metal/carbon interface. More subtle effects linked to the hybridization of the metal orbitals to sp^2 carbon (Nemec et al. 2006) could explain the differences



FIGURE 7.5 Micrographs made using a transmission electron microscope (TEM) of superconducting junctions, involving a carbon nanotube bundle, left and for a fullerene dimer formed by two C82 molecules in series, right. The weak links are free-standing over a slit and bridge superconducting electrodes deposited on a silicon membrane. This allows TEM imaging and electrical measurements on the same samples. (After Kasumov, A.Y. et al., *Science*, 284, 1508, 1999. With permission.)



FIGURE 7.6 Top schematic of electron transport through a "defect-less" carbon nanotube contacted with two metallic electrodes. Electron transport is ballistic along the nanotube: the voltage drop $V = \mu_1 - \mu_2$ is occurring at the metal/nanotube contacts which act as tunnel barriers partially transmitting the electron. Bottom: For low resistance barrier contacts, the device act as a Fabry–Perot interferometer in which standing electron waves are separated by the energy difference $\Delta E = hv_F/2L$.

of interface resistances that have been reproducibly observed between these different metals (see Figure 7.7).

While not superconducting by itself, the Pd or Ti interfacing layer is made thin enough (a few nanometers) so that it lets the superconductivity induced by a covering top layer made of aluminum (Jarillo-Herrero et al. 2006) or niobium (Pallecchi et al. 2008) establish through the whole sandwich by the proximity effect. Using those materials, high transparency contacts with almost transparency T close to unity (Javey et al. 2003) can be reproducibly achieved by metal evaporation thus placing connected nanotube junctions in the high coupling limit (Liang et al. 2001). Advances in synthesis methods of nanotubes (in situ grown by CVD), which allow nanotubes to be connected during their growth onto platinum contacts (Cao et al. 2005) are another promising fabrication route. This last method makes clean suspended nanotube junctions, which in the near future could make possible the coupling of nanomechanical vibration modes to superconducting charge transport, as has been recently observed with normal charge carriers, by using non-superconducting metal electrodes as contacts (Lassagne et al. 2009, Steele et al. 2009).

7.3.3 Nanotube Quantum Dot Connected to Superconducting Electrodes

In a CNT weak link, the device considered is a portion of a nanotube with a length L connected by the two superconducting contacts (see Figure 7.8).

At one dimension, a defect along the channel cannot be overcome by the diffusion of the incoming electrons like it occurs in a 2D or 3D system. Therefore, the slightest defect along the nanotube generates back scattering which cancel the transmission of a supercurrent by Andreev bound states. It is then extremely important to realize the injection of Cooper pairs in a perfectly clean system. The nanotube portion length L is usually chosen not to exceed 300 nm in order to limit the occurrence of these structural defects. In such a case, a ballistic transport is reached (i.e., the voltage drop is localized at the contacts, see the top of Figure 7.6). The sub-micron length and nanometer diameter of the nanotube junction makes the intrinsic capacitance C of the junction very small, creating a Coulomb blockade effect (Beenakker and van Houten 1992). A charging energy $e^2/2C$ contributes to their energy and adds to the kinetic energy which leads to the Andreev bound states becoming



FIGURE 7.7 Left: Cross section showing the charge density redistribution at a metal/carbon nanotube interface for Palladium (a) and Titanium contacts (b). These results are obtained using an ab-initio density functional theory. The titanium contact show a much stronger hybridization with the carbon surface compared to Palladium. Right: Contact reflection coefficient $r = 1 - t$, (where t is contact transmission) as a function of the contact length L_c, the transparency first increases linearly with the contact length then saturates at a constant value independent on the contact length. Their results shows that the optimal metal/carbon interface transparency is obtained for a contact combining low hybridization with a large contact length. (Adapted from Nemec, N. et al., *Phys. Rev. Lett.*, 96, 076802, 2006. With permission.)



FIGURE 7.8 Schematic diagram of a carbon nanotube superconducting transistor. The contacting electrodes are made of a bilayer of aluminum (for the source of superconductivity) and underlayer of few nanometer thick film either made of palladium or titanium to increase contact transparency. These latter materials are known for their good contact abilities on sp^2 carbon layers (see Figure 7.7). The highly doped silicon substrate is connected to a voltage source V_g and is used as a "backgate" electrode.

$$E_{e,h} = \frac{e^2}{2C}(\pm 1 - n_g)^2 \pm \hbar v_F k, \tag{7.6}$$

where n_g is the gate-induced charge on the nanotube [$n_g = C_g V_g / e$]; electrostatic degeneracy between charge states occurs at zero gate bias.

The wavevector k is quantized by the Andreev boundary condition at the superconducting interfaces in multiples of $1/L$. In the presence of the Coulomb repulsion in the Quantum dot, the Andreev bound states described in Section 7.2.5 split their energy in a sum of the charging energy term and the confinement energy term, which for the electron states give

$$E_e = \frac{e^2}{2C}(1 - n_g)^2 + \frac{\hbar v_F T}{2L}(\phi + \psi_e(n_g, \phi)), \tag{7.7}$$

and for hole states

$$E_h = \frac{e^2}{2C}(1 + n_g)^2 + \frac{\hbar v_F T}{2L}(\phi + \psi_h(n_g, \phi)), \tag{7.8}$$

where $\psi_h(n_g,\phi)$ is a gate-dependent phase. In most experiments, the charging energy e^2/C and quantization energies are of the same order of magnitude (typically 1–10 meV). The eigenstates are then mixed states of charge and Andreev bound states. Close to a degeneracy point (n_g=1/2), the CNT Andreev bound states become resonant with the Fermi level of the leads, thus maximizing the supercurrent flow. As this energy separation can be tuned by applying a gate voltage V_g to the nanotube, we are able to tune the maximum supercurrent (referred to as "switching current") with the gate voltage.

The gate dependence of this last quantity is then periodic (see Figure 7.9, left) and directly reflects the conductance variations observed in the normal state (linked to the Fabry–Perot-like oscillations described in the previous paragraph). By varying the electrostatic voltage V_g applied to the nanotube, it is possible to shift the position of these energy levels relative to the energy levels of the electrons in superconducting contacts (Figure 7.4b, right). When levels coincide, the maximum supercurrent that can pass before obtaining a resistive state (called "current jump") reaches its maximum. On the opposite, if Andreev bound states spectral weight decrease due to levels misalignment, the current will then be minimal. It has been shown (Cleuziou 2006) that even in the case of abscence of Andreev bound states, a tiny supercurrent (of the order of tens of pico-amperes) can be maintained through the CNT probably due to higher order cotunneling processes. It has been experimentally shown by Jarillo-Herrero et al. (2006) that the maximum superconducting current can indeed be controlled by the gate voltage (Figure 7.9).

Therefore, such CNT junctions implement superconducting transistors for which the switching current can be tuned with the gate voltage over a large dynamic range (typically up to 2–3 orders of magnitude, depending on the coupling; see Figure 7.9 right). The current–voltage curves show some marked hysteresis especially in the off-state. The origin of this hysteresis (Gang et al. 2009), which is usually attributed to the existence of a capacitance in parallel with the junction for tunnel weak links (Barone and Paterno 1982), is still debated in the case of these carbon weak links in which the capacitance is extremely small. Hysteresis could rather be associated with the Joule dissipation that occurs in the weak link after switching to the normal state as it has been recently observed in metallic junctions (Courtois et al. 2008). Heat dissipation within the tiny volume of the junction could delay the re-trapping of the weak link in the superconducting state once the current bias is decreased. This occurs especially when the nanotube is in the high resistance state (Off State, see Figure 7.9).

The maximum superconducting current that can be carried by a single-walled CNT is given by Equation 7.5 and is equal to $2\Delta/\hbar \sim 30\,\text{nA}$ for the two conducting channels of a metallic



FIGURE 7.9 Electron transport through a transparent carbon nanotube junction as a function of the gate-voltage V_g. Top left: (a) Gate modulation of the nanotube conductivity dI/dV at zero bias in the normal state. (b) Map of the conductivity for current bias I. At resonance, the nanotube conductance is close to the theoretical maximum $4e^2/h$ thus corresponds to the high transparency limit ($t \sim 1$). Gate oscillations are broadly distributed in gate due to the strong hybridization of the nanotube levels with the contacting leads. (c) Differential resistivity dV/dI versus current I and V_g in the superconducting state. Darkest zones around zero bias corresponds to the supercurrent flow which are occurring to the same gate voltages as the high conducting state for non-superconducting electrodes. Right column: Voltage–Current characteristics of a carbon nanotube superconducting transistor measured at low temperature, showing a modulation of the superconducting current for gate voltage corresponding respectively to the on and off state (depicted by the white dotted lines on the resistance map shown in left). The off-state show a strong hysteresis which completely vanished in the on-state.

single-walled CNT connected to Aluminum electrode. In early experiments, measured switching currents were of a few nanoamperes, typically 10%–20% of the expected value. The discrepancy between the predicted and the observed values have been attributed to the sensitivity of the superconducting current to external perturbations, such as micro-wave photons emitted by thermal fluctuations and traveling along the lines. A better control of the electromagnetic environment by using LC and RC filtering on the measurement lines (Jarillo-Herrero et al. 2006) and by implementing locally dissipative elements, such as on-chip resistors close to the nanotube junctions (Jorgensen et al. 2007), has proven to be helpful to stabilize the superconducting current and increase the measured value of the switching current.

7.3.4 High-Frequency Irradiation of Nanotube Weak Links

According to what is known as the AC Josephson Effect, the phase twist across the weak links varies in time at the frequency given by the characteristic frequency of the coupling. Upon irradiation with radio frequency (RF) electromagnetic waves (Barone and Paterno 1982), superconducting weak links are known to develop a series of voltages steps that are so precisely positioned that they are used to define the voltage standards (Hamilton 2000). In the case of the irradiation of a single quantum channel, a peculiar behavior is expected for the RF-irradiated Andreev states (Averin and Bardas 1995).

Experimental measurements (Cleuziou et al. 2007) showed that the voltage steps across the nanotube weak link follow a completely different behavior upon the RF irradiation power depending on if the nanotube is placed either in the “on” or “off” state (see Figure 7.10). This behavior appears to be linked to the existence of the hysteresis found in the direct current (DC) measurements (Figure 7.9) and is discussed in the previous paragraph. They have been associated with the change of dissipation (Liu et al. 2009) that occurs when the nanotube levels are aligned or misaligned with the level of the leads. The RF properties of the superconducting carbon-based junction is expected to be very interesting principally because of their tiny size, which induces an extremely low intrinsic capacitance C, thus leading to extremely high cut-off frequencies $(RC)^{-1}$ that could exceed tens of GHz (Burke 2004). The coupling of these weak links to superconducting resonators will allow for the assessment of their additional RF properties in the near future.



FIGURE 7.10 Carbon nanotube superconducting transistor behavior upon radio-frequency (RF) irradiation in the on and off state (respectively shown in the left and right columns). Top curves: Voltage current characteristics at several RF amplitudes showing the typical constant voltage steps, known as "Shapiro steps." Hysteresis in these steps is seen on the "on" state and vanishes in the "off" state. Middle panels: differential resistance *dV/dI* maps for increasing RF power showing a different behavior in the off and on state. Bottom panels: Numerical simulation of the data of the middle panels using the RSJ (resp. RCSJ) non linear model for the on (resp. off) states.

7.4 Nanotube-Based Superconducting Quantum Interferometers

7.4.1 Quantum Interference with Single Nanotube Weak Links

An interferometer is an apparatus that measures the phase differences between two wave components. Interferometers work by splitting a wave into two components, sending them off along different paths, and then recombining them to record an interference pattern. The pattern is dependent on the phase difference arising from changes in the conditions along their paths. A superconducting interferometer (referred to by its acronym "DC-SQUID" [Clarke and Braginski 2004], which stands for direct current superconducting quantum interferometer device) achieves a kind of "Young slits" experiment with Cooper pairs, the slit being implemented by 2 weak links placed in parallel.

The coherence of the photon beam is provided here by the coherence of the Cooper pair supercurrent. Such a device was first implemented in the 1960s by using oxide-based tunnel weak links (Jaklevic et al. 1964), which rapidly became ubiquitous in the field of superconducting electronics: SQUIDs have been successfully used as ultra-sensitive magnetometers as well as amplifiers of low-level signals and low-impedance sources (Clarke and Braginski 2004).

The main feature of this device is that the maximum superconducting current can be periodically modulated by a tiny magnetic flux threaded by the loop, with a period equal to the flux quantum ϕ_0 $h/2e$ (Figure 7.11, right). We briefly recall in the next paragraph the principle of operation of a DC-SQUID.

The two currents circulating in each weak link interfere with each other and each weak link induces a phase shift $\Delta\phi_i$. according to Equation 7.2.

The total supercurrent is therefore written as the sum of two currents flowing in each branch.

If one assumes a sinusoidal current-phase relation, one obtains

$$I = I_{c1}\sin(\Delta\phi_1) + I_{c2}\sin(\Delta\phi_2). \tag{7.9}$$

Furthermore, an additional controlled phase (analogous to a geometric phase) can be introduced by applying a magnetic flux Φ_{ext} through the loop formed by the two weak link branches. Because of the uniqueness of the superconducting wave function, Φ_{ext} couples the phase shifts induced by each of these junctions in the two branches

$$2\pi\left(\frac{\Phi_{ext}}{\Phi_o}\right) = \Delta\phi_1 - \Delta\phi_2 \,(\text{mod}.2\pi). \tag{7.10}$$

In practice, the SQUID is current-biased and one measures the maximum superconducting current before the onset of a finite voltage



FIGURE 7.11 Schematic diagram of a superconducting quantum interferometer (SQUID) based on carbon nanotube weak links (top) aligned with an atomic force micrograph of a real device. (Adapted from Cleuziou, J.-P. et al., *Nat. Nanotechnol.*, 1, 53, 2006.) Thanks to a peculiar fork geometry design, the weak links in each branch can be made of two portions of the same carbon nanotube generating two independent quantum dots. The phase shift between the two currents flowing in each arm (white arrows) is adjusted by the magnetic flux *F* threaded by the loop. The two electrodes, G1 and G2 allow the application of locally addressed gate voltages which tune independently the transparency of each portion of the nanotube according to the principles of the carbon nanotube junctions shown above.

across the device. This switching current is directly related to the critical current of the SQUID, which can be obtained by computing the maximum value of the solutions of Equations 7.9 and 7.10.

$$I_c = \sqrt{\left(I_{c1} - I_{c2}\right)^2 + 4I_{c1}I_{c2}\cos^2\left(\frac{\pi\Phi_{ext}}{\Phi_o}\right)}. \qquad (7.11)$$

Due to thermal or quantum fluctuations of the phase across the weak links, the measured switching current does not reach that critical value I_c but its magnetic flux dependence still follows the relation in Equation 7.11. The quantum interference, therefore, produces periodic oscillations of the current as a function of external magnetic flux, analogous to the bright fringes observed in an experiment of Young's slit and whose period is equal to the flux quantum $h/2e$.

At the nanometer scale, a single CNT can be used to implement the two weak links that are placed on both arms of the interferometer by using a forked geometry (Figure 7.11).

The two branches implement two nanotube quantum dots; their behavior has been detailed in Section 7.3.3. It is therefore possible to modulate the quantum interference by independently adjusting the intensity of coupling in each quantum dot (see the three limit cases in Figure 7.12). Such electrostatic control of a DC-SQUID is extremely useful, both to optimize its operation and its coupling to local magnetic fields to study the detailed physics of the molecular Josephson junction. More generally, it is an experimental model system for the study of the variation of the phase of charge carriers across a quantum dot. Many physical phenomena such as an equal number of electrons in the nanotube (including those related to interactions between the spins of electrons) have been predicted and may now be studied.

The integration of these nanotubes between superconducting electrodes opens the way for the realization of superconducting circuits operating at radio frequencies, particularly useful to follow the time evolution of magnetization of individual nano-objects. They could afford to explore how quantum states of magnetization of a molecule magnet can couple to those generated in a superconducting circuit (which are the basis of superconducting quantum bits).

7.4.2 Tunability of the Phase Shift across Nanotube Weak Links

For an odd electron number of charge sitting on the nanotube, a CNT weak link can behave as a quantum dot that has a nonzero spin state. It thus behaves as a "spin impurity" seen from the superconducting electrodes. Quantum dots populated with a odd number of electrons are prone to an additional electronic resonance called the Kondo Effect (Kouwenhoven and Glazman 2001). This resonance originates from the tendency of conduction electrons to screen the nonzero spin states of the quantum dot in a similar fashion as it occurs in a 3D metal, which contains a low level of magnetic impurities. This screening current adds to the usual conduction channel of the quantum dot and generates a conduction channel at zero bias, which bypasses the Coulomb blockade regime (Nygard et al. 2000). In the superconducting state, the nonzero spin tunneling induces higher order electron transfers events (Buitelaar et al. 2002) that allow the flipping of both spins of the Cooper pair during the tunneling through the nanotube. This amounts to changing the sign of the Cooper pair wave function. As can be seen in Equation 7.1, a change of sign in this wave function is equivalent to a phase shift of π in the superconducting phase.

Such an effect, in which the minimum energy state of one of the Josephson junctions (the so-called π-junction) is obtained for a phase difference of π instead of 0, has been the focus of intense studies. Reminiscent of ferromagnetic impurities in a Josephson junction, it was predicted some 20 years ago (Glazman and Matveev 1989) that a reverse Josephson current would take place in a junction involving tunneling through a quantum dot populated with an odd number of electrons. For a strong Kondo effect (Figure 7.2), the Josephson coupling is expected to be positive (0-junction) since the localized spin is screened due to the Kondo effect. On the other hand, for a weak Kondo effect, the large on-site interaction only allows the electrons in a Cooper pair to tunnel one-by-one via virtual processes in which the spin ordering of the Cooper pair is reversed, leading to a negative Josephson coupling (π-junction) and hence a reversed supercurrent. Controlling the phase-shift across a nanotube weak link can be achieved by tuning the charge induced on the weak link (see Figure 7.13).



FIGURE 7.12 Top: Schematics of three typical working points of a carbon nanotube SQUID, in case **I**, both junctions have a quantum level adjusted to the Fermi energy of the leads (on-resonance) and supercurrent can flow through the device. In **II** and **III**, one and two junctions are tuned off-resonance, respectively. Bottom left: Modulation of the conductance of the device in the normal state. Center: Modulation of the maximum superconducting current of the same device. The number refers to the three cases described above. (Adapted from Cleuziou, J.-P. et al., *Nat. Nanotechnol.*, 1, 53, 2006. With permission.)



FIGURE 7.13 Gate control of the phase in a carbon nanotube SQUID. Left: magnetic field dependence of the maximum supercurrent in a nanotube SQUID as a function for different lateral gate voltages V_g, the modulation can be tuned from an even (0-junction SQUID) to an odd (π-junction SQUID) curve. The modulation is highly non-sinusoidal between the two states (Right), Color-scale representation of differential resistivity dV/dI as a function of the lateral gate voltages V_{g1} and V_{g2} showing the periodic switching between zero and π modulation. The dotted lines corresponds to voltage gate range for which an odd number of electrons is in the quantum dot. Note that when both SQUID junctions has π modulation, the SQUID recovers normal (0) modulation. (Adapted from Cleuziou, J.-P. et al., *Nat. Nanotechnol.*, 1, 53, 2006. With permission.)

7.4.3 Application of Nanotube Weak Links to Magnetometry

SQUID-based magnetometry in the near field regime (i.e., for the detection of fields emitted by source at the distance smaller than the SQUID loop radius) has been exploited for nearly 15 years in the field of molecular magnetism (Wernsdorfer 2001). It is based on the inductive coupling of a nano-magnetic object placed near a constriction of the loop of a SQUID. A local change in flux, for example, induced by the magnetization reversal of a magnetic dipole in the vicinity of the loop (Wernsdorfer et al. 1995) will be detected by a variation in the SQUID switching current. By recording these changes while sweeping the magnetic field in direction and intensity, one can accurately study the physical conditions of magnetization switching of a nanoparticle or a assembly of molecules. Therefore, it is possible to study the details of the dynamics of magnetization reversal on nano-magnets and highlight, in the case of molecular magnets, the existence of a tunnel effect of this reversal (Wernsdorfer et al. 1997).

The current system is limited in sensitivity and the threshold corresponds to the detection of a few thousands of elementary spins. The miniaturization of the most sensitive SQUID (superconducting weak seal, represented here by the CNT) seems to be a promising way of gaining sensitivity.

The strong 1D geometrical form factor of CNT junctions combined with their tiny cross-section open some interesting perspectives concerning the magnetometry at the nanometer scale. Indeed one can show that shrinking the cross-section of a weak link allows for the optimization of the inductive coupling between the loop of the SQUID magnetometer and a magnetic object sitting in close vicinity of the weak link (Bouchiat 2009). This inductive coupling factor is known to be proportional to the inverse of the weak link cross-section radius. Therefore, miniaturization of the weak link footprint is indeed necessary to match the size of a single molecule magnet (see Figure 7.14).

Noise measurements on practical devices (Cleuziou et al. 2006) have shown that the detection threshold in CNT magnetometers should allow measurements in the near field regime of magnetized nano-objects of typically 10 Bohr magnetons, for example, strays emitted by a single molecular magnet (see Figure 7.14). The control and measurement of the magnetization of a single molecular magnet is indeed a promising way to implement spin Qubits, which are readily interfaced to coherent superconducting electronic currents. The fact that nanotube SQUIDs can see their current gated within a large dynamic from 10 nA down to picoampere critical currents (Cleuziou et al. 2006) (see Figure 7.9) is also a promising feature. This could allow the limiting of the back-action of the measuring instrument to the evolving quantum spin, thus helping to preserve long coherence times. More generally, magnetometers based on these ultra-miniaturized weak links could provide new instrumentation set-ups, useful for the building of a spintronics at the molecular scale (Bogani and Wernsdorfer 2008).



FIGURE 7.14 Optimization of the inductive coupling of single molecule magnet to the nanotube superconducting junction. Top left: artist view of the grafting of a single molecule magnet (here a "manganese-12" molecule) in close contact onto a carbon nanotube junction. Top right, cross section of the same assembly showing the stray field emitted from the magnetic molecule. Bottom right: cross section of a similar situation for the previous generation of weak links made of a nanowire with state-of-the art electron beam lithography. Bottom left: Simulation of the inductive coupling factor α for the two cases shown in right as a function of the distance z between the centers of the two coupled objects: the black curve stand for a lithography-made nanobridge ($r = 25$ nm) while the curve (labelled 3) depicts the situation for a single-walled carbon nanotube ($r = 1$ nm). The nanotube based weak link which diameter matches the molecule size, better grab the stray field and thus increase the inductive coupling by two order of magnitude with respect to the weak link made by top down lithography. The top straight line depicts the theoretical coupling limit ($\alpha = 1/2$) which is almost reached with a carbon nanotube junction.



FIGURE 7.15 Chemical functionalization of carbon nanotube weak links for single molecule magnetism applications. Top left: Schematics showing the grafting of carbon nanotubes with organic molecules using pyrene group (inset) that specifically bind onto nanotube side walls by p-p interaction. (After Chen, R. et al., *J. Am. Chem. Soc.*, 123, 3838, 2001.) Right: AFM topographic analysis of molecular magnet/nanotube hybrids. Top right: Height images of the same CNT acquired on repeating the grafting process: left one time, center four times, right ten times. Bottom right: Section profile along the same CNT before (black line) and after (gray line) multiple graftings of 1. Bottom left: Heights of the grafted objects. (Adapted from Bogani, L. et al., *Angew. Chem.*, 48, 746, 2009.)

The full integration of magnetic molecules coupled with the device is still to be made. This requires control of the binding of single magnetic molecules to the nanotube while preserving its good conduction properties. Progress has been made in that direction by using chemically functionalized organic entities (Chen et al. 2001) that can mimic on a few cells, the graphitic honeycomb lattice (pyrene groups, see Figure 7.15), thus through π–π interaction, they provide specific grafting along the nanotube side walls. Pyrene functionalized molecular magnets have been shown (Bogani et al. 2009) to specifically bind in solution in a rather controlled way onto nanotube junctions.

7.4.4 Application of Nanotube Weak Links to Quantum Information

As shown above, CNT-based weak links offer the possibility of realizing the controlled injection of Cooper pairs that travel as



FIGURE 7.16 Top left: Schematics of a carbon nanotube based Cooper pair splitter: the nanotube is coupled in its middle part to a voltage biased superconducting electrode (noted S) which injects Cooper pairs in the nanotube. The nanotube splits the current into two components which are collected by symmetrically positioned normal metal electrodes. Bottom left: Cross section of the same device. The two branches act as nanotube quantum dots noted QD_1 and QD_2 in a similarly geometry as previously presented nanotube SQUID. Right: schematics showing the two possible paths for the two correlated electrons that forms the Cooper pair which splits in the nanotube and travel in opposite directions. (Adapted from Bouchiat, V. et al., *Nanotechnology*, 14, 77, 2003.)

correlated quasi-particles in a 1D or 0D conductor. Many experiments taking advantage of splitting the quantum correlated charge carriers emitted from a superconducting electrode can be devised. They are mostly inspired from those already realized in quantum optics and propose to realize their fully-integrated solid-state counterparts involving Cooper pairs instead of correlated photon pairs. In Cooper pairs splitting experiment, an additional quantum degree of freedom is also provided by the spin of the electron.

Among interesting basic devices is the nanotube-based Cooper pair beam splitter (Figure 7.16). It consists of a single-walled CNT connected at both ends to normal state electrodes and coupled in its middle part to a superconducting nanowire. Such a device acts as an electronic beam splitter for correlated electrons originating from the superconductor. Note that this geometry is very similar to the nanotube SQUID described in Section 7.4, but with the notable difference of having spatially separated normal-state "collecting electrodes" instead of a single superconducting one found in the SQUID geometry (Figure 7.11).

The Cooper pair splitter device was first discussed on a theoretical level in 2002–2003 (Bena et al. 2002, Recher and Loss 2002, Bouchiat et al. 2003) and its first preliminary experimental realizations just appeared recently using either a CNT (Herrmann et al. 2010) or a III–V semiconducting nanowire (Hofstetter et al. 2009).

In this device, the splitting of Cooper pairs in the superconductor provides two electrons with opposite spins. In the case of a full splitting, they can travel into opposite directions in the nanotube and are individually collected at both ends of the nanotube (Figure 7.16). Thanks to the Andreev process, the Cooper pair splitter generates electrons that are simultaneously entangled in energy and in spin. Correlation and noise measurements of the current emerging from the nanotube should allow the testing of Bell inequalities (Bouchiat et al. 2003) with electrons instead of photons.

7.5 Graphene-Based Superconducting Weak Links

7.5.1 Proximity Effect in Graphene Weak Links

Graphene, a single atomic layer of graphite, exhibits unique electrical and mechanical properties on account of its reduced dimensionality and "relativistic" band structure. The transport properties of the graphene sheets have recently received a lot of attention on both experimental (Geim and Novoselov 2007) and theoretical points of view. On one hand, this is due to its 2D character and on the other hand, to its remarkable band structure combining a linear dispersion relation of electronic wave functions similar to mass-less particles and perfect electron hole symmetry. The Fermi surface consists of two cones touching at one singular point, the so-called Dirac point, where the density of states is zero (see Figure 7.4a). Over the last 5 years, graphene has emerged as a unique platform for testing new electronic properties of condensed matter (Figure 7.17).

By tuning a gate voltage positively or negatively, one can respectively induce a finite density of electrons and holes with a linear energy dispersion curve. Furthermore, this 2D electron gas can be exposed to external physicochemical functionalization and be easily connected with superconducting electrodes. Soon after first electron transport measurements, graphene has been shown to allow Cooper pair transport (Heersche et al. 2007) with a well-defined Josephson effect exhibiting microamperes of critical current (Figure 7.18) and clearly defined (Figure 7.18) multiple Andreev reflections (Du et al. 2008a, Heersche et al. 2007).



FIGURE 7.17 Left: Schematic diagram of a graphene-based superconducting weak link. The graphene carrier density is controlled by adjusting the backgate voltage on the silicon substrate, which is isolated from the device by a thermal oxide layer. Right: Atomic force micrograph of a first realized graphene superconducting junction. (Adapted from Heersche, H.B. et al., *Nature*, 446, 56, 2007.)

The supercurrent of such a junction can be modulated in intensity with the gate, which tunes the carrier type and density of the graphene sheet (see Figure 7.4b). Depending on the gate voltage applied to the graphene, a supercurrent can be mediated by either electrons or holes (Heersche et al. 2007), which makes graphene the first 2D ambipolar superconducting material. Unlike nanotube weak links, the modulation no more shows any gate periodicy in the modulation of the switching supercurrent because of the absence of lateral quantum confinement. The superconducting current is monotonically increased by increasing the gate and, as it is predicted by the number of conduction channels contributing in parallel to the superconducting current (Equations 7.4 and 7.5), the intensity of the maximum superconducting current is usually thousands of times the one measured for a CNT junction.

New features associated with the existence of Dirac Fermions have been predicted (Beenakker 2008). For example, due to the multiple conical valley band structure, the Andreev reflection, which usually is a retro-reflection (as seen in Figure 7.1), can be induced specularly with a high probability in undoped samples when the Fermi energy lies in the vicinity of the Dirac point (Beenakker 2006). Such effects, as well as the observation of peculiarities induced by the Andreev bound states (Titov and Beenakker 2006), require the realization of the ballistic graphene weak links, a challenging fabrication task since the mean free path of graphene samples usually made are below 0.1 µm. Promising routes are offered by making suspended graphene obtained by under-etching the supporting substrate. Such a process has been shown to greatly enhance the normal state electronic properties in the non-superconducting state by boosting mean free paths (Du et al. 2008b) and electronic mobilities (Bolotin et al. 2008).



FIGURE 7.18 Characteristics of a superconducting/graphene/superconducting junction. (a) Voltage–current characteristics of a graphene-based superconducting weak link. (From Heersche, H.B. et al., *Nature*, 446, 56, 2007. With permission.) (b) Resistance map of a two-junction graphene device showing the ambipolar gate dependence of the superconducting state (central zone denoted by the letter S). Differential resistance of a device showing dependence of critical current on back gate voltage (dashed line) at 20 mK. Traces of multiple Andreev reflections at constant voltages $2\Delta g/ne$ for $n = 1, 2, 3$ are indicated by the white dashed lines (n) 1 at top, $\Delta g \sim 75\,\mu\text{eV}$. (Adapted from Girit, Ç. et al., *Nano Lett.*, 9, 198, 2009.) (c) Differential resistance as a function of the voltage bias showing the multiple Andreev reflection peaks below the Gap 2D. (From Heersche, H.B. et al., *Nature*, 446, 56, 2007.)



FIGURE 7.19 (a) Scanning electron microscope image of a superconducting quantum interference device with weak links made of portion of the same single layer graphene flake (black, graphene; light gray, silicon oxide substrate; dark gray, Pd/Al electrodes Inset: close-up of sub-100 nm wide graphene Josephson junctions. (b) Maximum switching current as a function of magnetic field B and gate voltage V_g. The sinusoidal oscillations indicate quantum interference between the two graphene Josephson junctions. For a fixed magnetic field, the magnitude of the modulation can be controlled by the back gate. (After Girit, Ç. et al., *Nano Lett.*, 9, 198, 2009.)

In the case of graphene, this is predicted to lead to an unusual bias dependence of the differential conductance of the weak link. In most experiments, superconducting charge carriers are injected by the measuring electrodes. However, it has been predicted (Feigel'man et al. 2010) and experimentally shown (Kessler et al. 2010) that the superconductivity could be induced globally by decorating the graphene with an array of superconducting electrodes. In this latter case, the proximity effect generates a supercurrent, which percolates through the entire graphene sheet.

7.5.2 Graphene Nanotube Superconducting Quantum Interferometers

Graphene-based SQUIDs devices can be obtained in a similar way as has been done for CNT weak links. Indeed, the fabrication and operation of a two junction SQUID formed by a single graphene sheet contacted with aluminum/palladium electrodes in the geometry of a loop (see Figure 7.19) has been demonstrated in 2009 (Girit et al. 2009).

As for the nanotube SQUID, graphene SQUIDs allow the tuning of the quantum interference with an electrostatic gate with a dependence (Figure 7.19b) that follows the transparency given by the graphene weak link (Figure 7.18). It also suggests a new modality for the ultrasensitive magnetometry of nanomagnets chemically or physically attached to the carbon surface.

7.6 Fullerene-Based Superconducting Weak Links

This last category considers the smallest sp^2 carbon weak links that involve fullerene molecules (Smalley 1997). We consider a device made of a fullerene molecule (see Figure 7.4a, right) placed in a transistor geometry (depicted in Figure 7.4b). Interaction of the discrete levels of a molecular entity with the superconducting electrode has triggered a lot a theoretical studies (Choi et al. 2004, Novotny et al. 2005). Unlike all the previous carbon-based weak links discussed above, for which the properties depend not only upon the material properties but also on the electrode geometries



FIGURE 7.20 Fullerene based superconducting weak link. Top left: Schematics of the device C60 connected to superconducting source and drain. The device sits over an aluminum gate electrode whose thin native oxide forms the gate dielectrics. Top right: scanning electron micrograph of the device, showing the nanoscale gap created by electromigration. (scale bar = 300 nm). Bottom: Map of the differential resistance of the device as a function of the gate voltage (x axis) and the current bias (y axis). The black region corresponds to the superconducting state. The gate dependence of the superconducting current is in agreement with the expected dependence for a proximity coupled quantum dot. (After Winkelmann, C.B. et al., *Nat. Phys.*, 5, 876, 2009.)

(for example, in a nanotube weak link, we have seen that the weak link gate modulation is inversely proportional to the length of the weak link, which is defined by the gap between the electrode), fullerene-based weak links involve the entire molecule. Therefore, electron transport through the junction is supposed to exhibit fingerprints (Zazunov et al. 2006) linked to the intrinsic molecule states, such as vibrational modes (Park et al. 2000) or molecular magnetism (Lee et al. 2008). Indeed a set of experiments (see Figure 7.5, right) involving magnetically active molecules such as endofullerenes (Grose et al. 2008, Kasumov et al. 2005), which consist of additional atoms inserted in the carbon cage formed by the fullerene shell, are a sensitive probe of molecular magnetism.

7.6.1 Molecular Transistors Made by Electromigration

Recent progress in the field of molecular electronics now allows for the direct integration of molecular objects into electrical on-chip circuits. It has been shown that by inserting molecules into a nanometer gap by sectioning a metallic wire, it is possible to create a molecular transistor which conducting states are linked to molecular orbitals available for conduction (Park et al. 2000). This possibility was provided by the electromigration process (Park et al. 1999), which allows the generation of nanogaps in metallic wires with good yield and an unprecedented reproducibility.

7.6.2 Implementation of a C60 Superconducting Transistor

Such electromigration processes have been recently adapted to the fabrication of superconducting transistors involving a single C60 molecule inserted between gold/aluminum electrodes that can be measured at milliKelvin temperatures (Winkelmann et al. 2009). Figure 7.20 shows the gate control of the superconducting state achieved in this molecular transistor, in the case of low dissipation in the environment of the linking conductor. The observed switching current is significantly lower than the critical current and has been shown to follow the law

$$\frac{I_S}{I_0} = \left(1 - \sqrt{1 - \frac{G_N h}{2e^2}}\right)^{3/2}.$$

The results of a C60 molecular transistor (Winkelmann et al. 2009) show good agreement between the measured critical current as a function of gate voltage and the prediction for $I_c(V_g)$ when taking into account the phase oscillations across the weak link.

7.7 Concluding Remarks

A new class of molecular weak links has now become available for research, in which superconductors can be coupled with reliable transparent interfaces to nanostructures composed of a crystalline arrangement of sp^2-hybridized carbon. The main original feature offered by this new type of device is the tunability of the superconducting transport being possible through gate control of the weak link chemical potential offered by quantum confinement. The integration control over these nanostructures, which has been made possible by advances in nanofabrication, allows for the fabrication of hybrid devices that mix bottom-up and top-down approaches. They provide building blocks that pave the way for the realization of more complex devices that should be useful for quantum information and nanomagnetism.

Acknowledgment

The author warmly acknowledges Wolfgang Wernsdorfer for stimulating discussions. The author would like to thank Sathyanarayanamoorthy Sridharan and Klaus Sattler for their kind help.

References

Averin, D. and Bardas, A. 1995. ac Josephson effect in a single quantum channel. *Physical Review Letters*, 75: 1831.

Barone, A. and Paterno, G. 1982. *Physics and Applications of the Josephson Effect*. New York: John Wiley & Sons.

Beenakker, C. W. J. 2006. Specular Andreev reflection in graphene. *Physical Review Letters*, 97: 067007.

Beenakker, C. W. J. 2008. Colloquium: Andreev reflection and Klein tunneling in graphene. *Reviews of Modern Physics*, 80: 1337.

Beenakker, C. W. J. and van Houten, H. 1992. *Single-Electron Tunneling and Mesoscopic Devices* (eds. Koch, H. and Lübbig, H.) http://xxx.lanl.gov/abs/condmat/0111505l. Berlin, Germany: Springer.

Bena, C., Vishveshwara, S., Balents, L., and Fisher, M. P. A. 2002. Quantum entanglement in carbon nanotubes. *Physical Review Letters*, 89: 037901.

Bogani, L. and Wernsdorfer, W. 2008. Molecular spintronics using single-molecule magnets. *Nature Materials*, 7: 179.

Bogani, L., Danieli, C., Biavardi, E. et al. 2009. Single-molecule-magnet carbon-nanotube hybrids. *Angewandte Chemie*, 48: 746–750.

Bolotin, K. I., Sikes, K. J., Jiang, Z. et al. 2008. Ultrahigh electron mobility in suspended graphene. *Solid State Communications*, 146: 351.

Bouchiat, V. 2009. Detection of magnetic moments using a nano-SQUID: Limits of resolution and sensitivity in near-field SQUID magnetometry. *Superconductor Science and Technology*, 22: 064002.

Bouchiat, V., Chtchelkatchev, N., Feinberg, D. et al. 2003. Single-walled carbon nanotube–superconductor entangler: Noise correlations and Einstein–Podolsky–Rosen states. *Nanotechnology*, 14: 77–85.

Buitelaar, M. R., Nussbaumer, T., and Schonenberger, C. 2002. Quantum dot in the Kondo regime coupled to superconductors. *Physical Reviews Letters*, 89: 256801.

Burke, P. J. 2004. Ac performance of nanoelectronics: Towards a ballistic THz nanotube transistor. *Solid State Electronics*, 40: 1981.

Cao, J., Wang, Q., and Dai, H. 2005. Electron transport in very clean, as-grown suspended carbon nanotubes. *Nature Materials*, 4: 745–749.

Charlier, J.-C., Blase, X., and Roche, S. 2007. Electronic and transport properties of nanotubes. *Reviews of Modern Physics*, 79: 677.

Chen, R., Zhang, Y., Wang, D., and Dai, H. 2001. Non-covalent sidewall functionalization of single-walled carbon nanotubes for protein immobilization. *Journal of the American Chemical Society*, 123: 3838–3839.

Choi, M. S., Lee, M., Kang, K., and Belzig, W. 2004. Kondo effect and Josephson current through a quantum dot between two superconductors. *Physical Review B*, 70: 020502.

Clarke, J. and Braginski, A. I. 2004. *The SQUID Handbook*. Weinheim, Germany: Wiley-VCH.

Cleuziou, J.-P., Wernsdorfer, W., Bouchiat, V., Ondarcuhu, T., and Monthioux, M. 2006. Carbon nanotube superconducting quantum interference device. *Nature Nanotechnology*, 1: 53.

Cleuziou, J. P., Wernsdorfer, W., Andergassen, S. et al. 2007. Gate-tuned high frequency response of carbon nanotube Josephson junctions. *Physical Review Letters*, 99: 117001.

Courtois, H., Meschke, M., Peltonen, J. T., and Pekola, J. P. 2008. Origin of hysteresis in a proximity Josephson junction. *Physical Review Letters*, 101: 067002.

De Gennes, P. G. and Guyon, E. 1963. Superconductivity in "normal" metals. *Physics Letters*, 3: 168–169.

Du, X., Skachko, I., and Andrei, E. Y. 2008a. Josephson current and multiple Andreev reflections in graphene SNS junctions. *Physical Review B*, 77: 184507.

Du, X., Skachko, I., Barker, A., and Andrei, E. Y. 2008b. Approaching ballistic transport in suspended graphene. *Nature Nanotechnology*, 3: 491–495.

Feigel'man, M. V., Skvortsov, M. A., and Tikhonov, K. S. 2008. Proximity-induced superconductivity in graphene. *JETP Letters*, 88: 862.

Gang, L., Yong, Z., and Chun Ning, L. 2009. Gate-tunable dissipation and "superconductor-insulator" transition in carbon nanotube Josephson junctions. *Physical Review Letters*, 102: 016803.

Geim, A. K. and Novoselov, K. S. 2007. The rise of graphene. *Nature Materials*, 6: 183.

Girit, Ç., Bouchiat, V., Naaman, O. et al. 2009. Tunable graphene superconducting quantum interference device. *Nano Letters*, 9: 198–199.

Glazman, L. I. and Matveev, K. A. 1989. Resonant Josephson current through Kondo impurities in a tunnel barrier. *JETP Letters*, 49: 659.

Goffman, M. F., Cron, R., Levy Yeyati, A. et al. 2000. Supercurrent in atomic point contacts and Andreev states. *Physical Review Letters*, 85: 170.

Golubov, A. A., Kupriyanov, M. Y., and Il'ichev, E. 2004. The current-phase relation in Josephson junctions. *Reviews of Modern Physics*, 76: 411–469.

Grose, J. E., Tam, E. S., Timm, C. et al. 2008. Tunnelling spectra of individual magnetic endofullerene molecules. *Nature Materials*, 7: 884.

Hamilton, C. A. 2000. Josephson voltage standards. *Review of Scientific Instruments*, 71: 3611.

Heersche, H. B., Jarillo-Herrero, P., Oostinga, J. B., Vandersypen, L. M., and Morpurgo, A. F. 2007. Graphene JJ. *Nature*, 446: 56.

Herrmann, L. G., Portier, F., Roche, P. et al. 2010. Carbon nanotubes as cooper pair beam splitters. *Physical Review Letters*, 104: 026801.

Hofstetter, L., Csonka, S., Nygard, J., and Schonenberger, C. 2009. Cooper pair splitter realized in a two-quantum-dot Y-junction. *Nature*, 461: 960–963.

Imry, Y. and Landauer, R. 1999. Conductance viewed as transmission. *Reviews of Modern Physics*, 71: S306.

Jaklevic, R. C., Lambe, J., Silver, A. H., and Mercereau, J. E. 1964. Quantum interference effects in Josephson tunneling. *Physical Review Letters*, 12: 159–160.

Jarillo-Herrero, P., van Dam, J. A., and Kouwenhoven, L. P. 2006. Quantum supercurrent transistors in carbon nanotubes. *Nature*, 439: 953–956.

Javey, A., Guo, J., Wang, Q. et al. 2003. Ballistic carbon nanotube field-effect transistors. *Nature*, 424: 654–657.

Jørgensen, H. I., Grove-Rasmussen, K., Novotny, T., Flensberg, K., and Lindelof, P. E. 2006. Electron transport in single-wall carbon nanotube weak links in the Fabry-Perot regime. *Physical Review Letters*, 96: 207003.

Jorgensen, H. I., Novotny, T., Grove-Rasmussen, K., Flensberg, K., and Lindelof, P. E. 2007. Critical current 0-pi transition in designed Josephson quantum dot junctions. *Nano Letters*, 7: 2441–2445.

Josephson, B. D. 1962. Possible new effects in superconductive tunnelling. *Physics Letters*, 1: 251–253.

Kasumov, A. Y., Deblock, R., Kociak, M. et al. 1999. Supercurrents through single-walled carbon nanotubes. *Science*, 284: 1508.

Kasumov, A. Y., Tsukagoshi, K., Kawamura, M. et al. 2005. Proximity effect in a superconductor-metallofullerene-superconductor molecular junction. *Physical Review B*, 72: 033414.

Kessler, B. M., Girit, C. O., Zettl, A., and Bouchiat, V. 2010. Tunable superconducting phase transition in metal-decorated graphene sheets. *Physical Review Letters*, 104: 047001.

Klapwijk, T. M., Blonder, G. E., and Tinkham, M. 1982. Explanation of subharmonic energy gap structure in superconducting contacts. *Physica B*, 109: 1657.

Kouwenhoven, L. and Glazman, L. 2001. Revival of the Kondo Effect. *Physics World*, 14: 33.

Lassagne, B., Tarakanov, Y., Kinaret, J., Garcia-Sanchez, D., and Bachtold, A. 2009. Coupling mechanics to charge transport in carbon nanotube mechanical resonators. *Science*, 325: 1107–1110.

Lee, M., Jonckheere, T., and Martin, T. 2008. Josephson effect through a magnetic metallofullerene molecule. *Physical Review Letters*, 101: 146804.

Liang, W., Bockrath, M., Bozovic, D. et al. 2001. Fabry - Perot interference in a nanotube electron waveguide. *Nature*, 411: 665.

Likharev, K. K. 1979. Superconducting weak links. *Reviews of Modern Physics*, 51: 101.

Liu, G., Zhang, Y., and Lau, C. N. 2009. Gate-tunable dissipation and "Superconductor-insulator" transition in carbon nanotube Josephson junctions. *Physical Review Letters*, 102: 016803.

Morpurgo, A. F., Kong, J., Marcus, C. M., and Dai, H. 1999. Gate-controlled superconducting proximity effect in carbon nanotubes. *Science*, 286: 263–265.

Nemec, N., Tomanek, D., and Cuniberti, G. 2006. Contact dependence of carrier injection in carbon nanotubes: An Ab initio study. *Physical Review Letters*, 96: 076802.

Novotny, T., Rossini, A., and Flensberg, K. 2005. Josephson current through a molecular transistor in a dissipative environment. *Physical Review B*, 72: 224502.

Nygard, J., Cobden, D. H., and Lindelof, P. E. 2000. Kondo physics in carbon nanotubes. *Nature*, 408: 342–346.

Pallecchi, E., Gaaß, M., Ryndyk, D., and Strunk, C. 2008. Carbon nanotube Josephson junctions with Nb contacts. *Applied Physics Letters*, 93: 072501.

Park, H., Lim, A. K. L., Alivisatos, A. P., Park, J., and McEuen, P. L. 1999. Fabrication of metallic electrodes with nanometer separation by electromigration. *Applied Physics Letters*, 75: 301.

Park, H., Park, J., Lim, A. K. L. et al. 2000. Nanomechanical oscillations in a single-C60 transistor. *Nature*, 407: 57–60.

Recher, P. and Loss, D. 2002. Superconductor coupled to two Luttinger liquids as an entangler for electron spins. *Physical Review B*, 65: 165327.

Scheer, E., Joyez, P., Esteve, D., Urbina, C., and Devoret, M. H. 1997. Conduction channel transmissions of atomic-size aluminum contacts. *Physical Review Letters*, 78: 3535.

Smalley, R. E. 1997. Discovering the fullerenes. *Reviews of Modern Physics*, 69: 723.

Steele, G. A., Huttel, A. K., Witkamp, B. et al. 2009. Strong coupling between single-electron tunneling and nanomechanical motion. *Science*, 325: 1103–1107.

Titov, M. and Beenakker, C. W. J. 2006. Josephson effect in ballistic graphene. *Physical Review B*, 74: 041401.

Wernsdorfer, W. 2001. Classical and quantum magnetization reversal studies in nanometer-sized particles and clusters. *Advances in Chemical Physics*, 188: 99–190.

Wernsdorfer, W., Hasselbach, K., Mailly, D. et al. 1995. Seminal microSQUID particle WW. *Journal of Magnetism and Magnetic Materials*, 145: 33.

Wernsdorfer, W., Bonet Orozco, E., Hasselbach, K. et al. 1997. Macroscopic quantum tunneling of magnetization of single ferrimagnetic nanoparticles of Barium Ferrite. *Physical Review Letters*, 79: 4014–4017.

Winkelmann, C. B., Roch, N., Wernsdorfer, W., Bouchiat, V., and Balestro, F. 2009. Superconductivity in a single-C60 transistor. *Nature Physics*, 5: 876–879.

Zazunov, A., Fierberg, D., and Martin, T. 2006. Phonon squeezing in a superconducting molecular transistor. *Physical Review Letters*, 97: 196801.

8

Micromagnetic Modeling of Nanoscale Spin Valves

Bruno Azzerboni
University of Messina

Giancarlo Consolo
University of Messina

Giovanni Finocchio
University of Messina

8.1 Introduction **8**-1
8.2 Background **8**-3
Exchange Interactions • Anisotropy • Magnetostatic Interactions • External Field • Energy Balance and Free Energy Functional Formulation • Equation of Motion • Equation of Motion Including Spin-Transfer Torque Effects
8.3 Computational Micromagnetics of Nanoscale Spin-Valves: State of the Art **8**-7
Numerical Solution of LLGS Equation Based on FD Methods • Spin-Transfer Torque and Giant Magnetoresistance: Dual Phenomena • Nanoscale Devices: Pillar vs. Point-Contact
8.4 Conclusions and Future Perspective **8**-15
References **8**-16

8.1 Introduction

Magnetism is an open field in which physicists, electrical engineers, material scientists, mathematicians, chemists, metallurgists, and others practice together.

Today information technologies ranging from personal computers to mainframes use magnetic materials to store information on tapes, floppy diskettes, and hard disks. Our seemingly insatiable appetite for more computer memory will probably be met by a variety of magnetic recording technologies based on nanocrystalline thin-film media and magneto-optic materials. Personal computers and many of our consumer and industrial electronics components are now powered largely by lightweight switch-mode power supplies using new magnetic materials technology that was unavailable 20 years ago. Magnetic materials touch many other aspects of our lives. Each automobile contains dozens of motors, actuators, sensors, inductors, and other electromagnetic and magneto-mechanical components using hard (permanent) as well as soft magnetic materials. Electric power generation, transformation, and distribution systems rely on hundreds of millions of transformers and generators that use the principles of electromagnetic fields as well. Finally, magnetism is present in telecommunication systems, such as mobile phones, electronic article surveillance, asset protection, and access control because of the presence of oscillating circuits and resonators working at microwave frequencies.

Magnetism, along with electricity, belongs to a larger phenomenon, electromagnetism, by which we describe the force generated by the passage of an electric current through matter. When two electric charges are at rest, it appears to the observer that the force between them is merely electric. If the charges are in motion, however, and in this instance motion or rest is referred to in relation to the observer, then it appears as though a different force, known as magnetism, exists between them. In fact, the difference between magnetism and electricity is purely artificial. Both are manifestations of a single fundamental force, with magnetism simply being an abstraction that people use for the changes in electromagnetic force created by the motion of electric charges.

To gain a deeper understanding of magnetism and the materials classification, it is necessary to first introduce some basic concepts. First, within the area of research of magnetism, one can identify at least four different scales that give correspondingly four different levels of investigation, as shown in Figure 8.1.

The top level, magnetic hysteresis models, treats the phenomenology of technical magnetization curves. Such an approach is encountered whenever connections between hysteresis and domain phenomena can be established. There are several models to treat the magnetization phenomena (curves) at this level. The first scalar model of hysteresis was proposed by Preisach (1929). From 1929, lots of efforts have been focused on the physical interpretation of its parameters as well as the inclusion of aftereffects, accommodation, and magnetostriction phenomena (Bertotti 1998).

At the bottom level, we find the atomic description, which deals with the spin structure of magnetically ordered material and the arrangements of spins on the crystal lattice sites. It also describes the origin, interactions, mutual arrangement, and statistical thermodynamics of elementary magnetic moments by means of quantum mechanic theories.


Magnetic hysteresis models
Describing the average magnetization vector of a sample as a function of the external field
$\Delta x \gg D$
Domain theory
Describing the magnetic microstructure of a sample, the shape and detailed spatial arrangement of domain and domain boundaries
$\delta \ll \Delta x \approx D$
Micromagnetism
Describing the internal structure of domain walls and their substructures in terms of a continuum theory of classical magnetization vector field
$\Delta x \approx \delta$
Atomic (quantic) theory
Describing the origin, the interactions, the mutual arrangement and the statistical thermodynamics of elementary magnetic moments
$\Delta x \approx a \ll \delta$

FIGURE 8.1 The hierarchy of descriptive levels of magnetically ordered materials. The values in parenthesis indicate the sample dimensions for which the different theories are applicable. Δx is the characteristic scale for each theory, D, δ, and a are the domain size, the wall width, and the interatomic distance, respectively.

There exist two models working at the intermediate mesoscopic scale: domain theory and micromagnetism. The former combines discrete, uniformly magnetized domains, domain walls, and their microstructure. The latter is the continuum theory of magnetic moments, underlying the description of the magnetic microstructure. The domain theory is located at a scale larger than the domain wall width, whereas the micromagnetic scale is comparable with that scale (see Figure 8.2).

The starting point of the domain theory is to suppose a given domain's distribution in a specimen according to both experimental observations and energy balance. The main assumption is that the wall that divides the adjacent domains has a zero width. In other words, this is a model where the magnetization vector presents discontinuities when passing from a domain to the adjacent one. As cited briefly above, this theory is valid under the assumption that the domain wall width is negligible with respect to the other dimensions involved in the problem. Without going into detail, it has to be noted that the domain theory offers the possibility of describing a lot of real systems. In spite of this, its limitations lead to the need for building a more accurate and general theory.

The micromagnetic theory was developed first by Landau and Lifshitz (1935) on a variational principle: it searches for magnetization distributions with the total smallest energy. This variational principle leads to a set of differential equations, the micromagnetic equations, which were initially developed by the same authors for one-dimensional problems. Stimulated again by experimental work and its analysis, W.F. Brown extended the equations to three dimensions (Brown 1940, 1963).


Quantum mechanics
Micromagnetism
Domain theory
10^{-10}
10^{-9}
1 nm
10^{-8}
10^{-7}
10^{-6}
1 μm
10^{-5}
10^{-4}
10^{-3}
1 mm
… d (m)

FIGURE 8.2 Characteristic length scales for mathematical models of magnetism.

The micromagnetic equations are complicated nonlinear and nonlocal equations; they are therefore difficult to solve analytically, except in cases in which a linearization is possible. However, a number of problems in research need micromagnetic methods for their adequate treatment, such as the following:

1. The analysis of the behavior of small magnetic particles that are, at the same time, too small to accommodate a regular domain structure and too large to be described as uniformly magnetized
2. The determination of the spatial distribution of magnetization inside a domain wall
3. The calculation of the magnetic stability limits
4. The analysis of rapid magnetization dynamics occurring in nanoscale devices

To treat such problems, works on numerical solutions of the micromagnetic equations are increasingly pursued. It appears utopian, however, to apply micromagnetic methods to large-scale domain structures because the gap between the size of samples and the size of computational grids is simply too large and unaffordable computational times and memory allocation would be consequently required. According to these discussions, micromagnetic and domain theories should not be considered as mutually exclusive at all, but as complementary tools.

In this chapter, we will address our discussion on the usage of micromagnetic frameworks to describe the behavior of a class of novel devices that are currently investigated for their attracting potential applications (mainly as magnetic memories and microwave oscillators).

In 1996, in fact, almost contemporarily, Slonczewski (1996) and Berger (1996) predicted that a direct electric current passing through a magnetic material, adequately thick, becomes spin-polarized along the direction of its local magnetization vector. The current moving outward such a polarizer is thus referred to as "spin-polarized current." To some extent, it is possible to consider this phenomenon in analogy to what occurs in optical systems where a unpolarized light traverses a slab of polarizing material and causes the outgoing electromagnetic waves to oscillate along the direction of the transmission axis of the polarizer. If a spin-polarized current presents a sufficiently large amplitude and now traverses a second magnetic layer, it can transfer its spin-angular momentum and destabilize the static equilibrium orientation of the magnetization of this latter layer. Such phenomenon, which is correspondingly called "spin-transfer torque effect," has been indeed applied, from the very beginning, in multilayer systems called "spin-valve" like the one shown in Figure 8.3.

A classical spin-valve system consists of: a thicker magnetic layer, called fixed or pinned layer (PL), which acts as the spin-polarizer; a thinner magnetic layer, called free layer (FL), which is the one generally subjected to the action of the spin-transfer torque; and a nonmagnetic spacer, used to decouple the exchange interactions between PL and FL. Depending on the electrical conductivity of the intermediate layer, it is possible to build-up either "classical" spin-valve (CSV) devices, if the spacer is a metal, or nonclassical magnetic tunnel-junctions (MTJ), if the spacer is an insulator. The mechanism of the torque and the resulting magnetic dynamics have also been studied experimentally in magnetic wires based on the capability of the spin-transfer torque to move domain walls.



FIGURE 8.3 Schematic representation of the active region of a spin-valve when a perpendicular-to-plane electric current is injected through the structure. Please note that, because electrons bear negative charge, a downward current flow corresponds to an upward electron flow. A thicker ferromagnetic layer ("fixed" layer), having a magnetization vector $\mathbf{S}_{PL}$ fixed in space, and a thinner ferromagnetic layer ("free" layer), having a magnetization vector $\mathbf{S}_{FL}$ "free" to move, are separated by a nonmagnetic layer (spacer). The electrons of the current *I* exert a torque on the magnetization of the free layer. The current *I* is taken as positive when directed from the fixed to the free layer (electrons flow from the free into the fixed layer).

Moreover, depending on the geometry, properties of the layered magnetic structure, and magnitude and orientation of the external bias field, such a "spin-transfer torque effect" can lead either to the switching of the magnetization direction or to a stable magnetization precession of the magnetization of the thinner FL.

The discovery that spin-polarized current can alter a magnetic state opened several perspectives for a new class of nano-scale magnetic devices in which the additional degree of freedom constituted by the "spin" plays an important role. The corresponding new research area was consequently called *spintronics*, a short notation for "*spin-based electronics*". In general, spintronics refers to the study of the role played by electron (and more generally nuclear) spin in solid-state physics and in those devices that specifically exploit spin properties instead of, or in addition to, the degree of freedom given by the charge. The spin-transfer torque, by which spin-polarized currents can replace the role of a bias magnetic field in managing the spatial configuration of magnetization, offers the possibility of designing and building up a new class of devices and applications that includes, for example, magnetoresistive random access memory, logic gates, diodes and transistors, nano-oscillators, radiofrequency modulators, and detectors. To control device performance, it is critical to understand the nature of the spin-torque-driven magnetic excitations (Berkov and Miltat 2008, Ralph and Stiles 2008, Slavin and Tiberkevich 2008).

8.2 Background

We need, thus, a mathematical model to describe the magnetization dynamics driven by spin-polarized currents in nanoscale spin-valve systems.

To do that, as briefly introduced in Section 8.1, at a mesoscopic scale we need to introduce a continuum model, in terms of magnetic polarization per unit volume, and to characterize the state of a generic ferromagnetic body by means of its free energy.

To this aim, let us consider a region occupied by a magnetic body. Let us now focus on a "small" region dV_r within the body denoted by the position vector $r \in \Omega$. We refer to a "small" region to indicate that the volume dV_r is large enough to contain a huge number N of elementary magnetic moments $\boldsymbol{\mu}_j$, $j = 1,\ldots, N$, but small enough so that the average magnetic moment varies smoothly. In this respect, we define the magnetization vector field $\mathbf{M}(\mathbf{r})$, so that the product $\mathbf{M}(\mathbf{r})dV_r$ represents the net magnetic moment of the elementary volume dV_r:

$$\mathbf{M}(\mathbf{r}) = \frac{\sum_{j=1}^{N} \boldsymbol{\mu}_j}{\mathrm{d}V_r} \tag{8.1}$$

Moreover, we assume that the magnetization is also a function of time *t*:

$$\mathbf{M} = \mathbf{M}(\mathbf{r}, t) \tag{8.2}$$

The main hypotheses of *micromagnetism* consist of considering the magnetization vector **M** to be a continuous function of the position **r** within the body and whose modulus $|\mathbf{M}| = M_S$ is constant in time.

It is well known that the magnetization configuration of a ferromagnetic body should be such as to minimize its free energy $G(X, H, T) = F(X, T) - HX$. In this equation, $F(X, T)$ is the Helmholtz free energy of the system, H is the external field, and X is the state variable. The local minima obey the condition $\partial G/\partial X = 0$, by which all the metastable states are found. The great complication is that, in a space-dependent approach, X represents the full magnetization vector field $\mathbf{M}(\mathbf{r})$ defined over the entire body volume. Thus, the energy minimization has to be carried out in the infinite-dimensional functional space of all possible magnetization configurations, which, from the mathematical point of view, constitutes a nontrivial issue.

To characterize the energy landscape, it is necessary to first introduce the principal energy terms that control the behavior of a ferromagnetic body and show how they compete with each other.

It is well known that the most significant contributions to the energy balance arise from Maxwellian fields (magnetostatic and Zeeman) and non-Maxwellian ones (exchange and anisotropy). Let us briefly discuss each of them.

8.2.1 Exchange Interactions

The exchange interactions, which are the *source of the ferromagnetism,* should be vigorously analyzed by means of quantum theory, since this latter strongly concerns with spin–spin interactions. More specifically, on a scale in the order of the atomic scale, the exchange interaction tends to align neighboring magnetic moments. In other words, whenever **M**(**r**) changes orientation from point to point, we have some misalignment of the neighboring magnetic moments and this costs extra exchange energy. In view of a continuum average analysis in terms of a magnetization vector field, we expect that the exchange interactions tend to produce small uniformly magnetized regions, indeed observed experimentally and called magnetic domains.

The contribution of exchange interactions to the free energy of the whole magnetic body can be expressed as (Brown 1962)

$$F_{\mathrm{ex}} = \int_{\Omega} A\left[(\nabla m_x)^2 + (\nabla m_y)^2 + (\nabla m_z)^2\right] \mathrm{d}V \tag{8.3}$$

where

the parameter A is called "exchange constant"

the integration is extended over the whole volume region Ω

8.2.2 Anisotropy

Anisotropic effects in ferromagnetic bodies arise from the structure of the lattice and from particular symmetries that are produced in certain crystals. The experimental evidence of the existence of such energy-favored directions can be observed in certain ferromagnetic materials when, in the absence of external fields, the magnetization vector tends to be magnetized along precise directions, which in literature are referred to as *easy directions*. The fact that there is a "force" that tends to align magnetization along easy directions can be taken into account, in the micromagnetic framework, by means of an additional phenomenological term in the free energy functional

$$F_{\mathrm{an}}(\mathbf{m}) = \int_{\Omega} f_{\mathrm{an}}(\mathbf{m})\,\mathrm{d}V \tag{8.4}$$

where $f_{\mathrm{an}}(\mathbf{m})$ is the anisotropy free energy density. In this phenomenological analysis, the easy directions correspond to the minima of the anisotropy energy density, whereas the saddle-points and maxima of $f_{\mathrm{an}}(\mathbf{m})$ determine the medium-hard axes and the hard axes, respectively.

8.2.3 Magnetostatic Interactions

Magnetostatic interactions represent the way the elementary magnetic moments interact over long distances within the body. In fact, the magnetostatic field at a given location within the body depends on the contributions from the whole magnetization vector field. We refer to this property as "nonlocal" character. Magnetostatic interactions can be taken into account by introducing the appropriate magnetostatic field $\mathbf{H}_m$ according to the Maxwell equations for magnetized media

$$\begin{cases} \nabla\cdot\mathbf{H}_m = -\nabla\cdot\mathbf{M} & \text{in } \Omega \\ \nabla\cdot\mathbf{H}_m = 0 & \text{in } \Omega^c \\ \nabla\times\mathbf{H}_m = 0 \end{cases} \tag{8.5}$$

where the quantity $-\nabla\cdot\mathbf{M} = \rho_M$ plays the role of "magnetic charge" density.

The system (8.5) has to be completed with the boundary conditions at the body discontinuity surface $\partial\Omega$

$$\begin{cases} \mathbf{n}\cdot[\mathbf{H}_m]_{\partial\Omega} = \mathbf{n}\cdot\mathbf{M} \\ \mathbf{n}\times[\mathbf{H}_m]_{\partial\Omega} = 0 \end{cases} \tag{8.6}$$

where

the quantity $\mathbf{n}\cdot\mathbf{M} = \sigma_M$ plays the role of "surface magnetic charge" density

n is the outward normal to the boundary $\partial\Omega$ of the magnetic body

$[\mathbf{H}_m]_{\partial\Omega}$ is the jump of the vector field $\mathbf{H}_m$ across $\partial\Omega$

The expression for the contribution of magnetostatic interactions to the free energy of the system is given by

$$F_m = -\int_{\Omega_\infty} \frac{1}{2}\mu_0 \mathbf{M}\cdot\mathbf{H}_m \mathrm{d}V \tag{8.7}$$

Equation (8.7) denotes the *nonlocal* character of the magnetostatic field, as it functionally depends, through the boundary value problem (8.6), on the spatial distribution of the magnetization vector field through the entire body volume.

8.2.4 External Field

When a magnetic body is subjected to an external bias field $\mathbf{H}_{\text{ext}}$, the contribution to the energy is simply

$$F_{\text{ext}} = -\int_{\Omega} \mu_0 \mathbf{M}\cdot\mathbf{H}_{\text{ext}}\, \mathrm{d}V \tag{8.8}$$

This energy term is referred to in literature as Zeeman energy.

8.2.5 Energy Balance and Free Energy Functional Formulation

It is now possible to summarize the role played by each of the previous energy terms described above. In fact, because each energy contribution favors different energy minima configurations, the metastable configuration arises from a sort of competition among them. For example, a magnetic material uniformly magnetized along its easy axis presents a low energy contribution arising from both exchange and magnetocrystalline anisotropy fields, but, at the same time, a higher contribution coming from both the magnetostatic and Zeeman fields (if the applied field direction is different from the easy axis). On the contrary, a configuration having a minimum magnetostatic energy is a closed-loop structure, but such a configuration presents higher contributions coming from all the other energy terms.

The expression for the free energy of the ferromagnetic body can hence be formulated by collecting the previous equations

$$\begin{aligned} G(\mathbf{M},\mathbf{H}_{\text{ext}}) &= F_{\text{ex}} + F_{\text{an}} + F_m + F_{\text{ext}} \\ &= \int_{\Omega} \left\{ A\left[(\nabla m_x)^2 + (\nabla m_y)^2 + (\nabla m_z)^2 \right] \right. \\ &\qquad \left. + f_{\text{an}} - \frac{1}{2}\mu_0 \mathbf{M}\cdot\mathbf{H}_m - \mu_0 \mathbf{M}\cdot\mathbf{H}_{\text{ext}} \right\} \mathrm{d}V \end{aligned} \tag{8.9}$$

which can be put in the compact form by expressing the exchange interaction energy density as $A(\nabla\mathbf{m})^2$

$$G(\mathbf{M},\mathbf{H}_{\text{ext}}) = \int_{\Omega} \left\{ A(\nabla\mathbf{m})^2 + f_{\text{an}} - \frac{1}{2}\mu_0 \mathbf{M}\cdot\mathbf{H}_m - \mu_0 \mathbf{M}\cdot\mathbf{H}_{\text{ext}} \right\} \mathrm{d}V \tag{8.10}$$

By using a variational calculus, we are able to introduce now the so-called *effective field* as the variational derivative of the energy density of the system

$$\mathbf{H}_{\text{eff}} = -\frac{\delta G}{\delta \mathbf{M}} = \frac{2}{\mu_0 M_S}\nabla\cdot(A\nabla\mathbf{m}) - \frac{1}{\mu_0 M_S}\frac{\partial f_{\text{an}}}{\partial \mathbf{m}} + \mathbf{H}_m + \mathbf{H}_{\text{ext}} \tag{8.11}$$

where M_S expresses the saturation magnetization of the body.

8.2.6 Equation of Motion

Once the effective field is defined, it is possible to present the so-called Landau–Lifshitz (LL) equation (Landau and Lifshitz 1935)

$$\frac{\partial \mathbf{M}}{\partial t} = -\gamma \mathbf{M}\times\mathbf{H}_{\text{eff}} \tag{8.12}$$

which expresses the undamped precessional dynamics of the magnetization vector along the direction of the effective field (γ is the gyromagnetic ratio).

We observe that the Landau–Lifshitz equation (8.12) is a *conservative* (Hamiltonian) equation. Nevertheless, dissipative processes take place within the dynamic magnetization processes. The microscopic nature of this dissipation is still not clear and is currently the focus of considerable research. The approach generally followed to take into account dissipation precesses consists of introducing damping in a *phenomenological* way. Landau and Lifshitz introduced an additional torque term that pushes magnetization in the direction of the effective field. Then, the damped *Landau–Lifshitz equation* becomes, in the Gilbert formulation, (Gilbert 2004)

$$\frac{\partial \mathbf{M}}{\partial t} = -\gamma \mathbf{M}\times\mathbf{H}_{\text{eff}} + \frac{\alpha}{M_S}\left(\mathbf{M}\times\frac{\partial \mathbf{M}}{\partial t} \right) \tag{8.13}$$

where α is the Gilbert damping parameter. To better understand the meaning of undamped and damped precessional dynamics, in Figure 8.4 we sketched the trajectories described by Equations 8.12 and 8.13, respectively.

By means of simple algebraic steps, it could be easily demonstrated that Equation 8.13 can be rewritten in the equivalent form


$\mathbf{H}_{\text{eff}}$
$-\mathbf{M}\times\mathbf{H}_{\text{eff}}$
$\mathbf{M}$
Undamped precession
$\mathbf{M}\times\frac{\partial \mathbf{M}}{\partial t}$
$\mathbf{H}_{\text{eff}}$
$-\mathbf{M}\times\mathbf{H}_{\text{eff}}$
$\mathbf{M}$
Damped precession

FIGURE 8.4 Comparison between undamped and damped precession.

$$\frac{\partial \mathbf{M}}{\partial t} = -\frac{\gamma}{1+\alpha^2}\mathbf{M}\times\mathbf{H}_{\text{eff}} - \frac{\gamma\alpha}{1+\alpha^2}\frac{1}{M_S}\mathbf{M}\times(\mathbf{M}\times\mathbf{H}_{\text{eff}}) \qquad (8.14)$$

where the damping term is now expressed as a double vector product. Such formulation brings the advantage of being an explicit expression for the time derivative of the magnetization so that, as it will be more clear in the next paragraph, it is more suitable to be implemented in a numerical framework.

8.2.7 Equation of Motion Including Spin-Transfer Torque Effects

At this stage, spin-polarized current has not yet been considered.

It has been demonstrated that current-induced spin-transfer effects in a spin-valve layered structure, such as the one sketched in Figure 8.3, are taken into account by including another torque term (Slonczewski 1996) into the equation of motion. The dynamic equation for magnetization dynamics driven by spin-polarized currents is called the Landau–Lifshitz–Gilbert–Slonczewski (LLGS) equation, and it is in the form

$$\frac{\partial \mathbf{M}}{\partial t} = -\gamma(\mathbf{M}\times\mathbf{H}_{\text{eff}}) + \frac{\alpha}{M_S}\left(\mathbf{M}\times\frac{\partial \mathbf{M}}{\partial t}\right) + \frac{\sigma I}{M_S}f(r)\left[\mathbf{M}\times(\mathbf{M}\times\mathbf{p})\right] \qquad (8.15)$$

In this case, **M** is the magnetization vector of the FL while **p** is the unit vector in the direction of spin-polarization (magnetization of the PL), I is the electric current traversing the spin-valve structure, the dimensionless function $f(r)$ describes the spatial distribution of the current across the area of the FL, and the parameter σ is given by

$$\sigma = \frac{g\mu_B}{2eM_S LS}\varepsilon(\mathbf{M},\mathbf{p}) \qquad (8.16)$$

where

g is the Landè factor
μ_B is the Bohr magneton
e is the modulus of the electron charge
L is the FL thickness
S is the area of the region involved by the current flow
$\varepsilon(\mathbf{M},\mathbf{p})$ is the dimensionless spin-polarization efficiency (Slonczewski 1996, 1999)

The latter parameter is, in general, a function of the relative alignment between PL and FL and of the material under investigation. In its original formulation, Slonczewski derived the expression

$$\varepsilon(\mathbf{M},\mathbf{p}) = \left[\frac{-4+(1+\eta^3)\left(3+(\mathbf{M}\cdot\mathbf{p}/M_{S_{\text{FL}}}M_{S_{\text{PL}}})\right)}{4\eta^{3/2}}\right]^{-1} \qquad (8.17)$$

with η being the polarization factor characteristic of the polarizing material. It has to be noticed, however, that in most cases, this dependence does not lead to any qualitative or significant quantitative effects and, especially when only a qualitative understanding of the problem is required, can it be approximated by a constant value (generally treated as a free parameter to fit experimental data).

By comparing the formulation of the dissipation torque in Equation 8.14 and the formulation of the spin-transfer torque in Equation 8.15, one observes that, for a proper direction of the applied current (and exactly for *positive* current, which conventionally means electrons flowing from the FL to the PL), these expressions present a similar vector structure but with opposite signs (Slonczewski 1999, Slavin and Kabos 2005). A way to understand how these effects work is to consider that, while dissipation pushes the magnetization vector *toward* the direction of $\mathbf{H}_{\text{eff}}$, the spin-transfer pushes the magnetization vector *away* from the direction of **p**. For such a reason, we might associate with the spin-transfer torque term the character of a “negative” damping, which opposes the natural “positive” Gilbert dissipation term (Slavin and Kabos 2005). The equality between these two terms represents the necessary condition under which stable persistent magnetization oscillations take place in a dissipative medium.

To give a complete picture on the mechanism underlying the process of spin-polarization and the subsequent spin-transfer torque effect, let us summarize in Figure 8.5 the FL magnetization dynamics occurring for both positive and negative currents.

The spin-polarization occurs via the absorption of the incident transverse spin current. The mechanism responsible for the transfer of the spin-angular momentum is the exchange interaction felt by electrons in the ferromagnet, which exerts a torque on the electron spins and, in turn, induces a reaction torque on the magnetization. In fact, let us consider the situation in which electrons incident from a nonmagnet are arranged


$I<0$
$\Delta\mathbf{m}_{\text{FL}}$
$\Delta\mathbf{m}_{\text{PL}}$
$\mathbf{m}_{\text{PL}}$
$\mathbf{m}_{\text{FL}}$
PL
FL
Stabilizes parallel alignment
Magnetic
Non magnetic
$I>0$
$\mathbf{m}_{\text{FL}}$
$\mathbf{m}_{\text{PL}}$
$\Delta\mathbf{m}_{\text{FL}}$
PL
FL
Stabilizes antiparallel alignment

FIGURE 8.5 Spin-transfer torque effects for both directions of the current.

over a distribution of states represented by three different incident directions. All of these electrons are in the same spin state, which is transverse to the ferromagnetic spin density (e.g., the magnetization of either FL or PL). The reflected electron spins have a predominantly minority character and undergo a random spin rotation whose precession axis is on average directed along the direction antiparallel to the one of the ferromagnet. The transmitted majority electron spins, on the other hand, precess along the direction parallel to the ferromagnetic spin density as they go into the ferromagnet because the wave vectors for the majority and minority components are different. It has to be pointed out that, although the proposed picture is qualitatively correct for most of the commonly used metal/ferromagnet interfaces (e.g., Cu/Co), additional phenomena (such as spin-dephasing and spin-accumulation) should be taken into account to get a quantitative understanding of the investigated dynamics (Stiles and Miltat 2006).

By looking at Figure 8.5 it turns out that, for negative current (top figure), the electrons crossing the interface metal/FL are on average polarized along the direction of the PL and the applied torque ($\Delta\mathbf{m}_{FL}$) favors the parallel alignment between the two magnetic layers. The back-torque operated by the reflected electrons on the PL ($\Delta\mathbf{m}_{PL}$) is generally negligible as the PL presents usually large values for saturation magnetization and thickness, which keep it fixed in its equilibrium state. On the contrary, for positive current (bottom figure), the electrons reflected from the PL hit the interface metal/FL with an antiparallel polarization with respect to that of the PL. In this case, the consequent torque causes a destabilization of the FL magnetization, which tries to favor an antiparallel configuration between the magnetization of the two layers.

These phenomena hold under two main assumptions: (1) the length of the nonmagnetic path that electrons experience between the two magnetic layers has to be smaller than a given characteristic length scale, named “spin-diffusion length” (according to the classical drift diffusion model of spin transport, the ensemble averaged spin of electrons drifting and diffusing in a solid decays exponentially with distance due to spin dephasing interactions) and (2) the thickness of the magnetic layers is assumed to be too great for appreciable tunneling of minority-spin electrons, therefore, the component antiparallel to the magnetization is totally reflected back into the nonmagnetic spacer, while the component parallel to the magnetization is totally transmitted into the magnetic layer.

Of course, it has to be recalled that the current-driven destabilization mechanism, apart from occurring only for a proper direction of the spin-polarized current, also exhibits a *threshold* character, i.e., there exists a given critical current above which the phenomena observable in such devices (reversal or persistent oscillations) take place. The simplest explanation lies in the energy that the applied current has to supply to the system in order to modify the energy landscape created by all the contributions of the effective field and to balance the natural positive dissipation (Slonczewski 1999, Slavin and Kabos 2005).

8.3 Computational Micromagnetics of Nanoscale Spin-Valves: State of the Art

Let us come back to the mathematical viewpoint by recalling that the influence of current-induced spin-transfer effects on the magnetization dynamics of nanoscale devices is expressed by the LLGS equation (Equation 8.15). This differential equation presents a complex nonlinear and nonlocal structure, which, in general, prevents the formulation of an exact analytical solution unless strong simplifying assumptions are imposed to the analyzed problem.

To gain a better physical understanding of the complicated magnetization dynamics, alternative strategies make use of the numerical integration of the equation of motion by means of different techniques, such as boundary element (BE), finite elements (FE), finite differences (FD), or hybrid procedures. Such approaches, to some extent, offer better-accuracy solutions, with respect to analytical approaches, simply because they generally use a smaller set of restrictions and simplifying hypotheses. Numerical tools can also be used to explore the range of validity of analytical theories, an analysis which sometimes could not be carried out otherwise.

On a practical level, when numerically solving partial differential equations, the primary challenge is to create an equation that approximates the equation to be studied. The main requirement is the numerical stability of the integration scheme, meaning that errors in the input data and intermediate calculations do not accumulate and cause the resulting output to deviate substantially from the exact solution or, in the worst case, to be meaningless.

Let us give a brief overview of the numerical methods cited above.

The BE method is a numerical computational method used to solve linear partial differential equations that have been formulated as integral equations, and is applicable to problems for which Green’s functions can be calculated. The boundary element method attempts to use the given boundary conditions to fit boundary values into the integral equation, rather than values throughout the space defined by a partial differential equation. Once this is done, in the post-processing stage, the integral equation can then be used again to numerically calculate the solution directly at any desired point in the interior of the solution domain. The boundary element method is often more efficient than other methods, including finite elements, in terms of computational resources for problems where there is a small surface/volume ratio even though it generally gives rise to fully populated matrices, which in turn yield a substantial increase of the storage and computational time requirements. In these cases, compression techniques might be applied, even though additional restrictions to the problem have to be added.

The FE method is a numerical technique for finding the approximate solutions of partial differential equations as well as of integral equations. The solution approach is based either on eliminating the differential equation completely (steady-state problems) or rendering the partial differential equation into an approximating system of ordinary differential equations, which are then numerically integrated using standard techniques (e.g., Euler's method, Runge-Kutta, etc.). In other words, the basic idea is to replace the infinite dimensional linear problem with a finite dimensional version. The algorithm can be subdivided into two steps: (1) rephrase the original problem in its weak or variational form and (2) discretize the weak form in a finite dimensional space. In step (2), one has to choose both finite-dimensional subspace of the original space and the shape functions that constitute the basis of the searched solution in that subspace. Because the original space is subdivided into a mesh of polygonal cells having whatever geometrical shape (triangular, tetragonal, etc.) the FE method is a good choice for solving partial differential equations when the computational domain presents a complex geometrical structure (e.g., for nonflat boundaries problems), but also when the desired precision varies over the entire domain or when the solution lacks smoothness (see Figure 8.6).

FD methods are numerical methods for approximating the solutions to differential equations using finite difference equations to approximate derivatives. The FD method implies a discretization of the computational region by using prismatic cells and then each derivative in the equation of motion has to be approximated (by using a given integration scheme) by a certain discretization.

A comparison between the FE and FD methods brings out the following main considerations:

- The FD method is an approximation of the differential equation, while the FE method is an approximation of the solution.
- The most attractive feature of the FE method lies in its ability to handle complex geometries (and boundaries) by means of a proper choice of the discretization cells. The FD method, on the contrary, in its basic formulation, is restricted to handle rectangular shapes.
- The most attractive feature of the FD method lies in the fact that it might be very easy to be implemented.



FIGURE 8.6 Example of mesh for FE methods with variable grid size to get a better resolution in correspondence of regions of interest.

Let us now focus on the usage of FD methods with the aim of showing how the numerical solution of the LLGS equation can be carried out and, at the same time, offer a brief overview of the state-of-the-art micromagnetic studies applied to nanoscale devices.

8.3.1 Numerical Solution of LLGS Equation Based on FD Methods

The first step of a numerical approach consists of subdividing the entire volume of the specimen by using a regular mesh of prismatic cells ($\Delta_x \times \Delta_y \times \Delta_z$), as in Figure 8.7.

To establish a proper dimension for the grid size, it is necessary to define before a fundamental quantity, named "exchange length," as follows:

$$l_{\text{ex}} = \sqrt{\frac{2A}{\mu_0 M_S^2}} \tag{8.18}$$

The exchange length gives an estimation of the characteristic dimension on which exchange interactions are dominant. For typical magnetic materials (e.g., silicon-iron alloys, called "Permalloy") l_{ex} is in the order of 5 ÷ 10 nm. Therefore, one expects that on a spatial scale in the order of l_{ex}, the magnetization is spatially uniform. For such a reason, within a micromagnetic framework, the cell size has to be smaller than the exchange length value, i.e., typically a cell-size as large as a 2 ÷ 5 nm-side is used. At the same time, the cell size should not be considered too small for at least two reasons: (1) the computational time should be kept in an affordable range and (2) the cell dimensions should be consistent with the mesoscopic scale.

Once the spatial discretization is addressed, the next step is to choose a proper time-step $\Delta\tau$. This value changes according to the integration scheme adopted, and the main constrain it has to satisfy is the convergence of the solution. To check that convergence, the criterion generally used is to analyze the time-evolution of the total system energy. Because of dissipation, the energy can only diminish, so that a gradual increase of the total energy reflects a divergent algorithm.



FIGURE 8.7 Example of mesh for FD methods.

Then, starting from an initial configuration of magnetization $\mathbf{m}(\mathbf{r},\tau)\ \forall\mathbf{r}\in V$, we compute the effective field $\mathbf{h}_{\text{eff}}(\mathbf{r},\tau) = \mathbf{h}_{\text{eff}}(\mathbf{m}(\mathbf{r},\tau),\tau)$ (see below for details) in each computational cell.

After that, it is necessary to apply a numerical integration scheme to solve the LLGS equation and to obtain the updated value of the magnetization distribution in the next time step $\tau + \Delta\tau$: $\mathbf{m}(\mathbf{r},\tau + \Delta\tau)\ \forall\mathbf{r}\in V$. Many integration schemes can be applied, either explicit or implicit, either with a fixed time-step or with an adaptive time-step (e.g., Euler, predictor-corrector, Runge-Kutta, mid-point, Adams-Bashforth-Moulton, Milne-Simpson, etc.). In most cases, one has to compute a finite differences representation for the derivate: that is the main reason why an explicit formulation for $\partial\mathbf{M}/\partial t$, like the one in Equation 8.14, is preferable with respect to the one shown in Equation 8.13.

Because our goal is to model the dynamic behavior of spintronic devices having a spin-valve structure as the one presented in Section 8.2, it is now necessary to focus on some aspects related to the implementation of the effective field for such devices. In the cases under investigation, the effective field has to be updated to take into account the additional contributions:

$$\mathbf{H}_{\text{eff}} = \mathbf{H}_{\text{ex}} + \mathbf{H}_{\text{an}} + \mathbf{H}_{\text{m}} + \mathbf{H}_{\text{ext}} + \mathbf{H}_{\text{mc}} + \mathbf{H}_{\text{Amp}} + \mathbf{H}_{\text{eddy}} + \mathbf{H}_{\text{th}} \tag{8.19}$$

Here $\mathbf{H}_{\text{ex}}$, $\mathbf{H}_{\text{an}}$, $\mathbf{H}_{\text{m}}$, and $\mathbf{H}_{\text{ext}}$ represent the exchange, anisotropy, magnetostatic, and external field contributions already introduced previously. The new contributions arise from $\mathbf{H}_{\text{mc}}$, which represents the magnetostatic coupling between PL and FL (it has to be distinguished from $\mathbf{H}_{\text{m}}$, which is the self-magnetostatic, or demagnetizing, field induced by the magnetization of each layer within its volume); $\mathbf{H}_{\text{Amp}}$, which represents the Ampère (or Oersted) magnetic field created by the current flow; $\mathbf{H}_{\text{eddy}}$, the field contribution arising from eddy currents; and $\mathbf{H}_{\text{th}}$, which represents the stochastic contribution arising from thermal noise.

Let us now give some details about the numerical implementation of each contribution within a FD micromagnetic framework. To do that, we will use a normalized notation, where each term is divided by the saturation magnetization value and written in lowercase letter, e.g., $\mathbf{m} = \mathbf{M}/M_S$.

The exchange field, $\mathbf{h}_{\text{exc}}$, is computed by considering the discrete expression for the exchange energy

$$f_{\text{ex}}(i,j,k) = A\left[\left(\nabla m_x(i,j,k)\right)^2 + \left(\nabla m_y(i,j,k)\right)^2 + \left(\nabla m_z(i,j,k)\right)^2\right] \tag{8.20}$$

where we used the notation for each Cartesian component $\alpha = x,y,z$

$$(\nabla m_\alpha)^2 = \left(\frac{\partial m_\alpha}{\partial x}\right)^2 + \left(\frac{\partial m_\alpha}{\partial y}\right)^2 + \left(\frac{\partial m_\alpha}{\partial z}\right)^2 \tag{8.21}$$

Under the approximation of finite differences, the derivative is substituted by the incremental differences (computed at the center of each cell), that is

$$(\nabla m_\alpha)^2 \approx \left(\frac{\Delta_x m_\alpha}{\Delta x}\right)^2 + \left(\frac{\Delta_y m_\alpha}{\Delta y}\right)^2 + \left(\frac{\Delta_z m_\alpha}{\Delta z}\right)^2 \tag{8.22}$$

where Δx, Δy, Δz are the sizes of the computational cells, whereas Δ_x, Δ_y, Δ_z represent the finite difference operators along the Cartesian axes x, y, z. Let us consider the magnetization vector $\mathbf{M}(i, j, k) = M_S\mathbf{m}(i,j,k)$ at the point (i,j,k) and $\mathbf{M}(i+1, j, k) = M_S\mathbf{m}(i+1, j, k)$ the corresponding vector at the neighboring cell $(i+1, j, k)$ in the x direction. We can rewrite the expression (8.22) as follows:

$$\begin{aligned}\left(\frac{\Delta_x m_\alpha}{\Delta x}\right)^2 &= \left(\frac{m_x(i+1,j,k) - m_x(i,j,k)}{\Delta x}\right)^2\\ &= \frac{m_x^2(i+1,j,k) - 2m_x(i+1,j,k)m_x(i,j,k) + m_x^2(i,j,k)}{\Delta x^2}\end{aligned} \tag{8.23}$$

By taking into account that $|\mathbf{m}(i, j, k)| = 1\ \forall\ (i, j, k)$, the expression (8.23) can be simplified as

$$\left(\frac{\Delta_x m_\alpha}{\Delta x}\right)^2 = \frac{1}{\Delta x^2}\left[2 - 2m_x(i+1,j,k)m_x(i,j,k)\right] \tag{8.24}$$

Also, by taking into account the neighboring cell in the negative directions, one ends up with

$$\begin{aligned}\left(\nabla m_x\right)^2 \approx{}& \frac{1}{\Delta x^2}\Big[\big(2 - 2m_x(i+1,j,k)m_x(i,j,k)\big) + \big(2 - 2m_x(i,j,k)m_x(i-1,j,k)\big)\Big]\\ &+ \frac{1}{\Delta y^2}\Big[\big(2 - 2m_x(i,j+1,k)m_x(i,j,k)\big) + \big(2 - 2m_x(i,j,k)m_x(i,j-1,k)\big)\Big]\\ &+ \frac{1}{\Delta z^2}\Big[\big(2 - 2m_x(i,j,k+1)m_x(i,j,k)\big) + \big(2 - 2m_x(i,j,k)m_x(i,j,k-1)\big)\Big]\end{aligned} \tag{8.25}$$

Under the hypothesis of cubic cells ($\Delta x = \Delta y = \Delta z$), we can generalize Equation 8.25 to the case of $N_x \times N_y \times N_z$ cells (along the x, y, and z axis, respectively) as follows:

$$\begin{aligned}f_{\text{ex}}(i,j,k) &= \frac{2A}{\Delta x^2}\sum_{i'=1}^{N_x}\sum_{j'=1}^{N_y}\sum_{z'=1}^{N_z}\left[1 - \mathbf{m}(i,j,k)\mathbf{m}(i',j'k')\right]\\ &= \frac{2A}{\Delta x^2}N_xN_yN_z - \frac{2A}{\Delta x^2}\mathbf{m}(i,j,k)\sum_{i'=1}^{N_x}\sum_{j'=1}^{N_y}\sum_{z'=1}^{N_z}\mathbf{m}(i',j'k')\end{aligned} \tag{8.26}$$

The exchange field is computed by using the functional derivative of the energy ($\delta/\delta\mathbf{m}$), which becomes the ordinary derivative ($\partial/\partial\mathbf{m}$) in the discrete domain:

$$h_{\text{exc}}(i,j,k) = -\frac{1}{\mu_0 M_S{}^2}\frac{\partial f_{\text{ex}}(i,j,k)}{\partial\mathbf{m}(i,j,k)} \tag{8.27}$$

By substituting Equation 8.26 into Equation 8.27, one obtains the final implementation of the six-neighbors exchange field:

$$h_{\text{exc}}(i,j,k) = \frac{2A}{\mu_0 M_S^2}\left[\frac{\mathbf{m}(i+1,j,k)+\mathbf{m}(i-1,j,k)}{\Delta x^2} + \frac{\mathbf{m}(i,j+1,k)+\mathbf{m}(i,j-1,k)}{\Delta y^2} + \frac{\mathbf{m}(i,j,k+1)+\mathbf{m}(i,j,k-1)}{\Delta z^2}\right] \tag{8.28}$$

It should be pointed out that the partial derivative approximation for finite differences holds for small arguments, that is, when the angle formed between the magnetization vectors in two adjacent cells is small.

The anisotropy field, $\mathbf{h}_{\text{an}}$, in the case of uniaxial anisotropy, is simply computed by

$$h_{\text{ani}}(i,j,k) = \frac{2K_C}{\mu_0 M_S^2}\left(\mathbf{m}(i,j,k)\cdot\mathbf{u}_{\text{K}}\right)\mathbf{u}_{\text{K}} \tag{8.29}$$

where

K_C is the anisotropy constant

$\mathbf{u}_{\text{K}}$ is the direction of uniaxial anisotropy

Both magnetostatic fields ($\mathbf{H}_{\text{m}}$ and $\mathbf{H}_{\text{mc}}$) are computed by using the generalization of the demagnetizing tensor given in (Newell et al. 1993)

$$h_{m,\alpha}(i,j,k) = \sum_{\beta}^{(x,y,z)}\sum_{i'=1'}^{N_x}\sum_{j'=1}^{N_y}\sum_{z'=1}^{N_z} N_{\alpha\beta}(i-i',j-j',k-k')m_{\beta}(i',j',k') \tag{8.30}$$

where

$h_{m,\alpha}$ represents the component of the magnetostatic field

$N_{\alpha,\beta}(i-i',j-j',k-k')$ are the components of the Newell magnetostatic tensor, which only depend on both the distance between the source and the cell position, and the specimen geometry

The expression (8.30) presents the form of a three-dimensional convolution in the "*coordinates space*" (x,y,z). By using the *Convolution Theorem*, it is possible to express the previous convolution as a product scalar in the "*Fourier space*," or phases space (k_x,k_y,k_z):

$$\begin{aligned}\tilde{h}_{m,\alpha}(k_x,k_y,k_z) &= \Im\left[h_{m,\alpha}(i,j,k)\right]\\ &= \sum_{\beta}^{(x,y,z)}\Im\left[N_{\alpha\beta}(i,j,k)\right]\Im\left[m_{\beta}(i,j,k)\right]\\ &= \sum_{\beta}^{(x,y,z)}\tilde{N}_{\alpha\beta}(k_x,k_y,k_z)\tilde{m}_{\beta}(k_x,k_y,k_z)\end{aligned} \tag{8.31}$$

To calculate the magnetostatic field, $\mathbf{h}_{\text{m}}$, it is necessary to follow these steps: (1) calculate the Newell tensor coefficients $N_{\alpha,\beta}$; (2) perform the FFT of the previous tensor $\tilde{N}_{\alpha\beta}$; (3) perform the FFT of the magnetization distribution in each cell $\tilde{m}_{\beta}$; and (4) perform the inverse FFT of the inner product between $\tilde{N}_{\alpha\beta}$ and $\tilde{m}_{\beta}$:

$$\begin{aligned}h_{m,\alpha}(i,j,k) &= \Im^{-1}\left[\tilde{h}_{m,\alpha}(k_x,k_y,k_z)\right]\\ &= \Im^{-1}\left[\sum_{\beta}^{(x,y,z)}\Im\left[N_{\alpha\beta}(i,j,k)\right]\Im\left[m_{\beta}(i,j,k)\right]\right]\end{aligned} \tag{8.32}$$

By denoting with N the total number of grid cells, such approach brings a computational complexity that grows as $N\log N$.

The external field $\mathbf{h}_{\text{ext}}$ is simply computed, in the limit of uniform fields, by applying the corresponding components of the external field to each computational cell:

$$h_x(i,j,k) = \mathbf{h}_{\text{ext}}\cdot\hat{\mathbf{e}}_{\mathbf{x}},\quad h_y(i,j,k) = \mathbf{h}_{\text{ext}}\cdot\hat{\mathbf{e}}_{\mathbf{y}},\quad h_z(i,j,k) = \mathbf{h}_{\text{ext}}\cdot\hat{\mathbf{e}}_{\mathbf{z}} \tag{8.33}$$

Moreover, once we inject an electric current density $\mathbf{J} = J_0\mathbf{e}_{\mathbf{z}}$ into a spin-valve stack composed by ferromagnetic and metallic materials, a new magnetic field is generated according to the Ampère (or Oersted) law. The values of the *Ampère field*, $\mathbf{H}_{\text{Amp}}$, in each point of the volume can be calculated by using the Ampère law:

$$\nabla\times\mathbf{H}_{\text{Amp}}(\mathbf{r},t) = \mathbf{J}(\mathbf{r},t) \tag{8.34}$$

The Ampère field is a solenoidal field and thus exhibits the following properties:

$$\begin{cases}\nabla\cdot\mathbf{H}_{\text{Amp}}(\mathbf{r},t) = 0\\ \nabla\times\mathbf{H}_{\text{Amp}}(\mathbf{r},t) = \mathbf{J}(\mathbf{r},t)\end{cases} \tag{8.35}$$

An additional contribution arises from *eddy currents*. An eddy current (also known as a Foucault current) is an electrical phenomenon discovered by Léon Foucault in 1851. It is caused when a moving (or changing) magnetic field intersects a conductor or vice-versa. The relative motion causes a circulating flow of electrons, or current, within the conductor. These circulating eddies of current create electromagnets with magnetic fields that oppose the effect of the applied magnetic field (see Lenz's law). The stronger the applied magnetic field, or the greater the electrical conductivity of the conductor, or the greater the relative velocity of motion, the greater the currents developed and the greater the opposing field. The Maxwell equations for eddy currents are given by

$$\begin{cases}\nabla\times\mathbf{H}_{\text{eddy}}(\mathbf{r},t) = \sigma'\mathbf{E}(\mathbf{r},t) + \varepsilon'\dfrac{\partial\mathbf{E}(\mathbf{r},t)}{\partial t}\\ \nabla\cdot\mathbf{H}_{\text{eddy}}(\mathbf{r},t) = 0\\ \nabla\times\mathbf{E}(\mathbf{r},t) = -\dfrac{\partial\mathbf{B}(\mathbf{r},t)}{\partial t}\\ \nabla\cdot\mathbf{E}(\mathbf{r},t) = 0\end{cases} \tag{8.36}$$

where

σ' is the electrical conductivity
ε' is the electric permeability
$\mathbf{E}$ is the electric field

To perform an analogy between $\mathbf{H}_{\text{Amp}}(\mathbf{r}, t)$ and $\mathbf{H}_{\text{eddy}}(\mathbf{r}, t)$, in the former the source of the field is given by the applied current density $\mathbf{J}(\mathbf{r}, t)$, whereas in the latter the sources of the field are given by both the time variation of the magnetic field $-\partial\mathbf{B}(\mathbf{r}, t)/\partial t$ and the conduction current $\mathbf{J}_C = \sigma'\mathbf{E}(\mathbf{r}, t) + \varepsilon'(\partial\mathbf{E}(\mathbf{r}, t)/\partial t)$. The effects of eddy currents become relevant with an increase in the device volume and, since we will deal with structures with relative small volumes, this contribution is generally disregarded (Martinez et al. 2004).

It has to be noted that both $\mathbf{H}_{\text{Amp}}$ and $\mathbf{H}_{\text{mc}}$ are nonuniform fields so that their effects cannot be correctly evaluated by using *macrospin* models (by "macrospin" we mean a particle that remains homogeneously magnetized independently of external conditions). Figures 8.8 and 8.9 show examples of the spatial configuration of these fields for a structure having circular and rectangular cross-sections, respectively.

The last contribution to the effective field arises from the effect of thermal fluctuations (or noise) on the magnetization dynamics of nanoscale devices. Considering that experimental data are well described by the current dependent activation barriers that agree with the prediction of the LLG-based models (Garcia-Palacios and Lazaro 1998, Krivorotov et al. 2004, Li and Zhang 2004), it is possible to include in a micromagnetic framework a thermal field as an additive random field to the deterministic effective field for each cell. It is done by starting from the formalism of Brownian motion (Gardiner 1985, Kloeden and Platen 1999).



FIGURE 8.8 Spatial distribution of (a) Ampère field and (b) magnetostatic coupling field for a device having a circular cross-section.



FIGURE 8.9 Spatial distribution of (a) Ampère field and (b) magnetostatic coupling field for a device having a rectangular cross-section.

In this case, the previous deterministic equation become a stochastic one, named the *Langevin equation*. The fluctuating term, which appears in the Langevin equation presents an integral structure that needs to be analyzed by using the theory of stochastic processes (Brown 1963, 1979, Garcia-Palacios and Lazaro 1998).

From the physical point of view (Garcia-Palacios and Lazaro 1998), the more appropriate interpretation of those stochastic integrals is called the *Stratonovich interpretation*. In this sense, Brown (1963, 1979) developed the *Fokker–Planck equation* to study the temporal evolution of nonequilibrium probability distributions. Several techniques have been developed to solve the Fokker–Planck equation. Some of those allow the direct computation of the probability distribution of magnetization, while others numerically compute the eigenvalues and amplitudes of the most relevant dynamics modes. Instead of solving the Fokker–Planck equation, an approximation is to build the solutions of the Langevin equation (Garcia-Palacios and Lazaro 1998). The Langevin dynamics gives origin to the stochastic trajectories of the system variables (time-evolution of magnetization) and, starting from this approach, we can compute the statistic behavior by averaging over many realizations (for "realizations" we mean a particular statistic trajectory obtained by starting from a given sequence of aleatory numbers for the statistic system variables).

From the computational point of view, we should take into account that thermal fluctuations in magnetic media occur at correlation times much shorter than the typical response time of magnetic systems (Brown 1963, 1979). In other words, thermal fluctuations arise from high-frequency perturbations. The thermal field that is generally used to simulate thermal effects can be therefore represented as a *Wiener stochastic process* (Van Kampen 1987). Moreover, because fluctuations arise from the interaction between magnetization and an enormous number of microscopic degrees of freedom (phonons, conduction electrons, nuclear spins, etc.) having equivalent stochastic properties, it is generally assumed that the above stochastic process can be treated as a *Gaussian white noise* (Brown 1963, Garcia-Palacios and Lazaro 1998). The same microscopic degrees of freedom are responsible for the relaxation of the magnetization precession, because fluctuations and dissipation are phenomena strictly related each other (*Fluctuation-Dissipation Theorem*). Because of those degrees of freedom, the thermal field $\mathbf{H}_{\text{th}}$, to be added to the deterministic effective field, has to satisfy the properties of a Gaussian stochastic vector process.

This leads to a definition of the stochastic Langevin–Landau–Lifshitz–Gilbert (LLLG) equation. In order to also take into account the spin-torque term within this new formulation, the main hypotheses are: (1) the spin torque does not contain a fluctuating field, (2) the fluctuating field does not depend on spin torque, and (3) the magnetization configuration of the PL does not depend on temperature.

The thermal field, $\mathbf{H}_{\text{th}}$, is hence included as a random fluctuating three-dimensional vector quantity given by

$$\mathbf{H}_{\text{th}} = \xi\sqrt{2\frac{\alpha}{1+\alpha^2}\frac{k_B T}{\mu_0 \gamma' \Delta V M_S \Delta t}} \tag{8.37}$$

where

k_B is the Boltzmann constant

ΔV is the volume of the computational cubic cell

Δt is the simulation time-step

T is the temperature of the sample

$\gamma' = \gamma/(1 + \alpha^2)$

ξ is a Gaussian stochastic process

The thermal field satisfies the following statistical properties:

$$\begin{cases} \langle H_{\text{th},k}(t) \rangle = 0 \\ \langle H_{\text{th},k}(t) H_{\text{th},l}(t') \rangle = D\delta_{kl}\delta(t - t') \end{cases} \tag{8.38}$$

where k and l represent the Cartesian coordinates x, y, and z. According to this, each component of $\mathbf{H}_{\text{th}}$ is a space and time independent random Gaussian distributed number (Wiener process) with zero mean value. The constant D measures the strength of thermal fluctuations and its value is obtained from the Fokker–Planck equation.

Finally, the micromagnetic framework has to be completed with proper boundary conditions, which describe the behavior of the magnetization vector at the computational boundaries. The formulation of boundary conditions is therefore dependent on the geometry under investigation. Some examples will be given in Section 8.3.3.

8.3.2 Spin-Transfer Torque and Giant Magnetoresistance: Dual Phenomena

In Section 8.3.1, we described the spin-transfer torque mechanism and showed the dynamic equation of motion for the magnetization which includes this effect. We described that, if a spin-polarized current presents proper sign and amplitude, it may destabilize the equilibrium configuration of the magnetization of the thinner FL leading it to either a reversal process or a persistent precession. Lots of questions could immediately follow such analysis: are these phenomena so interesting to deserve potential applications in the field of information technology? If yes, how do we observe and detect experimentally these magnetization dynamics?

The answer lies in the existence of another phenomenon, called giant magnetoresistance (GMR), which can be considered the dual mechanism of the spin-transfer torque (STT). Observing the phenomena from a more general viewpoint, we can describe the STT as the mechanism by which we account for the modifications of the magnetic state of a system induced by an electric current. For duality, the GMR effect (Baibich et al, 1988, Parkin et al. 1990, 1991, Schad et al. 1994) accounts for the variations of the electrical state of a system induced by the magnetic state (see Figure 8.10). For the discovery of the GMR effect, Fert and Gruenberg shared the Nobel Prize for Physics in 2007.


Magneto resistance
Electron transport is affected by magnetic state
Spin-transfer-torque
Magnetic state is affected by electron transport

FIGURE 8.10 STT and GMR effects as dual mechanisms.

The GMR is a quantum-mechanical effect observed in thin film structures composed of alternating ferromagnetic and nonmagnetic metal layers and arises from the spin-dependent scattering of conduction electrons by spins in ferromagnetic layers. When the spin of ferromagnetic layers is anti-parallel to the conduction electrons, then the scattering is increased. Therefore, the magnetoresistivity will be varied by the relative orientation of magnetization in neighboring ferromagnetic layers separated by a nonmagnetic metallic thin layer. In detail, the GMR effect manifests itself as a significant decrease in resistance from the zero-field state, when the magnetization of adjacent ferromagnetic layers are antiparallel due to a weak anti-ferromagnetic coupling between layers, to a lower level of resistance when the magnetization of the adjacent layers align due to an applied external field. The spin of the electrons of the nonmagnetic metal align parallel or antiparallel with an applied magnetic field in equal numbers, and therefore suffer less magnetic scattering when the magnetizations of the ferromagnetic layers are parallel.

In the analyzed case of the three-layers system, it behaves as a spin-valve for electron transport from one ferromagnetic layer to the other. The relative alignment of the magnetization vectors of the two ferromagnetic layers can be easily detected by measuring the system resistance (see Figure 8.11). At the same time, it is possible to associate two different logic states to the different electric configurations (e.g., bit 0 = low-resistance state, bit 1 = high-resistance state). This is the basic working principle of magnetoresistive random access memories (MRAM). On the other hand, if the magnetization undergoes a persistent precession, the output signal might manifest itself as a periodic variation of the resistance of the device, which could be used to build up nanoscale oscillators.

8.3.3 Nanoscale Devices: Pillar vs. Point-Contact

Within the class of nanoscale devices, the two most common experimental geometries are the so-called nano-pillar and nano-contact (or point-contact).



FIGURE 8.11 A schematic of a GMR-based spin-valve GMR showing a higher resistance state in the anti-parallel configuration with respect to the parallel one.

The main differences existing between them involve both the lateral sizes and the current density distribution. In fact, nano-contact devices generally present larger lateral dimensions (in the order of tenths of microns) with respect to those of nano-pillar (hundreds of nanometers). In addition, the perpendicular-to-plane applied current involves the whole physical (cross-section) area of pillar devices, whereas only a reduced region (the contact area, typically of the radius of 10–80 nm) is involved in nano-contact devices (see Figure 8.12).

The nano-pillar structure is widely used as an elementary memory cell where spin-polarized current drives the process of magnetization reversal (or switching), even in the absence of an external bias magnetic field.

On the other hand, the nano-contact geometry becomes particularly suitable to design microwave spin-transfer oscillators with very narrow linewidths because it combines the advantages of having a larger effective volume (with respect to pillar devices) (Kim et al. 2008) and a negligible influence of edge roughness and defects (Rippard et al. 2004). In fact, in the case of extended nano-contact geometry (also referred to as "nonconfined" systems), the FL is not bounded in the plane; therefore, the magnetic oscillations induced by spin-polarized current can excite spin-wave modes, which propagate through the FL material (in analogy to the radiation of electromagnetic waves via a transmitting antenna). On the contrary, the finite sizes of a nano-pillar device make it more similar to a magnetic resonator because of its reflecting boundaries. In fact, the spin-wave eigenmodes of such resonators, even though they could be spatially nonuniform, can have only a discrete frequency spectrum determined by the finite in-plane sizes of the device.



FIGURE 8.12 Nano-pillar and nano-contact spin-valve geometries.

The structural differences between these two geometries imply not only different technological applications, but also require different approaches in the corresponding numerical investigations.

In fact, the micromagnetic study of the dynamics involved in a nano-pillar device can be carried out by directly applying the hints given in Sections 8.3.1 and 8.3.2 with the inclusion of normal boundary conditions at the computational edges (which also correspond to the physical edges, because of the finite dimensions):

$$\left.\frac{\partial \mathbf{m}}{\partial \mathbf{n}}\right|_{\partial\Omega} = 0 \tag{8.39}$$

($\mathbf{n}$ is the versor of the normal to the boundary $\partial\Omega$). We should notice that the normal derivative is different from zero only if surface anisotropy effects are taken into account.

On the other hand, the analysis of dynamics involved in nano-contact geometry requires a more sophisticated approach. In fact, one of the difficulties of FD methods lies in the fact that the investigated motion equation has to be solved in a discretized domain which, if applied to extended areas, would require prohibitive memory allocation and computational times. This is the case of nano-contact devices.

Nevertheless, theoretically boundless space extension problems have been solved by using special conditions at the boundaries of the reduced computational domain, in order to absorb the outgoing waves. Such a need for free-space simulation happens in a lot of physical problems and especially in wave-structure interactions.

Following the previous discussions, it is clear that FD techniques applied to extended geometries impose the numerical implementation of computational areas smaller than the physical ones. Therefore, it is necessary to develop a method for the waves absorption at the artificial boundaries to prevent the reflections of the propagating spin wave modes from these boundaries that, in a medium with relatively low dissipation (as Permalloy), might occur otherwise. If proper absorbing boundary conditions (ABC) are not considered, a spurious (purely computational) interference occurs which, in turn, can introduce a substantial distortion in the computed picture of the phenomenon and can seriously affect the properties of the excited spin-waves. As it will be shown below, due to the impossibility of implementing some sort of analytical operators within a micromagnetic framework for point-contact geometries, absorbing boundary conditions based on spatial-dependent damping functions have to be introduced.

The problem of finding the exact analytical formulation of the perfectly absorbing conditions for spin waves at the edges of the computational region has not been solved so far. The analytical formulation of ABC generally requires the knowledge of the exact wave solution (Enquist and Majda 1977, Renaut 1992, Alpert et al. 2002). In fact, the most general first-order analytical formulation for local ABC was introduced by Higdon (1987) as follows:

$$\left[\cos\theta\frac{\partial}{\partial t}-c\frac{\partial}{\partial x}\right]U=0 \tag{8.40}$$

where the Higdon operator is enclosed in brackets and it is used to completely absorb plane waves U propagating with speed c at the angles $\pm\theta$ with respect to the x axis. Unfortunately, from the numerical point of view, the lack of knowledge of the exact spin-wave velocity c does not allow the implementation of this formalism within a micromagnetic framework. Moreover, if we restrict the analysis to the case of perpendicular incidence (where $\cos\theta = 0$), the previous condition becomes the common boundary condition (see Equation 3.22) used in the modeling of the finite specimen $\partial U/\partial x = 0$, which cannot assure the waves absorption at each boundary.

Consequently, we need an alternative numerical strategy for the waves absorption at the computational boundaries. The attempts to find such conditions in numerical simulations have been undertaken by assuming that magnetic dissipation in the magnetic medium of the FL increases near the borders of the computational region according to a certain chosen empirical dependence on coordinates (Berkov and Gorn 2006, Consolo et al. 2007a,c). Following this idea, a micromagnetic approach could be generalized by including a site-dependent damping function in the model.

A possible scheme was first introduced by Berkov et al. in (Berkov and Gorn 2006) where the damping parameter was considered to vary between its physical value (α_O) and a higher artificial one ($\alpha_O + 2\Delta\alpha$) in a *smoothed* way, which starts at the distance from the center $r \approx (R_O - \sigma_\alpha)$ and involves a ring with a width of $\approx 2\sigma_\alpha$:

$$\alpha(r)=\alpha_O+\Delta\alpha\left(1+\tanh\frac{r-R_O}{\sigma_\alpha}\right) \tag{8.41}$$

The ABC introduced by Berkov are based on the following three main assumptions:

1. The dissipation within and nearby the contact area must be equal to its physical value.
2. Dissipation far from the contact area and close to the simulated boundaries must be large enough to ensure the wave energy absorption.
3. The spatial variation between these two values must be smooth enough to prevent wave reflection at the boundary.

Leaving the first two Berkov's assumptions unchanged, an alternative approach has been proposed in Consolo et al. (2007c) for perpendicular-to-plane magnetized films, and is based on the following requirements:

1. Creating a nonphysical absorbing medium surrounding the computational area
2. Considering a damping coefficient two orders of magnitude greater than the physical one just in the boundary cells
3. Entirely preserving the physical properties of the computational area

It has to be pointed out that, in spite of the formal equivalence between these empiric procedures and of the effectiveness of both procedures to absorb sufficiently well outgoing waves, the latter proposal, differently from the first one, allows the preservation of the physical properties in a larger computational area since it is based on the association of a localized *abrupt* change of the energy absorption at the computational boundaries

$$\begin{cases}\alpha(r)=\alpha_O & \text{for } r<R\\ \alpha(r)=m\cdot\alpha_O & \text{for } r=R\end{cases} \tag{8.42}$$

where

R is the radius of the computational area
m is the factor that amplifies the dissipation at the boundaries

Finally, as briefly introduced above, we need to mathematically formulate the difference existing in the spatial distribution of current for pillar and nano-contact devices, which is expressed by a proper choice of the dimensionless function $f(r)$ in Equation 8.15.

In particular, for pillar devices, by assuming a uniform current density distribution, it is quite straightforward to consider it as

$$\begin{cases}f(r)=1 & \text{for } r\le R\\ f(r)=0 & \text{for } r>R\end{cases} \tag{8.43}$$

which simply implies that all the computational cells are traversed by the same current value I.

On the other hand, for nanocontact geometry, it has to be taken into account that the current flow involves only the contact region of radius R_C so that, under the same condition of uniformity, we consider

$$\begin{cases}f(r)=1 & \text{for } r\le R_C\\ f(r)=0 & \text{for } r>R_C\end{cases} \tag{8.44}$$

which implies that only the computational cells within the contact area are traversed by the current I, whereas there exists an abrupt cut-off of the current outside the contact. While such an approximation is physically unrealistic, it has been demonstrated that it is able to capture most of the dynamics observed in laboratory experiments. However, more sophisticated shape functions can be derived by numerically solving the *Poisson equation* to get the corresponding current density distribution through the whole computational area.

8.4 Conclusions and Future Perspective

In this contribution, we presented a brief overview of a micromagnetic technique that is used to investigate the behavior of nanoscale spintronic devices. It is based on the numerical integration of the nonlinear LLGS equation. After developing a full-scale FD micromagnetic tool, a question might be asked. Is it possible to develop a framework simpler than the micromagnetic one but that allows for a gain in the equivalent understanding of the complex magnetization dynamics? Actually, magnetization dynamics might be most easily investigated using *macrospin* (less properly called "single-domain") approximation. The macrospin approximation assumes that the magnetization of a sample stays spatially uniform throughout its motion and can be treated as a single macroscopic spin. Since the spatial variation of the magnetization is frozen out, exploring the dynamics of magnetic systems is much more tractable using the macrospin approximation than it is using full micromagnetic simulations. The macrospin model makes it easy to explore the phase space of different torque models, and it has been a very useful tool for gaining a *zeroth-order* understanding of spin-torque physics. On the other hand, it obviously suffers from some intrinsic limitations (e.g., the impossibility of reproducing the nonuniform spatial distribution of magnetization and fields), which sometimes prevents the possibility of mimicking experimental data. It is possible to estimate qualitatively the critical size for which a macrospin approximation could be considered still sufficiently appropriate. It mainly depends on the competition between exchange and magnetostatic energy: the former favoring collinear (uniform) magnetic state, the latter favoring closed-flux configurations. As the exchange energy density of the closed-loop configuration obviously increases with decreasing particle size (because magnetization gradients become larger), it leads to the result that only a collinear magnetization state is energetically stable below a certain critical size. It could be demonstrated that such critical length-scale is about—four to eight times the exchange length (about 20–40 nm for usual soft magnetic materials).

On the other hand, micromagnetic frameworks offer a powerful tool for investigating magnetization phenomena occurring at the mesoscopic scale because of the accurate spatial resolution (few nanometers) and of the theoretically infinite bandwidth (restricted only by the integration time step). Because of that, it is also possible to gain additional information on the investigated problem, which could not be acquired from a laboratory experiment.

How can we summarize this issue between an accurate but time-consuming micromagnetic approach and a fast and often oversimplified macrospin model?

Let us recall that full-scale simulations are supposed to include more (and not fewer) known features of the investigated system than macrospin models and, at the same time, use fewer free (adjustable) parameters. Because of that, if a simplified macrospin approach were able to produce a better agreement with experiment than a micromagnetic approach, it would imply an incomplete comprehension of some crucial properties of the system under study. In other words, it does not necessarily mean that a wrong choice of the values of parameters has been considered, but rather it should recall for further studies to gain a better understanding of the problem, which in turn should bring some corrections to the model. Moreover, because full-scale simulations are quite time-consuming, it is necessary to get an accurate knowledge of the system parameters, together with their spatial dependence (especially near critical regions, such as close to the edges) from independent sources, such as a high-quality experiment. Such information is of crucial importance for the modeling of nano-scale devices due to their extremely small sizes.

What about present and future applications of micromagnetic framework?

So far, full-micromagnetic frameworks have been able to mimic the experimental behavior of most spintronic devices (pillar, nano-contact, MTJ, exchange-bias systems, phase-locked nano-contacts) as well as to perform predictions on new high-performance setups (Finocchio et al. 2006a,b, 2007, 2008, Choi et al. 2007, Consolo et al. 2007d, 2008, Hrkac 2008). At the same time, micromagnetic tools are successfully used to validate analytical theories as well. For example, the analysis of the disagreement reported between an analytical theory about the excitation of the nonlinear evanescent spin-wave "bullet" mode in in-plane magnetized nanocontact devices (Slavin and Tiberkevich 2005) and earlier results of micromagnetic simulations for the same geometry was intriguing and stimulating (Berkov and Gorn 2006). In fact, while the approximated theory was able to capture the underlying physics and consequently reproduce most of the experimental observations, micromagnetic simulations failed in that attempt. The problem was solved by using a new numerical strategy based on the application of decreasing currents starting from a large supercritical regime (Consolo et al. 2007b), which contains a lot of nonlinear "seeds." Apart from validating the theory, the micromagnetic approach has also been able to attribute the additional "subcritically-unstable" nature of these modes, enlarging the knowledge on the spin-wave modes supported by nano-contact devices.

From the experimental point of view, there is also an increasing interest in the dynamics (both switching and precession) involving magnetic tunnel junctions because of the discovery of very large TMR values (TMR is the difference in resistance between parallel and antiparallel orientation for the electrode magnetizations of a magnetic tunnel junction) at room temperature.

One reason for the interest in spin-torque effects in tunnel junctions is that these devices are better-suited than metallic magnetic multilayers for many types of applications. Tunnel junctions have higher resistances that can often be better impedance-matched to silicon-based electronics, and TMR values can now be made larger than the GMR values in metallic devices.

Devices based on those effects have already found very widespread applications as magnetic-field sensors in the read heads of magnetic hard disk drives as well as nonvolatile random access memory based on magnetic tunnel junctions.

Applications of spin transfer torques are so fascinating as well. Magnetic switching driven by the spin transfer effect can be much more efficient and more industrially intriguing than the usage of static magnetic fields or current-induced magnetic fields. This may enable the production of magnetic memory devices with much lower switching currents and hence greater energy efficiency as well as a larger integration density. The steady-state magnetic precession mode that can be excited by spin transfer is under investigation for a number of high-frequency applications, for example, nanometer-scale microwave sources (tunable by both magnetic field and current), detectors, mixers, modulators, phase shifters, and arrays (or matrixes) of phase-locked devices (whose coupling is used to increase the output power). One potential area of use is short-range chip-to-chip or even within-chip communications.

References

Alpert, B., Greengard, L., and Hagstrom T. 2002. Nonreflecting boundary conditions for the time-dependent wave equation. *J. Comput. Phys*. 180: 270–296.

Baibich, M.N. et al. 1988. Giant magnetoresistance of (001)Fe/(001) Cr magnetic superlattices. *Phys. Rev. Lett*. 61: 2472–2475.

Berger, L. 1996. Emission of spin waves by a magnetic multilayer traversed by a current. *Phys. Rev. B* 54: 9353–9358.

Berkov, D.V. and Gorn, N. 2006. Micromagnetic simulations of the magnetization precession induced by a spin-polarized current in a point-contact geometry. *J. Appl. Phys*. 99: 08Q701.

Berkov, D.V. and Miltat, J. 2008. Spin-torque driven magnetization dynamics: Micromagnetic modelling, *J. Magn. Magn. Mater*. 320: 1238–1259.

Bertotti, G. 1998. *Hysteresis in Magnetism*. Academic Press, Boston, MA.

Brown, W.F. 1940. Theory of the approach to magnetic saturation. *Phys. Rev*. 58: 736–743.

Brown, W.F. Jr. 1962. *Magnetostatic Principles in Ferromagnetism*, North-Holland Publishing Company, Amsterdam, the Netherlands.

Brown, W.F. 1963. *Micromagnetics*. Wiley, New York.

Brown, W.F. 1979. Thermal fluctuations in fine magnetic particles. *IEEE Trans. Magn*. MAG-15(5): 1196–1208.

Choi, S. et al. 2007. Double-contact spin-torque nano-oscillator with optimized spin-wave coupling: Micromagnetic modelling. *Appl. Phys. Lett*. 90: 083114.

Consolo, G. et al. 2007a. Boundary conditions for spin-wave absorption based on different site-dependent damping functions. *IEEE Trans. Magn*. 43: 2974–2976.

Consolo, G. et al. 2007b. Excitation of self-localized spin-wave bullets by spin-polarized current in in-plane magnetized magnetic nanocontacts: A micromagnetic study. *Phys. Rev. B* 76: 144410.

Consolo, G. et al. 2007c. Magnetization dynamics in nanocontact current controlled oscillators. *Phys. Rev. B* 75: 214428.

Consolo, G. et al. 2007d. Nanocontact spin-transfer oscillators based on perpendicular anisotropy in the free layer. *Appl. Phys. Lett*. 91: 162506.

Consolo, G. et al. 2008. Micromagnetic study of the above-threshold generation regime in a spin-torque oscillator based on a magnetic nano-contact magnetized at an arbitrary angle. *Phys. Rev. B* 78: 014420.

Enquist, B. and Majda, A. 1977. Absorbing boundary conditions for the numerical simulation of waves. *Math. Comput*. 31: 629–651.

Finocchio, G. et al. 2006a. Magnetization dynamics driven by the combined action of AC magnetic field and DC spin-polarized current. *J. Appl. Phys*. 99: 08G507.

Finocchio, G. et al. 2006b. Trends in spin-transfer driven magnetization dynamics of CoFe/AlO/Py and CoFe/MgO/Py magnetic tunnel junctions. *Appl. Phys. Lett*. 89: 262509.

Finocchio, G. et al. 2007. Magnetization reversal driven by spin-polarized current in exchange-biased nanoscale spin valves. *Phys. Rev. B* 76: 174408.

Finocchio, G. et al. 2008. Numerical study of the magnetization reversal driven by spin-polarized current in MgO based magnetic tunnel junctions. *Physica B* 403: 364–367.

Garcia-Palacios, J.L. and Lazaro, F.J. 1998. Langevin-dynamics study of the dynamical properties of small magnetic particles. *Phys. Rev. B* 58: 14937–14958.

Gardiner, C.W. 1985. *Handbook of Stochastic Methods*. Springer, Berlin, Germany.

Gilbert, T.L. 2004. A phenomenological theory of damping in ferromagnetic materials. *IEEE Trans. Magn*. 40: 3443–3449.

Higdon, R.L. 1987. Numerical absorbing boundary conditions for the wave equation. *Math. Comput*. 49: 65–90.

Hrkac, G. 2008. Mutual phase locking in high-frequency microwave nano-oscillators as a function of field angle. *J. Magn. Magn. Mater*. 320: L111–L115.

Kim, J.V., Tiberkevich, V., and Slavin, A. 2008. Generation linewidth of an auto-oscillator with a nonlinear frequency shift: Spin-torque nano-oscillator. *Phys. Rev. Lett*. 100: 017207.

Kloeden, P.E. and Platen E. 1999. *Numerical Solution of Stochastic Differential Equations*. Springer, Berlin, Germany.

Krivorotov, I.N. et al. 2004. Temperature dependence of spin-transfer-induced switching of nanomagnets. *Phys. Rev. Lett*. 93: 166603.

Landau, L.D. and Lifshitz, E.M. 1935. On the theory of the dispersion of magnetic permeability in ferromagnetic bodies. *Phys. Z. Sowjetunion* 8: 153–169.

Li, Z. and Zhang, S. 2004. Thermally assisted magnetization reversal in the presence of a spin-transfer torque. *Phys. Rev. B* 69: 134416.

Martinez, E., Torres, L., and Lopez-Diaz, L. 2004. Computing solenoidal fields in micromagnetic simulations. *IEEE Trans. Magn*. 40: 3240–3243.

Newell, A.J., Williams, W., and Dunlop, D.J. 1993. A generalization of the demagnetizing tensor for nonuniform magnetization. *J. Geophys. Res*. 98: 9551–9555.

Parkin, S.S., More, N., and Roche, K.P. 1990. Oscillations in exchange coupling and magnetoresistance in metallic superlattice structures: Co/Ru, Co/Cr, and Fe/Cr. *Phys. Rev. Lett*. 64: 2304–2307.

Parkin, S.S., Bhadra, R., and Roche, K.P. 1991. Oscillatory magnetic exchange coupling through thin copper layers. *Phys. Rev. Lett*. 66: 2152–2155.

Preisach, F. 1929. Investigations on the Barkhausen effect. *Ann. Physik* 3: 737–799.

Ralph, D.C. and Stiles, M.D. 2008. Spin-transfer torques. *J. Magn. Magn. Mater*. 320: 1190–1216.

Renaut, R.A. 1992. Absorbing boundary conditions, difference operators and stability. *J. Comput. Phys*. 102: 236–251.

Rippard, W.H. et al. 2004. Direct-current induced dynamics in $Co_{90}Fe_{10}/Ni_{80}Fe_{20}$ point contacts. *Phys. Rev. Lett*. 92: 027201.

Schad, R. et al. 1994. Giant magnetoresistance in Fe/Cr superlattices with very thin Fe layers. *Appl. Phys. Lett*. 64: 3500–3502.

Slavin, A.N. and Kabos, P. 2005. Approximate theory of microwave generation in a current-driven magnetic nanocontact magnetized in an arbitrary direction. *IEEE Trans. Magn*. 41: 1264–1273.

Slavin, A. and Tiberkevich, V. 2005. Spin-wave mode excited by spin-polarized current in a magnetic nanocontact is a standing self-localized wave bullet. *Phys. Rev. Lett*. 95: 237201.

Slavin, A. and Tiberkevich, V. 2008. Excitation of spin waves by spin-polarized current in magnetic nano-structures. *IEEE Trans. Magn*. 44: 1916–1927.

Slonczewski, J.C. 1996. Current-driven excitation of magnetic multilayers. *J. Magn. Magn. Mater*. 159: L1–L7.

Slonczewski, J.C. 1999. Excitation of spin waves by an electric current. *J. Magn. Magn. Mater*. 195: L261–L268.

Stiles, M.D. and Miltat J. 2006. Spin-transfer torque and dynamics. In *Spin Dynamics in Confined Magnetic Structures III*. Eds. B. Hillebrands and A. Thiaville, pp. 225–308. Springer, Berlin/Heidelberg, Germany.

Van Kampen, N.G. 1987. *Stochastic Processes in Physics and Chemistry*. North-Holland, Amsterdam, the Netherlands.

9

Quantum Spin Tunneling in Molecular Nanomagnets

9.1 Introduction 9-1
9.2 Spin Tunneling in Molecular Nanomagnets 9-2
9.3 Phonon-Assisted Spin Tunneling in Mn_{12} Acetate 9-5
9.4 Interference between Spin Tunneling Paths in Molecular Nanomagnets 9-5
Berry's Phase and Path Integrals
9.5 Incoherent Zener Tunneling in Fe_8 9-7
9.6 Coherent Néel Vector Tunneling in Antiferromagnetic Molecular Wheels 9-8
9.7 Berry-Phase Blockade in Single-Molecule Magnet Transistors 9-11
9.8 Concluding Remarks 9-12
Acknowledgment 9-13
References 9-13

Gabriel González
University of Central Florida

Michael N. Leuenberger
University of Central Florida

9.1 Introduction

Molecular magnets have attracted considerable interest recently among researchers because they are considered to be ideal systems to probe the interface between classical and quantum physics as well as to study decoherence in nanoscale systems. The advances in nanoscience during the last decade have made it possible to design and fabricate a wide variety of nanosize objects, ranging from a couple of micrometers all the way down to a few tens of nanometers, where quantum effects become important and give rise to new properties. One of the goals of miniaturization was the possibility of observing quantum tunneling effects in mesoscopic systems. One source for such a task is the so-called single-molecule magnets (SMM) and antiferromagnetic molecular wheels, in which the spin state of the molecule is known to behave quantum mechanically at low temperatures.

During the last decade, a tremendous progress in the experimental methods for contacting single molecules and measuring the electrical current through them has been achieved. The current through single magnetic molecules like Mn_{12} and Fe_8 has been measured and magnetic excited states have been identified (Jo et al., 2006; Henderson et al., 2007). In a three-terminal molecular single electron transistor, the current can flow between the source and drain leads via a sequential tunneling process through the molecular charge levels, thereby bringing the whole field of Coulomb-blockade physics to molecular systems.

Single-molecule magnets are mainly organic molecules containing multiple transition-metal ions bridged by organic ligands. These ions are strongly coupled by exchange interaction, yielding a large magnetic moment per molecule. The large spin combined with the large magnetic anisotropy provides an energy barrier for magnetization reversal. These systems provided for the first time evidence of quantum tunneling of the magnetization and interference effects as well as oscillations of the tunnel splitting.

Ferromagnetic molecular magnets such as Mn_{12} and Fe_8 show incoherent tunneling of the magnetization (Korenblit and Shender, 1978; Enz and Schilling, 1986; van Hemmen and Süto, 1986; Chudnovsky and Gunther, 1988) and allow one to study the interplay of thermally activated processes and quantum tunneling. The spin tunneling leads to two effects. First, the magnetization relaxation is accelerated whenever spin states of opposite direction become degenerate due to the variation of the external longitudinal magnetic field (Friedman et al., 1996; Thomas et al., 1996; Leuenberger and Loss, 1999, 2000a; Leuenberger and Loss). Second, the spin acquires a Berry phase during the tunneling process, which leads to oscillations of the tunnel splitting as a function of the external transverse magnetic field (Wernsdorfer and Sessoli, 1996; Wernsdorfer et al., 2000; Leuenberger and Loss, 2000b, 2001a).

Antiferromagnetic molecular wheels are another type of molecular magnets where an even number of transition metal ions with spin form a closed ring in which the exchange interaction between neighbors gives rise to a strong spin quantum dynamics. Antiferromagnetic molecular magnets such as ferric wheels belong to the most promising candidates for the observation of coherent quantum tunneling on the mesoscopic scale (Chiolero and Loss, 1998; Meier and Loss, 2000, 2001). In contrast to incoherent tunneling, in quantum coherent tunneling spins tunnel back and forth between energetically degenerate configurations at a tunneling rate which is *large* compared to the decoherence rate. The detection of quantum behavior is more challenging in antiferromagnetic molecular magnets than in ferromagnetic systems, but is feasible with present day experimental techniques.

Understanding the properties of molecular magnets is only a first step toward achieving technological applications in data storage, data processing, and quantum technologies. A possible next step will be the preparation and control of a well-defined single-spin quantum state of a molecular cluster. Although challenging, this task appears feasible with present-day experiments and would allow one to carry out quantum computing with molecular magnets (Leuenberger and Loss, 2001b).

9.2 Spin Tunneling in Molecular Nanomagnets

An effective spin Hamiltonian that captures the basic physics of a molecular nanomagnet is given by the following form:

$$\mathcal{H} = \mathcal{H}_0(\vec{S}) + \mathcal{H}_Z + \mathcal{H}_T + \mathcal{H}_{sb}. \tag{9.1}$$

We will now analyze each term in the Hamiltonian given in Equation 9.1 separately. The first term in Equation 9.1 is the dominant term of the Hamiltonian with spin quantum number $S = |\vec{S}| \gg 1$ and is called the uniaxial anisotropy, which results from the spin–orbit interactions and generates and easy magnetic axis for the magnetic moment of the nanomagnet. The assumption is that we have a single domain magnetic molecule in which the very strong exchange interactions align the microscopic electronic spins into a parallel or antiparallel configuration, resulting in a total spin $\vec{S} = \sum_j \vec{s}_j$ for the ferromagnetic moment or the Neél vector with $\vec{S} = \sum_j (-1)^j \vec{s}_j$, respectively.

For a nanomagnet like Fe$_8$, $\mathcal{H}_0(\vec{S}) = -AS_z^2$ where $A/k_B \approx 0.275\,\text{K}$ and generates an energy barrier that separates opposite spin projections (see Figure 9.1).

Quantum mechanics specifies that a particle in a symmetric double well potential undergoes a tunnel effect that makes the particle go back and forth from one well to the other with a frequency ω_T. This implies that the eigenfunctions of the Hamiltonian are delocalized, which means that there is a probability to find the particle either in one well or the other. In a similar fashion, there is a probability for the spin of the nanomagnet to change direction, i.e., if the spin of the nanomagnet points up there is a probability that at a later time the spin will be pointing down. At equilibrium and finite temperature, the probability that the spin is in state $|m\rangle$, where $S_z|m\rangle = m|m\rangle$ for $m = -s, -s+1, \ldots, s-1, s$, is given by

$$P_m = \frac{e^{-E_m/k_BT}}{Z} \tag{9.2}$$



FIGURE 9.1 The graph shows $\mathcal{H}_0$ vs. S_z where the horizontal lines indicate the energies of the quantum states.

where

Z is the partition function

$E_m = -Dm^2$

For the case when $T \to 0$ the probability for the spin to go from one well to the other satisfies the following equation:

$$\frac{dP(t)}{dt} \approx -\Gamma P(t) < 0. \tag{9.3}$$

Therefore $P(t) \propto e^{-\Gamma t}$, where Γ is the rate of decay and Γ^{-1} is known as the lifetime or characteristic time of the particle.

The second term in Equation 9.1 is the Zeeman energy resulting from the interaction of the spin with an external magnetic field, i.e., $\mathcal{H}_Z = \mu_B g \vec{S} \cdot \vec{H}$. A magnetic field applied along the easy axis of the molecule will tilt the potential well and for certain values of the magnetic field ($\delta H_z = (m + m')|A|/g\mu_B$), the energy levels on both sides of the anisotropy barrier coincide. Therefore the Hamiltonian given by $\mathcal{H} = -AS_z^2 + g\mu_B \delta H_z S_z$ is still doubly degenerate (see Figure 9.2).


Energy
Δ
$|m\rangle$
$|m'\rangle$
$W_{m,m+1}$
$\propto \delta H_z$
$|A\rangle = \frac{1}{\sqrt{2}}(|m\rangle - |m'\rangle)$
$|S\rangle = \frac{1}{\sqrt{2}}(|m\rangle + |m'\rangle)$

FIGURE 9.2 The graph shows $(\mathcal{H}_0 + \mathcal{H}_Z)$ vs. S_z in a constant magnetic field parallel to the easy axis. Δ denotes the tunnel splitting between states $|m\rangle$ and $|m'\rangle$.

These degeneracies can be removed by the term $\mathcal{H}_T$, which corresponds to the transverse anisotropies. For the nanomagnet Fe_8, the transverse anisotropy term is given by $\mathcal{H}_T = E(S_x^2 - S_y^2)$, where ($E/k_B \approx 0.046\,\text{K}$). The anisotropy term lifts the degeneracy, thereby creating an energy gap between the spin states $|m\rangle$ and $|m'\rangle$, denoted by $\Delta_{mm'}$. If the Hamiltonian possesses transverse terms, the pairwise degenerate states get split by $\Delta_{mm'}$ amount of energy. If the coupling of our system to an external bath is assumed to be zero, each pair of the degenerate states can be described by means of a two-state Hamiltonian:

$$\mathcal{H} = \begin{bmatrix} hm & \dfrac{\Delta_{mm'}}{2} \\ \dfrac{\Delta_{mm'}}{2} & hm' \end{bmatrix} = \frac{h}{2}(m+m')\begin{bmatrix} 1 & 0 \\ 0 & 1 \end{bmatrix} + \frac{h}{2}(m-m')\begin{bmatrix} 1 & \tan\theta \\ \tan\theta & -1 \end{bmatrix}, \tag{9.4}$$

where $\tan\theta = \Delta_{mm'}/h(m-m')$, $0 \le \theta < \pi$ and h is the longitudinal magnetic field with the coupling constant g and Bohr magneton μ_B absorbed, which makes the double well asymmetric, and $\Delta_{mm'}$ is the tunnel splitting between the states $|m\rangle$ and $|m'\rangle$. The eigenstates of Equation 9.4 read

$$|\psi_+\rangle = \cos\frac{\theta}{2}|m\rangle + \sin\frac{\theta}{2}|m'\rangle, \tag{9.5}$$

$$|\psi_-\rangle = -\sin\frac{\theta}{2}|m\rangle + \cos\frac{\theta}{2}|m'\rangle, \tag{9.6}$$

with eigenvalues

$$E_\pm = \frac{h}{2}\left[(m+m') \pm \frac{(m-m')}{\cos\theta}\right] = \frac{1}{2}\left[h(m+m') \pm \sqrt{h^2(m-m')^2 + \Delta_{mm'}^2}\right]. \tag{9.7}$$

$|\psi_+\rangle$ and $|\psi_-\rangle$ are delocalized as long as $h(m-m') \le \Delta_{mm'}$. It is only in this regime that a spin state can tunnel from one side of the barrier to the other, which is also relevant for the Zener tunneling (see Section 9.5). In the limit $h \to 0$, the eigenstates $|\psi_+\rangle$ and $|\psi_-\rangle$ are the symmetrical and antisymmetrical combinations of $|m\rangle$ and $|m'\rangle$, i.e., $|\psi_+\rangle = |S\rangle = \frac{1}{\sqrt{2}}(|m\rangle + |m'\rangle)$ and $|\psi_-\rangle = |A\rangle = \frac{1}{\sqrt{2}}(|m\rangle - |m'\rangle)$. For $\Delta_{mm'} \to 0$ we are left with $|\psi_+\rangle = |m\rangle$ and $|\psi_-\rangle = |m'\rangle$ for $h > 0$ and $|\psi_-\rangle = |m\rangle$ and $|\psi_+\rangle = |m'\rangle$ for $h < 0$ (Figure 9.3).

Let us now assume that the system starts in the state

$$|\psi(t=0)\rangle = |m\rangle = \cos\frac{\theta}{2}|\psi_+\rangle - \sin\frac{\theta}{2}|\psi_-\rangle, \tag{9.8}$$

from which one obtains immediately the time evolution

$$|\psi(t)\rangle = \cos\frac{\theta}{2}e^{-iE_+t/\hbar}|\psi_+\rangle - \sin\frac{\theta}{2}e^{-iE_-t/\hbar}|\psi_-\rangle. \tag{9.9}$$


$|\psi_+\rangle = |m'\rangle$
$|\psi_+\rangle = |A\rangle = \frac{1}{\sqrt{2}}(|m\rangle - |m'\rangle)$
$|\psi_+\rangle = |m\rangle$
Energy
$\Delta_{mm'}$
$|\psi_-\rangle = |m\rangle$
$|\psi_-\rangle = |S\rangle = \frac{1}{\sqrt{2}}(|m\rangle + |m'\rangle)$
$|\psi_-\rangle = |m'\rangle$
h

FIGURE 9.3 Anticrossing of the adiabatic eigenvalues $E_\pm = \frac{1}{2}\left[h(m+m') \pm \sqrt{h^2(m-m') + \Delta_{mm'}^2}\right]$. The Zener tunneling transition of the state $|\psi_+\rangle$ is adiabatic (see Section 9.5).

Then one can calculate the probability that the state $|m\rangle$ has tunneled to the state $|m'\rangle$ after time t:

$$\begin{aligned} |\langle m' \mid \psi(t)\rangle|^2 &= \left|\sin\frac{\theta}{2}\langle\psi_+ \mid \psi(t)\rangle + \cos\frac{\theta}{2}\langle\psi_- \mid \psi(t)\rangle\right|^2 \\ &= \left|\sin\frac{\theta}{2}\cos\frac{\theta}{2}(e^{-iE_+t/\hbar} - e^{-iE_-t/\hbar})\right|^2 \\ &= \sin^2\theta\sin^2\left(\frac{\sqrt{h^2(m-m')^2 + \Delta_{mm'}^2}}{2\hbar}t\right) \\ &= \frac{\Delta_{mm'}^2}{h^2(m-m')^2 + \Delta_{mm'}^2}\sin^2\left(\frac{\sqrt{h^2(m-m')^2 + \Delta_{mm'}^2}}{2\hbar}t\right) \end{aligned} \tag{9.10}$$

This means that both the tunneling behavior and also the two-level spin resonance behavior are described by a Rabi oscillation.

In reality, the spin of the SMM is interacting with the environment and this interaction is described by the last term in Equation 9.1. The interaction of the molecular magnet with the environment is due to the hyperfine interaction, dipole interaction, spin–phonon interaction, the interaction between the molecule and two contact leads, etc. When the spin interacts with its environment, the wavefunction loses the memory of its phase. This phenomenon is known as decoherence. In this case, the wavefunction is not longer appropriate to describe the system. The problem of a system that interacts with the environment is formulated by means of the density matrix formalism. The spin has a certain probability to be in state $|m\rangle$ at time t, which is described by the density matrix $\rho_m(t)$. Due to the interaction with the environment, the spin undergoes incoherent transitions from a state $|m\rangle$ to another state $|m'\rangle$ at a rate $W_{m'm}$ until $\rho_m(t)$, $-s \le m \le s$ reach their equilibrium value. This process is known as relaxation. If these transitions are independent of each other, the density matrix evolves according to the Pauli equation or master equation

$$\frac{d\rho_m(t)}{dt} = \sum_{m'}\left[W_{mm'}\rho_{m'}(t) - W_{m'm}\rho_m(t)\right] \tag{9.11}$$

where $W_{m'm}$ is the transition probability from state $|m\rangle$ to state $|m'\rangle$. The master equation (Equation 9.11) can also be written as

$$\frac{d\rho_m(t)}{dt} = \sum_{m'} A_{mm'}\rho_{m'}(t) \tag{9.12}$$

where

$$A_{mm'} = \begin{cases} W_{mm'} & \text{if } m \neq m' \\ -\sum_{m''}{}' W_{m''m'} & \text{if } m' = m, \end{cases} \tag{9.13}$$

the prime indicates that the term $m'' = m$ is to be omitted in the summation. A formal solution to Equation 9.11 can be obtained in the following manner, let

$$\rho_m(t) = p_m^{(n)} e^{-\Gamma_n t} \tag{9.14}$$

where Γ_n^{-1} is the characteristic time labeled by the index $n = 0, 1, \ldots, 2s$. Substituting Equation 9.14 into Equation 9.11, one obtains

$$-\Gamma_n p_m^{(n)} = \sum_{m'} \left[W_{mm'} - \delta_{mm'} \sum_{m''} W_{mm''} \right] p_{m'}^{(\mathrm{n})} = \sum_{m'} A_{mm'} p_{m'}^{(\mathrm{n})} \tag{9.15}$$

which implies that $-\Gamma_n$ is an eigenvalue of the master matrix defined in Equation 9.13. The master matrix is a square matrix $(2s + 1) \times (2s + 1)$, which is not Hermitian. However, the eigenvalue problem can be written in terms of the Hermitian real matrix by making the following transformation

$$B_{mm'} = A_{mm'} \exp\left[\frac{\beta(E_m - E_{m'})}{2} \right] = B_{m'm}. \tag{9.16}$$

It follows that the general solution of Equation 9.11 is then

$$\rho_m(t) = \exp\left[\frac{-\beta E_m}{2} \right] \sum_n c_n \mathcal{P}_m^{(n)} e^{-\Gamma_n t} \tag{9.17}$$

where $(\mathcal{P}_m^{(n)}, -\Gamma_n)$ are the $(2s + 1)$ orthonormal set of eigenvectors with the corresponding eigenvalues of the matrix (9.16) and $\mathcal{P}_m^{(n)} = p_m^{(n)} \exp(\beta E_m/2)$. The c_n are the constants related to the initial distribution of ρ_m by

$$c_n = \sum_k \rho_k(0) \mathcal{P}_k^{(n)} \exp\left[\frac{\beta E_k}{2} \right]. \tag{9.18}$$

Equation 9.11 is only valid for times where the correlation time τ_c in the heat bath is much smaller than the relaxation time of the spin system, necessary for the establishment of irreversibility in a macroscopic system. In fact, in order to describe quantum tunneling, it is necessary to use the *generalized master equation*. The generalized master equation that describes the relaxation of the spin due to phonon-assisted transitions including resonances due to tunneling is given by

$$\dot{\rho}_{mm'} = \frac{i}{\hbar}[\rho, \mathcal{H}_0]_{mm'} + \delta_{mm'} \sum_{n \neq m} \rho_n W_{mn} - \gamma_{mm'}\rho_{mm'}. \tag{9.19}$$

The difference to the usual master equation is that Equation 9.19 takes also off-diagonal elements of the density matrix $\rho(t)$ into account. This is essential to describe tunneling of the magnetization, which is caused by the overlap of the S_z states.

Let us consider the two-state system $\{|m\rangle, |m'\rangle\}$, which yields the two-state Hamiltonian in the presence of a bias field given in Equation 9.4. Next we insert the two-state Hamiltonian into the generalized master equation (Equation 9.19), which yields for the diagonal elements of the density matrix

$$\dot{\rho}_m = \frac{i\Delta_{mm'}}{2\hbar}(\rho_{mm'} - \rho_{m'm}) - W_m\rho_m + \sum_{n \neq m,m'} W_{mn}\rho_n \tag{9.20}$$

and for the off-diagonal elements

$$\dot{\rho}_{mm'} = -\left(\frac{i}{\hbar}\xi_{mm'} + \gamma_{mm'} \right)\rho_{mm'} + \frac{i\Delta_{mm'}}{2\hbar}(\rho_m - \rho_{m'}), \tag{9.21}$$

with $\xi_m = -Am^2 + g\mu_B \delta H_z m$ and $\xi_{mm'} = \xi_m - \xi_{m'}$, similarly for $m \leftrightarrow m'$. Ultimately, we are interested in the overall relaxation time τ of the quantity $\rho_s - \rho_{-s}$ (see Section 9.7) due to phonon-induced transitions. This τ turns out to be much longer than $\tau_\mathrm{d} = 1/\gamma_{mm'}$, which is the decoherence time of the decay of the off-diagonal elements $\rho_{mm'} \propto e^{-t/\tau_\mathrm{d}}$ of the density matrix ρ. Thus, we can neglect the time dependence of the off-diagonal elements, i.e., $\dot{\rho}_{mm'} \approx 0$. Physically this means that we deal with incoherent tunneling for times $t > \tau_\mathrm{d}$. Inserting then the stationary solution of Equation 9.21 into Equation 9.20, which leads to the complete master equation including resonant as well as nonresonant levels, we get

$$\dot{\rho}_m = -W_m\rho_m + \sum_{n \neq m,m'} W_{mn}\rho_n + \Gamma_{mm'}(\rho_{m'} - \rho_m), \tag{9.22}$$

where

$$\Gamma_{mm'} = \Delta_{mm'}^2 \frac{W_m + W_{m'}}{4\xi_{mm'}^2 + \hbar^2(W_m + W_{m'})^2} \tag{9.23}$$

is the transition rate from m to m' (induced by tunneling) in the presence of phonon damping. Note that Equation 9.22 is now of the usual form of a master equation, i.e., only diagonal elements of the density matrix $\rho(t)$ occur. For levels $k \neq m, m'$, Equation 9.22 reduces to

$$\dot{\rho}_k = -W_k\rho_k + \sum_n W_{kn}\rho_n. \tag{9.24}$$

We note that $\Gamma_{mm'}$ has a Lorentzian shape with respect to the external magnetic field δH_z occurring in $\xi_{mm'}$. It is thus this $\Gamma_{mm'}$ that will determine the peak shape of the magnetization resonances.

9.3 Phonon-Assisted Spin Tunneling in Mn_{12} Acetate

The magnetization relaxation of crystals and powders made of molecular magnets Mn_{12} has attracted much recent interest since several experiments (Sessoli et al., 1993; Novak and Sessoli, 1995; Novak et al., 1995; Paulsen and Park, 1995; Paulsen et al., 1995) have indicated unusually long relaxation times as well as increased relaxation rates (Friedman et al., 1996; Hernández et al., 1996; Thomas et al., 1996) whenever two spin states become degenerate in response to a varying longitudinal magnetic field H_z. According to earlier suggestions (Barbara et al., 1995), this phenomenon has been interpreted as a manifestation of incoherent macroscopic quantum tunneling (MQT) of the spin.

As long as the external magnetic field H_z is much smaller than the internal exchange interactions between the Mn ions of the Mn_{12} cluster, the Mn_{12} cluster behaves like a large single spin $\vec{S}$ of length $|\vec{S}| = 10$. For temperatures $1 \leq T \leq 10\,\text{K}$, its spin dynamics can be described by the spin Hamiltonian given in Equation 9.1, including the coupling between this large spin and the phonons in the crystal (Villain et al., 1994; Garanin and Chudnovsky, 1997; Hernández et al., 1997; Fort et al., 1998; Luis et al., 1998; Leuenberger and Loss, 1999, 2000a; Leuenberger and Loss).

The most general spin–phonon coupling reads

$$\begin{aligned}\mathcal{H}_{\text{sp}} &= g_1(\epsilon_{xx} - \epsilon_{yy}) \otimes (S_x^2 - S_y^2) + \frac{1}{2} g_2 \epsilon_{xy} \otimes \{S_x, S_y\} \\ &\quad + \frac{1}{2} g_3 (\epsilon_{xz} \otimes \{S_x, S_z\} + \epsilon_{yz} \otimes \{S_y, S_z\}) \\ &\quad + \frac{1}{2} g_4 (\omega_{xz} \otimes \{S_x, S_z\} + \omega_{yz} \otimes \{S_y, S_z\}), \end{aligned} \tag{9.25}$$

where

g_i are the spin–phonon coupling constants

$\epsilon_{\alpha\beta}(\omega_{\alpha\beta})$ is the (anti-)symmetric part of the strain tensor

From the comparison between experimental data (Friedman et al., 1996; Thomas et al., 1996) and calculation, it turns out that the constants $g_i \approx A\ \forall i$ (Leuenberger and Loss, 1999, 2000a; Leuenberger and Loss).

9.4 Interference between Spin Tunneling Paths in Molecular Nanomagnets

Recent experiments have pointed out the importance of the interference between spin tunneling paths in molecules. For instance, measurements of the magnetization in bulk Fe_8 have observed oscillations in the tunnel splitting $\Delta_{m,-m}$ between states $S_z = m$ and $-m$ as a function of a transverse magnetic field at temperatures between 0.05 and 0.7 K (see Landau, 1932). This effect can be explained by the interference between Berry phases associated to spin tunneling paths of opposite windings (DiVincenzo et al., 1992; van Delft and Henley, 1992).

Usually the Berry phase effect arises in systems that undergo an adiabatic cyclic evolution, and which occurs in such diverse fields as atomic, condensed matter, nuclear and elementary particle physics, and optics. The basic assumption for the derivation of the Berry phase is that, for a slowly varying time-dependent Hamiltonian $H(\vec{R}(t))$ that depends on parameters $R_1(t), R_2(t), \ldots, R_N(t)$ components of a vector $\vec{R}$, the eigenstate evolves in time according to

$$\left|\psi_i(\vec{R}(0))\right\rangle \to e^{i\varphi_i(t)} \left|\psi_i(\vec{R}(t))\right\rangle \exp\left[-\frac{i}{\hbar}\int_0^t E_i(\vec{R})dt\right]. \tag{9.26}$$

Plugging Equation 9.26 into Schrödinger's equation we have

$$\frac{d\varphi}{dt} = i\left\langle \psi_i \,|\, \nabla_{\vec{R}} \,|\, \psi_i \right\rangle \cdot \frac{d\vec{R}}{dt}, \tag{9.27}$$

thus, for $t = 0$ to $t = \tau$ we end up with

$$\varphi(\tau) - \varphi(0) = \int_{\vec{R}(0)}^{\vec{R}(\tau)} \left\langle \psi_i \,|\, i\nabla_{\vec{R}} \,|\, \psi_i \right\rangle d\vec{R}. \tag{9.28}$$

The term of Equation 9.28 is known as Berry's phase. The overall phase of a quantum state is not observable but the relative phases for a quantum system, which undergoes a coherent evolution, can be detected experimentally. Consider for example two paths $\vec{R}$ and $\vec{R}'$ with the same end points $\vec{R}(0) = \vec{R}'(0)$ and $\vec{R}(\tau) = \vec{R}'(\tau)$, the net Berry phase change is given by

$$\Delta\varphi = \oint \left\langle \psi_i \,|\, i\nabla_{\vec{R}} \,|\, \psi_i \right\rangle \cdot d\vec{R}. \tag{9.29}$$

This is a line integral around a closed loop in parameter space, which is nonzero in general. The classic example of Berry's phase is an electron at rest subjected to a time-dependent magnetic field of constant magnitude but changing direction. The Hamiltonian for this system is given by

$$\mathcal{H} = -\mu_B \vec{\sigma} \cdot \vec{H} = -\mu_B \begin{bmatrix} H_z & H_x - iH_y \\ H_x + iH_y & -H_z \end{bmatrix}, \tag{9.30}$$

where $\vec{H}(t) = H(\sin\theta(t)\cos(\phi(t)), \sin(\theta(t))\sin(\phi(t)), \cos(\theta(t)))$ and μ_B is Bohr magneton. It is easy to show that the eigenstate representing spin up along $\vec{H}(t)$ for Equation 9.30 has the form

$$\left|\uparrow\right\rangle = \begin{pmatrix} e^{-i\phi/2}\cos(\theta/2) \\ e^{i\phi/2}\sin(\theta/2) \end{pmatrix}. \tag{9.31}$$



FIGURE 9.4 The figure shows an electron in a constant magnetic field which sweeps around a closed curve $\mathcal{C}$ and subtends a solid angle Ω.

For the case when the magnetic field sweeps out an arbitrary closed circuit $\mathcal{C}$ (see Figure 9.4) we can apply Equation 9.29 to get the Berry phase

$$\Delta\varphi = -\frac{1}{2}\Omega(\mathcal{C}), \tag{9.32}$$

where $\Omega(\mathcal{C})$ is the solid angle described by the field $\vec{H}$ along the circuit $\mathcal{C}$.

9.4.1 Berry's Phase and Path Integrals

An alternative approach for quantum mechanics and hence for the calculation of the tunneling frequency is by means of path integrals which were introduced by Richard Feynman (Feynman, 1948). In this section, we will briefly explain the path integral approach to calculate the Berry phase in single molecular magnets.

Feynman showed that the probability amplitude $\langle x'|\exp[i(t'-t)\mathcal{H}/\hbar]|x\rangle$ for a particle that is at point x' at time t' if it was at point x at a time t can be expressed as the path integral

$$U(x',t'\,|\,x,t) = \int_x^{x'} \mathcal{D}[x'']\exp\left[\frac{iS_E}{\hbar}\right], \tag{9.33}$$

where

$$S_E = \int_t^{t'} dt\, L[x(t),\dot{x}(t)], \tag{9.34}$$

is the *Euclidean action*, which involves the classical Lagrangian $L[x(t), \dot{x}(t)]$ and $\int\mathcal{D}[x'']$ is an integral over all paths from x to x' defined as

$$\int_x^{x'} \mathcal{D}[x''] \equiv \lim_{N\to\infty}\left(\frac{m}{2\pi i\hbar\Delta t}\right)^{N/2}\prod_{n=1}^{N-1}\int dx_n, \tag{9.35}$$

where $x_n = x(t_n)$ and $t_n \in [t, t_1, \ldots, t_{N-1}, t']$. For purposes of actual evaluation of quantities using path-integral methods, it is common to get rid of the factor i in the exponential of Equation 9.33 by analytic continuation to imaginary times, through $\beta = it/\hbar$. Then, the path integral becomes equivalent to the partition function Z by noting $\beta = 1/k_BT$.

Quantum tunneling of a spin is often described with the terminology of a path integral. Consider a general single-spin Hamiltonian $\mathcal{H}_{z,n} = -AS_z^2 + B_n(S_+^n + S_-^n)$, with easy-axis ($A$) and transverse ($B_n$) anisotropy constants satisfying $A \gg B_n > 0$. Here, n is an even integer, i.e., $n = 2, 4, 6, \ldots$, so that $\mathcal{H}_z$ is invariant under time reversal. Such Hamiltonians are relevant for molecular magnets such as Mn_{12} (Fort et al., 1998; Leuenberger and Loss, 1999, 2000a) and Fe_8 (Leuenberger and Loss, 2000b). The corresponding classical anisotropy energy $E_{z,n}(\theta, \phi) = -As^2\cos^2\theta + B_ns^n\sin^n\theta\cos(n\phi)$ has the shape of a double-well potential, with the easy axis pointing along the z direction. It is obvious that the anisotropy energy remains invariant under rotations around the z-axis by multiples of the angle $\eta = 2\pi/n$. For the following calculation, it proves favorable to choose the easy axis along the y direction where the contour path does not include the south pole. Then the spin Hamiltonian and the anisotropy energy are changed into

$$\mathcal{H}_{y,n} = -AS_y^2 + B_n(S_+^n + S_-^n), \tag{9.36}$$

where now $S_\pm = S_z \pm iS_x$, and

$$E_{y,n}(\theta,\phi) = -As^2\sin^2\theta\sin^2\phi + B_ns^n \times\left[(\cos\theta + i\sin\theta\cos\phi)^n + (\cos\theta - i\sin\theta\cos\phi)^n\right]. \tag{9.37}$$

We are interested in the tunneling between the eigenstates $|m\rangle$ and $|-m\rangle$ of $-AS_y^2$, corresponding to the global minimum points ($\theta = \pi/2$, $\phi = -\pi/2$) and ($\theta = \pi/2$, $\phi = +\pi/2$) of $E_{y,n}$. For this, we evaluate the imaginary time transition amplitude between these points. For the ground-state tunneling ($m = s \gg 1$), this can be done by means of the coherent spin-state path integral (DiVincenzo et al., 1992)

$$\left\langle -\frac{\pi}{2}\middle|e^{-\beta\mathcal{H}}\middle|+\frac{\pi}{2}\right\rangle = \int_{\pi/2,-\pi/2}^{\pi/2,+\pi/2}\mathcal{D}\Omega\, e^{-S_E}, \tag{9.38}$$

where $\beta = 1/k_BT$ is the inverse temperature, $\mathcal{D}\Omega = \Pi_\tau d\Omega_\tau$, $d\Omega_\tau = [4\pi/(2s+1)]d(\cos\theta_\tau)d\phi_\tau$ the Haar measure of the S^2 sphere, and $S_E = \int_0^\beta d\tau[is\dot{\phi}(1-\cos\theta) + E_{y,n}]$ the Euclidean action, where the first term in S_E defines the Wess–Zumino (or Berry phase) term, which gives rise to topological interference effects for spin tunneling (DiVincenzo et al., 1992; von Delft and Henley, 1992). We can divide the S^2 surface area of integration in Equation 9.38 into n equally shaped subareas $\mathcal{A}_n$, so that we can factor out the following sum over Berry phase terms without the need of



FIGURE 9.5 Sum over Berry phase terms for $s = 10$ and $n = 4$.

evaluating the dynamical part of the path integral (i.e., the following result is valid for all m),

$$\left\langle -\frac{\pi}{2}\right| e^{-\beta\mathcal{H}_{y,n}} \left| +\frac{\pi}{2}\right\rangle \propto \sum_{k=1}^{n} e^{i(2\pi/n)(2k-1)m} = \frac{\sin(2\pi m)}{\sin(2\pi m/n)}, \qquad (9.39)$$

which vanishes whenever n is not a divisor of $2m$. Thus, the tunnel splitting energy $\Delta_{m,-m}$ between the states $|m\rangle$ and $|-m\rangle$ vanishes if $2m/n \notin Z$. However, if $2m/n \in Z$, the variable m must be extended to real numbers, i.e., $m \to \mu \in R$, in order to calculate the limit $\mu \to m$ of the ratio of the sine functions, which is plotted in Figure 9.5 for a special case. In order to visualize the interference between the Berry phases in Equation 9.39, we select one representative path of each subarea $\mathcal{A}_n$. Then the vanishing of the amplitude in Equation 9.39 for the case $n = 6$ (see Figure 9.6) can be thought of as a destructive interference between six different paths. Also, it is important to note that from the semiclassical point of view, the total classical energy of the spin system E must be conserved during the tunneling process. Therefore, the semiclassical paths do not follow the local minima of E with respect to θ alone, except for the case of purely quadratic (i.e., $n = 2$) anisotropies (DiVincenzo et al., 1992; Garg, 1993).



FIGURE 9.6 Berry phase interference between six different paths for $s = 10$ and $n = 6$.

From the above treatment, we conclude that tunneling between two degenerate spin states $|m\rangle$ and $|m'\rangle = |-m\rangle$ is topologically suppressed (i.e., the twofold degeneracy is not lifted) whenever n is *not* a divisor of $2m$. Since n is even this excludes immediately tunneling for all half-odd integer spins s (for all m and n), in accordance with Kramers degeneracy. For s integer, however, tunneling can be either allowed or suppressed, depending on the ratio $2m/n$. In the latter case, the twofold degeneracy of spin states is not lifted by the anisotropy, and we can view this result as a generalization of the Kramers theorem to integer spins.

9.5 Incoherent Zener Tunneling in Fe$_8$

Besides Mn$_{12}$, there have been several experiments on the molecular magnet Fe$_8$ that revealed macroscopic quantum tunneling of the spin (Barra et al., 1996; Wernsdorfer and Sessoli, 1996; Sangregorio et al., 1997; Ohm et al., 1998; Wernsdorfer et al., 2000). In particular, recent measurements on Fe$_8$ (Wernsdorfer and Sessoli, 1996; Wernsdorfer et al., 2000) lead to the development of the concept of the incoherent Zener tunneling (Leuenberger and Loss, 2000b; Leuenberger et al., 2003). The resulting Zener tunneling probability P_{inc} exhibits Berry phase oscillations as a function of the external transverse field H_x.

For many physical systems, the Landau–Zener model (Landau, 1932; Zener, 1932) has become an important tool for studying tunneling transitions (Crothers and Huges, 1977; Garga et al., 1985; Shimshoni and Gefen, 1991; Averin and Bardas, 1995). It must be noted that all quantum systems to which the Zener model (Landau, 1932) is applicable can be described by *pure* states and their *coherent* time evolution. In particular, the theory presented in Leuenberger and Loss (2000b) agrees well with recent measurements of $P_{\text{inc}}(H_x)$ for various temperatures in Fe$_8$ (Wernsdorfer and Sessoli, 1996; Wernsdorfer et al., 2000).

For the Zener transition, usually only the asymptotic limit is of interest. Therefore it is required that the range over which $\varepsilon_{mm'}(t) = \varepsilon_m - \varepsilon_{m'}$ is swept is much larger than the tunnel splitting $\Delta_{mm'}$ and the decoherence rate $\hbar\gamma_{mm'}$. In addition, the evolution of the spin system is restricted to times t that are much longer than the decoherence time $\tau_d = 1/\gamma_{mm'}$. In this case, tunneling transitions between pairs of degenerate excited states are incoherent. This tunneling is only observable if the temperature T is kept well below the activation energy of the potential barrier. Accordingly, one is interested only in times t that are larger than the relaxation times of the excited states. It was shown by Leuenberger and Loss (2000b) that the Zener tunneling can be described by Equation 9.22, where

$$\Gamma_{mm'}(t) = \frac{\Delta_{mm'}^2}{2} \frac{\gamma_{mm'}}{\varepsilon_{mm'}^2(t) + \hbar^2 \gamma_{mm'}^2} \tag{9.40}$$

is time dependent, in contrast to Equation 9.23. As usual, the abbreviations $\gamma_{mm'} = (W_m + W_{m'})/2$ and $W_m = \Sigma_n W_{nm}$ are used, where W_{nm} denotes the approximately time-independent transition rate from $|m\rangle$ to $|n\rangle$, which can be obtained via Fermi's golden rule (Leuenberger and Loss, 1999, 2000a). The tunnel splitting (Leuenberger and Loss, 1999, 2000a) is given by

$$\Delta_{mm'} = 2 \left| \sum_{\substack{m_1,\ldots,m_N \\ m_i \neq m,m'}} \frac{V_{m,m_1}}{\varepsilon_m - \varepsilon_{m_1}} \prod_{i=1}^{N-1} \frac{V_{m_i,m_{i+1}}}{\varepsilon_m - \varepsilon_{m_{i+1}}} V_{m_N,m'} \right|. \tag{9.41}$$

V_{m_i,m_j} denote off-diagonal matrix elements of the total Hamiltonian $\mathcal{H}_{\text{tot}}$.

Since all resonances n lead to similar results, Equation 9.22 is solved only in the unbiased case—corresponding to $n = 0$ (see below)—where the ground states $|s\rangle$, $|-s\rangle$ and the excited states $|m\rangle$, $|-m\rangle$, $m \in [-s+1, s-1]$ of the spin system with spin s are pairwise degenerate. In addition, it is assumed that the excited states are already in their stationary state, i.e., $\dot{\rho}_m = 0\ \forall m \neq s, -s$. Equation 9.22 leads then to

$$1 - P_{\text{inc}} \equiv \Delta\rho(t) = \exp\left\{ -\int_{t_0}^{t} dt' \,\Gamma_{\text{tot}}(t') \right\}, \tag{9.42}$$

where $\Delta\rho(t) = \rho_s - \rho_{-s}$, which satisfies the initial condition $\Delta\rho(t = t_0) = 1$, and thus $P_{\text{inc}}(t = t_0) = 0$. The total time-dependent relaxation rate is given by $\Gamma_{\text{tot}} = 2[\Gamma_{s,-s} + \Gamma_{\text{th}}]$, where the thermal rate Γ_{th}, which determines the incoherent relaxation via the excited states, is evaluated by means of relaxation diagrams (Leuenberger and Loss, 1999, 2000a).

Assuming linear time dependence, i.e., $\varepsilon_{mm'}(t) = \alpha_m^{m'} t$, in the transition region (Landau, 1932), and with $|\varepsilon_{mm'}^{<,>}| \gg \hbar\gamma_{mm'}$ one obtains from Equation 9.42

$$\Delta\rho = \exp\left\{ -\frac{2\Delta E_{s,-s}^2}{\hbar\alpha_s^{-s}} \arctan\left(\frac{\alpha_s^{-s}}{\hbar\gamma_{s,-s}} t \right) - \int_{-t}^{t} dt' \,\Gamma_{\text{th}} \right\}$$

$$\approx \exp\left\{ -\frac{\pi\Delta E_{s,-s}^2}{\hbar\alpha_s^{-s}} - \int_{-t}^{t} dt' \,\Gamma_{\text{th}} \right\}, \tag{9.43}$$

where $t_0 = -t$. In the low-temperature limit $T \rightarrow 0$ the excited states are not populated anymore and thus Γ_{th}, which consists of intermediate rates that are weighted by Boltzmann factors b_m (Leuenberger and Loss, 1999, 2000a), vanishes. Consequently, Equation 9.43 simplifies to

$$\Delta\rho = \exp\left\{ -\frac{\pi E_{s,-s}^2}{\hbar\alpha_s^{-s}} \right\} = \exp\left\{ -\frac{\pi E_{s,-s}^2}{\hbar\,|\dot{\varepsilon}_{s,-s}(0)|} \right\}. \tag{9.44}$$



FIGURE 9.7 Zener transition probability $P_{\text{inc}}(H_x)$ for temperatures T = 0.7, 0.65, 0.6, 0.55, 0.5, 0.45, and 0.05 K. The fit agrees well with data. Note that P_{inc} is equal to $2P$. (From Wernsdorfer, W. et al., *Europhys. Lett.*, 50, 552, 2000.)

The exponent in Equation 9.44 differs by a factor of 2 from the Zener exponent (Landau, 1932). This is not surprising since Γ_{tot} is the relaxation rate of $\Delta\rho$, where both ρ_s and ρ_{-s} are changed in time by the same amount, and *not* an escape rate like in the case of coherent Zener transition, where only the population of the initial state is changed in time. Equation 9.44 implies $P_{\text{inc}} = 1$ for $|\dot{\varepsilon}_{s,-s}(0)| \rightarrow 0$ (adiabatic limit) and $P_{\text{inc}} = 0$ for $|\dot{\varepsilon}_{s,-s}(0)| \rightarrow \infty$ (sudden limit). After fitting the parameters the incoherent Zener theory is in excellent agreement with experiments (Wernsdorfer and Sessoli, 1996; Wernsdorfer et al., 2000) for the temperature range $0.05\,\text{K} \leq T \leq 0.7\,\text{K}$ if the states $|\pm 10\rangle$, $|\pm 9\rangle$, and $|\pm 8\rangle$ are taken into account. In particular, the path leading through $|\pm 8\rangle$ gives a non-negligible contribution for $T \geq 0.6\,\text{K}$. One obtains the following from Equation 9.43 for Fe_8 in the case $n = 0$:

$$\begin{aligned} \Gamma_{\text{tot}} &= 2\left(\Gamma_{10}^{-10} + \sum_{n=9}^{8} \frac{b_n}{\dfrac{2}{W_{10,n}} + \dfrac{1}{\Gamma_{n,-n}}} \right), \\ \Delta\rho &= \exp\left\{ -\frac{\pi E_{10,-10}^2}{\hbar\alpha_{10}^{-10}} - \sum_{n=9}^{8} \frac{\pi E_{n,-n}^2 W_{10,n} b_n}{\alpha_n^{-n} \sqrt{E_{n,-n}^2 + \hbar^2 W_{10,n}^2}} \right\}, \end{aligned} \tag{9.45}$$

where the approximation $\gamma_{n,-n} \approx W_{10,n}$ and $|\varepsilon_{mm'}^{<,>}| \gg E_{n,-n}, \gamma_{n,-n}$ is used. $P_{\text{inc}} = 1 - \Delta\rho$, which is plotted in Figure 9.7, is in excellent agreement with the measurements (Wernsdorfer et al., 2000).

9.6 Coherent Néel Vector Tunneling in Antiferromagnetic Molecular Wheels

Antiferromagnetic molecular clusters are the most promising candidates for the observation of coherent quantum tunneling on the mesoscopic scale currently available (Chiolero and Loss, 1998). Several systems in which an even number N of antiferromagnetically coupled ions is arranged on a ring have been synthesized to date (Papaefthymiou et al., 1994; Fabretti et al., 1996; Schromm et al., 2001; Gatteschi et al., 2002). These systems are well described by the spin Hamiltonian

$$\hat{\mathcal{H}} = J\sum_{i=1}^{N} \hat{\mathbf{s}}_i \cdot \hat{\mathbf{s}}_{i+1} + g\mu_B \mathbf{H} \cdot \sum_{i=1}^{N} \hat{\mathbf{s}}_i - k_z \sum_{i=1}^{N} \hat{s}_{i,z}^2, \tag{9.46}$$

where

- $\hat{\mathbf{s}}_i$ is the spin operator at site i with spin quantum number s, $\hat{\mathbf{s}}_{N+1} \equiv \hat{\mathbf{s}}_1$
- J is the nearest neighbor exchange
- $\mathbf{H}$ is the magnetic field
- $k_z > 0$ the single ion anisotropy directed along the ring axis

The parameters J and k_z have been well established both for various ferric wheels (Papaefthymiou et al., 1994; Fabretti et al., 1996; Kelemen et al., 1998; Cornia et al., 1999; Jansen et al. 1999; Koch et al., 1999; Schromm et al., 2001; Zotos et al., 2001) with $N = 6$, 8, 10, and, more recently, also for a Cr wheel (Gatteschi et al., 2002). For $\mathbf{H} = 0$, the classical ground-state spin configuration of the wheel shows alternating (Néel) order with the spins pointing along $\pm\mathbf{e}_z$. The two states with the Néel vector $\mathbf{n}$ along $\pm\mathbf{e}_z$ (Figure 9.8), labeled $|\Uparrow\rangle$ and $|\Downarrow\rangle$, are energetically degenerate and separated by an energy barrier of height $Nk_z s^2$. Because antiferromagnetic exchange induces dynamics of Néel-ordered spins, the states $|\Uparrow\rangle$ and $|\Downarrow\rangle$ are not energy eigenstates. Rather, a molecule prepared in spin state $|\Uparrow\rangle$ would tunnel coherently between $|\Uparrow\rangle$ and $|\Downarrow\rangle$ at a rate Δ/h, where Δ is the tunnel splitting (Barbara and Chudnovsky, 1990; Krive and Zaslavskii, 1990). This tunneling of the Néel vector corresponds to a simultaneous tunneling of all N spins within the wheel through a potential barrier governed by the easy axis anisotropy. Within the framework of coherent state spin path integrals, an explicit expression for the tunnel splitting Δ as a function of magnetic field $\mathbf{H}$ has been derived (Chiolero and Loss, 1998). A magnetic field applied in the ring plane, H_x, gives rise to a Berry phase acquired by the spins during tunneling (DiVincenzo et al., 1992; van Delft and Henley, 1992; Garg, 1993; Leuenberger et al., 2003). The resulting interference of different tunneling paths leads to a sinusoidal dependence of Δ on H_x, which allows one to continuously tune the tunnel splitting from 0 to a maximum value which is of order of some Kelvin for the antiferromagnetic wheels synthesized to date.



FIGURE 9.8 The two degenerate classical ground state spin configurations of an antiferromagnetic molecular wheel with easy axis anisotropy.

The tunnel splitting Δ also enters the energy spectrum of the antiferromagnetic wheel as level spacing between the ground and first excited state. Thus, Δ can be experimentally determined from various quantities such as magnetization, static susceptibility, and specific heat. Even more information on the physical properties of antiferromagnetic wheels (Equation 9.46) can be obtained from a theoretical and experimental investigation of dynamical quantities, such as the correlation functions of the total spin $\hat{\mathbf{S}} = \sum_{i=1}^{N} \hat{\mathbf{s}}_i$ or of single spins within the antiferromagnetic wheel (Meier and Loss, 2000, 2001). By symmetry arguments, it follows that the correlation function of total spin, $\langle \hat{S}_\alpha(t)\hat{S}_\alpha(0)\rangle$, which is experimentally accessible via measurement of the alternating current (AC) susceptibility does not contain a component, which oscillates with the tunnel frequency Δ/h (Meier and Loss, 2000, 2001). Hence, neither the tunnel splitting nor the decoherence rate of Néel vector tunneling can be obtained by experimental techniques which couple to the *total* spin of the wheel. In contrast, the correlation function of a single spin

$$\left\langle \hat{s}_{i,z}(t)\hat{s}_{i,z}(0)\right\rangle \simeq s^2 \left(\frac{e^{-\beta\Delta/2}}{2\cosh(\beta\Delta/2)} e^{i\Delta t/\hbar} + \frac{e^{\beta\Delta/2}}{2\cosh(\beta\Delta/2)} e^{-i\Delta t/\hbar} \right) \tag{9.47}$$

exhibits the time dependence characteristic of coherent tunneling of the quantity $\hat{S}_{i,z}$ with a tunneling rate Δ/h (Meier and Loss, 2001). We conclude that *local* spin probes are required for the observation of the Néel vector dynamics. Nuclear spins, which couple (predominantly) to a given single spin $\hat{\mathbf{s}}_i$ are ideal candidates for such probes (Meier and Loss, 2001) and have already been used to study spin cross-relaxation between electron and nuclear spins in ferric wheels (Lascialfari et al., 1999; Pini et al., 2000).

For simplicity, we consider a single nuclear spin $\hat{\mathbf{I}}$, $I = 1/2$, coupled to one-electron spin by a hyperfine contact interaction $\hat{\mathcal{H}}' = A\hat{\mathbf{s}}_1 \cdot \hat{\mathbf{I}}$. According to Equation 9.47, the tunneling electron spin $\hat{\mathbf{s}}_1$ produces a rapidly oscillating hyperfine field $As\cos(\Delta t/\hbar)$ at the site of the nucleus.

Signatures of the coherent electron spin tunneling can thus also be found in the nuclear susceptibility. For a static magnetic field applied in the plane of the ring, H_x, it can be shown that the nuclear susceptibility

$$\chi''_{I,yy}(\omega) \simeq \frac{\pi}{4}\left[\tanh\left(\frac{\beta\gamma_I H_x}{2}\right)\delta(\omega - \gamma_I H_x/\hbar) + \left(\frac{As}{\Delta}\right)^2 \tanh\left(\frac{\beta\Delta}{2}\right)\delta(\omega - \Delta/\hbar)\right] - [\omega \to -\omega] \tag{9.48}$$

exhibits a *satellite resonance at the tunnel splitting* Δ *of the electron spin system* (Meier and Loss, 2001). Here, $\gamma_I H_x$ is the Lamor frequency of the nuclear spin and the first term in Equation 9.48 corresponds to the transition between the Zeeman split energy levels of I. Because typically $As \simeq 1\,\mathrm{mK}$ and $\Delta \leq 2\,\mathrm{K}$ in Fe_{10}, the spectral weight of the satellite peak is small compared to the one of the first term in Equation 9.48 unless the magnetic field is tuned such that Δ is significantly reduced compared to its maximum value. The observation of the satellite peak in Equation 9.48 is challenging, but possible with current experimental techniques (Meier and Loss, 2001). The experiment must be conducted with single crystals of an antiferromagnetic molecular wheel with sufficiently large anisotropy $k_z > 2J/(Ns)^2$ at high, tunable fields (10 T) and low temperatures (2 K). Moreover, because the tunnel splitting $\Delta(\mathbf{H})$ depends sensitively on the relative orientation of $\mathbf{H}$ and the easy axis (Jansen et al., 1999; Zotos et al., 2001), careful field sweeps are necessary to ensure that the satellite peak in Equation 9.48 has a large spectral weight.

The need for local spin probes such as NMR or inelastic neutron scattering to detect coherent Néel vector tunneling can be traced back to the translation symmetry of the spin Hamiltonian $\hat{\mathcal{H}}$ (Meier and Loss, 2000). If this symmetry is broken, e.g., by doping of the wheel, ESR also provides an adequate technique for the detection of coherent Néel vector tunneling. If one of the original Fe or Cr ions of the wheel with spin $s = 5/2$ or $s = 3/2$, respectively, is replaced by an ion with different spin $s' \neq s$, this will in general also result in a different exchange constant J' and single ion anisotropy k_z' at the dopand site, i.e.,

$$\hat{\mathcal{H}} = J\sum_{i=2}^{N-1}\hat{\mathbf{s}}_i\cdot\hat{\mathbf{s}}_{i+1} + J'(\hat{\mathbf{s}}_1\cdot\hat{\mathbf{s}}_2+\hat{\mathbf{s}}_1\cdot\hat{\mathbf{s}}_N) + g\mu_B\mathbf{H}\cdot\sum_{i=1}^{N}\hat{\mathbf{s}}_i - \left(k_z'\hat{s}_{1,z}^2 + k_z\sum_{i=2}^{N}\hat{s}_{i,z}^2\right). \tag{9.49}$$

Although thermodynamic quantities, such as magnetization, of the doped wheel may differ significantly from the ones of the undoped wheel, the picture of spin tunneling in antiferromagnetic molecular systems (Barbara and Chudnovsky, 1990; Krive and Zaslavskii, 1990) remains valid (Meier and Loss, 2000). However, due to unequal sublattice spins, a net total spin remains even in the Néel ordered state of the doped wheel (Figure 9.9). This allows one to distinguish the configurations sketched in Figure 9.8 according to their total spin. The dynamics of the total spin $\hat{s}$ is coupled to the one of the Néel vector (DiVincenzo et al., 1992), and coherent tunneling of the Néel vector results in a coherent oscillation of the total spin. Coherent Néel vector tunneling in doped wheels can hence also be probed by ESR. The AC susceptibility shows a resonance peak at the tunnel splitting Δ,

$$\chi''_{zz}(\omega \simeq \Delta/\hbar) = \pi(g\mu_B)^2\left|\langle e|\,\hat{S}_z\,|g\rangle\right|^2\tanh\left(\frac{\beta\Delta}{2}\right)\delta(\omega-\Delta/\hbar). \tag{9.50}$$

with a transition matrix element between the ground state $|g\rangle$ and first excited state $|e\rangle$,

$$\left|\langle e|\hat{S}_z|g\rangle\right| \simeq |s'-s|\frac{8Jk_z s^2}{(g\mu_B H_x)^2} \tag{9.51}$$

for $g\mu_B H_x \gg s\sqrt{8Jk_z}$. The matrix element in Equation 9.51 determines the spectral weight of the absorption peak in the ESR spectrum. The analytical dependence has been determined within a semiclassical framework and is in good agreement with numerical results obtained from exact diagonalization of small systems (Figure 9.9).

In conclusion, several antiferromagnetic molecular wheels synthesized recently are promising candidates for the observation of coherent Néel vector tunneling. Although the observation of this phenomenon is experimentally challenging, nuclear magnetic resonance, inelastic neutron scattering, and ESR on doped wheels are adequate experimental techniques for the observation of coherent Néel vector tunneling in antiferromagnetic molecular wheels.



(a) (b)

FIGURE 9.9 The doped antiferromagnetic molecular wheel acquires a tracer spin which follows the Néel vector dynamics (a). Comparison of results obtained for the matrix element $|\langle e|\hat{S}_z|g\rangle|$ with a coherent state spin path integral formalism (solid line) and by numerical exact diagonalization (symbols) for $N = 4$, $s = 5/2$, $s' = 2$, $J' = J$, $k_z = k_z' = 0.0055J$ (b).

9.7 Berry-Phase Blockade in Single-Molecule Magnet Transistors

Single-electron devices show many promising characteristics such as ultimate low power consumption, down scalability to atomic dimensions, and high switching speed. In addition, these devices are supposed to be good candidates for applications in quantum computation and quantum information technologies. Recently there has been a huge interest in using magnetic molecules with large spin in single-electron devices to uncover the effects that a large spin has upon electron transport through single-molecule magnets (SMM) (Sangregorio et al., 1997). During the past few years, recent experiments demonstrated the possibility to place individual molecules between the source and drain leads allowing electron transport measurements (Jo et al., 2006; Henderson et al., 2007). In a three terminal molecular single-electron transistor (SET), the molecule is situated between the source and drain leads with an insulated gate electrode underneath. The insulating ligands on the periphery of the molecule act as isolating barriers and current can flow between the source and drain leads via a sequential tunneling process through the molecular energy levels, which are tuned by the gate electrode (see Figure 9.10). Several experimental and theoretical groups have been trying to predict and prove the effects on electron transport through an individual molecular nanomagnet SET. Heersche et al. reported Coulomb blockade and conduction excitation characteristics in a Mn_{12} individual molecular nanomagnet SET. Negative differential conductance and current suppression effects were explained with a model that combines spin properties of the molecule with standard sequential tunneling theory.

Recently, experiments have pointed out the importance of the interference between spin tunneling paths in molecules and its effects on electron transport scenarios involving SMMs. These results indicate that the Berry-phase interference plays an important role in the transport properties of SMMs in SET devices. Last year, the authors of this book chapter published an article (González and Leuenberger, 2007) in which an effect called the *Berry-phase blockade* was explained. The effect we described is a quantum interference effect that can be detected experimentally by measuring the current through a single molecular electron transistor with oppositely polarized leads and by applying a transverse magnetic field along specific angles. In the following we summarize our results.



FIGURE 9.10 The sketch shows a three terminal molecular single-electron transistor. The ligands on the periphery of the molecule act as isolating barriers and electrons can flow between source and drain leads by sequential or cotunneling processes through the discrete energy levels of the molecule.

For weak coupling between the leads and the SMM we used the generalized master equation describing the electronic spin states of the SMM (see Section 9.2). The sequential tunneling rates for absorption of an electron in Equation 9.19 for ground states with spin s and s' in the case of low temperatures are given by

$$\begin{aligned} W_{s',s} &= \sum_l W_{s',s}^{(l)}, \quad W_{s',s}^{(l)} = w_{\downarrow}^{(l)} f_l(\Delta_{s',s}), \\ W_{-s',-s} &= \sum_l W_{-s',-s}^{(l)}, \quad W_{-s',-s}^{(l)} = w_{\uparrow}^{(l)} f_l(\Delta_{-s',-s}), \end{aligned} \tag{9.52}$$

and the tunneling rates for the emission of an electron are given by

$$\begin{aligned} W_{s,s'} &= \sum_l W_{s,s'}^{(l)}, \quad W_{s,s'}^{(l)} = w_{\downarrow}^{(l)}[1 - f_l(\Delta_{s,s'})], \\ W_{-s,-s'} &= \sum_l W_{-s,-s'}^{(l)}, \quad W_{-s,-s'}^{(l)} = w_{\uparrow}^{(l)}[1 - f_l(\Delta_{-s,-s'})], \end{aligned} \tag{9.53}$$

where $f_l(\Delta_{s',s}) = [1 + e^{(\Delta_{s',s} - \mu_l)/kT}]^{-1}$ is the Fermi function. $w_{\downarrow\uparrow}^{(l)}$ represents the spin-dependent transition rate from the $l \in$ [Left, Right] lead to the SMM and are defined in Fermi's golden rule approximation by $w_{\downarrow}^{(l)} = 2\pi D \nu_{\downarrow}^{(l)} |t_{\downarrow}^{(l)}|^2/\hbar$ and $w_{\uparrow}^{(l)} = 2\pi D \nu_{\uparrow}^{(l)} |t_{\uparrow}^{(l)}|^2/\hbar$, respectively, where D is the density of states and $\nu_{\uparrow}^{(l)}$ and $\nu_{\downarrow}^{(l)}$ are fractions of the number of spins polarized up and down of lead l such that $\nu_{\downarrow}^{(l)} + \nu_{\uparrow}^{(l)} = 1$. $t_{\uparrow}^{(l)}$ and $t_{\downarrow}^{(l)}$ are the tunneling amplitudes of lead l, respectively. Typical values for the tunneling rate of the electron range from around $w = 10^6\ s^{-1}$ to $w = 10^{10}\ s^{-1}$ (see González and Leuenberger, 2007, and references therein).

Solving the generalized master equation for the stationary limit, we obtained the coupled differential equations

$$\begin{aligned} \dot{\rho}_s = {} & \left(\frac{\Delta_{s,-s}}{2\hbar}\right)^2 \frac{2\gamma_{s,-s}}{(g\mu_B H_z(s-(-s)))^2/\hbar^2 + \gamma_{s,-s}^2} \\ & \times (\rho_{-s} - \rho_s) + W_{s,s'}\rho_{s'} - W_{s',s}\rho_s, \end{aligned} \tag{9.54}$$

$$\begin{aligned} \dot{\rho}_{-s} = {} & \left(\frac{\Delta_{s,-s}}{2\hbar}\right)^2 \frac{2\gamma_{s,-s}}{(g\mu_B H_z(s-(-s)))^2/\hbar^2 + \gamma_{s,-s}^2} \\ & \times (\rho_s - \rho_{-s}) + W_{-s,-s'}\rho_{-s'} - W_{-s',-s}\rho_{-s}. \end{aligned} \tag{9.55}$$

The other two differential equations are obtained by just replacing $s \leftrightarrow s'$ in the above equations. Solving the set of differential equations for ρ_s, ρ_{-s}, $\rho_{s'}$ and $\rho_{-s'}$ in the stationary case ($t \gg 1/W_{m,n}$), we obtain

$$\rho_s = (W_{s,s'}(W_{-s',-s} + \Gamma_{s,-s})\Gamma_{s',-s'} + W_{-s,-s'}(W_{s',s} + \Gamma_{s',-s'})\Gamma_{s,-s})/\eta,$$

$$\rho_{-s} = (W_{s,s'}(W_{-s,-s'} + \Gamma_{s',-s'})\Gamma_{s,\text{-}s} + W_{-s,-s'}(W_{s',s} + \Gamma_{s,-s})\Gamma_{s',-s'})/\eta,$$

$$\rho_{s'} = (W_{s',s}(W_{-s,-s'} + \Gamma_{s',-s'})\Gamma_{s,-s} + W_{-s',-s}(W_{s,s'} + \Gamma_{s,-s})\Gamma_{s',-s'})/\eta,$$

$$\rho_{-s'} = (W_{s',s}(W_{-s',-s} + \Gamma_{s,-s})\Gamma_{s',-s'} + W_{-s',-s}(W_{s,s'} + \Gamma_{s',-s'})\Gamma_{s,-s})/\eta, \tag{9.56}$$

where η is a normalization factor such that $\sum_n \rho_n = 1$. The incoherent tunneling rate is

$$\Gamma_{s,-s} = \left(\frac{\Delta_{s,-s}}{2\hbar}\right)^2 \frac{2\gamma_{s,-s}}{\left(g\mu_B H_z\left(s-(-s)\right)\right)^2 / \hbar^2 + \gamma_{s,-s}^2}. \tag{9.57}$$

We now proceed to define the current through the SMM in terms of the density matrix for the case of the single molecule magnet Ni_4. In the case of Ni_4 we have $s = 4$ and $s' = 7/2$, therefore the current reads

$$I = e(W_{4,7/2}\rho_{7/2} + W_{-4,-7/2}\rho_{-7/2}). \tag{9.58}$$

In the case of leads that are fully polarized in opposite directions, i.e., $\nu_\uparrow^{(L)} = \nu_\downarrow^{(R)} = 1$ or $\nu_\downarrow^{(L)} = \nu_\uparrow^{(R)} = 1$, we get one of the two following conditions for the transition rates, respectively:

$$W_{-4,-7/2} = W_{7/2,4} = 0 \quad \text{or} \quad W_{4,7/2} = W_{-7/2,-4} = 0. \tag{9.59}$$

Choosing the case $\nu_\uparrow^{(L)} = \nu_\downarrow^{(R)} = 1$ and using the condition $W_{-4,-7/2} = W_{7/2,4} = 0$, we obtain from Equation 9.58

$$\frac{e}{I} = \frac{2}{W_{-7/2,-4}} + \frac{1}{\Gamma_{4,-4}} + \frac{2}{W_{4,7/2}} + \frac{1}{\Gamma_{7/2,-7/2}}. \tag{9.60}$$

Equation 9.60 reflects the fact that the current through the SMM depends on the tunnel splittings. The transitions that contribute to the current through the SMM in the case of fully polarized leads $\nu_\uparrow^{(L)} = \nu_\downarrow^{(R)} = 1$ are $4 \to 7/2 \to -7/2 \to -4$. Figure 9.11 shows the current as a function of $H_\perp$ for fully polarized leads. If the tunnel splitting $\Delta_{4,-4}$ or $\Delta_{7/2,-7/2}$ is topologically quenched (see Figure 9.11), $\Gamma_{4,-4}$ or $\Gamma_{7/2,-7/2}$ vanishes (see Equation 9.57), which leads to complete current suppression according to Equation 9.60. Since this current blockade is a consequence of the topologically quenched tunnel splitting, we call it *Berry-phase blockade*. Note that the current can also be suppressed by applying H_z, which follows immediately from Equations 9.57 and 9.60.



FIGURE 9.11 The graph shows the $\log_{10} I$ vs. $H_\perp$. The scale varies from $I = 0.1$ nA to 1 fA. From the figure we see that the current is completely suppressed at the zeros of the tunnel splitting, i.e., $\Delta_{4,-4} = \Delta_{7/2,-7/2} = 0$.

9.8 Concluding Remarks

We have seen how molecular nanomagnets offer an interesting platform to explore the quantum dynamics of mesoscopic systems. The theoretical advantage of using molecular nanomagnets is that molecules are all identical to each other, allowing the performance of experiments on large assemblies of identical particles and detect quantum effects. Molecules can be investigated in solutions or solids depending on the experiment you want to perform, allowing accurate measurements. We have paid special attention to the quantum tunneling of the magnetization of molecular nanomagnets and the different approaches that exist to describe this phenomenon. In particular we have placed emphasis on the interference effects of the quantum tunneling of the magnetization via Berry's phase and we have included some of our recent results in this field (González and Leuenberger, 2007).

Molecular nanomagnets are also the subject of intense research in molecular electronics. Single-electron devices have taken advantage of the small size of nanomagnets to create electronic structures of atomic dimensions. These devices are supposed to be good candidates for applications in quantum computation and quantum information technologies. There has been also a lot of research on single-electron transistors (SET) made of molecular nanomagnets to study quantum effects such as the Kondo effect in this kind of structures (Leuenberger and Mucciolo, 2006). The Kondo effect is a very well known and studied phenomenon in condensed matter physics. This effect arises when a magnetic impurity is placed into a conductor, which causes a dramatic increase in the resistivity of the metal at low temperatures. The Kondo effect can be seen also in a single-electron transistor where the molecular nanomagnet plays the role of the magnetic impurity and the leads of the SET mimics the bulk metal. It has been shown that the Hamiltonian for a molecular nanomagnet placed in a SET device can be mapped onto the Kondo Hamiltonian (González et al., 2008). This result is of great interest because one can apply the poor man's scaling theory to describe the Kondo physics at low temperatures and see how the Berry-phase oscillations become temperature dependent. This fact allows us to conclude that the scaling equations can be checked experimentally by measuring the renormalized zero points of the Berry phase.

The field of molecular nanomagnets is growing very fast and chemistry is playing a major role concerning the growth of these nanostructures. New nanomagnets with novel and interesting magnetic properties are being produced, which demand more sophisticated theories to explain and describe the dynamics of these magnetic mesoscopic systems. One direction which remains a major area of investigation lately is related to storing and decoding information on a single spin state to be able to create a quantum computer. The implementation of Grover's algorithm with molecular nanomagnets has already been proposed, however, it is required to perform simultaneous manipulation of many spin phases without losing quantum coherence, which remains still an experimental challenge.

Acknowledgment

We acknowledge support from NSF-ECCS 0725514, the DARPA/MTO Young Faculty Award HR0011-08-1-0059, 0901784, and AFOSR FA 9550-09-1-0450.

References

Averin, D. and A. Bardas. AC Josephson effect in a single quantum channel. *Phys. Rev. Lett.*, 75:1831–1834, 1995.

Barbara, B. and E.M. Chudnovsky. Macroscopic quantum tunneling in antiferromagnets. *Phys. Lett. A*, 145:205–208, 1990.

Barbara, B., W. Wernsdorfer, L.C. Sampaio, J.G. Park, C. Paulsen, M.A. Novak, R. Ferré, D. Mailly, R. Sessoli, A. Caneschi, K. Hasselback, A. Benoit, and L. Thomas. Mesoscopic quantum tunneling of the magnetization. *J. Magn. Magn. Mater*, 140–144:1825–1828, 1995.

Barra, A.L., P. Debrunner, D. Gatteschi, C.E. Schulz, and R. Sessoli. Superparamagnetic-like behavior in an octanuclear iron cluster. *Europhys. Lett.*, 35:133–138, 1996.

Chiolero, A. and D. Loss. Macroscopic quantum coherence in molecular magnets. *Phys. Rev. Lett.*, 80:169–172, 1998.

Chudnovsky, E.M. and L. Gunther. Quantum tunneling of magnetization in small ferromagnetic particles. *Phys. Rev. Lett.*, 60:661–664, 1988.

Cornia, A., M. Affronte, J.C. Lasjaunias, and A. Caneschi. Low-temperature specific heat of Fe6 and Fe10 molecular magnets. *Phys. Rev. B*, 60:1161–1166, 1999.

Crothers, D.S. and J.G. Huges. Stueckelberg close-curve-crossing phases. *J. Phys. B*, 10:L557–L560, 1977.

DiVincenzo, D.P., D. Loss, and G. Grinstein. Suppression of tunneling by interference in half-integer-spin particles. *Phys. Rev. Lett.*, 69:3232–3235, 1992.

Enz, M. and R. Schilling. Magnetic field dependence of the tunnelling splitting of quantum spins. *J. Phys. C: Solid State Phys.*, 19:L711–L715, 1986.

Fabretti, A.C., S. Foner, D. Gatteschi, R. Grandi, A. Caneshi, A. Cornia, and L. Schenetti. Synthesis, crystal structure, magnetism, and magnetic anisotropy of cyclic clusters comprising six iron(iii) ions and entrapping alkaline ions. *Chem. Eur. J.*, 2:1379–1387, 1996.

Feynman R.P. Space-Time Approach to Non-Relativistic Quantum Mechanics. *Rev. Mod. Phys.*, 20:367–387, 1948.

Fort, A., A. Rettori, J. Villain, D. Gatteschi, and R. Sessoli. Mixed quantum-thermal relaxation in Mn12 acetate molecules. *Phys. Rev. Lett.*, 80:612–615, 1998.

Friedman, J.R., M.P. Sarachik, J. Tejada, and R. Ziolo. Macroscopic measurement of resonant magnetization tunneling in high-spin molecules. *Phys. Rev. Lett*, 76:3830–3833, 1996.

Garanin, D.A. and E.M. Chudnovsky. Thermally activated resonant magnetization tunneling in molecular magnets: Mn12ac and others. *Phys. Rev. B*, 56:11102–11118, 1997.

Garg, A. Topologically quenched tunnel splitting in spin systems without kramers' degeneracy. *Europhys. Lett.*, 22:205–210, 1993.

Garga, A., N.J. Onuchi, and V. Ambegaokar. Effect of friction on electron transfer in bio-molecules. *J. Chem. Phys.*, 83:4491–4503, 1985.

Gatteschi, D., A.A. Smith, M. Helliwell, R.E.P. Winpenny, A. Cornia, A.L. Barra, A.G.M. Jansen, E. Rentschler, J. van Slageren, R. Sessoli, and G.A. Timco. Magnetic anisotropy of the antiferromagnetic ring [cr8f8piv16]. *Chem. Eur. J.*, 8:277–285, 2002.

González, G. and M.N. Leuenberger. Berry-phase blockade in single-molecule magnets. *Phys. Rev. Lett.*, 98:256804-4, 2007.

González, G., M.N. Leuenberger, and E.R. Mucciolo. Kondo effect in single-molecule magnet transistors. *Phys. Rev. B*, 78:054445-12, 2008.

Henderson, J.J., C.M. Ramsey, E. del Barco, A. Mishra, and G. Christou. Fabrication of nano-gapped single-electron transistors for transport studies of individual single-molecule magnets. *J. Appl. Phys.*, 101:09E102, 2007.

Hernández, J.M., X.X. Zhang, F. Luis, J. Bartolomé, J. Tejada, J.R. Friedman, M.P. Sarachik, and R. Ziolo. Field tuning of thermally activated magnetic quantum tunnelling in mn12—ac molecules. *Europhys. Lett.*, 35:301–306, 1996.

Hernández, J.M., X.X. Zhang, J. Tejada, F. Luis, and R. Ziolo. Evidence for resonant tunneling of magnetization in Mn12sacetate complex. *Phys. Rev. B*, 55:5858–5865, 1997.

Jansen, A.G.M., A. Cornia, and M. Affronte. Magnetic anisotropy of Fe6 and Fe10 molecular rings by cantilever torque magnetometry in high magnetic fields. *Phys. Rev. B*, 60:12177–12183, 1999.

Jo, M.-H., J.E. Grose, K. Baheti, M.M. Deshmukh, J.J. Sokol, E.M. Rumberger, D.N. Hendrickson, J.R. Long, H. Park, and D.C. Ralph. Signatures of molecular magnetism in single-molecule transport spectroscopy. *Nano Lett.*, 6:2014–2020, 2006.

Kelemen, M.T., M. Weickenmeier, B. Pilawa, R. Desquiotz, and A. Geisselmann. Magnetic properties of new Fe6(triethanolaminate(3-))6 spin-clusters. *J. Magn. Magn. Mat.*, 177–181:748–749, 1998.

Koch, R., P. Müller, I. Bernt, R.W. Saalfrank, H.P. Andres, H.U. Güdel, O. Waldmann, J. Schülein, and O. Allenspach. Magnetic anisotropy of two cyclic hexanuclear Fe(iii) clusters entrapping alkaline ions. *Inorg. Chem.*, 38:5879–5886, 1999.

Korenblit, I.Ya. and E.F. Shender. Low-temperature properties of amorphous magnetic materials with random axis of anisotropy. *Sov. Phys. JETP*, 48:937–942, 1978.

Krive, I.V. and O.B. Zaslavskii. Macroscopic quantum tunnelling in antiferromagnets. *J. Phys. Condens. Matter*, 2:9457–9462, 1990.

Landau, L.D. On the theory of transfer of energy at collisions. *Phys. Z. Sowjetunion*, 2:46, 1932.

Lascialfari, A., F. Borsa, M. Horvati, A. Caneschi, M.H. Julien, Z.H. Jang, and D. Gatteschi. Proton NMR for measuring quantum level crossing in the magnetic molecular ring Fe10. *Phys. Rev. Lett.*, 83:227–230, 1999.

Leuenberger, M.N. and D. Loss. Spin relaxation in Mn12-acetate. *Europhys. Lett.*, 46:692–698, 1999.

Leuenberger, M.N. and D. Loss. Spin tunneling and phonon-assisted relaxation in Mn12-acetate. *Phys. Rev. B*, 61:1286–1302, 2000a.

Leuenberger, M.N. and D. Loss. Incoherent zener tunneling and its application to molecular magnets. *Phys. Rev. B*, 61:12200–12203, 2000b.

Leuenberger, M.N. and D. Loss. Spin tunneling and topological selection rules for integer spins. *Phys. Rev. B*, 63:054414-4, 2001a.

Leuenberger, M.N. and D. Loss. Quantum computing in molecular magnets. *Nature*, 410:789–793, 2001b.

Leuenberger, M.N. and D. Loss. Reply to the comment of E. M. Chudnovsky and D. A. Garanin on Spin relaxation in Mn_{12}-acetate. *Europhys. Lett.*, 52: 247–248, 2000.

Leuenberger, M.N., F. Meier, and D. Loss. Quantum spin dynamics in molecular magnets. *Monatshefte fuer Chemie*, 134:217–233, 2003.

Leuenberger, M.N. and E.R. Mucciolo. Berry-phase oscillation of the Kondo effect in single-molecule magnets. *Phys. Rev. Lett.*, 97:126601, 2006.

Luis, F., J. Bartolomé, and F. Fernández. Resonant magnetic quantum tunneling through thermally activated states. *Phys. Rev. B*, 57:505–513, 1998.

Meier, F. and D. Loss. Thermodynamics and spin-tunneling dynamics in ferric wheels with excess spin. *Phys. Rev. B*, 64:224411–224414, 2000.

Meier, F. and D. Loss. Electron and nuclear spin dynamics in antiferromagnetic molecular rings. *Phys. Rev. Lett.*, 86:5373–5376, 2001.

Novak, M.A. and R. Sessoli. *Quantum Tunneling of Magnetization*. L. Gunther and B. Barbara (eds.), Kluwer, Dordrecht, the Netherlands, 1995.

Novak, M.A., R. Sessoli, A. Caneschi, and D. Gatteschi. Magnetic properties of a Mn cluster organic compound. *J. Magn. Magn. Mater*, 146:211–213, 1995.

Ohm, T., C. Sangregorio, and C. Paulsen. Local field dynamics in a resonant quantum tunneling system of magnetic molecules. *Europhys. J. B*, 6:195–199, 1998.

Papaefthymiou, G.C., S. Foner, D. Gatteschi, K.L. Taft, C.D. Delfs, and S.J. Lippard. [Fe(OMe)2(O2CCH2Cl)]10, a molecular ferric wheel. *J. Am. Chem. Soc.*, 116:823–832, 1994.

Paulsen, C. and J.G. Park. *Quantum Tunneling of Magnetization*. L. Gunther and B. Barbara (eds.), Kluwer, Dordrecht, the Netherlands, 1995.

Paulsen, C., J.G. Park, B. Barbara, R. Sessoli, and A. Caneschi. Novel features in the relaxation times of Mn12Ac. *J. Magn. Magn. Mater*, 140–144:379–380, 1995.

Pini, M.G., A. Cornia, A. Fort, and A. Rettori. Low-temperature theory of proton NMR in the molecular antiferromagnetic ring Fe10. *Europhys. Lett.*, 50:88–93, 2000.

Sangregorio, C., T. Ohm, C. Paulsen, R. Sessoli, and D. Gatteschi. Quantum tunneling of the magnetization in an iron cluster nanomagnet. *Phys. Rev. Lett.*, 78:4645–4648, 1997.

Schromm, S., J. Schülein, P. Müller, I. Bernt, R.W. Saalfrank, O. Waldmann, R. Koch, and F. Hampel. Magnetic anisotropy of a cyclic octanuclear Fe(iii) cluster and magneto-structural correlations in molecular ferric wheels. *Inorg. Chem.*, 40:2986–2995, 2001.

Sessoli, R., D. Gatteschi, A. Caneschi, and M.A. Novak. Magnetic bistability in a metal-ion cluster. *Nature*, 365:141–143, 1993.

Shimshoni, E. and Y. Gefen. Onset of dissipation in zener dynamics: Relaxation vs. dephasing. *Ann. Phys.*, 210:16–80, 1991.

Thomas, L., F. Lionti, R. Ballou, D. Gatteschi, R. Sessoli, and B. Barbara. Macroscopic quantum tunnelling of magnetization in a single crystal of nanomagnets. *Nature*, 383:145–147, 1996.

von Delft, J. and C.L. Henley. Destructive quantum interference in spin tunneling problems. *Phys. Rev. Lett.*, 69:3236–3239, 1992.

van Hemmen, J.L. and A. Süto. Tunnelling of quantum spins. *Europhys. Lett.*, 1:481–490, 1986.

Villain, J., F. Hartmann-Boutron, R. Sessoli, and A. Rettori. Magnetic relaxation in big magnetic molecules. *Europhys. Lett.*, 27:159–164, 1994.

Wernsdorfer, W. and R. Sessoli. Quantum phase interference and parity effects in magnetic molecular clusters. *Science*, 284:133–135, 1996.

Wernsdorfer, W., R. Sessoli, A. Caneshi, D. Gatteschi, and A. Cornia. Nonadiabatic Landau-Zener tunneling in Fe8 molecular nanomagnets. *Europhys. Lett.*, 50:552–558, 2000.

Zener, C. Non-adiabatic crossing of energy levels. *Proc. R. Soc. Lond. A*, 137:696, 1932.

Zotos, X., B. Normand, X. Wang, and D. Loss. Magnetization in molecular iron rings. *Phys. Rev. B*, 63:184409, 2001.

10

Inelastic Electron Transport through Molecular Junctions

10.1 Introduction 10-1
10.2 Coherent Transport 10-2
10.3 Buttiker Model for Inelastic Transport 10-5
10.4 Vibration-Induced Inelastic Effects 10-6
10.5 Dissipative Transport 10-9
10.6 Polaron Effects: Hysteresis, Switching, and Negative Differential Resistance 10-11
10.7 Molecular Junction Conductance and Long-Range Electron-Transfer Reactions 10-13
10.8 Concluding Remarks 10-15
References 10-16

Natalya A. Zimbovskaya
University of Puerto Rico

10.1 Introduction

Molecular electronics is known to be one of the most promising developments in nanoelectronics, and the past decade has seen extraordinary progress in this field (Aviram et al. 2002, Cuniberti et al. 2005, Nitzan 2001). Present activities on molecular electronics reflect the convergence of two trends in the fabrication of nanodevices, namely, the top-down device miniaturization through the lithographic methods and bottom-up device manufacturing through the atom-engineering and the self-assembly approaches. The key element and the basic building block of molecular electronics is a junction including two electrodes (leads) linked by a molecule, as schematically shown in Figure 10.1. Usually, the electrodes are microscopic large but macroscopic small contacts that could be connected to a battery to provide the bias voltage across the junction. Such a junction may be treated as a quantum dot coupled to the charge reservoirs. The discrete character of energy levels on the dot (molecule) is combined with nearly continuous energy spectra on the reservoirs (leads) occurring due to their comparatively large size.

When the voltage is applied, an electric current flows through the junction. Successful transport experiments with molecular junctions (Ho 2002, Lortscher et al. 2007, Park et al. 2000, Poot et al. 2006, Reichert et al. 2002, Smit et al. 2002, Yu et al. 2004) confirm their significance as active elements in nanodevices. These include applications as rectifiers (molecular diodes), field-effect transistors (molecular triodes), switches, memory elements and sensors. Also, these experiments emphasize the importance of a thorough analysis of the physics underlying electron transport through molecular junctions. A detailed understanding of electron transport at the molecular scale is a key step to future device operations. A theory of electron transport in molecular junctions is being developed since the last two decades, and main transport mechanisms are currently elucidated in general terms (Datta 2005, Imry and Landauer 1999). However, a progress of the experimental capabilities in the field of molecular electronics brings new theoretical challenges causing a further development of the theory.

Speaking of transport mechanisms, it is useful to make a distinction between elastic electron transport when the electron energy remains the same as it travels through the junction, and inelastic transport processes when the electron undergoes energy changes due to its interactions with the environment. There are several kinds of processes bringing inelasticity in the electron transport in mesoscopic systems including molecular junctions. Chief among these are electron–electron and electron–phonon scattering processes. These processes may bring about significant inelastic effects modifying the transport properties of molecular devices and charging, desorption, and chemical reactions as well. To keep this chapter at a reasonable length, we concentrate on the inelastic effects originating from electron–phonon interactions.

In practical molecular junctions, the electron transport is always accompanied by nuclear motions in the environment. Therefore, the conduction process is influenced by the coupling between the electronic and the vibrational degrees of freedom. Nuclear motions underlie the interplay between the coherent electron tunneling through the junction and the inelastic thermally assisted hopping transport



FIGURE 10.1 Schematic drawing of a junction including two electrodes and a molecule in between (a). When the voltage is applied across the junction, electrochemical potentials μ_L and μ_R differ, and the conduction window opens up (b).

(Nitzan 2001). Also, electron–phonon interactions may result in polaronic conduction (Galperin et al. 2005, Gutierrez et al. 2005, Kubatkin et al. 2003, Ryndyk et al. 2008), and they are directly related to the junction heating (Segal et al. 2003) and to some specific effects such as alterations in both shape of the molecule and its position with respect to the leads (Komeda et al. 2002, Mitra et al. 2004, Stipe et al. 1999). The effects of electron–phonon interactions may be manifested in the inelastic tunneling spectrum (IETS) that presents the second derivative of the current in the junction d^2I/dV versus the applied voltage V. The inelastic electron tunneling microscopy has proven to be a valuable method for the identification of molecular species within the conduction region, especially when employed in combination with scanning tunneling microscopy and/or spectroscopy (Galperin et al. 2004).

Inelasticity in the electron transport through molecular junctions is closely related to the dephasing effects. One may say that incoherent electron transport always includes an inelastic contribution with the possible exception of the low temperature range. The general approach to theoretically analyzing electron transport through molecular junctions in the presence of dissipative/phase-breaking processes in both electronic and nuclear degrees of freedom is based on advanced formalisms (Segal et al. 2000, Skourtis and Mukamel 1995, Wingreen et al. 1989, 1993). These microscopic computational approaches have the advantages of being capable of providing detailed dynamics information. However, while considering stationary electron transport through molecular junctions, one may turn to the less time-consuming approach based on scattering matrix formalism (Buttiker 1986, Li and Yan 2001a,b), as discussed below.

10.2 Coherent Transport

To better show the effects of dissipation/dephasing on the electron transport through molecular junctions, it seems reasonable to start from the case where these effects do not occur. So, we consider a molecule (presented as a set of energy levels) placed in between two electrodes with nearly continuous energy spectra. While there is no bias voltage applied across the junction, the latter remains in equilibrium characterized by the equilibrium Fermi energy E_F, and there is no current flowing through it. When the bias voltage is applied, it keeps the left and right electrodes at different electrochemical potentials μ_L and μ_R. Then the electric current appears in the junction, and the molecular energy levels located in between the electrochemical potentials μ_L and μ_R play a major part in maintaining this current. Electrons from occupied molecular states tunnel to the electrodes in accordance with the voltage polarity, and the electrons from one electrode travel to another one using unoccupied molecular levels as intermediate states for tunneling. Usually, the electron transport in molecular junctions occurs via the highest occupied (HOMO) and the lowest unoccupied (LUMO) molecular orbitals that work as channels for electron transmission. Obviously, the current through the junction depends on the quality of contacts between the leads and the molecule ends. However, there also exists the limit for the conductance in the channels. As was theoretically shown (Landauer 1970), the maximum conductance of a channel with a single-spin degenerate-energy level equals:

$$G_0 = \frac{e^2}{\pi\hbar} = (25.8\ \text{k}\Omega)^{-1} \tag{10.1}$$

where
e is the electron charge
$\hbar$ is Planck's constant

This is a truly remarkable result for it proves that the minimum resistance $R_0 = G_0^{-1}$ of a molecular junction cannot become zero. In another words, one never can short-circuit a device operating with quantum channels. Also, the expression (10.1) shows that the conductance is a quantized quantity.

Conductance g in practical quantum channels associated with molecular orbitals can take on values significantly smaller that G_0, depending on the delocalization in the molecular orbitals participating in the electron transport. In molecular junctions it also strongly depends on the molecule coupling to the leads (quality of contacts), as was remarked before. The total resistance $r = g^{-1}$ includes contributions from the contact and the molecular resistances, and could be written as (Wingreen et al. 1993)

$$r = \frac{1}{G_0}\left(1 + \frac{1-T}{T}\right). \tag{10.2}$$

Here, T is the electron transmission coefficient that generally takes on values less than unity.

The general expression for the electric current flowing through the molecular junction could be obtained if one calculates the total probability for an electron to travel between two electrodes at a certain tunnel energy E and then integrates the latter over the whole energy range (Datta 1995). This results in the well-known Landauer expression:

$$I = \frac{e}{\pi\hbar}\int T(E)\big[f_L(E) - f_R(E)\big]dE. \qquad (10.3)$$

Here, $f_{L,R}(E)$ are Fermi distribution functions for the electrodes with chemical potentials $\mu_{L,R}$, respectively. The values of $\mu_{L,R}$ differ from the equilibrium energy E_F, and they are determined by the voltage distribution inside the system. Assuming that coherent tunneling predominates in electron transport, the electron transmission function is given by (Datta et al. 1997, Samanta et al. 1996):

$$T(E) = 2Tr\left\{\Delta_L G \Delta_R G^+\right\}, \qquad (10.4)$$

where

the matrices $\Delta_{L,R}$ represent the imaginary parts of the self-energy terms $\Sigma_{L,R}$ describing the coupling of the molecule to the electrodes

G is the Green's function matrix for the molecule whose matrix elements between the molecular states $\langle i|$ and $|j\rangle$ have the form

$$G_{ij} = \left\langle i\middle|E - H\middle|j\right\rangle. \qquad (10.5)$$

Here, H is the molecular Hamiltonian including the self-energy parts $\Sigma_{L,R}$.

When a molecule contacts the surface of electrodes, this results in a charge transfer between the molecule and the electrodes, and in a modification of the molecule energy states due to the redistribution of the electrostatic potential within the molecule. Besides, the external voltage applied across the junction brings additional changes to the electrostatic potential further modifying the molecular orbitals. The coupling of the molecule to the leads may also depend on the voltage distribution. So, generally, the electron transmission T inserted in Equation 10.3 and the electrochemical potentials $\mu_{L,R}$ depend on the electrostatic potential distribution in the system. To find the correct distribution of the electric field inside the junction one must simultaneously solve the Schrodinger equation for the molecule and the Poisson equation for the charge density, following a self-consistent converging procedure. This is a nontrivial and complicated task, and significant effort was applied to study the effect of electrostatic potential distribution on the electron transport through molecules (Damle et al. 2001, Di Ventra et al. 2000, Galperin et al. 2006, Lang and Avouris 2000a,b, Mujica et al. 2000, Xue and Ratner 2003a,b, 2004, Xue et al. 2001). Here, we put these detailed considerations aside, and we use the simplified expression for the electrochemical potentials:

$$\mu_L = E_F + \eta|e|V; \quad \mu_R = E_F - (1-\eta)|e|V, \qquad (10.6)$$

where the parameter η indicates how the bias voltage is distributed between the electrodes. Also, we assume that inside the molecule, the external electrostatic field is screened due to the charge redistribution, and the electron transmission is not sensitive to the changes in the voltage V. Although very simple, this model allows one to analyze the main characteristics of the electron transport through molecular junctions. Within this model one may write down the following expression for the self-energy parts (D'Amato and Pastawski 1990):

$$(\Sigma_\beta)_{ij} = \sum_k \frac{\tau^*_{ik,\beta}\,\tau_{kj,\beta}}{E - \varepsilon_{k,\beta} + is}. \qquad (10.7)$$

Here,

$\beta \in L, R$, $\tau_{ik,\beta}$ is the coupling strength between the ith molecular state and the kth state on the left/right lead

$\varepsilon_{k,\beta}$ are the energy levels on the electrodes

s is a positive infinitesimal parameter

Assuming that the molecule is reduced to a single orbital with the energy E_0 (a single-site bridge), Green's function accepts the form

$$G(E) = \frac{1}{E - E_0 - \Sigma_L - \Sigma_R}. \qquad (10.8)$$

Accordingly, in this case, one may simplify the expression (10.4) for the electron transmission:

$$T(E) = \frac{4\Delta_L\Delta_R}{(E-E_0)^2 + (\Delta_L + \Delta_R)^2}. \qquad (10.9)$$

To elucidate the main features of electron transport through molecular junctions we consider a few examples. In the first example, we mimic a molecule as a one-dimensional chain consisting of N identical hydrogen-like atoms with the nearest neighbors interaction. We assume that there is one state per isolated atom with the energy E_0, and that the coupling between the neighboring sites in the chain is characterized by the parameter b. Such a model was theoretically analyzed by D'Amato and Pastawski and in some other works (see e.g., Mujica et al. 1994). Based on Equations 10.4 and 10.5, it could be shown that for a single-site chain ($N = 1$) the electron transmission reveals a well-distinguished peak at $E = E_0$, shown in Figure 10.2. The height of this peak is determined by the coupling of the bridge site to the electrodes. The peak in the electron transmission arises because the molecular orbital $E = E_0$ works as the channel/bridge for electron transport between the leads. Similar peaks appear in the conductance $g = dI/dV$. Assuming the symmetric voltage distribution ($\eta = 1/2$), the peak in the conductance is located at $V = \pm 2E_0$. As for the current voltage characteristics, they display step-like shapes with the steps at $V = \pm 2E_0$. When the chain includes several sites, we obtain a set of states (orbitals) for our bridge instead of the single state $E = E_0$, and their number equals the number of



FIGURE 10.2 Coherent electron transmission (left panel) and current (right panel) versus bias voltage applied across a molecular junction where the molecule is simulated by a single electronic state. The curves are plotted assuming $\Delta_L = \Delta_R = 0.1\,\text{eV}$, $E_0 = -0.5\,\text{eV}$, $T = 30\,\text{K}$.



FIGURE 10.3 Coherent electron transmission (left panel) and current (right panel) through a junction with a five electronic states bridge. The curves are plotted for $\Delta_L = \Delta_R = 0.1\,\text{eV}$, $b = 0.3\,\text{eV}$, $E_0 = -0.5\,\text{eV}$, $T = 30\,\text{K}$.

sites in the chain. All these states are the channels for the electron transport. Correspondingly, the transmission reveals a set of peaks as presented in Figure 10.3. The peaks are located within the energy range with the width $4b$ around $E = E_0$. The coupling of the chain ends to the electrodes affects the transmission, especially near $E = E_0$. As the coupling strengthens, the transmission minimum values increase. Now, the current voltage curves exhibit a sequence of steps. The longer the chain, the more energy levels it possesses, and the more the number of steps in the I–V curves.

The second example concerns the electron transport through a carbon chain placed between copper electrodes. In this case, as well as for practical molecules, a preliminary step in transport calculations is to compute the relevant molecular energy levels and wave functions. Usually, these computations are carried out employing quantum chemistry software packages (e.g., Gaussian) or density functional-based software. Also, a proper treatment of the molecular coupling to the electrodes is necessary for it brings changes into the molecular energy states. For this purpose, one may use the concept of an "extended molecule" proposed by Xue et al. (2001). The point of this concept is that only a few atoms on the surface of the metallic electrode are significantly disturbed when the molecule is attached to the latter. These atoms are located in the immediate vicinity of the molecule end. Therefore, one may form a system consisting of the molecule itself and the atoms from the electrode surfaces perturbed by the molecular presence. This system is called the extended molecule and treated as such while computing the molecular orbitals. In the example considered, the extended molecule included four copper atoms on each side of the carbon chain. The results for electron transport are shown in Figure 10.4. Again, we observe a comb-like shape of the electron transmission corresponding to the set of transport channels provided by the molecular orbitals, and the stepwise I–V curve originating from the latter. Transport calculations similar to those described above were repeatedly carried out in the last two decades for various practical molecules (see e.g., Galperin et al. 2006, Xue and Ratner 2003a,b, Xue et al. 2001, Zimbovskaya 2003, 2008, Zimbovskaya and Gumbs 2002).



FIGURE 10.4 Coherent electron transmission (left panel) and current (right panel) through a carbon chain coupled to the copper leads at $T = 30$ K.

10.3 Buttiker Model for Inelastic Transport

An important advantage of the phenomenological model for the incoherent/inelastic quantum transport proposed by Buttiker (1986) is that this model could easily be adapted to analyze various inelastic effects in electron transport through molecules (and some other mesoscopic systems) avoiding complicated and time-consuming advanced methods, such as those based on the nonequilibrium Green's functions formalism (NEGF).

Here, we present the Buttiker model for a simple junction including two electrodes linked by a single-site molecular bridge. The bridge is attached to a phase-randomizing electron reservoir, as shown in Figure 10.5. Electrons tunnel from the electrodes to the bridge and vice versa via the channels 1 and 2. While on the bridge, an electron could be scattered into the channels 3 and 4 with a certain probability ε. Such an electron arrives at the reservoir where it undergoes inelastic scattering accompanied by phase-breaking and then the reservoir reemits it back to the channels 3 and 4 with the same probability. So, within the Buttiker model, the electron transport through the junction is treated as the combination of tunnelings through the barriers separating the molecule from the electrodes and the interaction with the phase-breaking electron reservoir coupled to the bridge site. The key parameter of the model is the probability ε that is closely related to the coupling strength between the bridge site and the reservoir. When $\varepsilon = 0$ the reservoir is detached from the bridge, and the electron transport is completely coherent and elastic. Within the opposite limit ($\varepsilon = 1$), electrons are certainly scattered into the reservoir that results in the overall phase randomization and inelastic transport.



FIGURE 10.5 Schematic drawing illustrating inelastic electron transport through a molecular junction within the Buttiker model.

Within the Buttiker model, the particle fluxes outgoing from the junctions J_i' could be presented as the linear combinations of the incoming fluxes J_k where the indexes i, k label the channels for the transport: $1 \le i, k \le 4$.

$$J_i' = \sum_k T_{ik} J_k. \tag{10.10}$$

The coefficients T_{ik} in these linear combinations are matrix elements of the transmission matrix that are related to the elements of the scattering matrix S, namely, $T_{ik} = |S_{ik}|^2$. The matrix S expresses the outgoing wave amplitudes b_1', b_2', a_3', a_4' in terms of the incident ones b_1, b_2, a_3, a_4. To provide the charge conservation in the system, the net current in the channels 3 and 4 linking the system with the dephasing reservoir must be zero, so we may write

$$J_3 + J_4 - J_3' - J_4' = 0. \tag{10.11}$$

The transmission for quantum transport could be defined as the ratio of the particle flux outgoing from the system and that one incoming to the latter. Solving Equations 10.10 and 10.11 we obtain

$$T(E) = \frac{J_2'}{J_1} = T_{21} + \frac{K_1 \cdot K_2}{2R}, \tag{10.12}$$

where

$$K_1 = T_{31} + T_{41}; \quad K_2 = T_{23} + T_{24};$$
$$R = T_{33} + T_{44} + T_{43} + T_{34}. \tag{10.13}$$

For the junction including the single-site bridge the scattering matrix S has the form (Buttiker 1986)

$$S = \frac{1}{Z}\begin{pmatrix} r_1 + \alpha^2 r_2 & \alpha t_1 t_2 & \beta t_1 & \alpha\beta t_1 r_2 \\ \alpha t_1 t_2 & r_2 + \alpha^2 r_1 & \alpha\beta r_1 t_2 & \beta t_2 \\ \beta t_1 & -\beta r_1 t_2 & \beta^2 r_1 & \alpha r_1 r_2 - \alpha \\ \alpha\beta t_1 r_2 & \beta t_2 & \alpha r_1 r_2 - \alpha & \beta^2 r_2 \end{pmatrix}. \tag{10.14}$$

Here, $Z = 1 - \alpha^2 r_1 r_2$, $\alpha = \sqrt{1-\varepsilon}$, $\beta = \sqrt{\varepsilon}$, and $r_{1,2}$ and $t_{1,2}$ are the amplitude reflection and the transmission coefficients for the two barriers. Later, the expression for this matrix suitable for the case of multisite bridges including several inelastic scatterers was derived (Li and Yan 2001a,b).

Assuming for certainty the charge flow from the left to the right, we may write down the following expression (Zimbovskaya 2005):

$$T(E) = \frac{g(E)(1+\alpha^2)\left[g(E)(1+\alpha^2) + 1 - \alpha^2\right]}{\left[g(E)(1-\alpha^2) + 1 + \alpha^2\right]^2}, \tag{10.15}$$

where

$$g(E) = 2\sqrt{\frac{\Delta_L \Delta_R}{(E - E_0)^2 (\Delta_L + \Delta_R)^2}}. \tag{10.16}$$

Now, the electron transmission strongly depends on the dephasing strength ε. As shown in Figure 10.6, coherent transmission ($\varepsilon = 0$) exhibits a sharp peak at $E = E_0$ that gives a step-like shape to the volt–ampere curve, as was discussed in the previous section. In the presence of dephasing, the peak gets eroded. When the ε value approaches 1 the I–V curve becomes linear, corroborating the ohmic law for the inelastic transport.

Within Buttiker's model, ε is introduced as a phenomenological parameter whose relation to the microscopic characteristics of the dissipative processes affecting electron transport through molecular junctions remains uncertain. To further advance this model one should find out how to express ε in terms of the relevant microscopic characteristics for various transport mechanisms. This should open the way to a making of a link between the phenomenological Buttiker model and the NEGF. Such an attempt has been carried out in recent works (Zimbovskaya 2005, 2008) where the effect of stochastic nuclear motion on electron transport through molecules was analyzed.

10.4 Vibration-Induced Inelastic Effects

The interaction of electrons with molecular vibrations is known to be an important source of inelastic contribution to the electron transport through molecules. Theoretical studies of vibrationally inelastic electron transport through molecules and other similar nanosystems (e.g., carbon nanotubes) have been carried out over the past few years by a large number of researchers (Cornaglia et al. 2004, 2005, Donarini et al. 2006, Egger and Gogolin 2008, Galperin et al. 2007, Gutirrez et al. 2006, Kushmerick et al. 2004, Mii et al. 2003, Ryndyk and Cuniberti 2007, Siddiqui et al. 2007, Tikhodeev and Ueba 2004, Troisi and Ratner 2006, Zazunov and Martin 2007, Zazunov et al. 2006a,b, Zimmerman et al. 2008). Also, manifestations of the electron–vibron interactions were experimentally observed (Agrait et al. 2003, Djukic et al. 2005, Lorente et al. 2001, Qin et al. 2004, Repp et al. 2005a,b, Segal 2001, Smit et al. 2004, Tsutsui et al. 2006, Wang et al. 2004, Wu et al. 2004, Zhitenev et al. 2002). To analyze vibration induced effects on electron transport through molecular bridges, one must assume that molecular orbitals are coupled



FIGURE 10.6 Electron transmission (left panel) and current (right panel) computed within the Buttiker model at various values of the dephasing parameter ε, namely, $\varepsilon = 0$ (dotted lines), $\varepsilon = 0.5$ (dashed lines), and $\varepsilon = 1$ (solid lines). The curves are plotted assuming that the molecule is simulated by a single orbital with $E_0 = -0.5$ eV at $\Delta_L = \Delta_R = 0.1$ eV, $T = 30$ K.

to the phonons describing vibrations. While on the bridge, electrons may participate in the events generated by their interactions with vibrational phonons. These events involve a virtual phonon emission and absorption. For rather strong electron–phonon interaction this leads to the appearance of metastable electron levels that could participate in the electron transport through the junctions, bringing an inelastic component to the current. As a result, vibration induced features occur in the differential molecular conductance dI/dV and in the IETS d^2I/dV^2. This was observed in experiments (see e.g., Qin et al. 2004, Zhitenev et al. 2002). Sometimes, even current voltage curves themselves exhibit an extra step originating from the electron–vibron interactions (Djukic et al. 2005).

Particular manifestations of electron–vibron interaction effects in the transport characteristics are determined by the relation of three relevant energies. These are the coupling strengths of the molecule to the electrodes $\Delta_{L,R}$, the electron–phonon coupling strength λ, and the thermal energy kT (k is the Boltzmann constant). When the molecule is weakly coupled to the electrodes ($\Delta_{L,R} \ll \lambda, \hbar\Omega$) and the temperature is low ($kT \ll \Delta_{L,R}$), the electron transfer through the junction may give rise to a strong vibrational excitation, and one may expect a pronounced vibrational resonance structure to appear in the electron transmission. Correspondingly, extra steps should occur in the I–V curves. A proper theoretical consideration of the electron transport in this regime could be carried out within the approach proposed by Wingreen et al. (1989). Here, we employ a very simple semi-quantitative approximation that, nevertheless, allows the qualitative description of this structure including the effect of higher phonon harmonics on the transport characteristics.

We consider a junction including a single-site bridge that is coupled to a single vibrational mode with the frequency Ω. An electron on the bridge may virtually absorb several phonons, which results in the creation of a set of metastable states with the energies $E_n = \tilde{E}_0 + n\,\hbar\Omega$ ($n = 0, 1, 2, \ldots$). Here, the energy $\tilde{E}_0$ is shifted with respect to E_0 due to the electron–phonon interaction. The difference in these energies E_p is called a polaronic shift and could be estimated as $E_p = \lambda^2/\hbar\Omega$ (Gutirrez et al. 2006, Ryndyk and Cuniberti 2007, Wingreen et al. 1989). At a weak coupling of the bridge state to the electrodes, the lifetime of these metastable states is long enough for them to serve as channels for the electron transmission. Therefore, one may roughly approximate the transmission as a sum of contributions from all these channels. The terms in the sum have a form similar to the well-known expression for coherent transmission (see Equation 10.9). However, every term includes the factor $P(n)$ that corresponds to the probability of the appearance of the metastable state. So, we obtain

$$T(E) = 2\Delta_L\Delta_R \sum_n \frac{P(n)}{(E - \tilde{E}_0 - n\hbar\Omega)^2 + (\Delta_L + \Delta_R)^2}. \tag{10.17}$$

Here (Cizek et al. 2004):

$$P(n) = \frac{1}{n!}\left(\frac{\lambda^2}{2\hbar^2\Omega^2}\right)^n \exp\left(-\frac{\lambda^2}{2\hbar^2\Omega^2}\right). \tag{10.18}$$

The phonon-induced peaks in the transmission are displayed in Figure 10.7 along with the transmission peak for coherent transport through a single-site bridge. As expected, the coupling of the electronic degrees of freedom to the vibrational motion splits the single peak in the coherent transmission into a set of smaller peaks associated with vibrational levels. The peaks could be resolved when $\Delta_{L,R} \ll \hbar\Omega$. This agrees with the results of the earlier theoretical works (Wingreen et al. 1989), as well as with the experiments (Qin et al. 2004, Zhitenev et al. 2002). Phonon-induced peaks in the transmission give rise to the steps in the I–V curves and rather sharp features (peaks and dips) in the IETS. The latter are shown in Figure 10.8 (left panel) and they resemble those obtained using proper NEGF-based calculations (Galperin et al. 2004).



FIGURE 10.7 The electron transmission versus energy (left panel) and the conductance versus voltage (right panel) for a junction with the molecular bridge simulated by a single electronic state weakly coupled to the leads: $\Delta_L = \Delta_R = 0.01$ eV, $E_0 = 0.5$ eV. Solid lines are plotted assuming that the bridge is coupled to a single phonon mode ($\hbar\Omega = 0.22$ eV, $\lambda = 0.3$ eV). Dashed lines correspond to the coherent electron transport.



FIGURE 10.8 The inelastic electron tunneling spectrum plotted against the bias voltage at $\hbar\Omega = 0.22\,\text{eV}$, $\lambda = 0.3\,\text{eV}$. Left panel: $\Delta_L = \Delta_R = 0.01\,\text{eV}$, $E_0 = 0.5\,\text{eV}$. Right panel: $\Delta_L = \Delta_R = 0.5\,\text{eV}$, $E_0 = 0.5\,\text{eV}$ (solid line), $E_0 = -0.5\,\text{eV}$ (dashed line).

When the molecule is strongly coupled to the electrodes ($\Delta_{L,R} \gg \lambda$) and the temperature is still low ($kT \ll \lambda$, $\hbar\Omega$), electron–vibron interaction effects are less pronounced. Both the current and the conductance are weakly affected by the electron–phonon coupling (Galperin et al. 2007, Tikhodeev and Ueba 2004). However, the IETS features remain distinguishable. These features appear at the threshold $V = \hbar\Omega/|e|$ that corresponds to the opening of a channel for inelastic transport. To analyze IETS in the simplest way one may use the result for electron transmission derived within the Buttiker model where the dephasing parameter ε is expressed in terms of the relevant energies, namely,

$$\varepsilon = \frac{\Gamma_{ph}}{2(\Delta_L + \Delta_R) + \Gamma_{ph}}, \tag{10.19}$$

where $\Gamma_{ph} = 2\text{Im}(\Sigma_{ph})$, and Σ_{ph} is the self-energy term originating from the electron–phonon interaction. Based on the nonequilibrium Green's function formalism, the expression for Γ_{ph} was derived in the form (Mii et al. 2003)

$$\begin{aligned}\Gamma_{ph}(E) = 2\pi\lambda^2 \int d\omega\rho(\omega)\big\{N(\omega)[\rho_{el}(E-\hbar\omega)\\ +\rho_{el}(E+\hbar\omega)] + (1+N(\omega))\big(\big[1-n(E-\hbar\omega)\big]\rho_{el}(E-\hbar\omega)\\ +n(E+\hbar\omega)\rho_{el}(E+\hbar\omega)\big) + N(\omega)\big(\big[1-n(E+\hbar\omega)\big]\rho_{el}(E+\hbar\omega)\\ +n(E-\hbar\omega)\rho_{el}(E-\hbar\omega)\big)\big\}\ .\end{aligned} \tag{10.20}$$

Here, $\rho_{el}(E)$ and $\rho_{ph}(\omega)$ are the phonon and the electron densities of states, respectively; $N(\omega)$ is the Bose–Einstein distribution function at the temperature T, and

$$n(E) = \frac{1}{2}\big[f_L(E) + f_R(E)\big]. \tag{10.21}$$

While considering a junction with a single-site bridge state coupled to the single vibrational mode, we can write the following expressions for ρ_{ph} and ρ_{el}:

$$\rho_{ph}(\omega) = \frac{1}{\pi\hbar}\frac{\gamma}{(\omega-\Omega)^2+\gamma^2}, \tag{10.22}$$

$$\rho_{el}(E) = \frac{1}{\pi}\frac{\Delta_L + \Delta_R}{(E-E_0)^2 + (\Delta_L+\Delta_R)^2}, \tag{10.23}$$

where the polaron shift is neglected, and the parameter γ characterizes the broadening of the maximum in ρ_{ph} at $\omega = \Omega$ due to the interaction of the vibrionic mode with the environment. At low temperatures, we may significantly simplify the expression for Γ_{ph}. Within the conduction window $\mu_R < E < \mu_L$, we get

$$\begin{aligned}\Gamma_{ph}(E) \approx \pi\lambda^2 \left\{ \int_0^{(\mu_L - E)/\hbar} d\omega\rho_{ph}(\omega)\rho_{el}(E+\hbar\omega) \right.\\ \left. + \int_0^{(E-\mu_R)/\hbar} d\omega\rho_{ph}(\omega)\rho_{el}(E-\hbar\omega) \right\}.\end{aligned} \tag{10.24}$$

Omitting from consideration the coupling of the phonon mode to the environment ($\gamma \to 0$), we may easily carry out the integration over ω in Equation 10.24, and we arrive at the result

$$\begin{aligned}\Gamma_{ph}(E) \approx \pi\lambda^2\{\rho_{el}(E+\hbar\Omega)\theta(\mu_L - \hbar\Omega - E)\\ +\rho_{el}(E-\hbar\omega)\theta(E-\mu_R-\hbar\Omega)\},\end{aligned} \tag{10.25}$$

where $\theta(x)$ is the step function.

Substituting the approximation for Γ_{ph} given by Equations 10.24 and 10.25 into the expression (10.19) for the dephasing parameter $\int$ and employing the earlier result (10.15) for the electron transmission, we may calculate the transport characteristics. The adopted simplified approach, as well as the NEGF-based calculations, shows that the IETS signal appears at the threshold determined by the frequency of the vibrational mode (see Figure 10.8, right panel). At first glance, one may expect the net current through the junction to increase at the threshold. Indeed, the inelastic contribution to the current increases from zero to a certain nonzero value at this threshold for the channel for inelastic transport to open up. However, more thorough studies show that both elastic and nonelastic contributions to the net current undergo changes at the inelastic tunneling threshold, and the elastic current could decrease there, as was first shown by Persson and Baratoff (1987). Moreover, this decrease in the elastic current may overweigh the contribution coming from the inelastic channel. Depending on the relative value of the elastic and the inelastic contributions to the net current near threshold, the IETS reveals a peak or a dip at the corresponding voltage. Experiments corroborate the variety in the IETS taken for molecular junctions (Djukic et al. 2005, Hahn et al. 2000, Wang et al. 2004, Zhitenev et al. 2002). The shape of the signal is very sensitive to the characteristics of the junction, such as the position of the electronic state, the electron–phonon and the molecule-to-leads coupling strengths, and the vibron frequency. For instance, at a very strong coupling of the molecular bridge to the leads, it could so happen that the backscattering by the negatively biased electrode electrons whose energies belong to the conduction window between μ_L and μ_R, are locally depleted near the junction. In this situation, the opening of the inelastic channel may cause the increased reflection (otherwise forbidden by the Fermi exclusion) leading to the decrease in the conduction. Consequently, the described scenario should result in the dip in the IETS signal. Also, as concluded in the recent work of Ryndyk and Cuniberti (2007, the sideband phonon-induced features in the electron spectral density discussed above could give rise to the corresponding features in the differential conductance *dI*/*dV* and IETS assuming that the molecule coupling to the leads is not too strong. Contributions from these sideband features may be responsible for the shape of the IETS signal at the threshold of the inelastic tunneling channel. These contributions could produce an extra inelastic signal, as well. The latter appears as an additional peak or a dip in the differential conductance.

The question of the current decrease/increase at the phonon excitation threshold that corresponds to the peak/dip in the IETS is not completely answered so far, and the appropriate theory is being developed (Balseiro et al. 2006, Egger and Gogolin 2008). Nevertheless, it is presently understood that three relevant energies, namely, molecule–electrode couplings $\Delta_{L,R}$, electron–phonon coupling strength λ, and the phonon energy $\hbar\Omega$ play a very important part in determining the shape of the IETS signal. Varying these parameters one may convert the IETS signal from a peak to a dip and vice versa.

At finite temperatures, molecular vibrations always occur in the presence of stochastic nuclear motions. These motions could be described as a phonon thermal bath. Coupling of vibrational modes to this bath further affects the electron transport causing energy dissipation. The dissipative processes must be taken into account to properly analyze the effects of electron–phonon interactions in the electron transport. Also, the displacements of ions involved in the molecular vibrations are accompanied by the changes in the electrostatic field inside the molecule. This could give rise to polaronic effects in electron transport. We discuss these issues in the next sections.

10.5 Dissipative Transport

Electron transport through molecular junctions is always accompanied by stochastic nuclear/ion motions in the close environment. Interactions of traveling electrons with these environmental fluctuations cause energy dissipation. The importance of dissipative effects depends on several factors. Among these factors the temperature, the size, and the complexity of the molecular bridge predominate. The temperature determines the intensity of the nuclear motions, and the size of the molecule determines the so-called contact time, that is, the time for an electron to travel through the junction, and in consequence, to contact the environment. It was shown by Buttiker and Landauer (1985) that the contact time is proportional to the number of sites (subunits) in the molecule providing intermediate states for the electron tunneling. For small molecules at low temperatures, the contact time is shorter than the characteristic times for fluctuations in the environment, so, the effect of the latter on the electron transport is not very significant. One may expect a small broadening of the molecule energy states to occur that brings a moderate erosion of the peaks in the electron transmission and the steps in the *I*–*V* characteristics.

On the contrary, in large-sized molecules such as proteins and DNA, electron transport is accompanied by strong energy dissipation. The significance of the system-environment interactions in macromolecules was recognized long ago in studies of long-range electron-transfer reactions. In these reactions, electrons travel between distant sites on the molecule called a donor and an acceptor. It was established that when an electron initially localized on the donor site moves to the acceptor site with a lower energy, the energy difference must be dissipated to the environment to provide the irreversibility of the transfer (Garg et al. 1985).

A usual way to theoretically analyze dissipative effects in the electron transport through molecules is to introduce a phonon bath representing the random motions in the environment. In general, there is no one/several dominating modes in the bath. Instead, the bath is characterized by a continuous spectral function of all relevant phonon modes $\rho_{ph}(\omega)$. The electrons are supposed to be coupled to the phonon bath, and this coupling is specified by the spectral function. The particular form of $\rho_{ph}(\omega)$ may be found based on molecular dynamics simulations. However, to qualitatively study the effect of dissipation on electron transport one can employ the expression (Mahan 2000)

$$\rho_{ph}(\omega) = \lambda \frac{\omega}{\omega_c} \exp\left(-\frac{\omega}{\omega_c} \right), \tag{10.26}$$

where
the parameter λ characterizes the electron–phonon coupling strength
ω_c is the cutoff frequency for the bath related to its thermal relaxation time $\tau_c = \omega_c^{-1}$

To illustrate the possible effects of dissipation on the electron transport we return to our simple model where the molecular bridge is represented by a single state. Now, we assume that this state is coupled to the phonon bath. This model is hardly appropriate to properly analyze the dissipative effects in the electron transport through practical molecules for the molecule length is very important for the dissipative effects to be pronounced. Nevertheless, it still could serve to basically outline the main features of the dissipative electron transport through molecular junctions. Also, the proposed model could be useful to analyze electron transport in doped polyacetylene/polyaniline–polyethylene oxide nanofibers (Zimbovskaya 2008). These conducting polymers could be treated as some kind of granular metals where metallic-like regions (grains) are embedded in the poorly conducting medium of the disorderly arranged polymer chains (MacDiarmid 2001). While in the metallic state, the intergrain electron transport in these nanofibers is mostly provided by electron tunneling through the intermediate states on the polymer chains between the grains (Prigodin and Epstein 2002). In this case, the contact time could be long enough for the effects of dissipation to be well manifested that justifies the adoption of the above model.

Again, one may carry out transport calculations using Equation 10.15 for the electron transmission, and by expressing ε in terms of the relevant energies. Substituting Equation 10.26 in the expression (10.20), we may calculate $\Gamma_{ph}(E)$. The energy dissipation effects are more distinctly pronounced at moderately high temperatures, so we assume $kT \gg \hbar\omega_c$. Then the main contribution to the integral over ω in Equation 10.20 originates from the low frequency region $\omega \ll \omega_c$; and we obtain the following approximation:

$$\Gamma_{ph}(E) = \frac{8kT\lambda\Gamma}{(E - E_0)^2 + \Gamma^2}, \tag{10.27}$$

where $\Gamma = \Delta_L + \Delta_R + (1/2)\Gamma_{ph}(E)$. Solving the obtained equation for Γ_{ph} and using Equation 10.19, we obtain (Zimbovskaya 2008)

$$\varepsilon = \frac{1}{2} \frac{\rho^2 \left(1 + \sqrt{1 + \rho^2}\right)}{4\left(\dfrac{E - E_0}{\Delta_L + \Delta_R}\right)^2 + \dfrac{1}{2}\left(1 + \sqrt{1 + \rho^2}\right)^3}, \tag{10.28}$$

where $\rho^2 = 32kT\lambda/(\Delta_L + \Delta_R)^2$.

Voltage dependencies of the conductance computed based on Equations 10.3, 10.15, and 10.28 are presented in Figure 10.10 (left panel). One may see that at low values of the bias voltage, the electrons coupling to the phonon bath bring an enhancement in the conduction. The effect becomes reversed as the voltage grows above a certain value. This happens because the phonon-induced broadening of the molecular level (the bridge) assists the electron transport at a small bias voltage. When the voltage rises, this effect is surpassed by the scattering effect of phonons that resist electron transport. The significance of the electron–phonon interactions is determined by the ratio of the coupling constant λ and the self-energy terms describing the bridge coupling to the electrodes. The phonon bath makes a significant effect on the transport characteristics when $\lambda > \Delta_{L,R}$.

Dissipative electron transport through large DNA molecules was studied both theoretically and experimentally (Gutierrez et al. 2005, Xu et al. 2004). Theoretical studies were based on a model where the molecule was simulated by a tight-binding chain of sites linking the electrodes and the attached side chains. Electrons were allowed to travel along the bridge chain and to hop to the nearby side chains. These chains were coupled to the phonon bath providing the energy dissipation (see Figure 10.9). Although proposed for specific kinds of poly (*dG*)-poly (*dC*) molecules, this model seems to be quite generic and useful for a larger class of macromolecules.

Several coupling regimes to the bath may be analyzed. The most preferred regime for dissipative effects to appear is the strong-coupling limit defined by the condition $\lambda/\omega_c > 1$. Within this regime, the characteristic time for the electron bath interactions is much shorter than the typical electron time scales. Consequently, the bath makes a significant impact on the molecule electronic structure. New bath-induced states appear in the molecular spectrum inside the HOMO–LUMO gap. However, these states are strongly damped due to the dissipative action of the bath (Gutierrez et al. 2005). As a result, a small finite density of phonon-induced states appears inside the gap supporting electron transport at a low bias voltage. So again, the environment induces incoherent phonon-assisted transport through molecular bridges. For illustration, we show here the results of



FIGURE 10.9 Schematic drawing of a molecular junction where the molecular bridge is coupled to the phonon bath via side chains.



FIGURE 10.10 Left panel: The electron conductance versus voltage for a junction with a single electronic state bridge directly coupled to the phonon thermal bath. The curves are plotted assuming $E_0 = 0.4\,\text{eV}$, $\Delta_L = \Delta_R = 0.1\text{eV}$, $T = 30\,\text{K}$, $\lambda = 0.3\,\text{eV}$ (solid line), $\lambda = 0.05\,\text{eV}$ (dashed line). Right panel: Electron transmission through the junction in the case when the bridge state interacts with the phonon bath via the side chain coupled to the bridge state with the coupling parameter w. The curves are plotted assuming $\Delta_L = \Delta_R = \Delta$, $w/\Delta = 20$, $E_0 = 0$, $\lambda = 0.3\,\text{eV}$ (solid line), $\lambda = 0.05\,\text{eV}$ (dashed line).

calculations carried out for a toy model with a single-site bridge with a side chain attached to the latter. The side chain is supposed to be coupled to the phonon bath. The results for the electron transmission are displayed in Figure 10.10 (right panel). We see that the original bridge state at $E = 0$ is completely damped but two new phonon-induced states emerge nearby that could support electron transport.

An important characteristics of the dissipative electron transport through molecular junctions is the power loss in the junction, that is, the energy flux from the electronic into the phononic system. Assuming the current flow from the left to the right, this quantity may be estimated as the sum of the energy fluxes $Q_{L,R}$ at the left and the right terminals (leads):

$$P = Q_L + Q_R. \tag{10.29}$$

One may express the energy fluxes in terms of renormalized currents at the electrodes $\tilde{I}_{L,R}(E)$ that are defined as follows (Datta 2005):

$$I_{L,R} = \frac{e}{\pi\hbar}\int \tilde{I}_{L,R}(E)dE. \tag{10.30}$$

Then $Q_{L,R}$ may be presented in the form

$$Q_{L,R} = \frac{1}{\pi\hbar}\int E\tilde{I}_{L,R}(E)dE. \tag{10.31}$$

We remark that the current $I_{L,R}$ in Equation 10.30 are related to the corresponding leads, and their signs are accordingly defined. An outgoing current is supposed to be positive whereas an incoming one is negative for each lead. To provide an electric charge conservation in the junction one must require that $I = I_L = -I_R$ for the chosen direction of the current flow. Therefore, the energy fluxes also have different signs. As for the $Q_{L,R}$ magnitudes, they may differ only if the renormalized currents $\tilde{I}_L(E)$ and $\tilde{I}_R(E)$ are distributed over energies in different ways. This cannot happen in the case of elastic transport, for in this case, $\tilde{I}_L(E) = -\tilde{I}_R(E)$. However, if the transport process is accompanied with the energy dissipation, the energy distributions for $\tilde{I}_L$ and $\tilde{I}_R$ may differ. In this case, electrons lose some energy while moving through the junction and this gives rise to the differences in the renormalized currents' energy distributions. For instance, in the case when the electrodes are linked with a single-state bridge, the energy distribution of $\tilde{I}_L(E)$ has a single maximum whose position is determined by the site energy E_0 and the applied bias voltage V. Assuming that the average energy loss due to dissipation could be estimated as ΔE, the maximum in the $\tilde{I}_R(E)$ distribution is shifted by this quantity, so the current $\tilde{I}_R(E)$ flows at lower energies compared to $\tilde{I}_L(E)$. This results in the power loss and the Joule heating in the junction (Segal et al. 2003).

10.6 Polaron Effects: Hysteresis, Switching, and Negative Differential Resistance

While studying electron transport through molecular junctions, hysteresis in the current–voltage characteristics was reported in some systems (Li et al. 2003). Multistability and stochastic switching were reported in single-molecule junctions (Lortscher et al. 2007) and in single metal atoms coupled to a metallic substrate through a thin ionic insulating film (Olsson et al. 2007, Repp et al. 2004).

The coupling of an electron belonging to a certain atomic energy level to the displacements of ions in the film brings a possibility of polaron formation in there. This leads to the polaron shift in the electron energy. It was noticed that multistability and hysteresis in molecular junctions mostly occurred when the molecular bridges included centers of long-living charged electronic states (redox centers). On these grounds, it was suggested that hysteresis in the I–V curves observed in molecular junctions appear due to the formation of polarons on the molecules (Galperin et al. 2005).

The presence of the polaron shift in the energy of a charged (occupied) electron state creates a difference between the latter and the energy of the same state while it remains unoccupied. Assuming, for simplicity, a single-state model for the molecular bridge coupled to a single optical phonon mode, we may write the following expression for the renormalized energy:

$$\tilde{E}_0(n_0) = E_0 - \frac{\lambda^2 n_0}{\hbar\Omega}, \tag{10.32}$$

where the electronic population on the bridge n_0 is given by

$$n_0 = \frac{1}{\pi}\int dE \frac{f_L(E)\Delta_L + f_R(E)\Delta_R}{\left[E - \tilde{E}_0(n_0)\right]^2 + \left(\Delta_L + \Delta_R\right)^2}. \tag{10.33}$$

So, as follows from Equation 10.32, the polaron shift depends on the bridge occupation n_0, and the latter is related to $\tilde{E}_0$ by Equation 10.33. Therefore, the derivation of an explicit expression for $\tilde{E}_0(n_0)$ is a nontrivial task even within the chosen simple model. Nevertheless, it could be shown that two local minima emerge in the dependence of the potential energy of the molecular junction including two electrodes linked by the molecular bridge, of the occupation number n_0. These minima are located near $n_0 = 0$ and 1, and they correspond to the neutral (unoccupied) and charged (occupied) states, respectively. This is illustrated in Figure 10.11 (left panel). These states are metastable, and their lifetime could be limited by the quantum switching (Mitra et al. 2005, Mozyrsky et al. 2006). When the switching time between the two states is longer than the characteristic time for the external voltage sweeping, one may expect the hysteresis to appear, for the states of interest live long enough to maintain it. Within the opposite limit, the average washes out the hysteresis. When the states are especially short-lived this could even result in a telegraph noise at a finite bias voltage that replaces the controlled switching.

Further, we consider long-lived metastable states and we concentrate on the I–V behavior. Let us for certainty assume that the bridge state at zero bias voltage is situated above the Fermi energy of the system and remains empty. As the voltage increases, one of the electrode's chemical potentials crosses the bridge level position, and the current starts to flow through the system. The I–V curve reveals a step at the bias voltage value corresponding to the crossing of the unoccupied bridge level with the energy E_0 by the chemical potential. However, while the current flows through the bridge, the level becomes occupied and, consequently, shifted due to the polaron formation. When the bias voltage is reversed, the current continues to flow through the shifted bridge state of the energy $\tilde{E}_0$, until the recrossing happens. Due to the difference in the energies of the neutral and the charged states, the step in the I–V curves appears at different values of the voltage, and this is the reason for the hysteresis loop to appear as shown on the right panel of Figure 10.11. One could also trace the hysteresis in the I–V characteristics starting from the filled (and shifted) bridge state.

Again, the hysteresis loop in the I–V curves may occur when both occupied and unoccupied states are rather stable, which means that the potential barrier separating the corresponding minima in the potential energy profile is high enough, so that quantum switching between the states is unlikely. This happens when the bridge is weakly coupled to the electrodes ($\Delta_{L,R} \ll \lambda^2/\hbar\Omega$), which is an obvious requirement for the involved states (neutral or charged) to the distinguishable. In other words, the broadening of the relevant levels due to the coupling to the electrodes must be much smaller that the polaron shift. As was recently shown (Ryndyk et al. 2008), the stronger the electron–phonon coupling, the less becomes the probability of the switching. At large values of λ, the tunneling between the charged and



FIGURE 10.11 Left panel: Schematic of the potential energy of the molecular junction versus the occupation number n_0. Right panel: Hysteresis in the current–voltage characteristics. The solid line corresponds to the transport via the unoccupied bridge electronic state, and the dashed line corresponds to the transport via the occupied state shifted due to the polaron formation.

the neutral states is exponentially suppressed. Also, it was shown that the symmetry/asymmetry in the coupling to the electrodes could significantly affect the hysteresis behavior (D'Amico et al. 2008, Ryndyk et al. 2008). For asymmetric junctions ($\Delta_L \neq \Delta_R$), two nearly stable states exist at the zero bias voltage. When the asymmetry is very strong, both states could appear stable at one bias voltage polarity and unstable when the polarity is reversed. It was suggested that under an appropriate choice of parameters, one may create a situation where the instability regions for the involved states do not overlap. These properties give grounds to conjecture that such strongly asymmetric junctions could reveal memory functionalities, that make them potentially useful in the fabrication of nanodevices.

Among the various potentially important properties of the electron transport through metal–molecule junctions, one may separate the negative differential resistance (NDR), that is, the decrease in the current I while the bias voltage across the molecule increases. The NDR effect was originally observed in tunneling semiconducting diodes (Kastner 1992). Later, it was viewed in quantum dots (Grobis et al. 2005, Repp et al. 2005a,b). Several possible scenarios were proposed to explain the NDR occurrence in electron transport through molecules. The effect could originate from the alignment and the subsequent disalignment of the Fermi levels of the electrodes with the molecular orbitals that happens as the bias voltage varies (Xue et al. 1999). Also, the NDR could appear as a Coulomb blockade-induced effect (Simonian et al. 2007) and/or due to some other reasons (Zimbovskaya and Pederson 2008). It is likely that different mechanisms could play a major part in the NDR appearance in different molecular junctions where it was observed so far.

Here, we discuss the NDR features in the current–voltage characteristics that originate from the electron coupling with the molecular vibrational modes. As was shown (Galperin et al. 2005, Yeganeh et al. 2007a,b), the polaron formation could give rise to the NDR. This may happen if the polaron shift in the energy of the occupied state moves the energy level away from the conduction window. As the shift depends on the electronic population, and the latter changes as the bias voltage increases, the occupied state falls out from the window between the chemical potentials of the electrodes at a certain value of the voltage. If the transport is being conducted via this occupied state, then it stops when this voltage value is reached. Correspondingly, the current value drops to zero revealing a distinctive NDR feature. This is a realistic scenario based on the main features of the electron transport through molecules under polaron formation.

In conclusion, electron–vibrion coupling could lead to the formation of a polaron that results in the energy differences between the occupied and the unoccupied states on the molecular bridge. At a weak interaction between the bridge and the electrodes and the strong electron–phonon coupling these charged and neutral states are metastable and could serve for electron conduction. This results in such interesting and potentially useful effects as the hysteresis and the NDR features in the current–voltage characteristics.

10.7 Molecular Junction Conductance and Long-Range Electron-Transfer Reactions

Long-range electron-transfer reactions play an important part in many biological processes such as photosynthesis and enzyme catalyses (Kuznetsov and Ulstrup 1999). Theoretical and experimental studies of these processes have lasted for more than four decades but they still remain within a very active research area. In the intramolecular electron-transfer reactions, the electric charge moves from one section of the molecule to another section of the same molecule. Long-range transfer typically occurs in large molecules such as proteins and/or DNA, so that these two sections are situated far apart from each other. A common setup for the transfer reactions includes a donor, a bridge, and an acceptor. Due to the large distances between the donor (where an electron leaves) and the acceptor (where it arrives) typical for the long-range transfer reactions, a direct coupling between the two is negligible. Therefore, the electron participating in the transfer needs a molecular bridge providing a set of intermediate states for electron transport.

Essentially, intramolecular electron transfer is a combination of nuclear environment fluctuations and electron tunneling. Electron-transfer reactions result from the response of a molecule to environmental polarization fluctuations that accompany nuclear fluctuations. The molecule responds by redistribution of the electronic density thus establishing opportunities for the charge transfer to occur. The main characteristic of the electron-transfer processes is the transfer rate K_{et} that is the inversed time of the reaction. The transfer rate for the electron tunneling in the molecule interior from the donor to the acceptor depends both on the electronic transmission amplitudes and the vibrionic coupling. The latter provides the energy exchange between the electronic and the nuclear systems.

Viewing fast electronic motions in the background of the slowly moving nuclei (nonadiabatic electron transfer) and applying the Fermi golden rule of perturbation theory, it was shown that K_{et} could be written in the form first suggested by Marcus (1965)

$$K_{et} = \frac{2\pi}{\hbar}\left|H_{\text{DA}}\right|^2 (FC). \tag{10.34}$$

Here, the first cofactor is the electron transmission coefficient, H_{DA}, which is the effective matrix element between the donor and the acceptor. The second term is the density of states weighted Franck–Condon factor that describes the effect of nuclear motions in the environment.

There exists a noticeable resemblance between the long-range electron transfer and the molecular conductance, and this resemblance was analyzed in several theoretical works (Dahnovsky 2006, Mujica et al. 1994, Nitzan 2001, Yeganeh et al. 2007a,b, Zimbovskaya 2003, Zimbovskaya and Gumbs 2002). The fundamental part in both molecular conduction and electron-transfer reactions is taken by the electron tunneling inside the molecule via the set of intermediate states. In large molecules, the electron involved in the transfer reaction or contributing to the conductance, with a high probability follows a few pathways that work as molecular bridges. The rest of the molecules do not significantly participate in the transfer/conduction and may be omitted from consideration in calculations of electron transmission (Jones et al. 2002; Beratan et al. 1992). On these grounds, it was suggested that the original molecule could be reduced to a simpler chain-like structure, and the latter may replace the former in calculations of molecular conductance and/or transfer rates (Daizadeh et al. 1997). Such simplification significantly eases computations of the molecular conductance and the electron-transfer rates in macromolecules.

The resemblance between the molecular conductance and the long-range electron transfer does not mean that these processes are nearly identical. Along with the similarities there are substantial differences between the former and the latter. For instance, the continuum of states causing the charge transport arises from the multitude of electronic states on the electrodes in the case of molecular conduction, and from the vibrations and fluctuations in the environment in the case of electron-transfer reactions. Also, the driving force that puts electrons in motion originates from the external bias voltage applied across the junction in the case of molecular conduction. In the electron-transfer situation, this force appears due to the electron–vibrionic interactions in the system, or the electron-transfer reaction starts as a result of a photoexcitation of the donor part of the molecule. The observables, namely, the molecular conductance g and/or current I, and the transfer rate K_{et} differ as well.

Notwithstanding these differences, the electron transport through molecular junctions and the electron transfer could be theoretically analyzed using the common formalism as recently proposed by Yeganeh et al. (2007b). Further, we follow their approach. The starting point is that one may simulate the donor–bridge–acceptor system as some kind of molecular junction, shown in Figure 10.12. Here, we represent the donor as a single state $|i\rangle$, and this state mimics the left lead (assuming the transport is from the left to the right). The donor is coupled to the bridge and the latter is coupled to the continuum of the final states $|f\rangle$ simulating the right lead. These couplings are described by the self-energy terms $\Delta_{i,f}$. For simplicity, we assume that there exists a single state on the bridge, and this state is coupled to a vibrionic mode of the frequency Ω. The latter mimics environment fluctuations. We assume that the "leads" are weakly coupled to the bridge ($\Delta_{L,R} \ll \lambda$), which is typical for electron-transfer situations. Also, the representation of the environment motions by the single vibrionic mode is justified only at low temperatures when the thermal energy kT is much smaller than the electron–vibrion coupling parameter λ.



FIGURE 10.12 Schematic of the model system used in the transfer rate calculations. The initial/final reservoirs correspond to the left/right leads in the molecular junction.

Now, we can write the Landauer expression for the current flowing through the "junction" using Equations 10.3 and 10.4. Assuming that the bridge includes only one state, we simplify Equation 10.4:

$$T(E) = 2T_r\left\{\Delta_i G \Delta_f G^\dagger\right\} = -2\frac{\Delta_i \Delta_f}{\Delta_i + \Delta_f}\mathrm{Im}(G). \tag{10.35}$$

Here, the subscripts i/f label the initial and the final states. Within the Fermi golden rule regime that allows the introduction of the transfer rate, the bridge must be coupled to the final states much more strongly than to the initial state ($\Delta_f \gg \Delta_i$). Therefore

$$\frac{\Delta_i \Delta_f}{\Delta_i + \Delta_f} \approx \Delta_i \tag{10.36}$$

and the coupling to the final states falls out of the expressions for electron transmission and current. Within the chosen model, this is a physically reasonable result for the final states reservoir (the right "electrode" in our junction) was merely introduced to impose a continuum of states maintaining the transfer process at a steady-state rate. Also, considering the current flow, we may suppose that the initial state is always filled [$f_i(E) = 1$], and the final states are empty [$f_f(E) = 0$]. Therefore, the current flow through the "junction" accepts the form

$$I = \frac{2e}{\pi\hbar}\int dE \Delta_i \,\mathrm{Im}(G). \tag{10.37}$$

Both the current and the transfer rate are fluxes closely related to each other, namely,

$K_{et} = I/e$. So, we may write

$$K_{et} = -\frac{2}{\pi\hbar}\int dE \Delta_i \,\mathrm{Im}(G). \tag{10.38}$$

Now, Δ_i could be computed using the expression (10.7) for the corresponding self-energy term. Keeping in mind that the "left electrode" includes a single state with the certain energy $\int_i$ we obtain

$$\Delta_i = \mathrm{Im}\left(\frac{|\tau_i|^2}{E - \varepsilon_i + is}\right) = \pi|\tau_i|^2\,\delta(E - \varepsilon_i). \tag{10.39}$$

Accordingly, the expression (10.38) for the transfer rate may be reduced to the form:

$$K_{et} = -\frac{2}{\hbar}|\tau_i|^2\,\mathrm{Im}\left[G(\varepsilon_i)\right], \tag{10.40}$$

where τ_i represents the coupling between the donor and the molecule bridge. It must be stressed that within the chosen model, τ_i is the only term representing the relevant state coupling that may be identified with the electronic transmission coefficient H_{DA} in the general expression (10.34) for K_{et}. This leaves us with the following expression for the Franck–Condon factor:

$$(FC) = -\frac{1}{\pi}\text{Im}\left[G(\varepsilon_i)\right]. \tag{10.41}$$

As discussed in Section 10.4, at a weak coupling of the bridge to the leads the electron–vibrionic interaction opens the set of metastable channels for the electron transport at the energies $E_n = \tilde{E}_0 + n\hbar\Omega$ ($n = 0, 1, 2\ldots$) where $\tilde{E}_0$ is the energy of the bridge state with the polaronic shift included. Green's function may be approximated as a weighted sum of contributions from these channels:

$$G(\varepsilon_i) = \sum_{n=0}^{\infty} P(n)\left[\varepsilon_i - \tilde{E}_0 - n\hbar\Omega + is\right]^{-1}, \tag{10.42}$$

where $s \to 0^+$, and the coefficients $P(n)$ are probabilities for the channels to appear given by Equation 10.18.

Substituting Equation 10.42 into Equation 10.41 we get

$$(FC) = \sum_{n=0}^{\infty} P(n)\delta(\Delta F - n\hbar\Omega). \tag{10.43}$$

Here, $\Delta F = \int_i - \tilde{E}_0 \equiv \int_i - E_0 + \lambda^2/(\hbar\Omega)$ is the exoergicity of the transfer reaction, that is, the free energy change originating from the nuclear displacements accompanied by polarization fluctuations. The effect of the latter is inserted via the reorganization term $\lambda^2/(\hbar\Omega)$ related to polaron formation. The exoergicity in the transfer reaction takes on a part similar to that of the bias voltage in the electron transport through molecular junctions. It gives rise to the electron motion through the molecules. In the particular case when the voltage drops between the initial state (left electrode) and the molecular bridge these two quantities are directly related by $|e|V = \Delta F$.

Usually, the long-range electron transfer is observed at moderately high (room) temperatures, so the low temperature approximation (10.43) for the Franck–Condon factor cannot be employed. However, the expression (10.41) remains valid at finite temperatures, only the expression for Green's function must be modified to include the thermal effects. It is shown (Yeganeh et al. 2007a,b) that within the high-temperature limit ($kT > \hbar\Omega$) the expression for the (FC) may be converted to the well-known form first proposed by Marcus:

$$(FC) = \frac{1}{\sqrt{4\pi E_p kT}}\exp\left[-\frac{(\Delta F - E)_p^2}{4E_p kT}\right], \tag{10.44}$$

where $E_p = \lambda^2/(\hbar\Omega)$ is the reorganization energy.

While studying the electron-transfer reactions in practical macromolecules, one keeps in mind that both the donor and the acceptor subsystems in the standard donor–bridge–acceptor triad are usually complex structures including multiple sites coupled to the bridge. Correspondingly, the bridge has a set of entrances and a set of exits that an electron can employ. At different values of the tunnel energy different sites of the donor and/or acceptor subsystems can give predominant contributions to the transfer. Consequently, an electron involved in the transfer arrives at the bridge and leaves from it via different entrances/exits, and it follows different pathways while on the bridge.

Also, nuclear vibrations in the environment could strongly affect the electron transmission destroying the pathways and providing a transition to a completely incoherent sequential hopping mechanism of the electron transfer. All this means that a proper computation of the electron transmission factor H_{DA} for practical macromolecules is a very complicated and nontrivial task. The strong resemblance between the electron-transfer reactions and the electron transport through molecules gives grounds to believe that studies of molecular conduction can provide important information concerning the quantum dynamics of electrons participating in the transfer reactions. One may expect that some intrinsic characteristics of the intramolecular electron transfer, such as the pathways of the tunneling electrons and the distinctive features of the donor/acceptor coupling to the bridge could be obtained in experiments on the electron transport through molecules. For instance, it was recently suggested to characterize electron pathways in molecules using the inelastic electron tunneling spectroscopy, and other advances in this area are to be expected.

10.8 Concluding Remarks

Presently, the electron transport through molecular-scale systems is being intensively studied both theoretically and experimentally. Largely, unceasing efforts of the research community to further advance these studies are motivated by important application potentials of single molecules as active elements of various nanodevices intended to compliment current silicon-based electronics. An elucidation of the physics underlying electron transport through molecules is necessary in designing and operating molecular-based nanodevices. Elastic mechanisms for the electron transport through metal–molecule–metal junctions are currently understood and described fairly well. However, while moving through the molecular bridge, an electron is usually affected by the environment, and it results in a change of its energy. So, inelastic effects appear, and they may bring noticeable changes in the electron transport characteristics. Here, we concentrated on the inelastic and the dissipative effects originating from the molecular bridge vibrations and thermally activated stochastic fluctuations. For simplicity and also to keep this chapter within a reasonable length, we avoided a detailed description of computational formalisms commonly used to theoretically analyze electron transport through molecular junctions. These formalisms are described elsewhere. We mostly focus on the physics of the inelastic effects in the electron transport. Therefore, we employ very simple models and techniques.

We remark that along with nonelasticity originating from electron–vibron interactions, which is the subject of the present review, there exist inelastic effects of different kinds. For instance, inelastic effects arise due to electron–photon interactions. Photoassisted transport through molecular junctions was demonstrated and theoretically addressed using several techniques. It is known that optical pumping could give rise to the charge flow in an unbiased metal–molecule–metal junction, and light emission in biased current-carrying junctions could occur. Also, there is the issue of molecular geometry. There are grounds to conjecture that in some cases the geometry of a molecule included in the junction may change as the current flows through the latter for bonds can break with enough amount of current. Obviously, this should bring a strong inelastic component to the transport, consequently affecting observables.

It is common knowledge that electron–electron interactions may significantly influence molecular conductance leading to a Coulomb blockade and a Kondo effect. To properly treat electron transport through molecular junctions one must take these interactions into consideration. Corresponding studies were carried out omitting electron–phonon interactions. However, a full treatment of the problem including both electron–electron and electron–phonon interactions has not been completed so far. There exist other theoretical challenges, such as the effect of bipolaron formation that originates from an effective electron–electron attraction via phonons.

Finally, practical molecular junctions are complex systems, and a significant effort is necessary to bring electron transport calculations to a result that could be successfully compared with the experimental data. For this purpose, one needs to compute molecular orbitals and the voltage distribution inside the junctions to get sufficient information on the vibronic spectrum of the molecule, the electron–phonon coupling strengths, and electron–electron interactions. One needs a good quantitative computational scheme for transport calculations where all this information can be accounted for. Currently, there remain some challenges that have not been properly addressed by theory. Therefore, a comparison between the theoretical and the experimental results on the molecular conductance sometimes does not bring satisfactory results. However, there are firm grounds to believe that further efforts of the research community will result in a detailed understanding of all the important aspects of molecular conductance including inelastic and dissipative effects. Such an understanding is paramount to the conversion of molecular electronics into a viable technology.

References

Agrait, N.; Yeati, A. L., and van Ruitenbeek, L. M. 2003. Quantum properties of atomic-sized conductors. *Phys. Rep.* **377**: 81–279.

Aviram, A.; Ratner, M. A., and Mujica, V. (Eds). 2002. *Molecular Electronics II*. New York: Annals of the New York Academy of Sciences.

Balseiro, C.A.; Cornaglia, P. S., and Grempel, D. R. 2006. Electron–phonon correlation effects in molecular transistors. *Phys. Rev. B* **74**: 235409.

Beratan, D. N.; Onuchic, J. N.; Winkler, J. R. et al. 1992. Electron-tunneling pathways in proteins. *Science* **258**: 1740–1741.

Buttiker, M. 1986. Role of quantum coherence in series resistors. *Phys. Rev. B* **33**: 3020–3026.

Buttiker, M. and Landauer, R. 1985. Traversal time for tunneling. *Phys. Scri.* **32**: 429–434.

Cizek, M.; Thoss, M., and Domcke, W. 2004. Theory of vibrationally inelastic electron transport through molecular bridges. *Phys. Rev. B* **70**: 125406.

Cornaglia, P. S.; Ness, H., and Grempel, D. R. 2004. Many-body effects on the transport properties of single-molecule devices. *Phys. Rev. Lett.* **93**: 147201.

Cornaglia, P. S.; Grempel, D. R., and Ness, H. 2005. Quantum transport through a deformable molecular transistor. *Phys. Rev. B* **71**: 075320.

Cuniberti, G.; Fagas, G., and Richter, K. (Eds). 2005. *Introductory Molecular Electronics: A Brief Overview*, Lecture Notes in Physics, Volume **680**. Berlin, Germany: Springer.

Dahnovsky, Yu. 2006. Modulating electron dynamics: Modified spin-boson approach. *Phys. Rev. B* **73**: 144303.

Daizadeh, I.; Gehlen, J. N., and Stuchebrukhov, A. A. 1997. Calculation of electronic tunneling matrix element in proteins: Comparison of exact and approximate one-electron methods for Ru-modified azurin. *J. Chem. Phys.* **106**: 5658–5666.

D'Amato, J. L. and Pastawski, H. M. 1990. Conductance of a disordered linear chain including inelastic scattering events. *Phys. Rev. B* **41**: 7411–7420.

D'Amico, P.; Ryndyk, D. A.; Cuniberti, G. et al. 2008. Charge-memory effect in a polaron model: Equation-of-motion method for Green functions. *New J. Phys.* **10**: 085002.

Damle, P. S.; Ghosh, A. W., and Datta, S. 2001. Unified description of molecular conduction: From molecules to metallic wires. *Phys. Rev. B* **64**: 201403.

Datta, S. 1997. *Electron Transport in Mesoscopic Systems*. Cambridge, U. K.: Cambridge University Press.

Datta, S. 2005. *Quantum Transport: Atom to Transistor*. Cambridge, U. K.: Cambridge University Press.

Di Ventra, M.; Pantelides, S. T., and Lang, N. D. 2000. First-principles calculations of transport properties of a molecular device. *Phys. Rev. Lett.* **84**: 979–982.

Djukic, D.; Thygesen, K. S.; Untiedt, C. et al. 2005. Stretching dependence of the vibration modes of a single-molecule Pt–H_2–Pt bridge. *Phys. Rev. B* **71**: 161402(R).

Donarini, A.; Grifoni, M., and Richter, K. 2006. Dynamical symmetry breaking in transport through molecules. *Phys. Rev. Lett.* **97**: 166801.

Egger, R. and Gogolin, A. O. 2008. Vibration-induced correction to the current through a single molecule. *Phys. Rev. B* **77**: 1098.

Galperin, M.; Ratner, M. A., and Nitzan, A. 2004. Inelastic electron tunneling spectroscopy in molecular junctions: Peaks and dips. *J. Chem. Phys.* **121**: 11965–11979.

Galperin, M.; Ratner, M. A., and Nitzan, A. 2005. Hysteresis, switching, and negative differential resistance in molecular junctions: A polaron model. *Nano Lett.* **5**: 125–130.

Galperin, M.; Nitzan, A., and Ratner, M. A. 2006. Molecular transport junction: Current from electronic excitations in the leads. *Phys. Rev. Lett.* **96**: 166803.

Galperin, M.; Ratner, M. A., and Nitzan, A. 2007. Topical review: Molecular transport junctions: Vibrational effects. *J. Phys. Condens. Matter* **19**: 103201.

Garg, A.; Onuchic, J. N., and Ambegaokar, V. 1985. Effect of friction on electron transfer in biomolecules. *J. Chem. Phys.* **83**: 4491–4503.

Grobis, M.; Wachowiak, A.; Yamachika, M. F. et al. 2005. Tuning negative differential resistance in a molecular film. *Appl. Phys. Lett.* **86**: 204102.

Gutierrez, R.; Mandal, S., and Cuniberti, G. 2005. Dissipative effects in the electronic transport through DNA molecular wires. *Phys. Rev. B* **71**: 235116.

Gutirrez, R.; Mohapatra, S.; Cohen, H. et al. 2006. Inelastic quantum transport in a ladder model: Implications for DNA conduction and comparison to experiments on suspended DNA oligomers. *Phys. Rev. B* **74**: 235105.

Hahn, J. R.; Lee, H. J., and Ho, W. 2000. Electronic resonance and symmetry in single-molecule inelastic electron tunneling. *Phys. Rev. Lett.* **85**: 1914–1917.

Ho, J. W. 2002. Single molecule chemistry. *J. Chem. Phys.* **117**: 11033–11061.

Imry, Y. and Landauer, R. 1999. Conductance viewed as transmission. *Rev. Mod. Phys.* **71**: S306–S312.

Jones, M. L.; Kurnikov I. V., and Beratan, D. N. 2002. The nature of tunneling pathway and average packing density model for protein-mediated electron transfer. *J. Phys. Chem. A* **106**: 200206.

Kastner, M. A. 1992. The single-electron transistor. *Rev. Mod. Phys.* **64**: 849–858.

Komeda, T.; Kim, Y.; Kawai, M. et al. 2002. Lateral hopping of molecules induced by excitation of internal vibration mode. *Science* **295**: 2055–2058.

Kubatkin, S.; Danilov, A.; Hjort, M. et al. 2003. Single-electron transistor of a single organic molecule with access to several redox states. *Nature* **425**: 698–701.

Kushmerick, J. G.; Lazorcik, J.; Patterson, C. H. et al. 2004. Vibronic contributions to charge transport across molecular junctions. *Nano Lett.* **4**: 63942.

Kuznetsov, A. M. and Ulstrup, I. 1999. *Electron Transfer in Physics and Biology*. Chichester, U. K.: John Wiley.

Landauer, R. 1970. Electrical resistance of disordered one-dimensional lattices. *Philos. Mag.* **21**: 863–867.

Lang, N. D. and Avouris, Ph. 2000a. Carbon-atom wires: Charge-transfer doping, voltage drop and the effect of distortions. *Phys. Rev. Lett.* **84**: 358–361.

Lang, N. D. and Avouris, Ph. 2000b. Electrical conductance of parallel atomic wires. *Phys. Rev. B* **62**: 7325–7329.

Li, X.-Q. and Yan, Y.-J. 2001a. Electrical transport through individual DNA molecules. *Appl. Phys. Lett.* **79**: 2190–2192.

Li, X.-Q. and Yan, Y.-J. 2001b. Scattering matrix approach to electronic dephasing in longrange electron transfer. *J. Chem. Phys.* **115**: 4169–4174.

Li, C.; Zhang, D.; Liu, X. et al. 2003. In_2O_3 nanowires as chemical sensors. *Appl. Phys. Lett.* **82**: 1613.

Lorente, N.; Persson, M.; Lauhon, L. J. et al. 2001. Symmetry selection rules for vibrationally inelastic tunneling. *Phys. Rev. Lett.* **86**: 2593–2596.

Lortscher, E.; Weber, H. B., and Riel, H. 2007. Statistical approach to investigating transport through single molecules. *Phys. Rev. Lett.* **98**: 176807.

MacDiarmid, A. G. 2001. Nobel lecture: "Synthetic metals": A novel role for organic polymers. *Rev. Mod. Phys.* **73**: 701–712.

Mahan, G. D. 2000. *Many-Particle Physics*. New York: Plenum.

Marcus, R. A. 1965. On the theory of electron-transfer reactions. VI. Unified treatment for homogeneous and electrode reactions. *J. Chem. Phys.* **43**: 679–701.

Mii, T.; Tikhodeev, S. G., and Ueba, H. 2003. Spectral features of inelastic electron transport via a localized state. *Phys. Rev. B* **68**: 205406.

Mitra, A.; Aleiner I., and Millis, A. J. 2004. Phonon effects in molecular transistors: Quantal and classical treatment. *Phys. Rev. B* **69**: 245302.

Mitra, A.; Aleiner I., and Millis, A. J. 2005. Semiclassical analysis of the nonequilibrium local polaron. *Phys. Rev. Lett.* **94**: 076404.

Mozyrsky, D.; Hastings, M. B., and Martin, I. 2006. Intermittent polaron dynamics: Born–Oppenheimer approximation out of equilibrium. *Phys. Rev. B* **73**: 035104.

Mujica, V.; Kemp, M., and Ratner, M. A. 1994. Electron conduction in molecular wires. I. A scattering formalism. *J. Chem. Phys.* **101**: 6849–6855.

Mujica, V.; Roitberg, A. E., and Ratner, M. A. 2000. Molecular wire conductance: Electrostatic potential spatial profile. *J. Chem. Phys.* **112**: 6834–6839.

Nitzan, A. 2001. Electron transmission through molecules and molecular interfaces. *Ann. Rev. Phys. Chem.* **52**: 681–750.

Olsson, F. E.; Paavilainen, S.; Persson, M. et al. 2007. Multiple charge states of Ag atoms on ultrathin NaCl films. *Phys. Rev. Lett.* **17**: 176803.

Park, H.; Park, J.; Lim, A. K. L. et al. 2000. Nanomechanical oscillations in a single-C_{60} transistor. *Nature* **407**: 57–60.

Persson, B. N. J. and Baratoff, A. 1987. Inelastic electron tunneling from a metal tip: The contribution from resonant processes. *Phys. Rev. Lett.* **59**: 339–342.

Prigodin, V. N. and Epstein, A. J. 2002. Nature of insulator–metal transition and novel mechanism of charge transport in highly doped electronic polymers. *Synth. Met.* **125**: 43–53.

Poot, M.; Osorio, E.; O'Neil, K. et al. 2006. Temperature dependence of three-terminal molecular junctions with sulfur end-functionalized tercyclohexylidenes. *Nano Lett.* **6**: 1031–1035.

Qin, X. H.; Nazin G. V., and Ho, W. 2004. Vibronic states in single molecule electron transport. *Phys. Rev. Lett.* **92**: 206102.

Reichert, J.; Ochs, R.; Beckmann, D. et al. 2002. Driving current through single organic molecules. *Phys. Rev. Lett.* **88**: 176804.

Repp, J.; Meyer, G.; Olsson, F. E. et al. 2004. Controlling the charge state of individual gold adatoms. *Science* **305**: 493–495.

Repp, J.; Meyer, G.; Stojkovic, S. M. et al. 2005a. Molecules on insulating films: Scanning-tunneling microscopy imaging of individual molecular orbitals. *Phys. Rev. Lett.* **94**: 026803.

Repp, J.; Meyer, G.; Paavilainen, S. et al. 2005b. Scanning tunneling spectroscopy of Cl vacancies in NaCl films: Strong electron–phonon coupling in double-barrier tunneling junctions. *Phys. Rev. Lett.* **95**: 225503.

Ryndyk, D. A. and Cuniberti, G. 2007. Nonequilibrium resonant spectroscopy of molecular vibrons. *Phys. Rev. B* **76**: 155430.

Ryndyk, D. A.; D'Amico, P.; Cuniberty, G. et al. 2008. Charge-memory polaron effect in molecular junctions. *Phys. Rev. B* **78**: 085409.

Samanta, M. P.; Tian, W.; Datta, S. et al. 1996. Electronic conduction through organic molecules. *Phys. Rev. B* **53**: R7626–R7629.

Segal, D.; Nitzan, A.; Davis, W. B. et al. 2000. Electron transfer rates in bridged molecular systems. 2. A steady-state analysis of coherent tunneling and thermal transitions. *J. Phys. Chem. B* **104**: 3817–3829.

Segal, D.; Nitzan, A., and Hnggi, P. 2003. Thermal conductance through molecular wires. *J. Chem. Phys.* **119**: 6840–6855.

Siddiqui, L.; Ghosh, A. W., and Datta, S. 2007. Phonon runaway in nanotube quantum dots. *Phys. Rev. B* **76**: 085433.

Simonian, N.; Li, J., and Likharev, K. 2007. Negative differential resistance at sequential single-electron tunnelling through atoms and molecules. *Nanotechnology* **18**: 424006.

Skourtis, S. S. and Mukamel, S. 1995. Superexchange versus sequential long range electron transfer: Density matrix pathways in Liouville space. *Chem. Phys.* **197**: 367–388.

Smit, R. H. M.; Noat, Y.; Untiedt, C. et al. 2002. Measurement of the conductance of a hydrogen molecule. *Nature* **419**: 906–909.

Smit, R. H. M.; Untiedt, C., and van Ruitenbeek, J. M. 2004. The high-bias stability of monatomic chains. *Nanotechnology* **15**: S472–S478.

Stipe, B. C.; Rezaei, M. A., and Ho, W. 1999. Localization of inelastic tunneling and the determination of atomic-scale structure with chemical specificity. *Phys. Rev. Lett.* **82**: 1724–1727.

Tikhodeev, S. G. and Ueba, H. 2004. Relation between inelastic electron tunneling and vibrational excitation of single adsorbateson metal surfaces. *Phys. Rev. B* **70**: 125414.

Troisi, A. and Ratner, M. A. 2006. Molecular transport junctions: Propensity rules for inelastic tunneling. *Nano Lett.* **6**: 1784–1788.

Tsutsui, M.; Kurokawa, S., and Sakai, A. 2006. Bias-induced local heating in Au atom-sized contacts. *Nanotechnology* **17**: 5334–5338.

Wang, W.; Lee, T.; Kretzchmar, I. et al. 2004. Inelastic electron tunneling spectroscopy of an alkanedithiol self-assembled monolayer. *Nano Lett.* **4**: 643–646.

Wingreen, N. S.; Jacobsen, K. W., and Wilkins, J. W. 1989. Inelastic scattering in resonant tunneling. *Phys. Rev. B* **40**: 11834–11850.

Wingreen, N. S.; Jauho, A.-P., and Meir, Y. 1993. Time-dependent transport through a mesoscopic structure. *Phys. Rev. B* **48**: 8487–8490.

Wu, S. W.; Nazin, G. V.; Chen, X. et al. 2004. Control of relative tunneling rates in single molecule bipolar electron transport. *Phys. Rev. Lett.* **93**: 236802.

Xu, B.; Zhang, P.; Li, X. et al. 2004. Direct conductance measurement of single DNA molecules in aqueous solution. *Nano Lett.* **4**: 1105–1108.

Xue, Y. and Ratner, M. A. 2003a. Microscopic study of electrical transport through individual molecules with metallic contacts. I. Band lineup, voltage drop, and high-field transport. *Phys. Rev. B* **68**: 115406.

Xue, Y. and Ratner, M. A. 2003b. Microscopic study of electrical transport through individual molecules with molecular contacts. II. Effect of interface structure. *Phys. Rev. B* **68**: 115407.

Xue, Y. and Ratner, M. A. 2004. End group effect on electrical transport through individual molecules: A microscopic study. *Phys. Rev. B* **69**: 085403.

Xue, Y.; Datta, S.; Hong, S. et al, 1999. Negative differential resistance in the scanning-tunneling spectroscopy of organic molecules. *Phys. Rev. B* **59**: R7852–R7855.

Xue, Y.; Datta, S., and Ratner, M. A. 2001. Charge transfer and "band lineup" in molecular electronic devices: A chemical and numerical interpretation. *J. Chem. Phys.* **115**: 4292–4299.

Yeganeh, S.; Galperin, M., and Ratner M. A. 2007a. Switching in molecular transport junctions: Polarization response. *J. Am. Chem. Soc.* **129**: 13313–13320.

Yeganeh, S.; Ratner, M. A., and Mujica, V. 2007b. Dynamics of charge transfer: Rate processes formulated with nonequilibrium Green's functions. *J. Chem. Phys.* **126**: 161103.

Yu, L. H.; Keane, Z. K.; Ciszek, J. W. et al. 2004. Inelastic electron tunneling via molecular vibrations in single-molecule transistors. *Phys. Rev. Lett.* **93**: 266802.

Zazunov, A. and Martin, T. 2007. Transport through a molecular quantum dot in the polaron crossover regime. *Phys. Rev. B* **76**: 033417.

Zazunov, A.; Feinberg, D., and Martin, T. 2006a. Phonon squeezing in a superconducting molecular transistor. *Phys. Rev. Lett.* **97**: 196801.

Zazunov, A.; Feinberg, D., and Martin, T. 2006b. Phonon-mediated negative differential conductance in molecular quantum dots. *Phys. Rev. B* **73**: 115405.

Zhitenev, N. B.; Meng, H., and Bao, Z. 2002. Conductance of small molecular junctions. *Phys. Rev. Lett.* **88**: 226801.

Zimbovskaya, N. A. 2003. Low temperature electronic transport and electron transfer through organic macromolecules. *J. Chem. Phys.* **118**: 4–7.

Zimbovskaya, N. A. 2005. Low temperature electronic transport through macromolecules and characteristics of intramolecular electron transfer. *J. Chem. Phys.* **123**: 114708.

Zimbovskaya, N. A. 2008. Inelastic electron transport in polymer nanofibers. *J. Chem. Phys.* **123**: 114705.

Zimbovskaya, N. A. and Gumbs, G. 2002. Long-range electron transfer and electronic transport through macromolecules. *Appl. Phys. Lett.* **81**: 1518–1520.

Zimbovskaya, N. A. and Pederson, M. R. 2008. Negative differential resistance in molecular junction: The effect of electrodes electronic structure. *Phys. Rev. B* **78**: 153105.

Zimmerman, J.; Pavone, P., and Cuniberti, G. 2008. Vibrational modes and low-temperature thermal properties of graphene and carbon nanotubes: Minimal force constant model. *Phys. Rev. B* **78**: 045410.

11

Bridging Biomolecules with Nanoelectronics

11.1 Introduction and Background 11-1
11.2 Preparation of Molecular Magnets 11-2
Folding of Magnetic Protein Mn,Cd-MT • Protein: A Mesoscopic System • Quasi-Static Thermal Equilibrium Dialysis for Magnetic Protein Folding
11.3 Nanostructured Semiconductor Templates: Nanofabrication and Patterning 11-6
Patterned Self-Assembly for Pattern Replication • Fabrication by Direct Inkjet and Mold Imprinting • Nanopatterned SAMs as 2D Templates for 3D Fabrication
11.4 Self-Assembling Growth of Molecules on the Patterned Templates 11-8
11.5 Magnetic Properties of Molecular Nanostructures 11-10
11.6 Conclusion and Future Perspectives 11-10
References 11-11

Kien Wen Sun
National Chiao Tung University

Chia-Ching Chang
National Chiao Tung University

11.1 Introduction and Background

The field of nanostructures has grown out of the lithographic technology developed for integrated circuits, but is now much more than simply making smaller transistors. In the early 1980s, microstructures became small enough to observe interesting quantum effects. These structures were smaller than the inelastic scattering length of an electron so that the electrons could remain coherent as they traversed them, giving rise to interference phenomena. Studies on the Aharonov–Bohm effect and universal conductance fluctuations led to the field of "mesoscale physics"—between macroscopic classical systems and fully quantized ones.

Now the size of the structures that can be produced is approaching the de Broglie wavelength of the electrons in the solids, leading to stronger quantum effects. In addition to interesting new physics, this drive toward smaller length scales has important practical consequences. When semiconductor devices reach about 100 nm, the essentially classical models of their behavior will no longer be valid. It is not yet clear how to make devices and circuits that will operate properly on these smaller scales. The replacement for the transistor, which must carry the technology to well below 100 nm, has not been identified. It is anticipated that the semiconductor industry will run up against this "wall" within about 10 years.

The current very large-scale integrated circuit paradigm based on complementary metal oxide semiconductor (CMOS) technology cannot be extended into a region with features smaller than 10 nm.[1] With a gate length well below 10 nm, the sensitivity of the silicon field-effect transistor parameters may grow exponentially due to the inevitable random variations in the device size. Therefore, an alternative nanodevice concept of molecular circuits was proposed, which was a radical paradigm shift from the pure CMOS technology to the hybrid semiconductor.[2] The concept combines the advantages of nanoscale components, such as the reliability of CMOS circuits, and the advantages of patterning techniques, which include the flexibility of traditional photolithography and the potentially low cost of nanoimprinting and chemically directed self-assembly. The major attraction of this concept is the incorporation of the richness of organic chemistry with the versatilities of semiconductor science and technology. However, before this, one needs to bring directed self-assembly from the present level of single-layer growth on smooth substrates to the reliable placement of three-terminal molecules on patterned semiconductor structures.

While physics and electrical engineering have been evolving from microstructures, to mesoscopic structures, and now to nanostructures, molecular biologists have always worked with objects of a few nanometers or less. A DNA molecule, for example, is very long (when stretched out), but it is about 2.5 nm wide with base pairs separated by 0.34 nm. Since the technology has not existed to directly fabricate and manipulate objects this small, various chemical techniques have been developed for cutting, tagging, and sorting large biological molecules. While enormously successful, these methods utilize batch processing of huge numbers of the molecules and rely on statistical interpretations. It is not possible, in principle, to sequence one particular DNA molecule with these techniques, for example. Ideally, one would like to stretch the DNA straight and simply read the sequence of the base pairs. While we are still far from this goal, nanofabrication techniques promise to bring us much closer.

During recent years, self-assembly has become one of the most important strategies used in biology for the development of complex, functional structures. Self-assembly on modified surfaces is one of the approaches to self-assemble structures that are particularly successful. By the coordination of molecules to surfaces, the molecular systems form ordered systems—self-assembled monolayers (SAMs). The SAMs are reasonably well understood and are increasingly useful technologically. A thin film of diblock copolymers can be self-assembled into ordered periodic structures at the molecular scale (~5–50 nm) and have been used as templates to fabricate quantum dots,[3,4] nanowires,[5–7] and magnetic storage media.[8] More recently, in epitaxial assembly of block-copolymer films, molecular level control over the precise size, shape, and spacing of the order domains was achieved with advanced lithographic techniques.[9] The development of methods for patterning and immobilizing biologically active molecules with micrometer and nanometer scale control has been proven integral to ranges of applications such as basic research, diagnostics, and drug discovery. Some of the most important advances have been in the development of biochip arrays that present either DNA,[10] protein,[11] or carbohydrates.[12] The use of patterned substrates for components of microfluidic systems for bioanalysis is also progressing rapidly.[13–15] Surface modification and patterning at the nanoscale to anchoring protein molecules is an important strategy on the way of obtaining the construction of new biocompatible materials with smart bioactive properties. In fact, surfaces patterned by protein molecules can act as active agents in a large number of important applications including biosensors capable of multifunctional biological recognition. In particular, physical adsorption of proteins onto semiconductor surfaces makes possible to combine the simplicity of the method with the versatility of chemical and physical properties of proteins.

In recent years, there has been substantial attention focused on the reactions of organic compounds with silicon surfaces. The major attraction is the incorporation of the richness of organic chemistry with the versatilities of semiconductor science and technology. More recently, it has been demonstrated that TEMPO,2,2,6,6-tetramathylpiperidinyloxy can bond with a single dangling bond on hydrogen-terminated Si(100) and Si(111) surfaces.[16] Functional organic molecular layers were found to self-assemble on metal[2] and semiconductor surfaces.[17] The technique of self-assembly is one of the few practical strategies available to arrive at one to three-dimensional ensembles of nanostructures. There are many different mechanisms by which self-assembly of molecules and nanoclusters can be accomplished, such as chemical reactions, electrostatic and surface forces, and hydrophobic and hydrophilic interactions.

In this chapter, we present most recent advances in the development of techniques in immobilizing a single nanostructure and producing arrays of 3D magnetic protein nanostructures with high throughput on surface modified semiconductor substrates. Well-characterized test nanostructures were prepared using current state-of-the-art nanofabrication techniques. Both nanoimaging and scanning probe microscopy studies (AFM, SEM, and TEM) on semiconductor nanostructures and these molecular self-assembly systems were performed. The combination of e-beam lithography, scanning probe microscope imaging, spectroscopy, and self-assembly approaches provide not only the high throughput of producing arrays of protein nanostructures but also with highest precision of positioning single nanostructure and/or single molecule.

11.2 Preparation of Molecular Magnets

11.2.1 Folding of Magnetic Protein Mn,Cd-MT

Metallothionein (MT) is a metal binding protein that binds seven divalent transition metals avidly via its twenty cysteines (Cys).[18] These Cys' form two metal binding clusters located at the carboxyl (α-domain) and amino (β-domain) terminals of MT.[19] The two clusters were identified as α-cluster $(M_4S_{11})^{3-}$ and the β-cluster $(M_3S_9)^{3-}$ (Figure 11.1),[20–22] where M denotes metal ions (Zn^{2+}, Cd^{2+}, or others), according to both x-ray crystallographic and NMR studies.[3] MT binds to metals ions via metal-thiol linkages.[19] As shown in Figure 11.1, the $(M_3S_9)^{3-}$ and $(M_4S_{11})^{3-}$ have the zinc-blende like structure that is similar to the "diluted magnetic semiconductor (DMS)" compounds.[23]

In general, semiconductors are not magnetic. However, a DMS exhibits magnetic properties by doping with Mn and Cd or other II–VI metal ions in certain ratio. The doped metal clusters among the semiconductors are in zinc-blende structures. Meanwhile, these semiconductors possess magnetic property only in low temperatures.[23] The magnetic properties may be the result of the d-sp^3 orbital hybridization and the alignment of the electron spins. The bridging sulfur atoms may also contribute to the alignment of the spins of the Mn^{2+} ions. Thus, by chelating the Mn^{2+} and Cd^{2+} with MT (i.e., Mn,Cd-MT), a "magnetic protein" may be obtained.

Recently, the single molecule magnets (SMMs) have attracted much attention.[24] However, the Curie temperature of these molecules has to be as low as 2–4 K[24–26] to avoid the thermal fluctuation among the electron spin within the molecules.[27] To be of practical utilization, it is highly desirable to create a room temperature molecular magnet.[28] With this intention in mind, one has to construct and investigate a new metal binding protein, MT, which sustained characteristic magnetic hysteresis loop from 10 to 330 K. The protein backbone may restrain the net spin moment of Mn^{2+} ions to overcome the minor thermal fluctuation. The magnetic-metallothionein (mMT) presented may reveal a possible approach to create high temperature molecular magnet. In order to prepare the Mn,Cd-MT magnetic proteins, the folding mechanism of protein should be introduced.

11.2.2 Protein: A Mesoscopic System

Protein is a complex biomolecule that contains a large number of basic residues—amino acids. Therefore, it is not possible to analyze it completely by macroscopic approaches. Meanwhile, it



β-Cluster α-Cluster

FIGURE 11.1 Metal binding clusters of MT that was modified from x-ray crystal structure (2). Where the circles denote metal ions Zn^{2+}, Cd^{2+}, or Mn^{2+}. Each metal ion was linked with protein via metal-thiol bonds.

is not feasible to describe the dynamics of its polypeptide chain behavior by using conventional statistical approaches either. Thus, a protein can be thought of as a mesoscopic system.[29] However, the conformational transition from unfolded state to the native state of a protein may be similar to the conventional phase transition model. In physics, a phase transition is the transformation of a thermodynamic system from one phase to another. In a folding process, proteins follow the thermodynamic theories and transform from the unfolded state to the folded state, where the state is defined as a region of configuration space with minimal potential.[30] Therefore, we named this conformational change as "state transition."[31] Due to the complexity of a protein folding system, a single experimental study may reveal only a part of the fact of protein folding. Therefore, we should examine the protein-folding problem with multidimensional approaches and integrate the findings to reveal the true mechanism of protein folding.

Protein folding may follow a spontaneous process[29] or a reaction-path directed process[30] *in vitro*. A choice between the two may be determined by the intrinsic properties of proteins, for example, the varying folding transition boundaries. However, a general model, named "first-order-like state transition model," in which the aggregated proteins exist within finite boundaries can encompass both processes without any conflictions.[31–36] According to this model, the folding path of the protein may not be unique. It can be folded, without being trapped in an aggregated state, via a carefully designed refolding path circumventing the transition boundary, that is, via an overcritical path.[31–36] The intermediates, following an overcritical path, are in a molten globular state,[37] and their behavior is consistent with both a sequential[38] and a collapse model.[39] However, both soluble (folded) and precipitated (unfolded) proteins can be observed in the direct folding reaction path *in vitro*. In terms of the "first-order-like state transition model" language, this can be described as stepping across the state transition line in the protein folding reaction phase diagram.[31,32] Since in protein refolding it is important to prevent protein aggregation *in vitro*, similarly, in biomedical applications, the revelation of the mechanism of the formation of the two states (unfolded and folded) becomes significant.

Previous studies have indicated that chemical environment,[40] temperature,[41] pH,[42] ionic strength,[43] dielectric constant,[44] and pressure[49]—considered as solvent effects collectively—could affect the fundamental structure, thermodynamics, and dynamics of polypeptides/proteins. The reaction ground state can be expressed as a dual-well potential according to the two-state transition model. The conformational energy, in general, of the unfolded state is relatively higher than that of the native state (Figure 11.1). When the system reaches thermal equilibrium, most protein molecules are found in their native state. No unfolded or intermediate states are observable. However, as described previously,[31–36] if a denaturant is added, the reaction potential may change accordingly as indicated in Figure 11.1. Then, an unfolded protein may be stable, as it is now at the lowest energy under the newly established equilibrium. The energy of the system can be expressed as follows:

$$H_{\mathrm{T}} = H_{\mathrm{p}} + \lambda H_{\mathrm{s}} \tag{11.1}$$

where H_{T}, H_{p}, and H_{s} denote the potential energy of the interacting protein-solvent total system, the protein, and the solvent, respectively. The factor, λ, is a weighting factor of the solvent environment ($0 \le \lambda \le 1$). It approaches unity when a denaturant is present as pure solvent and decreases in value as the concentration of the denaturant is reduced.

When λ of the system is changed drastically, direct folding ensues and leads to the release of some of the bound denaturant. According to the Donnan effect in a macromolecule-counter ions interactive system, the diffusion of the bound denaturant can be expressed by Fick's first law:

$$\vec{J} = -D\nabla n \tag{11.2}$$

where

n denotes the concentration of the denaturant that is dissociated from the protein
D denotes the diffusive constant
vector J denotes the flux, respectively, of the solute

According to the Einstein relation

$$D = \frac{kT}{6\pi\eta R_H} \tag{11.3}$$

where

k is the Boltzmann constant
T is the temperature in Kelvin
η is the viscosity of the solvent
R_H is the hydration radius of the solutes

Due to the intrinsic diffusion process, the solute exchange processes are not synchronous for all protein molecules. Therefore, the folding rate of protein may not be measured directly by a simple spectral technique, that is, the stopped-flow CD,[45] continuous-flow CD,[46] or fluorescence.[47] However, the reaction interval of protein folding can be revealed by the autocorrelation of reaction time from these direct measurements. The detailed mechanism and an example will be discussed later.

If we look at the energy landscape funnel model of protein folding,[48] it appears that proteins can be trapped in a multitude of local minima of the potential well in a complicated protein system. The native state, though, is at the lowest energy level. When thermal equilibrium is reached, most of the protein molecules are located in the lowest energy state, with a population ratio as low as $e^{-\Delta E/kT}$, according to the Maxwell–Boltzmann distribution in thermodynamics. The ΔE denotes the energy difference between the native state and a local minimum; k and T denote the Boltzmann constant and temperature in Kelvin, respectively. At high concentration (>0.1 mg/mL), however, considerable amount of insoluble protein has been observed in protein folding,[31,33–37,48] indicating that insoluble proteins are at an even lower energy state than the native protein. Therefore, by considering the intermolecular interactions during the protein folding process, the reaction energy landscape may be expressed as a three-well model (Figure 11.2). As shown in Figure 11.2, the unfolded protein (U) is in the highest energy state; the native protein (N) is in the lower energy state. However, the intermediate (I) that may cause further protein aggregation/precipitation is in the lowest energy state. Although the energy state of the intermediate/aggresome is the lowest energy state, the conformational energy of the individual proteins composing the aggresome may not be lower than the native protein. Namely, in single molecular simulation, this extra potential well of intermediate (I) is nonexistent. Therefore, in the conventional energy landscape model (the single molecule simulation model), the lowest energy state "I" cannot be observed. According to the Zwanzig's definition of state, the protein molecules in the intermediate (I) belong to an unfolded state.[13] Hence, in a direct folding reaction, the soluble (N) and the insoluble parts (U) can coexist and they can be observed simultaneously, which is similar to the situation where the phase transition line is crossed in reactions congruent to the "first-order phase transition" model. Therefore, we named the protein folding reaction as "first-order like state transition model" (as shown in Figure 11.3).



FIGURE 11.2 Three well model of multi-protein molecules folding reaction. The U denotes the unfolded state. N denotes the native state and I denotes the protein–protein complex (aggresome) intermediate.

The $\Phi(n_1, n_2, \ldots)$ in Figure 11.3 denotes the folding status of protein, where $n_1, n_2, \ldots$ represent the variables affecting the folding status, such as, temperature, concentration of denaturants, etc. The reaction curve indicates an overcritical reaction path of a quasi-static folding reaction. The gray area in Figure 11.3 indicates the state transition boundary of protein folding. The gray line and dash line indicate the reaction path of direct folding. By combining the three-well model (Figure 11.2) and the direct



FIGURE 11.3 The protein folding phase diagram, where the $\Phi(n_1, n_2, \ldots)$ denotes the folding status (the order parameter) of protein. The $n, n_1, n_2, \ldots$ denote the variables that affect the folding status such as temperature, concentration of denaturants, etc.

folding reaction of the "first-order like state transition model" (Figure 11.3), we realized that those folded protein molecules along the direct folding path might fold spontaneously or form aggregates. Spontaneous folding may be driven by enthalpy–entropy compensation.

As indicated previously, the conformation of protein changed with changes of the solvent environment. It seems that the protein may fold spontaneously, such as in Anfinsen's experiment[44] and direct folding reactions. The protein folding reaction, similar to all chemical reactions, reaches its equilibrium by following the fundamental laws of thermodynamics. Although protein folding has been studied extensively in certain model systems for over 40 years, the driving force at the molecular level remained unclear until recently.

It is known that polymers and macromolecules may self-assemble/self-organize into a wide range of highly ordered phases/states at thermal equilibrium.[49–52] In a condensed solvent environment, large molecules may self-organize to reduce their effective volume. Meanwhile, the number of the allowed states (Ω) of small molecules, such as buffer salt and other counter-ions in solution, increases considerably. Therefore, the entropy of the system, $\Delta S = R\ \ln(\Omega_f/\Omega_i)$, becomes large, where i and f denote the initial and final states, respectively. Meanwhile, the enthalpy change (ΔH) between the unfolded and native protein is around hundreds kcal/mol.[53] Therefore, the Gibbs free energy of the system, $\Delta G = \Delta H - T\mathrm{d}S$, becomes more negative in this system when the large molecules self-organize.[54] A similar entropy–enthalpy compensation mechanism has been used to solve the reaction of colloidal crystals that self-assemble spontaneously.[55,56]

According to our studies,[31,33–37] the effective diameter of the unfolded protein is about 1.7–2.5 fold larger than the folded protein. Therefore, with the same mechanism, those macromolecules (proteins) may tend to reduce their effective volumes and increase the system entropy when thermal equilibrium is reached. The increase in entropy may compensate for the change of the enthalpy of the system and enable the reaction to take place spontaneously. This may be the reaction molecular mechanism of spontaneous protein folding reactions. Meanwhile, a similar mechanism can be adopted into the self-assembly process of magnetic protein in nanopore arrays.

11.2.3 Quasi-Static Thermal Equilibrium Dialysis for Magnetic Protein Folding

Due to the intrinsic diffusion process, the solvent exchange rate is slow and thus the variation of λ is slow and can be thought of as quasi-static. Therefore, we named this buffer exchanging process as a quasi-static process. We manipulated the reaction direction of the protein folding through this process. Meanwhile, we can obtain stable intermediates in each thermal equilibrium state. These intermediates may help us reveal the molecular folding mechanism of protein that is to be discussed in Section 11.3. The following is an example of the stepwise folding method,[31,33–37] and the buffers used were described in these studies.

Step 1: The unfolded protein (U) was obtained by treating the precipitate or inclusion body with denaturing/unfolding buffer to make it 10 mg/mL in concentration. This solution was left at room temperature for 1 h. This process was meant to relax the protein structure by urea and pH (acidic or basic) environments. The disulfide bridges were reduced to SH groups and the protein was unfolded completely.

Step 2: The unfolded protein (U) in the denature/unfolding buffer was dialyzed against the folding buffer 1 for 72 h to dilute the urea concentration to 2 M, producing intermediate 1, or M_1.

Step 3: M_2 was obtained by dialyzing M_1 against the folding buffer 2 for 24 h to dilute urea concentration to 1 M.

Step 4: M_3, an intermediate without denaturant (urea) in solution, was then obtained by dialyzing M_2 against the folding buffer 3 for 24 h.

Step 5: M_3 was further dialyzed against the folding buffer 4 for 24 h, and the pH changed from 11 to 8.8 to produce M_4.

Step 6: Finally, the chemical chaperonin mannitol was removed by dialyzing M_4 against the native buffer for 8 h to yield M_5.

It should be noted that all the equilibrium time of each step is longer than the conventional dialysis time. In general, for the free solvent case, the solute may exchange with the buffer completely within hours. However, it is known that the denaturant molecules interact with protein, similar to the Donna effect, and the solute exchange may be slow and needs more time for the system to reach thermal equilibrium, especially for the first refolding stage. The folding time of each process is relatively longer than the regular solvent exchange process. Therefore, we can obtain the magnetic protein that follows a similar process. Protein microenvironment protects the net electron spin of molecules from thermal fluctuation.

The bridging ligands (i.e., sulfur atom, S) between the magnetic ions may be responsible for aligning the electron spin of magnetic ions. As indicated in Figure 11.4, the valance bonding electrons of the bridging Cys may hop between the bonded metal ions, such as Mn^{2+} and Cd^{2+}; whereas the Cd^{2+} in the β metal cluster is rather important in restraining the orientation of the electron spins of the bridging sulfurs and in aligning the spins of Mn^{2+} in the metal binding clusters. Therefore, this electron hopping effect may turn the Mn,Cd-MT into a magnetic molecule. However, the protein backbone surrounding the β metal cluster may provide a strong restraining effect to overcome the thermal fluctuations from the environment. Therefore, the magnetization can be observed in room temperature. However, the geometrical symmetry of the spin arrangement in all Mn-MT may cause partial or complete cancellation of detectable magnetization. These results also indicated that the threshold temperature of the molecular magnet might rise to room temperature if the proper prosthetic environment, such as protein backbone, can be linked against the thermal fluctuation of the temperature.



FIGURE 11.4 Proposed electron spin model of Mn^{2+} in β metal binding cluster of Mn,Cd-MT-2.

Therefore, we have successfully constructed a molecular magnet, Mn,Cd-MT, that is stable from 10 to 330 K. The observed magnetic moment can be explained by the highly ordered alignment of $(Mn_2CdS_9)^{3-}$ clusters embedded in the β-domain in which sulfur atoms serve as key bridging ligands. The discovery of mMT may allude to new schemes in constructing a completely different category of molecular magnets.

11.3 Nanostructured Semiconductor Templates: Nanofabrication and Patterning

The rapidly developing of interdisciplinary activity in nanostructuring is truly exciting. The intersections between the various disciplines are where much of the novel activity resides, and this activity is growing in importance. The basis of the field is any type of material (metal, ceramic, polymer, semiconductor, glass, and composite) created from nanoscale building blocks (clusters of nanoparticles, nanotube, nanolayers, etc.) that are themselves synthesized from atoms and molecules. Thus, the controlled synthesis of those building blocks and their subsequent assembly into nanostructures is one fundamental theme of this field. This theme draws upon all of the material-related disciplines from physics to chemistry to biology and to essentially all of the engineering disciplines as well.

The second and most fundamental important theme in this field is that the nanoscale building blocks, because of their size being below about 100 nm, impart to the nanostructures that are created from them new and improved properties and functionalities that are still unavailable in conventional materials and devices. The reason for this is that the materials in this size range can exhibit fundamentally new behavior when their sizes fall below the critical length scale associated with any given property. Thus, essentially any material property can be dramatically changed and engineered through the controlled size-selective synthesis and assembly of nanoscale building blocks. The present juncture is important in the fields of nanoscale solid-state physics, nanoelectronics, and molecular biology. The length scales and their associated physics and fabrication technology are all converging to the nanometer range.

The ability to fabricate structures with nanometer precision is of fundamental importance for any exploitation of nanotechnology. In particular, cost effective methods that are able to fabricate complex structures over large areas will be required. One of the main goals in the nanofabrication area is to develop general techniques for rapidly patterning large areas (a square centimeter, or more) with structures of nanometer sizes. Presently, electron-beam (e-beam) lithography is capable of defining patterns that are less than 10 nm. These patterns can then be transferred to a substrate using various ion milling/etching techniques. However, these are “heroic” experiments, and can only be made over a very limited area—typically a few thousand square microns, at most. While such areas are immediately useful for investigating the physics of nanostructures, the applications we would like to pursue will eventually require a faster writing scheme and much larger areas. The time and area constraints are determined by the direct e-beam writing. It is a “serial” process, defining single small regions at a time. Furthermore, the field of view for the e-beam system is typically less than 100 nm when defining the nanometer-scale structures. One simply cannot position the electron beam with nm precision over larger areas.

While e-beam lithographic methods are very general, in that essentially any shape can be written, we will also make use of “natural lithography” (tricks). Similarly, advances in the knowledge of the DNA structure has recently been applied to the fabrication of self-organized nm surface structures. There are many such “tricks” that could prove crucial to the success of the projects in allied fields. A list of current methods toward nanofabrication is given below.

11.3.1 Patterned Self-Assembly for Pattern Replication

By exploiting e-beam and focused ion beam lithography, self-assembled monolayers can be patterned into 10–20 nm features that can be functionalized with single molecules or small molecular groupings. These patterned areas will then be used as templates to direct the vertical assembly of stacks of molecules or to direct the growth of polymeric molecules. Schematics of the processes and the possible templates used are shown in Figure 11.5. The initial 2D pattern will thus be translated into 3D nanosized objects. With the capability of the full control over the interfacial properties, it will be possible to release the objects from the templates and transfer them to another substrate, after which the nanopatterned surface can be used again to provide an inexpensive replication technique.



(a)

(b)

FIGURE 11.5 E-beam lithography defined (a) nanopores and (b) nanotrenches on silicon templates. (From Chang, C.-C. et al., *Biomaterials*, 28, 1941, 2007. With permission. Elsevier.)

11.3.2 Fabrication by Direct Inkjet and Mold Imprinting

This part of the technique will draw on recent advances in printing techniques for direct patterning of surfaces. This involves the use of inkjet printing to deliver a functional material (semiconductor or metal) to a substrate, which is then controlled by patterning in the surface free energy of the substrate, to allow very accurate patterning of the printed material. Currently, devices show channel lengths down to 5 μm, but indications are that geometries can be reduced to submicron dimensions. The method will be concerned with the limits to resolution that can be achieved by this process, and also the structure and the associated electronic structure at polymer–polymer interfaces, such as that between semiconductor and insulator layers in the field-effect device.



FIGURE 11.6 Nanogratings on silicon templates by using thermal nano-imprinting technique.

In 1995, Professor Stephen Y. Chou of Princeton University invented a new fabrication method in the field of semiconductor fabrication. It is called nano-imprint lithography (NIL).[57] Briefly speaking, this technique was demonstrated by pressing the patterned mold to contact with the polymer resist directly. The patterns on the mold will transfer to the polymer resist without any exposure source. Therefore, the diffraction effect of light can be ignored, and the limitation is dependent only on the pattern size of the mold rather than on the wavelength of the exposure light. In Figure 11.6 we show a nano-grating structure made by using the thermal imprinting technique.

NIL technology is a physical deformation process and is very different from conventional optical lithography. This technology provides a different way to fabricate nanostructures with easy processes, high throughput, and low cost. Currently, there are three main NIL techniques under investigation, namely, hot-embossing nano-imprint lithography (H-NIL[57]), ultraviolet nano-imprint lithography (UV-NIL[58]), and soft lithography.[59] Those NIL technologies can be applied to many different research fields, including nano-electric devices,[60] bio-chips,[61] micro-optic devices,[62] micro-fluidic channels,[63] etc.

11.3.3 Nanopatterned SAMs as 2D Templates for 3D Fabrication

Modern lithographic techniques (e-beam or focused ion beam (FIB), SNOM lithography) are able to generate topographic (relief) patterns in the 10–50 nm size ranges. As a further step toward more complicated and functional 3D structures, chemical functionalization at a similar size scale is necessary. By exploiting e-beam, FIB, and near-field optical lithography, it is possible to pattern SAMs directly. Using lithography, the SAMs can either be locally destroyed and refilled with other molecules, or the surface of the SAMs can be activated to allow further chemical reactions. The resulting patterned surfaces will be chemically patterned. Patterns can be introduced to incorporate H-bonding, pi–pi stacking, or chemical reactivity. These patterned areas will be used as templates to direct the vertical assembly of stacks of molecules or to direct the growth of polymeric molecules. Large, extended aromatic molecules prefer to stack on top of each other due to pi–pi stacking. These molecules have interesting electronic properties as molecular wires. When surfaces can be patterned to incorporate "seeds" for the large aromatic molecules, the stacking can be directed away from the surface. The initial 2D pattern will thus be translated into 3D nanosized objects. With the full control over the interfacial properties, it will be possible to release the objects from the templates and transfer them to another substrate, after which the nanopatterned surface can be used again to provide an inexpensive replication technique.



FIGURE 11.7 (a) Flowchart of the lithography, etching processes, and growth of protein molecules, (b) schematics of the patterned templates with nanopores. (From Chang, C.-C. et al., *Biomaterials*, 28, 1941, 2007. With permission. Elsevier.)

11.4 Self-Assembling Growth of Molecules on the Patterned Templates

The self-assembling growth of the MT-2 proteins is demonstrated as follows. One mg/mL magnetic MT in Tris. HCL buffer solution was placed onto the patterned surface, and an electric field with an intensity of 100 V/cm was then applied for 5 min to drive the MT molecules into the nanopores. The sample was then washed with DI water twice to remove the unbounded MT molecules and salts on the surface (the schematic of the process is also shown in Figure 11.7a. Figure 11.8 shows the atomic force microscopy (AFM) image of the template surface with 40 nm nanopores after they were filled by the MT-molecules. Keep in mind that most of the Si surface was still protected by photoresist after the etching processes, which has prevented the MT-molecules from forming strong OH bonds with the Si surface underneath. Therefore, the electrical field-driven MT molecules were all anchored on those areas that were not covered with photoresist. The molecules landing in each pore were then self-assembly grown vertically from the bottom of the pore into the shape of a rod (as shown in Figure 11.8). These molecular nanorods have an average height of ~120 nm above the template surface and a diameter equal to the size of the nanopore.



FIGURE 11.8 Three-dimensional AFM image of the patterned magnetic molecules. The molecules have self-assembled to grow into a rod shape. (From Chang, C.-C. et al., *Biomaterials*, 28, 1941, 2007. With permission. Elsevier.)



FIGURE 11.9 Two-dimensional AFM images of the patterned MT-molecules on the template with pore size of 130 nm and pitch size of 300 nm. (From Chang, C.-C. et al., *Biomaterials*, 28, 1941, 2007. With permission. Elsevier.)

However, experiments on the templates with pore sizes larger than 100 nm gave quite different results. Figure 11.9 shows the two-dimensional AFM image of the template surface with larger pores, where we can see that the molecules did not grow vertically above the template surface. Therefore, we were not able to generate 3D images of this type of template. However, judging from the AFM phase images, the MT molecules did form a more dense structure in the larger pores compared with the case of the smaller pores. On templates with thinner photoresist and smaller pitch sizes (less than 600 nm), we also found that the molecules anchored in the pore can grow laterally toward the neighboring pores (data not shown).

By increasing both the e-beam exposure and dry etching time on the Si surface covered with a thin photoresist layer with a thickness of less than 150 nm, we were able to create a ring-type area with an exposed Si surface along the periphery of the nanopores. The SEM image of this type of template is shown in Figure 11.10. On this particular template, the molecules not only independently grew inside the pores, but they also grew along the circumference of the pores to form molecular rings on the template. Figure 11.11 shows the two-dimensional (2D) and three-dimensional (3D) AFM images of such molecular rings.

In order to gain better control of the formation of molecular nanostructures, it is important to uncover the underlying self-assembling growth mechanism. Molecular self-assembly



FIGURE 11.10 SEM image of the Si template shows a ring shape Si exposed area around the circumference of nanopores. (From Chang, C.-C. et al., *Biomaterials*, 28, 1941, 2007. With permission. Elsevier.)



FIGURE 11.11 (a) 2D and (b) 3D AFM images of the patterned MT-molecules. (From Chang, C.-W. et al., *Appl. Phys. Lett.*, 88(26), 263104, 2006. With permission. AIP.)

can be mediated by weak, noncovalent bonds—notably hydrogen bonds, ionic bonds (electrostatic interactions), hydrophobic interactions, van der Waals interactions, and water-mediated hydrogen bonds. Although these bonds are relatively insignificant in isolation, when combined together as a whole, they govern the structural conformation of all biological macromolecules and influence their interaction with other molecules. The water-mediated hydrogen bond is especially important for living systems, as all biological materials interact with water. We believe that the first layer of proteins anchored inside the nanopores was bonded with the Si surface dangling bonds. They have provided building blocks for proteins that arrived later. With the assistance of spatial confinement from the patterned nanostructures, the rest of the proteins are able to self-assemble via the van der Waals interactions and perform molecular self-assembly.

11.5 Magnetic Properties of Molecular Nanostructures

The magnetic properties of the self-assembled molecular nanorods were investigated with magnetic force microscopy (MFM). We monitored the change of contour of a particular nanorod on the template when an external magnetic field was applied. Figure 11.12a shows the MFM image of the nanorod without the external magnetic field. In Figure 11.12b, a magnetic field of 500 Oe was applied during the measurement with a field direction from the right to left. The strength of the field was kept at a minimum so as not to perturb the magnetic tip on the instrument. In Figure 11.12 we can see clearly that the contour of the nanorod has changed in shape as compared to the case with no applied field. It indicates that the molecular self-assembly carries a magnetic dipole moment that interacts with the external magnetic field.

11.6 Conclusion and Future Perspectives

Success in the synthesis of the magnetic molecules produced from metallothionein (MT-2) by replacing the Zn atoms with Mn and Cd has been demonstrated in this chapter. Hysteresis behavior in the magnetic dipole momentum measurements was observed over a wide range of temperatures when an external magnetic field was scanned. These magnetic MT molecules were also found to self-assemble into nanostructures with various shapes depending on the nanostructures patterned on the Si templates. Data from the MFM measurements indicate that these molecular self-assemblies also carry magnetic dipole momentum. Since the pore size, spacing and shape can easily and precisely be controlled by lithography and etching techniques, this work should open up a new path toward an entire class of new biomaterials that can be easily designed and prepared. The techniques developed in this particular work promise to facilitate the creation of many bio-related nanodevices and spintronics. Magnetic molecular self-assembly may find its use in data storage or magnetic recording systems, as an example. They can also act as spin biosensors and be placed at the gate of the semiconductor spin valve to control the spin current from the source to the drain. More importantly, this work should not be limited to MT-2 molecules



FIGURE 11.12 MFM images of nanorods (a) without the magnetic field (b) with a 500 Oe magnetic field applied with a field direction from right to left. (From Chang, C.-C. et al., *Biomaterials*, 28, 1941, 2007. With permission. Elsevier.)

and should be extended to other type of molecules and proteins as well. As mentioned in the beginning of this chapter, the various surface patterning techniques developed over the years to interface organic or biological materials with semiconductors have not only provided new tools for controlled 2D and 3D self-organized assemblies, but have also been essential to the creation and emergence of new semiconductor-molecular nanoelectronics as recently discussed by Likharev.[64]

In the future, it is important to develop techniques for growing and characterizing molecular self-assembly, single nanostructure, and molecule on semiconductor templates to bring a measure of control to the density, order, and size distribution of these molecular nanostructures. Using self-assembly techniques, one can routinely make molecular assembly with precise distances between them. Recent explorations of molecular self-assembly have sought to provide transverse dimensions on the mesoscopic nanometer scale. As a general—although not inviolate—rule, these attempts have led to very good local ordering (e.g., nearest neighbors).

We can anticipate, (1) the development of new (supra) molecular nanostructures via the self-assembling method (bottom up technique) and immobilization of single nanostructure or molecule; (2) the design of methods to functionalize molecular self-assembly and devices; (3) an integration of bottom-up and top-down procedures for the nano- and microfabrication of molecularly driven sensors, actuators, amplifiers, and switches; and (4) an increased understanding and appreciation of the science and engineering that lie behind nanoscale processes. All this and more is in the nature of the nanotechnology bonds as it impacts on biology and beyond. In the final analysis, however, the practice of biological synthesis that relies on molecular recognition and self-assembling processes within a very much more catholic framework than is currently being contemplated by most researchers that will dictate the pace of progress in synthesis.

The final goal is to understand this whole notion of what self-assembly is. One needs to really learn how to make use of the methods of organizing structures in more complicated ways than we can do now. On a molecular scale, the accurate and controlled application of intermolecular forces can lead to new and previously unachievable nanostructures. This is why molecular self-assembly (MSA) is a highly topical and promising field of research in nanotechnology today. MSA encompasses all structures formed by molecules selectively binding to a molecular site without external influence. With many complex examples all around us in nature (ourselves included), MSA is a widely observed phenomenon that has yet to be fully understood. Being more a physical principle than a single quantifiable property, it appears in engineering, physics, chemistry, and biochemistry, and is therefore truly interdisciplinary.

References

1. Sessoli R., Gatteschi D., Caneschi A., and Novak M.A. (1993), *Nature* (*London*), **365**, 141–143.
2. Fonticelli M., Azzaroni O., Benitez G., Martins M.E., Carro P., and Salvarezza R.C. (2004), *J. Phys. Chem. B*, **108**, 1898.
3. Park M., Harrison C., Chaikin P.M., Register R.A., and Adamson D.H. (1997), *Science* (*Washington*, *DC*), **276**, 1401–1404.
4. Li R.R., Dapkus P.D., Thompson M.E., Jeong W.G., Harrison C., Chaikin P.M., Register R.A., and Adamson D.H. (2000), *Appl. Phys. Lett.*, **76**, 1689–1691.
5. Thurn-Albrecht T., Schotter J., Kästle G.A., Emley N., Shibauchi T., Krusin-Elbaum L., Guarini K., Black C.T., Tuominen M.T., and Russell T.P. (2000), *Science* (*Washington, DC*), **290**, 2126–2129.
6. Kim H.C. et al. (2001), *Adv. Mater.*, **13**, 795–797.
7. Lopes W.A. and Jaeger H.M. (2001), *Nature*, **414**, 735–738.
8. Cheng J.Y. et al. (2001), *Adv. Mater.*, **13**, 1174–1178.
9. Kim S.O., Solak H.H., Stoykovich M.P., Ferrier N.J., de Pablo J.J., and Nealey P.F. (2003), *Nature*, **424**, 411–414.
10. Demers L.M., Ginger D.S., Park S.J., Li Z., Chung S.W., and Mirkin C.A. (2002), *Science* (*Washington*, *DC*), **296**, 1836–1838.
11. Hodneland C.D., Lee Y.S., Min D.H., and Mrksich M. (2002), *Proc. Natl. Acad. Sci.*, **99**, 5048–5052.
12. Houseman B.T. and Mrksich M. (2002), *Chem. Biol.*, **9**, 443–454.
13. Chen C.S., Mrksich M., Huang S., Whitesides G.M., and Ingber D.E. (1997), *Science* (*Washington*, *DC*), **276**, 1345–1347.
14. Mrksich M., Dike L.E., Tien J.Y., Ingber D.E., and Whitesides G.M. (1997), *Exp. Cell. Res.*, **235**, 305–313.
15. Chen C.S., Mrksich M., Huang S., Whitesides G.M., and Ingber D.E. (1998), *Biotech. Prog.*, **14**, 356–363.
16. Pitters J.L., Piva P.G., Tong X., and Wolkow R.A. (2003), *Nano Lett.*, **3**, 1431.
17. Wacaser B.A., Maughan M.J., Mowat I.A., Niederhauser T.L., Linford M.R., and Davis R.C. (2003), *Appl. Phys. Lett.*, **82**, 808.
18. Eaton D.L. (1985), *Toxicol. Appl. Pharmacol.*, **78**, 158–162.
19. Robbins A.H., McRee D.E., Williamson M., Collett S.A., Xuong N.H., Furey W.F., Wang B.C., and Stout C.D. (1991), *J. Mol. Biol.*, **221**, 1269–1293.
20. Messerle B.A., Schaffer A., Vasak M., Kagi J.H.R., and Wuthrich K. (1992), *J. Mol. Biol.* **225**, 433–443.
21. Boulanger Y., Goodman C.M., Forte C.P., Fesik S.W., and Armitage I.M. (1983), *Proc. Natl. Acad. Sci.*, **80**, 1501–1505.
22. Chang C.C. and Huang P.C. (1996), *Protein Eng.*, **9**, 1165–1172.
23. Wei S.H. and Zunger A. (1986), *Phys. Rev. Lett.*, **56**, 2391–2394.
24. Christou G., Gatteschi D., Hendrickson D.N., and Sessoli R. (2000), *MRS Bull.*, **25**, 66–71.
25. Sessoli R., Tsai H.L., Schake A.R., Wang S., Vincent J.B., Folting K., Gatteschi D., Christou G., and Hendrickson D.N. (1993), *J. Am. Chem. Soc.*, **115**, 1804–1816.
26. Aubin S.M.J., Dilley N.R., Pardi L., Kryzystek J., Wemple M.W., Brunel L.C., Maple M.B., Christou G., and Hendrickson D.N. (1998), *J. Am. Chem. Soc.*, **120**, 4991.
27. Friedman J.R., Sarachik M.P., Tejada J., and Ziolo R. (1996), *Phys. Rev. Lett.*, **76**, 3830–3833.

28. Bushby R.J. and Pailland J.-L. (1995), Molecular magnets, in *Introduction to Molecular Electronics*, M.C. Petty, M.R. Bryce, and D. Bloor (eds.), Edward Arnold, Hodder Headline, London, U.K.
29. Wolynes P.G. (1997), *Proc. Natl. Acad. Sci. U.S.A.*, **94**, 6170–6175.
30. Zwanzig R. (1997), *Proc. Natl. Acad. Sci. U.S.A.*, **94**, 148–150.
31. Chang C.-C., Yeh X.-C., Lee H.-T., Lin P.-Y., and Kan L.S. (2004), *Phys. Rev. E*, **70**, 011904.
32. Welker E., Wedemeyer W.J., Narayan M., and Scheraga H.A. (2001), *Biochemistry*, **40**, 9059–9064.
33. Chang C.-C., Su Y.-C., Cheng M.-S., and Kan L.S. (2002), *Phys. Rev. E*, **66**, 021903.
34. Chang C.-C., Tsai C.T., and Chang C.Y. (2002), *Protein Eng.*, **5**, 437–441.
35. Chang C.-C., Su Y.-C., Cheng M.-S., and Kan L.S. (2003), *J. Biomol. Struct. Dyn.*, **21**, 247–256.
36. Chang C.-C. and Kan L.-S. (2007), *Chin. J. Phys.*, **45**, 693–702.
37. Liu Y.-L., Lee H.-T., Chang C.-C., and Kan L.S. (2003), *Biochem. Biophys. Res. Commun.*, **306**, 59–63.
38. Levy Y., Jortner J., and Becker O. (2001), *Proc. Natl. Acad. Sci. U.S.A.*, **98**, 2188–2193.
39. Creighton T.E. (1993), *Proteins*, W.H. Freeman, New York.
40. Elcock A.H. (1999), *J. Mol. Biol.*, **294**, 1051–1062.
41. Ulrih N.P., Anderluh G., Macek P., and Chalikian, T.V. (2004), *Biochemistry*, **43**, 9536–9545.
42. Despa F., Fernandez A., and Berry R.S. (2004), *Phys. Rev. Lett.*, **93**, 228104.
43. Seefeldt M.B., Ouyang J., Froland W.A., Carpenter J.F., and Randolph T.W. (2004), *Protein Sci.*, **13**, 2639–2650.
44. Anfinsen C.B., Haber E., Sela M., and White F.H. Jr. (1961), *Proc. Natl. Acad. Sci.*, **47**, 1309–1314.
45. Su Z.D., Arooz M.T., Chen H.M., Gross C.J., and Tsong T.Y. (1996), *Proc. Natl. Acad. Sci.*, **93**, 2539–2544.
46. Roder H., Maki K., Cheng H., and Shastry M.C. (2004), *Methods*, **34**, 15–27.
47. Royer C.A. (1995), *Methods Mol. Biol.*, **40**, 65–89.
48. Misawa S. and Kumagai I. (1999), *Biopolymers*, **51**, 297–307.
49. Dinsmore A.D., Crocker J.C., and Yodh A.G. (1998), *Curr. Opin. Colloid Interface Sci.*, **3**, 5–11.
50. Gast A.P. and Russel W.B. (1998), *Phys. Today*, **51**, 24–30.
51. Pusey P.N. and van Megan W. (1986), *Nature*, **320**, 340–341.
52. Ackerson B.J. and Pusey P.N. (1988), *Phys. Rev. Lett.*, **61**, 1033–1036.
53. Tsong T.Y., Hearn R.P., Warthal D.P., and Sturtevant J.M. (1970), *Biochemistry*, **9**, 2666–2677.
54. Tokuriki N., Kinjo M., Negi S., Hoshino M., Goto Y., Urabe I., and Yomo T. (2004), *Protein Sci.*, **13**, 125–133.
55. Lin K.-H., Crocker J.C., Prasad V., Schofield A., Weitz D.A., Lubensky T.C., and Yodh A.G. (2000), *Phys. Rev. Lett.*, **85**, 1770–1773.
56. Lau A.W.C., Lin K.-H., and Yodh A.G. (2002), *Phys. Rev. E*, **66**, 020401.
57. Stephen Y.C., Peter R.K., and Preston J. R. (1995), *Appl. Phys. Lett.*, **67**, 3114–3116.
58. Bender M., Otto M., Hadam B., Spangenberg B., and Kurz H. (2000), *Microelectron. Eng.*, **53**, 233–236.
59. Xia Y. and Whitesides G.M. (1998), *Angew. Chem. Int.*, **37**, 550–575.
60. Lingjie G., Peter R.K., and Stephen Y.C. (1997), *Appl. Phys. Lett.*, **71**, 1881–1883.
61. Pépin A., Youinou P., Studer V., Lebib A., and Chen Y. (2002), *Microelectron. Eng.*, **61–62**, 927–932.
62. Li M., Tan H., Chen L., Wang J., and Chou S.Y., (2003), *J. Vac. Sci. Technol. B*, **21**, 660–663.
63. Cho Y.H., Lee S.W., Kim B.J., and Fujii T. (2007), *Nanotechnology*, **18**, 465303.
64. Likharev K.K. (2003), Hybrid semiconductor–molecular nanoelectronics. *The Industrial Physicist*, June/July 2003, Forum: 20–23.
65. Chang C.-C., Sun K.W., Lee S.F., and Kan L.S. (2007), *Biomaterials*, **28**, 1941–1947.
66. Chang C.-C., Sun, K.W., Kan, L.-S., and Kuan, C.-H. (2006), *Appl. Phys. Lett.*, **88**, 263104.

II

Nanoscale Transistors

12 **Transistor Structures for Nanoelectronics** *Jean-Pierre Colinge and Jim Greer* **12**-1
Introduction • Evolution of Silicon Processing: Technology Boosters • Nonplanar Multi-Gate Transistors • The Rise of Quantum Effects • Carbon Nanotube Transistors • Nonclassical Transistor Structures • Graphene Ribbon Nanotransistors • Sub-*kT/q* Switch • Single-Electron Transistor • Spin Transistor • Molecular Tunnel Junctions • Point Contacts and Conductance Quantum • Atomic-Scale Technology Computer-Aided Design • Conclusion • References

13 **Metal Nanolayer-Base Transistor** *André Avelino Pasa* **13**-1
Introduction • Band Diagram • *J–V* Characteristic • Fabrication • References

14 **ZnO Nanowire Field-Effect Transistors** *Woong-Ki Hong, Gunho Jo, Sunghoon Song, Jongsun Maeng, and Takhee Lee* **14**-1
Introduction • Background • Results and Discussion • Summary • Acknowledgment • References

15 **C_{60} Field Effect Transistors** *Akihiro Hashimoto* **15**-1
Introduction • Fullerene (C_{60}) • Solid C_{60} • van der Waals Epitaxy of C_{60} • Principles of Organic FET Functions • Fabrication of Fullerene Field Effect Transistors (C_{60} FET) • Characterization of C_{60} FETs on SiO_2 or on AlN • Summary • References

16 **The Cooper-Pair Transistor** *José Aumentado* **16**-1
Introduction • Theory of Operation • Fabrication • Practical Operation and Performance • Present Status and Future Directions • Acknowledgment • References

12

Transistor Structures for Nanoelectronics

12.1 Introduction **12**-1
12.2 Evolution of Silicon Processing: Technology Boosters **12**-2
12.3 Nonplanar Multi-Gate Transistors **12**-3
12.4 The Rise of Quantum Effects **12**-5
12.5 Carbon Nanotube Transistors **12**-6
12.6 Nonclassical Transistor Structures **12**-7
12.7 Graphene Ribbon Nanotransistors **12**-7
12.8 Sub-*kT*/*q* Switch **12**-8
12.9 Single-Electron Transistor **12**-8
12.10 Spin Transistor **12**-9
12.11 Molecular Tunnel Junctions **12**-9
12.12 Point Contacts and Conductance Quantum **12**-11
12.13 Atomic-Scale Technology Computer-Aided Design **12**-11
12.14 Conclusion **12**-12
References **12**-12

Jean-Pierre Colinge
University College Cork

Jim Greer
University College Cork

12.1 Introduction

In 1965, Gordon Moore predicted that the number of transistors that could be placed on a silicon chip would double every 18 months. This prediction became the official roadmap of the semiconductor industry and it still is the yardstick by which the progress of microelectronic devices and circuits is measured (Moore 1965). The MOS transistor, also called MOSFET (metal-oxide-semiconductor field-effect transistor) is the workhorse of the semiconductor industry and is at the heart of every digital circuit. Without the MOSFET, there would be no computer industry, no digital telecommunication systems, no video games, no pocket calculators, and no digital wristwatches.

Figure 12.1 shows the evolution of the number of MOS transistor per chip vs. calendar year, known as "Moore's law." Note that the vertical axis has a logarithmic scale. The effective length of the transistor, *L*, is the distance between the source and the drain in a region called the "channel region" where the electrostatics and the current flow are controlled by the gate. When the effective gate length becomes too small, the gate loses the control of that region and the so-called short-channel effects appear. These effects increase the OFF current of the device and render the current dependent of the drain voltage. In the most extreme cases, the transistor can no longer be turned off. The effective length of MOSFETs has shrunken from 10 μm in 1971 (Intel® 4004 processor) to 1 μm in the early 1980s, 0.1 μm in 2000, and 10 nm dimensions should be reached around 2015. Short-channel effects become so important in classical, planar MOSFETs with dimensions below 5 nm that new device structures that improve the electrostatic control of the channel by the gate are being explored. These devices are called multi-gate MOSFETs. They basically are silicon nanowires with a gate electrode wrapped around the channel region. This device architecture maximizes the control of the electrostatics in the channel region and allows one to reduce the effective channel length to sub-10 nm dimensions. At those dimensions, quantum transport effects start to kick in, and device simulators need to incorporate the Schrödinger equation to accurately model the transistor's electrical characteristics. Of course, the reduction of transistor size goes hand in hand with the increase of transistors on a chip. The first 32 Gb flash memory chips made using a 40 nm technology were announced in 2006. Each of these chips contains over 32 billion transistors. The number of transistor per chip is literally reaching astronomical proportions, considering that the 400 Gb mark will be reached around the year 2020. When this milestone is reached, there will be as many transistors on a single chip as there are stars in the Milky Way (Figure 12.1).

In 2008, the effective gate length of transistors that are used to fabricate microprocessors is 22 nm, and the thickness of the gate insulator is approximately 1 nm. Fully functional



FIGURE 12.1 Moore's law: number of transistors per chip vs. calendar year.

"gate-all-around" transistors made in a silicon nanowire with a diameter of only 3 nm, that is, roughly the same diameter as a carbon nanotube, were reported in 2006 (Singh et al. 2006). Although these transistors are not formally called "nanoelectronic devices," they are clearly of nanometer dimensions. Strictly speaking, the nanoelectronics era has already begun.

Section 12.2 describes the evolution of the MOS transistor as its structure reaches nanometer dimensions: new materials are used to optimize electrical conductivity and dielectric constant, semiconductor alloying and the introduction of stress are used to increase carrier mobility, and novel transistor geometries are employed to increase the electrostatic control of the channel by the gate.

12.2 Evolution of Silicon Processing: Technology Boosters

In the 1980s, only a handful of elements were used in silicon chips: boron, phosphorus, arsenic, and antimony for doping the silicon, oxygen, and nitrogen for growing or depositing insulators, and aluminum for making interconnections. A few elements, such as hydrogen, argon, chlorine, and fluorine are used during processing in the form of etching plasmas or oxidation-enhancing agents. Sulfur is used in sulfuric acid to clean wafers. In the 1990s, a few more elements were added to the list, such as titanium, cobalt, and nickel, used to form low-resistivity metal silicides, tungsten, used to form vertical interconnects known as "plugs," and bromine, used in a plasma form to etch silicon. The 2000s saw an explosion in the number of elements used in silicon processing: lanthanide (rare earth) metals are being used to form oxides with high dielectric constants (high-k dielectrics), carbon and germanium are used to change the lattice parameter and induce mechanical stresses in silicon, fluorides of noble gases are used in excimer laser lithography, and a variety of metals are used to synthesize compounds that have desirable work functions or Schottky characteristics. Virtually all elements are used, with the notable exception of alkaline metals, which create mobile charges in oxides, and, of course, radioactive elements (Figure 12.2).

The use of new elements to obtain new desirable properties is a technology booster that has made it possible to extend the life of CMOS and reduce dimensions beyond barriers that were previously considered insurmountable. For instance, the reduction


I
II
III
IV
V
VI
VII
O
1
2
3
4
5
6
7
1980s
1990s
2000s
Hydrogen 1 H 1.00794(7)
Helium 2 He 4.002602(2)
Lithium 3 Li 6.941(2)
Beryllium 4 Be 9.012182(3)
Boron 5 B 10.811(7)
Carbon 6 C 12.0107(8)
Nitrogen 7 N 14.00674(7)
Oxygen 8 O 15.9994(3)
Fluorine 9 F 18.9984032(5)
Neon 10 Ne 20.1797(6)
Sodium 11 Na 22.989770(2)
Magnesium 12 Mg 24.305(?)
Aluminium 13 Al 26.981538(2)
Silicon 14 Si 28.0855(3)
Phosphorus 15 P 30.973761(2)
Sulfur 16 S 32.066(6)
Chlorine 17 Cl 35.4527(9)
Argon 18 Ar 39.948(1)
Potasium 19 K 39.0983(1)
Calcium 20 Ca 40.078(4)
Scandium 21 Sc 44.955910(8)
Titanium 22 Ti 47.867(1)
Vanadium 23 V 50.9415(1)
Chromium 24 Cr 51.996(6)
Manganese 25 Mn 54.9380(9)
Iron 26 Fe 55.845(2)
Cobalt 27 Co 58.933200(9)
Nickel 28 Ni 58.6934(2)
Copper 29 Cu 63.546(3)
Zinc 30 Zn 65.39(2)
Gallium 31 Ga 69.723(1)
Germanium 32 Ge 72.61(2)
Arsenic 33 As 74.92160(2)
Selenium 34 Se 78.96(3)
Bromine 35 Br 79.904(1)
Krypton 36 Kr 83.80(1)
Rubidium 37 Rb 85.4678(3)
Strontium 38 Sr 87.62(1)
Yttrium 39 Y 88.90585(2)
Zirconium 40 Zr 91.224(4)
Niobium 41 Nb 92.90638(2)
Molybdenum 42 Mo 95.94(1)
Technetium 43 Tc [98.9063]
Ruthenium 44 Ru 101.07(2)
Rhodium 45 Rh 102.90550(2)
Palladium 46 Pd 106.42(1)
Silver 47 Ag 107.8682(2)
Cadmium 48 Cd 112.411(8)
Indium 49 In 114.818(3)
Tin 50 Sn 118.710(7)
Antimony 51 Sb 121.760(1)
Tellurium 52 Te 127.60(3)
Iodine 53 I 126.90447(3)
Xenon 54 Xe 131.29(2)
Caesium 55 Cs 132.90545(2)
Barium 56 Ba 137.327(7)
Lanthanum 57 La 138.9055(2)
Hafnium 72 Hf 178.49(2)
Tantalum 73 Ta 180.9479(1)
Tungsten 74 W 183.84(1)
Rhnium 75 Re 186.207(1)
Osmium 76 Os 190.23(3)
Iridium 77 Ir 192.217(3)
Platinum 78 Pt 195.078(2)
Gold 79 Au 196.96655(2)
Mercury 80 Hg 200.59(2)
Thallium 81 Th 204.3833(2)
Lead 82 Pb 207.2(1)
Bismuth 83 Bi 208.98038(2)
Polonium 84 Po [208.9824]
Astatine 85 At [209.9871]
Radon 86 Rn [222.0176]
Francium 87 Fr [223.0197]
Radium 88 Ra [220.0254]
Cerium 58 Ce 140.116(1)
Praseodymium 59 Pr 140.90765(2)
Nedodymium 60 Nd 144.24(3)
Promethium 61 Pm [144.9127]
Samarium 62 Sm 150.36(3)
Europium 63 Eu 151.964(1)
Gadolinium 64 Gd 157.25(3)
Terbium 65 Tb 158.92534(2)
Dysprosium 66 Dy 162.50(3)
Holmium 67 Ho 164.93032(2)
Erbium 68 Er 167.26(3)
Thulium 69 Tm 168.93421(2)
Ytterbium 70 Yb 173.04(3)
Lutetium 71 Lu 174.967(1)
Thorium 90 Th 232.038(1)
Protactinium 91 Pa 231.03588(2)
Uranium 92 U 238.0289(1)
Neptunium 93 Np [237.0482]
Plutonium 94 Pu [244.0642]
Americium 95 Am [243.0614]
Curium 96 Cm [247.0703]
Berkelium 97 Bk [247.0703]
Californium 98 Cf [251.0796]
Einsteinium 99 Es [252.0830]
Fermium 100 Fm [257.0951]
Mendelevium 101 Md [258.0984]
Nobelium 102 No [259.1011]
Lawrencium 103 Lr [262.110]

FIGURE 12.2 Elements used in silicon processing.

of gate oxide thickness below 1.5 nm leads to a gate tunnel current that quickly becomes prohibitively high. Replacing silicon dioxide by a high-k dielectrics such as hafnium oxide (HfO_2), which has a dielectric constant of 22 (vs. 3.9 for SiO_2), allows one to increase the thickness of the gate dielectric by a factor 22/3.9 = 5.5 without reducing the gate capacitance (i.e., the current drive of the transistor). The use of new gate dielectrics gave rise to the notion of equivalent oxide thickness, EOT, which is defined by the relationship $\mathrm{EOT} = t_d(\varepsilon_{ox}/\varepsilon_d)$, where t_d is the thickness of the dielectric layer, and ε_{ox} and ε_d are the permittivity of silicon dioxide and the dielectric material, respectively. For example, a 4 nm thick layer of HfO_2 is electrically equivalent to an SiO_2 layer of 0.7 nm.

To improve the properties of transistors, another technology booster is commonly used: stress. Compressive stress increases hole mobility in (110) silicon (i.e., in the direction of current flow of most transistors), while tensile stress increases electron mobility. Mobility can also be modified by using Si:Ge or Si:Ge:C alloys. Compressive stress can be induced in the channel region of a transistor by introducing germanium in the source and drain. The resulting "swelling" of the silicon in the source and drain compresses the channel region situated between them. Tensile stress can readily be obtained by depositing a silicon nitride contact-etch stop layer on top of the device. Mobility (and thus speed) improvement in excess of 50% can be obtained using stress techniques.

The third technology booster deals with the physical geometry of the transistor and is worth being described in detail. As the dimensions of the transistors are shrunk, the close proximity between the source and the drain reduces the ability of the gate electrode to control the potential distribution and the flow of current in the channel region, and undesirable effects, called the "short-channel effects" render MOSFETs inoperable. For all practical purposes, it seems impossible to scale the dimensions of classical "bulk" MOSFETs below 15 nm. If that limitation cannot be overcome, Moore's law would reach an end around year 2012.

Short-channel effects arise when electric field lines from source and drain affect the control of the channel region by the gate. These reduce the threshold voltage V_{TH} according to the expression $V_{TH} = V_{TH\infty} - \Delta V_{TH} - \mathrm{DIBL}$ where $V_{TH\infty}$ is the threshold voltage of a long-channel device, ΔV_{TH} is the "threshold voltage roll-off," due to the sharing of the space charge region underneath the gate between the gate, and the unbiased source and drain junctions, and DIBL is the "drain barrier lowering" which results from the increase of the share of the space charge region related to the drain junction when the drain voltage is increased. Short-channel effects can be minimized by reducing the junction depth and the gate oxide thickness. They can also be minimized by reducing the depletion depth through an increase in channel doping concentration. In modern devices, however, practical limits on the scaling of junction depth and gate oxide thickness lead to a significant increase of short channel effects and excessively large values of DIBL can quickly be reached.

12.3 Nonplanar Multi-Gate Transistors

The field lines in MOS transistors are illustrated graphically in Figure 12.3. In a bulk device (Figure 12.3A), the electric field lines propagate through the depletion regions associated with the junctions. Their influence on the channel can be reduced by increasing the doping concentration in the channel region. In very small devices, unfortunately, the doping concentration becomes very high ($>10^{19}$ cm^{-3}), which degrades carrier mobility. The situation can be improved by making the transistor in a thin film of silicon atop of an insulator. The silicon film is thin enough that it is fully depleted of majority carriers when a gate voltage is applied. Such a device is called fully depleted silicon-on-insulator (FDSOI) MOSFET. In FDSOI devices, most of the field lines propagate through the buried oxide (BOX) before reaching the channel region (Figure 12.3B). Short-channel effects can be further reduced by using a thin buried oxide and an underlying ground plane. In that case, most of the electric field lines from the source and drain terminate on the buried ground plane instead of the channel region (Figure 12.3C). This approach, however, has the inconvenience of increased junction capacitance and body effect (Xiong et al. 2002).

A much more efficient device configuration is obtained by using the double-gate transistor structure. This device structure was first proposed by Sekigawa and Hayashi in 1984 and was shown to reduce threshold voltage roll-off in short-channel devices (Sekigawa and Hayashi 1984). In a double-gate device, both gates are connected together. The electric field lines from source and drain underneath the device terminate



FIGURE 12.3 Encroachment of electric field lines from source and drain on the channel region in different types of MOSFETs: (A) Bulk MOSFET, (B) fully depleted SOI MOSFET, (C) fully depleted SOI MOSFET with thin buried oxide and ground plane, (D) double-gate MOSFET.

on the bottom gate electrode and, therefore, cannot reach the channel region (Figure 12.3D). Only the field lines that propagate through the silicon film itself can encroach on the channel region and degrade short-channel characteristics. This encroachment can be reduced by reducing the silicon film thickness.

Further improvement of short-channel effect control can be achieved by using a gate electrode that is wrapped around three sides of the channel region. The resulting device is known as a triple-gate FET, a term that includes the quantum-wire silicon-on-insulator (SOI) MOSFET (Baie et al. 1995) and the tri-gate MOSFET (Doyle et al. 2003, Kavalieros et al. 2006). The electrostatic integrity of triple-gate MOSFETs can be improved by extending the sidewall portions of the gate electrode to some depth in the buried oxide and underneath the channel region, which results in the formation of a Π-gate MOSFET (Park et al. 2001) or an Ω-gate FET (Yang et al. 2002, Ritzenthaler et al. 2006). The best possible electrostatic of the gate is obtained using "four" gates, or a gate that is wrapped around all sides of the channel region, thereby forming a gate-all-around silicon nanowire transistor (Singh et al. 2006). Using a combination of technology boosters, that is, using a tri-gate device in conjunction with strained silicon, a metal gate and/or high-k dielectric as gate insulator can be used to further enhance the performances of the device (Krivokapic et al. 2003, Andrieu et al. 2006, Kavalieros et al. 2006).

The quality of the electrostatic gate control over the channel can be expressed using a simple expression that can be derived from Poisson's equation (Colinge 2007a,b). It is found that short channel effects are basically nonexistent if the effective channel length is five times larger than that of a value called the "natural length" of the device, and noted λ. The natural length is given by

$$\lambda \cong \sqrt{\frac{\varepsilon_{si}}{n\varepsilon_{ox}} t_{si} t_{ox}}$$

where

t_{si} and t_{ox} are the thickness of the silicon film and the gate dielectric

ε_{si} and ε_{ox} is the permittivity of the silicon and the gate dielectric, respectively

n is the equivalent number of gates (ENG)

The ENG is basically equal to the physical number of sides of the devices covered by a gate and it expresses how efficiently the gate controls the electrostatics in the channel, assuming a square cross section ($W_{si} = t_{si}$). In a single gate device, n is equal to unity, $n = 2$ in a double-gate device, $n = 3$ in a tri-gate configuration, $n = 4$ in a gate-all-around (4 gates device), and $n \approx \pi$ in a π-gate device (Lee et al. 2007). The Ω-gate structure is a π-gate configuration with a larger lateral extension of the gate electrode underneath the channel region. The Ω-gate MOSFET has an effective number of gates larger than a π-gate, but smaller than a 4-gate device. The different configurations are shown in Figure 12.4.



FIGURE 12.4 Different multi-gate MOSFET configurations. 1, double-gate; 2, triple-gate; 3, quadruple-gate or gate-all-around; 4, Π or Ω gate.

Short-channel effects are absent if the effective gate length is larger than seven to eight times the natural length, λ. This behavior is common to all gate configurations. Acceptable level of short-channel effects (DIBL < 50 mV and subthreshold slope <75 mV/decade) are obtained if the effective gate length, L, is smaller than 4λ (Figure 12.5) (Lee et al. 2007). Thus, for instance, to have the same short-channel behavior than a gate-all-around device, a single-gate SOI transistor needs to be made in a silicon film that is twice as thin.



FIGURE 12.5 (A) Drain-induced barrier lowering (DIBL) and (B) subthreshold slope as a function of $L/2\lambda$ for different gate configurations. The gate oxide thickness is equal to 2 nm and the p-type channel doping concentration, N_A, is equal to 10^{18} cm^{-3}.

12.4 The Rise of Quantum Effects

As long as the cross section of the transistor stays above 10 nm classical models using the Poisson equation and drift-diffusion can be used. In smaller devices, however, quantum confinement of the electrons in two directions (perpendicular to the current flow) introduces some fundamental changes in the electronic properties of silicon. It is now necessary to solve the Schrödinger equation in conjunction with the Poisson equation. The density of states (DoS) for electrons in the conduction band in a three-dimensional crystal is a square root function of the electron energy: $\text{DoS} \approx \sqrt{E - E_{co}}$, where E_{co} is the minimum energy in the conduction band. In a two-dimensional crystal, the electrons are confined in one direction of space and free to move in the two other directions. As a result, energy subbands are formed within the conduction band. Each subband corresponds to a discrete energy level $E_{nz} = \hbar^2/2m(\pi n/t_{si})^2$ in the direction of confinement, z, and free motion in the two other directions of space (x and y). In this relationship, m is the mass of the electron, t_{si} is the crystal thickness in the z direction, and $n = 1, 2, 3, \ldots$. Within each subband the density of states is constant and thus independent of the electron energy: $\text{DoS} = (m/\hbar^2\pi t_{si})$ (Ando et al. 1982). In a one-dimensional crystal, where the electrons are confined in two directions of space and free to move in the third direction, energy subbands are formed within the conduction band. Each subband corresponds to a discrete energy level $E_{mnyz} = \hbar^2/2m[(\pi m/W_{si})^2 + (\pi n/t_{si})^2]$ in the directions of confinement, y and z, and free motion in the third directions, x. In this relationship, t_{si} is the crystal thickness in the z direction, W_{si} is the crystal width in the y direction and m and $n = 1, 2, 3, \ldots$. Within each subband the density of states is shaped as a peak as a function of the electron energy: $\text{DoS} \approx (E - E_{nmyz})^{-1/2}$ (Davies 1998). This is illustrated in Figure 12.6, which shows the DoS as a function of energy in a tri-gate transistor with a thickness and width of 5 nm × 5 nm (Figure 12.6A) and a similar device with a thickness and width of 100 nm × 5 nm (Figure 12.6B). The density of states in 3D silicon is shown as well for comparison. In the device with the smaller section the DoS shows a series of peaks, which is characteristic of a one-dimensional system. In the taller device, the peaks gather to form steps of a staircase. Each step of the staircase corresponds to an energy subband of a 2D system. An ideal 2D device would be infinitely tall, while the one simulated here has a thickness of only 100 nm. One nonetheless can observe that the curve tends to a series of steps having each a constant DoS value, which is characteristic of an ideal 2D system (Colinge 2007a,b).



FIGURE 12.6 Density of states (DoS) vs. electron energy in a tri-gate MOSFET with (A) $W_{si} = t_{si} = 5$ nm and (B) $W_{si} = 100$ nm and $t_{si} = 5$ nm.

The confinement of carriers also modifies the spatial distribution of the electrons in the transistor. Let us take the example of a pi-gate device. Classical simulation tools predict that inversion channels form preferentially along the corner edges of the device (Figure 12.7A). A simulation of the same device



FIGURE 12.7 Electron isoconcentration contours in an n-channel pi-gate MOSFET with $t_{si} = W_{si} = 7$ nm and $L = 10$ nm. $V_{GS} = 0.7$ V and $V_{DS} = 0.5$ V. (A) Classical simulation using Poisson and drift-diffusion equations; (B) quantum simulation using Poisson and Schrödinger equations with nonequilibrium Green function formalism.

that includes Schrödinger's equation paints a very different figure: in this case, the electrons are confined to one or two channels located midway between the center of the device and the top corners (Figure 12.7B). Under the particular bias conditions used in Figure 12.7B the device is near saturation and the channel emanating from the source splits into two channels near the drain. Quite clearly, quantum confinement has profound influences on the electron distribution and, therefore, on scattering and transport mechanisms (Kim and Lundstrom 2008).

12.5 Carbon Nanotube Transistors

Carbon (C), silicon (Si), and germanium (Ge) are group IV elements, a description used to indicate that these elements share the same column in the periodic table of the elements. Another way of stating that all three are group IV elements is to say that they share the same configurations for their outer shell electrons. One consequence is that C, Si, and Ge can occur naturally in the diamond structure; see Figure 12.8A. Carbon is also commonly found in the graphite structure consisting of layers of carbon sheets. Each sheet is formed by a monolayer of carbon atoms arranged in a close packed hexagonal pattern. A single layer or carbon sheet in graphite is known as graphene. Carbon nanotubes (CNTs) are graphene strips rolled up into hollow columns or tubes. Carbon in three of its naturally occurring forms, diamond, graphene, and nanotube, is depicted within Figure 12.8. The CNT shown in Figure 12.8C is formed by wrapping a single graphene sheet into itself and onto a cylindrical shape. Nanotubes formed in this way are referred to as single walled carbon nanotubes (SWCNT). Although not difficult to produce, SWCNTs were not observed experimentally until 1991 (Iijima 1991, Bethune et al. 1993). Under typical growth conditions, many concentric tubes can form and this structure is referred to as multi-walled carbon nanotubes (MWCNT). Graphene can be wrapped onto a cylinder in different ways, referred to as the chirality or "handedness" of the nanotube. Specific chiralities give rise to different structures that are categorized as "armchair," "zig-zag," or simply "chiral." The specific structures give rise to different electronic properties for a specific CNT, which may be insulating, semiconducting, or metallic. Selecting the chirality, and hence controlling a CNT's electronic properties, remains a challenge to the growth and subsequent processing for these materials (Ding et al. 2008).

SWCNTs can have diameters of less than 1 nm but they are typically found within a range of 1–3 nm diameters, whereas their lengths can be on the order of centimeters. For a given diameter and chirality, the electronic, thermal, and mechanical properties between two SWCNT are well matched as the atomic structure of a tube is essentially defect free. This perfect atomic structure results in near ballistic transport, i.e., no scattering along the tube length, and is an attractive feature suggesting the use of CNTs for nanoelectronics. Also, the nanotubes are predicted to be able to carry current densities of up to three orders of magnitude larger (×1000) than typical conductors such as copper and aluminium making them attractive for applications



FIGURE 12.8 Carbon in three of its forms: (A) diamond structure, (B) graphene sheet, (C) an example of a carbon nanotube. Note that other forms of carbon exist including amorphous carbon and hollow spheres known as the fullerenes.

in nanoelectronic interconnects. Initially, use for CNTs in electronics focuses on two applications: as "vias" between different levels of metallization (the "wiring" in an integrated circuit) and as the channel material in field effect transistors.

The use of CNT's as a material to fill vias is motivated by the need to have a highly conducting interconnection between two metallization layers, and the fact as circuit dimensions shrink, the cross sections of the vias also decreases. Extremely narrow vias are difficult to fill with conventional material deposition methods. One alternative is to deposit carbon in molecular form, for example, in the form of hollow carbon spheres C_{60} or "buckminsterfullerene." The radius of the C_{60} molecule is on the order of 1 nm and can readily fill vias with cross sections of only a few square nanometers. As the deposited carbon is heated with an appropriate catalytic metal at the base of the via, CNTs grow. The resulting lengths of the CNTs are easily able to span between two metallization layers. However, as mentioned previously, it is presently not possible to control during growth whether a tube will be insulating, semiconducting, or metallic. Hence it is required to grow MWCNTs or bundles of SWCNTs to insure that an appropriate number of metallic tubes are contained within the via. This imposes a constraint on the minimum allowable cross section and introduces a statistical element to via resistances.

CNT field effect transistors (CNTFETs) are transistors fabricated with a CNT as the channel. In the first demonstrations of transistor with a CNT channel, a nanotube is placed from solution or other means onto an oxidized silicon substrate, and a metal layer is deposited and patterned as two metal electrodes. The resulting structure is a CNT spanning the gap between a metal source and drain (Martel et al. 1998, Tans et al. 1998). A cross section of the resulting structure is depicted in Figure 12.9. These original structures required the CNTs to be deposited and located, followed by the deposition of the electrodes. The silicon substrate is used as the gate electrode in a so-called back gate configuration, limiting the performance of the transistors fabricated in this manner. Typical metals used to form the source and drain contacts include but are not limited to Ti, Ni, Al, and Au. For semiconducting nanotubes, the metal/CNT junctions form a Schottky barrier and it is found that holes are injected into the nanotubes resulting in a p-channel MOS transistor. It has been determined that thermal treatments of the structures can be used to generate a shift in the source/drain Fermi levels, believed to be caused by driving oxygen out of the metal, with the result that n-channel CNTFET devices can be fabricated (Appenzeller et al. 2002).



FIGURE 12.9 A CNT transistor in a back gated configuration. In this configuration, the CNT is connected between source and drain contacts and sits on an insulating oxide layer. The silicon substrate is used as a "back gate."

There are now more sophisticated procedures for fabricating CNTFETs including deposited gate oxides and gate electrodes. CNTFETs have been fabricated and compared to Si MOSFETs and it is found that the CNTFETs can have lower switching delays for devices with similar on–off ratios (Javey et al. 2004, Seidel et al. 2005). CNTFET device layout and fabrication has not been fully optimized for high-frequency behavior, but the theoretical predictions for the high velocities achievable for the charge carriers in the CNTs and the measured results for high frequency performance on non-optimized structures indicate that ballistically limited CNTFETS should outperform ballistically limited Si FETs (Guo et al. 2005). However, in order to achieve the benefits of CNTs in large-scale integration schemes, progress is needed in the placement and controlled growth of nanotubes with preselected electronic character.

12.6 Nonclassical Transistor Structures

Classical transistors are based on the drift and diffusion of electrons and holes due to the presence of the electric fields and carrier concentration gradients. Novel transistor concepts based on quantum effects such as tunneling through a barrier, intraband tunneling, or spin polarization, open the possibility of improved performance and new functionality.

12.7 Graphene Ribbon Nanotransistors

As mentioned, one of the obstacles to the use of CNTs in nanoelectronics is the ability to grow nanotubes with a specific electronic character, that is, insulating, semiconducting, or conducting. Recently, the ability to produce single sheets of graphene with linear dimensions of micrometers (or "microns") and with thicknesses of a single carbon atom has been achieved (Novoselov et al. 2004, 2005). In this sense, graphene is a truly "two-dimensional" material and displays unique electron properties—it is the only two-dimensional material with atomic thickness to be isolated to date. Graphene exhibits high conductivity and is being considered for use in high-speed electronic transistors. Due to the unique electronic structure of graphene, charge carriers move through a layer with zero mass and constant velocity. In common with CNTs, there is little scattering from defects. However, an ideal graphene sheet has a zero bandgap limiting its use in conventional electronic devices, although the unusual behavior of charge carriers in the material suggests it may be useful for nonclassical electronics. On the other hand, it is known that interactions of graphene with a semiconducting substrate can induce a bandgap of a fraction of an electron volt resulting in a narrow bandgap semiconductor.

Alternatively, for very narrow sheets or "nanoribbons" of graphene, the sheet edges can be chemically modified or "terminated" by different atoms or chemical groups. This results in a tailoring of the nanoribbon's electronic structure, and the resulting structure is a two-dimensional confined electron gas with lateral confinement lengths of only a few nanometers and a layer confinement length given by a single atom thickness. The material properties of graphene are only now beginning to be explored and transistor structures allowing for the introduction of local gate-tunable potential barriers within a graphene plane have been developed to explore charge transport mechanisms (Huard et al. 2007).

12.8 Sub-*kT/q* Switch

The power dissipated by a switching device is equal to $W = fC(V^2/2)$, where f is the switching frequency, C is the capacitance of the device, and V is the supply voltage. Quite clearly, reducing the supply voltage is the best way to reduce power consumption. Unfortunately, transistors, unlike mechanical switches and reed relays, cannot switch "instantly," and require a finite input voltage variation to switch from the off state to the on state. This behavior is fixed by the energy distribution of the electrons, and is a function of temperature T. The thermal energy is kT/q, where k is the Boltzmann constant, and q is the electron charge. At room temperature, the current in the best possible transistor needs an increase of input voltage of 60 mV to increase a decade (a 10-fold increase). This limit is referred to as the 60 mV/decade subthreshold slope. Thus, if one uses a supply voltage of 60 mV, the on/off current ratio of the transistor will only be equal to 10. In a chip that contains a billion of transistors, it is mandatory to reduce the off current to the subnanoampere level, which requires on/off current ratios in the order of 10^6 and thus a supply voltage of at very least 600 mV (in practice 0.8–1 V to get a decent current drive). Apart from cooling the devices in liquid nitrogen (where they require only 150 mV to achieve an on/off current ratio of 10^6), there is no real practical solution around the problem. Impact ionization in silicon-on-insulator (SOI) transistors has been long known to be capable of reducing the subthreshold slope below 60 mV/decade (Sundaresan and Chen 1990), but impact ionization requires large supply voltages, which defeats the purpose of realizing a low-voltage switch. More promising are devices based on band-to-band tunneling. Here, the variation of current is controlled by the variation of a tunnel barrier rather than by a change in electron concentration, which overcomes the kT/q limit. Such devices have been simulated and made in thin SOI films (Wang et al. 2004) and in carbon nanotubes (Appenzeller et al. 2004) but present technological challenges such as realizing extremely high doping concentrations in very thin films.

12.9 Single-Electron Transistor

The single-electron transistor (SET) comprises a source, a drain, a gate, and a channel region isolated from the source and drain by tunnel junctions. Since this region is usually very small, we will call it a "dot." When a small voltage is applied across a tunnel junction, it behaves like a capacitor, but electrons can tunnel through the barrier. If a constant voltage is applied to a tunnel junction, periodic current pulses, called "Coulomb oscillations," are produced. If the average current through the structure is I, the frequency of the Coulomb oscillations is equal to $f = I/q$, each pulse caused by the tunneling of a single electron through the barrier. Let us now consider two identical tunnel barriers in series (Figure 12.10A) with initial conditions $V_A = V_D = 0$ V. If voltage V_A is decreased, V_D is equal to $V_A/2$, since $C_1 = C_2 \equiv C$, but no current flows through the structure as long as the potential across C_1 is small enough. At the precise moment where the voltage across C_1 becomes large enough for an electron to tunnel through the junction, the voltage across C_1 is equal to $V_{At} - V_{At}/2 = V_{At}/2$. Note that the voltage across C_2 is also equal to $V_{At}/2$. When an electron tunnels into the dot, V_D jumps from $V_{At}/2$ to $V_{At}/2 - qC_2$ (V_A and V_D are negative values). At that moment, the voltage across C_1 drops to $V_{At}/2 + qC$ that is smaller than $V_{At}/2$ in absolute value, which inhibits the tunneling of another electron from the source into the dot. The voltage across C_2, on the other hand, is equal to $V_{At}/2 - qC$ that is larger than $V_{At}/2$ in absolute value, and the electron that was "stored" in the dot can now tunnel through C_2, giving rise to a drain current. In that process, the potential across C_1 is now increased above the critical value for tunneling, and the process repeats itself. The device is thus conducting if the applied voltage is larger, in absolute value, than a critical value, V_{At}. A more detailed analysis concludes that $V_{At} = -q/2C$ (Wasshuber et al. 1997). The region where no current flow is permitted ($V_{At} < V_A < -V_{At}$ with $V_{At} < 0$) is called the "Coulomb gap" (Figure 12.10B).

If we add a gate electrode that is capacitively coupled with the dot, we obtain a single-electron transistor. The dot potential, and thus the current flow, can now be modulated by the gate voltage. Depending on the gate voltage a discrete number of electrons



FIGURE 12.10 (A) Two tunnel barriers, C_1 and C_2, in series. (B) I–V characteristics of a double tunnel barrier structure.



FIGURE 12.11 Current flow in an SET in the V_G–V_A plane. The shadowed areas indicate regions of the V_G–V_A plane where Coulomb blockade prevents current flow and $n = -2, -1, 0, 1, 2$ indicates the number of electrons stored in the dot. Outside these regions, the current increases with the gate voltage.

(or holes, $n = \ldots -2, -1, 0, 1, 2, \ldots$) can be stored in the dot, which produces a series of Coulomb gaps. These can be observed in the V_G–V_A plane as a series of rhombus-shaped regions where no current flows through the device (Figure 12.11).

12.10 Spin Transistor

Another nonclassical device is based on the manipulation of information not by a transfer of charge, but by a transfer or modification of electron spin. "Spintronics," in analogy with "electronics" groups a series of devices that use electron spin instead of charge flow to carry information. One advantage of spin over charge is that spin can be easily manipulated by externally applied magnetic fields, a property that has been utilized in magnetic storage technology for many years (Das Sarma 2001). Spin transistors involve the injection of spin-polarized electrons from an emitter made out of a ferroelectric material into a semiconductor. A ferroelectric gate is used to either conserve the spin or reverse it as the electrons flow through toward the collector. The collector is ferroelectric, with the same spin as the source. The electrons will reach the collector if their original spin has been conserved, but if they are no longer aligned with the direction of magnetization of the collector, no current can pass.

12.11 Molecular Tunnel Junctions

The idea using single molecules as circuit elements along with a proposal for building a molecular rectifier dates back over 30 years (Aviram and Ratner 1974). However, experimental developments to explore the use of single molecules in electronics did not significantly advance until the introduction of scanning probe microscopy (SPM) and the use of break junctions to measure current voltage characteristics for nanometer scale objects. Measurement of currents across single molecules has been investigated for just over a decade (Reed et al. 1997). State of the art photo- and e-beam lithography is not able to reliably produce metal lines with gap spacing of less than 1 nm as needed to contact single molecules. SPM and break junction methods allow for molecules to span gaps of a nanometer or less formed between two metal electrodes. The motivation for using SPM and break junctions to form molecular tunnel junctions is similar, and we briefly describe the formation of a break junction gap used in the investigation of molecular electronics.

In Figure 12.12, the idea behind a break junction is illustrated. Two triangular metal regions are patterned on a polymer substrate and they meet at the "apex" formed by each of the triangular regions. A piezoelectrically activated piston stretches the polymer layer leading to the "breaking" of the metal junction. Since piezoelectric actuation can be controlled on an Ångström-scale, a gap spacing of a few atomic lengths can separate the metallic contacts formed. Many ingenious methods for trapping molecules in the resulting gaps have been devised, but it remains true that the detailed structure of the resulting molecular junctions remains largely undetermined. Given the ability to trap single molecules in the gaps and to measure the current–voltage characteristics for simple tunnel junctions, many experiments and calculations of the currents across molecules have been performed (Cuniberti et al. 2005). A typical atomistic view of a single molecule bonded between two metal electrodes is given in Figure 12.13.

Although there remain discrepancies between different measurements, different theoretical treatments, and between theory and experiment, there is convergence and improvement in the



FIGURE 12.12 Schematic of a break junction experiment: Two triangular metal patterns A are deposited on a polymer substrate B and meet at a "point." The piston C under the substrate is piezoelectrically actuated causing the polymer layer to stretch resulting in the metal contacts to separate producing gaps of less than 1 nm.



FIGURE 12.13 A "ball and stick" representation of the atomic positions and bonding structure of a 4,4′-biphenyldithiol (BPD) molecule bonded between two metal electrodes. Electrode atoms are metals, often gold is used. The "apex" of the electrode is a "linker", in this case a sulphur atom. The two molecular rings are formed by carbon atoms and "saturated" by hydrogen bonds.

reproducibility of the measurements of current–voltage characteristics in the experimental measurements on, for example, simple prototypical molecular junctions such as benzene dithiol (BDT) molecule, which is a benzene ring attached to the metal contacts through sulfur end groups (Reed et al. 1997, Dadosh et al. 2005, Lörtscher et al. 2007, Martin et al. 2008). Current experimental estimates for the resistance for a BDT molecule bonded between gold electrodes range between several MΩ to tens of MΩ. Early theoretical predictions often predicted currents orders of magnitude higher than those experimentally observed, and at least some of the reasons for these discrepancies have been identified and resolved (Delaney and Greer 2004, Lindsay and Ratner 2007). Theoretical predictions are now capable of predicting currents across molecular tunnel junctions within experimental uncertainties (Fagas and Greer 2007).

In Figure 12.14A, a representation of molecular tunnel junction is given in terms of an energy level diagram. On the left and right of the junction, the electrodes are represented as a set of dense energy levels characteristic of metals. Between the two electrodes, a few widely spaced energy levels represent the molecular region. For typical molecules being investigated in tunnel junctions, the molecular energy level spacings are on the order of an electron volt. If we take the Fermi level as the highest energy level in the electrodes, it is seen that in Figure 12.14A, one of the molecular levels lies above the Fermi energy and the other lies below. Hence, the highest energy level on the molecule is unoccupied and the lower level is filled. If a small voltage is applied across the junction, and if it is assumed that little current can flow through the lower occupied level (the electrons on the left and right "block" each other and current cannot flow), then it is seen that electrons leaving the electrodes near the Fermi level have no electronic states to flow across. The molecule in this case represents a barrier to the electrons, which must tunnel from the electrode at a lower voltage to that of a higher voltage. In this case, the current flow is described as nonresonant tunneling. As the voltage V across the tunnel is increased, the energy levels in the left and right electrodes are shifted up and down by $\varepsilon + eV/2$ and $\varepsilon - eV/2$, respectively, with the voltage converted to energy by multiplication of the electronic charge e. This leads to a situation where the unoccupied level on the molecule becomes "resonant" or aligned with an electrode energy level on one side of the molecular junction allowing current to flow freely between the electrodes as shown schematically in Figure 12.14B. In this case, the current across the molecule is due to resonant tunneling. These considerations can be quantified by what is commonly referred to as Landauer's formula (Datta 1997, Imry and Landauer 1999)

$$I = \frac{2e}{h}\int T(\varepsilon)[f_{\mathrm{L}}(\varepsilon) - f_{\mathrm{R}}(\varepsilon)]d\varepsilon,$$

with h Planck's constant. In this picture, states occupied in both the left and right electrodes "block" the current flow. This is described as the difference between the Fermi occupations $[f_{\mathrm{L}}(\varepsilon) - f_{\mathrm{R}}(\varepsilon)]$ for each state of energy ε in the left and right electrodes, respectively. For states that are not blocked, current can flow with transmission $T(\varepsilon)$. In Figure 12.14C, a typical current–voltage (IV) characteristic for a molecular junction is shown. At low voltages, the electrode states on one side of the junction become "unblocked" and current can flow, but there is no molecular state in the voltage window that allows electrons to traverse the molecule. The nonresonant tunneling behavior of the junction then implies a low value for the transmission coefficient and a corresponding small current. As a molecular state enters the voltage window as in Figure 12.14B, the transmission coefficient at energy ε increases substantially and results in a sudden increase in the current as the voltage increases. In Figure 12.14C, the onset of the resonant tunneling regime is clearly marked at the sudden increase in current above and below ±2 V.

Much of the recent work in molecular electronics is focused on describing the physics of current flow on a nanometer scale. There is effort needed to understand how to build switching or logic functions into a single molecule at a level that meets the stringent electronics requirements in terms of reproducibility, integration, and reliability, or indeed to pursue new functions for molecular electronics (Galperin et al. 2008). To explore the use of molecular electronics, efficient simulations of the behavior of molecules embedded into electronic circuits needs to be developed in a manner that allows the device models to be incorporated into circuit design methods (Fransson et al. 2006), but



FIGURE 12.14 (A) An energy level diagram of a molecular tunnel junction. The dense set of electron states on the left and right represent the electrodes; the discrete set of widely separated states represents the molecule in the junction. (B) As a voltage is applied, the electrode states are shifted and the unoccupied molecular energy level enters the voltage window. (C) A representative current–voltage characteristic for a molecular tunnel junction. (After Delaney, P. and Greer, J.C., *Phys. Rev. Lett.*, 93, 036805-1, 2004.)

this work can be characterized as in its infancy. The goal in these approaches is to develop analytical models combining mesoscopic quantum transport equations with information about the molecular junctions determined from electronic structure calculations. Unknown physical parameters are then extracted by fitting to measurements of electron transport across molecular tunnel junctions, for example, for the prototypical case of benzene-1,4-dithiol bonded between gold electrodes. The coupling strength of the molecule attached to the metal electrodes is difficult to measure or calculate, so this parameter is extracted by minimizing the difference between the model predictions and measured data. The resulting model can be used to reproduce the *IV* characteristics for a molecule in a manner similar to that used for conventional compact models of transistors.

12.12 Point Contacts and Conductance Quantum

There is a remarkable consequence of Landauer's formula. In Figure 12.15, a pictorial representation of a break junction is given with a single atom bridging between two electrodes. It has been demonstrated using high-resolution transmission electron microscopy that a single atom can be reproducibly trapped in the break junction just prior to breaking of the junction (Rodrigues et al. 2000). For these junctions, a single atomic state can be in resonance with the electrodes and the transmission can be near ideal with $T \approx 1$ within the applied voltage window. Landauer's formula predicts the conductance in this case to be $g = \partial I/\partial V \approx 2e^2/h$, corresponding to a resistance of approximately 12.9 kΩ. This result indicates for a single quantum "channel" with perfectly ballistic transmission $T = 1$, there is an intrinsic resistance known as the "contact resistance." This resistance cannot be eliminated for a quantum conduction channel and in this sense, resistance is quantized per ballistic conducting channel. For metals with many parallel conducting channels, this intrinsically quantum effect is not noticeable. However for quantum scale conductors with a few or only one conducting channel, the contact resistance is significant and has been observed both in low-dimensional semiconductor devices (van Wees et al. 1988, Wharam et al. 1988) and for atomic point contacts (Scheer et al. 1998).



FIGURE 12.15 A "ball and stick" representation of quantum point contact. In this case, a single atom is located at the center of the junction.

12.13 Atomic-Scale Technology Computer-Aided Design

The continued down scaling of MOSFETs and the exploration of nonclassical transistor structures impose new requirements for technology computer-aided design (TCAD). For the "end-of-the-roadmap" silicon devices and for transistors relying on quantum mechanical effects for their operation, explicit atomic-scale structures of the devices and the ability to predict quantum behavior needs to be included in TCAD tools. Methods from computational chemistry and physics are being coupled to TCAD tools for design at the atomic and molecular length scales, and this represents a true change in simulation philosophy. Microelectronics device design was incremental for much of the period 1960–2000; few revolutionary technology changes were needed. Hence, parameterizations and simulations optimized for a production technology generation were adequate to predict properties for the design of the next technology generation. As the new technology generation was developed, re-parameterizations of the models were then made to refine and optimize transistors and circuits. In this way, technology design and manufacture leapfrogged one another forward. Now, the fields of molecular electronics, quantum computation, as well as classical alternatives are actively under investigation as means to overcome anticipated technology limitations. Hence, the nature of TCAD simulation is changing: instead of predicting incremental changes to existing technologies, new TCAD tools must be able to assess proposed candidates from a large set of replacement technologies in order to remain useful. And, useful has a rigorous definition in this field—TCAD simulation must be capable of reliably assessing new technologies, be cheaper and faster than design-by-trial strategies, with the constraints including design cycle time, cost, and accuracy.

The technology simulation community is not starting from scratch in terms of atomic scale and quantum computations. The development of algorithms and programs dates back to early days of quantum theory (Hartree 1928). However, the development of algorithms and programs were not written with nanoelectronic TCAD needs in mind and with means for treating open quantum systems, that is, systems that exchange charge or energy with their environment as needed to describe transistors and other circuit elements driven by voltage sources are currently under development.

In Figure 12.16, a simple graphical representation of Moore's law deduced from the minimum transistor feature size is compared to the system sizes accessible to atomistic and ab initio calculations. Clearly increased computing power and memory resources have allowed for computation and simulation at larger and larger sizes. In the diagram, we have differentiated between ab initio calculations, which directly solve the electronic Schrödinger equation, and much less accurate but computationally cheaper atomistic simulations. Atomistic simulations rely on simple empirical models of atom–atom interactions, but cannot deliver any information about the electronic structure of materials. They require, however, many orders of magnitude



FIGURE 12.16 Convergence of atomistic and quantum mechanical simulations and nanoelectronics length scales.

less computational power for their description of matter and their use in the pharmaceutical and chemical industries is widespread. As a crude rule of thumb, accurate ab initio electronic structure codes can treat systems with a few hundred atoms to thousands of atoms, whereas atomistic methods can handle system sizes up to several tens of millions of atoms. Within a multiscale approach, atomistic simulations can be used to model aspects of the growth and processing of nanoscale structures. The electronic structure and charge transport in these systems can then be determined from ab initio techniques.

12.14 Conclusion

The size of transistors produced during the last 30 years by the microelectronics industry has shrunk by a factor of a hundred, from a few micrometers to a few tens of nanometers. As the limits of classical planar architecture are being reached, new transistor structures based on nanowire geometries are used to push the scaling down to nanometer dimensions. Quantum effects then begin to emerge, and the electrical characteristics of transistors no longer follow the predictions of classical simulation tools. The new behaviors imposed by quantum mechanics, on the other hand, pave the way for a new generation of devices with quantized current transport and nonconventional switching mechanisms.

References

Ando, T., Fowler, A.B., and Stern, F. 1982. Electronic properties of two-dimensional systems. *Review of Modern Physics* 54:437–672.

Andrieu, F., Dupré, C., Rochette, F., Faynot, O., Tosti, L., Buj, C., Rouchouze, E., Cassé, M., Ghyselen, B., Cayrefourcq, I., Brévard, L., Allain, F., Barbé, J.C., Cluzel, J., Vandooren, A., Denorme, S., Ernst, T., Fenouillet-Béranger, C., Jahan, C., Lafond, D., Dansas, H., Previtali, B., Colonna, J.P., Grampeix, H., Gaud, P., Mazuré, C., and Deleonibus, S. 2006. 25 nm short and narrow strained FDSOI with TiN/HfO$_2$ gate stack. *Symposium on VLSI Technology*, 16.4, Honolulu, HI.

Appenzeller, J., Knoch, J., Martel, R., Derycke, V., Wind, S.J., and Avouris, P. 2002. Carbon nanotube electronics. *IEEE Transactions on Nanotechnology* 1(4):84–89.

Appenzeller, J., Lin, Y.M., Knoch, J., and Avouris, P. 2004. Band-to-band tunneling in carbon nanotube field-effect transistors. *Physical Review Letters* 93(19):196805-1–196805-4.

Aviram, A. and Ratner, M.A. 1974. Molecular rectifiers. *Chemical Physics Letters* 29:277–283.

Baie, X., Colinge, J.P., Bayot, V., and Grivei, E. 1995. Quantum-wire effects in thin and narrow SOI MOSFETs. *Proceedings of the IEEE International SOI Conference*, Tucson, AZ, pp. 66–67.

Bethune, D.S., Klang, M.S., de Vries, M.S., Gorman, G., Savoy, R., Vazquez, J., and Beyers, R. 1993. Cobalt-catalysed growth of carbon nanotubes with single-atomic-layer walls. *Nature* 363:605–607.

Colinge, J.P. 2007a. Quantum-wire effects in trigate SOI MOSFETs. *Solid-State Electronics* 51(9):1153–1160.

Colinge, J.P. 2007b. *FinFETs and Other Multi-Gate Transistors*. Springer, Berlin, Germany.

Cuniberti, G., Fagas, G., and Richter, K. (eds.) 2005. *Introducing Molecular Electronics*, Lecture Notes in Physics. Springer, Berlin, Germany.

Dadosh, T., Gordin, Y., Krahne, R., Khivrich, I., Mahalu, D., Frydman, V., Sperling, J., Yacoby, A., and Bar-Joseph, I. 2005. Measurement of the conductance of single conjugated molecules. *Nature* 436:677–680.

Das Sarma, S. 2001. Spintronics. *American Scientist* 89:516–523.

Datta, S. 1997. *Electronic Transport in Mesoscopic Systems*. Cambridge University Press, Cambridge, U.K.

Davies, J.H. 1998. *The Physics of Low-dimensional Devices*. Cambridge University Press, Cambridge, U.K.

Delaney, P. and Greer, J.C. 2004. Correlated electron transport for molecular electronics. *Physical Review Letters* 93:036805-1–036805-4.

Ding, F., Larsson, P., Larsson, J.A., Ahuja, R., Duan, H., Rosen, A., and Bolton, K. 2008. The importance of strong carbon-metal adhesion for catalytic nucleation of single-wall carbon nanotubes. *Nano Letters* 8:463–468.

Doyle, B.S., Datta, S., Doczy, M., Jin, B., Kavalieros, J., Linton, T., Murthy, A., Rios, R., and Chau, R. 2003. High performance fully-depleted tri-gate CMOS transistors. *IEEE Electron Device Letters* 24(4):263–265.

Fagas, G. and Greer, J.C. 2007. Tunnelling in alkanes anchored to gold electrodes via amine end groups. *Nanotechnology* 18:424010-1–424010-4.

Fransson, J., Bengone, O.M., Larsson, J.A., and Greer, J.C. 2006. A physical compact model for electron transport across single molecules. *IEEE Nanotechnology* 5(6):745–749.

Galperin, M., Ratner, M.A., Nitzan, A., and Troisi, A. 2008. Nuclear coupling and polarization in molecular transport: Beyond tunneling to function. *Science* 319(5866):1056–1060.

Guo, J., Hasan, S., Javey, A., Bosman, G., and Lundstrom, M. 2005. Assessment of high frequency performance of carbon nanotube transistors. *IEEE Transactions on Nanotechnology* 4(6):715–721.

Hartree, D.R. 1928. The wave mechanics of an atom with a non-Coulomb central field. *Proceedings of the Cambridge Philosophical Society* 24:89–132.

Huard, B., Sulpizio, J.A., Stander, N., Todd, K., Yang, B., and Goldhaber-Gordon, D. 2007. Transport measurements across a tunable potential barrier in graphene. *Physical Review Letters* 98:236803-1–236803-4.

Iijima, S. 1991. Helical microtubules of graphitic carbon. *Nature* 354(6348):56–58.

Imry, Y. and Landauer, R. 1999. Conductance viewed as transmission. *Review of Modern Physics* 71:S306–S312.

Javey, A., Guo, J., Farmer, D.B., Wang, Q., Wang, D., Gordon, R.G., Lundstrom, M., and Daih. 2004. Carbon nanotube field-effect transistors with integrated ohmic contacts and high-? gate dielectrics. *Nano Letters* 4(3):447–450.

Kavalieros, J., Doyle, B., Datta, S., Dewey, G., Doczy, M., Jin, B., Lionberger, D., Metz, M., Rachmady, W., Radosavljevic, M., Shah, U., Zelick, N., and Chau, R. 2006. Tri-gate transistor architecture with high-k gate dielectrics, metal gates and strain engineering. *Symposium on VLSI Technology* 7.1, Honolulu, HI.

Kim, R. and Lundstrom, M. 2008. Characteristic features of 1-D ballistic transport in nanowire MOSFETs. *IEEE Transactions on Nanotechnology* 7(6):787–794.

Krivokapic, Z., Tabery, C., Maszara, W., Xiang, Q., and Lin, M.R. 2003. High-.performance 45-nm CMOS technology with 20-nm multi-gate devices. *Extended Abstracts of the International Conference on Solid State Devices and Materials* (*SSDM*), Nagoya, Japan, pp. 760–761.

Lee, C.W., Yun, S.R.N., Yu, C.G., Park, J.T., and Colinge, J.P. 2007. Device design guidelines for nano-scale MuGFETs. *Solid-State Electronics* 51(3):505–510.

Lindsay, S.M. and Ratner, M.A. 2007. Molecular transport junctions: Clearing mists. *Advanced Materials* 19:23–31.

Lörtscher, E., Weber, H.B., and Riel, H. 2007. Statistical approach to investigating transport through single molecules. *Physical Review Letters* 98:176807-1–176807-4.

Martel, R., Schmidt, T., Shea, H.R., Hertel, T., and Avouris, P. 1998. Single- and multi-wall carbon nanotube field-effect transistors. *Applied Physics Letters* 73:2447–2449.

Martin, C.A., Ding, D., van der Zant, H.S.J., and van Ruitenbeek, J.M. 2008. Lithographic mechanical break junctions for single-molecule measurements in vacuum: Possibilities and limitations. *New Journal of Physics* 10:065008-1–065008-18.

Moore, G. 1965. Cramming more components onto integrated circuits. *Electronics* 38(8):114–117.

Novoselov, K.S., Geim, A.K., Morozov, S.V., Jiang, D., Zhang, Y., Dubonos, S.V., Grigorieva, I.V., and Firsov, A.A. 2004. Electric field effect in atomically thin carbon films. *Science* 306:666–669.

Novoselov, K.S., Jiang, D., Schedin, F., Booth, T.J., Khotkevich, V.V., Morozov, S.V., and Geim, A.K. 2005. Two-dimensional atomic crystals. *Proceedings of the National Academy of Sciences USA* 102:10451–10453.

Park, J.T., Colinge, J.P., and Diaz, C.H. 2001. Pi-gate SOI MOSFET. *IEEE Electron Device Letters* 22:405–406.

Reed, M.A., Zhou, C., Muller, C.J., Burgin, T.P., and Tour, J.M. 1997. Conductance of a molecular junction. *Science* 278:252–254.

Ritzenthaler, R., Dupré, C., Mescot, X., Faynot, O., Ernst, T., Barbé, J.C., Jahan, C., Brévard, L., Andrieu, F., Deleonibus, S., and Cristoloveanu, S. 2006. Mobility behavior in narrow Ω-gate FET devices. *Proceedings of the IEEE International SOI Conference*, Niagara falls, ON, pp. 77–78.

Rodrigues, V., Fuhrer, T., and Ugarte, D. 2000. Signature of atomic structure in the quantum conductance of gold nanowires. *Physical Review Letters* 85:4124–4127.

Scheer, E., Agraït, N., Cuevas, J.C., Yeyati, A.L., Ludoph, B., Martín-Rodero, A., Bollinger, G.R., van Ruitenbeek, J.M., and Urbina, C. 1998. The signature of chemical valence in the electrical conduction through a single atom contact. *Nature* 394:154–157.

Seidel, R.V., Gvaham, A.P., Kretz, J., Rajasekharan, B., Duesberg, G.S., Liebau, M., Unger, E., Kreupl, F., and Hoenlein, W. 2005. Sub-20nm short channel carbon nanotube transistors. *Nano Letters* 5(1):147–150.

Sekigawa, T. and Hayashi, Y. 1984. Calculated threshold-voltage characteristics of an XMOS transistor having an additional bottom gate. *Solid-State Electronics* 27:827–829.

Singh, N., Agarwal, A., Bera, L.K., Liow, T.Y., Yang, R., Rustagi, S.C., Tung, C.H., Kumar, R., Lo, G.Q., Balasubramanian, N., and Kwong, D.L. 2006. High-performance fully depleted silicon nanowire (diameter<5 nm) gate-all-around CMOS devices. *IEEE Electron Device Letters* 27(5):383–386.

Sundaresan, R. and Chen, C.E. 1990. SIMOX devices and circuits. *Electrochemical Society Proceedings* 90(6):437–454.

Tans, S.J., Verschueren, A.R.M., and Dekker, C. 1998. Room-temperature transistor based on a single carbon nanotube. *Nature* 393:49–52.

Van Wees, B.J., van Houten, H., Beenakker, C.W.J., Williamson, J.G., Kouwenhoven, L.P., van der Marel, D., and Foxon, C.T. 1988. Quantized conductance of point contacts in a two-dimensional electron gas. *Physical Review Letters* 60:848–850.

Wang, P.F., Hilsenbeck, K., Nirschl, T., Oswald, M., Stepper, C., Weis, M., Schmitt-Landsiedel, D., and Hansch, W. 2004. Complementary tunneling transistor for low power application. *Solid-State Electronics* 48:2281–2286.

Wasshuber, C., Kosina, H., and Selberherr, S. 1997. SIMON-A simulator for single-electron tunnel devices and circuits. *IEEE Transactions on Computer-Aided Design of Integrated Circuits and Systems* 16(9):937–944.

Wharam, D.A., Thornton, T.J., Newbury, R., Pepper, M., Ahmed, H., Frost, J.E.F., Hasko, D.G., Peacock, D.C., Ritchie, D.A., and Jones, G.A.C. 1988. One-dimensional transport and the quantisation of the ballistic resistance. *Journal of Physics C* 21:L209–L214.

Xiong, W., Ramkumar, K., Jamg, S.J., Park, J.T., and Colinge, J.P. 2002. Self-aligned ground-plane FDSOI MOSFET. *Proceedings of the IEEE International SOI Conference*, San Jose, CA, pp. 23–24.

Yang, F.L., Chen, H.Y., Cheng, F.C., Huang, C.C., Chang, C.Y., Chiu, H.K., Lee, C.C., Chen, C.C., Huang, H.T., Chen, C.J., Tao, H.J., Yeo, Y.C., Liang, M.S., and Hu, C. 2002. 25 nm CMOS Omega FETs. *Technical Digest of IEDM*, New York, pp. 255–258.

13

Metal Nanolayer-Base Transistor

André Avelino Pasa
Universidade Federal de Santa Catarina

13.1 Introduction **13**-1
13.2 Band Diagram **13**-1
13.3 *J*–*V* Characteristic **13**-3
13.4 Fabrication **13**-4
References **13**-7

13.1 Introduction

A metal nanolayer-base transistor is a transistor with a metallic layer with nanometric thickness sandwiched between two semiconductor layers. The metal forms the base and the semiconductors the emitter and the collector. This device was proposed and demonstrated at the beginning of the 1960s by Rose (1960), Geppert (1962), and Atalla and Kahng (1962). The main characteristic of the device for applied purposes was the expected high operation frequency when compared to bipolar transistors with low resistance and short transit times in the thin metallic nanolayer base.

13.2 Band Diagram

The mechanism of the metal-base transistor can be understood by drawing the energy band diagram of the sandwich structure with emphasis on the interfaces. The contact between a metal and a semiconductor forms a metal–semiconductor (MS) junction that has a special electric characteristic described independently by Schottky (1938) and Mott (1938). These junctions have a rectifying electrical behavior due to the presence of a potential barrier at the interface between the two materials. In Figure 13.1, we illustrate two different ways of performing MS contacts. The most common one at the time when metal-base transistors (MBT) emerged was by pressing a metallic tip against the surface of the semiconductor (a), known as the point contact, and the most reliable one used currently (b), obtained by depositing a metallic layer on top of a semiconductor substrate.

The band diagram of an MS contact is displayed in Figure 13.2a. The metal, represented by the energy of the Fermi level (E_{Fm}) and the semiconductor, represented by the bottom of the conduction band (E_{C}), and the top of the valence band (E_{V}), are in contact and under equilibrium conditions. The Fermi level in the semiconductor side (E_{FS}) is close to E_{C}, since we are considering an n-type material. In this case, the barrier at the interface ($q\phi_{\mathrm{b}}$), named the Schottky barrier, is due to the flow of electrons from the semiconductor to the metal to attain the equilibrium conditions, i.e., $E_{\mathrm{FM}} - E_{\mathrm{FS}}$ along the two materials corresponding in solid-state physics to the condition of the same chemical potential through the whole system. Electrons flow to the metal instead of from the metal to the semiconductor, since we are considering the work function of the metal ($q\phi_{\mathrm{m}}$) to be higher than the semiconductor affinity ($q\chi_{\mathrm{S}}$). The band banding in the semiconductor is then a consequence of the flow of electrons and leads to a depletion region and the appearance of an electric field close to the interface. The field is contrary to that flow and reaches its maximum intensity in the equilibrium condition. Figure 13.2b and c display the band banding conditions under direct and reversed bias, respectively. Electrons at E_{FM} have to overcome the Schottky barrier with a height of $q\phi_{\mathrm{b}}$, which is independent of the applied voltage, to cross the interface. On the other hand, electrons at the conduction band of the semiconductor are favored to flow to the metal by applying a forward bias as shown in Figure 13.2b. Due to the fact that the flow from the semiconductor to the metal is facilitated by the external voltage V, the MS interface acts as a diode rectifying the current, and the device is named Schottky diode. From the point of view of fundamental physics, this device is known as a hot-carrier diode. The carriers are injected with energy higher than the energy of the Fermi level. In the case of silicon, the most used semiconductor in the microelectronic industry, the height of the Schottky barrier varies in the range of 0.5 and 1.0 eV, this being the energy in excess of the carriers entering the metal. In Figure 13.2c, the diode is a reverse bias and no flux of charge is expected from both sides of the barrier. However, in real devices, a reverse current is always observed with a magnitude depending on the thermal ejection of carriers over the barrier, and most important, on the existence of defects that locally control the transport mechanism. Band diagrams similar to the ones shown in Figure 13.2 can also be drawn for p-type semiconductors.



FIGURE 13.1 (a) Metal semiconductor contact obtained by pressing a metallic tip against the semiconductor surface (point contact). (b) MS contact formed by depositing a metallic layer on the surface of a semiconducting substrate.



FIGURE 13.2 (a) Energy band diagram of the MS contact with a Schottky barrier at the interface. (b) and (c) Shift of conduction and valence bands of the semiconductor under influence of an external bias. The quantities indicated in the figure are: E_{FM}, Fermi level of the metal; $q\phi_b$, Schottky barrier; $q\chi_s$, electron affinity; $q\psi_{bi}$, built in potential; E_{FS}, Fermi level of the semiconductor; E_C, energy of the bottom of the conduction band; E_V, energy of the top of the valence band; E_{vacuum}, energy of the vacuum level; and q is just the electronic charge.

The current density J across an MS interface under the application of the external bias voltage V is described by the thermionic emission (TE) theory (Rhoderick and Williams 1988), which depicts the transport of carriers injected over the interface barrier $q\phi_b$, given by

$$J = J_o e^{\frac{qV}{nkT}} \left[1 - e^{\frac{-qV}{kT}} \right], \tag{13.1}$$

where
n is the ideality factor
k Boltzmann's constant
T the absolute temperature
J_o the saturation current density defined as

$$J_o = A^* T^2 e^{\frac{-q\phi_b}{kT}}, \tag{13.2}$$

where A^* is Richardson's constant, given by

$$A^* = \frac{4\pi q m^* k^2}{h^3}, \tag{13.3}$$

where
m^* is the effective mass
h is Planck's constant

For silicon, A^* is equal to 32 A/cm^2 K^2 for the p-type and 110 A/cm^2 K^2 for the n-type. The ideality factor n, equal to 1 corresponds to the case when the TE theory ideally describes the transport of charge over the potential barrier. For $n > 1$ are represented situations with deviations from the ideal case and are originated by the presence of, for example, inhomogeneities and interfacial layers.

Figure 13.3a shows the characteristic J–V curve of a Co/Si-n Schottky diode. The Co layer with a thickness of 80 nm was electrodeposited and the contact area was 0.5 cm^2. The curve follows the expected behavior of the TE theory and barrier heights and ideality factors of about 0.6 eV and 1.2, respectively, were obtained for this system (Zandonay et al. 2008). Figure 13.3b shows the characteristic of the diode when the logarithm function is applied to absolute values of current, i.e., the logarithm function was applied to the positive current values in the positive voltage range and to the negative current values, multiplied by −1, in the negative voltage range. This typical representation of the diode response is easily obtained through the observation of the magnitude of the reverse current and the linear interval of the forward current that follows the exponential dependence on the voltage predicted by the TE theory.



FIGURE 13.3 Linear (a) and logarithm (b) representation of the J–V electric characteristic of a Co/Si-n electrodeposited Schottky diode with a thickness of Co of about 80 nm and $q\phi_b$ = 0.60 eV and n = 1.2. (After Zandonay, R. et al., *ECS Trans.*, 14, 359, 2008.)



FIGURE 13.4 Band diagram of the MBT consisting of a semiconductor-metal-semiconductor planar trilayer structure under equilibrium conditions (a) and under external bias (b). Emitter-base diode forward biased and collector-base diode reverse biased. V_{CB} and V_{EB} are the applied voltages at the collector and the emitter relative to the base, $q\phi_{bE}$ and $q\phi_{bC}$ are the Schottky barrier heights at the emitter-base and collector-base interfaces, respectively, and t_B is the thickness of the base.

In an MBT, the metal layer of the base forms two Schottky barriers, as shown in Figure 13.4a, one with the emitter, and one with the collector. The barriers are placed face-to-face and can be polarized independently by applying voltages to the emitter and collector terminals relative to the base terminal. The forward operation mode of the transistor consists in applying a forward voltage at the emitter-base diode, to inject carriers into the base, and a reverse bias at the collector-base diode, in order to assist the collection of carriers crossing the base, as displayed in Figure 13.4b.

For the case of n-type semiconductors, as illustrated in Figure 13.4, the electrons ejected by the emitter have to have enough energy to cross the base and overcome the barrier at collector side. In order to have current gains close to 1, the collector barrier height should be lower than the barrier height at the emitter side and the base thickness should be relatively thin. In other words, the number of electrons that reaches the collector is reduced by processes occurring when traveling from the emitter to the collector through the base, which could be expressed in general as

$$J_C = \alpha_T J_E, \tag{13.4}$$

where α_T is the total transport factor of hot electrons that takes into account a series of individual factors, such as electron scattering in the metal base, quantum-mechanical reflection at the base-collector interface, and emission and collection efficiency due to interaction in the emitter and the collector interfaces (Sze 1969). All these processes contribute toward reducing the current that is measured in the collector-base circuit. Specifically, the base-transport factor, α_B, responsible for the scattering of the electrons in the base by collisions with electrons, phonons, impurities, and defects, can be written as

$$\alpha_B = e^{-\frac{t_B}{\lambda}}, \tag{13.5}$$

where λ is the mean free path of the injected hot electrons into the base. This dependency indicates that α_B, and consequently α_T, is strongly affected by the base thickness. Typical values for λ are a few tens of nanometers as $\lambda = 22$ nm observed for electrons with a 1 eV crossing Au layer sandwiched between Si-n and Ge-n at room temperature (Sze 1969).

13.3 *J–V* Characteristic

Similarly to bipolar transistors, the MBTs can be characterized electrically by measuring the performance of the device in the three different configurations: common-base, common-emitter, and common-collector. The common-base configuration is the most commonly used to obtain the electrical response of the transistor and to determine the common-base current gain α_o, defined by the ratio between collector– emitter current densities, i.e.,

$$\alpha_o = \frac{J_C}{J_E} = \alpha_T - \frac{J_{reverse}}{J_E}, \tag{13.6}$$

where $J_{reverse}$ is the density of the current of the reverse biased collector-base diode. When the ratio between the reverse and the emitter current densities is considerable low, it can be neglected and $\alpha_o \approx \alpha_T$. In the common-base configuration, a fixed current is applied to the emitter and the collector-current density J_C is measured as a function of the collector-to-base voltage (V_{CB}). Figure 13.5 shows the vertical structure of the MBT, with emitter, base, and collector, in planar technology, and the circuit used for common-base measurements.

The transistor action for the common-base measurement corresponds to collector currents weakly dependent on the applied voltage between the collector and the base and strongly dependent on the emitter current. Figure 13.6 shows the typical response of a metal-base transistor for four different emitter currents densities, J_{E1} to J_{E4} with increasing values, showing a small increase of the collector current with the increase of the collector-to-base voltage, and the defined stages for the collector current that are determined by the intensity of the emitter current. The weak dependence of J_C on V_{CB} is attributed to a barrier height lowering with the reverse applied voltage at the collector Schottky diode



FIGURE 13.5 Schematic representation of a vertical structure with the emitter-base-collector of an MBT in planar technology. The bias circuit for common-base characterization is also shown. I_E is the current source connected in series to the emitter-base circuit and *A* is the current meter connected in series to the collector-base circuit that measures I_C, the collector current, as a function of voltage V_{CB} between the collector and the base.



FIGURE 13.6 Typical common-base characteristic of an n-metal-n transistor with collector current levels determined by the intensity of the emitter current and weakly dependent on the collector-to-base reverse voltage.

(Sze 1969), and for this reason, the current gain has to be calculated for a fixed voltage as shown in the figure, where

$$\alpha_o = \frac{J_{C2}}{J_{E2}} - \frac{J_{reverse}}{J_{E2}}. \tag{13.7}$$

13.4 Fabrication

The main concern related to metal-base transistors is the fabrication process. It is necessary to prepare a structure with metal-semiconductor interfaces that have Schottky barriers and reduced losses for the electrons ejected by the emitter. Electronic devices are usually based on single crystal semiconductors and the growth of semiconductor epitaxial layers on top of metals is a difficult issue, requiring sophisticated methods. Epitaxial growth is a process whereby the atoms reaching the surface are deposited following the same atomic structure (order) of the crystalline substrate. Molecular beam epitaxy (MBE), liquid phase epitaxy (LPE), and chemical vapor deposition (CVD) are techniques that allow the growth of monolithic structures. This kind of process increases the production cost and reduces possibilities of large-scale integration (circuits with a large density of devices), requiring ultrahigh vacuum deposition or high temperature fabrication steps.

The pioneering work of Geppert (1962) and Atalla and Kahng (1962) were performed by depositing metal layers (base) on top of single crystal semiconductor substrates (collector). The emitter was a crystalline semiconductor piece with a tip or a blunt corner pressed against the metallic layer (point contact). Geppert electrodeposited Cu on n-Ge and contacted with an n-Ge probe. Atalla and Kahng deposited Au thin films with thicknesses of 10 nm on n-Ge and the point contact was n-Si. A few years later, Kanô (1964) used a vacuum-evaporated emitter, CdSe, an Au thin layer as base, and Ge as the collector to fabricate a structure with a Schottky barrier height higher at the emitter (0.75 eV) and lower at the collector (0.45 eV). However, in all these cases described above, the achieved current gains were not more than 0.5, and others factors, such as reproducibility and rough interfaces limited the performance of the device for applications.

To improve the quality of the interfaces, especially since one of the main issues to be worked out was the point contacts with a low yield of reproducibility, different approaches were tried. Brodsky and Deneuville (Deneuville and Brodsky 1978) grew amorphous semiconductor layers to surmount the need for monolithic structures. The glow discharge-deposition process was used for depositing hydrogenated silicon carbide (a-CSi:H) as the emitter, and hydrogenated silicon (a-Si:H) as the collector. The base was a Pt layer. The barrier heights at the emitter and the collector were 0.96 and 0.75 eV, respectively. Though the fact that the heights are adequate for the collection process, the common-base current gain measured was not higher than 0.1.

Moreover, no significant increase in the transfer ratio was observed by growing the semiconductor-metal-semiconductor (SMS) structure using the epitaxy techniques mentioned above. Rosencher et al. (1984) and Hensel et al. (1985) grew monolithic Si-CoSi$_2$-Si structures and obtained transistors with characteristic similar to the one shown in Figure 13.6. The monolithic atomic structure obtained by these authors is shown in Figure 13.7. CoSi$_2$ is a metallic disilicide with a resistivity comparable to metals and with a small lattice mismatch (~1.4%) with Si allowing the epitaxial growth.

Tung et al. (1986) observed high values of α_o, as high as 0.95, with MBTs grown by MBE. However, they also detected the existence of pinholes in the base that directly connected the emitter to the collector. The electron transfer was in this case mainly through the small openings in the base layer, where the barrier height is lower than the Schottky height. This mechanism of transport is the operation principle behind the permeable-base



FIGURE 13.7 Atomic arrangement of the monocrystalline Si-$CoSi_2$-Si structure.

transistors (PMT), which incorporate a metal grid as base between the emitter and the collector (Bozler and Alley 1980). Even though the Si/$CoSi_2$/Si MBT showed a useful and a controllable current gain, its fabrication remained a challenge, requiring ultrahigh vacuum deposition and annealing.

The presence of pinholes in the base needs to be checked in all cases in order to see if the measured α_o is not a misleading interpretation of the direct contact between the emitter and the collector through the pinholes. A checking procedure was suggested by Rosencher et al. (1986) where the voltage between the emitter and the base is measured as a function of the collector-to-base voltage. The absence of pinholes leads to an independent voltage at the emitter-base junction, which is screened by the compact metal of the base.

A very significant innovation concerning metal nanolayer-base transistors was achieved with the advent of the spin transistor. Monsma et al. (1995) fabricated a metal-base transistor with a magnetic multilayer at the base. Magnetic multilayers are composed of ferromagnetic (F) and non-ferromagnetic (N) layers, with individual layer thicknesses of a few nanometers, and show electrical resistance depending on the applied magnetic field, a phenomenon known as giant magnetoresistance (GMR) (Baibich et al. 1988). Figure 13.8a shows the usual band structure of a metal-base transistor with the magnetic multilayer (MM) represented at the base. The difference is that in this case, the base-transport factor will also depend on the applied magnetic field, i.e., $\alpha_B = \alpha_B(H)$. For a ferromagnetic configuration of the multilayer, represented by (↑↑) and indicating the same magnetization direction (parallel) for the ferromagnetic layers, the magnetoresistance (MR) is low, and for anti-ferromagnetic, with the non-ferromagnetic layers aligned anti-parallel (↑↓), the MR is high. These two MR levels correspond to distinct α_B, $\alpha_B(\uparrow\uparrow) < \alpha_B(\uparrow\uparrow)$, since lower values of MR correspond to less scattering of the electrons when crossing the base, and consequently higher values of collector current. Figure 13.8b shows a common-base characteristic curve of a spin transistor for both configurations of the MM, with the excess current for the ferromagnetic configuration named magnetocurrent, quantified as the difference $\Delta J = J(\uparrow\uparrow) - J(\uparrow\downarrow)$. The magnetocurrent effect is calculated as $MC(\%) = 100\ [(J(\uparrow\uparrow) - J(\uparrow\downarrow)/J(\uparrow\downarrow))]$. The device demonstrated by Monsma et al. (1995) had initially a Co/Cu/Co multilayer at the base, with Co as ferromagnetic and Cu as non-ferromagnetic materials, and posteriorly a Pt layer was added to the emitter interface to tailor the barrier height relative to the collector interface (Monsma et al. 1998).

The magnetoresistance phenomenon is an effect observed at nanometer dimensions. It was first described in metallic nanolayers (Baibich et al. 1988) and subsequently in granular systems (Berkowitz et al. 1992, Xiao et al. 1992). It can be understood by assuming the model proposed by Mott (1964) that considers two channels for the conduction of electrons in ferromagnetic metals, one for spin up and one for spin down. The electrons transversally crossing a magnetic multilayer are assumed to suffer scattering in the layer with a magnetization contrary to their spin orientation. At low magnetic fields, when the magnetic multilayer is supposed to be in the anti-ferromagnetic alignment, the electron of both spin orientations will suffer scattering in alternate layers, and a higher MR will be measured. For high



(a) (b)

FIGURE 13.8 (a) Band diagram of an MBT with an F/N/F magnetic multilayer (MM) in the base. A metal was added at the emitter interface to tailor the barrier height in the emitter relative to the collector. The arrows indicate the direction of the magnetization of the layers. (b) Common-base characteristic of the spin transistor collector current for both configurations of the multilayer, ferromagnetic (↑↑), and antiferromagnetic (↑↓). (After Monsma, D.J. et al., *Phys. Rev. Lett.*, 74, 5260, 1995; Monsma, D.J. et al., *Science*, 281, 407, 1998.)



FIGURE 13.9 (a) Model of two channels and antiferromagnetic ($\uparrow\downarrow$) and ferromagnetic ($\uparrow\uparrow$) ordering in magnetic multilayers. (b) Typical curve for the magnetoresistance versus the applied magnetic field in magnetic multilayers.

magnetic fields, when the MM is ferromagnetic ordered, the electrons in the channel with the same orientation of the magnetization of the F layers will not suffer scattering by crossing the structure, and the electrons in the other channel will be scattered at each F layer. Since the channels are parallel, the total resistance will be reduced by the existence of the channel aligned with the magnetization of the ferromagnetic ordering of the layers. The alignment of the MM will have lower resistance, and the difference between both magnetic ordering is the magnetoresistive effect. Similarly to the magnetocurrent effect defined above, the MR effect can be written as $\mathrm{MR}(\%) = 100\,[(I(\uparrow\downarrow) - I(\uparrow\uparrow)/I(\uparrow\uparrow))]$. Figure 13.9a illustrates the scattering of electrons through the multilayered structure for both magnetic alignments, and in Figure 13.9b, the corresponding magnetoresistance curve when the field is varied from negative to positive values is shown.

The main disadvantages of the spin transistor proposed by Momsma et al. (1995) were related to the fabrication process that requires a vacuum bonding in order to sandwich the ferromagnetic multilayer between two-device quality silicon substrates, and the low transport factor observed ($<10^{-4}$). However, an easy method of fabricating MBTs with high current gains remained elusive.

A significant progress toward the fabrication process of TBMs was achieved by Meruvia et al. (2004) by using an organic semiconductor as the top layer in the vertical structure shown in Figure 13.5. A current gain as high as 1 was observed in the MBT with fullerene (C_{60}) as the emitter, Au thin layers as the base, and n-type silicon as the collector. The device is easy to fabricate since the organic layers can be prepared by regular methods such as electrodeposition, spin coating, and evaporation, and the approach opened the field of MBTs to hybrid structures with conducting polymers as the emitter and also as a pseudometallic base (Meruvia et al. 2005). The energy-band diagram of organic semiconductors is analogous to the one shown in Figure 13.4 for inorganic MBTs with barriers at interfaces and for the injection of hot carriers.

Most of the work expended on metal nanolayer-base transistors was in n-type devices. A p-type MBT was achieved by electrodepositing cuprous oxide (Cu_2O) (Delatorre et al. 2006). This semiconducting oxide is a p-type material with a 2.1 eV band-gap, a factor 2 higher than the band-gap of silicon of 1.1 eV. Figure 13.10 shows characteristic common-base curves obtained with the Cu_2O/Co/Si metal-base transistors with Co nanolayers of (a) 29 nm and (b) 33 nm, which display the transistor action in the third quadrant of the graphic as expected for p-metal-p devices.

The differences observed in Figure 13.10 by comparing the family of curves for the two base thicknesses used, 29 and 33 nm, indicate that the current gain is not only dependent on the thickness of the metallic layer but also that different transport mechanism are acting. For the 29 nm case, the collector current saturates at levels that are proportional to the emitter current, corresponding to a constant current gain. However, for 33 nm the I_C plateaus are not linear with I_E. When the test suggested in reference Rosencher et al. (1986) and described above to detect the presence of pinholes was applied to this p-metal-p transistor, a dependence of V_{EB} on V_{CB} was found. As can be seen in Figure 13.11a, for the thinner base layer, a significant dependence of V_{EB} on V_{CB} is observed. This dependency is a signature of the presence of pinholes in the base, which were also confirmed by the atomic force microscopy image shown in Figure 13.11b. The dark regions correspond to areas where no electrodeposition occurred, acting then as pinholes, allowing a direct contact of



FIGURE 13.10 Common-base characteristics of a p-type metal transistor with Cu_2O as emitter, p-type silicon as collector, and Co with thicknesses of (a) 29 nm and (b) 33 nm as base. (After Delatorre, R.G. et al., *Appl. Phys. Lett.*, 88, 233504-1, 2006. With permission.)



FIGURE 13.11 (a) Test of the dependency of V_{EB} on V_{CB} to check for the existence of pinholes in the base. (b) Atomic force microscopy of the Co metallic base with dark areas corresponding to regions not covered by the metal. (After Delatorre, R.G. et al., *Appl. Phys. Lett.*, 88, 233504-1, 2006. With permission.)



FIGURE 13.12 (a) Dependency of the current gain in the common-base configuration for two different Co thicknesses (29 and 33 nm). (b) Band diagram for the p-type metal base transistor with the two Schottky barriers and the expected barrier (dotted line) in the pinholes where the emitter and the collector are in contact, as expected for a permeable-base transistor. (After Delatorre, R.G. et al., *Appl. Phys. Lett.*, 88, 233504-1, 2006. With permission.)

the emitter with the collector. The bright areas are the Co grains. By increasing the base thickness, a considerable reduction in the pinholes occurred, since a lower dependence of V_{EB} on V_{CB} is observed for 33 nm in Figure 13.11a.

Figure 13.12a shows the dependency of the gain as a function of the emitter current for the two thicknesses of Co. The gain is equal to 1 and is independent of the emitter current for the case where the transistor has a higher density of pinholes. For a lower density of pinholes, the dependency of the current gain with the emitter current indicates that the gain increases with the energy of the ejected electron, i.e., with an increase of the emitter current, which is compatible with the view of electrons with higher energies being collected more easily at the collector interface. Figure 13.12b depicts the expected energy barriers for the p-type metal-base transistor in the case of two Schottky interfaces in the Cu_2O/Co/Si structure and the gradual variation of the barrier in the pinholes where the Cu_2O is in contact with p-Si. With an increasing base thicknesses, the MBT action dominates the PMT one, and on increasing the emitter current, higher gains should be observed since the energy of the electrons is higher, favoring the overcome of the collector to the base barrier.

References

Atalla, M. M. and Kahng, D. 1962. A new hot electron triode structure with semiconductor metal emitter. *IEEE Transactions on Electron Devices* ED-9: 507–508.

Baibich, M. N., Broto, J. M., Fert, A., Nguyen van Dau, F., Petroff, F., Eitenne, P., Creuset, G., Friederich, A., and Chazelas, J. 1988. Giant magnetoresistance of (001)Fe/(001)Cr magnetic superlattices. *Physical Review Letters* 61: 2472–2475.

Berkowitz, A. E., Mitchell, J. R., Carey, M. J., Young, A. P., Zhang, S., Spada, F. E., Parker, F. T., Hutten, A., and Thomas, G. 1992. Giant magnetoresistance in heterogeneous Cu-Co alloys. *Physical Review Letters* 68: 3745–3748.

Bozler, C. O. and Alley, G. D. 1980. Fabrication and numerical simulation of the permeable base transistor. *IEEE Transactions on Electron Devices* ED-27: 1128–1141.

Delatorre, R. G., Munford, M. L., Zandonay, R., Zoldan, V. C., Pasa, A. A., Schwarzacher, W., Meruvia, M. S., and Hümmelgen, I. A. 2006. p-Type metal-base transistor. *Applied Physics Letters* 88: 233504-1–233504-3.

Deneuville, A. and Brodsky, M. H. 1978. Thin-film metal base transistor structure with amorphous silicon. *Thin Solid Films* 55: 137–141.

Geppert, D. V. 1962. The metal base transistor. *Proceedings of the IRE* 50: 1527.

Hensel, J. C., Levi, A. F. J., Tung, R. T., and Gibson, J. M. 1985. Transistor action in Si/CoSi$_2$/Si heterostructures. *Applied Physics Letters* 47: 151–153.

Kanô, G. 1964. Schottky emitter type metal base transistor. *Japanese Journal of Applied Physics* 3: 363–364.

Meruvia, M. S., Hummelgen, I. A., Sartorelli, M. L., Pasa, A. A., and Schwarzacher, W. 2004. Organic-metal-semiconductor transistor with high gain. *Applied Physics Letters* 84: 3978–3980.

Meruvia, M. S., Benvenho, A. R. V., Hümmelgen, I. A., Pasa, A. A., and Schwarzacher, W. 2005. Pseudo-metal-base transistor with high gain. *Applied Physics Letters* 86: 263504-1–263504-3.

Monsma, D. J., Lodder, J. C., Popma, T. J. A., and Dieny, B. 1995. Perpendicular hot electron spin-valve effect in a new magnetic field sensor: The spin-valve transistor. *Physical Review Letters* 74: 5260–5263.

Monsma, D. J., Vlutters, R., and Lodder, J. C. 1998. Room temperature operating spin-valve transistors formed by vacuum bonding. *Science* 281: 407–409.

Mott, N. F. 1938. Note on the contact between a metal and an insulator on semiconductor. *Proceedings of the Cambridge Philosophical Society* 34: 568–572.

Mott, N. F. 1964. Electrons in transition metals. *Advances in Physics* 13: 325.

Rhoderick, E. H. and Williams, R. H. 1988. *Metal-Semiconductor Contacts*, 2nd edn. Oxford, U.K.: Clarendon.

Rose, A. 1960 (June). RCA Interim report 6A.

Rosencher, E., Delage, S., Campidelli, Y., and Arnaud D'Avitaya, F. 1984. Transistor effect in monolithic Si/CoSi$_2$/Si epitaxial structures. *Electronics Letters* 20: 762–764.

Rosencher, E., Badoz, P. A., Pfister, J. C., Arnaud d'Avitaya, F., Vincent, G., and Delage, S. 1986. Study of ballistic transport in Si-CoSi$_2$-Si metal base transistors. *Applied Physics Letters* 49: 271–273.

Schottky, W. 1938. Halbleitertheorie der sperrschicht. *Naturwissenschaften* 26: 843.

Sze, S. M. 1969. *Physics of Semiconductor Devices*. New York: Wiley.

Tung, R. T., Levi, A. F. J., and Gibson, J. M. 1986. Control of a natural permeable CoSi$_2$ base transistor. *Applied Physics Letters* 48: 635–637.

Xiao, J. Q., Jiang, J. S., and Chien, C. L. 1992. Giant magnetoresistance in nonmultilayer magnetic systems. *Physical Review Letters* 68: 3749–3752.

Zandonay, R., Delatorre, R. G., and Pasa, A. A. 2008. Electrical characterization of electrodeposited Co/p-Si Schottky diodes. *ECS Transactions* 14: 359–363.

14

ZnO Nanowire Field-Effect Transistors

Woong-Ki Hong
Gwangju Institute of Science and Technology

Gunho Jo
Gwangju Institute of Science and Technology

Sunghoon Song
Gwangju Institute of Science and Technology

Jongsun Maeng
Gwangju Institute of Science and Technology

Takhee Lee
Gwangju Institute of Science and Technology

14.1 Introduction **14**-1
14.2 Background.......... **14**-2
Basic Physical Parameters of ZnO • General Growth Methods of ZnO Nanowires • Field-Effect Transistor
14.3 Results and Discussion **14**-4
Growth by a Vapor Transport Method and Characterization of ZnO Nanowires • Fabrication and Characterization of ZnO Nanowire Field-Effect Transistors • N-Channel Depletion-Mode and Enhancement-Mode ZnO Nanowire FETs • Electronic Transport in Surface-Architecture-Controlled ZnO Nanowire FETs
14.4 Summary.......... **14**-14
Acknowledgment.......... **14**-14
References.......... **14**-14

14.1 Introduction

The top-down fabrication techniques, which involve photolithographic and subsequent etching techniques, have been used as conventional methods for device scaling in semiconductor industry for integrated electronic systems. However, due to the further downscaling of device size, the top-down approach faces the limitations of photolithographic/etching techniques as well as the increasing costs associated with lithography equipment (Lu and Lieber 2007). One promising method to overcome the limitations with the top-down methods is the bottom-up approach, which is a unique technique for fabricating functional devices, without the use of lithography techniques, through the chemical synthesis, self-assembly, and the manipulation of nanoscale elements such as small molecules, nanoparticles, nanotubes, and nanowires (Agarwal 2008). Recently, for the realization of integrated electronic systems through the bottom-up approach, these nanomaterials have attracted considerable interest due to their unique properties such as large surface-to-volume ratio, carrier and photon confinement, and high sensitivity. In particular, various semiconductor nanowires offer great potential as building blocks for nanoscale electronic and photonic device applications.

Among many semiconductor nanowires, ZnO with the preferentially hexagonal wurzite-type structure has a wide range of properties, from metallic to insulating conductivities (including n- and p-type conductivities), a direct wide band gap (~3.4 eV), large exciton-binding energy (~60 meV), radiation hardness, high transparency, piezoelectricity, room-temperature ferromagnetism, and chemical-sensing effects (Fan and Lu 2005, Klingshirn 2007, Schmidt-Mende and MacManus-Driscoll 2007). In particular, the advantage of large exciton-binding energy and a variety of nanostructures with relative cost-effectiveness provides excellent optical and electrical properties as a promising material for blue and ultraviolet optical devices, compared with GaN and GaN-based materials. Moreover, since ZnO has stronger radiation hardness than other common semiconductor materials such as Si, GaAs, CdS, and GaN, ZnO materials are promising for space applications (Look et al. 1999). In recent decades, due to these remarkable properties of ZnO materials and the demand for further miniaturization by semiconductor technology, tremendous efforts have been devoted to the growth and characterization of one-dimensional semiconductor ZnO nanostructures (or ZnO nanowires) as well as their versatile applications as a potential material for future nanoelectronics. For example, field-effect transistors (FETs) (Goldberger et al. 2005), sensors (Dorfman et al. 2006), light-emitting devices (Bao et al. 2006), solar cells (Law et al. 2005), as well as logic circuits (Park et al. 2005, Yeom et al. 2008) have been extensively investigated and demonstrated.

In particular, since nanowire-based FETs are the fundamental element for nanoelectronics among these versatile applications, ZnO nanowire-based FETs have been fabricated and intensively investigated in a typical back-gate configuration due to fabrication simplicity (Goldberger et al. 2005, Cha et al. 2006, Chang et al. 2006). The early studies of ZnO nanowire FETs have focused on their device performance (Cha et al. 2006, Chang et al. 2006), gas-sensing application (Fan and Lu 2006, Hsueh et al. 2007), photodetection (Kind et al. 2002, Fan et al. 2004a,b, Soci et al. 2007), and chemisorption/photodesorption (Li et al. 2005, Suehiro et al. 2006). However, in order to fabricate the functional devices from the ZnO nanowires, their fundamental properties must be carefully investigated because the presence of a large surface and interfacial area in nanowires can profoundly alter their performance (Hong et al. 2007, Xiong et al. 2007). Recently, there are a few studies on the role of geometric properties, surface states, and passivation on the transport properties of ZnO nanowire FETs, specifically on the influence of the presence of surface trap states at the interfaces associated with nanowire size and surface roughness (Hong et al. 2007, 2008a,b,c). The interfaces and interfacial states related to interface roughness play an important role not only in nanowire heterostructures, but also in the electronic transport properties of nanoscale transistors as fundamental elements for nanoelectronics (Hastas et al. 2002, Wang et al. 2005, Jung et al. 2007, Mieszawska et al. 2007). In addition, it is well known that metal-oxide semiconductors including ZnO nanostructures are strongly affected by the chemical adsorptions of ambient gases (Lagowski et al. 1977, Kolmakov and Moskovits 2004). Therefore, it is essential to understand the surface-roughness- and size-dependent effects on the electronic transport properties of nanowire transistors. Moreover, since ZnO nanowires are strongly influenced by chemical environments due to large surface-to-volume ratio (Goldberger et al. 2005, Li et al. 2005, Fan and Lu 2006, Suehiro et al. 2006, Hsueh et al. 2007), it is important to study the passivation effects of dielectric layer on the transport properties correlated to geometry and adsorbed species on the ZnO nanowires.

In this chapter, we review the basic electrical properties of FETs made from ZnO nanowires that were grown by a vapor transport method. We demonstrate that the transport properties of ZnO nanowire FETs are associated with the surface roughness, nanowire size, surface states, and/or defects, as well as the surface chemistry in surrounding environments. These explorations will give insights not only in understanding the transport properties but also in developing practically useful applications of nanowire-based devices.

14.2 Background

14.2.1 Basic Physical Parameters of ZnO

The ZnO in wurzite structure, which can be considered as a hexagonal close-packed lattice of zinc atoms tetrahedrally coordinated with four oxygen atoms, has the primitive translation vectors $\mathbf{a}_0$, $\mathbf{b}_0$, and $\mathbf{c}_0$ in which $\mathbf{a}_0$ and $\mathbf{b}_0$ lay in the x–y plane and are of equal length, whereas $\mathbf{c}_0$ is parallel to the z-axis (Figure 14.1). The values of the primitive translation vectors are $a_0 = b_0 = 0.3249$ nm and $c_0 = 0.5206$ nm at room temperature. The ratio c_0/a_0 of 1.602 deviates slightly from the value $c_0/a_0 = 1.633$ of the ideal hexagonal structure. The basic physical parameters for ZnO are summarized in Table 14.1 (Fan and Lu 2005, Klingshirn 2007, Schmidt-Mende and MacManus-Driscoll 2007). Based on these fundamental physical properties, intense research by many groups has been focused on the growth and characterization of ZnO nanostructures and their versatile device applications.



FIGURE 14.1 Crystal structure of ZnO.

TABLE 14.1 Basic Physical Parameters of ZnO

Property	Value
Lattice constants (at $T = 300$ K)	
a_0	0.3249 nm
c_0	0.5206 nm
a_0/c_0	1.602 (ideal structure: 1.633)
Density (ρ)	5.606 g/cm^3
Melting point	1975°C (2248 K)
Dielectric constant (ε)	8.66
Energy gap (E_g)	3.4 eV
Exciton-binding energy	60 meV
Electron effective mass (m_e^*)	0.24
Electron mobility (μ_e)	200 cm^2/V s
Hole effective mass (m_h^*)	0.59
Hole mobility (μ_h) (at $T = 300$ K)	5–50 cm^2/V s

In the following we explain briefly the growth by a vapor transport method and the characterization of ZnO nanowires and the detail fundamental properties of the FETs made from ZnO nanowires are explained in Section 14.3.

14.2.2 General Growth Methods of ZnO Nanowires

Semiconductor nanowires including ZnO nanowires have attracted considerable attention due to their unique properties, including their high anisotropic geometry and large surface-to-volume ratio. In order to utilize semiconductor nanowires for nanoelectronic devices, it is essential to rationally grow high-quality nanowires with tunable and modulated chemical composition, size, and morphology, and to precisely control doping concentration with both n- and p-type dopants. To this end, there are many efforts to control the nanowire properties, and numerous growth techniques have been developed (Dai et al. 2003, Law et al. 2004, Schmidt-Mende and MacManus-Driscoll 2007). In recent years, the interest in ZnO nanostructures has increased drastically and many researchers have intensively investigated on them. In general, ZnO nanostructures can be grown by either vapor-phase growth or aqueous solution growth methods. In particular, vapor-phase growth methods use gas-phase species as the initial starting reactants for the nanowire formation, and numerous growth techniques such as laser-assisted growth (Sun et al. 2006), chemical vapor deposition (Yang et al. 2002, Park et al. 2003), and thermal evaporation (Dai et al. 2003) have been developed to prepare gas-phase species. In these gas-phase production methods, nanowires are commonly grown via vapor–liquid–solid (VLS) or vapor–solid (VS) mechanisms. VLS process can be regarded as nanowire nucleation and growth via Zn accumulation in liquid catalyst particle (often Au), supersaturation, precipitation, and oxidation, whereas VS process can be described as one-dimensional nanostructure formation from vapor phase precursors in the absence of metal catalysts (Law et al. 2004).

14.2.3 Field-Effect Transistor

The FET, which is often called a unipolar transistor due to a majority carrier device, uses either electrons or holes for conduction. The FET is a three-terminal (source, drain, and gate) device in which the current through two terminals between source and drain is controlled by the gate (Sze 1981, Streetman and Banerjee 2000). The conductivity is varied by the electric field that is produced when the gate–source voltage (V_G) is increased; the drain–source current (I_{DS}) increases exponentially for V_G below threshold. The FETs are divided into several forms: a junction FET (JFET), a metal-semiconductor FET (MESFET), and a metal-insulator semiconductor FET (MISFET) or metal-oxide semiconductor FET (MOSFET) (Figure 14.2) (Sze 1981, Streetman and Banerjee 2000). In the JFET, the control (gate) voltage varies the depletion width of a reverse biased p–n junction with the channel between the source and drain (Figure 14.2a). Similarly, the MESFET is the JFET in which the reverse biased p–n junction is replaced by a metal-semiconductor Schottky junction (Figure 14.2b) The MOSFET is used to amplify or switch electronic signals and generally is consisting of three terminals (source, drain, and gate) and substrate (or body) (Figure 14.2c through f). In particular, since a gate electrode is separated from the semiconductor (substrate) by an oxide, there is effectively no dc gate current, and the channel is capacitively coupled to the gate via the electric field in the oxide. Furthermore, the FETs are



FIGURE 14.2 Basic classification of FETs. (a) JFET, (b) MESFET, and (c)–(f) four different types of MOSFET. (c) n-channel E-mode MOSFET and (d) n-channel D-mode MOSFET. (e) p-channel E-mode MOSFET and (f) p-channel D-mode MOSFET.



FIGURE 14.3 Basic current–voltage characteristics of FETs. (a) Typical transistor output characteristics (I_{DS}–V_{DS}). (b) Typical transistor transfer characteristics (I_{DS}–V_G).



FIGURE 14.4 Comparison of basic current–voltage characteristics of (a) "normally on" FET and (b) "normally off" FET.

distinguished as depletion-mode (D-mode) and enhancement-mode (E-mode) types in terms of the turn-on/off position and the polarity of the threshold voltage. The D-mode FETs exhibit the turn-on of the channel at zero gate bias and negative threshold voltages (Figure 14.2d and f), whereas the E-mode FETs exhibit the turn-off at zero gate bias and positive threshold voltages (Figure 14.2c and e). Therefore, D- and E-mode types are often called "normally on" and "normally off," respectively.

The basic current–voltage (*I*–*V*) characteristics of FETs are shown in Figure 14.3, where the complete set of I_{DS}–V_{DS} (drain–source current versus voltage) curves are called "output characteristics" (Figure 14.3a) and I_{DS}–V_G (drain–source current versus gate voltage) curves are called "transfer characteristics" (Figure 14.3b). In particular, the output characteristics are plotted as a function of the drain–source voltage (V_{DS}) for various gate voltages (V_G) and can be divided into three regions: (1) the linear region, where I_{DS} increase linearly with V_{DS} for a given V_G(>V_{th}); (2) the saturation region, where I_{DS} no longer increases as V_{DS} increases, i.e., it remains essentially constant; and (3) the breakdown region, where I_{DS} suddenly increases with the further increase of V_{DS} beyond saturation. Figure 14.4 displays the comparison of *I*–*V* characteristics between "normally on" (D-mode) FET (Figure 4.4a) and "normally off" (E-mode) FET (Figure 14.4b). The main difference is the position of the threshold voltage (V_{th}) along the V_G.

14.3 Results and Discussion

14.3.1 Growth by a Vapor Transport Method and Characterization of ZnO Nanowires

ZnO nanostructures can be simply grown using a thermal furnace system consisting of quartz tube, gas flow controller, and vacuum system. Figure 14.5 shows a schematic of furnace system and a series of the field emission scanning electron microscopy (FESEM) images of various ZnO nanostructures with distinctive geometrical morphologies formed by the vapor transport method using a furnace system, which is the most common method to grow ZnO nanowires. The shape and size of these nanostructures are strongly dependent on the various growth



FIGURE 14.5 (a) Schematic diagram of experimental apparatus for growth of ZnO nanostructures. FESEM images of (b) nanoribbons or nanoblets, (c) nanosheets, (d) nanocombs, (e) vertically well-aligned nanowire/nanorods, (f) random-oriented nanowire/nanorods, (g) corrugated nanowires, (h) nanotips or nanoneedles, and (i) nanowalls.

conditions such as temperature, gas flow rate, substrate itself, and the position of substrate. In general, the size, surface morphology, and the crystal structure of ZnO nanowires are commonly characterized using FESEM and transmission electron microscopy (TEM). In order to study the optical properties of ZnO nanowires, the photoluminescence (PL) spectra are measured. In addition, to investigate the electrical properties of ZnO nanowires, the FET-based device structures are fabricated as shown in Figure 14.6e and f and characterized.

The vertically well-aligned ZnO nanowires were grown on the sapphire substrates or ZnO-film-coated sapphire substrates (Figure 14.6a). Figure 14.6b shows the micro-photoluminescence (μPL) spectra of ZnO nanowires grown on the two different substrates. A He–Cd laser (325 nm) was used as an excitation source in the PL measurements. The μPL spectra were measured on the ZnO nanowires after they were transferred from the growth substrates to a silicon wafer in order to eliminate the signals coming from the ZnO film substrate itself. The ZnO nanowires grown on an Au-catalyst-free ZnO film substrate show a stronger defect emission in the PL spectrum than those grown on an Au-coated sapphire substrate. Since it is generally agreed that the defect emission is a surface-related process (Wang et al. 2006), the PL spectra suggest that the ZnO nanowires grown on an Au-catalyst-free ZnO film have a significantly larger number of surface defect sites. Figure 14.6c and d shows typical high-resolution TEM (HRTEM) images of ZnO nanowires grown on an Au-coated sapphire substrate and on an Au-catalyst-free ZnO film, respectively. The upper insets of Figure 14.6c and d are computed fast Fourier transform patterns obtained from the lattice fringes of ZnO nanowires, indicating that the ZnO nanowires grown on both substrates are single crystalline with a preferred growth direction of [0001]. The lower insets of Figure 14.6c and d are the low-magnification TEM images of ZnO nanowires showing the overall surface roughness along the nanowires. Both the low-magnification TEM images and the HRTEM images allow comparison between the surface structures of the ZnO nanowires grown on the two different types of substrates. Compared to the ZnO nanowires grown on an Au-coated sapphire substrate (Figure 14.6c), the ZnO nanowires grown on an Au-catalyst-free ZnO film (Figure 14.6d) are seen to be significantly rougher across the surfaces parallel to the growth direction, as is apparent in the HRTEM images, and as is indicated by the circled regions in the low-magnification TEM images of the lower inset in Figure 14.6d. Figure 14.6e and f show the schematic of nanowire FET device structure and the SEM image of a single ZnO nanowire connecting the source and drain electrodes.



FIGURE 14.6 (a) FESEM images of vertically well-aligned ZnO nanowires grown on Au-coated sapphire substrates or ZnO buffer film-coated substrates. (b) The μPL spectra of ZnO nanowires on the two substrates showing emissions at approximately 378 nm. HRTEM images of ZnO NWs grown on (c) an Au-coated sapphire substrate and (d) an Au-catalyst-free ZnO film. Insets are computed fast Fourier transform patterns (upper) and low-magnification TEM images (lower). (e) A schematic of the FET device structures. (f) A FESEM image of a single ZnO nanowire connected between source and drain electrodes in FET. (Adapted from Hong, W.-K. et al., *Appl. Phys. Lett.*, 90, 243103, 2007. With permission.)

14.3.2 Fabrication and Characterization of ZnO Nanowire Field-Effect Transistors

ZnO nanowire FETs with different gate structures have been fabricated and extensively investigated in the past several years. For example, there are four different types of gate configurations: back gate (Goldberger et al. 2005, Hong et al. 2007), top gate (Huang et al. 2001, Yeom et al. 2008), side gate (Cha et al. 2006), and surrounding gate (Ng et al. 2004, Wade et al. 2007). In particular, the FETs with back-gate and top-gate configurations have been intensively explored due to the fabrication simplicity. To fabricate ZnO nanowire FET device, the grown ZnO nanowires are first transferred from the growth substrate to a silicon wafer with thermally grown oxide or a bare silicon wafer by dropping and drying a nanowire suspension (Figure 14.7). The nanowire suspension is made by briefly sonicating the growth substrate of ZnO nanowires in ethanol or isopropyl alcohol (IPA) for tens of seconds. Metal electrodes forming Ohmic contacts between metal and ZnO nanowires are deposited by an evaporator or a sputter and defined as source and drain electrodes by



FIGURE 14.7 Fabrication process of ZnO nanowire FETs with (a) back gate and (b) top gate configurations.

lithography techniques and liftoff process (Figure 14.7). In back-gated FET configuration (Figure 14.7a), a pair of metal electrodes patterned on the ZnO nanowire channel serves as the source and drain and a degenerately doped silicon substrate serves the gate electrode. In top-gated FET configuration (Figure 14.7b), a metal gate electrode is formed above a gate dielectric layer on nanowires. Recently, tremendous efforts have been devoted to the fabrication and characterization of nanowire-based transistors. However, if functional FET devices with electrical contacts are to be made from nanowires, their fundamental properties must be carefully investigated due to the presence of the different interfaces and interfacial states in nanowire-based device. The different interfaces exist between the nanowire and passivation layer, nanowire and gate dielectrics, nanowire and electrodes, and nanowire and ambient gases.

In particular, since the semiconductor surfaces are strongly affected by the chemical adsorption of ambient gases (Wolkenstein 1991), the influence of chemisorptions of ambient gases in the case of semiconducting nanowires including ZnO nanowires are much more sensitive than their bulk counter part due to large surface-to-volume ratio (Lagowski et al. 1977, Kolmakov and Moskovits 2004). For example, surface defects such as oxygen vacancies act as the adsorption sites of O_2 molecules and form oxygen ions (O^-, O^{2-}, or O_2^-), and then the chemisorption of O_2 molecules depletes the surface electron and reduces the channel conductivity (Li et al. 2004, Zhang et al. 2004). Therefore, the passivation of ZnO nanowire FET devices is significantly important to remove the influence of water or gas molecules in ambient air on nanowire and to improve the FET performance by enhancing the gate-coupling effects (Hong et al. 2008a,b,c). In addition, other characterization conditions such as gate bias sweep rate can also influence the electronic transport in nanowire transistors due to the presence of surface states (Maeng et al. 2008).

In this section, we review the electrical properties of the surface-tailored smooth and rough ZnO nanowire FETs with and without surface passivation using poly(methyl metahacrylate) (PMMA), which is a polymeric resist commonly used in nanolithographic processes involving electron beam, deep UV, or x-ray radiation (Hong et al. 2008a,b,c). Furthermore, a detailed study of the passivation and gate sweep rate effects on the ZnO nanowire FETs under different oxygen environments is presented.

14.3.2.1 Passivation and Surface-Roughness Effects

The electrical characteristics before and after the passivation of the FET devices made from the surface-tailored smooth and rough ZnO nanowires are summarized in Figure 14.8. Figure 14.8a and b shows the output characteristics (source–drain current versus voltage, I_{DS}–V_{DS}) and transfer characteristics (source–drain current versus gate voltage, I_{DS}–V_G) for a FET made from smooth ZnO nanowires, respectively. The FETs made from smooth ZnO nanowires exhibit more well-defined saturation and pinch-off characteristics after passivation in comparison with the FET devices before passivation. In particular, the FET devices before passivation show decreasing separation in current between I_{DS} curves at larger currents in I_{DS}–V_{DS} curves (Figure 14.8a), which is attributed to either an electron injection barrier at the source electrode or to mobility degradation associated with the interface roughness scattering of channel electrons at the channel–insulator interface with increasing gate voltage (Dehuff et al. 2005). The I_{DS}–V_G curves in Figure 14.8b show the threshold voltages (V_{th}) of −4.16 and −2.25 V before and after passivation, respectively. The threshold voltage after passivation shifts toward the positive gate bias direction due to surface-depletion-induced channel-narrowing effect (Fan et al. 2004a,b, Ju et al. 2006, 2007). The current on/off ratios (I_{on}/I_{off}) both before and after passivation for this FET device of smooth ZnO nanowire exhibited 10^4–10^5 (insets of Figure 14.8b).

In contrast, Figure 14.8c and d shows the I_{DS}–V_{DS} and I_{DS}–V_G curves for a FET made from rough ZnO nanowires, respectively. The unpassivated FET devices exhibited the poor electrical characteristics, as the I_{DS}–V_{DS} curves shown in Figure 14.8c. The I_{DS} suddenly decreased with the further increase of V_{DS} and V_G beyond saturation and also the current between I_{DS} curves was not clearly separated. However, the passivated FET devices exhibited well-defined linear regions at low biases and saturation regions at high biases as typical transistors, indicating clear pinch-off behavior. Unlike the FET devices made from smooth ZnO nanowires, the threshold voltage for the FET devices made from rough ZnO nanowires exhibits a considerable shift toward the positive gate bias direction after passivation. The threshold voltage of the particular FET device shown in Figure 14.8d shifted from −12.5 to 8.9 V, indicating transition from D-mode to E-mode operations. Most of the passivated FET devices made from both smooth and rough ZnO nanowires exhibit superior electrical performance than the unpassivated FET devices made from rough ZnO nanowires. These results are in good agreement with the superior characteristics of the FETs passivated by SiO_2/Si_3N_4 or PMMA layer (Kim et al. 2003, Chang et al. 2006, Hong et al. 2008a,b,c). The current on/off ratios (I_{on}/I_{off}) both before



FIGURE 14.8 (a) I_{DS}–V_{DS} and (b) I_{DS}–V_G curves of a FET device made from rough ZnO nanowires before and after passivation. (c) I_{DS}–V_{DS} and (d) I_{DS}–V_G curves of a FET device made from rough ZnO nanowires before and after passivation. (Adapted from Hong, W.-K. et al., *Appl. Surf. Sci.*, 254, 7559, 2008c. With permission.)

and after passivation for the FET device of rough ZnO nanowire exhibited approximately 10^4–10^5 (insets of Figure 14.8d).

Furthermore, the electrical properties of the ZnO nanowire FETs have also been investigated and compared before and after the PMMA passivation under different environments of ambient air (20% O_2), dry O_2, and vacuum (10^{-3} Torr) environments (Song et al. 2008). Figure 14.9 shows a series of the I_{DS}–V_{DS} and the I_{DS}–V_G curves for a ZnO nanowire FET measured at different gate voltages under various oxygen environments before and after passivation, respectively. Figure 14.9a and b displays the I_{DS}–V_{DS} curves for the ZnO nanowire FET before and after passivation, respectively. As shown in Figure 14.9a, the current level is significantly affected by the environmental condition with O_2 molecules. The currents decrease significantly when the ZnO nanowire FET is exposed to dry O_2, as compared to the case in ambient air. When the oxygen is evacuated, the currents increase again. On the contrary, the I_{DS}–V_{DS} curves in Figure 14.9b show a negligible effect on the passivated ZnO nanowire FET by oxygen molecules in different oxygen environments. This is because the PMMA passivation layer prevents oxygen molecules from being adsorbed onto the nanowire. One can also notice that the ZnO nanowire FETs after passivation have a better electrical performance in terms of well-defined linear and saturation regions in I_{DS}–V_{DS} curves (Figure 14.9b). It has been reported that the passivation can improve the FET performance by enhancing the gate-coupling effect (Kim et al. 2006, Wunnicke 2006, Hong et al. 2008a,b,c). This passivation effect is more prominent in transfer characteristics, as shown in Figure 14.9c and d. A series of plots in Figure 14.9c and d shows the I_{DS}–V_G curves for the ZnO nanowire FET before and after passivation, respectively. The FET device was measured at a fixed source–drain voltage (V_{DS} = 0.1 V) under the same different environments of ambient air (20% O_2), dry O_2, and vacuum (~10^{-3} Torr). The I_{DS}–V_G plots in the semilogarithmic scale (insets of Figure 14.9c and d) show an on/off current ratio as large as 10^4–10^5 for both before and after passivation. Before passivation (Figure 14.9c), the threshold voltages of ZnO nanowire FET shifted from −1.73 (in ambient air) to 6.05 V (in dry O_2) in the positive gate bias direction. This is because more electrons are captured by the oxygen as the oxygen pressure is raised. Since the charge density is reduced after being exposed to dry O_2, more positive gate bias is needed to make currents flow in the nanowire channel, and thus the



FIGURE 14.9 I_{DS}–V_{DS} curves for different gate biases (from 6 to 10 V, with a step of 2 V) for a ZnO nanowire FET, acquired under ambient air, dry O_2, and vacuum conditions (a) before and (b) after passivation. I_{DS}–V_G curves at V_{DS} = 0.1 V for the ZnO nanowire FET, acquired under ambient air, dry O_2, and vacuum conditions (c) before and (d) after passivation. The insets in (c and d) show the semilogarithmic plot of the I_{DS}–V_G curves. (Adapted from Song, S. et al., *Appl. Phys. Lett.*, 92, 263109, 2008. With permission.)

threshold voltage shifts to the positive gate bias direction. When oxygen gas was evacuated to a vacuum level of 10^{-3} Torr, the threshold voltages of the nanowire FET shifted back from 6.05 (in dry O_2) to −0.10 V (in a vacuum) in the negative gate bias direction, as compared when they were exposed to a dry O_2 environment. This is due to the reduction of the trapping effects of oxygen in a vacuum. On the contrary, when the FET was passivated with PMMA, the threshold voltages were ~6 V and shifted very little under different oxygen environments, as shown in Figure 14.9d. Note that the threshold voltage is defined as the gate voltage obtained by extrapolating the linear portion of the I_{DS}–V_G curve from the point of maximum slope to zero drain current, in which the point of maximum slope is the point where transconductance (dI_{DS}/dV_G) is at a maximum (Arora 1993).

As a result, these phenomena can be explained by oxygen effects. The ambient oxygen partial pressure has a considerable effect on the electrical properties of ZnO nanowire FETs (Fan et al. 2004a,b). Particularly, the adsorbed oxygen molecules deplete the electrons in the ZnO nanowire and form oxygen ions (O^-, O^{2-}, or O_2^-) (Li et al. 2004). Then, the electrons in the ZnO nanowires are trapped by the adsorbed oxygen molecules, and thus the surface depletion region of ZnO nanowire can be formed, leading to current reduction and threshold voltage shift to the positive gate bias direction (Figure 14.9c). As the oxygen pressure is raised, more electrons are captured by the oxygen molecules at the nanowire surface. Correspondingly, the depletion region is widened and the carrier density in the ZnO nanowire is decreased even more when the FET is exposed to dry O_2 environment.

14.3.2.2 Sweep Rate Effect of Gate Bias

As aforementioned, the corresponding characteristics of nanowire FETs are sensitively dependent on the surrounding environments to which the devices are exposed, and whether or not the devices are passivated (Park et al. 2004, Chang et al. 2006, Song et al. 2008). Other characterization conditions can also influence electrically the interactive absorption of oxygen molecules on the nanowire surface. Particularly, the effect of gate bias sweep rate on the electronic transport properties of ZnO nanowire FETs has been investigated (Maeng et al. 2008). The electrical properties of ZnO nanowire FETs were measured as a function of gate bias sweep rate in different measurement environments.

Figure 14.8 show a series of I_{DS}–V_G curves measured at different gate bias sweep rates (2500, 250, 130, 100, 12, 6, 1.2, 0.3, 0.2, 0.1 V/s) at $V_{DS} = 0.5$ V under various environments. The insets in Figure 14.10 show the I_{DS}–V_G plots on a semilogarithmic scale. A ZnO nanowire FET device was systematically measured in ambient air, in an N_2-filled glove box, and in ambient air after the same device was passivated with a PMMA layer. Figure 14.10a shows the case of a ZnO nanowire FET (unpassivated) measured in ambient air. As the gate bias sweep rate was decreased from 2500 to 0.1 V/s, the current decreased and the threshold voltage shifted to the positive gate bias direction. These phenomena can be explained by the depletion of electrons by oxygen adsorption on the surface of the ZnO nanowire. As previously mentioned, the increase of oxygen concentration causes the change of conductivity by surface depletion in the nanowire channel, i.e., the adsorbed oxygen molecules that bind the electrons localized at the nanowire surface become oxygen ions in the forms of O^-, O^{2-}, or O_2^-, resulting in depletion of electrons and thus lowering the conductivity (Takata et al. 1976, Li et al. 2004, Sadek et al. 2007). Oxygen adsorption is sustained at an equilibrium condition in ambient air at zero gate bias. However, the gate bias induces more adsorption of oxygen ions due to the applied positive gate bias. Therefore, when the nanowire FET is applied with a slower gate bias rate, more electrons on the ZnO nanowire surface are trapped by the adsorbed oxygen ions, which results in a reduction of nanowire conduction channel region by the more depleted region. Thus, the current decreases, and the threshold voltage shifts to the positive gate bias direction. The effect of the gate bias sweep rate on the ZnO nanowire FET was investigated under different oxygen environments. The same ZnO nanowire FET device measured in ambient air (Figure 14.10a) was placed into an N_2-filled glove box after holding at a vacuum (~10^{-5} Torr) for 24 h. The I_{DS}–V_G curves measured in this N_2 environment are shown in Figure 14.10b. The conductivity of the ZnO nanowire FET device in the N_2 environment increased by about an order of magnitude, compared with the case of ambient air. In the N_2 environment, the nanowire FET has fewer oxygen ions on the surface, thus less surface depletion of electrons, resulting in an increase of the current. Unlike the case of the nanowire measured in ambient air, the nanowire device (unpassivated) in the N_2 environment was not influenced by the gate bias sweep rate, as is shown in Figure 14.10b. The current did not change and the threshold voltage did not shift. This is because of the relative absence of oxygen in the N_2-filled glove box; therefore, there is a negligible effect of oxygen absorption even at different gate bias sweep rates. In addition, the effect of the gate bias sweep rate on the same ZnO nanowire FET device after the passivation of PMMA layer was explored. The resulting I_{DS}–V_G curves after the passivation, measured in ambient air, are shown in Figure 14.10c. Although the change and shift are not as significant, the I_{DS}–V_G curves exhibited somewhat similar trends of the current change and threshold voltage shift for different gate bias sweep rates as the case of Figure 14.10a. Therefore, the effect of gate bias sweep rate on the nanowire channel can be explained as the following. Slower gate bias sweep rates imply longer gate biasing time. Captured oxygen ions are strongly bonded by positive gate bias, so that oxygen ions would not be easily detached. Thus, slow gate bias sweep rates will cause more oxygen absorption than fast gate bias sweep rates. More adsorbed oxygen molecules extend the surface depletion region. Consequently, a larger depletion region in the nanowire occurs by slower gate bias sweep rates and longer gate-biasing time, which results in the reduction of current and carrier density and a shift of gate bias in the positive gate bias direction. On the contrary, faster gate bias sweep rates are applied in relatively shorter gate biasing time. Therefore, fast gate bias sweep rates lead to less oxygen absorption.



FIGURE 14.10 I_{DS}–V_G curves for a ZnO nanowire FET as a function of gate bias sweep rate (2500, 250, 130, 100, 12, 6, 1.2, 0.3, 0.2, and 0.1 V/s) measured at $V_{DS} = 0.5$ V (a) under ambient air, (b) N_2-filled glove box, and (c) ambient air after PMMA passivation. The semilogarithmic plots of I_{DS}–V_G curves are shown in the insets. (Adapted from Maeng, J. et al., *Appl. Phys. Lett.*, 92, 233120, 2008. With permission.)

The current, threshold voltage, and carrier density were sensitively dependent on the gate bias sweep rate. These phenomena became more pronounced under environments with increased oxygen. The results of this study may offer how to characterize the surface effects of ZnO nanowire devices or other materials.

14.3.3 N-Channel Depletion-Mode and Enhancement-Mode ZnO Nanowire FETs

To date, although FETs using ZnO nanowires as active channels have been extensively investigated, most of the fabricated ZnO nanowire FETs were typically normally on type, n-channel depletion-mode (D-mode) behavior, which exhibited nonzero current at zero gate bias and negative threshold voltages. However, for a wide number of the applications of nanowire FETs in logic circuits, both D-mode and enhancement-mode (E-mode) FETs are required (Sedra and Smith 1991, Fortunato et al. 2004, Lee et al. 2006, Ma et al. 2007).

The electrical characteristics of D-mode and E-mode ZnO nanowire FETs are summarized in Figure 14.11. All the fabricated ZnO nanowire FETs were passivated by PMMA layer to remove the influence of water or gas molecules in ambient air on nanowire and to improve the FET performance by enhancing the gate-coupling effects. Note that although the structure of ZnO nanowire FET device is different from the conventional metal-oxide-semiconductor transistors, the operation mode of ZnO nanowire FETs is distinguished as D-mode or E-mode in terms of the polarity of the threshold voltage (Hong et al 2007). ZnO nanowire FETs with negative threshold voltages are normally on type, n-channel D-mode transistors, indicating that more negative gate bias should be applied to deplete carriers in the channel to reduce channel conductance, since the n-channel for current flow already exists at zero gate bias. In contrast, ZnO nanowire FETs with positive threshold voltages are normally off type, n-channel E-mode transistors, indicating that more positive gate bias is needed to make the channel, since the channel current does not flow at zero gate bias.

Figure 14.11a and b shows the electrical characteristics for n-channel D-mode ZnO nanowire FETs, whereas Figure 14.11c and d shows those for n-channel E-mode FETs. The I_{DS}–V_{DS} curves of both D-mode and E-mode FETs have well-defined linear regimes at low biases and saturation regimes at high biases. Figure 14.11b shows that the threshold voltage V_{th} is −4.14 V, indicating n-channel D-mode behavior. The I_{DS}–V_G plot in the semilogarithmic scale displays an on/off current ratio as large as 10^5 (inset of Figure 14.11b). In contrast, in the I_{DS}–V_G curves of Figure 14.11d, the threshold voltage V_{th} is +10.85 V, indicating n-channel E-mode behavior. The I_{DS}–V_G plot in the semilogarithmic scale shows an on/off current ratio as large as 10^6 (inset of Figure 14.11d).



FIGURE 14.11 (a) I_{DS}–V_{DS} and (b) I_{DS}–V_G curves for n-channel D-mode FET of ZnO nanowires grown on an Au-coated sapphire substrate. The inset shows the semilogarithmic plot of the I_{DS}–V_G curve at V_{DS} = 0.1 V. (c) I_{DS}–V_{DS} and (d) I_{DS}–V_G curves for n-channel E-mode FET of ZnO nanowires grown on an Au-catalyst-free ZnO film. The inset shows the semilogarithmic plot of the I_{DS}–V_G curve at V_{DS} = 0.1 V. (Adapted from Hong, W.-K. et al., *Appl. Phys. Lett.*, 90, 243103, 2007. With permission.)

14.3.4 Electronic Transport in Surface-Architecture-Controlled ZnO Nanowire FETs

It is well-known that interface roughness plays an important role in electronic transport for transistor devices (Hastas et al. 2002, Wang et al. 2005). In particular, the electronic transport in nanowire transistors can be influenced by the surface morphology of nanowires associated with the interface roughness, including the presence of surface trap states at the interfaces between the nanowires and the dielectric layers of nanowire FETs (Wang et al. 2004, Dayeh et al. 2007a,b). In order to investigate the influence of surface states and/or defects (associated with surface roughness and nanowire size) on the electronic transport properties in nanowire transistors, the surface morphology- and size-controlled ZnO nanowires were grown on the three sets of sapphire substrates with ZnO buffer films: (1) an undoped ZnO film with Au catalyst (denoted as Au–ZnO film) or without Au catalyst (denoted as ZnO film), (2) a gallium-doped ZnO film with Au catalyst (denoted as Au–GZO film) or without Au catalyst (denoted as GZO film), (3) an aluminum-doped ZnO film with Au catalyst (denoted as Au–AZO film) or without Au catalyst (denoted as AZO film). In addition, an Au-coated sapphire (denoted as Au-sapphire) substrate was also used for comparison with the ZnO buffer film-coated sapphire substrates. ZnO buffer films with approximately 1 μm thickness were grown on the sapphire substrates by a radio frequency (rf) sputtering system using a commercially sintered ZnO target, a Ga_2O_3 (1 wt%)-doped ZnO target, and an Al_2O_3 (1 wt%)-doped ZnO target. The Au thin film (~3 nm) was deposited on some substrates using an e-beam evaporator to form Au catalysts for the growth of nanowires.

Figure 14.12 shows the I_{DS}–V_G curves at V_{DS} = 0.1 V of the surface-architecture-controlled ZnO nanowire FETs, which exhibit different electronic transport characteristics. Insets in Figure 14.10 show the low-magnification TEM images of the surface-architecture-controlled ZnO nanowires grown on different substrates. The ZnO nanowires with relatively smaller diameters were found to have rougher surfaces than those with relatively larger diameters. The rough ZnO nanowires can have a larger surface-area-to-volume ratio than smooth ZnO nanowires. The FET devices made from smooth ZnO nanowires (nanowires grown on GZO, Au–AZO films, and Au-sapphire) have negative threshold voltages, indicating n-channel D-mode behavior that exhibits nonzero current at the zero gate bias. In contrast, the FETs made from rough ZnO nanowires (nanowires grown on Au–ZnO, ZnO, Au–GZO, and AZO films) have positive threshold voltages, indicating n-channel E-mode behavior that exhibits off-current status at zero gate bias.

Figure 14.13 shows cross-sectional schematics (Figure 14.13a and c) across the electrodes, ZnO nanowire, and dielectric layers with the corresponding equilibrium energy band diagram (Figure 14.13b and d) of the ZnO nanowire FETs at V_G = 0 V. Figure 14.13a and b shows the case for smooth ZnO nanowires, and Figure 14.13c and d depicts the case for rough ZnO



FIGURE 14.12 I_{DS}–V_G curves (measured at V_{DS} = 0.1 V) of FETs made from ZnO nanowires grown on (a) Au–ZnO and ZnO films, (b) Au–AZO and AZO films, (c) Au–GZO and GZO films, and (d) as Au-sapphire substrate. Labels are explained in the text. The insets show the low magnification TEM images of the surface-architecture-controlled ZnO nanowires. (Adapted from Hong, W.-K. et al., *Nano Lett.* 8, 950, 2008b. With permission.)



FIGURE 14.13 A cross-sectional view across the electrodes, ZnO nanowire, and dielectric layers (a and c) and the corresponding equilibrium energy band diagrams of nanowire FETs at $V_G = 0$ V (b and d) for smooth ZnO nanowires (a and b) and rough ZnO nanowires (c and d). (Adapted from Hong, W.-K. et al., *Nano Lett.*, 8, 950, 2008b. With permission.)

nanowires. For single crystalline semiconductor materials, band bending due to Fermi-level pinning can occur at surfaces and/or interfaces because the surface states and/or defects on single crystalline nanowires can induce trap energy levels at the interfaces (Wang et al. 2004, Calarco et al. 2005, Jones et al. 2007, Liao et al. 2007). The trapping of carrier electrons in the trap states can cause electron depletion in the channel, resulting in a threshold voltage shift and a conductance modulation (Ikeda 2002, Hossain et al. 2003, Fan et al. 2004a,b, Ju et al. 2007, Yoon et al. 2007). Correspondingly, the different electronic transport behavior between smooth and rough ZnO nanowires can be explained by considering the depletion of electron carriers due to surface band bending at the PMMA/ZnO nanowire and/or ZnO nanowire–SiO_2 interfaces as shown in Figure 14.13. Note that for the convenience of discussion and simplification of charge transport mechanism, it is assumed that the uniform charge and gate potential distribution for nanowires is with circular cross sections. However, the typical back-gate nanowire FET geometry can be significantly influenced by the cross-sectional shapes of nanowires and whether the nanowire is embedded or not (Wunnicke 2006). In addition, the back-gate nanowire FET geometry has the limitation in accuracy for calculating the gate-nanowire capacitance as well as the complication for the experimental extraction of transport parameters under the presence of depletion region and trap states (Dayeh et al. 2007a,b, Khanal and Wu 2007).

The depletion region by surface band bending and the effective conduction region (or effective diameter) can be estimated as (Taur and Ning 1998, Yu and Cardona 2001, Wang et al. 2004, Goldberger et al. 2005)



FIGURE 14.14 (a) Depletion width (W_d) and (b) effective diameter (D_{eff}) of ZnO nanowires as a function of surface barrier potential of ZnO nanowires at $N_D = 10^{16}$–10^{19} cm^{-3}.

$$W_d = \left(\frac{2\varepsilon_{ZnO}\, \phi_S}{e\, N_D} \right)^{1/2} \tag{14.1}$$

where

ϕ_S is the surface barrier potential
e is the electronic charge
N_D is the doping density
ε_{ZnO} is the dielectric constant of ZnO

Then by using the depletion approximation and charge neutrality condition (Taur and Ning 1998, Yu and Cardona 2001, Hossain et al. 2003), the surface trap density (N_t) can be estimated as $N_t = 2N_D W_d$. Thus, the effective diameter (D_{eff}) of the conduction layer in the nanowire channel can be expressed as

$$D_{eff} = D - \left(\frac{N_t}{N_D} \right) \tag{14.2}$$

where D is the geometrical diameter of nanowire. Therefore, by assuming that the $N_D = 10^{17}$/cm^3, $\varepsilon_{ZnO} = 8.66$ (Fan and Lu 2005), $\phi_S = 0.3$ eV, and the nanowire diameter (D) is 100 nm, we obtain $W_d = 54$ nm and $D < 2W_d$ from Equations 14.1 and 14.2 as shown in Figure 14.14.

14.4 Summary

In order to fabricate the functional devices from the ZnO nanowires, their fundamental properties must be carefully investigated because the presence of a large surface and interfacial area in nanowires can profoundly alter their performance. Therefore, it is essential to understand the surface-roughness- and size-dependent effects on the electronic transport properties of nanowire transistors. Furthermore, since ZnO nanowires are strongly influenced by chemical environments due to large surface-to-volume ratio, it is also important to study on the passivation effects of dielectric layer on the transport properties correlated to geometry and adsorbed species on the ZnO nanowires. In this chapter, we reviewed the electrical properties of FETs made from the surface-tailored smooth and rough ZnO nanowires that were grown by a vapor transport method. The transport properties of ZnO nanowire FETs are associated with the surface roughness, nanowire size, surface states, and/or defects as well as the surface chemistry in surrounding environments. The characteristics show that the electrical properties of ZnO nanowire FETs must be carefully investigated due to the various effects of nanowire surface and surrounding environments as well as interfaces. In the field of nanowire-based electronics, these explorations are important in understanding the transport properties and developing into practically useful device applications.

In future, in order to enable ZnO nanowire FETs to function as building blocks for the next-generation electronic circuitry, the ability to rationally grow nanowires with precisely the control of chemical composition, size, morphology, structure, and doping concentration will be required. Furthermore, the implementation of assembling any kind of functional nanodevices into highly integrated nanosystems must be intensively investigated.

Acknowledgment

This work was supported in part by the National Research Laboratory (NRL) Program, the National Core Research Center (NCRC) grant, and the World Clan University (WCU) program by the Korean Ministry of Education, Science and Technology (MEST).

References

Agarwal, R. 2008. Heterointerfaces in semiconductor nanowires. *Small* 4: 1872–1893.

Arora, N. 1993. *MOSFET Models for VLSI Circuit Simulation*. New York: Springer, Wien.

Bao, J., Zimmler, M. A., and Capasso, F. 2006. Broadband ZnO single-nanowire light-emitting diode. *Nano Lett.* 6: 1719–1722.

Calarco, R., Marso, M., Richter, T. et al. 2005. Size-dependent photoconductivity in MBE-grown GaN-nanowires. *Nano Lett*. 5: 981–984.

Cha, S. N, Jang, J. E., Choi, Y. et al. 2006. High performance ZnO nanowire field effect transistor using self-aligned nanogap gate electrodes. *Appl. Phys. Lett*. 89: 263102 (3 pp).

Chang, P.-C., Fan, Z., Chien, C.-J. et al. 2006. High-performance ZnO nanowire field effect transistors. *Appl. Phys. Lett*. 89: 133113 (3 pp).

Dai, Z. R., Pan, Z. W., and Wang, Z. L. 2003. Novel nanostructures of functional oxides synthesized by thermal evaporation. *Adv. Funct. Mater*. 13: 9–24.

Dayeh, S. A., Soci, C., Yu, P. K. L., Yu, E. T., and Wang, D. 2007a. Influence of surface states on the extraction of transport parameters from InAs nanowire field effect transistors. *Appl. Phys. Lett*. 90: 162112 (3 pp).

Dayeh, S. A., Soci, C., Yu, P. K. L., Yu, E. T., and Wang, D. 2007b. Transport properties of InAs nanowire field effect transistors: The effects of surface states. *J. Vac. Sic. Technol. B* 25: 1432–1436.

Dehuff, N. L., Kettenring, E. S., Hong, D. et al. 2005. Transparent thin-film transistors with zinc indium oxide channel layer. *J. Appl. Phys*. 97: 064505 (5 pp).

Dorfman, A., Kumar, N., and Hahm, J. 2006. Nanoscale ZnO-enhanced fluorescence detection of protein interactions. *Adv. Mater*. 19: 2685–2690.

Fan, Z. and Lu, J. G. 2005. Zinc oxide nanostructure: Synthesis and properties. *J. Nanosci. Nanotechnol*. 5: 1561–1573.

Fan, Z. and Lu, J. G. 2006. Chemical sensing with ZnO nanowire field-effect transistor. *IEEE Trans. Nanotechnol*. 5: 393–396.

Fan, Z., Chang, P.-C., Lu, J. G. et al. 2004a. Photoluminescence and polarized photodetection of single ZnO nanowires. *Appl. Phys. Lett*. 85: 6128–6130.

Fan, Z., Wang, D., Chang, P.-C., Tseng, W.-Y., and Lu, J. G. 2004b. ZnO nanowire field-effect transistor and oxygen sensing property. *Appl. Phys. Lett*. 85: 5923–5925.

Fortunato, E. M. C., Barquinha, P. M. C., Pimentel, C. C. M. B. G. et al. 2004. Wide-bandgap high-mobility ZnO thin-film transistors produced at room temperature. *Appl. Phys. Lett*. 85: 2541–2543.

Goldberger, J., Sirbuly, D. J., Law, M., and Yang, P. 2005. ZnO nanowire transistors. *J. Phys. Chem. B* 109: 9–14.

Hastas, N. A., Dimitriadis, C. A., and Kamarinos, G. 2002. Effect of interface roughness on gate bias instability of polycrystalline silicon thin-film transistors. *J. Appl. Phys*. 92: 4741–4745.

Hong, W.-K., Hwang, D.-K., Park, I.-K. et al. 2007. Realization of highly reproducible ZnO nanowire field effect transistors with n-channel depletion and enhancement modes. *Appl. Phys. Lett*. 90: 243103 (3 pp).

Hong, W.-K., Kim, B.-J., Kim, T.-W. et al. 2008a. Electrical properties of ZnO nanowire field effect transistors by surface passivation. *Colloids Surf. A* 313–314: 378–382.

Hong, W.-K., Sohn, J. I., Hwang, D.-K. et al. 2008b. Tunable electronic transport characteristics of surface-architecture-controlled ZnO nanowire field effect transistors. *Nano Lett*. 8: 950–956.

Hong, W.-K., Song, S., Hwang, D.-K. et al. 2008c. Effects of surface roughness on the electrical characteristics of ZnO nanowire field effect transistors. *Appl. Surf. Sci*. 254: 7559–7564.

Hossain, F. M., Nishii, J., Takagi, S. et al. 2003. Modeling and simulation of polycrystalline ZnO thin-film transistors. *J. Appl. Phys*. 94: 7768–7777.

Hsueh, T.-J., Chang, S.-J., Hsu, C.-L., Lin, Y.-R., and Chen, I.-C. 2007. Highly sensitive ZnO nanowire ethanol sensor with Pd adsorption. *Appl. Phys. Lett*. 91: 053111 (3 pp).

Huang, Y., Duan, X. F., Cui, Y. et al. 2001. Logic gates and computation from assembled nanowire building blocks. *Science* 294: 1313–1317.

Ikeda, H. 2002. Evaluation of grain boundary trap states in polycrystalline–silicon thin-film transistors by mobility and capacitance measurements. *J. Appl. Phys*. 91: 4637–4645.

Jones, F., Léonard, F., Talin, A. A., and Bell, N. S. 2007. Electrical conduction and photoluminescence properties of solution-grown ZnO nanowires. *J. Appl. Phys*. 102: 014305 (7 pp).

Ju, S., Lee, K., Janes, D. B. et al. 2006. ZnO nanowire field-effect transistors: Ozone-induced threshold voltage shift and multiple nanowire effects. In *Proceedings of the 6th IEEE Conference on Nanotechnology,* Cincinnati, OH, pp. 445–448.

Ju, S., Lee, K., Yoon, M.-H. et al. 2007. High performance ZnO nanowire field effect transistors with organic gate nanodielectrics: Effects of metal contacts and ozone treatment. *Nanotechnology* 18: 155201 (7 pp).

Jung, Y., Ko, D.-K., and Agarwal, R. 2007. Synthesis and structural characterization of single-crystalline branched nanowire heterostructures. *Nano Lett*. 7: 264–268.

Khanal, D. R. and Wu, J. 2007. Gate coupling and charge distribution in nanowire field effect transistors. *Nano Lett*. 7: 2778–2783.

Kim, W., Javey, A., Vermesh, O. et al. 2003. Hysteresis caused by water molecules in carbon nanotube field-effect transistors. *Nano Lett*. 3: 193–198.

Kim, H.-J., Lee, C.-H., Kim, D.-W., and Yi, G.-C. 2006. Fabrication and electrical characteristics of dual-gate ZnO nanorod metal-oxide semiconductor field-effect transistors. *Nanotechnology* 17: S327–S331.

Kind, H., Yan, H., Messer, B., Law, M., and Yang, P. 2002. Nanowire ultraviolet photodetectors and optical switches. *Adv. Mater*. 14: 158–160.

Klingshirn, C. 2007. ZnO: From basis towards applications. *Phys. Stat. Sol. B* 244: 3027–3073.

Kolmakov, A. and Moskovits, M. 2004. Chemical sensing and catalysis by one-dimensional metal-oxide nanostructures. *Annu. Rev. Mater. Res*. 34: 151–180.

Lagowski, J., Sproles, E. S. Jr., and Gatos, H. C. 1977. Quantitative study of the charge transfer in chemisorption; oxygen chemisorption on ZnO. *J. Appl. Phys*. 48: 3566–3575.

Law, M., Goldberger, J., and Yang, P. 2004. Semiconductor nanowires and nanotubes. *Annu. Rev. Mater. Res*. 34: 83–122.

Law, M., Greene, L. E., Johnson, J. C., Saykally, R., and Yang, P. 2005. Nanowire dye-sensitized solar cells. *Nat. Mater*. 4: 455–459.

Lee, C. A., Jin, S. H., Jung, K. D., Lee, J. D., and Park, B.-G. 2006. Full-swing pentacene organic inverter with enhancement-mode driver and depletion-mode load. *Solid State Electron*. 50: 1216–1218.

Li, Q. H., Liang, Y. X., Wan, Q. et al. 2004. Oxygen sensing characteristics of individual ZnO nanowire transistors. *Appl. Phys. Lett*. 85: 6389–6391.

Li, Q. H., Gao, T., Wang, Y. G., and Wang, T. H. 2005. Adsorption and desorption of oxygen probed from ZnO nanowire films by photocurrent measurements. *Appl. Phys. Lett*. 86: 123117 (3 pp).

Liao, Z.-M., Liu, K.-J., Zhang, J.-M., Xu, J., and Yu, D.-P. 2007. Effect of surface states on electron transport in individual ZnO nanowires. *Phys. Lett. A* 367: 207–210.

Look, D. C., Reynolds, D. C., Hemsky, J. W., Jones, R. L., and Sizelove, J. R. 1999. Production and annealing of electron irradiation damage in ZnO. *Appl. Phys. Lett*. 75: 811–813.

Lu, W. and Lieber, C. M. 2007. Nanoelectroncis from the bottom up. *Nat. Mater*. 6: 841–850.

Ma, R. M., Dai, L., and Qin, G. G. 2007. Enhancement-mode metal-semiconductor field-effect transistors based on single n-CdS nanowires. *Appl. Phys. Lett*. 90: 093109 (3 pp).

Maeng, J., Jo, G., Kwon, S.-S. et al. 2008. Effect of gate bias sweep rate on the electronic properties of ZnO nanowire field-effect transistors under different environments. *Appl. Phys. Lett*. 92: 233120 (3 pp).

Mieszawska, A. J., Jalilian, R., Sumanasekera, G. U., and Zamborini, F. P. 2007. The synthesis and fabrication of one-dimensional nanoscale heterojunctions. *Small* 3: 722–756.

Ng, H. T., Han, J., Yamada, T. et al. 2004. Single crystal nanowire vertical surrounded-gate field-effect transistor. *Nano Lett*. 4: 1247–1252.

Park, W. I., Yi, G.-C., Miyoung K., and Pennycook, S. J. 2003. Quantum confinement observed in ZnO/ZnMgO nanorod heterostructures. *Adv. Mater*. 15: 526–529.

Park, W. I, Kim, J. S., Yi, G.-C., Bae, M. H., and Lee, H.-J. 2004. Fabrication and electrical characteristics of high-performance ZnO nanorod field-effect transistors. *Appl. Phys. Lett*. 85: 5052–5054.

Park, W. I., Kim, J. S., Yi, G.-C., and Lee, H.-J. 2005. ZnO nanorod logic circuits. *Adv. Mater*. 17: 1393–1397.

Sadek, A. Z., Choopun, S., Wlodarski, W. et al. 2007. Characterization of ZnO nanoblet-based gas sensor for H_2, NO_2, and hydrocarbon sensing. *IEEE Sens. J*. 7: 919–924.

Schmidt-Mende, L. and MacManus-Driscoll, J. L. 2007. ZnO-nanostructures, defects, and devices. *Mater. Today* 10: 40–48.

Sedra, A. S. and Smith, K. C. 1991. *Microelectronic Circuits*, 3rd edn. Orlando, FL: Harcourt Brace College Publishers.

Soci, C., Zhang, A., Xiang, B. et al. 2007. ZnO nanowire UV photodetectors with high internal gain. *Nano Lett*. 7: 1003–1009.

Song, S., Hong, W.-K., Kwon, S.-S., and Lee, T. 2008. Passivation effects of ZnO nanowire field effect transistors under oxygen, ambient, and vacuum environments. *Appl. Phys. Lett*. 92: 263109 (3 pp).

Streetman, B. G. and Banerjee, S. 2000. *Solid State Electronic Devices*. Upper Saddle River, NJ: Prentice Hall.

Suehiro, J., Nakagawa, N., Hidaka, S.-I. et al. 2006. Dielectrophoretic fabrication and characterization of a ZnO nanowire-based UV photosensor. *Nanotechnology* 17: 2567–2573.

Sun, Y., Fuge, G. M., and Ashfold, M. N. R. 2006. Growth mechanisms for ZnO nanorods formed by pulsed laser deposition. *Superlattice. Microstruet*. 39: 33–40.

Sze, S. M. 1981. *Physics of Semiconductor Devices*. New York: John Wiley & Sons.

Takata, M., Tsubone, D., and Yanagida, H. 1976. Dependence of electrical conductivity of ZnO on degree of sintering. *J. Am. Ceram. Soc*. 59: 4–8.

Taur, Y. and Ning, T. H. 1998. *Fundamentals of Modern VLSI Devices*. Cambridge, U.K.: Cambridge University Press.

Wade, T. L., Hoffer, X., Mohammed, A. D. et al. 2007. Nanoporous alumina wire templates for surrounding-gate nanowire transistors. *Nanotechnology* 18: 125201 (4 pp).

Wang, D., Chang, Y.-L., Wang, Q. et al. 2004. Surface chemistry and electrical properties of germanium nanowires. *J. Am. Chem. Soc*. 126: 11602–11611.

Wang, J., Polizzi, E., Ghosh, A., Datta, S., and Lundstrom, M. 2005. Theoretical investigation of surface roughness scattering in silicon nanowire transistors. *Appl. Phys. Lett*. 87: 043101 (3 pp).

Wang, D., Seo, H. W., Tin, C.-C. et al. 2006. Effects of postgrowth annealing treatment on the pthotoluminescence of zinc oxide nanorods. *J. Appl. Phys*. 99: 113509 (3 pp).

Wolkenstein, T. 1991. *Electronic Processes on Semiconductor Surfaces during Chemisorptions*, (ed.) R. Morrison. New York: Consultants Bureau.

Wunnicke, O. 2006. Gate capacitance of back-gated nanowire field-effect transistors. *Appl. Phys. Lett*. 89: 083102 (3 pp).

Xiong, H. D., Wang, W., Li, Q. et al. 2007. Random telegraph signals in n-type ZnO nanowire field effect transistors at low temperature. *Appl. Phys. Lett*. 91: 053107 (3 pp).

Yang, P., Yan, H., Mao, S. et al. 2002. Controlled growth of ZnO nanowires and their optical properties. *Adv. Funct. Mater*. 12: 323–331.

Yeom, D., Keem, K., Kang, J. et al. 2008. NOT and NAND logic circuits composed of top-gate ZnO nanowire field-effect transistors with high-k Al_2O_3 gate layers. *Nanotechnology* 19: 265202 (5 pp).

Yoon, Y., Lin, J., Pearton, S. J., and Guo, J. 2007. Role of grain boundaries in ZnO nanowire field-effect transistors. *J. Appl. Phys*. 101: 024301 (5 pp).

Yu, P. Y. and Cardona, M. 2001. *Fundamentals of Semiconductors: Physics and Materials Properties*. Berlin, Germany: Springer-Verlag.

Zhang, Y., Kolmakov, A., Chretien, S. et al. 2004. Control of catalytic reactions at the surface of a metal oxide nanowire by manipulating electron density inside it. *Nano Lett*. 4: 403–407.

15

C_{60} Field Effect Transistors

15.1 Introduction 15-1
Fullerene (C_{60}) • Solid C_{60} Crystals • C_{60} Field Effect Transistors (C_{60} FETs) • Bell Laboratory Misconduct • Interfaces between Solid C_{60} and Insulator Films • Field Effect Doping • Operation Principles of C_{60} FETs • Superconductivity • Guides for This Chapter
15.2 Fullerene (C_{60}) 15-4
Discovery of Fullerene Family • Synthesis of C_{60} Molecules • Properties of C_{60} Molecule
15.3 Solid C_{60} 15-7
Crystal Structure • van der Waals Interaction of C_{60} • Structural Phase Transition • Electronic Structures • Optical Properties
15.4 van der Waals Epitaxy of C_{60} 15-10
Molecular Beam Epitaxy • van der Waals Epitaxy • Initial Growth Surface
15.5 Principles of Organic FET Functions 15-16
Device Structures of OFETs • Metal/Organic Layer Interface • Field Effect Doping for Solid C_{60} Layers • Am-Bipolar OFET Operations
15.6 Fabrication of Fullerene Field Effect Transistors (C_{60} FET) 15-18
Substrates: SiO_2 or AlN • Device Process • C_{60} Epitaxy • Measurements of FET Performance
15.7 Characterization of C_{60} FETs on SiO_2 or on AlN 15-19
I–V Characteristics • Sub-Threshold Region
15.8 Summary 15-20
References 15-21

Akihiro Hashimoto
University of Fukui

15.1 Introduction

15.1.1 Fullerene (C_{60})

Fullerene is a new carbon material system closely related with carbon micro-clusters and/or carbon ultrafine particles. In general, *micro-clusters* are defined as atomic clusters consisting of less than 1000 atoms. On the other hand, *ultrafine particles* are usually defined as particles consisting of atoms above the upper limit of micro-clusters. The discovery of fullerene was achieved in the process of researching of carbon micro-clusters and/or carbon ultrafine particles. Fullerene is the name of a family of carbon clusters such as C_{60}, C_{70}, and so on. In this chapter, we will use the word "fullerene" mainly as the name of the C_{60} clusters.

C_{60} clusters were first physically observed as a magic number cluster in the mass spectrum of cluster molecular beams, although their theoretical prediction had already existed in the pioneering research of these clusters. Furthermore, several large-scale production methods for C_{60} clusters were found in a study on the formation process of carbon fine particles from the resistive heating for carbon rods. In a sense, the discovery of the fullerene was due to serendipity. Further information will be provided in Section 15.2.

15.1.2 Solid C_{60} Crystals

High-purity solid C_{60} molecular crystals can be obtained from high-purity C_{60} powders by using the sublimation method or the vacuum evaporation method in an ultrahigh vacuum (UHV) environment similar to the molecular beam epitaxy (MBE). This method is preferable to the solution growth from a solvent for the separation of the C_{60} molecules because of the reduction of residual impurities during growth. The solid C_{60} crystal has a face-centered cubic structure (fcc, $Fm\bar{3}m$ symmetry) above 260 K, and the lattice constant is 1.4154 nm at 270 K. It is well known that each of the C_{60} molecules in the solid C_{60} crystal rotates continuously very fast with a rotation correlation time on the order of 10 ps. The C_{60} molecules behave as a sphere with a diameter of 0.71 nm. Therefore, the solid C_{60} crystal is called "the plastic crystal" with "a rotational diffusion" of the C_{60} molecules. The rotational diffusion means that the degrees of freedom of the molecular rotation are softened before the ones of the translational displacements. The electronic structure of the solid C_{60} has been extensively studied by many groups, and its semiconductor properties such as an energy band gap of about 1.6 eV are commonly known. Moreover, one of the alkali-doped C_{60}s, $RbCs_2C_{60}$, shows superconductivity with a critical temperature of 33 K. In addition, it is well known that all alkali-doped C_{60} systems, in general, show superconductivity. The epitaxy of the solid C_{60} layer has also been extensively studied by many groups known as the van der Waals epitaxy. The concept of lattice mismatches of the epitaxial layers to the substrate is applicable as they are similar to the cases of the conventional semiconductor epitaxy. Therefore, it is a little difficult to obtain high-quality solid C_{60} layers without any dislocations and/or any boundary for high lattice-mismatch combinations even in the van der Waals epitaxy. Further information will be provided in Sections 15.3 and 15.4.

15.1.3 C_{60} Field Effect Transistors (C_{60} FETs)

Fullerene field effect transistors (C_{60} FETs) are typical of the family of the organic FETs (OFETs). It is well known that solid C_{60} FETs have the highest electron mobility in the organic FET family, although most OFETs show the p-type, as shown in Figure 15.1 [1]. The various types of the OFET have been extensively studied in recent years, because of their large area fabrication, flexibility, light weight, and low cost. The most essential reason for their extensive research may be due to a resource problem in conventional Si and compound semiconductors. Carbon materials exist almost infinitely on earth and the modification of carbon compounds is very easy to obtain, because of vast chemical knowledge known about carbon compounds. Essentially, organic materials used in the OFETs are high-resistance materials without doping and, moreover, rather unique electronic properties appear even in the doped organic materials due to a strong electron–lattice interaction compared with conventional covalent semiconductors such as Si and GaAs. The doping materials in organic semiconductors, in general, do not form impurity levels in the mid-gap of the band gap. However, the electrons of highest isolated occupied molecular orbital (HOMO) levels of the doping materials can transfer directly to the lowest unoccupied molecular orbital (LUMO) levels of the organic semiconductor. In general, such charge transfer process is often accompanied with strong lattice distortion. Consequently, the mid-gap level or the impurity band never forms in conductive organic materials. Almost all conductive organic materials have similar electronic properties to intrinsic semiconductor systems even in impurity doping. The conductivity in the organic materials essentially comes from the properties of the electrode metals for organic materials. In that sense, the conventional Shockley–Bardeen theory cannot be applied to OFET operations. The situation for general OFETs is also common for solid C_{60} FETs. Further information will be provided in Sections 15.5 and 15.6.

15.1.4 Bell Laboratory Misconduct

In 2001, a research group in the Bell Laboratory had reported about the high-temperature superconductivity in the solid C_{60} FETs, and consequently an intensive study of C_{60} FET superconductivity has been performed by many research groups. However, none of the groups could show similar high-temperature superconductivity such as presented in the Bell Laboratory's presentation. This story is the beginning of infamous misconduct by Bell Laboratory. The investigation team for misconduct was immediately formed and they concluded that all reports for the solid C_{60} FET superconductivity from the Bell Laboratory were false [2]. One of the causes of the misconduct may be due to the severe competitive circumstances in the U.S. research society based on the market-driven principle in the research field. From a scientific viewpoint, we have not succeeded in forming



FIGURE 15.1 Improvement of mobility in OFET research field.

an ideal interface between the solid C_{60} and the insulator layers in the FET structure until now. In that sense, the superconductivity problem in the solid C_{60} FET remains until now an open question, in spite of the Bell Laboratory misconduct.

15.1.5 Interfaces between Solid C_{60} and Insulator Films

The interface between the solid C_{60} layer and the insulator layer such as SiO_2 is formed mainly by two different ways. The first way is a conventional FET fabrication process technique for C_{60} bulk. The second is an epitaxy of the solid C_{60} layer on a patterned insulator layer with electrode metals. In both ways, there are several problems in forming an ideal interface. Namely, there are damage problems accompanied with the formation process of the insulator layer on the C_{60} bulk surface in the first way, and lattice mismatch problems for the solid C_{60} epitaxy in the second way. The interface problem is very essential for electron transport; therefore, the characteristics of the C_{60} FETs such as I–V characteristics are strongly dependent on the interfacial states. It is well known that the I–V characteristics depend on adsorption molecules such as OH^- ions during the I–V measurements under the atmosphere. The conventional sputtering method to form the insulator layers on the solid C_{60} surface easily results in physical plasma damages from ions and/or the sputtered elements from the target during the deposition of the layers. Therefore, we can only obtain a rather disordered interface like the interface found between the solid C_{60} and the SiO_2 layers. On the other hand, even in the second way, we can also only obtain the amorphous C_{60} interface when the solid C_{60} layers are grown on the amorphous surfaces like SiO_2. The author's research group has proposed a new insulator layer made of epitaxial single crystalline AlN grown on the SiC and/or the Si substrates for single crystalline solid C_{60} growth. In principle, we can obtain a single crystal epitaxial layer of the solid C_{60} on the single crystalline AlN insulator layer. We will discuss about this new structure and the FET characteristics in the later sections. In these sections, we will see that we can obtain a higher performance C_{60} FET in comparison with the FET structures consisting of conventional amorphous solid C_{60}/SiO_2. Further information will be found in Sections 15.5 through 15.7.

15.1.6 Field Effect Doping

It is well known that chemical doping in solid C_{60} is not as controllable as with conventional semiconductors such as Si. This issue is the common problem for all the organic materials, including solid C_{60}. The key point of the problem is that almost all of organic materials behave as ideal intrinsic semiconductors with low conductivity and without mid-gap states. The carriers come from the source and the drain electrodes into the channel layer induced by an applied gate voltage. The carrier concentrations of the channel layer can be varied by controlling the supply of the carriers from the source and the drain electrodes through the modulation of the applied gate bias voltages. Certainly, in high-performance OFET, the am-bipolar transistor operation has been observed as direct proof of field effect doping, rather than by conventional chemical doping. Namely, this doping technique is completely different to chemical doping in conventional FET, in which the carriers come from bulk conduction bands due to the band bending at the interface, except for the similarity of the device structures. An important advantage of the field effect doping technique is am-bipolar carrier injections by controlling the polarity of the gate bias voltage. The operation polarity is determined by the combination of metals and organic materials. For example, when gold, Au, is used as an electrode, the channel layer of the C_{60} FET shows n-type conduction and it is said that the solid C_{60} is n-type material.

15.1.7 Operation Principles of C_{60} FETs

When the channel layer is formed by applying the gate bias voltage, the modulation of the gate bias voltage produces modulation of the channel conductance between the source and the drain. The typical characteristics of the drain current and the drain-source voltage (I_D–V_{SD} characteristics) with some gate voltage (as shown in Figure 15.2 as a schematic illustration) consist of three parts: the sub-threshold, the linear, and the saturation regions. In the sub-threshold region, the drain current gradually increases with the drain-source voltage due to the hopping transport mechanism. In the linear region, the uniform channel layer is formed by the applied gate voltages. Therefore, the drain current is proportional to the drain-source voltage just before the "pinch-off" voltage, according to the conventional FET theory. The channel layer just disappears due to a reverse bias voltage near the drain electrode at the pinch-off voltage. After the formation of depletion regions near the drain electrode at the pinch-off voltage, the external excess applied voltage of the drain-source electrodes is used as an extension of the depletion region in the channel layer. Therefore, in this region, the drain current saturates as a function of the applied drain-source voltage. These pictures are commonly observed for conventional semiconductor FET performances, except for the sub-threshold regions. However, in principle, the solid C_{60} FET, and in general, also high-performance OFETs are expected to result in the am-bipolar operation, which is completely different from the



FIGURE 15.2 Schematic illustration of typical I–V characteristics of OFET.

conventional semiconductor FET, because of the difference in the origin of the induced channel carriers. In solid C_{60} FETs, we can inject both the electrons and the holes into the channel layers. In principle, we can control the *p*- and/or the *n*-channels of FETs by using the polarity of the external applied gate voltage.

15.1.8 Superconductivity

In the future, it is expected that the C_{60} FET will possibly have superconductivity with a considerably high critical temperature, in spite of the Bell Laboratory misconduct. If we can realize the ideal interface between the high-quality intrinsic solid C_{60} layer and the insulator layer, then the am-bipolar operation will be observed with very high mobility. This will be possible, though the present stage for C_{60} FETs is very far from achieving the above-ideal situation even with the highest performances. Therefore, the superconductivity of the C_{60} FET still now remains an open question. It is a very interesting issue, especially related to the holes' injection in the FET structure. We have already proposed a new type of C_{60}/single crystalline AlN FET structures on SiC and/or Si substrates for investigating the possibility of superconductivity with a considerably high critical temperature. However, so far, the preliminary C_{60} FET performance is not at all so high.

15.1.9 Guides for This Chapter

In this chapter, we discuss in detail the basic and the advanced topics about C_{60} FETs. In Section 15.2, we describe the fundamental physical properties of C_{60} molecules, including a brief historical review, a large-scale production synthesis method, an electronic structure of C_{60} molecules, and the significant aspects of C_{60} FETs. In Section 15.3, we describe the various physical properties of solid C_{60} crystals. In Section 15.4, we describe the van der Waals epitaxy of the solid C_{60} layer to be used in a realistic application of the FET structures. In Section 15.5, the basic concept of organic FETs, including the C_{60} FET, will be described in order to understand the C_{60} FET operation. In Section 15.6, the realistic fabrication process of the C_{60} FET is discussed in detail. In Section 15.7, the characterizations of the C_{60} FET performance are described and we discuss about a strategy for the realization of high-performance C_{60} FETs. Finally, we summarize this article in Section 15.8.

15.2 Fullerene (C_{60})

In this section, we describe the minimal knowledge about fullerene, in particular, the C_{60} molecule, to help in understanding the following sections. For those who want to know more details than presented in every section, look in the review and textbook references at the end of this chapter.

15.2.1 Discovery of Fullerene Family

The discovery of fullerene certainly gave a heavy shock to the scientific society, especially in carbon chemistry. In 1985, Curl and coworkers discovered fullerene, the C_{60} molecules, at the Sussex and the Rice Universities [3]. It is well known that the name of "fullerene" is named after Richard Buckminster Fuller who is one of the representative modern architects in the United States. The existence of the C_{60} molecule had already theoretically been predicted as a "corannulene" molecule by Eiji Osawa in 1970. He noticed that the structure of a corannulene molecule was a subset of a soccer-ball shape and, therefore, he predicted that a full ball shape could also exist. Unfortunately, he reported his idea only in a Japanese journal, but news of his discovery did not reach Europe and America. Before the discovery of the fullerene, the only known stable structures of the carbon system were diamond, graphite, and amorphous carbon. Therefore, most people thought that it would be difficult for a new structure of the carbon system to exist, because of the long research history of carbon systems by the chemistry. However, in 1985, Harold Kroto, who was studying the origin of interstellar molecules, was interested in interstellar molecules that have curious absorption and emission spectra. He thought there was a possibility that some carbon systems, produced in the supernova process, were strongly related with the origin of the emission spectra. Initially, Kroto did not think about the C_{60} molecular structure at the beginning of the 1980s, but he thought about some carbon molecules with strange chain structures. In 1984, Kroto visited the Richard Smalley Lab in Rice University to discuss a new proposal for "a laser-vaporization cluster beam mass spectroscopy" (see Figure 15.3) in which a similar condition to the supernova process for the carbon cluster formation seems to have been generated [4]. The experimental results were unexpected. The mass spectra for the laser-ablated carbon systems showed strong intensity in the C_{60} molecule [5–7]. However, Kroto, Smalley,



FIGURE 15.3 Laser-vaporization cluster beam mass spectroscopy.

and Robert Curl could not explain at all the stable structure of the C_{60} molecule when they first observed the strong mass spectra from it. It is said that they had a sudden inspiration about the stable structure of the C_{60} molecule from a geodesic dome designed by a famous modern American architect, Buckminster Fuller. The geodesic dome has a mechanically stable structure due to the proper dispersion of the internal force of the dome. They reported their ideas about the stable structure of the C_{60} in an academic paper with several other scientific data. However, many carbon researchers did not pay so much attention to the paper. The researchers needed direct proof such as optical spectroscopic data of the C_{60} for the discussions about the structure of C_{60} molecule to be taken seriously. However, the amounts of C_{60} molecules produced by the laser-vaporization cluster beam mass spectroscopy were not enough at all for an optical spectroscopic measurement in spite of the high generation rate of the C_{60} molecules. It was difficult to construct an apparatus large enough for the laser-vapor evaporation method of the large-scale production of the C_{60} molecules to occur. Therefore, the fullerene proposal by Kroto et al. had to wait until large-scale production methods for the fullerene had improved.

15.2.2 Synthesis of C_{60} Molecules

In 1990, the American and German cooperative research groups found a new “gas evaporation method” for the large-scale production of fullerene [8]. In the new method, a highly purified carbon rod was directly heated by an electric current under the He gas ambient of 100 Torr. The yield of C_{60} molecules by using this method was about 10%. Moreover, Smalley’s group also developed another large-scale production method named the “contact arc method,” as shown in Figure 15.4, in which the maximum yield of C_{60} molecules reached at about 13% [9]. Some other large-scale production methods such as the RF-heating method [10] and the gas burning method [11] have been developed by now. They also have been used for the commercial large-scale production of C_{60} molecules.



FIGURE 15.4 Contact arc method.

Typical carbon soot produced by the contact arc method, for example, usually contains 0%–15% fullerene, in which C_{60} molecules consist of 70%–85% of the weight, 10%–15% of the weight is C_{70}, and other higher-order residual fullerene molecules. Krätschmer et al. discovered abstraction methods for obtaining C_{60} molecules from carbon soot produced by large-scale production methods like the gas evaporation method. They found out that fullerene such as C_{60} molecules can be easily dissolved into an organic solvent, while the rest of the carbon cannot be dissolved. They also observed that the sublimation temperatures of C_{60} and C_{70} molecules in UHV are different from each other: 300°C and 350°C for the C_{60} and C_{70} molecules, respectively [8]. The high purity abstraction rate of more than 99.97% of the C_{60} molecules from the soot was achieved by this molecular distillation method using the sublimation apparatus with a constant temperature gradient [12]. Furthermore, very recently, it has been reported that a purity of more than 99.99999% classes has been achieved by a N_2 atmospheric train-sublimation method by Laudise et al. (see Figure 15.5) [13].

On the other hand, liquid chromatography such as open-column chromatography for C_{60} molecules [14] and high-performance liquid chromatography (HPLC) [15] are also very popular and useful methods for the abstraction of C_{60} and higher-order fullerene like the C_{70} molecules. However, in general, the purity of the fullerene obtained by these methods cannot be as high compared with the molecular distillation method because of residues of the organic solvent.

In any case, the C_{60} molecular powder with a purity of 99.98% can be easily bought commercially. For the van der Waals epitaxy of solid C_{60} for the FETs, in general, the C_{60} molecular powder with the purity more than 99.98% has been used.

15.2.3 Properties of C_{60} Molecule

The hypothesis for the structure of the Buckminster fullerene C_{60} molecule proposed by Kroto and Smalley in 1985 was researched for the large-scale production of C_{60} samples using various types of spectroscopy. In particular, there were several important theoretical predictions about the lattice-vibration spectrum, for example, for the infrared absorption (IR) spectrum [16–19]. Theoretical investigations predicted that only the first four-order vibration modes in the IR spectrum were active among 174 degrees of freedom in the lattice vibrations of the C_{60} molecules, when the structure was a soccer-ball shape. Indeed, Krätchmer and Huffman used the four IR modes in the IR spectra to identify the C_{60} molecules in the carbon soot produced by their gas evaporation method, as mentioned in their 1990 academic paper on the large-scale production of fullerene.

According to their theoretical predictions, the C_{60} molecules with I_h symmetry have 46 vibration modes, including many



FIGURE 15.5 N_2 atmospheric train-sublimation method.

degenerated modes with 174 degrees of freedom in lattice vibrations. The 46 inner-molecule lattice-vibration modes of the C_{60} molecule were classified by the I_h symmetry as follows [20]:

$$\Gamma(C_{60}) = 2A_g + 3F_{1g} + 4F_{2g} + 6G_g + 8H_g + A_u + 4F_{1u} + 5F_{2u} + 6G_u + 7H_u \tag{15.1}$$

where the $4F_{1u}$ modes are only allowed for the IR active mode. On the other hand, the 10 modes of the $2A_g$ and the $8H_g$ modes are also allowed as Raman active modes. The IR (A) and the Raman (B) spectra from the solid C_{60} layers deposited on the Si substrate are shown in Figure 15.6. The 4 IR and the 10 Raman peaks in the spectra are clearly observed [21].

Other strong experimental data from the soccer-ball shape of C_{60} molecules can be obtained by ^{13}C nuclear magnetic resonance (^{13}C-NMR) measurements. Indeed, the Kroto research group at Sussex University and the Bethune research group at IBM (Almaden) obtained only one NMR signal due to the high I_h symmetry in the ^{13}C-NMR measurements [14,22]. Moreover, the x-ray diffraction for the $C_{60}(OsO_4)$ single crystal [23] and the neutron diffraction for the low-temperature solid C_{60} crystal succeeded in obtaining more direct proof of the soccer-ball shape structure of C_{60} molecules after stopping of the high-speed rotation of the C_{60} molecules by using various scientific techniques [24].

Buckminster fullerene consists of 12 pentagons and 20 hexagons that is a geometrical stable combination due to Euler's theorem as follows:

$$V + F = E + 2 \tag{15.2}$$

where V, F, and E are the numbers of the vertex, the face, and the side of a polyhedron, respectively. Euler's theorem is very helpful for the discussion about the geometrical stability of the higher-order fullerene structures. However, because the chemical stability is not equal to the geometrical one, we have to take into account the electronic structure of Buckminster fullerene. In the simplest calculation using the Hückel approximation, we can estimate the electron energy levels in the C_{60} molecule. When the electron pairs, in which each electron has the opposite spin from each other, occupy the lowest energy level and the electron pairs finally form a closed electron shell, the Buckminster fullerene becomes chemically stable, in addition to being geometrically stable. This is known as the "Hückel rule," and it is used for describing the chemical stability of the fullerene family.



FIGURE 15.6 Infrared (A) and Raman (B) spectra from solid C_{60} layers deposited on Si substrate.

The electronic structure of the C_{60} molecule is very unique because it has many degenerate levels due to high I_h symmetry. In the Hückel approximation, it is estimated that the HOMO level, h_u, is five-folded degenerated and the LUMO level, t_{1u}, is three-folded, and that the energy gap between the HOMO and the LUMO levels is about 1.5 eV. Therefore, it is assumed that the solid C_{60} crystal becomes a semiconductor [25–28]. A scanning tunneling microprobe (STM) observation under the UHV showed that the C_{60} molecules on a well-defined solid surface like Cu (111) or Si (111) 7 × 7 do not spin due to the interaction between the surface and the C_{60} molecules induced by a charge transfer from surface to the C_{60} molecules. Many other interesting properties of the C_{60} molecules are referred to another chapter in this handbook series.

15.3 Solid C_{60}

A solid C_{60} single crystal without any residual organic solvent can be obtained by using the sublimation method or a vacuum evaporation method like MBE, while solid C_{60} crystals grown by solution growth can easily include residual solvent.

15.3.1 Crystal Structure

The structure of the solid C_{60} bulk crystal grown by using the sublimation method has two kinds of structural phases. They are a high-temperature and a low-temperature phase above and below 260 K, respectively [29]. In the high-temperature phase above 260 K, the structure of the solid C_{60} is a fcc lattice with ($Fm\bar{3}m$) symmetry in the space group and the lattice constant is 1.4145 nm. The four C_{60} molecules in the unit cell of the solid C_{60} crystal look like balls with a diameter of 0.71 nm due to the high-speed spin rotation in the x-ray diffraction measurements. Each C_{60} molecule in the solid C_{60} crystal rotates very fast continuously with a rotation correlation time on the order of 10 ps, estimated from the line width of the ^{13}C-NMR spectra [30]. The rotational diffusion property of the C_{60} molecules in the solid C_{60} bulk was shown estimating the neutron inelastic scattering and the rotation potential of the C_{60} molecules that have many local minima with the thermal activation energy of 35 meV [31]. Therefore, the solid C_{60} crystal is called “the plastic crystal” with a rotational diffusion of C_{60} molecules, in which the degrees of freedom of molecular rotation are softened before the translational displacement.

15.3.2 van der Waals Interaction of C_{60}

The lattice vibration of solid C_{60} consists of two kinds of vibration modes, an inner-molecular and an intermolecular vibration. The inner-molecular vibration mode is due to the vibration in the degree of freedom in the C_{60} inner molecule. Therefore, the spectrum of the inner-molecule vibration is very similar to the isolated C_{60} molecule, described in Section 15.2. On the other hand, the intermolecular vibration modes are the proper vibration modes of solid C_{60}, and there are three kinds of modes: acoustic, optical, and libration modes. The phonon frequency of all modes (0–50 cm^{-1}) is lower than the vibration modes in conventional covalent crystal modes such as Si (0–530 cm^{-1}), because of the large mass of the fullerene molecules and the weak van der Waals interaction between the C_{60} molecules. The innermolecular vibration modes have a considerable higher frequency than the intermolecular vibration modes [32].



FIGURE 15.7 Lattice constant of solid C_{60} as a function of temperature.

15.3.3 Structural Phase Transition

The crystal structure of solid C_{60} suddenly changes from a fcc structure to a simple cubic (sc) structure when below 270 K in the first-order phase transition, because of the discontinuity in the variations of the lattice constant, as shown in Figure 15.7 [33].

15.3.4 Electronic Structures

The electronic structure of solid C_{60} has been extensively studied by many groups. They have already revealed certain aspects of its semiconductor nature, for example, the energy band gap of about 1.5 eV. Figure 15.8 shows the band structure of the fcc C_{60} crystal calculated by the density functional method, accompanied with π electron levels from an isolated C_{60} molecule calculated by the Hückel method, as presented by Saito and Oshiyama [28]. The electronic structure has a rather small dispersion and a narrow bandwidth (0.4 eV). They are just the origin of the band gap of fcc solid C_{60}. The solid C_{60} is a direct band-gap semiconductor in which the gap is the difference between the bottom of the LUMO and the top of the HOMO at X point.

The photo-emission spectroscopy (PES) and the inversion photo-emission spectroscopy (IPES) are very useful in directly observing the electronic structures of solid C_{60}. The HOMO–LUMO gap (3.7 eV) estimated from the PES and IPES spectra is larger than the gap estimated by the other techniques such as the absorption measurements. The middle energy points of the HOMO and the LUMO bands are above 2.25 eV and below 1.15 eV from the Fermi level, respectively. It is said that the large band gap in the PES and the IPES is due to the electron correlation effect [34].



FIGURE 15.8 Band structure of fcc C_{60} crystal calculated by density functional theory.

The HOMO and the HOMO-1 bands, which come from the h_u and the h_g-g_g, respectively, are π electron-like states. These bands are 5- and the 9-degenerated electron states. On the other hand, the empty states consist of the LUMO and the LUMO+1 bands that originate from the t_u and the t_g. They form 3-degenerated states in the empty bands.

The electrical conductivity σ of solid C_{60} is extremely low, that is, from 10^{-8} to 10^{-14} $(\Omega\ \text{cm})^{-1}$. Therefore, solid C_{60} is like an insulator [35,36]. The fluctuation in electrical conductivity is due to impurities and defects. Furthermore, there are difficulties in measuring high-resistance materials. The relative dielectric constant of solid C_{60} is 4.4 ± 0.2 [37]. The relative deviation of the dielectric constant ($\Delta\varepsilon/\varepsilon$) is due slightly to the temperature with a small discontinuity at 260 K. This variation is due to the phase transition from the fcc to the sc structures and a broad step-like dependence around 165 K in the low-temperature phase which occurs due to a disorder in the molecule's axis in the pentagon and hexagon directions [38].



FIGURE 15.9 Absorption and luminescence spectra for solid C_{60} deposited on a quartz substrate.

15.3.5 Optical Properties



FIGURE 15.10 Photoluminescence spectrum from solid C_{60} at 1.2 K.

The absorption and luminescence spectra for solid C_{60} deposited on a quartz substrate are shown in Figure 15.9 [39]. Three strong absorption peaks are observed at 221, 271, and 347 nm. These peaks come from the π–π* transition of the C_{60} molecules, because the peaks are also observed from C_{60} molecules dispersed in an organic solvent. The broad and weak bands, observed at around 600 nm, come from the forbidden transition between the t_{1u} and h_u levels. In contrast to these absorption peaks, the rather strong band at 430–520 nm comes from the proper absorption of solid C_{60}. A broad photoluminescence spectrum with peak energy at 737 nm is observed above 10 K, as shown in Figure 15.9b. However, the photoluminescence spectrum at 1.2 K, as shown in Figure 15.10, shows two luminescence bands excited by



FIGURE 15.11 Optical measurements results from infrared to ultraviolet wavelengths for $\varepsilon_1(\omega)$ and/or the $\varepsilon_2(\omega)$.

734 and 684 nm. The 734 and the 684 nm excited bands consist of the electronic transition and a vibronic transition [40].

The dielectric function, $\varepsilon(\omega)$, consists of the real part $\varepsilon_1(\omega)$ and the imaginary part $\varepsilon_2(\omega)$, as follows:

$$\varepsilon(\omega) = \varepsilon_1(\omega) + i\varepsilon_2(\omega) \tag{15.3}$$

The complex refractive index, $n_c(\omega)$, is the root of the dielectric function:

$$n_c(\omega)^2 = \varepsilon(\omega) \tag{15.4}$$

in which $n_c(\omega)$ consists of the real part, the refractive index $n(\omega)$, and the imaginary part, the extinction coefficient $\kappa(\omega)$. The $\varepsilon_1(\omega)$ and the $\varepsilon_2(\omega)$ are connected with the $n(\omega)$ and the $\kappa(\omega)$, as follows:

$$\begin{aligned} \varepsilon_1(\omega) &= n(\omega)^2 - \kappa(\omega)^2 \\ \varepsilon_2(\omega) &= 2n(\omega)\kappa(\omega) \end{aligned} \tag{15.5}$$

These optical constants can be obtained from the absorption and the reflection spectra. The dielectric function is the most important and basic physical quantity concerning the optical properties of the solid C_{60} layers. The typical results of the optical measurements results from the infrared to the ultraviolet wavelengths for the $\varepsilon_1(\omega)$ and/or the $\varepsilon_2(\omega)$ are shown in Figure 15.11 [41]. In the measurements, the solid 100 nm thick C_{60} layers were deposited on proper substrates such as Si and glass by using the vacuum evaporation method. Many coupled modes were observed in the thick solid C_{60} spectra in addition to inner-molecular F_{1u} vibration modes (526, 576, 1183, and 1428 cm^{-1}) and their two coupled modes (1539 and 2328 cm^{-1}), roughly below 0.3 eV. A solid C_{60} film is also assumed to be a nonlinear optical system due to the π-electrons in the molecules. Third-harmonic generations were reported by Kajzar. The third nonlinear susceptibility as a function of the wavelength is shown in Figure 15.12 [42].



FIGURE 15.12 Third nonlinear susceptibility as a function of the wavelength.

The photo-conducting spectra of the solid C_{60} deposited on glass substrates are shown in Figure 15.13 [39]. The photoconducting spectrum from the thin C_{60} layer just corresponds to the absorption spectrum. However, the behavior of the photoconductivity is out of phase with the absorption spectrum, as shown in Figure 15.13. The photo-conducting spectra show that the photo-active region of solid C_{60} is only limited to around the thin surface region and, therefore, the diffusion length of the photo-produced electrons and/or holes is very short. The electron-hole pairs can be produced within the thin small region, because the photons cannot penetrate deeply into the solid C_{60} layers. There is a decrease in one order of magnitude of the photoconductance due to oxygen exposure, because the oxygen molecules absorbed into the solid C_{60} layer work as recombination centers for the carriers, decreasing their lifetime and mobility. The absorption of the oxygen molecules into the solid C_{60} layers



FIGURE 15.13 Photo-conducting spectra of solid C_{60} deposited on glass substrates.

is a reversible process. In addition, photo-conductance recovering accompanied with oxygen adsorption is observed by the 180°C temperature mark annealing under a vacuum. However, a large irreversible deterioration of photo-conductance is induced by white light irradiation exposure to oxygen in the solid C_{60} layers, because of a chemical reaction between the oxygen atoms and the C_{60} molecules induced by white light irradiation.

The polymerization of solid C_{60} is induced by ultraviolet strong light irradiation and/or a low-energy (3–1500 eV) electron beam. We can check the polymerization in several ways; for example, by using the Raman frequency shift. The polymerization by ultraviolet light and the low-energy electron beam is due to an excitation of the electrons in the double bonds of the hexagons and the following reconstruction of new bonds structures between the C_{60} molecules [21,43]. However, the oxygen contamination in solid C_{60} layers has a suppression effect in the polymerization process, because the oxygen atoms work as the killer centers of the excited electrons before the formation of new bonds. Furthermore, the transition from dimmer to monomers is also induced by a thermal annealing at 200°C under an UHV environment. The activation energy of this process is estimated at about 1.25 eV [44].

15.4 van der Waals Epitaxy of C_{60}

The epitaxial growth of solid C_{60} on several proper substrates offers very attractive potential due to its new electrical and optical properties, provided we can obtain the ideal interface between solid C_{60} and the insulator layers. The intermolecular distance on the fcc solid C_{60} film is about 1 nm. This is several times longer than the inter-atomic distance on the top surface of semiconductor substrates such as GaN. The atomic arrangement of the GaN (0001) surface has a sixfold symmetry similar to a fcc solid C_{60} (111) surface. The inter-atomic distance GaN (0001) is about 0.319 nm, which is nearly one-third of the intermolecular distance of the C_{60} molecules in a fcc solid C_{60} (111) surface. If we define the lattice-mismatch as the difference between the intermolecular distances on the C_{60} (111) surface [45] and the distance is almost equal to three times the inter-atomic one on the GaN (0001) surface, then the lattice-mismatch becomes about 4.5% which is not so serious of a difference in the lattice-mismatch of solid C_{60} epitaxial growth. Additionally, it is well known that nitride is rather stable surface for chemical reactions. Therefore, this surface is assumed to be a chemically inactive plane. This plane is necessary for the epitaxy of a van der Waals molecular crystal without any covalent bonds to substrates [46]. It is equally important in the formation of a van der Waals interface in layered materials such as Mica [47] and MoS_2 [48]. Consequently, the solid C_{60} epitaxial growth on the proper substrates can be expected to appear under proper growth conditions. We call the epitaxy like this (solid C_{60} epitaxial growth without any covalent bonds to the substrates, except for the potential periodicity), "the van der Waals epitaxy." In this section, the basic knowledge about the epitaxial growth of a solid C_{60} single crystal layer is described.

15.4.1 Molecular Beam Epitaxy

Conventional solid source MBE is named after the epitaxial growth using molecular beams such as the C_{60} beam produced by conventional Knudsen thermal cells (K-cells) under an UHV environment below a background pressure of lower than 10^{-7} Pa. The conventional MBE system usually consists of a main chamber for epitaxial growth, a preparation chamber for the surface cleaning of the substrate, and an introduction chamber for the substrate charge from the atmosphere, as shown in Figure 15.14. Each chamber has a pumping system with several vacuum



FIGURE 15.14 Conventional MBE system.

monitoring systems such as a nude ion gauge in order to keep the UHV environment, and all chambers are connected via gate valves with each other. The main chamber has a sample holder with a sample heating system and a monitoring system for epitaxy. For example, a reflection of high-energy electron diffraction (RHEED) system and a quadrupole mass spectroscopic (Q-Mass) system are used for monitoring the growth surface and the background ambient during epitaxy, respectively. The main chamber should maintain the UHV environment as much as it is possible in order to suppress contamination during growth, allowing a cooling bag using liquid nitrogen or a water circular system to settle inside the chamber. The preparation chamber has a thermal heating system for sample cleaning and, in many cases, other in-situ characterization systems such as the Auger electron spectroscopic (AES) system in order to characterize the sample surface before and/or after epitaxy. The substrate prepared by the proper chemical cleaning treatment is installed into the introduction chamber from the atmosphere to the high vacuum environment. Then, the substrate is transferred from the introduction chamber to the preparation chamber through the gate valve to clean the surface and, occasionally, to perform some in-situ characterization under a UHV environment before growth. After the surface cleaning, the substrate is transferred into the main chamber for growth. In the main chamber, the K-cell and/or the substrate heating systems should fully do the out-gas procedure before the installation of the substrate. The beam flux also should be estimated by a nude ion gauge monitor before and after growth, if possible. The details of the general information of MBE growth and systems can be obtained from the proper reference books.

15.4.2 van der Waals Epitaxy

van der Waals epitaxy is an important technique in overcoming the restrictions in large lattice-mismatches in the crystal growth. According to Koma, the van der Waals interface can drastically relax the lattice-matched growth conditions, because of a weak interaction between the films and the substrates [46]. There has been much interest in using single crystalline C_{60} thin films grown by van der Waals epitaxy on hydrogen-terminated (H-terminated) Si substrates. These newly functional films have a great potential in many areas due to the discovery of the large-scale production synthesis methods of C_{60} molecules. However, it has still been difficult to obtain single-domain C_{60} thin solid films with the fcc structure on Si substrates, though single-domain C_{60} films can be grown on layered material substrates such as MoS_2 [48], GaSe [49], and Mica [47]. The growth of C_{60} films on H-terminated Si (111) substrates with quasi van der Waals interfaces shows a three-dimensional island growth mode. In addition, the film's grown structure contains a fcc double domain. Therefore, a large fcc single-domain film has not been obtained yet to the best of our knowledge.

The most popular device structures of C_{60} FETs is a bottom contact structure with a SiO_2 insulator layer formed on a conductive Si substrate as a gate electrode, and the details will be described in the later sections. In the bottom contact structure with the SiO_2 insulator layer, the C_{60} layer becomes an amorphous or a polycrystalline structure due to the amorphous surface of the SiO_2 layer. If we want to use the single crystalline solid C_{60} surface, then we have to apply the top contact structure to the single crystalline solid C_{60} bulk. The solid C_{60} bulk can only be obtained on the inside of the furnace wall by methods such as train sublimation. However, the obtained single crystal is usually very small. Although it is not impossible to make C_{60} FETs using such tiny C_{60} bulks, interface problems such as the ion damage always occur in the formation process of the insulator layer when using such a sputtering method. Therefore, in the current state-of-the-art technology, it is very difficult to obtain an ideal interface between solid C_{60} and insulator layer in both FET structures. There is a lot of discussion about the use of the bottom contact structure in the C_{60} FET because of the easy fabrication process, even for amorphous-like interfaces.

15.4.3 Initial Growth Surface

Here, we will discuss the relationship between the van der Waals epitaxy and the initial growth surface. We have already pointed out that the interaction between the C_{60} molecules and the initial surface plays an important role in the epitaxial growth of the solid C_{60} layer. Therefore, we discuss several types of surfaces such as the H-terminated Si (111) surface and/or the single crystalline AlN surface.

15.4.3.1 H-Terminated Si (111) Surfaces

In Figure 15.15, typical atomic force microscope (AFM) image and RHEED pattern of C_{60} epitaxy on an H-terminated Si (111) surface are shown. Petal-like islands with considerable low density are formed on the H-terminated Si (111) surface. The results strongly indicate that the van der Waals interaction between C_{60} molecules and the surface is not so strong and, therefore, that the migration length of the C_{60} molecules on a quasi van der Waals surface like the H-terminated Si (111) surface is considerably longer than conventional epitaxy such as with Si layers. However, we can control the island density and size by using a two-step growth technique, as shown in Figure 15.15. The two-step growth technique is well known as one of the most important techniques in achieving a high-quality single crystalline for high lattice-mismatch hetero-epitaxial systems. According to the two-step growth procedure, the C_{60} layers are grown at 150°C to enhance the surface migration of C_{60} molecules, after the formation of low-temperature buffer layer growth at 30°C successively annealed at 150°C to form a high nucleus density, respectively. The typical beam equivalent pressure of the C_{60} molecular beam (purity; >99.99%) was 5.0×10^{-9} Torr during growth, and the beam pressure corresponds to a growth rate of 0.8 nm/min [50].

A RHEED pattern from the grown layer by using the two-step growth technique showed a fcc single-domain structure, as shown in Figure 15.16. However, the RHEED pattern from the directly grown layer showed a double-domain fcc structure in



FIGURE 15.15 Typical AFM image and RHEED pattern of C_{60} epitaxy on an H-terminated Si (111) surface.



FIGURE 15.16 Typical AFM image and RHEED pattern of C_{60} grown layer by using two-step growth technique.

which the normal and the rotated domains on the Si substrate mixed with each other, as shown in Figure 15.16. According to Saito, in the case of C_{60} epitaxy on NaCl substrates, not only hexagonal (or truncated triangular) plates (which are single crystals) but also particles with irregular shapes which look like petals are observed. Such petal-like particles are rich in planar defects such as parallel and cyclic twining [47]. Therefore, the triangle islands formed in the two-step growth have a single-domain fcc structure. The petal-like islands formed in the direct growth have a double-domain fcc structure. These well-arranged dense islands on the surface obtained by the two-step growth may have a potential to form thick C_{60} films with the fcc single-domain structure.

15.4.3.2 Hexagonal GaN (0001) Surfaces with Ga-Polarity

The epitaxial growth of solid C_{60} on semiconductor substrates offers a very attractive potential due to its newly discovered electrical and optical properties. The atomic arrangement of the hexagonal GaN (0001) surface has a sixfold symmetry similar to the fcc solid C_{60} (111) surface. Its inter-atomic distance is about 0.319 nm, which is near one-third of the intermolecular distance of the C_{60} molecules in fcc solid C_{60} (111) surfaces. An extended lattice-mismatch in the van der Waals epitaxy can be defined as the difference between the intermolecular distance in the C_{60} (111) surface and the distance equal to three times the inter-atomic one in the h-GaN (0001) surface. The extended lattice-mismatch then becomes 4.5% which is the lowest among conventional semiconductor substrates in solid C_{60} epitaxial growth. Additionally, it is well known that the h-GaN surface is rather stable for chemical reactions. Therefore, the surface is expected to act as a chemically inactive plane which is necessary for van der Waals epitaxy as well as the van der Waals interface in layered materials such as Mica and MoS_2 [51].



FIGURE 15.17 Typical RHEED patterns from solid C_{60} layer grown on flat h-GaN (0001) surface at 100°C for 60 min.

The GaN (0001) surfaces formed on the α-Al_2O_3 substrates are prepared by a metal organic vapor phase epitaxy. Typical RHEED patterns from a solid C_{60} layer grown on a flat h-GaN (0001) surface at 100°C for 60 min are shown in Figure 15.17. The directions of the incident electron beam are parallel to (a) [1120] and (b) [11$\bar{1}$0] crystal axes of the h-GaN (0001) surface. The in-situ RHEED observation revealed that the C_{60} film growth did not occur at 150°C because of the re-evaporation of the C_{60} molecules from the surface. On the other hand, sharp streaks from the fcc (111) surface can be observed in the RHEED patterns, as shown in Figure 15.17. The results imply that the lattice-structure of the grown layer is mainly the fcc structure, and the relationship of the crystal axes between the epitaxial grown layers and the h-GaN (0001) substrates is C_{60} (111)||h-GaN (0001), C_{60} [10$\bar{1}$]||h-GaN [11$\bar{2}$0], C_{60} [11$\bar{2}$]||h-GaN [01$\bar{1}$0], as shown in Figure 15.18. Figure 15.19 shows a typical AFM image of the C_{60} layer on a flat h-GaN (0001) surface.


10 Å
C_{60} molecule
[01$\bar{1}$0]
[11$\bar{2}$0]
3.19 Å
h-GaN (0001) surface
C_{60} (111)||h-GaN (0001)
C_{60} [10$\bar{1}$1]||h-GaN [11$\bar{2}$0]
C_{60} [11$\bar{2}$]||h-GaN [01$\bar{1}$0]

FIGURE 15.18 Relationship of crystal axes between epitaxial grown layers and h-GaN (0001) substrates.



FIGURE 15.19 Typical AFM image of C_{60} layer on flat h-GaN (0001) surface.

The whole surface of the substrate was completely covered with highly dense C_{60} islands. The size of the islands was on the order of a sub-micron meter. Figure 15.20 shows the growth temperature dependency on grain size and density estimated from AFM images, as shown in Figure 15.19, in C_{60} growth on h-GaN and H-terminated Si. In the case of C_{60} growth on the h-GaN, the grain size slowly increases and the grain density rapidly decreases as a function of the growth temperature in comparison with the H-terminated Si substrate. The results indicate that the interaction between the C_{60} molecule and the h-GaN surface is extremely weak compared with C_{60} film growth on a H-terminated Si (111) surface. The evaporation of the C_{60} molecules on the GaN surface may very well easily occur and, consequently, it leads to a reduction of the diffusion length of C_{60} molecules during growth. Short diffusion and/or migration lengths may induce highly dense small grains, as shown in Figure 15.20.



FIGURE 15.20 Growth temperature dependency on grain size and density estimated from AFM images, as shown in Figure 15.19.

The experimental results for C_{60} direct growth on rough h-GaN (0001) surfaces show that a polycrystalline C_{60} layer can only be obtained. Furthermore, it suggests that the surface migration of the C_{60} molecules may be suppressed by the existence of various planes on the rough surface. The fcc C_{60} layers can be grown epitaxially even on a rough h-GaN (0001) surface by using the two-step growth technique, though only the polycrystalline C_{60} layers are obtained by direct growth. All experimental results strongly indicate that the periodicity of the h-GaN surface potential for the van der Waals epitaxy is easily and strongly modified by surface roughness. Therefore, the flatness of GaN substrate is also a very important factor in obtaining a high-quality C_{60} epitaxial layer.

15.4.3.3 Hexagonal AlN (0001) Surface with N-Polarity

The AlN single crystal layer can be grown on 6H-SiC [53,54], Si [55,56], and so on. The single crystal AlN layer has large bandgap energy (6.2 eV) and enough high dielectric breakdown voltage for C_{60} FET applications. Lattice-mismatch between the C_{60} fcc structure (111) and the h-AlN (0001) is 7.3% in C_{60} $[10\bar{1}]\|$AlN $[11\bar{2}0]$ (the 0° orientation) and 7.0% in C_{60} $[11\bar{2}]\|$AlN $[11\bar{2}0]$ (the 30° orientation), as shown in Figure 15.21. These values are acceptable under C_{60} van der Waals epitaxy [45]. Therefore, the AlN layer is assumed to be the substrate for single crystal C_{60} layers. However, the lattice-mismatch in both orientations, shown in Figure 15.21, is almost the same. Because the C_{60} van der Waals epitaxy has a character that the growth orientation on the smooth surface strongly depends on the lattice mismatch [45], it is a little difficult to predict the C_{60} orientations on the AlN surface. If the single crystal C_{60} layers can be grown on a AlN surface, a more perfect interface can be obtained than by an interface formed by the conventional sputtering method.

Figure 15.22 shows typical RHEED patterns from a solid C_{60} layer grown on a smooth AlN surface (RMS value: 0.9 nm) for 2 h at 100°C–160°C. All the RHEED patterns in Figure 15.22 indicate a fcc (111) structure. The ring pattern appears on a spot pattern below a growth temperature of 100°C. Both the RHEED patterns with the azimuth of electron beam paralleled to AlN $[10\bar{1}0]$ and AlN $[11\bar{2}0]$ at 100°C–130°C show the inclusion of C_{60} $[10\bar{1}]$ and C_{60} $[11\bar{2}]$ patterns, as shown in Figure 15.22. Moreover, twin patterns are also observed. On the other hand, the C_{60} $[10\bar{1}]$ pattern is only observed with a AlN $[11\bar{2}0]$ azimuth of the electron beam at 160°C, and the C_{60} $[11\bar{2}]$ pattern is only observed with a AlN $[10\bar{1}0]$ azimuth of the electron beam at 160°C, respectively, although the twin patterns are still observed at 160°C.

From the RHEED results we can summarize that the C_{60} layers that are grown at 100°C–130°C contain four kinds of grains, which are the C_{60} $[10\bar{1}]\|$AlN $[11\bar{2}0]$ (the 0° orientation) and its twin grains and the C_{60} $[11\bar{2}]\|$AlN $[11\bar{2}0]$ (the 30° orientation) and its twin grains, as shown in Figure 15.23. However, the RHEED intensity from the 0° orientation is always stronger than that from the 30° orientation. Figure 15.24 shows the intensity ratio of the 0° orientation grain as a function of the growth temperature. In this figure, the 0° orientation grains are grown more than the 30° orientation grains, and its ratio is about 7:3. The C_{60} layers that are grown at 160°C contain only the 0° orientation grains, although the twin grains still remain. The results strongly



0° orientation
(C_{60} $[10\bar{1}]\|$AlN $[11\bar{2}0]$)

30° orientation
(C_{60} $[11\bar{2}]\|$AlN $[11\bar{2}0]$)

FIGURE 15.21 C_{60} $[10\bar{1}]\|$AlN $[11\bar{2}0]$ (the 0° orientation) and 7.0% in C_{60} $[11\bar{2}]\|$AlN $[11\bar{2}0]$ (the 30° orientation).


• The RHEED patterns from the solid C_{60} layer on smooth AlN surface
e||AlN[10$\bar{1}$0]
e||AlN[11$\bar{2}$0]
AlN surface
100°C–130°C
160°C
Growth temperature

FIGURE 15.22 Typical RHEED patterns from solid C_{60} layer grown on smooth AlN surface (RMS value: 0.9 nm) for 2 h at 100°C–160°C.


100°C – 130°C
160°C
0° orientation
Double domain
C_{60} (first layer)
C_{60} (second layer)
AlN (10$\bar{1}$0)
30° orientation
AlN (11$\bar{2}$0)
Double domain
AlN (0001)

FIGURE 15.23 Summarized illustration of epitaxial relationship between solid C_{60} and AlN (0001) surface.



FIGURE 15.24 RHEED intensity ratio of 0° orientation grain as a function of growth temperature.

indicate that the C_{60} grains with the 0° orientations are stable on a smooth AlN surface in high-temperature growth, although the lattice-mismatch for each orientation is almost equal.

The solid C_{60} grains grown on the smooth AlN surface for 5 h at 100°C–160°C showed a three-dimensional island growth. Their grain density and grain size as a function of growth temperature show a trade-off relation which is strongly connected to the migration of C_{60} molecules and the covering of C_{60} layers on the AlN surface. The RHEED pattern for the solid C_{60} layer grown on the rough AlN (RMS value: 9.5 nm) surface at the 130°C shows a mixed pattern with a spot and a ring. The RHEED result indicates that the orientation of the grains is not controlled at all. Such random orientation can be improved by thermal annealing at 130°C after the low temperature growth at 30°C. However, the obtained C_{60} layers have multi-domain structures. The results indicate that the roughness of the AlN surface is also an important factor for C_{60} epitaxy. The RHEED pattern from the solid C_{60} layer grown on the polycrystalline AlN (RMS value: 0.7 nm) at 130°C shows a full ring pattern, which means the polycrystalline C_{60} layer is grown on the surface. It strongly indicates that the periodic atomic arrangement of the surface is also an important factor in C_{60} epitaxy as well as the surface roughness [52].

15.5 Principles of Organic FET Functions

The first report on the mobility measurement of an organic semiconductor material, merocyanine, using the field effect was published in the *Japanese Journal of Applied Physics* in 1984 by Kudo et al. [57]. Just after the first report on the field effect of the organic semiconductors, Koezuka et al. described the first OFET using polythiophene in 1987 [58]. After these innovations by Japanese researchers, the study of organic FETs has been extensively developed through the last two decades. The mobility of the carrier has achieved the same level as the ploy Si FETs in the late 1990s, as shown in Figure 15.1. Now, it has been reported that the highest mobility of organic FETs is 40 cm^2/V s in a single crystalline rubrene FET [59]. According to Haddon et al., the solid C_{60} layers were utilized at the active element in thin film FETs [60]. However, the mobility of the FET was found to be rather low (10^{-4} cm^2/V s) by Tang et al. [61]. Very recently, a group from the University of Tokyo has reported the highest electron mobility of 6.0 cm^2/V s in the C_{60} FET structures at a low temperature [62]. The developments of the OFETs performance have been rapid in recent years like other organic devices such as organic electro-luminescence (OEL) [63]. In this section, we discuss about the general principles of OFETs, including C_{60} FETs for a deeper understanding of C_{60} FET operation in the later sections.

15.5.1 Device Structures of OFETs

Organic transistor materials are classified mainly into two categories: low- and high-molecular compound systems such as rubrene and polythiophene, respectively. In general, low-molecular compound systems have a rather high mobility. Consequently, the research on the OFETs using low-molecular systems has been intense in recent years. Therefore, in this section, we will discuss about FETs using low-molecular compound systems. The various types of FET structures such as vertical structure [64] and the Schottky gate structure [65] have already been reported. However, in this section we will discuss metal insulator semiconductor (MIS) structures, which are the most popular FET structures. In the OFET structure, mainly two types of structures are usually used in research: (a) bottom and (b) top contact structures, as shown in Figure 15.25a and b, respectively. The bottom contact structure is the most popular structure in OFETs, because a fine-patterning technique for the short channel is easily applicable just after the deposition of the electrode metal, as shown in Figure 15.25a. The organic active elements are deposited on the source and drain electrodes and the insulator layer after the fine-patterning of the electrodes. In general, in the bottom contact structure, the considerably large height difference between the electrodes and the insulator surface becomes an origin of high contact resistance between the active organic element and the metal electrodes. The discontinuity between the electrode and the organic materials at the edge of the electrodes becomes an origin of fluctuation in the FET performance such as in the *I*–*V* curves. In contrast, active organic elements are deposited on a flat insulator surface before the electrode formation in the top contact structure. However, achieving the fine-patterning of the organic semiconductor material systems is considerably difficult. Therefore, the metal electrodes formation is usually performed by using a metal-mask vacuum evaporation method. Moreover, a high contact resistance between the top metal electrodes and the interface of the insulator–organic layer in the active channel region cannot be essentially avoided. In practice, the contact resistance is lower than the case of the bottom contact FET, because the metal atoms of the electrodes may diffuse into the organic layer. In general, SiO_2 layers thermally grown on a Si substrate are used as the insulator layer and gold is used as source and drain electrode. The interface between metal and organic semiconductor becomes a Schottky junction because of the large difference in the carrier density between the metal and organic materials without doping. Therefore, the off-current is very low due to the large contact resistance in the OFET operations.



FIGURE 15.25 Schematics of (a) bottom and (b) top contact FET structures.

15.5.2 Metal/Organic Layer Interface

Organic semiconductors show intrinsic semiconductor nature and have very low impurity states in the band gap. Therefore, carriers excited by thermal energy play an essential role in the current conduction of OFETs. Both the electrons and the holes contribute to the carrier transport in the same manner as in am-bipolar operations. However, many experimental reports have been published on *p*-type materials such as rubrene and *n*-type materials such as solid C_{60} layers. Such a material dependency on the conducting types in spite of an essentially am-bipolar nature in organic semiconductors had been a large mystery in the OFET research for many years. However, very recently, Yasuda et al. have reported about the am-bipolar operations in OFETs such as pentacene or Cu-ftalocianina which had been considered a *p*-type OFET [66]. According to them, the am-bipolar operation can be realized by using a potassium electrode with a low work function, instead of the Au with a considerably high work function. Moreover, Nishikawa et al. have reported about the am-bipolar operation of OFETs using the work function as a control by using a modification technique that uses self-organized mono-layered molecules on the surface of Au electrodes [67]. These results strongly indicate that the formation of the carrier accumulation layer at the interface of OFETs is completely different from that of conventional semiconductor FETs. Namely, although the carrier accumulation layer for conventional semiconductor materials is formed by impurity doping into bulk, the carrier injection from the electrode plays an essential and important role for the formation of the carrier accumulation layer in OFET structures. According to Tamura et al., the formation of the accumulation layer in OFETs can be explained consistently using by the Maxwell–Wagner model for dielectric materials. In other words, the formation of the carrier accumulation layer can only be realized by carrier injection from the electrode with a low injection barrier height. However, the carrier accumulation layer cannot be formed for a high injection barrier [68]. The results of the analysis of the formation of accumulation layers indicate that the type of carriers of the accumulation layer can be determined by the relationship between the work function of the electrode metals and the HOMO–LUMO levels of the organic semiconductor materials, that is, the Schottky barrier between the electrode metals and organic semiconductor surfaces.

15.5.3 Field Effect Doping for Solid C_{60} Layers

A field effect doping technique has been proposed as a new type carrier doping that is applied to the interface between solid C_{60} and insulator layers by applying an external voltage to it in a similar manner to conventional field effect transistor (FET) [60]. In this doping technique, the solid C_{60} layer is treated as a semiconductor that was theoretically predicted by Saito and Oshiyama [28]. Injected career density and/or polarity through the interactions between the electrodes metals and the solid C_{60} layer can be controlled by the value and the polarity of external gate voltage in this technique. This point is a great advantage in the field effect doping for C_{60} device fabrication techniques in comparison with conventional chemical doping. However, several serious problems need to be resolved before there are realistic device applications using the field effect doping technique. The most important problem to be fixed is how to form a well-controlled interface between the insulator and the solid C_{60} layers. The channel region is formed in several mono layers from the interface. In the fabrication of the FET structure, an excellent C_{60} interface without any damage can be formed by the deposition of a C_{60} vacuum on a single crystal insulator layer such as the AlN layer (as shown in Figure 15.26) because the AlN single crystal layer can be grown on 6H-SiC [53,54], Si [55,56], and so on. In the conventional sputtering method for insulator film deposition, it is easy to damage the interface region. Therefore, it is a little difficult to form a reproducible and excellent interface. On the other hand, the single crystalline AlN layer has the large band-gap energy (6.2 eV). In addition, it also has enough high dielectric breakdown and dielectric constant for C_{60} FET applications. Consequently, it is expected that the interface between the single crystalline solid C_{60} layers grown on a single crystalline AlN insulator layer will become one of the most promising structures for field effect doping.



FIGURE 15.26 Typical I_D–V_{SD} characteristics of fabricated C_{60} FETs with (a) conventional SiO_2 layers and with (b) newly proposed AlN layers.

15.5.4 Am-Bipolar OFET Operations

In general, organic semiconductors such as solid C_{60} films are essentially intrinsic semiconductors, with the characteristics of low carrier density and an absence of impurity levels in the band gap. Therefore, if we can remove the extrinsic factors such as the absorption of gas and the carrier traps and can choose the proper electrode metals, an am-bipolar transistor can be easily realized in contrast to conventional semiconductors. There are many ways to realize a practical am-bipolar transistor such as fabricating the device under a vacuum or using inert gas ambient to prevent the absorption gas effect. Another typical idea is the usage of an asymmetric Schottky barrier source–drain electrode structure using different metals with large or small work functions from each other. Moreover, organic polymers such as polymethyl methacrylate (PMMA) can be applied as insulator layers to remove the electron traps on the SiO_2 surface. The electrons and the holes can be injected simultaneously under am-bipolar operation. Therefore, it is expected that a pseudo-PN junction will result in light emission due to a recombination of simultaneously injected electrons and holes in the channel. Am-bipolar light-emitting transistors have been reported in the carbon nanotubes, the organic polymers, and the tetracene channel FETs [69–71]. Unfortunately, however, am-bipolar operations have not been observed in solid C_{60} FETs until now for no essential reason.

15.6 Fabrication of Fullerene Field Effect Transistors (C_{60} FET)

The most important problem in the fabrication of the C_{60} FETs is how to form an effective interface between the insulator and the solid C_{60} layer. In this section, we discuss a new structure of the C_{60} FETs, which consists of an epitaxial AlN layer as the insulator and a solid C_{60} epitaxial layer grown on a AlN (0001) surface to realize the ideal interface, in comparison with the most popular structure of C_{60}/SiO_2 FETs. First of all, the solid C_{60} growth on the AlN (0001) surface by using the MBE technique is described again, although we have already described it in Section 15.4. Furthermore, how C_{60} islands with a fcc structure can be obtained on a smooth single crystalline AlN surface has been explained. The experimental results show that four types of C_{60} islands, in general, are obtained: those with 0° of orientation and its twin ones, those with 30° of orientation and its twin ones. However, only the islands with 0° orientation can be obtained by controlling of the solid C_{60} growth temperature. Such results strongly indicate that an effective interface between the AlN insulator and the solid C_{60} layer can be formed for device applications. The fabrication of polycrystalline solid C_{60}/AlN FET structures and the conductive characteristic of C_{60} FETs as a function of the C_{60} grain size have also been described. The C_{60} grain size grown on the polycrystalline AlN insulator layer is always larger than on SiO_2 insulator layers. Moreover, the electron mobility increases with the C_{60} grain size. It is also shown that the activation energy in the hopping conduction below the threshold voltage decreases along with the C_{60} grain size. These results all strongly indicate that the C_{60}/AlN FET structure has a great potential in achieving an outstanding performance in C_{60} FETs [72].

15.6.1 Substrates: SiO_2 or AlN

The most popular substrate is a conductive Si substrate with a thermal oxidation layer, SiO_2. The SiO_2 layer has some excellent properties as an insulator layer, and it is well known in the Si-MOSFET world. However, the fatal shortcoming in the SiO_2 layer as the insulator layer of the solid C_{60} FET is that the amorphous surface structure prevents single crystalline solid C_{60} epitaxy. On the other hand, AlN layers grown on conductive Si (or SiC) substrates have similar excellent properties as the insulator films of C_{60} FETs to SiO_2 films, except that they have a crystal surface. The crystal surface of the insulator film is necessary in forming an ideal interface between solid C_{60} layers and the insulator layers. For van der Waals epitaxy of solid C_{60} layer to form the ideal interface, however, there are also other necessary conditions such as lattice-matched conditions and the surface roughness of the insulator layer to be met. Therefore, the AlN layer grown on the Si (or SiC) substrates has a great potential for the insulator layer of solid C_{60} FETs.

15.6.2 Device Process

The drain and source electrodes of gold are usually fabricated on the insulator layer by conventional lithography techniques. The channel length (L) and width (W) of the fabricated FET described here are 7.5 and 175 μm, respectively. After the lithography of the electrodes, the C_{60} layers are grown at 30°C–160°C by a conventional solid source MBE system.

15.6.3 C_{60} Epitaxy

The lattice mismatches between the solid C_{60} (111) surface with the fcc structure and the AlN (0001) surface with the wurtzite structure (h-AlN) are 7.3% in C_{60} $[10\bar{1}]\|$AlN $[11\bar{2}0]$ (0° orientation) and 7.0% in C_{60} $[11\bar{2}]\|$AlN $[11\bar{2}0]$ (30° orientation), as shown in Figure 15.21. The lattice mismatch can be permitted in the van der Waals epitaxy of the solid C_{60} layer [45]. It has been reported that a fcc C_{60} layer can be grown on h-GaN (0001) which is chemically stable just like AlN [51]. Therefore, AlN can be expected to be a substrate for the single crystal C_{60} layers. However, the lattice-mismatch in both orientations (shown in Figure 15.21) is almost the same. Because the C_{60} van der Waals epitaxy growth orientation on the smooth surface strongly depends on the lattice mismatch [45], it is a little difficult to predict the C_{60} orientations on the AlN surface by using the above considerations. If single crystalline C_{60} layers can be grown on the AlN surface, a more effective interface can be obtained than from an interface formed by the conventional sputtering method. However, no one has succeeded in forming a single crystalline C_{60} layer grown on the AlN surface so far. Therefore, we have to investigate the characteristics of FETs with polycrystalline solid C_{60} layers on the AlN surface while at the same time studying the single C_{60} layer growth on single AlN layers. In particular, it is very interesting that the size of the C_{60} grains may be strongly related to conductive characteristic such as the mobility and/or the activation energy of hopping conduction in FET performance.

A smooth single crystalline AlN surface (root mean square: RMS value: 0. 9 nm), a rough single crystalline AlN surface (RMS value: 9.5 nm), and a smooth polycrystalline AlN surface (RMS value: 0. 7 nm) can be formed by the nitridation of Al_2O_3 (0001) substrate or by the AlN growth on them by using radio-frequency plasma-assisted molecular beam epitaxy (RF-MBE). The C_{60} layers described here can also be grown on a AlN surface for 2–5 h at 60°C–160°C by a conventional solid-source MBE system under a base pressure of $\sim 10^{-7}$ Pa. The monitoring of the growth process is usually performed by RHEED. The surface morphology of the solid C_{60} grown layer can be characterized by using the AFM. The AlN layers should be grown on a p-type

Si (111) substrate by using the RF-MBE system at about 500 nm (RMS value: 1.7 nm) in order to fabricate the bottom contact FET structure. For the C_{60}/SiO_2 FET structure, for example, the *p*-type Si (100) substrate is ordinarily used as a substrate covered with a SiO_2 insulator layer thermally formed at roughly 250 nm (RMS value: 0.2 nm).

Figure 15.22 shows typical RHEED patterns from solid C_{60} layers grown on a smooth AlN surface (RMS value: 0.9 nm) for 2 h at 100°C–160°C. All RHEED patterns in Figure 15.22 show ones from the fcc (111) structure. Ring patterns appear in spot patterns below a growth temperature of 100°C. Both the RHEED patterns, the one with azimuth electron beam paralleled to the AlN $[10\bar{1}0]$ and the AlN $[11\bar{2}0]$ crystal directions from samples grown at 100°C–130°C, show the inclusion of both C_{60} $[10\bar{1}]$ and C_{60} $[11\bar{2}]$ patterns, as shown in Figure 15.22. Moreover, twin patterns are also observed. On the other hand, the C_{60} $[10\bar{1}]$ and the C_{60} $[11\bar{2}]$ patterns are only observed with the AlN [11–20] and AlN $[10\bar{1}0]$ azimuths from samples grown at 160°C, respectively. However, the twin patterns are still observed even at 160°C.

The RHEED results can be summarized as follows: the C_{60} layers grown at 100°C–130°C contain four kinds of islands which are in the C_{60} $[10\bar{1}]\|$AlN [11] (the 0° orientation) epitaxial relation and its twin islands. They are also in the C_{60} $[11\bar{2}]\|$AlN $[11\bar{2}0]$ (the 30° orientation) epitaxial relation and its twin islands, as shown in Figure 15.23. However, the RHEED intensity from the islands with the 0° orientation is always stronger than from the islands with the 30° orientation. Figure 15.24 shows the RHEED intensity ratio for both islands in the epitaxial relation with the 0° and the 30° orientations as a function of the growth temperature. The islands with 0° orientation are grown much larger than ones with 30° orientation. The ratio is about 7:3. The C_{60} layer grown at 160°C contains only islands with 0° orientation. However, the twin islands still remain. The results strongly indicate that the C_{60} islands with the 0° orientation are stable on a smooth AlN surface in high-temperature growth, while the lattice-mismatch for each orientation is almost the same.

The C_{60} islands grown on the smooth AlN surface at 100°C–160°C show a three-dimensional island growth. The density and the size of the islands, as a function of growth temperature, show a trade-off relation which is strongly connected to the migration of the C_{60} molecules and the covering of the C_{60} layers on the AlN surface.

The RHEED pattern for a solid C_{60} layer grown on a single AlN with a rough surface (RMS value: 9.5 nm) at 130°C shows a mixed pattern with a spot and a ring. The RHEED results indicate that the orientation of the grains is not controlled at all. Such random orientation can be improved by the thermal annealing at 130°C after a low-temperature growth at 30°C. However, the obtained C_{60} layers have multi-domain structures. The results indicate that the roughness of a single crystalline AlN surface is also one of the important factors for solid C_{60} epitaxy.

The RHEED pattern from a solid C_{60} layer grown on a polycrystalline AlN (RMS value: 1.7 nm) at 130°C shows a complete ring pattern. This means that a polycrystalline C_{60} layer is grown on the surface. Furthermore, it strongly indicates that the periodic atomic arrangement on the AlN surface is also an important factor in solid crystalline C_{60} epitaxy as well as in surface roughness [52].

The RHEED observations show that polycrystalline C_{60} layers can be grown on both AlN and SiO_2 layers. By observing the AFM in surface morphology, it was revealed that the grain size of the polycrystalline C_{60} layers grown on polycrystalline AlN layers was larger than those grown on SiO_2 layers under the same conditions of C_{60} growth. The results indicate that a better interface due to the obtained larger C_{60} grains can be made on AlN layers rather than on SiO_2 layers.

15.6.4 Measurements of FET Performance

A drain current versus a source–drain voltage (I_D–V_{SD}) characteristic of FETs are usually measured by a conventional three probe current-voltage measuring system in an ambient N_2 atmosphere to avoid oxidation.

15.7 Characterization of C_{60} FETs on SiO_2 or on AlN

15.7.1 *I–V* Characteristics

Typical I_D–V_{SD} characteristics of fabricated C_{60} FETs with (a) conventional SiO_2 layers and with (b) newly proposed AlN layers are shown in Figure 15.26a and b, respectively. The typical I_D–V_{SD} characteristics consist of three regions: (1) the sub-threshold, (2) the linear, and (3) the saturation regions, similar to the I_D–V_{SD} characteristics of polycrystalline Si thin-film transistors (TFTs) [73]. According to the standard explanation of polycrystalline Si TFTs, those three regions can be explained by the differences in the conduction mechanisms. The linear and/or the saturation regions in the I_D–V_{SD} curves can be understood by normal band conduction. The electron mobility can be estimated from the I_D–V_{SD} curves. The electron mobility of such C_{60} FETs with (a) SiO_2 and with (b) AlN layers are estimated from the I_D–V_{SD} curves, as shown in Figure 15.26a and b and are 2.0×10^{-2} and 9.0×10^{-2} cm^2/V s, respectively. It is well known that the grain size is closely related to the mobility in conventional polycrystalline Si TFTs. The electron mobility estimated from I_D–V_{SD} curves as a function of the C_{60} grain size is shown in Figure 15.27. The electron mobility increases with grain size similar to conventional polycrystalline Si TFTs.

15.7.2 Sub-Threshold Region

The sub-threshold region at a low V_{SD} can be understood as hopping a conduction region [74]. According to many reports on organic FETs, a hopping conduction is commonly observed in them, and it strongly depends on the temperature and the electric-field-strength in the channel [75]. The activation energy of carrier hopping in C_{60} FETs, which is estimated from the temperature dependence of the I_D–V_{SD} curves in the range of 200–300 K by a gate voltage of 7.5 V, is shown in Figure 15.28. The



FIGURE 15.27 Electron mobility estimated from I_D–V_{SD} curves as a function of C_{60} grain size.



FIGURE 15.28 Activation energy of carrier hopping in C_{60} FETs with AlN and SiO_2 insulator layers.

results clearly indicate that the activation energy decreases with grain size in a manner similar to organic FET cases [76].

Moreover, a disorder model for a hopping conduction is given by the following equation:

$$\mu = \mu_0 \exp\left[-\left(\frac{2}{3}\hat{\sigma}\right)^2\right]\exp\left[C(\hat{\sigma}^2 - \Sigma^2)E^{1/2}\right] \quad \hat{\sigma} = \frac{\sigma}{kT} \qquad (15.6)$$

where μ_0, σ, and Σ are the pre-exponential factors, the parameters of diagonal disorder, and the parameter of off-diagonal disorders, respectively [75]. The diagonal and the off-diagonal disorders mean the energetic and the positional disorders, respectively. When the Σ is larger than the σ, the electron mobility in a hopping conduction has a negative dependence on the electric-field-strength. The electron mobility in the hopping region is shown in Figure 15.29 as a function of the electrical field in the interface. The permittivity and the thickness of the AlN and the SiO_2 layers are different from each other. Consequently, the number of carriers induced by the gate voltage should be estimated as a function of the dielectric flux density. As shown in Figure 15.29, the electron mobility in a polycrystalline C_{60}/SiO_2 FET does not depend on the electric-field-strength. However, the electron mobility in the amorphous C_{60}/SiO_2 FET and the polycrystalline C_{60}/AlN FET decreases with the electric-field-strength. Therefore, such a negative slope in the electron mobility as a function of the electric-field-strength in the hopping region means that a positional disorder is dominant at the interface of those FETs. That is, a route for the conductive current without any relation to the electric-field-strength must be formed in polycrystalline C_{60}/AlN FETs and amorphous C_{60}/SiO_2 FETs. Such large positional disorders can be understood by looking at the geometrical interface roughness which is due to a rough surface morphology of the AlN layers in the case of C_{60}/AlN FETs and by the structural interface roughness due to the poor amorphous structure of the C_{60} layers in C_{60}/SiO_2 FETs.



FIGURE 15.29 Electron mobility in hopping region as a function of electrical field.

15.8 Summary

We have described solid C_{60} FETs starting from a basic explanation of C_{60} molecules to FET applications, through an introductory discussion about van der Waals epitaxy and organic FET operations. The most essential issue in C_{60} FET research at the present stage is the formation of an ideal interface between solid C_{60} and the insulator layers. To accomplish this, we need a new combination of solid C_{60} and insulator layers. In this chapter, we discussed that one of the possible strong candidates is a combination of solid C_{60} and single-crystalline AlN grown on either SiC or Si substrates. However, this problem still remains open to debate.

In the near future, it is expected that rather high-temperature superconductivity will be obtained to form the ideal interface in some solid C_{60} FET structures. The reasons of this expectation are based on the potential of hole-injection in field effect doping and high-energy inner-cluster phonon (~1000 K) which will assist in the superconductivity in the bulk of solid C_{60} [77,78]. Furthermore, the various combinations of carbon materials such as nanotubes and graphene with solid C_{60} FET structures will bring new applications like new molecular devices to reality. The C_{60} FET structures must play essential and important roles in carbon nano-electronics in the research beyond CMOS in the future.

References

1. http://www.aist.go.jp/aist e/latest reserach/2004/20041118/20041118.html: Latest researches, "n-Type Organic Thin Film Transistor Prepared by Printing Method."
2. http://www.lucent.com/news: Bell Lab Research Review Report, Report of the investigation committee on the possibility of scientific misconduct in the work of Hendrik Schön and Coauthors, 2006/11/29.
3. H. W. Kroto, J. R. Heath, S. C. O'Brien, R. F. Curl, and R. E. Smally, *Nature*, ***318***, 162 (1985).
4. E. A. Rohlfing, D. M. Cox, and A. Kaldon, *J. Chem. Phys.*, ***81***, 3322 (1984).
5. H. W. Kroto, *Angew. Chem. Int. Ed. Engl.*, ***31***, 111 (1992).
6. R. E. Smally, *The Science*, March/April, p. 22 (1991).
7. J. Baggott, *Perfect Symmetry*, Oxford University Press, Oxford, U.K. (1994).
8. W. Kratchmer, L. D. Lamb, K. Fostiropoulos, and D. R. Huffman, *Nature*, ***347***, 354 (1990).
9. R. E. Haufler et al., *J. Phys. Chem.*, ***94***, 8634 (9990).
10. G. Peters and M. Jansen, *Angew. Chem. Int. Ed. Engl.*, ***31***, 223 (1992).
11. J. B. Howard, J. T. McKinnon, Y. Markarousky, A. L. Lafleur, and M. E. Johnson, *Nature*, ***352***, 139 (1991).
12. R. D. Averitt, J. M. Alford, and N. J. Halas, *Appl. Phys. Lett.*, ***65***, 374 (1994).
13. R. A. Laudise, Ch. Kloc, P. G. Sinpkins, and T. Siegrist, *J. Cryst. Growth* ***187***, 449 (1998).
14. R. Taylor, J. P. Hare, A. K. Abdul-Sada, and H. W. Kroto, *J. Chem. Soc. Chem. Commun.*, ***20***, 1423–1425 (1990).
15. C. J. Welch and H. Pirkle, *J. Chromatogr.*, ***609***, 89 (1992).
16. S. Larsson, A. Volosov, and A. Rosen, *Chem. Phys. Lett.*, ***137***, 501 (1987).
17. D. E. Weeks and W. G. Harter, *J. Chem. Phys.*, ***90***, 4744 (1989).
18. R. E. Stanton and M. D. Newton, *J. Phys. Chem.*, ***92***, 2141 (1988).
19. S. J. Cyvin, E. Brendsdal, B. N. Cyvin, and J. Brunroll, *Chem. Phys. Lett.*, ***143***, 377 (1988).
20. M. S. Dresselhaus, G. Dresselhaus, and P. C. Eklund, *Science of Fullerenes and Carbon Nanotubes*, Chap.11, Academic Press, New York (1996).
21. A. M. Rao et al., *Science*, ***259***, 955 (1993).
22. R. D. Johnson, G. Meijer, and D. S. Bethune, *J. Am. Chem. Soc.*, ***112***, 8983 (1990).
23. J. M. Hawkins, A. L. Meyer, A. Timothy, S. Loren, and F. J. Salam, *J. Phys. Chem.*, ***95***, 9 (9991).
24. W. I. F. David et al., *Nature*, ***353***, 147 (1991).
25. R. C. Haddon, *Acc. Chem. Res.*, ***25***, 127 (1992).
26. R. C. Haddon, L. E. Brus, and K. Raghavachari, *Chem. Phys. Lett.*, ***125***, 459 (1996).
27. A. D. J. Haymet, *Chem. Phys. Lett.*, ***122***, 421 (1985).
28. S. Saito and A. Oshiyama, *Phys. Rev. Lett.*, ***66***, 2637–2640 (1991).
29. W. I. F. David, R. M. Ibberson, and T. Matsuo, *Proc. R. Soc. Lond.*, ***A442***, 129 (1993).
30. R. Tycko, R. C. Haddon, G. Dabbagh, S. H. Giarum, D. C. Douglassc, and A. M. Muujsce, *J. Phys. Chem.*, ***95***, 518 (1991).
31. D. A. Neumann et al., *Phys. Rev. Lett.*, ***67***, 3808 (1991).
32. A. F. Hebard, *Phys. Today*, ***45***, 26 (November 1992).
33. K. Prassides, H. W. Kroto, R. Taylor, D. H. M. Walton, W. I. F. David, J. Tomkinson, R. C. Haddon, M. J. Rosseinsky, and D. W. Murphy, *Carbon*, ***30***, 1277 (1992).
34. J. H. Weaver, *J. Phys. Chem. Solids*, ***53***, 1433 (1993).
35. T. Arai, Y. Murakami, H. Suenatsu, K. Kikuchi, Y. Achiba, and I. Ikemoto, *Solid State Commun.*, ***84***, 827 (1992).
36. J. Mort et al., *Chem. Phys. Lett.*, ***186***, 284 (1992).
37. A. F. Hebard, R. C. Haddon, R. M. Fleming, and A. R. Kortan, *Appl. Phys. Lett.*, ***59***, 2109 (1991).
38. G. B. Alers, B. Golding, A. R. Kortan, R. C. Haddon, and F. A. Thiel, *Science*, ***257***, 511 (1992).
39. S. Kazaoui, R. Ross, and N. Minami, *Solid State Commun.*, ***90***, 623 (1994).
40. D. J. van den Heuvel et al., *Chem. Phys. Lett.*, ***233***, 284 (1995).
41. B. Pevzner, A. F. Hebard, R. C. Haddon, S. D. Senturia, and M. D. Dresselhaus, *Mater. Res. Soc. Symp. Proc.*, ***359***, 423 (1995).
42. F. Kajzar, *Synth. Met.*, ***54***, 21 (1993).
43. Y. B. Zhao, D. M. Poirier, R. J. Pachman, and J. H. Weaver, *Appl. Phys. Lett.*, ***64***, 577 (1994).
44. P. Zhou et al., *Appl. Phys. Lett.*, ***60***, 2871 (1992).
45. K. Tanigaki, S. Kuroshima, and T. W. Ebbesen, *Thin Solid Film*, ***257***, 154 (1995).
46. A. Koma, *J. Cryst. Growth*, ***201/202***, 236 (1999).
47. Y. Saito, *Mater. Sci. Eng. B*, ***18***, 229 (1993).
48. M. Sakurai, H. Tada, and A. Koma, *Jpn. J. Appl.*, ***30***, L1892 (1991).
49. G. Genstlnblum, L. M. Yu, J. J. Pireaux, P. A. Thiry, R. Caudano, J. M. Themlin, S. Bouzidi, F. Coletti, and J. M. Debever, *Appl. Phys.*, ***A56***, 175 (1993).
50. H. Takashima, M. Nakaya, A. Yamamoto, and A. Hashimoto, *J. Cryst. Growth*, ***227/228***, 825 (2001).
51. H. Takashima, M. Nakaya, A. Yamamoto, and A. Hashimoto, *J. Cryst. Growth*, ***227/228***, 829 (2001).
52. D. Yokoyama, H. Nojiri, A. Yamamoto, and A. Hashimoto, *Phys. Stat. Sol.* (a), ***195***, 3 (2003).
53. N. Teraguchi, A. Suzuki, Y. Saito, T. Yamaguchi, T. Araki, and Y. Nanishi, *J. Cryst. Growth*, ***230***, 392 (2001).

54. N. Onojima, J. Suda, and H. Matsunami, *J. Cryst. Growth*, ***237–239***, 1012 (2002).
55. V. Lebedev, B. Schroter, G. Kipshidze, and W. Richter, *J. Cryst. Growth* ***207***, 266 (1999).
56. U. Kaiser, P. D. Brown, I. Khodos, C. J. Humphreys, H. P. D. Schenk, and W. Richter, *J. Mater. Res.*, ***14***, 2036 (1999).
57. K. Kudo, M. Yamashina, and T. Moriizumi, *Jpn. J. Appl. Phys.*, ***23***, 130 (1984).
58. H. Koezuka, A. Tsumura, and T. Ando, *Synth. Met.*, ***18***, 699 (1987).
59. J. Takeya, M. Yamagishi, Y. Tominari, R. Hirahara, Y. Nakazawa, T. Nishikawa, T. Kawase, T. Shimoda, and S. Ogawa, *Appl. Phys. Lett.*, ***90***, 102120 (2007).
60. R. C. Haddon, A. S. Perei, R. C. Morris, T. T. M. Palsta, A. F. Hebard, and R. M. Fleming, *Appl. Phys. Lett.*, ***67***, 121 (1995).
61. J. Tang, G. Xing, Y. Zhao, L. Jing, H. Yuan, F. Zhao, X. Gao, H. Qian, R. Su, K. Ibrahim, W. Chu, L. Zhang, and K. Tanigaki, *J. Phys. Chem.*, ***B111***, 11929 (2007).
62. M. Kitamura, S. Aomori, J. Ho Na, and Y. Arakawa, *Appl. Phys. Lett.*, ***93***, 033313 (2008).
63. J. Kido, M. Kimura, and K. Nagai, *Science*, ***267***, 1332 (1995).
64. D. X. Wang, Y. Tanaka, M. Iizuka, S. Kuniyoshi, K. Kudo, and K. Tanaka, *Jpn. J. Appl. Phys.*, ***38***, 256 (1999).
65. Y. Ohmori, K. Muro, M. Onoda, and K. Yoshino, *Jpn. J. Appl. Phys.*, ***31***, L646 (1992).
66. T. Yasuda, T. Goto, K. Fujita, and T. Tsutsui, *Appl. Phys. Lett.*, ***85***, 2098 (2004).
67. T. Nishikawa, S. Kobayashi, T. Nakanowatari, T. Mitani, T. Shimoda, Y. Kubozono, G. Yamamoto, H. Ishii, M. Niwano, and Y. Iwasa, *J. Appl. Phys.*, ***97***, 104509 (2005).
68. R. Tamura, E. Lim, T. Manaka, and M. Iwamoto, *J. Appl. Phys.*, ***100***, 114515 (2006).
69. J. A. Misewich, R. Martel, Ph. Avouris, J. C. Tsang, S. Heinze, and J. Tersoff, *Science*, ***300***, 783 (2003).
70. J. Zaumseil, R. H. Friend, and H, Sirringhaus, *Nat. Mater.*, ***5***, 69, (2006).
71. T. Takahashi, T. Takenobu, J. Takeya, and Y. Iwasa, *Adv. Funct. Mater.*, ***17***, 1623 (2007).
72. H. Nojiri, D. Yokoyama, A. Yamamoto, and A. Hashimoto, *Diamond Relat. Mater.*, ***14***, 518 (2005).
73. Y. G. Yoon, G. B. Kim, B. I. Lee, and S. K. Joo, *Thin Solid Films*, ***466***, 303–306 (2004).
74. C. P. Jarrett, K. Pichler, R. Newbould, and R. H. Friend, *Synth. Met.*, ***77***, 35–38 (1996).
75. H. Bassler, *Phys. Stat. Sol.*, (b) ***175***, 15–56 (1993).
76. K. Horiuchi, S. Uchino, K. Nakada, N. Aoki, M. Shimizu, and Y. Ochiai, *Physica B*, ***329–333***, 1538–1539 (2003).
77. T. W. Ebbesen, J. S. Tsai, K. Tanigaki, J. Tabuchi, Y. Shimakawa, Y. Kubo, I. Hirosawa, and J. Mizuki, *Nature*, ***355***, 620 (1992).
78. T. W. Ebbesen, J. S. Tsai, K. Tanigaki, H. Hiura, Y. Shimakawa, Y. Kubo, I. Hirosawa, and J. Mizuki, *Physica* C, **203**, 163 (1992).

16

The Cooper-Pair Transistor

16.1 Introduction 16-1
16.2 Theory of Operation 16-1
The Single Josephson Junction • Coulomb Blockade • Band Structure of the CPT • Quasiparticle Poisoning
16.3 Fabrication 16-9
Electron-Beam Lithography and Two-Angle Deposition • Aluminum and Gap Engineering
16.4 Practical Operation and Performance 16-10
Current Switching Electrometry • Zero-Biased rf Electrometry
16.5 Present Status and Future Directions 16-16
Acknowledgment 16-16
References 16-16

José Aumentado
National Institute of Standards and Technology

16.1 Introduction

The Cooper-pair transistor (CPT) is a three-terminal superconducting device composed of a mesoscale superconducting island connected to drain and source leads via ultrasmall (~100 nm) Josephson junctions (see Figure 16.1). Due to its small size, the energy to add a single Cooper pair to the island can be large compared with the typical temperatures at which similar quantum circuits are operated, $T < 100\,\mathrm{mK}$. Because of this, the transport properties of the device can be strongly dependent on the polarization charge presented by a capacitively coupled gate electrode and operated as a transistor with high input impedance. As an electrometer, it is useful as it can be operated with very little dissipation and should minimally influence the systems that it is measuring. As we will see, its similarity to another quantum circuit, the Cooper-pair box (CPB), marks it as a useful device to study decoherence in superconducting quantum bits (qubits) due to unpaired electrons.

While the CPT is topologically identical to the normal-state single-electron transistor (SET), it is operated in the superconducting state, and the superconducting nature of the device modifies the transport properties in several important ways. For our purposes, we also distinguish the CPT from the superconducting single-electron transistor (SSET) as a mode of operating this particular double-junction device. As a CPT, it is operated on the supercurrent branch near zero voltage in the coherent Cooper-pair transport regime, while as an SSET, it is operated at finite voltage bias and can include several incoherent hybrid quasiparticle/Cooper-pair tunneling processes.

16.2 Theory of Operation

As shown in Figure 16.1a, the device is composed of two Josephson junctions and can, at its core, be regarded as a single Josephson-like element with an added internal charge degree of freedom. This modification is important as it allows the CPT to act as a tuneable Josephson junction that is sensitive to charge. In this spirit, it is important that we begin with a conceptual understanding of a single Josephson junction.

16.2.1 The Single Josephson Junction

A superconducting Josephson junction is composed of a thin insulating barrier connecting two superconducting electrodes. In 1962, Brian Josephson made the remarkable statement that these junctions should support a supercurrent, that is, a dissipationless current at zero voltage (Josephson, 1962). This is a consequence of the finite quantum mechanical tunneling probability that arises from the spatial overlap in the superconducting order parameter on either side of a thin junction barrier. Josephson encapsulated this effect in the following equations that relate the current and the voltage to the dynamics of the phase difference across the junction*

$$I = I_0 \sin\delta \tag{16.1}$$

$$V = \varphi_0\dot{\delta}. \tag{16.2}$$

---

* We use the notational shorthand $\varphi_0 \equiv \hbar/2e$. This is simply the superconducting flux quantum $\Phi_0 = h/2e$ divided by 2π.



FIGURE 16.1 (a) Field emission micrograph of typical CPT. (b) 3D equivalent model showing two-angle/double image deposition (see Section 16.3) and location of junctions at the overlap. (c) The CPT is effectively a Josephson junction with a critical current and inductance that modulate with gate polarization charge/voltage $n_g \equiv C_g V_g / e$.

Taken at face value, these equations are the constitutive equations defining the Josephson junction as an inductor-like nonlinear circuit element. I_0 is a "critical current" beyond which the junction cannot support a supercurrent and the junction switches to a finite voltage branch in the current–voltage (I–V) characteristic. It can be computed from the low-temperature form of the Ambegaokar–Baratoff relation* (Ambegaokar and Baratoff, 1963).

$$I_0 = \frac{2}{eR_N} \frac{\Delta_1 \Delta_2}{\Delta_1 + \Delta_2} K\left(\frac{|\Delta_1 - \Delta_2|}{\Delta_1 + \Delta_2} \right), \tag{16.3}$$

where

Δ_1 and Δ_2 are the superconducting gap energies on either side of the insulating barrier

K is the complete elliptic integral of the first kind

If $\Delta_1 \sim \Delta_2$, $K \rightarrow \pi/2$ and

$$I_0 \simeq \frac{\pi}{eR_N} \frac{\Delta_1 \Delta_2}{\Delta_1 + \Delta_2}. \tag{16.4}$$

The most commonly used superconductor for CPTs (and SETs) is aluminum, $\Delta_{\text{Al}} = 180$–$250\,\mu\text{eV}$. Typical junction sizes are ~100 nm × 100 nm that yield junction resistances in the range of $10\,\text{k}\Omega < R_N < 100\,\text{k}\Omega$. With these parameters, the critical current ranges from 1 to 100 nA.

The presence of the phase δ across the junction in the equations marks it as an inductor-like element that can store magnetic flux. Following this reasoning, one can derive a Josephson inductance by finding the scaling coefficient between the voltage and the time derivative of the current,

$$L_J(I) = \frac{L_{J0}}{|\cos\delta|} = \frac{L_{J0}}{\sqrt{1-(I/I_0)^2}}, \quad \text{where } L_{J0} \equiv \frac{\varphi_0}{I_0}. \tag{16.5}$$

One can also define a Josephson energy that is a function of the phase difference δ,

$$E_J = \varphi_0 I_0 |\cos\delta| = E_{J0}\sqrt{1-\left(\frac{I}{I_0}\right)^2}, \quad \text{where } E_{J0} \equiv \varphi_0 I_0. \tag{16.6}$$

This can be interpreted as the magnetic energy that is stored in the element. This energy has a deeper significance as the coupling energy between Cooper-pair charge states on either side of the junction and will be important in calculating the energy bands of the CPT. For CPT Josephson junctions, the equivalent inductances are typically ~10–30 nH and the energies 20–80 μeV (0.2–1 K in temperature units).

16.2.1.1 The *I–V* Curve and Phase Dynamics

16.2.1.1.1 The I–V Curve

The CPT is operated on the so-called "supercurrent branch" of the I–V curve at (or near) zero voltage. The two measurement modes that we discuss in this chapter involve measuring the

---

* The form of the Ambegaokar–Baratoff relation shown here is uncommon in that it acknowledges the difference in gap energies that seems to be typical in evaporated aluminum junctions. This gap energy difference is usually ignored in the early SSET and CPT literature but has become important in more recent CPT experiments.



FIGURE 16.2 (a) Schematic I–V curve/characteristic for an ultrasmall Josephson junction. The ideal $T = 0$ I–V is shown in light gray, switching to the voltage state at $I_b = I_0$. For $T > 0$, thermal fluctuations can drive the system to the voltage state at much lower bias currents in ultrasmall ($A_{jn} < 0.01\,\mu\text{m}^2$) junctions, as shown in black. (b) $I_b < I_0$. The phase particle is trapped in a local minima of a washboard potential and $\langle\dot{\delta}\rangle = 0$ and no voltage is developed across the junction. (c) $I_b = I_0$. The washboard potential tilted at exactly the critical slope necessary to "release" the phase particle from its local minimum and enter a free-running state at finite voltage, V ($= \varphi_0\langle\dot{\delta}\rangle > 0$). (d) $I_b < I_0$. Phase diffusion. In ultrasmall junctions, thermal fluctuations can drive the phase to evolve in a 1D random walk of phase steps $\Delta\phi \simeq 2\pi$. Since the washboard is tilted, this results in a slow diffusion in one direction, V ($= \varphi_0\langle\dot{\delta}\rangle$) > 0, although it is still considered to be on the "supercurrent branch."

switching current I_{sw}, at which the CPT switches from the supercurrent branch to the finite-voltage branch as well as measuring the effective inductance L_J of the CPT when biased at zero current. While the small size of the junctions and internal charge degree of freedom will affect these parameters significantly, it is worthwhile to first look at the single junction case and understand how the dynamics of the phase determine the structure of the I–V curve (see Figure 16.2a).

16.2.1.1.2 The Resistively and Capacitively Shunted Junction (RCSJ) Model

A more realistic model of a single Josephson junction includes a parallel shunt resistance and capacitance (see inset in Figure 16.2a). The shunt resistance R encapsulates the resistance of the junction to normal/quasiparticle currents through the junction, while the capacitance C is simply the physical capacitance that arises from having two planar electrodes overlapping with an insulating barrier in between. In the junctions comprising a CPT, the intrinsic $R > 10\,\text{k}\Omega$ and is considered effectively "unshunted" since R is much bigger than the impedance presented by the Josephson inductance. As noted previously, the Josephson tunnel element is a nonlinear inductance but, for small phase excursions, it looks like a linear inductor. The circuit model presented then looks very much like a parallel LCR circuit or damped simple harmonic oscillator with a natural frequency

$$\omega_p = \frac{1}{\sqrt{L_{J0}C}} = \sqrt{\frac{2eI_0}{\hbar C}}. \qquad (16.7)$$

This is usually called the "plasma frequency" and has the significance of simply being the frequency of small oscillations for a Josephson junction.

Although this model can be used to describe the intrinsic Josephson junction dynamics, it is also useful in determining the dynamics when the junction is placed in an arbitrary measurement circuit. If, for instance, we want to current bias the junction, we might add a voltage source V_b in series with a resistor R_b and construct a Norton equivalent that is simply an ideal current bias $I_b = V_b/R_b$ in parallel with an output impedance R_b.[*] In this case, we can roll R_b into the shunt R in our RSJ model. With this simple circuit equivalent, we can derive a set of first-order differential equations defining the equations of motion for the phase by writing down Kirchoff's equations for the currents in each branch. We can write this system of equations as a single second-order differential equation

$$\ddot{\delta} + \frac{1}{RC}\dot{\delta} + \omega_p^2\left(\sin\delta - \left(\frac{I_b}{I_0}\right)\right) = 0. \qquad (16.8)$$

For small δ at zero current bias, this describes the motion of a particle with coordinate δ oscillating in a quadratic potential with a friction term, viz., it's a damped simple harmonic oscillator (and is consistent with our earlier statement that L_J is linear for small oscillations). At finite current bias, however, this equation describes the motion of the particle in a tilted sinusoidal (or *washboard*) potential.[†] We know from Equation 16.2 that in order for the junction to support a finite dc voltage across it, the particle must have some net motion in the phase, that is, $\langle\dot{\delta}\rangle \neq 0$. Since the particle is trapped at a fixed phase when $I_b < I_0$, we have a well-defined phase and the junction remains in the supercurrent state (see Figure 16.2b). By applying a bias current, we tilt the washboard and, when $I_b = I_0$, the particle is tipped out of its well and begins to run away (Figure 16.2c). In this free-running state, the time derivative of the phase has both an ac and a dc component corresponding to ac and dc voltages across the junction. In a more realistic treatment, I_b includes a stochastic contribution from thermal fluctuations due to the dissipation in the environment and so the current at which the junction switches to the free-running state is lower than I_0 since thermal excitations can drive the phase particle over the potential barrier prematurely. Because of this, the measured current is distributed according to the statistics of a thermally excited (Kramers) escape process (Fulton and Dunkleberger, 1974). We will differentiate this switching current I_{sw} from the ideal Ambegaokar–Baratoff value I_0 and remember that it is actually a statistical variable.

---

[*] This vast oversimplification has its caveats and must be amended to account for stray capacitance in the bias lines and any other reactances relevant in the frequency range of our junction dynamics (typically $\omega < 50\,\text{GHz}$ for small aluminum junctions).

[†] More in depth discussions of the RCSJ model can be found in Tinkham (2004) and Clarke and Braginski (2004).

If we reduce the current bias in the free-running, finite voltage state, the particle velocity begins to slow down due to the dissipation in the circuit. Once the dissipation rate can compensate for the ac power generated by the free-running voltage oscillations, the particle "retraps" into a minima in the washboard potential and the junction returns to the zero-voltage supercurrent branch. The current at which this happens, I_{ret}, the "return current" is an indication of the amount of damping or dissipation in the environment at the free-running oscillation frequency (Tinkham, 2004). Roughly, the closer to zero I_{ret} is, the less damping there is. Although the CPT is designed and operated in the unshunted, hysteretic regime, in many practical dc SQUID magnetometers, the junctions are intentionally shunted with damping resistors to eliminate hysteresis in the *I–V* measurement permitting stable finite voltage operation.

16.2.1.1.3 Concerns Specific to Small Junctions

While the picture above is the standard way to look at relatively large junctions (area $\gtrsim 1\,\mu\text{m}^2$), the junctions in CPTs are usually about a factor of 100 smaller and have much smaller capacitances. The main consequence of this is that the observed switching currents can easily be smaller than I_0 by an order of magnitude. One way to understand this is to return to the harmonic oscillator analogy. We can see that $\omega_p^2 \propto 1/C$, so C is an effective mass for our "phase particle." In CPT junctions, this means that the equivalent phase particle can be relatively light compared with its larger junction cousins and so thermal fluctuations, even at 100 mK, can have a more significant effect, kicking the particle into the free-running state much more easily. This has the end effect of reducing I_{sw} far below I_0 and also widening the distribution of I_{sw} (Figure 16.2a).

A more problematic effect of the light phase particle mass is the fact that the same thermal fluctuations can "kick" the phase particle from well to well in the washboard potential in a process called "phase diffusion" (Kautz and Martinis, 1990). At zero current bias, this results in a one-dimensional random walk in the phase with zero mean. At finite current, the tilt in the washboard biases this diffusive motion in one direction, such that the mean phase velocity $\langle\dot{\delta}\rangle$ can be positive (negative) at positive (negative) bias (see Figure 16.2d). The result of all of this is that at finite currents below the switching current, we often see a small finite voltage. This slope is fairly uniform near zero current and gives the supercurrent branch a slight resistive contribution that can correspond to 10 s or even 100 s of Ωs. The downside of this behavior is that the junction or CPT is not truly dissipationless.

For electrometer operation, we want I_{sw} to have as narrow a distribution as possible since it is the quantity that will vary with applied gate voltage/polarization charge. It has been demonstrated, however, that one can narrow this distribution and also increase I_{sw}, so that it is closer to I_0 by fabricating a larger capacitance (a few picofarad) in the leads shunting the junction to "weigh down" the phase particle (Joyez et al., 1994; Joyez, 1995).

16.2.2 Coulomb Blockade

While the above discussion of a single junction will eventually be relevant to the CPT measurements we are interested in, we have not yet seriously considered the role of the internal charge degree of freedom in determining the overall critical current and Josephson inductance in this device. This is, afterall, the knob that turns the CPT into a transistor.

We can qualitatively recognize the role of the island charge by first determining the energy required to charge the CPT island with a single electron charge e,

$$E_C = \frac{e^2}{2C_\Sigma}, \tag{16.9}$$

where

$$C_\Sigma \equiv C_{J1} + C_{J2} + C_g + C_{stray}. \tag{16.10}$$

Here, C_Σ is the total capacitance as seen by the island, and while it includes the junction and gate capacitances, it also includes a "catch-all" term, C_{stray}, that is meant to include any contributions from unintentional coupling to ground. In practice, $C_{stray} \ll C_\Sigma$ and can usually be ignored. The energy E_C is called the single-electron Coulomb blockade energy (Devoret and Grabert, 1992).

For typical junction capacitances $C_{J1,J2} \lesssim 1$ fF and gate capacitances of 0.01–1 fF, E_C can be on the order of ~100–400 μeV. In temperature units, this temperature is 1–5 K and is therefore a significant energy scale compared with typical operating temperatures. As noted previously, the Josephson energies of these junctions are roughly on par with the Coulomb blockade energies, so we can qualitatively assume that both energy scales will play a role in the transport.



$$n_g \equiv \frac{C_g V_g}{e}$$
$$C_\Sigma = C_1 + C_2 + C_g$$
$$E_C = \frac{e^2}{2C_\Sigma}$$

FIGURE 16.3 Simplified CPT schematic. Each ultrasmall junction has an associated Josephson energy and phase along with an overall Coulomb blockade energy that defines the energy required to place discrete charge on the island. Voltage applied to the gate injects "gate polarization charge" into modulating the Coulomb or ionization energy. This modulates its Josephson-like behavior through charge-phase duality (see text).

16.2.3 Band Structure of the CPT

Since we have two junctions in series (Figure 16.3), we must define separate phases for each junction δ_1 and δ_2.* We can now be more precise about the role of the charging energy by looking at the Hamiltonian for the CPT and how the contributions couple to the phases and the island charge n,

$$H = H_{J1} + H_{J2} + H_{CB} + H_{QP}. \qquad (16.11)$$

$H_{J1,J2}$ are the contributions due to the Josephson energy coupling the charge states on either side of the junctions, while H_{CB} is the Coulomb blockade contribution. Explicitly, we have

$$H_{J1,J2} = -E_J \cos\delta_{1,2} \qquad (16.12)$$

$$H_{CB} = \frac{E_C}{4}(n - n_g)^2. \qquad (16.13)$$

Here we have used the reduced gate voltage $n_g \equiv C_g V_g / e$ that is the polarization charge applied by the gate in electron units. H_{QP} is the contribution from quasiparticle excitations in the leads and on the island. Physically, they correspond to unpaired electrons/holes that can be introduced to the system via thermal excitations or some nonequilibrium process that can break Cooper pairs. While this is an important contribution, we ignore it now to facilitate the discussion.

We can write down a matrix equivalent of Equation 16.11 in the basis of island charge states $|n\rangle$, noting that the Josephson coupling terms that link Cooper-pair charge states on either state of the junction also link "adjacent" Cooper-pair charge states $|n\rangle \rightarrow |n \pm 2\rangle$.† Defining "external" and "internal" phases $\delta = \delta_1 + \delta_2$ and $\theta = \delta_1 - \delta_2$ and setting $\theta = 0$ (equivalent to assuming that the island has negligible inductance), we can write H in the charge basis. For example, the Hamiltonian spanning the Cooper-pair island charge states $|-2\rangle$, $|0\rangle$, and $|2\rangle$ is

$$H = \begin{bmatrix} E_C(-2-n_g)^2 & -\frac{1}{2}(E_{J1}e^{-i\delta/2} + E_{J2}e^{+i\delta/2}) & 0 \\ -\frac{1}{2}(E_{J1}e^{+i\delta/2} + E_{J2}e^{-i\delta/2}) & E_C(-n_g)^2 - \frac{1}{2} & (E_{J1}e^{-i\delta/2} + E_{J2}e^{+i\delta/2}) \\ 0 & -\frac{1}{2}(E_{J1}e^{+i\delta/2} + E_{J2}e^{-i\delta/2}) & E_C(2-n_g)^2 \end{bmatrix}. \qquad (16.14)$$

The eigenvalues for this matrix represent the energy bands and are functions of n_g and external phase δ. The choice of basis size (how big a matrix one really needs to write down) is dictated by the ratio of $E_{J1,2}/E_C$. If this ratio is small, charge is easily localized and the corresponding external phase fluctuations are large, so the device has a weak effective Josephson energy. In this case, the charge basis may be described well by a small subspace of $|n\rangle$ spanning only a few charge states near $|0\rangle$. If $E_{J1,2}/E_C \gtrsim 1$, this approximation fails and one must write down a larger matrix spanning a bigger subspace of $|n\rangle$. In this limit, the charge on the island is no longer as well defined as its quantum mechanical state is now described by a linear superposition of several charge states. Likewise, fluctuations in the CPT external phase are then small and the CPT begins to look like a single Josephson junction.

16.2.3.1 The Uncertainty Principle at Work

We can numerically diagonalize Equation 16.14 to calculate the eigenvalues at various n_g and δ. Figure 16.4 shows the resulting eigenenergy surfaces corresponding to the ground and first excited state energies, ϵ_0 and ϵ_1. The quantities that we want to measure, $I_{sw}(n_g)$ and $L_J(n_g)$, are defined by the first and second derivatives of these surfaces in the phase. The size of this modulation is a direct consequence of how well the CPT island localizes Cooper pairs, $n2e$, through the uncertainty relation between charge number and phase, $\Delta n \Delta\delta \geq 1/2$. In this sense, the CPT is a strange charge-based device because it relies on the competition between number and phase uncertainty. This is in contrast to the SSET or SET where E_C is entirely dominant. In the CPT, we would like E_C to be big but would also like E_J to be comparable in magnitude, so that the switching current is not so small that it is difficult to measure well. Similarly, rf measurements of the Josephson inductance (described later in this review) become easier at bigger E_J as larger signal powers can be used while biased on the supercurrent branch.

16.2.3.2 Calculation of the Critical Current Modulation

The critical current of the CPT can now be determined from the eigenenergies calculated above. By restricting to the ground state band $\epsilon(n_g, \delta)$, we can compute the critical current (Joyez, 1995)

$$I_0(n_g) = \frac{1}{\varphi_0} \left. \frac{\partial \epsilon_0(n_g, \delta)}{\partial \delta} \right|_{\delta_{max}}, \qquad (16.15)$$

---

* The phases δ_1 and δ_2 bear a strict conjugate correspondence to the number of Cooper pairs having "flown" through junctions 1 and 2. This discussion closely follows that given by Joyez (1995) and a more extensive discussion of choosing appropriate quantum variables appears there.

† For consistency with Joyez (1995), n in $|n\rangle$ refers to the single electron number and *not* Cooper pair number.



FIGURE 16.4 **(See color insert following page 20-14.)** The ground (ϵ_0) and first excited (ϵ_1) states calculated by numerically diagonalizing Equation 16.11 with the energies indicated in the figure.



FIGURE 16.5 Numerically calculated CPT critical currents for various ratios of $E_{J,jn}/E_C$. In this example, E_C is fixed at 115 μeV, while $E_{J,jn}$ is varied.

where δ_{max} is the phase maximizing the derivative.* In Figure 16.5, we show the calculated critical currents for several ratios of E_J/E_C. Note that the calculated currents are 2*e* periodic in the applied gate charge which is the result of the Josephson coupling of Cooper-pair charge states. In practice, measured switching currents in CPTs are usually significantly smaller than the calculated value due to small-junction effects noted above. However, the total magnitude of the modulation can be on the order of 10 nA for practical aluminum device parameters and is easily measured.

16.2.3.3 Calculation of the Effective Inductance Modulation

The ground state energy surface $\epsilon_0(n_g, \delta)$ corresponds to an effective Josephson energy that is a function of charge as well as phase. When the ratio $E_J/E_C \lesssim 1$, the phase dependence, while still 2π periodic, gets "peaky" near odd-integer n_g. Despite this, one may still define a Josephson inductance in a similar manner (Sillanpää et al., 2004; Naaman and Aumentado, 2006b), that is,

$$L_J(n_g) = \frac{1}{\varphi_0^2} \frac{\partial^2 \epsilon_0(n_g, \delta)}{\partial \delta^2}\bigg|_{\delta=0}. \qquad (16.16)$$

This is similar to Equation 16.5, but since the $\epsilon_0(n_g, \delta)$ is not strictly sinusoidal, we do not get the exactly the same result. For typical aluminum device parameters, the inductance modulation can be 10–100 nH and, like the switching current, is easily measured.

16.2.4 Quasiparticle Poisoning

Although the "quasiparticle" excitations that are talked about in superconductivity do not explicitly bear a well-defined charge, they do represent the screened excitations presented by an unpaired electron that might exist due to the breaking of a Cooper pair. A quasiparticle can tunnel onto a CPT island by "undressing" itself of its screening cloud and tunneling through a junction barrier alone. At this point, this additional charge presents a full electron charge offset to the CPT island. Since the CPT switching current and inductance are nominally 2*e* periodic in the gate charge, the addition of an extra electron can present a significant change in the way the CPT is operated, since it fluctuates the charge by *e*. In the literature, this problem was first discussed in terms of island "parity," but more recent work has favored the more colorful term "quasiparticle poisoning." The most important thing about quasiparticle poisoning for electrometry is that it is a stochastic process whose dynamics can happen on timescales comparable to our measurement time, so its effect on the resulting measurement must be well understood. That being said, quasiparticle poisoning has proven to be an interesting problem in itself, and the CPT has been very useful in its study.

---

* Incidentally, one can also take derivatives of the excited state eigenenergies and compute critical currents for those bands. Interested readers can see Flees et al. (1997) for further details.

To see how quasiparticles enter the picture, we now include the Hamiltonian H_{QP} in our description of the CPT,

$$H_{QP} = \sum_j \epsilon_j \gamma_j \gamma_j^\dagger. \tag{16.17}$$

The $\gamma_j, \gamma_j^\dagger$ are annihilation/creation operators for quasiparticle excitations in the superconductor (Tinkham, 2004), while ϵ_j is the energy of the excitation. In our case, this can be Δ_1 or Δ_2, remembering that the island and leads can have different gap energies. These quasiparticles are usually taken to be thermally generated and therefore have an exponentially small probability of existing at low temperatures. The expression for the quasiparticle density is (cf., Shaw et al., 2008),

$$n_{qp} = D(\epsilon_F)\sqrt{2\pi\Delta_j k_B T}\,\exp\left(\frac{-\Delta_j}{k_B T}\right). \tag{16.18}$$

$D(\epsilon_F)$ (=2.3 × 10^4 μm^{-3} J^{-1}) is the density of states at the Fermi energy and Δ_j is the superconducting gap energy in either film 1 or 2. Plugging in $\Delta \sim 200\,\mu$eV (aluminum) and T = 100 mK gives us 2 × 10^{-4} μm^{-3}. This is a very low number considering the volume of a generic CPT island and leads; yet we know, experimentally, that the actual quasiparticle density is typically 10–1000 μm^{-3} (Mazin, 2004; Shaw et al., 2008). The disparity in the thermal prediction versus the experimentally measured numbers is the first indication that the source for the quasiparticles we see at low temperatures is distinctly nonthermal in nature. As yet, no one has determined the source of these *nonequilibrium* quasiparticles and we are stuck with the problem of understanding them.

16.2.4.1 Energetics of the Nonequilibrium Quasiparticle Poisoning Process

Since we are forced to work in an environment filled with nonequilibrium quasiparticles, we must figure out how to include them in the band picture that we constructed above. We have three states of interest (see Figure 16.6) (Aumentado et al., 2004):



FIGURE 16.6 Three state nonequilibrium quasiparticle model. "0" state: no quasiparticles in vicinity of CPT, even parity. "ℓ" state: quasiparticle in leads even parity. "*i*" quasiparticle on island, odd parity.

State 0 No quasiparticles in or near the CPT island. *Even parity.*

State ℓ A quasiparticle is in the leads, in the vicinity of the CPT island. No quasiparticles on the island. *Even parity.*

State i A quasiparticle is on the CPT island. No quasiparticles in the leads near the island. *Odd parity.*

These states can all be described with the band structure derived in the previous section by offsetting the modulated energy surfaces by the superconducting gap energy, corresponding to where the quasiparticle lives, viz.,

$$\begin{aligned} E_0(n_g) &\equiv \epsilon_0(n_g, \delta = 0), \\ E_\ell(n_g) &\equiv \epsilon_0(n_g, \delta = 0) + \Delta_\ell, \\ E_i(n_g) &\equiv \epsilon_0(n_g + 1, \delta = 0) + \Delta_i. \end{aligned} \tag{16.19}$$

Here, we include the possibility of different gap energies in the leads and island, Δ_ℓ and Δ_i, respectively, and confine ourselves to $\delta = 0$. In principle, phase diffusion will smear these levels somewhat, but the average phase on the supercurrent branch will always be localized in the bottom of a potential well in the phase when biased near $I_b = 0$.

In Figure 16.7, we show the energy bands for two different pairs of island + gap energies using typical Coulomb, Josephson, and gap energies for an aluminum device. In the "type H" device (Figure 16.7a), the island gap is greater than the lead gap, and in the "type L" device, the reverse is true. Assuming that nonequilibrium quasiparticles are present, we can limit our discussion to E_ℓ and E_i. In the $T = 0$ limit, we expect the system to relax to the lowest energy state and the problem is reduced to whether the ℓ or i state energy is smallest (denoted in Figure 16.7a and d by the black dotted trace). For this purpose, we introduce the energy difference:*

$$\delta E_{\ell i}(n_g) \equiv E_i(n_g) - E_\ell(n_g). \tag{16.20}$$

At $T = 0$, the sign of this quantity determines what state we are in, that is,

$$\operatorname{sgn}[\delta E_{\ell i}] = \begin{cases} +1 & \text{even parity} \\ -1 & \text{odd parity} \end{cases} \tag{16.21}$$

---

* *A brief history detour.* In early treatments of quasiparticle poisoning, all quasiparticles were assumed to be thermal in nature, so the important energy in the problem is the free energy required for transition from 0 to i state (Tuominen et al., 1992, 1993; Amar et al., 1994; Joyez et al., 1994; Tinkham et al., 1995). This is basically the process of breaking a Cooper pair with thermal fluctuations. Experimentally, this model was more or less verified early on, but the situation was complicated by the anecdotal evidence that this picture failed to explain the numerous unpublished experiments that showed poisoning at low temperatures. In the absence of nonequilibrium quasiparticles, the early free energy theories are still valid and, in any case, when the system is heated sufficiently T > 250 mK, the thermal quasiparticle generation rate dominates over the nonequilibrium rate. For a good review of the early theory, see Tinkham (2004).



FIGURE 16.7 (a) Type H ($\Delta_\ell < \Delta_i$) energy bands. ℓ state/even parity (light gray), *i* state/odd parity (medium gray), 0 state/even parity (black solid). Minimum energy state is denoted as the black dotted trace. Corresponding even (light gray) and odd (medium gray) state (b) critical current and (c) effective inductance for a type H device. (d) Type L ($\Delta_\ell > \Delta_i$) energy bands. Corresponding even (light gray) and odd (medium gray) state (e) critical currents and (f) effective inductances for a type L device. Gray areas mark range in n_g where the CPT island is "trap-like," that is, a potential well for quasiparticles and the parity state is bimodal and can rapidly switch when coupled to thermal excitations.



FIGURE 16.8 (a) Barrier-like configuration of levels. (b) Trap-like configuration of levels.

$\delta E_{\ell i}$ is an effective potential barrier height for quasiparticles. When $\delta E_{\ell i}$ is positive, the CPT island looks like a barrier, and when it is negative, it looks like a trap (Figure 16.8). In reality, the system is at finite temperature, so this qualitative picture must be amended to include the possibility of thermal excitations (phonons) coupling to the quasiparticles and exciting them out of the trap. Since this is a thermal escape process, we must characterize the system in terms of the average lifetimes of the poisoned and unpoisoned states, τ_o and τ_e.* Likewise, it is also useful to talk about these lifetimes as rates, $\Gamma_{eo} = \Gamma_{0\ell} + \Gamma_{\ell i} = 1/\tau_o$ and $\Gamma_{oe} = \Gamma_{i\ell} = 1/\tau_e$. Γ_{eo} is known as the "poisoning rate" and Γ_{oe} is the "ejection rate."

Experimentally, at $T \lesssim 250$ mK, the poisoning rate Γ_{eo} has little temperature dependence and can be anywhere between 10^3 and 10^5 s^{-1} (Aumentado et al., 2004; Ferguson et al., 2006; Naaman and Aumentado, 2006b; Court et al., 2008b). The fact that this rate is constant in this temperature range points to the notion that the source is nonthermal in nature and the rate for Cooper-pair breaking in the leads determines the poisoning rate, $\Gamma_{eo} \sim \Gamma_{0\ell} \gg \Gamma_{\ell i}$. The ejection rate Γ_{oe} does, however, have a temperature dependence at these low temperatures since the process of kicking a quasiparticle out of a potential well is a thermal escape process. One can derive the probability of the even parity state (no quasiparticle on the island) using detailed balance arguments (Aumentado et al., 2004),

---

* The "*e*" and "*o*" refer to "even" and "odd" parity states. Odd parity corresponds to a single excess quasiparticle on the CPT island.

$$P_e = P_0 + P_\ell = \frac{1}{1+\beta_{0\ell}e^{-\delta E_{\ell i}/k_B T}}. \tag{16.22}$$

The factor, $\beta_{0\ell} \equiv \Gamma_{0\ell}/(\Gamma_{0\ell} + \Gamma_{\ell 0})$, accounts for the generation and recombination rates for nonequilibrium quasiparticles in the leads. What this all means is that there is not really any strictly quasiparticle-free zone for typical energies that we would use in practice.* In Figure 16.7, we denote the places where the CPT looks trap-like and it is apparent that both the L and H devices are affected. Even with the higher island gap, the H device can trap quasiparticles, albeit in a shallower potential, $\delta E_{\ell i}$ than presented by the L device and also over a smaller range in n_g.

It is interesting to note that if there is no source for nonequilibrium quasiparticles, $\Gamma_{0\ell} = 0$ ($\beta_{0\ell} = 0$) and $P_e = 1$ whether or not we have a barrier-like or trap-like profile. In other words, there would be no poisoning regardless of the relative gap energies. The fact that one sees poisoning easily in trap-like devices at low temperatures is the strongest indication that the quasiparticles in these systems are generated by some nonequilibrium process. Surprisingly, the temperature dependence above also predicts that the even state probability can actually be enhanced since, even though the poisoning rate might be fixed, the ejection rate can be increased by heating the CPT and giving quasiparticles energy to escape (Aumentado et al., 2004; Palmer et al., 2007).

This model of nonequilibrium quasiparticle poisoning was first roughly outlined and tested in Aumentado et al. (2004) using CPTs with engineered gap energy profiles and measured with the ramped current technique (see below). It was subsequently confirmed in several later experiments in both CPTs and CPBs using rf and dc techniques (Gunnarsson et al., 2004; Yamamoto et al., 2006; Palmer et al., 2007; Savin et al., 2007; Court et al., 2008b; Shaw et al., 2008).

16.3 Fabrication

16.3.1 Electron-Beam Lithography and Two-Angle Deposition

The majority of CPTs (and single-charge tunneling devices in general) are fabricated from evaporated aluminum using conventional electron beam lithography and electron-gun (or thermal) deposition techniques.

The most conventional method of fabrication is to first define the island and lead pattern of the CPT in a special double-layer e-beam resist stack that is spun onto a silicon substrate. The double-layer is constructed such that the upper “image” layer defines the pattern outline, while the lower “ballast” layer is meant to provide a vast “undercut” region underneath the image. This is usually achieved using resist for the lower layer that is much more sensitive to the e-beam exposure than the upper layer. When the pattern is written, the dosage required to generate the image overexposes the lower layer resist such that the pattern is much wider in the lower layer resist, forming an “undercut” region when the sample is developed (cf., Cord et al., 2006).



FIGURE 16.9 Angle deposition for the CPT. A mask is defined in electron-beam sensitive resist, usually in a bilayer configuration such that the underlayer is overdeveloped and the top (image) layer pattern can cast a shadow on the surface of the substrate from several angles. In this example, the leads for the device are deposited in the first deposition (dark gray) at an angle θ_1. After this deposition, oxygen is admitted into the deposition chamber forming an oxide on the surface of the metal. Finally, a second evaporation (light gray) is performed at θ_2 depositing the CPT island. In the process, Josephson junctions are formed at the overlap between the island and oxidized leads. (a) Shadow deposition through the top layer “image” resist. (b) Schematic of tilt configuration with respect to source.

The undercut region allows us to tilt the substrate so that the impinging aluminum atoms can deposit an image through the image resist mask at an angle (Figure 16.9). After the first aluminum deposition, oxygen is released into the chamber that grows a thin (<1 nm) insulating Al_xO_y layer on the surface of the aluminum. The substrate is then rotated to another angle and a second image is deposited onto the substrate such that it overlaps with the first oxidized image. In this manner, insulating junctions can be formed *in situ* without exposing the device to air. Subsequent processing removes the resist, so that it can be bonded up in a suitable measurement circuit. This process is called the “Dolan bridge” or “shadow deposition” technique (Dolan, 1977) and is used in almost all single-charge tunneling devices as well as most superconducting qubit designs. There are many variations on this technique but, surprisingly, the basic method has remained unchanged for more than 30 years.

16.3.2 Aluminum and Gap Engineering

Aluminum is regarded as the material of choice for these devices because of the general ease with which one can grow a reliable oxide layer at room temperature within the deposition chamber. Aluminum is easily deposited using both thermal and e-beam deposition techniques that are common to most clean rooms and requires very little in the way of special equipment. That being said, the CPT is a superconducting device whose operation is somewhat dependent on the quality of the superconducting gap.* In most general-purpose metal evaporators, the quality of the aluminum is completely beholden to the deposition hygiene of the community that uses the machine. For instance, the gap energy of aluminum is notoriously sensitive to the disorder and impurities that are present in the as-deposited film. For instance, two films deposited at identical rates but at different base pressures can yield gap energies that differ by 10s of μeV. This was done intentionally by Aumentado et al. (2004) to fabricate type L and H devices, but the same effect can be achieved by simply changing the thickness of the aluminum. It turns out that the gap energy can be enhanced substantially by making the film thinner (Townsend et al., 1972), and subsequent CPT experiments demonstrated that this method can be used to make CPTs (Yamamoto et al., 2006; Court et al., 2008a).

---

* The reason for this is not obvious. Basically, the difference in aluminum gap energies that one can achieve practically is ~50 μeV. In order to see any level of charge localization at $T = 100$ mK, we need $E_C \sim 100$ μeV. If we want useful switching current modulation (~10 nA) and inductance modulation (~10 nH), then we are stuck with $E_{J,jn} \sim 50$ μeV. For these values, it is difficult to get the E_ℓ and E_i bands to separate.

For reference, typical cryopumped e-gun deposition systems can have base pressures in the low 10^{-8} Torr range, especially if they are dedicated to aluminum and a few other well-behaved metals and employ a load-lock system for exchanging samples. These systems usually surpass more general use machines in film quality and oxide reproducibility. The author prefers e-gun deposition out of a bare water-cooled copper hearth rather than using thermal deposition out of a tungsten boat. Tungsten has a tendency to alloy with aluminum and repeated depositions from the same source yield films with inconsistent quality (resistivity and gap quality) and must be replaced on every pumpdown.

We note in passing that CPTs have been successfully fabricated from niobium with aluminum oxide junctions, but in none of the published work has anyone been able to reduce quasiparticle poisoning in any significant way. While this is awful for making charge-based qubits, these devices can still be used as electrometers, but the fabrication techniques can prove to be much more difficult since niobium is a refractory metal and difficult to evaporate. At its evaporating temperature, most practical deposition systems outgas so much that the quality of the film can be compromised and the integrity of the resist can also become an issue (Dolata et al., 2002, 2005). Others have used a sputtered niobium/aluminum oxide/niobium trilayer (ubiquitous in SQUID fabrication) and patterned using focused ion beam (Watanabe et al., 2004).

16.4 Practical Operation and Performance

The Coulomb, Josephson, and superconducting gap energies are all 10–300 μeV, so practical measurements are performed well below 1 K in a dilution refrigerator, usually at $T \lesssim 100\,\text{mK}$. There are currently two generic modes of operation of the CPT: current switching electrometry and rf electrometry. The main advantage of the current switching electrometry is its cost. rf electrometry can require relatively expensive microwave amplifiers, generators, and fast digitizers, while current switching electrometry can be achieved with simple function generators and voltage preamps operating with less than 1 MHz of bandwidth.

16.4.1 Current Switching Electrometry

One of the earliest methods for measuring the CPT was to measure the modulation of the switching current I_{sw} as a function of an applied gate voltage. This measurement is performed by cycling the current bias between the supercurrent and voltage branches in the I–V characteristic. We can track the current at which the CPT switches to the voltage state by tracking the voltage across the device and using a simple threshold trigger (see Figure 16.10). We can subdivide this measurement approach into ramped and



FIGURE 16.10 The switching current measurement. (a) Typical I–V curve for CPT device. The feature at ~0.4 mV ($\Delta_i + \Delta_\ell$) is the so-called Josephson quasiparticle peak or JQP and is due to more a complex Cooper-pair quasiparticle tunneling cycle. The device switches to the true voltage branch at $\gtrsim 2(\Delta_i + \Delta_\ell)$. Inset: Simplified measurement circuit schematic. (b) Expanded view of switching current cycle. The current is ramped along the supercurrent branch until the voltage across the CPT switches to the finite valued voltage branch. The current at which this happens is recorded, and the results of many ramp cycles are recorded in a switching current histogram as in (c).

---

* If the gap edge is not well defined and there is some finite density of states in the subgap, then the gap engineering arguments that we made previously lose their applicability. This is mostly only an issue in "dirtier" deposition systems.

pulsed current bias techniques. Each has its own merits, but the experimental literature is largely dominated by the ramped technique.

16.4.1.1 Ramped Switching Current Measurement

As the name suggests, the bias current through the CPT is ramped linearly in time such that the current exceeds the maximum switching current and is then returned to zero bias for the next cycle. The probability of switching at a particular current can be backed out from the histogram of switching currents accumulated over many cycles (see Figure 16.10a). This ramped bias current measurement was originally done in the late 1970s in relatively large junctions (Fulton and Dunkleberger, 1974), but the methodology is also suitable to small Josephson junction devices such as the CPT (Joyez, 1995).

This method can be used for electrometry since it yields a switching current histogram whose mean value changes with gate, but its power lies in the fact that one can obtain the switching or "escape" rate $\gamma_{sw}(I_p, n_g)$ through a straightforward transformation of the whole histogram as in the original work by Fulton and Dunkleberger (1974). This is useful since the escape rate contains information about the electron temperature and how well the system is isolated from external noise (Devoret et al., 1987).

16.4.1.2 Quasiparticle Poisoning in the Ramped Current Measurement

If quasiparticle poisoning is present, the effective Josephson energy of the CPT flickers between two different values corresponding to even and odd parities. Each of these energies has its own escape rate $\gamma_{sw,e}$ and $\gamma_{sw,o}$, and the observed switching current in any given ramp cycle is determined by the instantaneous state of the system as the current is ramped. If the ramp rate is fast enough such that it can span the distance separating the odd and even switching currents faster than the odd/even lifetimes, then the ramped measurement becomes a snapshot of the parity state and we see that the switching currents group around two distinct values as shown in type L device histograms in Figure 16.12.

In our example, the modulation of the switching current histograms is similar to that of the type H device, except that it shows a distinct 1*e* shifted image corresponding to the presence of the odd state, particularly where we predict the island potential to be trap-like. This bimodal behavior is really only evident if the measurement is faster than the state lifetimes. If the current bias ramp rate were slowed down significantly, then the system could flicker back and forth between parity states many times and we would only see switching distributions grouped around whichever parity state had the lowest switching current. That is, we would see a purely 1*e* modulation in the switching current. In the early literature, the available dc measurement techniques were unable to capture the dynamical nature of the quasiparticle parity states, and the periodicity (1*e* versus 2*e*) of the modulation was the only handle with which to gauge whether poisoning was present. Because of the dynamics of the poisoning process, this correlation can be misleading.

In the type L example given here, the device is definitely poisoned, particularly where we expect the island potential to look trap-like. However, if we examine the type H device's switching current modulation, it is distinctly 2*e* periodic (Figure 16.11). The early picture of poisoning would naively assume that the poisoning is not present when, in fact, it is happening much faster than a simple analysis would indicate. We know, for instance, that the island potential is trap-like over a narrower range and that the trap potential is shallow compared with the operating temperature (this is due to the gap engineering for the H device). Therefore, quasiparticles that get trapped on the island



FIGURE 16.11 (See color insert following page 20-14.) (a) Type H I_{sw} histograms versus n_g. Histogram height is displayed in grayscale on the right-hand side, whereas all counts are displayed equally on the left-hand side. As in Figure 16.7, the gray box in (a) denotes regions where the island potential is trap like for quasiparticles. (b) Selected histograms corresponding to several gate voltages. Device parameters: $\Delta_i = 246\,\mu\text{eV}$, $\Delta_\ell = 205\,\mu\text{eV}$, $E_C \simeq 115\,\mu\text{eV}$, and $E_{J1} = E_{J2} \simeq 82\,\mu\text{eV}$.



FIGURE 16.12 (a) Type L I_{sw} histograms versus n_g. Histogram height is displayed in grayscale on the right-hand side, whereas all counts are displayed equally on the left-hand side. As in Figure 16.7, the gray box in (a) denotes regions where the island potential is trap-like for quasiparticles. (b) Histogram at $n_g = 1$. Bimodal structure indicates relatively long-lived even and odd states. Device parameters: $\Delta_i = 205\,\mu\text{eV}$, $\Delta_\ell = 246\,\mu\text{eV}$, $E_C \simeq 115\,\mu\text{eV}$, and $E_{J1} = E_{J2} \simeq 78\,\mu\text{eV}$.

are rapidly ejected by thermal fluctuations. In this case, quasiparticles can jump in and out of the island before the CPT has time to latch into the free-running voltage state. In other words, the switching current measurement is bandwidth limited and is not able to see short-lived odd-parity events. While the average probability of being in the even state might be close to unity, quasiparticles may constantly be getting trapped and ejected at very rapid rates. In terms of the poisoning and ejection rates,

$$P_e = \frac{\Gamma_{oe}}{\Gamma_{eo} + \Gamma_{oe}}. \tag{16.23}$$

If the ejection rate Γ_{oe} is big compared with the poisoning rate Γ_{eo}, then P_e approaches one even though Γ_{eo} may be arbitrarily large itself. This is an insidious effect since it was previously common for many groups working in CPB qubits to assess their quasiparticle situation from what appeared to be clean 2*e* modulation characteristics. In fact, 2*e* modulation is observed in the presence of these fast quasiparticle dynamics when the measurement technique is slow in comparison. Since quasiparticles might have lifetimes far shorter than 1 μs, most available methods (dc and rf alike) can have problems with this.

In CPTs with deeper trap potentials, such as the type L devices we show here, the ejection rate can be slowed down significantly. Since the measurement shown in Figures 16.12 and 16.13c,d was performed with a ramp rate that was comparable to the quasiparticle ejection rate, it was possible to obtain a bimodal histogram of I_{sw}. In this case, it is easy to correlate the derived escape function with meaningful rates. The two slopes in Figure 16.13d are the even and odd state escape rates, $\gamma_{sw,e}$ and $\gamma_{sw,o}$, respectively. Thus, the bias current ramp is not infinitely fast, and the parity can flip from even to odd in the time it takes to ramp between the two current values corresponding to the odd and even state switching currents resulting in several switching events in the region between the peaks. These correspond to quasiparticles jumping into the CPT island during the bias ramp. Since the plateau that connects the even and odd switching rates is derived from the histogram counts between the even and odd peaks, it is a direct indication of the poisoning rate, Γ_{eo}. We can apply similar reasoning to the type H data in Figure 16.13a,b and notice that the escape rate for $n_g = 0.99$ is a little curvy, although the other escape rates shown look quite linear (on a semilogarithmic scale). While we do not develop a distinct plateau in this case, the deformation in the form of the escape rate is still an indication of very fast poisoning. This should not be a surprise since we expect the island to look trap-like at this gate voltage as we noted above. Thus, the lesson to be learned here is that despite appearances, the data shown in Figure 16.11 masks the fact that the type H device is poisoned.

16.4.1.3 Single Shot Measurement

In a single shot operation (Cottet et al., 2001), we pulse the current bias up from zero to some value I_p for a time τ_p. The probability of switching to the voltage state is given by

$$P_{sw}(n_g) = 1 - e^{-\gamma_{sw}(I_p, n_g)\tau}, \tag{16.24}$$

where $\gamma_{sw}(I_p, n_g)$ is the rate at which the CPT phase escapes to the free-running voltage state when instantaneously biased at I_p and n_g. If we are biased at n_g and wish to determine whether the polarization charge has shifted by δn_g, we need to figure out the likelihood of seeing a switching event that is actually due to the shift in switching probability versus just the probability of switching with no charge shift at all,

$$\Delta P_{sw}(n_g, \delta n_g) = e^{-\gamma_{sw}(I_p, n_g)\tau} - e^{-\gamma_{sw}(I_p, n_g + \delta n_g)\tau}. \tag{16.25}$$

If we want to measure this change in polarization charge in a single measurement, then we require that $\Delta P_{sw} = 1$. That is, if we pulse the bias current and see the CPT switch to the voltage state,



FIGURE 16.13 **(See color insert following page 20-14.)** (a,c) Switching current (I_{sw}) histograms and (b,d) derived switching/escape rates for a type H (barrier-like) and type L (trap-like) CPTs. For the type L device, the quasiparticle trapping behavior is evident in the bimodal I_{sw} distribution. In this case, the poisoning rate Γ_{eo} can be read directly from the derived escape rate in (d) as shown. Although the type H device is barrier-like for most n_g, it still looks like a trap near $n_g = 1$ (see Figure 16.7). This is apparent in the "curvy" structure of the escape curve for $n_g = 0.99$ as compared with the escape rates at other n_g in (b).

then the polarization charge has shifted by δn_g with certainty. This defines a minimum charge shift $\delta n_{g,ss}$ or voltage change $\delta V_{g,ss}$ (= $\delta n_{g,ss} e/C_g$) on the gate that can be detected with one measurement. If we want to detect a smaller change in gate voltage, then we would have to take multiple measurements until the uncertainty in the shift of $\langle I_{sw} \rangle$ is satisfactory. In many experiments, this is a completely reasonable approach. It is possible, however, to attempt to reduce the width of the switching current distribution by increasing the shunt capacitance across the CPT (increasing the effective mass of our imaginary phase particle) (Joyez, 1995).

In the end, pulsed single shot measurements have never been very popular. This may be because their chief use would have been in charge-based qubits, and other significant measurement schemes were shown to outperform it (Vion et al., 2002). However, it might still be a viable measurement method outside of superconducting quantum computing.

16.4.2 Zero-Biased rf Electrometry

The initial aim of the rf inductance measurements was to demonstrate a dissipationless (or near dissipationless) electrometer that could be used in charge-based quantum circuits such as the CPB, but the most useful application in recent years seems to have been to study the dynamics of quasiparticle tunneling.

Initial measurements of the Josephson (or "quantum") inductance of a CPT were performed by Sillanpää et al. (2004) and soon thereafter by Naaman and Aumentado (2006b). rf measurements of CPTs were also performed by Court and coworkers (Ferguson et al., 2006) as well, but these measurements focused on a modulation of the dissipation and were not strictly confined to the supercurrent branch.*

16.4.2.1 The rf Measurement Setup

Figure 16.14a shows a typical microwave circuit used in rf-CPT electrometry. In this scheme, the CPT is embedded in a tank circuit composed of the parasitic capacitance provided by the leads, the Josephson inductance of the CPT, and an extra surface mount inductor soldered to a printed circuit board near the chip to lower the tank resonance to the range of the microwave amplifier.†

Following the circuit path in Figure 16.14a, we reflect an incoming microwave signal (the *carrier*) off of the CPT resonator circuit and measure the amplitude and phase of the outgoing signal, that is, we measure the scattering parameter S_{11}. As shown

---

[*] It's important to note that measurement of the Josephson inductance (the second derivative of the ground state energy in phase) is conceptually linked to the "quantum capacitance" (the second derivative in charge). rf measurements of the capacitance have recently been shown to be an extremely useful measurement of charge-based qubits such as the CPB (Wallraff et al., 2004; Duty et al., 2005) and the transmon (Schuster, 2007).

[†] The word "parasitic" should be a tip-off to the reader that this scheme might be a little hit-or-miss and, indeed, it can be frustrating to target the operating frequency within 10% (this is the typical bandwidth for sub-1 GHz low-noise cryogenic amplifiers). While this setup is very similar to that used in typical rf-SET operation (Schoelkopf et al., 1998), it is not necessarily trivial to implement.



FIGURE 16.14 (a) Simplified rf-CPT measurement schematic. Incoming microwave power is directed toward CPT+ resonator through a directional coupler. The reflected wave is then amplified and measured at room temperature. In this schematic, several bandpass filters and attenuators have been omitted for simplicity. (b) Reflected power versus frequency at various gate voltages. (c) Reflected power modulation as a function of gate voltage for a fixed carrier frequency, $f_c = 515.2$ MHz. (Adapted from Naaman, O. and Aumentado, J., *Phys. Rev. B*, 73, 172504, 2006b.)

earlier, the gate-dependent Josephson inductance can be many 10s of nano-Henries and, since this inductance provides much of the total inductance available to the resonator, the frequency shift can be on the order of the bandwidth (typical Qs ~ 20–30). While a purely dissipationless circuit will reflect all of the signal ($|S_{11}|^2 = 1$) (Pozar, 2004), there are, in fact, a number of sources of dissipation, including the lossy traces on the pc board and leads on chip, the losses in the surface mount inductor and wire bonds, and, finally, the intrinsic CPT losses from any phase-diffusion resistance present. The end result is that there is a visible resonance dip in the reflected power amplitude $|S_{11}|^2$ (Figure 16.14b,c). For our purposes then, the frequency shift due to the modulation of the CPT Josephson inductance can be inferred from the reflected amplitude modulation.[*] That is, since the CPT inductance is a function of island charge, the final output microwave power amplitude and phase modulate with the gate-induced polarization charge.

Like the rf-SET, one can characterize the ultimate noise performance of this device as an electrometer in terms of an effective charge resolution in a 1 Hz bandwidth. In the rf measurement of the CPT inductance, the best number that has been reported is $\delta Q \sim 50\mu e/\sqrt{\text{Hz}}$ (Naaman and Aumentado, 2006b). That is, if we integrate the reflected power at the end of our measurement chain for 1 s, we can resolve a change in polarization charge at the gate electrode C_gV_g of 5.2×10^{-5} electrons. If we compare this with the best rf-SSET numbers $\delta Q < 5\mu e/\sqrt{\text{Hz}}$ (Brenning et al., 2006), the rf-CPT is more than 100 times slower at resolving the polarization charge. At first blush, this seems to put the rf-CPT at a disadvantage, but the rf-SSET charge resolution comes at the expense of using a relatively complex charge transport cycle that involves *both* quasiparticles and Cooper pairs. The back-acting voltage fluctuations of this cycle presented at the device they are measuring are equally nontrivial and have even been used to *cool* an electromechanical system that it was intended to measure (Naik et al., 2006). While some would consider this a feature of the rf-SSET, it seems to get away from the notion of simply wanting to use the device as a noninvasive electrometer. In fact, quasiparticle poisoning the rf-CPT has been used as a method to measure the effect of nearby SSETs, demonstrating that the latter emits nontrivial microwave power into its environment when voltage-biased (as they would be when operated as electrometers) (Naaman and Aumentado, 2007).

16.4.2.2 Operation Beyond 1 GHz

Although all of the published CPT experiments were operated with carrier frequencies below 1 GHz, this is not a fundamental requirement. In fact, this limitation seems to be determined by parasitic self-resonances in the surface-mount inductors, often used in these experiments. In principle, the operating frequency can be raised to many gigahertz using coplanar resonator techniques. The advantage of moving to higher frequencies is that wideband, low-noise HEMT amplifiers are now readily available in the 4–8 GHz range and all of the associated passive components (directional couplers and isolators) are smaller and much more common (less expensive).

---

[*] In principle, this information is also accessible through the phase of the outgoing signal and can be measured using an IQ mixer. Since loss was present in many of these experiments and the frequency shift was usually very obvious, measurement of the amplitude modulation has ended up being the simplest method.

16.4.2.3 Quasiparticle Poisoning in the rf-CPT

As in the switching current measurement, quasiparticle poisoning also has a dramatic effect on rf measurement. Unlike the switching current measurement, a qualitative understanding of the measurement response is very straightforward. Since the inductance of the CPT can switch instantaneously between two different parity states when the gate is biased into a trap-like regime, the reflected power also switches between two different amplitudes. This kind of response is more commonly known as "telegraph noise." A typical example is shown in Figure 16.15a for a type L device. We note that this is the same bimodal behavior that we observe in the switching current measurements except that we can sit at zero bias and watch quasiparticles jumping in and out of the CPT island. In Figure 16.15c, we histogram the telegraph time traces as a function of gate voltage, we get data that, unsurprisingly, are very similar to our bimodal switching current histograms in Figure 16.12.

The rates Γ_{eo} and Γ_{oe} can be derived from an analysis of these time-domain traces but requires a careful characterization of the system measurement bandwidth (Naaman and Aumentado, 2006a). Although it is possible to extract the poisoning rate Γ_{eo} from a switching current measurement, it is far more difficult to pull out an ejection rate. This is a direct consequence of the time-ordered nature of the current bias ramp. In contrast, the rf measurement is not burdened by this kind of time ordering in any obvious way, and both the poisoning and ejection rates are available.

The availability of the poisoning and ejection rates has provided further verification of the model presented in Aumentado et al. (2004), while confirming that nonequilibrium quasiparticles are generated in the leads at a constant rate below ~250 mK. In addition, the ejection rate Γ_{oe} has been used to validate the notion that biased SSETs emit nontrivial levels of microwave power into their environment (Naaman and Aumentado, 2007). This is important as for a long time rf-SSET electrometry had been considered a viable method of measuring CPB qubit charge states.



FIGURE 16.15 (a) Reflected power (linear units) of type L CPT at $n_g = 1$ in the time domain. The even (upper) and odd (lower) state levels are evident in telegraph-noise time traces. (b) Histogram of the full time trace. (c) Histograms versus gate voltage. (Adapted from Naaman, O. and Aumentado, J., *Phys. Rev. B*, 73, 172504, 2006b.)

16.4.2.4 Relation to the Cooper-Pair Box

Earlier, we alluded to the fact that the CPT was related to the CPB. In fact, when the CPT is biased at zero, it is identical to the CPB if the biasing circuit series impedance is small at the relevant parallel-junction plasma frequency. Since the problem of quasiparticle poisoning is also important to charge-based qubits such as the CPB (Nakamura et al., 1999; Wallraff et al., 2004), quantronium (Vion et al., 2002), and transmon (Koch et al., 2007), the fact that we can study it with relatively high instantaneous bandwidth in the CPT motivated several experiments aimed at studying the dynamics of the poisoning process in detail (Aumentado et al., 2004; Ferguson et al., 2006; Naaman and Aumentado, 2006b; Court et al., 2008b). Ultimately, it was realized that quantum capacitance measurements could achieve the same objective measuring CPBs directly and have yielded the most detailed quasiparticle poisoning studies to date (Lutchyn and Glazman, 2007; Shaw et al., 2008).

16.5 Present Status and Future Directions

The CPT is the simplest device in which dc transport characteristics can be correlated to the duality between charge and phase. Although the most prominent recent CPT experiments have focused on the problem of nonequilibrium quasiparticle poisoning, the CPT is also a promising general-purpose low-temperature, low-backaction electrometer. Since the most reliable techniques for fabricating these devices involve aluminum fabrication with gap, Josephson, and Coulomb blockade energies in the ~100–300 μeV range, operation is restricted to dilution refrigeration, so that the systems that one attaches it to must also be cold. While this seems restrictive at present, there are already several mesoscopic condensed matter systems that might benefit from minimally invasive fast electrometry.

Acknowledgment

The author wishes to acknowledge several important conceptual discussions with Ofer Naaman, Michel H. Devoret, and John M. Martinis.

References

Amar, A., Song, D., Lobb, C. J., and Wellstood, F. C. (1994). 2e and e periodic pair currents in superconducting coulomb-blockade electrometers. *Physical Review Letters*, 72(20):3234.

Ambegaokar, V. and Baratoff, A. (1963). Tunneling between superconductors. *Physical Review Letters*, 10(11):486.

Aumentado, J., Keller, M. W., Martinis, J. M., and Devoret, M. H. (2004). Nonequilibrium quasiparticles and 2e periodicity in single-cooper-pair transistors. *Physical Review Letters*, 92(6):066802.

Brenning, H., Kafanov, S., Duty, T., Kubatkin, S., and Delsing, P. (2006). An ultrasensitive radio-frequency single-electron transistor working up to 4.2 k. *Journal of Applied Physics*, 100:114321.

Clarke, J. and Braginski, A. I. (eds.). (2004). *The SQUID Handbook: Volume 1: Fundamentals and Technology of SQUIDs and SQUID Systems*. Wiley-VCH, Weinheim, Germany.

Cord, B., Dames, C., and Bergren, K. K. (2006). Robust shadow-mask evaporation via lithographically defined undercut. *Journal of Vacuum Science and Technology B*, 24(6):3139.

Cottet, A., Steinbach, A., Joyez, P., Vion, D., and Pothier, H. (2001). *Macroscopic Quantum Coherence and Quantum Computing*, p. 111. Kluwer Academic, Plenum Publishers, New York.

Court, N. A., Ferguson, A. J., and Clark, R. G. (2008a). Energy gap measurement of nanostructured aluminium thin films for single cooper-pair devices. *Superconductor Science and Technology*, 21(1):015013.

Court, N. A., Ferguson, A. J., Lutchyn, R., and Clark, R. G. (2008b). Quantitative study of quasiparticle traps using the single-cooper-pair transistor. *Physical Review B*, 77(10):100501.

Devoret, M. H. and Grabert, H. (1992). Introduction to single-charge tunneling. *Single Charge Tunneling: Coulomb Blockade Phenomena in Nanostructures (NATO Science Series: B)*, p. 1. Springer, New York.

Devoret, M. H., Esteve, D., Martinis, J. M., Cleland, A., and Clarke, J. (1987). Resonant activation of a brownian particle out of a potential well: Microwave-enhanced escape from the zero-voltage state of a Josephson junction. *Physical Review B*, 36(1):58.

Dolan, G. (1977). Offset masks for lift-off photoprocessing. *Applied Physics Letters*, 31(5):333.

Dolata, R., Scherer, H., Zorin, A., and Niemeyer, J. (2002). Single electron transistors with high-quality superconducting niobium islands. *Applied Physics Letters*, 80(15):2776.

Dolata, R., Scherer, H., Zorin, A., and Niemeyer, J. (2005). Single-charge devices with ultrasmall nb/alo/nb trilayer Josephson junctions. *Journal of Applied Physics*, 97:054501.

Duty, T., Johansson, G., Bladh, K., Gunnarsson, D., Wilson, C., and Delsing, P. (2005). Observation of quantum capacitance in the cooper-pair transistor. *Physical Review Letters*, 95(20):206807.

Ferguson, A. J., Court, N. A., Hudson, F. E., and Clark, R. G. (2006). Microsecond resolution of quasiparticle tunneling in the single-cooper-pair transistor. *Physical Review Letters*, 97(10):106603.

Flees, D., Han, S., and Lukens, J. (1997). Interband transitions and band gap measurements in bloch transistors. *Physical Review Letters*, 78(25):4817.

Fulton, T. and Dunkleberger, L. (1974). Lifetime of the zero-voltage state in Josephson tunnel junctions. *Physical Review B*, 9(11):4760.

Gunnarsson, D., Duty, T., Bladh, K., and Delsing, P. (2004). Tunability of a 2e periodic single cooper pair box. *Physical Review B*, 70(22):224523.

Josephson, B. (1962). Possible new effects in superconductive tunnelling. *Physics Letters*, 1(7):251.

Joyez, P. (1995). Le Transistor a une Paire de Cooper: un Systeme Quantique Macro-scopique. PhD thesis, L'Universite Paris, Paris, France.

Joyez, P., Lafarge, P., Filipe, A., Esteve, D., and Devoret, M. H. (1994). Observation of parity-induced suppression of Josephson tunneling in the superconducting single…. *Physical Review Letters*, 72(15):2458.

Kautz, R. and Martinis, J. (1990). Noise-affected iv curves in small hysteretic Josephson junctions. *Physical Review B*, 42(16):9903.

Koch, J., Yu, T. M., Gambetta, J. M., Houck, A. A., Schuster, D. I., Majer, J., Blais, A., Devoret, M. H., Girvin, S. M., and Schoelkopf, R. J. (2007). Charge insensitive qubit design from optimizing the cooper-pair box. *Physical Review A*, 74(4):042319.

Lutchyn, R. M. and Glazman, L. I. (2007). Kinetics of quasiparticle trapping in a cooper-pair box. *Physical Review B*, 75(18):184520.

Mazin, B. A. (2004). Microwave kinetic inductance detectors. PhD thesis, California Institute of Technology, Pasadena, CA.

Naaman, O. and Aumentado, J. (2006a). Poisson transition rates from time-domain measurements with a finite bandwidth. *Physical Review Letters*, 96(10):100201.

Naaman, O. and Aumentado, J. (2006b). Time-domain measurements of quasiparticle tunneling rates in a single-cooper-pair transistor. *Physical Review B*, 73(17):172504.

Naaman, O. and Aumentado, J. (2007). Narrow-band microwave radiation from a biased single-cooper-pair transistor. *Physical Review Letters*, 98(22):227001.

Naik, A., Buu, O., LaHaye, M. D., Armour, A. D., Clerk, A. A., Blencowe, M. P., and Schwab, K. C. (2006). Cooling a nanomechanical resonator with quantum back-action. *Nature*, 443:193.

Nakamura, Y., Pashkin, Y. A., and Tsai, J. S. (1999). Coherent control of macroscopic quantum states in a single-cooper-pair box. *Nature*, 398:786.

Palmer, B. S., Sanchez, C. A., Naik, A., Manheimer, M. A., Schneiderman, J. F., Echternach, P. M., and Wellstood, F. C. (2007). Steady-state thermodynamics of nonequilibrium quasiparticles in a cooper-pair box. *Physical Review B*, 76(5):054501.

Pozar, D. M. (2004). *Microwave Engineering*, 3rd edn. Wiley, New York.

Savin, A. M., Meschke, M., Pekola, J. P., Pashkin, Y. A., Li, T. F., Im, H., and Tsai, J. S. (2007). Parity effect in Al and Nb single electron transistors in a tunable environment. *Applied Physics Letters*, 91:063512.

Schoelkopf, R. J., Wahlgren, P., Kozhevnikov, A. A., Delsing, P., and Prober, D. E. (1998). The radio-frequency single-electron transistor (rf-set): A fast and ultrasensitive electrometer. *Science*, 280:1238.

Schuster, D. I. (2007). Circuit quantum electrodynamics. PhD thesis, Yale University, New Haven, CT.

Shaw, M. D., Lutchyn, R. M., Delsing, P., and Echternach, P. M. (2008). Kinetics of nonequilibrium quasiparticle tunneling in superconducting charge qubits. *Physical Review B*, 78(2):024503.

Sillanpää, M., Roschier, L., and Hakonen, P. (2004). Inductive single-electron transistor. *Physical Review Letters*, 93(6):066805.

Tinkham, M. (2004). *Introduction to Superconductivity*, 2nd edn. Dover, New York.

Tinkham, M., Hergenrother, J. M., and Lu, J. G. (1995). Temperature dependence of even-odd electron-number effects in the single-electron transistor. *Physical Review B*, 51(18):12649.

Townsend, P., Taylor, R., and Gregory, S. (1972). Superconducting behavior of thin-films and small particles of aluminum. *Physical Review B*, 5(1):54.

Tuominen, M. T., Hergenrother, J. M., Tighe, T. S., and Tinkham, M. (1992). Experimental evidence for parity-based 2e periodicity in a superconducting single-electron tunneling transistor. *Physical Review Letters*, 69(13):1997.

Tuominen, M. T., Hergenrother, J. M., Tighe, T. S., and Tinkham, M. (1993). Even-odd electron number effects in a small superconducting island: Magnetic-field dependence. *Physical Review B*, 47(17):11599.

Vion, D., Aassime, A., Cottet, A., Joyez, P., Pothier, H., Urbina, C., Esteve, D., and Devoret, M. H. (2002). Manipulating the quantum state of an electrical circuit. *Science*, 296:886.

Wallraff, A., Schuster, D. I., Blais, A., Frunzio, L., Huang, R.-S., Majer, J., Kumar, S., Girvin, S. M., and Schoelkopf, R. J. (2004). Strong coupling of a single photon to a superconducting qubit using circuit quantum electrodynamics. *Nature*, 431:162.

Watanabe, M., Nakamura, Y., and Tsai, J. (2004). Circuit with small-capacitance high-quality Nb Josephson junctions. *Applied Physics Letters*, 84(3):410.

Yamamoto, T., Nakamura, Y., Pashkin, Y. A., Astafiev, O., and Tsai, J. S. (2006). Parity effect in superconducting aluminum single electron transistors with spatial gap profile controlled by film thickness. *Applied Physics Letters*, 88(21):212509.

III

Nanolithography

17 **Multispacer Patterning: A Technology for the Nano Era** *Gianfranco Cerofolini, Elisabetta Romano, and Paolo Amato* **17**-1
Introduction • The Crossbar Process • Nonlithographic Preparation of Nanowires • Multispacer Patterning Techniques • Influence of Technology on Architecture • Fractal Nanotechnology • Appendixes • Abstract Technology • Concrete Technology • References

18 **Patterning and Ordering with Nanoimprint Lithography** *Zhijun Hu and Alain M. Jonas*.......... **18**-1
Introduction • Nanoimprint Lithography • Nanoshaping Functional Materials by Nanoimprint Lithography • Controlling Ordering and Assembly Processes by Nanoimprint Lithography • Conclusions and Perspectives • Acknowledgments • References

19 **Nanoelectronics Lithography** *Stephen Knight, Vivek M. Prabhu, John H. Burnett, James Alexander Liddle, Christopher L. Soles, and Alain C. Diebold* **19**-1
Introduction • Photoresist Technology • Deep Ultraviolet Lithography • Electron-Beam Lithography • Nanoimprint Lithography • Metrology for Nanolithography • Abbreviations • References

20 **Extreme Ultraviolet Lithography** *Obert R. Wood II* **20**-1
Introduction • Historical Background • Current State of the Art • EUVL Infrastructure Status • Future Perspectives • Abbreviations • References

17

Multispacer Patterning: A Technology for the Nano Era

17.1 Introduction 17-1
17.2 The Crossbar Process 17-2
17.3 Nonlithographic Preparation of Nanowires 17-3
Imprint Lithography • Spacer Patterning Technique
17.4 Multispacer Patterning Techniques 17-5
Additive Route—S^nPT_+ • Multiplicative Route—$S^nPT_\times$ • Three-Terminal Molecules
17.5 Influence of Technology on Architecture 17-10
Addressing • Comparing Crossbars Prepared with Additive or Multiplicative Routes • Applications—Not Only Nanoelectronics
17.6 Fractal Nanotechnology 17-12
Fractals in Nature • Producing Nanoscale Fractals via $S^nPT_\times$
Appendixes 17-14
17.A Abstract Technology 17-14
Bodies and Surfaces • Conformal Deposition and Isotropic Etching • Directional Processes • Selective Processes
17.B Concrete Technology 17-18
References 17-19

Gianfranco Cerofolini
University of Milano-Bicocca

Elisabetta Romano
University of Milano-Bicocca

Paolo Amato
Numonyx and University of Milano-Bicacca

17.1 Introduction

The evolution of integrated circuits (ICs) has been dominated by the idea of scaling down its basic constituent—the metal-oxide-semiconductor (MOS) field-effect transistor (FET). In turn, this has required the development of suitable lithographic techniques for its definition on smaller and smaller length scales. There are several generations of lithographic techniques, usually classified according to the technology required for the definition of the wanted features on photo- or electro-sensitive materials (resists): standard photolithography (436 nm, Hg *g*-line; refractive optics), deep ultraviolet (DUV) photolithography (193 nm, ArF excimer laser; refractive optics), immersion DUV photolithography (refractive optics), extreme ultraviolet (EUV) photolithography (13.5 nm, plasma-light source; reflective optics), and electron beam (EB) lithography (electron wavelength controlled by the energy, typically in the interval 10^{-3} to 10^{-2} nm).

The industrial system has succeeded in that, but the cost of ownership has in the meanwhile dramatically increased, because of either the required investment per machine,

$$\text{DUV} \ll \text{immersion DUV} \ll \text{EUV},$$

or the throughput,

$$\text{EB} \ll \text{DUV}.$$

It is just the dramatic cost escalation that is necessary for the reduction of the feature size that casts doubts on the possibility of continuing the current increase of IC density beyond the next 10 years.

Entirely new revolutionary technological device platforms, overcoming the complementary MOS (CMOS) paradigm, must likely be developed to enable the economical feasibility and scalability of electronic circuits to the tera scale intergation (TSI).

On another side, the preparation of ICs with bit density as high as 10^{11} cm^{-2} seems now possible, with modest changes in the current production process and marginal investment for the fabrication facility, within a different paradigm. The new paradigm is based on a structure, where a crossbar embodies in each of its cross-points a functional material able to perform by itself the functions of a memory cell [1].

The crossbar is indeed producible (via nonconventional lithography or even without any lithographic method) with geometry on the 10 nm length scale. Although the crossbar is not yet a circuit, it may nonetheless become a circuit if each cross-point contains a memory cell and each of them can be addressed, written, and read—that requires an external circuitry for addressing, power supply, and sensing. The best architecture for satisfying those functions is manifestly achieved embedding the crossbar in a CMOS circuitry [2]:

$$\begin{aligned}\text{TSI IC} = {} & \text{submicro CMOS IC} \cup \\ & \text{nano crossbar} \cup \\ & \text{nanoscopic cells.}\end{aligned}$$

This architecture reduces the problem of preparing TSI ICs to that of producing nanoscopic memory cells and inserting them into the cross-points of a crossbar structure. It would be a mere declaration of will were it not for the fact that molecules by themselves able to behave as memory cells have been not only designed [3–5] and synthesized [6,7], but also inserted in hybrid devices [8–12]. This fact opens immediately the possibility of a *hybrid route* to TSI ICs:

$$\begin{aligned}\text{Hybrid TSI IC} = {} & \text{submicro CMOS IC} \cup \\ & \text{nano crossbar} \cup \\ & \text{grafted functional molecules.}\end{aligned} \tag{17.1}$$

In this approach, the transport properties of programmable molecules are exploited for the preparation of externally accessible circuits. Because of this, it is usually referred to as molecular electronics.

The hypothesized TSI IC has thus a hybrid structure, formed by a nanometer-sized kernel (the functionalized crossbar), linked to a conventional submicrometer-sized CMOS control circuitry (producible with currently achievable technologies) and hosting molecular devices (whose production is left to chemistry).

17.2 The Crossbar Process

That self-assembled monolayers on preformed gold contacts may behave as nanoscale memory elements was demonstrated for thiol-terminated π-conjugated molecules containing amino or nitro groups [9]. The first demonstration of nonvolatile molecular crossbar memories employed self-assembled monolayers of thiol-terminated rotaxanes as reprogrammable cells [10]. The molecules were embedded between the metal layers forming the crossbar via a process that can be summarized as follows:

XB^1, deposition and definition of the first-level ("bottom") wire array

XB^2, deposition of the active reconfigurable molecules, working also as vertical spacer separating lower and upper arrays

XB^3, deposition and definition of the second-level ("top") wire array

Figure 17.1 sketches the XB process.

Although potentially revolutionary, the XB approach, with double metal strips, has been found to have serious limits:

- The organic active element is incompatible with high-temperature processing, so that the top layer must be deposited in XB^3 at room or slightly higher temperature. This need implies a preparation based on physical vapor deposition, where the metallic electrode results from the condensation of metal *atoms* on the outer surface of the deposited organic films. This process, however, poses severe problems of compatibility, because isolated metal atoms, quite irrespective of their chemical nature, are mobile and decorate the molecule, rather than being held as a film at its outer extremity [13–15].



FIGURE 17.1 The first proposed crossbar-architecture fabrication steps. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

- A safe determination of the conductance state of bistable molecules requires the application of a voltage V appreciably larger than k_BT/e (with k_B being the Boltzmann constant, T the absolute temperature, and $-e$ the electron charge), say $V = 0.1\text{–}0.2\,\mathrm{V}$. Applied to molecules with typical length around 3 nm, this potential sustains an electric field, of the order of $5 \times 10^5\ \mathrm{V\ cm^{-1}}$, sufficiently high to produce metal electromigration along the molecules [16].
- The energy barrier for metal-to-molecule electron transfer is controlled by the polarity of the contact, in turn increasing with the electronegativity difference along the bond linking metal and molecule [17]. The use of thiol terminations for the molecule, as implicit in the XB approach, is expected to be responsible for high-energy barriers because of the relatively high electronegativity of sulfur.

Even though the first difficulty can in principle be removed by slight sophistication of the process (for instance, as follows: spin-coating the organic monolayer with a dispersion of metal nanoparticles in a volatile solvent, evaporating the solvent, forming a relatively compact layer via coalescence of the metal particles, and compacting the resulting film by means of an additional amount of PVD metal), other difficulties are more fundamental in nature and require different materials.

A solution to the electromigration problem can be achieved preparing the bottom electrodes in the form of silicon wires



FIGURE 17.2 The basic idea of XB^*: preparing the crossbar before its functionalization.

(as done in [12]), and the top electrodes in the form conducting π-conjugated polymers (as suggested in [18]):

XB_+^1, deposition and definition of the bottom array of poly-silicon wires
XB_+^2, deposition of the active (reconfigurable) element, working also as vertical spacer separating lower and upper arrays
XB_+^3, deposition and definition of the top array of conducting π-conjugated polymers

The use of poly-silicon as material for the top array too seems impossible because it is prepared almost uniquely via chemical vapor deposition at incompatible temperatures with organic molecules.* The only way to overcome this difficulty consists thus in a process, $XB_\star$, where the two poly-silicon arrays defining the crossbar matrix are prepared *before* the insertion of the organic element [11]. Preserving a constant separation on the nanometer length scale is possible only via the growth of a sacrificial thin film on the first array before the deposition of the second one [21]:

$XB_\star^1$, preparation of a bottom array of poly-silicon wires
$XB_\star^2$, deposition of a sacrificial layer as vertical spacer separating lower and upper arrays
$XB_\star^3$, preparation of a top array of poly-silicon wires crossing the first-floor array
$XB_\star^4$, selective chemical etching of the spacer
$XB_\star^5$, insertion of the reprogrammable molecules in a way to link upper and lower wires in each cross-point

The basic idea of process $XB_\star$, of inserting the functional molecules after the preparation of the crossbar, is sketched in Figure 17.2.

Of the three considered processes (XB, XB_+, and $XB_\star$), the one based on double-silicon strips is certainly the most conservative one and is thus expected to be of easiest integration in IC processing. For this reason (and for the possibility of using three-terminal molecules, see Section 17.4.3), our attention will be concentrated on the $XB_\star$ route.

17.3 Nonlithographic Preparation of Nanowires

The preparation of a crossbar requires the use of simple geometries—essentially arrays of dielectrically insulated conductive wires. What is especially interesting is that wire arrays with pitch on the nanometer length scale are producible via nonlithographic techniques (NLTs). Not only is this preparation possible, but also the wire linear density already achieved with the NLTs described in the following is smaller than the one achievable via the most advanced EUV or EB lithographies. Such NLTs exploit the following features:

(V), the "vertical" control of film thickness, possible down to the subnanometer length scale provided that the film is sufficiently homogeneous.
(V-to-H), the transformation of films with "vertical" thickness t into patterns with "horizontal" width w:

$$t \xrightarrow{\text{NLT}} w.$$

These techniques are *imprint lithography* and two variants of the *multispacer patterning technique*.

17.3.1 Imprint Lithography

Imprint lithography (IL) is a contact lithography where properties (V) and (V-to-H) are exploited for the preparation of the mask. The process is essentially based on the sequential alternate deposition of two films, A and B, characterized by the existence of a preferential etching for one (say A) of them. After cutting at 90°, polishing, and controlled etching of A, one eventually gets a mask formed by nanometer-sized trenches running parallel to one another at a distance fixed by the thickness of B [22,23]. For instance, a contact mask for imprint lithography with pitch of 16 nm was prepared by growing on a substrate a quantum well via molecular beam epitaxy, cutting the sample perpendicularly to the surface, polishing the newly exposed surface, and etching selectively the different strata of the well [23]. The potentials of the preparation method based on superlattice nanowire pattern transfer (SNAP) are reviewed in Ref. [24].

---

* It is instead possible if the spacer is an inorganic film. This case, although not for molecular electronics, is interesting for memories based on phase-change materials [19] or mimicking the memristor [20].



FIGURE 17.3 Preparation of mold for imprint lithography (left) and its use as contact mask (right); the multilayer has been supposed to be produced with cycles of sequential depositions of silicon and SiO$_2$. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

Actually a number of variants for transferring the pattern to the surface have been developed: molding, embossing, and stamping are the ones most frequently considered [25]. In one of them (molding), after filling the trenches with a suitable polymer, the mask is used as a stamp, pressing it onto the surface; if the polymer has a higher affinity for the surface than for the mask, the pattern is transferred to the surface when the mask is eventually removed [25]. The transfer of the polymer to the surface is possible without loss of geometry only if the trench is sufficiently shallow; this implies that the polymer must sustain a subsequent process where it is used as mask for the definition (via directional etching) of the underlying structure with a high aspect ratio. Another method (embossing), sketched in the right-hand side of Figure 17.3, involves the pressure-induced transfer of the pattern from the mask to a plastic film and its subsequent polymerization.

Imprint lithography is generally believed to have potential advantages over conventional lithography because it can be carried out in ordinary laboratory with no special equipments [26]. This situation is expected to make it easy to run along the learning curve to a mature technology. However, very little is known about the overall yield, eventually resulting in production cost, of this process (preparation of mask and stamp, imprint, etching) when the geometries are on the length scale of tens of nanometers.

Imprint lithography has been the matter of extended investigation (see for instance, Refs. [25,26]) and will not be discussed here. Rather, this chapter is devoted to describe the multispacer patterning technique and to compare its two variants.

17.3.2 Spacer Patterning Technique

The multispacer patterning technique (S^{n}PT) is essentially based on the repetition of the spacer patterning technique (SPT). In turn, the SPT is an age-old technology originally developed for the dielectric insulation of metal electrodes contacting source and drain from the gate of metal-oxide-semiconductor (MOS) transistors.

The SPT involves the following steps:

SPT^0, the *lithographic definition* of a seed with sharp edge and high aspect ratio
SPT^1, the *conformal deposition* on this feature of a film of uniform thickness
SPT^2, the *directional etching* of the film until the original seed surface is exposed

If the process is stopped at this stage, it results in the formation of sidewalls of the original seed; otherwise, if

SPT^3, the original seed is removed via a *selective etching*

what remains is constituted only by the walls of the seed edges. Figure 17.4 sketches the various stages of SPT.

This technique has been demonstrated to be suitable for the preparation of features with minimum size of 7 nm [27,28] and has already achieved a high level of maturity, succeeding in the definition, with yield very close to unity, of nanoscopic bars with high aspect ratio.

The SPT may be sophisticated via the deposition of a multilayered film; Figure 17.5 shows the sidewalls resulting from the deposition of a multilayer and compares it with what is really done in the original application of SPT—the insulation of the source and drain electrodes from the gate [29].



FIGURE 17.4 Up: The spacer patterning technique: SPT^0, definition of a pattern with sharp edges; SPT^1, conformal deposition of a uniform film; SPT^2, directional etching of the deposited film up to the appearance of the original seed; and SPT^3, selective etching of the original feature. Down: Cross-section of a wire produced via SPT. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)



FIGURE 17.5 The original application of the SPT in microelectronics—dielectric insulation of the gate from source and drain electrodes. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

17.4 Multispacer Patterning Techniques

Two S^nPT routes have been considered: the additive (S^nPT_+) and multiplicative ($S^nPT_\times$) routes.

The S^nPT_+ is recent and was proposed having in mind the preparation of crossbars for molecular electronics [30–32]. The $S^nPT_\times$ is instead much older: the first demonstrators were developed for the generation of gratings with sub-lithographic period [33]; recently, however, this technique has been used for the preparation of wire arrays in biochips also [28]. Since no detailed comparison of the limits and relative advantages of these techniques is known, the following part will try to provide an understanding about them on the basis of fundamental considerations.

17.4.1 Additive Route—S^nPT_+

The S^nPT_+ is substantially based on n STP repetitions where *the original seed is not removed and each free wall of newly grown bars is used as a seed for the subsequent STP*. Each SPT_+ cycle starts from an assigned seed and proceeds with the following steps:

$S^nPT^1_+$, conformal deposition of a conductive material
$S^nPT^2_+$, directional etching of this material up to the exposure of the original seed
$S^nPT^3_+$, conformal deposition of an insulating material
$S^nPT^4_+$, directional etching of this material up to the exposure of the original seed

The basic idea of the S^nPT_+ is shown in Figure 17.6: the upper part sketches the process; the lower part shows instead how poly-silicon arrays separated by SiO_2 dielectrics with sub-lithographic pitch (35 nm) can indeed be produced [30–32].



FIGURE 17.6 Up: the additive multispacer patterning technique. Down an example of S^3PT_+ multispacer (with pitch of 35 nm and formed by a double layer poly-Si|SiO_2) resulting after three repetitions of the SPT_+. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

The sketch in Figure 17.6 shows a process in which lines are additively generated onto a progressively growing seed, preserving the original lithographic feature along the repetitions of the unit process. The unit process is based on two conformal depositions of uniform layers (poly-silicon and SiO_2) each followed by a directional etching.

Figure 17.7 shows, however, that a similar structure could be obtained by a cycle formed by

$S^nPT'_+$, conformal deposition of a bilayer film (formed by an insulating layer deposited before the conductive one—the order of deposition is fundamental)
$S^nPT''_+$, directional etching of this film up to the exposure of the original seed

Consider an array with pitch P of lithographic seeds, each with width W (and thus separated from one another by a distance $P-W$). Denote with the same symbols in lower case, p and w, the corresponding sub-lithographic quantities. Starting from the said array of lithographic seeds, after n repetitions of SPT_+ any seed is surrounded by $2n$ lines (an example with $n = 4$ is shown in Figure 17.8), so that the corresponding effective linear density K_n of spacer bars is given by



FIGURE 17.7 A variant of the additive multispacer patterning technique able to reduce the number of directional etching by a factor of 2 via sequential deposition of a bilayered film. Two possibilities are considered, consisting in the deposition first of either poly-silicon and then of SiO_2 (left), or the same layers in reverse order (right). (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)



FIGURE 17.8 An example of S^4PT_+, showing the construction of four silicon bars per side of the seed. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

$$K_n = \frac{2n}{P}.$$

The example of Figure 17.8 shows also that the process can be tuned to preserve the constancy with n of wire width w_n, $w_n = w$, and pitch p_n, $p_n = p$. On the contrary, the spacer heights s_n decrease almost linearly with n,

$$s_n \simeq s_0 - \tau n \tag{17.2}$$

(with τ the spacer height loss per SPT cycle), at least for n lower than a characteristic value $n^{\max}$.

This unavoidable decrease is ultimately due to the fact that the conformal coverage of a feature with high aspect ratio results necessarily in a rounding off of the edge shape with curvature radius equal the film thickness and that the subsequent directional etching produces a nonplanar surface. Figure 17.9 explains the reasons for the shape of the resulting bars: even assuming a perfect directional attack, the resulting spacer is not flat and there is a loss of height τ not smaller than t: $\tau \geq t$.

Figure 17.6 shows that the process can actually be controlled to have τ coinciding, within error, with its minimum theoretical value, $\tau = 1.0t$. Figure 17.8 shows however that τ depends on the process, and this can be tuned to have $\tau = 3.2t$.

Although the loss of height may seem a disadvantage, in Section 17.5.1 it will be shown how the controlled decrease of s_n with n may be usefully exploited.

Assuming the validity of Equation 17.2 until s_n vanishes, the maximum number $n^{\max}$ of SPT_+ repetitions is given by $n^{\max} = s_0/\tau$; after $n^{\max}$ SPT_+ repetitions, the seed is lost and the process cannot continue further. In view of the availability of techniques for the production of deep trenches with very high aspect ratios, in this analysis s_0 (and hence $n^{\max}$) may be regarded as almost a free parameter.

The optimum distance allowing the complete filling of the void regions separating the original lithographic seeds is therefore given by $P - W = 2n^{\max}p$. Hence, the maximum number of cross-points that can be arranged in any square of side P is given



FIGURE 17.9 Shape of a sidewall resulting after ideal conformal deposition and directional etching (top; five sketches) and an image of how it results in practice (bottom; magnification of the spacers shown in Fig. 6). (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

by $(2n^{\max})^2$, and the maximum effective cross-point density $\delta_+^{\max}$ achievable with the S^nPT_+ is given by

$$\delta_+^{\max} = \left(\frac{2n^{\max}}{P}\right)^2$$

$$= \frac{1}{p^2}\left(\frac{1}{1+W/2n^{\max}p}\right)^2. \tag{17.3}$$

Equation 17.3 shows that $\delta_+^{\max}$ depends on the lithography (through W) and on the sub-lithographic technique S^nPT_+ (through $n^{\max}$ and p).

Just to give an idea of the maximum obtainable density, Figure 17.6 shows that $p = 35\,\text{nm}$ has already been achieved and $n^{\max} \simeq 10$ is at the reach of the S^nPT_+; for $W = 0.1\,\mu\text{m}$ (characteristic value for IC high volume production) and $p = 30\,\text{nm}$, Equation 17.3 gives $\delta_+^{\max} \simeq 8\times10^{10}\ \text{cm}^{-2}$. The comparison of this prediction with the lithographically achievable cross-point density (currently of about $2 \times 10^9\ \text{cm}^{-2}$), shows that S^nPT_+ allows the cross-point density to be magnified by a factor of about 40. This is however achieved only with the construction of 10 consecutive spacers per (bottom and top) layer. The spacer technology is a mature technology with yields close to unity also when employed in more complex geometries than single lines. The increase of processing cost implied by its repeated application in IC processing has been discussed in Ref. [34]. Although this increase is moderate, the integration of so many SPT_+ cycles may, however, be not trivial and passes through the development of dedicated cluster tools.

It is however noted that the basic idea sketched in Figure 17.7 can be extended to remove this difficulty at least partially: the conformal deposition of a slab with n poly-silicon|insulator bilayers (the insulator being SiO_2, Al_2O_3,…) followed by its directional etching would indeed result in the formation of $2n$ dielectrically insulated poly-silicon wires. Figure 17.10 sketches the process.

The figure however shows that this dramatic simplification of the process can be done only for the deposition of the bottom array; its use for the top array would result in a distance of the top wire from the lower one varying with the order of poly-silicon layer.



FIGURE 17.10 Structure resulting after the deposition of a slab of six poly-silicon|SiO_2 bilayers (top) in one shot followed by the conformal attack stopped with the exposure of the original lithographic seed, resulting in an array of 12 sub-lithographic wires (bottom). (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

17.4.2 Multiplicative Route—$S^nPT_\times$

The SPT allows, starting from one seed, the preparation of *two* spacers [27]; in principle, this fact allows another, multiplicative, growth technique—$S^nPT_\times$. The multiplicative generation requires that both sides of each newly grown spacer are used as seeds for the subsequent growth—that is possible only if the original seed is etched away at the end of any cycle. In $S^nPT_\times$ each multiplicative $SPT_\times$ cycle involves therefore the following steps:

$S^nPT^1_\times$, conformal deposition of a film on the seed
$S^nPT^2_\times$, directional etching of the newly deposited film up to the exposure of the seed
$S^nPT^3_\times$, selective etching of the original seed

Figure 17.11 sketches two $S^nPT_\times$ repetitions.

Assume that the process starts from a seed formed by an array with pitch P of lithographically defined seeds (lines) each of width W, the linear density K_0 of lines being thus given by $K_0 = P^{-1}$. If lower and upper arrays have the same linear density K_0, the lithographic cross-point density is K_0^2 and the repetition of n (bottom) plus n (top) $S^nPT_\times$ results in a sub-lithographic cross-point density $\delta_\times$ given by

$$\delta_\times = 2^{2n} K_0. \tag{17.4}$$



FIGURE 17.11 Two $STP_\times$ steps for the formation of a sub-lithographic wire array starting from a lithographic seed array. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

For any assigned n, this density is optimized maximizing K_0, i.e., minimizing P. The minimum value of P is determined by the considered lithography, while W is adjusted to the wanted value controlling exposure, etching, etc. The appropriate ratio W/P is obtained with the following considerations.

Let the seeds be formed by a given material A (to be concrete we shall think of it as SiO_2) and the $SPT_\times$ be carried out depositing another material B (again for concreteness, we shall think of B as poly-silicon) forming a conformal layer of thickness $t_1 = \varrho_1 W$, with $\varrho_1 < 1$. After completion of the multiplicative SPT cycle, the surface will thus be covered by an array of $2K_0$ wires per unit length each of width $w_1 = t_1 = \varrho_1 W$.

Let the process proceed with the deposition of a film of A with thickness $t_2 = \varrho_2 w_1 = \varrho_1 \varrho_2 W$, with $\varrho_2 < 1$ (in the considered example, this process could be the oxidation of poly-silicon to an SiO_2 thickness t_2). After completion of the second $SPT_\times$ cycle, the surface will be covered by a spacer array of linear density $2^2 K_0$ each of width $w_2 = t_2 = \varrho_1 \varrho_2 W$. It is noted that in $S^nPT_\times$ the seed material at the end of each $SPT_\times$ is inverted from A to B or vice versa, so that the material of the original seed must be chosen in the relation to the parity (even or odd) of n.

In the following, the focus is on the search of the mask geometry that maximizes the spacer density. After n reiterations of the $SPT_\times$, the spacers will extend both beyond and beneath the original lithographic feature. The zone containing the spacers extends from the edge of the original lithographic feature both into the region separating them and into the region beneath the original feature by amounts l^n_{out} and l^n_{in} given by

$$\begin{aligned} l^n_{out} &= w_1 + w_2 + \cdots + w_n \\ &= W \sum_{k=1}^{n} \prod_{j=1}^{k} \varrho_j, \end{aligned} \tag{17.5}$$

$$\begin{aligned} l^n_{in} &= w_2 + \cdots + w_n \\ &= W \sum_{k=2}^{n} \prod_{j=1}^{k} \varrho_j. \end{aligned} \tag{17.6}$$

The estimate of l^n_{out} and l^n_{in} requires knowledge of various ϱ_k values; at this stage, it is impossible to state anything about them. Without pretending to describe the actual technology, but simply to have quantitative (although presumably correct at the order of magnitude) estimates, we assume ϱ_k independent of k, $\forall k(\varrho_k = \varrho)$. With this assumption Equations 17.5 and 17.6 become

$$\begin{aligned} l^n_{out} &= W \sum_{k=1}^{n} \varrho^k \\ &= W \frac{\varrho}{1-\varrho}(1-\varrho^n), \end{aligned} \tag{17.7}$$

$$
\begin{aligned}
l_{\text{in}}^{n} &= W\sum_{k=2}^{n}\varrho^{k} \\
&= W\frac{\varrho^{2}}{1-\varrho}(1-\varrho^{n-1}). \qquad (17.8)
\end{aligned}
$$

The least upper bounds of l_{out} and l_{in} are obtained taking the limit for $n \to +\infty$ in Equations 17.7 and 17.8: $l_{\text{out}} = \varrho/(1-\varrho)$ and $l_{\text{in}} = \varrho^2/(1-\varrho)$; moreover, already for relatively low values of n both ϱ^n and ϱ^{n-1} are negligible with respect to 1 so that we can reasonably assume

$$l_{\text{out}}^{n} \simeq W\varrho/(1-\varrho), \qquad (17.9)$$

$$l_{\text{in}}^{n} \simeq W\varrho^{2}/(1-\varrho). \qquad (17.10)$$

For any W, the optimum ϱ is obtained imposing the condition that all the region beneath the original lithographic feature is filled with nonoverlapping spacers: $2l_{\text{in}} = W$. Inserting this condition into Equation 17.10 gives

$$\varrho \simeq \frac{1}{2}. \qquad (17.11)$$

Similarly, the optimum size of the outer region is given by the following condition: $2l_{\text{out}} = P - W$. Inserting this condition into Equation 17.9 gives

$$P \simeq 3W. \qquad (17.12)$$

Choi et al. [28] have demonstrated that three $\text{SPT}_\times$ repetitions on a lithographically defined seed result in nanowire arrays of device quality and suggest that very long wires can indeed be produced with a high yield. However, even accepting that the process have a yield so high as to allow the preparation of noninterrupted wires over a length (on the centimeter length scale) comparable with the chip size, if the lines are used as conductive wires of the crossbar its length is so high to have a series resistance larger than the resistance of the molecules forming the memory cell. This problem was considered in Ref. [2], where it was shown that the crossbar memory can conveniently be organized in modules each hosting a sub-memory of size 1–4 kbits. This implies that each module must be framed in a region sufficiently large to allow the addressing of the memory cells. In this way the density calculated with Equation 17.4 is an upper value to the exploitable density.

17.4.3 Three-Terminal Molecules

The use of molecules in molecular electronics is essentially due to the fact that they embody in themselves the electrical characteristics of existing devices. The characteristics of nonlinear resistors, diodes, and Schmitt triggers have been reported for two-terminal molecules; their use as nonvolatile memory cells is possible thanks to the stabilization of a metastable state excited by the application of a high voltage (thus behaving as a kind of virtual third terminal). Three-terminal molecules offer more application perspectives not only because they can mimic transistors but also because they could exploit genuine quantum phenomena like the Aharonov–Bohm effect [35].

The application potentials of three-terminal molecules can however be really exploited only if all terminals can be contacted singularly. This is manifestly impossible using the XB or XB_+ routes, but is possible in the $\text{XB}_\star$ framework. The major advantage of poly-silicon in the $\text{XB}_\star$ route is that it does not pose the problem of metal electromigration. However, the multispacer technology can also be adapted for the preparation of nanowire arrays of poly-silicon and metals in arrangements that

- Allow the use of three-terminal molecules
- Facilitate the self-assembly of functional molecules
- Avoid the problem of metal electromigration

Assume that the top array defining the crossbar is formed by poly-silicon nanowires whereas the bottom array has a more complicate structure. Assume, as sketched in Figure 17.12a, that each conformal deposition is formed by the following multilayer:

$$\text{SiO}_2\,|\,\text{polysilicon}\,|\,\text{SiO}_2\,|\,\text{metal}\,|\,\text{SiO}_2\,|\,\text{polysilicon},$$

where the metal might be, for instance, platinum obtained via CVD from PtF_6 precursor.

After an SPT, one gets the structure sketched in Figure 17.12b; a subsequent time-controlled selective etch of the metal electrode will result in the formation of a recessed region, as sketched in Figure 17.12c.



FIGURE 17.12 The structure resulting after (a) conformal deposition of a multilayer, (b) its directional etching, (c) three repetitions of the above processes, and (d) the time-limited preferential attack of the metal. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)



FIGURE 17.13 The three-terminal molecule after the formation of a self-assembled monolayer on the metal and the grafting to the silicon. The larger separation between metal and top poly-silicon electrode than between top and bottom poly-silicon electrodes suggests that the metal surface is subjected to an electric stress much lower than that at the bottom silicon surface.

Now, observe that thiol-terminated molecules self-assemble spontaneously on many metals (like platinum, gold, etc.) forming closely packed monolayers. Therefore, if the considered three-terminal molecules contain two alkyne and one thiol terminations, they can arrange in the cross-points in an ordered way, allowing their covalent grafting by simple heat treatment, as sketched in Figure 17.13. This figure also explains why the electric field at the metal–sulfur interface may be significantly lower than at the silicon–carbon interface.

17.5 Influence of Technology on Architecture

Device architecture and preparation procedure are strongly interlocked. This will become especially clear considering that crossbars obtained via S^nPT_+ may be linked to the external world via methods that cannot be extended to $S^nPT_\times$.

17.5.1 Addressing

If the availability of nanofabrication techniques is fundamental in establishing a nanotechnology, not less vital is the integration of the nanostructures with higher-level structures: once the crossbar structure is formed, it is necessary to link it to the conventional silicon circuitry. This is especially difficult because the nanoworld is not directly accessible by means of standard lithographic methods—"the difficulties in communication between the nanoworld and the macroworld represent a central issue in the development of nanotechnology" [36].

The importance of addressing nanoscale elements in arrays goes beyond the area of memories and will be critical to the realization of other integrated nanosystems such as chemical or biological sensors, electrically driven nanophotonics, or even quantum computers.

In the following the attention will however be limited to the problem of addressing cross-points in a nanoscopic crossbar structure by means of externally accessible lithographic contacts.

Several strategies have been adopted to attack this problem: many of them involve materials and methods quite far from, if not orthogonal to, those of the planar technology [37–43].

The consistent strategies with the planar technology are discussed in Ref. [2]. Of them, one can be applied to all crossbars irrespective of their preparation methods. According to this strategy, each line defining the crossbar extends beyond the crossing region and in this zone it is used for addressing. This region is then covered with a protecting cap, which is etched away along a narrow (sub-lithographic) line misoriented with respect to the array by a small angle α. In this way the zones where the bars are not covered are separated by a distance that diverges for $\alpha \to 0$; thus, if α is sufficiently small, the separation between the zones no longer protected makes them accessible to conventional lithography and suitable for contacting the CMOS circuitry. In this method, each line is linked separately from the others to the external circuitry—addressing n^2 cross-points requires therefore $2n$ contacts.

The multispacer technique (in particular, the S^nPT_+) permits, however, novel strategies for the nano-to-litho link in addition to the ones suitable for crossbar prepared with other techniques.

In the first of such strategies, the original mask defining the seed is shaped with n indentations with size so scaled that (1) the first indentation is filled, with the fusion of the wires, after the first deposition; (2) the second indentation is filled, with the fusion of the wires, after the second deposition; (3)…; and (4) n, the nth indentation is filled, with the fusion of the wires, after the nth deposition.

Taking into account that the minimum distance between the centers of two adjacent fused layers is $W + 3p$ (say 150 nm) and that each contact requires the definition of a hole in a region with side $2p$ (say 70 nm), this technique allows the nano-to-litho link. Figure 17.14 shows the cross section demonstrating



FIGURE 17.14 Cross-section showing the fusion of the arms of the fourth wire grown on two sides of the indentation. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

how filling indentation with the fusion of the central wires may render them accessible to lithography. Similarly to the strategy considered above, in this method, each line is linked separately from the others to the external circuitry, so that addressing n^2 cross-points requires therefore $2n$ contacts.

The S^nPT_+ technique results in wires with different heights. This fact can be exploited to inhibit or enable them by means of dielectrically insulated lithographically defined electrodes in the geometry described in Ref. [2]. A crossbar with $n \times n$ cross-points can therefore be addressed by controlling the conduction along the wires from one Ohmic contact to the other by means of 2 + 2 electrodes. Therefore, for the addressing of n^2 cross-points, this method needs 3 + 3 electrodes only; however, as discussed in Ref. [2], this architecture requires a complex elaboration of the information involving analog-to-digital conversion, with subsequent analysis and elaboration of data.

17.5.2 Comparing Crossbars Prepared with Additive or Multiplicative Routes

While the repetition in additive way of n SPTs per (bottom and top) layers magnifies the lithographically achievable cross-point density K_0^2 by a factor of $(2n)^2$, the repetition in multiplicative way gives a magnification of 2^{2n}. The magnification factor increases quadratically for the additive way and exponentially with the multiplicative way.

To estimate numerically the process simplifications offered by $S^nPT_\times$ over SPT_+, consider for instance the case of the 3 $SPT_\times$ repetitions per layer. This would produce a magnification of the lithographic cross-point density by a factor of $2^3 \times 2^3$. Taking $W = 0.1\,\mu\text{m}$, after 3 $SPT_\times$ repetitions, the spacer width should be of 12.5 nm, with minimum separation of 25 nm. Taking into account Equation 17.12, the cross-point density achievable with the repetition of 2 × 3 $SPT_\times$ would thus be almost the same as that obtainable with the repetition of 2 × 10 SPT_+ (7×10^{10} cm^{-2} vs. 8×10^{10} cm^{-2}).

Figure 17.15 shows in plan view a comparison between the following crossbars:

(a) A 2 × 2 crossbar obtained by crossing lithographically defined lines.
(b) A 16 × 16 crossbar obtained via S^8PT_+ starting from lithographically defined seeds separated by a distance allowing the optimal arrangement of the wire arrays.
(c) An 16 × 16 crossbar obtained via $S^3PT_\times$ starting from lithographically defined seeds separated by a distance satisfying Equation 17.12.

The figure has been drawn in the following hypotheses:

- The lithographic lines in (a) and (b) have width at the current limit for large-volume production, say $W = 65$ nm.
- The height loss τ is such that the maximum number of repetitions in the additive route is 8, and the sub-lithographic pitch is the same as shown in Figure 17.6.



FIGURE 17.15 Plan-view comparison of the crossbars obtained (a) crossing lithographically defined lines, (b) using the lithographically defined lines above as seeds for S^8PT_+, and (c) using the lithographically defined lines above as seeds for $S^3PT_\times$. In each structure the square with dashed sides denotes a unit cell suitable for the complete surface tiling. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

- The lithographic width of (c) is chosen to allow the minimum pitch to be consistent with the one obtained with the additive route ($W = 100$ nm); in this way, producing sub-lithographic wires with width (12.5 nm) has been proved to be producible [28].

For $n \geq 3$, this comparison is so favorable to $S^nPT_\times$ to suggest its practical application. The following factors, however, would make S^nPT_+ preferable to $S^nPT_\times$:

1. If addressing the wires defining the crossbar are used also as addressing lines, they cannot run along the entire plane; their interruption for addressing reduces the available area.
2. In $S^nPT_\times$ all wires are produced collectively and have the same height and material characteristics. On the contrary, in S^nPT_+ the wires are produced sequentially, each SPT_+ repetition produces wires of decreasing height, and the characteristics of the material (or even the materials themselves) may vary in a controlled way from one cycle to another.

Whereas at the first glance all the S^nPT_+ features described the second item may seem detrimental, the analysis of Section 17.5.1 has clarified that they may be usefully exploited for cross-point addressing.

Deciding which route, between the additive and multiplicative ones, is actually more convenient for the preparation of hybrid devices depends on the particular application and circuit architecture. In fact, the multiplicative route (certainly less demanding for what concerns the preparation of the crossbar but more expensive for what concerns the nano-to-litho link) is presumably suitable for random access memories; on the contrary, the additive route (more demanding for the crossbar preparation, but much heavier for the elaboration of the signal) seems consistent with nonvolatile memories.

17.5.3 Applications—Not Only Nanoelectronics

The proposal of the S^nPT is quite recent [30,31], so that it has had only short time to be tested.

17.5.3.1 Electronics

Concerning the preparation of crossbars, the attention has mainly been concentrated on one side on the verification of the possibility of scaling the S^nPT_+ to large values of n (the productions of arrays with $n = 3$ [30,31], 4 [44], and 6 [45] have been reported) and on the other on the architectural impact of this technology [46–48]. In the middle, a demonstrator has been prepared showing the feasibility, without stressing the technology, of crossbars with cross-point density of 10^{10} cm^{-2} [45].

The electrical characterization of silicon nanowires has been the subject of only a few studies: Ref. [24], addressed to the nanonowires produced via the SNAP technique and Ref. [45], devoted to nanowires built with the S^nPT_+. The latter paper demonstrates that the S^nPT_+ is already suitable for the preparation of ultrahigh density memory.

The interest of a technology for the cheap production of nanowires is not limited to nanoelectronics but might extend to energetics.

17.5.3.2 Energetics

The large-scale availability of devices able to transform low-enthalpy heat (which would otherwise be dispersed into the environment) into electrical energy without complicate mechanical systems might impact the energy problem on a global scale. In principle the Seebeck effect provides a way for that. The ability of a material to operate as a Seebeck generator is contained in a parameter, ZT—a function of the Seebeck coefficient and of the electrical and thermal conductivities. The possibility of practical application is related to the occurrence of $ZT \gtrsim 1$.

From the technical point of view, Seebeck devices are already known, but materials with high Seebeck coefficient (multicomponent nanostructured thermoelectrics, such as Bi_2Te_3/Sb_2Te_3 thin-film superlattices, or embedded PbSeTe quantum dot superlattices) are expensive. This fact has allowed the application of direct thermoelectric generators only to situations (e.g., space) where cost is not important or due to other factors (e.g., weight in space application).

This state of affairs would significantly change only in the presence of highly efficient, low-cost materials. A new avenue to progress in such a direction has been the claim, by two independent collaborations [49,50], that silicon nanowires with width of 20–30 nm and rough surfaces having $ZT \simeq 1$. Although silicon is certainly a cheap material and a lot of technologies are known for its controlled deposition, this result is of potential practical interest only if the production of nanowires does not involve electron beam or extreme ultraviolet lithographies—hence the relevance of S^nPT.

It is also noted that the researchers of Refs. [49,50] employed wires with comparable height and width, thus characterized with a very high resistance. The S^nPT allows the preparation of wires with much higher aspect ratio (same width and much higher height—actually nanosheets). If it were possible to impart a sufficient roughness to the sidewalls of these sheets, it would result in much more efficient Seebeck generators.

17.6 Fractal Nanotechnology

There is an application where the multiplicative route is manifestly superior: the preparation of fractal structures on the sub-lithographic length scale.

17.6.1 Fractals in Nature

The volume V of any body with regular shape (spheric, cubic, …) varies with its area A as

$$V = g_3 A^{3/2}, \tag{17.13}$$

with g_3 being a coefficient related to the shape (for instance, $g_3 = (1/6)^{3/2}$ for cubes, $g_3 = 1/6\sqrt{\pi}$ for spheres, etc.; a well-known variational properties of the sphere guarantees that for all bodies $g_3 \le 1/6\sqrt{\pi}$). For bodies with regular shape the ratio A/V diverges for small V and vanishes for large V.

Life can be preserved against the second law of thermodynamics only in the presence of a production of negative entropy in proportion to the total mass of the organism. This is achieved via the establishment of a diffusion field sustained by the metabolism inside the organism [51]. Since the consumption of energy and neg-entropy of living systems increases in proportion to V whereas the exchange of matter increases A, small unicellular organisms (like bacteria) have no metabolic problem due to their shape and can grow satisfying Equation 17.13 preserving highly symmetric shapes (the smallest living bacterium, the pleuropneumonia like organism, with diameter 0.1–0.2 μm, is spherical). On the contrary, larger organisms (even procaryotic, like the amoeba) may survive only adapting their shapes to have an energy uptake coinciding with what is required to preserve living functions [52,53]:

$$V = g_2 A, \tag{17.14}$$

with g_2 being a coefficient characteristic of two-dimensional growth. Moreover, the need to adapt itself to the variable environmental conditions is satisfied only thanks to the existence of an inner organellum, the endoplasmatic reticulum [54], which can fuse to the external membrane, thus allowing an efficient change of area at constant volume [52,53]. This mechanism, however, can sustain the metabolism of unicellular organisms (like the amoeba) only for diameter of at most a few tens of micrometers.

Larger organisms require the organization of the constituting cells in tissues specialized to single functions. This specialization, however, requires the formation of a vascular network (to transport catabolites to, and anabolites from, each constituting cell) whose space-filling nature implies a fractal character [55]. Nature prefers to manifest itself with fractal shapes in other situations too, like for the mammalian lung (to allow a better O_2–CO_2 exchange) [56], the dendritic links of the neuron (to allow a high interconnection degree [57]).

That smoothness is not a mandatory feature of the way how nature expresses itself, but rather fractality is of ubiquitous occurrence in a large class of phenomena even in the mineral kingdom has become clear with Mandelbrot's question about the length of the Great Britain coast [58].

The fractality of nature is manifestly approximate, the lowest length scale being ultimately limited by the atomic nature of matter. That surfaces may continue to have a scale invariance down to the atomic size became however clear only after Avnir, Farin, and Pfeifer's study of the adsorption behavior of porous adsorbents [59–61].

Surprisingly enough, the artificial production of self-similar structures has remained largely unexplored. This is somewhat disappointing because the use of arrays or matrices with self-similar structures is potentially interesting even for applications. For instance, a matrix formed by the Cartesian product of two Cantor sets would provide a way for sensing with infinite probes a surface, leaving it almost completely uncovered. Although the minimum length scale is actually larger than the atomic one, that ideal case suggests the usefulness of the idea.

The lowest length scale of biological fractals is determined by cell size, say 10^4 nm. The preparation of self-similar structures on length scales between 10^2 and 10^4 nm is relatively easy via photolithography, but this scale seems inadequate for interesting applications like the highly parallel probing of single cells (as required, for instance, by the needs of systems biology [62]). Rather, for that application the appropriate length scale seems the one characteristic of nanotechnology, 1–10^2 nm.

17.6.2 Producing Nanoscale Fractals via $\text{S}^n\text{PT}_\times$

Imagine for a moment that, in spite of the atomistic nature of matter and of the inherent technological difficulties, the multiplicative route can be repeated indefinitely. Remembering that the (n + 1)th step generates a set $\mathcal{S}_{n+1^-}$, which is, nothing but the one at the nth, $\mathcal{S}_n$, at a lower scale, the sequence $\{\mathcal{S}_0,\ldots,\mathcal{S}_n,\ldots\}$ defines a fractal. This fractal, referred to as multispacer fractal set, is self-similar only if the height of each spacer varies with n as 2^{-n}, otherwise, the fractal is self-affine [63]. As mentioned above, the "spontaneous" decrease of height with n, Equation 17.2 renders the fractal self-affine. A self-similar fractal can be obtained at the end of process planarizing the whole structure with a resist and sputter-etching in a nonselective way the composite film until the thickness is reduced to $s_0/2^n$.

It is however noted that even assuming our ability to scale down the fabrication technology, the atomistic structure of matter limits anyway the above considerations to an interval of 1–2 orders of magnitude, ranging from few atomic layers to the lower limits of standard lithography.

Having clarified in which limits the set $\mathcal{S}_n$ may be considered a fractal, it is interesting to compare it with other fractal sets. The prototype of such sets, and certainly the most interesting from the speculative point of view, is the Cantor middle-excluded set. Figure 17.16 compares sequences of three process steps eventually leading to the multispacer fractal set $\mathcal{S}$ and to the Cantor set $\mathcal{C}$. The comparison shows interesting analogies: consider a multiplicative multispacer with $P = 2W$; if $w_n = (1/3)w_{n-1}$, the measure at each step of multifractal set coincides with that of the Cantor set. This implies that the multispacer fractal set has null measure. Similarly, it can be argued that the multispacer set, considered as a subset of the unit interval, has the same fractal dimension as the Cantor middle-excluded set—ln(2)/ln(3) [63]. At each step, the multispacer fractal set is characterized by a more uniform distribution of single intervals than the Cantor set; this makes the former more interesting for potential applications than the latter.

Once one has one-dimensional fractal sets, two-dimensional fractal sets can be constructed taking their Cartesian products. Although the mixed product $\mathcal{C}\times\mathcal{S}$ is possible, in the following, we concentrate on a comparison of the Cantor and multispacer fractal crossbars. Figure 17.17 compares their plan views showing

(A) A 16 × 16 crossbar obtained via $\text{S}^3\text{PT}_\times$ starting from lithographically defined seeds separated by a distance satisfying Equation 17.12

(B) A 16 × 16 crossbar obtained via $\text{S}^3\text{PT}_\times$ starting from lithographically defined seeds and arranging the process to generate the Cantor middle-excluded set

Although the potential applications of the Cantor set are quite far, trying to reproduce it on the nanometer length scale seems of a certain interest. This is compatible with existing technologies; a possible process would involve



FIGURE 17.16 Generation of the multispacer set (left) and of the Cantor middle-excluded set (right). (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)



FIGURE 17.17 Plan-view comparison of the crossbars obtained via $S^3PT_\times$, and a corresponding Cantor middle-excluded set; the width of the lithographic seed in $S^3PT_\times$ has been assumed to be at the technology forefront, whereas in the Cantor set it has been assumed sufficiently large to allow three reiterations of the process. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

(C1) the lithographic definition of the seed (formed, for instance, by poly-silicon) generating the Cantor set

(C2) its planarization (for instance, via the deposition of a low viscosity glass and its reflow upon heating)

(C3) the etching of this film to a thickness controlled by the exposure of the original seed

(C4) the selective etching of the original film

(C5) the conformal deposition of a film of the same material as the original seed (poly-silicon, in the considered example) and of thickness equal to 1/3 of its width

(C6) its directional etching

(C7) the selective etching of the space seed (glass, in the considered example)

Figure 17.18 sketches the overall process [64].

The preparation of fractal structures may appear at a first sight nothing but a mere exercise of technology stressing. The following examples suggest however the usefulness of a fractal technology:

1. The highly parallel and real-time sensing of single cells (as required, for instance, by the needs of systems biology [62] of by label-free immunodetection [65]) could be done with a minimum of perturbation (i.e., leaving almost completely uncovered the cell surface) by a matrix formed by the Cartesian product of two Cantor sets [63].



FIGURE 17.18 A process for the generation of Cantor's middle-excluded set. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

2. Superhydrophobic surfaces may be prepared controlling roughness and surface tension of nonwetting surfaces [66]. Whereas surface tension is a material property, roughness can be controlled by the preparation. For instance, roughness may be achieved by imparting a suitable (fractal) relief on the surface.
3. If the S^nPT is used for the preparation of crossbar structures for molecular electronics, the functionalization with organic molecules of the cross-points can only be done after the preparation of the hosting structure. According to the analysis of Ref. [44], this requires an accurate control of the rheological and diffusion properties in a medium embedded in a domain of complex geometry. Understanding how such properties change when the size is scaled and clarifying to which extent the domain can indeed be viewed as a fractal (so allowing the analysis on fractals [67] to be used for their description) may be a key point for the actual exploitation of already producible nanometer-sized wire arrays in molecular electronics.

Appendixes

17.A Abstract Technology

The processes considered in this chapter (conformal deposition, directional etching, and selective etching) have been introduced without specifying exactly what they are and which materials they involve. Although the reader certainly has a built-in idea of them, we however believe useful to provide their rigorous definition.

Once defined in rigorous mathematical terms, the processes of interest for this work are the building blocks of a nanotechnology that may be seen as the equivalent of Euclid's geometry, where the construction with straightedge and compass is replaced by the construction via conformal, directional or selective, deposition or etchings. Of course, the properties of a figure built with any real straightedge and compass are not exactly the same as those of the same figure constructed with the ideal straightedge and compass. Similarly, the use of real materials and processes produces structures that differ from those achievable via the ideal materials and processes. Nonetheless, it is convenient to develop the theory in abstract terms.

17.A.1 Bodies and Surfaces

The minimal characterization of a body is in terms of its geometry and constituting materials.

Definition 17.1 (Simple body) *A simple body* $\mathcal{B}_X$ *is a three-dimensional closed connected subset* B *of the Euclidean space* $\mathbb{E}^3$ *filled with a material* X:

$$\mathcal{B}_X = (B, X).$$

What is a material is considered here a primitive concept. It may be a substance, a mixture, a solution, or an alloy. The emphasis is on homogeneity—whichever region, however small, of B is considered, the constituting material is the same. When not necessary, the index denoting the constituting material will not be specified.

In view of the granular nature of matter, considering the limit for vanishing size is not relevant. Here and in the following when dealing with the concept of vanishing length (as it implicitly happens when considering the frontier $B^\star$ of B) we mean that the property holds true on the *ultimate length scale*. Although the ultimate length scale is an operative concept related to the probe used for observing the body, we however have in mind the molecular one. Analogously, we consider a body as indefinitely extended when its size is much bigger than the size variations induced by the considered processes. In this sense, a *wafer* is a simple body indefinitely extended over two dimensions.

Definition 17.2 (Composite body) *Consider the N-tuple of simple body* $(\mathcal{B}_{X^1}, \mathcal{B}_{X^2}, \ldots, \mathcal{B}_{X^N})$ *formed by nonoverlapping sets* $(B_1, B_2, \ldots, B_N)$, *with*

$$\forall I, J\left(B_i \cap B_j = B_i^\star \cap B_j^\star\right),$$

and let

$$B = \bigcup_{i=1}^{N} B_i.$$

If B *is connected and the simple bodies* $(\mathcal{B}_{X^1}, \mathcal{B}_{X^2}, \ldots, \mathcal{B}_{X^N})$ *contain at least two different materials* X^I *and* X^J, *then the N-tuple is a composite body.*

Definition 17.3 (Interface) *Let a composite body* $\mathcal{B}$ *be formed by simple bodies* $\mathcal{B}_{X^1}$ *and* $\mathcal{B}_{X^2}$ *with* $X^1 \neq X^2$; *the region*

$$F_{1|2} = B_1^\star \cap B_2^\star$$

defines the interface between $\mathcal{B}_{X^1}$ *and* $\mathcal{B}_{X^2}$.

For any $\mathbf{x}$ in $F_{1|2}$ all neighborhoods, however small, contain materials X^1 and X^2.

Definition 17.4 (Total surface) *The set*

$$S_{\text{tot}} = B^\star$$

is the total surface of $\mathcal{B}$.

Proposition 17.1 *Let a composite body* $\mathcal{B}$ *be formed by the N-tuple of simple body* $(\mathcal{B}_{X^1}, \mathcal{B}_{X^2}, \ldots, \mathcal{B}_{X^N})$. *Then*

$$S_{\text{tot}} = \bigcup_i B_i^\star \Big\backslash \bigcup_{j,k} F_{j/k}.$$

Definition 17.5 (Surface) *Let* $\mathcal{B}$ *be a composite body, and* $B_\bullet$ *be the smallest simply-connected (i.e., without holes) set containing B. Then*

$$S = B_\bullet^\star$$

is the outer surface (or simply surface) of $\mathcal{B}$.

Definition 17.6 (Inner surface) *Let* $\mathcal{B}$ *be a composite body. Then*

$$S_{\text{in}} = S_{\text{tot}} / S$$

is the inner surface of $\mathcal{B}$.

17.A.2 Conformal Deposition and Isotropic Etching

Definition 17.7 (Delta coverage) *For any body* $\mathcal{B} \leftarrow$ *with surface* S, *the additive delta coverage* $\overline{D}_{+\delta}$ *of thickness* δ *is the set*

$$\overline{D}_{+\delta} = \left\{\mathbf{x} : |\mathbf{x} - \mathbf{y}| \leq \delta \wedge \mathbf{y} \in S \wedge \mathbf{x} \notin B_\bullet \backslash S\right\}.$$

The delta coverage can be imagined to result from the application of an operator a_δ to B:

$$\overline{D}_{+\delta} = a_\delta(B).$$

The delta coverage $\overline{D}_{+\delta}$ is the "pod" of thickness δ covering the set *B*. The set obtained as union of *B* with its delta coverage is referred to a $B_{+\delta}$:

$$B_{+\delta} = B \cup a_\delta(B).$$

This operation can be reiterated, and the final set obtained after *n* iteration is referred to as $B^n_{+\delta}$:

$$B^n_{+\delta} = B^{n-1}_{+\delta} \cup a_\delta\left(B^{n-1}_{+\delta}\right),$$

where $B^1_{+\delta} = B_{+\delta}$ and $B^0_{+\delta} = B$.

The reiteration of a_δ is the base for the following definition:

Definition 17.8 (Conformal coverage) *A conformal coverage* $C_{+\delta}$ *of thickness* δ *is the following limit**:

$$C_{+\delta} = \lim_{n\to+\infty} \bigcup_{i=0}^{n-1} a_\delta\left(B^i_{+\delta/n}\right).$$

In other words, the conformal coverage process can be thought of as obtained by applying infinitely many delta coverages; one after another, and each one of infinitesimal thickness. As shown in Figure 17.19, in general conformal coverage and delta coverage of the same thickness can lead to different bodies. Moreover from the same figure it is clear that these transformations are not topological invariants.

Definition 17.9 (Conformal deposition) *A conformal deposition of a film of material Z of thickness* δ *is the pair* ($C_{+\delta}$, *Z*).

Note that the material *Z* may be different from the materials X^i forming the original body.

The following theorem is trivial:

Theorem 17.1 (Planarization) *Let* d_S *the diameter of* $\mathcal{B}$. *Irrespective of the shape of* $\mathcal{B} \leftarrow$ *the conformal deposition of a layer for which* $\delta \gg d_S$ *produces a body whose shape becomes progressively closer and closer to the spherical one as* δ increases. *If* $\mathcal{B} \leftarrow$ *is indefinitely extended in two directions, it undergoes a progressive planarization.*

Isotropic etching can be defined in a way similar to that used for conformal coverage by introducing an operator s_δ, characterized by the following definitions:



FIGURE 17.19 The different behavior of conformal coverage (left) and delta coverage (right). (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

$$s_\delta(B) = a_\delta(\mathbb{E}^3 \backslash B_\bullet),$$

$$B^n_{-\delta} = B^{n-1}_{-\delta} \backslash s_\delta\left(B^{n-1}_{-\delta}\right).$$

In general, the operator s_δ is not the inverse of a_δ. In fact, $s_\delta(B) = a_{-\delta}(B)$ only if *B* is a simply connected set. We refer to s_δ as *delta depletion*.

Definition 17.10 (Conformal depletion) *A conformal depletion* $E_{-\delta}$ *of thickness* δ *is the following limit*:

$$E_{-\delta} = \lim_{n\to+\infty} \bigcup_{i=0}^{n-1} s_\delta\left(B^i_{-\delta/n}\right).$$

Also in this case, it is true that in general the conformal depletion and delta depletion s_δ of the same thickness can lead to different bodies (see Figure 17.20).

Definition 17.11 (Isotropic etching) *An isotropic* (*nonselective*) *etching is a conformal depletion of thickness* δ *applied to a body* $\mathcal{B} \leftarrow$ *regardless of its constituting materials.*

The etching process just defined is nonselective. However the most part of etching are selective (see Section 17.A.4).

---

* Such a limit is naively clear, but its rigorous specification should require to elaborate many technical details that we prefer to skip in this appendix. The same considerations hold true anytime we introduce limits of this kind.



FIGURE 17.20 The different behavior of conformal depletion (left) and delta depletion (right). (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

17.A.3 Directional Processes

Definition 17.12 (Shadowed surface along d) *Let* **d** *be a unit vector in* $\mathbb{E}^3$. *For any point s belonging to the surface S consider the straight line* l_s *starting from s and oriented as* **d**. *If* l_s *intersects S, then s is said to be shadowed along* **d**. *The set all shadowed points of S is referred to as the shadowed surface* $S_{\mathbf{d}}$ *along* **d** *of the body* $\mathcal{B}$.

Definition 17.13 (Directional delta coverage along d) *The directional delta coverage along* **d** *is the set of points lying on the straight lines directed along* **d** *and going from the exposed surface to the same surface shifted along* **d** *by an amount* δ:

$$\overline{D}_{+\delta,+\mathbf{d}} = \{\mathbf{x} : \mathbf{x} = \mathbf{y} + a\mathbf{d} \wedge a \le \delta \wedge \mathbf{y} \in S \setminus S_{\mathbf{d}}\}.$$

Figure 17.21 shows the results of applying to a given set the delta coverage and the directional delta coverage along **d**.

By using the directional delta coverage along δ instead of the delta coverage, it is possible to define the directional deposition.

Definition 17.14 (Directional deposition) *A directional deposition* $C_{+\delta,+\mathbf{d}}$ *of thickness* δ *along* **d** *is the following limit*:

$$C_{+\delta,+\mathbf{d}} = \lim_{n\to+\infty} \bigcup_{i=0}^{n-1} a_{\delta,+\mathbf{d}}\left(B^{i}_{+\delta/n,+\mathbf{d}}\right),$$

where $a_{\delta,+\mathbf{d}}$ *is the operator associated with the directional delta coverage and* $B^{n}_{+\delta,+\mathbf{d}} = B^{n-1}_{+\delta,+\mathbf{d}} \cup a_{\delta,+\mathbf{d}}(B^{n-1}_{+\delta,+\mathbf{d}})$.



FIGURE 17.21 Comparison between delta coverage (left) and directional delta coverage along **d** (right) of the same thickness δ. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)



FIGURE 17.22 An example of directional deposition. (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

Figure 17.22 shows an example of directional deposition. This process (as shown in the figure) can create holes inside the bodies.

Analogously, to define the directional depletion we introduce the directional delta depletion:

Definition 17.15 (Directional delta depletion along d)

$$\overline{D}_{+\delta,-\mathbf{d}} = \left\{\mathbf{x} : \mathbf{x} = \mathbf{y} - a\mathbf{d} \wedge a \le \delta \wedge \mathbf{y} \in S \setminus S_{\mathbf{d}}\right\}.$$

Definition 17.16 (Directional etching along d) *A directional etching $E_{-\delta,-\mathbf{d}}$ of thickness δ is the following limit:*

$$E_{-\delta,-\mathbf{d}} = \lim_{n\to+\infty} \bigcup_{i=0}^{n-1} s_{\delta,-\mathbf{d}}\left(B^{i}_{-\delta/n,-\mathbf{d}}\right),$$

where $s_{\delta,-\mathbf{d}}$ is the operator associated to the directional delta depletion and $B^{n}_{-\delta,+\mathbf{d}} = B^{n-1}_{-\delta,-\mathbf{d}} \backslash s_{\delta,-\mathbf{d}}\left(B^{n-1}_{-\delta,-\mathbf{d}}\right)$.

17.A.4 Selective Processes

No indication has hitherto been given about the dependence of the same unit process on the material to which it is applied. In general the effect depends on the material, and this difference is referred to in terms of selectivity.

Before introducing selectivity, we note that the surface S of a body $\mathcal{B} \leftarrow$ is, in general, composed by different materials. In particular, by using Proposition 1 it is possible to define $S_{\text{tot},X}$, the subset of S_{tot} containing material X:

$$S_{\text{tot},X} = \bigcup_{X^i = X} B_i^{\star} \Big\backslash \bigcup_{j,k} F_{j|k},$$

and then the (outer) surface S_X composed by material X:

$$S_X = S_{\text{tot},X} \cap S.$$

Definition 17.17 (Selective delta depletion) *For any body $\mathcal{B} \leftarrow$ with surface S, the selective delta depletion $s_{\delta,X}(B)$ of thickness δ is the set*

$$s_{\delta,X}(B) = \left\{\mathbf{x} : |\mathbf{x}-\mathbf{y}| \le \delta \wedge \mathbf{y} \in S_X \wedge \mathbf{x} \notin B_{\bullet} \backslash S_X\right\}.$$

In other words, the selective delta depletion is a delta depletion that affects S_X only, not the whole surface S. We remark that, in general, $s_{\delta,X}(B)$ is not a connected set.

Definition 17.18 (Selectivity) *Any process is said to be selective with respect to materials X when, applied to a composite body $\mathcal{B}$ with frontier S, affects S_X only.*

Definition 17.19 (Selective etching) *A selective etching $E_{-\delta,X}$ of thickness δ is the following limit (in a sense to be defined):*

$$E_{-\delta,X} = \lim_{n\to+\infty} \bigcup_{i=0}^{n-1} s_{\delta,X}\left(B^{i}_{-\delta/n,X}\right),$$

where

$$B_{-\delta/n,X} = \left(B \setminus s_{\delta,X}(B)\right) \cup \left(\bigcup_{X^j \ne X} B_j\right),$$

and the iterative process is defined as in the previous cases.

As example of selective etching is given in Figure 17.23.



FIGURE 17.23 An example of selective etching ("liftoff"). (Reprinted from Cerofolini, G., *Nanoscale devices*, Springer, Berlin, Germany, 2009. With permission.)

17.B Concrete Technology

Together with the above operations, one could certainly define other, more complicate (or perhaps even formally more interesting), operations. What is of uppermost importance here is that *there already exist combinations of materials and processes of the silicon technology mimicking the ideal behaviors described above.*

The materials considered in this chapter are well known in the silicon technology: a practical model for wafer is any body extending in two directions exceedingly more than the change of thickness resulting from the considered processes and such that only the processes are actually carried out on only one of its major surfaces. Before undergoing any operations, such wafers have generally homogeneous chemical composition and high flatness and are referred to as substrates. In the typical situations considered herein the substrates are slices of single crystalline silicon. The other materials are polycrystalline silicon (poly-Si), SiO_2, Si_3N_4, and various metals (Al, Ti, Pt, Au,…).

The typical processes involved in the silicon technology are lithography (for the definition of geometries), wet or

TABLE 17.1 Shape Resulting after Etching or Growth Processes

	Shape	
Process	Conformal	Directional
Attack	Wet etching	Sputter etching
	← Plasma etching	
		Reactive ion etching →
Growth	CVD	PVD

gas-phase etchings, chemical or physical vapor deposition, planarization, doping (typically via ion implantation), and diffusion. A special class of materials is formed by resists, i.e., photoactive materials undergoing polymerization (or depolymerization) under illumination. The processes of interest here are the following:

Lithography requires a preliminary planarization with a resist, its patterning (i.e., the definition of a geometry) via the exposure through a mask to light, the selective etching of the exposed (or unexposed) resist, the selective etching first of the region not protected by the patterned resist, and eventually of this material.

Wet etchings are usually isotropic and are used for their selectivity: HF_{aq} etches isotropically SiO_2 leaving unchanged silicon and Si_3N_4; H_3PO_4 etches isotropically Si_3N_4 leaving unchanged silicon and SiO_2; $HF_{aq} + HNO_{3\,aq}$ etches Si leaving unchanged Si_3N_4 (but has poor selectivity with respect to SiO_2).

Sputter etching is produced by momentum transfer from a beam to a target and results typically in nonselective directional etching. Selectivity can be imparted exploiting reactive ion etching.

Plasma etching can be tuned to the situation: via a suitable choice of the atmosphere it can be used for the isotropic selective etching of Si, SiO_2 or Si_3N_4; it becomes progressively more directional and less selective applying a bias to the body ("target") with respect to the plasma.

Chemical vapor deposition is the typical way for the conformal deposition that occurs when the growth is controlled by reactions occurring at the growing surface. Poly-Si grows well on SiO_2 but requires an SiO_2 buffer layer for the growth on Si_3N_4; conversely Si_3N_4 is easily deposited on SiO_2. Silicon can be conformally covered by extremely uniform layers of SiO_2 with controlled thickness on the subnanometer range via *thermal oxidation*.

Physical vapor deposition is the typical way for the deposition of metal films. The corresponding growth mode is the positive counterpart of directional etching. The conformal deposition of a metal layer can only be done via CVD from volatile precursors (like metal carbonyls or metalorganic monomers).

Table 17.1 summarizes the shape (conformal or directional) resulting from the above processes.

References

1. Heath J. R., Kuekes P. J., Snider G. S., Williams R. S., A defect-tolerant computer architecture: Opportunities for nanotechnology. *Science, 280* (1998) 1716–1721.
2. Cerofolini G. F., Realistic limits to computation. II. The technological side. *Appl. Phys. A, 86* (2007) 31–42.
3. Aviram A., Ratner M., Molecular rectifiers. *Chem. Phys. Lett., 29* (1974) 277–283.
4. Joachim C., Gimzewski J. K., Aviram A., Electronics using hybrid-molecular and mono-molecular devices. *Nature, 408* (2000) 541–548.
5. Joachim C., Ratner M. A., Molecular electronics: Some views on transport junctions and beyond. *Proc. Natl. Acad. Sci. USA, 102* (2005) 8801–8808.
6. Tour J. M., Rawlett A. M., Kozaki M., Yao Y., Jagessar R. C., Dirk S. M., Price D. W., et al., Synthesis and preliminary testing of molecular wires and devices. *Chem. Eur. J., 7* (2001) 5118–5134.
7. Mendes P. M., Flood A. H., Stoddart J. F., Nanoelectronic devices from self-organized molecular switches. *Appl. Phys. A, 80* (2005) 1197–1209.
8. Chen J., Reed M. A., Rawlett A. M., Tour J. M., Large on-off ratios and negative differential resistance in a molecular electronic device. *Science, 286* (1999) 1550–1552.
9. Reed M. A., Chen J., Rawlett A. M., Price D. W., Tour J. M., Molecular random access memory cell. *Appl. Phys. Lett., 78* (2001) 3735–3737.
10. Luo Y., Collier C. P., Jeppesen J. O., Nielsen K. A., Delonno E., Ho G., Perkins J., et al, Two-dimensional molecular electronics circuits. *Chem. Phys. Chem., 3* (2002) 519–525.
11. Cerofolini G. F., Ferla G., Toward a hybrid micro-nanoelectronics. *J. Nanoparticle Res., 4* (2002) 185–191.
12. Green J. E., Choi J. W., Boukai A., Bunimovich Y., Johnston-Halperin E., Delonno E., Luo Y., et al., A 160-kilobit molecular electronic memory patterned at 10^{11} bits per square centimetre. *Nature, 445* (2007) 414–417.
13. Service R. F., Next-generation technology hits an early midlife crisis. *Science, 302* (2003) 556–559.
14. Stewart D. R., Ohlberg D. A. A., Beck P., Chen Y., Williams R. S., Jeppesen J. O., Nielsen K. A., Stoddart J. F., Molecule-independent electrical switching in Pt/organic monolayer/Ti devices. *Nano Lett., 4* (2004) 133–136.
15. Lau C. N., Stewart D. R., Williams R. S., Bockrath D., Direct observation of nanoscale switching centers in metal/molecule/metal structures. *Nano Lett., 4* (2004) 569–572.
16. Zhitenev N. B., Jiang W., Erbe A., Bao Z., Garfunkel E., Tennant D. M., Cirelli R. A., Control of topography, stress and diffusion at molecule metal interfaces. *Nanotechnology, 17* (2006) 1272–1277.
17. Stewart M. P., Maya F., Kosynkin D. V., Dirk S. M., Stapleton J. J., McGuiness C. L., Allara D. L., Tour J. M., Direct covalent grafting of conjugated molecules onto Si, GaAs and Pd surfaces from aryldiazonium salts. *J. Am. Chem. Soc., 126* (2004) 370–378.

18. Akkerman H. B., Blom P. W. M., de Leeuw D. M., de Boer B., Towards molecular electronics with large-area molecular junctions. *Nature, 441* (2006) 69–71.
19. Lankhorst M. H. R., Ketelaars B. W. S. M. M., Wolters R. A. M., Low-cost and nanoscale non-volatile memory concept for future silicon chips. *Nature Mater. 4* (2005) 347–352.
20. Strukov D. B., Snider G. S., Stewart D. R., Williams R. S., The missing memristor found. *Nature, 453* (2008) 80–83.
21. Cerofolini G. F., Romano E., Molecular electronics in silico. *Appl. Phys. A, 91* (2008) 181–210.
22. Natelson D., Willett R. L., West K. W., Pfeiffer L. N., Fabrication of extremely narrow metal wires. *Appl. Phys. Lett., 77* (2000) 1991–1993.
23. Melosh N. A., Boukai A., Diana F., Gerardot B., Badolato A., Heath J. R., Ultrahigh-density nanowire lattices and circuits. *Science, 300* (2003) 112–115.
24. Wang D., Sheriff B. A., McAlpine M., Heath J. R., Development of ultra-high density silicon nanowire arrays for electronics applications. *Nano Res., 1* (2008) 9–21.
25. Gates D. B., Xu Q. B., Stewart M., Ryan D., Willson C. G., Whitesides G. M., New approaches to nanofabrication. *Chem. Rev., 105* (2005) 1171–1196.
26. Whitesides G. M., Love J. C., The art of building small. *Sci. Am. Rep., 17* (2007) 12–21.
27. Choi Y.-K., Zhu J., Grunes J., Bokor J., Somorjai G. A., Fabrication of sub-10-nm silicon nanowire arrays by size reduction lithography. *J. Phys. Chem. B, 107* (2003) 3340–3343.
28. Choi Y.-K., Lee J. S., Zhu J., Somorjai G. A., Lee L. P., Bokor J., Sub-lithographic nanofabrication technology for nanocatalysts and DNA chips. *J. Vac. Sci. Technol. B, 21* (2003) 2951–2955.
29. Augendre E., Rooyackers R., de Potter de ten Broeck M., Kunnen E., Beckx S., Mannaert G., Vrancken C., et al., Thin L-shaped spacers for CMOS devices. *Eur. Solid-State Device Res., 2003. ESSDERC'03,* 2003, pp. 219–222.
30. Cerofolini G. F., Arena G., Camalleri M., Galati C., Reina S., Renna L., Mascolo D., Nosik V., Strategies for nanoelectronics. *Microelectron. Eng., 81* (2005) 405–419.
31. Cerofolini G. F., Arena G., Camalleri M., Galati C., Reina S., Renna L., Mascolo D., A hybrid approach to nanoelectronics. *Nanotechnology, 16* (2005) 1040–1047.
32. Cerofolini G. F., An extension of microelectronic technology to nanoelectronics. *Nanotechnol. E-Newslett., 7* (2005) 5–6.
33. Flanders D. C., Efremow N. N., Generation of <50 nm period gratings using edge defined techniques. *J. Vac. Sci. Technol. B, 1* (1983) 1105.
34. Cerofolini G. F., Mascolo D., A hybrid micro-nano-molecular route for nonvolatile memories. *Semicond. Sci. Technol., 21* (2006) 1315–1325.
35. Cardamone D. M., Stafford C. A., Mazumdar S., Controlling quantum transport through a single molecule. *Nano Lett., 6* (2006) 2422–2426.
36. Roukes M., Plenty of room indeed. *Sci. Am. Rep., 17,* 3 (2007) 4–11.
37. Huang Y., Duan X., Cui Y., Lauhon L. J., Kim K.-H., Lieber C. M., Logic gates and computation from assembled nanowire building blocks. *Science, 294* (2001) 1313–1317.
38. Zhong Z., Wang D., Cui Y., Bockrath M. W., Lieber C. M., Nanowire crossbar arrays as address decoders for integrated nanosystems. *Science, 302* (2003) 1377–1379.
39. DeHon A., Lincoln P., Savage J. E., Stochastic assembly of sublithographic nanoscale interfaces. *IEEE Trans. Nanotechnol., 2* (2003) 165–174.
40. Likharev K. K., Strukov D. B., CMOL: Devices, circuits, and architectures. In: *Introducing Molecular Electronics*, Cuniberti G., Fagas G., Richter K. Berlin, Germany: Springer, 2005, pp. 447–477.
41. Strukov D. B., Likharev K. K., Prospects for terabit-scale nanoelectronic memories. *Nanotechnology, 16* (2005) 137–148.
42. Beckman R., Johnston-Halperin E., Luo Y., Green J. E., Heath J. R., Bridging dimensions: Demultiplexing ultrahigh-density nanowire circuits. *Science, 310* (2005) 465–468.
43. Aswal D. K., Lenfant S., Guerin D., Yakhmi J. V., Vuillaume D., Self assembled monolayers on silicon for molecular electronics. *Anal. Chim. Acta, 568* (2006) 84–108.
44. Cerofolini G. F., Casuscelli V., Cimmino A., Di Matteo A., Di Palma V., Mascolo D., Romanelli E., Volpe M. V., Romano E., Steps farther toward micro-nano-mole integration via the multispacer patterning technique. *Semicond. Sci. Technol., 22* (2007) 1053–1060.
45. Ben Jamaa M. H., Cerofolini G., Leblebici Y., De Micheli G., Cost-efficient and CMOS-compatible fabrication of high-density poly-silicon nanowire crossbars with the multi-spacer patterning technique. In: *2009 VLSI Technology Symposium*, Kyoto, Japan, 2009.
46. Ben Jamaa M. H., Moselund K. E., Atienza D., Bouvet D., Ionescu A. M, Leblebici Y., De Micheli G., Fault-tolerant multi-level logic decoder for nanoscale crossbar memory arrays. In: *Proceedings of the 2007 IEEE/ACM International Conference on Computer-Aided Design*, IEEE Press, Piscataway, NJ, 2007, pp. 765–772.
47. Ben Jamaa M. H., Moselund K. E., Atienza D., Bouvet D., Ionescu A. M, Leblebici Y., De Micheli G., Variability-aware design of multilevel logic decoders for nanoscale crossbar memories. *IEEE Trans. Comput. Aided Des. Integr. Circuits Syst., 27* (2008) 2053–2067.
48. Ben Jamaa M. H., Atienza D., Leblebici Y., De Micheli G., A stochastic perturbative approach to design a defect-aware thresholder in the sense amplifier of crossbar memories. In: *14th Asia and South Pacific Design Automation Conference*, Yokohama, Japan, 2009.
49. Hochbaum A. I., Chen R. K., Delgado R. D., Liang W., Garnett E. C., Najarian M., Majumdar A., Yang P., Enhanced thermoelectric performance of rough silicon nanowires. *Nature, 451* (2008) 163–167.

50. Boukai A. I., Bunimovich Y., Tahir-Kheli J., Yu J.-K., Goddard III, W. A., Heath J. R., Silicon nanowires as efficient thermoelectric materials. *Nature, 451* (2008) 168–171.
51. Rashevsky N., *Mathematical Biophysics*, 3rd edn. New York: Dover, 1960.
52. Cerofolini G. F., Size, shape, growth and reproduction—Towards a physical morphology. *Solid Films, 79* (1981) 277–299.
53. Cerofolini G. F., The biomedium. Adsorbed water as a model for the aqueous medium, supporting life functions. *Adv. Colloid Interface Sci., 19* (1983) 103–136.
54. Ploegh H. L., A lipid-based model for the creation of an escape hatch from the endoplasmic reticulum. *Nature, 448* (2007) 435–438.
55. Gazit Y., Berk D. A., Leunig M., Baxter L. T., Jain R. K., Scale-invariant behavior and vascular network formation in normal and tumor tissue. *Phys. Rev. Lett., 75* (1995) 2428–2431.
56. Shlesinger M. F., West B. J., Complex fractal dimension of the bronchial tree. *Phys. Rev. Lett., 67* (1991) 2106–2108.
57. Simons M. J., Pellionisz A. J., Genomics, morphogenesis and biophysics: Triangulation of Purkinje cell development. *Cerebellum, 4* (2005) 1–9.
58. Mandelbrot B. B., *The Fractal Geometry of Nature*. New York: Freeman, 1982.
59. Pfeifer P., Avnir D., Chemistry in noninteger dimensions between two and three. I. Fractal theory of heterogeneous surfaces. *J. Chem. Phys., 79* (1983) 3558–3565; Erratum *80* (1984) 4573.
60. Avnir D., Farin D., Pfeifer P., Chemistry in noninteger dimensions between two and three. II. Fractal surfaces of adsorbents. *J. Chem. Phys., 79* (1983) 3566–3571.
61. Avnir D., Farin D., Pfeifer P., Molecular fractal surfaces. *Nature, 308* (1984) 261–263.
62. Hood L., Heath J. R., Phelps M. E., Lin B., Systems biology and new technologies enable predictive and preventative medicine. *Science, 306* (2004) 640–643.
63. Falconer K., *Fractal Geometry: Mathematical Foundations and Applications*, 2nd edn. New York: Wiley, 2003.
64. Cerofolini G. F., Narducci D., Amato P., Romano E., Fractal nanotechnology. *Nanoscale Res. Lett., 3* (2008) 381–383.
65. Stern E., Klemic J. F., Routenberg D. A., Wyrembak P. N., Turner-Evans D. B., Hamilton A. D., LaVan D. A., Fahmy T. M., Reed M. A., Label-free immunodetection with CMOS-compatible semiconducting nanowires. *Nature, 445* (2007) 519–522.
66. Tuteja A., Choi W., Ma M., Mabry J. M., Mazzella S. A., Rutledge G. C., McKinley G. H., Cohen R. E., Designing superoleophobic surfaces. *Science, 318* (2007) 1618–1622.
67. Kigami J., *Analysis on Fractals*. Cambridge, U.K.: Cambridge University Press, 2001.
68. Cerofolini, G., *Nanoscale Devices*. Berlin, Germany: Springer, 2009.

18

Patterning and Ordering with Nanoimprint Lithography

Zhijun Hu
Soochow University

Alain M. Jonas
Catholic University of Louvain

18.1 Introduction **18**-1
18.2 Nanoimprint Lithography **18**-3
18.3 Nanoshaping Functional Materials by Nanoimprint Lithography **18**-5
18.4 Controlling Ordering and Assembly Processes by Nanoimprint Lithography **18**-7
Ordering under Partial Confinement • Ordering under Full Confinement
18.5 Conclusions and Perspectives **18**-14
Acknowledgments **18**-14
References **18**-14

18.1 Introduction

Photolithography, which consists of etching locally a photosensitive polymer film spin-cast on a flat substrate (Figure 18.1, left column), is central to top-down micro- and nanofabrication methodologies. The image of a drawing is first projected on the film through a mask and possibly a set of lenses; subsequent development of the exposed regions, that is, removal of the exposed regions when a positive tone resist is used, results in the etching of the drawing in the polymer film (Rai-Choudhury 1997). This topographically patterned film then serves for further operations such as localized deposition of metals, etching of the underlying substrate, or ion implantation, which are basic processes for the fabrication of integrated circuits (IC) (Campbell 2001).

The need to increase the density of integration has resulted in a continuously decreasing size of the features to be lithographied. It is well known that a wave of wavelength λ is diffracted when passing through an opening of size a, and that the width of the central diffraction lobe is proportional to λ/a in the far-field limit (Born and Wolf 1980). Therefore, it does not come as a surprise that the resolution limit of photolithography is directly linked to the wavelength of the radiation used as well. Other factors also come into play (Campbell 2001) but need not interest us here. As a result, progress in downsizing photolithography led to a continuous decrease of λ, resulting simultaneously in rapidly rising costs (Resnick 2007). Starting from visible light, the trend thus went to deep UV, extreme UV (Wurm and Gwyn 2007), and soft x-ray lithography (Ueno 2007). In parallel, electron beam lithography (EBL) was developed to benefit from the short wavelength of accelerated electrons (Owen 1985, Suzuki 2007). However, EBL consists of scanning a beam of electrons over a film of an electrosensitive resist, which is essentially a serial process much slower than the all-at-once projection of a drawing. Therefore, EBL is restricted to niche uses such as research, low-volume production, or the fabrication of masks for photolithography.

The photolithographic process is actually more related to the etching technique used by artists to reproduce drawings than to the original lithographic technique. In etching, a film of wax is deposited on the surface of a metal plate. The artist removes locally the wax using a sharp stylus, and the metal plate is subsequently etched with acid where the wax is missing. The resulting metal plate is then used to reprint the drawing (bottom-left of Figure 18.1). Historically, other methods have been devised by mankind to reproduce drawings. Probably the oldest method is stamping, which can be traced back to prehistoric times when men and women of all continents inked their hands to impress the walls of caves. Traditional ink seals such as used in East Asia, known as 印章 in China, are remote descendants of this method. The stamping technique was also translated to micro- and nanotechnologies, in which it is currently known as microcontact printing (μCP) (Kumar and Whitesides 1993), the most prominent of the soft lithographic methods (Xia and Whitesides 1998, Xia et al. 1999, Gates et al. 2005). In μCP, a soft elastomer stamp is inked with a solution of a molecule capable to chemisorb on a substrate (Figure 18.1, central column). By pressing the stamp on the substrate, local grafting of the molecules ensues. The stamp softness is important to ensure conformal contact with the surface; however, it also results in undesirable sagging and deformation that usually limit μCP to the micrometer scale, even though higher resolutions were reported in favorable circumstances (Biebyuck et al. 1997, Odom et al. 2002). But more importantly, stamping methods only transfer a monolayer of ink on the surface of the substrate. The resulting drawing is thus



FIGURE 18.1 Schematic presentation of photolithography, microcontact printing, and nanoimprint lithography. The art drawings obtained by the corresponding historical drawing method are shown at the bottom. (Left) Doctor Faust, etching from Rembrandt, 1652; (center) a paleo-Indian handprint from Pedra Pintada, Brazil; (right) a Mesopotamian seal and its printout, *ca*. 1720–1650 BC, Syria.

essentially two-dimensional, as opposed to the three-dimensional nature of the topographically patterned polymer films used for integration technology. Therefore, μCP is more suited to create micrometer-scale chemical patterns that are used as platforms for bottom-up assembly processes (Mahalingam et al. 2004) or for the fabrication of arrays of biosensors (Kane et al. 1999), rather than for nanolithography.

Another ancient method of reproducing drawings is the embossing of soft materials such as paper, clay, or wax by hard seals. Historical records trace back to the kingdoms of Ancient Egypt and Mesopotamia, and there is evidence that seals were used as signatures in official Chinese documents before 220 BC. The method of embossing found its way in nanotechnology 5000 years after its initial discovery, where it is currently known as nanoimprint lithography (NIL) (Chou et al. 1995), hot embossing (Heyderman et al. 2000), or nanoembossing (Studer et al. 2002). NIL is a newcomer in the lithography field, since it was initially proposed in the mid-1990s only by Chou and coworkers (Chou et al. 1995, 1996); however, the method has rapidly attracted strong interest and is currently considered as one of the possible industrial options for reaching feature sizes below 30 nm (ITRS 2007). An overview of the method that consists of transferring a drawing in a polymer film by pressing a topographically patterned hard mold into the film (Figure 18.1, right column) is given in Section 18.2. Because NIL as such has already been reviewed extensively (Torres 2003, Guo 2004, Stewart and Willson 2005, Guo 2007, Resnick 2007, Schift and Kristensen 2007, Schift 2008), this section concentrates only on the most important features of the method required to understand the rest of the chapter. Note that NIL, like all other techniques mentioned above, leaves aside the issue of the fabrication of the master mold (or stamp for μCP, or mask for photolithography). Actually, the idea behind most advanced lithographic techniques is to fabricate masters by a slow, expensive but efficient technique such as EBL, and to replicate them in large numbers by a less expensive, more rapid method. This is not basically different from printing or stencil techniques, which also create one template from which many copies are produced. Obviously, the wear of the master is a potentially serious problem that is certainly more significant for methods involving a direct contact between the master and the film to be patterned, as in NIL or μCP.

The main advantages of NIL as a lithographic technique are the relatively limited cost of the method, its high throughput, and its capacity to reach very small feature sizes. But there is intrinsically more to NIL than simply the fabrication of three-dimensionally patterned polymer films for integration technology. NIL is basically a molding technique acting at the nanometer scale, which can thus be used to shape functional materials into nanowires, nanopillars, or other useful nanoobjects. This new trend is reviewed in Section 18.3. Even more interestingly, NIL can also be used as a way to control ordering processes (such as crystallization) at the nanometer scale. In this case, not only is the shape of the nanoobjects controlled during embossing but also their internal structure, which may give rise to enhanced performance compared with macroscopic materials. Recent examples of this promising emerging trend are given in Section 18.4. NIL is thus progressively moving from a purely lithographic method to a real polymer nanoprocessing tool, which might well be the niche where NIL will thrive in the future.

Before closing this section, it is useful to mention an interesting parallelism between the historical development of microscopy and lithography. Microscopy began with optical microscopes that are limited by diffraction to a spatial resolution of about λ/2 (Bergmann and Schaefer 1999), except when special setups are used in combination with fluorescent molecules (Klar et al. 2000). Higher resolutions are attained by decreasing the wavelength, leading to electron microscopes and soft x-ray microscopes (Chao et al. 2005). This clearly parallels the evolution of photolithography. However, the diffraction limit can also be beaten by changing entirely the principle of operation of the microscope. This is the case of scanning probe microscopes, in which a sharp tip is placed in contact or close to contact with a surface. In atomic force microscopy (AFM), for instance, the local force experienced by the tip is translated into an image in a way that depends on the specific mode of the operation selected (Kalinin and Gruverman 2007). The main point in the present context is that images of very high resolution can be obtained by switching from a wave-based imaging process to a contact-mode imaging process. This is not unlike the switch from a photolithography-based process to an embossing-based process. The comparison is even stronger when one realizes that AFM tips can be used as mechanical tools to orient polymer molecules (Leung and Goh 1992), just as NIL is shown in Section 18.4.

18.2 Nanoimprint Lithography

Contrarily to photolithography and EBL, NIL replicates a relief pattern in a heated thermoplastic or in a thermosetting polymer by mechanical deformation, rather than by a local photo- or electrochemical modification of the resist. The pattern is then frozen by cooling down or cross-linking the polymer. A schematic drawing of the original NIL process that was proposed for thermoplastic polymers is shown in Figure 18.2a (Chou et al. 1997). A thin film of an amorphous thermoplastic polymer is cast onto a rigid surface. The polymer film is softened by heating above its glass transition temperature. A rigid mold bearing nanoscale features is then pressed into the polymer film until the polymer flows into the recesses of the mold. The polymer film is finally hardened by decreasing the temperature below the glass transition, before the mold is removed. A thickness contrast is thus created in the polymer film after imprinting. A thin residual layer of polymer is most often intentionally left between the protrusions of the mold and the substrate in order to prevent direct impact of the hard mold on the substrate and thereby protect the fragile protrusions of the mold (Guo 2007). This residual layer is then removed by an anisotropic O_2 plasma etching process, which completes the pattern replication. However, Schulz et al. (2003) have concluded from a study of local mass transport and its effects on pattern replication that for optimal performance, the initial film thickness should be selected so as to have less than 100% filling of the mold cavities, which corresponds to nearly zero residual layer thickness.

As can be realized, a very attractive aspect of NIL is its intrinsic simplicity: the basic elements needed for NIL are limited to (1) a mold with a relief comprising a large number of nanofeatures, (2) a suitable resist such as a thermoplastic polymer that can be softened during imprinting and hardened after imprinting, and (3) a printing equipment setup allowing some control of process parameters such as temperature and



FIGURE 18.2 (a) Schematic drawing of the originally proposed NIL method. (b) SEM image of a mold with pillars of 10 nm lateral size and 60 nm height. (c) SEM image of the corresponding array of holes imprinted in a PMMA film. (Reprinted from Chou, S.Y. et al., *J. Vac. Sci. Technol. B*, 15, 2897, 1997. With permission.)

pressure. NIL is thus cost-efficient compared with other lithographic methods, while at the same time offering a good performance with respect to resolution and throughput. Unlike the development of photolithography and EBL, the lack of expensive optical components and light sources makes it much easier to construct an imprint setup. To meet the requirements of an NIL process, one needs only a well-controlled heating and cooling system and a setup for applying pressures. There are now many different companies selling NIL equipment, such as Obducat, EVGroup, or Süss MicroTec in the European Union, and Nanonex in the United States.

The mold used in NIL can essentially be any type of solid material that has a good mechanical strength and reasonable durability, and is usually made of silicon, dielectric materials such as silicon dioxide or silicon nitride, metals such as nickel, or even polymeric materials that are harder than the resist (Guo 2007). The desired nano- or microscale features defined on the molds are produced by any other lithographic processing such as photolithography, EBL, or even NIL itself, followed by localized metal deposition, reactive ion etching of metal-uncovered regions, and metal removal. In order to facilitate the separation of the mold from the substrate after imprinting, an anti-adhesion layer is normally coated on the mold surface. The requirements for this layer are that its interfacial tension with the imprinted material be large, whereas its surface tension in air be low. This favors the separation of the mold and imprinted material for thermodynamic reasons. Therefore, the most widely adopted approach is to form a self-assembled monolayer of a partially perfluorinated silane (e.g., 1*H*,1*H*,2*H*,2*H*-perfluorodecyltrichlorosilane) on the mold surface, preferably by a vapor-phase reaction (Jung et al. 2005). Mixtures of mono- and trichloro-perfluorinated silanes were also proposed (Schift et al. 2005). Perfluorinated organic materials are interesting because of their low surface tension in air and known incompatibility with hydrocarbons that favors a high interfacial tension with most polymers.

The imprinting resists used in NIL are typically thermoplastic amorphous homopolymers such as poly(methyl methacrylate) (PMMA), polycarbonate (PC), and polystyrene (PS). One common feature of these thermoplastic materials is that their viscosity and elastic modulus are significantly reduced by increasing the temperature above their glass transition temperature, T_g. Hence, the polymer viscoelastic fluid can be forced to flow into the recesses of the mold under a pressure of a few tens of bar and to conform exactly to the surface relief of the mold. As a rule of thumb, the pressure ranges usually from 10 to 100 bar and the imprint temperature is most often ~70°C–90°C above the T_g of the imprinted polymers. The polymer fluid can be easily hardened by cooling back to below T_g to freeze the imprinted nanostructures.

One key parameter for the selected polymer is its molar mass M that controls physical properties such as the glass transition temperature, the stiffness, the strength, and the viscosity (Gedde 1995). For instance, the viscosity scales as $M^{3.4}$ above some critical M_e, below which entanglements between chains do not exist in the melt (Rubinstein and Colby 2003). The pressure, imprinting times, and/or imprinting temperatures have therefore to be significantly increased for polymers of higher molar mass. Both printing temperature and pressure should be kept as low as possible in view of the time needed for temperature and pressure cycling. It is thus favorable to work with polymers of lower M, hence lower viscosity. However, because amorphous polymers of molar mass lower than M_e are brittle, they are not suitable for nanoimprinting. Typically, M_e is in the 10,000 g mol^{-1} range for styrenic and methacrylate amorphous polymers (Rubinstein and Colby 2003). Note also that the distribution of molar mass and the topology of the polymer (e.g., presence of long chain branches or cyclic chains) are important parameters with respect to rheological properties; these may thus be tuned for optimal throughput.

One unique advantage of NIL is that its resolution is not limited by factors such as light diffraction, scattering, and interference in the resist. The resolution limit of NIL can be smaller than the radius of gyration of polymer chains that is on the level of a few or a few tens of nanometers depending on molar mass. Figure 18.2b and c shows scanning electron microscopy (SEM) images of a mold with 10 nm diameter pillars and the replicated 10 nm hole array in PMMA (Chou et al. 1997), showing that indeed NIL can be used as a high-resolution nanolithographic technique.

Since the first report on NIL, the method has attracted strong interest from both industry and academia due to its merits such as high-resolution, low-cost, and inherent high-throughput resulting from parallelized processing. For lithography purposes, however, one of the drawbacks of the originally proposed NIL process is the thermal cycle that limits the throughput for semiconductor IC manufacturing. A variation of the NIL technique that uses a transparent mold and low-viscosity UV-curable monomers that cross-link upon UV exposure (step and flash imprint lithography, SFIL) was developed soon after (Ruchhoeft et al. 1999), allowing the process to be carried out at lower pressures and room temperature. Since the thermal cycle is avoided, SFIL is much faster than thermal NIL which makes it very attractive for the manufacturing of semiconductor IC devices (Resnick et al. 2003). Other variations include solvent-assisted NIL, in which the polymer is softened by a solvent vapor, and imprinting is performed at room temperature (Khang et al. 2001, Voicu et al. 2007).

In order to optimize the NIL process or widen its applications, understanding the cavity-filling process during imprinting is essential. At first sight, the initial step in the process of NIL is very similar to the technique of hot embossing, in which a polymer layer is thermally deformed using a rigid mold. However, with ever smaller feature sizes and increasingly complex mold geometries, the behavior of the thin polymer film during both molding and demolding becomes more complicated. The cavity fill process can be understood in first approximation as a squeeze flow, as shown in Figure 18.3a (Heyderman et al. 2000). Initially, the polymer flows on the cavity walls and wets them. The material in the center of the cavity is under compressive stress, causing a convex profile to form. The polymer surface thus raises and eventually touches the top of the cavity. Because squeeze flow, electrostatic interactions between the mold and polymer, capillary forces, van der Waals forces between the mold and the substrate



FIGURE 18.3 (a) Scheme of the forces acting on a polymer film during the filling of a cavity. (Reprinted from Heyderman, L.J. et al., *Microelectron. Eng.*, 54, 229, 2000. With permission.) (b) Cavity fill process depending on the ratio of cavity width to film thickness. (Reprinted from Rowland, H.D. et al., *J. Micromech. Microeng.*, 15, 2414, 2005. With permission.)

across the polymer fluid, and surface tensions appear in the balance of forces (Schift et al. 2001), a variety of self-organization phenomena can be triggered during imprinting, resulting sometimes in the formation of different undesirable patterns such as pillars, fractal-like patterns, and viscous fingers. Rowland et al. (2005) have investigated by numerical simulation the impact of polymer properties, mold geometry, and process conditions on the cavity-filling process. When the polymer flows vertically into an open cavity during imprinting, the polymer can deform either as a single peak centered in the cavity or as a dual peak where each peak remains close to the vertical sidewalls, depending upon geometry, as shown in Figure 18.3b. The ratio of cavity width to film thickness determines single versus dual-peak cavity filling, regardless of the absolute size of the features and also of the pressure or temperature applied during embossing.

18.3 Nanoshaping Functional Materials by Nanoimprint Lithography

It is important to note that the cavity fill process of NIL only moves the macromolecules of the imprinted resist from one place to another. The chemical properties of the imprinted resist are thus kept after imprinting, contrary to conventional lithography where a pattern is generally created by the irradiation-induced reaction of organic materials. Therefore, NIL can be adapted directly to pattern or shape of a wide range of relatively fragile materials such as functional polymers and biological macromolecules instead of photo- or electroresists. In this respect, NIL is attracting increasing attention for its ability to shape directly functional materials into nanostructures. NIL can therefore be used as an efficient nanoprocessing tool to shape a material for applications, requiring a synergy between its topography and its functional properties. NIL was therefore used

1. *To generate nanopores in materials*: The demand for low dielectric constant (low *k*) materials in the microelectronics industry has recently led to considerable interest in porous materials, especially nanoporous materials (Maier 2001). Imprinting can be used to create pores into a thin film of a dielectric material and therefore decreases its dielectric constant. For instance, Soles et al. demonstrated the direct patterning by NIL of sub-100 nm features into porous spin-on organosilicate glass materials (Ro et al. 2007, 2008).
2. *To shape the interface between two functional materials*: In organic heterojunction solar cells, the interface between donor and acceptor materials is crucial. This interface could be tailored by NIL. A thin film of conjugated polymer (serving as acceptor) was first imprinted in a controlled atmosphere (low vacuum or inert gas). Well-defined nanoscale structures were thus created in the acceptor layer. The other component (donor) of the system was then poured in the created trenches (Kim et al. 2007, Cheyns et al. 2008 and Aryal et al. 2008). The fill factor and power conversion efficiency were correspondingly increased.
3. *To create optical gratings in light-emitting materials*: Within recent years, organic dye-doped or conjugated polymer laser devices have received much attention as convenient and compact light sources. One of the important issues to make polymer lasers is the fabrication of a periodic surface relief in the conjugated or dye-doped polymers, with a period close to the wavelength of light. The periodic relief can modify the generation and propagation of light in these materials by interference effects. Chou et al. were the first to apply NIL to directly shape organic light-emitting materials, such as Alq3 (8-hydroxyquinoline aluminum) doped with DSMII dye molecules, or their blends with PMMA (Wang et al. 1999). Figure 18.4a shows AFM images of the resulting Alq3/DSMII gratings of 300 nm period. It was demonstrated that no degradation of the light emission efficiency is caused by the NIL process (Figure 18.4b). In addition, because the small dye molecules embedded in the PMMA matrix are slightly aligned by the imprinting process (see Section 18.4), an anisotropic photoluminescence behavior was observed (Wang et al. 2000).

Subsequently, Guo et al. (2002) successfully imprinted two-dimensional photonic crystal nanostructures in nonlinear optical dye-doped polymers. Pisignano et al. (2003, 2004) and Mele et al. (2005, 2006) showed that conjugated polymers and oligomers can be directly imprinted at room temperature under a very high pressure, based on the plastic deformation of the polymer. Figure 18.5a is an AFM image of a room temperature-imprinted organic semiconductor thin film. A study of the optical properties before and after imprinting (absorbance, luminescence, and quantum yield) again ruled out the possible degradation of the active materials even when imprinting was performed in air (Figure 18.5b). The imprinting of



FIGURE 18.4 Optical grating imprinted by NIL in a light-emitting material. (a) AFM height image of Alq3/DMSII gratings with a period of 300 nm. (b) The measured luminescence spectral intensity before and after imprinting, demonstrating the absence of sample degradation. (Reprinted from Wang, J. et al., *Appl. Phys. Lett.*, 75, 2767, 1999. With permission.)



FIGURE 18.5 Optical grating imprinted by NIL at room temperature in a light-emitting organic semiconductor. (a) AFM height image of the surface grating with a period of 400 nm. Image side: 10 μm. (b) Absorbance and integrated photoluminescence spectra before (line) and after (circles) imprinting, showing the absence of degradation. (c) Photoluminescence spectra at a selected emission angle, showing the presence of an interference peak after imprinting (circles) compared with the uniform film (line). The interference peak is due to the surface grating. (Reprinted from Pisignano, D. et al., *Adv. Mater.*, 16, 525, 2004. With permission.)

a surface periodic grating with wavelength-scale periodicity enhances the light emitted in specific directions due to interference effects (Figure 18.5c), and reduces the effective length covered by the photons in the material and thus the self-absorption inside the organic slab. These interference effects were subsequently used to build a distributed feedback (DFB) laser, wherein the surface grating serves to produce a narrow band of wavelengths by interference. Figure 18.6 displays the photoluminescence spectrum of such a DFB laser obtained by NIL using the conjugated light-emitting polymer (poly[2-methoxy-5-(2-ethylhexyloxy)-1,4-phenylenevinylene]) (MEH-PPV), showing a narrow emission at about 630 nm wavelength.

4. *To create antireflective structures on the surface of optical materials*: Two-dimensional antireflection subwavelength structures were also created by NIL on the surface of thin films in order to suppress Fresnel reflection. Fresnel reflection is a drawback for many optical systems, since it reduces the fraction of transmitted light, deteriorates the contrast of displays, and generates ghost images in imaging systems (Ting et al. 2008a,b). Surface relief gratings with periods smaller than the wavelength of light, named subwavelength gratings, may behave as antireflection surfaces. Figure 18.7a is an SEM image of antireflective PMMA nanostructures fabricated by NIL. The optical properties of a plain PMMA sheet with the ones of a patterned PMMA sheet are shown in Figure 18.7b, showing a significant reduction of glare after imprinting.
5. *To shape biomaterials*: Ohtake et al. (2004) reported that DNA can be directly patterned by NIL; interestingly, the patterned DNA retains its activity, showing that these biomacromolecules can withstand the relatively harsh processing conditions of NIL. Park et al. (2007) showed that chitosan, a derivative of a natural polysaccharide, can also be directly patterned by NIL at low temperature



FIGURE 18.6 (a) AFM height image of MEH-PPV gratings with a period of 600 nm patterned directly by NIL. (b) Distributed feedback emission spectra under pulsed excitations of increasing dose. The narrow band of wavelengths emitted at about 630 nm results from interference from the surface grating. Inset: the influence of excitation dose on the DFB emission intensity. (Reprinted from Mele, E. et al., *Appl. Phys. Lett.*, 89, 131109, 2006. With permission.)



FIGURE 18.7 (a) SEM image of PMMA films with imprinted antireflective nanostructures. (b) Comparison between a bare PMMA sheet and the imprinted PMMA sheet, showing an obvious damping of backlight glare. (Reprinted from Ting, C.-J. et al., *Nanotechnology*, 19, 205301, 2008a. With permission.)

and low pressure. The nanoimprinted chitosan patterns contain a large amount of primary amino groups for further chemical modification, and can be used, for instance, to graft proteins and DNA strands for biosensing purposes.

Interestingly, nanoshaping of functional *inorganic* materials is also possible by NIL. For instance, Grigoropoulos et al. (Ko et al. 2007, Park et al. 2008) demonstrated the direct nanoimprinting of thin films of gold nanoparticles. Because of their small size (2–3 nm), the nanoparticles start to melt at ~130°C–140°C, well below the melting point of bulk gold. A variety of gold nanostructures were fabricated, such as nanodots, nanowires, and serpentine nanowire arrays, showing the potential of the method for the direct fabrication of electrodes for nanoscopic devices. Imprinting of soft precursors of inorganic crystals and glasses was also reported, showing the possibility to use NIL to fabricate ceramic or inorganic glass nanostructures (Harnagea et al. 2003, Okinaka et al. 2006, Peroz et al. 2007). Finally, direct imprinting of silicon wafers was also achieved via laser-induced transient liquefaction of the imprinted material (Chou et al. 2002).

18.4 Controlling Ordering and Assembly Processes by Nanoimprint Lithography

As mentioned in Section 18.1, the application of NIL to organic materials such as semicrystalline polymers or liquid crystalline oligomers is capable to control the internal structure of the resulting nanoobjects. Consider semicrystalline polymers as an example. These materials crystallize in ~10 nm thick lamellar-shaped crystals, in which the chains are perpendicular or slightly inclined to the lamellar surface, and when emerging from the crystal surface either fold back in the same lamella or reenter a neighboring quasi-parallel lamella (Figure 18.8) (Gedde 1995, Reiter and Strobl 2006). The lateral sizes of polymer lamellae are in the micrometer range, and the lamellae are elongated in the preferred growth direction of the crystal. Successive lamellae are separated by amorphous interlayers, which accommodate the folds, loose loops, tie segments, and dangling ends of the chains (Mandelkern 1979, Gautam et al. 2000). The crystallization process occurs through nucleation from a central seed, most often an impurity (Wunderlich 1976), from which a complex assembly of lamellae forms by crystal growth, branching, and splaying (Bassett 1984). The resulting so-called spherulite has a radius in the micrometer range, and the preferred growth direction of the lamellae is essentially radial within the spherulites. Hence, at the supraspherulitic scale, semicrystalline polymers are isotropic, and consist of an intricate mixture of crystallized and amorphous nanoregions. Therefore, their properties are averages of different phases over all possible orientations, and include components resulting from the numerous crystal–amorphous interfaces present in a spherulite. This significantly reduces the performance of such materials.

Consider now the possible effects of NIL on such a complex morphology. Embossing is performed in the molten state, but the polymer crystallizes in the mold during cooling. First, the nucleation process could be affected, because NIL splits the melt into a very large number of small cavities. Since the probability to find a heterogeneous nucleating seed in a cavity depends on the product between the volume of each nanocavity and the number density of nucleating seeds in the melt, this probability may be well below 1. If so, crystallization in the nanocavity will either require the spontaneous formation of a nucleating germ in the melt, a process called homogeneous nucleation rarely encountered in practice when crystallizing bulk polymers, or the propagation of a crystal from the outside into the nanocavity (if the cavity is not totally isolated), which will only be possible when a nearby crystal grows in the proper orientation. The situation is similar to the one encountered when crystallizing polymers in microdroplets (Cormia et al. 1962, Massa and Dalnoki-Veress 2004), in microdomains of phase-separated block copolymers (Reiter et al. 2001, Loo et al. 2002, Muller et al. 2002), or in the nanopores of membranes (Steinhart et al. 2006, Woo et al. 2007), cases for which retarded crystallization and preferred orientation are often reported. One can thus expect identical effects to occur in NIL as well.



FIGURE 18.8 Scheme of the morphology of semicrystalline polymers seen at different length scales, showing spherulites (top-left image), stacks of lamellae (bottom-left image), lamellar crystals and amorphous interlayers (bottom-right image), and crystalline stems (top-right image).

Second, the crystal growth process might also be affected. It was demonstrated for the first time in Russia in 1972 (Sheftal and Bouzynin 1972), and rediscovered later in the United States (Smith and Flanders 1978), that topographically patterned amorphous surfaces may induce preferential orientation of growing crystals, provided the symmetry of the topography be adapted to the habit of the growing crystals. This phenomenon is known as “graphoepitaxy” or “artificial epitaxy” (Givargizov 1994, 2008), with reference to the epitaxy of crystals on crystalline substrates, where matching between the lattice planes of the growing crystal and of the substrate provides for preferential orientation. In graphoepitaxy, however, the matching occurs at a higher level and does not require a crystalline substrate. Key thermodynamic parameters are the shape of the growing entity and the symmetry of the substrate topography, as well as the surface tensions and surface tension anisotropies of the crystal–substrate and melt–substrate interfaces, which dictate the energy balance of the growing system (Mouthuy et al. 2007). On the kinetic side, the growth rates of the crystal along specific crystalline directions are also important parameters because they control the crystal shape, hence the graphoepitaxial matching. In the present context, the topography of the NIL mold may thus control graphoepitaxially the crystallization process of the polymer, resulting in a preferential alignment of specific crystallographic directions with respect to the nanofeatures of the mold.

A third factor that could affect the crystallization process in a NIL experiment is the degree of chain alignment that results from the melt embossing process. Polymers are viscoelastic fluids, which may keep for a long time a partial memory of the considerable squeeze flow experienced during the imprinting. In addition, polymer chains tend to align along flow lines during processing. This favors oriented crystallization (Miller 1979, Kumaraswamy et al. 1999, Somani et al. 2000) and the emergence of specific morphologies such as “shish-kebabs,” in which long crystalline nanofibers made of aligned chains (the “shishes”) serve as nuclei for oriented lamellar crystals (the “kebabs”) (Eder et al. 1989, Kimita et al. 2007). In NIL, the residual degree of chain alignment will depend on the molar mass of the polymer, on its previous processing history, and on its annealing time in the melt before crystallization. Note that chain orientation under flow is not easy to predict at the nanometer scale, since molecular confinement of the chains in a thin film leads to a substantially perturbed rheological behavior (Rowland et al. 2008).

A fourth factor is confinement itself. Most macromolecules have radii of gyration in the 10–50 nm range, close to the thickness of films used in NIL and to mold feature sizes, resulting in strong confinement of the chains. There is currently an ongoing discussion in the literature regarding the way confinement affects polymer properties such as glass transition and segmental mobility (Ellison and Torkelson 2003, Alcoutlabi and McKenna 2005) or whole chain motion (Rowland et al. 2008). Conflicting results have been published, and it is not possible to review them fairly in the present chapter. Instead, one should keep in mind that the conformation and dynamic properties of confined polymers may be substantially different in a nanocavity than in the bulk, which is likely to modify their crystallization behavior as well. Think only of the need that chains fold back and forth to form lamellar crystals (Figure 18.8). If this occurs in a space only slightly larger than the intrinsic lamellar thickness, significant perturbations of the crystallization process are clearly to be expected.

What is true for polymer crystallization should also be valid for other supramolecular assembly processes, such as the formation of liquid crystalline domains or the ordering of block copolymer mesophases. In the sequel, we will review the results obtained in this emerging field, for a range of systems such as amorphous rigid polymers, liquid crystalline polymers, semicrystalline polymers, and phase-separated block copolymers. NIL will be shown to be unique in its ability to orient crystals and chains in specific directions, resulting in favorable cases in a significant improvement of the performance of nanodevices. The results will be divided in two classes: NIL under either full or partial confinement. In the first case, the starting film thickness and the height of the protrusions on the mold are such that the mold can touch the surface of the substrate if pressed strongly enough (Figure 18.9). For a mold having a protruding surface fraction σ, each protrusion being of height h, full confinement will only be possible when the starting film thickness $d < (1 - \sigma)h$. Under this circumstance, each recess of the mold will be effectively isolated from other recesses. In contrast, when $d > (1 - \sigma)h$, a continuous residual film always remains between the substrate and the protruding features of the mold, no matter how hard the mold is pressed in the film (Schift and Heyderman 2003). In this case, information on the ordering process may propagate from recess to recess, which will have significant consequences on the global ordering of the sample.

18.4.1 Ordering under Partial Confinement

The first experimental demonstration of molecular alignment by NIL was obtained for chromophores dissolved in a standard PMMA resist, using line gratings as molds (Wang et al. 2000). Polarized photoluminescence and absorption measurements indicated that the dye molecules are aligned after imprint with their long axis along the grating lines, most probably due to the effect of flow during processing. The fluorescence anisotropy, $R = (I_{//} - I_{\perp})/(I_{//} + 2I_{\perp})$, quantifies the degree of alignment by comparing the fluorescence emission polarized parallel to the grating lines ($I_{//}$) and perpendicular to them ($I_{\perp}$). R values of 1 correspond to complete alignment, whereas $R = 0$ for isotropic systems. From the reported dichroic ratios $DR = I_{//}/I_{\perp}$, R values of 0.1–0.2 can be computed for this specific example, which shows that the polymer flow is able to align the dye molecules only moderately.

For semicrystalline polymers crystallized in partial confinement, no or limited preferential orientation of polymer crystals occurs when line gratings are used as molds (Hu et al. 2005, Okerberg et al. 2007). Thin films of poly(vinylidene fluoride) (PVDF, α-phase) crystallize in a normal spherulitic morphology and appear to be insensitive to the presence of the grooves of the NIL mold (Hu et al. 2005). The crystalline lamellae propagate from groove to groove, and the electron diffraction patterns do not show preferred orientation relative to the line grating direction (Figure 18.10). This can be ascribed to fast crystal growth in the thin residual film below the protrusions of the mold, from which crystallization propagates into the linear grooves of the mold. The final morphology is thus not dictated by the mold, but mainly by the processes occurring in the residual film. Similar results were obtained for poly(ethylene oxide) (PEO) (Okerberg et al. 2007), although partial elongation of the crystalline lamellae along the grooves of the mold was sometimes observed. As is readily apparent in Figure 18.11a, the global spherulitic shape is not affected by



FIGURE 18.9 Two configurations of NIL leading to different microstructures after imprint. For clarity, the mold was placed at the bottom of the drawing.



FIGURE 18.10 Microstructure of PVDF (α-phase) crystallized in NIL line grating molds under partial confinement (left: transmission electron micrograph; right: atomic force microscopy topograph). No preferential alignment is obtained, as shown by the arrows that highlight the direction of a few lamellar crystals. (Adapted from Hu, Z. et al., *Nano Lett*., 5, 1738, 2005.)

the NIL mold, and lamellae are found growing either perpendicular to the grooves (zone 1 in Figure 18.11a and b) or parallel to them (zone 2 in Figure 18.11a and c), depending on the orientation of the radius of the spherulite with respect to the line grating direction. These results clearly indicate that chain alignment by the flow is not sufficient to induce oriented crystal growth and that graphoepitaxy of semicrystalline polymers does not occur in partial confinement.

The situation is somewhat different when imprinting a low molar mass liquid crystalline conjugated polymer, poly(9,9-dioctylfluorene-*co*-benzothiadiazole) (F8BT), in its liquid crystalline nematic mesophase (Zheng et al. 2007, Schmid et al. 2008). This green-light-emitting polymer displayed after imprinting *R* values as large as 0.97, indicating that most polymer chains are aligned parallel to the line grating direction. The order parameter *R* was found to increase for thinner films, suggesting that the ordering starts from the surface of the mold and progressively vanishes when going down into the residual film. Polymer-light-emitting diodes (PLEDs) were successfully built based on nanoimprinted F8BT, giving rise to the emission of preferentially linearly polarized light (Figure 18.12). A field-effect transistor was also realized, and the hole mobility was 10–15 times larger parallel to the grating lines than perpendicular to them. These results directly illustrate the beneficial impact of aligning molecules, as far as charge mobility or emission polarization is concerned. It should,



FIGURE 18.11 Microstructure of PEO crystallized in NIL grating molds under partial confinement. Panel (a) is an optical micrograph displaying a spherulite; the vertical stripes indicate the direction of the lines of the grating used to imprint the sample. Panels (b) and (c) are AFM topographic images corresponding to the regions 1 and 2 of panel (a), respectively, and show different relative orientations of the lamellae compared with the line grating direction. (Reprinted from Okerberg, B.C. et al., *Macromolecules*, 40, 2968, 2007. With permission.)



FIGURE 18.12 (a) Electroluminescence of a PLED made of F8BT imprinted in partial confinement with a line grating. The luminescence is measured through a polarizer parallel (circles) or perpendicular (triangles) to the grating lines. (b) Optical images of the electroluminescent device seen through a polarizer oriented with respect to the grating lines as indicated in the figure. (c) Schematic drawing of the PLED structure. (Reprinted from Zheng, Z. et al., *Nano Lett*., 7, 987, 2007. With permission.)

however, be noted that NIL failed to align a similar light-emitting conjugated polymer, poly(9,9-dioctylfluorene) (F8) also displaying a liquid crystalline nematic mesophase (Song et al. 2008). This was tentatively ascribed to the higher molar mass (hence larger viscosity) of this polymer compared with F8BT. Clearly, NIL under partial confinement is able to align liquid crystalline polymers in favorable circumstances; however, further work is required to fully understand the factors which control this alignment that are probably similar to the ones driving the alignment of liquid crystals on buffing layers (Toney et al. 1995).

18.4.2 Ordering under Full Confinement

When the starting film thickness is small enough for the NIL mold to enter in contact with the substrate, full confinement arises (Figure 18.9b). In this case, the propagation of information from groove to groove is suppressed, and complete graphoepitaxial alignment happens as is demonstrated below. It is critical to realize that graphoepitaxial alignment occurs at some stage during the formation of a structure, depending on the details of the processing history. It may thus orient a growing crystal, or a liquid crystalline domain, or even a single molecule, depending on the basic structural element that interacts with the mold. The notion of basic structural element is thus key to understand and reconcile the results published in the literature, and will serve us as guide in the sequel.

When a *semicrystalline* polymer crystallizes from the isotropic melt in a NIL line grating mold, the basic structural element to consider is the *nascent crystal*. Because polymer crystals are usually elongated along their fast growth axis direction, alignment of this crystal axis along the grating lines is favored for geometrical reasons. This is, for instance, the case for PVDF crystallized in complete confinement in its orthorhombic α-form (Hu et al. 2005), whose fast b-axis is found by electron diffraction to align parallel to the grooves of the NIL mold (Figure 18.13a). Interestingly, when NIL molds containing curved grooves are used, the b-axis follows these curved tracks (Hu and Jonas, unpublished). This can only be possible if the resulting curved nanowires are polycrystalline. Note that graphoepitaxy in linear channels only aligns one crystal axis, leaving open the issue of the rotation of the crystal about this axis. It was found for NIL-imprinted α-PVDF that the chain c-axis is perpendicular to the substrate for films below about 100 nm (flat-on lamellae), whereas in thicker films, the crystals have their chain c-axis parallel to the substrate (edge-on lamellae) (Hu and Jonas, unpublished). In both cases, however, the b-axis remains parallel to the grooves. The variation from a flat-on to an edge-on orientation upon increasing film thickness is frequent with polymers and was tentatively rationalized recently (Wang et al. 2008).

For polymers imprinted in a *liquid crystalline phase*, then cooled into their crystalline phase, the basic structural element to consider differs depending on the detailed microstructure of the liquid crystalline phase. Poly(9,9-dioctylfluorene) (F8) was imprinted in its nematic liquid crystalline phase, in which chain axes tend to orient parallel to a director with no other form of long-range ordering (Hu et al. 2007). Thus, the basic structural element is simply a *rod-like chain*, which for entropic and geometrical reasons aligns parallel to the grooves. After cooling and crystallization, the preferential ordering is maintained, and the chain axis (which is the c-axis in the low-temperature crystal phase) remains parallel to the grooves, hence to the axis of the resulting nanowire (Figure 18.13b). The preferential alignment translates into polarized light emission, with an R factor of 0.65–0.7 testifying for a high degree of ordering. This is in stark contrast with the absence of preferential ordering reported when F8 was imprinted in partial confinement (Song et al. 2008), and shows the importance of full confinement for NIL-induced graphoepitaxy.

The semiconducting poly(3,3‴-didodecyl-quaterthiophene) (PQT) was also imprinted in its liquid crystalline phase under full confinement (Hu et al. 2007). PQT chains form in the liquid crystalline phase supramolecular rod-like nanostructures, in which extended chains pack with their π-stacking direction along the rod axis. The basic structural element is thus the *rod-like nanostructure*, whose long axis aligns parallel to the grooves of the mold. As a consequence, the π-stacking direction is parallel to the axis of the imprinted nanowire, and this orientation is kept when the polymer crystallizes on cooling. Therefore, the b-axis of the crystal, which is the π-stacking direction, is similarly aligned at the end of the process (Figure 18.13c), whereas the chain c-axis direction is perpendicular to the nanowire axis. The situation is therefore entirely different from F8, where the chain axis was aligned parallel to the nanowire axis. In the present case, this specific crystal setting is interesting for applications, because the PQT b-axis is the axis of high carrier mobility. A nanowire-based field-effect transistor was thus realized by nanoimprint, and it was demonstrated that the hole mobility is increased by a factor of 1.7 along the nanowire axis compared with an isotropic PQT film. Essentially identical results were reported later for nanoimprinted poly (3-hexylthiophene) (P3HT), which adopts a similar morphology as PQT (Aryal et al. 2009).

For rigid conjugated *amorphous* polymers, which cannot crystallize and do not adopt a liquid crystalline phase, the basic structural element to consider during imprinting is simply their *Kuhn segment*. The flexibility of a polymer is quantified by its persistence length L_p (Grosberg and Khokhlov 1994), which is the average distance over which the local orientation of the chain persists. Real chains can be modeled as equivalent freely jointed chains having rigid (Kuhn) segments of length $b_K = 2L_p$ connected by freely rotating junctions (Rubinstein and Colby 2003). Conjugated polymers have large persistence lengths, and therefore long Kuhn segments. These will tend to align parallel to the groove direction during imprinting. The resulting nanowire thus contains chains whose axes are parallel to the nanowire axis, which is favorable for conductivity. For polypyrrole (PPy), for instance, the conductivity was improved by a factor of 1.7 in the imprinted nanowires compared with the isotropic film (Hu et al. 2007), and this was correlated to the preferential chain alignment observed by birefringence measurements (Figure 18.13d).

As a final example of graphoepitaxial alignment by NIL in full confinement, the supramolecular assembly of a phase-separated


(020)
250 nm
(020) = b
F–C–F
H–C–H
F–C–F
H–C–H
=
(a)
(008)
500 nm
(008) = c
=
n
C8H17
C8H17
(b)
(200)
(300)
(010)
500 nm
(010) = b
CH3
(CH2)11
=
S
S
S
S
n
(CH2)11
H3C
(c)
Chain axis
Decreasing width
Long axis of nanowires
200 μm
=
H
N
N
H
n
(d)

FIGURE 18.13 Selected examples of functional polymers aligned preferentially by NIL in complete confinement. The left column contains transmission electron microscopy images of (a) nanowires of PVDF, (b) electroluminescent F8, (c) semiconducting PQT, and (d) a polarized microscopy image of birefringent arrays of nanowires of conducting PPy (the nanowire axes are at 45° with respect to the polarizer and analyzer directions). Insets in (a)–(c) are the corresponding electron diffraction, showing the crystallographic axis aligned parallel to the line grating direction of the mold. The right column presents schematic drawings of the basic structural elements aligned during imprinting (a nascent crystal for semicrystalline PVDF, rod-like chains of the nematic liquid crystalline phase of F8, a supramolecular rod of π-stacked chains in the liquid crystalline phase of PQT, and chain segments of the amorphous PPy). (Adapted from Hu, Z. et al., *Nano Lett.*, 5, 1738, 2005; Hu, Z. et al., *Nano Lett.*, 7, 3639, 2007.)



FIGURE 18.14 SEM images of a (PS-*b*-PMMA) diblock copolymer imprinted in full confinement in its hexagonal mesophase. The PMMA cylinders were etched away after mold removal, showing the graphoepitaxial alignment of the mesophase. (Reprinted from Li, H.-W. and Huck, W.T.S., *Nano Lett.*, 4, 1633, 2004. With permission.)

block copolymer is presented (Li and Huck 2004). The selected poly(styrene)-*block*-poly(methyl methacrylate) (PS-*b*-PMMA) copolymer consists of flexible amorphous blocks, which do not align by themselves. However, due to the microphase separation of the two incompatible blocks, the PMMA regions form nanocylinders located on the nodes of a hexagonal lattice, within a continuous PS matrix (Hamley 1998). Such microphase-separated copolymers are known to form graphoepitaxially oriented supramolecular crystals (Cheng et al. 2006, Bita et al. 2008). They should thus also align in NIL. Here, the proper structural element is the unit cell of the supramolecular crystal, whose unit cell parameters are in the 10 nm range and above. The axes of the block copolymer unit cell were indeed found to be parallel to the direction of the grooves of the mold (Figure 18.14), although which axis is parallel to the grooves depends on the thickness of the starting block copolymer film (Li and Huck 2004). However, the regularity of the packing was limited, most probably because the dimensions of the grooves were not exactly adapted to the natural period of the block copolymer (Li and Huck 2004). Nevertheless, this example illustrates nicely how one can combine two lithographic techniques together, namely, NIL and block copolymer lithography, since the PMMA can be etched away with UV radiation after imprinting, giving rise to a second level of patterning.

So far, all examples given above referred to line gratings as molds. Other feature shapes can be selected, but the success or failure of graphoepitaxy will depend on the match between the intrinsic size of the basic structural element and the shape of the nanofeatures of the mold (Givargizov 1994). When square cavities are selected instead of grooves, it is obvious that one cannot expect anymore preferential alignment in the plane of the film. However, this does not preclude ordering effects from appearing. This was reported for a statistical copolymer poly(vinylidene fluoride-*stat*-trifluoroethylene) [P(VDF-TrFE)], which was imprinted in its paraelectric liquid crystalline phase, then crystallized by cooling into the ferroelectric pseudohexagonal β-phase (Hu et al. 2009). The mold consisted of square nanocavities about 100 nm in lateral size, allowing to shape the polymer film into a dense array of nanosquares (Figure 18.15a). As expected, there is no preferential orientation in the plane of the film after imprint; however, the polar *b*-axis is aligned almost vertically, and the crystalline perfection is improved. This results in a much lower voltage than usually required to switch the direction of the electrical dipole moment. Figure 18.15b is a map of local polarization acquired by piezoresponse force microscopy (PFM), after writing the word “FeRAM” with a positive or negative bias (5 V) in the array of P(VDF-TrFE) imprinted nanostructures. Interestingly,



FIGURE 18.15 Array of ferroelectric P(VDF-TrFE) nanostructures nanoimprinted in complete confinement. The orientation of the polar *b*-axis is close to vertical. (a) AFM topography. (b) Piezoresponse amplitude of the same region after local poling with a positive (bright letters) or negative (dark letters) 5 V voltage. The piezoresponse amplitude is proportional to the local electric dipole moment, and was measured by PFM. (Adapted from Hu, Z. et al., *Nat. Mater.*, 8, 62, 2009.)

when nanoimprinting is performed with micro- instead of nanometer-sized cavities, no preferential orientation of the *b*-axis is noted, and the performance of the device is not improved compared with the macroscopic film (Zhang et al. 2007). This underlines the importance of confining crystallization to dimensions comparable to the intrinsic crystal size for optimal results. This example also illustrates that the combination of shaping and crystalline improvement afforded by NIL is extremely useful for device development. Indeed, high-density arrays of ferroelectric polymer crystals exhibiting a low switching voltage are attractive for the development of cheap organic random-access memories. Such systems are considered to be superior to electrically erasable and programmable read-only memories and to Flash memories in terms of write-access time and power consumption (Sheikholeslami and Gulak 2000).

18.5 Conclusions and Perspectives

NIL is by now a well-established lithographic technique, expected to play a significant role in the development of semiconductor technology. Attractive features are the parallelism afforded by the methodology, its potential low-cost, its high resolution, its versatility toward a large range of materials, the possibility to mix it with photoresist technology, and its compatibility with integration technology. However, the potential of NIL as a method to control the shape and internal order of functional materials is only being realized currently. NIL was shown in this chapter to be able to shape functional materials into gratings, arrays, nanowires, and other interesting nanoobjects for applications in optics or microelectronics. Far from being limited to polymeric materials, NIL is further opening its application range to biomacromolecules, sol–gel precursors of inorganic ceramics and glasses, and even hard crystalline solids such as silicon. When applied to materials capable to self-organize or crystallize, NIL is also capable to orient graphoepitaxially the basic structural elements of the material, provided it be performed under full confinement. In much rarer cases such as for liquid crystals of low molar mass, partial confinement may also lead to preferential orientation. The control over the internal structure of nanomolded materials translates into improved device performance. Thus, it was shown that NIL-induced graphoepitaxy results in polarized light emission for electroluminescent polymers, increased mobility of charge carriers in semiconducting polymers, increased conductivity for conjugated conducting polymers, or easier switching of electrical dipole moments for ferroelectric materials. It was also demonstrated in this chapter that the principles governing graphoepitaxial orientation can be rationalized based on the knowledge of the structure of the material and on the notion of basic structural element. This should help device designers to predict the effects of NIL on the microstructure of materials, and therefore to use fully the power of this promising nanoprocessing method.

Acknowledgments

The authors acknowledge the generous financial support from the Wallonia Region (Nanolitho, Nanosens, and Nanotic projects), the French Community of Belgium (ARC Nanorg and Dynanomove), the Belgian Federal Science Policy (IUAP SC^2 and FS^2), the Belgian National Fund for Scientific Research, the Solvay company through the Fondation Louvain, and the European Commission (STREP Metamos, NoE FAME), which permitted part of the research mentioned here to be performed. Access to the WinFab clean rooms is also gratefully acknowledged, as well as stimulating discussions and collaborations with colleagues and students in UCLouvain and elsewhere, too numerous to be all cited here.

References

Alcoutlabi, M. and McKenna, G. B. 2005. Effects of confinement on material behaviour at the nanometre size scale. *J. Phys. Condens. Matter* 17: R461–R524.

Aryal, M., Buyukserin, F., Mielczarek, K., Zhao, X.-M., Gao, J., Zhakidov, A., and Hu, W. W. 2008. Imprinted larger-scale high density polymer nanopillars for organic solar cells. *J. Vac. Sci. Technol. B* 26: 2562–2566.

Aryal, M., Trivedi, K., Hu, W. W. 2009. Nano-confinement induced chain alignment in ordered P3HT nonostructures defined by nanoimprint lithography. ACS Nano 3: 3085–3090.

Bassett, D. C. 1984. Electron microscopy and spherulitic organization in polymers. *CRC Crit. Rev. Solid State Mater. Sci.* 12: 97–163.

Bergmann, L. and Schaefer, C. 1999. *Optics of Waves and Particles*. Berlin, Germany: Walter de Gruyter.

Biebyuck, H. A., Larsen, N. B., Delamarche, E., and Michel, B. 1997. Lithography beyond light: Microcontact printing with monolayer resists. *IBM J. Res. Dev*. 41: 159–170.

Bita, I., Yang, J. K. W., Jung, Y. S., Ross, C. A., Thomas, E. L., and Berggren, K. K. 2008. Graphoepitaxy of self-assembled block copolymers on two-dimensional periodic patterned templates. *Science* 321: 939–943.

Born, M. and Wolf, E. 1980. *Principles of Optics*, 6th edition. Oxford, NY: Pergamon Press.

Campbell, S. A. 2001. *The Science and Engineering of Microelectronic Fabrication*. New York: Oxford University Press.

Chao, W. L., Harteneck, B. D., Liddle, J. A., Anderson, E. H., and Attwood, D. T. 2005. Soft X-ray microscopy at a spatial resolution better than 15 nm. *Nature* 435: 1210–1213.

Cheng, J. Y., Zhang, F., Smith, H. I., Vancso, G. J., and Ross, C. A. 2006. Pattern registration between spherical block-copolymer domains and topographical templates. *Adv. Mater.* 18: 597–601.

Cheyns, D., Vasseur, K., Rolin, C., Genoe, J., Poortmans, J., and Heremans, P. 2008. Nanoimprinted semiconducting polymer films with 50 nm features and their application to organic heterojunction solar cells. *Nanotechnology* 19: 424016.

Chou, S. Y., Krauss, P. R., and Renstrom, P. J. 1995. Imprint of sub-25 nm vias and trenches in polymers. *Appl. Phys. Lett.* 67: 3114–3116.

Chou, S. Y., Krauss, P. R., and Renstrom, P. J. 1996. Imprint lithography with 25 nm resolution. *Science* 252: 85–87.

Chou, S. Y., Krauss, P. R., Zhang, W., Guo, L. J., and Zhuang, L. 1997. Sub-10 nm imprint lithography and applications. *J. Vac. Sci. Technol. B* 15: 2897–2904.

Chou, S. Y., Keimel, C., and Gu, J. 2002. Ultrafast and direct imprint of nanostructures in silicon. *Nature* 417: 835–837.

Cormia, R. L., Price, F. P., and Turnbull, D. 1962. Kinetics of crystal nucleation in polyethylene. *J. Chem. Phys.* 37: 1333–1340.

Eder, G., Janeschitz-Kriegel, H., and Krobath, G. 1989. Shear induced crystallization, a relaxation phenomenon in polymer melts. *Prog. Coll. Polym. Sci.* 80: 1–7.

Ellison, C. J. and Torkelson, J. M. 2003. The distribution of glass-transition temperatures in nanoscopically confined glass formers. *Nat. Mater*. 2: 695–700.

Gates, B. D., Xu, Q. B., Stewart, M., Ryan, D., Wilson, C. G., and Whitesides, G. M. 2005. New approaches to nanofabrication: Molding, printing, and other techniques. *Chem. Rev.* 105: 1171–1196.

Gautam, S., Balijepalli, S., and Rutledge, G. C. 2000. Molecular simulations of the interlamellar phase in polymers: Effect of chain tilt. *Macromolecules* 33: 9136–9145.

Gedde, U. W. 1995. *Polymer Physics*. London, U.K.: Chapman & Hall.

Givargizov, E. I. 1994. Artificial epitaxy (Graphoepitaxy). In *Handbook of Crystal Growth*, Vol. 3, D. T. J. Hurle (Ed.), pp. 941–995. Amsterdam, the Netherlands: Elsevier.

Givargizov, E. I. 2008. Graphoepitaxy as an approach to oriented crystallization on amorphous substrates. *J. Cryst. Growth* 310: 1686–1690.

Grosberg, A. Y. and Khokhlov, A. R. 1994. *Statistical Physics of Macromolecules*. New York: American Institute of Physics.

Guo, L. J. 2004. Recent progress in nanoimprint technology and its applications. *J. Phys. D Appl. Phys*. 37: R123–R141.

Guo, L. J. 2007. Nanoimprint lithography: Methods and material requirements. *Adv. Mater.* 19: 495–513.

Guo, L. J., Cheng, X., and Chao, C. Y. 2002. Fabrication of photonic nanostructures in nonlinear optical polymers. *J. Mod. Opt*. 49: 663–673.

Hamley, I. W. 1998. *The Physics of Block Copolymers*. Oxford, NY: Oxford University Press.

Harnagea, C., Alexe, M., Schilling, J., Choi, J., Wehrspohn, R. B., Hesse, D., and Gosele, U. 2003. Mesoscopic ferroelectric cell arrays prepared by imprint lithography. *Appl. Phys. Lett.* 83: 1827–1829.

Heyderman, L. J., Schift, H., David, C., Gobrecht, J., and Schweizer, T. 2000. Flow behavior of thin polymer films used for hot embossing lithography. *Microelectron. Eng.* 54: 229–245.

Hu, Z., Baralia, G., Bayot, V., Gohy, J.-F., and Jonas, A. M. 2005. Nanoscale control of polymer crystallization by nanoimprint lithography. *Nano Lett.* 5: 1738–1743.

Hu, Z., Muls, B., Gence, L., Serban, D. A., Hofkens, J., Melinte, S., Nysten, B., Demoustier-Champagne, S., and Jonas, A. M. 2007. High-throughput fabrication of organic nanowire devices with preferential internal alignment and improved performance. *Nano Lett.* 7: 3639–3644.

Hu, Z., Tian, M., Nysten, B., and Jonas, A. M. 2009. Regular arrays of highly ordered ferroelectric polymer nanostructures for non-volatile low-voltage memories. *Nat. Mater.* 8: 62–67.

ITRS (International Technology Roadmap for Semiconductors), 2007 edition (http://www.itrs.net).

Jung, G.-Y., Li, Z., Wu, W., Chen, Y., Olynick, D. L., Wang, S.-Y., Tong, W. M., and Williams, R. S. 2005. Vapor-phase self-assembled monolayer for improved mold release in nanoimprint lithography. *Langmuir* 21: 1158–1161.

Kalinin, S. and Gruverman, A. 2007. *Scanning Probe Microscopy: Electrical and Electromechanical Phenomena at the Nanoscale*. New York: Springer.

Kane, R. S., Takayama, S., Ostuni, E., Ingber, D. E., and Whitesides, G. M. 1999. Patterning proteins and cells using soft lithography. *Biomaterials* 20: 2363–2376.

Khang, D.-Y., Yoon, H., and Lee, H. H. 2001. Room-temperature imprint lithography. *Adv. Mater.* 13: 749–752.

Kim, M.-S., Kim, J.-S., Cho, J. C., Shtein, M., Guo, L. J., and Kim, J. 2007. Flexible conjugated polymer photovoltaic cells with controlled heterojunctions fabricated using nanoimprint lithography. *Appl. Phys. Lett.* 90: 123113.

Kimita, S., Sakurai, T., Nozue, Y., Kasahara, T., Yamaguchi, N., Karino, T., Shibayama, M., and Kornfiled, J. A. 2007. Molecular basis of the shish-kebab morphology in polymer crystallization. *Science* 316: 1014–1017.

Klar, T. A., Jakobs, S., Dyba, M., Egner, A., and Hell, S. W. 2000. Fluorescence microscopy with diffraction resolution barrier broken by stimulated emission. *Proc. Natl. Acad. Sci. U.S.A.* 97: 8206–8210.

Ko, S. H., Park, I., Pan, H., Grigoropoulos, C. P., Pisano, A. P., Luscombe, C. K., and Fréchet, J. M. J. 2007. Direct Nanoimprinting of metal nanoparticles for nanoscale electronics fabrication. *Nano Lett.* 7: 1869–1877.

Kumar, A. and Whitesides, G. M. 1993. Features of gold having micrometer to centimeter dimensions can be formed through a combination of stamping with an elastomeric stamp and an alkanethiol ink followed by chemical etching. *Appl. Phys. Lett.* 63: 2002–2004.

Kumaraswamy, G., Issaian, A. M., and Kornfield, J. A. 1999. Shear-enhanced crystallization in isotactic polypropylene. 1. Correspondence between in situ rheo-optics and ex situ structure determination. *Macromolecules* 32: 7537–7547.

Leung, O. M. and Goh, M. C. 1992. Orientational ordering of polymers by atomic force microscope tip-surface interaction. *Science* 255: 64–66.

Li, H.-W. and Huck, W. T. S. 2004. Ordered block-copolymer assembly using nanoimprint lithography. *Nano Lett.* 4: 1633–1636.

Loo, Y. L., Register, R. A., and Ryan, A. J. 2002. Modes of crystallization in block copolymer microdomains: Breakout, templated, and confined. *Macromolecules* 35: 2365–2374.

Mahalingam, V., Onclin, S., Peter, M., Ravoo, B. J., Huskens, J., and Reinhoudt, D. N. 2004. Directed self-assembly of functionalized silica nanoparticles on molecular printboards through multivalent supramolecular interactions. *Langmuir* 20: 11756–11762.

Maier, G. 2001. Low dielectric constant polymers for microelectronics. *Prog. Polym. Sci.* 26: 3–65.

Mandelkern, L. 1979. Relation between properties and molecular morphology of semicrystalline polymers. *Faraday Discuss.* 68: 310–319.

Massa, M. V. and Dalnoki-Veress, K. 2004. Homogeneous crystallization of poly(ethylene oxide) confined to droplets: The dependence of the crystal nucleation rate on length scale and temperature. *Phys. Rev. Lett.* 92: 255509.

Mele, E., Di Benedetto, F., Persano, L., Cingolani, R., and Pisignano, D. 2005. Multilevel, room temperature nanoimprint lithography for conjugated polymer-based photonics. *Nano Lett.* 5: 1915–1919.

Mele, E., Camposeo, A., Stabile, R., Del Carro, P., Di Benedetto, F., Persano, L., Cingolani, R., and Pisignano, D. 2006. Polymeric distributed feedback lasers by room-temperature nanoimprint lithography. *Appl. Phys. Lett.* 89: 131109.

Miller, R. L. (Ed.). 1979. *Flow-Induced Crystallization in Polymer Systems*. New York: Gordon & Breach.

Mouthuy, P.-O., Melinte, S., Geerts, Y. H., and Jonas, A. M. 2007. Uniaxial alignment of nanoconfined columnar mesophases. *Nano Lett.* 7: 2627–2632.

Muller, A. J., Balsamo, V., Arnal, M. L., Jakob, T., Schmalz, H., and Abetz, V. 2002. Homogeneous nucleation and fractionated crystallization in block copolymers. *Macromolecules* 35: 3048–3058.

Odom, T. W., Love, J. C., Wolfe, D. B., Paul, K. E., and Whitesides, G. M. 2002. Improved pattern transfer in soft lithography using composite stamps. *Langmuir* 18: 5314–5320.

Ohtake, T., Nakamatsu, K., Matsui, S., Tabata, H., and Kawai, T. 2004. DNA nanopatterning with self-organization by using nanoimprint. *J. Vac. Sci. Technol. B* 22: 3275–3278.

Okerberg, B. C., Soles, C. L., Douglas, J. F., Ro, H. W., Karim, A., and Hines, D. R. 2007. Crystallization of poly(ethylene oxide) patterned by nanoimprint lithography. *Macromolecules* 40: 2968–2970.

Okinaka, M., Tsukagoshi, K., and Aoyagi, Y. 2006. Direct nanoimprint of inorganic-organic hybrid glass. *J. Vac. Sci. Technol. B* 24: 1402–1404.

Owen G. 1985. Electron lithography for the fabrication of microelectronic devices. *Rep. Prog. Phys.* 48: 795–851.

Park, I., Cheng, J., Pusano, A. P., Lee, E.-S., and Jeong, J.-H. 2007. Low temperature, low pressure nanoimprinting of chitosan as a biomaterial for bionanotechnology applications. *Appl. Phys. Lett.* 90: 093902.

Park, I., Ko, S. H., Pan, H., Grigoropoulos, C. P., Pisano, A. P., Fréchet, J. M. J., Lee, E.-S., and Jeong, J.-H. 2008. Nanoscale patterning and electronics on flexible substrate by direct nanoimprinting of metallic nanoparticles. *Adv. Mater.* 20: 489–496.

Peroz, C., Heitz, C., Barthel, E., Sondergard, E., and Goletto, V. 2007. Glass nanostructures fabricated by soft thermal nanoimprint. *J. Vac. Sci. Technol. B* 25: L27–L30.

Pisignano, D., Persano, L., Visconti, P., Cingolani, R., Gigli, G., Barbarella, G., and Favaretto, L. 2003. Oligomer-based organic distributed feedback lasers by room-temperature nanoimprint lithography. *Appl. Phys. Lett.* 83: 2545–2547.

Pisignano, D., Persano, L., Raganato M. F., Visconti, P., Cingolani, R., Barbarella, G., Favaretto, L., and Gigli, G. 2004. Room temperature nanoimprint lithography of non-thermoplastic organic film. *Adv. Mater.* 16: 525–529.

Rai-Choudhury, P. 1997. *Handbook of Microlithography, Micromachining, and Microfabrication: Vol. 1: Microlithography*. Bellingham, WA: SPIE Optical Engineering Press.

Reiter, G. and Strobl, G. R. (Eds.). 2006. *Progress in Understanding of Polymer Crystallization*. Lecture Notes in Physics, Vol. 714. Berlin, Germany: Springer.

Reiter, G., Castelein, G., Sommer, J. U., Rottele, A., and Thurn-Albrecht, T. 2001. Direct visualization of random crystallization and melting in arrays of nanometer-size polymer crystals. *Phys. Rev. Lett.* 87: 226101.

Resnick, D. J. 2007. Imprint lithography. In *Microlithography Science and Technology*, K. Suzuki and B. W. Smith (Eds.), pp. 465–499. Boca Raton, FL: Taylor & Francis.

Resnick, D. J., Dauksher, W. J., Mancini, D., Nordquist, K. J., Bailey, T. C., Johnson, S., Stacey, N., Ekerdt, J. G., Willson, C. G., Sreenivasan, S. V., and Schumaker, N. 2003. Imprint lithography for integrated circuit fabrication. *J. Vac. Sci. Technol. B* 21: 2624–2631.

Ro, H. W., Jones, R. L., Peng, H., Hines, D. R., Lee, H.-J., Lin, E. K., Karim, A., Yoon, D. Y., Gidley, D. W., and Soles, C. L. 2007. The direct patterning of nanoporous interlayer dielectric insulator films by nanoimprint lithography. *Adv. Mater*. 19: 2919–2924.

Ro, H. W., Peng, H., Niihara, K., Lee, H.-J., Lin, E. K., Karim, A., Gidley, D. W., Jinnai, H., Yoon, D. Y., Gidley, D. W., and Soles, C. L. 2008. Self-sealing of nanoporous low dielectric constant patterns fabricated by nanoimprint lithography. *Adv. Mater*. 20: 1934–1939.

Rowland, H. D., Sun, A. C., Schunk, P. R., and King, W. P. 2005. Impact of polymer film thickness and cavity size on polymer flow during embossing: Toward process design rules for nanoimprint lithography. *J. Micromech. Microeng*. 15: 2414–2425.

Rowland, H. D., King, W. P., Pethica, J. B., and Cross, G. L. W. 2008. Molecular confinement accelerates deformation of entangled polymers during squeeze flow. *Science* 322: 720–724.

Rubinstein, M. and Colby, R. H. 2003. *Polymer Physics*. Oxford, NY: Oxford University Press.

Ruchhoeft, P., Colburn, M., Choi, B., Nounu, H., Johnson, S., Bailey, T., Damle, S., Stewart, M., Ekerdt, J., Sreenivasan, S. V., Wolfe, J. C., and Willson, C. G. 1999. Patterning curved surfaces: Template generation by ion beam proximity lithography and relief transfer by step and flash imprint lithography. *J. Vac. Sci. Technol. B* 17: 2965–2969.

Schift, H. 2008. Nanoimprint lithography: An old story in modern times? A review. *J. Vac. Sci. Technol. B* 26: 458–480.

Schift, H. and Heyderman, L. J. 2003. Nanorheology. Squeeze flow in hot embossing of thin films. In *Alternative Lithography. Unleashing the Potentials of Nanotechnology*, C. M. Sotomayor Torres (Ed.), pp. 47–76. New York: Kluwer Academic/Plenum.

Schift, H. and Kristensen, A. 2007. Nanoimprint lithography. In *Springer Handbook of Nanotechnology*, 2nd edition, B. Bushan (Ed.), pp. 239–278. Berlin, Germany: Springer.

Schift, H., Heyderman, L. J., Auf der Maur, M., and Gobrecht, J. 2001. Pattern formation in hot embossing of thin polymer films. *Nanotechnology* 12: 173–177.

Schift, H., Saxer, S., Park, S., Padeste, C., Peiles, U., and Gobrecht, J. 2005. Controlled co-evaporation of silanes for nanoimprint stamps. *Nanotechnology* 16: S171–S175.

Schmid, S. A., Yim, K. H., Chang, M. H., Zheng, Z., Huck, W. T. S., Friend, R. H., Kim, J. S., and Herz, L. M. 2008. Polarization anisotropy dynamics for thin films of a conjugated polymer aligned by nanoimprinting. *Phys. Rev. B* 77: 115338.

Schulz, H., Wissen, M., and Scheer, H.-C. 2003. Local mass transport and its effect on global pattern replication during hot embossing. *Microelectron. Eng*. 67–68: 657–663.

Sheftal, N. N. and Bouzynin, N. A. 1972. Preferred orientation of crystallites on the substrate and effect of scratches. *Vestn. Mosk. Univ. Ser. Geol*. 27: 102–104.

Sheikholeslami, A. and Gulak, P. G. 2000. A survey of circuit innovations in ferroelectric random-access memories. *Proc. IEEE* 88: 667–688.

Smith, H. I. and Flanders, D. C. 1978. Oriented crystal growth on amorphous substrates using artificial surface-relief gratings. *Appl. Phys. Lett*. 32: 349–350.

Somani, R. H., Hsiao, B. S., Nogales, A., Srinivas, S., Tsou, A. H., Sics, I., Balta-Calleja, F. J., and Ezquerra, T. A. 2000. Structure development during shear flow-induced crystallization of i-PP: In-situ small-angle x-ray scattering study. *Macromolecules* 33: 9385–9394.

Song, M. H., Wenger, B., and Friend, R. H. 2008. Tuning the wavelength of lasing emission in organic semiconducting laser by the orientation of liquid crystalline conjugated polymer. *J. Appl. Phys*. 104: 033107.

Steinhart, M., Göring, P., Dernaika, H., Prabhukaran, M., Gösele, U., Hempel, E., and Thurn-Albrecht, T. 2006. Coherent kinetic control over crystal orientation in macroscopic ensembles of polymer nanorods and nanotubes. *Phys. Rev. Lett*. 97: 027801.

Stewart, M. D. and Willson, C. G. 2005. Imprint materials for nanoscale devices. *MRS Bull*. 30: 947–951.

Studer, V., Pepin, A., and Chen, Y. 2002. Nanoembossing of thermoplastic polymers for microfluidic applications. *Appl. Phys. Lett*. 80: 3614–3616.

Suzuki, K. 2007. Electron beam lithography systems. In *Microlithography Science and Technology*, K. Suzuki and B. W. Smith (Eds.), pp. 465–499. Boca Raton, FL: Taylor & Francis.

Ting, C.-J., Huang, M.-C., Tsai, H.-Y., Chou, C.-P., and Fu, C.-C. 2008a. Low cost fabrication of the large-area anti-reflection films from polymer by nanoimprint/hot-embossing technology. *Nanotechnology* 19: 205301.

Ting, C.-J., Chang, F.-Y., Chen, C.-F., and Chou, C.-P. 2008b. Fabrication of an antireflective polymer optical film with subwavelength structures using a roll-to-roll micro-replication process. *J. Micromech. Microeng*. 18: 075001.

Toney, M. F., Russell, T. P., Logan, J. A., Kikuchi, H., Sands, J. M., and Kumar, S. K. 1995. Near-surface alignment of polymers in rubbed films. *Nature* 374: 709–711.

Torres, C. M. (Ed.). 2003. *Alternative Lithography. Unleashing the Potentials of Nanotechnology*. New York: Kluwer Academic/Plenum.

Ueno, T. 2007. X-ray lithography. In *Microlithography Science and Technology*, K. Suzuki and B. W. Smith (Eds.), pp. 361–382. Boca Raton, FL: Taylor & Francis.

Voicu, N. E., Ludwigs, S., Crossland, E. J. W., Andrew, P., and Steiner, U. 2007. Solvent-vapor-assisted imprint lithography. *Adv. Mater*. 19: 757–767.

Wang, J., Sun, X., Chen, L., and Chou, S. Y. 1999. Direct nanoimprint of submicron organic light-emitting structures. *Appl. Phys. Lett.* 75: 2767–2769.

Wang, J., Sun, X., Chen, L., Zhuang, L., and Chou, S. Y. 2000. Molecular alignment in submicron patterned polymer matrix using nanoimprint lithography. *Appl. Phys. Lett.* 77: 166–168.

Wang, Y., Chan, C. M., Ng, K. M., and Li, L. 2008. What controls the lamellar orientation at the surface of polymer films during crystallization? *Macromolecules* 41: 2548–2553.

Woo, E., Huh, J., Jeong, Y. G., and Shin, K. 2007. From homogeneous to heterogeneous nucleation of chain molecules under nanoscopic cylindrical confinement. *Phys. Rev. Lett.* 98: 136103.

Wunderlich, B. 1976. *Macromolecular Physics. Vol. 2. Crystal Nucleation, Growth, Annealing*. New York: Academic Press.

Wurm, S. and Gwyn, C. 2007. EUV lithography. In *Microlithography Science and Technology*, K. Suzuki and B. W. Smith (Eds.), pp. 383–464. Boca Raton, FL: Taylor & Francis.

Xia, Y. N. and Whitesides, G. M. 1998. Soft lithography. *Annu. Rev. Mater. Sci.* 28: 153–184.

Xia, Y. N., Rogers, J. A., Paul, K. E., and Whitesides, G. M. 1999. Unconventional methods for fabricating and patterning nanostructures. *Chem. Rev.* 99: 1823–1848.

Zhang, L., Ducharme, S., and Li, J. 2007. Microimprinting and ferroelectric properties of poly(vinylidene fluoride-trifluoroethylene) copolymer films. *Appl. Phys. Lett.* 91: 172906.

Zheng, Z., Yim, K.-H., Saifullah, M. S. M., Welland, M. E., Friend, R. H., Kim, J.-S., and Huck, W. T. S. 2007. Uniaxial alignment of liquid-crystalline conjugated polymers by nanoconfinement. *Nano Lett.* 7: 987–992.

19

Nanoelectronics Lithography

Stephen Knight
National Institute of Standards and Technology

Vivek M. Prabhu
National Institute of Standards and Technology

John H. Burnett
National Institute of Standards and Technology

James Alexander Liddle
National Institute of Standards and Technology

Christopher L. Soles
National Institute of Standards and Technology

Alain C. Diebold
University at Albany

19.1 Introduction **19**-1
19.2 Photoresist Technology **19**-3
Fundamentals • Advances by Material Structure • Progress in Resists for EUV • Progress in Resists for 193 nm Immersion Lithography • Concluding Remarks
19.3 Deep Ultraviolet Lithography **19**-8
DUV Lithography Steppers • 193 nm Immersion Lithography • Double Patterning • Ultimate Resolution Limits of DUV Lithography
19.4 Electron-Beam Lithography **19**-14
Resolution • Throughput • Overlay • Cost of Ownership
19.5 Nanoimprint Lithography **19**-17
Variations of NIL • Fundamental Issues • Overlay Accuracy and Control • Technology Examples • Future Perspectives
19.6 Metrology for Nanolithography **19**-24
Advanced Lithographic Processes • Metrology for Advanced Lithography Processes • Proposed New CD Metrology Methods
Abbreviations **19**-27
References **19**-28

19.1 Introduction

The modern integrated circuit (IC), comprising memory, logic processors and analog function devices, are multicomponent and multilevel nanostructures prepared by a series of patterning and pattern-transfer steps. Figure 19.1 shows the cross-sectional hierarchical structure that starts from the smallest feature, the transistor, to dielectrics and metal contacts that are each well defined and must precisely overlay the previous layer. This three-dimensional nanoelectronics structure is manufactured by a rapid patterning process called lithography.

Since the invention of the transistor in 1947 by Bell Labs and Intel's first microprocessor in 1971, modern lithography has enabled the semiconductor industry to shrink device dimensions. The early progress was first quantified by Gordon Moore in 1965 and is now known as Moore's law.[1] While progress in all process steps are required to achieve the continual shrinking of circuit elements, the advancements in lithography have been the overwhelming driving force. Figure 19.2 shows how Moore's law has guided the industry's systematic increase in the number of transistors per chip since the introduction of the IC. Indeed, now and in the future, the industry will achieve productivity improvement primarily by feature reduction.[2]

While a wide variety of lithography technologies have been developed, optical step and repeat lithography technologies are the predominant methods of printing features on the semiconductor surfaces and overlying the interconnect structures. A number of competing technologies have been explored, such as x-ray[3,4] and flood electron beam (SCALPEL),[5,6] but optical lithography has dominated through vigorous optical technology and tool developments that have left it the lowest cost solution with highest throughput. Direct-write electron-beam technology provides the highest resolution and remains the leading technique for manufacturing the masks used by optical lithography. A novel way of comparing different lithography strategies is by a plot of resolution versus throughput, also known as "Tennant's Law,"[7,8] as plotted in Figure 19.3. In this plot, direct-write approaches, such as single-atom placement by scanning tunneling microscopy (STM), atomic-force microscopy (AFM) tip-induced oxidation, and electron-beam



FIGURE 19.1 Cross section of an integrated circuit, showing the active semiconductor and multilayer interconnect levels. (Reproduced from *International Technology Roadmap for Semiconductors*, 2007 edition, SEMATECH, Austin, TX, Figure INTC2, 2007. With permission.)



FIGURE 19.2 A composite plot of the scaling of the number of transistors, clock speed, and manufacturing technology versus the year of introduction of Intel Processors. (Data from www.intel.com/technology/timeline.pdf.)

lithography are compared with optical step and repeat lithography that replicate the features of a mask. The continued advancements in optical lithography have pushed the resolution to smaller features at higher pixel throughput, as analyzed by Brunner.[9]

The fundamental guide for optical step and repeat lithography is the Rayleigh equation, which provides the scaling criteria for predicting the smallest optically definable image[2]

$$R = k_1 \frac{\lambda}{\mathrm{NA}} = k_1 \frac{\lambda}{n \sin\theta}; \tag{19.1}$$

where

λ is the source wavelength
n is the medium refractive index
$n \sin\theta$ is the numerical aperture (NA) with the incidence angle (θ)
k_1 is a process dependent factor

While the Rayleigh equation defines the resolution, the ability of the photoresist to replicate the mask features is of critical importance. All approaches and manufacturing tools have taken advantage of the Rayleigh equation to predict transitions from each manufacturing technology node (smallest feature size) up to the diffraction limit. Optical lithography started with the near *ultra*violet (UV) g-line (436 nm) and i-lines (365 nm) of mercury-arc lamps and made way for laser sources in the deep *ultra*violet (DUV) from KrF (248 nm) and ArF (193 nm) excimers. A significant extension, immersion lithography, decreases the 193 nm wavelength by using water as the immersion fluid and is on track to produce features down to 32 nm. The next-generation photoresist materials, described in Section 19.2, for sub 22 nm features expect to image 13.4 nm radiation in extreme *ultra*violet (EUV) with all reflective lithography imaging tools.

While most of this chapter focuses on the leading-edge and next-generation technologies used for defining the finest features in nanoelectronics, it is important to recognize that for most applications it is necessary to connect the nano-world (transistor) to the macro-world (a computer motherboard). Figure 19.1 shows the cross section of an IC. Note that the interconnect sizes increase at subsequent higher levels. Therefore, the previous-generation tools continue to play crucial roles by migrating to the higher levels of interconnect.



FIGURE 19.3 The progress of optical step and repeat lithography has driven to higher resolution and throughput as described by "Tennant's Law," whereby the resolution (R) versus areal throughput (T) scales as $R = 2.3\,T^{0.2}$ (Adapted from Tennant, D., Limits of conventional lithography, in Timp, G.M. (ed.), *Nanotechnology*, AIP Press, New York, Chapter 4, p. 161, 1999. With permission.)

Microelectronics and now nanoelectronics technology have become a collaborative and competitive worldwide effort, as exemplified by the *International Technology Roadmap for Semiconductors* (ITRS), available to the public at http://www.itrs.net. The ITRS is updated every two years by subject matter experts from the semiconductor manufacturing industry, the tool and materials supplier industries, the factory automation infrastructure, academia, and government agencies. An important guiding aspect of the ITRS roadmap is the identification of the status of the technology nodes and guidance of the phases of research, development, and pre-production. In particular, the 2007 edition identifies potential lithographic solutions out to 2022, with a predicted dynamic random access memory half pitch of 11 nm and FLASH memory half pitch of 9 nm as shown in Figure 19.4.

In this roadmap, several emerging lithography approaches are highlighted. Double patterning with 193 nm DUV water immersion is expected to extend to the 32 nm half pitch era with high-volume production in 2013. Alternatively, contending technologies for 22 nm half pitch are EUV Lithography, 193 nm DUV immersion with higher index fluid and lens materials, maskless lithography (ML2), and nanoimprint lithography (NIL).[10,11] NIL is rapidly emerging as a low-cost, high-resolution, and versatile alternative to optical lithography. Below 22 nm half-pitch, the likely technology solutions are less clear. All the technologies mentioned above, along with new contenders, such as directed self assembly, have credible paths. However, each would have to surmount numerous technical difficulties while limiting exorbitant cost and loss in throughput.

In the rest of this chapter, we describe some of the challenges facing the photoresist materials (Section 19.2) used in optical lithography including some crucial aspects facing these materials as the feature dimensions are reduced to the length scale of the basic photoresist polymers. In Section 19.3, DUV lithography, the basic optics, advancements in steppers, and approaches to extend to higher-resolution, denser features are described. In Section 19.4, electron-beam lithography is covered with respect to the metrics of resolution, throughput, overlay requirements, and cost. Section 19.5 highlights a non-optical lithography approach, NIL. In this section, several variations of NIL for transferring mask features into a photoresist are described. Finally, in Section 19.6, we end with an overview of the metrology requirements for nanolithography. Figure 19.1 is a reminder that one must print and measure a wide-range of feature dimensions, from the nanoscale to the macroscale. Lastly, a separate chapter in this handbook is dedicated to EUV lithography.

19.2 Photoresist Technology

The optical image projected from a mask upon a thin film at the semiconductor wafer plane is the first step of photolithography.[10,12] The thin films that replicate the mask features are called photoresists with basic process as shown in Figure 19.5. The high sensitivity of photoresists to radiation have consistently met the challenges of smaller, high-fidelity features with increased throughput driven by memory and processor chip performance to feature size gains (Moore's law). The etch resistance of the



FIGURE 19.4 Roadmap for half pitch scaling. (Reproduced from *International Technology Roadmap for Semiconductors*, 2007 edition, SEMATECH, Austin, TX, Figure LITH5, 2007. With permission.)



FIGURE 19.5 Schematic of the lithographic process for positive and negative tone resist.

photoresist allows pattern transfer into the underlying semiconductor wafer.

Test structures, such as a line and space pattern as shown in Figure 19.6, must meet criteria as defined by the ITRS roadmap for critical dimension (CD). The CD is the feature size, for example, in a 32 nm half-pitch 1:1 dense line, a line with a width of 32 nm is followed by a space of equal size. The Rayleigh equation defines the resolution; however, the ability of the photoresist to perfectly replicate the mask features is of critical importance. The line-width variations called line-width roughness (LWR) and line-edge roughness (LER) must be reduced to less than 2 nm for 32 nm half pitch (HP) as they impact device performance.[13,14] Therefore, the photoresist materials chemistry plays a substantial role for both resolution and LER. Methods to extend resist resolution by double patterning methods and new photoresist architectures must be leveraged against meeting the LER requirements for sub-22 nm lithography.

19.2.1 Fundamentals

The requirements for advanced photoresists are discussed in the 2007 ITRS roadmap.[14] Specifically, the "Lithography" chapter highlights difficult challenges:

> Resist materials at <32 nm indicates three issues (1) Resist and antireflective coating materials composed of alternatives to PFAS [perfluoroalkysulfonate] compounds, (2) Limits of chemically amplified resist sensitivity for <32 nm half-pitch due to acid diffusion length, and (3) materials with improved dimensional and LWR control.

The details of the photoresist materials chemistry are at the heart of turning the optically defined patterns into three-dimensional


100 nm 1:1 Dense lines
AV-4700-2 2.0 kV 3.2 mm ×150k SE (U) 5/4/05
300 nm
Top-down schematic
Line-width and edge roughness
Line

FIGURE 19.6 Example of a cross-sectional SEM image of a 100 nm 1:1 line-space lithographic line. The fluctuations in the feature critical dimension along the line are quantified by line-edge roughness and line-width roughness metrics as indicated in the schematic.

nanoscale features. Chemically amplified photoresists are formulations of an acid-sensitive polymer film mixed with photoacid generators (PAGs) and other additives, such as base quenchers. Upon exposure through a mask, strong acids are formed by photolysis of the molecularly mixed PAG within the thin film. A post-exposure bake is then applied and the acidic protons (photoacids) diffuse along with the counter-anions and catalyze a deprotection reaction on the acid-sensitive polymer to change the local solubility for development in an aqueous hydroxide solution as shown in Figure 19.7. The photoacids are true catalysts as they are regenerated by each deprotection reaction;[15] hence, the term chemical amplification refers to the cascade of reactions that occur within the photoresist induced by a single photon. Therefore, these photoresists may be used at low exposure doses.

The chemical reaction-diffusion that forms the latent image and development must be understood and controlled at the nanometer length scale. Chemically amplified photoresists are also deposited onto bottom anti-reflection coatings (BARC) to eliminate the effects of standing waves. Interactions and component transport between the BARC and resist layer can lead to loss of profile control or pattern collapse and therefore must also be understood. Detailed studies of these interactions and transport mechanisms are needed to design materials for the successful fabrication of sub-32 nm structures.

As feature sizes are reduced to below 32 nm, a general problem of simultaneously minimizing dose sensitivity, CD, and LER was observed experimentally and theoretically. These observations suggest only two of these metrics may be met at the sacrifice of


hν
PAG
Photoacid generator
H^+R^-
Photoacid
H^+R^-+
Developer-insoluble polymer
Developer-soluble polymer + H^+R^-
100–10,000 cycles
Exposure dose profile
Photoacid image
Latent image
Developed image

FIGURE 19.7 Schematic of the photolysis process of a photoacid generator that forms a strong acid (H^+R^-) and the subsequent acid catalytic reaction that changes the solubility of the polymer in a developer solution. Schematic of the mask-defined dose profile, subsequent profile in the photoresist film that leads to a photoacid image and chemical latent image formed during the post-exposure bake. The final developed image is formed after selective dissolution in a developer solution as determined by the extent of chemical reaction in the nominally exposed regions.

the third. Several theoretical models[16–18] have been proposed, such as those by Bristol (2007)

$$\mathrm{LER} \approx \frac{1}{\sqrt{q\alpha D_e}}\sqrt{1+\frac{1}{\varepsilon}}\frac{1}{\mathrm{LILS}\cdot\delta}, \qquad (19.2)$$

where
- q is the number of photons/nm^2
- D_e is the dose at the line-edge (threshold for development)
- α is the fraction of light absorbed
- ε is the quantum efficiency defined by the (molecules of acids produced)/(number of absorbed photons)
- δ is the effective photoacid diffusion length
- LILS is the latent-image log slope

As shown in the schematic of Figure 19.7, the initial photoacid image is followed by a post-exposure bake step whereby the photoacid diffuses and reacts. The extent of the reaction will define a chemical latent image in the photoresist. The local slope of the chemical transformation, or latent-image log slope (LILS), at the point of development is critical to maximize. Qualitatively, a large exposure dose leads to a lower LER at fixed LILS and δ. However, notice that once smaller features are desired (δ < CD), then the photoacid diffusion length should be reduced; hence at fixed D_e, a smaller δ may increase LER. The full problem is a nonlinear reaction-diffusion equation and typically requires additional parameterization to include the effects of photoacid loss, photoacid trapping, and amine quenchers that react and diffuse. However, approaches such as Equation 19.2 provide qualitative insights into the resist problem. In cases when the material specifics were not known, the form of material constant = (half-pitch)^3 × (LER)^2 × (Sensitivity) has been used.[19]

Such resolution limits are linked to the fundamentals of photoacid generation (via D_e, α, ε) and chemical reaction-diffusion during the post-exposure bake that defines the LILS, choice of photoresist chemistry, PAG size, and processing time and the temperature that ultimately determines the photoacid diffusion length and development step that resolves the final feature. Experimental methods have been developed to quantitatively measure many of these parameters. More recently, parameters such as the photoacid diffusion length were estimated by modeling of the lithographic feature power spectrum.[16]

The efficient generation of photoacids is also crucial to photoresist technology. Analytical methods have been developed to measure photoacid generation and quantum efficiency.[20–23] Many of these techniques rely on a well-defined dose upon photoresist thin films followed by analytical approaches to determine the acid concentration via titration with a standard base. More recently, quantifying the quantum efficiency and acid generation mechanisms in EUV photoresists has taken a more important role as increasing the acid concentration or efficiency (Equation 19.2) is a method for reducing LER. For 248 and 193 nm lithography, photoresist polymers were designed for low absorbance, while the PAG absorbs strongly for photolysis. Since organic photoresist polymers absorb strongly in the EUV, the photolysis induced by the direct exposure of the 92 eV photon and secondary electrons are equally important. In fact, the ε for EUV exposure is greater than 1 due to the non-negligible contribution from lower energy secondary electrons. In both DUV and EUV lithography, the photoacid image plays the important role of changing the local solubility of the photoresist polymer in the nominally exposed regions (Figure 19.7).

During the post-exposure bake, the latent image (Figure 19.7) formed is a composition profile of the photoresist within the line:space feature. The true shape of this profile is due to the photoacid catalyzed reaction-diffusion process that cleaves (deprotection) a nonpolar side-group of the photoresist polymer. The influence of the optical image quality on the final developed feature may be probed by varying the aerial image contrast. Hinsberg et al. elegantly showed that the initial photoacid distribution, controlled through the exposure quality by interferometric lithography, significantly affects the printed feature quality.[24] Furthermore, using an image-fading technique, Pawloski et al. identified an apparent resolution limit in the final feature of 193 nm resists as quantified by LER versus the image-log slope (ILS).[25] These changes in the feature quality are also controlled by the reaction-diffusion of the photoacid[12] into the unexposed regions that leads to image spreading or blurring.[26] However, even with an ideal step-exposure condition, mimicked by forming a bilayer stack, the reaction-diffusion process induces an image blur. Controlling the photoacid reaction-diffusion (via LILS and δ) remains an important strategy for improving feature quality.

The transport properties of the photoacid are also influenced by the changes in the local chemical composition that occur during the deprotection reaction.[27] Houle et al. demonstrated that the evolving resist polymer chemistry plays a crucial role in lithographic imaging.[26] An increased photoacid size decreased the apparent diffusion length,[28,29] but also quantitatively increased the LILS.[30,31] However, the catalytic efficiency of the photoacid proton can dominate, such that by increasing the size of the photoacid counter-anion, image blur occurs primarily due to the local proton mobility, not diffusion of the acid-counter-anion pair.[32] Neutron reflectivity methods were developed to characterize the shape of the reaction-diffusion front with nanometer resolution.[14,30,31,33–37] In these studies, the influence of the evolving chemical composition on the spatial-extent of the reaction profile was directly measured.

Base quencher additives are also used in photoresist formulations to limit the reaction and diffusion of the photoacid catalyst into unexposed regions.[12,38] The influence of these neutralizing species on the reaction-diffusion process is complex.[39] The simplistic view of the quenchers solely acting to neutralize photoacid, thus decreasing the acid concentration, is not always correct.[40] The quencher appears to partially neutralize the photoacid less than stoichiometrically, influence the dissolution either as promoters or inhibitors, and increase the development induction time.[39] The partial neutralization initially reduces the amount of acid available after photolysis proportional to the base concentration.[40–42] The influence of quenchers on the chemical gradients in the film were suspected to control LER.[43] Direct measurements of the effect of amine quenchers on the reaction-diffusion profile shape (LILS) and spatial extent (δ) were determined by neutron reflectivity.[35]

A central assumption in these resolution limit models is a direct transfer of the chemical deprotection reaction-diffusion heterogeneity on the feature quality; the details of the development process are not considered. However, the bulk of photoresist thin films dissolve via reactive dissolution kinetics involving a well-defined steady-state swollen layer.[44–46] This swollen layer must approach the nominally unreacted and unexposed zone as bulk development ceases.[47] This crucial transition zone results from the initial deprotection latent image that can be controlled by aerial images, polymer chemistry, photoacid generators and base additives, and post-exposure bake conditions.[30,35] The mechanism of how the advancing swelling dissolution front faces the transition of soluble to insoluble species (solubility switch) is crucial for the understanding of resist resolution limits. This was addressed by neutron reflectivity techniques that directly measured the developer penetration and extent of line-edge swelling.[48–50] The residual swelling fraction at the feature edge remains diffuse over length scales (>10 nm) far exceeding the polymer chain dimensions during hydroxide development and water rinse step; the swelling layer eventually collapses upon drying. Alternative development approaches to control this residual swelling fraction may be needed to smooth and reduce LER.

19.2.2 Advances by Material Structure

In a typical polymer photoresist, the PAG is dissolved along with the photoresist polymer and spin cast to form a thin film mixture, or binary blend. Polymers provide flexible platforms to change functional groups in order to meet etch resistance, optical transparency, refractive index requirements, and a variety of acid-sensitive protecting groups. The high glass transition temperatures (typically, T_g > 140°C) provide dimensional stability and wide latitude in post-exposure bake temperature that increases the rates of reaction and photoacid diffusivity. Lastly, polymers have a large degree of lipophilicity in an aqueous base developer that provides a high-development contrast.[12]

Driven by the CD requirements, it was considered that reducing the photoacid diffusion length would enable smaller CD. The PAG and polymer blend approach may not be the most effective route, since the photoacid could diffuse to lengths longer than the CD. In order to address this viewpoint, an alternative resist structure was devised that covalently bonds the photoacid generator to the polymer as shown in Figure 19.8a.[51–54] With this approach, after exposure, the photoacid counter-anion remains covalently bound to the polymer thereby restricting the acidic



FIGURE 19.8 Cartoons of photoresist architecture alternative to polymer and PAG blends: (a) Photoresist polymer bound to the PAG, (b) molecular glass resist with variable core structure, (c) molecular glass resist bound to the PAG, and (d) PAG-core molecular resist.

proton diffusion length. Such approaches remain promising especially to increase the dose sensitivity.

Since the CD and LER metrics are approaching the characteristic dimensions of the photoresist polymers, alternative architectures were considered to extend photolithography by using lower molar mass molecules.[55] These molecular glass (MG) resists, while smaller, may also improve the uniformity of blends with PAG and other additives since miscibility of polymer blends decreases with increasing molar mass.[56] In general, the molecular glass resist has a well-defined small-molecule core that bears protected base-soluble groups (such as hydroxyls and carboxyls) as shown in Figure 19.8b. With this approach, the core chemistry can vary from calix[4]resorcinarenes (ring-like),[57–59] branched phenolic groups,[60,61] and hexaphenolic groups (disk-like).[62,63] Early approaches with MG led to low glass transition temperatures, however, such problems were resolved by increased hydrogen bonding functionality and the design of the core structure. The MG resists may also benefit from a more uniform development due to the lack of chain entanglements and reduced swelling, when compared with polymers; these are active areas of research. Experimental data using the quartz crystal microbalance method demonstrate that swelling appears during development even with molecular glass resists.[64] Most of these alternative resist structures adhere to the chemical amplification strategy. However, nonchemically amplified photoresists are also being considered as they do not contain photoacid generators and hence do not suffer from photoacid diffusion length constraints.[65]

Two other novel MG variants are a PAG covalently bound to the molecular resist (Figure 19.8c) and the core of the molecule serving as the PAG[66] (Figure 19.8d). As designed, there would be no need for the blending of PAG with such resist systems. In the case of Figure 19.8d, photolysis produces a photoacid, which then would deprotect the unexposed acid-sensitive protecting groups of the PAG-core molecular glass. These two approaches (Figure 19.8c and d) are smaller pixel sizes and true one-component systems that in principle eliminate surface segregation and phase separation in cast films. These alternate resist structures, however, typically require additives such as amine base quenchers to limit the diffusion of the photoacid catalyst into unexposed regions.

19.2.3 Progress in Resists for EUV

There has been progress in designing photoresists for EUV lithography in anticipation of the 22 nm nodes. The testing and development of new materials typically relies on direct lithographic testing to screen formulations. However, due to the lack of widely available EUV exposure tools, micro-field exposure tools (MET), such as the 0.3 NA SEMATECH Berkeley MET have an important role for resist testing. Substantial progress[67] in reaching CD challenges with commercial chemically amplified photoresist were reported with 20 nm half-pitch with an EUV dose sensitivity of (12.7–15.2) mJ/cm^2, which is near the theoretical Rayleigh resolution limit of the 0.3-NA system with a k_1 of 0.45. While progress in resolution and sensitivity were observed, LER remains a challenge. In fact, the fidelity of the resist feature may have non-negligible LER contributions from the EUV mask and optical trains as ascertained by modeling. After subtracting an estimated mask contribution, resist LER values appear to approach the 2 nm level. Additionally, a pattern collapse of sub-20 nm dense features suggests the intrinsic resolution could be better than expected. In fact, unoptimized model EUV polymers and MG photoresists clearly show 20 nm features as quantified by the latent image and developed image roughness.[68] Alternative development approaches[69] may provide new directions to break the resolution limits (Equation 19.2), which currently do not directly consider development effects, such as swelling and swelling layer collapse.

19.2.4 Progress in Resists for 193 nm Immersion Lithography

By inspection, the Rayleigh equation (Equation 19.1) directs that the smallest feature may be achieved by employing higher refractive index media (photoresist and immersion fluids). Currently, highly purified water with $n = 1.44$ is used as the immersion fluid and typical 193 nm polymers have $n \approx 1.7$. The development of photoresists and immersion fluids with higher n are needed. A strategy to increase the refractive index is by incorporating more polarizable heteroatoms, such as sulfur,[70–73] into the polymer structure. Halides such as Cl, Br, and I would increase the refractive index at the expense of absorption and possible photo-induced side reactions. Developer-soluble topcoat barriers[74–77] or engineered surface-segregating barrier-layer additives[78–83] are typically used to reduce or mitigate the leaching of critical components (PAG and quenchers) into the immersion fluid.

19.2.5 Concluding Remarks

Sub-32 nm critical dimensions come with many resist challenges. The challenges of reducing feature size and decreasing LER and sensitivity are inter-related. Current attempts to surpass resolution challenges include novel resist process strategies such as double patterning and double exposure as well as novel architectures. However, it is clear that the quality of the final patterned structures is inter-dependent upon the spatial distribution of the photoacid (optical image quality), the spatial extent of the reaction-diffusion process (latent image), and the development mechanisms. The guidance of the resist resolution metrics in cooperation with improved materials fundamentals will help photoresist materials achieve ever smaller features as suggested by the Rayleigh equation.

19.3 Deep Ultraviolet Lithography

Deep ultraviolet (DUV) lithography, using KrF or ArF excimer lasers with illumination wavelengths of 248 or 193 nm, respectively, is now the predominant technology for producing critical


Excimer laser illumination
Patterned photomask
NA = n^{fluid} sin θ
Optical system 4:1 reduction ratio
n^{fluid}
θ
Resist layer
Si wafer
(a)
ASML
TWINSCAN
(b)

FIGURE 19.9 (a) Schematic of the DUV photolithography exposure process. The numerical aperture is defined by NA = n^{fluid} sin θ, where θ is the half angle of the marginal rays and n^{fluid} is the index of the fluid (gas or liquid) between the final lens element and the resist. (b) Illustration of a commercial 193 nm immersion lithography system (ASML TWINSCAN XT:1950i), showing the cylindrical optics barrel in the center, the mask above the optics system, and an illuminated wafer below. (Courtesy of ASML, Veldhoven, the Netherlands. This illustration is based on an artist impression. No rights can be derived from it.)

layers of leading-edge, mass-market semiconductor logic and memory ICs. The technology is based on illuminating a patterned fused silica mask with diffused excimer laser radiation and imaging the transmitted light patterns with 4:1 image reduction onto a photosensitive-resist-coated Si wafer, using a diffraction-limited optical system. The process is indicated schematically in Figure 19.9a. The illuminated wafer is removed from the optical system for chemical processing steps to convert the exposed pattern (latent image) in the resist to a patterned structure on the wafer and put back into the optical system multiple times for further exposure/processing steps. State-of-the-art ICs are built up from about 20–30 layers, a significant fraction of which involve DUV exposure steps. An illustration of a leading-edge 193 nm immersion lithography exposure tool for volume production is shown in Figure 19.9b.

DUV lithography is an evolution of optical-projection lithography developed in the late 1960s and the 1970s using the strong spectral lines from mercury discharge lamps to illuminate first at 436 nm (g-line) and later at 365 nm (i-line). In these early systems, the pattern on the mask for the entire circuit was illuminated and imaged onto the wafer for a specified exposure time, and then the wafer was "stepped" to an adjacent unexposed position for another imaging of the circuit pattern. This was repeated until the wafer was filled with as many identical exposures as the wafer size allowed. These wafer "step-and-repeat" systems were termed "steppers."

In modern leading-edge DUV lithography systems, the full circuit illumination of the mask is replaced by a "scanned" illumination. A fraction of the circuit pattern on the mask is illuminated in a narrow strip across its width and the mask is scanned under this strip, while its image is projected with a 4:1 reduction ratio onto a wafer scanning in the opposite direction, at a speed relative to the mask reduced by the factor of 4. When the full circuit pattern has been exposed, the wafer is stepped to the next position and the process repeated. The exposure image is stepped-and-scanned across the wafer, producing typically over 50 full chip exposures on a 300 mm diameter wafer at a rate giving about 100 wafers per hour. These wafer "step-and-scan" systems are referred to as "scanners," though they are often referred to as "steppers" as well.

The first commercially available production optical-projection lithography system, the DSW4800, was introduced by GCA in 1978. It achieved a minimum feature resolution of a little over 1 μm and a slightly larger depth of focus.[10] At the time, it was fully understood that the resolution of the optical-projection lithography approach was fundamentally restricted by the diffraction limit given roughly by the Rayleigh resolution criterion in Equation 19.1. In DUV lithography, the process-dependent factor k_1 is of order 1 Ref. [10,84]. Actually, Equation 19.1 is intended to capture both the limiting effects of diffraction and the impact of the resist processing. Considering just the diffraction effects, Equation 19.1 would refer to the aerial image at the image plane, and k_1 would be determined only by the profile of the light intensity. However, the actual size of a feature ultimately created by the lithography process also depends on the chemical processing of the exposed resist as described in Section 19.2. For an isolated feature, this size can be any value, i.e., k_1 has no fundamental restrictions. On the other hand, for the dense structures of real circuits, e.g., modeled by a periodic structure, the separation between printed features (the pitch) is fundamentally limited. With the minimum feature size in Equation 19.1 defined as half the pitch for a single exposure, k_1 can be rigorously shown to have a minimum value of $k_1 = 0.25$ Ref. [10,84]. This limit holds for any single-exposure process, as long as the process has a linear dose response.

Because a functional circuit must have some topology and because imaging control is imperfect, the resist exposure process requires some finite depth of focus (DOF). This also has a diffraction and geometric limitation, which is characterized by Equation 19.3

$$\text{Depth of focus} = \frac{\lambda}{2n\left(1-\sqrt{1-\dfrac{\mathrm{NA}^2}{n^2}}\right)} \xrightarrow{\text{Small NA}} k_2\frac{n\lambda}{\mathrm{NA}^2}$$

$$= k_2\frac{\lambda}{n\sin^2\theta}, \qquad (19.3)$$

where, for small NAs, a process-dependent prefactor k_2 is conventionally used.[10,84] For large NAs, the exact form of the equation conventionally incorporates a different process-dependent prefactor $k_3 \times 4$.[85]

In the early 1980s, reasonable considerations about the prospect of significantly altering the parameters in Equations 19.1 and 19.3 to improve the resolution and DOF led to the conclusion that optical-projection lithography had an ultimate dense feature size resolution of about 0.5 μm. Consequently, it was assumed then that progress in high-volume-production ICs would require switching within a decade or so to alternative lithography techniques with more extendibility potential. These included electron-beam direct-write lithography (with multiple parallel beams), electron-projection lithography, ion-projection lithography, x-ray-proximity lithography, extreme-ultraviolet lithography, and nanoimprint lithography.[10] Few people, if anyone, publicly predicted then that the factors in Equations 19.1 and 19.3 would be relentlessly driven to enable optical-projection lithography to out-complete all the alternative technologies mentioned above, in cost and performance capabilities for volume production, at least into the second decade of this century.

19.3.1 DUV Lithography Steppers

A primary driver for this progress has been the wavelength factor in Equation 19.1. This can be seen in Figure 19.10, which shows a log-linear plot of critical feature sizes of leading-edge ICs as a function of year introduced into large-scale production, along with the illumination wavelength used. Wavelength reduction has been aggressively pursued in part because, as is clear from Equations 19.1 and 19.3, feature size reduction by decreasing wavelength reduces DOF less than that by increasing the NA. However, the switch from Hg-arc lamp illuminators with wavelengths at 436 and 365 nm to the DUV excimer laser sources with wavelengths at 248 nm (KrF) around 1995 and 193 nm (ArF) around 2000 was a very challenging one. Hg-arc lamp sources are compact, relatively inexpensive, reliable, and operate continuously. KrF and ArF excimer lasers are much more complex, are substantially more expensive to purchase and operate reliably, have undesirable laser coherence properties, and the illumination is pulsed. This last characteristic has been particularly troublesome because obtaining the required exposure doses fast enough for acceptable wafer throughputs requires very high pulse peak intensities. This puts very stringent requirements on the durability of lens and window materials in the optical system. Further, the shorter UV wavelengths substantially limit material options for these optical elements. In particular, at the time of the introduction of 248 nm lithography, UV-fused silica glass was the only UV-transmitting material that could meet the tight optical properties specifications for the large lenses required. For 193 nm systems, in addition to UV-fused silica, a second high-quality material, crystalline calcium fluoride (CaF_2), had to be developed for lenses to correct for chromatic aberrations in the optical system due to the wavelength dispersion of the index of fused silica (see Figure 19.10).



FIGURE 19.10 Plot of critical feature size (half pitch) of leading-edge semiconductor integrated circuits versus year of volume production, on a log-linear plot. Also included is the lithography wavelength used and the theoretical minimum half pitch for single exposures (0.25λ) for this wavelength. 157 nm technology has not been brought into production. Effective λ is λ/n for 193 nm immersion lithography. Optical materials used for lenses at each λ are also indicated.

Fused silica glass is an amorphous form of SiO_2, which minimizes the large birefringence effects of the uniaxial crystal structure of crystalline SiO_2 (quartz). However, the amorphous structure makes fused silica a thermodynamically metastable material and it suffers structural changes under exposure to high 193 nm laser intensities. These changes result in both volume compaction and rarefaction effects with different intensity dependencies.[86] The resulting refractive index and lens geometry changes can substantially degrade lens performance. To minimize these effects, maximum intensities have to be limited throughout the stepper optics, and the more durable CaF_2 lens elements generally must be used in the positions with highest intensities, for example, at the final lens position.

For wavelengths much below 193 nm, UV-fused silica glass has poor transmission, leaving only the cubic structure Group II fluorides as practical lens materials. Of these, only CaF_2 has been made with lithography-grade optical quality. Hence, wavelength extension to 157 nm with F_2 excimer lasers would require the lenses to be made only from CaF_2, or possibly from other related fluorides, such as BaF_2, if the optical quality could be significantly improved.[87] The availability of lithography-quality CaF_2 for lens material has been a key issue for the development of both 193 and 157 nm lithography technologies, and building a CaF_2 manufacturing infrastructure to support the needs of both of these technologies has been a major challenge. A principal difficulty with CaF_2 production is that its relatively low thermal conductivity and high thermal expansion coefficient requires it to be cooled very slowly from the melt in order to obtain low-strain, single-crystal material of the sufficiently large sizes needed for lenses. Even many weeks of controlled cooling in elaborate temperature-controlled furnaces gives a low yield of lens blanks meeting specifications. One result is that 193 nm stepper systems have been designed to use the minimum number of CaF_2 lens elements possible, though CaF_2 has not been designed out entirely.

A further unexpected complication from the use of CaF_2 lens elements in 193 and 157 nm lithography systems resulted from a faulty assumption that the cubic crystalline structure of CaF_2 would ensure isotropic- and polarization-independent optical properties (for high-quality crystals), as could be "demonstrated" by naive symmetry arguments and measurements at longer wavelengths. In fact, CaF_2 turned out to have substantial index anisotropy and birefringence at the short wavelengths of 193 and 157 nm.[88] This is due to the symmetry-breaking effects of the finite photon momentum at these wavelengths, giving rise to a "spatial-dispersion-induced" or "intrinsic" birefringence.[89] Fortunately, the symmetric nature of this effect has enabled it to be minimized by judiciously orienting the crystal axes of several lens elements to substantially cancel the effects.

Beyond 157 nm, a few shorter wavelengths have been considered for further resolution extension: 126 nm from Ar_2 excimer lasers[90] and 121.6 nm from hydrogen Lyman-α discharge sources.[91] At these wavelengths, the only transmissive optical materials known are LiF, which has high extrinsic absorption and poor exposure durability, and MgF_2, which has high natural birefringence due to its noncubic crystal structure. These shorter wavelength technologies have not been developed beyond feasibility studies.[90,91] Below about 100 nm, no practical material is transparent and refractive optics are not possible. For reasons primarily associated with the development of immersion lithography discussed later, 157 nm lithography, though demonstrated to be technically feasible,[87] has been dropped off of technology roadmaps.[14] It now appears likely that the shortest wavelength that will be used for production lithography with refractive optics is 193 nm.

As of 2008, 193 nm steppers are the primary tools for producing critical layers of high-volume, leading-edge ICs. Their ArF excimer laser sources are pulsed ($\approx$6 kHz, 10 mJ/pulse) and line narrowed ($\leq$0.25 pm spectral bandwidth).[92] The transmission photomasks are made from fused silica with Cr absorbing features and have thin-membrane pellicles to keep uncontrolled particles from collecting on the mask and imaging onto the wafer. The stepper optics are made of fused silica spherical and aspheric lenses, calcium fluoride lenses with clocked crystal axes, mirror elements with aspheric surfaces, and immersion fluids between the last lens element and the wafer, as discussed below.

While the wavelength was progressing down to 193 nm, the other two factors in Equation 19.1, k_1 and NA, were also being pushed towards their limits. A number of resolution enhancement techniques have been used to drive the k_1 factor down to achieve IC structures with half pitches corresponding to a value of k_1 approaching the limiting value of $k_1 = 0.25$.[93] Nearly all of these have been taken over from established optical techniques in other fields such as microscopy. These have included (1) illumination methods (off-axis illumination and partial-coherence control), (2) mask modifications to engineer desired wavefronts (phase shift masks, sub-resolution mask structures, and other optical proximity corrections), and (3) resist contrast improvements. For the 45 nm technology node, logic manufacturers are expected to operate with k_1 factors down to about 0.31,[94] and further extension with k_1 factors down to 0.29 is considered feasible.[95] Unfortunately, accompanying these gains, process latitudes have been shrinking to marginally tolerable levels. Clearly, k_1 factor improvements for single exposures are nearly tapped out.

The last factor left in Equation 19.1 is the numerical aperture, $NA = n \sin \theta$. For air between the final lens element and the wafer, the liming value is NA = 1. The GCA 4800 DSW stepper in 1978 had an NA of 0.28.[96] The NA has been increased steadily in newer designs by increasing the size and complexity, and consequently the cost of the lens systems. To contain the number and size of lens elements as the NA was increased, the lens system designs had to incorporate aspheric lenses and off-axis mirror elements (catadioptric designs). Further, as the NAs approached 0.9, the polarization effects could no longer be ignored and illumination polarization control became an essential part of the lithography process, further complicating the lithography tools and processes.[84,97] State-of-the-art dry 193 nm stepper optics have an NA of about 0.93, contain about 30 lenses, with a path length through lens material of about 1 m, and weigh 500 kg or more.[10] With dry NA limit of 1.0, there is very little possible gain left to justify the vastly increased cost and complexity needed for improvement—an exponential increase in cost for an asymptotic gain. The $\sin \theta$ factor is now also essentially tapped out.

Figure 19.10 shows, along with the critical feature size (half pitch), the limiting value of 0.25λ for each wavelength. Clearly, by 2006, the critical feature size 65 nm had approached its limit for 193 or 157 nm. In the 1990s, this projection was the reason why it was nearly universally assumed that alternative technologies, such as EUV lithography, would have to take over below this feature size. This has turned out to be incorrect primarily for two reasons: the NA is not limited to 1 if immersion fluids are included and the effective k_1 factor can be decreased below 0.25 with multiple exposures and processing on the same layer.

19.3.2 193 nm Immersion Lithography

Equation 19.1 is valid at the image plane, which of course must be in the resist. In principle, the $NA = n \sin \theta$ should be evaluated in the resist, which typically has a 193 nm index in the range


Lens
n^{lens}
NA = n^{lens} sin θ_1
Fluid
n^{fluid}
= n^{fluid} sin θ_f
θ_r
Resist
n^{resist}
= n^{resist} sin θ_r

FIGURE 19.11 Schematic of an on-axis ray and a marginal ray through the last elements of an immersion lithography optical system. The angles θ_l, θ_f, and θ_r are the angles of the marginal ray with respect to the surface normal in the lens, fluid, and resist, respectively. For the case shown here, the refractive index of the fluid is less than that of the lens and resist, and n^{fluid} is then the maximum possible NA of the system.

$n = 1.6$–1.7. However, by Snell's law ($n_1 \sin \theta_1 = n_2 \sin \theta_2$), NA = $n \sin \theta$ can equally well be evaluated above the resist. Until the recent introduction of the immersion stepper, the space between the final lens element and the wafer was filled with air or N_2 gas, with an index near $n = 1.0$. A consequence is that in spite of the much higher index of the resist, the NA has a maximum value of 1.0. However, as microscopists have known and exploited for centuries, adding a fluid between the image plane and the final lens element allows the maximum NA to be increased.[98–100] For a planer final lens element, the NA can theoretically be increased up to the lowest index of the resist, the fluid, or the lens, as indicated in Equation 19.4 and Figure 19.11:

$$\text{NA}_{\max} \le (n^{\text{resist}}, n^{\text{fluid}}, n^{\text{lens}}) \tag{19.4}$$

A nearly ideal immersion fluid for 193 nm lithography turned out to be purified water. It has sufficient transparency at this wavelength, is relatively innocuous to the resist and lens materials, is compatible with resist processing, has low enough viscosity to enable rapid wafer scanning, and is inexpensive. These properties enabled remarkably rapid development and implementation of immersion technology.[101] From the inception of substantial 193 nm immersion lithography efforts in late 2002,[102–105] it took only about 4 years for production-worthy water immersion systems to be built and the process brought into production. Immersion imaging does introduce some new issues, however, including bubble formation in the fluid, evaporation residue defects, resist-immersion fluid interactions, and fluid thermal effects. Polarization effects, already issues for dry systems, have been exacerbated at the extreme NAs of immersion lithography, requiring careful polarization control for differently oriented structures, which puts some restrictions on IC design.[106]

With water as the immersion fluid, having a 193 nm index of $n^{\text{water}} = 1.437$, the theoretical minimum half pitch ($\text{HP}^{\min}$) for a 193 nm exposure tool decreases to $\text{HP}^{\min} = 0.25 \times 193.4\,\text{nm}/1.437 = 33.6\,\text{nm}$. Furthermore, at HPs achievable for dry systems, Equations 19.1 and 19.3 show that for the same HP, the DOF is larger for the immersion approach. Note that the minimum HP for 157 nm dry systems is $\text{HP}^{\min} = 0.25 \times 157.6\,\text{nm}/1.0 = 39.4\,\text{nm}$, higher than that for 193 nm immersion systems. Attempts were made to identify high-index 157 nm immersion fluids, but only relatively low-index (n [157 nm] ≈ 1.35) fluorocarbon liquids were found to have any practical transparency at 157 nm,[107] and consequently 157 nm lithography technology was dropped from technology roadmaps. As of 2008, water-based 193 nm immersion lithography systems are being operated at an NA in the range of 1.30–1.35 to satisfy the 45 nm technology node with acceptable process latitudes.[14]

Approaches to extend 193 nm immersion lithography technology further with higher-index fluids have been pursued. Practical 193 nm transmitting organic fluids with 193 nm indices near $n = 1.65$ nm (second generation fluids) have been developed.[108,109] However, the last stepper lens element is made of calcium fluoride with a 193 nm index of $n = 1.50$, or fused silica, with an index of $n = 1.57$. By Equation 19.4, these materials are the bottlenecks for resolution extension. Thus, significant NA gain from higher-index fluids requires higher-index last lens materials as well. Higher-index UV lens materials have been explored for this purpose. Key practical materials identified include $Lu_3A_5O_{12}$ (LuAG) [$n = 2.21$] and polycrystalline $MgAl_2O_4$ (ceramic spinel) [$n = 1.93$].[110] LuAG has the highest index, but efforts have not yet succeeded in improving the 193 nm transmission to the specifications, which are stringent due to its high thermo-optic coefficient, dn/dT. Also, the large value of the intrinsic birefringence for this material is difficult to compensate for. Ceramic spinel solves this problem with its polycrystalline structure, but the polycrystalline nature also results in a high degree of scattering. A further possible high-index lens material being considered is α-Al_2O_3 (crystalline sapphire) [$n = 1.92$]. Its large natural birefringence due to its uniaxial crystal structure has limited its use in precision optics. However, with its crystal optic axis oriented along the optical axis of the system and with the polarization of all rays arranged to be oriented perpendicular to this axis, a sapphire last lens element could be manageable. As of this writing, LuAG is considered the most promising high-index lens material candidate,[111] and the industry is still considering whether the practical NA gain to about 1.50 is worth the development effort.

If a third-generation immersion fluid with an index near or above $n = 1.80$ could be developed, then an NA increase to near NA ≈ 1.7 could provide enough incentive to justify the substantial development effort required to implement it, because this would enable the 32 nm half-pitch technology node. Pure organic fluids with indices this high cannot have practical 193 nm transmissions. However, the indices of the fluids could in principle be increased to this level by loading the liquids with approximately (2–10) nanometer-size suspended particles of high-index oxide crystals, e.g., HfO_2 or LuAG, while maintaining acceptable transmission, scattering levels, and viscosities.[112–114] This approach is being explored, but it is regarded at best as complementary to multiple patterning approaches to resolution extension discussed next.

19.3.3 Double Patterning

The process-dependent k_1 factor has been driven down to near the hard limit of $k_1 = 0.25$ for single exposures. However, for multiple exposures and processing steps on the same layer, structures with half pitches corresponding to lower effective k_1 values are possible. A number of these multiple patterning approaches are now being pursued and these are expected to satisfy the requirements for the 32 nm half-pitch technology node and possibly the 22 nm node and below. These approaches differ by the number and sequence of exposure and processing steps used to achieve the desired features. Four basic types are illustrated schematically in Figure 19.12.[14] They all use the fact that while the structure pitch created by a single exposure is limited by diffraction, as characterized by Equation 19.1, processing can be used to tailor the line/space ratios in each period, and subsequent exposure and/or processing steps can interleave further structures to increase the structure density. In the Litho-Etch-Litho-Etch process, Figure 19.12a, two Litho-Etch processes are done in sequence with the second process shifted by half the period to give a pitch doubling. This general process can be used to create arbitrary structures with the half pitch shrunk by a factor of 2 below the diffraction limit, though this scale shrink requires tighter tolerances on line edge control and overlay, among other issues.

A serious difficulty with this process is that it requires that the wafer be taken out of the stepper track for etching and then realigned before the second exposure, creating overlay challenges and decreasing the throughput for the layer by a factor of about 2. A preferred approach would have the two exposures done in sequence with just one etch step at the end: Litho-Litho-Etch, shown in Figure 19.12b. Unfortunately, it can be shown that for a resist system with a linear dose response, as has been universal in DUV lithography, two exposures cannot generate patterns with pitches below the diffraction limit. However, with a nonlinear dose response system, this is possible. A number of nonlinear response approaches are being pursued, including contrast enhancement layers, 2-photon resists, and positive-and negative-tone threshold response resists.[115] One version, Litho-Freeze-Litho-Etch, shown in Figure 19.12c, is, particularly promising.[116] In this approach, the latent image captured in the resist from the first exposure is "frozen" by chemical treatment. The first frozen image region is protected from any photo response to a second exposure, then a single etch step can create the pitch-doubled structures.

A different approach, known as side wall (or spacer assist) double patterning, requires only one exposure step to create pitch doubling.[117] As illustrated in Figure 19.12d, the first exposure and development step is only to create sidewalls at the desired positions. A subsequent thin-film deposition on the sidewalls, chemical-mechanical polishing (CMP) to split the deposited structure,


Litho-Etch-Litho-Etch
Resist
Si
1st Litho
(resist-expose-develop)
1st Etch
2nd Litho
(resist-expose-develop)
2nd Etch
(a)
Litho-Litho-Etch (double exposure)
Nonlinear
resist
1st Litho
(nonlinear resist-expose)
2nd Litho
(expose-develop)
Etch
Least steps but
requires nonlinear
response process
(b)
Litho-Freeze-Litho-Etch
1st Litho
(resist-expose-develop)
"Freeze" 1st pattern
2nd Litho
(expose-develop)
Etch
(c)
Side wall process (spacer assist)
1st Litho
(resist-expose-develop)
Side-wall deposition
CMP
Etch
(d)

FIGURE 19.12 Double patterning approaches: (a) Litho-etch-litho-etch requires 2 exposures and 2 etch steps. (b) Litho-litho-etch (or double exposure) requires 2 exposures and only one etch step, but needs a resist process with a nonlinear dose response. (c) Litho-freeze-litho-etch has intermediate complexity, requiring 2 exposures, a chemical freezing process after the first exposure, and one etch step. (d) Side wall process (spacer assist) requires one exposure and one etch. It uses side wall deposition and chemical-mechanical polishing (CMP) to achieve doubled pitch.

and elimination of the original pattern enables the desired pitch doubled structures. This approach takes advantage of the well-understood and highly controllable thin-film-deposition technology to obtain the desired linewidths, independent of diffraction limits. Furthermore, the sidewall-derived structures are automatically self-aligned by the original structure. A difficulty with this approach is that restriction to patterning along sidewalls makes design layout much more difficult, and not all structures are topologically possible with single exposures. At least a further exposure/processing step is generally required for arbitrary structures. Still, this method is inherently extendable, and pitch quadrupling, etc. is possible in principle.

19.3.4 Ultimate Resolution Limits of DUV Lithography

Double patterning methods are already being used in IC production, and they are the declared technology solutions, using 193 nm water immersion tools, for several volume semiconductor manufacturers for the 32 nm half-pitch technology node projected for about 2013.[14] These approaches appear feasible for further resolution shrinking as well, e.g., the 22 nm half-pitch technology node. Redesign of 193 nm immersion steppers with high-index fluids and lens materials, in combination with double patterning techniques, offer the potential for further resolution extension and relaxation of the k_1 factor for a given resolution. When double patterning becomes routine, consideration of triple patterning, quadruple patterning, etc. may become tempting. However, this would likely have to come at the cost of much tighter process control requirements, such as CD and overlay control, than is presently attainable. Improvements to meet the requirements, along with the increased complexity (more exposures and processing steps per layer) will surely drive up costs substantially. There is little doubt that these DUV lithography extension approaches can be made to work technically. It is just a matter of whether they can operate at commercially viable costs and whether any reliable alternatives can be implemented at less cost. For example, rapidly increasing mask costs have made the numerous maskless technologies, such as multi electron–beam direct write schemes, very attractive, at least for low-volume production.

For high-volume leading-edge ICs, it is generally agreed that for the 22 nm half-pitch technology node and below, a reliable single-exposure EUV solution, with its larger depth of focus and more natural extendibility, would be preferred. However, formidable challenges, repeated introduction delays, and especially rapidly rising projected costs, have made this solution not so inevitable as it once seemed at the beginning of the decade. Cost is the ultimate driver. If or when DUV lithography is displaced, and what its ultimate practical resolution limits are, is now less clear than ever. The technology has thrived on remarkable innovativeness and resourcefulness and its development history does not suggest that these will cease. Previous predictions of its limits and of its imminent replacement have always been wrong.

19.4 Electron-Beam Lithography

Electron-beam lithography has demonstrated its utility over several decades as both a primary pattern generation tool for the semiconductor industry and as the premiere means of patterning small structures for advanced device development and research in myriad fields. Like any lithographic technology, its suitability for a given application depends on its performance with respect to the four metrics of resolution, throughput, pattern placement, and cost-of-ownership. As we shall see in the following sections, electron-beam systems excel with respect to resolution and pattern placement, but suffer from fundamental limits in terms of throughput.

19.4.1 Resolution

Resolution in a lithographic process is a rather ill-defined quantity since, by virtue of the fact that it is a process involving many steps, a large number of variables are involved. These can frequently be manipulated to produce isolated features far smaller than might, at first sight, be judged possible. The true test of the process is the minimum pitch of the features that can be fabricated. In what follows, we will consider primarily those factors that are unique to electron-beam exposure and neglect those that are common across the various exposure techniques—those are covered elsewhere in this chapter.

The ultimate resolution that can be obtained using electron-beam exposure is determined by the nature of the interactions of the electrons with the material being exposed. There are two parts to be considered: first, the trajectories that the incident, or primary, electrons follow within the material and second, the processes by which the energy deposited by the primary electrons is translated into developable chemistry in the exposed material.

The electron trajectories are determined by the combination of incident electron energy and resist/substrate atomic number.[118,119] At low energies/high atomic numbers, the electrons scatter strongly within the solid, which leads to substantial broadening of the beam as it penetrates the material. Since most resist materials are organic, their average atomic numbers are not dissimilar from that of carbon, so the beam broadening, or forward scattering in the resist, is determined principally by the electron energy. For this reason, most high-resolution systems operate at energies of 50–100 keV. In addition, because the beam broadening increases progressively as the electrons undergo additional elastic scattering events on their way through the resist, thin resists yield higher resolution images. Very low (<500 eV) incident energies have also been proposed as a means of generating high-resolution images.[120–122] In this case, the beam broadening is on the order of and constrained by the very short total range of the electrons within the resist. The resist thickness is therefore limited to that range, which may be insufficient for subsequent processing needs, and the resolution can only be improved by reducing the energy (and the resist thickness) to impractically small values.

The incident electron energy, E_0, has a dramatic impact on the dose needed to expose resist, which, for energies above about 5 keV, varies linearly with E_0. This is a reflection of how the inelastic scattering cross section varies with electron energy. The effect is captured by the Bethe continuous slowing-down approximation[123] that describes the average rate at which fast electrons lose energy along their trajectories. At high energies and resist thicknesses that are small relative to the electron range, the feature width is determined not by the deviations in the trajectories of the primary electrons due to elastic scattering, but by the volume in which they deposit energy. Although the primary electrons can cause chemical changes in the resist directly, it is normally assumed that the so-called fast secondary electrons generated by inelastic scattering of the primary beam are responsible for the majority of broken bonds in the resist.[124] This is because the low-energy secondary electrons have a much larger interaction cross section than those of the primary beam.[118] Conceptually, each primary electron trajectory can be thought of as surrounded by a cylinder of material 10–20 nm in diameter exposed by the secondaries that it generates. At very low incident electron energies, the stopping power increases significantly and the electrons deposit all their energy efficiently in the resist film, rather than carrying on through to the substrate.[125]

The resolution that can be achieved in a resist can also be estimated by considering the impact parameter for energy-loss events for the primary electrons. An electron traveling with velocity v, interacting with a stationary electron at a distance b delivers an impulse having a duration of approximately b/v and contains frequency components, ω, up to v/b. These correspond to a maximum energy transfer, ΔE, of $h\omega/2\pi$.[126,127] For 100 kV electrons and ΔEs of 5, 50, and 500 eV, b is 10, 1, and 0.1 nm, respectively. Normally, the energy scale relevant to resist exposure is on the order of a few electron volts (3.6 eV for the C–C bond), leading to an interaction distance of a few nanometers but in a few cases the energy needed is much higher, corresponding to a core-shell excitation, for example. In systems such as alkali metal halides, in which the exposure mechanism depends on the dissociation of the halide ions from the lattice, resolutions of 1–2 nm are achievable.[128–130] Unfortunately, the doses required are in the C/cm^2 range, which is not practical for manufacturing. Currently, the highest resolution material that is suitable for nanofabrication is hydrogen silsesquioxane (HSQ), which has demonstrated feature sizes as small as 7 nm half-pitch.[131] This is an inorganic, small-molecule resist that essentially forms silica upon exposure and development. Its increased mechanical strength relative to organic resist materials is one reason for its ability to produce small features, while its higher average atomic number may help reduce the range of the fast secondaries, contributing to its high resolution.

Electron–solid interactions also affect the resolution in electron-beam systems through the proximity effect. This is the additional exposure of the resist by electrons backscattered from the substrate and it leads to a loss in contrast and thus to a loss in resolution. At higher voltages and on low-atomic number substrates (e.g., Si or SiO$_2$), the backscattered electrons have a relatively large range ($\propto V^{5/3}$) and the contribution of the forward and backscattered electron doses can be captured by the two-Gaussian model[132]

$$D = D_0\left[e^{x^2/\alpha^2} + \eta e^{x^2/\beta^2}\right] \tag{19.5}$$

where

D_0 is the incident dose
α is the width of the forward-scattering distribution
β is the width of the backscattered distribution
η is the effective dose contributed by the backscattered electrons

As we have discussed above, α is typically on the order of 10 nm, while β is on the order of micrometers. η can be quite large, depending on the substrate's atomic number and is approximately 0.5 for Si at 100 kV.[133] This model is applicable if the forward and backscattered dose distributions can be readily separated. In this case, small, isolated features receive a dose of D_0, the centers of large features receive a dose of $D_0(1 + \eta)$, and all other types of features receive a pattern-density dependent dose that varies between those values. As long as the feature size is small compared with β, this dose variation can be corrected for either by adjusting the dose delivered to individual features,[134] applying the inverse of the background dose to produce a flat background,[135,136] or adjusting the size of the features[137,138] by using a pattern density averaged over a length scale on the order of β. However, if either α or β approach the feature size, then much more computationally intensive techniques must be used to perform an iterative correction procedure, as the correction applied to each feature affects its neighbor and vice versa.[139] At low energies and in high atomic number substrates such as GaAs or InP, the deposited energy distribution is more complex[140,141] and the proximity effect becomes much more difficult to correct. It is, however, important to point out that these phenomena are analogous to the flare and optical proximity effects encountered in advanced optical lithography, for which correction techniques are at an advanced stage of development.

So far in our discussion, we have implicitly assumed an ideal point source of electrons incident upon the resist. A close approximation can be achieved in practice with low-current, focused probes in electron microscopes. However, for practical applications, we need high beam currents, and this has a dramatic impact on the design and operation of electron-beam lithography tools and leads to systems in which the intrinsic resolution of the resist and process is often better than that of the electron optics.

19.4.2 Throughput

In the design of most optical systems, including electron microscopes, there is a trade-off between blur due to diffraction, which scales as 1/NA, where NA is the numerical aperture of the system, and aberrations that generally scale as some power of NA (a spherical aberration is often a dominant term and varies as NA^3). In electron-beam lithography systems, throughput is critical to their cost of ownership and ultimate utility. Unlike photons in a light-optical system, the electrons in an electron-optical system affect one another strongly through unscreened Coulomb repulsion. The interactions give rise to three principal effects: (1) the forces between electrons along the electron-optical axis lead to the speeding up or slowing down of individual electrons, which is equivalent to an energy spread in the beam, known as the Boersch effect; (2) the average force due to all the other electrons in the beam leads to deterministic changes in electron trajectories and leads, to first order, to an overall defocusing of the beam, known as the global space-charge effect; and (3) the interactions between individual electrons lead to random changes in individual electron trajectories, known as the stochastic space-charge effect. The severity of the Boersch effect depends on the chromatic aberration in the system. The global space-charge effect can be thought of as creating a negative lens in the system whose effects can be compensated for by refocusing the beam. However, if the current density is not uniform across the beam, that lens becomes highly aberrated and its effects cannot be compensated. The stochastic space-charge effect is not correctable. As might be expected, the space-charge effects are made worse when the electrons are forced closer together or can interact for longer periods and increase with beam current, I, and column length, L, and are mitigated when the electrons are spread farther apart or interact for shorter times and decrease with increasing numerical aperture α, the demagnification factor, M, and the accelerating voltage, V. The detailed dependence of beam blur on I, L, V, M, and α is particular to a given system and has been studied in depth for both single-column, probe-forming,[142] and projection systems.[143,144] Note that improvements realized by increasing the voltage are offset by the need to increase the beam current to compensate for the linear decrease in resist sensitivity with voltage.

The net result of these effects is that rather than balancing diffraction and aberration blurs, the system optimization must be performed by balancing space-charge and aberration blurs. This means that for any given beam current in a system, there is an optimum numerical aperture that must be used and a corresponding minimum blur that can be achieved. Any attempt to increase the beam current leads to an increase in beam blur. Electron-beam lithography systems for nanofabrication research are generally designed to provide the optimum resolution, with throughput as an important, but secondary goal. However, the semiconductor industry's continuing demand for ever-smaller features and higher throughputs has resulted in the disappearance of electron-beam lithography from the direct IC fabrication process because of the conflict between the need for increased beam currents to increase throughput and the need for the decreased beam currents necessary for improving resolution cannot be resolved at the feature sizes now required.

In the future, the throughput of electron-beam lithography, even for mask making, is likely to become worse. To understand why this is the case, it is necessary to examine how resist sensitivity scales with feature size.

If we consider a feature of CD L and allow it to vary by no more than $L/10$, then we can define an image pixel as $L/10 \times L/10$. In order for each pixel to be faithfully reproduced, we need the resist to be able to clearly distinguish between exposed and unexposed pixels. Even if the dose over a large area is fixed at a precise value, the arrival of the electrons at any pixel is a statistical process, with the number of electrons delivered following a Poisson distribution. This effect is frequently referred to as shot noise and has been extensively studied.[145–149] We can, therefore, define a minimum number, n, of electrons per pixel that is necessary to ensure that the error rate of improperly exposed pixels is suitably small. The total dose needed per unit area therefore becomes $100n/L^2$, i.e., it scales as $1/L^2$, and the beam current necessary to maintain a given real exposure rate must therefore scale in the same fashion.

19.4.3 Overlay

The fact that magnetic and electric fields can deflect electrons precisely and at high speed is one of the great strengths of electron-beam systems. In optical lithography systems, accurate and precise registration and overlay can only be achieved by ensuring nanometer-scale mechanical alignment between mask and wafer stages—physically massive systems that can only be controlled with bandwidths of a few tens of Hz. In electron-beam tools, it is not necessary to control the stage precisely (offsets of several micrometers between the actual and planned stage coordinates are common), because the position of the electron beam can be adjusted, at speeds of up to 100 kHz, to make up the difference, provided a suitable signal from the stage interferometers is available. There are generally differences in the coordinate system that are generated by the stage and the substrate. Normally, these are accounted for by periodically acquiring alignment mark information from the substrate. This procedure is susceptible to errors arising from drift occurring between mark measurements and schemes have been developed that enable registration data to be generated from the substrate continuously.[150] The ability to adjust the position of the beam, as well as characteristics such as focus and stigmation, in real time, makes it possible to correct for a large variety of errors, such as those caused by variations in substrate height. Along with the benefits it brings, the sensitivity to fields is also a source of difficulty associated with electron-beam systems: interference from dynamic fields must be reduced as far as possible, while that from static ones, such as those due to the small magnetic inhomogeneities of the stage, must be carefully mapped and calibrated out.

Another source of error peculiar to electron-beam tools, particularly at high voltages, is substrate heating. The total amount of energy deposited in the substrate scales as the square of the accelerating voltage because of the combination of the increasing energy per electron and the increasing resist dose required. The concomitant substrate heating can affect both pattern placement/overlay, as a result of thermal expansion,[151] and CD control, as resist sensitivity may vary with temperature.[152] Temperature increases are more severe in SiO_2 substrates because of silica's poor thermal conductivity, while Si substrates, with their higher coefficient of thermal expansion, are liable to greater placement errors.

19.4.4 Cost of Ownership

As we have seen, although electron-beam systems provided exceptional resolution, and are capable of precise pattern placement,[153] they are fundamentally limited in throughput. Historically, for relatively large feature sizes, the limiting factor in throughput was the serial nature of the writing process in probe-forming, or Gaussian-beam, systems and this led to the development of schemes such as shaped-beam,[154] cell-projection,[155] large-area,[6,156] and full-field projection[157] that sought to deliver more than one pixel's worth of information at a time. Unfortunately, as feature sizes decreased and the resolution requirements became more demanding, they all ran into space-charge limits. This has relegated electron-beam systems for production purposes to the fabrication of small numbers of high-value items such as photomasks, CD/DVD masters, and nanoimprint templates. There are two routes out of this dilemma: the first is to accept the limited throughput, but use the essential addressability of electron beams to create flexible systems—maskless lithography tools—that can create ICs without the need for masks and their associated costs;[158,159] the second is to avoid the space-charge limits of single columns by dividing and conquering—using multiple small columns to keep the electrons far enough apart so that their interactions are insignificant.[160,161] In the first case, the cost of ownership is competitive with photolithography for short-production run devices where only a few wafers worth of devices are produced for each mask set. In the second case, providing that issues associated with source uniformity, control, and brightness can be overcome, then it may be possible to have the best of both worlds—flexibility in patterning together with high throughput—making it directly competitive with optical lithography. Research and development are active in both areas.

19.5 Nanoimprint Lithography

Nanoimprint lithography (NIL) is rapidly emerging as a low-cost, high-resolution, and versatile alternative to optical lithography as a patterning technology for semiconductor fabrication and other applications that incorporate nanoelectronic devices.[162,163] Optical lithographic techniques, including state-of-the-art tools based on 193 nm radiation[98] or next-generation potential solutions, including extreme ultraviolet (EUV, 13.5 nm radiation) lithography,[164–166] rely upon selectively exposing a photoactive film to radiation via a photomask that defines the lithographic pattern of interest. A chemical reaction occurs in the exposed regions of the film that renders them soluble in an aqueous base, creating a physical pattern defined by the unexposed regions in the film. It is becoming increasingly difficult to control the resolution of this patterning process.

NIL offers a potentially simplified alternative to chemically amplified resists. All NIL techniques rely on a simple squeeze-flow mechanism whereby a resist flows into a well-defined physical cavity of nanoscale dimensions. It is a molding or replication technique where the ultimate resolution is defined by the physical dimensions of the imprint mold cavities.[167–170] If high-resolution masters can be created, high-resolution copies can be generated. It is also a repetitive stamping or replication technique. The well-defined patterns in the imprint master can be used to create thousands of replicas, analogous to how the metallic master for an LP record were used to stamp thousands of inexpensive vinyl copies for consumer use. Compared with optical lithography for high-volume nanomanufacturing, there is an important distinction worth highlighting. With optical lithography, every printing or copy of the nanostructured surface requires extremely tight control of the environmental conditions to maintain the sensitive balance of the complicated reaction, diffusion, and dissolution process for the chemically amplified resists.[171] This is precisely why state-of-the-art optical lithography tools cost upwards of $30 M apiece, providing a 65 nm patterning resolution, and semiconductor fabrication lines cost billions of dollars to construct.

The resolution of NIL is largely controlled by a simple squeeze-flow process.[167–170] As long as high-quality, high-resolution imprint masters can be fabricated, it is relatively easy to stamp out copies of the mold. In optical lithography, the ultimate patterning resolution is intrinsically coupled with the high volume manufacturing process making process control measures extremely important. Every single copy manufactured requires stringent control over the reaction, diffusion, and dissolution processes. With NIL, the resolution is less coupled with the high-volume manufacturing process and more dependent on the mold or imprint master fabrication. For these reasons, NIL tools tend to be significantly less expensive. Research and development grade imprint tools can be purchased for about $100 K, while manufacturing grade tools cost approximately $2 M, both with a sub 10 nm resolution.

Both optical and nanoimprint lithography are dependent on high-resolution masks or masters. In optical lithography, the mask sets required to fabricate a semiconductor device can cost several millions of dollars to produce, comprising a significant fraction of the manufacturing costs. These are phase-shifting optical masks in which blanket UV radiation is exposed to one side, generating selectively exposed regions in the resist film on the other side. This exposure is also done through a series of lenses where the features in the mask are approximately four times larger than the image at the wafer plane. In NIL, these mask costs are likely to increase. The squeeze-flow is a direct write process where the features in the mold are the same size as the features in the wafer plane; there is no longer this 4x reduction. This means that high-resolution and costly electron-beam lithography is needed to fabricate the imprint masks, compared with optical lithography where the mask resolution requirements are somewhat reduced because of the lens system. There are no lenses in NIL and the imprint masks may very well be more costly to produce. Furthermore, these expensive NIL mask sets must be mechanically pressed into the resist film. In optical lithography, the masks are isolated from the resist behind a transparent and protective pellicle. There are no protective pellicles in NIL and one must make direct mechanical contact of the expensive mask with the resist film.

In this section, we provide a general overview of the NIL technology. Our discussion will be largely limited to the field of nanoelectronics, including complementary metal-oxide semiconductor (CMOS) devices, although NIL is also widely considered to be a manufacturing alternative for several other forms of nanotechnology. We will elaborate on the differences between NIL and existing optical lithography techniques and discuss some of the unique materials and metrology challenges that NIL processes introduce. We will also provide a brief overview of some of the recent developments in applying NIL to nanoelectronics technologies.

19.5.1 Variations of NIL

19.5.1.1 Thermal NIL

NIL generically refers to pressing a hard mold or template decorated with nanoscale patterns into a softer material to lithographically define well-controlled nanostructures.[167–170] In most cases, pattern formation is accomplished by a squeeze-flow mechanism whereby the material flows into the mold in a liquid-like state (Figure 19.13). Of course, this requires "setting" the pattern in the liquid material. In the thermal embossing form of NIL, the resist is typically a glassy polymer.[167,168] During the imprint process, the film and the imprint mold are heated to above the glass transition of the polymer while applying an external pressure. Under elevated pressure and temperature, the polymer flows into the cavities of the mold. The pattern is set by cooling the system to below the glass transition of the polymer, where the material vitrifies into a rigid glass. When the mold is separated from the substrate, the surface is left with nanoscale patterns that are relief images of the mold cavities. A cavity in the mold becomes a polymeric pattern on the surface.



FIGURE 19.13 Schematic of the NIL process, showing both the thermal and UV forms.

The thermal embossing form of NIL is similar in concept to many of the bulk molding or forming processes used to manufacture large scale plastic components. High molecular mass polymers, even at temperatures far above their glass transition, tend to be high viscosity fluids. Flow does not always readily occur under quiescent conditions meaning that pressures must be applied to squeeze the material into the mold. Most NIL tools designed for thermal embossing are capable of applying pressure as high as 5 MPa. This is combined with maximum temperatures of typically 200°C–300°C, which means that most tools are capable of exceeding the rubbery plateau modulus for most polymer melts and able to induce material flow.

There are several different options when it comes to applying the heat and pressure for thermal NIL. One class of tools is largely based on the photomask aligner and wafer bonding systems widely used in the semiconductor industry. In many instances, an imprint module can be purchased as an add-on for an existing tool. In these systems, mechanical platens with heating elements are used to apply the temperature and pressure to the imprint mold and substrate. Their advantages are that they provide uniform heating through the large thermal mass of the platens and they often have a built-in capability for optical overlay alignment between the imprint mold and the substrate. The primary disadvantage is that maintaining parallel contact between the platens can be difficult. Misalignment of just a few μm can prevent conformal contact, which makes it very difficult to imprint nanoscale features over large areas. To overcome the conformal contact issues, some imprint tools utilize hydrostatic gas pressure to squeeze the imprint mold into the resist film.[172] This pressure is applied through what is essentially a deformable gas bladder. Since the NIL molds or masters are usually etched into thin Si or quartz wafers and imprinted onto similar thin Si substrates, the molds and wafers are able to bend or flex to a certain extent and increase the degree of conformal contact. In some tools, the pressure is applied through the top through the gas bladder while the substrate rests on a rigid metallic platen that provides the heating. These systems provide an optimal balance between uniform heating and conformal contact. There are also tools that utilize an entirely soft press technology, where pressure is applied through both the top and bottom through deformable gas bladders. In these cases, the bladders are transparent and the heating of the substrate is provided through infrared heat lamps. This soft press technology maximizes the pressure uniformity across the mold and substrate while the reduced thermal mass (no platens) allows for rapid heating and cooling rates. However, the noncontact optical heating means that temperature uniformity and stability are more difficult to achieve.

19.5.1.2 UV NIL

One disadvantage of thermal NIL is that it requires heating and applying pressure to the substrate. For certain applications, the patterned substrate may or may not be able to withstand the thermal budget associated with this process. Likewise, large temperature changes can induce thermal distortions, which make overlay and alignment difficult. UV NIL offers a low temperature alternative to thermal NIL. In UV NIL, the resist is a liquid-like (or low viscosity) monomer that readily flows into the mold cavities at room temperature with no heating and very little pressure.[169,170] In many instances, the liquid monomer is actually wicked into the mold via capillary forces, minimizing distortions of the substrate or the template (Figure 19.13). In the mold, the monomer undergoes a cross-linking reaction upon exposure to UV radiation, creating a hard glassy pattern that retains its shape after separating the mold from the substrate. This means that either the NIL mold or the supporting substrate must be transparent to the appropriate UV radiation. For this reason, the molds are typically fabricated in quartz wafers, whereas silicon and nickel are more common materials in thermal NIL. An additional requirement is that UV NIL is limited to patterning materials that cross-link under UV radiation. Thermal NIL can, in principle, be applied to any material in which flow can be induced.

19.5.1.3 Transfer Printing

Both the thermal and UV forms of NIL described thus far are similar to optical lithography in that a pattern is created in a resist film that has been previously deposited on the substrate of interest. It is also possible to employ the NIL technologies in a material transfer mode that is similar to most industrial forms of printing. In transfer printing, the material that is to be patterned is first applied to a patterned stamp or mold and then transferred via mechanical contact to the target substrate. This requires tuning of the differential adhesion between the pattern mold and the substrate such that the material adheres to the substrate more strongly than the patterned mold. There are two primary modes in which transfer printing can occur[173] (Figure 19.14). The first is a whole layer transfer where a continuous film with a nanoscale texture defined by the mold topology is transferred to the substrate. The second is a discrete transfer or inking mode where material is selectively transferred to the substrate from the protrusions of the mold; any material in the cavities of the mold is not transferred over. Whole layer transfer is used primarily to create topological patterns of a given material on the target substrate. Examples of this technology are being used to create nano- or microfluidic channels or devices. The discrete transfer mode can also be used to create physical patterns, but it also has the ability to create chemical patterns of a given surface energy or chemical functionality by essentially inking monolayers of a chemical compound. In this last case, the pattern may, to a first approximation, lack topology and not alter the smooth surface of the substrate. Chemical patterns like these are commonly considered in sensor-type applications.



FIGURE 19.14 Schematic of two modes of transfer printing: (a) whole-layer transfer and (b) inking.

19.5.1.4 Functional Materials

One of the biggest distinctions between NIL and competing optical lithography methods is rooted in the generality of the patterning process. In nearly all forms, optical lithography focuses on creating high-resolution patterns in sacrificial photoresist formulations. As mentioned previously, photoresists are highly complicated materials systems that balance chemical reactivity, acid diffusivity, and their dissolution behavior to optimize their patterning resolution. Once the pattern is formed, the resist becomes a sacrificial component for subsequent additive or subtractive processes to transfer the pattern into the functional materials of interest. On the contrary, the mechanical stamping and squeeze-flow processes used in NIL are generic mechanisms applicable to a wide range of materials. This means that a wide range of materials can be patterned directly by NIL, including functional materials. The resolution of NIL processes is controlled by the mold or mask fabrication process more so than optical lithography. The ability to directly stamp nanoscale structures into functional materials is a highly attractive way to simplify the number of parameters impacting patterning resolution, reduce the number of nanofabrication steps, and thereby reduce manufacturing costs.[174]

19.5.1.5 Tool Types

NIL is a low-cost nanopatterning alternative to optical lithography with the potential for high-volume manufacturability. Mechanical stamping processes have a long history in manufacturing environments and the same appears to be bearing true for the emerging field of nanomanufacturing. Stamping processes are intrinsically compatible with manufacturing assembly lines. However, NIL is still in its infancy period and most of the tools that are commercially available today are geared for R&D or the technology development. There are examples of high-throughput tools in the market, but most of the activity is still in the lab as opposed to pre-production. In this section, we review the different types of tools with respect to patterning throughput.

The most versatile tools on the market today also have the lowest throughput and least applicability for high volume nanofabrication. These account for most of the imprint tools sold today from companies like Nanonex, Obducat, or Jenoptik that utilize gas pressure through some type of deformable bladder to apply a very uniform pressure to the mold and the substrate. Typically, these tools are very flexible and provide the user with a wide variety of process control, at the sacrifice of throughput. The user has the freedom to place an arbitrary mold onto an arbitrary substrate, sandwiched between one or two sheets of deformable rubber or foil. This stack is then placed inside a movable gas chamber. The gas chamber closes down on the deformable bladders, creating pressure reservoirs on the top and/or bottom of the sample. A vacuum pumping system is also usually involved to evacuate the sample region between the bladders. Nitrogen or some other inert gas is then pumped into the chamber, generating pressures as high as approximately 5 MPa to press the mold into the substrate. Heat is then applied through either the optical heat lamps or thermal sample block to enable flow of the material into the mold cavity. After a prescribed heating cycle of a few minutes, the temperature is cooled back to room temperature and gas chambers are vented to release the pressure. The sample and the mold are then manually removed from the chamber and manually separated to reveal the patterned substrate. This process obviously describes the thermal form of NIL. The same general process applies for UV NIL with these tools with the exception that lower pressure is required and UV radiation is applied instead of heat. In either case, UV or NIL, these single stamp tools are capable of generating one patterned substrate approximately every 10–15 min with manual input from the user. For most applications, this throughput is not suitable for manufacturing. Rather they are designed for flexibility and ease of use. The sample chambers typically vary from approximately 5–20 cm in diameter and allow arbitrary form factors or piece parts to be imprinted. This is primarily useful for technology development. One notable exception is a large area single imprint tool being developed at the Korean Institute of Machinery and Materials.[175] This is a low pressure UV imprint tool capable of imprinting an entire 45 cm (diagonal) flat panel display uniformly in a single imprint. Cycle times of 4–5 min here would probably be more acceptable given the limited demand for such high-end displays. These cycle times would be totally unacceptable for the high volume demand of bit patterned magnetic media for data storage hard drives.

There are efforts to increase the throughput of imprinting tools. The next class of tools generically utilizes a stamp and repeat technology to generate multiple copies of a single pattern across a large substrate. This form of stamp or step and repeat technology is naturally compatible with the form factor of multiple dies (or devices) per wafer that is currently used in semiconductor fabrication.[170] So these types of tools tend to be targeted for CMOS devices. Molecular Imprints, Inc. is the pioneer in developing step and repeat tools, although other companies including EV Group and Nanonex now offer tools with similar capabilities. Throughput or manufacturability tends to be the primary driver for going from a single imprint to a step and repeat tool. For this reason, most step and repeat tools are based on the UV NIL process, which is usually faster because it lacks the heating and cooling cycles associated with thermal NIL. Furthermore, locally heating a selected region for imprinting on a larger wafer or substrate is difficult. It is much easier and faster to locally expose the imprinted region to UV radiation. Lastly, these step and repeat tools are usually optimized for throughput that comes at the price of the flexibility in the patterning processes or conditions. The general use single imprint tools typically offer greater flexibility. For example, single imprint tools are usually capable of performing either UV or thermal NIL on a variety of materials whereas step and repeat tools tend to be limited to UV NIL patterning of a given resist formulation that has been optimized for the system.

The NIL tools discussed thus far have largely been designed as drop-in replacement technologies for optical lithography, with the target applications in CMOS. However, there have been recent advances in building roll-to-roll NIL tools that are capable of patterning continuous sheets or strips of a nanopatterned substrate.[176,177] Roll-to-roll processes are capable of generating patterned media at a rate at least several orders of magnitude faster than traditional optical lithography, enabling high volume nanofabrication. However, roll-to-roll processes tend to provide very poor overlay capabilities, practically limiting the advantages to single-layer devices. For these reasons, the target applications migrate away from CMOS to emerging markets where nanopatterning has yet to be realized. Examples might include antifouling biological films, polarizing or antireflective optical coatings,[178] brightness enhancing films for large area displays, or flexible electronic devices like radio frequency ID tags.[179] In the roll-to-roll form of NIL, the mold cavities are fabricated onto either a circular drum or a tractor tread-like device. A continuous film is fed in between a pair of rollers that rotate in opposite directions, squeezing their textured surface(s) into the film. Roll-to-roll processes can be implemented in many different forms. The thermal form of NIL can be used to emboss nanoscale topology on the film or substrate by using heated rollers. Likewise, there are examples of UV NIL being implemented to create textured surfaces with roll-to-roll devices. The traditional forms of gravure or flexography can also be adapted to create roll-to-roll NIL transfer printing processes.

19.5.2 Fundamental Issues

There are a few commercial products being made with imprint today, proof that the technology is inherently manufacturable. Some of the companies operating in this space include Nano Opto, Heptagon, Omron, OVD Kingram, LG Electronics, Reflexite, MacDermid, Wavefront Technologies, and Spectratek.

Dr. Michael P.C. Watts is the founder and president of Impattern Solutions, an independent consulting company in the field of NIL. The company's website tracks the progress and commercialization of imprint-related technologies and provides updates at www.impattern.com. Most of the commercial success stories in the imprint field have thus far been related to optics or light. These include, in order of decreasing critical dimensions, refractive, diffractive, and sub-wavelength optical devices. However, even with the sub-wavelength devices, the minimum dimensions of the structures being fabricated commercially are typically on the order of 100 nm or larger, which by many definitions, is not within the nanoscale domain. The community has yet to see the realization of devices fabricated by NIL with dimensions strongly into the sub-100 nm regime. There are many examples of nanoelectronic technologies in the R&D phase that appear to have strong potential with respect to NIL, but several fundamental issues need to be resolved before these ideas can successfully make the transition from the lab to manufacturing. In this section, we briefly summarize some of the remaining technical roadblocks to the commercialization of nanoelectronics via NIL techniques.

19.5.2.1 Nanoimprint Materials Development

There are several examples of high resolution patterning being achieved with NIL. For years, Professor Chou's fabrication of 10 nm vias was the ultimate demonstration of high resolution pattering with NIL.[168] More recently, Professor John Roger's group demonstrated that the fabrication of 2 nm replicas of carbon nanotubes randomly distributed across a rigid substrate could be created within a polydimethylsiloxane (PDMS) resin using NIL processes.[180] Professor Chou's group has gone on to report the patterning periodic line-space patterns with a 6 nm half-pitch,[181] indicating that NIL has the potential resolution and patterning control that is commensurate with nanoelectronics (Figure 19.15).



FIGURE 19.15 Examples of high resolution patterning with NIL. Panels (a) shows a few carbon nanotubes with a diameter of 2 nm on a flat surface that served as the model imprint mold while panel (b) shows the resulting patterns that were replicated in PDMS. (Reprinted from Hua, F. et al., *Nano Lett*., 4(12), 2467, 2004. With permission. © 2004, American Chemical Society.) Panel (c) shows well regular line-space patterns that have been imprinted with critical dimension to a 6 nm half-pitch. (Reprinted from Austin, M.D. et al., *Nanotechnology*, 16(8), 1058, 2005. With permission.)

However, there is still a need for improving NIL materials or resists. Resolution is only part of the picture and a NIL resist must also satisfy a number of different properties. First, the material must be able to readily flow into the imprint mold. If harsh conditions that plastically deform the patterned material are required, the NIL processes may induce residual stress into the patterns.[182–184] It is desirable that the patterned media readily flows into the imprint mold. Likewise, the imprinted patterns must have the mechanical strength to resist pattern collapse. There are several examples of the critical aspect ratio for pattern collapse with decreasing feature size.[185] NIL is capable of generating very small patterns that make pattern collapse a significant concern. Furthermore, it is critical that the mold separates easily from the imprinted structure without destroying the sample. This requires both low surface energy mold treatment strategies that minimize adhesion between the imprint and the substrate as well as imprint materials with the cohesive strength to withstand the shear stress generated during mold separation.[186] Since external forces are required to pry the mold from the substrate, a mechanical load is placed on the patterns. It is a significant materials science challenge to maximize these properties simultaneously especially with functional nanoimprint materials.

19.5.2.2 Template Fabrication and Availability

The fabrication and availability of high quality templates or molds are crucial for NIL patterning technologies. With an ultimate resolution approaching just a few nm, even the slightest flaw in the master has the potential to be replicated into hundreds or thousands of imprinted copies. This means that significant efforts must be made to produce high quality imprint masters. Electron-beam (e-beam) lithography is the industry standard for producing high-resolution patterns with a resolution on the order of 10–20 nm. However, e-beam lithography is not practical for manufacturing since it is a slow, serial writing process and is very costly. One of the greatest attributes of NIL is that it can be considered as an e-beam replication technique. Once a costly pattern is fabricated by e-beam lithography into a mold or master material, thousands of high-resolution copies of the pattern can be replicated via NIL processes at a fraction of the initial cost.[187] This is a very attractive proposition, but it also means that a high quality imprint master is critical. Any mistake will be easily propagated through all of the copies.

19.5.2.3 Defect Inspection and Dimensional Metrology

The need to have high quality imprint templates has been articulated in the preceding section. Hand-in-hand with this requirement is the need to evaluate, quantify, and certify the pattern quality in both the imprint master and the resulting imprints. High-resolution patterning demands high-resolution pattern metrology. We have already mentioned the excessive costs for fabricating a NIL master or mold with large areas patterned with nanoscale features. Quantitative measurements to qualify that the imprint master meets the design specifications in terms of pattern shape are absolutely critical for making this investment. Likewise, fast and efficient high-resolution pattern metrology methods are also needed to monitor the high volume manufacturing processes. It is critical to have quantitative measures in place to determine if the manufacturing processes drift out of tolerance. For high-resolution patterning, this means high-resolution metrology. Even at the current 65 nm technology node, the “Metrology” chapter of the ITRS Roadmap contains roadblocks in terms of high-resolution CD metrologies.[188] The leap from 65 nm optical lithography to NIL processes that offer better than a 5 nm resolution raise significant concerns regarding our ability to quantitatively evaluate the patterns that we fabricate. This is not that big of an issue in the R&D phase of technology development, where one usually deals with highly optimized prototypes. However, high volume manufacturing processes demand quantitative process monitoring capabilities. With respect to pattern shape metrology, the ability to pattern with NIL greatly exceeds the limits of the current inspection tools.

NIL is essentially a direct pattern transfer process whereby the patterns in the imprint have the potential to be a mirror image of the patterns in the mold. This brings up the fidelity of the pattern transfer concept—how closely do the imprinted features resemble the mold. To achieve the greatest fidelity of pattern transfer, one must be able to minimize the shrinkage of the imprinted material in the mold (either up cross-linking or cooling) or any distortions of the pattern after imprinting. The fidelity of the pattern transfer concept is fundamentally unique to NIL. However, in NIL one can directly compare the dimensions of the mold cavity to the pattern to quantify the fidelity of the pattern transfer. This means that dimensional metrologies must be able to quantify both the mold and the imprinted patterns.[189]

19.5.2.4 Residual Layer Control

The objective in most imprint processes is typically to create isolated patterns on the substrate. However, there is always a continuous residual layer of resist material between the substrate and the patterns that needs to be removed. Simple volume filling arguments dictate the thickness of the residual layer, comparing the volume of material per unit area in the smooth film to the volume of the cavities in the mold. Even if there is less material in the film than there is in the mold cavities, the protrusions of the mold cannot be completely pressed into direct contact with the substrate; there is always a finite residual layer on the order of a few nanometers thick. While this residual layer is easily removed through reactive ion etching (RIE) processes, it is critical to achieve both a minimized and uniform residual layer. The minimized residual layer is important to maintain CD control. RIE processes are highly anisotropic, etching primarily vertically, however, there is a small amount of lateral trimming that occurs (Figure 19.16). If one has to etch through a thick residual layer, then the extent of lateral trimming can be significant; minimizing the residual layer minimizes the trimming. Furthermore, it is important to achieve a uniform residual layer across the entire field of the imprint. If there are thick and thin regions of residual layer, the RIE will break through to the substrate first in the thinner regions. When this happens, a micro loading effect occurs in the etch process where the concentration of plasma increases upon breakthrough (the plasma etch chemistries are biased to consume resist over the substrate). The result of micro-loading is an increased lateral etch rate, i.e., a localized enhancement in the lateral trimming. This nonuniform lateral trimming leads to a distribution of the pattern dimensions (loss of CD control).



FIGURE 19.16 A schematic illustrating how an accurate knowledge and control of the residual layer thickness is critical to controlling lateral trimming and critical dimension control. Overestimating the thickness of the residual layer can lead to excessive lateral trimming. A non-uniform residual layer can lead to a distribution of linewidths and a loss of CD control through a micro-loading effect.

Controlling the residual layer thickness is straight forward for imprint molds with uniform pattern fields. Simple volume filling calculations can be used to adjust the thickness of the film to minimize the residual layer, assuming that a uniform pressure is applied.[190] However, residual layer control becomes difficult when the pattern field contains a distribution of different patterns with different sizes and density. In this case, the volume filling calculations are different for the different regions of the mold.[191] Resist films are usually applied via spin coating techniques, which leads to a film of uniform thickness. In these situations, it is difficult to control the residual layer. The Molecular Imprints series of tools use a GDS-based drop on demand technology to deposit an optimized amount of resist material in each location to properly fill the mold. This technique can be very effective for minimizing the residual layer.[192,193]

19.5.3 Overlay Accuracy and Control

Depending on the application, it may or may not be important to align the imprint within the lateral directions with some features or fiduca markers on the substrate. There are many applications, such as anti-reflective optical coatings, where pattern overlay is not required. However, for nanoelectronic applications, one could imagine it being very important to align the imprint with circuit elements in the substrate. Most imprint tools offer some type of alignment capability. The alignment is usually achieved by fabricating a series of vernier gratings in both the imprint mold and the patterning substrate and use interferometers to sense very small changes in the in-plane dimensions.[194] Piezoelectric actuators can be incorporated into the imprint head to generate very small lateral position corrections that help precisely align the mold with the substrate. Most general use imprint tools are designed for molds and substrates that are not transparent, meaning that the comparison of the interference pattern from the two verniers is achieved through a series of mirrors and reflective light. With these types of tools, one is able to achieve overlay accuracies on the order of ±200 nm in the in-plane directions. Given the 5 nm or better patterning resolution of NIL, the accuracy with which a feature can be placed within the plane of the film is significantly worse. There are tools with higher overlay accuracy. Molecular Imprints produces highly specialized tools that are optimized for patterning with UV radiation only, using quartz molds that are optically transparent.[195] When it comes to overlay alignment, systems that are dedicated to patterning with transparent molds have a significant advantage because through wafer comparison of the optical verniers is possible. Eliminating the series of mirrors and reflective optics reduces the error in the overlay alignment, enabling sub-15 nm 3σ overlay accuracy. This is more commensurate with the ultimate patterning resolution of a few nm.

19.5.4 Technology Examples

There are a growing number of examples in the literature of nanoelectronic devices being fabricated by NIL processes, proving that the technique has potential (Figure 19.17). The most common examples are the cross-bar memory structures where a semiconducting material is sandwiched between orthogonally situated parallel line-space electrodes to be used as either data storage or logic devices.[196] Here, NIL processes are used to fabricate the parallel line-space electrode arrays. These devices can have half-pitch values as small as 17 nm for the electrode arrays and memory densities as high as 100 Gbit/cm^2. On the CMOS front, a recent joint effort from Toshiba and Molecular Imprints have demonstrated the fabrication of a functional sub-32 nm logic circuit using NIL.[197] Likewise, IBM and SEMATECH have reported the fabrication of 27 nm functional FINFET structures using NIL technologies.[198] Another sector where NIL processes are being widely adapted is for magnetic data storage media. The equivalent Moore's law for the hard disc industry is even more aggressive than that of the semiconductor industry, doubling in data storage capacity ever 12 months. To keep pace with this trend, the industry is moving towards bit patterned media. NIL processes are being developed to fabricate 25 nm posts of magnetic media on a pitch of approximately 40 nm.[199] These are just a few examples related to nanoelectronics where NIL technologies are being actively pursued. There are also a number of other applications in the optical and biotechnology fields where NIL methods are poised to have an impact. Two of the most prominent examples include wire grid polarizer elements for screen and display technologies[200,201] and photonic structures to facilitate light extraction in high brightness LEDs.[187]

19.5.5 Future Perspectives

In some respects, NIL is just one of a long list of next-generation lithography techniques that has been developed as an alternative to deep UV optical lithography for the semiconductor industry. However, none of these alternate technologies have even come close to supplanting optical lithography as the high volume lithography of choice for the electronics industry. While a debate over the merits of NIL to replace optical lithography for CMOS fabrication is beyond the scope of this review, it is important to realize that NIL is the first next generation lithography candidate to have a viable life outside of CMOS, and there are already success stories for the patterning technology in non-CMOS technologies. This means that the success or failure of NIL is not tied to the semiconductor industry; it has already succeeded. As microelectronics moves beyond CMOS into nanoelectronics with novel device architectures, dramatically different principals of operation, and the need for nanoscale patterning, NIL is on-pace to be a well-established generic nanoscale patterning technology of relevance. Next generation lithography techniques tied directly to the CMOS community (193 nm immersion, double patterning, EUV) are solely dependent on this community for success or failure. These patterning technologies will likely go away if they are not adapted by the semiconductor community. The same is not true for NIL.



FIGURE 19.17 Examples of several different technologies fabricated with NIL techniques: (a) a high-resolution image taken from the 17 nm half-pitch cross-bar nanowire circuit arrays made by SNAP. (Reprinted from Jung, G.Y. et al., *Nano Lett.*, 6(3), 351, 2006. With permission. © 2006, American Chemical Society.) (b) Bit patterned magnetic media for high density data storage showing 25 nm magnetic posts fabricated by NIL. (Reprinted from Dobisz, E.A. et al., *Proc. IEEE*, 96(11), 1836, 2008. With permission. © 2008, IEEE.) (c) A cross-sectional view of a 27 nm FinFET structure whose critical dimension was patterned by Step-and-Flash Imprint Lithography at Molecular Imprints, Austin, TX. Nominally identical structures led to functional FinFET devices. (From IBM Almaden Research Center, San Jose, CA. With permission.) (d) An array of photonic devices patterned uniformly over an entire 6 nm wafer for high brightness LED devices. (Reprinted from Miller, M. et al., *Proc. SPIE*, 6883, 68830D, 2008. With permission.)

19.6 Metrology for Nanolithography

19.6.1 Advanced Lithographic Processes

As optical lithography reaches its limits, new processes such as double patterning and double exposure are being explored as means of extending 193 nm immersion-based lithography. The goal of these patterning methods is patterning at dimensions that are less than those that can be printed in a single lithographic exposure step. Each of these process-based methods poses a unique challenge to all aspects of process control including metrology. These processes are summarized in Figures 19.18 through 19.20.[188]

Double exposure uses two reticles that must be precisely aligned so that the pattern placement is one pitch across the printed area. One photoresist layer is exposed twice with specially designed reticles resulting in densely spaced lines. This pattern can then be etched into the underlying films patterning the wafer with features having a ½ pitch less than can be printed using one reticle. This process is shown in Figure 19.18.

Double patterning is also done using two reticles that must be aligned with accuracy, so that the pattern placement has one pitch and close to one linewidth across the printed area. The first photoresist layer is exposed and then the film stack is etched leaving the pattern in the hard mask layer. Then the wafer is coated with BARC and resist and the second set of lines is patterned into the second BARC/resist layer. The resultant double pattern structure is etched into the poly silicon. Figure 19.19 provides great detail for double patterning processes for lines. Similar process steps are used for contacts and trenches.

Spacer double patterning is believed to be already in use in manufacturing. A slightly different film stack is used for spacer double patterning. First, a sacrificial poly silicon layer is patterned, spacer oxide is deposited, and the sacrificial poly silicon layer is removed resulting in a spacer pattern. This pattern is etched into the poly silicon layer. In Figure 19.20, this single reticle process is more fully described. The origin of the two sets of line shapes is due to the different shapes of each side of a spacer. The two sets of critical dimensions are due to the nature of the spacer deposition process.


"Positive" resist double exposure
Mask 1
Resist
Poly silicon
Wafer
(a)
"Positive" resist double exposure
Mask 1
1. Lithography step 1: Expose lines
Mask 2
2. Lithography step 2: Expose second set of lines
3. Etch step: Etch poly silicon lines
(b)

FIGURE 19.18 The double exposure method of patterning lines is shown. Lines are patterned using positive resist. (a) shows the film stack, and (b) shows the patterning process.


"Positive" resist dual patterning
1:1 mask
Line: space
Resist
BARC
Hard mask
Poly silicon
SiO$_2$
Wafer
(a)
Film stack
"Positive" resist dual patterning
1. 1st lithography step: Expose to ~1:2 in resist.
2. 1st etch: Trim leaving hard mask at 1:3
3. Coat with BARC and resist
4. 2nd lithography & 2nd etch steps: Expose and trim leaving 2nd set of lines at 1:3
5a. Etch pattern into poly silicon
5b. SEM cross-section showing two types of lines
100 nm
(b)

FIGURE 19.19 The double patterning method of patterning lines is shown. Lines are patterned using positive resist. (a) shows the film stack, and (b) shows the patterning process.


"Positive" resist spacer dual patterning
1:1 mask
Line: space
Resist
BARC
Sacrificial Poly
SiO$_2$
Poly silicon
SiO$_2$
Wafer
(a)
"Positive" resist spacer dual patterning
1. 1st lithography step: Expose to ~1:2 in resist.
2. 1st etch: Trim leaving sacrificial layer
3. Spacer deposition
4. Etch sacrificial lines
5. Etch poly silicon
100 nm
http://www.imec.be
(b)

FIGURE 19.20 The spacer double patterning method is shown. Lines are patterned using positive resist. (a) shows the film stack, and (b) shows the patterning process.

Overlay plays an important role in double pattering, spacer patterning, and double exposure pattering of lines. Overlay must be near perfect to achieve a uniform pitch. If the second exposure is shifted, every other space will be different. This impacts further processing, the measurement of CD and lineshape, and device performance. Etch is known to be sensitive to lineshape and the distance between lines. Etch uniformity can be reduced when the resist pattern is etched into the layer below.

19.6.2 Metrology for Advanced Lithography Processes

Measurement needs start with control of feature shape and placement on the mask (reticle), and follow through until the features are etched into the active layer of the device or interconnect structure.[188] Since optical masks are glass with chrome features, scanning electron microscope (SEM)-based measurements must overcome the charging inherent in the measurement of an insulator. The chrome features must have the correct linewidth and shape and must be placed on the mask in the correct position relative to each other. The recent introduction of "environmental" SEM allows for charge neutralization during the SEM-based measurement of CD and line shape on the mask.

The advanced lithographic process challenge metrology mainly through the two distributions of critical dimensions and line shapes especially the side wall angles of the lines. Two methods of CD measurement are used during manufacturing, namely CD-scanning electron microscopy (CD-SEM) and scatterometry. The term scatterometry typically refers to one of two optical methods of measuring critical dimensions using a grating test structure. One example of a grating test structure is an array of lines with a constant pitch and linewidth. Others include an array of contact holes. Scatterometry measurements can be done in a spectroscopic ellipsometer; the main challenge is analyzing the changes in the optical response that the grating structure imparts versus the response of an un-patterned film stack. The other approach to scatterometry is to measure the diffraction pattern from a single wavelength across a range of angles. Both methods of scatterometry require that an extensive database of simulated ellipsometric responses be placed into a library. Some libraries contain tens to hundreds of thousands of simulated structures for a single process step. Data from a sample is matched to this set of simulated responses. Accuracy requires that ellipsometry be sensitive to the small differences in optical response.

Ellipsometry measures the change in polarization of light after reflection from the sample surface. Spectroscopic ellipsometry-based scatterometry relies on the changes in polarization due to changes in the grating test structure as a function of wavelength. Advanced lithographic processes pose two challenges to scatterometry. One is shrinking feature size and the second is the two sets of distributions of CD and feature shape. Sensitivity to small changes in dimension is becoming increasingly difficult as feature size decreases below 50 nm for both CD-SEM and scatterometry. The previous method of single exposure and etch patterning required that scatterometry measure the average CD and line shape of a uniform grating structure. Double patterning and double exposure requires that scatterometry produce the average CD and line shape of two distributions of line shape. In situations where overlay errors result in a nonuniform pitch, the number of simulated data sets is greatly increased. Small differences in optical response make it very difficult to distinguish changes in CD and line shape. Recent commercial instrumentation extended the wavelength range of scatterometry further into the UV down to 150 nm. In general, UV wavelengths have improved the ability of scatterometry to measure CD and line shape for features with sub 50 nm dimensions.

The specifics of ellipsometry-based scatterometry are useful in understanding how critical dimensions are determined from a method associated with the determination of film thickness for unpatterned layers. The premise of ellipsometry is that light polarized in-plane of reflection (P) reflects differently than light polarized perpendicular to the plane of reflection (S). Ellipsometry determines the change in polarization of light in terms of Δ, which is the difference in phase change $= \Delta_P - \Delta_S$ and Ψ, which is related to the ratio of the change in intensity upon reflection through $\tan^{-1}(|R_P|/|R_S|)$, where R_P and R_S are the complex reflectivity's parallel and perpendicular to the reflectance plane. The reflectivity is determined by the dielectric function of the film stack. Reflection from a single film on a substrate depends on the complex dielectric function (refractive index) of the materials and the Fresnel reflection coefficients r_{12} between (1) air and (2) the film and r_{23} between (2) film and (3) the substrate. The reflection from an unpatterned film is determined by well-understood reflection coefficients[202]

$$R_P = \frac{(r_{12}^P + r_{23}^P e^{-i2\beta})}{(1 + r_{12}^P r_{23}^P e^{-i2\beta})} \qquad (19.6)$$

$$R_S = \frac{(r_{12}^S + r_{23}^S e^{-i2\beta})}{(1 + r_{12}^S r_{23}^S e^{-i2\beta})} \qquad (19.7)$$

where

$$\beta = 2\pi\left(\frac{d}{\lambda}\right) N_2 \cos\phi \qquad (19.8)$$

The film thickness dependence comes from the exponential term β where d is the film thickness, λ is the wavelength of the light, and N_2 is the complex refractive index of the film. The measurement of a patterned film stack requires that Maxwell's equations be solved. Typically, this is done using a rigorous coupled wave approximation (RCWA), and the RCWA equations must be solved at each wavelength for each structure. Changes in Ψ and Δ vs wavelength require solving the RCWA equations at enough wavelengths to observe subtle changes due to CD and line shape.[202]

The CD-SEM measurement of critical dimensions is also challenged by double patterning and double exposure. Measuring patterned photoresist requires the calibration of the rate of shrinkage of the resist vs. electron beam exposure time. This calibration requires the collection of enough data to provide statistically significant shrinkage rates. This must be done for each resist material. It is important to note that different resists are used for the fabrication of line and vias. Many IC manufacturers hold the resist formulas to be proprietary meaning that each resist formula will have different responses to electron beam exposure. Recent unpublished studies show that resist lines with a CD less than 25 nm shrink more rapidly than lines with a greater CD. Scatterometry measurements may also impact resist lines especially when measurements are done in UV.

There are important differences between CD-SEM and scatterometry in terms of the nature of information each provides. Advanced CD-SEM is capable of measuring the CD of two or more lines simultaneously. Future CD-SEMs may be able to measure several lines in a test area providing the average CD as well as the range of the CD in the test area. Scatterometry provides the average CD in the test area.

The measurement of line edge roughness in resist is critical for the control of device performance including leakage current. Industry standards organizations such as SEMI have driven consensus documents describing measurement methods for quantifying line edge roughness.[203] Line edge roughness on a nm scale produces gate CD width roughness that results in an increase in leakage current. Line edge roughness at longer scales produces an increase in carrier surface scattering that increases line resistivity. At this time, line edge roughness measurements can be done using CD-SEM or CD-AFM.

Overlay metrology is considerably more challenging for advanced lithography processes. Overlay measurements are typically done using specially designed optical microscopes and target structures that are patterned into both the upper and lower layers. Double patterning of trenches for interconnect lines have additional complications for metrology. If the overlay is shifted, then the trench CD also changes. Overlay measurement precision for all double patterning methods becomes at best a factor of 0.7 of the overlay required for a single exposure patterning of all the trenches. This has driven the development of new overlay test structures that include scattering bars that diffract light. SEM may provide an alternate means of measuring overlay.

19.6.3 Proposed New CD Metrology Methods

Many have speculated about the demise of CD-SEM and scatterometry. Even optical microscopy-based CD measurement is still done for features have larger CDs such as microelectromechanical systems (MEMS). It is possible that CD-SEM and scatterometry can not extend beyond the 22 nm half pitch. Two methods are being considered as potential replacements for scatterometry and CD-SEM. These are small angle x-ray scattering, which is known as CD-SAXS,[204] and He ion microscopy.[205] In CD-SAXS, a focused, monochromatic x-ray beam is transmitted through a grating test structure, as shown in Figure 19.21, that is similar to the ones used for scatterometry measurement. It is important to note that CD-SAXS can measure line edge roughness, average CD, individual CD, and line shape for the lines in the test structure.[206–209] At this time (2009), evaluation of the capabilities of He ion microscopy are in the initial stages.



FIGURE 19.21 CD SAXS schematic of using collimated x-ray beams with energy that are transmissive through a patterned silicon wafer resulting in scattering from an array of patterns.

Abbreviations

α	Fraction of light absorbed, when referring to resist technology
α	Width of the forward-scattering distribution, when referring to electron-beam lithography
β	Width of the backscattered distribution, when referring to electron-beam lithography
δ	Photoacid diffusion length, when referring to resist technology
ε	Photoacid generation efficiency, when referring to resist technology
η	The effective dose contributed by the backscattered electrons, when referring to electron-beam lithography
BARC	Bottom anti-reflective coating
CD	Critical dimension
CD-SEM	Critical dimension scanning electron microscope
CD-SAXS	Critical dimension small-angle x-ray scattering
CD-AFM	Critical dimension atomic force microscopy
CMOS	Complementary metal-oxide semiconductor
CMP	Chemical mechanical polishing
De	Dose at line-edge, when referring to resist technology
D_0	Incident dose, when referring to electron-beam lithography
DOF	Depth of focus
DUV	Deep-ultraviolet
E_0	Incident electron energy, when referring to electron-beam lithography
EUV	Extreme-ultraviolet
FINFET	Nonplanar, double-gate field effect transistor, “fin” refers to shape of semiconductor
HP	Half-pitch

HSQ	Hydrogen silsesquioxane
IC	Integrated circuit
ITRS	*International Technology Roadmap for Semiconductors*
LILS	Latent-image log slope
LED	Light emitting diode
LER	Line-edge roughness
LWR	Line-width roughness
MEMS	Microelectromechanical systems
MG	Molecular glass
ML2	Maskless lithography
NA	Numerical aperture
NIL	Nanoimprint lithography
PAG	Photoacid generator
PDMS	Polydimethylsiloxane
q	Number of photons/nm^2, when referring to resist technology
RIE	Reactive ion etch
SCALPEL	Scattering with angular limitation in projection electron-beam lithography
STM	Scanning tunneling microscopy
UV	Ultraviolet

Official contribution of the National Institute of Standards and Technology; not subject to copyright in the United States.

Certain commercial equipment and materials are identified in this paper in order to specify adequately the experimental procedure. In no case does such identification imply recommendations by the National Institute of Standards and Technology nor does it imply that the material or equipment identified is necessarily the best available for this purpose.

References

1. Moore, G. E., Cramming more components onto integrated circuits, *Electronics*, **38**, 114–117 (1965).
2. Huff, H., *Into the Nano Era, Springer Series in Materials Science*, Springer-Verlag, Berlin, Germany, **106**, (2009).
3. Maydan, D., Coquin, G. A., Maldonado, J. R. et al., High-speed replication of submicron features on large areas by x-ray lithography, *IEEE Transactions on Electron Devices*, **ED22**(7), 429 (1975).
4. Silverman, J. P., X-ray lithography: Status, challenges, and outlook for 0.13 mu m, *Journal of Vacuum Science & Technology B*, **15**(6), 2117 (1997).
5. Harriott, L. R., Berger, S. D., Biddick, C. et al., The SCALPEL proof of concept system, *Microelectronic Engineering*, **35**(1–4), 477 (1997).
6. Liddle, J. A., Berger, S. D., Biddick, C. J. et al., The scattering with angular limitation in projection electron-beam lithography (SCALPEL) system, *Japanese Journal of Applied Physics Part 1—Regular Papers Short Notes & Review Papers*, **34**(12B), 6663 (1995).
7. Tennant, D., Limits of conventional lithography, in G. M. Timp (ed.), *Nanotechnology*, AIP/Springer, New York, Chap. 4, p. 161 (1999).
8. Marrian, C. R. K. and Tennant, D. M., Nanofabrication, *Journal of Vacuum Science & Technology A*, **21**(5), S207–S215 (2003).
9. Brunner, T. A., Why optical lithography will live forever, *Journal of Vacuum Science & Technology B*, **21**(6), 2632 (2003).
10. Levinson, H. J., *Principles of Lithography*, 2nd edn., SPIE Press, Bellingham, WA, (2005).
11. Brillouet, M., An introduction to ultimate lithography, *Comptes Rendus Physique*, **7**(8), 837 (2006).
12. Ito, H., Chemical amplification resists for microlithography, *Advances in Polymer Science*, **172**, 37 (2005).
13. Chandhok, M., Datta, S., Lionberger, D., and Vesecky, S., Impact of line-width roughness on Intel's 65-nm process devices, *Advances in Resist Materials and Processing Technology XXIV, SPIE*, **6519**, 65191A (2007).
14. *International Technology Roadmap for Semiconductors*, 2007 edition, http://www.itrs.net, Lithography, p. 10. SEMATECH, Austin, TX.
15. Wallraff, G. M. and Hinsberg, W. D., Lithographic imaging techniques for the formation of nanoscopic features, *Chemical Reviews*, **99**(7), 1801 (1999).
16. Gallatin, G. M., Naulleau, P., Niakoula, D. et al., Resolution, LER, and sensitivity limitations of photoresists, *Emerging Lithographic Technologies XII, SPIE*, **6921**, 69211E (2008).
17. Bristol, R. L., The tri-lateral challenge of resolution, photospeed, and LER: Scaling below 50 nm? *Advances in Resist Materials and Processing Technology XXIV, SPIE*, **6519**, 65190W (2007).
18. Van Steenwinckel, D., Gronheid, R., Lammers, J. H. et al., A novel method for characterizing resist performance, *Advances in Resist Materials and Processing Technology XXIV, SPIE*, **6519**, 65190V (2007).
19. Wallow, T., Higgins, C., Brainard, R. et al., Evaluation of EUV resist materials for use at the 32 nm half-pitch node, *Emerging Lithographic Technologies XII, SPIE*, **6921**, 69211F (2008).
20. Fedynyshyn, T. H., Goodman, R. B., and Roberts, J., Polymer matrix effects on acid generation, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 692319 (2008).
21. Pawloski, A. R., Christian, and Nealey, P. F., A standard addition technique to quantify photoacid generation in chemically amplified photoresist, *Chemistry of Materials*, **13**(11), 4154 (2001).
22. Szmanda, C. R., Brainard, R. L., Mackevich, J. F. et al., Measuring acid generation efficiency in chemically amplified resists with all three beams, *Journal of Vacuum Science & Technology B*, **17**(6), 3356 (1999).
23. Brainard, R., Hassanein, E., Li, J. et al., Photons, electrons, and acid yields in EUV photoresists: A progress report, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 692325 (2008).

24. Hinsberg, W., Houle, F. A., Hoffnagle, J. et al., Deep-ultraviolet interferometric lithography as a tool for assessment of chemically amplified photoresist performance, *Journal of Vacuum Science & Technology B*, **16**(6), 3689 (1998).
25. Pawloski, A., Acheta, A., Lalovic, I., LaFontaine, B., and Levinson, H., Characterization of line edge roughness in photoresist using an image fading technique, *Proceedings of the SPIE, Advances in Resist Technology and Processing XXI*, **5376**, 414 (2004).
26. Houle, F. A., Hinsberg, W. D., Sanchez, M. I., and Hoffnagle, J. A., Influence of resist components on image blur in a patterned positive-tone chemically amplified photoresist, *Journal of Vacuum Science & Technology B*, **20**(3), 924 (2002).
27. Houle, F. A., Hinsberg, W. D., Morrison, M. et al., Determination of coupled acid catalysis-diffusion processes in a positive-tone chemically amplified photoresist, *Journal of Vacuum Science &Technology B*, **18**(4), 1874 (2000).
28. Croffie, E., Yuan, L., Cheng, M. S. et al., Modeling influence of structural changes in photoacid generators an 193 nm single layer resist imaging, *Journal of Vacuum Science & Technology B*, **18**(6), 3340 (2000).
29. Itani, T., Yoshino, H., Fujimoto, M., and Kasama, K., Photoacid bulkiness on dissolution kinetics in chemically amplified deep ultraviolet resists, *Journal of Vacuum Science & Technology B*, **13**(6), 3026 (1995).
30. Vogt, B. D., Kang, S., Prabhu, V. M. et al., Measurements of the reaction-diffusion front of model chemically amplified photoresists with varying photoacid size, *Macromolecules*, **39**(24), 8311 (2006).
31. Vogt, B. D., Kang, S., Prabhu, V. M. et al., The deprotection reaction front profile in model 193 nm methacrylate-based chemically amplified photoresists, *Advances in Resist Technology and Processing XXIII, Proceedings of SPIE*, **6153**, 615316 (2006).
32. Shi, X. L., Effect of Coulomb interaction and pKa on acid diffusion in chemically amplified resists, *Journal of Vacuum Science & Technology B*, **17**(2), 350 (1999).
33. Goldfarb, D. L., Angelopoulos, M., Lin, E. K. et al., Confinement effects on the spatial extent of the reaction front in ultrathin chemically amplified photoresists, *Journal of Vacuum Science & Technology B*, **19**(6), 2699 (2001).
34. Lin, E. K., Soles, C. L., Goldfarb, D. L. et al., Direct measurement of the reaction front in chemically amplified photoresists, *Science*, **297**(5580), 372 (2002).
35. Vogt, B. D., Kang, S., Prabhu, V. M. et al., Influence of base additives on the reaction diffusion front of model chemically amplified photoresists, *Journal of Vacuum Science & Technology B*, **25**, 175 (2006).
36. Wu, W. L., Prabhu, V. M., and Lin, E. K., Identifying materials limits of chemically amplified photoresists, *Advances in Resist Materials and Processing Technology XXIV, SPIE*, **6519**, 651902 (2007).
37. Lavery, K. A., Choi, K. W., Vogt, B. D. et al., Fundamentals of the reaction-diffusion process in model EUV photoresists, *Advances in Resist Technology and Processing XXIII, SPIE*, **6153**, 615313 (2006).
38. Houlihan, F., Person, D., Nalamasu, O. et al., Study of base additives for use in a single layer 193 nm resist based upon poly(norbornene/maleic anhydride/acrylic acid/tert-butyl acrylate), *Proceedings of the SPIE—The International Society for Optical Engineering*, **4345**, 67 (2001).
39. Pawloski, A. R., Christian, and Nealey, P. F., The multifunctional role of base quenchers in chemically amplified photoresists, *Chemistry of Materials*, **14**(10), 4192 (2002).
40. Houle, F. A., Hinsberg, W. D., and Sanchez, M. I., Acid-base reactions in a positive tone chemically amplified photoresist and their effect on imaging, *Journal of Vacuum Science & Technology B*, **22**(2), 747 (2004).
41. Hinsberg, W. D., Houle, F. A., Sanchez, M. I., and Wallraff, G. M., Chemical and physical aspects of the post-exposure baking process used for positive-tone chemically amplified resists, *IBM Journal of Research and Development*, **45**(5), 667 (2001).
42. Hinsberg, W., Houle, F., Sanchez, M. et al., Effect of resist components on image spreading during postexposure bake of chemically amplified resists, *Proceedings of the SPIE—The International Society for Optical Engineering*, **3999**, 148 (2000).
43. Michaelson, T. B., Pawloski, A. R., Acheta, A., Nishimura, Y., and Willson, C. G., The effects of chemical gradients and photoresist composition on lithographically generated line edge roughness, *Proceedings of SPIE*, **5753**, 368 (2005).
44. Hinsberg, W., Houle, F. A., Lee, S. W., Ito, H., and Kanazawa, K., Characterization of reactive dissolution and swelling of polymer films using a quartz crystal microbalance and visible and infrared reflectance spectroscopy, *Macromolecules*, **38**(5), 1882 (2005).
45. Hinsberg, W. D., Houle, F. A., Ito, H., Kanazawa, K., and Lee, S. W., Kinetics of reactive dissolution of lithographic polymers, *Proceedings of the 13th International Conference on Photopolymers*, *Advances in Imaging Materials and Processes*, *RETEC* 2003, 193 (2003).
46. Hinsberg, W. D., Houle, F. A., and Ito, H., Reactive dissolution of lithographic copolymers, *Proceedings of the SPIE, Advances in Resist Technology and Processing XXI*, **5376**, 352 (2004).
47. Houle, F. A., Hinsberg, W. D., and Sanchez, M. I., Kinetic model for positive tone resist dissolution and roughening, *Macromolecules*, **35**(22), 8591 (2002).
48. Prabhu, V. M., Vogt, B. D., Kang, S. et al., Direct measurement of the spatial extent of the in situ developed latent image by neutron reflectivity, *Journal of Vacuum Science & Technology B*, **25**(6), 2514 (2007).
49. Prabhu, V. M., Vogt, B. D., Kang, S. et al., Direct measurement of the in situ developed latent image: The residual swelling fraction, *Proceedings of SPIE*, **6519**, 651910 (2007).
50. Prabhu, V. M., Rao, A., Kang, S., Lin, E. K., and Satija, S. K., Manipulation of the asymmetric swelling fronts of photoresist polyelectrolyte gradient thin films, *The Journal of Physical Chemistry B*, **112**(49), 15628 (2008).

51. Wang, M. X., Gonsalves, K. E., Rabinovich, M., Yueh, W., and Roberts, J. M., Novel anionic photoacid generators (PAGs) and corresponding PAG bound polymers for sub-50 nm EUV lithography, *Journal of Materials Chemistry*, **17**(17), 1699 (2007).
52. Wang, M. X., Lee, C. T., Henderson, C. L. et al., Incorporation of ionic photoacid generator (PAG) and base quencher into the resist polymer main chain for sub-50 nm resolution patterning, *Journal of Materials Chemistry*, **18**(23), 2704 (2008).
53. Fukushima, Y., Watanabe, T., Ohnishi, R. et al., Optimization of photoacid generator in photoacid generation-bonded resist, *Japanese Journal of Applied Physics*, **47**(8), 6293 (2008).
54. Wu, H. P. and Gonsalves, K. E., Preparation of a photoacid generating monomer and its application in lithography, *Advanced Functional Materials*, **11**(4), 271 (2001).
55. Hirayama, T., Shiono, D., Hada, H., and Onodera, J., New photoresist based on amorphous low molecular weight polyphenols, *Journal of Photopolymer Science and Technology*, **17**(3), 435 (2004).
56. VanderHart, D. L., De Silva, A., Felix, N., Prabhu, V. M., and Ober, C. K., The effect of EUV molecular glass architecture on the bulk dispersion of a photo-acid generator, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 69231M (2008).
57. Young-Gil, K., Kim, J. B., Fujigaya, T., Shibasaki, Y., and Ueda, M., A positive-working alkaline developable photoresist based on partially tert-Boc-protected calix[4]resorcinarene and a photoacid generator, *Journal of Materials Chemistry*, **12**(1), 53 (2002).
58. Chang, S. W., Ayothi, R., Bratton, D. et al., Sub-50 nm feature sizes using positive tone molecular glass resists for EUV lithography, *Journal of Materials Chemistry*, **16**(15), 1470 (2006).
59. Yang, D., Chang, S. W., and Ober, C. K., Molecular glass photoresists for advanced lithography, *Journal of Materials Chemistry*, **16**(18), 1693 (2006).
60. De Silva, A., Lee, J. K., Andre, X. et al., Study of the structure-properties relationship of phenolic molecular glass resists for next generation photolithography, *Chemistry of Materials*, **20**(4), 1606 (2008).
61. Felix, N. M., De Silva, A., Luk, C. M. Y., and Ober, C. K., Dissolution phenomena of phenolic molecular glass photoresist films in supercritical CO2, *Journal of Materials Chemistry*, **17**(43), 4598 (2007).
62. De Silva, A., Felix, N., Sha, J., Lee, J. K., and Ober, C. K., Molecular glass resists for next generation lithography, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 69231L (2008).
63. De Silva, A., Felix, N., Forman, D., Sha, J., and Ober, C. K., New architectures for high resolution patterning, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 69230O (2008).
64. Toriumi, M., Santillan, J., Itani, T., Kozawa, T., and Tagawa, S., Dissolution characteristics and reaction kinetics of molecular resists for extreme-ultraviolet lithography, *Journal of Vacuum Science & Technology B*, **25**(6), 2486 (2007).
65. Nishimura, I., Heath, W. H., Matsumoto, K. et al., Non-chemically amplified resists for 193 nm lithography, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 69231C (2008).
66. Lawson, R. A., Lee, C. T., Yueh, W., Tolbert, L., and Henderson, C. L., Single molecule chemically amplified resists based on ionic and non-ionic PAGs, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 69230K (2008).
67. Naulleau, P. P., Anderson, C. N., Chiu, J. et al., Latest results from the SEMATECH Berkeley extreme ultraviolet microfield exposure tool, *Journal of Vacuum Science & Technology B* **27**, 66 (2009).
68. Woodward, J. T., Choi, K. W., Prabhu, V. M. et al., Characterization of the latent image to developed image in model EUV photoresists, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 69232B (2008).
69. Choi, K. W., Prabhu, V. M., Lavery, K. A. et al., Effect of photo-acid generator concentration and developer strength on the patterning capabilities of a model EUV photoresist, *Proceedings of SPIE*, **6519**, 651943 (2007).
70. Zimmerman, P. A., Byers, J., Piscani, E. et al., Development of an operational high refractive index resist for 193 nm immersion lithography, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 692306 (2008).
71. Matsumoto, K., Costner, E., Nishimura, I., Ueda, M., and Willson, C. G., High-index resist for 193-nm immersion lithography, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 692305 (2008).
72. Gonsalves, K. E., Wang, M., and Pujari, N. S., High refractive-index resists composed of anionic photoacid generator (PAG) bound polymers for 193 nm immersion lithography, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 69231P (2008).
73. Liu, H. P., Blakey, I., Conley, W. E. et al., Application of quantitative structure property relationship to the design of high refractive index 193i resist, *Journal of Micro-Nanolithography MEMS and MOEMS*, **7**(2), 023001 (2008).
74. Allen, R. D., Brock, P. J., Sundberg, L. et al., Design of protective topcoats for immersion lithography, *Journal of Photopolymer Science and Technology*, **18**(5), 615 (2005).
75. Terai, M., Kumada, T., Ishibashi, T. et al., Mechanism of immersion specific defects with high receding-angle topcoat, *Advances in Resist Materials and Processing Technology XXIV, SPIE*, **6519**, 65191S (2007).
76. Takebe, Y., Shirota, N., Sasaki, T., and Yokokoji, O., Development of top coat materials for ArF immersion lithography, *Advances in Resist Materials and Processing Technology XXIV, SPIE*, **6519**, 65191Y (2007).
77. Nakagawa, H., Goto, K., Shima, M. et al., Process optimization for developer soluble immersion topcoat material, *Advances in Resist Materials and Processing Technology XXIV, SPIE*, **6519**, 651923 (2007).

78. Sundberg, L. K., Sanders, D. P., Sooriyakumaran, R., Brock, P. J., and Allen, R. D., Contact angles and structure/surface property relationships of immersion materials, *Advances in Resist Materials and Processing Technology XXIV, SPIE*, **6519**, 65191Q (2007).
79. Shirota, N., Takebe, Y., Wang, S. Z., Sasaki, T., and Yokokoji, O., Development of non-topcoat resist polymers for 193-nm immersion lithography, *Advances in Resist Materials and Processing Technology XXIV, SPIE*, **6519**, 651905 (2007).
80. Wada, K., Kanna, S., and Kanda, H., Novel materials design for immersion lithography, *Advances in Resist Materials and Processing Technology XXIV, SPIE*, **6519**, 651908 (2007).
81. Wu, S., Tseng, A., Lin, B. et al., Non-topcoat resist design for immersion process at 32-nm node, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 692307 (2008).
82. Sanders, D. P., Sundberg, L. K., Brock, P. J. et al., Self-segregating materials for immersion lithography, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 692309 (2008).
83. Wang, D., Caporale, S., Andes, C. et al., Design consideration for immersion 193: Embedded barrier layer and pattern collapse margin, *Journal of Photopolymer Science and Technology*, **20**(5), 687 (2007).
84. Smith, B. W., Optics for photolithography, in K. Suzuki and B. W. Smith (eds.), *Microlithography: Science and Technology*, 2nd edn., CRC Press, Boca Raton, FL, (2007).
85. Lin, B. J., The k_3 coefficient in nonparaxial λ/NA scaling equations for resolution, depth of focus, and immersion lithography, *Journal of Microlithography Microfabrication and Microsystems*, **1**(1), 7 (2002).
86. Oldham, W. G. and Schenker, R. E., 193-nm lithographic system lifetimes as limited by UV compaction, *Solid State Technology*, **40**(4), 95–102 (1997).
87. Sewell, H., McClay, J., Jenkins, P. et al., 157 nm lithography—Window of opportunity, *Journal of Photopolymer Science and Technology*, **15**(4), 569 (2002).
88. Burnett, J. H., Levine, Z. H., and Shirley, E. L., Intrinsic birefringence in calcium fluoride and barium fluoride, *Physical Review B*, **64**(24), 241102 (2001).
89. Burnett, J. H., Levine, Z. H., Shirley, E. L., and Bruning, J. H., Symmetry of spatial-dispersion-induced birefringence and its implications for CaF_2 ultraviolet optics, *Journal of Microlithography Microfabrication and Microsystems*, **1**(3), 213 (2002).
90. Kang, H., Bourov, A., and Smith, B. W., Optical lithography at a 126-nm wavelength, *Emerging Lithographic Technologies V, SPIE*, **4343**, 797 (2001).
91. Liberman, V., Rothschild, M., Murphy, P. G., and Palmacci, S. T., Prospects for photolithography at 121 nm, *Journal of Vacuum Science & Technology B*, **20**(6), 2567 (2002).
92. Trintchouk, F., Ishihara, T., Gillespie, W. et al., XLA-300: The fourth-generation ArF MOPA light source for immersion lithography, *Optical Microlithography XIX, SPIE*, **6154**, 615423 (2006).
93. Wong, A. K. K., *Resolution Enhancement Techniques in Optical Lithography*, SPIE Press, Bellingham, WA, (2001).
94. Smayling, M. C., Liu, H. Y., and Cai, L., Low k_1 logic design using gridded design rules, *Design for Manufacturability through Design-Process Integration II, SPIE*, **6925**, 69250B (2008).
95. Borodovsky, Y., Marching to the beat of Moore's Law, *Advances in Resist Technology and Processing XXIII, SPIE*, **6153**, 615301 (2006).
96. Bruning, J. H., Optical lithography: 40 years and holding, *Optical Microlithography XX, SPIE*, **6520**, 652004 (2007).
97. Matsuyama, T., Ohmura, Y., and Williamson, D. M., The lithographic lens: Its history and evolution, *Optical Microlithography XIX, SPIE*, **6154**, 615403 (2006).
98. Kawata, H., Carter, J., Yen, A., and Smith, H. I., Optical projection lithography using lenses with numerical apertures greater than unity, *Microelectronic Engineering*, **9**, 31 (1989).
99. Mulkens, J., Flagello, D., Streefkerk, B., and Graeupner, P., Benefits and limitations of immersion lithography, *Journal of Microlithography Microfabrication and Microsystems*, **3**(1), 104 (2004).
100. Owen, G., Pease, R. F. W., Markle, D. A. et al., 1/8 μm optical lithography, *Journal of Vacuum Science & Technology B*, **10**(6), 3032 (1992).
101. de Klerk, J., Wagner, C., Droste, R. et al., Performance of a 1.35NA ArF immersion lithography system for 40-nm applications, *Optical Microlithography XX, SPIE*, **6520**, 65201Y (2007).
102. Lin, B., Drivers, prospects, and challenges for immersion lithography, *Third International Symposium on* 157 *nm Lithography*, Antwerp, Belgium (2002).
103. Owa, S., Shiraishi, N., Tanaka, I. et al., Nikon F2 exposure tool, *Third International Symposium on* 157 *nm Lithography*, Antwerp, Belgium (2002).
104. Smith, B. W., Kang, H., Bourov, A., and Cropanese, F., Extreme-NA water immersion lithography for 35–65 nm technology, *Third International Symposium on* 157 *nm Lithography*, Antwerp, Belgium (2002).
105. Switkes, M. and Rothschild, M., Resolution enhancement of 157-nm lithography by liquid immersion, *Optical Microlithography XV, SPIE*, **4691**, 459 (2002).
106. Adam, K. and Maurer, W., Polarization effects in immersion lithography, *Journal of Microlithography Microfabrication and Microsystems*, **4**(3), 031106 (2005).
107. Kunz, R. R., Switkes, M., Sinta, R. et al., Transparent fluids for 157-nm immersion lithography, *Journal of Microlithography Microfabrication and Microsystems*, **3**(1), 73 (2004).

108. French, R. H., Qiu, W., Yang, M. K. et al., Second generation fluids for 193 nm immersion lithography, *Optical Microlithography XIX, SPIE*, **6154**, 615415 (2006).
109. Furukawa, T., Hieda, K., Wang, Y. et al., High refractive index fluid for next generation ArF immersion lithography, *Journal of Photopolymer Science and Technology*, **19**(5), 641 (2006).
110. Burnett, J. H., Kaplan, S. G., Shirley, E. L. et al., High-index optical materials for 193 nm immersion lithography, *Optical Microlithography XIX, SPIE*, **6154**, 615418 (2006).
111. Parthier, L., Wehrhan, G., Seifert, F. et al., Development update of high index lens material LuAG for ArF Hyper NA immersion systems, *Fifth International Symposium on Immersion Lithography Extensions*, The Hague, the Netherlands, 22–25 September 2008.
112. Jahromi, S., Bremer, L., Tuinier, R., and Liebregts, S., Development of third generation immersion fluids based on dispersion of nanoparticles, *Fifth International Symposium on Immersion Lithography Extensions*, The Hague, the Netherlands, 22–25 September 2008.
113. Zimmerman, P., Rice, B., Rodriguez, R. et al., High index fluids to enable 1.55 and higher NA 193 nm immersion imaging, *Fifth International Symposium on Immersion Lithography Extensions*, The Hague, the Netherlands, 22–25 September 2008.
114. Zimmerman, P. A., Rice, B., Rodriguez, R. et al., The use of nanocomposite materials for high refractive index immersion lithography, *Journal of Photopolymer Science and Technology*, **21**(5), 621 (2008).
115. Byers, J., Lee, S., Jeri, K. et al., Double exposure materials: Simulation study of feasibility, *Journal of Photopolymer Science and Technology*, **20**(5), 707 (2007).
116. Hori, M., Nagai, T., Nakamura, A. et al., Sub-40-nm half-pitch double patterning with resist freezing process, *Advances in Resist Materials and Processing Technology XXV, SPIE*, **6923**, 69230H (2008).
117. Jung, W. Y., Kim, C. D., Eom, J. D. et al., Patterning with spacer for expanding the resolution limit of current lithography tool, *Design and Process Integration for Microelectronic Manufacturing IV, SPIE*, **6156**, 61561J (2006).
118. Reimer, L., *Transmission Electron Microscopy: Physics of Image Formation and Microanalysis*, 4th edn., Springer-Verlag, Berlin, Germany, (1985).
119. Bolorizadeh, M. and Joy, D. C., Effects of fast secondary electrons to low-voltage electron beam lithography, *Journal of Micro-Nanolithography MEMS and MOEMS*, **6**(2), 023004 (2007).
120. Baylor, L. R., Lowndes, D. H., Simpson, M. L. et al., Digital electrostatic electron-beam array lithography, *Journal of Vacuum Science & Technology B*, **20**(6), 2646 (2002).
121. Utsumi, T., Low-energy e-beam proximity lithography (LEEPL): Is the simplest the best? *Japanese Journal of Applied Physics Part 1-Regular Papers Short Notes & Review Papers*, **38**(12B), 7046 (1999).
122. Utsumi, T., Present status and future prospects of LEEPL, *Microelectronic Engineering*, **83**(4–9), 738 (2006).
123. Bethe, H., The theory of the passage of rapid neutron radiation through matter, *Annalen Der Physik*, **5**(3), 325 (1930).
124. Broers, A. N., Resolution limits of PMMA resist for exposure with 50 kV electrons, *Journal of the Electrochemical Society*, **128**(1), 166 (1981).
125. Tanuma, S., Powell, C. J., and Penn, D. R., Calculations of stopping powers of 100 eV to 30 keV electrons in 10 elemental solids, *Surface and Interface Analysis*, **37**(11), 978 (2005).
126. Han, G., Khan, M., Fang, Y. H., and Cerrina, F., Comprehensive model of electron energy deposition, *Journal of Vacuum Science & Technology B*, **20**(6), 2666 (2002).
127. Jackson, J. D., *Classical Electrodynamics*, 3rd edn., John Wiley & Sons Inc., New York, (1999).
128. Salisbury, I. G., Timsit, R. S., Berger, S. D., and Humphreys, C. J., Nanometer scale electron-beam lithography in inorganic materials, *Applied Physics Letters*, **45**(12), 1289 (1984).
129. Langheinrich, W. and Beneking, H., The resolution of the inorganic electron-beam resist LiF(AlF(3)), *Microelectronic Engineering*, **23**(1–4), 287 (1994).
130. Muray, A., Isaacson, M., and Adesida, I., AiF3—A new very high-resolution electron-beam resist, *Applied Physics Letters*, **45**(5), 589 (1984).
131. Yang, J. K. W. and Berggren, K. K., Using high-contrast salty development of hydrogen silsesquioxane for sub-10-nm half-pitch lithography, *Journal of Vacuum Science & Technology B*, **25**(6), 2025 (2007).
132. Parikh, M. and Kyser, D. F., Energy deposition functions in electron resist films on substrates, *Journal of Applied Physics*, **50**(2), 1104 (1979).
133. Watson, G. P., Berger, S. D., Liddle, J. A. et al., Precise measurement of the effective backscatter coefficient for 100-keV electron-beam lithography on Si, *Journal of Vacuum Science & Technology B*, **13**(6), 2535 (1995).
134. Watson, G. P., Fetter, L. A., and Liddle, J. A., Dose modification proximity effect correction scheme with inherent forward scattering corrections, *Journal of Vacuum Science & Technology B*, **15**(6), 2309 (1997).
135. Owen, G. and Rissman, P., Proximity effect correction for electron-beam lithography by equalization of background dose, *Journal of Applied Physics*, **54**(6), 3573 (1983).
136. Watson, G. P., Berger, S. D., Liddle, J. A., and Waskiewicz, W. K., A background dose proximity effect correction technique for scattering with angular limitation projection electron lithography implemented in hardware, *Journal of Vacuum Science & Technology B*, **13**(6), 2504 (1995).
137. Groves, T. R., Efficiency of electron-beam proximity effect correction, *Journal of Vacuum Science & Technology B*, **11**(6), 2746 (1993).
138. Seo, E. and Kim, O., Dose and shape modification proximity effect correction for forward-scattering range scale features in electron beam lithography, *Japanese Journal of Applied Physics Part 1-Regular Papers Short Notes & Review Papers*, **39**(12B), 6827 (2000).

139. Lee, S. Y., Jacob, J. C., Chen, C. M., Mcmillan, J. A., and Macdonald, N. C., Proximity effect correction in electron-beam lithography—A hierarchical rule-based scheme-pyramid, *Journal of Vacuum Science & Technology B*, **9**(6), 3048 (1991).
140. Patrick, W. and Vettiger, P., Optimization of the proximity parameters for the electron-beam exposure of nanometer gate-length GaAs metal-semiconductor field-effect transistors, *Journal of Vacuum Science & Technology B*, **6**(6), 2037 (1988).
141. Wuest, R., Strasser, P., Jungo, M. et al., An efficient proximity-effect correction method for electron-beam patterning of photonic-crystal devices, *Microelectronic Engineering*, **67–8**, 182 (2003).
142. Jansen, G. H., *Coulomb Interactions in Particle Beams*, Academic Press, New York, (1990).
143. Mkrtchyan, M. M., Liddle, J. A., Berger, S. D. et al., Stochastic scattering in charged particle projection systems: A nearest neighbor approach, *Journal of Applied Physics*, **78**(12), 6888 (1995).
144. Stickel, W., Simulation of Coulomb interactions in electron beam lithography systems—A comparison of theoretical models, *Journal of Vacuum Science & Technology B*, **16**(6), 3211 (1998).
145. Gallatin, G. M. and Liddle, J. A., Analytical model of the "Shot Noise" effect in photoresist, *Microelectronic Engineering*, **46**(1–4), 365 (1999).
146. Gallatin, G. M., Continuum model of shot noise and line edge roughness, *Lithography for Semiconductor Manufacturing II, SPIE*, **4404**, 123 (2001).
147. Kruit, P., Steenbrink, S., and Wieland, M., Predicted effect of shot noise on contact hole dimension in e-beam lithography, *Journal of Vacuum Science & Technology B*, **24**(6), 2931 (2006).
148. Neureuther, A. R., Pease, R. F. W., Yuan, L. et al., Shot noise models for sequential processes and the role of lateral mixing, *Journal of Vacuum Science & Technology B*, **24**(4), 1902 (2006).
149. Smith, H. I., A statistical-analysis of ultraviolet, x-ray, and charged-particle lithographies, *Journal of Vacuum Science & Technology B*, **4**(1), 148 (1986).
150. Ferrera, J., Wong, V. V., Rishton, S. et al., Spatial-phase-locked electron-beam lithography—Initial test-results, *Journal of Vacuum Science & Technology B*, **11**(6), 2342 (1993).
151. Fares, N., Stanton, S., Liddle, J., and Gallatin, G., Analytical-based solutions for SCALPEL wafer heating, *Journal of Vacuum Science & Technology B*, **18**(6), 3115 (2000).
152. Babin, S. and Kuzmin, I. Y., Experimental verification of the TEMPTATION (temperature simulation) software tool, *Journal of Vacuum Science & Technology B*, **16**(6), 3241 (1998).
153. Chao, W. L., Harteneck, B. D., Liddle, J. A., Anderson, E. H., and Attwood, D. T., Soft x-ray microscopy at a spatial resolution better than 15 nm, *Nature*, **435**(7046), 1210 (2005).
154. Sturans, M. A., Hartley, J. G., Pfeiffer, H. C. et al., EL5: One tool for advanced x-ray and chrome on glass mask making, *Journal of Vacuum Science & Technology B*, **16**(6), 3164 (1998).
155. Nakayama, Y., Okazaki, S., Saitou, N., and Wakabayashi, H., Electron-beam cell projection lithography—A new high-throughput electron-beam direct-writing technology using a specially tailored Si aperture, *Journal of Vacuum Science & Technology B*, **8**(6), 1836 (1990).
156. Pfeiffer, H. C., Projection reduction exposure with variable axis immersion lenses (PREVAIL)-A high throughput e-beam projection approach for next generation lithography, *Japanese Journal of Applied Physics Part 1-Regular Papers Short Notes & Review Papers*, **38**(12B), 7022 (1999).
157. Heritage, M. B., Electron-projection microfabrication system, *Journal of Vacuum Science & Technology*, **12**(6), 1135 (1975).
158. http://www.darpa.mil/MTO/Programs/nanowriter/index.html, 2009.
159. Kruit, P., High throughput electron lithography with the multiple aperture pixel by pixel enhancement of resolution concept, *Journal of Vacuum Science & Technology B*, **16**(6), 3177 (1998).
160. Chang, T. H. P., Thomson, M. G. R., Kratschmer, E. et al., Electron-beam microcolumns for lithography and related applications, *Journal of Vacuum Science & Technology B*, **14**(6), 3774 (1996).
161. Groves, T. R. and Kendall, R. A., Distributed, multiple variable shaped electron beam column for high throughput maskless lithography, *Journal of Vacuum Science & Technology B*, **16**(6), 3168 (1998).
162. Pease, R. F. and Chou, S. Y., Lithography and other patterning techniques for future electronics, *Proceedings of IEEE*, **96**(2), 248 (2008).
163. Sreenivasan, S. V., Nanoscale manufacturing enabled by imprint lithography, *MRS Bulletin*, **33**(9), 854 (2008).
164. Barty, A. and Goldberg, K. A., The effects of radiation induced carbon contamination on the performance of an EUV lithographic optic, *Proceedings of SPIE*, **5037**, 450 (2003).
165. Brainard, R. L., Henderson, C., Cobb, J. et al., Comparison of the lithographic properties of positive resists upon exposure to deep- and extreme-ultraviolet radiation, *Journal of Vacuum Science & Technology B*, **17**, 3384 (1999).
166. Brainard, R. L., Barclay, G. G., Anderson, E. H., and Ocola, L. E., Resists for next generation lithography, *Microelectronic Engineering*, **62**(707), 715 (2002).
167. Chou, S. Y., Krauss, P. R., and Renstrom, P. J., Imprint of sub-25 Nm vias and trenches in polymers, *Applied Physics Letters*, **67**(21), 3114 (1995).
168. Chou, S. Y., Krauss, P. R., and Renstrom, P. J., Imprint lithography with 25-nanometer resolution, *Science*, **272**(5258), 85 (1996).

169. Haisma, J., Verheijen, M., vandenHeuvel, K., and van den Berg, J., Mold-assisted nanolithography: A process for reliable pattern replication, *Journal of Vacuum Science & Technology B*, **14**(6), 4124 (1996).
170. Colburn, M., Johnson, S., Stewart, M. et al., Step and flash imprint lithography: A new approach to high-resolution patterning, *Proceedings of SPIE*, **3676**, 379 (1999).
171. Bratton, D., Yang, D., Dai, J. Y., and Ober, C. K., Recent progress in high resolution lithography, *Polymers for Advanced Technologies*, **17**(2), 94 (2006).
172. Gao, H., Tan, H., Zhang, W., Morton, K., and Chou, S. Y., Air cushion press for excellent uniformity, high yield, and fast nanoimprint across a 100 mm field, *Nano Letters*, **6**(11), 2438 (2006).
173. Huang, X. D., Bao, L. R., Cheng, X. et al., Reversal imprinting by transferring polymer from mold to substrate, *Journal of Vacuum Science & Technology B*, **20**(6), 2872 (2002).
174. Schmid, G. M., Stewart, M. D., Wetzel, J. et al., Implementation of an imprint damascene process for interconnect fabrication, *Journal of Vacuum Science & Technology B*, **24**(3), 1283 (2006).
175. Kim, K., Jeong, J., Park, S. et al., Development of a very large-area ultraviolet imprint lithography process, *Microelectronic Engineering*, **86**, 1983 (2009).
176. Ahn, S. H. and Guo, L. J., High-speed roll-to-roll nanoimprint lithography on flexible plastic substrates, *Advanced Materials*, **20**(11), 2044 (2008).
177. Tan, H., Gilbertson, A., and Chou, S. Y., Roller nanoimprint lithography, *Journal of Vacuum Science & Technology B*, **16**(6), 3926 (1998).
178. Ahn, S. H., Kim, J. S., and Guo, L. J., Bilayer metal wire-grid polarizer fabricated by roll-to-roll nanoimprint lithography on flexible plastic substrate, *Journal of Vacuum Science & Technology B*, **25**(6), 2388 (2007).
179. PolyIC. http://www.polyic.com, 2009.
180. Hua, F., Sun, Y. G., Gaur, A. et al., Polymer imprint lithography with molecular-scale resolution, *Nano Letters*, **4**(12), 2467 (2004).
181. Austin, M. D., Zhang, W., Ge, H. X. et al., 6 nm half-pitch lines and 0.04 mu m(2) static random access memory patterns by nanoimprint lithography, *Nanotechnology*, **16**(8), 1058 (2005).
182. Ding, Y. F., Ro, H. W., Germer, T. A. et al., Relaxation behavior of polymer structures fabricated by nanoimprint lithography, *ACS Nano*, **1**(2), 84 (2007).
183. Ding, Y. F., Ro, H. W., Alvine, K. J. et al., Nanoimprint lithography and the role of viscoelasticity in the generation of residual stress in model polystyrene patterns, *Advanced Functional Materials*, **18**(12), 1854 (2008).
184. Jones, R. L., Hu, T. J., Soles, C. L. et al., Real-time shape evolution of nanoimprinted polymer structures during thermal annealing, *Nano Letters*, **6**(8), 1723 (2006).
185. Hirai, Y., Yoshida, S., and Takagi, N., Defect analysis in thermal nanoimprint lithography, *Journal of Vacuum Science & Technology B*, **21**(6), 2765 (2003).
186. Jung, G. Y., Li, Z. Y., Wu, W. et al., Vapor-phase self-assembled monolayer for improved mold release in nanoimprint lithography, *Langmuir*, **21**(4), 1158 (2005).
187. Miller, M., Brooks, C., Lentz, D. et al., Step and flash imprint process integration techniques for photonic crystal patterning: Template replication through wafer patterning irrespective of tone, *Proceedings of SPIE*, **6883**, 68830D (2008).
188. *International Technology Roadmap for Semiconductors*, 2007 edition, http://www.itrs.net, Metrology. SEMATECH, Austin, TX
189. Li, M. T., Chen, L., Zhang, W., and Chou, S. Y., Pattern transfer fidelity of nanoimprint lithography on six-inch wafers, *Nanotechnology*, **14**(1), 33 (2003).
190. Lee, H. J., Ro, H. W., Soles, C. L. et al., Effect of initial resist thickness on residual layer thickness of nanoimprinted structures, *Journal of Vacuum Science & Technology B*, **23**, 3023 (2005).
191. Schulz, H., Wissen, M., and Scheer, H. C., Local mass transport and its effect on global pattern replication during hot embossing, *Microelectronic Engineering*, **67–68**, 657 (2003).
192. Kim, K. D., Jeong, J. H., Sim, Y. S., and Lee, E. S., Minimization of residual layer thickness by using the optimized dispensing method in S-FIL (TM) process, *Microelectronic Engineering*, **83**, 847 (2006).
193. Melliar-Smith, M., Lithography beyond 32 nm—A role for imprint? *Proceedings of SPIE*, **6520**, 652001 (2007).
194. Zhang, W. and Chou, S. Y., Multilevel nanoimprint lithography with submicron alignment over 4 in. Si wafers, *Applied Physics Letters*, **79**(6), 845 (2001).
195. Resnick, D. J., Dauksher, W. J., Mancini, D. et al., Imprint lithography for integrated circuit fabrication, *Journal of Vacuum Science & Technology B*, **21**(6), 2624 (2003).
196. Jung, G. Y., Johnston-Halperin, E., Wu, W. et al., Circuit fabrication at 17 nm half-pitch by nanoimprint lithography, *Nano Letters*, **6**(3), 351 (2006).
197. Hand, A., *Toshiba Validates Imprint Lithography for < 32 nm*, Semiconductor International, October, (2007).
198. Hart, M. W. IBM Almaden Research Center, DARPA Presentation. 2007.
199. Dobisz, E. A., Bandic, Z. Z., Tsai-Wei, W., and Albrecht, T., Patterned media: Nanofabrication challenges of future disk drives, *Proceedings of IEEE*, **96**(11), 1836 (2008).
200. Ahn, S. W., Lee, K. D., Kim, J. S. et al., Fabrication of a 50 nm half-pitch wire grid polarizer using nanoimprint lithography, *Nanotechnology*, **16**(9), 1874 (2005).
201. Yu, Z. N., Deshpande, P., Wu, W., Wang, J., and Chou, S. Y., Reflective polarizer based on a stacked double-layer subwavelength metal grating structure fabricated using nanoimprint lithography, *Applied Physics Letters*, **77**(7), 927 (2000).
202. Raymond, C., Scatterometry for semiconductor metrology, in A. C. Diebold (ed.), *Handbook of Silicon Semiconductor Metrology*, Dekker, New York, p. 477 (2001).
203. SEMI Standard. Test method for evaluation of line edge roughness and line width roughness, SEMI P47-0307.

204. Jones, R. L., Lin, E. K., Lin, Q. et al., Cross-section and critical dimension metrology in dense high aspect ratio patterns with CD-SAXS, *AIP Conference Proceedings*, **788**, 403 (2005).
205. Notte, J., Ward, B., Economou, N. et al., An introduction to the helium ion microscope, *AIP Conference Proceedings*, **931**, 489 (2007).
206. Wang, C. Q., Jones, R. L., Lin, E. K. et al., Characterization of correlated line edge roughness of nanoscale line gratings using small angle x-ray scattering, *Journal of Applied Physics*, **102**(2), 024901 (2007).
207. Wang, C. Q., Jones, R. L., Lin, E. K., Wu, W. L., and Leu, J., Small angle x-ray scattering measurements of lithographic patterns with sidewall roughness from vertical standing waves, *Applied Physics Letters*, **90**(19), 193122-3 (2007).
208. Hu, T. J., Jones, R. L., Wu, W. L. et al., Small angle x-ray scattering metrology for sidewall angle and cross section of nanometer scale line gratings, *Journal of Applied Physics*, **96**(4), 1983 (2004).
209. Jones, R. L., Hu, T., Lin, E. K. et al., Small angle x-ray scattering for sub-100 nm pattern characterization, *Applied Physics Letters*, **83**(19), 4059 (2003).

20

Extreme Ultraviolet Lithography

20.1 Introduction **20**-1
20.2 Historical Background **20**-2
EUV Imaging System Development • EUVL-Enabling Technologies
20.3 Current State of the Art **20**-5
EUVL Exposure Tools • EUV Device Integration
20.4 EUVL Infrastructure Status **20**-9
EUV Sources • EUV Masks • EUV Resists • EUV Mask Handling • EUV Optics and Mask Contamination
20.5 Future Perspectives **20**-14
Abbreviations **20**-16
References **20**-16

Obert R. Wood II
GLOBALFOUNDRIES

20.1 Introduction

Extreme ultraviolet (EUV) lithography extends conventional optical lithography to higher resolution because it utilizes an exceedingly short imaging wavelength (λ = 13.5 nm) and provides a larger depth of focus because it employs a small numerical aperture (NA = 0.25) imaging system. Although it has a number of similarities with visible, deep ultraviolet (DUV), and 193 nm lithography, EUV lithography (EUVL) presents several unique technical challenges. For example, because EUV radiation is not transmitted through ambient air, an EUVL tool must be operated in a vacuum environment. Since all solid materials strongly absorb EUV radiation, conventional refractive optics is not an option and reflective reticles and optics must be employed. Since no naturally occurring material provides more than about 1% reflectivity at normal incidence in the EUV spectral region, EUV mirrors must be coated with special multilayer (ML) reflective coatings. Since EUV sources are inefficient, a high-temperature plasma source requiring extremely high input power and careful management of waste heat must be used. Furthermore, because hydrocarbons and water vapor are cracked by EUV radiation, depositing carbon on mirror surfaces and oxidizing their reflective coatings, hydrocarbon and water vapor levels in an EUV exposure tool must be carefully controlled. While the development of EUVL has been and continues to be challenging, the successful insertion of EUVL into semiconductor manufacturing will bring many benefits, among which are a much wider process window and an ability to print linewidths at 22 nm and smaller.

The key components of a system for EUVL include (1) an illumination system consisting of a plasma EUV radiation source, a condenser to collect the light, and an illuminator; (2) a patterned reflective mask; (3) a 4×-reduction reflective imaging system comprised of six or more highly precise ML-coated aspheric mirrors; and (4) an EUV-sensitive resist. A diagram illustrating the key components in an EUVL exposure tool is shown in Figure 20.1.

Although a variety of sources can generate EUV radiation, the source illustrated in Figure 20.1 is a high-temperature plasma of the kind that can be produced by focusing a high-power pulsed laser on a target of lithium, tin, or xenon. EUV radiation reflected from a patterned reticle located on the mask stage is imaged by 4×-reduction projection optics onto a resist-coated silicon wafer located on the wafer stage. EUVL exposure tools use the same step and scan architecture employed in today's DUV and 193 nm exposure tools and will ultimately operate at similar throughputs, approximately 80–100 wafers/h.

The development of EUV imaging systems from the early 1980s to the present is summarized in Section 20.2, which also describes the key technology developments that made EUVL possible: ML reflective coatings, highly precise aspheric mirrors, and phase-shifting point-diffraction interferometers. The current state of the art in EUVL is summarized in Section 20.3. The current status of EUVL infrastructure development in sources, masks, resists, mask handling, and optics and mask contamination is described in Section 20.4. The elements of EUV technology at highest risk of not being ready when needed and the timing of EUV insertion into manufacturing are discussed in Section 20.5, and an extensive list of references is given at the end.


Mask stage
Projection optics
Illuminator
EUV source & collector
Collector
Plasma source
Water stage

FIGURE 20.1 Sketch showing the major subsystems in an exposure tool for extreme ultraviolet lithography.

20.2 Historical Background

20.2.1 EUV Imaging System Development

The most important developments in EUV imaging systems that took place in Europe, Japan, and the United States from 1985 to the present are illustrated in Figure 20.2.

The surface of each optical element in an EUV imaging system must be provided with a ML coating that reflects EUV radiation at near-normal angles of incidence. The use of normal-incidence reflective optics for x-ray microscopes and x-ray telescopes was proposed first in the early 1980s,[1–3] but efficient ML reflective coatings were not sufficiently advanced at that time to be of much use and the results of the early soft x-ray imaging experiments were not very encouraging. The earliest EUV imaging experiments were carried out using projection optics consisting of two spherical mirrors, a convex primary, and a concave secondary, arranged in a Schwarzschild form. In fact, projection optics of this type were used by Hiroo Kinoshita of NTT in 1985 in the very first EUVL imaging experiments. Initially, the imaging system mirrors consisted of tungsten–carbon MLs deposited on SiC substrates.[4] Later, an imaging system with reflective coatings designed to work near the absorption edge of Si was assembled at the High Energy Physics Laboratory in Tsukuba, Japan, but the alignment accuracy of the optics was poor and all of the replicated patterns were severely distorted. In 1984, an image of a 4 μm line and space pattern was finally produced and in 1986, at the Autumn Meeting of the Japan Society of Applied Physics, the results of the early imaging experiments were first made public.[5] Other early experiments that employed two-spherical-mirror projection optics were the demonstration by Bjorkholm et al. of AT&T in 1990 of diffraction-limited imaging near 14 nm wavelength using 20× reduction 0.08 NA Mo/Si ML-coated Schwarzschild optics to print features as small as 0.05 μm in poly (methyl metacrylate) resist,[6] and the development by Tichenor et al. of Sandia National Laboratory (SNL) in 1995 of the first EUVL laboratory tool capable of precise overlay combining 10× reduction, 0.088 NA Schwarzschild optics with accurate mask and wafer stages, and an integrated through-the-lens alignment system.[7]

The second stage in the evolution of EUVL imaging systems involved the development of two-aspherical-mirror projection optics. In 1993, Kinoshita et al. of NTT fabricated a 5× reduction, 0.07 NA two-aspherical-mirror imaging system with a 20 × 0.4 mm exposure area[8] based on a design first described by Kurihara et al.[9] and demonstrated the imaging of features as small as 0.25 μm across a 10 × 0.6 mm area and imaging of 0.15 μm features over a portion of a 2 × 0.6 mm ring-shaped field. In 1996, Haga et al. succeeded in expanding the exposure area of the two-aspherical-mirror imaging system to 20 × 25 mm by


EUV imaging system highlights
1985
1990
1995
2000
2005
2010
First EUVL imaging (NTT)5
First diffraction-limited imaging (AT&T)6
2-Aspherical-mirror imaging (NTT)8
2-Mirror 10× micro strepper (SNL, AT&T)7
3-Aspherical-mirror large-field replication (HIT)14
3-Aspherical+1-spherical-mirror ETS scanner (VNL)15
2-Aspherical-mirror 0.3NA MET (SEMATECH/Zeiss)11
6-Aspherical-mirror alpha demo tool (ASML/Zeiss)18
6-Aspherical-mirror EUVL pre-production tool (ASML/Zeiss)15

FIGURE 20.2 Major developments in EUVL imaging systems from 1985 to present.

utilizing new critical-illumination optics to illuminate a 20 × 0.6 mm ring-shaped area of the mask and by scanning the mask and wafer stages in synchronism.[10] In 2004, Naulleau et al. of Lawrence Berkeley National Laboratory (LBNL) demonstrated the printing capabilities of a 0.3 NA EUV micro-exposure tool (MET) at the Advanced Light Source in Berkeley.[11] The MET's 0.3 NA 5×-reduction two-aspherical-mirror imaging system (with maximum aspheric departure of 3.82 μm on the primary and 5.61 μm on the secondary), manufactured by Carl Zeiss in Germany, had an annular pupil with a central obscuration radius equal to 30% of the full pupil, a 1 × 3 mm field of view at the reticle plane (200 × 600 μm at the wafer plane), and provided ~22.5 nm resolution with conventional illumination (Rayleigh $k_1 = 0.5$) and smaller than 16 nm resolution with dipole illumination (Rayleigh $k_1 = 0.35$).[12]

The third stage in the evolution of EUV imaging systems involved the development of projection optics, which could support the larger exposure fields needed for device demonstrations. In 1996, Murakami et al. of Nikon Corporation described the design of a three-aspherical-mirror ring-field imaging system.[13] In 1998, Kinoshita et al. of Himeji Institute of Technology (Hyogo University today) described a three-aspherical mirror system for EUVL that included illumination optics, a scanning and alignment mechanism, a 0.1 NA 5× reduction imaging system that utilized three aspherical mirrors and one plane mirror, which supported 0.1 μm resolution printing by scanning a 1 mm wide by 30 mm long ring-shaped image field across a wafer, and a load-lock chamber for bringing wafers into and out of vacuum.[14] In 2001, Tichenor et al. of the Virtual National Laboratory, with personnel from LBNL, Lawrence Livermore National Laboratory (LLNL), and SNL, described system integration and performance of the EUV Engineering Test Stand (ETS) developed for the EUVLLC,[15] an Intel-led consortium of semiconductor manufacturers formed in 1997 to accelerate the commercialization of EUVL. The ETS's 0.1 NA 4× reduction projection optics, consisting of three aspherical mirrors (with max aspheric departures less than 10 μm) and one spherical mirror, provided a ±0.5 μm depth of focus (DOF), a scanned field size of 24 × 32.8 mm, and 100 nm resolution imaging. The extensive experimental work on the ETS and the involvement of personnel from six semiconductor companies in the EUVLLC project resulted in a high level of confidence that EUVL was ready for commercial development.

The most recent stage in the evolution of EUV imaging systems includes the development of six-aspherical-mirror ring-field projection optics by each of the three major suppliers of commercial lithographic exposure tools. The 0.25 NA 4× reduction imaging system in ASML's full-field scanning EUV Alpha Demo Tool (ADT), two of which were delivered to customers in 2007, is designed to print 40 nm dense lines and spaces over a 26 × 33 mm field and has recently been used to print 28 nm dense lines and spaces in a state-of-the-art resist.[16] The 0.25 NA 4× reduction six-aspherical-mirror imaging system in Nikon's EUV1 process development tool is designed to print 45 nm dense lines over a 26 × 23 mm field, and a set of EUV1 projection optics has recently demonstrated an extraordinarily low 0.4 nm root mean square (rms) wavefront error over a 26 × 2 mm static exposure field.[17] ASML's Model NXE: 3100 EUV preproduction tool, which is expected to be delivered to customers in 2010, will include a 0.25 NA six-aspherical-mirror imaging system with even lower wavefront error and with reduced imaging system flare.[16]

20.2.2 EUVL-Enabling Technologies

Four scientific and technical breakthroughs critical to the development of EUVL occurred between 1981 and 1996. These four major advances were the first demonstrations of normal-incidence imaging in the soft x-ray spectral region, the development of efficient ML reflective coatings, the fabrication and characterization of precision aspheres, and the improvement of phase-measuring interferometry (PMI).

20.2.2.1 Multilayer Reflective Coatings

Below 30 nm wavelength, no naturally occurring material provides more than about 1% normal incidence reflectance because the index of refraction of all materials in this region is nearly unity (actually slightly less than one). In 1972, Eberhard Spiller of IBM showed that ML films composed of two materials that have nearly identical index of refraction, but that have widely different values of EUV absorption, can lead to constructive interference and, hence, enhanced reflection in a narrow wavelength band peaked at the Bragg wavelength, $\lambda = 2\Lambda \sin(\theta)$, where Λ is the ML period and θ is the angle of incidence.[18] In 1985, Barbee et al.[19] demonstrated that the particular material combination of molybdenum and silicon results in an exceptionally high normal-incidence reflectivity at wavelengths just longer than the Si L absorption edge at 12.4 nm. Today, ML coatings can provide a usable normal incidence reflectance in narrow bands of EUV wavelength from 4.5 to 30 nm.[20] The normal incidence reflectance of the best modern Mo/Si ML, an example of which is shown in Figure 20.3, now approaches 70% in a narrow band of wavelengths near 13.5 nm.[21]



FIGURE 20.3 Reflectance of a Mo/Si ML measured with a commercial EUV reflectometer. (Reprinted from Wood, O., *AIP Conf. Proc.*, 931, 375, 2007. With permission.)

To maximize tool throughput, each of the mirrors in EUVL projection optics must have the highest possible reflectivity at 13.5 nm. To maximize imaging performance, the central wavelength of the reflectivity must be controlled to better than 0.01 nm. To support diffraction-limited printing, the mirror surfaces must have surface figure errors of the order of about 0.1 nm rms, and the ML coatings must not contribute more than approximately one-quarter of the total error, a requirement that leads to strict requirements on the thickness uniformity. The processing conditions for the deposition of Mo/Si ML coatings have now been optimized to obtain high reflectivity, low internal stress, and graded thickness simultaneously, and ML coatings are now available commercially at a number of institutions around the globe. Nikon Corporation recently succeeded in fabricating an aspheric mirror for an EUV imaging system with as little as 60 pm rms surface figure change before and after ML coating (small enough so that its effect on wavefront error can be ignored).[17]

20.2.2.2 Fabrication and Characterization of Aspheric Mirrors

The progress that has taken place in the fabrication and characterization of aspheric mirrors since the early 1990s is impressive. In the beginning, only low-departure aspheres could be fabricated and these were found to be only marginally usable in two-mirror EUV imaging systems. Polishing processes for aspheric mirrors have since been developed that can simultaneously reduce low spatial frequency roughness (LSFR), mid-spatial frequency roughness (MSFR), and high spatial frequency roughness (HSFR). Today, aspheres that meet the stringent requirements of a high-NA six-mirror EUV lithographic imaging system, less than 0.1 nm rms for LSRF, MSFR, and HSFR, are available commercially. Figure 20.4 shows some recent data from Nikon Corporation from a polished aspheric mirror for its EUV1 projection optics on which Nikon achieved an LSFR of 38 pm rms, an MSFR of 80 nm rms, and a HSFR of 68 nm rms.[17]

Surface figure data at low spatial frequencies, obtained from visible light interferometry, are needed to ensure diffraction-limited imaging. Surface finish data at high- and mid-spatial frequencies, obtained with an atomic force microscope and a white-light interferometric microscope, are needed to predict the distribution of scattered radiation in the imaging system. Surface roughness at high-spatial frequencies results in a loss of EUV reflectivity and, hence, system throughput. Surface roughness at mid-spatial frequencies can scatter light into the image plane and result in a loss of image contrast. For this reason, MSFR and the imaging system flare it causes is a serious concern for EUVL even today. A complete set of power spectral density (PSD) surface height data from an asphere for Nikon's EUV1 projection optics is also shown in Figure 20.4.[17] The smooth PSD curve shows that a high degree of precision has been successfully achieved in each of the important spatial wavelength regions.



FIGURE 20.4 Plot of surface height data from a polished aspheric mirror for the projection optics of Nikon's EUV1 projection optics expressed as power spectral density (nm^4) versus spatial frequency (nm^{-1}). (Reprinted from Murakami, K. et al., *Proc. SPIE*, 6921, 69210Q, 2008. With permission.)

20.2.2.3 The Phase-Shifting Point- Diffraction Interferometer

To achieve the highest possible resolution (diffraction-limited printing), the wavefront error of an imaging system must be less than λ/14, where λ is the operating wavelength (less than 1 nm when $\lambda = 13.5$ nm). For a six-mirror imaging system, this means that the error contributions from each individual mirror can be no larger than about 0.1 nm rms (assuming that the errors are uncorrelated and taking into account the doubling of the error that occurs on reflection). Visible-light phase-measuring interferometry (PMI) is the metrology most commonly used to provide the feedback needed for figuring a mirror surface. Since PMI is a comparative technique, its accuracy is limited by the quality of the reference. Recognizing this, Gary Sommargren (LLNL) in 1996 developed a new type of PMI, called phase-shifting diffraction interferometry (PSDI) that utilized a reference based on diffraction.[22] An experimental arrangement for PSDI configured to measure the surface figure of a concave off-axis aspheric mirror is illustrated in Figure 20.5.

Light leaving the end of a single-mode optical fiber diffracts, forming a spherical wavefront. Part of this wavefront is incident on the mirror being tested and is reflected back toward the fiber. This aberrated wavefront reflects from a semitransparent metal film on the face of the fiber and interferes with part of the original spherical wavefront to produce an interference pattern on a charge-coupled-device camera. Subsequent work has shown that PSDI can result in measurement accuracies approaching 0.10 nm rms.[23]

The total wavefront error of an EUV imaging system depends not only on the surface figure and alignment of each mirror but also on the spatially varying properties of their ML coatings. EUV interferometry, with phase-shifting point-diffraction interferometry (PS/PDI) and various forms of lateral-shearing interferometry, has been used to test and align a number of EUV imaging systems.[24] In fact, the 0.3 NA SEMATECH Berkeley MET was interferometrically aligned at EUV wavelengths using the PS/PDI technique and its wavefront error was shown to be about 0.8 nm rms in a 37-term annular Zernike polynomial dominated by higher order spherical aberration.[25] Because the wavefront error measured with visible light is not exactly the same as that measured with EUV radiation due to the phase change in reflection that occurs at a ML, to ensure that the six-mirror projection optics in future EUV exposure tools have wavefront errors below 1 nm, EUV interferometry has been or is being developed by each of the major suppliers of commercial lithography tools.

20.3 Current State of the Art

EUVL development has accelerated significantly in the last few years. Alpha-class EUV exposure tools are now in operation in Europe, Japan, and the United States. Significant improvements in both line/space and contact-hole performance of EUV-resist materials have been made due in large part to the availability of EUV MET tools that provide high-quality and high-contrast aerial images. The first EUV device integration exercises have been carried out using full-field EUVL exposure tools in Albany, New York and in Leuven, Belgium. This section presents the current state of the art in EUV exposure tools and a brief summary of the results of the device integrations exercise.

20.3.1 EUVL Exposure Tools

Two full-field EUVL research and development exposure tools were delivered by ASML in 2006, one to the College of Nanoscale Science and Engineering in Albany, New York and the other to the IMEC microelectronics research laboratory in Leuven, Belgium.[26] Another full-field EUVL R&D tool was delivered by Nikon Corporation to the Semiconductor Leading



FIGURE 20.5 Experimental arrangement for a phase-shifting diffraction interferometer configured to measure the surface figure of a concave off-axis aspheric mirror. (Reprinted from Sommargren, G., *OSA Trends Opt. Photon.*, 4, 108, 1996. With permission.)



FIGURE 20.6 **(See color insert following page 20-14.)** (a) Artist illustration of ASML's EUV ADT showing a DPP EUV source on the left, illumination optics in the middle, and mask, projection optics, and wafer on the right. (Courtesy of ASML, Veldhoven, the Netherlands.) (b) Image of 28 nm lines and spaces printed in a 50 nm thick layer of a chemically amplified resist using an ASML ADT. (Reprinted from Meiling, H. et al., *Proc. SPIE*, 7271, 727102, 2009. With permission.) (c) Image of 27 nm isolated line in 80 nm thick EUV-65 resist printed with an ASML ADT. (Reprinted from Pierson, B. et al., EUV resist performance on the ASML ADT and LBNL MET, *International EUVL Symposium*, Lake Tahoe, CA, 2008. With permission.) (d) Image of 28 nm diameter contact holes in 80 nm thick film of a chemically amplified resist printed at 45 mJ/cm^2 dose using an ASML ADT. (Reprinted from Koh, C. et al., *Proc. SPIE*, 7271, 727124, 2009. With permission.)

Edge Technologies (Selete) consortium in Tsukuba, Japan in 2007.[27] An artist's rendering of an ASML EUV ADT is shown in Figure 20.6a.

The EUV source for the ADT is a gas discharge–produced plasma fueled by Sn vapor. The ADT utilizes a reflective illuminator to supply partially coherent illumination ($\sigma = 0.5$) to a 6″ × 6″ × 0.25″ patterned reflective mask. A 4× reduction 0.25 NA reflective imaging system, comprised of six highly precise ML-coated aspheric mirrors, produces an image of the mask on resist-coated 300 mm diameter wafers. The ADT utilizes the same step and scan architecture employed in today's DUV and 193 nm exposure tools, although its throughput is limited to a few wafers per hour by the available source power. The specifications for the ADT include 40 nm resolution for dense lines and spaces, 30 nm for isolated lines, and 55 nm for contact holes, a field size of 26 × 33 mm, an overlay error of 12 nm mean $+3\sigma$, and an imaging system flare of 16%.[28] Nikon's EUV1 exposure tool includes a 4× reduction 0.25 NA six-mirror imaging system with about 10% flare and an illumination system that provides $\sigma = 0.8$ conventional illumination, and was designed for use in process development at the 45 nm half-pitch node. The specifications for the EUV1 include 45 nm resolution for dense lines and spaces and a field size of 26 × 33 mm.[29] Using 0.25 NA EUV ADTs, ASML recently demonstrated 28 nm resolution for dense lines and spaces in a 50 nm thick layer of a state-of-the-art chemically amplified resist (CAR) (illustrated in Figure 20.6b).[15] ASML in joint work with AMD, IBM, and Toshiba demonstrated 27 nm resolution for isolated lines at a DOF of 200 nm (illustrated in Figure 20.6c),[30] and SEMATECH demonstrated 28 nm resolution for dense contact holes in 80 nm thick films of resist at a DOF of 150 nm (illustrated in Figure 20.6d).[31]

Micro-field exposure tools have played and continue to play a key role in the development of EUV resists. This is because the relative simplicity of these tools enables them to provide a higher aerial image contrast than the early alpha-class EUVL exposure tools, since they utilize higher NA projection optics (0.3 NA instead of 0.25 NA) and support more sophisticated illumination modes, and their owners have been more willing to risk contaminating the projection optics by agreeing to print with resist materials that have high outgassing rates. Two MET tools, the Canon 0.3 NA small-field exposure tool at Selete in Tsukuba, Japan[32] and the SEMATECH Berkeley MET at the Advanced Light Source in California[11] use synchrotron radiation as their EUV source. The other two, an Exitech MS-13 at Intel Corporation in Oregon and another at the SEMATECH Resist Test Center in Albany, New York use a Xe discharge–produced plasma source. A CAD model of the SEMATECH Berkeley MET illustrating the major components of the exposure system as well as the EUV beam path[33] is shown in Figure 20.7a.


22 nm HP
548002.0 kV 3.4 mm ×200k 200 nm
54800 5.0 kV 2.8mm ×400k SE(M) 9/18/2008 15:36 100 nm
(b)
30 nm HP
54800 2.0 kV 3.4mm ×250k 200 nm
54800 5.0 kV 2.3mm ×400k SE(M) 9/16/2008 10:35 100 nm
(c)
From synchrotron
Scanner module
Reticle stage
0.3-NA MET (Zeiss)
Wafer stage and height sensor
Pupil-fill monitor
(a)

FIGURE 20.7 (a) CAD model of major exposure station components and beam path of the SEMATECH Berkeley MET. (b) Patterning of 1:1 dense lines and spaces in a 50 nm thick film of a chemically amplified resist at a sizing dose of 15.2 mJ/cm^2 using the SEMATECH Berkeley MET using rotated dipole illumination. (c) Patterning of 1:1 dense contact holes in a chemically amplified resist using the SEMATECH Berkeley MET using annular illumination. (Reprinted from Naulleau, P. et al., *Proc. SPIE*, 7271, 72710W, 2009. With permission.)

As mentioned in Section 20.2.1, the 0.3 NA MET optics support a resolution of 22.5 nm at a Rayleigh k_1 factor of 0.5 and a resolution of 16 nm at a Rayleigh k_1 factor of 0.35. Although the SEMATECH Berkeley MET utilizes the same projection optics design as the commercial METs, its unique lossless programmable-coherence illuminator allows it to print at considerably lower Rayleigh k_1 factor (that is, it supports better resolution) than the other MET tools. Another significant benefit of the SEMATECH Berkeley MET is that it is the only MET to have been interferometry-aligned at EUV wavelengths after integration into the tool at the operational location. Impressive resist performance improvements have been demonstrated for both line/space and contact-hole printing during the last year using the SEMATECH Berkeley MET. Figure 20.7b shows the printing of 22 nm half-pitch lines/spaces in a 50 nm thick resist film at about 20 mJ/cm^2 dose using 45° rotated dipole illumination[33]; Figure 20.7c shows the printing of 30 nm diameter contact holes at 48.6 mJ/cm^2 dose using 0.35/0.55 annular illumination.[33]

EUV interference lithography (IL) tools, like the ones at Paul Scherrer Institute (PSI) in Switzerland and at the University of Wisconsin in Madison, are exploring the ultimate resolution limits of resist materials and screening new candidate resist materials for lithographic performance before subjecting the expensive projection optics in the full-field EUV exposure tools to the risk of contamination from resist outgas products. The EUV-IL tool at PSI uses a spatially coherent EUV beam from the XIL beamline at the Swiss Light Source, with a central wavelength of 13.4 nm and a spectral width of about 2%–3%, to illuminate a transmission-diffraction-grating-based interferometer like the one illustrated in Figure 20.8a. The period of the interference fringes formed by this interferometer is equal to half the period of the diffraction gratings, which are patterned on thin silicon nitride membranes using electron beam lithography. Although the image contrast of EUV-IL can be influenced by a number of factors (transverse coherence length of the source, a difference in intensity between the two interfering EUV beams, mechanical instabilities, etc.), EUV-IL offers the advantage of nearly perfect aerial image contrast, performance that is difficult to achieve using projection or proximity lithography methods. EUV-IL at PSI has demonstrated resolution below 12.5 nm half-pitch in several electron beam resist materials. For example, a cross-sectional scanning electron microscope (SEM) image of 16.25 nm half-pitch lines and spaces in a 25 nm thick film of calixarene resist (*p*-chloromethyl-methoxy-calix[4]arene) is shown in Figure 20.8b[34] and a cross-sectional SEM image of 20 nm half-pitch lines and spaces in a 35 nm thick film of HSQ resist (hydrogen silsesquioxane) is shown in Figure 20.8c.[35]



FIGURE 20.8 (a) Sketch of system for EUV interference lithography produced by EUV radiation from two transmission gratings illuminated with EUV radiation from an undulator beamline at a synchrotron light source. (b) Cross-sectional SEM image of HSQ resist patterns with half-pitch of 20 nm produced by the EUV interference lithography at the PSI. (Reprinted from Ekinci, Y. et al., *Microelectron. Eng.*, 84, 700, 2007. With permission from Elsevier.) (c) Cross-sectional SEM image of calixarene patterns with half-pitch of 16.25 nm produced by the EUV interference lithography at PSI. (Reprinted from Solak, H. et al., *J. Vac. Sci. Technol. B*, 25, 91, 2007. With permission.)

20.3.2 EUV Device Integration

Now that the first generation of alpha-class EUVL exposure tools has been deployed and major exposure tool suppliers have established detailed roadmaps for the ramp-up of EUVL technology, one of the main challenges facing the semiconductor industry is to begin integrating EUVL into the semiconductor fabrication process so the technology will be ready to support high-volume manufacturing (HVM) when needed. EUV device integration exercises not only provide a realistic test of technology readiness but also highlight any remaining technical issues. Two EUV device integration exercises were carried out in 2008 and a number of others are currently underway. In 2008, the ASML EUV ADT in Albany was integrated into a standard semiconductor manufacturing flow by the AMD/IBM/Toshiba Alliance and used to pattern the first metal interconnect level of AMD test chips fabricated using 45 nm logic design rules,[36] and the ADT at IMEC in Belgium was used to pattern the contact hole level of a 32 nm



FIGURE 20.9 (a) EUV resist image of an area of the mask containing SRAM patterns. The unit cell is defined by the dashed rectangle. Rohm and Haas resist XP4502J with a film thickness of 150 nm was used. (Reprinted from La Fontaine, B. et al., *Proc. SPIE*, 6921, 69210P, 2008. With permission from SPIE.) (b) Comparison of yield from a baseline 45 nm process and a process using EUVL to print the M1 level. Each point in the baseline statistics represents a full wafer, whereas each point in the EUV statistics represents a 256 kbit SRAM area. (Reprinted from La Fontaine, B. et al., The future of EUV lithography, in Yamamoto, N. (ed), *Proceedings of SEMI Technology Symposium 2008*, SEMI Japan, Chiba, Japan, 2008. With permission.)

six-transistor SRAM cell based on FinFET technology.[37] More recently, EUV Alpha Demo Tools were used by the IBM/AMD/Toshiba Alliance in Albany to pattern two levels of a 22 nm test chip[38] by Samsung to pattern a contract hole level at the 4× DRAM node,[39] and by Hynix to compare the patterning fidelity of 193 nm immersion and EUVL at the 4×, 3×, and 2× DRAM nodes.[40]

Some results from the AMD/IBM/Toshiba Alliance EUV device integration exercise at the 45 nm logic node are shown in Figure 20.9. Figure 20.9a shows an EUVL image of memory structure (SRAM) patterns in a 150 nm thick film of Rohm and Haas XP4502J resist.[41] The SRAM unit cell is defined by the dashed rectangle. Once EUVL of the M1 layer was completed, the patterns were transferred to the underlying dielectric layer using reactive ion etching. The resulting trenches were filled with Cu using a damascene process and then polished. Electrical tests at the M1 level showed that individual transistors connected in this way had electrical characteristics very similar to those patterned using standard 193 nm immersion lithography. After further processing of the 45 nm node test chips to the fifth interconnect level, 256 kbit SRAMs were analyzed electrically for yield. The results in Figure 20.9b demonstrate the potential for EUVL to produce yield in extended devices when used to pattern one level. The yield data shown for the baseline process was calculated on full wafers, whereas the yield data for the EUV case was based on individual 256 kbit SRAM areas on five wafers.[41] Some of the best yielding 26 Mbit SRAM blocks had nearly 100% yield but did contain two failing cells. The location of the failing cells coincided with the location of a hard defect on the mask discovered during subsequent wafer and reticle inspection.

20.4 EUVL Infrastructure Status

Even after more than two decades of development, a number of technical challenges still need to be met before EUVL can be used in HVM. The steering committee of the International EUVL Symposium, with representatives from leading semiconductor manufacturers, EUVL Consortia in Europe, Japan, and the United States, and commercial EUVL exposure tool suppliers, has identified and ranked the list of critical technical issues on a yearly basis since 2002. The current list of critical issues, which was last updated and re-ranked in October 2008, is shown in Table 20.1. Even though this year's list is shorter than ever, the top three issues (focus areas, sources, masks, and resists) have remained at or near the top of each year's critical issue list and must be completely resolved before EUVL can be used in HVM.

TABLE 20.1 2008 EUV Focus Areas

Rank	Key Focus Areas
1	Long-term source operation with 100 W at IF and delivery of 5 MJ/day
2	Defect-free masks through lifecycle and inspection/review infrastructure
3	Resist resolution, sensitivity, and LEF met simultaneously
Areas of Significant Concern	
•	Reticle protection during storage, handling, and use
•	Projection/illuminator optics and mask lifetime

20.4.1 EUV Sources

The wavelength and spectral bandwidth of the source for an EUVL exposure tool, a 2% wavelength band around 13.5 nm, are set by the ML reflective coatings on the imaging system mirrors. The source power is set by the required exposure tool throughput, which to first order is determined by the transmission of the optical train (collector efficiency and illuminator, reticle, and projection optic reflectivities) and the resist sensitivity. Lithography exposure tool manufacturers have agreed on the following top-level specifications for an HVM EUV source: 115 W of collected source power at a plane behind the first source collector optic called the intermediate focus (IF), an etendue limit of 3 mm^2 sr, and a repetition rate of 10 kHz or higher.[42] The cost of ownership (COO) for an EUV source is likely to be determined by the lifetime of the source collector, which in turn will be limited by the effectiveness of the source debris mitigation system. The current EUV source requirements are very severe and significant progress needs to be made to achieve the performance required for HVM while still maintaining an acceptable COO. For the later stages of HVM, EUV sources with up to 400 W of IF power are likely to be needed. All sources under consideration for EUVL are based on hot plasmas created by an electrical discharge or by laser irradiation. The current status of the two leading EUV source technologies, discharge-produced plasma (DPP) and laser-produced plasma (LPP) are described in the next two sections.

20.4.1.1 Discharge-Produced Plasma EUV Sources

The major components of a DPP EUV source-collector module, the DPP source, the debris mitigation system, and the collector optic, are illustrated in Figure 20.10a.

A number of discharge configurations have been evaluated for use in a DPP EUV source. What these discharge configurations have in common is the azimuthal magnetic field generated by the large axial discharge current between the discharge electrodes, which compresses the source fuel (typically Xe gas or Sn vapor) to the hot plasma (about 30 eV electron temperature) required for efficient generation of EUV radiation at 13.5 nm. The debris mitigation system for a DPP EUV source must protect the collector against (1) sputtering by high-energy ions and atoms, (2) contamination by tin fuel, and (3) contamination by electrode material. A reduction in the collector sputter rate by a factor of approximately 50,000 has been demonstrated through improvements in debris mitigation, and the lifetime of the collector in a Sn DPP source today is limited only by contamination. When the limits of active protection of the collector against contamination are reached, *in situ* cleaning will be needed to further prolong the collector lifetime. The collector used with DPP sources usually consists of a number of nested shells (in a so-called Wolter design) that are fabricated using a nickel electroforming process and coated with a thick layer of ruthenium



FIGURE 20.10 (a) Schematic diagram of an EUV source-collector module containing an EUV Sn DPP source. (b) Schematic diagram of an EUV source-collector module for a Sn droplet source powered by a carbon dioxide laser.

to provide high grazing-incidence reflectance of EUV radiation. At SPIE Advanced Lithography 2009, Philips Extreme UV in a joint Philips/Xtreme solution reported achieving 8 W of in-band power at IF using 170 W/2πsr Sn DPP EUV source, a foil-trap-based debris mitigation system, and a six-shell Ru-coated grazing-incidence collector.[43]

The advantages of a DPP EUV source are its lower cost of manufacturing, its lower level of complexity, and its use of a lower cost grazing-incidence collector optic. DPP EUV source technology is more mature than LPP EUV source technology and DPP EUV sources are commercially available today. The disadvantages of DPP EUV sources are the large thermal load and short lifetime of the debris mitigation system and collector optic and the difficulty of scaling to higher powers without sacrificing component lifetime and reliability.

20.4.1.2 Laser-Produced Plasma EUV Sources

The major components of an LPP EUV source-collector module, an LPP source consisting of high-power pulsed laser, a droplet target generator, and a ML-coated normal-incidence collector, are shown in Figure 20.10b. In the early 1990s, a number of experimental and theoretical studies showed that LPP EUV sources could achieve conversion efficiencies from laser energy to EUV energy in a 2% bandwidth near a 13 nm wavelength of about 1%–2% depending on target material, laser intensity, laser pulse width, and laser wavelength. It was apparent from the very earliest experiments that debris ejected from the plasma posed a major threat to the lifetime of the collector due to (1) deposition of debris (particulates) from the source hardware, (2) deposition of atomic vapor from the source plasma, and (3) erosion by high-energy ions. Since that time, a great deal of effort has been put into designing and testing a variety of debris-mitigation schemes (gas curtains, electrostatic repeller fields, etc.) for LPP EUV sources. The only alternative to debris mitigation is to minimize debris production using mass-limited targets that supply only the amount of target material needed for efficient production of EUV radiation. One of the most promising methods of producing a mass-limited target is to introduce a stream of tiny droplets of target material into the laser focus, as shown in Figure 20.10b. At SPIE Advanced Lithography 2009, Cymer Inc. reported achieving about 45 W of EUV power at 50 kHz repetition rate in 400 ms-long bursts from a LPP EUV source operating at 50 kHz repetition rate using an approximately 12 kW CO_2 laser to ionize a succession of tiny Sn droplet targets.[44] Cymer has recently been able to accumulate nearly 1 MJ of EUV dose by operating a LPP Sn droplet source over a 3 day period for about 8 h per day.[44]

The advantages of an LPP EUV source are a lower rate of debris production due to the use of a mass-limited target and a larger standoff distance between the hot plasma and the collector optic, a higher radiation-collection efficiency and better thermal management due to the use of a normal-incidence collector, and the possibility of power scaling through spatial, temporal, and spectral multiplexing. The disadvantages of an LPP EUV source are its potentially higher capital cost and greater complexity (a high-power pulsed laser system, a droplet generator, and an ML-coated collector are required) and the relative immaturity of LPP technology (even after many years of development, the measured power at IF from LPP EUV sources has only recently surpassed that from DPP EUV sources).

20.4.2 EUV Masks

The second most critical issue for EUVL is the inability to fabricate a defect-free mask blank and the lack of the infrastructure needed for defect inspection and review. A reflective mask for EUVL consists of buffer and absorber (e.g., Cr or TaN) layers deposited on a ruthenium-capped Mo/Si ML-coated blank. The performance requirements for an EUV mask blank can be found in the SEMI P38-1103 Specification for Absorber Film Stacks and Multilayers on Extreme Ultraviolet Mask Blanks.[45] EUV masks are similar to masks for conventional optical lithography, except they are coated with 40 layer pairs of Mo (2.8 nm thick) and Si (4.1 nm thick) instead of a single layer of chrome, and the 6″ × 6″ × 0.25″ mask substrate is a low thermal expansion material instead of quartz, as shown in Figure 20.11.[46] The performance specifications for EUV mask substrates can be found in the SEMI P27-1102 Specifications for Extreme Ultraviolet Lithography Mask Substrates.[47] A patterned EUV mask, like the one shown in Figure 20.11, was fabricated from an ML-coated blank by selectively etching the absorber and buffer layers.

20.4.2.1 EUV Mask Blanks

Fabrication of a defect-free EUV mask blank is exceedingly difficult. First, it requires an almost perfectly flat (front-side flatness no more than 32 nm peak to valley for the 32 nm technology node) and defect-free substrate with an extremely low coefficient of thermal expansion (0 ± 12 ppb/K in the temperature



FIGURE 20.11 Cross-sectional TEM image showing EUV reflective mask architecture. (Reprinted from Levinson, H.J., *Principles of Lithography* 2nd edn., SPIE Press, Bellingham, WA, 2005. With permission.)

range from 12°C to 25°C). Then, it requires a coating technology that can deposit Mo/Si MLs with high reflectivity (65%–70%), good thickness uniformity, and nearly zero defect density (the defectivity specification for the 32 nm technology node is a defect density less than 0.003 defects/cm^2 at defect sizes greater than 25 nm). EUV mask blanks meeting the SEMI P38-1103 Class A production specifications for reflectance and uniformity are available today; deposition technologies and processes for zero-added–defect Mo/Si ML deposition are not.

In an attempt to accelerate the development of the zero-defect-adder Mo/Si deposition process needed to produce defect-free mask blanks, SEMATECH established the Mask Blank Development Center (MBDC) in Albany, New York in 2003. During the MBDC ramp-up, SEMATECH, in partnership with Veeco Instruments, successfully transferred technology developed at LLNL specifically for depositing low-defect ML coating on EUV blanks. A record of the MBDC's progress in reducing the defectivity on EUV blanks is shown in Figure 20.12.[48]

The champion plate from a recent deposition run exhibited only eight defects in the quality area of the plate (132 × 132 mm), corresponding to a defect density of 0.04 defects/cm^2 at defect sizes greater than 53 nm (polystyrene latex sphere equivalent size). At the present time, the defect density on the best blanks are dominated by defects that originate from substrate pits and bumps. The rate of progress in blank defect reduction is currently limited by the performance of available defect inspection tools. According to recent data from Intel Corporation, the most sensitive defect inspection tools have a 98% capture rate for 45 nm (SiO_2 sphere equivalent) defects on quartz and for 50 nm defects on MLs.[49] Further progress in defect-free EUVL mask development will require defect inspection tools with sensitivities down to approximately 25 nm. Whether this level of performance can be achieved by incremental improvements to existing tools or will require the development of an entirely new defect inspection tool platform is still an open question.

20.4.2.2 EUV Mask Defectivity

As with chrome-on-quartz masks for optical lithography today, the absorbing pattern on an EUV mask can be inspected using a commercially available DUV mask inspection tool and repaired as needed using focused-ion or electron-beam techniques. While the repair of defects that occur during the absorber patterning process is reasonably straightforward, repair of defects



FIGURE 20.12 Record of the defect reduction progress at the SEMATECH Mask Blank Development Center in Albany, New York. (Reprinted from Kearney, P. et al., *Proc. SPIE*, 6921, 69211X, 2008. With permission.)



FIGURE 20.13 Illustration of a multilayer phase defect that could result from a growth discontinuity or replicated substrate imperfection, which leads to an abrupt phase shift and, if resolved, a printable defect.

in the ML coating or on the substrate below the reflective coating is problematic. Examples of these "phase defects" were noticed during the course of EUV printing experiments as early as 1992 and were studied systematically by Nguyen et al. in 1994.[50] The illustration in Figure 20.13 shows how a small height difference in a ML coating can lead to cancellation of the reflective waves and an unexpected, high-contrast feature in the aerial image.

Recent results on EUV mask defectivity, determined by printing an EUV mask on resist-coated wafers and inspecting those wafers in a KLA-Tencor 2800 wafer inspection system operating in cell-to-cell mode, showed that only a few defects originated from the mask.[46] The resulting mask blank defect density inferred from these measurements (about 1 defect/cm^2) is approximately 30 times smaller than expected based on mask blank inspection statistics (30–60 defects/cm^2) and masks fabricated from state-of-the-art mask blanks should provide even better defectivity performance.

20.4.3 EUV Resists

The development of an EUV resist that can simultaneously meet the resolution, line-edge roughness (LER), and sensitivity requirements for insertion of EUVL into manufacturing is now ranked by the International EUVL Symposium Technical Steering Committee as the third highest risk to the commercialization of EUVL.

20.4.3.1 Current State of the Art

Because of the limited power available from current EUV sources, state-of-the-art EUV resists must be chemically amplified. The important properties of a chemically amplified resist (CAR) are due mainly to its photo acid generator and its polymer type, which in most cases is the same as those used in resists for 248 and 193 nm lithographies. The chief advantages of a CAR is its high sensitivity and resolution; its drawbacks are high LER, tendency towards pattern collapse, and high EUV light absorption. Pattern collapse depends on the aspect ratio of the resist pattern and, for features less than 30 nm in width, the critical aspect ratio is approximately 2. Assuming aspect ratio scaling continues to hold true, patterning for the 22 nm half-pitch node will require film thicknesses near 40 nm, although the situation can be improved somewhat using surfactant rinses, bilayer resist technologies, and supercritical CO$_2$ drying. The mechanism responsible for EUV light absorption in EUV resists differs from that in optical resists because the absorption results from the atomic nature of the excitation rather than from the making or breaking of molecular bonds. The high light absorption of all resist material in the EUV spectral region leads to resist patterns with sloping (non-vertical) sidewall profiles that, like pattern collapse, can be improved by using an ultrathin imaging layer over a hard mask in a bilayer or trilayer approach. The resolution performance of state-of-the-art EUV CAR resists printed with the SEMATECH Berkeley MET with 45° rotated dipole illumination is shown in Figure 20.7b, and with 0.35/0.55 annular illumination in Figure 20.7c.[33]

20.4.3.2 The RLS Challenge

The key lithographic performance parameters of CARs, resolution (R), line-edge roughness (L), and sensitivity (S), are highly interdependent—a fact that is often called the RLS challenge or the RLS trade-off. The correlation between resist sensitivity and resolution for a collection of EUV resists evaluated with the SEMATECH Berkeley MET in 2007[51] is shown in Figure 20.14a. Clearly, the materials that exhibit the highest resolution tend to be the least sensitive. The correlation between line edge roughness and sensitivity for a large selection of EUV resists, also tested on the SEMATECH Berkeley MET,[52] is shown in Figure 20.14b. Several attempts to model the interdependences among the performance parameters R, L, and S have been made. Among these, the lithographic uncertainty principle (K_{LUP}) described by van Steenwinckel et al.[53] and the Z-constant proposed by Wallow et al.[51] where [$Z \sim (\text{half-pitch})^3 \cdot \text{LER}^2 \cdot \text{sensitivity}$] have proven to be the most useful. While no single material simultaneously meets resolution, LER, and sensitivity targets for the 22 nm half-pitch node, a number of materials have been developed that meet both the resolution and sensitivity targets. LER remains the single most challenging performance parameter and, at this point, satisfactory values can only be obtained with a high aerial image contrast imaging system and at an unacceptably high exposure dose. The curve in Figure 20.14b is the prediction of a simple model for the shot noise-limited LER. Because of its short exposure wavelength, it is possible that EUVL could have an additional contribution to LER due to shot noise; for the same exposure energy, a EUV image will have a smaller number of photons per pixel. For the most sensitive resist formulations shown in Figure 20.14b, LER tends to be dominated by shot noise, whereas the LER in slower resists appears to be dominated by other effects.

20.4.4 EUV Mask Handling

Because EUV radiation is highly absorbed by all materials, a membrane pellicle for an EUVL mask is not generally considered to be practical and the current strategy for maintaining a defect-free EUV mask is to utilize a removable pellicle to protect the mask



FIGURE 20.14 (a) Observed correlation between resist sensitivity (dose to size at 40 nm half-pitch) and limiting resolution for a collection of EUV resist evaluated using the SEMATECH Berkeley MET. (Reprinted from Wallow, T. et al., *Proc. SPIE*, 6921, 69211F, 2008. With permission from SPIE.) (b) LER and sensitivity for a large selection of EUV resists evaluated using the SEMATECH Berkeley MET. The curve represents a simple model estimate for short-noise-limited LER. (Reprinted from La Fontaine, B. et al., *J. Vac. Sci. Technol. B*, 25, 2089, 2007. With permission.)

during shipping, handling, and storage and to remove the pellicle only when the mask is being inspected or when it is in the vacuum environment of an EUV exposure tool and is ready for exposure. An EUV-removable pellicle can be as simple as a protective, flat face plate that shields the patterned side of the mask from particulate contamination. Variants of the simple face plate are the Fala/Intel Bracket, which adds an additional level of protection by shielding the sides of the mask, the ASML frame, and storage box, which is used as the reticle carrier in their ADTs, and the Nikon, Canon, and Entegris inner pod, which includes a backside lid to form the enclosure shown in the inset of Figure 20.15. The results of four recent tests of a SEMI (draft) 4466-compliant inner pod fabricated by SEMATECH (a so-called S-pod) are shown in Figure 20.15. The data shows, on average, about 0.1 particle added per cycle of use, where cycle is defined as a round-trip shipment, vacuum pump vent, and accelerated storage test at 53 nm PSL equivalent inspection capability.[54]



FIGURE 20.15 s-Pod EUV reticle carrier test results for round-trip shipping, vacuum pumping and venting, and accelerated storage. Inset: photograph of reticle pod. (Reprinted from Gomei, Y. et al., *Proc. SPIE*, 6517, 65170W, 2008. With permission from SPIE; He, L. et al., *Proc. SPIE*, 6921, 69211Z, 2008. With permission.)

20.4.5 EUV Optics and Mask Contamination

Another area of significant concern is the shortening of the lifetime of the projection and illuminator optics and the reflective mask due to surface contamination. Water vapor and hydrocarbons are the two major contaminants present in the vacuum environment of an EUVL exposure tool that are known to reduce the lifetime of the reflecting surfaces. Of the two contaminants, carbon contamination is generally considered to be less damaging to optics' lifetimes because carbon films can be removed by hydrogen or oxygen cleaning. A particularly egregious example of carbon contamination is depicted in Figure 20.16,



FIGURE 20.16 EUV illuminator mirror showing strong signs of contamination. (Reprinted from La Fontaine, B. et al., *J. Vac. Sci. Technol. B*, 25, 2089, 2007. With permission.)

which shows a photograph of the first illuminator mirror from the SEMATECH EUV MET in Albany with an annular-shaped zone of darkening where the EUV radiation impinged on the mirror surface.

Because an oxide layer strongly absorbs EUV radiation (a 0.3 nm increase in oxide thickness leads to a more than 1% EUV reflectance loss) and is more difficult to remove, oxidation is viewed as a more serious threat to optics' lifetimes. The vacuum environment in an EUVL exposure tool can be modified (by introducing the appropriate gases) to strike a balance between oxidation and carbon growth. This method of contamination control was utilized in 2001 in the EUV Engineering Test Stand[55] (discussed in Section 20.2.1). Oxidation control involving the use of long-life anti-oxidative capping layers comprised of the metal oxides of V, Cr, or W together with carbon-film suppression and removal using EUV + O_2 *in situ* cleaning is a contamination-control strategy currently being explored in Japan.[56] At the 2008 EUVL Symposium, ASML presented data showing that the lifetime of the projection optics in both of its ADTs is at least 4.5×10^9 source pulses (about 1.5 years).[57] For an acceptable COO, the operational lifetime of the imaging system in an EUV exposure tool for HVM must be greater than 5 years (or 30,000 light-on hours). Since the models that have been developed to predict how contamination scales with EUV power density and environmental conditions have not yet reached the level of sophistication needed to accurately predict what the lifetime will be in an HVM tool, the integration of a moderately high-power EUV source with a full-field EUV scanner has become a critical need.

The masks in the EUV METs currently in operation around the world have now received a sufficiently large cumulative dose of EUV radiation that carbon contamination on their surfaces is becoming an issue. Attempts are being made to characterize mask contamination so the lifetime of an EUV mask can be predicted and a safe and effective mask-cleaning process can be developed. Preliminary results from Auger emission spectroscopy of the mask surface show clear signals of carbon and oxygen in the contaminated areas. Preliminary results from a print-based study of a contaminated mask showed that the primary effect of the contamination is an increase in dose to size with increasing contamination.[41] An analysis of wafers printed with the same mask after cleaning show that the original dose to size was recovered with only a slight reduction in DOF. The results also suggest that the increase in dose to size could be used as a metric to trigger a mask clean.

20.5 Future Perspectives

The two EUVL technology elements that are at highest risk of not being ready when needed are source power at intermediate focus (IF) and mask blank defectivity. Source power at IF, which is critically important to exposure tool throughput, currently falls far short of what will be needed for an EUVL pilot production tool. However, according to Cymer Inc.'s LPP source roadmap, a LPP EUV source with beta-level performance will be delivered to ASML in 1Q09 and a LPP EUV source with 100 W at IF will be available before the end of the 2009 calendar year.[57] If Cymer's LPP EUV source delivery schedule slips, ASML's EUV preproduction tool schedule will also slip and—because of this—source power at IF is generally regarded as the technology element that will determine the date of EUVL manufacturing insertion. Mask blank defectivity, which is critically important to the yield of electrically functional devices, also falls far short of what will be needed for HVM, and given the current rate of progress in blank defectivity reduction, it now seems likely that completely defect-free blanks will not be available in the foreseeable future. However, several of the blank-defect workarounds that are now being actively pursued, such as defect compensation and fiducials for blank disposition, could allow functional devices to be manufactured even at current blank defect levels. Most of the other EUVL technology elements are already able to satisfy 15 nm pilot line requirements. Mask handling, optics quality, resist resolution, and sensitivity are already in specification. The only other performance metric that is of concern is resist LER. The current best LER, about 3.0 nm (3σ) at 32 nm HP and 15 mJ/cm^2 dose, is much higher than the International Technology Roadmap for Semiconductors specification for the 15 nm hp node, 1.1 nm (3σ)[31]; however, the use of smoothing under-layers, special rinse liquids, and/or smoothing during etch transfer is expected to help close this gap.

EUVL provides a wider manufacturing process window, has a potentially higher throughput, and is the most easily extendible of all the lithographic technologies that have been evaluated as possible replacements for optical projection lithography. The wider process window and easier extendibility for EUVL can be seen most clearly by rearranging the Rayleigh equation for resolution (RES = $k_1\lambda$/NA, where RES is resolution, λ is wavelength, NA is numerical aperture, and k_1 is a process-dependent constant) to give an expression for k_1 in terms of resolution:

$$k_1 = \left[\frac{\text{NA}}{\lambda}\right]\text{RES} = \left[\frac{\text{NA}}{\lambda}\right]\text{HP} \tag{20.1}$$

where resolution (RES) has been replaced with the period, or half-pitch, of dense line and space patterns. Plots of k_1 versus HP (nm) for a 193 nm immersion exposure tool with a 1.30 NA imaging system and for EUV exposure tools with 0.25, 0.35, and 0.45 NA imaging systems are shown in Figure 20.17.

Also shown in Figure 20.17 are some dates from the roadmaps of the most aggressive semiconductor chip makers for the production ramps at the 32, 22, and 15 nm technology nodes (i.e., at which the logic HP is assumed to undergo an approximate 0.7 shrink). In the not-too-distant past, k_1 values of 0.6 and larger were needed for HVM. More recently, it has been found possible to work at lower values of k_1, at the cost of tighter process control, by employing a variety of resolution enhancement techniques such as off-axis illumination, phase-shifting masks, and application of optical proximity correction to the patterns on the mask. The limiting value for k_1 is 0.25, below which the image contrast for periodic line and space patterns is zero. The calculated values plotted in Figure 20.17 show that EUVL, even with the smallest NA imaging system, will allow a return to manufacturing process windows that seems impossibly large by today's standards. By utilizing EUV imaging systems with larger and larger NAs, the route to higher resolution that optical lithography took in the past, EUVL should be able to print dense features at HP well below 20 nm. In contrast, the process window for single-exposure 193 nm immersion lithography, with water as the immersion fluid, will shrink to zero at an HP approximately equal to 39 nm (solid line at k_1 = 0.25 in Figure 20.17). Even if major advances in high-index immersion fluids, high-index lens materials, and high-index resists are made, SE 193 nm immersion lithography is unlikely to be extended much below 32 nm HP, and double-exposure double-etch (DE^2) 193 nm immersion lithography is unlikely to be extended much below 22 nm HP (dashed line at k_1 = 0.18 in Figure 20.17).



FIGURE 20.17 A plot of the Rayleigh k_1 parameter vs. the half-pitch of dense 1:1 lines and spaces for a 193 nm immersion imaging system with 1.30 NA and 13.5 nm EUV imaging systems with 0.25, 0.35, and 0.45 NA.

Several full-field EUVL pilot production tools will be available in 2011. According to ASML's EUVL tool roadmap,[15] two EUVL exposure tool models will be available in 2011: the NXE 3100 preproduction tool (illustrated in Figure 20.18), which has a 0.25 NA imaging system, will support 4 nm overlay, and provide a throughput of about 60 wafers per hour; and a first-generation HVM tool, which will have a 0.32 NA imaging system, will support 3 nm overlay, and provide a throughput of about 150 wafers per hour. According to Canon's EUV tool development plan,[58] a six-mirror 0.3 NA imaging system will be available in 2011 for in-house testing purposes, but the first of Canon's VS2 HVM EUV exposure tools will not be available until late in 2015. According to Nikon's EUVL tool development scenario,[56] a 0.25 NA EUV2



FIGURE 20.18 **(See color insert following page 20-14.)** Artist illustration of ASML NXE: 3100 preproduction EUV exposure tool showing the LPP EUV source on the right, the illuminator optics in the center, and the mask and the projection optics on the right. (Courtesy of ASML, Veldhoven, the Netherlands.)

process development tool with lower wavefront error and lower flare imaging optics will be available at its factory early in 2011 and a greater than 0.3 NA EUV3 HVM EUVL exposure tools will be available early in 2012.

Abbreviations

ADT	Alpha Demo Tool
CAR	chemically amplified resist
COO	cost of ownership
DOF	depth of focus
DPP	discharge-produced plasma
DRAM	dynamic random access memory
DUV	deep ultraviolet
ETS	Engineering Test Stand
EUV	extreme ultraviolet
EUVL	extreme ultraviolet lithography
FET	field-effect transistor
HP	half-pitch
HSFR	high-spatial frequency roughness
HVM	high-volume manufacturing
IF	intermediate focus
IL	interference lithography
LBNL	Lawrence Berkeley National Laboratory
LER	line-edge roughness
LLNL	Lawrence Livermore National Laboratory
LPP	laser-produced plasma
LSRF	low spatial frequency roughness
LSI	lateral-shearing interferometry
MBDC	Mask Blank Development Center
MET	micro-exposure tool
ML	multilayer
MSRF	mid-spatial frequency roughness
NA	numerical aperture
PMI	phase-measuring interferometry
PSD	power spectral density
PSDI	phase-shifting diffraction interferometry
PSI	Paul Scherrer Institute
PSL	polystyrene latex (sphere)
PS/PDI	phase-shifting point-diffraction interferometry
SEM	scanning electron microscope
SNL	Sandia National Laboratory
SRAM	static random access memory
TEM	transmission electron microscope

References

1. Henry, J., Spiller, E., and Weisskopf, M., Imaging performance of a normal incidence x-ray telescope measured at 0.18 KeV, *Proc. SPIE* **316**, 166–168 (1981).
2. Lovas, I., Stanty, W., Spiller, E. et al., Design and assembly of a high resolution Schwarzschild microscope for soft-x-rays, *Proc. SPIE* **316**, 90–97 (1981).
3. Underwood, J.H. and Barbee, T.W. Jr., Soft x-ray imaging with a normal incidence mirror, *Nature* **294**, 429–431 (1981).
4. Takei, K. and Maeda, Y., Preparation of multi-layered tungsten-carbon films by ion beam sputtering, *Jpn. J. Appl. Phys.* **24**, 1366–1367 (1985).
5. Kinoshita, H., Kaneko, T., Takei, H. et al., Study on x-ray reduction projection lithography, *Presentation at the 47th Autumn Meeting of the Japan Society of Applied Physics*, Sapporo, Japan, Paper No. 28-ZF-15 (1986).
6. Bjorkholm, J., Bokor, J., Eichner, L. et al., Reduction imaging using multilayer coated optics: Printing of features smaller than 0.1 microns, *J. Vac. Sci. Technol. B* **8**, 1509–1513 (1990).
7. Tichenor, D.A., Kubiak, G.D., Haney, S.J. et al., Recent results in the development of an integrated EUVL laboratory tool, *Proc. SPIE* **2437**, 292–307 (1995).
8. Kinoshita, H., Kurihara, K., Mizota, T. et al., Large-area, high-resolution pattern replication by the use of a two-aspherical-mirror system, *Appl. Opt.* **32**, 7079–7083 (1993).
9. Kurihara, K., Kinoshita, H., Mizota, T. et al., Two-mirror telecentric optics for soft x-ray reduction lithography, *J. Vac. Sci. Technol. B* **9**, 3189–3192 (1991).
10. Haga, T., Tinone, M., Takenaka, H., and Kinoshita, H., Large-field (>20 × 25 mm^2) replication by EUV lithography, *Microelectron. Eng.* **30**, 179–182 (1996).
11. Naulleau, P., Goldberg, K.A., Anderson, E. et al., Status of EUV microexposure capabilities at the ALS using the 0.3-NA MET optic, *Proc. SPIE* **5374**, 881– 891 (2004).
12. Naulleau, P., Anderson, C., Chiu, J. et al., Advanced extreme ultraviolet resist testing using the SEMATECH Berkeley 0.3-NA micro field exposure tool, *Proc. SPIE* **6921**, 69213N1–69213N11 (2008).
13. Murakami, K., Oshino, T., Shimizu, S. et al., Basic technologies for extreme ultraviolet lithography, *OSA Trends Opt. Photon.* **4**, 16–20 (1996).
14. Kinoshita, H., Watanabe, T., Niibe, M. et al., Three-aspherical mirror system for EUV lithography, *Proc. SPIE* **3331**, 20–31 (1998).
15. Tichenor, D.A., Ray-Chaudhuri, A.K., Replogle, W.C. et al., System integration and performance of the EUV engineering test stand, *Proc. SPIE* **4343**, 19–37 (2001).
16. Meiling, H., Buzing, N., Cummings, K. et al., EUV system—Moving towards production, *Proc. SPIE* **7271**, 7271021–72710215 (2009).
17. Murakami, K., Oshino, T., Kondo, H. et al., Development status of projection optics and illumination optics for EUV1, *Proc. SPIE* **6921**, 69210Q1–69210Q7 (2008).
18. Spiller, E., Multilayer optics for x-rays, in P. Dhez and C. Weisbuch (eds.), *Physics, Fabrication and Applications of Multilayer Structures*, Plenum, New York (1987), pp. 271–309.
19. Barbee, T.W. Jr., Mrowka, S., and Hettrick, M., Molybedenum-silicon multilayer mirrors for the extreme ultraviolet, *Appl. Opt.* **24**, 883–886 (1985).

20. Stearns, D.G., Rosen, R.S., and Vernon, S.P., Multilayer mirror technology for soft-x-ray projection lithography, *Appl. Opt.* **32**, 6952–6960 (1993).
21. Perera, R.C.C. and Underwood, J.H., Results from our recently delivered automated reflectometer for measurement of reflectivity of EUV lithographic masks, *Poster Presentation at the 2006 International EUVL Symposium*, Barcelona, Spain, 15–18 October 2006.
22. Sommargren, G., Phase shifting diffraction interferometry for measuring extreme ultraviolet optics, *OSA Trends Opt. Photon.* **4**, 108–112 (1996).
23. Sommargren, G., Phillion, D., Johnson, M. et al., 100-picometer interferometry for EUVL, *Proc. SPIE* **4688**, 316–328 (2002).
24. Goldberg, K., Naulleau, P., Denham, P. et al., EUV interferometry of the 0.3 NA MET optics, *Proc. SPIE* **5037**, 69–74 (2003).
25. Goldberg, K., Naulleau, P., Denham, P. et al., EUV interferometric testing and alignment of the 0.3 NA MET optic, *Proc. SPIE* **5373**, 64–73 (2004).
26. Harned, N., Goethals, M., Groeneveld, R. et al., EUV lithography with the Alpha Demo Tools: Status and challenges, *Proc. SPIE* **6517**, 6517061–65170612 (2007).
27. Tawarayama, K., Aoyama, H., Magoshi, S. et al., Recent progress of EUV full-field exposure tools in Selete, *Proc. SPIE* **7271**, 7271181–7271188 (2009).
28. Meiling, H., Meyer, H., Banine, V. et al., First performance results of the ASML alpha demo tool, *Proc SPIE* **6151**, 6151081–61510812 (2006).
29. Miura, T., Murakami, K. Suzuki, K. et al., Nikon EUVL development progress update, *Proc. SPIE* **6517**, 6517071–65170710 (2007).
30. Pierson, B., Wallow, T., Mizuno, H. et al., EUV resist performance on the ASML ADT and LBNL MET, *Oral Presentation at the 2008 International EUVL Symposium*, Lake Tahoe, CA, 28 September 2008.
31. Koh, C., Ren, L., Georger, J. et al., Assessment of EUV resist readiness for 32 nm hp manufacturing, and extendibility study of EUV ADT using state-of-the-art resist, *Proc. SPIE* **7271**, 7271241–72712411 (2009).
32. Uzawa, S., Kubo, H., Miwa, Y. et al., Path to the HVM in EUVL through the development and evaluation of the SFET, *Proc. SPIE* **6517**, 6517081–65170811 (2007).
33. Naulleau, P., Anderson, E., Baclea-an, L.-M. et al., The SEMATECH Berkeley microfield exposure tool: Learning at the 22 nm node and beyond, *Proc. SPIE* **7271**, 72710W1–72710W11 (2009).
34. Solak, H.H., Ekinci, Y., Kaser, P., and Park, S., Photon-beam lithography reaches 12.5 nm half-pitch resolution, *J. Vac. Sci. Technol. B* **25**, 91–95 (2007).
35. Ekinci, Y., Solak, H.H., Padeste, C. et al., 20 nm line/space patterns in HSQ fabricated by EUV interference lithography, *Microelectron. Eng.* **84**, 700–704 (2007).
36. La Fontaine, B., Deng, Y., and Kim, R.-H., The use of EUV lithography to produced demonstration devices, *Proc. SPIE* **6921**, 69210P1–69210P10 (2008).
37. Lorusso, G.F., Hermans, J., Goethals, A.M. et al., Imaging performance of the EUV alpha demo tool at IMEC, *Proc. SPIE* **6921**, 69210O1–69210O11 (2008).
38. Wood, O., Koay, C.-S., Petrillo, K. et al., Integration of EUV lithography in the fabrication of 22-nm node devices, *Proc. SPIE* **7271**, 7271041–72710411 (2008).
39. Park, J.-O., Koh, C., Goo, D. et al., The application of EUV lithography for 40 nm node DRAM device and beyond, *Proc. SPIE* **7271**, 7271141–7271149 (2009).
40. Eom, T.-S., Park, S., and Park, J.-T., Comparative study of DRAM cell patterning between ArF immersion and EUV lithography, *Proc. SPIE* **7271**, 7271151–72711511 (2009).
41. La Fontaine, B., Wood, O., and Medeiros, D., The future of EUV lithography, N. Yamamoto (ed.), *Proceedings of SEMI Technology Symposium*, SEMI Japan, Chiba, Japan, 2008.
42. Ota., K., Watanabe, Y., Banine, V., and Frankin, H., EUV source requirements for EUV lithography, in Vivek Bakshi (ed.), *EUV Sources for Lithography*, SPIE Press, Bellingham, WA (2006), pp. 27–43.
43. Corthout, M., Apetz, R., Bruederman, J. et al., Sn DPP source-collector modules: Status of Alpha sources, Beta developments, and HVM experiments, *Proc. SPIE* **7271**, 72710A1–72710A10 (2009).
44. Brandt, D.C., Fomenkov, I.V., Ershov, A.I. et al., LPP source system development for HVM, *Proc. SPIE* **7271**, 727031–72710311 (2009).
45. SEMI P38-1103, Specifications for absorbing film stacks and multilayers on extreme ultraviolet lithography blanks, Semiconductor Equipment and Materials International, San Jose, CA (2003).
46. Levinson, H.J., *Principles of Lithography*, 2nd edn, SPIE Press, Bellingham, WA (2005).
47. SEMI P37-1102, Specifications for extreme ultraviolet lithography mask substrates, Semiconductor Equipment and Materials International, San Jose, CA (2003).
48. Kearney, P., Lin, C.C., Sugiyama, T. et al., Ion beam deposition for defect-free EUVL mask blanks, *Proc. SPIE* **6921**, 69211X1–69211X7 (2008).
49. Ma, A., Liang, T., Park, S.-J. et al., EUVL blank defect inspection capability at Intel, *2008 International EUVL Symposium*, Lake Tahoe, CA, September 29, 2008.
50. Nguyen, K., Attwood, D., Mizota, T. et al., Imaging of EUV lithography masks with programmed defects, *OSA Proc. Extreme Ultraviolet Lithography* **23**, 193–203 (1994).
51. Wallow, T., Higgins, C., Brainard, R. et al., Evaluation of EUV resist materials for use at the 32 nm half-pitch node, *Proc. SPIE* **6921**, 69211F1–69211F11 (2008).
52. La Fontaine, B., Deng, Y., Kim, R.-H. et al., Extreme ultraviolet lithography: From research to manufacturing, *J. Vac. Sci. Technol. B* **25**, 2089–2093 (2007).

53. Van Steenwinckel, D., Gronheid, T., Lammers, J.H. et al., A novel method for characterizing resist performance, *Proc. SPIE* **6519**, 65190V1–65190V12 (2007).
54. He, L., Wurm, S., Seidel, P. et al., Status of EUV reticle handling solutions in meeting 32 nm HP EUV lithography, *Proc. SPIE* **6921**, 69211Z1–69211Z10 (2008).
55. Malinowski, M., Grunow, P., Steinhaus, C. et al., Use of molecular oxygen to reduce EUV-induced carbon contamination of optics, *Proc. SPIE* **4343**, 347–356 (2001).
56. Miura, T., Murakami, K., Kawai, H. et al., Nikon EUVL development progress update, *Proc. SPIE* **7271**, 72711X1–72711X11 (2009).
57. Meiling, H., Lok, B., Hultermans, B. et al., EUV alpha demo tools—Stepping stones towards volume production, *2008 International EUVL Symposium*, Lake Tahoe, CA, 28 September 2008.
58. Hasegawa, T., Uzawa, S., Honda, T. et al., Development status of Canon's full-field EUVL tool, *Proc. SPIE* **7271**, 72711Y1–72711Y11 (2009).

IV

Optics of Nanomaterials

21 Cathodoluminescence of Nanomaterials *Naoki Yamamoto* **21**-1
Introduction • Fundamentals of Cathodoluminescence • Optical Properties of Semiconductor Quantum Structures • Quantum Structures • Application of TEM-CL • Acknowledgment • References

22 Optical Spectroscopy of Nanomaterials *Yoshihiko Kanemitsu* **22**-1
Introduction • Carbon Nanotubes • Nanoparticle Quantum Dots • Multiexciton Generation • Summary • Acknowledgments • References

23 Nanoscale Excitons and Semiconductor Quantum Dots *Vanessa M. Huxter, Jun He, and Gregory D. Scholes* **23**-1
Introduction to Nanoscale Excitons • Nonlinear Optical Properties of Semiconductor Quantum Dots • Two-Photon Absorption in Semiconductor Quantum Dots • Conclusion • References

24 Optical Properties of Metal Clusters and Nanoparticles *Emmanuel Cottancin, Michel Broyer, Jean Lermé, and Michel Pellarin* **24**-1
Introduction • Theoretical Description • Experimental Results: State of the Art • Conclusion and Outlooks • Acknowledgments • References

25 Photoluminescence from Silicon Nanostructures *Amir Sa'ar* **25**-1
Introduction • Synthesis of Silicon Nanostructures • Luminescence Properties of Silicon Nanostructures • The Vibron Model: The Relationship between Surface Polar Vibrations and Nonradiative Processes • Concluding Remarks • Acknowledgments • References

26 Polarization-Sensitive Nanowire and Nanorod Optics *Harry E. Ruda and Alexander Shik* **26**-1
Introduction • Single Nanowires and Nanorods • Arrays of Nanorods • Conclusion • Acknowledgments • References

27 Nonlinear Optics with Clusters *Sabyasachi Sen and Swapan Chakrabarti* **27**-1
General Introduction: Fundamentals of Nonlinear Optics and Different Nonlinear Optical Effects • Quantum Formulation of Nonlinear Optics • Nonlinear Optics with Materials • Why Are Clusters So Important? • Review of Nonlinear Optics with Clusters • Conclusions • References

28 Second-Harmonic Generation in Metal Nanostructures *Marco Finazzi, Giulio Cerullo, and Lamberto Duò* **28**-1
Introduction • Nonlinear Optics and Second Harmonic Generation • Second Harmonic Generation in Nanosystems • Leading Order Contributions to the Second Harmonic Generation Process in Nanoparticles • Emission Patterns and Light Polarization • Allowed and Forbidden Second Harmonic Emission Modes: Examples • Second Harmonic Generation in Single Gold Nanoparticles • Perspectives • Conclusions • Acknowledgments • References

29 Nonlinear Optics in Semiconductor Nanostructures *Mikhail Erementchouk and Michael N. Leuenberger* **29**-1
Introduction • Semiconductor-Field Hamiltonian in $\mathbf{k} \cdot \mathbf{p}$-Approximation • Quantum Equations of Motion • Perturbation Theory: Four-Wave Mixing Response • Nonperturbative Methods: Rabi Oscillations • Conclusion • Acknowledgment • References

30 Light Scattering from Nanofibers *Vladimir G. Bordo* **30**-1
Introduction • Background • Basic Theory • Some Numerical Results • Experimental Implementation • Discussion • Summary and Outlook • Acknowledgments • References

31 Biomimetics: Photonic Nanostructures *Andrew R. Parker* **31**-1
Introduction • Engineering of Antireflectors • Engineering of Iridescent Devices • Cell Culture • Diatoms and Coccolithophores • Iridoviruses • The Mechanisms of Natural Engineering and Future Research • Acknowledgments • References

21

Cathodoluminescence of Nanomaterials

21.1 Introduction **21**-1
21.2 Fundamentals of Cathodoluminescence **21**-2
Radiative Recombination • Exciton • TEM-Cathodoluminescence Technique
21.3 Optical Properties of Semiconductor Quantum Structures **21**-5
Band Structure of Semiconductor • Theory of Light Emission • Polarization
21.4 Quantum Structures **21**-8
Quantum Well • Quantum Wire
21.5 Application of TEM-CL **21**-15
InP Nanowires • GaAs Nanowire • ZnO Nanowires
Acknowledgment **21**-24
References **21**-24

Naoki Yamamoto
Tokyo Institute of Technology

21.1 Introduction

Dimensionality and size are two factors that introduce new properties into semiconductor materials and enable us to provide new functionality in semiconductor nanoelectrics and photonics. Semiconductor quantum wires have been intensively studied, on one hand, for the theoretical interest in physical properties due to quasi-one-dimensional quantum confinement of an electronic system (Sakaki, 1980; Ogawa and Takagahara, 1991; Tanatar et al., 1998) and, on the other hand, for practical application to future optoelectronic devices such as low-threshold lasers (Arakawa and Sakaki, 1982) and polarization-sensitive devices (Wang et al. 2001). One-dimensional nanostructures have been primarily synthesized by lithography and an epitaxial technique on semiconductor substrates (Arakawa and Sakaki, 1982; Ils et al., 1994; Someya et al., 1995). V- (Kapon et al., 1989) and T-shaped quantum wires (Pfeiffer et al., 1990) were fabricated using epitaxial growth techniques (Wang and Voliotis, 2006), namely, molecular beam epitaxy (MBE) and metalorganic vapor phase epitaxy (MOVPE). However, excitons in the quantum wires were observed to be localized in monolayer step-induced islands at low temperatures (Guilet et al., 2003). The fluctuation of confinement potential along a quantum wire is a serious issue for realizing the characteristic property of a one-dimensional structure.

The free-standing nanowires of many semiconductors are recently produced by the growth technique using nanosized liquid droplets of the metal solvent (Hiruma et al., 1995; Gudiksen et al., 2002; Wu et al., 2002). This technique has an advantage to produce heterogeneous structure along the wire such as *p*–*n* junctions (Gudiksen et al., 2002) and superlattices (Wu et al., 2002). The optical properties of the nanowires have been studied by photoluminescence (PL) and absorption spectroscopy, which showed the blue shift of the peak energy due to the quantum confinement effect and giant polarization anisotropy in PL and optical absorption. Those properties will provide a potentiality for new application of the semiconductor nanowires. In spite of many works for synthesizing nanowires, there have been very few experimental works for studying the optical properties of self-standing nanowires, especially for a single nanowire, because of the limitation in spatial resolution. An isolated single nanowire of InP was studied by PL (Wang et al., 2001), which showed giant polarization anisotropy in PL and photoconductivity measurement. The giant polarization anisotropy is partly due to the excitation process by light, because the electromagnetic field in the nanowire, which generates carriers, depends on the polarization direction of incident light. Polarization anisotropy can also be expected in the light emission process, as in the case of electroluminescence (EL) and cathodoluminescence (CL).

We studied the optical properties of semiconductor nanowires, observing cathodoluminescence (CL) spectra and polarized monochromatic CL images of nanowires by using a transmission electron microscope (TEM) combined with a CL detection system (TEM-CL). The TEM-CL technique has an advantage in high spatial resolution and ability to characterize nanoscale structures (Yamamoto, 1984; Mitsui et al., 1996; Yamamoto et al., 2003, 2008; Ino and Yamamoto, 2008). In Section 21.2, a principle of TEM-CL technique is described based on the fundamental knowledge of radiative recombination processes and property of exciton. Luminescence in semiconductor nanowires shows characteristic properties in emission energy and polarization, because the optical transition between electronic states is affected by the quantum confinement effect. For understanding these properties, the theory of the band structure in semiconductors and optical transitions are described in Section 21.3. Quantum confinement effect on the optical properties of semiconductor nanowires and dielectric effect on polarization properties are described in Section 21.4. Finally, the experimental results of the TEM-CL technique for the InP and GaAs nanowires, which show the quantum confinement effect, and for the ZnO nanowires, which show the dielectric effect, are described in Section 21.5.

21.2 Fundamentals of Cathodoluminescence

21.2.1 Radiative Recombination

Luminescence in semiconductors is light emission phenomenon due to the recombination of excited electrons in the conduction band with holes in the valence band (Voos et al., 1980). It is called photoluminescence (PL) when those electrons and holes, the carriers, are excited by light, and called cathodoluminescence (CL) when they are excited by fast electrons. The band structures are classified into two types, direct gap type and indirect gap type. In the former type, the conduction band minimum is located at the Γ point ($k = 0$) in the k-space, whereas it is shifted from the Γ point in the latter type. The valence band maximum is located at the Γ point. Then in the case of the direct gap band structure, the radiative interband transition from the electron states in the conduction band to the hole states in the valence band occur at the Γ point accompanying with emission of photon at high recombination probability. GaAs and InP have band structure of this type. Whereas in the indirect gap type, the transition occurs with the association of phonon, and the recombination rate is rather small. Si and GaP have band structure of this type.

Typical recombination processes in semiconductors are depicted in Figure 21.1 (Pankove, 1971). First group is radiative recombination processes, i.e., (a) interband transition from conduction band to valence band, (b)–(d) annihilation of free exciton (FX) composed of a pair of electron and hole, and related processes of bound excitons (BX), (e)–(g) transitions of carriers trapped by impurity states such as donor and acceptor states. Second group is nonradiative recombinations, i.e., (h) multiphonon scattering, and (i) Auger process.

Photon energies in the recombination processes in Figure 21.1 are slightly lower than the band gap energy E_g, though their values are different from each other. The emission intensity by the interband transition from conduction band to valence band is generally small compared with the other processes. Photon energies in the impurity-associated recombination processes (Figure 21.1e and f) are given as follows:

$$(D, h) : E = E_g - E_D \tag{21.1}$$

$$(e, A) : E = E_g - E_A, \tag{21.2}$$

where E_D and E_A are binding energies of the donor level and acceptor level, respectively. Photon energy associated with the donor–acceptor pair transition (D, A) is given by

$$(D, A) : E = E_g - E_D - E_A + \frac{e^2}{4\pi\varepsilon R}, \tag{21.3}$$

where
R is a distance between donor and acceptor
ε is the dielectric constant of the material
e is the elemental charge



FIGURE 21.1 Recombination processes in semiconductors.

TABLE 21.1 Basic Parameters on Exciton in Typical Semiconductors

			Band Gap (eV)				
	Structure	Band Type	E_g (4 K)	E_g (300 K)	Dielectric Constant	E_x (meV)	FX Radius (nm)
Si	Diamond	Indirect	1.1698	1.11	11.4	14.7	403
Ge	Diamond	Indirect	0.7454	0.669	15.36	4.15	11
GaAs	Zinc-blend	Direct	1.519	1.43	13.1	4.21	13
InP	Zinc-blend	Direct	1.4236	1.34	12.61	5.12	11
GaN	Wurtzite	Direct	3.507	3.39	10.4 ($\|_c$) 9.5 ($\perp_c$)	23	3
ZnO	Wurtzite	Direct	3.436	3.37	8.84 ($\|_c$) 8.47 ($\perp_c$)	59	1.4

Note: The data were gathered from many literatures. The values of FX radius are calculated from the data in the other columns.

The last term indicates the Coulomb energy of the electron and hole pair. The impurities locate at lattice sites and R takes many different values. Then the emission peak due to (D, A) is composed of the multiple peaks to become a single broad peak, and dependence of the peak position on temperature and excitation rate is different from that of the other luminescence peaks of a single recombination process.

21.2.2 Exciton

An electron and a hole in semiconductors attract each other to form a FX. FX emission dominates in the radiative recombination process at low temperatures. The binding energy of exciton can be obtained by solving Schrödinger equation for electron and hole system attracted by Coulomb potential (Basu, 1997; Yu and Cardona, 1999). The binding energy of the lowest energy level and Bohr radius of FX in a bulk crystal are expressed by the hydrogen atom model as

$$E_X = 13.6\left(\frac{\mu}{m_0}\right)\frac{1}{\varepsilon^2}\,[\text{eV}] \tag{21.4}$$

$$a_X = \varepsilon\left(\frac{m_0}{\mu}\right)a_B, \tag{21.5}$$

where

ε is a relative dielectric constant
m_0 is the electron mass
μ is the reduced effective mass $((1/\mu = (1/m_e^*) + (1/m_h^*))$
a_B is Bohr radius (0.0529 nm), respectively

Photon energy of the FX emission is given by

$$E = E_g - E_X. \tag{21.6}$$

Some of excitons are trapped by impurities to form BX. The recombinations of excitons bounded by a neutral donor and ionized donor are expressed by (D^0, X) and (D, X), respectively. Similarly those of excitons bounded by a neutral acceptor and ionized acceptor are expressed by (A^0, X) and (A, X), respectively. The photon energy of the recombination is given by

$$E = E_g - E_X - E_b, \tag{21.7}$$

where E_b is a binding energy for trapping exciton at impurities. The magnitude of E_b is about 1/3 of E_D and E_A or less.

Basic parameters are listed in Table 21.1 for typical semiconductors. The values of the band gap energy and exciton binding energy are taken after several literatures (Pankove, 1971; Vugaftman et al., 2001). Exciton radius in the last column is calculated by (21.4) and (21.5) using the relative dielectric constants and exciton binding energies listed in the table. The values give only a measure of the exciton radius, because the differences among the reported values for the listed parameters are fairly large.

21.2.3 TEM-Cathodoluminescence Technique

TEM-cathodoluminescence (TEM-CL) is a technique to observe luminescence spectra and scanning images using a converged electron beam having a probe size of nm order (Yamamoto, 2002, 2008). The characteristics of TEM-CL are as follows: (1) Inner structures can be observed by TEM using thin samples and comparison between TEM and CL images is possible and (2) high spatial resolution of about 100 nm can be achieved. In CL, incident electrons are scattered in a specimen from the incident beam direction, as shown in Figure 21.2. The scattered electrons produce secondary electrons and plasmons, which generate electron-hole pairs in the hatched region (generation region). The excited carriers diffuse into surroundings and some of them recombine radiatively in a surrounding region (diffusion region). The diffusion of the excess minority carriers is important, because majority carriers exist everywhere. The resolution of CL is given by the diameter of the diffusion region, which is determined by the following factors: (1) the electron beam diameter, (2) size of the generation region, and (3) the diffusion length of the minority carrier. The diameter of the electron beam is less than 10 nm, and is negligible compared with the other factors.



FIGURE 21.2 Carrier generation and light emission process in TEM-CL.

The diameter of the beam spread due to elastic scattering in a thin specimen of thickness t (μm) is given by

$$b = 6.25\left(\frac{Z}{E}\right)\left(\frac{\rho}{A}\right)^{1/2} t^{3/2}\ [\mu\text{m}], \tag{21.8}$$

where

Z is the atomic number
A is the atomic mass
E (keV) is an incident electron energy
ρ (g/cm^3) is the density (Goldstein et al., 1977)

For example, assuming that for GaAs, $Z_{av} = 32$, $A_{av} = 72.3$, $\rho = 5.3\,\text{g/cm}^3$, and a specimen thickness is 0.5 μm, we obtain $b = 0.24\,\mu\text{m}$. However, Monte Carlo simulation of the electron scattering showed that the electron density is concentrated on the center of the beam, so the effective beam spread is smaller than that given by Equation 21.8 (see Figure 21.3).


(a) (b)

FIGURE 21.3 Monte Carlo simulation of (a) carrier generation by incident electrons and (b) carrier diffusion.

Equation 21.8 indicates that the higher accelerating voltage and thinner specimen thickness are advantageous for realizing high spatial resolution. However, when the accelerating voltage exceeds 100 kV, CL intensity starts to decrease because of the formation of specimen damage such as vacancies. TEM is typically operated at an accelerating voltage of 80 kV for CL measurements.

Diffusion length is an effective parameter for determining spatial resolution in CL of semiconductors. In insulators we can ignore carrier diffusion, but in semiconductors, carrier diffusion occurs with diffusion length of about 100 nm for GaN and 1 μm for GaAs. The diffusion length depends on dopant density and temperature, and reduces by surface recombination effect in thin specimens (Nakaji et al., 2005; Ino and Yamamoto, 2008). In quantum structures of semiconductors, carriers are confined in the localized structures smaller than the diffusion length, and individual nanostructures can be observed in CL images with high resolution as in the case of self-standing nanowires.

TEM-CL system based on a 200 kV transmission electron microscope (JEM-2000FX) is illustrated in Figure 21.4. Samples



FIGURE 21.4 TEM-CL system.

are examined in the TEM, both in the stationary beam illumination mode and the scanning beam illumination mode. The scanning electron microscopy (SEM) imaging using a secondary electron detector and the scanning transmission electron microscopy (STEM) imaging using a transmitted electron beam detector are both possible in the TEM. A beam size of 10 nm in diameter and a probe current of 1 nA was conventionally used. The temperature of a sample can be varied from 20 K to room temperature using a liquid-He cooling holder and liquid-N_2 cooling holder.

Light emitted from a sample is collected by an ellipsoidal mirror or parabolic mirror, being guided through a polarizer and a monochromator, and is detected by a photomultiplier tube (PMT) with a GaAs photocathode for visible light and an InGaAs photocathode for infrared light. A CCD detector is also used for measuring spectra with high sensitivity. Monochromatic CL images can be obtained by scanning the electron beam in the SEM mode. This imaging technique is similar to SEM or EDX mapping, because we use the light intensity collected by the mirror, instead of secondary electron yields or x-ray intensities, as in the case of the SEM. An image is composed of, for example, 100 × 100 pixels, so that the focused electron beam is scanned across the specimen and stays 0.1 s for each pixel. Therefore, it takes 1,000 s to obtain one complete image. The CL images in this paper are shown with the absolute intensity.

In the CL detection system, a linear polarizer is located between the ellipsoidal mirror and monochrometer to select linearly polarized components of the emitted light; here *p*-polarized (*s*-polarized) light, which is detected with the polarization direction parallel (perpendicular) to the monochrometer slit, mainly involves linearly polarized light component parallel (perpendicular) to the longer axis of the ellipsoidal mirror or the axis of the parabola. A mask with a small hole is set in front of the CCD detector for the angular resolved measurement using the parabolic mirror. The mask is movable using an *X*-*Y* stage in a plane normal to the light path and selects an emission angle.

21.3 Optical Properties of Semiconductor Quantum Structures

21.3.1 Band Structure of Semiconductor

The wavefunction of a carrier in a semiconductor crystal of volume *V* is of a form of Bloch function,

$$\psi_{nk} = \frac{1}{\sqrt{V}} e^{i\boldsymbol{k}\cdot\boldsymbol{r}} u_{nk}(\boldsymbol{r}), \tag{21.9}$$

which is a product of a periodic function $u_{nk}(\boldsymbol{r})$ of the crystal lattice and a slowly varying function $\exp(i\boldsymbol{k}\cdot\boldsymbol{r})$. Subscripts *n* and $\boldsymbol{k}$ indicate a number of the Bloch band and wavevector, respectively. In many semiconductors of diamond and zinc-blend structures, the carrier wavefunction at the bottom of the conduction band has the *s*-like orbital and that at the top of the valence band has the *p*-like orbital (Basu, 1997; Yu and Cardona, 1999). The function $u_{n0}(\boldsymbol{r})$ has a form of the atomic orbital in the vicinity of the atoms. The band structure of semiconductor has been treated by the $\boldsymbol{k}\cdot\boldsymbol{p}$ perturbation theory (Luttinger and Kohn, 1955). The wavefunctions of electron states at the Γ point in the conduction band are given by the product of the atomic *s*-orbital function and spin orbital function as

$$u^c\frac{1}{2} = |s\uparrow\rangle \quad \text{and} \quad u^c\left(-\frac{1}{2}\right) = |s\downarrow\rangle \tag{21.10}$$

Here, $|\uparrow\rangle$ and $|\downarrow\rangle$ are the spin orbital functions with up and down spins, respectively. The wavefunctions of the hole states at Γ point in the valence band are given by the $\boldsymbol{k}\cdot\boldsymbol{p}$ theory using the atomic *p*-orbital functions $|X\rangle$, $|Y\rangle$, and $|Z\rangle$. Assuming that $\boldsymbol{k}$ is parallel to the *z* direction, the following functions are used as the valence band wavefunctions,

$$\begin{aligned}
u_{\frac{3}{2},\frac{3}{2}} &= -\frac{1}{\sqrt{2}}\,|(X+iY)\uparrow\rangle \\
u_{\frac{3}{2},-\frac{3}{2}} &= \frac{1}{\sqrt{2}}\,|(X-iY)\downarrow\rangle \\
u_{\frac{3}{2},\frac{1}{2}} &= -\frac{1}{\sqrt{6}}\left[|(X+iY)\downarrow\rangle - |2Z\uparrow\rangle\right] \\
u_{\frac{3}{2},-\frac{1}{2}} &= \frac{1}{\sqrt{6}}\left[|(X-iY)\uparrow\rangle + |2Z\downarrow\rangle\right] \\
u_{\frac{1}{2},\frac{1}{2}} &= -\frac{1}{\sqrt{3}}\left[|(X+iY)\downarrow\rangle + |Z\uparrow\rangle\right] \\
u_{\frac{1}{2},-\frac{1}{2}} &= -\frac{1}{\sqrt{3}}\left[|(X-iY)\uparrow\rangle - |Z\downarrow\rangle\right]
\end{aligned} \tag{21.11}$$

where subscripts *j* and m_j in u_{j,m_j} are quantum number of total angular momentum $\boldsymbol{J}$ and the *z* component J_z, respectively. The functions $u_{\frac{3}{2},\frac{3}{2}}$ and $u_{\frac{3}{2},-\frac{3}{2}}$ express the heavy hole (hh) wavefunctions, $u_{\frac{3}{2},\frac{1}{2}}$ and $u_{\frac{3}{2},-\frac{1}{2}}$ the light hole (lh) wavefunctions, and $u_{\frac{1}{2},\frac{1}{2}}$ and $u_{\frac{1}{2},-\frac{1}{2}}$ are those of the split-off band due to the spin–orbit interaction. Band structure, energy level, and dispersion can be calculated by orthogonalizing the Luttinger–Kohn Hamiltonian containing 2nd order $\boldsymbol{k}\cdot\boldsymbol{p}$ perturbation terms (Basu, 1997). The band structure of the direct gap type is schematically illustrated in Figure 21.5a. In the valence band of the zinc-blend structure, the hh and lh bands are degenerated at the Γ point, as seen in the figure, and the split-off band locates below them. Whereas in the wurtzite structure this degeneracy is dissolved, and the A, B, C bands exist separately (Figure 21.5b). The effective mass of hole is determined by the curvature of the dispersion curve at $\boldsymbol{k} = 0$, i.e., the small curvature gives a large effective mass.

If the wavevector of hole $\boldsymbol{k}_\text{h}$ is inclined from the *z*-axis, the hole wavefunctions of the valence band change from (21.11). Here we



FIGURE 21.5 Band structures near the direct gap of (a) zinc-blend structure and (b) wurtzite structure.

take a z' axis parallel to $\boldsymbol{k}_h$, and x' and y' axes to be normal to z', as shown in Figure 21.6. The Cartesian coordinates (x, y, z) are fixed in space, and the coordinates (x', y', z') are related to (x, y, z) by the rotation of angle θ around the y-axis and successive rotation of angle ϕ around the z-axis. The conversion matrix between the wavefunctions in the two coordinates is expressed as

$$\boldsymbol{T} = \begin{pmatrix} \cos\theta\cos\phi & -\sin\phi & \sin\theta\cos\phi \\ \cos\theta\sin\phi & \cos\phi & \sin\theta\sin\phi \\ -\sin\theta & 0 & \cos\theta \end{pmatrix}. \tag{21.12}$$

Namely, the wavefunction of the heavy hole is expressed in each coordinates as

$$-\frac{1}{\sqrt{2}}\left|\left(X'+iY'\right)\uparrow\right\rangle = -\frac{1}{\sqrt{2}}\{(\cos\theta\cos\phi - i\sin\phi)\,|\,X\rangle + (\cos\theta\sin\phi + i\cos\phi)\,|\,Y\rangle - \sin\theta\,|\,Z\rangle\}\,|\uparrow\rangle \tag{21.13}$$



FIGURE 21.6 Relation between the coordinates fixed in space and those associated with the wavevector of hole $\boldsymbol{k}_\text{h}$.

and that of the light hole is expressed as

$$\frac{1}{\sqrt{6}}\,|\,(X'-iY')\uparrow\rangle + \sqrt{\frac{2}{3}}\,|\,Z'\downarrow\rangle = \frac{1}{\sqrt{6}}\{(\cos\theta\cos\phi + i\sin\phi)\,|\,X\rangle + (\cos\theta\sin\phi - i\cos\phi)\,|\,Y\rangle - \sin\theta\,|\,Z\rangle\}\,|\uparrow\rangle + \sqrt{\frac{2}{3}}\left\{\sin\theta\cos\phi\,|\,X\rangle + \sin\theta\sin\phi\,|\,Y\rangle + \cos\theta\,|\,Z\rangle\right\}|\downarrow\rangle \tag{21.14}$$

21.3.2 Theory of Light Emission

Photon is emitted when an electron in the higher energy state transfers to the lower state. The transition probability can be given by the Fermi Golden rule,

$$W = \frac{2\pi}{\hbar}\sum_{\lambda}\sum_{f,i}|\langle f\,|\,H'\,|i\rangle|^2\;\delta(E_{f\lambda} - E_{i\lambda}). \tag{21.15}$$

Here, H' is the perturbation term due to the interaction between electron and photon appearing in the Hamiltonian, and is expressed as $H' = -(e/m)\boldsymbol{A}\cdot\boldsymbol{p}$ using a vector potential $\boldsymbol{A}$ and momentum $\boldsymbol{p}$. The wavefunctions of the initial and final states are denoted by $|i\rangle$ and $|f\rangle$, which are given by a product of wavefunctions of electron and photon. The summation over λ in (21.15) is taken over modes of photons. Substituting the above expression for the perturbation term, (21.15) can be rewritten as

$$W = \frac{2\pi}{\hbar}\sum_{\lambda}\sum_{f,i}\left(\frac{eA_0}{m}\right)^2 |\langle\psi_f|(\boldsymbol{e}\cdot\boldsymbol{p})e^{-i\boldsymbol{K}\cdot\boldsymbol{r}}|\psi_i\rangle|^2 \times (n_\lambda + 1)\delta(E_i - E_f - \hbar\omega). \tag{21.16}$$

where $\boldsymbol{K}$ is a wavevector of photon. The first term in $(n_\lambda + 1)$ expresses the stimulated emission and the second term expresses the spontaneous emission. In the following, we are only concerned with the spontaneous emission.

The rate of the spontaneous emission at a frequency ω in the transition from electron state in the conduction band to the hole state in the valence band is given by

$$R(\omega) = \frac{2\pi}{\hbar}\left(\frac{eA_0}{m}\right)^2\sum_{c,v}|M|^2 G(\hbar\omega) f_c(E_c)\left[1 - f_v(E_v)\right]\delta(E_c - E_v - \hbar\omega). \tag{21.17}$$

The summation over the photon modes is replaced by the optical density of states G, which is derived from the van Roosbroeck–Shockly relation as

$$G(\hbar\omega) = \frac{n^3}{\pi^2 c^3 \hbar^3}(\hbar\omega)^2, \tag{21.18}$$

where n is the refractive index of the material. $f_c(E_c)$ and $f_v(E_v)$ are Fermi distribution functions. It is noted that we should use the pseudo-Fermi energy instead of the equilibrium one, when carriers are excited by outer sources. The product of $f_c(1 - f_v)$ in (21.17) produces a sharp peak near the band gap energy ($E_c - E_v$) in luminescence spectra. This is clear difference from the absorption spectrum which shows multiple peaks due to $|M(\omega)|^2$ above the band gap energy.

The term M is an optical transition matrix element, giving emission intensity of the transition, and is written as

$$M = \langle \psi_v | e^{-i\boldsymbol{K}\cdot\boldsymbol{r}} (\boldsymbol{e}\cdot\boldsymbol{p}) | \psi_c \rangle \tag{21.19}$$

where $\boldsymbol{e}$ is a unit vector parallel to the electric field of light, i.e., the polarization direction. Using the momentum operator $\boldsymbol{p} = -i\hbar\nabla$ and wavefunctions of the conduction and valence bands, (21.19) can be rewritten as

$$M = -i\frac{\hbar}{V}\left[\int e^{i(\boldsymbol{k}_c-\boldsymbol{K}-\boldsymbol{k}_v)\cdot\mathbf{r}} \left\{ u_v^*(\boldsymbol{e}\cdot\nabla u_c) + i\,\boldsymbol{e}\cdot\boldsymbol{k}_c\, u_v^*\, u_c \right\} \mathrm{d}\mathbf{r}\right] \tag{21.20}$$

The second term is zero because of orthogonality of the wavefunctions. The following equation is valid for any periodic function of the lattice translation, $f(\boldsymbol{r}) = f(\boldsymbol{r} + \boldsymbol{R}_n)$,

$$\int f(\boldsymbol{r}) e^{i(\boldsymbol{k}_c-\boldsymbol{K}-\boldsymbol{k}_v)\cdot\boldsymbol{r}}\,\mathrm{d}\boldsymbol{r} = \sum_n e^{i(\boldsymbol{k}_c-\boldsymbol{K}-\boldsymbol{k}_v)\cdot\boldsymbol{R}_n} \times \int_{Vc} f(\boldsymbol{r}) e^{i(\boldsymbol{k}_c-\boldsymbol{K}-\boldsymbol{k}_v)\cdot\boldsymbol{r}}\,\mathrm{d}\boldsymbol{r} \propto \delta(\boldsymbol{k}_c - \boldsymbol{K} - \boldsymbol{k}_v) \tag{21.21}$$

Using this, the integral in (21.20) is found to be non-zero only when $\boldsymbol{k}_c = \boldsymbol{k}_v + \boldsymbol{K}$, indicating the conservation of wavevector in the transition. The wavelength of light with band gap energy is relatively long, i.e., $\boldsymbol{K} \ll \boldsymbol{k}_c, \boldsymbol{k}_v$ so we may approximate as $\boldsymbol{k}_c \approx \boldsymbol{k}_v$. As a result we obtain

$$M = \langle u_v | \boldsymbol{e}\cdot\boldsymbol{p} | u_c \rangle \delta_{\boldsymbol{k}_v,\boldsymbol{k}_c} \tag{21.22}$$

Here the condition $\boldsymbol{k}_c \approx \boldsymbol{k}_v$ indicates the "vertical" interband transition.

21.3.3 Polarization

The vector $\boldsymbol{e}$ in the optical transition matrix element indicates polarization direction of the electric field of light. Thus, the polarization in luminescence derives from the property of the matrix element. Here we consider

$$\langle u_v | \boldsymbol{p} | u_c \rangle$$

as a momentum vector. The vector $\boldsymbol{p}$ reflects the polarization of the emitted light; when $\boldsymbol{e}$ is perpendicular to $\boldsymbol{p}$, M is zero, which means that the polarization component perpendicular to $\boldsymbol{p}$ is zero. In other words, the x component of the electric field, E_x, is proportional to $\langle u_v | p_x | u_c \rangle$. From symmetry, only the following matrix elements of

$$\langle X | p_x | s \rangle = \langle Y | p_y | s \rangle = \langle Z | p_z | s \rangle = -i\frac{\hbar}{m}P = p_{cv} \tag{21.23}$$

are non-zero, where P is the factor introduced by Kane (1957).

For example, in the transition from the electron state of $|s\uparrow\rangle$ in the conduction band to the heavy hole state, the matrix elements can be written as

$$\begin{aligned} \left\langle \frac{3}{2},\frac{3}{2} \middle| p_x \middle| s\uparrow \right\rangle &= -\frac{1}{\sqrt{2}}\langle X | p_x | s \rangle = -\frac{1}{\sqrt{2}} p_{cv} \\ \left\langle \frac{3}{2},\frac{3}{2} \middle| p_y \middle| s\uparrow \right\rangle &= -\frac{i}{\sqrt{2}}\langle Y | p_y | s \rangle = -\frac{i}{\sqrt{2}} p_{cv} \\ \left\langle \frac{3}{2},\frac{3}{2} \middle| p_z \middle| s\uparrow \right\rangle &= 0 \end{aligned} \tag{21.24}$$

From these, the relation among the electric field components can be written as

$$\frac{E_y}{E_x} = e^{i\frac{\pi}{2}}, \quad E_z = 0 \tag{21.25}$$

This means that the light emitted toward the z direction has a right-handed circular polarization. This situation is illustrated in Figure 21.7, where we express $|X\rangle$ and $|Y\rangle$ in terms of pure angular momentum states. The wavevector $\boldsymbol{k}_h$ of the heavy hole is pointing to the z direction. The wavefunction of the heavy hole is extended parallel to the x-y plane, and its momentum vector $\boldsymbol{p}$ rotates on the same plane. The wavevector $\boldsymbol{k}_e$ of the electron in the conduction band is parallel to the z-axis, and the wavefunction has a spherical symmetry. In this recombination process of the electron and heavy hole, the angular momentum of the heavy hole is preserved as that of the circular polarized light.



FIGURE 21.7 Wavefunctions of the electron in the conduction band and the heavy hole in the valence band. Circularly polarized and linearly polarized light are emitted by the optical transition between them.

Similarly in the transition from the electron state $|s\uparrow\rangle$ in the conduction band to the light hole state $\left|\frac{3}{2},-\frac{1}{2}\right\rangle$, the matrix elements can be written as

$$\begin{aligned}
&\left\langle\frac{3}{2},-\frac{1}{2}\right|p_x\left|s\uparrow\right\rangle=\frac{1}{\sqrt{6}}\left\langle X\right|p_x\left|s\right\rangle=\frac{1}{\sqrt{6}}p_{cv}\\
&\left\langle\frac{3}{2},-\frac{1}{2}\right|p_y\left|s\uparrow\right\rangle=-\frac{i}{\sqrt{6}}\left\langle Y\right|p_y\left|s\right\rangle=-\frac{i}{\sqrt{6}}p_{cv}\\
&\left\langle\frac{3}{2},-\frac{1}{2}\right|p_z\left|s\uparrow\right\rangle=0
\end{aligned}\tag{21.26}$$

Then, light with a left-handed circular polarization is emitted. Whereas in the transition from the electron state $|s\downarrow\rangle$ to the light hole state $\left|\frac{3}{2},-\frac{1}{2}\right\rangle$, the matrix elements are written as

$$\begin{aligned}
&\left\langle\frac{3}{2},-\frac{1}{2}\right|p_x\left|s\downarrow\right\rangle=0\\
&\left\langle\frac{3}{2},-\frac{1}{2}\right|p_y\left|s\downarrow\right\rangle=0\\
&\left\langle\frac{3}{2},-\frac{1}{2}\right|p_z\left|s\downarrow\right\rangle=\sqrt{\frac{2}{3}}\left\langle Z\right|p_z\left|s\right\rangle=\sqrt{\frac{2}{3}}p_{cv}
\end{aligned}\tag{21.27}$$

In this case, light is linearly polarized parallel to the z-axis.

The emission intensity of CL is proportional to a mean square of the electric field vector. Therefore, in the transition from $|s\uparrow\rangle$ in the conduction band to the heavy hole state in the valence band, the emission intensity of light polarized in each direction is expressed as

$$I_x\propto\frac{1}{2}p_{cv}^2,\quad I_y\propto\frac{1}{2}p_{cv}^2,\quad I_z\propto 0\tag{21.28}$$

Similarly in the transition from $|s\uparrow\rangle$ in conduction band to the light hole state $\left|\frac{3}{2},-\frac{1}{2}\right\rangle$ in the valence band,

$$I_x\propto\frac{1}{6}p_{cv}^2,\quad I_y\propto\frac{1}{6}p_{cv}^2,\quad I_z\propto 0\tag{21.29}$$

And in the transition from $|s\downarrow\rangle$ in the conduction band to the light hole state $\left|\frac{3}{2},-\frac{1}{2}\right\rangle$ in the valence band,

$$I_x\propto 0,\quad I_y\propto 0,\quad I_z\propto\frac{2}{3}p_{cv}^2\tag{21.30}$$

The relative intensity and polarization of the emission associated with the transition between the conduction band and the valence band states are schematically depicted in Figure 21.8.



FIGURE 21.8 Relative intensity and polarization of the emission associated with the transition between the conduction band and the valence band states.

The semiconductors of zinc-blend structure are crystallographically isotropic, and any direction can be taken as the z-axis. Thus, the luminescence from the bulk crystal is not polarized, because the polarization of each recombination process cancels out as a whole. Typical cases in which polarized emission occurs are luminescence from quantum structures and that from semiconductors of wurtzite structure. In the case of quantum well structures, a unique axis appears normal to the well, and the heavy and light hole states have anisotropic distribution which causes dissociation of the band degeneration (Yu and Cardona, 1999). Similarly in semiconductors of wurtzite structure, the c-axis is a unique axis, and the bands of the heavy and light hole states are dissolved into the A and B bands. If the highest energy state in the valence band is heavy hole as in the case of GaN, the optical transition to the heavy hole state mainly occurs, and the luminescence is polarized perpendicular to the c-axis. In addition, the polarization property of luminescence changes by a strain field in semiconductor crystals, because a lattice strain causes an anisotropic deformation potential and reconstructs the band structure (Hensel and Feher, 1963; Pollak and Cardona, 1968).

21.4 Quantum Structures

When carriers are confined in small-scaled semiconductor structures, carrier wavefunctions form standing waves and start to show quantum character. The wavelength and wave number of a carrier in a one-dimensional potential well of an infinite height with a width of L are given as

$$\lambda=\frac{2L}{n},\quad k=\frac{n\pi}{L}\tag{21.31}$$

where n is an integer number. The wave number k can only take discrete values in this direction corresponding to n = 1, 2, 3, …, and has continuous value in the other direction. Kinetic energy in this direction takes discrete values given by

$$\Delta E = \frac{\hbar^2}{2m}k^2 = \frac{\hbar^2}{2m}\left(\frac{n\pi}{L}\right)^2 \tag{21.32}$$

This anisotropy in k gives rise to anisotropy in optical transition and polarization of luminescence. In the following section, we start with a quantum well structure because of simplicity in theoretical treatment and next move to a quantum wire structure which shows strong polarization property.

21.4.1 Quantum Well

We consider carriers confined in a thin semiconductor plate of a width L_z in the z direction. The wavefunction of electrons in the conduction band and holes in the valence band are expressed using the Bloch function $u_{c,v}(\boldsymbol{r})$ at $\boldsymbol{k} = 0$ under the effective mass approximation as

$$\Psi^e(\boldsymbol{r}) = \frac{1}{\sqrt{V}}\sin\left(\frac{n_c\pi}{L_z}z\right)e^{i(k_x x + k_y y)}\,u_c(\boldsymbol{r}) = \phi_e(z)e^{i(k_x x + k_y y)}\,u_c(\boldsymbol{r}) \tag{21.33}$$

$$\Psi^v(\boldsymbol{r}) = \frac{1}{\sqrt{V}}\sin\left(\frac{n_v\pi}{L_z}z\right)e^{i(k_x x + k_y y)}\,u_v(\boldsymbol{r}) = \phi_h(z)e^{i(k_x x + k_y y)}\,u_v(\boldsymbol{r}) \tag{21.34}$$

where ϕ_e and ϕ_h are envelop functions of the electron and hole, respectively, showing standing waves in the confined direction. The energy of the electron and hole measured from the top of the valence band are given by

$$E_e(n) = \frac{\hbar^2}{2m_e}\left(\frac{n_c\pi}{L_z}\right)^2 + \frac{\hbar^2}{2m_e}(k_x^2 + k_y^2) + E_g \tag{21.35}$$

$$E_h(n) = \frac{\hbar^2}{2m_h}\left(\frac{n_v\pi}{L_z}\right)^2 + \frac{\hbar^2}{2m_h}(k_x^2 + k_y^2) \tag{21.36}$$

where

m_e and m_h are the effective mass of electron and hole, respectively

n_c and n_v are their quantum numbers

Since wavevector components, k_x and k_y, take continuous values, mini bands are formed for each quantum number, as shown in Figure 21.9. It should be noted that (21.36) is a rough approximation because the band mixing should be considered for the valence band in the quantum structure, as shown in Figure 21.9. However, this gives a simple picture for the band splitting in the valence band. In the quantum well structure, the degenerated bands at the Γ point are dissolved, and the highest energy state is the heavy hole. Consequently, the transition from the electron state to the heavy hole state becomes dominant. Since the energy shift of the valence band is relatively small compared to that of the conduction band, the emission energy is roughly estimated from (21.35) and (21.36).



FIGURE 21.9 Wave functions, band structure, and density of states in a quantum well.

The probability of interband transition from the conduction band to the heavy hole state at the band edge (BE) is given by the following matrix element,

$$M = \langle\Psi^v|\boldsymbol{e}\cdot\boldsymbol{p}|\Psi^c\rangle = \langle\phi_h(z)|\phi_e(z)\rangle\left\langle u_{\frac{3}{2},\frac{3}{2}}\middle|\boldsymbol{e}\cdot\boldsymbol{p}\middle|u_c\right\rangle \tag{21.37}$$

The product of the electron and hole envelop functions is non-zero only when

$$n_c = n_v \tag{21.38}$$

If M is zero, the corresponding transition is inhibited. This gives the selection rule of the transition, and means that the optical interband transition only occurs between the electron and hole states of the same quantum number. The emission energy is given by

$$E(n) = E_e(n) - E_h(n) = \frac{\hbar^2}{2\mu}\left(\frac{n_c\pi}{L_z}\right)^2 + \frac{\hbar^2}{2\mu}(k_x^2 + k_y^2) + E_g \tag{21.39}$$

where μ is the reduced effective mass. The lowest energy transition occurs for $n_c = n_v = n = 1$. However, if the barrier height is finite, other transitions become permitted.

The polarization of emission from the quantum well is deduced from (21.37). Here we take the z-axis normal to the well. In the transition between the lowest mini bands at the BE, the wavevector of carrier is $\boldsymbol{k}_c = \boldsymbol{k}_v = (0, 0, \pi/L_z)$, which points to the z direction. Therefore, the result of (21.24) can be applied for this case, so the emission toward the z direction is a right-handed circular polarized light. Whereas light emitted along the well is linearly polarized parallel to the well.

In the interband transition between the electronic states with a finite $k_\perp$ component normal to the z-axis, the wavevector of the carriers is inclined from the z-axis, and the wavefunction of the valence band changes according to (21.13). The emission energy increases according to (21.39). In order to find the polarization of emitted light with this energy, the transition matrix element should be integrated over equivalent transitions of the same energy. Firstly we consider the transition from the $|s\uparrow\rangle$ state in the conduction band to the heavy hole state in the valence band. The wavevector component parallel to the z-axis is π/L_z, and then $\boldsymbol{k} = (k\sin\theta\cos\phi,\ k\sin\theta\sin\phi,\ \pi/L_z)$. The wavefunction of the heavy hole is expressed by (21.13). The x and y directions are equivalent, so here we consider the emission propagating in the x direction with the electric field parallel to the y direction (TE wave in Figure 21.10). After integrating over the azimuth angle ϕ, the averaged transition matrix element is given as

$$\begin{aligned}\langle |M|^2\rangle_{hh,TE} &= \frac{1}{2\pi}\int_0^{2\pi}\left|\left\langle \frac{3}{2},\frac{3}{2}\right|p_y\left|s\right\rangle\right|^2 d\phi \\ &= \frac{1}{2}\cdot\frac{1}{2\pi}\int_0^{2\pi}(\cos^2\theta\sin^2\phi+\cos^2\phi)\,d\phi = \frac{1}{4}p_{cv}^2(1+\cos^2\theta)\end{aligned} \tag{21.40}$$

Similarly for the electric field parallel to the z direction (TM wave), the averaged transition matrix element is given as

$$\begin{aligned}\langle |M|^2\rangle_{hh,TM} &= \frac{1}{2\pi}\int_0^{2\pi}\left|\left\langle \frac{3}{2},\frac{3}{2}\right|p_z\left|s\right\rangle\right|^2 d\phi \\ &= \frac{1}{2}\cdot\frac{1}{2\pi}\int_0^{2\pi}\sin^2\theta\,d\phi = \frac{1}{2}p_{cv}{}^2\sin^2\theta\end{aligned} \tag{21.41}$$



FIGURE 21.10 Wavevectors of the same energy states in the miniband. Light emission of both the TM mode and TE mode occurs from a quantum well.

If the $k_\perp$ component is zero ($k_x = k_y = 0$), i.e., $\theta = 0$ at the mini-BE, the TM component is zero and the polarization of the emission is parallel to the well. As the tilted angle θ from the z-axis increases, the emission energy increases with increasing $\boldsymbol{k}$ and the polarization direction tilts from the well plane.

21.4.2 Quantum Wire

21.4.2.1 Energy Levels in Quantum Wire

A semiconductor quantum wire of an infinite length along the z-axis with a rectangular cross section of the widths of L_x and L_y confines a carrier in an infinite barrier height. Electron wavefunction in the quantum nanowire is expressed in the effective mass approximation by a product of the Bloch function at the BE and the envelop function in the x-y plane normal to the wire axis. For simplicity we consider the electron state at the BE of the conduction band in semiconductors with a cubic symmetry and a direct band structure. The electron wavefunction is expressed as

$$\Psi^e(\boldsymbol{r}) = \phi^c(x,y)e^{ik_z z}u_c(\boldsymbol{r}) \tag{21.42}$$

The envelop function of the electron is written as

$$\phi^c(x,y) = \frac{1}{\sqrt{L_xL_y}}\sin\left(\frac{\pi n_c}{L_x}x\right)\sin\left(\frac{\pi m_c}{L_y}y\right) \tag{21.43}$$

where n_c and m_c are integer. The energy of the electron in the (n_c, m_c) band is given by

$$E_e(n_c,m_c) = \frac{\hbar^2}{2m_e}\left\{\left(\frac{\pi n_c}{L_x}\right)^2+\left(\frac{\pi m_c}{L_y}\right)^2\right\}+\frac{\hbar^2}{2m_e}k_z^2+E_g \tag{21.44}$$

where m_e is the electron effective mass. The lowest energy band corresponds to the quantum numbers of $n_c = m_c = 1$. Mini bands are formed from (21.44) in the conduction band, as shown in Figure 21.11. The density of states as a function of energy has sharp peaks at the mini-BE given by the first term, and shows a sawtooth shape.



FIGURE 21.11 Wave functions, band structure, and density of states in a quantum wire with a square cross section.

On the other hand, electrons in a quantum wire with a circular cross section of radius R has the following envelop functions expressed using the cylindrical coordinates (ρ, ϕ) as

$$\phi_e(\rho,\phi) \propto J_\ell\left(\frac{j_{n\ell}\rho}{R}\right)\cos(\ell\phi) \quad \text{or} \quad J_\ell\left(\frac{j_{n\ell}\rho}{R}\right)\sin(\ell\phi) \tag{21.45}$$

where

J_l is the Bessel function of the ℓth order

$j_{l,n}$ is the 0 point value of nth order given by the condition that $J_l(j_{l,n}) = 0$

The lowest values are given as $j_{0,1} = 2.405$, $j_{1,1} = 3.832$, and $j_{0,2} = 5.520$. A set of energy levels are derived as

$$E_e(\ell,n) = \frac{\hbar^2 j_{\ell,n}{}^2}{2m_eR^2} + \frac{\hbar^2}{2m_e}k_z{}^2 + E_g \tag{21.46}$$

All the energy states indicated by the quantum number (ℓ, n) are doubly degenerated, except for $\ell = 0$.

Change in electron energy levels in the conduction band due to the quantum confinement effect is large, whereas those of holes in the valence band are relatively small because of small curvature of the bands or large effective mass of hole. However, the band mixing occurs, and then the hole wavefunctions are formed by a mixture of the bulk wavefunctions in (21.11). This affects the property of the optical transitions. The hole wavefunctions are expressed by a linear combination of the bulk wavefunctions as

$$\Psi^v(\boldsymbol{r}) = e^{ik_z z}\sum_j \phi_j^v(x,y)u_j(\boldsymbol{r}) \quad \left(j=\frac{3}{2},\frac{1}{2},-\frac{1}{2},-\frac{3}{2}\right) \tag{21.47}$$

The envelop functions are written as

$$\phi_j^v(x,y) = \frac{1}{\sqrt{L_xL_y}}\sum_{n_v,m_v} c_j(n_v,m_v)\sin\left(\frac{\pi n_v}{L_x}x\right)\sin\left(\frac{\pi m_v}{L_y}y\right) \tag{21.48}$$

Here, we ignore the contribution of the split-off band to the mixing. The wavefunctions and energies in the valence band of the quantum wire can be derived from the theoretical calculation using the Luttinger–Kohn Hamiltonian in the effective mass approximation (Sercel and Vahala, 1990; Bockelmann and Bastard, 1992; McIntyre and Sham, 1992).

Theoretical treatments were firstly applied to the quantum wires manufactured from the quantum well structures, in which the wire has an axis parallel to the growth surface and rectangular shape in cross section (Tanaka and Sakaki, 1989; Tsuchiya et al., 1989). Because of the technological development for the fabrication of self-standing nanowire, energy band calculations have been done for self-standing wires with circular and rectangular cross sections of Si (Zhao et al., 2004), GaAs (Persson and Xu, 2004, Redlinski and Peeters, 2008), and InP (Pellegrini et al., 2005). The band dispersion of camel back structure appears in some of the high energy bands of the valence band. The character of the band structure such as the sequence of the levels does not change with the diameter of the quantum wire. The highest energy band in the valence band has a character of the light hole, and the second highest energy band has a character of the heavy hole. The difference in band structure between the nanowires grown in the [100] and [111] directions was shown in the GaAs nanowires (Redlinski and Peeters, 2008).

The luminescence due to exciton is generally dominant at low temperatures. The emission energy of the FX is given by the band gap energy minus the exciton binding energy as in (21.6). If the carrier confinement in quantum wires is perfect, the exciton binding energy becomes infinite in the limit of small wire size (Basu, 1997). A real nanowire has a finite size in diameter, the divergence can be avoided using a following potential for the Coulomb interaction between the electron-hole pair (Ando et al., 1991),

$$V(z,z_0) = -\frac{e^2}{4\pi\varepsilon}\frac{1}{\left(|z|+z_0\right)} \tag{21.49}$$

where z_0 is a parameter for the size effect of nanowire. Quantum confinement effect is large enough to be detected, when the diameter of the wire becomes comparable to or less than the exciton radius. The size dependence of the emission energy is approximately proportional to R^{-2}, as in (21.46). The theoretical calculations, including other effects, have been carried out for the size dependence of the emission energy; for example, the dielectric mismatch effect results in the $R^{-1.8}$ dependence (Redlinski and Peeters, 2008).

The barrier height of the carrier confinement is finite in real when a quantum wire is surrounded by another semiconductor or even by air. In such cases, the energy levels decrease from those given by (21.44) and (21.46), and the distances between the energy levels decrease, because they must exist below the barrier height level. When the diameter of wire decreases with the barrier height fixed, the energy levels move upward to gather near the barrier height level, and their total number decreases. However, at least one level is left at the barrier height in the symmetrical potential well in the limit of small size.

21.4.2.2 Luminescence from Quantum Wire

Luminescence from bulk crystals with cubic symmetry such as Si and GaAs is generally unpolarized, whereas that with hexagonal symmetry such as GaN and ZnO shows anisotropy in polarization because the *c*-axis is a unique axis. The luminescence from nanowires has been frequently observed to be polarized even for semiconductors with cubic symmetry. There are two reasons for the appearance of the polarization anisotropy in luminescence from nanowire; one is the anisotropy originated from the quantum effect, and another is the anisotropic response of nanowire to the electromagnetic fields parallel or perpendicular to the wire axis (Ruda and Shik, 2005, 2006).

The former effect appears when a diameter of nanowire becomes smaller than the exciton radius, which gives rise to the polarization anisotropy in the luminescence of excitons in the nanowire. The latter effect appears even in nanowires with diameter larger than the exciton radius.

21.4.2.2.1 Quantum Confinement Effect

The quantum confinement of carriers in thin nanowires affect on the polarization of luminescence. Here we treat a nanowire of a square cross section with a dimension of *a* and an infinite length. The wire is isotropic in the cross-sectional plane and the confinement potential has an infinite barrier height for carriers in the wire. At first we ignore the band mixing in the valence band, and use the wavefunctions of the one-band model expressed as follows:

$$\Psi^v(\boldsymbol{r}) = e^{ik_z z}\phi_j^v(x, y)u_j(\boldsymbol{r}) \tag{21.50}$$

When we take the heavy hole state for *j*, the transition matrix element is written as

$$M = \langle\psi_v|e^{-i\boldsymbol{K}\cdot\boldsymbol{r}}(\boldsymbol{e}\cdot\boldsymbol{p})|\psi_c\rangle = \sum_{k_i}\langle\phi_j^v|\phi_e\rangle\langle u_j(\boldsymbol{k}_i)|\boldsymbol{e}\cdot\boldsymbol{p}|u_c\rangle \tag{21.51}$$

Electron wavefunctions of the lowest energy states in the conduction band are expressed by (21.42) and (21.43) with $n_c = m_c = \pm1$. The transition occurs under the selection rule of $n_c = n_v$ and $m_c = m_v$ in (21.43) and (21.48). There are four corresponding heavy hole states of the same energy at the BE ($k_z = 0$), having the following wavevectors:

$$\boldsymbol{k_i} = \left(\pm\frac{\pi}{a}, \pm\frac{\pi}{a}, 0\right) : i = 1 \sim 4 \tag{21.52}$$

The wavefunctions of the heavy hole states with these wavevectors are given by substituting θ = 90° in (21.13) as

$$\left|\frac{3}{2},\frac{3}{2}\right\rangle_{k_i} = -\frac{1}{\sqrt{2}}\left\{-i\sin\phi_i\left|X\right\rangle + i\cos\phi_i\left|Y\right\rangle - \left|Z\right\rangle\right\}\left|\uparrow\right\rangle \tag{21.53}$$

Four azimuth angles of

$$\phi_1 = \frac{\pi}{4},\quad \phi_2 = \frac{3\pi}{4},\quad \phi_3 = \frac{5\pi}{4},\quad \phi_4 = \frac{7\pi}{4} \tag{21.54}$$

correspond to the four wavevectors. Similarly, the wavefunctions of the light hole states with the same wavevectors are written as

$$\left|\frac{3}{2},-\frac{1}{2}\right\rangle = \frac{1}{\sqrt{6}}\left\{i\sin\phi_i\left|X\right\rangle - i\cos\phi_i\left|Y\right\rangle - \left|Z\right\rangle\right\}\left|\uparrow\right\rangle + \sqrt{\frac{2}{3}}\left\{\cos\phi_i\left|X\right\rangle + \sin\phi_i\left|Y\right\rangle\right\}\left|\downarrow\right\rangle \tag{21.55}$$

If the transitions from the conduction band to those valence band states are assumed to occur independently, mean square of the transition matrix element is given as

$$|M|^2_{e-hh} = \frac{1}{4}\sum_{k_i}\left|\left\langle u_{\frac{3}{2},\frac{3}{2}}(\boldsymbol{k}_i)\middle|\boldsymbol{e}\cdot\boldsymbol{p}\middle|s\uparrow\right\rangle\right|^2 \tag{21.56}$$

Here, the term from $|s\downarrow\rangle$ to $\left|u_{\frac{3}{2},-\frac{3}{2}}(\boldsymbol{k}_i)\right\rangle$ is ignored, because it gives the same value as above. If we take the *z* direction along the wire axis, it follows that $\boldsymbol{e}\cdot\boldsymbol{p} = p_z$ for the polarization of emitted light parallel to the wire axis and $\boldsymbol{e}\cdot\boldsymbol{p} = p_x$ for that normal to the wire axis. Then the square of the transition matrix element is calculated using (21.52), and the two components parallel and perpendicular to the *z*-axis are obtained as

$$|M|^2_{e-hh\parallel} = \frac{1}{2}p_{ev}^2,\quad |M|^2_{e-hh\perp} = \frac{1}{4}p_{ev}^2 \tag{21.57}$$

The component parallel to the wire axis is larger than the perpendicular one because the transformed wavefunction in (21.52) involves a large $|Z\rangle$ component. When the polarization of light is inclined from the wire axis by an angle θ (Figure 21.12), the square of the transition matrix element can be written as

$$|M|^2_{e-hh} = \frac{1}{2}p_{ev}^2\cos^2\theta + \frac{1}{4}p_{ev}^2\sin^2\theta \tag{21.58}$$

The transition matrix element from the conduction band to the light hole state is calculated in the same way using (21.54),

$$|M|^2_{e-\ell h} = \frac{1}{6}p_{ev}^2\cos^2\theta + \frac{5}{12}p_{ev}^2\sin^2\theta \tag{21.59}$$

In this transition, the component perpendicular to the wire axis is larger than the parallel one. The two hole states locate at different energy levels, so the emission energy of this transition is



FIGURE 21.12 Light emissions from a nanowire polarized in directions inclined from the wire axis by angles of θ = 0° and 90°.

also different. If we use the relation $p_{cv}^2 = 3M^2$ in which M is the averaged value in the isotropic bulk crystal, the ratio between these transition matrix elements can be written as

$$\frac{|M|^2_{e-\ell h}}{|M|^2_{e-hh}} = \frac{\frac{1}{2}\cos^2\theta + \frac{5}{4}\sin^2\theta}{\frac{3}{2}\cos^2\theta + \frac{3}{4}\sin^2\theta} \tag{21.60}$$

This result was derived by several authors on the basis of the one-band model (Tanaka and Sakaki, 1989; Tsuchiya et al., 1989), though this treatment was claimed to be too simple, and later more reliable one was proposed on the basis of band mixing in the valence band.

In the photoluminescence excitation (PLE) spectrum of the quantum wires formed in the GaAs quantum well structure, two peaks were observed to appear near the BE energy, as shown in Figure 21.13 (Tsuchiya et al., 1989). On the other hand in the PL spectrum, only the lower energy peak appeared. The lower energy peak was assigned to be due to the transition to the heavy hole state, and the higher peak due to the transition to the light hole state, respectively. It appeared to be consistent with the result of (21.57). However, it was suggested that the one-band model cannot explain the polarization property correctly, and the theoretical treatment taking account of the band mixing in the valence band should be necessary. Sercel and Vahala (1990) showed that if the coherent combination of the hole states with the four wavevectors is considered in the one-band model, Equation 21.57 has a constant value (=1/3) independent of θ. They calculated the polarization dependence of the optical transition using the mixed states of the heavy and light holes in a cylindrical wire. As a result, the transition matrix elements associated with the two highest hole states were obtained as

$$|M|^2_{C-V\left(\frac{1}{2}\right)} = \left(\frac{2}{3}\cos^2\theta + \frac{1}{6}\sin^2\theta\right) p_{ev}^2 I^2_{C-V\left(\frac{1}{2}\right)} \tag{21.61}$$

$$|M|^2_{C-V\left(\frac{3}{2}\right)} = \frac{1}{2}\sin^2\theta \cdot p_{ev}^2\, I^2_{C-V\left(\frac{3}{2}\right)} \tag{21.62}$$

where I is an overlap integral. The optical transition of the lowest energy is C–V(1/2). The V(1/2) state involves only 41% of the heavy hole state. The single peak in the PL spectrum is due to this transition. The polarization component parallel to the wire axis is dominant in the emission, and the polarization ratio deduced from (21.60) is 60%. The polarization ratio becomes smaller as the barrier height decreases. The optical transition of the next lowest energy is C–V(3/2), and the V(3/2) state involves 67% of the heavy hole state. The polarization direction of the corresponding emission is perpendicular to the wire axis. The property of the polarization in these two transitions is well consistent with those of the two emission peaks in the PLE spectrum in Figure 21.13.



FIGURE 21.13 Photoluminescence (PL) and photoluminescence excitation (PLE) spectra of the quantum wires formed in the GaAs quantum well structure. (From Tsuchiya, M. et al., *Phys. Rev.*, 62, 455, 1989. With permission.)

Similar results were obtained in the calculation of optical absorption for self-standing GaAs nanowires (Redlinski and Peeters, 2008). The highest energy state in the valence band has a character of the light hole. The optical transition matrix element associated with this hole state has both polarization components parallel and perpendicular to the wire axis, and the former is much larger than the latter. The fine splitting of the lowest energy peak in the absorption spectrum appears in the [111] wire because of the anisotropy in the cross-sectional plane. The next highest energy state in the valence band has a character of the heavy hole, and the absorption occurs only for the polarization direction perpendicular to the wire axis. Emission energies in these two transitions are slightly different, so in PL and CL, the transition to the band having the light hole character is predominant.

21.4.2.2.2 Dielectric Effect

The second factor to affect the polarization of luminescence from semiconductor nanowires is the dielectric effect (Ruda and Shik, 2005). When a spatially homogeneous electric field is applied to a nanowire of cylindrical shape with the electric field vector parallel to the wire axis, magnitude and direction are the same both in and outside of the wire. Whereas the electric field is applied perpendicular to the wire axis, its magnitude is reduced by a factor of $(2\varepsilon_0/\varepsilon + \varepsilon_0)$, where ε and ε_0 are relative dielectric constants of semiconductor and surrounding material, respectively (Landau et al., 1984), i.e.,

$$\begin{aligned} E_{\parallel} &= E_{0\parallel} \\ E_{\perp} &= \frac{2\varepsilon_0}{\varepsilon + \varepsilon_0} E_{0\perp} \end{aligned} \tag{21.63}$$

This is true for the oscillating electric field of light if the diameter of the wire is sufficiently smaller than the wavelength of light. From this, the polarization dependence of the optical absorption is expressed by

$$\frac{k_{\parallel}}{k_{\perp}} = \left|\frac{\varepsilon+\varepsilon_0}{2\varepsilon_0}\right|^2 \tag{21.64}$$

This anisotropy appears in PL and light-induced current excited by polarized light.

As for the dielectric effect on the polarization of luminescence, we consider an oscillating electric dipole with a frequency of ω and a dipole moment of $\boldsymbol{d}_0 = (d_{0x}, d_{0y}, d_{0z})$ in a cylindrical nanowire. We take the z-axis parallel to the wire axis and the x-axis parallel to the propagating direction of emitted light which is normal to the wire axis. Here we consider an effective dipole moment $\boldsymbol{d} = (d_x, d_y, d_z)$ of which the electric potential in a free space is equivalent to that produced by $\boldsymbol{d}_0$ outside the nanowire. The relation between $\boldsymbol{d}$ and $\boldsymbol{d}_0$ can be written as

$$d_{x,y} = \frac{2\varepsilon_0}{\varepsilon+\varepsilon_0} d_{0x,y}, \quad d_z = d_{0z} \tag{21.65}$$

The magnitude of the pointing vector of light at the position far from the center of wire by x_0 is given by

$$\begin{aligned} S_{\parallel} &= \frac{a\omega^4}{6\pi\varepsilon_0^2 c^3 x_0}(d_x^2 + 2d_z^2) \\ S_{\perp} &= \frac{a\omega^4}{2\pi\varepsilon_0^2 c^3 x_0} d_y^2 \end{aligned} \tag{21.66}$$

for the components parallel and perpendicular to the wire axis, respectively. Here, c is the speed of light and a is a radius of the wire. Therefore, when the semiconductor is isotropic and $d_{0x} = d_{0y} = d_{0z}$, the ratio of intensity between the emissions polarized parallel and perpendicular to the wire axis is given as

$$\frac{I_{\parallel}}{I_{\perp}} = \frac{S_{\parallel}}{S_{\perp}} = \frac{d_x^2 + 2d_z^2}{3d_x^2} = \frac{(\varepsilon+\varepsilon_0)^2 + 2\varepsilon_0^2}{6{\varepsilon_0}^2} \tag{21.67}$$

The polarization ratio is given by

$$P = \frac{I_{\parallel} - I_{\perp}}{I_{\parallel} + I_{\perp}} = \frac{(\varepsilon+\varepsilon_0)^2 - 4\varepsilon_0^2}{(\varepsilon+\varepsilon_0)^2 + 8\varepsilon_0^2} \tag{21.68}$$

This indicates that P does not depend on the wire size. Since the dielectric constants of semiconductors are much larger than 1, the dielectric effect affects seriously on the polarization anisotropy. In case that the internal emission is not isotropic such as in the case of the wurtzite-type semiconductors and quantum wires, we have to consider that $d_{0x} = d_{0y} \neq d_{0z}$. In such cases, (21.68) changes to

$$P = \frac{I_{\parallel} - I_{\perp}}{I_{\parallel} + I_{\perp}} = \frac{(\varepsilon+\varepsilon_0)^2 p - 4\varepsilon_0^2}{(\varepsilon+\varepsilon_0)^2 p + 8\varepsilon_0^2} \tag{21.69}$$

where we define

$$p = \frac{d_{0z}^2}{d_{0x}^2} = \frac{|M_{\parallel}|^2}{|M_{\perp}|^2} \tag{21.70}$$

as a measure of the anisotropic internal emission.

For large nanowires, the above treatment becomes invalid when the diameter of the wire is comparable with the wavelength of emitted light, and the polarization depends on wire size. In this case, the retardation effect should be involved, and we have to solve the Helmholtz equation to find the electromagnetic field in the nanowires instead of the Laplace equation (Ruda and Shik, 2006). Consequently, the following equations are derived corresponding to (21.65)

$$\begin{aligned} d_x &= \sqrt{\varepsilon}\,\frac{J_1'(ka)H_1^{(1)}(ka) - J_1(ka)H_1^{(1)\prime}(ka)}{\sqrt{\varepsilon_0}\,J_1'(ka)H_1^{(1)}(k_0a) - \sqrt{\varepsilon}\,J_1(ka)H_1^{(1)\prime}(k_0a)}\, d_{0x} \equiv A_x d_{0x} \\ d_z &= \sqrt{\varepsilon}\,\frac{J_1(ka)H_0^{(1)}(ka) - J_0(ka)H_1^{(1)}(ka)}{\sqrt{\varepsilon}\,J_1(ka)H_0^{(1)}(k_0a) - \sqrt{\varepsilon_0}\,J_0(ka)H_1^{(1)}(k_0a)}\, d_{0z} \equiv A_z\, d_{0z} \end{aligned} \tag{21.71}$$

where J and H are the Bessel and first-kind Hankel functions

$$k = \sqrt{\varepsilon}\,\frac{\omega}{c}$$

$$k_0 = \sqrt{\varepsilon_0}\,\frac{\omega}{c}$$

The coefficient A expresses the effect of image force. It is noted that ε_0 and ε are the relative dielectric constants at the frequency ω, and different from the static values listed in Table 21.1. The relation of the wave numbers of light in the nanowire and surrounding material is written as $k = k_0\sqrt{\varepsilon/\varepsilon_0} = nk_0$, using the refractive index n of the material of the wire. The polarization ratio is given as

$$P = \frac{A_z^2\, p - A_x^2}{A_z^2\, p + 2A_x^2} \tag{21.72}$$

Figure 21.14 shows polarization ratio P as a function of $k_0a(=(\omega/c)a)$, calculated for various values of ε and p. The polarization is seen to strongly oscillate with k_0a. In the case that $\varepsilon = 4$ and $p = 1$, the points where $P = 0$ are given by $k_0a = 1.21, 1.91, 2.72, 3.5, \ldots$. It is found that the polarization ratio has a value calculated from (21.68), when the radius a is sufficiently smaller than the wavelength of light, λ_0. Then, the polarization ratio P decreases



FIGURE 21.14 Polarization ratio as a function of $k_0a(=(\omega/c)a)$ calculated by (21.72) for (a) various values of ε with $p = 1$, and (b) various values of p with $\varepsilon = 4$.

with increasing a, and is equal to zero at $a_1 = 0.193\lambda_0$. With further increasing a, P gradually approaches zero with oscillation. If p is not equal to 1, the asymptotic value of P is to be given by (21.69) for $k_0a = 0$ and $(p - 1)/(p + 2)$ in the limit of $k_0a \to \infty$.

21.5 Application of TEM-CL

21.5.1 InP Nanowires

InP has a direct band gap structure with a gap energy of 1.42 eV at 4 K. Exciton Bohr radius is about 11 nm, so the quantum confinement effects, energy shift of the near-edge emission, and polarization characteristics are expected to appear for nanowires with a diameter smaller than this radius. Exciton binding energy is 5 meV. The emission intensity of exciton in the bulk crystal is weak at higher temperatures, but it can be observed even at room temperature if the quantum effect is strong enough. The size dependence of emission energy by quantum confinement effect has been measured in PL and absorption spectroscopy (Yu et al., 2003), and theoretically treated for cylindrical nanowires (Pellegrini et al., 2005). The PL study by Wang et al. (2001) using a polarized light excitation showed extremely large degree of polarization ($P = 0.96$) along the wire axis in the luminescence from single InP nanowires. The peak shift in PL was small, and the anisotropic polarization was considered to be due to the dielectric effect. Mishra et al. (2007) showed that the PL emission from the InP nanowires of 80 nm in diameter having zinc-blend and wurtzite structures are polarized parallel and perpendicular to the wire axis, respectively.

InP nanowires were grown on InP substrates by the metal-organic vapor phase epitaxy (MOCVPE) technique with gold nanoparticles as the catalyst (Figure 21.15). From the TEM observation, the InP nanowire has the zinc-blend structure of cubic lattice. The wire axis is parallel to the [111] axis, and the nanowire contains many twin boundaries normal to the wire axis (Bhunia et al., 2003). The diameter of the nanowire is distributed in the range from 5 to 30 nm, and the most frequently observed size is 20 nm. The length can be controlled by the growth conditions such as group-III source gas flow rate and total growth time, and that of the present sample is 700 nm. Cross-sectional samples were made by cleaving the sample crystal normal to the (111) substrate surface, and were examined by TEM-CL (Yamamoto et al., 2006).



FIGURE 21.15 A SEM image of InP nanowires grown on InP.

Figure 21.15a shows a SEM image of InP nanowires standing straight on the InP substrate with various diameters. The image was taken at a tilt angle of 40°. Figure 21.16a shows a SEM image of a cross-sectional sample where the InP nanowires are standing perpendicular to the incident electron beam. The CL spectra from the nanowires and a substrate region are shown in Figure 21.16b with a common vertical scale, which were taken at room temperature with an electron beam scanning over an 0.5 μm × 0.5 μm area in each region. A broad peak appears in the CL spectrum from the nanowire region at peak energy of 1.50 eV. The band gap energy of the bulk InP is 1.34 eV at room temperature, and this peak energy is much higher than that expected from the quantum confinement effect for the nanowire of 20 nm in diameter. The intensity of the nanowire emission is one order stronger than that of the InP substrate. A monochromatic CL image in Figure 21.16c clearly shows that an intense emission comes from the



(a) (b) (c) (d)

FIGURE 21.16 (a) A SEM image of a cross-sectional sample, (b) room temperature CL spectra from the nanowires (NWRs) and substrate region with a common vertical scale. (c) and (d) are monochromatic CL images taken at photon energies of 1.419 and 1.473 eV, respectively.

nanowires rather than from the substrate at room temperature. Individual nanowire can be resolved in the CL image, as indicated by an arrow. The broad emission peak from the nanowires is considered to be due to the size distribution in wire diameter because the electron confinement energy of nanowire changes with wire diameter. Then the emissions of different energies are expected to come from the nanowires with different diameters. Figure 21.16c and d shows monochromatic CL images taken at photon energies of 1.419 and 1.473 eV, respectively. The images should reveal the distribution of nanowires which produce the emissions of these energies. However, the intensity distribution is almost the same in those images, and the nanowires with different diameters cannot be distinguished. This fact indicates that each nanowire gives the broad peak in the emission spectrum.

The temperature dependence of the emission spectrum from the nanowire is shown in Figure 21.17. The emission intensity of the broad peak does not increase with decreasing temperature from room temperature to 40 K, while that from the InP substrate strongly increases with cooling. The broad peak blueshifts with decreasing temperature and the behavior of the shift follows the Varshni's law. The deviation of the broad peak from the exciton peak in the bulk InP is about 170 meV. For the



FIGURE 21.17 Emission spectra from the nanowires taken at various temperatures.

recombination of carriers in the ground states ($l = 0$ and $n = 1$), the emission energy shift from the bulk one is roughly estimated from (21.46) to be $\Delta E_{0,1}$ = 31 meV for the InP wire of R = 10 nm with μ = 0.071 m and $j_{0,1}$ = 2.405. From the comparison, the observed value is much larger than the value expected from the average diameter of 20 nm. The diameter of the InP quantum wire with the energy shift of 170 meV is estimated to be about 5 nm from the previous data by (Yu et al., 2003). It can be considered that there exists a depletion region near the surface or an oxide layer on the nanowire sidewalls (Dionizio et al., 2008), which decreases a practical size of carrier confinement region.

Figure 21.18a shows CL spectra from the nanowire region and substrate region taken at 80 K, with an electron beam scanning over an 0.5 μm × 0.5 μm area. The emission peak at 1.412 eV comes from the InP substrate with a strong intensity, and the emission from the nanowires shows a strong peak at 1.417 eV. The deviation from the InP peak is 5 meV. This peak shift is much smaller than the value estimated from the quantum confinement effect. It is more likely to be considered that the emission comes from the strained InP substrate region near the surface, because a part of the carriers generated in the nanowires can drift into the substrate.

Figure 21.18b shows CL spectra in the wide energy range extended to more than 1.5 eV. In this spectral range, the CL intensity from the nanowire region is much stronger than that from the InP substrate. A broad peak appears in the spectrum from the nanowire region at 1.60 eV with a full-width half-maximum (FWHM) of 150 meV. Figure 21.18c is a SEM image of the nanowire region, and a corresponding panchromatic CL image taken at 80 K is shown in Figure 21.18d. The InP substrate shows a brighter contrast than the nanowires in this image. On the other hand, in monochromatic CL images taken at the photon energy of 1.55 and 1.632 eV (Figure 21.18e and f), the nanowires show much brighter contrast than the InP substrate. It is noticed that the intensity distributions in Figure 21.18e and f are similar to each other in spite of the existence of the size distribution in the nanowires. This means that the emission peak from each nanowire is sufficiently broad, even at low temperatures. If the broadening of the emission peak due to the phonon scattering process is dominant, the FWHM of the peak should become narrow with decreasing sample temperature, and split peaks from the nanowires with different diameters are expected to be observed. However, any split from the broad peak has not been observed, even for the measurement under a converged electron beam illumination at the nanowire region. One possible



FIGURE 21.18 (a) A CL spectrum from the nanowire region and substrate region taken at 80 K, and (b) a magnified spectrum of (a). (c) A SEM image of the nanowire region and (d) a corresponding panchromatic CL image. (e) and (f) are monochromatic CL images taken at photon energy of 1.55 and 1.632 eV, respectively.



FIGURE 21.19 CL spectra from the nanowire region and substrate region taken for the *p* (solid spots) and *s* (open spots) polarization directions.

explanation is that the broadening of the luminescence peak occurs due to carrier scattering by the impurities or defects such as twin boundaries involved in the nanowire during the growth. In such case, the FWHM is independent of temperature. However, the origin of the broadening is not yet clear.

The polarization dependence of the CL spectrum was measured, as shown in Figure 21.19, where *p*(*s*) polarization corresponds to the electric field oscillation of light parallel (normal) to the nanowire direction. It is found that the luminescent light emitted from the nanowires is highly polarized parallel to the wire direction, while that from the substrate is not polarized. The polarization ratio at the peak energy of 1.6 eV is 0.50. The value expected from the dielectric effect is $P = 0.93$ calculated in (21.68) with $\varepsilon = 12.0$, where the size dependence of the dielectric effect is neglected. In addition, the quantum confinement effect should be involved, i.e., (21.69) is used with $p(>1)$, the expected value must be larger than 0.93. The observed value is much smaller than the expected one. This is partly because the polarization mixing occurs due to reflection by the ellipsoidal mirror which corrects light emitted to a large solid angle. Wang et al. (2001) reported a large degree of polarization ($P = 0.96$) in the photoluminescence from InP nanowires. The PL was excited by a polarized light, so the polarization anisotropy is enhanced in the absorption process. Whereas in the CL experiment, the excitation is performed by the incident electrons, there is no anisotropy in excitation of carriers. Thus, the degree of polarization in the CL measurement is smaller than that in the polarized PL. The CL detection is recently improved by introducing the angler-resolved measurement system, as shown in the later section of ZnO nanowires.

21.5.2 GaAs Nanowire

Gallium arsenide (GaAs) has a zinc-blend structure, with a direct band gap of 1.519 eV at 0 K. Exciton radius is rather large, about 15 nm, so the quantum confinement effect on photon energy and polarization of the FX emission is expected for thin nanowires. The binding energy of FX in the bulk is about 4 meV, and the emission intensity of FX becomes weak at higher temperatures above 200 K, even in thin nanowires. Recently, self-standing nanowires of many semiconductors are produced by a growth technique using nanosized liquid droplets of a metal solvent (Hiruma et al., 1995; Gudiksen et al., 2002; Wu et al., 2002), and optical properties were theoretically studied (Persson and Xu, 2004; Redlinski and Peeters, 2008).

Figure 21.20a shows a SEM image of a GaAs nanowire sample covered by an $Al_{0.4}Ga_{0.6}As$ layer, self-standing on a Si(111) substrate. The average outer dimensions of the nanowires are 80 nm in diameter and 700 nm in height, and the average density of the nanowires is about 10 μm^{-2}. The sample was fabricated by a metalorganic chemical vapor phase epitaxy (MOCVPE) technique using Au nanoparticles as the catalyst (Bhunia et al., 2003; Tateno et al., 2004). First, an $Al_{0.3}Ga_{0.7}As$ nanowire was grown to 100 nm in height on the Si substrate, and then GaAs nanowire and $Al_{0.3}Ga_{0.7}As$ nanowires were successively grown to 100 and 180 nm, respectively. Finally, $Al_{0.4}Ga_{0.6}As$ was deposited as a capping layer, with a thickness of 100 nm to reduce the nonradiative recombination on the nanowire surface. Au dots with a radius of about 20 nm can be observed on top of the nanowires in Figure. 21.20a. Figure 21.20b schematically represents a diagram of the sample structure. The materials are direct-gap



FIGURE 21.20 (a) A SEM image of GaAs/AlGaAs nanowires with a core-shell structure, and (b) schematic diagram of the sample structure.

semiconductors, with energy gaps of 1.52 eV for GaAs, 1.96 eV for $Al_{0.3}Ga_{0.7}As$, and 2.11 eV for $Al_{0.4}Ga_{0.6}As$ at 0 K (Pavesi and Guzzi, 1994). The $Al_{0.4}Ga_{0.6}As$ capping layer acts as a potential barrier, so a stronger (weaker) confinement structure is formed in the GaAs ($Al_{0.3}Ga_{0.7}As$) wire region. Carriers excited in the wire by an electron beam are expected to flow into the GaAs wire region, and recombine at the bottom of the band. Therefore, CL only from GaAs nanowires is expected to have sharp emission peaks in the CL spectrum corresponding to their diameters.

Figure 21.21a shows a SEM image of the sample observed from the direction normal to the surface. The image was observed in the SEM mode using the TEM operated at an accelerating voltage of 80 kV with a scanning area of 1 μm^2 (Ishikawa et al., 2008). Figure 21.21b shows a panchromatic CL image of the same area as that shown in Figure 21.20a taken at 60 K. The localized CL intensity is distributed at the nanowires, and we can specify the emission of each nanowire from the comparison between the CL image and the SEM image. A spectrum from this area is shown in Figure 21.21c, where two broad peaks with a complex shape appear, reflecting the size distribution of the nanowires existing in this area. The emission spectra of similar shapes were frequently observed when the scanning area is of the order of 1 μm^2, although the peak energies are different. The spectrum taken from the wider area becomes a single broad peak extending over the energy range from 1.7 to 2.0 eV. The broadening of the CL peak is due to the superposition of many CL peaks from the nanowires of different diameters. To determine the effect of size distribution, we used a focused electron beam illuminating individual nanowires, A, B, and C indicated by circles in Figure 21.21a. As shown in Figure 21.21d, sharp peaks were observed to appear at different energies because of the difference in diameter of the wire. It is noted that some nanowires such as A and C show double emission peaks.

As for the diameters of the nanowires, it is difficult to determine them from the SEM image since the wires are covered by the AlGaAs layer with outer diameters of about 100 nm. The



FIGURE 21.21 (a) A SEM image of the GaAs/AlGaAs nanowires, and (b) a panchromatic CL image taken at 130 K. A scan area is 1 μm × 1 μm. (c) A CL spectrum taken from the 1 μm × 1 μm area in (b). (d) CL spectra taken from the individual nanowires marked A, B, and C in (a) and (b).

energy levels were previously theoretically studied by Persson and Xu (2004) for GaAs nanowhisker grown in the [111] direction, on the basis of a tight binding approach. According to the calculation of the transition at the Γ point, the peak energies from 1.7 to 2.0 eV in the CL spectrum from the wide area correspond to the diameters from 5 to 2 nm. These values are much smaller than that expected from a Au particle size of 20 nm. This has been similarly observed in InP self-standing nanowires (Yamamoto et al., 2006), where the peak shift is much larger than that expected from the outer dimensions of the wire. This means that a practical size of carrier confinement region is much smaller than the apparent diameter. Such narrowing of the confinement region may result from the inner stress near the GaAs/AlGaAs interface and interdiffusion of Al into the wire.

The temperature dependence of the CL spectra from the single nanowire A shown in Figure 21.21a is shown in Figure 21.22a. The lower energy peak (P1) appears below 140 K and the higher energy peak (P2) appears below 100 K. Their intensities increase with decreasing temperature. The intensity of the P2 peak increases rapidly at lower temperatures, and exceeds the P1 peak intensity at about 60 K. As shown in Figure 21.22b, the P1 peak energy shows a blue shift as temperature decreases, following the band gap shift described by Varshni's law (solid lines). The P1 emission can be attributed to the radiative recombination of excitons at the ground state of the GaAs wire because the emission peak predominates at low temperatures. The luminescence of excitons remains at rather high temperatures compared with that in bulk GaAs because the binding energy of excitons becomes large in nanowires owing to the quantum confinement effect (Basu, 1997). The appearance of the two peaks can be explained, assuming that the two parts having different energy states coexist along a single nanowire. The inhomogeneous intensity distribution was frequently observed along the tilted wires in the CL images and the polarization of the emitted light was randomly distributed with respect to the wire axis (Ishikawa et al., 2008). These facts indicate that the quantum-dot-like potential structure is formed along the wire, which does not emit a polarized light parallel to the wire axis.

Figure 21.23a shows a SEM image of a GaAs/AlGaAs nanowire with a core-shell structure, as illustrated in Figure 21.20, and Figure 21.23b shows a corresponding panchromatic CL image taken at 130 K. In the CL image, discontinuous contrast is seen to appear along the wire, which suggests the existence of a quantum dot-like structure in the GaAs core. Figure 21.23c is a spectrum image taken with the electron beam scanning along the wire axis. A peak line at a wavelength of 830 nm is attributed to the bulk luminescence of GaAs. This indicates that the carriers excited in the wire diffuse into the GaAs substrate because this peak vanishes for the nanowire separated from the substrate. It is noted that the emissions from those dots have a common spectral shape in the wavelength range from 700 to 800 nm, and the anisotropy in polarization is very small. We still need more consideration about the property of this luminescence.



FIGURE 21.22 (a) Temperature dependence of the CL spectrum from the nanowire A in Figure 21.21. (b) Temperature dependence of the peak energies of the two peaks. Solid lines show the temperature dependence of the band gaps of GaAs, $Al_{0.3}Ga_{0.7}As$, and $Al_{0.4}Ga_{0.6}As$, respectively, given by the Varshni's law. The solid curve of GaAs is shifted for easy comparison with the observed one.



(a) (b) (c)

FIGURE 21.23 (a) A SEM image of GaAs/AlGaAs nanowires and (b) a panchromatic CL image of the same area (3 μm × 3 μm) taken at 130 K. (c) A spectrum image taken with the electron beam scanning along a line A-B through the central nanowire in (a).

21.5.3 ZnO Nanowires

Zinc oxide (ZnO) is a wide gap semiconductor of wurtzite structure, with a gap energy of 3.44 eV at 4 K. The valence band structure of bulk ZnO near the BE is composed of three bands (A, B, and C band), and the character of the band has been controversy for many years. The highest energy band (the A band) of many wurtzite-type semiconductors such as GaN and CdSe has a character of heavy hole (the Γ_9 symmetry, as shown in Figure 21.5b), whereas many authors assume the Γ_7 symmetry character for ZnO (Meyer et al., 2004). The polarization studies showed that the inner emission due to the transition from the conduction band to the A band contain both polarization components parallel and perpendicular to the *c*-axis. The energy difference between the A and B band was reported to be very small, 4.9 meV. The exciton binding energy is about 60 meV which is much larger than the thermal energy at room temperature (k_BT = 25 meV), so the band-edge emission can be observed even at room temperature. However, the exciton radius is very small (a_X = 1.3 nm), and it is difficult to fabricate a ZnO quantum wire of such a small diameter. The quantum effect of ZnO nanowires has rarely been reported so far.

Recently, the optical properties of ZnO nanowires have been studied using self-standing nanowires grown parallel to the *c*-axis by MOCVD technique. Hsu et al. (2004) measured PL from narrow nanowires at room temperature and observed BE emission and green emission originated from defects. They showed that the BE emission is polarized parallel to the *c*-axis with the intensity ratio of $I_{\|}:I_{\perp} = 1:0.7$, whereas the green emission is polarized perpendicular to the *c*-axis with the ratio of $I_{\|}:I_{\perp} = 0.85:1$. The polarization dependence of photoconductivity was studied by Fan et al. (2004) using nanowires of 30–150 nm in diameter. The photoconductivity had a maximum value for polarization direction parallel to the *c*-axis. Yu et al. (2003) measured temperature dependence of PL spectrum from ZnO nanowires, showing peaks of BX emission, the *P* emission, and their phonon replica. The nanowires of wurtzite-type semiconductors such as GaN (Zhang and Xia, 2006; Chen et al., 2008) and CdSe (Lan et al., 2008) have also been studied. Chen et al. (2008) measured the size dependence in polarization of the BE emission from GaN nanowires, and explained the results from the dielectric effect and the anisotropy in the inner emission. The polarization ratio changed with temperature; the BE emission is polarized parallel to the *c*-axis at room temperature, and is unpolarized at 20 K. They explained this from the change in anisotropy of the internal emission.

In the TEM-CL study, ZnO smoke particles were made by burning a Zn wire in air, and were collected by a copper mesh coated by a carbon film with micrometer-size holes. The smoke particle has a tetrapod-like shape, with four legs growing along the *c*-axis. Figure 21.24 shows CL spectra taken from a thick leg of the ZnO smoke particle at various temperatures. Two peaks at wavelengths of 368 nm (3.370 eV) and 375 nm (3.307 eV) appear in the spectrum at 20 K. The peak at 368 nm can be attributed to the ionized donor BX emission (Meyer et al., 2004), and the peak



FIGURE 21.24 CL spectra taken from a thick leg of a ZnO smoke particle at various temperatures.

at 375 nm is due to the *P* emission, which is generated by Auger-like process associated with two excitons (Hvam, 1973; Li et al., 2008). A small peak at 393 nm (3.155 eV) is a phonon replica of the *P* emission. The photon energies of those peaks shift to lower energies with temperature, following the Varshni's law. A broad single peak (a BE emission) at room temperature can be recognized as a mixed peak composed of the BX emission, *P* emission, and their phonon replica.

Figure 21.25a shows a SEM image of a ZnO smoke particle with thick legs, and Figure 21.25b and c are monochromatic CL images taken at the peak wavelength at room temperature for the *p* and *s* polarizations, respectively. The BE emission from a leg marked A extending along the *y* direction is strong in the *p* polarization, whereas that from a leg marked B extending along the *x* direction is strong in the *s* polarization. These facts indicate that the BE emission is polarized perpendicular to the *c*-axis. The central part of the particle shows a dark contrast because the emission peak from this part is slightly shifted to the longer wavelength. The central part showed a bright contrast in the monochromatic CL image taken at 395 nm (Figure 21.25d). This peak shift may be caused by the band gap narrowing due to strain in the multiple twin structure at the central part.



FIGURE 21.25 (a) A SEM image of a ZnO smoke particle with thick legs, and (b) and (c) are monochromatic CL images taken at the peak wavelength (383 nm) at room temperature for the *p* and *s* polarizations, respectively. (d) A monochromatic CL image taken at 395 nm.

The polarization of the BE emission from ZnO nanowires depends on the diameter of the wire. CL light emitted from a single wire with a large diameter (300 nm) elongating perpendicular to the axis of the parabolic mirror was measured with changing polarization angle θ defined in Figure 21.12. The CL intensity as a function of θ is shown in Figure 21.26a. The light was emitted in a direction perpendicular to the thick wire axis. The solid angle of the detection is about 0.05 str. The intensity of the BE emission at 383 nm has a minimum at $\theta = 0°$, and shows $\cos^2\theta$-dependence. Polarization ratio is estimated to be −0.43 from the intensity ratio of $I_{\|c}/I_{\perp c} = 0.40$, which is deduced using the fitting function of

$$I(\theta) = (I_{\|} - I_{\perp})\cos^2\theta + I_{\perp} \qquad (21.73)$$

Whereas the BE emission from a thin nanowire with a diameter of 60 nm presented an opposite behavior in polarization, as shown in Figure 21.26b; the intensity has a maximum at $\theta = 0°$. The polarization ratio is estimated to be 0.31 from the intensity ratio of $I_{\|c}/I_{\perp c} = 1.9$.

The quantum confinement effect cannot affect the polarization property of the CL emission from the ZnO nanowires because the diameters of those wires are much larger than the exciton radius. Therefore, the parameter *p* related to the anisotropic internal emission is fixed regardless of the diameter of the nanowires, and should be given by the character of the optical transition in the bulk crystal. If the intensity ratio $I_{\|c}/I_{\perp c} = 0.40$ is considered as a bulk one, the parameter *p* can be calculated from (21.67) and (21.70) as follows:

$$p = \frac{d_{0z}{}^{2}}{d_{0x}{}^{2}} = \frac{1}{2}\left\{3\left(\frac{I_{\|}}{I_{\perp}}\right) - 1\right\} = 0.1 \qquad (21.74)$$



FIGURE 21.26 CL intensity from (a) a thick wire (diameter of 300 nm) and (b) a thin wire (60 nm) of ZnO measured by changing an angle θ.

If the highest energy state in the valence band has a character of the light hole, $p = 4$ is expected from (21.58) for the transition from the conduction band to valence band. The above value is too small compared to the expected one. In other words, the emission due to the transition to the light hole state should be mainly polarized parallel to the *c*-axis, but the observed one is rather polarized perpendicular to the *c*-axis. This fact indicates that the transition to the heavy hole state component in the A band considerably contributes to the CL emission. It was also observed that the polarization ratio does not change with temperature from 20 to 300 K.



FIGURE 21.27 Dependence of the polarization ratio on nanowire diameter measured from several nanowires with various diameters. Solid line is a calculated curve using the dielectric constant at the peak wavelength of 4.0 and $p = 0.25$.

The CL emission from the thick nanowire is polarized perpendicular to the wire axis (the *c*-axis), whereas that from the thin nanowire is polarized parallel to the wire axis. We should consider the dielectric effect for explaining this size dependence of the polarization. Figure 21.27 shows the dependence of the polarization ratio on nanowire diameter calculated from (21.71) and (21.72) with the dielectric constant at the peak wavelength to be 4.0 and with $p = 0.25$. This result well explains the behavior that the polarization ratio P is positive for thin nanowires, and turns to be negative for thick nanowires. The experimental values measured from ZnO nanowires with different diameters are plotted in Figure 21.27. The polarization ratio changes sign around a diameter of 100 nm, being fitted with the calculated curve.

The spatial variation of polarization can be measured from spectral images taken with scanning electron beam. Figure 21.28a and b shows a SEM image of a ZnO smoke particle with thick legs and a panchromatic CL image, respectively. Change in CL intensity appears along the leg. Figure 21.28c and d are *p*- and *s*-polarized spectral images taken with scanning electron beam along the line A-B in Figure 21.28a. The peak wavelength is 383 nm at room temperature. Polarization ratio calculated from the division of the peak intensities in the images of Figure 21.28c and d is shown in Figure 21.28e. The polarization ratio is seen to be −0.45 at a thinner part (D = 150 nm) and −0.25 at a thicker part along the line. One of the legs is standing vertically near the position B, and the polarization is vanished there.



FIGURE 21.28 (a) A SEM image of a ZnO smoke particle and (b) a panchromatic CL image, respectively. (c) and (d) are *p*- and *s*-polarized spectral images taken with scanning electron beam along the line A-B in (a). (e) Spatial variation of the polarization ratio along the line.

This behavior is qualitatively explained by the theoretical curve in Figure 21.27.

Other types of emission appear under a high excitation condition, when a thin nanowire is illuminated by a strong electron beam. The *P* emission is one of such types. Emission peak due to the exciton molecules appears near the BE peak, and shifts to the lower energies with increasing electron beam density. The emission peak due to the electron-hole plasma also appears at the lower energy side of the BE peak, and becomes predominant under the high excitation rate. The effect of shape and size of nanowires on the property of these emissions such as threshold condition of lasing has been studied recently (Johnson et al., 2003).

Acknowledgment

The author acknowledges Y. Watanabe, K. Tateno, G. Salviati, and L. Lazzarini for the supply of nanowire samples. This work has been supported by the Grant-in-Aid for Scientific Research from the Ministry of Education, Culture, Sports, Science and Technology of Japan.

References

Ando, H, Oohashi, H, and Kanbe, H, 1991, *J. Appl. Phys*. 70, 7024.

Arakawa, Y and Sakaki, H, 1982, *Appl. Phys. Lett*. **40**, 939.

Basu, PK, 1997, *Theory of Optical Processes in Semiconductors*, Oxford University Press, New York.

Bockelmann, U and Bastard, G, 1992, *Phys. Rev. B* **45**, 1688.

Bhunia, S, Kawamura, T, Watanabe, Y, Fujikawa, S, and Tokushima, K, 2003, *Appl. Phys. Lett*. **83**, 3371.

Chen, H-Y, Yang, Y-C, Lin, H-W, Chang, S-C, and Gwo, S, 2008, *Opt. Express* 16(17), 13465.

Dionizio, M, Venezuela, P, and Schmidt, TM, 2008, *Nanotechnology* 19, 065203.

Fan, Z, Chang, P-C, Lu, JG, Walter, EC, Penner, RM, Lin, C-H, and Lee, HP, 2004, *Appl. Phys. Lett*. 85(25), 6128.

Goldstein, JI, Costley, JL, Lorimer, GW, and Reed, SJB, 1977, *Scanning Electron Microscopy*, Vol. 1, pp. 315, IITRI, Chicago, IL.

Gudiksen, MS, Lauhon, LJ, Wang, J, Smith, DC, and Lieber, CM, 2002, *Nature* **415**, 617.

Guilet, T, Grousson, R, Voliotis, V, Wang, X-L, and Ogura, M, 2003, *Phys. Rev. B* **68**, 045319.

Hiruma, K, Yazawa, M, Katsuyama, T, Ogawa, K, Haraguchi, K, Koguchi, M, and Kakibayashi, H, 1995, *J. Appl. Phys*. **77**, 447.

Hsu, NE, Hung, WK, and Chen, YF, 2004, *J. Appl. Phys*. **96**(8), 4671.

Hvan, JM, 1973, Solid State Com. **12**, 95.

Hensel, JC and Feher, G, 1963, *Phys. Rev*. **129**, 1041.

Ils, P, Michel, M, Forchel, A, Gyuro, I, Klenk, M, and Zielinski, E, 1994, *Appl. Phys. Lett*. **64**, 496.

Ino, N and Yamamoto, N, 2008, *Appl. Phys. Lett*. **93**, 232103.

Ishikawa, K, Yamamoto, N, Tateno, K, and Watanabe, Y, 2008, *Jpn. J. Appl. Phys*. **47**(8), 6596.

Johnson, JC, Yan, H, Yang, P, and Saykally, RJ, 2003, *J. Phys. Chem. B* **107**, 8816.

Kane, EO, 1957, *J. Phys. Chem. Solids*. **1**, 249.

Kapon, E, Hwang, DM, and Bhat, R, 1989, *Phys. Rev. Lett*. **63**, 430.

Lan, A, Giblin, J, Protasenko, V, and Kuno, M, 2008, *Appl. Phys. Lett*. **92**, 183110.

Landau, LD, Lifshitz, EM, and Pitaevskii, LP, 1984, *Electrodynamics of Continuous Media*, Pergamon, Oxford, U.K.

Li, W, Gao, M, Chen, R, Zhang, X, Xie, S, and Peng, L-M, 2008, *Appl. Phys. Lett*. **93**, 023117.

Luttinger, JM and Kohn, W, 1955, *Phys. Rev*. **97**, 869.

McIntyre, CR and Sham, LJ, 1992, *Phys. Rev*. **45**, 9443.

Meyer, BK, Alves, H, Hofmann, DM et al., 2004, *Phys. Stat. Sol. (b)* **241**(2), 231.

Mishra, A, Titova, LV, Hoang, TB et al., 2007, *Appl. Phys. Lett*. **91**, 263104.

Mitsui, T, Yamamoto, N, Tadokoro, T, and Ohta, S, 1996, *J. Appl. Phys*. **80**, 6972.

Nakaji, D, Grillo, V, Yananoto, N, and Mukai, T, 2005, *J. Elect. Microscopy*. **54**, 223.

Ogawa, T and Takagahara, T, 1991, *Phys. Rev. B* **43**, 14325.

Pankove, JI, 1971, *Optical Processes in Semiconductors*, Dover Pub. Inc., New York.

Pavesi, L and Guzzi, M, 1994, *J. Appl. Phys*. **75**, 4779.

Pellegrini, G, Mattei, G, and Mazzoldi, P, 2005, *J. Appl. Phys*. **97**, 073706.

Persson, MP and Xu, HQ, 2004, *Nano Lett*. **4**, 2409.

Pfeiffer, L, West, KW, Stormer, HL, Eisenstein, JP, Baldwin, KW, Gershoni, D, and Spector, J, 1990, *Appl. Phys. Lett*. **56** 1697.

Pollak, FH and Cardona, M, 1968, *Phys. Rev*. **172**, 816.

Redlinski, P and Peeters, FM, 2008, *Phys. Rev. B* **77**, 075329.

Ruda, HE and Shik, A, 2005, *Phys. Rev. B* **72**, 115308.

Ruda, HE and Shik, A, 2006, *J. Appl. Phys*. **100**, 024314.

Sakaki, H, 1980, *Jpn. J. Appl. Phys*. **19**, L735.

Sercel, PC and Vahala, KJ, 1990, *Appl. Phys. Lett*. **57**, 545.

Someya, T, Akiyama, H, and Sakaki, H, 1995, *Phys. Rev. Lett*. **74**, 3664.

Tanaka, M and Sakaki, H, 1989, *Appl. Phys. Lett*. **54**, 1326.

Tanatar, B, Al-Hayek, I, and Tomak, M, 1998, *Phys. Rev. B* **58**, 9886.

Tateno, K, Gotoh, H, and Watanabe, Y, 2004, *Appl. Phys. Lett*. **85**, 1808.

Tsuchiya, M, Gaines, JM, Yan, RH, Simes, RJ, Holtz, PO, Coldren, LA, and Petroff, PM, 1989, *Phys. Rev*. **62**, 455.

Voos, M, Leheny, RF, and Shah, J 1980, Radiative recombination, in *Handbook on Semiconductors: Vol. 2 Optical Properties of Solids*, M. Balkanski (ed.), North-Holland, Amsterdam, the Netherlands.

Vugaftman, I, Meyer, JR, and Ram-Mohan, LR, 2001, *Appl. Phys. Rev*. **89**, 5815.

Wang, J, Gudiksen, MS, Duan, X, Cui, Y, and Lieber, CM, 2001, *Science* **293**, 1455.

Wang, X-L and Voliotis, V, 2006, *J. Appl. Phys*. **99**, 121301.

Wu, Y, Fan, R, and Yang, P, 2002, *Nano Lett*. **2**, 83.

Yananoto, N, Spence, JCH, and Fatty, D, 1984, *Phil. Mag. A* **49**, 609.

Yamamoto, N 2002, Development of CL for semiconductor research I: EM-CL study of microstructures and defects in semiconductor epilayers, in *Nanoscale Spectroscopy and Its Applications to Semiconductor Research*, Watanabe Y et al. (eds.), *Lecture Notes in Physics*, Vol. 588, Springer Verlag, Berlin, Germany.

Yamamoto, N, 2008, TEM-Cathodoluminescence study of semiconductor quantum dots and quantum wires, in *Beam Injection Based Nanocharacterization of Advanced Materials*, G. Salviati et al. (eds.), Research Signpost, Kerala, India.

Yamamoto, N, Itoh, H, Grillo, V, et al., 2003, *J. Appl. Phys.* **94**, 4315.

Yamamoto, N, Bhunia, S, and Watanabe, Y, 2006, *Appl. Phys. Lett.* **88**, 153106.

Yamamoto, N, Ishikawa, K, Akiba, K, Bhunia, S, Tateno, K, and Watanabe, Y, 2008, TEM-Cathodoluminescence study of semiconductor quantum dots and quantum wires, in *Beam Injection Based Nanocharacterization of Advanced Materials*, G. Salviati et al. (eds.), Research Signpost, Kerala, India.

Yu, H, Li, J, Loomis, RA, Wang L-W, and Buhro, WE, 2003, *Nat. Mater.* **2**, 517.

Yu, PY and Cardona, M 1999, *Fundamentals of Semiconductors*, Springer Verlag, Berlin, Germany.

Zhang, XW and Xia, JB, 2006, *J. Phys. Condens. Matter* **18**, 3107.

Zhao, X, Wei, CM, Yang, L, and Chou, MY, 2004, *Phys. Rev. Lett.* **92**(23), 236805.

22

Optical Spectroscopy of Nanomaterials

22.1 Introduction 22-1
22.2 Carbon Nanotubes 22-2
22.3 Nanoparticle Quantum Dots 22-4
22.4 Multiexciton Generation 22-6
22.5 Summary 22-7
Acknowledgments 22-7
References 22-7

Yoshihiko Kanemitsu
Kyoto University

22.1 Introduction

Over the past two decades, there have been extensive studies on the optical properties of semiconductor nanomaterials from the fundamental physics viewpoint and from the interest in the application to functional devices, because they exhibit unique size-dependent quantum properties [1–11]. In this chapter, we discuss optical properties of semiconductor nanomaterials of zero-dimensional (0D) nanoparticle quantum dots and one-dimensional (1D) carbon nanotubes. In optical studies of nanoparticle quantum dots and carbon nanotubes, we would like to point out two important reports opening new active fields: the discovery of room-temperature-visible luminescence from porous silicon in 1990 [12] and the discovery of efficient luminescence from isolated carbon nanotubes in 2002 [13]. These observations of efficient luminescence clearly show that nanoparticles and carbon nanotubes are high-quality crystalline semiconductors. Many different fabrication methods have been developed to obtain stable and efficient luminescence from nanoparticles and carbon nanotubes, e.g., core/shell nanoparticles, suspended isolated nanotubes, and so on [14–20]. These nanomaterials become new materials for optoelectronic devices such as wavelength-tunable light-emitting diodes and lasers, quantum light sources, and solar cell applications.

When semiconductor nanoparticles of sizes are comparable to or smaller than the exciton Bohr radius in bulk crystals, the excited state energies and optical properties are very sensitive to their sizes [1,21,22]. Usually, nanoparticle samples are an inhomogeneous system in the sense that they have a distribution of size and shape, and variations of surface structures and surrounding environments [2]. A large nanoparticle has small band-gap energy and a small nanoparticle has large band-gap energy. Furthermore, the nanoparticles have large surface-to-volume ratios, and then the optical properties of nanoparticles are also sensitive to surrounding environments. The exciton band-gap energy of semiconducting carbon nanotubes is also sensitive to the nanotube diameter and the chiral index. Then, we need to study the intrinsic optical processes in nanoparticle quantum dots and carbon nanotubes hidden by sample inhomogeneity using sophisticated optical spectroscopy.

If the laser light excites all nanoparticles or all nanotubes in the sample, the sample shows broad luminescence, reflecting size or diameter distributions. This "global" photoluminescence (PL) or nonresonantly excited luminescence contains contributions from all nanoparticles or all nanotubes in the sample, and the PL spectrum is inhomogeneously broadened, as shown in Figure 22.1a. These sample inhomogeneities are the origin of nonexponential PL decay. In inhomogeneously broadened systems, resonant excitation spectroscopy is a powerful method to obtain intrinsic information from broadened optical spectra. Under resonant excitation at energies within the global PL band, we can observe fine structures in PL spectra at low temperatures, as shown in Figure 22.1b. Resonant excitation at energies within the luminescence band results in a single zero-phonon PL line or a well-resolved phonon progression in PL spectra at low temperatures. In this case, we suppress the inhomogeneous broadening of the luminescence by selectively exciting a narrow subset of nanoparticles. Resonant excitation results in fluorescence line narrowing (FLN) in nanoparticle samples [23–27]. The resonantly excited PL spectra are sensitive to the nature of the band-edge structure and the surface structure [27–29]. Moreover, luminescence hole-burning (LHB) spectroscopy is another resonant excitation spectroscopy. In the LHB experiments, the sample is excited by intense laser at the energy within the PL band [30–32]. After prolonged laser irradiation (burning laser excitation), a spectral hole is formed near the burning laser energy in the luminescence



FIGURE 22.1 Luminescence spectra of semiconductor nanoparticles: (a) global luminescence spectrum, (b) resonantly excited luminescence spectrum, (c) LHB spectrum, and (d) single nanoparticle luminescence spectrum.

band. We obtain similar optical information from the FLN and LHB experiments. However, in the resonantly excited PL or FLN spectra, it is difficult to obtain the detailed spectrum near the excitation energy because of the scattering of the excitation laser light. In the LHB experiment, it is comparatively easy to observe the spectral change just at the excitation energy [32].

Single molecule (or nanomaterial) spectroscopy is the most powerful tool for understanding intrinsic optical properties of isolated molecules and nanomaterials [5,33]. Single nanoparticle spectroscopy makes it possible to probe inherent and novel optical properties in nondoped and impurity-doped semiconductor nanoparticles hidden by inhomogeneity, such as size distributions and surrounding environment variations [34–37]. As an example of unique optical phenomena, PL blinking (or PL intermittency) is revealed by single nanoparticle spectroscopy [35]. We have developed many different types of luminescence imaging microscopes. Our systems cover a wide spectral region and wide response times. The spatial resolution is typically about 1 μm in our confocal microscopes and about 50–100 nm in home-built near-field optical microscopes. In these space-resolved optical measurements, the most important point is the fabrication of stable and isolated nanomaterial samples. The nanomaterials should be isolated from each other, and the number density is dilute (about 1/μm^2 or less). The sample should be stable against oxidation and strong light illumination. Then, chemically synthesized materials are good samples for our optical studies. Here, we discuss the luminescence properties and the mechanism of spectral diffusion and PL blinking of single carbon nanotubes and nanoparticle quantum dots.

22.2 Carbon Nanotubes

A single-walled carbon nanotube (SWNT) with about 1 nm diameter and a length greater than several hundred nanometers is a prototype of 1D structures. The recent discovery of efficient PL from semiconducting SWNTs [13,38] has stimulated considerable efforts in understanding optical properties of SWNTs. The semiconducting SWNTs are 1D direct-gap band structures [8]. Because of the extremely strong electron–hole interactions (excitonic effects) in 1D materials, unique optical properties of SWNTs are determined by the dynamics of 1D excitons [8,39]. In addition, the electronic structure and the PL energy of SWNTs strongly depend on the diameter and the chiral index [38]. The SWNT samples are also inhomogeneous systems, similar to the nanoparticle samples, because many different species of nanotubes exist in the sample. The inhomogeneous broadening and the spectral overlapping of PL spectra cause the complicated PL dynamics of SWNTs. Single nanotube spectroscopy reveals the intrinsic excitonic properties of SWNTs [40–46], such as exciton energy, bright and dark exciton structures, exciton–phonon interaction, and so on.

For single nanotube spectroscopy, we synthesized spatially isolated carbon nanotubes on Si substrates using an alcohol catalytic chemical vapor deposition method [45,46]. In our experiments, the Si or SiO$_2$ substrates were patterned with parallel grooves, typically 500 nm wide and 500 nm deep using an electron-beam lithography technique. The isolated SWNTs grow from one side toward the opposite side of the groove. We used these SWNT samples without matrix and surfactant around the nanotubes to reduce the local environmental fluctuation effect. We show a typical PL spectrum of a single carbon nanotube suspended on the groove [assigned chiral index: (7,6)] at about 40 K in Figure 22.2a [46]. Very broad PL bands are observed in the ensemble-averaged spectrum of micelle-wrapped SWNTs dispersed in gelatin. The PL spectral shape of a single carbon



FIGURE 22.2 (a) PL spectrum of a typical suspended single SWNT [assigned chiral index (7,6)] in comparison with the ensemble-averaged spectrum of micelle-wrapped SWNTs dispersed in gelatin. (b) Polar plot of the PL intensity of a typical single SWNT versus the polarized direction of the excitation laser. The PL data (circle) were fitted using $\cos^2\theta$ (solid line). (Reprinted from Matsunaga, R. et al., *Phys. Rev. Lett.*, 101, 147404, 2008. With permission.)

nanotube is given by a Lorentzian function, and its linewidth of a few meV reflects homogeneous broadening. Figure 22.2b shows a polar plot of the PL intensity of a typical single carbon nanotube versus the polarization direction of the excitation laser light [46]. Since a 1D dipole moment exists, strong optical absorption occurs when the polarization of the excitation light parallels the nanotube axis. This PL anisotropy is useful for determining the direction of the observed nanotube axis for single nanotube spectroscopy and modulation spectroscopy.

The sharp luminescence spectra provide detailed information on the exciton fine structures. We studied the PL fine structure of single SWNTs under magnetic fields at low temperatures. A single sharp PL spectrum arising from bright exciton recombination is observed at zero magnetic field, as shown in Figure 22.2a. When the magnetic field is parallel to the nanotube axis, a new peak appears below the bright exciton peak. Figure 22.3a shows PL spectra of a single carbon nanotube under magnetic fields [46]. These PL spectra are fit well by two Lorentzian functions. With the magnetic field, the lower energy peak shows a redshift and the lower-energy peak intensity increases. We cannot observe these changes when the magnetic field is perpendicular to a single nanotube axis, as shown in Figure 22.3b [46]. The splitting of the PL peak occurs due to the magnetic flux parallel to the nanotube axis. These splitting and magnetic field dependence can be explained by the Aharonov–Bohm splitting of excitons based on the Ajiki and Ando model [8,47]. The singlet exciton states split into the bonding and antibonding exciton states, and this due to the short-range Coulomb interaction. The bonding state is odd parity (bright) and the antibonding is even (dark). The energy difference between the bright and dark exciton states also depends on the diameter of SWNTs. These experimental observations are consistent with the theoretical calculation. The dark exciton state exists about several meV below the bright exciton state. Studies of 1D dark excitons influencing optical responses of carbon nanotubes [48–52] are very important for optical device applications.



FIGURE 22.3 (a) Normalized magneto-PL spectra of a single (9,4) carbon nanotube at 20 K in the Voigt geometry. The split PL spectra are fit by two Lorentzian functions. (b) The normalized magneto-PL spectra of a single (9,5) carbon nanotube at 20 K in the Faraday geometry. The PL spectra are fit by a Lorentzian function. (Reprinted from Matsunaga, R. et al., *Phys. Rev. Lett.*, 101, 147404, 2008. With permission.)

The diameter dependence of the exciton energy in single carbon nanotubes is also revealed by single nanotube spectroscopy. At room temperature, the experimentally obtained PL spectra can be approximately reproduced by single Lorentzian functions. The observed PL peaks correspond to the zero-phonon lines of free excitons, and the spectral linewidth of the PL spectra is determined by the homogeneous broadening. We obtained PL spectra from many different isolated SWNTs with a variety of chiral indices. Figure 22.4a shows a distribution of the PL peak energies for the single SWNTs, indicated by diamonds [45]. In Figure 22.4b, we show some of the PL spectra from isolated SWNTs with various emission energies [45]. Only a single sharp peak can be seen in each spectrum. The PL linewidth clearly becomes broader as the diameter decreases. This shows that the exciton–phonon interaction is stronger in smaller diameter tubes.

The lowest exciton has fine structures (bright and dark excitons), and the fine structures will determine optical responses and cause unique phenomena. At low temperatures, we observe an interesting phenomenon, spectral diffusion. A few ten percents



FIGURE 22.4 (a) PL peak energy distribution of obtained PL spectra from about 180 different isolated SWNTs. (b) PL spectra for several species of single SWNTs at room temperature. SWNTs with higher PL emission energy tend to have a larger spectral linewidth. (Reprinted from Inoue, T. et al., *Phys. Rev. B*, 73, 233401, 2006. With permission.)

of the nanotubes show spectral diffusion. We consider that spectral diffusion is related to the exciton fine structure, bright and dark excitons. The PL fluctuation due to spectral diffusion is clearly observed at low temperatures. Spectral fluctuation occurs very slowly, the order of several seconds. Figure 22.5a shows a typical temporal evolution of the PL spectrum of SWNT showing spectral fluctuations at 40 K [53]. During spectral diffusion, the PL spectra clearly show two peaks. The lower energy is fitted by Gaussian and the higher energy is Lorentzian. From spectral fitting, we can determine the peak positions and linewidth of both peaks of the PL spectra. Temporal changes in two PL peak energies and linewidths of the lower energy PL band are shown in Figure 22.5b [53]. The higher energy peak is almost constant, but the lower energy peak fluctuates. We find a good correlation between the PL peak energy and the PL linewidth of the lower energy band. When the PL peak shows a low energy, the linewidth becomes wider. To clarify the origin of the spectral diffusion in the lower energy peak, the PL linewidth of the lower energy peaks is plotted as a function of the emission energy. We obtain the square root dependence of the linewidth on the emission energy [53]. This dependence suggests the quantum-confined Stark effect [54]. The spectral diffusion can be explained by the fluctuation of local electric field. The Stark effect causes a redshift in the exciton energy. A small, fast, local electric field fluctuation results from surface charge oscillations. These observations show that the energy splitting between the bright and the dark exciton states is estimated to be about a few meV [53]. This conclusion is well consistent with the magneto-optic results as mentioned before. Detailed understanding of fine structures of the lowest excitons is important for the optoelectronic applications of carbon nanotubes.



FIGURE 22.5 (a) Temporal evolutions of the PL spectrum of a single SWNT showing spectral fluctuations at 40 K. The solid curves indicate the results of fitting analysis assuming Gaussian and Lorentzian functions. (b)Temporal trace of the higher and lower energy peaks of the PL spectra of a single SWNT at 40 K. The temporal trace of the linewidth (FWHM) of the lower energy peaks. (Reprinted from Matsuda, K. et al., *Phys. Rev. B*, 77, 193405, 2008. With permission.)

22.3 Nanoparticle Quantum Dots

Similar spectral diffusion and PL blinking phenomena are also observed in nanoparticle quantum dots. PL blinking phenomenon is quite enhanced in 0D nanoparticles rather than 1D carbon nanotubes. PL blinking in single nanoparticles is caused by a random switching between light-emitting "on" and non-light-emitting "off" states under continuous-wave (cw) laser excitation. Since the first blinking observation in nanoparticles [35], the mechanism of nanoparticles PL blinking has been extensively discussed [55–70]. Ionization of nanoparticles due to nonradiative Auger recombination plays an essential role in PL blinking of single nanoparticles [55]. It is well accepted in this field that PL blinking originates from the photoionization and neutralization of nanocrystals under cw light illumination. In CdSe nanocrystals, for example, the non-light-emitting off-time state is due to positively charged nanoparticles, and the light-emitting on-time state is due to the neutral nanoparticle [55,70]. Spectral fluctuations during on-time suggest that both electrons and holes trapped on the nanoparticle surface cause transient and local electric field fluctuations in the light-emitting neutral nanoparticle. In neutral nanoparticles, excitons recombine radiatively. In ionized (or charged) nanoparticles, the photogenerated excitons and excess holes recombine nonradiatively through fast three-body Auger recombination. The PL blinking means that a nanoparticle repeats the neutralization and ionization under cw laser excitation.

PL blinking behavior is very sensitive to the local surrounding environments. Figure 22.6 shows the PL intensity time traces of a single CdSe nanoparticle on different substrates: glass, rough, and flat Au surfaces [66]. The samples are excited by cw laser at room temperature. The on-off PL blinking behavior is clearly observed on the glass substrate. The time distribution of the on and off states can be characterized by power law functions [57]. The power law distributions suggest that the PL blinking is caused by a very complicated process. On the metal surfaces, on the other hand, the PL off-time is drastically suppressed. The PL blinking suppression indicates that the very rapid neutralization of ionized nanoparticles occurs through the fast energy transfer. However, the enhancement



FIGURE 22.6 PL intensity time-traces of single CdSe/ZnS nanoparticles on the glass (a), the rough Au surface (b), and the flat Au surface (c). The inset of (a) is the histogram of the on-time (solid circles) and off-time (open circles) duration of the PL intensity time trace on the glass. (Reprinted from Matsunaga, R. et al., *Phys. Rev. Lett.*, 101, 147404, 2008. With permission.)



FIGURE 22.7 PL lifetime and PL intensity as a function of the distance between the CdSe nanoparticles monolayer and the Au film. (Reprinted from Ueda, A. et al., *Appl. Phys. Lett.*, 92, 133118, 2008. With permission.)

and quenching of the PL intensity depend on the roughness of the metal surface. On the rough surface, the PL intensity increases. In this experiment, rough Au surfaces are composed of an assembly of hemispherical particles with lateral sizes of 20–50 nm and peaks and valleys of roughly 15 nm. On the flat surface, however, the PL intensity decreases. The enhancement of the PL intensity depends on the excitation laser wavelength. The enhancement spectrum agrees well with the absorption spectrum for localized plasmon resonance [66].

Even on rough Au surfaces, we can observe both enhancement and quenching phenomena of the PL intensity. PL intensity on a rough Au surface depends on the polarization angle of the excitation laser [71]. Electric field enhancement depends on the polarization direction. The PL intensity of a single nanoparticle on glass does not change with the polarization angle. We obtain the microscopic structure of semiconductor nanoparticles and rough surfaces from the polarization and wavelength dependences. Thus, we conclude that the PL intensity enhancement is related to the electric field enhancement due to localized plasmon excitation. Studying PL blinking behaviors is a way to understand energy transfer processes between nanoparticles and surrounding environments.

Close-packed nanoparticle films or nanoparticle arrays show unique exciton energy transfer and charge carrier transport beyond isolated nanoparticles [72–79]. Many different types of closely packed nanoparticle films, arrayed nanoparticle solids, and nanoparticle suprasolids have been prepared [72–79]. In order to control energy transfer between excitons in semiconductors and plasmons in metals, we fabricate metal-semiconductor hetero-nanostructures and their PL spectrum and dynamics. We fabricated two types of semiconductor-metal nanoparticle heterostructures using the Langmuir–Blodgett technique: close-packed CdSe nanoparticle monolayers on Au substrates [80] and mixed CdSe and Au nanoparticle monolayers [81]. In close-packed CdSe nanoparticle monolayers on Au surfaces, the inert polymer thin film was inserted between the nanoparticle monolayer and the Au substrate. The distance between the excitons and plasmons, Δ, is controlled by the polymer thickness. Figure 22.7 summarizes the distance dependence of the PL lifetime and the time-integrated PL intensity [80]. There is a good correlation between the PL decay rate and the PL intensity. PL quenching only occurs when the distance between excitons and plasmons is less than 30 nm. In large distance samples, the PL decay rates in close-packed monolayers are much larger than those in isolated nanoparticles in solutions. The PL lifetime in the CdSe monolayers on the glass is governed by the nonradiative recombination of excitons in nanoparticles and the energy transfer from small to large CdSe nanoparticles, which have lower exciton energies. Furthermore, the PL decay increases with a decrease of the distance between the Au surface and the CdSe nanoparticle monolayer. This can be attributed to energy transfer from nanoparticles to surface plasmons of the Au surfaces. The reduction of both the PL lifetime and the PL intensity simultaneously occurs. PL quenching only occurs in the CdSe nanoparticle monolayer in close proximity to the Au films [80].

Close-packed monolayer films composed of CdSe and Au nanoparticles have simple two-dimensional hexagonal lattices [81]. The PL and optical density of the sample films depend on the Au nanoparticle concentration in the film, because of the spectral overlap between the exciton luminescence of CdSe nanoparticles and the plasmon absorption in Au nanoparticle. In the CdSe and Au nanoparticle mixed monolayer samples, the PL decay curves can be reproduced successfully using three exponential decay components. Three kinds of decay channel of excited states exist in the close-packed CdSe and Au nanoparticle monolayer. In mixed monolayer samples, the decay times are classified into three components: 0.2, 1, and 10 ns, as summarized in Figure 22.8a [81]. These decay times are almost independent of



FIGURE 22.8 (a) Decay time obtained by fitting using the three exponential decays as a function of the Au nanoparticle fraction. The broken lines are guides. (b) Schematic illustration of the configurations of the metal and semiconductor nanoparticles. Direct energy transfer from a nearest-neighbor (nn) CdSe nanoparticle (solid arrow) and from a next-nearest-neighbor (nnn) CdSe nanoparticle [broken arrow]. Stepwise CdSe → CdSe → Au nanoparticle energy transfer [dotted arrow]. (Reprinted from Hosoki, K. et al., *Phys. Rev. Lett.*, 100, 207404, 2008. With permission.)

the Au nanoparticle mixing ratio in the film. The 10-ns decay time originates from radiative recombination within CdSe nanoparticles in the films. As the Au nanoparticle fraction increases, the amplitudes of two 1- and 10-ns components decrease. The amplitude of the fast 0.2-ns decay component becomes dominant. These results indicate that the fast PL quenching is caused by the energy transfer to Au nanoparticles for the CdSe nanoparticles in contact with Au nanoparticles. Here, note that the decay component of about 1 ns is a unique characteristic of close-packed mixed nanoparticles solids. Energy transfer between the nearest-neighbor CdSe nanoparticles takes part in the slow PL quenching process of 1 ns in the mixed film. The 1-ns PL quenching process is the stepwise energy transfer from a CdSe nanoparticle to a CdSe nanoparticle to a Au nanoparticle, as illustrated in Figure 22.8b [81]. Therefore, we conclude that the PL dynamics are explained by three kinds of decay channel. The energy relaxation rate in semiconductor nanoparticles is controlled by changing local surrounding environments. These close-packed nanoparticle heterostructures will show unique exciton energy transfer, and charge carrier transport beyond isolated nanoparticles opens new application fields.

22.4 Multiexciton Generation

Finally, we discuss unique exciton–exciton interactions in nanoparticles and nanotubes. Nanoparticle quantum dots and carbon nanotubes provide an excellent stage for experimental studies of many-body effects of excitons or electrons on optical processes in semiconductors [82–84]. The reduced dielectric screening and the relaxation of the energy–momentum conservation rule in nanostructures enhance the Coulomb carrier–carrier interactions, leading to multi-carrier processes such as the quantized Auger recombination, multiple exciton generation (MEG), carrier multiplication (CM), and so on [7,85]. The achievement of efficient CM in semiconductors makes it possible to produce highly efficient solar cells with conversion efficiencies that exceed the Shockley–Queisser limit of 32% [86]. Strongly confined electrons and excitons in nanomaterials show unique nonlinear optical properties, compared to semiconductor bulk crystals.

Strong interactions between carriers or between excitons cause fast nonradiative Auger recombination of multiple excitons or carriers [82]. Intense interest in Auger recombination in nanoparticles has been stimulated by investigations and searches for new laser and solar cell materials [87–89]. In laser and solar cell applications, nonradiative Auger recombination dominates both the carrier density and the carrier lifetime, determining the device performance. Moreover, in transient absorption, PL, and terahertz conductivity experiments, fast Auger recombination has also been used as a probe in MEG and CM processes [89–96]. The CM efficiencies of nanoparticles are not clear, and the CM mechanism is under discussion. In SWNTs, for example, strong Coulomb interactions enhance the many-body effects of excitons. The fast Auger recombination of excitons has been observed by means of exciton homogeneous linewidth [97] and pump-probe measurements [98–100]. We studied MEG processes in SWNTs at room temperature by temporal change in the carrier density [101]. The fast-decay component grows at increasing excitation intensity. When the photon energy is three times larger than the band-gap energy, Auger recombination occurs efficiently even in the weak intensity region. In our experiment, CM is estimated to be about 1.3 under 4.65 eV excitation [101]. We pointed out that a possible mechanism of CM in carbon nanotubes is the impact ionization. Strong interactions between carriers or between excitons cause unique optical processes in semiconductor nanomaterials. Highly excited semiconductor nanomaterials show new optical functionalities.

22.5 Summary

We briefly discussed luminescence properties of carbon nanotubes and nanoparticle quantum dots by means of single molecular spectroscopy and time-resolved optical spectroscopy. These semiconductor nanomaterials show unique luminescence properties such as spectral diffusion and luminescence blinking. Energy transfer between nanomaterials and surrounding environments affects the PL spectra and dynamics of nanomaterials. Although this chapter is written as a review-type survey of our recent studies, we hope that discussions and many references cited are useful for the readers.

Acknowledgments

The author would like to thank many colleagues and graduate students for their contributions and discussions. In particular, Prof. K. Matsuda deserves mention here. Part of this work was supported by a Grant-in-Aid for Scientific Research on Innovative Area "Optical Science of Dynamically Correlated Electrons (DYCE)" (No. 20104006) from MEXT, Japan, and a Grant-in-Aid for Scientific Research (No. 21340084) from Japan Society for Promotion of Science (JSPS).

References

1. L. Brus: *J. Phys. Chem.* 90, 2555 (1986).
2. Y. Kanemitsu: *Phys. Rep.* 263, 1 (1995).
3. A. P. Alivisatos: *J. Phys. Chem.* 100, 13226 (1996).
4. A. G. Cullis, L. T. Canham, and P. D. J. Calcott: *J. Appl. Phys.* 82, 909 (1997).
5. S. A. Empedocles, R. Neuhauser, K. Shimizu, and M. G. Bawendi: *Adv. Mater.* 11, 1243 (1999).
6. A. P. Alivisatos: *Nat. Biotechnol.* 22, 47 (2004).
7. V. I. Klimov: *J. Phys. Chem. B* 110, 16827 (2006).
8. T. Ando: *J. Phys. Soc. Jpn.* 75, 024707 (2006).
9. D. J. Norris, Al. L. Efros, and S. C. Erwin: *Science*, 319, 776 (2008).
10. Ph. Avouris, M. Freitag, and V. Perebeinos: *Nat. Photon.* 2, 341 (2008).
11. R. Beaulac, P. I. Archer, S. T. Ochsenbein, and D. R. Gamelin: *Adv. Funct. Mater.* 18, 3873 (2008).
12. L. T. Canham: *Appl. Phys. Lett.* 57, 1046 (1990).
13. M. J. O'Connell, S. M. Bachilo, X. B. Huffman, V. C. Moore, M. S. Strano, E. H. Haroz, K. L. Rialon, P. J. Boul, W. H. Noon, C. Kittrell, J. Ma, R. H. Hauge, R. B. Weisman, and R. E. Smalley: *Science* 297, 593 (2002).
14. Y. Kanemitsu, T. Ogawa, K. Shiraishi, and K. Takeda: *Phys. Rev. B* 48, 4883 (1993).
15. C. B. Murray, D. J. Norris, and M. G. Bawendi: *J. Am. Chem. Soc.* 115, 8706 (1993).
16. M. A. Hines and P. Guyot-Sionnest: *J. Phys. Chem.* 100, 468 (1996).
17. X. Peng, M. C. Schlamp, A. V. Kadavanich, and A. P. Alivisatos: *J. Am. Chem. Soc.* 119, 7019 (1997).
18. Z. A. Peng and X. G. Peng: *J. Am. Chem. Soc.* 123, 183 (2001).
19. J. Lefebvre, Y. Homma, and P. Finnie: *Phys. Rev. Lett.* 90, 217401 (2003).
20. A. Nish, J.-Y Hwang, J. Doig, and R. J. Nicholas, *Nat Nanotechnol.* 2, 640 (2007).
21. Y. Kayanuma: *Phys. Rev. B* 38, 9797 (1988).
22. S. V. Gaponenko: *Optical Properties of Semiconductor Nanoparticles* (Cambridge University, Cambridge, U.K., 1998).
23. P. D. J. Calcott, K. J. Nash, L. T. Canham, M. J. Kane, and D. Brumhead: *J. Phys. Condens. Matter* 5, L91 (1993); *J. Lumin.* 57, 257 (1993).
24. T. Itoh, M. Nishijima, A. I. Ekimov, C. Gourdon, Al. L. Efros, and M. Rosen: *Phys. Rev. Lett.* 74, 1645 (1995).
25. N. Nirmal, D. J. Norris, M. Kuno, M. G. Bawendi, Al. L. Efros, and M. Rosen: *Phys. Rev. Lett.* 75, 3728 (1995).
26. Al. L. Efros, M. Rosen, M. Kuno, M. Nirmal, D. J. Norris, and M. Bawendi: *Phys. Rev. B* 54, 4843 (1995).
27. Y. Kanemitsu: *J. Lumin.* 100, 209 (2002).
28. Y. Kanemitsu, S. Okamoto, M. Otobe, and S. Oda: *Phys. Rev. B* 55, R7375 (1997).
29. Y. Kanemitsu and S. Okamoto: *Phys. Rev. B* 58, 9652 (1998).
30. T. Kawazoe and Y. Masumoto: *Phys. Rev. Lett.* 77, 4942 (1996).
31. D. Kovalev, H. Heckler, B. Averboukh, M. Ben-Chorin, M. Schwartzkopff, and F. Koch: *Phys. Rev. B* 57, 3741 (1998).
32. Y. Kanemitsu, H. Tanaka, Y. Fukunishi, T. Kushida, K. S. Min, and H. A. Atwater: *Phys. Rev. B* 62, 5100 (2000).
33. W. E. Moerner: *J. Phys. Chem. B* 106, 910 (2002).
34. S. A. Empedocles, D. J. Norris, and M. G. Bawendi: *Phys. Rev. Lett.* 77, 3873 (1996).
35. N. Nirmal, B. O. Dabbousi, M. G. Bawendi, J. I. Macklin, J. K. Trautman, T. D. Harris, and L. E. Brus: *Nature* 383, 802 (1996).
36. A. Ishizumi, K. Matsuda, T. Saiki, C. W. White, and Y. Kanemitsu: *Appl. Phys. Lett.* 87, 133104 (2005).
37. A. Ishizumi, C. W. White, and Y. Kanemitsu: *Appl. Phys. Lett.* 84, 2397 (2004).
38. S. M. Bachilo, M. S. Strano, C. Kittrell, R. H. Hauge, R. E. Smalley, and R. B. Weisman: *Science* 298, 2361 (2002).
39. F. Wang, G. Dukovic, L. E. Brus, and T. F. Heinz: *Science* 308, 838 (2005).
40. A. Hartschuh, H. N. Pedrosa, L. Novotny, and T. D. Krauss: *Science* 301, 1354 (2003).
41. J. Lefebvre, J. M. Fraser, P. Finnie, and Y. Homma: *Phys. Rev. B* 69, 075403 (2004).
42. K. Matsuda, Y. Kanemitsu, K. Irie, T. Saiki, T. Someya, Y. Miyauchi, and S. Maruyama: *Appl. Phys. Lett.* 86, 123116 (2005).

43. J. Lefebvre, D. G. Austing, J. Bond, and P. Finnie: *Nano Lett.* 6, 1603 (2006).
44. H. Htoon, M. J. O'Connell, P. J. Cox, S. K. Doorn, and V. I. Klimov: *Phys. Rev. Lett.* 93, 027401 (2004).
45. T. Inoue, K. Matsuda, Y. Murakami, S. Maruyama, and Y. Kanemitsu: *Phys. Rev. B* 73, 233401 (2006).
46. R. Matsunaga, K. Matsuda, and Y. Kanemitsu: *Phys. Rev. Lett.* 101, 147404 (2008).
47. H. Ajiki and T. Ando: *J. Phys. Soc. Jpn.* 62, 1255 (1993).
48. S. Zaric, G. N. Ostojic, J. Kono, J. Shaver, V. C. Moore, M. S. Strano, R. H. Hauge, R. E. Smalley, and X. Wei: *Science* 304, 1129 (2004).
49. S. Zaric, G. N. Ostojic, J. Shaver, J. Kono, O. Portugall, P. H. Frings, G. L. J. A. Rikken, M. Furis, S. A. Crooker, X. Wei, V. C. Moore, R. H. Hauge, and R. E. Smalley: *Phys. Rev. Lett.* 96, 016406 (2006).
50. H. Hirori, K. Matsuda, Y. Miyauchi, S. Maruyama, and Y. Kanemitsu: *Phys. Rev. Lett.* 97, 257401 (2006).
51. I. B. Mortimer and R. J. Nicholas: *Phys. Rev. Lett.* 98, 027404 (2007).
52. A. Srivastava, H. Htoon, V. I. Klimov, and J. Kono: *Phys. Rev. Lett.* 101, 087402 (2008).
53. K. Matsuda, T. Inoue, Y. Murakami, S. Maruyama, and Y. Kanemitsu: *Phys. Rev. B* 77, 193405 (2008).
54. S. A. Empedocles and M. G. Bawendi: *Science* 278, 2114 (1997); *J. Phys. Chem. B* 103, 1826 (1999).
55. Al. L. Efros and M. Rosen: *Phys. Rev. Lett.* 78, 1110 (1997).
56. R. G. Neuhauser, K. T. Shimizu, W. K. Woo, S. A. Empedocles, and M. G. Bawendi: *Phys. Rev. Lett.* 85, 3301 (2000).
57. M. Kuno, D. P. Fromm, H. F. Hamann, A. Gallagher, and D. J. Nesbitt: *J. Chem. Phys.* 115, 1028 (2001).
58. F. Koberling, A. Mews, and T. Basché: *Adv. Mater.* 13, 672 (2001).
59. K. T. Shimizu, W. K. Woo, B. R. Fisher, H. J. Eisler, and M. G. Bawendi: *Phys. Rev. Lett.* 89, 117401 (2002).
60. W. G. J. H. M. van Sark, P. L. T. M. Frederix, A. A. Bol, H. C. Gerritsen, and A. Meijerink: *Chem. Phys. Chem.* 3, 871 (2002).
61. M. Kuno, D. P. Fromm, S. T. Johnson, A. Gallagher, and D. J. Nesbitt: *Phys. Rev. B* 67, 125304 (2003).
62. J. Muller, J. M. Lupton, A. L. Rogach, J. Feldmann, D. V. Talapin, and H. Weller: *Appl. Phys. Lett.* 85, 381 (2004).
63. A. Issac, C. von Borczyskowski, and F. Cichos: *Phys. Rev. B* 71, 161302(R) (2005).
64. D. E. Gómez, J. van Embden, and P. Mulvaney: *Appl. Phys. Lett.* 88, 154106 (2006).
65. K. Zhang, H. Chang, A. Fu, A. P. Alivisatos, and H. Yang: *Nano Lett.* 6, 843 (2006).
66. Y. Ito, K. Matsuda and Y. Kanemitsu: *Phys. Rev. B* 75, 033309 (2007).
67. Y. Ito, K. Matsuda, and Y. Kanemitsu: *J. Phys. Soc. Jpn.* 77, 103713 (2008).
68. P. Frantsuzov, M. Kuno, B. Janko, and R. A. Marcus: *Nat. Phys.* 4, 519 (2008).
69. F. Stefani, J. Hoogenboom, and E. Barkal: *Phys. Today* 62(2), 34 (2009).
70. T. D. Krauss and L. E. Brus: *Phys. Rev. Lett.* 83, 4840 (1999).
71. K. Matsuda, Y. Ito, and Y. Kanemitsu: *Appl. Phys. Lett.* 92, 211911 (2008).
72. C. M. Murray, C. R. Kagan, and M. G. Bawendi: *Science* 270, 1966 (1995).
73. C. A. Leatherdale, C. R. Kagan, N. Y. Morgan, S. A. Empedocles, M. A. Kastner, and M. G. Bawendi: *Phys. Rev. B* 62, 2669 (2000).
74. M. P. Pileni: *J. Phys. Chem. B* 105, 3358 (2001).
75. C. R. Kagan, C. B. Murray, M. Nirmal, and M. G. Bawendi: *Phys. Rev. Lett.* 76, 1517 (1996).
76. C. R. Kagan, C. B. Murray, and M. G. Bawendi: *Phys. Rev. B* 54, 8633 (1996).
77. S. A. Crooker, J. A. Hollingsworth, S. Tretiak, and V. I. Klimov: *Phys. Rev. Lett.* 89, 186802 (2002).
78. M. Achermann, M. A. Petruska, S. A. Crooker, and V. I. Klimov: *J. Phys. Chem. B* 107, 13782 (2003).
79. O. I. Mićić, K. M. Jones, A. Cahill, and A. J. Nozik: *J. Phys. Chem. B* 102, 9791 (1998).
80. A. Ueda, T. Tayagaki, and Y. Kanemitsu: *Appl. Phys. Lett.* 92, 133118 (2008).
81. K. Hosoki, S. Yamamoto, T. Tayagaki, K. Matsuda, and Y. Kanemitsu: *Phys. Rev. Lett.* 100, 207404 (2008).
82. V. I. Klimov, A. A. Mikhailovsky, D. W. McBranch, C. A. Leatherdale, and M. G. Bawendi: *Science* 287, 1011 (2000).
83. V. I. Klimov, A. A. Mikhailovsky, S. Xu, A. Malko, J. A. Hollingsworth, C. A. Leatherdale, H. J. Eisler, and M. G. Bawendi: *Science* 290, 314 (2000).
84. Y. Kanemitsu, T. J. Inagaki, M. Ando, K. Matsuda, T. Saiki, and C. W. White: *Appl. Phys. Lett.* 81, 141 (2002).
85. A. J. Nozik: *Chem. Phys. Lett.* 457, 3 (2008).
86. W. Shockley and H. J. Queisser: *J. Appl. Phys.* 32, 510 (1961).
87. V. I. Klimov, S. A. Ivanov, J. Nanda, M. Achermann, I. Bezel, J. A. McGuire, and A. Piryatinski: *Nature* 447, 441 (2007).
88. T. Tayagaki, S. Fukatsu, and Y. Kanemitsu: *Phys. Rev. B* 79, 041301(R) (2009).
89. R. D. Schaller and V. I. Klimov: *Phys. Rev. Lett.* 92, 186601 (2004).
90. R. Ellingson, M. C. Beard, J. C. Johnson, P. Yu, O. I. Micic, A. J. Nozik, A. Shabaev, and A. L. Efros: *Nano Lett.* 5, 865 (2005).
91. M. C. Beard, K. P. Knutsen, P. Yu, J. M. Luther, Q. Song, W. K. Metzger, R. J. Ellingson, and A. J. Nozik: *Nano Lett.* 7, 2506 (2007).
92. G. Nair and M. G. Bawendi: *Phys. Rev. B* 76, 081304(R) (2007).
93. V. I. Klimov, J. A. McGuire, R. D. Schaller, and V. I. Rupasov: *Phys. Rev. B* 77, 195324 (2008).
94. G. Nair, S. M. Geyer, L. Y. Chang, and M. G. Bawendi: *Phys. Rev. B* 78, 125325 (2008).

95. J. J. H. Pijpers, E. Hendry, M. T. W. Milder, R. Fanciulli, J. Savolainen, J. L. Herek, D. Vanmaekelbergh, S. Ruhman, D. Mocatta, D. Oron, A. Aharoni, U. Banin, and M. Bonn: *J. Phys. Chem. C* 111, 4146 (2007); 112, 4783 (2008).
96. M. T. Trinh, A. J. Houtepen, J. M. Schins, T. Hanrath, J. Piris, W. Knulst, A. P. L. M. Goossens, and L. D. A. Siebbeles: *Nano Lett*. 8, 1713 (2008).
97. K. Matsuda, T. Inoue, Y. Murakami, S. Maruyama, and Y. Kanemitsu: *Phys. Rev. B* 77, 033406 (2008).
98. F. Wang, G. Dukovic, E. Knoesel, L. E. Brus, and T. F. Heinz: *Phys. Rev. B* 70, 241403(R) (2004).
99. F. Wang, Y. Wu, M. S. Hybertsen, and T. F. Heinz: *Phys. Rev. B* 73, 245424 (2006).
100. Y.-Z. Ma, L. Valkunas, S. L. Dexheimer, S. M. Bachilo, and G. R. Fleming: *Phys. Rev. Lett*. 94, 157402 (2005).
101. A. Ueda, K. Matsuda, T. Tayagaki, and Y. Kanemitsu: *Appl. Phys. Lett*. 92, 233105 (2008).

23

Nanoscale Excitons and Semiconductor Quantum Dots

Vanessa M. Huxter
University of Toronto

Jun He
University of Toronto

Gregory D. Scholes
University of Toronto

23.1 Introduction to Nanoscale Excitons **23**-1
23.2 Nonlinear Optical Properties of Semiconductor Quantum Dots **23**-5
23.3 Two-Photon Absorption in Semiconductor Quantum Dots **23**-6
Biological Imaging • Amplified Stimulated Emission and Lasing • Optical Power Limiting • Two-Photon Sensitizer
23.4 Conclusion **23**-8
References **23**-8

23.1 Introduction to Nanoscale Excitons

The optical properties of nanoscale excitons are of interest to researchers because their size tunability makes them of practical use; however, understanding the nature of these delocalized electronic states is a challenge (Scholes and Rumbles 2006, 2008). Nanoscale excitons are the electronic excited states formed by the absorption of light by nanoscale systems. A nanoscale system is any chemical or physical system that is in the nanometer-size regime. The kinds of systems that are the subject of this chapter tend to have properties lying between those of molecules and those of bulk semiconductors. Unlike excitons in bulk semiconductors, the energies of nanoscale excitons can often be changed by the size of the system. That property is envisioned, for example, to allow the color of solid-state lasers to be tuned.

Well-studied examples of nanoscale systems include semiconductor nanocrystals, carbon nanotubes (CNTs), organic conjugated polymers, and molecular aggregates, shown in Figure 23.1. The excitons in quantum dots and CNTs are closely related to molecular excited states; however, the size of the nanoscale systems has forced researchers to make severe approximations in their quantum-mechanical descriptions. Nonetheless, the excited states of nanoscale systems tend to be more amenable to approximate descriptions than molecules because the wavefunction delocalization reduces the importance of the electron correlation for an accurate calculation of the energies of electronic states. Such electronic excited states are often described as Wannier–Mott excitons (Banyai and Koch 1993; Basu 1997; Gaponenko 1998; Jorio et al. 2008). Other systems, like molecular aggregates, crystals, and certain proteins—namely, those involved in photosynthetic energy transduction—have optical properties that are better described with reference to the molecular building blocks of the aggregate. The lowest electronic excited states of these aggregates are called Frenkel excitons (Kasha 1976). Conjugated polymers, now used in organic light-emitting diodes and displays (OLEDs), have excited states somewhere between these limits (Sariciftci 1997; Hadziioannou and Malliaras 2006). This relationship is illustrated in Figure 23.2.

In the limiting case of Wannier–Mott excitons, it is assumed that the electronic interaction between the building blocks of the system—the atoms or unit cells—is large, akin to a chemical bond. In this case, orbitals that are delocalized over an entire system are a good starting point for describing one-electron states. Photoexcitation introduces an electron into the conduction orbitals, leaving a "hole" in the valence orbitals. The Wannier–Mott description assumes that there are many electrons in the system, so the atomic centers are highly screened from the outermost electrons, that is, the dielectric constant is high. In that case, it is considered reasonable to assume that the electron and the hole move freely in the background dielectric continuum and are weakly bound. The strength of this electron–hole attraction determines the "binding" of the lower energy, optically allowed states compared to the dense manifold of charge carrier states that lie higher in energy. In this model, the electron and the hole move under their mutual attraction in a dielectric continuum, and then the exciton energy levels are found as a series analogous to the states of the hydrogen atom. Note that this model can be useful, but it must be realized that it is highly approximate (Scholes 2008b), and it is only able to give limited insights. The conceptual advantage of this model is that it converges to the free carrier limit where the electron-hole attraction is negligible compared to the thermal energies. It can thereby be seen how the photoexcitation of a bulk semiconductor exciton efficiently produces charge carriers, which is how a typical semiconductor solar cell works.



FIGURE 23.1 **(See color insert following page 20-14.)** Excitons and structural size variations on the nanometer length scale. (a) The photosynthetic antenna of purple bacteria, LH2, is an example of a molecular exciton. The absorption spectrum clearly shows the dramatic distinction between the B800 absorption band, arising from essentially "monomeric" bacteriochlorophyll-a (Bchl) molecules, and the redshifted B850 band that is attributed to the optically bright lower exciton states of the 18 electronically coupled Bchl molecules. (b) The size-scaling of polyene properties, for example, oligophenylenevinylene oligomers, derives from the size-limited delocalization of the molecular orbitals. However, as the length of the chains increases, disorder in the chain conformation impacts the picture for exciton dynamics. Absorption and fluorescence spectra are shown as a function of the number of repeat units. (c) SWCNT size and "wrapping" determine the exciton energies. Samples contain many different kinds of tubes, therefore optical spectra are markedly inhomogeneously broadened. By scanning excitation wavelengths and recording a map of fluorescence spectra, the emission bands from various different CNTs can be discerned, as shown. (Courtesy of Dr. M. Jones). (d) Rather than thinking in terms of delocalizing the wavefunction of a semiconductor through interactions between the unit cells, the small size of the nanocrystal confines the exciton relative to the bulk. Size-dependent absorption spectra of PbS quantum dots are shown. (Adapted from Scholes, G. D. and Rumbles, G., *Nat. Mater.*, 5, 683, 2006.)

In order to further understand the formation of excitons in nanoscale systems, we will examine the case of semiconductors as a model system. The optical properties of semiconductor nanostructures lie in an intermediate regime between a molecular and a bulk description. In a bulk semiconductor, the dimensions of the system are practically infinite compared to the dimensions of the carriers (electrons and holes). In this case, the wavefunctions, which are standing waves in the material, are spread over an infinite number of unit cells (the repeat unit in a crystal), and the carriers (electrons and holes) are free particles. The density of states for the bulk material is continuous, as shown in Figure 23.3a. Note that in the case of a bulk semiconductor, the density of states for both the hole and the electron are continuous. These two continuous regions are separated by


Delocalized basis
Localized basis
NH
N
HN
Wannier excitons
Frenkel/Davydov excitons
O
*
n
Quantum dots
Conjugated organic materials
Supramolecular assemblies

FIGURE 23.2 Collective properties of nanoscale materials modify the optical properties, such as the wavelength and the dipole strength for light absorption. The elementary excitations are known as excitons. Excitons are formed through the collective absorption of light by two or more repeat units in a crystal, a molecular assembly, or a macromolecule. Wannier excitons are typical of atomic crystals, semiconductor quantum dots, aromatic molecules, CNTs, conjugated polymers, and so on. Supramolecular assemblies, including J-aggregates and photosynthetic light-harvesting antennae, typify Frenkel excitons—excitons in which the repeat units retain their identity to a significant degree.



FIGURE 23.3 Idealized representation of the density of electron states for (a) a bulk semiconductor system (3D) and a semiconductor system confined in (b) one dimension (a 2D system), (c) confined in two dimensions (a 1D system) and (d) confined in all three dimensions (a 0D system). In the bulk case, the energy levels form a continuous band. With increasing confinement, the density of states becomes more discrete, resulting in the delta functional form of the density of states in the 0D case.

the bandgap in which the density of states goes to zero for an ideal system. The bulk system is infinite in all three dimensions. The effect of spatially confining the electrons and holes in one, two, or three of those dimensions is to change the density of states. The spatial confinement of the electrons and holes in one dimension means that the wavefunctions of those particles are quantized in that same one dimension. However, the electrons and holes are not confined and can move freely in the other two dimensions. This is similar to the concept of a plane as a two-dimensional object in a three-dimensional space. Examples of these two-dimensional systems with a spatial confinement in one dimension are nanometer-height thin films and quantum wells. The quantization of the electrons and holes in one dimension changes the density of states from the bulk continuum to a step-type function, as shown in Figure 23.3b. Similarly, spatial confinement of the electrons and holes in two dimensions results in the quantization of the particles in those same two dimensions. In these systems, called quantum wires, the electrons and the holes can only move freely in one dimension. The quantization in two of three dimensions results in a further change in the density of states, which becomes more discrete with individual peaks as shown in Figure 23.3c. Finally, the spatial confinement of the electron and the hole in all three dimensions results in quantization in all three dimensions. In this case, the density of states is discrete and takes the form of delta functions, as shown in Figure 23.3d. These systems are called quantum dots and are discussed in more detail later in this chapter.

The physical confinement in one, two, or three dimensions changes the boundary conditions imposed on the wavefunctions and quantizes the behavior of the electrons and holes in one, two, or three dimensions. The boundary conditions associated with the spatial confinement of the wavefunctions, in turn, modify the density of states. The resulting change in the density of states from a continuous band in the bulk to discrete levels in a quantum dot is analogous to the particle in a box model in quantum mechanics. The physical dimensions required to spatially confine the electron or the hole depend on the size of the electron and hole wavefunctions. These are determined by the physical properties of the specific material and are usually on the order of one to tens of nanometers.

The quantum confinement of the electron and the hole wavefunctions modifies their interaction. The spatially overlapped electron and hole wavefunctions can associate through an energy-lowering Coulomb interaction due to their relative negative and positive charges, forming an exciton. This association can be described in analogy to a hydrogen atom and, as such, the size of the exciton is described using a Bohr radius. Just like the hydrogen atom, the lowest energy set of states is comprised of closely bound electron-hole pair configurations. These are the bound exciton states, which are the optically active states of the system (those that absorb and emit light). They tend to be clearly distinguished from a band of many higher energy states, which do not absorb light, but are the nanoscale-free carrier states (Scholes 2008b).

The energy separation between the lowest energy-exciton states and the onset of the carrier states is called the exciton-binding energy. We can think of the exciton-binding energy as the energy required to ionize an exciton. Notably, this ionization energy is significantly reduced compared to small, molecular systems because of the many different ways that the electron and the hole can be separated. The exciton-binding energy, meditated by an attractive Coulomb interaction, can also be thought of as the energy reduction associated with forming an exciton as compared to the energies of the free electron and hole confined in the three-dimensional potential. This exciton-binding energy shifts the positions of the energy levels. The exciton in a three-dimensional potential and the associated exciton levels are shown in Figure 23.4.



FIGURE 23.4 Confining the electron and the hole in a potential results in the formation of a hydrogen-like exciton and bound exciton states. The binding of the exciton is mediated through the Coulomb interaction.

The binding energy of excitons is a topic of widespread interest, especially because of its relevance to photovoltaic science. In high dielectric constant bulk-semiconductor materials the exciton-binding energy is typically small: 27 meV for CdS, 15 meV for CdSe, 5.1 meV for InP, and 4.9 meV for GaAs. The small exciton-binding energies of these materials make them well-suited for photovoltaic applications because the optically active exciton states absorb light, then the ambient thermal energy (~25 meV) is sufficient to convert the exciton to free carriers. Thus, the potential energy of the absorbed photon is converted to an electrical potential. On the other hand, in molecular materials, the electron-hole Coulomb interaction is substantial—usually a few eV. In nanoscale materials, we find a middle ground where exciton-binding energies are significant in magnitude—that is, excitons are important.

As an example, the valence and the conduction orbitals of a single-wall carbon nanotube (SWCNT) are shown in Figure 23.5. These are typical 1D densities-of-states as were introduced in Figure 23.3. If the electrons were non-interacting, then the lowest excitation energy of a SWCNT would be the same as the energy gap between the highest valence orbital and the lowest conduction orbital. In fact, this is the energy corresponding to the onset of carrier formation. Suitable quantum-chemical calculations introduce interactions between the electrons in these various orbitals, which captures the electron-hole attraction and thus leads to a significant stabilization of the excited states relative to



FIGURE 23.5 The attractive interaction of electrons and holes in a CNT (represented by the model at the top of the figure) results in the formation of excitons. This stabilizes the excited states relative to the orbital energy difference, lowering the energy of the optical gap.

those estimated with the more primitive model of orbital energy differences. That gives the correct energy of the optical absorption bands. The energy difference between the orbital energy difference and the optical gap is the exciton-binding energy. It has been predicted for SWCNTs to be ~0.3–0.5 eV (Zhao and Mazumdar 2004), which was later confirmed by an experiment (Ma et al. 2005; Wang et al. 2005).

As a result of the nature of excitons, the optical properties of nanoscale systems provide an interesting link between the properties of extended "bulk" systems and those of molecules. The study of excitons provides the opportunity for new insights into the behavior of nanoscale systems. For the rest of this chapter, we will focus on the properties of a particular nanoscale system: semiconductor quantum dots.

23.2 Nonlinear Optical Properties of Semiconductor Quantum Dots

Quantum-confined semiconductor nanocrystals, or quantum dots, have been the focus of intense study over the past three decades due to their size-tunable optical properties and unique physical characteristics. This area of research was founded in the early 1980s when researchers at Bell Laboratories (Rossetti et al. 1983) in the United States and the Yoffe Institute (Ekimov et al. 1980, Ekimov and Onushchenko 1982; Efros and Efros 1982) in Russia (then the U.S.S.R) independently described the properties of nanometer-sized semiconductor quantum dots. This work was quickly followed by studies on colloidal samples (Spanhel et al. 1987), leading to a further understanding of the optical and physical properties of quantum dots. Within less than a decade, a basic theoretical framework to describe the observed properties had been proposed and work was underway to explore the fundamental physics of these materials.

Much of the early work on quantum dots focused on semiconductor-doped glasses. These materials are characterized by broad size distributions and offer no possibility of control over the shape or the interface characteristics of the particles. The limitations of these doped glasses, particularly the broad size distribution that results in a large static inhomogeneity, masked many of the fundamental physical processes that were occurring in the quantum dots. However, the study of quantum dot systems underwent a revolution in 1993 when it was discovered that nucleation and a controlled growth of colloidal semiconductors could be achieved by injecting highly reactive organometallic precursors into a solvent system that coordinates to the colloid surface (Murray et al. 1993). This coordinating solvent, trioctylphosphine oxide, was an important discovery because it serves to arrest growth and stabilize the nanocrystals. This method allowed a simple and reproducible synthesis of high quality, nearly monodisperse cadmium chalcogenide nanocrystal samples. This development led to an explosion in the field and opened new avenues for research and technology including increased processibility, the possibility of mass production, and chemical manipulation for tailored shape control. In particular, this reliable method of making high-quality samples allowed the exploration of phenomena that had been previously unobservable due to static inhomogeneity associated with broad size distributions.

In addition to doped glasses and colloidal samples, there are epitaxially grown quantum dots. While colloidal nanocrystals tend to be sized in the range of 1–10 nm in diameter, epitaxial dots, which are grown on solid substrates, may be a couple of nanometers in height but with lateral dimensions of tens of nanometers. The physics of these materials differ from colloidal samples in some fundamental ways; however, the basic properties associated with quantum-confined nanocrystals apply to all three types of quantum dots. Different aspects of these properties have been explored in many comprehensive reviews. For instance, a review of the electronic properties was presented by Yoffe (1993, 2001). The optical nonlinearities of semiconductor nanocrystals were reviewed by Banfi's group (Banfi et al. 1998). Research on semiconductor quantum dots has evolved from fundamental science (Alivisatos 1996; Empedocles and Bawendi 1997; Klimov 2000; Klimov et al. 2000a,b) to lasing and amplification (Klimov 2006; Klimov et al. 2007), optical power limiting (He et al. 2007a,b), biological imaging (Bruchez et al. 1998; Dubertret et al. 2002; Larson et al. 2003; Michalet et al. 2005) and labeling (Seydack 2005), sensitization (Dayal and Burda 2008), and optical switching (Etienne et al. 2005; He et al. 2005a).

One of the defining features of a semiconductor is the bandgap, which separates the conduction band and the valence band. When a semiconductor material absorbs light, an electron is promoted from the valence to the conduction band. The wavelength of light absorbed and emitted from a semiconductor material is determined by the width of the bandgap. In semiconductors, when an electron moves from the valence to the conduction band, the resulting gap left in the valence band is called a hole. An exciton can be formed through an energy-lowering Coulomb interaction between the negative electron and the positive hole. In analogy with the hydrogen atom, the spatial extent of the exciton wavefunction is described by a quantity called the exciton Bohr radius. As a result of the three-dimensional spatial confinement of the exciton wavefunction, the density of states becomes discrete, as described earlier in the chapter. The position of these states, and therefore the energy of the gap, depends on the spatial confinement of the exciton, which is determined by the physical size of the nanocrystal. To a first approximation, this quantum-confinement effect can be described using the particle in a box or a simple quantum box model (Efros and Efros 1982; Brus 1984), in which the electron motion is restricted in all three dimensions by impenetrable walls. For a spherical nanocrystal with radius R, the quantum box model predicts that the size-dependence of the energy gap is proportional to $1/R^2$, indicating that the energy of the lowest transition increases as the nanocrystal size decreases. In addition, as described above, quantum confinement changes the continuous energy bands of a bulk semiconductor into discrete exciton energy levels. The exciton energy levels produce peaks in the absorption spectrum of quantum dots, which is in contrast to the continuous absorption spectrum of a bulk semiconductor (Alivisatos 1996).

The colloidal quantum dots discussed here are composed of a semiconductor core surrounded by a shell of organic ligand molecules (Murray et al. 1993). The organic capping prevents the uncontrolled growth and agglomeration of the nanoparticles. It also allows quantum dots to be chemically manipulated as if they were large molecules, with solubility and chemical reactivity determined by the identity of the organic molecules. The capping also provides an electronic passivation of the nanocrystals by terminating the dangling bonds on the surface. The unterminated dangling bonds can affect the emission efficiency of the quantum dots because they lead to a loss mechanism where electrons are rapidly trapped at the semiconductor surface before they have a chance to emit photons. Using colloidal chemical synthesis, one can prepare nanocrystals with nearly atomic precision with diameters ranging from nanometers to tens of nanometers and a size dispersion as narrow as 5% standard deviation. Because of the quantum-confinement effect, the ability to tune the size or shape of the nanocrystals translates into a means of controlling their optical properties, such as the absorption and emission wavelengths (Scholes and Rumbles 2006; Scholes 2008a).

In a quantum dot system, the three-dimensional confinement modifies the Hamiltonian, adding a potential that restricts how far apart the electron and the hole can be. This forced spatial overlap changes the density of states as described earlier in the chapter. The interaction between the confined electron and the hole, mediated by a Coulomb potential, leads to the formation of an exciton, which can be described in analogy to a hydrogen atom where an electron interacts with a nucleus. As a result of the discrete character of the density of states in quantum dots, as shown in Figure 23.3d, the oscillator strength is concentrated into those few transitions instead of being spread over a continuum of states. This means that the oscillator strength of the states in quantum dots is significantly enhanced. The concentration of the oscillator strength into a few transitions also enhances the nonlinear optical properties of quantum dots as compared to the bulk (Shalaev et al. 1996). As a result of their enhanced nonlinear optical properties, synthetically controllable size tunability and photostability, quantum dots continue to be of great interest both for fundamental research and device applications. One of these areas of research involves nonlinear two-photon absorption (2PA).

23.3 Two-Photon Absorption in Semiconductor Quantum Dots

Two-photon absorption in semiconductors is the simultaneous absorption of two photons of identical or different frequencies required to move an electron from the valence to the conduction band. As opposed to the linear intensity dependence of one-photon absorption (1PA), 2PA depends on the square of the light intensity. Therefore, 2PA is a third-order nonlinear optical process and many orders of magnitude weaker than 1PA. The 2PA coefficient, β, is directly related to the imaginary part of the third-order nonlinear susceptibility, $\chi^{(3)}$, by $\beta = 3\pi \mathrm{Im}\,\chi^{(3)}/(\lambda n_0^2 c \varepsilon_0)$, where n_0 is the linear refractive index, ε_0 is the dielectric constant in vacuum, λ the laser wavelength, and c the speed of light in vacuum (Sutherland 2003). Compared to 1PA, 2PA is associated with different selection rules for dipole transitions. For example, in CdSe quantum dots, one-photon transitions satisfy selection rules $\Delta L = 0, \pm 2$ and $\Delta F = 0, \pm 1$ while two-photon transitions satisfy $\Delta L = \pm 1, \pm 3$ and $\Delta F = 0, \pm 1, \pm 2$, where L is the orbital angular momentum of the envelope wavefunction and F is the total angular momentum (Schmidt et al. 1996). Therefore, the comparison between 1PA and 2PA spectra allows a more detailed optical analysis of electronic states in semiconductor quantum dots (Schmidt et al. 1996). For direct bandgap semiconductor quantum dots, a simple theory based on the effective mass approximation was proposed for both 1PA and 2PA (Fedorov et al. 1996). Although this simple model does not consider the mixing between the heavy and light holes bands, it works quite well for describing degenerate 2PA. Recently, this theory has been extended to obtain the analytical expressions for both degenerate and nondegenerate 2PA spectra of semiconductor quantum dots with the parabolic band approximation and $\vec{k}\cdot\vec{p}$ theory (Padilha et al. 2007).

As the incident laser intensity increases, the 2PA in semiconductor quantum dots will be saturated due to the limited density of states of the quantized energy levels (He et al. 2005b). If the allowed 2PA transitions are assumed to occur between the one atomic-like energy level in the conduction band and the other in the valence band, the ensemble of quantum dots can be approximately treated as a two-level system. Since the semiconductor quantum dots are not uniform in size, the saturation of 2PA for such an inhomogeneous system may be derived as $\beta(I) = \beta / \sqrt{1 + I_0^2 / I_{\mathrm{s,2PA}}^2}$ (Sutherland 2003). The saturation intensity, $I_{\mathrm{s,2PA}}$, in quantum dots can be described quantitatively by an inhomogeneously broadened, saturated 2PA model as (He et al. 2005b)

$$I_{\mathrm{s,2PA}}^2 = \frac{\hbar\omega\pi\Delta\omega p(2\omega)N_0}{{}_p\sqrt{\pi/2}\left(1 + \frac{g_k}{g_n}\right)\beta} \frac{g_k}{g_n} \tag{23.1}$$

where

$g_k(g_n)$ is the electronic degeneracy of the upper (lower) state
τ_{p} is the half width at the maximum of the femtosecond laser pulse
$\hbar\omega$ is the photon energy
N_0 is the number density of the quantum dots in the sample material
$p(2\omega)$ is the probability of a homogeneous class of absorbers with a central frequency of 2ω

The quantity $\Delta\omega$ is related to the dephasing time (T_2) of the excitation, i.e., the width of the homogeneous line shape.

Two-photon transition does not involve a real intermediate state. The single photon energy is less than that of the quantum dots bandgap. So 2PA is a non-resonant optical nonlinearity. The 2PA coefficients, β, can be determined by two-photon excited fluorescence, nonlinear transmission, Z scan, and pump-probe techniques (Sutherland 2003). For example, the differential equation describing the intensity change in a one-photon transparent but two-photon absorbing material is given by $dI_0/dz = -\beta I_0^2$, where I_0 is the peak intensity of the input laser beam inside the sample. The nonlinear transmission in such a material, excited by a focused continuous-wave (cw) Gaussian beam, can be expressed as follows (Sutherland 2003):

$$T(I_0) = \frac{\left[\ln(1 + \beta l I_0)\right]}{(\beta l I_0)} \tag{23.2}$$

where l is the thickness of the quantum dot sample. A comparison of the expressions for the energy transmittance of a cw top-hat, pulsed Gaussian and sech^2 beam are available in Sutherland (2003). From Equation 23.2 one can see that at a given input intensity (I_0) level, if the nonlinear transmission value is measured, the β value can be readily determined. The 2PA coefficient β is a macroscopic parameter characterizing the quantum dot composite material. The intrinsic 2PA coefficient of quantum dots, β_{QD}, can be derived as $\beta_{\mathrm{QD}} = \beta_{\mathrm{composite}} n_{0,\mathrm{composite}}^2 / \left(n_{0,\mathrm{QD}}^2 f_{\mathrm{v}} |f|^4\right)$, where f_{v} is the volume fraction of the quantum dots in the matrix and $f = 3n_{0,\mathrm{matrix}}^2 / (n_{0,\mathrm{QD}}^2 + 2n_{0,\mathrm{matrix}}^2)$ is the local field correction that depends on the dielectric constant of the quantum dots and the matrix material. In addition, the 2PA cross section can be calculated by the use of the definition: $\sigma_2 = \beta\hbar\omega/N_0$.

Two-photon absorption in semiconductor quantum dots has many important potential applications, some of which are discussed in more detail below.

23.3.1 Biological Imaging

Using quantum dot labeling, 2PA provides a possible way of performing biological imaging that is not possible by traditional one-photon methods as visible wavelengths cannot penetrate human tissue. As tagging materials, semiconductor quantum dots have advantages over fluorescent dyes, such as broad excitation and narrow emission bands, emission wavelength tunability, photostability, and enhanced brightness. The 2PA in robust water-soluble CdSe/ZnS core-shell quantum dots was found to be well-suited for use as fluorescent labels in multiphoton microscopy for biological imaging (Larson et al. 2003). The near-infrared two-photon excitation of such quantum dots in the "tissue optical window" (0.7–1.1 μm), in which water and hemoglobin absorb very little light, allows the extensive imaging of living systems, making further developments in medical diagnostics possible.

23.3.2 Amplified Stimulated Emission and Lasing

Quantum dot lasers have potential advantages, such as a temperature-insensitive lasing threshold and wide-range color tunability. Due to the quantum-size confinement, the 2PA cross-sections in semiconductor quantum dots are enhanced compared to the corresponding bulk material. This allows for a lower lasing threshold with a 2PA pumping mechanism. In addition, quantum dot lasers with 2PA excitation in the "tissue optical window" have important application prospects on laser-assisted biological-medical diagnostics and therapy. Recently, upconverted laser emission from a solution-processed CdSe/CdS/ZnS quantum dot waveguide-resonant cavity has been successfully demonstrated with femtosecond excitation at a wavelength of 800 nm (Zhang et al. 2008).

23.3.3 Optical Power Limiting

Optical power limiting and stabilization can be used to protect sensitive equipment or to control noise in laser beams (He et al. 2008). In this case, the output laser intensity approaches a constant value when the input intensity increases beyond a certain threshold, limiting the amount of optical power entering a system. Compared to optical-limiting materials based on organic chromophores, crystals, and polymers, semiconductor quantum dots have a large 2PA cross section and better photostability.

23.3.4 Two-Photon Sensitizer

Semiconductor quantum dots are excellent sensitizers for near-infrared 2PA due to their large and size-tunable 2PA cross sections. For example, quantum dots linked to phthalocyanines

(Pcs) can be excited using the 2PA of the quantum dots without any significant direct excitation of Pc molecules. In this case, Pcs are electron acceptor molecules, and a near-infrared excitation of the Pc molecules within the spectral therapeutic window (0.7–1.2 μm) can be realized via a two-photon sensitization of the quantum dot followed by an energy transfer to the Pc (Dayal and Burda 2008).

23.4 Conclusion

Excitons in nanoscale systems, particularly in semiconductor quantum dots, provide a link between the bulk and the molecular regimes. In quantum dots, the discrete density of states associated with the exciton results in an increased oscillator strength in the optically active levels and an increased nonlinear cross section. The increased nonlinear optical properties of quantum dots provide an opportunity for novel devices and experimental applications including those associated with 2PA. The unique properties of nanoscale excitons and the materials associated with them will provide inspiration and direction to future research.

References

Alivisatos, A. P. 1996. *Science* 271: 933.

Banfi, G. P., Degiorgio, V., and Ricard, D. 1998. *Adv. Phys*. 47: 447.

Banyai, L. and Koch, S. W. 1993. *Semiconductor Quantum Dots*. River Edge, NJ: World Scientific.

Basu, P. K. 1997. *Theory of Optical Processes in Semiconductors: Bulk and Microstructures*. New York: Oxford University Press.

Bruchez, M., Moronne, M., Gin, P., Weiss, S., and Alivisatos, A. P. 1998. *Science* 281: 2013.

Brus, L. E. 1984. *J. Chem. Phys*. 80: 4403.

Dayal, S. and Burda, C. 2008. *J. Am. Chem. Soc*. 130: 2890.

Dubertret, B., Skourides, P., Norris, D. J. et al. 2002. *Science* 298: 1759.

Efros, Al. L. and Efros, A. L. 1982. *Semiconductors* 16: 1209–1214.

Ekimov, A. I. and Onushchenko, A. A. 1982. *Semiconductors* 16: 1215–1219.

Ekimov, A. I., Onushchenko, A. A., and Tsekhomskii, V. A. 1980. *Sov. Glass Phys. Chem*. 6: 511–512.

Empedocles, S. A. and Bawendi, M. G. 1997. *Science* 278: 2114.

Etienne, M., Biney, A., Walser, A. D. et al. 2005. *Appl. Phys. Lett*. 87: 181913.

Fedorov, A. V., Baranv, A. V., and Inoue, K. 1996. *Phys. Rev. B* 54: 8627.

Gaponenko, S. V. 1998. *Optical Properties of Semiconductor Nanocrystals*. New York: Cambridge University Press.

Hadziioannou, G. and Malliaras, G. G. eds. 2006. *Semiconducting Polymers: Chemistry, Physics and Engineering*, Weinheim, Germany: Wiley-VCH.

He, J., Ji, W., Ma, G. H. et al. 2005a. *J. Phys. Chem. B* 109: 4373.

He, J., Mi, J., Li, H. P., and Ji, W. 2005b. *J. Phys. Chem. B* 109: 19184.

He, G. S., Yong, K. T., Zheng, Q. et al. 2007a. *Opt. Express* 15: 12818.

He, G. S., Zheng, Q., Yong, K. T. et al. 2007b. *Appl. Phys. Lett*. 90: 181108.

He, G. S., Tan, L., Zheng, Q., and Prasad, P. N. 2008. *Chem. Rev*. 108: 1245.

Jorio, A., Dresselhaus, M. S., and Dresselhaus, G. 2008. *Carbon Nanotubes: Advanced Topics in Synthesis, Structure, Properties and Applications*. New York: Springer.

Kasha, M. 1976. Molecular excitons in small aggregates. In *Spectroscopy of the Excited State*, ed. B. DiBartolo. New York: Plenum Press.

Klimov, V. I. 2000. *J. Phys. Chem. B* 104: 6112.

Klimov, V. I. 2006. *J. Phys. Chem. B* 110: 16827.

Klimov, V. I., Mikhailovsky, A. A., McBranch, D. W., Leatherdale, C. A., and Bawendi, M. G. 2000a. *Science* 287: 1011.

Klimov, V. I., Mikhailovsky, A. A., Xu, S. et al. 2000b. *Science* 290: 314.

Klimov, V. I., Ivanov, S. A., Nanda, J. et al. 2007. *Nature* 447: 441.

Larson, D. R., Zipfel, W. R., Williams, R. M. et al. 2003. *Science* 300: 1434.

Ma, Y. Z., Valkunas, L., Bachilo, S. M., and Fleming, G. R. 2005. *J. Phys. Chem. B* 109: 15671–15674.

Michalet, X., Pinaud, F. F., Bentolila, L. A. et al. 2005. *Science* 307: 538.

Murray, C. B., Norris, D. J., and Bawendi, M. G. 1993. *J. Am. Chem. Soc*. 115: 8706–8715.

Padilha, L. A., Fu, J., Hagan, D. J. et al. 2007. *Phys. Rev. B* 75: 075325.

Rossetti, R., Nakahara, S., and Brus, L. E. 1983. *J. Chem. Phys*. 79: 1086–1088.

Sariciftci, N. S. 1997. *Primary Photoexcitations in Conjugated Polymers: Molecular Exciton versus Semiconductor Band Model*. Singapore: World Scientific.

Schmidt, M. E., Blanton, S. A., Hines, M. A., and Guyot-Sionnest, P. 1996. *Phys. Rev. B* 53: 12629.

Scholes, G. D. 2008a. *Adv. Funct. Mater*. 18: 1157.

Scholes, G. D. 2008b. *ACS Nano* 2: 523–537.

Scholes, G. D. and Rumbles, G. 2006. *Nat. Mater*. 5: 683.

Scholes, G. D. and Rumbles, G. 2008. Excitons in nanoscale systems: Fundamentals and applications. In *Annual Review of Nano Research*, eds. G. Cao and C. J. Brinker. Hackensack, NJ: World Scientific.

Seydack, M. 2005. *Biosens. Bioelectron*. 20: 2454.

Shalaev, V. M., Poliakov, E. Y., and Markel, V. A. 1996. *Phys. Rev. B* 53: 2437.

Spanhel, L., Haase, M., Weller, H., and Henglein, A. 1987. *J. Am. Chem. Soc*. 109: 5649–5655.

Sutherland, R. L. 2003. *Handbook of Nonlinear Optics*. New York: Marcel Dekker.

Wang, F., Dukovic, G., Brus, L. E., and Heinz, T. F. 2005. *Science* 308: 838–841.

Yoffe, A. D. 1993. *Adv. Phys*. 42: 173.

Yoffe, A. D. 2001. *Adv. Phys*. 50: 208.

Zhang, C. F., Zhang, F., Zhu, T. et al. 2008. *Opt. Lett*. 33: 2437.

Zhao, H. B. and Mazumdar, S. 2004. *Phys. Rev. Lett*. 93: 157402.

24

Optical Properties of Metal Clusters and Nanoparticles

Emmanuel Cottancin
Université de Lyon

Michel Broyer
Université de Lyon

Jean Lermé
Université de Lyon

Michel Pellarin
Université de Lyon

24.1 Introduction **24**-1
24.2 Theoretical Description **24**-2
General Considerations on Bulk Metals • Optical Properties of Confined Metallic Systems
24.3 Experimental Results: State of the Art **24**-12
Nanoparticle Synthesis • Techniques of Optical Spectroscopy • Experimental Results
24.4 Conclusion and Outlooks **24**-21
Acknowledgments **24**-21
References **24**-22

24.1 Introduction

The discovery of fullerenes (Kroto et al. 1985) and the experimental evidence of the so-called magic cluster sizes (Knight et al. 1984, de Heer 1993), more than 25 years ago, were at the origin of unceasing investigations on small clusters and nanoparticles and have contributed to the emergence of nanosciences, at the crossing point of several branches such as physics, chemistry, or even biology. In view of their high surface-to-volume ratio, clusters possess properties, different from those of bulk matter, that are very sensitive to their size and shape, rendering them very attractive from both the fundamental and technological points of view. In particular, the metallic species of a few nanometers in diameter disclose electronic properties intermediate between those of molecular systems and those of bulk matter. Whereas the sparse energy levels are quantized in atoms and molecules and continuously distributed in the energy bands of the crystal (Ashcroft and Mermin 1976), they tend to bunch together in metallic clusters and thus pattern the so-called electronic shells. This shell structure was evidenced experimentally (magic sizes) in the early 1980s in several metals (de Heer 1993) and nicely interpreted in the frame of the *jellium* model (Brack 1993). However, it was shown that magic sizes can also be correlated with atomic shell closures (Martin 1996) and even that both electronic and geometric structures may compete with each other, depending on the temperature (Martin et al. 1990).

The optical properties of metallic clusters being directly underlain by their electronic structure, their optical study is, in this respect, of fundamental interest. For the rest, the fascinating colors of glasses doped with metallic powders have been known for ages even if their origin long remained mysterious. The synthesis of such materials is utilized since antiquity in the art of making jewels, ornamental glassware, or stained glass in the Middle Ages. One can quote the famous cup of Licurgus (Barber and Freestone 1990) from the fourth century AC (appearing red in transmission and green in reflection) or the stained-glass windows of the Chartres Cathedral in France. The colorful shade of these materials (such as glass ruby) was discovered empirically and various colors were obtained during the seventeenth century by alchemists, metallurgists, or glassworkers. For instance, Glauber mentions that *purple can be obtained by precipitating gold from its solution in aqua regia with a solution of tin compound* (Hunt 1976). It was however only in the nineteenth century that their optical properties started to become more systematically studied by Faraday who succeeded in producing gold colloids by reducing gold salts (Faraday 1857b) and showed that color effects are intimately correlated to the size and morphology of colloids. In the Bakerian lecture (Faraday 1857a), Faraday spoke about the experimental relations of gold to light in the following terms: “Light has a relation to the matter which it meets with in its course, and is affected by it, being reflected, deflected, transmitted, refracted, absorbed, &c. by particles very minute in their dimensions.” In the lineage of Faraday, Zsigmondy worked on colloidal suspensions and set up the ultra-microscope based on the scattering of particles observed in dark field by illuminating the material to be viewed with a light source placed at right angle to the plane of the objective (Zsigmondy 1926). In 1925, Zsigmondy was awarded the Nobel Prize for Chemistry for his work on the heterogeneous nature of colloidal solutions.

On a theoretical point of view, the pioneering experiments by Faraday have been interpreted later by Mie (1908) who solved Maxwell’s equations of a metallic sphere in a homogeneous medium submitted to an external electromagnetic field (plane wave). Mie showed that the original properties of metallic nanoparticles are a consequence of the "dielectric confinement" (limited volume of the material) of particles whose sizes are smaller or of the same order as the wavelength of the excitation field. At the same time, Maxwell-Garnett developed an effective field model (Maxwell-Garnett 1904) in order to describe the optical properties of a medium containing "*minute metal spheres*." The main feature in the optical extinction spectra of small metallic clusters is the emergence of a giant resonance in the near UV–visible range, called surface plasmon resonance (SPR) that is related to the collective motion of the conduction electrons induced by the applied field. This resonance is clearly noticeable only in the case of simple metal (alkali, trivalent) and noble metal (gold, silver, and copper) clusters. Its spectral position and width depend on the morphology of the particles (size, shape, and internal structure for alloyed systems), but also on their dielectric environment (medium in which the particles are embedded, local neighborhood) (Kreibig and Vollmer 1995). The development of numerous cluster sources (Sattler et al. 1980, Smalley 1983, Milani and de Heer 1990, Siekmann et al. 1991) in the 1980s enabled to probe the intrinsic properties of the clusters of very small size for which quantum size effects were expected. From a fundamental point of view, alkali clusters constitute a perfect model owing to their simple electronic structure and have been widely studied in the gas phase (Pedersen et al. 1991, Blanc et al. 1992, Bréchignac et al. 1992, de Heer 1993). However, they are immediately oxidized in contact with air once deposited on a surface, and thus are not suitable for applications. In spite of their more complex electronic structure, noble metal clusters in solution or embedded in a transparent matrix are more promising for potential applications because they are more robust toward oxidization. By varying the morphology, structure, or environment of these clusters, their optical response may be more or less controlled, making them attractive in several areas (linear and nonlinear optics [Kreibig and Genzel 1985], nanomaterials, nano-photonics, plasmonics, biosensors [Raschke et al. 2003]). Conversely, as the optical response is closely linked with the electronic structure, the SPR can also be used as a probe of the structure of metallic clusters, especially bimetallic systems or nanoalloys. Furthermore, the exaltation of the electromagnetic field in the vicinity of the particle can be exploited to increase the coupling of molecules with light, for developing biological markers for instance (McFarland and Duyne 2003).

Until the past few years, most of the experiments in this field were performed on cluster assemblies, and except the investigation of size-selected clusters in the gas phase, the results are blurred by averaging effects due to the unavoidable cluster size and shape dispersions in samples (Kreibig and Vollmer 1995, Cottancin et al. 2006). To overcome this drawback, new methods of spectroscopy have been developed within the past 10 years, in order to study a single nanoparticle (Tamaru et al. 2002, Raschke et al. 2003, Arbouet et al. 2004, Dijk et al. 2006, Billaud et al. 2007). This has opened up a new field of research, allowing for instance to investigate reliably more complex nano-objects or to study in detail shape effects on the optical response best than ever.

The aim of this chapter is to give some keys to understand the linear optical properties (absorption, scattering, and extinction) of metallic clusters and nanoparticles,* and to present the state of the art of the research in this field. Section 24.2 deals with the theoretical description of the optical response of a metallic particle submitted to an external field. After a brief focus on the optical response of a bulk metal, particular attention is paid to the dipolar approximation that is appropriate for clusters sizes much smaller than the wavelength of excitation. Size, shape, and structural effects that can be expected are then fully discussed. The case of small clusters, for which quantum finite size effects are expected, is concisely sketched, disregarding the case of very small clusters (below 100 atoms per cluster) for which ab initio calculations are necessary (Rubio et al. 1997, Bonacic-Koutecky et al. 2001, Harb et al. 2008). Finally, the broad outlines of the Mie theory required to describe the optical response of larger nanoparticles are given.

Section 24.3 is divided into three subsections. The first one briefly sets out various methods for producing clusters together with spectroscopic techniques for probing their optical properties. The second one gives an overview of the major results obtained on simple and noble metal clusters concerning size, shape, and multipolar effects in clusters and nanoparticles. Illustrations are taken equally from results obtained for cluster assemblies or single nanoparticles. Finally, the case of bimetallic clusters is described to illustrate the possibility of using the SPR as a structural probe.

24.2 Theoretical Description

24.2.1 General Considerations on Bulk Metals

In the bulk phase, the close packing of atoms involves an overlap of their outer atomic orbitals that strongly interact. This leads to a broadening of the discrete levels of the free atoms into bands (a continuum of electronic states), of very high density of states in metals. In this last case, the highest occupied energy band is called the conduction band and is filled with electrons originating from the outermost atomic orbitals. These electrons weakly interact with the ionic cores, and can be considered as quasi-free particles. They are delocalized in the metal and responsible for most of electrical and thermal transport properties. The highest occupied energy level in the conduction band (not completely filled in metals) is the Fermi level ε_F for which the electron velocity is the Fermi velocity v_F. Lower-energy atomic orbitals will give rise to deeper energy bands (valence bands) in the solid. In noble metals for instance, the highest of these bands originates from the *nd* atomic orbitals ($n = 3, 4, 5$ for Cu, Ag, and Au, respectively). It is narrow owing to its weak hybridization with the conduction band (Figure 24.1). When a metal interacts with light, it may absorb a photon of energy $h\nu$ promoting an electron from an occupied state to an unoccupied state, the latter being located in the incompletely filled conduction band. As for the occupied state, it belongs either to the conduction band or to the valence band. In the first case, the corresponding transition is called "intraband" transition and occurs in the infrared (IR)–visible range. The second case corresponds to "interband" transitions that can occur only if the photon energy is larger than the limiting value $\hbar\Omega_{ib}$ corresponding to the energy threshold required for reaching the Fermi level from the top of the valence band (see Figure 24.1). In simple metals like alkali or trivalents, this threshold is out of the optical domain (near UV–visible–near IR). Thus, only optical transitions within the conduction band may occur. For noble metals, it lies in the UV–visible range and interband transitions may happen in the visible-UV range (see Figure 24.1). The energy threshold occurs in the UV range for silver ($\hbar\Omega_{ib} \sim 4\,\text{eV}$, $\lambda_{ib} \sim 310\,\text{nm}$) and in the visible range for gold and copper ($\hbar\Omega_{ib} \sim 1.9\,\text{eV}$, $\lambda_{ib} \sim 650\,\text{nm}$).

---

* The term "cluster" is generally reserved for sizes lower than a few nanometers in diameter, whereas the term "nanoparticle" is used in the range between a few nanometers to a few hundreds of nanometers.

The optical response of the metal can be described entirely by its dielectric function $\varepsilon(\omega)$, which reflects its electronic structure. If a metal is submitted to an external electromagnetic (EM) field $\vec{E} = \vec{E}_o \cos(\omega t) = \Re(\vec{E}_o e^{-i\omega t})$, it is polarized such that its polarization (defined as the dipolar moment per volume unit) is $\vec{P} = \varepsilon_o \chi \vec{E}$, where ε_o is the vacuum permittivity and χ the dielectric susceptibility. The displacement vector can then be written as $\vec{D} = \varepsilon_o \vec{E} + \vec{P} = \varepsilon_o \varepsilon(\omega)\vec{E}$, where $\varepsilon(\omega) = 1 + \chi(\omega)$ denotes the relative dielectric function which is characteristic of the metal. A part of the response may be in phase with the exciting field ($\alpha \cos(\omega t)$), whereas the absorption effects induce a response in quadrature phase ($\alpha \sin(\omega t)$). Therefore, the dielectric function can be decomposed into a complex form $\varepsilon = \varepsilon_1 + i\varepsilon_2$. Let us recall that it is directly correlated to the optical index of the medium, $n_{\text{opt}} = n + i\kappa = \sqrt{\varepsilon}$, in which n is the refractive index and κ the extinction coefficient (Fox 2001). n_{opt} is real if the medium is non-absorbing.

In the case of simple metals, the Drude model (Drude 1900a,b, Ashcroft and Mermin 1976), developed originally to explain why metals are good conductors of heat and electricity, remains successful to interpret their optical properties (such as the fact that metals are good reflectors for frequencies lower than a threshold frequency, called plasma frequency [Fox 2001]). This model makes the basic assumption that most of the metal properties can be explained in first approximation by those of the conduction electrons if they are considered as independent and quasi-free. In this frame, when an oscillating electric field is applied, the free electrons oscillate and undergo collisions with other particles (electrons, ions, defects) with a characteristic scattering time $\tau = (1/\gamma_o)$, where γ_o is the average collision rate of electrons. Since the electrons are independent, their global response is the sum of all individual responses. By applying the principle of dynamics for an electron of effective mass m_e and charge $-e$, one obtains:

$$m_e \frac{d^2\vec{r}}{dt^2} = -\gamma_o m_e \frac{d\vec{r}}{dt} - e\vec{E}_o e^{-i\omega t}, \tag{24.1}$$

where $\vec{r}$ is the complex position vector of the electron. One can easily solve this equation and deduce the polarization in the metal:

$$\vec{P} = -\rho e\vec{r} = \frac{\varepsilon_o \omega_P^2}{m_e \omega(\omega + i\gamma_o)} \tag{24.2}$$

where ρ is the number of electrons per volume unit (electronic density) and

$$\omega_P = \sqrt{\frac{\rho e^2}{m_e \varepsilon_o}} \tag{24.3}$$

the plasma angular frequency that is introduced to interpret the high reflectivity of metals (Fox 2001) for frequencies lower than ω_P.



FIGURE 24.1 (Left) Schematic diagram of the transition from discrete electronic levels in atoms to electronic bands in the solid for noble metals. (Right) Schematic density of states for the $(n-1)$d and ns–p bands (left) of a noble metal. The ns–p band corresponding to quasi-free electrons in the metal is almost parabolic. As the atoms are brought closer together, their outer orbitals begin to overlap with each other and their strong interaction involves the formation of energy bands. Optical transitions inside the s–p band take place in the IR–visible range whereas interband transitions between the d-band and the conduction band may occur in the visible–near UV range.



FIGURE 24.2 Real and imaginary parts ε_1 and ε_2 of the dielectric function of silver (left) and gold (right). Comparison between the Drude model (gray lines) and the experimental measurements of Johnson and Christy (1972) (squares). The influence of d-core electrons is patent in the imaginary part of ε where an increase of ε_2 appears around 1.9 eV for gold and 4 eV for silver corresponding to the interband transition threshold $\hbar\Omega_{ib}$.

The so-called Drude dielectric function can then be written as (see also Figure 24.2)

$$\varepsilon^D(\omega) = 1 - \frac{\omega_P^2}{\omega(\omega + i\gamma_o)} \quad \text{or}$$

$$\begin{cases} \varepsilon_1^D(\omega) = 1 - \dfrac{\omega_P^2}{\omega^2 + \gamma_o^2} \approx 1 - \dfrac{\omega_P^2}{\omega^2} & (\text{if } \gamma_o \ll \omega) \\[2ex] \varepsilon_2^D(\omega) = \dfrac{\omega_P^2 \gamma_o}{\omega(\omega^2 + \gamma_o^2)} \approx \dfrac{\omega_P^2}{\omega^3}\gamma_o & (\text{if } \gamma_o \ll \omega) \end{cases} \tag{24.4}$$

This model is well suited to reproduce the dielectric function of simple metals, but in the case of noble metals, another term has to be added to the dielectric function in order to account for the polarization of the core electrons. The dielectric function then takes the following form:

$$\varepsilon = 1 + \chi^D + \chi^{IB} = \varepsilon^D + \varepsilon^{IB} - 1, \tag{24.5}$$

where ε^D denotes the component of the dielectric function associated with the conduction electrons and well described by the Drude model (D). It is related to the electron excitations inside the conduction band. ε^{IB} is related to interband (IB) transitions and depicts the contribution of the core electrons (d-electrons mainly) to the metal polarizability (Ashcroft and Mermin 1976). Figure 24.2 displays a comparison between the dielectric function calculated with the Drude model and the measured one, for gold and silver. If an almost clear agreement is observed in the IR range (below 1–1.5 eV), the experimental values distinctly deviate from the calculated ones in the visible-UV range, because of the interband transition contribution. The steep increase in ε_2 corresponds to the interband transition threshold $\hbar\Omega_{ib}$. In the case of copper (not shown here) the increase is steeper than in gold. It occurs at slightly higher wavelengths and is at the origin of the difference of the color of these two metals. As $\varepsilon_1(\omega)$ and $\varepsilon_2(\omega)$ are connected to each other with the Kramers–Kronig relationship (Ashcroft and Mermin 1976), the influence of interband transitions also explains the disagreement observed in the real part of $\varepsilon(\omega)$ between the Drude model and the experiment, the difference being larger in gold because of the proximity of the IB transitions.

24.2.2 Optical Properties of Confined Metallic Systems

24.2.2.1 Scattering, Absorption, and Extinction

In general, light is absorbed and scattered by a particle (see Figure 24.3). Absorption corresponds to the energy dissipation (heating) in the particle, whereas scattering is an elastic interaction of the wave with the particle. The EM field is reradiated by the particle in the whole space without a change of wavelength (Rayleigh scattering). If one assumes a particle in a homogeneous transparent medium (of dielectric function ε_m) submitted to an incoming plane wave $\vec{E}_i = \vec{E}_o e^{i(\vec{k}\vec{r} - \omega t)}$ of average intensity $I_o = (1/2)c\varepsilon_o\sqrt{\varepsilon_m}E_o^2$ (units: $\mathrm{W \cdot m^{-2}}$), the absorption and scattering cross sections (units: $\mathrm{m^2}$) are defined as the ratio between the absorbed power W_{abs} (unit: W) (respectively the scattered power W_{sca}) and the intensity I_o: $\sigma_{\text{abs}} = W_{\text{abs}}/I_o$ and $\sigma_{\text{sca}} = W_{\text{sca}}/I_o$.


$\vec{E_i} = \vec{E_o}e^{i(\vec{k}\vec{r}-\omega t)}$
W_s
$W_{\text{trans}} = W_o - W_{\text{abs}} - W_{\text{sca}}$
I_o
W_a
Detector
R
$\sigma_{\text{geo}} = \pi R^2$
σ_{ext}

FIGURE 24.3 Schematic view of light absorption, scattering, and extinction of a particle. (Top) A particle excited by an incident plane wave reemits a part of the incident power by scattering (W_{sca}) and absorbs the power W_a. An in-axis sensor placed far away from the particle detects the incident power minus the lost power related to extinction. The detector is far enough for neglecting a direct collection of the forward scattered light. (Bottom) Naive picture of the extinction cross section σ_{ext} corresponding to the loss induced by the presence of a spherical particle in the course of the plane wave. σ_{ext} may be smaller or larger than the apparent surface of the particle πR^2.

The extinction cross section, related to the total power lost in the propagation direction of the incident plane wave far away from the particle, is defined as the sum of both absorption and scattering cross sections: $\sigma_{\text{ext}} = \sigma_{\text{abs}} + \sigma_{\text{sca}}$. This can be viewed naively in terms of perfectly opaque transverse areas shadowing the incoming plane wave (see Figure 24.3). It should be emphasized that, depending on the wavelength, σ_{ext} may be different from the mere geometrical apparent area of the particle (see Figure 24.3).

In the case of metals, in particular simple and noble metals, the dielectric confinement gives rise to a giant resonance (called SPR or Mie resonance) in the UV–visible range due to collective electronic excitations. It will be shown that the dielectric confinement refers to as classical size effects.

24.2.2.2 Dipolar or Quasi-Static Approximation

Let us consider a spherical metallic particle of radius R embedded in a transparent medium of real dielectric function ε_m submitted to an incident EM field $\vec{E}_i = \vec{E}_o e^{i(\vec{k}\vec{r}-\omega t)}$, whose diameter is very small as compared to the wavelength of excitation (diameter $\phi \ll \lambda$). In this approximation, called quasi-static approximation, the spatial variations of the field inside the particle can be ignored and the field can be written as $\vec{E}_i(t) = \vec{E}_o e^{-i\omega t}$ (see the smaller particle in Figure 24.4). Moreover, as will be shown below, the scattering is negligible as compared to absorption for diameters below 20–40 nm (depending on the element) and $\sigma_{\text{ext}} \simeq \sigma_{\text{abs}}$.

In the presence of the EM field, the small metallic sphere is polarized (see Figure 24.4). By solving the Poisson equation in the absence of free charges ($\Delta V(\vec{r}) = 0$) inside and outside the particle, and considering the boundary conditions at the interface, the internal field is shown to be as follows (Bohren and Huffman 1983, Berthier 1993): $\vec{E}_{\text{int}} = 3\varepsilon_m/(\varepsilon + 2\varepsilon_m)\vec{E}_i(t)$, and the external field can be viewed as the sum of the incident field and the one created by a fictitious point dipole $\vec{p}(\omega,t) = 4\pi\varepsilon_o\varepsilon_m R^3((\varepsilon - \varepsilon_m)/(\varepsilon + 2\varepsilon_m))\vec{E}_i(t) = \alpha(\omega)\vec{E}_i(t)$, where $\alpha(\omega)$ is the dynamical polarizability (it is the reason why the quasi-static approximation is also called dipolar approximation). The mean power dissipated inside the particle can be expressed in terms of the imaginary part of the dynamic polarizability (component in quadrature phase with the incident field):

$$P_{\text{mean}} = \iiint \left\langle \vec{j}(t)\vec{E}_{\text{int}}(t) \right\rangle d\tau = \frac{E_o^2\omega}{2}\Im m(\alpha)$$


$\vec{E} = \vec{E}_o e^{-i(\omega t - \vec{k}\cdot\vec{r})}$
$\vec{k}$
ε_m
$\varepsilon(\omega) = \varepsilon_1 + i\varepsilon_2$
ε_m
$\varepsilon(\omega) = \varepsilon_1 + i\varepsilon_2$

FIGURE 24.4 Metallic sphere of dielectric function $\varepsilon(\omega)$ in a transparent medium of real dielectric function ε_m submitted to an external field $\vec{E}_i = \vec{E}_o e^{i(\vec{k}\vec{r}-\omega t)}$. Case of a small particle of diameter $\phi \ll \lambda$: the particle does not feel the spatial variations of the electric field: this is the quasi-static or dipolar approximation. The metallic sphere is polarized and the surface charge distribution creates a dipole. Case of a large particle of diameter $\phi \sim \lambda$: the spatial variations of the field inside the particle induces a more complex surface charge distribution, leading to multipolar modes like the displayed quadrupolar mode (see Mie theory Section 24.2.2.5).

where $\vec{j}(t)=-\rho e\vec{v}=\frac{\partial\vec{P}}{\partial t}$ and finally the absorption cross section takes the following form:

$$\sigma_{\text{abs}}(\omega)=\frac{9\omega\varepsilon_m^{3/2}}{c}\left(\frac{4}{3}\pi R^3\right)\frac{\varepsilon_2(\omega)}{(\varepsilon_1(\omega)+2\varepsilon_m)^2+\varepsilon_2(\omega)^2}, \tag{24.6}$$

where c denotes the velocity of light.

In general $\varepsilon_2(\omega)$ is relatively small in the case of simple and silver metals in the UV–visible range and $\sigma_{\text{abs}}(\omega)$ is strongly enhanced when

$$\varepsilon_1(\omega)+2\varepsilon_m=0 \tag{24.7}$$

This condition named resonance condition may be fulfilled for metals for which the real part of the dielectric function $\varepsilon_1(\omega)$ is negative (see Figure 24.2). The correlative resonance phenomenon is known as the SPR or Mie resonance and corresponds to the collective oscillation of the conduction electrons relative to the ionic background. By using Equations 24.4 and 24.5, the spectral position of the SPR can be approximately deduced from the resonance condition Equation 24.7. One obtains

$$\omega_{SPR}\simeq\frac{\omega_P}{\sqrt{\varepsilon_1^{IB}(\omega_{RPS})+2\varepsilon_m}}. \tag{24.8}$$

This equation indicates that the frequency resonance depends both on the material through ω_P and ε_1^{IB}, and on the medium in which the particle is embedded through ε_m. In alkali metals, as the IB transitions are negligible, one gets in vacuum ($\varepsilon_m=1$) the simple relation $\omega_{SPR}=\omega_P/\sqrt{3}$, which generally holds for a perfectly conducting metallic sphere.

It can be underlined that, in the frame of the quasi-static approximation, the extinction and scattering cross sections can be deduced directly from the Mie theory in the small-size range (Bohren and Huffman 1983). They take the following form at the lowest order:

$$\sigma_{\text{ext}}(\omega)=\frac{9\omega\varepsilon_m^{3/2}}{c}\left(\frac{4}{3}\pi R^3\right)\frac{\varepsilon_2(\omega)}{(\varepsilon_1(\omega)+2\varepsilon_m)^2+\varepsilon_2(\omega)^2} \tag{24.9}$$

$$\sigma_{\text{sca}}(\omega)=\frac{3\omega^4\varepsilon_m^2}{2\pi c^4}\left(\frac{4}{3}\pi R^3\right)^2\frac{(\varepsilon_1(\omega)-\varepsilon_m)^2+\varepsilon_2(\omega)^2}{(\varepsilon_1(\omega)+2\varepsilon_m)^2+\varepsilon_2(\omega)^2} \tag{24.10}$$

σ_{sca} varies with λ as $1/\lambda^4$ (Rayleigh-scattering) ($\lambda=(2\pi c/\omega)$ being the wavelength in vacuum) and exhibits the same resonance condition as the absorption cross section. For a given nanoparticle of diameter R, $(\sigma_{\text{sca}}/\sigma_{\text{ext}})\propto(R/\lambda)^3$. In the dipolar approximation ($\phi\ll\lambda$) the extinction is clearly dominated by absorption ($\sigma_{\text{sca}}\ll\sigma_{\text{abs}}=\sigma_{\text{ext}}$ [comparison of Equations 24.6 and 24.9]).

24.2.2.3 Intrinsic Size Effects

24.2.2.3.1 Dielectric Function of a Confined Metal

Except a mere volume factor, it is clear from Equation 24.6 that no size effects are predicted in the dipolar approximation. However, in this description, the dielectric function of the particle was assumed to be the one of the bulk. Actually, some modifications of the metallic dielectric function are expected because of confinement. Indeed, in a confined system, the collision rate of electrons is modified because of surface scattering that reduces the mean free path of electrons (Kreibig and Fragstein 1969, Kreibig and Genzel 1985, Kreibig and Vollmer 1995). The extra-scattering rate scales at v_F/ℓ, where v_F is the Fermi electron velocity and ℓ the limited mean free path for electron motion (of the order of the particle radius). For a spherical particle of radius R, the collision rate can be written as

$$\gamma(R)=\gamma_o+g\frac{v_F}{R}, \tag{24.11}$$

where g is the surface-scattering coefficient whose value is about unity (Kreibig and Vollmer 1995). The modification of the collision rate with size induces a modification of $\varepsilon^D(\omega,R)$. The dielectric function is then $\varepsilon(\omega,R)=\varepsilon^D(\omega,R)+\varepsilon^{IB}(\omega,\infty)-1$, where $\varepsilon^{IB}(\omega,\infty)$ refers to as the interband dielectric function.

In the dipolar approximation, this size dependence of the dielectric function induces a size variation of the absorption cross section, as illustrated Figure 24.5 in the case of copper, silver, and gold clusters embedded in alumina. The main features in the spectra are a damping and broadening of the SPR with decreasing size. For gold and copper, a slight red-shift of the resonance is expected within the frame of this model, which is not observed experimentally due to quantum size effects (Cottancin et al. 2006) as will be shown in the following section.

This phenomenological size evolution of $\varepsilon(\omega,R)$ may be recovered from a simple quantum approach of confined electrons in an infinite potential well (Kubo model [Kawabata and Kubo 1966]). Nevertheless this simple model is too crude to give an interpretation of the size effects observed in small alkali and noble metal clusters (except silver) because an infinite potential well cannot lead to the well-known spillout of electrons beyond the classical radius of clusters.

24.2.2.3.2 Quantum Size Effects

In the classical Mie theory, the electronic density $\rho_e(r)$ perfectly matches the positive ionic charge, but quantum calculations (Brack 1993) predict a significant overflow of electrons beyond the classical radius[*] of the cluster $R_C=r_S N_e^{1/3}$. Because of the finite depth of the potential well, the electronic density does not vanish beyond the cluster radius R_C (exponential decay). This spillout corresponds to an increase of a few angstroms of the effective cluster radius (conduction electron cloud) that becomes significant in small clusters ($\phi<5$ nm). In particular, it has a great influence on the optical properties of metallic clusters, especially on the size evolution of the SPR spectral position.

---

[*] Keeping in mind that the Wigner–Seitz radius r_S is correlated with the volume occupied by a conduction electron ($V_e=(4/3)\pi r_s^3$) in the bulk, one can easily deduce that the classical radius of a cluster containing N_e conduction electrons is: $R_C=r_S N_e^{1/3}$.



FIGURE 24.5 Size evolution of the theoretical absorption cross section σ_{abs} versus energy within the classical Mie theory in the dipolar approximation, taking into account the reduction of the mean free path in the particle, for copper, silver, and gold clusters embedded in porous alumina ($\varepsilon_m \simeq 2.7$). (From Cottancin, E. et al., *Theor. Chem. Acc.*, 116, 514, 2006.)



FIGURE 24.6 Schematic view of the jellium model: the ionic background is replaced by a homogeneous positive charge distribution with which the conduction electrons interact. (Right, top) Geometrical aspect of the jellium (dark gray) and the electron spillout (light gray). (Bottom) Corresponding evolution of both ionic (black line) and electronic (gray line) densities versus *r*. The electronic density overflows beyond the classical cluster radius: this is the so-called spillout.

On a quantum basis, the metallic clusters of a few nanometers in diameter are usually described by the standard jellium model (Brack 1993) in which the conduction electrons of a spherical cluster in vacuum are quantum mechanically treated, whereas the granular ionic structure is replaced by a spherical, homogeneous, positive-charge distribution: the jellium (of total positive charge *Q*). The problem to be solved is then the one of N_e electrons interacting together and with the potential created by the positively charged jellium. For $r < R_{N_e}$, the interaction potential energy between an electron and the jellium is equal to

$$V_{\text{jel}}(r) = \frac{1}{2}m(\omega_{RPS}^{cl})^2 r^2 - \frac{3}{8\pi\varepsilon_o}\frac{qQ}{R_C} \quad \text{where } \omega_{RPS}^{cl} = \frac{\omega_P}{\sqrt{3}}$$

The first term corresponds to the potential of a harmonic oscillator of angular frequency ω_{RPS}^{cl} (the SPR frequency in vacuum) in the case of simple metals for which $\varepsilon^{IB} = 0$ (see Equation 24.8).

The resolution of the problem may be achieved in the frame of the density functional theory (DFT) by solving self-consistently the Kohn–Sham equations (Hohenberg and Kohn 1964, Kohn and Sham 1965). When convergence is reached, the system can be considered formally as equivalent to a system of N_e-independent electrons moving in an effective central potential $V_{\text{eff}}(r)$ of finite depth. The most relevant results obtained in this framework are the electronic shell and supershell structures explaining the famous magic sizes, the beating patterns (Pedersen et al. 1991, Pellarin et al. 1995) and the rise of the spillout (see Figure 24.6) whose profile is almost independent of cluster size (Brack 1993). The interaction of a cluster with light may be investigated in the frame of the random phase approximation (Yannouleas et al. 1989) (RPA) or in the frame of the time-dependent local-density approximation (Eckardt 1985) (TD LDA), both using the jellium model. These formalisms account for the quantum size effects ignored in the classical approach. Figure 24.7 shows for instance results obtained with the TD LDA for the magic sizes of sodium clusters in vacuum. For small clusters ($N < 100$), the absorption spectrum is broad and highly structured. This fragmentation of the plasmon band is due to a phenomenon known as Landau damping and can be explained in a simple manner in terms of a discrete state (the plasmon) coupled to a continuum (Cohen-Tannoudji et al. 1996) (one-electron excitations). When the cluster size increases, the fragmentation persists, but the oscillator strength is concentrated in an ever-narrower spectral range around the plasmon frequency, adopting a quasi-Lorentzian distribution. A red-shift of the SPR with decreasing size is also observed, in qualitative agreement with experimental spectra obtained for alkali clusters as will be shown in the following section.

This red-shift of the resonance obtained through quantum calculations is intimately linked to the increasing spillout



FIGURE 24.7 Absorption cross sections of sodium clusters calculated using the quantum TDLDA formalism within the framework of the jellium model. The gray line curve is the classical result obtained with the sodium dielectric function calculated with the Drude model (r_s = 0.208 nm). Spectra with thin lines for N = 58,138,1284 were calculated using a smoothing parameter 10 times smaller (Perez et al. 2007). The spectra are highly structured at small sizes and red-shifted as compared to classical predictions. They gradually converge toward the classical predictions (gray dotted line) as the size increases. (From Perez, A. et al., Nanoscience, *Clusters and Colloids*, Springer Verlag, Berlin/Heidelberg, Germany, 2007.)

influence. This correlation may also be viewed through a simple classical argument by considering the expression of the Plasmon angular frequency in vacuum $\omega^{cl}_{RPS} = (\omega_P/\sqrt{3})$.

Recall that $\omega_P = \sqrt{\rho e^2/(m_e\varepsilon_o)}$ and let δ_{so} be the spillout parameter. The effective electronic cluster radius can be written as $R_e = R_C + \delta_{so} = r_s N_e^{1/3} + \delta_{so}$. As the electronic density is the ratio between the number of electrons and their occupied volume in the cluster $((4/3)\pi R_e^3)$, the angular frequency is approximately

$$\omega_{SPR} \simeq \frac{\omega_P}{\sqrt{3}}\left(1-\frac{3\delta_{so}}{2R_{N_e}}\right). \qquad (24.12)$$

The profile of the spillout being almost constant with the size, this relation shows that the SPR frequency shifts toward lower energies with decreasing size. The increasing influence of the spillout with decreasing size is pertinent to explain the red-shift of the SPR in alkali clusters. In the case of noble metal clusters, the screening of the core electrons (especially the d-electrons) and its modification near the cluster surface plays also a key role (see Section 24.3) that induces a blue-shift in copper and gold and a quenching of the resonance shift in silver (Lermé et al. 1998b, Palpant et al. 1998, Celep et al. 2004).

Let us recall that the case of very small clusters (a few tens of atoms per cluster) requires ab initio calculations (Bonacic-Koutecky et al. 1991, Rubio et al. 1997, Bonacic-Koutecky et al. 2001, Harb et al. 2008) and would demand a large development that is not the subject of this chapter.

24.2.2.4 Shape and Structure Effects

24.2.2.4.1 Influence of the Shape on the Optical Properties of Clusters

The optical response of clusters is noticeably modified by their shape when they deviate from a perfect sphere. For instance, in the case of ellipsoids, the degenerate SPR splits into as many SPRs as the different principal axes of deformation (three in general and two for spheroids). Although quantum calculations account well for these shape effects (Clemenger), they can be more easily understood in a classical approach assuming a quasi-static approximation. If the system exhibits a sufficient symmetry, like an ellipsoid, the problem can be solved analytically. Consider an ellipsoid of a metal of complex dielectric function $\varepsilon(\omega)$ in a medium of dielectric constant ε_m. In the frame of the quasi-static approximation, the Maxwell equations can be solved in ellipsoidal coordinates (Bohren and Huffman 1983). Taking into account the boundary conditions at the metal–external-medium interface, the absorption cross section for a light polarization along the principal axes $i = x, y, z$ (correlated to the semi-axes a, b, c of the ellipsoid [see Figure 24.7]) can be expressed as (Bohren and Huffman 1983)

$$\sigma^i_{\text{abs}} \simeq \sigma^i_{\text{ext}} = \frac{\omega\varepsilon_m^{3/2}}{c}\frac{V_{\text{ell}}}{L_i^2}\frac{\varepsilon_2(\omega)}{\left(\varepsilon_1(\omega)+\dfrac{1-L_i}{L_i}\varepsilon_m\right)^2+\varepsilon_2(\omega)^2}, \qquad (24.13)$$

where $V_{\text{ell}} = (4/3)\pi abc$ is the volume of the ellipsoid. The relation is similar to the one obtained for a sphere except for the additional geometrical factor:

$$L_i = \frac{abc}{2}\int_0^\infty \frac{du}{(u+l_i^2)\sqrt{(u+a^2)(u+b^2)(u+c^2)}} \quad \text{with } l_x = a,\ l_y = b,\ l_z = c.$$

The sum $L_x + L_y + L_z = 1$ and for a sphere $L_i = (1/3)$.

The optical response exhibits three resonances associated with the three principal axes of the ellipsoid if the excited light is not polarized. For a light polarization directed along the axis i, the resonance condition is in a first approximation: $L_i\varepsilon_1(\omega^i_{SPR}) + (1-L_i)\varepsilon_m = 0$ and the resonance occurs at

$$\omega_{SPR}^{i} \simeq \frac{\omega_P}{\sqrt{\varepsilon_1^{IB}(\omega_{RPS}) + \left(\dfrac{1-L_i}{L_i}\right)\varepsilon_m}}.$$

In the case of a spheroid for which two semi-axes are equal ($b = c < a$: prolate or $a < b = c$: oblate), the geometrical factors are analytically correlated to the aspect ratio (see Figure 24.8) of the spheroid (Bohren and Huffman 1983).

The influence of the shape on the optical extinction cross section is displayed in Figure 24.8 for silver prolate and oblate nanospheroids. In both cases, two resonance modes appear on each side of the resonance of the sphere of equivalent volume, the difference between both modes being all the more important as the aspect ratio is small. The resonances, red- or blue-shifted as compared to the resonance of the sphere, are correlated to the electronic motion along the large axis or the small axis of the particle. Experimentally, if the measurements are performed on non-oriented cluster assemblies all the resonance modes are observed and the resulting optical response is the sum of the responses along each axis. Actually, the shape influence is easier to investigate experimentally on single nanoparticles.



FIGURE 24.8 Shape evolution of the SPR for spheroidal silver clusters embedded in silica ($n = \sqrt{\varepsilon_m} = 1.5$). In each case, as one axis is degenerate the optical response gives rise to two resonances. The volume of the particle is constant and corresponds to the volume of a spherical particle of 20 nm in diameter. (a) Evolution of the maximum of the SPR versus the ratio between the small axis and the large axis (prolate and oblate cases). The gray and white points correspond to the white and gray arrows indicating the polarization direction of the incident light, respectively. (b) SPR for different aspect ratios $\eta = (c/a)$ in silver clusters embedded in silica (prolate case). Depending on the light polarization direction (see arrows), two resonances shifted as compared to the resonance obtained in the spherical case (black line) may be excited (gray and black circles). When the light polarization direction is along the large axis of the particle, the resonance is red-shifted, whereas it is blue-shifted if the particle is excited along its small axis, the smaller the aspect ratio, the larger the shift.

24.2.2.4.2 Influence of Chemical Structure

The optical response of metallic nanoparticles not only depends on their size and shape but also on their internal structure that can be heterogeneous. This is, for example, the case of mixed clusters made of several species (two for simplicity) in various proportions. Consider two chemical structures: a more or less homogeneous bimetallic alloying or a full spatial segregation of both metals (core/shell structure for instance). In the case of alloyed structures, the main difficulty is the knowledge of an effective dielectric function to use as an input for calculating the optical response. If the dielectric function has not been previously determined on corresponding alloys in the bulk phase (by optical measurements for instance), it is usually taken as the weighted average of the dielectric function of each constituent. But this hypothesis is crude because it assumes that the constituents are randomly segregated in nanodomains, each of them being described by a dielectric function taken as the one of the bulk phase. For alloyed structures at an atomic level, this approach may fail because the effective dielectric function of the alloy may be very different from those of each component.

The only structure for which calculations are currently feasible is the segregated core/shell structure that may develop in some particular systems. The problem can be solved exactly in the dipolar approximation for spherical or ellipsoidal shapes, and may be generalized to multi-shell structures. By solving Maxwell's equations and applying the successive boundary conditions on each interface, one can deduce the extinction and scattering cross sections. For a spherical core/shell cluster of core radius R_{core} and total radius R composed of two materials (with core and shell complex dielectric functions ε_c and ε_{sh}, respectively), the cross sections take the following form (Bohren and Huffman 1983):

$$\begin{cases} \sigma_{\text{ext}}(\omega) \simeq \sigma_{\text{abs}}(\omega) = \dfrac{3\omega\varepsilon_m^{1/2}}{c}\left(\dfrac{4}{3}\pi R^3\right)\Im\left(\dfrac{(\varepsilon_{sh}-\varepsilon_m)(\varepsilon_c+2\varepsilon_{sh})+f_v(\varepsilon_c-\varepsilon_{sh})(\varepsilon_m+2\varepsilon_{sh})}{(\varepsilon_{sh}+2\varepsilon_m)(\varepsilon_c+2\varepsilon_{sh})+2f_v(\varepsilon_{sh}-\varepsilon_m)(\varepsilon_c-\varepsilon_{sh})}\right) \\ \sigma_{\text{sca}}(\omega) = \dfrac{3\omega^4\varepsilon_m^2}{2\pi c^4}\left(\dfrac{4}{3}\pi R^3\right)^2 \Im\left|\dfrac{(\varepsilon_{sh}-\varepsilon_m)(\varepsilon_c+2\varepsilon_{sh})+f_v(\varepsilon_c-\varepsilon_{sh})(\varepsilon_m+2\varepsilon_{sh})}{(\varepsilon_{sh}+2\varepsilon_m)(\varepsilon_c+2\varepsilon_{sh})+2f_v(\varepsilon_{sh}-\varepsilon_m)(\varepsilon_c-\varepsilon_{sh})}\right|^2 \end{cases}$$

where $f_v = (R_{\text{core}}/R)^3$ is the volume ratio between the core and the cluster.

Such calculations can be performed on various bimetallic clusters or in the case of nanohybrid systems (dielectric–metal or semiconductor–metal). The reduction of the mean free path in the core and in the shell may be also taken into account (Granqvist and Hunderi 1978). As an illustration the optical response of a nanoshell containing a water core and a silver or copper shell embedded in water is displayed in Figure 24.9 for various shell thicknesses. This calculation, made in the frame of the dipolar approximation, is valid only for relatively small particles (Bohren and Huffman 1983). The most important feature in the spectra is a large red-shift of the resonance when the thickness of the metal decreases. In the case of copper, the SPR, damped and broadened in the full metal cluster, is progressively uncoupled from interband transitions (and thus enhanced) when the ratio between the thickness and the total radius decreases. A very similar evolution is expected for a gold nanoshell (Jain and El-Sayed 2007). One can also notice that for small shell thicknesses the resonance occurs at the same spectral range independently of the material (silver, copper, or gold). Such systems are very interesting because the position of the plasmon resonance can be easily tuned in the visible range by adjusting the shell thickness, which is very convenient for potential applications in medicine (Weissleder 2001).

24.2.2.5 Beyond the Dipolar Approximation: The Mie Theory

As emphasized before, when the size of the particle is very small compared to the wavelength of the exciting field, light scattering is negligible and the absorption cross section can be appropriately calculated by assuming the quasi-static (or dipolar) approximation. On the contrary, for large sizes as compared to the wavelength, the spatial distribution of the field amplitude in the particle volume cannot be disregarded (see the larger particle in Figure 24.4). One has to resort to the Mie theory for calculating the optical properties of particles subject to an incoming plane wave of angular frequency ω. This theory allows to determine the absorption and scattering cross sections, as well as the angular scattering pattern, of homogeneous spherical particles, of any radius, embedded in a homogeneous non-absorbing medium of dielectric function ε_m.

The theory (Bohren and Huffman 1983, Lermé et al. 2008) may be shortly sketched as follows. In a homogeneous medium the electric and magnetic field, $\vec{E}$ and $\vec{H}$ respectively, both satisfy the equations $\nabla\vec{V} = 0$ (zero divergence) and $\nabla^2\vec{V} + k^2\vec{V} = 0$ (vector Helmholtz wave equation), where $k = [\omega\varepsilon(\omega)\mu_0]^{1/2}$ is the wave vector in the medium and $\vec{V}$ stands for $\vec{E}$ or $\vec{H}$ ($\varepsilon(\omega) = \varepsilon_{\text{metal}}(\omega)$ in the particle and $\varepsilon(\omega) = \varepsilon_m$ outside the particle). In the Mie theory the incident, internal and scattered fields are expanded on the two sets of appropriate vector functions $\vec{M}_{nm}$ and $\vec{N}_{nm}$ (referred to as "the vector spherical harmonics") satisfying both previous Maxwell equations in the relevant homogeneous medium. These vector functions can be expressed in spherical coordinates (the origin being the particle center), and written as follows:

$$\vec{M}_{nm}(\vec{r},k) = K_{nm}\nabla\times\left[\vec{r}z_n(kr)P_n^m[\cos(\theta)]\exp(im\varphi)\right]$$

$$\vec{N}_{nm}(\vec{r},k) = \frac{1}{k}\nabla\times\vec{M}_{nm}(\vec{r}),$$

where

the $P_n^m(\theta)$'s are associated Legendre polynomials ($n = 1, 2, 3, \ldots$; $-n \le m \le n$)

$z_n(kr)$ are either spherical Bessel functions of the first kind $j_n(kr)$ (involved in the incident and internal electromagnetic field expansions), or spherical Hankel functions of the first kind $h_n^+(kr)$ (involved in the scattered field expansion, for ensuring the outgoing wave radiation condition, $\vec{M}_{nm}$ and $\vec{N}_{nm}$ are then denoted $\vec{M}_{nm}^+$ and $\vec{N}_{nm}^+$)

K_{nm} is a numerical factor



FIGURE 24.9 **(See color insert following page 20-14.)** Evolution of the absorption cross section of a nanoshell of silver (top) or copper (bottom) in the dipolar approximation versus energy (left) or versus wavelength (right) for various thicknesses of the shell. The core is filled with water and the external medium is also water (n = 1.33). The dielectric functions of copper and silver have been extracted from Palik (1985–1991). The correspondence between the energy in eV and the wavelength in nm is E (eV) = 1239.85/λ (nm). The total radius of the cluster is always 15 nm and the thickness takes the following values: $e = R - R_c$ = 5; 4; 3; 2; 1 nm corresponding to ratios between the shell thickness and the total cluster radius: (e/R) = 0.33; 0.27; 0.2; 0.13; 0.07. The spectra in black correspond to the fully homogeneous cluster.

The three involved fields (incident, scattering, and internal fields) can then be expressed as follows:

$$\begin{cases} \vec{E}_i(\vec{r}) = \displaystyle\sum_{n=1}^{\infty}\sum_{m=-n}^{n}[p_{nm}\vec{M}_{nm} + q_{nm}\vec{N}_{nm}] \\ \vec{E}_{\text{sca}}(\vec{r}) = \displaystyle\sum_{n=1}^{\infty}\sum_{m=-n}^{n}[a_{nm}\vec{M}_{nm}^{+} + b_{nm}\vec{N}_{nm}^{+}] \\ \vec{E}_{\text{int}}(\vec{r}) = \displaystyle\sum_{n=1}^{\infty}\sum_{m=-n}^{n}[c_{nm}\vec{M}_{nm} + d_{nm}\vec{N}_{nm}] \end{cases}$$

Owing to the orthogonality properties of the vector spherical harmonics, the four boundary conditions expressing the tangential continuity of the electric and magnetic fields at the surface of the sphere lead to a one-to-one relationship between the six various expansion coefficients corresponding to a given (n, m)-index set. For a given index set, they result in four linear algebraic equations allowing the expansion coefficients of the internal and scattered fields to be determined as a function of those characterizing the incident field. A mere proportionality relationship is obtained first between p_{nm}, a_{nm}, and c_{nm}, and second between q_{nm}, b_{nm}, and d_{nm}, the coefficients depending on $\varepsilon(\omega)$, ε_m, R, $j_n(x)$, and $h_n^+(x)$ (and their derivatives) for $x = kR$ or $x = k_mR$. Finally, the integration of the flux of the Poynting vector over a sphere enclosing the particle allows one to obtain the energy dissipated per second by scattering and absorption and thus extinction, and consequently the cross sections. All these observables can be expressed in terms of the expansion coefficients of the three involved fields:

$$\begin{cases} \sigma_{\text{sca}} = \dfrac{4\pi}{k^2}\displaystyle\sum_{n,m}\left\{|a_{nm}|^2 + |b_{nm}|^2\right\}\dfrac{1}{E_o^2} \\ \sigma_{\text{abs}} = -\dfrac{4\pi}{k^2}\displaystyle\sum_{n,m}\text{Re}\left\{a_{nm}p_{nm}^{*} + b_{nm}q_{nm}^{*}\right\}\dfrac{1}{E_o^2} - \sigma_{\text{sca}} \\ \sigma_{\text{ext}} = \sigma_{\text{abs}} + \sigma_{\text{sca}} \end{cases}$$

The vector spherical harmonics are defined according to Appendix A in reference Lermé et al. (2008).



FIGURE 24.10 Extinction (bold black line), absorption (gray line), and scattering (thin black line) cross sections calculated for silver clusters of diameter ϕ in water (n = 1.33) in the frame of the Mie theory. The dielectric function of silver is extracted from Johnson and Christy (1972). For small sizes extinction is dominated by absorption (for ϕ = 15 nm absorption and extinction are identical), whereas scattering becomes predominant for larger sizes.

Figure 24.10 gives the results of the Mie theory for silver nanoparticles of various sizes embedded in water (n = 1.33). A red-shift of the resonance with increasing size, which is correlated to multipolar effects, is clearly evidenced. Such size effects are sometimes referred to as extrinsic size effects (Kreibig and Vollmer 1995). The resonance is very different from the one expected in the quasi-static approximation and scattering is seen to be fastly dominant in the optical response for larger sizes. Notice that the spectra for smaller sizes do not involve surface effects and are thinner than the ones obtained previously since the modification of the collision rate at the cluster surface has not been included here (Section 24.2.2.3). For larger sizes, a shoulder appears at about 375 nm, which corresponds to the quadrupolar mode. This quadrupolar mode only appears in the absorption cross section for a diameter of about 60 nm. Experimentally, it has been observed in silver nanoparticles embedded in silica glass (p. 289 from reference Kreibig and Vollmer (1995)), but it is easier to observe on single nanoparticles (Billaud et al. 2007).

The Mie theory can be generalized to spherical core/shell structures and extended to several interacting spherical nanoparticles excited by an incident plane wave. In this latter case, the field felt by the particle is then the sum of the applied field and the fields scattered by the other particles. The optical response can be auto-coherently resolved. It should be emphasized that in addition to the analytical approaches, numerous numerical methods exist to deal with the particles of any shape or size (Kahnert 2003) or with pairs of nanoparticles in interaction (Romero, 2006). This subject arouses a large interest but is out of the range of this chapter.

24.3 Experimental Results: State of the Art

This section gives a brief outline of the main results obtained in this field of investigation through some illustrations on size, shape, and multipolar effects observed in simple and noble metal clusters. But first, the most common methods for producing clusters and some techniques for performing their optical spectroscopy are described.

24.3.1 Nanoparticle Synthesis

Clusters and nanoparticles can be synthesized either by chemical or physical processes. The former have been known for a long time and allow producing clusters in solution, in matrices or deposited on various substrates. The latter have been developed for almost 30 years.

24.3.1.1 Chemical Methods

Chemical methods can be classified into two main routes: the formation of clusters in glasses or the colloidal synthesis. The former has been worked out from antiquity and consists in including metallic powders and some reducing agent in a melting glass, which is then fastly cooled down in order to obtain a homogeneous glass doped with metal in an oxidized or ionic state (Doremus et al. 1992, Kreibig and Vollmer 1995, Shiomi and Umehara 2000). Various thermal or irradiation treatments are further applied to induce metallic reduction and the growth of metallic nanoparticles embedded in a transparent glass. This technique is nevertheless limited to noble metals with a low concentration (10^{-6} to 10^{-3}), but this is the only one giving volumic nanostructured glasses. The solgel technique (Brinker and Scherer 1990) is an alternative to elaborate such composite materials but only in the form of thin films. It consists in transforming a solution of precursors (solid particles in suspension: the sol) into a polymerized gel containing metallic ions on various substrates (by dip-coating, spin-coating, or pulverization). After drying, the films are thermally treated (annealed under reducing atmosphere, UV, or laser irradiation) allowing the reduction in metallic nanoparticles. This technique enables to prepare noble and transition metal clusters (Nogami et al. 1995, De et al. 1996, Canut et al. 2007) of sizes between a few nanometers to a few tens of nanometers embedded in various matrices with concentration ranging from 10^{-3} to 10^{-1}.

The second route is the colloidal technique (Link and El-Sayed 1999), which has known a large development within the past decades for elaborating self-organized nanostructures. The standard way consists in reducing metallic salts in aqueous solution at intermediate temperatures (300–400 K) thanks to reducing agents. The addition of organic compounds adsorbing on cluster surfaces will stabilize and control the growth reaction. The final cluster diameter is controlled by the nature and the concentration of the reagents (organic compounds and reducing agents): it can vary from a few nanometers to a few hundreds of nanometers. By this way, bimetallic clusters can also be prepared in the form of alloyed or segregated structures (Papavassiliou 1976, Torigoe et al. 1993, Liz-Marzan and Philipse 1995, Link et al. 1999). The optical properties of colloids are investigated either in solution or once they have been deposited on a substrate. However, they can be also transferred into the gas phase, with an electrospray source for instance, and then analyzed through mass spectrometry. They can even be deposited after an accurate selection of their size (Rauschenbach et al. 2006, Böttger et al. 2007). More recently, new methods have emerged allowing a reduction of the size dispersion that is a prerequisite for cluster self-assembling. By those ways clusters are generally passivated with ligands or surface-active molecules having an hydrophilic head and an hydrophobic chain (surfactants). Depending on their shape, related to the ratio between the head size and chain length, these molecules may form direct or reverse dynamic micelles (Pileni 1989) that can be viewed as molds in which nanoparticles can be chemically synthesized. For instance, the reverse micelles form aqueous droplets in nonaqueous solution that serve as nanoreactors for the cluster growth (Lisiecki and Pileni 1995, Lisiecki et al. 1996). By adding anions that adsorb on clusters, the final cluster size may be accurately controlled. Moreover, the shape may be also monitored by taking advantage of a selective adsorption on the various faces of the cluster during the growth. The mean size of the so-produced clusters is of a few nanometers in diameter, and nanorods, nanodisks, or nanowires may be obtained as well. This process reduces considerably the size dispersion and is thus a suitable way to generate 2D or 3D superlattices (Schmitt et al. 1997, Courty et al. 2001) that are model systems for investigating the influence of the cluster interactions on their optical or magnetic properties.

24.3.1.2 Physical Methods

An alternative way to generate clusters is the physical route. Two main approaches are usually considered. The first starts with the production under vacuum of an atomic vapor (thermal heating, laser ablation, etc.) that is further deposited on a suited substrate (de Heer 1993, Perez et al. 1997, 2001). Taking advantage of their diffusion on the surface, atoms can meet or be trapped on defects so as to form nucleation seeds that further grow under the form of clusters by the subsequent capture of other mobile atoms. This gives rise to 2D assemblies of cluster islands with size and shape dispersions that are generally difficult to control accurately. The atoms can also be deposited simultaneously with a dielectric matrix in which they are trapped and isolated. A further thermal treatment may then promote diffusion in the matrix volume so as to induce their grouping and the formation of embedded clusters. In this way, thin nanostructured films can be obtained (3D arrangement), but the cluster size and concentration are hardly controlled independently. It must be stressed that such samples can also be obtained, before annealing, by implanting high-energy metallic ions in a preformed thin film. A second method allows an independent and easier control of the cluster size and volumic concentration. It consists in directly producing clusters in the gas phase and depositing them on a substrate simultaneously with an embedding matrix. The available sources generating cluster beams work generally on the following principle (de Heer 1993): a metallic vapor obtained for instance by heating a metal in an oven is mixed with an inert gas to induce the cluster nucleation and growth. Then, the mixture undergoes an expansion through a nozzle giving birth to a continuous cluster beam. Depending on the temperature and pressure conditions in the source, the size range may strongly vary from a source to another one (seeded supersonic beam sources [Larsen et al. 1974], Sattler sources [Sattler et al. 1980], etc.). Instead of a metallic vapor, a plasma can be produced by lasers (pulsed laser vaporization sources [Smalley 1983, Milani and de Heer 1990]), by an electric discharge (PACIS sources [Siekmann et al. 1991]), or by magnetron sputtering (Hahn and Averback 1990). Cluster growth takes place during the high cooling of the plasma with an inert gas and the so-formed clusters may be charged or neutral. The main advantage is that clusters of refractory metals or alloys may be produced. Moreover, the cluster size distribution can be varied by controlling the inert gas pressure in the source (Richtsmeier et al. 1985).

The co-deposition technique of preformed clusters by the so-called low-energy cluster beam deposition (LECBD) has proven to be one of the most efficient technique for elaborating nanostructured thin films for optical as well as for other investigations. Here we mainly focus on the optical studies of supported nanoparticles, but it must be emphasized that many experiments have been carried out on free cluster beams produced by sources such as those mentioned before. This will be outlined in the following.

24.3.2 Techniques of Optical Spectroscopy

Metallic clusters may be optically investigated either in the gas phase or in nanostructured films. In the former, several methods are available to probe their optical response such as photodissociation, multiphoton ionization (MPI) or photo-depletion spectroscopy (Kreibig and Vollmer 1995). They are of particular importance as they allow to get information about their electronic structure. The principle of such methods is the following: a cluster absorbs a given number of photons of known energy, and its desexcitation leads to the appearance of at least two reaction products (electrons, ions, or neutral fragments) that are detected and counted by mass spectrometry. The nature of these products and the wavelength dependence of their counting rates give insight into the electronic structure of the primary cluster. MPI is rather devoted to very small clusters (of a few atoms), whereas beam depletion spectroscopy can be extended to larger clusters. By using size-selected cluster ion beams and detecting the fragment-size distribution, it is also possible to deduce photo-absorption cross sections (Bréchignac et al. 1992, 1993).

Concerning embedded clusters (samples of nanostructured films or of colloids in solution), the general setup to investigate their optical properties is composed of a light source directed through the sample and detectors for the measurements of the incident, transmitted, reflected, and scattered light that may be analyzed with a grating monochromator (Fox 2001) (see Figure 24.11). The transmittivity T yields the extinction of light correlated to absorption and scattering losses.

For small clusters, the scattering being negligible with respect to absorption, the transmittivity directly reflects absorption (if the thin film reflectivity R can be neglected) through the Beer–Lambert law: $T = (I_t/I_o) = e^{-K_{\text{obs}}e}$, where $K_{\text{abs}} = (4\pi/\lambda)\,\kappa(\omega)$, κ being the imaginary part of the effective optical index of the composite sample. This effective optical index may be estimated through effective medium theories, for instance the Maxwell–Garnett theory developed in the frame of the dipolar approximation for small embedded spheres and valid for low-volumic particle concentrations (<10%). Note that the particles can be considered almost isolated from each other if the volumic metal proportions are lower than a few percents. The optical response can then be compared to the expected response of a single cluster in a transparent medium. Of course, this requires an accurate characterization of the matrix in which the clusters are embedded. On the other hand, in the case of weakly absorbing thin films, in particular when the resonance is strongly damped as is observed in small clusters), the reflectivity can no longer be neglected and multilayer effects (Fabry–Pérot fringes) may blur the intrinsic response of the embedded clusters. To get rid of this spurious effect, a simple trick consists in using p-polarized light under Brewster incidence when measuring transmission (Cottancin et al. 2003).

All these measurements are carried out on cluster assemblies and the optical response corresponds to the average response of all the probed clusters. The unavoidable geometry fluctuations in the samples make delicate a precise determination of their specific properties. To overcome this difficulty the clusters may be size selected (Issendorff and Palmer 1999, Alayan et al. 2004) before co-deposition, but shape and environment fluctuations will persist. Another approach developed within the past 10 years aims at investigating a single deposited or embedded metallic nanoparticle. It requires highly sensitive spectroscopic methods since the optical density of the sample is considerably lower than in conventional nanostrutured films. Such investigations may be achieved through near-field or far-field microscopy. Indeed, when a particle is excited by an incident field, the diffracted field gives rise to evanescent waves in the vicinity of the particle and propagating waves far from the particle. In near-field microscopy an optical fiber tip is used as a probe of the field near the particle. By scanning the position of the tip on a sample, a map of the surface covered with deposited nanoparticles may be recorded, but the resolution is still limited by the tip size. In this way, gold nanoparticles of 20 nm in diameter have been detected (Klar et al. 1998). However, the interaction between the tip and the nanoparticles prevents a straightforward deduction of the



FIGURE 24.11 Schematic experimental setup for conventional scattering and extinction spectroscopy. Light sources and detectors may be combined with monochromators.

particle intrinsic properties. Far-field is more convenient as the obtained response is easier to compare with theory. To "bypass" the Rayleigh criterion, the basic idea is to isolate nanoparticles from each other by depositing them with very low concentration (less than one particle per square micrometer) to be sure that only one particle will be shined by a highly focused light beam. The most widespread technique is the dark-field confocal microscopy allowing the measurement of single-nanoparticle scattering and which can be viewed as an improvement of the ultramicroscope of Zsigmondy. The high sensitivity is obtained by using high numerical aperture refractive objectives with a mask (Dijk et al. 2006) or reflective objectives, both generating a shadow cone in which the scattered light can be collected with a negligible background signal. Nevertheless, as the scattering varies as V^2, such investigations remain restricted to particles larger than 20 nm in diameter (Tamaru et al. 2002, Raschke et al. 2003). On the other hand, interferometric methods have been also developed to detect smaller nanoparticles (Lindfors et al. 2004, Berciaud et al. 2005).

Besides scattering experiments, it is also possible to detect the overall extinction of light by a nanoparticle in a transmission measurement configuration, just as in conventional spectrophotometers. Using tightly focused light beams in a confocal geometry, an increased sensitivity may be reached thanks to a spatial modulation of the sample and a lock-in detection (Arbouet et al. 2004, Muskens et al. 2006, Billaud et al. 2007). The main advantage of this technique is that it enables the absolute measurement of the extinction cross-section if the incident field distribution in the focal plane is accurately characterized. Finally, it should be noticed that scattering or extinction measurements on single nanoparticles may be correlated to their electron microscopy images by using substrates compatible with optical measurements and electron microscopy (Tamaru et al. 2002, Billaud et al. 2008).

24.3.3 Experimental Results

This last section draws up some of the major experimental results relative to size and shape effects on the optical properties of metal clusters, emphasizing the role of the SPR as a probe of the internal structure of the cluster material. Because of the wealth of publications in this field for 20 years, the relevant state of the art will not be exhaustive. A more complete bibliography may be found in the appendix of Kreibig and Vollmer (1995) as well as in the references list cited below.

24.3.3.1 Size and Shape Effects in the Optical Response of Metal Clusters

24.3.3.1.1 Alkali Clusters

Let us first examine the experimental results concerning the SPR in alkali clusters. As mentioned before, alkalis are the simplest metals and their clusters represent ideal model systems that were widely studied during the 1990s. Because of their high sensitivity toward oxidization, most of the corresponding experiments were usually performed on cluster beams in the gas phase through photo-evaporation or depletion spectroscopy (Bréchignac et al. 1992, 1993, Borggreen et al. 1993, Pedersen et al. 1993). In all cases (lithium, sodium, potassium), the optical spectra are dominated from very small sizes (~8 atoms) by a broad absorption peak (the SPR) qualitatively similar to the classical predictions of the Drude model. Nevertheless, a red-shift of the resonance with decreasing size, correlated to the increasing spillout influence, is patent (see Figure 24.12a) whatever the element. The signature of the spillout effect has been also observed in the measurements of the static polarizability of sodium and lithium clusters (Knight et al. 1985, Bénichou et al. 1999). Indeed we have already underlined that because of the electronic spillout, the sphere containing the conduction electrons (of effective radius R_e) is larger than the geometrical volume enclosing the ionic cores (sphere of radius R_C). The main consequence is a correlated increase of the static cluster polarizability since it is proportional to the effective volume $(4/3)\pi R_e^3$. The calculations in the frame of the time-dependent local-density-approximation formalism (TDLDA) (within the simple jellium model) that have been shown in Figure 24.7 reproduce qualitatively the experimental results, in particular the red-shift of the resonance with decreasing size. Nevertheless, it should be emphasized that these calculations slightly overestimate the absolute value of the SPR in sodium clusters (the SPR occurs generally around 2.5–2.8 eV for sizes smaller than 100 atoms per cluster, whereas the calculations give values around 3 eV). In lithium the disagreement is larger. These discrepancies show that various ingredients, not included in the standard jellium model, have a noticeable influence. For instance the ionic-core polarization, which is disregarded in this framework, may induce a shift of the resonance toward smaller energies. This shift can be viewed classically through Equation 24.8 in which ε_1^{IB} would be chosen different from zero. Moreover, the profile of the effective potential confining the conduction s-electrons and hence also the electron density are known to be softened when electron–ion interaction pseudo-potentials (non-coulombic) are taken into consideration (Rubio et al. 1993, Lermé et al. 1995). The surface softness increases the electron spillout relative to the standard jellium model in which the electron–ion interaction is assumed to be coulombic. At last, the nonlocal character of the electron–ion pseudo-potential results in an increase of the effective conduction electron mass (for instance, in lithium the effective mass is $m_{\text{eff}} = 1.4\, m_e$). Both these effects lead to a decrease of the bulk plasma angular frequency ω_P, and hence of ω_{SPR}. On the other hand, the Drude parametrization of the dielectric function also leads to a larger value of the SPR frequency (~3.5 eV) than that deduced from experimental measurements on thin alkali films (~3.1 eV), showing similarly the crudeness of the model for the bulk phase. This shows that the conduction electrons do not really constitute a free electron gas in the bulk. If the details of the cluster electronic structure are obviously of great importance to obtain an accurate quantitative description of the optical properties of alkali clusters, the possible deviation of their shape from the ideal case of a sphere relative to the ideal case of a sphere deserves to be considered with care. The one-peak resonance observed for Na_{21}^+ and Na_{41}^+ (see Figure 24.12b) indicates that these clusters adopt an almost spherical shape since these magic sizes correspond to exact electronic closures in



FIGURE 24.12 (a) Photoabsorption cross sections for large lithium clusters ions Li_n^+ versus the photon energy. (From Bréchignac, C. et al., *Phys. Rev. Lett.*, 70, 2036, 1993. With permission.) (b) Photoabsorption cross sections per electron versus the photon energy, for various sizes of sodium clusters. (From Pedersen et al., *Z. Phys. D*, 26, 281, 1993. With permission.) In both figures, the lines are Lorentzian fits of the data.

the spherical jellium model. For non-magic sizes, the resonance is asymmetric, reflecting the existence of at least two resonance modes corresponding to plasmon excitations along the different principal axes of deformation of the cluster (see Figure 24.12b). One can thus say that the profile of resonance is an efficient probe of the cluster shape. Nevertheless, for very small sizes the multi-peak absorption spectra also reflect the electronic-level quantization.

At last, potassium and sodium clusters have been also investigated once deposited under ultrahigh vacuum (UHV) and exposed to various gases (Iline et al. 1999). Since the gases modify their surface tension after being adsorbed, clusters may experience a change in shape that can be detected through variations in absorption spectra. Nevertheless, the influence of the gas is not so easy to interpret as the size was not well controlled.

24.3.3.1.2 Noble Metal Clusters

In noble metal clusters, as the valence d-band and the conduction s–p band are energetically close to each other, the SPR emerges more or less easily depending on the element and is strongly influenced by the d-electrons. The simplest metal is silver because the threshold for interband transitions in the bulk is quite high (around 4 eV). The SPR emerges for very small sizes, in the range of less than 20 atoms, and it was measured both for ionic clusters (Tiggesbäumker et al. 1993) and for size-selected neutral clusters deposited in a rare gas matrix (Fedrigo et al. 1993). Nevertheless, the core electrons (d electrons mainly) play an important role. The screening they induce is responsible for a global red-shift of the SPR frequency as compared to the frequency expected from the standard jellium model (Pollack et al. 1991, de Heer 1993, Liebsch 1993a,b, Rubio and Serra 1993, Kreibig and Vollmer 1995, Lermé et al. 1998a,b, Palpant et al. 1998). For gold, the threshold for interband transitions is much lower (of the order of 2 eV). This results in a stronger red-shift of the SPR frequency and, in addition, a strong damping and broadening of the resonance band, especially for small particles (Kreibig and Vollmer 1995, Alvarez et al. 1997, Palpant et al. 1998, Gaudry et al. 2001). For copper, the interband threshold is similar to that of gold, of the order of 2 eV. The SPR occurs in the same frequency range as gold, but experiments show that the resonance band is much more damped and even disappears at low sizes for particles of typically 2–3 nm in diameter (few hundred of atoms) depending of the observation conditions (Lisiecki and Pileni 1995, Celep et al. 2004), e.g., on the dielectric constant of the matrix in which the particles are embedded. This specific behavior of copper clusters will be explained below.

Figure 24.13 illustrates the size evolution of the SPR in noble metal clusters in a size range below 10 nm in diameter for which quantum size effects are expected. The upper part of the figure displays experimental results on the size evolution of the SPR on the samples of noble metal clusters (copper, silver, and gold) embedded in alumina matrix (Lermé et al. 1998b, Palpant et al. 1998, Lermé 2000, Celep et al. 2004, Cottancin et al. 2006) at low concentrations (the matrix and the cluster size distributions have been carefully characterized). As the samples were elaborated with the same protocol and in the same matrix, a comparative study can be achieved. In gold clusters, the SPR band occurs around 2.3–2.4 eV in the same spectral region than the threshold of the interband transitions (2 eV), which continue, as for them, to induce adsorption in the UV range. Moreover, a blue shift and a damping of the resonance are observed when the cluster size decreases. In silver clusters, the SPR band peaks at about 2.9–3.0 eV, well below 4 eV the threshold of the interband transitions. Only a very small blue-shift of the resonance is measured when the cluster size decreases. For copper, the SPR band emerges hardly at about 2.15 eV from the steep increase of the interband transitions. Actually in copper the interband threshold is close to 2 eV (as in gold), but the corresponding absorption increases much more rapidly above 2 eV. The damping and the broadening of the SPR band, with decreasing sizes, are the most important features of the experimental observations, rather than a clear blue-shift as in gold. At very small sizes, the SPR



FIGURE 24.13 Size evolution of the experimental (top) and theoretical (bottom) absorption spectra obtained in the semi-quantal model for noble metal clusters of copper, silver and gold embedded in alumina (Cottancin et al. 2006). The volumic concentrations of metallic clusters embedded in the transparent matrix are in all cases rather low (<5%–6%) allowing to consider these systems as isolated clusters randomly dispersed. (From Cottancin, E. et al., *Theor. Chem. Acc.*, 116, 514, 2006.)

band tends to vanish in the steep rising edge of the interband transitions, but in the present experiments, it was not possible to produce clusters as small as 2 nm.

In the present size range (2 nm < ϕ < 5 nm), the Mie theory is not suited to explain the size evolution of the SPR, even if a size dependence of the scattering rate is assumed (see Equation 24.11). Indeed, the size evolution obtained from such calculations (Figure 24.5) shows a red-shift of the resonance in gold and copper in contradiction with experimental results. For a better interpretation of the experimental results, and as long as large particles are involved, a structureless jellium-type model approach seems quite appropriate and reasonable for investigating mean-size trends over broad-size domains. The calculations are based on the TDLDA within a jellium model including phenomenologically the absorption and screening properties of both the ionic-core background and the surrounding matrix through their dielectric functions $\varepsilon^{IB}(\omega)$ and ε_m (Lermé 2000). A first ingredient added in the model, well established in surface physics and correlated to the spatial localization of d-electrons wavefunctions, is a skin of a vanishing polarizability of thickness d of a few angstroms in which the polarization of the d-core electrons is ineffective ($\varepsilon^{IB} = 1$ in this shell). This skin of ineffective polarizability was firstly introduced by Liebsch for silver surfaces (Liebsch 1993a) and by Kresin for clusters (Kresin 1995). Moreover, a vacuum ring surrounding the particle, of thickness d_m, is introduced in the model in order to mimic the local matrix porosity estimated experimentally (see Figure 24.14).

Figure 24.13 shows the comparison between experiment and this semi-quantal theory. The theoretical calculations well reproduce the experimental trends when the cluster size decreases, namely the strong blue-shift of the SPR for gold, the very small blue-shift for silver, and the gradual disappearance of the SPR in the rising edge of the interband transitions for copper. This blue-shift is mainly due to the skin of ineffective screening by the d-electrons, which results in an all the more important blue-shift that the sizes are small. This blue-shift competes with the red-shift associated with the spillout of the s-electrons, that is a pure quantum effect. In gold, the blue-shift is predominant as compared to the red-shift. In silver, both are close to be compensated, inducing a rough quenching of the size effects. This different behavior of gold and silver clusters is easy to understand because the real part of ε^{IB} (which quantifies the screening) is much smaller in silver than in gold (of the order of 4 and 11, respectively, in the spectral range of the SPR [Cottancin et al. 2006]). The difference between gold and copper may be understood with regard to their respective dielectric functions. The main difference lies in the steeper increase of the imaginary part of ε^{IB} for copper, just above the interband threshold, leading to a stronger damping of the resonance. Actually, the vanishing of the resonance in copper is a signature of a blue-shift of the SPR, resulting in an increasing coupling with IB transitions.

Finally, the semi-quantal calculations appear to be the best compromise between completely ab initio methods limited to relatively small sizes and completely classical calculations that disregard the quantum size effects. These semi-quantal calculations, with a very limited number of semiempirical parameters, are able to predict the optical properties of the three noble metals in a size range from 1.5 to 10 nm in diameter. Above 10 nm, the quantum size effects are negligible and the Mie theory is well adapted.

As for shape effects, experiments have been performed on small silver cluster beams showing similar results as in alkalis (Tiggesbaümker et al. 1992, Tiggesbäumker et al. 1993). However the shape influence on the optical response of noble metal clusters and nanoparticles (essentially gold and silver) has been mostly investigated within the past 10 years on single nanoparticles. Indeed, the tremendous advances in the synthesis of various nano-objects (such as rods, prisms, chains, core/shell structures, pairs of nanoparticles, etc.) opened up a new field of investigations on their optical properties, in a size range where the multipolar effects are of major importance. For instance, silver nanoparticles of various shapes have been studied using dark-field optical microscopy and spectroscopy, in correlation with their electron microscopy images (Mock et al.



FIGURE 24.14 (Left) *Jellium* model: ionic (gray) and electronic (black line) densities. (Right) Semi-quantal model: cluster of radius $R_C = r_S N_e^{1/3}$ in matrix of dielectric function ε_m (d et d_m denote respectively the thicknesses of the shell of reduced polarizability and the vacuum ring surrounding the particle).



FIGURE 24.15 **(See color insert following page 20-14.)** (Top) Color image of a typical sample of silver nanoparticles as viewed under the dark-field microscope. The brightness of the particles increases from blue to red due to both the intrinsic optical scattering cross section and the spectral output of the light source (the red particle is overexposed). This image is correlated to its electron microscopy image (Bottom). (Reprinted from Mock, J.J. et al., *J. Chem. Phys.*, 116, 6755, 2002. With permission.)

2002). The spectral position of the resonance is so much shape dependent that spheres appear blue, pentagons green, and triangles mostly red (see Figure 24.15). A significant dispersion of the SPR peak position for triangular particles is observed. This phenomenon is probably due to the high sensitivity of the resonance to the height, the edge length, and the apex shapes (sharp or truncated) of the triangles as has been evidenced through numerical calculations based on the discrete dipole approximation (Sherry et al. 2006).

The main conclusion concerning all the numerous studies for which the state of the art is out of the topic of this chapter is that the SPR may be tailored by varying the shape or the structure of the nano-objects. Consequently, the attachment of specific molecules (such as proteins or antibodies) on the nanoparticle surface can be detected by an induced shift of the SPR (biosensors) (McFarland and Duyne 2003).

24.3.3.2 The SPR as a Probe of the Internal Structure of Bimetallic Clusters

Bimetallic particles are of double interest since they disclose size- and shape-dependent properties and mirror the original features of bulk alloys (a complete bibliography about nanoalloys can be found in Ferrando et al. (2008)). Depending on the thermodynamic properties of both components, mixed particles can form either homogeneous alloys or segregated core/shell structures. An insight into the bulk properties of both constituent materials (Wigner–Seitz radius (r_S), surface energies) and their corresponding binary phase diagrams brings indications about the possible structure of the composite clusters. In general, one expects the metal component with the lower surface energy to accumulate preferentially at the surface. However, in the case of systems in solution like colloids, one has to be careful with such simple rules, because the kinetics of reduction as well as the surface-adsorbed ions and the surrounding medium also come into play. Thermodynamical equilibrium conditions are not necessary reached and such particle architectures may be only metastable in this respect.

The dielectric function of mixed clusters being governed by its overall electronic structure, the optical response of bimetallic systems will be modified by varying the relative proportion of both constituents (Kelly et al. 2003, Hubenthal et al. 2005). For instance, in the case of gold–silver nanoparticles, by far the most-studied binary system (Morriss and Collins 1964, Papavassiliou 1976, Teo et al. 1987, Mulvaney et al. 1993, Liz-Marzan and Philipse 1995, Link et al. 1999), the SPR falls between those of gold and silver for alloyed systems. On the contrary, in core/shell geometries (that can be essentially obtained by chemical ways), the optical response displays two resonance peaks for sufficiently large particles.

As an illustration, Figure 24.16 shows the evolution of the optical response with varying compositions of aqueous solutions of alloyed gold–silver nanoparticles of diameters ranging from 15 to 50 nm (Russier-Antoine et al. 2008). The spectra exhibit a single SPR whose wavelength is found to move regularly, with increasing gold content, from the silver SPR to the gold one. This observation thus rules out the possibility of a core/shell structure for which two resonances would be expected.

However, the experimental spectra cannot be correctly reproduced by the Mie theory if the dielectric function of the alloy is taken as the volume-weighted average of the pure material dielectric functions. Such an hypothesis is physically relevant if the particle can be considered as built by the stacking of pure nanodomains that individually retain the electronic structure (dielectric function) of their corresponding bulk phase. Its failure indicates that the effective dielectric function is closely related to an alloying at a much lower scale (atomic level). It cannot be simply inferred from the dielectric function of each component but must be either obtained from available experimental data on similar bulk alloys or calculated from solid-state theory assuming an alloying at an atomic scale. In this system, measurements on annealed alloys (Nilsson 1970) have been performed and the corresponding dielectric functions exhibit a regular shift of the interband transition threshold with the gold composition that is not reproduced in the average dielectric function evoked just before. If this IB threshold is taken into account, i.e., if the dielectric function reproduces correctly the one measured experimentally, the optical spectra are in agreement with the theory, confirming thus that the nanoparticles adopt an alloyed structure at an atomic level. Similar works on smaller bimetallic gold–silver clusters produced by laser vaporization and embedded in alumina had lead to the



FIGURE 24.16 **(See color insert following page 20-14.)** (Left) Normalized UV–visible spectra of Au–Ag alloy nanoparticles with varying composition. (Insert) Location of the SPR maximum as a function of the gold content. (Right) Corresponding solutions whose colors vary from the red (pure gold nanoparticles) to the yellow (pure silver nanoparticle). (From Russier-Antoine, I. et al., *Phys. Rev. B*, 78, 35436, 2008. With permission.)

same conclusions about the internal structure of clusters, near from the one of annealed alloys (Gaudry 2001). Such a homogeneous alloyed structure is the likely one (for clusters produced by physical ways) in view of both their relative surface energies and Wigner–Seitz radii and regarding the bulk phase diagram of the Au–Ag system in which homogeneous solutions are thermodynamically possible for any relative composition (Massalski et al. 1986).

In the same way, the internal structure of mixed Ni–Ag and Pt–Ag clusters of a few nanometers in diameter, produced by laser vaporization and embedded in an alumina matrix (Cottancin et al. 2003), has been investigated. Concerning the bulk properties of these materials, the phase diagram of Ni–Ag shows that Ni and Ag are immiscible over the entire composition range (Massalski et al. 1986). One can suppose that the silver atoms will move onto the cluster surface for both systems since the surface energy of silver is the lowest one and that the resulting structure will be a core/shell one. As for the Pt–Ag phase diagram, several alloys are present (Massalski et al. 1986), so the assumption of a core/shell structure has to be taken with caution. Moreover, the atomic Wigner–Seitz radii of Ag and Ni are noticeably different (r_s(Ag) = 3.02 a.u. and r_s(Ni) = 2.6 a.u.) and a pronounced lattice mismatch is expected, whereas they are closer for Pt and Ag (r_s(Pt) = 2.9 a.u.).

The experimental spectra of both systems are displayed in Figure 24.17. In the case of the Ni–Ag system, the optical properties are found to be intermediate between those of pure silver and pure nickel clusters, with an SPR enlarged and blueshifted compared to pure silver clusters. This feature can be understood within the classical Mie theory assuming a segregation between both metals in a core/shell geometry and including the reduction of the mean free path in the silver shell. Moreover, low energy ion scattering (LEIS) measurements that consist in probing the cluster surface provide the evidence that the surface of the clusters is mainly covered with silver atoms. Such results permit to conclude that the core/shell geometry with silver on the surface is the most likely structure and that the dielectric function of the bimetallic system remains closely connected with the ones of its constituents. As for Pt–Ag clusters, LEIS measurements lead also to the conclusion that the cluster surface is mainly composed of silver; nevertheless, the absorption spectra do not exhibit a marked SPR, in contradiction with the calculated spectra for which a clear resonance is expected as in Ni–Ag clusters. Calculations assuming a dielectric function equal to the volumic-weighted average of the constituent ones predict also a large resonance band. Those results suggest that the Pt–Ag particles do not form a segregated core/shell structure, but rather an alloyed core with a surface enriched with silver atoms. Monte Carlo simulations (Calvo et al. 2008) performed on these systems show the same trends as from small sizes. In particular at zero temperature, silver and platinum seem to be segregated, whereas an increase in the temperature



FIGURE 24.17 (Left) (a) Evolution of the optical absorption spectra of Ni–Ag clusters (optical diameter of about 2.6–2.7 nm) with the nickel proportion. (b) Theoretical absorption K_{abs} within the classical core/shell model when the reduction of the mean free path in the silver shell is taken into account. (Right) (a) Evolution of the optical absorption spectra of Pt–Ag clusters (optical diameter of about 4 nm) with the platinum proportion. (b) Theoretical absorption K_{abs} within the classical core/shell model.

induces a better alloying with the surface remaining rich in silver. Finally, one can conclude that the lack of the SPR in experimental spectra shows in this case that the dielectric function of the bimetallic system is not simply correlated to those of its constituents as it is the case for Ni–Ag.

24.4 Conclusion and Outlooks

This chapter intended to shed light on the main ingredients involved in the linear optical properties of metallic clusters and nanoparticles such as size, shape, environment, and the chemical structure of particles. The optical studies of nanoparticles are naturally a wide-ranging field including dynamical processes or nonlinear optics that have not been developed in this chapter.

It has been shown that the colors of samples containing clusters or nanoparticles originate from the strong absorption and scattering (SPR) of the metal nanoparticles when the frequency of the exciting electromagnetic field is coherent with the collective conduction electron motion.

In small particles ($\phi < 20$–30 nm), the optical response can be in a first approximation described in the frame of the dipolar approximation. In addition, quantum size effects have to be taken into account for cluster sizes below 5–10 nm in diameter, involving a red-shift of the SPR in alkali clusters because of the increasing effect of the electronic spillout. In noble metals, the polarization of the core electrons (*d* electrons mainly) and their ineffective influence near the cluster surface result in a blue-shift that competes with the red-shift associated with the spillout effect. The size evolution of the SPR depends then on the element (Cu, Ag, or Au) constituting the clusters.

For larger sizes ($\phi > 20$–30 nm), the Mie theory accounts well for the optical response of spherical nanoparticles in a homogeneous medium. When the size increases, higher resonance modes become dominant and the SPR is red-shifted and spectrally broadened.

The synthesis of new particles of various sizes and shapes in the past decades and the development of highly sensitive methods for probing single nano-objects have opened a new field of investigations showing that the SPR may be tailored by tuning the shape or the composition of the metal particles. The understanding of their behavior with the help of computational methods and experiments on single particles gives high hopes for potential applications. For instance, the high sensitivity of the SPR toward the local neighborhood of the particle or the chemical nature of its surface can be used for making biosensors, giving information about surface changes of the particles, as for instance the red-shift observed in silver nanoparticles after several molecules have adsorbed (McFarland and Duyne 2003). Moreover the large local field enhancement that occurs near the particle surface is being used in Surface-Enhanced Raman Spectroscopy (Campion and Kambhampati 1998) or Plasmon Enhanced Fluorescence (Lee et al. 2004). The strong absorption of metal nanoparticles can even be exploited in plasmonic photothermal therapy (Dickerson et al. 2008, El-Sayed et al. 2006).

Acknowledgments

The authors are grateful to F. Calvo for the reading of the chapter and for his fruitful remarks.

References

Alayan, R., L. Arnaud, M. Broyer et al. (2004), Application of a static quadrupole deviator to the deposition of size-selected cluster ions from a laser vaporization source, *Rev. Sci. Instrum.*, **75**, 2461.

Alvarez, M. M., J. T. Khoury, T. G. Schaaff et al. (1997), Optical absorption spectra of nanocrystal gold molecules, *J. Phys. Chem. B*, **101**, 3706.

Arbouet, A., D. Christofilos, N. Del Fatti et al. (2004), Direct measurement of the single-metal-cluster optical absorption, *Phys. Rev. Lett.*, **93**, 127401.

Ashcroft,N. W. and N. D. Mermin (1976), *Solid State Physics*, International Edition, Saunders College, Philadelphia, PA.

Barber, D. J. and I. C. Freestone (1990), An investigation of the origin of the colour of the Licurgus cup by analytical Transmission Electron Microscopy, *Archaeometry*, **32**, 33–45.

Bénichou, E., R. Antoine, D. Rayane et al. (1999), Measurement of static electric dipole polarizabilities of lithium clusters: Consistency with measured dynamic polarizabilities, *Phys. Rev. A*, **59**, R1–R4.

Berciaud, S., L. Cognet and B. Lounis (2005), Photothermal absorption spectroscopy of individual semiconductor nanocrystals, *Nanoletters*, **5**, 2160.

Berthier, S. (1993), *Optique des Milieux Composites*, Polytechnica, Paris, France.

Billaud, P., J.-R. Huntzinger, E. Cottancin et al. (2007), Optical extinction spectroscopy of single silver nanoparticles, *Eur. Phys. J. D*, **43**, 271–274.

Billaud, P., S. Marhaba, E. Cottancin et al. (2008), Correlation between the extinction spectrum of a single metal nanoparticle ant its electron microscopy image, *J. Phys. Chem. C*, **112**, 978–982.

Blanc, J., V. Bonacic-Koutecky, M. Broyer et al. (1992), Evolution of the electronic structure of lithium clusters between four and eight atoms, *J. Chem. Phys.*, **96**, 1793.

Bohren, C. F. and D. P. Huffman (1983), *Absorption and Scattering of Light by Small Particles*, Wiley, New York.

Bonacic-Koutecky, V., P. Fantucci, and J. Koutecky (1991), Quantum chemistry of small clusters of elements of groups Ia, Ib, and IIa: Fundamental concepts, predictions, and interpretation of experiments, *Chem. Rev.*, **91**, 1035–1108.

Bonacic-Koutecky, V., V. Veyret, and R. Miltric (2001), Ab initio study of the absorption spectra of Ag_n (n = 5–8) clusters, *J. Chem. Phys.*, **115**, 10450.

Borggreen, J., P. Chowdhury, N. Kebaïli et al. (1993), Plasma excitations in charged sodium clusters, *Phys. Rev. B*, **48**, 17507.

Böttger, P. H. M., Z. Bi, D. Adolph et al. (2007), Electrospraying of colloidal nanoparticles for seeding of nanostructure growth, *Nanotechnology*, **18**, 105304.

Brack, M. (1993), The physics of simple metal clusters: Self-consistent jellium model and semiclassical approaches, *Rev. Mod. Phys.*, **65**, 677–731.

Bréchignac, C., P. Cahuzac, N. Kebaïli, J. Leygnier, and A. Sarfati (1992), Collective resonance in large free potassium cluster ions, *Phys. Rev. Lett.*, **68**, 3916.

Bréchignac, C., P. Cahuzac, J. Leygnier, and A. Sarfati (1993), Optical response of large lithium clusters: Evolution toward the bulk, *Phys. Rev. Lett.*, **70**, 2036–2039.

Brinker, C. J. and G. W. Scherer (1990), *Sol-Gel Science*, Academic Press, San Diego, CA.

Calvo, F., E. Cottancin, and M. Broyer (2008), Segregation, core alloying, and shape transitions in bimetallic nanoclusters: Monte Carlo simulations, *Phys. Rev. B*, **77**, 121406(R).

Campion, A. and P. Kambhampati (1998), Surface-enhanced Raman scattering, *Chem. Soc. Rev.*, **27**, 241–250.

Canut, B., M. G. Blanchin, V. Teodorescu, and A. Traverse (2007), Structure of Ni/SiO_2 films prepared by sol-gel dip coating, *J. Non Cryst. Solids*, **353**, 2646–2653.

Celep, G., E. Cottancin, J. Lermé et al. (2004), Optical properties of copper clusters embedded in alumina: An experimental and theoretical study of size dependence, *Phys. Rev. B*, **70**, 165409.

Clemenger, K. (1985), Ellipsoidal shell structure in free-electron metal clusters, *Phys. Rev. B*, **32**, 1359–1362.

Cohen-Tannoudji, C., B. Diu, and F. Laloë (1996) *Mécanique Quantique, Tome II*, Hermann, Paris, France.

Cottancin, E., G. Celep, J. Lermé et al. (2006), Optical properties of noble metal clusters as a function of the size: Comparison between experiments and a semi-quantal theory, *Theor. Chem. Acc.*, **116**, 514.

Cottancin, E., M. Gaudry, M. Pellarin, et al. (2003), Optical properties of mixed clusters: Comparative study of Ni/Ag and Pt/Ag clusters, *Eur. Phys. J. D*, **24**, 111–114.

Courty, A., C. Fermon, and M.-P. Pileni (2001), "Supra Crystals" made of nanocrystals, *Adv. Mater.*, **13**, 254.

De, G., M. Gusso, L. Tapfer et al. (1996), Annealing behavior of silver, copper and silver-copper nanoclusters in a silica matrix synthesized by the sol-gel technique, *J. Appl. Phys.*, **80**, 6734.

de Heer, W. A. (1993), The physics of simple metal clusters: Experimental aspects and simple models, *Rev. Mod. Phys.*, **65**, 611–675.

Dickerson, E. B., E. C. Dreaden, X. Huang et al. (2008), Gold nanorod assisted near-infrared plasmonic photothermal therapy (PPTT) of squamous cell carcinoma in mice, *Cancer Lett.*, **269**, 57–66.

Dijk, M. A. V., A. L. Tchebotareva, M. Orrit et al. (2006), Absorption and scattering microscopy of single nanoparticles, *Phys. Chem. Chem. Phys.*, **8**, 3486.

Doremus, R., S. C. Kao, and R. Garcia (1992), Optical absorption of small copper particles and the optical properties of copper, *Appl. Opt.*, **31**, 5773.

Drude, P. (1900a), Zur Elektronentheorie der Metalle, *Ann. Phys.*, **306**, 566–613.

Drude, P. (1900b), Zur Elektronentheorie der Metalle; II. Teil. Galvanomagnetische und thermomagnetische Effecte, *Ann. Phys.*, **308**, 369–402.

Eckardt, W. (1985), Size-dependent photoabsorption and photoemission of small metal particles, *Phys. Rev. B*, **31**, 6360.

El-Sayed, I. H., X. Hunang, and M. A. El-Sayed (2006), Selective laser photo-thermal therapy of epithelial carcinoma using anti-EGFR antibody conjugated gold nanoparticles, *Cancer Lett.*, **239**, 129–135.

Faraday, M. (1857a), The Bakerian lecture: Experimental relations of gold (and other metals) to light, *Philos. Trans. R. Soc. Lond.*, **147**, 145–181.

Faraday, M. (1857b), Experimental relations of gold (and other metals) to light, *Proc. R. Soc. Lond.*, 145–181.

Fedrigo, S., W. Harbich, and J. Buttet (1993), Collective dipole oscillations in small silver clusters embedded in rare-gas matrices, *Phys. Rev. B*, **47**, 10706.

Ferrando, R., J. Jellinek, and R. L. Johnston (2008), Nanoalloys: From theory to applications of alloys clusters and nanoparticles, *Chem. Rev.*, **108**, 845.

Fox, M. (2001), *Optical Properties of Solids*, Oxford University Press, New York.

Gaudry, M., J. Lermé, E. Cottancin et al. (2001), Optical properties of $(Au_xAg_{1-x})_n$ clusters embedded in alumina: Evolution with size and stoichiometry, *Phys. Rev. B*, **64**, 085407.

Granqvist, C. and O. Hunderi (1978), Optical absorption of ultrafine metal spheres with dielectric cores, *Z. Phys. B: Condens. Matter*, **30**, 47–51.

Hahn, H. and R. S. Averback (1990), The production of nanocrystalline powders by magnetron sputtering, *J. Appl. Phys.*, **67**, 1113.

Harb, M., F. Rabilloud, D. Simon et al. (2008), Optical absorption of small silver clusters: Ag_n, (n = 4–22), *J. Chem. Phys.*, **129**, 194108.

Hohenberg, P. and W. Kohn (1964), Inhomogeneous electron gas, *Phys. Rev.*, **136**, B864.

Hubenthal, F., T. Ziegler, C. Hendrich, M. Alschinger, and F. Träger (2005), Tuning the surface plasmon resonance by preparation of gold-core/silver-shell and alloy nanoparticles, *Eur. Phys. J. D*, **34**, 165–168.

Hunt, L. B. (1976), The true story of purple of cassius. The birth of gold-based glass and enamel colours, *Gold Bull.*, **9**, 134–139.

Iline, A., M. Simon, F. Stietz, and F. Träger (1999), Adsorption of molecules on the surface of small metal particles studied by optical spectroscopy, *Surf. Sci.*, **436**, 51–62.

Issendorff, B. V. and R. E. Palmer (1999), A new high transmission infinite range mass selector for cluster and nanoparticle beams, *Rev. Sci. Instrum.*, **70**, 4497.

Jain, P. K. and M. A. El-Sayed (2007), Universal scaling of plasmon coupling in metal nanostructures: Extension from particle pairs to nanoshells, *Nano Lett.*, **7**, 2854–2858.

Johnson, P. B. and R. W. Christy (1972), Optical constants of the noble metals, *Phys. Rev. B*, **6**, 4370–4379.

Kahnert, N. M. (2003), Numerical methods in electromagnetic scattering theory, *J. Quant. Spectrosc. Radiative Trans.*, **79–80**, 775–824.

Kawabata, A. and R. Kubo (1966), Electronic properties of fine metallic particles, *J. Phys. Soc. Jpn.*, **21**, 1767.

Kelly, K. L., E. Coronado, L. L. Zhao, and G. C. Schatz (2003), The optical properties of metal nanoparticles: The influence of size, shape and dielectric environment, *J. Phys. Chem. B*, **107**, 668–677.

Klar, T., M. Perner, S. Grosse et al. (1998), Surface plasmon resonance in single metallic nanoparticles, *Phys. Rev. Lett.*, **80**, 4249.

Knight, W. D., K. Clemenger, W. A. de Heer et al. (1984), Electronic shell structure and abundances of sodium clusters, *Phys. Rev. Lett.*, **52**, 2141 LP–2143.

Knight, W. D., K. Clemenger, W. A. de Heer, and W. A. Saunders (1985), Polarizability of alkali clusters, *Phys. Rev. B*, **31**, 2539–2540.

Kohn, W. and L. J. Sham (1965), Self-consistent equations including exchange and correlation effects, *Phys. Rev.*, **140**, A1133.

Kreibig, U. and C. V. Fragstein (1969), The limitation of electron mean free path in small silver particles, *Z. Phys.*, **224**, 307.

Kreibig, U. and L. Genzel (1985), Optical absorption of small metallic particles, *Surf. Sci.*, **156**, 678–700.

Kreibig, U. and M. Vollmer (1995) *Optical Properties of Metal Clusters*, Springer, Berlin, Germany.

Kresin, V. V. (1995), Collective resonances in silver clusters: Role of d electrons and the polarization-free surface layer, *Phys. Rev. B*, **51**, 1844.

Kroto, H. W., J. R. Heath, S. C. O'Brien, R. F. Curl, and R. E. Smalley (1985), C-60—Buckminsterfullerene, *Nature*, **318**, 162.

Larsen, R. A., S. K. Neoh, and D. R. Herschbach (1974), Seeded supersonic alkali atom beams, *Rev. Sci. Instrum.*, **45**, 1511.

Lee, J., A. O. Govorov, J. Dulka, and N. A. Kotov (2004), Bioconjugates of CdTe nanowires and Au nanoparticles: Plasmon-exciton interactions, luminescence enhancement, and collective effects, *Nano Lett.*, **4**, 2323.

Lermé, J. (2000), Introduction of quantum finite-size effects in the Mie's theory for a multilayered metal sphere in the dipolar approximation: Application to free and matrix-embedded noble metal clusters, *Eur. Phys. J. D*, **10**, 265.

Lermé, J., G. Bachelier, P. Billaud et al. (2008), Optical response of a single spherical particle in a tightly focused light beam: Application to the spatial modulation spectroscopy technique, *J. Opt. Soc. Am. A*, **25**, 493.

Lermé, J., B. Palpant, B. Prével et al. (1998a), Optical properties of gold metal clusters: A time dependent local density approximation investigation, *Eur. Phys. J. D*, **4**, 95–108.

Lermé, J., B. Palpant, B. Prével et al. (1998b), Quenching of the size effects in free and matrix-embedded silver clusters, *Phys. Rev. Lett.*, **80**, 5105.

Lermé, J., M. Pellarin, J. L. Vialle, and M. Broyer (1995), Effects of nonlocal ion pseudopotential on the electronic shell structure of metal clusters, *Phys. Rev. B*, **52**, 2868–2877.

Liebsch, A. (1993a), Surface plasmon dispersion and size dependence of Mie resonance: Silver versus simple metals, *Phys. Rev. B*, **48**, 11317.

Liebsch, A. (1993b), Surface plasmon dispersion of Ag, *Phys. Rev. Lett.*, **71**, 145.

Lindfors, K., T. Kalkbrenner, P. Stoller, and V. Sandoghdar (2004), Detection and spectroscopy of gold nanoparticles using supercontinuum white light confocal microscopy, *Phys. Rev. Lett.*, **93**, 037401.

Link, S. and M. A. El-Sayed (1999), Size and temperature dependance of the plasmon absorption of colloidal gold nanoparticles, *J. Phys. Chem. B*, **103**, 4212–4217.

Link, S., Z. L. Wang, and M. A. El-Sayed (1999), Alloy formation of gold-silver nanoparticles and the dependence on their absorption, *J. Phys. Chem. B*, **103**, 3529–3533.

Lisiecki, I. and M. P. Pileni (1995), Copper metallic particles synthesized "in situ" in reverse micelles: Influence of various parameters on the size of the particles, *J. Phys. Chem.*, **99**, 5077.

Lisiecki, I., F. Billoudet, and M. P. Pileni (1996), Control of the shape and the size of copper metallic clusters, *J. Phys. Chem.*, **100**, 4160–4166.

Liz-Marzan, L. M. and A. P. Philipse (1995), Stable hydrosols of bimetallic nanoparticles immobilized on imogolite fibers, *J. Phys. Chem.*, **99**, 15120–15128.

Martin, T. P. (1996), Shells of atoms, *Phys. Rep.*, **273**, 199–241.

Martin, T. P., T. Bergmann, H. Göhlich, and T. Lange (1990), Observation of electronic shells and shells of atoms in large Na clusters, *Chem. Phys. Lett.*, **172**, 209.

Massalski, T. B., J. L. Murray, L. H. Bernett, and H. Baker (1986), *Binary Alloy Phase Diagrams* (Vol. 1), American Society for Metals, Metals Park, OH.

Maxwell-Garnett, J. C. (1904), Colours in metal glasses and in metallic films, *Philos. Trans. R. Soc. Lond.*, **203**, 385.

McFarland, A. D. and R. P. V. Duyne (2003), Single silver nanoparticles as real-time optical sensors with zeptomole sensitivity, *Nano Lett.*, **3**, 1057–1062.

Mie, G. (1908), Beiträge zur Optik trüber Medien, speziell kolloidaler Metallösungen, *Ann. Phys.*, **25**, 377.

Milani, P. and W. A. de Heer (1990), Improved pulsed laser vaporization source for production of intense beams of neutral and ionized clusters, *Rev. Sci. Instrum*, **61**, 1835.

Mock, J. J., M. Barbic, D. R. Smith, D. A. Schultz, and S. Schultz (2002), Shape effects in plasmon resonance of individual colloidal silver nanoparticles, *J. Chem. Phys.*, **116**, 6755.

Morriss, R. H. and L. F. Collins (1964), Optical properties of multilayer colloids, *J. Chem. Phys.*, **41**, 3357–3363.

Mulvaney, P., M. Giersig, and A. Henglein (1993), Electrochemistry of multilayer colloids: Preparation and absorption spectrum of gold-coated silver particles, *J. Chem. Phys.*, **97**, 7061–7064.

Muskens, O. L., N. Del Fatti, F. Vallée et al. (2006), Single metal nanoparticle absorption spectroscopy and optical characterization, *Appl. Phys. Lett.*, **88**, 063109.

Nilsson, P. O. (1970), Electronic structure of disordered alloys: Optical and photoemission measurements on Ag-Au and Cu-Au alloys, *Phys. Kondens. Mater.*, **11**, 1–18.

Nogami, M., Y. Abe, and A. Nakamura (1995), Cu microcrystals in sol-gel derived glass, *J. Mater. Res.*, **10**, 2648.

Palik, E. D. (1985–1991), *Handbook of Optical Constants of Solids*, Academic Press, New York.

Palpant, B., B. Prével, J. Lermé et al. (1998), Optical properties of gold clusters in the size range 2–4 nm, *Phys. Rev. B.*, **57**, 1963.

Papavassiliou, G. C. (1976), Surface plasmons in small Au-Ag alloy particles, *J. Phys. F*, **6**, L103–L105.

Pedersen, J., S. Bjørnholm, J. Borggreen et al. (1991), Observation of quantum supershells in clusters of sodium atoms, *Nature*, **353**, 733–735.

Pedersen, J., J. Borggreen, P. Chowdhury et al. (1993), Plasmon profiles and shapes of sodium cluster ions, *Z. Phys. D*, **26**, 281–283.

Pellarin, M., E. Cottancin, B. Baguenard et al. (1995), Observation of two successive quantum supershells in a 15000-electron fermionic system, *Phys. Rev. B*, **52**, 16807.

Perez, A., P. Mélinon, V. Dupuis et al. (1997), Cluster assembled materials: A novel class of nanostructured solids with original structures and properties, *J. Phys. D*, **30**, 709.

Perez, A., P. Mélinon, V. Dupuis et al. (2001), Nanostructured materials from clusters: synthesis and properties, *Mater. Trans.*, **42**, 1460.

Perez, A., P. Mélinon, J. Lermé, and P.-F. Brevet (2007), Nanoscience (Chapter 7), *Clusters and Colloids*, Springer Verlag, Berlin/Heidelberg, Germany.

Pileni, M. P. (1989), *Structure and Reactivity in Reverse Micelles*, Elsevier Science, Amsterdam, the Netherlands.

Pollack, S. P., C. R. C. Wang, and M. M. Kappes (1991), On the optical response of Na_{20} and its relation to computational prediction, *J. Chem. Phys.*, **94**, 2496.

Raschke, G., S. Kowarik, T. Franzl et al. (2003), Biomolecular recognition based on single gold nanoparticle light scattering, *Nanoletters*, **3**, 935.

Rauschenbach, S., F. L. Stadler, E. Lunedei et al. (2006), Electrospray ion beam deposition of Clusters and Biomolecules, *Small*, **2**, 540–547.

Richtsmeier, S. C., E. K. Parks, K. Liu, L. G. Pobo, and S. J. Riley (1985), Gas phase reactions of iron clusters with hydrogen. I. Kinetics, *J. Chem. Phys.*, **82**, 3659.

Romero, I., J. Aizpurua, G. W. Bryant, and J. G. de Abajo (2006), Plasmons in nearly touching metallic nanoparticles: Singular response in the limit of touching dimers, *Opt. Express*, **14**, 9988.

Rubio, A. and L. Serra (1993), Dielectric screening effects on the photoabsorption cross section of embedded metallic clusters, *Phys. Rev. B*, **48**, 18222.

Rubio, A., J. A. Alonso, X. Blase, and S. G. Louie (1997), Theoretical models for the optical properties of clusters and nanostructures, *Int. J. Mod. Phys. B*, **11**, 2727–2776.

Rubio, A., L. C. Balbás, and J. A. Alonso (1993), Photoabsorption cross sections of sodium clusters: Electronic and geometrical effects, *Z. Phys. D*, **26**, 284–286.

Russier-Antoine, I., G. Bachelier, V. Sablonière et al. (2008), Surface heterogeneity in Au-Ag nanoparticles probed by hyper-Rayleigh scattering, *Phys. Rev. B*, **78**, 35436.

Sattler, K., J. Mühlbach, and E. Recknagel (1980), Generation of metal clusters containing from 2 to 500 atoms, *Phys. Rev. Lett.*, **45**, 821.

Schmitt, J., G. Decher, W. J. Dressick et al. (1997), Metal nanoparticle/polymer superlattice films: Fabrication and control of layer structure, *Adv. Mater.*, **9**, 61–65.

Sherry, L. J., R. Jin, C. A. Mirkin, G. C. Schatz, and R. P. V. Duyne (2006), Localized surface plasmon resonance spectroscopy of single silver triangular nanoprisms, *Nano Lett.*, **6**, 2060–2065.

Shiomi, H. and K. Umehara (2000), Preparation of SnO_2-Glass composite containing Cu particles reduced from copper ions in glass matrix—Effect of glass particle size on microstructure and electrical property, *Mater. Sci. Res. Int.*, **6**, 144–149.

Siekmann, H. R., C. Lüder, J. Faehrmann, H. O. Lutz, and K. H. Meiwes-Broer (1991), The pulsed arc cluster ion source (PACIS), *Z. Phys. D*, **20**, 417.

Smalley, R. E. (1983), Laser studies of metal cluster beams, *Laser Chem.*, **2**, 167.

Tamaru, H., H. Kuwata, H. Miyazaki, and K. Miyano (2002), Resonant light scattering from individual Ag nanoparticle and particle pairs, *Appl. Phys. Lett.*, **80**, 1826–1828.

Teo, B. K., K. Keating, and Y. H. Kao (1987), Observation of plasmon frequency in the optical spectrum of $Au_{18}Ag_{20}$ clusters: The beginning of the collective phenomenon characteristic of the bulk?, *J. Am. Chem. Soc.*, **109**, 3494–3495.

Tiggesbaümker, J., L. Köller, H. O. Lutz, and K. H. Meiwes-Broer (1992), Giant resonances in silver-cluster photofragmentation, *Chem. Phys. Lett.*, **190**, 42.

Tiggesbäumker, J., L. Köller, K. H. Meiwes-Broer, and A. Liebsch (1993), Blue shift of the Mie plasma frequency in Ag clusters and particles, *Phys. Rev. A*, **48**, R1749.

Torigoe, K., Y. Nakajima, and K. Esumi (1993), Preparation and characterization of colloidal silver platinum alloys, *J. Phys. Chem.*, **97**, 8304–8309.

Weissleder, R. (2001), A clearer vision for in vivo imaging, *Nat. Biotechnol.*, **19**, 316–317.

Yannouleas, C., R. A. Broglia, M. Brack, and P. F. Bortignon (1989), Fragmentation of the photoabsorption strength in neutral and charged metal microclusters, *Phys. Rev. Lett.*, **63**, 255–259.

Zsigmondy, R. A. (1926), Properties of colloids, *Nobel Lecture*.

25

Photoluminescence from Silicon Nanostructures

25.1 Introduction **25**-1
25.2 Synthesis of Silicon Nanostructures **25**-3
25.3 Luminescence Properties of Silicon Nanostructures **25**-7
Optical Characterizations and Luminescence Bands • CW Photoluminescence Experiments • Time-Resolved Photoluminescence Experiments
25.4 The Vibron Model: The Relationship between Surface Polar Vibrations and Nonradiative Processes **25**-15
The Silicon–Silicon Dioxide Interface • The Vibron Model • Experiments Supporting the Vibron Model
25.5 Concluding Remarks **25**-22
Acknowledgments **25**-22
References **25**-22

Amir Sa′ar
The Hebrew University of Jerusalem

25.1 Introduction

Silicon, the second-most abundant element on earth (after oxygen) having superior mechanical and electronic properties, has become the principal material of the semiconductors industry from the dawn of microelectronics, and apparently will remain dominant in the foreseen future. Silicon is a semiconductor whose electrical conductivity can be controlled over a wide range, either dynamically or permanently. Its oxidized state (SiO_2) is one of the best and most stable electrical insulator and its superior chemical and mechanical properties make silicon the ideal material for advanced materials processing. For all these reasons, silicon became essentially the sole player in electronic integrated circuits, being the basic building block of most electronic devices, from transistors and diodes to microprocessors, solar cells, wireless communication devices, and more.[1] Yet, silicon is not a good choice for photonic applications where optically active elements are required due to its indirect energy bandgap characteristics where energy's minima of the conduction and the valence bands do not fall at the same wavevector (i.e., the crystal Bloch momentum normalized to $\hbar$). The situation is schematically illustrated in Figure 25.1 where the energy-band diagram of silicon is shown and compared to that of GaAs, which is a direct bandgap semiconductor.

In a steady state, electrons (open circles) occupy the lowest energy states of the conduction band while holes (filled circles) occupy the upper states of the valence band. The emission of a photon takes place once the electron and the hole recombine radiatively, namely, conduction electrons drop down to empty states of holes in the valence band and, releasing their energy to photons of energy, $\hbar\omega = E_C - E_V \cong E_g$, where E_g is the bandgap energy of the semiconductor and $\hbar\omega$ is the photon energy. Besides energy, momentum should also be conserved during the process. However, as the photon wavelength ($\lambda = 2\pi/k \sim 1\,\mu\text{m}$ for silicon) is about three orders of magnitude larger than the de Broglie wavelength of the electrons (which is of the order of the lattice constant of the semiconductors ~5 Å), the photon momentum can be neglected relative to that of the electrons and the holes. In direct bandgap semiconductors like GaAs, both the electrons and the holes have the same momentum at the center of the Brillouin zone (Γ-point in Figure 25.1) and vertical radiative recombination can take place. In silicon, however, the large momentum mismatch between electrons and holes does not permit direct radiative recombination unless another entity, a phonon, for example, is involved in the recombination process. As a result, silicon is a poor emitter of light and cannot be utilized for applications where active light sources are required. In many papers and even textbooks this property of silicon is considered to be a disadvantage. However, one should remember that radiative recombination in direct bandgap semiconductors is a fast process (usually of the order of a few nanoseconds in direct bandgap semiconductors with $E_g \sim 1$–$2\,\text{eV}$) that limits the lifetime of the carriers (mainly that of the minority carriers in the semiconductor). In silicon, the slow radiative lifetime (of the order of few milliseconds in pure silicon[1]) allows the minority carriers to diffuse over macroscopically large distances (a few hundreds of micrometers and more), a highly favorable property for electronic applications.



FIGURE 25.1 Energy-band diagrams for silicon and GaAs where the dispersion curves are along the [100] direction (*X*-point) and the [111] direction (*L*-point). Conduction electrons (open circles) and valence holes (filled circles) occupy the band's minima with Δk (momentum/$\hbar$) being the wavevector's difference for silicon. Photon emission is not allowed for silicon.



FIGURE 25.2 **(See color insert following page 20-14.)** The PL spectrum from porous silicon with a maximum PL at a wavelength of about 675 nm. The photograph at the inset demonstrates the red color of the emitted PL from a circular layer of porous silicon (the sample has been illuminated with a UV lamp).

The situation is substantially different when dealing with silicon nanostructures. Generally speaking, semiconductor nanostructures[2,3] are artificially made semiconductor objects whose dimensions have been shrunk down to the nanometer length scales. They are classified according to their dimensionality, e.g., two-dimensional (2D) quantum wells, one-dimensional (1D) nanowires (or quantum wires), and zero-dimensional (0D) nanocrystals (or quantum dots[4]), where the classification is according to the number of unconfined dimensions along which carriers (electrons and holes) are still free to move. At the nanometric length scales, quantum confinement (QC) phenomena become important. For example, one should anticipate the momentum conservation law to relax with the decreasing size of the object. In case of silicon nanostructures, for example, a 0D silicon nanocrystal of radius R, we may use the Heisenberg uncertainty principle to estimate the wavevector relaxation: $\Delta k \sim 1/R$. As the relaxation of the wavevector conservation law increases with the decreasing size of the nanostructure, one may expect the radiative recombination rate to considerably increase once the wavevector mismatch, shown in Figure 25.1, becomes comparable to Δk, raising the question: Can we generate active photonic elements[5,6] from silicon nanostructures?

The above question has turned to be a practical subject in 1990 when Canham[7] reported on efficient red light emission from porous silicon (PS) under UV light illumination. PS is a nanometric random network of pores and silicon prepared by electrochemical etching of a silicon substrate.

Figure 25.2 shows a typical spectrum of the photoluminescence (PL) and a photograph of red light coming out from a PS layer. As the efficiency of the PL is comparable to that obtained from direct bandgap semiconductors, Canham in his pioneering work has suggested that quantum size effects might be responsible for efficient PL. Two complementary results seem to support this conclusion. The first is the presence of fairly small crystalline silicon nanostructures, in the form of nanocrystals and undulating nanowires, in the PS medium.[8] Secondly, the considerable blueshift of the maximum PL energy, and accordingly the energy bandgap, from about 1.12 eV (of bulk silicon crystals) to ~1.8 eV in PS, is another manifestation of QC in small semiconductor nanostructures.[2] Following Canham's discovery, a very extensive investigation has been conducted by many groups, aimed at verifying the QC model. Surprisingly, while many investigations provided additional support to the QC model,[9] a considerable number of works have reported results and properties of the PL that cannot be explained by the QC picture.[10] This puzzle has led numerous researchers to propose alternative models and theories that do not rely on QC, the more notable ones suggesting that surface phenomena are responsible for the PL.[11,12] In this picture, radiative transitions take place on the surface of the nanostructures either due to surface bonds, surface defects, imperfections, or even surface molecular species. In particular, the fact that certain properties of the PL depend on "surface chemistry," for example, the specific way that silicon surface bonds are terminated, have led certain researchers to suggest that surface phenomena are responsible for the luminescence from silicon nanostructures.[13]

Let us emphasize that surface phenomena are expected to play a major role in small nanostructures. To follow this, let us estimate the surface-to-volume (STV) ratio for few nanostructures of different dimensionality but having a simple geometrical form such as spheres (0D), cylinders (1D), and slabs (2D), as schematically shown in Figure 25.3.

In order to define a "volume" of the surface, we may estimate the surface's thickness of a given nanostructure, d, to be about 1–3 monolayers thick. For silicon (with a lattice constant of ~0.54 nm),


2D
1D
0D
d
R
d
R
d
R
$(\mathrm{STV})_{2D} = \frac{d \cdot S}{R \cdot S} = \frac{d}{R}$
$(\mathrm{STV})_{1D} = \frac{2\pi R \cdot d \cdot H}{\pi R^2 \cdot H} = 2\left(\frac{d}{R}\right)$
$(\mathrm{STV})_{0D} = \frac{4\pi R^2 \cdot d}{\frac{4}{3}\pi R^3} = 3\left(\frac{d}{R}\right)$

FIGURE 25.3 The surface-to-volume (STV) ratio for a 2D slab, 1D cylinder, and 0D sphere where R is the thickness of the slab, radius of the cylinder, and radius of the sphere, respectively. In all three cases, d represents the thickness of the surface.

we may take, $d \sim 1\,\mathrm{nm}$, to be an estimate of the surface's thickness. Hence, for a 0D spherical nanocrystal we find, STV = $3(d/R)$, where R is the radius of the sphere, so that for $R = 6\,\mathrm{nm}$ nanocrystal we get, STV ~ 0.5, meaning that 50% of the silicon atoms belong to the surface while for $R = 10\,\mathrm{nm}$, 33% of the silicon atoms sit on the surface of the nanocrystal. We conclude that surface phenomena become more and more appreciable with the decreasing size of the nanostructures and, on the nanoscales not only quantum size effects can affect the electronic properties of the nanostructures but also surface phenomena should carefully be considered as a possible source of interactions that may affect electronic properties of the nanostructures. This is particularly true for silicon, which is known to be material sensitive to surface termination and usually requires a special treatment for passivation.

Unfortunately, PS is not the ideal medium for the study of quantum size effects and surface phenomena at the nanoscale. PS is a random network of electrochemically etched pores and silicon that is characterized by a broad size and shapes distribution, it is chemically and mechanically unstable and it tends to change its properties with time (aging effects).[11] Hence, to a great extent, the puzzles and discrepancies between the QC and the surface chemistry (SC) models could not be resolved despite of the extensive investigation on PS. Yet, over the last decade, alternative techniques to fabricate silicon nanostructures, with better capabilities to control their size, shape, and the host matrix in which they are embedded, have emerged.[14] With these improved techniques, it is now possible to investigate the evolution of optical and electrical properties of silicon nanostructures versus size and dimensionality. Recent experimental results together with refined theories indicate that none of the above models alone, for example, the QC and the SC models, can explain the entire optical properties of silicon nanostructures.[15–17] Instead, a refined comprehensive model, which takes into account both quantum size effects and surface phenomena has to be developed.[18,19] The purpose of this chapter is to describe these recent developments in the field of silicon nanostructures, particularly those experiments and models that provide a support and verification to the mutual role played by QC and SC in shaping the optical properties of silicon nanostructures.[19] The interested readers are referred to earlier reviews and the rich literature in the field discussing each individual model (QC and SC) and the supporting/contradicting experimental results.[5–12]

25.2 Synthesis of Silicon Nanostructures

In this section, we briefly review some of the most popular techniques to synthesize light-emitting silicon nanostructures. The simplest and the less expensive method is based on PS, which is fabricated by electrochemical etching of crystalline silicon substrates using hydrofluoric acid (HF)–based solutions. The specific conditions to obtain light-emitting PS (like the PS sample shown in Figure 25.2)[20,21] are reviewed in detail in Refs. [22,23]. Light-emitting PS has a random, nanometric sponge-like structure with a fairly large surface area that can easily be accessed and chemically modified due to its porous characteristics. While this property of PS is of great advantage for certain applications such as chemical[24,25] and biochemical sensing,[26,27] it represents a major limitation for a consistent study of quantum size effects as the size, shape, and even the dimensionality of the nanocrystalline silicon objects are not well defined and can vary between samples and preparation techniques. Furthermore, as the PS matrix may contain various species such as SiO_x, amorphous silicon (a:Si), and other amorphous derivatives of silicon, the exact surface termination of the nanocrystalline silicon objects cannot be determined accurately. Aging effects can be quite significant in PS and may affect both optical properties and transport phenomena. For all these reasons and despite the extensive literature on luminescence from PS, the author of this chapter is in the opinion that in practice, it is impossible to draw consistent conclusions about nanoscale phenomena from PS alone.

The first experimental report on room-temperature PL from silicon nanostructures other than PS is related to silicon nanocrystals (SiNCs) fabricated by ion implantation of silicon into SiO_2 matrix.[28] Recently after, other methods to produce SiNCs embedded in SiO_2 matrices emerged,[14] including chemical vapor deposition (CVD)[29] of sub-stoichiometric oxide (SiO_x), RF magnetron sputtering,[30] reactive evaporation,[31] and plasma-enhanced CVD (PECVD).[32–34] In principle, all these methods require high-temperature annealing of the deposited films to produce phase separation of the excess silicon from the SiO_2 matrix followed by crystallization of the silicon into nanocrystalline particles. The ion implantation method[35–37] is quite popular due to its compatibility with the standard silicon CMOS technology (where it is routinely used to create doped silicon regions). In this technique, silicon ions are extracted from the plasma, accelerated toward the SiO_2 substrate by an electric field and losing their energy after traveling a given depth in the substrate. The thickness and the profile of the implanted layer depend mainly on the implantation dose and the ion energy. In principle, the lower the ion energy the narrower the implanted zone, however, implantation dose also decreases at lower ion energies, setting up a practical limit on the ion energy, which is typically in the range of 1–10 keV.

A similar result of forming oxide layers with excess silicon concentration has been obtained by RF magnetron sputtering. The sputtering process (sometime referred as physical vapor deposition ≡ PVD) involves a bombardment of silicon and SiO_2 solid targets by energetic ions (usually argon ions), removing atoms and molecules from the targets that are deposited on the substrate. As silicon dioxide is an electric insulator, an RF electric field is used to create the plasma between the substrate and the targets. A popular method to produce SiNCs is the co-sputtering technique[15,38] in which, the two targets (usually pure silicon and quartz) are simultaneously exposed to the ions, producing a mixed layer of silicon and oxide with the excess silicon being used to create SiNCs after high-temperature annealing. The thickness and the amount of excess silicon concentration are determined by the RF power as well as by the geometry of the sputtering chamber. Usually, in order to improve uniformity, the substrate is rotated and placed far enough from the targets. In certain cases however, particularly when size-dependent phenomena are to be investigated, it is desirable to put the substrate near the targets without rotation. In this case, the excess silicon concentration along the deposited film continuously varies from one edge of the substrate to the other edge,[15] as schematically illustrated in Figure 25.4.

The amount of excess silicon concentration can be determined by measuring the volume ratio of silicon and SiO_2 obtained from reference depositions of the single components (Si and SiO_2) under the same deposition conditions and is measured in unit of % excess silicon content in a given volume (x). In the experiments reported in Refs. [15,16], x varied from about 10% (at the edge



FIGURE 25.4 Schematic view of the co-sputtering method with the two targets of silicon and SiO_2 simultaneously exposed to energetic ions for producing a mixed layer of silicon and SiO_2. The amount of excess silicon decreases from the silicon target edge toward the SiO_2 target edge. Isolated silicon nanocrystals (and PL) have been observed in the range of $10\% \le x \le 35\%$. The two cross-section TEM images were taken from two different locations along the substrate with $x = 18\%$ and $x = 25\%$. A few nanocrystals are marked by white squares where the insets are the corresponding images obtained after spatial filtering.

closer to the SiO_2 target) up to about 80% (at the edge closer to the Si target). Luminescent SiNCs are obtained after high-temperature annealing from a limited range of $10\% \leq x \leq 35\%$ where isolated nanocrystals can be observed. At higher excess silicon content, a connected network of silicon clusters is formed, the PL diminishes, and both dark- and photoconductivities from the deposited layers appear, leading Balberg et al.[39] to propose that a formation of percolating connected network of silicon clusters gives rise to mutual exclusion of the PL and the transport.[40] Annealing of the as-deposited films at high temperatures of about 1150°C–1200°C in a controlled environment (Ar or N gas) leads to phase separation and crystallization of the silicon monomers. In Figure 25.4, we present a few examples of cross-section transmission electron microscope (TEM) micrographs obtained after thinning the samples by ion milling to allow passing of the electron beam through the specimen. The images shown in Figure 25.4 are related to two different values of excess silicon content, $x \approx 18\%$ and 25%. Nearly spherical SiNCs can clearly be seen in both images, revealing typical silicon lattice fringes of mainly the {111} silicon crystal planes (and sometime also the {220} crystal planes). The insets to each figure show the silicon crystallographic planes obtained after spatial filtering of the images in the frequency domain for selected SiNCs marked by solid white squares. The diameter of the nanocrystals is not constant but rather varies in the range of 2–10 nm. The histograms shown in Figure 25.5 were obtained after statistical processing of numerous TEM images, identifying SiNCs and measuring their diameters for each value of the excess silicon volume content. The profile of the histograms can be fitted to a Gaussian shape size distribution with a full width at half maximum (FWHM) of approximately 2 nm at the lower content ($x \approx 10\%$) and 3 nm at the higher silicon volume content ($x \approx 30\%$), reflecting the inhomogeneous characteristics of the samples, which are typical to almost all fabrication techniques. The average diameter of the nanocrystals increases with increasing silicon content and can be fitted to the following power law (solid line in Figure 25.5b):

$$d\,(\text{nm}) \cong 2(x - x_0)^{1/3} \tag{25.1}$$

where
  d is the average diameter of the SiNCs
  $x_0 = (8 \pm 2)\%$

The power exponent of 1/3 stems from the relationship between the diameter and the volume of the nanocrystals, reflecting the spherical characteristics of the SiNCs. Let us emphasize that SiNCs with a diameter smaller than 2 nm have not been observed so far, independent of the fabrication method that has been utilized, and Equation 25.1 is rather limited to the range of $10\% \leq x \leq 35\%$.



FIGURE 25.5 (a) Histograms showing the size distribution for selected samples having different excess silicon volume contents. The histograms have been obtained after statistical analysis of numerous TEM images, similar to those presented in Figure 25.4, identifying the nanocrystals and measuring their diameters. The solid lines represent the best fit to a Gaussian distribution function. (b) The variation of the average diameter of the nanocrystals versus the excess silicon volume content. The solid line represents the best fit to Equation 25.1.

Another elegant method to produce continuous size variation of SiNCs in a single deposition run is the laser pyrolysis of silane in a gas-flow reactor, which has been reported by Ledoux et al.[41] In this technique, a pulsed CO_2 laser produces a molecular beam of silicon nanoparticles having a size distribution of 3–7 nm with the larger nanoparticles moving slower than the smaller ones. Using a rotating mechanical chopper synchronized with the laser pulses, size-selected nanoparticles are transmitted and deposited at different locations across the substrate. The PL image shown in Figure 25.6 reveals a color variation of the PL



FIGURE 25.6 **(See color insert following page 20-14.)** (a) A photograph showing the PL variation along the substrate from silicon nanocrystals deposited by the laser pyrolysis technique. (b) The normalized PL spectra from different positions along the substrate. (Reprinted from Ledoux, G. et al., *Appl. Phys. Lett.*, 80, 4834, 2002. With permission.)

across the substrate that is correlated with the average size of the silicon nanoparticles.

A slightly narrower size distribution but a much better control of the position and the density of SiNCs has been achieved by synthesizing Si/SiO_2 superlattices. This method has been introduced by Lockwood et al.[42] who have used silicon molecular beam epitaxy (MBE) system combined with ex situ UV ozone oxidation for growing alternating nanolayers of amorphous silicon (a:Si) and SiO_2. Later, this approach has been adopted to create alternating layers of SiNCs and SiO_2 using PECVD,[43] low-pressure CVD (LPCVD)[44,45] and RF magnetron sputtering in the serial sputtering mode.[46] A key factor in all these methods is a good control of the layer's thicknesses down to the nanometric length scales and good uniformity, particularly of the interfaces between layers. A similar approach, based on depositing alternating SiO_x/SiO_2 layers with $1 \leq x < 2$, has also been introduced where phase separation during annealing gives rise to a formation of a:Si layers that later on crystallize to create SiNCs.[47] Results obtained by serial sputtering of silicon/SiO_2 superlattices are shown in Figure 25.7.[48]

In this method, individual layers are deposited one on top of the other at deposition rates of about 2–4 nm/min to achieve a good thickness control. Cross-section HRTEM images, shown in Figure 25.7, reveal the presence of 2D alternating layers of SiNCs separated by amorphous SiO_2 layers. The order and the high quality of the interfaces can be appreciated from the low-magnification TEM image at the inset to Figure 25.7(a) while the higher magnification HRTEM micrograph of Figure 25.7(b) reveals 2D layers of SiNCs with average diameter of about 4.3 nm and a statistical size distribution similar to those presented in Figure 25.5. Figure 25.7(a) presents a STEM (scanning TEM) micrograph obtained after introducing high angle annular dark field (HAADF) detector into the microscope for collecting



FIGURE 25.7 High-resolution, cross-section TEM micrographs of serially sputtered SiNCs embedded in SiO_2 matrices. (a) STEM image (high z-contrast) revealing nearly spherical SiNCs (bright spots) with average diameter of 3 nm, separated by 10 nm of SiO_2 layers. The inset shows a lower magnification image of the superlattice. (b) HRTEM image of selected layers of SiNCs (marked by circles) having average diameter of 4.3 nm.

electrons that undergo high angle inelastic scattering to yield high *z*-contrast (where *z* is the atomic number of the element). In this image, the average diameter of the SiNCs is about 3 nm.

25.3 Luminescence Properties of Silicon Nanostructures

25.3.1 Optical Characterizations and Luminescence Bands

In general, several luminescence bands can be excited from silicon nanostructures, but most of them are not directly related to the nanostructures but rather to defects and imperfections in the host matrix. A relatively strong but misleading band is the so-called "F"-band (Fast-band) which has been observed for oxidized PS and for most silicon nanostructures embedded in SiO_2 matrices.[11,49,50] The emission spectrum of this band extends over the blue-green (400–550 nm) range of the visible spectrum and is characterized by a fast PL decay time of several nanoseconds. This band has been observed from fully oxidized PS and from silicon nanostructures, such as silicon nanowires,[51,52] with fairly large diameters and therefore, cannot be associated with the nanostructures themselves but with luminescence oxide and interface defects. Other luminescence bands that have been reported but do not relate to quantum size effects are UV bands (~350 nm) and near-IR bands of bulk silicon, unsaturated silicon bonds, and rare-earth heavy ions in the silicon matrix.[11,12]

The size-dependent luminescence band, which shows a clear correlation with quantum size effects in silicon nanostructures, is called the "S"-band (Slow-band) and has been the subject of extensive investigation over the past two decades.[5–13] The emission spectrum from this band can be tuned over the green–red–near IR spectral ranges (500–900 nm) and is characterized by significantly slower PL decay times (compared to the F-band) in the range of few microseconds. In a typical PL experiment, carriers (electrons and holes) are optically excited via absorption of photons of energies exceeding the energy bandgap of the nanostructures, followed by nonradiative relaxation of the photocarriers into the lowest energy levels of the nanostructures and finally, radiative recombination of the carriers that generates PL photons (see Figure 25.8).

Several complementary methods including direct optical absorption,[53] ellipsometry,[54–56] and PLE[11,57] (PL excitation) have been utilized for revealing the absorption spectra from silicon nanostructures. In general, the absorption is substantially blueshifted relative to the PL spectrum with a weak tail below 3 eV and increasing absorption above 3 eV that resembles some of the crystalline and the amorphous silicon characteristics. Therefore, it is not simple to correlate absorption data with the nanostructures themselves as contributions from silicon species, defects, and other absorbing centers in the host matrix cannot be distinguished. The photoexcited carriers undergo a fast relaxation, on timescales of several picoseconds, releasing their energy via nonradiative processes (such as phonons emission) and are trapped in the lower energy levels of the nanostructures. Hence, the luminescence spectrum, particularly the luminescence from the S-band, can directly be correlated with the silicon nanostructures to provide a direct tool for studying the size effects in these nanostructures. Two kinds of PL experiments can be performed. In continuous wave (cw) PL experiments, the system approaches a steady state where all relaxation and transient phenomena have already disappeared and a steady state PL spectrum is measured. Time-resolved PL experiments allow studying dynamical aspects of the nanocrystals where, the investigated dynamics depends on the temporal resolution of the measurement system, particularly the time resolution of the optical detection system that follows the decay of the PL signal shortly after the excitation pulse is switched off. In silicon nanostructures, the dynamics associated with interband (e.g., conduction to valence) radiative and nonradiative relaxation processes is on timescales of few microseconds and therefore, the excitation source can be either a pulsed laser or a beam of a cw laser modulated by an external light modulator (such as acousto-optical modulator).



FIGURE 25.8 Schematic of the optical excitation process (solid line) generating electron (dotted circle)–hole (solid circle) pairs, followed by nonradiative relaxation into the lowest energy levels of the nanocrystal (dashed-dotted lines) and finally, radiative recombination of the electron–hole pair (exciton) to generate a photon (gray arrow). The scaling laws for the exciton energy and the bandgap energy (according to the QC model) are shown at the bottom of the figure.

25.3.2 CW Photoluminescence Experiments

One of the most convincing evidences for quantum size effects in silicon nanostructures comes from cw PL experiments on series of SiNCs having different diameters. The room temperature, normalized PL spectra shown in Figure 25.6 (SiNCs fabricated by laser pyrolysis of silane[41]) and Figure 25.9 (SiNCs fabricated by co-sputtering[15]) demonstrate this phenomenon where all PL spectra are blueshifted to higher energies for smaller nanocrystals. This behavior of the PL, e.g., a blueshift of the PL peak energy with the decreasing size of the nanocrystals, has also been observed for PS[9–11] and for SiNCs fabricated by other methods.[14] The relatively large bandwidth of all PL spectra (FWHM ≈ 200 meV) has been



FIGURE 25.9 The normalized PL spectra for co-sputtered SiNCs of different excess silicon volume content.

assigned to the inhomogeneous characteristics of the samples, for example, the broad size distributions shown in Figure 25.5 for co-sputtered SiNCs.

Figure 25.10 (top) presents the variation of the PL peak energy with the increasing excess silicon volume content, x, in the range of $10\% \leq x \leq 35\%$ (bottom axis of Figure 25.10) and accordingly, with the decreasing average diameter of the co-sputtered SiNCs (upper axis of Figure 25.10). The solid line in this figure represents the best fit of the experimental results to an inverse power law as follows:

$$E - E_G = \frac{b}{(x - x_0)^{\delta/3}} \tag{25.2}$$

where

- $\delta/3 \cong 0.45 \pm 0.1$ is the power exponent
- $E_G = 1.12\,\text{eV}$ is the energy bandgap of bulk silicon
- $x_0 \cong (9 \pm 2)\%$ (very close to the experimental value of x_0 obtained for the variation of the average diameter with x; see Equation 25.1)

Using Equations 25.1 and 25.2, we find a relationship between the PL energy shift (relative to bulk silicon) and the diameter of the SiNCs:

$$\Delta E = E - E_G = \frac{A}{d^\delta} \tag{25.3}$$

where

- $\delta \cong 1.35 \pm 0.3$
- ΔE is called the “confinement energy” of the nanocrystals



FIGURE 25.10 The variation of (a) the PL peak energy and (b) the integrated PL versus the excess silicon volume content (bottom axis) and the average diameter of the nanocrystals (top axis). The inset shows the non-normalized PL spectra at room temperature.

A very similar inverse power law with essentially the same power exponent has been found for SiNCs fabricated by laser pyrolysis of silane,[41] by PECVD,[34] and by other techniques. However, this power exponent deviates from the exponent predicted from a simple QC model, e.g., a particle confined into a spherical quantum dot having infinite potential barrier. In the latter case, the quantized energy levels of the dot are given by[2] $E_{n,l} = 2\hbar^2 z_{n,l}^2/(m^* d^2) \sim 1/d^2$, where $z_{n,l}$ are the lth root of the nth order spherical Bessel function and m^* is the effective mass of the carriers in the bulk medium. Therefore, in such a simple effective mass model, one would expect the confinement energy to vary as $\Delta E \sim 1/d^2$. Several factors may account for the deviation of δ from this simple model. A major factor, which has been ignored so far, is the Coulomb interaction between electrons and holes to create excitons. Excitons are bound states of electron–hole pairs that are created by the Coulomb attraction between the charged carriers. In a bulk silicon crystal, the Bohr radius of the exciton is given by $a_{ex} = \hbar^2 \varepsilon_{Si}/\mu e^2 \approx 5-7\,\text{nm}$, where ε_{Si} is the dielectric constant of silicon and μ is the reduced mass of the electron–hole pairs. QC modifies this picture, particularly when the size of the nanocrystals becomes comparable to the

Bohr radius of the exciton. In this case ($d/2 \leq a_{ex}$), which is called the strong confinement regime, the electrostatic Coulomb energy is scaled as $E_{ex} \approx e^2/(\varepsilon_{Si}d/2) \sim 1/d$ as opposed to $\sim 1/d^2$ of the effective mass model; see Figure 25.8. Thus, we can expect the power exponent to vary in the range of $1 \leq \delta \leq 2$ with $\delta \approx 2$ being the weak confinement limit for big nanocrystals. Indeed, recent first-principle calculations (meaning that the many-body problem of having a finite number of silicon atoms in a dot, including the specific form of surface termination bonds, has numerically been solved) such as the LCAO (linear combination of atomic orbitals)[58] and the pseudo-potential[59] methods, have found a power exponent of $\delta \cong 1.4$, in a very good agreement with the experimental results, thus providing a solid support to the QC model.

Yet, cw PL experiments provide additional information about SiNCs that cannot be easily interpreted by the QC model. Figure 25.10b shows the variation of the integrated PL intensity, which is obtained by integrating the area below the non-normalized PL spectra[15] (inset to Figure 25.10a) versus the silicon volume content (and the average diameter of the nanocrystals). In order to obtain the actual PL yield, one should take into account the varying density of SiNCs as lower x means lower density of SiNCs. The corrected PL yield, obtained after dividing the integrated PL by x, is shown in Figure 25.11. In this presentation, the precise number of photons absorbed per each unit area could only be estimated. While this quantity has not been measured directly, in several other experiments[41,60–63] aimed at measuring the absolute value of the PL yield, it has been found that the PL yield for SiNCs having a diameter of 4–5 nm is fairly high in the range of 60%–80%. Similar values have also been found for PS.[64] The maximum yield of 30%–50% shown in Figure 25.11 (for nanocrystals emitting their light in the 650–750 nm, red-orange spectral range) should be considered as a lower limit. However, the general trend of the PL yield, e.g., sharp increase with the decreasing diameter up to a maximum for 4–5 nm in diameter nanocrystals and a decrease of the yield for smaller nanocrystals, has been confirmed by numerous groups.[41,63] This finding cannot simply be explained by the QC model. According to this model, the smaller the nanocrystals the more pronounced is the relaxation of the momentum conservation rule (as confirmed experimentally[65]) and accordingly, a larger PL yield should be measured.[66] Further implications of the high PL yield and its relation to the rates of radiative and nonradiative processes in SiNCs is discussed in Section 25.3.3.



FIGURE 25.11 The PL yield versus the silicon volume content (bottom axis) and the average diameter of the nanocrystals (top axis). The inset illustrates schematically the two relaxation channels of radiative recombination (followed by photon emission) and nonradiative relaxation of the exciton.

Among the first experiments indicating the mutual role of QC and SC is the one reported by Wolkin et al.[17] In this experiment, a series of PS samples having different porosities have been kept under controlled environment to avoid oxidation and to ensure that the surface of the silicon nanostructures is passivated by Si–H chemical bonds. The state of passivation has been monitored by FTIR infrared spectroscopy to exclude the presence of Si–O and Si–OH bonds. A second group of similar PS samples were exposed to air for 24 h, allowing surface oxidation and the presence of Si–O bonds. Results of room-temperature PL measurements from both series of samples are presented in Figure 25.12. Despite that the actual average size of the silicon nanostructures cannot accurately be measured for PS, it is well known that smaller silicon features appear for larger porosities of the samples.[67] The PL spectra, shown in Figure 25.12a, show indeed a consistent blueshift with the increasing porosity for hydrogen-terminated PS samples. On the other hand, oxygen-terminated samples (Figure 25.12b) show, at first, a blueshift of the PL spectra up to the yellow (~600 nm) and then, no blueshift and even a redshift for the blue-green emitting PS samples. Clearly, this phenomenon cannot be explained by the QC model alone and the role of SC, particularly the passivation of the PS surface must be taken into account. The model proposed by Wolkin et al.[17] assumes that some of the dangling bonds, on the silicon oxide interface, are passivated by the Si=O double bond, which is known to be more stable than other forms of surface passivation.[68] Based on this assumption, the authors simulated the electronic band structure of SiNCs having Si=O double bonds at the silicon oxide interface. The results, shown in Figure 25.13, suggest that the QC model is valid for hydrogen-terminated SiNCs as radiative recombinations are via free excitons (e.g., excitons of the bulk nanocrystalline silicon core) for all sizes of the nanocrystals. However, for Si=O passivated SiNCs, both electrons and holes can be localized (or trapped) by the Si=O bonds where, in zone I of Figure 25.13 none of the carriers are trapped, in zone II only electrons are trapped, and in zone III both electrons and holes are trapped to form surface-trapped excitons. This model provides a nice and elegant explanation to the experimental results shown in Figure 25.12, particularly for kinetic properties associated with the joint contribution of SC and QC to the shift of the energy bandgap. Yet, as pointed out by these authors, the intensity of the PL (which is proportional to the integrated PL) increases by few orders of magnitude up to the orange emitting samples and then, diminishes for higher porosity samples emitting in the blue-green; quite similar to the PL yield presented in Figure 25.11 for co-sputtered



FIGURE 25.12 Room-temperature PL spectra from PS with different porosities (a) kept in Ar atmosphere, (b) after exposure to air. (Reprinted from Wolkin, M.V. et al., *Phys. Rev. Lett.*, 82, 197, 1999. With permission.)



FIGURE 25.13 Electronic states of SiNCs as a function of the cluster size and surface passivation. (Reprinted from Wolkin, M.V. et al., *Phys. Rev. Lett.*, 82, 197, 1999. With permission.)

SiNCs. Hence, dynamical characteristics of the nanocrystals still require sufficient explanations, particularly as the PL decay time from the blue-green PS samples have been reported[17] to be much faster (0.07 μs in the blue) than those of the red samples (~2 μs) and therefore, according to the QC model, should exhibit higher PL yield. Further discussion of this topic will be given in Section 25.4.2 after presenting the vibron model.

25.3.3 Time-Resolved Photoluminescence Experiments

The PL decay process from silicon nanostructures has been intensively investigated over the recent years, both from PS[11] and from SiNCs embedded in SiO_2 matrices.[69] In a typical setup, a train of short laser pulses excites the carriers to their lowest excitonic state from which they radiatively recombine to generate PL photons. The PL decay time is measured shortly after the pump laser is switched off using, for example, a gated photon-counting system that is mostly suitable for SiNCs since the relevant dynamics occurs on timescales of sub-microseconds up to few milliseconds.

A typical room-temperature, time-resolved PL decay curve from co-sputtered SiNCs with x = 18% (average diameter of ~4.5 nm) and at a PL energy of 1.65 eV (PL wavelength of ~750 nm), is shown in Figure 25.14. The temporal behavior of the



FIGURE 25.14 Room temperature, time-resolved PL decay normalized to the initial PL intensity taken at PL photon energy of 1.65 eV for the x ~ 18% sample (average diameter of 4.5 nm). The solid line represents the best fit of the experimental data (symbols) to the stretched-exponential decay function (Equation 25.4). The inset shows the PL decay curves at various low temperatures.

PL does not follow a simple exponential decay function [e.g., $I/I_0 = \exp(-t/\tau)$; notice the semilogarithmic scale of Figure 25.14], but rather a stretched-exponential decay function of the form:

$$I(t) = I_0 \exp\left[-\left(\frac{t}{\tau}\right)^{\beta}\right] \qquad (25.4)$$

where

τ is the characteristic PL lifetime

$0 < \beta \leq 1$ is the dispersion exponent of the PL decay function

This form of the PL decay function has been observed for many classes of silicon nanostructures[37,70] and is frequently assigned to disorder characteristics of systems where dispersive transport take place, particularly migration[71,72] and trapping–detrapping (or release) of photoexcited carriers.[73] This topic is directly related to transport phenomena in PS and SiNCs where dispersive transport has been observed and discussed,[21,74] but will not be reviewed here. The solid line in Figure 25.14 represents the best fit of the experimental data to Equation 25.4, yielding a PL lifetime of about ~40 μs and $\beta \sim 0.85$. As opposed to the dispersion exponent that is approximately independent on the PL energy, the PL decay time decreases with the increasing PL energy, from about 100 μs at 1.4 eV to few μs at 2 eV. This is rather important result as it indicates, again, about the inhomogeneous nature of the PL spectrum, in accordance with the inhomogeneous size distributions of the nanocrystals shown in Figure 25.5. According to the QC model, the smaller the SiNCs (and therefore, the breakdown of the *k*-conservation rule), the larger the radiative transitions rate and the faster the radiative lifetime. We will follow this picture, assuming that each wavelength in the PL spectrum probes a different size of the nanocrystals, as suggested by the QC model. In addition, let us denote the substantial dependence of the PL decay time (at a given PL energy) on temperature, shown at the inset to Figure 25.14. The lower is the sample temperature the longer is the PL decay time, approaching fairly slow PL lifetimes of about few milliseconds at low temperatures (below 50 K). The variation of the PL lifetime with temperature, for several PL energies, is presented in the Arrhenius plot (semilogarithmic scale versus the inverse temperature) of Figure 25.15.



FIGURE 25.15 Arrhenius plot (semilog scale versus the inverse temperature) of the PL lifetime, from the $x \sim 18\%$ sample, for several photon energies. The solid lines represent the best fit of the experimental data to the exchange-splitting model shown schematically at the inset with τ_U, τ_L, and Δ being the upper state (singlet) lifetime, the lower state (triplet) lifetime, and the splitting energy, respectively.

We can identify two distinct temperature regimes in Figure 25.15: a low-temperature regime (below 50–60 K) where the PL lifetime is essentially independent of temperature and a high-temperature regime (above 60 K) where the PL lifetime gets shorter with the increasing temperature. To follow these characteristics of the PL lifetime let us briefly describe the exchange-splitting model that has originally been proposed by Calcott et al.[75] for PS, and later on adopted for other classes of silicon nanostructures.[69] In typical semiconductors the lowest excitonic state is composed of conduction electrons having a total angular momentum of $J = 1/2$ (the sum of $L = 0$ orbital angular momentum of the conduction band and spin 1/2 of the electrons) and heavy holes states having $J = 3/2$ ($L = 1$ of the valence band and spin 1/2). Hence, the total angular momentum of the exciton can be either 1 or 2. Of course, QC makes this picture much more complicated as different bands can be mixed and the spherical symmetry of the ideal dot can be distorted (in fact, the spherical symmetry of the dot is always slightly distorted when constructed from a cubic crystal). Therefore, Calcott et al.[75] treated the exciton as composed of two spin 1/2 particles assuming that only the spin components of the total angular momentum are conserved. In this case, the total spin of the exciton can be either $S = 1$ (triplet) or $S = 0$ (singlet). The Coulomb exchange interaction between electrons and holes lifts the singlet–triplet degeneracy. To follow the role of the exchange interaction, let us point out that, according to the Pauli principle, a singlet state (which is antisymmetric with respect to exchange of the electron–hole spins) has to be symmetric with respect to exchange of the electron–hole orbital states, while the spin-triplet state has to be orbitally antisymmetric with respect to this exchange. Hence, the Coulomb energy associated with the exchange interaction is always larger for the spin-singlet state ($S = 0$) relative to the spin-triplet state ($S = 1$). The situation is schematically illustrated at the inset to Figure 25.15 where Δ is the singlet–triplet exchange splitting energy. In a bulk silicon crystal, the splitting energy is fairly small, of the order of ~150 μeV; however, since the exchange interaction is proportional to the overlap between the electron and the hole states, it can significantly be enhanced by confining the exciton into small nanostructures. This picture explains very well the behavior of the PL lifetime. Denoting the lifetimes of the upper singlet and the lower triplet states by τ_U and τ_L, respectively, and taking the population of the two states to be in thermal equilibrium (which is a reasonable assumption as relaxation processes between these neighboring states should very fast, of the order of few picoseconds), we find the following expression for the PL radiative lifetime:

$$\frac{1}{\tau_R} = \frac{g/\tau_L + (1/\tau_U)e^{-\Delta/kT}}{g + e^{-\Delta/kT}} \tag{25.5}$$

where

$1/\tau_L$ is the rate of radiative transitions from the lower triplet state

$1/\tau_U$ is the rate of radiative transitions from the upper singlet state

$g = g_L/g_U = 3$ is the level's degeneracy ratio* and the Bolzmann factor, $\exp(-\Delta/kT)$, takes into account the relative (thermal) population of the states

The solid lines in Figure 25.15 represent the best fit of the PL lifetimes to Equation 25.5. The appearance of two temperature regimes can be understood now as follows. At low temperatures (where $kT < \Delta$), only the lower triplet state of the exciton is populated and the PL decay time is dominated by the long lifetime of the triplet state. At higher temperatures, the upper singlet state becomes populated. If the radiative lifetime of this state is much faster than that of the lower triplet state, it will dominate the PL decay time at high temperatures, giving rise to exponentially faster lifetimes (versus the inverse temperature), which is in a very good agreement with the results shown in Figure 25.15. The upper state lifetime is expected to be (relatively) short since the spin singlet is an optically active state (e.g., radiative recombination of the exciton into the ground state of no exciton is allowed) as opposed to the lower triplet state, which is optically forbidden state according to the spin selection rules. The spin–orbit interaction[11] can mix the singlet–triplet states, making the triplet state weakly allowed. However, this interaction is fairly weak in silicon so that the lifetime of the triplet state is expected to be quite long.

Before discussing the application of this analysis to the various SiNCs samples (of variable silicon volume content), let us denote the contribution of nonradiative relaxation processes to the measured PL decay time. In principle, the measured (inverse) PL decay time is the sum of radiative and nonradiative relaxation rates, $\tau^{-1} = \tau_R^{-1} + \tau_{NR}^{-1}$, where τ_{NR} is the nonradiative relaxation time. Yet, as will be further explained hereafter, at high temperatures the measured PL decay time is dominated by radiative processes and we may take, $\tau_U \cong \tau_S$ (where τ_S is the singlet lifetime). At low temperatures, the contribution of nonradiative processes cannot be neglected; thus we have $\tau_L^{-1} = \tau_T^{-1} + \tau_{NR}^{-1}$, with τ_T being the triplet (radiative) lifetime.

The above analysis, which yields the upper level lifetime, the lower level lifetime, and the exchange-splitting energy for each of the PL energies, has been exploited to the entire set of SiNC samples having different average diameters.[15,16] The results are presented in Figure 25.16 for selected samples. Let us emphasize again that each of these samples is characterized by inhomogeneous, approximately Gaussian, size distribution of the nanocrystals (see Figure 25.5). The PL energy probes a given size (or diameter) of the nanocrystals within this distribution. This is schematically illustrated at the bottom of Figure 25.16, where a smaller PL energy is linked to a larger nanocrystal with a scale of diameters (based on Equation 25.3—the relationship between the PL energy and the diameter of the nanocrystals). For a given size distribution, the PL intensity varies across the PL spectrum yielding more photons near the average size of the



FIGURE 25.16 The variation of (a) the upper level lifetime, (b) the triplet–singlet exchange-splitting energy and (c) the lower level lifetime, as a function of the PL energy for various samples having different average diameters. The lower diameter scale correlates the PL energy to the diameter of the nanocrystals according to Equation 25.3. The solid lines in (a and b) represent a universal dependence of the upper level lifetime and the splitting energy on the diameter of the nanocrystals, while the dashed lines in (c) show the dependence of the lower level lifetime on the average size of the samples.

---

* The degeneracy ratio depends on the assumption regarding the total angular momentum of the states. However, the lifetime analysis is almost insensitive to the specific value of this ratio.

SiNCs. Nevertheless, according to the QC model the PL lifetime should be independent of the size distribution but rather characteristic of a given nanocrystal's diameter. In other words, according to the QC model, the PL lifetime should vary with the PL energy but should be *independent of the size distribution of the nanocrystals*. The results shown in Figure 25.16a for the upper state (singlet) lifetime and in Figure 25.16b for the exchange-splitting energy, remarkably follow the QC model. The upper state lifetime, τ_U, decreases by an order of magnitude (from about 40–50 μs down to 2–3 μs) with increasing PL energy, in agreement with the QC model where larger relaxation of the *k*-conservation rule is expected for smaller nanocrystals. Furthermore, all the results for τ_U from different samples having different average diameters, collapse into a single line (the blue line in Figure 25.16a) independent of the size distributions of the samples. The PL energy probes a lifetime of nanocrystals having the same diameter, which should be independent of how many nanocrystals of that size appear at a given distribution. A similar conclusion holds for the exchange-splitting energy. The smaller the nanocrystal, the larger the exciton confinement and the bigger the splitting energy. Here again, as the splitting energy is a size-dependent property of the nanocrystals, this energy should be independent of the size distribution and the results for all samples should collapse into a single line.

So far, we have found the upper state (singlet) lifetime and the exchange-splitting energy to provide a solid support to the QC model. However, a completely different behavior appears for the lower state (triplet) lifetime, τ_L. The lower state lifetime is essentially independent of the PL energy and therefore, is not a size-dependent property of the nanocrystals. In contrast, τ_L depends on the excess silicon volume content (x), and accordingly, on the average diameter of the SiNCs. Thus, the lower state lifetime cannot be assigned to radiative relaxation from the triplet state but rather to nonradiative relaxation processes that depend on the environment of the SiNCs, e.g., the amount of excess silicon in the host matrix and, as will be explained later, on the SC (or passivation) of the SiNCs. These findings suggest that *QC is responsible for the relatively fast radiative transitions rates from SiNCs, while SC is responsible for the fairly slow nonradiative relaxation processes in these nanocrystals*. Yet, both processes are responsible for the PL yield, η (see Section 25.3.2), which is derived from the competition between radiative and nonradiative recombination rates, as schematically illustrated at the inset to Figure 25.11, and is given by the following expression:

$$\eta = \frac{\tau_R^{-1}}{\tau_R^{-1} + \tau_{NR}^{-1}} = \frac{\tau_{NR}}{\tau_R + \tau_{NR}} = \frac{\tau}{\tau_R} \tag{25.6}$$

where $\tau^{-1} = \tau_R^{-1} + \tau_{NR}^{-1}$ is the total (measured) PL decay time. For high-yield samples (average diameter in the range of 4.5–5.5 nm), the PL decay time varies by more than two orders of magnitude over the 50–300 K temperature range (see Figure 25.15), while the integrated PL is approximately constant over the same temperature range (it varies by less than a factor of 2; see Figure 25.17).



FIGURE 25.17 The variation of the integrated PL as a function of temperature for various samples having different average diameters.

Both experiments (Figures 25.16 and 25.17) suggest that over the 50–300 K temperature range, the PL decay time is dominated by *radiative transitions* of the exciton where, $\tau_R \ll \tau_{NR}$. In this range, we find $\eta \cong$ constant ~1, in a good agreement with the high yield measured for these SiNCs. At this temperature range, radiative transitions are dominated by the upper-state lifetimes, $\tau \cong \tau_U \sim 2$–$50\,\mu$s, which should be compared to the nonradiative lifetimes, $\tau_{NR} \sim 1$–3 ms. Notice that nonradiative rates have been measured at low temperatures and, in general, one should expect faster nonradiative lifetimes at higher temperatures. Nevertheless, all experimental results indicate that $\tau_R \ll \tau_{NR}$ over the entire temperature range, up to room temperature.

Based on the assignment of radiative lifetime to the upper (singlet) state, we can estimate now the oscillator strength for optical transitions from this state. The oscillator strength, $f_{i\to j}$, is a dimensionless parameter that measures the strength of a dipole-allowed optical transition from a given *i*th state to another *j*th state, relative to all other dipole-allowed transitions from the same (*i*th) state. The oscillator strength is normalized so that the sum over all oscillator strengths originated from the same level, is equal to 1, a property which is known as the *f*-sum rule[76] (or the Thomas–Reiche–Kuhn sum rule). The relationship between the oscillator strength and the (spontaneous) radiative lifetime of the singlet state is given by[18]

$$f_{OS} = \frac{2\pi m c^3 \hbar^2 \varepsilon_0}{E^2 e^2 n} \frac{1}{\tau_U} \tag{25.7}$$

where

m is the electron mass
n is the refractive index of the medium
E is the photon energy

In Figure 25.18, we have plotted the oscillator strength for optical transitions, from the upper singlet state, versus the confinement energy, Δ*E*. Here again, all results from samples having



FIGURE 25.18 Semilogarithmic plot of the upper level oscillator strength versus the confinement energy, for various samples having different average diameters. The red line represents the best fit to Equation 25.8.

different average diameters collapse into a single function that, taking into account the limited range of variation, can be fitted into exponential form:*

$$f_{OS} = f_0 \exp\left(\frac{\Delta E}{E_{OS}}\right) \qquad (25.8)$$

where

$E_{OS} \cong 0.4 \pm 0.1\,\text{eV}$ is the characteristic oscillator strength energy

$f_0 \cong (3.5 \pm 1) \times 10^{-5}$ is the oscillator strength of the bulk crystal (no confinement)

The above analysis of the PL characteristics seems to adequately explain most of the experimental findings but, at the same time, open up other fundamental questions concerning the origin of the PL. Let us briefly summarize these findings and the most relevant questions[19]:

1. *Radiative Processes*: QC plays a major role here. For small silicon nanostructures, QC gives rise to a blueshift of the bandgap energy, up to the visible range of the spectrum, according to the power law of Equation 25.3. At the same time, the increasing bandgap energy gives rise to shorter radiative lifetimes since $\tau_U \sim 1/E^2$ (without taking into account the effect of confinement on the oscillator strength, which will be discussed hereafter). A second contribution of QC to radiative processes comes from the breakdown of the *k*- (or momentum) conservation rule. However, the effect of confinement on the rate of radiative transitions has been overestimated by many researchers over the years. Our estimate of the oscillator strength for the case of no confinement is, $f_0 \sim 10^{-5}$, in a fairly good agreement with the poor optical emission and the fairly slow radiative lifetimes (≥10 ms) from bulk silicon. QC enhances the oscillator strength for small nanocrystals, but only to the order of ~(2–3) × 10^{-4} and, apparently up to 10^{-3} for blue-emitting nanocrystals. For a comparison, in direct bandgap semiconductors the oscillator strength for interband transitions is ~1, about 3–4 orders of magnitude larger than the oscillator strength of our silicon nanostructures. A direct consequence of this result is the fairly slow radiative lifetimes in silicon nanostructures relative to direct bandgap semiconductors. For example, the radiative lifetime in GaAs (with energy bandgap of ~1.42 eV) is about few nanoseconds compared to few microseconds in silicon nanostructures; a result which is a direct manifestation of the 3–4 orders of magnitude differences in the oscillator strength. Some researchers might assign this conclusion to the so-called quasi-direct bandgap of silicon nanostructures, meaning that the oscillator strength for dipole allowed optical transitions is substantially smaller compared to direct bandgap semiconductors. However, the author of this chapter prefers not to talk about "bands" in small silicon nanostructures as we actually deal with a discrete set of levels rather than "bands."
2. *Nonradiative Processes*: As opposed to radiative processes, QC does not play a major role here. The efficient light emission from SiNCs is due to exceptionally slow nonradiative relaxation processes in SiNCs, of the order of few milliseconds. While this result explains very well the high quantum yield from SiNCs, it raises another fundamental question. The measured nonradiative lifetimes of few milliseconds are typical for the purest silicon wafers, with impurity levels of about 10^{13}–10^{14} cm^{-3} (e.g., one impurity atom per more than a billion of silicon atoms).[1] It is well known that higher density of impurities enhances nonradiative relaxation rates, for example, in p-type silicon crystals with boron concentration of about 10^{16} cm^{-3} the minority carriers' lifetime is about 0.1–1 μs; adding 10^{17} cm^{-3} Au impurities into the crystal gives rise to nonradiative lifetimes as short as 10^{-10} s. The high PL yield and the slow nonradiative relaxation times in SiNCs seem to be a universal property of SiNCs, essentially independent of the method of fabrication (see Section 25.2). Yet, these fabrication methods are not necessarily "clean" and free of imperfections, defects, and impurities. In fact, the quality of interfaces between SiNCs and the host matrices cannot be compared to those obtained by epitaxial growth methods; their shape and symmetry are less regular than nanocrystals synthesized by colloidal chemistry and the level of impurities and defects is far from those obtained by advanced silicon crystal growth techniques. Considering all these facts, one would expect to find much faster nonradiative relaxation times in SiNCs, at least a considerable variation of the PL yield among the various preparation techniques. It seems that *SC plays a major role in excluding nonradiative relaxation channels*

---

* Over the limited range where the oscillator strength has been measured, other functions such as power laws could also be fitted. The current exponential form should be considered as a guideline only.

in SiNCs. Understanding what possible mechanism could give rise to remarkably slower nonradiative relaxation rates is a major issue in the field and is expected not only to explain the origin of the efficient PL, but also to explore novel aspects of SC at the nanoscales. A possible mechanism that could prevent nonradiative relaxation processes at these length scales, and is related to SC, is presented and discussed in the following section (the vibron model). In principle, understanding this mechanism may open up new horizons concerning surface engineering of nonradiative processes at nanoscales.

25.4 The Vibron Model: The Relationship between Surface Polar Vibrations and Nonradiative Processes

The purpose of this section is to discuss basic properties of SiNCs surfaces, particularly the silicon–SiO$_2$ interface (Section 25.4.1) as most experimental data reported so far are related to SiNCs embedded in silicon dioxide matrices. The "vibron" model[19] (Section 25.4.2), which correlates surface vibrations at the silicon–SiO$_2$ interfaces to nonradiative processes, is proposed as a specific mechanism that passivates the nanocrystals against nonradiative relaxation channels. Such a mechanism can explain the role of SC and its influence on nonradiative relaxation processes in SiNCs. Finally, in Section 25.4.3, we describe recent experimental results that seem to support the vibron model.

25.4.1 The Silicon–Silicon Dioxide Interface

The silicon–SiO$_2$ interface is one of the most studied interfaces due to the vital role it plays in microelectronics, particularly in the MOS (metal-oxide-semiconductor) technology. In general, it is well known that thermally grown oxide on top of a crystalline silicon substrate has amorphous structure down to distances of about 1–3 nm away from the interface. The common picture of the interface is that of 1–2 monolayers of non-stoichiometric SiO$_x$ (with $1 < x < 2$), followed by 1–2 nm of strained SiO$_2$ and a remaining layer of stoichiometric, strain-free amorphous SiO$_2$.[1] The Si–SiO$_2$ interface plays a major role in the MOS technology as it can permanently trap charges (interface charges) acting as a source of voltage that shift the electrical characteristics of MOS devices. The amount of surface traps can be as high as 10^{15} cm^{-2} (meaning that essentially all surface atoms can trap charges); however, after hydrogen annealing that passivates most of surface dangling bonds, the amount of surface traps can be reduced to a level of ~10^{10} cm^{-2} or less. The electronic properties of bulk silicon crystals are almost insensitive to these imperfections due to the very small STV ratio of bulk materials (see, Figure 25.3). However, for small SiNCs, the circumstances are substantially different as the number of atoms (or molecules) belonging to the surface of the nanocrystal is similar to the number of silicon atoms of the "bulk" nanocrystal.

Several theoretical and experimental investigations have been conducted for exploring the nature of the interface transition region, of about 1–3 nm, where the structure changes from a perfect order of crystalline silicon to a disordered structure of amorphous SiO$_2$. Numerous reports[77–80] have shown that the interface may include few monolayers of compressed crystalline, epitaxial-oxide phase in the form of either cristoblite,[81] quartz, or even tridymite.[82] After few monolayers of strained crystalline oxide, the stress is released and amorphous phase of SiO$_2$ appears. A quite remarkable demonstration to the presence of crystalline SiO$_2$ phase at the Si–SiO$_2$ interface has been reported by Cho et al.[83] using thermally oxidized SOI (silicon-on-insulator) substrates to create a thin crystalline silicon layer embedded in between relatively thick amorphous SiO$_2$ (a 2D silicon quantum well*). The cross-section HRTEM images of these structures, which can be considered as 2D analogous[84] of 0D SiNCs, are shown in Figure 25.19a and b. Despite that the exact crystalline phase of SiO$_2$ could not be identified in this experiment, these images demonstrate the possibility of creating crystalline SiO$_2$ at the Si–SiO$_2$ transition region. Notice also that the model of surface passivation by Si=O double bonds (see Section 25.3.2) proposed by Wolkin et al.[17] has been shown to be consistent with the presence of cristoblite phase at the transition region of the interface.[85] The remarkable point about the TEM images shown in Figure 25.19a and b is the fairly thick crystalline-oxide layer, of ~2–3 nm, which may contain more than 10 monolayers of crystalline SiO$_2$. The situation is much more complicated when dealing with nonplanar surfaces such as the spherical surface of SiNCs. The EFTEM (energy filtered TEM) image of a single SiNC, shown in Figure 25.19c, was taken from Ref. [86] and is one of the best images of a single nanocrystal ever been reported. Daldosso et al.[86] provided clear evidences to the existence of a Si–SiO$_2$ spherical transition region, of about 1 nm in thickness, which is marked by the dashed lines in Figure 25.19c. While the signature of crystalline SiO$_2$ is absent in this image, it is worth noting that such a signature from few monolayers of a crystalline phase, thinner than 2 nm, has not been observed even for planar surfaces and definitely not for the much more challenging spherical surfaces discussed here. The presence of a spherical transition region made of crystalline SiO$_2$ is not a prerequisite for the vibron model to be discussed in Section 25.4.2. Yet, the existence of such a surface would provide a supplementary support to the model as coherent vibrations across the SiNCs surface, are expected to enhance the vibron effect (see Section 25.4.2) as compared to noncoherent vibrations. The presence of such a surface would also help to understand the analogy between the "classical" polaron problem and the vibron model as "phonons"

---

* Some readers may ask if such 2D silicon nanostructures could show similar quantum size effects (such as PL). However, as far as electronic properties are concerned, these 2D structures behave as 0D SiNCs. The reason is local fluctuations, on length scales of 1–2 monolayers, of the oxide layer that cannot be avoided during thermal oxidation. These fluctuations induce strong localization of the electronic wavefunctions that resembles the 0D characteristics of SiNCs (with lesser control of the additional confinement scales[84]).



FIGURE 25.19 HRTEM images of crystalline SiO_2 on ultrathin silicon (100) layers with thicknesses of (a) 1.9–2.2 nm and (b) 1.4–1.6 nm. (c) High-resolution energy filtered TEM of a SiNC. The presence of silicon (111) reticular planes is clearly visible in the core region. The dotted lines mark the interface transition region. (Reprinted from Daldosso, N. et al., *Phys. Rev. B.*, 68, 085327, 2003, Cho, E.-C. et al., *J. Appl. Phys.*, 96, 3211, 2004. With permission.)

are natural vibrations of a crystalline SiO_2 phase. However, this is essentially a technical point and the vibron model can be justified even in the absence of a crystalline SiO_2 shell.

25.4.2 The Vibron Model

Following the conclusions of Section 25.3, particularly the conclusion that the high PL efficiency is due to the inhibition of nonradiative relaxation in SiNCs, we should look for a specific mechanism, associated with SC, which can "passivate" the nanocrystals against nonradiative relaxation processes. Such a mechanism has been proposed in Refs. [18,19,87,88] and is called the "vibron" model. Let us briefly explain this model that assigns the inhibition of nonradiative channels to a resonant coupling between electronic states of the nanocrystals and surface vibrations of the silicon–oxygen bonds. These vibrations can be either noncoherent, e.g., vibrations associated with the Si–O and/or the Si=O bonds on the surface of the SiNCs, or coherent vibrations of a spherical crystalline SiO_2 shell that wraps the inner crystalline silicon core of the nanocrystals.

In general, a major source of scattering and relaxation in any semiconductor is the electron scattering from lattice vibrations of its own crystal, known as phonons.[89] The phonon dispersion relation (e.g., the relation between the frequency and the wavevector of the phonons) consists of two branches: an acoustic branch (where ω goes to zero as $\vec{k}$ approaches zero) and an optical branch of phonons that can interact with light (with nonzero value of ω at $\vec{k} \to 0$). In addition, each of these branches is divided into longitudinal and transversal phonon modes where, for longitudinal modes (LO and LA), the atoms vibrate parallel to the propagation direction while for transversal modes (TO and TA), the atoms vibrate perpendicular to the propagation direction of the phonons. In polar semiconductors (such as GaAs), where ions constructing a unit cell of the crystal carry positive and negatives (ionic) charges, longitudinal vibrations of the crystal generate a long-range polarization field. The polarization field is an electric field produced by the electric dipole moment of the vibrating ions, which is responsible for the strong interaction between LO phonons and charged carriers (electrons and holes) in polar semiconductors, and is a major source of scattering and energy dissipation in these semiconductors.[90] In silicon, however, the situation is quite different as silicon is a covalent semiconductor having the same atoms in a unit cell of the crystal that do not carry a net charge. Therefore, neither longitudinal nor transversal phonon vibrations in silicon generate a polarization field, giving rise to significantly slower phonon scattering rates compared to polar semiconductors. The presence of charged impurities, vibrating bonds, or any other source of oscillating electric dipoles (or charges) on the surface of silicon could generate electric field that interacts with the charged carriers. However, these are small surface effects that have minor impact on the electronic properties of bulk silicon crystals.

The situation is substantially different when dealing with low-dimensional silicon nanostructures, particularly small SiNCs. In these nanocrystals, the surface can no longer be treated as a small perturbation since a significant portion of the atoms sit on the surface of the nanocrystals (see Figure 25.3). While vibrations of the core silicon crystal cannot produce a polarization field, polar vibrating bonds on the surface of the nanocrystals can generate a polarization field, in the vicinity of the nanocrystals, that interacts with the charged carriers. This is the basic mechanism that stands behind the vibron model[19]. Some readers may argue that this picture seems to contradict our goal, e.g., finding a mechanism that will allow to passivate the nanocrystals against nonradiative processes. Indeed, the smaller are the nanocrystals the bigger is the surface area giving rise to larger amount of nonradiative relaxation channels. This is also the case for SiNCs with a diameter larger than 10 nm. However, for smaller SiNCs with a diameter less than 10 nm, a new mechanism of resonant coupling between surface vibrations and electronic states appears and allows passivating the nanocrystals against nonradiative channels.

To follow the origin of this mechanism, let us consider the SiNC schematically illustrated in Figure 25.20, which consists



FIGURE 25.20 Schematic illustration of a spherical silicon nanocrystal terminated with silicon–oxygen bonds. The dashed area represents a surface region where a crystalline SiO_2 shell could be formed. The inset illustrates the Si–O–Si asymmetric stretching mode of vibration.

of (approximately) spherical nanocrystalline silicon core terminated with silicon–oxygen bonds on its surface. Traditionally, finding the electronic levels and the vibrational modes of a bulk semiconductor have been treated as two independent problems (the so-called adiabatic approximation) as the electronic energies are of the order of few eV while vibrational (or phonon) energies are an order of magnitude smaller. At present, we will follow this picture, but later on we will reexamine this assumption. The SiNCs spectrum of electronic levels has been calculated by several groups using various techniques such as tight-binding,[58,91] pseudo-potential,[59] and effective mass.[92,93] Most reports have focused on the lowest unoccupied conduction level (called the LUMO state) and the highest occupied valence level (the HOMO state) as these levels are involved in interband optical transitions contributing to the PL. However, the vibron model requires some knowledge about higher excited states of the system. In direct bandgap semiconductor nanocrystals, it is convenient to classify the electronic levels according to their orbital symmetry using the standard atomic orbital notations, e.g., *S*, *P*, *D*, etc.[2] Several factors make the classification for SiNCs more complex. First, the anisotropic effective mass of conduction electrons (with a transverse mass of $0.19m_0$ and longitudinal mass of $0.92m_0$) may gives rise to a splitting of the levels with lower energy levels associated with the heavier mass. Secondly, the six minima degeneracy of the conduction band in bulk silicon (near the *X*-point, along the family of (100) directions; see Figure 25.1), which should be preserved for an ideal spherical dot, will be lifted by any deviation from a perfect spherical symmetry. In addition, a unique splitting into two groups of levels that are symmetric/antisymmetric under inversion (e.g., $\vec{k} \rightarrow -\vec{k}$) are expected for small SiNCs due to intervalley couplings.[91] Finally, mixing between different bands is expected in small SiNCs.

For the purpose of our model, we will ignore most of these fine splitting and mixing features, referring to the lowest two sublevels of each band as $1S_e$ and $1P_e$ for conduction electrons ($1S_h$ and $1P_h$ for holes), as schematically illustrated on the left side of Figure 25.21. E_g is the effective energy bandgap (the energy difference between the $1S_e$ and the $1S_h$ states) and ΔE_C and ΔE_V are the energy differences between lowest conduction and valence sublevels, respectively. On the right side of Figure 25.21, we schematically illustrate the configuration space diagram for the Si=O surface bonds (e.g., the variation of the potential energy versus the length of the Si=O bond) with a ground vibrational state and a first excited state having a vibrational energy of $\hbar\omega_{VB}$ (a common approximation here is taking the potential energy to be parabolic and the quantized vibrational levels and energies being the levels of a simple harmonic oscillator). The vibrational energies are measured upward for conduction electrons and downward for valence holes. Notice that vibrational energies are size independent (e.g., independent on the diameter of the nanocrystal), depending only on the type of bonding used to terminate the surface of the nanocrystal. On the other hand, the quantized electronic levels of the nanocrystal are size dependent and should increase with the decreasing diameter of the SiNCs. Hence, for (relatively) big SiNCs, one expects the conduction/valence energy differences to be fairly small compared to vibrational energies. With the decreasing size of the



FIGURE 25.21 Schematic illustration of the condition for resonant coupling between electronic sublevels and surface vibrations. On the left, the lowest electronic sublevels of the conduction ($1S_e$ and $1P_e$) and the valence ($1S_h$ and $1P_h$) bands are shown. ΔE_C and ΔE_V are the energy differences between these sublevels. On the right, the ground and the first excited vibrational states are shown (with $\hbar\omega_{VB}$ being the vibrational energy). The solid lines represent the potential energy for surface vibrations (in the configuration space). Resonant coupling occurs once the vibrational energy is equal to ΔE_C or ΔE_V.

nanocrystals, ΔE_C (and ΔE_V) increases until, for a given diameter of the nanocrystals, the two energies (electronic and vibrational) coincide. This is the condition for *a resonant coupling between surface vibrations and the electronic states of the nanocrystals via a polarization field of the vibrations.*

The above model should slightly be modified when dealing with surface phonons of a crystalline SiO_2 shell, but the main conclusion concerning resonant coupling between electronic states and surface phonons, remains valid.* In this case, we will focus our attention on LO phonons as these phonons generate a considerably large polarization field. In general, the dispersion relation of the phonons should be taken into account (e.g., the dependence of the phonon energy on the phonon wavevector, $\vec{q}$), but, to a first order approximation we may take the LO phonon energy to be dispersionless and equal to $\hbar\omega_{LO}$. When the condition for a strong coupling is fulfilled, $\Delta E \approx \hbar\omega_{LO}$, the electrons and the phonons are not anymore in the weak coupling regime where scattering and energy dissipation occur. Instead, the strong coupling between electrons and phonons gives rise to a creation of virtually everlasting mixed electron–phonon modes, called polarons. In polar semiconductor quantum dots, these polarons are due to strong coupling between the electrons and the LO phonons of the same crystalline core while in the vibron case, a similar coupling occurs between surface phonons of the crystalline shell and the core electrons. These surface polarons “passivate” the surface against nonradiative relaxation processes. Let us emphasize that this process of creating surface polarons (vibrons) is expected to be particularly important in silicon where, as opposed to polar semiconductors, only surface phonons (or vibrations) can produce a polarization field explaining the crucial role of SC in SiNCs.

The polaron state of nanocrystals can be viewed as a “dressed” state of the electron–phonon system. A simple illustration of a polaron state is depicted in Figure 25.22 where the negatively charged electron produces a local disturbance to the polarization field of the lattice (which is created by longitudinal lattice vibrations). In the vibron case, the surface polaron is a “dressed” state of the surface, meaning that the electron and/or the hole are coupled to the surface of the SiNC. This provides a direct explanation and a specific mechanism to the model of Wolkin et al.[17] of surface-trapped electrons/holes/excitons discussed in Section 25.3.2. Here again, resonant coupling to surface vibrations can produce a localized (or trapped) electron-surface vibrations, hole-surface vibrations, or a localization of the entire exciton as suggested by Verzelen et al.[94] Another important characteristic of the polaron problem, which can be utilized for experimental verification of the model, is the polaron energy splitting due to confinement. To follow this phenomenon, one needs to solve the entire polaron Hamiltonian including the electron-polar phonon interaction, finding the new eigen-energies of the polaron that becomes a mixed state of the electrons (or the holes) and the phonons. While the exact algebra is quite complicated and tedious, a simplified model has been proposed by Mahdouani et al.[95] by limiting the interaction into the subspace of the $|1S_{e(h)}, 1\vec{q}\rangle$ and $|1P_{e(h)}, 0\vec{q}\rangle$ uncoupled states, which are composed of the electronic ground state ($1S_{e(h)}$) + 1 phonon state ($1\vec{q}$), and the first excited electronic state ($1P_{e(h)}$) + 0 phonon state ($0\vec{q}$), respectively. In this subspace, the electron–phonon interaction Hamiltonian (known as the Fröhlich Hamiltonian[96]) takes the following form:



FIGURE 25.22 Schematic description of the polaron formation mechanism. On the left, the polarization field from the unperturbed lattice of charged ions is shown while on the right, the perturbed field (e.g., the polaron) created by a negatively charged electron (dotted circle) is presented.

$$H_{POL} = \begin{pmatrix} E_S + \hbar\omega_{LO} & W \\ W^* & E_P \end{pmatrix} \tag{25.9}$$

where

E_S, E_P are the electronic energies of the 1*S* and the 1*P* sublevels, respectively

$\hbar\omega_{LO}$ is the LO phonon energy

The off-diagonal electron–phonon interaction term is given by $W = \langle 1S_{e(h)}, 1\vec{q} | H_{el-ph} | 1P_{e(h)}, 0\vec{q} \rangle$

The solution to this problem (e.g., diagonalization of the Fröhlich Hamiltonian) yields the mixed electron (hole)–phonon states of the vibron and the energies of the vibron, which are schematically illustrated in Figure 25.23.

The lower energy branch (E_-) has a phonon-like behavior ($E_- \approx \hbar\omega_{LO}$) for small SiNCs and behaves as an electronic state ($1P_e$) for large SiNCs (with $E_- \approx \Delta E_C \sim 1/d^{\eta}$; see Equation 25.3). The upper branch (E_+) is electronic-like for small SiNCs and phonon-like for

---

* For the sake of simplicity, we have ignored the effect of confinement on the spectrum of phonons and their dispersion relation. However, this topic could lead to additional novel phenomena that have not been studied so far.



FIGURE 25.23 Schematic presentation of the vibron energies (solid lines) as a function of the nanocrystal diameter. The dashed lines represent the vibrational energy, which is not affected by the confinement (horizontal line), and the electronic energy (ΔE_C), which depends on the diameter of the nanocrystal.

large SiNCs. However, the most interesting behavior occurs for $\Delta E_C \approx \hbar\omega_{LO}$ (the resonant coupling condition), where the polaron states are mixed states of the form $\left|\psi^{\pm}_{POL}\right\rangle = a_{\pm}\left|1S_e,1\vec{q}\right\rangle + b_{\pm}\left|1P_e,0\vec{q}\right\rangle$ (with $|a_{\pm}|^2 + |b_{\pm}|^2 = 1$). Similar results can be obtained for the hole–phonon coupling[95] and for the exciton–phonon coupling.[94] In principle, the same formalism can be applied to noncoherent surface vibrations with $\hbar\omega_{VB}$ replacing $\hbar\omega_{LO}$. Yet, this problem requires further investigation as the application of the Fröhlich Hamiltonian for coupling to surface vibrations and/or amorphous phases has not been investigated so far. Finally, let us point out that measuring the vibron energies can provide a direct verification to the model. This is the subject of Section 25.4.3.

25.4.3 Experiments Supporting the Vibron Model

At first, let us mention several reports about polar optical phonons of the silicon–SiO_2 planar interfaces, which have been theoretically predicated[97] and experimentally observed.[98] In these planar Si–SiO_2 interfaces, polar optical phonons of the oxide layer give rise to enhanced scattering and energy dissipation, from charged carriers moving in the adjacent silicon channel of MOS devices and bipolar transistors having SiO_2 spacer layers.[98] In this case, the interaction with polar optical phonons causes a lower mobility of the carriers and a degradation of the current–voltage characteristics. As discussed in the previous section, this is the regime of weakly coupled electrons–phonons that is reflected by energy dissipation and enhanced nonradiative relaxation rates.

Among the first experiments providing direct evidence for vibrons in SiNCs is the one reported in Refs. [87,88]. In this experiment, the aim was to measure inter-sub-level (ISL) optical transitions between the quantized sublevels of SiNCs,[93] for example, the $|1S_e\rangle \to |1P_e\rangle$ and the $|1S_h\rangle \to |1P_h\rangle$ ISL transitions between the quantized states of the conduction and the valence bands, respectively (see Figure 25.21, left). Ignoring band mixing, let us indicate that these are optical transitions between sublevels coming from the same band and therefore, having the same Bloch wavefunction (for example, the same conduction Bloch state for both the $|1S_e\rangle$ and the $|1P_e\rangle$ sublevels). Hence, dipole matrix elements for optical transitions between these sublevels are reduced to dipole matrix elements between envelope states of these sublevels.[99,100] Thus, the $|1S_e\rangle \to |1P_e\rangle$ transition is a dipole allowed optical transition (with the oscillator strength for this transition being close to 1[91]) that can be measured by infrared absorption spectroscopy. Let us emphasize that ISL optical transitions are a direct manifestation of QC as these sublevels do not exist in bulk semiconductors.[101] In addition, according to the vibron model, these sublevels are expected to interact with surface polar vibrations yielding modified energy spectra similar to those presented in Figure 25.23. Therefore, this experiment should be sensitive to both QC and SC in SiNCs.

The experimental setup for measuring ISL transitions[101] in SiNCs includes a visible pump laser exciting electron–hole pairs* (excitons) and a weak, tunable IR probe beam measuring the photoinduced absorption (PIA) spectra. Both the photoinduced transmittance, ΔT, and the linear IR transmittance, T, are measured (by modulating the pump laser beam in one experiment and the probe beam in a second experiment using a lock-in detection method[87]) to obtain PIA: PIA = $\Delta T/T$.† The same set of co-sputtered SiNC samples, with varying average diameter (and silicon volume content; see Figure 25.5), which were used for the PL experiments (see Figures 25.9 through 25.11), have also been exploited for PIA measurements to allow investigation of possible correlation between these experiments.

Figure 25.24 presents the linear IR absorption (dashed line) and the PIA (solid line) spectra for SiNCs having an average diameter



FIGURE 25.24 Room temperature PIA (symbols and a solid line) and linear IR absorption (dashed line) spectra for the sample with average diameter of 4.5 nm.

---

* Since our SiNcs are essentially undoped, the carriers must optically be induced. Once a technology to introduce dopants into SiNCs will emerge, it would be interesting to investigate direct ISL transitions from SiNCs having a single type of carriers.

† The linear and the photoinduced transmittance are given by $T = T_0 e^{-\alpha \cdot d}$ and $\Delta T = T_0[e^{-\alpha \cdot d} - e^{-(\alpha+\Delta\alpha)\cdot d}]$ where α is the linear absorption coefficient and $\Delta\alpha$ is the photoinduced absorption coefficient. Hence, we find PIA $= \Delta T/T = 1 - e^{-\Delta\alpha \cdot d} \cong \Delta\alpha \cdot d$ where we have assumed that $\Delta\alpha \cdot d \ll 1$.

of 4.5 nm (x = 18%). The linear IR absorption spectrum includes a single absorption band, at about 130–150 meV (1050–1210 cm^{-1} in terms of wavenumbers), of the Si–O asymmetric stretching mode of vibration,[102,103] schematically illustrated in Figure 25.20. Similar linear IR absorption spectra have been obtained for all SiNCs embedded in SiO$_2$ matrices. The PIA spectrum reveals two photoinduced absorption bands; a relatively strong and narrow band at ~135 meV and a fairly broad, high-energy band at about 280 meV. The broadening of the PIA bands is expected here as absorption measurements average over all sizes of nanocrystals according to the size distribution of each sample (see Figure 25.5). In fact, the fairly narrow linewidth of the low-energy band (FWHM of ~20 meV) is quite surprising taking into account the size distribution. As the PIA technique is not sensitive to the polarity of the carriers, we may use the effective mass approximation for assigning the low-energy PIA band to valence-ISL (VISL) transitions and the high-energy band to conduction-ISL (CISL) optical transitions.[91–93] However, another explanation of assigning both bands to CISL transitions is possible, where the $1P_e$ state of the conduction splits into two sublevels, mainly due to differences between longitudinal and transversal conduction effective masses.[91] In the following, we follow the first scenario but the main conclusions of this experiment remain valid for the second scenario as well.

Next, in Figure 25.25, we show the PIA spectra for a series of SiNCs having variable average diameter, from 4 up to 6 nm. This is also the range of diameters where the two PIA bands could be resolved from the noise. Surprisingly, while the high-energy CISL absorption band shows a remarkable redshift with the increasing size of the nanocrystals, the low-energy VISL band presents a significantly weaker shift to the red, with the energy of the VISL transition (120–140 meV) being fairly close to the energy of the Si–O asymmetric stretching mode of vibration (~135 meV).



FIGURE 25.25 PIA spectra for selected samples of different average diameters from 4 up to 6 nm. The dashed lines indicate the remarkable redshift of the CISL band and the much weaker shift of the VISL band.



FIGURE 25.26 The measured ISL energies (left axis-CISL, right axis-VISL) versus the confinement energy. The horizontal dashed line indicates the energy of the Si–O asymmetric stretching mode of vibration.

To correlate the results with the vibron model, we present in Figure 25.26 the PIA peak energies for both ISL bands (ΔE_C and ΔE_V) versus the confinement energy, ΔE (defined here as $\Delta E = E_{PL} - E_G$ with E_{PL} being the peak PL energy of the sample). The CISL energies display a linear dependence on ΔE as expected from the QC model (where both ΔE and $\Delta E_C \sim 1/d^{\delta}$ according to Equation 25.3). On the other hand, the VISL energies show a sublinear dependence on ΔE, approaching the vibrational energy of the Si–O stretching mode of vibration. The dashed line in Figure 25.26 represents the expected dependence of the VISL energies on ΔE according to the QC model (i.e., $\Delta E_V \sim \Delta E$). This line crosses the vibrational energy of the Si–O vibration, which is independent of the size of the nanocrystals, and is represented by the horizontal dashed-dotted line in Figure 25.26. Hence, the anti-crossing of the VISL energies and the vibration energies, which resembles the anti-crossing shown in Figure 25.23 (the vibron model), suggests that electronic states of the valence band are resonantly coupled to Si–O surface vibrations to create vibrons.

Notice also that the amplitude (or the strength) of the PIA bands increases with the decreasing size of the nanocrystals, up to a diameter of ~4.5 nm and then, decreases until the PIA spectra could not be resolved for SiNCs smaller then 2.5 nm. These results provide additional support to the vibron model. The correlation between the integrated PIA (e.g., the area below the VISL absorption bands shown in Figure 25.25) and the integrated PL, which is presented in Figure 25.27, suggests that the same mechanism, e.g., the formation of vibrons, is also responsible for the high PL efficiency. For SiNCs having a diameter in the range of 4–4.5 nm, the energy difference between the lowest valence sublevels becomes comparable to those of the Si–O surface vibrations. As a result, long-lived vibrons are created giving rise to slow nonradiative relaxation rates that, in turn, enhance



FIGURE 25.27 The correlation between the integrated PL (dashed line and circles) and the integrated PIA (solid line and squares) where both the PL and the PIA have a maximum in the range of 4.5–5 nm.

the PL efficiency. This mechanism, which takes into account the mutual role of QC and SC, also explains the correlation between the PIA and the PL shown in Figure 25.27. Finally, let us point out that the Si–O asymmetric vibration is related to a "longitudinal" mode of vibration where the oxygen atom vibrates back and forth along the line joining the axis of the two silicon atoms (see Figure 25.20). This vibrational mode is expected to generate a strong polarization field relative to other Si–O vibrations[103] such as the symmetric stretching mode (at about 810 cm^{-1}), which can be seen in the linear IR absorption spectrum but without any correlation to the PIA spectra, and the Si–O rocking mode of vibration at ~450 cm^{-1}. Notice that, it has been suggested that the asymmetric lineshape of the Si–O stretching mode at ~1100 cm^{-1} (see Figure 25.24) is due to the two "quasi-phonon" modes of the amorphous SiO_2 medium,[104] with the AS_1 (first asymmetric stretching) mode at 1076 cm^{-1} being related to "in-phase" motion of adjacent oxygen atoms while the AS_2 mode at ~1250 cm^{-1} is related to "out-of-phase" motion of adjacent oxygen atoms.[103] Clearly, only the AS_1 mode is expected to generate a long-range polarization field, a result that can explain the strong asymmetry of the VISL band (see Figure 25.24), once approaching the high-energy shoulder of the linear Si–O stretching vibration.

Additional experimental results supporting the vibron model come from a single quantum dot spectroscopy of SiNCs fabricated by the laser pyrolysis technique (see Section 25.2). Martin et al.[105] have succeeded to dissolve SiNCs (surrounded by SiO_2), disperse them in polymer matrices and to spin-cast the nanocrystals on glass substrates for a single silicon nanoparticle spectroscopy. The PL spectra, shown in Figure 25.28 for two different sizes of nanocrystals, reveal vibronic features of low-energy PL satellites, at about 130–160 meV below the high-energy peaks. These satellite peaks have been interpreted as (surface) phonon-assisted optical transitions where the high-energy PL band is related to a zero-phonon transition (having homogeneous linewidth of ~100 meV) and a low-energy PL shoulder that is related to a phonon-assisted transition. Notice that phonon-assisted optical transitions (both interband[106] and ISL[58]) have been predicted for SiNCs; however, in most cases the bulk phonons of silicon have been considered rather than polar surface vibrations (which could be either Si–O surface vibrations, or AS phonons of amorphous-SiO_2 or LO phonons of a crystalline SiO_2 shell). A similar phenomenon of vibronic satellites in the PL spectrum has also been reported for PS particles.[107] In another work, vibronic features due to surface-oxide absorption band using ellipsometric measurements[108] have been reported. Seraphin et al.[109] have shown that modifying the surface passivation of SiNCs does not alter the PL spectrum and only the PL intensity is changed, apparently due to modification of the surface bonds with a higher PL intensity associated with the more polar surface bonds.



FIGURE 25.28 PL spectra of two, single SiNCs prepared by the laser pyrolysis techniques with vibronic features (low-energy shoulders). The dotted lines represent fitting to a double Gaussian lineshape. (Reprinted from Martin, J. et al., *Nano Lett.*, 8, 656, 2008. With permission.)

Finally, let us discuss the recent magneto-PL experiment reported by Godefroo et al.[110] In this experiment, pulsed magnetic fields up to 50 T have been applied to SiNCs and the corresponding energy shift of the PL has been measured. The high magnetic field acts to further confine the exciton with $\ell_B = \sqrt{\hbar/eB}$ being the magnetic confinement length. Hence, free excitons of bulk nanocrystals are expected to show a blueshift in response to high enough B-fields, while localized or trapped excitons are not expected to show a similar shift. Indeed, no blueshift of the PL has been measured for SiNCs embedded in SiO_2. The authors have interpreted these observations as a PL originated from defect centers in the oxide layer that wraps the nanocrystals. However, according to the vibron model, surface-localized vibrons should not present a blueshift either. In another experiment, the authors annealed the samples in hydrogen, at temperatures low enough to avoid the creation of hydrogenated a:Si. In this experiment a blueshift of the PL has been observed, thus confirming the experimental results of Wolkin et al.[17] where H-terminated SiNCs have shown monotonic blueshift of the PL with the decreasing size of the nanocrystals (or with the increasing B-field in the case of the Godefroo experiment[110]). The topic of hydrogen-terminated SiNCs remains a puzzle that has not been addressed in this chapter for the very simple reason that no reliable methods to produce stable, H-terminated SiNCs have been reported so far. Yet, the Si–H bonds are expected to be considerably more polar than the Si–O bonds. Hydrogen atoms are highly mobile ions that can easily penetrate over few nanometers into the nanocrystalline silicon core. Even small amount of hydrogen in the silicon core is expected to produce considerable polarization field of the "core" nanocrystal. This topic calls for further investigation as the current knowledge about H-terminated SiNCs is insufficient for drawing any reliable conclusions.

25.5 Concluding Remarks

This chapter has covered one specific topic from the much broader, rapidly expanding field of silicon nanostructures and their applications, focusing on the question about the origin of the PL and the specific role of QC and SC in the eluding game played by the luminescence. Yet, this specific question is an excellent example to a situation where *small is really different*. Namely, not a property of matter that scales down in proportion to the size of the material, but rather a truly new phenomenon that appears at, and only at the nanometric length scales. The PL from silicon nanostructures appears to be such a property. The role of QC and SC is another fascinating example to the case where *physics meets chemistry* and both disciplines of science merge together into one, multidisciplinary field of nanoscience.

The questions regarding the origin of the PL from silicon nanostructures are far from being fully resolved. Many open questions still exist, some have been discussed in this chapter, some did not, and most likely, some new fundamental questions and puzzles will emerge soon. Yet, the basic direction in attempting to merge QC and SC, rather than choosing one as a sole winner, seems to be the proper approach. It is just a matter of time to see if this subjective opinion of the author of this chpater is indeed correct or not.

Acknowledgments

The author would like to thank many of his (former and current) graduate students at the Hebrew University of Jerusalem for invaluable contributions to this work, particularly, M. Dovrat, D. Krapf, Y. Shalibo, N. Arad, Y. Oppenheim-Goshen, and Y. Raichman. I wish to acknowledge the fruitful collaboration with my colleagues at the Hebrew University, including J. Jedrzejewski, J. Shappir, and especially Prof. Isaac Balberg for stimulating and helpful discussions and for critical reading of the manuscript. I wish to acknowledge the technical staff of the unit for nano-characterization (UNC) at the Hebrew University of Jerusalem, particularly Dr. Inna Popov for her assistance with the TEM measurements. I have enjoyed a fruitful and productive collaboration with X.-H. Zhang from the Chinese Academy of Sciences in Beijing and Prof. S.-T. Lee from the City University of Honk Kong during a joint project on silicon nanowires. This work has been supported by the Israel Science Foundation (ISF), the Israeli Ministry of Science, the binational Chinese–Israeli research grant provided by the ministries of science of both countries.

References

1. S. M. Sze, *Physics of Semiconductors*, 2nd edn., Wiley-Interscience, New York (1981).
2. Al. L. Efros and M. Rosen, The electronic structure of semiconductor nanocrystals, *Annu. Rev. Mater. Sci.* **30**, 475–521 (2000).
3. P. Moriarty, Nanostructured materials, *Rep. Prog. Phys.* **64**, 297–381 (2001).
4. C. J. Murphy and J. L. Coffer, Quantum dots: A primer, *Appl. Spectrosc*. **56**, 16A–27A (2002).
5. L. Pavesi, Will silicon be the photonic material of the third millennium? *J. Phys.: Condens. Matter* **15**, R1169–R1196 (2003).
6. A. G. Nassiopoulou, Silicon nanocrystals in SiO_2 thin layers, in *Encyclopedia of Nanoscience and Nanotechnology*, Vol. 9, H. S. Nalwa, Ed., pp. 793–813, American Scientific, Stevenson Ranch, CA (2004).
7. L.T. Canham, Silicon quantum wire array fabrication by electrochemical and chemical dissolution of wafers, *Appl. Phys. Lett.* **57**, 1046–1048 (1990).
8. A. G. Cullis and L. T. Canham, Visible light emission due to quantum size effects in highly porous crystalline silicon, *Nature* **353**, 335–338 (1991).
9. D. Kovalev, H. Heckler, G. Polisski, and F. Koch, Optical properties of Si nanocrystals, *Phys. Stat. Sol. (b)* **215**, 871–932 (1999).
10. G. Amato, C. Delerue, and H.-J. von Bardeleben, Eds., Structural and optical properties of porous silicon nanostructures, *Optoelectronic Properties of Semiconductor and Superlattices*, Vol. **5**, Gordon & Breach, Amsterdam, the Netherlands (1997) and references therein.
11. A. G. Cullis, L. T. Canham, and P. D. J. Calcott, The structural and luminescence properties of porous silicon, *J. Appl. Phys.* **82**, 909–965 (1997).
12. O. Bisi, S. Ossicini, and L. Pavesi, Porous silicon: A quantum sponge structure for silicon based optoelectronics, *Surf. Sci. Rep*. **38**, 1–126 (2000).
13. J. Gole and D. A. Dixon, Potential role of silanones in the photoluminescence-excitation, visible-photoluminescence-emission, and infrared spectra of porous silicon, *Phys. Rev. B*. **57**, 12002–12016 (1998).
14. J. J. Heitmann, F. Müller, M. Zacharias, and U. Gösele, Silicon nanocrystals: Size matters, *Adv. Mater.* **17**, 795–803 (2005).
15. M. Dovrat, Y. Oppenheim, J. Jedrzejewski, I. Balberg, and A. Sa'ar, Radiative versus nonradiative decay processes in silicon nanocrystals probed by time-resolved photoluminescence spectroscopy, *Phys. Rev. B*. **69**, 155311 (2004).
16. M. Dovrat, Y. Goshen, I. Popov, J. Jedrzejewski, I. Balberg, and A. Sa'ar, The role of radiative and nonradiative relaxation processes in the generation of light from silicon nanocrystals, *Phys. Stat. Sol. (c)* **2**, 3440–3444 (2005).
17. M. V. Wolkin, J. Jorne, P. M. Fauchet, G. Allan, and C. Delerue, Electronic states and luminescence in porous silicon quantum dots: The role of oxygen, *Phys. Rev. Lett.* **82**, 197–200 (1999).

18. A. Sa'ar, M. Dovrat, J. Jedrzejewski, and I. Balberg, Optical inter- and intra-band transitions in silicon nanocrystals: The role of surface vibrations, *Phys. E: Low-Dimensi. Syst. Nanostruct.* **38**, 122–127 (2007).
19. A. Sa'ar, Photoluminescence from silicon nanostructures: The mutual role of quantum confinement and surface chemistry, *J. Nanophoton* **3**, 032501 (2009).
20. A. Givant, J. Shappir, and A. Sa'ar, Photoluminescence anisotropy from laterally anodized porous silicon, *Appl. Phys. Lett.* **73**, 3150–3152 (1998).
21. B. Urbach, E. Axelrod, and A. Sa'ar, Correlation between transport, dielectric, and optical properties of oxidized and nonoxidized porous silicon, *Phys. Rev. B* **75**, 205330 (2007).
22. V. Lehmann, *Electrochemistry of Silicon*, Wiley-VCH, Weinheim, Germany (2002).
23. W. Theiβ, Optical properties of porous silicon, *Surf. Sci. Rep.* **29**, 91–192 (1997).
24. E. Sabatani, Y. Kalisky, A. Berman, Y. Golan, N. Gutman, B. Urbach, and A. Sa'ar, Photoluminescence of polydiacetylene membranes on porous silicon utilized for chemical sensors, *Opt. Mater.* **38**, 1766–1774 (2008).
25. B. Urbach, N. Korbakov, Y. Bar-David, S. Yitzchaik, and A. Sa'ar, Composite structures of polyaniline and mesoporous silicon: Electrochemistry, optical and transport properties, *J. Phys. Chem. C* **111**, 16586–16592 (2007).
26. S. Ben-Tabou de-Leon, R. Oren, M. E. Spira, S. Yitzchaik, and A. Sa'ar, Neurons culturing and biophotonic sensing using porous silicon, *Appl. Phys. Lett.* **84**, 4361–4363 (2004).
27. H. Lin, T. Gao, J. Fantini, and M. J. Sailor, A porous silicon–palladium composite film for optical interferometric sensing of Hydrogen, *Langmuir* **20**, 5104–5108 (2004).
28. S. Furukawa and T. Miyasato, Three-dimensional quantum well effects in ultrafine silicon particles, *Jpn. J. Appl. Phys.* **27**, L2207–L2209 (1988).
29. W. S. Cheong, N. M. Hwang, and D. Y. Yoon, Observation of nanometer silicon clusters in the hot-filament CVD process, *J. Cryst. Growth* **204**, 52–61 (1999).
30. S. Charvet, R. Madelon, R. Rizk, B. Garrido, O. Gonzàlez-Varona, M. López, A. Pérez-Rodríguez, and J. R. Morante, Substrate temperature dependence of the photoluminescence efficiency of co-sputtered Si/SiO_2 layers, *J. Lumin.* **80**, 241–245 (1988).
31. U. Kahler and H. Hofmaeister, Visible light emission from Si nanocrystalline composites via reactive evaporation of SiO, *Opt. Mater.* **17**, 83–86 (2001).
32. A. J. Kenyon, P. F. Trwoga, C. W. Pitt, and G. Rehm, Luminescence efficiency measurements of silicon nanoclusters, *Appl. Phys. Lett.* **73**, 523–525 (1998).
33. Z.-X. Ma, X.-B. Liao, J. He, W. C. Cheng, G. Z. Yue, Y. Q. Wang, and G. L. Kong, Annealing behaviors of photoluminescence from SiO_x:H, *J. Appl. Phys.* **83**, 7934–7939 (1998).
34. L. Ferraioli, M. Wang, G. Pucker, D. Navarro-Urrios, N. Dadosso, C. Kompocholis, and L. Pavesi, Photoluminescence of silicon nanocrystals in silicon oxide, *J. Nanomater.* **2007**, 43491 (2007).
35. T. Shimizu-Iwayama, S. Nakao, and K. Saitoh, Optical and structural characterization of implanted nanocrystalline semiconductors, *Nucl. Instrum. Methods B* **121**, 450–454 (1997).
36. K. S. Min, K. V. Scheglov, C. M. Yang, H. A. Atwater, M. L. Brongersma, and A. Polman, Defect-related versus excitonic visible light emission from ion beam synthesized Si nanocrystals in SiO_2, *Appl. Phys. Lett.* **69**, 2033–2035 (1996).
37. J. Linnros, N. Lalic, A. Galeckas, and V. Grivickas, Analysis of the stretched exponential photoluminescence decay from nanometer-sized silicon crystals in SiO_2, *J. Appl. Phys.* **86**, 6128–6134 (1999).
38. Y. Posada, I. Balberg, L. F. Fonseca, O. Resto, and S. Z. Wiesz, Diffusion length measurements of minority carriers in Si-SiO_2 using the photo-grating technique, in *Microcrystalline and Nanocrystalline Semiconductors*—2000, Boston, MA, Materials Research Society Symposia Proceedings, No. 638, F.14.44, pp. 1–6, M. Fauchet, J. M. Buriak, L.T. Canham, N. Koshida, and B. E. White, Jr. Eds., MRS, Warrendale, PA (2001).
39. I. Balberg, E. Savir, J. Jedrzeijewski, A. G. Nassiopoulou, and S. Gardelis, Fundamental transport processes in ensembles of silicon quantum dots, *Phys. Rev. B* **75**, 235329 (2007).
40. I. Balberg, E. Savir, and J. Jedrzeijewski, The mutual exclusion of luminescence and transport in nanocrystalline silicon networks, *J. Non-Cryst. Solids* **338–340**, 102–105 (2004).
41. G. Ledoux, J. Gong, F. Huisken, O. Guillois, and C. Reynaud, Photoluminescence of size-separated silicon nanocrystals: Confirmation of quantum confinement, *Appl. Phys. Lett.* **80**, 4834–4836 (2002).
42. D. J. Lockwood, Z. H. Lu, and J.-M. Baribeau, Quantum confined luminescence in Si/SiO_2 superlattices, *Phys. Rev. Lett.* **76**, 539–541 (1996).
43. V. Vinciguerra, G. Franzò, F. Priolo, F. Iacona, and C. Spinella, Quantum confinement and recombination dynamics in silicon nanocrystals embedded in Si/SiO_2 superlattices, *J. Appl. Phys.* **87**, 8165–8173 (2000).
44. Z. Ma, L. Wang, K. Chen, W. Li, L. Zhang, Y. Bao, X. Wang, J. Xu, X. Huang, and D. Feng, Blue light emission in nc-Si/SiO_2 multilayers fabricated using layer by layer plasma oxidation, *J. Non-Cryst. Solids* **299–302**, 648–652 (2002).
45. P. Photopooulos, A. G. Nassiopoulou, D. N. Kouvatsos, and A. Travlos, Photo- and electroluminescence from nanocrystalline silicon single and multilayer structures, *Mater. Sci. Eng. B* **69–70**, 345–349 (2000).
46. L. Tsybeskov, K. D. Hirschman, S. P. Duttagupta, M. Zacharias, P. M. Fauchet, J. P. McCaffrey, and D. J. Lockwood, Nanocrystalline-silicon superlattice produced by controlled recrystallization, *Appl. Phys. Lett.* **72**, 43–45 (1998).
47. M. Zacharias, J. Heitmann, R. Scholz, U. Kahler, M. Schmidt, and J. Bläsing, Size-controlled highly luminescent silicon nanocrystals: A SiO/SiO_2 superlattice approach, *Appl. Phys. Lett.* **80**, 661–663 (2002).

48. M. Dovrat, Y. Shalibo, N. Arad, S.-T. Lee, and A. Sa'ar, Fine structure and selection rules for excitonic transitions in silicon nanostructures, *Phys. Rev. B* **79**, 125306 (2009).
49. N. G. Shang, U. Vetter, I. Gerhards, H. Hofsäss, C. Ronning, and M. Seibt, Luminescence centres in silica nanowires, *Nanotechnology* **17**, 3215–3218 (2006).
50. K. Sato and K. Hirakuri, Influence of paramagnetic defects on multicolored luminescence from nanocrystalline silicon, *J. Appl. Phys.* **100**, 114303 (2006).
51. M. Dovrat, N. Arad, X.-H. Zhang, S.-T. Lee, and A. Sa'ar, Optical properties of silicon nanowires from cathodoluminescence imaging and time-resolved photoluminescence spectroscopy, *Phys. Rev. B* **75**, 205343 (2007).
52. M. Dovrat, N, Arad, S. T. Lee, and A. Sa'ar, Cathodoluminescence and photoluminescence of individual silicon nanowires, *Phys. Stat. Sol. (a)* **204**, 1512–1517 (2007).
53. C. Meier, A. Gondorf, S. Lüttjohann, A. Lorke, and H. Wiggers, Silicon nanoparticles: Absorption, emission, and the nature of the electronic bandgap, *J. Appl. Phys.* **101**, 103112 (2007).
54. J. A. Moreno, B. Garrido, P. Pellegrini, C. Garcia, J. Arbiol, J. R. Morante, P. Marie, F. Gourbilleau, and R. Rizk, Size dependence of refractive index of Si nanoclusters embedded in SiO_2, *J. Appl. Phys.* **98**, 013523 (2005).
55. M. Mansour, A. En Naciri, L. Johann, J. J. Grob, and M. Stchakovsky, Dielectric function and optical transitions of silicon nanocrystals between 0.6 eV and 6.5 eV, *Phys. Stat. Sol. (a)* **205**, 845–848 (2008).
56. A. En Naciri, M. Mansour, L. Johann, J. J. Grob, and H. Rinnert, Influence of the implantation profiles of Si^+ on the dielectric function and optical transitions in silicon nanocrystals, *J. Chem. Phys.* **129**, 184701 (2008).
57. C. Cimpean, V. Groenewegen, V. Kuntermann, A. Sommer, and C. Kryschi, Ultrafast exciton relaxation dynamics in silicon quantum dots, *Laser Photonics Rev.* **3**, 138–145 (2009).
58. C. Delerue, G. Allen, and M. Lannoo, Theoretical aspects of the luminescence of porous silicon, *Phys. Rev. B* **48**, 11024–11036 (1993).
59. A. Zunger and L. W. Wang, Theory of silicon nanostructures, *Appl. Surf. Sci.* **102**, 350–359 (1996).
60. J. Valenta, R. Juhasz, and J. Linnros, Photoluminescence spectroscopy of single silicon quantum dots, *Appl. Phys. Lett.* **80**, 1070–1072 (2002).
61. J. D. Holmes, K. J. Ziegler, C. Doty, L. E. Pell, K. P. Johnston, and B. A. Korgel, Highly luminescent silicon nanocrystals with discrete optical transitions, *J. Am. Chem. Soc.* **123**, 3743–3748 (2001).
62. R. M. Sankaran, D. Holunga, R. C. Flagan, and K. P. Giapis, Synthesis of Blue luminescent Si nanoparticles using atmospheric-pressure microdischarges, *Nano Lett.* **5**, 537–541 (2005).
63. R. J. Walters, J. Kalkman, A. Polman, H. A. Atwater, and M. J. A. de Dood, Photoluminescence quantum efficiency of dense silicon nanocrystal ensembles in SiO_2, *Phys. Rev. B* **73**, 132302 (2006).
64. T. Suemoto, K. Tanaka, and A. Nakajima, Interpretation of the temperature dependence of the luminescence intensity, lifetime, and decay profiles in porous Si, *Phys. Rev. B* **49**, 11005–1109 (1994).
65. D. Kovalev, H. Heckler, M. Ben-Chorin, G. Polisski, M. Schwartzkopff, and F. Koch, Breakdown of the *k*-conservation rule in Si nanocrystals, *Phys. Rev. Lett.* **81**, 2803–2806 (1998).
66. T. Takagahara and K. Takeda, Theory of the quantum confinement effect on excitons in quantum dots of indirect-gap materials, *Phys. Rev. B* **46**, 15578–15581 (1992).
67. H. Koyama and N. Koshida, Photo-assisted tuning of luminescence from porous silicon, *J. Appl. Phys.* **74**, 6365–6367 (1993).
68. F. Herman and R. V. Kasowski, Electronic structure of defects at Si/SiO_2 interfaces, *J. Vac. Sci. Technol.* **19**, 395–401 (1981).
69. M. L. Brongersma, P. G. Kik, A. Polman, K. S. Min, and H. A. Atwater, Size-dependent electron-hole exchange interaction in Si nanocrystals, *Appl. Phys. Lett.* **76**, 351–353 (2000).
70. X. Wen, L.V. Dao, P. Hannaford, E.-C. Cho, Y. H. Cho, and M. A. Green, Excitation dependence of photoluminescence in silicon quantum dots, *New J. Phys.* **9**, 337 (2007).
71. L. Pavesi, Influence of dispersive exciton motion on the recombination dynamics in porous silicon, *J. Appl. Phys.* **80**, 216–225 (1996).
72. J. Heitmann, F. Müller, L. Yi, M. Zacharias, D. Kovalev, and F. Eichhorn, Excitons in Si nanocrystals: Confinement and migration effects, *Phys. Rev. B* **69**, 195309 (2004).
73. I. Balberg, Electrical transport mechanisms in ensembles of silicon quantum dots, *Phys. Stat. Sol. (c)* **5**, 3771–3775 (2008).
74. M. Ben-Chorin, F. Müller, F. Koch, W. Schirmacher, and M. Eberhard, Hopping transport on a fractal: ac conductivity of porous silicon, *Phys. Rev. B* **51**, 2199–2213 (1995).
75. P. D. Calcott, K. J. Nash, L. T. Canham, M. J. Kane, and D. Brumhead, Identification of radiative transitions in highly porous silicon, *J. Phys. Condens. Matter* **5**, L91–L98 (1993).
76. J. M. Ziman, *Principles of the Theory of Solids*, 2nd edn., Cambridge University Press, Cambridge, U.K. (1972).
77. A. Ourmazd, D. W. Taylor, A. Rentschler, and J. Bevk, $Si \rightarrow SiO_2$ transformation: Interfacial structure and mechanism, *Phys. Rev. Lett.* **59**, 213–216 (1987).
78. H. Kageshima, M. Uematsu, K. Akagi, S. Tsuneyuki, T. Akiyama, and K. Shiraishi, Theoretical study on atomic structures of thermally grown silicon oxide/silicon interfaces, *e-J. Surf. Sci. Nanotechnol.* **4**, 584–587 (2006).
79. V. V. Afanas'ev, A. Stesmans, and M. E. Twigg, Epitaxial growth of SiO_2 produced in silicon by oxygen ion implantation, *Phys. Rev. Lett.* **77**, 4206–4309 (1996).
80. C. Kaneta, T. Yamasaki, T. Uchiyama, T. Uda, and K. Kiyoyuki, Structure and electronic property of Si(100)/SiO_2 interface, *Microelectron. Eng.* **48**, 117–120 (1999).
81. T. Shimura, H. Misaki, M. Umeno, I. Takahashi, and J. Harada, X-ray diffraction evidence for the existence of epitaxial microcrystallites in thermally oxidized SiO_2 thin films on Si(111) surfaces, *J. Cryst. Growth* **166**, 786–791 (1995).

82. W. A. Dollase, The crystal structure at 220°C of orthorhombic high tridymite from the Steinbach meteorite, *Acta Crystallogr.* **23**, 617–623 (1967).
83. E.-C. Cho, M. A. Green, J. Xia, R. Corkish, and A. Nikulin, Atomistic structure of SiO_2/Si/SiO_2 quantum wells with an apparently crystalline silicon oxide, *J. Appl. Phys.* **96**, 3211–3216 (2004).
84. N. Pauc, V. Calvo, J. Eymery, F. Fournel, and N. Magnea, Electronic and optical properties of Si/SiO_2 nanostructures. II. Electron-hole recombination at the Si/SiO_2 quantum-well–quantum-dot transition, *Phys. Rev. B* **72**, 205325 (2005).
85. H. Kageshima and K. Shiraishi, Microscopic mechanism for SiO_2/Si interface passivation: Si=O double bond formation, *Surf. Sci.* **380**, 61–65 (1997).
86. N. Daldosso, M. Luppi, S. Ossicini, E. Degoli, R. Magri, G. Dalba, P. Fornasini, R. Grisenti, F. Rocca, L. Pavesi, S. Boninelli, F. Priolo, C. Spinella, and F. Iacona, Role of the interface region on the optoelectronic properties of silicon nanocrystals embedded in SiO_2, *Phys. Rev. B.* **68**, 085327 (2003).
87. A A. Sa'ar, Y. Reichman, M. Dovrat, D. Krapf, J. Jedrzejewski, and I. Balberg, Resonant coupling between surface vibrations and electronic states in silicon nanocrystals at the strong confinement regime, *Nano Lett.* **5**, 2443–2447 (2005).
88. A. Sa'ar, M. Dovrat, J. Jedrzejewski, I. Popov, and I. Balberg, The role of quantum confinement and surface chemistry in silicon nanocrystals at the strong confinement regime, *Phys. Stat. Sol. (a)* **204**, 1491–1496 (2007).
89. N. W. Ashcroft and N. D. Mermin, *Solid State Physics*, Saunders, Philadelphia, PA (1976).
90. J. Singh, *Physics of Semiconductors and Their Heterostructures*, McGraw-Hill, New York (1993).
91. G. Allen and C. Delerue, Efficient intraband optical transitions in Si nanocrystals, *Phys. Rev. B* **66**, 233303 (2002).
92. A. S. Moskalenko, J. Berakdar, A. A. Prokofiev, and I. N. Yassievich, Single-particle states in spherical Si/SiO_2 quantum dots, *Phys. Rev. B* **76**, 085427 (2007).
93. J. S. de Sousa, J.-P. Leburton, V. N. Freire, and E. F. da Silva, Intraband absorption in silicon nanocrystals: The combined effect of shape and crystal orientation, *Appl. Phys. Lett.* **87**, 031913 (2005).
94. O. O. Verzelen, R. Ferreira, and G. Bastard, Excitonic Polarons in semiconductor quantum dots, *Phys. Rev. Lett.* **88**, 146803 (2002).
95. M. Mahdouani, R. Bourguiga, and S. Jaziri, Polaronic states in Si nanocrystals embedded in SiO_2 matrix, *Physica E* **41**, 228–234 (2008).
96. G. D. Mahan, *Many-Particle Physics*, 3rd edn., Kluwer, New York (2000).
97. K. Hess and P. Vogl, Remote polar phonon scattering in silicon inversion layers, *Solid State Commun.* **30**, 797–799 (1979).
98. J.-Q. Lü and F. Koch, Polar phonon scattering at the Si-SiO_2 interface, *Microelectron. Eng.* **48**, 95–99 (1999).
99. For general reviews see: NATO ASI Series on *Quantum Well Intersubband Transitions: Physics and Devices*, E. Rosencher, B. Vinter, and B. Levine, Eds., *Series B: Physics*, Vol. **288**, Plenum Press, New York (1992); (b) *Series E: Applied Sciences*, Vol. **270**, Kluwer, Dordrecht, the Netherlands (1994); (c) *Intersubband Transitions in Quantum Wells: Physics and Devices*, S. S. Li and Yan-Kuin Su, Eds., Kluwer Academic, Boston, MA (1998).
100. A. Sa'ar, S. Calderon, A. Givant, O. Ben-Shalom, E. Kapon, and C. Caneau, Energy subbands, envelope states, and intersubband optical transitions in one-dimensional quantum wires: The local-envelope-states approach, *Phys. Rev. B* **54**, 2675–2684 (1996).
101. D. Krapf, S. H. Kan, U. Banin, O. Millo, and A. Sa'ar, Intersublevel optical transitions in InAs nanocrystals probed by photoinduced absorption spectroscopy: The role of thermal activation, *Phys. Rev. B* **69**, 073301 (2004).
102. H. J. Hrostowski and R. H. Kaiser, Infrared absorption of oxygen in silicon, *Phys. Rev.* **107**, 966–972 (1957).
103. C. T. Kirk, Quantitative analysis of the effect of disorder-induced mode coupling on infrared absorption in silica, *Phys. Rev. B* **38**, 1255–1273 (1988).
104. F. L. Galeener and G. Lucovsky, Longitudinal optical vibrations in glasses: GeO_2 and SiO_2, *Phys. Rev. Lett.* **37**, 1474–1478 (1976).
105. J. Martin, F. Cichos, F. Huisken, and C. von Borczyskowski, Electron–phonon coupling and localization of excitons in single silicon nanocrystals, *Nano Lett.* **8**, 656–660 (2008).
106. C. Delerue, G. Allan, and M. Lannoo, Electron-phonon coupling and optical transitions for indirect-gap semiconductor nanocrystals, *Phys. Rev. B* **64**, 193402 (2001).
107. M. D. Mason, G. M. Credo, K. D. Weston, and S. K. Buratto, Luminescence of individual porous Si chromophores, *Phys. Rev. Lett.* **80**, 5405–5408 (1998).
108. E. Lioudakis, A. Antoniou, A. Othonos, C. Christofides, A.G. Nassiopoulou, Ch.B. Lioutas, and N. Frangis, The role of surface vibrations and quantum confinement effect to the optical properties of very thin nanocrystalline silicon films, *J. Appl. Phys.* **102**, 083534 (2007).
109. A. A. Seraphin, S.-T. Ngiam, and K. D. Kolenbrander, Surface control of luminescence in silicon nanoparticles, *J. Appl. Phys.* **80**, 6429–6433 (1996).
110. S. Godefroo, M. Hayne, M. Jivanescu, A. Stesmans, M. Zacharias, O. I. Lebedev, G. Van Tendeloo, and V. V. Moshchalkov, Classification and control of the origin of photoluminescence from Si nanocrystals, *Nat. Nanotechnol.* **3**, 174–178 (2008).

26

Polarization-Sensitive Nanowire and Nanorod Optics

26.1 Introduction **26**-1
26.2 Single Nanowires and Nanorods **26**-1
Polarization of Absorption: General Concepts • Metal Nanostructures: Plasmon Phenomena • Semiconductor Nanostructures: Polarization of Luminescence • Nonlinear Phenomena in Metal and Semiconductor Nanowires • Core–Shell Nanowires
26.3 Arrays of Nanorods **26**-13
Polarization Memory in Random Nanorod Arrays • Plasmon Spectra in Self-Assembled Nanorod Structures
26.4 Conclusion **26**-17
Acknowledgments **26**-17
References **26**-18

Harry E. Ruda
University of Toronto

Alexander Shik
University of Toronto

26.1 Introduction

Our goal is to present a large group of optical phenomena observed in anisotropic nanostructures such as nanowires (NWs) and nanorods (NRs) placed in an environment with a dielectric constant ε_0 different from that of the nanostructure ε. Actually, this situation occurs for most experimental work on NWs and NRs. For instance, in recent years, a large number of works have emerged devoted to the fabrication and the investigation of NWs grown in a free-standing fashion from catalyst particle nano-islands (Duan and Lieber 2000), or in a dielectric template with cylindrical pores (Mei et al. 2003), as well as for solution-grown NRs (Peng et al. 2000). Since the dielectric constant of the semiconductor ε is usually of the order of 10 or larger, this situation is realized for NWs and NRs free-standing in air, dissolved in liquids, or embedded in most dielectric matrices. Such effects of dielectric mismatch are observed not only for the semiconductor but also for metal nanostructures, where ε also differs noticeably from ε_0 and, besides, has a complex character and a strong frequency dispersion.

Due to the dielectric mismatch, the optical electric field in the vicinity of nanostructures is dramatically distorted by polarization effects (image forces), and the field intensity inside nanostructures, and hence all light-induced phenomena (optical absorption, luminescence, photoconductivity, etc.), strongly depend on the orientation of NWs and NRs related to the light polarization. Similarly, light emitted by such nanostructures is also strongly polarized.

We emphasize that the effects considered have a pure electrodynamic nature. They are not related to the presence or absence of size quantization and other possible size phenomena in nanostructures. The effects have a very general character and, as will be shown later, the only condition for their presence, besides the dielectric mismatch with the environment, is the smallness of the NW and the NR diameter in comparison with the light wavelength, which is well satisfied in most semiconductor and metal nanostructures.

26.2 Single Nanowires and Nanorods

26.2.1 Polarization of Absorption: General Concepts

26.2.1.1 Thin Nanowires and Nanorods

It is well known that at the interface of two media with different dielectric constants, the parallel component of electric field **E**, and the normal component of electric induction $\varepsilon\mathbf{E}$ must be continuous. If we have a cylindrical NW in the external field $\mathbf{E_0}$, this means that its parallel component, $E_\parallel$, remains the same inside an NW: $E_\parallel = E_{0\parallel}$. On the contrary, the field normal to the NW axis, $E_\perp$, is different inside and outside the NW. For a planar interface, we would have $E_\perp = \varepsilon_0 E_{0\perp}/\varepsilon$ but for a cylinder where $E_\perp$ contains components both parallel and perpendicular to the interface, the expression is more complicated (Landau and Lifshitz 1984):

$$E_\perp = \frac{2\varepsilon_0}{\varepsilon + \varepsilon_0} E_{0\perp}. \tag{26.1}$$

If, instead of a long (in theory—infinitely long) NW, we have an NR, which can be considered as a prolate ellipsoid of revolution



FIGURE 26.1 Schematic view of an NW (a) and an NR (b). Depolarization factors $n_\parallel$ (curve 1) and $n_\perp$ (curve 2) for an NR (c).

with semi-axes a and $l/2$ ($a < l/2$) (Figure 26.1b), the internal field is expressed in terms of the so-called depolarization factors $n_{\parallel,\perp}$:

$$E_{\parallel,\perp} = \frac{\varepsilon_0}{\varepsilon_0 + (\varepsilon - \varepsilon_0)n_{\parallel,\perp}} E_{0\parallel,\perp}. \tag{26.2}$$

These factors depend only on the aspect ratio a/l (see Figure 26.1c) but not on the absolute dimensions and material of NRs and satisfy the conditions $n_\parallel + 2n_\perp = 1$ and $n_\parallel < n_\perp$, so that for $\varepsilon > \varepsilon_0$ the internal field, as in NWs, is maximal for the NR axis parallel to the electric field of light. For infinitely long NWs, $n_\parallel = 0$, $n_\perp = 1/2$, which gives us $E_\parallel = E_{0\parallel}$ and Equation 26.1. For simplicity, most of the results below are presented for the case of NWs but can be easily generalized to NRs by repeating the same calculations starting from Equation 26.2, rather than Equation 26.1.

For $\varepsilon > \varepsilon_0$, which is always the case for semiconductor nanostructures, Equations 26.1 and 26.2 have two important consequences:

1. The amplitude of the high-frequency electric field and, hence, the probability of optical transitions in a nanostructure depend dramatically on the light polarization, acquiring maximal values for light with a polarization parallel to its axis.
2. Illumination with unpolarized light creates a high-frequency electric field in the nanostructure with the predominant direction of the polarization parallel to its axis.

The practical consequence of the first effect is a strong dependence of the absorption coefficient α (both inter- and intraband) on the light polarization. The ratio of α in NWs for the two light polarizations is

$$\frac{\alpha_\parallel}{\alpha_\perp} = \left|\frac{\varepsilon + \varepsilon_0}{2\varepsilon_0}\right|^2. \tag{26.3}$$

For most semiconductors, this factor exceeds 30 for free-standing NWs ($\varepsilon_0 = 1$) and 4.7 for NWs in the Al_2O_3 matrix ($\varepsilon_0 \cong 3$ in the optical spectral region). Since photoconductivity and photoluminescence are proportional to the number of optically generated carriers, their anisotropy is given by the same Equation 26.3.

Note that, we consider the classical electrodynamic effects caused exclusively by the difference of the refractive indices for nanostructures and the environment. In quantum nanostructures with a noticeable size quantization, the optical matrix element becomes anisotropic (Sercel and Vahala 1990, McIntyre and Sham 1992), which may quantitatively modify the described polarization effects so that Equation 26.3 acquires an additional factor equal to the square of the ratio of the matrix elements for the two perpendicular directions.

Though the given expressions are derived for static electric fields, they remain valid for high-frequency fields as well (with ε and ε_0 corresponding to the field frequency ω), as long as the NW radius a or both the NR dimensions a, l remain much less than the light wavelength λ. The situation when this inequality is violated will be referred to as the case of "thick" NWs and considered separately in Sections 26.2.1.2 and 26.2.3.2.

The direct measurement of optical absorption in a single NW is difficult but can be replaced by measurements of photoluminescence excitation or photoconductivity (for NWs provided with contacts). All the phenomena discussed should be polarization-sensitive acquiring their maximum for the exciting light polarization parallel to the NWs. The effect in its pure form was first observed and explained in (Wang et al. 2001). The authors observed photo-luminescence and photoconductivity in InP NWs increasing up to 49 times when the polarization of the exciting light changed from perpendicular to parallel (Figure 26.2). This number exactly corresponds to Equation 26.3 for InP in air. Similar effects with a slightly lesser degree of polarization (maybe, owing to the misorientation of the NWs, the role of that is discussed elsewhere (Ruda and Shik 2005a)) were also observed in the photoluminescence of Si NWs (Qi et al. 2003) and the photoconductivity of ZnO and GaN NWs (Fan et al. 2004, Han et al. 2004).

26.2.1.2 Thick Nanowires

The quasi-static approach of the previous section is adequate only for thin nanostructures with $a \ll \lambda$. At the same time, a number of optical experiments (Fan et al. 2004, Hsu et al. 2004, Philipose et al. 2005) are performed in semiconductor NWs with a diameter as large as 100 nm and more. This is comparable with



FIGURE 26.2 Photoconductivity versus light-polarization angle in an InP NW with $a = 10\,\text{nm}$. (a) Schematic depicting the use of an NW as a photodetector: inset, field-emission scanning electron microscopy image of an NW and contact electrodes, scale bar 2 μm. (b) Conductance, G, versus excitation power density for the illumination polarized parallel (upper curve) and perpendicular (lower curve) to the NW; inset, photoconductivity anisotropy versus excitation power, equal to 0.96 for the shown device. (c) Conductance versus polarization angle. The measurements were performed at room temperature for the excitation wavelength 514.5 nm. (From Wang, J. et al., *Science*, 293, 1455, 2001. With permission.)

the interband light wavelength, which makes the formulae of Section 26.2.1.1 inapplicable for this case.

Now we theoretically consider the anisotropy of light absorption and the emission caused by image forces in semiconducting NWs of an arbitrary radius a. For a comparable to the light wavelength, the high-frequency electric field inside NWs is no longer uniform, and the polarization characteristics acquire a noticeable, non-monotonic spectral dependence allowing one to observe a number of new effects in the optical properties of NWs with submicron thickness.

We consider a cylindrical NW placed in an external ac electric field $\mathbf{E_0}$ and find the real field distribution $\mathbf{E}(\mathbf{r})$ created by $\mathbf{E_0}$ together with the NW-induced image forces. Then we calculate the total absorbed power proportional to $|\mathbf{E}(\mathbf{r})|^2$ integrated over the NW volume and study the dependence of this characteristic on the angle between $\mathbf{E_0}$ and the NW axis, which gives us the polarization dependence of our interest.

The main distinction to Section 26.2.1.1 consists in the need to find $\mathbf{E}(\mathbf{r})$ not from the Laplace but from the Helmholtz wave equation. Using cylindrical coordinates (ρ, z, φ), it can be written inside the NW ($\rho < a$) as

$$\frac{1}{\rho}\frac{\partial}{\partial\rho}\left(\rho\frac{\partial E_i}{\partial\rho}\right)+\frac{1}{\rho^2}\frac{\partial^2 E_i}{\partial\varphi^2}+\frac{\partial^2 E_i}{\partial z^2}+\varepsilon\frac{\omega^2}{c^2}E_i=0 \tag{26.4}$$

where c is the light velocity. Outside the NW ($\rho > a$) the equation differs from Equation 26.4 only by the replacement $\varepsilon \to \varepsilon_0$. The character of its solution depends on the mutual orientation of $\mathbf{E_0}$, the light wave vector $\mathbf{k}$, and the NW axis $\mathbf{z}$. Below, we will give only the final results of calculations referring the reader to the original work (Ruda and Shik 2006).

For $\mathbf{k} \perp \mathbf{z}$ (say, $k = k_x$) and $\mathbf{E_0} \parallel \mathbf{z}$, when $\mathbf{E}_0(\mathbf{r}) = E_0\,\mathbf{z}\exp[ik_0\rho\cos\varphi]$, the solution for $\mathbf{E}$ contains only a single component E_z given by the expression (Batygin and Toptygin 1978)

$$E_z(\rho,\varphi)=E_0\sum_{m=-\infty}^{\infty} i^m\frac{J'_m(ka)H_m^{(1)}(k_0a)-J_m(ka)H_m^{(1)'}(k_0a)}{\sqrt{\varepsilon}J'_m(ka)H_m^{(1)}(k_0a)-\sqrt{\varepsilon_0}J_m(ka)H_m^{(1)'}(k_0a)} \times J_m(k\rho)\exp(im\varphi) \tag{26.5}$$

where J_m and $H_m^{(1)}$ are the Bessel and the first-kind Hankel functions, $k=\sqrt{\varepsilon}\omega/c$, $k_0=\sqrt{\varepsilon_0}\omega/c$.

For the same direction of $\mathbf{k}$ but perpendicular polarization, $\mathbf{E_0} \parallel \mathbf{x}$, Equation 26.4 gives the following general solution inside the NW:

$$\mathbf{E}(\rho,\alpha)=\frac{2E_0a\varepsilon_0\nabla\left[J_1\left(\frac{\sqrt{\varepsilon-\varepsilon_0}\,\omega\rho}{c}\right)\cos\varphi\right]}{\varepsilon_0J_1\left(\frac{\sqrt{\varepsilon-\varepsilon_0}\,\omega a}{c}\right)+\varepsilon\frac{\sqrt{\varepsilon-\varepsilon_0}\,\omega a}{c}J'_1\left(\frac{\sqrt{\varepsilon-\varepsilon_0}\,\omega a}{c}\right)}. \tag{26.6}$$

At small a Equation 26.6 transforms into the static expression (Equation 26.1).



FIGURE 26.3 Spectral dependence of the polarization ratio $P^a = \left(I^a_{\|} - I^a_{\perp}\right)/\left(I^a_{\|} + I^a_{\perp}\right)$ in an NW for ε = 9, ε_0 = 1. (From Ruda, H.E. and Shik, A., *J. Appl. Phys.*, 100, 024314, 2006. With permission.)

Equations 26.5 and 26.6 show that, contrary to the case of a thin NW, the field distribution inside it is essentially nonuniform. However, real experimentally measured characteristics, such as the absorption, the photoconductivity, and the photoluminescence excitation spectra are determined not by details of this field distribution but by the total power absorbed, proportional to the integral of the light intensity over the NW cross section $I^a = \iint |E(\varphi,\alpha)|^2 \, d\varphi\rho d\rho$ (superscript *a* means absorption). Figure 26.3 shows the spectral dependence of the ratio $P^a = \left(I^a_{\|} - I^a_{\perp}/I^a_{\|} + I^a_{\perp}\right)$ characterizing the polarization dependence of the absorbed light intensity.

For $k_0a \rightarrow 0$, this ratio tends to the value $(\varepsilon^2 + 2\varepsilon\varepsilon_0 - 3\varepsilon_0^2)/(\varepsilon^2 + 2\varepsilon\varepsilon_0 + 5\varepsilon_0^2)$ corresponding to Equation 26.3. However, at higher light frequencies (or for thicker NWs) we can no longer claim that light with a parallel polarization has a much higher absorption coefficient since $I^a_{\|}$ and $I^a_{\perp}$, as well as their ratio, demonstrate a strong frequency dependence. This dependence is especially dramatic for $I^a_{\perp}$, which tends to infinity in a series of critical points corresponding to roots of the denominator Equation 26.6 and $P^a = -1$ in Figure 26.3. In our example of ε = 9, ε_0 = 1, the first of these points are k_0a = 0.68, 1.89, 3.02,. … Considering a cylindrical NW as an optical fiber, we can express each of critical points as the cut-off of a fiber mode LP_{1m} (*m* = 1, 2, 3…) with the same angular field distribution as Equation 26.6. At the cut-off, these modes become purely transverse and excited by an incident wave. The spectrum of $I^a_{\|}(\omega)$ has no singularities due to the absence of modes with a purely longitudinal polarization (**E** || **z**).

Since an infinite value $I^a_{\perp}$ at some fixed ω is definitely nonphysical, we must discuss what initial theoretical assumptions are inadequate and what phenomena are responsible for the real height of the absorption peaks. In our calculations, we have considered one single NW in the electric field of an infinite plane wave. In this case, the field in an NW can, in theory, acquire arbitrary high values remaining equal to $\mathbf{E_0}$ at very large distances. For an array of NWs with an area density *N*, the electric field will be redistributed between the NWs and their environment so that the total wave energy remains the same as that provided with external excitation in the absence of NWs and equal to $\varepsilon_0 E_0^2/4\pi$ per unit volume and the absorption coefficient is finite. There are also some other mechanisms of smoothening the mentioned singularities in $I^a_{\perp}$, e.g., non-rectilinearity and thickness fluctuations of NWs, which may become dominant at a low NW density.

The described frequency dependence of polarization-sensitive absorption has not yet been studied experimentally, except for the observation (Fan et al. 2004) that two different frequencies of excited light caused different degrees of photoconductivity anisotropy.

26.2.2 Metal Nanostructures: Plasmon Phenomena

26.2.2.1 Longitudinal and Transverse Plasmons

The conclusions of Section 26.2.1.1 and formulae presented there can be applied to both metal and semiconductor NWs and NRs but result in the different spectral dependences of optical anisotropy. The degree of polarization in thin NWs, determined exclusively by $\varepsilon/\varepsilon_0$, in semiconductor nanostructures does not explicitly depend on the light frequency ω (if we ignore the frequency dependence of ε, which in semiconductors is rather weak, even near the interband absorption edge). In metals, on the contrary, ε has a strong frequency dispersion caused by the electron plasma, which makes the polarization characteristics frequency-dependent even in the quasistatic limit of small nanostructures.

For an analytical description of these effects, we will use for ε the simplest Drude expression: $\varepsilon = 1 - \left(\omega_p^2/\omega(\omega - i\nu)\right)$ where ω_p is the plasma frequency in a bulk metal and ν is the scattering rate. Substituting this expression into Equation 26.2, we see that at a small ν (weak electron scattering), the optical electric field inside NRs increases dramatically at the frequency

$$\omega_{\|,\perp} = \frac{\omega_p\sqrt{n_{\|,\perp}}}{\varepsilon_0(1 - n_{\|,\perp}) + n_{\|,\perp}} \tag{26.7}$$

called the plasmon frequency,* which is smaller than ω_p and typically belongs to the visible spectral region. The optical absorption spectrum has a strong maximum near the plasmon frequency. In it seen that light polarized along the NR axis generates plasmons with the frequency $\omega_{\|}$ called longitudinal plasmons, while light with the perpendicular polarization generates transverse plasmons with the frequency $\omega_{\perp}$, larger than $\omega_{\|}$. In a random system of NRs with arbitrary orientations related to the light polarization (or for a nonpolarized optical excitation), the absorption spectrum has two absorption maxima: at $\omega_{\|}$ and $\omega_{\perp}$ (Kreibig and Vollmer 1995).

---

* $\omega_{\|,\perp}$ are often called the surface plasmon frequencies, to distinguish them from the plasmon frequency of bulk material ω_p.

We note that for long NWs $\omega_{\|} \to 0$, in other words, longitudinal plasmons cease to exist. Formally, it is due to the fact that in infinitely long cylinders, the parallel component of the electric field must be continuous at the interface and hence is uniform, without any structure characterizing plasma oscillations.

26.2.2.2 Transverse Plasmons in Nanowires

If we substitute the Drude expression for $\varepsilon(\omega)$ into Equation 26.3, we will see that the anisotropy of the optical absorption in metal NWs has an interesting spectral dependence. Far below the plasmon frequency, $|\varepsilon(\omega)|$ is very large, and the situation is similar to that in semiconductor NWs where the absorption is much higher for the light with parallel polarization. However, near the plasmon frequency, the absorption of the perpendicularly polarized light increases drastically, exceeding that for the parallel polarization and hence changing the sign of the anisotropy, as illustrated by Figure 26.4. At $\omega \to \infty$ the anisotropy tends to a constant value determined by ε_0 and equal to zero at $\varepsilon_0 = 1$.

Thus, the situation near the plasmon resonance is, to some extent, opposite to that of semiconductor NWs where, due to the large ε, the electric field of light is polarized mostly along the NW axis. In metal NWs, for light with the frequency in the transverse plasmon region polarized perpendicular to the NW axes, ε is close to zero. For this reason, the electric field in an NW has essentially normal polarization and very high amplitude—the effect often called the plasmon amplification (see also Section 26.2.5.3).

Though the described spectral dependences of absorption are very specific and interesting, their experimental observation is more difficult than for the effects in semiconductor NWs. In metals, we can measure neither the photoconductivity nor the luminescence excitation and have to restrict ourselves to direct measurements of optical absorption. The most straightforward method to employ is to investigate a large number of NWs suspended in some liquid optically inactive in the spectral region of interest. In this case, the orientation of NWs is random, and no polarization dependence should be observed. A strong anisotropy of absorbing objects will be revealed in a specific character of spectral dependence of the absorption coefficient (Figure 26.5). In this spectrum, strong low-frequency absorption is caused by NWs almost parallel to the light polarization while the plasmon maximum is formed by those with an orientation close to the perpendicular one.



FIGURE 26.4 Absorption anisotropy $P^a = (k_{\|} - k_{\perp})/(k_{\|} + k_{\perp})$ in metal NWs for $\varepsilon_0 = 1$ (curves 1) and $\varepsilon_0 = 3$ (curves 2). Solid curves correspond to $\nu = 0.1\omega_p$, dashed curves to $\nu = 0.5\omega_p$. (From Ruda, H.E. and Shik, A., *Phys. Rev. B*, 72, 115308, 2005a. With permission.)



FIGURE 26.5 Absorption spectrum of randomly oriented metal NWs. Solid curve corresponds to $\nu = 0.1\omega_p$, dashed curves to $\nu = 0.5\omega_p$. (From Ruda, H.E. and Shik, A., *Phys. Rev. B*, 72, 115308, 2005a. With permission.)

26.2.3 Semiconductor Nanostructures: Polarization of Luminescence

26.2.3.1 Thin Nanowires and Nanorods

In the previous sections 26.2.1 through 26.2.2, we considered the physical phenomena related to the fact that external nonpolarized light becomes strongly polarized inside a nanostructure with a high refractive index. Now, we discuss the related problem of polarization of light emitted by an NW. As a first step, we solve the auxiliary problem of finding the electric field created by an electric dipole placed at the axis of a cylinder with a radius a and a dielectric constant ε, in an environment with ε_0. Details of these calculations can be found in Ruda and Shik (2005a), and here we present only the final results. For the dipole moment $\mathbf{d}_0$ parallel to the cylinder axis (z-axis), the electric field of the radiation far from the NW, has the same amplitude and configuration as would be created by a dipole with the moment $\mathbf{d}_0$ in free space. For the normal orientation of $\mathbf{d}_0$ (along x-axis), the corresponding effective moment is given by $\mathbf{d} = 2\varepsilon_0\mathbf{d}_0/(\varepsilon + \varepsilon_0)$.

As a result, even for NWs with isotropic interband matrix elements (which is the case for cubic semiconductors and a moderate a when size quantization is negligible), where luminescence would otherwise be nonpolarized, a strong polarization under the influence of image forces is acquired.

As a second step, we consider the net polarization of luminescence from a line x, $y = 0$ containing a mixture of different emitting dipoles. We take a point z along the wire axis containing three mutually perpendicular dipoles d_x, d_y, d_z with a frequency ω and calculate the resulting electric field far from the NW at some point $(x_0, 0, 0)$ using the standard formula for the electric field of an emitting dipole and adding contributions of all line segments by integrating over z. Since radiation from different segments is incoherent, we do not add electric fields, but Poynting vectors **S** containing no phase factors. The resulting **S** is directed along the x-axis and for the two different light polarizations is

$$(S_x)_{\parallel} = \frac{\eta\omega^4}{6\pi\varepsilon_0^2 c^3 x_0}\left(d_x^2 + 2d_z^2\right), \tag{26.8}$$

$$(S_x)_{\perp} = \frac{\eta\omega^4}{2\pi\varepsilon_0^2 c^3 x_0} d_y^2 \tag{26.9}$$

where η is the density of dipoles per unit line length.

Combining these two problems and substituting $d_{x,y} = 2\varepsilon_0 d_{0x,y}/(\varepsilon + \varepsilon_0)$; $d_z = d_{0z}$ into Equations 26.8 and 26.9, provides the resulting polarization of light emitted by an NW. The intensity ratio for different light polarizations in the case of isotropic matrix elements is

$$\frac{I_{\parallel}^e}{I_{\perp}^e} = \frac{d_x^2 + 2d_z^2}{3d_z^2} \tag{26.10}$$

where superscript e means emission. If the bare dipole moment components $d_{0x,y,z}$ do not coincide due to size quantization or/and crystal anisotropy, this modifies the polarization character introducing anisotropy even in the absence of image forces, similar to the case of absorption.

It is seen from Equation 26.10 that light emitted by an NW with a dielectric constant higher than that of its environment, will be strongly polarized in the wire direction, which was clearly demonstrated experimentally (Wang et al. 2001, Qi et al. 2003). The effect is qualitatively similar to the property of absorption considered in Section 26.2.1.1 but the magnitude of polarization is different. By comparing Equation 26.3 with Equation 26.10 one can see that the degree of polarization for luminescence is less than for absorption. It is caused by the fact that, according to Equation 26.8, light with parallel polarization is generated not only by d_z dipole moments but also by d_x that are weakened by image forces. For example, for InP NWs ($\varepsilon = 12.7$) where, as was already mentioned in Section 26.2.1.1, $\alpha_{\parallel}/\alpha_{\perp} \cong 49$, Equation 26.10 gives $I_{\parallel}^e / I_{\perp}^e \cong 30$, in good agreement with the experimentally observed values of $\alpha_{\parallel}/\alpha_{\perp} \cong 48$ and $I_{\parallel}^e / I_{\perp}^e \cong 24$ (Wang et al. 2001).

All the results obtained above for semiconductor NWs remain valid also for NRs, except for the numerical values of polarization coefficients, which for NRs depend not only on $\varepsilon/\varepsilon_0$ but also on the depolarization coefficients, or, in other words, on the NR aspect ratio.

26.2.3.2 Thick Nanowires

Now we consider the polarization properties of luminescence from thick NWs where, according to Section 26.2.1.2, the electric field cannot be assumed uniform. Though in fact luminescence occurs throughout the whole NW volume, we will model it by an effective emitting dipole at the axis ($\rho = 0$). (Precise results can be obtained, if necessary, by using general formulae for a field created in a system of coaxial cylindrical layers by a dipole with an arbitrary position $\mathbf{r_0}$ followed by integration over $\mathbf{r_0}$, to be performed only numerically.) The general approach to similar problems is described in (Chew 1990), which allows us to present only the final expression for the resulting electric field outside the NW.

For the dipole moment $\mathbf{d_0}$ oriented along the NW axis ($d_0 = d_{0z}$), the electric field E_z far from the NW (at $\rho \gg k_0^{-1}$) is given by

$$\begin{aligned} E_z &\cong i\frac{d_{0z}\omega^2}{\varepsilon c^2 r}(\varepsilon - \varepsilon_0\cos^2\theta)\exp(ik_0 r - i\pi/4) \\ &\quad\times \frac{J_1(k_\rho^0 a)H_0^{(1)}(k_\rho^0 a) - J_0(k_\rho^0 a)H_1^{(1)}(k_\rho^0 a)}{J_1(k_\rho^0 a)H_0^{(1)}(k_{\rho 0}^0 a) - \dfrac{k_{\rho 0}^0}{k_\rho^0} J_0(k_\rho^0 a)H_1^{(1)}(k_{\rho 0}^0 a)} \end{aligned} \tag{26.11}$$

where

$k_\rho^0 = k_0\sqrt{\varepsilon/\varepsilon_0 - \cos^2\theta} = k\sqrt{1 - \varepsilon_0\cos^2\theta/\varepsilon}$

$k_{\rho 0}^0 = k_0 \sin\theta$

$r = \sqrt{\rho^2 + z^2}$

k_ρ^0 is the distance to the dipole

$\theta = \arccos(z/r)$ is the angle from the NW axis

If we consider the light emission normal to the dipole (along the y-axis) where $\theta = \pi/2$, the corresponding electric field will have the same coordinate dependence as that of a free dipole $\sim(d_{0z}\omega^2/c^2 r)\exp(ik_0 r)$ with an additional factor given by the fraction in Equation 26.11. Thus, the influence of image forces is equivalent to the replacement of $d_0 z$ with some effective dipole (Ruda and Shik 2006):

$$d_z = d_{0z}\sqrt{\varepsilon}\,\frac{J_1(ka)H_0^{(1)}(ka) - J_0(ka)H_1^{(1)}(ka)}{\sqrt{\varepsilon}J_1(ka)H_0^{(1)}(ka) - \sqrt{\varepsilon_0}J_0(ka)H_1^{(1)}(ka)} \equiv A_z d_{0z}. \tag{26.12}$$

For the perpendicular dipole orientation ($d_0 = d_{0x}$), similar calculations give

$$d_x = d_{0x}\sqrt{\varepsilon}\,\frac{J_1'(ka)H_0^{(1)}(ka) - J_0(ka)H_1^{(1)'}(ka)}{\sqrt{\varepsilon_0}J_1'(ka)H_0^{(1)}(ka) - \sqrt{\varepsilon}J_0(ka)H_1^{(1)'}(ka)} \equiv A_x d_{0x}. \tag{26.13}$$

Figure 26.6a shows the frequency dependence of the effective dipoles d_x and d_z. At $\omega \to 0$ they acquire the static values $d_z = d_{0z}$, $d_x = 2\varepsilon_0 d_{0x}/(\varepsilon + \varepsilon_0)$ given in Section 26.2.3.1, and then demonstrate strong oscillations. At a larger ω (or a larger a), the phases



FIGURE 26.6 (a) Spectral dependence of the effective dipoles d_x (1) and d_z (2) for an NW with $\varepsilon = 9$, $\varepsilon_0 = 1$; (b) spectral dependence of the polarization ratio P^e for the same NW. (From Ruda, H.E. and Shik, A., *J. Appl. Phys.*, 100, 024314, 2006. With permission.)

of oscillations close in, d_z approaches d_x, so that the radiation becomes almost unpolarized.

So far, we have analyzed the emission characteristics of one single effective dipole in an NW. To obtain the radiation characteristics of the whole NW, we must perform an integration over its length assuming the dipoles distributed uniformly along z, exactly as it was done in Section 26.2.3.2. Substituting Equations 26.12 and 26.13 into the first equality of Equation 26.10 and assuming an isotropic internal emission ($d_{0z} = d_{0x}$), we obtain the spectral dependence of the resulting polarization ratio $P^e = \left(I_\parallel^e - I_\perp^e / I_\parallel^e + I_\perp^e\right)$ presented at Figure 26.6b. The latter is seen to have a strong oscillatory character changing sign at some critical frequencies differing from those describing the polarization dependence of absorption (Figure 26.3).

It is evident from Figure 26.6b that, if the luminescence spectrum of an NW material contains several lines with noticeably different frequencies, the polarizations of these lines can be essentially different and even have an opposite sign. It was confirmed by experiments (Hsu et al. 2004) in ZnO NWs. This material contains two strong luminescence lines with frequencies differed 1.3 times (Figure 26.7a). As is seen from Figure 26.7b, these lines have opposite angular dependences, indicating at opposite signs of luminescence anisotropy.

Note that the same polarization phenomena must be observed not only for photo- but for any other mechanisms of luminescence. In the case of photoluminescence, a change in the exciting light polarization (for a fixed ω_{ex}) does not change the described spectra $I_\parallel^e / I_\perp^e(\omega_{em})$, but modifies the amplitudes $I_\parallel^e$ and $I_\perp^e$ synchronously according to the polarization dependence of the absorbed light intensity described in Section 26.2.1.2.

The luminescence excitation spectrum in most physical systems (including thick NWs with microscopic electronic properties coinciding with those of bulk semiconductors) actually reproduces the optical absorption spectrum and hence is given by the formulae of Section 26.2.1.2. Thus, we may claim that the polarization dependence of the luminescence excitation spectrum for any emission frequency and polarization is given by Figure 26.3.

26.2.4 Nonlinear Phenomena in Metal and Semiconductor Nanowires

26.2.4.1 Theory

It is evident that the polarization dependence of the internal optical field in NWs and NRs must result in anisotropy not only of linear but also of nonlinear optical phenomena, such as, e.g., the second harmonic generation (SHG). Moreover, one may



FIGURE 26.7 Luminescence spectrum of ZnO NW (a) with two emission lines and an angular dependence of the luminescence intensity (b) in these lines. (From Hsu, N.E. et al., *J. Appl. Phys.*, 96, 4671, 2004. With permission.)

expect the anisotropy of nonlinear effects to be larger than the linear ones, since the former are proportional to a higher degree of electric field.

The analysis of the SHG in NWs and NRs is less straightforward than that of linear effects where we took standard formulae for light absorption or emission in bulk materials and simply substituted the specific optical field distribution of nanostructures into them. On the contrary, in uniform bulk materials characterized by inversion symmetry, the SHG is completely absent. Hence, the theory of this effect in nanostructures should be developed from scratch.

We start from the classical expression connecting nonlinear polarization at the frequency 2ω with the spatial distribution of the electric field at the frequency ω (Blombergen et al. 1968):

$$\mathbf{P}^{2\omega} = \gamma\nabla(\mathbf{E}^{\omega})^2 + \beta\mathbf{E}^{\omega}(\nabla\mathbf{E}^{\omega}). \tag{26.14}$$

For nonconducting media, $\beta = -2\gamma$ and is determined by the square of linear susceptibility, while for metals $\beta = e/(8\pi m^*\omega^2\}$ and $\gamma = \beta[1 - \varepsilon(2\omega)]$ (for simplicity, $\varepsilon_0 = 1$ is assumed). Our task is to find $\mathbf{P}^{2\omega}$ for the $\mathbf{E}^{\omega}(\mathbf{r})$ determined for nanostructures in Section 26.2.1 and to use it for the calculation of the SHG intensity.

For the case of spherical nanocrystals, it was shown (Agarwal and Jha 1982) that the two terms on the right-hand side of Equation 26.14 correspond, respectively, to the volume component $\mathbf{P}_v^{2\omega}$ caused by the coordinate-dependent $\mathbf{E}^{\omega}$ inside the nanostructure and having a dipole symmetry, and the surface component $\mathbf{P}_s^{2\omega}$ caused exclusively by the nanostructure surface and with a quadrupole symmetry. Since the second term in Equation 26.14 for small nanocrystals essentially exceeds the first one, $\mathbf{P}_s^{2\omega}$ has a larger amplitude than $\mathbf{P}_v^{2\omega}$ but, at the same time, with a quadrupole, rather than a dipole symmetry, which emits less efficiently. For this reason, the relative role of these components is *a priori* not evident and depends on the direction and the polarization of light.

We restrict ourselves to the case of thin cylindrical NWs where $\omega a/c \ll 1$ can be used as a perturbation parameter. The particular expressions for $\mathbf{E}^{\omega}$ depend on the directions of the wave vector **k** and the electric field $\mathbf{E}_0^{\omega}$ of light related to the NW axis (*z*-axis) and can be obtained by expansion of the field distributions Equations 26.5 and 26.6 in terms of ω. There exist three possible optical geometries.

a. $\mathbf{k} \| \mathbf{z};\ \mathbf{E}_0^{\omega} \perp \mathbf{z}$ (longitudinal propagation, transverse polarization)

   In this case

$$E^{\omega} = E_x^{\omega} = \frac{2E_0^{\omega}}{[\varepsilon(\omega)+1]}(1 + ikz) \tag{26.15}$$

($k = \omega/c$). Substitution of Equation 26.15 into Equation 26.14 shows that $\mathbf{P}_v^{2\omega}$ is determined only by the coordinate-dependent component of $\mathbf{E}^{\omega}(\mathbf{r})$, directed along the NW axis (*z*-axis) and has the value

$$P_v^{2\omega} = \frac{8i\gamma k[E_0^{\omega}]^2}{[\varepsilon(\omega)+1]^2} = \text{const}(\mathbf{r}). \tag{26.16}$$

Thus, each elementary volume of the NW *dV* can be considered as an elementary dipole $\mathbf{P}_v^{2\omega}dV$ parallel to the NW axis. For such dipole orientation, its radiation is not disturbed by the image forces and is the same as for free dipoles (Ruda and Shik 2005a), not depending on the NW dielectric constant at the emission frequency, ε(2ω). The resulting radiation electric field at the distance $r \gg a$ from NW can be found as a sum of elementary dipoles along the whole NW. Calculations, shown in more detail in Ruda and Shik (2007a), show that at a large distance *r* from an NW ($r \gg a$; $kr \gg 1$) the SHG intensity per unit NW length is

$$I_v^{2\omega} = \frac{\pi^3\omega^3 a^4\left[P_v^{2\omega}\right]^2}{c^2} = \frac{64\pi^3\gamma^2\omega^5 a^4\left[E_0^{\omega}\right]^4}{c^4\left[\varepsilon(\omega)+1\right]^4}. \tag{26.17}$$

The radiation is emitted isotropically (independent of a particular direction of light polarization).

The surface component of polarization $\mathbf{P}_v^{2\omega}$ is determined by an $\mathbf{E}^{\omega}$ discontinuity at the NW interface caused by a dielectric mismatch, and for its determination we can retain only the first, uniform term in Equation 26.15. After simple transformations, we have

$$P_s^{2\omega} = \frac{4\beta[\varepsilon(\omega)-1]\left[E_0^{\omega}\right]^2}{[\varepsilon(\omega)+1]^2}\delta(\rho - a)\cos\alpha. \tag{26.18}$$

(ρ,α) are polar coordinates in the *xy*-plane. The direction of $\mathbf{P}_v^{2\omega}$ coincides with that of the $\mathbf{E}_0^{\omega}$ (*x*-axis). This distribution of polarization has a quadrupole symmetry. Due to the coordinate dependence of $P_s^{2\omega}$, the determination of the electric field of emitted light must contain integration not only over *z*, but over ρ and α as well. Besides, in this case, we deal with elementary dipoles directed not parallel (as for Equation 26.16) but perpendicular to the NW axis. Due to the image forces, the ac electric field of these dipoles is suppressed by the factor 2/[ε(2ω) + 1] (see Section 26.2.3.1). Under the same conditions as before, we get the intensity of this surface-related SHG component:

$$I_s^{2\omega} = \frac{4\pi^3\beta^2\omega^5 a^4\left[\varepsilon(\omega)-1\right]^2\left[E_0^{\omega}\right]^4}{c^4\left[\varepsilon(\omega)+1\right]^4\left[\varepsilon(2\omega)+1\right]^2}\sin^2(2\varphi) \tag{26.19}$$

where φ is the angle between the exciting-light wave vector **k** and the direction to the observation point. As for any quadrupole emitter, the intensity $I_s^{2\omega}$ has four directional lobes.

b. $\mathbf{k} \perp \mathbf{z}$; $\mathbf{E}_0^{\omega} \parallel \mathbf{z}$ (transverse propagation, longitudinal polarization)

In this case

$$E^{\omega} = E_z^{\omega} = E_0^{\omega}\left(1 + ikx\frac{1+\sqrt{\varepsilon(\omega)}}{2}\right) \tag{26.20}$$

and $\mathbf{P}_v^{2\omega}$, which is always colinear with the light wave vector, is directed along the x-axis normal to the NW and is equal to

$$P_v^{2\omega} = i\gamma k\left[E_0^{\omega}\right]^2\left[1+\sqrt{\varepsilon(\omega)}\right] = \text{const}(\mathbf{r}). \tag{26.21}$$

For such an orientation of elementary dipoles, the SHG is anisotropic with the radiation pattern directed perpendicularly to $\mathbf{k}$, and the ac electric field of these dipoles contains the factor $2/[\varepsilon(2\omega)+1]$. Adding the fields of elementary dipoles in the same manner as before, we get

$$\begin{aligned} I_v^{2\omega} &= \frac{4\pi^3\omega^3 a^4\left[P_v^{2\omega}\right]^2}{c^2\left[\varepsilon(2\omega)+1\right]^2}\sin^2\varphi \\ &= \frac{4\pi^3\gamma^2\omega^5 a^4\left[E_0^{\omega}\right]^4\left|1+\sqrt{\varepsilon(\omega)}\right|^2}{c^4\left[\varepsilon(2\omega)+1\right]^2}\sin^2\varphi. \end{aligned} \tag{26.22}$$

Since $\mathbf{P}_s^{2\omega}$ is caused only by the normal component of $\mathbf{E}_0^{\omega}$ suffering discontinuity at the NW interface, in the case considered it vanishes, and the SHG has only a dipole component given by Equation 26.22 and no quadrupole component.

c. $\mathbf{k} \perp \mathbf{z}$; $\mathbf{E}_0^{\omega} \perp \mathbf{z}$ (transverse propagation, transverse polarization)

$$E^{\omega} = E_x^{\omega} = \frac{2E_0^{\omega}}{\left[\varepsilon(\omega)+1\right]}(1+iky). \tag{26.23}$$

This geometry combines characteristic features of the two previous cases. As in case (a), the SHG contains both dipole and quadrupole components. The dipole component of the polarization has the same value as Equation 26.16 but a perpendicular, rather than a longitudinal, orientation. For this reason, its radiation has an anisotropic pattern and is affected by the image force (as in case (b)) resulting in the additional dependence of the SHG on $\varepsilon(2\omega)$:

$$I_v^{2\omega} = \frac{4\pi^3\omega^3 a^4\left[P_v^{2\omega}\right]^2}{c^2\left[\varepsilon(2\omega)+1\right]^2}\sin^2\phi = \frac{256\pi^3\gamma^2\omega^5 a^4\left[E_0^{\omega}\right]^4}{c^4\left[\varepsilon(\omega)+1\right]^4\left[\varepsilon(2\omega)+1\right]^2}\sin^2\phi. \tag{26.24}$$

The surface polarization component caused by the first term in Equations 26.15 and 26.23 is exactly the same as in the case (a) (it results from the fact that this component is determined exclusively by light polarization being independent of the value and the direction of **k**) and hence is described by Equation 26.19.

Let us summarize the results obtained thus far. The SHG was shown to consist of volume and surface components. They have, respectively, dipole and quadrupole symmetry and a different spatial distribution of emitted radiation at 2ω. It can be isotropic (Equation 26.17), bidirectional (Equations 26.22 and 26.24), or of a four-lobed shape (Equation 26.19). However, the integral radiation intensity, as in the case of spherical nanodots (Agarwal and Jha 1982), is given by qualitatively similar expressions differing by numerical coefficients and factors depending only on the NW dielectric constant. For this reason, SHG anisotropy is independent of the NW radius a (until the condition $a\omega/c \ll 1$ used in our calculations, remains valid). The explicit frequency dependence $I^{2\omega} \sim \omega^5$ is also the same in all formulae, and the possible spectral dependence of SHG anisotropy may occur only due to the frequency dispersion of the NW dielectric constant ε. The latter is of minor importance in semiconductors and dielectrics but may be very strong in metal NWs. That is why the characteristics of SHG anisotropy of these two classes of NW materials are very different and will be considered separately.

Semiconductor materials are characterized by high values of the dielectric constant (~10 or even more) with relatively weak frequency dependence. For this reason, in our estimates we do not distinguish between $\varepsilon(\omega)$ and $\varepsilon(2\omega)$ denoting both of them as ε. The ratio of the integral SHG for different NW orientations is independent not only of the NW material and the diameter but also of the light frequency ω, being a function of one single parameter ε. In the limit $\varepsilon \gg 1$, the ratio of the total SHG intensities $\overline{I_v^{2\omega}} + \overline{I_s^{2\omega}}$ (symbol $\bar{I}$ means averaging over ϕ) for all three cases considered is $36:\varepsilon^3:4$. It means that the SHG is maximal for the case (b) when the exciting light is polarized along the NW axis. The result is not unexpected since only in this geometry the optical electric field inside the NW is not weakened by NW polarization and is equal to the external field. It correlates with the linear optical phenomena (absorption, photoconductivity, photoluminescence) which are also maximal for this light polarization. Much less trivial is the dependence of the SHG in perpendicularly polarized light in the direction of the light wave vector. The SHG is essentially larger for light propagating along the NW since, for this geometry, the effective dipoles forming $\mathbf{P}_v^{2\omega}$ are oriented parallel to the NW and their emission is not weakened by NW polarization.

It is worth noting that in all three cases, the spatial distribution of the SHG has different characteristics. In case (a), the second harmonic is emitted in all directions perpendicular to the NW (the contribution of the quadrupole component is around 10%), while in case (b), the emission has a dipole and in case (c), a quadrupole symmetry. This fact should be taken into account while interpreting experimental results (see Section 26.2.4.2).

The main distinguishing feature of metal systems is the strong frequency dispersion of $\varepsilon(\omega)$, which, as in Section 26.2.2, will be approximated by the Drude formula. It is seen that, due to the factors $\varepsilon(\omega) + 1$ and $\varepsilon(2\omega) + 1$ in the denominators of Equations 26.17, 26.19, 26.22, and 26.24, the SHG is amplified dramatically near the frequencies $\omega_p/\sqrt{2}$ and $\omega_p/(2\sqrt{2})$ when the excitation frequency or its second harmonic coincides with the transverse plasmon frequency in a cylinder. In case (b), the resonance exists only for 2ω since the exciting light is polarized along the NW and does not interact with plasmons.

It is interesting to consider SHG anisotropy near these two resonance frequencies when the effect itself is anomalously large. As has been mentioned, at $\omega \cong \omega_p/\sqrt{2}$ the SHG increases dramatically for cases (a) and (c) remaining constant in case (b). In other words, for light with parallel polarization, the SHG is negligibly small compared to the case of perpendicular polarization (the situation opposite to semiconductor NWs). The surface quadrupole component (Equation 26.19) is in this case almost two orders of magnitude less than the volume dipole component. The formulae, Equations 26.17 and 26.24, describing the latter for two different geometries, differ by only 12%. This means that for perpendicular polarization, contrary to the semiconductor case, the total SHG intensity is practically independent of the direction of illumination, though in case (a), emission is isotropic and is polarized parallel to the NWs, while in case (c), it has a dipole symmetry and is polarized perpendicular to them.

At the plasmon resonance for emitted light, $\omega \cong \omega_p/(2\sqrt{2})$, all contributions to the SHG, except Equation 26.17, contain the diverging factor $[\varepsilon(2\omega) + 1]^2$, so that the SHG for all light directions and polarization increases at $\omega \to \omega_p/(2\sqrt{2})$ in a similar manner with the anisotropy remaining constant. Taking into account that $\varepsilon(\omega_p/(2\sqrt{2})) \cong -7$, it can be seen that in the vicinity of this low-frequency resonance, light with the parallel polarization (case (b)) causes a SHG three orders of magnitude larger than that with perpendicular polarization, qualitatively similar to the situation in semiconductor NWs.

26.2.4.2 Experiment

First experimental investigations of SHG in NWs (Barzda et al. 2008) were performed on ZnSe NWs with a length of 8–10 microns and a diameter of 80–100 nm, excited by a laser at a 1029 nm wavelength, that satisfies the quasi-static condition $\omega a/c \ll 1$. The angular dependence of the SHG efficiency $I_{SH}(\theta)$ measured by changing the angle θ between the sample axis and the excitation beam polarization is presented by experimental points at Figure 26.8. It is seen that this dependence has a very strong character with $I_{SH}(0)$ (parallel polarization) exceeding $I_{SH}(90°)$ (perpendicular polarization) by more than an order of magnitude.



FIGURE 26.8 Polarization dependence of the SHG intensity (Barzda et al. 2008). The dots represent experimentally measured values, the solid line corresponds to the theoretical formulae (Equations 26.25 and 26.26). (From Barzda, V. et al., *Appl. Phys. Lett.*, 92, 113111, 2008. With permission.)

An adequate quantitative interpretation must be based on the theoretical results of Section 26.2.4.1. In the experiment, the light wave vector **k** was always perpendicular to the NW, so that only conclusions for the cases (b) and (c) are relevant. It is claimed that the SHG caused by the optical field with a longitudinal polarization $E_\parallel$ can be written as the radiation of an effective dipole parallel to the light wave vector with the intensity distribution Equation 26.22 proportional to $\sin^2 \varphi$, while in the SHG caused by $E_\perp$, the dominating component has a quadrupole character (Equation 26.19) with the intensity proportional to $\sin^2(2\varphi)$. In the experiments, the detector collected radiation from a wide angle $-49° < \varphi < 49°$ (see Figure 26.9), so that Equations 26.19 and 26.22 should be integrated in these limits. This results in an additional form-factor equal to 0.36 for parallel and to 0.93 for perpendicular light polarization. By taking into account that $E_\parallel = E_0 \cos\theta$ and $E_\perp = 2E_0 \sin\theta/(\varepsilon + 1)$, we obtain the final result for the detected intensity of the SHG:



FIGURE 26.9 Schematic angular distribution of the SHG intensity for: (a) $\theta = 0$ (dipole mode) and (b) $\theta = 90°$ (quadrupole mode). **k** depicts the wave vector of the excitation light. The NW axis is perpendicular to the page. The orientation of the optical electric field $\mathbf{E}_0^\omega$ is perpendicular to the page in (a) and lies in the page plane in (b). The photodetector collects SHG radiation emitted in the forward direction within the shaded area. (From Barzda, V. et al., *Appl. Phys. Lett.*, 92, 113112, 2008. With permission.)

$$I_{SH} \propto E_0^4\left[\cos^4\theta + \frac{10.3(\varepsilon-1)^2\sin^4\theta}{(\varepsilon+1)^4(1+\sqrt{\varepsilon})^2}\right]. \qquad (26.25)$$

For semiconductor NWs with $\varepsilon \gg 1$, Equation 26.25 predicts giant angular oscillations of the SHG with the maximum/minimum ratio of the order $\varepsilon^3/10$. For ZnSe, the value of ε reported by different authors varies from 5.9 to 7.2 (Grigoriev and Meilikhov 1997) but even for the smallest of these numbers, the theoretical ratio exceeds the corresponding experimental value from Figure 26.8, which is close to 20. The most evident explanation is attributed to deviations from an ideal cylindrical NW geometry used in deriving Equations 26.19 and 26.22. Free-standing NWs are inevitably bent, so that the local value of θ changes along the NW. After replacing θ by $\theta + \delta\theta$ and averaging over small $\delta\theta$ with Gaussian properties, Equation 26.25 acquires an additional term

$$\delta I_{SH} \propto 3E_0^4\overline{(\delta\theta)^2}\sin^2\theta\left[2\cos^2\theta+\overline{(\delta\theta)^2}\sin^2\theta\right]. \qquad (26.26)$$

As a result, for $\overline{(\delta\theta)^2}\varepsilon^{3/2} > 2$ the maximum/minimum ratio becomes equal to $3\overline{(\delta\theta)^2}$, independent of the NW dielectric constant. The solid line in Figure 26.8 shows the theoretical angular dependence $I_{SH}(\theta)$ given by Equations 26.25 and 26.26 demonstrating a good agreement between theory and experiment. The best fitting of results was obtained for the value of the average NW corrugation $\overline{(\delta\theta)^2} \cong 0.2$.

26.2.5 Core–Shell Nanowires

26.2.5.1 Potential Distribution

So far, we have separately analyzed the optical properties of semiconductor and metal nanostructures and demonstrated their essential distinctions. In this connection, it is very interesting to investigate the properties of core–shell structures containing both types of layers, where luminescence in the semiconductor part can be amplified due to the plasmon effects in the metal part. Fabrication of such structures has been demonstrated experimentally (Lauhon et al. 2002, Choi et al. 2003).

As a starting point, we must find the formula for the intensity of the optical electric field inside such a structure, which would generalize Equation 26.1 to the case of an NW consisting of a central core with r_1 and a dielectric constant ε_1, and a shell with radius r_2 and a dielectric constant ε_2. Calculations show (Ruda and Shik 2005a) that an external electric field $\mathbf{E_0}$, perpendicular to the NW axis, creates in the core a uniform field

$$\mathbf{E_1} = \frac{4\varepsilon_0\varepsilon_2\mathbf{E_0}}{2\varepsilon_2(\varepsilon_1+\varepsilon_0)+p(\varepsilon_2-\varepsilon_1)(\varepsilon_2-\varepsilon_0)} \equiv A\mathbf{E_0} \qquad (26.27)$$

where $p = 1-(r_1/r_2)^2$ is the relative shell volume. The field in the shell is a sum of a uniform field and that of a linear dipole:

$$\mathbf{E_2} = \frac{2\varepsilon_0}{2\varepsilon_2(\varepsilon_1+\varepsilon_0)+p(\varepsilon_2-\varepsilon_1)(\varepsilon_2-\varepsilon_0)} \times\left\{(\varepsilon_1+\varepsilon_2)\mathbf{E_0}+2(\varepsilon_1-\varepsilon_2)(1-p)r_1^2\left[\frac{\mathbf{E_0}}{r^2}-\frac{2\mathbf{r}(\mathbf{r}\mathbf{E_0})}{r^4}\right]\right\}. \qquad (26.28)$$

For $\mathbf{E_0}$ parallel to the NW axis, $\mathbf{E_1} = \mathbf{E_2} = \mathbf{E_0}$. Formulae (Equations 26.27 and 26.28) can be used to determine the spectra and the polarization dependence of optical absorption in core–shell NWs. We restrict our analysis to the already mentioned case of a metal shell and a semiconductor core, promising luminescence amplification.

The specific features of the optical response of metal shells arise from the fact that the plasmon-related absorption maximum for the light with perpendicular polarization is split into two maxima with positions depending on the relationship between r_1 and r_2. The frequency regions near the plasmon resonances are characterized by an anomalously high electric field strength (light amplification) both in the core and in the shell. As it has been already pointed out for core–shell nanodots (Neeves and Birnboim 1989), this can be used for the enhancement of optical effects in a core (in NWs—only for light with perpendicular polarization). There is also a reciprocal effect: an oscillating dipole $\mathbf{d_0}$ in the core is created far from the wire radiation field that may be considerably larger than that in a uniform medium. This effect of light amplification will be considered later in Section 26.2.5.3. In the next section, we investigate the optical absorption near the plasmon resonances caused by the increased electric field $\mathbf{E_2}$ in the shell.

26.2.5.2 Spectra and Polarization Dependence of Absorption

To calculate the optical absorption in a core–shell NW caused by light with a perpendicular polarization, we must integrate the local absorption Im $\varepsilon_2|\mathbf{E_2}(\mathbf{r})|^2$ over the whole shell. Using the Drude formula for ε_2 and Equation 26.28 for $\mathbf{E_2}(\mathbf{r})$, we obtain the absorption spectra shown by solid lines in Figure 26.10. These contain two maxima corresponding to plasmon resonances where the real part of the denominator in Equations 26.27 and 26.28 vanishes and the electric field in the NW becomes anomalously large. With an increasing p, the maxima approach each other and the low-frequency one diminishes so that at $p \to 1$ we get a single peak at $\omega = \omega_p/\sqrt{2}$ corresponding to the plasma resonance in a metal cylinder.

Similar phenomena in core–shell nanodots have been already observed experimentally (Zhou et al. 1994, Oldenburg et al. 1998) and have a good theoretical description (Neeves and Birnboim 1989, Ruda and Shik 2005b). It is important to emphasize that, contrary to nanodots, the described two-peak absorption spectra in NWs are observed only for light polarized perpendicularly to the NWs. For parallel polarization, when the electric field in the NWs is equal to the external one, we have simple monotonically decreasing spectra reflecting the low-frequency absorption given by Im ε_2.



FIGURE 26.10 Absorption spectra of NW with a metal shell for $p = 0.2$ (a), 0.5 (b), 0.8 (c) and $\nu = 0.1\omega_p$ and a semiconductor core with $\varepsilon_1 = 3$ (curves 1) and $\varepsilon_1 = 10$ (curves 2) for light polarized perpendicularly to NWs. Solid curves correspond to the absorption in a metal shell, dashed curves—in a semiconductor core. (From Ruda, H.E. and Shik, A., *Phys. Rev. B*, 72, 115308, 2005a. With permission.)

If the core is a semiconductor with the bandgap $E_g < \hbar\omega$ then, besides the absorption described above, there is also interband absorption in the core proportional to $|\mathbf{E}_1(\mathbf{r})|^2$. The spectrum of this absorption can be easily calculated from Equation 26.27 and is shown by dashed lines in Figure 26.10. The spectrum also has a double maximum structure qualitatively similar to a metal shell one, but contrary to that, suffers a dramatic drop with an increasing ε_1 due to the extrusion of the electric field from the high-ε core. We emphasize that absorptions in a shell and a core depend on different parameters (i.e., the plasma frequency and the scattering rate in metals, and the bandgap width and the interband matrix element in semiconductors) and thus we can not compare the amplitudes of solid and dashed curves and say *a priori* what type of absorption is dominating. Moreover, it is also difficult to distinguish experimentally these two absorption components since the absorption spectra in a shell and a core have qualitatively similar characteristics. The problem can be solved by measuring the excitation spectrum for core luminescence, which is proportional only to the partial absorption in the core shown by the dashed lines in the figure.

As mentioned above, the dashed lines in Figure 26.10 actually show the spectral dependence of the electric field in a core $|\mathbf{E}_1(\mathbf{r})|^2$. As we have shown in Section 26.2.1, the semiconductor and the metal NWs have opposite characteristics of electrical anisotropy: the perpendicular component of the electric field is suppressed as compared with the parallel one, in a semiconductor NW, and enhanced in a metal NW in the vicinity of a plasmon frequency. In composite core–shell structures, both cases can be realized, depending on the shell thickness and the light frequency. The corresponding "phase diagram" using p-ω axes, is shown in Figure 26.11. The areas above the line(s) correspond to the "metal" case $E_\perp > E_{0\perp}$ while those below the line(s)—to the "semiconductor" case $E_\perp < E_{0\perp}$. In other words, these lines correspond to $|A| = 1$ where the amplification factor $A \equiv E_\perp/E_{0\perp}$ is given by Equation 26.27. At a small p, we naturally deal with the "semiconductor" regime. One might be surprised that at $p \to 1$, the regime is not "metal" but should be pointed so that the figure describes the field not in a metal shell, but in a semiconductor core, which in the limit of a pure metal nanowire $p \to 1$ simply disappears.

The condition $|A| > 1$ is satisfied in the vicinity of plasmon resonances, which means that for light-inducing interband absorption in the core, the intensity of the electron-hole pair generation, and hence, the intensity of the luminescence caused by these pairs is larger than in the absence of a metal shell. That is why, for A, we use the term "amplification factor."



FIGURE 26.11 Values of p and ω, for which $E_\perp = E_{0\perp}$ at $\varepsilon_1 = 3$ (solid line) and $\varepsilon_1 = 10$ (dashed lines). The area above the line(s) corresponds to $E_\perp > E_{0\perp}$. (From Ruda, H.E. and Shik, A., *Phys. Rev. B*, 72, 115308, 2005a. With permission.)

26.2.5.3 Luminescence Amplification

Metal shells may cause amplification not only of the ac electric field of exciting light but also of the light emitted by a semiconductor core. The ac electric field emitted by a core, which can be considered as an effective dipole $\mathbf{d}_0$, is disturbed by a metal shell so that the field far from the nanostructure looks like one created by some other effective dipole $\mathbf{d}$. By analogy with the previous section, we may expect that in the vicinity of a plasmon resonance, the condition $|d/d_0| \gg 1$ can be realized, which means an effective amplification of the emitted radiation as well.

Calculations show that the luminescence of core–shell structures is characterized by exactly the same rules as absorption. The field of dipoles parallel to the NW axis is not disturbed by image forces, while the field of perpendicular dipoles acquires the same amplification factor A as given by Equation 26.27. As a result, for an isotropic distribution of effective dipoles, such as in a cubic semiconductor core in the absence of size quantization, the emission from an NW acquires a partial polarization parallel to its axis at $|A| < 1$ (as in Section 26.2.3) or perpendicular at $|A| > 1$. Since A has a strong frequency dependence, the components of the emitted light with a different polarization may have different spectra depending on the metal shell parameters.

From the applied point of view, the most important conclusion is as follows: by a proper choice of the metal-shell parameters, we can make one of the plasmon peaks coincide with the luminescence line in the core, which will result in an increase in the luminescence intensity (Ruda and Shik 2005b). It would be even more attractive to enhance the photoluminescence dramatically by a simultaneous amplification of both the exciting and the emitting light. Such a situation often occurs in surface-enhanced Raman scattering (Moskovits 1985) but in luminescence, its realization is more difficult since the difference in frequencies of exciting ω_{ex} and emitted ω_{em} light is usually quite large and cannot be covered by a single plasmon peak. However, in core–shell structures, such double amplification can be reached by using both plasmon peaks as shown in Figure 26.10. In this case, the shell parameters should be chosen in such a way that the low-frequency peak corresponds to ω_{em} in a given NW core while the source of excitation is tuned for ω_{ex} to coincide with the second high-frequency peak (Ruda and Shik 2005a).

26.3 Arrays of Nanorods

26.3.1 Polarization Memory in Random Nanorod Arrays

26.3.1.1 Theory

The whole sections 26.2 was devoted to the optical properties of individual NWs or NRs and now we will discuss similar effects in NW arrays. All the polarization-dependent effects remain the same in such arrays as a system of parallel NWs (say, in porous dielectric matrices) with a relatively large distance between the NWs, but in the case of randomly oriented semiconductor NWs or NRs (say, in a polymer matrix or solution), the situation changes. Such a system has macroscopically isotropic optical properties but simultaneously possesses a very interesting property of polarization memory (Lavallard and Suris 1995, Ruda and Shik 2005a). If we excite photoluminescence in the system using polarized light, in accordance with Section 26.2.1, nonequilibrium carriers will be generated mostly in the NWs that are oriented close to and parallel to the light polarization. According to Section 26.2.3, light emitted by these NWs will have a preferable polarization parallel to their axes, or in other words, parallel to the polarization of the exciting radiation. In other words, an anisotropic random array of nanostructures "remembers" the polarization of the exciting radiation and emits luminescence in the same direction of polarization.

To calculate this effect in a random system of thin NWs, we assume that the NW array occupies the semi-space $x < 0$ and study the polarization of the net luminescence excited by z-polarized light and measured at some point $(x_0, 0, 0)$ outside the array (that is, $x_0 > 0$). The principle of calculation is as follows. We take some NWs with an orientation characterized by the spherical angles (θ, α) and consider it as a line of emitting dipoles with components d_0 along the NW axis and $2d_0\varepsilon_0/(\varepsilon + \varepsilon_0)$ in two other directions. Then, as in Section 26.2.3.1, we find the components $(S_x)_\parallel$ and $(S_x)_\perp$ of the Poynting vector created by these dipoles at the point $(x_0, 0, 0)$. Since, according to Equation 26.3, the intensity of the absorbed exciting light and hence the intensity of the luminescence depends on θ being proportional to $(\varepsilon + \varepsilon_0)^2\cos^2\theta + 4\varepsilon_0\sin^2\theta$, we integrate $(S_x)_\parallel$ and $(S_x)_\perp$ over θ and α with this weighting factor obtaining the total intensities $I_{\parallel,\perp}$ of light emission with polarizations parallel and perpendicular to the polarization of the exciting light.

Referring the reader to Ruda and Shik (2005a) for the details of calculations, we present only the final result:

$$\frac{I_{\parallel}}{I_{\perp}} = \frac{9[(\varepsilon+\varepsilon_0)^2+2\varepsilon_0^2](\varepsilon+\varepsilon_0)^2+20[(\varepsilon+\varepsilon_0)^2+2\varepsilon_0^2]+21(\varepsilon+\varepsilon_0)^2+336\varepsilon_0^2}{3[(\varepsilon+\varepsilon_0)^2+2\varepsilon_0^2](\varepsilon+\varepsilon_0)^2+44[(\varepsilon+\varepsilon_0)^2+2\varepsilon_0^2]+63(\varepsilon+\varepsilon_0)^2+168\varepsilon_0^2}. \qquad (26.29)$$

Equation 26.29 shows that maximal possible polarization, reached at $|\varepsilon/\varepsilon_0| \gg 1$, is equal to $I_{\parallel}/I_{\perp} = 3$. In terms of the polarization ratio $P = (I_{\parallel} - I_{\perp})/(I_{\parallel} + I_{\perp})$ it corresponds to $P = 0.5$. Figure 26.12 shows this polarization ratio for an arbitrary relationship between ε and ε_0. For InP NWs in air ($\varepsilon/\varepsilon_0 = 12.7$), we get $P = 0.44$. It is worth noting that at $\varepsilon < \varepsilon_0$ (e.g., in metal NWs near the plasmon resonance), when the electric field in the NWs has a preferably perpendicular orientation, the system also has a polarization memory. This effect is weaker than at a large ε, with the maximal $P = 6/68 = 0.088$.

As we have shown in Sections 26.2.1.2 and 26.2.3.2, for thick NWs, the polarization characteristics for absorption and emission vary dramatically with the light frequency. As a result, the polarization memory in these objects must demonstrate a strong dependence on the frequency of both the exciting (ω_{ex}) and the emitted (ω_{em}) light and even change its sign at some intervals of ω_{ex} and ω_{em}. The quantitative description of this effect (Ruda and Shik 2006) is based on the same approach as that for thin NWs resulting in Equation 26.29 but with two distinctions. First, the values of the longitudinal and the transverse components of the effective dipole moments in the NW are no longer constant but given by Equations 26.12 and 26.13 with $k = \omega_{em}/c$. Second, the intensity of the absorbed exciting light and hence the intensity of the luminescence (the weighting factor in the angular averaging) is now equal to $I_{\parallel}^{a}(\omega_{ex})\cos^2\theta + I_{\perp}^{a}(\omega_{ex})\sin^2\theta$ where the intensities of the absorbed light $I_{\parallel}^{a}$ and $I_{\perp}^{a}$ are determined from Equations 26.5 and 26.6 according to the procedure described in Section 26.2.1.2. The final answer for the ratio of luminescence intensities with polarization parallel and perpendicular to that of the exciting light is

$$\frac{I_{\parallel}^{e}}{I_{\perp}^{e}} = \frac{2I_{\perp}^{a}(\omega_{ex})[47d_x^2(\omega_{em})+10d_z^2(\omega_{em})]+3I_{\parallel}^{a}(\omega_{ex})[13d_x^2(\omega_{em})+12d_z^2(\omega_{em})]}{4I_{\perp}^{a}(\omega_{ex})[16d_x^2(\omega_{em})+11d_z^2(\omega_{em})]+3I_{\parallel}^{a}(\omega_{ex})[23d_x^2(\omega_{em})+4d_z^2(\omega_{em})]}. \qquad (26.30)$$



FIGURE 26.12 Luminescence polarization ratio in a random system of nanowires exited by polarized light. The dot-and-dash line corresponds to the limiting value $P = 0.5$. (From Ruda, H.E. and Shik, A., *Phys. Rev. B*, 72, 115308, 2005a. With permission.)

To clarify, we emphasize the difference in notations between Equations 26.29, 26.30 and 26.10 where $I_{\parallel}^{e}$ and $I_{\perp}^{e}$ referred to the light polarized parallel and perpendicular to the NW axis. Figure 26.13 shows the dependences of the system polarization ratio $P^e = (I_{\parallel}^{e} - I_{\perp}^{e})/(I_{\parallel}^{e} + I_{\perp}^{e})$ on the frequencies of the exciting



FIGURE 26.13 Polarization ratio of photoluminescence for a random NW system with $\varepsilon = 9$, $\varepsilon_0 = 1$. (a) Luminescence spectra $P^e(\omega_{em}a/c)$ for different ω_{ex}. Numbers at the curves indicate the values ω_{ex}/c. The curves corresponding to $\omega_{ex}a/c = 2.6$ and 2.8 practically coincide. (b) Excitation spectra $P^a(\omega_{ex}a/c)$ for different ω_{ems}. Numbers at the curves indicate the values of $\omega_{em}a/c$. The curves corresponding to $\omega_{em}a/c = 1.8$ and 2.8 practically coincide. For $\omega_{em}a/c = 2.6$ polarization is very close to zero and is not presented in the figure.

and the emitted light, given by Equation 26.30. Since in standard photoluminescence measurements ω_{ex} always exceeds ω_{em}, parts of the curves in Figure 26.13 where this condition is violated are given by dashed lines. At ω_{ex}, $\omega_{em} \to 0$, polarization tends to its low-frequency limit shown in Figure 26.12 and for our choice $\varepsilon/\varepsilon_0 = 9$ equal to $P^e \cong 0.40$.

It is important to mention that if the NW material is characterized by several luminescence lines with essentially different frequencies, then these lines may have different degrees of polarization, in accordance with Figure 26.6. Since the curve at the figure crosses the level $I^e_{\parallel} = I^e_{\perp}$, there exists even the possibility when one of the luminescent lines may have. The latter case could be called "polarization anti-memory."

26.3.1.2 Experiment

The effect of polarization memory was first observed in porous Si (Kovalev et al. 1995) that has only a distant resemblance to a system of NWs or NRs. Hence, for demonstration of its main experimental features, we have chosen subsequently more detailed measurements in CdSe/ZnS NRs (Kravtsova et al. 2007) with the aspect ratio $l/2a \cong 2.4$ dissolved in a liquid and hence having a randomly distributed orientation. Figure 26.14 shows the luminescence spectrum consisting of two peaks corresponding to interband transitions between different size-quantized states. Polarization properties of the emitted light are presented in the form of luminescence spectra for different angular positions of the analyzer related to the direction of the exciting light polarization $\mathbf{E}_0$. The luminescence is seen to be polarized mostly parallel to $\mathbf{E}_0$, in qualitative agreement with theoretical predictions.



FIGURE 26.14 Photoluminescence spectrum of the NR solution for excitation by linearly polarized light with $\lambda = 366$ nm. Different curves correspond to the luminescence components with a polarization in the direction forming the angle θ with the polarization of excitation. θ increases from the upper to the lower curve with the step 10°. The amplitude of the luminescence in the spectral region $\lambda < 520$ nm is shown with the magnification factor 10. (From Kravtsova, Y. et al., *Appl. Phys. Lett.*, 90, 083120, 2007. With permission.)

The quantitative treatment of the results meets with some difficulties. According to Equation 26.29, the amplitude of polarization memory in small nanostructures has some universal value depending only on $\varepsilon/\varepsilon_0$. However, in the experiment, this amplitude differs noticeably for two different spectral lines in the same NRs. Besides, for the short wavelength peak, the amplitude of polarization memory exceeded the theoretically predicted one, while for the long wavelength peak, it was always less. These results could be explained if the matrix element responsible for the ground state 573 nm-long wavelength peak is larger for perpendicular light polarization (it is really the case for NRs with a small aspect ratio (Hu et al. 2001)) while that at 470 nm is either more isotropic or larger for parallel polarization. This is in agreement with the theoretical (Li and Wang 2003) and the experimental (Thomas et al. 2005) conclusions of essentially different polarization properties of different optical transitions in NRs.

26.3.2 Plasmon Spectra in Self-Assembled Nanorod Structures

26.3.2.1 Self-Assembling of Metal Nanorods

In the recent years, an impressive success has been achieved in fabricating various arrays of metal NRs by their self-assembling in solution. The most comprehensive results in this direction were obtained by using Au NRs with the lateral surface covered by a double layer of hydrophilic molecules and the ends terminated with polystyrene molecular chains (Nie et al. 2007, 2008). Such building blocks in solution can form different ordered arrays, such as chains, bundles, raft-like structures, rings, etc. (Figure 26.15), depending on the chemical composition of the solvent. In these systems, the distances between the NRs are very small, compared to their diameter, so that the electric fields of plasmons in neighboring NRs overlap and the plasmon spectrum of the system becomes different from that of individual NRs and depends on the NR array topology. Figure 26.16 shows the plasmon absorption spectra in some of these structures formed from identical NRs. They consist of two peaks (longitudinal and transverse plasmons) where the long wavelength one, corresponding to longitudinal plasmons (see Section 26.2.2.1), demonstrates a strong dependence on the array geometry.

Some general qualitative regularities were already formulated in literature and found their experimental confirmation in systems of NRs and nanodots. It was demonstrated (Rechenberger et al. 2003, Su et al. 2003) that by reducing the inter-nanoparticle separation in the direction of light polarization, a red shift in the plasmon resonance occurs, in contrast with a blue shift for the perpendicular direction of polarization. It has a simple qualitative explanation. The end-to-end alignment of NRs increases the effective length of an NR, which results in a decrease of the longitudinal depolarization factor $n_{\parallel}$ and, according to Equation 26.7, a decrease in the longitudinal plasmon frequency $\omega_{\parallel}$, while the side-to-side arrangement increases the effective $n_{\parallel}$ and $\omega_{\parallel}$.



FIGURE 26.15 NR arrays obtained by self-assembling in different solvents. (From Fava, D. et al., *Adv. Mater.*, 20, 4318, 2008. With permission.)



FIGURE 26.16 Optical absorption spectra for various NR arrays. (From Nie, Z.H. et al., *J. Am. Chem. Soc.*, 130, 3683, 2008. With permission.)

In the next sections, we present theoretical models allowing one to make some quantitative calculations of plasmon characteristics and their comparison with the experiment.

26.3.2.2 Longitudinal Plasmon Shift

Let us consider some arbitrary system of metal NWs or strongly anisotropic NRs (further we will mention them simply as NWs) and find the polarization of each NW in an external uniform electric field $\mathbf{E}_0$. We assume that the NW radius a is many times smaller than both their length l, so that for calculations of longitudinal plasmons, the radial distribution of the induced charges is inessential and we may characterize each NW by a linear charge density $q(z)$ depending on one single coordinate z measured along the NW axis. In the absence of a direct electrical contact between the NWs, their total charges remain zero: $\int_{-l/2}^{l/2} q(z)\,dz = 0$. For each metal NW, the charge distribution $q(z)$ is found from the condition of equipotentiality (Ruda and Shik 2007b). It means that the external field potential $-E_{0z}z$ is exactly compensated by the joint potential created by the charges of all NWs including the given one. To describe the potential created by $q(z)$ of the same NW in a medium with the dielectric constant ε, we use the approximate expression $2q(z)\ln(l/a)/\varepsilon$ valid for $l \gg a$ (Averkiev and Shik 1996). Potentials of all other NWs can be obtained by a simple Coulomb expression neglecting the finite thickness of NWs.

We demonstrate the described procedure for the case of two in-line NWs separated by the interval b and occupying the segments $(-l - b/2, -b/2)$ and $(b/2, l + b/2)$ of the z-axis. Noting the charge densities in the NWs as $q_-(z)$ and $q_+(z)$, respectively, we obtain the system of two equations:

$$\frac{2q_\pm(z)}{\varepsilon}\ln\left(\frac{l}{a}\right) - E_{0z}z + \int_{\mp b/2}^{\mp b/2 \mp l} \frac{q_\mp(z')}{\varepsilon(z'-z)}\,dz' = C_\pm. \quad (26.31)$$

Instead of $q_\pm$, we introduce two dimensionless functions $\eta_\pm(\xi)$ determined from

$$q_\pm(z) = \frac{\varepsilon E_{0z}}{2\ln(l/a)}\left[z + l\eta_\pm(\xi)\right] \tag{26.32}$$

where ξ is the dimensionless coordinate measured from the center of the corresponding NWs: $\xi = [z \mp (b/2 + l/2)]/l$. It can be easily shown that $\eta_-(-\xi) = -\eta_+(\xi)$. Finding $C_\pm$ from the neutrality conditions: $\int_{-1/2}^{1/2} \eta_\pm(\xi)\,\mathrm{d}\xi = 0$, we reduce Equation 26.31 to one single equation for $\eta_+(\xi)$:

$$\begin{aligned} &2\ln\left(\frac{l}{a}\right)\eta_+(\xi) - \int_{-1/2}^{1/2} \frac{\eta_+(\xi')d\xi'}{\xi+\xi'+1+\beta} + \int_{-1/2}^{1/2} \eta_+(\xi')\ln\left(\frac{2\xi'+3+2\beta}{2\xi'+1+2\beta}\right)\mathrm{d}\xi' \\ &\quad = \frac{1}{2} + \ln\left(\frac{2+\beta}{1+\beta}\right) - (\xi+1+\beta)\ln\left(\frac{2\xi+3+2\beta}{2\xi+1+2\beta}\right) \\ &\quad + \frac{\beta}{2}\ln\left[\frac{\beta(2+\beta)^3}{(1+\beta)^4}\right] + \frac{\beta^2}{2}\ln\left[\frac{\beta(2+\beta)}{(1+\beta)^2}\right]. \end{aligned} \tag{26.33}$$

This equation was solved numerically for $l/a = 10$, which corresponds to the experimental results (Nie et al. 2007) to be discussed later. After $q(z)$ is found, the total dipole moment P of an NW is easily found: $P = \int zq(z)\mathrm{d}z$, which, in turn, determines the depolarization factor $n_\| = E_{0z}V/(4\pi P)$ (V is the NR volume) (Landau and Lifshitz 1984), connected with the longitudinal plasmon frequency $\omega_\|$ by Equation 26.7.

Using a similar approach, the frequency $\omega_\|$ was found (Ruda and Shik 2007b) for two other systems: the infinite periodic NR chain and a pair of two side-by-side NRs with the distance $d > 2a$ between the axes. The resulting dependences of the longitudinal plasmon frequency $\omega_\|$ on inter-NR distances b or d for all three cases are presented in Figure 26.17. It is seen that, in accordance with the above-mentioned qualitative considerations, $\omega_\|$ demonstrates a red shift for chains and a blue shift for bunches of NRs. Figure 26.17 also contains experimental points (Nie et al. 2007) partially taken from the curves of Figure 26.16. It is seen that the results for in-line structures (curves 1 and 2) demonstrate a good qualitative agreement but the experimental dependences are steeper than the theoretical. This effect can be caused by the fact that the polystyrene molecules connecting the NR tips are also polarized in the external electric field, so that the effective local dielectric constant of this gap exceeds that of the solvent. This distorts the electric field pattern and increases the intensity of inter-NR interaction and hence, the value of P, as compared to the ideal case considered above. For the side-by-side NR assemblies, practically all the lines of the electric field responsible for the inter-NR interaction are concentrated in the region filled by hydrophilic molecules, so that the dielectric inhomogeneity of the system is irrelevant, and curve 3 demonstrates not only qualitative but also quantitative agreement.



FIGURE 26.17 Dependence of the longitudinal plasmon frequency $\omega_\|$ (in units of $\omega_\|$ for individual NRs) on the distance between NRs with $l/a = 10$. 1, two in-line NRs (experimental points—triangles); 2, chain of NRs (experimental points—squares); 3, two parallel NRs (experimental points—stars).

26.4 Conclusion

We have described a large variety of polarization-sensitive optical phenomena in anisotropic nanostructures, such as NWs and NRs. The phenomena have a universal character being exclusively due to the difference in the dielectric constants between nanostructures and their environment. They include a strong dependence of linear (absorption, photoluminescence, photoconductivity, etc.) and nonlinear optical properties on polarization of the exciting light, as well as a high degree of polarization of luminescence emitted by these systems. The joint action of absorption and emission anisotropy results in a polarization memory in random arrays of NWs and NRs. In metal nanostructures, all the mentioned phenomena exhibit a dramatic dependence (including sometimes the change of sign) on the light frequency, related to plasmon effects. In composed metal-semiconductor nanostructures, these effects can be used for luminescence amplification. In ordered self-assembled arrays of metal NRs, the plasmon-related optical spectra are sensitive to the array geometry. All the described effects are provided with proper theoretical description and illustrated by experimental observations performed in recent years.

Acknowledgments

The authors would like to thank their collaborators, V. Barzda, R. Cisek, D. Fava, E. Kumacheva, Y. Kravtsova, U. Krull, L. Levina, S.F. Musikhin, Z.H. Nee, U. Philipose, and T.L. Spencer from the University of Toronto, whose experimental results are presented in this work.

References

Agarwal, G.S. and Jha, S.S. 1982. Theory of second harmonic generation at a metal surface with surface plasmon excitation. *Solid State Communications* 41: 499–501.

Averkiev, N.S. and Shik, A. 1996. Contact phenomena in quantum wires and porous silicon. *Semiconductors* 30: 112–116.

Barzda, V., Cisek, R., Spencer, T.L., Philipose, U., Ruda, H.E., and Shik, A. 2008. Giant anisotropy of second harmonic generation for a single ZnSe nanowire. *Applied Physics Letters* 92: 113111.

Batygin, V.V. and Toptygin, I.N. 1978. *Problems in Electrodynamics*. New York: Academic Press.

Blombergen, N., Chang, R.K., Jha, S.S., and Lee, C.H. 1968. Optical second-harmonic generation in reflection from media with inversion symmetry. *Physical Review* 174: 813–822.

Chew, W.C. 1990. *Waves and Fields in Inhomogeneous Media*. New York: Van Nostrand Reinhold.

Choi, H.-J., Johnson, J.C., He, R. et al. 2003. Self-organized GaN quantum wire UV lasers. *Journal of Physical Chemistry B* 107: 8721–8725.

Duan, X. and Lieber, C.M. 2000, General synthesis of compound semiconductor nanowires. *Advanced Materials* 12: 298–302.

Fan, Z., Chang, P., Lu, J.G. et al. 2004. Photoluminescence and polarized photodetection of single ZnO nanowires. *Applied Physics Letters* 85: 6128–6130.

Fava, D., Nie, Z.H., Winnik, M.A., and Kumacheva, E. 2008. Evolution of self-assembled structures of polymer-terminated gold nanorods in selective solvents. *Advanced Materials* 20: 4318–4322.

Grigoriev, I.S. and Meilikhov, E.Z. 1997. *Handbook of Physical Quantities*. Boca Raton, FL: CRC Press.

Han, S., Jin, W., Zhang, D. et al. 2004. Photoconduction studies on GaN nanowire transistors under UV and polarized UV illumination. *Chemical Physics Letters* 389: 176–180.

Hsu, N.E., Hung, W.K., and Chen, Y.F. 2004. Origin of defect emission identified by polarized luminescence from aligned ZnO nanorods. *Journal of Applied Physics* 96: 4671–4673.

Hu, J., Li, L., Yang, W., Manna, L., Wang, L., and Alivisatos, A.P. 2001. Linearly polarized emission from colloidal semiconductor quantum rods. *Science* 292: 2060–2063.

Kovalev, D., Ben Chorin, M., Diener, J. et al. 1995. Porous Si anisotropy from luminescence polarization. *Applied Physics Letters* 67: 1585–1587.

Kravtsova, Y., Krull, U., Musikhin, S.F., Levina, L., Ruda, H.E., and Shik, A. 2007. Polarization memory in a system of CdSe nanorods. *Applied Physics Letters* 90: 083120.

Kreibig, U. and Vollmer, M. 1995. *Optical Properties of Metal Clusters*. Berlin, Germany: Springer.

Landau, L.D. and Lifshitz, E.M. 1984. *Electrodynamics of Continuous Media*. New York: Pergamon Press.

Lauhon, L.J., Gudiksen, M.S., Wang, D., and Lieber, C.M. 2002. Epitaxial core-shell and core-multishell nanowire heterostructures. *Nature* 420: 57–61.

Lavallard, P. and Suris, R.A. 1995. Polarized photoluminescence of an assembly of non cubic microcrystals in a dielectric matrix. *Solid State Communications* 95: 267–269.

Li, J. and Wang, L. 2003. High energy excitations in CdSe quantum rods. *Nano Let*ters 3: 101–105.

McIntyre, C.R. and Sham, L.J. 1992. Theory of luminescence polarization anisotropy in quantum wires. *Physical Review B* 45: 9443–9446.

Mei, X., Blumin, M., Sun, M. et al. 2003. Highly-ordered GaAs/AlGaAs quantum dot arrays on GaAs(100) substrate grown by molecular beam epitaxy using nanochannels alumina masks. *Applied Physics Letters* 82: 967–969.

Moskovits, M. 1985. Surface-enhanced spectroscopy. *Reviews of Modern Physics* 57: 783–826.

Neeves, A.E. and Birnboim, M.H. 1989. Composite structures for the enhancement of nonlinear optical susceptibility. *Journal of the Optical Society of America B* 6: 787–796.

Nie, Z.H., Fava, D., Kumacheva, E. et al. 2007. Self-assembly of metal-polymer analogues of amphiphilic triblock copolymers. *Nature Materials* 6: 609–614.

Nie, Z.H., Fava, D., Rubinstein, M., and Kumacheva, E. 2008. Supramolecular assembly of gold nanorods end-terminated with polymer "pom-poms". *Journal of the American Chemical Society* 130: 3683–3689.

Oldenburg, S.J., Averitt, R.D., Westcott, S.L., and Halas, N.J. 1998. Nanoengineering of optical resonances. *Chemical Physics Letters* 288: 243–247.

Peng, X., Manna, L., Yang, W. et al. 2000. Shape control of CdSe nanocrystals. *Nature* 404: 59–61.

Philipose, U., Ruda, H.E., Shik, A., de Souza, C.F., and Sun, P. 2005. Light emission from ZnSe nanowires. *Proceedings of SPIE* 5971: 597116–597128.

Qi, J., Belcher, A.M., and White, J.M. 2003. Spectroscopy of individual silicon nanowires. *Applied Physics Letters* 82: 2616–2618.

Rechenberger, W., Hohenau, A., Leitner, A. et al. 2003. Optical properties of two interacting gold nanoparticles. *Optics Communications* 220: 137–141.

Ruda, H.E. and Shik, A. 2005a. Polarization-sensitive optical phenomena in semiconducting and metallic nanowires. *Physical Review B* 72: 115308.

Ruda, H.E. and Shik, A. 2005b. Plasmon phenomena and luminescence amplification in nanocomposite structures. *Physical Review B* 71: 245328.

Ruda, H.E. and Shik, A. 2006. Polarization-sensitive optical phenomena in thick semi-conducting nanowires. *Journal of Applied Physics* 100: 024314.

Ruda, H.E. and Shik, A. 2007a. Nonlinear optical phenomena in nanowires. *Journal of Applied Physics* 101: 034312.

Ruda, H.E. and Shik, A. 2007b. Polarization and plasmon effects in nanowire arrays. *Applied Physics Letters* 90: 223106.

Sercel, P.C. and Vahala, K.J. 1990. Analytical technique for determining the polarization dependence of optical matrix elements in quantum wires with band-coupling effects. *Applied Physics Letters* 57: 545–547.

Su, K.-H., Wei, Q.-H., Zhang, X. et al. 2003. Interparticle coupling effects on plasmon resonances in nanogold particles. *Nano Letters* 3: 1087–1090.

Thomas, N.L., Herz, E., Schöps, O., Woggon, U., and Artemyev, M.V. 2005. Exciton fine structure in single CdSe nanorods. *Physical Review Letters* 94: 016803.

Wang, J., Gudiksen, M.S., Duan, X., Cui, Y., and Lieber, C.M. 2001. Highly polarized luminescence and photodetection from single InP nanowires. *Science* 293: 1455–1457.

Zhou, H.S., Honma, I., Komiyama, H., and Haus, J.W. 1994. Controlled synthesis and quantum-size effect in gold-coated nanoparticles. *Physical Review B* 50: 12052–12056.

27

Nonlinear Optics with Clusters

Sabyasachi Sen
JIS College of Engineering

Swapan Chakrabarti
University of Calcutta

27.1 General Introduction: Fundamentals of Nonlinear Optics and Different Nonlinear Optical Effects **27**-1
27.2 Quantum Formulation of Nonlinear Optics **27**-2
27.3 Nonlinear Optics with Materials **27**-5
27.4 Why Are Clusters So Important? **27**-5
27.5 Review of Nonlinear Optics with Clusters **27**-5
27.6 Conclusions **27**-12
References **27**-12

27.1 General Introduction: Fundamentals of Nonlinear Optics and Different Nonlinear Optical Effects

In recent years, nonlinear optical (NLO) materials have attracted substantial research interests due to their potential applications in information processing and telecommunications [1–4]. NLO processes are particularly useful in photonic devices where photons are used to transmit and process information. Modification in the optical properties of a material by the strong oscillating electric field of a laser beam is in general discussed in the study of NLO. NLO processes have been observed in a wide variety of materials starting from molecules and clusters to bulk materials [5–14]. In molecular systems, the optical nonlinearity depends on the geometrical arrangement of molecules, whereas in case of bulk systems, the electronic characteristics of the system determine the optical nonlinearity. Various experimental as well as theoretical results have reported that NLO properties of small atomic clusters depend on the geometry and the electronic structure property of these materials [15,16].

In general, the electric dipole moment μ_a of a molecular system is expressed as

$$\begin{aligned}\mu_a &= \mu_a(E^b(\vec{r},t) = E^c(\vec{r},t) = E^d(\vec{r},t) \ldots. = 0)\\ &\quad + \sum_b \alpha_{ab} E^b(\vec{r},t) + \frac{1}{2!}\sum_{bc} \beta_{abc} E^b(\vec{r},t) E^c(\vec{r},t)\\ &\quad + \frac{1}{3!}\sum_{bcd} \gamma_{abcd} E^b(\vec{r},t) E^c(\vec{r},t) E^d(\vec{r},t) + \cdots, \qquad (27.1)\end{aligned}$$

In the above equation, $E^a(\vec{r},t)$, $E^b(\vec{r},t)$, …, are the external electric fields consisting of a monochromatic and a static part, and a, b, …. are equal to the Cartesian directions x, y, or z. The first term in Equation 27.1 denotes the dipole moment of the system. α_{ab}, β_{abc}, and γ_{abcd} represent the elements of the linear polarizability tensor, the first-order hyperpolarizability tensor, and the second-order hyperpolarizability tensor, respectively. The time dependence of the dipole moment leads to various frequency-dependent polarizabilities and hyperpolarizability tensors. The first-order hyperpolarizability tensor is described in terms of static first-order hyperpolarizability [β (0; 0, 0)], second-harmonic generation (SHG) [β (−2ω; ω, ω)], electro-optical Pockels effect (EOPE) [β (−ω; ω, 0)], optical rectification (OR) [β (0; ω, −ω)], sum-frequency generation (SFG), and difference-frequency generation (DFG). Similarly, in the case of the second-order hyperpolarizability tensor, apart from the static part [γ (0; 0, 0, 0)], there exists frequency-dependent components, namely, the third-harmonic generation (THG) [γ (−3ω; ω, ω, ω)], the electro-optical Kerr effect (EOKE) [γ (−ω; ω, 0, 0)], the dc-induced second-harmonic generation (dc-SHG or electric field-induced second-harmonic generation (EFISH)) [γ (−2ω; ω, ω, 0)], and the intensity-dependent refractive index (IDRI) [γ (−ω; ω, −ω, ω)] or the degenerate four-wave mixing (DFWM). Among the different NLO properties, the first-order hyperpolarizability is important because it is the simple third-order molecular property and responsible for phenomena such as the SHG and the EOPE. On the other hand, the second-order hyperpolarizability tensor is related to physical properties like the EOKE. It is also significant in the perspective of quantum optical effects like self-focusing and self-defocusing effects in a material.

In the presence of an electric field of field strength

$$E(t) = E_1 e^{-i\omega_1 t} + E_2 e^{-i\omega_2 t} + c.c, \qquad (27.2)$$

the second-order nonlinear polarization induced in a crystal is expressed as

$$P^{(2)}(t) = \chi^{(2)}E(t)^2, \tag{27.3}$$

$$\begin{aligned} P^{(2)}(t) = \chi^{(2)}[&E_1^2e^{-2i\omega_1 t} + E_2^2e^{-2i\omega_2 t} + 2E_1E_2e^{-i(\omega_1+\omega_2)t} \\ &+ 2E_1E_2^{\star}e^{-i(\omega_1-\omega_2)t} + c.c] + 2\chi^{(2)}[E_1E_1^{\star} + E_2E_2^{\star}], \end{aligned} \tag{27.4}$$

The first and second terms in Equation 27.4 represent the SHG, which is useful in the perspective of optoelectronic phenomenon such as tuning the frequency of the laser beam. The expression $2E_1E_2e^{-i(\omega_1+\omega_2)t}$ and $2E_1E_2^{\star}e^{-i(\omega_1-\omega_2)t}$ are associated with the sum-frequency generation (SFG) and the difference-frequency generation (DFG) respectively. The SFG is used to produce tunable radiation in the ultraviolet spectral region and the DFG produces tunable radiation in the infrared region. The process of the DFG is also used in the design of the optical parametric oscillator. The last term of Equation 27.4 does not show any frequency dependence and leads to a process known as optical rectification (OR).

The third order contribution to the nonlinear polarization is given by

$$P^{(3)}(t) = \chi^{(3)}E(t)^3, \tag{27.5}$$

In the case of the monochromatic applied electric field ($E(t) = \xi \cos \omega t$), the nonlinear polarization is expressed as

$$P^{(3)}(t) = \frac{1}{4}\chi^{(3)}\xi^3 \cos 3\omega t + \frac{3}{4}\chi^{(3)}\xi^3 \cos \omega t. \tag{27.6}$$

The first term of Equation 27.6 illustrates the third-harmonic generation (THG), which describes the response of the system at the frequency of 3ω. The second term in Equation 27.6 leads to a nonlinear contribution to the refractive index of the electromagnetic wave of frequency ω. This is recognized as the intensity-dependent refractive index (IDRI). In the presence of such nonlinearity, the refractive index becomes

$$n = n_0 + n_2 I, \tag{27.7}$$

where n_0 is the linear refractive index and

$$n_2 = \frac{12\pi^2}{n_0^2 c}\chi^{(3)}, \tag{27.8}$$

n_2 is an optical constant that characterizes the strength of the optical nonlinearity. I is the intensity of the incident wave expressed as $I = (n_0 c/8\pi)\xi^2$. The intensity-dependent refractive index (IDRI) is related to optical phenomenon, such as the self-focusing of the electromagnetic wave. Self-focusing occurs in a material in which n_2 is positive and the electromagnetic waves, with a nonuniform transverse intensity distribution, curve towards each other after passing through such material.

27.2 Quantum Formulation of Nonlinear Optics

A large number of quantum chemical techniques have been employed for the evaluation of the NLO properties of materials. Jensen et al. have developed a dipole interaction model. This model successfully describes the response properties of large aggregates of molecular clusters [17]. The density-matrix renormalization group (DMRG)-based formalism was proposed by Pati and coworkers and successfully applied in the description of the frequency-dependent NLO properties of π-conjugated systems [18]. Standard techniques like the time-density functional theory, the time-dependent Hartee Fock technique, as well as the finite-field methods [19] based on DFT are also very successful in describing the NLO responses of several classes of materials. The quantum chemical approach, like the density functional theory, had its limitations in the case of long-range dispersion interaction and has been improved by the introduction of the dispersion-corrected DFT DFD-D [20,21] technique. Higher-order wavefunction-based methods like the coupled cluster approach and the MP2 technique are also efficient but they are excessively expensive. In addition to these, the response properties are also evaluated through semi-empirical methods like ZINDO/MRDCI (multi reference doubles-configuration interaction) formalism with a correction vector. [22]. Another well-celebrated quantum chemical approach is the use of the two-state model proposed by Oudar and Chemla [23]. This model relates the nonlinear optical coefficients to the excited-state energy, the oscillator strength and the dipole moment of the molecule under consideration. The theoretical results of Zyss [24] and Andrews et al. [25] successfully established the two-state model of Oudar and Chemla. Datta and Pati [26] employed the two-state model to discuss the role of dipolar interaction and H-bonding in tuning the response properties in molecular aggregates. This model is simple and particularly useful in the case of charge-transfer systems [27]. In this two-state model, the expression of β is given by

$$\beta_{\text{two-level}} = \frac{3e^2}{2\hbar}\frac{\omega_{01} f \Delta\mu_{01}}{(\omega_{01}^2 - \omega^2)(\omega_{01}^2 - 4\omega^2)}$$

where

f is the oscillator strength
ω is the applied frequency
ω_{01} is the frequency of the optical transition between the ground state and the first dipole-allowed state
$\Delta\mu_{01}$ is the difference in moments between the ground state and the first dipole-allowed state

In the absence of an applied frequency, the above equation results in a first-order static hyperpolarizability tensor

$$\langle \beta(0;0,0) \rangle = 3\pi \frac{f\Delta\mu_{01}}{\omega_{01}^3}.$$

In two-state formalism, the parameters like f, ω_{01} and $\Delta\mu_{01}$ are estimated through standard excited approaches like the configuration interaction scheme (CIS) or the time-dependent density-functional theory (TDDFT).

Apart from all those techniques described in the above paragraph, another widely accepted quantum chemical technique of response calculation is the analytic approach. In this context, it will be useful to point out some of the basic differences between the finite-difference technique and the analytic approach. In the finite-difference technique, the energy is calculated at different values of the electric field; there after, the finite differentiation is performed to obtain the derivative of energies. The finite-difference method is suitable for any program capable of energy calculation in a perturbed system. However, the main limitation of this method is the prolonged computational time and it is not good enough when higher order derivatives of the energy are involved. On the contrary, in the analytical approach, physical properties are obtained by analytically evaluating the derivatives of the energy and are often preferred in response calculations. The main advantage of this technique is that it gives access to frequency-dependent properties and the data obtained are more accurate. This technique has been successfully applied by van Gisbergen et al. [28] in case of a set of small molecules. Sen et al. employed the same technique in case of CdSe clusters and Al_4M_4 clusters [11,13].

In the density-functional theoretical formulation of the analytic approach, the starting equation is a variation on the time-dependent Kohn–Sham (TDKS) equation. In order to obtain the starting equation of the analytic approach in the time-dependent density-functional theory (TDDFT), the action integral of the TDDFT is considered.

$$A = \int_{t_0}^{t_1} \mathrm{d}t \left\langle \psi(t) \right| i\frac{\partial}{\partial \mathrm{t}} - \hat{H}(t) \left| \psi(t) \right\rangle, \tag{27.9}$$

where ψ is the wave function of the system. In terms of time-dependent single-particle orbitals $\{\varphi_j(\vec{r},t)\}$, the action integral becomes

$$\begin{aligned} A[\{\varphi_j\}] = {} & \sum_{n}^{j} \int_{-\infty}^{t_1} \mathrm{d}t \int \mathrm{d}^3\vec{r}\, \varphi_j^*(\vec{r},t) \left(i\frac{\partial}{\partial t} + \frac{\nabla^2}{2} \right) \varphi_j(\vec{r},t) \\ & - \int_{-\infty}^{t_1} \mathrm{d}t \int \mathrm{d}^3\vec{r}\, \rho(\vec{r},t) v_{\text{ext}}(\vec{r},t) \\ & - \frac{1}{2} \int_{-\infty}^{t_1} \mathrm{d}t \int \mathrm{d}^3\vec{r} \int \mathrm{d}^3\vec{r}\,' \frac{\rho(\vec{r},t)\rho(\vec{r}\,',t)}{|\vec{r}-\vec{r}\,'|} - A_{xc}[\{\varphi_j\}], \end{aligned} \tag{27.10}$$

In Equation 27.10, the term $v_{\text{ext}}(\vec{r},t)$ is the time-dependent exchange-correlation potential and A_{xc} is the exchange-correlation part of the action functional. On considering the orthonormal Kohn–Sham orbital, the action integral produces the time-dependent Kohn–Sham equation as

$$\sum_j \varepsilon_{ij}(t)\varphi_j(\vec{r},t) + i\frac{\partial}{\partial t}\varphi_i(\vec{r},t) = \left[-\frac{\nabla^2}{2} + \nu_s(\vec{r},t) \right] \varphi_i(\vec{r},t) = F_s\varphi_i(\vec{r},t), \tag{27.11}$$

In Equation 27.11, $\nu_s(\vec{r},t)$ is the time-dependent Kohn–Sham potential and $\varepsilon_{ij}(\vec{r},t)$ is the Lagrangian multiplier. Different choices of Lagrangian multipliers are allowed. With $\varepsilon_{ij}(\vec{r},t) = 0$ we attain the canonical form of the Kohn–Sham equation. In the case of orbitals varying rapidly with time, $\varepsilon_{ij}(\vec{r},t)$ is suitably chosen to avoid an unphysical divergence in the Kohn–Sham equation. The time-dependent density $\rho(\vec{r},t)$ is obtained from the relation

$$\rho(\vec{r},t) = \sum_{i}^{\text{occupied}} \left| \varphi_i(\vec{r},t) \right|^2, \tag{27.12}$$

When $\varphi_i(\vec{r},t)$ is expanded in a fixed time-dependent basis set of atomic orbitals $\{\chi_\mu(\vec{r})\}$, the resulting expression becomes

$$\varphi_i(\vec{r},t) = \sum_{\mu} \chi_\mu(\vec{r}) C_\mu(t), \tag{27.13}$$

In Equation 27.13, the coefficient $C_\mu(t)$ manifests the time dependence of $\varphi_i(\vec{r},t)$. Finally, Equations 27.11 through 27.13 produces the time-dependent Kohn–Sham equation in the matrix form given by

$$F_s C - i\frac{\partial}{\partial t} SC = SC\varepsilon, \tag{27.14}$$

where S is the overlap matrix of the atomic orbitals with

$$S_{\mu\nu} = \int \mathrm{d}\vec{r}\, \chi_\mu^*(\vec{r}) \chi_\nu(\vec{r}), \tag{27.15}$$

The density matrix (D) is expressed in terms of the coefficient matrix C and the occupation number matrix n and is expressed as

$$D = CnC^\dagger. \tag{27.16}$$

The Kohn–Sham equation expressed in Equation 27.14 is the starting point of the perturbative expansion. Equation 27.14 is similar to the starting equation for the NLO calculation in the time-dependent Hartree–Fock technique (TDHF). In Equation 27.14, the term F_s represents the Kohn–Sham matrix or the Fock matrix. This is expressed as

$$F_s = h + DX\,2J + v_{xc}. \tag{27.17}$$

In the above equation, h is the one-electron integral matrix comprising kinetic energy, the Coulomb field of the nuclei, and the applied external electric field. J is the four-index Coulomb supermatrices.

When all matrices are expanded in different orders of external perturbation and ε is chosen as the time-dependent zero-order matrix, the canonical Kohn–Sham equation for the ground-state DFT is obtained and given by the following expression:

$$F_s^{(0)} C^{(0)} = S^{(0)} C^{(0)} \varepsilon^{(0)}. \tag{27.18}$$

The Lagrangian multiplier matrix $[\varepsilon^{(0)}]$ can be chosen at each order of perturbation. Now, if an external electric field of $E^a(\vec{r},t)$ is applied, the mathematical form of $E^a(\vec{r},t)$ being

$$E^a(\vec{r},t) = E^a(\vec{r})\mathrm{X}[1+e^{i\omega_a t}+e^{-i\omega_a t}], \tag{27.19}$$

then in the dipolar approximation, the external perturbation term (H) to the Kohn–Sham Hamiltonian becomes

$$H = \mu \cdot E(\vec{r},t) \tag{27.20}$$

where μ is the dipole-moment operator of the electrons.

The time dependence of the dipole moment produces various frequency-dependent hyperpolarizablity tensors. Frequency-dependent polarizability and hyperpolarizability tensors are obtained from the trace of the dipole moment matrix $[H^a]$ and the nth-order density matrix $[D^{(n)}]$ (where $n = 1$ for the linear polarizability α, $n = 2$ for the first-order hyperpolarizability tensor β, $n = 3$ for the second-order hyperpolarizability γ and so on). If the inducing electric field of frequency ω_a, ω_b, ω_c … acts in the direction a, b, c… the tensors can be represented as

$$\alpha_{ab}(-\omega_\sigma;\omega_b) = -\mathrm{Tr}\left[H^a D^b(\omega_b)\right], \tag{27.21}$$

$$\beta_{abc}(-\omega_\sigma;\omega_b,\omega_c) = -\mathrm{Tr}\left[H^a D^{bc}(\omega_b,\omega_c)\right], \tag{27.22}$$

$$\gamma_{abcd}(-\omega_\sigma;\omega_b,\omega_c,\omega_d) = -\mathrm{Tr}\left[H^a D^{bcd}(\omega_b,\omega_c,\omega_d)\right], \tag{27.23}$$

where $\omega_\sigma = \omega_b + \omega_c + \cdots$ These expressions are a set of generalized equations in terms of frequencies. The polarizability and the hyperpolarizability tensors defined above are determined through the iterative solution of the time-dependent Kohn–Sham (TDKS) equations given in Equation 27.14.

In ordinary TDDFT, the zeroth-order Kohn–Sham matrix is used, which is given by

$$F_s^{(0)} = h^{(0)} + D^{(0)}\mathrm{X}(2J) + v_{xc}^{(0)}, \tag{27.24}$$

where $h^{(0)}$ contains the external potential terms that are of zero order in the external field, kinetic energy and the nuclear Coulomb field. The Coulomb super matrix J is independent of the external electric field and results in a Coulomb term of the form $D^{ab\ldots n}(\omega_a, \omega_b, \ldots, \omega_n)\mathrm{X}(2J)$ in the nth-order Kohn–Sham matrix $F_s^{ab\ldots n}(\omega_a,\omega_b,\ldots,\omega_n)$. The external perturbation appears only in the first-order Kohn–Sham matrices. Higher-order Kohn–Sham matrices consist of a Coulomb and an exchange-correlation part. Therefore, the general formula for the higher-order Kohn–Sham matrices becomes

$$\begin{aligned} F_s^{ab\ldots n}(\omega_a,\omega_b,\ldots,\omega_n) &= D^{ab\ldots n}(\omega_a,\omega_b,\ldots,\omega_n)\mathrm{X}(2J) \\ &\quad + v_{xc}^{ab\ldots n}(\omega_a,\omega_b,\ldots,\omega_n), \end{aligned} \tag{27.25}$$

The Taylor expansions of F_s, C, ε, and D are inserted in the time-dependent Kohn–Sham equation (Equation 27.14), the normalization condition, and the density matrix (Equation 27.16). This results in a first-order time-dependent Kohn–Sham equation as

$$F_s^a(\omega)C^{(0)} + F_s^0 C^a(\omega) + \omega S^0 C^a(\omega) = S^{(0)}C^a(\omega)\varepsilon^{(0)} + S^{(0)}C^{(0)}\varepsilon^a(\omega). \tag{27.26}$$

Higher-order coupled equations are obtained by equating the left and the right hand sides of the TDKS equation, the normalization condition and the density matrix. The NLO properties are estimated through the iterative solution of the time-dependent Kohn–Sham equations up to a certain order n. Primarily, the static Kohn–Sham equations are solved that result in matrices $F_s^{(0)}$, $C^{(0)}$, $\varepsilon^{(0)}$, $D^{(0)}$, and the converged SCF density $\rho^{(0)}$. These matrices are needed for the solution of the first-order Kohn–Sham equation, which produces the first-order density matrix. The first-order density matrix yields the frequency-dependent polarizability component $[\alpha_{\mathrm{ab}}\ (-\omega_\sigma;\ \omega_{\mathrm{b}})]$ through Equation 27.21. The solution of the first-order equation provides matrices required for an iterative solution of the second-order equation. In either case, the technique adopted is called the $(2n + 1)$ theorem. The second-order equation is solved to get the second-order density matrix elements from which the frequency-dependent first-order hyperpolarizability tensor is obtained through Equation 27.23. If the external fields of the frequency zero and a common frequency ω are considered, a number of very important NLO properties become accessible. These are SHG $[\beta\ (-2\omega;\ \omega,\ \omega)]$, EOPE $[\beta\ (-\omega;\ \omega,\ 0)]$, OR $[\beta\ (0;\ \omega,\ -\omega)]$, and the static hyperpolarizability $[\beta\ (0;\ 0,\ 0)]$. Similar to the two previous cases, the $(2n + 1)$ theorem is also used to compute the higher-order hyperpolarizability tensors like γ, δ (third-order hyperpolarizability tensor), and the rest. When γ is calculated only at frequencies 0 and ω, THG $[\gamma\ (-3\omega;\ \omega,\ \omega,\ \omega)]$, EOKE $[\gamma\ (-\omega;\ \omega,\ 0,\ 0)]$, dc-SHG $[\gamma\ (-2\omega;\ \omega,\ \omega,\ 0)]$, and IDRI $[\gamma\ (-\omega;\ \omega,\ -\omega,\ \omega)]$ become accessible.

In practice, the average polarizability tensor is defined in terms of Cartesian components such as

$$\langle\alpha\rangle = \frac{\alpha_{xx}+\alpha_{yy}+\alpha_{zz}}{3}, \tag{27.27}$$

where, α_{xx}, α_{yy}, and α_{zz} are the diagonal elements of the polarizability-tensor matrix. The first-order hyperpolarizability tensor is defined as the third derivative of the energy with respect to the electric field components, and hence, involves one additional field differentiation compared to polarizabilities. The average first-order hyperpolarizability is defined as

$$\langle\beta\rangle = \left(\sum_i \beta_i\beta_i^*\right)^{1/2};\quad \beta_i = \frac{1}{3}\sum_j(\beta_{ijj}+\beta_{jij}+\beta_{jji}), \tag{27.28}$$

where the sums are over the coordinates x, y, z ($i, j = x, y, z$), and β_i^* refers to the conjugate of the vector β_i. The second-order hyperpolarizability tensor involves one additional field differentiation compared to the first-order analog. The average second-order hyperpolarizability is defined as

$$\langle\gamma\rangle = \frac{1}{15}\sum_{ij}(2\gamma_{iijj} + \gamma_{ijji}); \quad (i, j = x, y, z). \tag{27.29}$$

In some of the theoretical approaches second-order hyperpolarizability tensors are determined from a combination of analytical and finite-difference techniques [28]. All components of the γ tensor of interest (dc-SHG/EOKE/static second-order hyperpolarizability) are obtained from the analytical time-dependent calculation of the SHG/EOPE/static first-order hyperpolarizability in the presence of small electric fields. E.g., the relation used in the evaluation of EOKE is

$$\gamma_{abcd}(-\omega;\omega,0,0) = \lim_{E^d \to 0} \frac{\beta_{abc}(-\omega;\omega,0)\big|_{E=E^d}}{E^d}, \tag{27.30}$$

Frequency-dependent response properties can also be calculated from the time-averaged quasienergy [29]. In this formalism, the response properties are obtained as the derivative of the quasi energy and the same is estimated by using the variational criterion for the quasienergy and the time-averaged time-dependent Hellmann–Feynman theorem. Molecular properties are obtained by using the variational Lagrangian technique in accordance with the $2n + 1$ and the $2n + 2$ rules. Within this approach, the different frequency-dependent response properties are obtained from the simple extension of the variational perturbation theory to the Fourier component variational perturbation theory.

27.3 Nonlinear Optics with Materials

Much of the present research work in the field of nonlinear optics is motivated by certain nonlinear optical phenomena in suitable materials [14]. Some of these potentially useful phenomena include the ability to alter the frequency or color of light, to amplify one source of light with another, and to alter its transmission features through a medium. The nonlinear optical materials require unusual stability with respect to ambient conditions and high-intensity light sources. These materials can broadly be categorized into two major classes. The first is the class of inorganic materials, which includes semiconducting and metallic clusters, inorganic crystals, bulk materials, etc. The second belongs to the organic or, in general, molecular materials that include mainly organic crystals and polymers. For these systems, the optical nonlinearities are usually derived from their structures. In the present chapter, we will focus only on the first type, i.e., semiconducting and metallic clusters and their NLO behavior.

27.4 Why Are Clusters So Important?

Nonlinear optical processes in cluster materials provide the necessary information about the exact understanding of the quantum confinements and the surface effects in these systems [11]. In general, the properties at the nanoscale are usually nonmonotonic and oscillating in nature due to the quantum size effects, and as such, cluster materials can exhibit properties, which are quite different from those of the bulk [5,11,30]. More specifically, the energy band structure and the phonon distribution of cluster materials may differ from that of the bulk systems. Numerous theoretical as well as experimental investigations have been performed that show that the cluster-assembled materials have novel mechanical, electrical, and optical properties [5–16]. As mentioned earlier in this chapter, these NLO materials find huge applications in high-speed electro-optic devices for information processing and telecommunications [1–4]. In Section 27.5, we present a review on nonlinear optics with various cluster materials.

27.5 Review of Nonlinear Optics with Clusters

In this section, semiconducting clusters will be discussed first followed by metallic clusters. An example of a class of materials with a manifestation of unusual physicochemical and optical properties is cadmium selenide clusters [$(\mathrm{CdSe})_n$]. These $(\mathrm{CdSe})_n$ clusters are found to be the precursors of a wide range of low-dimensional materials such as quantum dots [7,10], tetrapods [31], and nanowires [32] that exhibit a variety of optical and electronic properties. The electronic properties of cadmium selenide clusters $(\mathrm{CdSe})_n$ and quantum dots are semiconducting in nature and these materials find tremendous application in the design and the development of novel nonlinear optical (NLO) materials. There have been a lot of experimental investigations [15,33] on the exploration of the NLO properties in CdSe clusters. The Hyper-Rayleigh scattering technique provides the experimental basis for NLO properties in CdSe clusters and nanoparticles [15]. Aktsipetrov et al. [33] have shown the size dependence of SHG from the surface of a composite material consisting of CdSe nanoparticles embedded in a glass matrix. The first-order hyperpolarizability in CdSe and CdS nanoparticles is reported to be very high [34].

Apart from the experimental works, theoretical *ab initio* investigations [8,11,12] have also been performed in order to calculate the NLO coefficients in CdSe clusters. Troparevsky and Chelikowsky [35], in their work, reported on the structural and the electronic properties (the energy gap between the highest occupied molecular orbital (HOMO) and the lowest unoccupied molecular orbital (LUMO), binding energies, and polarizabilities) of small $(\mathrm{CdS})_n$ and $(\mathrm{CdSe})_n$ clusters, where n ranges from 2 up to 8 using the pseudopotential method in real space. Karamanis et al. [36] have used DFT for the computation of static polarizability and anisotropy in the static polarizability of small CdSe clusters up to tetramer units (see Figure 27.1).



FIGURE 27.1 Evolution of the mean dipole polarizability with cluster size in a small CdSe cluster, (CdSe)$_n$. (From Karamanis, P. et al., *J. Chem. Phys.*, 124, 071101, 2006. With permission.)

Their investigations suggest that the optical properties of the bulk system can also be predicted from a plot of dipole polarizability per atom.

Later on, the same group of Karamanis extended their work on CdSe clusters, highlighting the importance of basis sets and electron correlation in these systems [12]. However, the calculations of the frequency-dependent optical polarizability, as well as that of hyperpolarizability tensors using theoretical methods remained an unresolved issue for CdSe clusters.

Recently, Sen and Chakrabarti [11], for the first time, investigated the frequency-dependent nonlinear optical properties (first- and second-order hyperpolarizability tensors) of (CdSe)$_n$ clusters up to the tetramer using the time-dependent density functional theory (TDDFT). Within the TDDFT, both the local-density approximation (LDA) and the generalized-gradient approximation (GGA) technique have been used. The more accurate LB94 (van Leeuwen and Baerends 94) [37] functional has been used under the GGA scheme. Response calculations have been implemented in the Amsterdam density functional package (ADF 2004.01) [38]. The analytical approach has been used for the evaluation of all the NLO coefficients. The calculated polarizability and hyperpolarizabilities depend on the choice of the basis set and the exchange-correlation potential. While the results obtained within the DFT are overestimated under the normal LDA and GGA functional, the coupled Hartree–Fock procedure exhibits exactly the opposite trend [39,40]. The static values of the average first-order hyperpolarizability (⟨β (0; 0, 0)⟩) and the average second-order hyperpolarizability (⟨γ (0; 0, 0, 0)⟩) of CdSe, Cd$_2$Se$_2$, Cd$_3$Se$_3$, and Cd$_4$Se$_4$ are depicted in Table 27.1.

TABLE 27.1 Average Static First and Second Order Static Hyperpolarizability in CdSe, Cd$_2$Se$_2$, Cd$_3$Se$_3$, and Cd$_4$Se$_4$

Sample	Average Static First-Order Hyperpolarizability, ⟨β (0;0,0)⟩ (a.u.)	Average Static Second-Order Hyperpolarizability, ⟨γ (0;0,0,0)⟩ (a.u.)
CdSe	−540.07 (LDA)	−556,680 (LDA)
Cd$_2$Se$_2$	Absent	7,306.5 (LDA)
		4,398.6 (LB94)
Cd$_3$Se$_3$	−0.12258 (LDA)	12,200 (LDA)
	−0.059125 (LB94)	8,929.3 (LB94)
Cd$_4$Se$_4$	Absent	89,565 (LDA)
		50,124 (LB94)

Source: Sen, S. and Chakrabarti, S., *Phys. Rev. B*, 74, 205435, 2006. With permission.

The frequency dependence of the SHG [β (−2ω; ω, ω)], the EOPE [β (−ω; ω, 0)], the EFISH [γ (−2ω; ω, ω, 0)], and the EOKE [γ (−ω; ω, 0, 0)] was paid premier attention in the investigation of Sen and Chakrabarti [11]. For a complete evaluation of the frequency dependence of NLO properties in different CdSe clusters, a wide range of frequencies (0 to 0.45 a.u.) was considered.

Figure 27.2 manifests the frequency behavior of ⟨β (−2ω; ω, ω)⟩ and ⟨β (−ω; ω, 0)⟩ in the case of CdSe and Cd$_3$Se$_3$ respectively. ⟨β (−2ω; ω, ω)⟩, being a frequency-dependent property, is of paramount interest and has been investigated extensively in numerous previous investigations [15,41,42]. High degrees of fluctuations in ⟨β (−2ω; ω, ω)⟩ are observed in all the cases. Experimentally, ⟨β (−2ω; ω, ω)⟩ in CdSe nanocrystals and quantum dots has been observed by the HRS technique and its size dependence was also verified [15]. It is evident from Figure 27.2 that ⟨β (−2ω; ω, ω)⟩ is negative over a wide range of frequencies. This makes CdSe and Cd$_3$Se$_3$ more significant in the perspective of quantum optics. The frequency variation in ⟨β (−2ω; ω, ω)⟩ divulges one more significant information, i.e., the abrupt increase in ⟨β (−2ω; ω, ω)⟩ at specific frequencies. At specific frequencies the magnitude of ⟨β (−2ω; ω, ω)⟩ becomes very high. It is a common notion that larger values of ⟨β (−2ω; ω, ω)⟩ are obtained at a near resonance of the input energy [5]. The presence of the near resonance indicates that linear absorption can occur at such frequencies.

Similar to the components of the first-order hyperpolarizability tensors, the components of the second-order hyperpolarizability tensors (⟨γ (−2ω; ω, ω, 0)⟩ and ⟨γ (−ω; ω, 0, 0)⟩) were reported to be highly sensitive to frequency variation. Figure 27.3 demonstrates the frequency dependence of different γ tensors. It was concluded from both LDA and LB94 results that both ⟨γ (−2ω; ω, ω, 0)⟩ and ⟨γ (−ω; ω, 0, 0)⟩ are negative over a wide range of frequencies. The change in the sign of ⟨γ (−2ω; ω, ω, 0)⟩ and ⟨γ (−ω; ω, 0, 0)⟩, due to the change in frequency is a significant observation. This led to a frequency selection in assigning the optical activity of the particular cluster.

In a separate study, Chakrabarti and coworkers [43] investigated the evolution of electric polarizability and the anisotropy of the polarizability at static as well as dynamic (Nd:YAG laser) frequencies with an increase in the cluster size for small, as well



FIGURE 27.2 Variation of ⟨β (−2ω; ω, ω)⟩ (SHG) and ⟨β (−ω; ω, 0)⟩ (EOPE) with a frequency at (a) LDA scheme for the CdSe cluster, (b) LDA, and (c) GGA (LB94) scheme for the Cd_3Se_3 cluster. (From Sen, S. and Chakrabarti, S., *Phys. Rev. B*, 74, 205435, 2006. With permission.)



FIGURE 27.3 Variation of ⟨γ (−2ω; ω, ω, 0)⟩ and ⟨γ (−ω; ω, 0, 0)⟩ with a frequency at LDA. (a) Scheme for the CdSe cluster, (b) LDA and

(*continued*)



FIGURE 27.3 (continued) (c) GGA (LB94) scheme for the Cd_2Se_2 cluster, (d) LDA and (e) GGA (LB94) scheme for the Cd_3Se_3 cluster, (f) LDA and (g) GGA (LB94) scheme for the Cd_4Se_4 cluster. (From Sen, S. and Chakrabarti, S., *Phys. Rev. B*, 74, 205435, 2006. With permission.)

as medium-sized $(CdSe)_n$ (n = 1–16) clusters within the density functional theory (DFT). The main motivation of that investigation was

1. None of the theoretical studies reported had gone beyond a cluster size of eight for the polarizability calculations for the CdSe clusters.
2. Except the study by Sen and Chakrabarti [11], no one was aware of any investigations where the dynamic hyperpolarizability for any system size was reported for the CdSe clusters.

Knowing the strong dependence of polarizability on the cluster diameter (the cluster size), they performed polarizability calculations beyond the cluster size of eight and calculated both static and dynamic polarizabilities.

Table 27.2 describes computed polarizability values at static and Nd:YAG laser frequencies. An even-odd oscillating behavior is observed in the anisotropy values between the dimer and the heptamer CdSe clusters.

Just like the CdSe clusters, GaAs is one such semiconducting cluster, which has gained a lot of importance over the past few years [5]. These cluster materials display long absorption tails in the low energy region [44] owing to the existence of free surfaces in it. Moreover, the static polarizabilities of these systems exceed the bulk value and follow a decreasing tendency with the increase in the cluster size [45]. The variable nature in the polarizabilities also indicates its "metallic-like" behavior. In the experimental investigation [46], it has been observed that the polarizabilities for small and medium-sized Ga_nAs_m clusters reside above and below the bulk limit. Albeit, there have been a lot of experimental and theoretical investigations [47–49] based on the NLO properties of GaAs bulk materials which suggest that GaAs should possess very large static second- and third-order susceptibilities, only a few of them deal with the theoretical evaluation of the hyperpolarizabilities of these cluster materials [50,51]. A recent work by Lan et al. [5] provides a systematic insight into the NLO properties of several small and medium Ga_nAs_m clusters, where $m + n$ runs up to 10. They employed the TDDFT method in combination with the sum-over-states (SOS) formalism to calculate the first- and second-order hyperpolarizability tensors. The results indicate the presence of large second- and third-order nonlinear susceptibilities in GaAs cluster materials similar to that of the bulk. These results also suggest that resonance absorption can be avoided in the frequency-dependent NLO experiments. Furthermore, the frequency dependence of second- and third-harmonic generation reveals that these clusters are good candidates for future NLO materials.

Besides these two clusters, investigations of the NLO properties have also been carried out on various other III-V atomic nanoclusters. Pineda and Karna [52] estimated the linear and the nonlinear polarizabilities of isolated GaN nanoclusters employing the *ab initio* time-dependent Hartree–Fock (TDHF) method. Their results suggest a strong dependence of the NLO properties on the size and the shape of the clusters. The linear and the nonlinear optical properties of $(CdS)_n$ clusters were analyzed and the merits of the DFT level calculations have been compared with different *ab initio* results, as well as the basis set dependence of the optical properties of these clusters has been evaluated by Maroulis and Pouchan [53].

Figure 27.4 depicts the variation in the mean polarizability and the mean second-order hyperpolarizability values in small $(CdS)_n$ clusters. The values suggest a reduction in the mean

TABLE 27.2 Average Values of Electric Polarizability per Atom ($\langle\alpha\rangle/2n$) and Anisotropy in Polarizability ($\Delta\alpha$) against the Cluster Size, $2n$ at Both Static (0.0 a.u.) and Nd:YAG Laser (0.04283 a.u.) Frequencies

			At 0.0 a.u. Frequency		At Nd:YAG Laser (0.04283 a.u.) Frequency	
Samples	n	$2n$	Polarizability per Atom ($\langle\alpha\rangle/2n$) (a.u.)	Anisotropy in Polarizability ($\Delta\alpha$) (a.u.)	Polarizability per Atom ($\langle\alpha\rangle/2n$) (a.u.)	Anisotropy in Polarizability ($\Delta\alpha$) (a.u.)
CdSe	1	2	34.0349	36.5416	31.3777	49.7528
Cd_2Se_2	2	4	30.9670	60.5853	32.5664	59.0703
Cd_3Se_3	3	6	29.8098	99.7527	30.5716	102.1434
Cd_4Se_4	4	8	29.5301	0.0000	30.8635	0.0000
Cd_5Se_5	5	10	32.4484	159.8706	33.3488	166.2891
Cd_6Se_6	6	12	29.1341	43.8215	30.0033	43.5338
Cd_7Se_7	7	14	29.0036	134.4511	29.9893	143.1402
Cd_8Se_8	8	16	29.5565	114.3660	30.4782	122.1772
Cd_9Se_9	9	18	29.4061	49.9355	30.2877	54.6105
$Cd_{10}Se_{10}$	10	20	29.8171	124.1952	30.7628	132.7159
$Cd_{11}Se_{11}$	11	22	29.8559	150.1088	30.7738	160.6296
$Cd_{12}Se_{12}$	12	24	28.4830	0.0165	29.3089	0.0169
$Cd_{13}Se_{13}$	13	26	30.9808	271.1190	32.0344	287.1187
$Cd_{14}Se_{14}$	14	28	30.3060	192.7016	31.2651	207.4891
$Cd_{15}Se_{15}$	15	30	30.2442	158.5999	31.1661	170.6002
$Cd_{16}Se_{16}$	16	32	33.5302	428.7594	34.9350	470.1254

Source: Jha, P.C. et al., *Comput. Mater. Sci.*, 44, 728, 2008. With permission.



FIGURE 27.4 Mean (a) dipole polarizability and (b) second-order hyperpolarizability in (CdS)$_n$ clusters. (From Maroulis, G. and Pouchan, C., *J. Phys. Chem. B*, 107, 10683, 2003. With permission.)

dipole polarizability, as well as in the second-order hyperpolarizability values with an increase in the cluster size. Moreover, the results obtained from B3LYP and other conventional *ab initio* methods are well in accordance with each other and also with the earlier theoretical results [35]. However, in the case of the monomer geometry, the difference in the hyperpolarizability values between these methods is quite large. Champagne et al. estimated [54] average second-order hyperpolarizabilities of Si$_n$ (n = 3–38) clusters using MP2, MP3, MP4, CCSD, and CCSD(T) levels of approximations and demonstrated the variation of polarizability and hyperpolarizability against the cluster size.

Apart from these semiconducting materials, cluster science has also made rapid progress in determining the electric properties of various metal clusters [55] including that of mixed metal. At first, a review of the some of the works based on the metal clusters containing only one type of atom is discussed, which is followed by some detailed analysis on mixed metal clusters. There are investigations on lithium [18,56,57], sodium [58], copper [59,60], nickel [61], niobium [62], and zinc [63] clusters. Maroulis and Xenides [57] reported highly accurate *ab initio* calculations on the polarizability and the hyperpolarizabilities of lithium tetramer, Li$_4$ with specially designed basis sets for Li. The molecule, Li$_4$ has got a very high anisotropic dipole polarizability and quite large second-order hyperpolarizability values. The main feature of this work is the extensive analysis of the basis set and the correlation effects in calculating the electric properties. The results indicate a discrepancy in dipole polarizabilities between theory and experiment, which might be resolved by measuring the anisotropy values experimentally. The same group also presented a thorough analysis of the performance of several density functional theoretical (DFT) calculations of the (hyper) polarizability of Li$_4$. Their investigations elucidated that of the various DFT methods employed; only the mPW1PW91 and the O3LYP methods produce reliable results. Papadopoulos et al. [63] studied the (hyper) polarizabilities of small and medium-sized zinc clusters employing a hierarchy of basis sets and computational methods. The relativistic effect on the electric polarizabilities has also been investigated by employing the Douglas–Kroll approximation. It has been observed that the relativity contribution is significant in these cluster materials; however, the correlation effect plays a major part in influencing the electro-optic properties.

The NLO properties of Ag nanoparticles embedded in a Si$_3$N$_4$ matrix was investigated by Traverse et al. [64]. They performed a two-color sum-frequency generation (2c-SFG) spectroscopy experiment, which exhibited a surface plasmon resonance at a 421 nm wavelength in the visible region and absorption in the infrared region. The third-order optical nonlinearity of dielectrics in the presence of nanoparticles has been experimentally investigated by Flytzanis [65]. Chen and coworkers performed [66] high-level *ab-initio* calculations [HF, MP2, the fourth-order perturbation theory using single, double, quadrupole substitutions, CCSD, and QCISD] on (HCN)$_n$…Li and Li…(HCN)$_m$ clusters with electride characteristics. A high value of static first hyperpolarizability is reported in both samples. The static second-order hyperpolarizability of a series of tri-nuclear metal cluster MS4(M′PPh$_3$)$_2$(M′PPh$_3$) (M = Mo, W; M′ = Cu, Ag, Au) have been estimated by [67] Chen and coworkers. They employed a finite-field approach using the hybrid density functional theory (B3LYP) and reported a very high value of second-order hyperpolarizability. The NLO properties of Au$_n$ clusters

TABLE 27.3 Average Hirshfeld Charge on the Al_4 Ring, Ground State Dipole Moment, Magnitude of Average Static First- and Second-Order Hyperpolarizability in Al_4M_4 (M = Li, Na, and K)

Sample	Average Hirshfeld Charge on the Al_4 Ring	Ground-State Dipole Moment (Debye)	Average Static First-Order Hyperpolarizability, $\langle\beta(0; 0, 0)\rangle$ (a.u.)	Average Static Second-Order Hyperpolarizability, $\langle\gamma(0; 0, 0, 0)\rangle$ (a.u.)
Al_4Li_4 (2D)	−0.247	0.049	145.922	1.299×10^6
Al_4Li_4 (3D)	−0.202	0.018	33.079	2.406×10^6
Al_4Na_4 (2D)	−0.258	0.003	21.537	1.275×10^6
Al_4Na_4 (3D)	−0.229	0.054	187.843	1.961×10^6
Al_4K_4 (2D)	−0.303	0.080	316.781	3.380×10^6
Al_4K_4 (3D)	−0.297	6.513	8863.074	1.149×10^7

Source: Sen, S. et al., *Phys. Rev. B*, 76, 115414, 2007. With permission.

and their alloyed clusters, $Au_{n-m}M_m$ (M = Ag, Cu; m = 1, 2) have been theoretically investigated by Xu and coworkers [68]. They used the usual TD-DFT as well as the B3LYP hybrid density functional employing the LANL2DZ basis set and measured the first-order hyperpolarizabilites of such clusters. They suggested that the high degree of NLO properties of these clusters are due to the lack of a centro-symmetric feature in these clusters and an enhancement in the transition electric dipole moment in alloyed clusters.

The optical properties of several mixed metal clusters such as Li_nCu_m, Na_4Pb_4, Na_6Pb, $Al_{11}Fe$, and $Al_{18}Fe$, Al_4M_4 (M = alkali metals) have also been investigated extensively [69,70]. In this context, we particularly mention the NLO properties of aluminum metal clusters [Al_4M_4 (M = Li, Na, and K)]. Various investigations have been performed on these Al_4M_4 systems and their anions due to their unique characteristic features and their structural similarity with that of cyclobutadiene, C_4H_4 [6]. These cluster materials are also important since they are better polarized than their organic counterparts. Earlier, Datta and Pati [6] investigated the static linear and nonlinear polarizabilities of Al_4M_4 (M = Li, Na, and K) systems. They predicted that structural changes through the broken inversion symmetry of Al_4M_4 could lead to a unique polarization response and large optical coefficients. In their work, both the static linear and nonlinear optical properties of these Al_4M_4 were estimated through ZINDO-multireference doubles configuration interaction (MRDCI) calculations. They emphasized that the large NLO properties of Al_4M_4 are due to the charge transfer from alkali metals to the Al_4 ring. In spite of the fact that their work exhibits an exceptionally high magnitude of static linear and nonlinear optical coefficients, it lacks the description of its dynamic counterparts. It is to be noted that the importance of a material in nonlinear optics and its applications in device fabrication demands a complete description of the frequency dependence. Hence, it was highly instructive to explore the dynamic (frequency-dependent) NLO properties of these clusters for their proper assessment in optical device fabrication and to explain whether the large NLO properties are due to a charge transfer interaction or due to other excitations.

Recently Sen et al. [13] reported various components of first- (SHG, EOPE, static first-order hyperpolarizability) and second- (EFISH, EOKE, and static second-order hyperpolarizability) order hyperpolarizability tensors at several near resonance frequencies. All these dynamic NLO properties of Al_4M_4 (M = Li, Na, and K) clusters have been explored using the TDDFT as a prime investigating tool. Within the TDDFT, the generalized gradient approximation (GGA) technique has been implemented with the use of a more accurate LB94 (van Leeuwen and Baerends 94) functional.

The magnitude of static $\langle\beta\rangle$ and $\langle\gamma\rangle$ along with an average Hirshfeld charge on the Al_4 ring and the ground-state dipole moments are shown in Table 27.3. It is quite clear from Table 27.3 that the magnitude of $\langle\beta(0;0,0)\rangle$ increases significantly from 2D to 3D in the case of Al_4Na_4 and Al_4K_4, on the other hand, a reverse trend is observed for Al_4Li_4.

Table 27.3 also suggests that the magnitudes of the average static $\langle\gamma(0;0,0,0)\rangle$ are very high (of the order of 10^6 and 10^7 a.u.) for all the clusters under investigation.

However, the central issue of the investigation of Sen and coworkers [13] was to explicate the frequency dependence of $\langle\beta(-2\omega; \omega, \omega)\rangle$, $\langle\beta(-\omega; \omega, 0)\rangle$, $\langle\gamma(-2\omega; \omega, \omega, 0)\rangle$, and $\langle\gamma(-\omega; \omega, 0, 0)\rangle$ in aluminum metal clusters. These components of the first- and second-order hyperpolarizability tensors were estimated in the vicinity of near-excitation frequencies with a substantial oscillator strength and presented in Table 27.4. A closer inspection of Table 27.4 reveals that $\langle\beta(-2\omega; \omega, \omega)\rangle$ and $\langle\beta(-\omega; \omega, 0)\rangle$ attain negative values at certain frequencies in all these cluster materials. Exceptionally high values [of the order of 10^6–10^8 a.u.] of $\langle\gamma(-2\omega; \omega, \omega, 0)\rangle$ and $\langle\gamma(-\omega; \omega, 0, 0)\rangle$ were also noticed. A significant observation was in the change in sign of $\langle\gamma(-2\omega; \omega, \omega, 0)\rangle$ and $\langle\gamma(-\omega; \omega, 0, 0)\rangle$ due to the change in frequency, which lead to a frequency selection in assigning the optical activity of a particular cluster.

In order to explain the observed high NLO coefficients in these aluminum metal clusters, an analysis of the magnitude of gross populations of molecular orbitals with the most significant SFO (Symmetrized Fragment Orbitals) was carried out. The SFO study divulged the role of charge transfer interactions. Molecular orbitals with the most significant SFO gross population indicated that except for Al_4K_4 (2D and 3D) and Al_4Li_4 (3D) there exists excitations other than a charge transfer interaction at near resonance frequencies.

Moreover, it is worth mentioning that the dynamic first-order hyperpolarizability tensors are functions of the excitation

TABLE 27.4 ⟨β(−2ω; ω, ω)⟩, ⟨β(− ω; ω, 0)⟩, ⟨γ(−2ω; ω, ω, 0)⟩, and ⟨γ (−ω; ω, 0, 0)⟩ Measured at Frequencies Nearer to Excitation Frequencies in Al_4M_4 (M = Li, Na and K)

Sample	Excitation Frequencies (a.u.)	Oscillator Strength	Frequency at which Data Are Taken (a.u.)	⟨β(−2ω; ω, ω)⟩ (a.u.)	⟨β(−ω; ω, 0)⟩ (a.u.)	⟨γ(−2ω; ω, ω, 0)⟩ (a.u.)	⟨γ(−ω; ω, 0, 0)⟩ (a.u.)
Al_4Li_4 (2D)	0.0205	0.0042	0.0200	−6081.100	12,741	8.988×10^6	-2.744×10^6
	0.0522	0.0034	0.0500	224.900	46.143	-5.239×10^5	1.155×10^6
	0.0558	0.0094	0.0540	−371.630	361.960	1.226×10^7	-7.558×10^5
Al_4Li_4 (3D)	0.0377	0.0441	0.0360	4057.900	−15,252	6.049×10^6	1.663×10^7
	0.0650	0.0863	0.0640	968.580	−902.360	2.729×10^7	-8.458×10^4
	0.0709	0.3736	0.0690	−638.610	236.140	-1.199×10^8	-1.866×10^7
Al_4Na_4 (2D)	0.0238	0.0068	0.0220	−429.590	2697.100	1.266×10^7	-7.639×10^7
	0.0403	0.0012	0.0390	51.085	−96.614	4.735×10^4	1.245×10^6
	0.0570	0.0852	0.0590	4641.500	−93.815	1.540×10^7	-6.290×10^6
Al_4Na_4 (3D)	0.0271	0.0301	0.0260	2193.700	−13333	1.675×10^7	-6.581×10^6
	0.0446	0.0060	0.0430	−452.340	−178.82	4.459×10^6	5.213×10^5
	0.0543	0.0099	0.0560	−7067.500	−168.550	1.242×10^7	1.401×10^6
Al_4K_4 (2D)	0.0244	0.0066	0.0230	305.930	864.090	1.286×10^6	6.640×10^6
	0.0427	0.0910	0.0410	−1465.600	3477.900	-3.240×10^7	3.698×10^7
	0.0431	0.0197	0.0440	−64908	−5213.200	-3.143×10^8	2.548×10^7
Al_4K_4 (3D)	0.0215	0.0010	0.0200	−231620	−16,582	1.842×10^7	-1.926×10^7
	0.0391	0.0105	0.0380	29403	150,940	9.758×10^6	2.791×10^7
	0.0416	0.0067	0.0400	−120770	380,220	-7.515×10^7	4.444×10^7

Source: Sen, S. et al., *Phys. Rev. B*, 76, 115414, 2007. With permission.

energy, the dipolar matrix, and the difference between the dipole moment of the ground and the excited states. On the other hand, components of the second-order hyperpolarizability tensor are associated with four dipolar matrices in the numerator and three excitation frequencies in the denominator. Hence, it is very difficult to find all the factors that play a dominant role in the high β and γ values in particular clusters.

27.6 Conclusions

Therefore, it is well established from both the theoretical as well as the experimental standpoint that cluster materials can be considered as promising candidates for future NLO devices due to their high nonlinear optical coefficient. However, the exploration of the fundamentals of the unique physicochemical behavior of these clusters is a challenge to modern physical and chemical research. A theoretical determination of a higher-order nonlinear optical coefficient is still a matter of extensive computation and there is need for further developments to provide a proper physical background for some of the higher-order optical coefficients. There is enough scope for future research work in the field of cluster science and the design of new cluster materials with interesting physical behavior.

References

1. M. Lee, E. H. Katz, C. Erben, D. M. Gill, P. Gopalan, J. D. Heber, and D. J. McGee, *Science* **298**, 1401 (2002).
2. Y. Shi, C. Zhang, H. Zhang, J. H. Bechtel, L. R. Dalton, B. H. Robinson, and W. H. Steier, *Science* **288**, 119 (2000).
3. J. Luo, M. Haller, H. Li, H.-Z. Tang, A. K.-Y. Jen, K. Jakka, C.-H. Chou, and C.-F. Shu, *Macromolecules* **37**, 248 (2004).
4. C. Zhang, L. R. Dalton, M. C. Oh, H. Zhang, and W. H. Steier, *Chem. Mater*. **13**, 3043 (2001).
5. Y.-Z. Lan, W.-D. Cheng, D.-S. Wu, J. Shen, S.-P. Huang, H. Zhang, Y.-J. Gong, and F.-F. Li, *J. Chem. Phys*. **124**, 094302 (2006).
6. A. Datta and S. K. Pati, *J. Phys. Chem. A* **108**, 9527 (2004).
7. A. Puzder, A. J. Williamson, F. Gygi, and G. Galli, *Phys. Rev. Lett*. **92**, 217401 (2004).
8. M. C. Troparevsky, L. Kronik, and J. R. Chelikowsky, *J. Chem. Phys*. **119**, 2284 (2003).
9. R. Jose, N. U. Zhanpeisov, H. Fukumura, Y. Baba, and M. Ishikawa, *J. Am. Chem. Soc*. **128**, 629 (2006).
10. J. Zhao, J. A. Bardecker, A. M. Munro, M. S. Liu, Y. Niu, I.-K. Ding, J. Luo, B. Chen, A. K.-Y. Jen, and D. S. Ginger, *Nano Lett*. **6**, 463 (2006).
11. S. Sen and S. Chakrabarti, *Phys. Rev. B* **74**, 205435 (2006).
12. P. Karamanis, G. Maroulis, and C. Pouchan, *Chem. Phys*. **331**, 19 (2006).
13. S. Sen, P. Seal, and S. Chakrabarti, *Phys. Rev. B* **76**, 115414 (2007).
14. P. N. Prasad and D. J. Williams in *Introduction to Nonlinear Optical Effects in Molecules and Polymers*. Wiley, New York (1991); S. P. Karna and A. T. Yeates in *Nonlinear Optical Materials*, Eds.; ACS Symposium Series 628, American Chemical Society, Washington, DC (1996).
15. M. Jacobsohn and U. Banin, *J. Phys. Chem. B* **104**, 1 (2000).
16. S.-i. Inoue and Y. Aoyagi, *Phys. Rev. Lett*. **94**, 103904 (2005).

17. L. Jensen, P.-O. Astrand, A. Osted, J. Kongsted, and K. V. Mikkelsen, *J. Chem. Phys.* **116**, 4001 (2002).
18. S. K. Pati, S. Ramashesha, Z. Shuai, and J. L. Bredas, *Phys. Rev. B: Condens. Matter* **59**, 14827 (1999).
19. K. B. Sophy and S. Pal, *J. Chem. Phys.* **118**, 10861 (2003); L. D. Freo, F. Terenziani, and A. Painelli, *J. Chem. Phys.* **116**, 755 (2002).
20. S. Grimme, *J. Comput. Chem.* **25**, 1463 (2004); Q. Wu and W. Yang, *J. Chem. Phys.* **116**, 515 (2002).
21. M. Elstner, P. Hobza, T. Frauenheim, S. Suhai, and E. Kaxiras, *J. Chem. Phys.* **114**, 5149 (2001).
22. S. K. Pati, T. J. Marks, and M. A. Ratner, *J. Am. Chem. Soc.* **123**, 7287 (2001); D. Beljonne, Z. Shuai, J. Cornil, D. dos Santos, and J. L. Bredas, *J. Chem. Phys.* **111**, 2829 (1999).
23. J. L. Oudar and D. S. Chemla, *J. Chem. Phys.* **66**, 2664 (1977); J. L. Oudar, *J. Chem. Phys.* **67**, 446 (1977).
24. J. J. Zyss, *Chem. Phys.* **71**, 909 (1979).
25. D. L. Andrews, L. C. Dávila Romero, and W. J. Meath, *J. Phys. B: At. Mol. Opt. Phys.* **32**, 1 (1999).
26. A. Datta and S. K. Pati, *Chem. Soc. Rev.* **35**, 1305 (2006).
27. P. Seal, P. C. Jha, and S. Chakrabarti, *J. Mol. Struct.: Theochem*, **855**, 64 (2008); D. R. Kanis, M. A. Ratner, and T. J. Marks, *Chem. Rev.* **94**, 195 (1994).
28. S. J. A. van Gisbergen, J. G. Snijders, and E. J. Baerends, *J. Chem. Phys.* **109**, 10644 (1998); S. J. A. van Gisbergen, J. G. Snijders, and E. J. Baerends, *J. Chem. Phys.* **109**, 10657 (1998).
29. O. Christiansen, P. JØrgensen, and C. HÄttig, *Int. J. Quantum Chem.* **88**, 1 (1998).
30. K. R. S. Chandrakumar, T. K. Ghanty, and S. K. Ghosh, *Int. J. Quantum Chem.* **105**, 166 (2005).
31. L. Manna, E. C. Scher, and A. P. Alivisatos, *J. Am. Chem. Soc.* **122**, 12700 (2000); J. Li and L. W. Wang, *Nano Lett.* **3**, 1357 (2003).
32. W. U. Huynh, J. J. Dittmer, and A. P. Alivisatos, *Science* **295**, 2425 (2002).
33. O. A. Aktsipetrov, P. V. Elyutin, A. A. Nikulin, and E. A. Ostrovskaya, *Phys. Rev. B* **51**, 17591 (1995).
34. B. S. Santos, G. A. L. Pereira, D. V. Petrov, and C. de Mello Donegá, *Opt. Commun.* **178**, 187 (2000).
35. M. C. Troparevsky and J. R. Chelikowsky, *J. Chem. Phys.* **114**, 943 (2001).
36. P. Karamanis, G. Maroulis, and C. Pouchan, *J. Chem. Phys.* **124**, 071101 (2006).
37. R. van Leeuwen and E. J. Baerends, *Phys. Rev. A* **49**, 2421 (1994).
38. http://www.scm.com
39. A. J. Cohen, N. C. Handy, and D. J. Tozer, *Chem. Phys. Lett.* **303**, 391 (1999).
40. R. M. Dickson and A. D. Becke, *J. Phys. Chem.* **100**, 16105 (1996).
41. D. V. Petrov, B. S. Santos, G. A. L. Pereira, and C. deMello-Donegá, *J. Phys. Chem. B* **106**, 5325 (2002).
42. N. Song, L. Men, J. P. Gao, Y. Bai, A. M. R. Beaudin, G. Yu, and Z. Y. Wang, *Chem. Mater.* **16**, 3708 (2004).
43. P. C. Jha et al., *Comput. Mater. Sci.* **44**, 728 (2008).
44. I. Vasiliev, S. Öğüt, and J. R. Chelikowsky, *Phys. Rev. B* **60**, R8477 (1999).
45. I. Vasiliev, S. Öğüt, and J. R. Chelikowsky, *Phys. Rev. Lett.* **78**, 4805 (1997).
46. R. Schäfer, S. Schlecht, J. Woenckhaus, and J. A. Becker, *Phys. Rev. Lett.* **76**, 471 (1996).
47. M. Zh. Huang and W. Y. Ching, *Phys. Rev. B* **47**, 9464 (1993).
48. Z. H. Levine and D. C. Allan, *Phys. Rev. Lett.* **66**, 41 (1991).
49. D. J. Moss, E. Ghahramani, J. E. Sipe, and H. M. van Driel, *Phys. Rev. B* **41**, 1542 (1990).
50. J. L. Wang, M. L. Yang, G. H. Wang, and J. J. Zhao, *Chem. Phys. Lett.* **367**, 448 (2003).
51. P. P. Korambath and S. P. Karna, *J. Phys. Chem. A* **104**, 4801 (2000).
52. A. C. Pineda and S. P. Karna, *Chem. Phys. Lett.* **429**, 169 (2006).
53. G. Maroulis and C. Pouchan, *J. Phys. Chem. B* **107**, 10683 (2003).
54. B. Champagne, M. Guillaume, D. Bégué, and C. Pouchan, *J. Comput. Methods Sci. Eng.* **7**, 297 (2007).
55. K. D. Bonin and V. V. Kresin, in *Electric Dipole Polarizabilities of Atoms, Molecules and Clusters*, World Scientific, Singapore (1997).
56. E. Benichou, R. Antoine, D. Rayane, B. Vezin, F. W. Dalby, Ph. Dugourd, M. Broyer et al., *Phys. Rev. A* **59**, R1 (1999).
57. G. Maroulis and D. Xenides, *J. Phys. Chem. A* **103**, 4590 (1999).
58. G. Tikhonov, V. Kasperovich, K. Wong, and V. V. Kresin, *Phys. Rev. A* **64**, 063202 (2001).
59. G. Maroulis, *J. Phys. Chem. A* **107**, 6495 (2003).
60. M. B. Knickelbein, *J. Chem. Phys.* **120**, 10450 (2004).
61. M. B. Knickelbein, *J. Chem. Phys.* **115**, 5957 (2001).
62. R. Moro, X. Xu, S. Yin, and W. A. de Heer, *Science* **300**, 1265 (2003).
63. M. G. Papadopoulos, H. Reis, A. Avramopoulos, S. Erkoç, and L. Amirouche, *J. Phys. Chem. B* **109**, 18822 (2005).
64. A. Traverse(a), C. Humbert, C. Six, A. Gayral, and B. Busson, E. *Phys. Lett.* **83**, 64004 (2008).
65. C. Flytzanis, *J. Phys. B* **38**, S661 (2005).
66. W. Chen, Z.-Ru Li, D. Wu, R. Li, and C. Sun, *J. Phys. Chem. B* **109**, 601 (2005).
67. X. Chen, K. Wu, J. G. Snijders, and C. Lin, *Chinese Chem. Lett.* **13**, 893 (2002).
68. Y. Xu, C. Xu, T. Zhou, and C. Cheng, *J. Mol. Struct. Theochem* **893**, 88 (2009).
69. P. Fuentealba, L. P.-Campos, and O. Reyes, *J. Comput. Methods Sci. Eng.* **4**, 589 (2004).
70. M. B. Torres and L. C. Balbás, *J. Comput. Methods Sci. Eng.* **4**, 517 (2004) and references therein.

28

Second-Harmonic Generation in Metal Nanostructures

28.1 Introduction **28**-1
28.2 Nonlinear Optics and Second Harmonic Generation **28**-2
28.3 Second Harmonic Generation in Nanosystems........ **28**-3
Spherical Isolated Particles and Plane-Wave Illumination • Low-Symmetry Particles • Nonuniform Illumination • Second Harmonic Generation in Resonant Metal Particles • Random Metal Nanostructures and Rough Metal Surfaces
28.4 Leading Order Contributions to the Second Harmonic Generation Process in Nanoparticles........ **28**-5
Conservation of Parity and Angular Momentum • Long-Wavelength Limit
28.5 Emission Patterns and Light Polarization **28**-8
Irradiated Intensity • Second Harmonic Polarization
28.6 Allowed and Forbidden Second Harmonic Emission Modes: Examples **28**-9
Plane-Wave Illumination • Illumination with a Laterally Limited Light Beam
28.7 Second Harmonic Generation in Single Gold Nanoparticles........ **28**-11
Near-Field Microscopy Setup • Fundamental Wavelength and Second Harmonic Maps • Second Harmonic Polarization Analysis
28.8 Perspectives........ **28**-15
28.9 Conclusions........ **28**-15
Acknowledgments........ **28**-16
References........ **28**-16

Marco Finazzi
Politecnico di Milano

Giulio Cerullo
Politecnico di Milano

Lamberto Duò
Politecnico di Milano

28.1 Introduction

The explosive growth of nanoscience and nanotechnology during the last decade has led to great interest in the investigation of nanoscale optical fields and to the development of experimental tools for their study (Novotny and Hecht 2006). One of the most remarkable effects in light interaction with metal nanostructures is the strong and spatially localized field amplitude enhancement, due to lightning rod effects induced by the sharp curvatures (Novotny and Hecht 2006) and/or resonant excitation of collective electron oscillations (plasma oscillations) in single or coupled particles (Grand et al. 2003, Mühlschlegel et al. 2005). The resonance frequencies associated with such oscillations and thus the optical properties can be tuned in a broad spectral range according to the material and the shape of the nanostructure. Particularly, gold and silver may sustain plasma oscillations at optical frequencies.

Field enhancements are best observed by exploiting nonlinear optical effects such as second-harmonic generation (SHG) (Smolyaninov et al. 1997, 2000, Jakubczyk et al. 1999, Zayats et al. 2000, Shen et al. 2001, Biagioni et al. 2007, Breit et al. 2007) or two-photon photo-luminescence (TPPL) (Jakubczyk et al. 1999, Bouhelier et al. 2003, 2005, Imura et al. 2005, 2006), which depend on the square of the light intensity, thus amplifying local field variations. To observe a significant nonlinear response, the samples are typically illuminated by high peak intensities, such as those associated with ultrashort laser pulses. Nonlinear optical microscopies, either in the far field or in the near field, are thus becoming powerful tools for the study of nanoscale field enhancements.

SHG was first experimentally demonstrated in 1961 (Franken et al. 1961) and has since then found many applications, especially in converting laser light to a different color. Another application more relevant to the content of this chapter is surface SHG. Although the sensitivity of the SHG process to boundaries was soon recognized (Bloembergen and Pershan 1962), it was only in the early 1980s that nonlinear optical spectroscopy of surfaces and interfaces started to develop as a well-established analysis tool in a wide area of fields (Shen 1989, Mc Gilp 1996, Bloembergen 1999, Lüpke 1999, Downer et al. 2001). The SHG ability to selectively probe surfaces and interfaces derives from a selection rule (see Section 28.2) that does not allow for dipole emission from the bulk of centrosymmetric materials. At the surface or interface, however, the symmetry of the bulk is broken and dipole generation is no longer forbidden. This peculiar property has determined the enormous spread of SHG-based techniques in the community of surface and interface physics. This technique has the advantages of being highly surface-sensitive, capable of remote sensing and in situ measurement, and applicable to any interface between two condensed media accessible by light, even if buried. Among the applications, surface SHG can be used to monitor the growth of monolayers on a surface or to probe the alignment of absorbed molecules.

This chapter presents theoretical and experimental results on SHG from metal nanostructures. It is organized as follows: Section 28.2 contains a brief description of the principles of nonlinear optics and SHG; Section 28.3 presents a survey of the recent literature on SHG from nanostructures; Section 28.4 introduces a theoretical analysis of SHG from nanostructures, allowing to derive selection rules for the process; Section 28.5 describes the light emission patterns and polarization, while Section 28.6 presents experimentally relevant illumination conditions. Section 28.7 reports experimental results on SHG from gold nanoparticles, while Sections 28.8 and 28.9 contain a discussion of possible future developments and conclusions, respectively.

28.2 Nonlinear Optics and Second Harmonic Generation

Nonlinear optics (Shen 1984, Boyd 2003) is the branch of physics that describes the phenomena that occur when the matter is illuminated by very intense light fields that have the capability of modifying its optical properties, thus generating an optical response that is a nonlinear function of the light intensity. Since electric fields strong enough to induce a nonlinear optical response can only be obtained by using the spatially and temporally coherent radiations provided by lasers, the birth of nonlinear optics closely coincides with the invention of the laser.

The physical origins of the nonlinear optical response of a material can be understood by recalling the Lorentz model, in which the atoms/molecules are modeled as harmonic oscillators that, driven by the external light field, become oscillating dipoles emitting light at the same frequencies as the driving field. In a harmonic oscillator, the restoring force is a linear function of displacement; for large displacements, however, nonlinear terms in the restoring force start to become significant, thus leading to an anharmonic oscillation and emission of new frequency components not present in the driving field.

Let us consider an electromagnetic wave crossing a material: the time-varying electric field $E(t)$ induces a time-dependent polarization (dipole moment per unit volume) $P(t)$, which is responsible for light emission. At low light intensities, the polarization is a linear function of the driving field:

$$P(t) = \varepsilon_0 \chi^{(1)} E(t), \tag{28.1}$$

where

ε_0 is the vacuum permittivity

$\chi^{(1)}$ is known as the linear susceptibility

As the intensity increases, further nonlinear terms in which the polarization is proportional to higher powers of the electric field must be considered:

$$P(t) = \varepsilon_0 [\chi^{(1)} E(t) + \chi^{(2)} E^2(t) + \chi^{(3)} E^3(t) + \cdots], \tag{28.2}$$

where the quantities $\chi^{(2)}$ and $\chi^{(3)}$ are known as second- and third-order nonlinear susceptibilities, respectively. By considering the vectorial nature of E and P, $\chi^{(1)}$ becomes a second-rank tensor, $\chi^{(2)}$ a third-rank tensor, and so on.

The $\chi^{(2)}$ term is responsible for second-order nonlinear optical effects, such as sum frequency generation, difference frequency generation, and SHG. The following text briefly describes the SHG process. Let us consider the geometry shown in Figure 28.1a, in which a monochromatic wave at the fundamental frequency ω, $E(t) = E_0 \cos(\omega t)$, impinges on a crystal with nonzero second-order susceptibility. The second-order polarization can then be written as

$$P^{(2)}(t) = \varepsilon_0 \chi^{(2)} E^2(t) = \varepsilon_0 \chi^{(2)} E_0^2 \cos^2(\omega t) = \frac{1}{2} \varepsilon_0 \chi^{(2)} E_0^2 [1 + \cos(2\omega t)]. \tag{28.3}$$



FIGURE 28.1 Scheme of SHG in a nanoparticle: two incoming FW photons are absorbed by the particle and their energy converted in a single photon with double frequency.

The nonlinear polarization thus contains, in addition to a constant term (optical rectification), a component at the second-harmonic (SH) frequency 2ω, which irradiates a field at the corresponding frequency. Note that, since the second-order nonlinear polarization depends on the square of the driving field amplitude E_0, the SHG efficiency is enhanced by high-peak power, pulsed illumination. The SHG process can also have a simple corpuscular interpretation, according to the energy-level scheme reported in Figure 28.1b: two fundamental wavelength (FW) photons at energy $\hbar\omega$ are absorbed to a virtual level of the material, and an SH photon with energy $2\hbar\omega$ is emitted, thus satisfying energy conservation.

In a centrosymmetric medium (i.e., a medium with a center of inversion), the $\chi^{(2)}$ term vanishes identically. In such a medium, in fact, by changing the sign of the driving field, also the sign of the nonlinear polarization must change. By substituting in Equation 28.3, one obtains

$$-P^2(t) = \varepsilon_0\chi^2[-E(t)]^2 = \varepsilon_0\chi^2 E^2(t), \qquad (28.4)$$

which can only be satisfied if $\chi^{(2)} \equiv 0$. Since gases, liquids, amorphous solids, and also several crystals possess an inversion symmetry, the second-order nonlinear susceptibility in such materials is zero, and thus, SHG is forbidden.

At the microscopic level, one can consider the single emitter (atom, molecule) as a nonlinear dipole radiating at the SH frequency 2ω. In order to generate a macroscopic SH signal, the fields emitted by the individual dipoles must interfere constructively, adding their contributions in phase. Since the phase of the nonlinear dipoles depends on the phase of the FW driving field, to achieve constructive interference between the nonlinear emissions at two different positions in the nonlinear medium, one must match the phase velocities of the FW field $v_{\mathrm{pFW}} = \omega/k_{\mathrm{FW}}$ and the SH field $v_{\mathrm{pSH}} = 2\omega/k_{\mathrm{SH}}$. From $v_{\mathrm{pFW}} = v_{\mathrm{pSH}}$, one obtains the condition $k_{\mathrm{SH}} = 2k_{\mathrm{FW}}$, also known as "phase-matching" condition, which implies that $n_{\mathrm{SH}} = n_{\mathrm{FW}}$, where n is the refractive index of the medium. If the phase-matching condition is satisfied, all the microscopic emissions add in phase and the SH field grows linearly (and the intensity quadratically) with the propagation distance. On the other hand, if $\Delta k = k_{\mathrm{SH}} - 2k_{\mathrm{FW}} \neq 0$, the SH field depends on the propagation coordinate x as $E_{\mathrm{SH}} \propto \chi^{(2)} \sin(\Delta k\, x/2)$. It thus increases for propagation up to a "coherence length" L_c such that $\Delta k\, L_c = \pi$, and then starts to decrease due to destructive interference.

Achievement of the phase matching condition is made difficult by the fact that most materials display, in the optical frequency range, a refractive index increasing monotonously with frequency (normal dispersion), so that $n_{\mathrm{SH}} > n_{\mathrm{FW}}$. One can obtain phase-matching condition exploiting the birefringence of noncentrosymmetric crystals, that is, the dependence of the refractive index on the polarization and propagation direction. By polarizing the SH wave along the direction giving the lower refractive index, one can satisfy the condition $n_{\mathrm{SH}} = n_{\mathrm{FW}}$ and thus achieve phase matching. Under such conditions, the SHG process can become so efficient that nearly all the FW power is converted to the SH (Parameswaran et al. 2002).

28.3 Second Harmonic Generation in Nanosystems

As discussed in Section 28.2, SHG is forbidden, within the dipole approximation, from the bulk of a centrosymmetric material but is allowed at its surface, where the inversion symmetry is broken. For this reason, SHG has been extensively applied since its discovery to the investigation of the surface properties of centrosymmetric media. In more recent years, thanks to its surface selectivity, SHG has attracted a considerable interest also as a tool to investigate the properties of nonplanar surfaces that characterize nanoscale systems. The following text presents a survey of the recent literature concerning SHG in nanostructures.

28.3.1 Spherical Isolated Particles and Plane-Wave Illumination

Perfectly spherical small particles made of isotropic material under FW plane-wave illumination represent the simplest geometry to study SHG in nanostructured systems. Experiments have been conducted on spherical dielectric (Wang et al. 1996, Yang et al. 2001, Shan et al. 2006) or metallic (Vance et al. 1998, Nappa et al. 2005) particles dispersed in dilute suspensions, or on colloidal particles, ordered in a centrosymmetric crystalline lattice (Martorell et al. 1997). The influence of the particle diameter (Yang et al. 2001, Nappa et al. 2005, Shan et al. 2006), concentration (Wang et al. 1996, Vance et al. 1998), and the presence of adsorbates (Wang et al. 1996) on SHG have been investigated, by performing angle- and polarization-resolved measurements (Martorell et al. 1997, Yang et al. 2001, Nappa et al. 2005, Shan et al. 2006).

The theory is in good agreement with the experiments, confirming that, when the sphere is small compared with the wavelength of light (Rayleigh limit), the leading-order SH radiation is emitted by a locally excited electric quadrupole and by an electric dipole directed along the direction of the propagation of the incident FW light beam that requires a nonlocal excitation mechanism, in which the phase variation of the pump beam across the sphere needs to be considered (Dadap et al. 1999, 2004). The locally excited electric dipole term, analogous to the source for linear Rayleigh scattering, is absent for the nonlinear case because the FW field induces mutually canceling polarizations at opposite sides of a centrosymmetric spherical particle (Dadap et al. 1999, 2004). The theory predicts the absence of any SHG signal in the forward direction, with both dipole and quadrupole contributions producing SH radiation with an intensity of leading order $(ka)^6$, k being the wave vector and a the particle diameter (Dadap et al. 1999, 2004). Theoretical models have been applied to describe SHG in particles larger than the Rayleigh limit (Dewitz et al. 1996, Pavlyukh and Hübner 2004) and to explicitly account for the electromagnetic response of conducting nanoparticles (Hua and Gersten 1986, Dewitz et al. 1996, Panasyuk et al. 2008).

28.3.2 Low-Symmetry Particles

The fact that SHG is forbidden in the bulk of centrosymmetric materials makes SHG very sensitive to the particle symmetry (Sandrock et al. 1999). For instance, experimental results suggest that SHG can be used to characterize the symmetry and chirality of carbon nanotubes (Su et al. 2008). It has been theoretically (Bachelier et al. 2008) and experimentally demonstrated (Martorell et al. 1997, Nappa et al. 2006) that slight structural deviations from the spherical shape may lead to SH radiation and polarization properties of nanoparticles differing significantly from those of a sphere. For gold particles with a diameter smaller than 50 nm, SHG is dominated by a dipole contribution that is not due to defects in the crystalline structure of the particle but to the deviation of the particle shape from that of a perfect sphere (Nappa et al. 2006, Bachelier et al. 2008). For larger sizes, retardation effects in the interaction of the electromagnetic fields with the particles cannot be neglected any longer, and the response exhibits a strong quadrupolar contribution (Martorell et al. 1997, Nappa et al. 2006).

The importance of local defects in breaking the symmetry of the particles and, consequently, in influencing the SHG process has been verified also in noncentrosymmetric gold nanostructures lithographed on a glass substrate (Canfield et al. 2004, Canfield et al. 2006). SHG from such particles show a high degree of polarization sensitivity and reveals that responses forbidden to ideal, symmetric particles are not only present but are relatively large compared with the allowed response (Canfield et al. 2004). Indeed, with respect to spherical or ellipsoidal nanoparticles, very different polarization selection rules and SH emission directions are obtained when the symmetry of the particle is lowered (Neacsu et al. 2005, Finazzi et al. 2007).

Despite the nonlinear optical properties of a particle are very sensitive to local field enhancement, the presence of very strong fields alone may not be sufficient for efficient SHG from centrosymmetric nanoparticles, as a consequence of the high symmetry selectivity of SHG. An example is SHG from arrays of noncentrosymmetric T-shaped gold nanodimers with a nanogap (Canfield et al. 2007). In this case, SHG arises from asymmetry in the local fundamental field distribution and is not strictly related to the nanogap size, which determines the intensity of the electric field between the dimers. Calculations show that the local field contains polarization components that are not present in the exciting field, which yield the dominant SHG response. The strongest SHG responses occur through the local surface susceptibility of the particles for a fundamental field distributed asymmetrically at the particle perimeters. Weak responses result from more symmetric distributions despite high field enhancement in the nanogap. Nearly constant field enhancement persists for relatively large nanogap sizes (Canfield et al. 2007).

28.3.3 Nonuniform Illumination

The shape of particles participating in the SHG process is not the only geometrical parameter that might affect the SH emission modes and efficiency. Actually, also the spatial distribution of the exciting field can have a great importance to determine the nonlinear response of particles. For instance, for a nonuniform polarizing field, the cancellation of the SH fields generated at opposite sides of a centrosymmetric spherical particle (see Section 28.3.1) is no longer exact and lower order SH emission becomes possible (Brudny et al. 2000). This issue is particularly important since, in practical experimental geometries, the polarizing field is in general neither of a pure longitudinal character nor a simple plane wave, as in the case illumination is performed by focusing the light beam with a microscope objective.

In this context, it is worth mentioning an important application of SHG, namely, second-harmonic imaging microscopy (SHIM), which is a technique used for imaging living cells or tissue by detecting the SHG signal generated by noncentrosymmetric molecules (Campagnola and Loew 2003). By exploiting the quadratic intensity dependence of the SHG signal that confines it to the focal volume, SHIM has the capability of three-dimensional imaging deep within the tissue. SHIM offers several advantages: since it does not rely on absorption from a real electronic state, as in fluorescence microscopy, it does not give rise to photobleaching or phototoxicity. In addition, as it exploits the intrinsic hyperpolarizability of noncentrosymmetric molecules, it is a label-free technique that does not require the use of exogenous probes.

A general theory for the quadratic nonlinear response of a single small nonmagnetic centrosymmetric sphere illuminated by a nonhomogeneous electromagnetic field was developed by Mochán et al. (2003), while general symmetry-based selection rules for SHG with arbitrary illumination are given by Finazzi et al. (2007) and discussed in Section 28.4. The importance of the nature of FW illumination has also been demonstrated experimentally. In fact, it has been shown that the SH radiation generated in Si spherical nanocrystallites displays a peak along the forward direction with a very narrow angular aperture (Jiang et al. 2001, 2002). As explained in Section 28.3.1, this result contradicts the behavior expected for the SH radiation produced by a single sphere illuminated by a plane wave, which should identically vanish along the forward direction (Dadap et al. 1999, 2004). Nevertheless, this observation can be explained (Brudny et al. 2003) by considering the nonuniform illumination FW field distribution, consisting of a strongly focused Gaussian beam. Similarly, in Si nanocrystals embedded uniformly in an SiO_2 matrix, a configuration consisting of two noncollinear, orthogonally polarized FW beams is found to greatly enhance the SHG yield with respect to single-beam illumination (Figliozzi et al. 2005). This effect has been attributed to the strong inhomogeneities in the FW field under double-beam illumination (Figliozzi et al. 2005).

28.3.4 Second Harmonic Generation in Resonant Metal Particles

Although SHG is subject to the same geometry-based selection rules in both metal and dielectric nanoparticles (Finazzi et al. 2007), a relevant difference is represented by the fact that, in metal particles, the linear and nonlinear optical properties are governed by collective electronic excitations (plasma oscillations), which can be tuned in a broad spectral range by choosing the proper particle geometry. In nanosystems, the quasiparticles associated with the collective electron excitations are often addressed to as localized surface plasmons (LSPs), or as localized plasmon polaritons, to indicate the associated electric field. In particular, depending on the size and the shape, metal particles made of gold and silver may display LSP resonance in the visible region. Thanks to this tunability, the nonlinear optical properties of noble-metal nanoparticles have found applications for in vitro and in vivo imaging (Nagesha et al. 2007), high-resolution analysis of tumor tissues (Durr et al. 2007, Bickford et al. 2008, Park et al. 2008), and enhanced photothermal therapies (O'Neal et al. 2004, El-Sayed et al. 2006).

A relevant enhancement of the SHG efficiency is observed when either the FW (Hubert et al. 2007) or the SH (Antoine et al. 1997, 1998, Hao et al. 2002, Johnson et al. 2002, Abid et al. 2004, Russier-Antoine et al. 2004) frequency is set at the LSP resonance of the nanoparticles. When the SH wavelength is tuned in the vicinity of the surface plasmon resonance, the wavelength analysis indicates that the interband transitions do not play a significant role in the total SH response (Antoine et al. 1998). Rather, the nonlinear optical behavior of the clusters is dominated by the free-electron gas-like response of the conduction band, the surface plasmon resonance being much sharper than the interband transition contribution (Antoine et al. 1998, Russier-Antoine et al. 2004). Similarly, the SHG efficiency as a function of the FW frequency shows a curve that reproduces the LSP resonance (Hubert et al. 2007). Both electric dipole and electric quadrupole contributions to the SH-radiated power are observed (Hao et al. 2002).

28.3.5 Random Metal Nanostructures and Rough Metal Surfaces

The strong local field enhancements in random metal nanoparticles and rough metal surfaces can be exploited to improve the efficiency of the interaction of light with molecules approached to such nanostructures (Hartschuh et al. 2003), a phenomenon that can be exploited in surface-enhanced spectroscopies to obtain single-molecule sensitivity. Among these, surface-enhanced Raman scattering (SERS) makes use of the excitation provided by LSP and high local fields in such structures to enhance the Raman emission of adsorbed molecules by several orders of magnitudes (generally 10^6, up to 10^{12}). Surface enhanced spectroscopies such as SERS are, therefore, intimately correlated with the plasmon properties of the nanostructures, offering, at the same time, unique potential for ultrasensitive molecular identification (Nie and Emery 1997). LSP-based nanosensors of biomolecules, based on the shift of the plasmon resonance frequency of thin metallic films, have been developed and are already commercially available.

Since SHG is extremely sensitive to both local fields and LSP resonances, both theoretical (Agarwal and Jha 1982, Stockman et al. 2004, Beermann et al. 2006, Singh and Tripathi 2007) and experimental studies performed with either far-field (Bozhevolnyi et al. 2003, Beermann and Bozhevolnyi 2004) or near-field techniques (Smolyaninov et al. 1997, Zayats et al. 2000) have addressed the SHG process in such disordered systems characterized by LSP interacting with local defects. The latter act as plasmon-scattering centers and might also provide highly localized electric fields due to the lightning rod effect. LSP resonances emerge as a consequence of multiple interparticle light scattering (Stockman et al. 2004, Beermann et al. 2006) and exhibit very different strength, phase, polarization, and localization characteristics (Bozhevolnyi et al. 2003, Beermann and Bozhevolnyi 2004). SH emission is experimentally observed from small and very bright spots, whose locations depend on the light wavelength (Bozhevolnyi et al. 2003) and polarization (Zayats et al. 2000, Bozhevolnyi et al. 2003). According to simulations (Stockman et al. 2004), the spatial distributions of the fundamental frequency and SH local fields are very different, with highly enhanced SH hot spots corresponding to areas where FW and SH eigenmodes overlap (Beermann et al. 2006). Another feature of SHG in rough metal surfaces is that SH fields show a very rapid spatial decay and are strongly depolarized and incoherent (Stockman et al. 2004).

28.4 Leading Order Contributions to the Second Harmonic Generation Process in Nanoparticles

As illustrated in Section 28.3, the shape of the nanoparticle plays a significant role in determining the conditions for efficient SHG, which can also be significantly influenced by the illumination geometry. The latter represents a particularly important point that needs to be considered when microscopic techniques are employed to locally study field-enhancement processes. In this case, the FW illumination is not a plane wave anymore, and strong field gradients (and even a nonvanishing longitudinal field component when scanning near-field optical microscopy (SNOM) is used) can be present in the illumination area. Although nanoscale SHG has already been discussed in the literature for few particle geometries excited by either far (Zhu 2007, Dadap 2008) or near (Bozhevolnyi and Lozovski 2000, 2002) FW fields, a set of general validity selection rules for SHG might be helpful in addressing more complicated particle geometries and FW field distributions. The following text addresses the concepts that allow one to derive selection rules for SHG in isolated nanoparticles from angular momentum and parity conservation laws, as discussed by Finazzi et al. (2007).

28.4.1 Conservation of Parity and Angular Momentum

In the rest reference frame of the particle, the SHG process consists of two photons, belonging to the FW field interacting with the particle, that transfer their energy to a photon in the SH field oscillating at double frequency (see Figure 28.1b). Therefore, the energy of the electromagnetic field is conserved and the particle is left in the ground state, that is, the particle initial and final states in the SHG process coincide. This fact has relevant consequences if the particle is symmetric. In this case, the particle ground state is an eigenstate of parity and, possibly, angular momentum operators. In other words, the particle has a well-defined parity (or angular momentum). Since the particle initial and final states are the same, the electromagnetic field cannot transfer parity or angular momentum quanta to the particle, and the total parity or angular momentum of the field will be conserved. These concepts can be expressed more formally by considering the explicit expression of the SHG process cross section σ. By using perturbation theory, σ can be expressed as a third-order term of the form

$$\sigma \propto \left| \sum_{u,w} \frac{\langle \varphi_0 | \hat{\mathbf{p}} \cdot \mathbf{A}_{\omega} | u \rangle \langle u | \hat{\mathbf{p}} \cdot \mathbf{A}_{\omega} | w \rangle \langle w | \hat{\mathbf{p}} \cdot \mathbf{A}_{2\omega} | \varphi_0 \rangle}{[(E_u - E_0) - \omega + i\Gamma_u][(E_w - E_u) - \omega + i\Gamma_w]} + \frac{\langle \varphi_0 | \hat{\mathbf{p}} \cdot \mathbf{A}_{\omega} | u \rangle \langle u | \hat{\mathbf{p}} \cdot \mathbf{A}_{2\omega} | w \rangle \langle w | \hat{\mathbf{p}} \cdot \mathbf{A}_{\omega} | \varphi_0 \rangle}{[(E_u - E_0) - \omega + i\Gamma_u][(E_w - E_u) + 2\omega]} + \frac{\langle \varphi_0 | \hat{\mathbf{p}} \cdot \mathbf{A}_{2\omega} | u \rangle \langle u | \hat{\mathbf{p}} \cdot \mathbf{A}_{\omega} | w \rangle \langle w | \hat{\mathbf{p}} \cdot \mathbf{A}_{\omega} | \varphi_0 \rangle}{[(E_u - E_0) + 2\omega][(E_w - E_u) - \omega + i\Gamma_w]} \right|^2, \qquad (28.5)$$

where

φ_0 is the particle ground state

u and w are eigenfunctions corresponding to excited states of the unperturbed particle

E_0, E_u, and E_w are the corresponding energies

Equation 28.5 consists of the sum of three terms, each corresponding to one of the Feynman diagrams shown in Figure 28.2. In the expression for σ, $\hat{\mathbf{p}}$ is the particle momentum operator, $\mathbf{A}_{2\omega}$ the SH vector potential, and $\mathbf{A}_{\omega}$ the vector potential of the *externally applied* FW field. Note that the field generated by the particle should not be added to $\mathbf{A}_{\omega}$ in Equation 28.5. In fact, the particle self-interactions, that is, the interactions between the particle and the electromagnetic field the particle produces are accounted for by u and w, which describe the electronic as well as the electromagnetic excitations of the particle. Retardation effects that play an important role in determining SHG in nanoparticles (Dadap et al. 1999, 2004) are therefore implicitly accounted for in Equation 28.5.

As far as parity and angular momentum are concerned, it is convenient to expand the FW and SH fields appearing in Equation 28.5 in terms of electric (E) and magnetic (M) multipoles, which represent the photon angular momentum eigenstates. Let L'_{ω} and L''_{ω} be the L^2 quantum numbers of the two FW absorbed photons, M'_{ω} and M''_{ω} their L_z quantum numbers, z being an arbitrary quantization axis, and $L_{2\omega}$ and $M_{2\omega}$ the respective quantum numbers for the emitted SH photon (see Figure 28.3). The Feynman diagram in Figure 28.2a gives a contribution to Equation 28.5 that can be expressed as the sum of T terms defined as follows:

$$T^{u,w}_{L'_{\omega},M'_{\omega},L''_{\omega},M''_{\omega},L_{2\omega},M_{2\omega}} \propto \langle \varphi_0 | \hat{\mathbf{p}} \cdot \mathbf{A}(L'_{\omega}, M'_{\omega}) | u \rangle \langle u | \hat{\mathbf{p}} \cdot \mathbf{A}(L''_{\omega}, M''_{\omega}) | w \rangle \langle w | \hat{\mathbf{p}} \cdot \mathbf{A}(L_{2\omega}, -M_{2\omega}) | \varphi_0 \rangle, \qquad (28.6)$$

where $\hat{\mathbf{p}} \cdot \mathbf{A}(L, M)$ represents the electric or magnetic multipole operator of order (L, M). $M_{2\omega}$ is taken with a negative sign since the emitted SH photon carries the corresponding L_z angular momentum component *away* from the particle. Similar terms can be given for the other Feynman diagrams in Figure 28.2. Each T term corresponds to an SHG interaction involving FW and SH photons characterized by a well-defined total angular momentum.

The selection rules that determine the conditions for which a given T term is identically zero depend on how the multipoles in Equation 28.6 transform under the particle symmetry group operations. When the particle has spherical symmetry, its ground as well as excited states are eigenstates of both L^2 and L_z. Therefore, the SH photon must carry away a total angular momentum equal to the sum of the angular momenta of the two FW incoming photons. In cylindrical symmetry, only the projection of the photon angular momentum along the symmetry axis (taken as the quantization axis z) needs to be conserved. The photon parity must be conserved in the case the particle displays inversion symmetry. If the particle is invariant under inversion symmetry with respect to a point (S_2 symmetry in Schoenflies notation, see Tinkham (1964)), then electric and magnetic multipoles of



(a) (b) (c)

FIGURE 28.2 The three Feynman diagrams corresponding to SHG. (Reprinted from Finazzi, M. et al., *Phys. Rev. B*, 76, 125414, 2007. With permission.)



FIGURE 28.3 Scheme of SHG reporting the L and M quantum numbers that define the angular momentum and parity of the photons involved in the process.

order (L, M) have opposite contributions to the total parity of the electromagnetic field, equal to $(-1)^L$ and $(-1)^{L+1}$, respectively (Jackson 1975). In the case the particle displays inversion symmetry (C_2 symmetry) with respect to the quantization axis, electric and magnetic multipoles have the same parity, given by $(-1)^M$ (Jackson 1975). Finally, considering inversion with respect to a plane perpendicular to the quantization axis (C_{1h} symmetry), the parity of electric and magnetic multipoles of order (L, M) is given by $(-1)^{L+M}$ and $(-1)^{L+M+1}$, respectively (Jackson 1975).

By considering the electromagnetic field conservation laws imposed by the particle symmetry and contributions to angular momentum and parity associated with each multipole, one can obtain the selection rules listed in Table 28.1, which allow to determine the nonvanishing T terms that contribute to the SGH process for any combination of FW and SH multipoles (Finazzi et al. 2007). Thus, to apply the selection rules listed in Table 28.1, one has to determine the multipole expansion of the impinging FW electromagnetic field in order to understand which SH multipoles can contribute to the generated SH radiation.

TABLE 28.1 SHG Selection Rules for the Different Particle Symmetries Illustrated in Figure 28.4

Symmetry and Point Group	Selection Rule
Spherical	$\begin{pmatrix} L'_\omega & L''_\omega & L_{2\omega} \\ M'_\omega & M''_\omega & -M_{2\omega} \end{pmatrix} \neq 0$ and
	$(-1)^{L'_\omega+L''_\omega+L_{2\omega}+m} = 1$
Cylindrical	$M'_\omega + M''_\omega - M_{2\omega} = 0$
Central, S_2	$(-1)^{L'_\omega+L''_\omega+L_{2\omega}+m} = 1$
Axial, C_2	$(-1)^{M'_\omega+M''_\omega-M_{2\omega}} = 1$
Reflection, C_{1h}	$(-1)^{L'_\omega+M'_\omega+L''_\omega+M''_\omega+L_{2\omega}-M_{2\omega}+m} = 1$

Source: Reprinted from Finazzi, M. et al., *Phys. Rev. B*, 76, 125414, 2007. With permission.

Note: Conservation of angular momentum for spherical symmetry corresponds to a condition involving a 3-j symbol (Tinkham 1964). The value m indicates the number of *magnetic* multipole transitions involved in the T term.



FIGURE 28.4 The particle symmetry groups discussed in the text and referred to the quantization axis z: (a) spherical, (b) cylindrical, (c) central, (d) axial, and (e) reflection symmetries across a mirror plane perpendicular to z. (Reprinted from Finazzi, M. et al., *Phys. Rev. B*, 76, 125414, 2007. With permission.)

If the symmetry of the particle results from a combination of symmetry groups, the corresponding conditions listed in Table 28.1 must be satisfied at the same time. For instance, SHG from particles with C_{2h} symmetry must obey both the selection rules for axial (C_2) and reflection (C_{1h}) symmetries with respect to the same quantization axis. For the same reason, when the particle exhibits two or three orthogonal symmetry axes, the corresponding selection rules must be simultaneously satisfied by the field multipole expansions expressed by using each symmetry axis as the quantization axis.

Note that, strictly speaking, the spherical and cylindrical symmetry groups would have to be excluded since they are not compatible with any of the symmetry properties of the various Bravais lattices. Moreover, crystallographic defects (such as grain boundaries, dislocations, and atomic vacancies) would disrupt the internal symmetry of the particles. Thus, it would seem that symmetry-based selection rules would not be respected by SHG in real nanostructures. However, such limitations are not expected to play a significant role in the metal structures that are usually investigated in nano-optics (Finazzi et al. 2007), which are typically realized in aluminum, silver, or gold. The electronic and electromagnetic properties of these materials are in fact well described by the free-electron model, so that the particle symmetry properties are independent from the particle crystallography but are just determined by the boundary conditions imposed by the particle surface.

28.4.2 Long-Wavelength Limit

In general, selection rules allow one to discriminate the transitions that, for symmetry reasons, cannot contribute to the cross section of a particular physical phenomenon, but they do not give any information about the magnitude of the nonvanishing contributions. However, by considering the multipole expansion of the electromagnetic FW and SH fields in the SHG process, it is possible not only to identify the emission channels that are ineffective to SHG but also to estimate a hierarchy among them, identifying the ones that mostly contribute to the SHG process. This is possible in the long-wavelength limit (Rayleigh limit) characterized by $ka \ll 1$, with k being the FW wave vector and a the particle lateral size. In fact, matrix elements of the form $\langle u \mid \hat{\mathbf{p}} \cdot \mathbf{A}(L,M) \mid w \rangle$ rapidly decrease when the multipole order L is increased (Jackson 1975). The ratio $R(L)$ between matrix elements for successive orders, L and (L + 1), of either electric or magnetic multipoles of the same frequency is

$$R(L) \sim \frac{ka}{2L}, \tag{28.7}$$

while the magnetic multipoles of order L have cross sections of the same order in ka as electric multipoles of order $(L + 1)$ (Jackson 1975, Dadap et al. 2004). Since the expression of the SHG cross section σ reported in Equation 28.5 depends on the square value of the sum of products involving three matrix elements, we need to consider only the contributions associated with the lowest order multipoles.

By restricting the analysis to the lowest order terms, five distinct SHG emission modes can be indicated. Following the notation in Dadap et al. (2004), these are E1 + E1 → E1, E1 + E2 → E1, E1 + M1 → E1, E1 + E1 → E2, and E1 + E1 → M1. In this notation, the first two symbols refer to the nature of the interaction with the FW field, and the third symbol describes the SH emission. For example, the E1 + E2 → E1 interaction represents electric dipole (E1) SH emission that arises through combined FW electric dipole and electric quadrupole (E2) excitations. M1 indicates a magnetic dipole transition. The E1 + E1 → E1 transition corresponds to the leading order contribution to the SHG process, generating an SH field with a magnitude of a factor $(ka)^{-1}$ higher than the field generated by the other terms, resulting in a $(ka)^{-2}$ higher irradiated power. The E1 + E1 → E1 interaction violates parity conservation for any incident FW field distribution on centrosymmetric particles since $(-1)^{L'_\omega + L''_\omega + L_{2\omega}} = (-1)^{1+1+1} = -1$, thus violating the selection rule for S_2 symmetry particles reported in Table 28.1. This channel may, however, be allowed for lower symmetry particles.

28.5 Emission Patterns and Light Polarization

The emission modes that participate in the SHG process can be experimentally identified by considering SH emission pattern and light polarization. In fact, each multipole contributing to the SHG process is characterized by a well-defined angular dependence of the irradiated intensity and polarization.

28.5.1 Irradiated Intensity

Let $\mathbf{k}_{2\omega}$ be the SH wave vector and $\mathbf{r}$ the position with respect to the particle. According to Jackson (1975), in the far-field limit characterized by $k_{2\omega} \gg r^{-1}$, the SH electric fields $\mathbf{E}^{(\mathrm{E})}_{L_{2\omega}M_{2\omega}}(\mathbf{r})$ and $\mathbf{E}^{(\mathrm{M})}_{L_{2\omega}M_{2\omega}}(\mathbf{r})$, produced by either electric or magnetic multipoles of order $(L_{2\omega}, M_{2\omega})$, are given by

$$\mathbf{E}^{(E)}_{L_{2\omega},M_{2\omega}}(\mathbf{r}) = -(-i)^{(L_{2\omega}+1)} \frac{e^{ik_{2\omega}r}}{k_{2\omega}r} (\hat{\mathbf{u}}_r \times \mathbf{r} \times \nabla Y_{L_{2\omega},M_{2\omega}}), \qquad (28.8a)$$

$$\mathbf{E}^{(M)}_{L_{2\omega},M_{2\omega}}(\mathbf{r}) = -(-i)^{(L_{2\omega}+1)} \frac{e^{ik_{2\omega}r}}{k_{2\omega}r} (\mathbf{r} \times \nabla Y_{L_{2\omega},M_{2\omega}}). \qquad (28.8b)$$

In Equations 28.8 $\hat{\mathbf{u}}_r$ is a unit vector in the radial direction, and $Y_{L_{2\omega},M_{2\omega}}$ is the spherical harmonic of order $(L_{2\omega}, M_{2\omega})$. Pure electric and magnetic SH multipoles have the same angular distribution of the time-averaged radiated power per solid angle $\mathrm{d}P/\mathrm{d}\Omega(L_{2\omega}, M_{2\omega})$. A graphical representation of the radiated power is given in Figure 28.5 for dipoles ($L_{2\omega} = 1$) and quadrupoles ($L_{2\omega} = 2$) (Jackson 1975). If more than a single multiplet is responsible for the generation of SH radiation, interference among the SH radiation emitted by the contributing multipoles occurs and the emission pattern can be significantly different from those in Figure 28.5. In such cases, identifying the multipoles that are responsible for the SH emission might be quite complicated. Further information, however, can be extracted by analyzing the polarization dependence of the SH radiation as a function of the polarization of the impinging FW field.


z
z
$L_{2\omega} = 1, M_{2\omega} = 0$
$L_{2\omega} = 1, M_{2\omega} = \pm 1$
z
z
z
$L_{2\omega} = 2, M_{2\omega} = 0$
$L_{2\omega} = 2, M_{2\omega} = \pm 1$
$L_{2\omega} = 2, M_{2\omega} = \pm 2$

FIGURE 28.5 Graphical representation of emission patterns $\mathrm{d}P/\mathrm{d}\Omega(L_{2\omega}, M_{2\omega})$ for dipoles (upper row) and quadrupoles (lower row). The time-averaged radiated power per unit solid angle displays cylindrical symmetry around the quantization axis z. (Reprinted from Finazzi, M. et al., *Phys. Rev. B*, 76, 125414, 2007. With permission.)

28.5.2 Second Harmonic Polarization

From Equations 28.8, one can also obtain the polarization state of the emitted SH light. Table 28.2 reports the direction of the electric far field for pure electric and magnetic multipoles with $L_{2\omega} \leq 2$. The direction is indicated by a combination of the mutually perpendicular unit vectors $\hat{\mathbf{u}}_\theta$ and $\hat{\mathbf{u}}_\phi$ defined in a spherical coordinate system centered on the particle, in which θ and ϕ are the polar and azimuthal angles, respectively, the former being referred to the z quantization axis. An imaginary (real) ratio between the coefficients of $\hat{\mathbf{u}}_\theta$ and $\hat{\mathbf{u}}_\phi$ corresponds to a $\pi/2$ (zero) phase difference between the two field components and hence indicates elliptical (linear) polarization (Jackson 1975).

TABLE 28.2 SH Electric Field Polarization for Pure Electric or Magnetic Multipoles with $L_{2\omega} \leq 2$

	$M_{2\omega} = 0$	$M_{2\omega} = \pm 1$	$M_{2\omega} = \pm 2$
$L_{2\omega} = 1\ (E)$	$\sin\theta\hat{\mathbf{u}}_\theta$	$e^{\pm i\phi}(\pm\cos\theta\hat{\mathbf{u}}_\theta \mp i\hat{\mathbf{u}}_\phi)$	
$L_{2\omega} = 1\ (M)$	$\sin\theta\hat{\mathbf{u}}_\phi$	$-e^{\pm i\phi}(i\hat{\mathbf{u}}_\theta \mp \cos\theta\hat{\mathbf{u}}_\phi)$	
$L_{2\omega} = 2\ (E)$	$-i\sin\theta\cos\theta\hat{\mathbf{u}}_\theta$	$e^{\pm i\phi}(\mp i\cos 2\theta\hat{\mathbf{u}}_\theta + \cos\theta\hat{\mathbf{u}}_\phi)$	$e^{\pm 2i\phi}\sin\theta(i\cos\theta\hat{\mathbf{u}}_\theta \pm \hat{\mathbf{u}}_\phi)$
$L_{2\omega} = 2\ (M)$	$-i\sin\theta\cos\theta\hat{\mathbf{u}}_\phi$	$-e^{\pm i\phi}(\cos\theta\hat{\mathbf{u}}_\theta + i\cos 2\theta\hat{\mathbf{u}}_\phi)$	$e^{\pm 2i\phi}\sin\theta\,(\pm\hat{\mathbf{u}}_\theta + i\cos\theta\hat{\mathbf{u}}_\phi)$

Source: Reprinted from Finazzi, M. et al., *Phys. Rev. B*, 76, 125414, 2007. With permission.

Note: For each point in space, the unit vectors $\hat{\mathbf{u}}_\theta$ and $\hat{\mathbf{u}}_\phi$ are, respectively, parallel and perpendicular to the plane containing the z (quantization) axis, and are both perpendicular to the radial unit vector $\hat{\mathbf{u}}_r$.

28.6 Allowed and Forbidden Second Harmonic Emission Modes: Examples

This section discusses some examples of applications of the arguments discussed above. Two relevant cases of FW illumination are addressed, namely, illumination with a plane wave and illumination with a strongly laterally limited beam, for example, through a high numerical aperture or via a near-field tip.

28.6.1 Plane-Wave Illumination

In an arbitrarily polarized FW plane wave propagating along the z direction, the field vector $\mathbf{A}(z)$ can be expressed as $\mathbf{A}(0)e^{ikz}$, with $\mathbf{A}(0)$ being a vector perpendicular to the propagation direction, $\mathbf{A}(0)\cdot\hat{\mathbf{u}}_z = 0$. By taking the origin of the z axis coincident with the particle position, and truncating the multipole expansion around $z = 0$ of the matrix element $\langle u \mid \hat{\mathbf{p}} \cdot \mathbf{A} \mid w\rangle$ to second order in ka, one obtains

$$\langle u|\hat{\mathbf{p}}\cdot\mathbf{A}|w\rangle \frac{E_w - E_u}{\hbar\omega}\langle u|\mathbf{r}\cdot\mathbf{E}(0)|w\rangle + \langle u|\hat{\mathbf{L}}\cdot\mathbf{B}(0)|w\rangle$$
$$+ ik\langle u|\hat{p}_z[xA_x(0) + yA_y(0)]|w\rangle. \tag{28.9}$$

In this expression, $\mathbf{E}(0)$ and $\mathbf{B}(0)$ are complex vectors representing the amplitude and phase of the electric and magnetic fields, respectively, at the particle position, while $A_x(0)$ and $A_y(0)$ are the complex components of $\mathbf{A}(0)$, and $\hat{\mathbf{L}} = \mathbf{r} \times \hat{\mathbf{p}}$. The three terms on the right-hand side of Equation 28.9 correspond to E1, M1, and E2 transitions, respectively.

Let us first discuss the case of circularly polarized light. In this case, it can be shown (Finazzi et al. 2007) that all the three FW absorption transitions described by the matrix elements in Equation 28.9 involve FW photons characterized by an L_z quantum number M_ω either equal to +1 or −1 according to the sign of the circular polarization (right or left) of the FW light impinging on the particle. By recalling that dipole terms are characterized by $L^2 = 1$ and quadrupole terms by $L^2 = 2$, the lowest allowed emission multipoles participating in the SHG process can be obtained from Table 28.1 in a straightforward manner. The allowed SH emission modes are listed in Table 28.3. As anticipated above, the lowest order transition E1 + E1 → E1 is forbidden under circularly polarized FW plane-wave illumination for particles displaying central symmetry, but it is allowed for noncentrosymmetric, noncylindrical particles. In this case, SH emission is given by an E1 term with $M_{2\omega} = 0$ or $M_{2\omega} = \pm 1$ for C_2 or C_{1h} symmetry, respectively. This emission mode corresponds to SHG from an electric dipole oriented parallel (for C_2 symmetry) or perpendicular (in the case of C_{1h} symmetry) to z. The lowest allowed SHG channel for spherical or cylindrical particles is E1 + E1 → E2 (Dadap et al. 1999, 2004), with $M_{2\omega} = \pm 2$. This SH emission mode corresponds to an irradiated SH power angular distribution displaying cylindrical symmetry around the propagation axis of the FW field, with a maximum in the plane perpendicular to z and a null in the forward and backward directions (Dadap et al. 1999, 2004), as displayed in Figure 28.5.

In the case of linearly polarized FW illumination, it is convenient to consider the selection rules that can be obtained by considering both the propagation direction of the FW plane wave (z axis) and the direction of the FW electric field vector (x axis) as the quantization axis. Therefore, one should calculate two multipole expansions of the FW wave, one for each choice of the quantization axis, and consider the possible values of both the L_z and L_x photon quantum numbers. Moreover, both axes should be taken into account to define the particle symmetry group. Let M_ω and $M_{2\omega}$ be the FW and SH photon L_z quantum numbers, and N_ω and $N_{2\omega}$ be the FW and SH photon L_x quantum numbers, respectively. It can be shown (Finazzi et al. 2007) that the multipole expansion

TABLE 28.3 SHG Selection Rules for the Different Particle Symmetries Illustrated in Figure 28.4, under Circularly Polarized Far-Field Plane-Wave Illumination

Symmetry and Point Group	E1 + E1 → E1	E1 + E1 → E2	E1 + E2 → E1	E1 + M1 → E1	E1 + E1 → M1
Spherical	Forbidden	Allowed for $M_{2\omega} = +2$ or -2	Forbidden	Forbidden	Forbidden
Cylindrical	Forbidden	Allowed for $M_{2\omega} = +2$ or -2	Forbidden	Forbidden	Forbidden
Central, S_2	Forbidden	Allowed	Allowed	Allowed	Allowed
Axial, C_2	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0, \pm 2$	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0$
Reflection, C_{1h}	Allowed for $M_{2\omega} = \pm 1$	Allowed for $M_{2\omega} = 0, \pm 2$	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0$

Source: Reprinted from Finazzi, M. et al., *Phys. Rev. B*, 76, 125414, 2007. With permission.

Note: Every transition multipole is considered separately. The propagation direction (z axis) is chosen as the quantization axis.

TABLE 28.4 SHG Selection Rules for the Different Particle Symmetries Illustrated in Figure 28.4, under Linearly Polarized Far-Field Plane-Wave Illumination

Symmetry and Point Group	E1 + E1 → E1	E1 + E1 → E2	E1 + E2 → E1	E1 + M1 → E1	E1 + E1 → M1
Spherical	Forbidden	Allowed for $M_{2\omega} = 0, \pm 2$	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0$	Forbidden
Cylindrical	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0, \pm 2$	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0$	Forbidden
Central, S_2	Forbidden	Allowed	Allowed	Allowed	Allowed
Axial, C_2	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0, \pm 2$	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0$
Reflection, C_{1h}	Allowed for $M_{2\omega} = \pm 1$	Allowed for $M_{2\omega} = 0, \pm 2$	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0$	Allowed for $M_{2\omega} = 0$

Source: Reprinted from Finazzi, M. et al., *Phys. Rev. B*, 76, 125414, 2007. With permission.
Note: The propagation direction (z axis) is chosen as the quantization axis.

TABLE 28.5 SHG Selection Rules for the Different Particle Symmetries Illustrated in Figure 28.4, under Linearly Polarized Far-Field Plane-Wave Illumination

Symmetry and Point Group	E1 + E1 → E1	E1 + E1 → E2	E1 + E2 → E1	E1 + M1 → E1	E1 + E1 → M1
Spherical	Forbidden	Allowed for $N_{2\omega} = 0$	Allowed for $N_{2\omega} = \pm 1$	Allowed for $N_{2\omega} = \pm 1$	Forbidden
Cylindrical	Allowed for $N_{2\omega} = 0$	Allowed for $N_{2\omega} = 0, \pm 2$	Allowed for $N_{2\omega} = \pm 1$	Allowed for $N_{2\omega} = \pm 1$	Allowed for $N_{2\omega} = 0$
Central, S_2	Forbidden	Allowed	Allowed	Allowed	Allowed
Axial, C_2	Allowed for $N_{2\omega} = 0$	Allowed for $N_{2\omega} = 0, \pm 2$	Allowed for $N_{2\omega} = \pm 1$	Allowed for $N_{2\omega} = \pm 1$	Allowed for $N_{2\omega} = 0$
Reflection, C_{1h}	Allowed for $N_{2\omega} = \pm 1$	Allowed for $N_{2\omega} = 0, \pm 2$	Allowed for $N_{2\omega} = \pm 1$	Allowed for $N_{2\omega} = \pm 1$	Allowed for $N_{2\omega} = 0$

Source: Reprinted from Finazzi, M. et al., *Phys. Rev. B*, 76, 125414, 2007.
Note: The electric field polarization direction (x axis) is chosen as the quantization axis.

of the FW plane wave corresponds to E1, M1, and E2 terms in Equation 28.9 that involve FW photons with an M_ω quantum number that can be either +1 or −1 but not 0. On the other hand, the expansion obtained by choosing the x axis as the quantization axis shows that the E1, M1, and E2 terms correspond to transitions involving FW photons with L^2 and L_x quantum numbers restricted to ($L_\omega = 1$, $N_\omega = 0$), ($L_\omega = 1$, $N_\omega = \pm 1$), and ($L_\omega = 2$, $N_\omega = \pm 1$), respectively. With these figures in mind and the general rules summarized in Table 28.1, one can find the selection rules listed in Tables 28.4 and 28.5. From these, one can see that the E1 + E1 → E1 SHG channel can be excited by linearly polarized FW plane-wave illumination in all noncentrosymmetric particles (Finazzi et al. 2007). In particular, if the particle exhibits C_2 symmetry either around the z or the x axis, SH emission will be given by an oscillating dipole parallel to the C_2 symmetry axis (Finazzi et al. 2007). In centrosymmetric particles illuminated by linearly polarized light, electric dipole SH emission is always given by a dipole parallel to z, while the quadrupole SH emission pattern is symmetric around x (see Figure 28.4) (Finazzi et al. 2007). M1 emission is forbidden (Dadap et al. 1999, 2004) because the selection rules would lead to $M_{2\omega} = N_{2\omega} = 0$, which correspond to a monopole term that cannot radiate (Finazzi et al. 2007).

28.6.2 Illumination with a Laterally Limited Light Beam

When the particle is illuminated by a laterally limited FW beam, which might be obtained by focusing with a high numerical-aperture objective or even with near-field illumination, and the beam waist is comparable with the particle size, the beam cannot be considered as a plane wave any longer. In this case, other emission channels than those listed in Tables 28.3 through 28.5 become available. In these conditions, in fact, the particle experiences large longitudinal components of the FW field, which are absent in the case of illumination with a plane wave. The presence of such longitudinal components can be easily understood for a converging beam focused by an objective, where the FW light wave vector **k** has a broad angular distribution determined by the objective numerical aperture. Intense longitudinal components should also be expected in the proximity of near-field probes (Novotny and Hecht 2006). The consequence is that SHG can be induced by a combined FW photon absorption from perpendicular field components acting on the particle (Figliozzi et al. 2005), which is not possible for plane-wave illumination. For instance, illuminating with a laterally confined beam, absorption of FW photons with L_z quantum number $M_\omega = 0$ from a linearly polarized FW field becomes possible, which is excluded for plane-wave illumination (Finazzi et al. 2007). For the same reason, FW photons with $M_\omega = 0, \pm 1, \pm 2$ are available for E2 absorption (Finazzi et al. 2007).

Another important difference with respect to in-plane wave illumination is represented by the fact that the rapid spatial variations of the field intensity can increase the relative weight of the higher-order multipoles in the SHG process. This is readily understood in far-field illumination when the spot size, which is limited by diffraction to about $1/k$, is comparable with the particle size a, resulting in a violation of the long-wavelength approximation. Similarly, strong field gradients are expected at the apex of a near field probe (Novotny and Hecht 2006), again invalidating the long-wavelength approximation and implying that high-order multipoles cannot be a priori neglected.



FIGURE 28.6 Allowed E1 second-harmonic emission channels for a particle with C_2 symmetry (axial particle over a substrate) excited by (a) a plane wave or (b) a laterally limited beam. The allowed directions of the particle electric dipole $q_{2\omega}$ generating the E1 second-harmonic radiation are indicated by the double-headed arrows on the particle. (Reprinted from Finazzi, M. et al., *Phys. Rev. B*, 76, 125414, 2007. With permission.)

As a relevant example, let us address SHG in lithographed particles on a substrate (see Section 28.7), such as those employed in surface-enhanced spectroscopy techniques. The presence of the substrate breaks the inversion symmetry with respect to the particle center. For ellipsoidal-shaped dots as those described by Grand et al. (2003) and Zavelani-Rossi et al. (2008), the particle symmetry group reduces to C_{2v} (see Figure 28.6). In this case, the selection rules governing SHG in C_2 symmetry around the z axis must apply, z being the substrate normal, which is taken parallel to the optical axis. The particles also belong to the C_{1h} symmetry group defined with respect to either the x or y axis, oriented parallel to the in-plane principal axes of the ellipsoids. However, this further symmetry does not provide more restrictive selection rules.

When such particles are excited with an FW plane wave with $\mathbf{k} \parallel z$ and considering only the lowest-order E1 + E1 → E1 transitions, M_ω can only assume the values ±1 both for linearly and circularly polarized light, so parity is conserved only for $M_{2\omega} = 0$, corresponding to SH emission from an electric dipole parallel to both $\mathbf{k}$ and z (see Figure 28.6) (Finazzi et al. 2007). When the particle is illuminated by a focused FW beam or by the near field of a tip, photons with $M_\omega = 0$ can be absorbed. This results in new SHG channels, namely the ones that correspond to SH radiation from electric dipoles lying in the plane of the substrate, becoming available (see Figure 28.6) (Finazzi et al. 2007). In this case, the details of the SH-radiated intensity and polarization will depend on the particle fine structure, which defines the relative strength of each channel.

28.7 Second Harmonic Generation in Single Gold Nanoparticles

As discussed in Section 28.3, the nonlinear optical response of nanostructured systems has been experimentally studied, so far, mainly by far-field techniques. These, however, are limited by diffraction and do not allow a direct mapping of the nanoscale field enhancement. These limitations can be overcome by SNOM, which can reach sub-100 nm lateral resolution. This technique consists of bringing the sample in interaction with the near field of a source (a tip or a backilluminated aperture in a metal-coated probe). In this case, the bandwidth of spatial frequencies associated with the evanescent waves from the probe is unlimited and the resolution can in principle be arbitrarily optimized. The response of the probe–sample interaction is recorded with standard far-field collection optics. State-of-the-art lateral resolution for aperture probes is around 50 nm. Near-field nonlinear optical microscopy is a powerful tool to characterize local field enhancements in metal nanostructures since it combines the great sensitivity of nonlinear optical response with the spatial superresolution of near-field microscopy. However, the technical challenges of combining scanning probe and ultrafast technologies and the typical low peak power available at the output of optical near field probes have so far limited the number of studies of SHG from single nanoparticles in closely packed arrangements (Biagioni et al. 2007, Breit et al. 2007, Celebrano et al. 2007, 2008a,b, Zavelani-Rossi et al. 2008).

This section describes SHG from single gold nanoparticles obtained with a SNOM setup. As illustrated in Section 28.6.2, the high lateral confinement typical of near-field illumination enables the observation and exploitation of unusual and peculiar SHG modes. Moreover, the acquisition of SH maps provides complementary information to FW images, which typically results from a complex interplay between scattering, absorption, and reflection, all contributing to light extinction (Novotny and Hecht 2006). The comparison between FW and SH maps therefore allows for a better interpretation of the optical response of metal nanoparticles and discriminating among different light extinction particle behaviors that would not be possible to address by just collecting the FW signals (Biagioni et al. 2007, Celebrano et al. 2007, 2008a,b, Zavelani-Rossi et al. 2008).

28.7.1 Near-Field Microscopy Setup

To observe SHG at the nanoscale, we combine high peak power and high spatial resolution by coupling femtosecond pulses to a hollow-pyramid aperture SNOM (see Figure 28.7). The pulses



FIGURE 28.7 Schematics of our SNOM, with the ultrashort laser beam coupled to the measurement head: The collection optics, filters, and detector are also indicated. PMT indicates a photomultiplier tube.

are generated by a long-cavity mode-locked Ti:sapphire oscillator (26 MHz repetition rate), producing 20 nJ, 27 fs pulses at 800 nm. The SNOM probe consists of a silicon nitride cantilever with a hollow pyramid tip. The tip is aluminum-coated with a circular aperture at the apex, with diameter ranging between 100 and 200 nm. This probe offers several advantages compared with metal-coated tapered optical fibers, such as larger taper angle, lower absorption, preservation of light polarization (Biagioni et al. 2005), and pulse duration (Labardi et al. 2005) at the output. These improvements enable achieving peak powers more than two orders of magnitude higher in the near field, resulting in greatly enhanced nonlinear optical response of the sample. Typical tip throughputs at 800 nm range between ~10^{-4} for the 100 nm tips and 5×10^{-3} for the 200 nm ones. The tips with larger aperture were selected for the experiments presented in this section. Tip-sample distance is controlled by an optical lever that is sensitive enough to allow nondestructive contact mode stabilization on the samples.

The FW/SH light is collected in the far field by a long working distance microscope objective (numerical aperture = 0.75) and split by a dichroic filter. The FW and the SH are simultaneously detected by photomultiplier tubes. Bandpass filters are inserted in the SH beam to further reject the FW and TPPL from the sample. A 30 nm bandpass interference filter centered at 405 nm is inserted in the SH beam path to reject TPPL from the sample, which is negligible for wavelength shorter than 450 nm (Bouhelier et al. 2005, Imura et al. 2005, 2006). The quadratic dependence of SH intensity on the excitation beam power was verified. A mechanical chopper with a 1:6 duty cycle allows increasing the peak power for a given level of average power, typically 1 mW incident on the tip, and lock-in detection improves the signal-to-noise ratio, allowing for faster scans (integration time 30–100 ms per point).

Hereafter, we present two different types of gold nanoparticles. The first ones are triangles (height 15–25 nm) on a glass substrate obtained from a projection pattern ("Fischer pattern" (Fischer and Zingsheim 1981)), in a hexagonal array with 453 nm periodicity. Such a sample is chosen as an example of a SNOM study of SHG in a dense network of particles. The second type of particles are well-separated isolated ellipsoids (height about 60 nm) produced by electron beam lithography on a quartz substrate (Grand et al. 2003) in square arrays.

28.7.2 Fundamental Wavelength and Second Harmonic Maps

Figure 28.8a shows the topography of the Fischer pattern together with its SH optical image (Figure 28.8b). The topography shows the regular array of gold triangles: most of them are well separated, some are in contact with each other, and big defects cover portions of the sample. In the FW image (not shown), triangles appear dark, although the resolution is poor due to the quite large aperture diameter. Nevertheless, contrasted and well-resolved SHG maps from the gold triangles are detected. The background signal is attributed to SHG from both the glass substrate and the tip edges. The inset of Figure 28.8b shows a line profile of the SH image, demonstrating very good signal-to-noise ratio, high contrast (3:1), and good spatial resolution (better than 100 nm, see Figure 28.8c). Figure 28.8 highlights the unique capability of nonlinear SNOM to image SHG from closely packed metal nanostructures. It is interesting to note that not all the triangles observed in topography emit SH radiation with the same efficiency: some of them display an intense SH emission, while others are nearly dark. This supports the absence of topographical artifacts (Hecht et al. 1997) in the image, proved by the fact that in further measurements (not shown here), the topographic resolution was missing, yet a clear and well-resolved SHG image could still be collected. The high variability of the SHG signal is addressed further below when SHG in isolated nanoparticles is discussed.

The lithographed nanorods are about 60 nm high, with a short axis of about 70 nm and long axes equal to 100, 150, or 400 nm. The array period is 1 µm. According to the Mie theory, the plasmon resonances in elongated structures depend on their aspect ratio. Indeed, far-field extinction spectra (see Figure 28.9), with exciting white light beam polarization parallel to the major axis, display a peak around 690 nm for the 100 nm ellipsoids, around 800 nm (i.e., resonant with our FW) for the 150 nm ones and more than 1000 nm for the 400 nm ones (not shown). These three distinct particle geometries thus provide different resonating regimes that correspond to different linear and nonlinear optical behaviors and near-field properties. These are highlighted in Figure 28.10, showing the particle topography, FW near-field extinction, and SH emission obtained with the FW illumination linear polarization parallel to the nanorod long axis. The optical images at both



(a) (b) (c)

FIGURE 28.8 Projection pattern: (a) topography and (b) SH SNOM image (size: $5 \times 2.9\,\mu m^2$). The dashed circle (A) shows an SH emitting triangle and solid circle (B) shows a dark one. (c) Cross section from the raw data of the SH image, along the dotted line.



FIGURE 28.9 Extinction spectra of gold nanorods with a major axis length either equal to 100 (squares) or 150 nm (dots). The spectra have been normalized to each other at the maximum extinction. The light polarization is parallel to the particle long axis. The extinction spectra of the 400 nm-long nanorods also, discussed in the text, are not reported since the longitudinal plasmon resonance falls off the range of the analyzer. (Courtesy of J. Grand and P.-M. Adam.)



FIGURE 28.10 **(See color insert following page 20-14.)** Nanoparticles: (a), (d), and (g) topography; (b), (e), and (h) FW transmission; and (c), (f), and (i) SH emission SNOM images with corresponding cross sections along the dashed lines, from the raw data. Incident light is polarized parallel to the major axis. The particle major axis lengths are 100 nm (a)–(c), 150 nm (d)–(f), and 400 nm (g)–(i). Image size: 3 × 3 μm². (Reprinted from Zavelani-Rossi, M. et al., *Appl. Phys. Lett.*, 92, 093119, 2008. With permission.)

the FW and the SH wavelengths strongly depend on the particle size. In particular, in FW maps, all the 100 nm ellipsoids appear bright, while all the 150 and 400 nm ellipsoids appear dark. In SH images, (1) most of the 100 nm-long particles do not emit, (2) most of the resonant 150 nm-long particles emit uniformly with high contrast (see line profiles in Figure 28.10), and (3) the 400 nm-long particles appear darker than the substrate. A general picture for these results can be obtained by a combined analysis of the FW and SH maps of the metal nanostructures. As apparent from Figure 28.10, the SH maps provide complementary information with respect to the FW images. For instance, only by comparing the SH emission properties of the 150 and 400 nm-long particles, it is possible to recognize that these fall in different optical regimes, due to the FW excitation being on or off resonance, respectively, with respect to the particle LSP excitations.

The near-field FW properties of the particles can be understood by recalling that the particle-to-background contrast in the near-field extinction maps results from the interference between an FW wave propagating into the far-field and a nonpropagating near-field distribution (Mikhailowsky et al. 2003). As a general rule, a metal particle should appear brighter than the background when the frequency of the excitation is higher than that of the particle LSP resonance, while it should be darker when the frequency of the FW excitation is set below the resonance (Mikhailowsky et al. 2003). At the LSP resonance, the particle should show no contrast with respect to the background. The presence of these interference effects explains the trend observed in the FW maps displayed in Figure 28.10, where the particles have a well-controlled aspect ratio, but it may hinder the interpretation of FW near-field images in other contexts, especially when the frequency of the LSP resonances of the particles is not known. However, the resonating behavior of the 150 nm-long nanorods becomes apparent from the SH maps, since these particles efficiently emit SH radiation as a result of the presence of strongly enhanced and localized electric field associated with the particle LSP oscillations, which are effectively excited only for these particles. Instead, most of the 100 nm-long particles do not emit SH radiation, and the 400 nm-long particles, being larger than the tip aperture, strongly absorb/scatter the SH light generated at the tip and appear darker than the background.

The nonlinear optical behavior of off-resonance particles is further highlighted in Figure 28.11, where FW and SH maps are collected by exciting the nanorods with an FW field parallel to the rod minor axis. With this type of excitation, the LSP resonance frequencies are shifted toward the blue region of the spectrum and cannot be excited by the FW light. In this case, SHG is observed at correspondence with the high-curvature regions of the particle, as a consequence of highly enhanced and localized electric fields by the lightning rod effect, in agreement with the theoretical predictions of Beermann and Bozhevolnyi (2004) and Stockman et al. (2004). It is interesting to note that, in Figure 28.11, the bright spots in the SH maps seem to correspond to



FIGURE 28.11 (a)–(c) FW transmission and (d)–(f) SH emission excited by incident FW light polarized perpendicular to the particle major axis. The particle major axis lengths are 100 nm (a) and (d), 150 nm (b) and (e), and 400 nm (c) and (f). (Reprinted from Zavelani-Rossi, M. et al., *Appl. Phys. Lett.*, 92, 093119, 2008. With permission.)

dark spots in the FW images, that is, the high-curvature regions where strong fields are localized also correspond to areas where larger FW scattering/absorption occurs, giving rise to a larger local linear extinction cross section. We believe that intense localized defects are also responsible for the high variability of the SHG efficiency displayed by nominally identical particles displaying quite similar FW (see Figures 28.8 and 28.10). In this case, local field enhancement would be associated with high-curvature defects in the particles.

To summarize, the SHG efficiency depends on the particle fine structure that determines (1) local FW field enhancements, induced either by LSP excitation or by lightning rod effects in areas with high-curvature or local imperfections and (2) the modes contributing to the emission process, which are described in the next section.

28.7.3 Second Harmonic Polarization Analysis

This section shows how the analysis of the polarization of the SH-emitted light might allow one to recognize which emission modes are contributing to the SHG process for a given particle geometry and illumination conditions. Such analysis will be applied to the same lithographed isolated gold particles, already described in Section 28.7.2.

The polarization state of the SH light emitted by the gold nanoellipsoids is analyzed as illustrated schematically in Figure 28.12. The FW light is polarized parallel to the major axes of the 150 nm-long particles to excite their strong longitudinal SPT resonance. The SH radiation polarization is analyzed by a polarizer on detection. Figure 28.13 shows two typical SH maps that are obtained with the analyzer parallel (Figure 28.13b) and perpendicular (Figure 28.13c) to the excitation polarization. From these maps, one can see that the SH light emitted by the nanoparticle is polarized parallel to its short axis (see Figure 28.13b,c,d). This particular polarization pattern of the emitted SH light is incompatible with the lowest allowed emission modes one should expect for such particles for an FW plane-wave illumination. In this case, in fact, SH radiation would be emitted by a dipole oscillating perpendicularly to the substrate sustaining the particle, as illustrated in Figure 28.6a. Such an emission mode would give the same SH maps independently from the direction of the analyzer axis. This is obviously in contradiction with the experimental results shown in Figure 28.13 and is a demonstration that a novel particle emission mode, which is forbidden for plane-wave illumination, becomes accessible. In fact, the presence of a symmetry-breaking substrate together with the strong longitudinal FW field component, typical of near-field illumination, allow for efficient excitation of an SH-emitting electric dipole perpendicular to both the incident FW light polarization and the detection axes,



FIGURE 28.12 Experimental geometry of the polarization analysis setup in the SNOM microscope. The FW light is polarized parallel to the particle major axis. SH maps have been collected for the two analyzer directions (b) and (c), corresponding to SH linear polarizations parallel and perpendicular to the FW polarization, respectively. The corresponding SH maps are shown in Figure 28.13b and c, respectively.



FIGURE 28.13 Nanoellipsoids with 150 nm major axis: topography (a), SH emission with a polarizer on detection parallel (b), and perpendicular (c) to the major axis (incident light is polarized parallel to the major axis). Image size: $0.6 \times 0.6\,\mu m^2$. (d) Intensity profiles from the raw data of images (b) (circles) and (c) (triangles).

as illustrated in Figure 28.6b. From the analysis of the SH polarization pattern in Figure 28.13, one can conclude that only the SH-emitting dipole perpendicular to the particle minor axis is significantly excited by the FW field. For this particle geometry, the SHG selection rules discussed in Section 28.4 do not exclude the possibility that SHG could be due to a dipole oscillating in the direction of the long axis of the particles, so there is no simple symmetry-based justification to the fact that such emission is not observed. This behavior has to be ascribed to the particular shape and resonance conditions of the particles. Such characteristics can in effect influence in a complex way the particle SH emission properties. To give a tentative explanation of this behavior, we remark that a much larger portion of gold–air interface is available along the long sides of the ellipsoid, so that a major contribution of SH light oriented parallel to the short axis might actually be expected as a surface contribution to SHG. Finally, we would like to stress that the spatial uniformity of the polarized SHG pattern measured on several particles is a hint of the negligible influence of particle defects, which can also lower the symmetry of the particles and contribute to SHG with modes that would otherwise be forbidden by parity and angular momentum conservation in a particle with a perfectly controlled shape.

28.8 Perspectives

A very promising perspective for future nano-optics is the possibility to simultaneously control of the spatial and temporal properties of the optical near field in the vicinity of a nanostructure by illumination with broadband optimally polarization- and time-shaped femtosecond light pulses. Adaptive shaping of the phase and amplitude of femtosecond laser pulses has been developed into an efficient tool for the directed manipulation of interference phenomena, thus providing coherent control over various quantum-mechanical systems. The interest to extend coherent control methods to nanostructures consists in overcoming the spatial limitation due to diffraction. Coherent control of the spatial and temporal evolution of optical near-fields by amplitude and polarization pulse shaping in plasmonic nanostructures has recently been theoretically proposed (Stockman et al. 2002, Brixner et al. 2005, 2006, Sukharev and Seideman 2007) and experimentally demonstrated (Aeschlimann et al. 2007) by applying an adaptative method based on measuring the local fields with two-photon photoemission electron microscopy. Progress in the coherent control of electric fields in nanostructures thus might open the access to simultaneously ultrafast and nanoscale new physics.

Nonlinear near-field optical microscopy might thus play an extremely important role in the development of nanoscale coherent control, since it can be employed as a probe of local field enhancement. In this frame, the temporal dynamics of the nonlinear phenomenon is, however, extremely important. SHG represents an ideal candidate to this task since the conversion of two FW photons into an SH photon is itself a coherent process (Imura et al. 2005), at variance from, for example, TPPL, which is incoherent in noble metal nanostructures (Imura et al. 2005). Indeed, we have recently demonstrated (Biagioni et al. 2009) that the TPPL yield in gold nanowires becomes independent of the pulse duration for laser pulses shorter than about 1 ps, while an inverse proportionality with the pulse duration would be expected for a fixed pulse energy. The origin of this behavior consists of the fact that TPPL in gold nanostructures is obtained after a 3*d* hole is produced by two sequential absorption steps involving a single photon (Imura et al. 2005), and is governed by the relaxation time of the *sp* conduction band hole generated after the first photon absorption. This temporal limitation would advise against the utilization of TPPL in probing near-field enhancement for coherent control applications, leaving SHG as a better adapted tool.

28.9 Conclusions

Thanks to the combination of surface sensitivity and symmetry selectivity, SHG is a very powerful tool to investigate the nanoscale properties of matter. The application of SHG techniques for investigating the structure and various other properties of small particles is a subject of considerable current interest and has stimulated a conspicuous number of both theoretical and experimental works in a broad range of subjects. In particular, being SHG a nonlinear optical process whose yield depends on the square power of the FW field intensity, SHG has found many applications in the study of the electric field enhancement mechanisms in metal nanostructures, where the lightning rod effect associated with high-curvature particles or resonantly excited plasma oscillations can lead to extremely intense and highly localized electric fields. Since nanoscience is attracting an exponentially growing attention, SHG in nanostructured systems will be a very hot topic for many years to come.

Acknowledgments

We would like to particularly thank Prof. Klaus Sattler for his kind invitation to write this chapter. We are also indebted to many colleagues and friends, whom we had the opportunity to work and discuss with during their activity concerning this work. Among these, we would like to mention M. Allegrini, P.-M. Adam P. Biagioni, M. Celebrano, G. Grancini, J. Grand, M. Labardi, D. Polli, M. Savoini, and M. Zavelani-Rossi.

M. F. and L. D. are also affiliated to L-NESS (Laboratory for Nanometric Epitaxial Structures on Silicon and for Spintronics), which is an Interuniversity Centre between Politecnico di Milano and Università di Milano Bicocca. G. C. is also affiliated to ULTRAS (National Laboratory for Ultrafast and Ultraintense Optical Science) research center, which is founded by the National Institute of the Physics of Matter (INFM) of the National Research Council (CNR).

References

Abid, J.-P., Nappa, J., Girault, H. H., and Brevet, P.-F. 2004. Pure surface plasmon resonance enhancement of the first hyperpolarizability of gold core–silver shell nanoparticles. *J. Chem. Phys.* **121**: 12577.

Aeschlimann, M., Bauer, M., Bayer, D. et al. 2007. Adaptive subwavelength control of nano-optical fields, *Nature* **446**: 301–304.

Agarwal, G. S. and Jha, S. S. 1982. Theory of second harmonic generation at a metal surface with surface plasmon excitation. *Solid State Commun.* **41**: 499–501.

Antoine, R., Brevet, P. F., Girault, H. H., Bethell, D., and Schiffrin, D. J. 1997. Surface plasmon enhanced non-linear optical response of gold nanoparticles at the air/toluene interface. *Chem. Commun.* **1997**: 1901–1902.

Antoine, R., Pellarin, M., Palpant, B. et al. 1998. Surface plasmon enhanced second harmonic response from gold clusters embedded in an alumina matrix. *J. Appl. Phys.* **84**: 4532.

Bachelier, G., Russier-Antoine, I., Benichou, E., Jonin, C., and Brevet, P. 2008. Multipolar second-harmonic generation in noble metal nanoparticles. *J. Opt. Soc. Am. B* **25**: 955–960.

Beermann, J. and Bozhevolnyi, S. I. 2004. Microscopy of localized second-harmonic enhancement in random metal nanostructures. *Phys. Rev. B* **69**: 155429.

Beermann, J., Bozhevolnyi, S. I., and Coello, V. 2006. Modeling of nonlinear microscopy of localized field enhancements in random metal nanostructures. *Phys. Rev. B* **73**: 115408.

Biagioni, P., Polli, D., Labardi, M. et al. 2005. Unexpected polarization behavior at the aperture of hollow-pyramid near-field probes. *Appl. Phys. Lett.* **87**: 223112.

Biagioni, P., Celebrano, M., Polli, D. et al. 2007. Nonlinear optics and spectroscopy at the nanoscale with a hollow-pyramid aperture SNOM. *J. Phys. Conf. Ser.* **61**: 125–129.

Biagioni, P., Celebrano, M., Savoini, M., Grancini, G., Brida, D., Mátéfi-Tempfli, S., Mátéfi-Tempfli, M., Duò, L., Hecht, B., Cerullo, G., and Finazzi, M. 2009. Dependence of the two-photon photoluminescence yield of gold nanostructures on the laser pulse duration. *Phys. Rev. B* **80**: 045411.

Bickford, L., Sun, J., Fu, K. et al. 2008. Enhanced multi-spectral imaging of live breast cancer cells using immunotargeted gold nanoshells and two-photon excitation microscopy. *Nanotechnology* **19**: 315102.

Bloembergen, N. 1999. Surface nonlinear optics: A historical overview. *Appl. Phys. B: Lasers Opt.* **68**: 289–293.

Bloembergen, N. and Pershan, P. S. 1962. Light waves at the boundary of nonlinear media. *Phys. Rev.* **128**: 606.

Bouhelier, A., Beversluis, M. R., and Novotny, L. 2003. Characterization of nanoplasmonic structures by locally excited photoluminescence. *Appl. Phys. Lett.* **83**: 5041–5043.

Bouhelier, A., Bachelot, R., Lerondel, G., Kostcheev, S., Royer P., and Wiederrecht, G. P. 2005. Surface plasmon characteristics of tunable photoluminescence in single gold nanorods. *Phys. Rev. Lett.* **95**: 267405.

Boyd, R. W. 2003. *Nolinear Optics*. Academic Press, San Diego, CA.

Bozhevolnyi, S. I. and Lozovski, V. Z. 2000. Self-consistent model for second-harmonic near-field microscopy. *Phys. Rev. B* **61**: 11139.

Bozhevolnyi, S. I. and Lozovski, V. Z. 2002. Second-harmonic scanning optical microscopy of individual nanostructures. *Phys. Rev. B* **65**: 235420.

Bozhevolnyi, S. I., Beermann, J., and Coello, V. 2003. Direct observation of localized second-harmonic enhancement in random metal nanostructures. *Phys. Rev. Lett.* **90**: 197403.

Breit, M., Malkmus, S., Feldmann, J., and Danzebrink, H. U. 2007. Near-field second harmonic generation by using uncoated silicon tips. *Appl. Phys. Lett.* **90**: 093114.

Brixner, T., Garcia de Abajo, F. J., Schneider, J., and Pfeiffer, W. 2005. Nanoscopic ultrafast space-time-resolved spectroscopy. *Phys. Rev. Lett.* **95**: 093901.

Brixner, T., García de Abajo, F. J., Schneider, J., Spindler, C., and Pfeiffer, W. 2006. Ultrafast adaptive optical near-field control. *Phys. Rev. B* **73**: 125437.

Brudny, V. L., Mendoza, B. S., and Mochán, W. L. 2000. Second-harmonic generation from spherical particles. *Phys. Rev. B* **62**: 11152.

Brudny, V. L., Mochán, W. L., Maytorena, J. A., and Mendoza, B. S. 2003. Second harmonic generation from a collection of nanoparticles. *Phys. Stat. Sol. B* **240**: 518–526.

Campagnola, P. J. and Loew, L. M. 2003. Second-harmonic imaging microscopy for visualizing biomolecular arrays in cells, tissues and organisms. *Nat. Biotechnol.* **11**: 1356–1360.

Canfield, B. K., Kujala, S., Jefimovs, K., Turunen, J., and Kauranen, M. 2004. Linear and nonlinear optical responses influenced by broken symmetry in an array of gold nanoparticles. *Opt. Express* **12**: 5418–5423.

Canfield, B. K., Kujala, S., Laiho, K., Jefimovs, K., Turunen, J., and Kauranen, M. 2006. Chirality arising from small defects in gold nanoparticle arrays. *Opt. Express* **14**: 950–955.

Canfield, B. K., Husu, H., Laukkanen, J., Bai, B. et al. 2007. Local field asymmetry drives second-harmonic generation in noncentrosymmetric nanodimers. *Nano Lett.* **7**: 1251–1255.

Celebrano, M., Zavelani-Rossi, M., Biagioni, P. et al. 2007. Mapping local field distribution at metal nanostructures by near-field second-harmonic generation. *Proc. SPIE* **6641**: 66411E.

Celebrano, M., Zavelani-Rossi, M., Polli, D., et al. 2008a. Mapping local field enhancements at nanostructured metal surfaces by second-harmonic generation induced in the near field. *J. Microsc.* **229**: 233–239.

Celebrano, M., Biagioni, P., Finazzi, M., et al. 2008b. Near-field second-harmonic generation from gold nanoellipsoids. *Phys. Stat. Sol. C* **5**: 2657–2661.

Dadap, J. I. 2008. Optical second-harmonic scattering from cylindrical particles. *Phys. Rev. B* **78**: 205322.

Dadap, J. I., Shan, J., Eisenthal, K. B., and Heinz, T. F. 1999. Second-harmonic Rayleigh scattering from a sphere of centrosymmetric material. *Phys. Rev. Lett.* **83**: 4045.

Dadap, J. I., Shan, J., and Heinz, T. F. 2004. Theory of optical second-harmonic generation from a sphere of centrosymmetric material: Small-particle limit. *J. Opt. Soc. Am. B* **21**: 1328–1347.

Dewitz, J. P., Hübner, W., and Bennemann, K. H. 1996. Theory for nonlinear Mie-scattering from spherical metal clusters. *Z. Phys. D: At. Mol. Clusters* **37**: 75–84.

Downer, M. C., Mendoza, B. S., and Gavrilenko, V. I. 2001. Optical second harmonic spectroscopy of semiconductor surfaces: Advances in microscopic understanding. *Surf. Interface Anal.* **31**: 966–986.

Durr, N. J., Larson, T., Smith, D. K., Korgel, B. A., Sokolov, K., and Ben-Yakar, A. 2007. Two-photon luminescence imaging of cancer cells using molecularly targeted gold nanorods. *Nano Lett.* **7**: 941–945.

El-Sayed, I. H., Huang, X., and El-Sayed, M. A. 2006. Selective laser photo-thermal therapy of epithelial carcinoma using anti-EGFR antibody conjugated gold nanoparticles. *Cancer Lett.* **239**: 129–135.

Figliozzi, P., Sun, L., Jiang, Y. et al. 2005. Single-beam and enhanced two-beam second-harmonic generation from silicon nanocrystals by use of spatially inhomogeneous femtosecond pulses. *Phys. Rev. Lett.* **94**: 047401.

Finazzi, M., Biagioni, P., Celebrano, M., and Duò, L. 2007. Selection rules for second-harmonic generation in nanoparticles. *Phys. Rev. B* **76**: 125414.

Fischer, U. Ch. and Zingsheim, H. P. 1981. Submicroscopic pattern replication with visible light. *J. Vac. Sci. Technol.* **19**: 881–885.

Franken, P. A., Hill, A. E., Peters, C. W., and Weinreich, G. 1961. Generation of optical harmonics. *Phys. Rev. Lett.* **7**: 118.

Grand, J., Kostcheev, S., Bijoeon, J.-L. et al. 2003. Optimization of SERS-active substrates for near-field Raman spectroscopy. *Synth. Met.* **139**: 621–624.

Hao, E. C., Schatz, G. C., Johnson, R. C., and Hupp, J. T. 2002. Hyper-Rayleigh scattering from silver nanoparticles. *J. Chem. Phys.* **117**: 5963.

Hartschuh, A., Pedrosa, H. N., Novotny, L., and Krauss, T. D. 2003. Simultaneous fluorescence and Raman scattering from single carbon nanotubes. *Science* **301**: 1354–1356.

Hecht, B., Bielefeldt, H., Inouye, Y., and Pohl, D. W. 1997. Facts and artifacts in near-field optical microscopy. *J. Appl. Phys.* **81**: 2492.

Hua, X. M. and Gersten, J. I. 1986. Theory of second-harmonic generation by small metal spheres. *Phys. Rev. B* **33**: 3756.

Hubert, C., Billot, L., Adam, P.-M. et al. 2007. Role of surface plasmon in second harmonic generation from gold nanorods. *Appl. Phys. Lett.* **90**: 181105.

Imura, K., Nagahara, T., and Okamoto, H. 2005. Near-field two-photon-induced photoluminescence from single gold nanorods and imaging of plasmon modes. *J. Phys. Chem. B* **109**: 13214–13220.

Imura, K., Nagahara, T., and Okamoto, H. 2006. Photoluminescence from gold nanoplates induced by near-field two-photon absorption. *Appl. Phys. Lett.* **88**: 023104.

Jackson, J. D. 1975. *Classical Electrodynamics*. Wiley, New York.

Jakubczyk, D., Shen, Y., Lal, M., Kim, K.S., Świątkewicz, J., and Prasad, P.N. 1999. Near-field probing of nanoscale nonlinear optical processes. *Opt. Lett.* **24**: 1151–1153.

Jiang, Y., Wilson, P. T., Downer, M. C., White, C. W., and Withrow, S. P. 2001. Second-harmonic generation from silicon nanocrystals embedded in SiO_2. *Appl. Phys. Lett.* **78**: 766.

Jiang, Y., Sun, L., and Downer, M. C. 2002. Second-harmonic spectroscopy of two-dimensional Si nanocrystal layers embedded in SiO_2 films. *Appl. Phys. Lett.* **81**: 3034.

Johnson, R. C., Li, J., Hupp, J. T., and Schatz, G. C. 2002. Hyper-Rayleigh scattering studies of silver, copper, and platinum nanoparticle suspensions. *Chem. Phys. Lett.* **356**: 534–540.

Labardi, M., Zavelani-Rossi, M., Polli, D. et al. 2005. Characterization of femtosecond light pulses coupled to hollow-pyramid near-field probes: Localization in space and time. *Appl. Phys. Lett.* **86**: 031105.

Lüpke, G. 1999. Characterization of semiconductor interfaces by second-harmonic generation. *Surf. Sci. Rep.* **35**: 75–161.

Martorell, J., Vilaseca, R., and Corbalán, R. 1997. Scattering of second-harmonic light from small spherical particles ordered in a crystalline lattice. *Phys. Rev. A* **55**: 4520.

Mc Gilp, J. F. 1996. A review of optical second-harmonic and sum-frequency generation at surfaces and interfaces. *J. Phys. D* **29**: 1812–1821.

Mikhailowsky, A. A., Petruska, M. A., Stockman, M. I., and Klimov, V. I. 2003. Broadband near-field interference spectroscopy of metal nanoparticles using a femtosecond white-light continuum. *Opt. Lett.* **28**: 1686–1688.

Mochán, W. L., Maytorena, J. A., Mendoza, B. S., and Brudny, V. L. 2003. Second-harmonic generation in arrays of spherical particles. *Phys. Rev. B* **68**: 085318.

Mühlschlegel, P., Eisler, H.-J., Martin, O. J. F., Hecht, B., and Pohl, D. W. 2005. Resonant optical antennas. *Science* **308**: 1607–1609.

Nagesha, D., Laevsky, G. S., Lampton, P. et al. 2007. In vitro imaging of embryonic stem cells using multiphoton luminescence of gold nanoparticles. *Int. J. Nanomed.* **2**: 813.

Nappa, J., Revillod, G., Russier-Antoine, I., Benichou, E., Jonin, C., and Brevet P. F. 2005. Electric dipole origin of the second harmonic generation of small metallic particles. *Phys. Rev. B* **71**: 165407.

Nappa, J., Russier-Antoine, I., Benichou, E., Jonin, Ch., and Brevet, P. F. 2006. Second harmonic generation from small gold metallic particles: From the dipolar to the quadrupolar response. *J. Chem. Phys.* **125**: 184712.

Neacsu, C. C., Reider, G. A., and Raschke, M. B. 2005. Second-harmonic generation from nanoscopic metal tips: Symmetry selection rules for single asymmetric nanostructures. *Phys. Rev. B* **71**: 201402(R).

Nie, S. M. and Emery, S. R. 1997. Probing single molecules and single nanoparticles by surface-enhanced Raman scattering. *Science* **275**: 1102–1106.

Novotny, L. and Hecht, B. 2006. *Principles of Nano-Optics*. Cambridge University Press, Cambridge, NY.

O'Neal, D. P., Hirsch, L. R., Halas, N. J., Payne, J. D., and West, J. L. 2004. *Cancer Lett.* **209**: 181.

Panasyuk, G. Y., Schotland, J. C., and Marke, V. A. 2008. Classical theory of optical nonlinearity in conducting nanoparticles. *Phys. Rev. Lett.* **100**: 047402.

Parameswaran, K. R., Kurz, J. R., Roussev, M. M., and Fejer, M. 2002. Observation of 99% pump depletion in single-pass second-harmonic generation in a periodically poled lithium niobate waveguide. *Opt. Lett.* **27**: 43–45.

Park, J., Estrada, A., Sharp, K. et al. 2008. Two-photon-induced photoluminescence imaging of tumors using near-infrared excited gold nanoshells. *Opt. Express* **16**: 1590–1599.

Pavlyukh, Y. and Hübner, W. 2004. Nonlinear Mie scattering from spherical particles. *Phys. Rev. B* **70**: 245434.

Russier-Antoine, I., Jonin, Ch., Nappa, J., Bénichou, E., and Brevet, P.-F. 2004. Wavelength dependence of the hyper Rayleigh scattering response from gold nanoparticles. *J. Chem. Phys.* **120**: 10748.

Sandrock, M. L., Pibel, C. D., Geiger, F. M., and Foss, Jr. C. A. 1999. Synthesis and second-harmonic generation studies of noncentrosymmetric gold nanostructures. *J. Phys. Chem. B* **103**: 2668–2673.

Shan, J., Dadap, J. I., Stiopkin, I., Reider, G. A., and Heinz, T. F. 2006. Experimental study of optical second-harmonic scattering from spherical nanoparticles. *Phys. Rev. A* **73**: 023819.

Shen, Y. R. 1984. *The Principles of Nonlinear Optics*. Wiley, New York.

Shen, Y. R. 1989. Optical second harmonic generation at interfaces. *Annu. Rev. Phys. Chem.* **40**: 327–350.

Shen, Y., Markowicz, P., Winiarz, J., Swiatkiewicz, J., and Prasad, P. N. 2001. Nanoscopic study of second-harmonic generation in organic crystals with collection-mode near-field scanning optical microscopy. *Opt. Lett.* **26**: 725–727.

Singh, D. B. and Tripathi, V. K. 2007. Surface plasmon excitation at second harmonic over a rippled surface. *J. Appl. Phys.* **102**: 083301.

Smolyaninov, I. I., Zayats, A. V., and Davis, C. C. 1997. Near-field second harmonic generation from a rough metal surface. *Phys. Rev. B* **56**: 9290.

Smolyaninov, I. I., Liang, H. Y., Lee, C. H., Davis, C. C., Aggarwal, S., and Ramesh, R. 2000. Near-field second-harmonic microscopy of thin ferroelectric films. *Opt. Lett.* **25**: 835–837.

Stockman, M. I., Faleev, S. V., and Bergman, D. J. 2002. Coherent control of femtosecond energy localization in nanosystems. *Phys. Rev. Lett.* **88**: 067402.

Stockman, M. I., Bergman, D. J., Anceau, C., Brasselet, S., and Zyss, J. 2004. Enhanced second-harmonic generation by metal surfaces with nanoscale roughness: Nanoscale dephasing, depolarization, and correlations. *Phys. Rev. Lett.* **92**: 057402.

Su, H. M., Ye, J. T., Tang, Z. K., and Wong, K. S. 2008. Resonant second-harmonic generation in monosized and aligned single-walled carbon nanotubes. *Phys. Rev. B* **77**: 125428.

Sukharev, M. and Seideman, T. 2007. Coherent control of light propagation via nanoparticle arrays. *J. Phys. B: At. Mol. Opt. Phys.* **40**: S283–S298.

Tinkham, M. 1964. *Group Theory and Quantum Mechanics*. McGraw-Hill, New York.

Vance, F. W., Lemon, B. I., and Hupp, J. T. 1998. Enormous hyper-Rayleigh scattering from nanocrystalline gold particle suspensions. *J. Phys. Chem. B* **102**: 10091–10093.

Wang, H., Yan, E. C. Y., Borguet, E., and Eisenthal, K. B. 1996. Second harmonic generation from the surface of centrosymmetric particles in bulk solution. *Chem. Phys. Lett.* **259**: 15–20.

Yang, N., Angerer, W. E., and Yodh, A. G. 2001. Angle-resolved second-harmonic light scattering from colloidal particles. *Phys. Rev. Lett.* **87**: 103902.

Zavelani-Rossi, M., Celebrano, M., Biagioni, P. et al. 2008. Near-field second-harmonic generation in single gold nanoparticles. *Appl. Phys. Lett.* **92**: 093119.

Zayats, A.V., Kalkbrenner, T., Sandoghdar, V., and Mlynek, J. 2000. Second-harmonic generation from individual surface defects under local excitation. *Phys. Rev. B* **61**: 4545.

Zhu, J. 2007. Theoretical study of the tunable second-harmonic generation (SHG) enhancement factor of gold nanotubes. *Nanotechnology* **18**: 225702.

29

Nonlinear Optics in Semiconductor Nanostructures

Mikhail Erementchouk
University of Central Florida

Michael N. Leuenberger
University of Central Florida

29.1 Introduction **29**-1
29.2 Semiconductor-Field Hamiltonian in **k** · **p**-Approximation **29**-2
29.3 Quantum Equations of Motion **29**-6
Electromagnetic Field • Semiconductor Dynamics • Rotating Wave Approximation
29.4 Perturbation Theory: Four-Wave Mixing Response **29**-11
29.5 Nonperturbative Methods: Rabi Oscillations **29**-16
29.6 Conclusion **29**-19
Acknowledgment **29**-19
References **29**-19

29.1 Introduction

The physics of semiconductor nonlinear response unites under the same cover a fascinating variety of different physical phenomena, theoretical ideas, and experimental approaches. It provides promising opportunities for technologies, for example, in the form of principally new light sources, and presents a convenient testing field for studying long-standing fundamental questions while raising new ones in fields ranging decoherence to low-energy quantum field theory.

It is not therefore, surprising, that the interest of researchers remains steadily persistent for already many decades. There are many books and reviews devoted to the details of different topics. However, as investigations move forward, new types of problems surface and the question of the basic principles of the theory of nonlinear response is raised again and again.

Perhaps the most clear demonstration of the recurring process of testing the background is the drastic change of the main theoretical methods, which took place in the 1990s. In the pre-1990s era, Green's functions method was the main technique used in the limit of zero, finite temperature, or nonequilibrium (the Keldysh technique). The main questions were formulated in terms of the spectral characteristics, and using the adiabatical approximation was the usual practice. With the development of new experimental methods and the improvement of the quality of the samples, the attention gradually moved toward the temporal behavior and the transient features of the excitations. As a result, in the post-1990s era, time dependence turned out to be the major question, and the typical theoretical approach became the method of the dynamical equations of motion. In a sense the whole topic was reinvented, making the question of fundamentals of the theory especially important.

In the following sections, we present the derivation of the main dynamical equations for the electromagnetic field and the semiconductor excitations in the general context of quantum field theory. Such an approach is particularly useful because the resonant interaction of light with the semiconductor results in constantly changing the number of elementary excitations in the semiconductor bands. Therefore, the respective description must admit the creation and annihilation of particles on the fundamental level. Also, in order to cover at least partially the various physical situations relevant for the problem of nonlinear response, we avoid using specific approximations such as, for example, the spherical symmetry of the hole's bands or the translational symmetry of the structures. The latter circumstance compels to formulate the major part of considerations in the coordinate representation. Finally, the main equations are derived for operators that makes them applicable for studying quantum statistics and other complex questions going beyond the single-particle correlation functions (Green's functions).

The structure of the presentation is as follows. In Section 29.2 we derive the quantum-field Hamiltonian in the **k** · **p**-approximation and briefly review the basic properties of the semiconductor bands. Section 29.3 is devoted to the derivation of the quantum equations of motion for the electromagnetic field and the semiconductor excitations. In Section 29.4, the perturbative approach of analyzing the quantum equations of motion is reviewed. Finally, in Section 29.5 we consider the semiconductor Bloch equation.

29.2 Semiconductor-Field Hamiltonian in $\mathbf{k}\cdot\mathbf{p}$-Approximation

The quantum dynamics of the electrons moving in the periodic lattice field in the semiconductor under the action of the external field is described in SI units by the Hamiltonian

$$\mathcal{H}_{mat} = \sum_{s} \int d\mathbf{x}\, \psi_s^{\dagger}(\mathbf{x}) \left\{ \frac{1}{2m} [\mathbf{p} - e\mathbf{A}(\mathbf{x})]^2 + U_l(\mathbf{x}) + U_{ext}(\mathbf{x}) \right\} \psi_s(\mathbf{x}) + \frac{1}{2} \sum_{s,s'} \int d\mathbf{x}_1\, d\mathbf{x}_2\, \psi_s^{\dagger}(\mathbf{x}_1) \psi_{s'}^{\dagger}(\mathbf{x}_2) V(\mathbf{x}_1 - \mathbf{x}_2) \psi_{s'}(\mathbf{x}_2) \psi_s(\mathbf{x}_1), \tag{29.1}$$

where

- $\psi_s(\mathbf{x})$ is the electron field operator
- s and s' are the electron spin indices
- $\mathbf{A}$ is the vector potential
- $U_l(\mathbf{x})$ is the periodic lattice potential
- $U_{ext}(\mathbf{x})$ is an external potential caused, for example, by the external static electric field
- $V(\mathbf{x}) = e^2/4\pi\epsilon_0\epsilon_b|\mathbf{x}|$, with ϵ_b being the background dielectric constant, is the potential of the Coulomb interaction between the electrons

In the following paragraphs we will be interested in establishing the relation with the standard $\mathbf{k}\cdot\mathbf{p}$ approach, therefore, we will omit both the external potential and the Coulomb interaction and will consider their effect later.

The main idea of the $\mathbf{k}\cdot\mathbf{p}$ approach is to employ the fact that we are interested in the weak and spatially smooth perturbations of the semiconductor near its ground state. Thus, we want to account exactly the effect of the periodic lattice potential forming the semiconductor ground state and to consider the deviation from it in the spirit of the perturbation theory.

In order to account for the effect of the periodic potential on the electron dynamics we need to develop an appropriate description of the respective electron single-particle states. The field operator $\psi^{\dagger}(\mathbf{x})$ can always be expanded in terms of the Bloch modes as

$$\psi_s^{\dagger}(\mathbf{x}) = \sum_{n} \int d\mathbf{k}\, \phi_{n,\mathbf{k}}^{\star}(\mathbf{x}) a_{n,\mathbf{k}}^{\dagger}, \tag{29.2}$$

where

- n enumerates the bands and includes the spin index
- the Bloch wave vector $\mathbf{k}$ lies in the first Brillouin zone
- the wave functions $\phi_{n,\mathbf{k}}(\mathbf{x})$ give the solutions of the respective Schrödinger equation in the periodic potential
- the operators $a_{n,\mathbf{k}}^{\dagger}$ are the operators, which create electrons in the respective Bloch states

According to the Bloch theorem the electron wave function $\phi_{n,\mathbf{k}}(\mathbf{x})$ can be presented as

$$\phi_{n,\mathbf{k}}(\mathbf{x}) = e^{i\mathbf{k}\cdot\mathbf{x}} u_{n,\mathbf{k}}(\mathbf{x}), \tag{29.3}$$

where $u_{n,\mathbf{k}}(\mathbf{x})$ is a periodic function solving the equation

$$\frac{\hbar^2}{2m}(-i\nabla + \mathbf{k})^2 u_{n,\mathbf{k}}(\mathbf{x}) + U_l(\mathbf{x}) u_{n\cdot\mathbf{k}}(\mathbf{x}) = \epsilon_n(\mathbf{k}) u_{n,\mathbf{k}}(\mathbf{x}). \tag{29.4}$$

This equation is Hermitian and, hence, functions $u_{n,\mathbf{k}}(\mathbf{x})$ for a fixed $\mathbf{k} = \mathbf{k}_0$ constitute a complete set on the space of periodic functions. We can, therefore, represent functions corresponding to other $\mathbf{k} \neq \mathbf{k}_0$ as the respective Fourier series

$$u_{n,\mathbf{k}}(\mathbf{x}) = \sum_{m} \alpha_{n,m}(\mathbf{k};\mathbf{k}_0) u_{m,\mathbf{k}_0}(\mathbf{x}) \tag{29.5}$$

with unitary $\alpha_{n,m}(\mathbf{k}; \mathbf{k}_0)$. The latter follows from orthonormality of the amplitudes $u_{n,\mathbf{k}}(\mathbf{x})$

$$\frac{1}{\mathcal{V}} \int d\mathbf{x}\, u_{n',\mathbf{k}}^{\star}(\mathbf{x}) u_{n',\mathbf{k}}(\mathbf{x}) = \frac{1}{(2\pi)^3} \delta_{nn'}, \tag{29.6}$$

where $\mathcal{V}$ is the volume of the elementary cell. Indeed, substituting Equation 29.5 into Equation 29.6 we obtain

$$\sum_{m} \alpha_{n'm}^{\star}(\mathbf{k};\mathbf{k}_0) \alpha_{nm}(\mathbf{k};\mathbf{k}_0) = \delta_{nn'}, \tag{29.7}$$

which explicitly shows the unitarity of $\alpha_{n,m}(\mathbf{k}; \mathbf{k}_0)$. This motivates the introduction of new (Luttinger–Kohn) function describing the electron states

$$\chi_{n,\mathbf{k}}(\mathbf{x}) = e^{i\mathbf{k}\cdot\mathbf{x}} u_{n,\mathbf{k}_0}(\mathbf{x}). \tag{29.8}$$

These functions constitute a complete orthonormal set similarly to the electron wave functions $\phi_{n,\mathbf{k}}(\mathbf{x})$. The proof demonstrates the typical line of arguments and, therefore, it is useful to consider it in detail. The completeness of the Luttinger–Kohn functions

$$\sum_{n} \int d\mathbf{k}\, \chi_{n,\mathbf{k}}^{\star}(\mathbf{x}) \chi_{n,\mathbf{k}}(\mathbf{x}') = \delta(\mathbf{x} - \mathbf{x}'). \tag{29.9}$$

follows from the respective relation for the electron wave functions

$$\sum_{n} \int d\mathbf{k}\, \phi_{n,\mathbf{k}}^{\star}(\mathbf{x}) \phi_{n,\mathbf{k}}(\mathbf{x}') = \delta(\mathbf{x} - \mathbf{x}') \tag{29.10}$$

if we use Equations 29.5 and 29.7. For orthonormality we need to consider

$$(n,\mathbf{k}|n',\mathbf{k}') \equiv \int d\mathbf{x}\, \chi_{n,\mathbf{k}}^{\star}(\mathbf{x}) \chi_{n',\mathbf{k}'}(\mathbf{x}) = \int d\mathbf{x}\, e^{i(\mathbf{k}-\mathbf{k}')\cdot\mathbf{x}} u_{n,\mathbf{k}_0}^{\star}(\mathbf{x}) u_{n',\mathbf{k}_0}(\mathbf{x}). \tag{29.11}$$

The product $u^{\star}_{n,\mathbf{k}_0}(\mathbf{x})u_{n',\mathbf{k}_0}(\mathbf{x})$ is a periodic function and therefore can be expanded in the Fourier series

$$u^{\star}_{n,\mathbf{k}_0}(\mathbf{x})u_{n',\mathbf{k}_0}(\mathbf{x}) = \sum_{\mathbf{Q}} B_{nn'}(\mathbf{Q})e^{i\mathbf{Q}\cdot\mathbf{x}}, \tag{29.12}$$

where the sum runs over the vectors of the reciprocal lattice and

$$B_{nn'}(\mathbf{Q}) = \frac{1}{\mathcal{V}}\int d\mathbf{x}\, e^{-i\mathbf{Q}\cdot\mathbf{x}}u^{\star}_{n,\mathbf{k}}(\mathbf{x})u_{n',\mathbf{k}}(\mathbf{x}). \tag{29.13}$$

Using this representation in Equation 29.11 we obtain

$$(n,\mathbf{k}|n',\mathbf{k}') = (2\pi)^3\sum_{\mathbf{Q}} B_{nn'}(\mathbf{Q})\delta(\mathbf{k}-\mathbf{k}'+\mathbf{Q}). \tag{29.14}$$

The Bloch-wave-vectors $\mathbf{k}$ and $\mathbf{k}'$ are inside the first Brillouin zone and, therefore, the only possibility to reach the singularity point of the δ-function is when $\mathbf{Q} = 0$ leading to $(n,\mathbf{k}|n',\mathbf{k}') = (2\pi)^3B_{nn'}(0)\delta(\mathbf{k}-\mathbf{k}')$. Taking into account Equation 29.6 we arrive at

$$(n,\mathbf{k}|n',\mathbf{k}') = \delta_{nn'}\delta(\mathbf{k}-\mathbf{k}'). \tag{29.15}$$

Such introduced functions $\chi_{n',\mathbf{k}'}(\mathbf{x})$ provide a general background and are used in different contexts in solid-state physics (Luttinger and Kohn 1955, Johnson and Hui 1993). In what follows we limit ourselves to the case $\mathbf{k}_0 = 0$ and will omit the index corresponding to the Bloch-wave-vector, simplifying notations.

In terms of the functions $\chi_{n,\mathbf{k}}(\mathbf{x})$ the electron field operator is presented as

$$\psi^{\dagger}_s(\mathbf{x}) = \sum_n \int d\boldsymbol{k}\,\chi^{\star}_{n,\mathbf{k}}(\mathbf{x})b^{\dagger}_{n,\mathbf{k}}. \tag{29.16}$$

Substituting this representation into Equation 29.1, adopting the Coulomb gauge for the vector potential, $\nabla\cdot\mathbf{A}(\mathbf{x}) \equiv 0$, taking into account Equation 29.4 and using the same trick as for Equation 29.15 we obtain

$$\begin{aligned}\mathcal{H}_{mat} &= \sum_{n,n'}\int d\mathbf{k}\left[\left(\epsilon_n \frac{\hbar^2k^2}{2m}\right)\delta_{n,n'} + \frac{\hbar}{m}\mathbf{k}\cdot\mathbf{p}_{n,n'}\right]b^{\dagger}_{n,\mathbf{k}}b_{n',\mathbf{k}}\\ &\quad -\frac{e}{m}\sum_{n,n'}\int d\mathbf{k}\,d\mathbf{q}\left[\mathbf{A}(\mathbf{q})(\mathbf{p}_{n,n'}+\hbar\mathbf{k}\delta_{n,n'}) - \frac{e}{2}A_2(\mathbf{q})\delta_{n,n'}\right]\\ &\quad \times b^{\dagger}_{n,\mathrm{k}+\mathrm{q}}b_{n',\mathrm{k}},\end{aligned} \tag{29.17}$$

where $A_2(\mathbf{q}) = (2\pi)^{-3/2}\int d\mathbf{x}\,A^2(\mathbf{x})e^{-i\mathbf{q}\cdot\mathbf{x}}$. The parameters of great importance introduced in Equation 29.17 are the matrix elements of the momentum operator between different bands

$$\mathbf{p}_{nn'} = -\frac{i\hbar}{\mathcal{V}}\int d\mathbf{x}\,u^{\star}_n(\mathbf{x})\nabla u_{n'}(\mathbf{x}), \tag{29.18}$$

which are responsible for the *interband* coupling and are the main parameters quantifying the strength of the light–matter interaction.

The first term in the r.h.s. of Equation 29.17 describes the dynamics of the semiconductor excitations, and the second term accounts for the interaction with the external field. The specific feature of the "eigen-part" of the Hamiltonian (that is the part which is independent of the external field) is that it is not diagonal with respect to bands. The reason for this is the special status given to the states corresponding to $\mathbf{k} = \mathbf{k}_0 = 0$. These states do not exhaust the eigenstates of the semiconductor and, therefore, the effective coupling between different bands should not be surprising. This coupling, however, is proportional to $\mathbf{k}$. Thus, if the relevant excitations are relatively weak and smooth, then the main contribution into the semiconductor dynamics would come from small $\mathbf{k}$ and we can treat the respective band coupling as a perturbation. As the first step we could just drop this term. This, however, gives obviously wrong results for the dynamics near the extreme points of the bands. Indeed, the resulting Hamiltonian would predict that the mass of the excitations in the conductance band is the mass of electron in empty space and that the energy of states in the valence band increases with $\mathbf{k}$. Both of these predictions contradict the experiment. Thus, it is necessary to develop a consistent procedure that allows taking the band coupling into account, similarly to the perturbation theory in quantum mechanics. Unfortunately, a straightforward implementation of this approach is significantly complicated by the complexity of the semiconductor band structure. It poses not principal, but technical difficulties, the resolution of which requires developing a special approach employing the symmetry properties of the semiconductor lattice. These questions are beyond the scope of the present consideration (see, e.g., Chapter III in Bir and Pikus (1974)), therefore we limit ourselves to a semiqualitative analysis, which clearly illustrates the main ideas and can be readily adopted for a particular situation, for example for studying the effect of the static magnetic field and so on.

In order to eliminate the off-diagonal elements of the eigen-part of the Hamiltonian we perform a unitary Schrieffer-Wolff transformation $T = e^S$

$$b_{n,\mathbf{k}} = \sum_m \int d\mathrm{q}(n,\mathbf{k}|T|m,\mathbf{q})c_{m,\mathbf{q}}, \quad b^{\dagger}_{n,\mathbf{k}} = \sum_m \int d\mathbf{q}(m,\mathbf{q}|T^{\dagger}|n,\mathbf{k})c^{\dagger}_{m,\mathbf{q}} \tag{29.19}$$

such that the eigen-part of the transformed Hamiltonian $\tilde{\mathcal{H}}_{mat} = T^{\dagger}\mathcal{H}_{mat}T$ is *approximately* diagonal. In Bir and Pikus (1974) a general procedure is discussed, which allows developing the respective perturbation theory up to any order. Here, however, we restrict ourselves to the first relevant order, as it is usually done in the $\mathbf{k}\cdot\mathbf{p}$-approximation. In terms of the "generator" S the transformed Hamiltonian is written as

$$\tilde{\mathcal{H}}_{mat} = \mathcal{H}_{mat} + [\mathcal{H}_{mat}, S] + \frac{1}{2}[[\mathcal{H}_{mat}, S], S] + \cdots \tag{29.20}$$

where $[A,B] = AB - BA$ denotes the usual matrix commutator. We want to treat different contributions on the different basis and therefore we present the Hamiltonian as $\mathcal{H}_{mat} = \mathcal{H}_0 + \mathcal{H}_p + \mathcal{H}_A$, where $\mathcal{H}_0$ stands for the diagonal part of the first term in the r.h.s. of Equation 29.17, $\mathcal{H}_p$ is the $\mathbf{k}\cdot\mathbf{p}$ part and $\mathcal{H}_A$ is the term related to the external field. Using this presentation in Equation 29.20 we obtain

$$\begin{aligned}\tilde{\mathcal{H}}_{mat} = {} & \mathcal{H}_0 + \mathcal{H}_p + \mathcal{H}_A + [\mathcal{H}_0, S] + [\mathcal{H}_p, S] + [\mathcal{H}_A, S] \\ & + \frac{1}{2}[[\mathcal{H}_0, S], S] + \frac{1}{2}[[\mathcal{H}_p, S], S] + \frac{1}{2}[[\mathcal{H}_A, S], S] + \cdots\end{aligned} \tag{29.21}$$

Since the $\mathbf{k}\cdot\mathbf{p}$-coupling between the bands is small, the transformation diagonalizing the Hamiltonian is close to identical and, hence, the generator S is in some sense small $\sim\mathbf{k}\cdot\mathbf{p}$. Therefore, in the lowest order no contributions come from the terms not shown in Equation 29.21 and, moreover, we need to drop the term $[[\mathcal{H}_p, S], S]$.

We choose S in such a way that the off-diagonal part of $\mathcal{H}_p$ is canceled in the leading order of $\mathbf{k}\cdot\mathbf{p}$. Or, since the diagonal part of $\mathcal{H}_p$ is 0, we find such S that

$$\mathcal{H}_p + [\mathcal{H}_0, S] = 0. \tag{29.22}$$

Resolving this equation with respect to the matrix elements of S yields

$$(n,\mathbf{k}|S|n',\mathbf{k}') = -\frac{\hbar\mathbf{k}\cdot\mathbf{p}_{nn'}}{m\omega_{nn'}}\delta(\mathbf{k}-\mathbf{k}'), \tag{29.23}$$

where $\omega_{nn'} = \epsilon_n - \epsilon_{n'}$.

Using found S for the field related terms in Equation 29.21, we will have among the others the terms of the form $\mathbf{A}(\mathbf{q})\otimes\mathbf{q}$, where $\otimes$ denotes the tensor product, so that in a Cartesian basis $(\mathbf{k}\otimes\mathbf{q})_{ij} = k_i q_j$. Generally the tensor $\mathbf{A}(\mathbf{q})\otimes\mathbf{q}$ is not zero. Its trace vanishes because of the Coulomb gauge imposed on the vector potential, but there are no other general restrictions on its form. Such terms, however, can still be neglected because of the smoothness of the external field. Indeed, because of the slow spatial variation of $\mathbf{A}(\mathbf{x})$ the main contribution into $\mathbf{A}(\mathbf{q})$ arises from small $\mathbf{q}$, which leads to the essential reduction of the tensor $\mathbf{A}(\mathbf{q})\otimes\mathbf{q}$ comparing to the field terms contained in $\mathcal{H}_A$ non-commuted with S in Equation 29.21. Thus, we obtain the matrix elements of the transformed Hamiltonian

$$\begin{aligned}&\left(n,\mathbf{k}\,|\,\tilde{\mathcal{H}}_{mat}\,|\,n',\mathbf{k}'\right) \\ &= \left(\epsilon_n + \frac{\hbar^2 k^2}{2m}\right)\delta_{nn'}\delta(\mathbf{k}-\mathbf{k}') \\ &\quad + \frac{\hbar^2}{2m^2}\sum_{n''}\mathbf{k}\cdot\mathbf{p}_{nn''}\mathbf{k}\cdot\mathbf{p}_{n''n'}\left(\frac{1}{\omega_{nn''}} + \frac{1}{\omega_{n'n''}}\right) \\ &\quad - \frac{e}{m}\int d\mathbf{q}\left[\mathbf{A}(\mathbf{q})\cdot(\mathbf{p}_{nn'} + \hbar\mathbf{k}'\delta_{nn'}) - \frac{e}{2}A_2(\mathbf{q})\delta_{nn'}\right]\delta(\mathbf{k}-\mathbf{k}'-\mathbf{q}) \\ &\quad - \frac{\hbar e}{m^2}\sum_{n''}\int d\mathbf{q}\,\delta(\mathbf{k}-\mathbf{k}'-\mathbf{q})\left[\frac{\mathbf{k}\cdot\mathbf{p}_{n''n'}\mathbf{A}(\mathbf{q})\cdot\mathbf{p}_{nn''}}{\omega_{n'n''}} + \frac{\mathbf{k}\cdot\mathbf{p}_{nn''}\mathbf{A}(\mathbf{q})\cdot\mathbf{p}_{n''n'}}{\omega_{nn''}}\right].\end{aligned} \tag{29.24}$$

It should be noted that because of the smoothness property discussed above the field terms are symmetric with respect to the change $\mathbf{k}\leftrightarrow\mathbf{k}'$.

The Hamiltonian with the matrix elements given by Equation 29.24 looks quite complex and barely simpler than the initial Hamiltonian. In order to discuss the physical meaning of different contributions into Equation 29.24, we introduce the spatial field operators $c_n(\mathbf{x})$ and $c_n^\dagger(\mathbf{x})$ according to

$$c_{n,\mathbf{k}} = \frac{1}{(2\pi)^{3/2}}\int d\mathbf{x}\, c_n(\mathbf{x})e^{-i\mathbf{k}\cdot\mathbf{x}} \tag{29.25}$$

and the tensors $\mathsf{M}_{nn'}$ of effective masses

$$\frac{1}{\mathsf{M}_{nn'}} = \frac{1}{m}1\delta_{nn'} + \frac{1}{m^2}\sum_{n''}\left[\frac{\mathbf{p}_{n''n'}\otimes\mathbf{p}_{nn''}}{\omega_{nn''}} + \frac{\mathbf{p}_{nn''}\otimes\mathbf{p}_{n''n'}}{\omega_{n'n''}}\right]. \tag{29.26}$$

Additionally we need to analyze the different types of interband, $n \neq n'$, and intraband, $n = n'$, couplings induced by the external field. It can be seen that the main term of interest from the perspective of the semiconductor nonlinear response is $\propto\mathbf{A}(\mathbf{q})\cdot\mathbf{p}_{nn'}$, while all others can be neglected. Indeed, the terms $\propto\mathbf{A}\otimes\mathbf{k}$ describing the interband coupling vanish in the limit $k \to 0$, and thus their contribution is negligible in the region of validity of the $\mathbf{k}\cdot\mathbf{p}$-approximation. In turn, the effect of the terms yielding the intraband coupling is small provided the gap Δ between the valence and the conduction bands is relatively wide. As will be shown below (see Equation 29.56), the strong interaction of light with the semiconductor occurs when the frequency of the electromagnetic field is tuned into the resonance with the gap, $\hbar\omega \approx \Delta$. Thus, the intraband coupling is $\propto\hbar(\Delta T)^{-1}$, where T is the duration of the external excitation field, and even at (reasonably) short time scales it can be neglected.

Taking into account these considerations the semiconductor Hamiltonian takes a compact form

$$\tilde{\mathcal{H}}_{mat} = \sum_{n,n'}\int d\mathbf{x}\, c_n^\dagger(\mathbf{x})\left[\epsilon_n\delta_{nn'} - \nabla\cdot\frac{\hbar^2}{2\mathsf{M}_{nn'}}\cdot\nabla - \mathbf{A}(\mathbf{x})\cdot\mathbf{d}_{nn'}\right]c_{n'}(\mathbf{x}), \tag{29.27}$$

where $\mathbf{d}_{nn'} = \mathbf{p}_{nn'}e/m$. This representation clarifies the physical meaning of the operators $c_n^\dagger(\mathbf{x})$. These are the field operators of quasiparticles corresponding to different bands and characterized by specific tensors of the effective mass. The logic of perturbative treatment of the band coupling implies neglecting the off-diagonal elements $\mathsf{M}_{nn'}$ for $n \neq n'$ as the respective correction are of higher order in $\mathbf{k} \cdot \mathbf{p}$ than those kept for derivation of Equation 29.27. This naturally leads to the definition of the effective masses M_{nn} of the respective bands. The explicit expression for the tensors of the effective mass given by $n = n'$ elements of Equation 29.26 gives the correct prediction of significant reduction of the masses compared to the electron mass in the empty space and even the negative sign of the mass of the upper valence bands, it also describes correctly the dependence on the width of the gap. However, it lacks more subtle but nevertheless important features, such as the mixing of heavy and light holes.

In order to discuss these features, we inspect closely the semiconductor band structure (see, e.g., Chapter 2 in Yu and Cardona (2004)). If the electrons were spinless, the lowest energy bands were the valence and conduction bands. In semiconductors with diamond- or zinc-blende structures (e.g., Ge, GaAs, InP) the valence band would be threefold degenerate. It turns out that under rotations which map the lattice into itself the states belonging to this band transform similarly to the states with the orbital momentum $\ell = 1$. Because of this, the band is called* $\Gamma_{4\upsilon}$. The states in the conduction band transform trivially, and in group-theoretical terms the band is called Γ_{1c}. In addition to this one needs to take into account the twofold degeneracy of each state due to the electron spin. This makes the conduction band twofold and the valence band sixfold degenerate. Directly it does not imply divergence of the terms in Equations 29.23 and 29.26 corresponding to the degenerate bands because the respective matrix elements of the momentum operator are zero. This, however, does imply certain sensitivity of these bands to the external perturbations. The interaction, which takes advantage of the degeneracy, is the spin–orbit interaction originating from the dependence of the electron energy on the orientation of the spin in spatially inhomogeneous potential (see, e.g., Chapter XII in Schiff (1949)). The spin–orbit interaction leads to partial lifting of the degeneracy forming the semiconductor band structure schematically shown in Figure 29.1.

Thus, in order to be able to describe the complex picture of the band coupling in semiconductors, we need to consider the tensors of the effective masses as phenomenological parameters and, in particular, to keep the interband tensors $\mathsf{M}_{n,n'}$ with $n \neq n'$. The great simplification comes from the consideration of restrictions imposed on the form of these tensors due to the lattice symmetry. Since the semiconductor lattice turns into itself under the action of the point symmetry group so does Hamiltonian (29.27). For a general set of tensors of the effective masses $\mathsf{M}_{n,n'}$ it might not be the case, thus the symmetry implies that these tensors must have a special structure. This line of arguments was implemented and clearly explained in the series of papers by Luttinger and Kohn (1955, Luttinger 1956).



FIGURE 29.1 Effects of the spin–orbit interaction on the semiconductor band structure. The vertical lines indicate the subbands in the valence and conduction bands, between which the matrix elements of the momentum operator are not zero, together with the helicity of the respective transition. The convention for masses is shown.

Studying these restrictions shows that in the conduction band the tensors of the effective masses are decoupled from all bands and are trivial $\mathsf{M}_{s,s'} = 1m_e\delta_{s,s'}$, where 1 is the unit tensor, and $\mathsf{M}_{s,\sigma} = \mathsf{M}_{\sigma,s} \equiv 0$. The tensors of the effective masses of the heavy and light holes are coupled $\mathsf{M}_{\sigma,\sigma'} \neq 0$ leading to the heavy–light hole hybridization. Additionally, the principal values of the tensors are not equal to each other leading to the anisotropy of the effective masses. It should be noted, however, that the anisotropy usually is not very strong and the mixing of the heavy and light holes is $\propto k^2$ and for small k the effect of hybridization is also small. This supports the popular approximation of spherical, decoupled heavy-hole and light-hole bands widely used for description of the semiconductor weak excitations. We also will use it for the qualitative discussions of some questions while keeping the main equations as general as possible.

So far we considered the case of a homogeneous semiconductor. In order to complete the derivation of the effective Hamiltonian we need to consider the spatial variation of the energies of the conduction and the valence bands due to the variation of composition and to include the terms responsible for the effect of the external static field and the Coulomb interaction between the electrons. To this end we take into consideration the last two terms in Hamiltonian (29.1) and substitute $\epsilon_n(\mathbf{x})$ for the variation of the bands edges. Generally, strong coordinate dependence of $\epsilon_n(\mathbf{x})$ would break the whole line of arguments, which allowed us to derive Equation 29.27 and to introduce the effective masses. It turns out, however, that as small as 10 elementary cells are sufficient for the approximation of effective mass to work. In particular, it can be safely applied for the description of the semiconductor quantum dots. Thus, the assumption of smoothness is fulfilled for composition-induced variations of the band edges (quantum heterostructures (Ivchenko 2005) or random interface fluctuations (Langbein et al. 2004)). It also usually holds for the external electric field (e.g., in the case of studying the quantum-confined Stark effect (Schmitt-Rink et al. 1989) on the optical semiconductor response). This assumption is employed in the standard manner. Taking into account that the main contribution into the dynamics comes from the small **k** part of Hamiltonian (29.24), one can show the validity of the important relation

---

* Strictly speaking, the correct formulation should sound like "the states transform according to irreducible representation Γ_4 of the point symmetry group of the lattice." Detailed and practical introduction into the group theory can be found in Yu and Cardona (2004) and Bir and Pikus (1974).

$$\int d\mathbf{x}\, f(\mathbf{x})\chi^{*}_{n,\mathbf{k}}(\mathbf{x})\chi_{n',\mathbf{k}'}(\mathbf{x}) = \delta_{n,n'}\int \frac{d\mathbf{x}}{(2\pi)^3} f(\mathbf{x})e^{-i(\mathbf{k}-\mathbf{k}')\cdot\mathbf{x}} \tag{29.28}$$

for sufficiently smooth $f(\mathbf{x})$. The key element is to observe that if the spatial Fourier spectrum $f(\mathbf{q})$ falls off fast enough, then $\delta(\mathbf{k}' - \mathbf{k} + \mathbf{q} = \mathbf{Q})$, with $\mathbf{Q}$ being the vector of the reciprocal lattice, reaches its singularity only when $\mathbf{Q} = 0$, or, in solid-state theory terms that the Umklapp processes can be neglected. Using relation (29.28) makes the transformation to the field operators $c_n(\mathbf{x})$, following Equations 29.16 and 29.19, trivial.

The Coulomb potential $V(\mathbf{x})$ is singular at the origin, therefore, generally its variation over an elementary cell is not small. However, the effect of the motion of electrons when they are extremely close to each other is not significant for the problem of the optical response. The strongest effect of the Coulomb interaction can be expected when it leads to the formation of bound states (excitons). The typical distance between the particles in such states significantly exceeds the lattice constants and the details of the behavior of the interaction potential at the origin are not important. Therefore, with good accuracy the Coulomb potential can be considered as slowly varying and one can apply relation (29.28).

Collecting these considerations, we can write down the full Hamiltonian in terms of the operators $c_n(\mathbf{x})$ and $c_n^{\dagger}(\mathbf{x})$

$$\begin{aligned}\mathcal{H}_{mat} = &\sum_{n,m}\int d\mathbf{x}\, c_n^{\dagger}(\mathbf{x})\left[\epsilon_n(\mathbf{x})\delta_{nm} - \nabla\cdot\frac{\hbar^2}{2\mathrm{M}_{nm}}\cdot\nabla - \mathbf{A}(\mathbf{x})\cdot\mathbf{d}_{nm}\right]c_m(\mathbf{x})\\ &+\frac{1}{2}\sum_{n,m}\int d\mathbf{x}_1\, d\mathbf{x}_2\, c_n^{\dagger}(\mathbf{x}_1)c_m^{\dagger}(\mathbf{x}_2)V(\mathbf{x}_1-\mathbf{x}_2)c_m(\mathbf{x}_2)c_n(\mathbf{x}_1).\end{aligned} \tag{29.29}$$

29.3 Quantum Equations of Motion

The main object of interest while studying the nonlinear response is the time dependence of observables such as the macroscopic electromagnetic field $\mathbf{A}(\mathbf{x}) = \langle\hat{\mathbf{A}}(\mathbf{x})\rangle$. These are determined by the state of the whole electromagnetic field–matter system. For example, if the system is in the coherent regime, that is, if the system can be described by the vector of state $|\Phi(t)\rangle$, then

$$\mathbf{A}(\mathbf{x}) = \langle\Phi(t)|\hat{\mathbf{A}}(\mathbf{x})|\Phi(t)\rangle = \langle\Phi(0)|U^{\dagger}(t;t_0)\hat{\mathbf{A}}(\mathbf{x})U(\mathrm{t};\mathrm{t}_0)|\Phi(0)\rangle, \tag{29.30}$$

where $|\Phi(0)\rangle$ is the initial state of the system and the time dependence of the system state $|\Phi(t)\rangle = U(t;t_0)|\Phi(0)\rangle$ is written in terms of the evolution operator

$$U(t;t_0) = \mathcal{T}_{+}\exp\left[-\frac{i}{\hbar}\int_{t_0}^{t} dt'\mathcal{H}(t')\right] \tag{29.31}$$

with $\mathcal{T}_{+}$ being the standard time-ordering operator. Here we have taken into account that the Hamiltonian may explicitly depend on time because of the presence of the external driving electromagnetic field.

The same ideology works also if the initial state is a mixture (e.g., thermal equilibrium) and therefore it should be described by the density matrix $\hat{\rho}(0)$. If there are no decohering processes, then one has

$$\mathbf{A}(\mathbf{x}) = \mathbf{Tr}\left[\hat{\rho}(t)\hat{\mathbf{A}}(\mathbf{x})\right] = \mathrm{Tr}\left[\hat{\rho}(0)U^{\dagger}(t;t_0)\hat{\mathbf{A}}(\mathbf{x})U(t;t_0)\right]\hat{\rho}(0). \tag{29.32}$$

Here we have explicitly spelled out the time dependence of the density matrix in the absence of the incoherent processes $\hat{\rho}(t) = U(t;t_0)\hat{\rho}(t)U^{\dagger}(t;t_0)$. The situation, however, becomes more complex when the decohering processes, for example, interaction with bath's phonons, is present. This problem can be treated rigorously using special methods (see, e.g., Chapter 3 in Mukamel (1995)), which are beyond the scope of the present consideration because they are somewhat excessive for the problem of finding the macroscopic electromagnetic field when a simple introduction of a phenomenological decay of the macroscopic polarization usually suffices.

The typical structure

$$\hat{O}(t) = U^{\dagger}(t;t_0)\hat{O}U(t;t_0) \tag{29.33}$$

appearing in Equations 29.30 and 29.32 defines the *Heisenberg representation* of the field operator $\hat{O}$. Since this representation plays the same role whether the initial state is coherent or not, it is often more convenient to study its time dependence rather than directly the time dependence of the state of the system or its density matrix. It can be easily checked that the time evolution of $\hat{O}(t)$ is governed by the Heisenberg equations of motion.

$$i\hbar\frac{\partial\hat{O}}{\partial t} = \left[\hat{O},\mathcal{H}\right]. \tag{29.34}$$

Since the explicit time dependence of the Hamiltonian does not change the derivation of the main equations of motion (all operators entering Equation 29.34 are taken at the same instant), we will omit the time argument in what follows.

29.3.1 Electromagnetic Field

We begin the general analysis of the semiconductor optical response from the derivation of the equations of motion of the electromagnetic field. The commutator in this equation is found using the commutation relation for the electromagnetic field in the Coulomb gauge (Cohen-Tannoudji et al. 1992)

$$\left[\hat{A}_j(\mathbf{x}_1),\ \epsilon_0\frac{\partial}{\partial t}\hat{A}_l(\mathbf{x}_2)\right] = \frac{i\hbar\delta_{jl}}{n^2(\mathbf{x}_1)}\delta^{\perp}(\mathbf{x}_1-\mathbf{x}_2), \tag{29.35}$$

where

$n(\mathbf{x})$ is the refractive index, which is allowed to be spatially inhomogeneous

j and l denote the Cartesian coordinates

$\hat{\delta}^{\perp}(\mathbf{x})$ is the transverse δ-function (Cohen-Tannoudji et al. 1992)

As Helmholtz's theorem (Arfken and Weber 2005) states any vector field $\mathbf{V}(\mathbf{x})$ can be presented as the sum of irrotational and solenoidal parts, $\mathbf{U}(\mathbf{x}) = \mathbf{U}_l(\mathbf{x}) + \mathbf{U}_t(\mathbf{x})$ with $\nabla \times \mathbf{U}_l(\mathbf{x}) \equiv 0$ and $\nabla \cdot \mathbf{U}_t(\mathbf{x}) \equiv 0$. The convolution of the vector field with the transverse δ-function returns the value of the solenoidal component $\mathbf{V}_r(\mathbf{x})$ at the point of singularity

$$\int d\mathbf{x}' \, \hat{\delta}^{\perp}(\mathbf{x} - \mathbf{x}')\mathbf{U}(\mathbf{x}') = \mathbf{U}_t(\mathbf{x}). \tag{29.36}$$

The Hamiltonian of the electromagnetic field has the standard form

$$\mathcal{H}_F = \frac{\epsilon_0}{2} \int d\mathbf{x} \left[n^2(\mathbf{x}) E^2(\mathbf{x}, t) + c^2 B^2(\mathbf{x}, t) \right], \tag{29.37}$$

where the transverse electric and magnetic fields are defined in terms of the vector potential as $\mathbf{E}(\mathbf{x}) = -\partial \mathbf{A}(\mathbf{x})/\partial t$ and $\mathbf{B}(\mathbf{x}) = \nabla \times \mathbf{A}(\mathbf{x})$. Substituting into Equation 29.34 $\mathcal{H} = \mathcal{H}_F + \mathcal{H}_{mat}$, where $\mathcal{H}_{mat}$ is given by Equation 29.29 one obtains the *quantum* equations of motion for the electromagnetic field

$$\frac{n^2(\mathbf{x})}{c^2} \ddot{\hat{\mathbf{A}}} = \nabla^2 \hat{\mathbf{A}} + \mu_0 \sum_{n,m} \int d^3\mathbf{x}' \, \hat{\delta}^{\perp}(\mathbf{x} - \mathbf{x}') \mathbf{d}_{nm} c_n^{\dagger}(\mathbf{x}') c_m(\mathbf{x}'). \tag{29.38}$$

This equation has the standard form of the inhomogeneous wave equation for the vector potential with the integral in the r.h.s. representing the current source.

Writing Equation 29.38 we have taken into account that $\nabla \cdot \mathbf{A}$ vanishes in the Coulomb gauge used for derivation of Equation 29.27. Since, generally, the vector field $\mathbf{U}(\mathbf{x}) = \mu_0 \sum_{n,m} \mathbf{d}_{nm} c_n^{\dagger}(\mathbf{x}) c_m(\mathbf{x})$ is not necessarily solenoidal, the presence of the transverse δ-function in the r.h.s. of Equation 29.38 is important to ensure that at any instant $\hat{\mathbf{A}}(\mathbf{x})$ does not violate the Coulomb gauge. Clearly, if one replaces the transverse δ-function by the usual (local) δ-function it implies effective adding to the source the irrotational component of $\mathbf{U}(\mathbf{x})$. According to Equation 29.36, the convolution of $\mathbf{U}(\mathbf{x})$ with the transverse δ-function is $\int d\mathbf{x}' \, \tilde{\hat{\delta}}^{\perp}(\mathbf{x} - \mathbf{x}')\mathbf{U}(\mathbf{x}') = \mathbf{U}(\mathbf{x}) - \mathbf{U}_l(\mathbf{x})$. Equation 29.38 is linear, therefore $\hat{\mathbf{A}}(\mathbf{x})$ can be presented as a superposition of two components, $\hat{\mathbf{A}}(\mathbf{x}) = \tilde{\hat{\mathbf{A}}}(\mathbf{x}) + \hat{\mathbf{A}}_l(\mathbf{x})$, which satisfy the wave equation of the same form as Equation 29.38, with $\mathbf{U}(\mathbf{x})$ and $-\mathbf{U}_l(\mathbf{x})$ serving as sources. Since $\mathbf{U}_l(\mathbf{x})$ is irrotational it can be presented as a gradient of a scalar function $\mathbf{U}_l(\mathbf{x}) = -\nabla\varphi(\mathbf{x})$. Furthermore, following the standard line of arguments as in electrostatics we obtain

$$\varphi(\mathbf{x}) = \frac{1}{4\pi} \int d\mathbf{x}' \frac{\nabla \cdot \mathbf{U}(\mathbf{x}')}{|\mathbf{x} - \mathbf{x}'|}. \tag{29.39}$$

Thus $\varphi(\mathbf{x})$ has the same form as the potential created by the charge spatially distributed with the density $\epsilon_0 \nabla \cdot \mathbf{U}(\mathbf{x})$. If $\tilde{\hat{\mathbf{A}}}(\mathbf{x})$ satisfies the same initial conditions as $\hat{\mathbf{A}}(\mathbf{x})$ the component $\hat{\mathbf{A}}_l(\mathbf{x})$ is early shown to be irrotational and, hence, it does not contribute to the outgoing radiation field but leads to a modification of the electron–electron interaction. This modification identically vanishes in many important physical situations, such as the excitation by the normally incident wave at a frequency tuned to the response with the heavy-hole excitons. While a rigorous study of the effect of $\hat{\mathbf{A}}_l(\mathbf{x})$ on the semiconductor dynamics is yet to be conducted, it can be conjectured that for the problems which will be studied below the respective correction of the electron–electron interaction is rather small and can be neglected; in other words one can approximate $\hat{\mathbf{A}}(\mathbf{x}) \approx \tilde{\hat{\mathbf{A}}}(\mathbf{x})$. This significantly simplifies Equation 29.38 since we can use the conventional δ-function instead of $\hat{\delta}^{\perp}(\mathbf{x} - \mathbf{x}')$ and perform the integration over $\mathbf{x}'$, obtaining

$$\frac{n^2(\mathbf{x})}{c^2} \ddot{\hat{\mathbf{A}}}(\mathbf{x}) = \nabla^2 \hat{\mathbf{A}}(\mathbf{x}) + \mu_0 \sum_{n,m} \mathbf{d}_{nm} c_n^{\dagger}(\mathbf{x}) c_m(\mathbf{x}). \tag{29.40}$$

This equation completely describes the electromagnetic field driven by the semiconductor excitations. The macroscopic field, as has been discussed above, is found by averaging $\hat{\mathbf{A}}(\mathbf{x})$ over the state of the combined semiconductor-field system. It should be noted, however, that Equation 29.40 can also be used in a more general context to find higher-order moments of the field, for example, single- or two-photon density matrix and so on.

29.3.2 Semiconductor Dynamics

The current, which enters the equation of motion of the electromagnetic field as a source, is determined by the operator of the interband polarization $c_n^{\dagger}(\mathbf{x}_1) c_m(\mathbf{x}_2)$ taken at the diagonal $\mathbf{x}_1 = \mathbf{x}_2$. Its time evolution is governed by the Heisenberg equation of motion (29.34). The electron operators obey the canonical anticommutation relation.

$$\left\{ c_n^{\dagger}(\mathbf{x}_1), c_m(\mathbf{x}_2) \right\} = \hbar \delta_{n,m} \delta(\mathbf{x}_1 - \mathbf{x}_2), \tag{29.41}$$

where $\{A, B\} = AB + BA$. The commutator $\left[c_n^{\dagger}(\mathbf{x}_1) c_m(\mathbf{x}_2), \mathcal{H} \right]$ is expressed in terms of the anticommutators using the relation, which holds for any four operators

$$[AB, CD] = A\{B, C\}D - \{A, C\}BD + CA\{B, D\} - C\{A, D\}B. \tag{29.42}$$

Substituting $\mathcal{H} = \mathcal{H}_F + \mathcal{H}_{mat}$ we obtain

$$\begin{aligned} i\hbar\frac{\partial}{\partial t}c_n^{\dagger}(\mathbf{x}_1)c_m(\mathbf{x}_2) = {} & \left[\epsilon_m(\mathbf{x}_2) - \epsilon_n(\mathbf{x}_1)\right]c_n^{\dagger}(\mathbf{x}_1)c_m(\mathbf{x}_2) \\ & + \sum_{j,k}\Bigg[\delta_{km}\nabla_1 \cdot \frac{\hbar^2}{2\mathsf{M}_{jn}} \cdot \nabla_1 - \delta_{jn}\nabla_2 \cdot \frac{\hbar^2}{2\mathsf{M}_{mk}} \cdot \nabla_2 \\ & + \delta_{mk}\hat{\mathbf{A}}(\mathbf{x}_1) \cdot \mathbf{d}_{jn} - \delta_{jn}\hat{\mathbf{A}}(\mathbf{x}_2) \cdot \mathbf{d}_{mk}\Bigg]c_j^{\dagger}(\mathbf{x}_1)c_k(\mathbf{x}_2) \\ & + c_n^{\dagger}(\mathbf{x}_1)\sum_j \int d\mathbf{x}'\left[V(\mathbf{x}_2 - \mathbf{x}') - V(\mathbf{x}_1 - \mathbf{x}')\right] \\ & \times c_j^{\dagger}(\mathbf{x}')c_j(\mathbf{x}')c_m(\mathbf{x}_2) \end{aligned} \tag{29.43}$$

where indices at ∇'s denote the number of the spatial variables they act on. The form of Equation 29.43 shows why it is not enough to consider directly the time dependence of the operator $c_n^{\dagger}(\mathbf{x}_1)c_m(\mathbf{x}_2)$ at the diagonal $\mathbf{x}_1 = \mathbf{x}_2$. Because of the presence of the spatial derivatives the rate of change of the operator at the diagonal is determined by the value the operator takes at the neighboring points requiring, thereby, studying the general case $\mathbf{x}_1 \neq \mathbf{x}_2$.

Equation 29.43 is presented in a general form unifying the conduction and the valence bands. This makes a constructive analysis difficult because the excitations belonging to different bands have distinctively different properties, for example, the mass of excitations in the conduction band (electrons) is positive while in the valence band (holes) it is negative. In order to account for these differences it is convenient to introduce special field operators for holes. It is done following the simple rule—creation of an electron in the valence band corresponds to annihilation of a hole and vice versa. As has been discussed above, different subbands in the valence and the conduction bands are enumerated by the projection of the angular momentum ($j = 1/2$ and $j = 3/2$ for the conduction and the valence bands, respectively). Thus, we introduce the hole operators according to $\upsilon_\sigma^{\dagger}(\mathbf{x}) \equiv c_{\upsilon,\sigma}(\mathbf{x})$ and $\upsilon_\sigma(\mathbf{x}) \equiv c_{\upsilon,\sigma}^{\dagger}(\mathbf{x})$. For the electrons in the conduction band we leave the same notation but will keep only the index corresponding to the spin of the electron so that $c_s^{\dagger}(\mathbf{x}) \equiv c_{c,s}^{\dagger}(\mathbf{x})$.

Rewriting Equation 29.43 in terms of the electron and hole operators is straightforward but is not free from the formal difficulties related to the fact that the holes exist on the background of all electrons filling the valence band. In a sense, in order to create a hole, one first needs to fill completely the valence band and then remove one electron. This naturally leads to divergences of the Coulomb energy. In order to demonstrate one kind of divergence let us consider the Coulomb term, which appears at the r.h.s. of Equation 29.43 for $n = \{c, s_1\}$, $m = \{c, s_s\}$ and $j = \{\upsilon, \sigma\}$

$$c_{s_1}^{\dagger}(\mathbf{x}_1)\int \mathrm{d}\mathbf{x}'\left[V(\mathbf{x}_2 - \mathbf{x}') - V(\mathbf{x}_1 - \mathbf{x}')\right]\upsilon_\sigma(\mathbf{x}')\upsilon_\sigma^{\dagger}(\mathbf{x}')c_{s_1}(\mathbf{x}_2). \tag{29.44}$$

If one tries to rewrite this expression in the normal form, that is, with all the creation operators collected on the left, one gets an additional term $\propto\{\upsilon_\sigma(\mathbf{x}'), \upsilon_\sigma^{\dagger}(\mathbf{x}')\} = \hbar\delta(\mathbf{x}' - \mathbf{x}')$, which is infinite if not meaningless. There are different ways to work around this divergence. One of them is to consider Equation 29.44 as a continuous limit of the respective model formulated in a discrete space, where the field operators taken at different cells of the space anticommute to Kronecker's δ so that $\left\{\upsilon_{\sigma,\mathbf{x}}, \upsilon_{\sigma,\mathbf{x}'}^{\dagger}\right\} = N\delta_{\mathbf{x},\mathbf{x}'}$ with some constant N. This gives for the term proportional to the anticommutator

$$c_{s_1,\mathbf{x}_1}^{\dagger}c_{s_1,\mathbf{x}_2}N\sum_{\mathbf{x}'}\left[V_{\mathbf{x}_2-\mathbf{x}'} - V_{\mathbf{x}_1-\mathbf{x}'}\right]. \tag{29.45}$$

Truncating the Coulomb potential $V_{\mathbf{x}}$ at infinity we see that this term vanishes regardless of the parameters of the truncation and the discretization. Thus, we can conclude that these divergencies do not contribute to the equations of motion.

A more different obstacle is the divergent band-gap renormalization, which enters the equations of motion in the form $\epsilon_\sigma \to \epsilon_\sigma + V(0)$. This divergence is of the same origin as the previous one but it cannot be discarded as easily. The reason is that we have introduced the band edges as the solutions of a single-electron problem, while the hole sees the band edges in the presence of all the electrons filling the valence band minus one. Therefore, the renormalization is a real physical effect. We incorporate it in the theory in a similar way as the elementary-charge renormalization is dealt with in quantum field theory. We will consider from now on that the hole energy offset $\epsilon_\sigma(\mathbf{x})$ in the equations of motion is the genuine one. This can be done because the actual band gap between the conduction and valence bands is directly observable (see, e.g., Equation 29.56).

Taking into account these considerations we obtain

$$\begin{aligned} & i\hbar\frac{\partial}{\partial t}\upsilon_\sigma^{\dagger}(\mathbf{x}_1)c_s^{\dagger}(\mathbf{x}_2) \\ & = \upsilon_\sigma^{\dagger}(\mathbf{x}_1)c_s^{\dagger}(\mathbf{x}_2)\left[\epsilon_\sigma(\mathbf{x}_1) + \hat{U}_\Delta(\mathbf{x}_1) - \epsilon_s(\mathbf{x}_2) - \hat{U}_\Delta(\mathbf{x}_2) + V(\mathbf{x}_1 - \mathbf{x}_2)\right] \\ & \quad + \frac{\hbar^2}{2}\left(\frac{1}{m_e}\nabla_2^2 + \sum_{\sigma'}\nabla_1 \cdot \frac{1}{\mathsf{M}_{\sigma,\sigma'}} \cdot \nabla_1\right) \times \upsilon_{\sigma'}^{\dagger}(\mathbf{x}_1)c_s^{\dagger}(\mathbf{x}_2) \\ & \quad - \hat{\mathbf{A}}(\mathbf{x}_1) \cdot \mathbf{d}_{\sigma,s}\delta(\mathbf{x}_1 - \mathbf{x}_2) + \sum_{s'}\hat{\mathbf{A}}(\mathbf{x}_1) \cdot \mathbf{d}_{\sigma,s'}c_s^{\dagger}(\mathbf{x}_2)c_{s'}(\mathbf{x}_1) \\ & \quad + \sum_{\sigma'}\hat{\mathbf{A}}(\mathbf{x}_2) \cdot \mathbf{d}_{\sigma',s}\upsilon_{\sigma'}^{\dagger}(\mathbf{x}_1)\upsilon_\sigma(\mathbf{x}_2), \\[2ex] & i\hbar\frac{\partial}{\partial t}c_{s_1}^{\dagger}(\mathbf{x}_1)c_{s_2}(\mathbf{x}_2) \\ & = c_{s_1}^{\dagger}(\mathbf{x}_1)\left[\epsilon_{s_2}(\mathbf{x}_2) + \hat{U}_\Delta(\mathbf{x}_2) - \epsilon_{s_1}(\mathbf{x}_1) - \hat{U}_\Delta(\mathbf{x}_1)\right]c_{s_2}(\mathbf{x}_2) \\ & \quad + \frac{\hbar^2}{2m_e}(\nabla_1^2 - \nabla_2^2)c_{s_1}^{\dagger}(\mathbf{x}_1)c_{s_2}(\mathbf{x}_2) \\ & \quad + \sum_{\sigma'}\left[\hat{\mathbf{A}}(\mathbf{x}_2) \cdot \mathbf{d}_{s_2,\sigma'}\upsilon_{\sigma'}^{\dagger}(\mathbf{x}_2)c_{s_1}^{\dagger}(\mathbf{x}_1) - \hat{\mathbf{A}}(\mathbf{x}_1) \cdot \mathbf{d}_{\sigma',s_1}c_{s_2}(\mathbf{x}_2)\upsilon_{\sigma'}(\mathbf{x}_1)\right], \\[2ex] & i\hbar\frac{\partial}{\partial t}\upsilon_{\sigma_2}^{\dagger}(\mathbf{x}_2)\upsilon_{\sigma_1}(\mathbf{x}_1) \\ & = \upsilon_{\sigma_2}^{\dagger}(\mathbf{x}_2)\left[\epsilon_{\sigma_2}(\mathbf{x}_2) + \hat{U}_\Delta(\mathbf{x}_2) - \epsilon_{\sigma_1}(\mathbf{x}_1) - \hat{U}_\Delta(\mathbf{x}_1)\right]\upsilon_{\sigma_1}(\mathbf{x}_1) \\ & \quad + \frac{\hbar^2}{2}\sum_{\sigma',\sigma''}\left(\nabla_1 \cdot \frac{\delta_{\sigma'',\sigma_2}}{\mathsf{M}_{\sigma',\sigma_1}} \cdot \nabla_1 - \nabla_2 \cdot \frac{\delta_{\sigma',\sigma_1}}{\mathsf{M}_{\sigma_2,\sigma''}} \cdot \nabla_2\right)\upsilon_{\sigma''}^{\dagger}(\mathbf{x}_2)\upsilon_{\sigma'}(\mathbf{x}_1) \\ & \quad + \sum_{s'}\left[\hat{\mathbf{A}}(\mathbf{x}_1) \cdot \mathbf{d}_{s',\sigma_1}\upsilon_{\sigma_2}^{\dagger}(\mathbf{x}_2)c_{s'}^{\dagger}(\mathbf{x}_1) - \hat{\mathbf{A}}(\mathbf{x}_2) \cdot \mathbf{d}_{\sigma_2,s'}c_{s'}(\mathbf{x}_2)\upsilon_{\sigma_1}(\mathbf{x}_1)\right], \end{aligned} \tag{29.46}$$

where

$$\hat{U}_\Delta(\mathbf{x}) = \int d\mathbf{x}'\, V(\mathbf{x}-\mathbf{x}')\left[\sum_{s'} c^\dagger_{s'}(\mathbf{x}')c_{s'}(\mathbf{x}') - \sum_{\sigma'} \upsilon^\dagger_{\sigma'}(\mathbf{x}')\upsilon_{\sigma'}(\mathbf{x}')\right]. \tag{29.47}$$

Equations 29.40 and 29.46 describe the coupled dynamics of the electromagnetic field and the semiconductor excitations in the endless variety of physical situations. They can be used for studying the modification of the radiative decay of the semiconductor excitations in photonic crystals (Sakoda 2005) or the speckle pattern caused by electron scattering on surface inhomogeneities of quantum wells and so on. In what follows we will be mostly interested in the effect of the many-body correlations on the nonlinear optical response and, therefore, we make the proper simplifications of the problem. We assume that the life time of a photon in the structure is not too long so that the polaritons, which are the coupled states of the photons and the semiconductor excitations, are not formed. In this case one can neglect the reabsorption of the photons emitted in the course of the radiative decay. This significantly simplifies the analysis of Equations 29.40 and 29.46 because now we can consider $\mathbf{A}(\mathbf{x})$ in Equation 29.46 as the external *classical* excitation field, solve Equation 29.46 for $c^\dagger_n(\mathbf{x}_1)c_m(\mathbf{x}_2)$, and then find the field produced by the semiconductor excitation using Equation 29.40.

29.3.3 Rotating Wave Approximation

The interaction of light with the semiconductor has a strong resonant character when the frequency of the excitation field, Ω, sweeps the vicinity of the gap, $\hbar\Omega \sim \Delta$. In order to see how the resonances show up in the equations of motion we consider Equations 29.46 in the linear approximation when we need only the equation with respect to the operator of the interband polarization

$$i\hbar\frac{\partial}{\partial t}\upsilon^\dagger_\sigma(\mathbf{x}_2)c^\dagger_s(\mathbf{x}_1) = -\hat{L}_{\sigma,s}\upsilon^\dagger_\sigma(\mathbf{x}_2)c^\dagger_s(\mathbf{x}_1) - \mathbf{A}(\mathbf{x}_1)\cdot\mathbf{d}_{\sigma,s}\delta(\mathbf{x}_1-\mathbf{x}_2), \tag{29.48}$$

where the operator $\hat{L}_{\sigma,s}$ is defined as

$$\hat{L}_{\sigma,s} = \epsilon_s(\mathbf{x}_1) - \epsilon_\sigma(\mathbf{x}_2) - V(\mathbf{x}_1-\mathbf{x}_2) - \frac{\hbar^2}{2}\left(\frac{1}{m_e}\nabla_1^2 + \nabla_2\cdot\frac{1}{\mathsf{M}_\sigma}\cdot\nabla^2\right). \tag{29.49}$$

We have also neglected the heavy-hole–light-hole mixing setting $\mathsf{M}_{\sigma',\sigma} = \delta_{\sigma',\sigma}\mathsf{M}_\sigma$. This does not make principle changes in the character of the following consideration, but greatly simplifies the notation.

Next we employ the spectral representation of the operator $\hat{L}_{\sigma,s}$

$$\hat{L}_{\sigma,s}f(\mathbf{x}_2,\mathbf{x}_1) = \sum_\mu E_\mu\phi^*_\mu(\mathbf{x}_2,\mathbf{x}_1)\int d\mathbf{x}'_1\,d\mathbf{x}'_2\,\phi_\mu(\mathbf{x}'_2,\mathbf{x}'_1)f(\mathbf{x}'_2,\mathbf{x}'_1), \tag{29.50}$$

where the formal summation over μ implies summing over the discrete part and integrating over the continuous part of the spectrum of the operator $\hat{L}_{\sigma,s}$, and E_μ and $\phi_\mu(\mathbf{x}_2,\mathbf{x}_1)$ are, respectively, the eigenvalues and the eigenfunctions, $\hat{L}_{\sigma,s}\phi_\mu = E_\mu\phi_\mu$. The operator $\hat{L}_{\sigma,s}$ is (formally) self-adjoint and, hence, its eigenvalues are real and the eigenfunctions form a complete orthonormal set.

Using Equation 29.50 in Equation 29.48 and convoluting both sides of Equation 29.48 with ϕ^*_μ we obtain the ordinary differential equation

$$-i\hbar\frac{\partial}{\partial t}\hat{P}^\dagger_\mu(t) = E_\mu\hat{P}^\dagger_\mu(t) + \mathcal{A}_\mu(t), \tag{29.51}$$

where we have introduced

$$\hat{P}^\dagger_\mu(t) = \int d\mathbf{x}_1\,d\mathbf{x}_2\,\phi_\mu(\mathbf{x}_2,\mathbf{x}_1)\upsilon^\dagger_\sigma(\mathbf{x}_2)c^\dagger_s(\mathbf{x}_1) \tag{29.52}$$

and

$$\mathcal{A}_\mu(t) = \int d\mathbf{x}\,\phi_\mu(\mathbf{x},\mathbf{x})\mathbf{A}(\mathbf{x},t)\cdot\mathbf{d}_{\sigma,s}. \tag{29.53}$$

The solution of Equation 29.51 is written as the sum of the general solution of the homogeneous equation (with $\mathcal{A}_\mu(t) \equiv 0$) and the partial solution of inhomogeneous

$$\hat{P}^\dagger_\mu(t) = \hat{P}^\dagger_\mu(0)e^{iE_\mu t/\hbar} + \frac{i}{\hbar}\int_0^t dt'\,e^{iE_\mu(t-t')/\hbar}\mathcal{A}_\mu(t'). \tag{29.54}$$

The first term is determined by the initial value of the operators $\upsilon^\dagger_\sigma(\mathbf{x}_2)c^\dagger_s(\mathbf{x}_1)$ or, according to the definition of the Heisenberg representation (see Equation 29.33), by their bare values. If, for example, initially the semiconductor is in the vacuum state (empty conduction band and filled valence band) the average value of the first term vanishes (see Equation 29.30) and, hence, it does not contribute to the average interband polarization and, accordingly, to the macroscopic electromagnetic field, which, as follows from Equation 29.40, is driven by $\left\langle\upsilon^\dagger_\sigma(\mathbf{x})c^\dagger_s(\mathbf{x})\right\rangle$.

In order to discuss the effect of the external field, we first assume that the external field changes harmonically with time

$$\mathbf{A}(\mathbf{x},t) = \mathbf{A}(\mathbf{x},\Omega)e^{-i\Omega t} + \mathbf{A}^*(\mathbf{x},\Omega)e^{i\Omega t}, \tag{29.55}$$

which yields

$$\left\langle 0\left|\hat{P}^{(\mu)}_{\sigma,s}(t)\right|0\right\rangle = \mathcal{A}^{(\mu)}_{\sigma,s}(\Omega)\frac{e^{iE_\mu t/\hbar} - e^{-i\Omega t}}{E_\mu + \hbar\Omega} + \bar{\mathcal{A}}^{(\mu)}_{\sigma,s}(\Omega)\frac{e^{iE_\mu t/\hbar} - e^{i\Omega t}}{E_\mu - \hbar\Omega}, \tag{29.56}$$

where $\mathcal{A}^{(\mu)}_{\sigma,s}(\Omega)$ and $\bar{\mathcal{A}}^{(\mu)}_{\sigma,s}(\Omega)$ are found using in Equation 29.53 $\mathbf{A}(\mathbf{x}, \Omega)$ and $\mathbf{A}^*(\mathbf{x}, \Omega)$, respectively. If $\Omega \approx E_\mu/\hbar$, then at the time scale $(\Omega + E_\mu/\hbar)^{-1} \ll t \ll |\Omega - E_\mu/\hbar|^{-1}$ the second term in Equation 29.56 increases linearly with time reflecting the resonant semiconductor response and eventually prevails over the first term, so that one can neglect the nonresonant contribution. This constitutes the *rotating wave approximation* widely used in studying the semiconductor optical response. For estimates we note that the smallest value E_μ is determined by the width of the gap, $\Delta = \epsilon_s - \epsilon_\sigma$, minus binding energy of a possible bound state. The value of the binding energy cannot be expected to be significant compared to Δ and thus we can take $E_\mu \approx \Delta$. In GaAs $\Delta \approx 1.5\,\text{eV}$ yielding the characteristic time scale

$$\mathrm{T}_R = \hbar\pi/\Delta \approx 1\,\text{fs}. \tag{29.57}$$

Thus, if the excitation field is approximately tuned into the resonance with the semiconductor gap and the duration of the excitation pulse significantly exceeds 1 fs, one can use the resonant approximation and neglect the nonresonant contribution. The reverse, however, should also be mentioned. The experiments with pulses with duration of few femtoseconds are readily available now and one should be careful in applying the resonant approximation for the description of such experiments.

Next we consider a more general case wherein the external field changes harmonically with slowly varying amplitude, for example, when the excitation field is a pulse of finite duration much longer than T_R, so that the temporal Fourier transform is localized in a vicinity of Δ with both detuning $|\Omega - \Delta/\hbar|$ and the width of the distribution much smaller than Δ. Obviously, in this case we can again separate the resonant and nonresonant contributions. Indeed, this is true for each major harmonic and, hence, for the whole excitation pulse.

This motivates taking advantage of the resonance condition on the level of the equations of motion. This can be easily done. Let the external field be of the form

$$\mathbf{A}(\mathbf{x},t) = \mathbf{A}_\Omega(\mathbf{x},t)e^{-i\Omega t} + \text{c.c.}, \tag{29.58}$$

where $\mathbf{A}_\Omega(\mathbf{x}, t)$ is a function slowly changing with time. Following Equation 29.54, we use in Equation 29.46 the ansatz

$$\upsilon_\sigma(\mathbf{x}) \to e^{-i\Omega t/2}\upsilon_\sigma(\mathbf{x}), \quad c_s(\mathbf{x}) \to e^{-i\Omega t/2}c_s(\mathbf{x}). \tag{29.59}$$

After canceling the factor $e^{i\Omega t}$ in the equation with respect to the operator of the interband polarization there will be two type of terms explicitly depending on time in the r.h.s. of Equation 29.46. The terms of the first type oscillate much faster than any typical time scale for the operators defined in Equation 29.59 and their contribution is small on the time scale $t > T_R$. Neglecting such terms corresponds to the rotating wave approximation and defining the operators according to Equation 29.59 is called the transition to the *rotating frame*.

We do not provide the form of the semiconductor equations of motion in the rotating frame but we would like to note that the width of the gap between the conduction and the valence bands in the equation for the operator of the interband polarization is renormalized by the frequency of the external field $\epsilon_s - \epsilon_\sigma \to \epsilon_s - \epsilon_\sigma - \hbar\Omega$. These equations can be derived as the Heisenberg equations of motion from the Hamiltonian $\mathcal{H} = \mathcal{H}_{e-h} + \mathcal{H}_{exc}$, where $\mathcal{H}_{e-h}$ is the electron–hole Hamiltonian written in the rotating frame

$$\begin{aligned}\mathcal{H}_{e-h} =& \sum_s \int d\mathbf{x}\, c_s^\dagger(\mathbf{x})\left[\epsilon_s(\mathbf{x}) - \hbar\Omega/2 - \frac{\hbar^2}{2m_e}\nabla^2\right]c_s(\mathbf{x})\\ &-\sum_{\sigma,\sigma'}\int d\mathbf{x}\,\upsilon_\sigma^\dagger(\mathbf{x})\left[\delta_{\sigma,\sigma'}\epsilon_\sigma(\mathbf{x}) - \delta_{\sigma,\sigma'}\hbar\Omega/2 - \nabla\cdot\frac{\hbar^2}{2\mathrm{M}_{\sigma,\sigma'}}\cdot\nabla\right]\upsilon_{\sigma'}(\mathbf{x})\\ &+\frac{1}{2}\sum_{s,s'}\int d\mathbf{x}_1\, d\mathbf{x}_2\, c_s^\dagger(\mathbf{x}_1)c_{s'}^\dagger(\mathbf{x}_2)V(\mathbf{x}_1 - \mathbf{x}_2)c_{s'}(\mathbf{x}_2)c_s(\mathbf{x}_1)\\ &+\frac{1}{2}\sum_{\sigma,\sigma'}\int d\mathbf{x}_1 d\mathbf{x}_2 \upsilon_\sigma^\dagger(\mathbf{x}_1)\upsilon_{\sigma'}^\dagger(\mathbf{x}_2)\,V(\mathbf{x}_1 - \mathbf{x}_2)\upsilon_{\sigma'}(\mathbf{x}_2)\upsilon_\sigma(\mathbf{x}_1)\\ &-\sum_{s,\sigma}\int d\mathbf{x}_1 d\mathbf{x}_2 \upsilon_\sigma^\dagger(\mathbf{x}_1)c_s^\dagger(\mathbf{x}_2)V(\mathbf{x}_1 - \mathbf{x}_2)c_s(\mathbf{x}_2)\upsilon_\sigma(\mathbf{x}_1)\end{aligned} \tag{29.60}$$

and $\mathcal{H}_{exc}$ is the Hamiltonian of interaction with the electromagnetic field in the rotating approximation

$$\mathcal{H}_{exc} = \sum_{s,\sigma}\int d\mathbf{x}[\mathbf{A}_\Omega(\mathbf{x},t)\cdot\mathbf{d}_{s,\sigma}\upsilon_\sigma^\dagger(\mathbf{x})c_s^\dagger(\mathbf{x}) + \mathbf{A}_\Omega^\star(\mathbf{x},t)\cdot\mathbf{d}_{\sigma,s}c_s(\mathbf{x})\upsilon_\sigma(\mathbf{x})], \tag{29.61}$$

where $\mathbf{A}_\Omega(\mathrm{x}, t)$ is the amplitude slowly changing with time. It is worth noting that Hamiltonian (29.60) reflects that holes and electrons have opposite charges—the Coulomb interaction between electrons and between holes increases the energy and, hence, leads to repulsion while the Coulomb interaction between the electrons and holes decreases the energy and corresponds to attraction.

While we derived Equation 29.61, taking into account only external classical excitation field, it can be generalized to describe the interaction of the semiconductor with the quantized electromagnetic field in the rotating wave approximation. For this one should represent $\hat{\mathbf{A}}(\mathbf{x})$ in terms of the photon creation and annihilation operators and use in Equation 29.61 instead of $\mathbf{A}_\Omega(\mathbf{x}, t)$ the part containing only the annihilation operators and instead of $\mathbf{A}_\Omega^\star(\mathbf{x}, t)$ the part with the photon creation operators. This illustrates an evident but important feature of the light–semiconductor interaction. The process of absorption of a photon is accompanied with the creation of the electron–hole pair and the emission results in destruction of a pair, so that the *operator* of the difference between the total numbers of the electrons and holes is a constant of motion

$$\int d\mathbf{x}\left[\sum_s c_s^\dagger(\mathbf{x})c_s(\mathbf{x}) - \sum_s \upsilon_\sigma^\dagger(\mathbf{x})\upsilon_\sigma(\mathbf{x}), \mathcal{H}\right] = 0. \tag{29.62}$$

29.4 Perturbation Theory: Four-Wave Mixing Response

The best understood way of analyzing the semiconductor nonlinear response is the perturbation theory with respect to the external excitation field because it allows for a general model independent formulation. For example, in Ostreich et al. (1998) the powerful formalism of Hubbard operators is used, which, as has been demonstrated in Ostreich (2001), allows a relatively straightforward extension to higher orders. Here we choose a more traditional approach developed in the standard $T = 0$ quantum field theory. The derivation of the main equations, however, significantly benefits from the idea of describing the semiconductor excitations in terms of genuine eigenstates borrowed from Ostreich et al. (1998).

We limit our consideration to the case when there is no external static field, i.e., $U_{\text{ext}}(\mathbf{x}) \equiv 0$, and the spatial variations of the band edges correspond to a single quantum well grown along z direction, $\epsilon_n(\mathbf{x}) = \epsilon_n + \Delta\epsilon_n(z)$. As has been discussed above the states reached in the course of the resonance excitation of the semiconductor are characterized by the definite numbers of the electron–hole pairs. The simplest states contain one such pair and can be created by acting on vacuum with the operator

$$\hat{B}^{\dagger}_{\mu} = \sum_{\sigma_\mu, s_\mu} \int d\mathbf{x}_1 d\mathbf{x}_2 \phi_\mu(\mathbf{x}_1, \mathbf{x}_2) \upsilon^{\dagger}_{\sigma_\mu}(\mathbf{x}_1) c^{\dagger}_{s_\mu}(\mathbf{x}_2), \tag{29.63}$$

where the index μ enumerates different states of the single electron–hole pair. The function $\phi_\mu(\mathbf{x}_1, \mathbf{x}_2)$ is chosen in such a way that the state $|\mu\rangle = \hat{B}^{\dagger}_{\mu}|0\rangle$ is the eigenstate of the semiconductor Hamiltonian without the excitation field

$$\mathcal{H}_{e-h} |\mu\rangle = E_\mu |\mu\rangle. \tag{29.64}$$

Substituting Equations 29.60 and 29.63 into this equation, we find that $\phi_\mu(\mathbf{x}_1, \mathbf{x}_2)$ satisfies the differential equation, which has the familiar structure (compare with Equation 29.48)

$$\begin{aligned} E_\mu \phi_\mu(\mathbf{x}_1, \mathbf{x}_2) = \Bigg[& \epsilon_{s_\mu}(\mathbf{x}_2) - \epsilon_{\sigma_\mu}(\mathbf{x}_1) - \hbar\Omega \\ & - \frac{\hbar}{2m_c} \nabla_2^2 - \nabla_1 \cdot \frac{\hbar^2}{2M_{\sigma',\sigma_\mu}} \cdot \nabla_1 - V(\mathbf{x}_2 - \mathbf{x}_1) \Bigg] \phi_\mu(\mathbf{x}_1, \mathbf{x}_2). \end{aligned} \tag{29.65}$$

This equation has the meaning of the stationary Schrödinger equation for two particles with opposite charges (the hole at point $\mathbf{x}_1$ and the electron at the point $\mathbf{x}_2$) moving in potentials $\epsilon_{\sigma_\mu}(\mathbf{x}_1)$ and $\epsilon_{s_\mu}(\mathbf{x}_2)$. Thus, $\phi_\mu(\mathbf{x}_1, \mathbf{x}_2)$ has the physical meaning of the electron–hole wave function corresponding to the particular stationary state. For a general form of potentials $\epsilon_{\sigma_\mu}(\mathbf{x}_1)$ and $\epsilon_{s_\mu}(\mathbf{x}_2)$. Equation 29.65 cannot be solved exactly and different approximate methods are developed for investigating the specific features of the solutions. We discuss the general properties of solutions of Equation 29.65 adopting the δ-functional approximation for the quantum well. In the framework of this approximation, the support of electron–hole wave function, that is, the region where the function is not identically zero along z direction is assumed to be limited by the position of the quantum well. Additionally, we neglect the off-diagonal interband elements and the anisotropy of the tensor of the holes effective mass, so we use $\mathsf{M}_{\sigma',\sigma_\mu} = 1\delta_{\sigma',\sigma_\mu}\mathsf{M}_{\sigma_\mu}$, where 1 is the unit tensor. This corresponds to neglecting the heavy-hole–light-hole mixing, which is valid if the hole momentum in plane of the quantum well is not too high (Zhu and Huang 1987). Under these approximations Equation 29.65 turns into the well-studied (and yet nontrivial (Parfitt and Portnoi 2002)) problem of the two-dimensional hydrogen atom.

The spectrum consists of the discrete and the continuous part. The discrete part corresponds to the bound electron–hole states, which are called *excitons*. Often this term is reserved for the bound states, however, often it is convenient to treat bound and unbound states on the equal ground and, therefore, the term "exciton" is also used as the short synonym of "electron–hole pair" regardless whether they are bound or not. From the perspective of Equation 29.64 operators $B^{\dagger}_{\mu}$ with the respective kernels $\phi_\mu(\mathbf{x}_1, \mathbf{x}_2)$ acting on vacuum create the exciton and thus $B^{\dagger}_{\mu}$ have the meaning of the exciton creation operators.

Because of the translational invariance of the r.h.s. of Equation 29.65 in the plane of the quantum well, the wave function admits the presentation

$$\phi_\mu(\mathbf{x}_1, \mathbf{x}_2) = e^{i\mathbf{K}_\mu \cdot \mathbf{R}} \tilde{\phi}_\mu(\mathbf{x}_1 - \mathbf{x}_2), \tag{29.66}$$

where

$\mathbf{K}_\mu$ is the momentum

$\mathbf{R} = (M_{\sigma_\mu}\mathbf{x}_1 + m_e\mathbf{x}_2)/(M_{\sigma_\mu} + m_e)$ is the position of the center of mass of the pair

Similarly to the three-dimensional case, the eigenstates of the two-dimensional hydrogen atom are enumerated by the main quantum number n and the angular momentum ℓ. Thus, in this case, the index μ in Equation 29.63 combines all the quantum numbers characterizing the specific exciton state $\mu = \{\mathbf{K}_\mu, s_\mu, \sigma_\mu, n_\mu, \ell_\mu\}$. The important property of the eigenstates of the two-dimensional hydrogen atom is that the wave function corresponding to the states with $\ell \neq 0$ vanishes at $\mathbf{x}_1 = \mathbf{x}_2$. Thus, as follows from Equation 29.61, these states do not contribute to the coupling with the electromagnetic field. Among the states with $\ell = 0$ the most important one is the state with the lowest energy, whose wave function has the form

$$\tilde{\phi}_\mu(\mathbf{x}) = \sqrt{\frac{2}{\pi r_\mu^2}} e^{-|x|/r_\mu}, \tag{29.67}$$

where the Bohr radius of the two-dimensional exciton is given by $r_\mu = \epsilon_b / 2 m_{\sigma_\mu} e^2$ (notice that it is two times smaller than in three dimensions) with m_{σ_μ} being the electron–hole-reduced mass, $1/m_{\sigma_\mu} = 1/m_e + 1/M_{\sigma_\mu}$.

Using solutions of Equation 29.65 we can incorporate the single-pair states into the theory. The full set of solutions is complete

$$\sum_\mu \phi^\star_\mu(\mathbf{x}_1, \mathbf{x}_2)\phi_\mu(\mathbf{x}'_1, \mathbf{x}'_2) = \delta(\mathbf{x}_1 - \mathbf{x}'_1)\delta(\mathbf{x}_2 - \mathbf{x}'_2), \tag{29.68}$$

where summation over μ implies summation over the discrete quantum numbers (e.g., ℓ and n for hydrogen-like bound excitons) and integration over continuous ones (such as the center of mass momentum $\mathbf{K}_\mu$). Relation (29.68) allows us to express any electron–hole operator in terms of the exciton operators, for example

$$\upsilon^\dagger_\sigma(\mathbf{x}) c^\dagger_s(\mathbf{y}) = \sum_{\mu | s_\mu = s, \sigma_\mu = \sigma} \phi^\star_\mu(\mathbf{x}, \mathbf{y}) \hat{B}^\dagger_\mu \tag{29.69}$$

and represent in terms of the exciton operators the Hamiltonian of the interaction of the semiconductor, Equation 29.61, with the electromagnetic field

$$\mathcal{H}_{exc} = \sum_\mu [\mathcal{A}^\star_\mu(t)\hat{B}_\mu + \mathcal{A}_\mu(t)\hat{B}^\dagger_\mu], \tag{29.70}$$

where

$$\mathcal{A}_\mu(t) = \int d\mathbf{x}\, \mathbf{A}_\Omega(\mathbf{x}, t) \cdot \mathbf{d}_{s_\mu, \sigma_\mu} \phi^\star_\mu(\mathbf{x}, \mathbf{x}). \tag{29.71}$$

The similarity between Equations 29.63 and 29.71 and Equations 29.52 and 29.53 is not accidental. If we act by the first equation in Equations 29.46 on vacuum $|0\rangle$ in the case of absent external field, we obtain the nonstationary Schrödinger equation for a single-pair state, so the operator $\hat{L}_{\sigma,s}$ defined in Equation 29.49 has the meaning of the single-pair Hamiltonian. The spectral representation of $\hat{L}_{\sigma,s}$ allows projecting on the eigenstates of the single-pair Hamiltonian, which are analogous to the projections on the genuine single-particle states defined by Equations 29.63 and 29.71. This demonstrates that the procedure shown above can be generalized to go beyond the adopted approximations.

The interaction Hamiltonian $\mathcal{H}_{exc}$ is considered as a perturbation and the theory is then built following the standard lines. First we account for the nonperturbed dynamics exactly introducing

$$\left|\tilde{\Phi}(t)\right\rangle = e^{i\mathcal{H}_{e-h}t/\hbar} \left|\Phi(t)\right\rangle, \tag{29.72}$$

so that if there is no perturbation, then $|\tilde{\Phi}(t)\rangle$ does not change with time. Using the fact that the system state satisfies the equation $i\hbar\partial\left|\Phi(t)\right\rangle/\partial t = \mathcal{H}\left|\Phi\right\rangle$, we find that the time evolution is governed by

$$i\frac{\partial}{\partial t}\left|\tilde{\Phi}(t)\right\rangle = \tilde{\mathcal{H}}_{exc}(t)\left|\tilde{\Phi}(t)\right\rangle, \tag{29.73}$$

where

$$\tilde{\mathcal{H}}_{exc}(t) = e^{i\mathcal{H}_{e-h}t/\hbar}\mathcal{H}_{exc}(t)e^{-i\mathcal{H}_{e-h}t/\hbar}. \tag{29.74}$$

The solution of Equation 29.73 is written in terms of the S-matrix

$$\left|\tilde{\Phi}(t)\right\rangle = S(t)\left|\tilde{\Phi}(0)\right\rangle, \tag{29.75}$$

where

$$S(t) = 1 + \sum_{n=1}^{\infty}\left(-\frac{i}{\hbar}\right)^n \int_{0 \le t_1 \le \ldots} \ldots \int_{\le t_n \le t} dt_1 \ldots dt_n \tilde{\mathcal{H}}_{exc}(t_1)\ldots\tilde{\mathcal{H}}_{exc}(t_n). \tag{29.76}$$

Often this expansion is presented in the compact form $S(t) = \mathcal{T}_+ \exp\left\{-i\hbar^{-1}\int_0^t dt'\tilde{\mathcal{H}}_{exc}(t')\right\}$ similarly to Equation 29.31; we, however, will need in what follows the explicit form of expansion (29.76).

Next, we express the observables

$$O(t) = \left\langle\hat{O}\right\rangle = \left\langle\Phi(t)\right|\hat{O}\left|\Phi(t)\right\rangle = \left\langle\tilde{\Phi}(t)\right| e^{i\mathcal{H}_{e-h}t/\hbar}\hat{O}\, e^{-i\mathcal{H}_{e-h}t/\hbar}\left|\tilde{\Phi}(t)\right\rangle \tag{29.77}$$

and notice that in this equation and in Equation 29.74 appears the same structure

$$\tilde{O}(t) = e^{i\mathcal{H}_{e-h}t/\hbar}\hat{O}e^{-i\mathcal{H}_{e-h}t/\hbar}, \tag{29.78}$$

which is called the *interaction representation* of the operator $\hat{O}$. Taking into account Equation 29.75 we obtain

$$O(t) = \left\langle S^\dagger(t)\tilde{O}(t)S(t)\right\rangle_0, \tag{29.79}$$

where $\langle\ldots\rangle_0 \equiv \langle\Phi(0)|\ldots|\Phi(0)\rangle$. Finally, the perturbation series is obtained substituting expansion (29.76) into Equation 29.79. The order of the perturbation is determined by the highest order of $\tilde{\mathcal{H}}(t)$ kept in the resulting expression.

We illustrate the perturbation theory in action finding the macroscopic exciton polarization, $P_\mu = \left\langle\hat{B}_\mu\right\rangle$ or

$$P_\mu = \left\langle S^\dagger(t)\tilde{B}_\mu(t)S(t)\right\rangle_0. \tag{29.80}$$

Let the initial state of the system be vacuum $|\Phi(0)\rangle = |0\rangle$. Below we will consider only such initial state, therefore, in order to shorten notations we will omit the index 0 and write averages over vacuum simply $\langle\ldots\rangle$. Since the semiconductor Hamiltonian $\mathcal{H}_{e-h}$ preserves both the number of electrons in the conduction band and the number of holes in the valence band, the exciton operator in the interaction representation acts in a similar way as in the Schrödinger or Heisenberg representations, namely, $\tilde{B}^\dagger_\mu(t)$ creates and $\tilde{B}_\mu(t)$ destroys an electron–hole pair, respectively. Hence, the terms in the expansion of the r.h.s. of Equation 29.80, which give nonzero contribution, must have balanced numbers of the exciton creation and annihilation operators. In particular, one can easily check that there are no contributions of even orders (zeroth, second, and so on).

There is only one term in the first order

$$\begin{aligned} P^{(1)}_\mu(t) &= -\frac{i}{\hbar}\sum_\nu\int_0^t dt_1\left\langle\tilde{B}_\mu(t)\tilde{B}^\dagger_\nu(t_1)\right\rangle\mathcal{A}_\nu(t_1) \\ &= -\frac{i}{\hbar}\int_0^t dt_1 e^{-iE_\mu(t-t_1)/\hbar}\mathcal{A}_\mu(t_1), \end{aligned} \tag{29.81}$$

where in the second equality we have taken into account Equation 29.64 and the fact that $\hat{B}_\mu\hat{B}^\dagger_\nu|0\rangle = \delta_{\mu,\nu}|0\rangle$, which follows from the commutation relation for the exciton operators

$$[\hat{B}_\mu\hat{B}^\dagger_\nu] = \hbar(\delta_{\mu,\nu} - \hat{C}_{\mu,\nu}), \tag{29.82}$$

where

$$\begin{aligned} \hat{C}_{\mu,\nu} = \int d\mathbf{x}'\,d\mathbf{y}'\,d\mathbf{x}\,d\mathbf{y}\,\phi_\nu(\mathbf{x}',\mathbf{y}')\phi^*_\mu(\mathbf{x},\mathbf{y})[\upsilon^\dagger_{\sigma_\nu}(\mathbf{x}')\upsilon_{\sigma_\mu}(\mathbf{x})\delta(\mathbf{y}-\mathbf{y}')\delta_{s_\nu,s_\mu} \\ + c^\dagger_{s_\nu}(\mathbf{y}')c_{s_\mu}(\mathbf{y})\delta(\mathbf{x}-\mathbf{x}')\delta_{\sigma_\nu,\sigma_\mu}]. \end{aligned} \tag{29.83}$$

These operators describe the deviation of excitons from bosons. It should be noted, however, that the deviation depends on the number of the electrons and holes. Thus, in the limit of weak excitations, the excitons can be approximately considered as bosons. However, as the population of the valence and conduction bands increases, one has to take into account the full form of the commutation relation.

Differentiating Equation 29.81 with respect to time we find

$$i\hbar\frac{\partial}{\partial t}P^{(1)}_\mu(t) = E_\mu P^{(1)}_\mu(t) + \mathcal{A}_\mu(t). \tag{29.84}$$

Comparing this with Equation 29.51 we can see that Equation 29.84 is nothing else but the exciton polarization of the linear response. This shows that the perturbation theory built with the help of the interaction representation correctly accounts for the nonperturbed dynamics of the semiconductor. With this regard it should be noted that this presents a convenient opportunity to account for the incoherent processes, which take place in real systems. As has been noted before a rigorous introduction of the decoherence requires developing a complex technique. For many purposes, however, it suffices to introduce the imaginary part of the single-exciton energies, $E_\mu \to E_\mu - i\hbar\Gamma_\mu$.

Before we move further, we would like to discuss some basic features of the amplitudes $\mathcal{A}_\mu(t)$. Substituting Equation 29.66 within Equation 29.71, we obtain

$$\mathcal{A}_\mu(t) = \tilde{\phi}^*_\mu(0)\int d\mathbf{x}\,e^{-i\mathbf{K}_\mu\cdot\mathbf{x}}\mathbf{A}_\Omega(\mathbf{x},t)\cdot\mathbf{d}_{s_\mu,\sigma_\mu}, \tag{29.85}$$

where the integration is taken over the plane of the quantum well. Thus, if the excitation field has the form of a plain wave $\mathbf{A}_\Omega(\mathbf{x}) \propto \exp(i\mathbf{K}\cdot\mathbf{x})$, then $\mathcal{A}_\mu \propto \delta(\mathbf{K}_\parallel - \mathbf{K}_\mu)$, that is, the plane wave only excites the exciton states with the same center of mass momentum as the projection of $\mathbf{K}$ on the plane of the quantum well, $\mathbf{K}_\parallel$. Moreover, as follows from Equation 29.40 the same in-plane momentum will be passed to the outgoing electromagnetic field. Such conservation of the in-plane momentum is not a specific feature of the linear response. If the excitation field is a plane wave, the translations $\Delta\mathbf{x}$ in the plane of the quantum well lead to the amplitudes $\mathbf{A}_\Omega(\mathbf{x})$ acquiring a phase factor, $\mathbf{A}_\Omega(\mathbf{x} + \Delta\mathbf{x}) = \exp(i\mathbf{K}_\parallel\cdot\Delta\mathbf{x})\mathbf{A}_\Omega(\mathbf{x})$; in other words, the excitation field possesses the translational symmetry. If this is the case, then, as can be easily checked, the full system of the equations of motion, Equations 29.46, is also translationally invariant (more precisely it has the same translational symmetry as the external field) with the following transformation rules for the solutions

$$\begin{aligned} \upsilon^\dagger_\sigma(\mathbf{x}_2 + \Delta\mathbf{x})c^\dagger_s(\mathbf{x}_1 + \Delta\mathbf{x}) &= \upsilon^\dagger_\sigma(\mathbf{x}_2)c^\dagger_s(\mathbf{x}_1)e^{i\mathbf{k}_\parallel\cdot\Delta\mathbf{x}}, \\ c^\dagger_{s_1}(\mathbf{x}_1 + \Delta\mathbf{x})c_{s_2}(\mathbf{x}_2 + \Delta\mathbf{x}) &= c^\dagger_{s_1}(\mathbf{x}_1)c_{s_2}(\mathbf{x}_2), \\ \upsilon^\dagger_{\sigma_2}(\mathbf{x}_2 + \Delta\mathbf{x})\upsilon_{\sigma_1}(\mathbf{x}_1 + \Delta\mathbf{x}) &= \upsilon^\dagger_{\sigma_2}(\mathbf{x}_2)\upsilon_{\sigma_1}(\mathbf{x}_1). \end{aligned} \tag{29.86}$$

This also results in the transfer of the incoming in-plane momentum to the outgoing wave.

The picture becomes more complex if the external field is a superposition of two-plane waves $\mathbf{A}_\Omega(\mathbf{x}) = \mathbf{A}_1\exp(i\mathbf{K}^{(1)}\cdot\mathbf{x})$ + $\mathbf{A}_2\exp(i\mathbf{K}^{(2)}\cdot\mathbf{x})$ with noncollinear in-plane components of the momenta, $\mathbf{K}^{(1)}_\parallel \neq a\mathbf{K}^{(2)}_\parallel$ for any number a. In this case, the external field is invariant with respect to infinitesimal translations in the direction perpendicular to $\Delta\mathbf{K} = \mathbf{K}^{(2)}_\parallel - a\mathbf{K}^{(1)}_\parallel$, while in the direction along $\Delta\mathbf{K}$ it is invariant only with respect to *finite* shifts $\Delta R = 2\pi/\Delta K$. For the polarization of linear response it brings nothing new, as one could expect only the exciton polarizations with the center of mass momenta $\mathbf{K}^{(1)}_\parallel$ and $\mathbf{K}^{(2)}_\parallel$ are produced. However, this is not necessarily the case for the nonlinear system of equations. Generally, it is invariant only with respect to finite translations. As we know from the basic theory of crystals whenever one has such symmetry, the momentum conserves only up to the vectors of the reciprocal lattice, which in our case are $m\Delta\mathbf{K}$ with integer m. Thus, in addition to the initial momenta presented in the excitation field, one might expect to see additional momenta appearing in the nonlinear response. This is, indeed, the case and the exciton polarizations corresponding to the "new" momenta are called the polarizations of *multiwave mixing* response for reasons which will become evident later.

In order to see the multiwave mixing response one needs to consider next orders of the perturbation theory. In the third order we have four terms, which we show schematically as

$$P_\mu^{(3)} \sim \left\langle B_\mu B B^\dagger B^\dagger \right\rangle + \left\langle B_\mu B^\dagger B B^\dagger \right\rangle + \left\langle B B^\dagger B_\mu B^\dagger \right\rangle + \left\langle B B_\mu B^\dagger B^\dagger \right\rangle \tag{29.87}$$

The operators that appear to the right from B_μ originate from the expansion of $S(t)$ in Equation 29.80, and those to the left from B_μ come from $S^\dagger(t)$. After some algebra we obtain

$$\begin{aligned}\hbar\frac{\partial}{\partial t}P_\mu^{(3)}(t) &= -(iE_\mu + \hbar\Gamma_\mu)P_\mu^{(3)}(t)\\ &\quad + i\hbar\sum_{\nu_1\nu_2\nu_3}\left\langle \hat{B}_{\nu_2}\hat{C}_{\mu,\nu_3}\hat{B}_{\nu_1}^\dagger\right\rangle \mathcal{A}_{\nu_3}(t)P_{\nu_2}^{(1)\star}(t)P_{\nu_1}^{(1)}(t)\\ &\quad + \sum_{\nu_1,\nu_2,\nu_3} P_{\nu_2}^{(1)^*}(t)\int_0^t dt'\left\langle \hat{D}_{\nu_2,\mu}e^{-i\mathcal{H}_{e-h}(t-t')/\hbar}\hat{B}_{\nu_3}^\dagger\hat{B}_{\nu_1}^\dagger\right\rangle \mathcal{A}_{\nu_3}(t')P_{\nu_1}^{(1)}(t'),\end{aligned} \tag{29.88}$$

where we have introduced the operator

$$\hat{D}_{\nu,\mu} = \left[\hat{B}_\nu,\left[\hat{B}_\mu,\mathcal{H}_{e-h}\right]\right], \tag{29.89}$$

which appears in calculations as $\langle 0|\hat{B}_\nu^\dagger\hat{B}_\mu^\dagger(\mathcal{H}_{e-h} - E_\nu - E_\mu) = \langle 0|\hat{D}_{\nu,\mu}$. In terms of the electron and hole operators $\hat{D}_{\nu,\mu}$ is written as

$$\begin{aligned}\hat{D}_{\nu,\mu} &= \int d\mathbf{x}_1 d\mathbf{y}_1 d\mathbf{x}_2 d\mathbf{y}_2 \phi_\mu^\star(\mathbf{x}_1,\mathbf{y}_1)\phi_\nu^\star(\mathbf{x}_2,\mathbf{y}_2)V(\mathbf{x}_1,\mathbf{y}_1 : \mathbf{x}_2,\mathbf{y}_2)\\ &\quad \times c_{s_\mu}(\mathbf{y}_1)\upsilon_{\sigma_\mu}(\mathbf{x}_1)c_{s_\nu}(\mathbf{y}_2)\upsilon_{\sigma\nu}(\mathbf{x}_2),\end{aligned} \tag{29.90}$$

where $V(\mathbf{x}_1, \mathbf{y}_2; \mathbf{x}_2, \mathbf{y}_2) = V(\mathbf{x}_1 - \mathbf{x}_2) + V(\mathbf{y}_1 - \mathbf{y}_2) - V(\mathbf{x}_1 - \mathbf{y}_2) - V(\mathbf{x}_2 - \mathbf{y}_1)$ is the energy of the Coulomb interaction between two excitons.

We rewrite the last term in Equation 29.88 in order to express it solely in terms of the polarizations of the linear response. For this we notice that for a symmetric matrix $G_{\kappa,\lambda} = G_{\lambda,\kappa}$ one has

$$\begin{aligned}&\frac{i\hbar}{2}\sum_{\kappa,\lambda} G_{\kappa,\lambda}e^{-i(E_\kappa+E_\lambda)t/\hbar}\frac{\partial}{\partial t}\left[P_\kappa^{(1)}(t)P_\lambda^{(1)}(t)e^{i(E_\kappa+E_\lambda)t/\hbar}\right]\\ &\quad = \sum_{\kappa,\lambda} G_{\kappa,\lambda}P_\kappa^{(1)}(t)\mathcal{A}_\lambda(t).\end{aligned} \tag{29.91}$$

Using this relation for the terms under the time integral in Equation 29.88 (the symmetry is ensured by $[\hat{B}_\mu^\dagger, \hat{B}_\nu^\dagger] = 0$) and integrating by part we obtain

$$\begin{aligned}\frac{\partial}{\partial t}P_\mu^{(3)}(t) &= -\left(i\frac{E_\mu}{\hbar} + \Gamma_\mu\right)P_\mu^{(3)}(t) + i\sum_{\kappa,\lambda,\nu} C_{\lambda,\mu}^{\nu,\kappa}\mathcal{A}_\nu(t)P_\lambda^{(1)\star}(t)P_\kappa^{(1)}(t)\\ &\quad + \frac{1}{2}\sum_{\kappa,\lambda,\nu} P_\lambda^{(1)^*}(t)\left[i\beta_{\lambda,\mu}^{\nu,\kappa}P_\kappa^{(1)}(t)P_\nu^{(1)}(t)\right.\\ &\quad \left. + \frac{1}{\hbar}\int_0^t dt'\, e^{-(\Gamma_\kappa+\Gamma_\nu)(t-t')}F_{\lambda,\mu}^{\nu,\kappa}(t-t')P_\kappa^{(1)}(t')P_\nu^{(1)}(t')\right],\end{aligned} \tag{29.92}$$

where we have introduced the incoherent decay into the integral term assuming that the decay of the pair of excitons is not affected by the interaction between them. We also have introduced $C_{\lambda,\mu}^{\nu,\kappa} = \left\langle \hat{B}_\lambda\hat{C}_{\mu,\nu}\hat{B}_\kappa^\dagger\right\rangle$, $\beta_{\lambda,\mu}^{\nu,\kappa} = \left\langle \hat{D}_{\lambda,\mu}\hat{B}_\nu^\dagger\hat{B}_\kappa^\dagger\right\rangle$, and $F_{\lambda,\mu}^{\nu,\kappa}(\tau) = \left\langle \hat{D}_{\lambda,\mu}e^{-i\mathcal{H}_{e-h}\tau/\hbar}\hat{D}_{\nu,\kappa}^\dagger\right\rangle$.

The term $\propto C_{\lambda,\mu}^{\nu,\kappa}$ in Equation 29.92 accounts for the effect of Pauli blocking of electrons. The parameters $\beta_{\lambda,\mu}^{\nu,\kappa}$ and the memory function $F_{\lambda,\mu}^{\nu,\kappa}(\tau)$ describe the effect of the exciton–exciton correlations. It should be emphasized that since we have taken into account exactly the dynamics of the semiconductor nonperturbed by the external field these parameters exactly account for the Coulomb interaction between the excitons. More complex many-body states, for example, triples of excitons will contribute only to the higher orders of the perturbation theory.

The important feature of $C_{\lambda,\mu}^{\nu,\kappa}$, $\beta_{\lambda,\mu}^{\nu,\kappa}$, and $F_{\lambda,\mu}^{\nu,\kappa}$ is that all of them are proportional to $\delta(\mathbf{K}_\mu + \mathbf{K}_\lambda - \mathbf{K}_\nu - \mathbf{K}_\kappa)$. The proof consists of two steps. First, we notice that after we expand the definitions of the operators entering the respective mean values, we will have at hand the vacuum averages of a set of the electrons and holes creation and annihilation operators taken at different coordinates multiplied by some scalar functions. The vacuum averages, however, do not change if we uniformly shift in the plane of the quantum well all the coordinates of the creation and annihilation operators. Indeed, when we transform the operator under-averaging to the normal form, that is, with all creation operators collected on the left side we perform transpositions of neighboring operators, which are functions of, say, $\mathbf{x}_1$ and $\mathbf{x}_2$, taking into account their anticommutation relations. This results at most in the appearance of $\delta(\mathbf{x}_1 - \mathbf{x}_2)$; thus, the vacuum average can depend only on the differences between different coordinates and, therefore, it does not change after the uniform translation.

Next, we notice that the scalar functions, which are obtained after the expansion of all definitions, acquire the phase factor only due to the translational properties of the exciton wave functions (see Equation 29.66), all other functions including $\tilde{\Phi}$ and the Coulomb potential in the Hamiltonian $\mathcal{H}_{e-h}$ are translationally invariant, so eventually we end up with an integral of the form

$$\boldsymbol{I}(\mathbf{K}_1,\ldots,\mathbf{K}_n)=\int d\mathbf{x}_1\ldots d\mathbf{x}_n \exp\left(i\sum_{j=1}^{n}\mathbf{K}_j\cdot\mathbf{x}_j\right)f(\mathbf{x}_1,\ldots,\mathbf{x}_n), \tag{29.93}$$

where $f(\mathbf{x}_1+\Delta\mathbf{x},\ldots,\mathbf{x}_n+\Delta\mathbf{x})=f(\mathbf{x}_1,\ldots,\mathbf{x}_n)$. We want to show that $\boldsymbol{I}(\mathbf{K}_1,\ldots,\mathbf{K}_n)\propto\delta(\mathbf{K}_1+\cdots+\mathbf{K}_n)$. To this end we present the integral in Equation 29.93 as

$$\boldsymbol{I}(\mathbf{K}_1,\ldots,\mathbf{K}_n)=\int d\mathbf{x}_1 e^{i\mathbf{K}_1\cdot\mathbf{x}_1}\int d\mathbf{x}_2\ldots d\mathbf{x}_n \exp\left(i\sum_{j=2}^{n}\mathbf{K}_j\cdot\mathbf{x}_j\right) \times f(0+\mathbf{x}_1,\mathbf{x}_2-\mathbf{x}_1+\mathbf{x}_1\ldots,\mathbf{x}_n-\mathbf{x}_1+\mathbf{x}_1), \tag{29.94}$$

using the translational invariance of the function $f(\mathbf{x}_1,\ldots,\mathbf{x}_n)$ and change the variables of integration in the multiple integral. This yields

$$\boldsymbol{I}(\mathbf{K}_1,\ldots,\mathbf{K}_n)=\int d\mathbf{x}_1 \exp\left(i\sum_{j=1}^{n}\mathbf{K}_j\cdot\mathbf{x}_1\right)\int d\mathbf{x}_2\ldots d\mathbf{x}_n \exp\left(i\sum_{j=2}^{n}\mathbf{K}_j\cdot\mathbf{x}_j\right) \times f(0,\mathbf{x}_2\ldots,\mathbf{x}_n). \tag{29.95}$$

The multiple integral does not depend on $\mathbf{x}_1$, so we can perform integration over $\mathbf{x}_1$ obtaining $\boldsymbol{I}(\mathbf{K}_1,\ldots,\mathbf{K}_n)\propto\delta(\mathbf{K}_1+\cdots+\mathbf{K}_n)$.

Thus, we prove that $P_\mu^{(3)}\propto\delta(\mathbf{K}_\mu+\mathbf{K}_\lambda-\mathbf{K}_\nu-\mathbf{K}_\kappa)$. Because four momenta have to add up to zero in order to have nonvanishing $P_\mu^{(3)}$, this type of response is called *four-wave mixing* response (see Figure 29.2). The possible values that $\mathbf{K}_\mu$ can take are obtained looking at different combinations of the momenta of the polarizations of the linear response, which are determined by the momenta of the incoming excitation, $\mathbf{K}_\parallel^{(1)}$ and $\mathbf{K}_\parallel^{(2)}$. We can see that in addition to $\mathbf{K}_\parallel^{(1)}$ and $\mathbf{K}_\parallel^{(2)}$ we also have $2\mathbf{K}_\parallel^{(2)}-\mathbf{K}_\parallel^{(1)}=\mathbf{K}_\parallel^{(2)}+\Delta\mathbf{K}$ and $\mathbf{K}_\parallel^{(1)}-\Delta\mathbf{K}$ in agreement with expected conservation of the momentum only up to multiples of $\Delta\mathbf{K}$.

It is important that the response in the four-wave mixing direction is created only owing to the many-body correlations in the semiconductor. As a result, the signal in the respective directions is not blurred by the nonabsorbed excitation field and the linear response. Therefore, four-wave mixing spectroscopy is a popular tool for experimentally studying the many-body properties of solids. Higher order of the perturbation theory will produce higher orders of wave mixing originating from the respective correlations, which recently started attracting significant attention.

We conclude the survey of the basics of the perturbation approach for developing a qualitative theory of the two-dimensional Fourier spectroscopy (Khalil et al. 2003, Jonas 2003), which recently became a powerful tool for studying the dynamics of the semiconductor excitations (Zhang et al. 2005, Li et al. 2006). The general scheme is the same as that of the standard four-wave mixing experiments with three pulses propagating along $\mathbf{K}^{(1)}$, $\mathbf{K}^{(2)}$, and $\mathbf{K}^{(3)}$ launched at $t=t_1$, t_2, and t_3, respectively. The difference from the standard technique is that measurements of the four-wave mixing signal are performed not at a fixed or at just a few values of the delay time $\tau=\min(t_2,t_3)-t_1$, but rather for a dense series of values lying in some interval. Subsequently, the Fourier transforms are done with respect to the delay time as well as with respect to the signal time. These two Fourier transforms constitute the two-dimensional Fourier spectrum.


$2\mathbf{K}^{(2)}-\mathbf{K}^{(1)}$
$\mathbf{K}^{(1)}$
Four-wave
$\mathbf{K}^{(2)}$
$2\mathbf{K}^{(1)}-\mathbf{K}^{(2)}$

FIGURE 29.2 Linear and four-wave mixing responses. Bold solid arrows show the momenta of the external excitation field. Dashed lines show the linear. Notice that the horizontal component of momentum does not conserve and the outgoing wave exists in both half-spaces. The solid arrows show the outgoing waves produced by the exciton polarization of the four-wave mixing response.

Equation 29.92 can be directly applied for finding the exciton polarization produced by the excitation pulses, one only needs to take into account that the pulses with different directions of the wave vectors strike the quantum well at different times (Erementchouk et al. 2007). As the simplest approximation we neglect the contribution of the memory function $F(\tau)$ and assume that its effect can be accounted for by a renormalization of $\beta_{\lambda,\mu}^{\nu,\kappa}$. Let Ω and ω correspond to the Fourier transform with respect to the signal and delay times, respectively. As one would expect the two-dimensional spectrum $P_\mu^{(3)}(\Omega,\omega)$ has resonances at the frequencies corresponding to the light-hole and the heavy-hole excitons (see Figure 29.3). It turns out, however, that the form of the resonances depends on whether they are created due to the Pauli blocking $\propto C_{\lambda,\mu}^{\nu,\kappa}$ or due to the Coulomb interaction $\beta_{\lambda,\mu}^{\nu,\kappa}$. We denote the respective contributions to the spectrum by $P_p(\Omega,\omega)$ and $P_C(\Omega,\omega)$ respectively. One can show that near particular resonance

$$\begin{aligned}P_p(\Omega,\omega)&\propto\frac{1}{(\Omega-\hbar^{-1}E_\kappa+i\Gamma_\kappa)(\omega+\hbar^{-1}E_\lambda+i\Gamma_\lambda)},\\ P_C(\Omega,\omega)&\propto\frac{1}{(\Omega-\hbar^{-1}E_\kappa+i\Gamma_\kappa)(\Omega-\hbar^{-1}E_\kappa+i\Gamma_\kappa+2i\Gamma_\lambda)(\omega+\hbar^{-1}E_\lambda+i\Gamma_\lambda)},\end{aligned} \tag{29.96}$$

where κ and λ stand for 1*s* state of either heavy- or light-hole excitons.

The contribution to the spectrum from the Pauli blocking has the Lorentz form along both the vertical and horizontal axes. The reason is that, as can be readily seen from Equation 29.92, the dependence on both the signal time $[P_\mu^{(3)}(t)]$ and delay



FIGURE 29.3 **(See color insert following page 20-14.)** The imaginary part of the two-dimensional Fourier spectrum, $P(\Omega, \omega)$. (a) The spectrum calculated using Equation 29.92. (b) The experimental results of Zhang et al. (2005).

time (through $P_\lambda^{(1)^*}(t)$ in the r.h.s. of Equation 29.92) is essentially the free evolution of the polarization directly created by the short excitation pulse. This evolution has the form of oscillations, which produce a simple pole after the Fourier transform. At the same time the resonances created by the Coulomb interaction, $P_C(\Omega, \omega)$, fall off asymptotically as $\propto 1/\omega$ and $\propto 1/\Omega^2$, along the ω- and Ω-axes, respectively. This is a consequence of the fact that the polarization of the four-mixing response $P_\mu^{(3)}(t)$ is continuously excited by the polarizations of the linear response. The dependence on the signal time is found as a convolution of the respective Green function with the source, similarly to how it was done in Equation 29.54. After the Fourier transform with respect to signal time it yields the product of Fourier images of the Green function and the source. This results in the asymptotic form $\propto 1/\Omega^2$ because of the harmonic time dependence of these functions.

This simple consideration shows that the two-dimensional Fourier spectroscopy allows one to distinguish between different types of the many-body correlations, which is almost impossible to do with the standard approach. For example, in experiments reported in Li et al. (2006), the form of the two-dimensional spectra is clearly asymmetric along different axes (see Figure 29.3b) indicating that due to relatively low intensity of excitations the contribution of the Pauli blocking into the nonlinear response was small compared to the effect of the Coulomb interaction.

29.5 Nonperturbative Methods: Rabi Oscillations

The drawback of the perturbative treatment of interaction of the electromagnetic field with the semiconductor is overestimating the resonant response. As follows from Equation 29.81 if the excitation field is tuned exactly to the resonance with an exciton state, the amplitude of the respective exciton polarization will indefinitely increase linearly with time. This, however, is impossible since with increase of the population of the conduction and the valence bands it becomes more difficult to add additional particles due to the Pauli blocking. Therefore, one would expect that the rate of change of the exciton polarization should change with time.

It turns out, however, that the effect of the environment is even stronger. The rate not only decreases, it reaches zero and then changes its sign, so the polarization starts to decrease until it completely vanishes. As a result the actual time dependence of the polarization has the form of oscillations, which are called *Rabi oscillations* by analogy with the effect of rotation of the magnetic moment in an external oscillating magnetic field.

In order to describe this effect we need to take into account the interaction with the electromagnetic field nonperturbatively. The problem of developing such nonperturbative description is that on the one hand there is no general way to study nonlinear operator equations other than using perturbation theory, while on the other hand there is no general way to map such equations onto the respective problem for regular functions. For example, averaging the first equation from Equations. 29.46 over vacuum (see e.g., Equation 29.30) one gets the dynamical equation for the interband polarization $p^{\star}_{\sigma,s}(\mathbf{x}_1,\mathbf{x}_2)=\left\langle \upsilon_\sigma^\dagger(\mathbf{x}_1)c_s^\dagger(\mathbf{x}_2)\right\rangle$, which contains in the r.h.s. the correlation functions of higher order, for example, $\langle \upsilon^\dagger c^\dagger c^\dagger c\rangle$, that is, the system will not be closed. An attempt to close the system by writing down the dynamical equation for new quantities will bring to attention correlation functions of even higher order and so on to infinity. Thus, one has to make the special approximation to truncate this hierarchy of the dynamical equations.

The simplest approximation of such kind is the Hartree–Fock approximation. It forces the closure at the level of the equation with respect to the interband polarization by applying the special decoupling scheme, which is illustrated by

$$\left\langle \upsilon_\sigma^\dagger(\mathbf{x}_1)c_{s_1}^\dagger(\mathbf{x}_2)c_{s_2}^\dagger(\mathbf{x}_3)c_{s_3}(\mathbf{x}_4)\right\rangle \approx \left\langle \upsilon_\sigma^\dagger(\mathbf{x}_1)c_{s_1}^\dagger(\mathbf{x}_2)\right\rangle\left\langle c_{s_2}^\dagger(\mathbf{x}_3)c_{s_3}(\mathbf{x}_4)\right\rangle - \left\langle \upsilon_\sigma^\dagger(\mathbf{x}_1)c_{s_2}^\dagger(\mathbf{x}_3)\right\rangle\left\langle c_{s_1}^\dagger(\mathbf{x}_2)c_{s_3}(\mathbf{x}_4)\right\rangle \quad (29.97)$$

Thus, we can express the four-point correlation functions in terms of the products of the two-point ones.

In the framework of the Hartree–Fock approximation we obtain from Equations 29.46 in the rotating wave approximation (here and below the summation over dashed spin indices is implied)

$$\begin{aligned}
-i\hbar\frac{\partial}{\partial t}p^{\star}_{\sigma,s}(\mathbf{x}_1,\mathbf{x}_2) &= \hat{K}_{\sigma,s}[p]+\mathcal{A}^{\star}_{\sigma,s}(\mathbf{x}_1)\delta(\mathbf{x}_1-\mathbf{x}_2)\\
&\quad-\int d\mathbf{x}'[\tilde{\mathcal{A}}^{\star}_{\sigma',s}(\mathbf{x}',\mathbf{x}_2)h_{\sigma,\sigma'}(\mathbf{x}_1,\mathbf{x}')\\
&\quad-\tilde{\mathcal{A}}^{\star}_{\sigma,s'}(\mathbf{x}',\mathbf{x}_1)e_{s,s'}(\mathbf{x}_2,\mathbf{x}')],\\
-i\hbar\frac{\partial}{\partial t}e_{s_1,s_2}(\mathbf{x}_1,\mathbf{x}_2) &= \hat{K}_{s_1,s_2}[e]\\
&\quad+\int d\mathbf{x}'[\tilde{\mathcal{A}}^{\star}_{\sigma',s_1}(\mathbf{x}',\mathbf{x}_1)p_{\sigma',s_2}(\mathbf{x}',\mathbf{x}_2)\\
&\quad-\tilde{\mathcal{A}}^{\star}_{\sigma',s_2}(\mathbf{x}',\mathbf{x}_2)p^{\star}_{\sigma',s_1}(\mathbf{x}',\mathbf{x}_1)],\\
-i\hbar\frac{\partial}{\partial t}h_{\sigma_1,\sigma_2}(\mathbf{x}_1,\mathbf{x}_2) &= \hat{K}_{\sigma_1,\sigma_2}[h]\\
&\quad+\int d\mathbf{x}'[\tilde{\mathcal{A}}^{\star}_{\sigma_1,s'}(\mathbf{x}_1,\mathbf{x}')p_{\sigma_2,s'}(\mathbf{x}_2,\mathbf{x}')\\
&\quad-\tilde{\mathcal{A}}^{\star}_{\sigma_2,s'}(\mathbf{x}_2,\mathbf{x}')p^{\star}_{\sigma_1,s'}(\mathbf{x}_1,\mathbf{x}')],
\end{aligned}\tag{29.98}$$

where $\mathcal{A}_{\sigma,s}(\mathbf{x})=\mathbf{A}_{\Omega}(\mathbf{x},t)\cdot d_{\sigma,s}$, the electron and hole correlation functions are $e_{s_1,s_2}(\mathbf{x}_1,\mathbf{x}_2)=\langle c^{\dagger}_{s_1}(\mathbf{x}_1)c_{s_2}(\mathbf{x}_2)\rangle$ and $h_{\sigma_1,\sigma_2}(\mathbf{x}_1,\mathbf{x}_2)=\left\langle \upsilon^{\dagger}_{\sigma_1}(\mathbf{x}_1)\upsilon_{\sigma_2}(\mathbf{x}_2)\right\rangle$, and we have introduced the modified coupling between the interband polarization and the charge densities

$$\tilde{\mathcal{A}}_{\sigma,s}(\mathbf{x},\mathbf{y})=\mathcal{A}_{\sigma,s}(\mathbf{x})\delta(\mathbf{x}-\mathbf{y})-V(\mathbf{x}-\mathbf{y})p_{\sigma,s}(\mathbf{x},\mathbf{y}).\tag{29.99}$$

The operators

$$\begin{aligned}
\hat{K}_{\sigma,s}[p^{\star}] &= \hat{H}_{\sigma,\sigma'}p^{\star}_{\sigma',s}+p^{\star}_{\sigma,s'}\hat{H}_{s',s}-V(\mathbf{x}_1-\mathbf{x}_2)p^{\star}_{\sigma,s}(\mathbf{x}_1,\mathbf{x}_2)\\
&\quad-\hbar\Omega p^{\star}_{\sigma,s}(\mathbf{x}_1,\mathbf{x}_2),\\
\hat{K}_{s_1,s_2}[e] &= \hat{H}_{s_1,s'}e_{s',s_2}-e_{s_1,s'}\hat{H}_{s',s_2},\\
\hat{K}_{\sigma_1,\sigma_2}[h] &= \hat{H}_{\sigma_1,\sigma'}h_{\sigma',\sigma_2}-h_{\sigma_1,\sigma'}\hat{H}_{\sigma',\sigma_2}
\end{aligned}\tag{29.100}$$

are expressed in terms of the integro-differential operators $\hat{H}$. The action of these operators is defined by

$$\begin{aligned}
\hat{H}_{s_1,s'}f_{\sigma'} &= \left[-\frac{\hbar^2}{2m_e}\nabla_1^2+\epsilon_{s_1}(\mathbf{x}_1)+U_{\Delta}(\mathbf{x}_1)\right]f_{s_1}(\mathbf{x}_1,\mathbf{x}_2)\\
&\quad-\int d\mathbf{x}'V(\mathbf{x}_1-\mathbf{x}')e_{s_1,s'}(\mathbf{x}_1,\mathbf{x}')f_{s'}(\mathbf{x}',\mathbf{x}_2),\\
\hat{H}_{\sigma_1,\sigma'}f_{\sigma'} &= -\nabla_1\cdot\frac{\hbar^2}{2M_{\sigma_1,\sigma'}}\cdot\nabla_1 f_{\sigma'}(\mathbf{x}_1,\mathbf{x}_2)-\left[\epsilon_{\sigma_1}(\mathbf{x}_1)+U_{\Delta}(\mathbf{x}_1)\right]f_{\sigma_1}(\mathbf{x}_1,\mathbf{x}_2)\\
&\quad-\int d\mathbf{x}'V(\mathbf{x}_1-\mathbf{x}')h_{\sigma_1,\sigma'}(\mathbf{x}_1,\mathbf{x}')f_{\sigma'}(\mathbf{x}',\mathbf{x}_2),
\end{aligned}\tag{29.101}$$

where $U_{\Delta}(\mathbf{x})=\langle\hat{U}_{\Delta}(\mathbf{x})\rangle$ (see Equation 29.47). It should be noted that for a semiconductor excited by a single-plane wave this potential vanishes in an overall neutral system due to the translational invariance. In the two-wave excitation setup the effect of U_{Δ} is small for bound exciton states if the order of the multiwave mixing response is not too high.

Equations 29.100 constitute the semiconductor Bloch equations, which are widely used for studying nonperturbative effects in the dynamics of optically excited semiconductors. It should be emphasized that the quantity of main interest is the exciton polarization P_{μ} since these are the excitons that constitute true single-particle semiconductor states. As follows from Equations 29.63 and 29.72, P_{μ} is related to the interband polarization $p_{\sigma,s}$ through

$$P_{\mu}=\int d\mathbf{x}\,d\mathbf{y}\,\phi^{\star}_{\mu}(\mathbf{x},\mathbf{y})p_{\sigma_{\mu},s_{\mu}}(\mathbf{x},\mathbf{y}).\tag{29.102}$$

For bound exciton states this naturally introduces a characteristic spatial scale, the exciton Bohr radius r_B (see Equation 29.67). At this point we assume that we deal with a deep and narrow quantum well, $\epsilon(\mathbf{x})=\epsilon+\Delta\epsilon(z)$, and that the system is invariant with respect to translations along the quantum well, that is, there are no random fluctuations of the width of the well.

The existence of the characteristic spatial scale together with the assumption that the typical spatial variation of the external excitation in the plane of the quantum well is small compared to the Bohr radius $K^{(1,2)}r_B \ll 1$ allows one to simplify the semiconductor Bloch equation using the parametric approximation. For this we introduce new spatial variables $\mathbf{R}=(\mathbf{x}+\mathbf{y})/2$ and $\mathbf{r}=\mathbf{x}-\mathbf{y}$. Having in mind the consecutive convolution of the solutions with the exciton wave function we can neglect the terms $\propto\Delta K r_B$ and leave only the dependence on $\mathbf{R}$ running along the quantum well as a parameter. Thus, assuming for simplicity that $\mathbf{K}^{(1)}=0$ we approximate Equations 29.98 by

$$\begin{aligned}
i\hbar\dot{p}_{\sigma,s}(\mathbf{r},\mathbf{R}) &= \tilde{K}_{\sigma,s}[p]+\mathcal{A}_{\sigma,s}(\mathbf{R})\delta(\mathbf{r})\\
&\quad-\int d\mathbf{r}'\Big[\tilde{\mathcal{A}}_{\sigma',s}(\mathbf{r}',\mathbf{R})h_{\sigma',\sigma}(\mathbf{r}'-\mathbf{r},\mathbf{R})-\tilde{\mathcal{A}}_{\sigma,s'}(\mathbf{r}',\mathbf{R})e_{s',s}(\mathbf{r}'-\mathbf{r},\mathbf{R})\Big],\\
-i\hbar\dot{e}_{s_1,s_2}(\mathbf{r},\mathbf{R}) &= \hat{K}_{s_1,s_2}[e]\\
&\quad+\int d\mathbf{r}'\Big[\tilde{\mathcal{A}}^{\star}_{\sigma',s_1}(\mathbf{r}',\mathbf{R})p_{\sigma',s_2}(\mathbf{r}'+\mathbf{r},\mathbf{R})-\tilde{\mathcal{A}}_{\sigma',s_2}(\mathbf{r}',\mathbf{R})p^{\star}_{\sigma',s_1}(\mathbf{r}'-\mathbf{r},\mathbf{R})\Big],\\
-i\hbar\dot{h}_{\sigma_1,\sigma_2}(\mathbf{r},\mathbf{R}) &= \hat{K}_{\sigma_1,\sigma_2}[h]\\
&\quad+\int d\mathbf{r}'\Big[\tilde{\mathcal{A}}^{\star}_{\sigma_1,s'}(\mathbf{r}',\mathbf{R})p_{\sigma_2,s'}(-\mathbf{r}-\mathbf{r}',\mathbf{R})-\tilde{\mathcal{A}}_{\sigma_2,s'}(\mathbf{r}',\mathbf{R})p^{\star}_{\sigma_1,s'}(\mathbf{r}+\mathbf{r}',\mathbf{R})\Big].
\end{aligned}\tag{29.103}$$

Here $\tilde{\mathcal{A}}_{\sigma,s}(\mathbf{r},\mathbf{R})=\mathcal{A}_{\sigma,s}(\mathbf{R})\delta(\mathbf{r})-V(\mathbf{r})p_{\sigma,s}(\mathbf{r},\mathbf{R})$ and the integro-differential operators in Equations 29.100 are substituted by

$$\begin{aligned}
\hat{H}_{s_1,s'}f_{s'} &= \left[\frac{\hbar^2}{2m_e}\nabla_{\mathbf{r}}^2+\epsilon_{s_1}(z)\right]f_{s_1}(\mathbf{r},\mathbf{R})-\int d\mathbf{r}'V(\mathbf{r}')e_{s_1,s'}(\mathbf{r}',\mathbf{R})f_{s'}(\mathbf{r}-\mathbf{r}',\mathbf{R}),\\
\hat{H}_{\sigma_1,\sigma'}f_{\sigma'} &= -\nabla_{\mathbf{r}}\cdot\frac{\hbar^2}{2\mathrm{M}_{\sigma_1,\sigma'}}\cdot\nabla_{\mathbf{r}}f_{\sigma'}(\mathbf{r},\mathbf{R})-\epsilon_{\sigma_1}(z)f_{\sigma_1}(\mathbf{r},\mathbf{R})\\
&\quad-\int d\mathbf{r}'V(\mathbf{r}')h_{\sigma_1,\sigma'}(\mathbf{r}',\mathbf{R})f_{\sigma'}(\mathbf{r}-\mathbf{r}',\mathbf{R}).
\end{aligned}\tag{29.104}$$

Equations 29.103 are sufficiently general for studying various nonlinear effects. Before we turn to further approximations in order to extract the Rabi oscillations, we would like to sketch the procedure to find the polarizations of multiwave mixing response. As has been discussed earlier in the case of two-wave excitation the translational invariance of the semiconductor equations along the quantum well is broken. Instead one has the symmetry with respect to finite translations $\Delta\mathbf{R} = 2\pi\Delta\mathbf{K}/\Delta K^2$. The same holds for the semiconductor Bloch equations, which is especially evident in the parametric approximation. Indeed, the parametric dependence on $\mathbf{R}$ originates from $\mathbf{A}(\mathbf{R})$, which is a periodic function of $\Delta\mathbf{R}$ and, hence, so are the solutions of Equations 29.103. Thus, the interband polarization $p_{\sigma,s}(\mathbf{r} = \mathbf{0}, \mathbf{R})$, which serves as the source of the outgoing re-emitted electromagnetic wave (see Equation 29.40), can be expanded in the Fourier series

$$p_{\sigma,s}(0,\mathbf{R}) = \sum_{m=-\infty}^{\infty} p_{\sigma,s}^{(m)} e^{im\Delta\mathbf{K}\cdot\mathbf{R}}. \tag{29.105}$$

The terms $m = 0$ and $m = 1$ correspond to the momenta brought by the excitation field, while the remaining terms are the polarizations of multiwave mixing response, for example, $m = -1, 2$ give the four-wave mixing polarizations, $m = -2, 3$ are the six-wave mixing components, and so on. In order to find the amplitudes of the multiwave mixing responses we merely use the formula of the inverse Fourier transform

$$p_{\sigma,s}^{(m)} = \int_0^1 d\alpha\, p_{\sigma,s}(0, \alpha\Delta\mathbf{R}) e^{-2\pi i\alpha m}. \tag{29.106}$$

Thus, once the solution of Equation 29.103 is known, the polarizations of the multiwave mixing response can be found immediately.

In order to see the oscillatory behavior of the interband polarization driven by the external field we need to make drastic simplifications of Equation 29.103, which correspond to considering the case of very short excitation pulses of high intensity. Such simplification is possible owing to the existence of the characteristic spatial scale and the radius of exciton states responsible for the resonant response. We consider all the terms in the r.h.s. of Equation 29.103 besides the kinetic energy as sources. The response, therefore, is governed by the free-particle propagators for the correlation functions and the Coulomb propagator for the interband polarization. The fundamental property of these propagators is that in the short time limit $t \to 0$ they turn to spatial δ-functions owing to fast spatial oscillations of the kernel

$$K(\mathbf{r}_1, \mathbf{r}_2; t) = \sqrt{\frac{m}{2\pi i t}} \exp\left[im \left| \mathbf{r}_1 - \mathbf{r}_2 \right|^2 / 2t \right]. \tag{29.107}$$

For example, for the interband polarization in the short time limit, the Coulomb propagator can be approximated by the free-particle propagator (Blinder 1984, Kunikeev 2000) with $m \approx m_h = (m_e^{-1} + M_{hh})^{-1}$ and $m \approx m_l = (m_e^{-1} + M_{lh})^{-1}$, where m_σ are the excitons' reduced masses. The effect of the dispersion of the electrons and holes on the *exciton* polarization is expressed as the distortion of the exciton wave function under the action of the free-particle propagators. The time scale, at which the distortion becomes essential, can be estimated as the time required for the initial δ-shape of the kernel to acquire the width of the order of the exciton Bohr radius. This leads to the estimate

$$T_c \sim \frac{m r_B^2}{4\pi}. \tag{29.108}$$

The numerical value of the typical time scale for GaAs is determined by $m_{hh} = 0.45 m_0$, $m_{lh} = 0.082 m_0$, $m = m_\Delta$, and $r_B = r_{xh} = \epsilon_b / 2 m_{xh} e^2$, where m_0 is the electron mass in empty space and $\epsilon_b = 13$ is the background dielectric function. Using these values in Equation 29.108 we find $T_c \sim 20$ fs. We would like to draw attention to the fact that $T_c \gg T_R \approx 1$ fs (see Equation 29.57), so that the rotating wave approximation is applicable at such time scales. Thus, for pulses with duration shorter than 20 fs and sufficiently high intensity, we can treat the semiconductor excitations as dispersionless. It can be shown that for the states in the discrete spectrum the condition is even less strict (Erementchouk and Leuenberger 2008).

In the dispersionless limit, Equations 29.103 take the simple form

$$\begin{aligned}
i\hbar\dot{p}_{\sigma,s}(\mathbf{r},\mathbf{R}) &= \mathcal{A}_{\sigma,s}(\mathbf{R})\delta(\mathbf{r}) - \mathcal{A}_{\sigma',s}(\mathbf{R}) h_{\sigma',\sigma}(-\mathbf{r},\mathbf{R}) - \mathcal{A}_{\sigma,s'}(\mathbf{R}) e_{s',s}(\mathbf{r},\mathbf{R}), \\
-i\hbar\dot{e}_{s_1,s_2}(\mathbf{r},\mathbf{R}) &= \mathcal{A}^{\star}_{\sigma',s_1}(\mathbf{R})\rho_{\sigma',s_2}(\mathbf{r},\mathbf{R}) - \mathcal{A}_{\sigma',s_2}(\mathbf{R})\rho^{\star}_{\sigma',s_1}(-\mathbf{r},\mathbf{R}), \qquad (29.109) \\
-i\hbar\dot{h}_{\sigma_1,\sigma_2}(\mathbf{r},\mathbf{R}) &= \mathcal{A}^{\star}_{\sigma_1,s'}(\mathbf{R})\rho_{\sigma_2,s'}(-\mathbf{r},\mathbf{R}) - \mathcal{A}_{\sigma_2,s'}(\mathbf{R})\rho^{\star}_{\sigma_1,s'}(\mathbf{r},\mathbf{R}),
\end{aligned}$$

where we assumed the strong resonance regime and neglected the small contribution $(\epsilon_s - \epsilon_\sigma - \hbar\Omega)p_{\sigma,s}$. The solutions of Equations 29.109 are singular, $\propto\delta(\mathbf{r})$, but by virtue of Equation 29.102 it does not pose any problem.

We limit ourselves to the consideration of the simplest case when the external field is circularly polarized with positive helicity (right polarized) and has the amplitude constant in the time, which corresponds to the continuous wave excitation tuned to resonance with the gap. The condition of circular polarization leaves only two nonvanishing interband polarizations corresponding to p_{h+} and p_{l+}, that is $\{\sigma = -3/2, s = -1/2\}$ and $\{\sigma = -1/2, s = 1/2\}$, respectively. Thus we find for the respective interband polarizations

$$p_{\sigma,s}(\mathbf{r},\mathbf{R};t) = -i\delta(\mathbf{r}) \frac{1}{\hbar\Omega_{\sigma,s}(\mathbf{R})} \mathcal{A}_{\sigma,s}(\mathbf{R}) \sin\left[\Omega_{\sigma,s}(\mathbf{R}) t \right], \tag{29.110}$$

where $\hbar\Omega_{\sigma,s}(\mathbf{R}) = \left| \mathcal{A}_{\sigma,s}(\mathbf{R}) \right|$. It should be noted that only when $\Omega_{\sigma,s}$ is uniform along the quantum well, that is, in the case of the single-wave excitation, it defines the frequency of the Rabi oscillations. When the semiconductor is excited by two incoming waves, the frequency of temporal oscillations of the polarizations of the multiwave mixing response at sufficiently long



FIGURE 29.4 The exciton polarization in the case when the excitation consists of two plane waves with noncollinear wave vectors. The solid and dashed lines show the response in the forward ($m = 1$) and the four-wave mixing ($m = 2$) directions for (a) $\Omega^{(1)}_{\sigma,s}/\Omega^{(2)}_{\sigma,s} = 1$, (b) $\Omega^{(1)}_{\sigma,s}/\Omega^{(2)}_{\sigma,s} = 2$. The effective time is defined as $\tilde{t} = \Omega^{(2)}_{\sigma,s} t$.

time scales have two characteristic frequencies obtained as superpositions of the Rabi frequencies of each pulse $\left|\Omega^{(1)}_{\sigma,s} \pm \Omega^{(2)}_{\sigma,s}\right|$ (see Figure 29.4).

29.6 Conclusion

In order to keep the introduction into the theory of the semiconductor nonlinear response concise, we have concentrated on the problem of low energy excitation, when the dynamics of the semiconductor is determined by the bound states of the electron–hole pairs (excitons). In this regime the most natural description is provided by the effective quantum field theory, which accounts for the nonconstant number of particles in the semiconductor bands. The operator equations of motion, in turn, give access to all the information about the semiconductor and the electromagnetic fields. Using these equations one can either study the time evolution of the observables such as the macroscopic electromagnetic field $\langle \mathbf{A}(\mathbf{x},t)\rangle$ or the exciton polarization $\left\langle \hat{B}_\mu \right\rangle$; or one can turn, for example, to the single-particle exciton density matrix $\left\langle \hat{B}^\dagger_\lambda \hat{B}_\mu \right\rangle$ in order to incorporate into the picture the decoherence effect of the interaction with the phonon bath; or one can study the many-body properties of the semiconductor excitations looking at, say, the two-exciton density matrix $\left\langle \hat{B}^\dagger_\kappa \hat{B}^\dagger_\lambda \hat{B}_\mu \hat{B}_\nu \right\rangle$.

Unfortunately, the analysis of the equations of motion is tremendously hardened by their nonlinearity. The complexity is not of merely technical origin but reflects the concealed variety of physical phenomena. This should be taken into account when the equations of motion are simplified. As demonstrated in the main text, one can relatively easily develop the perturbational description of the semiconductor dynamics. However, one should be careful in applying the results of the perturbational approach to the situation, when the intensity of the excitation is significantly high, so that the properly defined pulse area approaches π. The perturbational series diverges in this case signifying the appearance of a new class of phenomena related to the reconstruction of the spectrum. The effect of the reconstruction on the semiconductor dynamics requires a non-perturbative treatment and has been illustrated above for the example of the Rabi oscillations.

We have covered the basics of the theory to the degree where it can be straightforwardly applied to various physical situations. However, we have left many details mentioned only on the formal level, such as the symmetries of the semiconductor bands, the specific form of the tensors of effective masses, and the matrix elements of the momentum operator between different bands. These details, while being easy to incorporate into the theory developed in the main text, may significantly simplify the analysis of the particular case. As a source of the fundamental insight into the physics of semiconductors we would like to refer the reader to the great book by Yu and Cardona (2004), the details of the symmetrical properties of the solids are provided in Bir and Pikus (1974), and the optical semiconductor response is considered in Haug and Koch (2004).

Acknowledgment

We would like to thank Prof. Xiaoqin Li for providing us with the data obtained in the experiments reported in Zhang et al. (2005). We also thank Sergio Tafur for useful comments. We acknowledge support from NSF-ECCS 0725514, the DARPA/MTO Young Faculty Award HR0011-08-1-0059, NSF-ECCS 0901784, and AFOSR FA9550-09-1-0450.

References

Arfken, G. B. and H. J. Weber. *Mathematical Methods for Physicists*. Academic Press, New York, 6th edn., 2005.

Bir, G. L. and G. E. Pikus. *Symmetry and Strain-Induced Effects in Semiconductors*. Wiley, New York, 1974.

Blinder, S. M. Semiclassical approximation for the nonrelativistic Coulomb propagator. *Phys. Rev. Lett.*, 52(20):1771–1773, 1984.

Cohen-Tannoudji, C., J. Dupont-Roc, and G. Grynberg. *Atom–Photon Interactions. Basic Processes and Applications*. Wiley, New York, 1992.

Erementchouk, M. V. and M. N. Leuenberger. Rabi oscillations in semiconductor multiwave mixing response. *Phys. Rev. B*, 78:075206, 2008.

Erementchouk, M. V., M. N. Leuenberger, and L. J. Sham. Many-body interaction in semiconductors probed with two-dimensional Fourier spectroscopy. *Phys. Rev. B*, 76:115307, 2007.

Haug, H. and S. W. Koch. *Quantum Theory of the Optical and Electronic Properties of Semiconductors*. World Scientific, Singapore, 2004.

Ivchenko, E. L. *Optical Spectroscopy of Semiconductor Nanostructures*. Alpha Science International, Oxford, U.K., 2005.

Johnson, N. F. and P. M. Hui. Theory of propagation of scalar waves in periodic and disordered composite structures. *Phys. Rev. B*, 48(14):10118–10123, 1993.

Jonas, D. M. Two-dimensional femtosecond spectroscopy. *Annu. Rev. Phys. Chem.*, 54:425–463, 2003.

Khalil, M., N. Demirdoven, and A. Tokmakoff. Coherent 2d IR spectroscopy: Molecular structure and dynamics in solution. *J. Phys. Chem. A*, 107:5258–5279, 2003.

Kunikeev, S. D. Coulomb propagator in the WKB approximation. *J. Phys. A Math. Gen.*, 33:5405–5428, 2000.

Langbein, W., G. Kocherscheidt, and R. Zimmermann. Probing localized excitons by speckle analysis of resonant light scattering. In H. Kalt and M. Hetterich (eds.), *Optics of Semiconductors and Their Nanostructures*, vol. 146 of *Springer Series in Solid-State Sciences*, pp. 47–72. Springer, Berlin, Germany, 2004.

Li, X., T. Zhang, C. N. Borca, and S. T. Cundiff. Many-body interactions in semiconductors probed by optical two-dimensional Fourier transform spectroscopy. *Phys. Rev. Lett.*, 96:057406, 2006.

Luttinger, J. M. Quantum theory of cyclotron resonance in semiconductors: General theory. *Phys. Rev.*, 102(4):1030–1041, 1956.

Luttinger, J. M. and W. Kohn. Motion of electrons and holes in perturbed periodic fields. *Phys. Rev.*, 97(4):869–883, 1955.

Mukamel, S. *Principles of Nonlinear Optical Spectroscopy*. Oxford University Press, New York, 1995.

Ostreich, T. Higher-order Coulomb correlation in the nonlinear optical response. *Phys. Rev. B*, 64:245203, 2001.

Ostreich, T., K. Schonhammer, and L. J. Sham. Theory of exciton–exciton correlation in nonlinear optical response. *Phys. Rev. B*, 58(19):12920–12936, 1998.

Parfitt, D. G. W. and M. E. Portnoi. The two-dimensional hydrogen atom revisited. *J. Math. Phys.*, 43(10):4681–4691, 2002.

Sakoda, K. *Optical Properties of Photonic Crystals*, vol. 80 of *Optical Sciences*. Springer, Berlin, Germany, 2nd edn., 2005.

Schiff, L. I. *Quantum Mechanics*. McGraw Hill, New York, 1949.

Schmitt-Rink, S., D. S. Chemla, and D. A. B. Miller. Linear and nonlinear optical properties of semiconductor quantum wells. *Adv. Phys.*, 38(2):89–188, 1989.

Yu, P. Y. and M. Cardona. *Fundamentals of Semiconductors: Physics and Materials Properties*. Springer, Berlin, Germany, 2004.

Zhang, T., C. N. Borca, X. Li, and S.T. Cundiff. Optical two-dimensional Fourier transform spectroscopy with active interferometric stabilization. *Opt. Express*, 13(19):7432–7431, 2005.

Zhu, B. and K. Huang. Effect of valence-band hybridization on the exciton spectra in GaAs–$\mathrm{Ga}_{1-}x\mathrm{Al}_x\mathrm{As}$ quantum wells. *Phys. Rev. B*, 36(15):8102–8108, 1987.

30

Light Scattering from Nanofibers

30.1 Introduction **30**-1
30.2 Background **30**-1
30.3 Basic Theory **30**-3
Diffraction by a Cylindrical Nanofiber • Nanofiber Normal Modes • Calculation of the Scattered Field • Semicylinder on an Ideally Reflecting Surface
30.4 Some Numerical Results **30**-9
Angular Distribution of Scattered Light • Total Scattered Intensity versus Incidence Angle • Total Scattered Intensity versus Frequency • Excitation near Exciton Resonance
30.5 Experimental Implementation **30**-11
30.6 Discussion **30**-12
30.7 Summary and Outlook **30**-12
Acknowledgments **30**-13
References **30**-13

Vladimir G. Bordo
A.M. Prokhorov General Physics Institute

30.1 Introduction

The progress in nanotechnology has led to a possibility of fabricating needlelike crystals that have transverse dimensions in the submicron range. They can be grown from different inorganic semiconductor materials such as InP (Duan et al., 2001; Wang et al., 2001), ZnO (Huang et al., 2001), GaN (Johnson et al., 2002), CdS (Duan et al., 2003), GaSb (Chin et al., 2006), as well as from *p*-phenylene oligomers (Balzer and Rubahn, 2001, 2005; Schiek et al., 2005). Alternatively, one can also obtain fibers with a diameter of a few tens of nanometers by means of drawing from silica (Tong et al., 2003). Such structures are called nanofibers or nanowires. The morphology of individual nanofibers and their mutual alignment can be controlled by the use of appropriate growth conditions and substrate surfaces (Balzer and Rubahn, 2005). The nanofibers can be detached from the substrate, thus allowing one to study their properties under a variety of different conditions, including free-floating nanoaggregates (Brewer et al., 2005). They act as optical waveguides (Balzer et al., 2003; Johnson et al., 2003; Tong et al., 2003; Barrelet et al., 2004) and demonstrate remarkable photoluminescence properties (Wang et al., 2001; Thilsing-Hansen et al., 2005). Under pumping conditions, they can operate as nanoscale lasers (“nanolasers”) (Huang et al., 2001; Johnson et al., 2002, 2003; Duan et al., 2003; Agarwal et al., 2005; Quochi et al., 2005, 2006; Chin et al., 2006; Zimmler et al., 2008).

Light scattering by nanofibers plays an important role in optical processes at the nanoscale. Being grown on a substrate, nanofibers form an irregular array. The optical properties of such an ensemble are determined, on the one hand, by the optical response of individual aggregates and, on the other hand, by light scattering from nanofibers, which results in interaction between them. Light incident at a sample can launch the nanofiber optical modes or create excitons. Both processes manifest themselves in the intensity distribution of scattered light, thus providing valuable information on different nanofiber properties.

30.2 Background

In the simplest theoretical approach, a nanofiber is represented by an infinitely long dielectric circular cylinder. Light scattering by such an object was the first diffraction problem to be solved rigorously. Its solution dates back to Lord Rayleigh (Lord Rayleigh, 1881), who found the electromagnetic field diffracted from a cylinder of arbitrary radius and refractive index illuminated by a plane wave incident perpendicularly to its axis. Much later, that result was generalized to the case of oblique incidence (Wait, 1955). If α is the incidence angle relatively normal to the cylinder axis, then the scattered radiation is propagated along the surface of the cone with apical angle $(\pi - 2\alpha)$ (Kerker, 1969). The field amplitudes inside the cylinder and outside it are expressed in terms of a series of the Bessel functions of the first kind and Hankel functions, respectively. The result depends on the polarization of the incident wave. One can decompose it into two independent polarizations: (1) the transverse magnetic (TM) mode for which there is no magnetic vector component along the cylinder axis and (2) the transverse electric (TE) mode for which there is no electric field component along that axis. When the incident wave propagates perpendicularly to the cylinder axis, both the field inside the cylinder and the scattered field are of the same polarization as the incident wave. For oblique incidence, however, the incident TM waves are partially converted into scattered TE waves. Similarly, the incident TE waves are partially converted into scattered TM waves.

Light scattering in the far zone is characterized by the *scattering efficiency*, Q_{sca}, which is defined as the scattering cross section per unit length of the cylinder integrated over all the values of the scattering angle, θ, divided by the cylinder diameter, $2a$. If the polarization of the scattered radiation is not specified, light scattering is completely described by the two scattering efficiencies, $Q_{\text{sca}}^{\text{TM}}$ and $Q_{\text{sca}}^{\text{TE}}$, where the superscript denotes the polarization of the incident wave. In the limit where the diameter of the cylinder is sufficiently small relative to the wavelength, all the results are considerably simplified. If the refractive index of the cylinder relative to that of the surrounding medium is n and the wave number of the incident wave is k, the scattering efficiencies are reduced to the following form (Kerker, 1969):

$$Q_{\text{sca}}^{\text{TM}} = \frac{\pi^2(ka)^3}{8}(n^2-1)^2; \quad Q_{\text{sca}}^{\text{TE}} = \frac{\pi^2(ka)^3}{4}\left(\frac{n^2-1}{n^2+1}\right)^2. \qquad (30.1)$$

If the angle θ is not close to 0 or π,* the ratio of the intensities of the two components is

$$\rho = \frac{I^{\text{TE}}}{I^{\text{TM}}} = \frac{4\sin^2\theta}{(n^2+1)^2}. \qquad (30.2)$$

This leads to the conclusion that the radiation scattered in both forward and backward directions will be partially polarized even if the incident radiation is completely unpolarized.

The abandonment of the assumption of an infinite cylinder length leads to the necessity to use numerical methods. For some ranges of the relevant parameters, simplified treatments can provide accurate results. If the cylinder radius a is much smaller than the wavelength λ, the integral equation for the electric field amplitude can be solved by the method of moments (Uzunoglu et al., 1978). In the case where the parameter $ka(n-1)$ is comparable with unity or smaller, an iterative method can be applied, which is quite effective for both long (Cohen et al., 1983) and short (Haracz et al., 1984) cylinders. For the general case of a finite cylinder length l, the approach based on solving the electric field integral equation by using the method of moments is not very efficient. A more appropriate way is to apply a Fourier transform, which leads to a Fredholm integral equation of the first kind. This method has been applied to the cylinders with aspect ratios $p = l/(2a)$ as large as 10 and the lengths parameters up to $kl \sim 7$ (Shepherd and Holt, 1983). An alternative approach exploits the extended boundary condition method (EBCM), also known as the T-matrix method, in which both the incident and scattered fields are expanded in spherical vector wavefunctions. The truncation of the expansions at N terms leads to the system of $2N$ linear equations for the scattered field coefficients. The EBCM calculations carried out for the backscattering from a dielectric rod in the microwave region have demonstrated a satisfactory agreement with the existing experimental data (Ruppin, 1990). However, the EBCM method is tractable only when the size parameters ka and p are less than certain limits; e.g., for $n = 1.31$, $ka < 2.75$ and $p < 5.0$ (Kuik et al., 1994). Its convergence also becomes more difficult with increasing the dielectric constant of the cylinder.

A remarkable feature of light scattering from a dielectric cylinder at a fixed angle of incidence is the existence of resonant peaks in the scattering cross section plotted versus the size parameter (Van Bladel, 1977). Such peaks do not occur for a perfectly conducting cylinder and their sharpness increases with the dielectric constant of the cylinder. The resonant frequencies are determined by the poles of the expansion coefficients in the complex plane of the size parameter (Owen et al., 1981). The linewidths of the peaks are very sensitive to the circularity of the cylinder and to optical loss within or on the cylinder surface. These findings were confirmed experimentally in the scattering of either broadband radiation or light from a tunable laser by optical-communication fibers and used for the accurate determination of their diameters and shapes (Ashkin et al., 1981; Owen et al., 1981). The peaks of another kind are displayed in the dependence of the differential scattering efficiency on the angle between the incident light beam and the cylinder axis (Birkhoff et al., 1977). Fitting the angular positions of observed maxima in the scattered intensity provides a sensitive method for determining fiber radii, reproducible within ±3%–5%.

An essential feature of light scattering from nanofibers is reflection of the scattered radiation from the substrate surface. Therefore, it is desirable to take this effect into account when modeling nanofibers. If the cylinder axis is oriented parallelly to a flat reflecting surface, the diffraction problem is reduced to a two-dimensional one. The influence of the substrate can be calculated by introducing the Fresnel reflection coefficients. The corresponding solution can be found in the form of a series of the Bessel and Hankel functions. The procedure involves the truncation of the expansions for the field amplitudes at some index N, which is related to the size parameter by the rule $N \simeq 3ka$ (Borghi et al., 1997). Light scattering from nanofibers grown on a substrate involves the multiple-scattering effect. In some special cases, the nanofibers form an array of mutually parallel nanoaggregates oriented either parallelly or perpendicularly to the substrate surface. As it has been shown for an arbitrary configuration of parallel cylinders, the light scattering in such a system can be expressed as an infinite sum of the orders of scattering (Twersky, 1952). The first-order scattering originates from a diffraction of the incident wave on each cylinder. The second order results from a diffraction of the first-order-scattered radiation on each cylinder, and so on. A common approach to calculating the scattered field is to express the multiple-scattering linear equations in matrix form and then to find the corresponding scattering coefficients either by iterative method, or by direct matrix inversion, or by using a quadratic-programming algorithm. By this means, it has been found, in particular, that in an array of abutting cylinders, the resonant character of the cylinders with respect to the size parameter, ka, is damped (Bever and Allebach, 1992).

---

* We reckon the angle θ from the plane perpendicular to the plane of incidence (see Figure 30.1).

30.3 Basic Theory

In this section, we shall give the basic equations that describe light scattering from nanofibers (Bordo, 2006, 2007). We shall consider two models of a nanofiber: (1) an infinite circular dielectric cylinder (Figure 30.1) and (2) an infinite circular dielectric semicylinder placed on a perfectly reflecting surface (Figure 30.2). Although it might be possible that these models do not reproduce some details of light scattering, they nevertheless provide a fundamental understanding of this phenomenon. To match the conditions of many experiments with nanofibers, we assume that the incident radiation is represented by a pulsed Gaussian light beam.

30.3.1 Diffraction by a Cylindrical Nanofiber

Let us assume first that a nanofiber has a circular cross-section of radius a, both the nanofiber and surrounding medium are isotropic and are characterized by the dielectric functions ε_2 and ε_1, respectively. We choose the z axis along the nanofiber axis and the y axis in the plane containing both the z axis and the beam axis. Then the incident wave electric field has the form

$$\mathbf{E}_i(x,y,z,t) = \mathbf{E}_{i0}(x,y,z,t)\exp(-iq_{10}y + i\beta_0 z - i\omega_0 t), \qquad (30.3)$$



FIGURE 30.1 Model of a nanofiber: dielectric cylinder.



FIGURE 30.2 Model of a nanofiber: dielectric semicylinder on a perfectly reflecting surface.

where the field amplitude is given by

$$\mathbf{E}_{i0}(x,y,z,t) = \mathbf{E}_0 \exp\left[-\frac{x^2 + (y\sin\alpha + z\cos\alpha)^2}{2\sigma^2}\right]\exp\left(-\frac{t^2}{2\tau^2}\right), \qquad (30.4)$$

where

- $-q_{10}$ and β_0 are the projections of the wave vector onto the axes y and z, respectively
- ω_0 is the frequency of the incident wave
- α is the angle of incidence with respect to the y axis
- σ and τ are the radius and pulse duration of the light beam, respectively

A similar expression is valid for the magnetic field of the incident beam, $\mathbf{H}_i(x, y, z, t)$.

In experiments, the beam radius is much larger than the nanofiber radius, i.e., $\sigma \gg a$. In such a case, in the vicinity of the nanofiber, Equation 30.4 is reduced to the following* form:

$$\mathbf{E}_{i0}(z,t) \approx \mathbf{E}_0 \exp\left(-\frac{z^2\cos^2\alpha}{2\sigma^2}\right)\exp\left(-\frac{t^2}{2\tau^2}\right). \qquad (30.5)$$

On the other hand, to simplify the consideration, we shall assume that the beam radius is much less than the nanofiber length. Then one can neglect the edge effects and consider the nanofiber as infinitely long.

The total electric field has the form

$$\mathbf{E} = \begin{cases} \mathbf{E}_i + \mathbf{E}_1 & \text{if } r > a; \\ \mathbf{E}_2 & \text{if } r < a, \end{cases} \qquad (30.6)$$

where $\mathbf{E}_1$ and $\mathbf{E}_2$ are the electric field vectors of the scattered field and the field inside the nanofiber, respectively. The total magnetic field vector, $\mathbf{H}$, is represented in a similar form. The fields $\mathbf{E}_1$, $\mathbf{E}_2$, $\mathbf{H}_1$, and $\mathbf{H}_2$ in turn can be found in terms of the Hertz vectors, Π_1 and Π_2, whose rectangular components satisfy the scalar wave equation. The Hertz vector for an infinite cylinder has the only nonzero component, $\Pi_z \equiv \psi$, which can be decomposed into two contributions, ψ^{TM} and ψ^{TE}, associated with TM and TE polarizations, respectively. Then, the electromagnetic field components in the cylindrical coordinates (r, θ, z) are found as (Stratton, 1941)

$$E_{jr} = \frac{\partial^2\psi_j^{\mathrm{TM}}}{\partial z\partial r} - \frac{1}{cr}\frac{\partial^2\psi_j^{\mathrm{TE}}}{\partial t\partial\theta}, \qquad (30.7)$$

$$E_{j\theta} = \frac{1}{r}\frac{\partial^2\psi_j^{\mathrm{TM}}}{\partial z\partial\theta} + \frac{1}{c}\frac{\partial^2\psi_j^{\mathrm{TE}}}{\partial t\partial r}, \qquad (30.8)$$

---

* This approximation is valid outside the nanofiber region $|z| \le a\tan\alpha$.

$$E_{jz} = \frac{\partial^2 \psi_j^{\mathrm{TM}}}{\partial z^2} - \frac{\epsilon_j}{c^2} \frac{\partial^2 \psi_j^{\mathrm{TM}}}{\partial t^2}, \tag{30.9}$$

$$H_{jr} = \frac{\epsilon_j}{r} \frac{\partial^2 \psi_j^{\mathrm{TM}}}{\partial t \partial \theta} + \frac{\partial^2 \psi_j^{\mathrm{TE}}}{\partial z \partial r}, \tag{30.10}$$

$$H_{j\theta} = -\epsilon_j \frac{\partial^2 \psi_j^{\mathrm{TM}}}{\partial t \partial r} + \frac{1}{r} \frac{\partial^2 \psi_j^{\mathrm{TE}}}{\partial z \partial \theta}, \tag{30.11}$$

$$H_{jz} = \frac{\partial^2 \psi_j^{\mathrm{TE}}}{\partial z^2} - \frac{\epsilon_j}{c^2} \frac{\partial^2 \psi_j^{\mathrm{TE}}}{\partial t^2}, \tag{30.12}$$

where

- c is the speed of light in vacuum
- the subscript j labels different media: $j = 1$ corresponds to the surrounding medium, whereas $j = 2$ denotes the nanofiber interior

We shall seek the functions ψ_j^μ (μ = TM or TE) in the form of the Fourier integral

$$\psi_j^\mu(x, y, z, t) = \frac{1}{(2\pi)^2} \int_{-\infty}^{\infty} \int_{-\infty}^{\infty} \tilde{\psi}_j^\mu(x, y; \beta, \omega) e^{i\beta z - i\omega t} d\beta d\omega. \tag{30.13}$$

The representation (30.13) can be considered as a superposition of an infinite number of the elementary waves $\tilde{\psi}_j^\mu e^{i\beta z - i\omega t}$, each of which should satisfy the wave equation. The Fourier-transformed quantities $\tilde{\psi}_j^\mu$, therefore, can be expanded in the series of the cylindrical functions as follows:

$$\tilde{\psi}_j^{\mathrm{TM}}(r, \theta; \beta, \omega) = \frac{1}{q_j^2} \sum_{n=0}^{\infty} Z_n(q_j r)\left[a_{jn}(\beta, \omega)\sin(n\theta) + b_{jn}(\beta, \omega)\cos(n\theta)\right], \tag{30.14}$$

$$\tilde{\psi}_j^{\mathrm{TE}}(r, \theta; \beta, \omega) = \frac{1}{q_j^2} \sum_{n=0}^{\infty} Z_n(q_j r)\left[c_{jn}(\beta, \omega)\sin(n\theta) + d_{jn}(\beta, \omega)\cos(n\theta)\right], \tag{30.15}$$

where the functions $Z_n(X)$ are determined as

$$Z_n(X) = \begin{cases} H_n^{(1)}(q_1 r) & \text{if } r > a; \\ J_n(q_2 r) & \text{if } r < a, \end{cases} \tag{30.16}$$

with

$$q_j = \sqrt{\frac{\omega^2}{c^2}\epsilon_j - \beta^2}, \tag{30.17}$$

J_n and $H_n^{(1)}$ are the Bessel functions of the first kind and Hankel functions, respectively. The choice of the Bessel functions for the cylinder interior ensures finiteness of the solution at its center, whereas the Hankel functions have proper behavior at infinite distance from the cylinder.

The continuity of the tangential components of the total fields, $E_{j\theta}$, E_{jz}, $H_{j\theta}$, and H_{jz}, across the boundary $r = a$ leads to the equations for the coefficients a_{jn}, b_{jn}, c_{jn}, and d_{jn}. Taking into account that $y = r \sin\theta$, one can use the expansion

$$e^{-iq_{10} r \sin\theta} = \sum_{n=-\infty}^{\infty} J_n(q_{10} r) e^{-in\theta} \tag{30.18}$$

in Equation 30.3. Then, combining the terms with the same θ-dependence in the boundary conditions and performing the inverse Fourier transform, one obtains the following equations:

$$\hat{M}_n \vec{A}_n = \vec{F}_n, \tag{30.19}$$

$$\hat{M}_n \vec{B}_n = \vec{G}_n, \tag{30.20}$$

where

$$\hat{M}_n = \begin{pmatrix} J_n(q_2 a) & 0 & -H_n^{(1)}(q_1 a) & 0 \\ \frac{i\beta n}{q_2^2 a} J_n(q_2 a) & -\frac{i\omega}{c q_2} J_n'(q_2 a) & -\frac{i\beta n}{q_1^2 a} H_n^{(1)}(q_1 a) & \frac{i\omega}{c q_1} H_n^{(1)\varepsilon'}(q_1 a) \\ \frac{i\omega\epsilon_2}{c q_2} J_n'(q_2 a) & -\frac{i\beta n}{q_2^2 a} J_n(q_2 a) & -\frac{i\omega\epsilon_1}{c q_1} H_n^{(1)'}(q_1 a) & \frac{i\beta n}{q_1^2 a} H_n^{(1)}(q_1 a) \\ 0 & J_n(q_2 a) & 0 & -H_n^{(1)}(q_1 a) \end{pmatrix} \tag{30.21}$$

and

$$\vec{A}_n = \begin{pmatrix} a_{2n} \\ d_{2n} \\ a_{1n} \\ d_{1n} \end{pmatrix}, \quad \vec{B}_n = \begin{pmatrix} -b_{2n} \\ c_{2n} \\ -b_{1n} \\ c_{1n} \end{pmatrix}. \tag{30.22}$$

Here, the prime above the Bessel and Hankel functions denotes differentiation with respect to their argument. The vector functions $\vec{F}_n$ and $\vec{G}_n$ depend on the polarization of the incident beam and are determined as

$$\vec{F}_n^{\mathrm{TM}} = \begin{pmatrix} -2i\sigma_n \tilde{E}_{i0} \cos\alpha J_n(q_{10} a) \\ 2\sigma_n \tilde{E}_{i0} \sin\alpha\left[n J_n(q_{10} a)/q_{10} a\right] \\ 2\sigma_n \tilde{H}_{i0} J_n'(q_{10} a) \\ 0 \end{pmatrix}, \tag{30.23}$$

$$\vec{G}_n^{\mathrm{TM}} = \begin{pmatrix} -2\tau_n (1 - \sigma_n) \tilde{E}_{i0} \cos\alpha J_n(q_{10} a) \\ -2i\tau_n (1 - \sigma_n) \tilde{E}_{i0} \sin\alpha\left[n J_n(q_{10} a)/q_{10} a\right] \\ -2i\tau_n (1 - \sigma_n) \tilde{H}_{i0} J_n'(q_{10} a) \\ 0 \end{pmatrix}, \tag{30.24}$$

and

$$\vec{F}_n^{\mathrm{TE}} = \begin{pmatrix} 0 \\ -2i\tau_n(1-\sigma_n)\tilde{E}_{i0}J_n'(q_{10}a) \\ -2i\tau_n(1-\sigma_n)\tilde{H}_{i0}\sin\alpha\left[nJ_n(q_{10}a)/q_{10}a\right] \\ 2\tau_n(1-\sigma_n)\tilde{H}_{i0}\cos\alpha J_n(q_{10}a) \end{pmatrix}, \tag{30.25}$$

$$\vec{G}_n^{\mathrm{TE}} = \begin{pmatrix} 0 \\ -2\sigma_n\tilde{E}_{i0}J_n'(q_{10}a) \\ -2\sigma_n\tilde{H}_{i0}\sin\alpha\left[nJ_n(q_{10}a)/q_{10}a\right] \\ -2i\sigma_n\tilde{H}_{i0}\cos\alpha J_n(q_{10}a) \end{pmatrix}, \tag{30.26}$$

with

$$\sigma_n = \begin{cases} 0 & \text{if } n \text{ is even;} \\ 1 & \text{if } n \text{ is odd,} \end{cases} \tag{30.27}$$

and

$$\tau_n = \begin{cases} 1/2 & \text{if } n = 0; \\ 1 & \text{if } n \neq 0. \end{cases} \tag{30.28}$$

Here, we have introduced the Fourier-transformed amplitudes of the incident beam

$$\tilde{E}_{i0}(\beta,\omega) = E_0\frac{2\pi\sigma\tau}{\cos\alpha}\exp\left[-\frac{(\beta-\beta_0)^2\sigma^2}{2\cos^2\alpha}\right]\exp\left[-\frac{(\omega-\omega_0)^2\tau^2}{2}\right], \tag{30.29}$$

and a similar expression for $\tilde{H}_{i0}(\beta, \omega)$.

Solving Equations 30.19 and 30.20, one obtains the Fourier-transformed electromagnetic field components both inside the nanofiber and outside it. We shall be interested, however, in the field scattered by the nanofiber, which is described by the coefficients a_{1n}, b_{1n}, c_{1n}, and d_{1n}. They are found as

$$a_{1n}(\beta,\omega) = \frac{D_{1n}(\beta,\omega)}{D_n(\beta,\omega)}, \tag{30.30}$$

$$b_{1n}(\beta,\omega) = -\frac{D_{2n}(\beta,\omega)}{D_n(\beta,\omega)}, \tag{30.31}$$

$$c_{1n}(\beta,\omega) = \frac{D_{3n}(\beta,\omega)}{D_n(\beta,\omega)}, \tag{30.32}$$

$$d_{1n}(\beta,\omega) = \frac{D_{4n}(\beta,\omega)}{D_n(\beta,\omega)}, \tag{30.33}$$

where

D_n is the determinant of the matrix $\hat{M}_n$

D_{1n} and D_{4n} are the determinants of the matrices obtained from $\hat{M}_n$ by replacing the third and fourth columns with the column given by $\vec{F}_n$, respectively

D_{2n} and D_{3n} are the determinants of the matrices obtained from $\hat{M}_n$ by replacing the third and fourth columns with the column given by $\vec{G}_n$, respectively

The corresponding Fourier-transformed electric and magnetic field amplitudes can be written in the form

$$\tilde{E}_{1\mu}(r,\theta;\,\beta,\omega) = \tilde{E}_{i0}(\beta,\omega) \times\sum_{n=0}^{\infty}\left[A_{\mu n}(r;\,\beta,\omega)\sin(n\theta) + B_{\mu n}(r;\,\beta,\omega)\cos(n\theta)\right], \tag{30.34}$$

$$\tilde{H}_{1\mu}(r,\theta;\,\beta,\omega) = \tilde{H}_{i0}(\beta,\omega) \times\sum_{n=0}^{\infty}\left[C_{\mu n}(r;\,\beta,\omega)\sin(n\theta) + D_{\mu n}(r;\,\beta,\omega)\cos(n\theta)\right], \tag{30.35}$$

where the subscript μ runs over the components r, θ, and z, and the functions $A_{\mu n}$, $B_{\mu n}$, $C_{\mu n}$, and $D_{\mu n}$ are given by the equations

$$A_{rn}(r;\,\beta,\omega) = \frac{i\beta}{q_1}H_n^{(1)\prime}(q_1r)a_{1n}(\beta,\omega) - \frac{i\omega n}{cq_1^2r}H_n^{(1)}(q_1r)d_{1n}(\beta,\omega), \tag{30.36}$$

$$B_{rn}(r;\,\beta,\omega) = \frac{i\beta}{q_1}H_n^{(1)\prime}(q_1r)b_{1n}(\beta,\omega) + \frac{i\omega n}{cq_1^2r}H_n^{(1)}(q_1r)c_{1n}(\beta,\omega), \tag{30.37}$$

$$A_{\theta n}(r;\,\beta,\omega) = -\frac{i\beta n}{q_1^2r}H_n^{(1)}(q_1r)b_{1n}(\beta,\omega) - \frac{i\omega}{cq_1}H_n^{(1)\prime}(q_1r)c_{1n}(\beta,\omega), \tag{30.38}$$

$$B_{\theta n}(r;\,\beta,\omega) = \frac{i\beta n}{q_1^2r}H_n^{(1)}(q_1r)a_{1n}(\beta,\omega) - \frac{i\omega}{cq_1}H_n^{(1)\prime}(q_1r)d_{1n}(\beta,\omega), \tag{30.39}$$

$$A_{zn}(r;\beta,\omega) = H_n^{(1)}(q_1r)a_{1n}(\beta,\omega), \tag{30.40}$$

$$B_{zn}(r;\beta,\omega) = H_n^{(1)}(q_1r)b_{1n}(\beta,\omega). \tag{30.41}$$

$$C_{rn}(r;\,\beta,\omega) = \frac{i\omega\epsilon_1 n}{cq_1^2r}H_n^{(1)}(q_1r)b_{1n}(\beta,\omega) + \frac{i\beta}{q_1}H_n^{(1)\prime}(q_1r)c_{1n}(\beta,\omega), \tag{30.42}$$

$$D_{rn}(r;\beta,\omega) = -\frac{i\omega\epsilon_1 n}{cq_1^2 r}H_n^{(1)}(q_1 r)a_{1n}(\beta,\omega) + \frac{i\beta}{q_1}H_n^{(1)\prime}(q_1 r)d_{1n}(\beta,\omega), \tag{30.43}$$

$$C_{\theta n}(r;\beta,\omega) = \frac{i\omega\epsilon_1}{cq_1}H_n^{(1)\prime}(q_1 r)a_{1n}(\beta,\omega) - \frac{i\beta n}{q_1^2 r}H_n^{(1)}(q_1 r)d_{1n}(\beta,\omega), \tag{30.44}$$

$$D_{\theta n}(r;\beta,\omega) = \frac{i\omega\epsilon_1}{cq_1}H_n^{(1)\prime}(q_1 r)b_{1n}(\beta,\omega) + \frac{i\beta n}{q_1^2 r}H_n^{(1)}(q_1 r)c_{1n}(\beta,\omega), \tag{30.45}$$

$$C_{zn}(r;\beta,\omega) = H_n^{(1)}(q_1 r)c_{1n}(\beta,\omega), \tag{30.46}$$

$$D_{zn}(r;\beta,\omega) = H_n^{(1)}(q_1 r)d_{1n}(\beta,\omega). \tag{30.47}$$

Taking the Fourier transforms of Equations 30.34 and 30.35,

$$E_{1\mu}(r,\theta,z,t) = \frac{1}{(2\pi)^2}\int_{-\infty}^{\infty}\int_{-\infty}^{\infty}\tilde{E}_{1\mu}(r,\theta;\beta,\omega)e^{i\beta z - i\omega t}d\beta d\omega, \tag{30.48}$$

$$H_{1\mu}(r,\theta,z,t) = \frac{1}{(2\pi)^2}\int_{-\infty}^{\infty}\int_{-\infty}^{\infty}\tilde{H}_{1\mu}(r,\theta;\beta,\omega)e^{i\beta z - i\omega t}d\beta d\omega, \tag{30.49}$$

one obtains the solution of the problem under consideration.

The integrands in Equations 30.48 and 30.49 have the poles given by the zeros of the denominators $D_n(\beta,\omega)$ in Equations 30.30 through 30.33. On the other hand, these zeros determine the allowed values of pairs (β, ω) for the electromagnetic field in a free nanofiber, i.e., its normal modes (Stratton, 1941).

30.3.2 Nanofiber Normal Modes

Among the solutions of the equations

$$D_n(\beta,\omega) = 0, \tag{30.50}$$

there are those which are represented by pairs of real quantities $(\beta_{nm}, \omega_{nm})$. They give the propagation constants and frequencies of the waveguide (bound) modes. Such modes provide a complete description of the light propagation along the fiber in the steady-state regime far from the light source (Snyder and Love, 1983). Besides that, Equation 30.50 has solutions for which either β or ω, or both, have imaginary parts, i.e.,

$$\beta = \beta^r + i\beta^i, \tag{30.51}$$

$$\omega = \omega^r - i\omega^i. \tag{30.52}$$

The contribution of such poles to the integrals (30.48) and (30.49) leads to the transients along the fiber length or in time, or in both length and time, respectively. If β^i is small, the modes of the first type can propagate over long distances, and their portions localized within or near the fiber core are known as leaky modes (Snyder and Love, 1983). In the following, to distinguish between different modes, we shall call the first-type modes as *space-decaying* (*SD*) modes, whereas the second-type ones as *time-decaying* (*TD*) modes. Figure 30.3 shows the dispersion curves $\beta^r(\omega)$ calculated numerically for the SD modes, SD_{nm}, with $n = 0$–3 and represented in dimensionless variables. It has been assumed that $\varepsilon_1 = 1$ and $\varepsilon_2 = 2.89$, which correspond to an isolated nanofiber obtained from an isotropic *para*-hexaphenyl material immersed in vacuum. The dispersion curves for the bound modes are also shown in Figure 30.3. They are disposed between the light lines $\omega = c\beta/\sqrt{\epsilon_1}$ (LL_1) and $\omega = c\beta/\sqrt{\epsilon_2}$ (LL_2), and are denoted as it is accepted in the optical waveguide theory (Snyder and Love, 1983). The dispersion curves for the quantities $\beta^i(\omega)$ are shown in Figure 30.4. Figure 30.5 represents the dispersion relations $\omega^r(\beta)$ for $n = 0$–3 calculated for the TD modes, TD_{nm}. The corresponding imaginary parts, $\omega^i(\beta)$, for the modes that are not strongly decaying are plotted in Figure 30.6. Here, the subscript m numerates the modes with a given n according to the order they approach the axis β^r for the SD-modes or the axis ω^r for the TD-modes. One can observe that some of these modes, both SD and TD, can be considered as a continuation of waveguide modes beyond cutoff, which coincides with the light line LL_1. The imaginary parts of the propagation constants or frequencies for such modes increase with the deviation of the corresponding real parts from cutoff.



FIGURE 30.3 Dispersion curves of the SD modes. Real parts of the mode propagation constants. The modes with very large values of β^i are not shown in the figure. $\varepsilon_1 = 1$, $\varepsilon_2 = 2.89$. (Reprinted from Bordo, V., *J. Phys.: Condens. Matter*, 19, 236220-1, 2007. With permission.)

30.3.3 Calculation of the Scattered Field

When carrying out the integration in Equations 30.48 and 30.49, one can take into account that the functions $\tilde{E}_{i0}(\beta,\omega)$ and $\tilde{H}_{i0}(\beta,\omega)$ in the integrands are essentially different from



FIGURE 30.4 Same as Figure 30.3 but for the imaginary parts of the mode propagation constants. (Reprinted from Bordo, V., *J. Phys.: Condens. Matter*, 19, 236220-1, 2007. With permission.)



FIGURE 30.5 Dispersion curves of the TD modes. Real parts of the mode frequencies. $\varepsilon_1 = 1$, $\varepsilon_2 = 2.89$. (Reprinted from Bordo, V., *J. Phys.: Condens. Matter*, 19, 236220-1, 2007. With permission.)

zero around their maxima at $\beta = \beta_0$ and $\omega = \omega_0$. For typical experimental parameters, the widths of the corresponding peaks, $\Delta\beta \ll 1/a$ and $\Delta\omega \ll c/a$, and the slowly varying functions $A_{\mu n}(\beta, \omega)$, $B_{\mu n}(\beta, \omega)$, $C_{\mu n}(\beta, \omega)$, and $D_{\mu n}(\beta, \omega)$ can be taken off the integral at the point (β_0, ω_0).* The remaining integration leads to the result



FIGURE 30.6 Same as Figure 30.5 but for the imaginary parts of the mode frequencies, which fall into the range $|\omega^i a/(2\pi c)| \le 0.1$. (Reprinted from Bordo, V., *J. Phys.: Condens. Matter*, 19, 236220-1, 2007. With permission.)

$$E_{1\mu}(r,\theta,z,t) = E_{i0}(z,t)\exp(i\beta_0 z - i\omega_0 t) \times \sum_{n=0}^{\infty}\left[A_{\mu n}(r;\beta_0,\omega_0)\sin(n\theta) + B_{\mu n}(r;\beta_0,\omega_0)\cos(n\theta)\right], \tag{30.53}$$

$$H_{1\mu}(r,\theta,z,t) = H_{i0}(z,t)\exp(i\beta_0 z - i\omega_0 t) \times \sum_{n=0}^{\infty}\left[C_{\mu n}(r;\beta_0,\omega_0)\sin(n\theta) + D_{\mu n}(r;\beta_0,\omega_0)\cos(n\theta)\right], \tag{30.54}$$

where $E_{i0}(z, t)$ and $H_{i0}(z, t)$ are the amplitudes of the incident wave electric and magnetic fields, respectively. In other words, under typical experimental conditions, the illumination by a pulsed light beam can be treated as the case of an incident plane monochromatic wave if instead of its amplitudes, E_0 and H_0, one substitutes the pulsed beam envelope functions, $E_{i0}(z, t)$ and $H_{i0}(z, t)$, respectively.

We shall be interested in the intensity of light scattered in the *xy* plane. This quantity is determined by the time-averaged radial component of the Poynting vector

$$S_r = \frac{c}{8\pi}\mathrm{Re}(E_{1\theta}H_{1z}^{\star} - E_{1z}H_{1\theta}^{\star}), \tag{30.55}$$

where the asterisk denotes complex conjugation. The substitution of the field components, as shown in Equations 30.53 and 30.54, into Equation 30.55 gives the intensity of the scattered electromagnetic field at any distance from the nanofiber, i.e., in both near-field and far-field regions. In the far zone where $r \gg \lambda$, the

---

* See Bordo (2007) for detail.

Hankel functions and their derivatives can be replaced by their asymptotical expansions. Then in the leading order one obtains

$$S_r = S_r^{\mathrm{TM}} + S_r^{\mathrm{TE}}, \tag{30.56}$$

where the TM- and TE-polarized components are given by

$$S_r^{\mathrm{TM}}(\theta) = \frac{\omega\epsilon_1}{4\pi^2 q_{10}^2 r}\left|\sum_{n=0}^{\infty}(-i)^n[a_{1n}(\beta_0,\omega_0)\sin(n\theta) + b_{1n}(\beta_0,\omega_0)\cos(n\theta)]\right|^2 \tag{30.57}$$

and

$$S_r^{\mathrm{TE}}(\theta) = \frac{\omega}{4\pi^2 q_{10}^2 r}\left|\sum_{n=0}^{\infty}(-i)^n[c_{1n}(\beta_0,\omega_0)\sin(n\theta) + d_{1n}(\beta_0,\omega_0)\cos(n\theta)]\right|^2, \tag{30.58}$$

respectively. The total intensity scattered in all directions per unit length of the nanofiber is determined by the quantity

$$S_{\mathrm{tot}} \equiv \int_0^{2\pi} S_r(\theta)d\theta = S_{\mathrm{tot}}^{\mathrm{TM}} + S_{\mathrm{tot}}^{\mathrm{TE}} \tag{30.59}$$

with

$$S_{\mathrm{tot}}^{\mathrm{TM}} = \frac{\omega\epsilon_1}{4\pi q_{10}^2 r}\left\{\left|b_{10}(\beta_0,\omega_0)\right|^2 + \sum_{n=1}^{\infty}\left[\left|a_{1n}(\beta_0,\omega_0)\right|^2 + \left|b_{1n}(\beta_0,\omega_0)\right|^2\right]\right\} \tag{30.60}$$

and

$$S_{\mathrm{tot}}^{\mathrm{TE}} = \frac{\omega}{4\pi q_{10}^2 r}\left\{\left|d_{10}(\beta_0,\omega_0)\right|^2 + \sum_{n=1}^{\infty}\left[\left|c_{1n}(\beta_0,\omega_0)\right|^2 + \left|d_{1n}(\beta_0,\omega_0)\right|^2\right]\right\}. \tag{30.61}$$

If in an experiment, one varies either the angle of incidence of the light beam at a fixed frequency, or tunes the light frequency at a fixed angle of incidence, the scattered intensity will also change. In the former case, the intensity (30.56) has maxima at the values $\beta_0 = \beta_{nm}^r$ corresponding to the SD modes. In the latter case, the maxima in intensity occur at $\omega_0 = \omega_{nm}^r$ and correspond to the TD modes. The widths of those peaks are determined by the quantities β_{nm}^i and ω_{nm}^i, respectively.*

30.3.4 Semicylinder on an Ideally Reflecting Surface

The approach developed above can be equally applied to the nanofiber model represented by a circular semicylinder placed on an ideally reflecting plane. When the reflecting plane at $y = 0$ is present, the total electric field in the half-space $y > 0$ can be written as

$$\mathbf{E} = \mathbf{E}_i + \mathbf{E}_i^{\mathrm{ref}} + \mathbf{E}_1 + \mathbf{E}_1^{\mathrm{ref}}, \tag{30.62}$$

where $\mathbf{E}_i^{\mathrm{ref}}$ and $\mathbf{E}_1^{\mathrm{ref}}$ are the electric fields specularly reflected from the plane $y = 0$ originating from the incident wave and the field scattered by the nanofiber, respectively. A similar expression is valid for the magnetic field vector. The condition of an ideally reflecting surface implies that the tangential components of the total electric field at it are equal to zero. This requirement will be fulfilled if to introduce, instead of the reflecting plane, an image semicylinder illuminated by the image of the incident wave below the plane $y = 0$ so that $E_r = E_z = 0$ at both $\theta = 0$ and $\theta = \pi$ (Rao and Barakat, 1994). The same is true for the magnetic field components. The fields scattered by the image semicylinder, $\mathbf{E}_1^{\mathrm{im}}$ and $\mathbf{H}_1^{\mathrm{im}}$, are determined by Equations 30.34 through 30.47 with the substitutions

$$a_{1n}^{\mathrm{im}} = -a_{1n}, \quad b_{1n}^{\mathrm{im}} = -b_{1n}, \quad c_{1n}^{\mathrm{im}} = -c_{1n}, \quad d_{1n}^{\mathrm{im}} = -d_{1n}. \tag{30.63}$$

Then the components of the field scattered by the semicylinder in the presence of the reflecting plane are found as $\mathbf{E}_1(\theta) + \mathbf{E}_1^{\mathrm{im}}(-\theta)$ and $\mathbf{H}_1(\theta) + \mathbf{H}_1^{\mathrm{im}}(-\theta)$. Formally, the field components can be obtained from Equations 30.53 and 30.54 with the following substitutions:

$$A_{\mu n} \to 2A_{\mu n}, \quad B_{\mu n} \to 0, \quad C_{\mu n} \to 2C_{\mu n}, \quad D_{\mu n} \to 0. \tag{30.64}$$

Let us assume that the angle of incidence, α, differs from zero. Then the fields $\mathbf{E}_i^{\mathrm{ref}}$ and $\mathbf{H}_i^{\mathrm{ref}}$ do not contribute to the scattered intensity determined by S_r. In the far zone, its TM- and TE-polarized components are given by

$$S_r^{\mathrm{TM}}(\theta) = \frac{\omega\epsilon_1}{\pi^2 q_{10}^2 r}\left|\sum_{n=1}^{\infty}(-i)^n a_{1n}(\beta_0,\omega_0)\sin(n\theta)\right|^2 \tag{30.65}$$

and

$$S_r^{\mathrm{TE}}(\theta) = \frac{\omega}{\pi^2 q_{10}^2 r}\left|\sum_{n=1}^{\infty}(-i)^n c_{1n}(\beta_0,\omega_0)\sin(n\theta)\right|^2, \tag{30.66}$$

respectively. The corresponding total intensity scattered in all directions per unit length of the nanofiber is determined by the quantity

$$S_{\mathrm{tot}} = \int_0^{\pi} S_r(\theta)d\theta = \frac{\omega}{2\pi q_{10}^2 r}\sum_{n=1}^{\infty}\left[\epsilon_1\left|a_{1n}(\beta_0,\omega_0)\right|^2 + \left|c_{1n}(\beta_0,\omega_0)\right|^2\right]. \tag{30.67}$$

---

* Besides the maxima relatively the light frequency discussed here, there may also be maxima originating from resonances in $\varepsilon_2(\omega)$.

Note that here the sum over the modes starts from $n = 1$, indicating that the modes with $n = 0$ are not excited in the course of light scattering. The suppression of such modes is conditioned by the presence of the reflecting plane.

Let us consider the special case of normal incidence with respect to the substrate surface ($\alpha = 0$). In such a case, $\beta_0 = 0$ and the equations for TM and TE polarizations are completely separated. This means that for TM incident wave polarization, one can set $c_{1n} = d_{1n} = 0$. Besides that, the vector $\vec{F}_n$, Equation 30.23, is nonzero only for odd indices n. Then the coefficients a_{1n} are nonzero for odd n and only such modes can be observed in scattering. For TE incident wave polarization, $a_{1n} = b_{1n} = 0$ and the vector $\vec{G}_n$, Equation 30.26, is nonzero for odd n. As a result, one obtains the same selection rule as for TM polarization.

30.4 Some Numerical Results

We shall illustrate the general theory considered above with some numerical examples. All the calculations have been carried out for $\varepsilon_2 = 2.89$ that corresponds to an isotropic *para*-hexaphenyl film. We shall compare the results obtained for two different models of a nanofiber.

30.4.1 Angular Distribution of Scattered Light

Let us consider first the dependence of the Poynting vector component S_r, Equation 30.55, calculated in the far zone on the detection angle, θ. This quantity is determined by the coefficients a_{1n}, b_{1n}, c_{1n}, and d_{1n}, as shown in Equations 30.30 through 30.33. Their variation with the nanofiber radius, a, is more rapid for larger values of $q_{10} = (\omega_0/c)\sqrt{\epsilon_1}\cos\alpha$ and hence for smaller angles of incidence, α. Figures 30.7 and 30.8 show the angular distributions of light scattered by a cylindrical nanofiber for the TM and TE incident light polarizations, respectively, and for $\alpha = 45°$. One can see that in the case of the TM incident wave polarization, there are two lobes directed along the normal to the plane of incidence (at $\theta = 0°$ and $\theta = 180°$). For relatively large nanofiber radius, additional two lobes appear. In the case of the TE incident wave polarization, these lobes are more pronounced. Besides that, for small nanofiber radius, the angular distribution of scattered light is more isotropic as compared to the TM polarization.



FIGURE 30.7 Angular distribution of light scattered from a cylindrical nanofiber of different radii. TM incident wave polarization. $\alpha = 45°$, $\varepsilon_1 = 1$, $\varepsilon_2 = 2.89$. All curves are normalized to their maximum values.



FIGURE 30.8 Same as Figure 30.7 but for TE incident wave polarization.



FIGURE 30.9 Same as Figure 30.7 but for a semicylindrical nanofiber on a perfectly reflecting surface.

The same quantity but calculated for a semicylindrical nanofiber placed on a perfectly reflecting substrate and for the TM incident wave polarization is depicted in Figure 30.9. The scattering diagram for the TE incident wave polarization has a similar form. In this case, the lobes directed along the substrate plane are suppressed and light is scattered mainly around the plane of incidence.

30.4.2 Total Scattered Intensity versus Incidence Angle

Let us consider the total scattered intensity, S_{tot}, as a function of the incidence angle, α, or, equivalently, the quantity $\beta_0 = (\omega_0/c)\sqrt{\epsilon_1}\sin\alpha$. Figure 30.10 shows this dependence calculated for a cylinder and for the TM incident wave polarization with an account of the terms $n = 0$–10 in Equations 30.60 and 30.61. The individual contributions from the terms with $n = 0$, 1, and 2 are also shown in Figure 30.10, whereas the other contributions have much smaller amplitude. The intensity drop at $\beta_0 a \approx 2.2$ originates from the approach to the cutoff at which $q_{10} = 0$. The curve corresponding to $n = 2$ exhibits a shoulder around $\beta_0 a \approx 1.75$, which is also seen in the total intensity curve. Turning to Figure 30.3, one can identify it as being originating from the mode SD_{21}. The contributions of the other modes are not pronounced because of the large values of the propagation constant imaginary parts, β^i, corresponding to them. This plot can be compared with Figure 30.11, which represents the results of calculations for a semicylindrical nanofiber placed on an ideally reflecting surface. In this case, the zeroth term does not contribute to S_{tot} and the contribution of the term with $n = 2$ is equal



FIGURE 30.10 Light intensity scattered from a cylindrical nanofiber as a function of β_0 calculated for $\varepsilon_1 = 1$, $\varepsilon_2 = 2.89$, and $\omega_0 a/(2\pi c) = 0.35$. TM incident wave polarization.



FIGURE 30.11 Same as Figure 30.10 but for a semicylindrical nanofiber on a perfectly reflecting surface.

to zero at $\beta_0 = 0$ (normal incidence) in accordance with the selection rule discussed in Section 30.3.4. As a result, the shoulder in the total intensity originating from the mode SD_{21} becomes more distinct.

30.4.3 Total Scattered Intensity versus Frequency

Another situation when the light beam frequency is scanned at a fixed angle of incidence ($\alpha = 0$) is illustrated in Figure 30.12 for the case of scattering of a TM-polarized beam by a cylindrical nanofiber. This time the features in the total scattered intensity originate from the TD modes. They can be identified when comparing the positions of maxima, which occur for the curves with different n with the mode frequencies at $\beta_0 = 0$ in Figure 30.5.



FIGURE 30.12 Light intensity scattered from a cylindrical nanofiber as a function of ω_0 calculated for $\varepsilon_1 = 1$, $\varepsilon_2 = 2.89$. Normal incidence. TM incident wave polarization.



FIGURE 30.13 Same as Figure 30.12 but for a semicylindrical nanofiber on a perfectly reflecting surface. (Reprinted from Bordo, V., *J. Phys.: Condens. Matter*, 19, 236220-1, 2007. With permission.)

In the case of a semicylinder placed on an ideally reflecting plane (Figure 30.13), only modes with odd n can be excited, as it is expected from the selection rule (see Section 30.3.4). It is worthwhile to note that the modes distinct from those for TM polarization can be observed in the scattering of a TE-polarized light beam (not shown).

30.4.4 Excitation near Exciton Resonance

So far we have implied that the frequency of the incident beam is far from any resonance in the dielectric function of the nanofiber and its frequency dispersion can be neglected. Let us assume



FIGURE 30.14 Angular distribution of scattered light in the vicinity of the exciton resonance. TM incident wave polarization. $\varepsilon_1 = 1$, $\varepsilon_\infty = 2.89$, $a = 4c/\omega_T$, $\omega_L = 1.2\omega_T$, $\Gamma = 10^{-3}\omega_T$, and $\alpha = 30°$.

now that the frequency ω_0 is close to an exciton resonance of the nanofiber. Then its dielectric function can be written as follows:

$$\epsilon_2(\omega) = \frac{\omega_L^2 - \omega^2}{\omega_T^2 - \omega^2 + i\omega\Gamma}\epsilon_\infty, \qquad (30.68)$$

where

ω_T and ω_L are the frequencies of the transverse and longitudinal excitons, respectively
Γ is the relaxation constant
ε_∞ is the high-frequency dielectric constant, and the spatial dispersion has been neglected

Figure 30.14 shows the angular distribution of the scattered light in this case calculated for a semicylindrical nanofiber on an ideally reflecting surface. It is seen that the polar diagram of scattering changes dramatically in a narrow spectral interval when the frequency of the incident beam scans across the exciton resonance.

30.5 Experimental Implementation

Experimentally, one can observe light scattering from nanofibers in the following setup (Figure 30.15) (Fiutowski et al., 2008). A sample with deposited organic nanofibers is attached to a half-sphere made of fused silica ($n_s = 1.48$ at 325 nm) with a radius of 10 mm. The sample is oriented so that the nanofiber axes would be parallel to the plane of light incidence. A flat domain of parallelly oriented organic nanofibers is illuminated with a linearly polarized beam of a He-Cd laser ($\lambda = 325$ nm) from the half-sphere side, and the scattered light intensity is detected along the normal to the sample surface from the backside. The extinction ratio of the polarization system is 10^5. The light beam passes a pinhole of diameter 400 μm and is collimated before entering the half-sphere, which results in a beam divergence of less than 0.7° after leaving the half-sphere. The angles of incidence can be varied between 20° and 65° with respect to the normal axis of the plane of the half-sphere. A photomultiplier mounted on a goniometric table allows one to detect scattered light intensity distributions from a spot on the sample of a diameter of about 500 μm. The acceptance angle of the detection system is 44°. The absolute and relative accuracies of the incident and the detection angles are 1° and 0.5°, respectively. To observe only the wavelengths of interest, one can use band pass or interferometric filters in front of the photomultiplier.



FIGURE 30.15 Experimental setup. HWP, half-wave plate; P, polarizer; Ph, pinhole; MO, microscope objective; F, filter; and PMT, photomultiplier. Inset: Fluorescence microscopy image of a sample domain. (Reprinted from Fiutowski, J. et al., *Appl. Phys. Lett.*, 92, 073302-1, 2008. With permission.)

The intensity of light scattered perpendicularly to the sample surface as a function of the incidence angle, α, is shown in Figure 30.16. Clear peaks at $\alpha = 40°$ in both TE and TM incident light polarizations are observed. Those peaks originate from the



FIGURE 30.16 Intensity of light scattered perpendicularly to the sample surface as a function of the angle of incidence. The incident wave polarization is indicated in the inset. (Reprinted from Fiutowski, J. et al., *Appl. Phys. Lett.*, 92, 073302-1, 2008. With permission.)

nanofiber array exclusively, as seen from a comparison with the data obtained from a nanofiber-free mica surface. The scattered intensity decreases when the incidence angle exceeds the critical angle for total internal reflection at the quartz semisphere–air interface, $\alpha_c = 42.5°$. To describe the optical properties of a nanofiber grown on a substrate, we use the nanofiber model represented by a semicylinder placed on an ideally reflecting surface and considered above. Figure 30.17 shows the dispersion curves of the nanofiber normal modes plotted in the range of the size parameter, a/λ, corresponding to the experimentally observed typical nanofiber widths ($2a$) as well as the wavelength of the He-Cd laser used for excitation. The condition of the phase matching between the incident light and the nanofiber normal mode can be written as $\beta = (2\pi/\lambda)n_s \sin\alpha$. The corresponding dispersion line for the angle $\alpha = 40°$, at which the resonance in scattering is observed, is also shown in Figure 30.17.

The analysis of the polarization properties of the excited normal modes allows one to specify them. The sharp peak seen in the scattered light intensity at $\alpha = 40°$ has comparable amplitudes in both TE and TM incident wave polarizations. It can therefore be associated with the excitation of the hybrid SD_{12} mode. The increase in intensity at $\alpha < 26°$ originates probably from a resonance with the hybrid SD_{21} mode. The mode SD_{01} is suppressed in scattering due to the presence of the reflecting substrate (see Section 30.3.4).

The positions of the maxima in Figure 30.16 correspond to the most probable size parameter within the illuminated spot. The broadenings of the peaks observed in light scattering allow one to estimate the distribution of the nanofibers in the array over their widths. The angular broadening of about 7° corresponds to a scattering of 0.12λ in nanofiber diameters, which gives approximately 40 nm for the relevant wavelength. This value agrees qualitatively with that measured via atomic force microscope (AFM).



FIGURE 30.17 Dispersion curves of the SD modes plotted in the range of size parameters corresponding to measured nanofiber widths. The inclined dot-and-dash line indicates the dispersion for light incident at the angle $\alpha = 40°$.

30.6 Discussion

We have considered here the simplest theoretical models of nanofibers and applied them for the interpretation of the experimental results on light scattering from an array of organic nanoaggregates deposited on a mica substrate. Although the morphology of nanoaggregates is far from a cylindrical shape, light scattering from them can be similarly described in terms of excitation of their radiative normal modes. This conclusion is also supported by the measurements of photoluminescence excited in the course of light scattering (Fiutowski et al., 2008). In that case, the peaks in the photoluminescence intensity versus the angle of incidence originate from matching with the nanoaggregates' normal modes, both radiative and waveguiding. Such measurements being carried out at a varying frequency of incident light should allow one to determine the dispersion curves of the actual normal modes of nanoaggregates. Then, using an appropriate model, one could extract information on the morphology of nanofibers. However, it is necessary to keep in mind that the actual normal modes may differ from those of an isotropic cylindrical nanofiber. In particular, the optical anisotropy of nanoaggregates can cause distortion of the dispersion curves as well as their splitting.

Another point which has to be taken into account is the different morphology of nanoaggregates within the illuminated spot. As we have already mentioned, this leads to a broadening of the peaks in the intensity of scattered light. On the other hand, the data obtained from the scattering of a focused light beam reflect the local morphology of a sample and, thus, can be used for its local characterization.

30.7 Summary and Outlook

In this chapter, we have considered the theory which describes the scattering of a pulsed Gaussian light beam at an infinitely long dielectric cylinder. The results obtained for this model have been generalized to the model represented by a semicylinder placed on a perfectly reflecting plane. Although being rather simple, these approaches reproduce the main features of light scattering from nanofibers. In particular, this process can be understood in terms of the excitation of nanofiber radiative modes. As a result, the dependence of the scattered light intensity on the angle of incidence exhibits maxima corresponding to matching with the nanofiber SD modes.

These conclusions are in agreement with the measurements of light scattering from organic nanoaggregates grown on mica, which have demonstrated experimental evidence of mode launching in this system. Those modes show up as pronounced peaks in light scattering from the nanofibers. Using the model, one is able to identify specific modes that have been excited in the course of light scattering from the sample. The obtained results provide detailed information about possible electromagnetic mode propagation in nanosized, needle-shaped aggregates and also form the basis for a new way of optically characterizing the morphology of sub-wavelength-sized nanostructures via far-field scattering. The further development of this technique by using a tunable light source should allow one to determine the actual dispersion curves of nanofibers. On the other hand, one can use a broadband light source to illuminate the sample instead of a laser. In such a case, one should expect to observe peaks in the spectrum of scattered light, which originates from the excitation of TD nanofiber modes. The implementation of this technique with the use of a scanning near-field optical microscope for the registration of scattered field would provide an additional advantage. The data obtained in such a setup are not influenced by an averaging over the illuminated spot and, thus, are related to individual nanofibers. Another possible application of light scattering from nanofibers stems from correlation between the positions of peaks in scattered intensity and the dispersion of nanofiber normal modes. Any change in the optical properties of nanofibers caused by either heating, or mechanical tension, or adsorption of molecules from ambient medium would result in a shift of the peaks in light scattering. This opens up new opportunities for the creation of nanosensors of various kinds. Due to its generic nature, the method discussed in this chapter is not limited to organic nanofibers but can be equally well applied to other kind of light-emitting nanoaggregates.

Acknowledgments

The author is grateful to Prof. H.-G. Rubahn and Dr. L. Jozefowski for the discussions of the experimental aspects of light scattering from nanofibers.

References

Agarwal, R., Barrelet, C., and Lieber, C. (2005). Lasing in single cadmium sulfide nanowire optical cavity. *Nano Lett.*, 5:917–920.

Ashkin, A., Dziedzic, J., and Stolen, R. (1981). Outer diameter measurement of low birefringence optical fibers by a new resonant backscatter technique. *Appl. Opt.*, 20:2299–2303.

Balzer, F., Bordo, V., Simonsen, A., and Rubahn, H.-G. (2003). Optical waveguiding in individual nanometer-scale organic fibers. *Phys. Rev. B*, 67:115408–1–8.

Balzer, F. and Rubahn, H.-G. (2001). Dipole-assisted self-assembly of light-emitting *p*-nP needles on mica. *Appl. Phys. Lett.*, 79:3860–3862.

Balzer, F. and Rubahn, H.-G. (2005). Growth control and optics of organic nanoaggregates. *Adv. Funct. Mater.*, 15:17–24.

Barrelet, C., Greytak, A., and Lieber, C. (2004). Nanowire photonic circuit elements. *Nano Lett.*, 4:1981–1985.

Bever, S. and Allebach, J. (1992). Multiple scattering by a planar array of parallel dielectric cylinders. *Appl. Opt.*, 31:3524–3532.

Birkhoff, R., Ashley, J., Hubbel, H. Jr., and Emerson, L. (1977). Light scattering from micron-size fibers. *J. Opt. Soc. Am.*, 67:564–569.

Bordo, V. (2006). Light scattering from a nanofiber: Exact numerical solution of a model system. *Phys. Rev. B*, 73:205117-1–205117-7.

Bordo, V. (2007). Theory of nanofibre excitation by a pulsed light beam. *J. Phys. Condens. Matter*, 19:236220-1–236220-12.

Borghi, R., Santarsiero, M., Frezza, F., and Schettini, G. (1997). Plane-wave scattering by a dielectric circular cylinder parallel to a general reflecting flat surface. *J. Opt. Soc. Am. A*, 14:1500–1504.

Brewer, J., Maibohm, C., Jozefowski, L., Bagatolli, L., and Rubahn, H.-G. (2005). A 3D view on free-floating, space-fixed and surface-bound *para*-phenylene nanofibers. *Nanotechnology*, 16:2396–2401.

Chin, A., Vaddiraju, S., Maslov, A., Ning, C., Sunkara, M., and Meyyappan, M. (2006). Near-infrared semiconductor subwavelength-wire lasers. *Appl. Phys. Lett.*, 88:163115-1–163115-3.

Cohen, L., Haracz, R., Cohen, A., and Acquista, C. (1983). Scattering of light from arbitrary oriented finite cylinders. *Appl. Opt.*, 22:742–748.

Duan, X., Huang, Y., Agarwal, R., and Lieber, C. (2003). Single-nanowire electrically driven lasers. *Nature*, 421:241–245.

Duan, X., Huang, Y., Cui, Y., Wang, J., and Lieber, C. (2001). Indium phosphide nanowires as building blocks for nanoscale electronic and optoelectronic devices. *Nature*, 409:66–69.

Fiutowski, J., Bordo, V., Jozefowski, L., Madsen, M., and Rubahn, H.-G. (2008). Light scattering from an ordered array of needle-shaped organic nanoaggregates: Evidence for optical mode launching. *Appl. Phys. Lett.*, 92:073302-1–073302-3.

Haracz, R., Cohen, L., and Cohen, A. (1984). Perturbation-theory for scattering from dielectric spheroids and short cylinders. *Appl. Opt.*, 23:436–441.

Huang, M., Mao, S., Feick, H. et al. (2001). Room-temperature ultraviolet nanowire nanolasers. *Science*, 292:1897–1899.

Johnson, J., Choi, H.-J., Knutsen, K., Schaller, R., Yang, P., and Saykally, R. (2002). Single gallium nitride nanowire lasers. *Nat. Mater.*, 1:106–110.

Johnson, J., Yan, H., Yang, P., and Saykally, R. (2003). Optical cavity effects in ZnO nanowire lasers and waveguides. *J. Phys. Chem.*, 107:8816–8828.

Kerker, M. (1969). *The Scattering of Light and Other Electromagnetic Radiation*. Academic Press, New York.

Kuik, F., de Haan, J., and Hovenier, J. (1994). Single scattering of light by circular cylinders. *Appl. Opt.*, 33:4906–4918.

Lord Rayleigh (1881). On the electromagnetic theory of light. *Philos. Mag.*, 12:81–101.

Owen, J., Barber, P., Messinger, B., and Chang, R. (1981). Determination of optical-fiber diameter from resonances in the elastic scattering spectrum. *Opt. Lett.*, 6:272–274.

Quochi, F., Cordella, F., Mura, A., Bongiovanni, G., Balzer, F., and Rubahn, H.-G. (2005). One-dimensional random lasing in a single organic nanofiber. *J. Phys. Chem. B*, 109:21690–21693.

Quochi, F., Cordella, F., Mura, A., Bongiovanni, G., Balzer, F., and Rubahn, H.-G. (2006). Gain amplification and lasing properties of individual organic nanofibers. *Appl. Phys. Lett.*, 88:041106-1–041106-3.

Rao, T. and Barakat, R. (1994). Near-field scattering by a conducting cylinder partially buried in a conducting plane. *Opt. Commun.*, 111:18–25.

Ruppin, R. (1990). Electromagnetic scattering from finite dielectric cylinders. *J. Phys. D Appl. Phys.*, 23:757–763.

Schiek, M., Lützen, A., Koch, R. et al. (2005). Nanofibers from functionalized para-phenylene molecules. *Appl. Phys. Lett.*, 86:153107-1–153107-3.

Shepherd, J. and Holt, A. (1983). The scattering of electromagnetic radiation from finite dielectric circular cylinders. *J. Phys. A Math. Gen.*, 16:651–662.

Snyder, A. and Love, J. (1983). *Optical Waveguide Theory*. Chapman and Hall, London, U.K.

Stratton, J. (1941). *Electromagnetic Theory*. McGraw-Hill, New York.

Thilsing-Hansen, K., Neves-Petersen, M., Petersen, S., Neuendorf, R., Al-Shamery, K., and Rubahn, H.-G. (2005). Luminescence decay of oriented phenylene nanofibers. *Phys. Rev. B*, 72:115213-1–115213-7.

Tong, L., Gattass, R., Ashcom, J. et al. (2003). Subwavelength-diameter silica wires for low-loss optical wave guiding. *Nature*, 426:816–819.

Twersky, V. (1952). Multiple scattering of radiation by an arbitrary planar configuration of parallel cylinders. *J. Acoust. Soc. Am.*, 24:42–46.

Uzunoglu, N., Alexopoulos, N., and Fikioris, J. (1978). Scattering from thin and finite dielectric fibers. *J. Opt. Soc. Am.*, 68:194–197.

Van Bladel, J. (1977). Resonant scattering by dielectric cylinders. *IEEE J. Microwave Opt. Acoust.*, 1:41–50.

Wait, J. (1955). Scattering of a plane wave from a circular dielectric cylinder at oblique incidence. *Can. J. Phys.*, 33:189–195.

Wang, J., Gudiksen, M., Duan, X., Cui, Y., and Lieber, C. (2001). Highly polarized photoluminescence and photodetection from single indium phosphide nanowires. *Science*, 293:1455–1457.

Zimmler, M., Bao, J., Capasso, F., Müller, S., and Ronning, C. (2008). Laser action in nanowires: Observation of the transition from amplified spontaneous emission to laser oscillation. *Appl. Phys. Lett.*, 93:051101-1–051101-3.

31

Biomimetics: Photonic Nanostructures

Andrew R. Parker
The Natural History Museum

31.1 Introduction **31**-1
31.2 Engineering of Antireflectors **31**-1
31.3 Engineering of Iridescent Devices **31**-1
31.4 Cell Culture **31**-3
31.5 Diatoms and Coccolithophores **31**-5
31.6 Iridoviruses **31**-7
31.7 The Mechanisms of Natural Engineering and Future Research **31**-7
Acknowledgments **31**-8
References **31**-8

31.1 Introduction

Three centuries of research, beginning with Hooke and Newton, have revealed a diversity of optical devices at the nanoscale (or at least the submicron scale) in nature.[1] These include structures that cause random scattering, 2D diffraction gratings, 1D multilayer reflectors, and 3D liquid crystals (Figure 31.1a through d). In 2001, the first photonic crystal was identified as such in animals,[2] and since then the scientific effort in this subject has accelerated. Now we know of a variety of 2D- and 3D-photonic crystals in nature (e.g., Figure 31.1e and f), including some designs not encountered previously in physics.

Biomimetics is the extraction of good design from nature. Some optical biomimetic successes have resulted from the use of conventional (and constantly advancing) engineering methods to make direct analogues of the reflectors and antireflectors found in nature. However, recent collaborations between biologists, physicists, engineers, chemists, and material scientists have ventured beyond merely mimicking in the laboratory what happens in nature, leading to a thriving new area of research involving biomimetics via cell culture. Here, the nano-engineering efficiency of living cells is harnessed, and nanostructures such as diatom "shells" can be made for commercial applications via culturing the cells themselves.

31.2 Engineering of Antireflectors

Some insects benefit from antireflective surfaces, either on their eyes to see under low-light conditions, or on their wings to reduce surface reflections in transparent (camouflaged) areas. Antireflective surfaces, therefore, occur on the corneas of moth and butterfly eyes[3] and on the transparent wings of hawkmoths.[4] These consist of nodules, with rounded tips, arranged in a hexagonal array with a periodicity of around 240 nm (Figure 31.2b). Effectively they introduce a gradual refractive index profile at an interface between chitin (a polysaccharide, often embedded in a proteinaceous matrix; r.i. 1.54) and air, and hence reduce reflectivity by a factor of 10.

This "moth-eye structure" was first reproduced at its correct scale by crossing three gratings at 120° using lithographic techniques, and employed as antireflective surfaces on glass windows in Scandinavia.[5] Here, plastic sheets bearing the antireflector were attached to each interior surface of triple-glazed windows using refractive-index-matching glue to provide a significant difference in reflectivity. Today the moth-eye structure can be made extremely accurately using e-beam etching,[6] and is employed commercially on solid plastic and other lenses.

A different form of antireflective device, in the form of a sinusoidal grating of 250 nm periodicity, was discovered on the cornea of a 45-million-year-old fly preserved in amber[7] (Figure 31.2a). This is particularly useful where light is incident at a range of angles (within a single plane, perpendicular to the grating grooves), as demonstrated by a model made in photoresist using lithographic methods.[7] Consequently it has been employed on the surfaces of solar panels, providing a 10% increase in energy capture through reducing the reflected portion of sunlight.[8] Again, this device is embossed onto plastic sheets using holographic techniques.

31.3 Engineering of Iridescent Devices

Many birds, insects (particularly butterflies and beetles), fishes, and lesser-known marine animals display iridescent (changing color with angle) and/or "metallic" colored effects resulting from



FIGURE 31.1 Summary of the main types of optical reflectors found in nature; a–d where a light ray is (generally) reflected only once within the system (i.e., they adhere to the single scattering, or first Born, approximation), and e and f where each light ray is (generally) reflected multiple times within the system. (a) An irregular array of elements that scatter incident light into random directions. The scattered (or reflected) rays do not superimpose. (b) A diffraction grating, a surface structure, from where light is diffracted into a spectrum or multiple spectra. Each corrugation is about 500 nm wide. Diffracted rays superimpose either constructively or destructively. (c) A multilayer reflector, composed of thin (ca. 100 nm thick) layers of alternating refractive index, where light rays reflected from each interface in the system superimpose either constructively or destructively. Some degree of refraction occurs. (d) A "liquid crystal" composed of nano-fibers arranged in layers, where the nano-fibers of one layer lie parallel to each other yet are orientated slightly differently to those of adjacent layers. Hence spiral patterns can be distinguished within the structure. The height of the section shown here—one "period" of the system—is around 200 nm. (e) Scanning electron micrograph of the "opal" structure—a close-packed array of submicron spheres (a "3D photonic crystal")—found within a single scale of the weevil *Metapocyrtus* sp.; scale bar = 1 μm. (f) Transmission electron micrograph of a section through a hair (neuroseta) of the sea mouse *Aphrodita* sp. (Polychaeta), showing a cross section through a stack of submicron tubes (a "2D photonic crystal"); scale bar = 5 μm.

photonic nanostructures. These appear comparatively brighter than the effects of pigments and often function in animals to attract the attention of a potential mate or to startle a predator. An obvious application for such visually attractive and optically sophisticated devices is within the anticounterfeiting industry. For secrecy reasons, work in this area cannot be described, although devices are sought at different levels of sophistication, from effects that are discernable by the eye to fine-scale optical characteristics (polarization and angular properties, for example) that can be read only by specialized detectors. However, new research aims to exploit these devices in the cosmetics, paint, printing/ink, and clothing industries. They are even being tested in art to provide a sophisticated color-change effect.

Original work on exploiting nature's reflectors involved copying the design but not the size, where reflectors were scaled up to target longer wavelengths. For example, rapid prototyping was employed to manufacture a microwave analogue of a *Morpho* butterfly scale that is suitable for reflection in the 10–30 GHz region. Here the layer thicknesses would be in the order of 1 mm rather than 100 nm as in the butterfly, but the device could be employed as an antenna with broad radiation characteristics, or as an antireflection coating for radar. However, today techniques are available to manufacture nature's reflectors at their true size.

Nanostructures causing iridescence include photonic crystal fibers, opal and inverse opal, and unusually sculpted 3D architectures. Photonic crystals are ordered, often complex, sub-wavelength (nano) lattices that can control the propagation of light at the single-wave scale in the manner that atomic crystals control electrons.[9] Examples include opal (a hexagonal or square array of 250 nm spheres) and inverse opal (a hexagonal array of similar-sized holes in a solid matrix). Hummingbird feather barbs contain variation ultrathin layers with variations in porosity that cause their iridescent effects, due to the alternating nanoporous/fully dense ultrastructure.[10] Such layers have been mimicked using aqueous-based layering techniques.[10] The greatest diversity of 3D architectures can be found in butterfly scales, which can include micro-ribs with nano-ridges, concave multilayered pits, blazed gratings, and randomly punctate nano-layers.[11,12] The cuticle of many beetles contain



FIGURE 31.2 Scanning electron micrographs of antireflective surfaces. (a) Fly-eye antireflector (ridges on four facets) on a 45-million-year-old dolichopodid fly's eye. (Micrograph from Mierzejewski, P. With permission.) (b) Moth-eye antireflective surfaces. (c) Moth-eye mimic fabricated using ion-beam etching. Scale bars = 3 µm (a), 1 µm (b), 2 µm (c). (Micrograph by Boden, S.A. and Bagnall, D.M., Biomimetic subwavelength surfaces for near-zero reflection sunrise to sunset, *Proceedings 4th World Conference on Photovoltaic Energy, Conversion*, Waikoloa, HI, 2006. With permission.)

structurally chiral films that produce iridescent effects with circular or elliptical polarization properties.[13] These have been replicated in titania for specialized coatings,[13] where a mimetic sample can be compared with the model beetle and an accurate variation in spectra with angle is observed (Figure 31.3). The titania mimic can be nanoengineered for a wide range of resonant wavelengths; the lowest so far is a pitch of 60 nm for a circular Bragg resonance at 220 nm in a Sc_2O_3 film (Ian Hodgkinson, pers. com.).

Biomimetic work on the photonic crystal fibers of the *Aphrodita* sea mouse is underway. The sea mouse contains spines (tubes) with walls packed with smaller tubes of 500 nm, with varying internal diameters (50–400 nm). These provide a bandgap in the red region, and are to be manufactured via an extrusion technique. Larger glass tubes packed together in the proportion of the spine's nanotubes will be heated and pulled through a drawing tower until they reach the correct dimensions. The sea mouse fibre mimics will be tested for standard PCF applications (e.g., in telecommunications) but also for anticounterfeiting structures readable by a detector.

The analogues of the famous blue *Morpho* butterfly (Figure 31.4a) scales have been manufactured.[14,15] Originally, corners were cut. Where the *Morpho* wing contained two layers of scales—one to generate color (a quarter-wave stack) and another above it to scatter the light—the model copied only the principle.[14] The substrate was roughened at the nanoscale, and coated with 80 nm thick layers alternating in refractive index.[14] Therefore the device retained a quarter-wave stack centered in the blue region, but incorporated a degree of randomness to generate scattering. The engineered device closely matched the butterfly wing—the color observed changed only slightly with changing angle over 180°, an effect difficult to achieve and useful for a broad-angle optical filter without dyes.

A new approach to making the 2D "Christmas tree" structure (a vertical, elongated ridge with several layers of 70 nm thick side branches; Figure 31.4b) has been achieved using focused-ion-beam chemical-vapor deposition (FIB-CVD).[15] By combining the lateral growth mode with ion-beam scanning, the Christmas tree structures were made accurately (Figure 31.4c). However, this method is not ideal for low-cost mass production of 2D and 3D nanostructures, and therefore the ion-beam-etched Christmas trees are currently limited to high-cost items including nano- or micron-sized filters (such as "pixels" in a display screen or a filter). Recently further corners have been cut in manufacturing the complex nanostructures found in many butterfly scales, involving the replication of the scales in ZnO, using the scales themselves as templates[16] (Figure 31.4d and e).

31.4 Cell Culture

Sometimes nature's optical nanostructures have such an elaborate architecture at such a small (nano) scale that we simply cannot copy them using current engineering techniques. Additionally, sometimes they can be made as individual reflectors (as for the *Morpho* structure), but the effort is so great that commercial-scale manufacture would never be cost-effective.

An alternative approach to making nature's reflectors is to exploit an aspect other than design—that the animals or plants can make them efficiently. Therefore we can let nature manufacture the devices for us via cell-culture techniques. Animal cells are in the order of 10 µm in size and plant cells up to about 100 µm, and hence suitable for nanostructure production. The success of cell culture depends on the species and on type of cell from that species. Insect cells, for instance, can be cultured at room temperature, whereas an incubator is required for mammalian cells. Cell culture is not a straightforward method, however, since a culture medium must be established to which the cells adhere, before they can be induced to develop to the stage where they make their photonic devices.

The current work in this area centres on butterfly scales. The cells that make the scales are identified in chrysalises, dissected, and plated out. Then the individual cells are separated, kept alive in culture, and prompted to manufacture scales through the addition of growth hormones. Currently we have cultured blue *Morpho* butterfly scales in the lab that have identical optical and structural characteristics to natural scales. The cultured scales



FIGURE 31.3 (a) A Manuka (scarab) beetle with (b) titania mimetic films of slightly different pitches. (c) Scanning electron micrograph of the chiral reflector in the beetle's cuticle. (d) Scanning electron micrograph of the titania mimetic film. (Reproduced from DeSilva, L. et al., *Electromagnetics*, 25, 391, 2005. With permission.)



FIGURE 31.4 (a) A *Morpho* butterfly with (b) a scanning electron micrograph of the structure causing the blue reflector in its scales. (c) A scanning electron micrograph of the FIB-CVD-fabricated mimic. A Ga$^+$ ion beam (beam diameter 7 nm at 0.4 pA; 30 kV), held perpendicular to the surface, was used to etch a precursor of phenanthrene ($C_{14}H_{10}$). Both give a wavelength peak at around 440 nm and at the same angle (30°). (From Watanabe, K. et al., *Jpn. J. Appl. Phys.*, 44, L48, 2005. With permission.) (d) Scanning electron micrograph of the base of a scale of the butterfly *Ideopsis similes*. (e) Scanning electron micrograph of a ZnO replica of the same part of the scale in (d). (Reproduced from Zhang, W. et al., *Bioinspir. Biomim.*, 1, 89, 2006. With permission.)

could be embedded in a polymer or mixed into a paint, where they may float to the surface and self-align. Further work, however, is required to increase the level of scale production and to harvest the scales from laboratory equipment in appropriate ways. A far simpler task emerges where the iridescent organism is single-celled.

31.5 Diatoms and Coccolithophores

Diatoms are unicellular photosynthetic microorganisms. The cell wall is called the frustule and is made of the polysaccharide pectin impregnated with silica. The frustule contains pores (Figure 31.5a through c) and slits that give the protoplasm access to the external environment. There are more than 100,000 different of species of diatoms, generally 20–200 μm in diameter or length, but some can be up to 2 mm long. Diatoms have been proposed to build photonic devices directly in 3D.[17] The biological function of the optical property (Figure 31.5d) is at present unknown, but may affect light collection by the diatom. This type of photonic device can be made in silicon using a deep photochemical-etching technique (initially developed by Lehmann[18]) (e.g., Figure 31.5e). However, there is a new potential here since diatoms carry the added advantage of exponential growth in numbers—each individual can give rise to 100 million descendents in a month.

Unlike most manufacturing processes, diatoms achieve a high degree of complexity and hierarchical structure under mild physiological conditions. Importantly, the size of the pores does not scale with the size of the cell, thus maintaining the pattern. Fuhrmann et al.[17] showed that the presence of these pores in the silica cell wall of the diatom *Coscinodiscus granii* means that the frustule can be regarded as a photonic crystal slab waveguide. Furthermore, they present models to show that light may be coupled into the waveguide and give photonic resonances in the visible spectral range.

The silica surface of the diatom is amenable to simple chemical functionalization (e.g., Figure 31.6a through c). An interesting example of this uses a DNA-modified diatom template for the control of nanoparticle assembly.[19] Gold particles were coated with DNA complementary to that bound to the surface of the diatom. Subsequently, the gold particles were bound to the diatom surface *via* the sequence-specific DNA interaction. Using this method up to seven layers were added showing how a hierarchical structure could be built onto the template.

Porous silicon is known to luminesce in the visible region of the spectrum when irradiated with ultraviolet light.[20] This photoluminescence (PL) emission from the silica skeleton of diatoms was exploited by DeStafano[21] in the production of an optical gas sensor. It was shown that the PL of *Thalassiosira rotula* is strongly dependent on the surrounding environment. Both the optical intensity and peaks are affected by gases and organic vapors. Depending on the electronegativity and polarizing ability, some substances quench the luminescence, while others effectively enhance it. In the presence of the gaseous substances NO_2, acetone, and ethanol, the photoluminescence was quenched. This was because these substances attract electrons from the silica skeleton of the diatoms and hence quench the PL.



FIGURE 31.5 (a–c) Scanning electron micrographs of the intercalary band of the frustule from two species of diatoms, showing the square array of pores from *C. granii* ((a) and (b)) and the hexagonal arrays of pores from *C. wailesii* (c). These periodic arrays are proposed to act as photonic crystal waveguides. (d) Iridescence of the *C. granii* girdle bands. (e) Southampton University mimic of a diatom frustule (patented for photonic crystal applications); scanning electron micrograph. (Micrograph by Parker, G. With permission.)



FIGURE 31.6 Modification of natural photonic devices. (a)–(c) Diatom surface modification. The surface of the diatom was silanized, then treated with a heterobifunctional cross-linker, followed by attachment of an antibody via a primary amine group. (a) (i) Diatom exterior surface (ii) APS (iii) ANB-NOS (iv) primary antibody (v) secondary antibody with HRP conjugate. Diatoms treated with primary and secondary antibody with (b) no surface modification (c) after surface modification. (d and e) Scanning electron micrographs showing the pore pattern of the diatom *C. wailesii* (d) and after growth in the presence of nickel sulphate (e). Note the enlargement of pores, and hence change in optical properties, in (e). (f) "Photonic crystal" of the weevil *Metapocyrtus* sp., section through a scale, transmission electron micrograph; scale bar: 1 µm (see Parker[33]). (g) A comparatively enlarged diagrammatic example of cell membrane architecture: tubular christae in mitochondria from the chloride cell of sardine larvae. Evidence suggests that preexisting internal cell structures play a role in the manufacture of natural nanostructures; if these can be altered then so will the nanostructure made by the cell. (From Threadgold, L.T., *The Ultrastructure of the Animal Cell*, Pregamon Press, Oxford, U.K., 1967.)

Nucleophiles, such as xylene and pyridine, which donate electrons, had the opposite effect, and increased PL intensity almost ten times. Both quenching and enhancements were reversible as soon as the atmosphere was replaced by air.

The silica inherent to diatoms does not provide the optimum chemistry/refractive index for many applications. Sandhage et al.[22] have devised an inorganic molecular conversion reaction that preserves the size, shape, and morphology of the diatom while changing its composition. They perfected a gas/silica displacement reaction to convert biologically derived silica structures such as frustules into new compositions. Magnesium was shown to convert SiO_2 diatoms by a vapor phase reaction at 900°C to MgO of identical shape and structure, with a liquid Mg_2Si byproduct. Similarly, when diatoms were exposed to titanium fluoride gas, the titanium displaced the silicon, yielding a diatom structure made up entirely of titanium dioxide; a material used in some commercial solar cells.

An alternative route to silica replacement hijacks that native route for silica deposition in vivo. Rorrer et al.[23] sought to incorporate elements such as germanium into the frustule—a semiconductor material that has interesting properties that could be of value in optoelectronics, photonics, thin film displays, solar cells, and a wide range of electronic devices. Using a two-stage cultivation process, the photosynthetic marine diatom *Nitzschia* *frustulum* was shown to assimilate soluble germanium and fabricate Si-Ge-oxide nanostructured composite materials.

Porous glasses impregnated with organic dye molecules are promising solid media for tunable lasers and nonlinear optical devices, luminescent solar concentrators, gas sensors, and active waveguides. Biogenic porous silica has an open sponge-like structure and its surface is naturally OH-terminated. Hildebrand and Palenik[24] have shown that rhodamine B and 6G are able to stain diatom silica in vivo, and determined that the dye treatment could survive the harsh acid treatment needed to remove the surface organic layer from the silica frustule.

Now attention is beginning to turn additionally to coccolithophores—single-celled marine algae, also abundant in marine environments. Here, the cell secretes calcitic photonic crystal frustules, which, like diatoms, can take a diversity of forms, including complex 3D architectures at the nano- and microscales.

31.6 Iridoviruses

Viruses are infectious particles made up of the viral genome packaged inside a protein capsid. The iridovirus family comprises a diverse array of large (120–300 nm in diameter) viruses with icosahedral symmetry. The viruses replicate in the cytoplasm of insect cells. Within the infected cell the virus particles produce a paracrystalline array that causes Bragg refraction of light. This property has largely been considered esthetic to date, but the research group of Vernon Ward (New Zealand), in collaboration with the Biomaterials laboratory at Wright–Patterson Air Force base, is using iridoviruses to create biophotonic crystals. These can be used for the control of light, with this laboratory undertaking large-scale virus production and purification as well as targeting the manipulation of the surface of iridoviruses for altered crystal properties. These can provide a structural platform for a broad range of optical technologies, ranging from sensors to waveguides.

Virus nanoparticles, specifically *Chilo* and *Wiseana* Invertebrate Iridovirus, have been used as building blocks for iridescent nanoparticle assemblies. Here, virus particles were assembled in vitro, yielding films and monoliths with optical iridescence arising from multiple Bragg scattering from closely packed crystalline structures of the iridovirus. Bulk viral assemblies were prepared by centrifugation followed by the addition of glutaraldehyde, a cross-linking agent. Long-range assemblies were prepared by employing a cell design that forced virus assembly within a confined geometry followed by cross-linking. In addition, virus particles were used as core substrates in the fabrication of metallodielectric nanostructures. These comprise a dielectric core surrounded by a metallic shell. More specifically, a gold shell was assembled around the viral core by attaching small gold nanoparticles to the virus surface using inherent chemical functionality of the protein capsid.[25] These gold nanoparticles then acted as nucleation sites for electroless deposition of gold ions from solution. Such nano-shells could be manufactured in large quantities, and provide cores with a narrower size distribution and smaller diameters (below 80 nm) than currently used for silica. These investigations demonstrated that direct harvesting of biological structures, rather than biochemical modification of protein sequences, is a viable route to create unique, optically active materials.

31.7 The Mechanisms of Natural Engineering and Future Research

Where cell culture is concerned it is enough to know that cells *do* make optical nanostructures, which can be farmed appropriately. However, in the future an alternative may be to emulate the natural engineering processes ourselves, by reacting to the same concentrations of chemicals under the same environmental conditions, and possibly substituting analogous nano- or macro-machinery.

To date, the process best studied is the silica cell wall formation in diatoms. The valves are formed by the controlled precipitation of silica within a specialized membrane vesicle called the silica deposition vesicle (SDV). Once inside the SDV, silicic acid is converted into silica particles, each measuring approximately 50 nm in diameter. These then aggregate to form larger blocks of material. Silica deposition is molded into a pattern by the presence of organelles such as mitochondria spaced at regular intervals along the cytoplasmic side of the SDV.[26] These organelles are thought to physically restrict the targeting of silica from the cytoplasm, to ensure laying down of a correctly patterned structure. This process is very fast, presumably due to optimal reaction conditions for the synthesis of amorphous solid silica. Tight structural control results in the final species-specific, intricate exoskeleton morphology.

The mechanism whereby diatoms use intracellular components to dictate the final pattern of the frustule may provide a route for directed evolution. Alterations in the cytoplasmic morphology of *Skeletonema costatum* have been observed in cells grown in sublethal concentrations of Mercury and Zinc,[27] resulting in swollen organelles, dilated membranes, and vacuolated cytoplasm. Frustule abnormalities have also been reported in *Nitzschia liebethrutti* grown in the presence of mercury and tin.[28] Both metals resulted in a reduction in the length to width ratios of the diatoms, fusion of pores, and a reduction in the number of pores per frustule. These abnormalities were thought to arise from enzyme disruption either at the silica deposition site or at the nuclear level. We grew *Coscinodiscus wailesii* in sublethal concentrations of nickel and observed an increase in the size of the pores (Figure 31.6d and e), and a change in the phospholuminescent properties of the frustule. Here, the diatom can be "made to measure" for distinct applications such as stimuli-specific sensors.

Further, *trans*-Golgi-derived vesicles are known to manufacture the coccolithophore 3D "photonic crystals."[29] So the organelles within the cell appear to have exact control of (photonic) crystal growth ($CaCO_2$ in the coccolithophores) and packing (SiO_3 in the diatoms).[30,31] Indeed, Ghiradella[9] suggested that the employment of preexisting, intracellular structures lay behind the development of some butterfly scales, and Overton[32] reported the action of microtubules and microfibrils during butterfly-scale morphogenesis. Further evidence has been found to suggest that these mechanisms, involving the use of molds and nano-machinery (e.g., Figure 31.6f and g), reoccur with unrelated species, indicating that the basic "eukaryote" (containing a nucleus) cell can make complex photonic nanostructures with minimal genetic mutation.[33] The ultimate goal in the field of optical biomimetics, therefore, could be to replicate such machinery and provide conditions under which, if the correct ingredients are supplied, the optical nanostructures will self-assemble with precision.

For further information on the evolution of optical devices in nature, including those found in fossils, or when they first appeared on earth, see references.[34,35]

Acknowledgments

This work was funded by The Royal Society (University Research Fellowship), The Australian Research Council, European Union Framework 6 grant, and an RCUK Basic Technology grant.

References

1. Parker, A.R. 515 million years of structural colour. *J. Opt. A* **2**, R15–R28 (2000).
2. Parker, A.R., McPhedran, R.C., McKenzie, D.R., Botten, L.C., and Nicorovici, N.-A.P. Aphrodite's iridescence. *Nature* **409**, 36–37 (2001).
3. Miller, W.H., Moller, A.R., and Bernhard, C.G. The corneal nipple array. In C.G. Bernhard (ed.), *The Functional Organisation of the Compound Eye* (Pergamon Press, Oxford, U.K., 1966), pp. 21–33.
4. Yoshida, A., Motoyama, M., Kosaku, A., and Miyamoto, K. Antireflective nanoprotuberance array in the transparent wing of a hawkmoth *Cephanodes hylas*. *Zool. Sci.* **14**, 737–741 (1997).
5. Gale, M. Diffraction, beauty and commerce. *Phys. World* **2**, 24–28 (1989).
6. Boden, S.A. and Bagnall, D.M. Biomimetic subwavelength surfaces for near-zero reflection sunrise to sunset. *Proceedings of the 4th World Conference on Photovoltaic Energy, Conversion*, Waikoloa, HI (2006).
7. Parker, A.R., Hegedus, Z., and Watts, R.A. Solar-absorber type antireflector on the eye of an Eocene fly (45Ma). *Proc. R. Soc. Lond. B* **265**, 811–815 (1998).
8. Beale, B. Fly eye on the prize. *The Bulletin*, 46–48 (May 25, 1999).
9. Yablonovitch, E. Liquid versus photonic crystals. *Nature* **401**, 539–541 (1999).
10. Cohen, R.E., Zhai, L., Nolte, A., and Rubner, M.F. pH gated porosity transitions of polyelectrolyte multilayers in confined geometries and their applications as tunable Bragg reflectors. *Macromolecules* **37**, 6113 (2004).
11. Ghiradella, H. Structure and development of iridescent butterfly scales: Lattices and laminae. *J. Morph.* **202**, 69–88 (1989).
12. Berthier, S. *Les coulers des papillons ou l'imperative beauté. Proprietes optiques des ailes de papillons* (Springer, Paris, France, 2005), 142 pp.
13. DeSilva, L., Hodgkinson, I., Murray, P., Wu, Q., Arnold, M., Leader, J., and Mcnaughton, A. Natural and nanoengineered chiral reflectors: Structural colour of manuka beetles and titania coatings. *Electromagnetics* **25**, 391–408 (2005).
14. Kinoshita, S., Yoshioka, S., Fujii, Y., and Okamoto, N. Photophysics of structural color in the Morpho butterfly. *Forma* **17**, 103 (2002).
15. Watanabe, K., Hoshino, T., Kanda, K., Haruyama, Y., and Matsui, S. Brilliant blue observation from a *Morpho*-butterfly-scale quasi-structure. *Jpn. J. Appl. Phys.* **44**, L48–L50 (2005).
16. Zhang, W., Zhang, D., Fan, T., Ding, J., Gu, J., Guo, Q., and Ogawa, H. Bio-mimetic zinc oxide replica with structural color using butterfly (*Ideopsis similis*) wings as templates. *Bioinspir. Biomim.* 1, 89 (2006).
17. Fuhrmann, T., Lanwehr, S., El Rharbi-Kucki, M., and Sumper, M. Diatoms as living photonic crystals. *Appl. Phys. B* **78**, 257–260 (2004).
18. Lehmann, V. On the origin of electrochemical oscillations at silicon electrodes. *J. Electrochem. Soc.* **143**, 1313 (1993).
19. Rosi, N.L., Thaxton, C.S., and Mirkin, C.A. Control of nanoparticle assembly by using DNA-modified diatom templates. *Agnew Chem. Int. Ed.* **43**, 5500–5503 (2004).
20. Cullis, A.G., Canham, L.T., and Calcott, P.D.J. The structural and luminescence properties of porous silicon. *J. Appl. Phys.* **82**, 909–965 (1997).
21. De Stefano, L., Rendina, I., De Stefano, M., Bismuto, A., and Maddalena, P. Marine diatoms as optical chemical sensors. *Appl. Phys. Lett.* **87**, 233902 (2005).
22. Sandhage, K.H., Dickerson, M.B., Huseman, P.M., Caranna, M.A., Clifton, J.D., Bull, T.A., Heibel, T.J., Overton, W.R., and Schoenwaelder, M.E.A. Novel, bioclastic route to self-assembled, 3D, chemically tailored meso/nanostructures: Shape-preserving reactive conversion of biosilica (diatom) microshells. *Adv. Mater.* **14**, 429–433 (2002).
23. Rorrer, G.L., Chang, C.H., Liu, S.H., Jeffryes, C., Jiao, J., and Hedberg, J.A. Biosynthesis of silicon-germanium oxide nanocomposites by the marine diatom Nitzschia frustulum. *J. Nanosci. Nanotechnol.* **5**, 41–49 (2004).
24. Hildebrand, M. and Palenik, B. Grant report *Investigation into the Optical Properties of Nanostructured Silica from Diatoms*, La Jolla, CA (2003).
25. Radloff, C., Vaia, R.A., Brunton, J., Bouwer, G.T., and Ward, V.K. Metal nanoshell assembly on a virus bioscaffold. *Nano Lett.* **5**, 1187–1191 (2005).
26. Schmid, A.M.M. Aspects of morphogenesis and function of diatom cell walls with implications for taxonomy. *Protoplasma* **181**, 43–60 (1994).
27. Smith, M.A. The effect of heavy metals on the cytoplasmic fine structure of Skeletonema costatum (Bacillariophyta). *Protoplasma* **116**, 14–23 (1983).

28. Saboski, E. Effects of mercury and tin on frustular ultrastructure of the marine diatom *Nitzschia liebethrutti. Water, Air Soil Pollut.* **8**, 461–466 (1977).
29. Corstjens, P.L.A.M. and Gonzales, E.L. Effects of nitrogen and phosphorus availability on the expression of the coccolith-vesicle v-ATPase (subunit C) of Pleurochrysis (Haptophyta). *J. Phycol.* **40**, 82–87 (2004).
30. Klaveness, D. and Paasche, E. Physiology of coccolithophorids. In: *Biochemistry and Physiology of Protozoa*, 2nd edn., vol. 1 (Academic Press, New York, 1979), pp. 191–213.
31. Klaveness, D. and Guillard, R.R.L. The requirement for silicon in *Synura petersenii* (Chrysophyceae). *J. Phycol.* **11**, 349–355 (1975).
32. Overton, J. Microtubules and microfibrils in morphogenesis of the scale cells of *Ephestia kuhniella. J. Cell Biol.* **29**, 293–305 (1966).
33. Parker, A.R. Conservative photonic crystals imply indirect transcription from genotype to phenotype. *Recent Res. Develop. Entomol.* **5**, 1–10 (2006).
34. Parker, A.R. *In the Blink of an Eye* (Simon & Schuster, London, U.K., 2003), 316 pp.
35. Parker, A.R. A geological history of reflecting optics. *J. R. Soc. Lond. Interface* **2**, 1–17 (2005).

V

Nanophotonic Devices

32 Photon Localization at the Nanoscale *Kiyoshi Kobayashi* **32**-1
Introduction • Background • Dressing Mechanism and Spatial Localization of Photons • Summary and Future Perspective • Acknowledgments • References

33 Operations in Nanophotonics *Suguru Sangu and Kiyoshi Kobayashi* **33**-1
Introduction • Dissipation-Controlled Nanophotonic Devices • Nanophotonic Devices Using Spatial Symmetries • Summary • Acknowledgments • References

34 System Architectures for Nanophotonics *Makoto Naruse* **34**-1
Introduction • System Architectures Based on Optical Excitation Transfer • Hierarchical Architectures in Nanophotonics • Summary • References

35 Nanophotonics for Device Operation and Fabrication *Tadashi Kawazoe and Motoichi Ohtsu* **35**-1
Introduction • Excitation Energy Transfer in Nanophotonic Devices • Device Operation • Nanophotonics Fabrication • Summary • References

36 Nanophotonic Device Materials *Takashi Yatsui and Wataru Nomura* **36**-1
Introduction • Nanophotonic Devices Based on Quantum Dots • Nanophotonic AND-Gate Device Using ZnO Nanorod Double-Quantum-Well Structures • References

37 Waveguides for Nanophotonics *Jan Valenta, Tomáš Ostatnický, and Ivan Pelant* **37**-1
Introduction • Fabrication of Planar and Rib Waveguides • Experimental Techniques • Main Experimental Observations in Active Si-nc Waveguides • Theoretical Description of Active Lossy Waveguides • Application of Active Nanocrystalline Waveguides • Conclusions • Acknowledgments • References

38 Biomolecular Neuronet Devices *Grigory E. Adamov and Evgeny P. Grebennikov* **38**-1
Introduction • Some Techniques of Neuro-Molecular and Molecular Information Processing Using Bacteriorhodopsin (Basic Processes, Constructions, Technology) • Nanostructuring of Bacteriorhodopsin-Containing Molecular Media • Summary • References

32

Photon Localization at the Nanoscale

32.1 Introduction 32-1
32.2 Background 32-2
Difficulty in Defining a Wave Function of a Photon in Real Space • Effective Spatial Wave Function of a Single Photon • Canonical Field Quantization: Mode Functions, Field Operators, and Quantum States
32.3 Dressing Mechanism and Spatial Localization of Photons 32-5
Virtual Photon Cloud Surrounding a Neutral Source (in Ground State or Excited State) in QED • Electromagnetic Field Correlations and Intermolecular Interactions between Molecules in Either Ground or Excited States • Effective Near-Field Optical Interaction between Nanomaterials Disconnected but Closely Separated • Localization of a Photon Dressed by Matter Excitation in Nanomaterials at the Nanoscale
32.4 Summary and Future Perspective 32-17
Acknowledgments 32-17
References 32-17

Kiyoshi Kobayashi
University of Tokyo
Japan Science and Technology
University of Yamanashi

32.1 Introduction

You might think that the great success of quantum electrodynamics (QED) would settle the debate on the nature of light to provide a clear view of its behavior, where the photon is regarded as the unit of excitation associated with a quantized mode of the electromagnetic (radiation) field. However, Heisenberg's uncertainty principle tells us that a state of definite momentum, energy, and polarization associated with a plane wave used as a basis function of quantization must be completely indefinite in space and time. It suggests the difficulty of spatial localization of a photon as a particle. In fact, Newton and Wigner showed that a free photon, as a massless particle with spin 1, has no localized states on the basis of natural invariance requirements that localized states for which operators of the Lorentz group apply should be orthogonal to the undisplaced localized states, after a translation (Newton and Wigner 1949). According to them, one can obtain a general expression for a position operator for massive particles and for massless particles of spin 0 or 1/2, not for massless particles with finite spin, which indicates that there is no probability density for the position of the photon, and thus a position-representation wave function cannot be consistently introduced. It has also been shown that photons are not localizable, on the basis of imprimitive representations of the Euclidean group (Wightman 1962). It is now believed that photons are only weakly localizable, although single-photon states with arbitrarily fast asymptotic falloff of energy density exist, and that a lack of strict localizability is directly related to the absence of a position operator for a photon in free space and a position-representation photon wave function (Hawton 1999).

On the other hand, several authors have claimed that a minimum modification of the naive route leads to a wave-function description of a photon, even though the probability density for the position of a photon and a position-representation wave function cannot be consistently introduced. For example, it has been shown to be possible to introduce a position-representation wave function $\vec{\psi}(\vec{r}, t)$ for a photon, which is the expectation value of the photon energy in a region $d\vec{r}$ about $\vec{r}$ (Sipe 1995, Scully and Zubairy 1997, Hawton 1999, Roychoudhuri and Roy 2003). Mandel et al., from another viewpoint, have found that a photon wave function as a probability amplitude is possible in a coarse-grained volume whose linear dimensions are larger than the photon wavelength (Mandel 1966, Mandel and Wolf 1995, Inagaki 1998). The localization of the photon energy density and photodetection rates having an exponential or arbitrarily fast asymptotic falloff have been discussed, as well as causality (Hegerfeldt 1974, Pike and Sarkar 1987, Hellwarth and Nouchi 1996, Adlard et al. 1997, Bialynicki-Birula 1998, Keller 2005).

When the interactions with matter were considered, different views opened up. Dressed states and operators, dressed and half-dressed sources in nonrelativistic QED, electromagnetic field correlations, and intermolecular interactions between molecules in either ground or excited states have been discussed (Compagno et al. 1988, 1995, Cohen-Tannoudji et al. 1989, 1992, Power and Thirunamachandran 1993), focusing on the fact that a bare source interacting with a quantum field is surrounded by a cloud of virtual particles. It has been shown that the dressing of the source, or virtual cloud effects, can be detected by a test body (detector) located close to the source. Carniglia and Mandel (1971) proposed a complete basis for electromagnetic fields interacting with a material of refractive index n filled in a half space separated by vacuum in order to quantize the source fields, while Inoue and Hori (2001) discussed the detector modes and the behavior of a photon–atom interacting system near the material surface. Kobayashi et al. (2001) focused on the environmental effects on a nanomaterial interacting with photons and obtained a near-field optical interaction as an effective interaction between nanomaterials electronically disconnected, but closely located, in order to detect the cloud of virtual photons. They have also applied it to a discussion of nanophotonic devices (Sangu et al. 2004). Focusing on the photon degrees of freedom, on the other hand, photon hopping has been employed to discuss a photon–material interacting system (John and Quang 1995, Suzuura et al. 1996, Shojiguchi et al. 2003), and a photon dressing by material excitations has been recently discussed by using the photon-hopping model in real space and a quasiparticle model (Kobayashi et al. 2008).

Focusing on light–matter interactions at the nanoscale, we discuss a near-field optical interaction between nanomaterials surrounded by a macroscopic system, a dressing mechanism, and spatial localization of photons in this article, which is organized as follows. Section 32.2 is devoted to background issues for photon localization, in particular, the difficulty of the definition, effective methods, and free-field quantization. In Section 32.3 we discuss a dressing mechanism of photons and their localization in space, including virtual clouds of photons, electromagnetic field correlations and intermolecular interactions, effective near-field optical interactions, and phonons' effects on photon localization. Finally, a summary and a future outlook are presented.

32.2 Background

32.2.1 Difficulty in Defining a Wave Function of a Photon in Real Space

Since there is no probability density for the photon, and thus a position-representation wave function in free space cannot be consistently defined, one has to follow quantum electrodynamics (QED), that is, to redefine one- and a few-photon wave functions in a physically meaningful way in order to obtain fruitful insights into the photon–matter interacting system at the nanoscale. In the following subsections, we will give an overview of both approaches, after pointing out the difficulties involved with a position-representation wave function of a photon in free space.

We begin with Maxwell's equations in vacuum:

$$\nabla\times\vec{E}(\vec{r},t)=-\frac{1}{c}\frac{\partial\vec{B}(\vec{r},t)}{\partial t}, \tag{32.1a}$$

$$\nabla\times\vec{B}(\vec{r},t)=\frac{1}{c}\frac{\partial\vec{E}(\vec{r},t)}{\partial t}, \tag{32.1b}$$

where

c is the speed of light

$\vec{E}(\vec{r},t)$ and $\vec{B}(\vec{r},t)$ are electric and magnetic fields, respectively

Let us now define $\vec{\Phi}_{\pm}(\vec{r},t)$ as $\vec{\Phi}_{\pm}(\vec{r},t)=\vec{E}(\vec{r},t)\pm i\vec{B}(\vec{r},t)$; then, it follows from Maxwell's equations that $\vec{\Phi}_{\pm}(\vec{r},t)$ should satisfy

$$i\hbar\frac{\partial\vec{\Phi}_{\pm}(\vec{r},t)}{\partial t}=\pm c\hbar\nabla\times\vec{\Phi}_{\pm}(\vec{r},t). \tag{32.2}$$

Using the Fourier transform of these functions, we introduce the vectors $\vec{\gamma}_{\pm}(\vec{p},t)$ as

$$\vec{\Phi}_{\pm}(\vec{r},t)=\int\frac{d^3p}{(2\pi\hbar)^{3/2}}\vec{\gamma}_{\pm}(\vec{p},t)e^{i\vec{p}\cdot\vec{r}/\hbar}, \tag{32.3}$$

which is associated with $\gamma_{\pm}(\vec{p},t)$ as $\vec{\gamma}_{\pm}(\vec{p},t)=\gamma_{\pm}(\vec{p},t)\vec{e}_{\pm}(p)$ with

$$\vec{e}_{\pm}(\hat{p})=\mp\frac{1}{\sqrt{2}}[\vec{e}_1(\hat{p})\pm i\vec{e}_2(\hat{p})], \tag{32.4a}$$

where two unit vectors $\vec{e}_1(\hat{p})$ and $\vec{e}_2(\hat{p})$ are defined such that the unit vectors

$$\left[\vec{e}_1(\hat{p}),\,\vec{e}_2(\hat{p}),\,\hat{p}=\vec{p}/|\,\vec{p}\,|\right] \tag{32.4b}$$

form a right-handed triad. Then, it is easy to verify that $\gamma_{\pm}(\vec{p},t)$ satisfy a Schrödinger-like equation in the momentum representation

$$i\hbar\frac{\partial\gamma_{\pm}(\vec{p},t)}{\partial t}=cp\gamma_{\pm}(\vec{p},t), \tag{32.5}$$

which indicates that $\gamma_{\pm}(\vec{p},t)$ are probability amplitudes for photons of momentum $\vec{p}$, energy $E = cp$ with $p = |\vec{p}|$, and positive/negative helicity. Here note that

$$\vec{\gamma}^{\,*}_{+}(\vec{p},t)\cdot\vec{\gamma}_{+}(\vec{p},t)d\vec{p}=\vec{\gamma}^{\,*}_{-}(\vec{p}\cdot t)\cdot\vec{\gamma}_{-}(\vec{p},t)d\vec{p} \tag{32.6a}$$

and

$$\vec{\gamma}^{\,*}_{+}(\vec{p},t)\cdot\vec{\gamma}_{-}(\vec{p},t)=0 \tag{32.6b}$$

show the probability of detecting a photon of positive helicity and momentum $\vec{p}$ between $\vec{p}$ and $\vec{p} + d\vec{p}$, and likewise for a photon of negative helicity. Then the normalization condition is

$$\int\left[\vec{\gamma}_+^{\star}(\vec{p},t)\cdot\vec{\gamma}_+(\vec{p},t)+\vec{\gamma}_-^{\star}(\vec{p},t)\right]d^3p=1, \tag{32.7}$$

which leads to

$$\int\left[\vec{\Phi}_+^{\star}(\vec{r},t)\cdot\vec{\Phi}_+(\vec{r},t)+\vec{\Phi}_-^{\star}(\vec{r},t)\cdot\vec{\Phi}_-(\vec{r},t)\right]d^3r=1, \tag{32.8}$$

and it follows from the dynamical equations that

$$\vec{\Phi}_{\pm}(\vec{r},t)=\int\frac{d^3p}{(2\pi\hbar)^{3/2}}\vec{\gamma}_{\pm}(\vec{p},0)e^{-icpt/\hbar}e^{i\vec{p}\cdot\vec{r}/\hbar}. \tag{32.9}$$

Here we note that the sum of $\vec{\Phi}_{\pm}(\vec{r},t)$ might be regarded as the position-representation wave function of a photon, but it cannot be regarded as such because Newton and Wigner and also Wightman have shown that the photon, being a massless particle, is not localizable in free space, and that there does not exist a probability amplitude and density for the position of the photon in the usual sense (see also (32.15a) and (32.15b)) (Newton and Wigner 1949, Wightman 1962).

32.2.2 Effective Spatial Wave Function of a Single Photon

In order to avoid the difficulties mentioned above, Mandel defined an operator representing the number of photons in a volume *V* as the integral over *V* of a so-called "detection operator," which led a simple formula for the probability that *n* photons are present in *V*, when the linear dimensions of *V* are larger than the wavelength of light used (Mandel 1966).

Sipe took another approach to this issue, seeking a probability amplitude $\vec{\Psi}(\vec{r},t)$ for the photon energy to be detected about $d\vec{r}$ of $\vec{r}$ (Sipe 1995). Assuming that the integral of $\vec{\Psi}^{\star}(\vec{r},t)\cdot\vec{\Psi}(\vec{r},t)d\vec{r}$ over all space is proportional to the photon energy, we normalize it as follows:

$$\int\vec{\Psi}^{\star}(\vec{r},t)\cdot\vec{\Psi}(\vec{r},t)d^3r=\int cp\Big[\vec{\gamma}_+^{\star}(\vec{p},t)\cdot\vec{\gamma}_+^{\star}(\vec{p},t)$$
$$+\vec{\gamma}_-^{\star}(\vec{p},t)\cdot\vec{\gamma}_-^{\star}(\vec{p},t)\Big]d^3p. \tag{32.10}$$

It is easily shown that if $\vec{\Psi}(\vec{r},t)$ is set as

$$\vec{\Psi}(\vec{r},t)=\vec{\Psi}_+(\vec{r},t)+\vec{\Psi}_-(\vec{r},t), \tag{32.11a}$$

$$\vec{\Psi}_{\pm}(\vec{r},t)=\int\frac{\sqrt{cp}}{(2\pi\hbar)^{3/2}}\vec{\gamma}_{\pm}(\vec{p},t)e^{i\vec{p}\cdot\vec{r}/\hbar}d^3p, \tag{32.11b}$$

the normalization condition is satisfied. Here note that

$$\vec{\gamma}_+^{\star}(\vec{p},t)\cdot\vec{\gamma}_-(\vec{p},t)=0=\vec{\gamma}_-^{\star}(\vec{p},t)\cdot\vec{\gamma}_+(\vec{p},t) \tag{32.12}$$

and

$$i\hbar\frac{\partial\vec{\Psi}_{\pm}(\vec{r},t)}{\partial t}=\pm c\hbar\nabla\times\vec{\Psi}_{\pm}(\vec{r},t). \tag{32.13}$$

At the same time, $\vec{\Psi}_{\pm}(\vec{r},t)$ should be chosen to satisfy an initial condition given by

$$\vec{\Psi}_{\pm}(\vec{r},t)=\int\frac{\sqrt{cp}}{(2\pi\hbar)^{3/2}}\vec{\gamma}_{\pm}(\vec{p},0)e^{-icpt/\hbar}e^{i\vec{p}\cdot\vec{r}/\hbar}d^3p. \tag{32.14}$$

Since $\vec{\gamma}_{\pm}(\vec{p},t)$ and $\vec{\Psi}_{\pm}(\vec{p},\vec{r})$ are not the Fourier transform pairs, the arguments of the photon momentum $\vec{p}$ and the position $\vec{r}$ associated with the photon energy are not conjugate variables. When $\vec{\Phi}_{\pm}(\vec{r},t)$ and $\vec{\Psi}_{\pm}(\vec{r},t)$ are related by a local kernel, it can usually be regarded as a particle. However, $\vec{\Phi}_{\pm}(\vec{r},t)$, the Fourier transform of $\vec{\gamma}_{\pm}(\vec{p},t)$, is not a reasonable candidate for the position-representation wave function of the photon because of the following relation between $\vec{\Phi}_{\pm}(\vec{r},t)$ and $\vec{\Psi}_{\pm}(\vec{r},t)$

$$\vec{\Phi}_{\pm}(\vec{r},t)=\int w(\vec{r}-\vec{r}\,')\vec{\Psi}_{\pm}(\vec{r}\,',t)d^3r' \tag{32.15a}$$

with the nonlocal kernel

$$w(\vec{r}-\vec{r}\,')=\int\frac{1}{(2\pi)^3}\frac{e^{i\vec{k}\cdot(\vec{r}-\vec{r}\,')}}{\sqrt{\hbar ck}}d^3k. \tag{32.15b}$$

Nevertheless, $\vec{\Psi}(\vec{r},t)$ might be meaningful to describe the dynamics of a photon such as a spontaneous emission from an atom and the inverse process, or at least we can detect a photon, within the range of a detector's precision by placing a detector like an atom close to the source. In other words, it indicates that light–matter interactions near the source play an important role and should be treated consistently.

32.2.3 Canonical Field Quantization: Mode Functions, Field Operators, and Quantum States

It is natural to follow the canonical quantization of the electromagnetic field as a starting point for a discussion of light–matter interactions at the nanoscale. Since a lot of famous textbooks on

QED or quantum field theory have been published, we follow the essence of the theory and restrict ourselves to the free field that is free from charges and currents and whose scalar potential can be set to zero (Sakurai 1967, Roychoudhuri and Roy 2003). In the Coulomb gauge with $\nabla\cdot\vec{A}(\vec{r},t)=0$ for the vector potential $\vec{A}(\vec{r},t)$, three basic equations we work with for the free-field case are

$$\vec{B}(\vec{r},t)=\nabla\times\vec{A}(\vec{r},t), \tag{32.16a}$$

$$\vec{E}(\vec{r},t)=-\frac{1}{c}\frac{\partial\vec{A}(\vec{r},t)}{\partial t}, \tag{32.16b}$$

$$\nabla^2\vec{A}(\vec{r},t)-\frac{1}{c^2}\frac{\partial^2\vec{A}(\vec{r},t)}{\partial t^2}=0. \tag{32.16c}$$

We expand $\vec{A}(\vec{r},t)$ into a complete set of mode functions $\vec{u}_{\vec{k},a}(\vec{r})$ defined by the Helmholtz equation

$$(\nabla^2+\vec{k}^2)\vec{u}_{\vec{k},a}(\vec{r})=0, \tag{32.17}$$

and the boundary conditions set by the shape of a virtual cavity, for example, a box taken to be a cube of side $L = V^{1/3}$. It follows from the Coulomb gauge that the direction of $\vec{u}_{\vec{k},a}(\vec{r})$ has to be orthogonal to the wave vector $\vec{k}$, and thus there are two polarization degrees of freedom indicated by the index α. Note that the mode functions become more complicated, or even impossible for more sophisticated cavity shapes. The mode functions satisfy the orthonormality condition

$$\frac{1}{V}\int d^3r\vec{u}_\ell^{\star}(\vec{r})\cdot\vec{u}_{\ell'}(\vec{r})=\delta_{\ell\ell'}, \tag{32.18}$$

where we have for simplicity combined the three components of the wave vector $\vec{k}$ and the polarization index α to one index ℓ. Using the normalization constant A_t and the time-dependent amplitude $q_t(t)$, we have

$$\vec{A}(\vec{r},t)=\sum_\ell\left[A_\ell q_\ell(t)\vec{u}_\ell(\vec{r})+A_\ell^{\star}q_\ell^{\star}(t)\vec{u}_\ell^{\star}(\vec{r})\right], \tag{32.19}$$

where $q_t(t)$ follows from the differential equation of a harmonic oscillator of frequency $\Omega_\ell \equiv c|\vec{k}_\ell|$:

$$\frac{d^2q_\ell(t)}{dt^2}+\Omega_\ell^2q_\ell(t)=0. \tag{32.20}$$

The Hamiltonian of the field is

$$H=\frac{1}{8\pi}\int d^3r(\vec{E}^2+\vec{B}^2)=\frac{1}{8\pi}\int d^3r\left[\left(\frac{1}{c}\frac{\partial\vec{A}}{\partial t}\right)^2+(\nabla\times\vec{A})^2\right]. \tag{32.21}$$

Noticing a typical term for the $\vec{E}^2$ integration

$$\int\left(\frac{1}{c}\frac{dq_\ell}{dt}\right)\left(\frac{1}{c}\frac{dq_{\ell'}^{\star}}{dt}\right)\vec{u}_\ell(\vec{r})\cdot\vec{u}_{\ell'}^{\star}(\vec{r})d^3r=\left(\frac{\Omega_\ell}{c}\right)V|q_\ell|^2\,\delta_{\ell\ell'} \tag{32.22}$$

and for the $\vec{B}^2$ integration

$$\begin{aligned}\int(\nabla\times\vec{u}_\ell)\cdot(\nabla\times\vec{u}_{\ell'}^{\star})d^3r&=\int\nabla\cdot(\vec{u}_\ell\times\nabla\times\vec{u}_{\ell'}^{\star})d^3r+\int\vec{u}_\ell\cdot\left[\nabla\times\nabla\times\vec{u}_{\ell'}^{\star}\right]d^3r\\&=\int\vec{u}_\ell\cdot\left[\nabla(\nabla\cdot\vec{u}_{\ell'}^{\star})-\nabla^2\vec{u}_{\ell'}^{\star}\right]d^3r=-\int\vec{u}_\ell\cdot\nabla^2\vec{u}_{\ell'}^{\star}d^3r\\&=\left(\frac{\Omega_\ell}{c}\right)^2V\delta_{\ell\ell'}\end{aligned} \tag{32.23}$$

we obtain

$$H=\frac{V}{2\pi}\sum_\ell\left(\frac{\Omega_\ell}{c}\right)^2(A_\ell q_\ell)^{\star}(A_\ell q_\ell). \tag{32.24}$$

If we define

$$Q_\ell=\frac{1}{c}(q_\ell+q_\ell^{\star}), \tag{32.25a}$$

$$P_\ell=-i\frac{\Omega_\ell}{c}(q_\ell-q_\ell^{\star}),\quad A_\ell=\sqrt{\frac{4\pi}{V}}, \tag{32.25b}$$

the Hamiltonian can be expressed in terms of a collection of independent and uncoupled harmonic oscillators as

$$H=\sum_\ell\frac{1}{2}(P_\ell^2+\Omega_\ell^2Q_\ell^2). \tag{32.26}$$

Here, P_ℓ and Q_ℓ are seen to be canonical variables:

$$\frac{dP_\ell}{dt}=-\frac{\partial H}{\partial Q_\ell}, \tag{32.27a}$$

$$\frac{dQ_\ell}{dt}=\frac{\partial H}{\partial P_\ell}. \tag{32.27b}$$

The natural method to quantize the field is to replace the variable q_ℓ and its conjugate momentum $p_\ell \equiv dq_\ell/dt$ by operators $\hat{q}_\ell$ and $\hat{p}_\ell$ that satisfy the commutation relations $[\hat{q}_\ell,\hat{p}_\ell]=i\hbar\delta_{\ell\ell'}$, or $[Q_\ell,P_{\ell'}]=i\hbar\delta_{\ell\ell'}$. Then, the Hamiltonian operator for the quantized field can be written as follows:

$$\hat{H} = \sum_{\ell} \frac{1}{2}(\hat{P}_{\ell}^{2} + \Omega_{\ell}^{2}\hat{Q}_{\ell}^{2}). \tag{32.28}$$

Next we consider linear combinations of $\hat{P}_{\ell}$ and $\hat{Q}_{\ell}$, given by

$$\hat{a}_{\ell} = \sqrt{\frac{\Omega_{\ell}}{2h}}\left(\hat{Q}_{\ell} + \frac{i}{\Omega_{\ell}}\hat{P}_{\ell}\right), \tag{32.29a}$$

$$\hat{a}_{\ell}^{\dagger} = \sqrt{\frac{\Omega_{\ell}}{2h}}\left(\hat{Q}_{\ell} + \frac{i}{\Omega_{\ell}}\hat{P}_{\ell}\right), \tag{32.29b}$$

where we insert a factor to make $\hat{a}_{\ell}$ and $\hat{a}_{\ell}^{\dagger}$ dimensionless and thus satisfy the following boson commutation relations:

$$\left[\hat{a}_{\ell}, \hat{a}_{\ell'}\right] = -\frac{i}{2h}[\hat{Q}_{\ell}, \hat{P}_{\ell'}] + \frac{i}{2h}[P_{\ell}, Q_{\ell'}] = \delta_{\ell\ell'}. \tag{32.30}$$

Taking care of the order of $\hat{a}_{\ell}$ and $\hat{a}_{\ell'}^{\dagger}$, we obtain the Hamiltonian operator of the electromagnetic field as

$$\hat{H} = \sum_{\ell} \hbar\Omega_{\ell}\left(\hat{n}_{\ell} + \frac{1}{2}\right), \tag{32.31}$$

where $\hat{n}_{\ell} \equiv \hat{a}_{\ell}^{\dagger}\hat{a}_{\ell}$ denotes the number operator. The contribution 1/2 arises from the commutation relations and results in the familiar zero-point energy. Since there are infinitely many modes, the zero-point energy becomes infinite, but in general we drop this contribution by shifting the vacuum energy, which does not influence the dynamics. The quantization procedure is completed by writing the vector potential in terms of $\hat{a}_{\ell}$ and $\hat{a}_{\ell}^{\dagger}$ as a field operator

$$\hat{\vec{A}}\left(\vec{r}, t\right) = \sum_{\ell} \sqrt{\frac{2\pi\hbar c^{2}}{V\Omega_{\ell}}}\left(\hat{a}_{\ell}\vec{u}_{\ell} + \hat{a}_{\ell}^{\dagger}\vec{u}_{\ell}^{*}\right). \tag{32.32}$$

Thus, $\hat{a}_{\ell}^{\dagger}$ is called the creation operator for a photon specified in ℓ as corresponding to the quantum-mechanical excitations of the electromagnetic field, while $\hat{a}_{\ell}$ is interpreted as the annihilation operator for a photon in state ℓ. It is important to note that the $\vec{r}$ and t that appear in the quantized field $\hat{\vec{A}}(\vec{r}, t)$ are not quantum-mechanical variables but just parameters on which the field operator depends, and, in particular, $\vec{r}$ and t should not be regarded as the space–time coordinates of the photon.

When we adopt a linearly polarized plane wave as the mode function

$$\vec{u}_{\ell}\left(\vec{r}\right) = \vec{\varepsilon}_{\vec{k}\alpha}e^{i\vec{k}\cdot\vec{r}} \tag{32.33}$$

with the polarization vector $\vec{\varepsilon}_{\vec{k}\alpha}$, the energy and momentum of the photon are $\hbar\Omega_{\vec{k}} = \hbar\left|\vec{k}\right|c$ and $\hbar\vec{k}$, respectively. Therefore, the mass of the photon is zero. In addition, since $\vec{\varepsilon}_{\vec{k}\alpha}$ transforms like a vector, the general theory of angular momentum encourages us to associate with it one unit of angular momentum, which means that the photon has one unit of spin angular momentum.

The field operators described above operate on quantum state vectors, and quantum states $|\Psi\rangle$ of the electromagnetic field are, in general, multimode states that involve quantum states $|\psi_{\ell}\rangle$ for each mode ℓ. One of the useful quantum states is photon number states denoted by $|n_{\ell}\rangle$, which are eigenstates of the number operator $\hat{n}_{\ell}$

$$\hat{n}_{\ell}|n_{\ell}\rangle = n_{\ell}|n_{\ell}\rangle \tag{32.34}$$

with integer eigenvalues n_{ℓ}. At the same time, $|n_{\ell}\rangle$ are eigenstates of the Hamiltonian with eigenenergy $n_{\ell}\hbar\Omega_{\ell}$, that is, n_{ℓ} times the fundamental unit $\hbar\Omega_{\ell}$. It should be noted that n_{ℓ} quanta of energy $\hbar\Omega_{\ell}$ are in the mode, but the energy is distributed over the entire space, that is, not localized. Other useful quantum states used later are coherent states $|\alpha\rangle$, which are eigenstates of the annihilation operator $\hat{a}_{\ell}$ with eigenvalues α

$$\hat{a}_{\ell}|\alpha\rangle = \alpha|\alpha\rangle. \tag{32.35}$$

The phase of the coherent states is completely determined, while the number of photons is completely undetermined.

In the subsequent sections, we will employ a quantum electromagnetic field discussed above in order to discuss the nature of light–matter interactions apparently exhibited at the nanoscale.

32.3 Dressing Mechanism and Spatial Localization of Photons

32.3.1 Virtual Photon Cloud Surrounding a Neutral Source (in Ground State or Excited State) in QED

A quantum source material system interacting with a quantum field is influenced by virtual processes such as emission and absorption of virtual quanta of the field, and the source can be described as a dressed source, that is, the "bare" source surrounded by a cloud of virtual particles (Compagno et al. 1988, 1995). It is true for a detector. The virtual-cloud effects are responsible for the modification of the values of fundamental constants. For example, in nonrelativistic quantum electrodynamics, the presence of a virtual cloud around a hydrogen atom in its ground state contributes to the Lamb shift. Dressed-source effects can also be seen in different physical systems, such as a nucleon coupled to the meson field, and an electron coupled to the optical phonon modes of a semiconductor (polaron). The virtual cloud around the source also modifies the energy density distribution of the electromagnetic field, and the detailed properties have direct physical significance. The energy density of the virtual photon cloud at a given point is in fact related to the van der Waals interaction experienced by a suitable test object as a detector at that point. The presence of a virtual cloud around a source can influence not only its energy levels but also its dynamics.

Let us roughly estimate the linear dimensions of the virtual cloud surrounding the source or the detector. Even when the source–field system is in the ground state, a fluctuation of the field leads to the possibility of absorption or the emission of photons, not necessarily to the conservation of energy. Such energy imbalance δE is constrained by the Heisenberg uncertainty principle $\delta E \sim \hbar/\tau$, where τ is the duration of the fluctuation. Since these fluctuations take place continuously, a steady-state cloud of virtual photons is continuously emitted and reabsorbed. The virtual photon can only attain a finite distance from the source or the detector given by

$$r \sim c\tau \sim \frac{\hbar c}{\delta E}, \tag{32.36}$$

where c is the speed of light. For a transition corresponding to one of typical visible light, we set $\delta E \sim 2\,\text{eV}$ and obtain a typical linear dimension of 100 nm. This indicates that dressing effects might be prominent at the nanoscale.

We have discussed the virtual clouds of the source or detector in its ground state. From now on, we discuss the virtual cloud of the source or the detector in excited states, which can decay by emission of real photons. The above discussion inclines us to use the perturbation theory, but it fails due to the near degeneracy of states that gives rise to vanishing energy denominators at all the orders of perturbation theory. Another difficulty is the description of decay processes in a consistent way. One of such attempts is based on an extension of the eigenvalue problem to the complex E-plane. The underlying theory, unfortunately, has not yet been established, but it seems to imply time symmetry breaking and irreversibility in the dynamics of the system Section 32.3.2 will be devoted to an approach focusing on field correlations and intermolecular interactions due to the virtual clouds.

32.3.2 Electromagnetic Field Correlations and Intermolecular Interactions between Molecules in Either Ground or Excited States

The London–van der Waals interaction between two molecules in their ground states located in free space is attractive with an R^{-6} power law, where R is the intermolecular separation (Power and Thirunamachandran 1993). When both molecules are excited, the potential energy gives a repulsive force. If one of the pair is excited, the sign of the potential depends on the relative magnitudes of the relevant transition energies of the two molecules. In both cases the power law is R^{-6} in the near zone. On the other hand, the power law in the far zone tends to R^{-7} for large intermolecular separations, which is called the Casimir–Polder potential, since the finite speed of propagation (retardation effect) plays an important role in the far zone.

In these kinds of studies, the multipolar quantum dynamics in Coulomb gauge is employed because all the interactions, except for the Coulomb binding within each molecule, are mediated by transverse photons, and at the same time the retarded effects are automatically satisfied (Power and Thirunamachandran 1993). For example, for upward transitions from the ground state $|0\rangle$ to an excited state $|m\rangle$, the electric–electric spatial correlation expectation value after spatial averaging of the molecular orientation is given by using the second-order perturbation method to include virtual-cloud effects:

$$\left\langle D_i(\vec{r})D_j(\vec{r})\right\rangle_{m\leftarrow 0} \sim \begin{cases} \dfrac{\left|\vec{\mu}^{\,m0}\right|^2}{6\pi k_0 r^7}(13\delta_{ij}+7\hat{r}_i\hat{r}_j), & \text{for far zone } (k_0 r \gg 1), \\ \dfrac{\left|\vec{\mu}^{\,m0}\right|^2}{3r^6}(\delta_{ij}+3\hat{r}_i\hat{r}_j), & \text{for near zone } (k_0 r \ll 1) \end{cases} \tag{32.37}$$

where $D_i(\vec{r})$ is the i-component of the transverse displacement vector field $\vec{D}(\vec{r})$, which satisfies $\nabla\cdot\vec{D}(\vec{r})=0$, $\vec{\mu}^{\,m0}$ is the electric dipole transition moment for the molecular states $|m\rangle$ and $|0\rangle$, and $k_0 \equiv k_{m0} \equiv (E_m - E_0)/(\hbar c)$ denotes the wave number associated with the $m \leftarrow 0$ transition of the molecule. The i-component of the unit vector $\hat{r}$ is designated by $\hat{r}_i$, while the absolute value of the position vector $\vec{r}$ is expressed by r. The Kronecker delta is denoted by δ_{ij}.

Similarly, for downward transitions from an excited state $|p\rangle$ to the ground state $|0\rangle$, the electric–electric correlation function is obtained:

$$\left\langle D_i(\vec{r})D_j(\vec{r})\right\rangle_{0\leftarrow p} \sim \begin{cases} \dfrac{2p_0^4\left|\vec{\mu}^{\,0p}\right|^2}{3r^2}(\delta_{ij}-\hat{r}_i\hat{r}_j), & \text{for far zone } (p_0 r \gg 1), \\ \dfrac{\left|\vec{\mu}^{\,0p}\right|^2}{3r^6}(\delta_{ij}+3\hat{r}_i\hat{r}_j), & \text{for near zone } (p_0 r \ll 1), \end{cases} \tag{32.38}$$

where $p_0 \equiv p_{0p} \equiv (E_p - E_0)/(\hbar c)$ denotes the wave number associated with the $0 \leftarrow p$ transition of the molecule. It should be noted that the r^{-2} dependence arises from the real photon emission, while the r^{-6} dependence and the r^{-7} dependence are due to the virtual photon exchange. The far-zone behavior for the magnetic–magnetic correlation functions due to an electric-dipole source is also described by the same r^{-2} or r^{-7} dependence, while the near-zone result is different from its electric analog and the power law is r^{-5} instead of r^{-6}.

We have discussed the electric and magnetic correlation functions leading to the electric and magnetic energy densities associated with electric-dipole transitions in a source molecule, which can be detected by their effect on polarizable test bodies placed in the neighborhood of the source. This situation is analogous to an optical near-field system in which a nanometric material source connected to a macroscopic material and light source interacts with a nanometric detector connected to a macroscopic detector system. The difference is that the nanometric detector serving as a test body can disturb the field formed by the nanometric source in the case of the optical near-field system. We will move on to this topic in Section 32.3.3.

32.3.3 Effective Near-Field Optical Interaction between Nanomaterials Disconnected but Closely Separated

Several theoretical approaches to optical near-field problems, different from each other in viewpoints, have been proposed in the last two decades (Pohl and Courjon 1993, Ohtsu and Hori 1999). The optical near-field problems, including the application to nanophotonics, are ultimately regarded as how one should formulate a separated (more than two elements) composite system, each of which consists of a photon–electron–phonon interacting system on a nanometer scale as a source or a detector system and, which, at the same time, is connected with a macroscopic light–matter system. These questions must be clearly answered to achieve practical realization of nanophotonics. In order to provide a base for a variety of discussions in this research field, a new formulation has been developed within a quantum theoretical framework, putting matter excitations (electronic and vibrational) on an equal footing with photons (Kobayashi et al. 2001).

As discussed in Section 32.2, a "photon," whose concept has been established as a result of quantization of a free electromagnetic field, corresponds to a discrete excitation of electromagnetic modes in a virtual cavity. Unlike an electron, a photon is massless, and it is difficult to construct a wave function in the position representation that gives a picture of the photon as a spatially localized point particle like an electron. However, if there is a detector near the optical source, such as an atom, to absorb a photon in an area whose linear dimension is much smaller than the wavelength of light, it would be possible to detect a photon with the same precision as the detector size. In optical near-field problems, it is required to consider the interactions between light and nanomaterials surrounded by a macroscopic material system and detection of light by other nanomaterials on a nanometer scale. Then, a more serious question for the quantization of the field is how to define a virtual cavity, or which normal modes are to be used, since there exist more than two systems (nano-source and nano-detector) with arbitrary shape, size, and material in the nanometer region, which are still connected with a macroscopic material system, such as a source or a detector system. In this section, we describe a model and a theoretical approach to address the issue, which is essential to understand the operating principles nanophotonic devices, as well as nanofabrication using optical near fields (Ohtsu et al. 2008).


Incident light
Macroscopic material system
Virtual clouds of photons (dressed photons)
Relaxation
Nano source
Nano detector
Radiation

FIGURE 32.1 Nanometric source and detector system induced by incident light and a macroscopic material system.

Let us consider a nanomaterial system surrounded by an incident light and a macroscopic material system, which electromagnetically interacts with one another in a complicated way, as schematically shown in Figure 32.1. Using the projection operator method, we can derive an effective interaction between the relevant nanomaterials in which we are interested (nano-source and nano-detector—either one is in the excited state), as a result of renormalizing the other effects. It corresponds to an approach to describe "photons localized around nanomaterials," as if each nanomaterial would work as a detector and light source in a self-consistent way. The effective interaction related to optical near-fields is hereafter called a near-field optical interaction. As will be discussed in detail in this section, the near-field optical interaction between nanomaterials separated by R is as follows:

$$V_{\text{eff}} = \frac{\exp(-aR)}{R}, \tag{32.39}$$

where a^{-1} is the interaction range that represents the characteristic size of the nanomaterials and does not depend on the wavelength of the light used. It indicates that photons are localized around the nanomaterials (either of which is in the excited state) as a result of the interaction with matter fields, from which a photon, in turn, can acquire a finite mass. Therefore, we might consider that the near-field optical interaction is produced via localized photon hopping between nanomaterials. On the basis of the projection operator method, we will investigate formulation of an optical near-field system that was briefly mentioned above. Moreover, the explicit functional form of the near-field optical interaction will be given by using the effective interaction $m\hat{V}_{\text{eff}}$ in a perturbative way.

32.3.3.1 Relevant Nanometric Subsystem and Irrelevant Macroscopic Subsystem

As schematically illustrated in Figure 32.1, the optical near-field system consists of two subsystems: One is a macroscopic subsystem including the incident light, whose typical dimension is much larger than the wavelength of the incident light. The other is a nanometric subsystem (nano-source and nano-detector), whose constituents are, for example, a nanometric aperture or a protrusion at the apex of a near-field optical probe, and a nanometric sample. We call such an aperture or a protrusion a probe tip.

As a nanometric sample we mainly suppose a single atom/molecule, or quantum dot (QD). Two subsystems are interacting with each other, and it is very important to formulate the interaction consistently and systematically. Here let us call the nanometric subsystem a relevant subsystem n, and the macroscopic subsystem an irrelevant subsystem M. We are interested in the subsystem n; in particular, the interaction induced in the subsystem n. Therefore, it is the key to renormalize the effects originating from the subsystem M in a consistent and systematic way. Now we show a formulation based on the projection operator method, described below.

32.3.3.2 P Space and Q Space

It is preferable, for a variety of discussions, to express exact eigenstates $|\psi\rangle$ for the total system described by the total Hamiltonian $\hat{H}$ in terms of a small number of bases of as small a number of degrees of freedom as possible, which span P space. In the following, let us assume two states as the P-space components: $|\phi_1\rangle = |s^*\rangle|p\rangle\otimes|0_{(M)}\rangle$ and $|\phi_2\rangle = |s\rangle|p^*\rangle\otimes|0_{(M)}\rangle$, both of which are eigenstates of the unperturbed Hamiltonian $\hat{H}_0$. Here $|s\rangle$ and $|s^*\rangle$ are eigenstates of the sample that is isolated from the others, while $|p\rangle$ and $|p^*\rangle$ are eigenstates of the probe tip, which is also isolated. In addition, exciton polariton states, which are a mixture of photons and electron–hole pairs, are used as bases to describe the macroscopic subsystem M, and thus $|0_{(M)}\rangle$ represents the vacuum for exciton polaritons. Note that there exist photons and electronic matter excitations even in the vacuum state $|0_{(M)}\rangle$. The direct product is denoted by the symbol $\otimes$. The complementary space to the P space is called Q space, which is spanned by a huge number of bases of a large number of degrees of freedom not included in the P space, as schematically shown in Figure 32.2.

32.3.3.3 Effective Interaction Exerted in the Nanometric Subsystem

Noticing the relation between a bare interaction Hamiltonian $\hat{V} = \hat{H} - \hat{H}_0$ and an effective interaction Hamiltonian operator $\hat{V}_{\text{eff}}$, namely, $\langle\psi|\hat{V}|\psi\rangle = \langle\psi|P\hat{V}_{\text{eff}}P|\psi\rangle$, we obtain the effective interaction Hamiltonian operator in the P space, given by

$$\hat{V}_{\text{eff}} = (P\hat{J}^{\dagger}\hat{J}P)^{-1/2}(P\hat{J}^{\dagger}\hat{V}\hat{J}P)(P\hat{J}^{\dagger}\hat{J}P)^{-1/2}, \qquad (32.40)$$



FIGURE 32.2 Subdivision of the space spanned by eigenstates of the total Hamiltonian of the system.

and tracing out the other degrees of freedom gives an effective interaction Hamiltonian of the nanometric subsystem n after renormalizing the effects from the macroscopic subsystem M. Here, P is the projection operator, and Q is the complimentary operator defined by $Q = 1 - P$, both of which satisfy the following relations:

$$P = P^{\dagger}, \quad P^2 = P, \quad [P, \hat{H}_0] = 0, \qquad (32.41a)$$

$$Q = Q^{\dagger}, \quad Q^2 = Q, \quad [Q, \hat{H}_0] = 0, \qquad (32.41b)$$

$$PQ = QP = 0. \qquad (32.41c)$$

The operator $\hat{J}$ is defined by

$$\hat{J} = [1 - (E - \hat{H}_0)^{-1} Q\hat{V}]^{-1}, \qquad (32.42)$$

where E are the eigenvalues of the total Hamiltonian $\hat{H}$. Using the effective interaction Hamiltonian, one can forget the subsystem M as if the subsystem n were isolated and separated from the subsystem M.

To obtain an explicit expression of the effective interaction Hamiltonian, let us employ the bare interaction $\hat{V}$ between the two subsystems, which in the multipolar formalism (Craig and Thirunamachandran 1998) is given by

$$\hat{V} = -\left\{\hat{\vec{\mu}}_s \cdot \hat{\vec{D}}^{\perp}(\vec{r}_s) + \hat{\vec{u}}_p \cdot \hat{\vec{D}}^{\perp}(\vec{r}_p)\right\}, \qquad (32.43)$$

where the canonical momentum of the vector potential operator $\hat{\vec{A}}(\vec{r})$ is proportional to the transverse displacement vector field operator* $\hat{\vec{D}}^{\perp}(\vec{r})$, while the electric dipole operator is denoted as $\hat{\vec{\mu}}(\vec{r})$. It should be noted that there are no interactions, i.e., $\hat{V} = 0$, without incident photons in the macroscopic subsystem M. The subscripts s and p represent physical quantities related to the sample and the probe tip, respectively. Representative positions of the sample and the probe tip are chosen, for simplicity, by the vectors $\vec{r}_s$ and $\vec{r}_p$, respectively, but may be composed of several positions. In that case the quantities inside curly brackets in (32.43) should be read as a summation. The operator $\hat{\vec{\Pi}}(\vec{r})$ conjugate to $\hat{\vec{A}}(\vec{r})$ is expressed in terms of $\hat{\vec{D}}^{\perp}(\vec{r})$ as follows:

---

* The transverse component is defined by $\nabla \cdot \vec{F}^{\perp} = 0$, while the longitudinal component is defined by $\nabla \times \vec{F}^{\parallel} = 0$, for an arbitrary vector field $\vec{F}(\vec{r})$.

$$\hat{\vec{\Pi}}(\vec{r}) = -\frac{1}{4\pi c}\hat{\vec{E}}^{\perp}(\vec{r}) - \frac{1}{c}\hat{\vec{P}}^{\perp}(\vec{r}) = -\frac{1}{4\pi c}\hat{\vec{D}}^{\perp}(\vec{r}), \tag{32.44}$$

where $\hat{\vec{E}}^{\perp}(\vec{r})$ and $\hat{\vec{P}}^{\perp}(\vec{r})$ are the transverse electric field and the induced polarization field, respectively. With the help of the mode expansion of $\hat{\vec{A}}(\vec{r})$ and $\hat{\vec{\Pi}}(\vec{r})$, that is,

$$\hat{\vec{A}}(\vec{r}) = \sum_{k}\sum_{\lambda=1}\left(\frac{2\pi\hbar c^2}{V\omega_{\vec{k}}}\right)^{1/2}\vec{e}_{\lambda}(\vec{k})\left\{\hat{a}_{\lambda}(\vec{k})e^{i\vec{k}\cdot\vec{r}} + \hat{a}_{\lambda}^{\dagger}(\vec{k})e^{-i\vec{k}\cdot\vec{r}}\right\}, \tag{32.45}$$

and

$$\hat{\vec{\Pi}}(\vec{r}) = -\frac{i}{4\pi c}\sum_{\vec{k}}\sum_{\lambda=1}^{2}\left(\frac{2\pi\hbar\omega_{\vec{k}}}{V}\right)^{1/2}\vec{e}_{\lambda}(\vec{k})\left\{\hat{a}_{\lambda}(\vec{k})e^{i\vec{k}\cdot\vec{r}} - \hat{a}_{\lambda}^{\dagger}(\vec{k})e^{-i\vec{k}\cdot\vec{r}}\right\} \tag{32.46}$$

we can rewrite the transverse component of the electric displacement operator as

$$\hat{\vec{D}}^{\perp}(\vec{r}) = i\sum_{\vec{k}}\sum_{\lambda=1}^{2}\left(\frac{2\pi\hbar\omega_{\vec{k}}}{V}\right)^{1/2}\vec{e}_{\lambda}(\vec{k})\left\{\hat{a}_{\lambda}(\vec{k})e^{i\vec{k}\cdot\vec{r}} - \hat{a}_{\lambda}^{\dagger}(\vec{k})e^{-i\vec{k}\cdot\vec{r}}\right\}, \tag{32.47}$$

where the plane waves are used for the mode functions, and the creation and annihilation operators of a photon with wave vector $\vec{k}$, angular frequency $\omega_{\vec{k}}$, and polarization component λ are designated by $\hat{a}_{\lambda}^{\dagger}(\vec{k})$ and $\hat{a}_{\lambda}(\vec{k})$, respectively. The quantization volume is V, and the unit vector related to the polarization direction is shown by $\vec{e}_{\lambda}(\vec{k})$. Note that the electric field outside the material corresponds to $\hat{\vec{D}}^{\perp}(\vec{r})$.

Since exciton polariton states are employed as bases to describe the macroscopic subsystem M, the creation and annihilation operators of a photon in (32.47) are rewritten using the exciton polariton operators $\hat{\xi}^{\dagger}(\vec{k})$ and $\hat{\xi}(\vec{k})$, and then they are substituted into (32.43). Using the electric dipole operator defined by

$$\hat{\vec{\mu}}_{\alpha} = \left(\hat{B}(\vec{r}_{\alpha}) + \hat{B}^{\dagger}(\vec{r}_{\alpha})\right)\vec{\mu}_{\alpha}, \tag{32.48}$$

with the creation and annihilation operators of excitation in subsystem n, $\hat{B}^{\dagger}(\vec{r}_{\alpha})$ and $\hat{B}(\vec{r}_{\alpha})$, and the transition dipole moments $\vec{\mu}_{\alpha}$ ($\alpha = s, p$), we obtain the bare interaction in the exciton polariton picture:

$$\hat{V} = -i\sum_{\alpha=s}^{p}\sum_{\vec{k}}\left(\frac{2\pi\hbar}{V}\right)^{1/2}\left(\hat{B}(\vec{r}_{\alpha}) + \hat{B}^{\dagger}(\vec{r}_{\alpha})\right)\left(K_{\alpha}(\vec{k})\hat{\xi}(\vec{k}) - K_{\alpha}^{*}(\vec{k})\hat{\xi}^{\dagger}(\vec{k})\right). \tag{32.49}$$

Here $K_{\alpha}(\vec{k})$ is the coupling coefficient between the exciton polariton and the nanometric subsystem n, given by

$$K_{\alpha}(\vec{k}) = \sum_{\lambda=1}^{2}\left(\vec{\mu}_{\varepsilon}\cdot\vec{e}_{\lambda}(\vec{k})\right)f(k)e^{i\vec{k}\cdot\vec{r}_{\alpha}} \tag{32.50}$$

with

$$f(k) = \frac{ck}{\sqrt{\Omega(k)}}\sqrt{\frac{\Omega^2(k) - \Omega^2}{2\Omega^2(k) - \Omega^2 - (ck)^2}}. \tag{32.51}$$

The complex conjugate of $K_{\alpha}(\vec{k})$ is denoted by $K_{\alpha}^{*}(\vec{k})$, while c, $\Omega(k)$, and Ω are light speed in vacuum and the eigenfrequencies of both exciton polariton and electronic polarization of the macroscopic subsystem M, respectively. The dispersion relation for a free photon, $\omega_{\vec{k}} = ck$, is used in (32.51). Note that the wave-number dependence of $f(k)$ characterizes a typical interaction range of exciton polaritons coupled to the nanometric subsystem n.

The next step is to evaluate the amplitude of the effective interaction exerted on the nanometric subsystem, for example, the effective sample–probe-tip interaction in the P space after tracing out the polariton degrees of freedom:

$$V_{\text{eff}}(2,1) \equiv \langle\phi_2|\hat{V}_{\text{eff}}|\phi_1\rangle. \tag{32.52}$$

With the first-order approximation $\hat{J}^{(1)}$ of $\hat{J}$ in (32.42), we can explicitly write (32.52) in the following form:

$$\begin{aligned} V_{\text{eff}}(2,1) &= \langle\phi_2|P\hat{V}Q\hat{V}(E_P^0 - E_Q^0)^{-1}P\,|\,\phi_1\rangle + \langle\phi_2|P(E_P^0 - E_Q^0)^{-1}\hat{V}Q\hat{V}P|\phi_1\rangle \\ &= \sum_{m}\langle\phi_2|P\hat{V}Q|m\rangle\langle m|Q\hat{V}P|\phi_1\rangle\left(\frac{1}{E_{P1}^0 - E_{Qm}^0} + \frac{1}{E_{P2}^0 - E_{Qm}^0}\right). \end{aligned} \tag{32.53}$$

The second line shows that a virtual transition from the initial state $|\phi_1\rangle$ in the P space to an intermediate state $|m\rangle$ in the Q space is followed by a subsequent virtual transition from the intermediate state $|m\rangle$ to the final state $|\phi_2\rangle$ in the P space. Here $E_{P1}^0(E_{P2}^0)$ and E_{Qm}^0 denote eigenenergies of $|\phi_1\rangle(|\phi_2\rangle)$ in the P space and that of $|\phi_m\rangle$ in the Q space, respectively. Now we can proceed to the next step by substituting the explicit bare interaction $\hat{V}$ in (32.49) with (32.50) and (32.51) into (32.53). First of all, note that the one-exciton polariton state among arbitrary intermediate states $|m\rangle$ can only contribute to nonzero matrix elements. Therefore, (32.53) can be transformed into

$$V_{\text{eff}}(2,1) = -\frac{\hbar}{(2\pi)^2}\int d^3k\left[\frac{K_p(\vec{k})K_s^{*}(\vec{k})}{\Omega(k) - \Omega_0(s)} + \frac{K_s(\vec{k})K_p^{*}(\vec{k})}{\Omega(k) + \Omega_0(s)}\right], \tag{32.54}$$

where the summation over $\vec{k}$ is replaced by $\vec{k}$-integration, i.e., $\frac{V}{(2\pi)^3}\int d^3k$, in the usual manner. Excitation energies of the sample (between $|s^*\rangle$ and $|s\rangle$) and the probe tip (between $|p^*\rangle$ and $|p\rangle$) are denoted as $E_s = \hbar\Omega_0(s)$ and $E_p = \hbar\Omega_0(p)$, respectively.

Exchanging the arguments 1 and 2, or the role of the sample and probe tip, we can similarly calculate $V_{\mathrm{eff}}(1,2) \equiv \langle\phi_1|\hat{V}_{\mathrm{eff}}|\phi_2\rangle$:

$$V_{\mathrm{eff}}(1,2) = -\frac{\hbar}{(2\pi)^2}\int d^3k\left[\frac{K_s(\vec{k})K_p^{\star}(\vec{k})}{\Omega(k)-\Omega_0(p)} + \frac{K_p(\vec{k})K_s^{\star}(\vec{k})}{\Omega(k)+\Omega_0(p)}\right]. \tag{32.55}$$

Therefore, the total amplitude of the effective sample–probe-tip interaction is given by the sum of (32.54) and (32.55), which includes the effects from the macroscopic subsystem M. We write this effective interaction for the nanometric subsystem n as $V_{\mathrm{eff}}(\vec{r})$ in the following way:

$$V_{\mathrm{eff}}(\vec{r}) = -\frac{1}{4\pi^2}\sum_{\lambda=1}^{2}\sum_{\alpha=p,s}\int d^3k\left[\left(\vec{\mu}_p\cdot\vec{e}_\lambda(\vec{k})\right)\left(\vec{\mu}_s\cdot\vec{e}_\lambda(\vec{k})\right)\right] \times \hbar f^2(k)\left(\frac{e^{i\vec{k}\cdot\vec{r}}}{E(k)+E_\alpha} + \frac{e^{-i\vec{k}\cdot\vec{r}}}{E(k)-E_\alpha}\right) \tag{32.56}$$

where we have set $E(k) = \hbar\Omega(k)$, and $E_\alpha = \hbar\Omega_0(a^*) - \hbar\Omega_0(\alpha)$ for $\alpha = p$ and $\alpha = s$. The summation over polarization λ is performed as

$$\sum_{\lambda=1}^{2}\vec{e}_{\lambda i}(\vec{k})\vec{e}_{\lambda i}(\vec{k}) = \delta_{ij} - k_i k_j, \tag{32.57}$$

and thus the summation of $\left(\vec{\mu}_p\cdot\vec{e}_\lambda(\vec{k})\right)\left(\vec{\mu}_s\cdot\vec{e}_\lambda(\vec{k})\right)$ over λ can be reduced as follows:

$$\sum_{\lambda=1}^{2}\left(\vec{\mu}_p\cdot\vec{e}_\lambda(\vec{k})\right)\left(\vec{\mu}_s\cdot\vec{e}_\lambda(\vec{k})\right) = \sum_{\lambda=1}^{2}\sum_{i,j}\left(\vec{\mu}_{pi}\vec{e}_{\lambda i}(\vec{k})\right)\left(\vec{\mu}_{sj}\vec{e}_{\lambda j}(\vec{k})\right) = \sum_{i,j}\mu_{pi}\mu_{sj}\left(\delta_{ij} - \hat{k}_i\hat{k}_j\right) \tag{32.58}$$

with the unit vector $\hat{k} \equiv \vec{k}/k$. Noticing that $d^3k = k^2dkd\Omega = k^2dk \sin\theta d\theta d\varphi$ and

$$\delta_{ij}\int e^{\pm i\vec{k}\cdot\vec{r}}d\Omega = \delta_{ij}\int_0^{2\pi}\int_{-1}^{1} e^{\pm ikr\cos\theta}d(\cos\theta)d\varphi = \delta_{ij}\frac{2\pi}{ikr}(e^{ikr} - e^{-ikr}), \tag{32.59a}$$

$$-\int \hat{k}_i\hat{k}_j e^{\pm i\vec{k}\cdot\vec{r}}d\Omega = \frac{1}{k^2}\nabla_i\nabla_j\int e^{\pm i\vec{k}\cdot\vec{r}}d\Omega = \frac{2\pi}{ik^3}\nabla_i\nabla_j\left(\frac{e^{ikr} - e^{-ikr}}{r}\right), \tag{32.59b}$$

we find

$$\int(\delta_{ij} - \hat{k}_i\hat{k}_j)e^{\pm i\vec{k}\cdot\vec{r}}d\Omega = \delta_{ij}\frac{2\pi}{ik}\left(\frac{e^{ikr} - e^{-ikr}}{r}\right) + \frac{2\pi}{ik^3}\nabla_i\nabla_j\left(\frac{e^{ikr} - e^{-ikr}}{r}\right)$$
$$= 2\pi\left[\delta_{ij}\frac{(e^{ikr} - e^{-ikr})}{ikr} + (\delta_{ij} - 3\hat{r}_i\hat{r}_j)\left\{\frac{(e^{ikr} + e^{-ikr})}{k^2r^2} - \frac{(e^{ikr} - e^{-ikr})}{ikr^3r^3}\right\} - \frac{(e^{ikr} - e^{-ikr})}{ikr}\hat{r}_i\hat{r}_j\right] \tag{32.60}$$

where $\hat{r}$ is the unit vector defined by $\hat{r} \equiv \hat{r}/r$, and the jth component is denoted by $\hat{r}_j$. Hence, the effective interaction can be rewritten as

$$V_{\mathrm{eff}}(\vec{r}) = -\frac{1}{2\pi}\int_{-\infty}^{\infty}k^2dk\hbar f^2(k)\sum_{a=s,p}\left(\frac{1}{E(k)+E_a} + \frac{1}{E(k)-E_a}\right) \times\left\{(\vec{\mu}_s\cdot\vec{\mu}_p)e^{i\vec{k}\cdot\vec{r}}\left(\frac{1}{ikr} + \frac{1}{k^2r^2} - \frac{1}{ik^3r^3}\right) - (\vec{\mu}_s\cdot\hat{r})(\vec{\mu}_p\cdot\hat{r})e^{i\vec{k}\cdot\vec{r}} \times\left(\frac{1}{ikr} + \frac{3}{k^2r^2} - \frac{3}{ik^3r^3}\right)\right\} \tag{32.61}$$

where the integration range is extended from (0, ∞) to (−∞, ∞). When the dispersion relation of exciton polaritons, which have been chosen as a basis for describing the macroscopic subsystem M, is approximated as

$$E(k) = \hbar\Omega + \frac{(\hbar k)^2}{2m_{\mathrm{pol}}} = E_m + \frac{(\hbar ck)^2}{2E_{\mathrm{pl}}}, \tag{32.62}$$

in terms of the effective mass of exciton polaritons, m_{pol}, or $E_{\mathrm{pl}} = m_{\mathrm{pol}}c^2$ and the electronic excitation energy of the macroscopic subsystem M, $E_m = \hbar\Omega$, (32.61) is further simplified:

$$V_{\mathrm{eff}}(\vec{r}) = -\frac{1}{2\pi}\int_{-\infty}^{\infty}k^2dk\hbar f^2(k)\sum_{\alpha=s,p}\frac{2E_{\mathrm{pl}}}{(\hbar c)^2} \times\left\{\frac{1}{(k+i\Delta_{\alpha+})(k-i\Delta_{\alpha+})} + \frac{1}{(k+i\Delta_{\alpha-})(k-i\Delta_{\alpha-})}\right\}$$
$$\times\left\{(\vec{\mu}_s\cdot\vec{\mu}_p)e^{i\vec{k}\cdot\vec{r}}\left(\frac{1}{ikr} + \frac{1}{k^2r^2} - \frac{1}{ik^3r^3}\right) - \left(\vec{\mu}_s\cdot\hat{r}\right)\left(\vec{\mu}_p\cdot\hat{r}\right)e^{i\vec{k}\cdot\vec{r}} \times\left(\frac{1}{ikr} + \frac{3}{k^2r^2} - \frac{3}{ik^3r^3}\right)\right\}$$
$$\equiv \sum_{\alpha=s,p}\left[V_{\mathrm{eff},\alpha+}(\vec{r}) + V_{\mathrm{eff},\alpha-}(\vec{r})\right] \tag{32.63a}$$

with

$$\Delta_{\alpha\pm} \equiv \frac{1}{\hbar c}\sqrt{2E_{\mathrm{pl}}(E_m \pm E_\alpha)}, \quad (E_m > E_\alpha). \tag{32.63b}$$

The k-integration can be performed with the residues evaluated at $k = i\Delta_{\alpha\pm}$, and we have

$$\begin{aligned} V_{\mathrm{eff},\alpha\pm}(\vec{r}) = \mp\frac{1}{2}\Bigg[&(\vec{\mu}_s\cdot\vec{\mu}_p)\left\{\frac{(\Delta_{\alpha\pm})^2}{r} + \frac{\Delta_{\alpha\pm}}{r^2} + \frac{1}{r^3}\right\} W_{\alpha\pm} e^{-\Delta_{\alpha\pm} r} \\ &-(\vec{\mu}_s\cdot\hat{r})(\vec{\mu}_p\cdot\hat{r})\left\{\frac{(\Delta_{\alpha\pm})^2}{r} + \frac{3\Delta_{\alpha\pm}}{r^2} + \frac{3}{r^3}\right\} W_{\alpha\pm} e^{-\Delta_{\alpha\pm} r}\Bigg], \end{aligned} \tag{32.64a}$$

where the constants $W_{\alpha\pm}$ are defined by

$$W_{\alpha\pm} \equiv \frac{E_{\mathrm{pl}}}{E_\alpha}\frac{E_m^2 - E_\alpha^2}{(E_m \pm E_\alpha)(E_m - E_{\mathrm{pl}} \mp E_\alpha) - E_m^2/2}. \tag{32.64b}$$

If the angular average of $(\vec{\mu}_s\cdot\hat{r})(\vec{\mu}_p\cdot\hat{r})$ is taken, the expression

$$V_{\mathrm{eff}}(r) = -\frac{(\vec{\mu}_s\cdot\vec{\mu}_p)}{3}\sum_{\alpha=s,p}\left\{W_{\alpha+}(\Delta_{\alpha+})^2\frac{e^{-\Delta_{\alpha+}r}}{r} - W_{\alpha-}(\Delta_{\alpha-})^2\frac{e^{-\Delta_{\alpha-}r}}{r}\right\} \tag{32.65}$$

is obtained for the effective interaction, or the near-field optical interaction $V_{\mathrm{eff}}(r)$, which consists of the sum of the Yukawa functions $Y(\Delta_{\alpha\pm}r) \equiv e^{-\Delta_{\alpha\pm}r}/r$ with a shorter interaction range $\Delta_{\alpha+}$(heavier effective mass) and a longer interaction range $\Delta_{\alpha-}$(lighter effective mass).

To sum up, we find that the major part of the effective interaction exerted in the nanometric subsystem n is the Yukawa potential after renormalizing the effects from the macroscopic subsystem. This interaction comes from the mediation of massive virtual photons corresponding to the counter-rotating term, or polaritons, where exciton polaritons have been employed in an explicit formulation, but in principle other types of polaritons would be applicable. In this section we have mainly focused on the effective interaction of the nanometric subsystem n, after tracing out the other degrees of freedom. It is certainly possible to have a formulation with a projection onto the P space that is spanned in terms of the degrees of freedom of the massive virtual photons, although this is left as the subject of future work. This kind of formulation emphasizes a "dressed photon" picture, in which photons are not massless but massive, due to light–matter interactions at the nanoscale.

32.3.4 Localization of a Photon Dressed by Matter Excitation in Nanomaterials at the Nanoscale

In this section, we consider a simple model system, for example, a pseudo one-dimensional near-field optical probe system, to discuss the mechanism of photon localization in space as well as the phonon's role. In order to focus on the photon–phonon interaction, the interacting part between photon and electronic excitation is first expressed in terms of a polariton, and is called a photon in the model. Then the model Hamiltonian that describes the photon and phonon interacting system is presented. Using the Davydov transformation, we rewrite the Hamiltonian in terms of quasiparticles. On the basis of the Hamiltonian, we present numerical results on the spatial distribution of photons and discuss the mechanism of photon localization due to phonons.

32.3.4.1 Model Hamiltonian

We consider a near-field optical probe, schematically shown in Figure 32.3, as an example system where light interacts with both phonons and electrons in the probe on a nanometer scale. Here, the interaction of a photon and an electronic excitation is assumed to be expressed in terms of a polariton basis, as discussed above, and is hereafter called a photon so that special attention is paid to the photon–phonon interaction. The system is simply modeled as a one-dimensional atomic or molecular chain coupled with photon and phonon fields. The chain consists of finite N molecules (representatively called), each of which is located at a discrete point (called a molecular site) whose separation represents a characteristic scale of the near-field system. Photons are expressed in the site representation and can hop to the nearest neighbor sites due to the short-range interaction nature of the optical near fields.

The Hamiltonian for the above model is given by

$$\begin{aligned} \hat{H} = \sum_{i=1}^{N}\hbar\omega\hat{a}_i^\dagger\hat{a}_i + \left\{\sum_{i=1}^{N}\frac{\hat{p}_i^2}{2m_i} + \sum_{i=1}^{N-1}\frac{k}{2}(\hat{x}_{i+1} - \hat{x}_i)^2 + \sum_{i=1,N}\frac{k}{2}\hat{x}_i^2\right\} \\ + \sum_{i=1}^{N}\hbar\chi\hat{a}_i^\dagger\hat{a}_i\hat{x}_i + \sum_{i=1}^{N-1}\hbar J\left(\hat{a}_i^\dagger\hat{a}_{i+1} + \hat{a}_{i+1}^\dagger\hat{a}_i\right), \end{aligned} \tag{32.66}$$

where

$\hat{a}_i^\dagger$ and $\hat{a}_i$ correspondingly denote the creation and annihilation operators of a photon with energy $\hbar\omega$ at site i in the chain

$\hat{x}_i$ and $\hat{p}_i$ represent the displacement and conjugate momentum operators of the vibration, respectively



FIGURE 32.3 Simple one-dimensional model for a light–matter interacting system on a nanometer scale.

The mass of a molecule at site i is designated by m_i, and each molecule is assumed to be connected by springs with spring constant k. The third and fourth terms in (32.66) stand for the photon–vibration interaction with coupling constant χ and the photon hopping with hopping constant J, respectively. After the vibration field is quantized in terms of phonon operators of mode p and frequency Ω_p, $\hat{b}_p^\dagger$, and $\hat{b}_p$, the Hamiltonian (32.66) can be rewritten as

$$\hat{H} = \sum_{i=1}^{N} \hbar\omega \hat{a}_i^\dagger \hat{a}_i + \sum_{p=1}^{N} \hbar\Omega_p \hat{b}_p^\dagger \hat{b}_p + \sum_{i=1}^{N}\sum_{p=1}^{N} \hbar\chi_{ip} \hat{a}_i^\dagger \hat{a}_i (\hat{b}_p^\dagger + \hat{b}_p) + \sum_{i=1}^{N-1} \hbar J (\hat{a}_i^\dagger \hat{a}_{i+1} + \hat{a}_{i+1}^\dagger \hat{a}_i), \tag{32.67}$$

with the coupling constant χ_{ip} of a photon at site i and a phonon of mode p. It should be noted that the index p designates not the momentum but the mode number, because the translational invariance of the system is broken and the momentum is not a good quantum number. The site-dependent coupling constant χ_{ip} is related to the original coupling constant χ in terms of the transformation matrix as P_{ip} as

$$\chi_{ip} = \chi P_{ip} \sqrt{\frac{\hbar}{2m_i\Omega_p}}, \tag{32.68}$$

and the creation and annihilation operators of a photon and a phonon satisfy the boson commutation relation as $\left[\hat{a}_i, \hat{a}_j^\dagger\right] = \delta_{ij}$ and $\left[\hat{b}_p, \hat{b}_q^\dagger\right] = \delta_{pq}$. The Hamiltonian (32.67), which describes the model system, is not easily handled because of the third order of the operators in the interaction term. To avoid this difficulty, this direct photon–phonon interaction term in (32.67) is eliminated by the Davydov transformation in the following subsection.

32.3.4.2 Davydov Transformation

Before going into the explicit expression, we discuss a unitary transformation $\hat{U}$ generated by an anti-Hermitian operator $\hat{S}$, defined as

$$\hat{U} \equiv \exp(\hat{S}), \quad \text{with } \hat{S}^\dagger = -\hat{S} \tag{32.69a}$$

and

$$\hat{U}^\dagger = \hat{U}^{-1}. \tag{32.69b}$$

Assume a Hamiltonian $\hat{H}$ that consists of a diagonalized part $\hat{H}_0$ and a non-diagonal interaction part $\hat{V}$:

$$\hat{H} = \hat{H}_0 + \hat{V}. \tag{32.70}$$

Transforming the Hamiltonian in (32.70) as

$$\tilde{H} \equiv \hat{U}\hat{H}\hat{U}^\dagger = \hat{U}\hat{H}\hat{U}^{-1}, \tag{32.71}$$

we have

$$\begin{aligned}\tilde{H} &= \hat{H} + [\hat{S}, \hat{H}] + \frac{1}{2}\left[\hat{S}, [\hat{S}, \hat{H}]\right] + \cdots \\ &= \hat{H}_0 + \hat{V} + [\hat{S}, \hat{H}_0] + [\hat{S}, \hat{V}] + \frac{1}{2}\left[\hat{S}, [\hat{S}, \hat{H}_0]\right] + \cdots.\end{aligned} \tag{32.72}$$

If the interaction $\hat{V}$ can be perturbative, and if the operator $\hat{S}$ is chosen so that the second and third terms in (32.72) are canceled out, then

$$\hat{V} = -[\hat{S}, \hat{H}_0], \tag{32.73}$$

the Hamiltonian (32.70) is rewritten as

$$\tilde{H} = \hat{H}_0 - \frac{1}{2}\left[\hat{S}, [\hat{S}, \hat{H}_0]\right] + \cdots, \tag{32.74}$$

and can be diagonalized within the first order of $\hat{V}$.

Now we apply the above discussion to the model Hamiltonian (32.67),

$$\hat{H}_0 = \sum_{i=1}^{N} \hbar\omega \hat{a}_i^\dagger \hat{a}_i + \sum_{p=1}^{N} \hbar\Omega_p \hat{b}_p^\dagger \hat{b}_p, \tag{32.75a}$$

$$\hat{V} = \sum_{i=1}^{N}\sum_{p=1}^{N} \hbar\chi_{ip} \hat{a}_i^\dagger \hat{a}_i (\hat{b}_p^\dagger + \hat{b}_p), \tag{32.75b}$$

tentatively neglecting the hopping term. Assuming the anti-Hermitian operator $\hat{S}$

$$\hat{S} = \sum_{i}\sum_{p} f_{ip} \hat{a}_i^\dagger \hat{a}_i (\hat{b}_p^\dagger - \hat{b}_p), \tag{32.76a}$$

we can determine f_{ip} from (32.73) as follows:

$$f_{ip} = \frac{\chi_{ip}}{\Omega_p}. \tag{32.76b}$$

This operator form of $\hat{S}$ leads us to not the perturbative but the exact transformation of the photon and phonon operators:

$$\hat{\alpha}_i^\dagger \equiv \hat{U}^\dagger \hat{a}_i^\dagger \hat{U} = \hat{a}_i^\dagger \exp\left\{-\sum_{p=1}^{N} \frac{\chi_{ip}}{\Omega_p}\left(\hat{b}_p^\dagger - \hat{b}_p\right)\right\}, \tag{32.77a}$$

$$\hat{\alpha}_i \equiv \hat{U}^\dagger \hat{a}_i \hat{U} = \hat{a}_i \exp\left\{\sum_{p=1}^{N} \frac{\chi_{ip}}{\Omega_p}(\hat{b}_p^\dagger - \hat{b}_p)\right\}, \quad (32.77b)$$

$$\hat{\beta}_p^\dagger \equiv \hat{U}^\dagger \hat{b}_p^\dagger \hat{U} = \hat{b}_p^\dagger + \sum_{i=1}^{N} \frac{\chi_{ip}}{\Omega_p} \hat{a}_i^\dagger \hat{a}_i, \quad (32.77c)$$

$$\hat{\beta}_p \equiv \hat{U} \hat{b}_p \hat{U}^\dagger = \hat{b}_p + \sum_{i=1}^{N} \frac{\chi_{ip}}{\Omega_p} \hat{a}_i^\dagger \hat{a}_i. \quad (32.77d)$$

These transformed operators can be regarded as the creation and annihilation operators of quasiparticles—dressed photons and phonons—that satisfy the same boson commutation relations as those of photons and phonons before the transformation, namely, $\left[\hat{\alpha}_i, \hat{\alpha}_j^\dagger\right] = \hat{U}^\dagger \left[\hat{a}_i, \hat{a}_j\right] \hat{U} = \delta_{ij}$ and $\left[\hat{\beta}_p, \hat{\beta}_q^\dagger\right] = \hat{U}^\dagger \left[\hat{b}_p, \hat{b}_q^\dagger\right] \hat{U} = \delta_{pq}$.

Using the quasiparticle operators, we can rewrite the Hamiltonian (32.67) as

$$\hat{H} = \sum_{i=1}^{N} \hbar\omega \hat{\alpha}_i^\dagger \hat{\alpha}_i + \sum_{p=1}^{N} \hbar\Omega_p \hat{\beta}_p^\dagger \hat{\beta}_p - \sum_{i=1}^{N}\sum_{j=1}^{N}\sum_{p=1}^{N} \frac{\hbar\chi_{ip}\chi_{jp}}{\Omega_p} \hat{\alpha}_i^\dagger \hat{\alpha}_i \hat{\alpha}_j^\dagger \hat{\alpha}_j$$

$$+ \sum_{i=1}^{N-1} \hbar\left(\hat{J}_i \hat{\alpha}_i^\dagger \hat{\alpha}_{i+1} + \hat{J}_i^\dagger \hat{\alpha}_{i+1}^\dagger \hat{\alpha}_i\right), \quad (32.78a)$$

with

$$\hat{J}_i = J \exp\left\{\sum_{p=1}^{N} \frac{(\chi_{ip} - \chi_{i+1p})}{\Omega_p} (\hat{\beta}_p^\dagger - \hat{\beta}_p)\right\}, \quad (32.78b)$$

where it is noted that the direct photon–phonon coupling term has been eliminated, while the quadratic form $\hat{N}_i \hat{N}_j$ with the number operator of $\hat{N}_i = \hat{\alpha}_i^\dagger \hat{\alpha}_i$ has emerged as well as the site-dependent hopping operator $\hat{J}_i$ in (32.78b). The number states of quasiparticles are thus eigenstates of each terms of the Hamiltonian (32.78a), except the last term that represents the higher-order effect of photon–phonon coupling through the dressed photon hopping. Therefore, it is a more appropriate form to discuss the phonon's effect on photon's behavior as localization.

32.3.4.3 Quasiparticle and Coherent State

In the previous section, we have transformed the original Hamiltonian with the Davydov transformation. In order to grasp the physical meanings of the quasiparticles introduced above, the creation operator $\hat{\alpha}_i^\dagger$ is applied to the vacuum state $|0\rangle$. Then, it follows from (32.77a) that

$$\hat{\alpha}_i^\dagger |0\rangle = \hat{a}_i^\dagger \exp\left\{-\sum_{p=1}^{N} \frac{\chi_{ip}}{\Omega_p}\left(\hat{b}_p^\dagger - \hat{b}_p\right)\right\}|0\rangle,$$

$$= \hat{a}_i^\dagger \exp\left\{-\sum_{p=1}^{N} \frac{1}{2}\left(\frac{\chi_{ip}}{\Omega_p}\right)^2\right\} \exp\left\{-\frac{\chi_{ip}}{\Omega_p} \hat{b}_p^\dagger\right\}|0\rangle, \quad (32.79)$$

where a photon at site i is associated with phonons in a coherent state, i.e., a photon is dressed by an infinite number of phonons. This corresponds to the fact that an optical near field is generated from a result of interactions between the photon and matter fields.

When $\hat{\beta}_p^\dagger$ is applied to the vacuum state $|0\rangle$, we have

$$\hat{\beta}_p^\dagger |0\rangle = \hat{b}_p^\dagger |0\rangle, \quad (32.80)$$

and it is expressed by only the bare phonon operator (before the transformation) in the same p mode. Therefore, we mainly focus on the quasiparticle expressed by $(\hat{\alpha}_i^\dagger, \hat{\alpha}_i)$ in the following subsection. Note that it is valid only if the bare photon number (the expectation value of $\hat{\alpha}_i^\dagger \hat{\alpha}_i$ is not so large that the fluctuation is more important than the bare photon number. In other words, the model we are considering is suitable for discussing the quantum nature of a few photons in an optically excited probe system.

In the coherent state of phonons, the number of phonons, as well as energy, is fluctuating. This fluctuation allows incident photons into the probe system to excite phonon fields. When all the phonons are in the vacuum state at time $t = 0$, the excitation probability $P(t)$ that a photon incident on site i in the model system excites the phonon mode p at time t is given by

$$P(t) = 1 - \exp\left\{2\left(\frac{\chi_{ip}}{\Omega_p}\right)^2 \left[\cos(\Omega_p t) - 1\right]\right\}, \quad (32.81)$$

where the photon-hopping term is neglected for simplicity. The excitation probability oscillates at a frequency of $2\pi/\Omega_p$ and has the maximum value at $t = \pi/\Omega_p$. The frequencies of the localized phonon modes are higher than those of the delocalized ones, and the localized modes at the earlier time are excited by the incident photons.

Figure 32.4 shows the temporal evolution of the excitation probability $P_{p_0}(t)$ calculated from

$$P_{p_0}(t) = \left[1 - \exp\left\{2\left(\frac{\chi_{ip_0}}{\Omega_{p_0}}\right)^2 \left[\cos(\Omega_{p_0} t) - 1\right]\right\}\right]$$

$$\times \exp\left\{\sum_{p \neq p_0} 2\left(\frac{\chi_{ip}}{\Omega_p}\right)^2 \left[\cos(\Omega_p t) - 1\right]\right\}, \quad (32.82)$$

where a specific phonon mode p_0 is excited, while other modes are in the vacuum state. In Figure 32.4, the solid curve represents the probability that a localized phonon mode is excited as the p_0 mode, while the dashed curve illustrates how the lowest phonon mode is excited as the p_0 mode. It follows from the figure that the localized phonon mode is dominantly excited at an earlier time.



FIGURE 32.4 Temporal evolution of a specific phonon mode. The solid curve represents the probability for a localized phonon mode, while the dashed curve shows that of the lowest delocalized phonon mode.

32.3.4.4 Localization Mechanism of Dressed Photons

In this section, we discuss how phonons contribute to the spatial distribution of photons in the pseudo one-dimensional system under consideration. When there are no interactions between photons and phonons, the frequency and hopping constant are equal at all sites, and thus the spatial distribution of photons is symmetric. It means that no photon localization occurs at any specific site. However, if there are any photon–phonon interactions, spatial inhomogeneity or localization of phonons affects the spatial distribution of photons. On the basis of the Hamiltonian (32.78a), we analyze the contribution from the diagonal (the third term) and off-diagonal (the fourth term) parts of the Hamiltonian (32.78a) in order to investigate the localization mechanism of photons.

32.3.4.4.1 Contribution from the Diagonal Part

Let us rewrite the third term of the Hamiltonian (32.78a) with the mean field approximation as

$$-\sum_{i=1}^{N}\sum_{j=1}^{N}\sum_{p=1}^{N}\frac{\hbar\chi_{ip}\chi_{jp}}{\Omega_p}\hat{\alpha}_i^{\dagger}\hat{\alpha}_i\left\langle\hat{\alpha}_j^{\dagger}\hat{\alpha}_j\right\rangle \equiv -\sum_{i=1}^{N}\hbar\omega_i\hat{\alpha}_i^{\dagger}\hat{\alpha}_i, \qquad (32.83a)$$

with

$$\omega_i = \sum_{j=1}^{N}\sum_{p=1}^{N}\frac{\chi_{ip}\chi_{jp}}{\Omega_p}\left\langle\hat{\alpha}_j^{\dagger}\hat{\alpha}_j\right\rangle. \qquad (32.83b)$$

In addition, for the moment, we neglect the site dependence of the hopping operator $\hat{J}_i$, which is approximated as J. Then the Hamiltonian regarding the quasiparticles ($\hat{\alpha}$ and $\hat{\alpha}^{\dagger}$) can be expressed as

$$\hat{H} = \sum_{i=1}^{N}\hbar(\omega-\omega_i)\hat{\alpha}_i^{\dagger}\hat{\alpha}_i + \sum_{i=1}^{N-1}\hbar J\left(\hat{\alpha}_i^{\dagger}\hat{\alpha}_{i+1}+\hat{\alpha}_{i+1}^{\dagger}\hat{\alpha}_i\right), \qquad (32.84)$$

or in matrix form as

$$\hat{H} = \hbar\hat{\vec{\alpha}}^{\dagger}\begin{pmatrix} \omega-\omega_1 & J & \cdots & 0 \\ J & \omega-\omega_2 & \ddots & \vdots \\ \vdots & \ddots & \ddots & J \\ 0 & \cdots & J & \omega-\omega_N \end{pmatrix}\hat{\vec{\alpha}} \qquad (32.85a)$$

with

$$\hat{\vec{\alpha}} \equiv \left(\hat{\alpha}_1^{\dagger},\hat{\alpha}_2^{\dagger},\ldots,\hat{\alpha}_N^{\dagger}\right), \qquad (32.85b)$$

where the effect from the phonon fields is involved in the diagonal elements ω_i. Denoting an orthonormal matrix to diagonalize the Hamiltonian (32.85a) as Q and the rth eigenvalue as E_r, we have

$$\hat{H} = \sum_{r=1}^{N}\hbar E_r\hat{A}_r^{\dagger}\hat{A}_r \qquad (32.86a)$$

with

$$\hat{A}_r\sum_{i=1}^{N}(\mathrm{Q}^{-1})_{ri}\hat{\alpha}_i = \sum_{i=1}^{N}\mathrm{Q}_{ir}\hat{\alpha}_i, \qquad (32.86b)$$

and

$$\left[\hat{A}_r,\hat{A}_s^{\dagger}\right] \equiv \hat{A}_r\hat{A}_s^{\dagger} - \hat{A}_s^{\dagger}\hat{A}_r = \delta_{rs}. \qquad (32.86c)$$

Using the above relations (32.86a) through (32.86c), we can write down the time evolution of the photon number operator $\hat{N}_i$ at site i as follows:

$$\begin{aligned}\hat{N}_i(t) &= \exp\left(i\frac{\hat{H}}{\hbar}t\right)\hat{N}_i\exp\left(-i\frac{\hat{H}}{\hbar}t\right) \\ &= \sum_{r=1}^{N}\sum_{s=1}^{N}\mathrm{Q}_{ir}\mathrm{Q}_{is}\hat{A}_r^{\dagger}\hat{A}_s\exp\left\{i(E_r-E_s)t\right\}. \qquad (32.87)\end{aligned}$$

The expectation value of the photon number operator $\hat{N}_i(t)$ is then given by

$$\left\langle N_i(t)\right\rangle_j \equiv \left\langle\psi_j\middle|\hat{N}_i(t)\middle|\psi_j\right\rangle = \sum_{r=1}^{N}\sum_{s=1}^{N}\mathrm{Q}_{ir}\mathrm{Q}_{jr}\mathrm{Q}_{is}\mathrm{Q}_{js}\cos\left\{(E_r-E_s)t\right\}, \qquad (32.88)$$

in terms of one photon state at site j defined by

$$\left|\psi_j\right\rangle = \hat{\alpha}_j^\dagger\left|0\right\rangle = \sum_{r=1}^{N} \mathrm{Q}_{jr}\hat{A}_r^\dagger\left|0\right\rangle. \tag{32.89}$$

Since the photon number operator $\hat{N}_i$ commutes with the Hamiltonian (32.84), the total photon number is conserved, which means that a polariton, called a photon in this section, conserves the total particle number within the lifetime. Moreover, $\langle N_i(t)\rangle_j$ can be regarded as the observation probability of a photon at an arbitrary site i and time t, initially populated at site j. This function is analytically expressed in terms of the Bessel functions $J_{j\pm i}$:

$$\left\langle N_i(t)\right\rangle_j = \left\{J_{j-i}(2Jt) - (-1)^i J_{j+i}(2Jt)\right\}^2, \tag{32.90}$$

when there are no photon–phonon interactions ($\omega_i = 0$) and the total site number N becomes infinite. Here the argument J is the photon hopping constant, and (32.90) shows that a photon initially populated at site j delocalizes to the whole system.

Focusing on the localized phonon modes, we take the summation in (32.83b) over the localized modes only, which means that an earlier stage is considered after the incident photon excites the phonon modes, or that the duration of the localized phonon modes that are dominant over the delocalized modes is focused on (see Figure 32.4). This kind of analysis provides us with an interesting insight into the photon–phonon coupling constant and the photon hopping constant, which is necessary for understanding the mechanism of photon localization.

The temporal evolution of the observation probability of a photon at each site is shown in Figure 32.5. Without the photon–phonon coupling ($\chi = 0$), a photon spreads over the whole system as a result of the photon hopping, as shown in Figure 32.5a. Here the photon energy $\hbar\omega = 1.81\,\text{eV}$ and the hopping constant $\hbar J = 0.5\,\text{eV}$ are used in the calculation. Impurities are assumed to be doped at sites 3, 7, 11, 15, and 19, while the total number of sites N is 20, and the mass ratio of the host molecules to the impurities is 5. Figure 32.5b shows a result with $\chi = 1.4 \times 10^3$ fs^{-1} nm^{-1}; the other parameters used are the same as those in Figure 32.5a. It follows from the figure that a photon moves from one impurity site to another impurity site instead of delocalizing to the whole system. As the photon–phonon coupling constant becomes much larger than $\chi = 1.4 \times 10^3$ fs^{-1} nm^{-1}, a photon cannot move from the initial impurity site to others, but stays there.

The effect due to the photon–phonon coupling constant χ is expressed by the diagonal component in the Hamiltonian, while the off-diagonal component involves the photon hopping effect due to the hopping constant J. The above results indicate that a photon's spatial distribution depends on the competition between the diagonal and off-diagonal components in the Hamiltonian, i.e., χ and J, and that a photon can move among impurity sites and localize at those sites when both components are comparable under the condition

$$\chi \sim N\sqrt{\frac{kJ}{\hbar}}, \tag{32.91}$$

where the localization width seems very narrow.

32.3.4.4.2 Contribution from the Off-Diagonal Part

In the previous subsection, we have approximated J as a constant independent of the sites, in order to examine the photon's spatial distribution as well as the mechanism of the photon localization. Now let us treat the photon hopping operator $\hat{J}_i$ more rigorously, and investigate the site dependence of the off-diagonal contribution, which includes the inhomogeneity of the phonon fields. Noticing that a quasiparticle transformed from a photon



FIGURE 32.5 **(See color insert following page 20-14.)** Probability that a photon is found at each site as a function of time (a) without the photon–phonon coupling, and (b) with the photon–phonon coupling comparable to the photon hopping constant.

operator by the Davydov transformation is associated with phonons in the coherent state (see (32.77a) and (32.77b)), we take expectation values of $\hat{J}_i$ in terms of the coherent state of phonons $|\gamma\rangle$ as

$$J_i \equiv \langle\gamma|\hat{J}_i|\gamma\rangle. \tag{32.92}$$

Here, the coherent state $|\gamma\rangle$ is an eigenstate of the annihilation operator $\hat{b}_p$ with eigenvalue γ_p and satisfies

$$\hat{b}_p|\gamma\rangle = \gamma_p|\gamma\rangle. \tag{32.93}$$

Since the difference between the creation and annihilation operators of a phonon is invariant under the Davydov transformation, the following relation holds:

$$\hat{\beta}_p^\dagger - \hat{\beta}_p = \hat{b}_p^\dagger - \hat{b}_p. \tag{32.94}$$

Using (32.78b), (32.93), and (32.94), we can rewrite the site-dependent hopping constant J_i in (32.92) as

$$\begin{aligned} J_i &= J\langle\gamma|\exp\left\{\sum_{p=1}^{N} C_{ip}\left(b_p^\dagger - b_p\right)\right\}|\gamma\rangle \\ &= J\exp\left(-\frac{1}{2}\sum_{p=1}^{N} C_{ip}^2\right)\langle\gamma|\exp\left(\sum_{p'=1}^{N} C_{ip'}\hat{b}_{p'}^\dagger\right)\exp\left(-\sum_{p''=1}^{N} C_{ip''}\hat{b}_{p''}\right)|\gamma\rangle \\ &= J\exp\left(-\frac{1}{2}\sum_{p=1}^{N} C_{ip}^2\right), \end{aligned} \tag{32.95a}$$

where C_{ip} is denoted by

$$C_{ip} \equiv \frac{\chi_{ip} - \chi_{i+1p}}{\Omega_p}. \tag{32.95b}$$

Figure 32.6 shows the site dependence of J_i in the case of $N = 20$. Impurities are doped at sites 4, 6, 13, and 19. The mass ratio of the host molecules to the impurities is 5, while $\hbar J = 0.5\,\text{eV}$ and $\chi = 14.0\,\text{fs}^{-1}\,\text{nm}^{-1}$ are used. It follows from the figure that the hopping constants are highly modified around the impurity sites and the edge sites. The result implies that photons are strongly affected by localized phonons and hop to the impurity sites to localize. Here we have not considered the temperature dependence of J_i, which is important for phenomena dominated by incoherent phonons. This is because coherent phonons weakly depend on the temperature of the system. However, there remains room to discuss a more fundamental issue, i.e., whether the probe system is in a thermal equilibrium state or not.



FIGURE 32.6 Site dependence of the hopping constant J_i in the case of $N = 20$. Impurities are doped at sites 4, 6, 13, and 19. The mass ratio of the host molecules to the impurities is 1–0.2, whereas $\hbar J = 0.5\,\text{eV}$ and $\chi = 40.0\,\text{fs}^{-1}\,\text{nm}^{-1}$ are used.



FIGURE 32.7 Probability of photons observed at each site. The filled squares, circles, and triangles represent the results for $\chi = 0$, 40.0, and $54.0\,\text{fs}^{-1}\,\text{nm}^{-1}$, respectively. Other parameters are the same as Figure 32.6.

In Figure 32.7, we present a typical result that photons localize around the impurity sites in the system as the photon–phonon coupling constants χ vary from 0 to $40.0\,\text{fs}^{-1}\,\text{nm}^{-1}$ or $54.0\,\text{fs}^{-1}\,\text{nm}^{-1}$, while keeping $\hbar J = 0.5\,\text{eV}$. As depicted by the filled squares in the figure, photons delocalize and spread over the system without the photon–phonon couplings. When the photon–phonon couplings are comparable to the hopping constants, $\chi = 40.0\,\text{fs}^{-1}\,\text{nm}^{-1}$, photons can localize around the impurity site with a finite width and two sites at half width and half maximum (HWHM), as shown by the filled circles. This finite width of photon localization comes from the site-dependent hopping constants. As the photon–phonon couplings are larger than $\chi = 40.0\,\text{fs}^{-1}\,\text{nm}^{-1}$, photons can localize at the edge sites with a finite width, as well as the impurity sites. In Figure 32.7, the photon localization at the edge site, shown by the filled triangles, originates from the finite size effect of the molecular chain. This kind of localization of photons dressed by the coherent state of phonons leads us to a simple understanding of phonon-assisted photodissociation using an optical near field: molecules in the electronic ground state approach the probe tip within the localization range of the dressed photons, and can be vibrationally excited by the dressed-photon transfer to the molecules, via a multi-phonon component of the dressed photons, which might be followed by electronic excitation. Thus, it leads to the dissociation of the molecules even if an incident photon energy less than the dissociation energy is used.

As a natural extension of the localized photon model, we have discussed the inclusion of the phonon's effects into the model. The study was initially motivated by experiments on the photodissociation of molecules by optical near fields, whose results show unique features different from the conventional one with far fields (Ohtsu et al. 2008). After clarifying whether the vibration modes in a pseudo one-dimensional system are delocalized or localized, we focused on the interaction between dressed photons and phonons by using the Davydov transformation. We have theoretically shown that photons are dressed by the coherent state of phonons, and found that the competition between the photon–phonon coupling constant and the photon hopping constant governs the photon localization or delocalization in space. The obtained results lead us to a simple understanding of an optical near field itself as an interacting system of photon, electronic excitation (induced polarization), and phonon fields in a nanometer space, which are surrounded by macroscopic environments, as well as phonon-assisted photodissociation using an optical near field.

32.4 Summary and Future Perspective

We have briefly outlined the difficulties in defining the position-representation wave function of a photon, followed by several trials to overcome these issues. On the basis of canonical quantization of the electromagnetic fields in free space, we have discussed a dressing mechanism and spatial localization of photons, which is a natural viewpoint from light–matter interactions, or from virtual photon clouds and field correlations. Finally, with the projection operator method, we have shown an effective interaction between nanomaterials electronically disconnected, but closely separated, which are also surrounded by a macroscopic system, in order to detect the virtual clouds. We have discussed the photon dressing by material excitation and pointed out the importance of the phonon's role for spatial localization of photons at the nanoscale.

The pace of development in photonics has accelerated, but most of the underlying science of the field is still Maxwell's classical electromagnetism, not field-quantized photons. In the near future, however, we are anticipating new breakthroughs in nano- and atom photonics, where the localized and quantized nature of photons, as well as an exact quantization formulation for an optical near-field system, including relaxation processes at the nanoscale, will play a critical role.

Acknowledgments

The author is grateful to M. Ohtsu (University of Tokyo) and H. Hori (University of Yamanashi) for stimulating discussions and valuable comments from the early stage of this study. He is also thankful to S. Sangu (Ricoh Co. Ltd.), A. Shojiguchi (NEC Co.), Y. Tanaka (Tokyo Institute of Technology), and A. Sato (Tokyo Institute of Technology) for discussions and collaborations. He greatly acknowledges the valuable guidance given by M. Tsukada (University of Tokyo, emeritus, Tohoku University), K. Kitahara (Tokyo Institute of Technology, emeritus, International Christian University), M. Kitano (Kyoto University), Y. Masumoto (University of Tsukuba), K. Cho (Osaka University, emeritus), and T. Yabuzaki (Kyoto University, emeritus). Finally but not the least, he expresses his gratitude to H. Ito (Tokyo Inst. Technology). T. Kawazoe (University of Tokyo), T. Yatsui (University of Tokyo), T. Saiki (Keio University), K. Matsuda (Kyoto University), H. Nejo (National Institute of Materials Science), M. Naruse (National Institute of Information and Communication Technology), M. Ikezawa (University of Tsukuba), I. Banno (University of Yamanashi), and H. Ishihara (Osaka Prefecture University).

References

Adlard, C., Pike, E. R., and Sarkar, S. 1997. Localization of one-photon states. *Phys. Rev. Lett.* 79: 1585–1587.

Bialynicki-Birula, I. 1998. Exponential localization of photons. *Phys. Rev. Lett.* 80: 5247–5250.

Carniglia, C. K. and Mandel, L. 1971. Quantization of evanescent electromagnetic waves. *Phys. Rev. D* 3: 280–296.

Cohen-Tannoudji, C., Dupont-Roc, I., and Grynberg, G. 1989. *Photons and Atoms*. New York: Wiley.

Cohen-Tannoudji, C., Dupont-Roc, I., and Grynberg, G. 1992. *Atom-Photon Interactions: Basic Processes and Applications*. New York: Wiley.

Compagno, G., Passante, R., and Persico, F. 1988. Dressed and half-dressed neutral sources in nonrelativistic QED. *Phys. Scr.* T21: 33–39.

Compagno, G., Passante, R., and Persico, F. 1995. *Atom-Field Interactions and Dressed Atoms*. Cambridge, NY: Cambridge University Press.

Craig, D. P. and Thirunamachandran, T. 1998. *Molecular Quantum Electrodynamics*. New York: Dover Pub.

Hawton, M. 1999. Photon wave functions in a localized coordinate space basis. *Phys. Rev. A* 59: 3223–3227.

Hegerfeldt, G. 1974. Remarks on causality and particle localization. *Phys. Rev. D* 10: 3320–3321.

Hellwarth, R. W. and Nouchi, P. 1996. Focused one-cycle electromagnetic pulses. *Phys. Rev. E* 54: 889–895.

Inagaki, T. 1998. Physical meaning of the photon wave function. *Phys. Rev. A* 57: 2204–2207.

Inoue, T. and Hori, H. 2001. Quantization of evanescent electromagnetic waves based on detector modes. *Phys. Rev. A* 63: 063805(1)–063805(16).

John, S. and Quang, T. 1995. Photon-hopping conduction and collectively induced transparency in a photonic band gap. *Phys. Rev. A* 52: 4083–4088.

Keller, O. 2005. On the theory of spatial localization of photons. *Phys. Rep*. 411: 1–232.

Kobayashi, K., Sangu, S., Ito, H. et al. 2001. Near-field optical potential for a neutral atom. *Phys. Rev. A* 63: 013806(1)–063806(9).

Kobayashi, K., Tanaka, Y., and Kawazoe, T. et al. 2008. Localized photon model including phonon's degrees of freedom. In *Progress in Nano-Electro-Optics*, vol. VI, ed. M. Ohtsu, pp. 41–66. Berlin, Germany: Springer.

Mandel, L. 1966. Configuration-space photon number operators in quantum optics. *Phys. Rev*. 144: 1071–1077.

Mandel, L. and Wolf, E. 1995. *Optical Coherence and Quantum Optics*. Cambridge, NY: Cambridge University Press.

Newton, T. D. and Wigner, E. P. 1949. Localized states for elementary systems. *Rev. Mod. Phys*. 21: 400–406.

Ohtsu, M. and Hori, H. 1999. *Near-Field Nano-Optics*. New York: Kluwer Academic/Plenum.

Ohtsu, M., Kobayashi, K., Kawazoe, T. et al. 2008. *Principles of Nanophotonics*. Boca Raton, FL: CRC Press.

Pike, E. R. and Sarkar, S. 1987. Spatial dependence of weakly localized single-photon wave packets. *Phys. Rev. A* 35: 926–928.

Pohl, D. W. and Courjon, D. 1993. *Near Field Optics*. Dordrecht, the Netherlands: Kluwer Academic.

Power, E. A. and Thirunamachandran, T. 1993. Quantum electrodynamics with nonrelativistic sources. V. Electromagnetic field correlations and intermolecular interactions between molecules in either ground or excited states. *Phys. Rev. A* 47: 2539–2551.

Roychoudhuri, C. and Roy, R. eds. 2003. The nature of light: What is a photon? *Opn. Trends* 3: S1–S35.

Sakurai, J. J. 1967. *Advanced Quantum Mechanics*. Reading, MA: Addison-Wesley.

Sangu, S., Kobayashi, K., Shojiguchi, A. et al. 2004. Logic and functional operations using a near-field optically coupled quantum-dot system. *Phys. Rev. B* 47: 115334(1)–115334(13).

Scully, M. O. and Zubairy, M. S. 1997. *Quantum Optics*. Cambridge, U.K.: Cambridge University Press.

Shojiguchi, A., Kobayashi, K., Sangu, S. et al. 2003. Superradiance and dipole ordering of an N two-level system interacting with optical near fields. *J. Phys. Soc. Jpn*. 72: 2984–3001.

Sipe, J. E. 1995. Photon wave functions. *Phys. Rev. A* 52: 1875–1883.

Suzuura, H., Tsujikawa, T., and Tokihiro, T. 1996. Quantum theory for exciton polaritons in a real-space representation. *Phys. Rev. B* 53: 1294–1301.

Wightman, A. S. 1962. On the localizability of quantum mechanical systems. *Rev. Mod. Phys*. 34: 845–872.

33

Operations in Nanophotonics

33.1 Introduction **33**-1
33.2 Dissipation-Controlled Nanophotonic Devices **33**-2
Basic Principles • Nanophotonic Switch • Carrier Manipulation (Up-Converter)
33.3 Nanophotonic Devices Using Spatial Symmetries **33**-8
Basic Principles • AND- and XOR-Logic Gates • Nanophotonic Buffer Memory • Manipulation of Quantum-Entangled States
33.4 Summary **33**-13
Acknowledgments **33**-13
References **33**-13

Suguru Sangu
Ricoh Company, Ltd.

Kiyoshi Kobayashi
University of Yamanashi
Japan Science and Technology

33.1 Introduction

Recently, a vast number of studies on nanophotonics have been published in the field of nanoscale optical measurement and bioimaging with super-resolution (Ohtsu 1998, Maheswari et al. 1999, Hosaka and Saiki 2001, Matsuda et al. 2003) and information processing technologies (Biolatti et al. 2000, Rinaldis et al. 2002, Troiani et al. 2002), owing to the unique characteristics of optical near field, which far exceed the technical limitations of conventional optics (Ohtsu et al. 2008). Especially, nanophotonics has shown promise and is expected to be the technology for next-generation nanoscale devices dealing with large amounts of information resources and low energy consumption (Ohtsu et al. 2002). In such devices, optical near field plays an important role in nanophotonic device operations, since the optical near field is a mixed state between photon and matter excitation, not only breaking the diffraction limit that is dependent on the wave nature of light, but also utilizing interesting characteristics inherent in nanophotonics, such as unidirectional energy transfer, optical forbidden transition (Kawazoe et al. 2002), and operations based on coherence of nanometric matters (Sangu et al. 2004), which have not been used in conventional optical devices.

Nanophotonic device is interpreted as a system that consists of several matter systems, localized photon field (optical near field) for driving carriers in the systems, and free photon (radiation) field for extracting some information, as illustrated in Figure 33.1. The important point of nanophotonic system is that the spatial distribution of photons is localized in a nanometric space rather than the matter itself being nanometer-sized. From this point, valuable device operations inconsiderable in conventional optical devices are expected. Relating to a theoretical viewpoint, some restrictions under the long wavelength approximation is allowed in a nanophotonic device system (Cho 2004). Moreover, quantum nature appears in carrier dynamics.

In order to control the carriers, quantum systems with discrete energies, such as quantum dots and molecules, are adapted as matter systems because the processes with matter coherence and with energy dissipation are clearly distinguishable. And also, excitation energies and dissipation dynamics are readily determined by adjusting the sizes of quantum objects. In addition, optical allowed and forbidden transitions for external far-field light are usable to prepare initial excitations. In this chapter, a quantum-dot system is assumed as a matter system of nanophotonic device, and thus the signal carriers correspond to excitons, that is, electron–hole pairs, in the quantum dots. Although such systems resemble a quantum computation device, let us note that a nanophotonic device need not keep quantum coherence in the entire system, and is divided into several quantum coherent parts via dissipative process.

In this chapter, operation principles of typical nanophotonic operations are covered by describing exciton population dynamics theoretically and numerically on the basis of the density matrix formalism (Walls and Milburn 1994, Carmichael 1999, Breuer and Petruccione 2002). Basic formulations for energy transfer, dissipation, and exciton excitation are explained, and then, nanophotonic switch and carrier up-converter are numerically demonstrated in Section 33.2. In Section 33.3, nanophotonic device operations, such as logic gates and memory, are described, in which system coherence and spatial symmetries play important roles. As a summary, design concepts for nanophotonic device systems are discussed in Section 33.4.



FIGURE 33.1 Schematic representation of a nanophotonic device system, in which carriers are transferred via localized photon field with interaction length in the order of a matter size.

33.2 Dissipation-Controlled Nanophotonic Devices

In this section, nanophotonic devices, where signal carrier in a single input terminal transfers to that in an output one, are formulated and evaluated numerically. Dynamics of signal transfer and control in a nanophotonic device can be described by density matrix formalism. Since quantum mechanical theory expresses an energy-conservative system, dissipation process should be introduced by some sort of approximation because a functional device operation needs to guarantee unidirectional signal transfer. After explanation of basic principles of exciton energy transfer and creation of excitation in a quantum-dot system with dissipation process, some concrete functional operations are explained in the later part of this section.

33.2.1 Basic Principles

33.2.1.1 Energy Transfer between Two Quantum Dots

As the simplest example of carrier dynamics, exciton energy transfer between two quantum dots with radiative and nonradiative relaxations is described by using density matrix formalism (Carmichael 1999, Sangu et al. 2003). Figure 33.2 denotes energy diagram for a two-quantum-dot system, where exciton ground state in QD-A and first exciton excited state in QD-B resonantly couple with each other. This resonant condition can be realized by adjusting the size of quantum dots. For example, in the case of a cubic quantum dot, such as CuCl quantum dot (Masumoto 2002, Kawazoe et al. 2003), the energy with the quantum numbers (n_x, n_y, n_z) is given as

$$E_{(n_x,n_y,n_z)} = \frac{\pi^2\hbar^2}{2Ma^2}\left(n_x^2 + n_y^2 + n_z^2\right) + E_g, \quad (n_x, n_y, n_z = 1,2,3,\ldots), \tag{33.1}$$



FIGURE 33.2 Energy diagram of a two-quantum-dot system, where the sizes of quantum dots are determined to satisfy the resonant condition, and are set as a (QD-A) and $\sqrt{2}a$ (QD-B). There are exciton sublevels in QD-B because of unidirectional energy transfer. Intra-sublevel relaxation originates from coupling between excitons and phonon reservoir.

where M and E_g denote the exciton mass and bulk exciton energy, respectively. Obviously, when the sizes of QD-A and QD-B are set as a and $\sqrt{2}a$, respectively, the (1, 1, 1)-level in QD-A and (2, 1, 1), (1, 2, 1), and (1, 1, 2)-levels in QD-B are the same energy and, thus, they couple resonantly. In the following, the energy levels for three quantum numbers are dealt with collectively and labeled as $\hbar\Omega_1$- and $\hbar\Omega_2$-levels, since degeneracy of several energy levels is not essential. Energy state of the system is described by the following non-perturbative and interaction Hamiltonians:

$$\begin{aligned} \hat{H}_0 &= \hbar\Omega_2\left(\hat{A}^\dagger\hat{A} + \hat{B}_2^\dagger\hat{B}_2\right) + \hbar\Omega_1\hat{B}_1^\dagger\hat{B}_1, \\ \hat{H}_{\text{int}} &= \hbar U\left(\hat{A}^\dagger\hat{B}_2 + \hat{A}\hat{B}_2^\dagger\right), \end{aligned} \tag{33.2}$$

where

Ω_1 and Ω_2 are eigenfrequencies of QD-A and QD-B

U represents the optical near-field coupling strength, and creation and annihilation operators for excitons are depicted in Figure 33.2

The interaction Hamiltonian $\hat{H}_{\text{int}}$ is well known as the Förster-type interaction (Förster 1965), which is often used by describing intermolecular and inter-quantum-dot interaction. Although the actual interaction between QD-A and QD-B occurs via intermediate virtual states of exciton-polaritons (Kobayashi et al. 2000), which are the coupled state of excitons and photons, such exciton-polariton degree of freedom is neglected in Equation 33.2 as is traced out and renormalized in the coupling strength U.

Exciton dynamics can be expressed by using density operator $\hat{\rho}(t)$, which is a projection operator expanding a certain energy state to appropriate bases depending on possible exciton states in a quantum-dot system. There are a three-exciton state, three two-exciton states, three one-exciton states, and a vacuum state in a two-quantum-dot system, as illustrated in Figure 33.3. Equation of motion of the density operator is given by the Liouville equation in the case without dissipation (Breuer and Petruccione 2002). Dynamics with dissipation is often expressed by so-called Lindblad type notation on the bases of the first-order Born approximation (Carmicheal 1999), in which free photon and phonon fields are considered as energy reservoirs as follows:

$$\frac{\mathrm{d}\hat{\rho}(t)}{\mathrm{d}t}=\frac{1}{i\hbar}\left[\hat{H}_0+\hat{H}_{\text{int}},\hat{\rho}(t)\right]+\mathcal{D}_{\text{photon}}\hat{\rho}(t)+\mathcal{D}_{\text{phonon}}\hat{\rho}(t), \tag{33.3}$$

where $\mathcal{D}_{\text{photon (phonon)}}$ is a superoperator defined as

$$\mathcal{D}_{\text{photon}}\hat{\rho}(t)=\sum_{\alpha=A,B_1}\frac{\gamma_\alpha}{2}\left[2\hat{\alpha}\hat{\rho}(t)\hat{\alpha}^\dagger-\hat{\alpha}^\dagger\hat{\alpha}\hat{\rho}(t)-\hat{\rho}(t)\hat{\alpha}^\dagger\hat{\alpha}\right],$$

$$\begin{aligned}\mathcal{D}_{\text{phonon}}\hat{\rho}(t)=&\frac{\Gamma}{2}(n+1)\\&\times\left[2\hat{B}_2\hat{B}_1^\dagger\hat{\rho}(t)\hat{B}_2^\dagger\hat{B}_1-\hat{B}_2^\dagger\hat{B}_1\hat{B}_2\hat{B}_1^\dagger\hat{\rho}(t)-\hat{\rho}(t)\hat{B}_2^\dagger\hat{B}_1\hat{B}_2\hat{B}_1^\dagger\right]\\&+\frac{\Gamma}{2}n\left[2\hat{B}_2^\dagger\hat{B}_1\hat{\rho}(t)\hat{B}_2\hat{B}_1^\dagger-\hat{B}_2\hat{B}_1^\dagger\hat{B}_2^\dagger\hat{B}_1\hat{\rho}(t)-\hat{\rho}(t)\hat{B}_2\hat{B}_1^\dagger\hat{B}_2^\dagger\hat{B}_1\right],\end{aligned} \tag{33.4}$$

n is the number of phonons in the reservoir, and the number of photons is assumed as zero because of external field being a vacuum state. As you readily understand from the bottom of Equation 33.4, energy transfer between the excited and ground states of an exciton occurs by mediating the intra-sublevel transition with non-radiative relaxation constant Γ, which guarantees unidirectional energy transfer in the two-quantum-dot system.

Since analytical solution of Equation 33.3 is complex and the physical meaning is unclear, the following is discussed on the basis of numerical calculations. For far-field light excitation, excitons in a two-quantum-dot system are created via mixed states of several bases, which are shown in Figure 33.3, because the two quantum dots cannot distinguish each other due to the diffraction limit of light. On the other hand, high spatial resolution of optical near field permits direct access for individual quantum dots. For example, an optical fiber probe possesses sub-100 nm spatial resolution (Hosaka and Saiki 2001,


$|e\rangle_A|e,e\rangle_B$
Three-exciton state
$|e\rangle_A|e,g\rangle_B$
Two-exciton state
$|e\rangle_A|g,e\rangle_B$
$|g\rangle_A|e,e\rangle_B$
$|e\rangle_A|g,g\rangle_B$
$|g\rangle_A|e,g\rangle_B$
$|g\rangle_A|g,e\rangle_B$
One-exciton state
$|g\rangle_A|g,g\rangle_B$
Vacuum state

FIGURE 33.3 Appropriate base states in which excitation and ground states for an isolated quantum dot are used. There are eight bases, which include a three-exciton state, three two-exciton states, three one-exciton states, and a vacuum state.

Matsuda et al. 2003) and plasmonic excitation in metallic nanostructures are utilized as an interface in a nanophotonic device (Yatsui et al. 2001, Nomura et al. 2005). As an initial condition to demonstrate energy transfer between the two-quantum-dot systems, an exciton in QD-A is locally prepared that is expressed by density matrix elements of $\rho_{\text{in}}(t) = {}_A\langle e|_B\langle g,g|\hat{\rho}|e\rangle_A|g,g\rangle_B = 1$ and otherwise being zero. Output population is given by the density matrix element of $\rho_{\text{out}}(t) = {}_A\langle g|_B\langle g,e|\hat{\rho}|g\rangle_A|g,e\rangle_B$, which is the lower-level state excited in QD-B, and $(|g,e\rangle_B)^\dagger = {}_B\langle g,e|$. In this case, two- and three-exciton bases decouple from the output population dynamics, and it is enough to consider only four base states for calculating the dynamics.

In the following, numerical solutions in Equation 33.3 are explained, in which two types of typical dynamics appear depending on the optical near-field coupling strength. Figures 33.4 and 33.5 show the exciton population in the input (QD-A) and output (QD-B) energy levels, respectively, when the optical near-field coupling strength are applied as $U^{-1} = 10$ ps (Figures 33.4a and 33.5a) and 50 ps (Figures 33.4b and 33.5b). For Figure 33.4a, oscillating behavior still remains because the sublevel relaxation constant Γ is the same order of the coupling strength U. While in the case of $\Gamma > U$, coherence in the upper energy levels quickly reduces, and the exciton energy that is stored in the lowest energy level in the system is released as radiative relaxation. The exciton population given in Figure 33.5 is proportional to photoluminescence intensity from the coupled quantum-dot system.

Key point to design of a nanophotonic device is to determine energy transfer paths by using resonant coupling among plural energy states, and internal and external dissipation processes. Density matrix formalism discussed above is a useful tool to solve signal dynamics in an exciton–photon coupled or polariton-mediated system. In addition, multi-exciton process is important for functional operations, such as nanophotonic switch, which are given in Sections 33.2.2 and 33.2.3.



FIGURE 33.4 Temporal evolution of exciton population in the $\hbar\Omega_2$-level in QD-A (input). The optical near-field coupling strength are (a) $U^{-1} = 10$ ps and (b) 50 ps, and the other parameters are set as $\hbar\Omega_2 = 3.22$ eV ($M = 2.3m_e$, $E_g = 3.20$ eV, $a = 5$ nm or 7.07 nm), $\hbar\Omega_1 = 3.21$ eV ($a = 7.07$ nm), $\gamma_A^{-1} = 1$ ns, $\gamma_B^{-1} = 0.5$ ns, and $\Gamma^{-1} = 10$ ps, where a CuCl quantum cube is assumed as a coupled two-quantum-dot system. For simplicity, zero temperature ($n = 0$) is assumed.



FIGURE 33.5 Temporal evolution of exciton population in the $\hbar\Omega_1$-level in QD-B (output). The optical near-field coupling strength are (a) $U^{-1} = 10$ ps and (b) 50 ps, and the other parameters are the same as in Figure 33.4.

33.2.1.2 Creation of Excitation by an External Field

Before explanation of multi-exciton process, a way to describe the creation of signal carriers in a quantum-dot system is discussed by means of the density matrix formalism. There are two types of carrier excitations: resonant and nonresonant. In the resonant excitation, energy of external photon field (laser pulse) corresponds to that of the exciton state (Carmicheal 1999), and the equation of motion, which is given in Equation 33.3, is modified with additional contribution of $\hat{H}_r$ as

$$\frac{d\hat{\rho}(t)}{dt} = \frac{1}{i\hbar}\left[\hat{H}_0 + \hat{H}_{\text{int}} + \hat{H}_r, \hat{\rho}(t)\right] + \mathcal{D}_{\text{photon}}\hat{\rho}(t) + \mathcal{D}_{\text{phonon}}\hat{\rho}(t),$$
$$\hat{H}_r = -\hbar g\left(\hat{B}_1^\dagger \langle \hat{a} \rangle + \langle \hat{a}^\dagger \rangle \hat{B}_1\right) \approx -\hbar V(t)\left(\hat{B}_1^\dagger + \hat{B}_1\right), \tag{33.5}$$

where $\hat{a}$ and $\hat{a}^\dagger$ represent annihilation and creation operators of external photon field, and on the basis of the semi-classical approximation, $\langle \hat{a} \rangle = \langle \hat{a}^\dagger \rangle \equiv V(t)/g$. It means that the annihilation and creation operators are renormalized in the parameter (Rabi frequency) $V(t)$. Equation 33.5 expresses the coherent process, which is well known as π-pulse excitation.

While in the case of the nonresonant excitation, coherence between an exciton and a photon is already lost because of interaction among a large number of energy states. This situation appears in such a case that an exciton creates mediated by continuous energy levels and surrounding barrier levels. The formulation of exciton excitation is equivalent to exciton creation from photon reservoir with finite temperature. According to Equation 33.4, the following term is added to Equation 33.3 for nonresonant excitation:

$$\mathcal{P}_{\text{photon}}\hat{\rho}(t) = \sum_{\alpha = A, B_1} \frac{V_\alpha(t)}{2}\left[2\hat{\alpha}^\dagger \hat{\rho}(t)\hat{\alpha} - \hat{\alpha}\hat{\alpha}^\dagger \hat{\rho}(t) - \hat{\rho}(t)\hat{\alpha}\hat{\alpha}^\dagger\right], \tag{33.6}$$

where $V_\alpha(t)$ is pumping rate in the optically allowed state in QD-α.

The above formulations are useful for making initial excited states in a quantum-dot system as well as for applying control signal to select energy transfer paths. In the following, exciton population dynamics for a two-quantum-dot system (Figure 33.2), which is driven by the external photon field, is explained by using numerical results of Equations 33.5 and 33.6. When the bases are restricted less than the one-exciton state, there are four states in this system (See Figure 33.3). Temporal evolution of exciton population in the $\hbar\Omega_2$-levels in QD-A and $\hbar\Omega_1$-level in QD-B are plotted in Figure 33.6a and b, respectively, which is in the case of resonant excitation. The results for nonresonant excitation are also given in Figure 33.7a and b. In both cases, the time width of pumping is set as 50 ps, which is denoted by the vertical dashed lines in Figures 33.6a and 33.7a. Temporal evolutions for resonant and nonresonant excitation are similar with each other except for those in the period when an external field is applied. Since the resonant oscillation keeps matter coherence, the population once increases and then decreases beyond π-pulse excitation. Figures 33.7b and 33.8b represent the population in QD-B, and the temporal profiles are similar in both cases, where the decay profiles are determined by the radiative relaxation constant in the lower energy level in QD-B, but total populations (the area of population curves) reflect the population for the early stage in QD-A.

Resonant and nonresonant exciton creations are important for projecting input signal to a quantum-dot system as well as for controlling signal carrier transiently in a nanophotonics device. Due to the above formulations for energy transfer, dissipation, and creation of excitation, some functional device operations can be demonstrated numerically, which are discussed in Sections 33.2.2 and 33.2.3.

33.2.2 Nanophotonic Switch

General switching device consists of three terminals, which correspond to input, output, and control. Similarly, a three-quantum-dot system can operate as a nanophotonics switch,



FIGURE 33.6 Temporal evolution of exciton population in (a) $\hbar\Omega_2$-level in QD-A (input terminal) and (b) $\hbar\Omega_1$-level in QD-B (output terminal), where $\hbar\Omega_2$-level in QD-A is resonantly excited. The optical near-field coupling strength is U^{-1} = 50 ps, and the other parameters are the same as in Figure 33.4. The solid, dashed, dotted, and dot-dash, dot-dot-dash curves represent the pulse area of 0.5π, 0.75π, 1.0π, 1.25π, and 1.5π, respectively.



FIGURE 33.7 Temporal evolution of exciton population in (a) $\hbar\Omega_2$-level in QD-A (input port) and (b) $\hbar\Omega_1$-level in QD-B (output port), where $\hbar\Omega_2$-level in QD-A is nonresonantly excited. The parameters are the same as in Figure 33.6. The solid, dashed, dotted, dot-dash, and dot-dot-dash curves represent the pulse area of 0.5π, 0.75π, 1.0π, 1.25π, and 1.5π, respectively.



FIGURE 33.8 Energy diagram of a nanophotonic switch that consists of three quantum dots with the size ratio $A:B:C=1:\sqrt{2}:2$. Input and control signals are injected in the $\hbar\Omega_3$-level in QD-A and the $\hbar\Omega_1$-level in QD-C, respectively, and output signal is detected from the $\hbar\Omega_2$-level in QD-B. By mediating intra-sublevel relaxations, unidirectional energy transfer is guaranteed in this system.

where three quantum dots correspond to input, output, and control terminals (Kawazoe et al. 2003). In Figure 33.8, energy diagram of the three-quantum-dot system is illustrated where the two resonant paths are labeled $\hbar\Omega_2$ and $\hbar\Omega_3$. The resonance conditions can be realized by choosing the quantum-dot sizes as $A:B:C=1:\sqrt{2}:2$ (see Equation 33.1), where the interaction between QD-A and QD-B is not considered because interdot distance between them is assumed large enough for neglecting the interaction. The principle of the switching operation is as follows: when the control signal is injected in the $\hbar\Omega_1$-level in QD-C, the dissipation path toward the $\hbar\Omega_1$-level is blocked because of Fermionic feature of excitons in a system with discrete energies, an initial exciton in QD-A transfers to the second stable state of $\hbar\Omega_2$-levels in QD-B, and annihilates an exciton with a radiative photon. What is important for this type of functional operation, in which dissipation paths are selectively determined, is to deal with a multi-exciton dynamics in a system.

Equation of motion of the nanophotonic switch can be written in accordance with the manner presented in Section 33.2.1, where the considered bases are extended in two-exciton states, and resonant exciton excitations are applied as an input signal in QD-A and a control signal in QD-C. Since output luminescent intensity is proportional to the $\hbar\Omega_2$-level population in QD-B, the population dynamics in QD-B is discussed in the following.

Figure 33.9 represents the numerical result of one and two-exciton population dynamics. The dashed curve shows the output population in QD-B, when rectangular optical pulse (π-pulse) with the duration of 10 ps is injected in the input terminal of QD-A. The exciton created in QD-A transfers to QD-C



FIGURE 33.9 Temporal evolution of exciton population in the $\hbar\Omega_2$-level in QD-B (output terminal). The dashed and solid curves represent the cases where a single rectangular optical pulse is injected in QD-A (input terminal) and rectangular pulses are injected in the $\hbar\Omega_3$-level in QD-A (input terminal) and the $\hbar\Omega_1$-level in QD-C (control terminal). The parameters are set as follows: optical near-field coupling strength $U_{AC}^{-1} = U_{BC}^{-1} = 50$ ps, pulse duration $\Delta t = 10$ ps (π-pulse amplitude), radiative relaxation time $2^{-3}\gamma_A^{-1} = 2^{-3/2}\gamma_B^{-1} = \gamma_C^{-1} = 1000$ ps, intra-sublevel relaxation time $\Gamma_{B,32}^{-1} = 10$ ps, and $\Gamma_{B,21}^{-1} = \Gamma_{C,21}^{-1} = 20$ ps.



FIGURE 33.10 Temporal evolution of exciton population in the $\hbar\Omega_1$-level in QD-C (output port). The dashed curve represents the profile of the third rectangular optical pulse (π-pulse). The pumping pulse is injected with a delay of 200 ps and pulse duration of 10 ps. The other parameter values set are the same as in Figure 33.9.

via optical near-field coupling U_{AC} and then relaxes to the lowest energy level in QD-C because of fast intra-sublevel relaxation. Therefore, output population in QD-B is detected as very small value (OFF-state). While, the solid curve represents the case that two optical pulses with 10 ps-pulse duration are injected simultaneously in the lowest energy levels in QD-A and QD-C. In the early stage of the dynamics, a somewhat large signal with oscillation appears (ON-state). This is the result of occupation in the $\hbar\Omega_1$-level in QD-C, which is the optical nutation between lower resonant energy levels in QD-B and QD-C. The rise time or switching time is estimated less than 100 ps, which depends on the optical near-field coupling strength (Sangu et al. 2003).

The readers may see that the signal falling time from ON- to OFF-state is quite slower than the rising time from OFF- to ON-state. This is surely constrained by the radiative relaxation time in the control port of QD-C. However, the falling time is controllable by injection of the third control pulse, because π-pulse excitation can remove the exciton occupied in the $\hbar\Omega_1$-level in QD-C. Figure 33.10 represents the same result of exciton population dynamics shown in Figure 33.9, but additional rectangular optical pulse is injected with the delay of 200 ps in the control port of QD-C. The dashed curve represents timing of the control pulse. By injecting the third pulse, the optical nutation completely disappears and the dissipation path toward the lowest energy level in QD-C becomes effective.

Nanophotonic switches and nanophotonic devices, in which dissipation paths are controlled by the state-filling property of excitons, can realize quite low energy operations. Ideally, the energy loss is determined by intra-sublevel relaxation, which is in the order of a few tens of meV. This is a big advantage not only for miniaturizing photonic devices, but also for heat dissipation and wiring in nanometric devices.

33.2.3 Carrier Manipulation (Up-Converter)

Unidirectional energy transfer and switching operation are guaranteed by considering the phonon reservoir system which is coupled with excitons. On the other hand, intense pulse excitation can create the finite phonons in the phonon reservoir system. This leads to blow back an exciton from lower to upper energy levels, instantaneously. Therefore, direction of energy transfer is also controllable by external optical pulse, which has been demonstrated experimentally in the recent publication (Yatsui et al. 2009). This up-conversion dynamics is formulated in a two-quantum-dot system, as shown in Figure 33.2. The intense optical pulse should be dealt with coherent interaction between excitons in the $\hbar\Omega_1$-level in QD-B and external photons. Therefore, the equation of motion described in Equation 33.5 is adopted. Since the atomic lattice in the reservoir system is transiently vibrated by the optical pulse, the phonon number of $n(\omega_0)$ in Equation 33.4 is given as the following function:

$$n(\omega_0) = \frac{1}{\exp\left[\hbar\omega_0 / k_B T(I_{\text{in}})\right] - 1}, \tag{33.7}$$

where ω_0, T, and k_B are the angular frequency of incident light, temperature of the system, and the Boltzmann constant, respectively. Equation 33.7 is the Bose–Einstein distribution function. For simplicity, the temperature is assumed to be proportional to the time integration of the optical pulse, I_{in}. The calculated results of the exciton population dynamics are



FIGURE 33.11 Temporal evolution of exciton population in (a) the $\hbar\Omega_1$-level in QD-B and (b) the $\hbar\Omega_2$-level in QD-A, when the optical pulse is injected at the time 10 ps. The solid, dashed, and dotted curves represent the pulse area of 0.5π, 1.0π, and 1.5π, respectively. The parameters are set as follows: optical near-field coupling strength $U^{-1} = 50$ ps, pulse duration $\Delta t = 10$ ps (π-pulse amplitude), radiative relaxation time $2^{-3/2}\gamma_A^{-1} = \gamma_B^{-1} = 1000$ ps, and intra-sublevel relaxation time $\Gamma = 10$ ps in QD-B. The phonon number in given by $[\exp(8.0/A^2) - 1]^{-1}$ where A denotes the pulse area.

plotted in Figure 33.11. Figure 33.11a and b represent the populations in the $\hbar\Omega_1$-level in QD-B and in the $\hbar\Omega_2$-level in QD-A which is the up-converted energy level. The solid, dashed, and dotted curves correspond to π/2-pulse, π-pulse, and 3π/2-pulse, respectively. Owing to coherent excitation process by optical pulse injection, the population in the lower energy level in QD-B maximally increases for π-pulse excitation, and decreases for more intense excitation. Temporal evolution in this energy level obeys solely relaxation time of the lower energy level. The population dynamics in QD-A is more complex. The peak values depend on the population in the $\hbar\Omega_1$-level in QD-B for each optical pulse area while the number of phonons in the phonon reservoir monotonically increases depending on the power of the optical pulse. Therefore, population lifetime depicted in the dotted curve in Figure 33.11b becomes longer than the dashed one because of longer pulse injection period. Such an up-conversion signal cannot observe in an isolated quantum dot, since dipole inactive transition from QD-B to QD-A never occurs without optical near-field interaction.

Carrier dynamics driven by both exciton–photon and exciton–phonon interactions has large possibilities for some applications, such as novel light sources, optical near–far field interface devices, efficient photodetectors, and efficient photoelectric conversion devices (Yatsui et al. 2009).

33.3 Nanophotonic Devices Using Spatial Symmetries

In Section 33.2, nanophotonic devices, in which dissipation paths are selected by a state-filling condition in multi-exciton excitation states, were discussed. While another type of device using a coherently-coupled state shows interesting features. For such devices, the number of excitons in a system as well as the spatial symmetry of the system determine the device operations. In this section, some logical operations, memory operations, and operations mediating quantum entangled states are explained with basic theoretical formulations.

33.3.1 Basic Principles

33.3.1.1 Symmetric and Antisymmetric States

When two identical quantum dots sharing an exciton are coupled with each other, as shown in Figure 33.12, appropriate bases for coupled states instead of those for individual quantum dots give a clear view for system dynamics. There are two coupled states via optical near-field interaction that are described by using mixed states between vacuum and exciton states for individual quantum dots, are as follows:

$$\begin{aligned} |S\rangle &= \left(|e\rangle_A |g\rangle_B + |g\rangle_A |e\rangle_B\right)/\sqrt{2}, \\ |A\rangle &= \left(|e\rangle_A |g\rangle_B - |g\rangle_A |e\rangle_B\right)/\sqrt{2}, \end{aligned} \tag{33.8}$$

where the bases for the coupled states, $|S\rangle$ and $|A\rangle$ are called as symmetric and antisymmetric states as explained later in this section. At the beginning, energies in the symmetric and antisymmetric



FIGURE 33.12 Energy diagram for two identical quantum dots (left). The system is expressed as a superposition of symmetric and antisymmetric states (right).

states are evaluated. Since the system Hamiltonian in a two-quantum-dot system with optical near-field coupling is given as

$$\begin{aligned}\hat{H} &= \hat{H}_0 + \hat{H}_{\text{int}},\\ \hat{H}_0 &= \hbar\Omega\hat{A}^\dagger\hat{A} + \hbar\Omega\hat{B}^\dagger\hat{B},\\ \hat{H}_{\text{int}} &= \hbar U\left(\hat{A}^\dagger\hat{B} + \hat{A}\hat{B}^\dagger\right),\end{aligned} \tag{33.9}$$

where radiative relaxation terms are ignored for simplicity and assuming that the relaxation lifetime is longer than that of optical near-field interaction. The energies for these states are easily derived as

$$\begin{aligned}\langle S|\hat{H}|S\rangle &= \hbar(\Omega + U),\\ \langle A|\hat{H}|A\rangle &= \hbar(\Omega - U).\end{aligned} \tag{33.10}$$

Equation 33.10 explains that the symmetric and antisymmetric states have positive and negative energy shift U from the energy in each quantum dot, respectively. In order to extract carrier excitation from the two identical quantum-dot systems, the third (output) quantum dot is set with resonance energy to the symmetric state or antisymmetric state. Detailed explanation of energy transfer properties in the three-quantum-dot system is given in Section 33.3.1.2.

In this stage, to examine total dipole moment in such a system is quite instructive. The total dipole moment is expressed by an expectation value of a summation of creation and annihilation operators, such as

$$\begin{aligned}\langle S|\mu\sum_{\alpha=A,B}\left(\alpha^\dagger + \alpha\right)|g\rangle_A|g\rangle_B &= \sqrt{2}\mu,\\ \langle A|\mu\sum_{\alpha=A,B}\left(\alpha^\dagger + \alpha\right)|g\rangle_A|g\rangle_B &= 0,\end{aligned} \tag{33.11}$$

where μ denotes the dipole moment for QD-A and QD-B. Apparently, transition from vacuum state to the antisymmetric state is inactive and, thus, it cannot couple to the external far-field light; this is the reason this state is known as the antisymmetric state. In contrast, optical near field can excite the antisymmetric state because it has a spatial localization character beyond the diffraction limit of light, and can create an exciton in a one-side quantum dot. The state with an exciton is equal to a superposition between symmetric and antisymmetric states.

As described above, if the symmetric and antisymmetric states can be manipulated freely, coupling from near- to far-field light becomes controllable, which is useful for some functional operations, such as nanophotonic buffer memory. Furthermore, optical near-field coupling between the two identical quantum dots and the third output dot creates characteristic behaviors depending on spatial symmetry, where the symmetric and antisymmetric states play important roles, as explained in Section 33.3.1.2.

33.3.1.2 Selective Energy Transfer

For far-field light, excitation in each quantum dot is not distinguishable and radiation is proportional to total dipole moment, which is discussed in Section 33.3.1.1. However, optical near field can resolve the spatial distribution of exciton occupation in a nanometer scale. In order to access the excited states in a two-identical quantum-dot system by using optical near field, third quantum dot, QD-C, is considered as an output port. Figure 33.13 represents the energy transfer from two-identical quantum-dot system to the third quantum dot. The two identical quantum dots make symmetric and antisymmetric states via optical near-field interaction, and these states also couple to the third quantum dot with optical near-field interaction. Here, to evaluate transition moment between two identical quantum dots to the third quantum dot is useful for understanding the effect of spatial alignment of quantum dots. The interaction Hamiltonian is given as

$$\begin{aligned}\hat{H}_{\text{int},AC} &= \hbar U_{AC}\left(\hat{A}^\dagger\hat{C} + \hat{C}^\dagger\hat{A}\right),\\ \hat{H}_{\text{int},BC} &= \hbar U_{BC}\left(\hat{B}^\dagger\hat{C} + \hat{C}^\dagger\hat{B}\right),\end{aligned} \tag{33.12}$$

where U_{AC} and U_{BC} represent optical near-field coupling strength between QD-A and QD-C, and QD-B and QD-C, respectively. Using these interaction Hamiltonians, the transition matrix element from symmetric state to excited state in QD-C reads

$${}_A\langle g|_B\langle g|_C\langle e|\left(\hat{H}_{\text{int},AC} + \hat{H}_{\text{int},BC}\right)|S\rangle|g\rangle_C = \frac{\hbar(U_{AC} + U_{BC})}{\sqrt{2}}, \tag{33.13}$$

and that from antisymmetric state to excited state in QD-C is

$${}_A\langle g|_B\langle g|_C\langle e|\left(\hat{H}_{\text{int},AC} + \hat{H}_{\text{int},BC}\right)|A\rangle|g\rangle_C = \frac{\hbar(U_{AC} - U_{BC})}{\sqrt{2}}. \tag{33.14}$$



FIGURE 33.13 Schematic representation of energy transfer between two-identical quantum-dot system (input) and a larger quantum dot (output) than the other two. Antisymmetric state becomes dipole-allowed and dipole-forbidden states, depending on spatial symmetry of the output quantum dot.

From Equation 33.14, the transition matrix element can take a zero value when the initial state is an antisymmetric state and the coupling strength toward QD-C are set as $U_{AC} = U_{BC} \neq 0$. This condition can be realized by spatial symmetric alignment of quantum dots. Therefore, energy transfer mediating antisymmetric state is strongly dependent on spatial symmetry in a quantum-dot system.

The feature of selective energy transfer is useful for functional operations of a nanophotonic device, such as logic and memory operations. In the following sections, some functional operations using coherently coupled states, which are symmetric and antisymmetric states, are explained with numerical calculation results.

33.3.2 AND- and XOR-Logic Gates

Similar to Section 33.3.1.2, let us consider a three-quantum-dot system that consists of two identical input quantum dots (QD-A and QD-B) and the third output quantum dot (QD-C) with energy sublevels. QD-C is located in symmetrical position from QD-A and QD-B. Important points for this system are energy transfer reflecting spatial symmetry and difference of resonance conditions in one- and two-exciton states. By using these points, the principle of logic operations has been proposed (Sangu et al. 2004).

First, the case QD-C negatively detuned with energy shift $\hbar U$ is considered. Figure 33.14 represents energy diagram from initial state to final state in this system. The left (initial state) has no excitation in QD-C, and the right (final state) has an exciton in QD-C. Although negative energy shift creates resonance condition between the states of $|A\rangle|g\rangle_C$ and $|g\rangle_A|g\rangle_B|e\rangle_C$ for the one-exciton state, the energy transfer mediated by the antisymmetric state is not permitted in the quantum-dot system that is symmetrically aligned, as explained in Section 33.3.1.2. While, for the two-exciton state, the excited state $|e\rangle_A|e\rangle_B|g\rangle_C$ couples resonantly to the symmetric state $|S\rangle|e\rangle_C$, which is allowed transition. Therefore, this quantum-dot system permits the energy transfer only in the case of two-exciton state. This behavior represents just an AND-logic operation.



FIGURE 33.14 Energy diagram in three-quantum-dot system, which consists of two identical quantum dots (input port) and a third quantum dot (output port). The third quantum dot is negatively detuned against each input quantum dot. The energy transfer occurs only in the case of two-exciton state.



FIGURE 33.15 Energy diagram in three-quantum-dot system, which consists of two identical quantum dots (input port) and a third quantum dot (output port). The third quantum dot is positively detuned against each input quantum dot. The energy transfer occurs only in the case of one-exciton state.

Second, the energy level in QD-C is set as positive energy shift $\hbar U$. The energy diagram is illustrated in Figure 33.15. In this case, two-exciton state is inactive because of antisymmetric state, while symmetric one-exciton state $|S\rangle|g\rangle_C$ can resonantly couple to the final state of $|g\rangle_A|g\rangle_B|e\rangle_C$. This means that the energy transfer occurs when either QD-A or QD-B is initially excited, where excitation in a quantum dot in two-identical quantum-dot system is equivalent to excite symmetric and antisymmetric states, simultaneously (see Equation 33.8). This corresponds to the XOR-logic operation.

Temporal evaluation of the above two logic operations can be derived analytically on the basis of the density matrix formalism. The system Hamiltonian is the same as Equation 33.9 except for additional third quantum dot terms, which include non-perturbed energy and non-radiative intra-sublevel relaxation, and radiative relaxation is ignored because optical near-field coupling and sublevel relaxation process are assumed to be fast enough. Final solution for one-exciton state, which is detected in lower energy level in QD-C, is written as follows (Sangu et al. 2004):

$$\rho_{gge,gge}(t) = \frac{1}{2} + \frac{4U'^2}{\omega_+^2 - \omega_-^2} e^{-\frac{\Gamma}{2}t} \times \left[\cos\phi_+ \cos(\omega_+ t + \phi_+) - \cos\phi_- \cos(\omega_- t + \phi_-)\right], \tag{33.15}$$

where $\rho_{gge,gge}(t) \equiv {}_C\langle e|\, {}_B\langle g|\, {}_A\langle g|\rho(t)|g\rangle_A |g\rangle_B |e\rangle_C$, and the following abbreviations have been used:

$$\phi_\pm = \tan^{-1}\left(\frac{2\omega_\pm}{\Gamma}\right),$$

$$\omega_\pm^2 = \frac{1}{2}\left\{(\Delta\Omega - U)^2 + W_+ W_- \pm \sqrt{\left[(\Delta\Omega - U)^2 + W_+^2\right]\left[(\Delta\Omega - U)^2 + W_-^2\right]}\right\},$$

$$W_\pm = 2\sqrt{2}U' \pm \frac{\Gamma}{2}, \tag{33.16}$$

where $\hbar\Delta\Omega$ is the energy shift in QD-C against that in QD-A or QD-B. In Equation 33.15, the second term denotes the energy transfer or nutation between two-identical quantum-dot system QD-A and QD-B, and the third of QD-C. Apparently, this term becomes the maximum value in the case of positive detuning $\Delta\Omega = U$, because the denominator $\omega_+^2 - \omega_-^2$ becomes minimum. This corresponds to dynamics in the XOR-logic operation, as is mentioned in Figure 33.15. The exciton population can reach maximum value of 0.5 not 1. This is because one-side quantum dot in QD-A or QD-B is excited as an initial excitation, which is same as coupled state between symmetric and antisymmetric states, and the antisymmetric state cannot couple to QD-C due to the symmetrically aligned system.

On the other hand, analytical solution for two-exciton state is given in a similar form as

$$\begin{aligned}&\rho_{Se,Se}(t) + \rho_{gg2e,gg2e}(t)\\&\quad = 2\left\{\frac{1}{2} + \frac{4U'^2}{\omega_+'^2 - \omega_-'^2} e^{-\frac{\Gamma}{2}t}\left[\cos\phi_+ \cos\left(\omega_+' t + \phi_+'\right) - \cos\phi_- \cos\left(\omega_-' t + \phi_-'\right)\right]\right\},\end{aligned} \tag{33.17}$$

where $\rho_{Se,Se}(t) + \rho_{gg2e,gg2e}(t) \equiv {}_C\langle e|\langle S|\hat{\rho}\,(t)|S\rangle|e\rangle_C + {}_C\langle 2e|_B\langle g|_A\langle g|\rho(t)|g\rangle_A|g\rangle_B|2e\rangle_C$ is defined as the population in the lower level in QD-C and

$$\phi_\pm' = \tan^{-1}\left(\frac{2\omega_\pm'}{\Gamma}\right),$$

$$\omega_\pm'^2 = \frac{1}{2}\left\{\left(\Delta\Omega + U\right)^2 + W_+W_- \pm \sqrt{\left[\left(\Delta\Omega + U\right)^2 + W_+^2\right]\left[\left(\Delta\Omega + U\right)^2 + W_-^2\right]}\right\}. \tag{33.18}$$

From Equations 33.17 and 33.18, negative detuning $\Delta\Omega = -U$ makes resonance condition for two-exciton state, while the negative detuning for one-exciton state is off-resonant to symmetric state (see Equations 33.15 and 33.16). Therefore, the energy transfer rate is quite small. This is the AND-logic operation.

Population dynamics in these devices are plotted in Figure 33.16, where exciton population in QD-C is analytically derived by using Equations 33.15 and 33.17. The solid and dashed curves represent one- and two-exciton states, respectively. Figure 33.16a is the result of the AND-logic gate with negative detuning $\Delta\Omega = -U$, where the strength of optical near-field interaction between QD-A and QD-B, and that between QD-A(B) and QD-C are set as $U^{-1} = 10$ ps and $U'^{-1} = 50$ ps. In this operation, the two-exciton state in QD-A and QD-B is resonantly coupled with QD-C, while the one-exciton state is not, because of off-resonant condition. On the other hand, the XOR-logic operation is shown in Figure 33.16b. In this case, the one-exciton state in QD-A and QD-B is resonant to the energy level in QD-C, where initial population is prepared in QD-A, which is same as the coupled state between symmetric and antisymmetric states, and thus, the population reaches only the value of 0.5 because the antisymmetric state is a dark state in a spatially symmetric system. Although ON/OFF ratio is not so high, the XOR-logic gate operation is surely observed.

33.3.3 Nanophotonic Buffer Memory

As mentioned in Section 33.3.1.2, using energy transfer via a dipole inactive state, which can be controlled by energy detuning and quantum dot alignment or spatial symmetry, various functional operations inherent in nanophotonic devices are expected. In this section, one of interesting operations of a nanophotonic buffer memory is introduced. Quantum-dot alignment for realizing nanophotonic buffer memory is illustrated in Figure 33.17, in which two identical quantum dots (QD-A and QD-B) couple



FIGURE 33.16 Temporal evolution of exciton population in three-quantum-dot systems, which consist of input-side two identical quantum dots (QD-A and QD-B) and an output-side quantum dot (QD-C) with intra-sublevel relaxation. (a) and (b) represent the cases where upper energy level is negatively (AND-logic gate) and positively (XOR-logic gate) detuned. The solid and dashed curves correspond to the one-exciton and two-exciton states, respectively. The calculation parameters in Equations 33.15 through 33.18 are set as $U^{-1} = 10$ ps, $U'^{-1} = 50$ ps, and $\Gamma^{-1} = 10$ ps.



FIGURE 33.17 Schematic representation of nanophotonic buffer memory, which consists of two identical quantum dots, and the larger quantum dot with positive detuning $\Delta\Omega = U$. The three quantum dots are aligned maximally asymmetric and, thus, the coupling strength between QD-A and QD-C can be neglected.

to the third quantum dot (QD-C) with maximal asymmetric position. The third quantum dot is detuned positively with the energy $\hbar(\Omega + U)$, that is, $\Delta\Omega = U$, which has the same energy diagram as in Figure 33.15, but energy transfer via antisymmetric state is allowed. When both QD-A and QD-B are excited as an initial condition, the two-exciton state in the input side resonantly couples to antisymmetric state with excitation in QD-C and then relaxes to the one-exciton antisymmetric state. This antisymmetric state decouples with outer far-field light because of dipole inactive (dark) state. This is just buffer memory operation.

Dynamics of buffer memory operation is numerically evaluated by using density matrix formalism, as explained above. The calculation results are plotted in Figure 33.18, where the vertical axis represents population relating to the two-exciton coupled states, and the coupling strengths via optical near field are set as $U^{-1} = 10\,\text{ps}$ for QD-A and QD-B, and $U'^{-1} = 50\,\text{ps}$ for QD-B and QD-C (QD-A and QD-C are decoupled). The solid and dashed curves represent antisymmetric and symmetric states, respectively. In this calculation, radiative relaxation is ignored because the radiative relaxation time is longer than exciton population dynamics via optical near field and, thus, two-exciton antisymmetric state becomes the final state. Actually, the two-exciton state decays into the one-exciton antisymmetric state with a photon radiation from QD-C, and an exciton is retained in the system.

In Section 33.3.2, the dark state is used for suppressing energy transfer, leading to logical operations, while it is used to create excitation in a dark state in this section, which enables us to control far- and near-field conversion. It is one of the characteristic features of nanophotonic devices.



FIGURE 33.18 Temporal evolution of exciton population in three-quantum-dot systems, which have maximal asymmetric configuration (see Figure 33.17). The solid and dashed curves represent the populations for the antisymmetric two-exciton state and the symmetric two-exciton state, respectively. The antisymmetric state has a dipole inactive nature and, thus, the excitation is maintained in the three-quantum-dot system. The calculation parameters are set as $U^{-1} = 10\,\text{ps}$, $U'^{-1} = 50\,\text{ps}$, and $\Gamma^{-1} = 10\,\text{ps}$.

33.3.4 Manipulation of Quantum-Entangled States

As mentioned in Sections 33.3.1 through 33.3.3, a nanophotonic device system consists of coherent energy transfer process and dissipation process. Since the coherent energy transfer process maintains quantum coherence, this system can be used for quantum information processing as well as interface between quantum and classical computations. As an instructive example, a typical device that identifies quantum mixed states is numerically demonstrated in this section. Figure 33.19 schematically shows spatial alignment of quantum dots, where two identical quantum dots couple resonantly, and the excitations are led to two output quantum dots with positive (QD-C) and negative (QD-D) detuning. Both QD-C and QD-D are set at symmetric and asymmetric positions, respectively. Apparently, QD-C resonantly couples to the symmetric state in the input quantum dots, and QD-D couples to the antisymmetric state. Therefore, this device operates that input signal with arbitral quantum state divides two quantum bases of symmetric and antisymmetric states into two different output signals with different optical frequencies as well as different positions in a nanometric space. Temporal evolution of an input quantum mixed state is numerically calculated in Figure 33.20. When an input state $c_1|S\rangle + c_2|A\rangle$ is injected, where one-exciton state is assumed, the output exciton population in QD-C and QD-D



FIGURE 33.19 Spatial arrangement of a four-quantum-dot system, which has symmetric and asymmetric configurations simultaneously. QD-C resonantly couples with symmetric state in QD-A and QD-B, and QD-D couples with antisymmetric state.



FIGURE 33.20 Population dynamics in four-quantum-dot systems that have two identical quantum dots (QD-A and QD-B) for input ports of an arbitral quantum state, and output quantum dots (QD-C and QD-D) for identifying the input quantum states. The solid and dashed curves represent the output population of QD-C and QD-D, respectively, and the dotted lines correspond to the coefficients of an initial quantum mixed state. The calculation parameters in Equations 33.15 through 33.18 are set as $U^{-1} = 10\,\text{ps}$, $U'^{-1} = 50\,\text{ps}$, and $\Gamma^{-1} = 10\,\text{ps}$.

reflects the coefficients of c_1 and c_2 of an input state. In Figure 33.20, the coefficients of initial quantum mixed state are set as $c_1 = 1/3$ and $c_2 = 2/3$, and thus, the output populations approach these values asymptotically.

Although general quantum information processing devices are built upon quantum coherent states in whole device systems, nanophotonic devices are characterized by the control of dissipation processes, but keeping the quantum coherence locally. Such a mixed operation of classical and quantum information processing may open up future device technologies.

33.4 Summary

In this chapter, operation of a nanophotonic device, in which characteristics of the light localized among nanometric objects, that is, optical near fields, are positively used, has been demonstrated theoretically and numerically. Resonant energy transfer between quantum systems mediated by optical near-field interaction and fast energy relaxation in intra-energy levels via exciton–phonon interaction are fundamental for a switching device and excitation carrier manipulations, as discussed in Section 33.2. By using coupled states, which are made from resonant optical near-field interaction between quantum systems, nanophotonic logic-gate, memory, and quantum-classical interface devices can be realized with the help of selective energy transfer depending on energies of the coupled state and a selection rule for optical near and far fields. These nanophotonic devices are taken as extensions of classical devices, in which simple functions are tandemly arranged, to novel-type devices locally utilized the quantum nature. Here, the optical near fields play important roles for controlling quantum coherence and/or decoherence.

As a summary, key fundamental design concepts for nanophotonic inherent operations are enumerated in the following:

- Externally switchable dissipation paths
- Dependence of the number of excitation carriers
- Selection rule for optical near field based on spatial arrangement of quantum systems
- Selection rule for optical far field based on total dipole moment

The above may not explain all concepts for designing nanophotonic devices—additional unique natures may be hidden. Accomplished device systems might be realized, which have possible advantages such as low energy consumption, low heat liberation, large parallelism, miniaturization, and environmental tolerance, by comprehending physical phenomena inherent in nanophotonics correctly and designing nanophotonic devices from a standpoint throughout from nano- to macro-scales.

Acknowledgments

The authors are grateful to M. Ohtsu, T. Kawazoe, and T. Yatsui from the University of Tokyo for fruitful discussions. This work was mainly carried out at the project of ERATO, Japan Science and Technology Agency, from 1998 to 2003. The authors would like to thank the persons concerned.

References

Biolatti, E., Iotti, R. C., Zanardi, P., and Rossi, F. 2000. Quantum information processing with semiconductor macroatoms. *Phys. Rev. Lett.* 85: 5647–5650.

Breuer, H.-P. and Petruccione, F. 2002. *The Theory of Open Quantum Systems*. New York: Oxford University Press.

Carmichael, H. J. 1999. *Statistical Methods in Quantum Optics 1*. Berlin/Heidelberg, Germany: Springer-Verlag.

Cho, K. 2004. *Optical Response of Nanostructures: Microscopic Nonlocal Theory (Springer Series in Solid-State Sciences)*. Tokyo, Japan: Springer-Verlag.

Förster, T. 1965. Delocalized excitation and excitation transfer. In *Modern Quantum Chemistry*. O. Sinanoglu (Ed.), pp. 93–137. London, U.K.: Academic Press.

Hosaka, N. and Saiki, T. 2001. Near-field fluorescence imaging of single molecules with a resolution in the range of 10 nm. *J. Microsc*. 202: 362–364.

Kawazoe, T., Kobayashi, K., Lim, J., Narita, Y., and Ohtsu, M. 2002. Direct observation of optically forbidden energy transfer between CuCl quantum cubes via near-field optical spectroscopy. *Phys. Rev. Lett*. 88: 067404-1–067404-4.

Kawazoe, T., Kobayashi, K., Sangu, S., and Ohtsu, M. 2003. Demonstration of a nanophotonic switching operation by optical near-field energy transfer. *Appl. Phys. Lett*. 82: 2957–2959.

Kobayashi, K., Sangu, S., Ito H., and Ohtsu, M. 2000. Near-field optical potential for a neutral atom. *Phys. Rev. A* 63: 013806-1–013806-9.

Maheswari, R. U., Mononobe, S., Yoshida, K., Yoshimoto, M., and Ohtsu, M. 1999. Nanometer level resolving near field optical microscope under optical feedback in the observation of a single-string deoxyribo nucleic acid. *Jpn. J. Appl. Phys*. 38: 6713–6720.

Masumoto, Y. 2002. Persistent spectral hole burning in semiconductor quantum dots. In *Semiconductor Quantum Dots: Physics, Spectroscopy and Applications*. Y. Masumoto and T. Takagahara (Eds.), pp. 209–244. Berlin/Heidelberg, Germany: Springer-Verlag.

Matsuda, K., Saiki, T., Nomura, S., Mihara, M., Aoyagi, Y., Nair, S., and Takagahara, T. 2003. Near-field optical mapping of exciton wave functions in a GaAs quantum dot. *Phys. Rev. Lett*. 91: 177401–177404.

Nomura, W., Ohtsu, M., and Yatsui, T. 2005. Nanodot coupler with a surface plasmon polariton condenser for optical far/near-field conversion. *Appl. Phys. Lett*. 86: 181108-1–181108-3.

Ohtsu, M. 1998. *Near-Field Nano/Atom Optics and Technology*. Tokyo, Japan: Springer-Verlag.

Ohtsu, M., Kobayashi, K., Kawazoe, T., Sangu, S., and Yatsui, T. 2002. Nanophotonics: Design, fabrication, and operation of nanometric devices using optical near fields. *IEEE J. Sel. Top. Quantum Electron*. 8: 839–862.

Ohtsu, M., Kobayashi, K., Kawazoe, T., Yatsui, T., and Naruse, M. 2008. *Principles of Nanophotonics*. London, U.K.: Taylor & Francis.

Rinaldis, S. D., D'Amico, I., and Rossi, F. 2002. Exciton–exciton interaction engineering in coupled GaN quantum dots. *Appl. Phys. Lett*. 81: 4236–4238.

Sangu, S., Kobayashi, K., Kawazoe, T., Shojiguchi, A., and Ohtsu, M. 2003. Excitation energy transfer and population dynamics in a quantum dot system induced by optical near-field interaction. *J. Appl. Phys*. 93: 2937–2945.

Sangu, S., Kobayashi, K., Shojiguchi, A., and Ohtsu. M., 2004. Logic and functional operations using a near-field optically coupled quantum-dot system. *Phys. Rev. B* 69, 115334-1–115334-13.

Troiani, F., Hohenester, U., and Molinari, E. 2002. Electron–hole localization in coupled quantum dots. *Phys. Rev. B* 65: 161301-1–161301-4.

Walls, D. F. and Milburn, G. J. 1994. *Quantum Optics*. Berlin/Heidelberg, Germany: Springer-Verlag.

Yatsui, T., Kourogi, M., and Ohtsu, M. 2001. Plasmon waveguide for optical far/near-field conversion. *Appl. Phys. Lett*. 79: 4583–4585.

Yatsui, T., Sangu, S., Kobayashi, K., Kawazoe, T. et al. 2009. Nanophotonic energy up-conversion using ZnO nanorod double-quantum-well structures. *Appl. Phys. Lett*. 94: 083113-1–083113-3.

34

System Architectures for Nanophotonics

34.1 Introduction 34-1
34.2 System Architectures Based on Optical Excitation Transfer..34-1
Optical Excitation Transfer via Optical Near-Field Interactions and Its Functional Features • Parallel Architecture Using Optical Excitation Transfer • Secure Signal Transfer in Nanophotonics
34.3 Hierarchical Architectures in Nanophotonics... 34-6
Physical Hierarchy in Nanophotonics and Functional Hierarchy • Hierarchical Memory Retrieval • Design of *Unscalable* Hierarchical Response • Versatile Functionalities Based on Hierarchy in Optical Near-Fields
34.4 Summary..34-12
References...34-12

Makoto Naruse
National Institute of Information and Communications Technology
The University of Tokyo

34.1 Introduction

To accommodate the continuously growing amount of digital data and qualitatively new requirements demanded by industry and people in society, optics is expected to be highly integrated and to play a wider role in enhancing system performance. However, many technological difficulties remain to be in overcome in adopting optical technologies in critical information and communication systems; one problem is the poor integrability of optical hardware due to the diffraction limit of light (Pohl and Courjon 1993, Ohtsu and Hori 1999).

Nanophotonics, on the other hand, which is based on local interactions between nanometer-scale matters via optical near fields, offers ultrahigh-density integration since it is not constrained by the diffraction limit. Fundamental nanophotonic processes, such as optical excitation transfer via optical near fields between nanometer-scale matters, have been studied in detail (Ohtsu et al. 2002, 2008, Maier et al. 2003). Moreover, this higher integration density is not the only advantage that optical near fields have over conventional optics and electronics. From a system architectural perspective, nanophotonics drastically changes the fundamental design rules of functional optical systems, and suitable architectures may be built to exploit this. As a result, it also gives qualitatively strong impacts on information and communication systems.

This chapter discusses system architecture for nanophotonics considering the unique physical principles of optical near-field interactions as well as their experimental verification based on technological vehicles, such as quantum dots and engineered metal nanostructures. In particular, two unique physical processes in light–matter interactions in the nanometer scale are exploited. One is optical excitation transfer via optical near-field interactions and the other is the hierarchical property in optical near-field interactions, which are explained in Sections 34.2 and 34.3, respectively.

The overall structure of this chapter is outlined in Figure 34.1. Through these architectural and physical insights, nanophotonic information and communication systems are demonstrated, which overcome the integration-density limit imposed by the diffraction of light with ultralow-power operation, as well as provide unique functionalities that are only achievable using optical near-field interactions.

34.2 System Architectures Based on Optical Excitation Transfer

34.2.1 Optical Excitation Transfer via Optical Near-Field Interactions and Its Functional Features

In this section, optical excitation transfer processes involving optical near-field interactions are reviewed from a system perspective. Here, their fundamental principles are first briefly reviewed and their functional features are introduced for later discussion.

The interaction Hamiltonian between an electron and an electric field is given by

$$\hat{H}_{\text{int}} = -\int \hat{\psi}^{\dagger}(\vec{r})\vec{\mu}\hat{\psi}(\vec{r}) \cdot \hat{\vec{D}}(\vec{r})d\vec{r}, \tag{34.1}$$


System architecture for nanophotonics
Parallel architecture
In
D_1
D_M
Out
Secure signal transfer
V
Hierarchical architecture
Optical excitation transfer
Optical near-field interactions
Hierarchy in optical near-field interactions
Light–matter interaction in the nanometer scale

FIGURE 34.1 Overview of this section: from light–matter interactions on the nanometer scale to system architectures for nanophotonics.

where

$\vec{\mu}$ is a dipole moment
$\hat{\psi}^{\dagger}(\vec{r})$ and $\hat{\psi}(\vec{r})$ are, respectively, creation and annihilation operators of an electron at $\vec{r}$
$\hat{\vec{D}}(\vec{r})$ is the operator of electric flux density

In usual light–matter interactions, the operator $\hat{\vec{D}}(\vec{r})$ is a constant since the electric field of propagating light is considered to be constant on the nanometer scale. Therefore, as is well known, one can derive optical selection rules by calculating a transfer matrix of an electrical dipole. As a consequence, in the case of cubic quantum dots, for instance, transitions to states described by quantum numbers containing an even number are prohibited. In the case of optical near-field interactions, on the other hand, due to the steep electric field of optical near fields in the vicinity of nanoscale matter, an optical transition that violates conventional optical selection rules is allowed.

Optical excitations in nanostructures, such as quantum dots, can be transferred to neighboring ones via optical near-field interactions (Ohtsu et al. 2002, 2008). For instance, assume two cubic quantum dots, QD_A and QD_B, whose side lengths L are a and $\sqrt{2}a$, respectively (see Figure 34.2a). Suppose that the energy eigenvalues for the quantized exciton energy level specified by quantum numbers (n_x, n_y, n_z) in a QD with side length L are given by

$$E_{(n_x,n_y,n_z)} = E_B + \frac{\hbar^2\pi^2}{2ML^2}(n_x^2 + n_y^2 + n_z^2), \qquad (34.2)$$

where

E_B is the energy of the bulk exciton
M is the effective mass of the exciton

According to Equation 34.2, there exists a resonance between the level of quantum number (1, 1, 1) for QD_A and that of quantum number (2, 1, 1) for QD_B. There is an optical near-field interaction, which is denoted by U, due to the steep electric field in the vicinity of QD_A. Therefore, excitons in QD_A can move to the (2, 1, 1)-level in QD_B. Note that such a transfer is prohibited for propagating light since the (2, 1, 1)-level in QD_B contains an even number (Tang et al. 1993). In QD_B, the exciton sees a sublevel energy relaxation, denoted by Γ, which is faster than the near-field interaction, and so the exciton goes to the (1, 1, 1)-level of QD_B. It should be emphasized that the sublevel relaxation determines the unidirectional exciton transfer from QD_A to QD_B.

Now, several unique functional aspects should be noted in the above excitation transfer processes. First, as already mentioned, the transition from the (1, 1, 1)-level in QD_A to the (2, 1, 1)-level in QD_B is usually a dipole-forbidden transfer. In contrast, the optical near field allows such processes. Second, in the resonant energy levels of those quantum dots, optical excitation can go back and forth between QD_A and QD_B, which is called optical nutation. The direction of excitations is determined by the energy dissipation processes. Therefore, based on the above mechanisms, the flow of optical excitations can be controlled in quantum-dot systems via optical near-field interactions.

From an architectural standpoint, such a flow of excitations directly leads to digital processing systems and computational


QD$_A$
QD$_B$
a
$\sqrt{2}a$
U
(1,1,1)
(2,1,1)
Γ
(1,1,1)
(a)
S_1
QD$_1$
QD$_C$
QD$_3$
S_3
QD$_2$
S_2
(c)
S_1
S_2
S_3
+
Out
(b) Summation
CuCl in NaCl 40 K
Input (1,1,1)
Input (1,0,1)
Input (0,0,1)
Intensity (a.u.)
3.20
3.25
3.30
Photon energy (eV)
0
0.10
0.20
0.30
0.40
150 nm
(d) Output
Data
(e) Broadcast
OFF state
ON state
200 nm
200 nm
0.24
0

FIGURE 34.2 (a) Optical excitation transfer between quantum dots via optical near-field interactions. (b) Global summation: a basic function for memory-based architectures. (c) Quantum-dot arrangement for summation via an optical near field. (d) Intensity for three different input combinations and the spatial intensity distribution of the output photon energy. (e) Broadcast interconnects for parallel processing. Spatial intensity distribution of the output of 3-dot AND gates.

architectures. First of all, two different physical states appear by controlling the dissipation processes in the larger dot; this is the principle of the nanophotonic switch (Kawazoe et al. 2003). Also, such a flow control itself allows an architecture known as a binary decision diagram, where an arbitrary combinatorial logic operation is determined by the destination of a signal flowing from a root (Akers 1978).

Such optical excitation transfer processes also lead to unique system architectures. In this regard, Section 34.2.2 discusses a massively parallel architecture and its nanophotonic implementations. Also, Section 34.2.3 demonstrates that optical excitation transfer provides higher tamper resistance against attacks than conventional electrically wired devices, by focusing on environmental factors for signal transfer.

34.2.2 Parallel Architecture Using Optical Excitation Transfer

34.2.2.1 Memory-Based Architecture

This section discusses a memory-based architecture where computations are regarded as a table lookup or database search problem, which is also called content addressable memory (CAM) (Liu 2002). The inherent parallelism of this architecture is well matched with the physics of optical excitation transfer, and provides performance benefits in high-density, low-power operations.

In this architecture, input signal (content) serves as a query to a lookup table, and the output is the address of the data matching the input. This architecture plays a critical role in various systems for example in a data router where the output port for an incoming packet is determined based on the lookup tables.

All optical means for implementing such functions have been proposed, for instance, by using planar lightwave circuits (Grunnet-Jepsen et al. 1999). However, since separate optical hardware for each table entry is needed if based on today's known methods, if the number of entries in the routing table is on the order of 10,000 or more, the overall physical size of the system becomes impractically large. On the other hand, by using diffraction-limit-free nanophotonic principles, huge lookup tables can be configured compactly.

Then, it is important to note that the table lookup problem is equivalent to an inner product operation. Assume an N-bit input signal $\mathbf{S} = (s_1,\ldots,s_N)$ and reference data $\mathbf{D} = (d_1,\ldots,d_N)$. Here, the inner product $\mathbf{S}\cdot\mathbf{D} = \sum_{i=1}^{N} s_i \cdot d_i$ will provide a maximum value when the input perfectly matches the reference data with an appropriate modulation format (Naruse et al. 2004). Then, the function of a CAM is to derive j, which maximizes the $\mathbf{S}\cdot\mathbf{D}_j$.

34.2.2.2 Global Summation Using Near-Field Interactions

As discussed in Section 34.2.2.1, the inner product operations are the key functionalities of the memory-based architecture. The multiplication of two bits, namely, $x_i = s_i \cdot d_i$, has already been demonstrated by a combination of three quantum dots (Kawazoe et al. 2003). Therefore, one of the key operations remaining is the summation, or data gathering scheme, denoted by $\sum x_i$, where all data bits should be taken into account, as schematically shown in Figure 34.2b.

In known optical methods, wave propagation in free-space or in waveguides, using focusing lenses or fiber couplers, for example, well matches such a data gathering scheme because the physical nature of propagating light is inherently suitable for the collection or distribution of information, such as global summation. However, the level of the integration of these methods is restricted due to the diffraction limit of light. In nanophotonics, on the other hand, the near-field interaction is inherently physically local, although functional global behavior is required.

The global data gathering mechanism, or summation, is realized based on the unidirectional energy flow via an optical near field, as schematically shown in Figure 34.2c, where surrounding excitations are transferred toward a quantum dot $\mathrm{QD_C}$ located at the center (Kawazoe et al. 2005, Naruse et al. 2005b). This is based on the excitation transfer processes presented in Section 34.2.1 and in Figure 34.2a, where an optical excitation is transferred from a smaller dot ($\mathrm{QD_A}$) to a larger one ($\mathrm{QD_B}$) through a resonant energy sublevel and a sublevel relaxation process occurring at a larger dot. In the system shown in Figure 34.2c, similar energy transfers may take place among the resonant energy levels in the dots surrounding $\mathrm{QD_C}$ so that excitation transfer can occur. The lowest energy level in each quantum dot is coupled to a free photon bath to sweep out the excitation radiatively. The output signal is proportional to the (1, 1, 1)-level population in $\mathrm{QD_B}$.

A proof-of-principle experiment was performed to verify the nanoscale summation using CuCl quantum dots in a NaCl matrix, which has also been employed for demonstrating nanophotonic switches (Kawazoe et al. 2003) and optical nano-fountains (Kawazoe et al. 2005). A quantum-dot arrangement where small QDs ($\mathrm{QD_1}$–$\mathrm{QD_3}$) surrounded a large QD at the center ($\mathrm{QD_C}$) was chosen. Here, at most three light beams with different wavelengths, 325, 376, and 381.3 nm, are irradiated, which excite the quantum dots $\mathrm{QD_1}$–$\mathrm{QD_3}$ having sizes of 1, 3.1, and 4.1 nm, respectively. The excited excitons are transferred to $\mathrm{QD_C}$, and their radiation is observed by a near-field fiber probe tip. Notice the output signal intensity at a photon energy level of 3.225 eV in Figure 34.2d, which corresponds to a wavelength of 384 nm, or a $\mathrm{QD_C}$ size of 5.9 nm. The intensity varies approximately as 1:2:3 depending on the number of excited QDs in the vicinity, as observed in Figure 34.2d. The spatial intensity distribution was measured by scanning the fiber probe, as shown in the inset of Figure 34.2d, where the energy is converged at the center. Hence, this architecture works as a summation mechanism, counting the number of input channels, based on exciton energy transfer via optical near-field interactions.

Such a quantum-dot-based data-gathering mechanism is also extremely energy efficient compared to other optical methods such as focusing lenses or optical couplers. For example, the transmittance between two materials with refractive indexes n_1 and n_2 is given by $4n_1n_2/(n_1 + n_2)^2$; this gives a 4% loss if n_1 and n_2 are 1 and 1.5, respectively. The transmittance of an N-channel-guided wave coupler is $1/N$ from the input to the output if the coupling loss at each coupler is 3 dB. In nanophotonic summation, the loss is attributed to the dissipation between energy sublevels, which is significantly smaller. Incidentally, it is energy- and space-efficient compared to electrical CAM VLSI chips (Lin and Kuo 2001, Arsovski et al. 2003, Naruse et al. 2005a).

34.2.2.3 Broadcast Interconnects

For the parallel architecture shown in Section 34.2.2.2, it should also be noted that the input data should be commonly applied to all lookup table entries. In other words, broadcast interconnect is another important requirement for parallel architectures. Broadcast is also important in applications such as matrix-vector products (Goodman et al. 1978, Guilfoyle and McCallum 1996) and switching operations, for example, broadcast-and-select architectures (Li et al. 2001). Optics is in fact well suited to such broadcast operations in the form of simple imaging optics (Goodman et al. 1978, Guilfoyle and McCallum 1996) or in optical waveguide couplers; thanks to the nature of wave propagation. However, the integration density of this approach is physically limited by the diffraction limit, which leads to bulky system configurations.

The overall physical operation principle of broadcast using optical near fields is as follows. Suppose that the arrays of nanophotonic circuit blocks are distributed within an area whose size is comparable to the wavelength. For broadcasting, multiple input QDs simultaneously accept identical input data carried by diffraction-limited far-field light by tuning their optical frequency so that the light is coupled to dipole-allowed energy sublevels.

The far- and near-field coupling mentioned above is explained based on a model assuming cubic quantum dots, which was introduced in Section 34.2.1. According to Equation 34.2, there exists a resonance between the quantized exciton energy sublevel of quantum number (1, 1, 1) for the QD with effective side length a and that of quantum number (2, 1, 1) for the QD with effective side length $\sqrt{2}a$. Energy transfer from the smaller QD to the larger one occurs via optical near fields, which is forbidden for far-field light (Kawazoe et al. 2003).

The input energy level for the QDs, that is, the (1, 1, 1)-level, can also couple to the far-field excitation. This fact can be utilized for data broadcasting. One of the design restrictions is that energy sublevels for input channels do not overlap with those for output channels. Also, if there are QDs internally used for near-field coupling, dipole-allowed energy sublevels for those QDs cannot be used for input channels since the inputs are provided by far-field light, which may lead to the misbehavior of internal near-field interactions if resonant levels exist. Therefore, frequency partitioning among the input, internal, and output channels is important. The frequencies used for broadcasting, denoted by $\Omega_i = \{\omega_{i,1}, \omega_{i,2}, \ldots, \omega_{i,A}\}$, should be distinct values and should not overlap with the output channel frequencies $\Omega_o = \{\omega_{o,1}, \omega_{o,2}, \ldots, \omega_{o,B}\}$. A and B indicate the number of frequencies used for input and output channels, respectively. Also, there will be frequencies needed for internal device operations, which are not used for either input or output, denoted by $\Omega_n = \{\omega_{n,1}, \omega_{n,2}, \ldots, \omega_{n,C}\}$, where C is the number of those frequencies. Therefore, the design criteria for global data broadcasting is to exclusively assign input, output, and internal frequencies, Ω_i, Ω_o, and Ω_n, respectively.

In a frequency multiplexing sense, this interconnection method is similar to multi-wavelength chip-scale interconnection (De Souza et al. 1995). Known methods, however, require a physical space comparable to the number of diffraction-limited input channels due to wavelength demultiplexing, whereas in the nanophotonic scheme, the device arrays are integrated on the sub-wavelength scale, and multiple frequencies are multiplexed in the far-field light supplied to the device.

To verify the broadcasting method, the following experiments were performed using CuCl QDs inhomogeneously distributed in a NaCl matrix at a temperature of 22 K (Naruse et al. 2006). To operate a 3-dot nanophotonic switch (2-input AND gate) in the device, at most two input light beams (IN1 and IN2) were irradiated. When both inputs exist, an output signal is obtained from the positions where the switches exist, as described above. In the experiment, IN1 and IN2 were assigned to 325 and 384.7 nm, respectively. They were irradiated over the entire sample (global irradiation) via far-field light. The spatial intensity distribution of the output, at 382.6 nm, was measured by scanning a near-field fiber probe within an area of approximately 1 μm × 1 μm. When only IN1 was applied to the sample the output of the AND gate was ZERO (OFF state). When both inputs were irradiated the output was ONE (ON state). Note the regions marked by ■, ●, and ◆ in Figure 34.2e. In those regions, the output signal levels were, respectively, low and high, which indicate that multiple AND gates were integrated at densities beyond the scale of the globally irradiated input beam area. That is to say, broadcast interconnects to nanophotonic switch arrays are accomplished by diffraction-limited far-field light.

Combining this broadcasting mechanism with the summation mechanism discussed in Section 34.2.2.2 will allow the development of the nanoscale integration of massively parallel architectures, which have conventionally resulted in bulky configurations.

34.2.3 Secure Signal Transfer in Nanophotonics

In addition to breaking through the diffraction limit of light, such local interactions of optical near fields also have important functional aspects, such as in security applications, which particularly tamper resistance against attacks (Naruse et al. 2007a). One of the most critical security issues in present electronic devices is so-called side-channel attacks, by which information is tampered either invasively or noninvasively. This may be achieved, for instance, merely by monitoring their power consumption (Kocher et al. 1998).

In this section, it is shown that devices based on optical excitation transfer via near-field interactions are physically more tamper-resistant than their conventional electronic counterparts. The key is that the flow of information in nanoscale devices cannot be completed unless they are appropriately coupled with their environment (Hori 2001), which could possibly be the weakest link in terms of their tamper resistance. A theoretical approach is presented to investigate the tamper resistance of optical excitation transfer, including a comparison with electrical devices.

Here, the tampering of information is defined as involving simple signal transfer processes, since the primary focus is on their fundamental physical properties.

In order to compare the tamper resistance, an electronic system based on single-charge tunneling is introduced here, in which a tunnel junction with capacitance C and tunneling resistance R_T is coupled to a voltage source V via an external impedance $Z(\omega)$, as shown in Figure 34.3a. In order to achieve



FIGURE 34.3 Model of tamper resistance in devices based on (a) single charge tunneling and (b) optical excitation transfer. Dotted curves show the scale of a key device and dashed curves show the scale of the environment required for the system to work.

single charge tunneling, besides the condition that the electrostatic energy $E_C = e^2/2C$ of a single excess electron be greater than the thermal energy k_BT, the environment must have appropriate conditions, as discussed in detail in Ingold and Nazarov (1992). For instance, with an inductance L in the external impedance, the fluctuation of the charge is given by

$$\langle \delta Q^2 \rangle = \frac{e^2}{4\rho} \coth\left(\frac{\beta\hbar\omega_S}{2}\right), \tag{34.3}$$

where
$\rho = E_C/\hbar\omega_S$
$\omega_S = (LC)^{-1/2}$
$\beta = 1/k_BT$

Therefore, charge fluctuations cannot be small even at zero temperature unless $\rho \gg 1$. This means that a high-impedance environment is necessary, which makes tampering technically easy, for instance by adding another impedance circuit.

Here, let us define two scales to illustrate tamper resistance: (1) the scale associated with the key device size and (2) the scale associated with the environment required for operating the system, which are, respectively, indicated by dotted and dashed curves in Figure 34.3. In the case of Figure 34.3a, scale I is the scale of a tunneling device, whereas scale II covers all of the components. It turns out that the low tamper resistance of such wired devices is due to the fact that scale II is typically the macroscale, even though scale I is the nanometer scale.

In contrast, in the case of the optical excitation transfer shown in Figure 34.3b, the two quantum dots and their surrounding environment are governed by scale I. It is also important to note that scale II is the same as scale I. More specifically, the transfer of an exciton from QD_A to QD_B is completed due to the non-radiative relaxation process occurring at QD_B, which is usually difficult to tamper with. Theoretically, the sublevel relaxation constant is given by

$$\Gamma = 2\pi |g(\omega)|^2 D(\omega), \tag{34.4}$$

where
$\hbar g(\omega)$ is the exciton–phonon coupling energy at frequency ω
$\hbar$ is Planck's constant divided by 2π
$D(\omega)$ is the phonon density of states (Carmichael 1999)

Therefore, tampering with the relaxation process requires somehow "stealing" the exciton–phonon coupling, which would be extremely difficult technically.

It should also be noted that the energy dissipation occurring in the optical excitation transfer, derived theoretically as $E_{(2,1,1)} - E_{(1,1,1)}$ in QD_B based on Equation 34.2, should be larger than the exciton-phonon coupling energy of $\hbar\Gamma$, otherwise, the two levels in QD_B cannot be resolved. This is similar to the fact that the condition $\rho \gg 1$ is necessary in the electron-tunneling example, which means that the mode energy $\hbar\omega_S$ is smaller than the required charging energy E_C. By regarding $\hbar\Gamma$ as a kind of mode energy in the optical excitation transfer, the difference between the optical excitation transfer and a conventional wired device is the physical scale at which this mode energy is realized: nanoscale for the optical excitation transfer and macroscale for electric circuits.

34.3 Hierarchical Architectures in Nanophotonics

34.3.1 Physical Hierarchy in Nanophotonics and Functional Hierarchy

In this section, another feature of nanophotonics, the inherent hierarchy in optical near-field interactions, is exploited. As schematically shown in Figure 34.4a, there are multiple layers associated with the physical scale between the macroscale world and the atomic-scale world, which are primarily governed by propagating light and electron interactions, respectively. Between these two extremes, typically in scales ranging from a few nanometers to wavelength size, optical near-field interactions play a crucial role. In this section, such hierarchical properties in this mesoscopic or sub-wavelength regime are exploited.

Such physical hierarchy in optical near-field interactions will be analyzed by a simple dipole–dipole interaction model and an angular spectrum representation of optical near fields, as shown in Section 34.3.2. Before going into the details of the physical processes, functionalities required for system applications are briefly reviewed in terms of hierarchy.



FIGURE 34.4 (a) Hierarchy in optical near-field interactions. (b) Dipole–dipole interaction. (c) Signal contrast as a function of the ratio of the radius of the sample and the probe.

One of the problems for ultrahigh-density nanophotonic systems is interconnection bottlenecks, which have been addressed previously in Section 34.2.3 regarding broadcast interconnects. In fact, a hierarchical structure can be found in these broadcast interconnects by relating far-field effects at a coarser scale and near-field effects at a finer scale.

In this regard, it should also be mentioned that such physical differences in optical near-field and far-field effects can be used for a wide range of applications. The behavior of usual optical elements, such as diffractive optical elements, holograms, or glass components, is associated with their optical responses in optical far fields. In other words, nanostructures can exist in such optical elements as long as they do not affect the optical responses in far fields. Designing nanostructures accessible only via optical near fields provides additional, or hidden, information recorded in those optical elements, while maintaining the original optical responses in far fields. In fact, a "*hierarchical hologram*" or "*hierarchical diffraction grating*" has been experimentally demonstrated, as schematically shown in Figure 34.5 (Tate et al. 2008).

Since there is more hierarchy in the optical near-field regime, further applications should be possible, for example, it should be possible for nanometer-scale high-density systems to be gradually hierarchically connected to coarse layer systems.

Hierarchical functionalities are also important for several aspects of memory systems. One is related to recent high-density, huge-capacity memory systems, in which data retrieval or searching from entire memory archives is made even more difficult. Hierarchy is one approach for solving such a problem by making systems hierarchical, that is, by recording abstract data, metadata, or tag data in addition to the original raw data.

Hierarchy in nanophotonics provides a physical solution to achieve such functional hierarchy. As will be introduced below, low-density, rough information is read out at a coarser scale, whereas high-density, detailed information is read out at a finer scale. Sections 34.3.2 and 34.3.3 will show physical mechanisms for such hierarchical information retrieval.

Another issue in hierarchical functionalities will be security. High-security information is recorded at a finer scale, whereas less-critical security information is associated with a coarse layer. Also, in addition to associating different types of information with different physical scales, another kind of information can also be related to one or more layers of the physical hierarchy, for instance, traceability, history, or aging of information. Section 34.3.3 will demonstrate a *traceable* memory as an example.

34.3.2 Hierarchical Memory Retrieval

This section describes a physical model of optical near-field interactions based on dipole–dipole interactions (Ohtsu and Kobayashi 2004). Suppose that a probe, which is modeled by a sphere of radius r_P, is placed close to a sample to be observed, which is modeled as a sphere of radius r_S. Figure 34.4b shows three different sizes for the probe and the sample. When they are illuminated by incident light, whose electric field is $\mathbf{E}_0$, electric dipole moments are induced in both the probe and the sample; these moments are denoted by $\mathbf{p}_P = \alpha_P \mathbf{E}_0$ and $\mathbf{p}_S = \alpha_S \mathbf{E}_0$, respectively. The electric dipole moment induced in the sample $\mathbf{p}_S$, then generates an electric field, which changes the electric dipole moment in the probe by an amount $\Delta\mathbf{p}_P = \Delta\alpha_P \mathbf{E}_0$. Similarly, $\mathbf{p}_P$ changes the electric dipole moment in the sample by $\Delta\mathbf{p}_S = \Delta\alpha_S \mathbf{E}_0$. These electromagnetic interactions are called



FIGURE 34.5 Hierarchical optical elements, such as *hierarchical holograms*, based on different optical responses obtained in optical far and near fields.

dipole–dipole interactions. The scattering intensity induced by these electric dipole moments is given by

$$
\begin{aligned}
I &= \left|\mathbf{p}_P + \Delta\mathbf{p}_P + \mathbf{p}_S + \Delta\mathbf{p}_S\right|^2 \\
&\approx (\alpha_P + \alpha_S)^2 \,|\, E_0 \,|^2 + 4\Delta\alpha(\alpha_P + \alpha_S) \,|\, E_0 \,|^2
\end{aligned}
\tag{34.5}
$$

where $\Delta\alpha = \Delta\alpha_S = \Delta\alpha_P$ (Ohtsu and Kobayashi 2004). The second term in Equation 34.5 shows the intensity of the scattered light generated by the dipole–dipole interactions, containing the information of interest, which is the relative difference between the probe and the sample. The first term in Equation 34.5 is the background signal for the measurement. Therefore, the ratio of the second term to the first term of Equation 34.5 corresponds to a signal contrast, which will be maximized when the sizes of the probe and the sample are the same ($r_P = r_S$), as shown in Figure 34.4c. (A detailed derivation is found in Ohtsu and Kobabashi (2004).) Thus, one can see a scale-dependent physical hierarchy in this framework, where a small probe, say $r_P = D/2$, can nicely resolve objects with a comparable resolution, whereas a large probe, say $r_P = 3D/2$, cannot resolve a detailed structure but it can resolve a structure with a resolution comparable to the probe size. Therefore, although a large diameter probe cannot detect smaller-scale structure, it could detect certain features associated with its scale.

Based on the above simple hierarchical mechanism, a hierarchical memory system is constructed. Consider, for example, a maximum of N nanoparticles distributed in a region of a subwavelength scale. These nanoparticles can be nicely resolved by a scanning near-field microscope if the size of its fiber probe tip is comparable to the size of individual nanoparticles; in this way, the *first-layer* information associated with each distribution of nanoparticles is retrievable, corresponding to 2^N-different codes. By using a larger-diameter fiber probe tip instead, the distribution of the particles cannot be resolved, but a mean-field feature with a resolution comparable to the size of the probe can be extracted, namely, the number of particles within an area comparable to the size of the fiber probe tip. Thus, the *second-layer* information associated with the number of particles, corresponding to $(N + 1)$-different level of signals, is retrievable. Therefore, one can access different set of signals, 2^N or $N + 1$, depending on the scale of observation. This leads to hierarchical memory retrieval by associating this information hierarchy with the distribution and the number of nanoparticles using an appropriate coding strategy, as schematically shown in Figure 34.6a.

For example, in encoding N-bit information, $(N - 1)$-bit signals can be encoded by the distributions of nanoparticles while associating the remaining 1-bit with the number of nanoparticles. The details of encoding/decoding strategies will be found in Naruse et al. (2005c).

Simulations were performed assuming ideal isotropic metal particles to see how the second-layer signal varies depending on the number of particles using a finite-difference time-domain simulator (*Poynting for Optics*, a product of Fujitsu, Japan). Here, 80 nm-diameter particles are distributed over a 200 nm-radius circular grid at constant intervals. The solid circles in Figure 34.6d show calculated scattering cross sections as a function of the number of particles. A linear correspondence to the number of particles was observed. This result supports the simple physical model described above.

In order to experimentally demonstrate such principles, an array of Au particles, each with a diameter of around 80 nm, was distributed over a SiO_2 substrate in a 200 nm-radius circle. These particles were fabricated by a liftoff technique using electron-beam (EB) lithography with a Cr buffer layer. Each group of Au particles was spaced by 2 μm. A scanning electron microscope (SEM) image is shown in Figure 34.6b in which the values indicate the number of particles within each group. In order to illuminate all Au particles in each group and collect the scattered light from them, a near-field optical microscope (NOM) with a large-diameter-aperture (500 nm) metallized fiber probe was used in an illumination collection setup. The light source used was a laser diode with an operating wavelength of 680 nm. The distance between the substrate and the probe was maintained at 750 nm. Figure 34.6c shows an intensity profile captured by the probe, from which the second-layer information is retrieved. The solid squares in Figure 34.6d indicate the peak intensity of each section, which increased linearly. These results show the validity of hierarchical memory retrieval from nanostructures.

34.3.3 Design of *Unscalable* Hierarchical Response

The coarse graining process is usually an averaging process, meaning that the signal in the coarser layer is obtained in terms of a mean-field approximation of the fine-grained, lower-layer signals, which is also the case shown in Section 34.3.2. However, it should be noted that the optical near-field amplitude can be distributed independently at different scales of observation. In other words, the coarse graining of the optical near fields in fact provides an optical property independent of the lower-layer feature; such an *unscalable* hierarchical property of optical near fields will be analyzed below.

Here, the angular spectrum representation of the electromagnetic field is used for discussing the hierarchy in optical near fields (Wolf and Nieto-Vesperinas 1985, Inoue and Hori 2005, Naruse et al. 2007b). This allows an analytical treatment and gives an intuitive picture of the localization of optical near fields and represents relevance/irrelevance in optical near-field interactions at different scales of observation since it describes electromagnetic fields as a superposition of evanescent waves with different decay length and corresponding spatial frequency.

Suppose, for example, that there is an oscillating electric dipole, $\mathbf{d}^{(k)} = d^{(k)}(\cos\phi^{(k)}, 0)$, on the xz plane, which is oriented parallel to the x axis. Now, consider the electric field of radiation observed at a position displaced from the dipole by $\mathbf{R} = (r_{\|}^{(k)}\cos\varphi^{(k)}, z^{(k)})$. The angular spectrum representation of the z-component of the optical near field is given by



FIGURE 34.6 (a) Hierarchical memory retrieval from nanostructures. (b) SEM picture of an array of Au nanoparticles. Each section consists of up to seven nanoparticles. (c) Intensity pattern captured by a fiber probe tip whose diameter is comparable to the size of each section of nanoparticles. (d) Square marks: calculated scattering cross sections in each section, circular marks: peak intensity of each section in the intensity profile shown in (c).

$$E_z(\mathbf{R}) = \left(\frac{iK^3}{4\pi\varepsilon_0}\right)\int_1^\infty ds_\parallel \frac{s_\parallel}{s_z} f_z(s_\parallel, \mathbf{d}^{(1)}, \ldots, \mathbf{d}^{(N)}) \qquad (34.6)$$

where

$$f_z(s_\parallel, \mathbf{d}^{(1)}, \ldots, \mathbf{d}^{(N)}) = \sum_{k=1}^{N} d^{(k)} s_\parallel \sqrt{s_\parallel^2 - 1}\,\cos(\phi^{(k)} - \varphi^{(k)}) J_1\left(K r_\parallel^{(k)} s_\parallel\right) \times \exp\left(-K z^{(k)} \sqrt{s_\parallel^2 - 1}\right). \qquad (34.7)$$

Here, $s_\parallel$ is the spatial frequency of an evanescent wave propagating parallel to the x axis, and $J_n(x)$ represents Bessel functions of the first kind. Here, the term $f_z(s_\parallel, \mathbf{d}^{(1)}, \ldots, \mathbf{d}^{(N)})$ is called the angular spectrum of the electric field.

In the following, a two-layer system is introduced where (1) by observing very close to the dipoles, two items of first layer information are retrieved, and (2) by observing relatively far from the dipoles, one item of second-layer information is retrieved.

Suppose that there are two closely spaced dipole pairs (so there are four dipoles in total). The dipoles $\mathbf{d}^{(1)}$ and $\mathbf{d}^{(2)}$ are oriented in the same direction, namely, $\varphi^{(1)} = \varphi^{(2)} = 0$, and another dipole pair, $\mathbf{d}^{(3)}$ and $\mathbf{d}^{(4)}$, are both oriented in the opposite direction to $\mathbf{d}^{(1)}$ and $\mathbf{d}^{(2)}$, namely, $\varphi^{(3)} = \varphi^{(4)} = \pi$. These four dipoles are located at positions shown in Figure 34.7a. Here, at a position close to the x axis equidistant from $\mathbf{d}^{(1)}$ and $\mathbf{d}^{(2)}$, such as at the position A_1 in Figure 34.7a, the electric field is weak (logical ZERO) since (1) the angular spectrum originating from $\mathbf{d}^{(1)}$ and $\mathbf{d}^{(2)}$ vanishes, and (2) the electric field originating from $\mathbf{d}^{(3)}$ and $\mathbf{d}^{(4)}$ is small because they are far from the position A_1. In fact, as shown by the dashed curve in Figure 34.7b, since the angular spectrum at position A_1 oscillates, the integral of the angular spectrum, which is correlated to the field intensity at that point, will be low.

For the second layer retrieval, consider the observation at an intermediate position between the dipole pairs, such as the position B in Figure 34.7a. From this position, the four dipoles effectively appear to be two dipoles that are oriented in opposite directions to each other. As shown by the solid curve in Figure 34.7b, the angular spectrum involving relatively low



FIGURE 34.7 Examples of *unscalable* hierarchy in optical near fields. (a) The positions and orientations of four electric dipole systems. (b) And the corresponding angular spectrum observed at positions A_1, A_2, and B, indicating that the first-layer signals (obtained at A_1 and A_2) are logical ZEROs, while the second-layer signal (obtained at B) is logical ONE. (c) Calculated electric field intensity distribution agreed with theoretical predictions shown in (b). (d) Another electric field distribution where logical ONEs are retrieved at the first layer (A_1 and A_2) and logical ZERO is retrieved at the second layer (B).

spatial-frequency components shows a single peak, indicating that the electric field in the xy-plane is localized to the degree determined by its spectral width so that a logical ONE is retrievable at position B. Meanwhile, the angular spectrum observed at position A_2, shown in Figure 34.7a, is identical to that observed at position A_1, meaning that the electric field at A_2 is also at a low level.

To summarize the above mechanisms, a logical level of ONE in the second layer can be retrieved even though the two items of information retrieved in the first layer are both ZEROs; therefore, an unscalable hierarchy is achieved.

As described above, one of the two first-layer signals, the electric field at A_1, primarily depends on the dipole pair $\mathbf{d}^{(1)}$ and $\mathbf{d}^{(2)}$, and the other, the electric field at A_2, depends primarily on the dipole pair $\mathbf{d}^{(3)}$ and $\mathbf{d}^{(4)}$. The second-layer signal is determined by all of those dipoles. Concerning such a hierarchical mechanism, it was shown that a total of eight different signal combinations were achieved by appropriately orienting the four dipoles (Naruse et al. 2007b).

Numerical simulations were performed based on finite-difference time-domain methods to see how they agree with the theoretical analysis based on the angular spectrum. Four silver nanoparticles (of radius 15 nm) containing a virtual oscillating light source were assumed in order to simulate dipole arrays. Their positions are shown in Figure 34.7c. The first and the second layers were located 40 and 80 nm away from the dipole plane, respectively. The operating wavelength was 488 nm. The electric fields obtained at A_1, A_2, and B agree with the combinations of the first- and second-layer signals to be retrieved, as shown in Figure 34.7c. As another unscalable hierarchy example, Figure 34.7d represents a situation where logical ONEs are obtained at the first layer, while logical ZERO is obtained at the second layer. These agree with the theoretical analysis based on the angular spectrum.

34.3.4 Versatile Functionalities Based on Hierarchy in Optical Near-Fields

The hierarchical nature has been further exploited by combining other physical mechanisms in nanophotonics. For example, we can associate one of the hierarchical layers with energy dissipation processes. Specifically, a two-layer system is demonstrated where (1) at smaller scale, called *Scale* 1, the system should exhibit a unique response, and (2) at a larger scale, called *Scale* 2, the system should output two different signals. Such a hierarchical response can be applied to functions like the *traceability* of optical memory in combination with a localized energy dissipation process at Scale 1 (Naruse et al. 2008c). Optical access to this memory will be automatically recorded due to energy dissipation occurring locally in Scale 1, while at the same time, information will be read out based on Scale 2 behavior. Therefore, such hierarchy enables the traceability of optical memory, which will be important for the security (confidentiality is ensured) and management of digital content.

Shape-engineered metal nanostructures can achieve the hierarchy required for traceable memory (Naruse et al. 2008e). Here, two types of shapes are assumed. The first one (*Shape* I) has two triangular metal plates aligned in the same direction, and the other one (*Shape* II) has them facing each other, as shown in Figure 34.8a. The metal is gold, the gap between the two apexes is 50 nm, the horizontal length of one triangular plate is 173 nm, the angle at the apex is 30°, and the thickness is 30 nm. An incident uniform plane wave with a wavelength of 680 nm is assumed for input light. The polarization is parallel to the *x* axis in Figure 34.8b. Now, Scale 1 is associated with the scale around the gap of the triangles, and Scale 2 is associated with the scale covering both of the triangles, as shown in Figure 34.8a.

Regarding the optical response at Scale 1, as shown in Figure 34.8b, the electric field near the surface (1 nm away from the metal surface) shows an intensity nearly five orders of magnitude higher than the surrounding area. It should also be noted that nearly comparable electric-field enhancements are observed near the apexes of Shapes I and II, which are, respectively, denoted by the squares and circles in Figure 34.8b.

On the other hand, Shapes I and II exhibit different responses at Scale 2. As shown in Figure 34.8c, Shape I exhibits larger scattering cross section compared to Shape II. This indicates that a digital output is retrievable by observing the scattering from the entire structure (Scale 2), where, for example, digital 1 and 0 are associated with Shape I and Shape II, respectively.

In order to experimentally demonstrate the principle, Shapes I and II were fabricated in gold metal plates on a glass substrate by a liftoff technique using EB lithography. A NOM in an illumination collection setup was used with an apertured fiber probe having a diameter of 500 nm, as shown in Figure 34.8d. The light



FIGURE 34.8 (a) Hierarchy in optical near fields by engineering the shape of metal plates at nanometer scale. (b) In Scale 1, both shapes exhibit comparable electric-field enhancement. (c) In Scale 2, they exhibit different system responses. (d) Experimental setup for Scale 2 signal retrieval. (e) Electric field intensity for Scale 2 signals for both Shapes I and II.

source used was a laser diode with an operating wavelength of 780 nm. The distance between the substrate and the probe was maintained at 375 nm. Figure 34.8e shows the electric field intensity depending on the shape of the metal plates, where the Shape I series exhibited larger values compared to the Shape II series, as expected.

Hierarchical nature in optical near-field interactions provides other unique functions. For example, the near-field photoluminescence of semiconductor quantum dots exhibits a hierarchical nature and its spectra diversity is maximized at an optimal scale of the optical near fields. This leads to a novel *non-pixelated memory architecture*, which can simultaneously retrieve a sequence of bits, as opposed to conventional bit-sequential pixelated architecture. The principles have been experimentally verified by InAs quantum dots (Naruse et al. 2008a). Also, a nanophotonic *lock-and-key* system has been demonstrated for the authentication of applications based on shape-engineered nanostructures and their associated optical near fields (Naruse et al. 2008b,d).

34.4 Summary

In this chapter, fundamental nanophotonic system architectures were presented along with two principal physical features of nanophotonics: one is optical excitation transfer and the other is hierarchy in optical near-field interactions. Both of these physical features originate from light–matter interactions on the nanometer scale. It should be emphasized that those basic features provide versatile applications and functionalities besides the example demonstrations shown in the above sections. Also, there are many other degrees-of-freedom in the nanometer scale that need to be deeply understood for systems. Further exploration and attempts to exploit nanophotonics for future devices and systems will certainly be exciting.

References

Akers, S. B. 1978. Binary decision diagrams. *IEEE Trans. Comput.* C-27:509–516.

Arsovski, I., Chandler, T., and Sheikholeslami, A. 2003. A ternary content-addressable memory (TCAM) based on 4T static storage and including a current-race sensing scheme. *IEEE J. Solid-State Circuits* 38:155–158.

Carmichael, H. J. 1999. *Statistical Methods in Quantum Optics I*. Berlin, Germany: Springer-Verlag.

De Souza, E. A., Nuss, M. C., Knox, W. H. et al. 1995. Wavelength-division multiplexing with femtosecond pulses. *Opt. Lett.* 20:1166–1168.

Goodman, J. W., Dias, A. R., and Woody, L. M. 1978. Fully parallel, high-speed incoherent optical method for performing discrete Fourier transforms. *Opt. Lett.* 2:1–3.

Grunnet-Jepsen, A., Johnson, A. E., Maniloff, E. S. et al. 1999. Fibre Bragg grating based spectral encoder/decoder for lightwave CDMA. *Electron. Lett.* 35:1096–1097.

Guilfoyle, P. S. and McCallum, D. S. 1996. High-speed low-energy digital optical processors. *Opt. Eng.* 35:436–442.

Hori, H. 2001. Electronic and electromagnetic properties in nanometer scales. In *Optical and Electronic Process of Nano-Matters*, ed. M. Ohtsu, pp. 1–55. Tokyo: KTK Scientific/Dordrecht, the Netherlands: Kluwer Academic.

Ingold, G.-L. and Nazarov, Y. V. 1992. Charge tunneling rates in ultrasmall junctions. In *Single Charge Tunneling*, eds. H. Grabert and M. H. Devoret, pp. 21–107. New York: Plenum Press.

Inoue, T. and Hori, H., 2005. Quantum theory of radiation in optical near field based on quantization of evanescent electromagnetic waves using detector Mode. In *Progress in Nano-Electro-Optics IV*, ed. M. Ohtsu, pp. 127–199. Berlin, Germany: Springer-Verlag.

Kawazoe, T., Kobayashi, K., Sangu, S. et al. 2003. Demonstration of a nanophotonic switching operation by optical near-field energy transfer. *Appl. Phys. Lett.* 82:2957–2959.

Kawazoe, T., Kobayashi, K., and Ohtsu, M. 2005. Optical nanofountain: A biomimetic device that concentrates optical energy in a nanometric region. *Appl. Phys. Lett.* 86:103102 1–3.

Kocher, P., Jaffe, J., and Jun, B. 1998. Introduction to differential power analysis and related attacks. Cryptography Research. http://www.cryptography.com/resources/whitepapers/DPATechInfo.pdf

Li, B., Qin, Y., Cao, X. et al. 2001. Photonic packet switching: Architecture and performance. *Opt. Netw. Mag.* 2:27–39.

Lin, P.-F. and Kuo, J. B. 2001. A 1-V 128-kb four-way set-associative CMOS cache memory using wordline-oriented tag-compare (WLOTC) structure with the content-addressable-memory (CAM) 10-transistor tag cell. *IEEE J. Solid-State Circuits* 36:666–675.

Liu, H. 2002. Routing table compaction in ternary CAM, *IEEE Micro* 22:58–64.

Maier, S. A., Kik, P. G., Atwater, H. A. et al. 2003. Local detection of electromagnetic energy transport below the diffraction limit in metal nanoparticle plasmon waveguides, *Nat. Mater*. 2:229–232.

Naruse, M., Mitsu, H., Furuki, M. et al. 2004. Terabit all-optical logic based on ultrafast two-dimensional transmission gating. *Opt. Lett.* 29:608–610.

Naruse, M., Miyazaki, T., Kawazoe, T. et al. 2005a. Nanophotonic computing based on optical near-field interactions between quantum dots. *IEICE Trans. Electron.* E88-C:1817–1823.

Naruse, M., Miyazaki, T., Kubota, F. et al. 2005b. Nanometric summation architecture using optical near-field interaction between quantum dots. *Opt. Lett.* 30:201–203.

Naruse, M., Yatsui, T., Nomura, W. et al. 2005c. Hierarchy in optical near-fields and its application to memory retrieval *Opt. Express* 13:9265–9271.

Naruse, M., Kawazoe, T., Sangu, S. et al. 2006. Optical interconnects based on optical far- and near-field interactions for high-density data broadcasting. *Opt. Express* 14:306–313.

Naruse, M., Hori, H., Kobayashi, K. et al. 2007a. Tamper resistance in optical excitation transfer based on optical near-field interactions. *Opt. Lett.* 32:1761–1763.

Naruse, M., Inoue, T., Hori, H. 2007b. Analysis and synthesis of hierarchy in optical near-field interactions at the nanoscale based on Angular Spectrum. *Jpn. J. Appl. Phys.* 46:6095–6103.

Naruse, M., Nishibayashi, K., Kawazoe, T. et al. 2008a. Scale-dependent optical near-fields in InAs quantum dots and their application to non-pixelated memory retrieval. *Appl. Phys. Express* 1:072101 1–3.

Naruse, M., Yatsui, T., Hori, H. et al. 2008b. Polarization in optical near- and far-field and its relation to shape and layout of nanostructures. *J. App. Phys.* 103:113525 1–8.

Naruse, M., Yatsui, T., Kawazoe, T. et al. 2008c. Design and simulation of a nanophotonic traceable memory using localized energy dissipation and hierarchy of optical near-field interactions *IEEE Trans. Nanotechnol.* 7:14–19.

Naruse, M., Yatsui, T., Kawazoe, T., Tate, N. et al. 2008d. Nanophotonic matching by optical near-fields between shape-engineered nanostructures. *Appl. Phys. Express* 1:112101 1–3.

Naruse, M., Yatsui, T., Kim, J. H. et al. 2008e. Hierarchy in optical near-fields by nano-scale shape engineering and its application to traceable memory *Appl. Phys. Express* 1:062004 1–3.

Ohtsu, M. and Hori, H. 1999. *Near-Field Nano-Optics*. New York: Kluwer Academic/Plenum Publishers.

Ohtsu, M. and Kobayashi, K. 2004. *Optical Near Fields*. Berlin, Germany: Springer-Verlag.

Ohtsu, M., Kobayashi, K., Kawazoe, T. et al. 2002. Nanophotonics: Design, fabrication, and operation of nanometric devices using optical near fields. *IEEE J. Sel. Top. Quantum Electron.* 8:839–862.

Ohtsu, M., Kobayashi, K., Kawazoe, T. et al. 2008. *Principles of Nanophotonics*. Boca Raton, FL: Taylor & Francis.

Pohl, D. W. and Courjon, D. eds. 1993. *Near Field Optics*. Dordrecht, the Netherlands: Kluwer Academic.

Tang, Z. K., Yanase, A., Yasui, T. et al. 1993. Optical selection rule and oscillator strength of confined exciton system in CuCl thin films. *Phys. Rev. Lett.* 71:1431–1434.

Tate, N., Nomura, W., Yatsui, T. et al. 2008. Hierarchical hologram based on optical near- and far-field responses. *Opt. Express* 16:607–612.

Wolf, E. and Nieto-Vesperinas, M. 1985. Analyticity of the angular spectrum amplitude of scattered fields and some of its consequences. *J. Opt. Soc. Am. A.* 2:886–890.

35

Nanophotonics for Device Operation and Fabrication

35.1 Introduction 35-1
35.2 Excitation Energy Transfer in Nanophotonic Devices 35-1
35.3 Device Operation 35-3
Nanophotonic AND Gate • Nanophotonic NOT Gate • Interconnection with Photonic Devices
35.4 Nanophotonics Fabrication 35-7
Nonadiabatic Near-Field Optical CVD • Nonadiabatic Near-Field Photolithography
35.5 Summary 35-11
References 35-12

Tadashi Kawazoe
The University of Tokyo

Motoichi Ohtsu
The University of Tokyo

35.1 Introduction

The optical near field is an electromagnetic field that mediates the interaction between nanometric particles located in close proximity to each other. Nanophotonics utilizes this field to realize novel devices, fabrications, and systems. That is, a photonic device with a novel function can be operated by transferring the optical near-field energy between nanometric particles and subsequent dissipation. In such a device, the optical near field transfers a signal and carries the information. Novel photonic systems become possible by using these novel photonic devices. Furthermore, if the magnitude of the transferred optical near-field energy is sufficiently large, structures or conformations of nanometric particles can be modified, which suggests the feasibility of novel photonic fabrications.

Note that the true nature of nanophotonics is to realize "qualitative innovation" in photonic devices, fabrications, and systems by utilizing novel functions and phenomena caused by optical near-field interactions, which are impossible as long as conventional propagating light is used. On reading this note, one may understand that the advantage of going beyond the diffraction limit, that is, "quantitative innovation," is no longer essential, but only a secondary nature of nanophotonics. In this sense, one should also note that optical near-field microscopy, that is, the methodology used for image acquisition and interpretation in a nondestructive manner, is not an appropriate application of nanophotonics because the magnitude of the optical near-field energy transferred between the probe and sample must be extrapolated to zero to avoid destroying the sample.

Quantitative innovation has already been realized by breaking the diffraction limit. Examples include the optical–magnetic hybrid disk storage systems, nanophotonic devices and systems, and photochemical vapor deposition and photolithography. However, it is important to note that these examples also realize qualitative innovation. Details of these examples are described in this chapter.

35.2 Excitation Energy Transfer in Nanophotonic Devices

Kagan et al. observed the energy transfer among CdSe quantum dots (QDs) coupled via a dipole–dipole inter-dot interaction [1]. Crooker et al. also studied the dynamics of the exciton energy transfer in close-packed assemblies of monodisperse and mixed-size CdSe nanocrystal QDs and reported the energy-dependent transfer rate of excitons from smaller to larger dots [2]. These examples are based on the optical near-field interaction. The physical model for the unidirectional resonant energy transfer between QDs via the optical near-field interaction has been presented, and the optically forbidden energy transfer among randomly dispersed CuCl QDs has been demonstrated experimentally using optical near-field spectroscopy [3]. The theoretical analysis and temporal evolution of the energy transfer via the optical near-field interaction were discussed in Ref. [4]. This section reviews the principles of nanophotonic devices and experimental works involving the direct observation of energy transfer from the exciton state in a CuCl QD to the optically forbidden exciton state in another CuCl QD using optical near-field spectroscopy.

Cubic CuCl QDs embedded in an NaCl matrix have the potential to be an optical near-field coupling system that exhibits the optically forbidden energy transfer. This is made possible because for this system, other forms of energy transfer, such as carrier tunneling and Coulomb coupling, can be neglected as the carrier wave function is localized in the QDs; this occurs because the potential depth exceeds 4 eV and the Coulomb interaction is weak due to the small exciton Bohr radius of 0.68 nm in CuCl [3]. The energy transfer via a propagating light is also negligible, since the optically forbidden transition in nearly perfect cubic CuCl QDs is used; that is, the transition to the confined exciton energy levels has an even principal quantum number [5].

So far, this type of energy transfer has not been observed directly because such a nanometric system is usually extremely complex. However, CuCl QDs in a NaCl matrix is a very simple system. The translational motion of the exciton center of mass is quantized due to the small exciton Bohr radius for CuCl QDs, and CuCl QDs become cubic in a NaCl matrix [6–8]. The potential barrier of CuCl QDs in a NaCl crystal can be regarded as infinitely high, and the energy eigenvalues E_{n_x,n_y,n_z} for the quantized Z_3 exciton energy level (n_x, n_y, n_z) in a CuCl QD with side length L depends on the values of quantum numbers n_x, n_y, n_z, and the effective side length $d = (L - a_B)$ found after considering the dead layer correction [6], where a_B is an exciton Bohr radius. The exciton energy levels with even quantum numbers are dipole-forbidden states, which are optically forbidden [5]. However, the optical near-field interaction is finite for such coupling to the forbidden energy state [9].

Figure 35.1 shows schematic drawings of different-sized cubic CuCl QDs (A and B) and the confined exciton Z_3 energy levels. Here, d and $\sqrt{2}d$ are the effective side lengths of cubic QDs A and B, respectively. The quantized exciton energy levels of (1,1,1) in QD A and (2,1,1) in QD B resonate with each other. Under this resonant condition, the coupling energy of the optical near-field interaction is given by the following Yukawa function [9,10]:

$$V(r) = \frac{A}{r}\exp\left(-\frac{\pi\sqrt{3m_p}}{a\sqrt{m_e}}r\right),$$

where

A is a proportional constant

r is the separation between the two QDs

a is the size of the QD

m_p is the effective mass of an exciton–polariton

m_e is the effective mass of an electron



FIGURE 35.1 (a) Schematic drawings of closely located cubic CuCl QDs A and B with effective side lengths ($L - a_B$) of d and $\sqrt{2}d$, respectively, where L and a_B are the side lengths of the cubic quantum dots and the exciton Bohr radius, respectively. (b) Their exciton energy levels. n_x, n_y, and n_z represent quantum numbers of an exciton. E_B is the exciton energy level in a bulk crystal.

Assuming that the two CuCl QDs in the NaCl matrix have side lengths 5 and 7 nm (a size ratio of $1:\sqrt{2}$) and the inter-dot distance is 6.1 nm, then the coupling energy $V(r)$ is 5.05 μeV. This corresponds to an energy transfer time of 130 ps due to the optical near-field coupling, which is much shorter than the exciton lifetime of a few nanoseconds. In addition, the inter-sublevel transition τ_{sub}, from higher exciton energy levels to the lowest, as shown in Figure 35.1, is generally less than a few picoseconds [11] and is much shorter than the transfer time τ_{et}. Therefore, most of the energy of the excitation in a cubic CuCl QD with a side length of d is transferred to the lowest exciton energy level in a neighboring QD with a side length of $\sqrt{2}d$ and recombines radiatively in the lowest level.

The CuCl QDs embedded in NaCl matrix used experimentally were fabricated using the Bridgman method and successive annealing, and the average size of the QDs was found to be 4.3 nm. The sample was cleaved just before the near-field optical spectroscopy experiment to keep the sample surface clean. The cleaved surface of a 100 μm-thick sample was sufficiently flat for the experiment; that is, its roughness was less than 50 nm, at least within a few microns squared. A 325 nm He–Cd laser was used as the light source. A double-tapered fiber probe was fabricated using chemical etching and a 150 nm gold coating was applied [12]. A 50 nm aperture was fabricated using the pounding method [13].

The spatial distributions of the luminescence intensity, that is, near-field optical microscope images, clearly show anti-correlation features in their intensity distributions. This anti-correlation feature can be clarified by noting that these spatial distributions in luminescence intensity represent not only the spatial distributions of the QDs, but also some kind of resonant interaction between the QDs. This interaction induces energy transfer from QDs A (L = 4.6 nm) to QDs B (L = 6.3 nm) because most of the 4.6 nm QDs located close to 6.3 nm QDs cannot emit light, but instead transfer the energy to the 6.3 nm QDs. As a result, in the region containing embedded 6.3 nm QDs, the luminescence intensity from 4.6 nm QDs is low, while the intensity from the 6.3 nm QDs is high at the corresponding position. This anti-correlation feature originates from the near-field energy transfer, which appears for every pair of QDs with different sizes to satisfy the resonant conditions of the confinement exciton energy levels. This is the first spatially resolved observation of energy transfer between QDs via an optical near field. This evidence of the near-field energy transfer between QDs can give rise to a variety of applications, as shown in the following sections.

35.3 Device Operation

Optical fiber transmission systems require increased integration of photonic devices for higher data transmission rates. Since conventional photonic devices, for example, diode lasers and optical waveguides, have to confine light waves within their cavities and core layers, respectively, their minimum sizes are limited by the diffraction of light [14]. Therefore, they cannot meet the size requirement, which is beyond this diffraction limit. An optical near field is free from the diffraction of light and enables the operation and integration of nanometric optical devices. That is, by using a localized optical near field as the carrier, which is transmitted from one nanometric element to another, the above requirements can be met. Based on this idea, nanometer-sized photonic devices have been proposed, which are called *nanophotonic devices* [15]. A nanometric all-optical AND gate (i.e., a nanophotonic switch) is one of the most important devices for realizing nanophotonic integrated circuits, and the operation of a nanophotonic AND gate has been already demonstrated using a coupled QD system.

A logic gate, for example, an AND gate and a NOT gate, is a block in a digital system. Logic gates have some inputs and some outputs, and every terminal is under one of two binary conditions, low (0) or high (1), given by different optical intensities for the optical device. The logic state of the input terminal is controlled by the optical input signal, and the logic state of the output terminal changes depending on the logic state of the input terminals. An intensity of approximately zero and a much higher intensity are preferable in the low and high logic states, respectively, such that the ratio of high to low intensity exceeds 30 db. For nanophotonic devices, the high state (1), which is called "true," is defined simply as the higher intensity state and the low state (0), which is called "false," is defined as the lower intensity state.

Section 35.3.1 presents the operation of nanophotonic AND gates using three CuCl QDs [16,17], while a nanophotonic NOT gate using CuCl QDs is outlined in Section 35.3.2. The optically forbidden energy transfer between neighboring nanostructures via the optical near-field interaction, which was reviewed in Section 35.2, is a key phenomenon for these operations.

35.3.1 Nanophotonic AND Gate

Operation of a nanophotonic AND gate using cubic CuCl QDs embedded in a NaCl matrix has been demonstrated [16,17]. When closely spaced QDs with quantized energy levels resonate with each other, near-field energy is transferred between them, even if the transfer is optically forbidden, as noted in Section 35.2. The output is "true" when both inputs are "true"; otherwise, the output is "false." Figure 35.2a and b explains the "false" and "true" states of the proposed nanophotonic AND gate. Three cubic QDs, $QD_{\text{input A}}$, $QD_{\text{input B}}$, and QD_{output}, are used as the two inputs and output ports of the AND gate, respectively. Assuming an effective size ratio of $1:\sqrt{2}:2$, the quantized energy levels (1,1,1) in $QD_{\text{input A}}$, (2,1,1) in QD_{output}, and (2,2,2) in $QD_{\text{input B}}$ resonate with each other. Furthermore, energy levels (1,1,1) in QD_{output} and (2,1,1) in $QD_{\text{input B}}$ also resonate. In the "false" state operation (Figure 35.2a), for example, input A is "true" and input B is "false," almost all of the exciton energy in $QD_{\text{input A}}$ is transferred to the (1,1,1) level in the neighboring QD_{output}, and then to the (1,1,1) level in $QD_{\text{input B}}$. Therefore, the input energy escapes to $QD_{\text{input B}}$, and consequently no optical output signals are generated from QD_{output}. This means that the output is "false." In the "true" state (Figure 35.2a) when inputs A and B are both "true," the escape route to $QD_{\text{input B}}$ is blocked by the excitation of QD_{inputB} due to state filling in $QD_{\text{input B}}$ on applying the input B signal. Therefore, the input energy is transferred to QD_{output} and an optical output signal is generated. This means that the output is "true." These operating principles are realized with the condition $\tau_{ex} > \tau_{et} > \tau_{sub}$, where τ_{ex}, τ_{et}, and τ_{sub} are the exciton lifetime, energy transfer time between QDs, and inter-sublevel transition time, respectively. Since τ_{ex}, τ_{et}, and τ_{sub} are a few nanoseconds, 100 ps, and a few picoseconds, respectively, for the CuCl QDs used in a NaCl matrix, the condition of operation described in Section 35.2 is satisfied.



FIGURE 35.2 Principle of AND-gate operation. (a) and (b) The "false" and "true" states of the nanophotonic AND gate, respectively.

In an experiment using CuCl QDs embedded in a NaCl matrix, a double-tapered UV fiber probe was fabricated using chemical etching and coated with 150 nm-thick aluminum (Al) film. An aperture less than 50 nm in diameter was formed by the pounding method [13]. To confirm the AND-gate operation, the fiber probe was used to search for a trio of QDs that had an effective size ratio of $1:\sqrt{2}:2$. Since the homogeneous linewidth of a CuCl QD increases with the sample temperature [18,19], the allowance in the resonatable size ratio is 10% at 15 K. The separation of the QDs must be less than 30 nm for operation of the proposed AND gate because the energy transfer time increases with the separation; moreover, it must be shorter than the exciton lifetime. It is estimated that at least one trio of QDs that satisfies these conditions exists in a $2 \times 2\,\mu$m scan area. To demonstrate AND-gate operation, a QD trio had to be found in the sample, as shown in Figure 35.2.

Near-field photoluminescence (PL) pump-probe spectroscopy was used to find the QD trio. Figure 35.3 shows the PL spectrum obtained at the position where the QD trio exists. In this figure, peaks appear at the positions of the (1,1,1) levels in the 4.6 and 3.5 nm QDs. The appearance of the satellite peaks means that the AND-gate system proposed in Figure 35.2 was present in the area under the probe. In other words, a trio of cubic QDs with sizes of 3.5, 4.6, and 6.3 nm existed. Since their effective respective sizes $L - a_B$ were 2.8, 3.9, and 5.6 nm (a_B: an exciton Bohr radius of 0.7 nm in CuCl), the size ratio was close to $1:\sqrt{2}:2$ and they could be used as QD_{inputA}, QD_{output}, and QD_{inputB}, respectively. The pumping to the 6.3 nm QD blocks the energy transfer from the 3.5 and 4.6 nm QDs to the 6.3 nm QD due to state filling of the 6.3 nm QD, and the 3.5 and 4.6 nm QDs emit light that results in the peaks in Figure 35.3. Therefore, a QD trio for a nanophotonic AND gate was found. The PL peak from the 4.6 nm QD corresponds to the output signal in Figure 35.2b. The PL intensity from the 4.6 nm QD was 0.05–0.02 times the PL intensity from the 6.3 nm QD, which was obtained with the probe laser only. This value is quite reasonable considering the pumping pulse energy density of 10 μW/cm² because the probability density of excitons in a 6.3 nm QD is 0.1–0.05 [18], which is close to the PL intensity from the 4.6 nm QD. This result indicates that the internal quantum efficiency of the AND-gate system is close to unity.



FIGURE 35.3 Near-field differential PL spectra measured at the position of a QD trio acting as a nanophotonic AND gate.

In the experiment examining the AND-gate operation, the second harmonics of Ti:sapphire lasers (wavelengths 379.5 and 385 nm), which were tuned to the (1,1,1) exciton energy levels of QD_{inputA} and QD_{inputB}, respectively, were used as the signal light sources for inputs A and B. The output signal was collected by the fiber probe, and its intensity was measured using a cooled microchannel plate after passing through three interference filters of 1 nm bandwidth tuned to the (1,1,1) exciton energy level in QD_{output} at 383 nm. Figure 35.4a and b shows the spatial distribution of the output signal intensity in the "false" state (i.e., with one input signal only) and in the "true" state (i.e., with both input A and input B signals) using near-field spectroscopy at 15 K. The insets in this figure are schematic drawings of the existing QD trio used for the AND gate, which was confirmed by the near-field PL spectra. Here, separation of the QDs by less than 20 nm was estimated theoretically from time-resolved PL measurements, as explained in the next paragraph (see the illustrations in Figure 35.4). In the "false" state, no output signal was observed because the energy of the input signal was transferred to QD_{inputB} and swept out as PL at 385 nm. To quench the output signal in the "false" state, which was generated by accumulating excitons in QD_{inputB}, the input signal density to QD_{inputA} was regulated to less than 0.1 excitons in QD_{inputB}. In the "true" state, a clear output signal was obtained in the dashed circle of Figure 35.4b. The output signal was proportional to the intensity of the control signal, which had a density of 0.01–0.1 excitons in QD_{inputB}.

Next, the dynamic properties of the nanophotonic AND gate were evaluated using the time-correlation single-photon counting method. As a pulse-input B signal source, the 385 nm second harmonic of a mode-locked Ti:sapphire laser was used. The repetition rate of the laser was 80 MHz. To avoid cross talk originating from spectral broadening of the pulse duration between input signals



FIGURE 35.4 Spatial distribution of the output signal from the nanophotonic AND gate in the "false" (a) and "true" (b) states measured using near-field microscopy.



FIGURE 35.5 Temporal evolution of the output signal from the nanophotonic AND gate located in the dashed circle in Figure 35.4b. The duration and repetition rate of the control pulse were 10 ps and 80 MHz, respectively.

A and B, the pulse duration of the mode-locked laser was set to 10 ps. The time resolution of the experiment was 15 ps. Figure 35.5 shows the temporal evolution of the input B pulse signal (lower part) applicable to QD_{inputB} and the output signal (upper part) from QD_{output}. The output signal increases synchronously with the input B pulse within less than 100 ps, which agrees with the theoretically expected result based on the Yukawa model [9]. As this signal rise time is determined by the energy transfer time between the QDs, the separation between the QDs can be estimated from the rise time as being less than 20 nm; the rise time can be shortened to a few picoseconds by decreasing the separation of the QDs. Since the decay time of the output signal is limited by the exciton lifetime, this nanophotonic AND gate can be operated at a few hundred megahertz, and the operating frequency can be increased to several gigahertz by exciton quenching using plasmon coupling [20]. The output signal ratio between "true" and "false" was about 10, which is sufficient for use as an all-optical AND gate, and can be increased using a saturable absorber and electric field enhancement of the surface plasmon [21].

The advantages of this nanophotonic device are its small size and high-density integration capability based on the locality of the optical near field. The figure of merit (FOM) of an optical AND gate should be more important than the switching speed. Here, the FOM is defined as $F = C/Vt_{sw}P_{sw}$, where C, V, t_{sw}, and P_{sw} are the "true"–"false" (ON–OFF) ratio, volume of the device, switching time, and switching energy, respectively. The FOM of the nanophotonic AND gate is 10–100 times higher than that of conventional photonic gates because its volume and switching energy are 10^{-5} times and 10^{-3} times those of conventional photonic gates, respectively.

35.3.2 Nanophotonic NOT Gate

A nanophotonic NOT gate is a key device for realizing a functionally complete set of logic gates for nanophotonic systems, and its operation is demonstrated in this section using CuCl QDs [22]. Figure 35.6 shows a schematic explanation of the nanophotonic NOT gate. QD_{IN} and QD_{OUT} correspond to the input and output terminals of the NOT gate, respectively. Assuming a pair of QDs with a size ratio of $1+\alpha:\sqrt{2}\,(\alpha \ll 1)$, the quantized energy levels with the set of quantum numbers (2,1,1) in QD_{IN} and (1,1,1) in QD_{OUT} are slightly nonresonant with each other. The energy from the optical power supply generates an exciton in QD_{OUT}. Without the input signal (i.e., the input is "false"), the exciton in QD_{OUT} disappears and emits a photon, which is observed as an output signal, as shown in Figure 35.6a. That is, input = "false" and output = "true." Conversely, by applying the input signal (i.e., the input is "true"), the energy level (2,1,1) in QD_{IN} becomes resonant to (1,1,1) in QD_{OUT} due to broadening of its line width. This broadening was confirmed experimentally for CuCl QDs; anti-holes appear on both sides of the spectral hole in the absorption spectrum of CuCl QDs observed in a far-field hole-burning experiment at 5 K. This experimental result shows that the excitation broadens the homogeneous line width of QDs, which might arise from shortening of the phase relaxation time of the excitons in QDs due to carrier–carrier scattering. Consequently, the exciton energy in QD_{OUT} is transferred to QD_{IN} via an optical near-field interaction [3], which suppresses output signal generation (Figure 35.6b, i.e., input = "true" and output = "false"). As a result, the temporal behavior of the output signal is the inverse of that of the input signal. By selecting a suitable threshold to distinguish "true" and "false," these behaviors are used for a NOT gate.

CuCl QDs embedded in a NaCl matrix were used to verify operation of the NOT gate, as CuCl QDs offer discrete energy levels similar to the exciton described in Figure 35.6 [6]. The



FIGURE 35.6 A nanophotonic NOT gate. (a) and (b) Schematic explanation of the "true" and "false" states using cubic QDs.

mean size of the QDs was 4.1 nm and the mean distance between the QDs was 25 nm. In the experiment, the second harmonics of a continuous-wave (CW) Ti:sapphire laser ($\hbar\omega$ = 3.2704 eV) and a mode-locked Ti:sapphire laser ($\hbar\omega$ = 3.2195 eV) were used as the optical power supply and input signal pulse, respectively. The respective power densities were 1 and 2 W/cm^2 at the sample surface. Under the excitation condition, fewer than 0.1 excitons occurred in a QD. These lasers excited the sample from its back and the output signal was observed using a near-field spectrometer in collection mode. The sample temperature was controlled at 15 K. To find the QD pair acting as a nanophotonic NOT gate, the QD positions were mapped by measuring the luminescence distribution on the sample, which was obtained using a near-field spectrometer using He–Cd laser excitation ($\hbar\omega$ = 3.81 eV). The signal was observed after several QD pairs were selected as candidates for nanophotonic NOT-gate operation. Finally, a nanophotonic NOT gate was found, with the probability of about one device per 1 μm^2 of scanning area. Figure 35.7a shows the spatial distribution of the optical near-field output-signal intensity when an input signal is "false" (i.e., with the optical power supply only). Figure 35.7b shows the distribution when the input signal is "true." The insets in this figure are schematic drawings of an existing QD pair that function as a NOT gate, which was confirmed from the PL spectra. The sizes of the two QDs estimated from the wavelengths of their luminescence were 5.0 and 6.3 nm, which satisfy the NOT-gate operation condition, as shown in Figure 35.6. Note that the photon energy of the optical power supply ($\hbar\omega$ = 3.2704 eV) is maintained nonresonant to the (1,1,1) exciton level in the 5.0 nm QD ($\hbar\omega$ = 3.2304 eV) to decrease the artifact originating from the laser by using narrowband optical filters and observing a clear output signal. Sufficiently low optical power was supplied to the 5.0 nm QD from neighboring QDs [3,23]. The NOT-gated signal appears at the center of the dashed circle in Figure 35.7a, from which the size of the device was estimated to be 20 nm. Comparison of Figure 35.7a and b clearly demonstrates the operation of a NOT gate.

The dynamic behavior of the NOT gate was observed using the time-correlation single-photon counting method. Figure 35.8 shows the temporal evolution of the output signal. The horizontal dashed line indicates the output signal level without the input signal pulses (i.e., the input is "false"). Without the input pulses, the signal level is constant, since a CW laser was used as the optical power supply. This signal level is defined as "true." With the input pulses, the output signal increases within a time period shorter than the time resolution of 20 ps due to the artifact of the input pulses, and it decreases to a level lower than the initial level. Here, the signal level lower than the dotted line is defined as "false." Then, the output signal level becomes "false" 50 ps after the "true" input pulse. The fall time of the output signal to the minimum level is about 100 ps, which corresponds to the energy transfer time between QDs. The "false" output signal level recovers to the "true" level within 10 ns. The recovery time is longer than the exciton lifetime in 6.3 nm CuCl QDs (τ_{ex} ~ 1 ns) because the energy transfer from the optical power supply affects the recovery. That is, the recovery time depends on the competition between exciton annihilation via recombination and exciton creation via energy transfer.



FIGURE 35.7 The spatial distribution of the output signal from a nanophotonic NOT gate measured using near-field microscopy at Input = "false" (a) and Input = "true" (b).



FIGURE 35.8 The temporal evolution of the output signal from the nanophotonic NOT gate circled in Figure 35.7.

35.3.3 Interconnection with Photonic Devices

An interconnection device needs to be developed to collect the incident propagating light and drive the nanophotonic device for efficient operation of the system [15,24,25]. Conventional far-field optical devices, such as convex lenses and concave mirrors, cannot be used for this interconnection because of their diffraction-limited operation. This section demonstrates a novel optical device, the *optical nanofountain*, which concentrates optical energy in a nanometric region using optical near-field energy transfer among QDs. This nanometric optical device enables highly efficient interconnection to nanophotonic devices. The optical nanofountain is operated using the energy transfer between QDs via an optical near-field interaction, as shown in Figure 35.1 [9–11]. The unidirectional energy transfer from smaller to larger QDs concentrates the optical energy in a nanometric region. When different sized QDs with resonant energy sublevels are distributed, as shown in Figure 35.9a, energy transfer occurs via the optical near field, as illustrated by the arrows. Light incident to the QD array is ultimately concentrated in



FIGURE 35.9 Optical nanofountain. (a) Schematic explanation of the optical nanofountain and unidirectional energy transfer. (b) Spatial distribution of the PL intensity in an optical nanofountain. The bright spot surrounded by a dashed circle is the focal spot. (c) Spatial distribution of the PL intensity of CuCl QDs for $2.5\,\text{nm} \le L \le 10\,\text{nm}$ ($3.215\,\text{eV} \le E_p \le 3.350\,\text{eV}$) for the same area as in (b). The cubes represent the positions estimated from the PL intensity distribution.

the largest QD. The area of optical energy concentration corresponds to the size of the QD.

The name optical nanofountain was proposed because light spurts from the largest QD after it is concentrated by stepwise energy transfer from smaller neighboring QDs, so that this device looks like a fountain in a basin. From the experimental tests of nanophotonic AND-gate operation in Section 35.3.1, the concentration efficiency of this device should be close to unity because no other possible relaxation paths exist in the system. The operation of an optical nanofountain was demonstrated using CuCl cubic QDs embedded in a NaCl matrix. The average QD size was 4.2 nm and the average separation was less than 20 nm. Although the QDs have an inhomogeneous size distribution and are arranged in the matrix randomly, the operation can be confirmed if an appropriate QD group is found using a nanometric-resolution near-field spectrometer. For the operation, the optimum sample temperature T was 40 K. At $T < 40$ K, the resonant condition becomes tight due to narrowing of the homogeneous line width of the quantized energy sublevels, while at $T > 40$ K, the unidirectional energy transfer is obstructed by the thermal activation of excitons in the QDs. A 325 nm He–Cd laser was used as the excitation light source. A double-tapered UV fiber probe with an aperture 20 nm in diameter was fabricated using chemical etching and coated with a 150 nm-thick Al film to ensure sufficiently high detection sensitivity [12].

Figure 35.9b shows the typical spatial distribution of the PL from QDs operating as an optical nanofountain. The bright spot inside the dashed circle corresponds to a spurt from an optical nanofountain, i.e., the focal spot of the nanometric optical condensing device. The diameter of the focal spot was less than 20 nm, which was limited by the spatial resolution of the near-field spectrometer. From the Rayleigh criterion (i.e., resolution = $0.61 \cdot \lambda/\text{NA}$) [26], its numerical aperture (NA) was estimated to be 12 for $\lambda = 385$ nm. To demonstrate the detailed operating mechanism of the optical nanofountain, we show the size-selective PL intensity distribution; that is, the photon energy is shown in Figure 35.9c. Here, the collected PL photon energy, E_p, was $3.215\,\text{eV} \le E_p \le 3.350\,\text{eV}$, which corresponds to the PL from QDs of size $2.5\,\text{nm} \le L \le 10\,\text{nm}$. The area scanned by the probe are equivalent to those in Figure 35.9b. The PL intensity distribution is shown using a gray scale.

This device can also be used as a frequency selector based on the resonant frequency of the QDs, which can be applied, for example, to frequency domain measurements, multiple optical memories, multiple optical signal processing, and frequency division multiplexing.

Practical nanophotonic devices for room-temperature operation are under development using III–V compound semiconductor QDs [27] and ZnO nanorods [28].

35.4 Nanophotonics Fabrication

This section presents the nonadiabatic processes involved in optical chemical vapor deposition (CVD) and photolithography. These methods have realized qualitative innovation in nanofabrications by utilizing the spatially localized nature of optical near fields.

35.4.1 Nonadiabatic Near-Field Optical CVD

Conventional optical CVD utilizes a two-step process: photodissociation and adsorption. For photodissociation, a propagating light must resonate the reacting molecular gases to excite molecules from the ground state to an excited electronic state. The Franck–Condon principle holds that this resonance is essential for excitation. The excited molecules then relax to the dissociation channel, and the dissociated atoms adsorb to the substrate surface. However, a nonadiabatic photodissociation process is observed in near-field optical chemical vapor deposition (NFO-CVD) under the nonresonant condition of the electronic transition, which violates the Franck–Condon principle. This section discusses the nonadiabatic NFO-CVD of nanometric Zn dots and presents experimental results based on the exciton–phonon–polariton (EPP) model.

Figure 35.10 shows the cross-sectional profiles of the shear-force topographical images after NFO-CVD for photon energies of 5.08 eV ($\lambda = 244$ nm; broken curve) and 2.54 eV ($\lambda = 488$ nm; solid curve) of Zn dots deposited on a sapphire substrate in



FIGURE 35.10 Cross-sectional profiles of the shear-force topographical images of the deposited Zn patterns.

atomic-level steps [29]. In the experiment, diethylzinc (DEZn) was used as the CVD gas source. For the broken curve, the laser power was 1.6 μW and the irradiation time was 60 s. Before carrying out NFO-CVD, 0.4 nm-high atomic-level step structures were clearly observed on the sapphire substrate. After NFO-CVD, they disappeared and a deposited Zn dot less than 50 nm in diameter was seen at the center of the image. This occurred because the optical near field deposited the Zn dot directly under the apex of the fiber probe. Furthermore, since high-intensity propagating light leaks from a bare fiber probe, that is, one without a metallic coating, and is absorbed by the DEZn, a Zn layer was deposited on top of the atomic-step structures.

For the solid curve, the laser power was 150 μW and the irradiation time was 75 s. The photon energy (2.54 eV) was higher than the dissociation energy of DEZn, but it was still lower than the absorption edge of DEZn [30]. Therefore, it was not absorbed by DEZn. However, a Zn dot less than 50 nm in diameter appears at the center. While using conventional CVD with propagating light, a Zn film cannot be grown using a light source with a photon energy lower than the absorption edge (4.13 eV: λ = 300 nm) [31]. Deposited Zn dots were observed on the substrate just below the apex of the fiber probe using NFO-CVD. The atomic-level steps in this figure are still observed, despite the leakage of the propagating light from the bare fiber probe. These curves confirm that Zn dots with a full-width at half-maximum (FWHM) of 30 nm were deposited in the region where the optical near field is dominant.

The dashed curve has 4 nm-high tails on both sides of the dot, which represent the deposition caused by the leaked propagating light. This deposition process is based on the conventional adiabatic photochemical process. In contrast, the solid curve has no tails; therefore, it is clear that the leaked 488 nm propagating light did not deposit a Zn layer. Note that a Zn dot 30 nm in diameter without tails was deposited under nonabsorbed conditions (λ = 488 nm).

Figure 35.11 shows shear-force topographical images of the sapphire substrate after NFO-CVD using an optical near field with photon energies of 3.81 eV (λ = 325 nm) (a), 2.54 eV (λ = 488 nm) (b), and 1.81 eV (λ = 684 nm) (c). The respective laser power and irradiation time were (a) 2.3 μW and 60 s, (b) 360 μW and 180 s, and (c) 1 mW and 180 s. The high quality of the deposited Zn was confirmed by x-ray photoelectron spectroscopy. Furthermore, PL was observed from ZnO dots, which were fabricated by oxidizing the Zn dots deposited by NFO-CVD [8]. In Figure 35.11a, the photon energy ($\hbar\omega$) exceeds the dissociation energy (E_d) of DEZn, and is close to the absorption band edge (E_{abs}) of DEZn, i.e., $\hbar\omega > E_d$ and $\hbar\omega \cong E_{abs}$ [30]. The diameter (FWHM) and height of the topographical image were 45 and 26 nm, respectively. The small tail (shown by the dotted curve) represents a Zn layer less than 2 nm thick, and was deposited by the propagating light leaking from the bare fiber probe. This deposition is possible because the DEZn absorbs some of the propagating light at $\hbar\omega = 3.18$ eV. The very high peak suggests that the optical near field enhances the photodissociation rate at this photon energy because its intensity increases rapidly at the apex of the fiber probe. In Figure 35.11b, the photon energy still exceeds the dissociation energy of DEZn, but is lower than the absorption band edge of DEZn, i.e., $E_{abs} > \hbar\omega > E_d$ [30]. The diameter and height of the image were 50 and 24 nm, respectively. This image has no tail because Zn was not deposited by the high-intensity propagating light leaking from the bare fiber probe. This confirmed that the photodissociation of DEZn and Zn deposition occurred only with an optical near field of $\hbar\omega = 2.54$ eV. Figure 35.11c represents the cases $\hbar\omega < E_d$ and $\hbar\omega < E_{abs}$. Zn dots were deposited successfully at these low photon energies.



FIGURE 35.11 Shear-force topographical images after NFO-CVD at wavelengths of λ = 325 nm (a), 488 nm (b), and 684 nm (c). The laser output power and irradiation time for deposition were 2.3 μW and 60 s (a), 360 μW and 180 s (b), and 1 mW and 180 s (c), respectively.



FIGURE 35.12 The relationship between the photon flux and the rate of Zn deposition. The dotted, solid, and dashed curves represent the calculated values fitted to the experimental results.

The topographical image showed dots with a diameter of 40 nm and a height of 2.5 nm. The experimental results in Figure 35.11 demonstrate dissociation based on a nonadiabatic photochemical process that violates the Franck–Condon principle.

To discuss this novel dissociation process quantitatively, Figure 35.12 shows the relationship between the photon flux (*I*) and the deposition rate of Zn (*R*). For $\hbar\omega = 3.81$ eV (▲), *R* is proportional to *I*. For $\hbar\omega = 2.54$ eV (■) and 1.81 eV (●), higher order dependencies appear and *R* is fitted by the third-order function $R = a_{\hbar\omega}I + b_{\hbar\omega}I^2 + c_{\hbar\omega}I^3$. The respective values of $a_{\hbar\omega}$, $b_{\hbar\omega}$, and $c_{\hbar\omega}$ are $a_{3.81} = 5.0 \times 10^{-6}$, $b_{3.81} = 0$, and $c_{3.81} = 0$ for $\hbar\omega = 3.81$ eV, $a_{2.54} = 4.1 \times 10^{-12}$, $b_{2.54} = 2.1 \times 10^{-27}$, and $c_{2.54} = 1.5 \times 10^{-42}$ for $\hbar\omega = 2.54$ eV, and $a_{1.81} = 0$, $b_{1.81} = 4.2 \times 10^{-29}$, and $c_{1.81} = 3.0 \times 10^{-44}$ for $\hbar\omega = 1.81$ eV. The results of fitting are shown with the solid, dashed, and dotted curves in Figure 35.12. Since no conventional photochemical processes, for example, the Raman process and two-photon absorption, can explain these experimental results, the discussion below uses a unique theoretical model based on the discussion in Ref. [32].

Figure 35.13 shows the potential curves of an electron in a DEZn molecular orbital drawn as a function of the internuclear distance of the C–Zn bond, which is involved in photodissociation [30]. The relevant energy levels of the molecular vibration mode are indicated by the horizontal broken lines in each potential curve. When a propagating light is used, photo-absorption (indicated by the white arrow) triggers the dissociation of DEZn [33]. With an optical near field nonresonant to the electronic state, there are three possible origins of photodissociation [34]: (1) the multiple-photon absorption process; (2) a multiple-step transition process via the intermediate energy level induced by the fiber probe; and (3) multiple-step transition via an excited state of the molecular vibration mode. Case (1) is negligible because the optical power density was less than 10 kW/cm^2.



FIGURE 35.13 Potential curves of an electron in DEZn molecular orbitals. The relevant energy levels of the molecular vibration modes are indicated by the horizontal broken lines.

Case (2) is also negligible because the DEZn was dissociated by ultraviolet–near-infrared light, although DEZn does not have relevant energy levels over such a broad wavelength region. As a result, the experimental results strongly support Case (3). That is, the photodissociation is caused by a transition to an excited state via a molecular vibration mode, which involves three multiple-step excitation processes, as shown in Figure 35.13. Since the system is strongly coupled with the vibration state, it must be considered a nonadiabatic system.

For this consideration, an exciton–phonon polariton (EPP) model was presented in Ref. [32]. The EPP model holds that the optical near fields excite the molecular vibration mode due to the steep spatial gradient. Since the optical near-field energy distribution is spatially inhomogeneous in a molecule due to its gradient, the electrons respond inhomogeneously. As a result, the molecular vibration modes are excited because the molecular orbital changes and the molecule is polarized as a result of the inhomogeneous response of the electrons. The EPP model describes this excitation process quantitatively. The EPP is a quasiparticle, which is an exciton–polariton carrying the phonon (lattice vibration) generated by the steep spatial gradient of the optical field energy distribution. In contrast, since the propagating light energy distribution is homogeneous in a molecule, only the electrons in the molecule respond to the electric field of the propagating light. Therefore, the propagating light cannot excite the molecular vibration.

Zinc-bis(acetylacetonate) (Zn(acac)$_2$) has never been used for conventional optical CVD due to its low optical activity. With NFO-CVD, however, the optical near field can activate the molecule nonadiabatically and the dissociated Zn atom is adsorbed under the fiber probe. Figure 35.14a shows a shear-force topographical image of Zn deposited on a sapphire substrate. The laser power and irradiation time were 1 mW and 15 s, respectively. The Zn dot was 70 nm in diameter and 24 nm high [35,36]. The chemical stability of Zn(acac)$_2$ keeps the substrate surface clean and helps to fabricate an isolated nanostructure. Figure 35.14b shows the shear-force topographical image of a deposited Zn dot that is among the smallest ever fabricated using



FIGURE 35.14 Shear-force topographical images after NFO-CVD using Zn(acac)$_2$ with a 457 nm-wavelength light source. (a) A deposited Zn dot with a diameter of 70 nm and height of 24 nm. (b) A deposited Zn with a diameter of 5 nm and height of 0.3 nm.

NFO-CVD (5 nm in diameter and 0.3 nm high). The deposition conditions consisted of Zn(acac)$_2$ at a pressure of 70 mTorr in the CVD chamber and a laser wavelength, power, and irradiation time of 457 nm, 65 μW, and 30 s, respectively.

35.4.2 Nonadiabatic Near-Field Photolithography

Section 35.4.1 reviewed a unique nonadiabatic photochemical reaction, which was explained using the EPP model. According to this model, the nonadiabatic photochemical reaction can be considered a universal phenomenon and is applicable to several photochemical processes. This section reviews the application of the nonadiabatic photochemical reaction to photolithography, which can be called *nonadiabatic photolithography* [36,37]. For the mass production of photonic and electronic devices, nonadiabatic photolithography can be used because conventional photolithographic components can be applied to this system.

The wave properties of propagating light cause problems for high-resolution photolithography due to diffraction and the dependence on the coherency and polarization of the light source. To fabricate high-density corrugations, the optical coherent length is too long compared to the separation between adjacent corrugation elements, even when a Hg lamp is used. In addition, the absorption by the photoresist is insufficient to suppress interference of scattered light. Furthermore, since the intensity of the propagating light transmitted through a photomask strongly depends on its polarization, the photomask must be designed while considering these dependences. In contrast, the outstanding advantage of nonadiabatic photolithography is that it is free from these problems.



FIGURE 35.15 Experimental results of nonadiabatic photolithography. (a) A schematic of the photomask and Si substrate on which the photoresist (OFPR-800) was spin-coated. (b) Atomic force microscopy images of photoresist OFPR-800 exposed to the g-line of a Hg lamp. (c) AFM images of photoresist OFPR-800 developed after a 4 h exposure with a 672 nm laser.

Figure 35.15a shows a schematic configuration of the photomask and the Si substrate on which the photoresist (OFPR-800: Tokyo-Ohka Kogyo) was spin-coated. They were used in contact mode. Figure 35.15b and c shows atomic force microscopy (AFM) images of the photoresist surface after development. Figure 35.15b shows the result obtained using conventional photolithography. The g-line (436 nm) from a Hg lamp was used as the light source. The fabricated pattern of corrugation was an exact replica of the photomask. Conversely, with nonadiabatic photolithography using a 672 nm-wavelength light source, the grooves on the photoresist appeared along the edges of the Cr mask pattern, as shown in Figure 35.15c. The corrugated pattern was 30 nm deep. The line width was 150 nm, which was narrower than the wavelength of the light source. On the photomask, a steep spatial gradient of optical energy distribution is expected due to optical near fields, while direct irradiation with 672 nm light cannot expose the photoresist. This demonstrated that the photoresist was patterned using a nonadiabatic process.

Figure 35.16 shows AFM images of another photoresist surface (TDMR-AR87 for the 365 nm-wavelength i-line from a Hg lamp: Tokyo-Ohka Kogyo) after development. Figure 35.16a shows the corrugated pattern fabricated using linearly polarized g-line light. Two-dimensional arrays of circles and T-shapes have also been fabricated successfully on this photoresist



FIGURE 35.16 Experimental results of nonadiabatic photolithography. (a) AFM images of photoresist TDMR-AR87 exposed to the linearly polarized g-line of a Hg lamp for 3 s. (b) AFM images of photoresist TDMR-AR87 exposed to the linearly polarized g-line of a Hg lamp for 10 s using a circle-shaped array photomask. (c) AFM images of photoresist OTDMR-AR87 developed after a 40 s exposure to the g-line of a Hg lamp using a T-shaped array photomask.

(see Figure 35.16b and c). This would be impossible using adiabatic photolithography due to its polarization-dependent nature and interference effects.

An optically inactive electron beam (EB) resist film (ZEP-520: ZEON) can also be patterned nonadiabatically. Figure 35.17 shows an AFM image of the developed EB resist surfaces. The light source was the third harmonic of a Q-switched Nd:YAG laser and the exposure time was 5 min. A two-dimensional array of 1 μm-diameter disks was fabricated successfully, even on the EB resist, which would be impossible using propagating light. The developed pattern had a depth of 70 nm, which is sufficient for the subsequent etching of the substrate. Since the EB resist film has an extremely smooth surface, the homogeneity in the contact with the photomask was improved. This suggests that a smooth organic or inorganic thin film can be used as a photoresist irrespective of its optical inactivity.



FIGURE 35.17 AFM image of the surface of an electron beam resist exposed for 5 min using a Q-switched laser (355 nm) and a circle-shaped (1 μm diameter) array photomask.

35.5 Summary

After nanophotonics was proposed by M. Ohtsu in 1993 [38], it now exists as a novel field of optical technology in nanometric space. However, the name "nanophotonics" is occasionally used for photonic crystals [39], plasmonics [40], metamaterials [41,42], silicon photonics [43], and QD lasers [44] using conventional propagating lights. For example, plasmonics utilizes the resonant enhancement of the light in a metal by exciting free electrons. The letters "on" in the word "plasmon" represent the quanta, or the quantum mechanical picture of the plasma oscillation of free electrons in a metal. However, plasmonics utilizes the classical wave optical picture using conventional terminology, such as the refractive index, wave number, and guided mode. Even when a metal is irradiated with light that obeys the laws of quantum mechanics, the quantum mechanical property is lost because the light is converted into the plasma oscillation of electrons, which has a short phase relaxation time. Furthermore, the energy transferred via this interaction must be dissipated in the nanometric particles or adjacent macroscopic materials to fix the position and magnitude of the transferred energy. Since plasmonics does not deal with this local dissipation of energy, it is irrelevant for quantitative innovation by breaking the diffraction limit, or for qualitative innovation. Local energy transfer and its subsequent dissipation have become possible only in nanophotonics by using optical near fields [45,46].

Here, we should consider the stern warning by C. Shannon on the casual use of the term "information theory," which was a trend in the study of information theory during the 1950s [47]. The term "nanophotonics" has been used in a similar way, although some work in "nanophotonics" is not based on optical near-field interactions. For the true development of nanophotonics, one needs deep physical insights into the virtual exciton–polariton and the nanometric subsystem composed of electrons and photons.

References

1. Kagan, C. R., Murray, C. B., Nirmal, M., and Bawendi, M. G., 1996. Electronic energy transfer in CdSe quantum dot solids. *Phys. Rev. Lett.* **76**: 1517–1520.
2. Crooker, S. A., Hollingsworth, J. A., Tretiak, S., and Klimov, V. I., 2002. Spectrally resolved dynamics of energy transfer in quantum-dot assemblies: Towards engineered energy flows in artificial materials. *Phys. Rev. Lett.* **89**: 186802-1–186802-4.
3. Kawazoe, T., Kobayashi, K., Lim, J., Narita, Y., and Ohtsu, M., 2002. Direct observation of optically-forbidden energy transfer between CuCl quantum cubes via optical near-field. *Phys. Rev. Lett.* **88**: 067404-1–067404-4.
4. Sangu, S., Kobayashi, K., Shojiguchi, A., Kawazoe, T., and Ohtsu, M., 2006. Theory and principles of operation of nanophotonic functional devices. In M. Ohtsu (ed.) *Progress in Nano-Electro-Optics V*, Springer-Verlag, New York, pp. 1–62.
5. Tang, Z. K., Yanase, A., Yasui, T., Segawa, Y., and Cho, K., 1993. Optical selection rule and oscillator strength of confined exciton system in CuCl thin films. *Phys. Rev. Lett.* **71**: 1431–1434.
6. Sakakura, N. and Masumoto, Y., 1997. Persistent spectral-hole-burning spectroscopy of CuCl quantum cubes. *Phys. Rev. B* **56**: 4051–4055.
7. Ekimov, A. I., Eflos, AI. L., and Onushchenko, A. A., 1985. Quantum size effect in semiconductor microcrystals. *Solid State Commun.* **56**: 921–924.
8. Itoh, T., Yano, S., Katagiri, N., Iwabuchi, Y., Gourdon, C., and Ekimov, A. I., 1994. Interface effect on the properties of confined excitons in CuCl microcrystals. *J. Lumin.* **60&61**: 396–399.
9. Kobayashi, K., Sangu, S., Ito, H., and Ohtsu, M., 2001. Near-field optical potential for a neutral atom. *Phys. Rev. A* **63**: 013806-1–013806-9.
10. Ohtsu, M., 1998. *Near-Field Nano/Atom Optics and Technology*. Springer, Tokyo, Japan.
11. Suzuki, T., Mitsuyu, T., Nishi, K., Ohyama, H., Tomimasu, T., Noda, S., Asano, T., and Sasaki A., 1996. Observation of ultrafast all-optical modulation based on intersubband transition in n-doped quantum wells by using free electron laser. *Appl. Phys. Lett.* **69**: 4136–4138.
12. Saiki, T., Mononobe, S., Ohtsu, M., Saito, N., and Kusano, J., 1996. Tailoring a high-transmission fiber probe for photon scanning tunneling microscope. *Appl. Phys. Lett.* **68**: 2612–2614.
13. Saiki, T. and Matsuda, K., 1999. Near-field optical fiber probe optimized for illumination-collection hybrid mode operation. *Appl. Phys. Lett.* **74**: 2773–1775.
14. Yariv, A., 1971. *Introduction to Optical Electronics*. Holt, Rinehart & Winston, New York.
15. Ohtsu, M., Kobayashi, K., Kawazoe, T., Sangu, S., and Yatsui, T., 2002. Nano-photonics: Design, fabrication, and operation of nanometric devices using optical near fields. *IEEE J. Select. Top. Quantum Electron.* **8**: 839–862.
16. Kawazoe, T., Kobayashi, K., Sangu, S., and Ohtsu, M., 2003. Demonstration of a nanophotonic switching operation by optical near-field energy transfer. *Appl. Phys. Lett.* **82**: 2957–2959.
17. Kawazoe, T., Kobayashi, K., Sangu, S., and Ohtsu, M., 2003. Demonstrating nanophotonic switching using near-field pump-probe photoluminescence spectroscopy of CuCl quantum cubes. *J. Microsc.* **209**: 261–266.
18. Madelung, O., Schulg, M., and Weiss H., (eds), 1982. *Landolt-Bornstein, Physics of II-VI and I-VII Compounds, Semimagnetic Semiconductors*. vol. 17b. Springer-Verlag, Berlin, Germany.
19. Masumoto, Y., Kawazoe, T., and Matsuura, N., 1998. Exciton-confined-phonon interaction in quantum dots. *J. Lumin.* **76&77**: 189–192.
20. Neogi, A., Lee, C. W., Everitt, H. O., Kuroda, T., Tackeuchi, A., and Yablonovitch, E., 2002. Enhancement of spontaneous recombination rate in a quantum well by resonant surface plasmon coupling. *Phys. Rev. B* **66**: 153305-1–153305-4.
21. Raether, H., 1988. *Surface Plasmons, Vol. III of Springer Tracts in Modern Physics*. Springer-Verag, Berlin, Germany.
22. Kawazoe, T., Kobayashi, K., Akahane, K., Naruse, M., Yamamoto, N., and Ohtsu, M., 2006. Demonstration of nanophotonic NOT gate using near-field optically coupled quantum dots. *Appl. Phys. B* **84**: 243–246.
23. Kawazoe, T., Kobayashi, K., and Ohtsu, M., 2005. Optical nanofountain: A biomimetic device that concentrates optical energy in a nanometric region. *Appl. Phys. Lett.* **86**: 103102-1–103102-3.
24. Nomura, W., Ohtsu, M., and Yatsui, T., 2005. Nanodot coupler with a surface plasmon polariton condenser for optical far/near-field conversion. *Appl. Phys. Lett.* **86**: 181108-1–181108-3.
25. Nomura, W., Yatsui, T., and Ohtsu, M., 2006. Efficient optical near-field energy transfer along an Au nanodot coupler with size-dependent resonance. *Appl. Phys. B* **84**: 257–259.
26. Born, M. and Wolf, E., 1983. *Principles of Optics*, 6th edn. Pergamon Press, Oxford, U.K.
27. Nishibayashi, K., Kawazoe, T., Akahane, K., Yamamoto, N., and Ohtsu, M., 2008. Observation of interdot energy transfer between InAs quantum dots. *Appl. Phys. Lett.* **93**: 042101-1–042101-3.
28. Yatsui, T., Sangu, S., Kawazoe, T., Ohtsu, M., An, S.-J., Yoo, J., and Yi, G.-C., 2007. Nanophotonic switch using ZnO nanorod double-quantum-well structures. *Appl. Phys. Lett.* **90**: 223110-1–223110-3.
29. Yoshimoto, M., Maeda, T., Ohnishi, T., Koinuma, H., Ishiyama, O., Shinohara, M., Kubo, M., Miura, R., and Miyamoto, A., 1995. Atomic-scale formation of ultra-smooth surfaces on sapphire substrates for high-quality thin film fabrication. *Appl. Phys. Lett.* **67**: 2615–2617.
30. Calvert, J. G. and Patts, J. N. Jr., 1996. *Photochemistry*. Wiley, New York.
31. Shimizu, M., Kamei, H., Tanizawa, M., Shiosaki, T., and Kawabata, A., 1988. Low temperature growth of ZnO film by photo-MOCVD. *J. Cryst. Growth* **89**: 365–370.

32. Kobayashi, K., Kawazoe, T., and Ohtsu, M., 2008. Localized photon model including phonons' degrees of freedom. In M. Ohtsu (ed.) *Progress in Nano-Electro-Optics VI*, Springer-Verlag, Berlin, Germany, pp. 41–66.
33. Kawazoe, T., Kobayashi, K., Takubo, S., and Ohtsu, M., 2005. Nonadiabatic photodissociation process using an optical near field. *J. Chem. Phys.* **122**: 024715-1–024715-5.
34. Kawazoe, T., Yamamoto, Y., and Ohtsu, M., 2001. Fabrication of a nanometric Zn dot by nonresonant near-field optical chemical vapor deposition. *Appl. Phys. Lett.* **79**: 1184–1186.
35. Kawazoe, T., Kobayashi, K., and Ohtsu, M., 2006. Near-field optical chemical vapor deposition using Zn(acac)$_2$ with a non-adiabatic photochemical process. *Appl. Phys. B* **84**: 247–251.
36. Kawazoe, T. and Ohtsu, M., 2004. Adiabatic and nonadiabatic nanofabrication by localized optical near fields. *Proc. SPIE* **5339**: 619–630.
37. Yonemitsu, H., Kawazoe, T., Kobayashi, K., and Ohtsu, M., 2007. Nonadiabatic photochemical reaction and application to photolithography. *J. Lumin.* **122–123**: 230–233.
38. Ohtsu, M., (ed). 2006. *Progress in Nano-Electro-Optics V*, Spinger-Verlag, Preface to Volume V: Based on "nanophotonics" proposed by Ohtsu in 1993, OITDA (Optical Industry Technology Development Association, Japan) organized the nanophotonics technical group in 1994, and discussions on the future direction of nanophotonics were started in collaboration with academia and industry.
39. Ho, K. M., Chan, C. T., and Soukoulis, C. M., 1990. Existence of a photonic gap in periodic dielectric structures. *Phys. Rev. Lett.* **65**: 3152–3155.
40. Podolskiy, V. A., Sarychev, A. K., and Shalaev, V. M., 2003. Plasmon modes and negative refraction in metal nanowire composites. *Opt. Express* **11**: 735–745.
41. Shelby, R. A., Smith, D. R., and Shultz, S., 2001. Experimental verification of a negative index of refraction. *Science* **292**: 77–79.
42. Pendry, J. B., 2000. Negative refraction makes a perfect lens. *Phys. Rev. Lett.* **85**: 3966–3969.
43. Rong, H., Liu, A., Nicolaescu, R., and Paniccia, M., 2004. Raman gain and nonlinear optical absorption measurements in a low-loss silicon waveguide. *Appl. Phys. Lett.* **85**: 2196–2198.
44. Arakawa, Y. and Sakaki, H., 1982. Multidimensional quantum well laser and temperature-dependence of its threshold current. *Appl. Phys. Lett.* **40**: 939–941.
45. Ohtsu, M. and Kobayashi, K., 2003. *Optical Near Fields*, vol. 109–150. Springer-Verlag, Berlin, Germany.
46. Ohtsu, M., 2007. Nanooptics. In F. Traeger (ed.) *Handbook of Lasers and Optics*, Springer-Verlag, Berlin, Germany, pp. 1079–1090.
47. Shannon, C., 1956. The bandwagon. *IEEE Trans. Inform. Theory* **2**: 3.

36

Nanophotonic Device Materials

Takashi Yatsui
University of Tokyo

Wataru Nomura
University of Tokyo

36.1 Introduction **36**-1
36.2 Nanophotonic Devices Based on Quantum Dots **36**-1
Discrete Energy Levels in Spherical Quantum Dots • The Observation of Dissipated Optical Energy Transfer between CdSe QDs • Controlling the Energy Transfer between Near-Field Optically Coupled ZnO QDs
36.3 Nanophotonic AND-Gate Device Using ZnO Nanorod Double-Quantum-Well Structures **36**-7
References **36**-11

36.1 Introduction

Systems of optically coupled quantum structures should be applicable to quantum information processing (Bayer et al. 2001, Stinaff et al. 2006). Additional functional devices, i.e., nanophotonic devices (Ohtsu et al. 2002, Kawazoe et al. 2003, 2005, 2006), can be realized by controlling the exciton excitation in quantum dots (QDs) and quantum-well structures (QWs). This chapter reviews the recent achievements with nanophotonic devices based on colloidal QDs (Section 36.2) and nanorod QWs (Section 36.3).

36.2 Nanophotonic Devices Based on Quantum Dots

36.2.1 Discrete Energy Levels in Spherical Quantum Dots

The translational motion of the exciton center of mass is quantized in nanoscale semiconductors when the size is decreased so that it is as small as an exciton Bohr radius. If the QDs are assumed to be spheres with radius R, with the following potential

$$V(x) = \begin{cases} 0 & \text{for } |x| \le R \\ \infty & \text{for } |x| > R \end{cases} \tag{36.1}$$

the quantized energy levels are given by a spherical Bessel function as

$$R_{nl}(r) = A_{nl} j_l\left(\rho_{n,l}\frac{r}{R}\right) \tag{36.2}$$

Figure 36.1 shows the lth order of the spherical Bessel function. Note that an odd quantum number of l has an odd function and it is a dipole-forbidden energy state. To satisfy the boundary conditions as

$$R_{nl}(R) = A_{nl} j_l(\rho_{n,l}) = 0 \tag{36.3}$$

the quantized energy levels are calculated using

$$E(n,l) = E_{\mathrm{B}} + \frac{\hbar^2\pi^2}{2mR^2}\xi_{n,l}^2 \tag{36.4}$$

where $\pi\xi_{n,l} = \rho_{n,l}$ is the nth root of the spherical Bessel function of the lth order. The principal quantum number n and the angular momentum quantum number l take values $n = 1, 2, 3, \ldots$, and $l = 0, 1, 2, \ldots$, respectively. $\xi_{n,l}$ takes values $\xi_{1,0} = 1$, $\xi_{1,1} = 1.43$, $\xi_{1,2} = 1.83$, $\xi_{2,0} = 2$, and so on (see Table 36.1) (Sakakura and Masumoto 1997).

Figure 36.2 show schematic drawings of different-sized spherical QDs (X and Y) and confined exciton energy levels. Here, R and $1.43R$ are the radii of spherical QDs X and Y, respectively. According to Equation 36.4, the quantized exciton energy levels of $E(1,0)$ in QD X and $E(1,1)$ in QD Y resonate with each other. Although the energy state $E(1,1)$ is a dipole-forbidden state, the optical near-field interaction is finite for such coupling to the forbidden energy state (Kobayashi et al. 2000). In addition, the intersublevel transition, τ_{sub}, from higher exciton energy levels to the lowest one, is generally less than a few picoseconds and is much shorter than the transition time due to optical near-field coupling (τ_{ET}) (Suzuki et al. 1996). Therefore, most of the energy of the exciton in a QD X with radius R transfers to the lowest exciton energy level in the neighboring QD Y with a radius of $1.43R$ and recombines radiatively at the lowest level. In this manner, unidirectional energy flow is achieved.



FIGURE 36.1 *l*th order of spherical Bessel function. (a) $l = 0$ ($j_0(x) = (\sin x)/x$), (b) $l = 1$ ($j_1(x) = (1/x)(((\sin x)/x) - \cos x)$), and (c) $l = 2$ ($j_2(x) = (1/x)\,(((3 - x^2)/x^2)\sin x) - ((3/x)\cos x)$).

TABLE 36.1 Calculated $\xi_{n,l}$ to Satisfy the Condition of $j_l(\pi\xi_{n,l}) = 0$

	$l = 0$	$l = 1$	$l = 2$	$l = 3$	$l = 4$	•
$n = 1$	1	1.43	1.83	2.22	2.61	•
$n = 2$	2	2.46	2.90	3.31	•	•
$n = 3$	3	•	•	•	•	•
•	•	•	•	•	•	•



FIGURE 36.2 Schematic drawings of different-sized spherical QDs (X and Y) and the confined exciton energy levels.

36.2.2 The Observation of Dissipated Optical Energy Transfer between CdSe QDs

To evaluate the energy transfer and the energy dissipation, we used CdSe/ZnS core–shell QDs from *Evident Technologies*. As described in Section 36.2.1, assuming that the respective diameters, *D*, of the QD_{a1} and QD_{a2} were 2.8 and 4.1 nm, the ground energy level in the QD_{a1} and the excited energy level in the QD_{a2} resonate (Trallero-Giner et al. 1998). A solution of QDs_{a1} ($D = 2.8$ nm) and QDs_{a2} ($D = 4.1$ nm) in 1-feniloctane at a density of 1.0 mg/mL was dropped on mica substrate (see Figure 36.3a), such that areas *A* and *C* consisted of QDs_{a1} and QDs_{a2}, respectively, while there were both QDs_{a1} and QDs_{a2} in area *B*. Using transmission electron microscopy (TEM), we confirmed the mean center-to-center distance of each QD was maintained at about less than 10 nm in all areas, due to the 2 nm-thick ZnS shell and surrounding ligands (2 nm-length long chain amine) of the QDs (Figure 36.3b).

In the following experiments, the light source used was the third harmonic of a mode-locked Ti:sapphire laser (wavelength 306 nm, frequency 80 MHz, and pulse duration 2 ps). The incident power of the laser was 0.6 mW and the spot size was 1×10^{-3} cm^2. The density of QDs was less than 3.5×10^{12} cm^{-2} and the quantum yield of CdSe/ZnS QD was 0.5. Under these conditions, the probability of exciton generation by one laser pulse in each QD was calculated to be 1.6×10^{-2}. Therefore, we assumed single-exciton dynamics in the following experiments.

The energy transfer was confirmed using micro-photoluminescence (PL) spectroscopy. Temperature-dependent micro-PL spectra were obtained. In the spectral profile of the PL emitted from area *A*, we found a single peak which originated from the ground state of QD_{a1} at a wavelength of $\lambda = 540$ nm, from room temperature to 30 K (broken line in Figure 36.4). From area *C*, the single peak, which originated from the ground state of QD_{a2}, was found at $\lambda = 600$ nm (dotted line in Figure 36.4). By contrast, area *B* had two peaks at room temperature, as shown by solid line in Figure 36.4. This figure also shows that the PL intensity peak at $\lambda = 540$ nm decreased relative to that of at $\lambda = 600$ nm on decreasing the temperature. This relative decrease in the PL intensity originated from the energy transfer from the ground state in the QD_{a1} to the excited state in the QD_{a2} and the subsequent rapid dissipation to the ground state in the QD_{a2}. This is because the coupling between the resonant energy levels becomes stronger due to the increase in the exciton decay time on decreasing the temperature (Itoh et al. 1990). Furthermore, although nanophotonic device operation using CuCl quantum cubes (Kawazoe et al. 2003, 2005, 2006) and ZnO quantum wells (Yatsui et al. 2007) has been reported at 15 K, we observed the



FIGURE 36.3 (a) Schematic images of CdSe QDs dispersed substrate. Areas *A*, *B*, and *C* are covered by QDs_{a1}, both QDs_{a1} and QDs_{a2}, and QDs_{a2}, respectively. (b) TEM image of dispersed CdSe/ZnS core–shell QDs in area *B*.



FIGURE 36.4 Temperature dependence of the micro-PL spectra. Broken, solid, and dotted lines show the spectra from areas *A*, *B*, and *C*, respectively.

decrease in the PL intensity at λ = 540 nm at temperatures as high as 130 K, which is advantageous for the high-temperature operation of nanophotonic devices.

To confirm this energy transfer from QD_{a1} to QD_{a2} at the temperature under 130 K, we evaluated the dynamic property of the energy transfer using time-resolved spectroscopy with the time correlation single photon counting method. Circles A_{a1}, squares B_{a1}, and triangles B_{a2} in Figure 36.5a represent the respective time-resolved micro-PL intensities (60 K) from ground energy level in QD_{a1} ($D = 2.8$ nm) in area *A*, QD_{a1} ($D = 2.8$ nm) in area *B*, and QD_{a2} ($D = 4.1$ nm) in area *B*. The peak intensities at $t = 0$ were normalized to unity. Note that B_{a2} decreases faster than A_{a1}, although these signals were generated from QDs of the same size. In addition, although the exciton lifetime decreases on increasing the QD size, owing to the increased oscillator strength, B_{a2} decreased more slowly than A_{a1} over the range $t < 0.2$ ns (see the inset of Figure 36.5a). Furthermore, as we did not see any peak in the power spectra of A_{a1}, B_{a1}, and B_{a2}, we believe that the temporal signal changes originated from the optical near-field energy transfer and subsequent dissipation. Since the QDs_{a1} in area *B* were near QDs_{a2} whose excited energy level resonates with the ground energy level of the QD_{a1} (see Figure 36.5b), near-field coupling between the resonant levels resulted in the energy transfer from the QD_{a1} to the QD_{a2} and the consequent faster decrease in the excitons of the QD_{a1} in area *B* compared with area *A*. Furthermore, as a result of inflow of the carriers from the QD_{a1} to the QD_{a2}, the PL intensity from the QD_{a2} near the QD_{a1} decayed more slowly than that of the QD_{a1}.

For comparison, we also obtained time-resolved PL profiles of different pairs of CdSe/ZnS QDs. Their diameters were $D = 2.8$ nm (QD_{a1}) and 3.2 nm (QD_{b1}), which means that their energy levels did not resonant with each other. Figure 36.6a shows a schematic image of a sample named area *D*, where QDs_{a1} and QDs_{b1} are mixed with a mean center-to-center distance of less than 10 nm. Circles A_{a1} and diamonds D_{a1} in Figure 36.6b show the time-resolved PL intensity (30 K) from the ground energy level in QDs_{a1} from areas *A* and *D*, respectively. There is no difference in the decay profile. This indicates that the excited carriers in QDs_{a1} did not couple with QDs_{b1} due to their off-resonance and, consequently, no energy was transferred (Figure 36.6c). This supports the postulate that Figures 36.4 and 36.5 demonstrate energy transfer and subsequent dissipation due to near-field coupling between the resonant energy levels of the QDs_{a1} and QDs_{a2}.



FIGURE 36.5 (a) Time-resolved PL intensity profiles from QDs$_{a1}$ in area A (circles A_{a1}), QDs$_{a1}$ in area B (squares B_{a1}), and QDs$_{a2}$ in area B (triangles B_{a2}). The peak intensities were normalized at $t = 0$. (b) Schematic of the respective system configurations in areas A and B.



FIGURE 36.6 (a) Schematic image of CdSe QDs dispersed substrate area D. (b) Time-resolved PL intensity profiles from QDs$_{a1}$ in area A (circles A_{a1}) and QDs$_{a1}$ in area D (diamonds D_{a1}). The peak intensities were normalized at $t = 0$. (c) Schematic of the system configuration in area D.

To discuss the exciton energy transfer from QD$_{a1}$ to QD$_{a2}$ quantitatively, we investigated the exciton dynamics by fitting multiple exponential decay curve functions to curves A_{a1}, B_{a1}, and B_{a2} (Bawendi et al. 1992, Crooker et al. 2003):

$$A_{a1} = R_{S1}\exp\left(\frac{-t}{\tau_{s1}}\right) + R_{S2}\exp\left(\frac{-t}{\tau_{s2}}\right), \quad (36.5)$$

$$B_{a1} = R_S \cdot A_{a1} + R_{tS}\exp\left(\frac{-t}{\tau_t}\right), \quad (36.6)$$

and

$$B_{a2} = R_{L1}\exp\left(\frac{-t}{\tau_{L1}}\right) + R_{L2}\exp\left(\frac{-t}{\tau_{L2}}\right). \quad (36.7)$$

We used double exponential decay for A_{a1} and B_{a2} (Equations 36.5 and 36.7), which corresponds to the non-radiative lifetime (fast decay: τ_{S1} and τ_{L1}) and radiative lifetime of free-carrier recombinations (slow decay: τ_{S2} and τ_{L2}). Given the imperfect homogeneous distribution of the QDs$_{a1}$ in area B, some QDs$_{a1}$ lack energy transfer routes to QD$_{a2}$. However, we introduced the mean energy transfer time τ_t from QDs$_{a1}$ and QDs$_{a2}$ in Equation 36.6. In these equations, we neglected the energy dissipation time of about 1 ps (Guyot-Sionnest et al. 1999) because that is much smaller than exciton lifetimes and energy transfer time. Figure 36.7 shows the best-fitted numerical results and experimental data. Here, we used exciton lifetimes of τ_{S2} = 2.10 ns and τ_{L2} = 1.79 ns. The mean energy transfer time was τ_t = 135 ps, which is comparable with the observed energy transfer time (130 ps) in CuCl quantum cubes (Kawazoe et al. 2003) and ZnO QWs (Yatsui et al. 2007). Furthermore, the relation $\tau_t < \tau_{S2}$ agrees with the assumption that most of the excited excitons in QDs$_{a1}$ transfer to excited exciton energy level in a QD$_{a2}$ before being emitted from QD$_{a1}$.

36.2.3 Controlling the Energy Transfer between Near-Field Optically Coupled ZnO QDs

ZnO is a promising material for room-temperature operation of a nanophotonic device because of its large exciton binding energy (Ohtomo et al. 2000, Huang et al. 2001, Sun et al. 2002). Here, we



FIGURE 36.7 Experimental results (circles, squares and triangles) and fitting curves (broken, solid, and short broken lines) using Equations 36.5 through 36.7 for the PL intensity profiles. The fitting parameters are $R_{S1} = 0.560$, $\tau_{S1} = 2.95 \times 10^{-10}$, $R_{S2} = 0.329$, $\tau_{S2} = 2.10 \times 10^{-9}$, $R_S = 0.740$, $R_{tS} = 0.330$, $\tau t = 1.35 \times 10^{-10}$, $R_{L1} = 0.785$, $\tau_{L1} = 2.94 \times 10^{-10}$, $R_{L2} = 0.201$, $\tau_{L2} = 1.79 \times 10^{-9}$.

used chemically synthesized ZnO QD to realize a highly integrated nanophotonic device. We observed the energy transfer from smaller ZnO QDs to larger QDs with mutually resonant energy levels. The energy transfer time and energy transfer ratio between the two QDs were also calculated from the experimental results (Yatsui et al. 2008).

ZnO QDs were prepared using the sol-gel method (Spanhel and Anderson 1991, Meulenkamp 1998).

1. A sample of 1.10 g (5 mmol) of $Zn(Ac)_2 \cdot 2H_2O$ was dissolved in 50 mL of boiling ethanol at atmospheric pressure, and the solution was then immediately cooled to 0°C. A sample of 0.29 g (7 mmol) of $LiOH \cdot H_2O$ was dissolved in 50 mL of ethanol at room temperature in an ultrasonic bath and cooled to 0°C. The hydroxide-containing solution was then added dropwise to the $Zn(Ac)_2$ suspension with vigorous stirring at 0°C. The reaction mixture became transparent after approximately 0.1 g of LiOH had been added. The ZnO sol was stored at 0°C to prevent particle growth.
2. A mixed solution of hexane and heptane, with a volume ratio of 3:2, was used to remove the reaction products (LiAc and H_2O) from the ZnO sol.
3. To initiate the particle growth, the ZnO solution was warmed to room temperature. The mean diameter of ZnO QD was determined from the growth time, T_g.

Figure 36.8a shows a TEM image of synthesized ZnO dots after the second step. Dark areas correspond to the ZnO QD. This image suggested that monodispersed single crystalline particles were obtained.

To check the optical properties and diameters of our ZnO QD, we measured the photoluminescence (PL) spectra using He–Cd laser (λ = 325 nm) excitation at 5 K. We compared the PL spectra of ZnO QD with T_g = 0 and 42 h (solid and dashed curves in Figure 36.8b, respectively). A redshifted PL spectrum was obtained, indicating an increase in the QD diameter. Figure 36.8c shows the growth time dependence of the QD diameter. This was determined from the effective mass model, with peak energy in the PL spectra, $E_g^{bulk} = 3.35$ eV, $m_e = 0.28$, $m_h = 1.8$, and $\varepsilon = 3.7$ (Brus 1984). This result indicated that the diameter growth rate at room temperature was 1.1 nm/day.

Assuming that the diameters, D, of the QDS and the QDL were 3.0 and 4.5 nm, respectively, E_{S1} in the QDS and E_{L2} in the QDL resonated (Figure 36.9a). An ethanol solution of QDS and QDL was dropped onto a sapphire substrate. The mean surface-to-surface separation of the QD was approximately 3 nm.

The spectra S and L in Figure 36.9b correspond to the QDS and the QDL, with spectral peaks of 3.60 and 3.44 eV, respectively. The curve A in Figure 36.9b shows the spectrum from the QDS and QDL mixture with $R = 1$, where R is the ratio (number of QDS)/(number of QDL). The spectral peak of 3.60 eV, which corresponded to the PL from the QDS, was absent from this curve. This peak was thought to have disappeared due to energy transfer from the QDS to the QDL, because the first excited state of the QDL resonated with the ground state of the QDS. Our hypothesis was supported by the observation that when R was increase by eightfold, the spectral peak from the QDS reappeared (see spectrum C in Figure 36.9b).

To confirm this energy transfer from the QDS to the QDL at 5 K, we evaluated dynamic effects using time-resolved spectroscopy with the time-correlated single photon counting method. The light source used was the third harmonic of a mode-locked Ti:sapphire laser (photon energy 4.05 eV, frequency 80 MHz, and pulse duration 2 ps). We compared the signals from mixed samples with ratios R = 2, 1, and 0.5. The curves T_A ($R = 2$), T_B ($R = 1$), and T_C ($R = 0.5$) in Figure 36.10 show the respective time-resolved PL intensities from the ground state of the QDS (E_{S1}) at 3.60 eV. We investigated the exciton dynamics quantitatively by fitting multiple exponential decay curve functions (Bawendi et al. 1992, Crooker et al. 2003):

$$\text{TRPL} = A_1 \exp\left(\frac{-t}{\tau_1}\right) + A_2 \exp\left(\frac{-t}{\tau_2}\right) \tag{36.8}$$

We obtained average τ_1 and τ_2 values of 144 ps and 443 ps, respectively (see Table 36.2). Given the disappearance of the spectral peak at 3.60 eV in the PL spectra, it is likely that these values corresponded to the energy transfer time from the QDS to the QDL and the radiative decay time from the QDS, respectively. This hypothesis was supported by the observation that the average value of τ_1 (144 ps) was comparable with the observed energy transfer time in CuCl quantum cubes (130 ps) (Kawazoe et al. 2003).



FIGURE 36.8 (a) TEM image of the ZnO QD. The dark areas inside the white dashed circles correspond to the ZnO QD. (b) The PL spectra observed at 5 K. The solid and dashed curves indicate growth time $T_g = 0$ and 42 h, respectively. (c) The growth time dependence of the mean ZnO QD diameter.



FIGURE 36.9 (a) Schematic of the energy diagram between a QDS and QDL. (b) The PL spectra observed at 5 K. The labels S and L indicate QDS and QDL, respectively. The labels A, B, and C indicate mixes with *R* ratios of 1, 4, and 8, respectively.



FIGURE 36.10 Time-resolved PL spectra observed at 5 K. The values of R were 2, 1, and 0.5 for curves T_A, T_B, and T_C, respectively.

TABLE 36.2 Dependence of the Time Constants (τ_1 and τ_2) on R as Derived from the Two Exponential Fits of the Time-Resolved PL Signals and the Coefficient Ratio A_1/A_2

R = QDS/QDL	τ_1 (ps)	τ_2 (ps)	A_1/A_2
2	133	490	12.4
1	140	430	13.7
0.5	160	410	14.4
Average	144	443	

We also investigated the value of coefficient ratio A_1/A_2 (see Table 36.2); this ratio was inversely proportional to R, hence proportional to the number of QDL. This result indicated that an excess QDL caused energy transfer from QDS to QDL, instead of direct emission from the QDS.

We observed the dynamic properties of exciton energy transfer and dissipation between ZnO QD *via* an optical near-field interaction, using time-resolved PL spectroscopy. Furthermore, we successfully increased the energy transfer ratio between the resonant energy state, instead of the radiative decay from the QD. Chemically synthesized nanocrystals, both semiconductor QD and metallic nanocrystals (Brust and Kiely 2002), are promising nanophotonic device candidates, because they have uniform sizes, controlled shapes, defined chemical compositions, and tunable surface chemical functionalities.

36.3 Nanophotonic AND-Gate Device Using ZnO Nanorod Double-Quantum-Well Structures

ZnO/ZnMgO nanorod heterostructures have been fabricated and the quantum confinement effect has been observed from single QW structures (Park et al. 2003, 2004). In this section, we review the time-resolved near-field spectroscopy to demonstrate the switching dynamics that result from controlling the optical near-field energy transfer in ZnO nanorod double-quantum-well structures (DQWs). We observed nutation of the population between the resonantly coupled exciton states of DQWs, where the coupling strength of the near-field interaction decreased exponentially as the separation increased (Yatsui et al. 2007).

To evaluate the energy transfer, three samples were prepared (Figure 36.11a): (1) Single-quantum-well structures (SQWs) with a well-layer thickness of L_w = 2.0 nm (SQWs), (2) DQWs with L_w = 3.5 nm with 6 nm separation (1-DQWs), and (3) three pairs of DQWs with L_w = 2.0 nm with different separations (3, 6, and 10 nm), where each DQW was separated by 30 nm (3-DQWs). ZnO/ZnMgO quantum-well structures (QWs) were fabricated on the ends of ZnO nanorods with a mean diameter of 80 nm using catalyst-free metalorganic vapor phase epitaxy (Park et al. 2002). The average concentration of Mg in the ZnMgO layers used in this study was determined to be 20 atm %.

The far-field PL spectra were obtained using a He–Cd laser (λ = 325 nm) before detection using near-field spectroscopy. The emission signal was collected with an achromatic lens (f = 50 mm). The near-field photoluminescence (NFPL) spectra were obtained using a He–Cd laser (λ = 325 nm), collected with a fiber probe with an aperture diameter of 30 nm, and detected using a cooled charge-coupled device through a monochromator. Blueshifted PL peaks were observed at 3.499 (I_S), 3.429 (I_{1D}), and 3.467 (I_{3D}) eV in the far- and near-field PL spectra (Figure 36.12a). These peaks originated from the respective ZnO QWs because their energies are comparable to the predicted ZnO well-layer thicknesses of 1.7 (I_S), 3.4 (I_{1D}), and 2.2 (I_{3D}) nm, respectively, calculated using the finite square-well potential of the quantum confinement effect in ZnO SQWs (see Figure 36.12b) (Park et al. 2004).

To confirm the near-field energy transfer between QWs, we compared the time-resolved near-field PL (TR_{NFPL}) signals at the I_S, I_{1D}, and I_{3D} peaks. For the time-resolved near-field spectroscopy, the signal was collected using a micro-channel plate through a band-pass filter with 1 nm spectral width. Figure 36.13 shows the typical TR_{NFPL} of SQWs (TR_S), 1-DQWs (TR_{1D}), and 3-DQWs (TR_{3D}).

We calculate the exciton dynamics using quantum mechanical density-matrix formalism (Coffey and Friedberg 1978, Kobayashi et al. 2005), where the Lindblad-type dissipation is assumed for the relaxation due to exciton–photon and exciton–phonon couplings:



FIGURE 36.11 ZnO/ZnMgO nanorod quantum-well-structures. c: *c*-axis of the ZnO stem. (a) Schematic of ZnO/ZnMgO SQWs, DQWs (1-DQWs), and triple pairs of DQWs (3-DQWs). (b) Z-contrast TEM image of 3-DQWs clearly shows the compositional variation, with the bright layers representing the ZnO well layers. Scale bar: 50 nm.



FIGURE 36.12 Near-field time-resolved spectroscopy of ZnO nanorod DQWs at 15 K. (a) NF_S, NF_{1D}, NF_{3D}: near-field PL spectra. FF_S, FF_{1D}, FF_{3D}: far-field PL spectrum of ZnO SQWs ($L_w = 2.0$ nm), 1-DQWs ($L_w = 3.5$ nm, 6 nm separation), and 3-DQWs ($L_w = 2.0$ nm; 3, 6, and 10 nm separation). (b) Well width dependent on the exciton ground state and the first excited state. SQWs: open triangle, 1-DQWs: open circle, 3-DQWs: open square.

$$\dot{\rho} = -\frac{i}{\hbar}[H,\rho] + \sum_n \frac{\gamma_n}{2}\left(2A_n\rho A_n^{\dagger} - A_n^{\dagger}A_n\rho - \rho A_n^{\dagger}A_n\right) \qquad (36.9)$$

where

- ρ is the density operator
- H is the Hamiltonian in the considered system
- $A_n^{\dagger}$ and A_n are creation and annihilation operators for an exciton energy level labeled n
- γ_n is the photon or phonon relaxation constant for the energy level

The exciton population is calculated using matrix elements for all exciton states in the system considered. First, we apply the calculation to a three-level system of SQWs (Figure 36.14a), where the continuum state $\hbar\Omega_C$ is initially excited using a 10 ps laser pulse. Then, the initial exciton population in ZnO QWs is created in $\hbar\Omega_{1S}$, where the energy transfer from $\hbar\Omega_C$ to $\hbar\Omega_{1S}$ is expressed phenomenologically as a Gaussian input signal with a temporal width of $2\sigma_{1S}$ (an incoherent excitation term is added in Equation 36.9), because non-radiative relaxation paths via exciton–phonon coupling make a dephased input signal, statistically. Finally, an exciton carrier relaxes due to the electron–hole recombination with relaxation constant γ_{1S}. Figure 36.14b shows a numerical result and experimental data. Here, we used $2\sigma_{1S} = 100$ ps, and γ_{1S} was evaluated as 460 ps.

A similar calculation was applied for DQWs. We used two three-level systems, coupled via an optical near-field with a



FIGURE 36.13 TR$_S$, TR$_{1D}$, and TR$_{3D}$ show TR$_{NFPL}$ signal obtained at I$_S$, I$_{1D}$, and I$_{3D}$, respectively, using the 4.025 eV (λ = 308 nm) light with a pulse of 10 ps duration to excite the barrier layers of ZnO QWs.

coupling strength of U_{12} (Figure 36.14c). Figure 36.14d shows the numerical results for the exciton population in QWs$_1$ and the experimental data. Here $2\sigma_{1D}$ and $2\sigma_{2D}$ were set at 200 ps, which is twice the value for SQWs, because the relaxation paths extend the barrier energy state in the two quantum wells (QWs). γ_{1D} and γ_{2D} are evaluated as 200 ps. We believe that the faster relaxation for DQWs compared with SQWs reflects the lifetime of the coupled states mediated by the optical near-field. Furthermore, the characteristic behavior that results from near-field coupling appears as the oscillatory decay in Figure 36.14d. This indicates that the timescale of the near-field coupling is shorter than the decoherence time, and that coherent coupled states, such as symmetric and antisymmetric states (Sangu et al. 2004), determine the system dynamics. Furthermore, nutation never appears unless unbalanced initial exciton populations are prepared for $\hbar\Omega_{1D}$ and $\hbar\Omega_{2D}$. In the far-field excitation, only the symmetric state is excited because the antisymmetric state is dipole-inactive. Then, the exciton populations of the two quantum wells are equal and they have the same decay rate. By contrast, in the near-field excitation, both the symmetric and antisymmetric states are excited due to the presence of a near-field probe. Since the symmetric and antisymmetric states have different eigenenergies, the interference of these states generates a detectable beat signal. The unbalanced excitation rate is given by A_1/A_2 = 10 here. From



FIGURE 36.14 The schematic depict the (a) SQWs and (c) 1-DQWs system configurations. $\hbar\Omega_C$: barrier energy state with a central energy. Theoretical results on the transient exciton population dynamics (solid curves) and experimental PL data (filled squares) of (b) SQWs (same as curve TR$_S$ in Figure 36.13) and (d) 1-DQWs (same as curve TR$_{1D}$ in Figure 36.13).



FIGURE 36.15 Evaluation of the nutation frequencies between the QWs. (a) PS_S, PS_{1D}, and PS_{3D} show the power spectrum of TR_S, TR_{1D}, and TR_{3D}, respectively. (b) Separation *D* dependence of frequency of the nutation.

the period of nutation, the strength of the near-field coupling is estimated to be $U_{12} = 7.7\,\text{ns}^{-1}$ (= 4.9 μeV).

We evaluated nutation frequencies using Fourier analysis. In Figure 36.15a, the power spectral density of SQWs (PS_S) does not exhibit any peaks, indicating a monotonic decrease. By contrast, the power spectral density of 1-DQWs (PS_{1D}) had a strong peak at a frequency of $2.6\,\text{ns}^{-1}$. Furthermore, that of 3-DQWs (PS_{3D}) had three peaks at 1.9, 4.7, and $7.1\,\text{ns}^{-1}$. Since, the degree of the coupling strength, which is proportional to the frequency of the nutation, increases as the separation decreases, the three peaks correspond to the signals from DQWs with separations of 10, 6, and 3 nm, respectively. Since the coupling strength $\hbar U$ [eV] is given by $\hbar\pi f$ (f: nutation frequency), $\hbar U$ is estimated as 4.0, 9.9, and 14.2 μeV for DQWs with respective separations of 10, 6, and 3 nm. These values are comparable to that estimated above (U_{12} = 4.9 μeV). Furthermore, the peak intensity for the DQWs with 3 nm separation is much lower than for those with 10 nm separation, which might be caused by decoherence of the exciton state due to penetration of the electronic carrier. Considering the carrier penetration depth, the strong peak of DQWs with 10 nm separation originates from the near-field coupling alone. The solid line in Figure 36.15b shows the separation dependence of the peak frequency. The exponentially decaying dependence represented by this line supports the origin of the peaks in the power spectra from the localized near-field interaction between the QWs.

Next, we performed the switching operation. Figure 36.16a and b explains the "OFF" and "ON" states of the proposed nanophotonic switch, consisting of two coupled QWs. QW_1 and QW_2 are used as the input/output and control ports of the switch, respectively. Assuming L_w = 3.2 and 3.8 nm, the ground exciton state in QW_1 and the first excited state in QW_2 resonate. In the "OFF" operation (Figure 36.16a), all the exciton energy in QW_1 is transferred to the excited state in the neighboring QW_2 and relaxes rapidly to the ground state. Consequently, no output



FIGURE 36.16 The switching operation by controlling the exciton excitation. Schematic of the nanophotonic switch of (a) "OFF" state and (b) "ON" state.



FIGURE 36.17 (a) NF_{ON}, $NF_{Control}$, and NF_{OFF} show NFPL signal obtained with the illumination of input laser alone, control laser alone, and input and control laser, respectively.

signals are generated from QW_1. In the "ON" operation (Figure 36.16b), the escape route to QW_2 is blocked by the excitation of QW_2 owing to state filling in QW_2 on applying the control signal; therefore, an output signal is generated from QW_1.

Figure 36.17 shows the NFPL for the three pairs of DQWs with L_w = 3.2 and 3.8 nm with different separations (3, 6, and 10 nm). Curve NF_{OFF} was obtained with continuous input light illumination from a He–Cd laser (3.814 eV). No emission was observed from the exciton ground state of QW_1 (E_{A1}) or the excited state of QW_2 (E_{B2}) at a photon energy of 3.435 eV, indicating that the excited energy in QW_1 was transferred to the excited state of QW_2. Furthermore, the excited state of QW_2 is a dipole-forbidden level. Curve $NF_{Control}$ shows the NFPL signal obtained with control light excitation of 3.425 eV with a 10 ps pulse. Emission from the ground state of QW_2 at a photon energy of 3.425 eV was observed. Both input and control light excitation resulted in an output signal with an emission peak at 3.435 eV, in addition to the emission peak at 3.425 eV (curve NF_{ON}), which corresponds to the ground state of QW_2. Since the excited state of QW_2 is a dipole-forbidden level, the observed 3.435 eV emission indicates that the energy transfer from the ground state of QW_1 to the excited state of QW_2 was blocked by the excitation of the ground state of QW_2.

Finally, the dynamic properties of the nanophotonic switching were evaluated. We observed TR_{NFPL} signals at 3.435 eV with both input and control laser excitation (see Figure 36.18). The decay time constant was found to be 483 ps. The output signal increased synchronously, within 100 ps, with the control pulse. Since the rise time is considered equal to one-quarter of the nutation period τ (Sangu et al. 2003), the value agrees with those obtained for DQWs with the same well width in the range from τ/4 = 36 ps (3 nm separation) to τ/4 = 125 ps (10 nm separation).



FIGURE 36.18 Near-field time-resolved PL signal with "ON" state.

We observed the nutation between DQWs and demonstrated the switching dynamics by controlling the exciton excitation in the QWs. Examination of the electronic coupling between QWs is now in progress to analyze the detailed switching dynamics. For room-temperature operation, since the spectral width reaches thermal energy (26 meV), a higher Mg concentration in the barrier layers and narrower L_w are required so that the spectral peaks of the first excited state (E_2) and ground state (E_1) do not overlap. This can be achieved by using two QWs with L_w = 1.5 nm (QW_1) and 2 nm (QW_2) with a Mg concentration of 50%, where the energy difference between E_2 and E_1 in QW_2 is 50 meV (Park 2001).

References

Bawendi, M. G., Carroll, P. J., William, L. W., and Brus, L. E. 1992. Luminescence properties of CdSe quantum crystallites: Resonance between interior and surface localized states. *J. Chem. Phys.* 96: 946–954.

Bayer, M., Hawrylak, P., Hinzer, K. et al. 2001. Coupling and entangling of quantum states in quantum dot molecules. *Science* 291: 451–453.

Brus, L. E. 1984. Electron–electron and electron–hole interactions in small semiconductor crystallites: The size dependence of the lowest excited electronic state. *J. Chem. Phys.* 80: 4403–4409.

Brust, M. and Kiely, C. J. 2002. Some recent advances in nanostructure preparation from gold and silver particles: A short topical review. *Colloids Surf. A* 202: 175–186.

Coffey, B. and Friedberg, R. 1978. Effect of short-range Coulomb interaction on cooperative spontaneous emission. *Phys. Rev. A* 17: 1033–1048.

Crooker, S. A., Barrick, T., Hollingsworth, J. A., and Klimov, V. I. 2003. Multiple temperature regimes of radiative decay in CdSe nanocrystal quantum dots: Intrinsic limits to the dark-exciton lifetime. *Appl. Phys. Lett*. 82: 2793–2795.

Guyot-Sionnest, P., Shim, M., Matranga, C., and Hines, M. 1999. Intraband relaxation in CdSe quantum dots. *Phys. Rev. B* 60: R2181–R2184.

Huang, M. H., Mao, S., and Feick, H. 2001. Room-temperature ultraviolet nanowire nanolasers. *Science* 292: 1897–1899.

Itoh, T., Furumiya, M., Ikehara, T., and Gourdon, C. 1990. Size-dependent radiative decay time of confined excitons in CuCl microcrystals. *Solid State Commun*. 73: 271–274.

Kawazoe, T., Kobayashi, K., Akahane, K., Naruse, M., Yamamoto, N., and Ohtsu, M. 2006. Demonstration of nanophotonic NOT gate using near-field optically coupled quantum dots. *Appl. Phys. B* 84: 243–246.

Kawazoe, T., Kobayashi, K., and Ohtsu, M. 2005. Optical nanofountain: A biomimetic device that concentrates optical energy in a nanometric region. *Appl. Phys. Lett*. 86: 103102.

Kawazoe, T., Kobayashi, K., Sangu, S., and Ohtsu, M. 2003. Demonstration of a nanophotonic switching operation by optical near-field energy transfer. *Appl. Phys. Lett*. 82: 2957–2959.

Kobayashi, K., Sangu, S., Itoh, H., and Ohtsu, M. 2000. Near-field optical potential for a neutral atom. *Phys. Rev. A* 63: 013806.

Kobayashi, K., Sangu, S., Kawazoe, T., and Ohtsu, M. 2005. Exciton dynamics and logic operations in a near-field optically coupled quantum-dot system. *J. Lumin*. 112: 117–121.

Meulenkamp, E. A. 1998. Synthesis and growth of ZnO nanoparticles. *J. Phys. Chem. B* 102: 5566–5572.

Ohtomo, A., Tamura, K., Kawasaki, M. et al. 2000. Room-temperature stimulated emission of excitons in ZnO/(Mg, Zn)O superlattices. *Appl. Phys. Lett*. 77: 2204–2206.

Ohtsu, M., Kobayashi, K., Kawazoe, T., Sangu, S., and Yatsui, T. 2002. Nanophotonics: Design, fabrication, and operation of nanometric devices using optical near fields. *IEEE J. Sel. Top. Quantum Electron*. 8: 839–862.

Park, W. I., Yi, G.-C., and Jang, M. 2001. Metalorganic vapor-phase epitaxial growth and photoluminescent properties of $Zn_{1-x}Mg_xO$ (0 < x < 0.49) thin films. *Appl. Phys. Lett*. 79: 2022–2024.

Park, W. I., An, S. J., Long, Y.-J. et al. 2004. Photoluminescent properties of $ZnO/Zn_{0.8}Mg_{0.2}O$ nanorod single-quantum-well structures. *J. Phys. Chem. B* 108: 15457–15460.

Park, W. I., Kim, D. H., Jung, S.-W., and Yi, G.-C. 2002. Metalorganic vapor-phase epitaxial growth of vertically well-aligned ZnO nanorods. *Appl. Phys. Lett*. 80: 4232–4234.

Park, W. I., Yi, G.-C., Kim, M. Y., and Pennycook, S. J. 2003. Quantum confinement observed in ZnO/ZnMgO nanorod heterostructure. *Adv. Mater*. 15: 526–529.

Sakakura, N. and Masumoto, Y. 1997. Persistent spectral-hole-burning spectroscopy of CuCl quantum cubes. *Phys. Rev. B* 56: 4051–4055.

Sangu, S., Kobayashi, K., Kawazoe, T., Shojiguchi, A., and Ohtsu, M. 2003. Quantum-coherence effect in a quantum dot system coupled by optical near fields. *Trans. Mater. Res. Soc. Jpn*. 28: 1035–1038.

Sangu, S., Kobayashi, K., Shojiguchi, A., and Ohtsu, M. 2004. Logic and functional operations using a near-field optically coupled quantum-dot system. *Phys. Rev. B* 69: 115334.

Spanhel, L. and Anderson, M. A. 1991. Semiconductor clusters in the sol-gel process; quantized aggregation, gelation, and crystal growth in concentrated ZnO colloids. *J. Am. Chem. Soc*. 113: 2826–2833.

Stinaff, E. A., Scheibner, M., Bracker, A. S. et al. 2006. Optical signatures of coupled quantum dots. *Science* 311: 636–639.

Sun, H. D., Makino, T., Segawa, Y. et al. 2002. Enhancement of exciton binding energies in ZnO/ZnMgO multiquantum wells. *J. Appl. Phys*. 91: 1993–1997.

Suzuki, T., Mitsuyu, T., Nishi, K. et al. 1996. Observation of ultrafast all-optical modulation based on intersubband transition in n-doped quantum wells by using free electron laser. *Appl. Phys. Lett*. 69: 4136–4138.

Trallero-Giner, C., Debernardi, A., Cardona, M., Menendez-Proupin, M., and Ekimov, A. I. 1998. Optical vibrons in CdSe dots and dispersion relation of the bulk material. *Phys. Rev. B* 57: 4664–4669.

Yatsui, T., Jeong, H., and Ohtsu, M. 2008. Controlling the energy transfer between near-field optically coupled ZnO quantum dots. *Appl. Phys. B* 93: 199–202.

Yatsui, T., Sangu, S., Kawazoe, T., Ohtsu, M., An, S. J., Yoo, J., and Yi, G.-C. 2007. Nanophotonic switch using ZnO nanorod double-quantum-well structures. *Appl. Phys. Lett*. 90: 223110.

37

Waveguides for Nanophotonics

37.1 Introduction 37-1
Basic Types of Waveguides for Nanophotonics • Silicon Nanophotonics
37.2 Fabrication of Planar and Rib Waveguides 37-2
37.3 Experimental Techniques 37-4
Techniques to Study Internal Photoluminescence Propagation in Waveguides • Techniques to Study Propagation of Light from External Sources • Techniques to Study Losses and Optical Amplification in Waveguides
37.4 Main Experimental Observations in Active Si-nc Waveguides 37-7
37.5 Theoretical Description of Active Lossy Waveguides 37-9
37.6 Application of Active Nanocrystalline Waveguides 37-12
Amplification of Light • Other Applications
37.7 Conclusions 37-14
Acknowledgments 37-14
References 37-14

Jan Valenta
Charles University

Tomáš Ostatnický
Charles University

Ivan Pelant
Academy of Sciences
of the Czech Republic

37.1 Introduction

The term *nanophotonics* may be understood as abbreviation from "photonics of nanostructures." This rapidly evolving research area deals with light interaction in nanostructured materials and their applications in photonic devices like light sources, modulators, detectors, etc.

37.1.1 Basic Types of Waveguides for Nanophotonics

Optical waveguides are structures that are able to confine and guide optical electromagnetic field. *Classical waveguides* (optical fibers, Figure 37.1a) use refractive index difference between the core and the cladding layer to guide light by total internal reflection. When the size of waveguide approaches the wavelength of light, the confinement decreases and losses increase. Therefore, the size of practical classical waveguides is limited to several hundreds of nanometers. Somewhat better confinement can be achieved in more complex waveguides with guiding properties determined by the formation of photonic bands due to their regular spatial structure (Figure 37.1b and c): (1) *photonic crystal waveguides* using "defects" in periodic structures of photonic crystals to confine light and (2) *plasmonic waveguides* based on metallic nanostructures with plasmon resonance (see, e.g., Pavesi and Guillot 2006). Due to limited space, we are going to describe only a special type of the "classical" waveguides formed by luminescing silicon nanocrystals (Si-nc).

37.1.2 Silicon Nanophotonics

The recent years can be characterized by the association of microelectronics with optoelectronics or photonics. While the microelectronics is based almost exclusively on silicon (indirect band-gap semiconductor), photonic light sources are currently made out of direct band-gap III–V compounds (family of GaAs materials). In order to reduce the material diversity, an effort to develop an efficient, electrically pumped silicon-compatible light-emitting device is becoming very strong (Pavesi and Lockwood 2004). This tendency to "siliconize photonics" is driven also by the need to reduce the overheating of silicon integrated circuits due to the ohmic resistance of excessively long multilevel metal interconnects (Pavesi and Guillot 2006). Supplementary advantages like the reduction in charging (RC) time constant (speeding up the circuit performance) and prevention from crosstalks can be obtained as a bonus.

Since bulk silicon, as an indirect band-gap semiconductor, is a very bad light emitter, nanometer-sized silicon nanocrystals, brightly luminescent at room temperature, represent one of the possible solutions (Pavesi and Lockwood 2004). It is then expected that the light signal originating in Si-nc and carrying the required information propagates in a low-loss medium, which assures, at the same time, a good directionality of the radiation. It has been discovered recently that slabs of fused quartz SiO_2 "doped" with Si-nc are able to accomplish both the role of a light emitter and that of a waveguide (Khriachtchev et al. 2001, Valenta et al. 2003a, Khriachtchev et al. 2004). We shall call this type of nanophotonic waveguides (which generate the luminous signal themselves and therefore there is no need to



(a) Classical refractive waveguide (b) Photonic waveguide W1



(c) Plasmonic waveguide

FIGURE 37.1 Nanophotonic waveguides: (a) "Classical" waveguide based on total internal reflection using the core with higher refractive index than the cladding. (b) Photonic crystal waveguide formed by a "defect" in the regular structure—here is the W1 waveguide formed by a row of missing holes. (c) Plasmonic waveguide formed by a row of metallic nanocrystals.

couple the light to them from an external source) "active waveguides." In this chapter, we shall describe the preparation methods of active nanocrystalline waveguides, their experimentally observed properties, and relevant theoretical description. We shall also briefly mention their various application possibilities.

37.2 Fabrication of Planar and Rib Waveguides

There have been many various methods of how to grow thin sheets of luminescent Si-nc embedded in an optically transparent matrix: (1) *Implantation of fused quartz* (SiO_2) slabs with Si^+ ions (Figure 37.2) (Cheylan et al. 2000), (2) *reactive Si deposition onto fused quartz* (Khriachtchev et al. 2002), (3) *plasma-enhanced chemical vapor deposition* (PECVD) of substoichiometric silicon oxide SiO_x thin films on a Si substrate (Iacona et al. 2000), (4) *co-sputtering of a Si wafer and a piece of glass* using fused quartz plates or Si wafers as a substrate (Imakita et al. 2005), (5) *crystallization of Si/SiO$_2$ superlattices* with nm-thick amorphous Si or SiO layers (Riboli et al. 2004), and (6) *embedding of porous silicon grains into sol-gel derived SiO$_2$ layers* (Luterová et al. 2004), to list at least the most frequently used. Most of these techniques comprise high-temperature (1100°C–1200°C) annealing of deposited SiO_x films in order to achieve the phase separation between Si-nc and the SiO_2 matrix. The thickness of the resulting sheets containing Si-nc can vary from hundreds of nanometers to tens of micrometers. Due to the difference in refractive index between the matrix ($n_{\text{silica}} \approx 1.45$) and silicon ($n_{\text{Si}} \approx 3$), such sheets act as planar or rib waveguides. Interestingly, the attractive waveguiding features that we are going to discuss, namely, the wavelength selective guiding of light (which can be also called "spectral filtering") and microcavity-like behavior, are critically dependent upon the preparation method: Till now, they have been discovered only in samples fabricated using the first two methods. We describe them in detail.

Implantation of accelerated Si^+ ions can be applied either to fused quartz (silica) slabs or to a thin SiO_2 layer thermally



(a) Implantation (b)

FIGURE 37.2 (a) The schematics of a Si-nc planar waveguide preparation. (b) Refractive index profiles (n as a function of the depth z beneath the surface) of silicon nanocrystalline waveguides (implanted with 400 keV Si^+ ions and different implant fluences), extracted from optical transmission measurements. (After Valenta, J. et al., *J. Appl. Phys.*, 96, 5222, 2004.)

grown on a silicon wafer. Implantation energy varies usually between 30 and 600 keV, and implant fluences (ion doses) are of the order of 10^{16}–10^{17} cm^{-2}. The attractive waveguide properties of fabricated planar waveguides, i.e., pronounced emission line narrowing and high output beam directionality in the visible region, have been found in waveguides prepared from 1 mm thick silica (Infrasil) slabs with optically polished surface and edges, using the implantation energy of 400 keV and the implant fluences 1×10^{17} cm^{-2} to 6×10^{17} cm^{-2}. Because the Si^+ ions are almost monoenergetic, their stopping distance beneath the silica slab surface has only a small dispersion, which results in narrow and slightly skewed implant distribution, as reflected in the resulting refractive index profiles shown in Figure 37.2 (Valenta et al. 2004). Peak excess Si concentration was up to 26 atomic%. Spherical silicon nanocrystals with diameter distribution roughly from 4 to 6 nm were formed by annealing the implanted samples at 1100°C in a nitrogen ambient for 1 h. To enhance several times the luminescence intensity of Si-nc, an additional anneal at 500°C in forming gas ($N_2 + H_2$) for 1 h was applied (Cheylan and Elliman 2001). The last operation promotes enhanced hydrogen passivation of non-radiative defects.

The reactive silicon deposition has yielded substoichiometric SiO_x films on circular 1 mm-thick substrate silica plates (Khriachtchev et al. 2001, 2004). Electron beam evaporation and radio frequency cells were used as silicon and oxygen sources. The SiO_x layer thickness was ~2 μm, and the value of the x parameter varied around $x = 1.70$. The as-grown material contained amorphous Si inclusions. Annealing of these "suboxide" films at 1100°C in nitrogen atmosphere resulted in the formation of well-defined Si-nc with diameters of 3–4 nm, as evidenced by Raman spectroscopy. Extensive investigations of this type of silica waveguides containing Si-nc discovered a small effective optical birefringence inside the layers, however, without radically influencing the properties of the waveguides (Khriachtchev et al. 2007). Refractive index profile across the thickness of these waveguides is flat, unlike the preceding case of the implanted layers.

The reason why Si-nc waveguides fabricated using other techniques do not show the spectral filtering effect are not fully clear at present. Of course, the condition *sine non qua* is asymmetry of the waveguide, i.e., the waveguiding layer must not be sandwiched between two materials (cladding layers) having the same effective refractive index, as we shall see in the next section. One can speculate about several further critical parameters: suitable composition and optical quality of the matrix; suitable density of Si-nc (in the order of 10^{18} cm^{-3}); favorable layer thickness (around 1 μm); excellent flatness and parallelism of both interfaces; and, last but not least, certain optimum value of propagation losses (several dB/cm). The dominant losses in the waveguides under discussion are probably due to self-absorption and Mie light scattering on Si-nc clusters, not due to surface roughness (Pelant et al. 2006).

The above discussion has dealt implicitly with planar waveguides. Rib-loaded waveguides containing nanocrystals seem, in principle, even more desirable for nanophotonic applications. They can be also prepared using the ion implantation technique in either thin SiO_2 films thermally grown on Si or in polished fused quartz slabs, as described above. The rib structure can be formed (using standard photolithography and etching) by two possible means: either before or after the implantation procedure. Figure 37.3a represents schematics of such a rib waveguide structure.



FIGURE 37.3 (a) Sketch of a rib waveguide structure with silicon nanocrystals, prepared on a polished silica slab. The ribs were fabricated by optical lithography before Si^+ implantation. (b) Microscopic (reflection) image of a part of the structure. The spacing between the ribs is 100 μm. (c) Methods to selectively excite the rib waveguides through the TIR prism or the evanescent field of a fiber. (After Skopalová, E., Mode structure in the light emission from planar waveguides with silicon nanocrystals, Diploma thesis, Charles University, Prague, Czech Republic, 2007.)

Lateral confinement of the light in a narrow rib is expected, in comparison with the planar waveguides, to have some advantages: saving considerable space in photonics circuits and offering much wider variability in their design. On the other hand, the transition from the two-dimensional to the one-dimensional case can degrade the optical quality of the waveguide and introduce additional losses, such as those due to sidewall roughness or even due to considerably deformed rib cross section. Indeed, measurements of propagation losses in similar waveguides have given values above 10 dB/cm, and this loss coefficient even increases for rib widths below 4 μm (Pellegrino et al. 2005). Therefore, in what follows, we discuss predominantly the two-dimensional nanocrystalline waveguides, and limited space only will be given to the rib structures.

37.3 Experimental Techniques

37.3.1 Techniques to Study Internal Photoluminescence Propagation in Waveguides

One of the most important advantages of active waveguides is that light sources are embedded in the waveguide. In our material, Si nanocrystals forming the waveguide core can efficiently emit luminescence in the orange-red-infrared spectral range when excited with the UV-blue light (usually focused laser beam). Such internally produced light is automatically coupled to all possible modes of the waveguide: radiation, substrate, and guided modes (see Section 37.5). The emission modes may be distinguished by measuring their propagation direction, spectra, and polarization, which imposes requirements to experimental setup.

Two types of setups can be conveniently applied to study luminescence from active waveguides: (1) The micro-imaging-spectroscopy setup is based on a microscope connected to an imaging spectrograph with a CCD camera (Figure 37.4a). For good angular resolution, low numerical aperture (NA) objective lenses should be used (in our experiments, we used mostly the lens with 2.5 × magnification and NA = 0.075, i.e., an angular resolution of about 8.6°). The sample is fixed to an x–y–z table with a rotating holder and excited by a laser beam (325 nm from the cw He–Cd laser), approximately perpendicular to the objective axis. (2) In order to achieve better angular resolution, an experimental arrangement based on a goniometer is employed (Figure 37.4b). Here, the sample is fixed to the center of the goniometer, and the photoluminescence emission is collected by a silica optical fiber (core diameter 1 mm) rotated around the sample at a distance of 50 mm, giving an angular resolution slightly less than 1° (NA ~ 0.01). The output of the fiber can be coupled to the same detection system (a spectrograph with a CCD camera), as described above.

Typical images observed with the microscopic setup (Figure 37.4a) are illustrated in Figure 37.4c and d. Here, the diameter of the excitation spot, located about 1 mm from the sample edge, is roughly 1 mm. One can easily recognize PL emission from the excited spot as a bright ellipsoid. However, there is also a second



FIGURE 37.4 (a) Micro-spectroscopy setup for studying spatially resolved emission from waveguides, (b) collection of signals from a waveguide using optical fiber mounted on a goniometer. (c,d) Luminescence microimages of the active planar waveguide (obtained with the setup illustrated in panel a), where the elliptical spot is the spot excited by the laser beam and the light line is emission emanating from the sample facet. The inclination of the sample with regard to optical axis is −15° and +15°, respectively. (Adapted from Valenta, J. et al., *J. Appl. Phys.*, 96, 5222, 2004.)

contribution emanating from the facet of the sample. This light is obviously guided in the implanted layer or close to it. The images in Figure 37.4c and d were collected for sample inclination angles of −15° and +15°, respectively, i.e., in a geometry for which the excited spot was observed either directly (Figure 37.4c) or through the substrate (Figure 37.4d). The experimental arrangement shown in Figure 37.4a enables the detection of the PL either from the excited spot or from the edge of sample by positioning the entrance slit of the spectrograph to different locations of the PL image. All experiments described in this chapter were performed at room temperature.

37.3.2 Techniques to Study Propagation of Light from External Sources

The coupling of external light to narrow submicrometer waveguides is a difficult task. The most used approaches are as follows: (1) *Prism coupling of light* from the surface of the sample (Figure 37.5a). Light from Xe lamp, halogen lamp, or LED is collimated into a prism in contact with waveguide. For better optical contact, an immerse liquid should be dropped between the prism and the sample (the best optical contact—i.e., minimizing reflections on interface—is achieved when refractive index of the immersion liquid is between the values for the materials to be connected). A second prism may be placed on the opposite surface of waveguide to couple out the passing beam to avoid total internal reflection. (2) *Direct coupling into the facet* (Figure 37.5b, sometimes called *end-fire coupling*). The edge of the sample can be polished at some angle (here 70°) in order to separate light refracted to the higher index waveguide from light entering lower index substrate. For both the external light coupling setups, the signal can be collected by an optical fiber and guided to the entrance slit of the imaging spectrometer with a CCD detector. The other coupling methods described in literature are *grating coupling* and *evanescent wave coupling* (sometimes called waveguide-to-waveguide coupling) (see Figure 37.5c and d).



FIGURE 37.5 External light coupling into a narrow waveguide: (a) prism coupling, (b) end-fire coupling, (c) grating coupling, and (d) evanescent-wave coupling. (Adapted from Janda, P. et al., *J. Lumin.*, 121, 267, 2006; Pavesi, L. and Guillot, G. (Eds.), *Optical Interconnects. The Silicon Approach*, Springer-Verlag, Berlin, Germany, 2006.)

37.3.3 Techniques to Study Losses and Optical Amplification in Waveguides

The losses in waveguide are divided into *insertion* (*coupling*) *losses* and *propagation losses*, which contain *scattering*, *radiation*, and *absorption* (Figure 37.6a). If the waveguide material can be pumped to reach population inversion, the guided light may be amplified by stimulated emission. In this case, the absorption coefficient α becomes negative and it is called the gain coefficient $g(g = -\alpha)$.

The most used methods to measure losses in waveguides are (Figure 37.6b through e) (1) *"cutback" method* detecting light output from waveguide with different length; (2) *scattering detection* from different points of waveguide surface; (3) *Fabry–Perot resonance* method, which can be applied to waveguides with good facets; and (4) *shifting excitation spot* (SES) method; which can be applied to active waveguides.

Optical gain is measured by the *variable stripe-length* (VSL) method or by the *pump-and-probe* (PP) method. The principle of the VSL method consists in excitation of a narrow stripe-like region at the edge of a sample (Figure 37.7a) (Shaklee and Leheny 1971, Valenta et al. 2003b, Dal Negro et al. 2004). If the pumping is able to induce population inversion in studied material, photons passing through the excited region can be amplified by stimulated emission. It corresponds to a single-pass optical amplifier. If the emission from the sample edge $I^{\mathrm{VSL}}(l,\lambda)$ is detected as a function of the stripe length l, the net optical gain $G(\lambda)$ is calculated from a simple equation

$$I^{\mathrm{VSL}}(l,\lambda) = \frac{I_{\mathrm{sp}}(\lambda)}{G(\lambda)}\left[\exp(G(\lambda)\cdot l) - 1\right], \tag{37.1}$$

where

I_{sp} is the intensity of spontaneous emission

$G(\lambda) = [g(\lambda) - K]$ is net optical gain (K stands for losses and $g(\lambda)$ is material gain coefficient, i.e., negative absorption coefficient) (Valenta et al. 2002)

Equation 37.1 is valid only when $I_{\mathrm{sp}}(\lambda)$ and $g(\lambda)$ are constant over the whole excited stripe. It means that the exciting power density and properties of sample must be uniform. Also, the coupling of the output emission to a detector must be constant, independent of x, for any part of the stripe. In reality, the geometry and emission properties of the sample are never perfectly constant, and the coupling of light is influenced by directionality of emitted light, limited collection angle (NA), the confocal effect of imaging optics, etc. (Valenta et al. 2003b). Therefore, the SES method has been proposed to correct the VSL method (Valenta et al.


Scattering
Coupling
Output
Absorption losses
Guided light
Insertion losses
Radiation
(a)
Input
Output
Detection
$I(\ell)$
ℓ
(b)
Detection
Coupling
ℓ
$I(\ell)$
ℓ
(c)
Reflections
Reflections
Coupling
Detection
$I(\lambda)$
λ
(d)
Excitation
Detection
Active waveguide
ℓ
$I(\ell)$
ℓ
(e)

FIGURE 37.6 (a) Schematic illustration of losses in a waveguide. Methods to measure losses: (b) cutback, (c) scattering light detection, (d) Fabry–Perot resonance, and (e) SES methods.


Excited length
Moving shield
Pumping beam
Edge emission
Distance of the excited spot from the edge
Moving slit
Pumping beam
Edge emission
log I_{ASE} (a.u.)
Exponential increase
Saturation
(a)
Excited length (cm)
log I_{lum} (a.u.)
Exponential decrease
(b)
Distance from edge (cm)

FIGURE 37.7 The principle of the (a) VSL and (b) SES methods and typical dependence of the detected signal as function of the excited length and the distance from edge, respectively (lower panel). (Adapted from Park, J.H. and Steckl, A.J., *Appl. Phys. Lett.*, 85, 4588, 2004.)


Detection
Excitation
$I_{\mathrm{n}}^{\mathrm{SES}}$
1 2 3 4
n
X_0
d_n
Detection
Excitation
$I_{\mathrm{n}}^{\mathrm{VSL}}$
1 2 3 4
n
X_0
$l = n \cdot X_0$

FIGURE 37.8 Schematic illustration of the principle of combining the SES and VSL experiments.

2002). The principle of the SES method takes advantage of the fact that instead of the whole stripe, only small segments are excited and measured separately (Figure 37.7b).

Figure 37.8 illustrates the procedure to compare the VSL and SES results. The most transparent approach consists of SES measurement with the spot width equal to the shift step. Let us assume that the VSL measurement is done using the same elemental steps x_0 as the SES experiment (obviously, also the stripe width and excitation density must be the same for both SES and VSL). Then we can compare the VSL signal I_n^{VSL} for a stripe consisting of n elemental steps ($l = n \cdot x_0$) with integrated SES signal I_n^{iSES}, i.e., sum of SES signals from n steps



FIGURE 37.9 The basic arrangement of the PP experiment for a (a) planar and (b) rib waveguide.

$$I_n^{\text{iSES}} = \sum_{k=1}^{n} I_k^{\text{SES}}.$$

Integrated SES signal should contain the same amount of spontaneous emission as the VSL measurement (including losses and effects of imperfect experimental conditions), the only difference being that in VSL experiment some photons go through the excited area and might be amplified by stimulated emission or affected by induced absorption. Which effect takes place is clear from plotting both I_n^{VSL} and I_n^{iSES} in one figure.

Similarly, we can calculate the differential VSL intensity I_n^{dVSL}, i.e., the difference of signals obtained for stripe lengths $l = n \cdot x_0$ and $l = (n-1) \cdot x_0$

$$I_n^{\text{dVSL}} = I_n^{\text{VSL}} - I_{n-1}^{\text{VSL}}$$

and compare it with I_n^{SES}. Again, the detected signal comes from spontaneous emission in the nth excited spot that is passing through the excited or unexcited area for the dVSL and SES, respectively. In the ideal case, we can use equations $I_n^{\text{dVSL}} = \text{const}\exp[(g-K)d_n]$ and $I_n^{\text{SES}} = \text{const}\exp(-Kd_n)$ to derive the net optical gain $g(\lambda)$

$$g(\lambda) = \frac{\ln\left(I_n^{\text{dVSL}}(\lambda) / I_n^{\text{SES}}(\lambda)\right)}{d_n},$$

where d_n is the distance of the center of the nth spot from the edge.

The PP technique is based on the application of two beams: the first one is pumping the active sample and the second one is testing the state created by the pumping beam. In case of studying stimulated emission, the test beam may be amplified by stimulated emission. In general, the test beam spot must be situated inside the pumping spot in order to test area pumped as homogeneously as possible. In case of pulsed beams, the temporal coincidence of both pumping and testing pulses must be controlled (the test beam may be delayed after pumping pulses to study decay of the effect). If the thickness of the active layer is small, the induced effect on the test beam may be difficult to detect. Therefore, for waveguide samples, the test beam is often coupled to the waveguide, which is excited from the surface (Figure 37.9b). Then, changes of the outcoupled light with and without pumping are detected.

37.4 Main Experimental Observations in Active Si-nc Waveguides

The most important observations for active planar waveguides are (1) spectral filtering; (2) TE (transverse electric) and TM (transverse magnetic) mode splitting; and (3) high directionality of TE, TM mode emission. These effects are illustrated in Figure 37.10; the panel (a) shows that the PL leaving the edge of waveguide layer is substantially different from the PL perpendicular to the layer. The perpendicular PL is formed by a single band that corresponds to the well-known emission of Si nanocrystals, but the edge PL contains two narrow PL bands. Both narrow lines are linearly polarized, one in the direction of the waveguide layer (TE mode) and the second one perpendicular to the layer (TM mode). The spectral position of the TE and TM modes depends on the exact profile of the refractive index, it means on the implantation fluence (see also Figure 37.16, which shows spectra of another set of samples). The panels (b) and (c) illustrate that the TE and TM modes are emitted only in an extremely narrow angle (a few degrees), basically in the direction of the waveguide plane (only slightly inclined to the substrate, i.e., under positive angles in our notation).



FIGURE 37.10 PL spectra of five fused silica slabs implanted to the fluences of 4×10^{17} cm^{-2} to 6×10^{17} cm^{-2}. (a) Upper curves (a single wide band) correspond to PL emitted in a direction perpendicular to the waveguide, while lower spectra with doublet peaks are facet-PL detected in a direction $\alpha = 5°$ (a sketch of the experimental arrangement is shown in the inset). (b) Angle-resolved facet PL spectra of the sample 6×10^{17} cm^{-2}. (c) Polar representation of integrated PL intensity of the angle-resolved facet spectra from the panel b. Most of the PL intensity is emitted in a direction close to 0°. (Adapted from Janda, P. et al., *J. Lumin.*, 121, 267, 2006.)

The coupling and propagation of *external* light in active Si-nc waveguides were studied by the direct (end-fire) and the prism coupling (Figure 37.5a and b). The results for one sample are illustrated in Figure 37.11. For prism coupling, two broad transmission bands (in the blue and red spectral region) are observed in the measured spectral range. The positions of both bands coincide with those of the PL modes (Figure 37.10a). Our calculations show that the red and blue bands corresponds to the second and third order of substrate modes (the first order being in the infrared region), see Section 37.5 and Figure 37.14. Broadening of the mode structure may be a consequence of the very low number of reflections undertaken by coupled light before escaping to the substrate. Coupling of external light through a truncated facet (Figure 37.5b) gives the best result for a coupling angle $\gamma \sim 20°$, as expected (Figure 37.11, upper curves). In this configuration, the narrow and polarization-split peaks at an output angle $\alpha \sim 2°$ are detected. The peaks are, however, not transmission but absorption peaks. This can be understood if it is assumed that the detected light comes not from substrate modes (which represent a small portion of transmitted light) but from filtered transmitted light propagating almost parallel to the Si-nc waveguide from which a part of power escaped to the substrate modes that are, however, gradually absorbed in the waveguide core. The blue third order modes are much stronger compared to second order because of higher absorption in the blue spectral region.

Experimental observation of rib waveguides indicates (Figure 37.12) that normal guiding of light is improved—see increased intensity of the long-wave edge of PL spectra in Figure 37.12a and b. This is due to the introduction of confinement in the second lateral direction of waveguide (in this case, the confining refractive index profile is symmetrical and the contrast higher (compared to the implanted layer profile) as the surrounding medium is air). On the other hand, roughness of



FIGURE 37.11 Comparison of transmission spectra of a sample 5.5×10^{17} cm^{-2} obtained by the direct facet-coupling (upper curves, solid line—no polarization, dashed and dotted lines correspond to TE and TM polarization, respectively) and by the prism coupling (lower spectrum). (Adapted from Janda, P. et al., *J. Lumin.*, 121, 267, 2006.)



FIGURE 37.12 Comparison of the edge PL spectra from planar and rib waveguides (dashed and continuous line, respectively) in samples implanted to a fluence of (a) 3×10^{17} cm^{-2}, (b) 4×10^{17} cm^{-2}, (c) 5×10^{17} cm^{-2}, and (d) 6×10^{17} cm^{-2}.

the rib edges can introduce significant losses due to scattering. The influence of rib structure on the substrate (leaky) modes is less significant (see Figure 37.12c and d). This is because these modes propagate mostly in substrate, where the effect of side walls is negligible.

37.5 Theoretical Description of Active Lossy Waveguides

Light coupling to a waveguide and its further propagation may be understood in terms of coupling between the waveguide modes and nanocrystals emitting photons. Light field inside the waveguide may be expressed as a coherent superposition of excited waveguide modes, which arise as a solution of a homogeneous wave equation with proper boundary conditions [the waveguide modes are an orthonormal basis of the waveguide optical field (Snyder and Love 1983)]. It is therefore necessary to distinguish between various types of the waveguide modes in order to explain different types of energy transport in the waveguides.

Let us consider a common model structure with three transparent layers (see Figure 37.13): the top *cladding* layer with the refractive index n_1, the bottom *substrate* with the refractive index n_3, and the *core* with the refractive index $n_2 > n_3 > n_1$ and thickness d. We may imagine the modes as rays emerging from inside the waveguide core and propagating toward one of the core boundaries. At the boundary, the ray may be either totally reflected back to the core or it may be partially reflected and partially refracted. The ray then travels toward the other boundary where it totally or partially reflects again. Only those modes that are totally reflected twice during one round-trip may propagate in the core without losses: these are the common *guided modes*. There are, in addition, lossy modes that are called the *substrate radiation modes* (they are refracted only into the substrate) and the *radiation modes* refracted both to the substrate and the cladding.

In many applications, considering traveling of light at large distances compared to its wavelength (and thus working in the far-field limit), we may consider only the guided modes as efficient carriers of energy between a source and a detector. In silicon-based nanophotonics devices, however, the situation may be even more complicated. The typical distances between components on a chip may be comparable to the light wavelength and the far-field approach fails. It is therefore important to analyze an influence of the substrate radiation modes on the response. We may rule out the radiation modes at this stage: compared to the substrate modes, they play only a negligible role in the overall system behavior.



FIGURE 37.13 Schematic representation of propagation and decoupling of substrate modes.

Once light is emitted by a nanocrystal inside the waveguide mode, it undergoes internal reflections at the core/cladding and the core/substrate boundaries. The overall intensity of electric field of an excited mode inside the waveguide core may be written as superposition of the partial waves:

$$E_{\text{mode}}(\lambda,\theta_2) = E_0(\lambda)\left(1 + r_{21}r_{23}\exp\left[\frac{4\pi i n_2 d\cos(\theta_2)}{\lambda}\right] + \cdots\right)$$
$$= \frac{E_0(\lambda)}{1 - r_{21}r_{23}\exp[4\pi i n_2 d\cos(\theta_2)/\lambda]}. \qquad (37.2)$$

Here, r_{21} and r_{23} are the reflection coefficients at the respective boundaries, which depend upon the propagation angle θ_2. The wavelength is λ and $E_0(\lambda)$ is an effective emission amplitude of a nanocrystal to the waveguide mode. Considering the guided modes and thus $|r_{21}| = |r_{23}| = 1$, the electric field intensity reveals sharp resonances implying there are well-defined discrete guided modes. The energy carried by each mode is finite, indeed. Unlike the guided modes, the electric field intensity is finite for the substrate modes and there are no sharp resonances in the spectra. We may, however, resolve some weak resonances, depending on the phase factor of the term $r_{21}r_{23}\exp[4\pi i n_2 d\cos(\theta_2)/\lambda]$: the electric field is maximum if this term is positive and real.

It is clear from the ray optics that there are substrate modes that refract to the substrate at the angles near $\pi/2$, which means that they propagate nearly parallel to the core/substrate boundary; these modes may be understood as a crossover between the guided modes and the substrate radiation modes which decouple rapidly from the core, possessing mixed characteristics of the both types of modes. As the modes may be assigned to a distinct guided mode of the *n*th order (energy of the substrate mode is slightly below the cutoff energy of the *n*th guided mode), we denote each series of the substrate modes to be of the *n*th order (see Figure 37.14). The Fresnel formulae give us $|r_{21}| = 1$ and $|r_{23}| \approx 1$ in such a case (Figure 37.15), and it is then clear from Equation 37.2 that these substrate modes reveal sharp resonances in the spectra (for a fixed angle $\theta_2 < \arcsin(n_2/n_3)$). Energy carried by the substrate modes may be therefore comparable to the energy carried by guided modes. The most important point here is that this type of substrate modes cannot be experimentally distinguished from the guided modes at short distances from the source as they propagate near the core/substrate boundary. The substrate modes therefore significantly contribute to the system response and they may play an important role in many experiments as well as in real on-a-chip devices.

Although the guided and the substrate modes propagate in a similar direction, they may behave in very different ways because they propagate in two different environments. In our particular case, the guided modes are mostly localized inside the waveguide core doped by Si-nc, providing a possibility of reabsorption or optical amplification. The substrate modes, on the contrary, propagate in a transparent substrate and they are therefore neither amplified nor attenuated. Rigorous derivation of PL spectra in real waveguides accounting for losses or amplification, decoupling of the light from the waveguide and real detection geometry is presented elsewhere (Ostatnický et al. 2008); here, we summarize only the main results.

Considering lossy waveguide core, the substrate modes become dominant in the optical response of a waveguide when detected in the direction parallel to the core/substrate boundary using a



FIGURE 37.14 **(See color insert following page 20-14.)** Calculated spectral positions of the substrate modes as a function of (a) the refractive index contrast $\Delta n = n_2 - n_3$ and (b) the relative thickness of the waveguide core compared to the sample 5×10^{17} Si cm^{-2}. Gray scale indicates intensity from black up to white for the highest intensity. Several orders of modes are seen starting from the first one in infrared region.



FIGURE 37.15 Reflectance $R = |r_{ij}|^2$ and phase shifts ϕ on the planar boundary between two dielectric media plotted for TE and TM modes versus incident angle θ. S and G stand for substrate and guided modes, respectively. (Adapted from Pelant, I. et al., *Appl. Phys. B*, 83, 87, 2006.)



FIGURE 37.16 **(See color insert following page 20-14.)** (a) Photograph of the edge of a set of Si^+ ion implanted layers with direction of PL indicated by arrows, the edge is on the left. (b) Measured PL from samples implanted to different Si ion fluences in standard (the broadest curves) and waveguiding geometry (black lines, the slightly lighter gray lines stand for TE and TM resolved polarizations). (c) Theoretically calculated PL spectra. We note that these results were obtained on different set of samples than in Figure 37.10. The mode positions are not exactly the same for samples with identical implantation dose because the annealing conditions were slightly different. Therefore, the refractive index profiles are not identical. (Adapted from Pelant, I. et al., *Appl. Phys. B*, 83, 87, 2006.)

detector with a small numerical aperture. This situation is clearly illustrated through the comparison of our experimental data with the theoretical estimates in Figure 37.16 (we considered a continuous refractive index profile in our calculations). The broad part of the emission spectra originates from the (attenuated) guided modes and the narrow peaks are due to the substrate modes. The double-peak structure is further resolved as two single peaks with the respective TE and TM polarizations. In order to explain this point, we should remark that the coefficient r_{23} is real for the substrate modes while the coefficient r_{21} is in general complex. Considering a fixed angle of incidence θ_2, r_{21} gives different values of the phase shift for the respective TE and TM polarizations (see Figures 37.14 and 37.15). Therefore, the resonance condition is met at different wavelengths for different polarizations. From these considerations, the necessity of waveguide asymmetry for the appearance of the TE–TM polarization–resolved modes follows.

The TE–TM splitting was also reported in Khriachtchev et al. (2004), but the respective peaks have an opposite order in the spectra compared to our experiments. Our numerical calculations have shown that the TE–TM splitting depends strongly on the refractive index profile of the waveguide core. For the three-layer structures, the TE mode is positioned always at the high-energy side of the PL spectra. It is, nevertheless, possible to fabricate a structure with multiple layers or with a graded refractive index profile, which provides an arbitrary TE–TM splitting (including both negative and positive values and also their degeneracy); this feature is well illustrated in Figure 37.14b, where the respective TE and TM modes interchange depending on the thickness of the guiding layer.

The appearance of the substrate modes is well controllable by the parameters of the particular layers of the waveguide. Clearly, the optical thickness of the core d determines the resonance condition through the exponent in the denominator in Equation 37.2 and the ratio n_2/n_1 has influence on the phase of the r_{21} term. The latter may be used in detectors integrated on a chip—the cladding can be made of a material that changes its refractive index due to the changes of the surrounding environment conditions, and the position of the emission peak may then



FIGURE 37.17 (a) Measured PL spectra at different detection angles α relative to the waveguide axis. (b) Numerical simulation of the measurements from the panel a. The sample with an implantation fluence of 5×10^{17} cm^{-2}. (Adapted from Ostatnický, T. et al., Guiding and amplification of light due to silicon nanocrystals embedded in waveguides, in Khriachtchev, L. (ed.), *Silicon Nanophotonics*, World Scientific, Singapore, 2008, pp. 267–296.)

be correlated with some external variable (temperature, pH, etc., see Figure 37.20) (Luterová et al. 2006).

As the sharp resonance in the spectra of the substrate modes is restricted only to the region where $r_{23} \approx 1$, we may expect disappearance of the substrate modes at large detection angles, i.e., when the substrate modes do not propagate parallel to the core/substrate boundary. This feature is illustrated in Figure 37.17 in comparison to the experimental and the theoretical data. We see a very good agreement justifying the correctness of our model.

An important aspect of nanodevices is the magnitude of the decoupling length for the substrate modes, i.e., the distance at which the substrate modes completely leak out from the waveguide core. Our calculations (Ostatnický et al. 2008) show that this distance may be few micrometers but also it may be as large as several hundreds of micrometers. As a consequence, the appearance of the substrate modes and their decoupling from the waveguide core may be of a big importance in nanodevices on the contrary to the fiber optics where the optical response to any excitation is provided solely by the guided modes at the typical distances of the order from meters to kilometers.

37.6 Application of Active Nanocrystalline Waveguides

37.6.1 Amplification of Light

The significant narrowing of substrate leaky mode emission suggests immediately that optical amplification could be responsible for this observation. The VSL method (described in Section 37.3.3) has been applied to the planar asymmetric Si-nc waveguides in several laboratories (Khriachtchev et al. 2001, Ivanda et al. 2003, Luterová et al. 2005). It is tempting to interpret the frequently observed initial weak exponential growth of the VSL curve (Figure 37.18a) as a manifestation of the occurrence of optical gain. High output directionality of the substrate mode emission apparently supports such interpretation. However, it has turned out that, as shown above, it is very difficult if not impossible to evaluate correctly the optical gain magnitude of the substrate modes because the nonlinear growth can originate in the mode leaking itself. Figure 37.18 demonstrates that the evaluation of the VSL experiments can yield a false optical gain if proper comparison between the VSL and SES results is not taken into account. On the other hand, VSL measurements employing a high pulsed laser excitation, performed on a similar sample, revealed a characteristic switch from the light attenuation ($G < 0$) to amplification ($G > 0$) with increasing excitation energy density (Figure 37.19). It may be also of interest here to call the reader's attention to recent articles reporting firmly positive optical gain on leaky



FIGURE 37.18 VSL and SES measurements on a sample implanted to the dose of 4×10^{17} cm^{-2} under continuous wave excitation 325 nm, 0.26 W/cm^2: (a) VSL measurement at the peak of TE and TM modes and for non-guided PL around 825 nm. The fits (lines) give values of $G = 35$ and 28 cm^{-1} for TE and TM modes, respectively, and losses of 11 cm^{-1} for non-guided PL. (b) Results of the SES measurement performed under identical conditions as the VSL. (c) Integration of data from panel (b). The gain fits (lines) give values of $G = 29$ and 22 cm^{-1} for TE and TM modes, respectively. (Adapted from Valenta, J. et al., *Appl. Phys. Lett.*, 81, 1396, 2002.)



FIGURE 37.19 Time-resolved VSL measurement of optical amplification at position of the TM mode (760 nm) under pumping by 6 ns pulses, 355 nm. The fit with Equation 37.1 gives the net gain coefficient of (−6 ± 6) and (12 ± 2) cm^{-1} for pumping fluence of 5 and 86 mJ/cm^2, respectively. The threshold for positive gain is about 50 mJ/cm^2. Sample was implanted to a dose of 4 × 10^{17} cm^{-2}. (After Luterova, K. et al., *Phys. Status Solidi (c)*, 2, 3429, 2005.)

substrate modes in asymmetric thin-film organic waveguides (Nakanotani et al. 2007, Yokoyama et al. 2008).

At present, checking the reliability of the VSL method in the case of active asymmetric thin waveguides represents an issue requiring further investigation.

37.6.2 Other Applications

Although the benefit of the waveguide spectral filtering for nanocrystalline thin-film laser design is still controversial, the substrate modes may be attractive for other nanophotonic applications. Firstly, they provide a way how to *generate easily the spectrally narrow, polarization resolved and directional emission* in the wavelength range 650–950 nm without the necessity of building optical (micro)cavities. Moreover, this emission can be spectrally tuned simply by engineering the silicon excess content, as shown in Figures 37.10 and 37.16. Potential feasibility of these properties for *demultiplexing optical signal in photonic circuits* is evident, but improvement in quality of the rib waveguides is anticipated.

Secondly, spectral sensitivity of the radiative substrate modes to surrounding (organic) compounds can be utilized in *photonic sensing* (Figure 37.20): Magnitude of the refractive index



FIGURE 37.20 The influence of a drop of liquid on the PL spectra: (a) the drop is on the excited spot and (b) the drop is out of excited spot (between the spot and the sample edge). (c) Comparison of experimental (points) and calculated (line) positions of PL maxima for different refractive indices of liquid drops. Sample is implanted to a dose of 5 × 10^{17} cm^{-2}. (Adapted from Pelant, I. et al., *Appl. Phys. B*, 83, 87, 2006; Luterová, K. et al., *J. Appl. Phys.*, 100, 074307, 2006.)

n_1 of the compound (playing role of the cladding layer) affects markedly the spectral position of the TE–TM doublet. When n_1 exceeds the magnitude of the core refractive index ($n_2 \approx 1.45$), the condition of total reflection $|r_{21}| = 1$ is canceled and the TE–TM doublet completely disappears. A more systematic research in this direction is, however, missing.

Finally, the *active waveguides* give the chance to circumvent the *coupling problem* connected with discrete photonic elements, i.e., the problem of how to inject efficiently light from an external source in a waveguide (Orobtchouk 2006). The *active waveguides eliminate the need of any optical couplers* and enable it to design integrated photonic circuits. Theoretical analysis of active Si-nc devices integrating optical emission and waveguiding, compatible with silicon VLSI processing technology, have been submitted quite recently (Milgram et al. 2007, Redding et al. 2008).

37.7 Conclusions

Active waveguides formed by densely packed silicon nanocrystals represent a promising type of nanophotonic waveguides. In contrast to other types of nanowaveguides (based on photonic waveguides, plasmonic structures, etc.), it can be prepared by various technological approaches available and well mastered in many research and industrial laboratories. Its potential applications range from optical amplifiers and filters to optical sensors. The descriptions of characterization techniques and theory of waveguide modes in this chapter are applicable to many other waveguide structures.

Acknowledgments

This work was supported by the Czech Ministry of Education, Youth and Sports through the research center LC510 and research plans MSM0021620835 and 60840770022, the project 202/07/0818 of the Grant Agency of the Czech Republic, and the projects IAA101120804 and KAN401220801 of the Grant Agency of the Academy of Sciences. Research carried out in the Institute of Physics was supported by the Institutional Research Plan AV0Z10100521. The authors thank Prof. R.G. Elliman (Australian National University, Canberra) and Ing. V. Jurka for the fabrication of waveguides.

References

Cheylan, S. and Elliman, R. G. 2001. Effect of hydrogen on the photoluminescence of Si nanocrystals embedded in a SiO_2 matrix. *Applied Physics Letters* 78: 1225–1227.

Cheylan, S., Langford, N., and Elliman, R. G. 2000. The effect of ion-irradiation and annealing on the luminescence of Si nanocrystals in SiO_2. *Nuclear Instruments and Methods in Physical Research: Section B* 166–167: 851–856.

Dal Negro, L., Bettotti, P., Cazzanelli, M., Pacifici, D., and Pavesi, L. 2004. Applicability conditions and experimental analysis of the variable stripe length method for gain measurements. *Optics Communications* 229: 337–348.

Iacona, F., Franzò, G., and Spinella, C. 2000. Correlation between luminescence and structural properties of Si nanocrystals. *Journal of Applied Physics* 87: 1295–1303.

Imakita, K., Fujii, M., Yamaguchi, Y., and Hayashi, S. 2005. Interaction between Er ions and shallow impurities in Si nanocrystals. *Physical Review B* 71: 115440-1–115440-7.

Ivanda, M., Desnica, U. V., White, C. W., and Kiefer, W. 2003. Experimental observation of optical amplification in silicon nanocrystals. In L. Pavesi, S. Gaponenko, and L. Dal Negro (Eds.), *Towards the First Silicon Laser*, NATO Science Series, II: Mathematics, Physics and Chemistry, Vol. 93, pp. 191–96. Dordrecht, the Netherlands: Kluwer Academic Publishers.

Janda, P., Valenta, J., Ostatnický, T., Skopalová, E., Pelant, I., Elliman, R. G., and Tomasiunas, R. 2006. Nanocrystalline silicon waveguides for nanophotonics. *Journal of Luminescence* 121: 267–273.

Khriachtchev, L., Räsänen, M., Novikov, S., and Sinkkonen, J. 2001. Optical gain in Si/SiO_2 lattice: Experimental evidence with nanosecond pulses. *Applied Physics Letters* 79: 1249–1251.

Khriachtchev, L., Novikov, S., and Lahtinen, J. 2002. Thermal annealing of Si/SiO_2 materials: Modification of structural and photoluminescence emission properties. *Journal of Applied Physics* 92: 5856–5862.

Khriachtchev, L., Räsänen, M., Novikov, S., and Lahtinen, J. 2004. Tunable wavelength-selective waveguiding of photoluminescence in Si-rich silica wedges. *Journal of Applied Physics* 95: 7592–7601.

Khriachtchev, L., Navarro-Urios, D., Pavesi, L., Oton, C. J., Capuj, N. E., and Novikov, S. 2007. Spectroscopy of silica layers containing Si nanocrystals: Experimental evidence of optical birefringence. *Journal of Applied Physics* 101: 044310-1–044310-6.

Luterová, K., Dohnalová, K., Švrček, V., Pelant, I., Likforman, J.-P., Crégut, O., Gilliot, P., and Hönerlage, B. 2004. Optical gain in porous silicon grains embedded in sol-gel derived SiO_2 matrix under femtosecond excitation. *Applied Physics Letter* 84: 3280–3282.

Luterová, K., Navarro, D., Cazzanelli, M., Ostatnicky, T., Valenta, J., Cheylan, S., Pelant, I., and Pavesi, L. 2005. Stimulated emission in the active planar optical waveguide made of silicon nanocrystals. *Physica Status Solidi (c)* 2: 3429–3434.

Luterová, K., Skopalová, E., Pelant, I., Rejman, M., Ostatnický, T., and Valenta, J. 2006. Active planar optical waveguides with silicon nanocrystals: Leaky modes under different ambient conditions. *Journal of Applied Physics* 100: 074307.

Milgram, J. N., Wojcik, P., Mascher, P., and Knights, A. P. 2007. Optically pumped Si nanocrystal emitter integrated with low loss silicon nitride waveguides. *Optics Express* 15: 14679–14788.

Nakanotani, H., Adachi, C., Watanabe, S., and Katoh, R. 2007. Spectrally narrow emission from organic films under continuous-wave excitation. *Applied Physics Letters* 90: 231109-1–231109-3.

Orobtchouk, R. 2006. On chip optical waveguide interconnect: The problem of the in/out coupling. In L. Pavesi and G. Guillot (Eds.), *Optical Interconnects. The Silicon Approach*, pp. 263–290. Berlin, Germany: Springer-Verlag.

Ostatnický, T., Rejman, M., Valenta, J., Herynková, K., and Pelant, I. 2008. Guiding and amplification of light due to silicon nanocrystals embedded in waveguides. In L. Khriachtchev (Ed.), *Silicon Nanophotonics*, pp. 267–296. Singapore: World Scientific.

Park, J. H. and Steckl, A. J. 2004. Laser action in Eu-doped GaN thin-film cavity at room temperature. *Applied Physics Letters* 85: 4588–4590.

Pavesi, L. and Guillot, G. (Eds.). 2006. *Optical Interconnects. The Silicon Approach*. Berlin, Germany: Springer-Verlag.

Pavesi, L. and Lockwood, D. J. (Eds.). 2004. *Silicon Photonics*. Berlin, Germany: Springer-Verlag.

Pelant, I., Ostatnický, T., Valenta, J., Luterova, K., Skopalova, E., Mates, T., and Elliman, R. G. 2006. Waveguides cores containing silicon nanocrystals as active spectral filters for silicon-based photonics. *Applied Physics B* 83: 87–91.

Pellegrino, P., Garrido, B., Garcia, C., Arbiol, J., Morante, J. R., Melchiorri, M., Daldosso, N., Pavesi, L., Schedi, E., and Sarrabayrouse, G. 2005. Low-loss rib waveguides containing Si nanocrystals embedded in SiO_2. *Journal of Applied Physics* 97: 074312-1–074312-8.

Redding, B., Shi, S., Creazzo, T., and Prather, D. W. 2008. Electromagnetic modeling of active silicon nanocrystal waveguides. *Optics Express* 16: 8792–8799.

Riboli, F., Navarro-Urios, D., Chiasera A., Daldosso, N., Pavesi, L., Oton, C. J., Heitmann, J., Yi, L. X., Scholz, R., and Zacharias, M. 2004. Birefringence in optical waveguides made by silicon nanocrystal superlattices. *Applied Physics Letter* 85: 1268–1270.

Shaklee, K. L. and Leheny, R. F. 1971. Direct determination of optical gain in semiconductor crystals. *Applied Physics Letters* 18: 475–477.

Skopalová, E. 2007. Mode structure in the light emission from planar waveguides with silicon nanocrystals. Diploma thesis. Prague, Czech Republic: Charles University.

Snyder, A. W. and Love, J. D. 1983. *Optical Waveguide Theory*. London, U.K.: Chapman & Hall.

Valenta, J., Pelant, I., and Linnros, J. 2002. Waveguiding effects in the measurement of optical gain in a layer of Si nanocrystals. *Applied Physics Letters* 81: 1396–1398.

Valenta, J., Pelant, I., Luterová, K., Tomasiunas, R., Cheylan, S., Elliman, R., Linnros, J., and Honerlage, B. 2003a. Active planar optical waveguide made from luminescent silicon nanocrystals. *Applied Physics Letters* 82: 955–957.

Valenta, J., Luterová, K., Tomašiunas, R., Dohnalová, K., Hőnerlage, B., and Pelant, I. 2003b. Optical gain measurements with variable stripe length technique. In L. Pavesi, S. Gaponenko, and L. Dal Negro (Eds.), *Towards the First Silicon Laser*, NATO Science Series, II: Mathematics, Physics and Chemistry, Vol. 93, pp. 223–242. Dordrecht, the Netherlands: Kluwer Academic Publishers.

Valenta, J., Ostatnický, T., Pelant, I., Elliman, R. G., Linnros, J., and Hőnerlage, B. 2004. Microcavity-like leaky mode emission from a planar optical waveguide made of luminescent silicon nanocrystals. *Journal of Applied Physics* 96: 5222–5225.

Yokoyama, D., Moriwake, M., and Adachi, C. 2008. Spectrally narrow emissions from edges of optically and electrically pumped anisotropic organic films. *Journal of Applied Physics* 103: 123104-1–123104-13.

38

Biomolecular Neuronet Devices

Grigory E. Adamov
Central Scientific Research Institute of Technology “Technomash”

Evgeny P. Grebennikov
Central Scientific Research Institute of Technology “Technomash”

38.1 Introduction 38-1
Bacteriorhodopsin Is an Advanced Material for Molecular Nanophotonics
38.2 Some Techniques of Neuro-Molecular and Molecular Information Processing Using Bacteriorhodopsin (Basic Processes, Constructions, Technology) 38-2
Basic Process of Classic Optical Neural Network in Bacteriorhodopsin Medium • Neuronets Based on Multilayered Optical Structures Including Polymeric Bacteriorhodopsin-Containing Layers
38.3 Nanostructuring of Bacteriorhodopsin-Containing Molecular Media....................38-10
Procedure of Complex Estimation of Functional Characteristics of Bacteriorhodopsin-Containing Materials • Functional Characteristics of Nanostructured Bacteriorhodopsin Films • Metal Nanoparticles and Bacteriorhodopsin-Based Hybrid Nanostructures
38.4 Summary....................38-17
References....................38-17

38.1 Introduction

Due to the constant development of nanotechnologies and functional nanomaterials used in information systems, researchers need to look for new ideas and radically new constructive solutions to ensure efficient device operation, record-breaking high speed, and integration of elements. On the other hand, functional elements being formed in nanometer range require landmark approaches. It refers especially to the formation of information-logical devices at the molecular level. That is, the formation of nanodevices by direct impact on separate molecules or atoms is not efficient in the long run. The total time taken for operations with separate molecules leads to tremendous amount of time taken to form the device and huge costs.

Another techno-systematic problem is the necessity to use “macro–nano” and “nano–macro” interfaces to put in the original information and deduce final results. The advantages of the small-size molecular elements cannot help to ensure access to them. Probably the only effective way to arrange the bonding with molecular system is to use optical interaction.

Under the circumstances, it seems quite reasonable to refer to the most competent specialist, whose experience in creating molecular systems cannot raise any doubts, that is, to the nature itself and try to apply bionic principles to engineering and design. The solution seems to be connected with hierarchic structural and functional self-organization of molecular systems that use assemblies of molecules as a basis for molecular information-logical appliances.

Among all the information systems, bionic approach seems to be the most effective, harmonic, and holistic one; it is important to point out molecular neural network appliances. Both adaptive self-organization principles of data processing and self-organization principles of functional nanostructures can be applied to those systems.

Below you will find a detailed description of techno-systematic approaches aimed at implementation of biomolecular neural network appliances. Mentioned below, biological material—protein “bacteriorhodopsin”—has unique technological potential and its optical properties allow the use of optical input–output devices and create molecular appliances based on self-organization principles.

38.1.1 Bacteriorhodopsin Is an Advanced Material for Molecular Nanophotonics

Bacteriorhodopsin (BR)—light-sensitive protein—is similar to the optic rhodopsin of the human eye. BR is obtained from halobacteria containing BR in cellular membranes (so-called purple membranes). During the separation from the bacterial cells, purple membranes save the entire structure (Vsevolodov, 1988; Oesterhelt et al., 1991). The typical size of purple membranes is 500–1000 nm. It is the unique biocrystalline structure capable of saving its permanent properties for a number of years, which consists of dry and polymer films with the thickness from 5 nm (monolayer) up to a few tens of micrometers.

The fundamental BR property is the photochemical cycle availability: after the light quantum absorption, BR molecule passes through the sequence of states and spontaneously returns to the primary form (Figure 38.1). At that point, in compliance with the cycling of BR molecule state, the light-induced cycling



FIGURE 38.1 BR photocycle.

of optical characteristics (refraction and absorption indices) occurs (Haronian and Lewis, 1991; Zeisel and Hampp, 1992). Each of the interstitial states is identified as the intermediate according to its absorption spectrum. The existence of branched photocycles is typical for some BR types (Birge et al., 1999).

The main BR function in purple membranes is light-dependent proton transfer (H^+) over the purple membrane that results in electrochemical hydrogen potential formation on halobacteria membrane. The potential energy is utilized by cell. Ejection of H^+ occurs outside the cell membrane, and the H^+ is captured inside the cell (from cytoplasm). Supposedly, it happens during the formation and the disappearance of intermediate M412 (Siebert et al., 1982; Haronian and Lewis, 1991).

BR spectral sensitivity lies in the optical band (Figure 38.2). Absorption maximum in primary state of BR570 corresponds to wave length 570 nm. M412 in the main intermediate state reaches its absorption maximum at wave length 412 nm (Birge et al., 1999). The absorption of optical emission by BR-containing medium is characterized by certain peculiarities. That happens due to the change of adsorption sites concentration (molecules in form BR570), which is the result of light quantum absorption at wave length 570 nm by these sites and transition to form M412 with a low absorption at wave length 570 nm. As a result, absorption in the yellow range reduces; medium becomes more transparent—bleached. The intensity of BR-containing medium bleach effect depends particularly on the time of intermediate M412 molecules relaxation to form BR570. Relaxation time is characterized by half-value period of intermediate M412 molecules. The light effect at wave length 412 nm results in fast coercive transition of molecules to the primary state. The values of photocycle time parameters lie in the range from microseconds up to tens of seconds.



FIGURE 38.2 Absorption spectra of BR and of the main photocycle intermediates.

Thus, BR behaves as a photochromic medium with a quick time of information storage. Optical and dynamic BR characteristics change in wide range by production conditions and matrix composition (medium).

38.2 Some Techniques of Neuro-Molecular and Molecular Information Processing Using Bacteriorhodopsin (Basic Processes, Constructions, Technology)

38.2.1 Basic Process of Classic Optical Neural Network in Bacteriorhodopsin Medium

BR properties listed above allow us to illustrate one of the available basic processes of data transformation in BR-containing media. It is based on reversible light-sensitive changes of absorption index and appears in optical effects considered below.

38.2.1.1 Nonlinear Absorption of Optical Radiation: Medium Bleaching

The absorption of optical radiation in substance is described by some known classic equations. Generalized Bouguer–Beer law associates intensities of the incident light and the light transmitted through the substance layer with the thickness of the layer and molecular concentration of absorption agent:

$$I = I_0 \cdot e^{-D} = I_0 \cdot e^{-\alpha d} = I_0 \cdot e^{-\varepsilon c d}, \qquad (38.1)$$

where

I is the transmitted light intensity
I_0 is the incident light intensity
D is the optical density of the substance
α is the absorption index of the substance
d is the thickness of the substance layer
c is the molar concentration of absorbing substance molecules
ε is the extinction coefficient, characteristic feature of absorbing substance molecule

The values of ε, α, and D depend on the wave length of incident light. When the values of coefficients in Equation 38.1 are invariable, the transmitted light intensity is in direct proportion to the incident light intensity.

Nonlinear absorption of optical radiation by BR-containing media is connected to the change of absorption centers concentration (molecules in form BR570) as a result of light quanta absorption by these centers at wave length 570 nm and transformation to M412 with low absorption at wave length 570 nm. Finally, as was mentioned above, absorption in the yellow range ($\lambda = 570$ nm) decreases, medium becomes more transparent—bleached.

38.2.1.2 Indirect Interaction of Optical Radiation Fluxes in Bacteriorhodopsin-Containing Media

Mediated interaction of optical radiation fluxes appears during the sequential or combined transmission through the same part of BR-containing medium and is at its clearest for monochromatic radiation with wave length 412 and 570 nm.

As a result of interaction between BR and the radiation with wavelength 570 nm during the transmission through the medium, the energy of the light flux is absorbed, and in BR-containing medium, the photo-induced allocation of the absorption index forms. The light-induced allocation of the absorption index variation corresponds to energy distribution along the surface of the transmitted light wave front (Figure 38.3A).

Non-modulated along the front surface, the light pulse with the wave length of 570 or 412 nm (as actuating or inhibiting signal) absorbs spatially and nonuniformly in compliance with the changed value of the absorption index (Figure 38.3B and C).

Thus, the energy distribution along the preceding pulse front surface, indirectly, over the BR-containing medium, modulates the energy distribution along the following pulse front surface.

As a result, BR-containing medium is capable of accumulating (summing up) effects signed "+" and "–," correspondingly, at wave lengths 570 and 412 nm. Predicating upon the indirect interaction of optical radiation in BR-containing media, the method of formal neuron creation in such media is available to offer. At that point, all the main functions can be realized by optical technique.

38.2.1.3 One of the Possible Methods of Formal Neuron Main Functions Realization in Bacteriorhodopsin Medium

Realization of the main operations of neuronet algorithms—weighing of input signal vector according to the matrix of weighing coefficients of synaptic bonds; composition of weighed values of input signals; realization of activation (threshold) function by optical method without optoelectronic buffering—permits to simplify the construction and the technological realization of multilayered optical neuronet, to increase the integration of neuro-like elements in device, and to solve the problem of areal density limitation inherent in microelectronic elements and electric connections.

38.2.1.4 Formation of the Neuro-Like Element

The neuro-like element is formed under the exposure of optical emission with the spectrum, corresponding to the absorption spectrum of BR molecules' initial state and BR-containing material medium. This element is a part of the BR-containing medium with photo-induced absorption index. The threshold properties of such neurons are defined by the concentration ratio of molecules in primary and photo-induced forms, and the interaction of neuro-like elements is provided by optical emission.

The example of the similar neuronet realization, based on information conversion of basic process in BR-containing media (Figure 38.4), is considered below.

Construction for optical neuronet formation includes the following:

1. The source of the plane light front (transparent for normal incident light flux) providing the signal formation and transfer to neurons.
2. Photo-detecting layer based on BR-containing material for imaging of the input optical information by photo-induced variation (according to light energy distribution along the surface of input light front) of absorption/transmission in BR-containing medium.



FIGURE 38.3 The indirect interaction of optical radiation fluxes in BR-containing media: (A) green light pulse (modulated along the front surface) acts on a layer of BR-containing medium (nontransparent for green light); (B) modulated allocation of molecules in form M412 (transparent for green light) and BR570 (nontransparent for green light), (C) the action of unmodulated blue light pulse, (D) modulated blue pulse as a result of transmission via the modulated medium (BR-containing medium layer recovered the primary state).


1
2
4
5
6
7
Light
3
Realization of weighting function
Realization of the activation function
Realization of the weighted signals composition function

FIGURE 38.4 Neuronet organization based on the basic process: 1, 6—plane waveguides, including gitters for emission input/output; 2, 4, 7—BR-containing layers (photo-detecting layer, layer of weighting coefficients and neuron layer); 3, 5—cylindrical lenses.

3. Light flux expanding lens.
4. Layer of synaptic bond synthesis (matrix of weighing coefficients) made of BR-containing material.
5. The lens, focusing the light flux on layer 7 and forming the combination of input optical signals based on neuro-like elements in that manner.
6. The source of flat light front (transparent for normal incident light flux) for parallel comparison with thresholds, formation, and transfer to other layers of output neuron signals in layer 7 as light front, modulated by intensity along front surface according to the values of absorption/transmission area of BR-containing medium (corresponding to neuro-like elements).
7. The layer of neuro-like optical elements (being obtained on the basis of BR-containing material) composes input optical signals, traversing matrix 4 and realizing the activation function during the light front traverse from the source 6, and forms thereby output signals.

The input optical information in the form of light flux (input vector) effects the photo-detecting layer 2 that results in the absorption of light flux energy in BR-containing medium of photo-detecting layer and the distribution of the photo-induced absorption index forms.

Distribution of the photo-induced BR-containing medium absorption index along the surface and in depth corresponds to the power distribution along the surface of the effective light front.

Plain light front from the source 1, modulated by intensity according to the contour of absorption index of photo-detecting layer 2 by lens 3, allocates on the surface of weighing coefficients layer 4.

38.2.1.5 Realization of Weighing Function

The input vector weighing function comes around during the transfer process of input light signal—the components of input vector—over the matrix of weighing coefficients 4. By the component of input vector, we mean the quantity of the light energy (the intensity multiplied by exposure—exposition) affecting the matrix section.

Weighing coefficient (by which the input vector component is multiplied) is a transmission coefficient of the corresponding section of BR-containing matrix:

$$I_{w\,ij} \cdot t = \omega_{ij} \cdot I_{in\,i} \cdot t, \tag{38.2}$$

where

$I_{w\,ij}$ is the light intensity transmitted over the ij matrix section or weighed component of the input vector

$I_{in\,i}$ is the light intensity of the light front section or a component of the input vector

t is the exposition time of the corresponding component of the input vector

ω_{ij} is the weighing coefficient or transmission of the corresponding ij-section of the BR-containing matrix

Transmission of the ij matrix section is defined according to Bouguer–Beer law

$$\omega_{ij} = e^{-\varepsilon d c_{i/f\,ij}}, \tag{38.3}$$

where

ε is the BR absorption factor

d is the thickness of BR-containing layer

$c_{i/f\,ij}$ is the concentration of the BR molecules in the initial state in the ij matrix section

The properties of the input vector weighed components are formed by lens 5 in a light flux that gets to the inputs of the corresponding neuro-like elements of the layer 7.

38.2.1.6 Realization of the Weighed Signals Composition Function

Composition function of the input signals is realized in the BR-containing medium in layer 7 by the converging cylindrical lens 5 as a result of the combined effect at the same area of BR-containing medium of the light energy exposition by the corresponding components of the input vector.

Every component of the input vector contributes to the formation of the molecules ensemble in photo-induced state in proportion to the intensity and exposure time:

$$\Delta c_{j\,p/i} = k \cdot \sum I_{w\,ij} \cdot t, \tag{38.4}$$

where

$\Delta c_{j\,p/i}$ is the concentration of BR molecules in photo-induced spectral state

k is the coefficient of proportionality depending on the concentration of BR molecules in the initial state, cross-section interaction, photo response of BR-molecules transition from the initial to the photo-induced form, and the effecting light wave length

$I_{w\,ij}$ is the intensity of the input vector weighed ij-component

t is the exposure time of the input vector i-component

Thus, $\Delta c_{jp/i}$ contains information about the value of the weighed input interactions sum on the j-neuron.

38.2.1.7 Realization of the Activation Function

Magnitude $\sum_i I_{w\,ij} \cdot t$ (the total dose of light energy effecting on the j-area of BR-containing medium) assigns the point at the graph (dependence of the transmission value on the sum of weighed input effects) and defines the transmission of the light signal over the j-neuro-like element.

The changed transmission $\omega_{n/e}$ value of the BR-containing medium j-section according to the j-neuro-like element assigns the value of the activation function and the output signal of the neuro-like element in layer 7, according to Figure 38.5. This magnitude depends on the number of molecules possessing the changed spectral properties of the medium section corresponding to the neuro-like element of the layer 7 according to

$$\omega_{n/e\,j} = e^{-\varepsilon d(c_{i/f} - \Delta c_{j\,p/i})}. \tag{38.5}$$



FIGURE 38.5 Transmission (P_{out}/P_{in}) of BR-containing layer depending on the effective emission energy (P_{in}).

The graphic chart on the dependence of the BR-containing layer relative transmission on the emission energy consists of the area with the initial transmission value (unequal to zero), the area of almost linear transmission change, and the saturation area (Figure 38.5). In general, the curve corresponds to the activation function proposed for the neuronet realization by Grossberg (Wasserman, 1989). The similar compressive function automatically provides the output signal range from 0 to 1 and corresponds to the necessary requirements for realization of reconversion algorithm during the neuronet learning, for example, according to scheme (Wasserman, 1989).

The output signal formation of neuro-like element (threshold comparison and realization of the activation function) is carried out by the light front of the specified intensity and duration induced by the source-former 6.

The output signal of the neuro-like j-element is formed as an energy portion of the active light signal being transferred over to the corresponding section of BR-containing medium in the layer of neuro-like elements 7 (according to the transmission of the section considered) in conformity with the formula

$$I_{\text{out}\,n/e} \cdot t_{\text{active}} = W_{n/e} \cdot I_{\text{active}} \cdot t_{\text{active}}. \tag{38.6}$$

The minimum value of the output signal is fixed by the transmission of non-firing neuron (the input signals sum value is close to zero) and corresponds to the initial transmission of photochromic medium, and the maximum value is close to the value of active front energy and corresponds to the saturation area of the curve (Figure 38.5) and to the maximum excited state (transmission) of firing neuron. Output signals of neuro-like elements form the continued light front being modulated according to the activation function at every point of BR-containing layer 7. System learning (formation of matrix weighing coefficients) corresponds to the formation of adequate values of transmission coefficients of matrix sections based on BR-containing medium that can be achieved by the inverse transformation method.

The optical version of the inverse transformation method can be simply and effectively realized (failing optoelectronic transformations) by combined presentation of learning pair: the input image in its usual direction and the ordered output as the light front in the counter direction. Due to the reversibility of the light passing, both of light fronts will affect the matrix made of BR-containing material and will change the matrix transmission corresponding to the intensity distribution.

38.2.2 Neuronets Based on Multilayered Optical Structures Including Polymeric Bacteriorhodopsin-Containing Layers

The considered approach of neuro-computer element base formation takes into account the cyclicity of processes in living systems appearing, for example, in spontaneous activity of pacemaking (assigning the rhythm of functioning) neurons. As was conclusively shown in Prigogine (1980), the cyclicity proceeds as a result of the processes' self-organization in open nonlinear nonequilibrium systems and the origination of stable dissipative structures due to which the coordination of trophic processes (providing cell nutrition) is possible in living systems.

The similarity of cyclic processes in the living cell membranes (including neurons) and the processes under optical emission exposure in isolated purple membranes is obvious, particularly, taking into consideration that in that case one of the halobacteria trophic cycles is reproduced.

If the neuron is represented as a structure population (purple membranes) allocated in media and the interactions between the neurons are carried out by light fluxes, the "neurolike medium" in question can be considered as the alternative to the net of neuro-like elements (Grebennikov, 1997).

In the interpretation being stated, the problem of neuronet formation is in simulation of nonequilibrium nonlinear systems in BR-containing media with allocated parameters by optical emission of two different wave lengths corresponding to the absorption maxima of two "long-living" intermediates. It can be solved in the following consequence:

1. Using the spectral sensitivity of BR in optical range to initiate the cyclic light-dependent processes by the light flux and to control the processes by the application of emission with various wave lengths.
2. Stationary and dynamic structuring of BR-containing films by modulated light fluxes to create the conditions of formation and development of neuro-like relations in neuro-like medium and to correlate the multitude of cyclic processes.

Data input and processing in that case is "deformation" of the correlated cyclic processes in BR-containing medium, and the commands of system behavior control are the transient processes originating in the organized neuro-like medium.

On the other hand, analyzing the development tendencies of neuronet technology, the best perspective can be emphasized, and their combination in the same device can provide essential expansion of neuronet data processing:

1. *Optical mechanism of data transmission and processing*, which will allow to construct three-dimensional nets that function simultaneously at high speed. The problem of wide application is in large dimensions, peculiar to optical systems, and the inevitable efficiency losses due to multiple intermediate optoelectronic conversions and the finite size of the optoelectronic elements.

The application of continuous photochromic media with high resolution close to molecular level of data representation and processing can become a solution to the problem. BR is the most available and well-investigated (at present) photochromic material with sufficiently high cyclicity ($>10^6$) and is suitable for the considered purposes. Using BR enables to carry out data processing in optical mode without intermediate optoelectronic conversions and to increase the areal density of neuro-like elements value comparable to the native neuron systems.

2. *Neuro-like structure construction on the principles of self-organization of the processes in the open nonlinear allocated dissipative systems like biological objects*. Although in model version, systems require substance transfer proceeding for nonequilibrium conditions maintenance.

BR application can solve the problem of substance transfer that complicates the construction and limits the continuous working life of neuro-like media processing. Light-dependent properties of that material allow the open nonlinear allocated dissipative systems to simulate effectively. Optical exposure in the range of 520–650 nm is like the input flux and dissipative properties, and in that case can be provided by the component of trophic cycle that remains invariable in composition of artificial medium (for example, in polymeric matrix) and also by emission exposure in blue light range ($\lambda = 400–420$ nm).

3. *Element base adaptability* to losses of some elements during the preparation and exploitation compensated by self-organizing and self-modification of neuro-like structures. Application of continuous media based on BR in conjunction with optical methods permits to form neuro-like elements, and the bonds between it suit requirements according to the light energy allocation.

Classic methods of the light fluxes formation by lens systems result in the loss of advantages expected from significant density of neuro-like elements and dimension restrictions of elements and systems, peculiar to optical computers. Moreover, when the volume of BR-containing medium is greater, the probable process integration is higher. However, the emission access to all the molecule groups is more unfavorable as the medium absorption increases.

In the field of optoelectronic technology, efforts are made to deflate the construction dimension of optical neuro-computers by the application of multilayered structures. Multilayered structures forming neuronets and containing the layer of spatial light modulators as the liquid crystal matrix, the layer of photoconducting material (Engel, 1990) or material with the photovoltaic effect (Akiyama et al., 1995), and the layer of electric transducer-amplifiers (forming and transducing the commands to liquid crystal panels) are proposed.

Essential disadvantage of the proposed constructions is the facility of intermediate conversion of light exposure to electric current or voltage used for the following changes of optical transmission modulator. Furthermore, neuronet function realization requires the application for these purposes of optoelectronic and microelectronic elements. Consequently, the application of metallic conductors in inter-cell links for realization of neuro-systems with a great number of neurons results in delays in communication lines and neuronet processing deceleration due to the capacity influence of inter-cell communication lines. The existing areal density restrictions of optoelectronic elements and electrical bonds inevitably limit the spatial resolution of constructions.

38.2.2.1 Multilayered Constructions, Including Bacteriorhodopsin-Containing Films

We proposed multilayered structures including layers based on the BR for the realization of neuronet medium in nonequilibrium nonlinear dynamically allocated dissipative systems.

Supposedly, the multilayered structures would allow the data processing to continue at the level of BR molecules groups by forming neuro-like elements using optical methods in BR-containing media.

The basic processes in BR medium are defined by light-dependent changes in absorption index allocation profile along the surface of BR-containing polymeric films. In multilayered structures, many light fluxes circulate without interaction. This property is usually proved as an advantage of optical methods enabling data processing and transmission in the three-dimensional space. At the same time, the information arrays in the form modulate indirectly by intensity light fronts over the reciprocal fluctuation of absorption index local value of BR-containing media sections, and the local intensity value of the light front sections realize concurrent information interactions in the three-dimensional space of the multilayered structure.

We would like to consider a possibility of neuro-like element net organization in BR medium by optical method using multilayered structures (Figure 38.6) including BR-based layers, wave guide layers, and reflecting layers. To allocate light fluxes, the system of waveguides, transparent in the optical range, is formed in BR-containing medium. It is possible to input the controlled emission in the form of light front in BR-containing medium, activating at that point the groups of neuro-like elements, by producing the sections with the disturbed conditions of total internal reflection in waveguides.

It is expected that the multilayered structure will provide not only functioning and interaction of neurons and their ensembles but also the generation of new neurons and links (emission output from one layer and penetrating to the other layers) between single neurons and neuronets, and will permit, according to the information (image) at system output, to connect and to correlate the cyclical processes originating in BR medium. At that point, the process of self-organization of data processing system will continue.



FIGURE 38.6 Fragment of multilayer structure: 1—substrate (glass K-8); 2, 10—layers, containing BR; 3, 5—boundary layers of flat waveguide; 4—guide layer of flat waveguide; 6—emission input area; 7—input emission; 8—output emission; 9—output emission gitter, 11—input emission gitter; *L* is the length of the output emission gitter.

The adaptability principles realization of data processing elements and system self-organization will permit to essentially reduce the requirements of the elements and facility as a whole to provide reliable functioning in case of the single-element failure.

Reduction of technological requirements is achieved by that neuro-like elements and links that are formed in continuous (uniform, i.e., not divided into constructive matrix elements) transparent (without optical dispersion) layer of photochromic material according to the light energy allocation.

38.2.2.2 Expected Parameters of the Element Base

According to the traditional criteria, it is acceptable to evaluate the number of the neuro-like elements in medium containing BR at area 10 mm^2 in quantity not less than 10^6. At the area in question, not less than 10^{11} bonds per second are realized (circuit time 0.1 ms, coefficient of bond formation 10).

38.2.2.3 The Basic Elements of the Multilayered Structures

The multilayered structures (Figure 38.6) for the realization of the basic neuronet data processing include: the system of flat waveguides, the elements of optical emission input as gitter, and the devices of the surface light front formation (Figure 38.7).

BR-containing polymeric films are meant for neuro-like elements formation by the change of the absorption/transmission surface geometry by modulated light flux effect.

The elements of optical emission input in flat waveguides and the elements of output are made as diffraction lattices (gitters) (Zlenko et al., 1975; Unger, 1980). The angles of radiation input and output depend on different layer indexes and glitter spacing; therefore, those angles can be different for various multilayered waveguides.



FIGURE 38.7 Device for surface light front formation: Θ_1, Θ_2—angles of emission input; Λ_1, Λ_2—diffraction lattice spacing; n_0, n_1, n_2—refraction indices.

The device for surface light front formation (Figure 38.7) generates directed light fluxes for effective allocation of the light energy in BR-containing polymeric films for neuro-like elements concurrent formation, their concurrent interaction, and output of the data processing results in neuro-like element medium as optical signals.

38.2.2.4 Requirements of BR-Containing Polymeric Films

The following are the requirements of optical and geometrical properties of BR-containing polymeric films.

For photochromic effects (induced changes of refraction and absorption indexes) to significantly appear during functioning process, high optic density and consequently substantial BR concentration in polymeric films are needed. Optical density of such films should be 0.8–1.3. In those conditions, basic characteristics of BR-containing media are utilized under optimum light flux density so that the media could be used for technical purposes. Exposure to light of the fluxes with radiation density equal to 10–100 mW/cm^2 induces the films to experience changes in their absorption and transmission characteristics as much as 10%–50% from the original indexes in as long as 0.1–10 s.

Functioning of films under induced changes in absorption level requires quite homogenous distribution of BR concentration, as optical heterogeneity infringes the conversion of optical information.

Besides, we must ensure repeatability of the main structural parameters: film thickness, surface finish, homogenous BR distribution throughout film surface (1–10 cm^2), etc.

Requirements to physical and chemical properties of polymeric matrix. Selection of matrix material.

To minimize the influence of diffraction divergence on information conversion processes, the thickness of BR-containing films must be 6–14 μm. To reach the specified optical density with that thickness, the volume of BR content in polymeric films should be 40%–50%. Far from all, the polymers transparent in optical range can meet the requirements above. Moreover, only water-soluble polymers can be used to form BR-containing polymeric films.

The comparative studies held to form polyvinyl alcohol- and gelatine-based BR-containing polymeric films have proved that gelatin-based polymeric matrixes have obvious advantages.

Gelatin-based films could apparently have the highest possible BR concentration (up to 50 vol. %) without aggregation of PM fragments due to thermodynamic peculiarities of gelatin polymerization process. Gelatin properties allow us to avoid destruction of BR protein structure while making polymeric mixture and further polymerization.

PM fragments embedded into a gelatin matrix are long-lasting and resistant to many technological factors. Polymerized gelatin creates optimum conditions for BR to function while retaining enough water needed for photochromic cycle. For the same reason, gelatin matrices make it possible to place environment-modifying water-soluble components and to change the photo cycle time frame.

38.2.2.5 Obtaining of Bacteriorhodopsin-Containing Polymeric Films for Multilayered Structures

It is important for processing and conversion of optical information to take into consideration the dispersion of optical emission in BR-containing media conditioned by purple membranes size (500–1000 nm)—comparable to the wave length of the optical range emission. Therefore, the primary suspensions of PM and BR-containing films based on them are optically nonhomogeneous, which results in the functional properties loss.

The dispersion demagnification is reached consequently: at the step of preparation of purple membranes suspension—by PM fragments separation; at the steps of polymeric mixture preparation and polymerization—by elimination of the aggregation process of the purple membranes fragments.

38.2.2.5.1 Preparation of Bacteriorhodopsin Suspension

For the preparation of PM suspension, the triple centrifugal purification (3000 rpm, 5 min) was carried out; pH value and BR concentration in suspension were measured. The pH value is significant for the following polymeric solutions and film obtaining, since the investigations showed that at pH less than 4.1 PM aggregated, the optical transparency of the suspension was not achieved. It was determined that the ultrasound exposure results in the decrease of pH value in suspension at 0.2–0.4. The control of pH value was managed by the addition of 0.01 M borax buffer solution $Na_2B_4O_7 \cdot 10H_2O$, pH = 9.18. During the ultrasound treatment, the suspension temperature must not exceed 36°C.

As the result of technological investigations of ultrasound treatment, optically transparent homogeneous BR suspensions were obtained without detergent addition. The side effect can be the partial melting of protein. Optically transparent PM suspensions were obtained with BR concentration up to 15 mg/mL.

Size evaluation (8.7 ± 0.5 μm) of PM fragments in treated suspensions was carried out by the intensity of Rayleigh scattering and showed that the applied technological mode of suspension treatment permits to separate PM into naturally minimum fragments—trimers without BR protein destruction and the principle possibility of BR-containing medium optical resolution at the level of a few thousand lines per millimeter can be considered.

38.2.2.5.2 Preparation of Bacteriorhodopsin-Containing Mixture

During the preparation of polymeric mixture based on BR, the last exhibited the property of aggregation on the polymer molecules that lead to optical heterogeneity of films. As the result of technological experiments combining thermal parameters and operating pH of components, the conditions selected under that aggregation were not observed and transparent optically homogeneous BR-containing polymeric mixtures were obtained. At the step of polymeric mixture preparation, pH control of gelatine solution was carried out because pH value in gelatine solution depends either on the obtaining method or on gelatine concentration. The component stirring in the mixture was also carried out by the ultrasound exposure. All the modifying components were put into the polymeric mixture at the last step under condition: the final pH value of the polymeric mixture had to be >4.1.

38.2.2.6 The Properties of BR-Containing Polymeric Films for Multilayered Structures

According to the elaborated technology, there are transparent and optically homogeneous BR-containing polymeric films (thickness 6–14 μm with optical density 0.8–1.3 D at $\lambda = 570$ nm) on substrates of glass K-8 and fused quartz (area up to $60 \times 48\,\text{mm}^2$) and also on Si plates (76 mm in diameter).

38.2.2.6.1 Evaluation of PM Size Embedded to Film

Since during the film polymerization from the polymeric mixture fragment aggregation is possible, the evaluation of PM fragments size is being embedded into film. The placement of films with the embedded PM fragments in detection system between crossed polarizers resulted in no changes in the initial zero signal of photodetector. It means either no rotation of polarization in the light-pass direction, or no significant dispersion that confirms the PM fragments size to be much less than 0.63 μm.

Optical heterogeneity specified by surface geometry and allocation of BR concentration to the film surface is given below.

The distribution of optical absorption heterogeneity coefficient of BR-containing films is specified by the product of two values: the allocation heterogeneity of BR bulk concentration to the film surface and quality of the film surface as the local dilatation from the average thickness value. In the aggregate it results in the local dilatation of so-called surface concentration and, correspondingly, the optical density.

The optical homogeneity of the film being specified only by the surface quality is provided comparatively easily both for the films being realized by glazing method and for the films being obtained by centrifugation method. It was determined that the typical thickness deviation of BR-containing films being obtained equals less than 50 nm at length 10 mm, that, for example, at film thickness >5 μm equals <1%.

The support of the optical homogeneity being concerned with the allocation of BR bulk concentration along the film surface is hampered by the molecules migration in polymeric solutions during the polymerization process to the area of increased surface tension. Nevertheless, the attained deviation from the average value for allocation of BR bulk concentration does not exceed 3% since the changes of surface concentration and optical density lie in the same range.

38.2.2.6.2 The Structure of Bacteriorhodopsin-Containing Films

It is ascertained that the structure of BR-containing polymeric films surface depends on the obtaining conditions. Depending on pH, the surface is either smooth (Figure 38.8A) or it has punctual (100–300 nm) and rectilinear (400–1000 nm lengthwise, 100–200 nm wide) protuberances (Figure 38.8B and C). The cutting of the surface geometry elements is observed (Figure 38.8B). These investigations confirmed the necessity of pH value maintenance higher than 4.1.

Surface roughness (step height R_z of surface geometry) of the film with particle size of BR phase <10 nm amounts to $R_z \approx 0.1$ μm, with particle size of BR phase ~100–1000 nm $R_z \approx 0.6$–3.8 μm.

The analysis of the films with thickness 20 μm (containing BR-phase cutting) by Roentgen diffractometry led to the missing crystalline phase. Only amorphous gallo is observed on roentgenograms of BR-containing polymeric films, being formed under various conditions in the range of Bragg angles $2\theta = 5°$–8° ($k\alpha$—copper emission).

Clearly defined diffraction maximum appears on roentgenograms of some samples for angles $2\theta = 7.5°$–7.8° (Figure 38.9) corresponding to interplanar spacing $d/n = 1.179$–1.133 nm. For a number of samples, diffraction maximum appears on roentgenograms for angles $2\theta = 18°$–19° ($d/n = 0.467$–0.493 nm). That indicates the ordered placement of protein complexes in polymeric (gelatinous) matrix. Apparently, the axial texturing of lamellar protein complexes exists by the axis normal to the surface of BR plates.

38.2.2.6.3 Refraction Index of BR and BR-Containing Polymeric Films

Information about refraction index in literature (Hampp, 2000) is inconsistent and not exact enough to solve the problem of the multilayered structure construction. Therefore, we made our own measurements.



FIGURE 38.8 The structure of BR-containing polymeric film surface being formed from the polymeric mixture: (A) pH = 4.2–4.5; (B) pH = 3.8–4.0 (the enlarged surface fragment is presented at the insertion); (C) pH = 3.5–3.7.



FIGURE 38.9 Roentgenograms, obtained on the samples: 1—glass K-8; 2—glass K-8 with the deposited gelatinous film; 3—glass K-8 with the deposited BR-containing polymeric film.

The refraction index measurement was carried out using refractometer IRF-454B capable of measuring the refraction index in the range from 1.2 to 1.7 in reflected and transmitted light. BR-containing film was formed on the surface of measuring prism by the method of suspension glazing (concentration 15–20 mg/mL) and the following drying at 22°C temperature, relative 60% humidity. The film thickness reached 20 ± 5 μm.

The value 1.534 ± 0.002 of refraction index was obtained in the white light. This result is well reproducible on every one of the samples being prepared from the three different halobacteria strains and conforms to the results of the following refraction index measurements in polymeric BR-containing films. The value of the refraction index in that case is defined by BR concentration in the film.

The refraction index measurement of gelatin was held in order to predict the parameters of the polymeric BR-containing films under construction depending on BR concentration in the film. The refraction index value of polymeric film based on gelatin without BR (formation by the glazing method on the surface of the refractometer measuring prism) got equal to 1.543 ± 0.001. Refraction index was measured at 22°C temperature and relative 60% humidity.

The refraction index value of BR-containing gelatinous film with thickness 50 ± 10 μm lies in the range of 1.539–1.542 depending on BR concentration in gelatin.

38.3 Nanostructuring of Bacteriorhodopsin-Containing Molecular Media

Functional parameters of BR-based multilayered structures on the base of BR (the increase of photochromic sensitivity, management of photocycle duration) can reach their maximum capacity in use by additional nanostructuring of molecular media. Enhancement of functional properties of multilayered structures is caused by introduction of new functional elements—hybrid nanostructures—making it possible to further realize a new class of optical information systems based on self-organizing oscillatory and auto wave hierarchical processes in BR-containing nanocomposites.

Both nanotechnological and nanotechno-systematic approaches are described below.

While developing BR-based media used to process information with neural network methods, two ways of material structuring are applied. The first way means introduction of modifying organic and nonorganic additives into the system to improve functional characteristics of BR. Modification is done on molecular level that is why such material is a molecular one. The second way means building of hybrid functional structures with every component performing its own function. In this way, structuring goes at nanometric range instead of molecular level. Hybrid nanostructures are systems made of three components—colloidal nanoparticles (metal or semiconductor structures based on transition element [TM] chalcogenide), bridge molecules (spacers) with various linear dimensions, and BR molecules.

38.3.1 Procedure of Complex Estimation of Functional Characteristics of Bacteriorhodopsin-Containing Materials

To characterize and compare functional characteristics of BR-based films made by various methods and difference in thickness, optical absorption, structure, and content (including concentration of BR molecules), it is convenient to apply the designated factor for quantity estimation of photochromic sensitivity. For optimization of experimental investigations, we developed the simulator of photo-dependent processes and designated factor $k_{570}(t)$ of the photo-induced transitions of BR molecules from the primary state BR570:

$$k_{570}(t) = \frac{N_2(t)}{N_0} = \frac{N_0 - N_1(t)}{N_0}, \tag{38.7}$$

where

N_1 is concentration of BR570
N_2 is the concentration of BR412
$N_1 + N_2 = N_0$ is the total concentration of BR molecules

That factor $k_{570}(t)$ named by us as the coefficient of photo-induced transition of BR molecules from basic state BR570 was determined from experimental data of changing optical absorption at wavelength 570 nm under the influence of active inducing radiation. This complex parameter takes into consideration the temporary characteristics of excitation and relaxation processes, quantum efficiency, and cross-section of BR molecules contained in the nanocomposite nanostructured films (media).

While studying the influence of technological formation processes on properties of BR-containing materials, it is very labor-consuming to measure each of the above specified characteristics. Therefore, we use a model to describe photo-dependent processes that pass in BR-based materials under radiation.



FIGURE 38.10 Schematic diagram of a soft- and hardware complex designed to study functional characteristics of BR-based materials.

We have also designed a method to assess the functional characteristics of those media after one measurement. To carry out all necessary measurements, we can use a soft- and hardware complex (Figure 38.10), making it possible to combine light exposure with two wave lengths in the band of main intermediate absorption (at 570 and 412 nm, respectively).

The light radiated by the source of continuous testing radiation with up to 2 mW/cm^2 intensity passes through the sample and falls onto the monochromator where a narrow spectrum line (at 570 nm) is allocated. The signal goes to the photo-electronic multiplier being adjusted to convert the signal and transfer it to the oscillograph. The sample is exposed to light pulsed by the source of exciting radiation with intensity at least 10 times more than the intensity of testing radiation. The signal registered with the oscillograph goes to the computer for mathematic curve processing as per the below physical and mathematic ratios.

Based on the Buger–Lambert–Beer law, taking into consideration photo-induced changing concentrations N_1 and N_2, the expression has been obtained that allows to calculate the value of $k_{570}(t)$ from the experimental data recording testing light $\lambda = 570$ nm transmission changing under illumination of exciting radiation:

$$k_{570}(t) = \frac{\lg\left(I(t)/I_1\right)}{\lg\left(I_1/I_0\right)}, \tag{38.8}$$

where

I_0 is the intensity of the incident test light

I_1 is the intensity of the transmitted test light in the absence of exciting radiation

$I(t)$ is the intensity of the transmitted test light under exciting radiation at the time moment t

Also the proposed method of the complex estimation is based on the kinetic equation evaluating concentration distribution of BR molecules between forms of BR570 (N_1) and M412 (N_2):

$$\frac{dN_1}{dt} = -\sigma_1 \cdot A_1 \cdot \frac{P}{h \cdot \nu} \cdot N_1 + \frac{1}{\tau} \cdot N_2, \tag{38.9}$$

where

σ_1 is the absorption cross-section of BR570 form (on wavelength of acting light)

A_1 is the quantum yield of photoreaction

P is the power density of acting light

τ is the lifetime of M412 form

h is the Plank constant

ν is the acting light frequency

From the same experimental data (Figure 38.11) based on the solution of equation evaluating concentration distribution of BR molecules between forms BR570 (N_1) and M412 (N_2), the estimation of quantum yield of photoreaction A_1 from the value of the derivative at the point $t = 0$ (the beginning of exciting radiation action) and the estimation of the lifetime of M412 form τ from value of derivative at the point $t = t^*$ (the end of exciting radiation action) may be obtained. As time goes by, film transmission value being influenced by the relaxation of excited molecules approaches to the original transmission level.

38.3.2 Functional Characteristics of Nanostructured Bacteriorhodopsin Films

To form the effective functional structures out of biomaterials, we need to apply various technological methods. In particular, we can use BR-containing materials to prove the necessity to use



FIGURE 38.11 Typical curve of photo-induced changes of optical transmission of BR-containing media.

the additional nanostructuring of functional biomolecular films subject to storage and neural network processing with optical methods.

As a result of non-modified BR films' investigations, we established that immediately after obtaining the values, $k_{570}(t)$ are in interval 0.5–0.7 and then decrease to value 0.2 for 3–5 h and demonstrate this value during a few years. In the primary formed films, BR molecules constitute the structure that in time is destroyed in consequence of the heat oscillations, resulting in disordered molecule orientation relative to each other and destruction of hydrogen bonds. To keep the high photochromic sensitivity for the whole period, we can create additional linkages (covalent or hydrogenous) between protein molecules by using chemical reagents.

For example, our use of diamine (1.4-diaminobenzen [DAB]) in the ratio of BR:DAB = 1:3, 1:6 и 1:9 (molecular ratio) has resulted in increased values of factor $k_{570}(t)$ (0.35–0.5) in comparison with non-modified BR films (0.2–0.25) during 12 days. The stabilization of the primary formed BR structure occurs due to the fact that 1.4-diaminobenzen is an aromatic amine and capable to interact with the carboxyl groups of glutamic and aspartic acids. In our opinion, the high values $k_{570}(t)$ for BR:DAB films are the result of raising the lifetime of M412 form owing to the fact that 1,4-diaminobenzen screens extract proton groups.



FIGURE 38.12 Changing values $k_{570}(t)$ in the operation process for the films. BR:GA = 1:30, 1:10, and 1:5.

At the same time the use of glutaric dialdehyde (GA) with sodium tetraborate for the alkaline catalysis of the reaction of bonding between amine groups of BR lysine residues and aldehydic groups of GA (the Schiff base) for the samples BR:GA = 1:5 had more high values of factor $k_{570}(t) = 0.55$ (Figure 38.12), whereas BR:GA = 1:10 and 1:30 had $k_{570}(t) = 0.4–0.5$, which is explained by the high content of GA oxidation products by atmospheric O_2 (glutaric acid) that partially destroy BR molecules. The dynamics change of decay factor $k_{570}(t)$ value was studied during 1 year for BR:GA films (Figure 38.12). The samples BR:GA = 1:5 kept the high value of factor $k_{570}(t)$ (≥0.45) for 120 days. After 330 days for all the samples of BR:GA $k_{570}(t) = 0.3$.

Introduction of amino acids in the content of BR-containing films leads to even better results. The films of BR: glycine, BR: isoleucine, and BR: lysine in molecular ratio from 1:1 to 1:25 had been made. The BR: glycine and BR: isoleucine films were first inhomogeneous optically and characterized by the high light scattering, and consequently had low values of factor $k_{570}(t)$ within the limits of 0.05–0.1. The BR: lysine films were optically transparent and homogeneous. The dynamics of changing value $k_{570}(t)$ for the films with ratio BR: lysine = 1:10 and 1:25 was shown in Figure 38.13. The samples with the ratio BR: lysine = 1:25 kept stable higher values during not less than



FIGURE 38.13 Changing values $k_{570}(t)$ in the operation process for the films. BR: lysine = 1:10 and 1:25.

80 days—$k_{570}(t)$ (0.4–0.55)—in comparison with the check sample (0.15–0.2). At that optical density and transparency, films did not change throughout that time. The samples with ratio BR: lysine = 1:10 demonstrated higher values $k_{570}(t)$ (0.35–0.5) in comparison with the check sample (0.15–0.2) for 330 days.

The above results prove that there are considerable opportunities to improve functional characteristics of BR-containing materials by nanostructuring (by forming additional bonds between BR molecules).

38.3.3 Metal Nanoparticles and Bacteriorhodopsin-Based Hybrid Nanostructures

The other way to expand the functional opportunities of molecular nanophotonics materials is to form hybrid nanostructures. We suggest the system use of some physical phenomena common for nanoscale structures as the basic processes for photonic information systems. In particular, we can use the effect that nano-objects have on the lifetime of excited atoms and molecules located closer than radiation wavelength. This effect is rapidly enhanced near nanoparticles when strong electromagnetic fields locate at plasma resonance frequency. Strong local fields influence the speed of electron transitions (i.e., the processes of light absorption and spontaneous radiation). Such fields can also change spectral characteristics of those processes and lead to substantial enhancement of various nonlinear optical effects. In particular due to strong local fields we can manage tumescence enhancement and effective suppression (depending on the distance), have radiationless energy transition, and manage the quantum efficiency of BR photoreaction and the lifetime of its spectral intermediates. The specified mechanisms could be useful to design photonic devices, which perform basic functions of information systems on the basis of nonlinear dissipative media with distributed feedbacks. It is to be taken into account that the effect nanoparticles have on the excited state of the functional molecule becomes different with the change of the distance between them. This circumstance creates wide opportunities to crease hybrid nanostructure-based composition materials with bridge molecules of various lengths.

In general, hybrid nanostructures are the systems made of three components—colloidal nanoparticles, bridge molecules (spacers) with various linear dimensions, and functional (photochromic, photoluminescence, electroluminescence, etc.) molecules. Below is the description and diagram (Figure 38.14) to show different aspects of hybrid nanostructures' formation with metal nanoparticles.



FIGURE 38.14 Schematic composition of hybrid nanostructures.

Formation of the hybrid nanostructures with adjusted distance between a nanoparticle and a functional molecule includes several key stages:

1. Formation and stabilization of nanoparticles in the polar or nonpolar solvent.
2. Modification of nanoparticle surface in order to functionalize and to ensure selective and self-organizing hybrid nanostructures.
3. Binding of functional molecules with nanoparticle surface.

Formation of nanoparticles compatible with BR photochromic protein has its own peculiarities due to the biological nature of the material as water is used as the main solvent.

The number of spacers used to form BR-based hybrid structures is quite limited due to the chemical properties of both components. First, the spacers must be hydrophilic substances, well soluble in water. Second, functional groups are also very limited. As BR is a protein, its structure is based on polypeptide amino acid consequence, including among others asparagic and glutamic acid residues. Those residues have free carboxylate groups taking no part in the formation of peptide bonds. pH area, where BR demonstrates its functional characteristics, is limited to pH > 5. Under those conditions the molecule is negatively charged. Therefore, to bind with BR functional spacer, the groups must be positively charged. The most efficient spacers look like molecules, including free aliphatic positively charged amino acids. Those substances include, for example, symmetrical diamines (1.6-diaminohexane, 1.7-diaminoheptane) or lysine (2.5-diaminopentane acid). Besides, in low-molecular compounds, one can use polymers, including amino acids in their structure. Polylysine is one of such polymers.

Gold nanoparticle-based nanohybrid structures are relatively easy to form as gold nanoparticles are chemically inert in aqueous suspensions. At the first technological stage we apply the borohydride method, which makes it possible to get smaller particles with more homogenous size distribution than nanoparticles obtained by using the citrate method. Besides to reach that we do not need to use any additional technological tricks. To apply the borohydride method, add 1 mL 1% $HAuCl_4$, 0,5 mL 0.1 M K_2CO_3 to 100 mL distilled water. While stirring the mixture vigorously with a magnetic stirrer, add 140 μL 0.1 M $NaBH_4$ solution (in some 10 μL portions during 10 min).

The technological methods of forming hybrid structures that we are developing are based on mechanisms of special bonding and self-organization activated by interaction of spacers with the appropriate functional groups. To build hybrid nanostructures based on formed gold nanoparticles, we have to modify nanoparticle surface with amino-containing spacers, which are able to actively interact with both BR molecules and the surface of nanoparticle. We have selected symmetrical aliphatic diamines, in particular, 1.6-diaminohexane. The surface of nanoparticles is modified by introducing 1.6-diaminohexane water solution with up to 5000 spacer molecules to 1 nanoparticle. The intensity of spacer molecules bonding with the surface of nanoparticles can be indicated by the fact that after introducing 1.6-diaminohexane, excess gold nanoparticles are quick to aggregate (sometimes with residue). The results of that process can be seen while extracting films out of suspensions by methods of atom microscopic investigation (Figure 38.15).

Comprehensive studies have proved that we need to not only modify the surface of gold nanoparticles but also remove the suspension reacting system components that have failed to react during nanoparticle synthesis as those components destruct BR molecules and obstruct synthesis of hybrid structures. To solve this problem, we have suggested the use of dialyze. Place nanoparticle-containing suspension in the so-called dialysis bag, which is a hollow plastic container with some nanometer-size holes. Sink the dialysis bag into the solution of the substance to be introduced into the system (concentration of the solution should be enough to modify the surface of nanoparticles effectively). The volume of that solution is usually at least 10 times more than the volume of the original suspension. During the process, small organic and nonorganic molecules migrate through the hollow walls of the dialysis bag, depending on the concentration gradient of the hole. Nanoparticles that are bigger than bag holes stay inside the dialysis bag. Some time (around 2 days) later thermodynamic balance is reached. That means that concentration of organic and nonorganic substances get homogenous throughout the volume. Therefore, the solution inside the dialysis bag experiences dilution due to contaminating impurities to an extent and solution volume relates to the volume of the original suspension. Concentration of the substance to modify nanoparticle surface is the same as that of the original solution. Using this method, we have obtained gold nanoparticles with 1.6-diaminohexane-modified surface. Those suspensions are stable. The studies of spectral characteristics of such suspensions have proved that dialysis has no effect on the spectrum of gold nanoparticles form (Figure 38.16).





FIGURE 38.15 AFM characterization of the surface of gold nanoparticle-based films extracted from (A) a suspension with optimum 1.6-diaminohexane level; (B) from a suspension with excessive 1.6-diaminohexane level.

We have synthesized hybrid structures with nanoparticles to BR molecules ratio 1:3600. BR suspension (51 mg/mL) is used as an original one. Hybrid structures are formed by vigorously stirring the suspension with a magnetic stirrer for 2 days at the temperature of the reaction mixture equal to 20°C–25°C. Figure 38.17 demonstrates spectral characteristics of the hybrid nanostructures suspension based on gold nanoparticles, 1.6-diaminohexane, and BR. We have to stress that characteristic spectral maximums of certain components do not decompose and therefore make it more complicated to study functional characteristics of those structures. By using extraction, we have obtained films with the surface characterized by atom microscopic investigation (Figure 38.18).

The use of silver nanoparticles providing optimum combination of spectral characteristics in the nanoparticle–BR system is of more interest. At the same time, silver nanoparticles demonstrate substantial chemical and photochemical activity in water suspension and require special stabilization measures.



FIGURE 38.16 Spectrum of gold nanoparticles after dialysis with 1.6-diaminohexane solution.



FIGURE 38.17 Absorption spectrum for suspension of hybrid nanostructures based on gold nanoparticles, 1.6-diaminohexane, and BR.



FIGURE 38.18 AFM characterization of the surface of hybrid nanostructures films based on gold nanoparticles, 1.6-diaminohexane, and BR.

To solve this problem, we introduce bridge molecules with various functional groups into the reaction system used to synthesize nanoparticles. This single technological operation includes two stages: formation and stabilization of nanoparticles and modification of their surface.

By using this method, we have obtained water suspensions of hybrid nanostructures based on BR and silver nanoparticles while using cysteine, arginine, lysine, and polylysine as spacers.

To form water colloidal suspension of silver nanoparticles we have used the following original water solutions:

1. Cysteine, arginine, and lysine with concentrations $c = 0.09\%$, 0.118%, and 0.122% (weight) correspondingly
2. Polylysine with concentration $c = 0.125\%$ (weight)
3. Silver nitrate with concentration $c = 0.024\%$ (weight)
4. Water solution of sodium boron hydride with concentration $c = 0.4\%$ (weight) (to stabilize particles we have added 2.5% (vol.) 1 M solution of sodium hydroxide)

To form nanoparticles, first we add the specified volume of spacer solution (up to 0.2% total volume) into silver nitrate solution. Then we introduce 120 μL boron hydride solution (divided into several 30 μL portions to be introduced every 5 min) while stirring the mixture vigorously with a magnetic stirrer. Characteristic absorption maximums in the spectrums of silver nanoparticles suspensions stabilized with lysine, arginine, cysteine, and polylysine are at wavelength 390–400 nm (Figure 38.19). Comparing the bands of absorption of silver nanoparticles stabilized with monomer amino acids and stabilized with polylysine, we can conclude that nanoparticles stabilized with amino acids are smaller in size than nanoparticles stabilized with polylysine. That conclusion is proved by the fact that the spectral maximum of the polylysine-stabilized nanoparticles is located in a longer wavelength area, at $\lambda = 398$ nm, whereas absorption maximums for amino-acid-stabilized nanoparticles are located at $\lambda = 390$–392 nm. Nanoparticles of smaller sizes are likely to occur due to the higher mobility of monomer molecules as synthesis is a quick



FIGURE 38.19 Absorption spectra for suspensions of silver nanoparticles stabilized with various amino acids (arg—arginine; cys—cysteine; lys—lysine; plys—polylysine).



FIGURE 38.20 Absorption spectra for suspensions of cysteine-stabilized silver nanoparticles depending on various spacer concentrations.

reaction, whereas polymer molecules of polylysine are too big to take optimal confrontation that fast. It could also be explained by the fact that silver nanoparticles quite easily form nonspherical structures. This can lead to absorption maximums moving to the long wavelength area (Krutyakov et al., 2008).

The spectral characteristics (location of absorption maximum and absorption intensity) of the silver nanoparticle suspensions also depend on spacer concentration. Nanoparticles of the most homogenous sizes have been formed in suspensions with silver into spacer ratio close to 1:1. The fact is proved by the smaller semi-width of characteristic peaks in the nanoparticle spectrum (Figure 38.20).

Figure 38.19 demonstrates that characteristic maximums in the spectrum of absorption of silver nanoparticles and BR are divided into 160–170 nm to make it easier for the analysis and application of hybrid nanostructure optical properties to form functional nanocomposites to happen.

As mentioned above, the technological methods of forming hybrid nanostructures are based on the mechanisms of special bonding and self-organization activated by selecting appropriate bridge molecules for various functional groups. For example, during formation and stabilization of silver nanoparticle molecules of cysteine, arginine, lysine, and polylysine bond with the surface with the help of thio- (cysteine), guanydo- (arginine), or amino groups (lysine and polylysine). At the same time those molecules are spacers as they include additional amino groups which are able to actively interact with carboxyl groups of glutamic and asparagic acid residues, included in the amino acid consequence of BR. So, by using silver nanoparticles and BR molecules we can obtain hybrid nanostructures.

Such hybrid structures are synthesized with nanoparticles into BR molecules ratio equal to 1:3600. We use 5 mg/mL BR suspension as the original one. The hybrid nanostructures are formed by vigorously stirring the suspension with a magnetic stirrer for 1 day at the temperature of the reaction mixture equal to 22°C–25°C.

Figures 38.21 and 38.22 demonstrate spectral characteristics of hybrid nanostructures using lysine and polylysine as spacers.



FIGURE 38.21 Absorption spectrum for suspension of hybrid nanostructures based on silver nanoparticles, lysine, and BR.



FIGURE 38.22 Absorption spectrum for suspension of hybrid nanostructures based on silver nanoparticles, polylysine, and BR.

While analyzing the technological results of obtaining hybrid nanostructures, we have to pay attention to the following:

The spectral characteristics of hybrid nanostructure suspensions demonstrate two characteristic spectral maximums, corresponding to certain components. It proves that BR and nanoparticle bonding causes no destruction of materials and BR molecules keep their functioning.

1. The characteristic spectral maximums of certain components of hybrid nanostructures may be offset. For example, the suspension of hybrid nanostructures based on silver nanoparticles, lysine, and BR demonstrates absorption maximum offset for silver nanoparticles from 391 to 408 nm (Figure 38.21), whereas the location of absorption maximum for BR stays the same—568 nm. The suspension of hybrid nanostructures based on the silver nanoparticles, polylysine, and BR demonstrates absorption maximum offset for BR from 568 to 560 nm, whereas the location of absorption maximum for the silver nanoparticles stays almost the same 400 nm (Figure 38.22). It could possibly happen because of the different distances between nanostructure components due to various spacer molecules (≈0.75 nm of lysine and ≈1.5 nm of polylysine), the type of bonding with nanoparticle surface, and BR.
2. After measuring the spectral characteristics of hybrid nanostructures, we have found out considerably increased absorption by every component of hybrid nanostructure against the adaptive spectral characteristic calculated by the simple adding of the spectrum of separate components in the same concentration they have in the suspension of hybrid nanostructures. The absorption increase reaches 13% at $\lambda = 394$ nm (cysteine-stabilized silver nanoparticles) and 26% at $\lambda = 568$ nm (BR) (Figure 38.23).

Therefore, synthesized hybrid nanostructures demonstrate functionality, mutual influence of certain components on spectral characteristics of each other, as well as an influence on BR photocycle.



FIGURE 38.23 Factual spectrum of hybrid nanostructure suspension based on silver nanoparticles, cysteine, bacteriorhodopsin, and additive spectrum from spectra of separated components.

38.4 Summary

The use of molecules with conformation-adjusted relative position (distance and angle) of molecular groups including bridge functional groups as spacers can contribute to the development of nanotechnological and nanosystem approaches based on self-organization. Using the above method, we can regulate dipole–dipole interaction of a nanoparticle and a functional molecule. The effect is more obvious for nonspherical particles. Taking into the account that BR molecule performs photo-dependent transit of charge (H^+), the above method of regulating photochromic photoreaction and the lifetime of intermediates must be quite effective. The suggested approach can also be applied for hybrid nanostructures with different composition.

Therefore, we have demonstrated the system and technological aspects of self-organization of functional nanostructures of molecular photonics realizing bionic principles of neural network appliances operation.

The systems designed are expected to have some functional characteristics, making them to sense and analyze like live intellectual neural systems. For example, apart from having distributed and content-addressed memory and the ability to learn and identify steady images, those systems will be able to identify dynamic images, i.e., images of evolving objects. Such abilities are based on new functions built upon self-organization of structures and processes, including: adaptive sensing with feedbacks, regulating activity of various parts of artificial retina; adaptive change of sampling rate and of retina coverage; modeling of tunable retinal receptive fields with spatial filtering; and formation of structures sensitive to the direction and speed of object movements.

References

Akiyama, K., Takimoto, A., and Ogawa, H. 1995. Spatial light modulator and neural network. U.S. Patent 5428711.

Birge, R.R., Gillespie, N.B., Izaguirre, E.W., Kusnetzow, A., Lawrence, A.F., Singh, D., Song, Q.W., Schmidt, E., Stuart, J.A., Seetharaman, S., and Wise, K.J. 1999. Biomolecular electronic: Protein-based associative processors and volumetric memories. *Journal of Physical Chemistry B* 103: 10746–10766.

Engel, S.J. 1990. Neural network processing system. European Patent EP0382230A2.

Grebennikov, E.P. 1997. Light-radiation-induced structure formation of bacteriorhodopsin films for the development of self-organizing information processing systems. *Proceedings of SPIE* 3402: 460–465.

Hampp, N. 2000. Bacteriorhodopsin as a photochromic retinal protein for optical memories. *Chemical Review* 100: 1755–1776.

Haronian, D. and Lewis, A. 1991. Elements of a unique bacteriorhodopsin neural network architecture. *Applied of Optics* 30(5): 597–608.

Krutyakov, Yu.A., Kudrinskiy, A.A., Olenin, A.Yu., and Lisichkin, G.V. 2008. Synthesis and properties of silver nanoparticles: Advances and prospects. *Russian Chemical Review* 77(3): 233–257.

Oesterhelt, D., Brauchle, C., and Hampp, N. 1991. Bacteriorhodopsin: A biological material for information processing. *Quarterly Reviews of Biophysics* 24(4): 425–478.

Prigogine, I. 1980. *From Being to Becoming: Time and Complexity in the Physical Sciences*. San Francisco, CA, W. H. Freeman & Co.

Siebert, F., Mantele, W., and Kreutz, W. 1982. Evidence for the protonation of two internal carboxylic groups during the photocycle of bacteriorhodopsin. *FEBS Letters* 41: 82–87.

Unger, H.G. 1980. *Planar Optical Waveguides and Fibers*. Oxford, U.K., Oxford University Press.

Vsevolodov, N.N. 1988. *Biopigment-Photographic Recorders. Photomaterial Based on Bacteriorhodopsin*. Moscow, Science Publ. (in Russian).

Wasserman, F. 1989. *Neural Computing: Theory and Practice*. New York, Van Nostrand Reinhold Co.

Zeisel, D. and Hampp, N. 1992. Spectral relationship of light-induced refractive-index and absorption changes in bacteriorhodopsin films containing BR-WT and the variant BR-D96N. *Journal of Physical Chemistry* 96(19): 7787–7792.

Zlenko, A.A., Kiselev, V.A., Prokhorov, A.M., Spikhal'skii, A.A., and Sychugov, V.A. 1975. Emission and reflection of light by a corrugated section of a waveguide. *Soviet Journal of Quantum Electronics* 5: 1325–1328.

VI

Nanoscale Lasers

39 **Nanolasers** *Marek S. Wartak* **39**-1
Introduction: Properties of Laser Radiation • Overview of Lasers • Semiconductor Lasers • Rate Equation Approach • Definition of Nanolaser • Nanowire Lasers • Plasmonic Lasers • Photonic Crystal Lasers • Scattering Lasers • Organic Nanolasers • Applications • Conclusions • Acknowledgment • References

40 **Quantum Dot Laser** *Frank Jahnke* **40**-1
Introduction • Electronic States of Quantum Dots • Scattering Processes of Carriers in Quantum Dots • Optical Gain of the Active Material • Laser Emission Properties • Acknowledgments • References

41 **Mode-Locked Quantum-Dot Lasers** *Maria A. Cataluna and Edik U. Rafailov* **41**-1
Introduction • Ultrafast Laser Diodes • Quantum Dots: Distinctive Advantages for Ultrafast Diode Lasers • Mode-Locked Quantum-Dot Lasers: State of the Art • Summary and Outlook • Acknowledgments • References

39

Nanolasers

39.1 Introduction: Properties of Laser Radiation 39-1
39.2 Overview of Lasers 39-2
39.3 Semiconductor Lasers 39-2
39.4 Rate Equation Approach 39-4
39.5 Definition of Nanolaser 39-5
39.6 Nanowire Lasers 39-5
Ring Resonator Nanolasers • Theoretical Analysis of Nanowires • Recent Work on Nanowire Lasers
39.7 Plasmonic Lasers 39-8
Bowtie Structures • Dipole Nanolaser
39.8 Photonic Crystal Lasers 39-10
Edge-Emitting Photonic Crystal Nanolaser • Silicon Nanocrystals
39.9 Scattering Lasers 39-10
Mie Nanolasers • Random Lasers
39.10 Organic Nanolasers 39-11
39.11 Applications 39-12
Nanolaser Device Detects Cancer in Single Cells • Biological and Chemical Detection • Ultrahigh Data Storage
39.12 Conclusions 39-12
Acknowledgment 39-12
References 39-12

Marek S. Wartak
Wilfrid Laurier University

39.1 Introduction: Properties of Laser Radiation

A laser is a device that emits light (or more generally electromagnetic (EM) radiation) through a process called stimulated emission. The term "laser" is an acronym for light amplification by stimulated emission of radiation [1]. The first working laser was demonstrated on May 16, 1960, by Theodore Maiman at Hughes Research Laboratories. It was a pulsed ruby laser. The main characteristics of laser beam are monochromaticity, coherence, divergence, and brightness.

Monochromaticity is associated with the fact that in a laser, only an EM radiation at a particular frequency (or wavelength) is amplified. In practice, it has a certain range, called linewidth, which is determined by homogeneous and inhomogeneous broadening factors. The linewidth is very small compared with typical light sources. Additionally, due to the laser cavity, which forms a resonant system, the oscillation can occur only at the resonance frequencies of this cavity. This leads to the further narrowing of laser linewidth, often by several orders of magnitude.

Coherence is associated with the phase difference. For any EM wave, there are two kinds of coherence, namely, spatial and temporal coherence. Typical laser source emission is very coherent. Most other light sources emit incoherent light, which has a phase that varies randomly with time and position.

Let us illustrate first the spatial coherence. For that, consider two points of EM wave, which, at time $t = 0$, have phase difference ϕ_0. If for any time $t > 0$ the phase difference of EM wave at those points remains ϕ_0, we say the EM wave has perfect coherence between the two points. If this is true for any two points of the wave front, we say the wave has perfect spatial coherence.

Now, consider a fixed point on the EM wave front. If at any time the phase difference between time t and time $t + \Delta t$ remains the same, where Δt is some time delay, we say that the EM wave has temporal coherence over a time Δt. If Δt can be any value, we say the EM wave has a perfect temporal coherence. If this happens only in a range $0 < \Delta t < t_0$, we say it has partial temporal coherence, with a coherence time equal to t_0. Laser light is highly coherent, and this property has been widely used in measurement, holography, etc.

Laser beam is also highly *directional*, which implies that laser light has very small divergence. This is a direct consequence of the fact that laser beam comes from the resonant cavity, and only waves propagating along the optical axis can be sustained in the cavity. The directionality is described by the light beam divergence angle.

The brightness of a light source is defined as the power emitted per unit surface area per unit solid angle. Brightness is inversely proportional to the square of laser divergence; therefore laser light is much brighter than normal light source.

39.2 Overview of Lasers

In gas lasers, the active medium can be regarded effectively as an ensemble of absorption or amplification centers (like, e.g., atoms or molecules) with only electronic energy levels, which couple to the resonant optical field. Other electronic states are used to excite or pump the system.

The generic laser structure is shown in Figure 39.1. It consists of a resonator (cavity) formed by two mirrors and gain medium where the amplification of electromagnetic radiation (light) takes place. A laser is an oscillator analogously like an oscillator in electronics and requires a resonator, which provides feedback. Feedback is provided by two mirrors. Mirrors confine light and provide optical feedback. One of the mirrors is partially transmitting, which allows the light to escape from the device. There must be an external energy provided into the gain medium (process known as pumping). The most popular (practical) pumping mechanisms are by optical or electrical means.

The gain medium can be created in several ways. Conceptually, the simplest one is the collection of gas molecules. The pumping process excites these molecules into a higher energy level. The popular visualization of such collection of molecules is as two-level systems (TLS) (see Figure 39.2). Only two energies (out of many in the case of a molecule) are selected and the transitions are considered within these two energies. As illustrated, three basic processes are possible: absorption, spontaneous emission, and stimulated emission.

Such TLS are found very often in nature. Generally, for an atomic system, for the case under consideration, we can always separate just two energy levels: upper level and ground state, thereby forming TLS.



FIGURE 39.1 Generic laser structure: two mirrors with a gain medium in between. The two mirrors form a cavity, which confines the light and provides the optical feedback. One of the mirrors is partially transmitted and thus allows light to escape. The resulting laser light is directional, with a small spectral bandwidth.



FIGURE 39.2 Possible electronic transitions in two-level system. (a) Absorption, (b) Stimulated emission, and (c) Spontaneous emission.

Electron can be excited into upper level due to external interactions (for lasers through a process known as pumping). Electrons can lose their energies radiatively (emitting photons) or nonradiatively, say by collisions with phonons.

For laser action to occur, the pumping process must produce population inversion meaning that there are more molecules in the excited state (here upper level with energy E_2) than in the ground state. If population inversion is present in the cavity, the incoming light can be amplified by the system (see Figure 39.2b) where one incoming photon generates two photons as the output.

The way how TLS is practically utilized results in various types of lasers, like gaseous, solid state, or semiconductor. Also, different types of resonators are possible as will be discussed in subsequent sections.

39.3 Semiconductor Lasers

A significant percentage of today's lasers are fabricated using the semiconductor technology. Those devices are known as semiconductor lasers. Over the last 15 years or so, several excellent books describing different aspects and different types of semiconductor lasers have been published [2,3].

The operation of semiconductor lasers as sources of electromagnetic radiation is based on the interaction between EM radiation and the semiconductor. Typical semiconductor laser structures are shown in Figure 39.3. These lasers can be classified as in-plane laser where light propagates in a parallel direction [4] and vertical cavity surface emitting laser (VCSEL) [5].

The largest dimension of in-plane structures is typically in the range of 250 μm (longitudinal direction) and as such cannot be considered as a nanolaser. The structure of interest to us is the one where light propagates perpendicularly to wafer's surface and it is known as VCSEL (see Figure 39.3b). The typical diameter of VCSEL cylinder is about 10 μm.

The basic semiconductor laser is just a p–n junction (see Figure 39.4) in which the cross-section along the lateral–transversal directions is shown. Current flows (holes on p-side and electrons on n-side) along the vertical direction, whereas the light travels horizontally and leaves the device on both sides.

Light propagation with amplification is illustrated in Figure 39.5. Mathematically it is described by assuming that there is no phase change on reflection at either end (left and right). The left end is defined as $z = 0$ and right end as $z = L$. At the right facet, the forward optical wave has a fraction r_R reflected (amplitude



FIGURE 39.3 In-plane laser (a) and VCSEL (b).



FIGURE 39.4 The basic p–n junction laser.



FIGURE 39.5 Schematic illustration of the amplification in a Fabry–Perot (FP) semiconductor laser with homogeneously distributed gain.

reflection) and after reflection the fraction travels back (from right to left).

In order to form a stable resonance, the amplitude and phase of the single round trip must match the amplitude and phase of the starting wave. At arbitrary point z inside the cavity (see Figure 39.5) the forward wave is

$$E_0 e^{gz}\ e^{-j\beta z}$$

where we have dropped e^{jwt} common term and $g = g_m - \alpha_m$. Here r_R and r_L are, respectively, right and left reflectivities, g is gain (and loss), L length of the cavity, and β the propagation constant.

The wave traveling one full round will be

$$\{E_0 e^{gz}\ e^{-j\beta z}\}\ \{e^{g(L-z)} e^{-j\beta(L-z)}\}\{r_R e^{gL} e^{-j\beta L}\}\times\{r_L e^{gz} e^{-j\beta z}\} \tag{39.1}$$

The above terms are interpreted as follows. In the first bracket, there is an original forward propagating wave at z, in the second bracket, there is wave traveling from z to L, third bracket describes wave propagating from $z = L$ to $z = 0$, and the last one contains wave traveling from $z = 0$ to the starting point z. At that point, the wave must match original wave and thus one obtains condition for stable oscillations:

$$r_R r_L e^{2gL} e^{-2j\beta L} = 1 \tag{39.2}$$

That condition can be split into amplitude condition

$$r_R r_L e^{2(g_m - \alpha_m)L} = 1 \tag{39.3}$$

and phase condition

$$e^{-2j\beta L} = 1. \tag{39.4}$$

From the amplitude condition, the following relation is obtained:

$$g_m = \alpha_m + \frac{1}{2L} \ln \frac{1}{r_R r_L} \tag{39.5}$$

From the phase condition, it follows that

$$2\beta L = 2\pi n \tag{39.6}$$

where n is an integer. The last equation determines wavelengths of oscillations since

$$\beta = \frac{2\pi}{\lambda_m} \tag{39.7}$$

with λ_m being the wavelength.

In VCSEL, the cavity is formed by the so-called Bragg mirrors and an active region typically consists of several quantum well layers separated by barrier layers (see Figure 39.3). Bragg mirrors consist of several layers of different semiconductors, which have different values of refractive index. Due to the Bragg reflection,



FIGURE 39.6 Illustration of various active regions with different dimensionality. (a) three-dimensional (3D) or bulk structure, (b) two-dimensional (2D) structure known as quantum well, (c) one-dimensional (1D) structure known as quantum wire, and (d) zero-dimensional (0D) structure known as quantum dot. (Adapted from Arakawa, Y. and Sakaki, H., *Appl. Phys. Lett.*, 40, 939, 1982.)



FIGURE 39.7 Calculated gain spectra for quantum dot, quantum wire and quantum well. For comparison, results for bulk crystal are also shown as dotted line. (Adapted from Asada, M. et al., *IEEE J. Quantum Electron.*, 22, 1915, 1986.)

such a structure shows a very large reflectivity (around 99.9%). Such large values are needed because a very short distance of propagation of light does not allow to build enough amplification when propagating between mirrors.

From the electromagnetic analysis of the optical cavity, the quality factor Q of the cavity [6] can be determined as

$$Q = \frac{\Delta\omega}{\omega_0} \tag{39.8}$$

where

$\Delta\omega$ is the cavity linewidth

ω_0 the resonant frequency of the cavity

Gain spectra (also other properties) strongly depend on size of the active region. Different gain media are possible, consisting of 0D, 1D, 2D, 3D (bulk) structures (see Figure 39.6). The typical thickness of a quantum well is about 10 nm. The dimensionality of these structures have profound consequences on laser properties. An illustration of gain spectra obtained with gain media for structures of different dimensionalities is shown in Figure 39.7. As can be seen, the shape of spectrum becomes sharper with increasing quantization dimension. This is due to the variation of the density of states.

39.4 Rate Equation Approach

In a typical laser, there exists two types of subsystems: photons and carriers. A quantitative description of a laser system is given in terms of rate equations. One introduces the number of photons S inside the cavity and number of carriers N (can be also a number of excited molecules for some systems). The rate equations describe the time evolution of S and N, as follows:

$$\frac{dN}{dt} = \eta_i \frac{I}{qV} - \frac{N}{\tau} - v_g g(N)S \tag{39.9}$$

$$\frac{dS}{dt} = \Gamma v_g g(N)S - \frac{S}{\tau_p} + \Gamma\beta R_{\text{sp}} \tag{39.10}$$

We have explicitly indicated that gain g depends on the carrier's concentration.

In Equation 39.9 the first term is responsible for pumping (in this case electrical), with I being the current, the second term accounts phenomenologically for losses, and the last one describes coupling to the photon system.

The last term in Equation 39.10 accounts for spontaneous emission (with the coefficient β). The β coefficient describes the amount of spontaneous emission that contributes to the lasing mode. The β factor is inversely proportional to the number of available modes into which the gain medium can spontaneously emit photons. In typical in-plane lasers, it is a small number (like 10^{-4}) [3]. The value of β is between 0 and 1.

The typical power–current characteristic of semiconductor laser is shown in Figure 39.8 for two extreme cases of β. When $\beta = 1$, all the spontaneously emitted photons end up in the lasing mode. For small values of β, the laser has a well-defined threshold. At threshold, the optical gain compensates for the losses. Above the threshold, the laser operates in a stimulated emission mode and below the threshold, spontaneous emission dominates.

A large β is the key factor in single-photon laser sources [7,8]. The (still hypothetical) case of $\beta = 1$ is often referred to as a thresholdless laser [9]. In the thresholdless laser, all photons participate in the stimulated emission. Such a device would require a small amount of energy to operate. Its dimensions should be very small, say ~λ.



FIGURE 39.8 Current–power characteristics for two values of spontaneous emission factor.

Several issues must be addressed before one could fabricate thresholdless laser [10,11]. Those include: (a) optical modes that induce undesired spontaneous emission should be suppressed where possible, (b) creation of a single-cavity mode with a sufficiently high Q factor and a small modal volume is essential, and (c) excited carriers should be concentrated to emit light coupled to the single-mode cavity.

39.5 Definition of Nanolaser

The need to reduce the size of the semiconductor laser is one of the most active and challenging areas of modern optoelectronics. On the theoretical side, size reduction is important for understanding the basic laser concepts and fundamental light–matter interactions. On the practical side, smaller lasers will find various applications as light sources in integrated optical systems.

If photonics should be compatible with VLSI as for as lasers are concerned, photonic devices must shrink in size to 100 nm (or less) length scales. As indicated in the previous section, the smallest lasers available commercially today are VCSELs. However, in the last few years, the new type of even smaller devices is emerging, namely, nanowire lasers. Their cylindrical dimensions range from few tens up to hundreds of nanometers, whereas their lengths are typically within a few hundreds of microns.

The typical volume of conventional miniature lasers such as VCSELs is determined by the volume of the cavity mode. The effective wavelength in the dielectric should be of the order of the characteristic length of the device. This leads to the existence of the effective modal volume $V > (\lambda/2n)^3$, a condition known as the diffraction limit. Reduction of the volume of the active region is the potential factor for lowering the threshold current.

Recent advances in technology allow the fabrication of optical nanoscale devices where the wave nature of photons becomes one of the most critical variables. It provides the challenges in the realization of a tiny coherent photon source. The localization of the wave is difficult when wavelengths of photons become much larger than the spatial variation of the confinement structure.

As the dimensions of optical nanodevices scale down, devices can be fabricated with effectively only one optical emission mode. These structures could be termed *nanolasers* (see [8]). Alternatively, nanolasers can be defined as structures having dimensions smaller than the wavelength of light in all three dimensions [12]. Recent summaries of research on nanolasers can be found in Refs. [12,13].

In the following sections, we will discuss examples of recently the developed nanolasers (and related) structures:

- Nanowire lasers
- Plasmonic lasers
- Photonic crystal lasers
- Scattering lasers
- Organic lasers

We conclude this chapter with a brief discussion of applications of nanolasers in sensing and medicine.

39.6 Nanowire Lasers

Various types of nanocavities have been fabricated and a coherent laser emission from such structures has been observed. Among others, lasing has been demonstrated in droplets [14,15], silica [16], and polystyrene spheres [17], semiconductor microdisks [18–20], micropillars [21], photonic crystal cavities [22], nanoribbons [23], ZnO arrays [24], GaN nanowires [25], and single-crystal ZnO nanowires [26].

Several methods of the synthesis of semiconductor nanowire heterostructures have been developed, including chemical vapor deposition and the vapor–liquid–solid growth of crystalline semiconductor nanowires. Recent progress in the development of semiconductor nanowires was reviewed by Lauhon et al. [27].

The schematics of a typical cylindrical nanowire laser is shown in Figure 39.9 and the possible schemes of current injection are schematically shown in Figure 39.10. These structures provide photon confinement in volumes of a few cubic wavelengths. A typical lateral dimension of a nanowire is between 20 and 400 nm, with a length in the range of 2–40 μm. As was shown in the journal articles cited earlier, it is possible to grow nanowire arrays with tight control over size (diameter <20 nm) and uniformity (<±10%).

A significant reduction in size of nanometer laser was possible due to large spatial overlap between the active medium (the wire itself) and the guided mode, which propagates along the axial direction. A strong lateral optical confinement is also created. It originates due to the size of the structure itself and also due to large dielectric contrast (difference) between the nanowire material itself and the surrounding material. The end facets of the nanowire form axial Fabry–Perot-type cavity necessary for laser action.

Early experimental evidence for guided modes in nanowires surrounded by air has been reported by Johnson et al. [25] and Duan et al. [28]. Lasing was observed in structures that are rather thick (radius in the 80–200 nm range). In these structures, quantization effects are absent. Such structures can function as the active medium and waveguide at the same time. Structures



FIGURE 39.9 Side view of a nanowire laser. (Adapted from Maslov, A.V. and Ning, C.Z., *Appl. Phys. Lett.*, 83, 1237, 2003.)



FIGURE 39.10 Possible schemes of current injection in nanowires: (a) through the ends of the nanowire and (b) from the core and shell regions. (Adapted from Maslov, A.V., *J. Appl. Phys.*, 99, 024314, 2006.)

with much smaller dimensions (radius about 1 nm) have also been fabricated [29]. In such samples, quantization effects play a dominant role. As an example, resonant nanowire cavity fabricated by Huang et al. [24] achieved gain and lasing through an excitonic lasing action in ZnO with a threshold of 40 kW/cm^2 under optical excitation. (In this case, because of optical pumping, the density of optical power is provided instead of value of electrical current.) A summary of the properties of basic materials used to fabricate nanowires is shown in Table 39.1.

TABLE 39.1 Basic Properties of Materials Used to Fabricate Nanowires

Materials	Emission Wavelength (nm)	Threshold (nJ/cm$^{2)}$	Gain (cm^{-1})	Reference
GaN	370–390	500	400–1000	[85]
ZnO	370–400	70	1000–3000	[85]
CdS	510	—	—	[28]

39.6.1 Ring Resonator Nanolasers

Microrings are common building blocks in photonics [30]. Formation of nanoring resonator is also possible by converting the nanowire into a ring [31].

This change of shape results in a significant modification of the optical spectra of the cavity. For example, the photoluminescence displays Fabry–Perot (FP) resonances that match those calculated for ring resonance. Also, the dielectric imperfection at the overlapping junction causes each FP mode to split into a doublet, thus breaking the degeneracy between clockwise and anticlockwise photon propagation (see Figure 39.11b).

Microring nanolasers were fabricated and analyzed by Berkeley group led by Yang [31]. The ring structure was fabricated from a linear GaN nanowire (see Figure 39.11). We show here a GaN nanowire before manipulation into a ring configuration (a) and after creation of ring geometry (b). It is not a subwavelength device as can be seen from that figure. In the ring after coupling, a dielectric discontinuity is introduced (since each ends of the original wire are now positioned side by side). This side-by-side overlap is responsible for evanescent coupling between cavity arms (see Figure 39.12).

The circulating optical modes within a resonator cavity containing a defect are theoretically equivalent to a photonic molecule [32] (compare Figure 39.11c). Dielectric discontinuity after coupling leads to perturbation within the cavity and breaks the resonance degeneracy into clockwise and counterclockwise mode propagations. It is known that such perturbed cavity is theoretically equivalent to two perfect cavities that are coupled.



FIGURE 39.11 Transition from wire linear cavity to a ring resonator and the theoretically equivalent photonic molecule. (Adapted from Pauzauskie, P.J. et al., *Phys. Rev. Lett.*, 96,143903, 2006.)



FIGURE 39.12 Cross-section view of the ring structure showing the side-by-side overlap that enables evanescent coupling between cavity modes.

The lasing behavior between nanowires and their resonator counterpart is also markedly different. The emission maximum of ring laser is red shifted up to 10 nm relative to the wire (see [31]).

39.6.2 Theoretical Analysis of Nanowires

For a mathematically oriented reader, we provide here the main elements of theory of nanolasers. This section can be skipped in the first reading.

Theoretical and numerical analysis of nanowire lasers was reported in a series of papers by Maslov and Ning [33–37] and also by Chen and Towe [38]. From experiments, we know that lasing occurs through the end facets of the nanowire (see Figure 39.9 (from Ref. [33].)

The nanowire can support transverse electric (TE_{0m}) and transverse magnetic (TM_{0m}) modes, which have only three field components and no dependence on ϕ and hybrid modes (HE_{nm} and EH_{nm}), which have all six field components [33]. In the axial approximation, the field components are of the type [34]

$$\tilde{E}_z^n(r) = \begin{cases} A_n J_n(\kappa_2 r), & r < r' \\ B_n J_n(\kappa_2 r) + C_n Y_n(\kappa_2 r), & r' < r < R \\ D_n H_n(\kappa_1 r), & r > R \end{cases} \tag{39.11}$$

$$\tilde{H}_z^n(r) = \begin{cases} F_n J_n(\kappa_2 r), & r < r' \\ G_n J_n(\kappa_2 r) + N_n Y_n(\kappa_2 r), & r' < r < R \\ M_n H_n(\kappa_1 r), & r > R \end{cases} \tag{39.12}$$

where J_n and Y_n are the Bessel functions of the first and second kind, respectively. $H_n = H_n^{(1)} = J_n + iY_n$ is the Bessel function of the third kind (Hankel's function). Also, the following definitions of transverse wave numbers were introduced: $\kappa_{1,2}^2 = \varepsilon_{1,2}\omega^2/c^2 - h^2$. The eight unknown coefficients A, B, C, D, F, G, N, and M should be determined from the boundary conditions at the interfaces $r = r'$ and $r = R$.

The numerical approach is based on solving Maxwell's equations using finite difference time-domain (FDTD) method in cylindrical coordinates [35]. Typical computational window is shown in Figure 39.13.

The modes supported in such nanowire structures are similar to those of optical fibers (for a discussion of modes in fiber, see [39]) but are more localized due to high refractive index contrast between the nanowires and the surrounding air.

The Maslov–Ning analysis suggests that the natural facets of the nanowires provide very low quality factors (of the order of hundreds) for nanowires of about 10 μm in length. These factors are very sensitive to the mode type and nanowire radius.

Far-field patterns of the emitted radiation were also discussed [34,35]. It was determined how the radiation pattern depends on the lasing mode. The radiation is emitted in a very broad range of angles with respect to the nanowire axis. Also, the directionality weakens with an increase of the nanowire radius.



FIGURE 39.13 Schematic of the FDTD computational domain. (Adapted from Maslov, A.V. and Ning C.Z., *Opt. Lett.*, 29, 572, 2004.)

Using their methods, Maslov and Ning recently reported on the numerical analysis of semiconductor nanowire covered with a metal as a possible laser waveguide [40]. Their analysis opens the possibilities of fabricating even smaller nanowire-based lasers. Maslov and Ning analyzed the possible advantages of using a semiconductor nanowire encased in a metal as a laser waveguide. They showed that despite large Joule loss, such structure can be a good candidate for subwavelength laser operating in TM_{01} mode.

Coupled drift–diffusion simulations of nanowire lasers have been recently reported by Chen and Towe [38]. They extended the FDTD approach by including carrier effects. Their method is based on numerical solution of the steady-state 2D drift–diffusion carrier transport equations, which are coupled with the photon generation rate equations. The basic system of equations is as follows:

$$\nabla \cdot \left[-\varepsilon \nabla \psi(x,y) \right] = q\left[p(x,y) - n(x,y) + N_D^+ - N_A^- \right] \tag{39.13}$$

$$\nabla \cdot \mathbf{J}_n = -q\left[G(n,p) - R_{\mathrm{sp}}(n,p) - R_{\mathrm{st}}(n,p) - R_{\mathrm{Auger}}(n,p) - R_{\mathrm{SRH}}(n,p) \right] \tag{39.14}$$

$$\nabla \cdot \mathbf{J}_p = q\left[G(n,p) - R_{\mathrm{sp}}(n,p) - R_{\mathrm{st}}(n,p) - R_{\mathrm{Auger}}(n,p) - R_{\mathrm{SRH}}(n,p) \right] \tag{39.15}$$

$$\mathbf{J}_n = qD_n \nabla n(x,y) - q\mu_n n(x,y) \nabla \psi(x,y) \tag{39.16}$$

$$\mathbf{J}_p = -qD_p \nabla p(x,y) - q\mu_p p(x,y) \nabla \psi(x,y) \tag{39.17}$$

$$G_m S_m - \frac{S_m}{\tau_{p,m}} + R_{sp,m} = 0 \tag{39.18}$$

where $G(n, p)$ is the carrier generation rate, $R_{\mathrm{sp}}(n, p)$ is the local spontaneous recombination rate, $R_{\mathrm{st}}(n, p)$ is the local stimulated recombination rate, $R_{\mathrm{SRH}}(n,p)$ represents Shockley–Read–Hall (SRH) dark recombination rate, G_m, S_m, $\tau_{p,m}$, $R_{sp,m}$ are, respectively, the modal gain, the photon number in the cavity, photon lifetime and for the mth lasing mode, and the spontaneous emission rate that couples to the mth lasing mode.

39.6.3 Recent Work on Nanowire Lasers

We conclude the section on nanowires with a description of recent works that go beyond single cylindrical nanowire. First, we describe nanowires with metal coating and then the combination of nanowires and quantum wells.

The dimensions of semiconductor nanolasers can be further shrunk by using metal-coated nanowires. Such a structure was first fabricated in 2007 by Hill et al. [41] and this structure was shown to be the smallest electrically pumped nanolaser. They coated a thin semiconductor heterostructure post made of In/InGaAs/InP with a layer of gold as shown in Figure 39.14. The diameter was 210 nm. Electrons are injected through the top of the pillar and holes are injected through a large-area lateral contact.

The device lased in the near-infrared at a wavelength of 1408 nm. The mode was an HE_{11}-like mode oscillating near the InGaAs region cutoff frequency.

All previously described studies have concentrated on fabrication of nanolasers from homogeneous semiconductors such as gallium nitride (GaN). This means that the laser wavelength is determined by the band gap of the used material. In such a design, there is no possibility to tune the properties of the laser.

However, with proper technological tools, structures in which gain and cavity functionalities are decoupled can be designed and fabricated. The purpose of decoupling the gain medium and the cavity is not to separate but to combine the best properties of both subsystems. Thus quantum wells provide the optical gain medium whereas the nanowire acts as the optical cavity.



FIGURE 39.14 (a) Structure of the cavity formed by a semiconductor pillar encapsulated in gold. (b) Cross-section of the pillar. (Adapted from Hill, M.T. et al., *Nat. Photonics*, 1, 589, 2007.)



FIGURE 39.15 Cross-sectional view of a (a) GaN-based core/multi-shell nanowire structure and (b) the corresponding energy band diagram. (c) InGaN multiple quantum well (MQW) nanowire structure. (Adapted from Qian, F. et al., *Nat. Mater.*, 7, 701, 2008; Qian, F. et al., *Nano Lett.*, 5, 2287, 2005.)

This new type of nanolasers was described by Qian et al. [42]. The structure is shown in Figure 39.15. It consists of a GaN nanowire core that acts as the optical cavity surrounded by InGaN/GaN multiple quantum well (MQW) shells that serve as a composition-tunable gain medium. By varying the indium content, the emission wavelength can be tuned between 365 and 494 nm, with all devices operating at room temperature. Their nanowire heterostructure contains 3 to 26 quantum wells. Typical nanowires were 200–400 nm in "diameter" and 20–60 μm in length. Although the nanolasers were optically pumped, the authors believe that electrical injection is possible.

39.7 Plasmonic Lasers

Surface plasmon mode confinement has been used to achieve subwavelength modal dimensions at the expense of optical loss [43–45]. Several structures that involve plasmons were proposed. A comprehensive introduction to the main physical aspects involved in plasmonic devices were recently summarized by Dragoman and Dragoman [46].

A summary of the analysis of the plasmonic nanoresonators has recently been provided by Maier [47]. Plasmon cavities can confine electromagnetic energy into both physical and effective mode volumes far below the diffraction limit.

Manolatou et al. [48,49] proposed and analyzed a family of nanoscale cavities for electrically pumped surface-emitting semiconductor lasers that use surface plasmons to provide optical confinement. The analyzed cavities have radii between 100 and 300 nm and the heights of the dielectric part of the cavity between 100 and 250 nm. The metal layers were assumed to be thick enough to prohibit light transmission. The typical circular nanopatch laser analyzed by Manolatou and Rana [49] is shown in Figure 39.16.



FIGURE 39.16 Circular nanopatch laser.



FIGURE 39.17 Horseshoe optical nanoantenna. (Adapted from Sarychev, A.K. and Tartakovsky, G., *Phys. Rev. B*, 75, 085436, 2007.)

Sarychev and Tartakovsky [50,51] proposed plasmonic nanolaser where the metal nanoantenna operates similarly to a resonator. The structure is shown in Figure 39.17. In this type of laser, metallic horseshoe-shaped nanoantenna interacts with a two-level amplifying system (TLS). TLS can represent quantum dot and can be pumped optically or electrically. The size of the proposed plasmonic nanolaser is much smaller than the wavelength.

39.7.1 Bowtie Structures

Bowtie structure consists of two opposing tip-to-tip metallic nanotriangles separated by a gap with an active element in the form of quantum dot in-between or quantum wells below it. The interaction of a single quantum dot with a bowtie antenna was demonstrated by Farahani et al. [52] for visible light. The enhancement of the electromagnetic field in such a structure was described by Sundaramurthy et al. [53]. They also conducted FDTD analysis. The theory of the electrically pumped plasmonic nanolaser based on bowtie structure was recently reported by Chang et al. [54]. They considered both quantum dot and quantum well.

The geometry of a bowtie nanolaser is shown in Figure 39.18. It consists of a metallic bowtie separated (typically) by about 20 nm. Multiple quantum wells are located below the metallic bowtie, which at optical frequencies have negative dielectric constant. The bowtie tips reduce the effective volume of the cavity mode and lead to the field enhancement around the bowtie tips. This results in an increase of the stimulated and spontaneous emission rates and significant decrease of the threshold current.



FIGURE 39.18 The geometry of a bowtie plasmonic nanolaser. Typical separation between metallic nanotriangles is 20 nm. (Adapted from Chang, S.-W. et al., *Opt. Express*, 16, 10580, 2008.)

39.7.2 Dipole Nanolaser

Diple nanolaser (DNL) has been proposed by Protsenko et al. [55,56]. It consists of a metallic nanoparticle of size r_0 and a two-level system (TLS) of size r_2 formed by a quantum dot, separated by a small distance r (see Figure 39.19). The device does not need an optical cavity and may have a volume much smaller than λ, the lasing wavelength. An incoherent pump provides population inversion in the TLS. The system can be pumped optically or electrically, in which case pumping is provided by injection of carriers from the bands of a semiconductor material surrounding an embedded quantum dot.

The transition frequency of TLS ω_2 is close to the plasmon resonance frequency ω_p of the metallic nanoparticle. There is a strong interaction (a dipole interaction) between those two systems through a near field. It is known that such coupled interaction significantly modifies optical emission.

To understand the operation of DNL, let us remind ourselves that the usual lasing mechanism involves stimulated emission into the mode of a cavity (for the single mode operation) from a medium in which there is a population inversion. Above the threshold condition, when stimulated emission (gain) exceeds absorption plus internal losses, the energy from incoherent pump is transferred into coherent laser radiation with a narrow lasing spectrum.

In DNL, instead of electromagnetic field, one deals with linear oscillations of polarization of a medium. Such a medium can be excited in such a way that the total energy flux into polarization exceeds losses. This leads to polarization oscillations with a narrow spectrum. The analysis of dipole nanolaser conducted by Protensko et al. [55] is based on equations of motion identical to Maxwell–Bloch equations for a TLS in the electromagnetic field of a cavity. Lasing conditions are created when the population



FIGURE 39.19 Dipole nanolaser. Nanoparticle (here on the right) is labeled with "0," TLS (here on the left) has label "2." (Adapted from Protsenko, I.E. et al., *Phys. Rev. A*, 71, 063812, 2005.)

inversion D of energy states of TLS is maintained by optical pumping or injection current to be [56]

$$D > D_{\text{th}} \tag{39.19}$$

where $D_{\text{th}} = (r/r_{\text{cr}})^6$, $r_{\text{cr}} = (4|\alpha_0||\alpha_2|)^{1/6}$ and α_0 and α_2 are polarizabilities of the nanoparticle and the TLS. When D exceeds the threshold value D_{th}, the macroscopic dipole moment of two particles appears spontaneously and they emit coherent dipole radiation at the frequency $\omega \approx \omega_{\text{plr}}$, the nanoparticle plasmon resonance frequency. Condition (39.19) is fulfilled if the distance between particles is small, which means a strong interaction between them through the near field.

39.8 Photonic Crystal Lasers

Photonics crystal (PC) structure consists of a drilled repeating pattern of holes through the laser material. This pattern is called a photonic crystal. One can deliberately introduce an irregularity, or defect, into the crystal pattern, for example, by slightly shifting the positions of two holes. The photonic crystal structure and the defect prevent light of most frequencies from existing in the structure, with the exception of a small band of frequencies that can exist in the region near the defect.

Photonic crystal defect microcavities can provide extremely small mode volume [22,57]. The schematic of the laser proposed by Painter et al. [22] is shown in Figure 39.20. The interhole separation is 515 nm. It was fabricated from InGaAsP grown by MOCVD on an InP substrate. The active region consists of four (here only two are shown) 9 nm 0.85% compressively strained InGaAsP quantum wells. Two-dimensional photonic crystal hexagonal lattice was formed by etching, resulting in air holes that penetrate through the active region and into an underlying sacrificial InP layer.

Over the last few years, various devices have been fabricated and characterized [58–61]. Such structures are associated with single-photon sources, which are required for quantum computing and quantum communications. Single-photon sources are recent applications of the Purcell effect in quantum-dot microcavities.



FIGURE 39.20 Cross-section through the middle of the photonic crystal microcavity. A defect is formed (shown in the middle) by removing a single hole. (Adapted from Painter, O. et al., *Science*, 284, 1819, 1999.)

Recently, scientists from the Yokohama National University in Japan [61] have reported interesting results concerning PC nanolasers. They demonstrated high-performing room-temperature nanolaser in the form of PC slab. The laser is made of a GaInAsP. This ultrasmall laser has a modal volume close to the diffraction limit. When operating in a high-Q mode (about 20,000), it will be useful for optical devices in optical integrated circuits. In a moderate-Q (1500) configuration, the nanolaser needs only an extremely small amount of external power to bring the device to the threshold of producing laser light. In this near-thresholdless operation, it might permit the emission of very low light levels, even single photons.

39.8.1 Edge-Emitting Photonic Crystal Nanolaser

Tiny resonators and waveguides based on photonic crystals provide a promising approach to fabricating high-density photonic integrated circuits. Recently, Yang et al. [62] reported the first demonstration of an edge-emitting photonic crystal nanocavity laser integrated with a photonic crystal waveguide. The structure is based on a double-heterostructure photonic crystal nanocavity with a InAs quantum dot active region. The device consists of four photonic crystal sections, each with a slightly different lattice constant. Five layers of InAs quantum dots, each with a quantum dot density of about $2 \times 10^{10}/\text{cm}^2$, were embedded in the 220 nm-thick GaAs membrane. An output waveguide is butt coupled to the mirror with the fewer number of periods. The device was optically pumped with a semiconductor laser diode at 850 nm wavelength. The threshold peak pump power absorbed by the cavity was estimated to be 12 μW.

39.8.2 Silicon Nanocrystals

Compatibility with CMOS materials have stimulated research on nanoscale silicon laser by Jaiswal and Norris [63]. They have theoretically analyzed and numerically simulated various designs based on photonic crystal concept and utilizing Si nanocrystals embedded in SiO_2. Their studies were motivated by observations of optical gain in silicon nanocrystals [64].

Pavesi et al. [64] observed light amplification in silicon itself. Silicon nanocrystals in the form of quantum dots were dispersed in a silicon dioxide matrix. Net optical gain was seen in both waveguide and transmission configurations, with the material gain being of the same order as that of direct band gap quantum dots. Their findings open the possibility for the fabrication of a silicon laser.

39.9 Scattering Lasers

In scattering lasers, the feedback is provided through scattering of light instead of a cavity [65]. These lasers are of two basic types: Mie lasers consisting of only one sphere and random lasers that are formed by many scattering particles. In Mie lasers, the surface of the sphere serves as multiple scatterer, while in random lasers, scattering is provided by randomly distributed particles.

In both types of scattering lasers, the average particle size used in typical experiments was about 5–10 μm [66,67]. They are, therefore, not of the size of true nanolasers.

39.9.1 Mie Nanolasers

In a Mie nanolaser, the mirrors of a conventional laser are replaced by the boundary of a microsphere. Light is multiply scattered at the boundary, and along the boundary, whispering gallery modes (WGMs) at a certain wavelength exist for specific sizes of the sphere.

WGMs occur at particular resonant wavelengths of light for a given droplet size (see Figure 39.21). At these wavelengths, the light undergoes total internal reflection at the particle surface and, after one roundtrip, interferes constructively. It becomes trapped within the particle for timescales of the order of nanoseconds.

The nomenclature of these modes derive from the observation of Lord Rayleigh in the dome in St. Paul's Cathedral in London. He observed sound ("whispers") propagating along the walls and circling around the dome several times.

Theoretical and experimental study of spherical resonators, which form the basis of Mie lasers, is still an open field of research. This interest stems from the analysis of fundamental processes such as scattering, energy propagation through disordered media, and cavity quantum electrodynamics, and from the large number of applications in photonics, chemistry, meteorology, astronomy, and sensing.

39.9.2 Random Lasers

In random lasers, the conventional optical cavity is replaced by light scattering from many particles. They do not have mirrors or optical elements.

In random lasers, the feedback is provided by multiple scattering of light at many scattering points. Random laser does not have a clear feedback mechanism like a conventional laser. It is nonresonant, even disordered and works in qualitatively different way than feedback by a resonant cavity (see [68] for a recent review). A comparison of conventional and random laser is shown in Figure 39.22. The wavelengths of random lasers span from the ultraviolet to the mid-infrared region. The materials used in random lasers include inorganic dielectrics, semiconductors, polymers, and liquids. The size of random lasers can vary from a cubic micrometer to hundreds of cubic millimeters.



FIGURE 39.21 Whispering gallery mode inside a microsphere.



FIGURE 39.22 Comparison of conventional and random laser. (Adapted from Wiersma, D., *Nature*, 406, 132, 2000.)

A short history of the development of random lasers is as follows:

- In 1968, Letokhov [69] described an idea of scattering with "negative absorption."
- In 1994, Lawandy et al. [70] conducted experiments on scatterers in laser dye and observed threshold and line narrowing.
- In 1995, Wiersma et al. [67] conducted multiple scattering experiments in Ti:Al_2O_3 random lasers.

Recently a definite reference on solid state random lasers was published by Noginov [71] who tried to answer the question of what is a random laser by reviewing many types of random lasers. On the theoretical side, we mention two approaches to describe scattering lasers [72,73].

Fratalocchi et al. [72] derived a 3D vector set of Maxwell–Bloch equations, which were solved numerically by employing FDTD method. They performed a series of numerical experiments by investigating the process of laser emission from a single nanosphere covered by a layer of active material for different pumping rates.

Novel theoretical approach to diffusive random lasers has recently been developed by Tuereci et al. [73]. They developed a model by considering all the possible ways in which light can reflect back and forth in the medium. In their approach, they considered coexistence of gain, nonlinear interactions, and overlapping resonances.

39.10 Organic Nanolasers

Ease of fabrication make organic materials attractive for various optoelectronic devices, including lasers. O'Carroll et al. [74] used the flexibility of structuring organic materials to fabricate subwavelength optical nanowire lasers.

Using a melt-assisted template wetting method, they synthesized arrays of semicrystalline nanowires with diameters in a range of 150–400 nm, and with typical length of ~6 μm. Their structures are cylindrical wires with optically flat end facets, which form optical cavities. Lasers were optically pumped by an external pump laser. The observed that lasing wavelength (about $\lambda = 460$ nm) was determined by a standard standing wave condition.

Organic lasers can potentially have various applications [75] as inexpensive and lightweight sources of coherent radiation.

39.11 Applications

To conclude this chapter, we briefly discuss a few recent applications of nanolasers focused on nanowire and photonic crystal-based devices.

39.11.1 Nanolaser Device Detects Cancer in Single Cells

Investigators at Sandia National Laboratories in New Mexico reported a method to rapidly detect cancer in a single cell using nanolaser techniques [76,77]. Their technique, which allows the investigator to distinguish between malignant and normal cells, has the potential of detecting cancer at a very early stage, a development that could change profoundly the way cancer is diagnosed and treated.

The method of determination of malignant cells is based on a technique that rapidly assesses the properties of cells flown through a nanolaser. They observed biophotonic differences in normal and cancer mouse liver cells by using intracellular mitochondria as biomarkers for disease. This difference arises from the fact that mitochondria, the internal organelles that produce energy in a cell, are scattered in a chaotic, unorganized manner in malignant cells, while they form organized networks in healthy cells. This difference produces a marked change in the way that malignant cells scatter laser light.

39.11.2 Biological and Chemical Detection

Optofluidic integration of a new type of photonic crystal nanolaser incorporated into a microfluidic chip was described by Kim et al. [78]. The proposed nanolasers are an ideal platform for high-fidelity biological and chemical detection tools in micro-total-analytical or lab-on-a-chip systems. Its operation is based on the wavelength tunability induced by the refractive index variation of the fluid.

A record high sensitivity utilizing photonic crystal nanolaser was recently reported by Kita et al. [79]. The index resolution limit of their sensor could be $<10^{-6}$.

39.11.3 Ultrahigh Data Storage

Ikkawi et al. [80] reported the development of a near-field optical system capable of focusing light into a spot with diameter of less than 30 nm. To fabricate this type of nanolaser, they deposited a 100 nm thick aluminum film on the emitting edge of a laser diode and then used a focused ion beam to etch various apertures into the film. Their nanolaser technique is capable of storing data beyond 10 Tbit/in^2.

39.12 Conclusions

In this chapter, we provided an introduction to the concept of nanolasers, which are considered to be applicable as main elements, among others, in nanoscale optoelectronics. We discussed numerous examples of recently developed nanolasers.

The field of nanolasers shows rapid progress both on the research side as well as in applications. Examples include nanowire lasers with diameters as small as 100 nm. They find applications in medicine and in biological and chemical sensing. There is no doubt that field of nanolasers is set for interesting research in future and that nanolaser devices will find new and yet unforeseen applications.

Acknowledgment

I would like to acknowledge the financial support provided by the Natural Science and Engineering Research Council of Canada (NSERC).

References

1. A. Yariv. *Quantum Electronics*, 3rd edn. Wiley, New York, 1989.
2. B. Mroziewicz, M. Bugajski, and W. Nakwaski. *Physics of Semiconductor Lasers*. Polish Scientific Publishers/North-Holland, Warszawa, Amsterdam, the Netherlands, 1991.
3. L.A. Coldren and S.W. Corzine. *Diode Lasers and Photonic Integrated Circuits*. Wiley, New York, 1995.
4. G.P. Agrawal and N.K. Dutta. *Semiconductor Lasers*, 2nd edn. Kluwer Academic Publishers, Boston, MA/Dordrecht, the Netherlands/London, U.K., 2000.
5. C.W. Wilmsen, H. Temkin, and L.A. Coldren, (eds.). *Vertical-Cavity Surface-Emitting Lasers*. Cambridge University Press, Cambridge, U.K., 1999.
6. R. Coccioli, M. Boroditsky, K.W. Kim, Y. Rahmat-Samii, and E. Yablonovitch. Smallest possible electromagnetic mode volume in a dielectric cavity. *IEE Proc. Optoelectron.*, 145:391–397, 1998.
7. C. Santori, D. Fattal, J. Vuckovic, G.S. Solomon, and Y. Yamamoto. Indistinguishable photons from a single-photon device. *Nature*, 419:594–597, 2002.
8. S. Strauf, K. Hennessy, M.T. Rakher, Y.-S. Choi, A. Badolato, L.C. Andreani, E.L. Hu, P.M. Petroff, and D. Bouwmeester. Self-tuned quantum dot gain in photonic crystal lasers. *Phys. Rev. Lett.*, 96:127404, 2006.
9. H. Yokoyama. Physics and device applications of optical microcavities. *Science*, 256:66–70, 1992.
10. E. Yablonovitch. Inhibited spontaneous emission in solid-state physics and electronics. *Phys. Rev. Lett.*, 58:2059–2062, 1987.
11. S. Noda. Seeking the ultimate nanolaser. *Science*, 314:260–261, 2006.
12. P.L. Gourley. Nanolasers. *Sci. Am.*, 278:56–61, 1998.
13. S.S. Mao. Nanolasers: Lasing from nanoscale quantum wires. *Int. J. Nanotechnol.*, 1:42–85, 2004.
14. S.-X. Qian, J. B. Snow, H.-M. Tzeng, and R.K. Chang. Lasing droplets: Highlighting the liquid–air interface by laser emission. *Science*, 231:486–488, 1986.

15. H.B. Lin, J.D. Eversole, and A.J. Campillo. Spectral properties of lasing microdroplets. *J. Opt. Soc. Am. B*, 9:43–50, 1992.
16. M. Cai, O. Painter, K.J. Vahala, and P.C. Sercel. Fiber-coupled microsphere laser. *Opt. Lett.*, 25:1430–1432, 2000.
17. M. Kuwata-Gonokami, K. Takeda, H. Yasuda, and K. Ema. Laser emission from dye-doped polystyrene microsphere. *Jpn. J. Appl. Phys. Lett.*, 2, 32:L99–L101, 1992.
18. B. Gayral, J.M. Gerard, A. Lemaitre, C. Dupuis, L. Manin, and J.L. Pelouardb. High-q wet-etched GaAs microdisks containing InAs quantum boxes. *Appl. Phys. Lett.*, 75:1908–1910, 1999.
19. S.L. McCall, A.F.J. Levi, R.E. Slusher, S.J. Pearton, and R.A. Logan. Whispering-gallery mode microdisk lasers. *Appl. Phys. Lett.*, 60:289–291, 1992.
20. N.B. Rex, R.K. Chang, and L.J. Guido. Threshold lowering in GaN micropillar lasers by means of spatially selective optical pumping. *IEEE Photon. Technol. Lett.*, 13:1–3, 2001.
21. J.L. Jewell, S.L. McCall, Y.H. Lee, A. Scherer, A.C. Gosasard, and J.H. English. Lasing characteristics of GaAs microresonators. *Appl. Phys. Lett.*, 54:1400–1402, 1989.
22. O. Painter, R.K. Lee, A. Scherer, A. Yariv, J.D. O'Brien, P.D. Dapkus, and I. Kim. Two-dimensional photonic band-gap defect mode laser. *Science*, 284:1819–1821, 1999.
23. H. Yan, J. Johnson, M. Law, R. He, K. Knutsen, J.R. McKinney, J. Pham, R. Saykally, and P. Yang. ZnO nanoribbon microcavity lasers. *Adv. Mater.*, 15:1907–1911, 2003.
24. M.H. Huang, S. Mao, H. Feick, H. Yan, Y. Wu, H. Kind, E. Weber, R. Russo, and P. Yang. Room-temperature ultraviolet nanowire nanolasers. *Science*, 292:1897–1899, 2001.
25. J.C. Johnson, H.-J. Choi, K.P. Knutsen, R.D. Schaller, P. Yang, and R.J. Saykally. Single gallium nitride nanowire lasers. *Nat. Mater.*, 1:106–110, 2002.
26. M.A. Zimmler, J. Bao, F. Capasso, S. Mller, and C. Ronning. Laser action in nanowires: Observation of the transition from amplified spontaneous emission to laser oscillation. *Appl. Phys. Lett.*, 93:051101, 2008.
27. L.J. Lauhon, M.S. Gudiksen, and C.M. Lieber. Semiconductor nanowire heterostructures. *Phil. Trans. R. Soc. Lond. A*, 362:1247–1260, 2004.
28. X. Duan, Y. Huang, R. Agarval, and C.M. Lieber. Single-nanowire electrically driven lasers. *Nature*, 421:241, 2003.
29. Y. Gu, I.L. Kuskovsky, M. Yin, S. O'Brien, and G.F. Neumark. Quantum confinement in ZnO nanorods. *Appl. Phys. Lett.*, 85:3833, 2004.
30. C.R. Pollock and M. Lipson. *Integrated Photonics*. Kluwer Academic Publishers, Boston, MA, 2003.
31. P.J. Pauzauskie, D.J. Sirbuly, and P. Yang. Semiconductor nanowire ring resonator laser. *Phys. Rev. Lett.*, 96:143903, 2006.
32. M. Bayer, T. Gutbrod, J.P. Reithmaier, and A. Forchel. Optical modes in photonic molecules. *Phys. Rev. Lett.*, 81:2582–2585, 1998.
33. A.V. Maslov and C.Z. Ning. Reflection of guided modes in a semiconductor nanowire laser. *Appl. Phys. Lett.*, 83:1237–1239, 2003.
34. A.V. Maslov, M.I. Bakunov, and C.Z. Ning. Distribution of optical emission between guided modes and free space in a semiconductor nanowire. *J. Appl. Phys.*, 99:024314, 2006.
35. A.V. Maslov and C.Z. Ning. Far-field emission of a semiconductor nanowire laser. *Opt. Lett.*, 29:572–574, 2004.
36. A.V. Maslov and C.Z. Ning. Modal gain in a semiconductor nanowire laser with anisotropic bandstructure. *IEEE J. Quantum Electron.*, 40:1389–1397, 2004.
37. A.V. Maslov and C.Z. Ning. Band structure and optical absorption of GaN nanowires grown along c axis. *Phys. Rev. B*, 72:125319, 2005.
38. L. Chen and E. Towe. Coupled optoelectronic modeling and simulation of nanowire lasers. *J. Appl. Phys.*, 100:044305, 2006.
39. J.W. Buck. *Fundamentals of Optical Fibers*, 2nd edn. Wiley-Interscience, Hoboken, NJ, 2004.
40. A.V. Maslov and C.Z. Ning. Metal-encased semiconductor nanowires as waveguides for ultra-small lasers. In *Conference on Lasers and Electro-Optics, CLEO*, 6–11 May 2007, Baltimore, MD, pp. 1–2, 2007.
41. M.T. Hill, Y.-S. Oei, B. Smalbrugge, Y. Zhu, T. De Vries, P.J. Van Veldhoven, F.W.M. Van Otten, T.J. Eijkemans, J.P. Turkiewicz, H. De Waardt, E.J. Geluk, S.-H. Kwon, Y.-H. Lee, R. Noetzel, and M. K. Smit. Lasing in metallic-coated nanocavities. *Nat. Photon.*, 1:589–594, 2007.
42. F. Qian, Y. Li, S. Gradecak, H.-G. Park, Y. Ding, Z.L. Wang, and C.M. Lieber. Multi-quantum-well nanowire heterostructures for wavelength-controlled lasers. *Nat. Mater.*, 7:701–706, 2008.
43. W.L. Barnes, A. Dereux, and T.W. Ebbesen. Surface plasmon subwavelength optics. *Nature*, 424:824–830, 2003.
44. M.L. Brongersma, J.W. Hartman, and H.A. Atwater. Electromagnetic energy transfer and switching in nanoparticle chain arrays below the diffraction limit. *Phys. Rev. B*, 62:R16358, 2000.
45. J.A. Dionne, L.A. Sweatlock, H.A. Atwater, and A. Polman. Plasmon slot waveguides: Towards chip-scale propagation with subwavelength-scale localization. *Phys. Rev. B*, 73:035407, 2006.
46. M. Dragoman and D. Dragoman. Plasmonics: Applications to nanoscale terahertz and optical devices. *Prog. Quantum Electron.*, 32:1–41, 2008.
47. S.A. Maier. Effective mode volume of nanoscale plasmon cavities. *Opt. Quantum Electron.*, 38:257–267, 2006.
48. F. Rana, C. Manolatou, and S.G. Johnson. Nanoscale semiconductor plasmon lasers. In *Conference on Lasers and Electro-Optics, CLEO*, 6–11 May 2007, Baltimore, MA, pp. 1–2, 2007.
49. C. Manolatou and F. Rana. Subwavelength nanopatch cavities for semiconductor plasmon lasers. *IEEE J. Quantum Electron.*, 44:435–447, 2008.
50. A.K. Sarychev and G. Tartakovsky. Magnetic plasmonic metamaterials in actively pumped host medium and plasmonic nanolaser. *Phys. Rev. B*, 75:085436, 2007.

51. A.K. Sarychev, A.A. Pukhov, and G. Tartakovsky. Metamaterial comprising plasmonic nanolaser. *PIERS Online*, 3:1264–1267, 2007.
52. J.N. Farahani, D.W. Pohl, H.-J. Eisler, and B. Hecht. Single quantum dot coupled to a scanning optical antenna: A tunable superemitter. *Phys. Rev. Lett.*, 95:017402, 2005.
53. A. Sundaramurthy, K.B. Crozier, G.S. Kino, D.P. Fromm, P.J. Schuck, and W.E. Moerner. Field enhancement and gap-dependent resonance in a system of two opposing tip-to-tip Au nanotriangles. *Phys. Rev. B*, 72:165409, 2005.
54. S.-W. Chang, C.-Y.A. Ni, and S.L. Chuang. Theory of bowtie plasmonic nanolaser. *Opt. Express*, 16:10580–10595, 2008.
55. I.E. Protsenko, A.V. Uskov, O.A. Zaimidoroga, V.N. Samoilov, and E.P. O'Reilly. Dipole nanolaser. *Phys. Rev. A*, 71:063812, 2005.
56. I.E. Protsenko, N.F. Starodubtsev, V.M. Rudoy, O.V. Dementieva, N.N. Naumov, O.A. Zaimidoroga, and V.N. Samoilov. Plasmon resonance, laser generation and photo-effect in thin heterogeneous layers and nanostructures. In V.V. Samartsev (ed.), *Photon Echo and Coherent Spectroscopy*, vol. 6181 of Proc. SPIE, Bellingham, WA, 2005, p. 618116.
57. K.J. Vahala. Optical microcavities. *Nature*, 424:839–846, 2003.
58. H.-G. Park, C.J. Barrelet, Y. Wu, B. Tian, F. Qian, and C.M. Lieber. A wavelength-selective photonic-crystal waveguide coupled to a nanowire light source. *Nat. Photon.*, 2008.
59. K. Nozaki, H. Watanabe, and T. Baba. Photonic crystal nanolaser monolithically integrated with passive waveguide for effective light extraction. *Appl. Phys. Lett.*, 92:021108, 2008.
60. T. Yoshie, M. Loncar, K. Okamoto, Y. Qiu, O.B. Shchekin, H. Chen, D.D. Deppe and A. Scherer. Photonic crystal nanocavities with quantum well or quantum dot active material. In A. Abidi, A. Scherer, and S.-Y. Lin (eds.), *Photonic Crystal Materials and Devices II*, vol. 5360 of Proc. SPIE, Bellingham, WA, 2004, pp. 16–23.
61. K. Nozaki, S. Kita, and T. Baba. Room temperature continuous wave operation and controlled spontaneous emission in ultrasmall photonic crystal nanolaser. *Opt. Express* 15:7506–7514, 2007.
62. T. Yang, A. Mock, J.D. OBrien, S. Lipson, and D.G. Deppe. Edge-emitting photonic crystal double-heterostructure nanocavity lasers with InAs quantum dot active material. *Opt. Lett.*, 32:1153–1155, 2007.
63. S.L. Jaiswal and P.M. Norris. Variations in a design for a nanoscale silicon laser. In P.V. Farrell, F.-P. Chiang, C.R. Mercer, and G. Shen (eds.), *Optical Diagnostics for Fluids Solids, and Combustion II*, vol. 5191 of Proc. SPIE, Bellingham, WA, 2003, pp. 226–233.
64. L. Pavesi, L. Dal Negro, C. Mazzolenim, G. Franzo, and F. Priolo. Optical gain in silicon nanocrystals. *Nature*, 408:440–444, 2000.
65. K.L. van der Molen. Experiments on scattering lasers from Mie to random. PhD thesis, University of Twente, 2007.
66. K.L. van der Molen, P. Zijlstra, A. Lagendijk, and A.P. Mosk. Laser threshold of Mie resonances. *Opt. Lett.*, 31:1432–1434, 2006.
67. D.S. Wiersma, M.P. van Albada, and A. Lagendijk. Coherent backscattering of light from amplifying random media. *Phys. Rev. Lett.*, 75:1739–1743, 1995.
68. D. Wiersma. The physics and applications of random lasers. *Nat. Phys.*, 4:359–367, 2008.
69. V.S. Letokhov. Generation of light by a scattering medium with negative resonance absorption. *Sov. Phys. JETP*, 26:835 840, 1968.
70. N.M. Lawandy, R.M. Balachandran, A.S.L. Gomes, and E. Sauvain. Laser action in strongly scattering media. *Nature*, 368:436–438, 1994.
71. M. Noginov. *Solid-State Random Lasers*. Springer-Verlag, New York, 2005.
72. A. Fratalocchi, C. Conti, and G. Ruocco. Mode competitions and dynamical frequency pulling in Mie nanolasers: 3D ab-initio Maxwell-Bloch computations. *Opt. Express* 16:8342–8349, 2008.
73. H.E. Tuereci, L. Ge, S. Rotter, and A.D. Stone. Strong interactions in multimode random lasers. *Science*, 320:643–646, 2008.
74. D. O'Carroll, I. Lieberwirth, and G. Redmond. Microcavity effects and optically pumped lasing in single conjugated polymer nanowires. *Nat. Nanotechnol.*, 2:180–184, 2007.
75. R.J. Holmes. Nanowire lasers go organic. *Nat. Nanotechnol.*, 2:141–142, 2007.
76. P.L. Gourley, J.K. Hendricks, A.E. McDonald, R.G. Copeland, K.E. Barrett, C.R. Gourley, and R.K. Naviaux. Ultrafast nanolaser flow device for detecting cancer in single cells. *Biomed Microdevices*, 7:331–9, 2005.
77. P.L. Gourley and R.K. Naviaux. Optical phenotyping of human mitochondria in a biocavity laser. *IEEE J. Sel. Top. Quantum Electron.*, 11:818–826, 2005.
78. S.-H. Kim, J.-H. Choi, S.-K. Lee, S.H. Kim, S.-M. Yang, Y.-H. Lee, C. Seassal, P. Regrency and P. Viktorovitch. Optofluidic integration of a photonic crystal nanolaser. *Opt. Express*, 16:6515–6527, 2008.
79. S. Kita, K. Nozaki, and T. Baba. Refractive index sensing utilizing cw photonic crystal nanolaser and its arrayed configuration. In *OSA/CLEO/QELS*, San Jose, CA, page paper CM06, 2008.
80. R. Ikkawi, N. Amos, A. Krichevsky, R. Chomko, D. Litvinov, and S. Khizroev. Nanolasers to enable data storage beyond 10 tbit/in^2. *Appl. Phys. Lett.*, 91:153115, 2007.
81. Y. Arakawa and H. Sakaki. Multidimensional quantum well laser and temperature dependence of its threshold current. *Appl. Phys. Lett.*, 40:939–941, 1982.
82. M. Asada, Y. Miyamoto, and Y. Suematsu. Gain and the threshold of three-dimensional quantum-box lasers. *IEEE J. Quantum Electron.*, 22:1915–1921, 1986.
83. F. Qian, S. Gradecak, Y. Li, C.-Y. Wen, and C.M. Lieber. Core/multishell nanowire heterostructures as multicolor, high-efficiency light-emitting diodes. *Nano Lett.*, 5:2287–2291, 2005.
84. D. Wiersma. The smallest random laser. *Nature*, 406:132–133, 2000.
85. P.J. Pauzauskie and P.D. Yang. Nanowire photonics. *Mater. Today*, 9:36–45, 2006.

40

Quantum Dot Laser

40.1 Introduction 40-1
Material Systems • Edge Emitter Laser Diodes
40.2 Electronic States of Quantum Dots 40-4
Localized and Delocalized States in Self-Assembled Structures • Envelope-Function Approximation and Effective-Mass Approach • Continuum Approaches and Atomistic Models
40.3 Scattering Processes of Carriers in Quantum Dots 40-5
Carrier–Carrier Interaction • Carrier–Phonon Interaction
40.4 Optical Gain of the Active Material 40-10
Optical Susceptibility • Interband Transitions and Macroscopic Polarization • Optical Gain Calculations • Gain Saturation, Refractive Index, and α-Factor
40.5 Laser Emission Properties 40-13
Rate Equations for Quantum-Dot Systems • Microscopic Generalization: Semiconductor Effects • Quantum-Dot Microcavity Lasers: Modifications of the Photon Statistics
Acknowledgments 40-16
References 40-16

Frank Jahnke
University of Bremen

40.1 Introduction

The success of optoelectronics is largely based on the availability of efficient and reliable semiconductor lasers. Most prominent among the many applications are optical data storage solutions on CDs, DVDs, and BDs or the fiber-based optical communication. The initial success started with conventional laser diodes (Casey and Panish, 1978a,b; Agrawal and Dutta, 1993; Chuang, 1995). More recent microcavity lasers (Li and Iga, 2003) provide a new level of miniaturization and novel emission properties.

In general, the laser emission is based on population inversion of the electronic states, which contribute to the radiative recombination. For semiconductor lasers, it has been realized early (Dingle and Henry, 1976) that the carrier confinement in quantum wells leads to improved laser properties, like a laser threshold reduction. The successful demonstration of this effect was based on advances in the material growth (Tsang, 1982). The use of quantum dots (QDs) as an active material promises even greater benefits. First of all, one gains more freedom to engineer the emission wavelength (Bimberg et al., 1999). Another advantage is the enhancement of the single-particle density of states. For states experiencing a carrier confinement in all three dimensions, discrete electronic energies similar to the spectrum of atomic systems are obtained. This has led to predictions of further increased efficiency for laser applications, which are based on less temperature-dependent operational parameters (Arakawa and Sakaki, 1982), further reduced threshold currents and higher differential gain (Asada et al., 1986), higher modulation bandwidth (Kim et al., 2004) and reduced anti-guiding effects (Newell et al., 1999), as well as a reduced sensitivity to material defects. Also, the miniaturization of the active material in connection with new microcavity laser resonators opens the door for novel applications in quantum information technologies.

The goal of this chapter is to provide an introduction to the physics underlying QD lasers. We will discuss the fundamental properties of the QDs, which are relevant for laser applications, as well as the important interaction processes that determine the laser properties.

40.1.1 Material Systems

Various techniques can be employed for the fabrication of QDs. Each approach has advantages for particular applications. Self-assembled QDs, which are typically obtained in the Stranski–Krastanov growth mode, are the most widely used for optoelectronic devices. Colloidal semiconductor nanostructures, which can be functionalized as biological markers, are less practical for the device integration. Lateral QDs, which are fabricated by etching of quantum wells following electron beam lithography, have the advantage of better controllable size and position. They are favorable for quantum-transport studies. The slow preparation process, the low dot density, and defect formation prevent the broad use of this method in optoelectronics.

For emission in the near infrared and red, including the frequencies for optical fiber telecommunication networks at 1300 and 1500 nm, the GaAs material system (GaAs/AlGaAs, InGaAs/GaAs) is routinely used. The self-organized growth of QDs is well established for this material system. The fabrication starts with the strained growth of a two-dimensional wetting layer (WL) on a substrate with a higher band gap and lower lattice constant. After a critical thickness is reached, partial strain relaxation changes the morphology to a thinner two-dimensional layer and small three-dimensional islands. These islands constitute the self-assembled QDs after their overgrowth with a higher band-gap material.

II–VI compounds with a wider band gap like CdSe, CdTe, or ZnSe provide emission in the green and yellow spectral range (Klude et al., 2004; Sebald et al., 2009). However, issues of the device lifetime due to degradation effects have so far prevented the broad application in light emitting devices. Also the growth mechanism often differs from that in III–V compounds. For example, CdTe/ZnTe has a similar lattice mismatch to InAs/GaAs, but the growth of CdTe QDs starts with two-dimensional platelets on which small dots are formed. Isolated dots are growing, when the material thickness exceeds a critical value.

The group-III nitride material system, like GaN/AlN or InGaN/GaN, received much attention for applications in light emitters due to their extended range of emission frequencies from visible light to UV emission (Nakamura and Chichibu, 2000). While the nonradiative loss of carriers due to trapping at threading dislocations lowers the efficiency of group-III quantum-well light emitters, this effect is reduced by the three-dimensional carrier confinement in QDs. Nitride-based heterostructures with a wurtzite crystal structure are known to have built-in electrostatic fields due to the spontaneous polarization and piezoelectric effects, which lower the spatial overlap of the electron and hole wave functions thereby reducing the interband recombination efficiency.

40.1.2 Edge Emitter Laser Diodes

Two different types of semiconductor lasers need to be distinguished in general. They vary in design, properties, and applications. In conventional edge-emitting laser diodes, the feedback for the laser mode is provided by an optical cavity, which is formed by the cleaved end faces of the device (Agrawal and Dutta, 1993; Chuang, 1995). Correspondingly, the emission occurs from the edge of the semiconductor chip. The low mirror reflectivity due to the jump of the refractive index from the semiconductor material to air results in a short cavity lifetime (large cavity damping). To compensate for the cavity losses, a large propagation length of the laser mode through the active material is necessary. The large cavity length in the range of a few hundred micrometers in turn leads to a small frequency spacing between the cavity modes, so that many modes appear within the gain region of the active material. As a result, edge emitters typically operate multimode. Also the spontaneous emission of the active material is distributed over a large number of nonlasing modes, which leads to a pronounced laser threshold as discussed in Section 40.5.



FIGURE 40.1 Edge-emitting laser (left) and vertical-cavity surface-emitting laser (right) with active region (A), waveguide layers (W), upper and lower Bragg mirrors (B), contacts (C), and light output (O). The arrows indicate the direction of the current flow.

The optical gain is achieved by current-injection pumping of the active material. For an edge-emitting laser diode, it is outlined in Figure 40.1 that the electrical injection current flows perpendicular to the optical cavity modes and the emission direction, which is characteristic for this type of devices. To provide an efficient confinement of the pumped charge carriers to the active region, a heterostructure design is used, where the active layer is positioned between materials with wider band gaps. A common heterostructure has a GaAs active layer between AlGaAs barriers. The carrier confinement is increased by designing the laser structure to be very thin in the direction of current flow, which is also the epitaxial growth direction. Additional cladding layers can be used to confine the optical mode in the transverse direction by means of a waveguide geometry and to increase the spatial overlap of the optical mode with the active region. Such a design is called double heterostructure and was independently proposed by Kroemer as well as Alferov and Kazarinov (Casey and Panish, 1978a). The conventional laser configuration works very well, as is evident from its wide ranging applications in many electro-optical systems.

This design allows for a natural integration of self-organized QDs as active material. Since the dots are grown in layers, these can serve as the planes in which the optical mode propagates. To increase the modal gain, often several layers are staggered. Accompanied with the large number of QDs and unavoidable fluctuations of the individual QD properties (mostly geometry and composition) is a large inhomogeneous broadening of the emission spectrum of the active material.

On the other hand, the combination of edge emission and active layer shape give rise to several disadvantages (independent on whether quantum wells or QDs are used as active material). For edge emission, the laser transverse and lateral modes depend on the cross section of the gain region, which is very thin in the transverse dimension for carrier confinement and wide in the lateral dimension for output power. The resulting near field of the laser emission is highly elongated, which does not match well to the circular cross section of optical fibers for possible out-coupling. Since the transverse beam dimension is very small, typically of the order of 1 μm or less, the transverse beam divergence is rather high (typically ≈50° full angle) because of diffraction. Therefore, the far field of the laser emission is also highly elongated. The beam astigmatism together with the high divergence makes design and fabrication of coupling optics rather challenging. Approaches to single-mode operation involve embedded gratings or buried heterostructures, which increase the unit costs and limit the output power.

40.1.2.1 Microcavity Lasers

Microcavity lasers represent a new type of devices. In analogy to the carrier confinement, one utilizes a strong confinement of the electromagnetic field. Cavity dimensions of the order of the light wavelength are characteristic of microcavity lasers. Due to the strongly reduced gain length, this requires very high mirror reflectivities larger 99%. To characterize microresonators, one uses the cavity quality factor $Q = \omega_c/\Delta\omega_c$ with the cavity frequency ω_c and the spectral linewidth $\Delta\omega_c$. The combination of small mode volume and high Q-factor leads to modifications in the density of states of the electromagnetic field. According to Fermi's golden rule, this allows to enhance or inhibit the spontaneous recombination probability, which is known as Purcell effect (Vahala, 2003; Lodahl et al., 2004). Particularly important for lasers is that the small cavity dimensions strongly increase the frequency spacing between the cavity modes. Microcavity lasers can be designed in a way to find only a single high-Q cavity mode within the gain spectrum of the active material, thus allowing genuine single-mode laser operation. The Purcell effect can also be used to suppress the spontaneous emission into other low-Q modes (e.g., modes propagating in other directions). This leads to a strongly reduced laser threshold, and the possibility of thresholdless lasers has been discussed (Yokoyama and Brorson, 1989; Rice and Carmichael, 1994) as a consequence of the novel physics.

The foundation of microcavity lasers lies in the improved engineering of optical resonators in combination with the new physics in the field of cavity-quantum electrodynamics. This includes mastering Maxwell's equations in even more and more complicated materials and geometries and still being able to predict the electromagnetic properties and the response of devices. The photon confinement is based either on Bragg or total internal reflection. A central role plays the concept of photonic bandgap materials. Here, one uses the analogy to the electronic band structure, which emerges for the electron motion in a lattice periodic potential. Photonic structures with periodic modulations of the refractive index can be designed in a way that a photonic band gap for the light propagation, the so-called stop band appears.

For practical device applications, vertical-cavity surface-emitting lasers (VCSELs) are frequently used, since many of the above mentioned disadvantages of the edge-emitting design are avoided. The VCSEL constitutes of a Fabry-Perot resonator, in which the very high reflectivity is achieved with distributed Bragg reflectors (DBRs), consisting of epitaxially grown periodic layers of different refractive indices (Jewell et al., 1991). The typical DBR has alternating layers that are each λ/4 thick so as to provide constructive interference of the reflected waves from each interface. The spacer layer between the DBRs acts as a defect giving rise to the high-Q cavity mode, which provides the photon confinement.

The basic VCSEL structure is that of an effectively one-dimensional resonator with a length of a few μm. The active region between the mirrors consists either of one or a few quantum wells or layers with QDs, which are embedded between cladding layers. The short cavity length of this structure allows to design a single high-Q (longitudinal) cavity mode within the spectral gain region of the active material. For laser structures, current confinement to a small area of the active region has been introduced by means of oxide apertures.

Since the optical cavity axis is in the vertical (epitaxial growth) direction (see Figure 40.1), the laser emission for a VCSEL occurs out of the surface of the wafer. This surface emitting configuration has several desirable features. Being independent of the gain layer cross section, there is more flexibility in the shape and size of the transverse optical mode. In particular, a circular beam can be realized. With an approximately 6 μm diameter circular output aperture, lowest order (Gaussian-like) transverse mode operation with less than 10° beam divergence is possible (Chang-Hasnain et al., 1991). Other advantages of a VCSEL are even more practical in nature. Unlike an edge-emitter, the VCSEL mirrors are fabricated during the epitaxial growth of the entire wafer, so that the mirrors of hundreds of lasers can be manufactured simultaneously. Edge emitters can only be combined to one-dimensional laser arrays, whereas with surface emitters truly two-dimensional arrays are routinely possible. To test an edge emitter, one needs to expose the edges, which means cleaving the wafer and applying the necessary facet preparations. These are time consuming and therefore costly steps that have to be repeated for each laser diode. Surface emitters can be fabricated, tested, and operated at the wafer level.

The VCSEL design has its own challenges. This gain-length reduction has to be compensated by the high cavity Q, putting great demands on the quality of the DBR mirrors. Having only one high-Q cavity resonance in the spectral gain region, the laser threshold current is very sensitive to the position of this resonance in relation to the peak of the material gain spectrum. From this, a related complication arises: the cavity-gain alignment can be maintained typically only within a small temperature range, because gain spectrum and cavity resonances have different temperature dependences. The gain spectrum shifts in frequency because of the temperature dependence of the bandgap energy and the carrier distributions. The cavity resonances shift with temperature due to thermally-induced changes in the refractive indices of the mirror material and the material within the optical cavity. The result is a temperature dependence of the cavity-gain alignment, which plays an important role in the sensitivity of a VCSEL output to temperature variations.

An additional transverse mode confinement in VCSEL structures can be introduced with the fabrication of micropillars, e.g., due to a combination of electron-beam lithography and various etching methods. The resulting three-dimensional confinement of the optical mode to a very small volume of the order of the cubic light wavelength strongly increases the efficiency of the light–matter interaction. With the three-dimensional photon confinement, the Purcell effect can be used for a strong suppression of the spontaneous emission into non-lasing modes. Even higher cavity-*Q* factors for three-dimensional mode confinement have been achieved in microdisks or microspheres. They lack, however, the directionality of the light emission. The ultimate control of the photon confinement and record values for the cavity-*Q* has been possible in photonic crystal structures.

Both in conventional edge-emitters and in microcavity lasers, the QD physics that determines the properties of the gain material is the same and the effects discussed in the subsequent chapters equally apply. Nonetheless, the miniaturization of microcavity lasers can be pushed to the extreme case where only a single QD resonantly interacts with a single high-*Q* optical mode. This system is the analogous to the single-atom micromaser or the one-atom laser of quantum optics and opens the door for novel applications in quantum-information technologies like quantum cryptography (Fattal et al., 2004) and quantum computers (Scholz et al., 2006). Essential physical effects or mechanisms are the generation of single-photons on demand (Michler et al., 2000) or correlated photons (Moreau et al., 2001), as well as the demonstration of vacuum field Rabi oscillations (strong coupling) (Reithmaier et al., 2004; Yoshie et al., 2004).

40.2 Electronic States of Quantum Dots

The single-particle states will be taken as the starting point for the description of the electronic and optical properties of semiconductor QDs as active material in lasers. In terms of quantum mechanics, single-particle states constitute the basis for the analysis of interaction processes. Interaction matrix elements can be formulated with the corresponding wave functions, and transition processes can be described in terms of the single-particle states.

40.2.1 Localized and Delocalized States in Self-Assembled Structures

Due to the three-dimensional carrier confinement, QDs possess localized states in contrast to the band structure of the bulk material. Nevertheless, the single-particle states are closely related to the properties of the bulk material. Especially the optical selection rules and symmetry properties of the interaction matrix elements reflect properties of the underlying crystal lattice. Also band mixing effects and built-in crystal fields are results of the lattice properties.

Depending on material composition and growth conditions like temperature and material flux, a variety of different QD geometries can be fabricated (Jacobi, 2003). In the following, we consider self-assembled QD systems in a characteristic geometry, which consist of lens-shaped caps positioned on a residual two-dimensional WL, as shown in the left part of Figure 40.2. For the frequently used InGaAs/GaAs material system, one finds typically a diameter of 10–30 nm and a height-to-diameter aspect ratio of 0.3–0.4. The random distribution of QDs on the WL plane has a density of 10^{10}–10^{11} cm^{-2}.

From the geometry of the QD-islands on top of the two-dimensional WL, the single-particle energy spectrum can be understood qualitatively. The WL provides a confinement of carriers in the growth direction and—in the absence of QDs—a free carrier motion in the perpendicular WL plane, as in a quantum well. At the position of the islands, the height of the lower band-gap material increases, thus reducing the ground-state energy and therefore giving rise to an additional in-plane confinement potential. The resulting effective three-dimensional carrier confinement in the QDs leads to a localized state with discrete energies for electrons and holes. These discrete states are located energetically below a quasi-continuum of delocalized states, corresponding to the two-dimensional motion of carriers in the WL. At even higher energies, one finds the barrier states, which are delocalized in all three dimensions. The energy levels of the combined QD-WL system are sketched in the right part of Figure 40.2. The actual number of discrete QD states is limited by the height of the confinement potential as



FIGURE 40.2 Cross section (a) and top view (b) TEM image of self-assembled InGaAs/GaAs QDs. The corresponding energy spectrum (c) contains localized states due to the three-dimensional carrier confinement, which are positioned energetically below a quasi-continuum of delocalized states corresponding to the two-dimensional motion of carriers in the WL. (From Anders, S. et al., *Phys. Rev. B*, 66, 125309, 2002.)

well as the geometry of the dots. As we will discuss in Section 40.3, the delocalized states play an important role for the scattering processes in light-emitters based on QDs and, hence, need to be included in the analysis of the single-particle states.

40.2.2 Envelope-Function Approximation and Effective-Mass Approach

The simplest approach to the carrier confinement in semiconductors is based on the envelope-function approximation. The starting point is the Bloch theorem, which represents the wave functions in a three-dimensional crystal in the form

$$\Phi_{\boldsymbol{k}}(\boldsymbol{r}) = e^{i\boldsymbol{k}\cdot\boldsymbol{r}}u_{\lambda}(\boldsymbol{r}), \tag{40.1}$$

describing plane waves modulated with the lattice-periodic Bloch function $u_{\lambda}(\boldsymbol{r})$, where λ is the band index and $\boldsymbol{k}$ is the carrier wave vector. In a confinement situation, one assumes that the three-dimensional plane wave can be replaced with envelope wave functions that are localized in one, two, or three dimensions.

In effective-mass approximation, one assumes that the actual QD and the two-dimensional WL consist of the same semiconductor material, in which the carrier motion experiences a constant potential energy and a kinetic energy of the carriers that can be expressed in terms of an effective mass m^*. The structure is embedded in a buffer material with a larger band gap. This is described by a step-wise increase of the confinement potential $V(\boldsymbol{r})$ to the outside region. Typically, the effective mass is also different in the buffer material, which is expressed with a step-wise constant $m^*(\boldsymbol{r})$. The Schrödinger equation

$$\left[\frac{\hbar^2}{2m^*(\boldsymbol{r})}\Delta + V(\boldsymbol{r})\right]\phi_n(\boldsymbol{r}) = \varepsilon_n\phi_n(\boldsymbol{r}) \tag{40.2}$$

defines the confinement wave functions $\phi_n(\boldsymbol{r})$, which replace the plane waves in Equation 40.1, and provides the corresponding energies ε_n for the single-particle states.

For the geometry displayed in the left part of Figure 40.2, several simplifications of the solution of Equation 40.2 are possible. The rotational symmetry allows for a classification of the single-particle states according to their angular momentum and to effectively reduce the three-dimensional problem to a two-dimensional one. Details for the solution of this problem are discussed in Wojs et al. (1996). Additionally, when the QD height-to-diameter aspect ratio is small, one can distinguish a weak (strong) confinement situation in the WL plane (growth direction), and in good approximation the confinement wave function can be separated into the corresponding components

$$\Phi_n(\boldsymbol{r}) = \varphi_{l,\lambda}(\varrho)\xi_{\sigma,\lambda}(z)u_{\lambda}(\boldsymbol{r}), \tag{40.3}$$

with $\boldsymbol{r} = (\varrho, z)$. The in-plane envelope function $\varphi_{l,\lambda}(\varrho)$ represents both localized and delocalized states for the QD and WL contributions, respectively. In a simple but often useful approximation, the in-plane confinement of flat QDs with cylindrical symmetry is described by a two-dimensional harmonic confinement potential with a characteristic equidistant spacing of the corresponding energies (Wojs et al., 1996). In the WL, the in-plane momentum $\boldsymbol{k}$ is a good quantum number if the effect of the localized states on the continuum is neglected. Thus, the quasi-continuum of the WL states (in the absence of QDs) is modeled by using plane waves for the corresponding in-plane envelope functions $\varphi_{l,\lambda}(\varrho)$. However, the localized QD states and the delocalized WL states are solutions of a single-particle problem for one common confinement potential and must, therefore, form an orthogonal basis. By performing a separate ansatz for the QD and WL contributions, this orthogonality is not ensured. It can be enforced, for example, by an orthogonalization procedure of the continuum states. The obtained so-called orthogonal plane waves (OPWs) represent a more correct description of the WL states. For details, we refer the reader to Nielsen et al. (2004, 2005).

40.2.3 Continuum Approaches and Atomistic Models

The effective-mass approach has several shortcomings. Band-mixing effects usually modify the electronic states, and a more detailed description of the valence-band structure is often desired. This can be included in semiempirical continuum approaches like $k\cdot p$-models or atomistic tight-binding approaches. The latter account also for symmetry properties of the atoms in the crystal unit cell, which can influence optical transition rules, and allows to study systematically the combined influence of structure and chemical morphology including alloy fluctuations and defects.

These effects are particularly important in nitride-based heterostructures, and for these systems extensive studies of the electronic states have been performed. The valence band of a wurtzite nitride semiconductor is strongly nonparabolic due to the small spin–orbit and crystal-field splitting (Chuang and Chang, 1996; Vurgaftman and Meyer, 2003). The hexagonal symmetry of the crystal leads to the subbands having the same effective mass along the *c*-axis. Therefore, the confinement of the holes in this direction due to the WL is not able to separate these subbands, and strong subband mixing, and nonparabolicity effects remain present. Also modifications of the wave functions due to built-in fields and their screening due to excited carriers are important.

First-principle calculations are available for the computation of the electronic structure of small QD systems (200–400 atoms). Due to the large number of atoms together with the absence of translational symmetry, which greatly simplifies bulk calculations, density functional theory-based approaches are computationally too demanding to date.

40.3 Scattering Processes of Carriers in Quantum Dots

To utilize the specific optical properties of QDs, we are interested in recombination processes between the conduction and valence band states associated with the three-dimensional carrier confinement. Efficient light emitters like LEDs rely on a large



FIGURE 40.3 Fundamental carrier scattering processes in QD-based light emitters.

population of the QD states with electrons and holes. For laser applications, the realization of optical gain even requires population inversion. Electrical current injection leads to the generation of carriers in the delocalized states. These carriers need to be scattered into the localized QD states (carrier capture). Also efficient carrier scattering between the QD states (carrier relaxation) is necessary to obtain a large ground-state population. The corresponding transition processes are schematically shown in Figure 40.3. Likewise, optically pumped QD lasers depend on fast carrier-scattering processes. The two important intrinsic scattering mechanisms contributing to the capture and relaxation are the carrier–carrier Coulomb interaction, which can be assisted by carriers in bound (QD) or extended (WL) states, and the carrier–phonon interaction. Both mechanisms are discussed separately in Sections 40.3.1 and 40.3.2. These scattering processes are also an important source for optical dephasing, which strongly influences the optical properties. Furthermore, this underscores the integral part the WL states play for the physics and application of self-assembled QDs.

Experimental insight into carrier scattering processes can be obtained by ultrafast optical pump–probe spectroscopy, ranging from absorption measurements to advanced two-color pump–probe and four-wave mixing experiments (Shah, 1999). Both at room temperature and at lower temperatures, efficient carrier scattering processes have been demonstrated.

40.3.1 Carrier–Carrier Interaction

The most simple and at the same time most efficient form of carrier–carrier collisions involves the energy transfer between two particles. To analyze the corresponding re-distribution of the carrier population within a quantum-statistical treatment, one can investigate the dynamics of the carrier population $f_\nu(t)$ for the state ν as a function of time t. The corresponding equation of motion for $f_\nu(t)$ can be formulated on different levels of refinement. Frequently used are kinetic equations with Boltzmann scattering rates, which describe the temporal change of the carrier population $f_\nu(t)$ due to various scattering processes into and out of the states ν according to

$$\frac{\partial}{\partial t} f_\nu = (1 - f_\nu) S_\nu^{\text{in}} - f_\nu S_\nu^{\text{out}}. \tag{40.4}$$

To obtain this form, a Markov approximation has been used, where one assumes that the population changes at a given time t depend explicitly only on the population functions $f_\nu(t)$ at the same time. Generally, the scattering rates are proportional to the population f of the initial states and to the nonoccupation $1 - f$ of the final states. Correspondingly, on the RHS of Equation 40.4, the in-scattering (out-scattering) rate, which increases (decreases) the population, is proportional to the non-occupation probability $1 - f_\nu$ (occupation probability f_ν).

For the Coulomb interaction, where two carriers are scattered from the states ν_1 and ν_3 into ν and ν_2 and vice versa, the scattering integral S_ν^{in} is given by

$$S_\nu^{\text{in}} = \frac{2\pi}{\hbar} \sum_{\nu_1, \nu_2, \nu_3} W_{\nu\nu_2\nu_3\nu_1} [W^{\star}_{\nu_2\nu_3\nu_1} \quad - W^{\star}_{\nu\nu_2\nu_1\nu_3}\ ]$$
$$\times f_{\nu_1}(1 - f_{\nu_2}) f_{\nu_3} \delta(\tilde{\varepsilon}_\nu - \tilde{\varepsilon}_{\nu_1} + \tilde{\varepsilon}_{\nu_2} - \tilde{\varepsilon}_{\nu_3}). \tag{40.5}$$

A similar expression for the out-scattering contribution S_ν^{out} is obtained by replacing $f \to 1 - f$. The population factors account for the availability of scattering partners, as discussed above. The sum involves all available initial states for in-scattering processes as well as all possible scattering partners that can be provided in QD or WL states.

In Markov approximation, the delta function accounts for strict energy conservation of the scattering processes. This approximation is valid in the long time limit, where scattering events are considered for times that are much larger than the inverse scattering rates. Even in this case, it is necessary to account for renormalizations of the single-particle energies $\tilde{\varepsilon}_\nu$ by the Coulomb interaction instead of using free-carrier energies ε_ν as done in the perturbation theory.

The scattering cross section is also determined by the matrix elements of the screened Coulomb interaction $W_{\nu\nu_2\nu_3\nu_1}$. The first and second terms in the square brackets correspond to direct and exchange Coulomb scattering, respectively.

A treatment beyond the Markov approximation is possible within a quantum-kinetic description (Haug and Jauho, 1996). Then the delta-function is replaced by the spectral functions of the involved carriers, and time-integrals over the past of the system account for memory effects. The most simple form of a quantum-kinetic equation requires two further approximations: (1) Within the generalized Kadanoff–Baym ansatz (GKBA), closed equations for single-time population functions are obtained (see Haug and Jauho, 1996 for detailed discussions). (2) The quasiparticle properties of the involved carriers are described by renormalized energies and damping (finite lifetime of the quasiparticle state), which can be summarized in complex energies $\hat{\varepsilon}_\nu$. The latter approximation is related to the Fermi liquid theory



FIGURE 40.4 Capture times for electrons (a) and holes (b) and relaxation times for electrons (c) and holes (d) as a function of the total carrier density in the system N_{sys} for the following quantum-dot states of an InGaN/GaN material system and room temperature: s-shell (solid lines), p-shell (dotted lines), d_0-shell (dashed-dotted lines), and $d_{\pm}$-shell (dashed lines). (From Nielsen, T.R. et al., *Phys. Rev. B*, 72, 235311, 2005. With permission.)

and valid for large carrier densities, where excitonic effects can be neglected. The quantum-kinetic equation with the discussed approximations has the form

$$\frac{\partial}{\partial t} f_\nu(t) = \int_{-\infty}^{t} dt' \left\{[1-f_\nu(t')]S_\nu^{\text{in}}(t,t') - f_\nu(t')S_\nu^{\text{out}}(t,t')\right\}, \quad (40.6)$$

where the in-scattering rate, which now depends on two time arguments, is given by

$$\begin{aligned} S_\nu^{\text{in}}(t,t') = \frac{1}{\hbar^2}\text{Re}\sum_{\nu_1,\nu_2,\nu_3} & W_{\nu\nu_2\nu_3\nu_1}(t)\left[W^{\star}_{\nu\nu_2\nu_3\nu_1}(t') - W^{\star}_{\nu\nu_2\nu_1\nu_3}(t')\right] \\ & \times f_{\nu_1}(t')\left[1-f_{\nu_2}(t')\right]f_{\nu_3}(t') \\ & \times \exp\left(-\frac{i}{\hbar}(\hat{\varepsilon}_\nu - \hat{\varepsilon}_{\nu_1} + \hat{\varepsilon}_{\nu_2} - \hat{\varepsilon}_{\nu_3}(t-t')\right). \qquad (40.7) \end{aligned}$$

The out-scattering rate is again obtained from $f \rightarrow 1-f$. It turns out, that especially for the calculation of dephasing and its influence on optical absorption and gain spectra, the quantum-kinetic description leads to more realistic results. As discussed in Lorke et al. (2006a), for the description of dephasing in optical spectra, equations similar to (40.6) and (40.7) are used for the polarization dynamics, which will be discussed in Section 40.4.3.

The results for the capture of carriers from the WL into the QD states and for the relaxation between the QD levels are shown in Figure 40.4. Capture and relaxations times have been defined as those times τ_ν, in which the system returns to thermal equilibrium due to the respective processes after a small perturbation. In relaxation-time approximation, one finds $1/\tau_\nu = S_\nu^{\text{in}} + S_\nu^{\text{out}}$, where the scattering rates are evaluated for quasi-equilibrium population functions. With increasing carrier density in the system, the scattering times are decreasing due to the larger number of available scattering partners. For the energetically lower s-shell, direct carrier capture from the WL is less efficient than capture into the p-shell and subsequent relaxation into the s-shell. For further details, we refer the reader to Nielsen et al. (2005).

In the following, we provide additional information on the analysis of carrier–carrier scattering processes. The determination of the Coulomb interaction matrix elements, which enter in Equations 40.5 and 40.7, involves two steps. The bare (unscreened) interaction matrix elements can be calculated from the single-particle wavefunctions $\Phi_\nu(\mathbf{r})$, see Section 40.2, of the involved electronic states according to

$$V_{\nu\nu_2\nu_3\nu_1} = \int d^3r d^3r' \Phi_\nu^{\star}(\mathbf{r})\Phi_{\nu_2}^{\star}(\mathbf{r}')v(\mathbf{r}-\mathbf{r}')\Phi_{\nu_3}(\mathbf{r}')\Phi_{\nu_1}(\mathbf{r}), \qquad (40.8)$$

where $v(\mathbf{r}-\mathbf{r}') = e^2/(4\pi\varepsilon_0\epsilon|\mathbf{r}-\mathbf{r}'|)$ is the Coulomb potential with the background dielectric function ϵ. The electron charge and the vacuum dielectric constant are given by e and ε_0, respectively.

A second step involves the inclusion of screening effects due to excited carriers. From the nature of screening as well as from the excitation conditions at elevated temperatures (considered for optoelectronic applications), it appears natural to account only for screening due to the carriers in the delocalized WL states. A consistent theory of screening for the QD-WL system is developed in Nielsen et al. (2005). On these grounds, a simplified treatment can be justified, which consists in the replacement of $v(\mathbf{r} - \mathbf{r}')$ in Equation 40.8 by a two-dimensionally screened Coulomb potential. The time-dependence of the screened Coulomb matrix elements $W_{\nu\nu_2\nu_3\nu_1}(t)$ is introduced via the carrier population functions $f_\nu(t)$, which determine the screening for the present excitation conditions via a longitudinal dielectric function.

The renormalized single-particle energies, that enter in the scattering rates (40.5) and (40.7), can be obtained from the free-carrier energies by adding Hartree, exchange, and correlation self-energy contributions. The Hartree self-energy involves the electrostatic interaction with all other excited electrons and holes. Only in a system with local charge neutrality, the Hartree terms cancel. In QDs, local charging appears as a result of different electron and hole populations, different envelope wave functions for electrons and holes, as well as due to the charge separation of electrons and holes in a built-in electrostatic fields (Nielsen et al., 2005).

40.3.2 Carrier–Phonon Interaction

For low carrier densities, when carrier–carrier Coulomb scattering is less important, the interaction of carriers with phonons provides the only remaining efficient scattering mechanism. At higher carrier densities, the carrier–phonon interaction remains important, since the Coulomb scattering is unable to dissipate kinetic energy from the carrier system. Note that the carrier–carrier scattering leads to an evolution of the carrier system towards a quasi-equilibrium state for electrons and holes. However, it conserves the average kinetic energy of the carriers. Pumping of carriers with above-average kinetic energy and the preferred recombination of carriers in the highly populated states with below-average kinetic energy effectively heats up the carrier system. This excess kinetic energy can only be dissipated to the crystal lattice via the emission of phonons. A thermalization of the carriers with respect to the crystal lattice is essential for efficient laser operation, since the increasing carrier temperature diminishes the optical gain via a reduction of the population inversion.

40.3.2.1 Perturbation Theory versus Polaron Picture

The early work on carrier–phonon interaction in semiconductor QDs has been based on the application of time-dependent perturbation theory. This method has previously been applied to bulk semiconductors or quantum wells. In these cases, its success is based on the application to carriers in continuum states. For the discussion of carrier–phonon interaction involving localized QD states with discrete energies, one has to consider the fact that the transition matrix elements provide only efficient coupling to phonons with small momenta (Bockelmann and Bastard, 1990; Inoshita and Sakaki, 1997). The strongest contribution to the interaction of carriers with lattice vibrations is typically provided by LO-phonons due to the Coulomb-like coupling of carriers to lattice displacements in polar crystals. The nearly constant LO-phonon energy, at least for the considered small phonon momenta, and the energy-conservation requirement from Fermi's golden rule led to the prediction of inefficient carrier transitions between the QD states, except for the unlikely coincidence of transition energies between the QD states with the LO-phonon energy. The other, usually less important interaction process is provided via deformation potential coupling to LA-phonons. For small phonon momenta, their energy is too small to facilitate efficient carrier scattering processes between the QD states. On these ground, particularly due to the application of perturbation theory, inefficient carrier–phonon scattering processes in QD systems have been predicted (Benisty et al., 1991). To prevent this so-called *phonon bottleneck*, only much less efficient higher-order processes, like those involving combinations of LA- and LO-phonons (Inoshita and Sakaki, 1992; Jiang and Singh, 1998) or the contributions of carrier–carrier scattering processes at elevated carrier densities have been proposed.

For a more advanced description of the interaction with LO-phonons, one has to take into account that freely moving charge carriers in ionic crystals are surrounded by a cloud of lattice distortions. The renormalization of electrons and holes introduced by the corresponding interaction leads to the emergence of a quasiparticle called polaron. In the past, polarons have mostly been studied for semiconductor structures with a quasi-continuum of electronic states, like bulk materials or quantum wells. Then, electronic transitions are already possible within a free-carrier picture. For the usually considered materials with weak polar coupling, this explains why the application of perturbation theory already provides the leading contributions of polaron effects. They consist in a lowering of the carrier energy (polaron shift) in a renormalization of the carrier mass and the dielectric constant for the Coulomb interaction of carriers, and in a small broadening of the electronic states (Schäfer and Wegener, 2002).

On the contrary, it has been pointed out in Inoshita and Sakaki (1997) and Kral and Khas (1998), and Verzelen et al. (2002) that even in materials with weak polar coupling, the interaction of carriers in localized QD states with LO-phonons leads to strong modifications of the electronic properties. In this case, the phonon satellites of one state hybridize with other discrete states, even if the level spacing does not match the LO-phonon energy. The resulting new quasiparticle of the strongly interacting system are called QD-polarons. They cannot be treated within perturbation theory. Therefore, a simple discussion of carrier–phonon interaction based on Fermi's golden rule is not applicable to QDs. Related to this is an ongoing controversy in the QD literature regarding experimental evidence for (Minnaert et al., 2001; Urayama et al., 2001; Xu et al., 2002) and against (Tsitsishvili et al., 2002; Peronne et al., 2003; Quochi et al., 2003) the phonon bottleneck.

Early investigations of QD-polarons have been based on the "random phase approximation" (RPA) (Inoshita and Sakaki, 1997; Kral and Khas, 1998) or on the direct diagonalization of a restricted state space (Verzelen et al., 2002), where only localized states are considered. For a single discrete electronic state, an analytic treatment of the interaction with LO-phonons is possible within the "independent boson model" (Mahan, 1990). The numerical extension to several discrete electronic states is discussed in Stauber et al., (2000). However, in this work, the influence of delocalized WL states with a quasi-continuum of energies, which plays a key role for carrier generation in optoelectronic devices, has been neglected. When investigations are restricted to localized states with discrete energies, RPA results deviate from a more accurate direct diagonalization of a restricted system. On the other hand, the inclusion of WL states provides a natural source of broadening of the electronic states, which justifies the application of the RPA.

The next step in the analysis of carrier–phonon scattering in QD systems was the development of a theory that accounts for the scattering of renormalized quasiparticles (QD-polarons). This became possible within a quantum-kinetic theory that has been applied to the problem of carrier capture and relaxation (Seebeck et al., 2005). Such a quantum-kinetic description naturally incorporates both non-Markovian effects on ultrafast timescales and a nonperturbative treatment of the carrier–phonon interaction in the polaron picture. Polaronic renormalization effects have been found to be the main origin for fast carrier capture and relaxation processes, as well as efficient carrier thermalization on a picosecond timescale. The results strongly deviate from a perturbative treatment using Fermi's golden rule.

40.3.2.2 Polaron States and Kinetics

In the following, the retarded Green's function $G^{\mathrm{r}}_{\alpha}(\tau)$ with the time τ and the state index α is used to describe the quasiparticle renormalizations of QD electrons and holes in the single-particle states α due to the nonperturbative interaction with LO-phonons. In the absence of interaction, this function oscillates with the free-carrier energy ε_α according to

$$G^{\mathrm{r}}_{\alpha}(\tau) = \frac{i}{\hbar}\Theta(\tau)e^{-\frac{i}{\hbar}\varepsilon_\alpha \tau} \tag{40.9}$$

and the Fourier transform

$$G^{\mathrm{r}}_{\alpha}(\omega) = \frac{1}{\hbar\omega - \varepsilon_\alpha + i\eta}, \tag{40.10}$$

with the frequency ω has a pole at the free-carrier energy with $\eta > 0$, $\eta \to 0$. Quasiparticle renormalizations are obtained from the solution of the Dyson equation:

$$\left[i\hbar\frac{\partial}{\partial\tau} - \varepsilon_\alpha\right]G^{\mathrm{r}}_{\alpha}(\tau) = \delta(\tau) + \int_0^\tau d\tau' G^{\mathrm{r}}_{\alpha}(\tau')\sum_\beta G^{\mathrm{r}}_{\beta}(\tau-\tau')D^{>}_{\alpha\beta}(\tau-\tau'), \tag{40.11}$$

where the sum involves all available states β. The Dyson equation contains a self-energy for the many-body description of interaction processes. In Equation 40.11, the so-called random-phase approximation has been used to formulate the interaction term with the phonon propagator

$$D^{\substack{>\\<}}_{\alpha\beta}(\tau) = \sum_{\vec{q}} |M_{\alpha\beta}(\vec{q})|^2 \times [n_{\mathrm{LO}}e^{\pm i\omega_{\mathrm{LO}}\tau} + (1+n_{\mathrm{LO}})e^{\mp i\omega_{\mathrm{LO}}\tau}], \tag{40.12}$$

where

n_{LO} is a Bose–Einstein function for the population of the phonon modes (assumed to act as a bath in thermal equilibrium)
ω_{LO} is the LO-phonon frequency

The sum over the three-dimensional phonon wave vector $\vec{q}$ involves all phonon modes. For an introduction into the many-body theory in general and Green's functions in particular, we refer the reader to Schäfer and Wegener (2002) and Mahan (1990).

The Dyson equation (Equation 40.11) takes into account all possible virtual transitions due to carrier–phonon interaction for a carrier in the state α. The single-particle energies for both localized and delocalized states are considered, and the corresponding wave functions enter via the interaction matrix elements $M_{\alpha\beta}$.

The Fourier transform of the retarded Green's function directly provides the spectral function $\hat{G}_\alpha(\omega) = -2\,\mathrm{Im}\,G^{\mathrm{r}}_{\alpha}(\omega)$ that reflects the density of states (DOS) for a carrier in the state α. Only for noninteracting carriers, the spectral function contains a delta-function at the free-particle energies, expressing that each state is associated with a single energy. This picture changes due to the quasiparticle renormalizations.

The dynamics of the carrier population due to interaction with LO-phonons can be described with a quantum-kinetic equation (Schafer and Wegener, 2002; Seebeck et al., 2005)

$$\begin{aligned}\frac{\partial}{\partial t}f_\alpha(t) = 2\,\mathrm{Re}\sum_\beta\int_{-\infty}^{t} dt' G^{\mathrm{r}}_{\beta}(t-t')[G^{\mathrm{r}}_{\alpha}(t-t')]^{\star}\\ \times\left\{f_\alpha(t')\left[1-f_\beta(t')\right]D^{<}_{\alpha\beta}(t'-t) - [1-f_\alpha(t')f_\beta(t')D^{>}_{\alpha\beta}(t'-t)]\right\}.\end{aligned} \tag{40.13}$$

In comparison to Boltzmann scattering rates, the delta-functions are replaced by convolutions of the phonon propagator with retarded Green's functions. The latter account for the polaronic renormalizations of the initial and final carrier states. Furthermore, memory effects are included by the time dependence of the population factors on the past evolution of the system.

Boltzmann scattering integrals follow as a limiting case, when the Markov approximation is applied (population functions $f_\alpha(t')$ are taken at the external time t) and when quasiparticle renormalizations are neglected with the use of free-carrier retarded Green's functions (40.9).

Examples for ultrafast carrier scattering processes in the polaron picture are displayed in Figure 40.5. Even if the level



FIGURE 40.5 Temporal evolution of the QD electron population due to scattering of carriers with LO-phonons. Calculations have been performed in the polaron picture for the InGaAs/GaAs material system at room temperature. Left: carrier relaxation from the initially populated p-shell (top) into the initially empty s-shell (bottom). Right: carrier capture from the WL into the initially empty p-shell (top) and s-shell (bottom). Different energy spacings ΔE between the s- and p-shell in units of the LO-phonon energy are compared. (From Seebeck, J. et al., *Phys. Rev. B*, 71, 125327, 2005. With permission.)

spacing between s and p-shell and between p-shell and WL bandedge exceeds the LO-phonon energy by 40%, efficient carrier relaxation and carrier capture are observed, while Boltzmann scattering integrals would predict vanishing carrier transitions for the interaction with LO-phonons.

40.4 Optical Gain of the Active Material

Of central importance for the design process and for various emission properties of lasers are the optical gain of the active material and the corresponding refractive index changes. Both quantities are linked via the optical susceptibility, which is introduced in this section.

In the following, we give some examples for the role of the optical gain. The threshold current of a laser is determined by the transparency carrier density at which the active material switches from absorption to optical gain. The carrier-density dependence of the gain influences the modulation bandwidth, and the temperature dependence of the optical gain is the main factor for the temperature stability of the laser operation. It is also important to study the physical mechanisms of gain saturation, which limits the achievable optical gain.

For the edge-emitting laser structures, the optical mode propagates in the QD plane and refractive index changes, which are induced by excited carriers, directly influence the mode properties like frequency chirp or filamentation, as well as the laser linewidth. In the following, we establish a microscopic picture to determine these gain and refractive index properties in QD systems.

40.4.1 Optical Susceptibility

From Maxwell's equations, a wave equation for the optical field $\boldsymbol{E}(\boldsymbol{r},t)$ can be derived, which describes how the emitted field from the sample can be traced back to the macroscopic polarization $\boldsymbol{P}(\boldsymbol{r},t)$ inside the sample:

$$\left(-\nabla\times\nabla\times-\frac{1}{c^2}\frac{\partial^2}{\partial t^2}\right)\boldsymbol{E}(\boldsymbol{r},t)=\mu_0\frac{\partial^2}{\partial t^2}\boldsymbol{P}(\boldsymbol{r},t). \tag{40.14}$$

The polarization represents the macroscopic dipole density in the medium, which is induced by the field itself, as expressed by the optical susceptibility

$$\boldsymbol{P}(\boldsymbol{r},t)=\int d^3r'\int dt'\chi(\boldsymbol{r},\boldsymbol{r}',t,t')\boldsymbol{E}(\boldsymbol{r}',t'). \tag{40.15}$$

In order to fulfill Equations 40.14 and 40.15 simultaneously, a self-consistent solution is necessary: the field determined from the wave equation should be the same function entering the calculation of the polarization. For simplicity, we neglect the tensorial character of χ and consider given polarization directions for $\boldsymbol{P}$ and $\boldsymbol{E}$.

From Equation 40.15 can be inferred that the susceptibility is a response function describing the answer of the medium to the optical field. Mathematically this can be expressed with the functional derivative

$$\chi(\boldsymbol{r},\boldsymbol{r}',t,t')=\frac{\delta P(\boldsymbol{r},t)}{\delta E(\boldsymbol{r}',t')}. \tag{40.16}$$

The optical absorption spectrum is commonly defined via the *linear response* of the medium. In this case, χ depends only on the difference of the time arguments (as can be shown from the explicit quantum mechanical calculation of the macroscopic polarization). Then one obtains in Equation 40.15 a convolution in time, which translates into a product in Fourier space and to give

$$\chi_{\mathrm{QD}}(\omega) = \frac{P_{\mathrm{QD}}(\omega)}{E_{\mathrm{QD}}(\omega)}. \tag{40.17}$$

For notational simplicity, we have no longer written the space dependence of the functions. In the considered case of an active material of QDs, the optical susceptibility is given as the macroscopic QD polarization P_{QD} divided by the linear optical test field at the QD position E_{QD}.

The absorption spectrum $\alpha(\omega)$ as well as the refractive index changes of the medium due to resonant excitation $\delta n(\omega)$ of the QD system is given by

$$-K\delta n(\omega) + i\alpha(\omega) = \frac{\omega}{\varepsilon_0 n_B c L}\chi_{\mathrm{QD}}(\omega), \tag{40.18}$$

where

c and ε_0 are the speed of light and permittivity in vacuum
n_B is the background refractive index
L is the thickness of the QD sheet
K is the wave number of the optical field

40.4.2 Interband Transitions and Macroscopic Polarization

The macroscopic optical QD polarization can be determined from the quantum mechanical expectation value of the dipole operator $\langle \boldsymbol{d} \rangle = \mathrm{Tr}\{\boldsymbol{d}\rho\} = \sum_{\nu_1,\nu_2} \boldsymbol{d}_{\nu_1,\nu_2}\rho_{\nu_2,\nu_1}$, which is calculated with the statistical operator ρ. Since $\boldsymbol{d}$ is a single-particle operator, a partial trace over the statistical operator can be performed in a way that only the single-particle statistical operator with the matrix elements ρ_{ν_1,ν_2} contributes. The sum involves all single-particle states of the chosen basis, as discussed for QD systems in Section 40.2.

In the following, we further specify the single-particle density-matrix elements. The diagonal elements represent the population of the state ν and have already been abbreviated by f_ν in Section 40.3. The off-diagonal elements Ψ_{ν_1,ν_2} are transition amplitudes between the corresponding states. Then the single-particle density matrix has the form

$$\rho_{\nu_1,\nu_2} = \begin{pmatrix} f_{\nu_1} & \Psi_{\nu_1,\nu_2} \\ \Psi^{\star}_{\nu_1,\nu_2} & f_{\nu_2} \end{pmatrix}. \tag{40.19}$$

For the calculation of the optical polarization, we use that the diagonal dipole-matrix elements vanish exactly. Also, we consider only interband transition contributions to the dipole coupling. For the final calculation of the macroscopic QD polarization, we assume that the optical field averages over sufficiently many QDs to obtain

$$\boldsymbol{P}_{\mathrm{QD}}(t) = n_{\mathrm{QD}}\langle \boldsymbol{d} \rangle = n_{\mathrm{QD}} \sum_{\nu_1,\nu_2} \boldsymbol{d}_{\nu_1,\nu_2}\Psi_{\nu_1,\nu_2}(t), \tag{40.20}$$

with the (sheet) density of QDs n_{QD}.

40.4.3 Optical Gain Calculations

A consistent microscopic theory for the calculation of coherent optical properties (related to the interaction of the active material with a classical optical field) can be formulated on the basis of equations of motion for the single-particle density matrix elements. These equations can be derived from the Hamiltonian of the QD system, which contains the contributions of free-carriers, their dipole interaction with the optical fields, as well as further relevant interaction processes like the Coulomb interaction of carriers and the carrier–phonon interaction.

When only the free-carrier Hamiltonian and the dipole interaction with the optical field are considered, the density matrix elements obey the optical Bloch equations (Meystre and Sargent III, 1991). We obtain coupled equations for the interband transition amplitude $\Psi_{\nu_1,\nu_2}(t)$ and for the occupation probabilities $f_{\nu_{1,2}}(t)$.

$$i\hbar\frac{\partial}{\partial t}\Psi_{\nu_1,\nu_2} = \left(\epsilon_{\nu_1} - \epsilon_{\nu_2} - \frac{i\hbar}{T_2}\right)\Psi_{\nu_1,\nu_2} + (f_{\nu_1} - f_{\nu_2})d_{\nu_1,\nu_2}E_{\mathrm{QD}}, \tag{40.21}$$

$$\frac{\partial}{\partial t}f_{\nu_1} = \frac{i}{\hbar}\sum_{\nu_2}[d_{\nu_1,\nu_2}E_{\mathrm{QD}}\Psi^{\star}_{\nu_1,\nu_2} - c.c.] - \frac{f_{\nu_1} - F_{\nu_1}}{T_1}, \tag{40.22}$$

$$\frac{\partial}{\partial t}f_{\nu_2} = -\frac{i}{\hbar}\sum_{\nu_1}[d_{\nu_1,\nu_2}E_{\mathrm{QD}}\Psi^{\star}_{\nu_1,\nu_2} - c.c.] - \frac{f_{\nu_2} - F_{\nu_2}}{T_1}. \tag{40.23}$$

A phenomenological way to include the influence of carrier scattering and dephasing is via time constants $T_{1,2}$, respectively. For the last term in Equations 40.22 and 40.23, a relaxation-time approximation has been used, which describes the evolution of the occupation probabilities $f_{\nu_{1,2}}$ toward quasi-equilibrium functions $F_{\nu_{1,2}}$ on a time-scale T_1. Damping of the interband transition amplitude Ψ_{ν_1,ν_2}, which determines the linewidth of the interband transitions, is accounted for with the dephasing time T_2 in Equation 40.21.

The stationary solution of Equation 40.21 together with Equations 40.17 and 40.20 allows to calculate the optical susceptibility in the form

$$\chi_{\mathrm{QD}}(\omega) = n_{\mathrm{QD}}\sum_{\nu_1,\nu_2}|d_{\nu_1,\nu_2}|^2(f_{\nu_1} - f_{\nu_2}) \times \left[\frac{1}{\hbar\omega - \varepsilon_{\nu_{12}} + \frac{i}{T_2}} - \frac{1}{\hbar\omega - \varepsilon_{\nu_{12}} + \frac{i}{T_2}}\right]. \tag{40.24}$$

The imaginary part of $\chi_{QD}(\omega)$ describes the absorption spectrum of the system and reveals discrete lines for interband transitions between the QD states $\nu_{1,2}$ with a linewidth $\propto 1/T_2$ at the interband energies $\varepsilon_{\nu_1\nu_2} = \varepsilon_{\nu_1} - \varepsilon_{\nu_2}$. When the population in the upper state exceeds that in the lower state, the population factor $f_{\nu_1} - f_{\nu_2}$ changes its sign and the system switches from absorption to optical gain.

It should be noted that the optical Bloch equations (Equations 40.21 through 40.23) and the resulting susceptibility (40.24) represent only a free-carrier picture, which is usually a poor approximation for a quantitative analysis. Important is the additional inclusion of Coulomb interaction effects in the optical Bloch equations for semiconductor systems (Haug and Koch, 2004), which is responsible for different types of effects. First of all, the interband Coulomb exchange interaction between electrons and holes accounts for excitonic effects at low excitation densities and interband Coulomb enhancement of the optical transitions. Secondly, energy renormalization shows up as excitation-dependent shifts of the transition energies, of which the band-gap renormalization is the most prominent signature. A closer inspection reveals, however, nonrigid shifts of all states. As a third modification, the microscopic replacement for scattering terms, expressed by the relaxation approximation in Equations 40.22 and 40.23, has been provided in Section 40.3. For consistency, similar terms need to be used in Equation 40.21 to describe the excitation-induced dephasing, which replaces the constant dephasing time T_2. Furthermore, screening of the Coulomb interaction contributes to a nonlinear dependence of the optical properties on the excitation conditions.



FIGURE 40.6 Imaginary part of the optical susceptibility, representing the absorption spectrum, versus energy relative to the band edge of the WL for a InGaAs/GaAs QD system. The spectrum contains two interband transitions due to confined states, which are magnified in the inset. (From Lorke, M. et al., *Phys. Rev. B,* 73, 085324, 2006. With permission.)

40.4.4 Gain Saturation, Refractive Index, and α-Factor

A microscopic theory for gain calculations in QD systems, which includes excitonic effects as well as excitation-induced energy renormalization and dephasing due to the screened Coulomb interaction and carrier–phonon interaction, has been developed in Lorke et al. (2006a). An example for the transition of a QD system from absorption to gain with increasing excitation density is shown in Figure 40.6. The calculations are performed at room temperature and assume a quasi-equilibrium distribution of the carriers over the QD and WL states due to efficient carrier-scattering processes. For a low excitation density (dotted line), QD s-shell and p-shell transitions as well as the WL exciton resonance at $E - E_G \approx -138$, -80, and -17 meV, respectively, are broadened due to carrier–phonon and carrier–carrier scattering processes. With increasing carrier density, the transition lines are bleached (due to phase-space filling) and further broadened (due to increased scattering efficiency). Note that bleaching reduces the oscillator strength, which needs to be distinguished from the increasing the linewidth (broadening). With population inversion of the QD states, optical gain is realized. Just above the transparency carrier density, only the s-shell transition exhibits optical gain. At higher carrier densities, the optical gain of the p-shell and of the WL are taking over. The WL gain is due to the increased population of the corresponding quantum-well-like states. The combination of band-gap shrinkage and band filling positions the WL gain near the low-density WL exciton resonance. The related small excitation-dependent shifts of the quantum well gain are discussed in Chow and Koch (1999).

When the QD states are completely populated with electrons and holes, a further increase of the total carrier density in the system does not lead to a larger optical gain at the corresponding transitions. This is clearly visible at the s-shell transition for the largest carrier densities in Figure 40.6. A higher carrier density in the assumed quasi-equilibrium situation only increases the population of the higher QD states and the WL states. The complete filling of the QD states is the origin for the observed gain saturation. Adding even more carriers to the system finally starts to reduce the QD ground-state gain due to further increasing dephasing (Lorke et al., 2006b).

At low carrier densities, the QD interband transition lines can be associated with QD excitons. The terminology might be viewed with reservations, since the electron–hole pairs are restricted to the QDs by the confinement potential and not—like quantum-well or bulk-semiconductor excitons—bound by the Coulomb interaction. The interplay of direct and exchange Coulomb interaction even allows for “anti-bound” states; a biexciton transition with an energy larger than that of two exciton transitions is the most prominent example. With the term "QD exciton," one emphasizes the role of the Coulomb interaction for characterizing the states. For quantum well and bulk semiconductor excitons, it is known that the delicate balance of energy renormalization (mainly band-gap shrinkage) and reduction of the exciton binding energy due to phase-space filling and screening leads to a nearly constant energetic position of the exciton resonance, which is bleached and broadened for increasing carrier density. The same behavior is observed for the WL exciton in Figure 40.6. However, the QD excitons show a pronounced red shift, which persists as a shift of the gain peaks at elevated carrier densities. When the energy renormalization is determined within a many-body theory formulated in a single-particle basis, it is the result of a partial compensation of state-diagonal and state-nondiagonal self-energies. It can be shown that this partial compensation is strongly reduced in QD systems (Lorke et al., 2006a).

The physics of QD gain spectra is expected to play an important role for QD-microcavity lasers with a small number of dots. In edge-emitting devices, inhomogeneous broadening can mask the discussed effects until the sample quality improves or the laser behavior (saturation effects, gain dynamics) is examined in greater detail.

The excitation-induced refractive index changes are directly linked to the corresponding absorption spectra via the Kramers–Kronig relation (Haug and Koch, 2004), since both can be derived from the complex optical susceptibility according to Equation 40.18. Refractive index changes directly influence the mode properties of edge-emitting lasers, including filamentation, as well as frequency chirp and emission spectra. In the past, the α-factor (linewidth-enhancement factor, antiguiding parameter) has been used to characterize the importance of the excitation-density-induced refractive index changes. In the free-carrier picture outlined above, the discrete nature of the QD states leads to symmetric absorption lines and vanishing refractive index changes at the absorption peak. The resulting value of zero for the α-factor has led to the prediction of many beneficial properties of QD lasers. Calculations based on microscopic semiconductor models show deviations from this simple picture, but also smaller α-factors than for quantum-well lasers (Lorke et al., 2007).

40.5 Laser Emission Properties

The optical gain characterizes the active material itself, while the steady-state and dynamical emission properties of lasers depend more generally on the interplay of the photon and carrier systems. The optical gain determines the rate of stimulated emission of photons into the laser mode. Together with the spontaneous emission rate, which is related to the photoluminescence spectrum, and the cavity losses, these processes govern the laser field inside the laser resonator and the light output. The carrier dynamics is determined by the interplay of the pump process, the transfer of carriers into the laser levels, as well as the optical processes.

The most intuitive approach to the steady-state and dynamical properties of lasers is provided by rate equations, which will be introduced in Section 40.5.1. Such a theory is based on restricting the information about the laser output to the mean photon number in the laser mode, as well as on a convenient parametrization of the rates for various processes. A generalization, which allows the systematic inclusion of semiconductor effects, is outlined in Section 40.5.2. The statistical properties of the light emission as well as the control of light–matter interaction in microcavity lasers are addressed in Section 40.5.3.

40.5.1 Rate Equations for Quantum-Dot Systems

In a rate-equation description (Yokoyama and Brorson, 1989; Rice and Carmichael, 1994), one uses two coupled dynamical equations for the number of photons in the laser mode n and the number of excited emitters N, which are QDs for the present purpose:

$$\frac{d}{dt}N = P - \frac{nN}{\tau_l} - \frac{N}{\tau_{sp}}, \tag{40.25}$$

$$\frac{d}{dt}n = -2\kappa n + \frac{(n+1)N}{\tau_l}. \tag{40.26}$$

The pump rate P increases the emitter number, while the cavity loss rate 2κ reduces the photon number. The loss rate is directly connected to the Q-factor of the laser mode, $Q = \hbar\omega_l/2\kappa$, with the laser frequency ω_l. The total rate of spontaneous emission N/τ_{sp}, which includes emission into all available lasing and nonlasing modes, reduces the number of excited emitters, while only the spontaneous emission directed into the laser mode N/τ_l contributes to the increase of the respective photon number. The simulated emission is additionally proportional to the mean photon number n, and the corresponding rate nN/τ_l appears in both rate equations with opposite signs.

An important parameter to characterize laser resonators is the β-factor, which is defined as the ratio of the spontaneous emission rate into the laser mode to the total spontaneous emission according to

$$\beta = \frac{1/\tau_l}{1/\tau_{sp}}. \tag{40.27}$$

In edge-emitting laser diodes, the large number of nonlasing modes leads to small values of $\beta = 10^{-6} \ldots 10^{-5}$, while in microcavity lasers the spontaneous emission into nonlasing modes can be strongly suppressed and $\beta \approx 1$ is approached.

A general evaluation of the rate equations can be readily performed by means of a direct numerical solution in time for a given pump rate P. If the initial condition is the unexcited system and the pump rates are switched on to a constant value, the solution either shows a smooth evolution to the steady-state or damped relaxation oscillations (Milonni and Eberly, 1991), depending on the chosen parameters.

The results for the steady-state solution and various β-factors are shown in Figure 40.7. A set of parameters referring to



FIGURE 40.7 Calculated input–output curves from the laser rate equations for $\beta = 1$ to 10^{-5} from top to bottom. The photon number and the pump rate are scaled with β in order to have the thresholds appear at equal pump intensities for better comparison. (From Gies, C. et al., *Phys. Rev. A*, 75, 013803, 2007. With permission.)

QD-microcavity lasers as been used: $\tau_{sp} = 50\,\text{ps}$ and $\kappa = 20\,\mu\text{eV}$. The corresponding cavity lifetime is about 17 ps, yielding a *Q*-factor of ≈30,000. The curves show a typical intensity jump $\propto \beta^{-1}$ from below to above threshold. In the limit $\beta = 1$, the kink in the input–output curve disappears.

The above discussed form of the rate equations is based on various assumptions. Only one optical mode is subject to stimulated emission; otherwise separate rate equations for the photon numbers in different laser modes need to be used and their modal gain determining τ_l needs to be distinguished. The derivation of the rate equations from a microscopic theory is based on the adiabatic elimination of transition amplitudes as well as on the factorization of carrier and photon correlations (Rice and Carmichael, 1994). Furthermore, in the rate equations, one assumes that the spontaneous and stimulated recombination rates are proportional to number of excited emitters *N*. Our discussion of the optical gain in Section 40.4.3 has already revealed that this is only a rough estimate neglecting optical nonlinearities and saturation effects. Furthermore, each QD is assumed to possess only two possible configurations, the excited and de-excited state. In reality, QDs often contain more than two localized states that can be occupied by several charge carriers. This can lead to various modifications of the simple "atomic approach."

The form of the spontaneous recombination term in the laser rate equations predicts an exponential decay of the photoluminescence after pulsed excitation and in the absence of stimulated emission. Recent experiments with self-assembled InGaAs/GaAs QDs embedded in GaAs-based micropillars (Schwab et al., 2006) showed, however, a nonexponential decay of the time-resolved photoluminescence. Furthermore, this decay was shown to be accompanied by a strong dependence on the excitation intensity. These two effects make it impossible to assign a single spontaneous emission lifetime to the QDs and question the simple picture used in the rate equations. This further underscores the importance of semiconductor models for a more detailed microscopic description of photoluminescence and gain in QD systems.

40.5.2 Microscopic Generalization: Semiconductor Effects

A semiconductor theory for QD lasers can be formulated on the basis of equations of motions for the carrier occupation probabilities of the QD levels and the photon number in the laser mode. For a microscopic derivation, one starts from the Hamiltonian describing the quantized electromagnetic field, the carrier system in second quantization, and the carrier–photon interaction in dipole approximation. Further interaction processes, like the Coulomb interaction of carriers and the carrier–phonon interaction, can be included systematically. Heisenberg equations of motion for the carrier and photon operators can be used to derive dynamical equations for the mean photon number ($n = b^\dagger b$) and the carrier occupation functions $f_\nu^e = \langle c_\nu^\dagger c_\nu \rangle, f_\nu^h = 1 - \langle v_\nu^\dagger v_\nu \rangle$. In these expectation values, $b^\dagger$ and b are photon creation and annihilation operators, $c_\nu^\dagger$ and c_ν are creation and annihilation operators for conduction-band carriers in the states ν and $v_\nu^\dagger v_\nu$ are the corresponding valence-band operators, respectively. The contribution of the interaction of carriers with the laser mode then leads to

$$\left(\frac{d}{dt} + 2\kappa\right) n = \frac{2}{\hbar} |g|^2 \sum_{\nu'} \text{Re}\left\langle b^\dagger v_{\nu'}^\dagger c_{\nu'} \right\rangle, \qquad (40.28)$$

$$\frac{d}{dt} f_\nu^{e,h}\Big|_{\text{opt}} = -\frac{2}{\hbar} |g|^2 \,\text{Re}\left\langle b^\dagger v_\nu^\dagger c_\nu \right\rangle, \qquad (40.29)$$

with the light–matter coupling strength *g*. It can be seen that the corresponding dynamics of the photon number and carrier populations are determined by the photon-assisted polarization $\langle b^\dagger v_\nu^\dagger c_\nu \rangle$, that describes the expectation value for a correlated event, where a photon is created in connection with an interband transition of an electron from the conduction to the valence band. The sum over ν involves all possible interband transitions from various QDs.

The time evolution of the photon-assisted polarization follows from its equation of motion,

$$\begin{aligned}\left(\frac{d}{dt} + \kappa + \Gamma + i(\tilde{\varepsilon}_\nu^e + \tilde{\varepsilon}_\nu^h - \hbar\omega_l)\right)\left\langle b^\dagger v_\nu^\dagger c_\nu \right\rangle \\ = f_\nu^e f_\nu^h - (1 - f_\nu^e - f_\nu^h) n \\ + i(1 - f_\nu^e - f_\nu^h) \sum_\alpha V_{\nu\alpha\nu\alpha} \left\langle b^\dagger v_\alpha^\dagger c_\alpha \right\rangle \\ + \sum_\alpha C_{\alpha\nu\nu\alpha}^x + \delta\left\langle b^\dagger b c_\nu^\dagger c_\nu \right\rangle - \delta\left\langle b^\dagger b v_\nu^\dagger v_\nu \right\rangle.\end{aligned} \qquad (40.30)$$

Here, the free evolution of $\left\langle b^\dagger v_\nu^\dagger c_\nu \right\rangle$ is determined by the detuning of the QD transitions at the renormalized energies $\tilde{\varepsilon}_\nu^{e,h}$ from the optical mode ω_l. Cavity losses κ and dephasing processes represented by Γ lead to a damping of the time evolution and to a broadening of the spectral components of the optical processes, which are spontaneous and stimulated emission. When deriving the equation of motion for $\langle b^\dagger v_\nu^\dagger c_\nu \rangle$, one finds that the source term of spontaneous emission is described by an expectation value of four carrier operators $\langle c_\alpha^\dagger v_\alpha v_\nu^\dagger c_\nu \rangle$. For uncorrelated carriers, the Hartree–Fock factorization of this source term leads to $f_\nu^e f_\nu^h$, which appears as the first term on the right hand side of Equation 40.30. It describes a spontaneous recombination probability proportional to the occupation probabilities of electrons and holes, as expected in a free-carrier picture, but opposed to the situation in an atomic system, where the recombination depends only on the electron population. However, electrons and holes will not just contribute as independent carriers. Correlation contributions to the spontaneous emission are included in $C^x_{\alpha\nu\nu\alpha} = \delta\langle c_\alpha^\dagger v_\nu^\dagger c_\nu v_\alpha \rangle$. These correlations describe the joint probability of a two-particle process, where two interband carrier transitions between the states α and ν take place. As mentioned above, the indices include not only the electronic states but also the QD position. Consequently, one must distinguish between correlated transitions within one QD, which can be due to an excitonic population, and correlations of transitions within two separate QDs. The latter case is connected to the phenomenon of superfluorescence or superradiant coupling of different emitters. The Coulomb interaction contributes to the excitonic correlations of electrons and holes, which, in turn, are weakened by screening, phase-space filling, and dephasing effects of the excited carriers. The detailed microscopic description of these correlations is an intricate problem of many-body theory, and for further details we refer the interested reader to Baer et al. (2006).

In a similar fashion, stimulated emission or re-absorption of photons is represented by $(1 - f_\nu^e - f_\nu^h)n$ in the absence of carrier–photon correlations. The latter are represented by $\delta\langle b^\dagger b c_\nu^\dagger c_\nu \rangle$ and $\delta\langle b^\dagger b v_\nu^\dagger v_\nu \rangle$, which require their own equations of motion. Furthermore, the interband Coulomb–exchange interaction with the matrix elements $V_{\nu\alpha\nu\alpha}$ is responsible for excitonic effects similar to its appearance in the semiconductor Bloch equations (Haug and Koch, 2004).

While the semiconductor theory offers the potential to account for various interaction effects in a much more detailed way, this also complicates a numerical analysis significantly. Results from the semiconductor theory for the input–output curves are shown in the lower part of Figure 40.8. Deviations from the rate-equation results involve a different height in the intensity jump at the laser threshold and saturation effects. The semiconductor theory also opens the possibility to calculate parameters entering rate equation models based on single-particle properties and interaction effects.

40.5.3 Quantum-Dot Microcavity Lasers: Modifications of the Photon Statistics

Latest advances in the growth and design of semiconductor-QD microcavity lasers have now attained the regime of β-values close to unity (Strauf et al., 2006; Ulrich et al., 2007). The strongly increased cavity-Q (corresponding to a long lifetime of photons in the cavity) allows to fabricate QD-based lasers with a small number of dots in the active region. The strongly enhanced light-matter coupling and the operation with a small number of photons in the laser mode leads to novel emission properties that are directly related to the quantum-mechanical nature of light. In particular, the photon statistics of the emitted radiation does no longer exhibit the transition from thermal to coherent radiation for increasing pumping, and "nonclassical" properties on the level of few photons can be realized.



FIGURE 40.8 Input–output curves and auto-correlation functions $g^{(2)}$ ($\tau = 0$) for various β-factors calculated with the semiconductor model. (From Gies, C. et al., *Phys. Rev. A*, 75, 013800, 2007. With permission.)

To characterize these systems, one needs to study the coherence properties of the emitted light and the statistical properties of the photons. Following Glauber, the quantum states of light can be characterized in terms of photon correlation functions. Coherence properties of the electromagnetic field itself are reflected by the (normalized) correlation function of first order,

$$g^{(1)}(\tau) = \frac{\langle b^\dagger(t) b(t+\tau) \rangle}{\langle b^\dagger(t) b(t) \rangle}. \qquad (40.31)$$

Its decay in τ is determined by the coherence time of the emitted light $\tau_c = \int |g^{(1)}(\tau)|^2 \, d\tau$. Here, $b^\dagger$ and b are again the creation and annihilation operators for photons in the laser mode. Information about the statistical properties of the emitted light can be deduced from the correlation function of second order at zero delay time

$$g^{(2)}(\tau = 0) = \frac{\langle n^2 \rangle - \langle n \rangle}{\langle n \rangle^2} = \frac{\langle b^\dagger b b^\dagger b \rangle - \langle b^\dagger b \rangle}{\langle b^\dagger b \rangle^2}. \quad (40.32)$$

The function $g^{(2)}(\tau = 0)$ reflects the possibility of the correlated emission of two photons at the same time. Often discussed are the limiting cases of light emission from a thermal, a coherent, and a single-emitter light source. Thermal light is characterized by an enhanced probability that two photons are emitted at the same time (bunching), reflected in a value of $g^{(2)}(0) = 2$. For coherent light emission with Poisson statistics, one finds $g^{(2)}(0) = 1$. An ideal single-photon emitter exhibits antibunching with $g^{(2)}(0) = 0$. This, the second-order correlation function, can be used to characterize the emission and to analyze the transition from thermal (or even sub-Poissonian) to coherent light emission.

For atomic systems, various methods have been established to analyze photon correlation functions. A master equation can be used to describe an ensemble of emitters interacting with a single high-Q laser cavity mode and a bath of non-lasing modes (Rice and Carmichael, 1994). For a single-atom laser, a direct analysis of the von Neumann equation for the statistical operator including the coupling to dissipative systems is possible (Mu and Savage, 1992). Semiconductor effects can be included in generalized equations of motion for higher-order carrier and photon correlation functions (Gies et al., 2007). Results of a semiconductor theory for the second-order photon correlation function are displayed in the upper part of Figure 40.8. For smaller β-factors referring to conventional lasers, the output-intensity jump at the laser threshold is accompanied with a sudden change of the correlation function between values representing thermal and coherent light. For increasing values of β, the gradually disappearing jump in the photon number is connected with a smoother transition of $g^{(2)}(0)$ and the presence of correlations for small pump rates.

Acknowledgments

The author thanks P. Gartner and J. Wiersig for the intense and productive collaboration on the covered subjects. The contributions from our PhD students T. Nielsen, N. Baer, J. Seebeck, M. Lorke, and C. Gies are also gratefully acknowledged. This work was financially supported by the Deutsche Forschungsgemeinschaft. We also thank P. Gartner and C. Gies for the critical reading of the manuscript and A. Beuthner for the preparation of Figure 40.1.

References

Agrawal, G. P. and N. K. Dutta. 1993. *Semiconductor Laser*. Norwell, MA: Kluwer.

Anders, S., C. S. Kim, B. Klein, M. W. Keller, R. P. Mirin, and A. G. Norman. 2002. Bimodal size distribution of self-assembled In_xGa_{1-x} As quantum dots. *Phys. Rev. B* **66**:125309.

Arakawa, Y. and H. Sakaki. 1982. Multidimensional quantum well laser and temperature dependence of its threshold current. *Appl. Phys. Lett.* **40**:939.

Asada, M., Y. Miyamoto, and Y. Suematsu. 1986. Gain and the threshold of three-dimensional quantum-box lasers. *IEEE J. Quantum Electron.* **QE-22**:1915.

Baer, N., C. Gies, J. Wiersig, and F. Jahnke. 2006. Luminescence of a semiconductor quantum dot system. *Eur. Phys. J. B* **50**:411.

Benisty, H., C. M. Sotomayor-Torres, and C. Weisbuch. 1991. Intrinsic mechanism for the poor luminescence properties of quantum-box systems. *Phys. Rev. B* **44**:10945.

Bimberg, D., M. Grundmann, and N. N. Ledentsov. 1999. *Quantum Dot Heterostructures*. Chichester, U.K.: John Wiley & Sons.

Bockelmann, U. and G. Bastard. 1990. Phonon scattering and energy relaxation in two-, one-, and zero-dimensional electron gases. *Phys. Rev. B* **42**:8947.

Casey, H. C. and M. B. Panish. 1978a. *Heterostructure Lasers—Part A: Fundamental Principles*. New York: Academic Press.

Casey, H. C. and M. B. Panish. 1978b. *Heterostructure Lasers—Part B: Materials and Operating Characteristics*. New York: Academic Press.

Chang-Hasnain, C. J., J. P. Harbison, G. Hasnain, A. C. von Lehmen, L. T. Florenz, and N. G. Stoffel. 1991. Dynamic, polarization, and transverse mode characteristics of vertical cavity surface emitting lasers. *IEEE J. Quantum Electron.* **27**:1402.

Chow, W. W. and S. W. Koch. 1999. *Semiconductor-Laser Fundamentals*. Berlin, Germany: Springer.

Chuang, S. L. 1995. *Physics of Optoelectronic Devices*. New York: Wiley.

Chuang, S. L. and C. S. Chang. 1996. $k \cdot p$ method for strained wurtzite semiconductors. *Phys. Rev. B* **54**:2491.

Dingle, R. and C. H. Henry. 1976. Quantum effects in heterostructure lasers. U.S. Patent 3982207.

Fattal, D., E. Diamanti, K. Inoue, and Y. Yamamoto. 2004. Quantum teleportation with a quantum dot single photon source. *Phys. Rev. Lett.* **92**:037904.

Gies, C., J. Wiersig, M. Lorke, and F. Jahnke. 2007. Semiconductor model for quantum-dot-based microcavity lasers. *Phys. Rev. A* **75**:013803.

Haug, H. and A.-P. Jauho. 1996. *Quantum Kinetics in Transport & Optics of Semiconductors*, 1st edn. Berlin, Germany: Springer.

Haug, H. and S. W. Koch. 2004. *Quantum Theory of the Optical and Electronic Properties of Semiconductors*, 4th edn. Singapore: World Scientific Publishing Company.

Inoshita, T. and H. Sakaki. 1992. Electron relaxation in a quantum dot: Significance of multiphonon processes. *Phys. Rev. B* **46**:7260.

Inoshita, T. and H. Sakaki. 1997. Density of states and phonon-induced relaxation of electrons in semiconductor quantum dots. *Phys. Rev. B* **56**:4355.

Jacobi, K. 2003. Atomic structure of InAs quantum dots on GaAs. *Prog. Surf. Sci.* **71**:185.

Jewell, J. L., J. P. Harbison, A. Scherer, Y. H. Lee, and L. T. Florez. 1991. Vertical-cavity surface-emitting lasers: Design, growth, fabrication, characterization. *IEEE J. Quantum Electron.* **27**:1332.

Jiang, H. and J. Singh. 1998. Self-assembled semiconductor structures: Electronic and optoelectronic properties. *IEEE J. Quantum Electron.* **34**:1188.

Kim, S. M., Y. Wang, M. Keever, and J. S. Harris. 2004. High-frequency modulation characteristics of 1.3 μm InGaAs quantum dot lasers. *IEEE Photon. Technol. Lett.* **16**:377.

Klude, M., T. Passow, R. Kröger, and D. Hommel. 2004. Electrically pumped lasing from CdSe quantum dots. *Electron. Lett.* **37**:1119.

Kral, K. and Z. Khas. 1998. Electron self-energy in quantum dots. *Phys. Rev. B* **57**:2061.

Li, H. E. and K. Iga, eds. 2003. *Vertical-Cavity Surface-Emitting Laser Devices*, 1st edn. Berlin, Germany: Springer.

Lodahl, P., A. F. van Driel, I. S. Nikolaev, A. Irman, K. Overgaag, D. Vanmaekel-bergh, and W. L. Vos. 2004. Controlling the dynamics of spontaneous emission from quantum dots by photonic crystals. *Nature* **430**:654.

Lorke, M., T. R. Nielsen, J. Seebeck, P. Gartner, and F. Jahnke. 2006a. Influence of carrier-carrier and electron-phonon correlations on optical absorption and gain in quantum-dot systems. *Phys. Rev. B* **73**:085324.

Lorke, M., W. W. Chow, T. R. Nielsen, J. Seebeck, P. Gartner, and F. Jahnke. 2006b. Anomaly in the excitation dependence of optical gain in semiconductor quantum dots. *Phys. Rev. B* **74**:035334.

Lorke, M., F. Jahnke, and W. Chow. 2007. Excitation dependence of gain and carrier induced refractive index changes in quantum dots. *Appl. Phys. Lett.* **90**:051112.

Mahan, G. D. 1990. *Many-Particle Physics*, 2nd edn. New York: Plenum.

Meystre, P. and M. Sargent III. 1991. *Elements of Quantum Optics*, 2nd edn. New York: Springer.

Michler, P., A. Kiraz, C. Becher, W. V. Schoenfeld, P. M. Petroff, L. Zhang, E. Hu, and A. Imamoglu. 2000. A quantum dot single-photon turnstile device. *Science* **290**:2282.

Milonni, P. and J. H. Eberly. 1991. *Lasers*, 1st edn. New York: John Wiley & Sons.

Minnaert, A. W. E., A. Yu. Silov, W. van der Vleuten, J. E. M. Haverkort, and J. H. Wolter. 2001. Frhlich interaction in InAs/GaAs self-assembled quantum dots. *Phys. Rev. B* **63**:075303.

Moreau, E., I. Robert, L. Manin, V. Thierry-Mieg, J. M. Gerad, and I. Abram. 2001. Quantum cascade of photons in semiconductor quantum dots. *Phys. Rev. Lett.* **87**:183601.

Mu, Y. and C. M. Savage. 1992. One-atom lasers. *Phys. Rev. A* **46**:5944.

Nakamura, S. and S. F. Chichibu, eds. 2000. *Introduction to Nitride Semiconductor Blue Lasers and Light Emitting Diodes*, 1st edn. Boca Raton, FL: CRC Press.

Newell, T. C., D. J. Bossert, A. Stintz, B. Fuchs, K. J. Malloy, and L. F. Lester. 1999. Gain and linewidth enhancement factor in InAs quantum-dot laserdiodes. *IEEE Photon. Technol. Lett.* **11**:1527.

Nielsen, T. R., P. Gartner, and F. Jahnke. 2004. Many-body theory of carrier capture and relaxation in semiconductor quantum-dot lasers. *Phys. Rev. B* **69**:235314.

Nielsen, T. R., P. Gartner, M. Lorke, J. Seebeck, and F. Jahnke. 2005. Coulomb scattering in nitride-based self-assembled quantum dot systems. *Phys. Rev. B* **72**:235311.

Peronne, E., F. Fossard, F. H. Julien, J. Brault, M. Gendry, B. Salem, G. Bremond, and A. Alexandrou. 2003. Dynamic saturation of an intersublevel transition in self-organized InAs/InAlAs quantum dots. *Phys. Rev. B* **67**:205329.

Quochi, F., M. Dinu, L. N. Pfeiffer, K. W. West, C. Kerbage, R. S. Windeler, and B. J. Eggleton. 2003. Coulomb and carrier-activation dynamics of resonantly excited InAs/GaAs quantum dots in two-color pump-probe experiments. *Phys. Rev. B* **67**:235323.

Reithmaier, J. P., G. Sek, A. Löffler, C. Hofmann, S. Kuhn, S. Reitzenstein, L. V. Keldysh, V. D. Kulakovskii, T. L. Reinecke, and A. Forchel. 2004. Strong coupling in a single quantum dot-semiconductor microcavity system. *Nature* **432**:197.

Rice, P. R. and H. J. Carmichael. 1994. Photon statistics of cavity-QED lasers. *Phys. Rev. A* **50**:4318.

Schäfer, W. and M. Wegener. 2002. *Semiconductor Optics and Transport Phenomena*, 1st edn. Berlin, Germany: Springer-Verlag.

Scholz, M., T. Aichele, S. Ramelow, and O. Benson. 2006. Deutsch-Jozsa algorithm using triggered single photons from a single quantum dot. *Phys. Rev. Lett.* **96**:180501.

Schwab, M., H. Kurtze, T. Auer, T. Berstermann, M. Bayer, J. Wiersig, N. Baer et al. 2006. Radiative emission dynamics of quantum dots in a single cavity micropillar. *Phys. Rev. B* **74**:045323.

Sebald, K., C. Kruse, and J. Wiersig. 2009. Properties and prospects of blue-green emitting II-VI-based monolithic microcavities. *Phys. Stat. Sol.* (*b*) **246**:255.

Seebeck, J., T. R. Nielsen, P. Gartner, and F. Jahnke. 2005. Polarons in semiconductor quantum-dots and their role in the quantum kinetics of carrier relaxation. *Phys. Rev. B* **71**:125327.

Shah, J. 1999. *Ultrafast Spectroscopy of Semiconductors and Semiconductor Nanostructures*. Berlin, Germany: Springer-Verlag.

Stauber, T., R. Zimmermann, and H. Castella. 2000. Electron-phonon interaction in quantum dots: A solvable model. *Phys. Rev. B* **62**:7336.

Strauf, S., K. Hennessy, M. T. Rakher, Y.-S. Choi, A. Badolato, L. C. Andreani, E. L. Hu, P. M. Petroff, and D. Brouwmeester. 2006. Self-tuned quantum dot gain in photonic crystal lasers. *Phys. Rev. Lett.* **96**:127404.

Tsang, W. T. 1982. Extremely low threshold (AlGa)As graded-index waveguide separate-confinement heterostructure lasers grown by molecular beam epitaxy. *Appl. Phys. Lett*. **40**:217.

Tsitsishvili, E., R. V. Baltz, and H. Kalt. 2002. Temperature dependence of polarization relaxation in semiconductor quantum dots. *Phys. Rev. B* **66**:161405.

Ulrich, S. M., C. Gies, J. Wiersig, S. Reitzenstein, C. Hofmann, A. Löffler, A. Forchel, F. Jahnke, and P. Michler. 2007. Photon statistics of semiconductor microcavity lasers. *Phys. Rev. Lett*. 98:043906.

Urayama, J., T. B. Norris, J. Singh, and P. Bhattacharya. 2001. Observation of phonon bottleneck in quantum dot electronic relaxation. *Phys. Rev. Lett*. **86**:4930.

Vahala, K. 2003. Optical microcavities. *Nature* **424**:839.

Verzelen, O., R. Ferreira, G. Bastard, T. Inoshita, and H. Sakaki. 2002. Polaron effects in quantum dots. *Phys. Stat. Sol.* (*a*) **190**:213.

Vurgaftman, I. and J. R. Meyer. 2003. Band parameters for nitrogen-containing semiconductors. *J. Appl. Phys*. **94**:3675.

Wojs, A., P. Hawrylak, S. Fafrad, and L. Jacak. 1996. Electronic structure and magneto-optics of self-assembled quantum dots. *Phys. Rev. B* **54**:5604.

Xu, S., A. A. Mikhailovsky, J. A. Hollingsworth, and V. I. Klimov. 2002. Hole intra-band relaxation in strongly confined quantum dots: Revisiting the phonon bottleneck problem. *Phys. Rev. B* **65**:045319.

Yokoyama, H. and S. D. Brorson. 1989. Rate equation analysis of microcavity lasers. *J. Appl. Phys*. **66**:4801.

Yoshie, T., A. Scherer, J. Hendrickson, G. Khitrova, H. M. Gibbs, G. Rupper, C. Ell, O. B. Shchekin, and D. G. Deppe. 2004. Vacuum Rabi splitting with a single quantum dot in a photonic crystal nanocavity. *Nature* **432**:200.

41

Mode-Locked Quantum-Dot Lasers

41.1 Introduction 41-1
41.2 Ultrafast Laser Diodes 41-2
Basics of Mode Locking • Mode-Locking Techniques in Semiconductor Lasers • Passive Mode Locking: Physics and Devices • Requirements for Successful Passive Mode Locking • Self-Phase Modulation and Dispersion
41.3 Quantum Dots: Distinctive Advantages for Ultrafast Diode Lasers.......................... 41-5
The Role of Dimensionality in Semiconductor Lasers • Quantum Dots: Materials and Growth • Broad Gain Bandwidth • Ultrafast Carrier Dynamics • Low Absorption Saturation Fluence • Low Threshold Current and Low Temperature Sensitivity • Low Linewidth Enhancement Factor
41.4 Mode-Locked Quantum-Dot Lasers: State of the Art 41-8
Pulse Duration • Toward Higher Pulse Repetition Rates • Temperature Resilience of Mode- Locked QD Lasers • Mode Locking Involving Excited-State Transitions
41.5 Summary and Outlook 41-10
Critical Discussion • Future Perspectives
Acknowledgments 41-10
References 41-10

Maria A. Cataluna
University of Dundee

Edik U. Rafailov
University of Dundee

41.1 Introduction

Over the last three decades, laser physics has advanced dramatically. Starting from lasers operated in a continuous wave (cw) regime, scientists have developed techniques for generating periodic sequences of optical pulses with ultrashort durations—between a few picoseconds (1×10^{-12} s) and a few femtoseconds (1×10^{-15} s). To put this into perspective, 1 fs compared to 1 s is the same as 1 s compared to 32 million years! Such ultrafast lasers have important applications in medicine, micromachining, optical communications, spectroscopy, and anything else that requires studying physics at extremely high powers or extremely short timescales. For instance, these lasers have been successfully adapted in eye surgery, because ultrashort pulses can make extremely precise cuts with minimum thermal damage.

However, despite the wide range of important areas that can benefit from ultrafast lasers, the use of these lasers is constrained due to several limitations. The ultrafast lasers currently available are often bulky, expensive, and difficult to operate. The ideal ultrafast laser would be a low-cost, handheld, and turnkey laser—features which could be offered by semiconductor lasers. Semiconductor lasers cannot yet directly generate the sub-100 fs pulses routinely available from crystal-based lasers, but they represent the most compact and efficient sources of picosecond and sub-picosecond pulses. Furthermore, the bias can be easily adjusted to determine the pulse duration and the optical power, thus offering, to some extent, electrical control of the characteristics of the output pulses. These lasers also offer the best option for the generation of high-repetition rate trains of pulses, owing to their small cavity size. Ultrafast diode lasers have thus been favored over other laser sources for high-frequency applications such as optical data/telecommunications. Being much cheaper to fabricate and operate, ultrafast semiconductor lasers also offer the potential for dramatic cost savings in a number of applications that traditionally use solid-state lasers. The deployment of high-performance ultrafast diode lasers would therefore have a significant economic impact, by enabling ultrafast applications to become more profitable, and even facilitate the emergence of new applications.

Novel nanomaterials such as quantum dots (QDs) have enhanced the characteristics of semiconductor lasers, greatly improving their performance. QDs are tiny clusters of semiconductor material with dimensions of only a few nanometers. At these small sizes, materials behave very differently, giving QDs distinctive physical properties of quantum nature—for instance, the emission wavelength or "color" depends on the size of the dot! These nanomaterials afford major advantages in ultrafast science and technology, and they can form the basis for very compact and efficient lasers delivering short pulses of the order of hundreds of femtoseconds (Rafailov et al., 2007).

In this chapter, we show how QDs have enabled the generation of ultrashort pulses from compact optical sources based on semiconductor laser diodes. In Section 41.2, the necessary background information is presented on ultra-short-pulse generation from diode lasers. The concept of mode locking is introduced, and an overview of the mode-locking techniques available for semiconductor lasers is provided. The unique properties of QD materials and their suitability for ultra-short-pulse diode lasers are explained in Section 41.3. Finally, a summary of the state of the art in the field of QD mode-locked laser diodes is provided in Section 41.4. The chapter is finalized by a summary and an outlook on the future perspectives of this fascinating field.

41.2 Ultrafast Laser Diodes

41.2.1 Basics of Mode Locking

Mode locking is a technique that involves the locking of the phases of the longitudinal modes in a laser. This results in the generation of a sequence of pulses with a repetition rate corresponding to the cavity round-trip time. This well-established technique enables the production of the shortest pulse durations and the highest repetition rates available from ultrafast lasers, whether they are semiconductor or crystal-based laser systems. In a standing-wave resonator, the pulse repetition rate f_R is given by

$$f_R = \frac{c}{2nL}$$

where

c is the speed of light in vacuum
n is the refractive index
L is the length of the laser cavity

In terms of Fourier analysis, there is an inverse proportionality between the duration of a mode-locked pulse and the corresponding bandwidth of its optical spectrum. The product of both the pulse duration $\Delta\tau$ and the optical frequency bandwidth $\Delta\nu$ is called the time-bandwidth product (TBWP). For a given frequency bandwidth, there is a minimum corresponding pulse duration—if this is the case and the optical spectrum is symmetrical, then the pulse is said to be transform-limited, and the TBWP equals a constant K, whose value depends on the shape of the pulse, whether it is Gaussian, hyperbolic, secant, squared, or Lorentzian. By measuring the full-width at half maximum from an optical spectrum $\Delta\lambda$, it is easy to calculate the TBWP of a given pulse:

$$\Delta\nu \cdot \Delta\tau = K \quad \Rightarrow \quad \frac{c}{\lambda^2}\Delta\lambda \cdot \Delta\tau = K$$

Another important property of mode-locked lasers is that the energy that was dispersed in several modes while in cw operation, is now concentrated in short pulses of light. This implies that although the output average power P_{av} may be low, the pulse peak power P_{peak} can be significantly higher:

$$P_{\text{peak}} = \frac{E_{\text{p}}}{\Delta\tau} \quad \Rightarrow \quad P_{\text{peak}} = \frac{1}{\Delta\tau}\cdot\frac{P_{\text{av}}}{f_R}$$

where E_{p} is the pulse energy.

41.2.2 Mode-Locking Techniques in Semiconductor Lasers

In recent years, mode-locked laser diodes have been at the center of a quest for ultrafast, transform-limited, and high-repetition-rate lasers. To achieve these goals, a variety of mode-locking techniques and semiconductor device structures have been demonstrated and optimized (Vasil'ev, 1995). The three main forms of mode locking can be described as active, passive, and hybrid techniques, as outlined below.

Active mode locking relies on the direct modulation of the gain with a frequency equal to the repetition frequency of the cavity, or to a sub-harmonic of this frequency. The main advantages of this approach are the resultant low jitter and the ability to synchronize the laser output with the modulating electrical signal. These features are especially relevant for optical transmission and signal-processing applications. However, high repetition frequencies are not readily obtained through directly driven modulation of lasers because fast RF (radiofrequency) modulation of the drive current becomes progressively more difficult with increase in frequency.

The frequency limitation imposed by electronic drive circuits can be overcome by employing passive mode-locking techniques. This scheme typically utilizes a saturable absorbing region in the laser diode. In a saturable absorber, the loss decreases as the optical intensity increases. This feature acts as a discriminator between cw and pulsed operation and can facilitate a self-starting mechanism for mode locking. Most importantly, saturable absorption plays a crucial role in shortening the duration of the circulating pulses, as will be explained, thus providing the shortest pulses achievable by all three techniques and the absence of a RF source simplifies the fabrication and operation considerably. Passive mode locking also allows for higher pulse repetition rates that are determined solely by the cavity length.

Inspired by active and passive mode locking, the technique of hybrid mode locking meets the best of both worlds because the pulse generation is initiated by an RF current imposed in the gain or absorber section, while further shaping and shortening is assisted by saturable absorption. The next section explores in more detail the physical mechanisms behind passive mode locking.*

---

* From this point, mode locking will implicitly mean passive mode locking, unless otherwise stated.

41.2.3 Passive Mode Locking: Physics and Devices

So far, a simple frequency-domain picture for mode locking has been provided, where the relative phases are of primary relevance. A physical model for passive mode locking can alternatively and equivalently be described in terms of the temporal broadening and narrowing mechanisms.

Upon startup of laser emission, the laser modes initially oscillate with relative phases that are random such that the radiation pattern consists of noise bursts. If one of these bursts is energetic enough to provide a fluence that matches the saturation fluence of the absorber, it will bleach the absorption. This means that around the peak of the burst where the intensity is higher, the loss will be smaller, while the low-intensity wings become more attenuated. The pulse generation process is thus initiated by this family of intensity spikes that experience lower losses within the absorber carrier lifetime.

The dynamics of absorption and gain play a crucial role in pulse shaping. In steady state, the unsaturated losses are higher than the gain. When the leading edge of the pulse reaches the absorber, the loss saturates more quickly than the gain, which results in a net gain window, as depicted in Figure 41.1. The absorber then recovers from this state of saturation to the initial state of high loss, thus attenuating the trailing edge of the pulse. It is thus easy to understand why the saturation fluence and the recovery time of the absorber are of primary importance in the formation of mode-locked pulses.

This temporal scenario can be connected to the previously described frequency domain description of mode locking. The burst of noise is the result of an instantaneous phase locking occurring among a number of modes. The self-saturation at the saturable absorber then helps to sustain and strengthen this favorable combination, by discriminating against the lower power cw noise.



FIGURE 41.1 A schematic diagram of the main components that forms a two-section laser diode (top). Loss and gain dynamics that lead to pulse generation (bottom).



FIGURE 41.2 A schematic of a two-section semiconductor laser diode.

In practical terms, a saturable absorber can be integrated monolithically into a semiconductor laser, by electrically isolating one section of the device (Figure 41.2). By applying a reverse bias to this section, the carriers that are photogenerated by the pulses can be more efficiently swept out of the absorber, thus enabling the saturable absorber to recover more quickly to its initial state of high loss. An increase in the reverse bias serves to decrease the absorber recovery time, and this will have the effect of further shortening the pulses.

41.2.4 Requirements for Successful Passive Mode Locking

Ultrafast carrier dynamics are fundamental for successful mode locking in semiconductor lasers, particularly in the saturable absorber, because the absorption should saturate faster and recover faster. Indeed, the absorption recovery time is one of the determining factors for obtaining ultrashort pulses. In particular, for high-repetition-rate lasers, the absorber recovery time should be much shorter than the cavity period so that the absorber can return to a state of total attenuation prior to the incidence of each incoming pulse. The fast absorption recovery also prevents the appearance of satellite pulses within the window of the net gain. On the other hand, the gain recovery time should be shorter than the cavity round-trip time. Thus, for lasers operating at pulse repetition rates of 20 GHz or more, this means that the recovery times of both gain and absorption should be much shorter than 40 ps.

The saturation dynamics represents another crucial aspect for successful mode locking, as shown schematically in Figure 41.3. Such dynamics can be translated in terms of saturation fluence F_{sat} or saturation energy $E_{sat} = A \cdot F_{sat}$, where A is the optical mode cross-sectional area. The saturation energy is an indication of how much energy is necessary to saturate the absorption or the gain. Indeed, to achieve robust mode locking, the saturation



FIGURE 41.3 Dependence of absorption/gain with carrier concentration in a semiconductor laser.

energy of the absorber $E_{\text{sat}}^{\text{a}}$ should be as small as possible and smaller than the saturation energy of the gain $E_{\text{sat}}^{\text{g}}$:

$$E_{\text{sat}}^{\text{a}} = \frac{h\nu A}{\frac{\partial a}{\partial N}} < E_{\text{sat}}^{\text{g}} = \frac{h\nu A}{\frac{\partial g}{\partial N}}$$

where
- h is Planck's constant
- ν is the optical frequency
- $\partial a/\partial N$ and $\partial g/\partial N$ are the differential loss and gain, respectively

The special dependence of the loss/gain with carrier density in a semiconductor laser allows $\partial a/\partial N > \partial g/\partial N$, as shown in Figure 41.3.

This condition implies that the absorber will saturate faster than the gain for a given pulse fluence, thus enabling the creation of the net gain window as already mentioned. The ratio between saturation energies should also be as large as possible to ensure that the losses saturate more strongly than the gain.

41.2.5 Self-Phase Modulation and Dispersion

In a semiconductor material, both the refractive index and gain (or loss) depend on the carrier density and are thus strongly coupled. As the pulse propagates in the gain section,* the carrier density and thus the gain is depleted across the pulse, as the carriers recombine through stimulated emission. This leads to a dynamic increase of the refractive index, which then introduces a phase modulation on the pulse, changing the instantaneous frequency across the pulse. This phenomenon is called self-phase modulation (SPM) and is one of the main nonlinear effects associated with pulse propagation in semiconductor media.

To understand the mechanism of SPM, consider the simple and illustrative example of a plane wave $E(t, x)$:

$$E(t,x) = E_0 \exp i\Phi(t) = E_0 \exp i(\omega_0 t - kx), \quad k = \frac{\omega_0}{c} n(t)$$

where
- $\Phi(t)$ is the time-varying phase
- k is the wave vector
- ω_0 is the optical carrier frequency
- c is the speed of light
- $n(t)$ is the time-varying refractive index

The instantaneous frequency is the time derivative of the phase and thus can be written as

$$\omega(t) = \frac{\partial}{\partial t}\Phi(t) = \omega_0 - \frac{\omega_0}{c}\frac{\partial n(t)}{\partial t}x$$

From this expression, it is clear that if the refractive index varies with time, then the instantaneous frequency of the plane wave will vary relative to ω_0 and in a manner proportional to the temporal derivative of the index. The time dependence of this instantaneous frequency is called the frequency chirp. An up-chirp† (down-chirp) means that the frequency increases (decreases) with time. An example of a frequency up-chirped pulse is illustrated in Figure 41.4.

SPM is not dispersive in itself, but the pulse will not remain transform-limited when it propagates in a dispersive material such as the laser medium. The effect of dispersion manifests itself in the variation of refractive index for different wavelengths which means that different spectral components will travel at different speeds. For an up-chirped pulse, the frequency is higher in the trailing edge than in the leading edge. When the pulse propagates through a material exhibiting positive (normal) dispersion, the trailing edge of the pulse propagates more slowly than the leading edge of the pulse and so this results in a temporal broadening of the pulse.

In a monolithic two-section mode-locked semiconductor laser, where a saturable absorber and a gain section coexist, the resulting chirp is a balance between the effects caused by the absorber and the gain. In the gain section, a frequency up-chirp results, while the saturable absorber helps to further



FIGURE 41.4 Illustration of an electric field of a strongly up-chirped pulse, where the instantaneous frequency increases with time.

---

[*] In the following discussion, reference is made mostly to gain to simplify the description. However, all this reasoning can be applied equally well to the absorber.

[†] Up-chirp is also known as blue-chirp or positive chirp.

shape the pulse by contributing with a negative chirp. With a suitable balance between both sections, the chirp can be close to zero thereby leading to transform-limited pulses. Unfortunately, this is the exception rather than the rule, because this usually only occurs for a limited set of bias conditions and/or for given ratios of absorber/gain lengths. Therefore, up-chirp prevails for passively mode-locked lasers, leading to significant pulse broadening as the pulse propagates. The combined effect of SPM and dispersion impose the strongest limitation in the achievable shortest duration of pulses from mode-locked semiconductor diode lasers.

The mechanism of SPM implies that in addition to the original frequency ω_0, there are now more frequencies inside the pulse envelope. This richer spectral content is not necessarily unhelpful because it can provide bandwidth support for shorter pulses, if the chirp of a pulse can be removed by provision of a suitable dispersion-induced chirp of the opposite sign. For up-chirped pulses, a dispersion compensation setup can be configured such that a negative (anomalous) group velocity dispersion is able to slow down the leading edge of the pulse and speed the blueshifted trailing edge to such an extent that at a certain point both edges propagate simultaneously and the pulse is shorter.

To routinely generate pulses that are nearly transform-limited, an alternative could be found in the choice of a material that exhibits lower coupling between refractive index and gain, as described by linewidth enhancement factor (LEF), or α-factor:

$$\alpha = -\frac{4\pi}{\lambda}\frac{dn/dN}{dg/dN}$$

A higher α-factor implies a more significant coupling between gain and refractive index changes with carrier concentration and thus the possibility for higher levels of SPM and frequency chirp.

41.3 Quantum Dots: Distinctive Advantages for Ultrafast Diode Lasers

41.3.1 The Role of Dimensionality in Semiconductor Lasers

The history of semiconductor laser materials has been punctuated by dramatic revolutions. Everything started with the proposal of p-n junction semiconductor lasers in 1961, followed by experimental realization on different semiconductor materials (Basov et al., 1961; Basov, 1964). However, the lasers fabricated at that time exhibited an extremely low efficiency due to high optical and electrical losses. In fact, until the mid-1960s, only bulk materials were used in semiconductor devices, which were functionalized by introducing a doping profile. At the time, pioneers like Alferov and Herbert Kroemer independently considered the hypothesis of building heterostructures, consisting of layers of different semiconductor materials (Alferov, 2001). The classic heterostructure example consists of a lower bandgap layer surrounded by a higher bandgap semiconductor material. Such design results in electronic and optical confinement, because a higher bandgap semiconductor also exhibits a higher refractive index. The enhanced confinement improved notably the operational characteristics of laser diodes, in particular the threshold current density, which decreased by two orders of magnitude.

But another revolution was about to come when it was realized that the confinement of electrons in lower dimensional semiconductor structures translated into completely new optoelectronic properties, when compared to bulk semiconductors. And how small should this confinement be? In order to answer this question, let us recall the concept of the de Broglie wavelength of thermalized electrons, λ_B:

$$\lambda_B = \frac{h}{p} = \frac{h}{\sqrt{2m^* E}}$$

where

h is the Planck's constant
p is the electron momentum
m^* is the electron effective mass
E is the energy

In the case of III–V compound semiconductors, λ_B is typically of the order of tens of nanometers (Saleh and Teich, 1991). If one of the dimensions of a semiconductor is comparable or less than λ_B, the electrons will be strongly confined in one dimension, while moving freely in the remaining two dimensions—this is the case of a quantum well (QW). A quantum wire is a one-dimensional confined structure, while a QD is confined in all the three dimensions. QDs are thus tiny clusters of semiconductor material with dimensions of only a few nanometers, surrounded by a semiconductor matrix that has a higher bandgap.

The spatial confinement of the carriers in lower dimensional semiconductors leads to dramatically different energy–momentum relations in the directions of confinement, which results in completely new density of states, when compared to the bulk case, as depicted in Figure 41.5. As dimensionality decreases, the density of states is no longer continuous or quasi-continuous but becomes quantized. In the case of QDs, the charge carriers occupy only a restricted set of energy levels rather like the electrons in an atom, and for this reason, QDs are sometimes referred to as "artificial atoms."

For a given energy range, the number of carriers necessary to fill out these states reduces substantially as the dimensionality decreases, which implies that it becomes easier to achieve transparency and inversion of population—with the resulting reduction of threshold current density. In fact, this reduction has been quite spectacular over the years, with sudden jumps whenever the dimensionality is decreased (Alferov, 2001).



FIGURE 41.5 Schematic structures of bulk and low-dimensional semiconductors and corresponding density of states. The density of states in different confinement configurations: (a) bulk; (b) quantum well; (c) quantum wire; and (d) quantum dot.

41.3.2 Quantum Dots: Materials and Growth

The group of QD materials that has shown particular promise is based on III–V QDs epitaxially grown on a semiconductor substrate. For instance, InGaAs/InAs QDs on a GaAs substrate emit in the 1–1.3 μm wavelength range, which could be extended to 1.55 μm. Alternatively, InGaAs/InAs QDs can be grown on an InP substrate that covers emission in the 1.4–1.9 μm wavelength range (Ustinov et al., 2003).

The remarkable achievements in QD epitaxial growth have enabled the fabrication of QD lasers, amplifiers, and saturable absorbers offering excellent performance characteristics. To date, the most promising results have been achieved using the spontaneous formation of three-dimensional islands during strained layer epitaxial growth in a process known as the Stranski–Krastanow mechanism (Goldstein et al., 1985; Ustinov et al., 2003). In this process, when a film A is epitaxially grown over a substrate B, the initial growth occurs layer by layer, but beyond a certain critical thickness, three-dimensional islands start to form—the quantum dots. A continuous film lies underneath the dots, and is called the wetting layer. The most important condition in this technique is that the lattice constant of the deposited material is larger than the one of the substrate. This is the case of an InAs film (lattice constant of 6.06 Å) on a GaAs substrate (lattice constant of 5.64 Å), for example.

In spite of being an extremely complex process, the Stranski–Krastanow mode is now widely used in the self-assembly of QDs. An advantage of this technique is that films can be grown using the well-known techniques of molecular beam epitaxy (MBE) and metal organic chemical vapor deposition (MOCVD), and therefore the science of QDs growth has benefited immensely from all the previous knowledge gained with this technology. These are also good news for commercialization, because manufacturers do not have to invest in new epitaxy equipment to fabricate these structures.

Due to the statistical fluctuations occurring during growth, there is a distribution in dot size, height, and composition but, at the moment, epitaxy techniques have evolved to such an extent that the amount of fluctuations can be reasonably controlled, and can be as small as a few percent.

If the dots are grown on a plane surface, their lateral positions will be random. An example of such structure is shown in Figure 41.6. In the self-assembly process, there is no standard way of arranging the dots in a planar ordered way, unless they are encouraged to grow at particular positions in a pre-patterned substrate.

At present, the densities of QDs lie typically between 10^9 cm^{-2} and 10^{11} cm^{-2}. The sparse distribution of QDs results in a low value of optical gain. Thus, the levels of gain and optical confinement provided by a single layer of QDs may not be enough for the optimal performance of a laser. In order to circumvent this problem, QDs can also be grown in stacks, which allows an increase in the modal gain without increasing the internal optical mode loss (Smowton et al., 2001), where the various layers are usually separated by GaAs barriers. The GaAs separators are responsible for transmitting the tensile strain from layer to layer, inducing the formation of ordered arrays of QDs aligned on top of each other. Further optical confinement is enabled through the cladding of such arrays within layers of higher refractive index and bandgap energy, therefore forming a heterostructure.



FIGURE 41.6 Photographs of an InGaAs quantum dots grown on GaAs substrate: (a) A TEM image of a single sheet of quantum dots. (b) A TEM image of a cross section of an 8-layer thick stack of quantum dots in GaAs layers.

41.3.3 Broad Gain Bandwidth

A QD laser was proposed in 1976 (Dingle and Henry, 1976) and the first theoretical treatment was published in 1982 (Arakawa and Sakaki, 1982). The main motivation was to conceive a design for a low-threshold, single-frequency, and temperature-insensitive laser, owing to the discrete nature of the density of states. In fact, practical devices exhibit the predicted outstandingly low thresholds (Kovsh et al., 2004; Liu et al., 2005), but the spectral bandwidths of such lasers are significantly broader than those of conventional QW lasers (Rafailov et al., 2007). This results from the self-organized growth of QDs, leading to a Gaussian distribution of dot sizes, with a corresponding Gaussian distribution of emission frequencies. Additionally, lattice strain may vary across the wafer, thus further affecting the energy levels in the quantum dots. These effects lead to the inhomogeneous broadening of the gain—a useful phenomenon in the context of ultrafast applications, because a very wide bandwidth is available for the generation, propagation, and amplification of ultrashort pulses. The effects of inhomogeneous broadening on the density of states are schematically illustrated in Figure 41.7. However, it is important to stress that a highly inhomogeneously broadened gain also encompasses a number of disadvantages, because it partially defeats the purpose of a reduced dimensionality, by broadening the density of states. Indeed, the fluctuation in the size of the QDs has the effect of increasing the transparency current and reducing the modal and differential gain (Qasaimeh, 2003; Dery and Eisenstein, 2005). Therefore, much effort has been put into improving the dots uniformization by engineering the growth and post-growth processes (Ustinov et al., 2003).

The extremely broad bandwidth available in QD mode-locked lasers offers potential for generating sub-100 fs pulses provided all of the bandwidth can be engaged coherently and dispersion effects suitably minimized.



FIGURE 41.7 Schematic morphology and density of states for charge carriers in (a) an ideal quantum-dot system and (b) a real quantum-dot system, where inhomogeneous broadening is illustrated.



FIGURE 41.8 Schematic of the energy levels in a QD material (a), and radiative transitions via GS—ground state (b) and ES—excited state (c). CB—Conduction band; VB—valence band.

Indeed, it has been shown that there is usually some gain in narrowing/filtering effects in mode-locked QW lasers (Delfyett et al., 1998). With the inhomogeneously broadened gain bandwidth exhibited by QDs, there is support for more bandwidth and this can oppose the effect of pulse broadening that may arise from spectral narrowing. Additionally, due to the particular nature of QD lasers, many possibilities open up in respect of the exploitation of ground-state (GS) and excited-state (ES) bands,* as schematically represented in Figure 41.8. Such versatility has been successfully exploited in a multiple-wavelength-band switchable mode locking (Cataluna et al., 2006c). On the other hand, the interplay between GS and ES can be deployed in novel mode-locking regimes (Cataluna et al., 2006a). Using an external cavity, it is possible to set up tunable mode-locked sources that can operate in the wavelength range that extends from the GS to the ES transition bands (Kim et al., 2006a).

41.3.4 Ultrafast Carrier Dynamics

In the initial studies of QD materials, it was thought that their carrier dynamics would be significantly slower than those in QW materials due to a phonon bottleneck effect (Mukai et al., 1996). Interestingly, experiments have demonstrated quite the opposite. As a consequence of access to a number of recombination paths for the carriers, QD structures exhibit ultrafast recovery both under absorption and gain conditions (Borri et al., 2006). In two evaluations, the absorber dynamics of surface and waveguided QD structures were investigated by using a pump-probe technique (Borri et al., 2000; Rafailov et al., 2004b). This showed the existence of at least two distinct time constants for the recovery of the absorption. A fast recovery of around 1 ps is followed by a slower recovery process that extends over 100 ps (Rafailov et al., 2004b).

More recently, sub-picosecond carrier recovery was measured directly in a QD absorption modulator when a reverse bias was applied (Malins et al., 2006). Absorption recovery times ranged from 62 ps down to 700 fs and showed a decrease by nearly two orders of magnitude when the reverse bias applied to the structure was changed from 0 V to −10 V. This important observation provides significant promise for ultrafast modulators that can operate above 1 THz and for the optimization of saturable absorbers used for the passive mode locking of semiconductor lasers at high repetition rates, where the absorption recovery should occur within the round-trip time of the cavity. Crucially, the shaping mechanism of the fast absorption recovery also enhances the shortening of the mode-locked pulses, and thus QD lasers have the potential for generating shorter pulses than their QW counterparts.

---

* Ground and excited states are also available in quantum wells. However, the δ-like density of states associated with quantum dots enables an easier access to the ES, owing to the faster saturation of the GS in quantum dots.

41.3.5 Low Absorption Saturation Fluence

QD-based saturable absorbers exhibit lower saturation fluence than QW-based materials due to their delta-like density of states. For example, in a QD one electron is enough to achieve transparency and two to achieve inversion. This characteristic facilitates the self-starting of mode locking at modest pulse energies. This feature is particularly important in high-repetition-rate lasers where the optical energy available in each pulse is small. Indeed, it has also been observed that the saturation power is at least 2–5 times smaller for a QD saturable absorber than for a QW-based counterpart when integrated in a monolithic mode-locked laser (Thompson et al., 2004a). In this paper, the authors pointed out that saturation would further depend on the density of dots, reverse bias, and inhomogeneous broadening.

41.3.6 Low Threshold Current and Low Temperature Sensitivity

As devices, QD diode lasers have the advantage of requiring a very low threshold current to initiate lasing (Ustinov et al., 2003). This attribute applies also to operation in the mode-locking regime, because most QD lasers exhibit mode-locked operation right from the threshold of laser emission. (Bistability between the non-lasing state and the onset of lasing/mode locking might be present, as has been shown experimentally (Huang et al., 2001; Thompson et al., 2006b) and numerically (Viktorov et al., 2006).) A low threshold current is clearly advantageous because this can represent a device that is compatible as an efficient and compact source of ultrashort pulses where the demand for electrical power can be very low. Furthermore, having a low threshold avoids the need for higher carrier densities for pumping the laser and this implies less amplified spontaneous emission and reduced optical noise in the generated pulse sequences.

Due to the discrete nature of their density of states, QD lasers also exhibit low-temperature sensitivity (Mikhrin et al., 2005), making them excellent candidates for applications where resilience to temperature effects is important.

41.3.7 Low Linewidth Enhancement Factor

One of the main motivations for the enthusiastic investigation of QD materials in the last few years has been the theoretically predicted potential for very low values of LEF, owing to the symmetry of the gain associated with QD structures. The possibility of a low LEF is very attractive for a number of performance aspects, such as lower frequency chirp in directly modulated lasers, lower sensitivity to optical feedback effects, and suppressed beam filamentation. The potential of a lower effect of SPM in QD lasers also held a promise for the generation of transform-limited pulses. However, disparate reports have been published in the last 3 years, with some reports of LEF values of nearly zero (Newell et al., 1999), and others with values of LEF similar (Ukhanov et al., 2004) or significantly higher than in QW structures (Dagens et al., 2005). Ultimately, the LEF is a characteristic that is highly dependent on the operation conditions of the laser, and as such, its meaning always needs to be contextualized for a set of particular conditions. This is a topic that is currently under intense investigation.

41.4 Mode-Locked Quantum-Dot Lasers: State of the Art

41.4.1 Pulse Duration

The first demonstration of a QD mode-locked laser was reported in 2001, with pulse durations of ~17 ps at 1.3 μm and repetition rate of 7.4 GHz, using passive mode locking (Huang et al., 2001). Hybrid mode locking at the same wavelength was demonstrated in 2003 by the Cambridge University group (Thompson et al., 2003); they reported an upper limit estimation of 14.2 ps for the shortest pulses measured at a repetition rate of 10 GHz. Later in 2004, the same group demonstrated Fourier-transform-limited 10 ps pulses at 18 GHz repetition rate, using passive mode locking (Thompson et al., 2004b).

In 2004, we demonstrated the generation of sub-picosecond pulses directly from a QD laser where the shortest pulse durations were measured to be 390 fs, without any form of supplementary pulse compression (Rafailov et al., 2004a, 2005). These pulses were generated by a two-section passively mode-locked QD laser and this was the first time that sub-picosecond pulses were generated directly from such a monolithic laser.

The generation of sub-picosecond pulses was reported later by several groups (Laemmlin et al., 2006; Thompson et al., 2006b). In one of these reports (in 2006), Thompson and coworkers demonstrated the generation of pulses as short as 790 fs, by using a flared waveguide configuration in a two-section QD laser (Thompson et al., 2006b). Because the beam mode size in the saturable absorber section was much smaller than that in the gain section, the ratio of saturation fluences in the absorber and gain sections was increased. This enhanced the pulse formation mechanisms and allowed for better pulse shaping and shortening.

There has also been much effort in designing QD-based mode-locked sources that could be deployed in the 1.55 μm band (Lelarge et al., 2007). Ultra-short-pulse generation has been achieved from single-section lasers based either on InAs QDs (Renaudier et al., 2005) or quantum dashes (Gosset et al., 2006) grown on an InP substrate. These authors have suggested that there are no fundamental differences between the QDs and dashes in the context of mode-locked laser sources.

41.4.2 Toward Higher Pulse Repetition Rates

To achieve higher repetition rates in mode-locked lasers, it is necessary to decrease the cavity length. This poses a significant challenge to QD lasers because of their lower gain and the operation in short cavities may shift the emission to the ES band (Markus et al., 2003). To avoid this problem, a higher number of QD layers should be deployed in the active region. Using this simple approach, the highest repetition rate directly generated from a passively mode-locked QD two-section laser was 80 GHz (Laemmlin et al., 2006), when a 15-layer structure was used. Another method to boost the repetition rate of mode-locked lasers is to use colliding pulse mode locking. This technique is similar to passive mode locking, but the saturable absorber region is placed at the precise center of the gain section. Two counter-propagating pulses from each outer gain section therefore meet in the saturable absorber region, bleaching it much more efficiently than if just one pulse was present. This process can also result in shorter and more stable pulses. Owing to the device geometry, mode locking is achieved at the second harmonic of the fundamental (round-trip) frequency, and the pulse repetition rate is doubled. A variation of colliding pulse mode locking is harmonic mode locking, where more than two pulses circulate in the cavity, the number being equal to the harmonic. Colliding-pulse mode-locking was first demonstrated for QD lasers in 2005 (Thompson et al., 2005), resulting in a modest repetition rate of 20 GHz. Harmonic mode locking has also been demonstrated with repetition rates of approximately 40, 80, 120, and 240 GHz (Rae et al., 2006).

41.4.3 Temperature Resilience of Mode-Locked QD Lasers

Due to their delta-function-like density of states, QDs offer great potential for designing temperature-resilient devices. If their high-speed performance is also proven to be resilient to temperature, QD lasers can become the next generation of sources for ultrafast optical telecoms and datacoms, because the constraint of using thermoelectric coolers can be avoided, thus decreasing cost and complexity. In this context, we have demonstrated stable passive mode-locked operation of a two-section QD laser over an extended temperature range (from 20°C to 80°C) at relatively high output average powers (Cataluna et al., 2006b).

Additionally, to meet the requirements for high-speed communications, it is important to investigate the temperature dependence of the pulse duration. For instance, in communication systems with transmission rates of 40 Gb/s or more, the temporal interval between pulses is less than 25 ps and so the duration of the optical pulses should be well below this value at any operating temperature. We have shown that the pulse duration and the spectral width decrease significantly as the temperature is increased up to 70°C (Cataluna et al., 2007). The combination of all these effects resulted in a sevenfold decrease of the time-bandwidth product (the pulses were still highly chirped due to the strong SPM and dispersion effects in the semiconductor material).

To account for the decrease in pulse duration with temperature, a model for mode locking in QD lasers was used. It was found that the pulse durations are determined principally by the escape rate of the carriers in the absorber section, which lead to a decrease of absorber recovery time with increasing temperature, thus inducing a decrease in the pulse durations. This has been verified recently using ultrafast spectroscopy to probe the absorber recovery time as a function of temperature (Malins et al., 2007).

41.4.4 Mode Locking Involving Excited-State Transitions

It has been observed that laser emission in QD lasers can access the transitions in GS, ES or both (Markus et al., 2003), as represented in Figure 41.8. Furthermore, sub-picosecond gain recovery has been demonstrated for both GS and ES transitions in electrically pumped QD amplifiers (Schneider et al., 2005). In this reported work, the LEF was shown to decrease significantly for wavelengths below the GS transition, even becoming negative at ES thereby implying a potential for chirp-free operation for the range of wavelengths involved. Laser emission in the ES is also characterized by a higher differential gain than GS, with associated benefits for ultrafast QD lasers. We have demonstrated an optical gain-switched QD laser, where pulses were generated from both GS and ES, and where the ES pulses were shorter than those generated by GS alone (Rafailov et al., 2006). The potential for shorter and chirp-free pulses from ES transitions motivated us to investigate the mode-locked operation of QD lasers in this band. We demonstrated, for the first time, passive mode locking via GS (1260 nm) or ES (1190 nm) in a QD laser, at repetition frequencies of 21 and 20.5 GHz, respectively (Cataluna et al., 2006c). The switch between these two states in the mode-locking regime was easily achieved by changing the electrical biasing conditions, thus providing full control of the operating spectral band. It is important to stress that the average power in both operating modes was relatively high and exceeded 25 mW. In the range of bias conditions explored in this study, the shortest pulse duration measured for ES transitions was ~7 ps, where the spectral bandwidth was 5.5 nm, at an output power of 23 mW. These pulse durations are similar to those generated by GS mode locking at the same power level.

Although pulse durations from ES spectral band have been below expectations so far, it is our opinion that exploitation of the ES transitions—a unique feature of QD lasers—can lead to a new generation of high-speed sources, where mode locking involves electrically switchable GS or ES transitions that are spectrally distinct. This could enable a range of applications extending from time-domain spectroscopy, through to optical interconnects, wavelength-division multiplexing, and ultrafast optical processing.

41.5 Summary and Outlook

41.5.1 Critical Discussion

In this chapter, we have presented the physics and reported on the progress of ultrafast laser diodes based on QD materials.

The results presented in the literature show that monolithic passively mode-locked QD lasers can currently surpass the performance of similar QW lasers in terms of pulse duration (Rafailov et al., 2005, Thompson et al., 2006b). There are other particular features where QD lasers have already been shown to have a superior performance, notably in the case of pulse timing jitter where record low values have been reported (Choi et al., 2006, Thompson et al., 2006a).

We strongly believe that the appeal of QD lasers also resides in the novel functionalities that are distinctive of QDs. These are the exploitation of an ES level as a means to achieve novel mode-locking regimes; the temperature resilience offered by the quantized density of states; lower threshold and higher output power levels; and access to the enlarged spectral bandwidths associated with the inhomogeneously broadened gain features. These characteristics are not only useful from an operational point of view, but also provide some insights into a more comprehensive understanding of the underlying physical mechanisms of mode locking in QD lasers.

41.5.2 Future Perspectives

Although there have been many advances in the control of the growth of QD laser having ultra-low threshold current and temperature resilience, it is not yet understood what is the most advantageous QD structure layout to be used in the regime of mode locking. In particular, it is not clear what is the optimum level of inhomogeneous broadening that results in shorter and higher peak power pulses. Therefore, it is relevant to investigate if and how the inhomogeneously broadened spectral modes are engaged coherently in the generation of ultrashort pulses and how that effect could be used to improve the performance of the lasers toward sub-picosecond pulse durations. Exploiting novel QD materials based on p-doped and tunnel injection structures could also bring advantages in minimizing the effect of any deleterious SPM effects in mode-locked lasers.

Comparison between theory and experiment of undoped and p-doped lasers has shown how this technique can improve the LEF (Kim and Chuang, 2006b). By tuning the level of doping, lasers can exhibit zero and even negative LEF at low current densities (Alexander et al., 2007). Tunnel injection QD structures can also be of great interest for use in mode-locked lasers, as the injection of cold carriers may bring many benefits to the operation of mode-locked lasers (Delfyett, 2006). The LEF has been recently calculated and has been demonstrated to be much less than that reported for other lasers (Mi and Bhattacharya, 2007). Selective excitation of population in these lasers has been demonstrated, which could lead to a mitigation of the inhomogeneous broadening effects and contribute to a narrower spectrum and the production of transform-limited pulses (Bret and Gires, 1964).

The ES spectral band can also be exploited in tunable lasers using QD materials where the inhomogeneous broadening is controlled so as to maximize the overlap between GSs and ESs. While in cw operation, QD lasers have been demonstrated with tunability ranges up to 200 nm (Varangis, 2000), by exploiting the gain available from the GSs and ESs. Combining this tunability with the possibility of generating ultrashort pulses, it will be possible to achieve a new generation of versatile lasers emitting pulses across a wide range of wavelengths—as if we had compressed many different lasers into a single laser! Such disruptive characteristics will offer endless possibilities and enable applications never seen before in science and technology.

Acknowledgments

We wish to thank Dr. D. Livshits, Dr. I. Krestnikov, and Dr. A. Kovsh from Innolume GmbH (Dortmund) for helping to prepare samples and for stimulating discussions.

This work was supported in part by the European Community's Seventh Framework Programme FAST-DOT under grant agreement 224338.

References

Alexander, R. R., Childs, D., Agarwal, H. et al. 2007. Zero and controllable linewidth enhancement factor in p-doped 1.3 μm quantum dot lasers. *Japanese Journal of Applied Physics* 46: 2421–2423.

Alferov, Z. I. 2001. Nobel Lecture: The double heterostructure concept and its applications in physics, electronics, and technology. *Reviews of Modern Physics* 73: 767.

Arakawa, Y. and Sakaki, H. 1982. Multidimensional quantum well laser and temperature dependence of its threshold current. *Applied Physics Letters* 40: 939–941.

Basov, N. G. 1964. Nobel lecture: Semiconductor lasers. http://www.nobel.se/physics/laureates/1964/basov-lecture.html.

Basov, N. G., Krokhin, O. N., and Popov, Y. M. 1961. The possibility of use of indirect transitions to obtain negative temperature in semiconductors. *Soviet Physics JETP* 12: 1033.

Borri, P., Langbein, W., Hvam, J. M., Heinrichsdorff, F., Mao, M. H., and Bimberg, D. 2000. Spectral hole-burning and carrier-heating dynamics in InGaAs quantum-dot amplifiers. *IEEE Journal of Selected Topics in Quantum Electronics* 6: 544–551.

Borri, P., Schneider, S., Langbein, W., and Bimberg, D. 2006. Ultrafast carrier dynamics in InGaAs quantum dot materials and devices. *Journal of Optics A-Pure and Applied Optics* 8: S33–S46.

Cataluna, M. A., Mcrobbie, A. D., Sibbett, W., Livshits, D. A., Kovsh, A. R., and Rafailov, E. U. 2006a. New mode locking regime in a quantum-dot laser: Enhancement by simultaneous CW excited-state emission. *Conference on Lasers and Electro-Optics/Quantum Electronics and Laser Science Conference paper CThH3*: CThH3, Long Beach, CA.

Cataluna, M. A., Rafailov, E. U., Mcrobbie, A. D., Sibbett, W., Livshits, D. A., and Kovsh, A. R. 2006b. Stable mode-locked operation up to 80°C from an InGaAs quantum-dot laser. *IEEE Photonics Technology Letters* 18: 1500–1502.

Cataluna, M. A., Sibbett, W., Livshits, D. A., Weimert, J., Kovsh, A. R., and Rafailov, E. U. 2006c. Stable mode locking via ground- or excited-state transitions in a two-section quantum-dot laser. *Applied Physics Letters* 89: 81124–3.

Cataluna, M. A., Viktorov, E. A., Mandel, P. et al. 2007. Temperature dependence of pulse duration in a mode-locked quantum-dot laser. *Applied Physics Letters* 90: 101102–3.

Choi, M.-T., Kim, J.-M., Lee, W., and Delfyett, P. J. 2006. Ultralow noise optical pulse generation in an actively mode-locked quantum-dot semiconductor laser. *Applied Physics Letters* 88: 131106–3.

Dagens, B., Markus, A., Chen, J. X. et al. 2005. Giant linewidth enhancement factor and purely frequency modulated emission from quantum dot laser. *Electronics Letters* 41: 323–324.

Delfyett, P. J. 2006. Personal communication.

Delfyett, P. J., Shi, H., Gee, S., Barty, C. P. J., Alphonse, G., and Connolly, J. 1998. Intracavity spectral shaping in external cavity mode-locked semiconductor diode lasers. *IEEE Journal of Selected Topics in Quantum Electronics* 4: 216–223.

Dery, H. and Eisenstein, G. 2005. The impact of energy band diagram and inhomogeneous broadening on the optical differential gain in nanostructure lasers. *IEEE Journal of Quantum Electronics* 41: 26–35.

Dingle, R. and Henry, C. H. 1976. Quantum effects in heterostructure lasers. U.S. Patent.

Goldstein, L., Glas, F., Marzin, J. Y., Charasse, M. N., and Roux, G. L. 1985. Growth by molecular beam epitaxy and characterization of InAs/GaAs strained-layer superlattices. *Applied Physics Letters* 47: 1099–1101.

Gosset, C., Merghem, K., Martinez, A. et al. 2006. Subpicosecond pulse generation at 134 GHz using a quantum-dash-based Fabry-Perot laser emitting at 1.56 μm. *Applied Physics Letters* 88: 241105–3.

Huang, X. D., Stintz, A., Li, H., Lester, L. F., Cheng, J., and Malloy, K. J. 2001. Passive mode-locking in 1.3 μm two-section InAs quantum dot lasers. *Applied Physics Letters* 78: 2825–2827.

Kim, J., Choi, M. T., Lee, W., and Delfyett, P. J. 2006a. Wavelength tunable mode-locked quantum-dot laser. *Enabling Photonics Technologies for Defense, Security, and Aerospace Applications II*: 6243: M2430.

Kim, J. and Chuang, S. L. 2006b. Theoretical and experimental study of optical gain, refractive index change, and linewidth enhancement factor of p-doped quantum-dot lasers. *IEEE Journal of Quantum Electronics* 42: 942–952.

Kovsh, A. R., Ledentsov, N. N., Mikhrin, S. S. et al. 2004. Long-wavelength (1.3–1.5 μm) quantum dot lasers based on GaAs. *Physics and Simulation of Optoelectronic Devices XII*: 5349: 31–45.

Laemmlin, M., Fiol, G., Meuer, C. et al. 2006. Distortion-free optical amplification of 20–80 GHz modelocked laser pulses at 1.3 μm using quantum dots. *Electronics Letters* 42: 697–699.

Lelarge, F., Dagens, B., Renaudier, J. et al. 2007. Recent advances on InAs/InP quantum dash based, semiconductor lasers and optical amplifiers operating at 1.55 mu m. *IEEE Journal of Selected Topics in Quantum Electronics* 13: 111–124.

Liu, H. Y., Childs, D. T., Badcock, T. J. et al. 2005. High-performance three-layer 1.3-μm InAs-GaAs quantum-dot lasers with very low continuous-wave room-temperature threshold currents. *IEEE Photonics Technology Letters* 17: 1139–1141.

Malins, D. B., Gomez-Iglesias, A., White, S. J., Sibbett, W., Miller, A., and Rafailov, E. U. 2006. Ultrafast electroabsorption dynamics in an InAs quantum dot saturable absorber at 1.3 μm. *Applied Physics Letters* 89: 171111–3.

Malins, D. B., Gomez-Iglesias, A., Cataluna, M. A., Rafailov, E. U., Sibbett, W., and Miller, A. 2007. Temperature dependence of electroabsorption dynamics in an InAs quantum dot saturable absorber at 1.3 μm. *CLEO-Europe'07*: CF-6, Munich, Germany.

Markus, A., Chen, J. X., Paranthoen, C., Fiore, A., Platz, C., and Gauthier-Lafaye, O. 2003. Simultaneous two-state lasing in quantum-dot lasers. *Applied Physics Letters* 82: 1818–1820.

Mi, Z. and Bhattacharya, P. 2007. Analysis of the linewidth-enhancement factor of long-wavelength tunnel-injection quantum-dot lasers. *IEEE Journal of Quantum Electronics* 43: 363–369.

Mikhrin, S. S., Kovsh, A. R., Krestnikov, I. L. et al. 2005. High power temperature-insensitive 1.3 μm InAs/InGaAs/GaAs quantum dot lasers. *Semiconductor Science and Technology* 20: 340–342.

Mukai, K., Ohtsuka, N., Shoji, H., and Sugawara, M. 1996. Phonon bottleneck in self-formed $In_xGa_{1-x}As/GaAs$ quantum dots by electroluminescence and time-resolved photoluminescence. *Physical Review B* 54: R5243–R5246.

Newell, T. C., Bossert, D. J., Stintz, A., Fuchs, B., Malloy, K. J., and Lester, L. F. 1999. Gain and linewidth enhancement factor in InAs quantum-dot laser diodes. *IEEE Photonics Technology Letters* 11: 1527–1529.

Qasaimeh, O. 2003. Effect of inhomogeneous line broadening on gain and differential gain of quantum dot lasers. *IEEE Transactions on Electron Devices* 50: 1575–1581.

Rae, A. R., Thompson, M. G., Penty, R. V. et al. 2006. Harmonic mode-locking of a quantum-dot laser diode. *LEOS* 2006: ThR5, Montreal, QC, Canada.

Rafailov, E. U., Cataluna, M. A., Sibbett, W. et al. 2004a. High-power ultrashort pulses output from a mode-locked two-section quantum-dot laser. *Conference on Lasers and Electro-Optics/International Quantum Electronics Conference*: CPDB5, post-deadline, San Francisco, CA.

Rafailov, E. U., White, S. J., Lagatsky, A. A. et al. 2004b. Fast quantum-dot saturable absorber for passive mode-locking of solid-state lasers. *IEEE Photonics Technology Letters* 16: 2439–2441.

Rafailov, E. U., Cataluna, M. A., Sibbett, W. et al. 2005. High-power picosecond and femtosecond pulse generation from a two-section mode-locked quantum-dot laser. *Applied Physics Letters* 87: 81107–3.

Rafailov, E. U., Mcrobbie, A. D., Cataluna, M. A., O'faolain, L., Sibbett, W., and Livshits, D. A. 2006. Investigation of transition dynamics in a quantum-dot laser optically pumped by femtosecond pulses. *Applied Physics Letters* 88: 41101–3.

Rafailov, E. U., Cataluna, M. A., and Sibbett, W. 2007. Mode-locked quantum-dot lasers. *Nature Photonics* 1: 395–401.

Renaudier, J., Brenot, R., Dagens, B. et al. 2005. 45 GHz self-pulsation with narrow linewidth in quantum dot Fabry-Perot semiconductor lasers at 1.5 μm. *Electronics Letters* 41: 1007–1008.

Saleh, B. E. A. and Teich, M. C. 1991. *Fundamentals of Photonics*. New York: Wiley.

Schneider, S., Borri, P., Langbein, W. et al. 2005. Excited-state gain dynamics in InGaAs quantum-dot amplifiers. *IEEE Photonics Technology Letters* 17: 2014–2016.

Smowton, P. M., Herrmann, E., Ning, Y., Summers, H. D., Blood, P., and Hopkinson, M. 2001. Optical mode loss and gain of multiple-layer quantum-dot lasers. *Applied Physics Letters* 78: 2629–2631.

Thompson, M. G., Marinelli, C., Tan, K. T. et al. 2003. 10 GHz hybrid modelocking of monolithic InGaAs quantum dot lasers. *Electronics Letters* 39: 1121–1122.

Thompson, M. G., Marinelli, C., Chu, Y. et al. 2004a. Properties of InGaAs quantum dot saturable absorbers in monolithic mode-locked lasers. *IEEE* 19th *International Semiconductor Laser Conference, Conference Digest*, Matsue-shi, Japan.

Thompson, M. G., Tan, K. T., Marinelli, C. et al. 2004b. Transform-limited optical pulses from 18 GHz monolithic modelocked quantum dot lasers operating at 1.3 μm. *Electronics Letters* 40: 346–347.

Thompson, M. G., Marinelli, C., Zhao, X. et al. 2005. Colliding-pulse modelocked quantum dot lasers. *Electronics Letters* 41: 248–250.

Thompson, M. G., Larson, D., Rae, A. et al. 2006a. Monolithic hybrid and passive mode-locked 40 GHz quantum dot laser diodes. 32nd *European Conference on Optical Communication*: We4.6.3, Cannes, France.

Thompson, M. G., Rae, A., Sellin, R. L. et al. 2006b. Subpicosecond high-power mode locking using flared waveguide monolithic quantum-dot lasers. *Applied Physics Letters* 88: 133119–3.

Ukhanov, A. A., Stintz, A., Eliseev, P. G., and Malloy, K. J. 2004. Comparison of the carrier induced refractive index, gain, and linewidth enhancement factor in quantum dot and quantum well lasers. *Applied Physics Letters* 84: 1058–1060.

Ustinov, V. M., Zhukov, A. E., Egorov, A. Y., and Maleev, N. A. 2003. *Quantum Dot Lasers*. New York: Oxford University Press.

Varangis, P. M., Li, H., Liu, G. T., Newell, T. C., Stintz, A., Fuchs, B., Malloy, K. J., and Lester, L. F. 2000. Low-threshold quantum dot lasers with 201 nm tuning range. *Electronics Letters* 36: 1544–1545.

Vasil'ev, P. 1995. *Ultrafast Diode Lasers: Fundamentals and Applications*. Boston, MA: Artech House.

Viktorov, E. A., Mandel, P., Vladimirov, A. G., and Bandelow, U. 2006. Model for mode locking in quantum dot lasers. *Applied Physics Letters* 88: 201102–3.

Zhang, L., Cheng, L., Gray, A. L. et al. 2005. Low timing jitter, 5 GHz optical pulses from monolithic two-section passively mode-locked 1250/1310 nm quantum dot lasers for high-speed optical interconnects. *Optical Fiber Communication Conference, OFC/NFOEC* OWM4, Anaheim, CA.

Index

A

- AFM, *see* Atomic force microscopy
- Aharonov–Bohm effect, 11-1
- Aluminum and gap engineering, 16-9 thru 16-10
- Ambegaokar–Barato relation, 16-2
- AND and XOR logic gates, 33-10 thru 33-11
- Andreev bound states, 7-3 thru 7-4
- Andreev reflection, 7-2
- Atomic force microscopy (AFM), 6-11 thru 6-12, 35-10
- Atomic-scale technology computer-aided design (TCAD), 12-11 thru 12-12
- Atomistic models, 40-5

B

- Bacteriorhodopsin (BR)
  - absorption spectra, 38-1 thru 38-2
  - basic process
    - activation function realization, 38-5
    - formal neuron main functions realization, 38-3
    - medium bleaching, 38-2 thru 38-3
    - neuro-like element formation, 38-3 thru 38-4
    - optical radiation fluxes, indirect interaction, 38-3
    - weighed signals composition function realization, 38-4 thru 38-5
    - weighing function realization, 38-4
  - nanostructure
    - complex estimation procedure, 38-10 thru 38-11
    - functional characteristics, 38-12 thru 38-14
    - hybrid nanostructures, 38-13 thru 38-17
  - optical neuronets
    - basic elements, multilayered structures, 38-7 thru 38-8
    - cyclicity processes, 38-5 thru 38-6
    - data processing, 38-6
    - element base parameters, 38-7
    - light fluxes formation, 38-6
    - multilayered constructions, 38-7
    - polymeric film property, 38-9 thru 38-10
    - polymeric film requirements, 38-8
    - polymeric mixture preparation, 38-8 thru 38-9
    - suspension preparation, 38-8
  - photocycle, 38-1 thru 38-2
- Berry's phase interference
  - definition, 9-5
  - electron in constant magnetic field, 9-6
  - path integrals, 9-6 thru 9-7
  - in single-molecule magnet transistors, 9-11 thru 9-12
- Biomaterial shaping, 18-6 thru 18-7
- Biomimetics, photonic nanostructures
  - antireflector engineering, 31-1, 31-3
  - cell culture, 31-3, 31-5
  - diatoms and coccolithophores
    - frustule, 31-5
    - *Nitzschia frustulum*, 31-6 thru 31-7
    - photochemical-etching technique, 31-5
    - photoluminescence (PL) emission, 31-5 thru 31-6
    - photonic device, 31-5 thru 31-6
    - porous glass, 31-7
  - eukaryote cell, 31-8
  - iridescent device engineering
    - *Aphrodita* sea mouse, 31-3
    - 2D christmas tree structure, 31-3 thru 31-4
    - metallic colored effect, 31-1 thru 31-2
    - *Morpho* butterfly scale, 31-2 thru 31-4
    - optical characteristics, 31-2
    - photonic crystal, 31-2
  - iridoviruses, 31-7
  - optical reflector types, 31-1 thru 31-2
  - silica deposition vesicle (SDV), 31-7
  - trans-Golgi-derived vesicle, 31-7
- Biomolecular neuronet devices, *see* Bacteriorhodopsin
- Bose–Einstein distribution function, 10-8
- Bowtie plasmonic nanolaser, 39-9
- Bragg mirrors, 39-3
- Bragg MOKE technique, 4-8 thru 4-9
- Break junction experiment, 12-9
- Bucky shuttle memory element, 3-16 thru 3-17
- Buttiker model, 10-5 thru 10-6

C

- Cantor's middle-excluded set, 17-13 thru 17-14
- Capacitance spectroscopy
  - capacitance transient spectroscopy (*see* Deep level transient spectroscopy)
  - depletion region
    - depletion capacitance, 2-13 thru 2-14
    - p–n junction, 2-12
    - Schottky contact, 2-11 thru 2-12
    - width of, 2-13
- Carbon nanotube (CNT) memory elements
  - CNFET-based memory
    - band structure, 3-3
    - charge-storage stability, 3-5 thru 3-6
    - controlling storage nodes, 3-6 thru 3-7
    - Fuhrer's device, 3-4
    - nanotube storage nodes, 3-9
    - optoelectronic memory, 3-7
    - Radosavljevic's device, 3-5
    - redox active molecules, 3-7
    - schematic cross section, 3-2
    - two-terminal memory devices, 3-7 thru 3-9
  - electromigration CNT, 3-16 thru 3-17
  - NEMS-based memory
    - capacitive force response, 3-9
    - feedback-controlled nanocantilevers, 3-12 thru 3-13
    - linear bearing nanoswitch, 3-14 thru 3-16
    - nanorelays, 3-11 thru 3-12
    - nonvolatile random access memory, 3-10 thru 3-11
    - properties, 3-9
    - vertically aligned carbon nanotubes, 3-13 thru 3-14
- Carbon nanotube transistors, 12-6 thru 12-7
- Carbon nanotube weak link
  - experimental realizations, 7-6 thru 7-7
  - Fabry–Perot cavity, 7-6
  - high-frequency irradiation, 7-9 thru 7-10
  - nanotube quantum dot
    - CNT superconducting transistor, 7-7 thru 7-8
    - gate dependence, 7-8 thru 7-9

- Carrier–carrier interaction
  - capture and relaxation time, 40-7
  - Coulomb interaction matrix element, 40-7
  - Markov approximation, 40-6
  - quantum-kinetic equation, 40-7
  - screening effects, 40-7 thru 40-8
- Carrier manipulation (up-converter), 33-7 thru 33-8
- Carrier–phonon interaction
  - perturbation theory *vs*. polaron picture, 40-8 thru 40-9
  - polaron states and kinetics, 40-9 thru 40-10
- Cathodoluminescence
  - band structure, types, 21-2
  - donor–acceptor pair transition, 21-2
  - exciton, 21-3
  - recombination process, 21-2
  - TEM-CL (*see* Transmission electron microscope-cathodoluminescence)
- C$_{60}$ field effect transistors
  - Bell Laboratory misconduct, 15-2 thru 15-3
  - characterization on SiO$_2$/AlN
    - I–V characteristics, 15-19
    - sub-threshold region, 15-19 thru 15-20
  - fabrication of
    - C$_{60}$ epitaxy, 15-18 thru 15-19
    - device process, 15-18
    - performance measurements, 15-19
    - SiO$_2$/AlN substrates, 15-18
  - field effect doping, 15-3
  - operation principles, 15-3 thru 15-4
  - solid C$_{60}$ and insulator films interface, 15-3
  - superconductivity, 15-4
- Charge-selective deep level transient spectroscopy, 2-16
- Charge trap memories, 2-6 thru 2-7
- Chemically amplified resist (CAR), 20-12
- Classical Faraday effect, 1-13
- CNT field-effect transistor (CNTFET), 12-7
  - band structure, 3-3
  - charge-storage stability, 3-5 thru 3-6
  - Fuhrer's device, 3-4
  - optoelectronic memory, 3-7
  - Radosavljevic's device, 3-5
  - schematic cross section, 3-2
  - storage nodes
    - control, 3-6 thru 3-7
    - nanotube storage nodes, 3-9
    - redox active molecules, 3-7
  - two-terminal memory devices, 3-7 thru 3-9
- Coherent electron transport
  - electrochemical potential expression, 10-3
  - self-energy parts expression, 10-3
  - through a carbon chain, 10-4
  - via HOMO, 10-2
  - via LUMO, 10-2
- Coherent Néel vector tunneling
  - doped antiferromagnetic molecular wheel, 9-10
  - satellite resonance, 9-10
  - two degenerate classical ground state, 9-9
- Computational micromagnetics
  - boundary element (BE) method, 8-7
  - finite difference (FD) method
    - Ampère field, 8-10
    - anisotropy field computation, 8-10
    - exchange field computation, 8-9
    - exchange length, 8-8
    - Langevin equation, 8-11
    - magnetostatic field computation, 8-10
    - mesh for, 8-8
    - spatial distribution field, 8-11
    - thermal field computation, 8-12
    - *vs*. FE method, 8-8
  - finite element (FE) method, 8-7 thru 8-8
  - pillar *vs*. point-contact, 8-12 thru 8-15
  - spin-transfer torque and giant magnetoresistance, 8-12 thru 8-13
- Confined metallic systems
  - chemical structure influence, 24-10 thru 24-11
  - cluster shape influence, 24-8 thru 24-9
  - dielectric function, 24-6
  - dipolar approximation, 24-10 thru 24-12
  - quantum size effects, 24-6 thru 24-8
  - quasi-static approximation/dipolar, 24-5 thru 24-6
  - scattering, absorption, and extinction, 24-4 thru 24-5
- Conformal deposition and isotropic etching, 17-15 thru 17-17
- Contact arc method, 15-5
- Control ordering and assembly processes
  - crystal growth process, 18-8
  - crystallization process, 18-8
  - full confinement factor, 18-11 thru 18-14
  - partial confinement factor, 18-9 thru 18-11
  - semicrystalline polymers morphology, 18-8
- Cooper-pair transistor (CPT)
  - aluminum and gap engineering, 16-9 thru 16-10
  - band structure
    - critical current modulation calculation, 16-5 thru 16-6
    - effective inductance modulation calculation, 16-6
    - uncertainty principle at work, 16-5
  - Coulomb blockade, 16-4 thru 16-5
  - current switching electrometry
    - quasiparticle poisoning, 16-11 thru 16-12
    - ramped switching current measurement, 16-11
    - single shot measurement, 16-12 thru 16-13
    - switching current measurement, 16-10
  - electron-beam lithography and two-angle deposition, 16-9
  - quasiparticle poisoning, 16-6 thru 16-9
  - single Josephson junction
    - Ambegaokar–Barato relation, 16-2
    - concerns specific to small junctions, 16-4
    - field emission micrograph, 16-2
    - *I–V* curve, 16-2 thru 16-3
    - RCSJ model, 16-3 thru 16-4
  - zero-biased rf electrometry
    - operation beyond 1 GHz, 16-14 thru 16-15
    - quasiparticle poisoning, 16-15
    - relation to the cooper-pair box, 16-16
    - rf measurement setup, 16-13 thru 16-14
- Coulomb blockade, 16-4 thru 16-5
- Coulomb carrier–carrier interaction, 22-6
- Crossbar process, 17-2 thru 17-3
- C$_{60}$ superconducting transistor, 7-18
- Current switching electrometry
  - quasiparticle poisoning, 16-11 thru 16-12
  - ramped switching current measurement, 16-11
  - single shot measurement, 16-12 thru 16-13
  - switching current measurement, 16-10

D

- Davydov transformation, 32-12 thru 32-13, 32-16
- Deep level transient spectroscopy (DLTS)
  - charge-selective deep level transient spectroscopy, 2-16
  - measurement principle, 2-14 thru 2-15
  - rate window and double-boxcar method, 2-15 thru 2-16
- Deep ultraviolet (DUV) lithography
  - CaF$_2$ lens elements, 19-11
  - depth of focus (DOF), 19-9 thru 19-10
  - double patterning, 19-13 thru 19-14
  - fused silica glass, 19-10
  - 193 nm immersion lithography, 19-11 thru 19-12
  - numerical aperture, 19-11
  - optical-projection lithography system, 19-9
  - photolithography exposure process, 19-9
  - plot of critical feature size, 19-10
  - ultimate resolution limits, 19-14
- Depletion capacitance, 2-13 thru 2-14
- Dipolar approximation
  - expansion coefficients, 24-11
  - extrinsic size effects, 24-12
  - incident, scattering, and internal fields, 24-11
  - quadrupolar mode, 24-12
  - vector Helmholtz wave equation, 24-10
- Dipole nanolaser, 39-9 thru 39-10
- Discharge-produced plasma EUV source, 20-9 thru 20-10
- Dissipated optical energy transfer
  - CdSe QDs, schematic images, 36-2 thru 36-3

  - dispersed substrate area, 36-3 thru 36-4
  - dynamic property of, 36-3
  - experimental results, 36-4 thru 36-5
  - exponential decay curve functions, 36-4
  - temperature dependent micro- (PL) spectroscopy, 36-2 thru 36-3
- Dissipation-controlled nanophotonic devices
  - carrier manipulation (up-converter), 33-7 thru 33-8
  - energy transfer between two quantum dots
    - density matrix formalism, 33-2 thru 33-3
    - energy diagram, 33-2
    - excitation creation, 33-5 thru 33-6
    - exciton dynamics, 33-3 thru 33-4
    - resonant coupling, 33-4
  - nanophotonic switch
    - energy diagram, 33-6
    - exciton population, 33-6 thru 33-7
    - ON- to OFF-state, 33-7
    - switching operation, 33-6
  - spatial symmetry, 33-8 thru 33-13
- Dissipative electron transport
  - contact time, 10-9
  - electron conductance *vs.* voltage, 10-10 thru 10-11
  - junction power loss, 10-11
  - phonon bath, 10-9 thru 10-10
  - through large DNA molecules, 10-10
- Domain theory, 8-2
- Donnan effect, 11-3
- Double-boxcar method, 2-15 thru 2-16
- Double exposure method, 19-24 thru 19-25
- Double patterning, 19-13 thru 19-14
- Drude expression, 26-4
- Drude model, 24-3 thru 24-4
- Dynamic random access memory (DRAM)
  - cell array structure, 2-2
  - endurance, 2-3
  - planar cell layout, 2-2 thru 2-3
  - *vs.* Flash memory, 2-4
- Dyson equation, 40-9

E

- Edge emitter laser diodes
  - microcavity lasers, 40-3 thru 40-4
  - optical gain, 40-2
  - types, 40-2
- Effective-mass approach, 40-5
- Effective near-field optical interaction
  - effective interaction Hamiltonian operator, 32-8
  - effective sample–probe-tip interaction, 32-10
  - electric displacement operator, 32-9
  - electromagnetic field correlations and intermolecular interactions, 32-6 thru 32-7
  - exciton polariton, 32-9
  - irrelevant macroscopic subsystem, 32-7 thru 32-8
  - nanomaterial system, 32-7
  - photon–electron–phonon interacting system, 32-7
  - P space and Q space, 32-8
  - Yukawa functions, 32-11
- Electromigration CNT, 3-16 thru 3-17
- Electron-beam lithography
  - cost of ownership, 19-17
  - overlay, 19-16 thru 19-17
  - resolution, 19-14 thru 19-15
  - throughput, 19-15 thru 19-16
- Electron–phonon interactions, 10-2, 10-7, 10-10
- Electron-transfer reactions, 10-13 thru 10-15
- Envelope-function approximation, 40-5
- EPR entanglement, 1-16
- EUV imaging system development, 20-2 thru 20-3
- EUVL, *see* Extreme ultraviolet lithography
- Excitation energy transfer, 35-1 thru 35-3
- Exciton–phonon–polariton (EPP) model., 35-7
- Extended boundary condition method (EBCM), 30-2
- Extreme ultraviolet lithography (EUVL)
  - alpha demo tool (ADT), 20-3
  - aspheric mirrors, 20-4
  - components, 20-1
  - defect-free blanks, 20-14
  - DPP EUV source-collector module, 20-9 thru 20-10
  - EUV device integration, 20-8 thru 20-9
  - 2008 EUV focus areas, 20-9
  - EUV masks
    - blanks, 20-10 thru 20-11
    - defectivity, 20-11 thru 20-12
    - round-trip shipment, 20-13
    - SEMI P27-1102 specifications, 20-10
    - S-pod, 20-13
  - EUV resists, 20-12
  - exposure tools
    - ASML, 20-5 thru 20-6
    - CAD model, 20-6 thru 20-7
    - interference lithography, 20-7 thru 20-8
    - scanning electron microscope (SEM) image, 20-7
    - SEMATECH Berkeley MET, 20-6 thru 20-7
    - six-mirror imaging system, 20-6
  - high-power pulsed laser, 20-1
  - immersion lithography, 20-15
  - intermediate focus, definition, 20-9
  - LPP EUV source-collector module, 20-10
  - multilayer (ML) reflective coating, 20-1, 20-3 thru 20-4
  - normal-incidence reflective optics, 20-2
  - optics and mask contamination, 20-13 thru 20-14
  - phase-shifting point-diffraction interferometer (PS/PDI), 20-5
  - projection optics, 20-2 thru 20-3
  - Rayleigh equation, 20-14 thru 20-15

F

- Fabry–Perot cavity, 7-6
- Feedback-controlled nanocantilevers, 3-12 thru 3-13
- Fermi Golden rule, 21-6
- Ferroelectricity fundamentals
  - ferroelectric correlation length, 6-4
  - ferroelectric hysteresis loops, 6-4
  - perovskite oxide BaTiO3 unit cell, 6-3
  - phenomenological definition, 6-2
  - second-order ferroelectric phase transition, 6-3
  - thermodynamic theory, 6-3
- Ferroelectric RAM (FeRAM), 2-4 thru 2-5
- Ferromagnetic islands
  - experimental techniques, 4-5
  - ferromagnetic domains, 4-2 thru 4-3
  - ferromagnetic dots
    - longitudinal Bragg MOKE, 4-8 thru 4-9
    - micromagnetic simulation results, 4-7 thru 4-8
    - nucleation and annihilation field, 4-7
    - permalloy dots array, 4-7
  - ferromagnetic rings, 4-9
  - ferromagnetic spirals, 4-10 thru 4-11
  - ferromagnetism, 4-1 thru 4-2
  - hysteresis loops, 4-3
  - magnetostatic interactions
    - honeycomb structure, 4-13
    - onion state, 4-12
    - open frame system, 4-11
    - Py dipole arrays, 4-12 thru 4-13
    - spin ice state, 4-11
    - symmetrical stable remanent states, 4-12
  - micromagnetic simulations, 4-3 thru 4-5
  - noncircular rings, 4-9 thru 4-10
  - rectangular and elliptical islands, 4-6 thru 4-7
  - sub-micrometer-sized island preparation, 4-5
- Ferromagnetic molecular magnets, 9-1
- Ferromagnetic rings, 4-9
- Ferromagnetic spirals, 4-10 thru 4-11
- Fick's first law, 11-3 thru 11-4
- Figure of merit (FOM), 35-5
- Finite difference (FD) method, LLGS
  - Ampère field, 8-10
  - anisotropy field computation, 8-10
  - exchange field computation, 8-9
  - exchange length, 8-8
  - Langevin equation, 8-11
  - magnetostatic field computation, 8-10
  - mesh for, 8-8
  - spatial distribution field, 8-11
  - thermal field computation, 8-12
  - *vs.* FE method, 8-8
- Flash memories
  - electron per cell *vs.* feature size, 2-4
  - schematic band structure, 2-3
  - *vs.* DRAM, 2-4

- Floating nano-dots, 5-2
- Fluctuation-dissipation theorem, 8-11
- Fokker–Planck equation, 8-11
- FOM, *see* Figure of merit
- Förster type interaction, 33-3
- Fourier transform, 32-2
- Fowler–Nordheim tunneling, 6-11
- Fractal nanotechnology
  - fractals in nature, 17-12 thru 17-13
  - producing nanoscale fractals via S^nPT_x, 17-13 thru 17-14
- Franck–Condon factor, 10-13, 10-15
- Fuhrer's device, 3-4
- Fullerene (C_{60})
  - discovery of, 15-4 thru 15-5
  - FET
    - Bell Laboratory misconduct, 15-2 thru 15-3
    - characterization on SiO_2/AlN, 15-19 thru 15-20
    - fabrication of, 15-18 thru 15-19
    - field effect doping, 15-3
    - operation principles, 15-3 thru 15-4
    - solid C_{60} and insulator films interface, 15-3
    - superconductivity, 15-4
  - MBE, 15-10 thru 15-11
  - micro-clusters, 15-1
  - properties of, 15-5 thru 15-7
  - solid crystals, 15-1 thru 15-2
    - absorption and luminescence spectra, 15-8
    - crystal structure, 15-7
    - electronic structures, 15-7 thru 15-8
    - optical measurements results, 15-9
    - photo-conducting spectra, 15-10
    - photoluminescence spectrum, 15-8
    - structural phase transition, 15-7
    - third nonlinear susceptibility, 15-9
    - van der Waals interaction, 15-7
  - synthesis of, 15-5
  - van der Waals epitaxy (*see* van der Waals epitaxy)
- Fullerene-based superconducting weak links, 7-17 thru 7-18
- Full-width at half-maximum (FWHM), 35-8
- Fully depleted silicon-on-insulator (FDSOI) devices, 12-3

G

- Gas evaporation method, 15-5
- Giant magnetoresistance (GMR), 8-12 thru 8-13, 13-5
- Graphene-based superconducting weak links
  - proximity effect, 7-15 thru 7-17
  - SQUIDs devices, 7-17
- Graphene ribbon nanotransistors, 12-7 thru 12-8
- Grover algorithm, 1-9 thru 1-12

H

- Half pitch scaling, 19-4
- Hamiltonian model, 32-11 thru 32-12
- Heisenberg's uncertainty principle, 32-1
- Hellmann–Feynman theorem, 27-5
- Helmholtz equation, 32-4
- Hierarchical memory retrieval, 34-7 thru 34-8
- Horseshoe optical nanoantenna., 39-9
- Hot-carrier diode, 13-1
- Hybrid nanostructures
  - absorption spectrum, 38-14 thru 38-15
  - AFM characterization, gold nanoparticle, 38-14 thru 38-15
  - borohydride method, 38-13
  - bridge molecules, 38-15
  - dialyze, 38-14
  - factual spectrum, 38-17
  - gold nanoparticles spectrum, 38-14
  - schematic composition, 38-13
  - spectral characteristics, 38-17
  - water colloidal suspension, silver nanoparticles, 38-15 thru 38-16

I

- III–V semiconductor quantum dots
  - self-organized quantum dots
    - based nanomemories, 2-10
    - carrier emission process, 2-9
    - electron and hole states, 2-9
    - fabrication, 2-8
  - semiconductor material hetereostructure, 2-7 thru 2-8
- 193 nm Immersion lithography
  - DUV lithography, 19-11 thru 19-12
  - photoresist technology, 19-8
- Imprint lithography (IL), 17-3 thru 17-4
- Incoherent Zener tunneling, 9-7 thru 9-8
- Inelastic electron transport
  - Buttiker model, 10-5 thru 10-6
  - coherent transport
    - curves, 10-4 thru 10-5
    - electrochemical potential expression, 10-3
    - self-energy parts expression, 10-3
    - through a carbon chain, 10-4
    - via HOMO, 10-2
    - via LUMO, 10-2
  - dissipative transport
    - contact time, 10-9
    - electron conductance *vs.* voltage, 10-10 thru 10-11
    - junction power loss, 10-11
    - phonon bath, 10-9 thru 10-10
    - through large DNA molecules, 10-10
  - molecular junction conductance and long-range reactions, 10-13 thru 10-15
  - polaron effects, 10-11 thru 10-13
  - vibration-induced inelastic effects
    - electron transmission *vs.* energy, 10-7
    - electron–vibron interaction, 10-6 thru 10-07
    - inelastic electron tunneling spectrum, 10-8 thru 10-9
    - polaronic shift, 10-7
- Inelastic electron tunneling spectrum (IETS), 10-8 thru 10-9
- InGaAs/GaAs quantum dots
  - carrier storage, 2-17
  - with additional AlGaAs barrier, 2-18 thru 2-20
- Intensity-dependent refractive index (IDRI), 27-2
- Interband transitions, 40-11
- Intrinsic size effects
  - dielectric function, 24-6
  - quantum size effects
    - absorption cross section *vs.* energy, 24-7
    - jellium model, 24-7
    - Mie theory, 24-6
    - plasmon angular frequency, 24-8
- Iridoviruses, 31-7

J

- Jaynes–Cummings model, 1-6 thru 1-7
- Josephson weak link, 7-2 thru 7-3

K

- Kohn–Sham equation, 24-7
- Kohn–Sham matrix, 27-4
- Kuhn segment, 18-11

L

- Landau–Ginzburg–Devonshire theory, 6-1 thru 6-2
- Landau–Lifshitz–Gilbert–Slonczewski (LLGS) equation
  - general form, 8-6
  - solution based on FD method
    - Ampère field, 8-10
    - anisotropy field computation, 8-10
    - exchange field computation, 8-9
    - exchange length, 8-8
    - Langevin equation, 8-11
    - magnetostatic field computation, 8-10
    - mesh for, 8-8
    - spatial distribution field, 8-11
    - thermal field computation, 8-12
    - *vs.* FE method, 8-8
- Landau–Zener model, 9-7
- Langevin equation, 8-11
- Laser emission properties
  - microscopic generalization, semiconductor effects, 40-14 thru 40-15
  - photon statistics modifications, 40-15 thru 40-16
  - rate equations description, 40-13 thru 40-14
- Laser-produced plasma EUV source, 20-10

Laser-vaporization cluster beam mass spectroscopy, 15-4
Lawrence Berkeley National Laboratory (LBNL), 20-3
Lift-off technique, 6-7
Linear bearing nanoswitch, 3-14 thru 3-16
Liouville equation, 33-3
Localized surface plasmons (LSPs), 28-5
Loss–DiVincenzo proposal
  RKKY interaction, 1-8 thru 1-9
  using quantum dots and electric gates, 1-7 thru 1-8
Low-dimensional sp^2 carbon structures, 7-4 thru 7-5
Low-energy cluster beam deposition (LECBD), 24-13
Low linewidth enhancement factor, 41-8

M

Macroscopic polarization, 40-11
Magnetically ordered materials, 8-1 thru 8-2
Magnetic-metallothionein (mMT), 11-2
Magnetic protein folding
  Donnan effect, 11-3
  first-order-like state transition model, 11-3
  of Mn,Cd-MT, 11-2
  protein folding phase diagram, 11-4
  quasi-static thermal equilibrium dialysis, 11-5 thru 11-6
  self-assemble, 11-5
  three well model, 11-4
Magnetocrystalline anisotropy, 4-4
Magnetoresistive RAM, 2-5
Mask Blank Development Center (MBDC), 20-11
Maxwell–Garnett theory, 24-14
MBE, *see* Molecular beam epitaxy
Metal and semiconductor nanowire
  dipole orientation, 26-8
  frequency dispersion, 26-10
  Gaussian properties, 26-11
  linear optical phenomena, 26-9
  nonlinear polarization, 26-8
  plasmon resonance, 26-10
  radiation pattern, 26-9
  second harmonic generation (SHG), 26-7 thru 26-8
  SHG angular distribution, 26-10
Metal clusters and nanoparticles
  alkali clusters, 24-15 thru 24-16
  bimetallic cluster
    annealed alloy measurement, 24-19
    dielectric function, 24-19
    gold–silver alloy nanoparticle, 24-19 thru 24-20
    low energy ion scattering (LEIS) measurement, 24-20
    Ni–Ag cluster optical absorption spectra, 24-20 thru 24-21
  bulk metals
    conduction band, 24-2 thru 24-3
    dielectric function, 24-3
    Drude dielectric function, 24-4
    intraband and interband transition, 24-3
    Kramers–Kronig relationship, 24-4
    plasma frequency, 24-3
  cluster source, 24-2
  confined metallic systems, optical properties
    chemical structure influence, 24-10 thru 24-11
    cluster shape influence, 24-8 thru 24-9
    dielectric function, 24-6
    dipolar approximation, 24-10 thru 24-12
    quantum size effects, 24-6 thru 24-8
    quasi-static approximation/dipolar, 24-5 thru 24-6
    scattering, absorption, and extinction, 24-4 thru 24-5
  dielectric confinement, 24-2
  electronic shells, 24-1
  minute metal spheres, 24-2
  nanoparticle synthesis
    chemical methods, 24-12 thru 24-13
    physical methods, 24-13 thru 24-14
  noble metal clusters
    discrete dipole approximation, 24-19
    gold clusters, 24-17
    jellium model, 24-18
    silver clusters, 24-17
    SPR, 24-16 thru 24-17
    TDLDA, 24-18
  optical spectroscopy, 24-14 thru 24-15
  single nanoparticle, 24-2
  spectroscopic techniques, 24-2
Metallic dot
  capacitance and coupling coefficient, 5-3 thru 5-4
  influence of polarization
    coupling coefficient analytical expression, 5-6 thru 5-7
    dielectric medium potential, 5-7
  method of images, 5-4 thru 5-5
  numerical implementation
    invertible matrix, 5-7
    vs. classical approximation, 5-7 thru 5-9
  semi-analytical expression for capacitance
    B_1 coefficients expression, 5-4 thru 5-5
    capacitance matricial expression, 5-6
    partial capacitance expression, 5-6
  semi-analytical expression for potential, 5-6
Metal nanolayer-base transistor
  band diagram
    band banding conditions, 13-1
    Co/Si-n Schottky diode characteristics, 13-2
    hot-carrier diode, 13-1
    MS contacts, 13-1 thru 13-2
    TE theory, 13-2
  fabrication
    atomic arrangement, 13-4 thru 13-5
    dependency of the current gain, 13-7
    epitaxial growth, 13-4
    glow discharge-deposition process, 13-4
    magnetic multilayers, 13-5 thru 13-6
    organic semiconductor as top layer, 13-6
    test of dependency, 13-7
  J–V characteristic, 13-3 thru 13-4
Metal nanostructures
  allowed and forbidden second harmonic emission modes
    laterally limited light beam, 28-10 thru 28-11
    plane-wave illumination, 28-9 thru 28-10
  emission patterns and light polarization, 28-8 thru 28-9
  field enhancements, 28-1
  lightning rod effects, 28-1
  second harmonic generation
    nanoparticles, 28-5 thru 28-8
    nanosystems, 28-3 thru 28-5
    nonlinear optics, 28-2 thru 28-3
    single gold nanoparticles, 28-11 thru 28-15
  two-photon photo-luminescence (TPPL) yield, 28-15
Metal-semiconductor (MS) junction, 13-1
Microcavity lasers, 40-3
Micromagnetic theory, 8-2
Mie nanolasers, 39-11
Mie theory, 24-6, 24-10, 24-12
Mode-locked quantum-dot lasers
  advantages, 41-5 thru 41-8
  basics, 41-2
  excited-state transitions, 41-9
  passive mode locking, physics and devices, 41-3
  pulse duration, 41-8
  pulse repetition rates, 41-9
  requirements, 41-3 thru 41-4
  self-phase modulation and dispersion, 41-4 thru 41-5
  semiconductor lasers, 41-2
  temperature resilience, 41-9
Molecular beam epitaxy (MBE), 6-5 thru 6-6
  C_{60}, 15-10 thru 15-11
Molecular junction conductance, 10-13 thru 10-15
Molecular magnets preparation
  magnetic properties, molecular nanostructures, 11-10 thru 11-11
  magnetic protein folding
    Donnan effect, 11-3
    first-order-like state transition model, 11-3
    of Mn,Cd-MT, 11-2
    protein folding phase diagram, 11-4
    quasi-static thermal equilibrium dialysis, 11-5 thru 11-6
    self-assemble, 11-5
    three well model, 11-4

  nanostructured semiconductor templates
    direct inkjet and mold imprinting, 11-7
    nanopatterned SAMs for 3D fabrication, 11-7 thru 11-8
    patterned self-assembly, 11-6 thru 11-7
  self-assembling growth
    patterned magnetic molecules, AFM, 11-8
    patterned MT molecules, AFM, 11-9
    Si template, SEM image, 11-9
Molecular nanomagnets
  coherent Néel vector tunneling
    doped antiferromagnetic molecular wheel, 9-10
    satellite resonance, 9-10
    two degenerate classical ground state, 9-9
  incoherent Zener tunneling in Fe$_8$, 9-7 thru 9-8
  phonon-assisted spin tunneling in Mn$_{12}$ acetate, 9-5
  single-molecule magnet transistors, 9-11 thru 9-12
  spin tunneling
    anticrossing of adiabatic eigenvalues, 9-3
    Berry's phase and path integrals (*see* Berry's phase interference)
    generalized master equation, 9-4
    Pauli or master equation, 9-3 thru 9-4
    Rabi oscillation, 9-3
    spin Hamiltonian, 9-2
    uniaxial anisotropy, 9-2
Molecular transistors, 7-18
Molecular tunnel junctions, 12-9 thru 12-11
Monte Carlo simulation, 24-20
Moore's law, 12-1 thru 12-2
Multiferroic tunnel junction, 6-18
Multilayer polymeric structures
  bacteriorhodopsin suspension preparation, 38-8
  basic elements, 38-7 thru 38-8
  containing mixture, 38-8 thru 38-9
  cyclicity processes, 38-5 thru 38-6
  data transmission and processing, 38-6
  element base adaptability, 38-6
  expected parameters, 38-7
  fragments, 38-7
  property, 38-9 thru 38-10
  requirements, 38-8
Multilayer (ML) reflective coating, 20-1, 20-3 thru 20-4
Multispacer patterning technique
  abstract technology
    bodies and surfaces, 17-15
    conformal deposition and isotropic etching, 17-15 thru 17-17
    directional processes, 17-17 thru 17-18, 17-18
  additive route—S^{n}PT$_+$, 17-5 thru 17-7
  addressing cross-point, 17-10 thru 17-11
  concrete technology, 17-18 thru 17-19
  crossbar-architecture fabrication steps, 17-2
  crossbar comparison, 17-11 thru 17-12
  electronics application, 17-12
  energetics application, 17-12
  fractal nanotechnology
    fractals in nature, 17-12 thru 17-13
    producing nanoscale fractals via S^{n}PT$_x$, 17-13 thru 17-14
  multiplicative route—S^{n}PT$_x$, 17-8 thru 17-9
  nonlithographic nanowire preparation
    imprint lithography (IL), 17-3 thru 17-4
    spacer patterning technique (SPT), 17-4 thru 17-5
  three-terminal molecules, 17-9 thru 17-10

N

Nano-dot, *see* Spherical dot in plate capacitor
Nanoelectromechanical systems (NEMS) based memory
  capacitive force response, 3-9
  feedback-controlled nanocantilevers, 3-12 thru 3-13
  linear bearing nanoswitch, 3-14 thru 3-16
  nanorelays, 3-11 thru 3-12
  nonvolatile random access memory, 3-10 thru 3-11
  properties, 3-9
  vertically aligned carbon nanotubes, 3-13 thru 3-14
Nanoelectronics lithography
  advanced lithographic processes
    CD-SAXS, 19-27
    CD-scanning electron microscopy (CD-SEM), 19-26
    double exposure method, 19-24 thru 19-25
    ellipsometry measurements, 19-26
    line edge roughness measurement, 19-27
    overlay measurements, 19-27
    scatterometry measurements, 19-26
    spacer double patterning method, 19-25
  DUV lithography
    CaF$_2$ lens elements, 19-11
    depth of focus (DOF), 19-9 thru 19-10
    double patterning, 19-13 thru 19-14
    fused silica glass, 19-10
    193 nm immersion lithography, 19-11 thru 19-12
    numerical aperture, 19-11
    optical-projection lithography system, 19-9
    photolithography exposure process, 19-9
    plot of critical feature size, 19-10
    ultimate resolution limits, 19-14
  electron-beam lithography
    cost of ownership, 19-17
    overlay, 19-16 thru 19-17
    resolution, 19-14 thru 19-15
    throughput, 19-15 thru 19-16
  NIL
    defect inspection and dimensional metrology, 19-22
    functional materials, 19-19
    nanoimprint materials development, 19-21
    overlay accuracy and control, 19-23
    residual layer control, 19-22 thru 19-23
    technology examples, 19-23 thru 19-24
    template fabrication and availability, 19-21 thru 19-22
    thermal NIL, 19-18 thru 19-19
    tool types, 19-19 thru 19-20
    transfer printing, 19-19
    UV NIL, 19-19
  photoresist technology
    base quencher additives, 19-6 thru 19-7
    EUV lithography, 19-8
    line and space pattern, 19-4 thru 19-5
    material structure advances, 19-7 thru 19-8
    193 nm immersion lithography, 19-8
    photolysis process of photoacid generator, 19-5 thru 19-6
    positive and negative tone resist, 19-4
    residual swelling fraction, 19-7
    resist materials, 19-4 thru 19-5
Nanofibers, light scattering
  angular distribution, 30-9
  cylindrical nanofiber diffraction
    Bessel function, 30-4
    electromagnetic field components, 30-3
    Fourier-transformed amplitudes, 30-5 thru 30-6
    incident beam polarization, 30-4 thru 30-5
    incident wave electric field, 30-3
    inverse Fourier transform, 30-4
  definition, 30-1
  dispersion curves, 30-12
  exciton resonance excitation, 30-10 thru 30-11
  Fresnel reflection coefficient, 30-2
  Hankel functions, 30-1
  He-Cd laser, 30-11
  ideal surface reflection, 30-8 thru 30-9
  inorganic semiconductor materials, 30-1
  multiple-scattering linear equation, 30-2
  normal modes, 30-6
  optical process, 30-1
  photoluminescence measurement, 30-12
  photomultiplier, 30-11
  polarization properties, 30-12
  pulsed Gaussian light beam, 30-12
  scattered field calculation, 30-6 thru 30-8
  scattered light intensity, 30-12
  scattering efficiency, 30-2

  - T-matrix method, 30-2
  - total scattered intensity *vs.* frequency, 30-10
  - total scattered intensity *vs.* incidence angle, 30-9 thru 30-10
- Nanoimprint lithography (NIL)
  - cavity fill process, 18-4 thru 18-5
  - control ordering and assembly processes
    - crystal growth process, 18-8
    - crystallization process, 18-8
    - full confinement factor, 18-11 thru 18-14
    - partial confinement factor, 18-9 thru 18-11
    - semicrystalline polymers morphology, 18-8
  - defect inspection and dimensional metrology, 19-22
  - functional materials, 19-19
  - functional materials nanoshaping
    - antireflective structure creation, 18-6
    - biomaterial shaping, 18-6 thru 18-7
    - interface shaping, 18-5
    - nanopore generation, 18-5
    - optical grating creation, 18-5 thru 18-6
  - imprinting resists, 18-4
  - molds in, 18-4
  - nanoimprint materials development, 19-21
  - overlay accuracy and control, 19-23
  - residual layer control, 19-22 thru 19-23
  - resolution limit, 18-4
  - technology examples, 19-23 thru 19-24
  - template fabrication and availability, 19-21 thru 19-22
  - thermal NIL, 19-18 thru 19-19
  - for thermoplastic polymers, 18-3
  - tool types, 19-19 thru 19-20
  - transfer printing, 19-19
  - UV NIL, 19-19
- Nanolasers
  - applications, 39-12
  - definition, 39-5
  - laser radiation property, 39-1 thru 39-2
  - nanowire, 39-5 thru 39-8
  - organic nanolasers, 39-11
  - overview, 39-2
  - photonic crystal lasers, 39-10
  - plasmonic lasers, 39-8 thru 39-10
  - rate equation approach, 39-4 thru 39-5
  - scattering lasers, 39-10 thru 39-11
  - semiconductor lasers, 39-2 thru 39-4
- Nanomaterials
  - cathodoluminescence
    - band structure, types, 21-2
    - donor–acceptor pair transition, 21-2
    - exciton, 21-3
    - recombination process, 21-2
    - TEM-CL (*see* Transmission electron microscope-cathodoluminescence)
  - kinetic energy, 21-8 thru 21-9
  - optical spectroscopy
    - global photoluminescence, 22-1
    - luminescence hole-burning (LHB) spectroscopy, 22-1
    - luminescence spectra, 22-1 thru 22-2
    - multiexciton generation, 22-6 thru 22-7
    - nanoparticle quantum dots, 22-4 thru 22-6
    - optical properties, 22-1
    - semiconductor nanoparticles, 22-1
    - single molecule spectroscopy, 22-2
    - SWNT (*see* Single-walled carbon nanotube)
  - photoluminescence (PL), 21-1 thru 21-2
  - quantum well, 21-9 thru 21-10
  - quantum wire
    - density of states, 21-10
    - electron wavefunction, 21-10
    - hole wave-functions, 21-11
    - homogeneous electric field, 21-13
    - intensity and polarization ratio, 21-14 thru 21-15
    - Luttinger–Kohn Hamiltonian, 21-11
    - optical absorption, 21-14
    - photoluminescence excitation (PLE) spectrum, 21-13
    - polarization anisotropy, 21-11
    - quantum confinement effect, 21-12 thru 21-13
    - transition matrix element, 21-12 thru 21-13
  - semiconductor quantum structures, optical properties
    - Bloch function, 21-5
    - conversion matrix, 21-6
    - light emission theory, 21-6 thru 21-7
    - Luttinger–Kohn Hamiltonian, 21-5
    - polarization, 21-7 thru 21-8
  - semiconductor quantum wires, 21-1
  - transmission electron microscope (TEM), 21-1 thru 21-2
- Nanomemories
  - based on III–V semiconductor QD, 2-7 thru 2-10 (*see also* Quantum dot memories)
  - semiconductor
    - charge trap memories, 2-6 thru 2-7
    - single electron memories, 2-7
- Nanometer-sized ferroelectric capacitors
  - characterization of films and capacitors
    - *P-E* hysteresis loop measurements, 6-10 thru 6-11
    - RBS, 6-8
    - scanning probe techniques, 6-11 thru 6-13
    - XRD, 6-8 thru 6-10
  - deposition techniques
    - combinatorial PLD and MBE systems, 6-8
    - MBE, 6-5 thru 6-6
    - PLD, 6-6
    - sputter deposition, 6-6 thru 6-7
  - ferroelectricity fundamentals
    - ferroelectric correlation length, 6-4
    - ferroelectric hysteresis loops, 6-4
    - perovskite oxide BaTiO3 unit cell, 6-3
    - phenomenological definition, 6-2
    - second-order ferroelectric phase transition, 6-3
    - thermodynamic theory, 6-3
  - low-temperature superconducting Josephson junctions, 6-18 thru 6-19
  - multiferroic tunnel junction, 6-18
  - novel functional oxide tunnel junctions, 6-18
  - patterning
    - electron beam lithography, 6-8
    - lift-off technique, 6-7
    - photo-mask steps, 6-8
  - physical phenomena
    - depolarizing-field effect, 6-15 thru 6-16
    - intrinsic size effect, ultrathin films, 6-17
    - strain effect, 6-14 thru 6-15
  - "research triangle," 6-1 thru 6-2
  - tunneling magnetoresistance (TMR), 6-18
- Nanoparticle quantum dots
  - Au nanoparticles, 22-6
  - CdSe/ZnS nanoparticles, 22-4 thru 22-5
  - close-packed monolayer films, 22-5
  - decay times, 22-5 thru 22-6
  - enhancement and quenching phenomena, 22-5
  - light-emitting neutral nanoparticle, 22-4
  - PL blinking phenomena, 22-4
  - unique exciton energy transfer, 22-5
- Nanophotonic buffer memory, 33-11 thru 33-12
- Nanophotonic devices
  - AND-gate, ZnO nanorod
    - electronic carrier penetration, 36-10
    - exciton–phonon couplings, 36-7 thru 36-8
    - exciton populations, 36-9
    - input laser llumination, 36-11
    - micro-channel plate, 36-7
    - near-field spectroscopy, 36-7 thru 36-8
    - nutation frequency evaluation, 36-10
    - schematic depict, SQW, 36-9
    - single-quantum-well structures(SQW), 36-7 thru 36-8
    - switching operation, 36-10 thru 36-11
  - dissipation-controlled nanophotonic devices
    - carrier manipulation (up-converter), 33-7 thru 33-8
    - energy transfer between two quantum dots, 33-2 thru 33-5
    - nanophotonic switch, 33-5 thru 33-7
  - operation
    - excitation energy transfer, 35-1 thru 35-3
    - nanophotonic AND gate, 35-4 thru 35-5
    - nanophotonic NOT gate, 35-5 thru 35-6
    - photonic devices interconnection, 35-6 thru 35-7

- quantum dot materials
  - controlling the energy transfer, 36-4 thru 36-6
  - discrete energy levels, 36-1 thru 36-2
  - dissipated optical energy transfer, 36-2 thru 36-4
  - near-filed optically coupled ZnO QDs, 36-4 thru 36-7
- schematic representation, 33-2
- using spatial symmetries
  - AND- and XOR-logic gates, 33-10 thru 33-11
  - nanophotonic buffer memory, 33-11 thru 33-12
  - quantum entangled states manipulation, 33-12 thru 33-13
  - selective energy transfer, 33-9 thru 33-10
  - symmetric and antisymmetric states, 33-8 thru 33-9

Nanophotonics
- devices (*see* Nanophotonic devices)
- fabrication
  - NFO-CVD (*see* Nonadiabatic near-field optical CVD)
  - nonadiabatic near-field photolithography, 35-10 thru 35-11
- hierarchical architectures
  - memory retrieval, 34-7 thru 34-9
  - physical and functional, 34-6 thru 34-7
  - unscalable design, 34-8 thru 34-10
- optical excitation transfer (*see* Optical excitation transfer)
- parallel architecture
  - broadcast interconnects, 34-4 thru 34-5
  - global summation, 34-4
  - memory-based architecture, 34-3 thru 34-4
  - secure signal transfer, 34-5 thru 34-6
- switch
  - energy diagram, 33-6
  - exciton population, 33-6 thru 33-7
  - ON- to OFF-state, 33-7
  - switching operation, 33-6
- versatile functionalities, 34-10 thru 34-12
- waveguides (*see* Nanophotonic waveguides)

Nanophotonic waveguides
- active lossy waveguides
  - cladding layer, 37-9
  - double-peak structure, 37-11
  - electric field intensity, 37-10
  - Fresnel formulae, 37-10
  - substrate modes, 37-12
  - TE–TM splitting, 37-11
- active Si-nc waveguides
  - direct facet-coupling, 37-8 thru 37-9
  - PL spectra, 37-7 thru 37-8
  - prism coupling, 37-8
  - refractive index, 37-7
- external source light propagation, 37-5
- internal photoluminescence propagation, 37-4 thru 37-5
- losses and optical amplification
  - insertion (coupling) loss, 37-5
  - loss measurement methods, 37-5 thru 37-6
  - propagation loss, 37-5
  - pump-and-probe (PP) method, 37-5, 37-7
  - shifting excitation spot (SES) method, 37-5 thru 37-6
  - variable stripe-length (VSL) method, 37-5 thru 37-7
- nanocrystalline waveguides
  - light amplification, 37-12 thru 37-13
  - optical couplers, 37-14
  - photonic circuits, 37-13
  - PL spectra, 37-13
- planar and rib waveguide fabrication
  - advantages, 37-4
  - cladding layers, 37-3
  - fused quartz implantation, 37-2 thru 37-3
  - optical transparent matrix, 37-2
  - reactive silicon deposition, 37-3
  - SiO_2 film, 37-3
  - spectral filtering, 37-2
- silicon nanophotonics, 37-1 thru 37-2

Nanorelays, 3-11 thru 3-12

Nanoscale excitons
- definition, 23-1
- density of states, 23-2 thru 23-3
- electron-hole attraction, 23-1
- electron quantum confinement, 23-4
- exciton-binding energy, 23-4
- extended bulk system, 23-5
- Frenkel excitons, 23-1
- optical properties, semiconductor nanostructure, 23-2
- semiconductor quantum dots
  - nonlinear optical properties, 23-5 thru 23-6
  - two-photon absorption (2PA), 23-6 thru 23-8
- single-wall carbon nanotube (SWCNT), 23-4 thru 23-5
- spatial electron confinement, 23-3 thru 23-4
- Wannier–Mott excitons, 23-1

Nanoscale spin valves
- anisotropic effects, 8-4
- computational micromagnetics (*see* Computational micromagnetics)
- energy balance and free energy functional formulation, 8-5
- equation of motion, 8-5 thru 8-6
- exchange interactions, 8-4
- external bias field, 8-5
- magnetization vector, 8-3 thru 8-4
- magnetostatic interactions, 8-4 thru 8-5
- spin-transfer torque effects, 8-6 thru 8-7

Nanoshaping functional materials
- antireflective structure creation, 18-6
- biomaterial shaping, 18-6 thru 18-7
- interface shaping, 18-5
- nanopore generation, 18-5
- optical grating creation, 18-5 thru 18-6

Nanotube-based superconducting quantum interferometers
- magnetometry applications, 7-13 thru 7-14
- quantum information applications, 7-14 thru 7-15
- quantum interference with weak links, 7-10 thru 7-11
- tunability of the phase shift, 7-11 thru 7-12

Nanowire lasers
- basic properties, 39-6
- cavity structure, 39-8
- GaN nanowire cross section, 39-8
- ring resonator, 39-6 thru 39-7
- schematic representation, 39-5 thru 39-6

N_2 atmospheric train-sublimation method, 15-5 thru 15-6

Near-field optically coupled ZnO QDs
- energy diagram, 36-6
- growth time dependence, 36-5
- TEM image, 36-5 thru 36-6
- time constants dependence, 36-7
- time-resolved PL intensity, 36-5, 36-7

Near-field photoluminescence (NFPL), 36-7

Negative differential resistance (NDR), 10-13

Nonadiabatic near-field optical CVD (NFO-CVD), 35-7
- electron potential curves, 35-9
- photodissociation, 35-7
- photon flux relationship, 35-9
- sapphire substrate, 35-8
- shear-force topographical images, cross section, 35-7 thru 35-8

Nonadiabatic photolithography, 35-10

Noncircular rings, 4-9 thru 4-10

Nonconventional semiconductor memories
- FeRAM, 2-4 thru 2-5
- magnetoresistive RAM, 2-5
- PCRAM, 2-5 thru 2-6

Nonlinear optics
- average Hirshfeld charge, 27-11
- cadmium selenide clusters ($(CdSe)_n$), 27-5
- cluster materials, 27-5
- density functional theory (DFT), 27-9
- Douglas–Kroll approximation, 27-10
- electric dipole moment, 27-1
- excitation frequency, 27-11 thru 27-12
- frequency-dependent optical polarizability, 27-6
- frequency variation, 27-6 thru 27-8
- generalized-gradient approximation (GGA) technique, 27-6
- hyperpolarizability tensor, 27-1
- inorganic materials, 27-5
- intensity-dependent refractive index (IDRI), 27-2
- lithium tetramer, 27-10
- mean dipole polarizability, 27-5 thru 27-6
- mean second-order hyperpolarizability, 27-9 thru 27-10

  - metallic cluster, 27-5
  - mixed metal cluster, 27-11
  - nanocluster, 27-9
  - Nd:YAG laser frequency, 27-9
  - organic materials, 27-5
  - quantum formulation
    - average polarizability tensor, 27-4
    - density matrix, 27-3
    - dipole interaction model, 27-2
    - frequency-dependent response properties, 27-5
    - Kohn–Sham equation, 27-3
    - Lagrangian multiplier matrix, 27-4
    - Taylor expansion, 27-4
    - time-dependent density-functional theory (TDDFT), 27-3
    - two-state model, 27-2
  - second-order hyperpolarizability tensor, 27-12
  - second-order nonlinear polarization, 27-2
  - semiconducting cluster, 27-5
  - of semiconductor nanostructures (*see* Semiconductor nanostructures)
  - symmetrized fragment orbitals (SFO), 27-11
  - time-dependent Hartree–Fock (TDHF) method, 27-9
- Nonlithographic nanowire preparation
  - imprint lithography (IL), 17-3 thru 17-4
  - spacer patterning technique (SPT), 17-4 thru 17-5
- Nonplanar multi-gate transistors, 12-3 thru 12-4
- Nonvolatile memories (NVM), *see* Flash memories

O

- Optical excitation transfer
  - parallel architecture
    - broadcast interconnects, 34-4 thru 34-5
    - global summation, 34-4
    - memory-based architecture, 34-3 thru 34-4
    - secure signal transfer, 34-5 thru 34-6
  - via optical near-field interactions
    - global summation, 34-2 thru 34-3
    - light–matter interactions, 34-2
- Optical nanofountain, 35-6 thru 35-7
- Optical near-field (ONF), 34-10 thru 34-12
  - coupling strength, 33-4 thru 33-7
  - ONF system, 32-6 thru 32-7
- Optical neuronets
  - basic elements, multilayered structures, 38-7 thru 38-8
  - cyclicity processes, 38-5 thru 38-6
  - data processing, 38-6
  - element base parameters, 38-7
  - light fluxes formation, 38-6
  - multilayered constructions, 38-7
  - polymeric film property, 38-9 thru 38-10
  - polymeric film requirements, 38-8
  - polymeric mixture preparation, 38-8 thru 38-9
  - suspension preparation, 38-8
- Optical-projection lithography system, 19-9
- Optical spectroscopy
  - luminescence hole-burning (LHB) spectroscopy, 22-1
  - luminescence spectra, 22-1 thru 22-2
  - multiexciton generation, 22-6 thru 22-7
  - nanoparticle quantum dots, 22-4 thru 22-6
  - optical properties, 22-1
  - semiconductor nanoparticles, 22-1
  - single molecule spectroscopy, 22-2
  - SWNT (*see* Single-walled carbon nanotube)
- Optical transition matrix element, 21-7
- Organic FET
  - am-bipolar operations, 15-17 thru 15-18
  - device structures, 15-16
  - field effect doping, 15-17
  - metal/organic layer interface, 15-16 thru 15-17
- Organic nanolasers, 39-11
- Ovonic unified memory (OUM), *see* Phase-change RAM

P

- Passivation, 14-7 thru 14-9
- Passive mode locking
  - physics and devices, 41-3
  - requirements, 41-3 thru 41-4
- Pauli equation, 9-3 thru 9-4
- Phase-change RAM (PCRAM), 2-5 thru 2-6
- Phase-matching condition, 28-3
- Phase-shifting point-diffraction interferometer (PS/PDI), 20-5
- Phonon-assisted spin tunneling, Mn$_{12}$ acetate, 9-5
- Photolithography, 18-1 thru 18-3; *see also* Nonadiabatic photolithography
- Photoluminescence (PL)
  - energy-band diagram, 25-1 thru 25-2
  - photon momentum, 25-1
  - porous silicon (PS), 25-2
  - quantum confinement (QC) model, 25-2
  - quantum size effects, 25-3
  - silicon nanostructures
    - Arrhenius plot, 25-11
    - confinement energy, 25-8
    - co-sputtered SiNC, 25-7 thru 25-8
    - Coulomb exchange interaction, 25-11
    - dynamical characteristics, 25-10
    - excitons, 25-8
    - *f*-sum rule/Thomas–Reiche–Kuhn sum rule, 25-13
    - nanocrystal size distribution, 25-12 thru 25-13
    - nonradiative process, 25-14 thru 25-15
    - optical characterizations and luminescence bands, 25-7
    - oscillator strength *vs.* confinement energy, 25-13 thru 25-14
    - PL decay time, 25-10
    - PL yield *vs.* silicon volume content, 25-9
    - radiative process, 25-14
    - relaxation process, 25-11
    - spin-orbit interaction, 25-12
    - surface passivation, 25-9
    - synthesis, 25-3 thru 25-7
  - SiO$_2$, 25-1
  - surface phenomena, 25-3
  - surface-to-volume (STV) ratio, 25-2 thru 25-3
  - vibron model
    - adiabatic approximation, 25-17
    - conduction-ISL (CISL), 25-20
    - core nanocrystal, 25-22
    - electron–phonon interaction, 25-18
    - inter-sub-level (ISL) optical transition, 25-19
    - laser pyrolysis technique, 25-21
    - nanocrystal passivation, 25-16
    - noncoherent surface vibration, 25-19
    - phonon dispersion relation, 25-16
    - photoinduced absorption (PIA) spectra, 25-19 thru 25-20
    - polaron formation mechanism, 25-18
    - polar optical phonon, 25-19
    - resonant coupling condition, 25-17
    - silicon–oxygen bond, 25-16 thru 25-17
    - silicon–silicon dioxide (SiO$_2$) interface, 25-15 thru 25-16
    - Si–O vibration, 25-20 thru 25-21
    - valence-ISL (VISL), 25-20
- Photolysis process, 19-5 thru 19-6
- Photo-mask steps, 6-8
- Photonic crystal lasers, 39-10
- Photonic crystal waveguide, 37-1 thru 37-2
- Photon localization
  - canonical field quantization
    - eigenstates, 32-5
    - Hamiltonian operator, 32-4 thru 32-5
    - harmonic oscillator, 32-4
    - Helmholtz equation, 32-4
    - light–matter interaction, 32-3
    - quantization procedure, 32-5
  - dressing mechanism and spatial localization
    - Davydov transformation, 32-12 thru 32-13, 32-16
    - effective interaction Hamiltonian operator, 32-8
    - effective sample-probe-tip interaction, 32-10
    - electric displacement operator, 32-9
    - electromagnetic field correlations and intermolecular interactions, 32-6 thru 32-7
    - exciton polariton, 32-9
    - Hamiltonian model, 32-11 thru 32-12
    - irrelevant macroscopic subsystem, 32-7 thru 32-8
    - mean field approximation, 32-14
    - nanomaterial system, 32-7

      phonon-assisted photodissociation, 32-17
      photon–electron–phonon interacting system, 32-7
      photon hopping operator, 32-15 thru 32-16
      photon number operator, 32-14 thru 32-15
      photon–phonon coupling constant, 32-15
      pseudo one-dimensional near-field optical probe system, 32-11
      P space and Q space, 32-8
      quasiparticle and coherent state, 32-13 thru 32-14
      virtual photon cloud, 32-5 thru 32-6
      Yukawa functions, 32-11
   effective spatial wave function, 32-3
   Heisenberg's uncertainty principle, 32-1
   position-representation wave function, 32-1
   quantum electrodynamics (QED), 32-1
   virtual cloud effects, 32-2
   wave function definition, 32-2 thru 32-3
Photoresist technology
   base quencher additives, 19-6 thru 19-7
   EUV lithography, 19-8
   line and space pattern, 19-4 thru 19-5
   material structure advances, 19-7 thru 19-8
   193 nm immersion lithography, 19-8
   photolysis process of photoacid generator, 19-5 thru 19-6
   positive and negative tone resist, 19-4
   residual swelling fraction, 19-7
   resist materials, 19-4 thru 19-5
Piezoresponse force microscopy (PFM), 6-12 thru 6-13
Plasmon amplification, 26-5
Plasmon frequency, 26-4
Plasmonic lasers
   bowtie structures, 39-9
   dipole nanolaser, 39-9 thru 39-10
   horseshoe optical nanoantenna., 39-9
   surface plasmon mode confinement, 39-8
Plasmonic waveguides, 37-1 thru 37-2
PLD, *see* Pulsed laser deposition
Point contacts and conductance quantum, 12-11
Poisson–Schrödinger resolution, 5-13, 5-18
Polarization-sensitive nanowire and nanorod optics
   absorption coefficient, 26-4
   anisotropic nanostructure, 26-1
   core–shell nanowires
      luminescence amplification, 26-13
      potential distribution, 26-11
      spectra and polarization dependence, 26-11 thru 26-13
   depolarization factors, 26-2
   electrodynamic effects, 26-2
   first-kind Hankel function, 26-3
   Helmholtz wave equation, 26-3
   light-induced phenomena, 26-1
   metal and semiconductor nanowires, nonlinear phenomena
      dipole orientation, 26-8
      frequency dispersion, 26-10
      Gaussian properties, 26-11
      linear optical phenomena, 26-9
      nonlinear polarization, 26-8
      plasmon resonance, 26-10
      radiation pattern, 26-9
      second harmonic generation (SHG), 26-7 thru 26-8
      SHG angular distribution, 26-10
   metal nanostructures, 26-4 thru 26-5
   optical properties, 26-3
   photoconductivity, 26-2 thru 26-3
   planar interface, 26-1
   plasmon spectra
      longitudinal plasmon shift, 26-16 thru 26-17
      self-assembling, 26-15 thru 26-16
   polarization memory, random nanorod arrays
      luminescence polarization ratio, 26-14
      polarization antimemory, 26-15
      polarization-dependent effects, 26-13
   polarization ratio, 26-4
   semiconductor nanostructures, 26-2
      intensity ratio, 26-6
      isotropic interband matrix element, 26-5
      Poynting vector, 26-6
      radiation characteristics, 26-7
      refractive index, 26-5
      ZnO NW luminescence spectrum, 26-7
Power spectral density (PSD), 20-4
Proximity effect, 7-15 thru 7-17
Pulsed laser deposition (PLD), 6-6

Q

Quantum computing
   atom–light interaction
      Jaynes–Cummings model, 1-6 thru 1-7
      in RWA, 1-4 thru 1-6
   Loss–DiVincenzo proposal
      RKKY interaction, 1-8 thru 1-9
      using quantum dots and electric gates, 1-7 thru 1-8
   physical implementation conditions, 1-3
   qubits and quantum logic gates, 1-2 thru 1-3
   semiconductor quantum dots
      classical Faraday effect, 1-13
      electronic band structure, 1-12
      quantum Faraday effect, 1-13 thru 1-14
   SPFE
      conditional Faraday rotation, 1-16
      GHZ quantum teleportation, 1-16 thru 1-18
      Jaynes–Cummings Hamiltonian description, 1-14 thru 1-15
      quantifying EPR entanglement, 1-16
      quantum computing, 1-18 thru 1-20
   with molecular magnet
      double-well potential, 1-11
      Feynman diagrams, 1-10
      Grover's algorithm implementation, 1-12
      single-spin Hamiltonian description, 1-10
   Zeeman effects
      strong external field, 1-4
      weak external field, 1-4
Quantum dot laser
   edge emitter laser diodes (*see* Edge emitter laser diodes)
   electronic state
      continuum approaches and atomistic models, 40-5
      envelope-function approximation, 40-5
      localized and delocalized, self-assembled structures, 40-4 thru 40-5
   laser emission properties
      microscopic generalization, 40-14 thru 40-15
      photon statistics modifications, 40-15 thru 40-16
      rate equations, 40-13 thru 40-14
   material systems, 40-1 thru 40-2
   optical gain
      gain saturation, refractive index, and α-factor, 40-12 thru 40-13
      interband transitions and macroscopic polarization, 40-11
      optical gain calculations, 40-11 thru 40-12
      optical susceptibility, 40-10 thru 40-11
      transparency carrier density, 40-10
   scattering process
      carrier–carrier interaction, 40-6 thru 40-8
      carrier–phonon interaction, 40-8 thru 40-10
Quantum dot (QD) memories; *see also* Self-organized quantum dots
   hysteresis measurements, 2-22
   write time measurements, 2-22 thru 2-23
Quantum entangled states, 33-12 thru 33-13
Quantum Faraday effect, 1-13 thru 1-14
Quantum spin tunneling
   anticrossing of adiabatic eigenvalues, 9-3
   Berry's phase and path integrals (*see* Berry's phase interference)
   generalized master equation, 9-4
   Pauli or master equation, 9-3 thru 9-4
   Rabi oscillation, 9-3
   spin Hamiltonian, 9-2
   uniaxial anisotropy, 9-2
Quantum teleportation, 1-16 thru 1-18
Quasiparticle poisoning
   energetics of the nonequilibrium process, 16-7 thru 16-9

- in ramped current measurement, 16-11 thru 16-12
- in rf measurement, 16-15
Quasi-static thermal equilibrium dialysis, 11-5 thru 11-6

R

Rabi oscillation, 9-3, 29-16 thru 29-19
Radosavljevic's device, 3-5
Random lasers, 39-11
Rate window method, 2-15 thru 2-16
RBS, *see* Rutherford backscattering spectrometry
Rectangular and elliptical islands, 4-6 thru 4-7
Relevant nanometric subsystem, 32-7 thru 32-8
"Research triangle," 6-1 thru 6-2
Resistively and capacitively shunted junction (RCSJ) model, 16-3 thru 16-4
Richardson's constant, 13-2
Rotating wave approximation (RWA), 1-4 thru 1-6
Rutherford backscattering spectrometry (RBS), 6-8

S

Sawyer-Tower circuit, 6-10
Scattering lasers, 39-10 thru 39-11
Schottky barrier, 13-1
Schottky contact, 2-11 thru 2-12
Second harmonic generation
- nanoparticles
  - crystallographic defects, 28-7
  - Feynman diagram, 28-6
  - fundamental wavelength (FW) field interaction, 28-5
  - long-wavelength limit, 28-7 thru 28-8
  - perturbation theory, 28-6
  - retardation effects, 28-6
  - scanning near-field optical microscopy (SNOM), 28-5
  - SHG selection rules, 28-7
- nanosystems
  - low-symmetry particles, 28-4
  - nonuniform illumination, 28-4
  - random metal nanostructures and rough metal surfaces, 28-5
  - resonant metal particles, 28-4 thru 28-5
  - spherical isolated particles and plane-wave illumination, 28-3
- nonlinear optics, 28-2 thru 28-3
- SH electric field polarization, 28-9
- single gold nanoparticles
  - Fischer pattern, 28-12
  - lithographed nanorods, 28-12 thru 28-13
  - near-field FW properties, 28-13
  - near-field nonlinear optical microscopy, 28-11
  - nonlinear optical behavior, 28-13 thru 28-14
  - second harmonic polarization analysis, 28-14 thru 28-15
  - SHG efficiency, 28-14
  - SNOM, 28-11 thru 28-12

Second harmonic maps, 28-12 thru 28-14
Self-organized quantum dots
- based nanomemories, 2-10
- carrier emission process, 2-9
- charge carrier storage
  - hole storage in GaSb/GaAs QD, 2-17 thru 2-18
  - in InGaAs/GaAs QD, 2-17
  - InGaAs/GaAs QD with AlGaAs barrier, 2-18 thru 2-20
  - storage time, 2-20 thru 2-21
- electron and hole states, 2-9
- fabrication, 2-8
- localization energy and carrier storage time determination (*see* Capacitance spectroscopy)

Self-phase modulation (SPM), 41-4 thru 41-5
Semi-analytical approach numerical validation
- convergence, 5-19
- FEM approach, 5-19 thru 5-21

Semiconductor lasers
- Bragg mirrors, 39-3
- in-plane laser, 39-2 thru 39-3
- vertical cavity surface emitting laser (VCSEL), 39-2

Semiconductor nanomemories
- charge trap memories, 2-6 thru 2-7
- single electron memories, 2-7

Semiconductor nanostructures
- four-wave mixing response, perturbation theory
  - electron–hole pair, 29-11
  - excitation field possess, 29-13
  - excitons, definition, 29-11
  - Green function, 29-16
  - macroscopic exciton polarization, 29-12
  - multiwave mixing response, 29-14
  - Pauli blocking spectrum, 29-15
  - phase factor, 29-14
  - quantum well, 29-11
  - semiconductor nonlinear response, 29-11
  - S-matrix, 29-12
- Green's functions method, 29-1
- quantum equations
  - Coulomb energy, 29-8
  - Coulomb gauge, 29-6
  - density matrix, 29-6
  - divergent band-gap renormalization, 29-8
  - electromagnetic field–matter system, 29-6
  - electron–electron interaction, 29-7
  - Heisenberg equation, 29-7
  - Heisenberg representation, 29-6
  - Helmholtz's theorem, 29-7
  - radiative decay, 29-9
  - rotating wave approximation, 29-9 thru 29-10
- quantum field theory, 29-1
- rabi oscillations, nonperturbative methods
  - exciton polarization, 29-19
  - Fourier series, 29-18
  - Hartree–Fock approximation, 29-17
  - integro-differential operator, 29-17
  - interband polarization, 29-18
  - spacial decoupling scheme, 29-16
- semiconductor-field hamiltonian, $\mathbf{k}\cdot\mathbf{p}$-approximation
  - Bloch mode, 29-2
  - Coulomb gauge, 29-4
  - effective mass, 29-5
  - electron field operator, 29-3
  - Fourier series, 29-3
  - heavy–light hole hybridization, 29-5
  - Hermitian equation, 29-2
  - interband coupling, 29-3
  - intraband coupling, 29-4
  - Luttinger–Kohn function, 29-2
  - quantum dynamics, 29-2
  - Schrieffer–Wolff transformation, 29-3
  - semiconductor quantum dot, 29-5
  - spatial field operators, 29-4
  - spatial Fourier spectrum, 29-6
  - spin-orbit interaction, 29-5

Semiconductor quantum dots
- nonlinear optical properties, 23-5 thru 23-6
- two-photon absorption (2PA)
  - amplified stimulated emission and lasing, 23-7
  - CdSe, 23-6
  - continuous-wave (cw) Gaussian beam, 23-7
  - incident laser intensity, 23-6 thru 23-7
  - optical power limiting and biological imaging, 23-7
  - two-photon sensitizer, 23-7 thru 23-8

Silica deposition vesicle (SDV), 31-7
Siliconize photonics, 37-1
Silicon nanostructures
- Arrhenius plot, 25-11
- confinement energy, 25-8
- co-sputtered SiNC, 25-7 thru 25-8
- Coulomb exchange interaction, 25-11
- dynamical characteristics, 25-10
- excitons, 25-8
- *f*-sum rule/Thomas-Reiche-Kuhn sum rule, 25-13
- nanocrystal size distribution, 25-12 thru 25-13
- nonradiative process, 25-14 thru 25-15
- optical characterizations and luminescence bands, 25-7
- oscillator strength *vs*. confinement energy, 25-13 thru 25-14
- PL decay time, 25-10

  - PL yield *vs.* silicon volume content, 25-9
  - radiative process, 25-14
  - relaxation process, 25-11
  - spin-orbit interaction, 25-12
  - surface passivation, 25-9
  - synthesis
    - co-sputtering method, 25-4
    - electrochemical etching, 25-3
    - high angle annular dark field (HAADF) detector, 25-6 thru 25-7
    - laser pyrolysis, 25-5
    - molecular beam epitaxy (MBE) system, 25-6
    - silicon nanocrystals (SiNCs), 25-3 thru 25-4
    - silicon/SiO_2 serial sputtering, 25-6
    - transmission electron microscope (TEM), 25-5
- Silicon quantum dot
  - boundary conditions, 5-14
  - charge density in the nanocrystal, 5-17
  - DOF *vs.* maximum mesh size, 5-16
  - mesh algorithm, 5-15
  - meshing optimization, 5-16
  - quarter-structure in FEM, 5-14
  - structure for FEM simulation, 5-14
  - total energy of system, 5-17
  - *vs.* metallic approximation, 5-17 thru 5-18
- Single electron memories, 2-7
- Single-electron transistor (SET), 12-8 thru 12-9
- Single-molecule magnet transistors, 9-11 thru 9-12
- Single-photon Faraday rotation (SPFE)
  - conditional Faraday rotation, 1-16
  - GHZ quantum teleportation, 1-16 thru 1-18
  - Jaynes–Cummings Hamiltonian description, 1-14 thru 1-15
  - quantifying EPR entanglement, 1-16
  - quantum computing
    - Alice's quantum dot, 1-19
    - Bob's quantum dot, 1-19
    - Leuenberger's scheme, 1-18
    - optical Stark effect, 1-20
- Single-walled carbon nanotube (SWNT)
  - 1D direct-gap band structure, 22-2
  - exciton states, 22-3
  - Lorentzian function, 22-3
  - PL spectrum, 22-3 thru 22-4
  - Si/SiO_2 substrate, 22-2
  - spectral diffusion, 22-4
  - Stark effect, 22-4
- Small angle x-ray scattering (CD-SAXS), 19-27
- Spacer double patterning method, 19-25
- Spacer patterning technique (SPT), 17-4 thru 17-5
- Spatial symmetry
  - nanophotonic buffer memory, 33-11 thru 33-12
  - quantum entangled states manipulation, 33-12 thru 33-13
  - selective energy transfer, 33-9 thru 33-10
  - symmetric and antisymmetric states, 33-8 thru 33-9
  - AND and XOR logic gates, 33-10 thru 33-11
- Spherical dot in plate capacitor
  - geometry and notations, 5-3
  - metallic dot
    - B_l coefficients expression, 5-4 thru 5-5
    - boundary conditions for potential, 5-4
    - capacitance and coupling coefficient, 5-3 thru 5-4
    - capacitance matricial expression, 5-6
    - method of images, 5-4 thru 5-5
    - numerical implementation and results, 5-7 thru 5-9
    - partial capacitance expression, 5-6
    - polarization influence, 5-6 thru 5-7
    - semi-analytical expression for potential, 5-6
  - semiconductor dot
    - multiple electrons, 5-12 thru 5-13
    - quantization effects, 5-9 thru 5-10
    - quantum dot with single electron, 5-10 thru 5-11
    - second electron addition, 5-11 thru 5-12
  - silicon quantum dot
    - boundary conditions, 5-14
    - charge density in the nanocrystal, 5-17
    - DOF *vs.* maximum mesh size, 5-16
    - mesh algorithm, 5-15
    - meshing optimization, 5-16
    - quarter-structure in FEM, 5-14
    - structure for FEM simulation, 5-14
    - total energy of system, 5-17
    - *vs.* metallic approximation, 5-17 thru 5-18
- Spin-transfer torque effect, 8-3
  - for both directions of current, 8-6
  - and giant magnetoresistance, 8-12 thru 8-13
  - LLGS equation, 8-6
  - spin-diffusion length, 8-7
- Spin transistor, 12-9
- Spintronics, 1-1, 8-3, 12-9
- Spin-valve system
  - active region, 8-3
  - nanoscale (*see* Nanoscale spin valves)
- Sputter deposition, 6-6 thru 6-7
- Static random access memory (SRAM) unit cell, 20-8 thru 20-9
- Stratonovich interpretation, 8-11
- Sub-*kT/q* switch, 12-8
- Substrate radiation mode, 37-9
- Superconducting Josephson junction
  - Ambegaokar–Barato relation, 16-2
  - concerns specific to small junctions, 16-4
  - field emission micrograph, 16-2
  - *I–V* curve, 16-2 thru 16-3
  - RCSJ model, 16-3 thru 16-4
- Superconducting quantum interferometers (SQUID), *see* Nanotube-based superconducting quantum interferometers
- Superconducting weak links
  - carbon nanotube weak link
    - experimental realizations, 7-6 thru 7-7
    - Fabry–Perot cavity, 7-6
    - high-frequency irradiation, 7-9 thru 7-10
    - nanotube quantum dot, 7-7 thru 7-9
  - coherent transport, 7-2
  - electronic state density, 7-2
  - fullerene-based links, 7-17 thru 7-18
  - gate control, 7-4 thru 7-5
  - graphene-based links
    - proximity effect, 7-15 thru 7-17
    - SQUIDs devices, 7-17
  - Josephson effect, 7-2 thru 7-3
  - low-dimensional sp^2 carbon structures, 7-4 thru 7-5
  - nanotube-based SQUID
    - magnetometry applications, 7-13 thru 7-14
    - quantum information applications, 7-14 thru 7-15
    - quantum interference with weak links, 7-10 thru 7-11
    - tunability of the phase shift, 7-11 thru 7-12
  - normal electron transport, 7-3
  - transport through Andreev bound states, 7-3 thru 7-4
- Surface-architecture-controlled transistors
  - depletion width and effective diameter, 14-14
  - electrode CS, 14-12 thru 14-13
  - I_{DS}–V_G curves, 14-12
  - surface band bending, 14-13
- Surface plasmon resonance (SPR)/Mie resonance, 24-2, 24-6
- Surface-roughness effects, 14-7 thru 14-9
- Sweep rate effect, 14-9 thru 14-11

T

- Thermal NIL, 19-18 thru 19-19
- Thermionic emission (TE) theory, 13-2
- Thomas–Reiche–Kuhn sum rule, 25-13
- Three-dimensional carrier confinement, 40-4, 40-5
- Three-terminal molecules, 17-9 thru 17-10
- Time-bandwidth product (TBWP), 41-2
- Time-dependent Kohn–Sham equation, 27-3
- Time-dependent local-density approximation (TD LDA), 24-7 thru 24-8, 25-15
- TMOS, schematic behavior, 5-1 thru 5-2
- Transfer printing, 19-19
- Transistor structures
  - atomic-scale TCAD, 12-11 thru 12-12
  - carbon nanotube transistors, 12-6 thru 12-7
  - graphene ribbon nanotransistors, 12-7 thru 12-8

- molecular tunnel junctions, 12-9 thru 12-11
- Moore's law, 12-1 thru 12-2
- nonclassical transistor structures, 12-7
- nonplanar multi-gate transistors, 12-3 thru 12-4
- point contacts and conductance quantum, 12-11
- quantum effects, 12-5 thru 12-6
- SET, 12-8 thru 12-9
- silicon processing, technology boosters, 12-2 thru 12-3
- spin transistor, 12-9
- sub-*kT/q* switch, 12-8

Transmission electron microscope-cathodoluminescence (TEM-CL)
- carrier generation and light emission process, 21-3 thru 21-4
- characteristics, 21-3
- diffusion length, 21-4
- gallium arsenide (GaAs) nanowire
  - CL spectra, temperature dependence, 21-20
  - GaAs/AlGaAs nanowire, SEM image, 21-18 thru 21-19, 21-21
  - zinc-blend structure, 21-18
- InP nanowires
  - broad peak blue-shifts, 21-16
  - CL spectra, 21-17 thru 21-18
  - degree of polarization, 21-18
  - electron confinement energy, 21-16
  - emission energy, 21-15
  - metal-organic vapor phase epitaxy (MOCVPE) technique, 21-15
  - phonon scattering process, 21-17
  - SEM image, 21-15 thru 21-16
- Monte Carlo simulation, 21-4
- photomultiplier tube (PMT), 21-5
- resolution factors, 21-3
- scanning electron microscopy (SEM), 21-5
- zinc oxide (ZnO) nanowires
  - CL intensity, 21-22
  - CL spectra, 21-21
  - emission peak, 21-24
  - fitting function, 21-22
  - optical properties, 21-21
  - polarization ratio, 21-23
  - smoke particles, 21-22 thru 21-23
  - wurtzite-type semiconductor, 21-21

Tunneling magnetoresistance (TMR), 6-18

Tunnel magnetoresistance (TMR) effect, 2-5

Two-level amplifying system (TLS)., 39-9

U

Ultrafast laser diodes
- broad gain bandwidth, 41-7
- dimensionality role, 41-5 thru 41-6
- low absorption saturation fluence, 41-8
- low threshold current and low temperature sensitivity, 41-8
- materials and growth, 41-6
- ultrafast carrier dynamics, 41-7 thru 41-8

Ultrahigh data storage, 39-12

UV NIL, 19-19

V

van den Berg's ferromagnetic islands, 4-3

van der Waals epitaxy
- bottom contact structure, 15-11
- initial growth surface
  - hexagonal AlN (0001) surface, 15-14 thru 15-16
  - hexagonal GaN (0001) surfaces, 15-12 thru 15-14
  - H-terminated Si (111) surfaces, 15-11 thru 15-12

van Roosbroeck thru Shockly relation, 21-6 thru 21-7

Vapor–liquid–solid (VLS) mechanism, 14-3

Vapor transport method
- FESEM images, vertically well-aligned nanowires, 14-5 thru 14-6
- furnace system schematic, 14-4 thru 14-5

Vertical-cavity surface-emitting lasers (VCSELs), 40-3

W

Wess–Zumino phase, *see* Berry's phase

X

X-ray diffraction (XRD)
- reciprocal space maps, 6-9
- specular reflectivity method, 6-9 thru 6-10
- synchrotron x-ray scattering measurements, 6-9

Z

Zeeman effects, 1-4

Zero-biased rf electrometry
- operation beyond 1 GHz, 16-14 thru 16-15
- quasiparticle poisoning, 16-15
- relation to the cooper-pair box, 16-16
- rf measurement setup, 16-13 thru 16-14

ZnO nanorod double quantum-well structures, 36-7 thru 36-11

ZnO nanowire field-effect transistors
- crystal structure of ZnO, 14-2
- fabrication and characterization
  - back gate and top gate configurations, 14-7
  - passivation and surface-roughness effects, 14-7 thru 14-9
  - sweep rate effect, 14-9 thru 14-11
- FET, 14-3 thru 14-4
- general growth methods, 14-2 thru 14-3
- N-channel depletion-mode and enhancement-mode, 14-11
- physical parameters of ZnO, 14-2
- surface-architecture-controlled transistors
  - depletion width and effective diameter, 14-14
  - electrode CS, 14-12 thru 14-13
  - I_{DS}–V_G curves, 14-12
  - surface band bending, 14-13
- vapor transport method
  - FESEM images, vertically well-aligned nanowires, 14-5 thru 14-6
  - furnace system schematic, 14-4 thru 14-5



FIGURE 16.4 The ground (ϵ_0) and first excited (ϵ_1) states calculated by numerically diagonalizing Equation 16.11 with the energies indicated in the figure.



FIGURE 16.11 (a) Type H I_{sw} histograms versus n_g. Histogram height is displayed in grayscale on the right-hand side, whereas all counts are displayed equally on the left-hand side. As in Figure 16.7, the gray box in (a) denotes regions where the island potential is trap like for quasiparticles. (b) Selected histograms corresponding to several gate voltages. Device parameters: $\Delta_i = 246\,\mu$eV, $\Delta_\ell = 205\,\mu$eV, $E_C \simeq 115\,\mu$eV, and $E_{J1} = E_{J2} \simeq 82\,\mu$eV.



FIGURE 16.13 (a,c) Switching current (I_{sw}) histograms and (b,d) derived switching/escape rates for a type H (barrier-like) and type L (trap-like) CPTs. For the type L device, the quasiparticle trapping behavior is evident in the bimodal I_{sw} distribution. In this case, the poisoning rate Γ_{eo} can be read directly from the derived escape rate in (d) as shown. Although the type H device is barrier-like for most n_g, it still looks like a trap near $n_g = 1$ (see Figure 16.7). This is apparent in the "curvy" structure of the escape curve for $n_g = 0.99$ as compared with the escape rates at other n_g in (b).



FIGURE 20.6 (a) Artist illustration of ASML's EUV ADT showing a DPP EUV source on the left, illumination optics in the middle, and mask, projection optics, and wafer on the right. (Courtesy of ASML, Veldhoven, the Netherlands.)



FIGURE 20.18 Artist illustration of ASML NXE: 3100 preproduction EUV exposure tool showing the LPP EUV source on the right, the illuminator optics in the center, and the mask and the projection optics on the right. (Courtesy of ASML, Veldhoven, the Netherlands.)



FIGURE 23.1 Excitons and structural size variations on the nanometer length scale. (a) The photosynthetic antenna of purple bacteria, LH2, is an example of a molecular exciton. The absorption spectrum clearly shows the dramatic distinction between the B800 absorption band, arising from essentially "monomeric" bacteriochlorophyll-a (Bchl) molecules, and the redshifted B850 band that is attributed to the optically bright lower exciton states of the 18 electronically coupled Bchl molecules. (b) The size-scaling of polyene properties, for example, oligophenylenevinylene oligomers, derives from the size-limited delocalization of the molecular orbitals. However, as the length of the chains increases, disorder in the chain conformation impacts the picture for exciton dynamics. Absorption and fluorescence spectra are shown as a function of the number of repeat units. (c) SWCNT size and "wrapping" determine the exciton energies. Samples contain many different kinds of tubes, therefore optical spectra are markedly inhomogeneously broadened. By scanning excitation wavelengths and recording a map of fluorescence spectra, the emission bands from various different CNTs can be discerned, as shown. (Courtesy of Dr. M. Jones). (d) Rather than thinking in terms of delocalizing the wavefunction of a semiconductor through interactions between the unit cells, the small size of the nanocrystal confines the exciton relative to the bulk. Size-dependent absorption spectra of PbS quantum dots are shown. (Adapted from Scholes, G. D. and Rumbles, G., *Nat. Mater.*, 5, 683, 2006.)



FIGURE 24.9 Evolution of the absorption cross section of a nanoshell of silver (top) or copper (bottom) in the dipolar approximation versus energy (left) or versus wavelength (right) for various thicknesses of the shell. The core is filled with water and the external medium is also water ($n = 1.33$). The dielectric functions of copper and silver have been extracted from Palik (1985–1991). The correspondence between the energy in eV and the wavelength in nm is E (eV) = 1239.85/λ (nm). The total radius of the cluster is always 15 nm and the thickness takes the following values: $e = R - R_c = 5; 4; 3; 2; 1$ nm corresponding to ratios between the shell thickness and the total cluster radius: $(e/R) = 0.33; 0.27; 0.2; 0.13; 0.07$. The spectra in black correspond to the fully homogeneous cluster.



FIGURE 24.15 (Top) Color image of a typical sample of silver nanoparticles as viewed under the dark-field microscope. The brightness of the particles increases from blue to red due to both the intrinsic optical scattering cross section and the spectral output of the light source (the red particle is overexposed). This image is correlated to its electron microscopy image (Bottom). (Reprinted from Mock, J.J. et al., *J. Chem. Phys.*, 116, 6755, 2002. With permission.)



FIGURE 24.16 (Left) Normalized UV–visible spectra of Au–Ag alloy nanoparticles with varying composition. (Insert) Location of the SPR maximum as a function of the gold content. (Right) Corresponding solutions whose colors vary from the red (pure gold nanoparticles) to the yellow (pure silver nanoparticle). (From Russier-Antoine, I. et al., *Phys. Rev. B*, 78, 35436, 2008. With permission.)



FIGURE 25.2 The PL spectrum from porous silicon with a maximum PL at a wavelength of about 675 nm. The photograph at the inset demonstrates the red color of the emitted PL from a circular layer of porous silicon (the sample has been illuminated with a UV lamp).



FIGURE 25.6 (a) A photograph showing the PL variation along the substrate from silicon nanocrystals deposited by the laser pyrolysis technique. (b) The normalized PL spectra from different positions along the substrate. (Reprinted from Ledoux, G. et al., *Appl. Phys. Lett.*, 80, 4834, 2002. With permission.)



FIGURE 28.10 Nanoparticles: (a), (d), and (g) topography; (b), (e), and (h) FW transmission; and (c), (f), and (i) SH emission SNOM images with corresponding cross sections along the dashed lines, from the raw data. Incident light is polarized parallel to the major axis. The particle major axis lengths are 100 nm (a)–(c), 150 nm (d)–(f), and 400 nm (g)–(i). Image size: 3 × 3 µm^2. (Reprinted from Zavelani-Rossi, M. et al., *Appl. Phys. Lett.*, 92, 093119, 2008. With permission.)



FIGURE 29.3 The imaginary part of the two-dimensional Fourier spectrum, $P(\Omega, \omega)$. (a) The spectrum calculated using Equation 29.92. (b) The experimental results of Zhang et al. (2005).



FIGURE 32.5 Probability that a photon is found at each site as a function of time (a) without the photon–phonon coupling, and (b) with the photon–phonon coupling comparable to the photon hopping constant.



FIGURE 37.14 Calculated spectral positions of the substrate modes as a function of (a) the refractive index contrast $\Delta n = n_2 - n_3$ and (b) the relative thickness of the waveguide core compared to the sample 5×10^{17} Si cm^{-2}. Gray scale indicates intensity increasing from black up to white for the highest intensity. Several orders of modes are seen starting from the first one in infrared region.



FIGURE 37.16 (a) Photograph of the edge of a set of Si$^+$ ion implanted layers with direction of PL indicated by arrows, the edge is on the left. (b) Measured PL from samples implanted to different Si ion fluences in standard (the broadest curves) and waveguiding geometry (black lines, the slightly lighter gray lines stand for TE and TM resolved polarizations). (c) Theoretically calculated PL spectra. We note that these results were obtained on different set of samples than in Figure 37.10. The mode positions are not exactly the same for samples with identical implantation dose because the annealing conditions were slightly different. Therefore, the refractive index profiles are not identical. (Adapted from Pelant, I. et al., *Appl. Phys. B*, 83, 87, 2006.)

Physics

HANDBOOK OF NANOPHYSICS

Nanoelectronics and Nanophotonics



Many bottom-up and top-down techniques for nanomaterial and nanostructure generation have enabled the development of applications in nanoelectronics and nanophotonics. **Handbook of Nanophysics: Nanoelectronics and Nanophotonics** explores important recent applications of nanophysics in the areas of electronics and photonics. Each peer-reviewed chapter contains a broad-based introduction and enhances understanding of the state-of-the-art scientific content through fundamental equations and illustrations, some in color.

This volume discusses how different nanomaterials, such as quantum dots and nanotubes, are used in quantum computing, capacitors, and transistors. Leading international experts review the potential of the novel patterning techniques in molecular electronics as well as nanolithography approaches for producing semiconductor circuits. They also describe optical properties of nanostructures, nanowires, nanorods, and clusters, including cathodoluminescence, photoluminescence, and polarization sensitivity. In addition, the book covers nanophotonic devices and nanolasers.

Nanophysics brings together multiple disciplines to determine the structural, electronic, optical, and thermal behavior of nanomaterials; electrical and thermal conductivity; the forces between nanoscale objects; and the transition between classical and quantum behavior. Facilitating communication across many disciplines, this landmark publication encourages scientists with disparate interests to collaborate on interdisciplinary projects and incorporate the theory and methodology of other areas into their work.

CRC Press
Taylor & Francis Group
an **informa** business
www.crcpress.com

6000 Broken Sound Parkway, NW
Suite 300, Boca Raton, FL 33487
270 Madison Avenue
New York, NY 10016
2 Park Square, Milton Park
Abingdon, Oxon OX14 4RN, UK

75500
ISBN: 978-1-4200-7550-2
90000
9 781420 075502
www.crcpress.com

75500_COVER_vol_6_final.indd 1

Springer Handbook of Nanotechnology

Springer Handbook provides a concise compilation of approved key information on methods of research, general principles, and functional relationships in physics and engineering. The world's leading experts in the fields of physics and engineering will be assigned by one or several renowned editors to write the chapters comprising each volume. The content is selected by these experts from Springer sources (books, journals, online content) and other systematic and approved recent publications of physical and technical information.

The volumes will be designed to be useful as readable desk reference book to give a fast and comprehensive overview and easy retrieval of essential reliable key information, including tables, graphs, and bibliographies. References to extensive sources are provided.

Springer
Berlin
Heidelberg
New York
Hong Kong
London
Milan
Paris
Tokyo

Springer Handbook of Nanotechnology

Bharat Bhushan (Ed.)

With 972 Figures and 71 Tables

Springer

Professor Bharat Bhushan
Nanotribology Laboratory
for Information Storage and MEMS/NEMS
The Ohio State University
206 W. 18th Avenue
Columbus, Ohio 43210-1107
USA

Library of Congress Cataloging-in-Publication Data
Springer handbook of nanotechnology / Bharat Bhushan (ed.)
p. cm.
Includes bibliographical references and index
ISBN 3-540-01218-4 (alk. paper)
1. Nanotechnology--Handbooks, manuals, etc. I. Bhushan, Bharat; 1949-

T174.7S67 2003
620′.5--dc22 2003064953

ISBN 3-540-01218-4
Spinger-Verlag Berlin Heidelberg New York

This work is subject to copyright. All rights reserved, whether the whole or part of the material is concerned, specifically the rights of translation, reprinting, reuse of illustrations, recitation, broadcasting, reproduction on microfilm or in any other way, and storage in data banks. Duplication of this publication or parts thereof is permitted only under the provisions of the German Copyright Law of September, 9, 1965, in its current version, and permission for use must always be obtained from Springer-Verlag. Violations are liable for prosecution under the German Copyright Law.

Springer-Verlag is a part of Springer Science+Business Media

springeronline.com

©Springer-Verlag Berlin Heidelberg 2004
Printed in Germany

The use of designations, trademarks, etc. in this publication does not imply, even in the absence of a specific statement, that such names are exempt from the relevant protective laws and regulations and therefore free for general use.

Product liability: The publisher cannot guarantee the accuracy of any information about dosage and application contained in this book. In every individual case the user must check such information by consulting the relevant literature.

Production and typesetting: LE-TeX GbR, Leipzig
Handbook coordinator: Dr. W. Skolaut, Heidelberg
Typography, layout and illustrations: schreiberVIS, Seeheim
Cover design: eStudio Calamar Steinen, Barcelona
Cover production: *design&production* GmbH, Heidelberg
Printing and binding: Stürtz AG, Würzburg

Printed on acid-free paper
SPIN 10890790 62/3141/YL 5 4 3 2 1 0

Foreword by Neal Lane

In a January 2000 speech at the California Institute of Technology, former President W. J. Clinton talked about the exciting promise of "nanotechnology" and the importance of expanding research in nanoscale science and engineering and in the physical sciences, more broadly. Later that month, he announced in his State of the Union Address an ambitious $ 497 million federal, multi-agency national nanotechnology initiative (NNI) in the fiscal year 2001 budget; and he made the NNI a top science and technology priority within a budget that emphasized increased investment in U.S. scientific research. With strong bipartisan support in Congress, most of this request was appropriated, and the NNI was born.

Nanotechnology is the ability to manipulate individual atoms and molecules to produce nanostructured materials and sub-micron objects that have applications in the real world. Nanotechnology involves the production and application of physical, chemical and biological systems at scales ranging from individual atoms or molecules to about 100 nanometers, as well as the integration of the resulting nanostructures into larger systems. Nanotechnology is likely to have a profound impact on our economy and society in the early 21st century, perhaps comparable to that of information technology or advances in cellular and molecular biology. Science and engineering research in nanotechnology promises breakthroughs in areas such as materials and manufacturing, electronics, medicine and healthcare, energy and the environment, biotechnology, information technology and national security. It is widely felt that nanotechnology will lead to the next industrial revolution.

Nanometer-scale features are built up from their elemental constituents. Micro- and nanosystems components are fabricated using batch-processing techniques that are compatible with integrated circuits and range in size from micro- to nanometers. Micro- and nanosystems include Micro/NanoElectroMechanical Systems (MEMS/NEMS), micromechatronics, optoelectronics, microfluidics and systems integration. These systems can sense, control, and activate on the micro/nanoscale and can function individually or in arrays to generate effects on the macroscale. Due to the enabling nature of these systems and the significant impact they can have on both the commercial and defense applications, industry as well as the federal government have taken special interest in seeing growth nurtured in this field. Micro- and nanosystems are the next logical step in the "silicon revolution".

The discovery of novel materials, processes, and phenomena at the nanoscale and the development of new experimental and theoretical techniques for research provide fresh opportunities for the development of innovative nanosystems and nanostructured materials. There is an increasing need for a multidisciplinary, systems-oriented approach to manufacturing micro/nanodevices which function reliably. This can only be achieved through the cross-fertilization of ideas from different disciplines and the systematic flow of information and people among research groups.

Nanotechnology is a broad, highly interdisciplinary, and still evolving field. Covering even the most important aspects of nanotechnology in a single book that reaches readers ranging from students to active researchers in academia and industry is an enormous challenge. To prepare such a wide-ranging book on nanotechnology, Professor Bhushan has harnessed his own knowledge and experience, gained in several industries and universities, and has assembled about 90 internationally recognized authors from three continents to write 38 chapters. The authors come from both academia and industry.

Professor Bharat Bhushan's comprehensive book is intended to serve both as a textbook for university courses as well as a reference for researchers. It is a timely addition to the literature on nanotechnology, which I anticipate will stimulate further interest in this important new field and serve as an invaluable resource to members of the international scientific and industrial community.

The Editor-in-Chief and his team are to be warmly congratulated for bringing together this exclusive, timely, and useful Nanotechnology Handbook.

Prof. Neal Lane

University Professor
Department of Physics and Astronomy and James A. Baker III Institute for Public Policy Rice University Houston, Texas USA

Served in the Clinton Administration as Assistant to the President for Science and Technology and Director of the White House Office of Science and Technology Policy (1998–2001) and, prior to that, as Director of the National Science Foundation (1993–1998). While at the White House, he was instrumental in creating NNI.

Foreword by James R. Heath

Nanotechnology has become an increasingly popular buzzword over the past five years or so, a trend that has been fueled by a global set of publicly funded nanotechnology initiatives. Even as researchers have been struggling to demonstrate some of the most fundamental and simple aspects of this field, the term nanotechnology has entered into the public consciousness through articles in the popular press and popular fiction. As a consequence, the expectations of the public are high for nanotechnology, even while the actual public definition of nanotechnology remains a bit fuzzy.

Why shouldn't those expectations be high? The late 1990's witnessed a major information technology (IT) revolution and a minor biotechnology revolution. The IT revolution impacted virtually every aspect of life in the western world. I am sitting on an airplane at 30,000 feet at the moment, working on my laptop, as are about half of the other passengers on this plane. The plane itself is riddled with computational and communications equipment. As soon as we land, many of us will pull out cell phones, others will check email via wireless modem, some will do both. This picture would be the same if I was landing in Los Angeles, Beijing, or Capetown. I will probably never actually print this text, but will instead submit it electronically. All of this was unthinkable a dozen years ago. It is therefore no wonder that the public expects marvelous things to happen quickly. However, the science that laid the groundwork for the IT revolution dates back 60 years or more, with its origins in the fundamental solid state physics.

By contrast, the biotech revolution was relatively minor and, at least to date, not particularly effective. The major diseases that plagued mankind a quarter century ago are still here. In some third world countries, the average lifespan of individuals has actually decreased from where it was a full century ago. While the costs of electronics technologies have plummeted, health care costs have continued to rise. The biotech revolution may have a profound impact, but the task at hand is substantially more difficult to what was required for the IT revolution. In effect, the IT revolution was based on the advanced engineering of two-dimensional digital circuits constructed from relatively simple components – extended solids. The biotech revolution is really dependent upon the ability to reverse engineer three-dimensional analog systems constructed from quite complex components – proteins. Given that the basic science behind biotech is substantially younger than the science that has supported IT, it is perhaps not surprising that the biotech revolution has not really been a proper revolution yet, and it likely needs at least another decade or so to come to fruition.

Where does nanotechnology fit into this picture? In many ways, nanotechnology depends upon the ability to engineer two- and three-dimensional systems constructed from complex components such as macromolecules, biomolecules, nanostructured solids, etc. Furthermore, in terms of patents, publications, and other metrics that can be used to gauge the birth and evolution of a field, nanotech lags some 15–20 years behind biotech. Thus, now is the time that the fundamental science behind nanotechnology is being explored and developed. Nevertheless, progress with that science is moving forward at a dramatic pace. If the scientific community can keep up this pace and if the public sector will continue to support this science, then it is possible, and perhaps even likely, that in 20 years from now we may be speaking of the nanotech revolution.

The Nanotechnology Handbook is timely in assembling chapters in the broad field of nanotechnology with an emphasis on reliability. The handbook should be a valuable reference for experienced researchers as well as for a novice in the field.

Prof. James R. Heath

Department of Chemistry
Mail Code: 127-72
California Institute of Technology
Pasadena, CA 91125, USA

Worked in the group of Nobel Laureate Richard E. Smalley at Rice University (1984–88) and co-invented Fullerene molecules which led to a revolution in Chemistry including the realization of nanotubes. The work on Fullerene molecules was cited for the 1996 Nobel Prize in Chemistry. Later he joined the University of California at Los Angeles (1994–2002), and co-founded and served as a Scientific Director of The California Nanosystems Institute.

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Preface

On December 29, 1959 at the California Institute of Technology, Nobel Laureate Richard P. Feynman gave a talk at the Annual meeting of the American Physical Society that has become one classic science lecture of the 20th century, titled "There's Plenty of Room at the Bottom." He presented a technological vision of extreme miniaturization in 1959, several years before the word "chip" became part of the lexicon. He talked about the problem of manipulating and controlling things on a small scale. Extrapolating from known physical laws, Feynman envisioned a technology using the ultimate toolbox of nature, building nanoobjects atom by atom or molecule by molecule. Since the 1980s, many inventions and discoveries in fabrication of nanoobjects have been a testament to his vision. In recognition of this reality, in a January 2000 speech at the same institute, former President W. J. Clinton talked about the exciting promise of "nanotechnology" and the importance of expanding research in nanoscale science and engineering. Later that month, he announced in his State of the Union Address an ambitious $ 497 million federal, multi-agency national nanotechnology initiative (NNI) in the fiscal year 2001 budget, and made the NNI a top science and technology priority. Nanotechnology literally means any technology done on a nanoscale that has applications in the real world. Nanotechnology encompasses production and application of physical, chemical and biological systems at size scales, ranging from individual atoms or molecules to submicron dimensions as well as the integration of the resulting nanostructures into larger systems. Nanofabrication methods include the manipulation or self-assembly of individual atoms, molecules, or molecular structures to produce nanostructured materials and sub-micron devices. Micro- and nanosystems components are fabricated using top-down lithographic and nonlithographic fabrication techniques. Nanotechnology will have a profound impact on our economy and society in the early 21st century, comparable to that of semiconductor technology, information technology, or advances in cellular and molecular biology. The research and development in nanotechnology will lead to potential breakthroughs in areas such as materials and manufacturing, nanoelectronics, medicine and healthcare, energy, biotechnology, information technology and national security. It is widely felt that nanotechnology will lead to the next industrial revolution.

Reliability is a critical technology for many micro- and nanosystems and nanostructured materials. No book exists on this emerging field. A broad based handbook is needed. The purpose of this handbook is to present an overview of nanomaterial synthesis, micro/nanofabrication, micro- and nanocomponents and systems, reliability issues (including nanotribology and nanomechanics) for nanotechnology, and industrial applications. The chapters have been written by internationally recognized experts in the field, from academia, national research labs and industry from all over the world.

The handbook integrates knowledge from the fabrication, mechanics, materials science and reliability points of view. This book is intended for three types of readers: graduate students of nanotechnology, researchers in academia and industry who are active or intend to become active in this field, and practicing engineers and scientists who have encountered a problem and hope to solve it as expeditiously as possible. The handbook should serve as an excellent text for one or two semester graduate courses in nanotechnology in mechanical engineering, materials science, applied physics, or applied chemistry.

We embarked on this project in February 2002, and we worked very hard to get all the chapters to the publisher in a record time of about 1 year. I wish to sincerely thank the authors for offering to write comprehensive chapters on a tight schedule. This is generally an added responsibility in the hectic work schedules of researchers today. I depended on a large number of reviewers who provided critical reviews. I would like to thank Dr. Phillip J. Bond, Chief of Staff and Under Secretary for Technology, US Department of Commerce, Washington, D.C. for suggestions for chapters as well as authors in the handbook. I would also like to thank my colleague, Dr. Huiwen Liu, whose efforts during the preparation of this handbook were very useful.

I hope that this handbook will stimulate further interest in this important new field, and the readers of this handbook will find it useful.

September 2003

Bharat Bhushan
Editor

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Editors Vita

Dr. Bharat Bhushan received an M.S. in mechanical engineering from the Massachusetts Institute of Technology in 1971, an M.S. in mechanics and a Ph.D. in mechanical engineering from the University of Colorado at Boulder in 1973 and 1976, respectively, an MBA from Rensselaer Polytechnic Institute at Troy, NY in 1980, Doctor Technicae from the University of Trondheim at Trondheim, Norway in 1990, a Doctor of Technical Sciences from the Warsaw University of Technology at Warsaw, Poland in 1996, and Doctor Honouris Causa from the Metal-Polymer Research Institute of National Academy of Sciences at Gomel, Belarus in 2000. He is a registered professional engineer (mechanical). He is presently an Ohio Eminent Scholar and The Howard D. Winbigler Professor in the Department of Mechanical Engineering, Graduate Research Faculty Advisor in the Department of Materials Science and Engineering, and the Director of the Nanotribology Laboratory for Information Storage & MEMS/NEMS (NLIM) at the Ohio State University, Columbus, Ohio. He is an internationally recognized expert of tribology on the macro- to nanoscales, and is one of the most prolific authors in the field. He is considered by some a pioneer of the tribology and mechanics of magnetic storage devices and a leading researcher in the fields of nanotribology and nanomechanics using scanning probe microscopy and applications to micro/nanotechnology. He has authored 5 technical books, 45 handbook chapters, more than 450 technical papers in referred journals, and more than 60 technical reports, edited more than 25 books, and holds 14 U.S. patents. He is founding editor-in-chief of World Scientific Advances in Information Storage Systems Series, CRC Press Mechanics and Materials Science Series, and Microsystem Technologies – Micro- & Nanosystems and Information Storage & Processing Systems (formerly called Journal of Information Storage and Processing Systems). He has given more than 250 invited presentations on five continents and more than 60 keynote/plenary addresses at major international conferences.

Dr. Bhushan is an accomplished organizer. He organized the first symposium on Tribology and Mechanics of Magnetic Storage Systems in 1984 and the first international symposium on Advances in Information Storage Systems in 1990, both of which are now held annually. He is the founder of an ASME Information Storage and Processing Systems Division founded in 1993 and served as the founding chair during 1993–1998. His biography has been listed in over two dozen Who's Who books including Who's Who in the World and has received more than a dozen awards for his contributions to science and technology from professional societies, industry, and U.S. government agencies. He is also the recipient of various international fellowships including the Alexander von Humboldt Research Prize for Senior Scientists, Max Planck Foundation Research Award for Outstanding Foreign Scientists, and the Fulbright Senior Scholar Award. He is a foreign member of the International Academy of Engineering (Russia), Belorussian Academy of Engineering and Technology and the Academy of Triboengineering of Ukraine, an honorary member of the Society of Tribologists of Belarus, a fellow of ASME, IEEE, and the New York Academy of Sciences, and a member of STLE, ASEE, Sigma Xi and Tau Beta Pi.

Dr. Bhushan has previously worked for the R & D Division of Mechanical Technology Inc., Latham, NY; the Technology Services Division of SKF Industries Inc., King of Prussia, PA; the General Products Division Laboratory of IBM Corporation, Tucson, AZ; and the Almaden Research Center of IBM Corporation, San Jose, CA.

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

List of Authors

Chong H. Ahn
University of Cincinnati
Department of Electrical and Computer
Engineering and Computer Science
814 Rhodes Hall
Cincinnati, OH 45221-0030, USA
e-mail: *chong.ahn@uc.edu*

Boris Anczykowski
nanoAnalytics GmbH
Gievenbecker Weg 11
48149 Münster, Germany
e-mail: *anczykowski@nanoanalytics.com*

Massood Z. Atashbar
Western Michigan University
Department of Electrical
and Computer Engineering
200 Union Street SE
Kalamazoo, MI 49008-5329, USA
e-mail: *massood.atashbar@wmich.edu*

Wolfgang Bacsa
Université Paul Sabatier
Laboratoire de Physique des Solides (LPST)
118 Route de Narbonne
31062 Toulouse Cedex 4, France
e-mail: *bacsa@lpst.ups-tlse.fr*

William Sims Bainbridge
National Science Foundation
Division of Information and Intelligent Systems
4201 Wilson Boulevard
Arlington, VA 22230, USA
e-mail: *wbainbri@nsf.gov*

Antonio Baldi
Institut de Microelectronica de Barcelona (IMB)
Centro National Microelectrónica (CNM-CSIC)
Campus Universitat Autonoma de Barcelona
08193 Barcelona, Spain
e-mail: *Antoni.baldi@cnm.es*

Philip D. Barnes
Ohio State University
Biomedical Engineering Center
1080 Carmack Road
Columbus, OH 43210, USA
e-mail: *d_skill@yahoo.com*

James D. Batteas
National Institute of Standards and Technology
Surface and Microanalysis Science Division
100 Bureau Drive Mailstop 8372
Gaithersburg, MD 20899-8372, USA
e-mail: *james.batteas@nist.gov*

Roland Bennewitz
McGill University
Physics Department
3600 rue University
Montreal, QC H3A 2T8, Canada
e-mail: *roland@physics.mcgill.ca*

Alan D. Berman
Monitor Venture Enterprises
241 S. Figueroa St. Suite 300
Los Angeles, CA 90012, USA
e-mail: *alan.berman.2001@anderson.ucla.edu*

Bharat Bhushan
The Ohio State University
Nanotribology Laboratory for Information Storage
and MEMS/NEMS
206 W. 18th Avenue
Columbus, OH 43210-1107, USA
e-mail: *bhushan.2@osu.edu*

Gerd K. Binnig
IBM Zurich Research Laboratory
Micro-/Nanomechanics
Säumerstraße 4
8803 Rüschlikon, Switzerland
e-mail: *gbi@zurich.ibm.com*

Marcie R. Black
Massachusetts Institute of Technology
Department of Electrical Engineering
and Computer Science
77 Massachusetts Avenue
Cambridge, MA 02139, USA
e-mail: *marcie@alum.mit.edu*

Jean-Marc Broto
University Toulouse III
Laboratoire National
des Champs Magnétiques Pulsés (LNCMP)
143 Avenue de Rangueil
31432 Toulouse Cedex 4, France
e-mail: *broto@insa-tlse.fr*

Robert W. Carpick
University of Wisconsin-Madison
Department of Engineering Physics
1500 Engineering Drive
Madison, WI 53706-1687, USA
e-mail: *carpick@engr.wisc.edu*

Tsung-Lin Chen
National Chiao Tung University
Department of Mechanical Engineering
30050 Shin Chu, Taiwan
e-mail: *tsunglin@mail.nctu.edu.tw*

Yu-Ting Cheng
National Chiao Tung University
Department of Electronics Engineering
& Institute of Electronics
1001, Ta-Hsueh Road
300 HsinChu, Taiwan
e-mail: *ytcheng@faculty.nctu.edu.tw*

Giovanni Cherubini
IBM Zurich Research Laboratory
Storage Technologies
Säumerstraße 4
8803 Rüschlikon, Switzerland
e-mail: *cbi@zurich.ibm.com*

Jin-Woo Choi
Louisiana State University
Department of Electrical
and Computer Engineering
102 South Campus Drive
Baton Rouge, LA 70803-5901, USA
e-mail: *choi@ece.lsu.edu*

Shawn J. Cunningham
WiSpry, Inc.
Colorado Springs Design Center
7150 Campus Drive, Suite 255
Colorado Springs, CO 80920, USA
e-mail: *shawn.cunningham@wispry.com*

Michel Despont
IBM Zurich Research Laboratory
Micro-/Nanomechanics
Säumerstraße 4
8803 Rüschlikon, Switzerland
e-mail: *dpt@zurich.ibm.com*

Gene Dresselhaus
Massachusetts Institute of Technology
Francis Bitter Magnet Laboratory
77 Massachusetts Avenue
Cambridge, MA 02139, USA
e-mail: *gene@mgm.mit.edu*

Mildred S. Dresselhaus
Massachusetts Institute of Technology
Department of Electrical Engineering
and Computer Science and Department of Physics
77 Massachusetts Avenue
Cambridge, MA 02139, USA
e-mail: *millie@mgm.mit.edu*

Martin L. Dunn
University of Colorado at Boulder
Department of Mechanical Engineering
Campus Box 427
Boulder, CO 80309, USA
e-mail: *martin.dunn@colorado.edu*

Urs T. Dürig
IBM Zurich Research Laboratory
Micro-/Nanomechanics
Säumerstraße 4
8803 Rüschlikon, Switzerland
e-mail: *drg@zurich.ibm.com*

Evangelos Eleftheriou
IBM Zurich Research Laboratory
Storage Technologies
Säumerstraße 4
8803 Rüschlikon, Switzerland
e-mail: *ele@zurich.ibm.com*

Mauro Ferrari
Ohio State University
Biomedical Engineering Center
1080 Carmack Road
Columbus, OH 43210-1002, USA
e-mail: *Ferrari.5@osu.edu*

Emmanuel Flahaut
Université Paul Sabatier
CIRIMAT (Centre Interuniversitaire de Recherche
et d'Ingénierie des Matériaux)
118 Route de Narbonne
31062 Toulouse Cedex 04, France
e-mail: *flahaut@chimie.ups-tlse.fr*

Lásló Forró
Swiss Federal Institute of Technology (EPFL)
Institute of Physics of Complex Matter
Ecublens
1015 Lausanne, Switzerland
e-mail: *laszlo.forro@epfl.ch*

Jane Frommer
IBM Almaden Research Center
Department of Science and Technology
650 Harry Road
San Jose, CA 95120, USA
e-mail: *frommer@Almaden.ibm.com*

Harald Fuchs
Universität Münster
Physikalisches Institut
Wilhelm-Klemm-Straße 10
48149 Münster, Germany
e-mail: *fuchsh@uni-muenster.de*

Franz J. Giessibl
Universität Augsburg
Lehrstuhl für Experimentalphysik VI
Universitätsstraße 1
86135 Augsburg, Germany
e-mail: *franz.giessibl@physik.uni-augsburg.de*

Enrico Gnecco
University of Basel
Department of Physics
Klingelbergstraße 82
4056 Basel, Switzerland
e-mail: *Enrico.Gnecco@unibas.ch*

Gérard Gremaud
Swiss Federal Institute of Technology (EPFL)
Institute of Physics of Complex Matter
Ecublens
1015 Lausanne, Switzerland
e-mail: *gremaud@epfl.ch*

Jason H. Hafner
Rice University
Department of Physics & Astronomy
PO BOX 1892
Houston, TX 77251-1892, USA
e-mail: *hafner@rice.edu*

Stefan Hengsberger
University of Applied Science of Fribourg
Bd de Pérolles
1705 Fribourg, Switzerland
e-mail: *stefan.hengsberger@eif.ch*

Peter Hinterdorfer
Johannes Kepler University of Linz
Institute for Biophysics
Altenbergerstraße 69
4040 Linz, Austria
e-mail: *peter.hinterdorfer@jku.at*

B. Bhushan • © Springer 2004

Roberto Horowitz
University of California at Berkeley
Department of Mechanical Engineering
5121 Etcheverry Hall
Berkeley, CA 94720-1742, USA
e-mail: *horowitz@me.berkeley.edu*

Hirotaka Hosoi
Japan Science and Technology Corporation
Innovation Plaza, Hokkaido
060-0819 Sapporo, Japan
e-mail: *hosoi@sapporo.jst-plaza.jp*

Jacob N. Israelachvili
University of California
Department of Chemical Engineering
and Materials Department
Santa Barbara, CA 93106, USA
e-mail: *Jacob@engineering.ucsb.edu*

Ghassan E. Jabbour
University of Arizona
Optical Sciences Center
1630 East University Boulevard
Tucson, AZ 85721, USA
e-mail: *gej@optics.arizona.edu*

Harold Kahn
Case Western Reserve University
Department of Materials Science and Engineering
10900 Euclid Avenue
Cleveland, OH 44106-7204, USA
e-mail: *kahn@cwru.edu*

András Kis
Swiss Federal Institute of Technology (EPFL)
Institute of Physics of Complex Matter
Ecublens
1015 Lausanne, Switzerland
e-mail: *andras@igahpse.epfl.ch*

Jané Kondev
Brandeis University
Physics Department
Waltham, MA 02454, USA
e-mail: *kondev@brandeis.edu*

Andrzej J. Kulik
Swiss Federal Institute of Technology (EPFL)
Institute of Physics of Complex Matter
1015 Lausanne, Switzerland
e-mail: *andrzej.kulik@epfl.ch*

Christophe Laurent
Université Paul Sabatier
CIRIMAT (Centre Interuniversitaire de Recherche
et d'Ingénierie des Matériaux)
118 Route de Narbonne
31062 Toulouse Cedex 04, France
e-mail: *laurent@chimie.ups-tlse.fr*

Stephen C. Lee
Ohio State University
Biomedical Engineering Center
1080 Carmack Road
Columbus, OH 43210-1002, USA
e-mail: *Lee@bme.ohio-state.edu*

Yunfeng Li
University of California at Berkeley
Department of Mechanical Engineering
5121 Etcheverry Hall
Berkeley, CA 94720-1740, USA
e-mail: *yunfeng@me.Berkeley.edu*

Liwei Lin
University of California at Berkeley
Mechanical Engineering Department
5126 Etcheverry
Berkeley, CA 94720-1740, USA
e-mail: *lwlin@me.berkeley.edu*

Yu-Ming Lin
Massachusetts Institute of Technology
Department of Electrical Engineering
and Computer Science
77 Massachusetts Avenue
Cambridge, MA 02139, USA
e-mail: *yming@mgm.mit.edu*

Huiwen Liu
Ohio State University
Nanotribology Laboratory for Information Storage and MEMS/NEMS
3070 St John Ct 7
Columbus, OH 43210-1107, USA
e-mail: *liu.403@osu.edu*

Adrian B. Mann
Rutgers University
Department of Ceramics and Materials Engineering
607 Taylor Road
Piscataway, NJ 08854, USA
e-mail: *abmann@rci.rutgers.edu*

Othmar Marti
University of Ulm
Department of Experimental Physics
Albert-Einstein-Allee 11
89069 Ulm, Germany
e-mail: *Othmar.Marti@physik.uni-ulm.de*

Jack Martin
Analog Devices, Inc.
Micromachined Products Division
21 Osborn Street
Cambridge, MA 02139, USA
e-mail: *jack.martin@analog.com*

Brendan McCarthy
University of Arizona
Optical Sciences Center
1630 East University Boulevard
Tucson, AZ 85721, USA
e-mail: *bmccarthy@optics.arizona.edu*

Mehran Mehregany
Case Western Reserve University
Department of Electrical Engineering
and Computer Science
188 Bingham Building
Cleveland, OH 44106, USA
e-mail: *mxm31@cwru.edu*

Ernst Meyer
University of Basel
Institute of Physics
Klingelbergstraße 82
4056 Basel, Switzerland
e-mail: *Ernst.Meyer@unibas.ch*

Marc Monthioux
UPR A-8011 CNRS
Centre d'Elaboration des Matériaux
et d'Etudes Structurales (CEMES)
29 Rue Jeanne Marvig
31055 Toulouse Cedex 4, France
e-mail: *monthiou@cemes.fr*

Markus Morgenstern
University of Hamburg
Institute of Applied Physics
Jungiusstraße 11
20355 Hamburg, Germany
e-mail: *mmorgens@physnet.uni-hamburg.de*

Seizo Morita
Osaka University
Department of Electronic Engineering
Yamada-Oka 2-1
565-0871 Suita-Citiy, Osaka, Japan
e-mail: *smorita@ele.eng.osaka-u.ac.jp*

Koichi Mukasa
Hokkaido University
Nanoelectronics Laboratory
Nishi-8, Kita-13, Kita-ku
060-8628 Sapporo, Japan
e-mail: *mukasa@nano.eng.hokudai.ac.jp*

Martin H. Müser
University of Western Ontario
Department of Applied Mathematics
WSC 139, Faculty of Science
London, Ontario N6A 5B7, Canada
e-mail: *mmuser@uwo.ca*

Kenn Oldham
University of California at Berkeley
Department of Mechanical Engineering
5121 Etcheverry Hall
Berkeley, CA 94720-1740, USA
e-mail: *oldham@newton.berkeley.edu*

Hiroshi Onishi
Kanagawa Academy of Science and Technology
Surface Chemistry Laboratory
KSP East 404, 3-2-1 Sakado, Takatsu-ku,
Kawasaki-shi
213-0012 Kanagawa, Japan
e-mail: *oni@net.ksp.or.jp*

René M. Overney
University of Washington
Department of Chemical Engineering
Seattle, WA 98195-1750, USA
e-mail: *roverney@u.Washington.edu*

Alain Peigney
Université Paul Sabatier
CIRIMAT (Centre Inter-universitaire de Recherches
et d'Ingénierie des Matériaux) – UMR CNRS 5085
118 Route de Narbonne
31062 Toulouse Cedex 4, France
e-mail: *peigney@chimie.ups-tlse.fr*

Oliver Pfeiffer
University of Basel
Institute of Physics
Klingelbergstraß 82
4056 Basel, Switzerland
e-mail: *Oliver.Pfeiffer@stud.unibas.ch*

Rob Phillips
California Institute of Technology
Mechanical Engineering and Applied Physics
1200 California Boulevard
Pasadena, CA 91125, USA
e-mail: *phillips@aero.caltech.edu*

Haralampos Pozidis
IBM Zurich Research Laboratory
Storage Technologies
Säumerstraße 4
8803 Rüschlikon, Switzerland
e-mail: *hap@zurich.ibm.com*

Prashant K. Purohit
California Institute of Technology
Mechanical Engineering
1200 California Boulevard
Pasadena, CA 91125, USA
e-mail: *prashant@caltech.edu*

Oded Rabin
Massachusetts Institute of Technology
Department of Chemistry
77 Massachusetts Avenue
Cambridge, MA 02139, USA
e-mail: *oded@mgm.mit.edu*

Françisco M. Raymo
University of Miami
Department of Chemistry
1301 Memorial Drive
Coral Gables, FL 33146-0431, USA
e-mail: *fraymo@miami.edu*

Manitra Razafinimanana
Université Paul Sabatier
Centre de Physique des Plasmas
et leurs Applications (CPPAT)
118 Route de Narbonne
31062 Toulouse Cedex, France
e-mail: *razafinimanana@cpat.ups-tlse.fr*

Mark O. Robbins
Johns Hopkins University
Department of Physics and Astronomy
3400 North Charles Street
Baltimore, MD 21218, USA
e-mail: *mr@jhu.edu*

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

John A. Rogers
University of Illinois
Department of Materials Science and Engineering
1304 W. Green Street
Urbana, IL 61801, USA
e-mail: *jrogers@uiuc.edu*

Mark Ruegsegger
Ohio State University
Biomedical Engineering Center
1080 Carmack Road
Columbus, OH 43210, USA
e-mail: *mark@bme.ohio-state.edu*

Marina Ruths
Åbo Akademi University
Department of Physical Chemistry
Porthansgatan 3–5
20500 Åbo, Finland
e-mail: *mruths@abo.fi*

Dror Sarid
University of Arizona
Optical Sciences Center
1630 East University Boulevard
Tucson, AZ 85721, USA
e-mail: *sarid@optics.arizona.edu*

Akira Sasahara
Kanagawa Academy of Science and Technology
Surface Chemistry Laboratory
KSP East 404, 3-2-1 Sakado, Takatsu-ku,
Kawasaki-shi
213-0012 Kanagawa, Japan
e-mail: *ryo@net.ksp.or.jp*

André Schirmeisen
University of Münster
Institute of Physics
Whilhem-Klemm-Straße 10
48149 Münster, Germany
e-mail: *schira@uni-muenster.de*

Alexander Schwarz
University of Hamburg
Institute of Applied Physics
Jungiusstraße 11
20355 Hamburg, Germany
e-mail: *aschwarz@physnet.uni-hamburg.de*

Udo D. Schwarz
Yale University
Department of Mechanical Engineering
15 Prospect Street
New Haven, CT 06510, USA
e-mail: *udo.schwarz@yale.edu*

Philippe Serp
Ecole Nationale Supèrieure d'Ingénieurs
en Arts Chimiques et Technologiques
Laboratoire de Catalyse, Chimie Fine et Polymères
118 Route de Narbonne
31077 Toulouse, France
e-mail: *Philippe.Serp@ensiacet.fr*

Bryan R. Smith
Ohio State University
Biomedical Engineering Center
1080 Carmack Road
Columbus, OH 43210, USA
e-mail: *bryan@bme.ohio-state.edu*

Anisoara Socoliuc
University of Basel
Institute of Physics
Klingelbergstraße 82
4056 Basel, Switzerland
e-mail: *A.Socoliuc@unibas.ch*

Yasuhiro Sugawara
Osaka University
Department of Applied Physics
Yamada-Oka 2-1
565-0871 Suita, Japan
e-mail: *sugawara@ap.eng.osaka-u.ac.jp*

George W. Tyndall
IBM Almaden Research Center
Science and Technology
6369 Didion Ct.
San Jose, CA 95123, USA
e-mail: *tyndallgw@netscape.net*

Peter Vettiger
IBM Zurich Research Laboratory
Manager Micro-/Nanomechanics
Säumerstraße 4
8803 Rüschlikon, Switzerland
e-mail: *pv@zurich.ibm.com*

Darrin J. Young
Case Western Reserve University
Electrical Engineering and Computer Science
10900 Euclid Avenue
Cleveland, OH 44106, USA
e-mail: *djy@po.cwru.edu*

Babak Ziaie
University of Minnesota
Department of Electrical
and Computer Engineering
200 Union Street SE
Minneapolis, MN 55455, USA
e-mail: *ziaie@ece.umn.edu*

Christian A. Zorman
Case Western Reserve University
Department of Electrical Engineering
and Computer Science
719 Glennan Building
Cleveland, OH 44106, USA
e-mail: *caz@po.cwru.edu*

Philippe K. Zysset
Technische Universität Wien
Institut für Leichtbau und Flugzeugbau (ILFB)
Gußhausstraße 27–29
1040 Wien, Austria
e-mail: *philippe.zysset@epfl.ch*

Contents

List of Tables XXIX
List of Abbreviations XXXIII

1 **Introduction to Nanotechnology** 1
  1.1 Background and Definition of Nanotechnology 1
  1.2 Why Nano? 2
  1.3 Lessons from Nature 2
  1.4 Applications in Different Fields 3
  1.5 Reliability Issues of MEMS/NEMS 4
  1.6 Organization of the Handbook 5
  References 5

Part A Nanostructures, Micro/Nanofabrication, and Micro/Nanodevices

2 **Nanomaterials Synthesis and Applications: Molecule-Based Devices** 9
  2.1 Chemical Approaches to Nanostructured Materials 10
  2.2 Molecular Switches and Logic Gates 14
  2.3 Solid State Devices 22
  2.4 Conclusions and Outlook 35
  References 36

3 **Introduction to Carbon Nanotubes** 39
  3.1 Structure of Carbon Nanotubes 40
  3.2 Synthesis of Carbon Nanotubes 45
  3.3 Growth Mechanisms of Carbon Nanotubes 59
  3.4 Properties of Carbon Nanotubes 63
  3.5 Carbon Nanotube-Based Nano-Objects 68
  3.6 Applications of Carbon Nanotubes 73
  References 86

4 **Nanowires** 99
  4.1 Synthesis 100
  4.2 Characterization and Physical Properties of Nanowires 110
  4.3 Applications 131
  4.4 Concluding Remarks 138
  References 138

5 **Introduction to Micro/Nanofabrication** 147
  5.1 Basic Microfabrication Techniques 148
  5.2 MEMS Fabrication Techniques 159

5.3 Nanofabrication Techniques 170
References 180

6 **Stamping Techniques for Micro and Nanofabrication: Methods and Applications** 185
6.1 High Resolution Stamps 186
6.2 Microcontact Printing 187
6.3 Nanotransfer Printing 190
6.4 Applications 193
6.5 Conclusions 200
References 200

7 **Materials Aspects of Micro- and Nanoelectromechanical Systems** 203
7.1 Silicon 203
7.2 Germanium-Based Materials 210
7.3 Metals 211
7.4 Harsh Environment Semiconductors 212
7.5 GaAs, InP, and Related III-V Materials 217
7.6 Ferroelectric Materials 218
7.7 Polymer Materials 219
7.8 Future Trends 220
References 221

8 **MEMS/NEMS Devices and Applications** 225
8.1 MEMS Devices and Applications 227
8.2 NEMS Devices and Applications 246
8.3 Current Challenges and Future Trends 249
References 250

9 **Microfluidics and Their Applications to Lab-on-a-Chip** 253
9.1 Materials for Microfluidic Devices and Micro/Nano Fabrication Techniques 254
9.2 Active Microfluidic Devices 257
9.3 Smart Passive Microfluidic Devices 262
9.4 Lab-on-a-Chip for Biochemical Analysis 270
References 276

10 **Therapeutic Nanodevices** 279
10.1 Definitions and Scope of Discussion 280
10.2 Synthetic Approaches: “top-down” versus “bottom-up” Approaches for Nanotherapeutic Device Components 285
10.3 Technological and Biological Opportunities 288
10.4 Applications for Nanotherapeutic Devices 307
10.5 Concluding Remarks: Barriers to Practice and Prospects 315
References 317

Part B Scanning Probe Microscopy

11 **Scanning Probe Microscopy – Principle of Operation, Instrumentation, and Probes** 325
11.1 Scanning Tunneling Microscope 327
11.2 Atomic Force Microscope 331
11.3 AFM Instrumentation and Analyses 347
References 364

12 **Probes in Scanning Microscopies** 371
12.1 Atomic Force Microscopy 372
12.2 Scanning Tunneling Microscopy 382
References 383

13 **Noncontact Atomic Force Microscopy and Its Related Topics** 385
13.1 Principles of Noncontact Atomic Force Microscope (NC-AFM) 386
13.2 Applications to Semiconductors 391
13.3 Applications to Insulators 397
13.4 Applications to Molecules 404
References 407

14 **Low Temperature Scanning Probe Microscopy** 413
14.1 Microscope Operation at Low Temperatures 414
14.2 Instrumentation 415
14.3 Scanning Tunneling Microscopy and Spectroscopy 419
14.4 Scanning Force Microscopy and Spectroscopy 433
References 442

15 **Dynamic Force Microscopy** 449
15.1 Motivation: Measurement of a Single Atomic Bond 450
15.2 Harmonic Oscillator: A Model System for Dynamic AFM 454
15.3 Dynamic AFM Operational Modes 455
15.4 Q-Control 464
15.5 Dissipation Processes Measured with Dynamic AFM 468
15.6 Conclusion 471
References 471

16 **Molecular Recognition Force Microscopy** 475
16.1 Ligand Tip Chemistry 476
16.2 Fixation of Receptors to Probe Surfaces 478
16.3 Single-Molecule Recognition Force Detection 479
16.4 Principles of Molecular Recognition Force Spectroscopy 482
16.5 Recognition Force Spectroscopy: From Isolated Molecules to Biological Membranes 484
16.6 Recognition Imaging 489
16.7 Concluding Remarks 491
References 492

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Part C Nanotribology and Nanomechanics

17 **Micro/Nanotribology and Materials Characterization Studies Using Scanning Probe Microscopy** 497
- 17.1 Description of AFM/FFM and Various Measurement Techniques 499
- 17.2 Friction and Adhesion 507
- 17.3 Scratching, Wear, Local Deformation, and Fabrication/Machining ... 518
- 17.4 Indentation 526
- 17.5 Boundary Lubrication 530
- 17.6 Closure 538
- References 539

18 **Surface Forces and Nanorheology of Molecularly Thin Films** 543
- 18.1 Introduction: Types of Surface Forces 544
- 18.2 Methods Used to Study Surface Forces 546
- 18.3 Normal Forces Between Dry (Unlubricated) Surfaces 550
- 18.4 Normal Forces Between Surfaces in Liquids 554
- 18.5 Adhesion and Capillary Forces 564
- 18.6 Introduction: Different Modes of Friction and the Limits of Continuum Models 569
- 18.7 Relationship Between Adhesion and Friction Between Dry (Unlubricated and Solid Boundary Lubricated) Surfaces 571
- 18.8 Liquid Lubricated Surfaces 580
- 18.9 Role of Molecular Shape and Surface Structure in Friction 591
- References 594

19 **Scanning Probe Studies of Nanoscale Adhesion Between Solids in the Presence of Liquids and Monolayer Films** 605
- 19.1 The Importance of Adhesion at the Nanoscale 605
- 19.2 Techniques for Measuring Adhesion 606
- 19.3 Calibration of Forces, Displacements, and Tips 610
- 19.4 The Effect of Liquid Capillaries on Adhesion 612
- 19.5 Self-Assembled Monolayers 618
- 19.6 Concluding Remarks 624
- References 624

20 **Friction and Wear on the Atomic Scale** 631
- 20.1 Friction Force Microscopy in Ultra-High Vacuum 632
- 20.2 The Tomlinson Model 636
- 20.3 Friction Experiments on Atomic Scale 638
- 20.4 Thermal Effects on Atomic Friction 642
- 20.5 Geometry Effects in Nanocontacts 646
- 20.6 Wear on the Atomic Scale 649
- 20.7 Molecular Dynamics Simulations of Atomic Friction and Wear 651
- 20.8 Energy Dissipation in Noncontact Atomic Force Microscopy 654
- 20.9 Conclusion 656
- References 657

21 **Nanoscale Mechanical Properties – Measuring Techniques and Applications** 661
21.1 Local Mechanical Spectroscopy by Contact AFM 662
21.2 Static Methods – Mesoscopic Samples 667
21.3 Scanning Nanoindentation: An Application to Bone Tissue 674
21.4 Conclusions and Perspectives 682
References 682

22 **Nanomechanical Properties of Solid Surfaces and Thin Films** 687
22.1 Instrumentation 688
22.2 Data Analysis 694
22.3 Modes of Deformation 702
22.4 Thin Films and Multilayers 707
22.5 Developing Areas 711
References 712

23 **Atomistic Computer Simulations of Nanotribology** 717
23.1 Molecular Dynamics 718
23.2 Friction Mechanisms at the Atomic Scale 723
23.3 Stick-Slip Dynamics 732
23.4 Conclusions 734
References 735

24 **Mechanics of Biological Nanotechnology** 739
24.1 Science at the Biology–Nanotechnology Interface 740
24.2 Scales at the Bio-Nano Interface 746
24.3 Modeling at the Nano-Bio Interface 752
24.4 Nature's Nanotechnology Revealed: Viruses as a Case Study 755
24.5 Concluding Remarks 760
References 761

25 **Mechanical Properties of Nanostructures** 763
25.1 Experimental Techniques for Measurement of Mechanical Properties of Nanostructures 765
25.2 Experimental Results and Discussion 770
25.3 Finite Element Analysis of Nanostructures with Roughness and Scratches 778
25.4 Closure 785
References 786

Part D Molecularly Thick Films for Lubrication

26 **Nanotribology of Ultrathin and Hard Amorphous Carbon Films** 791
26.1 Description of Commonly Used Deposition Techniques 795
26.2 Chemical Characterization and Effect of Deposition Conditions on Chemical Characteristics and Physical Properties 800

26.3 Micromechanical and Tribological Characterizations of Coatings Deposited by Various Techniques 805
References 827

27 **Self-Assembled Monolayers for Controlling Adhesion, Friction and Wear** 831
27.1 A Primer to Organic Chemistry 834
27.2 Self-Assembled Monolayers: Substrates, Head Groups, Spacer Chains, and End Groups 839
27.3 Tribological Properties of SAMs 841
27.4 Closure 856
References 857

28 **Nanoscale Boundary Lubrication Studies** 861
28.1 Lubricants Details 862
28.2 Nanodeformation, Molecular Conformation, and Lubricant Spreading 864
28.3 Boundary Lubrication Studies 866
28.4 Closure 880
References 881

29 **Kinetics and Energetics in Nanolubrication** 883
29.1 Background: From Bulk to Molecular Lubrication 885
29.2 Thermal Activation Model of Lubricated Friction 887
29.3 Functional Behavior of Lubricated Friction 888
29.4 Thermodynamical Models Based on Small and Nonconforming Contacts 890
29.5 Limitation of the Gaussian Statistics – The Fractal Space 891
29.6 Fractal Mobility in Reactive Lubrication 892
29.7 Metastable Lubricant Systems in Large Conforming Contacts 894
29.8 Conclusion 895
References 895

Part E Industrial Applications and Microdevice Reliability

30 **Nanotechnology for Data Storage Applications** 899
30.1 Current Status of Commercial Data Storage Devices 901
30.2 Opportunities Offered by Nanotechnology for Data Storage 907
30.3 Conclusion 918
References 919

31 **The "Millipede" – A Nanotechnology-Based AFM Data-Storage System** 921
31.1 The Millipede Concept 923
31.2 Thermomechanical AFM Data Storage 924
31.3 Array Design, Technology, and Fabrication 926

31.4 Array Characterization 927
31.5 *x*/*y*/*z* Medium Microscanner 929
31.6 First Write/Read Results with the 32×32 Array Chip 931
31.7 Polymer Medium 932
31.8 Read Channel Model 939
31.9 System Aspects 943
31.10 Conclusions 948
References 948

32 **Microactuators for Dual-Stage Servo Systems in Magnetic Disk Files** 951
32.1 Design of the Electrostatic Microactuator 952
32.2 Fabrication 962
32.3 Servo Control Design of MEMS Microactuator Dual-Stage Servo Systems 968
32.4 Conclusions and Outlook 978
References 979

33 **Micro/Nanotribology of MEMS/NEMS Materials and Devices** 983
33.1 Introduction to MEMS 985
33.2 Introduction to NEMS 988
33.3 Tribological Issues in MEMS/NEMS 989
33.4 Tribological Studies of Silicon and Related Materials 995
33.5 Lubrication Studies for MEMS/NEMS 1003
33.6 Component-Level Studies 1009
References 1017

34 **Mechanical Properties of Micromachined Structures** 1023
34.1 Measuring Mechanical Properties of Films on Substrates 1023
34.2 Micromachined Structures for Measuring Mechanical Properties 1024
34.3 Measurements of Mechanical Properties 1034
References 1037

35 **Thermo- and Electromechanics of Thin-Film Microstructures** 1039
35.1 Thermomechanics of Multilayer Thin-Film Microstructures 1041
35.2 Electromechanics of Thin-Film Microstructures 1061
35.3 Summary and Mention of Topics not Covered 1078
References 1078

36 **High Volume Manufacturing and Field Stability of MEMS Products** 1083
36.1 Manufacturing Strategy 1086
36.2 Robust Manufacturing 1087
36.3 Stable Field Performance 1102
References 1106

37 **MEMS Packaging and Thermal Issues in Reliability** 1111
37.1 MEMS Packaging 1111
37.2 Hermetic and Vacuum Packaging and Applications 1116
37.3 Thermal Issues and Packaging Reliability 1122
37.4 Future Trends and Summary 1128
References 1129

Part F Social and Ethical Implication

38 **Social and Ethical Implications of Nanotechnology** 1135
38.1 Applications and Societal Impacts 1136
38.2 Technological Convergence 1139
38.3 Major Socio-technical Trends 1141
38.4 Sources of Ethical Behavior 1143
38.5 Public Opinion 1145
38.6 A Research Agenda 1148
References 1149

Acknowledgements 1153
About the Authors 1155
Detailed Contents 1171
Subject Index 1189

List of Tables

Part A Nanostructures, Micro/Nanofabrication, and Micro/Nanodevices

3 Introduction to Carbon Nanotubes

Table 3.1 Different carbon morphologies 50
Table 3.2 Carbon nanofilament morphologies and some basic synthesis conditions 62
Table 3.3 Adsorption properties and sites of SWNTs and MWNTs 65
Table 3.4 Preparation and catalytic performances of some nanotube-supported catalysts................................. 77
Table 3.5 Applications for nanotube-based multifunctional materials ... 84

4 Nanowires

Table 4.1 Selected syntheses of nanowires by material 101

5 Introduction to Micro/Nanofabrication

Table 5.1 Typical dry etch chemistries... 157
Table 5.2 Surface micromachined sacrificial/structural combinations 165

7 Materials Aspects of Micro- and Nanoelectromechanical Systems

Table 7.1 Selected materials for MEMS and NEMS................................. 204

9 Microfluidics and Their Applications to Lab-on-a-Chip

Table 9.1 Overview of the different polymer micro/nano fabrication techniques 257

10 Therapeutic Nanodevices

Table 10.1 Ideal characteristics of nanodevices...................................... 282
Table 10.2 Orthogonal conjugation chemistries 295

Part B Scanning Probe Microscopy

11 Scanning Probe Microscopy – Principle of Operation, Instrumentation, and Probes

Table 11.1 Comparison of Various Conventional Microscopes with SPMs ... 326
Table 11.2 Relevant properties of materials used for cantilevers............. 339
Table 11.3 Measured vertical spring constants and natural frequencies of triangular (V-shaped) cantilevers made of PECVD Si_3N_4 341
Table 11.4 Vertical and torsional spring constants of rectangular cantilevers made of Si and PECVD.................... 341
Table 11.5 Noise in Interferometers 353

13 Noncontact Atomic Force Microscopy and Its Related Topics

Table 13.1 Comparison between the adatom heights observed in an AFM image and the variety of properties for inequivalent adatoms 393

Part C Nanotribology and Nanomechanics

17 Micro/Nanotribology and Materials Characterization Studies Using Scanning Probe Microscopy

Table 17.1 Comparison of typical operating parameters in SFA, STM, and AFM/FFM used for micro/nanotribological studies............ 498
Table 17.2 Surface roughness and coefficients of friction of various samples in air.. 518

18 Surface Forces and Nanorheology of Molecularly Thin Films

Table 18.1 Types of surface forces in vacuum vs. in liquid (colloidal forces) 545
Table 18.2 Van der Waals interaction energy and force between macroscopic bodies of different geometries 551
Table 18.3 Electrical "double-layer" interaction energy and force between macroscopic bodies.. 556
Table 18.4 The three main tribological regimes characterizing the changing properties of liquids.. 570
Table 18.5 Effect of molecular shape and short-range forces on tribological properties.. 592

19 Scanning Probe Studies of Nanoscale Adhesion Between Solids in the Presence of Liquids and Monolayer Films

Table 19.1 Interactions evaluated by atomic force microscopy adhesion measurements... 620

21 Nanoscale Mechanical Properties – Measuring Techniques and Applications

Table 21.1 Summary of the mechanical properties of carbon nanotubes.. 672
Table 21.2 Absolute and relative changes of the indentation modulus with respect to the initial values under wet conditions 680

22 Nanomechanical Properties of Solid Surfaces and Thin Films

Table 22.1 Results for some experimental studies of multilayer hardness 710

24 Mechanics of Biological Nanotechnology

Table 24.1 Sizes of entities in comparison to the size of *E. coli* 748
Table 24.2 Time scales of various events in biological nanotechnology 750

25 Mechanical Properties of Nanostructures

Table 25.1 Hardness, elastic modulus, fracture toughness, and critical load results of the bulk single-crystal Si(100) and thin films of undoped polysilicon, SiO_2, SiC, Ni-P, and Au 770

Table 25.2 Summary of measured parameters from quasi-static bending tests 775
Table 25.3 Stresses and displacements for materials that are elastic, elastic-plastic, or elastic-perfectly plastic 784

Part D Molecularly Thick Films for Lubrication

26 Nanotribology of Ultrathin and Hard Amorphous Carbon Films

Table 26.1 Summary of the most commonly used deposition techniques . 796
Table 26.2 Experimental results from EELS and Raman spectroscopy 801
Table 26.3 Experimental results of FRS analysis 802
Table 26.4 Experimental results of physical properties 802
Table 26.5 Hardness, elastic modulus, fracture toughness, fatigue life, critical load during scratch, coefficient of friction of various DLC coatings 809

27 Self-Assembled Monolayers for Controlling Adhesion, Friction and Wear

Table 27.1 Relative electronegativity of selected elements 835
Table 27.2 Names and formulas of selected hydrocarbons 836
Table 27.3 Names and formulas of selected alcohols, ethers, phenols, and thiols 836
Table 27.4 Names and formulas of selected aldehydes and ketones 837
Table 27.5 Names and formulas of selected carboxylic acids and esters ... 838
Table 27.6 Names and formulas of selected organic nitrogen compounds 838
Table 27.7 Some examples of polar and nonpolar groups 839
Table 27.8 Organic groups listed in the increasing order of polarity 839
Table 27.9 Selected substrates and precursors used for formation of SAMs 840
Table 27.10 The roughness, thickness, tilt angles, and spacer chain lengths of SAMs 846
Table 27.11 Melting point of typical organic compounds similar to HDT and BPT SAMs 851
Table 27.12 Calculated and measured relative heights of HDT and MHA self-assembled monolayers 855
Table 27.13 Calculated and measured residual film thickness for SAMs under critical load 855
Table 27.14 Bond strengths of the chemical bonds in SAMs 856

28 Nanoscale Boundary Lubrication Studies

Table 28.1 Typical properties of Z-15 and Z-DOL 863

Part E Industrial Applications and Microdevice Reliability

30 Nanotechnology for Data Storage Applications

Table 30.1 A comparison of the parameters of HDD and ODD 903

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Table 30.2 Perceived technical limits for hard disk drive technology........ 904
Table 30.3 A table of probe storage operating parameters 909
Table 30.4 Probe storage projected performance 909

31 The "Millipede" – A Nanotechnology-Based AFM Data-Storage System

Table 31.1 Areal density and storage capacity 947

32 Microactuators for Dual-Stage Servo Systems in Magnetic Disk Files

Table 32.1 Parameters of the electrostatic microactuator 960

33 Micro/Nanotribology of MEMS/NEMS Materials and Devices

Table 33.1 Dimensions and masses in perspective 985
Table 33.2 Selected bulk properties of SiC and Si(100)............................. 996
Table 33.3 Surface roughness and micro- and macroscale coefficients of friction of selected samples... 997
Table 33.4 RMS, microfriction, microscratching/microwear, and nanoindentation hardness data for various virgin, coated, and treated silicon samples 999
Table 33.5 Summary of micro/nanotribological properties of the sample materials 1001
Table 33.6 Surface roughness parameters and microscale coefficient of friction 1009
Table 33.7 Coefficient of static friction measurements of MEMS devices and structures 1015

35 Thermo- and Electromechanics of Thin-Film Microstructures

Table 35.1 Stresses, curvature, and strains in a film/substrate system...... 1045
Table 35.2 Predicted and measured curvature per unit negative temperature change for gold/polysilicon microstructures as a function of the polysilicon thickness. 1053

37 MEMS Packaging and Thermal Issues in Reliability

Table 37.1 Summary of bonding mechanisms....................................... 1116
Table 37.2 The Maximum Likelihood Estimation for Mean Time To Failure (MTTF) 1127

List of Abbreviations

μCP	microcontact printing
μTAS	micro-total analysis systems
2-DEG	two-dimensional electron gas

A

A	adenine
ABS	air-bearing surface
ADEPTS	antibody directed enzyme-prodrug therapy
AFAM	atomic force acoustic microscopy
AFM	atomic force microscope/microscopy
AIDCN	2-amino-4,5-imidazoledicarbonitrile
AM	amplitude modulation
APCVD	atmospheric pressure chemical vapor deposition
ASA	anti-stiction agent
ATP	adenosine triphosphat

B

BE	boundary element
BioMEMS	biological or biomedical microelectromechanical systems
BP	bit pitch
BPI	bits per inch
bpsi	bits per square inch
BSA	bovine serum albumin

C

C	cytosine
CA	constant amplitude
CBA	cantilever beam array
CCVD	catalytic chemical vapor deposition
CDS	correlated double sampling
CDW	charge density wave
CE	capillary electrophoresis
CE	constant excitation mode
CFM	chemical force microscopy
CG	controlled geometry
CNT	carbon nanotube
COC	cyclic olefin copolymers
COF	chip-on-flex
COGs	cost of goods
CSM	continuous stiffness measurement
CTE	coefficient of thermal expansion
CTLs	cytoxic T-lymphocytes
CVD	chemical vapor deposition

D

DAS	dimer adatom stacking
DBR	distributed Bragg reflector
DCs	dendritic cells
DFB	distributed feedback
DFM	dynamic force microscopy
DFT	density functional theory
DLC	diamond-like carbon
DLP	digital light processing
DLVO	Derjaguin–Landau–Verwey–Overbeek
DMD	digital micromirror device
DMT	Derjaguin–Muller–Toporov
DOS	density of states
DPN	dip-pen nanolithography
DRIE	deep reactive ion etching
DSC	differential scanning calorimetry
DSP	digital signal processor
DT	diphteria toxin
DWNTs	double-wall nanotubes

E

EAM	embedded atom method
EBD	electron beam deposition
ECR-CVD	electron cyclotron resonance chemical vapor deposition
EDC	1-ethyl-3-(3-diamethylaminoprophyl) carbodiimide
EDP	ethylene diamine pyrocatechol
EDS	energy dispersive X-ray spectrometer
EELS	electron energy loss spectrometer/spectroscopy
EFC	electrostatic force constant
EFM	electric field gradient microscopy
EHD	electrohydrodynamic
EL	electro-luminiscence
EO	electro-osmosis
EOF	electro-osmotic flow
EPR	enhanced permeability and retention effect
ESD	electrostatic discharge

F

FAD	flavin adenine dinucleotide
FC	flip chip technique
FCA	filtered cathodic arc
FCP	force calibration plot
FD	finite difference
FE	finite element
FEM	finite element method/modeling

FET	field-effect transistor
FFM	friction force microscope/microscopy
FIB	focused ion beam
FID	free induction decay
FIM	field-ion microscope/microscopy
FKT	Frenkel-Kontorova-Tomlinson
FM	frequency modulation
FM-AFM	frequency modulation AFM
FMEA	failure mode effect analysis
FMM	force modulation mode
FM-SFM	frequency-modulation SFM
FS	force spectroscopy

G

G	guanine
GIO	grazing impact oscillator
GMR	giant magnetoresistance
GOD	glucose oxidase
Gox	flavoenzyme glucose oxidase

H

HARMEMS	high-aspect-ratio MEMS
HDD	hard disk drive
HF	hydrofluoric acid
HOP	highly oriented pyrolytic
HOPG	highly oriented pyrolytic graphite
HPMA	hydroxyl polymethacrylamide
HtBDC	hexa-tert-butyl-decacyclene
HTCS	high temperature superconductivity

I

IBD	ion beam deposition
IC	integrated circuit
ICAM-1	intercellular adhesion molecule-1
IFM	interfacial force microscope
ISE	indentation size effect
ITO	indium tin oxide

J

JKR	Johnson–Kendall–Roberts

K

KPFM	Kelvin probe force microscopy

L

LB	Langmuir–Blodgett
LCC	leadless chip carrier
LDOS	local density of states
LEDs	light-emitting diodes
LFA-1	leukocyte function-associated antigen-1
LFM	lateral force microscope
LFT	linear fractional transformation
LN	liquid nitrogen
LPCVD	low pressure chemical vapor deposition
LQG	linear quadratic Gaussian
LTR	loop-transfer recovery
LTSPM	low-temperature SPM
LTSTS	low-temperature scanning tunneling spectroscopy
LVDT	linear variable differential transformers

M

MAP	manifold absolute pressure
MD	molecular dynamics
MDS	molecular dynamics simulation
ME	metal evaporated
MEMS	microelectromechanical systems
MFM	magnetic field microscope/microscopy
MHA	16-mercaptohexadecanoic acid thiol
MHC	major histocompatibility complex
MHD	magnetohydrodynamic
MIM	metal/insulator/metal
MLE	maximum likelihood estimator
MOCVD	metalorganic CVD
MP	metal particle
MPTMS	mercaptopropyltrimethoxysilane
MRAM	magnetoresistive RAM
MRFM	magnetic resonance force microscopy
MRFM	molecular recognition force microscopy
MRI	magnetic resonance imaging
MTTF	mean time to failure
MWCNT	multiwall carbon nanotube

N

NA	nucleic acid
NBMN	3-nitrobenzal malonitrile
NC-AFM	noncontact atomic force microscopy
NCS	neocarzinostatin
NEMS	nanoelectromechanical systems
NMP	no moving part
NNI	National Nanotechnology Initiative
NSOM	near-field scanning optical microscope/microscopy
NTA	nitrilotriacetate
nTP	nanotransfer printing
NVRAM	nonvolatile random access memories

O

ODD	optical disk drives
OMVPE	organometallic vapor phase epitaxy
OT	optical tweezers
OTE	octadecyltrimethoxysilane
OTS	octadecyltrichlorosilane

OUM	Ovonyx unified memory

P

P/W	power to weight
PA	plasminogen activator
PAMAM	poly(amido) amine
PAPP	p-aminophenyl phosphate
PC	ploycarbonate
PC-RAM	phase change RAM
pDA	1,4-phenylenediamine
PDMS	polydimethylsiloxane
PDP	2-pyridyldithiopropionyl
PE	polyethylene
PECVD	plasma enhanced CVD
PEG	poly(ethylene glycol)
PES	photoemission spectroscopy
PES	position error signal
PET	poly(ethylene terephthalate)
PFDA	perfluorodecanoic acid
PFPE	perfluoropolyether
PL	photoluminescence
PMMA	poly(methylmethacrylate)
PS	polystyrene
PSG	phosphorus-doped glass
PSGL-1	P-selection glycoprotein ligand-1
PTFE	polytetrafluoroethylene
PZT	lead zirconate titanate

Q

QCM	quartz-crystal microbalance

R

RES	reticuloendothelial system
RF	radiofrequency
RH	relative humidity
RICM	reflection interface contrast microscopy
RIE	reactive ion etching
RLS	recursive least square algorithm
RPES	relative position error signal
RTP	rapid thermal processing

S

SACA	static advancing contact angle
SAED	selected area electron diffraction
SAM	self-assembling monolayer
SAM	scanning acoustic microscopy
SCM	scanning capitance microscopy
SCPM	scanning chemical potential
SEcM	scanning electrochemical microscopy
SEFM	scanning electrostatic force microscopy
SEM	scanning electron microscope/microscopy
SFA	surface forces apparatus
SFAM	scanning force acoustic microscopy
SFD	shear flow detachment
SFM	scanning force microscopy
SFS	scanning force spectroscopy
SICM	scanning ion conductance microscopy
SIMO	single-input–multi-output
SISO	single-input–single-output
SKPM	scanning Kelvin probe microscopy
SLAM	scanning local-acceleration microscopy
SMA	shape memory alloy
SMANCS	S-Methacryl-neocarzinostatin
SMM	scanning magnetic microscopy
SN	scanning nanoindentation
SNOM	scanning near-field optical microscopy
SPM	scanning probe microscopy
sPROMS	structurally programmable microfluidic system
SPS	spark plasma sintering
SRAM	static random access memory
ssDNA	single stranded DNA
SSNA	single-stranded nucleic acid molecule
SThM	scanning thermal microscopy
STM	scanning tunneling microscope/microscopy
SWCNT	single-wall carbon nanotubes
SWNT	single-wall nanotubes

T

T	thymine
TAAs	tumor associated antigens
TEM	transmission electron microscopy
TESP	tapping-mode etched silicon probe
TGA	thermo-gravimetric analysis
TIRM	total internal reflection microscopy
TMAH	tetramethyl ammonium hydroxide
TMAH	tetramethyl-aluminium hydroxide
TP	track pitch
TPI	tracks per inch
TRM/TMR	track mis-registration
T-SLAM	variable-temperature SLAM
TTF	tetrathiofulvane

U

UHV	ultrahigh vacuum

V

VCM	voice coil motor
VCO	voltage-controlled oscillator
VLS	vapor-liquid-solid
VLSI	very large-scale integration

X

XRD	X-ray diffraction

1. Introduction to Nanotechnology

by B. Bhushan

A biological system can be exceedingly small. Many of the cells are very tiny, but they are very active; they manufacture various substances; they walk around; they wiggle; and they do all kinds of marvelous things – all on a very small scale. Also, they store information. Consider the possibility that we too can make a thing very small which does what we want – that we can manufacture an object that maneuvers at that level.

(From the talk "There's Plenty of Room at the Bottom", delivered by Richard P. Feynman at the annual meeting of the American Physical Society at the California Institute of Technology, Pasadena, CA, on December 29, 1959.)

1.1 **Background and Definition of Nanotechnology** 1

1.2 **Why Nano?** 2

1.3 **Lessons from Nature** 2

1.4 **Applications in Different Fields** 3

1.5 **Reliability Issues of MEMS/NEMS** 4

1.6 **Organization of the Handbook** 5

References 5

1.1 Background and Definition of Nanotechnology

On Dec. 29, 1959, at the California Institute of Technology, Nobel Laureate Richard P. Feynman gave a talk at the annual meeting of the American Physical Society that has become one of the twentieth century's classic science lectures, titled "There's Plenty of Room at the Bottom" [1.1]. He presented a technological vision of extreme miniaturization several years before the word "chip" became part of the lexicon. He talked about the problem of manipulating and controlling things on a small scale. Extrapolating from known physical laws, Feynman envisioned a technology using the ultimate toolbox of nature, building nanoobjects atom by atom or molecule by molecule. Since the 1980s, many inventions and discoveries in the fabrication of nanoobjects have become a testament to his vision. In recognition of this reality, the National Science and Technology Council (NSTC) of the White House created the Interagency Working Group on Nanoscience, Engineering and Technology (IWGN) in 1998. In a January 2000 speech at the same institute, former President William J. Clinton talked about the exciting promise of nanotechnology and, more generally, the importance of expanding research in nanoscale science and technology. Later that month, he announced in his State of the Union Address an ambitious $ 497 million federal, multi-agency National Nanotechnology Initiative (NNI) in the fiscal year 2001 budget, and made it a top science and technology priority [1.2, 3]. The objective of this initiative was to form a broad-based coalition in which academe, the private sector, and local, state, and federal governments would work together to push the envelope of nanoscience and nanoengineering to reap nanotechnology's potential social and economic benefits.

Nanotechnology literally means any technology performed on a nanoscale that has applications in the real world. Nanotechnology encompasses the production and application of physical, chemical, and biological systems at scales ranging from individual atoms or molecules to submicron dimensions, as well as the integration of the resulting nanostructures into larger systems. Nanotechnology is likely to have a profound impact on our economy and society in the early twenty-first century, comparable to that of semiconductor technology, information technology, or cellular and molecular biology. Science and technology research in nanotechnology promises breakthroughs in such areas as materials and manufacturing, nanoelectronics, medicine and healthcare, energy, biotechnology, information technology, and national security. It is widely felt that nanotechnology will be the next industrial revolution.

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Nanometer-scale features are mainly built up from their elemental constituents. Chemical synthesis – the spontaneous self-assembly of molecular clusters (molecular self-assembly) from simple reagents in solution – or biological molecules (e.g., DNA) are used as building blocks for the production of three-dimensional nanostructures, including quantum dots (nanocrystals) of arbitrary diameter (about 10 to 10^5 atoms). A variety of vacuum deposition and nonequilibrium plasma chemistry techniques are used to produce layered nanocomposites and nanotubes. Atomically controlled structures are produced using molecular beam epitaxy and organo-metallic vapor phase epitaxy. Micro- and nanosystem components are fabricated using top-down lithographic and nonlithographic fabrication techniques and range in size from micro- to nanometers. Continued improvements in lithography for use in the production of nanocomponents have resulted in line widths as small as 10 nanometers in experimental prototypes. The nanotechnology field, in addition to the fabrication of nanosystems, provides the impetus to development of experimental and computational tools.

The micro- and nanosystems include micro/nanoelectromechanical systems (MEMS/NEMS) (e.g., sensors, actuators, and miniaturized systems comprising sensing, processing, and/or actuating functions), micromechatronics, optoelectronics, microfluidics, and systems integration. These systems can sense, control, and activate on the micro/nanoscale and function individually or in arrays to generate effects on the macroscale. The microsystems market in 2000 was about $ 15 billion, and, with a projected 10–20 % annual growth rate, it is expected to increase to more than $ 100 billion by the end of this decade. The nanosystems market in 2001 was about $ 100 million and the integrated nanosystems market is expected to be more than $ 25 billion by the end of this decade. Due to the enabling nature of these systems, and because of the significant impact they can have on the commercial and defense applications, venture capitalists, industry, as well as the federal government have taken a special interest in nurturing growth in this field. Micro- and nanosystems are likely to be the next logical step in the "silicon revolution."

1.2 Why Nano?

The discovery of novel materials, processes, and phenomena at the nanoscale, as well as the development of new experimental and theoretical techniques for research provide fresh opportunities for the development of innovative nanosystems and nanostructured materials. Nanosystems are expected to find various unique applications. Nanostructured materials can be made with unique nanostructures and properties. This field is expected to open new venues in science and technology.

1.3 Lessons from Nature

Nanotechnology is a new word, but it is not an entirely new field. Nature has many objects and processes that function on a micro- to nanoscale [1.2, 4]. The understanding of these functions can guide us in imitating and producing nanodevices and nanomaterials.

Billions of years ago, molecules began organizing themselves into the complex structures that could support life. Photosynthesis harnesses solar energy to support plant life. Molecular ensembles are present in plants, which include light harvesting molecules, such as chlorophyll, arranged within the cells on the nanometer to micrometer scales. These structures capture light energy, and convert it into the chemical energy that drives the biochemical machinery of plant cells. Live organs use chemical energy in the body. The flagella, a type of bacteria, rotates at over 10,000 RPM [1.5]. This is an example of a biological molecular machine. The flagella motor is driven by the proton flow caused by the electrochemical potential differences across the membrane. The diameter of the bearing is about 20–30 nm, with an estimated clearance of about 1 nm.

In the context of tribology, some biological systems have anti-adhesion surfaces. First, many plant leaves (such as lotus leaf) are covered by a hydrophobic cuticle, which is composed of a mixture of large hydrocarbon molecules that have a strong hydrophobia. Second, the surface is made of a unique roughness distribution [1.6, 7]. It has been reported that for some leaf surfaces, the roughness of the hydrophobic leaf surface decreases wetness, which is reflected in a greater contact angle of water droplets on such surfaces.

1.4 Applications in Different Fields

Science and technology continue to move forward in making the fabrication of micro/nanodevices and systems possible for a variety of industrial, consumer, and biomedical applications. A range of MEMS devices have been produced, some of which are commercially used [1.4, 8–12]. A variety of sensors are used in industrial, consumer, and biomedical applications. Various microstructures or microcomponents are used in micro-instruments and other industrial applications, such as micromirror arrays. Two of the largest "killer" industrial applications are accelerometers (about 85 million units in 2002) and digital micromirror devices (about $ 400 million in sales in 2001). Integrated capacitive-type, silicon accelerometers have been used in airbag deployment in automobiles since 1991 [1.13, 14]. Accelerometer technology was about a billion-dollar-a-year industry in 2001, dominated by Analog Devices followed by Motorola and Bosch. Commercial digital light processing (DLP) equipment using digital micromirror devices (DMD) were launched in 1996 by Texas Instruments for digital projection displays in portable and home theater projectors, as well as table-top and projection TVs [1.15, 16]. More than 1.5 million projectors were sold before 2002. Other major industrial applications include pressure sensors, inkjet printer heads, and optical switches. Silicon-based piezoresistive pressure sensors for manifold absolute pressure sensing for engines were launched in 1991 by NovaSensor, and their annual sales were about 25 million units in 2002. Annual sales of inkjet printer heads with microscale functional components were about 400 million units in 2002. Capacitive pressure sensors for tire pressure measurements were launched by Motorola. Other applications of MEMS devices include chemical sensors; gas sensors; infrared detectors and focal plane arrays for earth observations; space science and missile defense applications; pico-satellites for space applications; and many hydraulic, pneumatic, and other consumer products. MEMS devices are also being pursued in magnetic storage systems [1.17], where they are being developed for super-compact and ultrahigh recording-density magnetic disk drives. Several integrated head/suspension microdevices have been fabricated for contact recording applications [1.18, 19]. High-bandwidth, servo-controlled microactuators have been fabricated for ultrahigh track-density applications, which serve as the fine-position control element of a two-stage, coarse/fine servo system, coupled with a conventional actuator [1.20–23]. Millimeter-sized wobble motors and actuators for tip-based recording schemes have also been fabricated [1.24].

BIOMEMS are increasingly used in commercial and defense applications (e.g., [1.4,25–28]). Applications of BIOMEMS include biofluidic chips (otherwise known as microfluidic chips, bioflips, or simply biochips) for chemical and biochemical analyses (biosensors) in medical diagnostics (e.g., DNA, RNA, proteins, cells, blood pressure and assays, and toxin identification) and implantable pharmaceutical drug delivery. The biosensors, also referred to as lab-on-a-chip, integrate sample handling, separation, detection, and data analysis onto one platform. Biosensors are designed to either detect a single or class of (bio)chemicals or system-level analytical capabilities for a broad range of (bio)chemical species known as micro total analysis systems (μTAS). The chips rely on microfluidics and involve the manipulation of tiny amounts of fluids in microchannels using microvalves for various analyses. The test fluid is pumped into the chip generally using an external pump for analyses. Some chips have been designed with an integrated electrostatically actuated diaphragm-type micropump. Silicon-based, disposable blood-pressure sensor chips were introduced in the early 1990s by NovaSensor for blood pressure monitoring (about 20 million units in 2002). A variety of biosensors are manufactured by various companies, including ACLARA, Agilent Technologies, Calipertech, and I-STAT.

After the tragedy of Sept. 11, 2001, concern over biological and chemical warfare has led to the development of handheld units with bio- and chemical sensors for the detection of biological germs, chemical or nerve agents, mustard agents, and chemical precursors to protect subways, airports, the water supply, and the population [1.29].

Other BIOMEMS applications include minimal invasive surgery, such as endoscopic surgery, laser angioplasty, and microscopic surgery. Implantable artificial organs can also be produced.

Micro-instruments and micro-manipulators are used to move, position, probe, pattern, and characterize nanoscale objects and nanoscale features. Miniaturized analytical equipment includes gas chromatography and mass spectrometry. Other instruments include micro-STM, where STM stands for scanning tunneling microscope.

Examples of NEMS include nanocomponents, nanodevices, nanosystems, and nanomaterials, such as microcantilever with integrated sharp nanotips for STM and atomic force microscopy (AFM), AFM array (millipede) for data storage, AFM tips for nanolithography, dip-pen nanolithography for printing molecules, biological (DNA) motors, molecular gears, molecularly thick films (e.g., in giant magneto-resistive or GMR heads and magnetic media), nanoparticles, (e.g., nanomagnetic particles in magnetic media), nanowires, carbon nanotubes, quantum wires (QWRs), quantum boxes (QBs), and quantum transistors [1.30–34]. BIONEMS include nanobiosensors – a microarray of silicon nanowires, roughly a few nm in size, to selectively bind and detect even a single biological molecule, such as DNA or protein, by using nanoelectronics to detect the slight electrical charge caused by such binding, or a microarray of carbon nanotubes to electrically detect glucose, implantable drug-delivery devices – e.g., micro/nanoparticles with drug molecules encapsulated in functionized shells for a site-specific targeting application, and a silicon capsule with a nanoporous membrane filled with drugs for long term delivery, nanodevices for sequencing single molecules of DNA in the Human Genome Project, cellular growth using carbon nanotubes for spinal cord repair, nanotubes for nanostructured materials for various applications, such as spinal fusion devices, organ growth, and growth of artificial tissues using nanofibers.

Nanoelectronics can be used to build computer memory, using individual molecules or nanotubes to store bits of information, as well as molecular switches, molecular or nanotube transistors, nanotube flat-panel displays, nanotube integrated circuits, fast logic gates, switches, nanoscopic lasers, and nanotubes as electrodes in fuel cells.

1.5 Reliability Issues of MEMS/NEMS

There is an increasing need for a multidisciplinary, system-oriented approach to manufacturing micro/nanodevices that function reliably. This can only be achieved through the cross-fertilization of ideas from different disciplines and the systematic flow of information and people among research groups. Common potential failure mechanisms for MEMS/NEMS that need to be addressed in order to increase reliability are: adhesion, friction, wear, fracture, fatigue, and contamination. Surface micro/nanomachined structures often include smooth and chemically active surfaces. Due to the large surface area to volume ratio in MEMS/NEMS, they are particularly prone to stiction (high static friction) as part of normal operation. Fracture occurs when the load on a microdevice is greater than the strength of the material. Fracture is a serious reliability concern, particularly for the brittle materials used in the construction of these components, since it can immediately, or eventually, lead to catastrophic failures. Additionally, debris can be formed from the fracturing of microstructures, leading to other failure processes. For less brittle materials, repeated loading over a long period causes fatigue that would also lead to the breaking and fracturing of the device. In principle, this failure mode is relatively easy to observe and simple to predict. However, the materials properties of thin films are often not known, making fatigue predictions prone to error.

Many MEMS/NEMS devices operate near their thermal dissipation limit. They may encounter hot spots that can cause failures, particularly in weak structures such as diaphragms or cantilevers. Thermal stressing and relaxation caused by thermal variations can create material delamination and fatigue in cantilevers. In large temperature changes, as experienced in the space environment, bimetallic beams will also experience warping due to mismatched coefficients of thermal expansion. Packaging has been a big problem. The contamination, which probably happens in packaging and during storage, can also strongly influence the reliability of MEMS/NEMS. For example, a particulate dust landed on one of the electrodes of a comb drive can cause catastrophic failure. There are no MEMS/NEMS fabrication standards, which makes it difficult to transfer fabrication steps in MEMS/NEMS between foundaries.

Obviously, studies of determination and suppression of active failure mechanisms affecting this new and promising technology are critical to the high reliability of MEMS/NEMS and are determining factors in successful practical application.

Mechanical properties are known to exhibit a dependence on specimen size. Mechanical property evaluation of nanometer-scaled structures is carried out to help design reliable systems, since good mechanical properties are of critical importance in such applications. Some of the properties of interest are: Young's modulus of elasticity, hardness, bending strength, fracture toughness, and fatigue life. Finite element modeling is carried out to study the effects of surface roughness and scratches on stresses in nanostructures. When nanostructures are smaller than a fundamental physical length scale, conventional theory may no longer apply, and new phenomena may emerge. Molecular mechanics is used to simulate the behavior of a nano-object.

1.6 Organization of the Handbook

The handbook integrates knowledge from the fabrication, mechanics, materials science, and reliability points of view. Organization of the book is straightforward. The handbook is divided into six parts. This first part introduces the nanotechnology field, including an introduction to nanostructures, micro/nanofabrication and, micro/nanodevices. The second part introduces scanning probe microscopy. The third part provides an overview of nanotribology and nanomechanics, which will prepare the reader to understand the tribology and mechanics of industrial applications. The fourth part provides an overview of molecularly thick films for lubrication. The fifth part focuses on industrial applications and microdevice reliability. And the last part focuses on the social and ethical implications of nanotechnology.

References

1.1 R. P. Feynmann: There's plenty of room at the bottom, Eng. Sci. **23** (1960) 22–36, and www.zyvex.com/nanotech/feynman.html (1959)

1.2 I. Amato: Nanotechnology, www.ostp.gov/nstc/html/iwgn/iwgn.public.brochure/welcome.htm or www.nsf.gov/home/crssprgm/nano/nsfnnireports.htm (2000)

1.3 Anonymous: National nanotechnology initiative, www.ostp.gov/nstc/html/iwgn.fy01budsuppl/nni.pdf or www.nsf.gov/home/crssprgm/nano/nsfnnireports.htm (2000)

1.4 I. Fujimasa: *Micromachines: A New Era in Mechanical Engineering* (Oxford Univ. Press, Oxford 1996)

1.5 C. J. Jones, S. Aizawa: The bacterial flagellum and flagellar motor: Structure, assembly, and functions, Adv. Microb. Physiol. **32** (1991) 109–172

1.6 V. Bergeron, D. Quere: Water droplets make an impact, Phys. World **14** (May 2001) 27–31

1.7 M. Scherge, S. Gorb: *Biological Micro- and Nanotribology* (Springer, Berlin, Heidelberg 2000)

1.8 B. Bhushan: *Tribology Issues and Opportunities in MEMS* (Kluwer, Dordrecht 1998)

1.9 G. T. A. Kovacs: *Micromachined Transducers Sourcebook* (WCB McGraw-Hill, Boston 1998)

1.10 S. D. Senturia: *Microsystem Design* (Kluwer, Boston 2001)

1.11 T. R. Hsu: *MEMS and Microsystems* (McGraw-Hill, Boston 2002)

1.12 M. Madou: *Fundamentals of Microfabrication: The Science of Miniaturization*, 2nd edn. (CRC, Boca Raton 2002)

1.13 T. A. Core, W. K. Tsang, S. J. Sherman: Fabrication technology for an integrated surface-micromachined sensor, Solid State Technol. **36** (October 1993) 39–47

1.14 J. Bryzek, K. Peterson, W. McCulley: Micromachines on the march, IEEE Spectrum (May 1994) 20–31

1.15 L. J. Hornbeck, W. E. Nelson: Bistable deformable mirror device, OSA Technical Digest **8** (1988) 107–110

1.16 L. J. Hornbeck: A digital light processing(tm) update – Status and future applications (invited), Proc. Soc. Photo-Opt. Eng. **3634** (1999) 158–170

1.17 B. Bhushan: *Tribology and Mechanics of Magnetic Storage Devices*, 2nd edn. (Springer, New York 1996)

1.18 H. Hamilton: Contact recording on perpendicular rigid media, J. Mag. Soc. Jpn. **15** (Suppl. S2) (1991) 481–483

1.19 T. Ohwe, Y. Mizoshita, S. Yonoeka: Development of integrated suspension system for a nanoslider with an MR head transducer, IEEE Trans. Magn. **29** (1993) 3924–3926

1.20 D. K. Miu, Y. C. Tai: Silicon micromachined scaled technology, IEEE Trans. Industr. Electron. **42** (1995) 234–239

1.21 L. S. Fan, H. H. Ottesen, T. C. Reiley, R. W. Wood: Magnetic recording head positioning at very high track densities using a microactuator-based, two-stage servo system, IEEE Trans. Ind. Electron. **42** (1995) 222–233

1.22 D. A. Horsley, M. B. Cohn, A. Singh, R. Horowitz, A. P. Pisano: Design and fabrication of an angular microactuator for magnetic disk drives, J. Microelectromech. Syst. **7** (1998) 141–148

1.23 T. Hirano, L.S. Fan, D. Kercher, S. Pattanaik, T.S. Pan: HDD tracking microactuator and its integration issues, Proc. ASME Int. Mech. Eng. Congress, MEMS, New York 2000, ed. by A.P. Lee, J. Simon, F.K. Foster, R.S. Keynton (ASME, New York 2000) 449–452

1.24 L.S. Fan, S. Woodman: Batch fabrication of mechanical platforms for high-density data storage, 8th Int. Conf. Solid State Sensors and Actuators (Transducers '95)/Eurosensors IX, Stockholm (June, 1995) 434–437

1.25 P. Gravesen, J. Branebjerg, O.S. Jensen: Microfluidics – A review, J. Micromech. Microeng. **3** (1993) 168–182

1.26 C. Lai Poh San, E.P.H. Yap (Eds.): *Frontiers in Human Genetics* (World Scientific, Singapore 2001)

1.27 C.H. Mastrangelo, H. Becker (Eds.): *Microfluidics and BioMEMS*, Proc. SPIE **4560** (SPIE, Bellingham 2001)

1.28 H. Becker, L.E. Locascio: Polymer microfluidic devices, Talanta **56** (2002) 267–287

1.29 M. Scott: MEMS and MOEMS for national security applications, , Reliability, Testing, and Characterization of MEMS/MOEMS II, Proc. SPIE **4980** (SPIE, Bellingham 2003)

1.30 K.E. Drexler: *Nanosystems: Molecular Machinery, Manufacturing and Computation* (Wiley, New York 1992)

1.31 G. Timp (Ed.): *Nanotechnology* (Springer, Berlin, Heidelberg 1999)

1.32 E.A. Rietman: *Molecular Engineering of Nanosystems* (Springer, Berlin, Heidelberg 2001)

1.33 H.S. Nalwa (Ed.): *Nanostructured Materials and Nanotechnology* (Academic, San Diego 2002)

1.34 W.A. Goddard, D.W. Brenner, S.E. Lyshevski, G.J. Iafrate: *Handbook of Nanoscience, Engineering, and Technology* (CRC, Boca Raton 2003)

Part A

Nanostruc

Part A Nanostructures, Micro/Nanofabrication, and Micro/Nanodevices

2 Nanomaterials Synthesis and Applications: Molecule-Based Devices
Françisco M. Raymo, Coral Gables, USA

3 Introduction to Carbon Nanotubes
Marc Monthioux, Toulouse, France
Philippe Serp, Toulouse, France
Emmanuel Flahaut, Toulouse, France
Manitra Razafinimanana, Toulouse, France
Christophe Laurent, Toulouse, France
Alain Peigney, Toulouse, France
Wolfgang Bacsa, Toulouse, France
Jean-Marc Broto, Toulouse, France

4 Nanowires
Mildred S. Dresselhaus, Cambridge, USA
Yu-Ming Lin, Cambridge, USA
Oded Rabin, Cambridge, USA
Marcie R. Black, Cambridge, USA
Gene Dresselhaus, Cambridge, USA

5 Introduction to Micro/Nanofabrication
Babak Ziaie, Minneapolis, USA
Antonio Baldi, Barcelona, Spain
Massood Z. Atashbar, Kalamazoo, USA

6 Stamping Techniques for Micro and Nanofabrication: Methods and Applications
John A. Rogers, Urbana, USA

7 Materials Aspects of Micro- and Nanoelectromechanical Systems
Christian A. Zorman, Cleveland, USA
Mehran Mehregany, Cleveland, USA

8 MEMS/NEMS Devices and Applications
Darrin J. Young, Cleveland, USA
Christian A. Zorman, Cleveland, USA
Mehran Mehregany, Cleveland, USA

9 Microfluidics and Their Applications to Lab-on-a-Chip
Chong H. Ahn, Cincinnati, USA
Jin-Woo Choi, Baton Rouge, USA

10 Therapeutic Nanodevices
Stephen C. Lee, Columbus, USA
Mark Ruegsegger, Columbus, USA
Philip D. Barnes, Columbus, USA
Bryan R. Smith, Columbus, USA
Mauro Ferrari, Columbus, USA

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

2. Nanomaterials Synthesis and Applications: Molecule-Based Devices

The constituent components of conventional devices are carved out of larger materials relying on physical methods. This top-down approach to engineered building blocks becomes increasingly challenging as the dimensions of the target structures approach the nanoscale. Nature, on the other hand, relies on chemical strategies to assemble nanoscaled biomolecules. Small molecular building blocks are joined to produce nanostructures with defined geometries and specific functions. It is becoming apparent that nature's bottom-up approach to functional nanostructures can be mimicked to produce artificial molecules with nanoscaled dimensions and engineered properties. Indeed, examples of artificial nanohelices, nanotubes, and molecular motors are starting to be developed. Some of these fascinating chemical systems have intriguing electrochemical and photochemical properties that can be exploited to manipulate chemical, electrical, and optical signals at the molecular level. This tremendous opportunity has lead to the development of the molecular equivalent of conventional logic gates. Simple logic operations, for example, can be reproduced with collections of molecules operating in solution. Most of these chemical systems, however, rely on bulk addressing to execute combinational and sequential logic operations. It is essential to devise methods to reproduce these useful functions in solid-state configurations and, eventually, with single molecules. These challenging objectives are stimulating the design of clever devices that interface small assemblies of organic molecules with macroscaled and nanoscaled electrodes. These strategies have already produced rudimentary examples of diodes, switches, and transistors based on functional molecular components. The rapid and continuous progress of this exploratory research will, we hope, lead to an entire generation of molecule-based devices that might ultimately find useful applications in a variety of fields, ranging from biomedical research to information technology.

2.1 Chemical Approaches to Nanostructured Materials 10
- 2.1.1 From Molecular Building Blocks to Nanostructures 10
- 2.1.2 Nanoscaled Biomolecules: Nucleic Acids and Proteins 10
- 2.1.3 Chemical Synthesis of Artificial Nanostructures 12
- 2.1.4 From Structural Control to Designed Properties and Functions 12

2.2 Molecular Switches and Logic Gates 14
- 2.2.1 From Macroscopic to Molecular Switches 15
- 2.2.2 Digital Processing and Molecular Logic Gates 15
- 2.2.3 Molecular AND, NOT, and OR Gates 16
- 2.2.4 Combinational Logic at the Molecular Level 17
- 2.2.5 Intermolecular Communication 18

2.3 Solid State Devices 22
- 2.3.1 From Functional Solutions to Electroactive and Photoactive Solids 22
- 2.3.2 Langmuir–Blodgett Films 23
- 2.3.3 Self-Assembled Monolayers 27
- 2.3.4 Nanogaps and Nanowires 31

2.4 Conclusions and Outlook 35

References 36

2.1 Chemical Approaches to Nanostructured Materials

The fabrication of conventional devices relies on the assembly of macroscopic building blocks with specific configurations. The shapes of these components are carved out of larger materials by exploiting physical methods. This top-down approach to engineered building blocks is extremely powerful and can deliver effectively and reproducibly microscaled objects. This strategy becomes increasingly challenging, however, as the dimensions of the target structures approach the nanoscale. Indeed, the physical fabrication of nanosized features with subnanometer precision is a formidable technological challenge.

2.1.1 From Molecular Building Blocks to Nanostructures

Nature efficiently builds nanostructures by relying on chemical approaches. Tiny molecular building blocks are assembled with a remarkable degree of structural control in a variety of nanoscaled materials with defined shapes, properties, and functions. In contrast to the top-down physical methods, small components are connected to produce larger objects in these bottom-up chemical strategies. It is becoming apparent that the limitations of the top-down approach to artificial nanostructures can be overcome by mimicking nature's bottom-up processes. Indeed, we are starting to see emerge beautiful and ingenious examples of molecule-based strategies to fabricate chemically nanoscaled building blocks for functional materials and innovative devices.

2.1.2 Nanoscaled Biomolecules: Nucleic Acids and Proteins

Nanoscaled macromolecules play a fundamental role in biological processes [2.1]. Nucleic acids, for example, ensure the transmission and expression of genetic information. These particular biomolecules are linear polymers incorporating nucleotide repeating units (Fig. 2.1a). Each nucleotide has a phosphate bridge and a sugar residue. Chemical bonds between the phosphate of one nucleotide and the sugar of the next ensures the propagation of a polynucleotide strand from the $5'$ to the $3'$ end. Along the sequence of alternating sugar and phosphate fragments, an extended chain of robust covalent bonds involving carbon, oxygen, and phosphorous atoms forms the main backbone of the polymeric strand.

Every single nucleotide of a polynucleotide strand carries one of the four heterocyclic bases shown in Fig. 2.1b. For a strand incorporating 100 nucleotide repeating units, a total of 4^{100} unique polynucleotide sequences are possible. It follows that nature can fabricate a huge number of closely related nanostructures relying only on four building blocks. The heterocyclic bases appended to the main backbone of alternating phosphate and sugar units can sustain hydrogen bonding and $[\pi \cdots \pi]$ stacking interactions. Hydrogen bonds, formed between [N−H] donors and either N or O acceptors, encourage the pairing of adenine (A) with thymine (T) and of guanine (G) with cytosine (C). The stacking interactions involve attractive contacts between the extended π-surfaces of heterocyclic bases.

In the *B* conformation of deoxyribonucleic acid (DNA), the synergism of hydrogen bonds and $[\pi \cdots \pi]$ stacking glues pairs of complementary polynucleotide strands in fascinating double helical supermolecules (Fig. 2.1c) with precise structural control at the subnanometer level. The two polynucleotide strands wrap around a common axis to form a right-handed double helix with a diameter of ca. 2 nm. The hydrogen bonded and $[\pi \cdots \pi]$ stacked base pairs lie at the core of the helix with their π-planes perpendicular to the main axis of the helix. The alternating phosphate and sugar units define the outer surface of the double helix. In *B*-DNA, approximately ten base pairs define each helical turn corresponding to a rise per turn or helical pitch of ca. 3 nm. Considering that these molecules can incorporate up to approximately 10^{11} base pairs, extended end-to-end lengths spanning from only few nanometers to hundreds of meters are possible.

Nature's operating principles to fabricate nanostructures are not limited to nucleic acids. Proteins are also built joining simple molecular building blocks, the amino acids, by strong covalent bonds [2.1]. More precisely, nature relies on 20 amino acids differing in their side chains to assemble linear polymers, called polypeptides, incorporating an extended backbone of robust [C−N] and [C−C] bonds (Fig. 2.2a). For a single polymer strand of 100 repeating amino acid units, a total of 20^{100} unique combinations of polypeptide sequences are possible. Considering that proteins can incorporate more than one polypetide chain with over 4,000 amino acid residues each, it is obvious that nature can assemble an enormous number of different biomolecules relying on the same fabrication strategy and a relatively small pool of building blocks.


c)
Sugar residue
Heterocyclic base
5' end → HO
O
Phosphate bridge → O=P–O
O⁻
Nucleotide repeating unit
n
a)
Polynucleotide strand
O=P–O ← 3' end
3 nm
2 nm
B-DNA double helix
b)
≡
NH₂
N
A
O
NH
NH₂
G
C
Me
T

Fig. 2.1a–c A polynucleotide strand **(a)** incorporates alternating phosphate and sugar residues joined by covalent bonds. Each sugar carries one of four heterocyclic bases **(b)**. Noncovalent interactions between complementary bases in two independent polynucleotide strands encourage the formation of nanoscaled double helixes **(c)**


a)
Amino acid repeating unit
Ammonium end → H₃N⁺
O
R
N
H
n
O⁻ ← Carboxylate end
b)
2 nm
c)
Polypeptide strand
2 nm
3 nm
Polypeptide sheet
0.5 nm
Polypeptide helix

Fig. 2.2a–c A polypeptide strand **(a)** incorporates amino acid residues differing in their side chains and joined by covalent bonds. Hydrogen bonding interactions curl a single polypeptide strand into a helical arrangement **(b)** or lock pairs of strands into nanoscaled sheets **(c)**

The covalent backbones of the polypeptide strands form the main skeleton of a protein molecule. In addition, myriad secondary interactions, involving noncovalent contacts between portions of the amino acid residues, control the arrangement of the individual polypeptide chains. Intrastrand hydrogen bonds curl single polypeptide chains around a longitudinal axis in a helical fashion to form tubular nanostructures ca. 0.5 nm wide and ca. 2 nm long (Fig. 2.2b). Similarly, interstrand hydrogen bonds can align from 2 up to 15 parallel or antiparallel polypeptide chains to form nanoscaled sheets with average dimensions of 2 × 3 nm (Fig. 2.2c). Multiple nanohelices and/or nanosheets combine into a unique three-dimensional arrangement dictating the overall shape and dimensions of a protein.

2.1.3 Chemical Synthesis of Artificial Nanostructures

Nature fabricates complex nanostructures relying on simple criteria and a relatively small pool of molecular building blocks. Robust chemical bonds join the basic components into covalent scaffolds. Noncovalent interactions determine the three-dimensional arrangement and overall shape of the resulting assemblies. The multitude of unique combinations possible for long sequences of chemically connected building blocks provides access to huge libraries of nanoscaled biomolecules.

Modern chemical synthesis has evolved considerably over the past few decades [2.2]. Experimental procedures to join molecular components with structural control at the picometer level are available. A multitude of synthetic schemes to encourage the formation of chemical bonds between selected atoms in reacting molecules have been developed. Furthermore, the tremendous progress of crystallographic and spectroscopic techniques has provided efficient and reliable tools to probe directly the structural features of artificial inorganic and organic compounds. It follows that designed molecules with engineered shapes and dimensions can be now prepared in a laboratory relying on the many tricks of chemical synthesis and the power of crystallographic and spectroscopic analyses.

The high degree of sophistication reached in this research area translates into the possibility of mimicking the strategies successfully employed by nature to fabricate chemically nanostructures [2.3]. Small molecular building blocks can be synthesized and joined covalently following routine laboratory procedures. It is even possible to design the stereoelectronic properties of the assembling components in order to shape the geometry of the final product with the assistance of noncovalent interactions. For example, five bipyridine building blocks (Fig. 2.3) can be connected in five synthetic steps to produce an oligobipyridine strand [2.4]. The five repeating units are bridged by [C−O] bonds and can chelate metal cations in the bay regions defined by their two nitrogen atoms. The spontaneous assembly of two organic strands in a double helical arrangement occurs in the presence of inorganic cations. In the resulting helicate, the two oligobipyridine strands wrap around an axis defined by five Cu(I) centers. Each inorganic cation coordinates two bipyridine units with a tetrahedral geometry imposing a diameter of ca. 0.6 nm on the nanoscaled helicate [2.5]. The overall length from one end of the helicate to the other is ca. 3 nm [2.6]. The analogy between this artificial double helix and the *B*-DNA double helix shown in Fig. 2.1c is obvious. In both instances, a supramolecular glue combines two independent molecular strands into nanostructures with defined shapes and dimensions.

The chemical synthesis of nanostructures can borrow nature's design criteria as well as its molecular building blocks. Amino acids, the basic components of proteins, can be assembled into artificial macrocycles. In the example of Fig. 2.4, eight amino acid residues are joined through the formation of [C−N] bonds in multiple synthetic steps [2.7]. The resulting covalent backbone defines a circular cavity with a diameter of ca. 0.8 nm [2.8]. In analogy to the polypeptide chains of proteins, the amino acid residues of this artificial oligopeptide can sustain hydrogen bonding interactions. It follows that multiple macrocycles can pile on top of each other to form tubular nanostructures. The walls of the resulting nanotubes are maintained in position by the cooperative action of at least eight primary hydrogen bonding contacts per macrocycle. These noncovalent interactions maintain the mean planes of independent macrocycles in an approximately parallel arrangement with a plane-to-plane separation of ca. 0.5 nm.

2.1.4 From Structural Control to Designed Properties and Functions

The examples in Figs. 2.3 and 2.4 demonstrate that modular building blocks can be assembled into target compounds with precise structural control at the picometer level through programmed sequences of synthetic steps. Indeed, modern chemical synthesis offers access to complex molecules with nanoscaled dimensions and, thus, provides cost-effective strategies for the production and characterization of billions of engineered nanostructures in parallel. Furthermore, the high degree of structural control is accompanied by the possibility of designing specific properties into the target nanostructures. Electroactive and photoactive components can be integrated chemically into functional molecular machines [2.9]. Extensive electrochemical investigations have demonstrated that inorganic and organic compounds can exchange electrons with macroscopic electrodes [2.10]. These studies have unraveled the processes responsible for the oxidation and reduction of numerous functional groups and indicated viable design criteria to adjust the ability of molecules to accept or donate electrons [2.11]. Similarly, detailed photochemical and photophysical investigations have elucidated the mechanisms responsible for the absorption and emission of photons at the molecular level [2.12]. The vast knowledge established on the interactions between light and molecules offers the opportunity to engineer chromophoric and fluorophoric functional groups with defined absorption and emission properties [2.11, 13].

The power of chemical synthesis to deliver functional molecules is, perhaps, better illustrated by the molecular motor shown in Fig. 2.5. The preparation of this [2]rotaxane requires 12 synthetic steps starting from known precursors [2.14]. This complex molecule incorporates a Ru(II)-trisbipyridine stopper bridged to a linear tetracationic fragment by a rigid triaryl spacer. The other end of the tetracationic portion is terminated by a bulky tetraarylmethane stopper. The bipyridinium unit of this dumbbell-shaped compound is encircled by a macrocyclic polyether. No covalent bonds join the macrocyclic and linear components.


Me
N
×2
N
OH + Br
3 ×
N
N
Br
Me
N
Bipyridine ligand
N
O
Synthesis
N
N
O
N
N
O
N
N
O
N
N
Me
Cu(I)
≡
3 nm
0.6 nm
Synthetic double helix
Oligobipyridine strand
≡

Fig. 2.3 An oligobipyridine strand can be synthesized joining five bipyridine subunits by covalent bonds. The tetrahedral coordination of pairs of bipyridine ligands by Cu(I) ions encourages the assembly two oligobipyridine strands into a double helical arrangement


4 × Me
CO₂H
D
NH₂
+
4 × HO₂C
CO₂H
L
NH₂
Synthesis
H₂NOC
O
H
N
Me O
NH
CO₂H
O
HN
O
NH
Me
Me
HN
0.8 nm
NH
O
HO₂C
N
H
N
H
O
O
Me
CONH₂
≡
Oligopeptide macrocycle
Synthetic nanotube
Self-assembly
0.8 nm
0.5 nm

Fig. 2.4 Cyclic oligopeptides can be synthesized joining eight amino acid residues by covalent bonds. The resulting macrocycles self-assemble into nanoscaled tube-like arrays


Electroactive dimethyl bipyridinium
Electroactive bipyridinium
Photoactive Ru(II)-trisbipyridine stopper
Macrocyclic polyether
Ru2+
Me
N
O
t-Bu
Et
5 nm

Fig. 2.5 This nanoscaled [2]rotaxane incorporates a photoactive Ru(II)-trisbipyridine stopper and two electroactive bipyridinium units. Photoinduced electron transfer from the photoactive stopper to the encircled electroactive unit forces the macrocyclic polyether to shuttle to the adjacent bipyridinium dication

Rather, hydrogen bonding and $[\pi \cdots \pi]$ stacking interactions maintain the macrocyclic polyether around the bipyridinium unit. In addition, mechanical constrains associated with the bulk of the two terminal stoppers prevent the macrocycle to slip off the thread. The approximate end-to-end distance for this [2]rotaxane is ca. 5 nm.

The bipyridinium and the 3,3′-dimethyl bipyridinium units within the dumbbell-shaped component undergo two consecutive and reversible monoelectronic reductions [2.14]. The two methyl substituents on the 3,3′-dimethyl bipyridinium dication make this electroactive unit more difficult to reduce. In acetonitrile, its redox potential is ca. 0.29 V more negative than that of the unsubstituted bipyridinium dication. Under irradiation at 436 nm in degassed acetonitrile, the excitation of the Ru(II)-trisbipyridine stopper is followed by electron transfer to the unsubstituted bipyridinium unit. In the presence of a sacrificial electron donor (triethanolamine) in solution, the photogenerated hole in the photoactive stopper is filled, and undesired back electron transfer is suppressed. The permanent and light-induced reduction of the dicationic bipyridinium unit to a radical cation depresses significantly the magnitude of the noncovalent interactions holding the macrocyclic polyether in position. As a result, the macrocycle shuttles from the reduced unit to the adjacent dicationic 3,3′-dimethyl bipyridinum. After the diffusion of molecular oxygen into the acetonitrile solution, oxidation occurs restoring the dicationic form of the bipyridinium unit and its ability to sustain strong noncovalent bonds. As a result, the macrocyclic polyether shuttles back to its original position. This amazing example of a molecular shuttle reveals that dynamic processes can be controlled reversibly at the molecular level relying on the clever integration of electroactive and photoactive fragments into functional and nanoscaled molecules.

2.2 Molecular Switches and Logic Gates

Everyday, we routinely perform dozens of switching operations. We turn on and off our personal computers, cellular phones, CD players, radios, or simple light bulbs at a click of a button. Every single time, our finger exerts a mechanical stimulation on a control device, namely a switch. The external stimulus changes the physical state of the switch closing or opening an electric circuit and enabling or preventing the passage of electrons.

Overall, the switch transduces a mechanical input into an electrical output.

2.2.1 From Macroscopic to Molecular Switches

The use of switching devices is certainly not limited to electric circuits. For example, a switch at the junction of a railroad can divert trains from one track to another. Similarly, a faucet in a lavatory pipe can block or release the flow of water. Of course, the nature of the control stimulations and the character of the final outcome vary significantly from case to case, but the operating principle behind each switching device is the same. In all cases, input stimulations reach the switch changing its physical state and producing a specific output.

The development of nanoscaled counterparts to conventional switches is expected to have fundamental scientific and technological implications. For instance, one can envisage practical applications for ultraminiaturized switches in areas ranging from biomedical research to information technology. The major challenge in the quest for nanoswitches, however, is the identification of reliable design criteria and operating principles for these innovative and fascinating devices. Chemical approaches to implement molecule-sized switches appear to be extremely promising. The intrinsically small dimensions of organic molecules coupled with the power of chemical synthesis are the main driving forces behind these exploratory investigations.

Certain organic molecules adjust their structural and electronic properties when stimulated with chemical, electrical, or optical inputs. Generally, the change is accompanied by an electrochemical or spectroscopic response. Overall, these nanostructures transduce input stimulations into detectable outputs and, appropriately, are called molecular switches [2.15, 16]. The chemical transformations associated with these switching processes are often reversible. The chemical system returns to the original state when the input signal is turned off. The interconverting states of a molecular switch can be isomers, an acid and its conjugated base, the oxidized and reduced forms of a redox active molecule, or even the complexed and uncomplexed forms of a receptor [2.9, 15, 16]. The output of a molecular switch can be a chemical, electrical, and/or optical signal that varies in intensity with the interconversion process. For example, changes in absorbance, fluorescence, pH, or redox potential can accompany the reversible transformation of a molecular switch.

2.2.2 Digital Processing and Molecular Logic Gates

In present computer networks, data are elaborated electronically by microprocessor systems [2.17] and are exchanged optically between remote locations [2.18]. Data processing and communication require the encoding of information in electrical and optical signals in the form of binary digits. Using arbitrary assumptions, logic thresholds can be established for each signal and, then, 0 and 1 digits can be encoded following simple conventions. Sequences of electronic devices manipulate the encoded bits executing logic functions as a result of basic switching operations.

The three basic AND, NOT, and OR operators combine binary inputs into binary outputs following precise logic protocols [2.17]. The NOT operator converts an input signal into an output signal. When the input is 0, the output is 1. When the input is 1, the output is 0. Because of the inverse relationship between the input and output values, the NOT gate is often called "inverter" [2.19]. The OR operator combines two input signals into a single output signal. When one or both inputs are 1, the output is 1. When both inputs are 0, the output is 0. The AND gate also combines two input signals into one output signal. In this instance, however, the output is 1 only when both inputs are 1. When at least one input is 0, the output is 0.

The output of one gate can be connected to one of the inputs of another operator. A NAND gate, for example, is assembled connecting the output of an AND operator to the input of a NOT gate. Now the two input signals are converted into the final output after two consecutive logic operations. In a similar fashion, a NOR gate can be assembled connecting the output of an OR operator to the input of a NOT gate. Once again, two consecutive logic operations determine the relation between two input signals and a single output. The NAND and NOR operations are termed universal functions because any conceivable logic operation can be implemented relying only on one of these two gates [2.17]. In fact, digital circuits are fabricated routinely interconnecting exclusively NAND or exclusively NOR operators [2.19].

The logic gates of conventional microprocessors are assembled interconnecting transistors, and their input and output signals are electrical [2.19]. But the concepts of binary logic can be extended to chemical, mechanical, optical, pneumatic, or any other type of signal. First it is necessary to design devices that can respond to these stimulations in the same way transistors respond to electrical signals. Molecular switches respond to a variety of input stimulations producing specific outputs and can, therefore, be exploited to implement logic functions [2.20, 21].

2.2.3 Molecular AND, NOT, and OR Gates

More than a decade ago, researchers proposed a potential strategy to execute logic operations at the molecular level [2.22]. Later, the analogy between molecular switches and logic gates was recognized in a seminal article [2.23], in which it was demonstrated that AND, NOT, and OR operations can be reproduced with fluorescent molecules. The pyrazole derivative **1** (Fig. 2.6) is a molecular NOT gate. It imposes an inverse relation between a chemical input (concentration of H^+) and an optical output (emission intensity). In a mixture of methanol and water, the fluorescence quantum yield of **1** is 0.13 in the presence of only 0.1 equivalents of H^+ [2.23]. The quantum yield drops to 0.003 when the equivalents of H^+ are 1,000. Photoinduced electron transfer from the central pyrazoline unit to the pendant benzoic acid quenches the fluorescence of the protonated form. Thus, a change in H^+ concentration (I) from a low to a high value switches the emission intensity (O) from a high to a low value. The inverse relationship between the chemical input I and the optical output O translates into the truth table of a NOT operation if a positive logic convention (low = 0, high = 1) is applied to both signals. The emission intensity is high (O = 1) when the concentration of H^+ is low (I = 0). The emission intensity is low (O = 0) when the concentration of H^+ is high (I = 1).

The anthracene derivative **2** (Fig. 2.6) is a molecular OR gate. It transduces two chemical inputs



H^+	Emission
Low	High
High	Low

I	O
0	1
1	0

Na^+	K^+	Emission
Low	Low	Low
Low	High	High
High	Low	High
High	High	High

I1	I2	O
0	0	0
0	1	1
1	0	1
1	1	1

H^+	Na^+	Emission
Low	Low	Low
Low	High	Low
High	Low	Low
High	High	High

I1	I2	O
0	0	0
0	1	0
1	0	0
1	1	1

Fig. 2.6 The fluorescence intensity of the pyrazoline derivative **1** is high when the concentration of H^+ is low, and vice versa. The fluorescence intensity of the anthracene derivative **2** is high when the concentration of Na^+ and/or K^+ is high. The emission is low when both concentrations are low. The fluorescence intensity of the anthracene **3** is high only when the concentrations of H^+ and Na^+ are high. The emission is low in the other three cases. The signal transductions of the molecular switches **1**, **2**, and **3** translate into the truth tables of NOT, OR, and AND gates, respectively, if a positive logic convention is applied to all inputs and outputs (low = 0, high = 1)

(concentrations of Na^+ and K^+) into an optical output (emission intensity). In methanol, the fluorescence quantum yield is only 0.003 in the absence of metal cations [2.23]. Photoinduced electron transfer from the nitrogen atom of the azacrown fragment to the anthracene fluorophore quenches the emission. After the addition of 1,000 equivalents of either Na^+ or K^+, the quantum yield raises to 0.053 and 0.14, respectively. Similarly, the quantum yield is 0.14 when both metal cations are present in solution. The complexation of one of the two metal cations inside the azacrown receptor depresses the efficiency of the photoinduced electron transfer enhancing the fluorescence. Thus, changes in the concentrations of Na^+ (I1) and/or K^+ (I2) from low to high values switch the emission intensity (O) from a low to a high value. The relationship between the chemical inputs I1 and I2 and the optical output O translates into the truth table of an OR operation if a positive logic convention (low = 0, high = 1) is applied to all signals. The emission intensity is low (O = 0) only when the concentration of Na^+ and K^+ are low (I1 = 0, I2 = 0). The emission intensity is high (O = 1) for the other three input combinations.

The anthracene derivative **3** (Fig. 2.6) is a molecular AND gate. It transduces two chemical inputs (concentrations of H^+ and Na^+) into an optical output (emission intensity). In a mixture of methanol and *iso*-propanol, the fluorescence quantum yield is only 0.011 in the absence of H^+ or Na^+ [2.23]. Photoinduced electron transfer from either the tertiary amino group or the catechol fragment to the anthracene fluorophore quenches the emission. After the addition of either 100 equivalents of H^+ or 1,000 equivalents of Na^+, a modest change of the quantum yield to 0.020 and 0.011, respectively, is observed. Instead, the quantum yield increases to 0.068 when both species are present in solution. The protonation of the amino group and the insertion of the metal cation in the benzocrown ether receptor depress the efficiency of the photoinduced electron transfer processes enhancing the fluorescence. Thus, changes in the concentrations of H^+ (I1) and Na^+ (I2) from low to high values switch the emission intensity (O) from a low to a high value. The relationship between the chemical inputs I1 and I2 and the optical output O translates into the truth table of an AND operation if a positive logic convention (low = 0, high = 1) is applied to all signals. The emission intensity is high (O = 1) only when the concentration of H^+ and Na^+ are high (I1 = 1, I2 = 1). The emission intensity is low (O = 0) for the other three input combinations.

2.2.4 Combinational Logic at the Molecular Level

The fascinating molecular AND, NOT, and OR gates illustrated in Fig. 2.6 have stimulated the design of related chemical systems able to execute the three basic logic operations and simple combinations of them [2.20, 21]. Most of these molecular switches convert chemical inputs into optical outputs. But the implementation of logic operations at the molecular level is not limited to the use of chemical inputs. For example, electrical signals and reversible redox processes can be exploited to modulate the output of a molecular switch [2.24]. The supramolecular assembly **4** (Fig. 2.7) executes a XNOR function relying on these operating principles. The π-electron rich tetrathiafulvalene (TTF) guest threads the cavity of a π-electron deficient bipyridinium (BIPY) host. In acetonitrile, an absorption band associated with the charge-transfer interactions between the complementary π-surfaces is observed at 830 nm. Electrical stimulations alter the redox state of either the TTF or the BIPY units encouraging the separation of the two components of the complex and the disappearance of the charge-transfer band. Electrolysis at a potential of +0.5 V oxidizes the neutral TTF unit to a monocationic state. The now cationic guest is expelled from the cavity of the tetracationic host as a result of electrostatic repulsion. Consistently, the absorption band at 830 nm disappears. The charge-transfer band, however, is restored after the exhaustive back reduction of the TTF unit at a potential of 0 V. Similar changes in the absorption properties can be induced addressing the BIPY units. Electrolysis at −0.3 V reduces the dicationic BIPY units to their monocationic forms encouraging the separation of the two components of the complex and the disappearance of the absorption band. The original absorption spectrum is restored after the exhaustive back oxidation of the BIPY units at a potential of 0 V. Thus, this supramolecular system responds to electrical stimulations producing an optical output. One of the electrical inputs (I1) controls the redox state of the TTF unit switching between 0 and +0.5 V. The other (I2) determines the redox state of the bipyridinium units switching between −0.3 and 0 V. The optical output (O) is the absorbance of the charge-transfer band. A positive logic convention (low = 0, high = 1) can be applied to the input I1 and output O. A negative logic convention (low = 1, high = 0) can be applied to the input I2. The resulting truth table corresponds to that of a XNOR circuit (Fig. 2.7). The charge-transfer absorbance is high (O = 1) only when one voltage input is low and the other

4



TTF	BIPY	Absorbance
Low	Low	High
Low	High	Low
High	Low	Low
High	High	High

XNOR

I1	I2	O
0	0	1
0	1	0
1	0	0
1	1	1

Fig. 2.7 The charge-transfer absorbance of the complex **4** is high when the voltage input addressing the tetrathiafulvalene (TTF) unit is low and that stimulating the bipyridinium (BIPY) units is high and vice versa. If a positive logic convention is applied to the TTF input and to the absorbance output (low = 0, high = 1) while a negative logic convention is applied to the BIPY input (low = 0, high = 1), the signal transduction of **4** translates into the truth table of a XNOR circuit

is high (I1 = 0, I2 = 0) or vice versa (I1 = 1, I2 = 1). It is important to note that the input string with both I1 and I2 equal to 1 implies that input potentials of $+0.5$ and -0.3 V are applied simultaneously to a solution containing the supramolecular assembly **4** and not to an individual complex. Of course, the concomitant oxidation of the TTF guest and reduction of the BIPY units in the very same complex would be unrealistic. In bulk solution, instead, some complexes are oxidized while others are reduced, leaving the average solution composition unaffected. Thus, the XNOR operation executed by this supramolecular system is a consequence of bulk properties and not a result of unimolecular signal transduction.

Optical inputs can be employed to operate the three-state molecular switch of Fig. 2.8 in acetonitrile solution [2.25]. This chemical system responds to three inputs producing two outputs. The three input stimulations are ultraviolet light (I1), visible light (I2), and the concentration of H$^+$ (I3). One of the two optical outputs is the absorbance at 401 nm (O1), which is high when the molecular switch is in the yellow-green state **6** and low in the other two cases. The other optical output is the absorbance at 563 nm (O2), which is high when the molecular switch is in the purple state **7** and low in the other two cases. The colorless spiropyran state **5** switches to the merocyanine form **7** upon irradiation with ultraviolet light. It switches to the protonated merocyanine from **6** when treated with H$^+$. The colored state **7** isomerizes back to **5** in the dark or upon irradiation with visible light. Alternatively, **7** switches to **6** when treated with H$^+$. The colored state **6** switches to **5**, when irradiated with visible light, and to **7**, after the removal of H$^+$. In summary, this three-state molecular switch responds to two optical inputs (I1 and I2) and one chemical input (I3) producing two optical outputs (O1 and O2). Binary digits can be encoded on each signal applying positive logic conventions (low = 0, high = 1). It follows that the three-state molecular switch converts input strings of three binary digits into output strings of two binary digits. The corresponding truth table (Fig. 2.8) reveals that the optical output O1 is high (O1 = 1) when only the input I3 is applied (I1 = 0, I2 = 0, I3 = 1), when only the input I2 is not applied (I1 = 1, I2 = 0, I3 = 0), or when all three inputs are applied (I1 = 1, I2 = 0, I3 = 0). The optical output O2 is high (O2 = 1) when only the input I1 is applied (I1 = 1, I2 = 0, I3 = 0) or when only the input I3 is not applied (I1 = 1, I2 = 0, I3 = 0). The combinational logic circuit (Fig. 2.8) equivalent to this truth table shows that all three inputs determine the output O1, while only I1 and I3 control the value of O2.

2.2.5 Intermolecular Communication

The combinational logic circuits in Figs. 2.7 and 2.8 are arrays of interconnected AND, NOT, and OR operators. The digital communication between these basic logic elements ensures the execution of a sequence of simple logic operations that results in the complex logic function processed by the entire circuit. It follows that



I1	I2	I3	O1	O2
0	0	0	0	0
0	0	1	1	0
0	1	0	0	0
1	0	0	0	1
0	1	1	0	0
1	0	1	1	0
1	1	0	0	1
1	1	0	1	0

Fig. 2.8 Ultraviolet light (I1), visible light (I2), and H^+ (I3) inputs induce the interconversion between the three states **5**, **6**, and **7**. The colorless state **5** does not absorb in the visible region. The yellow-green state **6** absorbs at 401 nm (O1). The purple state **7** absorbs at 563 nm (O2). The truth table illustrates the conversion of input strings of three binary digits (I1, I2, and I3) into output strings of two binary digits (O1 and O2) operated by this three-state molecular switch. A combinational logic circuit incorporating nine AND, NOT, and OR operators correspond to this particular truth table

the logic function of a given circuit can be adjusted altering the number and type of basic gates and their interconnection protocol [2.17]. This modular approach to combinational logic circuits is extremely powerful. Any logic function can be implemented connecting the appropriate combination of simple AND, NOT, and OR gates.

The strategies followed so far to implement complex logic functions with molecular switches are based on the careful design of the chemical system and on the judicious choice of the inputs and outputs [2.20, 21]. A specific sequence of AND, NOT, and OR operations is programmed in a single molecular switch. No digital communication between distinct gates is needed since they are built in the same molecular entity. Though extremely elegant, this strategy does not have the same versatility of a modular approach. A different molecule has to be designed, synthesized, and analyzed every single time a different logic function has to be realized. In addition, the degree of complexity that can be achieved with only one molecular switch is fairly limited. The connection of the input and output terminals of independent molecular AND, NOT, and OR operators, instead, would offer the possibility of assembling any combinational logic circuit from three basic building blocks.

In digital electronics, the communication between two logic gates can be realized connecting their terminals with a wire [2.19]. Methods to transmit binary data between distinct molecular switches are not so obvious and must be identified. Recently we developed two strategies to communicate signals between compatible molecular components. In one instance, a chemical signal is communicated between two distinct molecular switches [2.26]. They are the three-state switch illustrated in Fig. 2.8 and the two-state switch of Fig. 2.9. The merocyanine form **7** is a photogenerated base. Its *p*-nitrophenolate fragment, produced upon irradiation of the colorless state **5** with ultraviolet light, can abstract a proton from an acid present in the same solution. The resulting protonated form **6** is a photoacid. It releases a proton upon irradiation with visible light and can protonate a base co-dissolved in the same medium. The orange azopyridine **8** switches to the red-purple azopyridinium **9** upon protonation. This process is reversible, and the addition of a base restores the orange state **8**. It follows that photoinduced proton transfer can be exploited to communicate a chemical signal from **6** to **8** and from **9** to **7**. The two colored states **8** and **9** have different absorption properties in the visible region. In acetonitrile, the orange state **8** absorbs at 422 nm, and the red-purple state **9** absorbs at 556 nm. The changes in absorbance of these two bands can be exploited to monitor the photoinduced exchange of protons between the two communicating molecular switches.



I1	I2	O
0	0	0 or 1
0	1	1
1	0	0
1	1	0

Fig. 2.9 The concentration of H^+ controls the reversible interconversion between the two states **8** and **9**. In response to ultraviolet (I1) and visible (I2) inputs, the three-state molecular switch in Fig. 2.7 modulates the ratio between these two forms and the absorbance (O) of **9** through photoinduced proton transfer. The truth table and sequential logic circuit illustrate the signal transduction behavior of the two communicating molecular switches. The interconversion between the five three-digit strings of input (I1 and I2) and output (O) data is achieved varying the input values in steps

The three-state molecular switch and the two-state molecular switch can be operated sequentially when dissolved in the same acetonitrile solution. In the presence of one equivalent of H^+, the two-state molecular switch is in state **9** and the absorbance at 556 nm is high ($O = 1$). Upon irradiation with ultraviolet light ($I1 = 0$), **5** switches to **7**. The photogenerated base deprotonates **9** producing **8** and **6**. As a result, the absorbance at 556 nm decreases ($O = 0$). Upon irradiation with visible light ($I2 = 1$), **6** switches to **5** releasing H^+. The result is the protonation of **8** to form **9** and restore the high absorbance at 556 nm ($O = 1$). In summary, the three-state molecular switch transduces two optical inputs ($I1 =$ ultraviolet light, $I2 =$ visible light) into a chemical signal (proton transfer) that is communicated to the two-state molecular switch and converted into a final optical output ($O =$ absorbance at 556 nm).

The logic behavior of the two communicating molecular switches is significantly different from those of the chemical systems illustrated in Figs. 2.6, 2.7, and 2.8 [2.26]. The truth table in Fig. 2.9 lists the four possible combinations of two-digit input strings and the corresponding one-digit output. The output digit O for the input strings 01, 10, and 11 can take only one value. In fact, the input string 01 is transduced into a 1, and the input strings 10 and 11 are converted into 0. Instead, the output digit O for the input string 00 can be either 0 or 1. The sequence of events leading to the input string 00 determines the value of the output. The boxes ***a*–*e*** in Fig. 2.9 illustrates this effect. They correspond to the five three-digit input/output strings. The transformation of one box into any of the other four is achieved in one or two steps by changing the values of I1 and/or I2. In two instances (***a*** and ***b***), the two-state molecular switch is in state **9**, and the output signal is high ($O = 1$). In the other three cases (***c***, ***d***, and ***e***), the two-state molecular switch is in state **8**, and the output signal is low ($O = 0$). The strings 000 (***e***) and 001 (***a***) correspond to the first entry of the truth table. They share the same input digits but differ in the output value. The string 000 (***e***) can be obtained only from the string 100 (***c***) varying the value of I1. Similarly, the string 001 (***a***) can be accessed only from the string 011 (***b***) varying the value of I2. In both transformations, the output digit remains unchanged. Thus, the value of O1 in the parent string is memorized and maintained in the daughter string when both inputs become 0. This memory effect is the fundamental operating principle of sequential logic circuits [2.17], which are used extensively to assemble the memory elements of modern microprocessors. The sequential logic circuit equivalent to the truth table of the two communicating molecular switches is also shown in Fig. 2.9. In this circuit, the input data I1 and I2 are combined through NOT, OR, and AND operators. The output of the AND gate O is also an input of the OR gate and controls, together with I1 and I2, the signal transduction behavior.

The other strategy for digital transmission between molecules is based on the communication of optical signals between the three-state molecular switch (Fig. 2.8) and fluorescent compounds [2.27, 28]. In the optical network of Fig. 2.10, three optical signals travel from an excitation source to a detector after passing through two quartz cells. The first cell contains an equimolar acetonitrile solution of naphthalene, anthracene, and tetracene. The second cell contains an acetonitrile solu-



I1	I2	I3	O1	O2	O3
0	0	0	0	1	1
0	0	1	0	0	1
0	1	0	0	1	1
1	0	0	0	0	0
0	1	1	0	1	1
1	0	1	0	0	1
1	1	0	0	0	0
1	1	1	0	0	1

Fig. 2.10 The excitation source sends three monochromatic light beams (275, 357, and 441 nm) to a quartz cell containing an equimolar acetonitrile solution of naphthalene, anthracene and tetracene. The three fluorophores absorb the exciting beams and reemit at 305, 401, and 544 nm, respectively. The light emitted in the direction perpendicular to the exciting beams passes through another quartz cell containing an acetonitrile solution of the three-state molecular switch shown in Fig. 2.7. Ultraviolet (I1), visible (I2), and H^+ (I3) inputs control the interconversion between the three states of the molecular switch. They determine the intensity of the optical outputs reaching the detector and correspond to the naphthalene (O1), anthracene (O2), and tetracene (O3) emissions. The truth table and equivalent combinational logic illustrate the relation between the three inputs and the three outputs. The output O1 is always 0, and it is not influenced by the three inputs. Only two inputs determine the value of O3, while all of them control the output O2

tion of the three-state molecular switch. The excitation source sends three consecutive monochromatic light beams to the first cell stimulating the emission of the three fluorophores. The light emitted in the direction perpendicular to the exciting beam reaches the second cell. When the molecular switch is in state **5**, the naphthalene emission at 335 nm is absorbed and a low intensity output (O1) reaches the detector. Instead, the anthracene and tetracene emissions at 401 and 544 nm, respectively, pass unaffected and high intensity outputs (O2 and O3) reach the detector. When the molecular switch is in state **6**, the naphthalene and anthracene emissions are absorbed and only the tetracene emission reaches the detector ($O1 = 0$, $O2 = 0$, $O3 = 1$). When the molecular switch is state **7**, the emission of all three fluorophores is absorbed ($O1 = 0$, $O2 = 0$, $O3 = 0$). The interconversion of the molecular switch between the three states is induced addressing the second cell with ultraviolet (I1), visible (I2) and H^+ (I3) inputs. Thus, three independent optical outputs (O1, O2 and O3) can be modulated stimulating the molecular switch with two optical and one chemical input. The truth table in Fig. 2.10 illustrates the relation between the three inputs (I1, I2 and I3) and the three outputs (O1, O2 and O3), when positive logic conventions are applied to all signals. The equivalent logic circuit shows that all three inputs control the anthracene channel O2, but only I1 and I3 influence the tetracene channel O3. Instead, the intensity of the naphthalene channel O1 is always low, and it is not affected by the three inputs.

The operating principles of the optical network in Fig. 2.10 can be simplified to implement all-optical logic gates. The chemical input inducing the formation of the protonated form **6** of the molecular switch can be eliminated. The interconversion between the remaining two states **5** and **7** can be controlled relying exclusively on ultraviolet inputs. Indeed, ultraviolet irradiation induces the isomerization of the colorless form **5** to the colored species **7**, which reisomerizes to the original state in the dark. Thus, a single ultraviolet source is sufficient to control the switching from **5** to **7** and vice versa. On the basis of these considerations, all-optical NAND, NOR, and NOT gates can be implemented operating sequentially or in parallel from one to three independent switching elements [2.28]. For example, the all-optical network illustrated in Fig. 2.11 is a three-input NOR gate. A monochromatic optical signal travels from a visible source to a detector. Three switching elements are aligned along the path of the traveling light. They are quartz cells containing an acetonitrile solution of the mo-



I1	I2	I3	O
0	0	0	1
0	0	1	0
0	1	0	0
1	0	0	0
0	1	1	0
1	0	1	0
1	1	0	0
1	1	1	0

Fig. 2.11 The visible source sends a monochromatic beam (563 nm) to the detector. The traveling light is forced to pass through three quartz cells containing the molecular switch illustrated in Fig. 2.7. The three switching elements are operated by independent ultraviolet inputs. When at least one of them is on, the associated molecular switch is in the purple form **7**, which can absorb and block the traveling light. The truth table and equivalent logic circuit illustrate the relation between the three inputs I1, I2, and I3 and the optical output O

lecular switch shown in Fig. 2.8. The interconversion of the colorless form **5** into the purple isomer **7** is induced stimulating the cell with an ultraviolet input. The reisomerization from **7** to **5** occurs spontaneously, as the ultraviolet sources is turned off. Using three distinct ultraviolet sources, the three switching elements can be controlled independently.

The colorless form **5** does not absorb in the visible region, while the purple isomer **7** has a strong absorption band at 563 nm. Thus, a 563 nm optical signal leaving the visible source can reach the detector unaffected only if all three switching elements are in the nonabsorbing state **5**. If one of the three ultraviolet inputs I1, I2, or I3 is turned on, the intensity of the optical output O drops to 3–4% of its original value. If two or three ultraviolet inputs are turned on simultaneously, the optical output drops to 0%. Indeed, the photogenerated state **7** absorbs and blocks the traveling light. Applying positive logic conventions to all signals, binary digits can be encoded in the three optical inputs and in the optical output. The resulting truth table is illustrated in Fig. 2.11. The output O is 1 only if all three inputs I1, I2, or I3 are 0. The output O is 0 if at least one of the three inputs I1, I2, or I3 is 1. This signal transduction corresponds to that executed by a three-input NOR gate, which is a combination of one NOT and two OR operators.

2.3 Solid State Devices

The fascinating chemical systems illustrated in Figs. 2.6–2.11 demonstrate that logic functions can be implemented relying on the interplay between designed molecules and chemical, electrical and/or optical signals [2.20, 21].

2.3.1 From Functional Solutions to Electroactive and Photoactive Solids

These molecular switches, however, are operated exclusively in solution and remain far from potential applications in information technology at this stage. The integration of liquid components and volatile organic solvents in practical digital devices is hard to envisage. Furthermore, the logic operations executed by these chemical systems rely on bulk addressing. Although the individual molecular components have nanoscaled dimensions, macroscopic collections of them are employed for digital processing. In some instances, the operating principles cannot even be scaled down to the unimolecular level. Often bulk properties are responsible for signal transduction. For example, a single fluorescent compound **2** cannot execute an OR operation. Its azacrown appendage can accommodate only one metal cation. As a result, an individual molecular switch can respond to only one of the two chemical inputs. It is a collection of numerous molecular switches dissolved in an organic solvent that responds to both inputs enabling an OR operation.

The development of miniaturized molecule-based devices requires the identification of methods to transfer the switching mechanisms developed in solution to the solid state [2.29]. Borrowing designs and fabrication strategies from conventional electronics, researchers are starting to explore the integration of molecular components into functional circuits and devices [2.30–33]. Generally, these strategies combine lithography and surface chemistry to assemble nanometer-thick organic films on the surfaces of microscaled or nanoscaled electrodes. Two main approaches for the deposition of organized molecular arrays on inorganic supports have emerged so far. In one instance, amphiphilic molecular building blocks are compressed into organized monolayers at air/water interfaces. The resulting films can be transferred on supporting solids employing the Langmuir–Blodgett technique [2.34]. Alternatively, certain molecules can be designed to adsorb spontaneously on the surfaces of compatible solids from liquid or vapor phases. The result is the self-assembly of organic layers on inorganic supports [2.35].

2.3.2 Langmuir–Blodgett Films

Films of amphiphilic molecules can be deposited on a variety of solid supports employing the Langmuir–Blodgett technique [2.34]. This method can be extended to electroactive compounds incorporating hydrophilic and hydrophobic groups. For example, the amphiphile **10** (Fig. 2.12) has a hydrophobic hexadecyl tail attached to a hydrophilic bipyridinium dication [2.36, 37]. This compound dissolves in mixtures of chloroform and methanol, but it is not soluble in moderately concentrated aqueous solutions of sodium perchlorate.



Fig. 2.12 The compression of the amphiphilic dication **10** with a moving barrier results in the formation of a packed monolayer at the air/water interface. The lifting of an electrode pre-immersed in the aqueous subphase encourages the transfer of part of the monolayer on the solid support

Thus the spreading of an organic solution of **10** on an aqueous sodium perchlorate subphase affords a collection of disorganized amphiphiles floating on the water surface (Fig. 2.12), after the organic solvent has evaporated. The molecular building blocks can be compressed into a monolayer with the aid of a moving barrier. The hydrophobic tails align away from the aqueous phase. The hydrophilic dicationic heads and the accompanying perchlorate counterions pack to form an organized monolayer at the air/water interface. The compression process can be monitored recording the surface pressure (π)-area per molecule (A) isotherm, which indicates a limiting molecular area of ca. 50 Å^2. This value is larger than the projected area of an oligomethylene chain. It correlates reasonably, however, with the overall area of a bipyridinium dication plus two perchlorate anions.

The monolayer prepared at the air/water interface (Fig. 2.12) can be transferred on the surface of a indium-tin oxide electrode pre-immersed in the aqueous phase. The slow lifting of the solid support drags the monolayer away from the aqueous subphase. The final result is the coating of the electrode with an organic film containing electroactive bipyridinium building blocks. The modified electrode can be integrated in a conventional electrochemical cell to probe the redox response of the electroactive layer. The resulting cyclic voltammograms reveal the characteristic waves for the first reduction process of the bipyridinium dications, confirming the successful transfer of the electroactive amphiphiles from the air/water interface to the electrode surface. The integration of the redox waves indicates a surface coverage of ca. 4×10^{10} mol cm^{-2}. This value corresponds to a molecular area of ca. 40 Å^2 and is in excellent agreement with the limiting molecular area of the π–A isotherm.

These seminal experiments demonstrate that electroactive amphiphiles can be organized into uniform monolayers at the air/water interface and then transferred efficiently on the surface of appropriate substrates to produce electrode/monolayer junctions. The resulting electroactive materials can become the functional components of molecule-based devices. For example, bipyridinium-based photodiodes can be fabricated following this approach [2.38, 39]. Their operating principles rely on photoinduced electron transfer from chromophoric units to bipyridinium acceptors. The electroactive and photoactive amphiphile **11** (Fig. 2.13) incorporates hydrophobic ferrocene and pyrene tails and a hydrophilic bipyridinium head. Chloroform solutions of **11** containing ten equivalents of arachidic acid can be spread on an aqueous calcium chloride subphase in a Langmuir trough. The amphiphiles can be compressed into a mixed monolayer, after the evaporation of the organic solvent. Pronounced steps in the corresponding π–A isotherm suggest that the bulky ferrocene and pyrene groups are squeezed away from the water surface. In the final arrangement, both photoactive groups align above the hydrophobic dication.



Fig. 2.13 Mixed monolayers of the amphiphile **11** and arachidic acid can be transferred from the air/water interface to the surface of an electrode to generate a molecule-based photodiode

A mixed monolayer of **11** and arachidic acid can be transferred from the air/water interface to the surface of a transparent gold electrode following the methodology illustrated for the system in Fig. 2.12. The coated electrode can be integrated in a conventional electrochemical cell. Upon irradiation at 330 nm under an inert atmosphere, an anodic photocurrent of ca. 2 nA develops at a potential of 0 V relative to a saturated calomel electrode. Indeed, the illumination of the electroactive monolayer induces the electron transfer from the pyrene appendage to the bipyridinium acceptor and then from the reduced acceptor to the electrode. A second intramolecular electron transfer from the ferrocene donor to the oxidized pyrene fills its photogenerated hole. Overall, a unidirectional flow of electrons across the monolayer/electrode junction is established under the influence of light.

The ability to transfer electroactive monolayers from air/water interfaces to electrode surfaces can be exploited to fabricate molecule-based electronic devices. In particular, arrays of interconnected electrode/monolayer/electrode tunneling junctions can be assembled combining the Langmuir–Blodgett technique with electron beam evaporation [2.33]. Fig. 2.14 illustrates a schematic representation of the resulting devices. Initially, parallel fingers are patterned on a silicon wafer with a silicon dioxide overlayer by electron beam evaporation. The bottom electrodes deposited on the support can be either aluminum wires covered by an aluminum oxide or n-doped silicon lines with silicon dioxide overlayers. Their widths are ca. 6 or 7 μm, respectively. The patterned silicon chip is immersed in the aqueous subphase of a Langmuir trough prior to monolayer formation. After the compression of electroactive amphiphiles at the air/water interface, the substrate is pulled out of the aqueous phase to encourage the transfer of the molecular layer on the parallel bottom electrodes as well as on the gaps between them. Then, a second set of electrodes orthogonal to the first is deposited through a mask by electron beam evaporation. They consist of a titanium underlayer plus an aluminum overlayer. Their thicknesses are ca. 0.05 and 1 μm, respectively, and their width is ca. 10 μm. In the final assembly, portions of the molecular layer become sandwiched between the bottom and top electrodes. The active areas of these electrode/monolayer/electrode junctions are ca. 60–70 μm^2 and correspond to ca. 10^6 molecules.

The [2]rotaxane **12** (Fig. 2.14) incorporates a macrocyclic polyether threaded onto a bipyridinium-based backbone [2.40, 41]. The two bipyridinium dications are bridged by a m-phenylene spacer and terminated by tetraarylmethane appendages. These two bulky groups trap mechanically the macrocycle preventing its dis-



Fig. 2.14 The [2]rotaxane **12** and the [2]catenane **13** can be compressed into organized monolayers at air/water interfaces. The resulting monolayers can be transferred on the bottom electrodes of a patterned silicon support. After the deposition of a top electrode, electrode/monolayer/electrode junctions can be assembled. Note that only the portion of the monolayer sandwiched between the top and bottom electrodes is shown in the diagram. The oxidation of the tetrathiafulvalene unit of the [2]catenane **13** is followed by the circumrotation of the macrocyclic polyether to afford the [2]catenane **14**. The process is reversible, and the reduction of the cationic tetrathiafulvalene unit restores the original state

sociation from the tetracationic backbone. In addition, their hydrophobicity complements the hydrophilicity of the two bipyridinium dications imposing amphiphilic character on the overall molecular assembly. This compound does not dissolve in aqueous solutions and can be compressed into organized monolayers at air/water interfaces. The corresponding π–A isotherm reveals a limiting molecular area of ca. 130 Å^2. This large value is a consequence of the bulk associated with the hydrophobic tetraarylmethane tails and the macrocycle encircling the tetracationic backbone.

Monolayers of the [2]rotaxane **12** can be transferred from the air/water interface to the surfaces of the bottom aluminum/aluminum oxide electrodes of a patterned silicon chip with the hydrophobic tetraarylmethane groups pointing away from the supporting substrate. The subsequent assembly of a top titanium/aluminum electrode affords electrode/monolayer/electrode junctions. Their current/voltage signature can be recorded grounding the top electrode and scanning the potential of the bottom electrode. A pronounced increase in current is observed when the potential is lowered below -0.7 V. Under these conditions, the bipyridinium-centered LUMOs mediate the tunneling of electrons from the bottom to the top electrode leading to a current enhancement. A similar current profile is observed if the potential is returned to 0 and then back to -2 V. Instead, a modest increase in current in the opposite direction is observed when the potential is raised above $+0.7$ V. Presumably, this trend is a result of the participation of the phenoxy-centered HOMOs in the tunneling process. After a single positive voltage pulse, however, no current can be detected if the potential is returned to negative values. In summary, the positive potential scan suppresses irreversibly the conducting ability of the electrode/molecule/electrode junction. The behavior of this device correlates with the redox response of the [2]rotaxane **12** in solution. Cyclic voltammograms reveal reversible monoelectronic reductions of the bipyridinium dications. But they also show two irreversible oxidations associated, presumably, with the phenoxy rings of the macrocycle and tetraarylmethane groups. These observations suggest that a positive voltage pulse applied to the electrode/monolayer/electrode junction oxidizes irreversibly the sandwiched molecules suppressing their ability to mediate the transfer of electrons from the bottom to the top electrode under a negative bias.

The device incorporating the [2]rotaxane **13** can be exploited to implement simple logic operations [2.40]. The two bottom electrodes can be stimulated with voltage inputs (I1 and I2) while measuring a current output (O) at the common top electrode. When at least one of the two inputs is high (0 V), the output is low (< 0.7 nA). When both inputs are low (-2 V), the output is high (ca. 4 nA). If a negative logic convention is applied to the voltage inputs (low = 1, high = 0) and a positive logic convention is applied to the current output (low = 0, high = 1), the signal transduction behavior translates into the truth table of an AND gate. The output O is 1 only when both inputs are 1. Instead, an OR operation can be executed if the logarithm of the current is considered as the output. The logarithm of the current is -12 when both voltage inputs are 0 V. It raises to ca. -9 when one or both voltage inputs are lowered to -2 V. This signal transduction behavior translates into the truth table of an OR gate if a negative logic convention is applied to the voltage inputs (low = 1, high = 0) and a positive logic convention is applied to the current output (low = 0, high = 1). The output O is 1 when at least one of the two inputs is 1.

The [2]catenane **13** (Fig. 2.14) incorporates a macrocyclic polyether interlocked with a tetracationic cyclophane [2.42, 43]. Organic solutions of the hexafluorophosphate salt of this [2]catenane and six equivalents of the sodium salt of dimyristoylphosphatidic acid can be co-spread on the water surface of a Langmuir trough [2.44]. The sodium hexafluorophosphate formed dissolves in the supporting aqueous phase, while the hydrophilic bipyridinium cations and the amphiphilic anions remain at the interface. Upon compression, the anions align their hydrophobic tails away from the water surface forming a compact monolayer above the cationic bipyridinium derivatives. The corresponding π–A isotherm indicates limiting molecular areas of ca. 125 Å^2. This large value is a consequence of the bulk associated with the two interlocking macrocycles.

Monolayers of the [2]catenane **13** can be transferred from the air/water interface to the surfaces of the bottom n-doped silicon/silicon dioxide electrodes of a patterned silicon chip with the hydrophobic tails of the amphiphilic anions pointing away from the supporting substrate [2.45, 46]. The subsequent assembly of a top titanium/aluminum electrode affords electrode/monolayer/electrode arrays. Their junction resistance can be probed grounding the top electrode and maintaining the potential of the bottom electrode at $+0.1$ V. If a voltage pulse of $+2$ V is applied to the bottom electrode before the measurement, the junction resistance probed is ca. 0.7 GΩ. After a pulse of -2 V applied to the bottom electrode, the junction resistance probed at $+0.1$ V drops ca. 0.3 GΩ. Thus, alternating positive and negative voltage pulses can switch reversibly the junction resistance between high and low values. This intriguing behavior is a result of the redox and dynamic properties of the [2]catenane **13**.

Extensive spectroscopic and crystallographic studies [2.42, 43] demonstrated that the tetrathiafulvalene unit resides preferentially inside the cavity of the tetracationic cyclophane of the [2]catenane **13** (Fig. 2.14). Attractive $[\pi \cdots \pi]$ stacking interactions between the neutral tetrathiafulvalene and the bipyridinium dications are responsible for this co-conformation. Oxidation of the tetrathiafulvalene generates a cationic form that is expelled from the cavity of the tetracationic cyclophane. After the circumrotation of the macrocyclic polyether, the oxidized tetrathiafulvalene is exchanged with the neutral 1,5-dioxynaphthalene producing the [2]catenane **14** (Fig. 2.14). The reduction of the tetrathiafulvalene back to its neutral state is followed by the circumrotation of the macrocyclic polyether, which restores the original state **14**. The voltage pulses applied to the bottom electrode of the electrode/monolayer/junction oxidize and reduce the tetrathiafulvalene unit inducing the interconversion between the forms **13** and **14**. The difference in the stereoelectronic properties of these two states translates into distinct current/voltage signatures. Indeed, their ability to mediate the tunneling of electrons across the junction differs significantly. As a result, the junction resistance probed at a low voltage after an oxidizing pulse is significantly different from that determined under the same conditions after a reducing pulse.

2.3.3 Self-Assembled Monolayers

In the examples illustrated in Figs. 2.12–2.15, monolayers of amphiphilic and electroactive derivatives are assembled at air/water interfaces and then transferred on the surfaces of appropriate substrates. An alternative strategy to coat electrodes with molecular layers relies on the ability of certain compounds to adsorb spontaneously on solid supports from liquid or vapor phases [2.35]. In particular, the affinity of certain sulfurated functional groups for gold can be exploited to encourage the self-assembly of organic molecules on microscaled and nanoscaled electrodes.

The electrode/monolayer/electrode junction in Fig. 2.15a incorporates a molecular layer between two gold electrodes mounted on a silicon nitride support. This device can be fabricated combining chemical vapor deposition, lithography, anisotropic etching, and self-assembly [2.47]. Initially, a silicon wafer is coated with a 50 nm thick layer of silicon nitride by low pressure chemical vapor deposition. Then, a square of $400 \times 400\,\mu\text{m}$ is patterned on one side of the coated wafer by optical lithography and reactive ion etching. Anisotropic etching of the exposed silicon up to the other side of the wafer leaves a suspended silicon nitride membrane of $40\times40\,\mu\text{m}$. Electron beam lithography and reactive ion etching can be used to carve a bowl-shaped hole (diameter = 30–50 nm) in the membrane. Evaporation of gold on the membrane fills the pore producing a bowl-shaped electrode. Immersion of the substrate in a solution of the thiol **15** results in the self-assembly of a molecular layer on the narrow part of the bowl-shaped electrode. The subsequent evaporation of a gold film on the organic monolayer produces an electrode/monolayer/electrode junction (Fig. 2.15a) with a contact area of less than 2,000 nm^2 and approximately 1,000 molecules.



Fig. 2.15 **(a)** A monolayer of the thiol **15** is embedded between two gold electrodes maintained in position by a silicon nitride support. **(b)** A monolayer of the bisthiol **16** is located between two gold electrodes and stimulated by a silicon gate

Under the influence of voltage pulses applied to one of the two gold electrodes in Fig. 2.15a, the conductivity of the sandwiched monolayer switches reversibly between low and high values [2.48]. In the initial state, the monolayer is in a low conducting mode. A current output of only 30 pA is detected, when a probing voltage of $+0.25$ V is applied to the bowl-shaped electrode. If the same electrode is stimulated with a short voltage pulse of $+5$ V, the monolayer switches to a high conducting mode. Now a current output of 150 pA is measured at the same probing voltage of $+0.25$ V. Repeated probing of the current output at various intervals of time indicates that the high conducting state is memorized by the molecule-based device, and it is retained for more than 15 min. The low conducting mode is restored after either a relatively long period of time or the stimulation of the bowl-shaped electrode with a reverse voltage pulse of -5 V. Thus the current output switches from a low to a high value, if a high voltage input is applied. It switches from a high to a low value, under the influence of a low voltage pulse. This behavior offers the opportunity to store and erase binary data in analogy to a conventional random access memory [2.17]. Binary digits can be encoded on the current output of the molecule-based device applying a positive logic convention (low $=0$, high $=1$). It follows that a binary 1 can be stored in the molecule-based device applying a high voltage input, and it can be erased applying a low voltage input [2.48].

The electrode/monolayer/electrode junctions in Fig. 2.14 and in Fig. 2.15a are two-terminal devices. A voltage input is applied to one terminal, and a current output is measured at the other. The implementation of molecule-based transistors, however, requires three terminals. A third electrode is needed to gate the current flowing between the source and drain terminals. These types of devices are much more versatile than their two-terminal counterparts for the implementation of logic functions. But the incorporation of molecular components in a three-terminal configuration is considerably more challenging. A remarkable example is the composite assembly in Fig. 2.15b [2.49]. This field-effect transistor integrates a monolayer of the bisthiol **16** and three electrodes. Conventional lithography and anisotropic etching are employed to define a vertical step in a doped silicon substrate. The resulting structure is covered with an insulating layer of silicon dioxide with a thickness of ca. 30 nm. Then gold is evaporated on the bottom part of the step to allow the self-assembly the bisthiol **16**. Under the influence of the gate voltage, the molecular components embedded in this device modulate the current flowing between the source and drain electrodes. The intensity of the drain current increases by five orders of magnitude if the gate voltage is lowered below -0.2 V. It is important to note, however, that only the molecules within 5 nm from the monolayer/insulator interface are responsible for conduction. Thus the current/voltage behavior of this three-terminal device is determined only by few thousand molecules.

Conventional transistors are the basic building blocks of digital circuits [2.19]. They are routinely interconnected with specific configurations to execute designed logic functions. The molecule-based transistor in Fig. 2.15b is no exception. It can be used to assemble real electronic circuits incorporating molecular components. The connection of the drain terminals of two molecule-based transistors affords an inverter [2.49]. In this basic circuit, an output voltage switches from a high (0 V) to a low value (-2 V) when an input voltage varies from a low (-2 V) to a high value (0 V) and vice versa. This signal transduction behavior translates into the truth table of a NOT gate, if a positive logic convention (low $=0$, high $=1$) is applied to the input and output voltages.

The ability of thiols to self-assemble on the surface of gold can be exploited to fabricate nanocomposite materials integrating organic and inorganic components. For example, the bisthiol **17** forms monolayers (Fig. 2.16a) on gold electrodes with surface coverages of ca. 4.1×10^{10} mol cm^2 [2.50, 51]. The formation of a thiolate–gold bond at one of the two thiol ends of **17** is responsible for adsorption. The remaining thiol group points away from the supporting surface and can be exploited for further functionalization. Gold nanoparticles adsorb on the molecular layer (Fig. 2.16b), once again, as a result of thiolate–gold bond formation. The immersion of the resulting material in a methanol solution of **17** encourages the adsorption of an additional organic layer (Fig. 2.16c) on the composite material. Following these procedures, up to ten alternating organic and inorganic layers can be deposited on the electrode surface. The resulting assembly can mediate the unidirectional electron transfer from the supporting electrode to redox active species in solution. For example, the cyclic voltammogram of the $[\mathrm{Ru(NH_3)_6}]^{3+/2+}$ couple recorded with a bare gold electrode reveals a reversible reduction process. In the presence of ten alternating molecular and nanoparticle layers on the electrode surface, the reduction potential shifts by ca. -0.2 V and the back oxidation wave disappears. The pronounced potential shift indicates that $[\mathrm{Ru(NH_3)_6}]^{3+}$ accepts electrons only after the surface-confined bipyridinium dications have been reduced. The lack of reversibility indicates that the back oxidation to the bipyridinium dications inhibits the transfer of electrons from the $[Ru(NH_3)_6]^{2+}$ to the electrode. Thus the electroactive multilayer allows the flow of electrons in one direction only in analogy to conventional diodes.

The current/voltage behavior of individual nanoparticles in Fig. 2.16b can be probed by scanning tunneling spectroscopy in an aqueous electrolyte under an inert atmosphere [2.52]. The platinum-iridium tip of a scanning tunneling microscope is positioned above one of the gold particles. The voltage of the gold substrate relative to the tip is maintained at $-0.2\,\mathrm{V}$ while that relative to a reference electrode immersed in the same electrolyte is varied to control the redox state of the electroactive units. Indeed, the bipyridinium dications in the molecular layer can be reduced reversibly to a monocationic state. The resulting monocations can be reduced further and, once again, reversibly to a neutral form. Finally, the current flowing from the gold support to the tip of the scanning tunneling microscope is monitored as the tip–particle distance increases. From the distance dependence of the current, inverse length decays of ca. 16 and $7\,\mathrm{nm}^{-1}$ for the dicationic and monocationic states, respectively, of the molecular spacer can be determined. The dramatic decrease indicates that the reduction of the electroactive unit facilitates the tunneling of electrons through the gold/molecule/nanoparticle/tip junction. In summary, a change in the redox state of the bipyridinium components can be exploited to gate reversibly the current flowing through this nanoscaled device.

Similar nanostructured materials, combining molecular and nanoparticles layers, can be prepared on layers on indium-tin oxide electrodes following multistep procedures [2.53]. The hydroxylated surfaces of indium-tin oxide supports can be functionalized with 3-ammoniumpropylysilyl groups and then exposed to gold nanoparticles having a diameter of ca. 13 nm [2.54, 55]. Electrostatic interactions promote the adsorption of the nanoparticles on the organic layer (Fig. 2.17a). The treatment of the composite film with the bipyridinium cyclophane **18** produces an organic layer on the gold nanoparticles (Fig. 2.18b). Following this approach, alternating layers of inorganic nanoparticles and organic building blocks can be assembled on the indium-tin oxide support. Cyclic voltammograms of the resulting materials show the oxidation of the gold nanoparticles and the reduction of the bipyridinium units. The peak current for both processes increases with the number of alternating layers. Comparison of these values indicates that the ratio between the number of tetracationic cyclophanes and that of the nanoparticles is ca. 100 : 1.


a)
Gold
Adsorption of gold nanoparticles
b)
Gold
Gold
Gold
Adsorption of the bisthiol 17
c)
Gold
Gold
Gold
HS
Br⁻
N+
17
+N
SH

Fig. 2.16 **(a)** The bisthiol **18** self-assembles on gold electrodes as a result of thiolate–gold bond formation. **(b)** Gold nanoparticles adsorb spontaneously on the molecular layer. **(c)** Exposure of the composite assembly to a solution of **18** results in the formation of an additional molecular layer on the surface of the gold nanoparticles

The tetracationic cyclophane **18** binds dioxyarenes in solution [2.56, 57]. Attractive supramolecular forces between the electron deficient bipyridinium units and the electron rich guests are responsible for complexation. This recognition motif can be exploited to probe the ability of the composite films in Fig. 2.17b,c to sense electron rich analytes. In particular, hydroquinone is expected to enter the electron deficient cavities of the surface-confined cyclophanes. Cyclic voltammograms consistently reveal the redox waves associated with the reversible oxidation of hydroquinone even when very small amounts of the guest (ca. 1×10^{5} M) are added to the electrolyte solution [2.54, 55]. No redox response can be detected with a bare indium–tin oxide electrode under otherwise identical conditions. The supramolecular association of the guest and the surface confined


a)
O
O–Si
O
NH3
Gold
Indium-Tin
oxide
18
Adsorption
of 18
b)
Gold
Indium-Tin
oxide
19
Me
Me
Ru2+
Me
Me
Adsorption of
gold nanoparticles
c)
Gold
Gold
Indium-Tin
oxide
d)
PO3H
Titanium
dioxide
Ru2+
N+
Me
Tin
oxide
PO3H

Fig. 2.17 **(a)** Gold nanoparticles assemble spontaneously on prefunctionalized indium-tin oxide electrodes. **(b)** Electrostatic interactions encourage the adsorption of the tetracationic cyclophane **18** on the surface-confined nanoparticles. **(c)** An additional layer of nanoparticles assembles on the cationic organic coating. Similar composite films can be prepared using the tetracationic [2]catenane **19** instead of the cyclophane **18**. **(d)** Phosphonate groups can be used to anchor molecular building blocks to titanium dioxide nanoparticles

cyclophanes increases the local concentration of hydroquinone at the electrode/solution interface enabling its electrochemical detection.

Following a related strategy, the [2]catenane **19** (Fig. 2.17) can be incorporated into similar composite arrays [2.58,59]. This interlocked molecule incorporates a Ru(II)/trisbipyridine sensitizer and two bipyridinium acceptors. Upon irradiation of the composite material at 440 nm, photoinduced electron transfer from the sensitizer to the appended acceptors occurs. The photogenerated hole in the sensitizer is filled after the transfer of an electron from a sacrificial electron donor present in the electrolyte solution. Under a positive voltage bias applied to the supporting electrode, an electron flow from the bipyridinium acceptors to the indium-tin oxide support is established. The resulting current switches between high and low values as the light source is turned on and off.

Another photoresponsive device, assembled combining inorganic nanoparticles with molecular building blocks, is illustrated in Fig. 2.17d. Phosphonate groups can be used to anchor a Ru(II)/trisbipyridine complex with an appended bipyridinium dication to titanium dioxide nanoparticles deposited on a doped tin oxide electrode [2.60, 61]. The resulting composite array can be integrated in a conventional electrochemical cell filled with an aqueous electrolyte containing triethanolamine. Under a bias voltage of -0.45 V and irradiation at 532 nm, 95% of the excited ruthenium centers transfer electrons to the titanium dioxide nanoparticles. The other 5% donate electrons to the bipyridinium dications. All the electrons transferred to the bipyridinium acceptors return to the ruthenium centers, while only 80% of those accepted by the nanoparticles return to the transition metal complexes. The remaining 15% reach the bipyridinium acceptors, while electron transfer from sacrificial triethanolamine donors fills the photogenerated holes left in the ruthenium sensitizers. The photoinduced reduction of the bipyridinium dication is accompanied by the appearance of the characteristic band of the radical cation in the absorption spectrum. This band persists for hours under open circuit conditions. But it fades in ca. 15 s under a voltage bias of $+1$ V, as the radical cation is oxidized back to the dicationic form. In summary, an optical stimulation accompanied by a negative voltage bias reduces the bipyridinium building block. The state of the photogenerated form can be read optically, recording the absorption spectrum in the visible region, and erased electrically, applying a positive voltage pulse.

2.3.4 Nanogaps and Nanowires

The operating principles of the electroactive and photoactive devices illustrated in Figs. 2.12–2.17 exploit the ability of small collections of molecular components to manipulate electrons and photons. Designed molecules are deposited on relatively large electrodes and can be addressed electrically and/or optically by controlling the voltage of the support and/or illuminating its surface. The transition from devices relying on collections of molecules to unimolecular devices requires the identification of practical methods to contact single molecules. This fascinating objective demands the rather challenging miniaturization of contacting electrodes to the nanoscale.

A promising approach to unimolecular devices relies on the fabrication of nanometer-sized gaps in metallic features followed by the insertion of individual molecules between the terminals of the gap. This strategy permits the assembly of nanoscaled three-terminal devices equivalent to conventional transistors [2.62–64]. A remarkable example is illustrated in Fig. 2.18a [2.62]. It incorporates a single molecule in the nanogap generated between two gold electrodes. Initially electron beam lithography is used to pattern a gold wire on a doped silicon wafer covered by an insulating silicon dioxide layer. Then the gold feature is broken by electromigration to generate the nanogap. The lateral size of the separated electrodes is ca. 100 nm and their thickness is ca. 15 nm. Scanning electron microcopy indicates that the facing surfaces of the separated electrodes are not uniform and that tiny gaps between their protrusions are formed. Current/voltage measurements suggest that the size of the smallest nanogap is ca. 1 nm. When the



Fig. 2.18 **(a)** Nanoscaled transistors can be fabricated inserting a single molecule (**20** or **21**) between source and drain electrodes mounted on a silicon/silicon dioxide support. **(b)** A DNA nanowire can bridge nanoelectrodes suspended above a silicon dioxide support

breakage of the gold feature is preceded by the deposition of a dilute toluene solution of C_{60} (**20**), junctions with enhanced conduction are obtained. This particular molecule has a diameter of ca. 0.7 nm and can insert in the nanogap facilitating the flow of electrons across the junction.

The unique configuration of the molecule-based device in Fig. 2.18a can reproduce the functions of a conventional transistor [2.19] at the nanoscale. The two gold terminals of the junction are the drain and source of this nanotransistor, and the underlying silicon wafer is the gate. At a temperature of 1.5 K, the junction conductance is very small, when the gate bias is low, and increases in steps at higher voltages [2.62]. The conductance gap is a consequence of the finite energy required to oxidize/reduce the single C_{60} positioned in the junction. It is interesting that the zero-conductance window also changes with the gate voltage and can be opened and closed reversibly adjusting the gate bias.

A similar strategy can be employed to fabricate a nanoscaled transistor incorporating the Co(II) complex **21** shown in Fig. 2.18 [2.64]. In this instance, a silicon dioxide layer with a thickness of ca. 30 nm is grown thermally on a doped silicon substrate. Then a gold wire with a width of ca. 200 nm and a thicknesses of ca. 10–15 nm is patterned on the silicon dioxide overlayer by electron beam lithography. After extensive washing of the substrate with acetone and methylene chloride and cleaning with oxygen plasma, the gold wire is exposed to a solution of the bisthiol **21**. The formation of thiolate–gold bonds promotes the self-assembly of the molecular building block on the gold surface. At this point, electromigration-induced breakage produces a gap of 1–2 nm in the gold wire. The surface-confined bisthiol **21** is only 0.24 nm long and, therefore, it can insert in the nanogap producing an electrode/molecule/electrode junction.

The cobalt center in **21** can be oxidized/reduced reversibly between Co(II) and Co(III) [2.64]. When this electroactive molecule is inserted in a nanogap (Fig. 2.18a), its ability to accept and donate electrodes dictates the current/voltage profile of the resulting electrode/molecule/electrode junction. More precisely, no current flows across the junction below a certain voltage threshold. As the source voltage is raised above this particular value, the drain current increases in steps. The threshold associated with the source voltage varies in magnitude with the gate voltage. This intriguing behavior is a consequence of the finite energy necessary to oxidize/reduce the cobalt center and of a change in the relative stabilities of the oxidized and reduced forms Co(II) and Co(III) with the gate voltage. In summary, the conduction of the electrode/molecule/electrode junction can be tuned adjusting the voltage of the silicon support. The behavior of this molecule-based nanoelectronic device is equivalent to that of a conventional transistor [2.19]. In both instances, the gate voltage regulates the current flowing from the source to the drain.

The electromigration-induced breakage of preformed metallic features successfully produces nanogaps by moving apart two fragments of the same wire. Alternatively, nanogaps can be fabricated reducing the separation of the two terminals of much larger gaps. For example, gold electrodes separated by a distance of 20–80 nm can be patterned on a silicon/silicon dioxide substrate by electron beam lithography [2.65]. The relatively large gap between them can be reduced significantly by the electrochemical deposition of gold on the surfaces of both electrodes. The final result is the fabrication of two nanoelectrodes separated by ca. 1 nm and with a radius of curvature of 5–15 nm. The two terminals of this nanogap can be “contacted” by organic nanowires grown between them [2.66]. In particular, the electropolymerization of aniline produces polyaniline bridges between the gold nanoelectrodes. The conductance of the resulting junction can be probed immersing the overall assembly in an electrolyte solution. Employing a bipotentiostat, the bias voltage of the two terminals of the junction can be maintained at 20 mV, while their potentials are scanned relative to that of a silver/silver chloride reference electrode. Below ca. 0.15 V, the polymer wire is in an insulating state and the current flowing across the junction is less than 0.05 nA. At this voltage threshold, however, the current raises abruptly to ca. 30 nA. This value corresponds to a conductivity for the polymer nanojunction of 10–100 S cm^{-1}. When the potential is lowered again below the threshold, the current returns back to very low values. The abrupt decrease in current in the backward scan is observed at a potential that is slightly more negative than that causing the abrupt current increase in the forward scan. In summary, the conductance of this nanoscaled junction switches on and off as a potential input is switched above and below a voltage threshold.

It is interesting to note that the influence of organic bridges on the junction conductance can be exploited for chemical sensing. Nanogaps fabricated following a similar strategy but lacking the polyaniline bridge alter their conduction after exposure to dilute solutions of small organic molecules [2.67]. Indeed, the organic analytes dock into the nanogaps producing a marked decrease in the junction conductance. The magnitude of the conductance drop happens to be proportional to the analyte–nanoelectrode binding strength. Thus the presence of the analyte in solution can be detected probing the current/voltage characteristics of the nanogaps.

Nanogaps between electrodes patterned on silicon/silicon dioxide supports can be bridged also by DNA double strands [2.68, 69]. The device in Fig. 2.18b has a 10.4 nm long poly(G)–poly(C) DNA oligomer suspended between two nanoelectrodes. It can be fabricated patterning a 30 nm wide slit in a silicon nitride overlayer covering a silicon/silicon dioxide support by electron beam evaporation. Underetching the silicon dioxide layer leaves a silicon nitride finger, which can be sputtered with a platinum layer and chopped to leave a nanogap of 8 nm. At this point, a microdroplet of a dilute solution of DNA is deposited on the device and a bias of 5 V is applied between the two electrodes. Electrostatic forces encourage the deposition of a single DNA wire on top of the nanogap. As soon as the nanowire is in position, current starts to flow across the junction. The current/voltage signature of the electrode/DNA/electrode junction shows currents below 1 pA at low voltage biases. Under these conditions, the DNA nanowire is an insulator. Above a certain voltage threshold, however, the nanowire becomes conducting and currents up to 100 nA can flow across the junction through a single nanowire. Assuming that direct tunneling from electrode to electrode is extremely unlikely for a relatively large gap of 8 nm, the intriguing current/voltage behavior has to be a consequence of the participation of the molecular states in the electron transport process. Two possible mechanisms can be envisaged. Sequential hopping of the electrons between states localized in the DNA base pairs can allow the current flow above a certain voltage threshold. But this mechanism would presumably result in a Coulomb blockade voltage gap that is not observed experimentally. More likely, electronic states delocalized across the entire length of the DNA nanowire are producing a molecular conduction band. The off-set between the molecular conduction band and the Fermi levels of the electrodes is responsible for the insulating behavior at low biases. Above a certain voltage threshold, the molecular band and one of the Fermi levels align facilitating the passage of electrons across the junction.



Fig. 2.19 **(a)** Nanoscaled junctions can be assembled on silicon/silicon dioxide supports crossing pairs of orthogonally arranged single-wall carbon nanotubes with chromium/gold electrical contacts at their ends. **(b)** Nanotransistors can be fabricated contacting the two ends of a single-wall carbon nanotube deposited on an aluminum/aluminum oxide gate with gold sources and drain. One or two nanotube transistors can be integrated into nanoscaled NOT **(c)** and NOR **(d)** logic gates

Carbon nanotubes are extremely versatile building blocks for the assembly of nanoscaled electronic devices. They can be used to bridge nanogaps [2.70–73] and assemble nanoscaled cross junctions [2.74–76]. In Fig. 2.19a, a single-wall carbon nanotube crosses over another one in an orthogonal arrangement [2.74]. Both nanotubes have electrical contacts at their ends.

The fabrication of this device involves three main steps. First, alignment marks for the electrodes are patterned on a silicon/silicon dioxide support by electron beam lithography. Then the substrate is exposed to a dichloromethane suspension of single-wall SWNT carbon nanotubes. After washing with isopropanol, crosses of carbon nanotubes in an appropriate alignment relative to the electrode marks are identified by tapping mode atomic force microscopy. Finally chromium/gold electrodes are fabricated on top of the nanotube ends, again, by electron beam lithography. The conductance of individual nanotubes can be probed by exploiting the two electric contacts at their ends. These two-terminal measurements reveal that certain nanotubes have metallic behavior, while others are semiconducting. It follows that three distinct types of cross junctions differing in the nature of their constituent nanotubes can be identified on the silicon/silicon dioxide support. Four terminal current/voltage measurements indicate that junctions formed by two metallic nanotubes have high conductance and ohmic behavior. Similarly, high junction conductance and ohmic behavior is observed when two semiconducting nanotubes cross. The current/voltage signature of junctions formed when a metallic nanotube crosses a semiconducting one are, instead, completely different. The metallic nanotube depletes the semiconducting one at the junction region producing a nanoscaled Schottky barrier with a pronounced rectifying behavior.

Similar fabrication strategies can be exploited to assemble nanoscaled counterparts of conventional transistors. The device in Fig. 2.19b is assembled patterning an aluminum finger on a silicon/silicon dioxide substrate by electron beam lithography [2.76]. After exposure to air, an insulating aluminum oxide layer forms on the aluminum finger. Then a dichloromethane suspension of single-wall carbon nanotubes is deposited on the resulting substrate. Atomic force microscopy can be used to select carbon nanotubes with a diameter of ca. 1 nm positioned on the aluminum finger. After registering their coordinates relative to alignment markers, gold contacts can be evaporated on their ends by electron beam lithography. The final assembly is a nanoscaled three-terminal device equivalent to a conventional field effect transistor [2.19]. The two gold contacts are the source and drain terminals, while the underlying aluminum finger reproduces the function of the gate. At a source to drain bias of ca. -1.3 V, the drain current jumps from ca. 0 to ca. 50 nA when the gate voltage is lowered from -1.0 to -1.3 V. Thus moderate changes in the gate voltage vary significantly the current flowing through the nanotube-based device in analogy to a conventional enhancement mode p-type field effect transistor [2.19].

The nanoscaled transistor in Fig. 2.18a has a microscaled silicon gate that extends under the entire chip [2.62, 64]. The configuration in Fig. 2.19b, instead, has nanoscaled aluminum gates for every single carbon nanotube transistor fabricated on the same support [2.76]. It follows that multiple nanoscaled transistors can be fabricated on the same chip and operated independently following this strategy. This unique feature offers the possibility of fabricating nanoscaled digital circuits by interconnecting the terminals of independent nanotube transistors. The examples in Fig. 2.19c,d illustrate the configurations of nanoscaled NOT and NOR gates implemented using one or two nanotube transistors. In Fig. 2.19c, an off-chip bias resistor is connected to the drain terminal of a single transistor while the source is grounded. A voltage input applied to the gate modulates the nanotube conductance altering the voltage output probed at the drain terminal. In particular, a voltage input of -1.5 V lowers the nanotube resistance (26 MΩ) below that of the bias resistor (100 MΩ). As a result, the voltage output drops to 0 V. When the voltage input is raised to 0 V, the nanotube resistance increases above that of the bias resistor and the voltage output becomes -1.5 V. Thus the output of this nanoelectronic device switches from a high (0 V) and to a low (-1.5 V) level as the input shifts from a low (-1.5 V) to a high (0 V) value. The inverse relation between input and output translates into a NOT operation if a negative logic convention (low = 1, high = 0) is applied to both signals.

In Fig. 2.15d, the source terminals of two independent nanotube transistors fabricated on the same chip are connected by a gold wire and grounded [2.76]. Similarly, the two drain terminals are connected by another gold wire and contacted to an off-chip bias resistors. The gate of each nanotube can be stimulated with a voltage input and the voltage output of the device can be probed at their interconnected drain terminals. When the resistance of at least one of the two nanotubes is below that of the resistor, the output is 0 V. When both nanotubes are in a nonconducting mode, the output voltage is -1.5 V. Thus if a low voltage input -1.5 V is applied to one or both transistors, the output is high (0 V). When both voltage inputs are high (0 V), the output is low (-1.5 V). If a negative logic convention (low = 1, high = 0) is applied to all signals, the signal transduction behavior translates in to a NOR operation.

2.4 Conclusions and Outlook

Nature builds nanostructured biomolecules relying on a highly modular approach [2.1]. Small building blocks are connected by robust chemical bonds to generate long strands of repeating units. The synergism of a multitude of attractive supramolecular forces determines the three-dimensional arrangement of the resulting polymeric chains and controls the association of independent strands into single and well-defined entities. Nucleic acids and proteins are two representative classes of biomolecules assembled with subnanometer precision through the subtle interplay of covalent and noncovalent bonds starting from a relatively small pool of nucleotide and amino acid building blocks.

The power of chemical synthesis [2.2] offers the opportunity of mimicking nature's modular approach to nanostructured materials. Following established experimental protocols, small molecular building blocks can be joined together relying on the controlled formation of covalent bonds between designed functional groups. Thus artificial molecules with nanoscaled dimensions can be assembled piece by piece with high structural control. Indeed, helical, tubular, interlocked, and highly branched nanostructures have been all prepared already exploiting this general strategy and the synergism of covalent and noncovalent bonds [2.3].

The chemical construction of nanoscaled molecules from modular building blocks also offers the opportunity for engineering specific properties in the resulting assemblies. In particular, electroactive and photoactive fragments can be integrated into single molecules. The ability of these functional subunits to accept/donate electrons and photons can be exploited to design nanoscaled electronic and photonic devices. Indeed, molecules that respond to electrical and optical stimulations producing detectable outputs have been designed already [2.16]. These chemical systems can be employed to control the interplay of input and output signals at the molecular level. Their conceptual analogy with the signal transduction operated by conventional logic gates in digital circuits is evident. In fact, electroactive and photoactive molecules able to reproduce AND, NOT, and OR operations as well as simple combinational of these basic logic functions are already a reality [2.20, 21].

Most of the molecular switches for digital processing developed so far rely on bulk addressing. In general, relatively large collections of functional molecules are addressed simultaneously in solution. The realization of molecule-based devices with reduced dimensions as well as practical limitations associated with liquid phases in potential applications are encouraging a transition from the solution to the solid state. The general strategy followed so far relies on the deposition of functional molecules on the surfaces of appropriate electrodes following either the Langmuir–Blodgett methodology [2.34] or self-assembly processes [2.35]. The combination of these techniques with the nanofabrication of insulating, metallic, and semiconducting features on appropriate supports has already allowed the realization of fascinating molecule-based devices [2.30–33, 53]. The resulting assemblies integrate inorganic and organic components and, in some instances, even biomolecules to execute specific functions. They can convert optical stimulations into electrical signals. They can execute irreversible and reversible switching operations. They can sense qualitatively and quantitatively specific analytes. They can reproduce the functions of conventional rectifiers and transistors. They can be integrated within functioning nanoelectronic devices capable of simple logic operations.

The remarkable examples of molecule-based materials and devices now available demonstrate the great potential and promise for this research area. At this stage, the only limit left to the design of functional molecules is the imagination of the synthetic chemist. All sort of molecular building blocks with tailored dimensions, shapes, and properties are more or less accessible with the assistance of modern chemical synthesis. Now, the major challenges are (1) to master the operating principles of the molecule-based devices that have been and continue to be assembled and (2) to expand and improve the fabrication strategies available to incorporate molecules into reliable device architectures. As we continue to gather further insights in these directions, design criteria for a wide diversity of molecule-based devices will emerge. It is not unrealistic to foresee the evolution of an entire generation of nanoscaled devices, based on engineered molecular components, that will find applications in a variety of fields ranging from biomedical research to information technology. Perhaps nature can once again illuminate our path, teaching us not only how to synthesize nanostructured molecules but also how to use them. After all, nature is replete with examples of extremely sophisticated molecule-based devices. From tiny bacteria to higher animals, we are all a collection of molecule-based devices.

References

2.1 D. Voet, J. G. Voet: *Biochemistry* (Wiley, New York 1995)

2.2 K. C. Nicolau, E. C. Sorensen: *Classics in Total Synthesis* (VCH, Weinheim 1996)

2.3 J.-M. Lehn: *Supramolecular Chemistry: Concepts and Perspectives* (VCH, Weinheim 1995)

2.4 M. M. Harding, U. Koert, J.-M. Lehn, A. Marquis-Rigault, C. Piguet, J. Siegel: Synthesis of unsubstituted and 4,4'-substituted oligobipyridines as ligand strands for helicate self-assembly, Helv. Chim. Acta **74** (1991) 594–610

2.5 J.-M. Lehn, A. Rigault, J. Siegel, B. Harrowfield, B. Chevrier, D. Moras: Spontaneous assembly of double-stranded helicates from oligobipyridine ligands and copper(I) cations: Structure of an inorganic double helix, Proc. Natl. Acad. Sci. USA **84** (1987) 2565–2569

2.6 J.-M. Lehn, A. Rigault: Helicates: Tetra- and pentanuclear double helix complexes of Cu(I) and poly(bipyridine) strands, Angew. Chem. Int. Ed. Engl. **27** (1988) 1095–1097

2.7 J. D. Hartgerink, J. R. Granja, R. A. Milligan, M. R. Ghadiri: Self-assembling peptide nanotubes, J. Am. Chem. Soc. **118** (1996) 43–50

2.8 M. R. Ghadiri, J. R. Granja, R. A. Milligan, D. E. McRee, N. Khazanovich: Self-assembling organic nanotubes based on a cyclic peptide architecture, Nature **366** (1993) 324–327

2.9 V. Balzani, A. Credi, F. M. Raymo, J. F. Stoddart: Artificial molecular machines, Angew. Chem. Int. Ed. **39** (2000) 3348–3391

2.10 A. J. Bard, L. R. Faulkner: *Electrochemical Methods: Fundamentals and Applications* (Wiley, New York 2000)

2.11 V. Balzani (Ed.): *Electron Transfer in Chemistry* (Wiley-VCH, Weinheim 2001)

2.12 J. D. Coyle: *Principles and Applications of Photochemistry* (Wiley, New York 1988)

2.13 J. F. Stoddart (Ed.): Molecular machines, Acc. Chem. Res. **34** (2001) 409–522

2.14 P. R. Ashton, R. Ballardini, V. Balzani, A. Credi, K. R. Dress, E. Ishow, C. J. Kleverlaan, O. Kocian, J. A. Preece, N. Spencer, J. F. Stoddart, M. Venturi, S. Wenger: A photochemically driven molecular-level abacus, Chem. Eur. J. **6** (2000) 3558–3574

2.15 B. L Feringa (Ed.): Photochromism: memories and switches, Chem. Rev. **100** (2000) 1683–1890

2.16 B. L. Feringa (Ed.): *Molecular Switches* (Wiley-VCH, Weinheim 2001)

2.17 R. J. Mitchell: *Microprocessor Systems: An Introduction* (Macmillan, London 1995)

2.18 D. R. Smith: *Digital Transmission Systems* (Van Nostrand Reinhold, New York 1993)

2.19 S. Madhu: *Electronics: Circuits and Systems* (SAMS, Indianapolis 1985)

2.20 A. P. de Silva, N. D. McClenaghan, C. P. McCoy: Logic Gates. In: *Electron Transfer in Chemistry*, ed. by V. Balzani (Wiley-VCH, Weinheim 2001) pp. 156–185

2.21 F. M. Raymo: Digital processing and communication with molecular switches, Adv. Mater. **14** (2002) 401–414

2.22 A. Aviram: Molecules for memory, logic and amplification, J. Am. Chem. Soc. **110** (1988) 5687–5692

2.23 A. P. de Silva, H. Q. N. Gunaratne, C. P. McCoy: A molecular photoionic AND gate based on fluorescent signaling, Nature **364** (1993) 42–44

2.24 M. Asakawa, P. R. Ashton, V. Balzani, A. Credi, G. Mattersteig, O. A. Matthews, M. Montalti, N. Spencer, J. F. Stoddart, M. Venturi: Electrochemically induced molecular motions in pseudorotaxanes: A case of dual-mode (oxidative and reductive) dethreading, Chem. Eur. J. **3** (1997) 1992–1996

2.25 F. M. Raymo, S. Giordani: Signal processing at the molecular level, J. Am. Chem. Soc. **123** (2001) 4651–4652

2.26 F. M. Raymo, S. Giordani: Signal communication between molecular switches, Org. Lett. **3** (2001) 3475–3478

2.27 F. M. Raymo, S. Giordani: Digital communication through intermolecular fluorescence modulation, Org. Lett. **3** (2001) 1833–1836

2.28 F. M. Raymo, S. Giordani: All-optical processing with molecular switches, Proc. Natl. Acad. Sci. USA **99** (2002) 4941–4944

2.29 A. J. Bard: *Integrated Chemical Systems: A Chemical Approach to Nanotechnology* (Wiley, New York 1994)

2.30 R. M. Metzger: Electrical rectification by a molecule: The advent of unimolecular electronic devices, Acc. Chem. Res. **32** (1999) 950–957

2.31 C. Joachim, J. K. Gimzewski, A. Aviram: Electronics using hybrid-molecular and mono-molecular devices, Nature **408** (2000) 541–548

2.32 J. M. Tour: Molecular electronics. Synthesis and testing of components, Acc. Chem. Res. **33** (2000) 791–804

2.33 A. R. Pease, J. O. Jeppesen, J. F. Stoddart, Y. Luo, C. P. Collier, J. R. Heath: Switching devices based on interlocked molecules, Acc. Chem. Res. **34** (2001) 433–444

2.34 M. C. Petty: *Langmuir–Blodgett Films: An Introduction* (Cambridge Univ. Press, Cambridge 1996)

2.35 A. Ulman: *An Introduction to Ultrathin Organic Films* (Academic, Boston 1991)

2.36 C. Lee, A. J. Bard: Comparative electrochemical studies of *N*-Methyl-*N'*-hexadecyl viologen monomolecular films formed by irreversible adsorption and the Langmuir–Blodgett method, J. Electroanal. Chem. **239** (1988) 441–446

2.37 C. Lee, A. J. Bard: Cyclic voltammetry and Langmuir film isotherms of mixed monolayers of *N*-docosoyl-

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

N′-methyl viologen with arachidic acid, Chem. Phys. Lett. **170** (1990) 57–60

2.38 M. Fujihira, K. Nishiyama, H. Yamada: Photoelectrochemical responses of optically transparent electrodes modified with Langmuir–Blodgett films consisting of surfactant derivatives of electron donor, acceptor and sensitizer molecules, Thin Solid Films **132** (1985) 77–82

2.39 M. Fujihira: Photoelectric conversion with Langmuir–Blodgett films. In: *Nanostructures Based on Molecular Materials*, ed. by W. Göpel, C. Ziegler (VCH, Weinheim 1992) pp. 27–46

2.40 C. P. Collier, E. W. Wong, M. Belohradsky, F. M. Raymo, J. F. Stoddart, P. J. Kuekes, R. S. Williams, J. R. Heath: Electronically configurable molecular-based logic gates, Science **285** (1999) 391–394

2.41 E. W. Wong, C. P. Collier, M. Belohradsky, F. M. Raymo, J. F. Stoddart, J. R. Heath: Fabrication and transport properties of single-molecule-thick electrochemical junctions, J. Am. Chem. Soc. **122** (2000) 5831–5840

2.42 M. Asakawa, P. R. Ashton, V. Balzani, A. Credi, C. Hamers, G. Mattersteig, M. Montalti, A. N. Shipway, N. Spencer, J. F. Stoddart, M. S. Tolley, M. Venturi, A. J. P. White, D. J. Williams: A chemically and electrochemically switchable [2]catenane incorporating a tetrathiafulvalene unit, Angew. Chem. Int. Ed. **37** (1998) 333–337

2.43 V. Balzani, A. Credi, G. Mattersteig, O. A. Matthews, F. M. Raymo, J. F. Stoddart, M. Venturi, A. J. P. White, D. J. Williams: Switching of pseudorotaxanes and catenanes incorporating a tetrathiafulvalene unit by redox and chemical inputs, J. Org. Chem. **65** (2000) 1924–1936

2.44 M. Asakawa, M. Higuchi, G. Mattersteig, T. Nakamura, A. R. Pease, F. M. Raymo, T. Shimizu, J. F. Stoddart: Current/Voltage characteristics of monolayers of redox-switchable [2]catenanes on gold, Adv. Mater. **12** (2000) 1099–1102

2.45 C. P. Collier, G. Mattersteig, E. W. Wong, Y. Luo, K. Beverly, J. Sampaio, F. M. Raymo, J. F. Stoddart, J. R. Heath: A [2]catenane based solid-state electronically reconfigurable switch, Science **289** (2000) 1172–1175

2.46 C. P. Collier, J. O. Jeppesen, Y. Luo, J. Perkins, E. W. Wong, J. R. Heath, J. F. Stoddart: Molecular-based electronically switchable tunnel junction devices, J. Am. Chem. Soc. **123** (2001) 12632–12641

2.47 J. Chen, M. A. Reed, A. M. Rawlett, J. M. Tour: Large on-off ratios and negative differential resistance in a molecular electronic device, Science **286** (1999) 1550–1552

2.48 M. A. Reed, J. Chen, A. M. Rawlett, D. W. Price, J. M. Tour: Molecular random access memory cell, Appl. Phys. Lett. **78** (2001) 3735–3737

2.49 J. H. Schön, H. Meng, Z. Bao: Self-assembled monolayer organic field-effect transistors, Nature **413** (2001) 713–716

2.50 D. I. Gittins, D. Bethell, R. J. Nichols, D. J. Schiffrin: Redox-controlled multilayers of discrete gold particles: A novel electroactive nanomaterial, Adv. Mater. **9** (1999) 737–740

2.51 D. I. Gittins, D. Bethell, R. J. Nichols, D. J. Schiffrin: Diode-like electron transfer across nanostructured films containing a redox ligand, J. Mater. Chem. **10** (2000) 79–83

2.52 D. I. Gittins, D. Bethell, D. J. Schiffrin, R. J. Nichols: A nanometer-scale electronic switch consisting of a metal cluster and redox-addressable groups, Nature **408** (2000) 67–69

2.53 A. N. Shipway, M. Lahav, I. Willner: Nanostructured gold colloid electrodes, Adv. Mater. **12** (2000) 993–998

2.54 A. N. Shipway, M. Lahav, R. Blonder, I. Willner: Bis-bipyridinium cyclophane receptor–Au nanoparticle superstructure for electrochemical sensing applications, Chem. Mater. **11** (1999) 13–15

2.55 M. Lahav, A. N. Shipway, I. Willner, M. B. Nielsen, J. F. Stoddart: An enlarged bis-bipyridinum cyclophane–Au nanoparticle superstructure for selective electrochemical sensing applications, J. Electroanal. Chem. **482** (2000) 217–221

2.56 R. E. Gillard, F. M. Raymo, J. F. Stoddart: Controlling self-assembly, Chem. Eur. J. **3** (1997) 1933–1940

2.57 F. M. Raymo, J. F. Stoddart: From supramolecular complexes to interlocked molecular compounds, Chemtracts – Organic Chemistry **11** (1998) 491–511

2.58 M. Lahav, T. Gabriel, A. N. Shipway, I. Willner: Assembly of a Zn(II)-porphyrin-bipyridinium dyad and Au-nanoparticle superstructures on conductive surfaces, J. Am. Chem. Soc. **121** (1999) 258–259

2.59 M. Lahav, V. Heleg-Shabtai, J. Wasserman, E. Katz, I. Willner, H. Durr, Y. Hu, S. H. Bossmann: Photoelectrochemistry with integrated photosensitizer-electron acceptor Au-nanoparticle arrays, J. Am. Chem. Soc. **122** (2000) 11480–11487

2.60 G. Will, S. N. Rao, D. Fitzmaurice: Heterosupramolecular optical write-read-erase device, J. Mater. Chem. **9** (1999) 2297–2299

2.61 A. Merrins, C. Kleverlann, G. Will, S. N. Rao, F. Scandola, D. Fitzmaurice: Time-resolved optical spectroscopy of heterosupramolecular assemblies based on nanostructured TiO_2 films modified by chemisorption of covalently linked ruthenium and viologen complex components, J. Phys. Chem. B **105** (2001) 2998–3004

2.62 H. Park, J. Park, A. K. L. Lim, E. H. Anderson, A. P. Alivisatos, P. L. McEuen: Nanomechanical oscillations in a single C_{60} transistor, Nature **407** (2000) 57–60

2.63 W. Liang, M. P. Shores, M. Bockrath, J. R. Long, H. Park: Kondo resonance in a single-molecule transistor, Nature **417** (2002) 725–729

2.64 J. Park, A. N. Pasupathy, J. I. Goldsmith, C. Chang, Y. Yaish, J. R. Petta, M. Rinkoski, J. P. Sethna,

H. D. Abruna, P. L. McEuen, D. C. Ralph: Coulomb blockade and the Kondo effect in single-atom transistors, Nature **417** (2002) 722–725
2.65 C. Z. Li, H. X. He, N. J. Tao: Quantized tunneling current in the metallic nanogaps formed by electrodeposition and etching, Appl. Phys. Lett. **77** (2000) 3995–3997
2.66 H. He, J. Zhu, N. J. Tao, L. A. Nagahara, I. Amlani, R. Tsui: A conducting polymer nanojunction switch, J. Am. Chem. Soc. **123** (2001) 7730–7731
2.67 A. Bogozi, O. Lam, H. He, C. Li, N. J. Tao, L. A. Nagahara, I. Amlani, R. Tsui: Molecular adsorption onto metallic quantum wires, J. Am. Chem. Soc. **123** (2001) 4585–4590
2.68 A. Bezryadin, C. N. Lau, M. Tinkham: Quantum suppression of superconductivity in ultrathin nanowires, Nature **404** (2000) 971–974
2.69 D. Porath, A. Bezryadin, S. de Vries, C. Dekker: Direct measurement of electrical transport through DNA molecules, Nature **403** (2000) 635–638
2.70 S. J. Tans, M. H. Devoret, H. Dai, A. Thess, E. E. Smalley, L. J. Geerligs, C. Dekker: Individual single-wall carbon nanotubes as quantum wires, Nature **386** (1997) 474–477
2.71 A. F. Morpurgo, J. Kong, C. M. Marcus, H. Dai: Gate-controlled superconducting proximity effect in carbon nanotubes, Nature **286** (1999) 263–265
2.72 J. Nygård, D. H. Cobden, P. E. Lindelof: Kondo physics in carbon nanotubes, Nature **408** (2000) 342–346
2.73 W. Liang, M. Bockrath, D. Bozovic, J. H. Hafner, M. Tinkham, H. Park: Fabry–Perot interference in a nanotube electron waveguide, Nature **411** (2001) 665–669
2.74 M. S. Fuhrer, J. Nygård, L. Shih, M. Forero, Y.-G. Yoon, M. S. C. Mazzoni, H. J. Choi, J. Ihm, S. G. Louie, A. Zettl, P. L. McEuen: Crossed nanotube junctions, Science **288** (2000) 494–497
2.75 T. Rueckes, K. Kim, E. Joselevich, G. Y. Tseng, C.-L. Cheung, C. M. Lieber: Carbon nanotube-based nonvolatile random access memory for molecular computing, Science **289** (2000) 94–97
2.76 A. Bachtold, P. Hadley, T. Nakanishi, C. Dekker: Logic circuits with carbon nanotube transistors, Science **294** (2001) 1317–1320

3. Introduction to Carbon Nanotubes

Carbon nanotubes are among the amazing objects that science sometimes creates by accident, without meaning to, but that will likely revolutionize the technological landscape of the century ahead. Our society stands to be significantly influenced by carbon nanotubes, shaped by nanotube applications in every aspect, just as silicon-based technology still shapes society today. The world already dreams of space-elevators tethered by the strongest of cables, hydrogen-powered vehicles, artificial muscles, and so on – feasts that would be made possible by the emerging carbon nanotube science.

Of course, nothing is set in stone yet. We are still at the stage of possibilities and potential. The recent example of fullerenes – molecules closely related to nanotubes, whose importance was so anticipated that their discovery in 1985 brought a Nobel Prize to their finders in 1996 although few related applications have actually yet reached the market – teaches us to play the game of enthusiastic predictions with some caution. But in the case of carbon nanotubes, expectations are high. Taking again the example of electronics, the miniaturization of chips is about to reach its lowest limits. Are we going to accept that our video camera, computers, and cellular phones no longer decrease in size and increase in memory every six months? Surely not. Always going deeper, farther, smaller, higher is a characteristic unique to humankind, and which helps to explain its domination of the living world on earth. Carbon nanotubes can help us fulfill our expectation of constant technological progress as a source of better living.

In this chapter, after the structure, synthesis methods, growth mechanisms, and properties of carbon nanotubes will be described, an entire section will be devoted to nanotube-related nano-objects. Indeed, should pristine nanotubes reach any limitation in some area, their ready and close association to foreign atoms, molecules, and compounds offers the prospect of an even magnified set of properties. Finally, we will describe carbon nanotube applications supporting the idea that the future for the science and technology of carbon nanotubes looks very promising.

3.1 **Structure of Carbon Nanotubes** 40
  3.1.1 Single-Wall Nanotubes 40
  3.1.2 Multiwall Nanotubes 43

3.2 **Synthesis of Carbon Nanotubes** 45
  3.2.1 Solid Carbon Source-Based Production Techniques for Carbon Nanotubes 45
  3.2.2 Gaseous Carbon Source-Based Production Techniques for Carbon Nanotubes 52
  3.2.3 Miscellaneous Techniques 57
  3.2.4 Synthesis of Aligned Carbon Nanotubes 58

3.3 **Growth Mechanisms of Carbon Nanotubes** 59
  3.3.1 Catalyst-Free Growth 59
  3.3.2 Catalytically Activated Growth........ 60

3.4 **Properties of Carbon Nanotubes**............ 63
  3.4.1 Variability of Carbon Nanotube Properties 63
  3.4.2 General Properties 63
  3.4.3 SWNT Adsorption Properties 63
  3.4.4 Transport Properties 65
  3.4.5 Mechanical Properties.................. 67
  3.4.6 Reactivity 67

3.5 **Carbon Nanotube-Based Nano-Objects** ... 68
  3.5.1 Hetero-Nanotubes 68
  3.5.2 Hybrid Carbon Nanotubes............. 68
  3.5.3 Functionalized Nanotubes............ 71

3.6 **Applications of Carbon Nanotubes**.......... 73
  3.6.1 Current Applications 73
  3.6.2 Expected Applications Related to Adsorption 76

References 86

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Carbon nanotubes have been synthesized for a long time as products from the action of a catalyst over the gaseous species originating from the thermal decomposition of hydrocarbons (see Sect. 3.2). Some of the first evidence that the nanofilaments thus produced were actually nanotubes – i. e., exhibiting an inner cavity – can be found in the transmission electron microscope micrographs published by *Hillert* et al. in 1958 [3.1]. This was of course related to and made possible by the progress in transmission electron microscopy. It is then likely that the carbon filaments prepared by *Hughes* and *Chambers* in 1889 [3.2], reported by *Maruyama* et al. [3.3] as probably the first patent ever deposited in the field, and whose preparation method was also based on the catalytically enhanced thermal cracking of hydrocarbons, were already carbon nanotube-related morphologies. The preparation of vapor-grown carbon fibers had actually been reported as early as more than one century ago [3.4, 5]. Since then, the interest in carbon nanofilaments/nanotubes has been recurrent, though within a scientific area almost limited to the carbon material scientist community. The reader is invited to consult the review published by *Baker* et al. [3.6] regarding the early works. The worldwide enthusiasm came unexpectedly in 1991, after the catalyst-free formation of nearly perfect concentric multiwall carbon nanotubes (c-MWNTs, see Sect. 3.1) was reported [3.7] as by-products of the formation of fullerenes by the electric-arc technique. But the real breakthrough occurred two years later, when attempts in situ to fill the nanotubes with various metals (see Sect. 3.5) led to the discovery – again unexpected – of single-wall carbon nanotubes (SWNTs) simultaneously by *Iijima* et al. [3.8] and *Bethune* et al. [3.9]. Single-wall carbon nanotubes were really new nano-objects many of whose properties and behaviors are quite specific (see Sect. 3.4). They are also beautiful objects for fundamental physics as well as unique molecules for experimental chemistry, still keeping some mystery since their formation mechanisms are a subject of controversy and are still debated (see Sect. 3.3). Potential applications seem countless, although few have reached a marketable status so far (see Sect. 3.6). Consequently, about five papers a day with carbon nanotubes as the main topic are currently published by research teams from around the world, an illustration of how extraordinarily active – and highly competitive – is this field of research. It is a quite unusual situation, similar to that of fullerenes, which, by the way, are again carbon nano-objects structurally closely related to nanotubes.

This is not, however, only about scientific exaltation. Economical aspects are leading the game to a greater and greater extent. According to experts, the world market is predicted to be more than 430 M $ in 2004 and estimated to grow to several b $ before 2009. That is serious business, and it will be closely related to how scientists and engineers will be able to deal with the many challenges found on the path from the beautiful, ideal molecule to the reliable – and it is hoped, cheap – manufactured product.

3.1 Structure of Carbon Nanotubes

It is simple to imagine a single-wall carbon nanotube (SWNT). Ideally, it is enough to consider a perfect graphene sheet (a graphene being the same polyaromatic mono-atomic layer made of an hexagonal display of sp^2 hybridized carbon atoms that genuine graphite is built up with), to roll it into a cylinder (Fig. 3.1) paying attention that the hexagonal rings put in contact join coherently, then to close the tips by two caps, each cap being a hemi-fullerene with the appropriate diameter (Fig. 3.2a–c).

3.1.1 Single-Wall Nanotubes

Geometrically, there is no restriction regarding the tube diameter. But calculations have shown that collapsing the single-wall tube into a flattened two-layer ribbon is energetically more favorable than maintaining the tubular morphology beyond a diameter value of ~ 2.5 nm [3.10]. On the other hand, it intuitively comes to mind that the shorter the radius of curvature, the higher the stress and the energetic cost, although SWNTs with diameters as low as 0.4 nm have been successfully synthesized [3.11]. A suitable energetic compromise is thus reached for ~ 1.4 nm, the most frequent diameter encountered regardless of the synthesis techniques (at least those based on solid carbon source) when conditions for high SWNT yields are used. There is no such restriction for nanotube length, which only depends on limitations brought by the preparation method and the specific conditions used for the synthesis (thermal gradients, res-



Fig. 3.1 Sketch of the way to make a single-wall carbon nanotube, starting from a graphene sheet (adapted from [3.12])



Fig. 3.2a–c Sketch of three different SWNT structures as examples for **(a)** a zig-zag-type nanotube, **(b)** an armchair-type nanotube, **(c)** a helical nanotube (adapted from [3.13])

idence time, etc.). Experimental data are consistent with these statements, since SWNTs wider than 2.5 nm are scarcely reported in literature, whatever the preparation method, while SWNT length can be in the micrometer or the millimeter range. These features make single-wall carbon nanotubes a unique example of single molecules with huge aspect ratios.

Two important consequences derive from the SWNT structure as described above:

1. All carbon atoms are involved in hexagonal aromatic rings only and are therefore in equivalent position, except at the nanotube tips where $6 \times 5 = 30$ atoms at each tip are involved in pentagonal rings (considering that adjacent pentagons are unlikely) – though not more, not less, as a consequence of the Euler's rule that also governs the fullerene structure. In case SWNTs are ideally perfect, their chemical reactivity will therefore be highly favored at the tube tips, at the very location of the pentagonal rings.
2. Though carbon atoms are involved in aromatic rings, the C=C bond angles are no longer planar as they should ideally be. This means that the hybridization of carbon atoms are no longer pure sp^2 but get some percentage of the sp^3 character, in a proportion that increases as the tube radius of curvature decreases. For example, the effect is the same as for the C_{60} fullerene molecules, whose radius of curvature is 0.35 nm, and the subsequent sp^3 character proportion about 30%. On the one hand, this is supposed to make the SWNT surface (though consisting of aromatic ring faces) a bit more reactive than regular, planar graphene, relatively speaking. On the other hand, this somehow induces a variable overlapping of the bands of density of states, thereby inducing a unique versatile electronic behavior (see Sect. 3.4).

As illustrated by Fig. 3.2, there are many ways to roll a graphene into a single-wall nanotube, some of the resulting nanotubes enabling symmetry mirrors both parallel and perpendicular to the nanotube axis (such as the SWNTs from Fig. 3.2a and 3.2b), some others not (such as the SWNT from Fig. 3.2c). By correspondence with the terms used for molecules, the latter are commonly called "chiral" nanotubes. "Helical" should be preferred, however, in order to respect the definition of chirality, which makes all chiral molecules unable to be superimposed on their own image in a mirror. The various ways to roll graphene into tubes are therefore mathematically defined by the vector of helicity $\boldsymbol{C}_\mathrm{h}$, and the angle of helicity θ, as follows (referring to Fig. 3.1):

$$\boldsymbol{OA} = \boldsymbol{C}_\mathrm{h} = n\boldsymbol{a}_1 + m\boldsymbol{a}_2$$

with

$$\boldsymbol{a}_1 = \frac{a\sqrt{3}}{2}\boldsymbol{x} + \frac{a}{2}\boldsymbol{y} \quad \text{and} \quad \boldsymbol{a}_2 = \frac{a\sqrt{3}}{2}\boldsymbol{x} - \frac{a}{2}\boldsymbol{y}$$
$$\text{where} \quad a = 2.46\,\text{Å}$$

and

$$\cos\theta = \frac{2n+m}{2\sqrt{n^2+m^2+nm}}$$

where n and m are the integers of the vector $\boldsymbol{OA}$ considering the unit vectors $\boldsymbol{a}_1$ and $\boldsymbol{a}_2$.

The vector of helicity $\boldsymbol{C}_\mathrm{h}(=\boldsymbol{OA})$ is perpendicular to the tube axis, while the angle of helicity θ is taken with respect to the so-called zig-zag axis, i. e., the vector of helicity that makes nanotubes of the "zig-zag" type (see below). The diameter D of the corresponding nanotube is related to $\boldsymbol{C}_\mathrm{h}$ by the relation:

$$D = \frac{|\boldsymbol{C}_\mathrm{h}|}{\pi} = \frac{a_\mathrm{CC}\sqrt{3(n^2+m^2+nm)}}{\pi}\,,$$

where

$$\underset{\text{(graphite)}}{1.41\,\text{Å}} \le a_{\mathrm{C=C}} \le \underset{(\mathrm{C}_{60})}{1.44\,\text{Å}}\,.$$



Fig. 3.3 Image of two neighboring chiral SWNTs within a SWNT bundle as seen by high resolution scanning tunneling microscopy (by courtesy of Prof. Yazdani, University of Illinois at Urbana, USA)

The C−C bond length is actually elongated by the curvature imposed, taking the average value for the C_{60} fullerene molecule as a reasonable upper limit, and the value for flat graphenes in genuine graphite as the lower limit (corresponding to an infinite radius of curvature). Since $\boldsymbol{C}_\mathrm{h}$, θ, and D are all expressed as a function of the integers n and m, they are sufficient to define any SWNT specifically, by noting them (n, m). Obtaining the values of n and m for a given SWNT is simple by counting the number of hexagons that separate the extremities of the $\boldsymbol{C}_\mathrm{h}$ vector following the unit vector $\boldsymbol{a}_1$ first, then $\boldsymbol{a}_2$ [3.12]. In the example of Fig. 3.1, the SWNT that will be obtained by rolling the graphene so that the two shaded aromatic cycles superimpose exactly is a (4,2) chiral nanotube. Similarly, SWNTs from Fig. 3.2a to 3.2c are (9,0), (5,5), and (10,5) nanotubes respectively, thereby providing examples of zig-zag–type SWNT (with an angle of helicity $= 0°$), armchair-type SWNT (with an angle of helicity of $30°$) and a chiral SWNT, respectively. This also illustrates why the term "chiral" is sometimes inappropriate and should preferably be replaced by "helical". Armchair (n, n) nanotubes, though definitely achiral from a standpoint of symmetry, exhibit a "chiral angle" different from 0. "Zig-zag" and "armchair" qualifications for achiral nanotubes refer to the way carbon atoms are displayed at the edge of the nanotube cross section (Fig. 3.2a and 3.2b). Generally speaking, it is clear from Figs. 3.1 and 3.2a that having the vector of helicity perpendicular to any of the three overall C=C bond directions will provide zig-zag–type SWNTs, noted (n,0), while having the vector of helicity parallel to one of the three C=C bond directions will provide armchair-type SWNTs, noted (n, n). On the other hand, because of the sixfold symmetry of the graphene sheet, the angle of helicity θ for the chiral (n, m) nanotubes is such as $0 < \theta < 30°$. Figure 3.3 provides two examples of what chiral SWNTs look like, as seen by means of atomic force microscopy.

Planar graphenes in graphite have π electrons, which are satisfied by the stacking of graphenes that allows van der Waals forces to develop. Similar reasons make fullerenes gather and order into fullerite crystals and SWNTs into SWNT ropes (Fig. 3.4a). Spontaneously, SWNTs in ropes tend to arrange into an hexagonal array, which corresponds to the highest compactness achievable (Fig. 3.4b). This feature brings new periodicities



Fig. 3.4a,b High resolution transmission electron microscopy images of a SWNT rope **(a)** longitudinal view. At the top of the image an isolated single SWNT also appears. **(b)** cross section view (from [3.14])

with respect to graphite or turbostratic polyaromatic carbon crystals. Turbostatic structure corresponds to graphenes which are stacked with random rotations or translations instead of being piled up following sequential ABAB positions, as in graphite structure. This implies that no lattice atom plane exists anymore other than the graphene planes themselves (corresponding to the (001) atom plane family). These new periodicities make diffraction patterns specific and quite different from that of other sp^2-carbon-based crystals, although hk reflections, which account for the hexagonal symmetry of graphene plane, are still present. On the other hand, $00l$ reflections, which account for the stacking sequence of graphenes in regular, "multilayered" polyaromatic crystals that does not exist in SWNT ropes, are absent. Such a hexagonal packing of SWNTs within the ropes requires that SWNTs exhibit similar diameters, which is the common case for SWNTs prepared by the electric arc or the laser vaporization processes. SWNTs prepared these ways are actually about 1.35 nm wide (diameter value for a (10,10) tube, among others), for reasons still unclear but related to the growth mechanisms specific to the conditions provided by these techniques (see Sect. 3.3).

3.1.2 Multiwall Nanotubes

Building multiwall carbon nanotubes is a little bit more complex, since it has to deal with the various ways graphenes can be displayed and mutually arranged within a filament morphology. Considering the usual textural versatility of polyaromatic solids, a similar versatility can be expected. Likewise, diffraction patterns no longer differentiate from that of anisotropic polyaromatic solids. The easiest MWNT to imagine is the concentric type (c-MWNT), in which SWNTs with regularly increasing diameters are coaxially displayed according to a Russian-doll model into a multiwall nanotube (Fig. 3.5). Such nanotubes are generally formed either by the electric-arc technique (without need of any catalyst) or by catalyst-enhanced thermal cracking of gaseous hydrocarbons or CO disproportionation (see Sect. 3.2). The number of walls (or number of coaxial tubes) can be anything, starting from two, with no upper limit. The intertube distance is approximately that of the intergraphene distance in turbostratic, polyaromatic solids, i. e. 0.34 nm (as opposed to 0.335 nm in genuine graphite), since the increasing radius of curvature imposed on the concentric graphenes prevents the carbon atoms from being displayed as in graphite, i. e., each of the carbon atoms from a graphene facing alternatively either a ring center or a carbon atom from the neighboring graphene. But two cases allow such a nanotube to reach – totally or partially – the 3-D crystal periodicity of graphite. One is to consider a high number of concentric graphenes, i. e. concentric graphenes with long radius of curvature. In that case, the shift of the relative positions of carbon atoms from superimposed graphenes is so small with respect to that in graphite that some commensurability is possible. It may result in MWNTs with the association of both structures, i. e. turbostratic in the core and graphitic in the outer part [3.15]. The other case occurs for c-MWNTs exhibiting faceted morphologies, originating either from the synthesis process or more likely from



Fig. 3.5 High resolution transmission electron microscopy image (longitudinal view) of a concentric multiwall carbon nanotube (c-MWNT) prepared by electric arc. In *insert*, sketch of the Russian-doll-like display of graphenes

subsequent heat-treatments at high temperatures (e.g., 2,500 °C) in inert atmospheres. Obviously, facets allow graphenes to get back a flat arrangement of atoms – except at the junction between neighboring facets – in which the specific stacking sequence of graphite can develop.

Another frequent inner texture for multiwall carbon nanotubes is the so-called herringbone texture (h-MWNTs), in which graphenes make an angle with respect to the nanotube axis (Fig. 3.6). The angle value varies upon the processing conditions (e.g., the catalyst morphology or the atmosphere composition), from 0 (in which case the texture turns into that of a c-MWNT) to 90° (in that case, the filament is no longer a tube, see below), and the inner diameter varies so that the tubular feature can be lost [3.19], justifying that the latter can be called nanofibers rather than nanotubes. h-MWNTs are exclusively obtained by processes involving catalysts, generally catalyst-enhanced thermal cracking of hydrocarbons or CO disproportionation.



Fig. 3.6a,b One of the earliest high resolution transmission electron microscopy image of a herringbone (and bamboo) multi-wall nanotube (bh-MWNT, longitudinal view) prepared by CO disproportionation on Fe-Co catalyst. **(a)** as-grown. The nanotube surface is made of free graphene edges. **(b)** after 2,900 °C heat-treatment. Both the herringbone and the bamboo textures have become obvious. Graphene edges from the surface have buckled with neighbors (*arrow*), closing the access to the intergraphene spacing (adapted from [3.16])

One unresolved question is whether the herringbone texture, which actually describes the texture projection rather than the overall three-dimensional texture, originates from the scroll-like spiral arrangement of a single graphene ribbon or from the stacking of independent truncated-cone-like graphenes. Although the former is more likely for energetic reasons since providing a minimal and constant amount of transitorily unsatisfied bonds during the nanotube growth (similar to the well-known growth mechanism from a screw dislocation), the question is still debated.

Another common feature is the occurrence, at a variable frequency, of a limited amount of graphenes oriented perpendicular to the nanotube axis, thus forming the so-called "bamboo" texture. It cannot be a texture by its own but affects in a variable extent either c-MWNT (bc-MWNT) or h-MWNT (bh-MWNT) textures (Figs. 3.6 and 3.7). The question may be addressed whether such filaments, though hollowed, should still be called nanotubes, since the inner cavity is no longer opened all along the filament as it is for a genuine tube. They therefore are sometimes referred as "nanofibers" in literature.

Nanofilaments that definitely cannot be called nanotubes are those built from graphenes oriented perpendicular to the filament axis and stacked as piled-up plates. Although they actually correspond to h-MWNTs with the graphene/MWNT axis angle = 90°, the occurrence of inner cavity is no longer possible, and such filaments are therefore most often referred to as "platelet-nanofibers" in literature [3.19].



Fig. 3.7a,b Transmission electron microscopy images from bamboo-multi-wall nanotubes (longitudinal views). **(a)** low magnification of a bamboo-herringbone multi-wall nanotube (bh-MWNT) showing the nearly periodic feature of the texture, which is very frequent. (from [3.17]); **(b)** high resolution image of a bamboo-concentric multi-wall nanotube (bc-MWNT) (modified from [3.18])

As opposed to SWNTs, whose aspect ratio is so high that acceding the tube tips is almost impossible, aspect ratio for MWNTs (and carbon nanofibers) are generally lower and often allow one to image tube ends by transmission electron microscopy. Except for c-MWNTs from electric arc (see Fig. 3.5) that grow following a catalyst-free process, nanotube tips are frequently found associated with the catalyst crystal from which they have been formed.

MWNT properties (see Sect. 3.4) will obviously depend on the perfection and orientation of graphenes in the tube more than any other feature (e.g., the respective spiral angle of the constituting nanotubes for c-MWNTs has little importance). Graphene orientation is a matter of texture, as described above. Graphene perfection is a matter of nanotexture, which is commonly used to describe other polyaromatic carbon materials, and which is quantified by several parameters preferably obtained from high resolution transmission electron microscopy (Fig. 3.8). Both texture and nanotexture depend on the processing conditions. While the texture type is a permanent, intrinsic feature only able to go toward complete alteration upon severe degradation treatments (e.g., oxidation), however, nanotexture can be improved by subsequent thermal treatments at high temperatures (e.g., > 2,000 °C) or, reversibly, possibly degraded by chemical treatments (e.g., slight oxidation conditions).



Fig. 3.8 Sketch explaining the various parameters obtained from high resolution (lattice fringe mode) transmission electron microscopy for quantifying nanotexture: L_1 is the average length of perfect (distortion-free) graphenes of coherent areas; N is the number of piled-up graphenes in the coherent (distortion-free) areas; L_2 is the average length of continuous though distorted graphenes within graphene stacks; β is the average distortion angle. L_1 and N are more or less related to L_a and L_c obtained from X-ray diffraction

3.2 Synthesis of Carbon Nanotubes

Producing carbon nanotubes so that the currently planned applications become marketable requires solving some problems that are more or less restrictive depending on the cases. One example is to specifically control the configuration (chirality), the purity, or the structural quality of SWNTs, with the production capacity adapted to the application. One condition would be to understand perfectly the mechanism of nanotube nucleation and growth, which remains the object of a lot of controversy in spite of an intense, worldwide experimental effort. This problem is partly explained by the lack of knowledge regarding several parameters controlling the synthesis conditions. For instance, neither the temperatures of nanotube condensation and formation nor the manner in which they are influenced by the synthesis parameters are known. Equally often unknown is the exact and accurate role of the catalysts in nanotube growth. Given the large number of experimental parameters and considering the large range of conditions that the several synthesis techniques correspond to, it is quite legitimate to think of more than one mechanism intervening in the nanotube formation.

3.2.1 Solid Carbon Source-Based Production Techniques for Carbon Nanotubes

Among the different SWNT production techniques, the three processes (laser ablation, solar energy, and electric arc) presented in this section have at least two common points: a high temperature ($1,000\,\mathrm{K} < T < 6,000\,\mathrm{K}$) medium and the fact that the carbon source originates from the erosion of solid graphite. In spite of these common points, both the morphologies of the carbon nanostructures and the SWNT yields can differ notably with respect to the experimental conditions.

Before being utilized for carbon nanotube synthesis, these techniques permitted the production of fullerenes. Laser vaporization of graphite was actually the very first method to demonstrate the existence of fullerenes, including the most popular one (because the most stable and therefore the most abundant), C_{60} [3.20]. On the other hand, the electric arc technique was (and still is) the first method to produce fullerenes in relatively large quantities [3.21]. As opposed to the fullerene formation, which requires the presence of carbon atoms in high temperature media and the absence of oxygen, the utilization of these techniques for the synthesis of nanotubes requires an additional condition, i. e. the presence of catalysts in one of the electrode or the target.

In case of these synthesis techniques requiring relatively high temperatures to sublime graphite, the different mechanisms such as the carbon molecule dissociation and the atom recombination processes take place at different time scales, from nanosecond to microsecond and even millisecond. The formation of nanotubes and other graphene-based products appears afterward with a relatively long delay.

The methods of laser ablation, solar energy, and electric arc are based on an essential mechanism, i. e. the energy transfer resulting from the interaction between either the target material and an external radiation (laser beam or radiation emanating from solar energy) or the electrode and the plasma (in case of electric arc). This interaction is at the origin of the target or anode erosion leading to the formation of a plasma, i. e. an electrically neutral ionized gas, composed of neutral atoms, charged particles (molecules and ionized species), and electrons. The ionization degree of this plasma, defined by the ratio $(n_e/n_e + n_o)$, where n_e and n_o are the density of electrons and that of neutral atoms respectively, highlights the importance of energy transfer between the plasma and the material. The characteristics of this plasma and notably the fields of temperature and of concentration of the various species present in the plasma thereby depend not only on the nature and composition of the target or that of the electrode but also on the energy transferred.

One of the advantages of these different synthesis techniques is the possibility of varying a large number of parameters, which allow the composition of the high temperature medium to be modified and, consequently, the most relevant parameters to be determined, in order to define the optimal conditions for the control of carbon nanotube formation. But a major drawback of these techniques – as for any other technique for the production of SWNTs – is that SWNTs never come pure, i. e. they are associated with other carbon phases and catalyst remnants. Although purification processes are proposed in literature and by some commercial companies to rid these undesirable phases, they are all based on oxidation (e.g. acidic) processes that are likely to affect deeply the SWNT structure [3.14]. Subsequent thermal treatments at ∼ 1,200 °C under inert atmosphere, however, succeed somewhat in recovering the former structure quality [3.24].

Laser Ablation

After the first laser was built in 1960, physicists immediately made use of it as a means of concentrating a large quantity of energy inside a very small volume within a relatively short time. The consequences of this energy input naturally depends on the characteristics of the device employed. During the interaction between the laser beam and the material, numerous phenomena superimpose and/or follow each other within the time range, each of these processes being sensitive to such different parameters as the laser beam characteristics, the incoming power density (also termed "fluence"), the nature of the target, and the environment surrounding it. For instance, the solid target can merely heat up, or melt, or vaporize depending on the power provided.

While this technique was used successfully to synthesize fullerene-related structures for the very first time [3.20], the synthesis of SWNTs by laser ablation came only ten years later [3.22].

Laser Ablation – Experimental Devices

Two types of laser devices are utilized nowadays for carbon nanotube production: lasers operating in pulsed mode on the one hand and lasers operating in continuous mode on the other hand, the latter generally providing a smaller influence.

An example of the layout indicating the principle of a laser ablation device is given in Fig. 3.9. A graphite pellet containing the catalyst is put in the middle of an inert gas-filled quartz tube placed in an oven maintained at a temperature of 1,200 °C [3.22, 23]. The energy of the laser beam focused on the pellet permits it to vaporize and sublime the graphite by uniformly bombarding its surface. The carbon species swept by a flow of neutral gas are thereafter deposited as soot in different regions: on the conical water-cooled copper collector, on the quartz tube walls, and on the backside of the pellet.



Fig. 3.9 Sketch of an early laser vaporization apparatus (adapted from [3.22, 23])

Various improvements have been made to this device in order to increase the production efficiency. For example, *Thess* et al. [3.25] employed a second pulsed laser that follows the initial impulsion but at a different frequency in order to ensure a more complete and efficient irradiation of the pellet. This second impulsion has the role of vaporizing the coarse aggregates issued from the first ablation and thereby making them participate in the active carbon feedstock involved in the nanotube growth. Other modifications were brought by *Rinzler* et al. [3.24], who inserted a second quartz tube of a smaller diameter coaxially disposed inside to the first one. This second tube has the role of reducing the vaporization zone and thereby permitting an increase in the quantity of sublimed carbon. They also arranged to place the graphite pellet on a revolving system so that the laser beam uniformly scans its whole surface.

Other groups have realized that, as far as the target contains both the catalyst and the graphite, the latter evaporates in priority and the pellet surface becomes more and more metal rich, resulting in a decrease of the efficiency in nanotube formation in the course of the process. To solve this problem, *Yudasaka* et al. [3.27] utilized two pellets facing each other, one entirely made from the graphite powder and the other from an alloy of transition metals (catalysts), and irradiated simultaneously.

A sketch of a synthesis reactor based on the vaporization of a target at a fixed temperature by a continuous CO_2 laser beam ($\lambda = 10.6\,\mu m$) is shown in Fig. 3.10 [3.26]. The power can be varied from 100 W to 1,600 W. The temperature of the target is measured with an optical pyrometer, and these measurements are used to regulate the laser power to maintain a constant vaporization temperature. The gas, heated by the contact with the target, acts as a local furnace and creates an extended hot zone, making an external furnace unnecessary. The gas is extracted through a silica pipe, and the solid products formed are carried away by the gas flow through the pipe and then collected on a filter. The synthesis yield is controlled by three parameters: the cooling rate of the medium where the active, secondary catalyst particles are formed, the residence time, and the temperature (in the 1,000–2,100 K range) at which SWNTs nucleate and grow [3.28].

But devices equipped with facilities to gather in situ data such as the target temperature are few and, generally speaking, among the numerous parameters of the laser ablation synthesis technique. The most studied are the nature of the target, the nature and concentration of the catalysts, the nature of the neutral gas flow, and the temperature of the outer oven (when any).



Fig. 3.10 Sketch of a synthesis reactor with a continuous CO_2 laser device (adapted from [3.26])

Laser Ablation – Results

In the absence of catalysts in the target, the soot collected mainly contains multiwall nanotubes (c-MWNTs). Their lengths can reach 300 nm. Their quantity and structure quality are dependent on the oven temperature. The best quality is obtained for an oven temperature set at 1,200 °C. At lower oven temperatures, the structure quality decreases, and the nanotubes start presenting many defects [3.23]. As soon as small quantities (few percents or less) of transition metals (Ni, Co) playing the role of catalysts are incorporated into the graphite pellet, products yielded undergo significant modifications, and SWNTs are formed instead of MWNTs. The yield of SWNTs strongly depends on the type of metal catalyst used and is seen to increase with furnace temperature, among other factors. The SWNTs have remarkably uniform diameter and they self-organize into rope-like crystallites 5–20 nm in diameter and tens to hundreds of micrometers in length (Fig. 3.11). The ends of all SWNTs appear to be perfectly closed with hemispherical end caps showing no evidence of any as-



Fig. 3.11 Low magnification TEM images of a typical raw SWNT material obtained from the laser vaporization technique. Fibrous morphologies are SWNT bundles, and dark particles are catalyst remnants. Raw SWNT materials from electric arc exhibit a similar aspect (from [3.14])

sociated metal catalyst particle, although, as pointed out in Sect. 3.1, finding the two tips of a SWNT is rather challenging, considering the huge aspect ratio of the nanotube and their entanglement. Another feature of SWNTs produced with this technique is that they are supposedly "cleaner" than those produced employing other techniques, i. e., associated with a lower amount of an amorphous carbon phase, either coating the SWNTs or gathered into nano-particles. Such an advantage, however, stands only for synthesis conditions specifically set to ensure high quality SWNTs. It can no longer be true when conditions are such that high yields are preferred, and SWNTs from electric arc may appear cleaner than SWNTs from laser vaporization [3.14].

The laser vaporization technique is one of the three methods currently used to prepare SWNTs as commercial products. SWNTs prepared that way were first marketed by Carbon Nanotechnologies Inc. (Texas, USA), with prices as high as $ 1,000/g (raw materials) until December 2002. As a probable consequence of the impossibility to lower the amount of impurities in the raw materials, they have recently decided to focus on fabricating SWNTs by the HiPCo technique (see Sect. 3.2.2). Though laser-based method are generally considered not competitive in the long term for the low-cost production of SWNTs compared to CCVD-based methods (see Sect. 3.2.2), prediction of prices as low as $ 0.03 per gram of raw high concentration SWNT soot are expected in the near future (Acolt S.A., Switzerland).

Electric-Arc Method

Electric arcs between carbon electrodes have been studied as light sources and radiation standards for a very long time. Lately they have received renewed attention for their use in producing new fullerenes-related molecular carbon nanostructures such as genuine fullerenes or nanotubes. This technique was first brought to light by *Krätschmer* et al. [3.21] who utilized it to achieve the production of fullerenes in macroscopic quantities. In the course of investigating the other carbon nanostructures formed along with the fullerenes and more particularly the solid carbon deposit forming onto the cathode, Iijima [3.7] discovered the catalyst-free formation of perfect c-MWNT-type carbon nanotubes. Then, as mentioned in the introduction of this chapter, the catalyst-promoted formation of SWNTs was incidentally discovered after some amounts of transition metals were introduced into the anode in an attempt to fill the c-MWNTs with metals while they grow [3.8, 9]. Since then, a lot of work has been carried out by many groups using this technique to understand the mechanisms of nanotube growth as well as the role played by the catalysts (when any) for the synthesis of MWNTs and/or SWNTs [3.29–41].

Electric-Art Method – Experimental Devices

The principle of this technique is to vaporize carbon in the presence of catalysts (iron, nickel, cobalt, yttrium, boron, gadolinium, and so forth) under reduced atmosphere of inert gas (argon or helium). After the triggering of the arc between two electrodes, a plasma is formed consisting of the mixture of carbon vapor, the rare gas (helium or argon), and the vapors of catalysts. The vaporization is the consequence of the energy transfer from the arc to the anode made of graphite doped with catalysts. The anode erosion rate is more or less important depending on the power of the arc and also on the other experimental conditions. It is noteworthy that a high anode erosion does not necessarily lead to a high carbon nanotube production.

An example of a reactor layout is shown in Fig. 3.12. It consists of a cylinder of about 30 cm in diameter and about 1 m in height, equipped with diametrically opposed sapphire windows located so that they face the plasma zone in view of observing the arc. The reactor possesses two valves, one for carrying out the primary evacuation (0.1 Pa) of the chamber, the other permitting it to fill with a rare gas up to the desired working pressure.

Contrary to the solar energy technique, SWNTs are deposited (provided appropriate catalysts are used) in



Fig. 3.12 Sketch of an electric arc reactor

different regions of the reactor: (1) the collaret, which forms around the cathode; (2) the web-like deposits found above the cathode; (3) the soot deposited all around the reactor walls and bottom. On the other hand, MWNTs are formed embedded in a hard deposit adherent to the cathode, whenever catalysts are used or not. The cathode deposits formed under the cathode. The formation of collaret and web is not systematic and depends on the experimental conditions as indicated in Table 3.1, as opposed to cathode deposit and soot that are systematically found.

Two graphite rods of few millimeters in diameter constitute the electrodes between which a potential difference is applied. The dimensions of these electrodes vary according to the authors. In certain cases, the cathode has a greater diameter than the anode in order to facilitate their alignment [3.32, 42]. Other authors utilize electrodes of the same diameter [3.41]. The whole device can be designed horizontally [3.33, 41] or vertically [3.34, 36–38]. The advantage of the latter is the symmetry brought by the verticality with respect to gravity, which facilitates computer modeling (regarding convection flows, for instance).

Two types of anodes can be utilized as soon as catalysts need to be introduced: (1) graphite anodes in which a coaxial hole is drilled several centimeters in length and in which catalyst and graphite powders are mixed; (2) graphite anodes in which the catalysts are homogeneously dispersed [3.43]. The former are by far the most popular, due to their ease of fabrication.

The optimization of the process regarding the nanotube yield and quality is attempted by studying the role of various parameters such as the type of doped anode (homogeneous or heterogeneous catalyst dispersion), the nature as well as the concentration of catalysts, the nature of the plasmagenic gas, the buffer gas pressure, the arc current intensity, and the distance between electrodes. Investigating the result of varying these parameters on the type and amount of carbon nanostructures formed is, of course, the preliminary work that has been done. Though electric arc reactors equipped with the related facilities are few (see Fig. 3.12), investigating the missing link, i. e. the effect of varying the parameters on the plasma characteristics (fields of concentration species and temperature), is likely to provide a more comprehensive understanding of the phenomena involved in nanotube formation. This has been recently developed by atomic and molecular optical emission spectroscopy [3.34, 36–39, 41].

Finally, mention has to be made of attempts to make the electric arc within liquid media such as liquid nitrogen [3.44] or water [3.45, 46], the goal being easier processing since they do not require pumping devices or a closed volume and therefore are likely to allow continuous synthesis. This adaptation has not, however, reached the state of mass production.

Electric-Arc Method – Results

In view of the numerous results obtained with this electric-arc technique, it appears clearly that both the nanotube morphology and the nanotube production efficiency strongly depend on the experimental conditions and, in particular, on the nature of the catalysts. It is worth noting that the products obtained do not consist solely in carbon nanotubes but also in nontubular forms of carbon such as nanoparticles, fullerene-like structures including C_{60}, poorly organized polyaromatic carbons, nearly amorphous nanofibers, multiwall shells, single-wall nanocapsules, and amorphous carbon as reported in Table 3.1 [3.35, 37, 38]. In addition, catalyst remnants are found all over the place, i. e. in the soot, collaret, web, and cathode deposit in various concentration. Generally, at pressure value of about 600 mbar of helium, for 80 A arc current and 1 mm electrode gap, the use of Ni/Y as coupled catalysts favors more particularly the synthesis of SWNTs [3.8, 33, 47]. For such conditions providing high SWNT yields, SWNT concentrations are higher in the collaret (in the range of 50–70 %), then in the web (∼ 50% or less), then in the soot. On the

Table 3.1 Different carbon morphologies obtained by changing the type of anode, the type of catalysts, and pressure value, in a series of arc-discharge experiments (electrode gap = 1 mm)

Catalyst (atom%) **Arc conditions**	**0.6Ni + 0.6Co (homogeneous anode)** $P \sim 60$ **kPa** $I \sim 80$ **A**	**0.6Ni + 0.6Co (homogeneous anode)** $P \sim 40$ **kPa** $I \sim 80$ **A**	**0.5Ni + 0.5Co** $P \sim 60$ **kPa** $I \sim 80$ **A**	**4.2Ni + 1Y** $P \sim 60$ **kPa** $I \sim 80$ **A**
Soot	• **MWNT** + **MWS** + **POPAC** or **Cn** ± catalysts $\phi \sim 3-35$ nm • NANF + catalysts • AC particles + catalysts • [*DWNT*], [*SWNT*], ropes or isolated, + POPAC	• **POPAC** and **AC** particles + **catalysts** $\phi \sim 2-20$ nm • NANF + catalysts $\phi \sim 5-20$ nm + MWS • [*SWNT*] $\phi \sim 1-1.4$ nm, distorted or damaged, isolated or ropes + Cn	• **AC** and POPAC particles + catalysts $\phi \sim 3-35$ nm • **NANF** + catalysts $\phi \sim 4-15$ nm • [*SWNT*] $\phi \sim 1.2$ nm, isolated or ropes	• **POPAC** and **AC** + particles + catalysts $\phi \leq 30$ nm • SWNT $\phi \sim 1.4$ nm, clean + Cn, short with tips, [*damaged*], isolated or ropes $\phi \leq 25$ nm • [*SWNC*] particles
Web	• [*MWNT*], **DWNT**, $\phi\, 2.7 - \mathbf{4} - 5.7$ nm SWNT $\phi\, 1.2-1.8$ nm, isolated or **ropes** $\phi < 15$ nm, + POPAC ± **Cn** • AC particles + catalysts $\phi \sim 3-40$ nm + MWS • [*NANF*]	None	None	• **SWNT**, $\phi \sim 1.4$ nm, isolated or **ropes** $\phi \leq 20$ nm, + **AC** • POPAC and AC particles + catalysts $\phi \sim 3 - \mathbf{10} - 40$ nm + MWS
Collaret	• **POPAC** and **SWNC** particles • Catalysts $\phi \sim 3-250$ nm, $<$ **50** nm + MWS • SWNT $\phi\, 1-1.2$ nm, [*opened*], **distorted**, isolated or **ropes** $\phi < 15$ nm, + **Cn** • [*AC*] particles	• **AC** and **POPAC** particles + catalysts $\phi \sim 3-25$ nm • SWNT $\phi \sim 1-1.4$ nm clean + Cn, [*isolated*] or ropes $\phi < 25$ nm • Catalysts $\phi \sim 5-50$ nm + MWS, • [SWNC]	• **Catalysts** $\phi \sim 3-170$ nm + MWS • AC or POPAC particles + **catalysts** $\phi \sim 3-50$ nm • SWNT $\phi \sim 1.4$ nm clean + Cn isolated or ropes $\phi < 20$ nm	• **SWNT** $\phi \sim 1.4-2.5$ nm, clean + Cn, [*damaged*], isolated or **ropes** $\phi < 30$ nm • POPAC or AC particles + catalysts $\phi \sim 3-30$ nm • [*MWS*] + catalysts or catalyst-free.
Cathode deposit	• **POPAC** and SWNC particles • **Catalysts** $\phi \sim 5-300$ nm MWS • MWNT $\phi < 50$ nm • [*SWNT*] $\phi \sim 1.6$ nm clean + Cn, isolated or ropes	• **POPAC** and **SWNC** particles + Cn • Catalysts $\phi \sim 20-100$ nm + MWS	• **MWS**, catalyst-free • **MWNT** $\phi < 35$ nm • POPAC and PSWNC particles • [*SWNT*], isolated or ropes • [*Catalysts*] $\phi \sim 3-30$ nm	•**SWNT** $\phi \sim 1.4-4.1$ nm, clean + **Cn**, short with tips, isolated or ropes $\phi \leq 20$ nm. • **POPAC** or **AC** particles + catalysts $\phi \sim 3-30$ nm • MWS + catalysts $\phi < 40$ nm or catalyst-free • [*MWNT*]

Abundant – Present – [*Rare*]

Glossary: AC: amorphous carbon; POPAC: poorly organised polyaromatic carbon; Cn: fullerene-like structure, including C_{60}; NANF: nearly amorphous nanofiber; MWS: multiwall shell; SWNT: single-wall nanotube; DWNT: double-wall nanotube, MWNT: multiwall nanotube; SWNC: single-wall nanocapsule.

other hand, c-MWNTs are found in the cathode deposit. SWNT lengths are micrometric and, typically, outer diameters range around 1.4 nm. Taking the latter conditions as a reference experiment (Table 3.1, column 4), Table 3.1 illustrates the consequence of changing the parameters. For instance (Table 3.1, column 3), using Ni/Co instead of Ni/Y as catalysts prevents the formation of SWNTs. But when the Ni/Co catalysts are homogeneously dispersed in the anode (Table 3.1, column 1), the formation of nanotubes is promoted again, but MWNTs with two or three walls prevail over SWNTs, among which DWNTs (double-wall nanotubes) make a majority. But it is enough to decrease the ambient pressure from 60 to 40 kPa (Table 3.1, column 2) for getting back to conditions where the nanotube formation is impeached.

Recent works have attempted to replace graphite powder (sp^2 hybridized carbon) by diamond powder (sp^3 hybridized carbon) to mix with the catalyst powder and fill hollowed-type graphite anodes. The result was an unexpected but quite significant increase (up to +230%) in the SWNT yield [3.39,40]. Such experiments reveal, as for the comparison between the results from using homogeneous instead of heterogeneous anodes that the physical phenomena (charge and heat transfers) that occurred in the anode during the arc are of utmost importance, which was neglected until now.

It is clear that while the use of rare earth element (such as Y) as a single catalyst does not provide the conditions to grow SWNTs, associating it with a transition metal (such as Ni/Y) seems to correspond to the most appropriate combinations, leading to the highest SWNT yields [3.42]. On the other hand, using a single rare earth element may lead to unexpected results, such as the anticipated closure of graphene edges from a c-MWNT wall with the neighboring graphene edges from the same wall side, leading to the preferred formation of telescope-like and open c-MWNTs able to contain nested Gd crystals [3.36, 38]. Such a need for bimetallic catalysts has just begun to be understood as a possible requirement to promote the transitory formation of nickel particles coated with yttrium carbide, whose lattice constants are somewhat commensurable with that of graphenes [3.48].

Figure 3.13 illustrates the kind of information provided by the analysis of the plasma by means of emission spectroscopy, i. e. radial temperature (Fig. 3.13a) or C_2 species concentration (Fig. 3.13b) profiles in the plasma. A common feature is that a huge vertical gradient (∼ 500 K/mm) rapidly establishes (at ∼ 0.5 mm from the center in the radial direction) from the bottom to the top of the plasma, as a probable consequence of convection phenomena (Fig. 3.13a). The zone of actual SWNT formation is beyond the limit of the volume analyzable in the radial direction, corresponding to colder areas. The C_2 concentration increases dramatically from the anode to the cathode and decreases dramatically in the radial direction (Fig. 3.13b). This demonstrates that C_2 moieties are secondary products resulting from the recombination of primary species formed from the anode. It also suggests that C_2 moieties may be the building blocks for MWNTs (formed at the cathode) but not for SWNTs [3.38, 40].



Fig. 3.13a,b Typical temperature **(a)** and C_2 concentration **(b)** profiles in the plasma at the anode surface (*square*), at the plasma center (*dot*), and at the cathode surface (*triangle*) for "standard" conditions (see text). Gradients are similar whatever the catalyst, although absolute value may vary

Although many aspects of it still need to be understood, the electric-arc method is one of the three methods currently used to produce SWNTs as commercial products. At the French company Nanoledge S.A. (Montpellier, France), for instance, current production (for 2003) reaches $\sim 20\,\mathrm{kg/year}$ (raw SWNTs, i. e. not purified), with a marketed price of $\sim 90\,\mathrm{Euros/g}$, which is much cheaper than any other production method so far. A decrease to $2-5\,\mathrm{Euros/g}$ is expected for sometime before 2007, with a SWNT production capacity of $4-5\,\mathrm{tons/year}$. Amazingly, raw SWNTs from electric arc proposed by Bucky USA (Texas, USA) are still proposed at a marketed price of \$ 1,000/g.

Solar Furnace

Solar furnace devices were originally utilized by several groups to produce fullerenes [3.49–51]. *Heben* et al. [3.52] and *Laplaze* et al. [3.53] later modified their former devices in order to use them for carbon nanotube production. This modification consisted mainly in using more powerful ovens [3.54, 55].

Solar Furnace – Experimental Devices

The principle of this technique is again based on the sublimation in an inert gas of a mixture of graphite powder and catalysts formerly placed in a crucible. An example of such a device is shown in Fig. 3.14. The solar rays are collected by a plain mirror and reflected toward a parabolic mirror that focuses them directly onto a graphite pellet under controlled atmosphere. The high temperature of about $4{,}000\,\mathrm{K}$ permits both the carbon and the catalysts to vaporize. The vapors are then dragged by the neutral gas and condense onto the cold walls of the thermal screen. The reactor consists of a brass support cooled by water circulation, on which Pyrex® chambers with various shapes can be fixed (Fig. 3.14b). This support contains a watertight passage permitting the introduction of the neutral gas and a copper rod on which the target is mounted. The target is surrounded by a graphite tube that plays both the role of a thermal screen to reduce radiation losses (very important in the case of graphite) and the role of a duct to lead carbon vapors to a filter in order to avoid soot deposits on the Pyrex® chamber wall. A graphite crucible filled with powdered graphite (for fullerene synthesis) or a mixture of graphite and catalysts (for nanotube synthesis) is utilized in order to reduce the conduction losses.

These studies primarily investigated the target composition, the type and concentration of catalysts, the flow-rate, the composition and pressure of the plasmagenic gas inside the chamber, and the oven power. The objectives are similar to that of works carried out with the other solid-carbon-source-based processes. When possible, specific in situ diagnostics (pyrometry, optical emission spectroscopy, etc.) are also performed in order to understand better the role of the various parameters (temperature measurements at the crucible surface, along the graphite tube acting as thermal screen, C_2 radical concentration in the immediate vicinity of the crucible).

Solar Furnace – Results

Some results obtained by different groups concerning the influence of the catalysts can be summarized as follows. With Ni/Co and at low pressure, the sample collected contains mainly MWNTs with bamboo texture, carbon shells, and some bundles of SWNTs [3.54]. At higher pressures, only bundles of SWNTs are obtained with fewer carbon shells. With Ni/Y and at a high pressure, relatively long bundles of SWNTs are observed. With Co, SWNT bundles are obtained in the soot with SWNT diameters ranging from 1 to 2 nm. Laplaze et al. [3.54] observed very few nanotubes but a large quantity of carbon shells.

In order to proceed to a large-scale synthesis of single-wall carbon nanotubes, which is still a challenge for chemical engineers, *Flamant* et al. [3.56] recently demonstrated that solar energy–based synthesis is a versatile method to obtain SWNTs and can be scaled from $0.1-0.5\,\mathrm{g/h}$ to $10\,\mathrm{g/h}$ and then to $100\,\mathrm{g/h}$ productivity using existing solar furnaces. Experiments at medium scale (10-g/h, 50 kW solar power) have proven the feasibility of designing and building such a reactor and of the scaling-up method. Numerical simulation was meanwhile performed in order to improve the selectivity of the synthesis, in particular by controlling the carbon vapor cooling rate.

3.2.2 Gaseous Carbon Source-Based Production Techniques for Carbon Nanotubes

As mentioned in the introduction of this chapter, the catalysis-enhanced thermal cracking of gaseous carbon source (hydrocarbons, CO) – commonly referred to as catalytic chemical vapor deposition (CCVD) – has been known to produce carbon nanofilaments for a long time [3.4], so that reporting all the works published in the field since the beginning of the century is almost impossible. Until the 90s, however, carbon nanofilaments were mainly produced to act as a core substrate for the subsequent growth of larger (micrometric) carbon fibers – so-called vapor-grown carbon fibers – by means of thickening through mere catalyst-free CVD processes [3.57, 58]. We therefore are going to focus instead on the more recent attempts made to prepare genuine carbon nanotubes.

The synthesis of carbon nanotubes (either single- or multiwalled) by CCVD methods involves the catalytic decomposition of a carbon containing source on small metallic particles or clusters. This technique involves either an heterogeneous process if a solid substrate has a role or an homogeneous process if everything takes place in the gas phase. The metals generally used for these reactions are transition metals, such as Fe, Co, and Ni. It is a rather "low temperature" process compared to arc-discharge and laser-ablation methods, with the formation of carbon nanotubes typically occurring between 600 °C and 1,000 °C. Because of the low temperature, the selectivity of the CCVD method is generally better for the production of MWNTs with respect to graphitic particles and amorphous-like carbon, which remain an important part of the raw arc-discharge SWNT samples, for example. Both homogeneous and heterogeneous processes appear very sensitive to the nature and the structure of the catalyst used, as well as to the operating conditions. Carbon nanotubes prepared by CCVD methods are generally much longer (few tens to hundreds of micrometers) than those obtained by arc discharge (few micrometers). Depending on the experimental conditions, it is possible to grow dense arrays of nanotubes. It is a general statement that MWNTs from CCVD contain more structural defects (i. e., exhibit a lower nanotexture) than MWNTs from arc, due to the lower temperature reaction, which does not allow any structural rearrangements. These defects can be removed by subsequently applying heat treatments in vacuum or inert atmosphere to the products. Whether such a discrepancy is also true for SWNTs remains questionable. CCVD SWNTs are generally gathered into bundles that are generally of smaller diameter (few tens of nm) than their arc-discharge and laser-ablation counterparts (around 100 nm in diameter). CCVD provides reasonably good perspectives of large-scale and low-cost processes for the mass production of carbon nanotubes, a key point for their applications at the industrial scale.

A last word concerns the nomenclature. Because work in the field started more than one century ago, denomination of the carbon objects prepared by this method has changed with time with regard to the authors, research areas, and fashions. The same objects are found to be called vapor grown carbon fibers, nanofilaments, nanofibers, and from now on, nanotubes. Specifically regarding multilayered fibrous morphologies (since single-layered fibrous morphologies cannot be otherwise than SWNT anyway), the exact name should be vapor-grown carbon nanofilaments (VGCNF). Whether or not the filaments are then tubular is a matter of textural description, which should go with other textural features such as bamboo, herringbone, concentric, etc. (see Sect. 3.1.2). But the usage has decided otherwise. In the following, we will therefore use MWNTs for any hollowed nanofilament, whether they contain transversally oriented graphene walls or not. Any other nanofilament will be named "nanofiber."



Fig. 3.14a,b Sketch of a solar energy reactor in use in Odeilho (France). **(a)** Gathering of sun rays, focused in F; **(b)** Example of Pyrex® chamber placed in **(a)** so that the graphite crucible is at the point F (adapted from [3.56])

Heterogeneous Processes

Heterogeneous CCVD processes are basically simple and consist, within a furnace heated to the desired temperature, in passing a gaseous flow containing a given proportion of a hydrocarbon (mainly CH_4, C_2H_2, C_2H_4, or C_6H_6, usually as a mixture with either H_2 or an inert gas such as Ar) over small transition metal particles (Fe, Co, Ni). The latter are previously deposited onto an inert substrate, for instance, by spraying a suspension of the metal particles on it, or any other method. The reaction is chemically defined as catalysis-enhanced thermal cracking

$$C_xH_y \rightarrow x\,C + y/2\,H_2\ .$$

Catalysis-enhanced thermal cracking was used as early as the late 19th century (see beginning of chapter). Further extensive works before the 90s include those by Baker et al. [3.6, 59], or *Endo* et al. [3.60, 61]. Several review papers have been published since then, such as [3.62], in addition to many regular papers.

CO can be used instead of hydrocarbons, the reaction is then chemically defined as catalysis-enhanced disproportionation

$$2\,CO \rightarrow C + CO_2\ .$$

Heterogeneous Processes – Experimental Devices

The ability of catalysis-enhanced CO disproportionation in making carbon nanofilaments was reported by *Davis* et al. [3.63] as early as 1953, probably for the first time. Extensive following works were performed by *Boehm* [3.64], *Audier* et al. [3.16, 65–67], and *Gadelle* et al. [3.68–71].

Although formation mechanisms for SWNTs and MWNTs can be quite different (see Sect. 3.3, or refer to a review article such as [3.72]), many of the parameters of the catalytic processes have a similar and important role on the type of nanotubes formed: the temperature, the duration of the treatment, the gas composition and flow rate, and of course the catalyst nature and size. At a given temperature, depending mainly on the nature of both the catalyst and the carbon-containing gas, the catalytic decomposition will take place at the surface of the metal particles, followed by a mass-transport of the freshly produced carbon either by surface or volume diffusion until the carbon concentration reaches the solubility limit, and the precipitation starts.

It is now agreed that the formation of CCVD carbon nanotubes occurs on metal particles of a very small size, typically in the nanometer-size range [3.72]. These catalytic metal particles are prepared mainly by reduction of transition metals compounds (salts, oxides) by H_2, prior to the nanotube formation step (where the carbon containing gas is required). It is possible, however, to produce these catalytic metal particles in situ in presence of the carbon source, allowing for a one-step process [3.73]. Because the control of the metal particle size is the key point (they have to be kept at a nanometric size), their coalescence is generally avoided by supporting them on an inert support such as an oxide (Al_2O_3, SiO_2, zeolites, $MgAl_2O_4$, MgO, etc.), or more rarely on graphite. A low concentration of the catalytic metal precursor is required to limit the coalescence of the metal particles that may happen during the reduction step.

There are two main ways for the preparation of the catalyst: (a) the impregnation of a substrate with a solution of a salt of the desired transition metal catalyst, and (b) the preparation of a solid solution of an oxide of the chosen catalytic metal in a chemically inert and thermally stable host oxide. The catalyst is then reduced to form the metal particles on which the catalytic decomposition of the carbon source will lead to carbon nanotube growth. In most cases, the nanotubes can then be separated from the catalyst (Fig. 3.15).

Heterogeneous Processes – Results with CCVD Involving Impregnated Catalysts

A lot of work was already done in this area even before the discovery of fullerenes and carbon nanotubes, but although the formation of tubular carbon structures by catalytic processes involving small metal particles was clearly identified, the authors did not focus on the preparation of SWNTs or MWNTs with respect to the other carbon species. Some examples will be given here to illustrate the most striking improvements obtained.

With the impregnation method, the process generally involves four different and successive steps: (1) the impregnation of the support by a solution of a salt (nitrate, chloride) of the chosen metal catalyst; (2) the drying and calcination of the supported catalyst to get the oxide of the catalytic metal; (3) the reduction in a H_2-containing atmosphere to make the catalytic metal particles and at last (4) the decomposition of a carbon-containing gas over the freshly prepared metal particles that will lead to the nanotube growth. For example, *Ivanov* et al. [3.74] have prepared nanotubes by the decomposition of C_2H_2 (pure or in mixture with H_2) on well-dispersed transition metal particles (Fe, Co, Ni, Cu) supported on graphite or SiO_2. Co-SiO_2 was found to be the best catalyst/support combination for the preparation of MWNTs, but most of the other combinations led to carbon filaments, sometimes covered with amorphous-like carbon. The same authors have developed a precipitation-ion-exchange method that provides a better dispersion of metals on silica compared to the classical impregnation technique. The same group has then proposed the use of a zeolite-supported Co catalyst [3.75, 76], resulting in very finely dispersed metal particles (from 1 to 50 nm in diameter). Only on this catalyst could they observe MWNTs with a diameter around 4 nm and only two or three walls. *Dai* et al. [3.77] have prepared SWNTs by CO disproportionation on nano-sized Mo particles. The diameters of the nanotubes obtained are closely related to that of the original particles and range from 1 to 5 nm. The nanotubes obtained by this method are free of amorphous carbon coating. It is also found that a synergetic effect occurs in the case of an alloy instead of the components alone, and one of the most striking examples is the addition of Mo to Fe [3.78] or Co [3.79].

Heterogeneous Processes – Results with CCVD Involving Solid-Solutions-Based Catalysts

A solid solution of two metal oxides is formed when some ions of one of the metals are found in substitution of the other metal ions. For example, Fe_2O_3 can be prepared in solid solution into Al_2O_3 to give a $Al_{2-2x}Fe_{2x}O_3$ solid solution. The use of a solid solution allows a perfect homogeneity of the dispersion of each oxide one in the other. These solid solutions can be prepared by different ways but the co-precipitation of mixed-oxalates and the combustion synthesis have been used mainly for the preparation of nanotubes. The synthesis of nanotubes by catalytic decomposition of CH_4 over $Al_{2-2x}Fe_{2x}O_3$ solid solutions was originated by *Peigney* et al. [3.73] and then studied extensively by the same group using different oxides such as spinel-based solid solutions ($Mg_{1-x}M_xAl_2O_4$ with M = Fe, Co, Ni, or a binary alloy [3.80, 81] or magnesia-based solid solutions [3.80, 82] ($Mg_{1-x}M_xO$, with M = Fe, Co or Ni)). Because of the very homogeneous dispersion of the catalytic oxide, it is possible to produce very small catalytic metal particles, at the high temperature required for the decomposition of CH_4 (which was chosen for its greater thermal stability compared to other hydrocarbons). The method proposed by these authors involves the heating of the solid solution from room temperature to a temperature between 850 °C and 1,050 °C in a mixture of H_2 and CH_4, typically containing 18 mol.% of CH_4. The nanotubes obtained depend clearly on the nature of both the transition metal (or alloy) used and the inert oxide (matrix), the latter because the Lewis acidity seems to play an important role [3.83]. For example, in the case of solid solutions containing around 10 wt% of Fe, the amount of carbon nanotubes obtained is decreasing in the following order depending of the matrixoxide: $MgO > Al_2O_3 > MgAl_2O_4$ [3.80]. In the case of MgO-based solid solutions the nanotubes can be very easily separated from the catalyst by dissolving it, in diluted HCl, for example [3.82]. The nanotubes obtained are typically gathered into small diameter bundles (less than 15 nm) with lengths up to 100 µm. The nanotubes are mainly SWNTs and DWNTs, with diameters ranging between 1 and 3 nm.


Supported catalyst or solid solution
Catalytical metal particles
CNTs
(1)
(2)
(3)

Fig. 3.15 Formation of nanotubes by the CCVD-based impregnation technique. (1) Formation of the catalytic metal particles by reduction of a precursor; (2) Catalytic decomposition of a carbon-containing gas, leading to the growth of carbon nanotubes (CNTs); (3) Removal of the catalyst to recover the CNTs (from [3.80])

Obtaining pure nanotubes by the CCVD method requires, as for all the other techniques, the removal of the catalyst. When a catalyst supported (impregnation) in a solid solution is used, the supporting – and catalytically inactive – oxide is the main impurity, both in weight and volume. When oxides such as Al_2O_3 or SiO_2 (or even combinations) are used, aggressive treatments involving hot caustic solutions (KOH, NaOH) for Al_2O_3 or the use of HF for SiO_2 are required. These treatments have no effect, however, on the other impurities such as other forms of carbon (amorphous-like carbon, graphitized carbon particles and shells, and so on). Oxidizing treatments (air oxidation, use of strong oxidants such as HNO_3, $KMnO_4$, H_2O_2) are thus required and allow for the removal of most of the unwanted forms of carbon but are resulting in a low yield of remaining carbon nanotubes, which are often quite damaged. *Flahaut* et al. [3.82] were the first to use a MgCoO solid solution to prepare SWNTs and DWNTs that could be easily separated without any damage by a fast and safe washing with an aqueous HCl solution.

In most cases, only very small quantities of catalyst (typically less than 500 mg) have been used, and most claims for "high yield" productions of nanotubes are based on laboratory experimental data, without taking into account all the technical problems related to the scaling up of a laboratory-scale CCVD reactor. At the present time, although the production of MWNTs is possible at an industrial scale, the production of SWNTs at an affordable cost is still a challenge.

Homogeneous Processes

The homogenous route, also called "floating catalyst method," differs from the other CCVD-based methods because it uses only gaseous species and does not require the presence of any solid phase in the reactor. The basic principle of this technique, similar to the other CCVD processes, is to decompose a carbon source (ethylene, xylene, benzene, carbon monoxide, etc.) on nanometric transition metallic (generally Fe, Co, or Ni) particles in order to obtain carbon nanotubes. The catalytic particles are formed directly in the reactor, however, and are not introduced before the reaction, as it happens in the supported CCVD, for instance.

Homogeneous Processes – Experimental Devices

The typical reactor used in this technique is a quartz tube placed in an oven to which the gaseous feedstock, containing the metal precursor, the carbon source, some hydrogen, and a vector gas (N_2, Ar, or He), is sent. The first zone of the reactor is kept at a lower temperature, and the second zone, where the formation of tubes occurs, is heated to 700–1,200 °C. The metal precursor is generally a metal-organic compound, such as a zero-valent carbonyl compound like $Fe(CO)_5$ [3.84], or a metallocene [3.85–87], for instance ferrocene, nickelocene or cobaltocene. It may be advantageous to make the reactor vertical, in order for the effect of gravity to be symmetrically dispatched on the gaseous volume inside the furnace and to help in maintaining for a while the solid products in fluidized bed.

Homogeneous Processes – Results

The metal-organic compound decomposes in the first zone of the reactor to generate the nanometric metallic particles that can catalyze the nanotubes formation. In the second part of the reactor, the carbon source is decomposed to atomic carbon which then is responsible for the formation of nanotubes.

This technique is quite flexible and both single-walled nanotubes [3.88] and multiwalled nanotubes [3.89] have been obtained depending on the carbon feedstock gas; it has also been exploited for some years in the production of vapor grown carbon nanofibers [3.90].

The main drawback of this type of process is again, as for heterogeneous processes, the difficulty to control the size of the metal nanoparticles, and thus the nanotube formation is often accompanied by the production of undesired carbon forms (amorphous carbon or polyaromatic carbon phases found as various phases or as coatings). In particular, encapsulated forms have been often found, as the result of the creation of metallic particles that are too big to be active for growing nanotubes (but are still effective for catalytically decomposing the carbon source) and be totally recovered by graphene layers.

The same kind of parameters as for heterogeneous processes have to be controlled in order to finely tune this process and obtain selectively the desired morphology and structure of the nanotubes formed, such as: the choice of the carbon source; the reaction temperature; the residence time; the composition of the incoming gaseous feedstock with a particular attention paid to the role played by hydrogen proportion, which can control the orientation of graphenes with respect to the nanotube axis thus switching from c-MWNT to h-MWNT [3.69]; and the ratio of the metallorganic precursor to the carbon source (for lower values, SWNTs are obtained [3.85]). As recently demonstrated, the overall process can be improved by adding other compounds such as ammonia or sulfur-containing species to the reactive gas phase. The former allows aligned nanotubes and mixed C-N nanotubes [3.91] to be obtained, the latter results in a significant increase in productivity [3.90].

It should be emphasized that only small productions have been achieved so far, and the scale up toward industrial exploitation seems quite difficult because of the large number of parameters that have to be considered. A critical one is to be able to increase the quantity of metallorganic compound that has to be sent in the reactor, as a requirement to increase the production, without obtaining too big particles. This problem has not yet been solved. An additional problem inherent in the process is the possibility of clogging the reactor due to the deposition of metallic nanoparticles on the reactor walls followed by carbon deposition.

A significant breakthrough concerning this technique could be the process developed at Rice University, the so-called HiPCo^{TM} process to produce SWNTs of very high purity [3.92]. This gas phase catalytic reaction uses carbon monoxide to produce, from $[Fe(CO)_5]$, a SWNT material claimed to be relatively free of by-products. The temperature and pressure conditions required are applicable to industrial plants. The company Carbon Nanotechnologies Inc. (Houston, TX, USA) actually sells raw SWNT materials prepared that way, at a marketed price of $ 375/g, doubled if purified (2003 data). Other companies are more specialized in MWNTs such as Applied Sciences Inc. (Cedarville, Ohio, USA), which currently has a production facility of ∼ 40 tons/year of ∼ 100 nm large MWNTs (Pyrograf-III), or Hyperion Catalysis (Cambridge, MA, USA), which makes MWNT-based materials.

Templating

Another technique interesting to describe briefly, though definitely not suitable for mass production, is the templating technique. It is the second method only (the first being the electric-arc technique, when considering the formation of MWNTs on the cathode) able to synthesize carbon nanotubes without any catalyst. Any other work reporting the catalyst-free formation of nanotubes is likely to have been fooled by metallic impurities present in the reactor or by some other factors having brought a chemical gradient to the system. Another original aspect is that it allows aligned nanotubes to be obtained naturally, without the help of any subsequent alignment procedure. But recovering the nanotubes only requires the template to be removed (dissolved), which means the former alignment of the nanotubes is lost.

Templating – Experimental Devices

The principle of the technique is to deposit a solid carbon coating obtained from CVD method onto the walls of an appropriate porous substrate whose pores are displayed as parallel channels. The feedstock is again a hydrocarbon, as a common carbon source. The substrate can be alumina or zeolite for instance, however, which present natural channel pores, while the whole is heated to a temperature able to crack the hydrocarbon selected as carbon source (Fig. 3.16).


Anodic aluminium oxide film
Carbon tubes
Carbon deposition on the pore wall
(Propylene, 800 °C)
HF washing
50 – 100μm
10 – 500μm

Fig. 3.16 Principle of the templating technique for the catalyst-free formation of single-walled or concentric-type multi-walled carbon nanotubes (from [3.93])

Templating – Results

Provided the chemical vapor deposition mechanism (which is actually better described as a chemical vapor infiltration mechanism) is well controlled, the synthesis results in the coating of the channel pore walls by a variable number of graphenes. Both MWNTs (exclusively concentric type) or SWNTs can be obtained. The smallest SWNTs (diameters ∼ 0.4 nm) ever obtained mentioned in Sect. 3.1 have actually been synthesized by this technique [3.11]. Lengths are directly determined by channel lengths, i. e. by the thickness of the substrate plate. A main advantage is the purity of the tubes (no catalyst remnants, and little other carbon phases). On the other hand, the nanotube structure is not closed at both ends, which can be an advantage or a drawback, depending on the application. For instance, recovering the tubes requires the porous matrix to dissolve using one of the chemical treatment previously cited. The fact that tubes are open makes them even more sensitive to the acid attack.

3.2.3 Miscellaneous Techniques

In addition to the major techniques described in Sects. 3.2.1 and 3.2.2, many attempts can be found in literature to produce nanotubes by various ways, with a generally specific goal, such as looking for a low-cost or a catalyst-free production process. None has been sufficiently convincing so far to be presented as a serious alternative to the major processes described previously. Some examples are provided in the following.

Hsu et al. [3.94] have succeeded in preparing MWNTs (including coiled MWNTs, a peculiar morphology resembling a spring) by a catalyst-free (although Li was present) electrolytic method, by running a 3–5 A current between two graphite electrodes (a graphite crucible as the anode and a graphite rod as the cathode). The graphite crucible was filled with lithium chloride, while the whole was heated in air or argon at ∼ 600 °C. As with many other techniques, by-products such as encapsulated metal particles, carbon shells, amorphous carbon, and so on, are formed.

Cho et al. [3.95] have proposed a pure chemistry route, by the polyesterification of citric acid onto ethylen glycol at 50 °C, followed by a polymerization at 135 °C, then carbonized at 300 °C under argon, then oxidized at 400 °C in air. Despite the latter oxidation step, the solid product surprisingly contains short MWNTs, although obviously with a poor nanotexture. By-products such as carbon shells and amorphous carbon are also formed.

Li et al. [3.96] have also obtained short MWNTs by a catalyst-free (although Si is present) pyrolytic method which involves heating silicon carbonitride nanograins in a BN crucible to 1,200–1,900 °C in nitrogen within a graphite furnace. No details are given about the possible occurrence of by-products, but they are likely considering the complexity of the chemical system (Si-C-B-N) and the high temperatures involved.

Terranova et al. [3.98] have investigated the catalyzed reaction between a solid carbon source and atomic hydrogen. Graphite nanoparticles (∼ 20 nm) are sent with a stream of H_2 onto a Ta filament heated at 2,200 °C. The species produced, whatever they are, then hit a Si polished plate warmed to 900 °C and supporting transition metal particles. The whole chamber is under a dynamic vacuum of 40 torr. SWNTs are supposed to form according to the authors, although images are poorly convincing. One major drawback of the method, besides its complexity compared to others, is the difficulty of recovering the "nanotubes" from the Si substrates onto which they seem to be firmly bonded.

A last example is an attempt to prepare nanotubes by diffusion flame synthesis [3.99]. A regular gaseous hydrocarbon source (ethylene, . . .) added with ferrocene vapor is sent within a laminar diffusion flame made from air and CH_4 whose temperature range is 500–1,200 °C. SWNTs are actually formed, together with encapsulated metal particles, soot, and so on. In addition to a low yield, the SWNT structure is quite poor.

3.2.4 Synthesis of Aligned Carbon Nanotubes

Several applications (such as field-emission-based display, see Sect. 3.6) require that carbon nanotubes grow as highly aligned bunches, in highly ordered arrays, or located at specific positions. In that case, the purpose of the process is not mass production but controlled growth and purity, with subsequent control of nanotube morphology, texture, and structure. Generally speaking, the more promising methods for the synthesis of aligned nanotubes are based on CCVD processes, which involve molecular precursors as carbon source, and method of thermal cracking assisted by the catalytic activity of transition metal (Co, Ni, Fe) nanoparticles deposited onto solid supports. Few attempts have been made so far to obtain such materials with SWNTs. But the catalyst-free templating methods related to that described in Sect. 3.2.2 are not considered here, due to the lack of support after the template removal, which does not allow the former alignment to be maintained.

During the CCVD-growth, nanotubes can self-assemble into nanotube bunches aligned perpendicular to the substrate if the catalyst film on the substrate has a critical thickness [3.100], the driving forces for this alignment are the van der Waals interactions between the nanotubes, which allow them to grow perpendicularly to the substrates. If the catalyst nanoparticles are deposited onto a mesoporous substrate, the mesoscopic pores may also cause a certain effect on the alignment when the growth starts, thus controlling the growth direction of the nanotubes. Two kinds of substrates have been used so far in this purpose: mesoporous silica [3.101, 102] and anodic alumina [3.103].

Different methods have been reported in the literature for metal particles deposition onto substrates: (i) deposition of a thin film on alumina substrates from metallic-salt precursor impregnation followed by oxidation/reduction steps [3.104], (ii) embedding catalyst particles in mesoporous silica by sol-gel processes [3.101], (iii) thermal evaporation of Fe, Co, Ni, or Co-Ni metal alloys on SiO_2 or quartz substrates under high vacuum [3.105, 106], (iv) photolithographic patterning of metal-containing photoresist polymer with the aid of conventional black and white films as a mask [3.107] and, electrochemical deposition at the bottom of the pores in anodic aluminum oxide templates [3.103].

Depositing the catalyst nanoparticles onto a previously patterned substrate allows one to control the frequency of local occurrence and the display of the MWNT bunches formed. The as-produced materials mainly consist in arrayed, densely packed, freestanding, aligned MWNTs (Fig. 3.17), which is quite



Fig. 3.17 Example of a free-standing MWNT array obtained from the pyrolysis of a gaseous carbon source over catalyst nanoparticles previously deposited onto a patterned substrate. Each square-base rod is a bunch of MWNTs aligned perpendicular to the surface (from [3.97])



Fig. 3.18a–c Sketch of a double-furnace CCVD device for the organo-metallic/hydrocarbon co-pyrolysis process. In **(a)**: sublimation of the precursor; in **(b)**: decomposition of the precursor and MWNTs growth onto the substrate. **(c)** Example of the densely packed and aligned MWNT material obtained (from [3.108])

suitable for field emission-based applications for instance [3.97].

When a densely packed coating of vertically aligned MWNTs is desired (Fig. 3.18b), another route is the pyrolysis of hydrocarbons in the presence of organometallic precursor molecules like ferrocene or iron pentacarbonyl, operating in a dual furnace system (Fig. 3.18a). The organo-metallic precursor (e.g., ferrocene) is first sublimed at low temperature in the first furnace or is injected as a solution along with the hydrocarbon feedstock, then the whole components are pyrolyzed at higher temperature in the second furnace [3.88, 108–111]. The parameters that must be taken into account are the heating or feeding rate of ferrocene, the flow rate of the vector gas (Ar or $\mathrm{N_2}$) and of the gaseous hydrocarbon, and the temperature of pyrolysis (650–1,050 °C). Generally speaking, the co-deposition process using $[\mathrm{Fe(CO)_5}]$ as catalyst source implies its thermal decomposition at elevated temperatures to produce atomic iron that deposits on the substrates in the hot zone of the reactor. As the nanotube growth occurs simultaneously with the introduction of $[\mathrm{Fe(CO)_5}]$, the temperatures chosen for the growth depend on the carbon feedstock utilized, e.g., they can vary from 750 °C for acetylene to 1,100 °C for methane. Mixtures of $[\mathrm{FeCp_2}]$ and xylene or $[\mathrm{FeCp_2}]$ and acetylene have also been used successfully for the production of freestanding MWNTs.

The nanotube yield and quality are directly linked with the amount and size of the catalyst particles, and since the planar substrates used do not exhibit high surface area, the dispersion of the metal can be a key step in the process. It has been observed that an etching pretreatment of the surface of the deposited catalyst thin film with $\mathrm{NH_3}$ may be critical for an efficient growth of nanotubes by bringing the appropriate metal particle size distribution. It may also favor the alignment of MWNTs and prevent the formation of amorphous carbon from thermal cracking of acetylene [3.112].

3.3 Growth Mechanisms of Carbon Nanotubes

Growth mechanisms of carbon nanotubes are still debated. But researchers have been impressively imaginative and have made a number of hypotheses. One reason is that conditions allowing carbon nanofilaments to grow are very diverse, which means that related growing mechanisms are many. For given conditions, the truth is even probably a combination or a compromise between some of the proposals. Another reason is that phenomena are quite fast and difficult to observe in situ. It is generally agreed, however, that growth should occur so that the number of dangling bonds is limited, for energetic reasons.

3.3.1 Catalyst-Free Growth

As already mentioned, in addition to the templating technique which merely relates to chemical vapor infiltration mechanism for pyrolytic carbon, the growth of c-MWNT as a deposit onto the cathode in the electric-arc method is a rare example of catalyst-free carbon nanofilament growth. The driving forces are obviously related to the electric field, i. e. related to charge transfers from an electrode to the other via the particles contained in the plasma. How the MWNT nucleus forms is not clear, but once it has started, it may include the direct incorporation of C_2 species to the primary graphene structure as it was formerly proposed for fullerenes [3.113]. This is supported by recent C_2 radical concentration measurements that revealed an increasing concentration of C_2 from the anode being consumed to the growing cathode (Fig. 3.13), indicating, first, that C_2 are secondary species only, and second, that C_2 species could actually participate actively in the growth mechanism of c-MWNTs in the arc method.

3.3.2 Catalytically Activated Growth

Growth mechanisms involving catalysts are more difficult to ascertain, since they are more diverse. Although a more or less extensive contribution of a VLS (Vapor-Liquid-Solid [3.114]) mechanism is rather well admitted, it is quite difficult to find comprehensive and plausible explanations able to account for both the various conditions used and the various morphologies observed. What follows is an attempt to provide overall explanations of most of the phenomena, while remaining consistent with the experimental data. We did not consider hypotheses for which there are a lack of experimental evidence, such as the moving nano-catalyst mechanism, which proposed that dangling bonds from a growing SWNT may be temporarily stabilized by a nano-sized catalyst located at the SWNT tip [3.23], or the scooter mechanism, which proposed that C dangling bonds are temporarily stabilized by a single catalyst atom, moving all around the SWNT cross section edge, allowing subsequent C atom addition [3.115].

From the various results, it appears that the most important parameters are probably the thermodynamic conditions (only temperature will be considered here), the catalyst particle size, and the presence of a substrate. Temperature is critical and basically corresponds to the discrepancy between CCVD methods and solid-carbon-source based method.

Low Temperature Conditions

Low temperature conditions are typical from CCVD conditions, since nanotubes are frequently found to grow far below 1,000 °C. If conditions are such that the catalyst is a crystallized solid, the nanofilament is probably formed according to a mechanism close to a VLS mechanism, in which three steps are defined: (i) adsorption then decomposition of C-containing gaseous moieties at the catalyst surface; (ii) dissolution then diffusion of the C-species through the catalyst, thus forming a solid solution; (iii) back precipitation of solid carbon as nanotube walls. The texture is then determined by the orientation of the crystal faces relative to the filament axis (Fig. 3.19), as demonstrated beyond doubt by transmission electron microscopy images such as that in *Rodriguez* et al. [3.19]. This mechanism can therefore provide either c-MWNT, or h-MWNT, or platelet nanofiber.

If conditions are such that the catalyst is a liquid droplet, either because of higher temperature conditions or because of lower temperature melting catalyst, a mechanism similar to that above can still occur, really VLS (vapor = gaseous C species, liquid = molten catalyst, S = graphenes), but there are obviously no more crystal faces to orientate preferentially the rejected graphenes. Energy minimization requirements will therefore tend to make them concentric and parallel to the filament axis.

With large catalyst particles (or in the absence of any substrate), the mechanisms above will generally follow a "tip growth" scheme, i. e., the catalyst will move forward while the rejected carbon form the nanotube behind, whether there is a substrate or not. In that case,



Fig. 3.19 Illustration of the relationships between the catalyst crystal outer morphology and the subsequent carbon nanofilament inner texture. Crystal are drawn from their images in the projected plane perpendicular to the electron beam in a transmission electron microscope, i. e. crystal morphology in the out-of-plane dimension is not ascertained (adapted from [3.19])

chances are high that one end is open. On the contrary, when catalyst particles deposited onto a substrate are small enough (nanoparticles) to be refrained to move by the interaction forces with the substrate, the growth mechanism will follow a "base growth" scheme, i. e. the carbon nanofilament grows away from the substrate leaving the catalyst nanoparticle attached to the substrate (Fig. 3.20).

The bamboo texture that affects both the herringbone and the concentric texture may reveal a specificity of the dissolution-rejection mechanism, i. e. a periodic, discontinuous dynamics of the phenomenon. Once the catalyst has reached the saturation threshold regarding its content in carbon, it expulses it quite suddenly. Then it becomes again able to incorporate a given amount of carbon without having any catalytic activity for a little while, then over-saturation is reached again, etc. Factors controlling such a behavior, however, are not determined.

It is then clear that, in any of the mechanisms above, 1 catalyst particle = 1 nanofilament. This explains why, although making SWNT by CCVD methods is possible, controlling the catalyst particle size is critical, since it thereby controls the subsequent nanofilament to be grown from it. Reaching a really narrow size distribution in CCVD is quite challenging, specifically as far as nanosizes are concerned when growing SWNTs is the goal. Only particles < 2 nm will be able to make it (Fig. 3.20), since larger SWNTs would energetically not be favored [3.10]. Another specificity of the CCVD method and from the related growth mechanisms is that the process can be effective all along the isothermal zone of the reactor furnace since continuously fed with a carbon-rich feedstock, which is generally in excess, with a constant composition at a given time of flight of the species. Coarsely, the longer the isothermal zone in gaseous carbon excess conditions, the longer the nanotubes. This is why the nanotube lengths can be much longer than that obtained by solid-carbon-source-based methods.

Table 3.2 provides guidelines for the relationships between the synthesis conditions and the type of nanotube formed.

High Temperature Conditions

High temperature conditions are typical from solid-carbon-source based methods such as electric arc, laser vaporization, or solar furnace (see Sect. 3.2). The huge temperatures involved (several thousands °C) atomize both the carbon source and the catalyst. Of course, catalyst-based SWNTs do not form in the area of highest temperatures (contrary to c-MWNT in the electric arc method), but the medium is made of atoms and radicals all mixed, some of which are likely to condense into the same droplet (since it will be liquid at the beginning). At some distance from the atomization zone, the medium is therefore made of carbon metal alloy droplets and of secondary carbon species that range from C_2 to higher order molecules such as corannulene which is made of a central pentagon surrounded by 5 hexagons. (The preferred formation of such a molecule can be explained by the former association of carbon atoms into a pentagon, because it is the fastest way to limit dangling bonds at low energetic cost, thereby providing a fixation site for other carbon atoms (or C_2) which also will tend to close into a ring, again to limit dangling bonds. Since adjacent pentagons are not energetically favoured, these cycles will be hexagons. Such a molecule is thought to be a probable precursor for fullerenes. Fullerenes are actually always produced, even in conditions which produce SWNTs.) The same event of saturation in C of the carbon-metal alloy droplet occurs as described in Sect. 3.3.2, resulting in the precipitation of excess C outside the particle upon the effect of the decreasing thermal gradient in the reactor, which decreases the solubility threshold of C in the metal [3.117]. Once the "inner" carbon atoms reach the catalyst particle surface, they meet the "outer" carbon species, including corannulene, that will con-



Fig. 3.20 High resolution transmission electron microscopy images of several SWNTs grown from iron-based nanoparticles by CCVD method, showing that particle sizes determine SWNT diameters in that case (adapted from [3.116])

Table 3.2 Guidelines indicating the relationships between possible carbon nanofilament morphologies and some basic synthesis conditions

		Increasing temperature … → … and physical state of catalyst			Substrate		Thermal gradient	
		Solid (crystallized)	**Liquid from melting**	**Liquid from clusters**	**Yes**	**No**	**Low**	**High**
Catalyst particle size	$<\sim$ **3** nm	SWNT	SWNT	?	base-growth	tip-growth	long length	short length
	$>\sim$ **3** nm	MWNT (c,h,b) platelet nanofiber	c-MWNT	SWNT	tip-growth			
Nanotube diameter		(heterogeneous related to catalyst particle size)		homogeneous (independent) from particle size)				
Nanotube/particle		one nanotube/particle		several SWNTs/particle				

tribute to cap the merging nanotubes. Once formed and capped, nanotubes can grow both from the inner carbon atoms (Fig. 3.21a), according to the VLS mechanism proposed by *Saito* et al. [3.117], and from the outer carbon atoms, according the adatom mechanism proposed by *Bernholc* et al. [3.118]. In the latter, carbon atoms from the surrounding medium in the reactor are attracted then stabilized by the carbon/catalyst interface at the nanotube/catalyst surface contact, promoting their subsequent incorporation at the tube base. The growth mechanism therefore mainly follows the base growth scheme. But once the nanotubes are capped, C_2 species still remaining in the medium and which meet the growing nanotubes far from the nanotube/catalyst interface, may still incorporate the nanotubes from both the side wall or the tip, thereby giving rise to some proportion of Stone–Wales defects [3.40]. The occurrence of a nanometer-thick surface layer of yttrium carbide (onto the main Ni-containing catalyst core), whose some lattice distances are commensurable with that of the C−C distance in graphene, as recently revealed by *Gavillet* et al. [3.48], could possibly play a beneficial role in the stabilization effect at the nanotube/catalyst interface and explain why SWNT yield is enhanced by such bimetallic alloys (as opposed to single metal catalysts).

A major difference with the low temperature mechanisms described for CCVD methods is that many nanotubes are formed from a single, relatively large (∼ 10−50 nm) catalyst particle (Fig. 3.21b), whose size distribution is therefore not as critical as for the low



Fig. 3.21 **(a)** Mechanism proposed for SWNT growth (see text). **(b)** Transmission electron microscopy image of SWNT growing radial to a large Ni catalyst particle surface in the electric arc experiment. (modified from [3.17])

temperature mechanisms (particles that are too large, however, would induce polyaromatic shells instead of nanotubes). That is why SWNT diameters are much more homogeneous than for CCVD methods. Why the most frequent diameter is ∼ 1.4 nm is again a matter of energy balance. Single-wall nanotubes larger than ∼ 2.5 nm are not stable [3.10]. On the other hand, strain to the C−C angles increases as the radius of curvature decreases. Such diameter (1.4 nm) should therefore correspond to the best energetic compromise. Another difference with the low temperature mechanisms for CCVD is that temperature gradients are huge, and the gas phase composition surrounding the catalysts droplets is also subjected to rapid changes (as opposed to what could happen in a laminar flow of a gaseous feedstock whose carbon source is in excess). This explains why nanotubes from arc are generally shorter than nanotubes from CCVD, and why mass production by CCVD should be favored. In the latter, the catalytic role of the metallic particle can be recurrent as long as the conditions are maintained. In the former, surrounding conditions change continuously, and the window for efficient catalysis effect can be very narrow. Lowering temperature gradients in solid carbon source-based SWNT producing methods such as the electric-arc reactor should therefore be a way to increase the SWNT yield and length [3.119]. Amazingly, this is in opposition to fullerene production from arc.

3.4 Properties of Carbon Nanotubes

Carbon is a unique light atom that can form one-, two-, or threefold strong chemical bonds. The planar threefold configuration forms graphene planes that can, under certain growth conditions (see Sect. 3.3), adopt a tubular geometry. Properties of the so-called carbon nanotubes may change drastically depending on whether SWNTs or MWNTs are considered (see Sect. 3.1).

3.4.1 Variability of Carbon Nanotube Properties

Properties of MWNTs are generally not much different from that of regular polyaromatic solids (which may exhibit graphitic, or turbostratic, or intermediate crystallographic structure), and variations are then mainly driven by the textural type of the MWNTs considered (concentric, herringbone, bamboo) and the quality of the nanotexture (see Sect. 3.1), both of which control the extent of anisotropy. Actually, for polyaromatic solids, whose structural entities are built with stacked graphenes, bond strength is quite different depending on whether the in-plane direction is considered (which includes only very strong – covalent – and therefore very short – 0.142 nm bonds) or the direction perpendicular to it (which includes only very weak – van der Waals – and therefore very loose – ∼ 0.34 nm bonds). Such heterogeneity is not found in single (isolated) SWNTs. But the heterogeneity is back along with the related consequences when SWNTs associate into bundles. Therefore, properties – and applicability – for SWNTs may also change dramatically depending on whether single SWNT or SWNT ropes are involved.

In the following, we will emphasize SWNT properties, as far as their original structure often leads to original properties with respect to that of regular polyaromatic solids. But we will also sometimes cite properties of MWNTs for comparison.

3.4.2 General Properties

SWNT-type carbon nanotube diameters fall in the nanometer range and can be hundreds of micrometers long. SWNTs are narrower in diameter than the thinnest line able to be obtained by electron beam lithography. SWNTs are stable up to 750 °C in air (but start being damaged earlier through oxidation mechanisms, as demonstrated by their subsequent ability to be filled with molecules, see Sect. 3.5) and up to ∼ 1,500–1,800 °C in inert atmosphere beyond which they transform into regular, polyaromatic solids (i. e., phases built with stacked graphenes instead of single graphenes) [3.120]. They have half the mass density of aluminum. While the length of SWNTs can be macroscopic, the diameter has a molecular dimension. As a molecule, properties are closely influenced by the way atoms are displayed along the molecule direction. The physical and chemical behavior of SWNTs are therefore related to their unique structural features [3.121].

3.4.3 SWNT Adsorption Properties

An interesting feature of SWNTs is their very high surface area, the highest ever due to the fact that a single graphene sheet is probably the unique example of a material energetically stable in normal conditions while consisting of a single layer of atoms. Ideally, i. e. not considering SWNTs in bundles but isolated SWNTs, and provided the SWNTs have one end opened (by oxidation treatment for instance), the real surface area can be equal to that of a single, flat graphene, i. e. $\sim 2{,}700\,\mathrm{m^2/g}$ (accounting for both sides).

But practically, nanotubes – specifically SWNTs – are more often associated with many other nanotubes to form bundles, then fibers, films, papers, etc. than as a single entity. Such architectures develop various porosity ranges important for determining adsorption properties (the latter aspects are also developed in Sect. 3.6.2, focused on applications). It is thus most appropriate to discuss adsorption on SWNT-based materials in term of adsorption on the outer or inner surfaces of such bundles. Furthermore, theoretical calculations have predicted that the molecule adsorption on the surface or inside of the nanotube bundle is stronger than that on an individual tube. A similar situation exists for MWNTs where adsorption could occur either on or inside the tubes or between aggregated MWNTs. Additionally, it has been shown that the curvature of the graphene sheets constituting the nanotube walls can result in a lower heat for adsorption with respect to that of a planar graphene (see Sect. 3.1.1).

Accessible SWNT Surface Area

Various studies dealing with the adsorption of nitrogen on MWNTs [3.122, 123] and SWNTs [3.124] have highlighted the porous nature of these two materials. Pores in MWNTs can be divided mainly into inner hollow cavities of small diameter (narrowly distributed, mainly 3–10 nm) and aggregated pores (widely distributed, 20–40 nm), formed by interaction of isolated MWNTs. It is also worth noting that the ultra-strong nitrogen capillarity in the aggregated pores contributes to the major part of the total adsorption, showing that the aggregated pores are much more important than the inner cavities of the MWNTs for adsorption. Adsorption of N_2 has been studied on as-prepared and acid-treated SWNTs, and the results obtained point out the microporous nature of SWNT materials, as opposed to the mesoporous MWNT materials. Also, as opposed to isolated SWNTs (see above), surface areas well above $400\,\mathrm{m^2g^{-1}}$ have been measured for SWNT-bundle-containing materials, with internal surface areas of $300\,\mathrm{m^2g^{-1}}$ or higher.

The theoretical specific surface area of carbon nanotubes ranges over a broad scale, from 50 to $1{,}315\,\mathrm{m^2g^{-1}}$ depending on the number of walls, the diameter, or the number of nanotubes in a bundle of SWNTs [3.125]. Experimentally, the specific surface area of SWNTs is often larger than that of MWNTs. Typically, the total surface area of as-grown SWNTs ranges between 400 and $900\,\mathrm{m^2g^{-1}}$ (micropore volume, $0.15–0.3\,\mathrm{cm^3g^{-1}}$), whereas values ranging between 200 and $400\,\mathrm{m^2g^{-1}}$ for as-produced MWNTs are often reported. In the case of SWNTs, the diameter of the tubes and the number of tubes in the bundle will affect mainly the BET value. It is worth noting that opening/closing of the central canal noticeably contributes to the adsorption properties of nanotubes. In the case of MWNTs, chemical treatments such as KOH activation are efficient to develop a microporosity, and surface areas as high as $1{,}050\,\mathrm{m^2g^{-1}}$ have been reported [3.126]. Thus it appears that opening or cutting as well as chemical treatments (purification step for example) of carbon nanotubes can considerably affect their surface area and pore structure.

Adsorption Sites and Binding Energy of the Adsorbates

An important problem to solve when considering adsorption on nanotubes is the identification of the adsorption sites. Adsorption of gases in a SWNT bundle can occur inside the tubes (pore), in the interstitial triangular channels between the tubes, on the outer surface of the bundle, or in a groove formed at the contact between adjacent tubes on the outside of the bundle (Fig. 3.22). Starting from closed-end SWNTs, simple molecules can adsorb on the walls of the outer nanotubes of the bundle and preferably on the external grooves. For the more attractive sites, corresponding to the first adsorption stages, it seems that adsorption or condensation in the interstitial channel of SWNT bundles depends on the size of the molecule (or on the SWNT diameters) and on their interaction energies [3.127]. Then, adapted treatments to open the tubes will favour the gas adsorption (e.g., O_2, N_2 in the inner walls [3.128, 129]). For hydro-



Fig. 3.22 Sketch of a SWNT bundle illustrating the four different adsorption sites

gen and other small molecules, computational methods have shown that, for open SWNTs, the pore, interstitial, and groove sites are energetically more favourable than the surface site, with respect to the increasing number of carbon nanotubes interacting with the adsorbed molecules [3.130].

For MWNTs, adsorption can occur in the aggregated pores, inside the tube or on the external walls. In the latter case, the presence of defects, as incomplete graphene layers, has to be taken into consideration. Although adsorption between the graphenes (intercalation) has been proposed in the case of hydrogen adsorption in h-MWNTs or platelet nanofibers [3.132], it is unlikely for many molecules due to steric effect and should not prevail for small molecules due to long diffusion path.

Few studies deal with adsorption sites in MWNTs, however it has been shown that butane adsorbs more in the case of MWNTs with smaller outside diameters, which is consistent with another statement that the strain brought to curved graphene surfaces affects sorption. Most of the butane adsorbs to the external surface of the MWNTs while only a small fraction of the gas condensed in the pores [3.133]. Comparative adsorption of krypton or of ethylene on MWNTs or on graphite has allowed scientists to determine the dependence of the adsorption and wetting properties on the specific morphology of the nanotubes. Higher condensation pressure and lower heat of adsorption were found on nanotubes with respect to graphite [3.134]. These differences result mainly from a decrease in the lateral interactions between the adsorbed molecules, related to the curvature of the graphene sheets.

A limited number of theoretical as well as experimental works exist on the values of the binding energies for gases on carbon nanotubes. If most of these studies report low binding energies on SWNTs, consistent with a physisorption, some experimental results, in particular in the case of hydrogen, are still controversial (see Sect. 3.6.2). In the case of platelet nanofibers, the initial dissociation of hydrogen on graphite edge sites, which constitute the majority of the nanofiber surface has been proposed [3.135]. For carbon nanotubes, a mechanism that involves H_2 dissociation on residual metal catalyst followed by H spillover and adsorption on the most reactive nanotube sites could be envisaged [3.136]. Doping nanotubes with alkali may enhance hydrogen adsorption, due to the charge transfer from the alkali metal to the nanotube, which polarizes the H_2 molecule and induces dipole interaction [3.137].

Generally speaking, the adsorbates can be either charge donors or acceptors to the nanotubes. The observed trends in the binding energies of gases with different van der Waals radii suggest that the groove sites of SWNTs are the preferred low coverage adsorption sites due to their higher binding energies. Finally, several studies have shown that, at low coverage, the binding energy of the adsorbate on SWNT is between 25% and 75% higher than the binding energy on a single graphene. This discrepancy can be attributed to an increase of the effective coordination in the binding sites, such as the groove sites, in SWNTs bundles [3.138, 139]. Representative results concerning the adsorption properties of SWNTs and MWNTs are summarized on Table 3.3.

Table 3.3 Adsorption properties and sites of SWNTs and MWNTs. Letters in column 5 refer to Fig. 3.22. Data of two last columns are from [3.131]

Type of nanotube	Porosity (cm^3g^{-1})	Surface area (m^2/g)	Binding energy of the adsorbate	Adsorption sites	Attractive potential per site (eV)	Surface area per site (m^2/g)
SWNT (bundle)	Microporous V_{micro}: 0.15–0.3	400–900	Low, mainly physisorption 25–75 % > graphite	Surface (A) Groove (B) Pore (C) Interstitial (D)	0.049 0.089 0.062 0.119	483 22 783 45
MWNT	Mesoporous	200–400	Physisorption	Surface Pore Aggregated pores	–	–

3.4.4 Transport Properties

The narrow diameter of SWNTs has a strong influence on its electronic excitations due to its small size compared to the characteristic length scale of low energy electronic excitations. Combined with the particular shape of the electronic band structure of graphene, carbon nanotubes are ideal quantum wires. The conduction and the valence band of the graphene touch on the 6 corners (K points) of the Brillouin zone [3.140]. By rolling the graphene to form a tube, new periodic boundary conditions for the electronic wave functions superimpose, which give rise to one-dimensional sub-bands: $C_n K = 2q$ where q is an integer and C_n the vector $na_1 + ma_2$ characteristic of the diameter and the helicity of the tube (see Sect. 3.1). If one of these sub-bands passes through one of the K points, the nanotube will be metallic, otherwise it will be semiconductor with a gap inversely proportional with the diameter. For a tube with a diameter of 3 nm, the gap falls in the range of the thermal energy at room temperature. As pointed out in Sect. 3.1 already, knowing (n, m) then allows one to predict whether or not the tube exhibits a metallic behavior. To summarize, we can say that the electronic structure of SWNTs depends both on the orientation of the honeycomb lattice with respect to the tube axis and the radius of curvature imposed to the bent graphene sheet. This explains why properties of MWNTs quickly become no different from regular, polyaromatic solids as the number of walls (graphenes) increases, since the radius of curvature increases meanwhile. In addition, the conduction occurs essentially through the external tube (for c-MWNTs), but the interactions with the internal coaxial tubes may make the electronic properties vary. For small diameter MWNTs exhibiting a low number of walls, typically two (DWNTs), the relative lattice orientation of the two superimposed graphenes remains determinant, and the resulting overall electronic behavior can either be metallic or semiconductor upon structural considerations [3.141]. Another consequence, valid for any nano-sized carbon nanotube whatever the number of walls, is that applying stresses to the tube is also likely to change its electronic behavior, as a consequence of the variation brought to the position of the sub-bands with respect to the K points of the Brillouin zone [3.142].

The details of electronic properties of SWNTs are not well understood yet, and numerous theoretical and experimental works have revealed fascinating effects [3.143]. An assembly of agglomerated tubes (ropes) increases the complexity. Moreover, investigating the electron properties of a single SWNT requires one to characterize and control the properties of the electrical contacts. Likewise, the interaction with the substrate influence the bulk transport properties a lot when SWNTs embedded in a medium (e.g., a composite) are considered. The conduction of charge carriers in metallic SWNTs is thought to be ballistic (i. e., independent from length) due to the expected small number of defects [3.144–146] with a predicted electric conductance twice the fundamental conductance unit $G_0 = 4e/h$ because of the existence of two propagating modes. Because of the reduced scattering, metallic SWNTs can transport huge current densities (max 10^9 A/cm^2) without being damaged, i. e. about three orders of magnitude higher than in Cu. On the other hand, in a one-dimensional system, electrons often localize due to structural defects or disorder. In case the contact resistance is too high, a tunnel barrier is formed, and the charge transport is dominated by tunneling effects. Several transport phenomena were reported in the literature of this regime: weak localization due to quantum interferences of the electronic wave functions that leads to an increase of the resistivity [3.147–149], Coulomb blockade at low temperature that characterizes by conductance oscillations as the gate voltage increases [3.148], superconductivity induced by superconductor contacts [3.150], or spin polarization effects induced by ferromagnetic contacts [3.151]. Furthermore, due to enhanced Coulomb interactions, one-dimensional metals are expected to show drastic changes in the density of states at the Fermi level and are described by a Luttinger liquid [3.148]. This behavior is expected to result in the variation of conductance vs. temperature that follows a power law, with a zero conductance at low temperature.

As mentioned previously, SWNTs are model systems to study one-dimensional charge transport phenomena. Due to the of mesoscopic dimension of the morphology, the one-dimensional structure of the nanotube has strong singularities in the electronic density of states (DOS) that fall in the energy range of visible light. As a consequence, visible light is strongly absorbed. It has been observed that flash illumination with a broadband light can lead to spontaneous burning of a macroscopic sample of agglomerated (i. e., ropes) carbon nanotubes in air and room temperature [3.152].

As a probable consequence of both the small number of defects (at least the kind of defects that oppose phonon transport) and the cylindrical topography, SWNTs exhibit a large phonon mean free path, which results in a high thermal conductivity. The thermal conductivity of SWNTs is comparable to that of a single, isolated graphene layer or high purity diamond [3.153] or possibly higher (~ 6,000 W/mK).

Finally, carbon nanotubes may also exhibit a positive or negative magneto-resistance depending on the current, the temperature, and the field, whether they are MWNTs [3.154] or SWNTs [3.149].

3.4.5 Mechanical Properties

While tubular nano-morphology is also observed for many two-dimensional solids, carbon nanotubes are unique through the particularly strong threefolded bonding (sp^2 hybridization of the atomic orbitals) of the curved graphene sheet, which is stronger than in diamond (sp^3 hybridization) as revealed by their difference in C−C bond length (0.142 vs. 0.154 nm for graphene and diamond respectively). This makes carbon nanotubes – SWNTs or c-MWNTs – particularly stable against deformations. The tensile strength of SWNTs can be 20 times that of steel [3.155] and has actually been measured equal to ~ 45 GPa [3.156]. Very high tensile strength values are also expected for ideal (defect-free) c-MWNTs, since combining perfect tubes concentrically is not supposed to be detrimental to the overall tube strength, provided the tube ends are well capped (otherwise, concentric tubes could glide relative to each other, inducing high strain). Tensile strength values as high as ~ 150 GPa have actually been measured for perfect MWNTs from electric arc [3.157], although the reason for such a high value compared to that measured for SWNTs is not clear. It probably reveals the difficulty in carrying out such measurements in a reliable manner. At least, flexural modulus, for perfect MWNTs should logically exhibit higher values than SWNTs [3.155], with a flexibility that decreases as the number of walls increases. On the other hand, measurements performed on defective MWNTs obtained from CCVD gave a range of 3–30 GPa [3.158]. Tensile modulus, also, reaches the highest values ever, 1 TPa for MWNTs [3.159], and possibly even higher for SWNTs, up to 1.3 TPa [3.160, 161]. Figure 3.23 illustrates how spectacularly defect-free carbon nanotubes could revolutionize the current panel of high performance fibrous materials.

3.4.6 Reactivity

The chemical reactivity of graphite, fullerenes, and carbon nanotubes exhibits some common features. Like any small object, carbon nanotubes have a large surface with which they can interact with their environment (see Sect. 3.4.1). It is worth noting, however, that the chemistry of nanotubes chemistry differs from that of regular polyaromatic carbon materials because of their unique shape, small diameter, and structural properties. Compared to graphite, perfect SWNTs have no chemically active dangling bonds (the reactivity of polyaromatic solids is known to occur mainly through graphene edges). Compared to fullerenes, the ratio of "weak" sites (C−C bonds involved in heterocycles) over strong sites (C−C bonds between regular hexagons) is only slightly different from 0 for ideally perfect tubes (as opposed to 1 in C_{60} fullerenes – C_{60} molecules have 12 pentagons (therefore accounting for $5 \times 12 = 30$ C−C bonds) and 20 hexagons, each of them having three C−C bonds not involved in an adjacent pentagon but shared with a neighboring hexagon (therefore accounting for $20 \times 3 \times 1/2 = 30$ C−C bonds involved in hexagons only). Although graphene faces are chemically relatively inert, the radius of curvature imposed on the graphene in nanotubes enforces the three formerly planar C−C bonds characteristic of the genuine sp^2 hybridization to accept distortions in bond angles that make them closer and closer to the situation of three of the four C−C bonds in diamond (characteristic of the genuine sp^3 hybridization) as the radius of curvature decreases. Even though it is not enough to bring a genuine chemical reactivity to the carbon atoms, a consequence is to consider that either nesting sites are created at the concave sur-



Fig. 3.23 Plot of the tensile strength versus tensile modulus for current fibrous materials, as compared to SWNTs. *Large circles* are PAN-based carbon fibers, which include the highest tensile strength fiber available on the market (T1000 from Torayca); *Triangles* are pitch-based carbon fibers, which include the highest tensile modulus fiber on the market (K1100 from Amoco)

face, or strong physisorption sites are created above each carbon atom of the convex surface, both with a bonding efficiency that increases as the nanotube diameter decreases.

As already pointed out in Sect. 3.1, the chemical reactivity of SWNTs (and c-MNWTs) is supposed to come mainly from the caps, since they contain six pentagons each, as opposed to the tube body, which supposedly contains hexagons only. Indeed, oxidizing treatments applied to carbon nanotubes (air oxidation, wet-chemistry oxidation) are known to open the nanotube tips rather selectively [3.162]. But the ability of SWNTs to be opened by oxidation methods then filled with foreign molecules such as fullerenes (see Sect. 3.5) reveals the occurrence of side defects [3.14], whose identification and occurrence were discussed then proposed to be an average of one Stone–Wales defect every 5 nm along the tube length, involving an amount of about 2% of the carbon atoms for the example of a regular (10,10) SWNT [3.163] – a Stone–Wales defect is made of four adjacent heterocycles, two pentagons and two heptagons, displayed by pairs in opposition. Such a defect actually allows localized double bonds to be formed between the carbon atoms involved in the defect (instead of the electrons participating to the delocalized electron cloud above the graphene as usual, enhancing the chemical reactivity, e.g. toward chlorocarbenes [3.163]). This means that the overall chemical reactivity of carbon nanotubesshould strongly depend on the way they are synthesized. For example, SWNTs prepared by the arc-discharge method are supposed to contain fewer structural defects compared to CCVD-synthesized SWNTs, which have a higher chemical reactivity. Of course, the reactivity of h-MWNT-type nanotubes is intrinsically higher, due to the occurrence of accessible graphene edges at the nanotube surface.

3.5 Carbon Nanotube-Based Nano-Objects

3.5.1 Hetero-Nanotubes

Hetero-nanotubes are defined here as carbon nanotubes whose carbon atoms, part or all of them, are substituted with another element while the overall honeycomb lattice-based graphene structure is maintained. Elements involved are, therefore, boron and/or nitrogen. Benefits can be new behaviors (e.g., BN nanotubes are electrical insulators), improved properties (e.g., regarding the resistance to oxidation), or better control of the properties. One current challenge is actually to control the processing so that the desired SWNT structure is selectively synthesized (metallic or semiconductor). In this regard, it was demonstrated that substituting some C atoms by N or B atoms lead to SWNTs whose electrical behavior is systematically metallic [3.164, 165].

Some examples of hetero-nanotubes, though mainly MWNTs, are found in literature, whose hetero-atom involved is generally nitrogen due to the ease of introducing some gaseous or solid nitrogen and/or boron containing species (e.g., N_2, NH_3, BN, HfB_2) in existing MWNT synthesis devices [3.164, 166] until complete substitution of carbon [3.167, 168]. An amazing result of such attempts to synthesize hetero-MWNTs was the subsequent formation of “multilayered” c-MWNTs, i. e. MWNTs whose constituting coaxial tubes were alternatively made of carbon graphenes and boron nitride graphenes [3.169]. On the other hand, examples of hetero-SWNTs are few. But the synthesis of B- or N-containing SWNTs has been recently reported [3.165, 170].

3.5.2 Hybrid Carbon Nanotubes

Hybrid carbon nanotubes are here defined as carbon nanotubes, SWNTs or MWNTs, whose inner cavity has been filled, partially or entirely, by foreign atoms, molecules, compounds, or crystals. Such hybrids are thereby noted as X@SWNT (or X@MWNT, if appropriate, where X is the atom, molecule, etc. involved) [3.171].

Motivation

Why filling carbon nanotubes? The very small inner cavity of nanotubes is an amazing tool to prepare and study the properties of confined nanostructures of any nature, such as salts, metals, oxides, gases, or even discrete molecules like C_{60}, for example. Because of the almost one-dimensional structure of carbon nanotubes (specifically considering SWNTs), different physical and/or chemical properties can be expected for the encapsulated foreign materials or possibly for the overall hybrid materials. Indeed, when the volume available inside a carbon nanotube is small enough, the foreign material can be made mainly of “surface atoms” of reduced coordinence. The overall former motivation was then to tentatively form metal nanowires likely to be interesting for electronic applications (quantum wires). Metals were the preferred fillers, and nanotubes were mostly considered merely as nano-molds, likely to be removed afterward. But it is likely that the removal of the SWNT "container" to liberate the confined one-dimensional structure may destroy or at least transform it because of the stabilizing effect brought by the interactions with the nanotube wall.

Filling nanotubes while they grow (in situ filling) was one of the pioneering methods. In most cases, however, the filling step is separated from the step of synthesis of the nanotubes. Three methods can then be distinguished: (a) wet chemistry procedures, and physical procedures, involving (b) capillarity filling by a molten material or (c) filling by a sublimated material.

Generally speaking, the estimation of the filling rate is problematic and most of the time is taken merely from the TEM observation, without any statistics on the number of tubes observed. Moreover, as far as SWNTs are concerned, the fact that the nanotubes are gathered into bundles makes difficult the observation of the exact number of filled tubes, as well as the estimation of the filled length for each tube.

Filling carbon nanotubes with materials that could not have been introduced directly is also possible. This can be accomplished by first filling the nanotubes with an appropriate precursor (i. e., able to sublime, or melt, or solubilize) that will later be transformed by chemical reaction or by a physical interaction such as electron beam irradiation, for example [3.172]. In the case of secondary chemical transformation, the reduction by H_2 is the most frequently used to obtain nanotubes filled with metals [3.173]. Sulfides can be obtained as well by using H_2S as reducing agent [3.173].

Because the inner diameter of SWNTs is generally smaller than that of MWNTs, it is more difficult to fill them, and the driving forces involved in the phenomena are not yet totally understood (see the review paper by [3.163]). Consequently, more than one hundred articles dealing with filled MWNTs were already published by the time this chapter was written. We, therefore, did not attempt to review all the works. We chose to cite the pioneering works, then to focus on the more recent works dealing with the more challenging topic of filling SWNTs.

In Situ Filling Method

Most of the first hybrid carbon nanotubes ever synthesized were directly obtained in the course of their processing. This concerns only MWNTs, prepared by the arc-discharge method in its early hours, for which the filling materials were easily introduced in the system by drilling a central hole in the anode and filling it with the heteroelements. First attempts were all reported the same year [3.174–178], with elements such as Pb, Bi, YC_2, TiC, etc. Later on, *Loiseau* et al. [3.179] showed that MWNTs could also be filled to several μm in length by elements such as Se, Sb, S, and Ge, but only as nanoparticles with elements such as Bi, B, Al and Te. Sulfur was suggested to play an important role during the in situ formation of filled MWNTs by arc-discharge [3.180]. This technique is no longer the preferred one because of the difficulty in controling the filling ratio and yield and in achieving mass production.

Wet Chemistry Filling Method

The wet chemistry method requires the opening of the nanotubes tips by chemical oxidation prior to the filling step. This is generally obtained by refluxing the nanotubes in diluted nitric acid [3.181–183], although other oxidizing liquid media may work as well, e.g. $[HCl + CrO_3]$ [3.184] or chlorocarbenes formed from the photolytic dissociation of $CHCl_3$ [3.163] as a rare example of a nonacidic liquid route for opening SWNTs. If a dissolved form (salt, oxide, etc.) of the desired metal is meanwhile introduced during the opening step, some of it will get inside the nanotubes. An annealing treatment (after washing and drying of the treated nanotubes) may then lead to the oxide or to the metal, depending on the annealing atmosphere [3.162]. Although the wet chemistry method looked promising because a wide variety of materials can be introduced within nanotubes this way, and because it operates at temperature not much different from room temperature, attention has to be paid to the oxidation method that has to be carried out as the first steps. The damages brought to the nanotubes by severe treatments (e.g., nitric acid) make them improper for use with SWNTs. Moreover, the filling yield is not very important, as a probable consequence of the presence of the solvent molecules that also enter the tube cavity, and the subsequent filled lengths rarely exceed 100 nm. Recent results have been obtained, however, using wet chemistry filling by *Mittal* et al. [3.184] who have filled SWNTs ropes by CrO_3 with an average yield of $\sim 20\%$.

Molten State Filling Method

The physical method involving a liquid (molten) phase is more restrictive, first, because some materials may start decomposing when they melt, and second because the melting point has to be compatible with the nanotubes, i. e. thermal treatment temperature should remain below the temperature of transformation or damaging of the nanotubes. Because the filling is occurring by capillarity, the surface tension threshold of the molten material was found to be 100–200 $\mathrm{N/cm^2}$ [3.185]. But this threshold was proposed for MWNTs, whose inner diameters (5–10 nm) are generally larger than those of SWNTs (1–2 nm). In a typical filling experiment, the MWNTs are closely mixed with the desired amount of filler by gentle grinding, and the mixture is then vacuum-sealed in a silica ampoule. The ampoule is then slowly heated to a temperature above the melting point of the filler, then is slowly cooled. The use of this method does not require any opening of the nanotubes prior to the heat treatment. The mechanism of nanotube opening is not yet established clearly, but it is certainly related to the chemical aggressivity of the molten materials toward carbon and more precisely toward graphene defects in the tube structure (see Sect. 3.4.4).

Most of the works on SWNTs involving this method were performed by Sloan and coworkers at Oxford University [3.187], although other groups followed the same procedure [3.86, 181, 183]. Precursors to fill the nanotubes were mainly metals halides. Although little is known yet about the physical properties of halides crystallized within carbon nanotubes, the crystallization itself of molten salts within small diameter SWNTs has been studied in detail, revealing a strong interaction between the one-dimensional crystals and the surrounding graphene wall. For example, *Sloan* et al. [3.188] have described two-layer 4 : 4 coordinated KI crystals formed within SWNTs of around 1.4 nm diameter. These two-layer crystals are "all surface" and have no "internal" atoms. Significant lattice distortions occur compared to the bulk structure of KI, where the normal coordinence is 6 : 6 (meaning that each ion is surrounded by six identical closer neighbors). Indeed, the distance between two ions across the SWNT capillary is 1.4 times the same distance along the tube axis. This denotes an accommodation of the KI crystal to the confined space provided by the inner nanotube cavity in the constrained crystal direction (across the tube axis). This implies that the interactions between the ions and the surrounding carbon atoms are strong. The volume dimension available within the nanotubes thus somehow controls the crystal structure of inserted materials. For instance, the structure and orientation of encapsulated $\mathrm{PbI_2}$ crystals inside their capillaries were found to arrange in different ways inside SWNTs and DWNTs, with respect to the diameter of the confining nanotubes [3.186]. In the case of SWNTs, most of the obtained encapsulated one-dimensional $\mathrm{PbI_2}$ crystals exhibit a strong preferred orientation with their (110) planes aligning at an angle of ca. 60° to the SWNT axes as shown in Fig. 3.24a and 3.24b. Due to the extremely small diameter of the nanotube capillaries, individual crystallites are often only a few polyhedral layers thick, as outlined in Fig. 3.24d to 3.24h. As a result of lattice terminations enforced by capillary confinement, the edging polyhedra must be of reduced coordination, as indicated in Fig. 3.24g and 3.24h. In the case of $\mathrm{PbI_2}$ formed inside DWNTs, similar crystal growth behavior was generally observed to occur in narrow nanotubes with diameters comparable to that of SWNTs. As the diameter of the encapsulating capillaries increases, however, different preferred orientations are frequently observed (Fig. 3.25). In this example, the $\mathrm{PbI_2}$ crystal is oriented with the [121] direction parallel to the direction of the electron beam (Fig. 3.25a to 3.25d). If the $\mathrm{PbI_2}$@DWNT hybrid is viewed "side-on" (as indicated by the arrow in Fig. 3.25e) polyhedral slabs are seen to arrange along the capillary, oriented at an angle of ca. 45° with respect to the tubule axis.



Fig. 3.24 HRTEM images and corresponding structural model for $\mathrm{PbI_2}$ filled SWNTs (from [3.186])

Sublimation Filling Method

This method is even more restrictive than the previous one, since it is applicable only to a very limited number of compounds due to the requirement for the filling materials to sublimate within the temperature range of thermal stability of the nanotubes. Examples are therefore few. Actually, except for an attempt to fill SWNTs with $\mathrm{ZrCl_4}$ [3.189], the only example published so far is the formation of $\mathrm{C_{60}}$@SWNT (whose popular nickname is "peapods"), reported for the first time in 1998 [3.190], where regular ∼ 1.4 nm large SWNTs are filled with C_{60} fullerene molecule chains (Fig. 3.26a). Of course, the process requires a pre-opening of the SWNTs by some method, as discussed previously, typically either acid attack [3.191] or heat-treatment in air [3.192]. Then the opened SWNTs are put into a sealed glass tube together with fullerene powder and placed into a furnace heated above the sublimation temperature for fullerite ($>\sim 350\,°\mathrm{C}$). Since there is no limitation related to Laplace's law or the presence of solvent since only gaseous molecules are involved, filling efficiency may actually reach ∼ 100% [3.192].

Remarkable behaviors have been revealed since then, such as the ability of the C_{60} molecules to move freely within the SWNT cavity (Fig. 3.26b and 3.26c) upon random ionization effects from electron irradiation [3.193], or to coalesce into 0.7 nm large inner elongated capsules upon electron irradiation [3.194], or into a 0.7 nm large nanotube upon subsequent thermal treatment above 1,200 °C [3.193, 195]. Annealing of C_{60}@SWNT materials may thus appear as an efficient way to produce DWNTs with nearly constant inner (∼ 0.7 nm) and outer (∼ 1.4 nm) diameters. DWNTs produced this way are actually the smallest MWNTs synthesized so far.

Based on the successful synthesis of so-called endofullerenes previously achieved [3.13], further development of the process has recently led to the synthesis of more complex nanotube-based hybrid materials such as La_2@C_{80}@SWNTs [3.196], Gd@C_{82}@SWNTs [3.197], or $Er_xSc_{3-x}N$@C_{80}@SWNT [3.198] among other examples. These provide even more extended perspective regarding the potential applications of peapods, which are still being investigated.

Finally the last example to cite is the successful attempt to produce peapods by a related method, by using accelerated fullerene ions (instead of neutral gaseous molecules) to enforce the fullerenes to enter the SWNT structure [3.199].



Fig. 3.25 HRTEM images (experimental and simulations), and corresponding structural model for a PbI_2 filled double-wall carbon nanotube (from [3.186])



Fig. 3.26a–c HRTEM images of **(a)** example of five regular C_{60} molecules encapsulated together with two higher fullerenes (C_{120} and C_{180}) as distorted capsules (*on the right*) within a regular 1.4 nm diameter SWNT. **(a)–(c)** Example of the diffusion of the C_{60}-molecules along the SWNT cavity. The time between each image of the sequence is about 10 s. The fact that nothing occurs between **(a)** and **(b)** reveals the randomness of the ionisation events generated by the microscope electron beam and assumed to be responsible for the molecule displacement

3.5.3 Functionalized Nanotubes

Based on the reactivity of carbon nanotubes as discussed in Sect. 3.4.6, the functionalization reactions can be divided into two main groups. One is based on the chemical oxidation of the nanotubes (tips, structural defects) leading to carboxylic, carbonyl, and/or hydroxyl functions. These functions are then used for additional reactions, to attach oligomeric or polymeric functional entities. The second group is based on direct addition to the graphitic-like surface of the nanotubes (i. e. without any intermediate step). Examples of the latter reactions include oxidation or fluorination (an important first step for further functionalization with other organic groups). Properties and applications of functionalized nanotubes have been reviewed recently [3.200].

Oxidation of Carbon Nanotubes

Carbon nanotubes are often oxidized and therefore opened before chemical functionalization to increase their chemical reactivity (creation of dangling bonds). Chemical oxidation of nanotubes is mainly achieved using either wet chemistry or gaseous oxidants such as oxygen (typically air) or CO_2. Depending on the synthesis process, the oxidation resistance of the nanotubes can vary. When oxidation is carried out through gas phases, thermo-gravimetric analysis (TGA) is of great use to determine at which temperature the treatment should be applied. It is important to know that TGA accuracy increases as the heating rate diminishes, while the literature often provides TGA analyses obtained in nonoptimized conditions, leading to overestimated oxidation temperatures. The presence of catalyst remnants (metals, more rarely oxides), the type of nanotubes (SWNTs, c-MWNTs, h-MWNTs), and the oxidizing agent (air, O_2 is an inert gas, CO_2, etc.) as well as the flow rate used make difficult the comparison of published results. It is generally agreed, however, that amorphous carbon burns first, followed by SWNTs and then multiwall materials (shells, MWNTs), even if TGA is often unfortunately not able to clearly separate the different oxidation steps. The more common method used for nanotube oxidation is that of aqueous solutions of oxidizing reagents. The main one is nitric acid, either concentrated or diluted (around 3 moles per liter in most cases), but oxidants such as potassium dichromate ($K_2Cr_2O_7$), hydrogen peroxide (H_2O_2), or potassium permanganate ($KMnO_4$) are very often used as well. HCl, like HF, do not damage nanotubes because these acids are not oxidizing.

Functionalization of Oxidized Carbon Nanotubes

Carboxylic groups located at the nanotube tips can be coupled with different chemical groups. Oxidized nanotubes are usually reacted with thionyl chloride ($SOCl_2$) to generate the acyl chloride, even if a direct reaction is theoretically possible with alcohols or amines, for example. Reaction of SWNTs with octadecylamine (ODA) was reported by *Chen* et al. [3.201] after reaction of oxidized SWNTs with $SOCl_2$. The functionalized SWNTs have substantial solubility in chloroform ($CHCl_3$), dichloromethane (CH_2Cl_2), aromatic solvents, and carbon bisulfide (CS_2). Many other reactions between functionalized nanotubes (after reaction with $SOCl_2$) and amines have been reported in the literature and will not be reviewed here. Noncovalent reactions between the carboxylic groups of oxidized nanotubes and octadecylammonium ions are possible [3.202], providing solubility in tetrahydrofuran (THF) and CH_2Cl_2. Functionalization by glucosamine using similar procedures [3.203] allowed the water solubilization of SWNTs, which is of special interest when considering biological applications of functionalized nanotubes. Functionalization with lipophilic and hydrophilic dendra (with long alkyl chains and oligomeric poly(ethyleneglycol) groups) has been achieved by amination and esterification reactions [3.204], leading to solubility of the functionalized nanotubes in hexane, chloroform, and water. It is interesting to note that in the latter case, the functional groups could be removed just by modifying the pH of the solution (base- and acid-catalyzed hydrolysis reaction conditions, [3.205]). A last example is the possible interconnection of nanotubes via chemical functionalization. This has been recently achieved by *Chiu* et al. [3.206] using the already detailed acyl chloride way and a bifunctionalized amine to link the nanotubes by the formation of amide bonds.

Sidewall Functionalization of Carbon Nanotubes

The covalent functionalization of the nanotube walls is possible by means of fluorination reactions. It was first reported by *Mickelson* et al. [3.207], with F_2 gas (the nanotubes can then be defluorinated, if required, with anhydrous hydrazine). As recently reviewed by *Khabashesku* et al. [3.208], it is then possible to use these fluorinated nanotubes to carry out subsequent derivatization reactions. Thus, sidewall-alkylated nanotubes can be prepared by nucleophilic substitution (Grignard synthesis or reaction with alkyllithium precursors [3.209]). These alkyl sidewall groups can be removed by air oxidation. Electrochemical addition of aryl radicals (from the reduction of aryl diazonium salts) to nanotubes has also been reported by *Bahr* et al. [3.210]. Functionalization of the nanotube external wall by cycloaddition of nitrenes, addition of nuclephilic carbenes, or addition of radicals has been described by *Holzinger* et al. [3.211]. Electrophilic addition of dichlorocarbene to SWNTs occurs by reaction with the deactivated double bonds in the nanotube wall [3.212]. Silanization reactions are another way to functionalize nanotubes, although only tested with MWNTs. *Velasco-Santos* et al. [3.213] have reacted oxidized MWNTs with an organosilane ($RsiR'_3$, with R being an organo-functional group attached to silicon) and obtained organo-functional groups attached to the nanotubes by silanol groups.

Noncovalent sidewall functionalization of nanotubes is important because the covalent bonds are associated with changes from sp^2 to sp^3 in the hybridization of the carbon atoms involved, which corresponds to a loss of the graphite-like character. As a consequence, physical properties of functionalized nanotubes, specifically SWNTs, may be modified. One possibility for achieving noncovalent functionalization of nanotubes is to wrap the nanotubes in a polymer [3.214], which allows their solubilization (thus improving the processing possibilities) while preserving their physical properties.

Finally, it is worth keeping in mind that all these chemical reactions are not specific to nanotubes and may occur to most of the carbonaceous impurities present in the raw materials. This makes difficult the characterization of the functionalized samples and thus requires one to perform the experiments starting with very pure carbon nanotube samples, which is unfortunately not always the case for the results reported in the literature. On the other hand, purifying the nanotubes to start with may also bias the functionalization experiments since purification requires chemical treatments. But the demand for such products does exist already, and purified then fluorinated SWNTs can be found on the market at $ 900/g (Carbon Nanotechnologies Inc., 2003).

3.6 Applications of Carbon Nanotubes

Carbon nanotubes can be inert and can have a high aspect ratio, high tensile strength, low mass density, high heat conductivity, large surface area, and versatile electronic behavior including high electron conductivity. While these are the main characteristics of the properties for individual nanotubes, a large number of them can form secondary structures such as ropes, fibers, papers, thin films with aligned tubes, etc., with their own specific properties. The combination of these properties makes them ideal candidates for a large number of applications provided their cost is sufficiently low. The cost of carbon nanotubes depends strongly on both the quality and the production process. High quality single shell carbon nanotubes can cost 50–100 times more than gold. But synthesis of carbon nanotubes is constantly improving, and sale prizes fall by 50% per year. Application of carbon nanotubes is therefore a very fast moving area with new potential applications found every year, even several times per year. Making an exhaustive list is again a challenge we will not take. Below are listed applications considered "current" (Sect. 3.6.1) either because already marketed, or because up-scaling synthesis is being processed, or because prototypes are currently developed by profit-based companies. Other applications are said to be "expected" (Sect. 3.6.2).

3.6.1 Current Applications

High mechanical strength of carbon nanotubes makes them a near to ideal force sensor in scanning probe microscopy (SPM) with a higher durability and the ability to image surfaces with a high lateral resolution, the latter being a typical limitation of conventional force sensors (ceramic tips). The idea was first proposed and experimented by Dai et al. [3.77] using c-MWNTs. It was extended to SWNTs by *Hafner* et al. [3.215], since small diameters of SWNTs were supposed to bring higher resolution than MWNTs due to the extremely short radius of curvature of the tube end. But commercial nanotube-based tips (e.g., Piezomax, Middleton, WI, USA) use MWNTs for processing convenience. It is also likely that the flexural modulus of SWNTs is too low and therefore induces artifacts affecting the lateral resolution when scanning a rough surface. On the other hand, the flexural modulus of c-MWNTs is supposed to increase with the number of walls, but the radius of curvature of the tip meanwhile increases.

Near-Field Microscope Probes

SWNT or MWNT, such nanotube-based SPM tips also offer the perspective of being functionalized, in the prospect of making selective images based on chemical discrimination by "chemical force microscopy" (CFM). Chemical function imaging using functionalized nanotubes represents a huge step forward in CFM because the tip can be functionalized very accurately (ideally at the very nanotube tip only, where the reactivity is the highest), increasing the spatial resolution. The interaction between chemical species present at the end of the nanotube tip and a surface containing chemical functions can be recorded with great sensitivity, allowing the chemical mapping of molecules [3.216, 217].

Today the cost of nanotube-based SPM tips is in the range of $ 200/tip. Such a high cost is explained both



Fig. 3.27 Scanning electron microscopy image of a carbon nanotube (MWNT) mounted onto a regular ceramic tip as a probe for atomic force microscopy

by the processing difficulty, which ideally requires one to grow or mount a single MWNT in the appropriate direction at the tip of a regular SPM probe (Fig. 3.27), and by the need to individually control the tip quality. Such a market has been estimated at ∼ $ 20 M/year.

Field Emission-Based Devices

Based on a pioneering work by *de Heer* et al. [3.218], carbon nanotubes have been demonstrated to be efficient field emitters and are currently being incorporated in several applications, including flat panel display for television sets or computers (whose a first prototype was exhibited by Samsung in 1999) or any devices requiring an electron producing cathode, such as X-ray sources. The principle of a field-emission-based screen is demonstrated in Fig. 3.28a. Briefly, a potential difference is brought between emitting tips and an extraction grid so that electrons are taking out from the tips and sent onto an electron sensitive screen layer. Replacing the glass support and protection of the screen by some polymer-based material will even allow the develope of flexible screens. As opposed to regular (metallic) electron emitting tips, the structural perfection of carbon nanotubes allows higher electron emission stability, higher mechanical resistance, and longer life time. First of all, it allows energy savings since it needs lower (or no) heating temperature of the tips and requires much lower threshold voltage. As an illustration for the latter, producing a current density of 1 mA/cm^2 is possible for a threshold voltage of 3 V/µm with nanotubes, while it requires 20 V/µm for graphite powder and 100 V/µm for regular Mo or Si tips. The subsequent reductions in cost and energy consumption are estimated at 1/3 and 1/10 respectively. Generally speaking, the maximum current density obtainable ranges between 10^6 A/cm^2 and 10^8 A/cm^2 depending on the nanotubes involved (e.g., SWNT or MWNT, opened or capped, aligned or not) [3.219–221]. Although nanotube side-walls seem to emit as well as nanotube tips, many works have dealt (and are still dealing) with growing nanotubes perpendicular to the substrate surface as regular arrays (Fig. 3.28b). Besides, using SWNTs instead of MWNTs does not appear necessary for many of these applications when they are used as bunches. On the other hand, when considering single, isolated nanotubes, SWNTs are generally less preferable since they allow much lower electron doses than do MWNTs, although they are likely meanwhile to provide an even higher coherent source (an useful feature for devices such as electron microscopes or X-ray generators).

The market associated with this application is huge. With such major companies involved as Motorola, NEC, NKK, Samsung, Thales, Toshiba, etc., the first commercial flat TV sets and computers using nanotube-based screens are about to be seen in stores, and companies such as Oxford Instruments and Medirad are about to commercialize miniature X-ray generators for medical applications on the basis of nanotube-based cold cathodes developed by Applied Nanotech Inc.



Fig. 3.28 **(a)** Principle of a field-emitter-based screen. **(b)** Scanning electron microscope image of a nanotube-based emitter system (*top view*). *Round dots* are MWNT tips seen through the holes corresponding to the extraction grid. By courtesy of *Legagneux* (Thales Research & Technology, Orsay, USA)

Chemical Sensors

The electrical conductance of semiconductor SWNTs was recently demonstrated to be highly sensitive to the change in the chemical composition of the surrounding atmosphere at room temperature, due to the charges transfer between the nanotubes and the molecules from the gases adsorbed onto the SWNT surface. It has also been shown that there is a linear dependence between the concentration of the adsorbed gas and the difference in electrical properties, and that the adsorption is reversible. First tries involved NO_2 or NH_3 [3.222] and O_2 [3.223]. SWNT-based chemical NO_2 and NH_3 sensors are characterized by extremely short response time (Fig. 3.29), thus being different from conventionally used sensors [3.222, 224]. High sensitivity toward water or ammonia vapors has been measured on SWNT-SiO_2 composite [3.225]. This study indicated the presence of p-type SWNTs dispersed among the predominant metallic SWNTs, and that chemisorption of gases on the surface of the semiconductor SWNTs is responsible for the sensing action. The determination of CO_2 and O_2 concentrations on SWNT-SiO_2 composite has also been reported [3.226]. By doping nanotubes with palladium nanoparticles, *Kong* et al. [3.227] have also shown that the modified material could reveal the presence of hydrogen up to 400 ppm whereas the as-grown material was totally ineffective.

Generally speaking, the sensitivity of the new nanotube-based sensors is three orders of magnitude higher than that of standard solid state devices. In addition, the interest in using nanotubes as opposed to current sensors is the simplicity and the very small size of the system in which they can be placed, the fact that they can operate at room temperature, and their selectivity, which allows a limited number of sensor device architectures to be built for a variety of industrial purposes, while the current technology requires a large diversity of devices based on mixed metal oxide, opto-mechanics, catalytic beads, electrochemistry, etc. The market opportunity is expected to be $ 1.6 billion by 2006, including both the biological area and the chemical industrial area. Nanotube-based sensors are currently developed in both large and small companies, such as Nanomix (USA), for example.



Fig. 3.29a,b Demonstration of the ability of SWNTs in detecting molecule traces in inert gases. **(a)** Increase in a single SWNT conductance when 20 ppm of NO_2 are added to an argon gas flow. **(b)** Same with 1% NH_3 added to the argon gas flow (from [3.222])

Catalyst Support

Carbon materials are attractive supports in heterogeneous catalytic processes due to their ability to be tailored to specific needs: indeed, activated carbons are already currently employed as catalyst supports because of their high surface area, their stability at high temperatures (under not oxidizing atmosphere), and the possibility of controlling both their porous structure and the chemical nature of their surface [3.228, 229]. The attention has been brought to nano-sized fibrous morphologies of carbon that appeared during the last decade, showing novel interesting potentialities as supports [3.230]. Carbon nanofibers (also improperly called graphite nanofibers) and carbon nanotubes have been used successfully and shown to present, as catalyst-supporting materials, properties superior to that of such other regular catalyst-supports as activated carbon, soot, or graphite [3.231]. The use of graphite nanofibers as a direct catalyst for oxidative dehydrogenation has also been reported [3.232].

The morphology and size of carbon nanotubes, especially since they do present huge lengths vs. diameters (= aspect ratio), can play a significant role in catalytic applications due to their ability to disperse catalytically active metal particles. Their electronic properties are also of primary importance [3.233] since this conductive support may be exerting electronic perturbation as well as geometric constraint on the dispersed metal particles. A recent comparison between the interaction of transition metal atoms with carbon nanotube walls and that with graphite indicates major differences in bonding sites, magnetic moments, and charge-transfer direction [3.234]. Thus the possibility of strong metal-support interaction has to be taken into account. Their mechanical strength is also important and makes them resistant to attrition in view of recycling. Their external or internal surface presents strong hydrophobicity and strong adsorption ability toward organic molecules. Finally, for MWNT-based catalyst-supports, the relatively high surface area and the absence of microporosity (i. e., pores < 2 nm) associated with a high meso- and macropore volume (see Sect. 3.4.3) result in significant improvements of the catalytic activity, in the case of liquid-phase reactions when compared to catalysts supported on activated carbon. With nanotube supports, the mass transfer limitation of the reactants to the active sites is actually prevented due to the absence of microporosity, and the apparent contact time of the products with the catalyst is diminished, leading to more active and more selective catalytic effects.

The most widely used technique to prepare carbon nanotube-supported catalysts is the incipient wetness impregnation, in which the purified support is impregnated with a solution of the metal precursor, then dried, calcinated and/or reduced in order to obtain metal particles dispersed on the support. The chemical treatment and/or the modification of the carbon nanotube surface was found to be a useful tool to control its hydrophobic or hydrophilic character [3.236]. A strong metal/support interaction can thus be expected from the occurrence of functionalized groups created by the oxidation of the support surface, resulting in smaller particle sizes [3.237]. A more sophisticated technique to achieve the grafting of metal particles onto carbon nanotubes consists of functionalizing the outer surface of the tubes and then performing a chemical reaction with a metal complex, thus resulting in a good dispersion of the metallic particles (Fig. 3.30) [3.235].

Selected examples of some carbon nanotube-based catalysts together with the related preparation routes and catalytic activities are listed in Table 3.4.

The market is huge for this application since it most often concerns the "heavy" chemical industry. It implies and requires mass production of low-cost nanotubes, processed by methods other than solid-carbon-source-based methods (see Sect. 3.2.1). Such an application also requires some surface reactivity, making the h-MWNT type nanotubes with a poor nanotexture (see Sect. 3.1.2) the most suitable starting material for preparing such catalyst supports. Catalysis-enhanced thermal cracking of gaseous carbon precursors is therefore preferred, and pilot plants are already being built by major chemical industrial companies (e.g., Ato-Fina, France).



Fig. 3.30 Transmission electron microscopy image showing rhodium nanoparticles supported on MWNT surface (from [3.235])

3.6.2 Expected Applications Related to Adsorption

The adsorption and interaction of gases, liquids, or metal with carbon nanotubes has attracted much attention in the past several years. The applications resulting from the adsorption properties of carbon nanotubes can be arbitrarily divided into two groups. The first group is based on the consequences of molecule adsorption on nanotube electronic properties, whose main application is the chemical sensors (see Sect. 3.6.1). The second group includes gas storage, gas separation, or the use of carbon nanotubes as adsorbent and results from the morphological characteristics of carbon nanotubes (surface area, aspect ratio, and so forth). Among the three latter potential applications, the possibility of storing gases, and more particularly hydrogen, on carbon nanotubes has received most of the attention.

Table 3.4 Preparation and catalytic performances of some nanotube-supported catalysts

Catalyst	Preparation route	Catalytic reaction	Comments
Ru/MWNT+SWNT [3.230]	Liquid phase impregnation, no pretreatment of the tubes	Liquid phase cinnamaldehyde hydrogenation	Different kind of metal support interaction compared to activated carbon
Pt/MWNT electrodes [3.149]	Electrode-less plating with pre-functionalization of MWNT	Oxygen reduction for fuel cells applications	High electrocatalytic activity
Rh/MWNT [3.235]	Surface mediated organometallic synthesis, pre-functionalization of MWNT	Liquid phase hydroformylation and hydrogenation	Higher activity of Rh/MWNT compared to Rh/activated carbon
Ru-alkali/MWNT [3.238]	Liquid phase impregnation, no pretreatment of the tubes	Ammonia synthesis, gas phase reaction	Higher activity with MWNT than with graphite
Rh-phosphine/MWNT [3.239]	Liquid phase grafting from [RhH(CO)(PPh$_3$)$_3$]	Liquid phase hydroformylation	Highly active and regioselective catalyst

Gas Storage – Hydrogen

The development of lightweight and safe system for hydrogen storage is necessary for a wide use of highly efficient H_2-air fuel cells in transportation vehicles. The U.S. Department of Energy Hydrogen Plan has set a standard by providing a commercially significant benchmark for the amount of reversible hydrogen adsorption. This benchmark requires a system-weight efficiency (the ratio of H_2 weight to system weight) of 6.5 wt% hydrogen and a volumetric density of 63 kgH_2/m^3.

From now on, the failure to produce a practical storage system for hydrogen has prevented hydrogen from coming to the commercial forefront as a transportation fuel. The ideal hydrogen storage system needs to be light, compact, relatively inexpensive, safe, easy to use, and reusable without the need for regeneration. While research and development are continuing on such technologies as liquid hydrogen systems, compressed hydrogen systems, metal hydride systems, and superactivated carbon systems, all have serious disadvantages. For example, liquid hydrogen systems are very expensive, primarily because the hydrogen must be cooled to about −252 °C. For example, a liquid hydrogen system will cost about four times more than an equivalent amount of gasoline. Further, liquid hydrogen must be kept cooled to prevent it from boiling away, even when the vehicle is parked.

Compressed hydrogen is much cheaper than liquid hydrogen but also much bulkier.

Metal hydride systems store hydrogen as a solid in combination with other materials. For example, metal hydrides are produced by bathing a metal, such as palladium or magnesium, in hydrogen. The metal splits the dihydrogen gas molecules and binds the hydrogen atoms to the metal until released by heating. The disadvantages of a metal hydride system are its weight (typically about eight times more than an equivalent amount of liquid hydrogen or an equivalent amount of gasoline) and the need to warm it up to release the hydrogen.

Superactivated carbon is the basis of another system for storing hydrogen that initially showed commercial potential. Superactivated carbon is a material similar to the highly porous activated carbon used in water filters but can gently hold hydrogen molecules by physisorption at sub-zero temperatures. The colder the carbon, the less heat is needed to disturb the weak forces holding the carbon and hydrogen together. Again, a major disadvantage of such a system is that preventing the hydrogen from escaping requires it to constantly remain at very low temperatures, even when the vehicle is parked.

Consequently there still remains a great need for a material that can store hydrogen and is light, compact, relatively inexpensive, safe, easy to use, and reusable without regeneration. Recently some articles or patents concerning the very high, reversible adsorption of hydrogen in carbon nanotubes or platelet nanofibers have aroused tremendous interest in the research community, stimulating much experimental and theoretical works. Most of the works on hydrogen adsorption on carbon nanotubes have been recently reviewed [3.240–243].

A group from Northeastern University [3.132, 244] was the first to report the supposedly successful hydrogen storage in carbon layered nanostructures possessing some crystallinity. The authors claimed that, in platelet nanofibers (3–50 nm in width), hydrogen can be stored up to 75 wt%, meaning a C/H ratio of 1/9. Complete hydrogen desorption occurs only at very high temperature. The same authors have recently pointed out the dramatic role of the treatment that has to be applied to the carbon nanofibers prior to H_2 adsorption [3.244]. This thermal treatment, though simple (1,000 °C in an inert gas), is a critical procedure in order to remove chemisorbed gases from the edge and step regions of the carbon structures. Failure to achieve this condition results in a dramatic decrease in the hydrogen adsorption performance of the materials. In this work, the authors have performed the experiments at room temperature, and 100 bar of H_2, hydrogen uptake between 20 and 40 wt% were recorded. The authors have also demonstrated by XRD measurements that structural perturbation of the material was produced following hydrogen treatment, and that it was manifested by an expansion of the graphitic interplane distance (from 0.34 before H_2 adsorption to 0.347 after H_2 uptake).

Hydrogen adsorption and desorption measurements on nanofibers similar to that used by *Rodriguez* et al. [3.19] were also performed by *Ahn* et al. [3.245]. The authors have measured a hydrogen uptake of 2.4 wt%. In fact, in their study, none of the graphite nanofiber material tested has indicated hydrogen storage abilities that exceed the values already reported for activated carbons.

Adsorption of H_2 on platelet nanofibers was computed by Monte Carlo simulations [3.246]. The graphene spacing was optimized to maximize the weight fraction of H_2 adsorbed. Given the results of their calculations, the authors concluded that no physically realistic graphite-hydrogen potential can account for the tremendous adsorption ability reported by the group from Penn State.

Rzepka et al. [3.247] have also used theoretical Monte Carlo calculation to calculate the amount of physically adsorbed hydrogen molecules in carbon slit pores of dimensions similar to that used by the Penn State group (i. e., 0.34 nm as the interplanar distance between graphenes in the nanofibers). They reached the conclusion that no hydrogen can be adsorbed at all. Even if the interplanar distance is assumed to expand during the adsorption process, the maximum calculated adsorption is 1 wt% for $d = 0.7$ nm. These authors concluded that the Penn State experimental results could not be attributed to some "abnormal capillary condensation effect" as initially claimed. Since then, nobody has been able to duplicate it experimentally.

Meanwhile, hydrogen storage experiments were also attempted on SWNTs. The first work was reported by *Dillon* et al. [3.248] who used temperature-programmed desorption measurements. A major drawback of their experimental procedure was that they used only 1 mg of *unpurified* soot containing 0.1% of SWNTs. They attributed the reversible hydrogen capacity of 0.01 wt% observed to the SWNTs only, therefore leading to a presumable capacity of 5–10 wt% for a pure nanotubes sample. TPD experiments shown H_2 desorption between -170 and $+100$ °C. Despite the weakness of the demonstration, the paper, which was published not much before that of Chambers et al. [3.132], has induced a worldwide excitement for the field.

Hydrogen adsorption measurements were also performed on SWNT samples of high purity [3.249]. At -193 °C, 160 bar of H_2 were admitted and the hydrogen adsorption was found to exceed 8 wt%. In this case, the authors proposed that hydrogen is first adsorbed on the outer surfaces of the crystalline material. But no data concerning H_2 desorption are given.

In recent reports, Dresselhaus and coworkers [3.240, 250] reported hydrogen storage in SWNTs (1.85 nm of average diameter) at room temperature. A hydrogen storage capacity of 4.2 wt% was achieved reproducibly under 100 bar for a SWNT-containing material of about 0.5 g that was previously soaked in hydrochloric acid and then heat-treated (500 °C) in vacuum. The purity of the sample was estimated from TGA and TEM observations to be about 50 to 60%. Moreover, 78% of the adsorbed hydrogen could be released under ambient pressure at room temperature, while the release of the residual stored hydrogen required some heating at 200 °C.

A valuable input to the topic was brought by *Hirscher* et al. [3.251], who demonstrated that several of the supposedly successful experiments regarding the storage of H_2 in SWNTs were actually misled by the hydrogen storage capacity of Ti nanoparticles originating from the sonoprobe frequently used at one step or another of the procedure, specifically when the SWNT material is previously purified.

Density functional theory (DFT) was used [3.252] to estimate H_2 adsorption in SWNTs. From their calculations, within the regime of operating conditions where adsorptive storage seems attractive, the storage properties of H_2 in a SWNT system appear to fall far short of the DOE target. In their model, rolling graphite into a cylindrical sheet does not significantly alter the nature of the carbon–H_2 interaction, in contradiction with the latest calculations, which indicate that the possibilities of physisorption increase as the radius of curvature of SWNTs decreases [3.253].

More recently, however, *Lee* et al. [3.254, 255] have also used DFT calculations to search for hydrogen adsorption sites and predict maximum storage capacity in SWNTs. They have found two chemisorption sites, at the exterior and the interior of the tube wall. Thus they predict a maximum hydrogen storage capacity that can exceed 14 wt% (160 kgH_2/m^3). The authors have also considered H_2 adsorption in multiwall carbon nanotubes and have predicted lower storage capacities for the latter.

Calculations are constrained, however, by the starting hypotheses. While considering the same (10,10) SWNT, although calculations based on DFT predict a 14.3% storage [3.254], calculations based on a geometrical model predict 3.3% [3.240], and calculations based on quantum mechanical molecular dynamics model predict 0.47% [3.256].

In conclusion, neither the experimental results, obviously biased by some problem in the procedures, nor theoretical results are yet able to demonstrate that an efficient storage of H_2 is achievable for carbon nanotubes, whatever the type. But the definitive failure statement cannot yet be claimed. Further efforts have to be made to enhance H_2 adsorption of these materials, in particular (i) by adjusting the surface properties that can be modified by chemical or mechanical treatments, and (ii) by adjusting the material structure (pore size and curvature). Whether the best carbon material will then be nanotube-based is another story.

Gas Storage – Gases Other than Hydrogen

Encouraged by the potential applications related to hydrogen adsorption, several research groups have tried to use carbon nanotubes as a stocking and transporting mean for other gases such as: oxygen, nitrogen, noble gases (argon and xenon), and hydrocarbons (methane, ethane, and ethylene). These studies have shown that carbon nanotubes could become the world's smallest gas cylinders combining low weight, easy transportability, and safe use with acceptable adsorbed quantities. Thanks to their nano-sizes, nanotubes might also be used in medicine where physically confining special gases (like ^{133}Xe for instance) prior to injection would be extremely useful.

Kusnetzova et al. [3.257] have conducted experiments with xenon and found that a very significant enhancement (280 times more, up to a molar ratio $N_{Xe}/N_C = 0.045$) can be achieved by opening the SWNT bundles by thermal activation at 800 °C. With this treatment the gas can be adsorbed inside the nanotubes and the rates of adsorption are also increased.

The possibility of storing argon in carbon nanotubes has been studied with encouraging results by *Gadd* et al. [3.258]: their experiments show that large amounts of argon can be trapped into catalytically grown MWNTs (20–150 nm) by hot isostatic pressing (HIP-ing) for 48 hours at 650 °C under an argon pressure of 1,700 bar. Energy dispersive X-ray spectroscopy was used to determine that the gas was located inside the tubes and not on their walls. Further studies determined the argon pressure inside the tubes at room temperature. The authors estimated this feature to be around 600 bars, indicating that the equilibrium pressure was attained in the tubes during the HIP-ing and that MWNTs would be a convenient material for storing that gas.

Gas Separation

As SWNTs or MWNTs have regular geometries that can, to some extent, be controllable, they could be used to develop precise separation tools. If the sorption mechanisms are known, it should be possible to control sorption of various gases through combinations of temperature, pressure, and nanotube morphology. Since the large-scale production of nanotubes is now constantly progressing and may result in low costs, accurate separation methods based on carbon nanotubes have started to be investigated.

A theoretical study has aimed to determine the effect of different factors such as the diameter of the tubes, the density and the type of the gas used on the flow of molecules inside the nanotubes. An atomistic simulation with methane, ethane, and ethylene [3.259] has shown that the molecule mobility decreases with the decrease of the diameter of the tube for each of the three gases. Ethane and ethylene have a smaller mobility due to the stronger interaction they seem to have with the nanotube walls. In another theoretical study on the possibility of hydrocarbon mixture separation on SWNT bundles, the authors conclude on the possibility of using carbon nanotubes to separate methane/n-butane and methane/isobutene mixtures [3.260], with an efficiency that increases as the average tube diameter decreases. An experimental work was also performed by the same group on the sorption of butane on MWNTs [3.133].

Simulation by grand canonical Monte Carlo for separation of hydrogen and carbon monoxide by adsorption on SWNT has also been reported [3.261]. In most of the situations studied, SWNTs are found to adsorb more CO than H_2, and an excellent separation effect could probably be obtained, again, by varying the SWNT average diameter.

Adsorbents

Carbon nanotubes were recently found to be able to adsorb some toxic gases such as dioxins [3.262], fluoride [3.263], lead [3.264], or alcohols [3.265] better than the materials used so far, such as activated carbon. These pioneering works opened a new field of applications as cleaning filters for many industrial processes having hazardous by-products. Adsorption of dioxins, which are very common and persistent carcinogenic by-products of many industrial processes, is a good example of the interest of nanotubes in this field. Ecological consciousness has imposed emission limits on dioxin-generating sources in many countries, but finding materials that can act as effective filters, even at extremely low concentrations, is a big issue. *Long* et al. [3.262] have found that nanotubes can attract and trap more dioxins than activated carbons or other polyaromatic materials that are currently used as filters. This improvement is probably due to the stronger interaction forces that exist between dioxin molecules and the nanotube curved surfaces compared to those for flat graphene sheets.

The adsorption capacity of Al_2O_3/MWNT for fluoride from water has been reported to be 13.5 times that of activated carbon and 4 times that of Al_2O_3 [3.263]. The same group has also reported an adsorption capacity of lead from water by MWNTs higher than that by activated carbon [3.264]. The possibility to using graphite nanofibers to purify water from alcohols has also been explored [3.265]. These experimental results suggest that carbon nanotubes may be promising adsorbents for the removal of polluting agents from water.

Bio-Sensors

Attaching molecules of biological interest to carbon nanotubes is an ideal way to realize nanometer-sized biosensors. Indeed, the electrical conductivity of such functionalized nanotubes would depend on modifications of the interaction of the probe with the studied media, because of chemical changes or as result of their interaction with target species. The science of attaching biomolecules to nanotubes is rather recent and was inspired by similar research in the fullerene area. Some results have already been patented, and what was looking like a dream a couple of years ago may become reality in the near future. The use of the internal cavity of nanotubes for drug delivery would be another amazing application, but little work has been carried out so far to investigate the harmfulness of nanotubes in the human body. MWNTs have been used by *Mattson* et al. [3.266] as a substrate for neuronal growth. They have compared the activity of untreated MWNTs with that of MWNTs coated with a bioactive molecule (4-hydroxynonenal) and observed that on these latter functionalized nanotubes, neurons elaborated multiple neurites. This is an important result illustrating the feasibility of using nanotubes as substrate for nerve cell growth.

Davis et al. [3.267] have immobilized different proteins (metallothionein, cytochrome c and c_3, β-lactamase I) in MWNTs and checked that these molecules were still catalytically active compared to the nonimmobilized ones. They have shown that confining a protein within a nanotube provides some protection toward the external environment. Protein immobilization via noncovalent sidewall functionalization was proposed by *Chen* et al. [3.268] by using a bifunctional molecule (1-pyrenebutanoic acid, succinimidyl ester). This molecule is maintained to the nanotube wall by the pyrenyl group, and amine groups or biological molecules can react with the ester function to form amid bonds. This method was also used to immobilize ferritin and streptavidin onto SWNTs. It has the main advantage of not modifying the SWNT wall and keeping unperturbed the sp^2 structure, maintaining the physical properties of the nanotubes. *Shim* et al. [3.269] have functionalized SWNTs with biotin and observed specific binding with streptavidin, illustrating biomolecular recognition possibilities. *Dwyer* et al. [3.270] have functionalized SWNTs by covalently coupling DNA strands to them using EDC(1-ethyl-3-(3-dimethylaminopropyl) carbodiimide hydrochloride) but did not test biomolecular recognition; other proteins such as bovine serum albumin (BSA) [3.271] have been attached to nanotubes using the same process (diimide-activated amidation with EDC) and most of the attached proteins remained bioactive. Instead of working with individual nanotubes (or more likely nanotube bundles in the case of SWNTs), *Nguyen* et al. [3.272] have functionalized nanotubes arrayed with a nucleic acid, still using EDC as the coupling agent, in order to facilitate the realization of biosensors based on protein-functionalized nanotubes. Recently *Azamian* et al. [3.273] have immobilized a series of biomolecules (cytochrome c, ferritin, and glucose oxydase) on SWNTs and observed that the use of EDC was not always necessary, indicating that the binding was predominantly noncovalent. In the case of glucose oxydase, they have tested the catalytic activity of functionalized nanotubes immobilized on a glassy carbon electrode and observed a tenfold greater catalytic response compared to that in the absence of modified SWNTs.

Functionalization of nanotubes with biomolecules is still in its infancy, and their use as biosensors may lead to practical applications earlier than expected. For example, functionalized nanotubes can be used as AFM tips (see Sect. 3.6.1) allowing to perform "chemical force microscopy" (CFM), allowing single-molecule measurements. Even in the case of nonfunctionalized CNT-based tips, important improvements have been obtained for the characterization of biomolecules (see the review by [3.215]).

Composites

Because of their exceptional morphological, electrical, thermal, and mechanical characteristics, carbon nanotubes are particularly promising materials as reinforcement in composite materials with metal, ceramic, or polymer matrix. Key basic issues include the good dispersion of the nanotubes, the control of the nanotube/matrix bonding, the densification of bulk composites and thin films, and the possibility of aligning the nanotubes. In addition, the nanotube type (SWNT, c-MWNT, h-MWNT, etc.) and origin (arc, laser, CCVD, etc.) is also an important variable since determining the structural perfection, surface reactivity, and aspect ratio of the reinforcement.

Considering the major breakthrough that carbon nanotubes are expected to make in the field, the following will give an overview of the current work on metal-, ceramic- and polymer-matrix composites reinforced with nanotubes. We will not consider nanotubes merely coated with another material will not be considered here. We discussed filled nanotubes in Sect. 3.5.2. Applications involving the incorporation of nanotubes to materials for purposes other than structural will be mentioned in Sect. 3.6.2.

Metal Matrix Composites

Nanotube-metal matrix composites are still rarely studied. The materials are generally prepared by standard powder metallurgy techniques, but the dispersion of the nanotubes is not optimal. Thermal stability and electrical and mechanical properties of the composites are investigated. The room temperature electrical resistivity of hot-pressed CCVD MWNTs-Al composites increases slightly by increasing the MWNT volume fraction [3.274]. The tensile strength and elongation of nonpurified arc-discharge MWNT-Al composites are only slightly affected by annealing at 873 K in contrast to that of pure Al [3.275]. The Young's modulus of nonpurified arc-discharge MWNTs-Ti composites is about 1.7 times that of pure Ti [3.276]. The formation of TiC, probably resulting from the reaction between amorphous carbon and the matrix, was observed, but the MWNTs themselves were not damaged. An increase of the Vickers hardness by a factor 5.5 over that of pure Ti was associated with the suppression of coarsening of the Ti grains, the TiC formation, and the addition of MWNTs with an extremely high Young's modulus. CCVD MWNTs-Cu composites [3.277] also show a higher hardness and a lower friction coefficient and wear loss. A deformation of 50–60 % of the composites was observed. A MWNTs-metallic glass Fe82P18 composite [3.278] with a good dispersion of the MWNTS was prepared by the rapid solidification technique.

Ceramic Matrix Composites

Carbon nanotube-containing ceramic-matrix composites are a bit more frequently studied, most efforts made to obtain tougher ceramics [3.279]. Composites can be processed following the regular processing route, in which the nanotubes are usually mechanically mixed with the matrix (or a matrix precursor) then densified using hot-pressing sintering of the slurry or powders. *Zhan* et al. [3.280] ball-milled SWNT bundles (from the HiPCo technique) and nanometric alumina powders, producing a fairly homogeneous dispersion, supposedly without damaging the SWNTs. On the other hand, interesting results were obtained using the spark plasma sintering (SPS) technique, which was able to prepare fully dense composites without damage to the SWNTs [3.281]. Other original composite processing include sol-gel route, by which bulk and thin film composites were prepared [3.282], and in situ SWNT growth in ceramic foams, using procedures closely related to that described in Sect. 3.2.2 [3.283].

Ma et al. [3.284] prepared MWNT-SiC composites by hot-pressing mixtures of CCVD MWNTs and nano-SiC powders. They claimed that the presence of the MWNTs provides an increase of about 10% of both the bending strength and fracture toughness, but the dispersion of the MWNTs looks poor. Several detailed studies [3.82, 285–288] have dealt with the preparation of nanotube-Fe-Al_2O_3, nanotube-Co-MgO, and nanotube-Fe/Co-$MgAl_2O_4$ composites by hot-pressing of the corresponding composite powders. The nanotubes were grown in situ in the starting powders by a CCVD method [3.73, 80, 289–293] and thus are very homogeneously dispersed between the metal-oxide grains, in a way that could be impossible to achieve by mechanical mixing. The nanotubes (mostly SWNTs and DWNTs) gather in long, branched bundles smaller than 50 nm in diameter, which appear to be very flexible. Depending on the matrix and hot-pressing temperature, a fraction of the nanotubes seems to be destroyed during hot-pressing in a primary vacuum. The increase of the quantity of nanotubes (ca. 2–12 wt%) leads to a refinement of the microstructure but also to a strong decrease in relative density (70–93 %). Probably because of this, the fracture strength and the toughness of the nanotube-containing composites are generally lower than those of the nanotube-free metal-oxide composites and only marginally higher than those of the corresponding ceramics. SEM observations revealed both the trapping of some of the nanotubes within the matrix grains or at grain boundaries and a relatively good wetting in the case of alumina. Most nanotubes are cut near the fracture surface after some pull-out and could contribute to a mechanical reinforcement.

Siegel et al. [3.294] claimed that the fracture toughness of 10 vol.% MWNTs-alumina hot-pressed composites is increased by 24% (to 4.2 MPa m$^{1/2}$) over that of pure alumina. But the density and grain size are not reported, so it is difficult to consider this result as an evidence for the beneficial role of the MWNTs themselves. A confirmation could be found in the work by *Sun* et al. [3.281] who developed a colloidal route to coat the nanotubes with alumina particles prior to another mixing step with alumina particles then densification by SPS. A very large gain in fracture toughness (calculated from Vickers indentation) is reported (from 3.7 MPa m$^{1/2}$ for pure Al_2O_3 to 4.9 MPa m$^{1/2}$ for an addition of 0.1 wt% of SWNT nanotubes, and to 9.7 MPa m$^{1/2}$ for an addition of 10 wt%). But it is possible that the beneficial input of the nanotubes is due to the previous coating of the nanotubes before sintering, resulting in an improved bonding with the matrix.

Bulk properties other than mechanical are also worth being investigated. Interestingly, the presence of well dispersed nanotubes confers an electrical conductivity to the otherwise insulating ceramic-matrix composites. The percolation threshold is very low – in the range 0.2–0.6 wt% of carbon – due to the very high aspect ratio of nanotubes. Varying the nanotube quantity in the starting powders allows the electrical conductivity to be controlled in the range 0.01–10 S cm^{-1}. Moreover, the extrusion at high temperatures in vacuum allows the nanotubes to be aligned in the matrix, thus inducing an anisotropy in the electrical conductivity [3.295]. One of the early works involved MWNTs in a superconducting $Bi_2Sr_2CaCu_2O_{8+\delta}$ matrix [3.296]. The application of SWNTs for thermal management in partially stabilized zirconia [3.297] and of MWNTs-lanthanum cobaltate composites for application as an oxygen electrode in zinc/air [3.298] were reported more recently. The friction coefficient was also shown to increase and the wear loss to decrease upon the increase in nanotube volume fraction in carbon/carbon composites [3.299].

The latter is one of the few examples in which carbon has been considered as a matrix. Another one is the work reported by *Andrews* et al. [3.300], who introduced 5 wt% of SWNTs into a pitch material before spinning the whole as a SWNT-reinforced pitch-fiber. Subsequent carbonization transformed it into a SWNT-reinforced carbon fiber. Due to the contribution of the SWNTs, which were aligned by the spinning stresses, the resulting gain in tensile strength, modulus, and electrical conductivity with respect to the nonreinforced carbon fiber was claimed to be 90, 150, and 340%, respectively.

Polymer Matrix Composites

Nanotube-polymer composites, first reported by *Ajayan* et al. [3.301] are now intensively studied, notably epoxy- and polymethylmethacrylate (PMMA)-matrix composites. Regarding the mechanical characteristics, the three key issues affecting the performance of a fiber-polymer composite are the strength and toughness of the fibrous reinforcement, its orientation, and a good interfacial bonding crucial for the load transfer to occur [3.302]. The ability of the polymer to form large-diameter helices around individual nanotubes favors the formation of a strong bond with the matrix [3.302]. Isolated SWNTs may be more desirable than MWNTs or bundles for dispersion in a matrix because of the weak frictional interactions between layers of MWNTs and between SWNTs in bundles [3.302]. The main mechanisms of load transfer are micromechanical interlocking, chemical bonding, and van der Waals bonding between the nanotubes and the matrix. A high interfacial shear stress between the fiber and the matrix will transfer the applied load to the fiber over a short distance [3.303]. SWNTs longer than 10–100 μm would be needed for significant load-bearing ability in the case of nonbonded SWNT-matrix interactions, whereas the critical length for SWNTs cross-linked to the matrix is only 1 μm [3.304]. Defects are likely to limit the working length of SWNTs [3.305], however.

The load transfer to MWNTs dispersed in an epoxy resin was much higher in compression than in tension [3.303]. It was proposed that all the walls of the MWNTs are stressed in compression, whereas only the outer walls are stressed in tension because all the inner tubes are sliding within the outer. Mechanical tests performed on 5 wt% SWNT-epoxy composites [3.306] showed that SWNTs bundles were pulled out of the matrix during the deformation of the material. The influence of the nanotube/matrix interfacial interaction was evidenced by *Gong* et al. [3.307]. It was also reported that coating regular carbon fiber with MWNTs prior to their dispersion into an epoxy matrix improves the interfacial load transfer, possibly by local stiffening of the matrix near interface [3.308].

As for ceramic matrix composites, the electrical characteristics of SWNT- and MWNT-epoxy composites are described with the percolation theory. Very low percolation threshold (below 1 wt%) is often reported [3.309–311]. Industrial epoxy loaded with 1 wt% unpurified CCVD-prepared SWNTs showed an increase in thermal conductivity of 70% and 125% at 40 K and at room temperature, respectively [3.309]. Also, the Vickers hardness rose with the SWNT loading up to a factor of 3.5 at 2 wt%. Thus both the thermal and mechanical properties of such composites are improved without the need to chemically functionalize the SWNTs.

Likewise, the conductivity of laser-prepared SWNT-PMMA composites increases with the load in SWNTs (1–8 wt% SWNTs) [3.302]. Thermogravimetric analysis shows that, compared to pure PMMA, the thermal degradation of PMMA films occurs at a slightly higher temperature when 26 wt% MWNTs are added [3.312]. Improving the wetting between the MWNTs and the PMMA by coating the MWNTs with poly(vinylidene fluoride) prior to melt-blending with PMMA resulted in an increased storage modulus [3.313]. The impact strength in aligned SWNT-PMMA composites was significantly increased with only 0.1 wt% of SWNTs, possibly because of a weak interfacial adhesion, and/or of the high flexibility of the SWNTs, and/or the pullout and sliding effects of individual SWNTs within bundles [3.314]. The transport properties of arc-discharge SWNTs-PMMA composite films (10 μm thick) were studied in great detail [3.315, 316]. The electrical conductivity increases by nine orders of magnitude from 0.1 to 8 wt% SWNTs. The room temperature conductivity is again well described with the standard percolation theory, confirming the good dispersion of the SWNTs in the matrix.

Polymer composites with other matrices include CCVD-prepared MWNT-polyvinyl alcohol [3.317], arc-prepared MWNT-polyhydroxyaminoether [3.318], arc-prepared MWNT-polyurethane acrylate [3.319, 320], SWNT-polyurethane acrylate [3.321], SWNT-polycarbonate [3.322], MWNT-polyaniline [3.323], MWNT-polystyrene [3.324], SWNT-polyethylene [3.325], CCVD-prepared MWNT-polyacrylonitrile. [3.326], MWNT-oxotitanium phthalocyanine [3.327], arc-prepared MWNT-poly(3-octylthiophene) [3.328], SWNT-poly(3-octylthiophene) [3.329], and CCVD MWNTs-poly(3-hexylthiophene) [3.330]. These works deal mainly with films 100–200 micrometer thick and aim to study the glass transition of the polymer, mechanical, and electrical characteristics as well as photoconductivity.

A great deal of work is also devoted to nano-tube-polymer composites for applications as materials for molecular optoelectronics, using primarily poly(m-phenylenevinylene-co-2,5-dioctoxy-p-phenylenevinylene) (PmPV) as the matrix. This conjugated polymer tends to coil, forming a helical structure. The electrical conductivity of the composite films (4–36 wt% MWNTs) is increased by eight orders of magnitude compared to that of PmPV [3.331]. Using the MWNT-PmPV composites as the electron-transport-layer in light-emitting diodes results in a significant increase in brightness [3.332]. The SWNTs act as a hole-trapping material blocking the holes in the composites, this being probably induced through long-range interactions within the matrix [3.333]. Similar investigations were carried out on arc-discharge SWNTs-polyethylene dioxythiophene (PEDOT) composite layers [3.334] and MWNTs-polyphenylenevinylene composites [3.335].

To conclude, two critical issues have to be considered for the application of nanotubes as reinforcement for advanced composites. One is to chose between SWNTs and MWNTs. The former seem more beneficial for the purpose of mechanical strengthening, provided they are isolated or arranged into cohesive yarns so that the load is able to be conveniently transferred from a SWNT to another. Unfortunately, despite recent advances [3.336–339], this is still a technical challenge. The other issue is to tailor the nanotube/matrix interface with respect to the matrix. This is a current topic for many laboratories involved in the field.

Multifunctional Materials

One of the major benefits expected from incorporating carbon nanotubes in other solid or liquid materials is bringing some electrical conductivity to them while not affecting the other properties or behaviors of these materials. As already mentioned in the previous section, the percolation threshold is reached at very low load with nanotubes. Tailoring the electrical conductivity of a bulk material is then achievable by adjusting the nanotube volume fraction in the formerly insulating material while not making this fraction too large anyway. As demonstrated by Maruyama [3.3], there are three regimes of interest regarding the electrical conductivity: (i) electrostatic discharge, e.g., to prevent fire or explosion hazard in combustible environments or perturbations in electronics, which requires electrical resistivity less than $10^{12}\ \Omega\,\mathrm{cm}$; (ii) electrostatic painting, which requires the material to be painted to be electrical conductive enough (electrical resistivity below $10^6\ \Omega$ cm) to prevent the charged paint droplets to be repelled; (iii) electromagnetic interference shielding, which is achieved for electrical resistivity lower than $10\ \Omega$ cm.

Materials are often asked to be multifunctional, e.g. having both high electrical conductivity and high toughness, or high thermal conductivity and high thermal stability, etc. The association of several materials, each of them bringing one of the desired features, therefore generally meets this need. Exceptional features and properties of carbon nanotubes make them likely to be a perfect multifunctional material in many cases. For instance, materials for satellites are often required to be electrical conductive, mechanically self-supporting, able to transport the excess heat away, sometimes be protected against electromagnetic interferences, etc., while exhibiting minimal weight and volume. All these properties should be possible with a single nanotube-containing composite material instead of complex multi-materials combining layers of polymers, aluminum, copper, etc. Table 3.5 provides an overview of various fields in which nanotube-based multifunctional materials should find an application.

Nano-Electronics

As reported in Sects. 3.1.1 and 3.4.4, SWNT nanotubes can be either metallic (with an electrical conductivity higher than that of copper), or semiconductor. This has inspired the design of several components for nanoelectronics. First, metallic SWNTs can be used as mere ballistic conductors. Moreover, as early as 1995,

Table 3.5 Applications for nanotube-based multifunctional materials (from [3.3]), by courtesy of B. Maruyama (WPAFB, Dayton, Ohio)

Fiber fraction	Applications system	Mechanical			Electrical			Thermal		Thermo-mechanical	
		Strength/ stiffness	Specific strength	through-thickness strength	Static dissipation	Surface Conduction[a]	EMI shielding	Service[b] temp.	conduction/ dissipation[c]	Dimensional Stability[d]	CTE reduction[e]
Low Volume fraction (fillers)											
Elastomers	Tires	×			×				×		
Thermo Plastics	Chip package				×				×		
	Electronics/ Housing	×					×	×	×		
Thermosets	Epoxy products	×	×	×		×				×	×
	Composites			×						×	
High Volume Fraction											
Structural composites	Space/aircraft components		×	×							
High conduction composites	Radiators	×							×	×	
	Heat exchangers	×						×	×		×
	EMI shield	×					×				

[a] For electrostatic painting, to mitigate lightning strikes on aircraft, etc.

[b] To increase service temperature rating of product

[c] To reduce operating temperatures of electronic packages

[d] Reduces warping

[e] Reduces microcracking damage in composites

realizing a rectifying diode by joining one metallic SWNT to one semiconductor SWNT (hetero-junction) was proposed by *Lambin* et al. [3.340], then later by *Chico* et al. [3.341] and *Yao* et al. [3.342]. Also, field-effect transistors (FET) can be built by the attachment of a semiconductor SWNT across two electrodes (source and drain) deposited on an insulating substrate that serves as a gate electrode [3.343, 344]. Recently the association of two such SWNT-based FETs has made a voltage inverter [3.345].

All the latter developments are fascinating and provide promising perspectives for nanotube-based electronics. But progress is obviously needed before making SWNT-based integrated circuits on a routine basis. A key point is the need to be able to prepare selectively either metallic or semiconductor nanotubes. Although a way has been proposed to destroy selectively metallic SWNTs from bundles of undifferentiated SWNTs [3.347], the method is not scalable and selective synthesis would be preferable. Also, defect-free nanotubes are required. Generally speaking, it relates to another major challenge, which is to be able to fabricate at industrial scale integrated circuits including nanometer-size components that only sophisticated imaging methods (AFM) are able to visualize.

Nano-Tools, Nano-Devices, Nano-Systems

Due to the ability of graphene to expand slightly when electrically charged, nanotubes have been found to act conveniently as actuators. *Kim* et al. [3.346] demonstrated it by designing "nano"-tweezers able to grab, manipulate, release nano-objects (the "nano"-bead having been handled for the demonstration was actually closer to micrometer than nanometer), and measure their electrical properties. This was made possible quite simply by depositing two non-interconnected gold coatings onto a pulled glass micropipette (Fig. 3.31), then attaching two MWNTs (or two SWNT-bundles) ∼ 20–50 nm in diameter to each of the gold electrodes. Applying a voltage (0–8.5 V) between the two electrodes then makes the tube tips to open and close reversibly in a controlled manner.



Fig. 3.31 Sketch explaining how the first nano-tweezers were designed. First is a glass micropipette (dark cone, *top*). Then two Au coatings (in grey, *middle*) are deposited so that they are not in contact. Then a voltage is applied to the electrodes (from [3.346])

A similar experiment, again rather simple, was proposed by *Baughman* et al. the same year (1999) [3.348], consisting in mounting two SWNT-based paper strips ("bucky-paper") on both sides of an insulating double-side tape. The two bucky-paper strips were previously loaded with Na^+ and Cl^-, respectively. When 1 V was applied between the two paper strips, both expand, but the strip loaded with Na^+ expands a bit more, forcing the whole system to bend. Though performed in a liquid environment, such a behavior has inspired the authors to predict a future for their system as "artificial muscles."

Another example of amazing nano-tools is the nanothermometer proposed by *Gao* et al. [3.349]. A single MWNT was used, in that case, partially filled with liquid gallium. Upon the effect of temperature variations in the range 50–500 °C, the gallium goes up and down reversibly within the nanotube cavity at reproducible level with respect to the values of the temperature applied.

Of course, nano-tools such as nano-tweezers or nano-thermometers will hardly reach a commercial development so to justify industrial investments. But such experiments are more than amazing laboratory curiosities. They definitely demonstrate the ability of carbon nanotubes as parts for future nano-devices, including nanomechanics-based systems.

Supercapacitors

Supercapacitors include two electrodes immersed in an electrolyte (e.g., 6 M KOH), separated by an insulating ion-permeable membrane. Charging the capacitors is achieved by applying a potential between the two electrodes, making the cations and the anions moving toward the electrode oppositely charged. Suitable electrodes should exhibit a high electrical conductivity and a high surface area since the capacitance is proportional to it. Actually, the surface area should originate mainly from the appropriate combination of mesopores (to allow the electrolyte components to circulate well, which is related to the charging speed) and micropores (whose walls are the surface of attraction and fixation sites for the ions). Based on early works by

Niu et al. [3.350], such a combination was found to be reached with the specific architecture offered by packed and entangled h-MWNTs with a poor nanotexture (see Sect. 3.1.2). But, activation pre-treatments are necessary. For instance, a capacitor made from nanotubes with surface area $= 220\,\mathrm{m}^2/\mathrm{g}$ exhibited a capacitance of $20\,\mathrm{F/g}$, which increased up to $100\,\mathrm{F/g}$ after an activation treatment was applied to the nanotubes so that their surface area reaches $880\,\mathrm{m}^2/\mathrm{g}$ [3.126]. Alternatively, again due to their specific architecture induced by their huge aspect ratio, nanotubes can also be used as supports for conductive polymer coatings, e.g., polypyrrole or polyaniline [3.351], which otherwise would make a too dense phase (i. e. not allowing an easy circulation and penetration of ions). Supercapacitors built from such composites can overcome more than 2,000 charging cycles, with current density as high as $350\,\mathrm{mA/g}$ [3.352]. Capacitors including nanotubes already have capacitance as high as $180–200\,\mathrm{F/g}$, i. e. equivalent to that obtained with electrodes built from regular carbon materials, with the advantage of faster charging [3.126]. Current works will certainly lead to further optimization of both the nanotube material architecture and the nanotube-supported conductive polymers, giving reasonable perspectives for the commercial use of nanotubes as components for supercapacitors.

References

3.1 M. Hillert, N. Lange: The structure of graphite filaments, Zeitschr. Kristall. **111** (1958) 24–34

3.2 T. V. Hughes, C. R. Chambers: US Patent 405,480 (1889)

3.3 B. Maruyama, K. Alam: Carbon nanotubes and nanofibers in composite materials, SAMPE J. **38** (2002) 59–70

3.4 P. Schützenberger, L. Schützenberger: Sur quelques faits relatifs à l'histoire du carbone, C. R. Acad. Sci. Paris **111** (1890) 774–778

3.5 C. Pélabon, H. Pélabon: Sur une variété de carbone filamenteux, C. R. Acad. Sci. (Paris) **137** (1903) 706–708

3.6 R. T. K. Baker, P. S. Harris: The formation of filamentous carbon. In: *Chemistry and Physics of Carbon*, Vol. 14, ed. by P. L. Walker Jr., P. A. Thrower (Dekker, New York 1978) pp. 83–165

3.7 S. Iijima: Helical microtubules of graphite carbon, Nature **354** (1991) 56–58

3.8 S. Iijima, T. Ichihashi: Single-shell carbon nanotubes of 1-nm diameter, Nature **363** (1993) 603–605

3.9 D. S. Bethune, C. H. Kiang, M. S. de Vries, G. Gorman, R. Savoy, J. Vazquez, R. Bayers: Cobalt-catalysed growth of carbon nanotubes with single-atomic-layer walls, Nature **363** (1993) 605–607

3.10 J. Tersoff, R. S. Ruoff: Structural properties of a carbon-nanotube crystal, Phys. Rev. Lett. **73** (1994) 676–679

3.11 N. Wang, Z. K. Tang, G. D. Li, J. S. Chen: Single-walled 4 Å carbon nanotube arrays, Nature **408** (2000) 50–51

3.12 N. Hamada, S. I. Sawada, A. Oshiyama: New one-dimensional conductors, graphitemicrotubules, Phys. Rev. Lett. **68** (1992) 1579–1581

3.13 M. S. Dresselhaus, G. Dresselhaus, P. C. Eklund: *Science of Fullerenes and Carbon Nanotubes* (Academic, San Diego 1995)

3.14 M. Monthioux, B. W. Smith, B. Burteaux, A. Claye, J. Fisher, D. E. Luzzi: Sensitivity of single-wall nanotubes to chemical processing: An electron microscopy investigation, Carbon **39** (2001) 1261–1272

3.15 H. Allouche, M. Monthioux: Chemical vapor deposition of pyrolytic carbon onto carbon nanotubes II – Structure and texture, Carbon (2003) accepted

3.16 M. Audier, A. Oberlin, M. Oberlin, M. Coulon, L. Bonnetain: Morphology and crystalline order in catalytic carbons, Carbon **19** (1981) 217–224

3.17 Y. Saito: Nanoparticles and filled nanocapsules, Carbon **33** (1995) 979–988

3.18 P. J. F. Harris: *Carbon Nanotubes and Related Structures* (Cambridge Univ. Press, Cambridge 1999)

3.19 N. M. Rodriguez, A. Chambers, R. T. Baker: Catalytic engineering of carbon nanostructures, Langmuir **11** (1995) 3862–3866

3.20 H. W. Kroto, J. R. Heath, S.C. O'Brien, R. F. Curl, R. E. Smalley: C_{60} Buckminsterfullerene, Nature **318** (1985) 162–163

3.21 W. Krätschmer, L. D. Lamb, K. Fostiropoulos, D. R. Huffman: Solid C_{60}: A new form of carbon, Nature **347** (1990) 354–358

3.22 T. Guo, P. Nikolaev, A. G. Rinzler, D. Tomanek, D. T. Colbert, R. E. Smalley: Self-assembly of tubular fullerenes, J. Phys. Chem. **99** (1995) 10694–10697

3.23 T. Guo, P. Nikolaev, A. Thess, D. T. Colbert, R. E. Smalley: Catalytic growth of single-walled nanotubes by laser vaporisation, Chem. Phys. Lett. **243** (1995) 49–54

3.24 A. G. Rinzler, J. Liu, H. Dai, P. Nikolaev, C. B. Huffman, F. J. Rodriguez-Macias, P. J. Boul, A. H. Lu, D. Heymann, D. T. Colbert, R. S. Lee, J. E. Fischer, A. M. Rao, P. C. Eklund, R. E. Smalley: Large scale purification of single wall carbon nanotubes: Process, product and characterization, Appl. Phys. A **67** (1998) 29–37

3.25 A. Thess, R. Lee, P. Nikolaev, H. Dai, P. Petit, J. Robert, C. Xu, Y. H. Lee, S. G. Kim, D. T. Colbert, G. Scuseria, D. Tomanek, J. E. Fischer, R. E. Smal-

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

ley: Crystalline ropes of metallic carbon nanotubes, Science **273** (1996) 487–493

3.26 L. M. de la Chapelle, J. Gavillet, J. L. Cochon, M. Ory, S. Lefrant, A. Loiseau, D. Pigache: A continuous wave CO_2 laser reactor for nanotube synthesis, Proc. Electronic Properties Novel Materials-XVI Int. Winterschool – AIP Conf. Proc., Melville 1999, ed. by H. Kuzmany, J. Fink, M. Mehring, S. Roth (Springer, Berlin, Heidelberg 1999) **486** 237– 240

3.27 M. Yudasaka, T. Komatsu, T. Ichihashi, S. Iijima: Single wall carbon nanotube formation by laser ablation using double targets of carbon and metal, Chem. Phys. Lett. **278** (1997) 102–106

3.28 M. Castignolles, A. Foutel-Richard, A. Mavel, J. L. Cochon, D. Pigache, A. Loiseau, P. Bernier: Combined experimental and numerical study of the parameters controlling the C-SWNT synthesis via laser vaporization, Proc. Electronic Properties of Novel Materials-XVI Int. Winterschool – AIP Conf. Proc., Melville 2002, ed. by H. Kuzmany, J. Fink, M. Mehring, S. Roth (Springer, Berlin, Heidelberg 2002) **633** 385–389

3.29 T. W. Ebbesen, P. M. Ajayan: Large-scale synthesis of carbon nanotubes, Nature **358** (1992) 220–221

3.30 D. Ugarte: Morphology and structure of graphitic soot particles generated in arc-discharge C_{60} production, Chem. Phys. Lett. **198** (1992) 596–602

3.31 T. W. Ebbesen: Carbon nanotubes, Ann. Rev. Mater. Sci. **24** (1994) 235–264

3.32 T. Beltz, J. Find, D. Herein, N. Pfänder, T. Rühle, H. Werner, M. Wohlers, R. Schlögl: On the production of different carbon forms by electric arc graphite evaporation, Ber. Bunsenges. Phys. Chem. **101** (1997) 712–725

3.33 C. Journet, W. K. Maser, P. Bernier, A. Loiseau, L. M. de la Chapelle, S. Lefrant, P. Deniard, R. Lee, J. E. Fischer: Large-scale production of single-walled carbon nanotubes by the electric-arc technique, Nature **388** (1997) 756–758

3.34 K. Saïdane, M. Razafinimanana, H. Lange, M. Baltas, A. Gleizes, J. J. Gonzalez: Influence of the carbon arc current intensity on fullerene synthesis, Proc. 24th Int. Conf. on Phenomena in Ionized Gases, Warsaw 1999, ed. by P. Pisarczyk, T. Pisarczyk, J. Wotowski, 203–204

3.35 H. Allouche, M. Monthioux, M. Pacheco, M. Razafinimanana, H. Lange, A. Huczko, T. P. Teulet, A. Gleizes, T. Sogabe: Physical characteristics of the graphite-electrode electric-arc as parameters for the formation of single-wall carbon nanotubes, Proc. Eurocarbon (Deutsche Keram. Ges., Berlin 2000) 1053–1054

3.36 M. Razafinimanana, M. Pacheco, M. Monthioux, H. Allouche, H. Lange, A. Huczko, A. Gleizes: Spectroscopic study of an electric arc with Gd and Fe doped anodes for the carbon nanotube formation, Proc. 25th Int. Conf. on Phenomena in Ionized Gases, Nagoya 2001, ed. by E. Goto (Nagoya Univ., Nagoya 2001) Extend. Abstr. **3** 297–298

3.37 M. Razafinimanana, M. Pacheco, M. Monthioux, H. Allouche, H. Lange, A. Huczko, P. Teulet, A. Gleizes, C. Goze, P. Bernier, T. Sogabe: Influence of doped graphite electrode in electric arc for the formation of single wall carbon nanotubes, Proc. 6th Eur. Conf. on Thermal Plasma Processes – Progress in Plasma Processing of Materials, New York 2000, ed. by P. Fauchais (Begell House, New York 2001) 649–654

3.38 M. Pacheco, H. Allouche, M. Monthioux, A. Razafinimanana, A. Gleizes: Correlation between the plasma characteristics and the morphology and structure of the carbon phases synthesised by electric arc discharge, Proc. 25th Biennial Conf. on Carbon, Lexington 2001 (Univ. of Kentucky, Lexington 2001) Extend. Abstr.(CD-Rom), Novel/14.1

3.39 M. Pacheco, M. Monthioux, M. Razafinimanana, L. Donadieu, H. Allouche, N. Caprais, A. Gleizes: New factors controlling the formation of single-wall carbon nanotubes by arc plasma, Proc. Carbon 2002 Int. Conf., Beijing 2002 (Tsinghua Univ., Beijing 2002) (CD-Rom/Oral/I014)

3.40 M. Monthioux, M. Pacheco, H. Allouche, M. Razafinimanana, N. Caprais, L. Donnadieu, A. Gleizes: New data about the formation of SWNTs by the electric arc method, Electronic Properties of Molecular Nanostructures, AIP Conf. Proc., Melville 2002, ed. by H. Kuzmany, J. Fink, M. Mehring, S. Roth (Springer, Berlin, Heidelberg 2002) 182–185

3.41 H. Lange, A. Huczko, M. Sioda, M. Pacheco, M. Razafinimanana, A. Gleizes: Influence of gadolinium on carbon arc plasma and formation of fullerenes and nanotubes, Plasma Chem. Plasma Process **22** (2002) 523–536

3.42 C. Journet: La production de nanotubes de carbone. Ph.D. Thesis (University of Montpellier II, Montpellier 1998)

3.43 T. Sogabe, T. Masuda, K. Kuroda, Y. Hirohaya, T. Hino, T. Ymashina: Preparation of B_4C-mixed graphite by pressureless sintering and its air oxidation behavior, Carbon **33** (1995) 1783–1788

3.44 M. Ishigami, J. Cumings, A. Zettl, S. Chen: A simple method for the continuous production of carbon nanotubes, Chem. Phys. Lett. **319** (2000) 457–459

3.45 Y. L. Hsin, K. C. Hwang, F. R. Chen, J. J. Kai: Production and in-situ metal filling of carbon nanotube in water, Adv. Mater. **13** (2001) 830–833

3.46 H. W. Zhu, X. S. Li, B. Jiang, C. L. Xu, C. L. Zhu, Y. F. Zhu, D. H. Wu, X. H. Chen: Formation of carbon nanotubes in water by the electric arc technique, Chem. Phys. Lett. **366** (2002) 664–669

3.47 W. K. Maser, P. Bernier, J. M. Lambert, O. Stephan, P. M. Ajayan, C. Colliex, V. Brotons, J. M. Planeix, B. Coq, P. Molinie, S. Lefrant: Elaboration and characterization of various carbon nanostructures, Synth. Met. **81** (1996) 243–250

3.48 J. Gavillet, A. Loiseau, J. Thibault, A. Maigné, O. Stéphan, P. Bernier: TEM study of the influence of the catalyst composition on the formation and growth of SWNT, Proc. Electronic Properties Novel Materials-XVI Int. Winterschool – AIP Conf. Proc., Melville 2002, ed. by H. Kuzmany, J. Fink, M. Mehring, S. Roth (Springer, Berlin, Heidelberg 2002) **633** 202–206

3.49 L. P. F. Chibante, A. Thess, J. M. Alford, M. D. Diener, R. E. Smalley: Solar generation of the fullerenes, J. Phys. Chem. **97** (1993) 8696–8700

3.50 C. L. Fields, J. R. Pitts, M. J. Hale, C. Bingham, A. Lewandowski, D. E. King: Formation of fullerenes in highly concentrated solar flux, J. Phys. Chem. **97** (1993) 8701–8702

3.51 P. Bernier, D. Laplaze, J. Auriol, L. Barbedette, G. Flamant, M. Lebrun, A. Brunelle, S. Della-Negra: Production of fullerenes from solar energy, Synth. Met. **70** (1995) 1455–1456

3.52 M. J. Heben, T. A. Bekkedhal, D. L. Schultz, K. M. Jones, A. C. Dillon, C. J. Curtis, C. Bingham, J. R. Pitts, A. Lewandowski, C. L. Fields: Production of single wall carbon nanotubes using concentrated sunlight, Proc. Symp. Recent Adv. Chem. Phys. Fullerenes Rel. Mater., Pennington 1996, ed. by K. M. Kadish, R. S. Ruoff (Electrochemical Society, Pennington 1996) INC **3** 803–811

3.53 D. Laplaze, P. Bernier, C. Journet, G. Vié, G. Flamant, E. Philippot, M. Lebrun: Evaporation of graphite using a solar furnace, Proc. 8th Int. Symp. Solar Concentrating Technol., Köln 1996, ed. by M. Becker, M. Balmer (C. F. Müller Verlag, Heidelberg 1997)

3.54 D. Laplaze, P. Bernier, W. K. Maser, G. Flamant, T. Guillard, A. Loiseau: Carbon nanotubes : The solar approach, Carbon **36** (1998) 685–688

3.55 T. Guillard, S. Cetout, L. Alvarez, J. L. Sauvajol, E. Anglaret, P. Bernier, G. Flamant, D. Laplaze: Production of carbon nanotubes by the solar route, Eur. Phys. J. **5** (1999) 251–256

3.56 G. Flamant, D. Luxembourg, C. Mas, D. Laplaze: Carbon nanotubes from solar energy; a chemical engineering approach of the scale up, Proc. Am. Inst. Chem. Eng. Ann. Meeting, Indianapolis 2002, in print

3.57 G. G. Tibbets, M. Endo, C. P. Beetz: Carbon fibers grown from the vapor phase: A novel material, SAMPE J. **22** (1989) 30

3.58 R. T. K. Baker: Catalytic growth of carbon filaments, Carbon **27** (1989) 315–323

3.59 R. T. K. Baker, P. S. Harris, R. B. Thomas, R. J. Waite: Formation of filamentous carbon from iron, cobalt, and chromium catalyzed decomposition of acetylene, J. Catal. **30** (1973) 86–95

3.60 T. Koyama, M. Endo, Y. Oyuma: Carbon fibers obtained by thermal decomposition of vaporized hydrocarbon, Jap. J. Appl. Phys. **11** (1972) 445–449

3.61 M. Endo, A. Oberlin, T. Koyama: High resolution electron microscopy of graphitizable carbon fiber prepared by benzene decomposition, Jap. J. Appl. Phys. **16** (1977) 1519–1523

3.62 N. M. Rodriguez: A review of catalytically grown carbon nanofibers, J. Mater. Res. **8** (1993) 3233–3250

3.63 W. R. Davis, R. J. Slawson, G. R. Rigby: An unusual form of carbon, Nature **171** (1953) 756

3.64 H. P. Boehm: Carbon from carbon monoxide disproportionation on nickel and iron catalysts; morphological studies and possible growth mechanisms, Carbon **11** (1973) 583–590

3.65 M. Audier, A. Oberlin, M. Coulon: Crystallographic orientations of catalytic particles in filamentous carbon; case of simple conical particles, J. Cryst. Growth **55** (1981) 546–549

3.66 M. Audier, M. Coulon: Kinetic and microscopic aspects of catalytic carbon growth, Carbon **23** (1985) 317–323

3.67 M. Audier, A. Oberlin, M. Coulon: Study of biconic microcrystals in the middle of carbon tubes obtained by catalytic disproportionation of CO, J. Cryst. Growth **57** (1981) 524–534

3.68 A. Thaib, G. A. Martin, P. Pinheiro, M. C. Schouler, P. Gadelle: Formation of carbon nanotubes from the carbon monoxide disproportionation reaction over CO/Al_2O' and Co/SiO' catalysts, Catal. Lett. **63** (1999) 135–141

3.69 P. Pinheiro, M. C. Schouler, P. Gadelle, M. Mermoux, E. Dooryhée: Effect of hydrogen on the orientation of carbon layers in deposits from the carbon monoxide disproportionation reaction over Co/Al_2O_3 catalysts, Carbon **38** (2000) 1469–1479

3.70 P. Pinheiro, P. Gadelle: Chemical state of a supported iron-cobalt catalyst during CO disproportionation. I. Thermodynamic study, J. Phys. Chem. Solids **62** (2001) 1015–1021

3.71 P. Pinheiro, P. Gadelle, C. Jeandey, J. L. Oddou: Chemical state of a supported iron-cobalt catalyst during CO disproportionation. II. Experimental study, J. Phys. Chem. Solids **62** (2001) 1023–1037

3.72 C. Laurent, E. Flahaut, A. Peigney, A. Rousset: Metal nanoparticles for the catalytic synthesis of carbon nanotubes, New J. Chem. **22** (1998) 1229–1237

3.73 A. Peigney, C. Laurent, F. Dobigeon, A. Rousset: Carbon nanotubes grown in situ by a novel catalytic method, J. Mater. Res. **12** (1997) 613–615

3.74 V. Ivanov, J. B. Nagy, P. Lambin, A. Lucas, X. B. Zhang, X. F. Zhang, D. Bernaerts, G. Van Tendeloo, S. Amelinckx, J. Van Landuyt: The study of nanotubules produced by catalytic method, Chem. Phys. Lett. **223** (1994) 329–335

3.75 V. Ivanov, A. Fonseca, J. B. Nagy, A. Lucas, P. Lambin, D. Bernaerts, X. B. Zhang: Catalytic production and purification of nanotubules having fullerene-scale diameters, Carbon **33** (1995) 1727–1738

3.76 K. Hernadi, A. Fonseca, J. B. Nagy, D. Bernaerts, A. Fudala, A. Lucas: Catalytic synthesis of carbon nanotubes using zeolite support, Zeolites **17** (1996) 416–423

3.77 H. Dai, A. G. Rinzler, P. Nikolaev, A. Thess, D. T. Colbert, R. E. Smalley: Single-wall nanotubes produced by metal-catalysed disproportionation of carbon monoxide, Chem. Phys. Lett. **260** (1996) 471–475
3.78 A. M. Cassel, J. A. Raymakers, J. Kong, H. Dai: Large scale CVD synthesis of single-walled carbon nanotubes, J. Phys. Chem. B **109** (1999) 6484–6492
3.79 B. Kitiyanan, W. E. Alvarez, J. H. Harwell, D. E. Resasco: Controlled production of single-wall carbon nanotubes by catalytic decomposition of CO on bimetallic Co-Mo catalysts, Chem. Phys. Lett. **317** (2000) 497–503
3.80 E. Flahaut: Synthèse par voir catalytique et caractérisation de composites nanotubes de carbone-metal-oxyde Poudres et matériaux denses. Ph.D. Thesis (Univers. Paul Sabatier, Toulouse 1999)
3.81 A. Govindaraj, E. Flahaut, C. Laurent, A. Peigney, A. Rousset, C. N. R. Rao: An investigation of carbon nanotubes obtained from the decomposition of methane over reduced $Mg_{1-x}M_xAl_2O_4$ spinel catalysts, J. Mater. Res. **14** (1999) 2567–2576
3.82 E. Flahaut, A. Peigney, C. Laurent, A. Rousset: Synthesis of single-walled carbon nanotube-Co-MgO composite powders and extraction of the nanotubes, J. Mater. Chem. **10** (2000) 249–252
3.83 J. Kong, A. M. Cassel, H. Dai: Chemical vapor deposition of methane for single-walled carbon nanotubes, Chem. Phys. Lett. **292** (1998) 567–574
3.84 R. Marangoni, P. Serp, R. Feurrer, Y. Kihn, P. Kalck, C. Vahlas: Carbon nanotubes produced by substrate free metalorganic chemical vapor deposition of iron catalyst and ethylene, Carbon **39** (2001) 443–449
3.85 R. Sen, A. Govindaraj, C. N. R. Rao: Carbon nanotubes by the metallocene route, Chem. Phys. Lett. **267** (1997) 276–280
3.86 Y. Y. Fan, H. M. Cheng, Y. L. Wei, G. Su, S. H. Shen: The influence of preparation parameters on the mass production of vapor grown carbon nanofibers, Carbon **38** (2000) 789–795
3.87 L. Ci, J. Wei, B. Wei, J. Liang, C. Xu, D. Wu: Carbon nanofibers and single-walled carbon nanotubes prepared by the floating catalyst method, Carbon **39** (2001) 329–335
3.88 O. A. Nerushev, M. Sveningsson, L. K. L. Falk, F. Rohmund: Carbon nanotube films obtained by thermal vapour deposition, J. Mater. Chem. **11** (2001) 1122–1132
3.89 F. Rohmund, L. K. L. Falk, F. E. B. Campbell: A simple method for the production of large arrays of aligned carbon nanotubes, Chem. Phys. Lett. **328** (2000) 369–373
3.90 G. G. Tibbets, C. A. Bernardo, D. W. Gorkiewicz, R. L. Alig: Role of sulfur in the production of carbon fibers in the vapor phase, Carbon **32** (1994) 569–576
3.91 W. Q. Han, P. Kholer-Riedlich, T. Seeger, F. Ernst, M. Ruhle, N. Grobert, W. K. Hsu, B. H. Chang, Y. Q. Zhu, H. W. Kroto, M. Terrones, H. Terrones: Aligned CN_x nanotubes by pyrolysis of ferrocene under NH_3 atmosphere, Appl. Phys. Lett. **77** (2000) 1807–1809
3.92 R. E. Smalley, J. H. Hafner, D. T. Colbert, K. Smith: Catalytic growth of single-wall carbon nanotubes from metal particles, US patent US19980601010903 (1998)
3.93 T. Kyotani, L. F. Tsai, A. Tomita: Preparation of ultrafine carbon tubes in nanochannels of an anodic aluminum oxide film, Chem. Mater. **8** (1996) 2109–2113
3.94 W. K. Hsu, J. P. Hare, M. Terrones, H. W. Kroto, D. R. M. Walton, P. J. F. Harris: Condensed-phase nanotubes, Nature **377** (1995) 687
3.95 W. S. Cho, E. Hamada, Y. Kondo, K. Takayanagi: Synthesis of carbon nanotubes from bulk polymer, Appl. Phys. Lett. **69** (1996) 278–279
3.96 Y. L. Li, Y. D. Yu, Y. Liang: A novel method for synthesis of carbon nanotubes: Low temperature solid pyrolysis, J. Mater. Res. **12** (1997) 1678–1680
3.97 S. Fan, M. Chapline, N. Franklin, T. Tombler, A. M. Cassel, H. Dai: Self-oriented regular arrays of carbon nanotubes and their field emission properties, Science **283** (1999) 512–514
3.98 M. L. Terranova, S. Piccirillo, V. Sessa, P. Sbornicchia, M. Rossi, S. Botti, D. Manno: Growth of single-walled carbon nanotubes by a novel technique using nanosized graphite as carbon source, Chem. Phys. Lett. **327** (2000) 284–290
3.99 R. L. Vander Wal, T. Ticich, V. E. Curtis: Diffusion flame synthesis of single-walled carbon nanotubes, Chem. Phys. Lett. **323** (2000) 217–223
3.100 Y. Y. Wei, G. Eres, V. I. Merkulov, D. H. Lowdens: Effect of film thickness on carbon nanotube growth by selective area chemical vapor deposition, Appl. Phys. Lett. **78** (2001) 1394–1396
3.101 W. Z. Li, S. S. Xie, L. X. Qian, B. H. Chang, B. S. Zou, W. Y. Zhou, R. A. Zha, G. Wang: Large scale synthesis of aligned carbon nanotubes, Science **274** (1996) 1701–1703
3.102 F. Zheng, L. Liang, Y. Gao, J. H. Sukamto, L. Aardahl: Carbon nanotubes synthesis using mesoporous silica templates, Nanolett. **2** (2002) 729–732
3.103 S. H. Jeong, O.-K. Lee, K. H. Lee, S. H. Oh, C. G. Park: Preparation of aligned carbon nanotubes with prescribed dimension: Template synthesis and sonication cutting approach, Chem. Mater. **14** (2002) 1859–1862
3.104 N. S. Kim, Y. T. Lee, J. Park, H. Ryu, H. J. Lee, S. Y. Choi, J. Choo: Dependence of vertically aligned growth of carbon nanotubes on catalyst, J. Phys. Chem. B **106** (2002) 9286–9290
3.105 C. J. Lee, D. W. Kim, T. J. Lee, Y. C. Choi, Y. S. Park, Y. H. Lee, W. B. Choi, N. S. Lee, G.-S. Park, J. M. Kim: Synthesis of aligned carbon nanotubes using thermal chemical vapor deposition, Chem. Phys. Lett. **312** (1999) 461–468
3.106 W. D. Zhang, Y. Wen, S. M. Liu, W. C. Tjiu, G. Q. Xu, L. M. Gan: Synthesis of vertically aligned carbon

nanotubes on metal deposited quartz plates, Carbon **40** (2002) 1981–1989
3.107 S. Huang, L. Dai, A. W. H. Mau: Controlled fabrication of large scale aligned carbon nanofiber/nanotube patterns by photolithography, Adv. Mater. **14** (2002) 1140–1143
3.108 R. Andrews, D. Jacques, A. M. Rao, F. Derbyshire, D. Qian, X. Fan, E. C. Dickey, J. Chen: Continous production of aligned carbon nanotubes: A step closer to commercial realization, Chem. Phys. Lett. **303** (1999) 467–474
3.109 C. N. R. Rao, R. Sen, B. C. Satishkumar, A. Govindaraj: Large aligned carbon nanotubes bundles from ferrocene pyrolysis, Chem. Commun. **15** (1998) 1525–1526
3.110 X. Zhang, A. Cao, B. Wei, Y. Li, J. Wei, C. Xu, D. Wu: Rapid growth of well-aligned carbon nanotube arrays, Chem. Phys. Lett. **362** (2002) 285–290
3.111 X. Zhang, A. Cao, Y. Li, C. Xu, J. Liang, D. Wu, B. Wei: Self-organized arrays of carbon nanotube ropes, Chem. Phys. Lett. **351** (2002) 183–188
3.112 K. S. Choi, Y. S. Cho, S. Y. Hong, J. B. Park, D. J. Kim: Effects of ammonia on the alignment of carbon nanotubes in metal-assisted chemical vapor deposition, J. Eur. Cer. Soc. **21** (2001) 2095–2098
3.113 M. Endo, H. W. Kroto: Formation of carbon nanofibers, J. Phys. Chem. **96** (1992) 6941–6944
3.114 R. S. Wagner: VLS mechanisms of crystal growth. In: *Whisker Technology*, ed. by P. Levit A. (Wiley, New York 1970) pp. 47–72
3.115 Y. H. Lee, S. G. Kim, D. Tomanek: Catalytic growth of single-wall carbon nanotubes: An ab initio study, Phys. Rev. Lett. **78** (1997) 2393–2396
3.116 H. Dai: Carbon Nanotubes: Synthesis, integration, and properties, Acc. Chem. Res. **35** (2002) 1035–1044
3.117 Y. Saito, M. Okuda, N. Fujimoto, T. Yoshikawa, M. Tomita, T. Hayashi: Single-wall carbon nanotubes growing radially from Ni fine particles formed by arc evaporation, Jpn. J. Appl. Phys. **33** (1994) L526–L529
3.118 J. Bernholc, C. Brabec, M. Buongiorno Nardelli, A. Malti, C. Roland, B. J. Yakobson: Theory of growth and mechanical properties of nanotubes, Appl. Phys. A **67** (1998) 39–46
3.119 M. Pacheco: Synthèse des nanotubes de carbone par arc electrique. Ph.D. Thesis (Université Toulouse III, Toulouse 2003)
3.120 K. Méténier, S. Bonnamy, F. Béguin, C. Journet, P. Bernier, L. M. de la Chapelle, O. Chauvet, S. Lefrant: Coalescence of single walled nanotubes and formation of multi-walled carbon nanotubes under high temperature treatments, Carbon **40** (2002) 1765–1773
3.121 P. G. Collins, P. Avouris: Nanotubes for electronics, Sci. Am. **283** (2000) 38–45
3.122 Q.-H. Yang, P. X. Hou, S. Bai, M. Z. Wang, H. M. Cheng: Adsorption and capillarity of nitrogen in aggregated multi-walled carbon nanotubes, Chem. Phys. Lett. **345** (2001) 18–24
3.123 S. Inoue, N. Ichikuni, T. Suzuki, T. Uematsu, K. Kaneko: Capillary condensation of N_2 on multi-wall carbon nanotubes, J. Phys. Chem. **102** (1998) 4689–4692
3.124 M. Eswaramoorthy, R. Sen, C. N. R. Rao: A study of micropores in single-walled carbon nanotubes by the adsorption of gases and vapors, Chem. Phys. Lett. **304** (1999) 207–210
3.125 A. Peigney, Ch. Laurent, E. Flahaut, R. R. Bacsa, A. Rousset: Specific surface area of carbon nanotubes and bundles of carbon nanotubes, Carbon **39** (2001) 507–514
3.126 E. Frackowiak, S. Delpeux, K. Jurewicz, K. Szostak, D. Cazorla-Amoros, F. Béguin: Enhanced capacitance of carbon nanotubes through chemical activation, Chem. Phys. Lett. **336** (2002) 35–41
3.127 M. Muris, N. Dupont-Pavlosky, M. Bienfait, P. Zeppenfeld: Where are the molecules adsorbed on single-walled nanotubes?, Surf. Sci. **492** (2001) 67–74
3.128 A. Fujiwara, K. Ishii, H. Suematsu, H. Kataura, Y. Maniwa, S. Suzuki, Y. Achiba: Gas adsorption in the inside and outside of single-walled carbon nanotubes, Chem. Phys. Lett. **336** (2001) 205–211
3.129 C. M. Yang, H. Kanoh, K. Kaneko, M. Yudasaka, S. Iijima: Adsorption behaviors of HiPco single-walled carbon nanotubes aggregates for alcohol vapors, J. Phys. Chem. **106** (2002) 8994–8999
3.130 J. Zhao, A. Buldum, J. Han, J. P. Lu: Gas molecule adsorption in carbon nanotubes and nanotube bundles, Nanotechnology **13** (2002) 195–200
3.131 K. A. Williams, P. C. Eklund: Monte Carlo simulation of H_2 physisorption in finite diameter carbon nanotube ropes, Chem. Phys. Lett. **320** (2000) 352–358
3.132 A. Chambers, C. Park, R. T. K. Baker, N. Rodriguez: Hydrogen storage in graphite nanofibers, J. Phys. Chem. B. **102** (1998) 4253–4256
3.133 J. Hilding, E. A. Grulke, S. B. Sinnott, D. Qian, R. Andrews, M. Jagtoyen: Sorption of butane on carbon multiwall nanotubes at room temperature, Langmuir **17** (2001) 7540–7544
3.134 K. Masenelli-Varlot, E. McRae, N. Dupont-Pavlosky: Comparative adsorption of simple molecules on carbon nanotubes. Dependence of the adsorption properties on the nanotube morphology, Appl. Surf. Sci. **196** (2002) 209–215
3.135 D. J. Browning, M. L. Gerrard, J. B. Lakeman, I. M. Mellor, R. J. Mortimer, M. C. Turpin: Studies into the storage of hydrogen in carbon nanofibers: Proposal of a possible mechanism, Nanolett. **2** (2002) 201–205
3.136 F. H. Yang, R. T. Yang: Ab initio molecular orbital study of adsorption of atomic hydrogen on graphite: insight into hydrogen storage in carbon nanotubes, Carbon **40** (2002) 437–444
3.137 G. E. Froudakis: Why alkali-metal-doped carbon nanotubes possess high hydrogen uptake, Nanolett. **1** (2001) 531–533

3.138 H. Ulbricht, G. Moos, T. Hertel: Physisorption of molecular oxygen on single-wall carbon nanotube bundles and graphite, Phys. Rev. B **66** (2002) 075404-1–075404-7

3.139 H. Ulbricht, J. Kriebel, G. Moos, T. Hertel: Desorption kinetics and interaction of Xe with single-wall carbon nanotube bundles, Chem. Phys. Lett. **363** (2002) 252–260

3.140 R. Saito, G. Dresselhaus, M.S. Dresselhaus: *Physical Properties of Carbon Nanotubes* (Imperial College Press, London 1998)

3.141 A. Charlier, E. McRae, R. Heyd, M.F. Charlier, D. Moretti: Classification for double-walled carbon nanotubes, Carbon **37** (1999) 1779–1783

3.142 A. Charlier, E. McRae, R. Heyd, M.F. Charlier: Metal semi-conductor transitions under uniaxial stress for single- and double-walled carbon nanotubes, J. Phys. Chem. Solids **62** (2001) 439–444

3.143 H. Ajiki, T. Ando: Electronic states of carbon nanotubes, J. Phys. Soc. Jap. **62** (1993) 1255–1266

3.144 C.T. White, T.N. Todorov: Carbon nanotubes as long ballistic conductors, Nature **393** (1998) 240–242

3.145 S. Frank, P. Poncharal, Z.L. Wang, W.A. de Heer: Carbon nanotube quantum resistors, Science **280** (1998) 1744–1746

3.146 W. Liang, M. Bockrath, D. Bozovic, J.H. Hafner, M. Tinkham, H. Park: Fabry–Perot interference in a nanotube electron waveguide, Nature **411** (2001) 665–669

3.147 L. Langer, V. Bayot, E. Grivei, J.-P. Issi, J.-P. Heremans, C.H. Olk, L. Stockman, C. van Haesendonck, Y. Buynseraeder: Quantum transport in a multiwalled carbon nanotube, Phys. Rev. Lett. **76** (1996) 479–482

3.148 M. Bockrath, D.H. Cobden, J. Lu, A.G. Rinzler, R.E. Smalley, L. Balents, P.L. McEuen: Luttinger-liquid behaviour in carbon nanotubes, Nature **397** (1999) 598–601

3.149 K. Liu, S. Roth, G.S. Duesberg, G.T. Kim, D. Popa, K. Mukhopadhyay, R. Doome, J. B'Nagy: Antilocalization in multiwalled carbon nanotubes, Phys. Rev. B **61** (2000) 2375–2379

3.150 Y.A. Kasumov, R. Deblock, M. Kociak, B. Reulet, H. Bouchiat, I.I. Khodos, Y.B. Gorbatov, V.T. Volkov, C. Journet, M. Burghard: Supercurrents through single-walled carabon nanotubes, Science **284** (1999) 1508–1511

3.151 B.W. Alphenaar, K. Tsukagoshi, M. Wagner: Magnetoresistance of ferromagnetically contacted carbon nanotubes, Phys. Eng. **10** (2001) 499–504

3.152 P.M. Ajayan, M. Terrrones, A. de la Guardia, V. Hue, N. Grobert, B.Q. Wei, H. Lezec, G. Ramanath, T.W. Ebbesen: Nanotubes in a flash – Ignition and reconstruction, Science **296** (2002) 705

3.153 S. Berber, Y. Kwon, D. Tomanek: Unusually high thermal conductivity of carbon nanotubes, Phys. Rev. Lett. **84** (2000) 4613–4616

3.154 S.N. Song, X.K. Wang, R.P.H. Chang, J.B. Ketterson: Electronic properties of graphite nanotubules from galvanomagnetic effects, Phys. Rev. Lett. **72** (1994) 697–700

3.155 M.-F. Yu, O. Lourie, M.J. Dyer, K. Moloni, T.F. Kelley, R.S. Ruoff: Strength and breaking mechanism of multiwalled carbon nanotubes under tensile load, Science **287** (2000) 637–640

3.156 D.A. Walters, L.M. Ericson, M.J. Casavant, J. Liu, D.T. Colbert, K.A. Smith, R.E. Smalley: Elastic strain of freely suspended single-wall carbon nanotube ropes, Appl. Phys. Lett. **74** (1999) 3803–3805

3.157 B.G. Demczyk, Y.M. Wang, J. Cumingd, M. Hetamn, W. Han, A. Zettl, R.O. Ritchie: Direct mechanical measurement of the tensile strength and eleastic modulus of multiwalled carbon nanotubes, Mater. Sci. Eng. A **334** (2002) 173–178

3.158 R.P. Gao, Z.L. Wang, Z.G. Bai, W.A. De Heer, L.M. Dai, M. Gao: Nanomechanics of inidividual carbon nanotubes from pyrolytically grown arrays, Phys. Rev. Lett. **85** (2000) 622–625

3.159 M.M.J. Treacy, T.W. Ebbesen, J.M. Gibson: Exceptionally high Young's modulus observed for individual carbon nanotubes, Nature **381** (1996) 678–680

3.160 N. Yao, V. Lordie: Young's modulus of single-wall carbon nanotubes, J. Appl. Phys. **84** (1998) 1939–1943

3.161 O. Lourie, H.D. Wagner: Transmission electron microscopy observations of fracture of single-wall carbon nanotubes under axial tension, Appl. Phys. Lett. **73** (1998) 3527–3529

3.162 S.C. Tsang, Y.K. Chen, P.J.F. Harris, M.L.H. Green: A simple chemical method of opening and filling carbon nanotubes, Nature **372** (1994) 159–162

3.163 M. Montioux: Filling single-wall carbon nanotubes, Carbon **40** (2002) 1809–1823

3.164 W.K. Hsu, S.Y. Chu, E. Munoz-Picone, J.L. Boldu, Firth S., P. Franchi, B.P. Roberts, A. Shilder, H. Terrones, N. Grobert, Y.Q. Zhu, M. Terrones, M.E. McHenry, H.W. Kroto, D.R.M. Walton: Metallic behaviour of boron-containing carbon nanotubes, Chem. Phys. Lett. **323** (2000) 572–579

3.165 R. Czerw, M. Terrones, J.C. Charlier, X. Blasé, B. Foley, R. Kamalakaran, N. Grobert, H. Terrones, D. Tekleab, P.M. Ajayan, W. Blau, M. Rühle, D.L. Caroll: Identification of electron donor states, in N-doped carbon nanotubes, Nanolett. **1** (2001) 457–460

3.166 O. Stephan, P.M. Ajayan, C. Colliex, P. Redlich, J.M. Lambert, P. Bernier, P. Lefin: Doping graphitic and carbon nanotube structures with boron and nitrogen, Science **266** (1994) 1683–1685

3.167 A. Loiseau, F. Willaime, N. Demoncy, N. Schramchenko, G. Hug, C. Colliex, H. Pascard: Boron nitride nanotubes, Carbon **36** (1998) 743–752

3.168 C.C. Tang, L.M. de la Chapelle, P. Li, Y.M. Liu, H.Y. Dang, S.S. Fan: Catalytic growth of nanotube and nanobamboo structures of boron nitride, Chem. Phys. Lett. **342** (2001) 492–496

3.169 K. Suenaga, C. Colliex, N. Demoncy, A. Loiseau, H. Pascard, F. Willaime: Synthesis of nanoparticles and nanotubes with well separated layers of boron-nitride and carbon, Science **278** (1997) 653–655

3.170 D. Golberg, Y. Bando, L. Bourgeois, K. Kurashima, T. Sato: Large-scale synthesis and HRTEM analysis of single-walled B-and N-doped carbon nanotube bundles, Carbon **38** (2000) 2017–2027

3.171 B. Burteaux, A. Claye, B.W. Smith, M. Monthioux, D.E. Luzzi, J.E. Fischer: Abundance of encapsulated C_{60} in single-wall carbon nanotubes, Chem. Phys. Lett. **310** (1999) 21–24

3.172 D. Ugarte, A. Châtelain, W.A. de Heer: Nanocapillarity and chemistry in carbon nanotubes, Science **274** (1996) 1897–1899

3.173 J. Cook, J. Sloan, M.L.H. Green: Opening and filling carbon nanotubes, Fuller. Sci. Technol. **5** (1997) 695–704

3.174 P.M. Ajayan, S. Iijima: Capillarity-induced filling of carbon nanotubes, Nature **361** (1993) 333–334

3.175 P.M. Ajayan, T.W. Ebbesen, T. Ichihashi, S. Iijima, K. Tanigaki, H. Hiura: Opening carbon nanotubes with oxygen and implications for filling, Nature **362** (1993) 522–525

3.176 S. Seraphin, D. Zhou, J. Jiao, J.C. Withers, R. Loufty: Yttrium carbide in nanotubes, Nature **362** (1993) 503

3.177 S. Seraphin, D. Zhou, J. Jiao, J.C. Withers, R. Loufty: Selective encapsulation of the carbides of yttrium and titanium into carbon nanoclusters, Appl. Phys. Lett. **63** (1993) 2073–2075

3.178 R.S. Ruoff, D.C. Lorents, B. Chan, R. Malhotra, S. Subramoney: Single-crystal metals encapsulated in carbon nanoparticles, Science **259** (1993) 346–348

3.179 A. Loiseau, H. Pascard: Synthesis of long carbon nanotubes filled with Se, S, Sb, and Ge by the arc method, Chem. Phys. Lett. **256** (1996) 246–252

3.180 N. Demoncy, O. Stephan, N. Brun, C. Colliex, A. Loiseau, H. Pascard: Filling carbon nanotubes with metals by the arc discharge method: The key role of sulfur, Eur. Phys. J. B **4** (1998) 147–157

3.181 C.H. Kiang, J.S. Choi, T.T. Tran, A.D. Bacher: Molecular nanowires of 1 nm diameter from capillary filling of single-walled carbon nanotubes, J. Phys. Chem. B **103** (1999) 7449–7551

3.182 Z.L. Zhang, B. Li, Z.J. Shi, Z.N. Gu, Z.Q. Xue, L.M. Peng: Filling of single-walled carbon nanotubes with silver, J. Mater. Res. **15** (2000) 2658–2661

3.183 A. Govindaraj, B.C. Satishkumar, M. Nath, C.N.R. Tao: Metal nanowires and intercalated metal layers in single-walled carbon nanotubes bundles, Chem. Mater. **12** (2000) 202–205

3.184 J. Mittal, M. Monthioux, H. Allouche: Synthesis of SWNT-based hybrid nanomaterials from photolysis-enhanced chemical processes, Chem. Phys. Lett. **339** (2001) 311–318

3.185 E. Dujardin, T.W. Ebbesen, H. Hiura, K. Tanigaki: Capillarity and wetting of carbon nanotubes, Science **265** (1994) 1850–1852

3.186 E. Flahaut, J. Sloan, K.S. Coleman, V.C. Williams, S. Friedrichs, N. Hanson, M.L.H. Green: 1D p-block halide crystals confined into single walled carbon nanotubes, Proc. Mater. Res. Soc. Symp. **633** (2001) A13.15.1–A13.15.6

3.187 J. Sloan, A.I. Kirkland, J.L. Hutchison, M.L.H. Green: Integral atomic layer architectures of 1D crystals inserted into single walled carbon nanotubes, Chem. Commun. (2002) 1319–1332

3.188 J. Sloan, M.C. Novotny, S.R. Bailey, G. Brown, C. Xu, V.C. Williams, S. Friedrichs, E. Flahaut, R.L. Callender, A.P.E. York, K.S. Coleman, M.L.H. Green, R.E. Dunin-Borkowski, J.L. Hutchison: Two layer 4 : 4 co-ordinated KI crystals grown within single walled carbon nanotubes, Chem. Phys. Lett. **329** (2000) 61–65

3.189 G. Brown, S.R. Bailey, J. Sloan, C. Xu, S. Friedriechs, E. Flahaut, K.S. Coleman, J.L. Hutchinson, R.E. Dunin-Borkowski, M.L.H. Green: Electron beam induced in situ clusterisation of 1D $ZrCl_4$ chains within single-walled carbon nanotubes, Chem. Commun. **9** (2001) 845–846

3.190 B.W. Smith, M. Monthioux, D.E. Luzzi: Encapsulated C_{60} in carbon nanotubes, Nature **396** (1998) 323–324

3.191 B.W. Smith, D.E. Luzzi: Formation mechanism of fullerene peapods and coaxial tubes: A path to large scale synthesis, Chem. Phys. Lett. **321** (2000) 169–174

3.192 K. Hirahara, K. Suenaga, S. Bandow, H. Kato, T. Okazaki, H. Shinohara, S. Iijima: One-dimensional metallo-fullerene crystal generated inside single-walled carbon nanotubes, Phys. Rev. Lett. **85** (2000) 5384–5387

3.193 B.W. Smith, M. Monthioux, D.E. Luzzi: Carbon nanotube encapsulated fullerenes: A unique class of hybrid material, Chem. Phys. Lett. **315** (1999) 31–36

3.194 D.E. Luzzi, B.W. Smith: Carbon cage structures in single wall carbon nanotubes: A new class of materials, Carbon **38** (2000) 1751–1756

3.195 S. Bandow, M. Takisawa, K. Hirahara, M. Yudasoka, S. Iijima: Raman scattering study of double-wall carbon nanotubes derived from the chains of fullerenes in single-wall carbon nanotubes, Chem. Phys. Lett. **337** (2001) 48–54

3.196 B.W. Smith, D.E. Luzzi, Y. Achiba: Tumbling atoms and evidence for charge transfer in $La_2@C_{80}@$SWNT, Chem. Phys. Lett. **331** (2000) 137–142

3.197 K. Suenaga, M. Tence, C. Mory, C. Colliex, H. Kato, T. Okazaki, H. Shinohara, K. Hirahara, S. Bandow, S. Iijima: Element-selective single atom imaging, Science **290** (2000) 2280–2282

3.198 D.E. Luzzi, B.W. Smith, R. Russo, B.C. Satishkumar, F. Stercel, N.R.C. Nemes: Encapsulation of metallofullerenes and metallocenes in carbon nanotubes, Proc. Electronic Properties of Novel Materials-XVI Int. Winterschool – AIP Conf. Proc., Melville 2001, ed. by

H. Kuzmany, J. Fink, M. Mehring, S. Roth (Springer, Berlin, Heidelberg 2001) **591** 622–626

3.199 G. H. Jeong, R. Hatakeyama, T. Hirata, K. Tohji, K. Motomiya, N. Sato, Y. Kawazoe: Structural deformation of single-walled carbon nanotubes and fullerene encapsulation due to magnetized plasma ion irradiation, Appl. Phys. Lett. **79** (2001) 4213–4215

3.200 Y. P. Sun, K. Fu, Y. Lin, W. Huang: Functionalized carbon nanotubes: Properties and applications, Acc. Chem. Res. **35** (2002) 1095–1104

3.201 J. Chen, M. A. Hamon, M. Hui, C. Yongsheng, A. M. Rao, P. C. Eklund, R. C. Haddon: Solution properties of single-walled carbon nanotubes, Science **282** (1998) 95–98

3.202 J. Chen, A. M. Rao, S. Lyuksyutov, M. E. Itkis, M. A. Hamon, H. Hu, R. W. Cohn, P. C. Eklund, D. T. Colbert, R. E. Smalley, R. C. Haddon: Dissolution of full-length single-walled carbon nanotubes, J. Phys. Chem. B **105** (2001) 2525–2528

3.203 F. Pompeo, D. E. Resasco: Water solubilization of single-walled carbon nanotubes by functionalization with glucosamine, Nanolett. **2** (2002) 369–373

3.204 Y. P. Sun, W. Huang, Y. Lin, K. Fu, A. Kitaygorodskiy, L. A. Riddle, Y. J. Yu, D. L. Carroll: Soluble dendron-functionalized carbon nanotubes: Preparation, characterization, and properties, Chem. Mater. **13** (2001) 2864–2869

3.205 K. Fu, W. Huang, Y. Lin, L. A. Riddle, D. L. Carroll, Y. P. Sun: Defunctionalization of functionalized carbon nanotubes, Nanolett. **1** (2001) 439–441

3.206 P. W. Chiu, G. S. Duesberg, U. Dettlaff-Weglikowska, S. Roth: Interconnection of carbon nanotubes by chemical functionalization, Appl. Phys. Lett. **80** (2002) 3811–3813

3.207 E. T. Mickelson, C. B. Huffman, A. G. Rinzler, R. E. Smalley, R. H. Hauge, J. L. Margrave: Fluorination of single-wall carbon nanotubes, Chem. Phys. Lett. **296** (1998) 188–194

3.208 V. N. Khabashesku, W. E. Billups, J. L. Margrave: Fluorination of single-wall carbon nanotubes and subsequent derivatization reactions, Acc. Chem. Res. **35** (2002) 1087–1095

3.209 P. J. Boul, J. Liu, E. T. Michelson, C. B. Huffman, L. M. Ericson, I. W. Chiang, K. A. Smith, D. T. Colbert, R. H. Hauge, J. L. Margrave, R. E. Smalley: Reversible side-wall functionalization of buckytubes, Chem. Phys. Lett. **310** (1999) 367–372

3.210 J. L. Bahr, J. Yang, D. V. Kosynkin, M. J. Bronikowski, R. E. Smalley, J. M. Tour: Functionalization of carbon nanotubes by electrochemical reduction of aryl diazonium salts: A bucky paper electrode, J. Am. Chem. Soc. **123** (2001) 6536–6542

3.211 M. Holzinger, O. Vostrowsky, A. Hirsch, F. Hennrich, M. Kappes, R. Weiss, F. Jellen: Sidewall functionalization of carbon nanotubes, Angew. Chem. Int. Ed. **40** (2001) 4002–4005

3.212 Y. Chen, R. C. Haddon, S. Fang, A. M. Rao, P. C. Eklund, W. H. Lee, E. C. Dickey, E. A. Grulke, J. C. Pendergrass, A. Chavan, B. E. Haley, R. E. Smalley: Chemical attachment of organic functional groups to single-walled carbon nanotube material, J. Mater. Res. **13** (1998) 2423–2431

3.213 C. Velasco-Santos, A. L. Martinez-Hernandez, M. Lozada-Cassou, A. Alvarez-Castillo, V. M. Castano: Chemical functionalization of carbon nanotubes through an organosilane, Nanotechnology **13** (2002) 495–498

3.214 A. Star, J. F. Stoddart, D. Steuerman, M. Diehl, A. Boukai, E. W. Wong, X. Yang, S. W. Chung, H. Choi, J. R. Heath: Preparation and properties of polymer-wrapped single-walled carbon nanotubes, Angew. Chem. Int. Ed. **41** (2002) 1721–1725

3.215 J. H. Hafner, C. L. Cheung, A. T. Wooley, C. M. Lieber: Structural and functional imaging with carbon nanotube AFM probes, Progr. Biophys. Molec. Biol. **77** (2001) 73–110

3.216 S. S. Wong, E. Joselevich, A. T. Woodley, C. L. Cheung, C. M. Lieber: Covalently functionalized nanotubes as nanometre-size probes in chemistry and biology, Nature **394** (1998) 52–55

3.217 C. L. Cheung, J. H. Hafner, C. M. Lieber: Carbon nanotube atomic force microscopy tips: Direct growth by chemical vapor deposition and application to high-resolution imaging, Proc. Nat. Acad. Sci. (2000) 973809–973813

3.218 W. A. de Heer, A. Châtelain, D. Ugarte: A carbon nanotube field-emission electron source, Science **270** (1995) 1179–1180

3.219 J. M. Bonard, J. P. Salvetat, T. Stockli, W. A. de Heer, L. Forro, A. Chatelain: Field emission from single-wall carbon nanotube films, Appl. Phys. Lett. **73** (1998) 918–920

3.220 W. Zhu, C. Bower, O. Zhou, G. Kochanski, S. Jin: Large curent density from carbon nanotube field emitters, Appl. Phys. Lett. **75** (1999) 873–875

3.221 Y. Saito, R. Mizushima, T. Tanaka, K. Tohji, K. Uchida, M. Yumura, S. Uemura: Synthesis, structure, and field emission of carbon nanotubes, Fuller. Sci. Technol. **7** (1999) 653–664

3.222 J. Kong, N. R. Franklin, C. Zhou, M. G. Chapline, S. Peng, K. Cho, H. Dai: Nanotube molecular wire as chemical sensors, Science **287** (2000) 622–625

3.223 P. G. Collins, K. Bradley, M. Ishigami, A. Zettl: Extreme oxygen sensitivity of electronic properties of carbon nanotubes, Science **287** (2000) 1801–1804

3.224 H. Chang, J. D. Lee, S. M. Lee, Y. H. Lee: Adsorption of NH_3 and NO_2 molecules on carbon nanotubes, Appl. Phys. Lett. **79** (2001) 3863–3865

3.225 O. K. Varghese, P. D. Kichambre, D. Gong, K. G. Ong, E. C. Dickey, C. A. Grimes: Gas sensing characteristics of multi-wall carbon nanotubes, Sens. Actuators B **81** (2001) 32–41

3.226 K. G. Ong, K. Zeng, C. A. Grimes: A wireless, passive carbon nanotube-based gas sensor, IEEE Sens. J. **2/2** (2002) 82–88

3.227 J. Kong, M. G. Chapline, H. Dai: Functionalized carbon nanotubes for molecular hydrogen sensors, Adv. Mater. **13** (2001) 1384–1386

3.228 F. Rodriguez-Reinoso: The role of carbon materials in heterogeneous catalysis, Carbon **36** (1998) 159–175

3.229 E. Auer, A. Freund, J. Pietsch, T. Tacke: Carbon as support for industrial precious metal catalysts, Appl. Catal. A **173** (1998) 259–271

3.230 J. M. Planeix, N. Coustel, B. Coq, B. Botrons, P. S. Kumbhar, R. Dutartre, P. Geneste, P. Bernier, P. M. Ajayan: Application of carbon nanotubes as supports in heterogeneous catalysis, J. Am. Chem. Soc. **116** (1994) 7935–7936

3.231 B. Coq, J. M. Planeix, V. Brotons: Fullerene-based materials as new support media in heterogeneous catalysis by metals, Appl. Catal. A **173** (1998) 175–183

3.232 G. Mestl, N. I. Maksimova, N. Keller, V. V. Roddatis, R. Schlögl: Carbon nanofilaments in heterogeneous catalysis: An industrial application for new carbon materials?, Angew. Chem. Int. Ed. Engl. **40** (2001) 2066–2068

3.233 J. E. Fischer, A. T. Johnson: Electronic properties of carbon nanotubes, Current Opinion Solid State Mater. Sci. **4** (1999) 28–33

3.234 M. Menon, A. N. Andriotis, G. E. Froudakis: Curvature dependence of the metal catalyst atom interaction with carbon nanotubes walls, Chem. Phys. Lett. **320** (2000) 425–434

3.235 R. Giordano, Ph. Serp, Ph. Kalck, Y. Kihn, J. Schreiber, C. Marhic, J.-L. Duvail: Preparation of Rhodium supported on carbon canotubes catalysts via surface mediated organometallic reaction, Eur. J. Inorg. Chem. (2003) 610–617

3.236 T. Kyotani, S. Nakazaki, W.-H. Xu, A. Tomita: Chemical modification of the inner walls of carbon nanotubes by HNO_3 oxidation, Carbon **39** (2001) 782–785

3.237 Z. J. Liu, Z. Y. Yuan, W. Zhou, L. M. Peng, Z. Xu: Co/carbon nanotubes monometallic system: The effects of oxidation by nitric acid, Phys. Chem. Chem. Phys. **3** (2001) 2518–2521

3.238 H.-B. Chen, J. D. Lin, Y. Cai, X. Y. Wang, J. Yi, J. Wang, G. Wei, Y. Z. Lin, D. W. Liao: Novel multi-walled nanotubes-supported and alkali-promoted Ru catalysts for ammonia synthesis under atmospheric pressure, Appl. Surf. Sci. **180** (2001) 328–335

3.239 Y. Zhang, H. B. Zhang, G. D. Lin, P. Chen, Y. Z. Yuan, K. R. Tsai: Preparation, characterization and catalytic hydroformylation properties of carbon nanotubes-supported Rh-phosphine catalyst, Appl. Catal. A **187** (1999) 213–224

3.240 M. S. Dresselhaus, K. A. Williams, P. C. Eklund: Hydrogen adsorption in carbon materials, Mater. Res. Soc. Bull. (November 1999) 45–50

3.241 H.-M. Cheng, Q.-H. Yang, C. Liu: Hydrogen storage in carbon nanotubes, Carbon **39** (2001) 1447–1454

3.242 G. G. Tibbetts, G. P. Meisner, C. H. Olk: Hydrogen storage capacity of carbon nanotubes, filaments, and vapor-grown fibers, Carbon **39** (2001) 2291–2301

3.243 F. L. Darkrim, P. Malbrunot, G. P. Tartaglia: Review of hydrogen storage adsorption in carbon nanotubes, Int. J. Hydrogen Energy **27** (2002) 193–202

3.244 C. Park, P. E. Anderson, C. D. Tan, R. Hidalgo, N. Rodriguez: Further studies of the interaction of hydrogen with graphite nanofibers, J. Phys. Chem. B **103** (1999) 10572–1058

3.245 C. C. Ahn, Y. Ye, B. V. Ratnakumar, C. Witham, R. C. Bowman, B. Fultz: Hydrogen adsorption measurements on graphite nanofibers, Appl. Phys. Lett. **73** (1998) 3378–3380

3.246 Q. Wang, J. K. Johnson: Computer simulations of hydrogen adsorption on graphite nanofibers, J. Phys. Chem. B **103** (1999) 277–281

3.247 M. Rzepka, P. Lamp, M. A. de la Casa-Lillo: Physisorption of hydrogen on microporous carbon and carbon nanotubes, J. Phys. Chem. B **102** (1998) 10894–10898

3.248 A. C. Dillon, K. M. Jones, T. A. Bekkedahl, C. H. Kiang, D. S. Bethune, M. J. Heben: Storage of hydrogen in single-walled carbon nanotubes, Nature **386** (1997) 377–379

3.249 Y. Ye, C. C. Ahn, C. Witham, R. C. Bowman, B. Fultz, J. Liu, A. G. Rinzler, D. Colbert, K. A. Smith, R. E. Smalley: Hydrogen adsorption and cohesive energy of single-walled carbon nanotubes, Appl. Phys. Lett. **74** (1999) 2307–2309

3.250 C. Liu, Y. Y. Fan, M. Liu, H. T. Cong, H. M. Cheng, M. S. Dresselhaus: Hydrogen storage in single-walled carbon nanotubes at room temperature, Science **286** (1999) 1127–1129

3.251 M. Hirscher, M. Becher, M. Haluska, U. Dettlaff-Weglikowska, A. Quintel, G. S. Duesberg, Y. M. Choi, P. Dwones, M. Hulman, S. Roth, I. Stepanek, P. Bernier: Hydrogen storage in sonicated carbon materials, Appl. Phys. A **72** (2001) 129–132

3.252 P. A. Gordon, R. B. Saeger: Molecular modeling of adsorptive energy storage: Hydrogen storage in single-walled carbon nanotubes, Ind. Eng. Chem. Res. **38** (1999) 4647–4655

3.253 P. Marinelli, R. Pellenq, J. Conard: H stocké dans les carbones un site légèrement métastable, matériaux, Tours 2002 AF-14-020

3.254 S. M. Lee, H. Y. Lee: Hydrogen storage in single-walled carbon nanotubes, Appl. Phys. Lett. **76** (2000) 2877–2879

3.255 S. M. Lee, K. S. Park, Y. C. Choi, Y. S. Park, J. M. Bok, D. J. Bae, K. S. Nahm, Y. G. Choi, C. S. Yu, N. Kim, T. Frauenheim, Y. H. Lee: Hydrogen adsorption in carbon nanotubes, Synth. Met. **113** (2000) 209–216

3.256 H. Cheng, G. P. Pez, A. C. Cooper: Mechanism of hydrogen sorption in single-walled carbon nanotubes, J. Am. Chem. Soc. **123** (2001) 5845–5846

3.257 A. Kusnetzova, D. B. Mawhinney, V. Naumenko, J. T. Yates, J. Liu, R. E. Smalley: Enhancement of adsorption inside of single-walled nanotubes: Opening the entry ports, Chem. Phys. Lett. **321** (2000) 292–296

3.258 G. E. Gadd, M. Blackford, S. Moricca, N. Webb, P. J. Evans, A. M. Smith, G. Jacobsen, S. Leung, A. Day, Q. Hua: The world's smallest gas cylinders?, Science **277** (1997) 933–936

3.259 Z. Mao, S. B. Sinnott: A computational study of molecular diffusion and dynamic flow through carbon nanotubes, J. Phys. Chem. B **104** (2000) 4618–4624

3.260 Z. Mao, S. B. Sinnott: Separation of organic molecular mixtures in carbon nanotubes and bundles: Molecular dynamics simulations, J. Phys. Chem. B **105** (2001) 6916–6924

3.261 C. Gu, G.-H. Gao, Y. X. Yu, T. Nitta: Simulation for separation of hydrogen and carbon monoxide by adsorption on single-walled carbon nanotubes, Fluid Phase Equilibria **194/197** (2002) 297–307

3.262 R. Q. Long, R. T. Yang: Carbon nanotubes as superior sorbent for dioxine removal, J. Am. Chem. Soc. **123** (2001) 2058–2059

3.263 Y. H. Li, S. Wang, A. Cao, D. Zhao, X. Zhang, C. Xu, Z. Luan, D. Ruan, J. Liang, D. Wu, B. Wei: Adsorption of fluoride from water by amorphous alumina supported on carbon nanotubes, Chem. Phys. Lett. **350** (2001) 412–416

3.264 Y. H. Li, S. Wang, J. Wei, X. Zhang, C. Xu, Z. Luan, D. Wu, B. Wei: Lead adsorption on carbon nanotubes, Chem. Phys. Lett. **357** (2002) 263–266

3.265 C. Park, E. S. Engel, A. Crowe, T. R. Gilbert, N. M. Rodriguez: Use of carbon nanofibers in the removal of organic solvents from water, Langmuir **16** (2000) 8050–8056

3.266 M. P. Mattson, R. C. Haddon, A. M. Rao: Molecular functionalization of carbon nanotubes and use as substrates for neuronal growth, J. Molec. Neurosci. **14** (2000) 175–182

3.267 J. J. Davis, M. L. H. Green, H. A. O. Hill, Y. C. Leung, P. J. Sadler, J. Sloan, A. V. Xavier, S. C. Tsang: The immobilization of proteins in carbon nanotubes, Inorg. Chim. Acta **272** (1998) 261–266

3.268 R. J. Chen, Y. Zhang, D. Wang, H. Dai: Noncovalent sidewall functionalization of single-walled carbon nanotubes for protein immobilization, J. Am. Chem. Soc. **123** (2001) 3838–3839

3.269 M. Shim, N. W. S. Kam, R. J. Chen, Y. Li, H. Dai: Functionalization of carbon nanotubes for biocompatibility and biomolecular recognition, Nanolett. **2** (2002) 285–288

3.270 C. Dwyer, M. Guthold, M. Falvo, S. Washburn, R. Superfine, D. Erie: DNA-functionalized single-walled carbon nanotubes, Nanotechnology **13** (2002) 601–604

3.271 H. Huang, S. Taylor, K. Fu, Y. Lin, D. Zhang, T. W. Hanks, A. M. Rao, Y. Sun: Attaching proteins to carbon nanotubes via diimide-activated amidation, Nanolett. **2** (2002) 311–314

3.272 C. V. Nguyen, L. Delzeit, A. M. Cassell, J. Li, J. Han, M. Meyyappan: Preparation of nucleic acid functionalized carbon nanotube arrays, Nanolett. **2** (2002) 1079–1081

3.273 B. R. Azamian, J. J. Davis, K. S. Coleman, C. B. Bagshaw, M. L. H. Green: Bioelectrochemical single-walled carbon nanotubes, J. Am. Chem. Soc. **124** (2002) 12664–12665

3.274 C. L. Xu, B. Q. Wei, R. Z. Ma, J. Liang, X. K. Ma, D. H. Wu: Fabrication of aluminum-carbon nanotube composites and their electrical properties, Carbon **37** (1999) 855–858

3.275 T. Kuzumaki, K. Miyazawa, H. Ichinose, K. Ito: Processing of carbon nanotube reinforced aluminum composite, J. Mater. Res. **13** (1998) 2445–2449

3.276 T. Kuzumaki, O. Ujiie, H. Ichinose, K. Ito: Mechanical characteristics and preparation of carbon nanotube fiber-reinforced Ti composite, Adv. Eng. Mater. **2** (2000) 416–418

3.277 S. R. Dong, J. P. Tu, X. B. Zhang: An investigation of the sliding wear behavior of Cu-matrix composite reinforced by carbon nanotubes, Mater. Sci. Eng. A **313** (2001) 83–87

3.278 Y. B. Li, Q. Ya, B. Q. Wei, J. Liang, D. H. Wu: Processing of a carbon nanotubes-Fe82P18 metallic glass composite, J. Mater. Sci. Lett. **17** (1998) 607–609

3.279 A. Peigney: Tougher ceramics with carbon nanotubes, Nature Mater. **2** (2003) 15–16

3.280 G. D. Zhan, J. D. Kuntz, J. Wan, A. K. Mukherjee: Single-wall carbon nanotubes as attractive toughening agents in alumina-based composites, Nature Mater. **2** (2003) 38–42

3.281 J. Sun, L. Gao, W. Li: Colloidal processing of carbon nanotube/alumina composites, Chem. Mater. **14** (2002) 5169–5172

3.282 V. G. Gavalas, R. Andrews, D. Bhattacharyya, L. G. Bachas: Carbon nanotube sol-gel composite materials, Nanolett. **1** (2001) 719–721

3.283 S. Rul, Ch. Laurent, A. Peigney, A. Rousset: Carbon nanotubes prepared in-situ in a cellular ceramic by the gelcasting-foam method, J. Eur. Ceram. Soc. **23** (2003) 1233–1241

3.284 R. Z. Ma, J. Wu, B. Q. Wei, J. Liang, D. H. Wu: Processing and properties of carbon nanotube/nano-SiC ceramic, J. Mater. Sci. **33** (1998) 5243–5246

3.285 C. Laurent, A. Peigney, O. Dumortier, A. Rousset: Carbon nanotubes-Fe-alumina nanocomposites. Part II: Microstructure and mechanical properties of the hot-pressed composites, J. Eur. Ceram. Soc. **18** (1998) 2005–2013

3.286 A. Peigney, C. Laurent, A. Rousset: Synthesis and characterization of alumina matrix nanocomposites containing carbon nanotubes, Key Eng. Mater. **132–136** (1997) 743–746

3.287 A. Peigney, C. Laurent, E. Flahaut, A. Rousset: Carbon nanotubes in novel ceramic matrix nanocomposites, Ceram. Intern. **26** (2000) 677–683

3.288 S. Rul: Synthèse de composites nanotubes de carbone-métal-oxyde. Ph.D. Thesis (Université Toulouse III, Toulouse 2002)

3.289 E. Flahaut, A. Peigney, C. Laurent, C. Marliere, F. Chastel, A. Rousset: Carbon nanotube-metal-oxide nanocomposites: Microstructure, electrical conductivity and mechanical properties, Acta Mater. **48** (2000) 3803–3812

3.290 R. R. Bacsa, C. Laurent, A. Peigney, W. S. Bacsa, T. Vaugien, A. Rousset: High specific surface area carbon nanotubes from catalytic chemical vapor deposition process, Chem. Phys. Lett. **323** (2000) 566–571

3.291 P. Coquay, A. Peigney, E. De Grave, R. E. Vandenberghe, C. Laurent: Carbon nanotubes by a CVD method. Part II: Formation of nanotubes from (Mg,Fe)O catalysts, J. Phys. Chem. B **106** (2002) 13199–13210

3.292 E. Flahaut, Ch. Laurent, A. Peigney: Double-walled carbon nanotubes in composite powders, J. Nanosci. Nanotech. **3** (2003) 151–158

3.293 A. Peigney, P. Coquay, E. Flahaut, R. E. Vandenberghe, E. De Grave, C. Laurent: A study of the formation of single- and double-walled carbon nanotubes by a CVD method, J Phys. Chem. B **105** (2001) 9699–9710

3.294 R. W. Siegel, S. K. Chang, B. J. Ash, J. Stone, P. M. Ajayan, R. W. Doremus, L. S. Schadler: Mechanical behavior of polymer and ceramic matrix nanocomposites, Scr. Mater. **44** (2001) 2061–2064

3.295 A. Peigney, E. Flahaut, C. Laurent, F. Chastel, A. Rousset: Aligned carbon nanotubes in ceramic-matrix nanocomposites prepared by high-temperature extrusion, Chem. Phys. Lett. **352** (2002) 20–25

3.296 S. L. Huang, M. R. Koblischka, K. Fossheim, T. W. Ebbesen, T. H. Johansen: Microstructure and flux distribution in both pure and carbon-nanotube-embedded $Bi_2Sr_2CaCu_2O_{8+\delta}$ superconductors, Physica C **311** (1999) 172–186

3.297 L. L. Yowell: Thermal management in ceramics: Synthesis and characterization of a zirconia-carbon nanotube composite, Proc Mater. Res. Soc. Symp. **633** (2002) A17.4.1–A17.4.6

3.298 A. Weidenkaff, S. G. Ebbinghaus, T. Lippert: $Ln_{1-x}A_xCoO_3$ (Ln = Er, La; A = Ca, Sr)/carbon nanotube composite materials applied for rechargeable Zn/Air batteries, Chem. Mater. **14** (2002) 1797–1805

3.299 D. S. Lim, J. W. An, H. J. Lee: Effect of carbon nanotube addition on the tribological behavior of carbon/carbon composites, Wear **252** (2002) 512–517

3.300 R. Andrews, D. Jacques, A. M. Rao, T. Rantell, F. Derbyshire, Y. Chen, J. Chen, R. C. Haddon: Nanotube composite carbon fibers, Appl. Phys. Lett. **75** (1999) 1329–1331

3.301 P. M. Ajayan, O. Stephan, C. Colliex, D. Trauth: Aligned carbon nanotube arrays formed by cutting a polymer resin-nanotube composite, Science **265** (1994) 1212–14

3.302 R. Haggenmueller, H. H. Gommans, A. G. Rinzler, J. E. Fischer, K. I. Winey: Aligned single-wall carbon nanotubes in composites by melt processing methods, Chem. Phys. Lett. **330** (2000) 219–225

3.303 L. S. Schadler, S. C. Giannaris, P. M. Ajayan: Load transfer in carbon nanotube epoxy composites, Appl. Phys. Lett. **73** (1998) 3842–3844

3.304 S. J. V. Frankland, A. Caglar, D. W. Brenner, M. Griebel: Molecular simulation of the influence of chemical cross-links on the shear strength of carbon nanotube-polymer interfaces, J. Phys. Chem. B **106** (2002) 3046–3048

3.305 H. D. Wagner: Nanotube-polymer adhesion: A mechanics approach, Chem. Phys. Lett. **361** (2002) 57–61

3.306 P. M. Ajayan, L. S. Schadler, C. Giannaris, A. Rubio: Single-walled carbon nanotube-polymer composites: Strength and weakness, Adv. Mater. **12** (2000) 750–753

3.307 X. Gong, J. Liu, S. Baskaran, R. D. Voise, J. S. Young: Surfactant-assisted processing of carbon nanotube/polymer composites, Chem. Mater. **12** (2000) 1049–1052

3.308 E. T. Thostenson, W. Z. Li, D. Z. Wang, Z. F. Ren, T. W. Chou: Carbon nanotube/carbon fiber hybrid multiscale composites, J. Appl. Phys. **91** (2002) 6034–6037

3.309 M. J. Biercuk, M. C. Llaguno, M. Radosavljevic, J. K. Hyun, A. T. Johnson, J. E. Fischer: Carbon nanotube composites for thermal management, Appl. Phys. Lett. **80** (2002) 2767–2769

3.310 S. Barrau, P. Demont, A. Peigney, C. Laurent, C. Lacabanne: DC and AC conductivity of carbon nanotube – Epoxy composites macromolecules, Macromol. **36** (2003) 5187–5194

3.311 J. Sandler, M. S. P. Shaffer, T. Prasse, W. Bauhofer, K. Schulte, A. H. Windle: Development of a dispersion process for carbon nanotubes in an epoxy matrix and the resulting electrical properties, Polymer **40** (1999) 5967–5971

3.312 Z. Jin, K. P. Pramoda, G. Xu, S. H. Goh: Dynamic mechanical behavior of melt-processed multi-walled carbon nanotube/poly(methyl methacrylate) composites, Chem. Phys. Lett. **337** (2001) 43–47

3.313 Z. Jin, K. P. Pramoda, S. H. Goh, G. Xu: Poly(vinylidene fluoride)-assisted melt-blending of multi-walled carbon nanotube/poly(methyl methacrylate) composites, Mat. Res. Bull. **37** (2002) 271–278

3.314 C. A. Cooper, D. Ravich, D. Lips, J. Mayer, H. D. Wagner: Distribution and alignment of carbon nanotubes and nanofibrils in a polymer matrix, Compos. Sci. Technol. **62** (2002) 1105–1112

3.315 J. M. Benoit, B. Corraze, S. Lefrant, W. J. Blau, P. Bernier, O. Chauvet: Transport properties of PMMA-carbon nanotubes composites, Synth. Met. **121** (2001) 1215–1216

3.316 J. M. Benoit, B. Corraze, O. Chauvet: Localization, Coulomb interactions, and electrical heating in single-wall carbon nanotubes/polymer composites, Phys. Rev. B: Cond. Matter. Mater. Phys. **65** (2002) 241405/1–241405/4

3.317 M. S. P. Shaffer, A. H. Windle: Fabrication and characterization of carbon nanotube/poly(vinyl alcohol) composites, Adv. Mater. **11** (1999) 937–941

3.318 L. Jin, C. Bower, O. Zhou: Alignment of carbon nanotubes in a polymer matrix by mechanical stretching, Appl. Phys. Lett. **73** (1998) 1197–1199

3.319 H. D. Wagner, O. Lourie, Y. Feldman, R. Tenne: Stress-induced fragmentation of multiwall carbon nanotubes in a polymer matrix, Appl. Phys. Lett. **72** (1998) 188–190

3.320 H. D. Wagner, O. Lourie, X. F. Zhou: Macrofragmentation and microfragmentation phenomena in composite materials, Composites Part A **30A** (1998) 59–66

3.321 J. R. Wood, Q. Zhao, H. D. Wagner: Orientation of carbon nanotubes in polymers and its detection by Raman spectroscopy, Composites Part A **32A** (2001) 391–399

3.322 Q. Zhao, J. R. Wood, H. D. Wagner: Using carbon nanotubes to detect polymer transitions, J. Polym. Sci., Part B: Polym. Phys. **39** (2001) 1492–1495

3.323 M. Cochet, W. K. Maser, A. M. Benito, M. A. Callejas, M. T. Martinesz, J. M. Benoit, J. Schreiber, O. Chauvet: Synthesis of a new polyaniline/nanotube composite: In-situ polymerisation and charge transfer through site-selective interaction, Chem. Commun. **16** (2001) 1450–1451

3.324 D. Qian, E. C. Dickey, R. Andrews, T. Rantell: Load transfer and deformation mechanisms in carbon nanotube-polystyrene composites, Appl. Phys. Lett. **76** (2000) 2868–2870

3.325 C. Wei, D. Srivastava, K. Cho: Thermal expansion and diffusion coefficients of carbon nanotube-polymer composites, Los Alamos Nat. Lab., Preprint Archive, Condensed Matter (archiv:cond-mat/0203349) (2002) 1–11

3.326 C. Pirlot, I. Willems, A. Fonseca, J. B. Nagy, J. Delhalle: Preparation and characterization of carbon nanotube/polyacrylonitrile composites, Adv. Eng. Mater. **4** (2002) 109–114

3.327 L. Cao, H. Chen, M. Wang, J. Sun, X. Zhang, F. Kong: Photoconductivity study of modified carbon nanotube/oxotitanium phthalocyanine composites, J. Phys. Chem. B **106** (2002) 8971–8975

3.328 I. Musa, M. Baxendale, G. A. J. Amaratunga, W. Eccleston: Properties of regular poly(3-octylthiophene)/multi-wall carbon nanotube composites, Synth. Met. **102** (1999) 1250

3.329 E. Kymakis, I. Alexandou, G. A. J. Amaratunga: Single-walled carbon nanotube-polymer composites: Electrical, optical and structural investigation, Synth. Met. **127** (2002) 59–62

3.330 K. Yoshino, H. Kajii, H. Araki, T. Sonoda, H. Take, S. Lee: Electrical and optical properties of conducting polymer-fullerene and conducting polymer-carbon nanotube composites, Fuller. Sci. Technol. **7** (1999) 695–711

3.331 S. A. Curran, P. M. Ajayan, W. J. Blau, D. L. Carroll, J. N. Coleman, A. B. Dalton, A. P. Davey, A. Drury, B. McCarthy, S. Maier, A. Strevens: A composite from poly(m-phenylenevinylene-co-2,5-dioctoxy-p-phenylenevinylene) and carbon nanotubes. A novel material for molecular optoelectronics, Adv. Mater. **10** (1998) 1091–1093

3.332 P. Fournet, D.F. O'Brien, J. N. Coleman, H. H. Horhold, W.J. Blau: A carbon nanotube composite as an electron transport layer for M3EH-PPV based light-emitting diodes, Synth. Met. **121** (2001) 1683–1684

3.333 H. S. Woo, R. Czerw, S. Webster, D. L. Carroll, J. Ballato, A. E. Strevens, D. O'Brien, W.J. Blau: Hole blocking in carbon nanotube-polymer composite organic light-emitting diodes based on poly (m-phenylene vinylene-co-2, 5-dioctoxy-p-phenylene vinylene), Appl. Phys. Lett. **77** (2000) 1393–1395

3.334 H. S. Woo, R. Czerw, S. Webster, D. L. Carroll, J. W. Park, J. H. Lee: Organic light emitting diodes fabricated with single wall carbon nanotubes dispersed in a hole conducting buffer: The role of carbon nanotubes in a hole conducting polymer, Synth. Met. **116** (2001) 369–372

3.335 H. Ago, K. Petritsch, M. S. P. Shaffer, A. H. Windle, R. H. Friend: Composites of carbon nanotubes and conjugated polymers for photovoltaic devices, Adv. Mater. **11** (1999) 1281–1285

3.336 B. Vigolo, A. Pénicaud, C. Coulon, C. Sauder, R. Pailler, C. Journet, P. Bernier, P. Poulin: Macroscopic fibers and ribbons of oriented carbon nanotubes, Science **290** (2000) 1331–1334

3.337 B. Vigolo, P. Poulin, M. Lucas, P. Launois, P. Bernier: Improved structure and properties of single-wall carbon nanotube spun fibers, Appl. Phys. Lett. **11** (2002) 1210–1212

3.338 P. Poulin, B. Vigolo, P. Launois: Films and fibers of oriented single wall nanotubes, Carbon **40** (2002) 1741–1749

3.339 K. Jiang, Q. Li, S. Fan: Spinning continuous carbon nanotube yarn, Nature **419** (2002) 801

3.340 P. Lambin, A. Fonseca, J. P. Vigneron, J. B'Nagy, A. A. Lucas: Structural and electronic properties of bent carbon nanotubes, Chem. Phys. Lett. **245** (1995) 85–89

3.341 L. Chico, V. H. Crespi, L. X. Benedict, S. G. Louie, M. L. Cohen: Pure carbon nanoscale devices: Nanotube heterojunctions, Phys. Rev. Lett. **76** (1996) 971–974

3.342 Z. Yao, H. W. C. Postma, L. Balents, C. Dekker: Carbon nanotube intramolecular junctions, Nature **402** (1999) 273–276

3.343 S. J. Tans, A. R. M. Verschueren, C. Dekker: Room temperature transistor based on single carbon nanotube, Nature **393** (1998) 49–52
3.344 R. Martel, T. Schmidt, H. R. Shea, T. Hertel, P. Avouris: Single and multi-wall carbon nanotube field effect transistors, Appl. Phys. Lett. **73** (1998) 2447–2449
3.345 V. Derycke, R. Martel, J. Appenzeller, P. Avouris: Carbon nanotube inter- and intramolecular logic gates, Nanolett. **1** (2001) 453–456
3.346 P. Kim, C. M. Lieber: Nanotube nanotweezers, Science **286** (1999) 2148–2150
3.347 P. G. Collins, M. S. Arnold, P. Avouris: Engineering carbon nanotubes using electrical breakdown, Science **292** (2001) 706–709
3.348 R. H. Baughman, C. Changxing, A. A. Zakhidov, Z. Iqbal, J. N. Barisci, G. M. Spinks, G. G. Wallace, A. Mazzoldi, D. de Rossi, A. G. Rinzler, O. Jaschinki S. Roth, M. Kertesz: Carbon nanotubes actuators, Science **284** (1999) 1340–1344
3.349 Y. Gao, Y. Bando: Carbon nanothermometer containing gallium, Nature **415** (2002) 599
3.350 C. Niu, E. K. Sichel, R. Hoch, D. Moy, H. Tennent: High power electro-chemical capacitors based on carbon nanotube electrodes, Appl. Phys. Lett. **70** (1997) 1480–1482
3.351 E. Frackowiak, F. Béguin: Electrochemical storage of energy in carbon nanotubes and nanostructured carbons, Carbon **40** (2002) 1775–1787
3.352 E. Frackowiak, K. Jurewicz, K. Szostak, S. Delpeux, F. Béguin: Nanotubular materials as electrodes for supercapacitors, Fuel Process. Technol. **77** (2002) 213–219

4. Nanowires

Nanowires are especially attractive for nanoscience studies as well as for nanotechnology applications. Nanowires, compared to other low dimensional systems, have two quantum confined directions while still leaving one unconfined direction for electrical conduction. This allows them to be used in applications which require electrical conduction, rather than tunneling transport. Because of their unique density of electronic states, nanowires in the limit of small diameters are expected to exhibit significantly different optical, electrical, and magnetic properties from their bulk 3-D crystalline counterparts. Increased surface area, very high density of electronic states and joint density of states near the energies of their van Hove singularities, enhanced exciton binding energy, diameter-dependent bandgap, and increased surface scattering for electrons and phonons are just some of the ways in which nanowires differ from their corresponding bulk materials. Yet the sizes of nanowires are typically large enough (>1 nm in the quantum confined direction) to have local crystal structures closely related to their parent materials, thereby allowing theoretical predictions about their properties to be made on the basis of an extensive literature relevant to their bulk properties.

Not only do nanowires exhibit many properties that are similar to, and others that are distinctly different from those of their bulk counterparts, nanowires have the advantage from an applications standpoint in that some of the materials parameters critical for certain properties can be independently controlled in nanowires but not in their bulk counterparts. Certain properties can also be enhanced nonlinearly in small diameter nanowires by exploiting the singular aspects of the 1-D electronic density of states. Furthermore, nanowires have been shown to provide a promising framework for applying the "bottom-up" approach [4.1] for the design of nanostructures for nanoscience investigations and for potential nanotechnology applications. Driven by: (1) these new research and development opportunities, (2) the smaller and smaller length scales now being used in the semiconductor, opto-electronics, and magnetics industries, and (3) the dramatic development of the biotechnology industry where the action is also at the nanoscale, the nanowire research field has developed with exceptional speed in the last few years. A review of the current status of nanowire research is therefore of significant broad interest at the present time. This review aims to focus on nanowire properties that differ from those of their parent crystalline bulk materials, with an eye toward possible applications that might emerge from the unique properties of nanowires and from future discoveries in this field.

4.1 **Synthesis** 100
  4.1.1 Template-Assisted Synthesis 100
  4.1.2 VLS Method for Nanowire Synthesis 105
  4.1.3 Other Synthesis Methods 107
  4.1.4 Hierarchical Arrangement and Superstructures of Nanowires 108

4.2 **Characterization and Physical Properties of Nanowires** 110
  4.2.1 Structural Characterization 110
  4.2.2 Transport Properties 115
  4.2.3 Optical Properties 126

4.3 **Applications** 131
  4.3.1 Electrical Applications 131
  4.3.2 Thermoelectric Applications 133
  4.3.3 Optical Applications 134
  4.3.4 Chemical and Biochemical Sensing Devices 137
  4.3.5 Magnetic Applications 137

4.4 **Concluding Remarks** 138

References 138

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

For quick reference, examples of typical nanowires that have been synthesized and studied are listed in Table 4.1. Also of use to the reader are review articles that focus on a comparison between nanowire and nanotube properties [4.2] and the many reviews that have been written about carbon nanotubes [4.3–5], which can be considered as a model one-dimensional system.

4.1 Synthesis

In this section we survey the most common synthetic approaches that have successfully afforded high quality nanowires of a large variety of materials (see Table 4.1). In Sect. 4.1.1, we discuss methods that make use of various templates with nanochannels to confine the nanowire growth to two dimensions. In Sect. 4.1.2, we present the synthesis of nanowires by the vapor-liquid-solid mechanism and its many variations. In Sect. 4.1.3, we present examples of other synthetic methods of general applicability. The last part of this section (Sect. 4.1.4) features several approaches that have been developed to organize nanowires into simple architectures.

4.1.1 Template-Assisted Synthesis

The template-assisted synthesis of nanowires is a conceptually simple and intuitive way to fabricate nanostructures [4.7–10]. These templates contain very small cylindrical pores or voids within the host material, and the empty spaces are filled with the chosen material, which adopts the pore morphology, to form nanowires. In this section, we describe the templates first and then describe strategies for filling them to make nanowires.

Template Synthesis

In template-assisted synthesis of nanostructures, the chemical stability and mechanical properties of the template, as well as the diameter, uniformity, and density of the pores are important characteristics to consider. Templates frequently used for nanowire synthesis include anodic alumina (Al_2O_3), nano-channel glass, ion track-etched polymers, and mica films.

Porous anodic alumina templates are produced by anodizing pure Al films in various acids [4.11–13]. Under carefully chosen anodization conditions, the resulting oxide film possesses a regular hexagonal array of parallel and nearly cylindrical channels, as shown in Fig. 4.1a. The self-organization of the pore structure in an anodic alumina template involves two coupled processes: pore formation with uniform diameters and pore ordering. The pores form with uniform diameters because of a delicate balance between electric-field-enhanced diffusion, which determines the growth rate of the alumina, and dissolution of the alumina into the acidic electrolyte [4.12]. The pores are believed to self-order because of mechanical stress at the aluminum-alumina interface due to volume expansion during the anodization. This stress produces a repulsive force between the pores, causing them to arrange in a hexagonal lattice [4.14]. Depending on the anodization conditions, the pore diameter can be systematically varied from < 10 nm up to 200 nm with a pore density in the range of $10^9 – 10^{11}$ pores/cm^2 [4.11, 12, 15, 16]. Many groups have shown that the pore size distribution and the pore ordering of the anodic alumina templates can be significantly improved by a two-step anodization technique [4.6, 17, 18] in which the aluminum oxide layer is dissolved after the first anodization in an acidic solution followed by a second anodization under the same conditions.



Fig. 4.1 **(a)** SEM images of the top surfaces of porous anodic alumina templates anodized with an average pore diameter of 44 nm [4.6]. **(b)** SEM image of the particle track-etched polycarbonate membrane, with a pore diameter of 1 µm [4.7]

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Table 4.1 Selected syntheses of nanowires by material

Material	Growth Technique	Reference
Ag	DNA-template, redox	[4.23]
	template, pulsed ECD^a	[4.24]
Au	template, ECD^a	[4.25, 26]
Bi	stress-induced	[4.27]
	template, vapor-phase	[4.28]
	template, ECD^a	[4.29], [4.30], [4.31]
	template, pressure-injection	[4.32], [4.16, 33]
Bi_2Te_3	template, dc ECD^a	[4.34]
CdS	liquid-phase (surfactant), recrystallization	[4.35]
	template, ac ECD^a	[4.36], [4.37]
CdSe	liquid-phase (surfactant), redox	[4.38]
	template, ac ECD^a	[4.39], [4.40]
Cu	vapor deposition	[4.41]
	template, ECD^a	[4.42]
Fe	template, ECD^c	[4.15], [4.43]
	shadow deposition	[4.44]
GaN	template, CVD^c	[4.45]
	VLS^b	[4.46, 47]
GaAs	template, liquid/vapor OMCVD^d	[4.48]
Ge	high-T, high-P liquid-phase, redox	[4.49]
	VLS^b	[4.50]
	oxide-assisted	[4.51]
InAs	template, liquid/vapor OMCVD^d	[4.48]
InP	VLS^b	[4.52]
Mo	step decoration, ECD^a+ redox	[4.53]
Ni	template, ECD^a	[4.22], [4.31, 54]
PbSe	liquid phase	[4.55]
Pd	step decoration, ECD^a	[4.56]
Se	liquid-phase, recrystallization	[4.57]
	template, pressure injection	[4.58]
Si	VLS^b	[4.59]
	laser-ablation VLS^b	[4.60]
	oxide-assisted	[4.61]
	low-T VLS^b	[4.62]
Zn	template, vapor-phase	[4.63]
	template, ECD^a	[4.64]
ZnO	VLS^b	[4.65]
	template, ECD^a	[4.64, 66]

[a] Electrochemical deposition

[b] Vapor-liquid-solid growth

[c] Chemical vapor deposition

[d] Organometallic chemical vapor deposition

Springer Handbook of Nanotechnology
B. Bhushan • © Springer 2004

Another type of porous template commonly used for nanowire synthesis is the template type fabricated by chemically etching particle tracks originating from ion bombardment [4.19], such as track-etched polycarbonate membranes (Fig. 4.1b) [4.7,20,21] and also mica films [4.22].

Other porous materials can be used as host templates for nanowire growth, as discussed by *Ozin* [4.8]. Nanochannel glass (NCG), for example, contains a regular hexagonal array of capillaries similar to the pore structure in anodic alumina with a packing density as high as 3×10^{10} pores/cm^2 [4.9]. Porous Vycor glass that contains an interconnected network of pores less than 10 nm was also employed for the early study of nanostructures [4.68]. Mesoporous molecular sieves [4.69], termed MCM-41, possess hexagonally packed pores with very small channel diameters that can be varied between 2 nm and 10 nm. Conducting organic filaments have been fabricated in the nanochannels of MCM-41 [4.70]. Recently the DNA molecule has also been used as a template for growing nanometer-sized wires [4.23].

Diblock copolymers, polymers that consist of two chain segments with different properties, have also been utilized as templates for nanowire growth. When the two segments are immiscible in each other, phase segregation occurs, and depending on their volume ratio, spheres, cylinders, and lamellae may self-assemble. To form self-assembled arrays of nanopores, copolymers composed of polystyrene and polymethylmethacrylate [P(S-b-MMA)] [4.71] were used. By applying an electric field while the copolymer was heated above the glass transition temperature of the two constituent polymers, the self-assembled cylinders of PMMA could be aligned with their main axis perpendicular to the film. Selective removal of the PMMA component afforded the preparation of 14-nm-diameter ordered pore arrays with a packing density of 1.9×10^{11} cm^{-3}.

Nanowire Template Assisted Growth by Pressure Injection

The pressure injection technique is often employed when fabricating highly crystalline nanowires from a low-melting point material and when using porous templates with robust mechanical strength. In the high-pressure injection method, the nanowires are formed by pressure injecting the desired material in liquid form into the evacuated pores of the template. Due to the heating and the pressurization processes, the templates used for the pressure injection method must be chemically stable and be able to maintain their structural integrity at high temperatures and high pressures. Anodic aluminum oxide films and nano-channel glass are two typical materials used as templates in conjunction with the pressure injection filling technique. Metal nanowires (Bi, In, Sn, and Al) and semiconductor nanowires (Se, Te, GaSb, and Bi_2Te_3) have been fabricated in anodic aluminum oxide templates using this method [4.32,58,67].

The pressure P required to overcome the surface tension for the liquid material to fill the pores with a diameter d_W is determined by the Washburn equation [4.72]:

$$d_W = -4\gamma\cos\theta/P\,, \tag{4.1}$$

where γ is the surface tension of the liquid, and θ is the contact angle between the liquid and the template. To reduce the required pressure and to maximize the filling factor, some surfactants are used to decrease the surface tension and the contact angle. For example, the introduction of Cu in the Bi melt can facilitate filling the



Fig. 4.2a–c XRD patterns of bismuth/anodic alumina nano-composites with average bismuth wire diameters of **(a)** 40 nm, **(b)** 52 nm, and **(c)** 95 nm [4.67]. The Miller indices corresponding to the lattice planes of bulk Bi are indicated above the individual peaks. The majority of the Bi nanowires are oriented along the $[10\bar{1}1]$ and $[01\bar{1}2]$ directions for $d_W \geq 60$ nm and $d_W \leq 50$ nm, respectively [4.16,67]. The existence of more than one dominant orientation in the 52-nm Bi nanowires is attributed to the transitional behavior of *intermediate*-diameter nanowires as the preferential growth orientation is shifted from $[10\bar{1}1]$ to $[01\bar{1}2]$ with decreasing d_W

pores in the anodic alumina template with liquid Bi and can increase the number of nanowires prepared [4.16]. But some of the surfactants might cause contamination problems and therefore should be avoided. Nanowires produced by the pressure injection technique usually possess high crystallinity and a preferred crystal orientation along the wire axis. For example, Fig. 4.2 shows the X-ray diffraction (XRD) patterns of Bi nanowire arrays of three different wire diameters with an injection pressure of $\sim 5{,}000$ psi [4.67], demonstrating that the major ($> 80\%$) crystal orientation of the wire axes in the 95-nm and 40-nm diameter Bi nanowire arrays are, respectively, normal to the (202) and (012) lattice planes. These are denoted by $[10\bar{1}1]$ and $[01\bar{1}2]$ when using a hexagonal unit cell, suggesting a wire-diameter-dependent crystal growth direction. On the other hand, 30 nm Bi nanowires produced using a much higher pressure of $> 20{,}000$ psi show a different crystal orientation of (001) along the wire axis [4.33], indicating that the preferred crystal orientation may also depend on the applied pressure, with the most dense packing direction along the wire axis for the highest applied pressure.

Electrochemical Deposition

The electrochemical deposition technique has attracted increasing attention as an alternative method for fabricating nanowires. Traditionally, electrochemistry has been used to grow thin films on conducting surfaces. Since electrochemical growth is usually controllable in the direction normal to the substrate surface, this method can be readily extended to fabricate 1-D or 0-D nanostructures, if the deposition is confined within the pores of an appropriate template. In the electrochemical methods, a thin conducting metal film is first coated on one side of the porous membrane to serve as the cathode for electroplating. The length of the deposited nanowires can be controlled by varying the duration of the electroplating process. This method has been used to synthesize a wide variety of nanowires e.g., metals (Bi [4.21, 29]; Co [4.73, 74]; Fe [4.15,75]; Cu [4.20,76]; Ni [4.22,73]; Ag [4.24,77]; Au [4.25,26]); conducting polymers [4.7,29]; superconductors (Pb [4.78]); semiconductors (CdS [4.37]); and even superlattice nanowires with A/B constituents (such as Cu/Co [4.20,76]) have been synthesized electrochemically (see Table 4.1).

In the electrochemical deposition process, the chosen template has to be chemically stable in the electrolyte during the electrolysis process. Cracks and defects in the templates are detrimental to the nanowire growth, since the deposition processes primarily occur in the more accessible cracks, leaving most of the nanopores unfilled. Particle track-etched mica films or polymer membranes are typical templates used in the simple dc electrolysis. To use anodic aluminum oxide films in the dc electrochemical deposition, the insulating barrier layer that separates the pores from the bottom aluminum substrate has to be removed, and a metal film is then evaporated onto the back of the template membrane [4.79]. Compound nanowire arrays, such as Bi_2Te_3, have been fabricated in alumina templates with a high filling factor using the dc electrochemical deposition [4.34]. Figures 4.3a and b, respectively, show the top view and cross-sectional SEM images of a Bi_2Te_3 nanowire array [4.34]. The light areas are associated with Bi_2Te_3 nanowires, the dark regions denote empty pores, and the surrounding gray matrix is alumina.

Surfactants are also used with electrochemical deposition when necessary. For example, when using templates derived from PMMA/PS diblock copolymers (see above), methanol is used as a surfactant is used to facilitate pore filling [4.71], thereby achieving $\sim 100\%$ filling factor.

It is also possible to employ an ac electrodeposition method in anodic alumina templates without the removal of the barrier layer, by utilizing the rectifying



Fig. 4.3 **(a)** SEM image of a Bi_2Te_3 nanowire array in cross section showing a relatively high pore filling factor. **(b)** SEM image of a Bi_2Te_3 nanowire array composite along the wire axis [4.34]

properties of the oxide barrier. In ac electrochemical deposition, although the applied voltage is sinusoidal and symmetric, the current is greater during the cathodic half-cycles, making deposition dominant over the stripping, which occurs in the subsequent anodic half-cycles. Since no rectification occurs at defect sites, the deposition and stripping rates are equal, and no material is deposited. Hence, the difficulties associated with cracks are avoided. In this fashion, metals, such as Co [4.74] and Fe [4.15, 75], and semiconductors, such as CdS [4.37], have been deposited into the pores of anodic aluminum oxide templates without removing the barrier layer.

In contrast to nanowires synthesized by the pressure injection method, nanowires fabricated by the electrochemical process are usually polycrystalline, with no preferred crystal orientations, as observed by XRD studies. Some exceptions exist, however. For example, polycrystalline CdS nanowires, fabricated by an ac electrodeposition method in anodic alumina templates [4.37], possibly have a preferred wire growth orientation along the *c*-axis. In addition, *Xu* et al. have prepared a number of single-crystal II-VI semiconductor nanowires, including CdS, CdSe, and CdTe, by dc electrochemical deposition in anodic alumina templates with a nonaqueous electrolyte [4.36, 40]. Furthermore, single-crystal Pb nanowires can be formed by pulse electrodeposition under over-potential conditions, but no specific crystal orientation along the wire axis was observed [4.78]. The use of pulse currents is believed to be advantageous for the growth of crystalline wires because the metal ions in the solution can be regenerated between the electrical pulses and, therefore, uniform deposition conditions can be produced for each deposition pulse. Similarly, single crystal Ag nanowires were fabricated by pulsed electro-deposition [4.24].



Fig. 4.4 **(a)** TEM image of a single Co(10 nm)/Cu(10 nm) multilayered nanowire. **(b)** A selected region of the sample at high magnification [4.76]

One advantage of the electrochemical deposition technique is the possibility of fabricating multilayered structures within nanowires. By varying the cathodic potentials in the electrolyte that contains two different kinds of ions, different metal layers can be controllably deposited. In this fashion, Co/Cu multilayered nanowires have been synthesized [4.20, 76]. Figure 4.4 shows TEM images of a single Co/Cu nanowire of about 40 nm in diameter [4.76]. The light bands represent Co-rich regions, and the dark bands represent Cu-rich layers. This electrodeposition method provides a low-cost approach to preparing multilayered 1-D nanostructures.

Vapor Deposition

Vapor deposition of nanowires includes physical vapor deposition (PVD) [4.28], chemical vapor deposition (CVD) [4.80], and metallorganic chemical vapor deposition (MOCVD) [4.48]. Like electrochemical deposition, vapor deposition is usually capable of preparing smaller-diameter (≤ 20 nm) nanowires than pressure injection methods, since it does not rely on the high pressure and surface tension involved to insert the material into the pores.

In the physical vapor deposition technique, the material to be filled is first heated to produce a vapor, which is then introduced through the pores of the template and cooled to solidify. Using an especially designed experimental setup [4.28], nearly single-crystal Bi nanowires in anodic aluminum templates with pore diameters as small as 7 nm have been synthesized, and these Bi nanowires were found to possess a preferred crystal growth orientation along the wire axis, similar to the Bi nanowires prepared by pressure injection [4.16, 28].

Compound materials that result from two reacting gases have also been prepared by the chemical vapor deposition (CVD) technique. For example, single-crystal GaN nanowires have been synthesized in anodic alumina templates through a gas reaction of Ga_2O vapor with a flowing ammonia atmosphere [4.45, 80]. A different liquid/gas phase approach has been used to prepare polycrystalline GaAs and InAs nanowires in a nanochannel glass array [4.48]. In this method, the nanochannels are filled with one liquid precursor (e.g., Me_3Ga or Et_3In) via a capillary effect, and the nanowires are formed within the template by reactions between the liquid precursor and the other gas reactant (e.g., AsH_3).

Nanotube Synthesis with Templates and as Templates

Recently carbon nanotubes, an important class of 1-D nanostructures, have been fabricated within the pores of anodic alumina templates using a chemical vapor deposition technique [4.81–84] to form highly ordered two-dimensional carbon nanotube arrays. A small amount of metal catalyst (e.g., Co) is first electrochemically deposited on the bottom of the pores. The templates are then placed in a furnace and heated to $\sim 700-800\,°\mathrm{C}$ with a flowing gas consisting of a mixture of N_2 and acetylene (C_2H_2) or ethylene (C_2H_4). The hydrocarbon molecules are pyrolyzed to form carbon nanotubes in the pores of the template with the help of the metal catalysts. Well-aligned nanotube arrays have stimulated much interest because of their great potential in various applications, such as cold-cathode flat panel displays. Of particular interest is the use of zeolite templates with very narrow pores (< 1 nm diameter) that permit the growth of carbon nanotubes with diameters of 0.42 nm, having only 10 carbon atoms around the circumference [4.85].

The hollow cores of carbon nanotubes have also been used to synthesize a variety of nanowires of very small diameter [4.86]. These very small diameter nanowires have been extensively studied by high resolution TEM but have not yet been characterized to the same degree regarding their physical properties.

4.1.2 VLS Method for Nanowire Synthesis

Some of the recent successful syntheses of semiconductor nanowires are based on the so-called vapor-liquid-solid (VLS) mechanism of anisotropic crystal growth. This mechanism was first proposed for the growth of single crystal silicon whiskers 100 nm to hundreds of microns in diameter [4.87]. The proposed growth mechanism (see Fig. 4.5) involves the absorption of source material from the gas phase into a liquid droplet of catalyst (a molten particle of gold on a silicon substrate in the original work [4.87]). Upon supersaturation of the liquid alloy, a nucleation event generates a solid precipitate of the source material. This seed serves as a preferred site for further deposition of material at the interface of the liquid droplet, promoting the elongation of the seed into a nanowire or a whisker, and suppressing further nucleation events on the same catalyst. Since the liquid droplet catalyzes the incorporation of material from the gas source to the growing crystal, the deposit grows anisotropically as a whisker whose diameter is dictated by the diameter of the liquid alloy droplet. The nanowires thus obtained are of high purity, except for the end containing the solidified catalyst as an alloy particle (see Figs. 4.5, 4.6a). Real-time observations of the alloying, nucleation, and elongation steps in the growth of germanium nanowires from gold nanoclusters by the VLS method were recorded by in situ TEM [4.88].



Fig. 4.5 Schematic diagram illustrating the growth of silicon nanowires by the VLS mechanism

Reduction of the average wire diameter to the nanometer scale requires the generation of nanosized catalyst droplets. Due to the balance between the liquid-vapor surface free energy and the free energy of condensation, however, the size of a liquid droplet, in equilibrium with its vapor, is usually limited to the micrometer range. This obstacle was overcome in recent years by several new methodologies: 1) Advances in the synthesis of metal nanoclusters have made monodispersed nanoparticles commercially available. These can be dispersed on a solid substrate in high dilution so that when the temperature is raised above the melting point, the liquid clusters do not aggregate [4.59]. 2) Alternatively, metal islands of nanoscale sizes can self-form when a strained thin layer is grown or heat treated on a non-epitaxial substrate [4.50]. 3) Laser-assisted catalytic VLS growth is a method used to generate nanowires under nonequilibrium conditions. By laser ablation of a target containing both the catalyst and the source materials, a plasma is generated from which catalyst nanoclusters nucleate as the plasma cools down. Single crystal nanowires grow as long as the particle remains liquid [4.60]. 4) Interestingly, by optimization of the material properties of the catalyst-nanowire system, conditions can be achieved for which nanocrystals nucleate in a liquid catalyst pool supersaturated with the nanowire material, migrate to the surface due to a large surface tension, and continue growing as nanowires perpendicular to the liquid surface [4.62]. In this case, supersaturated nanodroplets are sustained on the outer



Fig. 4.6 **(a)** TEM images of Si nanowires produced after laser ablating a $Si_{0.9}Fe_{0.1}$ target. The dark spheres with a slightly larger diameter than the wires are solidified catalyst clusters [4.60]. **(b)** Diffraction contrast TEM image of a Si nanowire. The crystalline Si core appears darker than the amorphous oxide surface layer. The inset shows the convergent beam electron diffraction pattern recorded perpendicular to the wire axis, confirming the nanowire crystallinity [4.60]. **(c)** STEM image of $Si/Si_{1-x}Ge_x$ superlattice nanowires in the bright field mode. The scale bar is 500 nm [4.90]

end of the nanowire due to the low solubility of the nanowire material in the liquid [4.89].

A wide variety of elemental, binary, and compound semiconductor nanowires has been synthesized by the VLS method, and relatively good control over the nanowire diameter and diameter distribution has been achieved. Researchers are currently focusing attention on the controlled variation of the materials properties along the nanowire axis. To this context, researchers have modified the VLS synthesis apparatus to generate compositionally modulated nanowires. GaAs/GaP modulated nanowires have been synthesized by alternately ablating targets of the corresponding materials in the presence of gold nanoparticles [4.92]. p-Si/n-Si nanowires were grown by chemical vapor deposition from alternating gaseous mixtures containing the appropriate dopant [4.92]. $Si/Si_{1-x}Ge_x$ nanowires were grown by combining silicon from a gaseous source with germanium from a periodically ablated target (see Fig. 4.6c) [4.90]. Finally, using an ultra-high vacuum chamber and molecular beams, InAs/InP nanowires with atomically sharp interfaces were obtained [4.93]. These compositionally modulated nanowires are expected to exhibit exciting electronic, photonic, and thermoelectric properties.

Silicon and germanium nanowires grown by the VLS method consist of a crystalline core coated by a relatively thick amorphous oxide layer (2–3 nm) (see Fig. 4.6b). These layers are too thick to be the result of ambient oxidation, and it has been shown that these oxides play an important role in the nanowire growth process [4.61, 91]. Silicon oxides were found to serve as a special and highly selective catalyst, that significantly enhances the yield of Si nanowires, without the need for metal catalyst particles [4.61, 91, 94]. A similar yield enhancement was also found in the synthesis of Ge nanowires from the laser ablation of Ge powder mixed with GeO_2 [4.51]. The Si and Ge nanowires produced from these metal-free targets generally grow along the [112] crystal direction [4.95] and have the benefit that no catalyst clusters are found on either ends of the nanowires. Based on these observations



Fig. 4.7 TEM image showing the two major morphologies of Si nanowires prepared by the oxide assisted growth method [4.91]. Notice the absence of metal particles when compared to Fig. 4.6a. The *arrow* points at an oxide-linked chain of Si nanoparticles

and other TEM studies, an oxide-enhanced nanowire growth mechanism different from the classical VLS mechanism was proposed, in which no metal catalyst is required during the laser ablation-assisted synthesis [4.91]. It is postulated that the nanowire growth is dependent on the presence of SiO (or GeO) vapor. This decomposes in the nanowire tip region into Si (or Ge), which is incorporated into the crystalline phase, and SiO_2 (or GeO_2), which contributes to the outer coating. The initial nucleation events generate oxide-coated spherical nanocrystals. The [112] crystal faces have the fastest growth rate, and therefore the nanocrystals soon begin elongating along this direction to form one-dimensional structures. The Si_mO or Ge_mO ($m > 1$) layer on the nanowire tips may be at temperatures near their molten states, catalyzing the incorporation of gas molecules in a directional fashion [4.95]. Besides nanowires with smooth walls, a second morphology of chains of non-oriented nanocrystals linked by oxide necks is frequently observed (indicated by an arrow in Fig. 4.7). In addition, it was found by STM studies that about 1% of the wires consist of a regular array of two alternating segments, 10 nm and 5 nm in length, respectively [4.96]. The segments, whose junctions form an angle of 30°, are probably a result of alternating growth along different crystallographic orientations (see Sect. 4.2.1).

4.1.3 Other Synthesis Methods

In this section we review several other general procedures available for the synthesis of a variety of nanowires. We focus on “bottom-up” approaches, which afford many kinds of nanowires in large numbers and do not require highly sophisticated equipment (such as scanning microscopy or lithography based methods). We exclude cases for which the nanowires are not self sustained (such as in the case of atomic rows on the surface of crystals).

Gates et al. have demonstrated a solution-phase synthesis of nanowires with controllable diameters [4.57, 97], without the use of templates, catalysts, or surfactants. They make use of the anisotropy of the crystal structure of trigonal selenium and tellurium, which can be viewed as rows of 1-D helical atomic chains. They base their approach on the mass transfer of atoms during an aging step from a high free-energy solid phase (e.g., amorphous selenium) to a seed (e.g., trigonal selenium nanocrystal) that grows preferentially along one crystallographic axis. The lateral dimension of the seed, which dictates the diameter of the nanowire, can be controlled by the temperature of the nucleation step. Furthermore, Se/Te alloy nanowires were synthesized by this method, and Ag_2Se compound nanowires were obtained by treating selenium nanowires with $AgNO_3$ [4.98–100].

More often, however, the use of surfactants is necessary to promote the anisotropic 1-D growth of nanocrystals. Solution phase synthetic routes have been optimized to produce monodispersed quantum dots, i. e., zero-dimensional isotropic nanocrystals [4.101]. Surfactants are necessary in this case to stabilize the interfaces of the nanoparticles and retard oxidation and aggregation processes. Detailed studies on the effect of growth conditions revealed that they can be manipulated to induce a directional growth of the nanocrystals, usually generating nanorods (aspect ratio of ≈ 10), and in favorable cases, nanowires of high-aspect ratios. *Heath* and *LeGoues* [4.49] synthesized germanium nanowires by reducing a mixture of $GeCl_4$ and phenyl-$GeCl_3$ at high temperature and high pressure. The phenyl ligand was essential for the formation of high-aspect ratio nanowires [4.49]. In growing CdSe nanorods [4.38], Alivisatos et al. used a mixture of two surfactants, whose concentration ratio influenced the structure of the nanocrystal. It is believed that different surfactants have different affinities and different absorption rates for the different crystal faces of CdSe, thereby regulating the growth rate of these faces. A coordinating alkyl-diamine solvent was used to grow polycrystalline PbSe nanowires at low temperatures [4.55]. Here, the surfactant-induced directional growth is believed to occur, through the formation of organometallic complexes in which the bidentate ligand assumes the equatorial positions, thus hindering the ions from approaching each other in this plane. Additionally, the alkyl-amine molecules coat the external surface of the wire, preventing lateral growth. The aspect ratio of the wires increased as the temperature was lowered in the range $10 < T < 117\,°C$. Ethylenediamine was used to grow CdS nanowires and tetrapods by a solvo-thermal recrystallization process starting with CdS nanocrystals or amorphous particles [4.35]. While the coordinating solvent was crucial for the nanowire growth, the researchers did not clarify its role in the shape and phase control.

Stress-induced crystalline bismuth nanowires have been grown from sputtered films of layers of Bi and CrN. The nanowires presumably grow from defects and cleavage fractures in the film and are up to several millimeter in lengths with diameters ranging from 30 to 200 nm [4.27]. While the exploration of this technique has only begun, stress-induced unidirectional

© Springer 2004

growth should be applicable to a variety of composite films.

Selective electrodeposition along the step edges in highly oriented pyrolytic graphite (HOPG) was used to obtain MoO_2 nanowires as shown in Fig. 4.8. The site-selectivity was achieved by applying a low overpotential to the electrochemical cell in which the HOPG served as cathode, thus minimizing the nucleation events on less favorable sites (i. e., plateaus). While these nanowires cannot be removed from the substrate, they can be reduced to metallic molybdenum nanowires, which can then be released as free-standing nanowires. Other metallic nanowires were also obtained by this method [4.53, 102]. In contrast to the template synthesis approaches described above, in this method the substrate defines only the position and orientation of the nanowire, not its diameter. In this context, other surface morphologies, such as self-assembled grooves in etched crystal planes, have been used to generate nanowire arrays via gas-phase shadow deposition (for example: Fe nanowires on (110)NaCl [4.44]). The cross-section of artificially prepared superlattice structures has also been used for site-selective electrodeposition of parallel and closely spaced nanowires [4.103]. Nanowires prepared on the above-mentioned substrates would have semicircular, rectangular, or other unconventional cross-sectional shapes.


Graphite
Elektrodeposition of MoO_2 nanowires
Reduction to Mo° in H_2 at 500 °C for ≈ 1h
Cast poly(styrene) film
Lift-off of embedded Mo° nanowires
Poly(styrene)

Fig. 4.8 Schematic of the electrodeposition step edge decoration of HOPG (highly oriented pyrolytic graphite) for the synthesis of molybdenum nanowires [4.53, 102]

4.1.4 Hierarchical Arrangement and Superstructures of Nanowires

Ordering nanowires into useful structures is another challenge to address in order to harness the full potential of nanowires for applications. We will first review examples of nanowires having a nontrivial structure and then proceed to describe methods to create assemblies of nanowires of a predetermined structure.

We have already mentioned in Sect. 4.1.2 that the preparation of nanowires with a graded composition or with a superlattice structure along their main axis was demonstrated by controlling the gas-phase chemistry as a function of time during the growth of the nanowires by the VLS method. Control of the composition along the axial dimension was also demonstrated by a template-assisted method, for example by the consecutive electrochemical deposition of different metals in the pores of an alumina template [4.104]. Alternatively, the composition can be varied along the radial dimension of the nanowire, for example, by first growing a nanowire by the VLS method and then switching the synthesis conditions to grow a different material on the surface of the nanowire by CVD. This technique was demonstrated for the synthesis of Si/Ge and Ge/Si coaxial (or core-shell) nanowires [4.105], and it was shown that by a thermal annealing process the outer shell can be formed epitaxially on the inner core. A different approach was adopted by *Wang* et al. who generated a mixture of coaxial and biaxial SiC-SiO_x nanowires by the catalyst-free high-temperature reaction of amorphous silica and a carbon/graphite mixture [4.106].

A different category of nontrivial nanowires is that of nanowires having a nonlinear structure, resulting from multiple one-dimensional growth steps. Members of this category are tetrapods, which were mentioned in the context of liquid-phase synthesis (Sect. 4.1.3). In this process, a tetrahedral quantum-dot core is first grown, and then the conditions are modified to induce a one-dimensional growth of a nanowire from each one of the facets of the tetrahedron. A similar process



Fig. 4.9a–d SEM images of **(a)** 6-fold **(b)** 4-fold and **(c)** 2-fold symmetry nanobrushes made of an In_2O_3 core and ZnO nanowire brushes [4.107], and of **(d)** ZnO nanonails [4.108]

produced high-symmetry In_2O_3/ZnO hierarchical nanostructures. From a mixture of heat-treated In_2O_3, ZnO and graphite powders, faceted In_2O_3 nanowires were first obtained, on which oriented shorter ZnO nanowires crystallized [4.107]. Brush-like structures were obtained as a mixture of 11 structures of different symmetries. For example, two, four, or six rows of ZnO nanorods could be found on different core nanowires, depending on the crystallographic orientation of the main axis of the core nanowire, as shown in Fig. 4.9. Comb-like structures entirely made of ZnO were also reported [4.65].

Control of the position of a nanowire in the growth process is important for preparing devices or test structures containing nanowires, especially when involving a large array of nanowires. Post-synthesis methods to align and position nanowires include microfluidic channels [4.110], Langmuir–Blodgett assemblies [4.109], and electric-field assisted assembly [4.111]. The first method involves the orientation of the nanowires by the liquid flow direction when a nanowire solution is injected into a microfluidic channel assembly and by the interaction of the nanowires with the side walls of the channel. The second method involves the alignment of nanowires at a liquid-gas or liquid-liquid interface by the application of compressive forces on the interface (Fig. 4.10). The third technique is based on dielectrophoretic forces that pull polarizable nanowires toward regions of high field strength. The nanowires align between two isolated electrodes that are capacitatively coupled to a pair of buried electrodes biased with an AC voltage. Once a nanowire shorts the electrodes, the electric field is eliminated, preventing more nanowires from depositing. The above techniques have been successfully used to prepare electronic circuitry and optical devices out of nanowires (see Sects. 4.3.1 and 4.3.3). Alternatively, alignment and positioning of the nanowires can be specified and controlled during their growth by the proper design of the synthesis. For example, ZnO nanowires prepared by the VLS method were grown into an array in which both their position on the substrate and their growth direction and orientation were controlled [4.65]. The nanowire growth region was defined by patterning the gold film, which serves as a catalyst for the ZnO nanowire growth, employing soft-lithography, e-beam lithography, or photolithography. The orientation of the nanowires was achieved by selecting a substrate with a lattice structure matching that of the nanowire material to facilitate the epitaxial growth. These conditions result in an array of nanowire posts at predetermined positions, all vertically aligned with the same crystal growth orientation (see Fig. 4.11). A similar structure could be obtained by the template-mediated electrochemical synthesis of nanowires (see Sect. 4.1.1), particularly if anodic alumina with its parallel and ordered channels is used. The control over the



Fig. 4.10 A TEM image of a smectic phase of a $BaCrO_4$ nanorod film (*left inset*) achieved by the Langmuir–Blodgett technique, as depicted by the illustration [4.109]



Fig. 4.11a–c SEM images of ZnO nanowire arrays grown on a sapphire substrate, where **(a)** shows patterned growth, **(b)** shows a higher resolution image of the parallel alignment of the nanowires, and **(c)** shows the faceted side-walls and the hexagonal cross section of the nanowires. For nanowire growth, the sapphire substrates were coated with a 1.0 to 3.5 nm thick patterned layer of Au as the catalyst, using a TEM grid as the shadow mask. These nanowires have been used for nanowire laser applications [4.115]

location of the nucleation of nanowires in the electrochemical deposition is determined by the pore positions and the back-electrode geometry. The pore positions can be precisely controlled by imprint lithography [4.112]. By growing the template on a patterned conductive substrate that serves as a back-electrode [4.113,114], different materials can be deposited in the pores at different regions of the template.

4.2 Characterization and Physical Properties of Nanowires

In this section we review the structure and properties of nanowires, and the interrelationship between the two. The discovery and investigation of nanostructures were galvanized by advances in various characterization and microscopy techniques that enable materials characterization to take place at smaller and smaller length scales, reaching down to individual atoms. For applications, characterization of the nanowire structural properties is especially important so that a reproducible relationship between their desired functionality and their geometrical and structural characteristics can be established. Due to the enhanced surface-to-volume ratio in nanowires, their properties may depend sensitively on their surface condition and geometrical configuration. Even nanowires made of the same material may possess dissimilar properties due to differences in their crystal phase, crystalline size, surface conditions, and aspect ratios, which depend on the synthesis methods and conditions used in their preparation.

4.2.1 Structural Characterization

Structural and geometric factors play an important role in determining the various attributes of nanowires, such as their electrical, optical and magnetic properties. Various novel tools, therefore, have been developed and employed to obtain this important structural information at the nanoscale. At the micron scale, optical techniques are extensively used for imaging structural features. Since the sizes of nanowires are usually comparable to or, in most cases, much smaller than the wavelength of visible light, traditional optical microscopy techniques are usually limited in characterizing the morphology and surface features of nanowires. Electron microscopy techniques, therefore, play a more dominant role at the nanoscale. Since electrons interact more strongly than photons, electron microscopy is particularly sensitive relative to X-rays for the analysis of tiny samples.

In this section we review and give examples of how scanning electron microscopy, transmission electron microscopy, scanning probe spectroscopies, and diffraction techniques are used to characterize the structure of nanowires. To provide the necessary basis for developing reliable structure-property relations, we apply multiple characterization tools to the same samples.

Scanning Electron Microscopy (SEM)

SEM usually produces images down to length scales of ∼ 10 nm and provides valuable information regarding the structural arrangement, spatial distribution, wire density, and geometrical features of the nanowires. Examples of SEM micrographs shown in Figs. 4.1 and

4.3 indicate that structural features at the 10 nm to 10 μm length scales can be probed, providing information on the size, size distribution, shapes, spatial distributions, density, nanowire alignment, filling factors, granularity etc. As another example, Fig. 4.11a shows an SEM image of ZnO nanowire arrays grown on a sapphire substrate [4.115], which provides evidence for the nonuniform spatial distribution of the nanowires on the substrate. This distribution was attained by patterning the catalyst film to define high density growth regions and nanowire-free regions. Figure 4.11b, showing a higher magnification of the same system, indicates that these ZnO nanowires grow perpendicular to the substrate, are well aligned with approximately equal wire lengths, and have wire diameters in the range of $20 < d_W < 150$ nm. The SEM micrograph in Fig. 4.11c provides further information about the surface of the nanowires, showing it to be well-faceted and forming a hexagonal cross-section, indicative of nanowire growth along the ⟨0001⟩ direction. The uniformity of the nanowire size, its alignment perpendicular to the substrate, and its uniform growth direction, as suggested by the SEM data, are linked to the good epitaxial interface between the (0001) plane of the ZnO nanowire and the (110) plane of the sapphire substrate. (The crystal structures of ZnO and sapphire are essentially incommensurate, with the exception that the *a* axis of ZnO and the *c* axis of sapphire are related almost exactly by a factor of 4, with a mismatch of less than 0.08% at room temperature [4.115].) The well-faceted nature of these nanowires has important implications for their lasing action (see Sect. 4.3.2). Figure 4.12 shows an SEM image of GaN nanowires synthesized by a laser-assisted catalytic growth method [4.46], indicating a random spatial orientation of the nanowire axes and a wide diameter distribution for these nanowires, in contrast to the ZnO wires in Fig. 4.11 and to arrays of well-aligned nanowires prepared by template-assisted growth (see Fig. 4.3).



Fig. 4.12 SEM image of GaN nanowires in a mat arrangement synthesized by laser-assisted catalytic growth. The nanowires have diameters and lengths on the order of 10 nm and 10 μm, respectively [4.46]

Transmission Electron Microscopy (TEM)

TEM and high resolution transmission electron microscopy (HRTEM) are powerful imaging tools to study nanowires at the atomic scale, and they usually provide more detailed geometrical features than are seen in SEM images. TEM studies also yield information regarding the crystal structure, crystal quality, grain size, and crystal orientation of the nanowire axis. When operating in the diffraction mode, selected area electron diffraction (SAED) patterns can be made to determine the crystal structure of nanowires. As an example, the TEM images in Fig. 4.13 show four different morphologies for Si nanowires prepared by the laser ablation of a Si target [4.116]: (a) spring-shaped; (b) fishbone-shaped (indicated by solid arrow) and frog-egg-shaped (indicated by the hollow arrow), (c) pearl-shaped, while (d) shows the poly-sites of nanowire nucleation. The crystal quality of nanowires is revealed from high resolution TEM images with atomic resolution, along with selected area electron diffraction (SAED) patterns. For example, Fig. 4.14 shows a TEM image of one of the GaN nanowires from Fig. 4.12, indicating single crystallinity and showing (100) lattice planes, thus demonstrating the growth direction of the nanowire. This information is supplemented by the corresponding electron diffraction pattern in the upper right.

The high resolution of the TEM also allows for the investigation of the surface structure of the nanowires. In many cases the nanowires are sheathed with a native oxide layer or an amorphous oxide layer that forms during the growth process. This can be seen in Fig. 4.6b for silicon nanowires and in Fig. 4.15 for germanium nanowires [4.51], showing a mass-thickness contrast TEM image and a selected-area electron diffraction pattern of a Ge nanowire. The main TEM image shows that these Ge nanowires possess an amorphous GeO_2 sheath with a crystalline Ge core oriented in the [211] direction.

Dynamical processes of the surface layer of nanowires can be studied by using an in situ environ-



Fig. 4.13a–d TEM morphologies of four special forms of Si nanowires synthesized by the laser ablation of a Si powder target. **(a)** A spring-shaped Si nanowire; **(b)** fishbone-shaped (indicated by a *solid arrow*) and frog-egg-shaped (indicated by a *hollow arrow*) Si nanowires; and **(c)** pearl-shaped nanowires, while **(d)** shows poly-sites for the nucleation of silicon nanowires (indicated by *arrows*) [4.116]



Fig. 4.14 Lattice resolved high resolution TEM image of one GaN nanowire (*left*) showing that (100) lattice planes are visible perpendicular to the wire axis. The electron diffraction pattern (*top right*) was recorded along the ⟨001⟩ zone axis. A lattice-resolved TEM image (*lower right*) highlights the continuity of the lattice up to the nanowire edge, where a thin native oxide layer is found. The directions of various crystallographic planes are indicated in the *lower right* figure [4.46]

mental TEM chamber, which allows TEM observations to be made while different gases are introduced or as the sample is heat treated at various temperatures, as illustrated in Fig. 4.16. The figure shows high resolution TEM images of a Bi nanowire with an oxide coating and the effect of a dynamic oxide removal process carried out within the environmental chamber of the TEM [4.117]. The amorphous bismuth-oxide layer



Fig. 4.15 A mass-thickness contrast TEM image of a Ge nanowire taken along the [0$\bar{1}$1] zone axis and a selected-area electron diffraction pattern (*upper left inset*) [4.51]. The Ge nanowires were synthesized by laser ablation of a mixture of Ge and GeO_2 powder. The core of the Ge nanowire is crystalline, while the surface GeO_2 is amorphous

coating the nanowire (Fig. 4.16a) is removed by exposure to hydrogen gas within the environmental chamber of the TEM, as indicated in Fig. 4.16b.

By coupling the powerful imaging capabilities of TEM with other characterization tools, such as an electron energy loss spectrometer (EELS) or an energy dispersive X-ray spectrometer (EDS) within the TEM instrument, additional properties of the nanowires can be probed with high spatial resolution. With the EELS technique, the energy and momentum of the incident and scattered electrons are measured in an inelastic electron scattering process to provide information on the energy and momentum of the excitations in the nanowire sample. Fig. 4.17 shows the dependence on nanowire diameter of the electron energy loss spectra of Bi nanowires. The spectra were taken from the center of the nanowire, and the shift in the energy of the peak position (Fig. 4.17) indicates the effect of the nanowire diameter on the plasmon frequency in the nanowires. The results show changes in the electronic structure of Bi nanowires as the wire diameter decreases [4.118]. Such changes in electronic structure as a function of nanowire diameter are also observed in their transport (Sect. 4.2.2) and optical (Sect. 4.2.3) properties and are related to quantum confinement effects.



Fig. 4.16 High resolution transmission electron microscope (HRTEM) image of a Bi nanowire (*left*) before and (*right*) after annealing in hydrogen gas at 130 °C for 6 hours within the environmental chamber of the HRTEM instrument to remove the oxide surface layer [4.117]

EDS measures the energy and intensity distribution of X-rays generated by the impact of the electron beam on the surface of the sample. The elemental composition within the probed area can be determined to a high degree of precision. The technique was particularly useful for the compositional characterization of superlattice



Fig. 4.17 Electron energy loss spectra (EELS) taken from the center of bismuth nanowires with diameters of 35, 60, and 90 nm. The shift in the volume plasmon peaks is due to the wire diameter effects on the electronic structure [4.118]

nanowires [4.90] and core-sheath nanowires [4.105] (see Sect. 4.1.2).

Scanning Tunneling Probes

Several scanning probe techniques [4.119], such as scanning tunneling microscopy (STM), electric field gradient microscopy (EFM) [4.16], magnetic field microscopy (MFM) [4.54], and scanning thermal microscopy (SThM) [4.120], combined with atomic force microscopy (AFM), have been employed to study the structural, electronic, magnetic, and thermal properties of nanowires. A scanning tunneling microscope can be employed to reveal both topographical structural information, such as that illustrated in Fig. 4.18, as well as information on the local electronic density of states of a nanowire, when used in the STS (scanning tunneling spectroscopy) mode. Figure 4.18 shows STM height images (taken in the constant current STM mode) of MoSe molecular wires deposited from a methanol or acetonitrile solution of $Li_2Mo_6Se_6$ on to Au substrates. The STM image of a single MoSe wire (Fig. 4.18a) exhibits a 0.45 nm lattice repeat distance in a MoSe molecular wire. When both STM and STS measurements are made on the same sample, the electronic and structural properties can be correlated, for example, as in the joint STM/STS studies on Si nanowires [4.96], showing alternating segments of a single nanowire identified with growth along [110] and [112] directions, and different I–V characteristics measured for the [110] segments as compared with the [112] segments.



Fig. 4.18a–d STM height images, obtained in the constant current mode, of MoSe chains deposited on an Au(111) substrate. **(a)** A single chain image, and **(b)** a MoSe wire bundle. **(c)** and **(d)** Images of MoSe wire fragments containing 5 and 3 unit cells, respectively [4.119]. The scale bars are all 1 nm

Magnetic field microscopy (MFM) has been employed to study magnetic polarization of magnetic nanowires embedded in an insulating template, such as an anodic alumina template. For example, Fig. 4.19a shows the topographic image of an anodic alumina template filled with Ni nanowires, and Fig. 4.19b demonstrates the corresponding magnetic polarization of each nanowire in the template. This micrograph shows that a magnetic field microscopy probe can distinguish between spin-up and spin-down nanowires in the nanowire



Fig. 4.19 **(a)** Topographic image of a highly ordered porous alumina template with a period of 100 nm filled with 35 nm diameter nickel nanowires. **(b)** The corresponding MFM (magnetic force microscope) image of the nano-magnet array, showing that the pillars are magnetized alternately "up" (*white*) and "down" (*black*) [4.54]

array, thereby providing a method for measuring interwire magnetic dipolar interactions [4.54].

X-Ray Analysis

Other characterization techniques commonly used to study the crystal structure and chemical composition of nanowires include X-ray diffraction and X-ray energy dispersion analysis (EDAX). The peak positions in the X-ray diffraction pattern can be used to determine the chemical composition and the crystal phase structure of the nanowires. For example, Fig. 4.2 shows that Bi nanowires have the same crystal structure and lattice constants as bulk bismuth. Both the X-ray diffraction pattern (XRD) for an array of aligned Bi nanowires (Fig. 4.2) and the SAED pattern for individual Bi nanowires [4.16] suggest that the nanowires have a common axis of crystal orientation.

As another example of an XRD pattern for an array of aligned nanowires, Fig. 4.20 shows the X-ray diffraction pattern of the ZnO nanowires displayed in Fig. 4.11. Only (00ℓ) diffraction peaks are observed for these aligned ZnO nanowires, indicating that their preferred growth direction is (001) along the wire axis. A similar preferred growth orientation was also observed for Bi nanowires produced by high pressure injection (see Sect. 4.1.1), while the vapor phase and low pressure injection filling techniques give preferred alignment along lower symmetry axes (see Fig. 4.2).

EDAX has been used to determine the chemical composition, stoichiometry of compound nanowires, or the impurity content in the nanowires. But the results from EDAX analysis should be interpreted carefully to avoid systematic errors.

4.2.2 Transport Properties

The study of nanowire electrical transport properties is important for nanowire characterization, electronic device applications, and the investigation of unusual transport phenomena arising from one-dimensional quantum effects. Important factors that determine the transport properties of nanowires include the wire diameter (important for both classical and quantum size effects), material composition, surface conditions, crystal quality, and the crystallographic orientation along the wire axis, which is important for materials with anisotropic materials parameters, such as the effective mass tensor, the Fermi surface, or the carrier mobility.

Electronic transport phenomena in low-dimensional systems can be roughly divided into two categories: ballistic and diffusive transport. Ballistic transport phenomena occur when electrons travel across the nanowire without any scattering. In this case, the conduction is mainly determined by the contacts between the nanowire and the external circuit, and the conductance is quantized into an integral number of universal conductance units $G_0 = 2e^2/h$ [4.121, 122]. Ballistic transport phenomena are usually observed in very short quantum wires, such as those produced by using mechanically controlled break junctions (MCBJ) [4.123, 124] where the electron mean free path is much longer than the wire length, and the conduction is a pure quantum phenomenon. To observe ballistic transport, the thermal energy must also obey the relation $k_BT \ll \varepsilon_j - \varepsilon_{j-1}$, where $\varepsilon_j - \varepsilon_{j-1}$ is the energy separation between subband levels j and $j-1$. On the other hand, for nanowires with lengths much larger than the carrier mean free path, the electrons (or holes) undergo numerous scattering events when they travel along the wire. In this case, the transport is in the diffusive regime, and the conduction is dominated by carrier scattering within the wires due to phonons (lattice vibrations), boundary scattering, lattice and other structural defects, and impurity atoms.



Fig. 4.20 X-ray diffraction pattern of aligned ZnO nanowires (see Fig. 4.11) grown on a sapphire substrate. Only $[00\ell]$ diffraction peaks are observed for the nanowires, owing to their well-oriented growth orientation. Strong diffraction peaks for the sapphire substrate are also found [4.115]

Conductance Quantization in Metallic Nanowires

The ballistic transport of 1-D systems has been extensively studied since the discovery of quantized conductance in 1-D systems in 1988 [4.121, 122]. The phenomena of conductance quantization occur when the diameter of the nanowire is comparable to the electron Fermi wavelength, which is on the order of 0.5 nm for most metals [4.125]. Most conductance quantization experiments up to the present were performed by joining and separating two metal electrodes. As the two metal electrodes are slowly separated, a nano-contact is formed before it breaks completely (see Fig. 4.21a), and conductance in integral multiple values of G_0 is observed through these nano-contacts. Fig. 4.21b shows the conductance histogram built with 18,000 contact breakage curves between two gold electrodes at room temperature [4.126], with the electrode separation up to ~ 1.8 nm. The conductance quantization behavior is found to be independent of the contact material and has been observed in various metals, such as Au [4.126], Ag, Na, Cu [4.127], and Hg [4.128]. For semimetals such as Bi, conductance quantization has also been observed for an electrode separation of as long as 100 nm at 4 K because of the long Fermi wavelength (~ 26 nm) [4.125], indicating that the conductance quantization may be due to the existence of well-defined quantum states localized at a constriction instead of resulting from the atom rearrangement as the electrodes separate. Since the conductance quantization is observed only in breaking contacts, or for very narrow and very short nanowires, most nanowires of practical interest (possessing lengths of several microns) lie in the diffusive transport regime, where the carrier scattering is significant and should be considered.



Fig. 4.21 **(a)** Schematic representation of the last stages of the contact breakage process [4.126]. **(b)** Histogram of conductance values built with 18,000 gold contact breakage experiments in air at room temperature, showing conductance peaks at integral values of G_0. In this experiment the gold electrodes approach and separate at 89,000 Å/s [4.126]

I–V Characterization of Semiconducting Nanowires

The electronic transport behavior of nanowires may be categorized based on the relative magnitude of three length scales: carrier mean free path ℓ_W, the de Broglie wavelength of electrons λ_e, and the wire diameter d_W. For wire diameters much larger than the carrier mean free path ($d_W \gg \ell_W$), the nanowires exhibit transport properties similar to bulk materials, which are independent of the wire diameter, since the scattering due to the wire boundary is negligible compared to other scattering mechanisms. For wire diameters comparable or smaller than the carrier mean free path ($d_W \sim \ell_W$ or $d_W < \ell_W$) but still much larger than the de Broglie wavelength of the electrons ($d_W \gg \lambda_e$), the transport in nanowires is in the classical finite size regime, in which the band structure of the nanowire is still similar to that of bulk while the scattering events at the wire boundary alter their transport behavior. For wire diameters comparable to the electronic wavelength $d_W \sim \lambda_e$, the electronic density of states is altered dramatically and quantum subbands are formed due to the quantum confinement effect at the wire boundary. In this regime, the transport properties are further influenced by the change in the band structure. Transport properties for nanowires in the classical finite size and quantum size regimes, therefore, are highly diameter-dependent.

Researchers have investigated the transport properties of various semiconducting nanowires and have demonstrated their potential for diverse electronic devices, such as for p-n diodes [4.129, 130], field effect transistors [4.129], memory cells, and switches [4.131] (see Sect. 4.3.1). The nanowires studied so far in this context have usually been made from conventional semiconducting materials, such as group IV and III-V compound semiconductors via the VLS growth method (see Sect. 4.1.2), and their nanowire properties have been compared to their well-established bulk properties. Interestingly, the physical principles for describing bulk semiconductor devices also hold for devices based on these semiconducting nanowires with wire diameters of tens of nanometers. For example, Fig. 4.22 shows the current–voltage (I–V) behavior of a 4-by-1 crossed p-Si/n-GaN junction array at room temperature [4.129]. The long horizontal wire in the figure is a p-Si nanowire (10–25 nm in diameter) and the four short vertical wires are n-GaN nanowires (10–30 nm in diameter). Each of the four nanoscale cross points independently forms a p-n junction with current rectification behavior, as shown by the I–V curves in Fig. 4.22, and the junction behavior (e.g., the turn-on voltage) can



Fig. 4.22 I–V behavior for a 4(p) by 1(n) crossed p-Si/n-GaN junction array shown schematically in the inset. The four curves represent the I–V response for each of the four junctions, showing similar current rectifying characteristics in each case. The length scale bar between the two middle junctions is 2 µm [4.129]. The p-Si and n-GaN nanowires are 10–25 nm and 10–30 nm in diameter, respectively



Fig. 4.23 Gate-dependent I–V characteristics of a crossed nanowire field-effect transistor (FET). The n-GaN nanowire is used as the nano-gate, with the gate voltage indicated (0, 1, 2, and 3 V). The inset shows the current vs. V_{gate} for a nanowire gate (*lower curve*) and for a global back-gate (*top curve*) when the bias voltage is set at 1 V [4.129]

be controlled by varying the oxide coating on these nanowires [4.129].

Huang et al. have demonstrated nanowire junction diodes with a high turn-on voltage (~ 5 V) by increasing the oxide thickness at the junctions. The high turn-on voltage enables the use of the junction in a nanoscale FET as shown in Fig. 4.23 [4.129], where I–V data for a p-Si nanowire are presented, for which the n-GaN nanowire with a thick oxide coating is used as a nano-gate. By varying the nano-gate voltage, the conductance of the p-Si nanowire can be changed by more than a factor of 10^5 (lower curve in the inset), whereas the conductance changes by only a factor of ten when a global back-gate is used (top curve in the inset of Fig. 4.23). This behavior may be due to the thin gate dielectric between the crossed nanowires and the better control of the local carrier density through a nano-gate. Based on the gate-dependent I–V data of these p-Si nanowires, it is found that the mobility for holes in the p-Si nanowires may be higher than that for bulk p-Si, although further investigation is required for a complete understanding.

Because of the enhanced surface-to-volume ratio of nanowires, their transport behavior may be modified by changing their surface conditions. For example, researchers have found that by coating n-InP nanowires with a layer of redox molecules such as cobalt phthalocyanine, the conductance of the InP nanowires may change by orders of magnitude by altering the charge state of the redox molecules to provide bistable nanoscale switches [4.131]. The resistance (or conductance) of some nanowires (e.g., Pd nanowires) is also very sensitive to the presence of certain gases (e.g., H_2) [4.132, 133], and this property may be utilized for sensor applications to provide improved sensitivity compared to conventional sensors based on bulk material (see Sect. 4.3.4).

Although it remains unclear how the size may influence the transport properties and device performance of semiconducting nanowires, many of the larger diameter semiconducting nanowires are expected to be described by classical physics, since their quantization energies $\hbar^2/(2m_e d_W^2)$ are usually smaller than the thermal energy $k_B T$. By comparing the quantization energy with the thermal energy, the critical wire diameter below which quantum confinement effects become significant is estimated to be 1 nm for Si nanowires at room temperature, which is much smaller than the size of many of the semiconducting nanowires that have been investigated so far. By using material systems with much smaller effective carrier masses m_e (such as bismuth), the critical diameter for which such quantum effects can be observed is increased, thereby facilitating the study of quantum confinement effects. It is for this reason that the bismuth nanowire system has been studied so extensively. Furthermore, since the crystal structure and lattice constants of bismuth nanowires are the same as for 3-D crystalline bismuth, it is possible to carry out detailed model calculations to guide and to interpret transport and optical experiments on bismuth nanowires. For these reasons, bismuth can be considered as a model system for studying 1-D effects in nanowires.

Temperature-Dependent Resistance Measurements

Although nanowires with electronic properties similar to their bulk counterparts are promising for constructing nano-devices based on well-established knowledge of their bulk counterparts, it is expected that quantum size effects in nanowires will likely be utilized to generate new phenomena absent in bulk materials and thus provide enhanced performance and novel functionality for certain applications. In this context, the transport properties of bismuth (Bi) nanowires have been extensively studied, both theoretically [4.134] and experimentally [4.28, 30, 67, 135–138] because of their promise for enhanced thermoelectric performance. Transport studies of ferromagnetic nanowire arrays, such as Ni or Fe, have also received much attention because of their potential for high-density magnetic storage applications.

The very small electron effective mass components and the long carrier mean free paths in Bi facilitate the study of quantum size effects in the transport properties of nanowires. Quantum size effects are expected to become significant in bismuth nanowires with diameters smaller than 50 nm [4.134], and the fabrication of crystalline nanowires of this diameter range is relatively easy.

Figure 4.24a shows the T dependence of the resistance $R(T)$ for Bi nanowires ($7 \leq d_W < 200$ nm) synthesized by vapor deposition and pressure injection [4.28], illustrating the quantum effects in their temperature-dependent resistance. In Fig. 4.24a, the $R(T)$ behavior of Bi nanowires is dramatically different from that of bulk Bi and is highly sensitive to the wire diameter. The $R(T)$ curves in Fig. 4.24a show a non-monotonic trend for larger-diameter (70 and 200 nm) nanowires, although $R(T)$ becomes monotonic with T for small-diameter (≤ 48 nm) nanowires. This dramatic change in the behavior of $R(T)$ as a function of d_W is attributed to a unique semimetal-semiconductor transition phenomena in Bi [4.139], induced by quantum size effects. Bi is a semimetal in bulk form, in which the T-point valence band overlaps with the L-point conduction band by 38 meV at 77 K. As the wire diameter decreases, the lowest conduction subband increases in energy, and the highest valence subband decreases in energy. Model calculations predict that the band overlap should vanish in Bi nanowires (with their wire axes along the trigonal direction) at a wire diameter ~ 50 nm [4.134].

The resistance of Bi nanowires is determined by two competing factors: the carrier density that increases with T, and the carrier mobility that decreases with T. The non-monotonic $R(T)$ for large-diameter Bi nanowires is due to a smaller carrier concentration variation at low temperature (≤ 100 K) in semimetals, so that the electrical resistance is dominated by the mobility factor in this temperature range. Based on the semiclassical transport model and the established band structure of Bi nanowires, the calculated $R(T)/R(300\,\mathrm{K})$ for 36-nm and 70-nm Bi nanowires is shown by the solid curves in Fig. 4.24c to illustrate different $R(T)$ trends for semiconducting and semimetallic nanowires, respectively [4.67]. The curves in Fig. 4.24c exhibit trends consistent with experimental results. The condition for the semimetal–semiconductor transition in Bi nanowires can be experimentally determined, as shown by the measured resistance ratio $R(10\,\mathrm{K})/R(100\,\mathrm{K})$ of Bi nanowires as a function of wire diameter [4.140] in Fig. 4.25. The maximum in the resistance ratio $R(10\,\mathrm{K})/R(100\,\mathrm{K})$ at $d_W \sim 48$ nm indicates the wire diameter for the transition of Bi nanowires from a semimetallic phase to a semiconducting phase. The semimetal–semiconductor transition and the semiconducting phase in Bi nanowires are examples of new transport phenomena, resulting from low dimensionality and absent in the bulk 3-D phase, which further increase the possible benefits from the properties of nanowires for desired applications (see Sect. 4.3.2).

It should be noted that good crystal quality is essential for observing the quantum size effect in nanowires, as shown by the $R(T)$ plots in Fig. 4.24a. For example, Fig. 4.24b shows the normalized $R(T)$ measurements of Bi nanowires with larger diameters (200 nm–2 μm) prepared by electrochemical deposition [4.30], and these nanowires possess monotonic $R(T)$ behaviors, quite different from those of the corresponding nanowire diameters shown in Fig. 4.24a. The absence of the resistance maximum in Fig. 4.24b is due to the lower crystalline quality for nanowires prepared by electrochemical deposition, which tends to produce polycrystalline nanowires with a much lower



Fig. 4.24 **(a)** Measured temperature dependence of the resistance $R(T)$ normalized to the room temperature (300 K) resistance for bismuth nanowire arrays of various wire diameters d_W [4.28]. **(b)** $R(T)/R(290\,K)$ for bismuth wires of larger d_W and lower mobility [4.30]. **(c)** Calculated $R(T)/R(300\,K)$ of 36-nm and 70-nm bismuth nanowires. The *dashed curve* refers to a 70-nm polycrystalline wire with increased boundary scattering [4.139]



Fig. 4.25 Measured resistance ratio $R(10\,K)/R(100\,K)$ of Bi nanowires as a function of diameter. The peak indicates the transition from a semimetallic phase to a semiconducting phase as the wire diameter decreases [4.141]

carrier mobility. This monotonic $R(T)$ for semimetallic Bi nanowires at a higher defect level is also confirmed by theoretical calculations, as shown by the dashed curve in Fig. 4.24c for 70-nm wires with increased grain boundary scattering [4.139].

The theoretical model developed for Bi nanowires not only provides good agreement with experimental results, but it also plays an essential role in understanding the influence of the quantum size effect, the boundary scattering, and the crystal quality on their electrical properties. The transport model has also been generalized to predict the transport properties of Te-doped Bi nanowires [4.67], Sb nanowires [4.142], and BiSb alloy nanowires [4.143], and good agreement between experiment and theory has also been obtained for these cases. While the electronic density of states may be significantly altered due to quantum confinement effects, various scattering mechanisms related to the transport properties of nanowires can be accounted for by Matthiessen's rule.

For nanowires with diameters comparable to the phase-breaking length, their transport properties may be further influenced by localization effects. It has been predicted that in disordered systems, the extended electronic wave functions become localized near defect sites, resulting in the trapping of carriers and giving rise to a different transport behavior. Localization effects are also expected to be more pronounced as dimensionality and sample size are reduced. Localization effects on the transport properties of nanowire systems have been studied on Bi nanowires [4.144] and, more recently, on Zn nanowires [4.63]. Figure 4.26 shows the measured $R(T)/R(300\,\text{K})$ of Zn nanowires fabricated by vapor deposition in porous silica or alumina [4.63]. While 15 nm Zn nanowires exhibit an $R(T)$ behavior with a T^1 dependence as expected for a metallic wire, the $R(T)$ of 9 nm and 4 nm Zn nanowires exhibits a temperature dependence of $T^{-1/2}$ at low temperature, consistent with 1-D localization theory. Thus, due to this localization effect, the use of nanowires with very small diameters for transport applications may be limited.



Fig. 4.26 Temperature dependence of the resistance of Zn nanowires synthesized by vapor deposition in various porous templates [4.63]. The data are given as points, the *full line* are fits to a T^1 law for 15 nm diameter Zn nanowires in an SiO_2 template, denoted by Zn/SiO_2. Fits to a combined T^1 and $T^{-1/2}$ law were made for the smaller nanowire diameter composite denoted by 9 nm Zn/Al_2O_3 and 4 nm Zn/Vycor glass

Magnetoresistance

Magnetoresistance (MR) measurements provide an informative technique for characterizing nanowires because these measurements yield a great deal of information about the electron scattering with wire boundaries, the effects of doping and annealing on scattering, and localization effects in the nanowires [4.137]. For example, at low fields the MR data show a quadratic dependence on the B field from which carrier mobility estimates can be made (see Fig. 4.27 at low B field).

Figure 4.27 shows the longitudinal magnetoresistance ($\boldsymbol{B}$ parallel to the wire axis) for 65 nm and 109 nm Bi nanowire samples (before thermal annealing) at 2 K. The MR maxima in Fig. 4.27a are due to the classical size effect, where the wire boundary scattering is reduced as the cyclotron radius becomes smaller than the wire radius in the high field limit, resulting in a decrease in the resistivity. This behavior is typical for the longitudinal MR of Bi nanowires in the diameter range of 45 nm to 200 nm [4.28, 136, 137, 145], and the peak position B_m moves to lower B field values as the wire diameter increases, as shown in Fig. 4.27c [4.145], in which B_m varies linearly with $1/d_W$. The condition for the occurrance of B_m is approximately given by $B_m \sim 2c\hbar k_F/ed_W$ where k_F is the wave vector at the Fermi energy. The peak position, B_m, is found to increase linearly with temperature in the range of 2 to 100 K, as shown in Fig. 4.27b [4.145]. As T is increased, phonon scattering becomes increasingly important, and therefore a higher magnetic field is required to reduce the resistivity associated with boundary scattering sufficiently to change the sign of the MR. Likewise, in-



Fig. 4.27 **(a)** Longitudinal magnetoresistance, $\Delta R(B)/R(0)$, at 2 K as a function of B for Bi nanowire arrays with diameters 65 and 109 nm before thermal annealing. **(b)** The peak position B_m as a function of temperature for the 109 nm diameter Bi nanowire array after thermal annealing. **(c)** The peak position B_m of the longitudinal MR (after thermal annealing) at 2 K as a function of $1/d_W$, the reciprocal of the nanowire diameter [4.145]

creasing the grain boundary scattering is also expected to increase the value of B_m at a given T and wire diameter.

The presence of the peak in the longitudinal MR of nanowires requires a high crystal quality with long carrier mean free paths along the nanowire axis, so that most scattering events occur at the wire boundary instead of at a grain boundary, at impurity sites, or at defect sites within the nanowire. *Liu* et al. have investigated the MR of 400-nm Bi nanowires synthesized by electrochemical deposition [4.21], and no peak in the longitudinal MR is observed. The absence of a magnetoresistance peak may be attributed to a higher defect level in the nanowires produced electrochemically and to a large wire diameter, much longer than the carrier mean free path. The negative MR observed for the Bi nanowire arrays above B_m (see Fig. 4.27) shows that wire boundary scattering is a dominant scattering process for the longitudinal magnetoresistance, thereby establishing that the mean free path is larger than the wire diameter and that a ballistic transport behavior is indeed observed in the high field regime.

In addition to the longitudinal magnetoresistance measurements, transverse magnetoresistance measurements (**B** perpendicular to the wire axis) have also been performed on Bi nanowires array samples [4.28, 137, 145], where a monotonically increasing B^2 dependence over the entire range $0 \leq B \leq 5.5$ T is found for all Bi nanowires studied thus far. This is as expected, since the wire boundary scattering cannot be reduced by a magnetic field perpendicular to the wire axis. The transverse magnetoresistance is also found always to be larger than the longitudinal magnetoresistance in nanowire arrays.

By applying a magnetic field to nanowires at very low temperatures (≤ 5 K), one can induce a transition from a 1-D confined system at low magnetic fields to a 3-D confined system as the field strength increases, as shown in Fig. 4.28 for the longitudinal MR of Bi nanowire arrays of various nanowire diameters (28–70 nm) for $T < 5$ K [4.137]. In these curves, a subtle step-like feature is seen at low magnetic fields, which is found to depend only on the wire diameter, and is independent of temperature, the orientation of the magnetic field, and even on the nanowire material (e.g., in Sb nanowires [4.142]). The lack of a dependence of the magnetic field at which the step appears on temperature, field orientation, and material type indicates that



Fig. 4.28 Longitudinal magnetoresistance as a function of magnetic field for Bi nanowires of the diameters indicated. The vertical bars indicate the critical magnetic field B_c at which the magnetic length equals the nanowire diameter [4.137]

the phenomenon is related to the magnetic field length, $L_H = (\hbar/eB)^{1/2}$. The characteristic length L_H is the spatial extent of the wave function of electrons in the lowest Landau level, and L_H is independent of the carrier effective masses. Setting $L_H(B_c)$ equal to the diameter d_W of the nanowire defines a critical magnetic field strength, B_c, below which the wave function is confined by the nanowire boundary (the 1-D regime), and above which the wave function is confined by the magnetic field (the 3-D regime). The physical basis for this phenomenon is associated with confinement of a single magnetic flux quantum within the nanowire cross section [4.137]. This phenomenon, though independent of temperature, is observed for $T \leq 5$ K, since the phase breaking length has to be larger than the wire diameter. This calculated field strength, B_c, indicated in Fig. 4.28 by vertical lines for the appropriate nanowire diameters, provides a good fit to the step-like features in these MR curves.

The Shubnikov–de Haas (SdH) quantum oscillatory effect, which results from the passage of the quantized Landau levels through the Fermi energy as the field strength varies, should, in principle, provide the most direct measurement of the Fermi energy and carrier density. For example, *Heremans* et al. have demonstrated that SdH oscillations can be observed in Bi nanowire samples with diameters down to 200 nm [4.146] and have demonstrated that Te doping can be used to raise the Fermi energy in Bi nanowires. Such information on the Fermi energy is important because, for certain applications based on nanowires, it is necessary to place the Fermi energy near a subband edge where the density of states has a sharp feature. But due to the unusual 1-D geometry for nanowires, other characterization techniques commonly used in bulk materials to determine the Fermi energy and the carrier concentration (e.g., the Hall measurement) cannot be applied for nanowire systems. The observation of the SdH oscillatory effect requires very high crystal quality samples that allow carriers to execute a complete cyclotron orbit in the nanowire before they are scattered. For small nanowire diameters, large magnetic fields are required to produce cyclotron radii smaller than the wire radius. For some nanowire systems, all Landau levels may have passed through the Fermi level at such a high field strength, and in such a case, no oscillations can be observed. The localization effect may also prevent the observation of SdH oscillations for very small diameter (≤ 10 nm) nanowires. Observing SdH oscillations in highly doped samples (as may be required for certain applications) may be difficult because impurity scattering reduces the mean free path, requiring high $\boldsymbol{B}$ fields to satisfy the requirement that carriers complete a cyclotron orbit prior to scattering. Although SdH oscillations provide the most direct method of measuring the Fermi energy and carrier density of nanowire samples, this technique may not work, however, for smaller diameter nanowires, or for heavily doped nanowires.

Thermoelectric Properties

Nanowires are predicted to be promising for thermoelectric applications [4.134, 147], due to their novel band structure compared to their bulk counterparts and the expected reduction in thermal conductivity associated with enhanced boundary scattering (see Sect. 4.2.2). Due to the sharp density of states at the 1-D subband edges (where the van Hove singularities occur), nanowires are expected to exhibit enhanced Seebeck coefficients compared to their bulk counterparts. Since the Seebeck coefficient measurement is independent of the number of nanowires contributing to the signal, the measurements on nanowire arrays of uniform wire diameter are, in principle, as informative as single-wire measurements. The major challenge in measuring the Seebeck coefficient of nanowires lies in the design of tiny temperature probes to determine accurately the temperature difference across the nanowire. Figure 4.29a shows the schematic experimental setup for the Seebeck coefficient measurement of nanowire arrays [4.148], where two thermocouples are placed on both faces of a nanowire array and a heater is attached on one face of the array to generate a temperature gradient along the nanowire axis. Ideally the size of the thermocouples should be much smaller than the thickness of the nanowire array template (i. e., the nanowire length) to minimize error. However, due to the thinness of most templates ($\leq 50\,\mu$m) and the large size of commercially available thermocouples ($\sim 12\,\mu$m), the measured Seebeck coefficient values are usually underestimated.



Fig. 4.29 **(a)** Experimental setup for the measurement of the Seebeck coefficient in nanowire arrays [4.148]. **(b)** Measured Seebeck coefficient as a function of temperature for Bi (○,▽) and $Bi_{0.95}Sb_{0.05}$ (●,▼) nanowires with different diameters. The *solid curve* denotes the Seebeck coefficient for bulk Bi [4.139]

The thermoelectric properties of Bi nanowire systems have been investigated extensively because of their potential as good thermoelectric materials. Figure 4.29b shows the measured Seebeck coefficient $S(T)$ as a function of temperature for nanowire arrays with diameters of 40 and 65 nm and different isoelectronic Sb alloy concentrations [4.139]; $S(T)$ results for bulk Bi are shown (*solid curve*) for comparison. Enhancement in the thermopower is observed in Fig. 4.29b as the wire diameter decreases and as the Sb content increases, which is attributed to the semimetal–semiconductor transition induced by quantum confinement and to Sb alloying effects in $Bi_{1-x}Sb_x$ nanowires. *Heremans* et al. have observed a substantial increase in the thermopower of Bi nanowires as the wire diameter further decreases, as shown in Fig. 4.30a for 15 nm Bi/silica and 9 nm Bi/alumina nanocomposites [4.63]. The enhancement is due to the sharp density of states near the Fermi energy in a 1-D system. Although the samples in Fig. 4.30a also possess very high electrical resistance ($\sim$ GΩ), the results for the 9 nm Bi/alumina samples show that the Seebeck coefficient can be enhanced by almost 1,000 times relative to bulk material. But for Bi nanowires with very small diameters (~ 4 nm), the localization effect becomes dominant, which compromises the thermopower enhancement. Therefore, for Bi nanowires, the optimal wire diameter range for the largest thermopower enhancement is found to be between 4 to 15 nm [4.63].

The effect of the nanowire diameter on the thermopower of nanowires has also been observed in Zn nanowires [4.63]. Figure 4.30b shows the Seebeck coefficient of 9 nm Zn/alumina and 4 nm Zn/Vycor glass nanocomposites, exhibiting enhanced thermopower as the wire diameter decreases. It is found that while 9 nm Zn nanowires still exhibit metallic behavior, the thermopower of 4 nm Zn nanowires shows a different temperature dependence, which may be due to the 1-D localization effect, although further investigation is required for a definitive identification of the conduction mechanism in such small nanowires.

Quantum Wire Superlattices

The studies on superlattice nanowires, which possess a periodic modulation in their materials composition



Fig. 4.30 **(a)** Absolute value of the Seebeck coefficient of two 15 nm Bi/silica samples, and two 9 nm Bi/alumina nanocomposite samples, in comparison to bulk Bi and 200 nm Bi nanowires in the pores of alumina templates [4.63]. The *full line* on top of the figure is a fit to a T^{-1} law. The Seebeck coefficient of the 9 nm Bi/alumina composite is positive; the rest are negative. **(b)** The Seebeck coefficient of 9 nm Zn/Al_2O_3 and 4 nm Zn/Vycor glass nanocomposite samples in comparison to bulk Zn [4.63]

along the wire axis, have attracted much attention recently because of their promise in such applications as thermoelectrics (see Sect. 4.3.2) [4.149], nanobarcodes (see Sect. 4.3.3) [4.90], nanolasers (see Sect. 4.3.3) [4.92], one-dimensional waveguides, and resonant tunneling diodes [4.93, 150]. Figure 4.31a shows a schematic structure of a superlattice nanowire consisting of interlaced quantum dots of two different materials, as denoted by A and B. Various techniques have been developed to synthesize superlattice nanowire structures with different interface conditions, as mentioned in Sect. 4.1.1 and Sect. 4.1.2.



Fig. 4.31 **(a)** Schematic diagram of superlattice (segmented) nanowires consisting of interlaced nanodots A and B of the indicated length and wire diameter. **(b)** Schematic potential profile of the subbands in the superlattice nanowire [4.149]

In this superlattice (SL) nanowire structure, the electronic transport along the wire axis is made possible by the tunneling between adjacent quantum dots, while the uniqueness of each quantum dot and its 0-D characteristic behavior is maintained by the energy difference of the conduction or valence bands between quantum dots of different materials (see Fig. 4.31b), which provides some amount of quantum confinement. Recently *Björk* et al. have observed interesting nonlinear I–V characteristics with a negative differential resistance in one-dimensional heterogeneous structures made of InAs and InP, where InP serves as the potential barrier [4.93, 150]. The nonlinear I–V behavior is associated with the double barrier resonant tunneling in one-dimensional structures, demonstrating the capability of transport phenomena in superlattice nanowires via tunneling and the possibility of controlling the electronic band structure of the SL nanowires by carefully selecting the constituent materials. This kind of new structure is especially attractive for thermoelectric ap-



Fig. 4.32 Optimal ZT calculated as a function of segment length for 10-nm diameter PbSe/PbS nanowires at 77 K, where "optimal" refers to the placement of the Fermi level to optimize ZT. The optimal ZT for 10-nm diameter PbSe, PbS, and $PbSe_{0.5}S_{0.5}$ nanowires are 0.33, 0.22, and 0.48, respectively [4.141]

plications, because the interfaces between the nanodots can reduce the lattice thermal conductivity by blocking the phonon conduction along the wire axis, while electrical conduction may be sustained and even benefit from the unusual electronic band structures due to the periodic potential perturbation. For example, Fig. 4.32 shows the calculated dimensionless thermoelectric figure of merit $ZT = S^2\sigma T/\kappa$ (see Sect. 4.2.2) where κ is the total thermal conductivity (including both the lattice and electronic contribution) of 10-nm diameter PbS/PbSe superlattice nanowires as a function of the segment length. A higher thermoelectric performance than for $PbSe_{0.5}S_{0.5}$ alloy nanowires can be achieved for a 10 nm diameter superlattice nanowire with segment lengths ≤ 7 nm. But the localization effect, which may become important for very short segment lengths, may jeopardize this enhancement in the ZT of superlattice nanowires [4.141].

Thermal Conductivity of Nanowires

Experimental measurements of the temperature dependence of the thermal conductivity $\kappa(T)$ of individual suspended nanowires have been carried out to study the dependence of $\kappa(T)$ on the wire diameter. In this context, measurements have been made on nanowires down to only 22 nm in diameter [4.151]. Such measurements are very challenging and are now possible because of technological developments in fabricating and using nanometer size thermal scanning probes [4.120, 152, 153]. The experiments show that the thermal conductivity of small homogeneous nanowires may be more than one order of magnitude smaller than in the bulk, arising mainly from strong boundary scattering effects [4.154]. Phonon confinement effects may eventually become important at still smaller diameter nanowires (see Sect. 4.2.3). Measurements on mats of nanowires (see, for example, Fig. 4.12) do not generally give reliable results because the contact thermal resistance between adjacent nanowires tends to be high, which is in part due to the thin surface oxide coating that most nanowires have. This surface oxide coating may also be important for thermal conductivity measurements on individual suspended nanowires because of the relative importance of phonon scattering at the lateral walls of the nanowire.

The most extensive experimental thermal conductivity measurements have been done on Si nanowires [4.151] where $\kappa(T)$ measurements have been made on nanowires in the diameter range of $22 \leq d_W \leq 115$ nm. The results show a large decrease in the peak of $\kappa(T)$ associated with umklapp processes as d_W decreases, indicating a growing importance of boundary scattering and a corresponding decreasing importance of phonon–phonon scattering. At the smallest wire diameter of 22 nm, a linear $\kappa(T)$ dependence is found experimentally, consistent with a linear T dependence of the specific heat for a 1-D system and a temperature independent mean free path and velocity of sound.

Model calculations for $\kappa(T)$ based on a radiative heat transfer model have been carried out for Si nanowires [4.155]. These results show that the predicted $\kappa(T)$ behavior for Si nanowires is similar to that observed experimentally in the range of $37 \leq d_W \leq 115$ nm regarding both the functional form of $\kappa(T)$ and the magnitude of the relative decrease in the maximum thermal conductivity κ_{max} as a function of d_W. But the model calculations predict a substantially larger magnitude for $\kappa(T)$ (by 50% or more) than is observed experimentally. Furthermore, the model calculations (see Fig. 4.33) do not reproduce the experimentally observed linear T dependence for the 22 nm nanowires, but rather predict a 3-D behavior for both the density of states and the specific heat in 22 nm nanowires [4.155, 156].

Thermal conductance measurements on GaAs nanowires below 6 K show a power law dependence, but the T dependence becomes somewhat less pronounced below ~ 2.5 K [4.152]. This deviation from the power law temperature dependence led to a more detailed study of the quantum limit for the thermal conductance. To carry out these more detailed experiments, a mesoscopic phonon resonator and waveguide device were



Fig. 4.33 Predicted thermal conductivity of Si nanowires of various diameters [4.155]

constructed that included four ~ 200 nm wide and 85 nm thick silicon nitride nanowire-like nano-constrictions (see Fig. 4.34a) to establish the quantized thermal conductance limit of $g_0 = \pi^2 k_B^2 T/3h$ (see Fig. 4.34b) for ballistic phonon transport [4.157, 158]. For temperatures above 0.8 K, the thermal conductance in Fig. 4.34b follows a T^3 law, but as T is further reduced, a transition to a linear T dependence is observed, consistent with a phonon mean free path of ~ 1 µm, and a thermal conductance value approaching $16g_0$, corresponding to four massless phonon modes per channel and four channels in their phonon waveguide structure (see Fig. 4.34a). Ballistic phonon transport occurs when the thermal phonon wavelength (380 nm for the experimental structure) is somewhat greater than the width of the phonon waveguide at its constriction.

4.2.3 Optical Properties

Optical methods provide an easy and sensitive tool for measuring the electronic structure of nanowires since optical measurements require minimal sample preparation (for example, contacts are not required) and the measurements are sensitive to quantum effects. Optical spectra of 1-D systems, such as carbon nanotubes, often show intense features at specific energies near singularities in the joint density of states formed under strong quantum confinement conditions. A variety of optical techniques have shown that the properties of nanowires are different from those of their bulk counterparts, and this section of the review focuses on these differences.

Although optical properties have been shown to provide an extremely important tool for the characterization of nanowires, the interpretation of these measurements is not always straightforward. The wavelength of light used to probe the sample is usually smaller than the wire length but larger than the wire diameter. Hence, the probe light used in an optical measurement cannot be focused solely onto the wire, and the wire and the substrate on which the wire rests (or host material, if the wires are embedded in a template) are simultaneously probed. For measurements, such as photo-luminescence



Fig. 4.34 **(a)** Suspended mesoscopic phonon device used to measure ballistic phonon transport. The device consists of an 4×4 µm "phonon cavity" (*center*) connected to four Si_3N_4 membranes, 60 nm thick and less than 200 nm wide. The two bright "C" shaped objects on the phonon cavity are thin film heating and sensing Cr/Au resistors, whereas the *dark regions* are empty space. **(b)** Log–log plot of the temperature dependence of the thermal conductance G_0 of the structure in **(a)** normalized to $16g_0$ (see text) [4.158]

(PL), if the substrate does not luminescence or absorb in the frequency range of the measurements, PL directly measures the luminescence of the nanowires and the substrate can be ignored. In reflection and transmission measurements, however, even a nonabsorbing substrate can modify the measured spectra of nanowires.

In this section, we discuss the determination of the dielectric function for nanowires in the context of effective medium theories. We then discuss various optical techniques with appropriate examples that sensitively differentiate nanowire properties from those also found in the parent bulk material, giving particular emphasis to electronic quantum confinement effects. Finally, we review phonon confinement effects.

The Dielectric Function

In this subsection we review the use of effective medium theory as a method to handle the optical properties of nanowires whose diameters are typically smaller than the wavelength of light, noting that observable optical properties of materials can be related to the complex dielectric function [4.159, 160]. Effective medium theories [4.161, 162] can be applied to model the nanowire and substrate as one continuous composite with a single complex dielectric function $(\epsilon_1 + \mathrm{i}\epsilon_2)$, where the real and imaginary parts of the dielectric function ϵ_1 and ϵ_2 are related to the index of refraction (n) and the absorption coefficient (K) by the relation $\epsilon_1 + \mathrm{i}\epsilon_2 = (n + \mathrm{i}K)^2$. Since photons at visible or infrared wavelengths "see" a dielectric function for the composite nanowire array/substrate system that is different from that of the nanowire itself, the optical transmission and reflection are different from what they would be if the light were focused only on the nanowire. One commonly observed consequence of effective medium theory is the shift in the plasma frequency in accordance with the percentage of nanowire material contained in the composite [4.163]. The plasma resonance occurs when $\epsilon_1(\omega)$ becomes zero, and the plasma frequency of the nanowire composite will shift to lower (higher) energies when the magnitude of the dielectric function of the host materials is larger (smaller) than that of the nanowire.

Although reflection and transmission measurements probe both the nanowire and the substrate, the optical properties of the nanowires can be independently determined. One technique for separating the dielectric function of the nanowires from the host is to use an effective medium theory in reverse. Since the dielectric function of the host material is often known, and since the dielectric function of the composite material can be measured by the standard method of using reflection and transmission measurements in combination with either the Kramer–Kronig relations or Maxwell's equations, the complex dielectric function of the nanowires can be deduced. This approach has been used successfully, for example, in determining the frequency dependence of the real and imaginary parts of the dielectric function $\epsilon_1(\omega)$ and $\epsilon_2(\omega)$ for a parallel array of bismuth nanowires filling the pores of an alumina template [4.164].

Optical Properties Characteristic of Nanowires

A wide range of optical techniques are available for the characterization of nanowires to distinguish their properties from those of their parent bulk materials. Some differences in properties are geometric, such as the small diameter size and the large length-to-diameter ratio (also called the aspect ratio), while other differences focus on quantum confinement issues.

Probably the most basic optical technique is to measure the reflection and/or transmission of a nanowire to determine the frequency-dependent real and imaginary parts of the dielectric function. This technique has been used, for example, to study the band gap and its temperature dependence in gallium nitride nanowires in the 10−50 nm range in comparison to bulk values [4.165]. The plasma frequency, free carrier density, and donor impurity concentration as a function of temperature were also determined from the infrared spectra, which is especially useful for nanowire research since Hall effect measurements cannot be made on nanowires.

Photo-luminescence (PL) or fluorescence spectroscopy is a common method to study nanowires. Emission techniques probe the nanowires directly, and the effect of the host material does not have to be considered. This characterization method has been used to study many properties of nanowires, such as the optical gap behavior, oxygen vacancies in ZnO nanowires [4.66], strain in Si nanowires [4.166], and quantum confinement effects in InP nanowires [4.92]. Figure 4.35 shows the photo-luminescence of InP nanowires as a function of wire diameter, thereby providing direct information on the effective band gap. As the wire diameter of an InP nanowire is decreased so that it becomes smaller than the bulk exciton diameter of 19 nm, quantum confinement effects set in, and the band gap is increased. This results in an increase in the PL peak energy because of the stronger electron–hole Coulomb binding energy within the quantum-confined nanowires as the wire radius gets smaller than the effective Bohr radius for the exciton for bulk InP. The smaller the effective mass, the larger the quantum con-



Fig. 4.35a–d Photo-luminescence of InP nanowires of varying diameters at 7 K ((**b**) and (**d**)) and room temperature ((**a**) and (**c**)), showing quantum confinement effects of the exciton for wire diameters less than 20 nm [4.92]

finement effects. When the shift in the peak energy as a function of nanowire diameter (Fig. 4.35a) is analyzed using an effective mass model, the reduced effective mass of the exciton is deduced to be $0.052m_0$, which agrees quite well with the literature value of $0.065m_0$ for bulk InP. Although the line widths of the PL peak for the small diameter nanowires (10 nm) are smaller at low temperature (7 K), the observation of strong quantum confinement and band gap tunability effects at room temperature are significant for photonics applications of nanowires (see Sect. 4.3.3).

The resolution of photo-luminescence (PL) optical imaging of a nanowire is, in general, limited by the wavelength of light. But when a sample is placed very close to the detector, the light is not given a chance to diffract, and so samples much smaller than the wavelength of light can be resolved. This technique is known as near-field scanning optical microscopy (NSOM) and has been used successfully [4.167] to image nanowires. For example, Fig. 4.36 shows the topographical (a) and PL (b) NSOM images of a single ZnO nanowire.

Magneto-optics can be used to measure the electronic band structure of nanowires. For example, magneto-optics in conjunction with photo-conductance has been proposed [4.168] as a tool to determine band parameters for nanowires, such as the Fermi energy, electron effective masses, and the number of subbands to be considered [4.168]. Since different nanowire subbands have different electrical transmission properties, the electrical conductivity changes when light is used to excite electrons to higher subbands, thereby providing a method for studying the electronic structure of nanowires optically. Magneto-optics can also be used to study the magnetic properties of nanowires in relation to bulk properties [4.44, 169]. For example, the surface magneto-optical Kerr effect has been used to measure



Fig. 4.36 **(a)** Topographical and **(b)** photoluminescence (PL) near-field scanning optical microscopy (NSOM) images of a single ZnO nanowire waveguide [4.167]

the dependence of the magnetic ordering temperature of Fe-Co alloy nanowires on the relative concentration of Fe and Co [4.169], and it was used to find that, unlike the case of bulk Fe-Co alloys, cobalt in nanowires inhibits magnetic ordering.

Nonlinear optical properties of nanowires have received particular attention since the nonlinear behavior is often enhanced over that in bulk materials and since the nonlinear effects can be utilized for many applications. One such study measured the second harmonic generation (SHG) and third harmonic generation (THG) in a single nanowire by using near-field optical microscopy [4.170]. ZnO nanowires were shown to have strong SHG and THG effects that are highly polarization-sensitive, and this polarization sensitivity can be explained on the basis of optical and geometrical considerations. Some components of the second harmonic polarization tensor are found to be enhanced in nanowires while others are suppressed as the wire diameter is decreased, and such effects could be of interest for device applications. The authors also showed that the second-order nonlinearities are mostly wavelength independent for $\lambda < 400\,\mathrm{nm}$, which is in the transparent regime for ZnO, below the onset of band gap absorption; this observation is also of interest for device applications.

Reflectivity and transmission measurements have also been used to study the effects of quantum confinement and surface effects on the low energy indirect transition in bismuth nanowires [4.171]. *Black* et al. [4.171] investigated an intense and sharp absorption peak in bismuth nanowires, which is not observed in bulk bismuth. The energy position E_p of this strong absorption peak increases with decreasing diameter. But the rate of increase in energy with decreasing diameter $|\partial E_p/\partial d_W|$ is an order of magnitude less than that predicted for either a direct interband transition or for intersubband transitions in bismuth nanowires. On the other hand, the magnitude of $|\partial E_p/\partial d_W|$ agrees well with that predicted for an indirect L-point valence to T-point valence band transition (see Fig. 4.37). Since both the initial and final states for the indirect L-T point valence band transition downshift in energy as the wire diameter d_W is decreased, the shift in the absorption peak results from a *difference* between the effective masses and not from the actual value of either of the masses. Hence the diameter dependence of the absorption peak energy is an order of magnitude less for a valence to valence band indirect transition than for a direct interband L-point transition. Furthermore, the band-tracking effect for the indirect transition gives rise to a large value for the joint density of states, thus accounting for the high intensity of this feature. The enhanced coupling of this indirect transition to an applied optical field arises through the gradient of the dielectric function, which is large at the bismuth-air or bismuth-alumina interfaces. It should be noted that, in contrast to the surface effect for bulk samples, the whole nanowire contributes to the optical absorption due to the spatial variation in the dielectric function, since the penetration depth is larger than or comparable to the wire diameter. In addition, the intensity can be quite significant because abundant initial state electrons, final state holes, and appropriate phonons exist for making an indirect L-T point valence band transition at room temperature. Interestingly, the polarization dependence of this absorption peak is such that the strong absorption is present when the electric field is perpendicular to the wire axis but is absent when the electric field is parallel to the wire axis; this is contrary to a traditional polarizer, such as a carbon nanotube in which the optical E field is polarized by the nanotube itself to be aligned along the carbon nanotube axis. The observed polarization dependence for bismuth nanowires is consistent



Fig. 4.37 **(a)** The measured optical transmission spectra as a function of wavenumber (1/λ) of a ∼ 45 nm diameter bismuth nanowire array. **(b)** The simulated optical transmission spectrum resulting from an indirect transition of an *L* point electron to a *T* point valence subband state. The insert in **(a)** shows the bismuth Brillouin zone, and the location of the *T*-point hole and of the three *L*-point electron pockets, including the nondegenerate A, and the doubly degenerate B pockets. The insert in **(b)** shows the indirect *L* to *T* point electronic transition induced by a photon with an energy equal to the energy difference between the initial and final states minus the phonon energy (about 100 cm^{-1}) needed to satisfy conservation of energy in a Stokes process [4.171]



Fig. 4.38 Room temperature Raman-scattering spectra of GaN nanowires and of a 5 µm thick GaN epilayer film with green (514.5 nm) laser excitation. The Raman-scattering response was obtained by dividing the measured spectra by the Bose–Einstein thermal factor [4.172]

with a surface-induced effect that increases the coupling between the L-point and T-point bands throughout the full volume of the nanowire. Figure 4.37 shows the experimentally observed transmission spectrum in bismuth nanowires of ~ 45 nm diameter (a), and for comparison, the simulated optical transmission from an indirect transition in bismuth nanowires of ~ 45 nm diameter is also shown in (b). The indirect L to T point valence band transition mechanism [4.171] is also consistent with observations of the effect on the optical spectra of a decrease in the nanowire diameter and of n-type doping of bismuth nanowires with Te.

Phonon Confinement Effects

Phonons in nanowires are spatially confined by the nanowire cross-sectional area, crystalline boundaries and surface disorder. These finite size effects give rise to phonon confinement, causing an uncertainty in the phonon wave vector, which typically gives rise to a frequency shift and a lineshape broadening. Since zone center phonons tend to correspond to maxima in the phonon dispersion curves, the inclusion of contributions from a broader range of phonon wave vectors results in both a downshift in frequency and an asymmetric broadening of the Raman line that developes a low frequency tail. These phonon confinement effects have been theoretically predicted [4.173,174] and experimentally observed in GaN [4.172], as shown in Fig. 4.38 for GaN nanowires with diameters in the range 10–50 nm. The application of these theoretical models indicates that broadening effects should be noticeable as the wire diameter in GaN nanowires decreases to ~ 20 nm. When the wire diameter further decreases to ~ 10 nm, the frequency downshift and asymmetric Raman line broadening effects should become observable in the Raman spectra for the GaN nanowires but are not found in the corresponding spectra for bulk GaN.

The experimental spectra in Fig. 4.38 show the four $A_1 + E_1 + 2E_2$ modes expected from symmetry considerations for bulk GaN crystals. Two types of quantum confinement effects are observed. The first type is the observation of the downshift and asymmetric broadening effects discussed above. Observations of such downshifts and asymmetric broadening have also been recently reported in 7 nm diameter Si nanowires [4.175]. A second type of confinement effect found in Fig. 4.38 for GaN nanowires is the appearance of additional Raman features not found in the corresponding bulk spectra and associated with combination modes and a zone boundary mode. Resonant enhancement effects were also observed for the A_1(LO) phonon at 728 cm^{-1} (see Fig. 4.38) at higher laser excitation energies [4.172].

4.3 Applications

In the preceding sections we have reviewed many of the central characteristics that make nanowires in some cases similar and in some cases very different from their parent materials. We have also shown that some properties are diameter dependent and are therefore tunable during synthesis. Thus it is of great interest to find applications for nanowires that could benefit in unprecedented ways from both the unique and tunable properties of nanowires and the small size of these nanostructures, for use in the miniaturization of conventional devices. As the synthetic methods for the production of nanowires are maturing (Sect. 4.1), and nanowires can be made in reproducible and cost-effective ways, it is only a matter of time before applications will be explored seriously. This is a timely development, as the semiconductor industry will soon be reaching what seems to be its limit in feature-size reduction and approaching a classical-to-quantum size transition. At the same time the field of biotechnology is expanding through the availability of tremendous genome information and innovative screening assays. Since nanowires are the size of the shrinking electronic components and of cellular biomolecules, it is only natural for nanowires to be good candidates for applications in these fields. Commercialization of nanowire devices, however, will require reliable mass-production, effective assembly techniques, and quality-control methods.

In this section, we discuss applications of nanowires to electronics (Sect. 4.3.1), thermoelectrics (Sect. 4.3.2), optics (Sect. 4.3.3), chemical and biological sensing (Sect. 4.3.4), and magnetic media (Sect. 4.3.5).

4.3.1 Electrical Applications

The microelectronics industry continues to face technology (e.g., lithography) and economic challenges as the device feature size is decreased, especially below 100 nm. The self-assembly of nanowires might present a way to construct unconventional devices that do not rely on improvements in photo-lithography and, therefore, do not necessarily imply increasing fabrication costs. Devices made from nanowires have several advantages over those made by photolithography. A variety of approaches has been devised to organize nanowires via self-assembly (see Sect. 4.1.4), thus eliminating the need for the expensive lithographic techniques normally required to produce devices the size of typical nanowires, which we discuss earlier (see Sect. 4.1). In addition, unlike traditional silicon processing, different semiconductors can be simultaneously used in nanowire devices to produce diverse functionalities. Not only can wires of different materials be combined, but a single wire can be made of different materials. For example, junctions of GaAs and GaP show rectifying behavior [4.92], thus demonstrating that good electronic interfaces between two different semiconductors can be achieved in the synthesis of multicomponent nanowires. Transistors made from nanowires could also have advantages because of their unique morphology. For example, in bulk field effect transistors (FETs), the depletion layer formed below the source and drain region results in a source-drain capacitance that limits the operation speed. In nanowires, however, the conductor is surrounded by an oxide and thus the depletion layer cannot be formed. Depending on the device design, the source-drain capacitance in nanowires could be greatly minimized and possibly eliminated.



Fig. 4.39a,b Optoelectrical characterization of a crossed nanowire junction formed between 65-nm n-type and 68-nm p-type InP nanowires. **(a)** Electroluminescence (EL) image of the light emitted from a forward-biased nanowire p-n junction at 2.5 V. *Inset*, photoluminescence (PL) image of the junction. **(b)** EL intensity as a function of operation voltage. *Inset*, the SEM image and the I–V characteristics of the junction [4.52]. The scale bar in the *inset* is 5 µm

Device functionalities common in conventional semiconductor technologies, such the p-n junction diodes [4.129], field-effect transistors [4.131], logic gates [4.129], and light-emitting diodes [4.52, 92], have been recently demonstrated in nanowires, showing their promise as the building blocks for the construction of complex integrated circuits by employing the "bottom-up" paradigm. Several approaches have been investigated to form nanowire diodes (see Sect. 4.2.2). For example, Schottky diodes can be formed by contacting a GaN nanowire with Al electrodes [4.130]. Furthermore, p-n junction diodes can be formed at the crossing of two nanowires, such as the crossing of n and p-type InP nanowires doped by Te and Zn, respectively [4.52], or Si nanowires doped by phosphorus (n-type) and boron (p-type) [4.176]. In addition to the crossing of two distinctive nanowires, heterogeneous junctions have also been constructed inside a single wire, either along the wire axis in the form of a nanowire superlattice [4.92] or perpendicular to the wire axis by forming a core-shell structure of silicon and germanium [4.105]. These various nanowire junctions not only possess similar current rectifying properties (see Fig. 4.22) as expected for bulk semiconductor devices, but they also exhibit electro-luminescence (EL) that may be interesting for optoelectronic applications, as shown in Fig. 4.39 for the electroluminescence of a crossed junction of n and p-type InP nanowires [4.52] (see Sect. 4.3.3).

In addition to the two-terminal nanowire devices, such as the p-n junctions described above, it is found that the conductance of a semiconductor nanowire can be significantly modified by applying voltage at a third gate terminal, implying the utilization of nanowires as a field-effect transistor (FET). This gate terminal can either be the substrate [4.46, 47], a separate metal contact located close to the nanowire [4.177], or another nanowire with a thick oxide coating in the crossed nanowire junction configuration [4.129]. We discuss the operation principles of these nanowire-based FETs in Sect. 4.2.2. Various logic devices performing basic logic functions have been demonstrated using nanowire junctions [4.129], as shown in Fig. 4.40 for the OR and AND logic gates constructed from 2-by-1 and 1-by-3 nanowire p-n junctions, respectively. By functionalizing nanowires with redox active molecules to store charges, the nanowire FETs can exhibit bi-stable logic *on* or *off* states [4.131], which may be used for nonvolatile memory or as switches.



Fig. 4.40a–d Nanowire logic gates: **(a)** Schematic of logic OR gate constructed from a 2(p-Si) by 1(n-GaN) crossed nanowire junction. The *inset* shows the SEM image (*bar:* 1 µm) of an assembled OR gate and the symbolic electronic circuit. **(b)** The output voltage of the circuit in **(a)** versus the four possible logic address level inputs: (0,0); (0,1); (1,0); (1,1), where logic 0 input is 0 V and logic 1 is 5 V (same for below). **(c)** Schematic of logic AND gate constructed from a 1(p-Si) by 3(n-GaN) crossed nanowire junction. The *inset* shows the SEM image (*bar:* 1 µm) of an assembled AND gate and the symbolic electronic circuit. **(d)** The output voltage of the circuit in **(c)** versus the four possible logic address level inputs [4.129]

Nanowires have also been proposed for applications associated with electron field emission [4.178], such as flat panel displays, because of their small diameter and large curvature at the nanowire tip, which may reduce the threshold voltage for the electron emission [4.179]. In this connection, the demonstration of very high field emission currents from the sharp tip (∼ 10 nm radius) of a Si cone [4.178] and from carbon nanotubes [4.180] stimulates interest in this potential application opportunity for nanowires.

The concept of constructing electronic devices based on nanowires has already been demonstrated, and the next step for electronic applications would be to devise a feasible method for integration and mass production. We expect that in order to maintain the growing rate of device density and functionality in the existing electronics industry, new kinds of complementary electronic devices will emerge from this "bottom-up" scheme for nanowire electronics, different from what has been produced by the traditional "top-down" approach pursued by conventional electronics.

4.3.2 Thermoelectric Applications

One proposed application for nanowires is for thermoelectric cooling and for the conversion between thermal and electrical energy [4.156, 181]. The efficiency of a thermoelectric device is measured in terms of a dimensionless figure of merit ZT, where Z is defined as

$$Z = \frac{\sigma S^2}{\kappa}, \tag{4.2}$$

in which σ is the electrical conductivity, S is the Seebeck coefficient, κ is the thermal conductivity, and T is the temperature. In order to achieve a high ZT and therefore efficient thermoelectric performance, a high electrical conductivity, a high Seebeck coefficient, and a low thermal conductivity are required. In 3-D systems, the electronic contribution to κ is proportional to σ in accordance with the Wiedemann–Franz law, and normally materials with high S have a low σ. Hence an increase in the electrical conductivity (e.g., by electron donor doping) results in an adverse variation in both the Seebeck coefficient (decreasing) and the thermal conductivity (increasing). These two trade-offs set the upper limit for increasing ZT in bulk materials, with the maximum ZT remaining at ∼ 1 at room temperature for the 1960–1995 time frame.

The high electronic density of states in quantum-confined structures is proposed as a promising possibility to bypass the Seebeck/electrical conductivity trade-off and to control each thermoelectric-related variable independently, thereby allowing for an increased electrical conductivity, a relatively low thermal



Fig. 4.41 **(a)** Calculated ZT of 1-D(nanowire) and 2-D(quantum well) bismuth systems at 77 K as a function of d_W, denoting the wire diameter or film thickness. The thermoelectric performance (i. e., ZT) is expected to improve greatly when the wire diameter is small enough so that the nanowire become a one-dimensional system. **(b)** Contour plot of optimal ZT values for p-type $Bi_{1-x}Sb_x$ nanowires vs. wire diameter and antimony concentration calculated at 77 K [4.183]

conductivity, and a large Seebeck coefficient simultaneously [4.182]. For example, Figs. 4.29b and 4.30a in Sect. 4.2.2 show an enhancement in S for bismuth an dbismuth-antimony nanowires as the wire diameter decreases. In addition to alleviating the undesired connections between σ, S, and the electronic contribution to the thermal conductivity, nanowires also have the advantage that the phonon contribution to the thermal conductivity is greatly reduced because of boundary scattering (see Sect. 4.2.2), thereby achieving a high ZT. Figure 4.41a shows the theoretical values for ZT vs. sample size for both bismuth thin films (2-D) and nanowires (1-D) in the quantum confined regime, exhibiting a rapidly increasing ZT as the quantum size effect becomes more and more important [4.182]. In addition, the quantum size effect in nanowires can be combined with other parameters to tailor the band structure and electronic transport behavior (e.g., Sb alloying in Bi) to further optimize ZT. For example, Fig. 4.41b shows the predicted ZT for p-type $Bi_{1-x}Sb_x$ alloy nanowires as a function of wire diameter and Sb content x [4.183]. The occurrence of a local ZT maxima in the vicinity of $x \sim 0.13$ and $d_W \sim 45$ nm is due to the coalesce of ten valence bands in the nanowire and the resulting unusual high density of states for holes, which is a phenomenon absent in bulk $Bi_{1-x}Sb_x$ alloys. For nanowires with very small diameters, it is speculated that localization effects will eventually limit the enhancement of ZT. But in bismuth nanowires, localization effects are not significant for wires with diameters larger than 9 nm [4.63]. In addition to 1-D nanowires, ZT values as high as ~ 2 have also been experimentally demonstrated in macroscopic samples containing PbSe quantum dots (0-D) [4.184] and stacked 2-D films [4.154].

Although the application of nanowires to thermoelectrics seems very promising, these materials are still in the research phase of the development cycle and quite far from being commercialized. One challenge for thermoelectric devices based on nanowires lies in finding a suitable host material that will not reduce ZT too much due to the unwanted heat conduction through the host material. The host material should, therefore, have a low thermal conductivity and occupy as low a volume percentage in the composite material as possible while still providing the quantum confinement and the support for the nanowires.

4.3.3 Optical Applications

Nanowires also hold promise for optical applications. One-dimensional systems exhibit a singularity in their joint density of states, allowing quantum effects in nanowires to be optically observable, sometimes, even at room temperature. Since the density of states of a nanowire in the quantum limit (small wire diameter) is highly localized in energy, the available states quickly fill up with electrons as the intensity of the incident light is increased. This filling up of the subbands, as well as other effects unique to low-dimensional materials, lead to strong optical nonlinearities in quantum wires. Quantum wires may thus yield optical switches with a lower switching energy and increased switching speed compared to currently available optical switches.

Light emission from nanowires can be achieved by photo-luminescence (PL) or electro-luminescence (EL), distinguished by whether the electronic excitation is achieved by optical illumination or by electrical stimulation across a p-n junction, respectively. PL is often used for optical properties characterization, as described in Sect. 4.2.3, but from the applications point of view, EL is a more convenient excitation method. Light emitting diodes (LEDs) have been achieved in junctions between a p-type and an n-type nanowire (Fig. 4.39) [4.52] and in superlattice nanowires with p-type and n-type segments [4.92]. The light emission was localized to the junction area and was polarized in the superlattice nanowire.

Light emission from quantum wire p-n junctions is especially interesting for laser applications, because quantum wires can form lasers with lower excitation thresholds compared to their bulk counterparts, and they also exhibit a decreased temperature sensitivity in their performance [4.185]. Furthermore, the emission wavelength can be tuned for a given material composition by only altering the geometry of the wire.

Lasing action has been reported in ZnO nanowires with wire diameters much smaller than the wavelength of the light emitted ($\lambda = 385\,\text{nm}$) [4.115] (see Fig. 4.42). Since the edge and lateral surface of ZnO nanowires are faceted (see Sect. 4.2.1), they form optical cavities that sustain desired cavity modes. Compared to conventional semiconductor lasers, the exciton laser action employed in zinc oxide nanowire lasers exhibits a lower lasing threshold ($\sim 40\,\text{kW/cm}^2$) than their 3-D counterparts ($\sim 300\,\text{kW/cm}^2$). In order to utilize exciton confinement effects in the lasing action, the exciton binding energy ($\sim 60\,\text{meV}$ in ZnO) must be greater than the thermal energy ($\sim 26\,\text{meV}$ at 300 K). Decreasing the wire diameter increases the excitation binding energy and lowers the threshold for lasing. PL NSOM imaging confirmed the waveguiding properties of the anisotropic and well-faceted structure of ZnO nanowires, limiting the emission to the tips of the ZnO nanowires [4.167].

Laser action has been also observed in GaN nanowires [4.186]. Unlike ZnO, GaN has a small exciton binding energy, of only $\sim 25\,\text{meV}$. Furthermore, since the wire radii used in this study (15–75 nm) [4.186] are larger than the Bohr radius of excitons in GaN (11 nm), the exciton binding energy is not expected to increase in these GaN wires and quantum confinement effects such as shown in Fig. 4.35 for InP are not expected. Some tunability of the center of the spectral intensity, however, was achieved by increasing the intensity of the pump power, causing a redshift in the laser emission, which is explained as a band gap renormalization as a result of the formation of an electron-hole plasma. Heating effects were excluded as the source of the spectral shift.



Fig. 4.42 A schematic of lasing in ZnO nanowires and the PL spectra of ZnO nanowires at two excitation intensities. One PL spectra is taken below the lasing threshold, and the other above it [4.115]

Nanowire photodetectors were also proposed. ZnO nanowires were found to display a strong photocurrent response to UV light irradiation [4.187]. The conductivity of the nanowire increased by four orders of magnitude compared to the dark state. The response of the nanowire was reversible and selective to photon energies above the band gap, suggesting that ZnO nanowires could be a good candidate for optoelectronic switches.

Nanowires have also been proposed for another type of optical switching. Light with its electric field normal to the wire axis excites a transverse free carrier resonance inside the wire, while light with its electric field parallel to the wire axis excites a longitudinal free carrier resonance inside the wire. Since nanowires are highly anisotropic, these two resonances occur at two different wavelengths and thus result in absorption peaks at two different energies. Gold nanowires dispersed in an aqueous solution align along the electric field when a DC voltage is applied. The energy of the absorption peak can be toggled between the transverse and longitudinal resonance energies by changing the alignment of the nanowires under polarized light illumination using an electric field [4.188, 189]. Thus, electro-optical modulation is achieved.

Nanowires may also be used as barcode tags for optical read out. Nanowires containing gold, silver, nickel, palladium, and platinum were fabricated [4.104] by electrochemical filling of porous anodic alumina, so that each nanowire consisted of segments of various metal constituents. Thus many types of nanowires can be made from a handful of materials and identified by the order of the metal segments along their main axis and the length of each segment. Barcode read out is possible by reflectance optical microscopy. The segment length is limited by the Rayleigh diffraction limit and not by synthesis limitations; thus it can be as small as 145 nm. Figure 4.43a shows an optical image of many Au-Ag-Au-Ag bar-coded wires, where the silver segments show higher reflectivity. Figure 4.43b is a backscattering mode FE-SEM image of a single nanowire, highlighting the composition and segment length variations along the nanowire.

Both the large surface area and the high conductivity along the length of nanowires are favorable for their use in inorganic-organic solar cells [4.190], which offer promise from a manufacture-ability and cost effective standpoint. In a hybrid nanocrystal-organic solar cell, the incident light forms bound electron–hole pairs (excitons) in both the inorganic nanocrystal and in the surrounding organic medium. These excitons diffuse to the inorganic–organic interface and disassociate to form an electron and a hole. Since conjugated polymers usually have poor electron mobilities, the inorganic phase is chosen to have a higher electron affinity than the organic phase so that the organic phase carries the holes and the semiconductor carries the electrons. The separated electrons and holes drift to the external electrodes through the inorganic and organic materials, respectively. But only those excitons formed within an exciton diffusion length from an interface can disassociate before recombining, and therefore the distance between the dissociation sites limits the efficiency of a solar cell. A solar cell prepared from a composite of CdSe nanorods inside poly (3-ethylthiophene) [4.190] yielded 6.9% monochromatic power efficiencies and 1.7% power conversion efficiencies under A.M. 1.5 illumination (equal to solar irradiance through 1.5 times the air mass of the earth at direct normal incidence). The nanorods provide a large surface area with good chemical bonding to the polymer for efficient charge transfer and exciton dissociation. Furthermore, they provide a good conduction path for the electrons to reach the electrode. Their enhanced absorption coefficient and their tunable band gap are also characteristics that can be used to enhance the energy conversion efficiency of solar cells.



Fig. 4.43 **(a)** An optical image of many short Au-Ag-Au-Au bar-coded wires and **(b)** an FE-SEM image of an Au/Ag bar-coded wire with multiple strips of varying length. The insert in **(a)** shows a histogram of the particle lengths for 106 particles in this image [4.104]

4.3.4 Chemical and Biochemical Sensing Devices

Sensors for chemical and biochemical substances with nanowires as the sensing probe are a very attractive application area. Nanowire sensors will potentially be smaller, more sensitive, demand less power, and react faster than their macroscopic counterparts. Arrays of nanowire sensors could, in principle, achieve nanometer scale spatial resolution and therefore provide accurate real-time information regarding not only the concentration of a specific analyte but also its spatial distribution. Such arrays, for example, could be very useful for dynamic studies on the effects of chemical gradients on biological cells. The operation of sensors made with nanowires, nanotubes, or nano-contacts is based mostly on the reversible change in the conductance of the nanostructure upon absorption of the agent to be detected, but other detection methods, such as mechanical and optical detection, are conceptually plausible. The increased sensitivity and faster response time of nanowires are a result of the large surface-to-volume ratio and the small cross-section available for conduction channels. In the bulk, on the other hand, the abundance of charges can effectively shield external fields, and the abundance of material can afford many alternative conduction channels. Therefore a stronger chemical stimulus and longer response time are necessary to observe changes in the physical properties of a 3-D sensor in comparison to a nanowire.

Cui et al. placed silicon nanowires made by the VLS method (Sect. 4.1.2) between two metal electrodes and modified the silicon oxide coating of the wire by the addition of molecules sensitive to the analyte to be detected [4.191]. For example, a pH sensor was made by covalently linking an amine containing silane to the surface of the nanowire. Variations in the pH of the solution into which the nanowire was immersed caused protonation and deprotonation of the $-NH_2$ and the $-SiOH$ groups on the surface of the nanowire. The variation in surface charge densities regulates the conductance of the nanowire; due to the p-type characteristics of a silicon wire, the conductance increases with the addition of negative surface charge. The combined acid and base behavior of the surface groups results in an approximately linear dependence of the conductance on pH in the pH range 2 to 9, thus leading to a direct readout pH meter. This same type of approach was used for the detection of the binding of biomolecules, such as streptavidin using biotin-modified nanowires (see Fig. 4.44). This nanowire-based device has high sensitivity and could detect streptavidin binding down to a 10 pM (10^{-12} mole) concentration. The chemical detection devices were made in a field-effect transistor geometry, so that the back-gate potential could be used to regulate the conductance in conjugation with the chemical detection and to provide a real time direct read out [4.191]. The extension of this device to detect multiple analytes, using multiple nanowires each sensitized to a different analyte, could provide for fast, sensitive and in-situ screening procedures.

Favier et al. used a similar approach, making a nanosensor for the detection of hydrogen out of an array of palladium nanowires between two metal contacts [4.56]. They demonstrated that nanogaps were present in their nanowire structure, and upon absorption of H_2 and formation of Pd hydride, the nanogap structure would close and improve the electrical contact, thereby increasing the conductance of the nanowire array. The response time of these sensors was 75 msec, and they could operate in the range of 0.5 to 5% H_2 before saturation occurred.



Fig. 4.44 **(a)** Streptavidin molecules bind to a silicon nanowire functionalized with biotin. The binding of streptavidin to biotin causes the nanowire to change its resistance. **(b)** The conductance of a biotin-modified silicon nanowire exposed to streptavidin in a buffer solution (regions 1 and 3) and with the introduction of a solution of antibiotin monoclonal antibody (region 2) [4.191]

4.3.5 Magnetic Applications

It has been demonstrated that arrays of single domain magnetic nanowires can be prepared with controlled nanowire diameter and length, aligned along a common direction and arranged in a close-packed ordered array (see Sect. 4.1.1), and that the magnetic properties (coercivity, remanence, and dipolar magnetic interwire interaction) can be controlled to achieve a variety of magnetic applications [4.54, 71].

Magnetic information storage is the most interesting of these applications. The large nanowire aspect ratio (length/diameter) prevents the onset of the "superparamagnetic" limit at which the magnetization direction in the magnetic grains can be reversed by the thermal energy $k_B T$, thereby resulting in loss of recorded data in the magnetic recording medium. The magnetic energy in a grain can be increased by increasing either the volume or the anisotropy of the grain. If the volume is increased, the particle size increases, and thus, the resolution is decreased. For spherical magnetized grains, the superparamagnetic limit at room temperature is reached at 70 Gbit/in^2. In nanowires, the anisotropy is very large and yet the wire diameters are small, so the magnetostatic switching energy can easily be above the thermal energy while the spatial resolution is large. For magnetic data storage applications, a large aspect ratio is needed for the nanowires to maintain a high coercivity, and a sufficient separation between nanowires is needed to suppress inter-wire magnetic dipolar coupling (see Sect. 4.2.1). Thus nanowires can form stable and highly dense magnetic memory arrays with packing densities in excess of 10^{11} wires/cm^2.

The onset of superparamagnetism can be prevented in the single domain magnetic nanowire arrays that have already been fabricated either using porous alumina templates to make Ni nanowires with 35 nm diameters [4.54] or diblock copolymer templates [4.71] to make Co nanowires, with mean diameters of 14 nm and 100% filling of the template pores (see Sect. 4.1.1). Ordered magnetic nanowire arrays that have already been demonstrated offer the exciting promise for achieving systems permitting 10^{12} bits/in^2 data storage.

4.4 Concluding Remarks

A review has been presented of synthesis, characterization, and physical properties of nanowires, with particular reference to nanowire properties that differ from those of their bulk counterparts and to potential applications that might result from the special structure and properties of nanowires. We have shown in this chapter that the emerging field of nanowire research has developed rapidly over the past few years, driven by the development of a variety of complementary nanowire synthesis methods and of effective tools to measure both their structure and properties, as reviewed, respectively, in Sect. 4.1 and Sect. 4.2. At present, much of the progress is at the demonstration-of-concept level, with many gaps in knowledge remaining to be elucidated, theoretical models to be developed, and new nanowire systems to be explored. Having demonstrated that many of the most interesting discoveries to date relate to nanowire properties not present in their bulk material counterparts, we can expect future research emphasis to be focused increasingly on smaller diameter nanowires, where new unexplored physical phenomena related to quantum confinement effects are more likely to be found. We can also expect the development of applications to soon follow. Many promising applications are now at the early demonstration stage (see Sect. 4.3), but are moving ahead rapidly because of their promise for new functionality, not previously available, to the fields of electronics, opto-electronics, biotechnology, magnetics, and energy conversion and generation, among others. Many exciting challenges remain in advancing both the nanoscience and the nano-technological promise already demonstrated by the nanowire research described in this review.

References

4.1 R. P. Feynman: There's plenty of room at the bottom, Eng. Sci. (February 1960) 22

4.2 M. S. Dresselhaus, Y.-M. Lin, O. Rabin, A. Jorio, A. G. Souza Filho, M. A. Pimenta, R. Saito, G. G. Samsonidze, G. Dresselhaus: Nanowires and nanotubes, Mater. Sci. & Eng. C **1008** (2002) 1–12

4.3 R. Saito, G. Dresselhaus, M. S. Dresselhaus: *Physical Properties of Carbon Nanotubes* (Imperial College Press, London 1998)

4.4 M. S. Dresselhaus, G. Dresselhaus, P. Avouris (Eds.): *Carbon Nanotubes: Synthesis Structure, Properties and Applications* (Springer, Berlin, Heidelberg 2001)

4.5 R. C. Haddon: Special issue on carbon nanotubes, Accounts Chem. Res. **35** (2002) 997–1113

4.6 Y.-M. Lin, X. Sun, S. Cronin, Z. Zhang, J. Y. Ying, M. S. Dresselhaus: Fabrication and transport properties of Te-doped bismuth nanowire arrays, Molecular Electronics: MRS Symp. Proc., Boston 1999, ed. by S. T. Pantelides, M. A. Reed, J. Murday, A. Aviran (Materials Research Society Press, Pittsburgh 2000) **582** H10.3 (1–6)

4.7 C. R. Martin: Nanomaterials: A membrane-based synthetic approach, Science **266** (1994) 1961–1966

4.8 G. A. Ozin: Nanochemistry: synthesis in diminishing dimensions, Adv. Mater. **4** (1992) 612–649

4.9 R. J. Tonucci, B. L. Justus, A. J. Campillo, C. E. Ford: Nanochannel array glass, Science **258** (1992) 783–785

4.10 J. Y. Ying: Nanoporous systems and templates, Sci. Spectra **18** (1999) 56–63

4.11 J. W. Diggle, T. C. Downie, C. W. Goulding: Anodic oxide films on aluminum, Chem. Rev. **69** (1969) 365–405

4.12 J. P. O'Sullivan, G. C. Wood: The morphology and mechanism of formation of porous anodic films on aluminum, Proc. Roy. Soc. London A **317** (1970) 511–543

4.13 A. P. Li, F. Müller, A. Birner, K. Neilsch, U. Gösele: Hexagonal pore arrays with a 50 – 420 nm interpore distance formed by self-organization in anodic alumina, J. Appl. Phys. **84** (1998) 6023–6026

4.14 O. Jessensky, F. Müller, U. H. Gösele: Self-organized formation of hexagonal pore arrays in anaodic alumina, Appl. Phys. Lett. **72** (1998) 1173–1175

4.15 D. AlMawlawi, N. Coombs, M. Moskovits: Magnetic-properties of Fe deposited into anodic aluminum-oxide pores as a function of particle-size, J. Appl. Phys. **70** (1991) 4421–4425

4.16 Z. Zhang, D. Gekhtman, M. S. Dresselhaus, J. Y. Ying: Processing and characterization of single-crystalline ultrafine bismuth nanowires, Chem. Mater. **11** (1999) 1659–1665

4.17 F. Li, L. Zhang, R. M. Metzger: On the growth of highly ordered pores in anodized aluminum oxide, Chem. Mater. **10** (1998) 2470–2480

4.18 H. Masuda, M. Satoh: Fabrication of gold nanodot array using anodic porous alumina as an evaporation mask, Jpn. J. Appl. Phys. **35** (1996) L126–L129

4.19 E. Ferain, R. Legras: Track-etched membrane – dynamics of pore formation, Nucl. Instrum. Methods B **84** (1993) 331–336

4.20 A. Blondel, J. P. Meier, B. Doudin, J.-P. Ansermet: Giant magnetoresistance of nanowires of multilayers, Appl. Phys. Lett. **65** (1994) 3019–3021

4.21 K. Liu, C. L. Chien, P. C. Searson, Y. Z. Kui: Structural and magneto-transport properties of electrodeposited bismuth nanowires, Appl. Phys. Lett. **73** (1998) 1436–1438

4.22 L. Sun, P. C. Searson, C. L. Chien: Electrochemical deposition of nickel nanowire arrays in single-crystal mica films, Appl. Phys. Lett. **74** (1999) 2803–2805

4.23 E. Braun, Y. Eichen, U. Sivan, G. Ben-Yoseph: DNA-templated assembly and electrode attachment of a conducting silver wire, Nature **391** (1998) 775–778

4.24 G. Sauer, G. Brehm, S. Schneider, K. Nielsch, R. B. Wehrspohn, J. Choi, H. Hofmeister, U. Gösele: Highly ordered monocrystalline silver nanowire arrays, J. Appl. Phys. **91** (2002) 3243–3247

4.25 G. L. Hornyak, C. J. Patrissi, C. M. Martin: Fabrication, characterization, and optical properties of gold nanoparticle/porous alumina composites: the non-scattering Maxwell-Garnett limit, J. Phys. Chem. B **101** (1997) 1548–1555

4.26 X. Y. Zhang, L. D. Zhang, Y. Lei, L. X. Zhao, Y. Q. Mao: Fabrication and characterization of highly ordered Au nanowire arrays, J. Mater. Chem. **11** (2001) 1732–1734

4.27 Y.-T. Cheng, A. M. Weiner, C. A. Wong, M. P. Balogh, M. J. Lukitsch: Stress-induced growth of bismuth nanowires, Appl. Phys. Lett. **81** (2002) 3248–3250

4.28 J. Heremans, C. M. Thrush, Y.-M. Lin, S. Cronin, Z. Zhang, M. S. Dresselhaus, J. F. Mansfield: Bismuth nanowire arrays: synthesis and galvanomagnetic properties, Phys. Rev. B **61** (2000) 2921–2930

4.29 L. Piraux, S. Dubois, J. L. Duvail, A. Radulescu, S. Demoustier-Champagne, E. Ferain, R. Legras: Fabrication and properties of organic and metal nanocylinders in nanoporous membranes, J. Mater. Res. **14** (1999) 3042–3050

4.30 K. Hong, F. Y. Yang, K. Liu, D. H. Reich, P. C. Searson, C. L. Chien, F. F. Balakirev, G. S. Boebinger: Giant positive magnetoresistance of Bi nanowire arrays in high magnetic fields, J. Appl. Phys. **85** (1999) 6184–6186

4.31 A. J. Yin, J. Li, W. Jian, A. J. Bennett, J. M. Xu: Fabrication of highly ordered metallic nanowire arrays by electrodeposition, Appl. Phys. Lett. **79** (2001) 1039–1041

4.32 Z. Zhang, J. Y. Ying, M. S. Dresselhaus: Bismuth quantum-wire arrays fabricated by a vacuum melting and pressure injection process, J. Mater. Res. **13** (1998) 1745–1748

4.33 T. E. Huber, M. J. Graf, C. A. Foss Jr., P. Constant: Processing and characterization of high-conductance bismuth wire array composites, J. Mater. Res. **15** (2000) 1816–1821

4.34 M. S. Sander, A. L. Prieto, R. Gronsky, T. Sands, A. M. Stacy: Fabrication of high-density, high aspect ratio, large-area bismuth telluride nanowire arrays by electrodeposition into porous anodic alumina templates, Adv. Mater. **14** (2002) 665–667

4.35 M. Chen, Y. Xie, J. Lu, Y. J. Xiong, S. Y. Zhang, Y. T. Qian, X. M. Liu: Synthesis of rod-, twinrod-, and tetrapod-shaped CdS nanocrystals using a highly oriented solvothermal recrystallization technique, J. Mat. Chem. **12** (2002) 748–753

4.36 D. Xu, Y. Xu, D. Chen, G. Guo, L. Gui, Y. Tang: Preparation of CdS single-crystal nanowires by electrochemically induced deposition, Adv. Mater. **12** (2000) 520–522

4.37 D. Routkevitch, T. Bigioni, M. Moskovits, J. M. Xu: Electrochemical fabrication of CdS nanowire arrays in porous anodic aluminum oxide templates, J. Phys. Chem. **100** (1996) 14037–14047

4.38 L. Manna, E. C. Scher, A. P. Alivisatos: Synthesis of soluble and processable rod-, arrow-, teardrop-, and tetrapod-shaped CdSe nanocrystals, J. Am. Chem. Soc. **122** (2000) 12700–12706

4.39 D. Routkevitch, A. A. Tager, J. Haruyama, D. Al-Mawlawi, M. Moskovits, J. M. Xu: Nonlithographic nano-wire arrays: fabrication, physics, and device applications, IEEE Trans. Electron. Dev. **43** (1996) 1646–1658

4.40 D. S. Xu, D. P. Chen, Y. J. Xu, X. S. Shi, G. L. Guo, L. L. Gui, Y. Q. Tang: Preparation of II-VI group semiconductor nanowire arrays by dc electrochemical deposition in porous aluminum oxide templates, Pure Appl. Chem. **72** (2000) 127–135

4.41 R. Adelung, F. Ernst, A. Scott, M. Tabib-Azar, L. Kipp, M. Skibowski, S. Hollensteiner, E. Spiecker, W. Jäger, S. Gunst, A. Klein, W. Jägermann, V. Zaporojtchenko, F. Faupel: Self-assembled nanowire networks by deposition of copper onto layered-crystal surfaces, Adv. Mater. **14** (2002) 1056–1061

4.42 T. Gao, G. W. Meng, J. Zhang, Y. W. Wang, C. H. Liang, J. C. Fan, L. D. Zhang: Template synthesis of single-crystal Cu nanowire arrays by electrodeposition, Appl. Phys. A **73** (2001) 251–254

4.43 F. Li, R. M. Metzger: Activation volume of α-Fe particles in alumite films, J. Appl. Phys. **81** (1997) 3806–3808

4.44 A. Sugawara, T. Coyle, G. G. Hembree, M. R. Scheinfein: Self-organized Fe nanowire arrays prepared by shadow deposition on NaCl(110) templates, Appl. Phys. Lett. **70** (1997) 1043–1045

4.45 G. S. Cheng, L. D. Zhang, Y. Zhu, G. T. Fei, L. Li, C. M. Mo, Y. Q. Mao: Large-scale synthesis of single crystalline gallium nitride nanowires, Appl. Phys. Lett. **75** (1999) 2455–2457

4.46 Y. Huang, X. Duan, Y. Cui, C. M. Lieber: Gallium nitride nanowire nanodevices, Nano. Lett. **2** (2002) 101–104

4.47 Y. Cui, X. Duan, J. Hu, C. M. Lieber: Doping and electrical transport in silicon nanowires, J. Phys. Chem. B **104** (2000) 5213–5216

4.48 A. D. Berry, R. J. Tonucci, M. Fatemi: Fabrication of GaAs and InAs wires in nanochannel glass, Appl. Phys. Lett. **69** (1996) 2846–2848

4.49 J. R. Heath, F. K. LeGoues: A liquid solution synthesis of single-crystal germanium quantum wires, Chem. Phys. Lett. **208** (1993) 263–268

4.50 Y. Wu, P. Yang: Germanium nanowire growth via simple vapor transport, Chem. Mater. **12** (2000) 605–607

4.51 Y. F. Zhang, Y. H. Tang, N. Wang, C. S. Lee, I. Bello, S. T. Lee: Germanium nanowires sheathed with an oxide layer, Phys. Rev. B **61** (2000) 4518–4521

4.52 X. Duan, Y. Huang, Y. Cui, J. Wang, C. M. Lieber: Indium phosphide nanowires as building blocks for nanoscale electronic and optoelectronic devices, Nature **409** (2001) 66–69

4.53 M. P. Zach, K. H. Ng, R. M. Penner: Molybdenum nanowires by electrodeposition, Science **290** (2000) 2120–2123

4.54 K. Nielsch, R. Wehrspohn, S. F. H. Kronmuller, J. Barthel, J. Kirschner, U. Gosele: Magnetic properties of 100 nm nickel nanowire arrays obtained from ordered porous alumina templates, MRS Symp. Proc. **636** (2001) D19 (1–6)

4.55 E. Lifshitz, M. Bashouti, V. Kloper, A. Kigel, M. S. Eisen, S. Berger: Synthesis and characterization of PbSe quantum wires, multipods, quantum rods, and cubes, Nano. Lett. **3** (2003) 857–862

4.56 F. Favier, E. C. Walter, M. P. Zach, T. Benter, R. M. Penner: Hydrogen sensors and switches from electrodeposited palladium mesowire arrays, Science **293** (2001) 2227–2231

4.57 B. Gates, B. Mayers, B. Cattle, Y. Xia: Synthesis and characterization of uniform nanowires of trigonal selenium, Adv. Funct. Mat. **12** (2002) 219–227

4.58 C. A. Huber, T. E. Huber, M. Sadoqi, J. A. Lubin, S. Manalis, C. B. Prater: Nanowire array composites, Science **263** (1994) 800–802

4.59 Y. Cui, L. J. Lauhon, M. S. Gudiksen, J. Wang, C. M. Lieber: Diameter-controlled synthesis of single crystal silicon nanowires, Appl. Phys. Lett. **78** (2001) 2214–2216

4.60 A. M. Morales, C. M. Lieber: A laser ablation method for the synthesis of crystalline semiconductor nanowires, Science **279** (1998) 208–211

4.61 N. Wang, Y. F. Zhang, Y. H. Tang, C. S. Lee, S. T. Lee: SiO_2-enhanced synthesis of Si nanowires by laser ablation, Appl. Phys. Lett. **73** (1998) 3902–3904

4.62 M. K. Sunkara, S. Sharma, R. Miranda, G. Lian, E. C. Dickey: Bulk synthesis of silicon nanowires using a low-temperature vapor-liquid-solid method, Appl. Phys. Lett. **79** (2001) 1546–1548

4.63 J. P. Heremans, C. M. Thrush, D. T. Morelli, M.-C. Wu: Thermoelectric power of bismuth nanocomposites, Phys. Rev. Lett. **88** (2002) 216801(1–4)

4.64 Y. Li, G. S. Cheng, L. D. Zhang: Fabrication of highly ordered ZnO nanowire arrays in anodic alumina membranes, J. Mater. Res. **15** (2000) 2305–2308

4.65 P. Yang, H. Yan, S. Mao, R. Russo, J. Johnson, R. Saykally, N. Morris, J. Pham, R. He, H.-J. Choi: Controlled growth of ZnO nanowires and their optical properties, Adv. Func. Mat. **12** (2002) 323–331

4.66 M. J. Zheng, L. D. Zhang, G. H. Li, W. Z. Chen: Fabrication and optical properties of large-scale uniform zinc oxide nanowire arrays by one-step electrochemical deposition technique, Chem. Phys. Lett. **363** (2002) 123–128

4.67 Y.-M. Lin, S. B. Cronin, J. Y. Ying, M. S. Dresselhaus, J. P. Heremans: Transport properties of Bi nanowire arrays, Appl. Phys. Lett. **76** (2000) 3944–3946

4.68 C. A. Huber, T. E. Huber: A novel microstructure: semiconductor-impregnated porous Vycor glass, J. Appl. Phys. **64** (1988) 6588–6590

4.69 J. S. Beck, J. C. Vartuli, W. J. Roth, M. E. Leonowicz, C. T. Kresge, K. D. Schmitt, C. T.-W. Chu, D. H. Olson, E. W. Sheppard, S. B. McCullen, J. B. Higgins, J. L. Schlenker: A new family of mesoporous molecular sieves prepared with liquid crystal templates, J. Am. Chem. Soc. **114** (1992) 10834–10843

4.70 C.-G. Wu, T. Bein: Conducting polyaniline filaments in a mesoporous channel host, Science **264** (1994) 1757–1759

4.71 T. Thurn-Albrecht, J. Schotter, G. A. Kästle, N. Emley, T. Shibauchi, L. Krusin-Elbaum, K. Guarini, C. T. Black, M. T. Tuominen, T. P. Russell: Ultrahigh-density nanowire arrays grown in self-assembled diblock copolymer templates, Science **290** (2000) 2126–2129

4.72 A. W. Adamson: *Physical Chemistry of Surfaces* (Wiley, New York 1982) p. 338

4.73 R. Ferré, K. Ounadjela, J. M. George, L. Piraux, S. Dubois: Magnetization processes in nickel and cobalt electrodeposited nanowires, Phys. Rev. B **56** (1997) 14066–14075

4.74 H. Zeng, M. Zheng, R. Skomski, D. J. Sellmyer, Y. Liu, L. Menon, S. Bandyopadhyay: Magnetic properties of self-assembled Co nanowires of varying length and diameter, J. Appl. Phys. **87** (2000) 4718–4720

4.75 Y. Peng, H.-L. Zhang, S.-L. Pan, H.-L. Li: Magnetic properties and magnetization reversal of α-Fe nanowires deposited on alumina film, J. Appl. Phys. **87** (2000) 7405–7408

4.76 L. Piraux, J. M. George, J. F. Despres, C. Leroy, E. Ferain, R. Legras, K. Ounadjela, A. Fert: Giant magnetoresistance in magnetic multilayered nanowires, Appl. Phys. Lett. **65** (1994) 2484–2486

4.77 S. Bhattacharrya, S. K. Saha, D. Chakravorty: Nanowire formation in a polymeric film, Appl. Phys. Lett. **76** (2000) 3896–3898

4.78 G. Yi, W. Schwarzacher: Single crystal superconductor nanowires by electrodeposition, Appl. Phys. Lett. **74** (1999) 1746–1748

4.79 D. AlMawlawi, C. Z. Liu, M. Moskovits: Nanowires formed in anodic oxide nanotemplates, J. Mater. Res. **9** (1994) 1014–1018

4.80 G. S. Cheng, L. D. Zhang, S. H. Chen, Y. Li, L. Li, X. G. Zhu, Y. Zhu, G. T. Fei, Y. Q. Mao: Ordered nanostructure of single-crystalline GaN nanowires in a honeycomb structure of anodic alumina, J. Mater. Res. **15** (2000) 347–350

4.81 D. N. Davydov, P. A. Sattari, D. AlMawlawi, A. Osika, T. L. Haslett, M. Moskovits: Field emitters based on porous aluminum oxide templates, J. Appl. Phys. **86** (1999) 3983–3987

4.82 J. Li, C. Papadopoulos, J. M. Xu, M. Moskovits: Highly-ordered carbon nanotube arrays for electronic applications, Appl. Phys. Lett. **75** (1999) 367–369

4.83 T. Iwasaki, T. Motoi, T. Den: Multiwalled carbon nanotubes growth in anodic alumina nanoholes, Appl. Phys. Lett. **75** (1999) 2044–2046

4.84 J. S. Suh, J. S. Lee: Highly ordered two-dimensional carbon nanotube arrays, Appl. Phys. Lett. **75** (1999) 2047–2049

4.85 Z. M. Li, Z. K. Tang, H. J. Liu, N. Wang, C. T. Chan, R. Saito, S. Okada, G. D. Li, J. S. Chen, N. Nagasawa, S. Tsuda: Polarized absorption spectra of single-walled 4 Å carbon nanotubes aligned in channels of an $AlPO_4$-5 single crystal, Phys. Rev. Lett. **87** (2001) 127401 (1–4)

4.86 J. Sloan, A. I. Kirkland, J. L. Hutchison, M. L. H. Green: Structural characterization of atomically regulated nanocrystals formed within single-walled carbon nanotubes using electron microscopy, Acc. Chem. Res. **35** (2002) 1054–1062

4.87 R. S. Wagner, W. C. Ellis: Vapor-liquid-solid mechanism of single crystal growth, Appl. Phys. Lett. **4** (1964) 89–90

4.88 Y. Wu, P. Yang: Direct observation of vapor-liquid-solid nanowire growth, J. Am. Chem. Soc. **123** (2001) 3165–3166

4.89 S. Sharma, M. K. Sunkara, R. Miranda, G. Lian, E. C. Dickey: A novel low temperature synthesis method for semiconductor nanowires Synthesis, Functional Properties and Applications of Nanostructures: Mat. Res. Soc. Symp. Proc., San Francisco 2001, ed. by H. W. Hahn, D. L. Feldheim, C. P. Kubiak, R. Tannenbaum, R. W. Siegel (Materials Research Society Press, Pittsburgh 2001) **676** Y1.6

4.90 Y. Wu, R. Fan, P. Yang: Block-by-block growth of single-crystalline Si/SiGe superlattice nanowires, Nano. Lett. **2** (2002) 83–86

4.91 N. Wang, Y. H. Tang, Y. F. Zhang, C. S. Lee, S. T. Lee: Nucleation and growth of Si nanowires from silicon oxide, Phys. Rev. B **58** (1998) R16024–R16026

4.92 M. S. Gudiksen, L. J. Lauhon, J. Wang, D. C. Smith, C. M. Lieber: Growth of nanowire superlattice structures for nanoscale photonics and electronics, Nature **415** (2002) 617–620

4.93 M. T. Björk, B. J. Ohlsson, T. Sass, A. I. Persson, C. Thelander, M. H. Magnusson, K. Deppert, L. R. Wallenberg, L. Samuelson: One-dimensional steeplechase for electrons realized, Nano. Lett. **2** (2002) 87–89

4.94 Y. F. Zhang, Y. H. Tang, N. Wang, C. S. Lee, I. Bello, S. T. Lee: One-dimensional growth mechanism of crystalline silicon nanowires, J. Cryst. Growth **197** (1999) 136–140

4.95 S. T. Lee, Y. F. Zhang, N. Wang, Y. H. Tang, I. Bello, C. S. Lee, Y. W. Chung: Semiconductor nanowires from oxides, J. Mater. Res. **14** (1999) 4503–4507

4.96 D. D. D. Ma, C. S. Lee, Y. Lifshitz, S. T. Lee: Periodic array of intramolecular junctions of silicon nanowires, Appl. Phys. Lett. **81** (2002) 3233–3235

4.97 B. Gates, Y. Yin, Y. Xia: A solution-phase approach to the synthesis of uniform nanowires of crystalline selenium with lateral dimensions in the range of 10–30 nm, J. Am. Chem. Soc. **122** (2000) 12582–12583

4.98 B. Mayers, B. Gates, Y. Yin, Y. Xia: Large-scale synthesis of monodisperse nanorods of Se/Te alloys through a homogeneous nucleation and solution growth process, Adv. Mat. **13** (2001) 1380–1384

4.99 B. Gates, Y. Wu, Y. Yin, P. Yang, Y. Xia: Single-crystalline nanowires of Ag_2Se can be synthesized by templating against nanowires of trigonal Se. J. Am. Chem. Soc., **123** (2001) 11500–11501

4.100 B. Gates, B. Mayers, Y. Wu, Y. Sun, B. Cattle, P. Yang, Y. Xia: Synthesis and characterization of crystalline Ag_2Se nanowires through a template-engaged reaction at room temperature, Adv. Funct. Mat. **12** (2002) 679–686

4.101 X. Peng, J. Wickham, A. P. Alivisatos: Kinetics of II-VI and III-V colloidal semiconductor nanocrystal growth: 'focusing' of size distributions, J. Am. Chem. Soc. **120** (1998) 5343–5344

4.102 M. P. Zach, K. Inazu, K. H. Ng, J. C. Hemminger, R. M. Penner: Synthesis of molybdenum nanowires with millimeter-scale lengths using electrochemical step edge decoration, Chem. Mater. **14** (2002) 3206–3216

4.103 N. A. Melosh, A. Boukai, F. Diana, B. Gerardot, A. Badolato, P. M. Petroff, J. R. Heath: Ultrahigh-density nanowire lattices and circuits, Science **300** (2003) 112–115

4.104 S. R. Nicewarner-Peña, R. G. Freeman, B. D. Reis, L. He, D. J. Peña, I. D. Walton, R. Cromer, C. D. Keating, M. J. Natan: Submicrometer metallic barcodes, Science **294** (2001) 137–141

4.105 L. J. Lauhon, M. S. Gudiksen, D. Wang, C. M. Lieber: Epitaxial core-shell and core-multishell nanowire heterostructures, Nature **420** (2002) 57–61

4.106 Z. L. Wang, Z. R. Dai, R. P. Gao, Z. G. Bai, J. L. Gole: Side-by-side silicon carbide-silica biaxial nanowires: Synthesis, structure, and mechanical properties, Appl. Phys. Lett. **77** (2000) 3349–3351

4.107 J. Y. Lao, J. G. Wen, Z. F. Ren: Hierarchical ZnO nanostructures, Nano. Lett. **2** (2002) 1287–1291

4.108 J. Y. Lao, J. Y. Huang, D. Z. Wang, Z. F. Ren: ZnO nanobridges and nanonails, Nano. Lett. **3** (2003) 235–238

4.109 P. Yang, F. Kim: Langmuir–Blodgett assembly of one-dimensional nanostructures, CHEMPHYSCHEM **3** (2002) 503–506

4.110 B. Messer, J. H. Song, P. Yang: Microchannel networks for nanowire patterning, J. Am. Chem. Soc. **122** (2000) 10232–10233

4.111 P. A. Smith, C. D. Nordquist, T. N. Jackson, T. S. Mayer, B. R. Martin, J. Mbindyo, T. E. Mallouk: Electric-field assisted assembly and alignment of metallic nanowires, Appl. Phys. Lett. **77** (2000) 1399–1401

4.112 H. Masuda, H. Yamada, M. Satoh, H. Asoh, M. Nakao, T. Tamamura: Highly ordered nanochannel-array architecture in anodic alumina, Appl. Phys. Lett. **71** (1997) 2770–2772

4.113 O. Rabin, P. R. Herz, S. B. Cronin, Y.-M. Lin, A. I. Akinwande, M. S. Dresselhaus: Nanofabrication using self-assembled alumina templates, Nonlithographic and Lithographic Methods for Nanofabrication: MRS Symposium Proceedings, Boston 2000, ed. by J. A. Rogers, A. Karim, L. Merhari, D. Norris, Y. Xia (Materials Research Society Press, Pittsburgh 2001) **636** D4.7 (1–6)

4.114 A. Rabin, P. R. Herz, Y.-M. Lin, A. I. Akinwande, S. B. Cronin, M. S. Dresselhaus: Formation of thick porous anodic alumina films and nanowire arrays on silicon wafers and glass, Adv. Funct. Mater. **13** (2003) 631–638

4.115 M. H. Huang, S. Mao, H. Feick, H. Yan, Y. Wu, H. Kind, E. Weber, R. Russo, P. Yang: Room-temperature ultraviolet nanowire nanolasers, Science **292** (2001) 1897–1899

4.116 Y. H. Tang, Y. F. Zhang, N. Wang, C. S. Lee, X. D. Han, I. Bello, S. T. Lee: Morphology of Si nanowires synthesized by high-temperature laser ablation, J. Appl. Phys. **85** (1999) 7981–7983

4.117 S. B. Cronin, Y.-M. Lin, O. Rabin, M. R. Black, G. Dresselhaus, M. S. Dresselhaus, P. L. Gai: Bismuth nanowires for potential applications in nanoscale electronics technology, Microsc. Microanal. **8** (2002) 58–63

4.118 M. S. Sander, R. Gronsky, Y.-M. Lin, M. S. Dresselhaus: Plasmon excitation modes in nanowire arrays, J. Appl. Phys. **89** (2001) 2733–2736

4.119 L. Venkataraman, C. M. Lieber: Molybdenum selenide molecular wires as one-dimensional conductors, Phys. Rev. Lett. **83** (1999) 5334–5337

4.120 A. Majumdar: Scanning thermal microscopy, Annual Rev. Mater. Sci. **29** (1999) 505–585

4.121 D. A. Wharam, T. J. Thornton, R. Newbury, M. Pepper, H. Ahmed, J. E. F. Frost, D. G. Hasko, D. C. Peacock, D. A. Ritchie, G. A. C. Jones: One-dimensional transport and the quantization of the ballistic resistance, J. Phys. C: Solid State Phys. **21** (1988) L209–L214

4.122 B. J. van Wees, H. van Houten, C. W. J. Beenakker, J. G. Williamson, L. P. Kouvenhoven, D. van der Marel, C. T. Foxon: Quantized conductance of point contacts in a two-dimensional electron gas, Phys. Rev. Lett. **60** (1988) 848–850

4.123 C. J. Muller, J. M. van Ruitenbeek, L. J. de Jongh: Conductance and supercurrent discontinuities in atomic-scale metallic constrictions of variable width, Phys. Rev. Lett. **69** (1992) 140–143

4.124 C. J. Muller, J. M. Krans, T. N. Todorov, M. A. Reed: Quantization effects in the conductance of metallic contacts at room temperature, Phys. Rev. B **53** (1996) 1022–1025

4.125 J. L. Costa-Krämer, N. Garcia, H. Olin: Conductance quantization in bismuth nanowires at 4 K, Phys. Rev. Lett. **78** (1997) 4990–4993

4.126 J. L. Costa-Krämer, N. Garcia, H. Olin: Conductance quantization histograms of gold nanowires at 4 K, Phys. Rev. B **55** (1997) 12910–12913

4.127 C. Z. Li, H. X. He, A. Bogozi, J. S. Bunch, N. J. Tao: Molecular detection based on conductance quantization of nanowires, Appl. Phys. Lett. **76** (2000) 1333–1335

4.128 J. L. Costa-Krämer, N. Garcia, P. Garcia-Mochales, P. A. Serena, M. I. Marques, A. Correia: Conductance quantization in nanowires formed between micro and macroscopic metallic electrodes, Phys. Rev. B **55** (1997) 5416–5424

4.129 Y. Huang, X. Duan, Y. Cui, L. J. Lauhon, K.-H. Kim, C. Lieber: Logic gates and computation from assembled nanowire building blocks, Science **294** (2001) 1313–1317

4.130 J.-R. Kim, H. Oh, H. M. So, J.-J. Kim, J. Kim, C. J. Lee, S. C. Lyu: Schottky diodes based on a single GaN nanowire, Nanotechnology **13** (2002) 701–704

4.131 X. Duan, Y. Huang, C. M. Lieber: Nonvolatile memory and programmable logic from molecule-gated nanowires, Nano. Lett. **2** (2002) 487–490

4.132 E. C. Walter, R. M. Penner, H. Liu, K. H. Ng, M. P. Zach, F. Favier: Sensors from electrodeposited metal nanowires, Surf. Inter. Anal. **34** (2002) 409–412

4.133 E. C. Walter, K. H. Ng, M. P. Zach, R. M. Penner, F. Favier: Electronic devices from electrodeposited metal nanowires, Microelectron. Eng. **61–62** (2002) 555–561

4.134 Y.-M. Lin, X. Sun, M. S. Dresselhaus: Theoretical investigation of thermoelectric transport properties of cylindrical Bi nanowires, Phys. Rev. B **62** (2000) 4610–4623

4.135 K. Liu, C. L. Chien, P. C. Searson: Finite-size effects in bismuth nanowires, Phys. Rev. B **58** (1998) R14681–R14684

4.136 Z. Zhang, X. Sun, M. S. Dresselhaus, J. Y. Ying, J. Heremans: Magnetotransport investigations of ultrafine single-crystalline bismuth nanowire arrays, Appl. Phys. Lett. **73** (1998) 1589–1591

4.137 J. Heremans, C. M. Thrush, Z. Zhang, X. Sun, M. S. Dresselhaus, J. Y. Ying, D. T. Morelli: Magnetoresistance of bismuth nanowire arrays: A possible transition from one-dimensional to three dimensional localization, Phys. Rev. B **58** (1998) R10091–R10095

4.138 L. Sun, P. C. Searson, C. L. Chien: Finite-size effects in nickel nanowire arrays, Phys. Rev. B **61** (2000) R6463–R6466

4.139 Y.-M. Lin, O. Rabin, S. B. Cronin, J. Y. Ying, M. S. Dresselhaus: Semimetal-semiconductor transition in $Bi_{1-x}Sb_x$ alloy nanowires and their thermoelectric properties, Appl. Phys. Lett. **81** (2002) 2403–2405

4.140 Y.-M. Lin, S. B. Cronin, O. Rabin, J. Y. Ying, M. S. Dresselhaus: Transport properties and observation of semimetal-semiconductor transition in bi-based nanowires, Nanocrystalline Semiconductor Materials and Devices: MRS Symp. Proc., Boston 2002, ed. by J. M. Buriak, D. D. M. Wayner, L. Tsyeskov, F. Priolo, B. E. White, Boston 2003) **737** F3.14

4.141 Y.-M. Lin, M. S. Dresselhaus: Transport properties of superlattice nanowires and their potential for thermoelectric applications, Nanocrystalline Semiconductor Materials and Devices: MRS Symp. Proc., Boston 2002, ed. by J. M. Buriak, D. D. M. Wayner, L. Tsyeskov, F. Priolo, B. E. White (Materials Research Society Press, Boston 2003) **737** F8.18

4.142 J. Heremans, C. M. Thrush, Y.-M. Lin, S. B. Cronin, M. S. Dresselhaus: Transport properties of antimony nanowires, Phys. Rev. B **63** (2001) 085406(1–8)

4.143 Y.-M. Lin, S. B. Cronin, O. Rabin, J. Y. Ying, M. S. Dresselhaus: Transport properties of $Bi_{1-x}Sb_x$ alloy nanowires synthesized by pressure injection, Appl. Phys. Lett. **79** (2001) 677–679

4.144 D. E. Beutler, N. Giordano: Localization and electron–electron interaction effects in thin Bi wires and films, Phys. Rev. B **38** (1988) 8–19

4.145 Z. Zhang, X. Sun, M. S. Dresselhaus, J. Y. Ying, J. Heremans: Electronic transport properties of single crystal bismuth nanowire arrays, Phys. Rev. B **61** (2000) 4850–4861

4.146 J. Heremans, C. M. Thrush: Thermoelectric power of bismuth nanowires, Phys. Rev. B **59** (1999) 12579–12583

4.147 L. D. Hicks, M. S. Dresselhaus: Thermoelectric figure of merit of a one-dimensional conductor, Phys. Rev. B **47** (1993) 16631–16634

4.148 Y.-M. Lin, S. B. Cronin, O. Rabin, J. Heremans, M. S. Dresselhaus, J. Y. Ying: Transport properties of Bi-related nanowire systems, Anisotropic Nanoparticles: Synthesis, Characterization and Applications: MRS Symp. Proc., Boston 2000, ed. by S. Stranick, P. C. Searson, L. A. Lyon, C. Keating (Materials Research Society Press, Pittsburgh 2001) **635** C4301–C4306

4.149 Y.-M. Lin, M. S. Dresselhaus: Thermoelectric properties of superlattice nanowires, Phys. Rev. B **68** (2003) 075304 (1–14)

4.150 M. T. Björk, B. J. Ohlsson, C. Thelander, A. I. Persson, K. Deppert, L. R. Wallenberg, L. Samuelson: Nanowire resonant tunneling diodes, Appl. Phys. Lett. **81** (2002) 4458–4460

4.151 D. Li: Thermal transport in individual nanowires and nanotubes. Ph.D. Thesis (Univ. California, Berkeley 2002)

4.152 T. S. Tighe, J. M. Worlock, M. L. Roukes: Direct thermal conductance measurements on suspended monocrystalline nanostructures, Appl. Phys. Lett. **70** (1997) 2687–2689

4.153 S. T. Huxtable, A. R. Abramson, C.-L. Tien, A. Majumdar, C. LaBounty, X. Fan, G. Zeng, J. E. Bowers, A. Shakouri, E. T. Croke: Thermal conductivity of Si/SiGe and SiGe/SiGe superlattices, Appl. Phys. Lett. **80** (2002) 1737–1739

4.154 R. Venkatasubramanian, E. Siivola, T. Colpitts, B. O'Quinn: Thin-film thermoelectric devices with high room-temperature figures of merit, Nature **413** (2001) 597–602

4.155 C. Dames, G. Chen: Modeling the thermal conductivity of a SiGe segmented nanowire, 21st Int. Conf. Thermoelectrics: Proc. ICT Symposium, Long Beach 2002 (IEEE, Piscataway 2002) 317–320
4.156 G. Chen, M.S. Dresselhaus, G. Dresselhaus, J.-P. Fleurial, T. Caillat: Recent developments in thermoelectric materials, Int. Mater. Rev. **48** (2003) 45–66
4.157 K. Schwab, E.A. Henriksen, J.M. Worlock, M.L. Roukes: Measurement of the quantum of thermal conductance, Nature **404** (2000) 974–977
4.158 K. Schwab, J.L. Arlett, J.M. Worlock, M.L. Roukes: Thermal conductance through discrete quantum channels, Physica E **9** (2001) 60–68
4.159 M. Cardona: *Light scattering in solids* (Springer, Berlin, Heidelberg 1982)
4.160 P.Y. Yu, M. Cardona: *Fundamentals of Semiconductors* (Springer, Berlin, Heidelberg 1995) Chap. 7
4.161 J.C.M. Garnett: Colours in metal glasses, in metallic films, and in metallic solutions, Philos. Trans. Roy. Soc. London A **205** (1906) 237–288
4.162 D.E. Aspnes: Optical properties of thin films, Thin Solid Films **89** (1982) 249–262
4.163 U. Kreibig, L. Genzel: Optical absorption of small metallic particles, Surf. Sci. **156** (1985) 678–700
4.164 M.R. Black, Y.-M. Lin, S.B. Cronin, O. Rabin, M.S. Dresselhaus: Infrared absorption in bismuth nanowires resulting from quantum confinement, Phys. Rev. B **65** (2002) 195417(1–9)
4.165 M.W. Lee, H.Z. Twu, C.-C. Chen, C.-H. Chen: Optical characterization of wurtzite gallium nitride nanowires, Appl. Phys. Lett. **79** (2001) 3693–3695
4.166 D.M. Lyons, K.M. Ryan, M.A. Morris, J.D. Holmes: Tailoring the optical properties of silicon nanowire arrays through strain, Nano. Lett. **2** (2002) 811–816
4.167 J.C. Johnson, H. Yan, R.D. Schaller, L.H. Haber, R.J. Saykally, P. Yang: Single nanowire lasers, J. Phys. Chem. B **105** (2001) 11387–11390
4.168 S. Blom, L.Y. Gorelik, M. Jonson, R.I. Shekhter, A.G. Scherbakov, E.N. Bogachek, U. Landman: Magneto-optics of electronic transport in nanowires, Phys. Rev. B **58** (1998) 16305–16314
4.169 J.P. Pierce, E.W. Plummer, J. Shen: Ferromagnetism in cobalt-iron alloy nanowire arrays on W(110), Appl. Phys. Lett. **81** (2002) 1890–1892
4.170 J.C. Johnson, H. Yan, R.D. Schaller, P.B. Petersen, P. Yang, R.J. Saykally: Near-field imaging of nonlinear optical mixing in single zinc oxide nanowires, Nano. Lett. **2** (2002) 279–283
4.171 M.R. Black, Y.-M. Lin, S.B. Cronin, M.S. Dresselhaus: Using optical measurements to improve electronic models of bismuth nanowires, 21st Int. Conf. Thermoelectrics: Proc. ICT Symposium, Long Beach 2002 (IEEE, Piscataway 2002) 253–256
4.172 H.-L. Liu, C.-C. Chen, C.-T. Chia, C.-C. Yeh, C.-H. Chen, M.-Y. Yu, S. Keller, S.P. DenBaars: Infrared and Raman-scattering studies in single-crystalline GaN nanowires, Chem. Phys. Letts. **345** (2001) 245–251
4.173 H. Richter, Z.P. Wang, L. Ley: The one phonon Raman-spectrum in microcrystalline silicon, Solid State Commun. **39** (1981) 625–629
4.174 I.H. Campbell, P.M. Fauchet: The effects of microcrystal size and shape on the one phonon Raman-spectra of crystalline semiconductors, Solid State Commun. **58** (1986) 739–741
4.175 R. Gupta, Q. Xiong, C.K. Adu, U.J. Kim, P.C. Eklund and: Laser-induced Fanoresonance scattering in silicon nanowires, Nano. Lett. **3** (2003) 627–631
4.176 Y. Cui, C.M. Lieber: Functional nanoscale electronic devices assembled using silicon nanowire building blocks, Science **291** (2001) 851–853
4.177 S.-W. Chung, J.-Y. Yu, J.R. Heath: Silicon nanowire devices, Appl. Phys. Lett. **76** (2000) 2068–2070
4.178 M. Ding, H. Kim, A.I. Akinwande: Observation of valence band electron emission from n-type silicon field emitter arrays, Appl. Phys. Lett. **75** (1999) 823–825
4.179 F.C.K. Au, K.W. Wong, Y.H. Tang, Y.F. Zhang, I. Bello, S.T. Lee: Electron field emission from silicon nanowires, Appl. Phys. Lett. **75** (1999) 1700–1702
4.180 P.M. Ajayan, O.Z. Zhou: Applications of carbon nanotubes. In: *Carbon Nanotubes: Synthesis, Structure, Properties and Applications*, Vol. 80, ed. by M.S. Dresselhaus, G. Dresselhaus, P. Avouris (Springer, Berlin, Heidelberg 2001) pp. 391–425
4.181 G. Dresselhaus, M.S. Dresselhaus, Z. Zhang, X. Sun, J. Ying, G. Chen: Modeling thermoelectric behavior in Bi nano-wires, Seventeenth Int. Conf. Thermoelectrics: Proc. ICT'98, Nagoya 1998, ed. by K. Koumoto (Institute of Electrical and Electronics Engineers Inc, Piscataway 1998) 43–46
4.182 L.D. Hicks, M.S. Dresselhaus: The effect of quantum well structures on the thermoelectric figure of merit, Phys. Rev. B **47** (1993) 12727–12731
4.183 O. Rabin, Y.-M. Lin, M.S. Dresselhaus: Anomalously high thermoelectric figure of merit in $Bi_{1-x}Sb_x$ nanowires by carrier pocket alignment, Appl. Phys. Lett. **79** (2001) 81–83
4.184 T.C. Harman, P.J. Taylor, M.P. Walsh, B.E. LaForge: Quantum dot supertattice thermoelectric materials and devices, Science **297** (2002) 2229–2232
4.185 V. Dneprovskii, E. Zhukov, V. Karavanskii, V. Poborchii, I. Salamatini: Nonlinear optical properties of semiconductor quantum wires, Superlattices Microstruct. **23** (1998) 1217–1221
4.186 J.C. Johnson, H.-J. Choi, K.P. Knutsen, R.D. Schaller, P. Yang, R.J. Saykally: Single gallium nitride nanowire lasers, Nature Mater. **1** (2002) 106–110
4.187 H. Kind, H. Yan, B. Messer, M. Law, P. Yang: Nanowire ultraviolet photodetectors and optical switches, Adv. Mat. **14** (2002) 158–160

4.188 B. M. I. van der Zande, M. Böhmer, L. G. J. Fokkink, C. Schönenberger: Colloidal dispersions of gold rods: Synthesis and optical properties, Langmuir **16** (2000) 451–458

4.189 B. M. I. van der Zande, G. J. M. Koper, H. N. W. Lekkerkerker: Alignment of rod-shaped gold particles by electric fields, J. Phys. Chem. B **103** (1999) 5754–5760

4.190 W. U. Huynh, J. J. Dittmer, A. P. Alivisatos: Hybrid nanorod-polymer solar cells, Science **295** (2002) 2425–2427

4.191 Y. Cui, Q. Wei, H. Park, C. Lieber: Nanowire nanosensors for highly sensitive and selective detection of biological and chemical species, Science **293** (2001) 1289–1292

Springer Handbook of Nanotechnology
B. Bhushan • © Springer 2004

5. Introduction to Micro/Nanofabrication

In this chapter, we discuss various *micro/nanofabrication* techniques used to manufacture structures in a wide range of dimensions (mm–nm). Starting with some of the most common microfabrication techniques (lithography, deposition, and etching), we present an array of *micromachining* and *MEMS* technologies that can be used to fabricate microstructures down to ∼1 μm. These techniques have attained an adequate level of maturity to allow for a variety of MEMS-based commercial products (pressure sensors, accelerometers, gyroscopes, etc.). More recently, nanometer-sized structures have attracted an enormous amount of interest. This is mainly due to their unique electrical, magnetic, optical, thermal, and mechanical properties. These could lead to a variety of electronic, photonic, and sensing devices with a superior performance compared to their macro counterparts. Subsequent to our discussion on MEMS and micromachining, we present several important *nanofabrication* techniques currently under intense investigation. Although e-beam and other high resolution lithographies can be used to fabricate nanometer-sized structures, their serial nature and/or cost preclude their widespread application. This has forced investigators to explore alternative and potentially superior techniques such as *strain engineering*, *self-assembly*, and *nano-imprint* lithography. Among these, self-assembly is the most promising method, due to its low cost and the ability to produce nanostructures at different length scales.

5.1 **Basic Microfabrication Techniques** 148
  5.1.1 Lithography 148
  5.1.2 Thin Film Deposition and Doping ... 149
  5.1.3 Etching and Substrate Removal 153
  5.1.4 Substrate Bonding 157

5.2 **MEMS Fabrication Techniques** 159
  5.2.1 Bulk Micromachining 159
  5.2.2 Surface Micromachining 163
  5.2.3 High-Aspect-Ratio Micromachining 166

5.3 **Nanofabrication Techniques** 170
  5.3.1 E-Beam and Nano-Imprint Fabrication 171
  5.3.2 Epitaxy and Strain Engineering 172
  5.3.3 Scanned Probe Techniques 173
  5.3.4 Self-Assembly and Template Manufacturing 176

References 180

Recent innovations in the area of *micro/nanofabrication* have created a unique opportunity for manufacturing structures in the nanometer–millimeter range. The available six orders of magnitude dimensional span can be used to fabricate novel electronic, optical, magnetic, mechanical, and chemical/biological devices with applications ranging from sensors to computation and control. In this chapter, we will introduce major micro/nanofabrication techniques currently used to fabricate structures in the nanometer to several hundred micrometer range. We will focus mainly on the most important and widely used techniques and will not discuss specialized methods. After a brief introduction to basic microfabrication, we will discuss *MEMS*-fabrication techniques used to build microstructures down to about 1 μm in dimensions. Following this, we will discuss several major top-down and bottom-up nanofabrication methods that have shown great promise in manufacturing *nanostructures* (dimensions < 1 μm).

5.1 Basic Microfabrication Techniques

Most micro/nanofabrication techniques have their roots in the standard fabrication methods developed for the semiconductor industry [5.1–3]. Therefore, a clear understanding of these techniques is necessary for anyone embarking on a research and development path in the micro/nano area. In this section, we will discuss major microfabrication techniques used most frequently in the manufacturing of micro/nanostructures. Some of these techniques such as thin-film deposition and etching are common between the micro/nano and VLSI microchip fabrication disciplines. However, several other techniques that are more specific to the micro/nanofabrication area will also be discussed in this section.

5.1.1 Lithography

Lithography is the technique used to transfer a computer generated pattern onto a substrate (silicon, glass, GaAs, etc.). This pattern is subsequently used to etch an underlying thin film (oxide, nitride, etc.) for various purposes (doping, etching, etc.). Although photolithography, i. e., the lithography using a UV light source, is by far the most widely used lithography technique in microelectronic fabrication, electron-beam (e-beam) and X-ray lithography are two other alternatives that have attracted considerable attention in the MEMS and nanofabrication areas. We will discuss photolithography in this section and postpone the discussion of e-beam and X-ray techniques to the subsequent sections dealing with MEMS and nanofabrication.

The starting point following the creation of the computer layout for a specific fabrication sequence is the generation of a photomask. This involves a sequence of photographic processes (using optical or e-beam pattern generators) that results in a glass plate having the desired pattern in the form of a thin ($\sim$ 100 nm) chromium layer. Following the generation of photomask, the lithography process can proceed as shown in Fig. 5.1. This sequence demonstrates the pattern transfer onto a substrate coated with silicon dioxide. However, the same technique is applicable to other materials. After depositing the desired material on the substrate, the photolithography process starts with spin coating the substrate with a photoresist. This is a polymeric photosensitive material that can be spun onto the wafer in liquid form (usually an adhesion promoter such as hexamethyldisilazane HMDS is used prior to the application of the resist). The spinning speed and photoresist viscosity will determine the final resist thickness, which is typically between 0.5–2.5 µm. Two different kinds of photoresist are available: positive and negative. In the positive resist, the UV-exposed areas will be dissolved in the subsequent development stage, whereas in the negative photoresist, the exposed areas will remain intact after the development. Due to its better performance with regard to the process control in small geometries, the positive resist is the most extensively used photoresist in the VLSI processes. After spinning the photoresist on the wafer, the substrate is soft baked (5–30 min at 60–100 °C) in order to remove the solvents from the resist and improve the adhesion. Subsequently, the mask is aligned to the wafer and the photoresist is exposed to a UV source.

Depending on the separation between the mask and the wafer, three different exposure systems are available: 1) contact, 2) proximity, and 3) projection. Although contact printing gives better resolution compared to the proximity technique, the constant contact of the mask with photoresist reduces the process yield and can damage the mask. Projection printing uses a dual-lens optical system to project the mask image onto the wafer. Since only one die at a time can be exposed, this requires a step-and-repeat system to totally cover the wafer area. Projection printing is by far the most widely used system in microfabrication and can yield superior resolutions compared to contact and proximity methods. The exposure source for photolithography depends on the resolution. Above 0.25 µm minimum line width, high pressure mercury lamp is adequate (436 nm g-line and 365 nm i-line). However, between 0.25 and 0.13 µm, deep UV sources such as excimer lasers (248 nm KrF and 193 nm ArF) are required. Although there has been extensive competition for the below 0.13 µm regime (including e-beam and X-ray), extreme UV (EUV) with



Fig. 5.1 Lithography process flow

a wavelength of 10–14 nm seems to be the preferred technique [5.4].

After exposure, the photoresist is developed in a process similar to the development of photographic film. The resist is subsequently hard baked (20–30 min at 120–180 °C) in order to further improve the adhesion. The hard bake step concludes the photolithography sequence by creating the desired pattern on the wafer. Next, the underlying thin film is etched, and the photoresist is stripped in acetone or other organic removal solvents. Figure 5.2 shows schematic drawing of photolithography steps with a positive photoresist.

5.1.2 Thin Film Deposition and Doping

Thin-film deposition and doping are used extensively in micro/nanofabrication technologies. Most of the fabricated micro/nanostructures contain materials other than that of the substrate, which are obtained by various deposition techniques, or by modification of the substrate. The following is a list of a few typical applications for the deposited and/or doped materials used in micro/nanofabrication that gives an idea of the required properties:

- Mechanical structure
- Electrical isolation
- Electrical connection
- Sensing or actuating
- Mask for etching and doping
- Support or mold during deposition of other materials (sacrificial materials)
- Passivation

Most of the deposited thin films have different properties than those of their corresponding “bulk” forms (for example, metals show higher resistivities as thin films). In addition, the techniques utilized to deposit these materials have a great impact on their final properties. For instance, internal stress (compressive or tensile) in a film is strongly process-dependent. Excessive stress may crack or detach the film from the substrate and therefore must be minimized, although it may also be useful for certain applications. Adhesion is another important issue that needs to be taken into account when depositing thin films. In some cases such as the deposition of noble metals (e.g., gold) an intermediate layer (chromium or titanium) may be needed to improve the adhesion. Finally, step coverage and conformality are two properties that can also influence the choice of deposition technique. Figure 5.3 illustrates these concepts.



Fig. 5.2 Schematic drawing of the photolithographic steps with a positive photoresist (PR)



Fig. 5.3a–d Step coverage and conformality: **(a)** poor step coverage, **(b)** good step coverage, **(c)** nonconformal layer, and **(d)** conformal layer

Oxidation

Oxidation of silicon is a process used to obtain a thin film of SiO_2 of excellent quality (very low density of defects) and thickness homogeneity. Although it is not properly a deposition, the result is the same, i. e., a thin layer of a new material covering the surface is produced. The oxidation process is typically carried out at temperatures in the range of 900 °C to 1,200 °C in the presence of O_2 (dry oxidation) or H_2O (wet oxidation). The reactions for oxide formation are:

$$\mathrm{Si_{(solid)}} + \mathrm{O_{2(gas)}} \Rightarrow \mathrm{SiO_{2(solid)}}$$

and

$$\mathrm{Si_{(solid)}} + 2\mathrm{H_2O_{(steam)}} \Rightarrow \mathrm{SiO_{2(solid)}} + 2\mathrm{H_{2(gas)}} \,.$$

Although the rate of the oxide growth is higher for wet oxidation, it is achieved at the expense of a lower oxide quality (density). Since silicon atoms from the substrate participate in the reaction, the substrate is consumed as the oxide grows ($\sim 44\%$ of the total thickness lies above the line of the original silicon surface). The oxidation of silicon also occurs at room temperature, however, a layer of about 20 Å (native oxide) is enough to passivate the surface and prevent further oxidation. To grow thicker oxides, wafers are introduced into an electric resistance furnace such as the one represented in Fig. 5.4. Tens of wafers can be processed in a single batch in such equipment. By strictly controlling the timing, temperature, and gas flow entering the quartz tube, the desired thickness can be achieved with a high accuracy. Thicknesses ranging from a few tens of Angstroms to 2 μm can be obtained in reasonable times. Despite the good quality of the SiO_2 obtained by silicon oxidation (also called *thermal oxide*), the use of this process is often limited to the early stages of fabrication, since some of the materials added during the formation of structures may not withstand the high temperatures. The contamination of the furnace when the substrates have been previously in contact with certain etchants such as KOH, or when materials such as metals have been deposited also pose limitations in most of the cases.

Doping

The introduction of certain impurities in a semiconductor can change its electrical, chemical, and even mechanical properties. Typical impurities, or *dopants*, used in silicon include boron (to form p-type regions) and phosphorous or arsenic (to form n-type regions). Doping is the main process used in the microelectronic industry to fabricate major components such as diodes and transistors. In micro/nanofabrication technologies doping has additional applications such as the formation of piezoresistors for mechanical transducers and the creation of etch stop layers. Two different techniques are used to introduce the impurities into a semiconductor substrate: diffusion and ion implantation.

Diffusion is the process that became dominant in the initial years following the invention of the integrated circuit to form n- and p-type regions in the silicon. The diffusion of impurities into the silicon occurs only at high temperatures (above 800 °C). Furnaces used to carry out this process are similar to the oxidation ones. The dopants are introduced into the furnace's gaseous atmosphere from liquid or solid sources. Figure 5.5 illustrates the process of creating an n-type region by diffusion of phosphor from the surface into a p-type substrate. A masking material is previously deposited and patterned on the surface to define the areas to be doped. However, because diffusion is an isotropic process, the doped area will also extend underneath the mask. In microfabrication, diffusion is mainly used for the formation of very highly doped boron regions (p^{++}), which are usually used as an etch stop in bulk *micromachining*.

Ion implantation allows a more precise control of the dose (total amount of impurities introduced per area unit)



Fig. 5.4 Schematic representation of a typical oxidation furnace



Fig. 5.5 Formation of an n-type region on a p-type silicon substrate by diffusion of phosphorous

and the impurity profile (concentration versus depth). In ion implantation, the impurities are ionized and accelerated toward the semiconductor surface. The penetration of impurities in the material follows a Gaussian distribution. After implantation, an annealing process is needed to activate the impurities and repair the damage in the crystal structure produced by the ion collisions. A *drive-in* process to redistribute the impurities performed in a standard furnace such as the ones used for oxidation or diffusion may be required as well.

Chemical Vapor Deposition and Epitaxy

As its name suggests, chemical vapor deposition (CVD) includes all the deposition techniques using the reaction of chemicals in a gas phase to form the deposited thin film. The energy needed for the chemical reaction to occur is usually supplied by maintaining the substrate at elevated temperatures. Other alternative energy sources such as plasma or optical excitation are also used, with the advantage of requiring a lower temperature at the substrate. The most common CVD processes in microfabrication are LPCVD (low pressure CVD) and PECVD (plasma enhanced CVD).

The LPCVD process is typically carried out in electrically heated tubes, similar to the oxidation tubes, equipped with pumping capabilities to achieve the needed low pressures (0.1 to 1.0 torr). A large number of wafers can be processed simultaneously, and the material is deposited in both sides of the wafers. The process temperatures depend on the material to be deposited, but generally are in the range of 550 to 900 °C. As in the oxidation, high temperatures and contamination issues can restrict the type of processes used prior to the LPCVD. Typical materials deposited by LPCVD include silicon oxide (e.g., $SiCl_2H_2 + 2N_2O \Rightarrow SiO_2 + 2N_2 + 2HCl$ at 900 °C), silicon nitride (e.g., $3SiH_4 + 4NH_3 \Rightarrow Si_3N_4 + 12H_2$ at 700–900 °C), and polysilicon (e.g., $SiH_4 \Rightarrow Si + 2H_2$ at 600 °C). Due to its faster etch rate in HF, in situ phosphorous-doped LPCVD oxide (phosphosilicate glass or PSG) is used extensively as the sacrificial layer in surface micromachining. Conformality in this process is excellent, even for very high-aspect-ratio structures. Mechanical properties of LPCVD materials are good compared to others such as PECVD, and LPCVD materials often used as structural materials in microfabricated devices. Stress in the deposited layers depends on the material, deposition conditions, and subsequent thermal history (e.g., post-deposition anneal). Typical values are: 100–300 MPa (compressive) for oxide, ~ 1 GPa (tensile) for stoichiometric nitride, and ~ 200–300 MPa (tensile) for polysilicon. The stress in nitride layers can be reduced to nearly zero by using a silicon-rich composition. Since the stress values can vary over a wide range, one has to measure and characterize the internal stress of deposited thin films for any specific equipment and deposition conditions.

The PECVD process is performed in plasma systems such as the one represented in Fig. 5.6. The use of RF energy to create highly reactive species in the plasma allows for the use of lower temperatures at the substrates (150 to 350 °C). Parallel-plate plasma reactors normally used in microfabrication can only process a limited number of wafers per batch. The wafers are positioned horizontally on top of the lower electrode, so only one side gets deposited. Typical materials deposited with PECVD include silicon oxide, nitride, and amorphous silicon. Conformality is good for low-aspect-ratio structures, but becomes very poor for deep trenches (20% of the surface thickness inside through-wafer holes with aspect ratio of ten). Stress depends on deposition parameters and can be either compressive or tensile. PECVD nitrides are typically non-stoichiometric (Si_xN_y) and are much less resistant to etchants in masking applications.

Another interesting type of CVD is epitaxial growth. In this process, a single crystalline material is grown as an extension of the crystal structure of the substrate. It is possible to grow dissimilar materials if the crystal structures are somehow similar (lattice-matched). Silicon-on-sapphire (SOS) substrates and some heterostructures are fabricated in this way. However, most



Fig. 5.6 Schematic representation of a typical PECVD system

common in microfabrication is the growth of silicon on another silicon substrate. Of particular interest for the formation of microstructures is the selective epitaxial growth. In this process the silicon crystal is allowed to grow only in windows patterned on a masking material. Many CVD techniques have been used to produce epitaxial growth. The most common for silicon is thermal chemical vapor deposition or *vapor phase epitaxy* (VPE). *Metallorganic chemical vapor deposition* (MOCVD) and *molecular beam epitaxy* (MBE) are the most common for growing high quality III-V compound layers with nearly atomic abrupt interfaces. The former uses vapors of organic compounds with group III atoms such as trimethylgallium [$Ga(CH_3)_3$] and group V hydrides such as AsH_3 in a CVD chamber with fast gas switching capabilities. The latter typically uses molecular beams from thermally evaporated elemental sources aiming at the substrate in an ultrahigh vacuum chamber. In this case, rapid on/off control of the beams is achieved by using shutters in front of the sources. Finally, it should be mentioned that many metals (molybdenum, tantalum, titanium, and tungsten) can also be deposited using LPCVD. These are attractive for their low resistivities and their ability to form silicides with silicon. Due to its application in the new interconnect technologies, copper CVD is an active area of research.

Physical Vapor Deposition (Evaporation and Sputtering)

In physical deposition systems the material to be deposited is transported from a source to the wafers, both being in the same chamber. Two physical principles are used to do so: evaporation and sputtering.

In evaporation, the source is placed in a small container with tapered walls, called a crucible, and heated up to a temperature at which evaporation occurs. Various techniques are utilized to reach the high temperatures needed, including the induction of high currents with coils wound around the crucible and the bombardment of the material surface with an electron beam (e-beam evaporators). This process is mainly used to deposit metals, although dielectrics can also be evaporated. In a typical system, the crucible is located at the bottom of a vacuum chamber, whereas the wafers are placed lining the dome-shaped ceiling of the chamber, Fig. 5.7. The main characteristic of this process is very poor step coverage, including shadow effects, as illustrated in Fig. 5.8. As will be explained in subsequent sections, some microfabrication techniques utilize these effects to pattern the deposited layer. One way to improve the step coverage is by rotating and/or heating the wafers during the deposition.



Fig. 5.7 Schematic representation of an electron-beam deposition system



Fig. 5.8 Shadow effects observed in evaporated films. *Arrows* show the trajectory of the material atoms being deposited

In sputtering, a target of the material to be deposited is bombarded with high-energy inert ions (usually argon). The outcome of the bombardment is that individual atoms or clusters are removed from the surface and ejected toward the wafer. The physical nature of this process allows its use with virtually any existing material. Examples of interesting materials for microfabrication that are frequently sputtered include metals, dielectrics, alloys (such as shape memory alloys), and all kinds of compounds (for example, piezoelectric PZT). The inert ions bombarding the target are produced in DC or RF plasma. In a simple parallel-plate system, the top electrode is the target and the wafers are placed horizontally on top of the bottom electrode. In spite of its lower deposition rate, step coverage in sputtering is much better than in evaporation. Yet, the films obtained



Fig. 5.9 Typical cross section evolution of a trench while being filled with sputter deposition

with this deposition process are nonconformal. Figure 5.9 illustrates successive sputtering profiles in a trench.

Both evaporation and sputtering systems are often capable of depositing more than one material simultaneously or sequentially. This capability is very useful in obtaining alloys and multilayers (e.g., multilayer magnetic recording heads are sputtered). For certain low reactivity metals such as Au and Pt, the previous deposition of a thin layer of another metal is needed to improve the adhesion. Ti and Cr are two frequently used adhesion promoters. Stress in evaporated or sputtered layers is typically tensile. The deposition rates are much higher than most CVD techniques. However, due to stress accumulation and cracking, a thickness beyond 2 µm is rarely deposited with these processes. For thicker depositions a technique described in the next section is sometimes used.

Electroplating

Electroplating (or electrodeposition) is a process typically used to obtain thick (tens of micrometers) metal structures. The sample to be electroplated is introduced in a solution containing a reducible form of the ion of the desired metal and is maintained at a negative potential (cathode) relative to a counter electrode (anode). The ions are reduced at the sample surface and the insoluble metal atoms are incorporated into the surface. As an example, copper electrodeposition is frequently done in copper sulfide-based solutions. The reaction taking place at the surface is $Cu^{2+} + 2e^{-} \rightarrow Cu_{(s)}$. Recommended current densities for electrodeposition processes are on the order of 5 to 100 mA/cm^2.

As can be deduced from the process mechanism, the surface to be electroplated has to be electrically conductive and preferably of the same material as the deposited one if a good adhesion is desired. In order to electrodeposit metals on top of an insulator (the most common case) a thin film of the same metal, called the seed layer, is previously deposited on the surface. Masking of the seed layer with a resist permits selective electroplatingat the patterned areas. Figure 5.10 illustrates a typical sequence of the steps required to obtain isolated metal structures.

5.1.3 Etching and Substrate Removal

Thin film and bulk substrate etching is another fabrication step that is of fundamental importance to both VLSI processes and micro/nanofabrication. In the VLSI area, various conducting and dielectric thin films deposited for passivation or masking purposes must be removed at some point or another. In micro/nanofabrication, in addition to thin film etching, very often the substrate (silicon, glass, GaAs, etc.) also needs to be removed in order to create various mechanical micro-/nanostructures (beams, plates, etc.). Two important figures of merit for any etching process are selectivity and directionality. Selectivity is the degree to which the etchant can differentiate between the masking layer and the layer to be



Fig. 5.10a–d Formation of isolated metal structures by electroplating through a mask: **(a)** seed layer deposition, **(b)** photoresist spinning and patterning, **(c)** electroplating, **(d)** photoresist and seed layer stripping

etched. Directionality has to do with the etch profile under the mask. In an isotropic etch, the etchant attacks the material in all directions at the same rate, creating a semicircular profile under the mask, Fig. 5.11a. In an anisotropic etch, the dissolution rate depends on specific directions, and one can obtain straight sidewalls or other noncircular profiles, Fig. 5.11b. One can also divide the various etching techniques into wet and dry categories. In this chapter, we will use this classification and discuss different wet etchants, followed by the dry etching techniques used most often in micro/nanofabrication.

Wet Etching

Historically, wet etching techniques preceded the dry ones. These still constitute an important group of etchants for micro/nanofabrication, in spite of their less frequent application in the VLSI processes. Wet etchants are by and large isotropic and show superior selectivity to the masking layer compared to various dry techniques. In addition, due to the lateral undercut, the minimum feature achievable with wet etchants is limited to $> 3\,\mu m$. Silicon dioxide is commonly etched in a dilute (6:1, 10:1, or 20:1 by volume) or buffered HF (BHF, HF + NH_4F) solutions (etch rate of $\sim 1{,}000$ Å/min in BHF). Photoresist and silicon nitride are the two most common masking materials for the wet oxide etch. The wet etchant for silicon nitride is hot (140–200 °C) phosphoric acid with silicon oxide as the masking material. Nitride wet etch is not very common (except for blanket etch), due to the masking difficulty and unrepeatable etch rates. Metals can be etched using various combinations of acids and base solutions. There are also many commercially available etchant formulations for aluminum, chromium, and gold that can be used easily. A comprehensive table of various metal etchants can be found in [5.5].

Anisotropic and isotropic wet etching of crystalline (silicon and gallium arsenide) and non-crystalline (glass) substrates are important topics in micro/nanofabrication [5.6–10]. In particular, the realization of the possibility of anisotropic wet etching of silicon is considered the beginning of the micromachining and MEMS discipline. Isotropic etching of silicon using HF/HNO_3/CH_3COOH (various different formulations have been used) dates back to the 1950s and is still frequently used to thin down the silicon wafer. The etch mechanism for this combination has been elucidated and is as follows: HNO_3 is used to oxidize the silicon, which is subsequently dissolved away in the HF. The acetic acid is used to prevent the dissociation of HNO_3 (the etch works as well without the acetic acid). For short etch times, silicon dioxide can be used as the masking material However, one needs to use silicon nitride if a longer etch time is desired. This etch also shows dopant selectivity with the etch rate dropping at lower doping concentrations ($< 10^{17}\,cm^{-3}$ n- or p-type). Although this effect can potentially be used as an etch stop mechanism in order to fabricate microstructures, the difficulty in masking has prevented a widespread application of this approach. Glass can also be isotropically etched using the HF/HNO_3 combination with the etch surfaces showing considerable roughness. This has been used extensively in fabricating microfluidic components (mainly channels). Although Cr/Au is usually used as the masking layer, long etch times require a more robust mask (bonded silicon has been used for this purpose).



Fig. 5.11a,b Profile for isotropic **(a)** and anisotropic **(b)** etch through a photoresist (PR) mask

Silicon anisotropic wet etch constitutes an important technique in bulk micromachining. The three most important silicon etchants in this category are potassium hydroxide (KOH), ethylene diamine pyrochatechol (EDP), and tetramethyl ammonium hydroxide (TMAH). These are all anisotropic etchants that attack silicon along preferred crystallographic directions. In addition, they all show a marked reduction in the etch rate in heavily doped ($> 5 \times 10^{19}\,cm^{-3}$) boron ($p^{++}$) regions. The chemistry behind the action of these etchants is not yet very clear, but it seems that silicon atom oxidation at the surface and its reaction with hydroxyl ions (OH^-) are responsible for the formation of a soluble silicon complex ($SiO_2(OH)^{2-}$). The etch rate depends on the concentration and temperature and is usually around $1\,\mu m/min$ at temperatures of 85–115 °C. Common masking materials for anisotropic wet etchants are silicon dioxide and nitride, the latter being superior for longer etch times. The crystallographic plane which shows the slowest etch rate is the (111) plane. Although the lower atomic concentration along these planes have been speculated as the reason for this phenomenon, the evidence is inconclusive, and other factors must be included to account for this remarkable etch stop property. The anisotropic behavior of these etchants with respect to the (111) planes have been used extensively to create



Fig. 5.12a,b Anisotropic etch profiles for: **(a)** (100) and **(b)** (110) silicon wafers

beams, membranes, and other mechanical and structural components. Figure 5.12 shows the typical cross sections of (100) and (110) silicon wafers etched with an anisotropic wet etchant. As can be seen, the (111) slow planes are exposed in both situations, one creating 54.7° sloped sidewalls in the (100) wafer and the other creating vertical sidewalls in the (110) wafer. Depending on the dimensions of the mask opening, a V-groove or a trapezoidal trench is formed in the (100) wafer. A large enough opening will allow the silicon to be etched all the way through the wafer, thus creating a thin dielectric membrane of the other side. It should be mentioned that exposed convex corners have a higher etch rate than the concave ones, resulting in an undercut that can be used to create dielectric (e.g., nitride) cantilever beams. Figure 5.13 shows a cantilever beam fabricated using the convex corner undercut on a (100) wafer.

The three above mentioned etchants show different directional and dopant selectivities. KOH has the best (111) selectivity (400/1) followed by TMAH and EDP. However, EDP has the highest selectivity with respect to the deep boron diffusion regions. Safety and CMOS compatibility are other important criteria for choosing a particular anisotropic etchant. Among the three mentioned etchants TMAH is the most benign, whereas EDP is extremely corrosive and carcinogenic. Silicon can be dissolved in TMAH in order to improve its selectivity with respect to aluminum. This property has made TMAH very appealing for post-CMOS micromachining for which aluminum lines have to be protected. Finally, it should be mentioned that one can modulate the etch rate using a reverse biased p–n junction (electrochemical etch stop). Figure 5.14 shows the setup commonly used to perform electrochemical etching. The silicon wafer under etch consists of an n-epi region on a p-type substrate. Upon the application of a reverse bias voltage to the structure (p-substrate is in contact with the solution and n-epi is protected using a water tight fixture), the p-substrate is etched away. When the n-epi regions are exposed to the solution, an oxide passivation layer is formed and etch is stopped. This technique can be used to fabricate single-crystalline silicon membranes for pressure sensors and other mechanical transducers.

Dry Etching

Most dry etching techniques are plasma-based. They have several advantages compared with wet etching. These include smaller undercut (allowing smaller lines to be patterned) and higher anisotropicity (allowing high-aspect-ratio vertical structures). However, the selectivity of dry etching techniques is lower than the wet etchants, and one must take into account the finite etch rate of the masking materials. The three basic dry etching techniques, namely, high-pressure plasma etching, reactive ion etching (RIE), and ion milling utilize different mechanisms to obtain directionality.

Ion milling is a purely physical process that utilizes accelerated inert ions (e.g., Ar^+) striking perpendic-



Fig. 5.13 Top view and cross section of a dielectric cantilever beam fabricated using convex corner undercut



Fig. 5.14 Electrochemical etch setup

ular to the surface to remove the material (pressure $\sim 10^{-4}$–10^{-3} torr), Fig. 5.15a. The main characteristics of this technique are very low etch rates (on the order of a few nanometers per minute) and poor selectivity (close to 1:1 for most materials); hence it is generally used to etch very thin layers. In high-pressure (10^{-1}–5 torr) plasma etchers, highly reactive species are created that react with the material to be etched. The products of the reaction are volatile, so that they diffuse away and new material is exposed to the reactive species. Directionality can be achieved, if desired, with the sidewall passivation technique (Fig. 5.15b). In this technique, nonvolatile species produced in the chamber deposit and passivate the surfaces. The deposit can only be removed by physical collision with incident ions. Because the movement of the ions has a vertical directionality, the deposit is removed mainly at the horizontal surfaces, while the vertical walls remain passivated. In this fashion, the vertical etch rate becomes much higher than the lateral one.



Fig. 5.15a–c Simplified representation of etching mechanisms for **(a)** ion milling, **(b)** high-pressure plasma etching, and **(c)** RIE

The RIE etching, also called ion-assisted etching, is a combination of physical and chemical processes. In this technique, the reactive species react with the material only when the surfaces are "activated" by the collision of incident ions from the plasma (e.g., by breaking bonds at the surface). As in the previous technique, the directionality of the ion's velocity produces many more collisions in the horizontal surfaces than in the walls, thus generating faster etching rates in the vertical direction (Fig. 5.15c). To further increase the etch anisotropy, sidewall passivation methods in some cases, are also used. An interesting case is the *deep reactive ion etching* (DRIE) technique, capable of achieving aspect ratios of 30:1 and silicon etching rates of 2 to 3 μm/min (through-wafer etch is possible). In this technique, the passivation deposition and etching steps are performed sequentially in a two-step cycle, as shown in Fig. 5.16. In commercial silicon DRIE etchers, SF_6/Ar is typically used for the etching step and a combination of Ar and a fluoropolymer ($n\mathrm{CF}_2$) for the passivation step. A Teflon-like polymer about 50 nm thick is deposited during the latter step, covering only the sidewalls (Ar^+ ion bombardment removes the Teflon on the horizontal surfaces). Due to the cyclic nature of this process, the sidewalls of the etched features show a periodic "wave-shape" roughness in the range of 50 to 400 nm.

Dry etching can also be performed in non-plasma equipment if the etching gases are reactive enough. The so-called vapor phase etching (VPE) processes can be carried out in a simple chamber with gas feeding and pumping capabilities. Two examples of VPE are xenon difluoride (XeF_2) etching of silicon and HF-vapor etching of silicon dioxide. Due to its isotropic nature, these processes are typically used for etching sacrificial layers and releasing structures while avoiding stiction problems (see Sects. 5.2.1 and 5.2.2).



Fig. 5.16a–d DRIE cyclic process: **(a)** photoresist patterning, **(b)** etch step, **(c)** passivation step, and **(d)** etch step

Table 5.1 Typical dry etch chemistries

Si	CF_4/O_2, CF_2Cl_2, CF_3Cl, $SF_6/O_2/Cl_2$, $Cl_2/H_2/C_2F_6/CCl_4$, C_2ClF_5/O_2, Br_2, SiF_4/O_2, NF_3, ClF_3, CCl_4, CCl_3F_5, C_2ClF_5/SF_6, C_2F_6/CF_3Cl, CF_3Cl/Br_2
SiO_2	CF_4/H_2, C_2F_6, C_3F_8, CHF_3/O_2
Si_3N_4	$CF_4/O_2/H_2$, C_2F_6, C_3F_8, CHF_3
Organics	O_2, CF_4/O_2, SF_6/O_2
Al	BCl_3, BCl_3/Cl_2, $CCl_4/Cl_2/BCl_3$, $SiCl_4/Cl_2$
Silicides	CF_4/O_2, NF_3, SF_6/Cl_2, CF_4/Cl_2
Refractories	CF_4/O_2, NF_3/H_2, SF_6/O_2
GaAs	BCl_3/Ar, $Cl_2/O_2/H_2$, $CClH_3/H_2$ H_2, CH_4/H_2, $CCl_2F_2/O_2/Ar/He$
InP	CH_4/H_2, C_2H_6/H_2, Cl_2/Ar
Au	$C_2Cl_2F_4$, Cl_2, $CClF_3$

Most importantly, materials can be etched with the aforementioned techniques, and for each material a variety of chemistries is available. Table 5.1 lists some of the most common materials along with selected etch recipes [5.11]. For each chemistry, the etch rate, directionality, and selectivity with respect to the mask materials depend on parameters such as the flow/rates of the gases entering the chamber, the working pressure, and the RF power applied to the plasma.

5.1.4 Substrate Bonding

Substrate (wafer) bonding (silicon-silicon, silicon-glass, and glass-glass) is among the most important fabrication techniques in microsystem technology [5.12, 13]. It is frequently used to fabricate complex 3-D structures both as a functional unit and as part of the final microsystem package and encapsulation. The two most important bonding techniques are silicon-silicon fusion (or silicon direct bonding) and silicon-glass electrostatic (or anodic) bonding. In addition to these techniques, several other alternative methods that utilize an intermediate layer (eutectic, adhesive, and glass frit) have also been investigated. All these techniques can be used to bond the substrates at the wafer level. In this chapter, we will only discuss wafer-level techniques and will not treat the device level bonding methods (e.g., e-beam and laser welding).

Silicon Direct Bonding

Direct silicon, or fusion bonding, is used in the fabrication of micromechanical devices and silicon-on-insulator (SOI) substrates. Although it is mostly used to bond two silicon wafers with or without an oxide layer, it has also been used to bond different semiconductors such as GaAs and InP [5.13]. One main requirement for a successful bond is sufficient planarity (< 10 Å surface roughness and $< 5\,\mu$m bow across a 4" wafer) and cleanliness of the surfaces. In addition, thermal expansion mismatch also needs to be considered if bonding of two dissimilar materials is contemplated. The bonding procedure is as follows: The silicon- or oxide-coated silicon wafers are first thoroughly cleaned. Subsequently, the surfaces are hydrated (activated) in HF or boiling nitric acid (RCA clean also works). This renders the surfaces hydrophilic by creating an abundance of hydroxyl ions. Then the substrates are brought together in close proximity (starting from the center to avoid the void formation). The close approximation of the bonding surfaces allows the short-range attractive van der Waals forces to bring the surfaces into intimate contact on an atomic scale. Following this step, a hydrogen bond between the two hydroxyl-coated silicon wafers bonds the substrates together. These steps can be performed at room temperatures; however, in order to increase the bond strength a high temperature (800–1,200 °C) anneal is usually required. A big advantage of silicon fusion bonding is the thermal matching of the substrates.

Anodic Bonding

Silicon-glass anodic (electrostatic) bonding is another major substrate joining technique that has been used extensively for microsensor packaging and device fabrication. The main advantage of this technique is its lower bonding temperature, which is around 300–400 °C. Figure 5.17 shows the bonding setup. A glass wafer (usually Pyrex 7740 for its thermal expansion match to silicon)



Fig. 5.17 Glass-to-silicon anodic bonding setup

is placed on top of a silicon wafer, and the sandwich is heated to 300–400 °C. Subsequently, a voltage of $\sim 1{,}000\,\mathrm{V}$ is applied to the glass-silicon sandwich with the glass connected to the cathode. The bond starts immediately after the application of the voltage and spreads outward from the cathode contact point. The bond can be visually observed as a dark greyish front that expands throughout the wafer.

The bonding mechanism is as follows: During the heating period, glass sodium ions move toward the cathode and create a depletion layer at the silicon-glass interface. A strong electrostatic force is therefore created at the interface that pulls the substrates into intimate contact. The exact chemical reaction responsible for anodic bonding is not yet clear, but covalent silicon oxygen bond at the interface seems to be responsible for the bond. Silicon-to-silicon anodic bonding using sputtered or evaporated glass interlayer is also possible.

Bonding with Intermediate Layers

Various other wafer bonding techniques utilizing an intermediate layer have also been investigated [5.13]. Among the most important ones are adhesive, eutectic, and glass frit bonds. Adhesive bond using a polymer (e.g., polyimides, epoxies, thermoplast adhesives, and photoresists) in between the wafers has been used to join different wafer substrates [5.14]. Complete curing (in an oven or using dielectric heating) of the polymer before or during the bonding process prevents subsequent solvent outgas and void formation. Although reasonably high bonding strengths can be obtained, these bonds are non-hermetic and unstable over time.

In the eutectic bonding process, gold-coated silicon wafers are bonded together at temperatures greater than the silicon-gold eutectic point (363 °C, 2.85% silicon and 97.1% Au) [5.15]. This process can achieve high bonding strength and good stability at relatively low temperatures. For good bond uniformity, silicon dioxide must be removed from the silicon surface prior to the deposition of the gold. In addition, all organic contaminants on the gold surface must be removed (using UV light) prior to the bond. Pressure should also be applied in order to achieve a better contact. Although eutectic bond can be accomplished at low temperatures, achieving uniformity over large areas has proven to be challenging. More recently, localized silicon-gold eutectic bonding has been reported. In this technique, a silicon cap is bonded to another silicon wafer having a gold micro-heater (0.27 Å current for a bonding temperature of about 800 °C), Fig. 5.18 [5.16].



Fig. 5.18 Eutectic bonding with localized heating

Glass frit can also be used as an interlayer in substrate bonding. In this technique, first a thin layer of glass is deposited and pre-glazed. The glass-coated substrates are then brought into contact, and the sandwich is heated to above the glass melting temperature (typically $< 600\,°\mathrm{C}$). Like in the eutectic process, pressure must be applied for adequate contact [5.17].

Bond Characterization

Two major characterization techniques for substrate bonding evaluation are: 1) visual inspection and 2) blade test [5.12]. Once the bond has been completed, the bonding surfaces can be visually inspected for the presence of voids, cracks, and nonuniformity. The silicon-glass anodic bond interface does not require any particular imaging instrument and can be inspected with an unaided eye or under a light microscope. However, infrared imaging, X-ray photography, and ultrasonic methods are necessary for opaque substrates (mainly silicon-silicon). Although infrared transmission has some resolution limits due to its wavelength, it



Fig. 5.19 Blade test technique for the measurement of bond strength

is the most common tool in bond inspection and offers a quality technique with a simple IR source and a CCD camera.

The blade test is often performed in order to estimate the specific surface energy (and hence bond strength), Fig. 5.19. In this test, a blade is inserted between the bonded substrates and a crack is induced. The length of the crack is then measured and the specific surface energy is calculated using the following equation [5.18]:

$$g = \frac{3Et^3y^2}{8L^4} ,$$

where g is the surface energy (erg/cm^2), E is the Young's modulus of substrate (dyne/cm^2), t is the thickness of the wafer, y is the half-thickness of the blade, and L is the crack length. The crack length is usually measured using the interference fringes parallel to theblade edge under an IR light source. A semi-quantitative technique for evaluation of the bond strength is the pull test. This technique is based on using a test fixture (or tensometer) for measuring the force required to pull two bonded substrates apart. The pull test is more effective on small samples and can be used to compare different bonding techniques without the need to accurately measure the surface energy.

5.2 MEMS Fabrication Techniques

In this section, we will discuss various important MEMS fabrication techniques commonly used to build various microdevices (microsensors and microactuators) [5.6–10]. The dimensional spectrum of the microstructures that can be fabricated using these techniques span from 1 mm to 1 µm. As mentioned in the introduction, we will mostly emphasize the more important techniques and will not discuss specialized methods.

5.2.1 Bulk Micromachining

Bulk micromachining is the oldest MEMS technology and hence probably one of the more mature ones [5.8, 9]. It is currently by far the most commercially successful one, helping manufacture devices such as pressure sensors and ink-jet print heads. Although there are many different variations, the basic concept behind bulk micromachining is selective removal of the substrate (silicon, glass, GaAs, etc.). This allows the creation of various micromechanical components such as beams, plates, and membranes that can be used to fabricate a variety of sensors and actuators. The most important microfabrication techniques used in bulk micromachining are wet and dry etch and substrate bonding. Although one can use different criteria in dividing the bulk micromachining techniques into separate categories, we will use a historical time line for this purpose. Starting with the more traditional wet etching techniques, we will proceed to the more recent ones that use deep RIE and wafer bonding.

Bulk Micromachining Using Wet Etch and Wafer Bonding

The use of anisotropic wet etchants to remove silicon can be regarded as the beginning of the micromachining era. Back side etch was used to create movable structures such as beams, membranes, and plates, Fig. 5.20. Initially, the etching was timed to create a specified thickness. However, this technique proved inadequate in creating thin structures ($< 20\,\mu$m). Subsequent use of various etch stop techniques allowed the creation of thinner membranes in a more controlled fashion. As mentioned in Sect. 5.1.3, heavily doped boron regions and electrochemical bias can be used to drastically slow down the etch process and hence create controllable thickness microstructures. Figure 5.21a,b show the cross section of two piezoresistive pressure sensors fabricated using electrochemical and P^{++} etch stop techniques. The use of the P^{++} method requires the epitaxial growth of a lightly doped region on top of a P^{++} etch stop layer.



Fig. 5.20 Wet anisotropic silicon back side etch

This layer is subsequently used for the placement of piezoresistors. However, if no active component is required, one can simply use the P^{++} region to create a thin membrane, Fig. 5.21c.



Fig. 5.21a–c Wet micromachining etch stop techniques: **(a)** electrochemical with n-epi on p substrate, **(b)** P^{++} etch stop with n-epi, and **(c)** P^{++} etch stop without n-epi



Fig. 5.22 Freestanding microstructure fabrication using deep and shallow boron diffusions and EDP release

The P^{++} etch stop technique can also be used to create isolated thin silicon structures through the dissolution of the entire lightly doped region [5.19]. This technique was successfully used to fabricate silicon recording and stimulate electrodes for biomedical applications. Figure 5.22 shows the cross section of such a process that relies on deep (15–20 μm) and shallow boron (2–5 μm) diffusion steps to create microelectrodes with flexible connecting ribbon cables. An extension of this process that uses a combination of P^{++} etch stop layers and silicon-glass anodic bonding has also been developed. This process is commonly known as the dissolved wafer process and has been used to fabricate a variety of microsensors and microactuators [5.20]. Figure 5.23 shows the cross section of this process. Figure 5.24 shows an SEM photograph of a micro-accelerometer fabricated using the dissolved wafer process.

It is also possible to merge wet bulk micromachining and microelectronics fabrication processes to build mi-



Fig. 5.23a–e Dissolved wafer process sequence, **(a)** KOH etch, **(b)** deep B diffusion, **(c)** shallow B diffusion, **(d)** silicon-glass anodic bond, and **(e)** release in EDP



Fig. 5.24 SEM photograph of a micro-accelerometer fabricated using the dissolved wafer process [5.20]



Fig. 5.25 Suspended island created on a prefabricated CMOS chip using front-side wet etch and electrochemical etch stop

cromechanical components on the same substrate as the integrated circuits (CMOS, Bipolar, or BiCMOS) [5.21]. This is very appealing since it allows the integration of interface and signal processing circuitry with MEMS structures on a single chip. However, important fabrication issues such as process compatibility and yield have to be carefully considered. Among the most popular techniques in this category is the post-processing of the CMOS integrated circuits by front side etching in TMAH solutions. As mentioned previously, silicon-rich TMAH does not attack aluminum and therefore can be used to undercut microstructures in an already processed CMOS chip. Figure 5.25 shows a schematic of such a process in which front side wet etch and electrochemical etch stop have been used to produce suspended beams. This technique has been used extensively to fabricate a variety of microsensors (e.g., humidity, gas, chemical, and pressure). Figure 5.26 shows a photograph of a post-CMOS processed chemical sensor.



Fig. 5.26 Photograph of a post-CMOS processed cantilever beam resonator for chemical sensing [5.21]

Bulk Micromachining Using Dry Etch

Bulk silicon micromachining using dry etch is a very attractive alternative to the wet techniques described in the previous section. These techniques were developed in the mid-1990s, following the successful efforts to develop processes for anisotropic dry silicon etch. More recent advances in deep silicon RIE and the availability of SOI wafers with a thick top silicon layer have increased the application of these techniques. These techniques allow the fabrication of high-aspect-ratio vertical structures in isolation or along with on-chip electronics. Process compatibility with active microelectronics is less of a concern in dry methods, since many of them do not damage the circuit or its interconnect.

The most simple dry bulk micromachining technique relies on the front side undercut of microstructures using XeF_2 vapor phase etch [5.22]. As mentioned before, this, however, is an isotropic etch and, therefore, has a limited application. A combination of isotropic/anisotropic dry etch is more useful and can be used to create a variety of interesting structures. Two successful techniques using this combination are single-crystal reactive etching and metallization (SCREAM) [5.23] and post-CMOS dry release using aluminum/silicon dioxide laminate [5.24]. The first technique relies on the combination of isotropic/anisotropic dry etch to create single crystalline suspended structures. Figure 5.27 shows the cross section of the process. It starts with an anisotropic (Cl_2/BCl_3) silicon etch using an oxide mask (Fig. 5.27b). This is followed by a conformal PECVD oxide deposition (Fig. 5.27c). Subsequently, an anisotropic oxide etch is used to remove the oxide at the bottom of the



Fig. 5.27 Cross section of the SCREAM process



Fig. 5.28a–e SEM photograph of a structure fabricated using SCREAM process: **(a)** comb-drive actuator, **(b)** suspended spring, **(c)** spring support, **(d)** moving suspended capacitor plate, and **(e)** fixed capacitor plate [5.25]



Fig. 5.29 Cross section of the process flow for the post-CMOS dry microstructure fabrication

trenches leaving the sidewall oxide intact (Fig. 5.27d). At this stage, an isotropic silicon etch (SF_6) is performed that results in undercut and release of the silicon structures (Fig. 5.27e). Finally, if electrostatic actuation is desired, a metal can be sputtered to cover the top and sidewall of the microstructure and the bottom of the cavity formed below it (Fig. 5.27f). Figure 5.28 shows an SEM photograph of a comb-drive actuator fabricated using SCREAM technology.

The second dry release technique relies on the masking capability of aluminum interconnect lines in a CMOS integrated circuit to create suspended microstructures. Figure 5.29 shows the cross section of this process. As can be seen, the third level Al of a prefabricated CMOS chip is used as a mask to anisotropically etch the underlying oxide layers all the way to the silicon (CHF_3/O_2), Fig. 5.29b. This is followed by an anisotropic silicon etch to create a recess in the silicon, which will be used in the final step to facilitate the undercut and release, Fig. 5.29c. Finally, an isotropic silicon etch is used to undercut and release the structures, Fig. 5.29d. Figure 5.30 shows an SEM photograph of a comb-drive actuator fabricated using this technology.

In addition to the methods described above, recent advancements in the development of deep reactive ion etching of silicon (DRIE, see Sect. 5.1.3) have created new opportunities for dry bulk micromachining techniques (see Sect. 5.2.3). One of the most important ones uses thick silicon SOI wafers that are commercially available in various top silicon thicknesses [5.26]. Figure 5.31 shows the cross section of a typical process using DRIE and SOI wafers. The top silicon layer is patterned and etched all the way to the buried oxide, Fig. 5.31b. The oxide is subsequently removed in HF, releasing suspended single crystalline microstructures, Fig. 5.31c. In a modification of this process, the substrate can also be removed from the back side, allowing



Fig. 5.30 SEM photograph of a comb-drive actuator fabricated using aluminum mask post-CMOS dry release [5.27]



Fig. 5.31 DRIE processes using SOI wafers

easy access from both sides (this allows an easier release and prevents stiction), Fig. 5.31d.

5.2.2 Surface Micromachining

Surface micromachining is another important MEMS microfabrication technique that can be used to create movable microstructures on top of a silicon substrate [5.28]. This technique relies on the deposition of structural thin films on a sacrificial layer that is subsequently etched away, resulting in movable micromechanical structures (beams, membranes, plates, etc.). The main advantage of surface micromachining is that extremely small sizes can be obtained. In addition, it is relatively easy to integrate the micromachined structures with on-chip electronics for increased functionality. However, due to the increased surface nonplanarity with any additional layer, there is a limit to the number of layers that can be deposited. Although one of the earliest reported MEMS structures was a surface micromachined resonant gate transistor [5.29], material-related difficulties resulted in the termination of efforts in this area. In the mid-1980s, improvements in the field of thin film deposition rekindled interest in surface micromachining [5.30]. Later in the same decade, polysilicon surface micromachining was introduced, which opened the door to the fabrication of a variety of microsensors (accelerometers, gyroscopes, etc.) and microactuators (micromirrors, RF switches, etc.). In this section, we will concentrate on the key process steps involved in surface micromachining fabrication and the various materials used in the surface micromachining process. In addition, monolithic integration of CMOS with MEMS structures and 3-D surface micromachining are also discussed.

Basic Surface Micromachining Processes

The basic surface micromachining process is illustrated in Fig. 5.32. The process begins with a silicon substrate on top of which a sacrificial layer is grown and patterned, Fig. 5.32a. Subsequently, the structural material is deposited and patterned, Fig. 5.32b. As can be seen, the structural material is anchored to the substrate through the openings created in the sacrificial layer during the previous step. Finally, the sacrificial layer is removed, resulting in the release of the microstructures Fig. 5.32c. In wide structures, it is usually necessary to provide access holes in the structural layer for a fast sacrificial layer removal. It is also possible to seal microcavities cre-



Fig. 5.32 Basic surface micromachining fabrication process

ated by the surface micromachining technique [5.8, 9]. This can be done at the wafer level and is a big advantage in applications such as pressure sensors that require a sealed cavity. Figure 5.33 shows two different techniques that can be used for this purpose. In the first, following the etching of the sacrificial layer, a LPCVD dielectric layer (oxide or nitride) is deposited to cover and seal the etch holes in the structural material, Fig. 5.33a. Since the LPCVD deposition is performed at reduced pressures, a sub-atmospheric pill-box microcavity can be created. In the second technique, also called reactive sealing, the polysilicon structural material is oxidized following the sacrificial layer removal, Fig. 5.33b. If access holes are small enough, the grown oxide can seal the cavity. Due to the consumption of the oxygen during the growth process, the cavity is sub-atmospheric.

The most common sacrificial and structural materials are phosphosilicate glass (PSG) and polysilicon, respectively (low temperature oxide, or LTO, is also frequently used as the sacrificial layer). However, there are several other sacrificial/structural combinations that have been used to create a variety of surface micromachined structures. Important design issues related to the choice of the sacrificial layer are: 1) quality (pinholes, etc.), 2) ease of deposition, 3) deposition rate, 4) deposition temperature, and 5) etch difficulty and selectivity (sacrificial layer etchant should not attack the structural layer). The particular choice of material for structural layers depends on the desired properties and the specific application. Several important requirements are: 1) ease of deposition, 2) deposition rate, 3) step coverage, 4) mechanical properties (internal stress, stress gradient, Young's modulus, fracture strength, and internal damping), 5) etch selectivity, 6) thermal budget and history, 7) electrical conductivity, and 8) optical reflectivity. Two examples from the commercially available surface micromachined devices illustrate various successful sacrificial/structural combinations. Texas Instruments's deformable mirror display (DMD) spatial light modulator uses aluminum as the structural material (good optical reflectivity) and photoresist as the sacrificial layer (easy dry etch and low processing temperatures, allowing easy post-IC integration with CMOS) [5.32], Fig. 5.34. In contrast, Analog Devices's microgyroscope uses polysilicon structural material and a PSG sacrificial layer, Fig. 5.35. Two recent additions to the collection of available structural layers are poly-silicon-germanium and poly-germanium [5.33, 34]. These are intended to be a substitute for polysilicon in applications where the high polysilicon deposition temperature (around 600 °C) is forbidding (e.g., CMOS integration).



Fig. 5.33 Two sealing techniques for surface micromachined created cavities



Fig. 5.34 SEM photographs of Texas Instrument micromirror array [5.28]



Fig. 5.35 SEM photograph of Analog Devices gyroscope [5.31]

Table 5.2 Several important surface micromachined sacrificial/structural combinations

System	Sacrificial layer	Structural layer	Structural layer etchant	Sacrificial layer etchant
1	PSG or LTO	Poly-Si	RIE	Wet or vapor HF
2	Photoresist, polyimide	Metals (Al, Ni, Co, Ni-Fe)	Various metal etchants	Organic solvents, plasma O_2
3	Poly-Si	Nitride	RIE	KOH
4	PSG or LTO	Poly-Ge	H_2O_2 or RCA1	Wet or vapor HF
5	PSG or LTO	Poly-Si-Ge	H_2O_2 or RCA1	Wet or vapor HF

Unlike LPCVD polysilicon, poly-germanium (poly-Ge) and poly-silicon-germanium (poly-$Si_{1-x}Ge_x$) can be deposited at temperatures as low as 350 °C (poly-Ge deposition temperature is usually lower than poly-SiGe). Table 5.2 summarizes important surface micromachined sacrificial/structural combinations.

An important consideration in the design and processing of surface micromachined structures is the issue of stiction [5.8, 9, 35, 36]. This can happen during the release step if a wet etchant is used to remove the sacrificial layer, or during the device lifetime. The reason for stiction during release is the surface tension of the liquid etchant, which can hold the microstructure down and cause stiction. This usually happens when the structure is compliant and does not possess enough spring constant to overcome the surface tension force of the rinsing liquid (i. e., water). There are several ways one can alleviate the release-related stiction problem. These include: 1) the use of dry or vapor phase etchant, 2) the use of solvents with lower surface tension, 3) geometrical modifications, 4) CO_2 critical drying, 5) freeze drying, and 6) *self-assembled monolayer* (SAM) or organic thin-film surface modification. The first technique prevents stiction by not using a wet etchant, although in the case of vapor phase release, the condensation possibility is existent and can cause some stiction. The second method uses rinsing solvents such as methanol with a lower surface tension than water. This is usually followed by a rapid evaporation of the solvent on a hot plate. However, this technique is not optimum, and many structures still stick. The third technique is geometrical, which provides dimples in the structural layer in order to reduce the contact surface area and hence reduce the attractive force. The fourth and fifth techniques rely on the phase change (in one case CO_2 and the other butyl-alcohol), which avoids the liquid phase altogether by directly going to the gas phase. The last technique uses self-assembled monolayers or organic thin films to coat the surfaces with a hydrophobic layer. The stiction that occurs during the operating lifetime of the device (in-use stiction) is due to the condensation of moisture on the surfaces, electrostatic charge accumulation, or direct chemical bonding. Surface passivation using self-assembled monolayers or organic thin films can be used to reduce the surface energy and reduce or eliminate the capillary forces and direct chemical bonding. These organic coatings also reduce electrostatic forces if a thin layer is applied directly to the semiconductor (without the intervening oxide layer). Commonly used organic coatings include fluorinated fatty acids (Texas Instruments aluminum micromirrors), silicone polymeric layers (Analog Devices accelerometers), and siloxane self-assembled monolayers.

Surface Micromachining Integration with Active Electronics

Integration of surface micromachined structures with on-chip circuitry can increase performance and simplify packaging. However, issues related to process compatibility and yield must be carefully considered. The two most common techniques are MEMS-first and MEMS-last techniques. In the MEMS-last technique, the integrated circuit is first fabricated and surface micromachined structures are subsequently built on top of the silicon wafer. An aluminum structural layer with a photoresist sacrificial layer is an attractive combination due to the low thermal budget of the process (Texeas Instruments micromirror array). However, in applications where mechanical properties of Al are not adequate, polysilicon structural material with LTO or PSG sacrificial layer must be used. Due to the rather high deposition temperature of polysilicon, this combination requires special attention with regard to the thermal budget. For example, aluminum metallization must be avoided and substituted with refractory metals such as tungsten. This can only be achieved at a greater process complexity and lower transistor performance.

MEMS-first technique alleviates these difficulties by fabricating the microstructures at the very beginning of the process. But if the microstructures are processed first, they have to be buried in a sealed trench to eliminate the interference of microstructures with subsequent CMOS processes. Figure 5.36 shows a cross section of a MEMS-first fabrication process developed at the Sandia National Laboratory [5.37]. The process starts with a shallow anisotropic etching of trenches in a silicon substrate to accommodate the height of the polysilicon structures fabricated later on. A silicon nitride layer is then deposited to provide isolation at the bottom of the trenches. Next, several layers of polysilicon and sacrificial oxide are deposited and patterned in a standard surface micromachining process. Subsequently, the trenches are completely filled with sacrificial oxide and the wafers are planarized with chemical-mechanical polishing (this avoids complication in the following lithographic steps). After an annealing step, the trenches are sealed with a nitride cap. At this point, a standard CMOS fabrication process is performed. At the end of the CMOS process, the nitride cap is etched and the buried structures released by etching the sacrificial oxide.



Fig. 5.36 Cross section of the Sandia MEMS-first integrated fabrication process



Fig. 5.37 Silicon pin-and-sample hinge scanner with 3-D surface micromachined structures [5.38]

3-D Microstructures Using Surface Micromachining

Three-dimensional surface microstructures can be fabricated using surface micromachining. The fabrication of hinges for the vertical assembly of MEMS was a major advance toward achieving 3-D microstructures [5.39]. Optical microsytems have greatly benefited from surface micromachined 3-D structures. These microstructures are used as passive or active components (micromirror, Fresnel lens, optical cavity, etc.) on a silicon optical bench (silicon microphotonics). An example is the Fresnel lens that has been surface micromachined in polysilicon and then erected using hinge structures and locked in place using micromachined tabs, thus liberating the structure from the horizontal plane of the wafer [5.38, 40]. Various microactuators (e.g., comb drive and vibromotors) have been used to move these structures out of the silicon plane and into position. Figure 5.37 shows an SEM photograph of a bar-code micro-scanner using a silicon optical microbench with 3-D surface micromachined structures.

5.2.3 High-Aspect-Ratio Micromachining

The bulk and surface micromachining technologies presented in the previous sections fulfill the requirements of a large group of applications. Certain applications, however, require the fabrication of high-aspect-ratio structures, which is not possible with the aforementioned technologies. In this section, we describe three technologies, LIGA, HEXSIL, and HARPSS, capable of producing structures with vertical dimensions much larger than the lateral dimensions by means of X-ray lithography (LIGA) and DRIE etching (HEXSIL and HARPSS).

LIGA

LIGA is a high-aspect-ratio micromachining process that relies on X-ray lithography and electroplating (in German: *LI*thographie *G*lvanoformung *A*bformung) [5.41, 42]. We already introduced the concept of the plating-through-mask technique in Sect. 5.1.2 (see Fig. 5.10). With standard UV photolithography and photoresists, the maximum thickness achievable is on the order of a few tens of microns and the resulting metal structures show tapered walls. LIGA is a technology based on the same plating-through-mask idea, but can be used to fabricate metal structures of thicknesses ranging from a few microns to a few millimeters with almost vertical sidewalls. This is achieved using X-ray lithography and special photoresists. Due to their short wavelength, X-rays are capable of penetrating a thick photoresist layer with no scattering and defining features with lateral dimensions down to 0.2 µm (aspect ratio > 100 : 1).

The photoresists used in LIGA should comply with certain requirements, including sensitivity to X-rays, resistance to electroplating chemicals, and good adhesion to the substrate. Based on such requirements Poly-(methylmethacrylate) (PMMA) is considered an optimal choice for the LIGA process. Application of the thick photoresist on top of the substrate can be performed by various techniques such as multiple spin coating, pre-cast PMMA sheets, and plasma polymerization coating. The mask structure and materials for X-ray lithography must also comply with certain requirements. The traditional masks based on



Fig. 5.38 SEM of assembled LIGA-fabricated nickel structures [5.41]



Fig. 5.39a–e Sacrificial LIGA process: **(a)** UV lithography for sacrificial layer patterning, **(b)** X-ray lithography, **(c)** electroplating, **(d)** structure releasing, **(e)** top view of the movable structure

Part A | 5.2

glass plates with a patterned chrome thin layer are not suitable, because X-rays are not absorbed in the chromium layer and the glass plate is not transparent enough. Instead, X-ray lithography uses a silicon nitride mask with gold as the absorber material (typically formed by electroplating gold to a thickness of 10–20 µm). The nitride membrane is supported by a silicon frame, which can be fabricated using bulk micromachining techniques. Once the photoresist is exposed to the X-rays and developed, the process proceeds with the electroplating of the desired metal. Ni is the most common, although other metals and metallic compounds such as Cu, Au, NiFe, and NiW are also electroplated in LIGA processes. A good agitation of the plating solution is the key in obtaining a uniform and repeatable result during this step. A paddle plating cell, based on a windshield wiper-like device moving only 1 mm away from the substrate surface, provides extremely reproducible agitation. Figure 5.38 shows an SEM of a LIGA microstructure fabricated by electroplating nickel.



Fig. 5.40a–f HEXSIL process flow: **(a)** DRIE, **(b)** sacrificial layer deposition, **(c)** structural material deposition and trench filling, **(d)** etch structural layer from the surface, **(e)** etch sacrificial layer and pulling out of the structure, **(f)** example of a HEXSIL fabricated structure

Due to the high cost of the X-ray sources (synchrotron radiation), the LIGA technology was initially intended for the fabrication of molds that could be used many times in hot embossing or injection molding processes. However, it has been also used in many applications to directly form high-aspect-ratio metal structures on top of a substrate. A cheaper alternative to the LIGA process (with somewhat poorer qualities) called UV-LIGA, or "poor man's LIGA", has been proposed [5.43, 44]. This process uses SU-8 negative photoresists (available for spin coating at various thicknesses ranging from 1 to 500 µm) and standard contact lithography equipment. Using this technique, aspect ratios larger than 20:1 have been demonstrated. A major problem of this alternative is the removal of the SU-8 photoresist after plating. Various methods with different degrees of success have been proposed. These include: wet etching with special solvents, burning at high temperatures (600 °C), dry etching, use of a release layer, and high-pressure water jet etching.

A variation of the basic LIGA process, shown in Fig. 5.39, permits the fabrication of electrically isolated movable structures, and thus opens more possibilities for sensor and actuator design using this technology [5.45]. The so-called sacrificial LIGA (SLIGA) starts with the patterning of the seed layer. Subsequently, a sacrificial layer (e.g., titanium) is deposited and patterned. The process then proceeds as usual in standard LIGA until the last step when the sacrificial layer is removed. The electroplated structures that overlap with the sacrificial layer are released in this step.

HEXSIL

The second method for fabricating high-aspect-ratio structures, which is based on a template replication technology, is *HEXSIL* (*HEX*agonal honeycomb poly*SIL*icon) [5.46]. Figure 5.40 shows a simplified process flow. A high-aspect-ratio template is first formed in a silicon substrate using DRIE. Next, a sacrificial multilayer is deposited to allow the final release of the structures. The multilayer is composed of one or more PSG nonconformal layers to provide fast etch release (∼ 20 µm/min in 49% HF) alternated with conformal layers of either oxide or nitride to provide enough thickness for proper release of the structures. The total thickness of the sacrificial layer has to be larger than the shrinkage or elongation of the structures caused by the relaxation of the internal stress (compressive or tensile) during the release step. Otherwise, the structures will clamp themselves to the walls of the template and their retrieval will not be possible. Any material



Fig. 5.41 SEM micrograph of an angular microactuator fabricated using HEXSIL [5.48]



Fig. 5.42a–d HARPSS process flow. **(a)** Nitride deposition and patterning, DRIE etching and oxide deposition, **(b)** poly 1 deposition and etch back, oxide patterning and poly 2 deposition and patterning, **(c)** DRIE etching, **(d)** silicon isotropic etching

that can be conformally deposited and yet not damaged during the HF release step is suitable for the structural layer. Structures made of polysilicon, nitride, and electroless nickel [5.47] have been reported. Nickel can only be deposited in combination with polysilicon since a conductive surface is needed for the deposition to occur. After deposition of structural materials, a blanket etch (poly or nitride) or a mechanical lapping (nickel) is performed to remove the excess materials from the surface. Finally, a 49% HF with surfactant is used to dissolve the sacrificial layers. The process can be repeated many times using the same template, thus considerably lowering the fabrication costs. Figure 5.41 shows an SEM photograph of a microactuator fabricated using the HEXSIL process.

HARPSS

The *h*igh *a*spect *r*atio combined with *p*oly and *s*ingle-crystal *s*ilicon (*HARPSS*) technology is another technique capable of producing high-aspect-ratio, electrically isolated polycrystalline and single-crystal silicon microstructures with capacitive air gaps ranging from submicrometer to tens of micrometers [5.50]. The structures, tens to hundreds of micrometers thick, are defined by trenches etched with DRIE and filled with oxide and poly layers. The release of the microstructures is done at the end by means of a directional silicon etch followed by an isotropic etch. The small, vertical gaps and thick structures possible with this technology can be applied to the fabrication of a variety of MEMS devices, particularly inertial sensors [5.51] and RF beam resonators [5.52]. Figure 5.42 shows the process flow at the cross section of a single-crystal silicon beam resonator. The HARPSS process starts with the deposition and patterning of a silicon nitride layer that will be used to isolate the poly structure's connection pads from the substrate. High-aspect-ratio trenches (∼ 5 µm wide) are then etched into the substrate using a DRIE etcher. Next, a conformal oxide layer (LPCVD) is deposited. This layer has two functions: 1) to protect the structures during the dry etch release and 2) to define the submicrometer gap between silicon and polysilicon structures. Following the oxide deposition, the trenches are completely filled with LPCVD polysilicon. The polysilicon



Fig. 5.43 SEM photograph of a micro-gyroscope fabricated using HARPSS process [5.49]

is etched back, and the underneath oxide is patterned to provide anchor points for the structures. A second layer of polysilicon is then deposited and patterned. Finally, the structures are released using a DRIE step followed by an isotropic silicon etch through a photoresist mask that exposes only the areas of silicon substrate surrounding the structures. It should be noted that single-crystal silicon structures are not protected at the bottom during the isotropic etch. This causes the single-crystal silicon structures to be etched vertically from the bottom, and thus be shorter than the polysilicon structures. Figure 5.43 shows an SEM photograph of a micro-gyroscope fabricated using the HARPSS process.

5.3 Nanofabrication Techniques

The microfabrication techniques discussed so far were mostly geared toward fabricating devices in the 1 mm to 1 µm dimensional range (submicron dimensions being possible in certain techniques such as *HARPSS* using a dielectric sacrificial layer). Recent years have witnessed a tremendous surge of interest in fabricating sub-micro (1 µm–100 nm) and nanostructures (1–100 nm range) [5.53]. This interest arises from both practical and fundamental view points. At the more scientific and fundamental level, nanostructures provide an interesting tool in studying electrical, magnetic, optical, thermal, and mechanical properties of matter at the nanometer scale. These include important quantum mechanical phenomena (e.g., conductance quantization, band-gap modification, coulomb blockade, etc.) arising from the confinement of charged carriers in structures such as quantum wells, wires, and dots, Fig. 5.44. On the practical side, nanostructures can provide significant improvements in the performance of electronic/optical devices and sensors. In the device area, investigators have been mostly interested in fabricating nanometer-sized transistors in anticipation of technical difficulties forecasted in extending Moore's law beyond 100 nm resolution. In addition, optical sources and detectors having nanometer-sized dimensions exhibit improved characteristics unachievable in larger devices (e.g., lower threshold current, improved dynamic behavior, and improved emission line-width in quantum dot lasers). These improvements create novel possibilities for next-generation computation and communication devices. In the sensors area, shrinking dimensions beyond conventional optical lithography can provide major improvements in sensitivity and selectivity.

One can broadly divide various nanofabrication techniques into top-down and bottom-up categories. The first approach starts with a bulk or thin film material and removes selective regions to fabricate nanostructures (similar to micromachining techniques). The second method relies on molecular recognition and self-assembly to fabricate nanostructures out of smaller building blocks (molecules, colloids, and clusters). The top-down approach is an offshoot of standard lithography and micromachining techniques. On the other hand, the bottom-up approach has more of a chemical engineering and material science flavor and relies on fundamentally different principles. In this chapter, we will discuss four major nano-fabrication techniques. These include: i) e-beam and *nano-imprint* fabrication, ii) *epitaxy* and *strain engineering*, iii) scanned probe techniques, and iv) *self-assembly* and *template manufacturing*.



Fig. 5.44a–c Several important quantum confinement structures, **(a)** quantum well, **(b)** quantum wire, and **(c)** quantum dot

5.3.1 E-Beam and Nano-Imprint Fabrication

In previous sections, we discussed several important lithography techniques used commonly in MEMS and microfabrication. These include various forms of UV (regular, deep, and extreme) and X-ray lithographies. However, due to the lack of resolution (in the case of the UV), or the difficulty in manufacturing mask and radiation sources (X-ray), these techniques are not suitable for nanometer-scale fabrication. E-beam lithography is an attractive alternative technique for fabricating nanostructures [5.54]. It uses an electron beam to expose an electron-sensitive resist such as polymethyl methacrylate (PMMA) dissolved in trichlorobenzene (positive) or poly chloromethylstyrene (negative) [5.55]. The e-beam gun is usually part of a scanning electron microscope (SEM), although transmission electron microscopes (TEM) can also be used. Although electron wavelengths on the order of 1 Å can be easily achieved, electron scattering in the resist limits the attainable resolutions to > 10 nm. The beam control and pattern generation are achieved through a computer interface. E-beam lithography is serial and, hence, it has a low throughput. Although this is not a major concern in fabricating devices used in studying fundamental microphysics, it severely limits large scale nanofabrication. E-beam lithography, in conjunction with such processes as lift-off, etching, and electro-deposition, can be used to fabricate various nanostructures.

An interesting new technique that circumvents the serial and low throughput limitations of the e-beam lithography for fabricating nanostructures is the nano-imprint technology [5.56]. This technique uses an e-beam fabricated hard material master (or mold) to stamp and deform a polymeric resist. This is usually followed by a reactive ion etching step to transfer the stamped pattern to the substrate. This technique is economically superior, since a single stamp can be used repeatedly to fabricate a large number of nanostructures. Figure 5.45 shows a schematic illustration of nano-imprint fabrication. First, a hard material (e.g., silicon or SiO_2) stamp is created using e-beam lithography and reactive ion etching. Then, a resist-coated substrate is stamped, and, finally, an anisotropic RIE is performed to remove the resist residue in the stamped area. At this stage, the process is complete and one can either etch the substrate or, if metallic nanostructures are desired, evaporate the metal and perform a lift off. The resist used in nano-imprint technology can be thermal plastic, UV-curable, or thermal-curable polymer. For a thermal plastic resist (e.g., PMMA), the substrate is heated to above the glass transition temperature (T_g) of the polymer before stamping and is cooled to below T_g before the stamp is removed. Similarly, the UV and thermal-curable resists are fully cured before the stamp is separated. Nano-imprint technology resolution is limited by the mold and polymer strengths and can be as small as 10 nm. More recently, the nano-imprint technique has been used to stamp a silicon substrate in less than 250 ns using a XeCl excimer laser (308 nm) and a quartz mask (laser assisted direct imprint, LADI), Fig. 5.46 [5.57].



Fig. 5.45 Schematic illustration of nano-imprint fabrication



Fig. 5.46 Ultrafast silicon nano-imprinting using an excimer laser



Quartz

Silicon

Fig. 5.47a,b SEM micrographs of **(a)** quartz mold and **(b)** imprinted silicon surface using LADI [5.57]

Figure 5.47 shows SEM micrographs of the quartz mold and imprinted silicon substrate with 140-nm lines using LADI.

5.3.2 Epitaxy and Strain Engineering

Atomic precision deposition techniques such as molecular beam epitaxy (MBE) and metallo-organic chemical vapor deposition (MOCVD) have proven to be effective tools in fabricating a variety of quantum confinement structures and devices (quantum well lasers, photodetectors, resonant tunneling diodes, etc.) [5.58–60]. Although quantum wells and superlattices are the structures that lend themselves most easily to these techniques (see Fig. 5.44a), quantum wires and dots have also been fabricated by adding subsequent steps such as etching and selective growth. Fabrication of quantum well and superlattice structures using epitaxial growth is a mature and well developed field and, therefore, will not be discussed in this chapter. Instead, we will concentrate on quantum wire and dot nanostructure fabrication using basic epitaxial techniques [5.61, 62].

Quantum Structure Nanofabrication Using Epitaxy on Patterned Substrates

There have been several different approaches to the fabrication of quantum wires and dots using epitaxial layers. The most straight forward technique involves e-beam lithography and etching of an epitaxial grown layer (e.g., InGaAs on GaAs substrate) [5.63]. However, due to the damage and/or contamination during lithography, this method is not very suitable for active device fabrication (e.g., quantum dot lasers). Several other methods involving regrowth of epitaxial layers over nonplanar surfaces such as step-edge, cleaved-edge, and patterned substrate have been used to fabricate quantum wires and dots without the need for lithography and etching of the quantum confined structure [5.62, 64]. These nonplanar surface templates can be fabricated in a variety of ways such as etching through a mask or cleavage along crystallographic planes. Subsequent epitaxial growth on top of these structures results in a set of planes with different growth rates depending on the geometry or surface diffusion and adsorption effects. These effects can significantly enhance or limit the growth rate on certain planes, resulting in lateral patterning and confinement of deposited epitaxial layers and formation of quantum wires (in V grooves) and dots (in inverted pyramids). Figure 5.48a shows a schematic cross section of an InGaAs quantum wire fabricated in a V-groove InP. As can be seen, the growth rate on the sidewalls is lower than that of the top and bottom surfaces. Therefore, the thicker InGaAs layer at the bottom of the V-groove forms a quantum wire confined from the sides by a thinner layer with a wider bandgap. Figure 5.48b shows a quantum wire formed using epitaxial growth over a dielectric pat-



Fig. 5.48 **(a)** InGaAs quantum wire fabricated in a V-groove InP and **(b)** AlGaAs quantum wire fabricated through epitaxial growth on a masked GaAs substrate

terned planar substrate. In both of these techniques, it is relatively easy to create quantum wells. However, in order to create quantum wires and dots one still needs e-beam lithography to pattern the groove and window templates.

Quantum Structure Nanofabrication Using Strain-Induced Self-Assembly

A more recent technique for fabricating quantum wires and dots involves strain-induced *self-assembly* [5.62, 65]. The term *self-assembly* represents a process whereby a strained 2-D system reduces its energy by a transition into a 3-D morphology. The most commonly used material combination for this technique is the $In_xGa_{1-x}As/GaAs$ system, which offers a large lattice mismatch (7.2% between InAs and GaAs) [5.66,67], although recently Ge dots on Si substrate have also attracted considerable attention [5.68]. This method relies on lattice mismatch between an epitaxial grown layer and its substrate to form an array of quantum dots or wires. Figure 5.49 shows a schematic of the strain-induced self-assembly process. When the lattice constants of the substrate and the epitaxial layer differ considerably, only the first few deposited monolayers crystallize in the form of an epitaxial strained layer in which the lattice constants are equal. When a critical thickness is exceeded, a significant strain in the layer leads to the breakdown of this ordered structure and the spontaneous formation of randomly distributed islets of regular shape and similar size (usually < 30 nm in diameter). This mode of growth is usually referred to as the Stranski-Krastanow mode. The quantum dot size, separation, and height depend on the deposition parameters (i. e., total deposited material, growth rate, and temperature) and material combinations. As can be seen, this is a very convenient method to grow perfect crystalline nanostructures over a large area without any lithography and etching. One major drawback of this technique is the randomness of the quantum dot distribution. It should be mentioned that this technique can also be used to fabricate quantum wires by strain relaxation bunching at the step edges.



Fig. 5.49a–c Stranski-Krastanow growth mode, **(a)** 2-D wetting layer, **(b)** growth front roughening and breakup, and **(c)** coherent 3-D self-assembly

5.3.3 Scanned Probe Techniques

The invention of scanned probe microscopes in the 1980s revolutionized atomic-scale imaging and spectroscopy. In particular, scanning tunneling and atomic force microscopes (STM and AFM) have found widespread applications in physics, chemistry, material science, and biology. The possibility of atomic-scale manipulation, lithography, and nanomachining using such probes was considered from the beginning and has matured considerably over the past decade. In this section, after a brief introduction to scanned probe microscopes, we will discuss several important nano-lithography and machining techniques that have been used to create nanometer-sized structures.

The scanning probe microscopy (SPM) systems are capable of controlling the movement of an atomically sharp tip in close proximity to or in contact with a surface with subnanometer accuracy. Piezoelectric positioners are typically used to achieve such accuracy. High resolution images can be acquired by raster scanning the tips over a surface while simultaneously monitoring the interaction of the tip with the surface. In scanning tunneling microscope systems, a bias voltage is applied to the sample and the tip is positioned close enough to the surface, so that a tunneling current develops through the gap (Fig. 5.50a). Because this current is extremely sensitive to the distance between the tip and the surface, scanning the tip in the x-y plane while recording the tunnel current permits the mapping of the surface topography with resolution on the atomic scale. In a more common mode of operation, the amplified current signal is connected to the z-axis piezoelectric positioner through



Fig. 5.50a,b Scanning probe systems: **(a)** STM and **(b)** AFM

a feedback loop, so that the current and, therefore, the distance are kept constant throughout the scanning. In this configuration the picture of the surface topography is obtained by recording the vertical position of the tip at each x-y position.

The STM system only works for conductive surfaces because of the need to establish a tunneling current. The atomic force microscopy was developed as an alternative for imaging either conducting or nonconducting surfaces. In AFM, the tip is attached to a flexible cantilever and is brought in contact with the surface (Fig. 5.50b). The force between the tip and the surface is detected by sensing the cantilever deflection. A topographic image of the surface is obtained by plotting the deflection as a function of the x-y position. In a more common mode of operation, a feedback loop is used to maintain a constant deflection, while the topographic information is obtained from the cantilever vertical displacement. Some scanning probe systems use a combination of the AFM and STM modes, i. e., the tip is mounted in a cantilever with an electrical connection, so both the surface forces and the tunneling currents can be controlled or monitored. STM systems can be operated in ultrahigh vacuum (UHV STM) or in air, whereas *AFM* systems are typically operated in air. When a scanning probe system is operated in air, water adsorbed onto the sample surface accumulates underneath the tip, forming a meniscus between the tip and the surface. This water meniscus plays an important role in some of the scanning probe techniques described below.

Scanning Probe Induced Oxidation

Nanometer-scale local oxidation of various materials can be achieved using scanning probes operated in air and biased at a sufficiently high voltage, Fig. 5.51. Tip bias of −2 to −10 V is normally used with writing speeds of 0.1–100 µm/s in an ambient humidity of 20–40 %. It is believed that the water meniscus formed at the contact point serves as an electrolyte such that the biased tip anodically oxidizes a small region of the surface [5.70]. The most common application of this principle is the oxidation of hydrogen-passivated silicon. A dip in HF solution is typically used to passivate the silicon surfaces with hydrogen atoms. Patterns of oxide “written” on a silicon surface can be used as a mask for wet or dry etching. Ten-nm line width patterns have been successfully transferred to a silicon substrate in this fashion [5.71]. Various metals have also been locally anodized using this approach such as alu-



Fig. 5.51 SEM image of an inverted, truncated pyramid array fabricated on a silicon SOI wafer by SPM oxidation and subsequent etch in TMAH (pitch is 500 nm) [5.69]

minum or titanium [5.72]. An interesting variation of this process is the anodization of deposited amorphous silicon [5.73]. Amorphous silicon can be deposited at low temperature on top of many materials. The deposited silicon layer can be patterned and used as, for example, the gate of a 0.1 μm CMOS transistor [5.74], or it can be used as a mask to pattern an underlying film. The major drawback of this technique is poor reproducibility due to tip wear during the anodization. However, using AFM in noncontact mode has overcome this problem [5.70].

Scanning Probe Resist Exposure and Lithography

Electrons emitted from a biased SPM tip can be used to expose a resist the same way e-beam lithography does (Fig. 5.52) [5.74]. Various systems have been used for this lithographic technique. These include constant current STM, noncontact AFM, and AFM with constant tip-resist force and constant current. The systems using AFM cantilevers have the advantage of performing imaging and alignment tasks without exposing the resist. Resists well characterized for e-beam lithography (e.g., PMMA or SAL601) have been used with scanning probe lithography to achieve reliable sub-100-nm lithography. The procedure for this process is as follows. The wafers are cleaned and the native oxide (in the case of silicon or poly) is removed with a HF dip. Subsequently, 35–100 nm-thick resist is spin-coated on top of the surface. The exposure is done by moving the SPM tip over the surface while applying a bias voltage high enough to produce an emission of electrons from the tip (a few tens of volts). Development of the resist is performed in standard solutions following the exposure. Features below 50 nm in width have been achieved with this procedure.



Fig. 5.52 Scanning probe lithography with organic resist



Fig. 5.53 Schematic representation of the dip-pen nanolithography working principle

Dip-Pen Nanolithography

In dip-pen nanolithography (DPN), the tip of an AFM operated in air is "inked" with a chemical of interest and brought into contact with a surface. The ink molecules flow from the tip onto the surface as with a fountain pen. The water meniscus that naturally forms between the tip and the surface enables the diffusion and transport of the molecules, as shown in Fig. 5.53. Inking can be done by dipping the tip in a solution containing a small concentration of the molecules followed by a drying step (e.g., blowing dry with compressed difluoroethane). Line widths down to 12 nm with spatial resolution of 5 nm have been demonstrated with this technique [5.75]. Species patterned with DPN include conducting polymers, gold, dendrimers, DNA, organic dyes, antibodies, and alkanethiols. Alkanethiols have also been used as an organic monolayer mask to etch a gold layer and subsequently etch the exposed silicon substrate.

Other Scanning Probe Nanofabrication Techniques

A great variety of nanofabrication techniques using scanning probe systems have been demonstrated. Some of these are proof of concept demonstrations, and their utility as a viable and repeatable fabrication process has yet to be evaluated. For example, a substrate can be mechanically machined using STM/AFM tips acting as plows or engraving tools [5.76]. This can be used to directly create structures in the substrate, although it is more commonly used to pattern a resist for a subsequent etch, liftoff, or electro-deposition step. Mechanical nanomachining with SPM probes can be facilitated by heating the tip above the glass transition of a polymeric substrate material. This approach has been applied to SPM-based high-density data storage in polycarbonate substrates [5.77].

Electric fields strong enough to induce the emission of atoms from the tip can be easily generated by applying voltage pulses above 3 V. This phenomenon has been used to transfer material from the tip to the surface and vice versa. Ten- to 20-nm mounds of metals such as Au, Ag, or Pt have been deposited or removed from a surface in this fashion [5.78]. The same approach has been used to extract single atoms from a semiconductor surface and re-deposit them elsewhere [5.79]. Manipulation of nanoparticles, molecules, and single atoms on top of a surface has also been achieved by simply pushing or sliding them with the SPM tip [5.80]. Metals can also be locally deposited by the STM chemical vapor deposition technique [5.81]. In this technique, a precursor organometallic gas is introduced in the STM chamber. A voltage pulse applied between the tip and the surface dissociates the precursor gas into a thin layer of metal. Local electro-chemical etch [5.82] and electro-deposition [5.83] are also possible using SPM systems. A droplet of suitable solution is first placed on the substrate. Then the STM tip is immersed into the droplet and a voltage is applied. In order to reduce Faradaic currents the tip is coated with wax such that only the very end is exposed to the solution. Sub-100-nm feature size has been achieved using this technique.

Using a single tip to serially produce the desired modification in a surface leads to very slow fabrication processes that are impractical for mass production. Many of the scanning probe techniques developed thus far, however, could also be performed by an array of tips, which would increase their throughput and make them more competitive compared with other parallel nanofabrication processes. This approach has been demonstrated for imaging, lithography [5.84], and data storage [5.85] using both 1-D and 2-D arrays of scanning probes. With the development of larger arrays with individual control of force, vertical position, and current advances, we might see these techniques become standard fabrication processes in the industry.

5.3.4 Self-Assembly and Template Manufacturing

Self-assembly is a nanofabrication technique that involves aggregation of colloidal nano-particles into the final desired structure [5.86]. This aggregation can be either spontaneous (entropic) and due to the thermodynamic minima (energy minimization) constraints, or chemical and due to the complementary binding of organic molecules and supramolecules (molecular self-assembly) [5.87]. Molecular self-assembly is one of the most important techniques used in biology for the development of complex functional structures. Since these techniques require that the target structures be thermodynamically stable, they tend to produce structures that are relatively defect-free and self-healing. Self-assembly is by no means limited to molecules or the nano-domain and can be carried out on just about any scale, making it a powerful bottom-up assembly and manufacturing method (multiscale ordering). Another attractive feature of this technique relates to the possibility of combining self-assembly properties of organic molecules with the electronic, magnetic, and photonic properties of inorganic components. *Template manufacturing* is another bottom-up technique that utilizes material deposition (electroplating, CVD, etc.) in nano-templates in order to fabricate nanostructures. The nano-templates used in this technique are usually prepared using self-assembly techniques. In the following sections, we will discuss various important self-assembly and template manufacturing techniques currently under heavy investigation.

Physical and Chemical Self-Assembly

The central theme behind the self-assembly process is spontaneous (physical) or chemical aggregation of colloidal nano-particles [5.88]. Spontaneous self-assembly exploits the tendency of mono-dispersed nano- or sub-micro colloidal spheres to organize into a face-centered cubic (FCC) lattice. The force driving this process is the desire of the system to achieve a thermodynamically stable state (minimum free energy). In addition to spontaneous thermal self-assembly, gravitational, convective, and electrohydrodynamic forces can also be used to induce aggregation into complex 3-D structures. Chemical self-assembly requires the attachment of a single molecular organic layer (*self-assembled monolayer*, or *SAM*) to the colloidal particles (organic or inorganic) and subsequent self-assembly of these components into a complex structure using molecular recognition and binding.

Physical Self-Assembly. This is an entropic-driven method that relies on the spontaneous organization of colloidal particles into a relatively stable structure through non-covalent interactions. For example, colloidal polystyrene spheres can be assembled into a 3-D structure on a substrate that is held vertically in the colloidal solution, Fig. 5.54 [5.89, 90]. Upon the



Fig. 5.54 Colloidal particle self-assembly onto solid substrates upon drying in vertical position



Fig. 5.55 Cross-sectional SEM image of a thin planar opal silica template (spheres 855 nm in diameter) assembled directly on a Si wafer [5.89]

evaporation of the solvent, the spheres aggregate into a hexagonal close packed (HCP) structure. The interstitial pore size and density are determined by the polymer sphere size. The polymer spheres can be etched into smaller sizes after forming the HCP arrays, thereby altering the template pore separations [5.91]. This technique can fabricate large patterned areas in a quick, simple, and cost-effective way. A classic example is the natural assembly of on-chip silicon photonic bandgap crystals [5.89], which are capable of reflecting the light arriving from any direction in a certain wavelength range [5.92]. In this method, a thin layer of silica colloidal spheres is assembled on a silicon substrate. This is achieved by placing a silicon wafer vertically in a vial containing an ethanolic suspension of silica spheres. A temperature gradient across the vial aids the flow of silica spheres. Figure 5.55 shows the cross-sectional SEM image of a thin planar opal template assembled directly on a Si wafer from 855 nm spheres. Once such a template is prepared, LPCVD can be used to fill the interstitial spaces with Si, so that the high refractive index of silicon provides the necessary bandgap.

One can also deposit colloidal particles into a patterned substrate (template-assisted self-assembly, TASA) [5.93, 94]. This method is based on the principle that when aqueous dispersion of colloidal particles is allowed to dewet from a solid surface that is already patterned, the colloidal particles are trapped by the recessed regions and assembled into aggregates of shapes and sizes determined by the geometric confinement provided by the template. The patterned arrays of templates can be fabricated using conventional contact-mode photolithography, which gives control over the shape and dimensions of the templates, thereby allowing the assembly of complex structures from colloidal particles. The cross-sectional view of a fluidic cell used in TASA is shown in Fig. 5.56. The fluidic cell has two parallel glass substrates to confine the aqueous dispersion of the colloidal particles. The surface of the bottom substrate is patterned with a 2-D array of templates. When the aqueous dispersion is allowed to slowly dewet across the cell, the capillary force exerted on the liquid pushes the colloidal spheres across the surface of the bottom substrate until they are physically trapped by the templates. If the concentration of the colloidal dispersion is high enough, the template will be filled by the maximum number of colloidal particles determined by the geometrical confinement. This method can be used to fabricate a variety of polygonal and polyhedral aggregates that are difficult to generate [5.95].



Fig. 5.56 A cross-sectional view of the fluidic cell used for template-assisted self-assembly

Chemical Self-Assembly. Organic and supramolecular SAMs play a critical role in colloidal particle self-assembly. SAMs are robust organic molecules that are chemically adsorbed onto solid substrates [5.96]. Most often, they have a hydrophilic (polar) head that can be bonded to various solid surfaces and a long, hydrophobic (nonpolar) tail that extends outward. SAMs are formed by the immersion of a substrate in a dilute solution of the molecule in an organic solvent. The resulting film is a dense organization of molecules arranged to expose the end group. The durability of a SAM is highly dependent on the effectiveness of the anchoring to the surface of the substrate. SAMs have been widely studied, because the end group can be functionalized to form precisely arranged molecular arrays for various applications ranging from simple, ultrathin insulators and lubricants to complex biological sensors. Chemical self-assembly uses organic or supramolecular SAMs as the binding and recognition sites for fabricating complex 3-D structures from colloidal nano-particles. Most commonly used organic monolayers include: 1) organosilicon compounds on glass and native surface oxide layer of silicon, 2) alkanethiols, dialkyl disulfides, and dialkyl sulfides on gold, 3) fatty acids on alumina and other metal oxides, and 4) DNA.

Octadecyltrichlorosilane (OTS) is the most common organosilane used in the formation of SAMs, mainly because of the fact that it is simple, readily available, and forms good, dense layers [5.97, 98]. Alkyltrichlorosilane monolayers can be prepared on clean silicon wafers whose surface is SiO_2 (with almost 5×10^{14} SiOHgroups/cm^2). Figure 5.57 shows the schematic representation of the formation of alkylsiloxane monolayers by adsorption of alkyltrichlorosilanes from solution onto Si/SiO_2 substrates. Since the silicon-chloride bond is susceptible to hydrolysis, a limited amount of water has to be present in the system in order to obtain good quality monolayers. Monolayers made of methyl- and vinyl-terminated alkylsilanes are autophobic to the hydrocarbon solution and hence emerge uniformly dry from the solution, whereas monolayers made of ester-terminated alkylsilanes emerge wet from the solution used in their formation. The disadvantage of this method is that if the alkyltrichlorosilane in the solvent adhering to the substrate is exposed to water, a cloudy film is deposited on the surface due to formation of a gel of polymeric siloxane.



Fig. 5.57 **(a)** Alkylsiloxane formed from the adsorption of alkyltrichlorosilane on Si/SiO_2 substrates. **(b)** Schematic representation of the process

Another important organic SAM system is the alkanethiols ($X(CH_2)_nSH$, where X is the endgroup) on gold [5.96, 99–101]. A major advantage of using gold as the substrate material is that it does not have a stable oxide, and thus it can be handled in ambient conditions. When a fresh, clean, hydrophilic gold substrate is immersed (several minutes to several hours) into a dilute solution (10^{-3} M) of the organic sulfur compound (alkanethiols) in an inorganic solvent, a close-packed, oriented monolayer can be obtained. Sulfur is used as the head group, because of its strong interaction with gold substrate (44 kcal/mol), resulting in the formation of a close-packed, ordered monolayer. The end group of alkanethiol can be modified to render hydrophobic or hydrophilic properties to the adsorbed layer. Another method for depositing alkanethiol SAM is soft-lithography. This technique is based on inking a PDMS stamp with alkanethiol and its subsequent transfer to planar and nonplanar substrates. Alkanethiol functionalized surfaces (planar, nonplanar, spherical) can also be used to self-assemble a variety of intricate 3-D structures [5.102].

Carboxylic acid derivatives self-assemble on surfaces (e.g., glass, Al_2O_3, and Ag_2O) through an acid-base reaction, giving rise to monolayers of fatty acids [5.103]. The time required for the formation of a complete monolayer increases with decreased concentration. A higher concentration of carboxylic acid is required to form a monolayer on gold compared to Al_2O_3. This is due to differences in the affinity of the COOH groups (more affinity to Al_2O_3 and glass than gold) and also the surface concentration of the salt-forming oxides in the two substrates. In the case of amorphous metal oxide surfaces, the chemisorption of alkanoic acids is not unique. For example, on Ag_2O the carboxylate two oxygen atoms bind to the substrate in a nearly symmetrical manner, resulting in ordered monolayers with a chain tilt angle from the surface normally of 15° to 25°. But on CuO and Al_2O_3, the oxygen atoms bind themselves symmetrically and the chain tilt angle is close to 0°. The structure of the monolayers is thus a balance of the various interactions taking place in the polymer chains.

Deoxyribonucleic acid (DNA), the framework on which all life is built, can be used to self-assemble nanomaterials into useful macroscopic aggregates that display a number of desired physical properties [5.104]. DNA consists of two strands, which are coiled around each other to form a double helix. When the two strands are uncoiled, singular strands of nucleotides are left. These nucleotides consist of a sugar (pentose ring) a phosphate (PO_4), and a nitrogenous base. The order and architecture of these components are essential for the proper structure of a nucleotide. There are typically four nucleotides found in DNA: Adenine (A), Guanine (G), Cytosine (C), and Thyamine (T). A key property of the DNA structure is that the described nucleotides bind specifically to another nucleotide when arranged in the two-strand double helix (A to T and C to G). This specific bonding capability can be used to assemble nanophase material and nano-structures [5.105]. For example, nucleotide functionalized nano-gold particles have been assembled into complex 3-D structures by attaching DNA strands to the gold via an enabler or linker [5.106]. In a separate work, DNA was used to assemble nanoparticles into macroscopic materials. This method uses alkane dithiol as the linker molecule to connect the DNA template to the nanoparticle. The thiol groups at each end of the linker molecule covalently attach themselves to the colloidal particles to form aggregate structures [5.107].

Template Manufacturing

Template manufacturing refers to a set of techniques that can be used to fabricate 3-D organic or inorganic structures from a nano-template. These templates differ in material, pattern, feature size, overall template size, and periodicity. Although nano-templates can be fabricated using e-beam lithography, the serial nature of this technique prohibits its widespread application. Self-assembly is the preferred technique that can produce large-area nano-templates in a massively parallel fashion. Several nano-templates have been investigated for use in template manufacturing. These include polymer colloidal spheres, alumina membranes, and nuclear-track etched membranes. Colloidal spheres can be deposited in a regular 3-D array using the techniques described in the previous section (see Figs. 5.54–5.56). Porous aluminum oxide membranes can be fabricated by the anodic oxidation of aluminum [5.108]. The oxidized film consists of columnar arrays of hexagonal, close-packed pores with a separation comparable to the pore size. By controlling the electrolyte species, temperature, anodizing voltage and time, different pore sizes, density and height can be obtained. The pore size and depth can further be adjusted by etching the oxide in an appropriate acid. Templates of porous polycarbonate or mica membranes can be fabricated by nuclear-track etched membranes [5.109]. This technique is based on the passage of high-energy decay fragments from a radioactive source through a dielectric material. The particles leave behind chemically active damaged tracks that subsequently can be etched to create pores throughout the thickness of the membrane [5.110, 111]. Unlike the other methods, the pore separation and, hence, the pore density are independent of the pore size. The pore density is only determined by the irradiation process.

Following template fabrication, the interstitial spaces (in the case of colloidal spheres) or pores (in the case of alumina and polycarbonate membranes) in the template are filled with the desired material [5.91, 112]. This can be done using a variety of deposition techniques such as electroplating and CVD. The final structure can be a composite of nano-template and deposited mater-


$A1_2O_3$ membrane after Ag evaporation and initial Ag electro-deposition
1. $Au^+ + e^- \rightarrow Au$ × Coulomb (C)
2. $Ag^+ + e^- \rightarrow Ag$ × C
3. $Au^+ + e^- \rightarrow Au$ 2× C
4. $Ag^+ + e^- \rightarrow Ag$ × C
5. $Au^+ + e^- \rightarrow Au$ × C
1. $Au^+ + e^- \rightarrow Au$ × C
2. $Ag^+ + e^- \rightarrow Ag$ 2× C
3. $Au^+ + e^- \rightarrow Au$ × C
1. Ag film dissolution with HNO_3
2. $A1_2O_3$ dissolution with NaOH

Fig. 5.58 Synthesis of nano-bar-code particles



Fig. 5.59 **(a)** Optical and **(b)** FE-SEM images of Au-Ag multistripe particle 5.116

ial, or the template can be selectively etched, resulting in an air-filled 3-D complex structure. For example, nickel [5.111], iron [5.113], and cobalt [5.114] nanowires have been electrochemically grown into porous template matrices. Three-dimensional photonic crystals have been fabricated by electrochemical deposition of CdSe and silicon into polystyrene and silica colloidal assembly templates [5.89, 115]. An interesting example of template-assisted manufacturing is the synthesis of nanometer metallic bar codes [5.116]. These nano-bar codes are prepared by the electrochemical reduction of metallic ions into the pores of an aluminum oxide membrane followed by their release through etching of the template [5.117–119]. This procedure is schematically illustrated in Fig. 5.58. A back-side silver film is used as the working electrode for the reduction of metallic ions (silver and gold in this case) from solution. Up to seven different metallic segments as short as 10 nm and as long as several micrometers with 13 distinguishable stripes have been fabricated using this technique. Optical reflectivity is used to read out the striping pattern encoded in the metal particles [5.116]. Figure 5.59 shows optical and field emission scanning electron microscope images of a Au-Ag multistripe nano-bar code (Ag stripes ranging in length from 60 to 240 nm separated by Au segments of 550 nm). These coded nano-particles can be used in fluorescence and mass-spectrometry-based assays, enabling a wide variety of bioanalytical measurements.

References

5.1 S. A. Campbell: *The Science and Engineering of Microelectronic Fabrication* (Oxford Univ. Press, New York 2001)

5.2 C. J. Jaeger: *Introduction to Microelectronic Fabrication* (Prentice Hall, New Jersey 2002)

5.3 J. D. Plummer, M. D. Deal, P. B. Griffin: *Silicon VLSI Technology* (Prentice Hall, New Jersey 2000)

5.4 J. E. Bjorkholm: EUV lithography: the successor to optical lithography, Intel Technol. J. **2** (1998) 1–8

5.5 J. L. Vossen: *Thin Film Processes* (Academic Press, New York 1976)

5.6 M. Gad-el-Hak (Ed.): *The MEMS Handbook* (CRC Press, Boca Raton 2002)

5.7 T.-R. Hsu: *MEMS and Microsystems Design and Manufacture* (McGraw-Hill, New York 2002)

5.8 G. T. A. Kovacs: *Micromachined Transducers Sourcebook* (McGraw-Hill, New York 1998)

5.9 G. T. A. Kovacs, N. I. Maluf, K. A. Petersen: Bulk micromachining of silicon, Proc. IEEE **86**(8) (1998) 1536–1551

5.10 P. Rai-Choudhury (Ed.): *Handbook of Microlithography, Micromachining and Microfabrication* (SPIE, Bellingham 1997)

5.11 T. J. Cotler, M. E. Elta: Plasma-etch technology, IEEE Circuits & Devices Mag. **6** (1990) 38–43

5.12 U. Gosele, Q. Y. Tong: Semiconductor wafer bonding, Annu. Rev. Mater. Sci. **28** (1998) 215–241

5.13 Q. Y. Tong, U. Gosele: *Semiconductor Wafer Bonding: Science and Technology* (Wiley, New York 1999)

5.14 F. Niklaus, P. Enoksson, E. Kalveston, G. Stemme: Void-free full-wafer adhesive bonding, J. Micromech. Microeng. **11** (2000) 100–107

5.15 C. A. Harper: *Electronic Packaging and Interconnection Handbook* (McGraw-Hill, New York 2000)

5.16 Y. T. Cheng, L. Lin, K. Najafi: Localized silicon fusion and eutectic bonding for MEMS fabrication and packaging, J. Microelectromech. Syst. **9**(1) (2000) 3–8

5.17 W. H. Ko, J. T. Suminto, G. J. Yeh: Bonding techniques for microsensors. In: *Micromachining and Micropackaging for Transducers* (Elsevier, Amsterdam 1985)

5.18 W. P. Maszara, G. Goetz, A. Caviglia, J. B. McKitterick: Bonding of silicon wafers for silicon-on-insulator, J. Appl. Phys. **64**(10) (1988) 4943–4950

5.19 K. Najafi, K. D. Wise, T. Mochizuki: A high-yield IC-compatible multichannel recording array, IEEE Trans. Electron Devices **32** (1985) 1206–1211

5.20 A. Selvakumar, K. Najafi: A high-sensitivity *z* axis capacitive silicon microaccelerometer with a tor-

tional suspension, J. Microelectromech. Syst. **7** (1998) 192–200
5.21 H. Baltes, O. Paul, O. Brand: Micromachined thermally based CMOS microsensors, Proc. IEEE **86**(8) (1998) 1660–1678
5.22 B. Eyre, K. S. J. Pister, W. Gekelman: Multi-axis microcoil sensors in standard CMOS, Proc. SPIE Conf. Micromachined Devices and Components, Austin 1995, 183–191
5.23 K. A. Shaw, Z. L. Zhang, N. C. MacDonnald: SCREAM: a single mask single-crystal silicon process for microelectromechanical structures, Proc. IEEE Workshop Micro Electro Mechanical Systems, Fort Lauderdale 1993, 155–160
5.24 G. K. Fedder, S. Santhanam, M. L. Reed, S. C. Eagle, D. F. Guillo, M. S. C. Lu, L. R. Carley: Laminated high-aspect-ratio microstructures in a conventional CMOS process, Proc. IEEE Workshop Micro Electro Mechanical Systems, San Diego 1996, 13–18
5.25 N. C. MacDonald: SCREAM MicroElectroMechanical Systems, Microelectron. Eng. **32** (1996) 51–55
5.26 B. P. Van Drieenhuizen, N. I. Maluf, I. E. Opris, G. T. A. Kovacs: Force-balanced accelerometer with mG resolution fabricated using silicon fusion bonding and deep reactive ion etching, Proc. Int. Conf. Solid-State Sensors and Actuators, Chicago 1997, 1229–1230
5.27 X. Huikai, L. Erdmann, Z. Xu, K. J. Gabriel, G. K. Fedder: Post-CMOS processing for high-aspect-ratio integrated silicon microstructures, J. Microelectromech. Syst. **11** (2002) 93–101
5.28 J. M. Bustillo, R. S. Muller: Surface micromachining for microelectromechanical systems, Proc. IEEE **86**(8) (1998) 1552–1574
5.29 H. C. Nathanson, W. E. Newell, R. A. Wickstrom, J. R. Davis: The resonant gate transistor, IEEE Trans. Electron Devices **14** (1967) 117–133
5.30 R. T. Howe, R. S. Muller: Polycrystalline silicon micromechanical beams, Proc. Electrochem. Soc. Spring Meeting, Montreal 1982, 184–185
5.31 J. A. Geen, S. J. Sherman, J. F. Chang, S. R. Lewis: Single-chip surface-micromachined integrated gyroscope with 50 degrees/hour root Allan variance, IEEE J. Solid-State Circuits **37** (2002) 1860–1866
5.32 P. F. Van Kessel, L. J. Hornbeck, R. E. Meier, M. R. Douglass: A MEMS-based projection display, Proc. IEEE **86**(8) (1998) 1687–1704
5.33 A. E. Franke, D. Bilic, D. T. Chang, P. T. Jones, R. T. Howe, G. C. Johnson: Post-CMOS integration of germanium microstructures, Proc. Micro Electro Mechanical Systems, Orlando 1999, 630–637
5.34 S. Sedky, P. Fiorini, M. Caymax, S. Loreti, K. Baert, L. Hermans, R. Mertens: Structural and mechanical properties of polycrystalline silicon germanium for micromachining applications, J. Microelectromech. Syst. **7** (1998) 365–372
5.35 N. Tas, T. Sonnenberg, H. Jansen, R. Legtenberg, M. Elwenspoek: Stiction in surface micromachining, J. Micromech. Microeng. **6** (1996) 385–397
5.36 R. Maboudian, R. T. Howe: Critical review: adhesion in surface micromechanical structures, J. Vac. Sci. Technol. B **15**(1) (1997) 1–20
5.37 J. H. Smith, S. Montague, J. J. Sniegowski, J. R. Murray, P. J. McWhorter: Embedded micromechanical devices for the monolithic integration of MEMS with CMOS, Proc. Int. Electron Devices Meeting, Washington 1995, 609–612
5.38 R. S. Muller, K. Y. Lau: Surface-micromachined microoptical elements and systems, Proc. IEEE **86**(8) (1998) 1705–1720
5.39 K. S. J. Pister, M. W. Judy, S. R. Burgett, R. S. Fearing: Microfabricated hinges: 1 mm vertical features with surface micromachining, Proc. 6th Int. Conf. Solid-State Sensors and Actuators, San Francisco 1991, 647–650
5.40 L. Y. Lin, S. S. Lee, M. C. Wu, K. S. J. Pister: Micromachined integrated optics for free space interconnection, Proc. IEEE MicroElectroMechanical Systems Workshop, Amsterdam 1995, 77–82
5.41 H. Guckel: High-aspect-ratio micromachining via deep X-ray lithography, Proc. IEEE **86**(8) (1998) 1586–1593
5.42 E. W. Becker, W. Ehrfeld, P. Hagmann, A. Maner, D. Munchmeyer: Fabrication of microstructures with high aspect ratios and great structural heights by synchrotron radiation lithography, galvanoforming, and plastic molding (LIGA process), Microelectron. Eng. **4** (1986) 35–56
5.43 K. Y. Lee, N. LaBianca, S. A. Rishton, S. Zolgharnain, J. D. Gelorme, J. Shaw, T. H. P. Chang: Micromachining applications of a high resolution ultra-thick photoresist, J. Vac. Sci. & Technol. B **13** (1995) 3012–3016
5.44 K. Roberts, F. Williamson, G. Cibuzar, L. Thomas: The fabrication of an array of microcavities utilizing SU-8 photoresist as an alternative 'LIGA' technology, Proc. Thirteenth Biennial University/Government/Industry Microelectronics Symposium, Minnesota 1999 (IEEE, Piscataway 1999) 139–141
5.45 C. Burbaum, J. Mohr, P. Bley, W. Ehrfeld: Fabrication of capacitive acceleration sensors by the LIGA technique, Sensors & Actuators A **27** (1991) 559–563
5.46 C. G. Keller, R. T. Howe: Hexsil bimorphs for vertical actuation, Digest of Technical Papers 8th Int. Conf. Solid-State Sensors and Actuators and Eurosensors IX, Stockholm 1995, 99–102
5.47 C. G. Keller, R. T. Howe: Nickel-filled hexsil thermally actuated tweezers, Digest of Technical Papers 8th Int. Conf. Solid-State Sensors and Actuators and Eurosensors IX, Stockholm 1995, 376–379
5.48 D. A. Horsley, M. B. Cohn, A. Singh, R. Horowitz, A. P. Pisano: Design and fabrication of an angular microactuator for magnetic disk drives, J. Microelectromech. Syst. **7** (1998) 141–148

5.49 N. Yazdi, F. Ayazi, K. Najafi: Micromachined inertial sensors, Proc. IEEE **86** (1998) 1640–1659
5.50 F. Ayazi, K. Najafi: High aspect-ratio combined poly and single-crystal silicon (HARPSS) MEMS technology, J. Microelectromech. Syst. **9** (2000) 288–294
5.51 F. Ayazi, K. Najafi: A HARPSS polysilicon vibrating ring gyroscope, J. Microelectromech. Syst. **10** (2001) 169–179
5.52 Y. S. No, F. Ayazi: The HARPSS process for fabrication of nano-precision silicon electromechanical resonators, Proc. 2001 1st IEEE Conference on Nanotechnology, 2001, 489–494
5.53 G. Timp: *Nanotechnology* (Springer, New York 1998)
5.54 P. Rai-Choudhury (Ed.): *Handbook of Microlithography, Micromachining and Microfabrication* (SPIE, Bellingham 1997)
5.55 L. Ming, C. Bao-qin, Y. Tian-Chun, Q. He, X. Qiuxia: The sub-micron fabrication technology, Proc. 6th Int. Conf. Solid-State and Integrated-Circuit Technol. (IEEE, 2001) 452–455
5.56 S. Y. Chou: Nano-imprint lithography and lithographically induced self-assembly, MRS Bulletin **26** (2001) 512–517
5.57 S. Y. Chou, C. Keimel, J. Gu: Ultrafast and direct imprint of nanostructures in silicon, Nature **417** (2002) 835–837
5.58 M. A. Herman: *Molecular Beam Epitaxy: Fundamentals and Current Status* (Springer, New York 1996)
5.59 J. S. Frood, G. J. Davis, W. T. Tsang: *Chemical Beam Epitaxy and Related Techniques* (Wiley, New York 1997)
5.60 S. Mahajan, K. S. Sree Harsha: *Principles of Growth and Processing of Semiconductors* (McGraw-Hill, New York 1999)
5.61 S. Kim, M. Razegi: Advances in quantum dot structures. In: *Processing and Properties of Compound Semiconductors*, ed. by R. Willardson, H. S. Navawa (Academic Press, New York 2001)
5.62 D. Bimberg, M. Grundmann, N. N. Ledentsov: *Quantum Dot Heterostructures* (Wiley, New York 1999)
5.63 G. Seebohm, H. G. Craighead: Lithography and patterning for nanostructure fabrication. In: *Quantum Semiconductor Devices and Technologies*, ed. by T. P. Pearsall (Kluwer, Boston 2000)
5.64 E. Kapon: Lateral patterning of quantum well heterostructures by growth on nonplanar substrates. In: *Epitaxial Microstructures*, ed. by A. C. Gossard (Academic Press, New York 1994)
5.65 F. Guffarth, R. Heitz, A. Schliwa, O. Stier, N. N. Ledentsov, A. R. Kovsh, V. M. Ustinov, D. Bimberg: Strain engineering of self-organized InAs quantum dots, Phys. Rev. B **64** (2001) 085305(1)–085305(7)
5.66 M. Sugawara: *Self-Assembled InGaAs/GaAs Quantum Dots* (Academic Press, New York 1999)
5.67 B. C. Lee, S. D. Lin, C. P. Lee, H. M. Lee, J. C. Wu, K. W. Sun: Selective growth of single InAs quantum dots using strain engineering, Appl. Phys. Lett. **80** (2002) 326–328
5.68 K. Brunner: Si/Ge nanostructures, Rep. Prog. Phys. **65** (2002) 27–72
5.69 F. S. S. Chien, W. F. Hsieh, S. Gwo, A. E. Vladar, J. A. Dagata: Silicon nanostructures fabricated by scanning probe oxidation and tetra-methyl ammonium hydroxide etching, J. Appl. Phys. **91** (2002) 10044–10050
5.70 M. Calleja, J. Anguita, R. Garcia, K. Birkelund, F. Perez-Murano, J. A. Dagata: Nanometer-scale oxidation of silicon surfaces by dynamic force microscopy: reproducibility, kinetics and nanofabrication, Nanotechnology **10** (1999) 34–38
5.71 E. S. Snow, P. M. Campbell, F. K. Perkins: Nanofabrication with proximal probes, Proc. IEEE **85** (1997) 601–611
5.72 H. Sugimura, T. Uchida, N. Kitamura, H. Masuhara: Tip-induced anodization of titanium surfaces by scanning tunneling microscopy: a humidity effect on nanolithography, Appl. Phys. Lett. **63** (1993) 1288–1290
5.73 N. Kramer, J. Jorritsma, H. Birk, C. Schonenberger: Nanometer lithography on silicon and hydrogenated amorphous silicon with low energy electrons, J. Vac. Sci. & Technol. B **13** (1995) 805–811
5.74 H. T. Soh, K. W. Guarini, C. F. Quate: *Scanning Probe Lithography* (Kluwer, Boston 2001)
5.75 C. A. Mirkin: Dip-pen nanolithography: automated fabrication of custom multicomponent, sub-100 nanometer surface architectures, MRS Bulletin **26** (2001) 535–538
5.76 L. L. Sohn, R. L. Willett: Fabrication of nanostructures using atomic-force-microscope-based lithography, Appl. Phys. Lett. **67** (1995) 1552–1554
5.77 H. J. Mamin, B. D. Terris, L. S. Fan, S. Hoen, R. C. Barrett, D. Rugar: High-density data storage using proximal probe techniques, IBM J. Res. & Dev. **39** (1995) 681–699
5.78 K. Bessho, S. Hashimoto: Fabricating nanoscale structures on Au surface with scanning tunneling microscope, Appl. Phys. Lett. **65** (1994) 2142–2144
5.79 I. W. Lyo, P. Avouris: Field-induced nanometer-to atomic-scale manipulation of silicon surfaces with the STM, Science **253** (1991) 173–176
5.80 M. F. Crommie, C. P. Lutz, D. M. Eigler: Confinement of electrons to quantum corrals on a metal surface, Science **262** (1993) 218–220
5.81 A. de Lozanne: Pattern generation below 0.1 micron by localized chemical vapor deposition with the scanning tunneling microscope,, Japan. J. Appl. Physic **33** (1994) 7090–7093
5.82 L. A. Nagahara, T. Thundat, S. M. Lindsay: Nanolithography on semiconductor surfaces under an etching solution, Appl. Phys. Lett. **57** (1990) 270–272
5.83 T. Thundat, L. A. Nagahara, S. M. Lindsay: Scanning tunneling microscopy studies of semiconductor

electrochemistry, J. Vac. Sci. & Technol. A **8** (1990) 539–543

5.84 S. C. Minne, S. R. Manalis, A. Atalar, C. F. Quate: Independent parallel lithography using the atomic force microscope, J. Vac. Sci. & Technol. B **14** (1996) 2456–2461

5.85 M. Lutwyche, C. Andreoli, G. Binnig, J. Brugger, U. Drechsler, W. Haeberle, H. Rohrer, H. Rothuizen, P. Vettiger: Microfabrication and parallel operation of 5 × 5 2D AFM cantilever arrays for data storage and imaging, Proc. MEMS '98 (1998), 8–11

5.86 G. M. Whitesides, B. Grzybowski: Self-assembly at all scales, Science **295** (2002) 2418–2421

5.87 P. Kazmaier, N. Chopra: Bridging size scales with self-assembling supramolecular materials, MRS Bulletin **25** (2000) 30–35

5.88 R. Plass, J. A. Last, N. C. Bartelt, G. L. Kellogg: Self-assembled domain patterns, Nature **412** (2001) 875

5.89 Y. A. Vlasov, X.-Z. Bo, J. G. Sturm, D. J. Norris: On-chip natural self-assembly of silicon photonic bandgap crystals, Nature **414** (2001) 289–293

5.90 C. Gigault, D.-K. Veress, J. R. Dutcher: Changes in the morphology of self-assembled polystyrene microsphere monolayers produced by annealing, J. Colloid Interface Sci. **243** (2001) 143–155

5.91 J. C. Hulteen, P. Van Duyne: Nanosphere lithography: a materials general fabrication process for periodic particle array surfaces, J. Vac. Sci. Technol. A **13** (1995) 1553–1558

5.92 J. D. Joannopoulos, P. R. Villeneuve, S. Fan: Photonic crystals: putting a new twist on light, Nature **386** (1997) 143–149

5.93 T. D. Clark, R. Ferrigno, J. Tien, K. E. Paul, G. M. Whitesides: Template-directed self-assembly of 10-μm-sized hexagonal plates, J. Am. Chem. Soc. **124** (2002) 5419–5426

5.94 S. A. Sapp, D. T. Mitchell, C. R. Martin: Using template-synthesized micro-and nanowires as building blocks for self-assembly of supramolecular architectures, Chem. Mater. **11** (1999) 1183–1185

5.95 Y. Yin, Y. Lu, B. Gates, Y. Xia: Template assisted self-assembly: a practical route to complex aggregates of monodispersed colloids with well-defined sizes, shapes and structures, J. Am. Chem. Soc. **123** (2001) 8718–8729

5.96 J. L. Wilbur, G. M. Whitesides: Self-assembly and self-assembles monolayers in micro and nanofabrication. In: *Nanotechnology*, ed. by G. Timp (Springer, New York 1999)

5.97 S. R. Wasserman, Y. T. Tao, G. M. Whitesides: Structure and reactivity of alkylsiloxane monolayers formed by reaction of alkyltrichlorosilanes on silicon substrates, Langmuir **5** (1989) 1074–1087

5.98 C. P. Tripp, M. L. Hair: An infrared study of the reaction of octadecyltrichlorosilane with silica, Langmuir **8** (1992) 1120–1126

5.99 D. R. Walt: Nanomaterials: top-to-bottom functional design, Nature **1** (2002) 17–18

5.100 J. Noh, T. Murase, K. Nakajima, H. Lee, M. Hara: Nanoscopic investigation of the self-assembly processes of dialkyl disulfides and dialkyl sulfides on Au(111), J. Phys. Chem. B **104** (2000) 7411–7416

5.101 M. Himmelhaus, F. Eisert, M. Buck, M. Grunze: Self-assembly of n-alkanethiol monolayers: a study by IR-visible sum frequency spectroscopy (SFG), J. Phys. Chem. **104** (2000) 576–584

5.102 A. K. Boal, F. Ilhan, J. E. DeRouchey, T. Thurn-Albrecht, T. P. Russell, V. M. Rotello: Self-assembly of nanoparticles into structures spherical and network aggregates, Nature **404** (2000) 746–748

5.103 A. Ulman: *An Introduction to Ultrathin Organic Films: From Langmuir–Blodgett to Self-Assembly* (Academic Press, New York 1991)

5.104 E. Winfree, F. Liu, L. A. Wenzler, N. C. Seeman: Design and self-assembly of two-dimensional DNA crystals, Nature **394** (1998) 539–544

5.105 J. H. Reif, T. H. LaBean, N. C. Seeman: Programmable assembly at the molecular scale: self-assembly of DNA lattices, Proc. 2001 IEEE Int. Conf. Robotics and Automation (IEEE, 2001) 966–971

5.106 A. P. Alivisatos, K. P. Johnsson, X. Peng, T. E. Wilson, C. J. Loweth, M. P. Bruchez Jr, P. G. Schultz: Organization of 'nanocrystal molecules' using DNA, Nature **382** (1996) 609–611

5.107 C. Y. Cao, R. Jin, C. A. Mirkin: Nanoparticles with Raman spectroscopic fingerprints for DNA and RNA detection, Science **297** (2002) 1536–1540

5.108 H. Masuda, H. Yamada, M. Satoh, H. Asoh: Highly ordered nanochannel-array architecture in anodic alumina, Appl. Phys. Lett. **71** (1997) 2770–2772

5.109 R. L. Fleischer: *Nuclear Tracks in Solids: Principles and Applications* (Univ. of California Press, Berkeley 1976)

5.110 R. E. Packard, J. P. Pekola, P. B. Price, R. N. R. Spohr, K. H. Westmacott, Y. Q. Zhu: Manufacture observation and test of membranes with locatable single pores, Rev. Sci. Instrum. **57** (1986) 1654–1660

5.111 L. Sun, P. C. Searson, C. L. Chien: Electrochemical deposition of nickel nanowire arrays in single-crystal mica films, Appl. Phys. Lett. **74** (1999) 2803–2805

5.112 Y. Du, W. L. Cai, C. M. Mo, J. Chen, L. D. Zhang, X. G. Zhu: Preparation and photoluminescence of alumina membranes with ordered pore arrays, Appl. Phys. Lett. **74** (1999) 2951–2953

5.113 S. Yang, H. Zhu, D. Yu, Z. Jin, S. Tang, Y. Du: Preparation and magnetic property of Fe nanowire array, J. Magn. Mater. **222** (2000) 97–100

5.114 M. Sun, G. Zangari, R. M. Metzger: Cobalt island arrays with in-plane anisotropy electrodeposited in highly ordered alumina, IEEE Trans. Magn. **36** (2000) 3005–3008

5.115 P. V. Braun, P. Wiltzius: Electrochemically grown photonic crystals, Nature **402** (1999) 603–604

5.116 S. R. Nicewarner-Pena, R. G. Freeman, B. D. Reiss, L. He, D. J. Pena, I. D. Walton, R. Cromer, C. D. Keating, M. J. Natan: Submicrometer metallic barcodes, Science **294** (2001) 137–141
5.117 D. Almalawi, C. Z. Ziu, M. Moskovits: Nanowires formed in anodic oxide nanotemplates, J. Mater. Res. **9** (1996) 1014
5.118 J. C. Hulteen, C. R. Martin: A general template-based method for the preparation of nanomaterials, J. Mater. Chem. **7** (1997) 1075–1087
5.119 B. R. Martin, D. J. Dermody, B. D. Reiss, M. Fang, L. A. Lyon, M. J. Natan, T. E. Mallouk: Orthogonal self-assembly on colloidal gold-platinum nanorods, Adv. Mater. **11** (1999) 1021–1025

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

6. Stamping Techniques for Micro and Nanofabrication: Methods and Applications

This chapter highlights some recent advances in high resolution printing methods, in which a "stamp" forms a pattern of "ink" on the surface it contacts. It focuses on two approaches whose capabilities, level of development, and demonstrated applications indicate a strong potential for widespread use, especially in areas where conventional methods are unsuitable. The first of these, known as microcontact printing, uses a high resolution rubber stamp to print patterns of chemical inks, mainly those that lead to the formation of organic self-assembled monolayers (SAMs). These printed SAMs can be used either as resists in selective wet etching, or as templates in selective deposition to form structures of a variety of materials. The other approach, referred to as nanotransfer printing, uses similar high resolution stamps, but ones inked with solid thin film materials. In this case, SAMs, or other types of surface chemistries, bond these films to a substrate that the stamp contacts. The material transfer that results upon removal of the stamp forms a pattern in the geometry of the relief features, in a purely additive fashion. In addition to providing detailed descriptions of these micro/nanoprinting techniques, this chapter illustrates their use in some areas where these methods may provide attractive alternatives to more established lithographic methods.

6.1 **High Resolution Stamps** 186
6.2 **Microcontact Printing** 187
6.3 **Nanotransfer Printing** 190
6.4 **Applications** 193
  6.4.1 Unconventional Electronic Systems 193
  6.4.2 Lasers and Waveguide Structures 198
6.5 **Conclusions** 200
References 200

The demonstrator applications span fields as diverse as biotechnology (intravascular stents), fiber optics (tunable fiber devices), nanoanalytical chemistry (high resolution nuclear magnetic resonance), plastic electronics (paper-like displays), and integrated optics (distributed feedback lasers). The growing interest in nanoscience and nanotechnology motivates research and the development of new methods that can be used for nanofabricating the relevant test structures or devices. The attractive capabilities of the techniques described here, together with the interesting and subtle materials science, chemistry, and physics associated with them, make this a promising area for basic and applied study.

There is considerable interest in methods for building structures that have micron or nanometer dimensions. Historically, research and development in this area has been driven mainly by the needs of the microelectronics industry. The spectacularly successful techniques that have emerged from those efforts – photolithography, electron beam lithography, etc. – are extremely well suited to the tasks for which they were principally designed: forming structures of radiation sensitive materials (e.g., photoresists or electron beam resists) on ultra-flat glass or semiconductor surfaces. Significant challenges exist in adapting these methods for new emerging applications and areas of research that require patterning of unusual systems and materials (e.g., those in biotechnology, plastic electronics, etc.), structures with nanometer dimensions (i. e., below 50–100 nm), large areas in a single step (i. e., larger than a few square centimeters), or non-planar (i. e., rough or curved) surfaces. These established techniques also have the disadvantage of high capital and operational costs. As a result, some of the oldest and conceptually simplest forms of lithography – embossing, molding, stamping, writing, etc. – are now being re-examined for their potential to serve as the basis for nanofabrica-

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

tion techniques that can avoid these limitations [6.1]. Considerable progress has been made in the last few years, mainly by combining these approaches or variants of them with new materials, chemistries, and processing techniques. This chapter highlights some recent advances in high resolution printing methods, in which a "stamp" forms a pattern of "ink" on a surface that it contacts. It focuses on approaches whose capabilities, level of development, and demonstrated applications indicate a strong potential for widespread use, especially in areas where conventional methods are unsuitable.

Contact printing involves the use of an element with surface relief (i. e., the stamp) for transferring material applied to its surface (i. e. the ink) to locations on a substrate that it contacts. The printing press, one of the earliest manufacturable implementations of this approach, was introduced by Gutenberg in the fifteenth century. The general approach has since been used almost exclusively for producing printed text or images with features that are one hundred microns or larger in their minimum dimension. The resolution is determined by the nature of the ink and its interaction with the stamp and/or substrate, the resolution of the stamp, and the processing conditions that are used for printing or converting the pattern of ink into a pattern of functional material. This chapter focuses on (1) printing techniques that are capable of micron and nanometer resolution, and (2) their use for fabricating key elements of active electronic or optical devices and subsystems. It begins with an overview of some methods for fabricating high resolution stamps and then illustrates two different ways that these stamps can be used to print patterns of functional materials. Applications that highlight the capabilities of these techniques and the performance of systems that are constructed with them are also presented.

6.1 High Resolution Stamps

The printing process can be separated into two parts: fabrication of the stamp and the use of this stamp to pattern features defined by the relief on its surface. These two processes are typically quite different, although it is possible in some cases to use patterns generated by a stamp to produce a replica of that stamp. The structure from which the stamp is derived, which is known as the "master", can be fabricated with any technique that is capable of producing well-defined structures of relief on a surface. This master can then be used directly as the stamp, or to produce stamps via molding or printing procedures. It is important to note that the technique for producing the master does not need to be fast or low in cost. It also does not need to possess many other characteristics that might be desirable for a given patterning task: It is used just once to produce a master, which is directly or indirectly used to fabricate stamps. Each one of these stamps can then be used many times for printing.

In a common approach for the high resolution techniques that are the focus of this chapter, an established lithographic technique, such as one of those developed for the microelectronics industry, defines the master. Figure 6.1 schematically illustrates typical processes. Here, photolithography patterns a thin layer of resist on a silicon wafer. Stamps are generated from this structure in one of two ways: By casting against this master, or by etching the substrate with the patterned resist as a mask. In the first approach, the master itself can be used multiple times to produce many stamps, typically using a light or heat-curable prepolymer. In the second, the etched substrate serves as the stamp. Additional stamps can be generated either by repeating the lithography and etching, or by using the original stamp to print replica stamps. For minimum lateral feature sizes greater than ∼ 1–2 microns, contact or proximity mode photolithography with a mask produced by direct write photolithography represents a convenient method to fabricate the master. For features smaller than ∼ 2 microns, several different techniques can be used [6.2], including: (1) projection mode photolithography [6.3], (2) direct write electron beam (or focused ion beam) lithography [6.4, 5], (3) scanning probe lithography [6.6–9] or (4) laser interference lithography [6.10]. The first approach requires a photomask generated by some other method, such as direct write photolithography or electron beam lithography. The reduction (typically 4×) provided by the projection optics relaxes the resolution requirements on the mask and enables features as small as ∼ 90 nm when deep ultraviolet radiation and phase shifting masks are used. The costs for these systems are, however, very high and their availability for general research purposes is limited. The second method is flexible in the geometry of patterns that can be produced, and the writing sys-



Fig. 6.1 Schematic illustration of two methods for producing high resolution stamps. The first step involves patterning a thin layer of some radiation sensitive material, known as the resist, on a flat substrate, such as a silicon wafer. It is convenient to use an established technique, such as photolithography or electron beam lithography, for this purpose. This structure, known as the master, is converted to a stamp either by etching or molding. In the first case, the resist acts as a mask for etching the underlying substrate. Removing the resist yields a stamp. This structure can be used directly as a stamp to print patterns, or to produce additional stamps. In the molding approach, a prepolymer is cast against the relief structure formed by the patterned resist on the substrate. Curing (thermally or optically) and then peeling the resulting polymer away from the substrate yields a stamp. In this approach, many stamps can be made with a single master, and each stamp can be used many times

tems are highly developed: 30–50 nm features can be achieved with commercial systems [6.11], and < 10 nm features are possible with research tools, as first demonstrated more than 25 years ago by *Broers* [6.12]. The main drawbacks of this method are that it is relatively slow and it is difficult to pattern large areas. Like projection mode photolithography, it can be expensive. The third method, scanning probe lithography, is quite powerful in principle, but the tools are not as well established as those for other approaches. This technique has atomic resolution, but its writing speed can be lower and the areas that can be patterned are smaller than electron beam systems. Interference lithography provides a powerful, low cost tool for generating periodic arrays of features with dimensions down to 100–200 nm; smaller sizes demand ultraviolet lasers, and patterns with aperiodic or non-regular features are difficult to produce.

6.2 Microcontact Printing

Microcontact printing (μCP) [6.13] is one of several soft lithographic techniques – replica molding, micromolding in capillaries, microtransfer molding, near-field conformal photolithography using an elastomeric phase-shifting mask, etc. – that have been developed as alternatives to established methods for micro- and nanofabrication [6.14–18]. μCP uses an elastomeric element (usually polydimethylsiloxane – PDMS) with high resolution features of relief as a stamp to print patterns of chemical inks. It was mainly developed for use with inks that form self-assembled monolayers (SAMs) of alkanethiolates on gold and silver. The procedure for carrying out μCP in these systems is remarkably simple: A stamp, inked with a solution of alkanethiol, is brought into contact with the surface of a substrate to transfer ink molecules to regions where the stamp and substrate contact. The resolution and effectiveness of μCP rely on conformal contact between the stamp and the surface of the substrate, rapid formation of highly ordered monolayers [6.19], and autophobicity of the SAM, which effectively blocks the reactive spreading of the ink across the surface [6.20]. It can pattern SAMs over relatively large areas (∼ up to 0.25 ft^2 have been demonstrated in prototype electronic devices) in a single impression [6.21]. The edge resolution of SAMs printed onto thermally evaporated gold films is on the order of 50 nm, as determined by lateral force microscopy [6.22]. Microcontact printing has been used with a range of different SAMs on various substrates [6.14]. Of these, alkanethiolates on gold, silver, and palladium [6.23] presently give the highest resolution. In many cases, the mechanical properties of the stamp limit the sizes of the smallest features that can be achieved: The most commonly used elastomer (Sylgard 184, Dow Corning) has a low modulus, which can lead to mechanical collapse or sagging for features of relief with aspect



Fig. 6.2 Schematic illustration of microcontact printing. The first step involves inking a stamp with a solution of a material that is capable of forming a self-assembled monolayer (SAM) on a substrate that will be printed. In the case illustrated here, the ink is a millimolar concentration of hexadecanethiol (HDT) in ethanol. Directly applying the ink to the surface of the stamp with a pipette prepares the stamp for printing. Blowing the surface of the stamp dry and placing it on a substrate delivers the ink to areas where the stamp contacts the substrate. The substrate consists of a thin layer of Au on a flat support. Removing the stamp after a few seconds of contact leaves a patterned SAM of HDT on the surface of the Au film. The printed SAM can act as a resist for the aqueous-based wet etching of the exposed regions of the Au. The resulting pattern of conducting gold can be used to build devices of various types

ratios greater than ~ 2 or less than ~ 0.05. Stamps fabricated with high modulus elastomers avoid some of these problems [6.24, 25]. Conventional stamps are also susceptible to in-plane mechanical strains that can cause distortions in the printed patterns. Composite stamps that use thin elastomer layers on stiff supports are effective at minimizing this source of distortion [6.26]. Methods for printing that avoid direct mechanical manipulation of the stamp can reduce distortions with conventional and composite stamps [6.21]. This approach has proven effective in large area flexible circuit applications that require accurate multilevel registration.

The patterned SAM can be used either as a resist in selective wet etching or as a template in selective deposition to form structures of a variety of materials: metals, silicon, liquids, organic polymers, and even biological species. Figure 6.2 schematically illustrates the use of µCP and wet etching to pattern a thin film of Au. Figure 6.3 shows SEM images of nanostructures of gold (20 nm thick, thermally evaporated with a 2.5 nm layer of Ti as an adhesion promoter) and silver (~ 100 nm thick formed by electroless deposition using commercially available plating baths) [6.27] that were fabricated using this approach. In the first and second examples, the masters for the stamps consisted of photoresist patterned on silicon wafers with projection and contact mode photolithography, respectively. Placing these masters in a desiccator for ~ 1 h with a few drops of tridecafluoro-1,1,2,2-tetrahydrooctyl-1-trichlorosilane forms a silane monolayer on the exposed native oxide of the silicon. This monolayer prevents adhesion of the master to PDMS (Sylgard 184), which is cast and cured from a 10:1 mixture of prepolymer and curing agent. Placing a few drops of a ~ 1 mM solution of hexadecanethiol (HDT) in ethanol on the surface of the stamps, and then blowing them dry with a stream of nitrogen prepares them for printing. Contacting the metal film for a few seconds with the stamp produces a patterned self-assembled monolayer (SAM) of HDT. An aqueous etchant (1 mM $K_4Fe(CN)_6$, 10 mM $K_3Fe(CN)_6$, and 0.1 M $Na_2S_2O_3$) removes the unprinted regions of the silver [6.28]. A similar solution (1 mM $K_4Fe(CN)_6$, 10 mM $K_3Fe(CN)_6$, 1.0 M KOH, and 0.1 M $Na_2S_2O_3$)



Fig. 6.3 Scanning electron micrographs of typical structures formed by microcontact printing a self-assembled monolayer ink of hexadecanethiol onto a thin metal film followed by etching of the unprinted areas of the film. The *left frame* shows an array of Au (20 nm-thick) dots with ~ 500 nm diameters. The *right frame* shows a printed structure of Ag (100 nm thick) in the geometry of interdigitated source/drain electrodes for a transistor in a simple inverter circuit. The edge resolution of patterns that can be easily achieved with microcontact printing is ~ 50–100 nm



Fig. 6.4 Schematic illustration of a simple method to print lines on the surfaces of optical fibers. Rolling a fiber over the inked stamp prints a pattern onto the fiber surface. Depending on the orientation of the fiber axis with the line stamp illustrated here, it is possible in a single rotation of the fiber to produce a continuous microcoil, or arrays of bands or stripes

can be used for etching the bare gold [6.29]. The results of Fig. 6.3 show that the roughness on the edges of the patterns is ∼ 50–100 nm. The resolution is determined by the grain size of the metal films, the isotropic etching process, slight reactive spreading of the inks, and edge disorder in the patterned SAMs.

The structures of Fig. 6.3 were formed on the flat surfaces of silicon wafers (left image) and glass slides (right image). An attractive feature of μCP and certain other contact printing techniques is their ability to pattern features with high resolution on highly curved or rough surfaces [6.18, 30, 31]. This type of patterning task is difficult or impossible to accomplish with photolithography due to its limited depth of focus and the difficulty of casting uniform films of photoresist on non-flat surfaces. Figure 6.4 shows, as an example, a straightforward approach for high resolution printing on the highly curved surfaces of optical fibers. Here, simply rolling the fiber over an inked stamp prints a pattern on the entire outer surface of the fiber. Simple staging systems allow alignment of features to the fiber axis; they also ensure registration of the pattern from one side of the fiber to the other [6.16]. Figure 6.5 shows 3 micron-wide lines and spaces printed onto the surface of a single mode optical fiber (diameter 125 μm). The bottom frame shows a freestanding metallic structure with the geometry and mechanical properties of an intravascular stent, which is a biomedical device that is commonly used in balloon angioplasty procedures. In this latter case μCP followed by electroplating generated the Ag microstructure on a sacrificial glass cylinder that was subsequently etched away with concentrated hydrofluoric acid [6.32]. Other examples of microcontact printing on non-flat surfaces (i. e., low cost plastic sheets and optical ridge waveguides) appear in the applications section of this chapter.



Fig. 6.5 Optical micrographs of some three-dimensional microstructures formed by microcontact printing on curved surfaces. The *top frame* shows an array of 3-micron lines of Au (20 nm)/Ti (1.5 nm) printed onto the surface of an optical fiber. This type of structure can be used as an integrated photomask for producing mode-coupling gratings in the core of the fiber. The *bottom frames* show a freestanding metallic microstructure formed by (1) microcontact printing and etching a thin (100 nm-thick) film of Ag on the surface of a glass microcapillary tube, (2) electroplating the Ag to increase its thickness (to tens of microns) and (3) etching away the glass microcapillary with concentrated hydrofluoric acid. The structure shown here has the geometry and mechanical properties of an intravascular stent, which is a biomedical device commonly used in balloon angioplasty

6.3 Nanotransfer Printing

Nanotransfer printing (nTP) is a more recent high resolution printing technique, which uses surface chemistries as interfacial "glues" and "release" layers (rather than "inks", as in μCP) to control the transfer of solid material layers from relief features on a stamp to a substrate [6.33–35]. This approach is purely additive (i. e., material is only deposited in locations where it is needed), and it can generate complex patterns of single or multiple layers of materials with nanometer resolution over large areas in a single process step. It does not suffer from surface diffusion or edge disorder in the patterned inks of μCP, nor does it require post-printing etching or deposition steps to produce structures of functional materials. The method involves four components: (1) a stamp (rigid, flexible, or elastomeric) with relief features in the geometry of the desired pattern, (2) a method for depositing a thin layer of solid material onto the raised features of this stamp, (3) a means of bringing the stamp into intimate physical contact with a substrate, and (4) surface chemistries that prevent adhesion of the deposited material to the stamp and promote its strong adhesion to the substrate. nTP has been demonstrated with SAMs and other surface chemistries for printing onto flexible and rigid substrates with hard inorganic and soft polymer stamps. Figure 6.6 presents a set of procedures for using nTP to pattern a thin metal bilayer of Au/Ti with a surface transfer chemistry that relies on a dehydration reaction [6.33]. The process begins with fabrication of a suitable stamp. Elastomeric stamps can be built using the same casting and curing procedures described for μCP. Rigid stamps can be fabricated by (1) patterning resist (e.g., electron beam resist or photoresist) on a substrate (e.g., Si or GaAs), (2) etching the exposed regions of the substrate with an anisotropic reactive ion etch, and (3) removing the resist, as illustrated in Fig. 6.1. For both types of stamps, careful control of the lithography and the etching steps yields features of relief with nearly vertical or slightly re-entrant sidewalls. The stamps typically have depths of relief $> 0.2\,\mu\text{m}$ for patterning metal films with thicknesses $< 50\,\text{nm}$.

Electron beam evaporation of Au (20 nm; 1 nm/s) and Ti (5 nm; 0.3 nm/s) generates uniform metal bilayers on the surfaces of the stamp. A vertical, collimated flux of metal from the source ensures uniform deposition only on the raised and recessed regions of relief. The gold adheres poorly to the surfaces of stamps made of GaAs, PDMS, glass, or Si. In the process of Fig. 6.6, a fluorinated silane monolayer acts to reduce further the adhesion when a Si stamp (with native oxide) is used. The Ti layer serves two purposes: (1) it promotes adhesion between the Au layer and the substrate after pattern


Form Si stamp, fluorinate surface
CF₃ CF₃ CF₃ CF₃
(CF₂)₅ (CF₂)₅ (CF₂)₅ (CF₂)₅
(CF₂)₂ (CF₂)₂ (CF₂)₂ (CF₂)₂
Si Si Si Si
O O O O O
O O O O
Si Si Si Si
Evaporate Au, Ti from a collimated source
Ti/Au
Plasma oxidize Ti and PDMS substrate
OH OH
Si Si
Au
Ti Ti Ti
OH OH OH
Contact
Remove
Au
Ti Ti Ti Ti
O O O O
Si Si Si Si

Fig. 6.6 Schematic illustration of nanotransfer printing procedures. Here, interfacial dehydration chemistries control the transfer of a thin metal film from a hard inorganic stamp to a conformable elastomeric substrate (thin film of polydimethylsiloxane (PDMS) on a plastic sheet). The process begins with the fabrication of a silicon stamp (by conventional lithography and etching) followed by surface functionalization of the native oxide with a fluorinated silane monolayer. This layer ensures poor adhesion between the stamp and a bilayer metal film (Au and Ti) deposited by electron beam evaporation. A collimated flux of metal oriented perpendicular to the surface of the stamp avoids deposition on the sidewalls of relief. Exposing the surface Ti layer to an oxygen plasma produces titanol groups. A similar exposure for the PDMS produces silanol groups. Contacting the metal-coated stamp to the PDMS results in a dehydration reaction that links the metal to the PDMS. Removing the stamp leaves a pattern of metal in the geometry of the relief features

transfer, and (2) it readily forms a ∼ 3 nm oxide layer at ambient conditions, which provides a surface where the dehydration reaction can take place. Exposing the titanium oxide (TiO_x) surface to an oxygen plasma breaks bridging oxygen bonds, thus creating defect sites where water molecules can adsorb. The result is a titanium oxide surface with some fractional coverage of hydroxyl (−OH) groups (titanol).

In the case of Fig. 6.6, the substrate is a thin film of PDMS (10–50 μm thick) cast onto a sheet of poly(ethylene terephthalate) (PET; 175 μm thick). Exposing the PDMS to an oxygen plasma produces surface (−OH) groups (silanol). Placing the plasma oxidized, Au/Ti-coated stamp on top of these substrates leads to intimate, conformal contact between the raised regions of the stamp and the substrate, without the application of any external pressure. (The soft, conformable PDMS is important in this regard.) It is likely that a dehydration reaction takes place at the (−OH)-bearing interfaces during contact; this reaction results in permanent Ti−O−Si bonds that produce strong adhesion between the two surfaces. Peeling the substrate and stamp apart transfers the Au/Ti bilayer from the raised regions of the stamp (to which the metal has extremely poor adhesion) to the substrate. Complete pattern transfer from an elastomeric stamp to a thin elastomeric substrate occurs readily at room temperature in open air with contact times of less than 15 seconds. When a rigid stamp is employed, slight heating is needed to induce transfer. While the origin of this difference is unclear, it may reflect the comparatively poor contact when rigid stamps are used; similar differences are also observed in cold welding of gold films [6.36].

Figure 6.7 shows scanning electron micrographs of a pattern produced using a GaAs stamp generated by electron beam lithography and etching. The frames on the right show images of the metal-coated stamp before printing (top) and the transferred pattern (bottom). The resolution appears to be limited only by the resolution of the stamp itself, and perhaps by the grain size of the metal films. Although the accuracy in multilevel registration that is possible with nTP has not yet been quantified, its performance is likely similar to that of embossing techniques when rigid stamps are used [6.37].

A wide range of surface chemistries can be used for the transfer. SAMs are particularly attractive due to their chemical flexibility. Figure 6.8 illustrates the use of a thiol terminated SAM and nTP for forming patterns of Au on a silicon wafer [6.34]. Here, the vapor phase co-condensation of the methoxy groups of molecules of 3-mercaptopropyltrimethoxysilane (MPTMS) with the −OH terminated surface of the wafer produces a SAM of MPTMS with exposed thiol (−SH) groups. PDMS stamps can be prepared for printing on this surface by coating them with a thin film (∼ 15 nm) of Au using conditions (thermal evaporation 1.0 nm/s; ∼ 10^{-7} torr base pressure) that yield optically smooth, uniform films without the buckling that has been observed in the past with similar systems [6.38]. Nanocracking that sometimes occurs in the films deposited in this way can be reduced or eliminated by evaporating a small amount of Ti onto the PDMS before Au deposition and/or by exposing the PDMS surface briefly to an oxygen plasma. Bringing this coated stamp into contact with the MPTMS SAM leads to the formation of sulfur–gold bonds in the regions of contact. Removing the stamp after a few seconds efficiently transfers the gold from the raised regions of the stamp (Au does not adhere to the PDMS) to the substrate. Covalent bonding of the SAM glue to both the substrate and the gold leads to good adhesion of the printed patterns: They easily pass Scotch



Fig. 6.7 Scanning electron micrograph (SEM) of a pattern produced by nanotransfer printing. The structure consists of a bilayer of Au (20 nm)/Ti (1 nm) (*white*) in the geometry of a photonic bandgap waveguide printed onto a thin layer of polydimethylsiloxane on a sheet of plastic (*black*). Electron beam lithography and etching of a GaAs wafer produced the stamp that was used in this case. The transfer chemistry relied on condensation reactions between titanol groups on the surface of the Ti and silanol groups on the surface of the PDMS. The *frames on the right* show SEMs of the Au/Ti-coated stamp (*top*) before printing and on the substrate (*bottom*) after printing. The electron beam lithography and etching used to fabricate the stamp limit the minimum feature size (∼ 70 nm) and the edge resolution (∼ 5–10 nm) of this pattern



Fig. 6.8 Schematic illustration of steps for nanotransfer printing a pattern of a thin layer of Au onto a silicon wafer using a self-assembled monolayer (SAM) surface chemistry. Plasma oxidizing the surface of the wafer generates $-$OH groups. Solution or vapor phase exposure of the wafer to 3-mercaptopropyl-trimethoxysilane yields a SAM with exposed thiol groups. Contacting an Au-coated stamp to this surface produces thiol linkages that bond the gold to the substrate. Removing the stamp completes the transfer printing process

tape adhesion tests. Similar results can be obtained with other substrates containing surface $-$OH groups. For example, Au patterns can be printed onto $\sim 250\,\mu$m-thick sheets of poly(ethylene terephthalate) (PET) by first spin casting and curing (130 °C for 24 h) a thin film of an organosilsesquioxane on the PET. Exposing the cured film ($\sim 1\,\mu$m thick) to an oxygen plasma and then to air produces the necessary surface ($-$OH) groups. Figure 6.9 shows some optical micrographs of typical printed patterns in this case [6.34].

Similar surface chemistries can guide transfer to other substrates. Alkanedithiols, for example, are useful for printing Au onto GaAs wafers [6.35]. Immersing these substrates (freshly etched with 37% HCl for ~ 2 min to remove the surface oxide) in a 0.05 M solution of 1,8-octanedithiol in ethanol for 3 h produces a monolayer of dithiol on the surface. Although the chemistry of this system is not completely clear, it is generally believed that the thiol end groups bond chemically to the surface. Surface spectroscopy suggests the formation of Ga$-$S and As$-$S bonds. Contacting an Au-coated PDMS stamp with the treated substrate causes the exposed thiol endgroups to react with Au in the regions of contact. This reaction produces permanent Au$-$S bonds at the stamp/substrate interface (see insets in Fig. 6.2 for idealized chemical reaction schemes). Figure 6.10 illustrates a representative optical micrograph of an Au pattern generated by nTP on GaAs.



Fig. 6.9 Optical micrographs of patterns of Au (15 nm thick) formed on plastic (*left frame*) and silicon (*right frame*) substrates with nanotransfer printing. The transfer chemistries in both cases rely on self-assembled monolayers with exposed thiol groups. The minimum feature sizes and the edge resolution are both limited by the photolithography used to fabricate the stamps



Fig. 6.10 Optical micrograph of a pattern of Au (15 nm thick) formed on a GaAs substrate using nanotransfer printing. The transfer chemistry in this case relies on a dithiol layer formed on the substrate. The minimum feature sizes and the edge resolution are both limited by the photolithography used to fabricate the stamps

6.4 Applications

Promising potential applications for the types of printing techniques described in the previous sections include those where the patterning requirements cannot be met with existing tools or those where the costs of these conventional methods are prohibitively high.We have focused our efforts partly on unusual electronic systems such as flexible plastic circuits and devices that rely on electrodes patterned on curved objects such as microcapillaries and optical fibers. We have also explored photonic systems such as distributed feedback structures for lasers and other integrated optical elements that demand sub-micron features.The sections below highlight several examples in each of these areas.

6.4.1 Unconventional Electronic Systems

A relatively new direction in electronics research seeks to establish low cost plastic materials, substrates, and printing techniques for large area flexible electronic devices, such as paper-like displays. These types of novel devices can complement those (e.g., high density memories, high speed microprocessors, etc.) that are well suited to existing inorganic (e.g., silicon) electronics technologies. High resolution patterning methods for defining the separation between the source and drain electrodes (i. e., channel length) of transistors in these plastic circuits are particularly important because this dimension determines current output and other important characteristics [6.39].

Although conventional patterning techniques, such as photolithography or electron beam lithography, have the required resolution, they are not appropriate because they are expensive and generally require multiple processing steps with resists, solvents, and developers, which can be difficult to use with organic active materials and plastic substrates. Microcontact and nanotransfer printing are both particularly well suited for this application. They can be combined and matched with other techniques, such as ink jet or screen printing, to form a complete system for patterning all layers in practical plastic electronic devices [6.40].



Fig. 6.11 Schematic cross-sectional view (*top*) and electrical performance (*bottom*) of an organic thin film transistor with microcontact printed source and drain electrodes. The structure consists of a substrate (PET), a gate electrode (indium tin oxide), a gate dielectric (spin cast layer of organosilsesquioxane), source and drain electrodes (20 nm Au and 1.5 nm Ti), and a layer of the organic semiconductor pentacene. The electrical properties of this device are comparable to or better than those that use pentacene with photolithographically defined source/drain electrodes and inorganic dielectrics, gates, and substrates

Figure 6.11 illustrates schematically a cross-sectional view of a typical organic transistor. The frame on the right shows the electrical switching characteristics of a device that uses source/drain electrodes of Au patterned by μCP, a dielectric layer of an organosilsesquioxane, a gate of indium tin oxide (ITO), and a PET substrate. The effective semiconductor mobility extracted from these data is comparable to those measured in devices that use the same semiconductor (pentacene in this case) with inorganic substrates and dielectrics, and gold source/drain electrodes defined by photolithography. Our recent work [6.1,27,41]with μCP in the area of plastic electronics demonstrates: (1) methods for using cylindrical "roller" stamps mounted on fixed axles for printing in a continuous reel-to-reel fashion, high resolution source/drain electrodes in ultrathin gold and silver deposited from solution at room temperature using electroless deposition, (2) techniques for performing registration and alignment of the printed features with other elements of a circuit over large areas, (3) strategies for achieving densities of defects that are as good as those observed with photolithography when the



Fig. 6.12 Image of a flexible plastic active matrix backplane circuit whose finest features (transistor source/drain electrodes, and related interconnects) are patterned by microcontact printing. The circuit rests partly on the elastomeric stamp that was used for printing. The circuit consists of a square array of interconnected organic transistors, each of which acts locally as a voltage-controlled switch to control the color of an element in the display. The *inset* shows an optical micrograph of one of the transistors

patterning is performed outside of clean room facilities, (4) methods for removing the printed SAMs to allow good electrical contact of the electrodes with organic semiconductors deposited on top of them, and (5) materials and fabrication sequences that can efficiently exploit these printed electrodes for working organic TFTs in large scale circuits.

Figure 6.12 provides an image of a large area plastic circuit with critical features defined by µCP. This circuit is a flexible active matrix backplane for a display. It consists of a square array of interconnected transistors, each of which serves as a switching element that controls the color of a display pixel [6.21,42]. The transistors themselves have the layout illustrated in Fig. 6.11, and they use similar materials. The semiconductor in this image is blue (pentacene), the source/drain level is Au, the ITO appears green in the optical micrograph in the inset. Part of the circuit rests on the stamp that was used for µCP. The smallest features are the source and drain electrodes (∼ 15 µm lines), the interconnecting lines (∼ 15 µm lines), and the channel length of the transistor (∼ 15 µm). This circuit incorporates five layers of material patterned with good registration of the source/drain, gate, and semiconductor levels. The simple printing approach is illustrated in Fig. 6.13 [6.21]. Just before use, the surface of the stamp is cleaned using a conventional adhesive roller lint remover; this procedure removes dust from the stamp in a manner that does



Fig. 6.13 Schematic illustration of fabrication steps for microcontact printing onto large areas of plastic sheets. The process begins with cleaning the stamp using a conventional adhesive roller lint remover. This procedure effectively removes dust particles. To minimize distortions, the stamp rests face up on a flat surface and is not manipulated directly during the printing. Alignment and registration are achieved with alignment marks on one side of the substrate and the stamp. By bending the plastic sheet, contact is initiated on one side of the stamp. The contact line is then allowed to progress gradually across the stamp. This approach avoids the formation of air bubbles that can frustrate good contact. After the substrate is in contact with the stamp for a few seconds, the plastic substrate is separated from the stamp by peeling it away, beginning in one corner. Good registration (maximum cumulative distortions less than 50 microns over an area of 0.25 square feet) and low density of defects can be achieved with this simple approach. It is also well suited for use with rigid composite stamps designed to even further reduce the level of distortion

not contaminate or damage its surface. Inking the stamp and placing it face up on a flat surface prepares it for printing. Matching the cross hair alignment marks on the corners of one edge of the stamp with those patterned in the ITO brings the substrate into registration with the stamp. During this alignment, features on the stamp are viewed directly through the semitransparent substrate. By bending the PET sheet, contact with the stamp is initiated on the edge of the substrate that contains the cross hair marks. Gradually unbending the sheet allows contact to progress across the rest of the surface. This printing procedure is attractive because it avoids distortions that can arise when directly manipulating the flexible rubber stamp. It also minimizes the number and size of trapped air pockets that can form between the stamp and substrate. Careful measurements performed after etching the unprinted areas of the gold show that over the entire 6"×6" area of the circuit, (1) the overall alignment accuracy for positioning the stamp relative to the substrate (i. e., the offset of the center of the distribution of registration errors) is $\sim 50-100\,\mu$m, even with the simple approach used here, and (2) the distortion in the positions of features in the source/drain level, when referenced to the gate level, can be as small as $\sim 50\,\mu$m (i. e., the full width at half maximum of the distribution of registration errors). These distortions represent the cumulative effects of deformations in the stamp and distortions in the gate and column electrodes that may arise during the patterning and processing of the flexible PET sheet. The density of defects in the printed patterns is comparable to (or smaller than) that in resist patterned by contact mode photolithography when both procedures are performed outside of a cleanroom facility (i. e., when dust is the dominant source of defects).



Fig. 6.14 Schematic exploded view of the components of a pixel in an electronic paper-like display (*bottom frame*) that uses a microcontact printed flexible active matrix backplane circuit (*illustration near the bottom frame*). The circuit is laminated against an unpatterned thin sheet of electronic ink (*top frame*) that consists of a monolayer of transparent polymer microcapsules (diameter ~ 100 microns). These capsules contain a heavily dyed black fluid and a suspension of charged white pigment particles (see *right inset*). When one of the transistors turns on, electric fields develop between an unpatterned transparent frontplane electrode (indium tin oxide) and a backplane electrode that connects to the transistor. Electrophoretic flow drives the pigment particles to the front or the back of the display, depending on the polarity of the field. This flow changes the color of the pixel, as viewed from the front of the display, from black to white or vice versa

Figure 6.14 shows an "exploded" view of a paper-like display that consists of a printed flexible plastic backplane circuit, like the one illustrated in Fig. 6.13, laminated against a thin layer of "electronic ink" [6.21, 43]. The electronic ink is composed of a monolayer of transparent polymer microcapsules that contain a suspension of charged white pigment particles suspended in a black liquid. The printed transistors in the backplane circuit act as local switches, which control electric fields that drive the pigments to the front or back of the display. When the particles flow to the front of a microcapsule, it appears white; when they flow to the back, it appears black. Figure 6.15 shows a working sheet of active matrix electronic paper that uses this design. This prototype display has several hundred pixels and an optical contrast that is both independent of the viewing angle and significantly better than newsprint. The device is ~ 1 mm thick, is mechanically flexible, and weighs $\sim 80\%$ less than a conventional liquid crystal display of similar size. Although these displays have only a relatively coarse resolution, all of the processing techniques, the μCP method, the materials, and the electronic inks are suitable for the large numbers of



Fig. 6.15 Electronic paper-like display showing two different images. The device consists of several hundred pixels controlled by a flexible active matrix backplane circuit formed by microcontact printing. The relatively coarse resolution of the display is not limited by material properties or by the printing techniques. Instead, it is set by practical considerations for achieving high pixel yields in the relatively uncontrolled environment of the chemistry laboratory in which the circuits were fabricated



Fig. 6.16 The *top frame* shows current-voltage characteristics of an n-channel transistor formed with electrodes patterned by nanotransfer printing that are laminated against a substrate that supports an organic semiconductor, a gate dielectric, and a gate. The *inset* shows an optical micrograph of the interdigitated electrodes. The *bottom frame* on the right shows the transfer characteristics of a simple CMOS inverter circuit that uses this device and a similar one for the p-channel transistor

pixels required for high information content electronic newspapers and other systems.

Like μCP, nTP is well suited to forming high resolution source/drain electrodes for plastic electronics. nTP of Au/Ti features in the geometry of the drain and source level of organic transistors and with appropriate interconnects on a thin layer of PDMS on PET yields a substrate that can be used in an unusual but powerful way for building circuits: Soft, room temperature lamination of such a structure against a plastic substrate that supports the semiconductor, gate dielectric, and gate levels yields a high performance circuit embedded between two plastic sheets [6.33,44]. (Details of this lamination procedure are presented elsewhere.) The left frame of Fig. 6.16 shows the current-voltage characteristics of a laminated n-channel transistor that uses the organic semiconductor copper hexadecafluorophthalocyanine (n-type) and source/drain electrodes patterned with nTP. The inset shows an optical micrograph of the printed interdigitated source/drain electrodes of this device. The bottom frame of Fig. 6.16 shows the transfer characteristics of a laminated complementary organic inverter circuit whose electrodes and connecting lines are defined by nTP. The p-channel transistor in this circuit used pentacene for the semiconductor [6.33].

In addition to high resolution source/drain electrodes, it is possible to use nTP to form complex multilayer devices with electrical functionality on plastic substrates [6.34]. Figure 6.17 shows a metal/insulator/metal (MIM) structure of Au (50 nm), SiN_x (100 nm; by plasma enhanced vapor deposition, PECVD), Ti (5 nm), and Au (50 nm) formed by transfer printing with a silicon stamp that is coated sequentially with these layers. In this case, a short reactive ion etch (with CF_4), after the second Au deposition, removes the SiN_x from the sidewalls of the stamp. nTP transfers these layers in a patterned geometry to a substrate of Au(15 nm)/Ti(1 nm)-coated PDMS(50 μm)/PET(250 μm). Interfacial cold welding between the Au on the surfaces of the stamp and substrate bonds the multilayers to the substrate. Figure 6.3 illustrates the procedures, the structures (lateral dimensions of 250 μm × 250 μm, for ease of electrical probing), and their electrical characteristics. These MIM capacitors have performance similar to devices fabricated on silicon wafers by photolithography and lift-off. This example illustrates the ability of nTP to print patterns of materials whose growth conditions (high temperature SiN_x by PECVD, in this case) prevent their direct deposition or processing on the substrate of interest (PET, in this case). The cold welding transfer approach has also been exploited in other ways for patterning components for plastic electronics [6.45, 46].

Another class of unusual electronic/optoelectronic devices relies on circuits or circuit elements on curved surfaces. This emerging area of research was stimulated primarily by the ability of μCP to print high resolution features on fibers and cylinders. Figure 6.18 shows a conducting microcoil printed with μCP on a microcapillary tube using the approach illustrated in Fig. 6.4. The coil serves as the excitation and detection element for high resolution proton nuclear magnetic resonance of nanoliter volumes of fluid that are housed in the bore of the microcapillary [6.47]. The high fill factor and other considerations lead to extremely high sensitivity with such printed coils. The bottom frame of Fig. 6.18 shows the spectrum of an ∼ 8 nL volume of ethylbenzene. The narrow lines demonstrate the high resolution that is possible with this approach. Similar coils can be used as magnets [6.48], springs [6.32], and electrical transformers [6.49]. Figure 6.19 shows an optical micrograph and the electrical measurements from a concentric cylindrical microtransformer that uses a microcoil printed on a microcapillary tube with a ferromagnetic wire threaded through its core. Inserting this



Fig. 6.17 Multilayer thin film capacitor structure printed in a single step onto a plastic substrate using the nanotransfer printing technique. A multilayer of Au/SiN_x/Ti/Au was first deposited onto a silicon stamp formed by photolithography and etching. Contacting this stamp to a substrate of Au/PDMS/PET forms a cold weld that bonds the exposed Au on the stamp to the Au coating on the substrate. Removing the stamp produces arrays of square (250 μm × 250 μm) metal/insulator/metal capacitors on the plastic support. The *black line* shows the measured current–voltage characteristics of one of these printed capacitors. The *brown line* corresponds to a similar structure formed on a rigid glass substrate using conventional photolithographic procedures. The characteristics are the same for these two cases. The slightly higher level of noise in the printed devices results, at least partly, from the difficulty in making good electrical contacts to structures on the flexible plastic substrate



Fig. 6.18 The *top frame* shows an optical micrograph of a continuous conducting microcoil formed by microcontact printing onto a microcapillary tube. This type of printed microcoil is well suited for excitation and detection of nuclear magnetic resonance spectra from nanoliter volumes of fluid housed in the bore of the microcapillary. The *bottom frame* shows a spectra trace collected from an ∼ 8 nL volume of ethyl benzene using a structure similar to the one shown in the top frame



Fig. 6.19 The *inset* shows a concentric microtransformer formed using microcoils printed onto two different microcapillary tubes. The smaller of the tubes (outer diameter 135 microns) has a ferromagnetic wire threaded through its core. The larger one (outer diameter 350 microns) has the smaller tube threaded through its core. The resulting structure is a microtransformer that shows good coupling coefficients at frequencies up to ∼ 1 MHz. The graph shows its performance

structure into the core of a larger microcapillary that also supports a printed microcoil completes the transformer [6.49]. This type of device shows good coupling coefficients up to relatively high frequencies. Examples of other optoelectronic components appear in fiber optics where microfabricated on-fiber structures serve as integrated photomasks [6.16] and distributed thermal actuators [6.18].

6.4.2 Lasers and Waveguide Structures

In addition to integral components of unconventional electronic systems, useful structures for integrated optics can be built by using µCP and nTP to print sacrificial resist layers for etching glass waveguides. These printing techniques offer the most significant potential value for this area when they are used to pattern fea-

Fig. 6.20 ▶ Schematic illustration of the use of microcontact printing (µCP) for fabricating high resolution gratings that can be incorporated into distributed planar laser structures or other components for integrated optics. The geometries illustrated here are suitable for 3rd order distributed feedback (DFB) lasers that operate in the red


Photolithography,
reactive ion etching
~ 1 mm
300 nm
~ 1 mm
Oxide
Silicon
50 – 150 nm
Cast elastomer against
etched oxide, remove from oxide
Elastomer
Ink stamp with HDT,
microcontact print
on gold, etch gold
Lines of gold
(thickness
~ 20 nm)
Glass slide
Reactive ion tech,
remove gold
300 nm
50 – 150 nm

Fig. 6.21 ▶ Schematic illustrations and lasing spectra of plastic lasers that use microcontact printed resonators based on surface relief distributed Bragg reflectors (DBRs) and distributed feedback gratings (DFBs) on glass substrates. The grating periods are ∼ 600 nm in both cases. The lasers use thin film plastic gain media deposited onto the printed gratings. The laser shows emission in a narrow wavelength range, with a width that is limited by the resolution of the spectrometer used to characterize the output. In both cases, the emission profiles, the lasing thresholds and other characteristics of the devices are comparable to similar lasers that use resonators formed by high resolution projection mode photolithography



tures that are smaller than those that can be achieved with contact mode photolithography. Mode coupling gratings and distributed laser resonators are two such classes of structures. We have demonstrated µCP for forming distributed feedback (DFB) and distributed Bragg reflector (DBR) lasers that have narrow emission line widths [6.50]. This challenging fabrication


Elastomer
Gold-coated oxide
2 µm
Silicon
Print, etch
300 nm
Gold
10 µm
Oxide
Reactive ion etch exposed oxide
5 – 50 nm
Remove gold
~ 1 mm
~ 1 mm
10 µm
Intensity (arb. units)
620
630
640
650
660
Wavelength (nm)

Fig. 6.22 The *top frames* gives a schematic illustration of steps for microcontact printing high resolution gratings directly onto the top surfaces of ridge waveguides. The printing defines a sacrificial etch mask of gold that is subsequently removed. Producing this type of structure with photolithography is difficult because of severe thickness nonuniformities that appear in photoresist spin cast on this type of non-planar substrate. The *upper bottom frame* shows a top view optical micrograph of printed gold lines on the ridge waveguides. The *lower bottom frame* shows the emission output of a plastic photopumped laser that uses the printed structure and a thin evaporated layer of gain media

demonstrates the suitability of μCP for building structures that have (1) feature sizes significantly less than one micron (∼ 300 nm), *and* (2) long-range spatial coherence (∼ 1 mm). The lasers employ optically pumped gain material deposited onto DFB or DBR resonators formed from periodic relief on a transparent substrate. The gain media confines light to the surface of the structure; its thickness is chosen to support a single transverse mode. To generate the required relief, lines of gold formed by μCP on a glass slide act as resists for reactive ion etching of the glass. Removing the gold leaves a periodic pattern of relief (600 nm period, 50 nm depth) on the surface of the glass (see Fig. 6.20). Figure 6.21 shows the performance of plastic lasers that use printed DFB and DBR resonators with gain media consisting of thin films of PBD doped with 1% by weight of coumarin 490 and DCMII, photopumped with 2 ns pulses from a nitrogen laser with intensities $> 5\,\mathrm{kW/cm^2}$ [6.50]. Multimode lasing at resolution-limited line widths was observed at wavelengths corresponding to the third harmonic of the gratings. These characteristics are similar to those observed in lasers that use resonators generated with photolithography and better than those that use imprinted polymers [6.51].

Contact printing not only provides a route to low cost equivalents of gratings fabricated with other approaches, but also allows the fabrication of structures that would be difficult or impossible to generate with photolithography. For example, μCP can be used to form DFB resonators directly on the top surfaces of ridge waveguides [6.52]. Figure 6.22 illustrates the procedures. The bottom left frame shows an optical micrograph of the printed gold lines. Sublimation of a ∼ 200 nm film of tris(8-hydroxyquinoline) aluminum (Alq) doped with 0.5–5.0 weight percent of the laser dye DCMII onto the resonators produces waveguide DFB lasers. The layer of gain material itself provides a planar waveguide with air and polymer as the cladding layers. The relief waveguide provides lateral confinement of the light. Photopumping these devices with the output of a pulsed nitrogen laser (∼ 2 ns, 337 nm) causes lasing due to Bragg reflections induced by the DFB structures on the top surfaces of the ridge waveguides. Some of the laser emission scatters out of the plane of the waveguide at an angle allowed by phase matching conditions. In this way, the grating also functions as an output coupler and offers a convenient way to characterize the laser emission. The bottom right frame of Fig. 6.22 shows the emission profile.

6.5 Conclusions

This chapter provides an overview of two contact printing techniques that are capable of micron and submicron resolution. It also illustrates some applications of these methods that may provide attractive alternatives to more established lithographic methods. The growing interest in nanoscience and technology makes crucial the development of new methods for fabricating the relevant test structures and devices. The simplicity of the techniques described here, together with the interesting and subtle materials science, chemistry, and physics associated with them, make this a promising area for basic and applied study.

References

6.1 C. A. Mirkin, J. A. Rogers: Emerging methods for micro- and nanofabrication, MRS Bull. **26** (2001) 506–507

6.2 H. I. Smith, H. G. Craighead: Nanofabrication, Phys. Today **43** (February 1990) 24–43

6.3 W. M. Moreau (Ed.): *Semiconductor Lithography: Principles and Materials* (Plenum, New York 1988)

6.4 S. Matsui, Y. Ochiai: Focused ion beam applications to solid state devices, Nanotechnology **7** (1996) 247–258

6.5 J. M. Gibson: Reading and writing with electron beams, Phys. Today **50** (1997) 56–61

6.6 L. L. Sohn, R. L. Willett: Fabrication of nanostructures using atomic-force microscope-based lithography, Appl. Phys. Lett. **67** (1995) 1552–1554

6.7 E. Betzig, K. Trautman: Near-Field optics – microscopy, spectroscopy, and surface modification beyond the diffraction limit, Science **257** (1992) 189–195

6.8 A. J. Bard, G. Denault, C. Lee, D. Mandler, D. O. Wipf: Scanning electrochemical microscopy: A new technique for the characterization and modification of surfaces, Acc. Chem. Res. **23** (1990) 357

6.9 J. A. Stroscio, D. M. Eigler: Atomic and molecular manipulation with the scanning tunneling microscope, Science **254** (1991) 1319–1326

6.10 J. Nole: Holographic lithography needs no mask, Laser Focus World **33** (1997) 209–212

6.11 A. N. Broers, A. C. F. Hoole, J. M. Ryan: Electron beam lithography – resolution limits, Microelectron. Eng. **32** (1996) 131–142

6.12 A. N. Broers, W. Molzen, J. Cuomo, N. Wittels: Electron-beam fabrication of 80 A metal structures, Appl. Phys. Lett. **29** (1976) 596

6.13 A. Kumar, G. M. Whitesides: Features of gold having micrometer to centimeter dimensions can be formed through a combination of stamping with an elastomeric stamp and an alkanethiol ink followed by chemical etching, Appl. Phys. Lett. **63** (1993) 2002–2004

6.14 Y. Xia, G. M. Whitesides: Soft lithography, Angew. Chem. Int. Ed. **37** (1998) 550–575

6.15 Y. Xia, J. A. Rogers, K. E. Paul, G. M. Whitesides: Unconventional methods for fabricating and patterning nanostructures, Chem. Rev. **99** (1999) 1823–1848

6.16 J. A. Rogers, R. J. Jackman, J. L. Wagener, A. M. Vengsarkar, G. M. Whitesides: Using microcontact printing to generate photomasks on the surface of optical fibers: A new method for producing in-fiber gratings, Appl. Phys. Lett. **70** (1997) 7–9

6.17 B. Michel, A. Bernard, A. Bietsch, E. Delamarche, M. Geissler, D. Juncker, H. Kind, J. P. Renault, H. Rothuizen, H. Schmid, P. Schmidt-Winkel, R. Stutz, H. Wolf: Printing meets lithography: Soft approaches to high-resolution printing, IBM J. Res. Dev. **45** (2001) 697–719

6.18 J. A. Rogers: Rubber stamping for plastic electronics and fiber optics, MRS Bull. **26** (2001) 530–534

6.19 N. B. Larsen, H. Biebuyck, E. Delamarche, B. Michel: Order in microcontact printed self-assembled monolayers, J. Am. Chem. Soc. **119** (1997) 3017–3026

6.20 H. A. Biebuyck, G. M. Whitesides: Self-organization of organic liquids on patterned self-assembled monolayers of alkanethiolates on gold, Langmuir **10** (1994) 2790–2793

6.21 J. A. Rogers, Z. Bao, K. Baldwin, A. Dodabalapur, B. Crone, V. R. Raju, V. Kuck, H. Katz, K. Amundson, J. Ewing, P. Drzaic: Paper-like electronic displays: Large area, rubber stamped plastic sheets of electronics and electrophoretic inks, Proc. Nat. Acad. Sci. **98** (2001) 4835–4840

6.22 J. L. Wilbur, H. A. Biebuyck, J. C. MacDonald, G. M. Whitesides: Scanning force microscopies can image patterned self-assembled monolayers, Langmuir **11** (1995) 825–831

6.23 J. C. Love, D. B. Wolfe, M. L. Chabinyc, K. E. Paul, G. M. Whitesides: Self-assembled monolayers of alkanethiolates on palladium are good etch resists, J. Am. Chem. Soc. **124** (2002) 1576–1577

6.24 H. Schmid, B. Michel: Siloxane polymers for high-resolution, high-accuracy soft lithography, Macromolecules **33** (2000) 3042–3049

6.25 K. Choi, J. A. Rogers: A photocurable poly(dimethylsiloxane) chemistry for soft lithography in the nanometer regime, J. Am. Chem. Soc. **125** (2003) 4060–4061

6.26 J. A. Rogers K. E. Paul, G. M. Whitesides: Quantifying distortions in soft lithography, J. Vac. Sci. Technol. B **16** (1998) 88–97

6.27 J. Tate, J. A. Rogers, C. D. W. Jones, W. Li, Z. Bao, D. W. Murphy, R. E. Slusher, A. Dodabalapur, H. E. Katz, A. J. Lovinger: Anodization and microcontact printing on electroless silver: Solution-based fabrication procedures for low voltage organic electronic systems, Langmuir **16** (2000) 6054–6060

6.28 Y. Xia, E. Kim, G. M. Whitesides: Microcontact printing of alkanethiols on silver and its application to microfabrication, J. Electrochem. Soc. **143** (1996) 1070–1079

6.29 Y. N. Xia, X. M. Zhao, E. Kim, G. M. Whitesides: A selective etching solution for use with patterned self-assembled monolayers of alkanethiolates on gold, Chem. Mater. **7** (1995) 2332–2337

6.30 R. J. Jackman, J. Wilbur, G. M. Whitesides: Fabrication of submicrometer features on curved substrates by microcontact printing, Science **269** (1995) 664–666

6.31 R. J. Jackman, S. T. Brittain, A. Adams, M. G. Prentiss, G. M. Whitesides: Design and fabrication of topologically complex, three-dimensional microstructures, Science **280** (1998) 2089–2091

6.32 J. A. Rogers, R. J. Jackman, G. M. Whitesides: Microcontact printing and electroplating on curved substrates: a new means for producing free-standing three-dimensional microstructures with possible applications ranging from micro-coil springs to coronary stents, Adv. Mater. **9** (1997) 475–477

6.33 Y.-L. Loo, R. W. Willett, K. Baldwin, J. A. Rogers: Additive, nanoscale patterning of metal films with a stamp and a surface chemistry mediated transfer process: Applications in plastic electronics, Appl. Phys. Lett. **81** (2002) 562–564

6.34 Y.-L. Loo, R. W. Willett, K. Baldwin, J. A. Rogers: Interfacial chemistries for nanoscale transfer printing, J. Am. Chem. Soc. **124** (2002) 7654–7655

6.35 Y.-L. Loo, J. W. P. Hsu, R. L. Willett, K. W. Baldwin, K. W. West, J. A. Rogers: High-resolution transfer printing on GaAs surfaces using alkane dithiol self-assembled monolayers, J. Vac. Sci. Technol. B. **20** (2002) 2853–2856

6.36 G. S. Ferguson, M. K. Chaudhury, G. B. Sigal, G. M. Whitesides: Contact adhesion of thin gold-films on elastomeric supports – cold welding under ambient conditions, Science **253** (1991) 776–778

6.37 W. Zhang, S. Y. Chou: Multilevel nanoimprint lithography with submicron alignment over 4 in Si wafers, Appl. Phys. Lett. **79** (2001) 845–847

6.38 N. Bowden, S. Brittain, A. G. Evans, J. W. Hutchinson, G. M. Whitesides: Spontaneous formation of ordered structures in thin films of metals supported on an elastomeric polymer, Nature **393** (1998) 146–149
6.39 J. A. Rogers, Z. Bao, A. Dodabalapur, A. Makhija: Organic smart pixels and complementary inverter circuits formed on plastic substrates by casting, printing and molding, IEEE Electron Dev. Lett. **21** (2000) 100–103
6.40 Z. Bao, J. A. Rogers, H. E. Katz: Printable organic and polymeric semiconducting materials and devices, J. Mater. Chem. **9** (1999) 1895–1904
6.41 J. A. Rogers, Z. Bao, A. Makhija: Non-photolithographic fabrication sequence suitable for reel-to-reel production of high performance organic transistors and circuits that incorporate them, Adv. Mater. **11** (1999) 741–745
6.42 P. Mach, S. Rodriguez, R. Nortrup, P. Wiltzius, J. A. Rogers: Active matrix displays that use printed organic transistors and polymer dispersed liquid crystals on flexible substrates, Appl. Phys. Lett. **78** (2001) 3592–3594
6.43 J. A. Rogers: Toward paperlike displays, Science **291** (2001) 1502–1503
6.44 Y.-L. Loo, T. Someya, K. W. Baldwin, P. Ho, Z. Bao, A. Dodabalapur, H. E. Katz, J. A. Rogers: Soft, conformable electrical contacts for organic transistors: High resolution circuits by lamination, Proc. Nat. Acad. Sci. USA **99** (2002) 10252–10256
6.45 C. Kim, P. E. Burrows, S. R. Forrest: Micropatterning of organic electronic devices by cold-welding, Science **288** (2000) 831–833
6.46 C. Kim, M. Shtein, S. R. Forrest: Nanolithography based on patterned metal transfer and its application to organic electronic devices, Appl. Phys. Lett. **80** (2002) 4051–4053
6.47 J. A. Rogers, R. J. Jackman G. M. Whitesides, D. L. Olson, J. V. Sweedler: Using microcontact printing to fabricate microcoils on capillaries for high resolution ^{1}H-NMR on nanoliter volumes, Appl. Phys. Lett. **70** (1997) 2464–2466
6.48 J. A. Rogers, R. J. Jackman, G. M. Whitesides: Constructing single and multiple helical microcoils and characterizing their performance as components of microinductors and microelectromagnets, J. Microelectromech. Syst. (JMEMS) **6** (1997) 184–192
6.49 R. J. Jackman, J. A. Rogers, G. M. Whitesides: Fabrication and characterization of a concentric, cylindrical microtransformer, IEEE Trans. Magn. **33** (1997) 2501–2503
6.50 J. A. Rogers, M. Meier, A. Dodabalapur: Using stamping and molding techniques to produce distributed feedback and Bragg reflector resonators for plastic lasers, Appl. Phys. Lett. **73** (1998) 1766–1768
6.51 M. Berggren, A. Dodabalapur, R. E. Slusher, A. Timko, O. Nalamasu: Organic solid-state lasers with imprinted gratings on plastic substrates, Appl. Phys. Lett. **72** (1998) 410–411
6.52 J. A. Rogers, M. Meier, A. Dodabalapur: Distributed feedback ridge waveguide lasers fabricated by nanoscale printing and molding on non-planar substrates, Appl. Phys. Lett. **74** (1999) 3257–3259

7. Materials Aspects of Micro- and Nanoelectromechanical Systems

Two of the more significant technological achievements during the last 20 years have been the development of MEMS and its new offshoot, NEMS. These developments were made possible in large measure by significant advancements in the materials and processes used in the fabrication of MEMS and NEMS devices. And while initial developments capitalized on a mature Si infrastructure, recent advances have used materials and processes not associated with IC fabrication, a trend that is likely to continue as new application areas are identified.

A well-rounded understanding of MEMS and NEMS requires a basic knowledge of the materials used to construct the devices, since material properties often govern device performance. An understanding of the materials used in MEMS and NEMS is really an understanding of material systems. Devices are rarely constructed of a single material, but rather a collection of materials, each providing a critical function and often working in conjunction with each other. It is from this perspective that the following chapter is constructed. A preview of the materials selected for inclusion is presented in Table 7.1. From this table it is easy to see that this chapter is not a summary of all materials used in MEMS and NEMS, as such a work would itself constitute a text of significant size. It does, however, present a selection of some of the more important material systems, including examples that illustrate the importance of viewing MEMS and NEMS in terms of material systems.

7.1 **Silicon** ... 203
  7.1.1 Single Crystal Silicon ... 204
  7.1.2 Polysilicon ... 205
  7.1.3 Porous Silicon ... 208
  7.1.4 Silicon Dioxide ... 208
  7.1.5 Silicon Nitride ... 209

7.2 **Germanium-Based Materials** ... 210
  7.2.1 Polycrystalline Ge ... 210
  7.2.2 Polycrystalline SiGe ... 210

7.3 **Metals** ... 211

7.4 **Harsh Environment Semiconductors** ... 212
  7.4.1 Silicon Carbide ... 212
  7.4.2 Diamond ... 215

7.5 **GaAs, InP, and Related III-V Materials** ... 217

7.6 **Ferroelectric Materials** ... 218

7.7 **Polymer Materials** ... 219
  7.7.1 Polyimide ... 219
  7.7.2 SU-8 ... 220
  7.7.3 Parylene ... 220

7.8 **Future Trends** ... 220

References ... 221

7.1 Silicon

Use of silicon (Si) as a material for microfabricated sensors dates back to the 1950s when *C. S. Smith* published a paper describing the piezoresistive effect in germanium (Ge) and Si [7.1]. *Smith* found that the piezoresistive coefficients of Si were significantly higher than those associated with conventional metal strain gauges, a finding that led to the development of Si strain gauges in the early 1960s. Throughout the 1960s and early 1970s, various Si bulk micromachining techniques were developed, which ultimately led to the commercial production of piezoresistive Si pressure sensors during this period. The subsequent development of surface micromachining techniques for Si, along with the recognition that micromachined Si structures could potentially be integrated with Si IC devices, marked the advent of MEMS and positioned Si as the primary MEMS material.

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Table 7.1 Distinguishing characteristics and application examples of selected materials for MEMS and NEMS

Material	Distinguishing Characteristics	Application Examples
Single crystal Silicon (Si)	High quality electronic material, selective anisotropic etching	Bulk micromachining, piezoresistive sensing
Polycrystalline Si (polysilicon)	Doped Si films on sacrificial layers	Surface micromachining, electrostatic actuation
Silicon Dioxide (SiO_2)	Insulating, etched by HF, compatible with polysilicon	Sacrificial layer in polysilicon surface micromachining, passivation layer for devices
Silicon Nitride (Si_3N_4, Si_xN_y)	Insulating, chemically resistant, mechanically durable	Isolation layer for electrostatic devices, membrane and bridge material
Polycrystalline Germanium (poly Ge), Polycrystalline Silicon-Germanium (poly Si-Ge)	Deposited at low temperatures	Integrated surface micromachined MEMS
Gold (Au), Aluminum (Al)	Conductive thin films, flexible deposition techniques	Innerconnect layers, masking layers, electromechanical switches
Nickel-Iron (NiFe)	Magnetic alloy	Magnetic actuation
Titanium-Nickel (TiNi)	Shape-memory alloy	Thermal actuation
Silicon Carbide (SiC) Diamond	Electrically and mechanically stable at high temperatures, chemically inert, high Young's modulus to density ratio	Harsh environment MEMS, high frequency MEMS/NEMS
Gallium Arsenide (GaAs), Indium Phosphide (InP), Indium Arsenide (InAs), and related materials	Wide bandgap, epitaxial growth on related ternary compounds	RF MEMS, optoelectronic devices, single crystal bulk and surface micromachining
Lead Zirconate Titanate (PZT)	Piezoelectric material	Mechanical sensors and actuators
Polyimide	Chemically resistant, high temperature polymer	Mechanically flexible MEMS, bioMEMS
SU-8	Thick, photo-definable resist	Micromolding, high-aspect-ratio structures
Parylene	Biocompatible polymer, deposited at room temperature by CVD	Protective coatings, molded polymer structures

7.1.1 Single Crystal Silicon

For MEMS applications, single crystal Si serves several key functions. It is one of the most versatile materials for bulk micromachining, due to the availability of anisotropic etching processes in conjunction with good mechanical properties. Having a Young's modulus of about 190 GPa, Si compares favorably, from a mechanical perspective, with steel, which has a Young's modulus of about 210 GPa. Favorable mechanical properties enable Si to be used as a material for membranes, beams, and other such structures. For surface micromachining applications, single crystal Si substrates are used primarily as mechanical platforms on which Si and non-Si device structures can be fabricated. Use of high-quality single crystal wafers enables the fabrication of integrated MEMS devices, at least for materials and processes that are compatible with Si ICs.

Bulk micromachining is a process whereby etching techniques are used in conjunction with etch masks and etch stops to selectively sculpt micromechanical structures from a bulk substrate. From the materials perspective, single crystal Si is a relatively easy material to bulk micromachine, due to the availability of anisotropic etchants, such as potassium hydroxide (KOH) and tetramethyl-aluminum hydroxide (TMAH), that attack the (100) and (110) Si crystal planes significantly faster than the (111) crystal planes. For example, the etching rate ratio of (100) to (111) planes in Si is about 400:1 for a typical KOH/water etch solution. Silicon dioxide (SiO_2), silicon nitride (Si_3N_4), and some metallic thin films (e.g., Cr, Au, etc.) provide good etch masks for most Si anisotropic etchants.

In contrast to anisotropic etching, isotropic etching exhibits no selectivity to the various crystal planes. From a processing perspective, isotropic etching of Si is commonly used for removal of work-damaged surfaces, creation of structures in single-crystal slices, and patterning single-crystal or polycrystalline films. The most commonly used isotropic Si etchants are mixtures of hydrofluoric (HF) and nitric (HNO_3) acid in water or acetic acid (CH_3COOH), with the etch rate dependent on the ratio of HF to HNO_3.

In terms of etch stops, boron-doped Si is effective for some liquid reagents. Boron-doped etch stops are often less than 10 μm thick, since the boron concentration in Si must exceed $7 \times 10^{19}\,cm^3$ for the etch stop to be effective, and the doping is done by diffusion. It is possible to create a boron-doped etch stop below an undoped Si layer using ion implantation; however, the practical implant depth is limited to a few microns.

Well-established dry etching processes are available to pattern single crystal Si. The process spectrum ranges from physical mechanisms such as sputtering and ion milling to chemical mechanisms such as plasma etching. Reactive ion etching (RIE) is the most commonly used dry etching technique to etch Si. By combining both physical and chemical processes, RIE is a highly effective anisotropic Si etching technique that is independent of crystalline orientation. Fluorinated compounds such as CF_4, SF_6, and NF_3, or chlorinated compounds such as CCl_4 or Cl_2, sometimes mixed with He, O_2, or H_2, are commonly used in Si RIE. The RIE process is highly directional, which enables direct pattern transfer from an overlying masking material to the etched Si surface. SiO_2 thin films are often used as a masking material, owing to its chemical durability and ease in patterning. Process limitations (i. e., etch rates) restrict the etch depths of Si RIE to less than 10 microns. However, a process called deep reactive ion etching (DRIE) has extended the use of anisotropic dry etching to depths well beyond several hundred microns.

Using the aforementioned processes and techniques, a wide variety of microfabricated devices have been made from single crystal Si, such as piezoresistive pressure sensors, accelerometers, and mechanical resonators, to name a few. Using nearly the same approaches but on a smaller scale, top-down nanomachining techniques have been used to fabricate nanoelectromechanical devices from single crystal Si. Single crystal Si is particularly well-suited for nanofabrication, because high crystal quality substrates with very smooth surfaces are readily available. By coupling electron-beam (e-beam) lithographic techniques with conventional Si etching, device structures with submicron dimensions have been fabricated. Submicron, single crystal Si nanomechanical structures have been successfully micromachined from bulk Si wafers [7.2] and silicon-on-insulator (SOI) wafers [7.3]. In the former case, an isotropic Si etch was performed to release the device structures, whereas in the latter, the 50 nm to 200 nm structures were released by dissolving the underlying oxide layer in HF. An example of nanoelectromechanical beam structures fabricated from a single crystal Si substrate is shown in Fig. 7.1.


Fig. 7.1 A collection of Si nanoelectromechanical beam resonators fabricated from a single-crystal Si substrate (courtesy M. Roukes, Caltech)

7.1.2 Polysilicon

Surface micromachining is a process whereby a sequence of thin films, often of different materials, is deposited and selectively etched to form the desired micromechanical (or microelectromechanical) structure. In contrast to bulk micromachining, the substrate serves primarily as a platform to support the device. For Si-based surface micromachined MEMS, polycrystalline Si (polysilicon) is most often used as the structural material, silicon dioxide (SiO_2) as the sacrificial material, silicon nitride (Si_3N_4) for electrical isolation of device structures, and single crystal Si as the substrate. Like single crystal Si, polysilicon can be doped during or after film deposition. SiO_2 can be thermally grown or deposited on Si over a broad temperature range (e.g., 200 °C to 1,150 °C) to meet various process and material



Fig. 7.2 SEM micrograph of a surface-micromachined polysilicon micromotor fabricated using a SiO_2 sacrificial layer

requirements. SiO_2 is readily dissolvable in hydrofluoric acid (HF), which does not etch polysilicon and, thus, can be used to dissolve SiO_2 sacrificial layers. Si_3N_4 is an insulating film that is highly resistant to oxide etchants. The polysilicon micromotor shown in Fig. 7.2 was surface micromachined using a process that included these materials.

For MEMS and IC applications, polysilicon films are commonly deposited using a process known as low-pressure chemical vapor deposition (LPCVD). The typical polysilicon LPCVD reactor is based on a hot wall, resistance-heated furnace. Typical processes are performed at temperatures ranging from 580 °C to 650 °C and pressures from 100 to 400 mtorr. The most commonly used source gas is silane (SiH_4).



Fig. 7.3 Deposition rate versus substrate temperature for in situ boron-doped (◇) and undoped (●) polysilicon films grown by atmospheric pressure chemical vapor deposition [7.4]

Polysilicon thin films consist of a collection of small single crystal grains whose microstructure and orientation is a function of the deposition conditions [7.5]. For typical LPCVD processes (e.g., 200 mtorr), the amorphous-to-polycrystalline transition temperature is about 570 °C, with amorphous films deposited below the transition temperature. At 600 °C, the grains are small and equiaxed, while at 625 °C, the grains are large and columnar [7.5]. The crystal orientation is predominantly (110) Si for temperatures between 600 °C and 650 °C, while the (100) orientation is dominant for temperatures between 650 °C and 700 °C.

In terms of chemical resistance, polysilicon is very much like single crystal Si. The oxidation rate of undoped polysilicon is typically between that of (100)- and (111)-oriented single crystal Si. For temperatures below 1,000 °C, heavily phosphorus-doped polysilicon oxidizes at a rate significantly higher than undoped polysilicon.

The resistivity of polysilicon can be modified using the doping methods developed for single crystal Si. Diffusion is an effective method for doping polysilicon films, especially for heavy doping of thick films. Phosphorous, which is the most commonly used dopant in polysilicon MEMS, diffuses significantly faster in polysilicon than in single crystal Si, due primarily to enhanced diffusion rates along grain boundaries. The diffusivity in polysilicon thin films (i. e., small equiaxed grains) is about $1 \times 10^{12}\ \mathrm{cm}^2/\mathrm{s}$.

Ion implantation is also used to dope polysilicon films. A high-temperature annealing step is usually required to electrically activate the implanted dopants, as well as to repair implant-related damage in the polysilicon films. In general, the conductivity of implanted polysilicon films is not as high as films doped by diffusion.

In situ doping of polysilicon is performed by simply including a dopant gas, usually diborane (B_2H_6) or phosphine (PH_3), in the CVD process. The addition of dopants during the deposition process not only modifies the conductivity, but also affects the deposition rate of the polysilicon films. As shown in Fig. 7.3, the inclusion of boron generally increases the deposition rate of polysilicon relative to undoped films [7.4], while phosphorus (not shown) reduces the rate. In situ doping can be used to produce conductive films with uniform doping profiles without requiring the high-temperature steps usually associated with diffusion or ion implantation. Although commonly used to produce doped polysilicon for electrostatic devices, *Cao* et al. [7.6] have used in situ phosphorus-doped polysilicon films in piezoresistive strain gauges, achieving gauge factors as high as 15 for a single strip sensor.

The thermal conductivity of polysilicon is a strong function of its microstructure and, therefore, the conditions used during deposition [7.5]. For fine-grained films, the thermal conductivity is about 25% of the value of single crystal Si. For thick films with large grains, the thermal conductivity ranges between 50% and 85% of the single crystal value.

Like the electrical and thermal properties of polysilicon, the as-deposited residual stress in polysilicon films depends on microstructure. For films deposited under typical conditions (200 mtorr, 625 °C), the as-deposited polysilicon films have compressive residual stresses. The highest compressive stresses are found in amorphous Si films and polysilicon films with a strong, columnar (110) texture. For films with fine-grained microstructures, the stress tends to be tensile. Annealing can be used to reduce the compressive stress in as-deposited polysilicon films. For instance, compressive residual stresses on the order of 500 MPa can be reduced to less than 10 MPa by annealing the as-deposited films at 1,000 °C in a N_2 ambient [7.7, 8]. Recent advances in the area of rapid thermal annealing (RTA) indicate that RTA provides an effective method of stress reduction in polysilicon films. *Zhang* et al. [7.9] reported that a 10 s anneal at 1,100 °C was sufficient to completely relieve the stress in films that originally had a compressive stress of about 340 MPa. RTA is particularly attractive in situations where the process parameters require a low thermal budget.

As an alternative to high-temperature annealing, *Yang* et al. [7.10] have developed an approach that actually utilizes the residual stress characteristics of polysilicon deposited under various conditions to construct polysilicon multilayers that have the desired thickness and stress values. The multilayers are comprised of alternating tensile and compressive polysilicon layers that are deposited in a sequential manner. The tensile layers consist of fine-grained polysilicon grown at a temperature of 570 °C, while the compressive layers are made up of columnar polysilicon deposited at 615 °C. The overall stress in the composite film depends on the number of alternating layers and the thickness of each layer. With the proper set of parameters, a composite polysilicon multilayer can be deposited with near zero residual stress and no stress gradient. The process achieves stress reduction without high-temperature annealing, a considerable advantage for integrated MEMS processes.

Many device designs require thick polysilicon structural layers that are not readily achievable using conventional LPCVD polysilicon, due to process-related limitations. For these designs, epitaxial Si reactors can be used to grow polysilicon films. Unlike conventional LPCVD processes with deposition rates of less than 100 Å/min, epitaxial processes have deposition rates on the order of 1 micron/min [7.11]. The high deposition rates result from the much higher substrate temperatures ($> 1{,}000$ °C) and deposition pressures (> 50 torr) used in these processes. The polysilicon films are usually deposited on SiO_2 sacrificial layers to enable surface micromachining. An LPCVD polysilicon seed layer is sometimes used to control nucleation, grain size, and surface roughness. As with conventional polysilicon, the microstructure and residual stress of the epi-poly films, as they are known, is related to deposition conditions. Compressive films generally have a mixture of [110] and [311] grains [7.12, 13], while tensile films have a random mix of [110], [100], [111], and [311] grains [7.12]. The Young's modulus of epi-poly measured from micromachined test structures is comparable to LPCVD polysilicon [7.13]. Mechanical properties test structures [7.11–13], thermal actuators [7.11], electrostatically actuated accelerometers [7.11], and gryoscopes [7.14] have been fabricated from these films.

All of the aforementioned polysilicon deposition processes utilize substrate temperatures in excess of 570 °C either during film deposition, or in post-deposition processing steps. As a low temperature alternative to LPCVD polysilicon, *Abe* et al. [7.15] and *Honer* et al. [7.16] have developed sputtering processes for polysilicon. Early work [7.15] emphasized the ability to deposit very smooth (25 Å) polysilicon films on thermally oxidized wafers at reasonable deposition rates (191 Å/min) and with low residual compressive stresses. The process involved DC magnitron sputtering from a Si target using an Ar sputtering gas, a chamber pressure of 5 mtorr, and a power of 100 W. The authors reported that a post-deposition anneal at 700 °C in N_2 for two hours was needed to crystallize the deposited film and perhaps lower the stress. *Honer* et al. [7.16] sought to develop a polymer-friendly, Si-based surface micromachining process based on polysilicon sputtered onto polyimide and PSG sacrificial layers. To improve the conductivity of the micromachined Si structures, the sputtered Si films were sandwiched between two TiW cladding layers. The device structures on polyimide were released using oxygen plasma etching. The processing step with the highest temperature was, in fact, the polyimide cure at 350 °C. To test the robustness of the process, sputter-deposited Si microstructures were fabricated on substrates containing CMOS devices. As expected from thermal budget considerations, the authors reported no measurable degradation of device performance.

7.1.3 Porous Silicon

Porous Si is produced by room temperature electrochemical etching of Si in HF. If configured as an electrode in an HF-based electrochemical circuit, positive charge carriers (holes) at the Si surface facilitate the exchange of F atoms with H atoms, that terminate the Si surface. The exchange continues in the subsurface region, leading to the eventual removal of the fluorinated Si. The quality of the etched surface is related to the density of holes at the surface, which is controlled by the applied current density. For high current densities, the density of holes is high and the etched surface is smooth. For low current densities, the hole density is low and clustered in highly localized regions associated with surface defects. Surface defects become enlarged by etching, which leads to the formation of pores. Pore size and density are related to the type of Si used and the conditions of the electrochemical cell. Both single crystal and polycrystalline Si can be converted to porous Si.

The large surface-to-volume ratios make porous Si attractive for gaseous and liquid applications, including filter membranes and absorbing layers for chemical and mass sensing [7.17]. When single crystal substrates are used, the unetched porous layer remains single crystalline and is suitable for epitaxial Si growth. It has been shown that CVD coatings do not generally penetrate the porous regions, but rather overcoat the pores at the surface of the substrate [7.18]. The formation of localized Si-on-insulator structures is, therefore, possible by simply combining pore formation with epitaxial growth, followed by dry etching to create access holes to the porous region, and thermal oxidation of the underlying porous region. A third application uses porous Si as a sacrificial layer for polysilicon and single crystalline Si surface micromachining. As shown by *Lang* et al. [7.18], the process involves the electrical isolation of the solid structural Si layer by either pn-junction formation through selective doping, or use of electrically insulating thin films, since the formation of pores only occurs on electrically charged surfaces. A weak Si etchant will aggressively attack the porous regions with little damage to the structural Si layers and can be used to release the devices.

7.1.4 Silicon Dioxide

Silicon dioxide (SiO_2) is one of the most widely used materials in the fabrication of MEMS. In polysilicon surface micromachining, SiO_2 is used as a sacrificial material, since it can be easily dissolved using etchants that do not attack polysilicon. SiO_2 is widely used as etch mask for dry etching of thick polysilicon films, since it is chemically resistant to dry etching processes for polysilicon. SiO_2 films are also used as passivation layers on the surfaces of environmentally sensitive devices.

The most common processes used to produce SiO_2 films for polysilicon surface micromachining are thermal oxidation and LPCVD. Thermal oxidation of Si is performed at temperatures of 900 °C to 1,200 °C in the presence of oxygen or steam. Since thermal oxidation is a self-limiting process, the maximum practical film thickness that can be obtained is about 2 μm, which is sufficient for many sacrificial applications. As noted by its name, thermal oxidation of Si can only be performed on Si surfaces.

SiO_2 films can be deposited on a wide variety of substrate materials by LPCVD. In general, LPCVD provides a means for depositing thick (> 2 μm) SiO_2 films at temperatures much lower than thermal oxidation. Known as low-temperature oxides, or LTO for short, these films have a higher etch rate in HF than thermal oxides, which translates to significantly faster release times when LTO films are used as sacrificial layers. Phosphosilicate glass (PSG) can be formed using nearly the same deposition process as LTO by adding a phosphorus-containing gas to the precursor flows. PSG films are useful as sacrificial layers, since they generally have higher etching rates in HF than LTO films.

PSG and LTO films are deposited in hot-wall, low-pressure, fused silica furnaces in systems similar to those described previously for polysilicon. Precursor gases include SiH_4 as a Si source, O_2 as an oxygen source, and, in the case of PSG, PH_3 as a source of phosphorus. LTO and PSG films are typically deposited at temperatures of 425 °C to 450 °C and pressures ranging from 200 mtorr to 400 mtorr. The low deposition temperatures result in LTO and PSG films that are slightly less dense than thermal oxides, due to the incorporation of hydrogen in the films. LTO films can, however, be densified by an annealing step at high temperature (1,000 °C). The low density of LTO and PSG films is partially responsible for the increased etch rate in HF.

Thermal SiO_2 and LTO are electrical insulators used in numerous MEMS applications. The dielectric constants of thermal oxide and LTO are 3.9 and 4.3, respectively. The dielectric strength of thermal SiO_2 is 1.1×10^6 V/cm, and for LTO it is about 80% of that value [7.19]. The stress in thermal SiO_2 is compressive with a magnitude of about 300 MPa [7.19]. For LTO, however, the as-deposited residual stress is tensile, with a magnitude of about 100 MPa to 400 MPa [7.19]. The addition of phosphorous to LTO decreases the tensile residual stress to about 10 MPa for phosphorus concentrations of 8% [7.20]. As with polysilicon, the properties of LTO and PSG are dependent on processing conditions.

Plasma-enhanced chemical vapor deposition (PECVD) is another common method to produce oxides of silicon. Using a plasma to dissociate the gaseous precursors, the deposition temperatures needed to deposit PECVD oxide films is lower than for LPCVD films. For this reason, PECVD oxides are quite commonly used as masking, passivation, and protective layers, especially on devices that have been coated with metals.

Quartz is the crystalline form of SiO_2 and has interesting properties for MEMS. Quartz is optically transparent, piezoelectric, and electrically insulating. Like single crystal Si, quartz substrates are available as high quality, large area wafers that can be bulk micromachined using anisotropic etchants. A short review of the basics of quartz etching by *Danel* et al. [7.21] is recommended for those interested in the subject. Quartz has recently become a popular substrate material for microfluidic devices due to its optical, electronic, and chemical properties.

Another SiO_2-related material that has recently found uses in MEMS is spin-on-glass (SOG). SOG is a polymeric material with a viscosity suitable for spin coating. Two recent publications illustrate the potential for SOG in MEMS fabrication. In the first example, *Yasseen* et al. [7.22] detailed the development of SOG as a thick-film sacrificial molding material for thick polysilicon films. The authors reported a process to deposit, polish, and etch SOG films that were 20 microns thick. The thick SOG films were patterned into molds and filled with 10 micron-thick LPCVD polysilicon films, planarized by selective CMP, and subsequently dissolved in a wet etchant containing HCl, HF, and H_2O to reveal the patterned polysilicon structures. The cured SOG films were completely compatible with the polysilicon deposition process. In the second example, *Liu* et al. [7.23] fabricated high-aspect ratio channel plate microstructures from SOG. Electroplated nickel (Ni) was used as a molding material, with Ni channel plate molds fabricated using a conventional LIGA process. The Ni molds were then filled with SOG, and the sacrificial Ni molds were removed in a reverse electroplating process. In this case, the fabricated SOG structures (over 100 microns tall) were micromachined glass structures fabricated using a molding material more commonly used for structural components.

7.1.5 Silicon Nitride

Silicon nitride (Si_3N_4) is widely used in MEMS for electrical isolation, surface passivation, etch masking, and as a mechanical material. Two deposition methods are commonly used to deposit Si_3N_4 thin films: LPCVD and PECVD. PECVD silicon nitride is generally nonstoichiometric (sometimes denoted as $Si_xN_y:H$) and may contain significant concentrations of hydrogen. Use of PECVD silicon nitride in micromachining applications is somewhat limited because it has a high etch rate in HF (e.g., often higher than that of thermally grown SiO_2). However, PECVD offers the ability to deposit nearly stress-free silicon nitride films, an attractive property for encapsulation and packaging.

Unlike its PECVD counterpart, LPCVD Si_3N_4 is extremely resistant to chemical attack, making it the material of choice for many Si bulk and surface micromachining applications. LPCVD Si_3N_4 is commonly used as an insulating layer because it has a resistivity of 10^{16} $\Omega \times$cm and field breakdown limit of 10^7 V/cm. LPCVD Si_3N_4 films are deposited in horizontal furnaces similar to those used for polysilicon deposition. Typical deposition temperatures and pressures range between 700 °C to 900 °C and 200 mtorr to 500 mtorr, respectively. The standard source gases are dichlorosilane (SiH_2Cl_2) and ammonia (NH_3). To produce stoichiometric Si_3N_4, a NH_3 to SiH_2Cl_2 ratio of 10:1 is commonly used. The microstructure of films deposited under these conditions is amorphous.

The residual stress in stoichiometric Si_3N_4 is large and tensile, with a magnitude of about 1 GPa. Such a large residual stress causes films thicker than a few thousand angstroms to crack. Nonetheless, thin stoichiometric Si_3N_4 films have been used as mechanical support structures and electrical insulating layers in piezoresistive pressure sensors [7.24]. To enable the use of Si_3N_4 films for applications that require micron-thick, durable, and chemically resistant membranes, Si_xN_y films can be deposited by LPCVD. These films, often referred to as Si-rich or low-stress nitride, are intentionally deposited with an excess of Si by simply decreasing the ratio of NH_3 to SiH_2Cl_2 during deposition. Nearly stress-free films can be deposited using a NH_3 to SiH_2Cl_2 ratio of 1 : 6, a deposition temperature of 850 °C, and a pressure of 500 mtorr [7.25]. The increase in Si content not only leads to a reduction in tensile stress, but also a decrease in the etch rate in HF. Such properties have enabled the development of fabrication techniques that would otherwise not be feasible with stoichiometric Si_3N_4. For example, low stress silicon nitride has been bulk micromachined using silicon as the sacrificial material. In this case, an anisotropic Si etchant (TMAH) was used to dissolve the sacrificial silicon. *French* et al. [7.26] used PSG as a sacrificial layer to surface micromachine low-stress nitride, capitalizing on the HF resistance of the nitride films.

7.2 Germanium-Based Materials

Like Si, Ge has a long history as a semiconductor device material, dating back to the development of the earliest transistors and semiconductor strain gauges. Issues related to the water solubility of germanium oxide, however, stymied the development of Ge for microelectronic devices. Nonetheless, there is a renewed interest in using Ge in micromachined devices due to the relatively low processing temperatures required to deposit the material.

7.2.1 Polycrystalline Ge

Thin polycrystalline Ge (poly-Ge) films can be deposited by LPCVD at temperatures as low as 325 °C on Si, Ge, and SiGe substrates [7.27]. Ge does not nucleate on SiO_2 surfaces, which prohibits the use of thermal oxides and LTO films as sacrificial layers, but enables the use of these films as sacrificial molds. Residual stress in poly-Ge films deposited on Si substrates can be reduced to nearly zero after short anneals at modest temperatures (30 s at 600 °C). Poly-Ge is essentially impervious to KOH, TMAH, and BOE, enabling the fabrication of Ge membranes on Si substrates [7.27]. The mechanical properties of poly-Ge are comparable to polysilicon, having a Young's modulus of 132 GPa and a fracture stress between 1.5 GPa and 3.0 GPa [7.28]. Mixtures of HNO_3, H_2O, and HCl and H_2O, H_2O_2, and HCl, as well as the RCA SC-1 cleaning solution isotropically etch Ge. Since these mixtures do not etch Si, SiO_2, Si_3N_4, and SiN, poly-Ge can be used as a sacrificial substrate layer in polysilicon surface micromachining. Using these techniques, devices such as poly-Ge-based thermistors and Si_3N_4 membrane-based pressure sensors, made using poly-Ge sacrificial layers, have been fabricated [7.27]. *Franke* et al. [7.28] found no performance degradation in Si CMOS devices following the fabrication of surface micromachined poly-Ge structures, thus demonstrating the potential for on-chip integration of Ge electromechanical devices with Si circuitry.

7.2.2 Polycrystalline SiGe

Like poly-Ge, polycrystalline SiGe (poly-SiGe) is a material that can be deposited at temperatures lower than those required for polysilicon. Deposition processes include LPCVD, APCVD, and RTCVD (rapid thermal CVD) using SiH_4 and GeH_4 as precursor gases. Deposition temperatures range from 450 °C for LPCVD [7.29] to 625 °C by rapid thermal CVD (RTCVD) [7.30]. In general, the deposition temperature is related to the concentration of Ge in the films, with higher Ge concentrations resulting in lower deposition temperatures. Like polysilicon, poly-SiGe can be doped with boron and phosphorus to modify its conductivity. In situ boron doping can be performed at temperatures as low as 450 °C [7.29]. *Sedky* et al. [7.30] showed that the deposition temperature of conductive films doped with boron could be further reduced to 400 °C if the Ge content was kept at or above 70%.

Unlike poly-Ge, poly-SiGe can be deposited on a number of sacrificial substrates, including SiO_2 [7.30], PSG [7.28], and poly-Ge [7.28]. For Ge rich films, a thin polysilicon seed layer is sometimes used on SiO_2 surfaces since Ge does not readily nucleate on oxide surfaces. Like many compound materials, variations in film composition can change the physical properties of the material. For instance, etching of poly-SiGe by H_2O_2 becomes significant for Ge concentrations over 70%. *Sedky* et al. [7.31] have shown that the microstructure, film conductivity, residual-stress, and residual stress gradient are related to the concentration of Ge in the material. With respect to residual stress, *Franke* et al. [7.29] produced in situ boron-doped films with residual compressive stresses as low as 10 MPa.

The poly-SiGe, poly-Ge material system is particularly attractive for surface micromachining since H_2O_2 can be used as a release agent. It has been reported that poly-Ge etches at a rate of 0.4 microns/min in H_2O_2, while poly-SiGe with Ge concentrations below 80% have no observable etch rate after 40 hrs [7.32]. The ability to use H_2O_2 as a sacrificial etchant makes the combination of poly-SiGe and poly-Ge extremely attractive for surface micromachining from the processing, safety, and materials compatibility points of view. Due to the conformal nature of LPCVD processing, poly-SiGe structural elements, such as gimbal-based microactuator structures, have been made by high-aspect ratio micromolding [7.32]. Capitalizing on the low deposition temperatures, an integrated MEMS fabrication process with Si ICs has been demonstrated [7.29]. In this process, CMOS structures are first fabricated on Si wafers. Poly-SiGe mechanical structures are then surface micromachined using a poly-Ge sacrificial layer. A significant advantage of this design is that the MEMS structure is positioned directly above the CMOS structure, thus reducing the parasitic capacitance and contact resistance characteristic of interconnects associated with side-by-side integration schemes. Use of H_2O_2 as the sacrificial etchant means that no special protective layers are required to protect the underlying CMOS layer during release. In addition to its utility as a material for integrated MEMS devices, poly-SiGe has been identified as a material well suited for micromachined thermopiles [7.33] due to its lower thermal conductivity relative to Si.

7.3 Metals

It can be argued that of all the material categories associated with MEMS, metals may be among the most enabling, since metallic thin films are used in many different capacities ranging from etch masks used in device fabrication to interconnects and structural elements in microsensors and microactuators. Metallic thin films can be deposited using a wide range of techniques, including evaporation, sputtering, CVD, and electroplating. Since a complete review of the metals used in MEMS is far beyond the scope of this chapter, the examples presented in this section were selected to represent a broad cross section of where metals have found uses in MEMS.

Aluminum (Al) and gold (Au) are among the most widely employed metals in microfabricated electronic and electromechanical devices, as a result of their use as innerconnect and packaging materials. In addition to these critical electrical functions, Al and Au are also desirable as electromechanical materials. One such example is the use of Au micromechanical switches for RF MEMS. For conventional RF applications, chip level switching is currently performed using FET- and PIN diode-based solid state devices fabricated from gallium arsenide (GaAs) substrates. Unfortunately, these devices suffer from insertion losses and poor electrical isolation. In an effort to develop replacements for GaAs-based solid state switches, *Hyman* et al. [7.34] reported the development of an electrostatically actuated, cantilever-based micromechanical switch fabricated on GaAs substrates. The device consisted of a silicon nitride-encased Au cantilever constructed on a sacrificial silicon dioxide layer. The silicon nitride and silicon dioxide layers were deposited by PECVD, and the Au beam was electroplated from a sodium sulfite solution inside a photoresist mold. A thin multilayer of Ti and Au was sputter deposited in the mold prior to electroplating. The trilayer cantilever structure was chosen to minimize the deleterious effects of thermal and process-related stress gradients in order to produce unbent and thermally stable beams. After deposition and pattering, the cantilevers were released in HF. The processing steps proved to be completely compatible with GaAs substrates. The released cantilevers demonstrated switching speeds better than 50 µs at 25 V with contact lifetimes exceeding 10^9 cycles.

In a second example from RF MEMS, *Chang* et al. [7.35] reported the fabrication of an Al-based micromachined switch as an alternative to GaAs FETs and PIN diodes. In contrast to the work by *Hyman* et al. [7.34], this switch utilizes the differences in the residual stresses in Al and Cr thin films to create bent cantilever switches that capitalize on the stress differences in the materials. Each switch is comprised of a series of linked bimorph cantilevers designed in such a way that the resulting structure bends significantly out of the plane of the wafer due to the stress differences in the bimorph. The switch is drawn closed by electrostatic attraction. The bimorph consists of metals that can easily be processed with GaAs wafers, thus making integration with GaAs devices possible. The released switches were relatively slow, at 10 ms, but an actuation voltage of only 26 V was needed to close the switch.

Thin-film metallic alloys that exhibit the shape-memory effect are of particular interest to the MEMS community for their potential in microactuators. The shape-memory effect relies on the reversible transformation from a ductile martensite phase to a stiff austenite phase in the material with the application of heat. The reversible phase change allows the shape-memory effect to be used as an actuation mechanism, since the material changes shape during the transition. It has been found that high forces and strains can be generated from shape-memory thin films at reasonable power inputs, thus enabling shape-memory actuation to be used in MEMS-based microfluidic devices, such as microvalves and micropumps. Titanium-nickel (TiNi) is among the most popular of the shape-memory alloys, owing to its high actuation work density ($50\,\mathrm{MJ/m^3}$) and large bandwidth (up to 0.1 kHz) [7.36]. TiNi is also attractive because conventional sputtering techniques can be employed to deposit thin films, as detailed in a recent report by *Shih* et al. [7.36]. In this study, TiNi films were deposited by co-sputtering elemental Ti and Ni targets, and a co-sputtering TiNi alloy and elemental Ti targets. It was reported that co-sputtering from TiNi and Ti targets produced better films due to process variations related to the roughening of the Ni target in the case of Ti and Ni co-sputtering. The TiNi/Ti co-sputtering process has been used to produce shape-memory material for a silicon spring-based microvalve [7.37].

Use of thin-film metal alloys in magnetic actuator systems is another example of the versatility of metallic materials in MEMS. Magnetic actuation in microdevices generally requires the magnetic layers to be relatively thick (tens to hundreds of microns) to generate magnetic fields of sufficient strength to generate the desired actuation. To this end, magnetic materials are often deposited by thick film methods, such as electroplating. The thickness of these layers exceeds what can feasibly be patterned by etching, so plating is often performed in microfabricated molds made from materials such as polymethylmethacrylate (PMMA). The PMMA mold thickness can exceed several hundred microns, so X-rays are used as the exposure source during the patterning steps. When necessary, a metallic thin film seed layer is deposited prior to plating. After plating, the mold is dissolved, which frees the metallic component. Known as LIGA (short for Lithography, Galvanoforming and Abformung), this process has been used to produce a wide variety of high-aspect ratio structures from plateable materials, such as nickel-iron (NiFe) magnetic alloys [7.38] and Ni [7.39].

In addition to elemental metals and simple compound alloys, more complex metallic alloys commonly used in commerical macroscopic applications are finding their way into MEMS applications. One such example is an alloy of titanium known as Ti-6Al-4V. Composed of 88% titanium, 6% aluminum and 4% vanadium, this alloy is widely used in commercial aviation due to its weight, strength, and temperature tolerance. *Pornsin-sirirak* et al. [7.40] have explored the use of this alloy in the manufacture of MEMS-based winged structures for micro aerial vehicles. The authors considered this alloy not only because of its weight and strength, but also because of its ductility and its etching rate at room temperature. The designs for the wing prototype were modelled after the wings of bats and various flying insects. For this application, Ti-alloy structures patterned from bulk (250 μm-thick) material by an HF/HNO_3/H_2O etching solution were used, rather than thin films. Parylene-C (detailed in Sect. 7.7.3) was deposited on the patterned alloy to serve as the wing membrane. The miniature micromachined wings were integrated into a test setup, and several prototypes actually demonstrated short duration flight.

7.4 Harsh Environment Semiconductors

Silicon Carbide (SiC) has long been recognized as the leading semiconductor for use in high temperature and high power electronics and is currently receiving attention as a material for harsh environment MEMS.

7.4.1 Silicon Carbide

SiC is a polymorphic material that exists in cubic, hexagonal, and rhombehedral polytypes. The cubic polytype, called 3C-SiC, has an electronic bandgap of 2.3 eV, which is over twice that of Si. Numerous hexagonal and rhombehedral polytypes have been identified, the two most common being 4H-SiC and 6H-SiC. The electronic bandgap of 4H- and 6H-SiC is even higher than 3C-SiC – 2.9 and 3.2 eV, respectively. SiC films can be doped to create n-type and p-type material. The stiffness of SiC is quite large relative to Si, with a Young's modulus ranging from 300 GPa to 450 GPa, depending on the microstructure. SiC is not etched in any wet Si etchants or by XeF_2, a popular dry Si etchant used for releasing device structures [7.41]. SiC is a material that does not melt, but rather sublimes at temperatures in excess of 1,800 °C. Single crystal 4H- and 6H-SiC wafers are commercially available, but smaller in diameter (3 inches) and much more expensive than Si.

SiC thin films can be grown or deposited using a number of different techniques. For high-quality single crystal films, APCVD and LPCVD processes are most commonly employed. Homoepitaxial growth of 4H- and 6H-SiC yields high quality films suitable for microelectronic applications, but only on substrates of the same polytype. These processes usually employ dual precursors, such as SiH_4 and C_3H_8, and are performed at temperatures ranging from 1,500 °C to 1,700 °C. Epitaxial films with p-type or n-type conductivity can be grown using aluminum and boron for p-type films and nitrogen and phosphorus for n-type films. Nitrogen is so effective at modifying the conductivity of SiC that growth of undoped SiC is extremely challenging, because the concentrations of residual nitrogen in typical deposition systems are sufficient for n-type doping.

APCVD and LPCVD can also be used to deposit 3C-SiC on Si substrates. Heteroepitaxy is possible, despite a 20% lattice mismatch, because 3C-SiC and Si have similar lattice structures. The growth process involves two key steps. The first step, called carbonization, converts the near surface region of the Si substrate to 3C-SiC by simply exposing it to a hydrocarbon/hydrogen mixture at high substrate temperatures ($> 1{,}200\,°C$). The carbonized layer forms a crystalline template on which a 3C-SiC film can be grown by adding a silicon-containing gas to the hydrogen/hydrocarbon mix. The lattice mismatch between Si and 3C-SiC results in the formation of crystalline defects in the 3C-SiC film, with the density being highest in the carbonization layer and decreasing with increasing thickness. The crystal quality of 3C-SiC films is nowhere near that of epitaxially grown 4H- and 6H-SiC films; however, the fact that 3C-SiC can be grown on Si substrates enables the use of Si bulk micromachining techniques to fabricate a host of 3C-SiC-based mechanical devices. These include microfabricated pressure sensors [7.42] and nanoelectromechanical resonant structures [7.43].

Polycrystalline SiC (poly-SiC) has proven to be a very versatile material for SiC MEMS. Unlike single crystal versions of SiC, poly-SiC can be deposited on a variety of substrate types, including such common surface micromachining materials as polysilicon, SiO_2, and Si_3N_4, using a much wider range of processes than epitaxial films. Commonly used deposition techniques include LPCVD [7.41, 44, 45] and APCVD [7.46, 47]. The deposition of poly-SiC requires much lower substrate temperatures than epitaxial films, ranging from roughly 700 °C to 1,200 °C. Amorphous SiC can be deposited at even lower temperatures (25 °C to 400 °C) by PECVD [7.48] and sputtering [7.49]. The microstructure of poly-SiC films is temperature, substrate, and process dependent. For amorphous substrates, such as SiO_2 and Si_3N_4, APCVD poly-SiC films deposited from silane and propane are oriented randomly with equiaxed grains [7.47], whereas for oriented substrates, such as polysilicon, the texture of the poly-SiC film matches that of the substrate [7.46]. By comparison, poly-SiC films deposited by LPCVD from dichlorosilane and acetylene are highly textured (111) films with a columnar microstructure [7.44], while films deposited from disilabutane have a distribution of orientations [7.41]. This variation suggests that device performance can be tailored by selecting the proper substrate and deposition conditions.

Direct bulk micromachining of SiC is very difficult due to its chemical inertness. Although conventional wet chemical techniques are not effective, several electrochemical etch processes have been demonstrated and used in the fabrication of 6H-SiC pressure sensors [7.50]. The etching processes are selective to the conductivity of the material, so dimensional control of the etched structures depends on the ability to form doped layers, which can only be formed by in situ or ion implantation processes, since solid source diffusion is not possible at reasonable processing temperatures. This constraint somewhat limits the geometrical complexity of the patterned structures, as compared with conventional plasma-based etching. To fabricate thick (hundreds of microns), 3-D, high-aspect ratio SiC structures, a molding technique has been developed [7.39]. The molds are fabricated from Si substrates using deep reactive ion etching and then filled with SiC using a combination of thin epitaxial and thick polycrystalline film CVD processes. The thin film process is used to protect the mold from pitting during the more aggressive mold filling SiC growth step. The mold filling process coats all surfaces of the mold with a SiC film as thick as the mold is deep. To release the SiC structure, the substrate is first mechanically polished to expose sections of the Si mold, then the substrate is immersed in a Si etchant to completely dissolve the mold. This process has been used to fabricate solid SiC fuel atomizers [7.39], and a variant has been used to fabricate SiC structures for micropower systems [7.51].

In addition to CVD processes, bulk micromachined SiC structures can be fabricated using sintered SiC powders. *Tanaka* et al. [7.52] describe a process in which SiC components, such as micro gas turbine engine rotors, can be fabricated from SiC powders using a micro-reaction-sintering process. The molds are microfabricated from Si using DRIE and filled with SiC and graphite powders mixed with a phenol resin. The molds are then reaction-sintered using a hot isostatic pressing technique. The SiC components are then released from the Si mold by wet chemical etching. The authors reported that the component shrinkage was less than 3%. The bending strength and Vickers hardness of the micro-reaction-sintered material was roughly 70 to 80% of commercially available reaction-sintered SiC, the difference being attributed to the presence of unreacted Si in the micro-scale components.

In a related process, *Liew* et al. [7.54] detail a technique to create silicon carbon nitride (SiCN) MEMS structures by molding injectable polymer precursors. Unlike the aforementioned processes, this technique uses SU-8 photoresists for the molds. SU-8, detailed later in this chapter, is a versatile photo-definable polymer in which thick films (hundreds of microns) can be patterned using conventional UV photolithographic techniques. After patterning, the molds are filled with the SiCN-containing polymer precursor, lightly polished, and then subjected to a multistep heat-treating process. During the thermal processing steps, the SU-8 mold decomposes, and the SiCN structure is released. The resulting SiCN structures retain many of the same properties of stoichiometric SiC.



Fig. 7.4 SEM micrograph of a poly-SiC lateral resonant structure fabricated using a multilayer, micromolding-based micromachining process [7.53]

Although SiC cannot be etched using conventional wet etch techniques, thin SiC films can be patterned using conventional dry etching techniques. RIE processes using fluorinated compounds, such as CHF_3 and SF_6 combined with O_2, an inert gas, or H_2. The high oxygen content in these plasmas generally prohibits the use of photoresist as a masking material, therefore, hard masks made of Al, Ni, and ITO are often used. RIE-based SiC surface micromachining processes with polysilicon and SiO_2 sacrificial layers have been developed for single layer devices [7.55,56]. Multilayered structures are very difficult to fabricate by direct RIE because the etch rates of the sacrificial layers are much higher than the SiC structural layers, making critical dimensional control very difficult and RIE-based SiC multilayer processes impractical.

To address the issues related to RIE of multilayer SiC structures, a micromolding process for patterning SiC films on sacrificial layer substrates has been developed [7.57]. In essence, the micromolding technique is the thin film analog to the molding-based, bulk micromachining technique presented earlier. The micromolding process utilizes polysilicon and SiO_2 films as both molds and sacrificial substrate layers, with SiO_2 molds used with polysilicon sacrificial layers and vica versa. These films are deposited and patterned using conventional methods, thus leveraging the well characterized and highly selective processes developed for polysilicon MEMS. Poly-SiC films are simply deposited into the micromolds, and mechanical polishing is used to remove poly-SiC from the top of the molds. Appropriate etchants are then used to dissolve the molds and sacrificial layers. The micromolding method utilizes the differences in chemical properties of the three materials in this system in a way that bypasses the difficulties associated with chemical etching of SiC. This technique has been extended to multilayer processes that have been used to fabricate SiC micromotors [7.57] and the lateral resonant structure shown in Fig. 7.4 [7.53].

Yang et al. [7.43] have recently shown that the chemical inertness of SiC facilitates the fabrication of NEMS devices. In this work, the authors present a fabrication method to realize SiC mechanical resonators with sub-micron thickness and width dimensions. The resonators were fabricated from ∼ 260 nm-thick 3C-SiC films epitaxially grown on (100) Si wafers. The films were patterned into 150 nm-wide beams ranging in length from 2 to 8 μm. The beams were etched in a $NF_3/O_2/Ar$



Fig. 7.5 SEM micrograph of a 3C-SiC nanomechanical beam resonator fabricated by electron-beam lithography and dry etching processes (courtesy M. Roukes, Caltech)

plasma using an evaporated Cr etch mask. After patterning, the beams were released by etching isotropically the underlying Si using a NF_3/Ar plasma. The inertness of the SiC film to the Si etchant enables the dry release of the nanomechanical beams. An example of a 3C-SiC nanomechanical beam is shown in Fig. 7.5.

7.4.2 Diamond

Diamond is commonly known as nature's hardest material, making it ideal for high wear environments. Diamond has a very large electronic bandgap (5.5 eV), which makes it attractive for high temperature electronics. Undoped diamond is a high quality insulator with a dielectric constant of 5.5; however it can be relatively easily doped with boron to create p-type conductivity. Diamond has a very high Young's modulus (1,035 GPa), making it suitable for high frequency micromachined resonators, and it is among nature's most chemically inert materials, making it well suited for harsh chemical environments.

Unlike SiC, fabrication of diamond MEMS is currently restricted to polycrystalline and amorphous material, since epitaxial-quality single-crystal diamond wafers are not yet commercially available. Polycrystalline diamond films can be deposited on Si and SiO_2 substrates, but the surfaces often must be seeded by diamond powders, or biased with a negative charge to initiate growth. In general, diamond nucleates much more readily on Si surfaces than on SiO_2 surfaces, an effect that has been used to selectively pattern diamond films into micromachined AFM cantilever probes using SiO_2 molding masks [7.58].

Bulk micromachining of diamond is very difficult given its extreme chemical inertness. Diamond structures have nevertheless been fabricated using bulk micromachined Si molds to pattern the structures [7.59]. The Si molds were fabricated using conventional micromachining techniques and filled with polycrystalline diamond deposited by hot filament chemical vapor deposition (HFCVD). The HFCVD process uses hydrogen as a carrier gas and methane as the carbon source. The process was performed at a substrate temperature of 850 °C to 900 °C and a pressure of 50 mtorr. The Si substrate was seeded prior to deposition using a diamond particle/ethanol solution. After deposition, the top surface of the structure was polished using a hot iron plate. After polishing, the Si mold was removed in a Si etchant, leaving behind the micromachined diamond structure. This process was used to produce high-aspect-ratio capillary channels for microfluidic applications [7.60] and components for diffractive optics, laser-to-fiber alignment, and power device cooling structures [7.61].

Due to the nucleation processes associated with diamond film growth, surface micromachining of polycrystalline diamond thin films requires modifications to conventional micromachining to facilitate film growth on sacrificial substrates. Conventional RIE methods are generally ineffective, so initial work focused on developing selective deposition techniques. One early method used selective seeding to form patterned templates for diamond nucleation. The selective seeding process employed the lithographic patterning of photoresist that contained diamond powders [7.62]. The diamond-loaded photoresist was deposited and patterned onto a Cr-coated Si wafer. During the onset of diamond growth, the patterned photoresist rapidly evaporates, leaving behind the diamond seed particles in the desired locations. A patterned diamond film is then selectively grown on these locations.

A second process utilizes selective deposition directly on sacrificial substrate layers. This process combines conventional diamond seeding with photolithographic patterning and etching to fabricate micromachined diamond structures on SiO_2 sacrificial layers [7.63]. The process can be performed in one of two ways. The first approach begins with the seeding of an oxidized Si wafer. The wafer is coated with photoresist and photolithographically patterned. Unmasked regions of the seeded SiO_2 film are then partially etched, forming a surface unfavorable for diamond growth. The photoresist is then removed, and a diamond film is deposited on the seeded regions. The second approach also begins with an oxidized Si wafer. The wafer is coated with photoresist, photolithographically patterned, and then seeded with diamond particles. The photoresist is removed, leaving behind a patterned seed layer suitable for selective growth. These techniques have been successfully used to fabricate cantilever beams and bridge structures.

A third method to surface micromachine polycrystalline diamond films follows the conventional approach of film deposition, dry etching, and release. The chemical inertness of diamond renders most conventional plasma chemistries useless; however, oxygen-based ion beam plasmas can be used to etch diamond thin films [7.64]. A simple surface micromachining process begins with the deposition of a polysilicon sacrificial layer on a Si_3N_4-coated Si wafer. The polysilicon layer is seeded using diamond slurry, and a diamond film is deposited by HFCVD. Since photoresist is not resistant to O_2 plasmas, an Al masking film is deposited and patterned. The diamond films are then etched in the O_2 ion beam plasma, and the structures are released by etching the polysilicon with KOH. This process has been used to create lateral resonant structures, but a significant stress gradient in the films rendered the devices nonoperational.



Fig. 7.6 SEM micrograph of the folded beam truss of a diamond lateral resonator. The diamond film was deposited using a seeding-based hot filament CVD process. The micrograph illustrates the challenges currently facing diamond MEMS, namely, roughened surfaces and residual stress gradients

In general, conventional HFCVD requires that the substrate be pretreated with a seeding layer prior to diamond film growth. However, a method called biased enhanced nucleation (BEN) has been developed that enables the growth of diamond on unseeded Si surfaces. *Wang* et al. [7.65] have shown that if Si substrates are masked with patterned SiO_2 films, selective diamond growth will occur primarily on the exposed Si surfaces, and a slight HF etch is sufficient to remove the adventitious diamond from the SiO_2 mask. This group was able to use this method to fabricate diamond micromotor rotors and stators on Si surfaces.

Diamond is a difficult but not impossible material to etch using RIE techniques. It is well-known that diamond will be etched in oxygen plasmas, but these plasmas are not generally well suited for device fabrication, because the etches tend to be isotropic. A recent development, however, suggests that RIE processes for diamond are close at hand. *Wang* et al. [7.65] describe a process to fabricate a vertically actuated, doubly clamped micromechanical diamond beam resonator using RIE. The process outlined here addresses two key issues related to diamond surface micromachining, namely, residual stress gradients in the diamond films and diamond patterning techniques. A microwave plasma CVD reactor was used to grow the diamond films on sacrificial SiO_2 layers pretreated with a nanocrystalline diamond powder, resulting in a uniform nucleation density at the diamond/SiO_2 interface. The diamond films were etched in a CF_4/O_2 plasma using Al as a hard mask. Reasonably straight sidewalls were created, with roughness attributable to the surface roughness of the faceted diamond film. An Au/Cr drive electrode beneath the sacrificial oxide remained covered throughout the diamond patterning steps and, thus, was undamaged during the diamond etching process.

In conjunction with recent advances in RIE and micromachining techniques, work is being performed to develop diamond deposition processes specifically for MEMS applications. Diamond films grown using conventional techniques, especially processes that require pre-growth seeding, tend to have high residual stress gradients and roughened surface morphologies as a result of the highly faceted, large grain polycrystalline films that are produced by these methods (see Fig. 7.6). The rough surface morphology degrades the patterning process, resulting in roughened sidewalls in etched structures and roughened surfaces of films deposited over these layers. Unlike polysilicon and SiC, a post-deposition polishing process is not technically feasible for diamond due to its extreme hardness. For the fabrication of multilayer diamond devices, methods to reduce the surface roughness of the as-deposited films are highly desirable. Along these lines, *Krauss* et al. [7.66] reported the development of an ultrananocrystalline diamond film that exhibits a much smoother surface morphology than comparable diamond films grown using conventional methods. Unlike conventional CVD diamond films that are grown using a mixture of H_2 and CH_4, the ultrananocrystalline diamond films are grown from mixtures of Ar, H_2, and C_{60} or Ar, H_2, and CH_4. Although the processes are still under development, *Krauss* et al. [7.66] have demonstrated the viability of the ultrananocrystalline diamond films as conformal coatings on Si surfaces, as well as their utility in several micromachining processes.

7.5 GaAs, InP, and Related III-V Materials

Gallium Arsenide (GaAs), Indium Phosphide (InP), and related III-V compounds have favorable piezoelectric and optoelectric properties, high piezoresistive constants, and wide electronic bandgaps relative to Si, making them attractive for various sensor and optoelectronic applications. Like Si, significant research in bulk crystal growth has led to the development of GaAs and InP substrates, which are commercially available as high quality, single crystal wafers. Unlike compound semiconductors, such as SiC, III-V materials can be deposited as ternary and quaternary alloys with lattice constants that closely match the binary compounds from which they are derived (i. e., $Al_xGa_{1-x}As$ and GaAs), thus permitting the fabrication of a wide variety of heterostructures that facilitate device performance.

Crystalline GaAs has a zinc blend crystal structure with an electronic bandgap of 1.4 eV, enabling GaAs electronic devices to function at temperatures as high as 350 °C [7.67]. High quality, single crystal wafers are commercially available, as are well developed metalorganic chemical vapor deposition (MOCVD) and molecular beam epitaxy (MBE) growth processes for epitaxial layers of GaAs and its alloys. GaAs does not outperform Si in terms of mechanical properties, however, its stiffness and fracture toughness are still suitable for micromechanical devices.

Micromachining of GaAs is relatively straightforward, since many of its lattice-matched ternary and quaternary alloys have sufficiently different chemical properties to allow their use as sacrificial layers [7.68]. For example, the most common ternary alloy for GaAs is $Al_xGa_{1-x}As$. For values of x less than or equal to 0.5, etchants containing mixtures of HF and H_2O will etch $Al_xGa_{1-x}As$ without attacking GaAs, while etchants containing NH_4OH and H_2O_2 attack GaAs isotropically, but do not etch $Al_xGa_{1-x}As$. Such selectivity enables the micromachining of GaAs wafers using lattice-matched etch stops and sacrificial layers. Devices fabricated using these methods include comb drive lateral resonant structures [7.68], pressure sensors [7.69, 70], thermopile sensors [7.71], Fabry–Perot detectors [7.72], and cantilever-based sensors and actuators [7.73, 74]. In addition, nanoelectromechanical devices, such as suspended micromechanical resonators [7.75] and tethered membranes [7.76], have been fabricated using these techniques. An example of a nanoelectromechanical beam structure fabricated from GaAs is shown in Fig. 7.7.

In addition to using epitaxial layers as etch stops, ion implantation methods can also be used to produce etch stops in GaAs layers. *Miao* et al. [7.77] describe a process that uses electrochemical etching to selectively remove n-type GaAs layers. The process relies on the creation of a highly resistive near surface GaAs layer on an n-type GaAs substrate by low dose nitrogen implantation in the MeV energy range. A pulsed electrochemical etch method using a H_2PtCl_6, H_3PO_4, H_2SO_4 platinum electrolytic solution at 40 °C with 17 V, 100 ms pulses is sufficient to selectively remove n-type GaAs at about 3 μm/min. Using this method, stress-free, tethered membranes could readily be fabricated from the high resistive GaAs layer. The high implant energies enable the fabrication of membranes several microns in thickness. Moreover, the authors demonstrated that if the GaAs wafer were etched in such a way as to create an undulating surface prior to ion implantation, corrugated membranes could be fabricated. These structures can sustain much higher deflection amplitudes than flat structures.

Micromachining of InP closely resembles the techniques used for GaAs. Many of the properties of InP are similar to GaAs in terms of crystal structure, mechanical stiffness, and hardness. However, the optical properties of InP make it particularly attractive for micro-optomechanical devices to be used in the 1.3 to 1.55 μm wavelength range [7.78]. Like GaAs, single crystal wafers of InP are readily available, and



Fig. 7.7 SEM micrograph of a GaAs nanomechanical beam resonator fabricated by epitaxial growth, electron-beam lithography, and selective etching (courtesy of M. Roukes, Caltech)

ternary and quaternary lattice-matched alloys, such as InGaAs, InAlAs, InGaAsP, and InGaAlAs, can be used as either etch stop and/or sacrificial layers, depending on the etch chemistry [7.68]. For instance, InP structural layers deposited on $\text{In}_{0.53}\text{Al}_{0.47}\text{As}$ sacrificial layers can be released using etchants containing $C_6H_8O_7$, H_2O_2, and H_2O. In addition, InP films and substrates can be etched in solutions containing HCl and H_2O using $\text{In}_{0.53}\text{Ga}_{0.47}\text{As}$ films as etch stops. Using InP-based micromachining techniques, multi-air gap filters [7.79], bridge structures [7.78], and torsional membranes [7.72] have been fabricated from InP and its related alloys.

In addition to GaAs and InP, materials such as indium arsenide (InAs) can be micromachined into device structures. Despite a 7% lattice mismatch between InAs and (111) GaAs, high quality epitaxial layers can be grown on GaAs substrates. As described by *Yamaguchi* et al. [7.80], the surface Fermi level of InAs/GaAs structures is pinned in the conduction band, enabling the fabrication of very thin conductive membranes. In fact, the authors have successfully fabricated freestanding InAs structures that range in thickness from 30 to 300 nm. The thin InAs films were grown directly on GaAs substrates by MBE and etched using a solution containing H_2O, H_2O_2, and H_2SO_4. The structures, mainly doubly clamped cantilevers, were released by etching the GaAs substrate using a $H_2O/H_2O_2/NH_4OH$ solution.

7.6 Ferroelectric Materials

Piezoelectric materials play an important role in MEMS technology for sensing and mechanical actuation applications. In a piezoelectric material, mechanical stress produces a polarization, and, conversely, a voltage-induced polarization produces a mechanical stress. Many asymmetric materials, such as quartz, GaAs, and zinc oxide (ZnO), exhibit some piezoelectric behavior. Recent work in MEMS has focussed on the development of ferroelectric compounds, such as lead zirconate titanate, $\text{Pb}(\text{Zr}_x\text{Ti}_{1-x})\text{O}_3$, or PZT for short, because such compounds have high piezoelectric constants that result in high mechanical transduction. It is relatively straightforward to fabricate a PZT structure on top of a thin freestanding structural layer (i. e., cantilever, diaphragm). Such a capability enables the piezoelectric material to be used in sensor applications or actuator applications for which piezoelectric materials are particularly well suited. Like Si, PZT films can be patterned using dry etch techniques based on chlorine chemistries, such as Cl_2/CCl_4, as well as ion beam milling using inert gases like Ar.

PZT has been successfully deposited in thin film form using co-sputtering, CVD, and sol-gel processing. Sol-gel processing is particularly attractive because the composition and homogeneity of the deposited material over large surface areas can be readily controlled. The sol-gel process outlined by *Lee* et al. [7.81] uses PZT solutions made from liquid precursors containing Pb, Ti, Zr, and O. The solution is deposited by spin coating on a Si wafer that has been coated with a $Pt/Ti/SiO_2$ thin film multilayer. The process is executed to produce a PZT film in layers, with each layer consisting of a spin-coated layer that is dried at 110 °C for 5 min and then heat treated at 600 °C for 20 min. After building up the PZT layer to the desired thickness, the multilayer was heated at 600 °C for up to 6 hrs. Prior to this anneal, a PbO top layer was deposited on the PZT surface. An Au/Cr electrode was then sputter-deposited on the surface of the piezoelectric stack. This process was used to fabricate a PZT-based force sensor. *Xu* et al. [7.82] describe a similar sol-gel process to produce 12 μm-thick, crack-free PZT films on Pt-coated Si wafers and 5 μm-thick films on insulating ZrO_2 layers to produce micromachined MHz-range, two-dimensional transducer arrays for acoustic imaging.

Thick film printing techniques for PZT have been developed to produce thick films in excess of 100 μm. Such thicknesses are desired for applications that require actuation forces that cannot be achieved with the much thinner sol-gel films. *Beeby* et al. [7.83] describe a thick film printing process whereby a PZT paste is made from a mixture of 95% PZT powder, 5% lead borosilicate powder, and an organic carrier. The paste was then printed through a stainless steel screen using a thick film printer. Printing was performed on an oxidized Si substrate that is capped with a Pt electrode. After printing, the paste was dried and then fired at 850 °C to 950 °C. Printing could be repeated to achieve the desired thickness. The top electrode consisted of an evaporated Al film. The authors found that it was possible to perform plasma-based processing on the printed substrates, but that the porous nature of the printed PZT films made them unsuitable for wet chemical processing.

7.7 Polymer Materials

Polyimides comprise an important class of durable polymers that are well suited for many of the techniques used in conventional MEMS processing. In general, polyimides can be acquired in bulk, or deposited as thin films by spin coating. Polyimides can be patterned using conventional dry etching techniques and processed at relatively high temperatures. These attributes make polyimides an attractive group of polymers for MEMS that require polymer structural and/or substrate layers, such as microfabricated biomedical devices, for which inertness and flexibility are important parameters.

7.7.1 Polyimide

Shearwood et al. [7.84] explored the use of polyimide as a robust mechanical material for microfabricated audio membranes. The authors fabricated 7 μm-thick, 8 mm-diameter membranes on GaAs substrates by bulk micromachining the GaAs substrate using a NH_3/H_2O_2 solution. They realized 100% yield and, despite a low Young's modulus (~ 3 GPa), observed flat membranes to within 1 nm after fabrication.

Jiang et al. [7.85] capitalized on the strength and flexibility of polyimide to fabricate a flexible sheer-stress sensor array based on Si sensors. The sensor array consisted of a collection of Si islands linked by two polyimide layers. Each Si sensor island was $250 \times 250\ \mu m^2$ in area and 80 μm in thickness. Al was used as an electrical innerconnect layer. The two polyimide layers served as highly flexible hinges, giving the sensor array the ability to be mounted on curved surfaces. The sensor array was successful in profiling the shear-stress distribution along the leading edge of a rounded delta wing.

The chemical and temperature durability of polyimides enables their use as a sacrificial layer for a number of commonly used materials, such as evaporated or sputter-deposited metals. *Memmi* et al. [7.86] developed a fabrication process for capacitive micromechanical ultransonic transducers using polyimide as a sacrificial layer. The authors showed that the polyimide could withstand the conditions used to deposit silicon monoxide by evaporation and silicon nitride by PECVD at 400 °C. Recent work by *Bagolini* et al. [7.87] has shown that polyimides can even be used as sacrificial layers for PECVD SiC.

In the area of microfabricated biomedical devices, polyimide is receiving attention as a substrate material for implantable devices, owing to its potential biocompatiblity and mechanical flexibility. *Stieglitz* [7.88] reported on the fabrication of multichannel microelectrodes on polyimide substrates. Instead of using polyimide sheets as starting substrates, Si carrier wafers coated with a 5 μm-thick polyimide film were used. Pt microelectrodes were then fabricated on these substrates using conventional techniques. Thin polyimide layers were deposited between various metal layers to serve as insulating layers. A capping polyimide layer was then deposited on the top of the substrates, and the entire polyimide/metal structure was peeled off the Si carrier wafers. Backside processing was then performed on the freestanding polyimide structures to create devices that have exposed electrodes on both surfaces. In a later paper, *Stieglitz* et al. [7.89] describe a variation of this process for neural prostheses.

7.7.2 SU-8

SU-8 is a negative-tone, epoxy-like photoresist that is receiving much attention for its versatility in MEMS processing. It is a high-aspect-ratio, UV-sensitive resist designed for applications requiring single-coat resists with thicknesses on the order of 500 microns [7.90]. SU-8 has favorable chemical properties that enable it to be used as a molding material for high-aspect-ratio electroplated structures (as an alternative to LIGA), and as a structural material for microfluidics [7.90]. In terms of mechanical properties, *Lorenz* et al. [7.91] reported that SU-8 has a modulus of elasticity of 4.02 GPa, which compares favorably with a commonly used polyamid (3.4 GPa).

In addition to the aforementioned conventional uses for SU-8, several interesting alternative uses are beginning to appear in the literature. *Conradie* et al. [7.92] have used SU-8 to trim the mass of silicon paddle oscillators as a means to adjust the resonant frequency of the beams. The trimming process involves the patterning of SU-8 posts on Si paddles. The process capitalizes on the relative chemical stability of the SU-8 resin, in conjunction with the relatively large masses that can be patterned using standard UV exposure processes.

SU-8 is also of interest as a bonding layer material for wafer bonding processes using patterned bonding layers. *Pan* et al. [7.93] compared several UV photo-definable polymeric materials and found that SU-8 exhibited the highest bonding strength (20.6 MPa) for layer thicknesses up to 100 μm.

7.7.3 Parylene

Parylene (poly-paraxylylene) is another emerging polymeric MEMS material due in large part to its biocompatibility. It is particularly attractive from the fabrication perspective, because it can be deposited by CVD at room temperature. Moreover, the deposition process is conformal, which enables parylene coatings to be applied to prefabricated structures, such as Si microneedles [7.94], low stress silicon nitride membrane particle filters [7.95], and micromachined polyimide/Au optical scanners [7.96]. In the first two cases, the parylene coating served to strengthen the microfabricated structures, while in the last case, it served to protect the structure from condensing water vapor.

In addition to its function as a protective coating, parylene can actually be micromachined into freestanding components. *Noh* et al. [7.97] demonstrated a method to create bulk micromachined parylene microcolumns for miniature gas chromatographs. The structure is fabricated using a micromolding technique by which Si molds are fabricated by DRIE and coated with parylene to form three sides of the microcolumn. A second wafer is coated with parylene, and the two are bonded together via a fusion bonding process. After bonding, the structure is released from the Si mold by KOH etching. In a second example, *Yao* et al. [7.98] describe a dry release process for parylene surface micromachining. In this process, sputtered Si is used as a sacrificial layer onto which a thick sacrificial photoresist is deposited. Parylene is then deposited on the photoresist and patterned into the desired structural shape. The release procedure is a two step process. First, the photoresist is dissolved in acetone. This results in the parylene structure sticking to the sputtered Si. Next, a dry BrF_3 etch is performed, which dissolves the Si and releases the parylene structures. Parylene beams that were 1 mm long and 4.5 μm thick were successfully fabricated using this technique.

7.8 Future Trends

The rapid expansion of MEMS in recent years is due in large part to the inclusion of new materials that have expanded the functionality of microfabricated devices beyond what is achievable in silicon. This trend will certainly continue as new application areas for micro- and nanofabricated devices are identified. Many of these applications will likely require both new materials and new processes to fabricate the micro- and nanomachined devices for these yet to be identified applications. Currently, conventional micromachining techniques employ a top-down approach that begins with either bulk substrates or thin films. Future MEMS and NEMS will likely incorporate materials that are created using a bottom-up approach. A significant challenge facing device design and fabrication engineers alike will be how to marry top-down and bottom-up approaches to create devices and systems that cannot be made using either process alone.

References

7.1 C. S. Smith: Piezoresistive effect in germanium and silicon, Phys. Rev. **94** (1954) 1–10

7.2 A. N. Cleland, M. L. Roukes: Fabrication of high frequency nanometer scale mechanical resonators from bulk Si crystals, Appl. Phys. Lett. **69** (1996) 2653–2655

7.3 D. W. Carr, H. G. Craighead: Fabrication of nanoelectromechanical systems in single crystal silicon using silicon on insulator substrates and electron beam lithography, J. Vac. Sci. Technol. B **15** (1997) 2760–2763

7.4 J. J. McMahon, J. M. Melzak, C. A. Zorman, J. Chung, M. Mehregany: Deposition and characterization of in situ boron doped polycristalline silicon films for microelectromechanical systems applications, Mater. Res. Soc. Proc. **605** (2000) 31–36

7.5 T. Kamins: *Polycrystalline Silicon for Integrated Circuits and Displays*, 2nd edn. (Kluwer, Boston 1998)

7.6 L. Cao, T. S. Kin, S. C. Mantell, D. Polla: Simulation and fabrication of piezoresistive membrane type MEMS strain sensors, Sens. Actuators **80** (2000) 273–279

7.7 H. Guckel, T. Randazzo, D. W. Burns: A simple technique for the determination of mechanical strain in thin films with application to polysilicon, J. Appl. Phys. **57** (1985) 1671–1675

7.8 R. T. Howe, R. S. Muller: Stress in polysilicon and amorphous silicon thin films, J. Appl. Phys. **54** (1983) 4674–4675

7.9 X. Zhang, T. Y. Zhang, M. Wong, Y. Zohar: Rapid thermal annealing of polysilicon thin films, J. Microelectromech. Syst. **7** (1998) 356–364

7.10 J. Yang, H. Kahn, A.-Q. He, S. M. Phillips, A. H. Heuer: A new technique for producing large-area as-deposited zero-stress LPCVD polysilicon films: The multipoly process, J. Microelectromech. Syst. **9** (2000) 485–494

7.11 P. Gennissen, M. Bartek, P. J. French, P. M. Sarro: Bipolar-compatible epitaxial poly for smart sensors: Stress minimization and applications, Sens. Actuators A **62** (1997) 636–645

7.12 P. Lange, M. Kirsten, W. Riethmuller, B. Wenk, G. Zwicker, J. R. Morante, F. Ericson, J. A. Schweitz: Thick polycrystalline silicon for surface-micromechanical applications: Deposition, structuring, and mechanical characterization, Sens. Actuators A **54** (1996) 674–678

7.13 S. Greek, F. Ericson, S. Johansson, M. Furtsch, A. Rump: Mechanical characterization of thick polysilicon films: Young's modulus and fracture strength evaluated with microstructures, **9** (1999) 245–251

7.14 K. Funk, H. Emmerich, A. Schilp, M. Offenberg, R. Neul, F. Larmer: A surface micromachined silicon gyroscope using a thick polysilicon layer, Proc. of the 12th Int. Conf. Microelectromech. Systems, Orlando 1999, ed. by K. J. Gabriel, K. Najafi (IEEE, Piscataway 1999) 57–60

7.15 T. Abe, M. L. Reed: Low strain sputtered polysilicon for micromechanical structures, Proc. 9th Int. Workshop Microelectromech. Systems, San Diego 1996, ed. by M. G. Allen, M. L. Reed (IEEE, Piscataway 1996) 258–262

7.16 K. Honer, G. T. A. Kovacs: Integration of sputtered silicon microstructures with pre-fabricated CMOS circuitry, Sens. Actuators A **91** (2001) 392–403

7.17 R. Anderson, R. S. Muller, C. W. Tobias: Porous polycrystalline silicon: A new material for MEMS, J. Microelectromech. Syst. **3** (1994) 10–18

7.18 W. Lang, P. Steiner, H. Sandmaier: Porous silicon: A novel material for microsystems, Sens. Actuators A **51** (1995) 31–36

7.19 S. K. Ghandhi: *VLSI Fabrication Principles – Silicon and Gallium Arsenide* (Wiley, New York 1983)

7.20 W. A. Pilskin: Comparison of properties of dielectric films deposited by various methods, J. Vac. Sci. Technol. **21** (1977) 1064–1081

7.21 J. S. Danel, F. Michel, G. Delapierre: Micromachining of quartz and its application to an acceleration sensor, Sens. Actuators A **21–23** (1990) 971–977

7.22 A. Yasseen, J. D. Cawley, M. Mehregany: Thick glass film technology for polysilicon surface micromachining, J. Microelectromech. Syst. **8** (1999) 172–179

7.23 R. Liu, M. J. Vasile, D. J. Beebe: The fabrication of nonplanar spin-on glass microstructures, J. Microelectromech. Syst. **8** (1999) 146–151

7.24 B. Folkmer, P. Steiner, W. Lang: Silicon nitride membrane sensors with monocrystalline transducers, Sens. Actuators A **51** (1995) 71–75

7.25 M. Sekimoto, H. Yoshihara, T. Ohkubo: Silicon nitride single-layer X-ray mask, J. Vac. Sci. Technol. **21** (1982) 1017–1021

7.26 P. J. French, P. M. Sarro, R. Mallee, E. J. M. Fakkeldij, R. F. Wolffenbuttel: Optimization of a low-stress silicon nitride process for surface micromachining applications, Sens. Actuators A **58** (1997) 149–157

7.27 B. Li, B. Xiong, L. Jiang, Y. Zohar, M. Wong: Germanium as a versatile material for low-temperature micromachining, J. Microelectromech. Syst. **8** (1999) 366–372

7.28 A. Franke, D. Bilic, D. T. Chang, P. T. Jones, T. J. King, R. T. Howe, C. G. Johnson: Post-CMOS integration of germanium microstructures, Proc. 12th Int. Conf. Microelectromech. Syst., Orlando 1999, ed. by K. J. Gabriel, K. Najafi (IEEE, Piscataway 1999) 630–637

7.29 A. E. Franke, Y. Jiao, M. T. Wu, T. J. King, R. T. Howe: Post-CMOS modular integration of poly-SiGe microstructures using poly-Ge sacrificial layers, Technical Digest – Solid State Sens. Actuator Workshop,

Hilton Head 2000, ed. by L. Bousse (Transducers Research Foundation, Cleveland Heights Ohio 2000) 18–21
7.30 S. Sedky, P. Fiorini, M. Caymax, S. Loreti, K. Baert, L. Hermans, R. Mertens: Structural and mechanical properties of polycrystalline silicon germanium for micromachining applications, J. Microelectromech. Syst. **7** (1998) 365–372
7.31 S. Sedky, A. Witvrouw, K. Baert: Poly SiGe, a promising material for MEMS monolithic integration with the driving electronics, Sens. Actuators A **97–98** (2002) 503–511
7.32 J. M. Heck, C. G. Keller, A. E. Franke, L. Muller, T.-J. King, R. T. Howe: High aspect ratio polysilicon-germanium microstructures, Proc. 10th Int. Conf. Solid State Sens. Actuators, Sendai 1999, ed. by M. Esashi, T. Morizumi (IEE of Japan, Tokyo 1999) 328–334
7.33 P. Van Gerwen, T. Slater, J. B. Chevrier, K. Baert, R. Mertens: Thin-film boron-doped polycrystalline silicon$_{70\%}$-germanium$_{30\%}$ for thermopiles, Sens. Actuators A **53** (1996) 325–329
7.34 D. Hyman, J. Lam, B. Warneke, A. Schmitz, T. Y. Hsu, J. Brown, J. Schaffner, A. Walson, R. Y. Loo, M. Mehregany, J. Lee: Surface micromachined RF MEMS switches on GaAs substrates, Int. J. Radio Frequency Microwave Commun. Eng. **9** (1999) 348–361
7.35 C. Chang, P. Chang: Innovative micromachined microwave switch with very low insertion loss, Sens. Actuators **79** (2000) 71–75
7.36 C. L. Shih, B. K. Lai, H. Kahn, S. M. Phillips, A. H. Heuer: A robust co-sputtering fabrication procedure for TiNi shape memory alloys for MEMS, J. Microelectromech. Syst. **10** (2001) 69–79
7.37 G. Hahm, H. Kahn, S. M. Phillips, A. H. Heuer: Fully microfabricated silicon spring biased shape memory actuated microvalve, Technical Digest – Solid State Sens. Actuator Workshop, Hilton Head Island 2000, ed. by L. Bousse (Transducers Research Foundation, Cleveland Heights Ohio 2000) 230–233
7.38 S. D. Leith, D. T. Schwartz: High-rate through-mold electrodeposition of thick (>200 micron) NiFe MEMS components with uniform composition, J. Microelectromech. Syst. **8** (1999) 384–392
7.39 N. Rajan, M. Mehregany, C. A. Zorman, S. Stefanescu, T. Kicher: Fabrication and testing of micromachined silicon carbide and nickel fuel atomizers for gas turbine engines, J. Microelectromech. Syst. **8** (1999) 251–257
7.40 T. Pornsin-sirirak, Y. C. Tai, H. Nassef, C. M. Ho: Titanium-alloy MEMS wing technology for a microaerial vehicle application, Sens. Actuators A **89** (2001) 95–103
7.41 C. R. Stoldt, C. Carraro, W. R. Ashurst, D. Gao, R. T. Howe, R. Maboudian: A low temperature CVD process for silicon carbide MEMS, Sens. Actuators A **97–98** (2002) 410–415
7.42 M. Eickhoff, H. Moller, G. Kroetz, J. von Berg, R. Ziermann: A high temperature pressure sensor prepared by selective deposition of cubic silicon carbide on SOI substrates, Sens. Actuators **74** (1999) 56–59
7.43 Y. T. Yang, K. L. Ekinci, X. M. H. Huang, L. M. Schiavone, M. L. Roukes, C. A. Zorman, M. Mehregany: Monocrystalline silicon carbide nanoelectromechanical systems, Appl. Phys. Lett. **78** (2001) 162–164
7.44 C. A. Zorman, S. Rajgolpal, X. A. Fu, R. Jezeski, J. Melzak, M. Mehregany: Deposition of polycrystalline 3C-SiC films on 100 mm-diameter (100) Si wafers in a large-volume LPCVD furnace, Electrochem. Solid State Lett. **5** (2002) G99–G101
7.45 I. Behrens, E. Peiner, A. S. Bakin, A. Schlachetzski: Micromachining of silicon carbide on silicon fabricated by low-pressure chemical vapor deposition, J. Micromech. Microeng. **12** (2002) 380–384
7.46 C. A. Zorman, S. Roy, C. H. Wu, A. J. Fleischman, M. Mehregany: Characterization of polycrystalline silicon carbide films grown by atmospheric pressure chemical vapor deposition on polycrystalline silicon, J. Mater. Res. **13** (1996) 406–412
7.47 C. H. Wu, C. H. Zorman, M. Mehregany: Growth of polycrystalline SiC films on SiO_2 and Si_3N_4 by APCVD, Thin Solid Films **355–356** (1999) 179–183
7.48 P. Sarro: Silicon carbide as a new MEMS technology, Sens. Actuators **82** (2000) 210–218
7.49 N. Ledermann, J. Baborowski, P. Muralt, N. Xantopoulos, J. M. Tellenbach: Sputtered silicon carbide thin films as protective coatings for MEMS applications, Surf. Coat. Technol. **125** (2000) 246–250
7.50 R. S. Okojie, A. A. Ned, A. D. Kurtz: Operation of a 6H-SiC pressure sensor at 500 °C, Sens. Actuators A **66** (1998) 200–204
7.51 K. Lohner, K. S. Chen, A. A. Ayon, M. S. Spearing: Microfabricated silicon carbide microengine structures, Mater. Res. Soc. Symp. Proc. **546** (1999) 85–90
7.52 S. Tanaka, S. Sugimoto, J.-F. Li, R. Watanabe, M. Esashi: Silicon carbide micro-reaction-sintering using micromachined silicon molds, J. Microelectromech. Syst. **10** (2001) 55–61
7.53 X. Song, S. Rajgolpal, J. M. Melzak, C. A. Zorman, M. Mehregany: Development of a multilayer SiC surface micromachining process with capabilities and design rules comparable with conventional polysilicon surface micromachining, Mater. Sci. Forum **389–393** (2001) 755–758
7.54 L. A. Liew, W. Zhang, V. M. Bright, A. Linan, M. L. Dunn, R. Raj: Fabrication of SiCN ceramic MEMS using injectable polymer-precursor technique, Sens. Actuators A **89** (2001) 64–70
7.55 A. J. Fleischman, S. Roy, C. A. Zorman, M. Mehregany: Polycrystalline silicon carbide for surface micromachining, Proc.9th Int. Workshop Microelectromech. Systems, San Diego 1996, ed. by M. G. Allen, M. L. Reid (IEEE, Piscataway 1996) 234–238

7.56 A. J. Fleischman, X. Wei, C. A. Zorman, M. Mehregany: Surface micromachining of polycrystalline SiC deposited on SiO_2 by APCVD, Mater. Sci. Forum **264-268** (1998) 885–888

7.57 A. Yasseen, C. H. Wu, C. A. Zorman, M. Mehregany: Fabrication and testing of surface micromachined polycrystalline SiC micromotors, Electron Device Lett. **21** (2000) 164–166

7.58 T. Shibata, Y. Kitamoto, K. Unno, E. Makino: Micromachining of diamond film for MEMS applications, J. Microelectromech. Syst. **9** (2000) 47–51

7.59 H. Bjorkman, P. Rangsten, P. Hollman, K. Hjort: Diamond replicas from microstructured silicon masters, Sens. Actuators **73** (1999) 24–29

7.60 P. Rangsten, H. Bjorkman, K. Hjort: Microfluidic components in diamond, Proc. 10th Int. Conf. Solid State Sens. Actuators, Sendai 1999, ed. by M. Esashi, T. Morizumi (IEE of Japan, Tokyo 1999) 190–193

7.61 H. Bjorkman, P. Rangsten, K. Hjort: Diamond microstructures for optical microelectromechanical systems, Sens. Actuators **78** (1999) 41–47

7.62 M. Aslam, D. Schulz: Technology of diamond microelectromechanical systems, Proc. 8th Int. Conf. Solid State Sens. Actuators, Stockholm 1995, ed. by I. Lundstrum (Foundation for Sensor and Actuator Technology, Stockholm 1995) 222–224

7.63 R. Ramesham: Fabrication of diamond microstructures for microelectromechanical systems (MEMS) by a surface micromachining process, Thin Solid Films **340** (1999) 1–6

7.64 Y. Yang, X. Wang, C. Ren, J. Xie, P. Lu, W. Wang: Diamond surface micromachining technology, Diamond Rel. Mater. **8** (1999) 1834–1837

7.65 X. D. Wang, G. D. Hong, J. Zhang, B. L. Lin, H. Q. Gong, W. Y. Wang: Precise patterning of diamond films for MEMS application, J. Mater. Processing Technol. **127** (2002) 230–233

7.66 A. R. Krauss, O. Auciello, D. M. Gruen, A. Jayatissa, A. Sumant, J. Tucek, D. C. Mancini, N. Moldovan, A. Erdemire, D. Ersoy, M. N. Gardos, H. G. Busmann, E. M. Meyer, M. Q. Ding: Ultrananocrystalline diamond thin films for MEMS and moving mechanical assembly devices, Diamond Rel. Mater. **10** (2001) 1952–1961

7.67 K. Hjort, J. Soderkvist, J.-A. Schweitz: Galium arsenide as a mechanical material, J. Micromech. Microeng. **4** (1994) 1–13

7.68 K. Hjort: Sacrificial etching of III-V compounds for micromechanical devices, J. Micromech. Microeng. **6** (1996) 370–365

7.69 K. Fobelets, R. Vounckx, G. Borghs: A GaAs pressure sensor based on resonant tunnelling diodes, J. Micromech. Microeng. **4** (1994) 123–128

7.70 A. Dehe, K. Fricke, H. L. Hartnagel: Infrared thermopile sensor based on AlGaAs-GaAs micromachining, Sens. Actuators A **46-47** (1995) 432–436

7.71 A. Dehe, K. Fricke, K. Mutamba, H. L. Hartnagel: A piezoresistive GaAs pressure sensor with GaAs/AlGaAs membrane technology, J. Micromech. Microeng. **5** (1995) 139–142

7.72 A. Dehe, J. Peerlings, J. Pfeiffer, R. Riemenschneider, A. Vogt, K. Streubel, H. Kunzel P. Meissner, H. L. Hartnagel: III-V compound semiconductor micromachined actuators for long resonator tunable Fabry–Perot detectors, Sens. Actuators A **68** (1998) 365–371

7.73 T. Lalinsky, S. Hascik, Z. Mozolova, E. Burian, M. Drzik: The improved performance of GaAs micromachined power sensor microsystem, Sens. Actuators **76** (1999) 241–246

7.74 T. Lalinsky, E. Burian, M. Drzik, S. Hascik, Z. Mozolova, J. Kuzmik, Z. Hatzopoulos: Performance of GaAs micromachined microactuator, Sens. Actuators **85** (2000) 365–370

7.75 H. X. Tang, X. M. H. Huang, M. L. Roukes, M. Bichler, W. Wegscheider: Two-dimensional electron-gas actuation and transduction for GaAs nanoelectromechanical systems, Appl. Phys. Lett. **81** (2002) 3879–3881

7.76 T. S. Tighe, J. M. Worlock, M. L. Roukes: Direct thermal conductance measurements on suspended monocrystalline nanostructures, Appl. Phys. Lett. **70** (1997) 2687–2689

7.77 J. Miao, B. L. Weiss, H. L. Hartnagel: Micromachining of three-dimensional GaAs membrane structures using high-energy nitrogen implantation, J. Micromech. Microeng. **13** (2003) 35–39

7.78 C. Seassal, J. L. Leclercq, P. Viktorovitch: Fabrication of InP-based freestanding microstructures by selective surface micromachining, J. Micromech. Microeng. **6** (1996) 261–265

7.79 J. Leclerq, R. P. Ribas, J. M. Karam, P. Viktorovitch: III-V micromachined devices for microsystems, Microelectron. J. **29** (1998) 613–619

7.80 H. Yamaguchi, R. Dreyfus, S. Miyashita, Y. Hirayama: Fabrication and elastic properties of InAs freestanding structures based on InAs/GaAs(111) A heteroepitaxial systems, Physica E **13** (2002) 1163–1167

7.81 J. B. Lee, J. English, C. H. Ahn, M. G. Allen: Planarization techniques for vertically integrated metallic MEMS on silicon foundry circuits, J. Micromech. Microeng. **7** (1997) 44–54

7.82 B. Xu, L. E. Cross, J. J. Bernstein: Ferroelectric and antiferroelectric films for microelectromechanical systems applications, Thin Solid Films **377-378** (2000) 712–718

7.83 S. P. Beeby, A. Blackburn, N. M. White: Processing of PZT piezoelectric thick films on silicon for microelectromechanical systems, J. Micromech. Microeng. **9** (1999) 218–229

7.84 C. Shearwood, M. A. Harradine, T. S. Birch, J. C. Stevens: Applications of polyimide membranes to MEMS technology, Microelectron. Eng. **30** (1996) 547–550

7.85 F. Jiang, G. B. Lee, Y. C. Tai, C. M. Ho: A flexible micromachine-based shear-stress sensor array and its application to separation-point detection, Sens. Actuators **79** (2000) 194–203

7.86 D. Memmi, V. Foglietti, E. Cianci, G. Caliano, M. Pappalardo: Fabrication of capacitive micromechanical ultrasonic transducers by low-temperature process, Sens. Actuators A **99** (2002) 85–91

7.87 A. Bagolini, L. Pakula, T. L. M. Scholtes, H. T. M. Pham, P. J. French, P. M. Sarro: Polyimide sacrificial layer and novel materials for post-processing surface micromachining, J. Micromech. Microeng. **12** (2002) 385–389

7.88 T. Stieglitz: Flexible biomedical microdevices with double-sided electrode arrangements for neural applications, Sens. Actuators A **90** (2001) 203–211

7.89 T. Stieglitz, G. Matthias: Flexible BioMEMS with electrode arrangements on front and back side as key component in neural prostheses and biohybrid systems, Sens. Actuators B **83** (2002) 8–14

7.90 H. Lorenz, M. Despont, N. Fahrni, J. Brugger, P. Vettiger, P. Renaud: High-aspect-ratio, ultrathick, negative-tone-near-UV photoresist and its applications in MEMS, Sens. Actuators A **64** (1998) 33–39

7.91 H. Lorenz, M. Despont, N. Fahrni, N. LaBianca, P. Renaud, P. Vettiger: SU-8: A low-cost negative resist for MEMS, J. Micromech. Microeng. **7** (1997) 121–124

7.92 E. H. Conradie, D. F. Moore: SU-8 thick photoresist processing as a functional material for MEMS applications, J. Micromech. Microeng. **12** (2002) 368–374

7.93 C. T. Pan, H. Yang, S. C. Shen, M. C. Chou, H. P. Chou: A low-temperature wafer bonding technique using patternable materials, J. Micromech. Microeng. **12** (2002) 611–615

7.94 P. A. Stupar, A. P. Pisano: Silicon parylene, and silicon/parylene micro-needles for strength and toughness, Technical Digest 11th Int. Conf. Solid State Sens. Actuators, Munich 2001, ed. by E. Obermeier (Springer, Berlin, Heidelberg 2001) 1368–1389

7.95 X. Yang, J. M. Yang, Y. C. Tai, C. M. Ho: Micromachined membrane particle filters, Sens. Actuators **73** (1999) 184–191

7.96 J. M. Zara, S. W. Smith: Optical scanner using a MEMS actuator, Sens. Actuators A **102** (2002) 176–184

7.97 H. S. Noh, P. J. Hesketh, G. C. Frye-Mason: Parylene gas chromatographic column for rapid thermal cycling, J. Microelectromech. Syst. **11** (2002) 718–725

7.98 T. J. Yao, X. Yang, Y. C. Tai: BrF_3 dry release technology for large freestanding parylene microstructures and electrostatic actuators, Sens. Actuators A **97–98** (2002) 771–775

8. MEMS/NEMS Devices and Applications

Microelectromechanical Systems (MEMS) have played key roles in many important areas, for example transportation, communication, automated manufacturing, environmental monitoring, health care, defense systems, and a wide range of consumer products. MEMS are inherently small, thus offering attractive characteristics such as reduced size, weight, and power dissipation and improved speed and precision compared to their macroscopic counterparts. Integrated circuits (IC) fabrication technology has been the primary enabling technology for MEMS besides a few special etching, bonding and assembly techniques. Microfabrication provides a powerful tool for batch processing and miniaturization of electromechanical devices and systems into a dimensional scale, which is not achievable by conventional machining techniques. As IC fabrication technology continues to scale toward deep sub-micron and nano-meter feature sizes, a variety of nanoelectromechanical systems (NEMS) can be envisioned in the foreseeable future. Nano-scale mechanical devices and systems integrated with nanoelectronics will open a vast number of new exploratory research areas in science and engineering. NEMS will most likely serve as an enabling technology merging engineering with the life sciences in ways that are not currently feasible with the micro-scale tools and technologies. MEMS has been applied to a wide range of fields. Over hundreds of micro-devices have been developed for specific applications. It is thus difficult to provide an overview covering every aspect of the topic. In this chapter, key aspects of MEMS technology and application impacts are illustrated through selecting a few demonstrative device examples, which consist of pressure sensors, inertial sensors, optical and wireless communication devices. Microstructure examples with dimensions on the order of sub-micron are presented with fabrication technologies for future NEMS applications. Although MEMS has experienced significant growth over the past decade, many challenges still remain. In broad terms, these challenges can be grouped into three general categories; (1) fabrication challenges, (2) packaging challenges, and (3) application challenges. Challenges in these areas will, in large measure, determine the commercial success of a particular MEMS device both in technical and economic terms. This chapter presents a brief discussion of some of these challenges as well as possible approaches to address them.

8.1 MEMS Devices and Applications 227
  8.1.1 Pressure Sensor 227
  8.1.2 Inertial Sensor 229
  8.1.3 Optical MEMS 233
  8.1.4 RF MEMS 239

8.2 NEMS Devices and Applications 246

8.3 Current Challenges and Future Trends 249

References 250

Microelectromechanical systems, generally referred to as MEMS, has had a history of research and development spanning a few decades. Besides the traditional microfabricated sensors and actuators, the field covers micromechanical components and systems integrated or micro-assembled with electronics on the same substrate or package, achieving high performance functional systems. These devices and systems have played key roles in many important areas, such as transportation, communication, automated manufacturing, environmental monitoring, health care, defense systems, and a wide range of consumer products. MEMS are inherently small, thus offering such attractive characteristics as reduced size, weight, and power dissipation, as well as improved speed and precision compared to their macroscopic counterparts. The development of MEMS requires appropriate fabrication technologies that enable the definition of small geometries, precise dimension



Fig. 8.1 SEM micrograph of a polysilicon microelectromechanical motor [8.1]

control, design flexibility, interfacing with microelectronics, repeatability, reliability, high yield, and low cost. Integrated circuits (IC) fabrication technology meets all of the above criteria and has been the primary enabling fabrication technology for MEMS, besides a few special etching, bonding and assembly techniques. Microfabrication provides a powerful tool for batch processing and miniaturization of electromechanical devices and systems into a dimensional scale, which is not achievable by conventional machining techniques. Most MEMS devices exhibit a length or width ranging from micrometers to several hundreds of micrometers with a thickness from submicrometer up to tens of micrometers, depending upon the fabrication technique employed. A physical displacement of a sensor or an actuator is typically on the same order of magnitude. Figure 8.1 shows an SEM micrograph of a microelectromechanical motor developed in the late 1980s [8.1]. Polycrystalline silicon (polysilicon) surface micromachining technology was used to fabricate the micromotor, achieving a diameter of 150 μm and a minimum vertical feature size on the order of a micrometer. A probe tip is also shown in the micrograph for a size comparison. This device example, and similar others [8.2], demonstrated what MEMS technology could accomplish in microscale machining at the time and served as a strong technology indicator for continued MEMS development. The field has expanded greatly in recent years along with rapid technology advances. Figure 8.2, for example, shows a photo of micro-gears fabricated in the mid-1990s using a five-level polysilicon surface micromachining technology [8.3]. This device represents one of the most advanced surface micromachining fabrication processes developed to date. One can imagine that a wide range of sophisticated microelectromechanical devices and systems can be realized through applying such technology in the future. As IC fabrication technology continues to scale toward deep submicron and nanometer feature sizes, a variety of nanoelectromechanical systems (NEMS) can be envisioned in the near future. Nanoscale mechanical devices and systems integrated with nanoelectronics will open a vast number of new exploratory research areas in science and engineering. NEMS will most likely serve as an enabling technology, merging engineering with the life sciences in ways that are not currently feasible with microscale tools and technologies.

This chapter will provide a general overview of MEMS and NEMS devices and their applications. MEMS technology has been applied to a wide range of fields. Over hundreds of micro-devices have been developed for specific applications. Therefore, it is difficult to provide an overview that covers every aspect of the topic. It is the authors' intent to illustrate key aspects of MEMS technology, and its impact on specific applications by selecting a few demonstrative device examples. For a wide-ranging discussion of nearly all types of micromachined sensors and actuators, books by *Kovacs* [8.4] and *Senturia* [8.5] are recommended.



Fig. 8.2 SEM micrograph of polysilicon micro-gears [8.5]

8.1 MEMS Devices and Applications

MEMS devices have played key roles in many areas of development. Microfabricated sensors, actuators, and electronics are the most critical components in implementing a complete system for a specific function. Microsensors and actuators can be fabricated by various micromachining processing technologies. In this section, a number of selected MEMS devices are presented to illustrate the basic device operating principles, as well as demonstrate key aspects of microfabrication technology and its application impact.

8.1.1 Pressure Sensor

Pressure sensors are one of the early devices realized by silicon micromachining technologies and have become successful commercial products. The devices have been widely used in various industrial and biomedical applications. The sensors can be based on piezoelectric, piezoresistive, capacitive, and resonant sensing mechanisms. Silicon bulk and surface micromachining techniques have been used for sensor batch fabrication, thus achieving size miniaturization and low cost. Two types of pressure sensors – piezoresistive and capacitive – are described here for illustration purposes.

Piezoresistive Sensor

The piezoresistive effect in silicon has been widely used for implementing pressure sensors. A pressure-induced strain deforms the silicon band structure, thus changing the resistivity of the material. The piezoresistive effect is typically crystal-orientation dependent and is also affected by doping and temperature. A practical piezoresistive pressure sensor can be implemented by fabricating four sensing resistors along the edges of a thin silicon diaphragm, which acts as a mechanical amplifier to increase the stress and strain at the sensor site. The four sensing elements are connected in a bridge configuration with push-pull signals to increase the sensitivity. The measurable pressure range for such a sensor can be from 10^{-3} to 10^{6} torr, depending on the design. An example of a piezoresistive pressure sensor is shown in Fig. 8.3. The device consists of a silicon diaphragm suspended over a reference vacuum cavity to form an absolute pressure sensor. An external pressure applied over the diaphragm introduces a stress on the sensing resistors, resulting in a resistance value change corresponding to the pressure. The fabrication sequence is outlined as follows. The piezoresistors are typically first formed through a boron diffusion process, followed by a high temperature annealing step in order to achieve a resistance value on the order of a few kilo-ohms. The wafer is then passivated with a silicon dioxide layer, and contact windows are opened for metallization. At this point, the wafer is patterned on the backside, followed by a timed silicon wet etch to form the diaphragm, typically having a thickness around a few tens of micrometers. The diaphragm can have a length of several hundreds of micrometers. A second silicon wafer is then bonded to the device wafer in a vacuum to form a reference vacuum cavity, thus completing the fabrication process. The second wafer can also be further etched through to form an inlet port, implementing a gauge pressure sensor [8.6]. The piezoresistive sensors are simple to fabricate and can be readily interfaced with electronic systems. However, the resistors are temperature dependent and consume DC power. Long-term characteristic drift and resistor thermal noise ultimately limit the sensor resolution.

Capacitive Sensor

Capacitive pressure sensors are attractive because they are virtually temperature independent and consume zero DC power. The devices do not exhibit initial turn-on drift and are stable over time. Furthermore, CMOS microelectronic circuits can be readily interfaced with the sensors to provide advanced signal conditioning and processing, thus improving overall system performance. An example of a capacitive pressure sensor is shown in Fig. 8.4. The device consists of an edge-clamped silicon diaphragm suspended over a vacuum cavity. The diaphragm can be square or circular with a typical thickness of a few micrometers and a length or radius of a few hundred micrometers, respectively. The vacuum



Fig. 8.3 Cross-sectional schematic of a piezoresistive pressure sensor



Fig. 8.4 Cross-sectional schematic of a capacitive pressure sensor



Fig. 8.5 Cross-sectional schematic of a touch-mode capacitive pressure sensor

cavity typically has a depth of a few micrometers. The diaphragm and substrate form a pressure dependent airgap variable capacitor. An increased external pressure causes the diaphragm to deflect towards the substrate, resulting in an increase in the capacitance value. A simplified fabrication process can be outlined as follows. A silicon wafer is first patterned and etched to form the cavity. The wafer is then oxidized and bonded to a second silicon wafer with a heavily doped boron layer, which defines the diaphragm thickness, at the surface. The bonding process can be performed in a vacuum to realize the vacuum cavity. If the vacuum bonding is not performed at this stage, a low-pressure sealing process can be used to form the vacuum cavity after patterning the sensor diaphragm, provided that sealing channels are available. The silicon substrate above the boron layer is then removed through a wet etching process, followed by patterning to form the sensor diaphragm, which serves as the device top electrode. Contact pads are formed by metallization and patterning. This type of pressure sensor exhibits a nonlinear characteristic and a limited dynamic range. These phenomena, however, can be alleviated by applying an electrostatic-force-balanced feedback architecture. A common practice is to introduce another electrode above the sensing diaphragm through wafer bonding [8.7], forming two capacitors in series, with the diaphragm being the middle electrode. The capacitors are interfaced with electronic circuits, that convert the sensor capacitance value to an output voltage corresponding to the diaphragm position. This voltage is further processed to generate a feedback signal to the top electrode, thereby introducing an electrostatic pull up force to maintain the deflectable diaphragm at its nominal position. This negative feedback loop would substantially minimize the device nonlinearity and also extend the sensor dynamic range.

A capacitive pressure sensor achieving an inherent linear characteristic response and a wide dynamic range can be implemented by employing a touch mode architecture [8.8]. Figure 8.5 shows the cross-sectional view of a touch-mode pressure sensor. The device consists of an edge-clamped silicon diaphragm suspended over a vacuum cavity. The diaphragm deflects under an increasing external pressure and touches the substrate, causing a linear increase in the sensor capacitance value beyond the touch point pressure. Figure 8.6 shows a typical device characteristic curve. The touch point pressure can be designed by engineering the sensor geometric parameters, such as diaphragm size, thickness, cavity depth, etc., for various application requirements. The device can be fabricated using a process flow similar to the flow outlined for the basic capacitive pressure sensor. Figure 8.7 presents a photo of a fabricated touch-mode sensor employing a circular diaphragm with a diameter of 800 μm and a thickness of 5 μm suspended over a 2.5 μm vacuum cavity. The device achieves a touch point pressure of 8 psi and exhibits a linear capacitance range of 33 pF at 10 psi to 40 pF at 32 psi (absolute pressures).

The above processes use bulk silicon materials for machining and are usually referred to as bulk



Fig. 8.6 Characteristic response of a touch-mode capacitive pressure



Fig. 8.7 Photo of a touch-mode capacitive pressure sensor [8.12]

micromachining. The same devices can also be fabricated using so-called surface micromachining. Surface micromachining technology is attractive for integrating MEMS sensors with on-chip electronic circuits. As a result, advanced signal processing capabilities, such as data conversion, offset and noise cancellation, digital calibration, temperature compensation, etc., can be implemented adjacent to microsensors on the same substrate, providing a complete, high performance microsystem solution. The single chip approach also eliminates external wiring, which is critical for minimizing noise pickup and enhancing system performance. Surface micromachining, simply stated, is a method of fabricating MEMS through depositing, patterning, and etching a sequence of thin films with thicknesses on the order of a micrometer. Figure 8.8 illustrates a typical surface micromachining process flow [8.9]. The process starts by depositing a layer of sacrificial material, such as silicon dioxide, over a wafer, followed by anchor formation. A structural layer, typically a polysilicon film, is deposited and patterned. The underlying sacrificial layer is then removed to release the suspended microstructure and complete the fabrication sequence. The processing materials and steps are compatible with the standard integrated circuit process and, thus, can be readily incorporated as an add-on module to an IC process [8.9–11]. A similar surface micromachining technology has been developed to produce monolithic pressure sensor systems [8.12]. Figure 8.9 shows an SEM micrograph of an array of MEMS capacitive pressure sensors fabricated with BiCMOS electronics on the same substrate. Each sensor consists of a 0.8 μm-thick circular polysilicon membrane with a diameter on the order of 20 μm suspended over a 0.3 μm-deep vacuum cavity. The devices operate using the same principle as the sensor shown in Fig. 8.4. A close view of the sensor cross section is shown in Fig. 8.10, which shows the suspended membrane and underneath air gap. These sensors have demonstrated operations in pressure ranges up to 400 bar with an accuracy of 1.5%.



Fig. 8.8 Simplified fabrication sequence of surface micromachining technology

8.1.2 Inertial Sensor

Micromachined inertial sensors consist of accelerometers and gyroscopes. These devices are one of the important types of silicon-based MEMS sensors that have been successfully commercialized. MEMS ac-



Fig. 8.9 SEM micrograph of polysilicon surface-micromachined capacitive pressure sensors [8.12]



Fig. 8.10 SEM micrograph of a close-up view of a polysilicon surface-micromachined capacitive pressure sensor [8.12]

celerometers alone have the second largest sales volume after pressure sensors. Gyroscopes are expected to reach a comparable sales volume in the foreseeable future. Accelerometers have been used in a wide range of applications, including automotive application for safety systems, active suspension and stability control, biomedical application for activity monitoring, and numerous consumer products, such as head-mount displays, camcorders, three-dimensional mouse, etc. High sensitivity accelerometers are crucial for implementing self-contained navigation and guidance systems. A gyroscope is another type of inertial sensor that measures rate or angle of rotation. The devices can be used along with accelerometers to provide heading information in an inertial navigation system. Gyroscopes are also useful in such applications as automotive ride stabilization and rollover detection, camcorder stabilization, virtual reality, etc. Inertial sensors fabricated by micromachining technology can achieve reduced size, weight, and cost, all which are critical for consumer applications. More importantly, these sensors can be integrated with microelectronic circuits to achieve a functional microsystem with high performance.

Accelerometer

An accelerometer generally consists of a proof mass suspended by compliant mechanical suspensions anchored to a fixed frame. An external acceleration displaces the support frame relative to the proof mass. The displacement can result in an internal stress change in the suspension, which can be detected by piezoresistive sensors as a measure of the external acceleration. The displacement can also be detected as a capacitance change in capacitive accelerometers. Capacitive sensors are attractive for various applications because they exhibit high sensitivity and low temperature dependence, turn-on drift, power dissipation, and noise. The sensors can also be readily integrated with CMOS electronics to perform advanced signal processing for high system performance. Capacitive accelerometers may be divided into two categories: vertical and lateral sensors. Figure 8.11 shows sensor structures for the two versions. In a vertical device, the proof mass is suspended above the substrate electrode by a small gap typically on the order of a micrometer, forming a parallel-plate sense capacitance. The proof mass moves in the direction perpendicular to the substrate (z-axis) upon a vertical input acceleration, thus changing the gap and the capacitance value. The lateral accelerometer consists of a number of movable fingers attached to the proof mass, forming a sense capacitance with an array of fixed parallel fingers. The sensor proof mass moves in a plane parallel to the substrate when subjected to a lateral input acceleration, thus changing the overlap area of these fingers and, hence, the capacitance value. Figure 8.12 shows an SEM top view of a surface micromachined polysilicon z-axis accelerometer [8.13]. The device consists of a $400\,\mu\text{m} \times 400\,\mu\text{m}$ proof mass with a thickness of $2\,\mu\text{m}$ suspended above the substrate electrode by four folded beam suspensions with an air gap around $2\,\mu\text{m}$, thus achieving a sense capacitance of approximately 500 fF.

The visible holes are used to ensure complete removal of the sacrificial oxide underneath the proof mass at the end of the fabrication process. The sensor can be interfaced with a microelectronic charge amplifier, converting the capacitance value to an output voltage for further signal processing and analysis. Force feedback architecture can be applied to stabilize the proof mass position. The combs around the periphery of the proof mass can exert an electrostatic levitation force on the proof mass to achieve the position control, thus improving the system frequency response and linearity performance [8.13].

Surface micromachined accelerometers typically suffer from severe mechanical thermal vibration, commonly referred to as Brownian motion [8.14], due to the small proof mass, resulting in a high mechanical noise floor that ultimately limits the sensor resolution. Vacuum packaging can be employed to minimize this adverse effect, but with a penalty of increasing system complexity and cost. Accelerometers using large proof masses fabricated by bulk micromachining, or a combination of surface and bulk micromachining techniques are attractive for circumventing this problem. Figure 8.13 shows an SEM micrograph of an all-silicon z-axis accelerometer fabricated through a single silicon wafer by using a combined surface and bulk micromachining process to obtain a large proof mass with dimensions of approximately $2\,\text{mm} \times 1\,\text{mm} \times 450\,\mu\text{m}$ [8.15]. The large mass suppresses the Brownian motion effect, achieving a high performance with a resolution on the order of several μg.

A surface micromachined lateral accelerometer developed by Analog Devices Inc. is shown in Fig. 8.14. The sensor consists of a center proof mass supported by folded beam suspensions with arrays of attached movable fingers, forming a sense capacitance with the fixed parallel fingers. The device is fabricated using a 6 μm-thick polysilicon structural layer with a small air gap on the order of a micrometer to increase the sensor capacitance value, thus improving the device resolution. Figure 8.15 shows a close-up view of the finger structure for a typical lateral accelerometer. Each movable finger forms differential capacitances with two adjacent fixed fingers. This sensing capacitance configuration is attractive for interfacing with differential electronic detection circuits to suppress common-mode noise and other undesirable signal coupling. Monolithic accelerometers with a three-axis sensing capability integrated with on-chip electronic detection circuits have been realized using surfacing micromachining and CMOS microelectronics fabrication technologies [8.16]. Figure 8.16 shows



Fig. 8.11a,b Schematics of vertical **(a)** and lateral **(b)** accelerometers



Fig. 8.12 SEM micrograph of a polysilicon surface-micromachined z-axis accelerometer [8.13]


Silicon frame
Top and bottom stiffener supports
Silicon proof mass
Top and bottom support beams
Metal pads
0024 15KV X23 3 1 mm WD37

Fig. 8.13 SEM micrograph of a MEMS z-axis accelerometer fabricated using a combined surface and bulk micromachining technology [8.15]

a photo of one of these microsystem chips, which has an area of 4 mm × 4 mm. One vertical accelerometer and two lateral accelerometers are placed at the chip center with corresponding detection electronics along the periphery. A z-axis reference device, which is not movable, is used with the vertical sensor for electronic interfacing. The prototype system achieves a sensing resolution on the order of 1 mG with a 100 Hz bandwidth along each axis. The level of performance is adequate for automobile safety activation systems, vehicle stability, active suspension control, and various consumer products.



Fig. 8.14 SEM micrograph of a polysilicon surface-micromachined lateral accelerometer (courtesy of Analog Devices Inc.)



Fig. 8.15 SEM micrograph of a capacitive sensing finger structure

Gyroscope

Most micromachined gyroscopes employ vibrating mechanical elements to sense rotations. The sensors rely on the energy transfer between two vibration modes of a structure caused by Coriolis acceleration. Figure 8.17 presents a schematic of a z-axis vibratory rate gyroscope. The device consists of an oscillating mass electrostatically driven into resonance along the drive-mode axis using comb fingers. An angular rotation along the vertical axis (z-axis) introduces a Coriolis acceleration, which results in a structure deflection along the sense-mode axis, shown in the figure. The deflection changes the differential sense capacitance value, which can be detected as a measure of input angular rotation. A z-axis vibratory rate gyroscope operating on this principle is fabricated using surface micromachining technology and integrated together with electronic detection circuits, as illustrated in Fig. 8.18 [8.17]. The micromachined sensor is fabricated using polysilicon structural material with a thickness around 2 µm and occupies an area of 1 mm × 1 mm. The sensor achieves a resolution of approximately $1°/\mathrm{s}/\sqrt{\mathrm{Hz}}$ under a vacuum pressure around 50 mtorr.

A dual-axis gyroscope based on a rotational disk at its resonance can be used to sense angular rotation along two lateral axes (x-axis and y-axis). Figure 8.19 shows a device schematic demonstrating the operating principle. A rotor disk supported by four mechanical suspensions can be driven into angular resonance along the z-axis. An input angular rotation along the x-axis will generate a Coriolis acceleration, causing the disk to rotate along the y-axis and vice versa. This Coriolis acceleration-induced rotation will change the sensor capacitance values between the disk and the different sensing electrodes underneath. The capacitance change can be detected and processed by electronic interface circuits. Angular rotations along the two lateral axes can be measured simultaneously using this device architecture. Figure 8.20 shows a photo of a dual-axis gyroscope fabricated using a 2 µm-thick polysilicon surface micromachining technology [8.18]. As shown in the figure, curved electrostatic drive combs are positioned along the circumference of the rotor dick to drive it into resonance along the vertical axis. The gyroscope exhibits a low random walk of $1°/\sqrt{\mathrm{h}}$ under a vacuum pressure around 60 mtorr. With accelerometers and gyroscopes, each capable of three-axis sensing, a micromachine-based inertial measurement system providing a six-degree-of-freedom sensing capability can be realized. Figure 8.21 presents a photo of such a system containing a dual-axis gyroscope, a z-axis gyroscope, and a three-axis accelerometer chip integrated with microelectronic circuitry. Due to the precision in device layout and fabrication, the system can measure angular rotation and acceleration without the need to align individual sensors.



Fig. 8.16 Photo of a monolithic three-axis polysilicon surface-micromachined accelerometer with integrated interface and control electronics [8.16]


Structural anchor to substrate
z–axis
Input rotation
Sense mode
Comb drives to
sustain oscillation
Driven mode
Interdigitated comb finger
deflection sense capacitors

Fig. 8.17 Schematic of a vibratory rate gyroscope

8.1.3 Optical MEMS

Surface micromachining has served as a key enabling technology to realize microeletromechanical optical devices for various applications ranging from sophisticated visual information displays and fiber-optic telecommunication to bar-code reading. Most of the existing optical systems are implemented using conventional optical components, which suffer from bulky size, high cost, large power consumption, and poor efficiency and reliability issues. MEMS technology is promising for producing miniaturized, reliable, inexpensive



Fig. 8.18 Photo of a monolithic polysilicon surface-micromachined *z*-axis vibratory gyroscope with integrated interface and control electronics [8.17]


z-axis drive
x-axis coriolis output oscillations
y-axis coriolis output oscillations
Input rate Ω_x
Input rate Ω_y

Fig. 8.19 Schematic of a dual-axis gyroscope


Rotor
Electrostatic drive combs
600 µm

Fig. 8.20 Photo of a polysilicon surface-micromachined dual-axis gyroscope [8.18]

Fig. 8.21 ▾ Photo of a surface-micromachined inertial measurement system with a six-degree sensing capability


z-axis gyro
x,*y*-axis gyro
x,*y*,*z*-axis accelerometer

optical components to revolutionize conventional optical systems [8.19]. In this section of the chapter, a few selected MEMS optical devices will be presented to illustrate their impact on the fields of visual display, precision optical platform, and data switching for optical communication.

Visual Display

An early MEMS device successfully used for various display applications is the Texas Instruments Digital Micromirror Device (DMD). The DMD technology can achieve higher performance in terms of resolution, brightness, contrast ratio, and convergence than the conventional cathode ray tube and is critical for digital high definition television applications. A DMD consists of a large array of small mirrors with a typical area of 16 μm × 16 μm, as illustrated in Fig. 8.22. A probe tip is shown in the figure for a size comparison. Figure 8.23 shows an SEM micrograph of a close-up view of a DMD pixel array [8.20]. Each mirror is capable of rotating by ±10 degrees, corresponding to either the "on" or "off" position, due to an electrostatic actuation force. Light reflected from any on-mirrors passes through a projection lens and creates images on a large screen. Light from the remaining off-mirrors is reflected away from the projection lens to an absorber. The amount of time during each video frame that a mirror remains in the on-state determines shades of gray, from black for zero on-time to white for a hundred percent on-time. Color can be added by a color wheel or a three-DMD chip setup. The three-DMD chips are used for projecting red, green, and blue colors. Each DMD pixel consists of a mirror connected by a mirror support post to an underlying yoke. The yoke, in turn, is connected by torsion hinges to the support posts, as shown in Fig. 8.24 [8.21]. The support post and hinges are hidden under the mirror to avoid light diffraction and, thus, improve contrast ratio and optical efficiency. There are two gaps on the order of a micrometer, one between the mirror, the underlying hinges and the address electrodes, and a second between the coplanar address electrodes, the hinges and an underlying metal layer from the CMOS static random access memory (SRAM) structure. The yoke is tilted over the second gap by an electrostatic actuation force, thereby rotating the mirror plate. The SRAM determines which angle the mirror needs to be tilted by applying proper actuation voltages to the mirror and address electrodes. The DMD is fabricated using an aluminum-based surface micromachining technology. Three layers of aluminum thin film are deposited and patterned to form the mirror and its suspension system. Polymer material is used as the sacrificial layer and is removed by a plasma etch at the end of the process to freely release the micromirror structure. The micromachining process is compatible with standard CMOS fabrication, allowing the DMD to be monolithically integrated with a mature CMOS address circuit technology, thus achieving high yield and low cost. Figure 8.25 shows an SEM micrograph of a fabricated DMD pixel revealing its cross section after an ion milling. A close-up view of the yoke and hinge support under the mirror is shown in Fig. 8.26.


Fig. 8.22 Photo of a digital micromirror device (DMD) array (courtesy of Texas Instruments)


Fig. 8.23 SEM micrograph of a close-up view of a DMD pixel array [8.20]



Fig. 8.24 Detailed structure layout of a DMD pixel [8.21]



Fig. 8.25 SEM micrograph of a DMD pixel after removing half of the mirror plate using ion milling (courtesy of Texas Instruments)



Fig. 8.26 SEM micrograph of a close view of a DMD yoke and hinges [8.21]

Precision Optical Platform

The growing optical communication and measurement industry requires low cost, high performance optoelectronic modules, such as laser-to-fiber couplers, scanners, interferometers, etc. A precision alignment and the ability to actuate optical components, such as mirrors, gratings, and lenses, with sufficient accuracy are critical for high performance optical applications. Conventional hybrid optical integration approaches, such as the silicon optical bench, suffers from a limited alignment tolerance of ±1 µm and also lacks component actuation capability [8.22, 23]. As a result, only simple optical systems can be constructed with no more than a few components, thus severely limiting the performance. Micromachining, however, provides a critical enabling technology, allowing movable optical components to be fabricated on a silicon substrate. High-precision component movement can be achieved through electrostatic actuation. By combining micromachined movable optical components with lasers, lenses, and fibers on the same substrate, an on-chip, complex, self-aligning optical system can be realized. Figure 8.27a shows an SEM micrograph of a surface micromachined, electrostatically actuated microreflector for laser-to-fiber coupling and external cavity laser applications [8.24]. The device consists of a polysilicon mirror plate hinged to a support beam. The mirror and the support, in turn, are hinged to a vibromotor-actuator slider. The micro-hinge technology [8.25] allows the joints to rotate out of the substrate plane to achieve large aspect ratios. Common-mode actuation of the sliders results in a translational motion, while differential slider motion produces an out-of-plane mirror rotation. These motions permit the microreflector to redirect an optical beam in a desirable location. Each of the two slides is actuated with an integrated microvibromotor, shown in Fig. 8.27b. The vibromotor consists of four electrostatic comb resonators with attached impact arms driving a slider through oblique



Fig. 8.27 **(a)** SEM micrograph of a surface-micromachined, electrostatically actuated microreflector; **(b)** SEM micrograph of a surface-micromachined vibromotor [8.24]

impact. The two opposing impacters are used for each travel direction to balance the forces. The resonator is a capacitively driven mass anchored to the substrate through a folded beam flexure. The flexure compliance determines the resonant frequency and travel range of the resonator. When the comb structures are driven at their resonant frequency (around 8 KHz), the slider exhibits a maximum velocity of over 1 mm/s. Characterization of the vibromotor also shows that a slider step resolution of less than 0.3 μm can be achieved [8.26], making it attractive for precision alignment of various optical components. The prototype microreflector can obtain an angular travel range over 90 degrees and a translational travel range of 60 μm. By using this device, beam steering, fiber coupling, and optical scanning have been demonstrated.

Optical Data Switching

High-speed communication infrastructures are highly desirable for transferring and processing real-time voice and video information. Optical fiber communication technology has been identified as the critical backbone to support such systems. A high performance optical data switching network, which routes various optical signals from sources to destinations, is one of the key building blocks for system implementation. At present, optical signal switching is performed by using hybrid optical-electronic-optical (O-E-O) switches. These devices first convert incoming light from input fibers to electrical signals and then route the electrical signals to the proper output ports after signal analyses. At the output ports, the electrical signals are converted back to streams of photons or optical signals for further transmission over the fibers. The O-E-O switches are expensive to build, integrate, and maintain. Furthermore, they consume a substantial amount of power and introduce additional latency. It is, therefore, highly desirable to develop an all-optical switching network in which optical signals can be routed without intermediate conversion into electrical form, thus minimizing power dissipation and system delay. While a number of approaches are being considered for building all-optical switches, MEMS technology is attractive because it can provide arrays of tiny movable mirrors that can redirect incoming beams from input fibers to corresponding output fibers. As described in the previous sections, these micromirrors can be batch fabricated using silicon micromachining technologies, achieving an integrated solution with the potential for low cost. A significant reduction in power dissipation is also expected.

Figure 8.28 shows an architecture of a two-dimensional micromirror array forming a switching matrix with rows of input fibers and columns of output fibers (or vice versa). An optical beam from an input fiber can be directed to an output fiber by activating the cor-



Fig. 8.28 Schematic of a two-dimensional micromirror-based fiber optic switching matrix

responding reflecting micromirror. Switches with eight inputs and eight outputs can be readily implemented using this technique, which can be further extended to a 64 × 64 matrix. The micromirrors are moved between two fixed stops by digital control, eliminating the need for precision motion control. Figure 8.29 presents an SEM micrograph of a simple 2 × 2 MEMS fiber optic switching network prototype for an illustration purpose [8.27]. The network includes a mirror chip passively integrated with a silicon submount, which contains optical fibers and ball lenses. The mirror chip consists of four surface-micromachined vertical torsion mirrors. The four mirrors are arranged so that in the "reflection" mode, the input beams are reflected by two 45-degree vertical torsion mirrors and coupled with the output fibers located on the same side of the chip. In the "transmission" mode, the vertical torsion mirrors are rotated out of the optical paths, allowing the input beams to be coupled with the opposing output fibers. Figure 8.30 shows an SEM micrograph of a polysilicon vertical torsion mirror. The device consists of a mirror plate attached to a vertical supporting frame by torsion beams and a vertical back electrode plate. The mirror plate is approximately 200 µm wide, 160 µm long, and 1.5 µm thick. The mirror surface is coated with a thin layer of gold to improve the optical reflectivity. The back plate is used to electrostatically actuate the mirror plate, so that the mirror can be rotated out of the optical path in the "transmission" mode. Surface micromachining with micro-hinge technology is used to realize the overall structure. The back electrode plate is integrated with a scratch drive actuator array [8.28] for self-assembly. The self-assembly approach is critical when multiple vertical torsion mirrors are used to implement more advanced functions.



Fig. 8.29 SEM micrograph of a 2 × 2 MEMS fiber optic switching network [8.27]

A more sophisticated optical switching network with a large scaling potential can be implemented by using a three-dimensional (3-D) switching architecture, as shown in Fig. 8.31. The network consists of arrays of two-axis mirrors to steer optical beams from input fibers to output fibers. A precision analog closed-loop mirror position control is required to accurately direct a beam along two angles, so that one input fiber can be optically



Fig. 8.30 SEM micrograph of a polysilicon surface-micromachined vertical torsion mirror [8.27]

connected to any output fiber. The optical length depends little on which sets of fibers are connected, thus achieving a more uniform switching characteristic, which is critical for implementing large scale networks. Two-axis mirrors are the crucial components for implementing the 3-D architecture. Figure 8.32 shows an SEM micrograph of a surface micromachined two-axis beam-steering mirror positioned by using self-assembly technique [8.29]. The self-assembly is accomplished during the final release step of the mirror processing sequence. Mechanical energy is stored in a special high-stress layer during the deposition, which is put on top of the four assembly arms. Immediately after the assembly arms are released, the tensile stress in this layer causes the arms to bend upward, pushing the mirror frame and lifting it above the silicon substrate. All mirrors used in the switching network can be fabricated simultaneously without any human intervention or external power supply.

8.1.4 RF MEMS

The increasing demand for wireless communication applications, such as cellular and cordless telephony, wireless data networks, two-way paging, global positioning systems, etc., feeds a growing interest in building miniaturized wireless transceivers with multi-standard capabilities. Such transceivers will greatly enhance the convenience and accessibility of various wireless services independent of geographic location. Miniaturizing current single-standard transceivers through a high level of integration is a critical step toward building transceivers that are compatible with multiple standards. Highly integrated transceivers will also result in reduced package complexity, power consumption, and cost. At present, most radio transceivers rely on a large number of discrete frequency-selection components, such as radio frequency (RF) and intermediate frequency (IF) band-pass filters, RF voltage-controlled oscillators (VCOs), quartz crystal oscillators, solid-state switches, etc., to perform the necessary analog signal processing. Figure 8.33 shows a schematic of a super-heterodyne radio architecture, in which discrete components are shaded. These off-chip devices occupy the majority of the system area, thus severely hindering transceiver miniaturization. MEMS technology, however, offers a potential solution to integrate these discrete components onto silicon substrates with microelectronics, achieving a size reduction of a few orders of magnitude. It is, therefore, expected to become a technology that will ultimately enable the miniaturization of radio transceivers for future wireless communications.



Fig. 8.31 Schematic of a three-dimensional micromirror-based fiber optic switching matrix



Fig. 8.32 SEM micrograph of a surface micromachined two-axis beam-steering micromirror positioned using self-assembly technique [8.29]


LNA
Image rejection filter (ceramic)
Mixer
IF channel selection filter (SAW)
IF amp
Mixer
To base band
RF VCO
PLL
PLL
IF VCO
Crystal
RF switch
RF filter (ceramic)
RF VCO
PLL
Power amplifier
From base band
Mixer
Low-pass filter

Fig. 8.33 Schematic of a super-heterodyne radio architecture

MEMS Variable Capacitors

Integrated high performance variable capacitors are critical for low noise VCOs, antenna tuning, tunable matching networks, etc. Capacitors with high quality factors (Q), large tuning range, and linear characteristics are crucial for achieving system performance requirements. On-chip silicon PN junction and MOS-based variable capacitors suffer from low quality factors (below 10 at 1 GHz), limited tuning range, and poor linearity, and are, therefore, inadequate for building high performance transceivers. MEMS technology has demonstrated monolithic variable capacitors, achieving stringent performance requirements. These devices typically rely on an electrostatic actuation method to vary the air gap between a set of parallel plates [8.30–33], or vary the capacitance area between a set of conductors [8.34], or mechanically displace a dielectric layer in an air-gap capacitor [8.35]. Improved tuning ranges have been achieved with various device configurations. Figure 8.34 shows SEM micrographs of an aluminum micromachined variable capacitor fabricated on a silicon substrate [8.30]. The device consists of a 200 µm × 200 µm aluminum plate with a thickness of



Fig. 8.34 **(a)** SEM micrograph of a top view of an aluminum surface-micromachined variable capacitor; **(b)** SEM micrograph of a cross-sectional view of the variable capacitor [8.30]

1 µm suspended above the bottom electrode by an air gap of 1.5 µm. Aluminum is selected as the structural material due to its low resistivity, which is critical for achieving a high quality factor at high frequencies. A DC voltage applied across the top and bottom electrodes introduces an electrostatic pull-down force, which pulls the top plate towards the bottom electrode, thus changing the device capacitance value. The capacitors are fabricated using aluminum-based surface micromachining technology. Sputtered aluminum is used for building the capacitor top and bottom electrodes. Photoresist serves as the sacrificial layer, which is then removed through an oxygen-based plasma dry etch to release the microstructure. The processing technology requires a low thermal budget, allowing the variable capacitors to be fabricated on top of wafers with completed electronic circuits without degrading the performance of active devices. Figure 8.35 presents an SEM micrograph of four MEMS tunable capacitors connected in parallel. This device achieves a nominal capacitance value of 2 pF and a tuning range of 15% with 3 V. A quality factor of 62 has been demonstrated at 1 GHz, which matches or exceeds that of discrete varactor diodes and is at least an order of magnitude larger than that of a typical junction capacitor implemented in a standard IC process.

MEMS tunable capacitors, based on the varying capacitance area between a set of conductors, have been demonstrated. Figure 8.36 shows an SEM micrograph of such a device [8.34]. The capacitor is composed of arrays of interdigitated electrodes, which can be electrostatically actuated to vary the electrode overlap area. A close-up view of the electrodes is shown in Fig. 8.37. The capacitor is fabricated using a silicon-on-insulator (SOI) substrate with a top silicon layer thickness of about 20 µm to obtain a high-aspect ratio for the electrodes, which is critical for achieving a large capacitance density and reduced tuning voltage. The silicon layer is etched to form the device structure, followed by the removal of the oxide underneath to release the capacitor. A thin aluminum layer is then sputtered over the capacitor to reduce the series resistive loss. The device exhibits a quality factor of 34 at 500 MHz and can be tuned between 2.48 pF and 5.19 pF with an actuation voltage under 5 V, corresponding to a tuning range of 100%. Figure 8.38 shows the variation of electrode overlap under different tuning voltages.

Tunable capacitors relying on a movable dielectric layer have been fabricated using MEMS technology. Figure 8.39 presents an SEM micrograph of a copper-based micromachined tunable capacitor [8.35]. The device consists of an array of copper top electrodes suspended above a bottom copper plate with an air gap of approximately 1 µm. A thin nitride layer is deposited, patterned, and suspended between the two copper layers by lateral mechanical spring suspensions after sacrificial release. A DC voltage applied across the copper layers introduces a lateral electrostatic pull-in force on the nitride, resulting in a movement that changes the overlapping area between each copper electrode and the bottom plate and, hence, the device capacitance. The


Fig. 8.35 SEM micrograph of four MEMS aluminum variable capacitors connected in parallel [8.30]



Fig. 8.36 SEM micrograph of a silicon tunable capacitor using a comb drive actuator [8.34]



Fig. 8.37 SEM micrograph of a close view of tunable capacitor comb fingers [8.34]



Fig. 8.38 Photos of comb fingers at different actuation voltages [8.34]

tunable capacitor achieves a quality factor of over 200 at 1 GHz with 1 pF capacitance, due to the highly conductive copper layers, and a tuning range around 8% with 10 V.



Fig. 8.39 SEM micrograph of a copper surface-micromachined tunable capacitor with a movable dielectric layer [8.35]

Micromachined Inductors

Integrated inductors with high quality factors are as critical as the tunable capacitors for high performance RF system implementation. They are the key components for building low noise oscillators, low loss matching networks, etc. Conventional on-chip spiral inductors suffer from limited quality factors of around 5 at 1 GHz, an order of magnitude lower than the required values from discrete counterparts. The poor performance is mainly due to substrate loss and metal resistive loss at high frequencies. Micromachining technology provides an attractive solution to minimizing these loss contributions, hence, enhancing the device quality factors. Figure 8.40 shows an SEM micrograph of a 3-D coil inductor fabricated on a silicon substrate [8.36]. The device consists of four-turn 5 µm-thick copper traces electroplated around an insulating Alumina core with a 650 µm × 500 µm cross section. Compared to spiral inductors, this geometry minimizes the coil area, which is in close proximity to the substrate, and, hence, the eddy-current loss, resulting in a maximized Q-factor and device self-resonant frequency. Copper is selected as the interconnect metal because of its low sheet resistance, critical for achieving a high Q-factor. The inductor achieves a 14 nH inductance value with a quality factor of 16 at 1 GHz. A single-turn 3-D device exhibits a Q-factor of 30 at 1 GHz, which matches the performance of discrete counterparts. The high-Q 3-D inductor and MEMS tunable capacitors, shown in Fig. 8.35, have been employed to implement a RF CMOS VCO achieving a low phase noise performance suitable for typical wireless communication applications, such as GMS cellular telephony [8.37].

Other 3-D inductor structures, such as the levitated spiral inductors, have been demonstrated using micromachining fabrication technology. Figure 8.41 shows an SEM micrograph of a levitated copper inductor,



Fig. 8.40 SEM micrograph of a 3-D coil inductor fabricated on a silicon substrate [8.36]



Fig. 8.41 SEM micrograph of a levitated spiral inductor fabricated on a glass substrate [8.38]

which is suspended above the substrate by supporting posts [8.38]. The levitated geometry can minimize the substrate loss, thus achieving an improved quality factor. The inductor shown in the figure achieves a 14 nH inductance value with a Q-factor of 38 at 1.8 GHz using a glass substrate.

A self-assembled out-of-plane coil has been fabricated using micromachining technology. The inductor winding traces are made of refractory metals with controlled built-in stress such that the traces can curl out of the substrate surface upon release and interlock into each other to form coil windings. Figure 8.42 shows an SEM micrograph of a self-assembled out-of-plane coil inductor [8.39]. A close-up view of an interlocking trace is shown in Fig. 8.43. Copper is plated on the interlocked traces to form highly conductive windings at the end of the processing sequence. The inductor shown in Fig. 8.42 achieves a quality factor around 40 at 1 GHz.



Fig. 8.42 SEM micrograph of a self-assembled out-of-plane coil inductor [8.39]



Fig. 8.43 SEM micrograph of an interlocking trace from a self-assembled out-of-plane oil inductor [8.39]

MEMS Switches

The microelectromechanical switch is another potentially attractive miniaturized component enabled by micromachining technologies. These switches offer superior electrical performance in terms of insertion loss, isolation, linearity, etc. and are intended to replace off-chip solid state counterparts, which provide switching between the receiver and transmitter signal paths. They are also critical for building phase shifters, tunable antennas, and filters. The MEMS switches can be broken into two categories: capacitive and metal-to-metal contact types. Figure 8.44 presents a cross-sectional schematic of a RF MEMS capacitive switch. The device consists of a conductive membrane, typically made of aluminum or gold alloy, suspended above a coplanar electrode by an air gap of a few micrometers. For RF or microwave applications, actual metal-to-metal contact is not necessary; rather, a step change in the plate-to-plate capacitance realizes the switching function. A thin silicon nitride layer with a thickness on the order of 1,000 Å is typically deposited above the bottom electrode. When the switch is in the on-state, the membrane is high, resulting in a small plate-to-plate capacitance and, hence, a minimum high-frequency signal coupling (high isolation) between the two electrodes. In the off-state (with a large enough applied DC voltage), the switch provides a large capacitance due to the thin dielectric layer, thus causing a strong signal coupling (low insertion loss). The capacitive switch consumes near zero power, which is attractive for low power portable applications. Switching cycles numbering in the millions for this type of device have been demonstrated. Figure 8.45 shows a top view photo of a fabricated MEMS capacitive switch [8.40]. Surface micromachining technology, using metal for the electrodes and polymer as the sacrificial layer, is used to fabricate the device. The switch can be actuated with a DC voltage on the order of 50 V and exhibits a low insertion loss of approximately −0.28 dB at 35 GHz and a high isolation of −35 dB at the same frequency.



Fig. 8.44 Cross-sectional schematics of an RF MEMS capacitive switch



Fig. 8.45 Top view photo of a fabricated RF MEMS capacitive switch [8.40]

Metal-to-metal contact switches are important for interfacing large bandwidth signals, including DC. This type of device typically consists of a cantilever beam, or clamped-clamped bridge with a metallic contact pad positioned at the beam tip or underneath the bridge center. Through an electrostatic actuation, a contact can be formed between the suspended contact pad and an underlying electrode on the substrate [8.41–43]. Figure 8.46 shows a cross-sectional schematic of a metal-to-metal contact switch [8.43]. The top view of the fabricated device is presented in Fig. 8.47. The switch exhibits an actuation voltage of 30 V, a response time of 20 μs, and the mechanical strength to withstand 10^9 actuations. An isolation greater than 50 dB below 2 GHz and insertion loss less than 0.2 dB from DC through 40 GHz have been demonstrated.

MEMS Resonators

Microelectromechanical resonators based on polysilicon comb-drive structures, suspended beams, and center-pivoted disk configurations have been demonstrated for performing analog signal processing [8.44–48]. These micro-resonators can be excited into mechanical reso-



Fig. 8.46 Cross-sectional schematic of a metal-to-metal contact switch [8.43]



Fig. 8.47 Top view photo of a fabricated metal-to-metal contact switch [8.43]



Fig. 8.48 SEM micrograph of a surface micromachined comb drive resonator integrated with CMOS sustaining electronics [8.44]

nance through an electrostatic drive. The mechanical motion causes a change of device capacitance, resulting in an output electrical current when a proper DC bias voltage is used. The output current exhibits the same frequency as the mechanical resonance, thus achieving an electrical filtering function through the electro mechanical coupling. Micromachined polysilicon flexural-mode mechanical resonators have demonstrated a quality factor greater than 80,000 in a 50 µtorr vacuum [8.49]. This level of performance is comparable to a typical quartz crystal and is, therefore, attractive for implementing monolithic low noise and low drift reference signal sources. Figure 8.48 shows an SEM micrograph of a surface micromachined comb-drive resonator integrated with CMOS sustaining electronics on the same substrate to form a monolithic high-Q MEMS resonator-based oscillator [8.44]. The oscillator achieves an operating frequency of 16.5 KHz with a clean spectral purity. A chip area of approximately 420 µm × 230 µm is consumed for fabricating the overall system, representing a size reduction by orders of magnitude compared to conventional quartz crystal oscillators.

Micromachined high-Q resonators can be coupled to implement low-loss frequency selection filters. Figure 8.49 shows an SEM micrograph of a surface micromachined polysilicon two-resonator, spring-coupled bandpass micromechanical filter [8.46]. The filter consists of two silicon micromechanical clamped-clamped beam resonators, coupled mechanically by a soft spring, all suspended 0.1 µm above the substrate. Polysilicon strip lines underlie the central regions of each resonator and serve as capacitive transducer electrodes positioned



Fig. 8.49 SEM micrograph of a polysilicon surface micromachined two-resonator spring-coupled bandpass micromechanical filter [8.46]

to induce resonator vibration in a direction perpendicular to the substrate. Under normal operation, the device is excited capacitively by a signal voltage applied to the input electrode. The output is taken at the other end of the structure, also by capacitive transduction. The filter achieves a center frequency of 7.81 MHz, a bandwidth of 0.23%, and an insertion loss less than 2 dB. The achieved performance is attractive for implementing filters in the low MHz range.

To obtain a higher mechanical resonant frequency with low losses, a surface micromachined contour-mode disk resonator has been proposed, as shown in Fig. 8.50 [8.48]. The resonator consists of a polysilicon disk suspended 5,000 Å above the substrate with a single anchor at its center. Plated metal input electrodes surround the perimeter of the disk with a narrow separation of around 1,000 Å, which defines the capacitive, electromechanical transducer of the device. To operate the device, a DC bias voltage is applied to the structure with an AC input signal applied to the electrodes, resulting in a time varying electrostatic force acting radially on the disk. When the input signal matches the device resonant frequency, the resulting electrostatic force is amplified by the Q factor of the resonator, resulting in the expansion and contraction of the disk along its radius. This motion, in turn, produces a time varying output current at the same frequency, thus achieving the desirable filtering. The prototype resonator demonstrates an operating frequency of 156 MHz with a Q factor of 9,400 in vacuum. The increased resonant frequency is comparable to the first intermediate frequency used in a typical wireless transceiver design and is thus suitable for implementing IF bandpass filters. A higher operating frequency is needed in order to potentially replace the RF frequency selection filters with microelectromechanical resonators.



Fig. 8.50 SEM micrograph of a polysilicon surface-micromachined contour-mode disk resonator [8.48]

8.2 NEMS Devices and Applications

Unlike their microscale counterparts, nanoelectromechanical systems (NEMS) are made of electromechanical devices that have critical structural dimensions on the submicron scale. These devices are attractive for applications where structures of very small mass provide essential functionality, such as force sensors, chemical sensors, biological sensors, and ultrahigh frequency resonators, to name a few. NEMS fabrication processes can be categorized according to the two approaches used to create the structures. Top-down approaches utilize submicron lithographic techniques to fabricate device structures from bulk material, either thin films or thick substrates. Bottom-up approaches involve the fabrication of nanoscale devices in much the same way that nature constructs objects, by sequential assembly using atomic and molecular building blocks. While many contend that bottom-up approaches will eventually dominate the fabrication of NEMS, most of the functional NEMS devices are currently created utilizing top-down techniques that combine existing process technologies, such as submicron electron-beam lithography, conventional film growth, and chemical etching. Top-down approaches make integration with microscale packaging relatively straightforward since the only significant difference between the nanoscale and microscale processing steps is the method used to pattern the various features.

In large measure, NEMS has followed a developmental path similar to that of MEMS in that both have leveraged existing processing techniques. For instance, the electron-beam lithographic techniques used in top-down NEMS fabrication are the same techniques that have become standard in the fabrication of submicron ICs. Furthermore, the materials used in many of the first generation, top-down NEMS devices (Si, GaAs, Si_3N_4, SiC) were first used in ICs and then in MEMS. Like the first MEMS devices, the first generation NEMS structures consist of freestanding nanomechanical beams, paddle oscillators, and tethered plates made using simple bulk and single layer surface "nano" machining processes. As an introduction to this new and exciting class of devices, the following section reviews the development of some of these first generation NEMS devices.

Like Si MEMS, Si NEMS capitalizes on well developed processing techniques for Si and the availability of high quality substrates. *Cleland* et al. [8.50] reported a relatively simple process to fabricate nanomechanical clamped-clamped beams directly from single crystal (100) Si substrates. As illustrated in Fig. 8.51, the process begins with the thermal oxidation of a Si substrate (Fig. 8.51a). Large Ni contact pads were then fabricated using optical lithography and lift-off. A polymethyl methacrylate (PMMA) lift-off mold was then deposited and patterned, using electron-beam lithography, into the shape of nanomechanical beams (Fig. 8.51b). Ni was then deposited and patterned by lifting off the PMMA (Fig. 8.51c). Next, the underlying oxide film was patterned by RIE using the Ni film as an etch mask. After oxide etching, nanomechanical beams were patterned by etching the Si substrate using RIE, as shown in Fig. 8.51d. Following Si RIE, the Ni etch mask was removed, and the sidewalls of the Si nanomechanical beams were lightly oxidized in order to protect them during the release step (Fig. 8.51e). After performing an anisotropic SiO_2 etch to clear any oxide from the field areas, the Si beams were released using an isotropic Si RIE step, as shown in Fig. 8.51f. After release, the protective SiO_2 film was removed by wet etching in HF (Fig. 8.51g). Using this process, the authors reported the successful fabrication of nanomechanical Si beams with micron-scale lengths ($\sim 8\,\mu m$) and submicron widths (330 nm) and heights (800 nm).



Fig. 8.51a–g Cross-sectional schematics of a process to fabricate nanomechanical beams directly from a silicon substrate: **(a)** after thermal oxidation; **(b)** after PMMA coating and electron beam lithography; **(c)** after Ni deposition and lift-off; **(d)** after anisotropic SiO_2 and Si etching; **(e)** after Ni etching, thermal oxidation, and anisotropic SiO_2 etching; **(f)** after release by isotropic Si etching; **(g)** after oxide removal

The advent of silicon-on-insulator (SOI) substrates with high quality, submicron-thick silicon top layers enables the fabrication of nanomechanical Si beams with fewer processing steps than the aforementioned technique, since the buried oxide layer makes these device structures relatively easy to pattern and release. Additionally, the buried SiO_2 layer electrically isolates the beams from the substrate. *Carr* et al. [8.51] detail a process that uses SOI substrates to fabricate submicron clamped-clamped mechanical beams and



Fig. 8.52a–e Cross-sectional schematics of a process to fabricate nanomechanical structures using silicon-on-insulator substrates: **(a)** starting SOI substrate; **(b)** after coating with PMMA and electron beam lithography; **(c)** after Al deposition and lift-off; **(d)** after anisotropic Si etching; **(e)** after release by SiO_2 etching

suspended plates with submicron tethers. The process, presented in Fig. 8.52, begins with the deposition of PMMA on an SOI substrate. The SOI substrate has a top Si layer that is either 50 nm or 200 nm in thickness. The PMMA is patterned into a metal lift-off mask by electron beam lithography (Fig. 8.52b). An aluminum film is then deposited and patterned by lift-off into a Si etch mask, as shown in Fig. 8.52c. The nanomechanical beams are then patterned by Si RIE and released by etching the underlying SiO_2 in a buffered hydrofluoric acid solution, as shown in Fig. 8.52d and Fig. 8.52e, respectively. Using this process, nanomechanical beams that were 7 to 16 µm in length, 120 to 200 nm in width, and 50 or 200 nm in thickness were successfully fabricated.

Fabrication of NEMS structures is not limited to Si. In fact, III-V compounds, such as gallium arsenide (GaAs), make particularly good NEMS materials from a fabrication perspective because thin epitaxial GaAs films can be grown on lattice-matched materials that can be used as sacrificial release layers. A collection of clamped-clamped nanomechanical GaAs beams fabricated on lattice-matched sacrificial layers having micron-scale lengths and submicron widths and thicknesses is shown in Fig. 8.53. *Tighe* et al. [8.52] reported on the fabrication of GaAs plates suspended with nanomechanical tethers. The structures were made from single crystal GaAs films that were epitaxially grown on aluminum arsenide (AlAs) sacrificial layers. Ni etch masks were fabricated using electron beam lithography and lift-off, as described previously. The GaAs films were patterned into beams using a chemically assisted ion beam etching process and released using a highly selective AlAs etchant. In a second example, *Tang* et al. [8.53] capitalized on the ability to grow high quality GaAs layers on ternary compounds, such as $Al_xGa_{1-x}As$, to fabricate complex GaAs-based structures, such as submicron clamped-clamped beams from GaAs/AlGaAs quantum well heterostructures. As with the process described by *Tighe* et al. [8.52], this process exploits a lattice matched sacrificial layer, in this case $Al_{0.8}Ga_{0.2}As$, which can be selectively etched to release the heterostructure layers.

Several unique approaches have been developed to actuate and sense the motion of NEMS devices. Electrostatic actuation can be used to actuate beams [8.54], tethered meshes [8.55], and paddle oscillators [8.56]. *Sekaric* et al. [8.57] have recently shown that low power lasers can be used to drive paddle oscillators into self-oscillation by induced thermal effects on the structures.



Fig. 8.53 SEM micrograph of a set of nanomechanical GaAs clamped-clamped beam resonators (courtesy of M. Roukes, Caltech)

In these examples, an optical detection scheme based on the modulation of incident laser light by a vibrating beam is used to detect the motion of the beams. *Cleland* et al. [8.50] describe a magnetomotive transduction technique that capitalizes on a time-varying Lorentz force created by an alternating current in the presence of a strong magnetic field. In this case, the nanomechanical beam is positioned in the magnetic field so that an AC current passing through the beam is transverse to the field lines. The resulting Lorentz force causes the beam to oscillate, which creates an electromotive force along the beam that can be detected as a voltage. Thus, in this method, the excitation and detection are performed electrically. In all of the above-mentioned cases, the measurements were performed in vacuum, presumably to minimize the effects of squeeze-film damping, as well as mass loading due to adsorbates from the environment.

For the most part, NEMS technology is still in the initial stage of development. Technological challenges related to fabrication and packaging will require innovative solutions before such devices make a significant commercial impact. Nevertheless, NEMS devices have already been used for precision measurements [8.58], enabling researchers to probe the properties of matter [8.59, 60] on a nanoscopic level. Whether or not NEMS makes an impact in the commercial sector, they will undoubtedly prove to be useful platforms for a host of experiments and scientific discoveries in fields ranging from physics to biology.

8.3 Current Challenges and Future Trends

Although the field of MEMS has experienced significant growth over the past decade, many challenges still remain. In broad terms, these challenges can be grouped into three general categories: (1) fabrication, (2) packaging, and (3) application. Challenges in these areas will, in large measure, determine the commercial success of a particular MEMS device, both in technical and economic terms. The following presents a brief discussion of some of these challenges, as well as possible approaches to address them.

In terms of fabrication, MEMS is currently dominated by planar processing techniques, which find their roots in silicon IC fabrication. The planar approach and the strong dependence on silicon worked well in the early years, since many of the processing tools and methodologies that are commonplace in IC fabrication could be directly utilized in the fabrication of MEMS devices. This approach lends itself to the integration of MEMS with silicon ICs. Therefore, it is still popular for various applications. However, modular process integration of micromachining with standard IC fabrication is not straightforward and represents a great challenge in terms of processing material compatibility, thermal budget requirements, etc. Furthermore, planar processing places significant geometric restrictions on device designs, especially for complex mechanical components requiring high-aspect ratio three-dimensional geometries, which are certain to increase as the application areas for MEMS continue to grow. Along the same lines, new applications will likely demand materials other than silicon that may not be compatible with the conventional microfabrication approach, posing a significant challenge if integration with silicon microelectronics is required. Micro-assembly technique can become an attractive solution to alleviate these issues. Multifunctional microsystems can be implemented by assembling various MEMS devices and electronic building blocks fabricated through disparate processing technologies. Microsystem on a common substrate will likely become the ultimate solution. Development of sophisticated modeling programs for device design and performance will become increasingly important as fabrication processes and device designs become more complex. In terms of NEMS, the most significant challenge is likely the integration of nano- and microfabrication techniques into a unified process, since NEMS devices are likely to consist of both nanoscale and microscale structures. Integration will be particularly challenging for nanoscale devices fabricated using a bottom-up approach, since no analog is found in microfabrication. Nevertheless, hybrid systems consisting of nanoscale and microscale components will become increasingly common as the field continues to expand.

Fabrication issues notwithstanding, packaging is and will continue to be a significant challenge to the implementation of MEMS. MEMS is unlike IC packaging, which benefits from a high degree of standardization. MEMS devices inherently require interaction with the environment, and since each application has in some way a unique environment, standardization of packaging becomes extremely difficult. This lack of standardization tends to drive up the costs associated with packaging, making MEMS less competitive with alternative approaches. In addition, packaging tends to negate the effects of miniaturization based upon microfabrication, especially for MEMS devices requiring protection from certain environmental conditions. Moreover, packaging can cause performance degradation of MEMS devices, especially in situations where the environment exerts mechanical stresses on the package, which, in turn, results in a long-term device performance drift. To address many of these issues, wafer-level packaging schemes that are customized to the device of interest will likely become more common. In essence, packaging of MEMS will move away from the conventional IC methods, which utilize independently manufactured packages, toward custom packages, which are created specifically for the device as part of the batch fabrication process.

Without question, the advancement of MEMS will open many new potential application areas to the technology. In most cases, MEMS will be one of several alternatives available for implementation. For cost-sensitive applications, the trade off between technical capabilities and cost will challenge those who desire to commercialize the technology. The biggest challenge to the field will be to identify application areas that are well suited for MEMS/NEMS technology and have no serious challengers. As MEMS technology moves away from the component level and towards microsystems solutions, it is likely that such application areas will come to the fore.

References

8.1 M. Mehregany, S. F. Bart, L. S. Tavrow, J. H. Lang, S. D. Senturia: Principles in design and microfabrication of variable-capacitance side-drive motors, J. Vac. Sci. Tech. A **8** (1990) 3614–3624

8.2 Y.-C. Tai, R. S. Muller: IC-processed electrostatic synchronous micromotors, Sens. Actuators **20** (1989) 49–55

8.3 M. S. Rodgers, J. J. Sniegowski: 5-level polysilicon surface micromachine technology: Application to complex mechanical systems, Technical Digest, Solid-State Sens. Actuator Workshop, Hilton Head Island 1998 (Transducers Research Foundation, Cleveland 1998) 144–149

8.4 G. T. A. Kovacs: *Micromachined Transducer Sourcebook* (McGraw-Hill, Boston 1998)

8.5 S. D. Senturia: *Microsystem Design* (Kluwer, Dordrecht 1998)

8.6 J. E. Gragg, W.E. McCulley, W. B. Newton, C. E. Derrington: Compensation and calibration of a monolithic four terminal silicon pressure transducer, Technical Digest, IEEE Solid-State Sens. Actuators Workshop, Hilton Head Island 1984 (IEEE, Piscataway 1984) 21–27

8.7 Y. Wang, M. Esashi: A novel electrostatic servo capacitive vacuum sensor, Technical Digest, IEEE Int. Conf. Solid-State Sens. Actuators, Chicago 1997 (Transducers Conference, Chicago 1997) 1457–1460

8.8 W. H. Ko, Q. Wang: Touch mode capacitive pressure sensors, Sens. Actuators **75** (1999) 242–251

8.9 J. M. Bustillo, R. T. Howe, R. S. Muller: Surface micromachining for microelectromechanical systems, Proc. IEEE **86** (1998) 1552–1574

8.10 J. H. Smith, S. Montague, J. J. Sniegowski, J. R. Murray, P. J. McWhorter: Embedded micromechanical devices for the monolithic integration of MEMS with CMOS, Technical Digest, IEEE Int. Electron Devices Meeting, Washington D.C. 1993 (IEEE, Piscataway 1993) 609–612

8.11 T. A. Core, W. K. Tsang, S. J. Sherman: Fabrication technology for an integrated surface-micromachined sensor, Solid State Technol. **36**(10) (1993) 39–40, 42, 44, 46–47

8.12 H. Kapels, R. Aigner, C. Kolle: Monolithic surface-micromachined sensor system for high pressure applications, Technical Digest, Int. Conf. Solid-State Sens. Actuators, Munich 2001 (Transducers Conference, Chicago 2001) 56–59

8.13 C. Lu, M. Lemkin, B. E. Boser: A monolithic surface micromachined accelerometer with digital output, Technical Digest, IEEE Int.Solid-State Circuits Conferernce, San Francisco 1995 (IEEE, Piscataway 1995) 160–161

8.14 T. B. Gabrielson: Mechanical-thermal noise in micromachined acoustic and vibration sensors, IEEE Trans. Electron Devices **40** (1993) 903–909

8.15 N. Yazdi, K. Najafi: An all-silicon single-wafer fabrication technology for precision microaccelerometers, Technical Digest, IEEE Int. Conf. Solid-State Sens. Actuators, Chicago 1997 (Transducers Conference, Chicago 1997) 1181–1184

8.16 M. Lemkin, M. A. Ortiz, N. Wongkomet, B. E. Boser, J. H. Smith: A 3-axis surface micromachined $\Sigma\Delta$ accelerometer, Technical Digest, IEEE Int. Solid-State Circuits Conference, San Francisco 1997 (IEEE, Piscataway 1997) 202–203

8.17 W. A. Clark, R. T. Howe: Surface micromachined *Z*-axis vibratory rate gyroscope, Technical Digest, IEEE Solid-State Sens. Actuators Workshop, Hilton Head Island 1996 (Transducers Research Foundation, Inc., Cleveland 1996) 283–287

8.18 T. Juneau, A. P. Pisano: Micromachined dual input axis angular rate sensor, Technical Digest, IEEE Solid-State Sens. Actuators Workshop, Hilton Head Island 1996 (Transducers Research Foundation, Inc., Cleveland 1996) 299–302

8.19 R. S. Muller, K. Y. Lau: Surface-micromachined microoptical elements and systems, Proc. IEEE **86** (1998) 1705–1720

8.20 L. J. Hornbeck: Current status of the digital micromirror device (DMD) for projection television applications, Technical Digest, IEEE Int. Electron Devices Meeting, Washington D.C. 1993 (IEEE, Piscataway 1993) 381–384

8.21 P. F. Van Kessel, L. J. Hornbeck, R. E. Meier, M. R. Douglass: A MEMS-based projection display, Proc. IEEE **86** (1998) 1687–1704

8.22 M. S. Cohen, M. F. Cina, E. Bassous, M. M. Opyrsko, J. L. Speidell, F. J. Canora, M. J. DeFranza: Packaging of high density fiber/laser modules using passive alignment techniques, IEEE Trans. Comp., Hybrids, Manufact. Technol. **15** (1992) 944–954

8.23 M. J. Wale, C. Edge: Self-aligned flip-chip assembly of photonic devices with electrical and optical connections, IEEE Trans. Comp., Hybrids, Manufact. Technol. **13** (1990) 780–786

8.24 M. J. Daneman, N. C. Tien, O. Solgaard, K. Y. Lau, R. S. Muller: Linear vibromotor-actuated micromachined microreflector for integrated optical systems, Technical Digest, IEEE Solid-State Sens. Actuators Workshop, Hilton Head Island 1996 (Transducers Research Foundation, Inc., Cleveland 1996) 109–112

8.25 K. S. J. Pister, M. W. Judy, S. R. Burgett, R. S. Fearing: Microfabricated hinges, Sens. Actuators A **33** (1992) 249–256

8.26 O. Solgaard, M. Daneman, N. C. Tien, A. Friedberger, R. S. Muller, K. Y. Lau: Optoelectronic packaging using silicon surface-micromachined alignment mirrors, IEEE Photon. Technol. Lett. **7** (1995) 41–43

8.27 S. S. Lee, L. S. Huang, C. J. Kim, M. C. Wu: 2 × 2 MEMS fiber optic switches with silicon sub-mount for low-cost packaging, Technical Digest, IEEE Solid-State Sens. Actuators Workshop, Hilton Head Island 1998 (Transducers Research Foundation, Inc., Cleveland 1998) 281–284

8.28 T. Akiyama, H. Fujita: A quantitative analysis of scratch drive actuator using buckling motion, Technical Digest, 8th IEEE Int. MEMS Workshop, Amsterdam 1995 (IEEE, Piscataway 1995) 310–315

8.29 V. A. Aksyuk, M. E. Simon, F. Pardo, S. Arney: Optical MEMS design for telecommunications applications, Technical Digest, Solid-State Sensors and Actuators Workshop, Hilton Head Island 2002 (Transducers Research Foundation, Cleveland 2002) 1–6

8.30 D. J. Young, B. E. Boser: A micromachined variable capacitor for monolithic low-noise VCOs, Technical Digest, Solid-State Sens. Actuator Workshop, Hilton Head Island 1996 (Transducers Research Foundation, Cleveland 1996) 86–89

8.31 A. Dec, K. Suyama: Micromachined electromechanically tunable capacitors and their applications to RF IC's, IEEE Trans. Microwave Theory Techniques **46** (1998) 2587–2596

8.32 Z. Li, N. C. Tien: A high tuning-ratio silicon-micromachined variable capacitor with low driving voltage, Technical Digest, Solid-State Sens. Actuator Workshop, Hilton Head Island 2002 (Transducers Research Foundation, Inc., Cleveland 2002) 239–242

8.33 Z. Xiao, W. Peng, R. F. Wolffenbuttel, K. R. Farmer: Micromachined variable capacitor with wide tuning range, Technical Digest, Solid-State Sens. Actuator Workshop, Hilton Head Island, South Carolina 2002 (Transducers Research Foundation, Inc., Cleveland 2002) 346–349

8.34 J. J. Yao, S. T. Park, J. DeNatale: High tuning-ratio MEMS-based tunable capacitors for RF communications applications, Technical Digest, Solid-State Sens. Actuator Workshop, Hilton Head Island 1998 (Transducers Research Foundation, Inc., Cleveland 1998) 124–127

8.35 J. B. Yoon, C. T.-C. Nguyen: A high-Q tunable micromechanical capacitor with movable dielectric for RF applications, Technical Digest, IEEE Int. Electron Devices Meeting, San Francisco 2000 (IEEE, Piscataway 2000) 489–492

8.36 D. J. Young, V. Malba, J. J. Ou, A. F. Bernhardt, B. E. Boser: Monolithic high-performance three-dimensional coil inductors for wireless communication applications, Technical Digest, IEEE Int. Electron Devices Meeting, Washington D.C. 1997 (IEEE, Piscataway 1997) 67–70

8.37 D. J. Young, B. E. Boser, V. Malba, A. F. Bernhardt: A micromachined RF low phase noise voltage-controlled oscillator for wireless communication, Int. J. RF Microwave Computer-Aided Eng. **11** (2001) 285–300

8.38 J. B. Yoon, C. H. Han, E. Yoon, K. Lee, C. K. Kim: Monolithic High-Q Overhang Inductors Fabricated on Silicon and Glass Substrates, Technical Digest, IEEE Int. Electron Devices Meeting, Washington D.C. 1999 (IEEE, Piscataway 1999) 753–756

8.39 C. L. Chua, D. K. Fork, K. V. Schuylenbergh, J. P. Lu: Self-assembled out-of-plane high Q inductors, Technical Digest, Solid-State Sens. Actuator Workshop, Hilton Head Island 2002 (Transducers Research Foundation, Inc., Cleveland 2002) 372–373

8.40 C. L. Goldsmith, Z. Yao, S. Eshelman, D. Denniston: Performance of low-loss RF MEMS capacitive switches, IEEE Microwave Guided Wave Lett. **8** (1998) 269–271

8.41 J. J. Yao, M. F. Chang: A surface micromachined miniature switch for telecommunication applications with signal frequencies from DC up to 40 GHz, Technical Digest, 8th Int. Conf. Solid-State Sens. Actuators, Stockholm 1995 (Transducers Conference, Chicago 1995) 384–387

8.42 P. M. Zavracky, N. E. McGruer, R. H. Morrison, D. Potter: Microswitches and microrelays with a view toward microwave applications, Int. J. RF Microwave Computer-Aided Eng. **9** (1999) 338–347

8.43 D. Hyman, J. Lam, B. Warneke, A. Schmitz, T. Y. Hsu, J. Brown, J. Schaffner, A. Walston, R. Y. Loo, M. Mehregany, J. Lee: Surface-micromachined RF MEMs switches on GaAs substrates, Int. J. RF Microwave Computer-Aided Eng. **9** (1999) 348–361

8.44 C. T. C. Nguyen, R. T. Howe: CMOS microelectromechanical resonator oscillator, Technical Digest, IEEE Int. Electron Devices Meeting, Washington D.C. 1993 (IEEE, Piscataway 1993) 199–202

8.45 L. Lin, R. T. Howe, A. P. Pisano: Microelectromechanical filters for signal processing, IEEE J. Microelectromechan. Syst. **7** (1998) 286–294

8.46 F. D. Bannon III, J. R. Clark, C. T. C. Nguyen: High frequency micromechanical filter, IEEE J. Solid-State Circuits **35** (2000) 512–526

8.47 K. Wang, Y. Yu, A. C. Wong, C. T. C. Nguyen: VHF free-free beam high-Q micromechanical resonators, Technical Digest, 12th IEEE Int. Conf. Micro Electro Mechanical Systems, San Francisco 1999 (IEEE, Piscataway 1999) 453–458

8.48 J. R. Clark, W. T. Hsu, C. T. C. Nguyen: High-Q VHF micromechanical contour-mode disk resonators, Technical Digest, IEEE Int. Electron Devices Meeting, San Francisco 2000 (IEEE, Piscataway 2000) 493–496

8.49 C. T. C. Nguyen, R. T. Howe: Quality factor control for micromechanical resonator, Technical Digest, IEEE Int. Electron Devices Meeting, San Francisco 1992 (IEEE, Piscataway 1992) 505–508

8.50 A. N. Cleland, M. L. Roukes: Fabrication of high frequency nanometer scale mechanical resonators from bulk Si crystals, Appl. Phys. Lett. **69** (1996) 2653–2655

8.51 D. W. Carr, H. G. Craighead: Fabrication of nanoelectromechanical systems in single crystal silicon using silicon on insulator substrates and electron beam lithography, J. Vac. Sci. Technol. B **15** (1997) 2760–2763

8.52 T. S. Tighe, J. M. Worlock, M. L. Roukes: Direct thermal conductance measurements on suspended monocrystalline nanostructures, Appl. Phys. Lett. **70** (1997) 2687–2689

8.53 H. X. Tang, X. M. H. Huang, M. L. Roukes, M. Bichler, W. Wegsheider: Two-dimensional electron-gas actuation and transduction for GaAs nanoelectromechanical systems, Appl. Phys. Lett. **81** (2002) 3879–3881

8.54 D. W. Carr, S. Evoy, L. Sekaric, H. G. Craighead, J. M. Parpia: Measurement of mechanical resonance and losses in nanometer scale silicon wires, Appl. Phys. Lett. **75** (1999) 920–922

8.55 D. W. Carr, L. Sekaric, H. G. Craighead: Measurement of nanomechanical resonant structures in single-crystal silicon, J. Vac. Sci. Technol. B **16** (1998) 3821–3824

8.56 S. Evoy, D. W. Carr, L. Sekaric, A. Olkhovets, J. M. Parpia, H. G. Craighead: Nanofabrication and electrostatic operation of single-crystal silicon paddle oscillators, J. Appl. Phys. **86** (1999) 6072–6077

8.57 L. Sekaric, M. Zalalutdinov, S. W. Turner, A. T. Zehnder, J. M. Parpia, H. G. Craighead: Nanomechanical resonant structures as tunable passive modulators, Appl. Phys. Lett. **80** (2002) 3617–3619

8.58 A. N. Cleland, M. L. Roukes: A nanometre-scale mechanical electrometer, Nature **392** (1998) 160–162

8.59 K. Schwab, E. A. Henriksen, J. M. Worlock, M. L. Roukes: Measurement of the quantum of thermal conductance, Nature **404** (2000) 974–977

8.60 S. Evoy, A. Olkhovets, L. Sekaric, J. M. Parpia, H. G. Craighead, D. W. Carr: Temperature-dependent internal friction in silicon nanoelectromechanical systems, Appl. Phys. Lett. **77** (2000) 2397–2399

9. Microfluidics and Their Applications to Lab-on-a-Chip

Various microfluidic components and their characteristics, along with the demonstration of two recent achievements of lab-on-a-chip systems have been reviewed and discussed. Many microfluidic devices and components have been developed during the past few decades, as introduced earlier for various applications. The design and development of microfluidic devices still depend on the specific purposes of the devices (actuation or sensing) due to a wide variety of application areas, which encourages researchers to develop novel, purpose-specific microfluidic devices and systems. Microfluidics is the real multidisciplinary research field that requires basic knowledge in fluidics, micromachining, electromagnetics, materials, and chemistry for better applications.

Among the various application areas of microfluidics, one of the most important application areas is the lab-on-a-chip system. Lab-on-a-chip is becoming a revolutionary tool for many different applications in chemical and biological analyses due to its fascinating advantages (fast and low cost) over conventional chemical or biological laboratories. Furthermore, the simplicity of lab-on-a-chip systems will enable self-testing capability for patients or health consumers overcoming space limitation.

9.1 Materials for Microfluidic Devices and Micro/Nano Fabrication Techniques 254
9.1.1 Silicon 254
9.1.2 Glass 254
9.1.3 Polymer 255

9.2 Active Microfluidic Devices 257
9.2.1 Microvalves 258
9.2.2 Micropumps 260

9.3 Smart Passive Microfluidic Devices 262
9.3.1 Passive Microvalves 262
9.3.2 Passive Micromixers 265
9.3.3 Passive Microdispensers 266
9.3.4 Microfluidic Multiplexer Integrated with Passive Microdispenser 267
9.3.5 Passive Micropumps 269
9.3.6 Advantages and Disadvantages of the Passive Microfluidic Approach 269

9.4 Lab-on-a-Chip for Biochemical Analysis 270
9.4.1 Magnetic Micro/Nano Bead-Based Biochemical Detection System 270
9.4.2 Disposable Smart Lab-on-a-Chip for Blood Analysis 273

References 276

Microfluidics covers the science of fluidic behaviors on the micro/nanoscales and the engineering of design, simulation, and fabrication of the fluidic devices for the transport, delivery, and handling of fluids on the order of microliters or smaller volumes. It is the backbone of the BioMEMS (Biological or Biomedical Microelectromechanical Systems) and lab-on-a-chip concept, as most biological analyses involve fluid transport and reaction. Biological or chemical reactions on the micro/nanoscale are usually rapid since small amounts of samples and reagents are used, which offers a quick and low cost analysis.

A fluidic volume of 1 nanoliter (1 nl) can be understood as the volume in a cube surrounded by 100 μm in each direction. It is much smaller than the size of a grain of table salt! Microfluidic devices and systems handle sample fluids in this range for various applications, including inkjet printing, blood analysis, biochemical detection, chemical synthesis, drug screening/delivery, protein analysis, DNA sequencing, and so on.

Microfluidic systems consist of microfluidic platforms or devices for fluidic sampling, control, monitoring, transport, mixing, reaction, incubation, and analysis. To construct microfluidic systems, or lab-on-a-chips, microfluidic devices must be functionally integrated on a microfluidic platform using proper micro/nano fabrication techniques. In this chapter, the basics of microfluidicdevices and their applications to

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

lab-on-a-chip are briefly reviewed and summarized. Basic materials and fabrication techniques for microfluidic devices will be introducedfirst and various active and passive microfluidic components will be described. Then, their applications to lab-on-a-chip, or biochemical analysis, will be discussed.

9.1 Materials for Microfluidic Devices and Micro/Nano Fabrication Techniques

Various materials are being used for the fabrication of microfluidic devices and systems. Silicon is one of the most popular materials in micro/nano fabrication because its micromachining has been well established over decades. In general, the advantages to using silicon as a substrate or structural material include good mechanical properties, excellent chemical resistance, well characterized processing techniques, and the capability for integration of control/sensing circuitry as a semiconductor. Other materials such as glass, quartz, ceramics, metals, and polymers are also being used for substrates and structures in micro/nano fabrication, depending on the application. Among these materials, polymers or plastics have recently become one of the more promising materials for lab-on-a-chip applications, due to their excellent material properties for biochemical fluids and their low cost manufacturability. Main issues in the fabrication techniques of microfluidic devices and systems usually lie in forming microfluidic channels, key micro/nano structures of lab-on-a-chip. In this section, the basic micro/nano fabrication techniques for silicon, glass, and polymers are described.

9.1.1 Silicon

Microfluidic channels on silicon substrates are usually formed either by wet (chemical) etching or by dry (plasma) etching. Crystalline silicon has a preferential etch direction, depending on which crystalline plane is exposed to an etchant. Etch rate is slowest in ⟨111⟩ crystalline direction – approximately 100:1 etch rate anisotropy compared with ⟨100⟩:⟨111⟩ or ⟨110⟩:⟨111⟩. Potassium hydroxide (KOH), tetra-methyl ammonium hydroxide (TMAH), and ethylene diamine pyrocatechol (EDP) are commonly used silicon anisotropic etchants. In most cases, silicon dioxide (SiO_2) or silicon nitride (Si_3N_4) is used as a masking material during the etching process. Anisotropic etchants and basic etching mechanisms are summarized by *Ristic* et al. [9.1]. There is also an isotropic wet etching process available using a mixture of fluoric acid (HF), nitric acid (HNO_3), and acetic acid (CH_3COOH), so-called “HNA”. HNA etches in all directions with almost the same etch rate regardless of crystalline directions. Figure 9.1 illustrates wet anisotropic and isotropic etching profiles.



Fig. 9.1a–c Wet etching of silicon substrate for anisotropic and isotropic etching: **(a)** isotropic etching profile, **(b)** anisotropic etching profile (long term), and **(c)** anisotropic etching profile (short term)

Reactive ion etching (RIE) is also one of the most commonly used dry etching processes to generate microfluidic channels or deep trench structures on silicon substrate. In this dry etching technique, radio frequency (RF) energy is used to excite ions in a gas to an energetic state. The energized ions supply the necessary energy to generate physical and chemical reactions on the exposed area of the substrate, which starts the etching process. RIE can generate strong anisotropic, as well as isotropic profiles, depending on the gases used, the condition of plasma, and the applied power. Further information on reactive ion etching process, including deep reactive ion etching (DRIE), on silicon substrate can be found in the literature [9.2–5].

Many microfluidic devices were realized using silicon as a substrate material, including microvalves and micropumps, which are covered in the next section.

9.1.2 Glass

Glass substrate has been widely used for the fabrication of microfluidic systems and lab-on-a-chip due to its excellent optical transparency and ease of electro-osmotic flow (EOF). Chemical wet etching and thermal fusion bonding are the common fabrication techniques for glass substrate. Chemical wet etching and the bonding technique have also been widely reported [9.6, 7]. Most commonly used etchants are hydrofluoric acid (HF), buffered hydrofluoric acid, and a mixture of hydrofluoric acid, nitric acid, and deionized water (HF, HNO_3, H_2O). Gold with an adhesion layer of chrome is most often used as etch mask for wet etching of glass substrate. Since glass has no crystalline structure, only isotropic etch profiles are obtained as forming a hemispherical-shaped channel. Often the problem is that stresses within the surface layers of the glass cause preferential etching, and scratches created by polishing or handling errors cause spikes etched in the channels. Pre-etching is one method to release stress, which causes defects in channels after etching. Another way to improve the channel etching process is to anneal the glass wafers before etching. Annealing can be done nearly at glass transition temperature for at least a couple of hours. Figure 9.2 shows two examples of poorly etched channels without the pre-etching and annealing steps compared with an etched channel without defects. Other fabrication techniques for glass substrate include photoimageable glass, as *Dietrich* et al. [9.8] reported. Anisotropy is introduced in glass by making the glass photosensitive using lithium/aluminium/silicates composition.

One of the most successful examples of using glass as a substrate material in lab-on-a-chip applications is the capillary electrophoresis (CE) chip, fabricated using the glass etching and fusion bonding technique, since the most advantageous property of glass is an excellent optical transparency that is required for the most lab-on-a-chip using optical detection including capillary electrophoresis microchips [9.6, 7, 9].

9.1.3 Polymer

Among several substrates available for lab-on-a-chip, polymers, or plastics, have recently become one of the most popular and promising substrates due to their low cost, ease-of-fabrication, and favorable biochemical reliability and compatibility. Plastic substrates, such as polyimide, PMMA, PDMS, polyethylene or polycarbonate, offer a wide range of physical and chemical material parameters for the applications of lab-on-a-chip, generally at low cost using replication approaches. Polymers and plastics are promising materials in microfluidic and lab-on-a-chip applications because they can be used for mass production using casting, hot embossing, and injection molding techniques. This mass production capability allows the successful commercialization of lab-on-a-chip technology, including disposable lab-on-a-chip. While several fabrication methods have recently been developed, three fabrication techniques – casting, hot embossing, and injection molding – are major techniques of great interest. Figure 9.3 shows schematic illustrations of these polymer microfabrication techniques.

For polymer or plastic micro/nano fabrication, a mold master is essential for replication. Mold masters are fabricated using photolithography, silicon/glass bulk etching, and metal electroplating, depending on the application. Figure 9.4 summarizes mold masters from different fabrication techniques.

Photolithography, including UV-LIGA [9.10, 11] and LIGA [9.12], is used to fabricate mold masters for casting or soft lithography replication, while silicon-based and electroplated mold masters are used for hot embossing replication. For injection molding, electroplated metallic mold masters are preferable.



Fig. 9.2a–c Isotropically etched microfluidic channels on glass substrate: **(a)** poorly etched channel with large under etching, **(b)** poorly etched channel with spikes, and **(c)** well etched channel without any defects


a)
Solvent pouring step
Solvent curing
Cured polymer
Final polymer part
b)
Pressure
Mold
Plastic
Heat
Pressure
Heat
Final plastic part
c)
Molding block
Mold cavity
Molten polymer
Completely filled cavity
Ejected plastic part

Fig. 9.3a–c Concept of polymer micro/nano fabrication techniques: **(a)** casting, **(b)** hot embossing, and **(c)** injection molding


a)
b)
Spin coat photoresist
c)
Exposure
Develop photoresist
Electroplate
Reactive ion etching
Strip photoresist

Fig. 9.4a–c Mold masters in polymer/plastic fabrication: **(a)** photolithography-based mold master, **(b)** silicon-based mold master, and **(c)** mold master by electroplating

Casting or soft lithography [9.13, 14] usually offers flexible access to microfluidic structures using mostly poly(dimethylsiloxane) (PDMS) as a casting material. A mixture of the elastomer precursor and curing agent is poured over a master mold structure. After curing, the replicated elastomer is released from the mold master, having transferred a reverse structure of the mold master. Patterns of a few nm can be achieved using this technique.

While casting can be carried out in room temperature, hot embossing requires a slightly higher temperature – up to glass transition temperature of the plastic substrate to be replicated. The hot embossing technique has been developed by several research groups [9.15–17]. A mold master is placed in the chamber

Table 9.1 Overview of the different polymer micro/nano fabrication techniques

Fabrication type	Casting	Hot embossing	Injection molding
Investment	Low	Moderate	High
Manufacturability	Low	Moderate	High
Cycle time	8–10 hrs	1 hr	1 min
Polymer choices	Low	Moderate	Moderate
Mold replication	Good	Good	Good
Reusability of mold	No (photolithography-based molds)	Yes	Yes

of a hot embossing system with the plastic substrate, then heated plates press both the plastic substrate and the mold master, as illustrated in Fig. 9.3b. After a certain amount of time (typically 5–20 minutes, depending on the plastic substrate), the plates are cooled down to release the replicated plastic substrate. Hot embossing offers mass production of polymer microstructures, as its cycle time is less than an hour.

Injection molding is a technique to fabricate polymer microstructures at low cost and high volumes [9.18]. A micromachined mold master is placed in the molding block of the injection molding machine, as illustrated in Fig. 9.3c. The plastic in granular form is melted and then injected into the cavity of a closed mold block, where the mold master is located. The molten plastic continues to flow into and fill the mold cavity until the plastic cools down to a highly viscous melt, and a cooled plastic part is ejected. In order to ensure good flow properties during the injection molding process, thermoplastics with low or medium viscosity are desirable. So the filling of the mold cavity, and, subsequently, the microstructures depend on the viscosity of the plastic melt, injection speed, molding block temperature, and nozzle temperature of the injection unit. This technique allows very rapid replication and high volume mass production. Typical cycle time is several seconds for most applications. However, due to high shear force on the mold master inside of the mold cavity during injection molding, metallic mold masters are highly recommended. Polymethylmethacrylate (PMMA), polyethylene (PE), polystyrene (PS), polycarbonate (PC), and cyclic olefin copolymers (COC) are common polymer/plastic materials for both hot embossing and injection mold replication.

All of these polymer/plastic replication techniques are summarized in Table 9.1. Since each technique differs from the others, fabrication techniques and materials have to be selected according to the application.

9.2 Active Microfluidic Devices

Microfluidics devices are essential for the development of lab-on-a-chip or µTAS (Micro-Total Analysis Systems). A number of different microfluidic devices have been developed with basic structures analogous to the macroscale fluidic devices. Such devices include microfluidic valves, microfluidic pumps, microfluidic mixers, etc. The devices listed above have been developed both as active and passive devices. While passive microfluidic devices are generally easy to fabricate, they do not offer the same functional diversity that the active microfluidic devices provide. For example, passive microvalves based on surface tension effect [9.19] can operate a few times to hold the liquid, which is acceptable for a disposable format. Once the air-liquid interface passes over the valve mechanism, the operation characteristics of the valve will differ, due to the change of surface energy over the channel. Similarly, passive check valves [9.20–22] are dependent on the pressure of the fluid for operation. Since the active microvalves can be triggered on/off depending on an external signal regardless of the fluid system status, there have been considerable research efforts to develop active microfluidic devices. However, the active devices usually require its expense as desired functional and fabrication complexity.

This section reviews some of the active microfluidic devices, such as microvalves, micropumps, and active microfluidic mixers. Passive counterparts of these microfluidic devices will be discussed in the next section.

9.2.1 Microvalves

Active microvalves have been an area of intense research over the past decade, and a number of novel design and actuation schemes have been developed. This makes the categorization of active microvalves a confusing enterprise. Classification schemes for active microvalves include:

1. Fluidics handled – liquid/gas/liquid and gas
2. Materials used for the structure – silicon/polysilicon/glass/polymer
3. Actuation mechanisms – electrostatic/pneumatic/thermopneumatic, etc.
4. Physical actuating microstructures – membrane type, flap type, ball valve, etc.

All of the classification schemes listed above are valid, but the most commonly used method [9.23, 24] is the classification based on the actuation mechanisms.

In this section, the various microvalves are discussed in terms of their actuation mechanisms and their relevance to the valve mechanism, as well as fluid handled and special design criteria.

Pneumatically/Thermopneumatically Actuated Microvalves

Pneumatic actuation uses an external air line (or pneumatic source) to actuate a flexible diaphragm. Pneumatic actuation offers such attractive features as high force, high displacement, and rapid response time. Figure 9.5 illustrates a schematic concept of pneumatically actuated microvalves. *Schomburg* et al. [9.25] demonstrated pneumatically actuated microvalves.

Pneumatically actuated microvalves have also been demonstrated using polymeric substrate. *Hosokawa* et al. [9.26] demonstrated a pneumatically actuated three-way microvalve system using a PDMS platform. The microfluidic lines and the pneumatic lines are fabricated on separate layers.

Thermopneumatic actuation is typically performed by heating a fluid (usually gas) in a confined cavity, as illustrated in Fig. 9.6. The increase in temperature leads to a rise in pressure of the gas, and this pressure is used for deflecting a membrane for valve operation. Thermopneumatic actuation is an inherently slow technique but offers very high forces when compared to other techniques [9.23]. Thermopneumatically actuated microvalves have been realized by many researchers using various substrates and diaphragm materials [9.27–29].



Fig. 9.5 Schematic concept of pneumatically actuated microvalve



Fig. 9.6 Schematic concept of thermopneumatically actuated microvalve

Electrostatically Actuated Microvalves

Electrostatic actuation has been widely explored for a number of applications, including pressure sensors, comb drives, active mirror arrays, etc. Electrostatically actuated devices typically have a fairly simple structure and are easy to fabricate. A number of fabrication issues, such as stiction and release problems of membranes and valve flaps, need to be addressed for realizing practical electrostatic microvalves. *Sato* et al. [9.30] have developed a novel membrane design in which the deflection "propagates" through the membrane, rather than deforming it entirely. Figure 9.7 shows a schematic sketch of the actuation mechanism and valve design. The use of this "S-shaped" design allows them to have relatively large gaps across the two surfaces, as the electrostatic force must only be concentrated at the edges of the S-shape where the membrane is deflected. *Robertson* et al.



Fig. 9.7a,b Electrostatically actuated microvalve with S-Shaped film element: propagation of bend in the film as **(a)** open and **(b)** closed (adapted from [9.30]). Reproduced by permission of IOP Publishing Limited

[9.31] have developed an array of electrostatically actuated valves using a flap design (rather than a membrane) for sealing fluid flow. The demonstrated system is suitable for very low pressure gas control systems such as the ones needed in a clean room environment.

Wijngaart et al. [9.33] have developed a high-stroke, high pressure electrostatic actuator for valve applications. This reference provides a good overview of the theoretical design parameters used to design and analyze an electrostatically actuated microvalve.

Piezoelectrically Actuated Microvalve

Piezoelectric actuation schemes offer a significant advantage in terms of operating speed; they are typically the fastest actuation scheme at the expense of a reduced actuator stroke. Also, piezoelectric materials are more challenging to incorporate into fully integrated MEMS devices. *Watanabe* et al. [9.34] and *Stehr* et al. [9.35] demonstrated piezoelectric actuators for valve applications. A film of piezoelectric material is deposited on the movable membrane, and upon application of an electric potential, a small deformation occurs in the piezo film that is transmitted to the valve membrane.

Electromagnetically Actuated Microvalves

Electromagnetic actuators are typically capable of delivering high force and range of motion. A significant advantage of electromagnetic microvalves is that they are relatively insensitive to external interference. However, electromagnetic actuators involve a fairly complex fabrication process. Usually, a soft electromagnetic material like Ni-Fe (nickel-iron permalloy) is used as a membrane layer, and an external electromagnet is used to actuate this layer. *Sadler* et al. [9.32] have developed a microvalve using the electromagnetic actuation scheme shown in Fig. 9.8.

They have demonstrated a fully integrated magnetic actuator with magnetic interconnection vias to guide the magnetic flux. The valve seat design, also shown in Fig. 9.8, allows for very intimate contact between the Ni-Fe valve membrane and the valve seat, hence, achieving an ultralow leak rate when the valve is closed.

Jackson et al. [9.36] demonstrate an electromagnetic microvalve using "magnetic" PDMS as the membrane material. For this application, the PDMS pre-polymer is loaded with soft magnetic particles and then cured to form the valve membrane. The PDMS membrane



Fig. 9.8a,b Electromagnetically actuated microvalves: **(a)** schematic illustration and **(b)** photograph of the electromagnetically actuated microvalve as a part of lab-on-a-chip (after [9.32])

is then assembled over the valve body, and miniature electromagnets are used to actuate the membrane.

Other Microvalve Actuation Schemes

Microvalves have most commonly been implemented with one of the actuation schemes listed above. However, these are not the only actuation schemes that are used for microvalves. Some others include the use of SMA (shape memory alloys) [9.37], electrochemical actuation [9.38], etc. SMA actuation schemes offer the advantage of generating very large forces when the SMA material is heated to its original state. *Neagu* et al. [9.38] present an electrochemically actuated microvalve. In their device, an electrolysis reaction is used to generate oxygen in a confined chamber. This chamber is sealed by a deformable membrane that deflects due to increased pressure. The reported microvalve has relatively fast actuation time and can generate very high pressures. *Yoshida* et al. [9.39] present a novel approach to the microvalve design: a micro-electro-rheological valve (ER valve). An electro-rheological fluid is loaded into the microchannel, and, depending on the strength of an applied electric field, the viscosity of the ER fluid changes considerably. A higher viscosity is achieved when an electric field is applied perpendicular to the flow direction. This increased viscosity leads to a drop in the flow rate, allowing the ER fluid to act as a valve. Of course, this technique is limited to fluids that can exhibit such properties; nevertheless, it provides a novel idea to generate on-chip microvalves.

The ideal characteristics for a microvalve are listed by Kovacs [9.24]. However, of all the microvalves listed above, none can satisfy all the criteria. Thus, microvalve design, fabrication, and utility are highly application-specific and most microvalves try to generate the performance characteristics that are most useful for the intended application.

9.2.2 Micropumps

One of the most challenging tasks in developing a fully integrated microfluidic system has been the development of efficient and reliable micropumps. In macroscale, a number of pumping techniques exist such as peristaltic pumps, vacuum-driven pumps, venturi-effect pumps, etc. However, in microscale, most mechanical pumps rely on pressurizing the working fluid and forcing it to flow through the system. Practical vacuum pumps are not available in microscale. There are also some effects such as electro-osmotic pumping, that are only possible on the microscale. Consequently, electrokinetic driving mechanisms have also been widely studied for microfluidic pumping applications.

In the previous section, various microvalves that are used for microfluidic control were discussed. They were presented based on the actuation schemes that they employ. A similar classification can also be adopted for micropumps. However, rather than using the same classification scheme, the micropumps are categorized based on the type of microvalve mechanism used as part of the pumping mechanism. Broadly, the mechanical micropumps can be classified as check-valve controlled microvalves or diffuser pumps. Either mechanism can use various actuation schemes such as electrostatic, electromagnetic, piezoelectric, etc. Micropumps driven by direct electrical control form separate category and are discussed following the mechanical micropumps.

Micropumps Using Check Valve Design

Figure 9.9 shows a typical mechanical micropump with check valves. This pump consists of an inlet and an outlet check valve with a pumping chamber in between. A membrane is deflected upwards, and a low pressure zone is created in the pumping chamber. This forces the inlet check valve open, and fluid is sucked into the pumping chamber. As the membrane returns to its original state and continues to travel downwards, a positive pressure builds up, which seals the inlet valve while simultaneously opening the outlet valve. The fluid is then ejected and the pump is ready for another cycle.

A number of other techniques have been used to realize mechanical micropumps with check valves and a pumping chamber. *Jeon* et al. [9.40] present a micropump that uses PDMS flap valves to control the pumping mechanism, *Koch* et al. [9.41], *Cao* et al. [9.42], *Park* et al. [9.43], and *Koch* et al. [9.44] present piezoelectrically driven micropumps. *Xu* et al. [9.45] and *Makino*



Fig. 9.9a,b Operation of micropump using check valve design: **(a)** check valves are closed and **(b)** check valves are open

et al. [9.46] present SMA driven micropumps. *Chou* et al. [9.47] present a novel rotary pump using a soft lithography approach. As explained in the active valve section, valves can be created on a PDMS layer using separate liquid and air layers. When a pressure is applied to the air lines, the membranes deflect to seal the fluidic path. *Chou* et al. [9.47] have implemented a series of such valves in a loop. When they are deflected in a set sequence, the liquid within the ring is pumped by peristaltic motion.

An interesting approach toward the development of a bidirectional micropump has been used by *Zengerle* et al. [9.48]. Their design has two flap valves at the inlet and outlet of the micropump, which work in the forward mode at low actuation frequencies and in the reverse direction at higher frequencies. *Zengerle* et al. [9.48] attribute the change in pumping direction to the phase shift between the response of the valves and the pressure difference that drives the fluid. *Carrozza* et al. [9.49] use a different approach to generate the check valves. Rather than using the conventional membrane or flap type valves, they use ball valves by employing a stereolithographic approach. The developed pump is actuated using a piezoelectric actuation scheme.

Diffuser Micropumps

The use of nozzle-diffuser sections, or pumps with fixed valves, or pumps with dynamic valves has been extensively researched. The basic principle of these pumps is based on the idea that the geometrical structure used as an inlet valve has a preferential flow direction toward the pumping chamber, and the outlet valve structure has a preferential flow direction away from the pumping chamber. An illustrative example of this concept is shown in Fig. 9.10. As can be readily seen, these pumps are designed to work with liquids only. When the pump is in suction mode, the flow in the inlet diffuser structure is primarily directed toward the pump, and a slight backflow occurs from the outlet diffuser (acting as a nozzle) section. When the pump is in pressure mode, the outlet diffuser section allows most of the flow out of the pump, whereas the inlet diffuser section allows a slight backflow. The net effect is that liquid pumping occurs from left to right.

Diffuser micropumps are simple and valveless structures that improve pumping reliability [9.50], but they cannot eliminate backflow problems.

These micropumps can also be described as flow rectifiers, analogous to diodes in electrical systems. *Forster* et al. [9.51] have used the Tesla valve geometry, instead of the diffuser section, and the reference presents a detailed discussion of the design parameters and operational characteristics of their fixed-valve micropumps.



Fig. 9.10a,b Operating principle of a diffuser micropump: **(a)** suction mode and **(b)** pumping mode

Electric/Magnetic Field Driven Micropumps

An electric field can be used to directly pump liquids in microchannels using such techniques as electro-omosis (EO), electrohydrodynamic (EHD) pumping, magnetohydrodynamic (MHD) pumping, etc. These pumping techniques rely on creating an attractive force for some of the ions in the liquid, and the remaining liquid is dragged along to form a bulk flow.

When a liquid is introduced into a microchannel, a double-layer charge exists at the interface of the liquid and the microchannel wall. The magnitude of this charge is governed by the zeta potential of the channel-liquid pair. Figure 9.11 shows a schematic view of the electro-osmotic transport phenomenon.

As shown in Fig. 9.11, the channel wall is negatively charged, which attracts the positive ions in solution. When a strong electric field is applied along the length of the microchannel, the ions at the interface experience an attractive force toward the cathode. As the positive ions move toward the cathode, they exert a drag force on the bulk fluid, and net fluid transport occurs from the anode to the cathode. It is interesting to note that the flow profile of the liquid plug is significantly different from the pressure-driven flow. Unlike the parabolic flow profile of pressure-driven flow, electro-osmotic transport leads to an almost vertical flow profile. The electro-osmotic transport phenomenon is only effective across very narrow channels.



Fig. 9.11 Schematic sketch explaining the principle of electro-osmotic fluid transport

EHD can be broadly broken down into two subcategories: injection type and induction type. In injection type EHD, a strong electric field ($\sim 100\,\mathrm{kV/cm}$) is applied across a dielectric liquid. This induces charge formation in the liquid, and these induced (or injected) charges are then acted upon by the electrical field for pumping. Induction type EHD relies on generating a gradient/discontinuity in the conductivity and/or permitivity of the liquid. *Fuhr* et al. [9.52] explain various techniques that can be used to generate gradients for non-injection type EHD pumping.

MHD pumps rely on creating a Lorentz force on the liquid particles in the presence of an externally applied electric field. MHD has been demonstrated using both DC [9.53] and AC [9.54] excitations. MHD, EHD, and electro-osmotic transport share one feature in common that makes them very appealing for microfluidic systems; namely, none requires microvalves to regulate the flow. This makes these pumping techniques very reliable, as there is no concern of wear and tear of the microvalves, or any other moving parts of the micropump. However, it has been difficult to implement these actuation schemes on a complete microscale, owing to the high voltages/electromagnets, etc. required for these actuation schemes.

9.3 Smart Passive Microfluidic Devices

Passive microfluidics is a powerful technique for the rapidly evolving discipline of BioMEMS. It is a fluid control topology in which the physical configuration of the microfabricated system primarily determines the functional characteristics of the device/system. Typically, passive microfluidic devices do not require an external power source, and the control exerted by the devices is based, in part, on energy drawn from the working fluid, or based purely on surface effects, such as surface tension, selective hydrophobic/hydrophilic control, etc. Most passive microfluidic devices exploit various physical properties such as shape, contact angle, and flow characteristics to achieve the desired function. Passive microfluidic systems are usually easier to implement and allow for a simple microfluidic system with little or no control circuitry. A further list of advantages and disadvantages of passive microfluidic systems (or devices) is considered toward the end of this section.

Passive microfluidic devices can be categorized based on:

- Function – microvalves, micromixers, filters, reactors, etc.
- Fluidic medium – gas or liquid
- Application – biological, chemical, or other
- Substrate material – silicon, glass, polysilicon, polymer, or others

In this section, we will study various passive microfluidic devices that are categorized based on their function. Passive microfluidic devices include, but are not limited to, microvalves, micromixers, filters, dispensers, etc. [9.24].

9.3.1 Passive Microvalves

Passive microvalves have been a subject of great interest ever since the inception of the lab-on-a-chip concept. Microvalves are a key component of any microfluidic system and are essential for fluidic sequencing operations. Since most chemical and biochemical reactions require about five to six reaction steps, passive microvalves with limited functionality are ideally suited for such simple tasks. Passive microvalves can be broadly categorized as follows:

- Silicon/polysilicon or polymer-based check valves
- Passive valves based on surface tension effects
- Hydrogel-based biomimetic valves

Passive Check Valves

Shoji et al. [9.23] provide an excellent review of check-type passive microvalves. Some of the valves, shown in Fig. 9.12, illustrate the various techniques that can be used to fabricate check valves.

Figure 9.12a shows a microvalve fabricated using silicon bulk etching techniques. A through hole (pyramidal cavity) is etched through a silicon wafer that is sandwiched between two glass wafers. The normally closed valve is held in position by the spring effect of the silicon membrane. Upon applying pressure at the lower fluidic port, the membrane deflects upwards, allowing fluid flow through the check valve. The same working principle is employed by the microvalve shown in Fig. 9.12b. However, instead of using a membrane supported on all sides, a cantilever structure is used for the flap. This reduces the burst pressure, i.e., the minimum pressure required to open the microvalve. Figure 9.12c shows that the membrane structure can also be realized using a polysilicon layer deposited on a bulk-etched silicon wafer. Poly-silicon processes typically allow tighter control over dimensions and, consequently, offer more repeatable operating characteristics. Figure 9.12d shows the simplest type of check valve where the V-groove etched in a bulk silicon substrate acts as a check valve. However, the low contact area between the flaps of the microvalve leads to nontrivial leakage rates in the forward direction. Figures 9.12e and f show check valve designs that are realized using polymer/metal films, in addition to the traditional glass/silicon platform. This technique offers a significant advantage in terms of biocompatibility characteristic and controllable operating characteristics. The surface properties of polymers can be easily tailored using a wide variety of techniques such as plasma treatment and surface adsorption [9.55]. Thus, in applications for which the biocompatibility requirements are very stringent, it is preferable to have polymers as the fluid contacting material. Furthermore, polymer properties such as stiffness, can also be controlled in some cases based on the composition and/or processing conditions. Thus, it may be possible to fabricate microvalves with different burst pressures by using different processing conditions for the same polymer.

In addition to the passive check valves reviewed by *Shoji* et al. [9.23], other designs include check valves using composite titanium/polyimide membranes [9.20,21], polymeric membranes such as Mylar or KAPTON [9.56], or PDMS [9.40], and metallic membranes such as [9.22].

Terray et al. [9.57] present an interesting approach to fabricating ultra-small passive valve structures. They have demonstrated a technique to polymerize colloidal particles into linear structures using an optical trap to form microscale particulate valves.



Fig. 9.12a–f Various types of passive microvalve designs: **(a)** membrane type with MESA structure; **(b)** cantilever or flap valve; **(c)** polysilicon membrane; **(d)** V-groove type; **(e)** titanium/polyimide membrane; and **(f)** silicone float valve. Adapted from [9.23]. Reproduced by permissions of IOP Publishing Limited

Passive Valves Based on Surface Tension Effects

The passive valves listed in the previous section use the forced motion of the membrane or flap to control the flow of fluids. These valves are prone to such problems as clogging and mechanical wear and tear. Passive valves based on surface tension effects, on the other hand, have no moving parts and control the fluid motion based on their physical structure and the surface property of the substrate. Figure 9.13 shows a schematic sketch of a passive microvalve on a hydrophobic substrate [9.19].

The Hagen–Poiseuille equation for laminar flow governs the pressure drops in microfluidic systems with laminar flow. For a rectangular channel with a high width to height ratio, the pressure drop is governed by the equation

$$\Delta P=\frac{12L\mu.Q}{wh^3}\,, \tag{9.1}$$

where L is the length of the microchannel, μ is the dynamic viscosity of the fluid, Q is the flow rate, and w and h are the width and height of the microchannel, respectively. Varying L or Q can control the pressure drop for a given set of w and h.

An abrupt change in the width of the channel causes a pressure drop at the point of restriction. For a hydrophobic channel material, an abrupt decrease in channel width causes a positive pressure drop:

$$\Delta P_2=2\sigma_1\cos(\theta_c)\left[\left(\frac{1}{w_1}+\frac{1}{h_1}\right)-\left(\frac{1}{w_2}+\frac{1}{h_2}\right)\right], \tag{9.2}$$

where σ_1 is the surface tension of the liquid, θ_c is the contact angle, and w_1, h_1 and w_2, h_2 are the width and height of the two sections before and during the restriction, respectively. Setting h as constant through the system, ΔP_2 can be varied by adjusting the ratio of w_1 and w_2. *Ahn* et al. [9.19] have proposed and implemented a novel structurally programmable microfluidic system (sPROMs) based on the passive microfluidic approach. In short, the sPROMs system consists of a network of microchannels with passive valves of the type shown in the passive valve section. If the pressure drop of the passive valves is set to be significantly higher than the pressure drop of the microchannel network, then the position of the liquid in the microchannel network can be controlled accurately. By applying sequentially higher pressure pulses, the liquid is forced to move from one passive valve to another. Thus, the movement of the fluid within the microfluidic channels is "programmed" using the physical structure of the microfluidic system, and this forms the basic idea behind sPROMs.



Fig. 9.13 Structure of a passive microvalve based on surface tension effects (adapted from [9.19])

The abrupt transition from a wide channel to a narrow channel can also be affected along the height of the microchannel. Furthermore, the passive valve geometry shown in Fig. 9.13 is not exclusive. *Puntambekar* et al. [9.58] have demonstrated different geometries of passive valves, as shown in Fig. 9.14a. As shown in Fig. 9.14b,



Fig. 9.14 Analysis of different geometries of passive valves. After [9.58], reproduced by permission of The Royal Society of Chemistry

the various geometries of the passive valves in Fig. 9.14a can act as effective passive valves without having an abrupt transition. This is important in order to avoid the dead volume that is commonly encountered across an abrupt step junction.

The use of surface tension to control the operation of passive valves is not limited to hydrophobic substrates. *Madou* et al. [9.59] demonstrate a capillarity-driven stop valve on a hydrophilic substrate. On a hydrophilic substrate, the fluid can easily "wick through" in the narrow region. However, at the abrupt transition to a larger channel section, the surface tension effects will not allow the fluid to leave the narrow channel. Thus, in this case, the fluid is held at the transition from the narrow capillary to the wide outlet channel.

Another mechanism to implement passive valves is the use of hydrophobic patches on a normally hydrophilic channel. *Handique* et al. [9.60] demonstrate the use of this technique to implement passive valves for a DNA analysis system. The fluid is sucked into the microfluidic channels via capillary suction force. The hydrophobic patch exerts a negative capillary pressure that stops the further flow of fluid. The use of hydrophobic patches as passive valves is reported by *Andersson* et al. [9.61].

Other Passive Microvalves

A novel approach to realizing passive valves that are responsive to their surrounding environment is demonstrated by *Low* et al. [9.62] and *Yu* et al. [9.63]. *Yu* et al. [9.63] have developed customized polymer "cocktails" that are polymerized in situ around prefabricated posts. The specialized polymer is selectively responsive to stimuli such as pH, temperature, electric fields, light, carbohydrates, and antigens.

Another interesting approach in developing passive valves has been adopted by *Foster* et al. [9.51]. They have developed the so-called no moving part (NMP) valves, which are based on a physical configuration that allows a higher flow rate along a direction compared to the reverse direction.

9.3.2 Passive Micromixers

The successful implementation of microfluidic systems for many lab-on-a-chip systems is partly owing to the significant reduction in volumes handled by such systems. This reduction in volume is made possible by the use of microfabricated features and channel dimensions ranging from a few μm to several hundred μm. Despite the advantage offered by the micron-sized channels, one of the significant challenges has been the implementation of effective microfluidic mixers on the microscale. Mixing on a macroscale is a turbulent flow regime process. However, on the microscale, because of the low Reynolds numbers as a result of the small channel dimensions, most flow streams are laminar in nature, which does not allow for efficient mixing. On the other hand, diffusion is an important factor in mixing because of the short diffusion lengths.

There have been numerous attempts to realize micromixers using both active and passive techniques. Active micromixers rely on creating localized turbulence to enhance the mixing process, whereas passive micromixers usually enhance the diffusion process. The diffusion process can be modeled by the following equation:

$$\tau = \frac{d^2}{D}\,, \tag{9.3}$$

where τ is the mixing time, d is the distance, and D is the diffusion coefficient. Equation (9.3) illustrates the diffusion-dominated mixing at the microscale. Because of the small diffusion lengths (d), the mixing times can be made very short. The simplest category of micromixers is illustrated in Fig. 9.15. In these mixers, creating a convoluted path increases the path length that the two fluids share, leading to higher diffusion and more complete mixing. However, these mixers only exhibit good mixing performance at low flow rates, in the range of a few μl/min.

Mitchell et al. [9.64] have demonstrated three-dimensional micromixers that can achieve better



Fig. 9.15 Diffusion-enhanced mixers based on long, convoluted flow path

performance by alternately laminating the two fluid streams to be mixed. *Beebe* et al. [9.65] have created a chaotic mixer that has the convoluted channel along three dimensions. This micromixer works on the principle of forced advection resulting from repeated turns in three dimensions. Furthermore, at each turn, eddies are generated because of the difference in flow velocities along the inner and outer radii, which enhances the mixing.

Stroock et al. [9.68] demonstrate a passive micromixer that uses chaotic mixing by superimposing a transverse flow component on the axial flow. Ridges are fabricated at the bottom of microchannels. The flow resistance is lower along the ridges (peak/valley) and higher in the axial direction. This generates a helical flow pattern that is superimposed on the laminar flow. The demonstrated mixer shows good mixing performance over a wide range of flow velocities.

Hong et al. [9.66] have demonstrated a passive micromixer based on the Koanda effect. Their design uses the effects of diffusion mixing at low flow velocities; at high flow velocities, a convective component is added perpendicular to the flow direction, allowing for rapid mixing. This mixer shows excellent mixing performances across a wide range of flow rates because of the dual mixing effects. Figure 9.16 shows a schematic sketch of the mixer structure.

The mixer works on the principle of superimposing a parabolic flow profile in a direction perpendicular to the flow direction. The parabolic profile creates a Taylor dispersion pattern across the cross section of the flow path. The dispersion is directly proportional to the flow velocity, and higher flow rates generate more dispersion mixing.



Fig. 9.16 Mixing unit design for the Coanda effect mixer. The actual mixer has mixing unit pairs in series (after [9.66])


Mixture of low/high diffusivity molecules
Mostly low diffusivity molecules
Mostly high diffusivity molecules
Diluent

Fig. 9.17 Conceptual illustration of the H-Sensor. Adapted from [9.67]

Brody et al. [9.67] have used the laminar flow characteristics in a microchannel to develop a diffusion-based extractor. When two fluid streams, where fluid 1 is loaded with particles of different diffusivity and fluid 2 is a diluent, are forced to flow together in a microchannel, they form two laminar streams with little mixing. If the length that the two streams are in contact is carefully adjusted, only particles with high diffusivity (usually small molecules) can diffuse across into the diluent stream, as shown in Fig. 9.17. The same idea can be extended to a T-filter. *Weigl* et al. [9.69] have demonstrated a rapid diffusion immunoassay using the T-filter.

9.3.3 Passive Microdispensers

The principle of the structurally programmable microfluidic systems (sPROMs) was introduced earlier in the passive valve section. One of the key components of the sPROMs system is the microdispenser, which is designed to accurately and repeatedly dispense fluidic volumes in the micro- to nanoliter range. This would allow the dispensing of a controlled amount of the analyte into the system that could be used for further biochemical analysis. Figure 9.18 shows a schematic sketch of the microdispenser design [9.58].

The microdispenser works on the principle of graduated volume measurement. The fluid fills up the exact fixed volume of the reservoir, and the second passive valve at the other end of the microdispenser stops further



Fig. 9.18 Schematic sketch of the microdispenser. Adapted from [9.58], reproduced by permission of The Royal Society of Chemistry

motion. When the reservoir is filled with fluid, the fluidic actuation is stopped, and, simultaneously, pneumatic actuation from the air line causes a split in the fluid column at point A (Fig. 9.18). Thus, the accuracy of the reservoir decides the accuracy of the dispensed volume. Since the device is manufactured using UV-LIGA lithography techniques, highly accurate and reproducible volumes can be defined. The precisely measured volume of fluid is expelled to the right from the reservoir. The expelled fluid then starts to fill up the measuring channel. When the fluid reaches point B (Fig. 9.18), the third microvalve holds the fluid column.

Figure 9.19 shows an actual operation sequence of the microdispenser. Figure 9.19f shows that the dispensed volume is held by passive valve 3, and at this stage, the length (and hence volume) can be calculated using the on-chip scale. In experiments only, the region in the immediate vicinity of the scale was viewed using a stereomicroscope for measuring the length of the fluid column. The microdispenser demonstrated above is reported to have dispensing variation of less than 1% between multiple dispensing cycles.

9.3.4 Microfluidic Multiplexer Integrated with Passive Microdispenser

Ahn et al. [9.19] have demonstrated the sPROMs technology to be an innovative method of controlling liquid



Fig. 9.19a–f Microphotographs of microdispenser sequence: **(a)** fabricated device; **(b)** fluid at reservoir inlet; **(c)** reservoir filling; **(d)** reservoir filled; **(e)** split in liquid column due to pneumatic actuation; and **(f)** fluid ejected to measurement channel and locked in by passive valve. After [9.58], reproduced by permission of The Royal Society of Chemistry



Fig. 9.20a,b Microfluidic multiplexer with integrated dispenser: **(a)** schematic sketch and **(b)** fabricated device filled with dye (after [9.58])

movement in a programmed fashion in a microfluidic network. By integrating this technique with the microdispensers, a more functionally useful microfluidic system can be realized. Figure 9.20a shows a schematic illustration of the microfluidic multiplexer with the integrated dispenser, and Fig. 9.20b shows an actual device fabricated using rapid prototyping techniques [9.70].



Fig. 9.21a–d Microphotographs showing operation of sequential multiplexer: **(a)** first level division; **(b)** second level division; **(c)** continued multiplexing; and **(d)** end of sequential multiplexing sequence (after [9.58])

The operation of the microdispenser has been explained earlier in this section. Briefly, the fluid is loaded in the fixed-volume metering reservoir via a syringe pump. The fluid is locked in the reservoir by the passive valve at the outlet of the reservoir. When a higher pressure is applied via the air inlet line, the liquid column is split and the fluid is dispensed into the graduating channel.

The microfluidic multiplexer is designed to have a programmed delivery sequence, as shown in Fig. 9.20a, where the numbers on each branch of the multiplexer indicates the filling sequence. This sequential filling is achieved by using different ratios of passive valves along the multiplexer section. For instance, at the first branching point, the passive valve at the upper branch offers less resistance than the passive valve at the beginning of the lower branch. Thus, the dispensed fluid will first fill the top branch. After filling the top branch, the liquid encounters another passive valve at the end of the top branch. The pressure needed to push beyond this valve is higher than the pressure needed to push liquid into the lower branch of the first split. The liquid will then fill the lower branch. This sequence of nonsymmetrical passive valves continues along all the branches of the multiplexer, as shown in Fig. 9.21.

The ability to sequentially divide and deliver liquid volumes was demonstrated for the first time using a passive microfluidic system. This approach has the potential to deliver very simple microfluidic control systems that are capable of a number of sequential microfluidic manipulation steps required in a biochemical analysis system.

9.3.5 Passive Micropumps

A passive system is defined inherently as one that does not require an external energy source. Thus, the term passive micropump might seem misnomer upon initial inspection. However, there have been some efforts dedicated to realizing a passive micropump that essentially does not draw energy from an external source, but stores the required actuation energy in some form and converts it to mechanical energy on demand.

Passive Micropump Based on Osmotic Pressure

Nagakura et al. [9.71] have demonstrated a mesoscale osmotic actuator that converts chemical energy to mechanical displacement. Osmosis is a well-known phenomenon by which liquid is transported across a semipermeable membrane to achieve a uniform concentration distribution across the membrane. If the membrane is flexible, such as the one used by *Nagakura* et al. [9.71], then the transfer of liquid would cause the membrane to deform and act as an actuator. The inherent drawback of using osmosis as an actuation mechanism is that it is a very slow process: Typical response times (on a macroscale) are on the order of several hours. However, osmotic transport scales favorably to the microscale, and it is expected that these devices will have response times on the order of several minutes, rather than hours. Based on this idea, *Nagakura* et al. [9.71] are developing a miniature insulin pump. *Su* et al. [9.72] have demonstrated a microscale osmotic actuator that is capable of developing pressures as high as 35 MPa. This is still a relatively unexplored realm in BioMEMS actuation, and it has good potential for applications such as sustained drug delivery.

Passive Pumping Based on Surface Tension

Glenn et al. have demonstrated pumping action using the difference between the surface tension pressure at the inlet and outlet of a microfluidic channel. In the simplest case, a small drop of a fluid is placed at one end of a straight microchannel, and a much larger drop of fluid is placed at the opposite end of the microchannel. The pressure within the small drop is significantly higher than the pressure within the large drop, due the difference in the surface tension effects across the two drops. Consequently, the liquid will flow from the small drop and add to the larger drop. The flow rate can be varied by changing various parameters such as the volume of the pumping drop, the surface free energy of the liquid, or the resistance of the microchannel, etc. This pumping scheme is very easy to realize and can be used for a wide variety of fluids.

Evaporation-Based Continuous Micropump

Effenhauser et al. [9.73] have demonstrated a continuous flow micropump based on a controlled evaporation approach. Their concept is based on the controlled evaporation of a liquid through a membrane into a gas reservoir. The reservoir contains a suitable adsorption agent that draws out the liquid vapors and maintains a low vapor pressure conducive to further evaporation. If the liquid being pumped is replenished from a reservoir, capillary forces will ensure that the fluid is continuously pumped through the microchannels as it evaporates on the other end into the adsorption reservoir. Though the pump suffers from inherent disadvantages such as strong temperature dependence and operation only in suction mode, it offers a very simple technique for fluidic transport.

9.3.6 Advantages and Disadvantages of the Passive Microfluidic Approach

This chapter has covered a number of different passive microfluidic devices and systems. Passive microfluidic devices have only recently been a subject of considerable research effort. One of the reasons for this interest is the long list of advantages that passive microfluidic devices offer. However, since most microfluidic devices are very application-specific (and even more so for passive microfluidic devices), the advantages are not to be considered universally applicable for all the devices/systems. Some of the advantages that are commonly found are:

- avoid the need for an "active" control system;
- usually very easy to fabricate;
- the passive microfluidic systems with no moving parts are inherently more reliable because of the lack of mechanical wear and tear;
- offer very repeatable performance once the underlying phenomena are well understood and characterized;
- highly suited for BioMEMS applications – can easily handle a limited number of microfluidic manipulation sequences;
- well suited for low cost, mass production approach;

- low cost offers the possibility of having disposable microfluidic systems for specific applications, such as working with blood;
- can offer other interesting possibilities, such as biomimetic response.

However, like all MEMS devices, passive microfluidic devices or systems are not the solution to the microfluidic handling problem. Usually they are very application-specific – they cannot be reconfigured for another application easily. Other disadvantages are listed below:

- suited for well understood, niche applications for which the fluidic sequencing steps are well decided,
- strongly dependent on variances in the fabrication process,
- usually not very suitable for a wide range of fluidic mediums.

9.4 Lab-on-a-Chip for Biochemical Analysis

Recent development in MEMS (microelectromechanical systems) has brought a new and revolutionary tool in biological or chemical applications: "lab-on-a-chip". New terminology, such as micro total analysis systems and lab-on-a-chip, was introduced in the last decade, and several prototype systems have been reported.

The idea of lab-on-a-chip is basically to reduce biological or chemical laboratories to a microscale system, hand-held size or smaller. Lab-on-a-chip systems can be made out of silicon, glass, and polymeric materials, and the typical microfluidic channel dimensions are in the range of several tens to hundreds of µm. Liquid samples or reagents can be transported through the microchannels from reservoirs to reactors using electrokinetic, magnetic, or hydrodynamic pumping methods. Fluidic motions or biochemical reactions can also be monitored using various sensors, which are often used for biochemical detection of products.

There are many advantages to using lab-on-a-chip over conventional chemical or biological laboratories. One of the important advantages lies in its low cost. Many reagents and chemicals used in biological and chemical reactions are expensive, so the prospect of using very small amounts (in micro- to nanoliter range) of reagents and chemicals for an application is very appealing. Another advantage is that lab-on-a-chip requires very small amounts of reagents/chemicals (which enables rapid mixing and reaction) because biochemical reaction is mainly involved in the diffusion of two chemical or biological reagents, and microscale fluidics reduces diffusion time as it increases reaction probabilities. In practical terms, reaction products can be produced in a matter of seconds/minutes, whereas laboratory scale can take hours, or even days. In addition, lab-on-a-chip systems minimize harmful by-products since their volume is so small. Complex reactions of many reagents could happen on lab-on-a-chip that have ultimate potential in DNA analysis, biochemical warfare agent detection, biological cell/molecule sorting, blood analysis, drug screening/development, combinatorial chemistry, and protein analysis. In this section, two recent developments of microfluidic systems for lab-on-a-chip applications will be introduced: (a) magnetic micro/nano bead-based biochemical detection system and (b) disposable smart lab-on-a-chip for blood analysis.

9.4.1 Magnetic Micro/Nano Bead-Based Biochemical Detection System

In the past few years, a large number of microfluidic prototype devices and systems have been developed, specifically for biochemical warfare detection systems and portable diagnostic applications. The BioMEMS team at the University of Cincinnati has been working on the development of a remotely accessible generic microfluidic system for biochemical detection and biomedical analysis, based on the concepts of surface-mountable microfluidic motherboards, sandwich immunoassays, and electrochemical detection techniques [9.74, 75]. The limited goal of this work is to develop a generic MEMS-based microfluidic system and to apply the fluidic system to detect bio-molecules, such as specific proteins and/or antigens, in liquid samples. Figure 9.22 illustrates the schematic diagram of a generic microfluidic system for biochemical detection using a magnetic bead approach for both sampling and manipulating the target bio-molecules [9.76, 77].

The analytical concept is based on sandwich immunoassay and electrochemical detection [9.78], as illustrated in Fig. 9.23. Magnetic beads are used as both substrates of antibodies and carriers of target antigens.



Fig. 9.22 Schematic diagram of a generic microfluidic system for biochemical detection (after [9.75])

A simple concept of magnetic bead-based bio-sampling with electromagnet for the case of sandwich immunoassay is shown in Fig. 9.24.

Antibody-coated beads are introduced on the electromagnet and separated by applying magnetic fields. While holding the antibody-coated beads, antigens are injected into the channel. Only target antigens are immobilized and, thus, separated on the magnetic bead surface due to antibody/antigen reaction. Other antigens get washed out with the flow. Next, enzyme-labeled secondary antibodies are introduced and incubated, along with the immobilized antigens. The chamber is then rinsed to remove all unbound secondary antibodies. Substrate solution, which will react with enzyme, is injected into the channel, and the electrochemical detection is performed. Finally, the magnetic beads are released to the waste chamber, and the bio-separator is ready for another immunoassay. Alkaline phosphatase (AP) and p-aminophenyl phosphate (PAPP) were chosen as enzyme and electrochemical substrate, respectively. Alkaline phosphatase makes PAPP turn into its electrochemical product, p-aminophenol (PAP). By applying potential, PAP gives electrons and turns into 4-quinoneimine (4QI), which is the oxidant form of PAP.



Fig. 9.23 Analytical concept based on sandwich immunoassay and electrochemical detection. After [9.77], reproduced by permission of The Royal Society of Chemistry

For the successful immunoassay, the biofilter [9.76] and the immunosensor were fabricated separately and integrated together. The integrated biofilter and immunosensor were surface-mounted using a fluoropolymer bonding technique [9.79] on a microfluidic motherboard, which contains microchannels fabricated by glass etching and glass-to-glass direct bonding technique. Each inlet and outlet were connected to sample reservoirs through custom-designed microvalves. Figure 9.25 shows the integrated microfluidic biochemical detection system for magnetic bead-based immunoassay.

After a fluidic sequencing test, full immunoassays were performed in the integrated microfluidic system to prove magnetic bead-based biochemical detection and sampling function. Magnetic beads (Dynabeads$^{®}$ M-280, Dynal Biotech Inc.) coated with biotinylated sheep anti-mouse immunoglobulin G (IgG) were injected into the reaction chamber and separated on the surface of the biofilter by applying magnetic fields. While holding the magnetic beads, antigen (mouse IgG) was injected into the chamber and incubated. Then



Fig. 9.24a–g Conceptual illustration of bio-sampling and immuno-assay procedure: **(a)** injection of magnetic beads; **(b)** separation and holding of beads; **(c)** flowing samples; **(d)** immobilization of target antigen; **(e)** flowing labeled antibody; **(f)** electrochemical detection; and **(g)** washing out magnetic beads and ready for another immunoassay (after [9.77], reproduced by permission of The Royal Society of Chemistry)

secondary antibody with label (rat anti-mouse IgG conjugated alkaline phosphatase) and electrochemical substrate (PAPP) to alkaline phosphatase was sequentially injected and incubated to ensure production of PAP. Electrochemical detection using an amperometric time-based detection method was performed during incubation. After detection, magnetic beads with all the reagents were washed away, and the system was ready for another immunoassay. This sequence was repeated for every new immunoassay. The flow rate was set to 20 μl/min in every step. After calibration of the electrochemical immunosensor, full immunoassays were performed following the sequence stated above for different antigen concentrations: 50, 75, 100, 250, and 500 ng/ml. Concentration of primary antibody-coated magnetic beads and conjugated secondary antibody was 1.02×10^7 beads/ml and 0.7 μg/ml, respectively. Immunoassay results for different antigen concentrations are shown in Fig. 9.26.

Immunoreactant consumed during one immunoassay was 10 μl (20 μl/min × 30 s), and total assay time was less than 20 min, including all incubation and detection steps.

The integrated microfluidic biochemical detection system has been successfully developed and fully tested for fast and low volume immunoassays using magnetic beads, which are used as both immobilization surfaces and bio-molecule carriers. Magnetic bead-based immunoassay, as a typical example of biochemical detection and analysis, has been performed on the integrated microfluidic biochemical analysis system that includes a surface-mounted biofilter and immunosensor on a glass microfluidic motherboard. Protein sampling capability has been demonstrated by capturing target antigens.

The methodology and system can also be applied to generic bio-molecule detection and analysis systems by replacing the antibody/antigen with appropriate bio receptors/reagents, such as DNA fragments or oligonucleotides, for the application to DNA analysis and/or high throughput protein analysis.



Fig. 9.25 Photograph of the fabricated lab-on-a-chip for magnetic bead-based immunoassay



Fig. 9.26 Immunoassay results measured by amperometric time-based detection method (after [9.77], reproduced by permission of The Royal Society of Chemistry)

9.4.2 Disposable Smart Lab-on-a-Chip for Blood Analysis

One of several substrates available for bio-fluidic chips, plastics have recently become one of the most popular and promising substrates due to their low cost, ease of fabrication, and favorable biochemical reliability and compatibility. Plastic substrates, such as polyimide, PMMA, PDMS, polyethylene, or polycarbonate, offer a wide range of physical and chemical material parameters for the applications of bio-fluidic chips, generally at low cost using replication approaches. The disposable smart plastic biochip is composed of integrated modules of plastic fluidic chips for fluid regulation, chemical and biological sensors, and electronic controllers. As a demonstration vehicle, the biochip has the specific goal of detecting and identifying three metabolic parameters such as PO_2 (partial pressure of oxygen), lactate, and glucose from a blood sample. The schematic concept of the cartridge-type disposable lab-on-a-chip for blood analysis is illustrated in Fig. 9.27. The disposable lab-on-a-chip cartridge has been fabricated using plastic micro-injection molding and plastic-to-plastic direct bonding techniques. The biochip cartridge consists of a fixed volume microdispenser based on the sPROMs (structurally programmable microfluidic system) technique [9.70], an air-bursting, on-chip pressure source [9.80], and electrochemical biosensors [9.81].

A passive microfluidic dispenser measures exact amounts of sample to be analyzed, and then the air-bursting on-chip power source is detonated to push the graduated sample fluid from the dispenser reservoir. Upon air bursting, the graduated sample fluid travels through the microfluidic channel into sensing reservoirs, under which the biosensor array is located, as shown in Fig. 9.28.


Screen-printed conductive traces
Biosensor using gelbased solid electrolyte
Smart passive microdispenser
Plastic substrate
Blood sample injection
Air-bursting on-chip pressure source
Sample fluid
Air (from on-chip pressure source)

Fig. 9.27 Schematic illustration of smart and disposable plastic lab-on-a-chip by *Ahn* et al. [9.82]

An array of disposable biosensors consisting of an oxygen sensor and a glucose sensor has been fabricated using screen-printing technology [9.81]. Measurements from the developed biosensor array can be done based on tiny amounts of sample (as low as 100 nl). The glucose sensor is designed by adding two additional layers above the oxygen sensor (Fig. 9.29), which are glucose semipermeable membrane and glucose oxidase (GOD) layers.

The principle of the oxygen sensor is based on amperometric detection that when the oxygen diffusion profile from the sample to electrode surface is saturated, which means a constant oxygen gradient distribution profile is generated, the current is proportional only to the oxygen concentration in the solution. A silicone layer is spin-coated and utilized as an oxygen semipermeable membrane because of its high permeability and low signal-to-noise ratio. Water molecules pass through the silicone membrane and reconstitute the gel-based electrolyte so the Cl^- ions can move close to the anode to coalesce with Ag^+. The number of electrons in this reaction is counted by the measuring system.

For the glucose sensor, the additional layers – glucose semipermeable membrane (polyurethane) and the immobilized GOD (in a polyacrylamide gel) – allow direct conversion of the oxygen sensor to a glucose sensor. The glucose molecules will pass through the semipermeable layer and be oxidized immediately. The oxygen sensor will measure hydrogen peroxide, which is a byproduct of glucose oxidation. The level of hydrogen peroxide is proportional to the glucose level in sample. The fabricated disposable plastic lab-on-a-chip cartridge was inserted into a hand-held type biochip analyzer for analysis of human blood sample, as shown in Fig. 9.30. The prototype biochip analyzer consists of biosensor detection circuitry, timing/sequence circuitry for the air-bursting, on-chip power source, and a display unit. The battery-operated biochip analyzer initiated the sensing sequence and displayed readings in one minute. Measured glucose and PO_2 levels in human blood sample are also shown in Fig. 9.31.

The development of the disposable smart microfluidic-based biochips is of immediate relevance to several patient-monitoring systems, specifically for point-of-care health monitors. Since the developed biochip is a low cost, plastic-based system, we envision a disposable application for monitoring clinically significant parameters such as PO_2, glucose, lactate, hematocrit, and pH. These health indicators provide an early warning system for the detection of patient status and can also serve as markers for disease and toxicity monitoring.



Fig. 9.28 Upon air-bursting, sample fluid travels through the microchannel into biosensor detection chamber. Biosensor was detached for clear micro-photographs. Dotted line indicates where biosensor is supposed to be attached (after [9.82])


Sample in micro-fluidic channel
O_2
O_2
O_2 semi-permeable membrane
O_2
O_2
Gel-based solid electrolyte
$AgCl^-$
AgCl
Ag^+
Ag
$2H_2O$
$4OH^-$
$O_2 + 4e^-$
e^-
Measuring system
e^-

Fig. 9.29 Electrochemical and analytical principle of the developed disposable biosensor for partial oxygen concentration sensing (after, © 2002 IEEE [9.81])


Disposable lab-on-a chip cartridge
174
URACELL
BioMEMS @ UC

Fig. 9.30 Hand-held type disposable smart lab-on-a-chip analyzer (after [9.82])



Fig. 9.31a,b Measurement results from the biochip cartridge and analyzer: **(a)** PO_2 calibration curve and **(b)**glucose level (after [9.81])

References

9.1 L. Ristic, H. Hughes, F. Shemansky: Bulk micromachining technology. In: *Sensor Technology and Devices*, ed. by L. Ristic (Artech House, Norwood 1994) pp. 49–93

9.2 M. Esashi, M. Takinami, Y. Wakabayashi, K. Minami: High-rate directional deep dry etching for bulk silicon micromachining, J. Micromech. Microeng. **5** (1995) 5–10

9.3 H. Jansen, M. de Boer, R. Legtenberg, M. Elwenspoek: The black silicon method: A universal method for determining the parameter setting of a fluorine-based reactive ion etcher in deep silicon trench etching with profile control, J. Micromech. Microeng. **5** (1995) 115–120

9.4 Z. L. Zhang, N. C. MacDonald: A RIE process for submicron silicon electromechanical structures, J. Micromech. Microeng. **2** (1992) 31–38

9.5 C. Linder, T. Tschan, N. F. de Rooij: Deep dry etching techniques as a new IC compatible tool for silicon micromachining, Technical Digest of the 6th International Conference on Solid-State Sensors and Actuators (Transducers '91), San Francisco June 24–27, 1991 (IEEE, Piscataway 1991) 524–527

9.6 D. J. Harrison, A. Manz, Z. Fan, H. Ludi, H. M. Widmer: Capillary electrophoresis and sample injection systems integrated on a planar glass chip, Anal. Chem. **64** (1992) 1926–1932

9.7 A. Manz, D. J. Harrison, E. M. J. Verpoorte, J. C. Fettinger, A. Paulus, H. Ludi, H. M. Widmer: Planar chips technology for miniaturization and integration of separation technique into monitoring systems, J. Chromatography **593** (1992) 253–258

9.8 T. R. Dietrich, W. Ehrfeld, M. Lacher, M. Krämer, B. Speit: Fabrication technologies for microsystems utilizing photoetchable glass, Microelectron. Eng. **30** (1996) 497–504

9.9 S. C. Jacobson, R. Hergenroder, L. B. Koutny, J. M. Ramsey: Open channel electrochromatography on a microchip, Anal. Chem **66** (1994) 2369–2373

9.10 M. G. Allen: Polyimide-based process for the fabrication of thick electroplated microstructures, Proc. of the 7th International Conference on Solid-State Sensors and Actuators (Transducers '93), Yokohama June 7–10, 1993 (IEE of Jpn., Tokyo 1993) 60–65

9.11 C. H. Ahn, M. G. Allen: A fully integrated surface micromachined magnetic microactuator with a multilevel meander magnetic core, IEEE/ASME J. Microelectromech. Syst. (MEMS) **2** (1993) 15–22

9.12 E. W. Becker, W. Ehrfeld, P. Hagmann, A. Maner, D. Munchmeyer: Fabrication of microstructures with high aspect ratios and great structural heights by synchrotron radiation lithography, galvanofoming, and plastic moulding (LIGA Process), Microelectronic Eng. **4** (1986) 35–36

9.13 C. S. Effenhauser, G. J. M. Bruin, A. Paulus, M. Ehrat: Integrated capillary electrophoresis on flexible silicone microdevices: Analysis of DNA restriction fragments and detection of single DNA molecules on microchips, Anal. Chem. **69** (1997) 3451–3457

9.14 D. C. Duffy, J. C. McDonald, O. J. A. Schueller, G. M. Whitesides: Rapid prototyping of microfluidic systems in poly(dimethylsiloxane), Anal. Chem. **70** (1998) 4974–4984

9.15 L. Martynova, L. Locascio, M. Gaitan, G. W. Kramer, R. G. Christensen, W. A. MacCrehan: Fabrication of plastic microfluid channels by imprinting methods, Anal. Chem. **69** (1997) 4783–4789

9.16 H. Becker, W. Dietz, P. Dannberg: Microfluidic manifolds by polymer hot embossing for micro-TAS applications, Proc. of Micro-Total Analysis Systems '98, Banff, Canada 1998, ed. by D. J. Harrison, A. van den Berg (Kluwer, Dordrecht 1998) 253–256

9.17 H. Becker, U. Heim: Hot embossing as a method for the fabrication of polymer high aspect ratio structures, Sens. Actuators A **83** (2000) 130–135

9.18 R. M. McCormick, R. J. Nelson, M. G. Alonso-Amigo, J. Benvegnu, H. H. Hooper: Microchannel electrophoretic separations of DNA in injection-molded plastic substrates, Anal. Chem. **69** (1997) 2626–2630

9.19 C. H. Ahn, A. Puntambekar, S. M. Lee, H. J. Cho, C.-C. Hong: Structurally programmable microfluidic systems, Proc. of Micro-Total Analysis systems 2000, Enschede 2000, ed. by A. van den Berg, W. Olthius, P. Bergveld (Kluwer, Dordrecht 2000) 205–208

9.20 W. Schomburg, B. Scherrer: 3.5 mm thin valves in titanium membranes, J. Micromech. Microeng. **2** (1992) 184–186

9.21 A. Ilzofer, B. Ritter, C. Tsakmasis: Development of passive microvalves by the finite element method, J. Micromech. Microeng. **5** (1995) 226–230

9.22 B. Paul, T. Terharr: Comparison of two passive microvalve designs for microlamination architectures, J. Micromech. Microeng. **10** (2000) 15–20

9.23 S. Shoji, M. Esashi: Microflow device and systems, J. Micromech. Microeng. **4** (1994) 157–171

9.24 G. T. A. Kovacs: *Micromachined Transducers Sourcebook* (McGraw-Hill, New York 1998)

9.25 W. Schomburg, J. Fahrenberg, D. Maas, R. Rapp: Active valves and pumps for microfluidics, J. Micromech. Microeng. **3** (1993) 216–218

9.26 K. Hosokawa, R. Maeda: A pneumatically-actuated three way microvalve fabricated with polydimethylsiloxane using the membrane transfer technique, J. Micromech. Microeng. **10** (2000) 415–420

9.27 J. Fahrenberg, W. Bier, D. Maas, W. Menz, R. Ruprecht, W. Schomburg: A microvalve system fabricated by thermoplastic molding, J. Micromech. Microeng. **5** (1995) 169–171

9.28 C. Goll, W. Bacher, B. Bustgens, D. Maas, W. Menz, W. Schomburg: Microvalves with bistable buckled diaphragms, J. Micromech. Microeng **6** (1996) 77–79

9.29 A. Ruzzu, J. Fahrenberg, M. Heckele, T. Schaller: Multi-functional valve components fabricated by combination of LIGA process and high precision mechanical engineering, Microsystem Technol. **4** (1998) 128–131

9.30 K. Sato, M. Shikida: An electrostatically actuated gas valve with S-shaped film element, J. Micromech. Microeng. **4** (1994) 205–209

9.31 J. Robertson, K. D. Wise: A low pressure micromachined flow modulator, Sens. Actuators A **71** (1998) 98–106

9.32 D. J. Sadler, K. W. Oh, C. H. Ahn, S. Bhansali, H. T. Henderson: A new magnetically actuated microvalve for liquid and gas control applications, Proc. of the 6th International Conference on Solid-State Sensors and Actuators (Transducers '99), Sendai 1999 (IEE of Jpn., Tokyo 1999) 1812–1815

9.33 W. Wijngaart, H. Ask, P. Enoksson, G. Stemme: A high-stroke, high-pressure electrostatic actuator for valve applications, Sens. Actuators A **100** (2002) 264–271

9.34 T. Watanabe, H. Kuwano: A microvalve matrix using piezoelectric actuators, Microsystem Technol. **3** (1997) 107–111

9.35 M. Stehr, S. Messner, H. Sandmaier, R. Zangerle: The VAMP – A new device for handling liquids and gases, Sens. Actuators A **57** (1996) 153–157

9.36 W. Jackson, H. Tran, M. O'Brien, E. Rabinovich, G. Lopez: Rapid prototyping of active microfluidic components based on magnetically modified elastomeric materials, J. Vac. Sci. Technol. B **19** (2001) 596

9.37 M. Kohl, K. Skrobanek, S. Miyazaki: Development of stress-optimized shape memory microvalves, Sens. Actuators A **72** (1999) 243–250

9.38 C. Neagu, J. Gardeniers, M. Elwenspoek, J. Kelly: An electrochemical active valve, Electrochemica Acta **42** (1997) 3367–3373

9.39 K. Yoshida, M. Kikuchi, J. Park, S. Yokota: Fabrication of micro-electro-rheological valves (ER valves) by micromachining and experiments, Sens. Actuators A **95** (2002) 227–233

9.40 N. Jeon, D. Chiu, C. Wargo, H. Wu, I. Choi, J. Anderson, G. M. Whitesides: Design and fabrication of integrated passive valves and pumps for flexible polymer 3-dimensional microfluidic systems, Biomedical Microdevices **4** (2002) 117–121

9.41 M. Koch, N. Harris, A. Evans, N. White, A. Brunnschweiler: A novel micropump design with thick-film piezoelectric actuation, Meas. Sci. Technol. **8** (1997) 49–57

9.42 L. Cao, S. Mantell, D. Polla: Design and simulation of an implantable medical drug delivery system using microelectromechanical systems technology, Sens. Actuators A **94** (2001) 117–125

9.43 J. Park, K. Yoshida, S. Yokota: Resonantly driven piezoelectric micropump fabrication of a micropump having high power density, Mechatronics **9** (1999) 687–702

9.44 M. Koch, A. Evans, A. Brunnschweiler: The dynamic micropump driven with a screen printed PZT actuator, J. Micromech. Microeng. **8** (1998) 119–122

9.45 D. Xu, L. Wang, G. Ding, Y. Zhou, A. Yu, B. Cai: Characteristics and fabrication of NiTi/Si diaphragm micropump, Sens. Actuators A **93** (2001) 87–92

9.46 E. Makino, T. Mitsuya, T. Shibata: Fabrication of TiNi shape memory micropump, Sens. Actuators A **88** (2001) 256–262

9.47 H. Chou, M. Unger, S. Quake: A microfabricated rotary pump, Biomedical Microdevices **3** (2001) 323–330

9.48 R. Zengerle, J. Ulrich, S. Kulge, M. Richter, A. Richter: A bidirectional silicon micropump, Sens. Actuators A **50** (1995) 81–86

9.49 M. Carrozza, N. Croce, B. Magnani, P. Dario: A piezoelectric driven stereolithography-fabricated micropump, J. Micromech. Microeng. **5** (1995) 177–179

9.50 H. Andersson, W. Wijngaart, P. Nilsson, P. Enoksson, G. Stemme: A valveless diffuser micropump for microfluidic analytical systems, Sens. Actuators B **72** (2001) 259–265

9.51 F. Forster, R. Bardell, M. Afromowitz, N. Sharma: Design, fabrication and testing of fixed-valve micropumps, Proc. ASME Fluids Engineering Division, ASME Int. Mechanical Engineering Congress and Exposition **234** (1995) 39–44

9.52 G. Fuhr, T. Schnelle, B. Wagner: Travelling wave driven microfabricated electrohydrodynamic pumps for liquids, J. Micromech. Microeng. **4** (1994) 217–226

9.53 J. Jang, S. Lee: Theoretical and experimental study of MHD micropump, Sens. Actuators A **80** (2000) 84–89

9.54 A. Lemoff, A. P. Lee: An AC magnetohydrodynamic micropump, Sens. Actuators B **63** (2000) 178–185

9.55 J. DeSimone, G. York, J. McGrath: Synthesis and bulk, surface and microlithographic characterization of poly(1-butene sulfone)-g-poly(dimethylsiloxane), Macromolecules **24** (1994) 5330–5339

9.56 A. Wego, L. Pagel: A self-filling micropump based on PCB technology, Sens. Actuators A **88** (2001) 220–226

9.57 A. Terray, J. Oakey, D. Marr: Fabrication of colloidal structures for microfluidic applications, Appl. Phys. Lett. **81** (2002) 1555–1557

9.58 A. Puntambekar, J.-W. Choi, C. H. Ahn, S. Kim, V. B. Makhijani: Fixed-volume metering microdispenser module, Lab on a Chip **2** (2002) 213–218

9.59 M. Madou, Y. Lu, S. Lai, C. Koh, L. Lee, B. Wenner: A novel design on a CD disc for 2-point calibration measurement, Sens. Actuators A **91** (2001) 301–306

9.60 K. Handique, D. Burke, C. Mastrangelo, C. Burns: On-chip thermopneumatic pressure for discrete drop pumping, Anal. Chem. **73** (2001) 1831–1838

9.61 H. Andersson, W. Wijngaart, P. Griss, F. Niklaus, G. Stemme: Hydrophobic valves of plasma deposited octafluorocyclobutane in DRIE channels, Sens. Actuators B **75** (2001) 136–141

9.62 L. Low, S. Seetharaman, K. He, M. Madou: Microactuators toward microvalves for responsive controlled drug delivery, Sens. Actuators B **67** (2000) 149–160

9.63 Q. Yu, J. Bauer, J. Moore, D. Beebe: Responsive biomimetic hydrogel valve for microfluidics, Appl. Phys. Lett. **78** (2001) 2589–2591

9.64 M. Mitchell, V. Spikmans, F. Bessoth, A. Manz, A. de Mello: Towards organic synthesis in microfluidic devices: Multicomponent reactions for the construction of compound libraries, Proc. of Micro-Total Analysis systems 2000, Enschede 2000, ed. by A. van den Berg, W. Olthius, P. Bergveld (Kluwer, Dordrecht 2000) 463–465

9.65 D. Beebe, R. Adrian, M. Olsen, M. Stremler, H. Aref, B. Jo: Passive mixing in microchannels: Fabrication and flow experiments, Mecanique & Industries, **2** (2001) 343–348

9.66 C.-C. Hong, J.-W. Choi, C. H. Ahn: A novel in-plane passive micromixer using Coanda effect, Proc. of the μTAS 2001 Symposium, Monterey 2001, ed. by J. M. Ramsey, A. van den Berg (Kluwer, Dordrecht 2001) 31–33

9.67 J. Brody, P. Yager: Diffusion-based extraction in a microfabricated device, Sens. Actuators A **54** (1996) 704–708

9.68 A. Stroock, S. Dertinger, A. Ajdari, I. Mezic, H. Stone, G. M. Whitesides: Chaotic mixer for microchannels, Science **295** (2002) 647–651

9.69 B. Weigl, P. Yager: Microfluidic diffusion-based separation and detection, Science **283** (1999) 346–347

9.70 A. Puntambekar, J.-W. Choi, C. H. Ahn, S. Kim, S. Bayyuk, V. B. Makhijani: An air-driven fluidic multiplexer integrated with microdispensers, Proc. of the μTAS 2001 Symposium, Monterey 2001, ed. by J. M. Ramsey, A. van den Berg (Kluwer, Dordrecht 2001) 78–80

9.71 T. Nagakura, K. Ishihara, T. Furukawa, K. Masuda, T. Tsuda: Auto-regulated osmotic pump for insulin therapy by sensing glucose concentration without energy supply, Sens. Actuators B **34** (1996) 229–233

9.72 Y. Su, L. Lin, A. Pisano: Water-powered osmotic microactuator, Proc. of the 14th IEEE MEMS Workshop (MEMS 2001), Interlaken 2001 (IEEE, Piscataway 393–396

9.73 C. Effenhauser, H. Harttig, P. Kramer: An evaporation-based disposable micropump concept for continuous monitoring applications, Biomedical Devices **4** (2002) 27–32

9.74 C. H. Ahn, H. T. Henderson, W. R. Heineman, H. B. Halsall: Development of a generic microfluidic system for electrochemical immunoassay-based remote bio/chemical sensors, Proc. of Micro-Total Analysis Systems '98, Banff, Canada 1998, ed. by D. J. Harrison, A. van den Berg (Kluwer, Dordrecht 1998) 225–230

9.75 J.-W. Choi, K. W. Oh, A. Han, N. Okulan, C. A. Wijayawardhana, C. Lannes, S. Bhansali, K. T. Schlueter, W. R. Heineman, H. B. Halsall, J. H. Nevin, A. J. Helmicki, H. T. Henderson, C. H. Ahn: Development and characterization of microfluidic devices and systems for magnetic bead-based biochemical detection, Biomedical Microdevices **3** (2001) 191–200

9.76 J.-W. Choi, C. H. Ahn, S. Bhansali, H. T. Henderson: A new magnetic bead-based, filterless bio-separator with planar electromagnet surfaces for integrated bio-detection systems, Sens. Actuators B **68** (2000) 34–39

9.77 J.-W. Choi, K. W. Oh, J. H. Thomas, W. R. Heineman, H. B. Halsall, J. H. Nevin, A. J. Helmicki, H. T. Henderson, C. H. Ahn: An integrated microfluidic biochemical detection system for protein analysis with magnetic bead-based sampling capabilities, Lab on a Chip **2** (2002) 27–30

9.78 O. Niwa, Y. Xu, H. B. Halsall, W. R. Heineman: Small-volume voltammetric detection of 4-aminophenol with interdigitated array electrodes and its application to electrochemical enzyme immunoassay, Anal. Chem. **65** (1993) 1559–1563

9.79 K. W. Oh, A. Han, S. Bhansali, H. T. Henderson, C. H. Ahn: A low-temperature bonding technique using spin-on fluorocarbon polymers to assemble microsystems, J. Micromech. Microeng. **12** (2002) 187–191

9.80 C.-C. Hong, J.-W. Choi, C. H. Ahn: A disposable on-chip air detonator for driving fluids on point-of-care systems, Proc. of the 6th International Conference on Micro Total Analysis Systems (μ-TAS), Nara 2002, ed. by Y. Baba, S. Shoji, A. van den Berg (Kluwer, Dordrecht 2002)

9.81 C. Gao, J.-W. Choi, M. Dutta, S. Chilukuru, J. H. Nevin, J. Y. Lee, M. G. Bissell, C. H. Ahn: A fully integrated biosensor array for measurement of metabolic parameters in human blood, Proc. of the 2nd Second Annual International IEEE-EMBS Special Topic Conference on Microtechnologies in Medicine and Biology, Madison May 2–4, 2002, ed. by A. Dittmar, D. Beebe (IEEE, New York 2002) 223–226

9.82 C. H. Ahn, J.-W. Choi, A. Puntambekar, C.-C. Hong, X. Zhu, C. Gao, R. Trichur, S. Chilukuru, M. Dutta, S. Murugesan, S. Kim, Y.-S. Sohn, J. H. Nevin, G. Beaucage, J.-B. Lee, J. Y. Lee, M. G. Bissell: Disposable biochip cartridge for clinical diagnostics toward point-of-care systems, Proc. of the 6th International Conference on Micro Total Analysis Systems (μ-TAS), Nara 2002, ed. by Y. Baba, S. Shoji, A. van den Berg (Kluwer, Dordrecht 2002) 187–189

10. Therapeutic Nanodevices

Therapeutic nanotechnology offers minimally invasive therapies with high densities of function concentrated in small volumes, features that may reduce patient morbidity and mortality. Unlike other areas of nanotechnology, novel physical properties associated with nanoscale dimensionality are not the raison d'etre of therapeutic nanotechnology, whereas the aggregation of multiple biochemical (or comparably precise) functions into controlled nanoarchitectures is. Multifunctionality is a hallmark of emerging nanotherapeutic devices, and multifunctionality can allow nanotherapeutic devices to perform multi-step work processes, with each functional component contributing to one or more nanodevice subroutine such that, in aggregate, subroutines sum to a cogent work process. Cannonical nanotherapeutic subroutines include tethering (targeting) to sites of disease, dispensing measured doses of drug (or bioactive compound), detection of residual disease after therapy and communication with an external clinician/operator. Emerging nanotherapeutics thus blur the boundaries between medical devices and traditional pharmaceuticals. Assembly of therapeutic nanodevices generally exploits either (bio)material self assembly properties or chemoselective bioconjugation techniques, or both. Given the complexity, composition, and the necessity for their tight chemical and structural definition inherent in the nature of nanotherapeutics, their cost of goods (COGs) might exceed that of (already expensive) biologics. Early therapeutic nanodevices will likely be applied to disease states which exhibit significant unmet patient need (cancer and cardiovascular disease), while application to other disease states well-served by conventional therapy may await perfection of nanotherapeutic design and assembly protocols.

10.1 Definitions and Scope of Discussion 280
10.1.1 Design Issues 281
10.1.2 Utility and Scope of Therapeutic Nanodevices 285

10.2 Synthetic Approaches: "top-down" versus "bottom-up" Approaches for Nanotherapeutic Device Components 285
10.2.1 Production of Nanoporous Membranes by Microfabrication Methods: A top-down Approach 285
10.2.2 Synthesis of Poly(amido) Amine (PAMAM) Dendrimers: A bottom-up Approach 286
10.2.3 The Limits of top-down and bottom-up Distinctions with Respect to Nanomaterials and Nanodevices 287

10.3 Technological and Biological Opportunities 288
10.3.1 Assembly Approaches 288
10.3.2 Targeting: Delimiting Nanotherapeutic Action in Three-Dimensional Space 296
10.3.3 Triggering: Delimiting Nanotherapeutic Action in Space and Time 298
10.3.4 Sensing Modalities 302
10.3.5 Imaging Using Nanotherapeutic Contrast Agents 304

10.4 Applications for Nanotherapeutic Devices 307
10.4.1 Nanotherapeutic Devices in Oncology 307
10.4.2 Cardiovascular Applications of Nanotherapeutics 310
10.4.3 Nanotherapeutics and Specific Host Immune Responses 311

10.5 Concluding Remarks: Barriers to Practice and Prospects 315
10.5.1 Complexity in Biology 315
10.5.2 Dissemination of Biological Information 315
10.5.3 Cultural Differences Between Technologists and Biologists 316

References 317

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

10.1 Definitions and Scope of Discussion

Nanotechnology is a field in rapid flux and development, as cursory examination of this volume shows, and definition of its meets and bounds, as well as identification of sub-disciplines embraced by it, can be elusive. The word means many things to many people, and aspects of multiple disciplines, from physics to information technology to biotechnology, legitimately fall into the intersection of the Venn diagram of disciplines that defines nanotechnology. The breadth of the field allows almost any interested party to contribute to it, but the same ambiguity can render the field diffuse and amorphous. If nanotechnology embraces everything, what then is it? The ambiguity fuels cognitive dissonance that can result in frustrating interactions between investigators and funders, authors and editors, and entrepreneurs and investors. Some consideration of the scope of the field therefore is useful.



Fig. 10.1a–c Antibodies resemble purpose-built devices with distinct functional domains [10.1]. Native antibodies are composed of four polypeptide chains: two heavy chains (H_C) and two light chains (L_C), joined by interchain disulfide linkages (lines between H_C and L_C moieties). Amino and carboxy termini of individual polypeptide chains are indicated (by N and C). Antigen binding domains are responsible for specific antigen recognition, vary from antibody to antibody, and are indicated by the thicker lines. Common effector functions (F_C receptor binding, complement fixation, etc.) are delimited to domains of the antibodies that are constant from molecule to molecule. **(a)** A native IgG antibody is monospecific but bivalent in its antigen binding capacity. **(b)** An engineered, bispecific, bivalent antibody capable of recognizing two distinct antigens. **(c)** An engineered antibody fragment (single chain Fv or SCFv) that is monospecific and monovalent can recognize only one antigenic determinant and is engineered to lack common effector functions. This construct is translated as a single, continuous polypeptide chain (hence the name SCFv) because a peptide linker (indicated by the connecting line in the figure) is incorporated to connect the carboxy end of the H_C fragment and the amino end of the L_C fragment

To frame the discussion, we will define nanotechnology as the discipline that aims to satisfy desired objectives using materials and devices whose valuable properties are based on a specific nanometer-scale element of their structures. The field is unabashedly application-oriented, so its raison d'être is fulfillment of tasks of interest: technical information is important primarily to the extent that it bears on device design, function, or application.

The meaning of "therapeutic" is largely self-explanatory and refers here to intervention in *human* disease processes (although many of the approaches discussed are equally applicable to veterinary medicine). Our discussion will be confined primarily to therapeutics used in vivo, because such applications clearly benefit from the low invasiveness that ultra-small, but multipotent, nanotherapeutics potentially offer. It is debatable whether imaging, diagnostic, or sensing devices can be considered therapeutic in this context, though, as we will see, sensing/diagnostic functionalities are often inextricable elements of therapeutic nanodevices, and it is difficult to consider so-called smart nanotherapeutics without discussion of their sensing capabilities.

Our definition of nanotechnology projects several corollaries. First, it embraces macroscale structures whose useful properties derive from their nanoscale aspects. Second, the modifier "specific" (as in, "specific nanometer-scale elements") is intended to exclude materials whose utility derives solely from properties inherent in being finely divided (high surface-to-volume ratios, for instance), or other bulk chemical and physical properties. We made the exclusion based on our assessment that therapeutic nanodevices are more intriguing than nanomaterials per se (see below), though we will engage these attributes where they are germane to specific devices or therapeutic applications. Third, our definition implies that limited nanotechnology has been available since the 1970s in the form of biotechnology. Based on their nanoscale structures, individual biological macromolecules (such as proteins) often exhibit the coordinated, modular multifunctionality that is characteristic of purpose-built devices (Fig. 10.1). An analogous, but perhaps less persuasive, argument can be made that organic chemistry is an early form of nanotechnology. Compared to organic small molecules, protein functional capabilities and properties are generally more complex and extremely dependent on their conformation in three-dimensional space at nanometer scale. The nanotechnology sobriquet, therefore, may be more appropriate to biotechnology than organic chemistry.

Biological macromolecules rely on the deployment of specific chemical functionalities to specific relative distributions in space with nanometer (and greater) resolution for their function, so the inclusion of molecular engineering aspects of biotechnology practice under the nanotechnology rubric is legitimate, despite the discomfort it may cause traditionally trained engineers. As we will see, intervention in human disease often requires inclusion of biomolecules in therapeutic devices: frequently, no functional synthetic analogue of active proteins and nucleic acids is available.

As described above, this chapter focuses primarily on nanoscale therapeutic devices as opposed to therapeutic nanomaterials. Devices are integrated functional structures and not mixtures of materials. Devices exhibit desirable emergent properties inherent in their design: the properties emerge as the result of the spatial and/or temporal organization, and coordination and regulation of action of individual components. The organization of components in devices allows them to perform multistep, cogent work processes that can't be mimicked by simple admixtures of individual components. In fact, if device functions can be mimicked well by simple mixtures of components, the labor involved in configuring and constructing a nanoscale device is not warranted. Our device definition thus excludes nanomaterials used as drug formulation excipients (pharmacologically inert materials included in formulations that improve pharmacophore uptake, biodistribution, pharmacokinetic, handling, storage, or other properties), but embraces those same materials as integral components of drug delivery or other clinical devices.

10.1.1 Design Issues

The biotechnology industry historically has focused on production of individual soluble protein and nucleic acid molecules for pharmaceutical use, with only limited attention paid to functional supramolecular structures [10.2–7]. This bias toward free molecules flies in the face of the obvious importance of integrated supramolecular structures in biology and, to the casual observer, may seem an odd gap in attention and emphasis on the part of practicing biotechnologists. The bias toward single molecule, protein therapeutics, however, follows from the fact that biotechnology is an industrial activity, governed by market considerations. Of the myriad potential therapeutics that might be realized from biotechnology, single protein therapeutics are among the easiest to realize from both technical and regulatory perspectives and so warrant extensive industrial attention. This is changing, however, and more complex entities (actual supramolecular therapeutic devices) have and will appear with increasing frequency in the twenty-first century.

New top-down and bottom-up materials derived from micro/nanotechnology provide the opportunity to complement the traditional limits of biotechnology by providing scaffolds that can support higher level organization of multiple biomolecules to perform work activities they could not perform as free, soluble molecules. Such supramolecular structures have been called nanobiotechnological devices [10.8], nanobiological devices [10.2–7], or semi-synthetic nanodevices and figure prominently in therapeutic nanotechnology.

Incorporation of / Interaction with Biomolecules

In general, design of nanodevices is similar to design of other engineered structures, providing that the special properties of the materials (relating to their nanoscale aspects such as quantum, electrical, mechanical, biological properties, etc.), as well as their impact in therapy, are considered. Therapeutics can interact with patients on multiple levels, ranging from organismal to molecular, but it is reasonable to expect that most nanotherapeutics will interface with patients at the nanoscale at least to some extent [10.2–5, 9–14]. Typically, this means interaction between therapeutics and biological macromolecules, supramolecular structures and organelles, which, in turn, often dictates the incorporation of biological macromolecules (and other biostructures) into nanodevices [10.2, 5, 13–15]. Incorporating biological structures into (nanobiological) devices presents special challenges that do not occur in other aspects of engineering practice.

Unlike fully synthetic devices, semi-biological nanodevices must incorporate pre-fabricated biological components (or derivatives thereof), and therefore the intact nanodevices are seldom made entirely de novo. As a corollary, knowledge of properties of biological device components is often incomplete (as they were not made by human design), and therefore the range of activities inherent in any nanobiological device design may be much less obvious and less well-defined than it is for fully synthetic devices. Further complicating the issue, the activities of biological molecules are often multifaceted (many genes and proteins exhibit pleiotropic activities), and the full range of functionality of individual biological molecules in interactions with other biological systems (as in nanotherapeutics) is often not known. This makes design and prototyping of biological nanodevices an empirically intensive, iterative process [10.3–5, 14].

Biological macromolecules have properties, particularly those relating to their stability, that can limit their use in device contexts. In general, proteins, nucleic acids, lipids, and other biomolecules are more labile to physical insult than are synthetic materials. With the possible exceptions of topical agents or oral delivery and endosomal uptake of nanotherapeutics (both involving exposure to low pH), patients can tolerate conditions encountered by nanobiological therapeutics in vivo, and device lability in the face of *physical* insult is generally a major consideration only in ex vivo settings (relating to storage, sterilization, ex vivo cell culture, etc.). Living organisms remodel themselves constantly in response to stress, development, pathology, and external stimuli. For instance, epithelial tissues and blood components are constantly eliminated and regenerated, and bone and vasculature are continuously remodeled. The metabolic facilities responsible (circulating and tissue-bound proteases and other enzymes, various clearance organs, the immune system, etc.) can potentially process biological components of nanobiological therapeutic devices as well as endogenous materials, leading to partial or complete degradation of nanotherapeutic structure, function, or both. Furthermore, the host immune and wound responses protect the host against pathogenic organism incursions by mechanisms that involve sequestering and degrading the pathogens. Nanobiological therapeutics are subject to the actions of these host defense systems and to normal remodeling processes. As we will discuss, various strategies to stabilize biomolecules and structures in heterologous in vivo environments are applicable to nanobiological therapeutics [10.3, 16–20]. Conversely, instability of active biocomponents can offer a valuable and simple way to delimit the activity of nanotherapeutics containing biomolecules.

Nanotherapeutic Design Paradigms

Several early attempts to codify the canonical properties of ideal nanobiological devices, and therapeutic nanodevices in particular, have been made [10.5, 13, 15, 21] and are summarized in Table 10.1. In general, nanobiological devices contain biological components that retain their function in new (device) contexts. In other words, one must abstract enough of a functional biological unit from its native context to allow it to perform the function for which it was selected. If one wishes, for example, to appropriate the specific antigen recognition property of an antibody for a device function (say, in targeting, discussed later), it is not necessary to incorporate the entire 150,000 atomic mass unit (AMU) antibody, the bulk of which is devoted to functions other than antigen recognition (see Fig. 10.1 [10.1]), but it *is* critical to incorporate the approximately 20,000 AMU of the antibody essential for specific antibody–antigen

Table 10.1 Some ideal characteristics of nanodevices. (**A**) Characteristics of all nanobiological devices [10.2, 5, 13–15]. (**B**) Desirable characteristics of therapeutic platforms [10.2, 5, 13–15]

A
Biological molecules must retain function.
Device function is the result of the summed activities of device components.
The relative organization of device components drives device function.
Device functions can be unprecedented in the biological world.
B
Therapeutics should be minimally invasive.
Therapeutics should have the capacity to target sites of disease.
Therapeutics should be able to sense disease states in order to:
– report conditions at the disease site to clinicians.
– administer metered therapeutic interventions.
Therapeutic functions should be segregated into standardized modules.
Modules should be interchangeable to tune therapeutic function.



Fig. 10.2 The bacmid molecular cloning system is a molecular device designed to allow efficient production of recombinant insect viruses (baculovirus) in *Escherichia coli* [10.22–24]. Baculovirus is replicated in *E. coli* by the F plasmid origin of replication (F ori), and as such, is called a bacmid. The bacmid also includes an engineered transposable DNA element 7 (Tn7) attachment site isolated from the chromosome of an enteric bacteria (AttTn7). AttTn7 can receive Tn7 elements transposed from other cellular locations. A donor plasmid (donor) is replicated by a temperature-sensitive plasmid pSC101 origin of replication (ts ori). The donor also incorporates an expression cassette containing both the gene of interest for ultimate expression in insect cells and a selectable genetic marker operable in *E. coli*. The expression cassette is flanked by DNA sequences (attL and attR) that are recognized by the Tn7 transposition machinery. Tn7 transposition machinery resides elsewhere in the same *E. coli* cell. When donor plasmid is introduced into *E. coli* containing bacmid, Tn7 transposition machinery causes the physical relocation of expression cassettes from donor plasmid to bacmid. Unreacted donor plasmid is conveniently removed by elevating the incubation temperature, causing the ts pSC101 replicon to cease to function, in turn, causing the donor to be lost. If selection for the genetic markers within the expression cassette is applied at this point, the only *E. coli* that survive are those containing recombinant bacmid (i. e., those that have received the gene for insect cell expression by transposition from the donor). Recombinant bacmid are conveniently isolated from *E. coli* and introduced into insect cell culture, where expression of the gene of interest occurs

binding. Device function is the result of the summed and various activities of biological and synthetic device components, as well, though functional biological components generally exist in the context of higher order systems that support the organisms of which they are a part by the control the nanobiological device designer can exert on the relative organization of biological device components allows biomolecules abstracted from their native context and incorporated in nanobiotechnological devices to contribute to functions entirely different from those they performed in their organismal contexts. All of these features are illustrated in the bacmid, or Bac-to-Bac, system, a commercially available molecular cloning device ([10.22–24] and Fig. 10.2). This system configures prokaryotic genetic elements from multiple sources into a device for producing recombinant eukaryotic viruses, a function that is unprecedented in nature. The system is feasible because of the modularity of the genetic elements involved and because of the strict control of the relative arrangement of genetic elements allowed by recombinant DNA technology. Analogous devices based on bacterial and eukaryotic regulatory elements to pre-program the micro- and nanoscale architectural properties and physiological behavior of living things are now being realized [10.25, 26].

Bacmid provides an example of a nontherapeutic nanobiological device and illustrates some specific design approaches for building functional devices with biocomponents. Hypothetical properties of nanoscale devices specifically for therapeutic purposes have been codified (Table 10.1) and bear examination [10.13, 15].

In nanotherapeutic applications, devices should be noninvasive and target therapeutic payloads to sites of disease to maximize therapeutic benefit while minimizing undesired side effects. This of course implies the existence of therapeutic effector functions in these nanodevices, to give devices the ability to remediate a physiologically undesirable condition. Beyond that, several attributes relate to sensing of biomolecules, cells, or physical conditions (sensing disease itself, identification of residual disease, and, potentially, targeting capacity, responding to intrinsic or externally supplied triggers for payload release). Other properties relate to communication between device subunits (for instance, between sensor and effector domains of the device)



Fig. 10.3 A hypothetical, modular nanotherapeutic patterned after the dendrimer-based cluster agent for oncology of Baker [10.15]. As described in the text, each dendrimer subunit is grown from an initiator core (C), and the tunable surface groups of the dendrimers are represented by Z. Each dendrimer subunit has a specific, dedicated function in the device: the central dendrimer encapsulates small molecule therapeutics (E), whereas other functional components are segregated to other dendrimer components. These include biochemical targeting/tethering functions (Ta), therapeutic triggering functions to allow activation of prodrug portions of the device by an external operator (Tr), metal or other constituents for imaging (I), and sensing functions (S) to mediate intrinsically controlled activation/release of therapeutic. This design constitutes a therapeutic platform [10.13, 15] because of its modular design. The depicted device is only one possible configuration of an almost infinite number of analogous therapeutics that can be tuned to fit particular therapeutic needs by interchanging functional modules

or between the device and an external operator (external triggering and data documentation capability). With appropriate design, device functions can be modular [10.13, 15]. As discussed below, this approach allows construction of nanotherapeutic platforms (such as the dendrimer-based therapeutic of Fig. 10.3, dendrimer synthesis and assembly are discussed later), as opposed to single one-off devices that are capable of only one therapeutic task.

The vision of nanoscale therapeutic platforms arose from collaboration between the National Cancer Institute (NCI) and the National Aeronautics and Space Agency (NASA). NASA is concerned with minimal mass therapeutics: therapeutics, along with almost everything else used by astronauts, must be launched from Earth. NCI is interested in early detection of disease to improve prognosis. Since this requires screening a population predominantly of healthy patients, the screening mode must be minimally invasive. The considerations of both agencies might be met with ultra-small (micro- or nanoscale) multipotent therapeutic devices. Furthermore, the proposed therapeutic platforms should not only remediate undesired physiological conditions but also have the capacity to recognize them and report them. Extensive capability for molecular recognition and communication with external clinicians/operators is integral to the requirements of NASA and NCI. These capacities would allow drugs or other therapeutic interventions to be provided in a controlled fashion, to maximize benefit and minimize side effects, and is the essence of "smart" therapeutics (see the discussion of targeting and triggering below).

Though substantial progress has been made in device design and realization, no fully realized multipotent nanoscale therapeutic platform has yet been commercialized, but the therapeutic platform paradigm, in which devices are modular, with functional tasks segregated into individual modules, has potential to be extremely powerful. Classes of broadly similar devices could be tailored to specific disease states by interchanging modules (targeting modules, drugs dispensers, etc.) as appropriate to the disease state or therapeutic course. Thus, the hypothetical device represents a possible therapeutic platform composed of functional modules that could be for use in particular indications or in specific individuals.

10.1.2 Utility and Scope of Therapeutic Nanodevices

Therapeutic nanotechnology will be useful, of course, when the underlying biology of the disease states involved is amenable to intervention at the nanoscale. As we will discuss, while several disease states and physiological conditions (cancer, vaccination, cardiovascular disease, etc.) are particularly accessible to nanoscale interventions, some nanotechnological approaches may be applicable more broadly. Much as was the case with the introduction of recombinant protein therapeutics over the last 20 years, nanotherapeutics may present regulatory and pharmacoeconomic challenges related to their novelty and their cost of goods (COGs).

10.2 Synthetic Approaches: "top-down" versus "bottom-up" Approaches for Nanotherapeutic Device Components

Synthesis of nanomaterials is commonly thought of in terms of "top-down" or "bottom-up" processes. Top-down approaches begin with larger starting materials and, in a more or less controlled fashion (depending on the technique), remove material until the desired structure is achieved. Most microfabrication techniques for inorganic materials (lithography and milling techniques, etc.) fit this description. In contrast, bottom-up approaches begin with smaller subunits that are assembled, again with varying levels of control, depending on technique, into the final product. Key examples of materials made by bottom-up approaches include some inorganic structures. This includes "handmade" structures created by using direct atomic or molecular placement by force microscopy (discussed below), structures built using various deposition or growth methods, as well as all polymerization methods of synthesis. Thus, almost all biologic macromolecules and most biogenic structures, including mineralized biomaterials, are made by bottom-up methods. To make the distinction between top-down and bottom-up approaches more concrete, we will consider an example of each.

10.2.1 Production of Nanoporous Membranes by Microfabrication Methods: A top-down Approach

Lithography can be summarized by three basic steps: 1) Pattern Design (generation of masks), 2) Pattern Definition (exposure), and 3) Pattern Transfer (etching/liftoff). Optical lithography uses masks to form patterns on resist/substrate surfaces to produce features. The technique's power lies in its reproducibility and its capacity to manufacture via highly parallel processes. The key limitation of photolithography lies in the fact that resolution of features is diffraction-limited by the wavelength of light used. To address this limitation, short-wave radiation (i. e., X-rays with wavelengths of about 1 nm wavelength) can be generated by synchrotron or other sources (from X-ray tubes, discharge plasma, or laser plasma), controlled, and focused for use in X-ray lithographic techniques [10.27]. The process is identical conceptually to optical lithography but requires special masks and resists amenable to the high-frequency radiation used. Combinations of filters and mirrors can produce resolutions in feature size of less than 100 nm, with fabrication throughputs congruent with those of other optical lithography processes. Limited access to synchrotron sources in turn limits the wide application of the method, however. The relatively long wavelengths used in conventional photolithography are generally unsuitable for formation of nanoscale features unless some clever technical expedient, like the use of a sacrificial layer (described below for generating nanoporous membranes) is employed.

As we will discuss in consideration of applications of nanotherapeutic devices, there are numerous potential applications for tunable nanopore membranes [10.16–18]. For certain applications, such as immunoisolation (see below), the distribution of pore sizes must be tight and nearly perfect. Until the late 1990s, this was an unattainable objective.



Fig. 10.4a–d Nanoporous silicon membranes are fabricated by a top-down approach [10.16–18]. **(a)** Pore exit holes are plasma-etched through p+ silicon (*dark brown*) and boronated silicon (*grey*). **(b)** Controlled depth silicon oxide (*white*) layer is grown on the structure. **(c)** A thick polysilicon layer (*light brown*) is deposited over the oxide, and pore exits are established by back-side plasma etch. **(d)** Pores are opened by removal of the sacrificial layer with hydrofluoric acid. The membranes themselves are macroscale objects that fit under the nanotechnology rubric because they derive their useful properties from controlled nanoscale architecture

The key technical innovation facilitating the microfabrication of highly defined nanoporous membranes was an approach featuring a sacrificial oxide layer sandwiched between two structural layers that ultimately is etched away to define the pore pathway and diameter [10.16–18]. The sacrificial layer (SiO_2) is sandwiched between a silicon wafer and a polysilicon layer: pore channel diameter is determined by the SiO_2 thickness. In the process (Fig. 10.4), the top of a silicon wafer is doped with boron to increase its mechanical robustness, and p+ silicon is overlaid. Pore exit holes are plasma etched through the p+ and doped material. In the pore dimension-determining step, SiO_2 is grown on the wafer by dry thermal oxidation, a process allowing control of oxide layer thickness to within 1 nm. This oxide constitutes the critical sacrificial layer. A thick polysilicon layer (again, boron-doped for mechanical strength) is then deposited over the oxide. Pore entry holes are etched by plasma etch, offset from the exit pores. Ultimately, the offset will require the diffusion pathway of the finished structure to pass through a "bottleneck" whose diameter is determined by the thickness of the sacrificial layer. The backside of the wafer is anisotropically etched to expose the doped layer of the wafer (now the bottom of the membrane structure). Pores are opened by removal of exposed sacrificial layer using concentrated hydrofluoric acid.

10.2.2 Synthesis of Poly(amido) Amine (PAMAM) Dendrimers: A bottom-up Approach

PAMAM dendrimers are remarkably defined synthetic molecules made using polymer chemistry (Fig. 10.5). Their unique structural attribute is their fractal geometry, and their unique physical property is their high monodispersity. Clever use of orthogonal conjugation strategies in their synthesis drives their monodispersity [10.28–30].

Orthogonal conjugation involves the mutually exclusive reactivity of the chemical specificities present in the reaction: when the orthogonal reactants are present in a vessel, and the reaction is carried at appropriate stoichiometry, only a monodisperse single product is formed. PAMAM dendrimers are among the most monodisperse synthetic materials available and, within limits, their sizes, surface chemistries, and shapes can be controlled at the synthetic level. To a greater or lesser extent, these desirable material properties of dendrimers are caused by an orthogonal synthetic strategy.



Fig. 10.5 PAMAM dendrimers are grown bottom-up using sequential orthogonal synthetic steps [10.28–30]. Dendrimers are grown from amine cores, in this case ammonia, by sequential addition of methyl acrylate, followed by an independent reaction addition reaction involving ethylene diamine. Together, these two half-steps constitute a full generation of dendrimer growth. PAMAM dendrimers are classified by their generation of growth as being G_0, G_1, G_2, etc., as indicated in the figure

PAMAM dendrimers are usually built from an initiator core (an amine) in sequential shells, called generations (i. e., G_0, G_1, G_2, etc.). Each generation comprises two synthetic half-steps, each of which is self-limiting in that the reagents performing each addition step are reactive only with the distinct chemical functionalities added to the growing dendrimer in the *previous* addition reaction. Reagent is added until the chemical functionalities from the previous step are fully consumed (Fig. 10.5). In the first synthetic half-step, methyl acrylate is added to the amine precusor, adding a carboxy-terminated functionality to all amine branch points. Polymer intermediates terminating in such carboxy functionalities are called "half-generation." In the second half-step, the generation is completed. Ethylene diamine is added, resulting in a branched amine-terminated adduct for each carboxylate group of the half-generation precursor. In general, before proceeding to downstream synthetic operations, products of individual reactions are purified so that only functionalities incorporated into growing dendrimer are available for subsequent reactions. Under ideal conditions, only a single chemical structure can result from each generation of growth, and with adequate purification between addition reactions; in the absence of limitations on the completeness of each reaction (such as steric limitations which become manifest in dendrimers of generation 6 and above), dendrimers of each generation are perfectly identical to each other.

10.2.3 The Limits of top-down and bottom-up Distinctions with Respect to Nanomaterials and Nanodevices

Some materials can be produced by alternate means, some of which are bottom-up, some of which are top-down approaches. For instance, carbon nanotubes can be synthesized in an arguably top-down approach from graphite sheets in an arc oven or can be grown bottom-up, by a metal-catalyzed polymerization method [10.31]. Additionally, not all finished materials can be classified as either top-down or bottom-up: synthetic protocols can contain both steps. For instance, while proteins are synthesized from lower molecular weight amino acid precursors by chemically or biologically mediated polymerization (bottom-up), they are often made as precursor molecules that are processed to a final product by chemical or enzymatic cleavage (top-down, see [10.32] for an overview). While the question of whether any given material is made top-down or bottom-up can be ambiguous, the synthetic provenance of multicomponent nanodevices can be even more so. In analogy to biogenic materials, synthetic polymers are bottom-up materials per se, but fabrication of raw polymeric materials into final device architectures often involves top-down steps [10.33]. As we will see, therapeutic nanodevices frequently contain both synthetic and biologic components, and strict top-down and bottom-up categorization of these devices is often not applicable.

10.3 Technological and Biological Opportunities

This section considers selected enablers for therapeutic nanodevices. Some are purely technological: nanomaterial self-assembly properties, bioconjugation methods, engineered polymers for conditional release of therapeutics, external triggering strategies, and so forth. Others relate to disease-state tissue or cell-specific biology that can be exploited by nanotherapeutics, such as the emerging vascular address system and intrinsic triggering approaches. In association with those applications, we will consider additional biological opportunities for nanoscale approaches specific to particular disease states.

10.3.1 Assembly Approaches

Assembly of components into devices is amenable to multiple approaches. In the case of devices comprising a single molecule or processed from a single crystal (some microfabricated structures, single polymers, or grafted polymeric structures) assembly may not be an issue. Integration of multiple, separately microfabricated components may sometimes be necessary (as in the immunoisolation capsule discussed below) and may sometimes drive the need for assembly, even for silicon devices. Furthermore, many therapeutic nanodevices contain multiple, chemically diverse components that must be assembled precisely to support their harmonious contribution to device function.

"One off" Nanostructures and Low Throughput Construction Methods

Direct-write technologies can obtain high (nanometer scale) resolution. For instance, electron-beam (e-beam) lithography is a technique requiring no mask, and that can yield resolutions on the order of tens of nanometers, depending on the resist materials used [10.34]. Resolution in e-beam lithography ultimately is limited by electron scattering in the resist and electron optics, and like most direct-write approaches, e-beam lithography is limited in its throughput. Parallel approaches involving simultaneous writing with up to 1,000 shaped e-beams are under development [10.34] and may mitigate limitations in manufacturing rate.

Force microscopy approaches utilize an ultrafine cantilever tip (typically with point diameters of 50 nm or less, Fig. 10.6) in contact with, or tapping, a surface or a stage. The technique can be used to image molecules, to analyze molecular biochemical properties (like ligand-receptor affinity [10.35]), or to manipulate materials at nanoscale. In the latter mode, force microscopy has been used to manipulate atoms to build individual nanostructures since the mid-1980s. This has led to construction of structures that are precise to atomic levels of resolution (Fig. 10.6), though the manufacturing throughput of "manual" placement of atoms by force microscopy is limited.

Dip-pen nanolithography (DPN) is a force microscopy methodology that can achieve high resolution features (features of 100 nm or less) in a single step. In DPN, the AFM tip is coated with molecules to be deployed on a surface, and the molecules are transferred from the AFM tip to the surface as the coated tip contacts it. DPN also can be used to functionalize surfaces with two or more constituents and is well suited for deployment of functional biomolecules on synthetic surfaces with nanoscale precision [10.36, 37]. DPN suffers the limitations of synthetic throughput typical of AFM construction strategies.

Much as multibeam strategies might improve throughput in e-beam lithography [10.34], multiple tandem probes may increase assembly throughput for construction methods that depend on force microscopy significantly, but probably not sufficiently to allow manufacture of bulk quantities of nanostructures, as will likely be needed for consumer nanotherapeutic devices. As standard of care evolves increasingly toward tailored courses of therapy [10.38] and individual therapeutics become increasingly multicapable and powerful, however, relatively low throughput synthesis/assembly methods may become more desirable. For the moment, though, ideal manufacturing approaches for nanotherapeutic devices resemble either industrial polymer chemistry, occurring in bulk, in convenient buffer



Fig. 10.6 (a) A schematic depiction of an atomic force microscope cantilever and tip interacting with materials on a surface. Tips typically have points of 50 nm or less in diameter [10.31, 39]. **(b)** Schematic of multiplexed AFM tips performing multiple operations in parallel [10.31, 39]. **(c)** AFM image of a quantum corral, a structure built using AFM manipulation of individual atoms (from the IBM Image Gallery)

systems, or in massively parallel industrial microfabrication approaches. In any case, therapy for a single patient may involve billions of billions of individual nanotherapeutic units, so each individual nanotherapeutic structure must require only minimal input from a human synthesis/manufacturing technician.

Self-Assembly of Nanostructures

Self-assembly has been long recognized as a potentially critical labor-saving approach to construction of nanostructures [10.40], and many organic and inorganic materials have self-assembly properties that can be exploited to build structures with controlled configurations. Self-assembly processes are driven by thermodynamic forces and generally result in structures that are not covalently linked. Intra/intermolecular forces driving assembly can be electrostatic or hydrophobic interactions, hydrogen bonds, and van der Waals interactions between and within subunits of the self-assembling structures and the assembly environment. Thus, final configurations are limited by the ability to "tune" the properties of the subunits and control the assembly environment to generate particular structures.

Self-Assembly of Carbon Nanostructures

Carbon nanotubes (Fig. 10.7) spontaneously assemble into higher order [10.31] structures (nanoropes) as the result of hydrophobic interactions between individual tubes. Multi-wall carbon nanotubes (MWCNT) are well-known structures that can be viewed as self-assembled, nested structures of nanotubes with tube diameters decreasing serially from the outermost to innermost tubes. The striking resemblance that MWCNT have to macroscale bearings has been noted and exploited [10.41]. MWCNT linear bearings can be actuated by application of mechanical force to the inner nanotubes of the MWCNT assembly. Actuation causes the assembly to undergo a reversible telescoping motion. Interestingly, these linear MWCNT bearings exhibit essentially no wear as the result of friction between bearing components.

C_{60} fullerenes and single wall carbon nanotubes (SWCNT) also spontaneously assemble (Fig. 10.7) into higher order nanostructures called "peapods" [10.42] in which fullerene molecules are encapsulated in nanotubes. The fullerenes of peapods modulate the local electronic properties of the SWCNT in which they are encapsulated and may allow tuning of carbon nanotube electrical properties. The potentially fine-level control of nanotube properties may prove useful in nanotube-containing electrical devices, particularly in cases wherein nanotubes are serving as molecular wires. In this capacity, carbon nanotubes have been incorporated into FETs (field effect transistors, discussed below under sensing architectures [10.43]), and other molecular electronic structures. Ultimately, these architectures may result in powerful, ultra-small computers to provide the intelligence of "smart," indwelling nanotherapeutic



Fig. 10.7a–d **(a)** Shown to scale are two highly defined carbon nanostructures: a C_{60} fullerene and (10, 10) single wall carbon nanotube (SWCNT). **(b)** A self-assembled nanorope composed of carbon nanotubes that assemble by virtue of hydrophobic interactions [10.31,39]. **(c)** Schematic depiction of another self-assembled carbon nanostructure (a peapod) consisting of the fullerenes and SWCNT of 7a, and wherein the fullerenes are encapsulated in the SWCNT [10.42]. Fullerene encapsulation in the peapods modulates local electronic properties of the SWCNT. **(d)** A nanotube field effect transistor (FET) consisting of gold source and drain electrodes on an aluminum stage with a carbon nanotube serving as the FET channel [10.43]

devices. In general, though, fullerenes, nanotubes carbon nanoropes, nanotube bearings, and peapods have yet to find extensive biological application, in part because of their extreme hydrophobicity, presumably poor biocompatibility, and high chemical stability [10.31, 39]. But controlled derivatization of nanotubes may be possible through a number of approaches [10.31, 39] including controlled introduction of bond strain to render individual carbons of the tubes selectively chemically reactive (so-called mechanosynthesis). Carbon nanotubes and fullerenes, however, owe many of their remarkable properties (chemical stability, mechanical robustness, some electrical properties) to the fact that all the valences of the constituent carbon atoms (except those at the ends of nanotubes that are "open") are satisfied. Thus, to derivatize carbon nanostructures is to degrade them, a fact one must consider when the design purposes that drove incorporation of carbon structures into a therapeutic depends on the chemical perfection of the material.

Self-Assembly of Materials Made by Traditional Polymer Chemistry

In the realms of drug delivery and biomedical micro and nanodevices, the most familiar self-assembled structures are micelles [10.44–46]. These structures are formed from the association of block co-polymer subunits (Fig. 10.8), each individual subunit containing hydrophobic and hydrophilic domains. Micelles spontaneously form when the concentration of their subunits exceeds the critical micelle concentration (cmc) in a solvent in which one of the polymeric domains is immiscible (Fig. 10.8). The cmc is determined by the immiscible polymeric domain and can be adjusted by control of the chemistry and length of the immiscible domain, as well as by control of solvent conditions. Micelles formed at low concentrations from low-cmc polymers are stable at high dilution. Micelles formed from polymer monomers with high cmcs can dissociate upon dilution, a phenomenon that might be exploited to control release of therapeutic cargos. If desired, micelles can be stabilized by covalent cross-linking to generate shell-stabilized structures [10.44–47].

The size dispersity and other properties of micelles can be manipulated by control of solvent conditions, incorporation of excipients (to modulate polymer packing properties), temperature, and agitation. From the standpoint of size, reasonably monodisperse preparations (polydispersity of 1–5%) of nanoscale micellar structures can be prepared [10.44–47]. The immense versatility of industrial polymer chemistry allows micellar structures to be tuned chemically to suit the task at hand. They can be modified for targeting or to support higher order assembly properties. They can be made to imbibe therapeutic or other molecules for delivery and caused to dissociate or disgorge themselves of payloads at desired times or bodily sites under the influence of local physical/chemical conditions. The tunability of these and other properties at the level of monomeric polymer subunits as well as the level of assembled higher order structures make micelles potentially powerful nanoscale drug delivery and imaging vehicles.

Fractal materials, such as dendritic polymers, whose synthesis and structure were discussed previously, exhibit packing properties that can be exploited to assemble higher order aggregate structures called "tecto(dendrimers)" [10.48]. In fact, these self-assembly properties are being exploited in oncological nanotherapeutics as Fig. 10.3 shows [10.15, 49]. In principle, these self-assembling therapeutic complexes need not be pre-formed prior to administration. Individual functional modules of the therapeutic assembly might be administered sequentially, potentially to tailor therapies more precisely to individual patient responses.

Stoichiometric Control and Self-Assembly

As the preceding examples demonstrate, self-assembly approaches sometimes do not feature precise control of subunit identity and stoichiometry in the assembled complexes. This can be a limitation when the stoichiometry and relative arrangement of differentiable individual subunits is critical to device function. Stoichiometry is less an issue when the self-assembling components are identical and functionally fungible, as in the synthetic, peptidyl anti-infective illustrated in Fig. 10.9 [10.50,51].

In the anti-infective architecture, individual peptide components are flat, circular molecules. The planar character of the toroidal subunits is a consequence of the alternating chirality of alternating D-L amino acids (aas) in the primary sequence of the peptide rings. Alternating D and L aas is not possible in proteins made by ribosomal synthesis [10.32]. Ribosomes recognize and incorporate into nascent polypeptides only L amino acids, and so, as the result of aa chirality and bond strain, peptides made by ribosomes cannot be made flat, closed toroids like those of the peptidyl anti-infectives. Much as in α-helical domains of ribosomally synthesized proteins, however, the aa R-groups (which are of varying hydrophobic or hydrophilic chemical specificities [10.32]) are arranged in the plane of the closed D, L rings extending out from the center of the rings. Hydrogen bonds between individual rings govern self-assembly of the toroids into rod-like stacks, while the R-groups dominate interactions between multiple stacks of toroids and other macromolecules and structures (see below).

The planar toroidal subunits can be administered as monomers and self-assemble into multi-toroid rods at the desired site of action (in biological membranes). But the peptide toroids R-groups are chemically tuned so that the rod structures into which they spontaneously assemble intercalate preferentially in specific lipid bilayers (i. e., in pathogen vs. host membranes). Moreover, the assembled rods may undergo an additional level of self-assembly into multi-rod structures, spanning pathogen membranes [10.50, 51]. Whether as single rod or multiple rod assemblies, membrane intercalation by stacked toroids reduces the integrity of pathogen membranes selectively, and therefore particular toroid species exhibit selective toxicity to specific pathogens.

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004


a)
H_2O
H_2O
H_2O
H_2O
b)
Dialysis against water
Polymer and drug in organic solvent
c)
organic solvent
Evaporation
Polymer in water
Hydrophilic block
Hydrophobic block
Block copolymer
Drug
d)
Incorporation in micelles (arb. units)
25
20
15
10
5
0
–10
–9
–8
–7
–6
–5
–4
–3
Log concentration

Fig. 10.8a–d Micellar drug delivery vehicles and their self-assembly from block copolymers [10.44–46]. **(a)** Morphology of a micelle in aqueous buffer. Hydrophobic and hydrophilic polymer blocks, copolymers containing the blocks, micelles generated from the block copolymers, and (hydrophobic) drugs for encapsulation in the micelles are indicated. **(b)** Micelle self-assembly and charging with drug occuring simultaneously when the drug-polymer formulation is transitioned from organic to aqueous solvent by dialysis. **(c)** Pre-formed micelles can be passively imbibed with drugs in organic solvent. Organic solvent is then removed by evaporation, resulting in compression of the (now) drug-bearing hydrophobic core of the micelle. **(d)** An illustration of concentration-driven micelle formation. At and above the critical micelle concentration (cmc), block copolymer monomers assemble into micelles, rather than exist as free block copolymer molecules. The *arrow* indicates the cmc for this system



Fig. 10.9 A self-assembling peptide antibiotic nanostructure [10.50, 51]. Peptide linkages and the α-carbons and their pendant R groups are indicated. The synthetic peptide rings are planar as the result of the alternating chirality (D or L) of their amino acid (aa) constituents. R groups of aas radiate out from the center of the toroid structure. Individual toroids self-assemble (stack) as the result of hydrogen bonding interaction between amine and carboxy groups of the peptide backbones of adjacent toroids. The surface chemistry of multi-toroid stacks is tuned at the level of the aa sequence and, therefore, R group content of the synthetic peptide rings. The chemical properties of the stacked toroid surfaces allow them to intercalate into the membranes of pathogenic organisms with lethal consequences. The specific membrane preferences for intercalation of the compound are tuned by control of R group content of torroids

These toroidal, synthetic antibiotics, and other nanoscale antimicrobials represent critically needed, novel antibacterial agents. Resistance to traditional, microbially derived antibiotics often is tied to detoxifying functions associated with secondary metabolite synthesis; these detoxifying functions are essential for the viability of many antibiotic producing organisms (for instance, see [10.52]). The genes encoding such detoxifying functions are rapidly disseminated to other microorganisms, accounting for the rapid evolution of drug resistant organisms that has bedeviled antimicrobial chemotherapy for the last 25 years. Synthetic nanoscale antibiotics, like the peptide toroids [10.50, 51] and the N8N antimicrobial nanoemulsion [10.53], act by mechanisms entirely distinct from those of traditional secondary metabolite antibiotics, and no native detoxifying gene exists. Therefore, novel nanoscale antimicrobials may not be subject to the unfortunately rapid rise in resistant organisms associated with most secondary metabolite antibiotics, though this remains to be seen. As bacterial infection continues to re-emerge as a major cause of morbidity and mortality in the developed world, consequence of increasing antibiotic-resistant pathogens, novel nanoscale antibiotics will become more important.

Biomolecules in Therapeutic Nanodevices: Self-Assembly and Orthogonal Conjugation

Biological macromolecules undergo self-assembly at multiple levels, and like all instances of such construction, biological self-assembly processes are driven by thermodynamic forces. Some biomolecules undergo intramolecular self-assembly (as in protein folding from linear peptide sequences, Fig. 10.10). Higher order structures are, in turn, built by self-assembly of smaller self-assembled subunits (for instance, structures assembled by hybridization of multiple oligonucleotides, enzyme complexes, fluid mosaic membranes, ribosomes, organelles, cells, tissues, etc.).

Proteins are nonrandom copolymers of 20 chemically distinct amino acid (aa) subunits [10.32]. The precise order of aas (i. e., via interactions between aa side chains) drives the linear polypeptide chains to form specific secondary structures (the α helices and β sheet structures seen in Fig. 10.10). The secondary structures have their own preferences for association, which, in turn, leads to the formation of the tertiary and quartenary structures that constitute the folded protein structures. In its entirety, this process produces consistent structures that derive their biological functions from strict control of the deployment of chemical



Fig. 10.10a,b Self-assembly and biological macromolecules **(a)** Linear peptide chains (with amino and carboxy ends, as well as sulfhydral groups of cysteine residues indicated) undergoe a multistep folding process that involves the formation of secondary structures (α-helices, indicated by heavy helical regions, and β-sheet regions, indicated by the heavy anti-parallel arrows) that themselves associate into a tertiary structure. Final conformation is stabilized by the formation of intrachain disulfide linkages involving cysteine thiol groups. **(b)** A fluorescence transfer device that depends on self-assembly of biomolecules. The device is composed of donor (D) and acceptor (A) molecules brought into close proximity (within a few angstroms) by the base pair hybridization of complementary oligonucleotides. When the structure is assembled, acceptor and donor are energetically coupled, and fluorescence transfer can occur [10.54–57]

specificities (the aa side chains) in three-dimensional space.

Biomolecules can be used to drive assembly of nanostructures, either as free molecules or conjugated to heterologous nanomaterials. For instance, three-dimensional nanostructures can be made by DNA hybridization [10.54–57]. Such DNA nanostructures can exhibit tightly controlled topographies but limited integrity in terms of geometry [10.57], due to the flexibility of DNA strands. Oligonucleotides, antibodies and other specific biological affinity reagents can also be used to assemble nanostructures (Fig. 10.10, see also targeting and triggering discussions below). Often the domains of biomolecules responsible for assembly and recognition are small, continuous, and discrete enough that they can be abstracted from their native context as modules and appended to other nanomaterials of interest to direct formation of controlled nanoscale architectures (for instance, see the SCFv antibody fragement of Fig. 10.1).

Several orthogonal bioconjugate approaches have arisen from the field of protein semisynthesis [10.20, 58, 59]. These protein synthetic chemistries allow site-specific conjugation of polypeptides to heterologous materials in bulk, as the result of conjugation between exclusively, mutually reactive electrophile-nucleophile pairs (analogous to dendrimer synthesis discussed above, see Table 10.2). They have been applied to the synthesis of multiple therapeutic nanodevices [10.2–5, 7, 14, 58, 59].

As described above, proteins are profoundly dependent on their three-dimensional shapes: chemical derivatization at critical aa sites can profoundly impact protein bioactivity. Because conjugation can be directed to pre-selected sites via orthogonal approaches, and since the sites of conjugation in the protein can be chosen because the proteins involved tolerate adducts at those positions, proteins coupled to nanomaterials by such orthogonal methodologies often retain their

Table 10.2 Orthogonal conjugation chemistries originally derived for protein semi-synthesis but applicable to conjugation of proteins to nanomaterials [10.20, 58, 59] (R′ = H: Aldehyde, R = alkyl: Ketone)

	Electrophile		Nucleophile		Product
1.		+	H_2N-O-R''	⟶	
			Aminooxy		Oxime
2.		+		⟶	
			Hydrazide		Hydrazone
3.		+		⟶	
			Thiosemicarbazide		Thiosemicarbazone
4.		+		⟶	
			β-Aminothiol		Thiazolidine
5.		+		⟶	
	Thiocarboxylate		α-Halocarbonyl		Thioester
6.		+	 $H_2N-\underset{S^-}{\underset{\vert}{CH}}-\overset{O}{\overset{\Vert}{C}}-R$	⟶	 $R-\overset{O}{\overset{\Vert}{C}}-NH-\underset{SH}{\underset{\vert}{CH}}-\overset{O}{\overset{\Vert}{C}}-R'$
	Thioester		Cysteine		Amide

biological activity. In contrast, protein bioactivity in conjugates generally is lost or profoundly impaired when proteins are coupled to nanomaterials using promiscuous chemistries. For instance, proteins such as cytokines (and other protein hormones) elicit their effects by interacting with a receptor, and a large fraction of their surface (20% or more) is involved in receptor binding, directly or indirectly. Promiscuous chemistries (1-ethyl-3-(3-diamethylaminopropyl) carbodiimide or EDC, conjugation, see [10.60]) used to conjugate cytokines to nanoparticles tend to inactivate hIL-3 and other cytokines whereas the same protein/particle bioconjugates retain bioactivity if judiciously chosen orthogonal conjugation strategies are used (Lee & Parthasarathy, unpublished). Proteins for which only a small portion of their surfaces contribute to the interesting portions of their bioactivities (from the standpoint of the nanodevice designer), such as some enzymes or intact antibodies (Fig. 10.1) may be somewhat less sensitive to promiscuity of the bioconjugate strategy used [10.20, 58, 59], but the benefits of orthogonal conjugation strategies can also apply to these protein bioconjugates [10.20, 58, 59]. The potential utility of orthogonal conjugation for incorporation of active biological structures into semi-synthetic nanodevices is becoming more fully recognized and cannot be overestimated [10.58, 59].

10.3.2 Targeting: Delimiting Nanotherapeutic Action in Three-Dimensional Space

Delivery of therapeutics to sites of action is a key strategy to enhance clinical benefit, particularly for drugs useful within only narrow windows of concentration because of their toxicity (i. e., drugs with narrow therapeutic windows). Diverse targeting approaches are available, ranging from methods exploiting differential extravasation limits of vasculature of different tissues (see the discussion of oncology below), sizes, and surface chemistry preferences for cellular uptake (see discussion of vaccines below); preferential partition of molecules and particles into specific tissues by virtue of their charges, sizes, surface chemistry, or extent of opsonization (see below); or the affinity of biological molecules decorating the nanodevice for counter-receptors on the cells or tissues of interest.

The Reticuloendothelial System and Clearance of Foreign Materials

Physical properties such as surface chemistry and particle size can drive targeting of nanomaterials (and presumably nanodevices containing them) to some tissues. For instance, the pharmacokinetic (P_k) and biodistribution (B_d) properties [10.32] of many drugs and nanomaterials are driven by their clearance in urine, which is in turn governed by the filtration preferences of the kidney. Most molecules making transit into urine have masses of less than 25 to 50 kilodaltons (kDa; 25–50 kDa particles corresponding *loosely* to effective diameters of about 5 nm or less) and are preferably positively charged; these parameters are routinely modulated to control clearance rates of administered drugs. Clearance of low molecular weight (nano)materials in urine can be suppressed by tuning their molecular weights and effective diameters, typically accomplished by chemical conjugation, to polymers such as poly(ethylene glycol) [10.19]. Polymer conjugation (pegylation) has been applied to many different materials and may provide some degree of charge shielding. Pegylation also increases effective molecular weights of small materials above the kidney exclusion limit, diverting them from rapid clearance in urine.

Coating foreign particles with serum proteins (opsonization [10.61]) is the first step in the clearance of foreign materials. Opsonized particles are recognized and taken up by tissue dendritic cells (DCs) and specific clearance organs. These tissues (thymus, liver, and spleen, constituting the organs of the reticuloendothelial system or RES) extract materials from circulation by both passive diffusion and active processes (receptor-mediated endocytosis). Charge-driven, receptor-mediated uptake of synthetic nanomaterials occurs in the RES and can result in partition of positively charged nanoparticles into the RES. For instance, PAMAM dendritic polymers exhibit high positive charge densities related to the large number of primary amines on their surfaces [10.28–30]. In experimental animals, biodistribution of unmodified PAMAM dendrimers is limited nearly exclusively to RES organs [10.62]. This unfavorable biodistribution can be modulated by "capping" the dendrimers (i. e., derivatizing the dendrimer to another chemical specificity, such as carboxy or hydroxyl functionalities [10.15, 62]).

Despite legitimate applications of targeting to the kidney and the RES (for instance in glomerular disease [10.63]), intrinsic targeting to clearance sites is of interest primarily as a technical problem that impedes therapeutic delivery to other sites. In such cases, numerous targeting strategies are available, some of which depend on synthetic nanomaterial properties (for instance, see discussion of the enhanced permeability and retention or EPR effect in the context of oncology, below) to minimize uptake of nanotherapeutic devices by clearance systems and maximize delivery to desired sites. Targeting via biological affinity reagents decorating the surfaces of therapeutic nanodevices may be the most direct approach.



Fig. 10.11 (a) A schematic of a filamentous phage particle encapsulating DNA encoding a gene of interest (your favorite gene, or yfg) and presenting the corresponding protein (your favorite protein or yfp) on its surface. The linkage between yfp and yfg provided by the phage allows simultaneous affinity isolation and recovery of proteins of interest along with replicable genetic elements encoding them. When variant protein libraries are built by this method, they can be sorted for their ability to bind receptors by affinity. **(b)** A library of filamentous phage presenting random peptides is shown schematically. The library is injected into the vasculature of an animal (in this case, a mouse), where individual phage bind specific receptors present in the vasculature of different tissues. The animals are sacrificed, and organs of interest are harvested. Phage particles bound to receptors of vasculature of the organ at hand can be eluted by any of several methods (low pH elution is schematically shown here). *E. coli* is infected with the eluted phage particles and clonally propagated, allowing identification of the peptides encoded by the eluted phage, which mediated binding to the vascular receptors. Ultimately, this allows the identification of consensus peptide sequences that recognize specific receptors on the vasculature of the organ or tissue involved. These receptors constitute the molecular addresses for these organs, and the peptides isolated from phage eluted from them are biological affinity reagents that can be used to direct nanotherapeutic devices to vasculature of particular organs. **(c)** Specific recognition of vascular beds of two distinct tissues (A and B) via recognition of organ-specific vascular addresses (the Y and box-shaped receptors shown on vascular endothelium) by specific peptides (the *triangle* and the *square*) presented on the phage surface is depicted [10.64–66]

Nanotherapeutic Targeting Exploiting Biological Affinity Properties

Tissue-specific delivery by biological affinity requires the presence of tissue-specific surface features, most commonly proteins or glycoproteins (tissue-specific antigens). Historically the search for tissue-specific antigens for drug targeting, whether associated with tumors or other cells, organs or tissues, has been arduous and not entirely gratifying. The primary problems are specificity (few antigens are uniquely present in any single tissue), availability (some tissues may not have their own unique antigenic signature or marker), and therapeutic extravasation or directed migration in tissue spaces (markers in tissue may not be accessible from vasculature). An exciting recent development in biochemical targeting is the discovery of a vascular address system [10.64–66].

The vascular address system has been characterized by administering a peptide phage display to library animals, resecting individual organs, and extracting phage from the vasculature of the isolated organs (Fig. 10.11 [10.64–66]; see [10.67] for a discussion of display technology). Amazingly, phage isolated from different organs exhibited distinct consensus presented peptide sequences, indicating that the vasculature of individual organs presented unique cognate receptors, each bound by a different short (ten amino acids or fewer) consensus peptide sequence that had been affinity selected from the phage display library. Furthermore, the affinity-selected peptides have the capacity to tether nano- to microscale particles to the site of their cognate receptors (as illustrated by the binding phage particles presenting the peptides to specific vascular locations). Site-specific drug delivery using the vascular address system has already been demonstrated [10.68,69]: it has further been used to target an apoptotic (cytocidal) agent to the prostate and to direct destruction of the organ in an animal model [10.68].

Mapping of the vascular address system is currently underway [10.64] and holds the promise of specific delivery of therapeutic agents to vasculature of specific organs. It remains to be seen whether each organ has a single molecular marker constituting its address that is amenable to binding a single peptide sequence; organs may instead have unique constellations of antigenic markers. If so, specific targeting may be possible using multiple peptides, each peptide binding its cognate receptor on target organ vasculature very weakly. Peptides used in such a multivalent targeting strategy would be chosen to reflect the unique constellation of address markers present in the target tissue. Affinities of cognates for linear peptides are often very low [10.67], though their aggregate affinity may be substantially higher than that of any peptide-vascular address cognate alone. Under ideal conditions, the affinity of such a multipeptide, multicognate complex should be the equivalent of the products of the affinities of each constituent peptide for its individual constituent cognate. Such multivalent interaction avidities can be extremely high (and the corresponding effective affinity constants are also high) but seldom fully realize their theoretical maximums (Lee & Parthasarathy, unpublished; see [10.32] for a review of receptor biochemistry).

It should be noted that most of the vascular addresses identified to date deliver materials to the organ vasculature: extravasation and access of organ tissue spaces by nanotherapeutics remains a separate issue.

10.3.3 Triggering: Delimiting Nanotherapeutic Action in Space and Time

Controlled triggering of therapeutic action is the other side of the targeting coin. If the site and time of nanotherapeutic delivery cannot be adequately controlled, the site of therapeutic action can be delimited by spatially- or temporally-specific triggering. The triggering event might drive release of active therapeutic from a reservoir, or chemical or physical processing of drug materials from an inert to an active form (inert administrations that are converted to active form at a specific time or place drugs which are activated by a chemical reaction occurring their sites of action are called prodrugs, Fig. 10.12). Three major triggering strategies are widely used: external stimuli, intrinsic triggering, and secondary signaling (multicomponent systems). Triggering strategies require nanotherapeutic delivery devices to be sensitive to a controlled triggering event, or a spatially/temporally intrinsic triggering event mediated by the host. Obviously, the triggering event itself must be tolerable to the patient.



Fig. 10.12 One possible configuration of a prodrug, in which carrier/trigger and effector functions are separate functional domains of the therapeutic. The key feature of prodrugs is that they are therapeutically inert (as indicated by the colorless effector domain) until an activation event occurs (mediated here through the carrier/trigger domain, with effector activation indicated by its change to a star shape). Activation events can involve cleavage of inhibitory carrier/trigger domains from effectors. Other activation strategies involve a chemical change or shift in conformation of the effector, mediated through the carrier/trigger domain and in response to an environmental condition

Nanotherapeutic Triggering Using External Stimuli

External stimuli are provided by an external nanodevice operator/clinician, usually in the form of a site-specific energy input, typically light, ultrasound, or magnetic or electrical fields. Organic polymeric structures are very amenable to interaction with these energy sources. For instance, micellar structures can be reversibly dissociated with ultrasound, in which case they disgorge their contents or expose their internal spaces to the environment during ultrasound pulses (20 to 90 kilohertz range). The process has been used to control release of cytotoxin (doxorubicin) from micelles (Fig. 10.13), and short ultrasound transients might be used for pulsatile or intermittent exposure of patients to therapeutics [10.70].

Light is another popular external triggering modality. Bioactive materials can be covalently associated to a nanoscale-delivery vehicle by photo-labile linkages [10.15, 71, 72], or micelles can be constructed so that their permeability is altered as the result of exposure to light [10.72]. In the latter case, light input can cause photopolymerization resulting in micelle compaction that drives release of therapeutic cargo or photo-oxidation, which causes loss of micellar integrity to release encapsulated materials. The ability of light to penetrate dense tissues is a clear limitation to this approach. This concern can be accommodated by polymer systems responsive to wavelengths that penetrate tissue efficiently (usually in the red-infrared region of the spectrum), or by use of systems such as fiber optics to deliver light to deep tissues [10.15, 71, 72].

Externally applied magnetic fields can also be used to control nanotherapeutic activity. For instance, eddy currents induced by alternating magnetic fields can heat nanometallic particles and their immediate vicinity, an approach that has been successfully applied to control the bioactivity of individual biological macromolecules [10.73]. Colloidal gold particles are covalently conjugated to biomolecules (nucleic acid, or NA, duplexes or proteins), and alternating magnetic



Fig. 10.13 Externally applied stimuli can trigger drug release: hydrophobic drug molecules are reversibly deployed from micelles in response to acoustic stimuli [10.70]. Intact pluronic micelles maintain the hydrophobic cytotoxin doxorubicin in a hydrophobic environment (the core of the micelle, as in Fig. 10.4). Doxorubicin fluorescence is quenched in aqueous environments, and hence changes in integrity of pluronic micelles carrying doxorubicin can be monitored by doxorubicin fluorescence. Here, an ultrasound pulse is applied to suspensions of such micelles or to doxorubicin in solution. Application of ultrasound triggers exposure of micelle-encapsulated doxorubicin to the aqueous solvent (i. e., drug release), as demonstrated by the reduction in fluorescence. After cessation of the acoustic pulse, doxorubicin is repackaged into the micelles, as evidenced by the increase in fluorescence after the ultrasound administration (*Line* a). Ultrasound has no impact on fluorescence of doxorubicin in solution, as expected (*Line* b)

fields are used to induce heating sufficient to cause dissociation of hybridized NA structures or denaturation of protein three-dimensional structures. Within certain parameters, the process is reversible and so allows the construction of semi-biological assembly or release switches. The modality has clear application to temporally specific triggered release, but the current inability to direct magnetic fields to pre-selected tissue locations may limit its use for spatially specific triggering.

Nanotherapeutic Triggering by Intrinsic Physiological Conditions

Intrinsic triggering is a prodrug strategy that depends on the conditions at the desired site of action to trigger the activity of the nanotherapeutic. Much as the three-dimensional conformation of, and therefore the activity of, proteins can be controlled in external triggering strategies [10.73], proteins can be engineered to make their conformations sensitive to intrinsic conditions at their desired sites of activity (see [10.3] for a discussion of protein engineering for use in nanobiotechnological devices). For instance, noncovalent complexes of a diphtheria toxin (DT) protein variant and a bispecific antibody (Fig. 10.1) have been engineered for specific toxicity to cells that can take up the complexes [10.75]. The bi-specific antibody recognizes both a cell-specific surface receptor as well as the DT in an inactive (nontoxic) configuration. Antibody binding to the receptor results in receptor-mediated endocytosis of the complex in target cells. As a result of the lower pH of the endosomal compartment (reaching pH 4–5 in endosomes, as opposed to the constant pH 7–8 in circulation) into which the bound complex is taken up, the DT variant protein undergoes a three-dimensional conformational shift to its toxic form. This conformation of DT is not recognized by the bispecific antibody, so the toxin dissociates from the complex and kills the cell. Hypoxia-triggered prodrugs have also been developed that are activated either by chemical reduction or by enzymatic activities induced in hypoxic tissues. Extreme hypoxia [10.76] is a unique feature of neoplastic tissue, so these strategies have clear application in oncology. Clinical manipulation of the extent of tumor oxygenation is possible [10.77] and may also be possible in other tissues. If so, redox state-dependent triggering approaches may have applications beyond cancer (Fig. 10.14a).

Enzyme-activated delivery (EAD [10.74], Fig.10.14) is another prodrug-like triggering strategy in which the properties of a nanoscale drug-delivery vehicle are altered at the site of action by an enzymatic activity endogenous to that site. Most typically, this involves a liposomal or micellar nanostructure from which designed pendent groups can be cleaved by metabolic enzymes (alkaline phosphatase, phospholipases, proteases, glycosidic enzymes, etc.) that are highly expressed at the site of therapy. Nanostructures are designed so that enzymatic cleavage of the pendent group causes a conformational or electrostatic change in the polymeric components of the delivery device, rendering the micellar structure fusogenic, leaky, or causing partial or complete dissociation of the structure [10.12] (Fig. 10.14c). This has the result of delivering or releasing therapeutic payloads at pre-selected sites.



Fig. 10.14 Intrinsic conditions at desired sites of therapeutic action can trigger release of active drug molecules. Enzyme activated delivery (EAD) is an intrinsic triggering strategy that depends on chemical cleavage of the carrier/trigger to induce changes in the properties of the delivery vehicle to allow delivery of drug [10.74]. Here a surface functionality is cleaved from a micellar drug delivery vehicle, rendering the micelle fusogenic and allowing it to fuse with the cell membrane. As a result, the therapeutic payload of the micelle is delivered to the cytosol of target cells. Tuning of micellar surface functionalities and their linkages to the block copolymers constituting micelles theoretically can be used as target delivery to a variety of intracellular compartments



Fig. 10.15a,b Secondary biochemical signals can trigger release of active therapeutics. **(a)** Antibody directed enzyme-prodrug therapy (ADEPT) exploits enxyme-monoclonal antibody (mAB) bioconjugates to activate prodrugs [10.78]. Here, a mAB (like the native IgG of Fig. 10.1) is covalently liked to a catalyst (C in rhombus, usually an enzyme). The binding specificity of the monoclonal antibody causes the bioconjugate to bind to a desired target site (possibly by recognition of a vascular address, as shown in Fig. 10.11). The catalyst (enzyme) specificity of the bioconjugate is capable of triggering activation of a prodrug, much as in Fig. 10.12. The corresponding prodrug is then administered (represented as in Fig. 10.12). The enzyme localized at the desired target site of therapeutic action then activates the prodrug (represented here by cleavage of carrier/trigger moiety and change in shape of the effector to a star, as in Fig. 10.12). **(b)** Another secondary signaling triggering strategy [10.55]. Here, single stranded nucleic acid (SSNA) drives assembly of an activating complex for a prodrug. A catalyst (indicated again by C) is conjugated to an oligonucleotide that hybridizes to a single stranded nucleic acid (SSNA). A prodrug, containing an effector domain (E) and a second oligonucleotide, in this case homologous to a region of the same SSNA, and proximal to the site of hybridization of the first oligonucleotide, is also administered. Catalyst specificity is tuned to correspond to linkage between the prodrug effector and oligonucleotide. The catalyst in the assembled structure is sufficiently close to the prodrug to cleave the linkage between effector and oligonucleotide, releasing active drug (star). Potentially, prodrug and catalyst oligonucleotides might dissociate from the SSNA and the cycle could be repeated. Note the similarity to Fig. 10.10

Nanotherapeutic Triggering Using Secondary Signaling

Secondary signaling or multicomponent delivery systems are more complex delivery strategies (Fig. 10.15). These systems can feature site-specific and systemic delivery of one or more components. One class of such systems is the so-called ADEPTS devices (antibody directed enzyme-prodrug therapy, Fig. 10.15 [10.78]). ADEPTS systems feature affinity-based targeting of an enzymatic prodrug activator to a desired site, followed by systemic administration of a prodrug. ADEPTS is used primarily for oncology, and so the prodrug involved is generally one that can be activated to cytotoxicity. Since prodrug dosing is systemic, prodrug toxicity must be de minimus in the inactive form, and the activating catalyst must not be present at locations where cytotoxicity would be deleterious. To address this issue, the nanotherapeutic designer can chose to engineer an activation mechanism that has no physiological analogue in the host. In addition, tuned, high lability of the active drug can potentially delimit the site and extent of cytotoxic effect mediated by ADEPTS systems.

Other secondary signaling systems rely on DNA hybridization to assemble therapeutic components into catalytically active complexes at their sites of action [10.55]: in this system, the individual components lack therapeutic activity until they are brought within a few nanometers of each other by hybridization to a target single-stranded nucleic acid molecule (SSNA in Fig. 10.15, potentially a RNA species expressed in a tissue or cell type of interest). At this point, the catalytic moiety and the prodrug moieties are sufficiently close in space to allow catalytic cleavage of the active component from the prodrug. As depicted, this strategy makes no provision for delivery of drug and catalyst bioconjugates to the site of interest, nor for their transit across biological membranes. The system is similar to the DNA hybridization-driven fluorescence transfer system of Fig. 10.10.

Alternatively, secondary signaling systems can exploit competitive displacement of therapeutics from a carrier structure [10.79]. In this case, a non-covalent complex of engineered antibody and plasminogen activator (PA) is tethered to blood and fibrin clots by antibody affinity for fibrin. PA is released from the bound complex (to dissociate the clot) using bolus systemic administration of a nontoxic binding competitor for PA to the antibody complex. The strategy establishes a high local concentration of PA at clot sites, efficiently dissolving clots and potentially minimizing systemic side effects.

Layering Strategies for Fine Control of Nanotherapeutic Action

It should be clear that many of these approaches may be broadly applicable to trigger events other than drug release or to drive assembly or disassembly of therapeutic nanostructures in situ. It should also be clear that these approaches are often complementary, and that multiple approaches can be used in single nanotherapeutic devices (Fig. 10.3, Table 10.1 [10.11–13, 15, 71, 78, 80]). Layering targeting and triggering approaches tends to make devices more complex, but it also allows clinician/operators to intervene at multiple points in therapy, potentially leading to finer control of the therapeutic process and better clinical outcomes.

10.3.4 Sensing Modalities

The need for "smart" therapy is a key theme of therapeutic nanotechnology and pharmacology as a whole. Drugs with narrow therapeutic windows should be delivered only to their desired site of action and be pharmacologically active only when that activity is needed. These strategies can limit undesired secondary effects of therapy, some of which can be debilitating or life threatening, as discussed elsewhere in this chapter. One possible approach to this issue is the incorporation of sensing capability (specifically, the capacity to recognize appropriate contexts for therapeutic activity) into nanotherapeutic devices. Sensing capability may allow self-regulation of a therapeutic device, reporting to an external clinician/device operator (though this begins to touch on imaging applications, see below), or both. In the context of our discussion of therapeutic nano- and microscale devices, we will consider primarily electrical and electrochemical sensor systems, particularly microfabricated (Field Effect Transistor or FET, and cantilever) and conducting polymer sensors.

Sensor Systems

Sensing is predominantly a higher-order device functionality, depending on multiple device components, though one could argue that some targeting/triggering strategies, particularly targeting by bioaffinity and intrinsic triggering strategies, must, a priori, incorporate at least limited sensing capability. But biosensors, as they are typically considered, are multifunctional, multicomponent devices [10.81]. Usually a biosensor system is composed of signal transducer, sensor interface, biological detection (bioaffinity) agent, and an associated assay methodology, with each system component governed by its inherent operational considerations.

The transducer component determines the physical size and portability of the biosensor system. Signal transducers are moieties that are sensitive to a physical-chemical change in their environment and that undergo some detectable change in chemistry, structure, or state as the result of analyte (the thing to be sensed) recognition. Analytes for nanotherapeutic application could be biomolecules, like proteins, small molecules (organic or inorganic), ions (salts or hydrogen ions), or physical conditions (such as redox state, temperature). Interfaces are the sensor components that interact directly with the analyte. For sensor use in nanotherapeutic devices, immobilized or otherwise captured biological molecules (proteins, nucleic acids) often constitute the sensor interface. Whatever the chemical nature of the interface, it determines the selectivity, sensitivity, and stability of the sensing system and also is a dominant determinant of sensor operational limits. Assay methodology determines the need (or lack thereof) for analyte tracers, the number of analytical reagents, and the complexity and rapidity of the sensing process. Nanotherapeutics are of interest at least in part because they can be minimally invasive, low complexity, yet robust and accurate; convenient assay methods are therefore highly desirable.

Cantilever Biosensors

Micromechanical cantilevers (discussed above in conjunction with force microscopy, Fig. 10.6) transduce sensed events by mechanical means [10.82]. Both changes in the resonant frequency and deflection of cantilevers resulting from analyte binding or dissociation can be conveniently and sensitively detected. These changes in cantilever state can be conveniently detected by optical, capacitive, interferometry, or piezoresistive/piezoelectric methods, among others. Microfabricated cantilever dimensions range from micron to sub-micron range, with potential for further dimensional optimization (by carbon nanotubes appended to them, for instance [10.82]). They are operationally versatile and can be used in air, vacuum, or liquid, although they suffer some degradation in performance in liquid media. Like most micromachined structures, they can be batch fabricated and conveniently multiplexed.

Cantilevers used in atomic force microscopy (AFM, see also discussion of one-off nanostructures above) approaches can be used to study individual biomolecular interactions [10.35, 81]. In this approach, cantilever tips are derivatized with biomolecules (effectively, one member of a receptor/counter-receptor pair), and the tip-bound biomolecule is allowed to bind its counter-receptor (itself bound on a surface). Under non-equilibrium conditions, (i. e., conditions that result in thermodynamically irreversible changes in analyte molecular structures), the force required to disrupt single molecular interactions can be measured and related to classical biochemical parameters of receptor binding. The method has been applied to interactions between hormones and their receptors, sugars and lectins, as well as hybridizing DNA strands.

Cantilever systems sensitively detect changes in mass at their surfaces: changes as small as a mass density of $0.67\,\mathrm{ng/cm^{-3}}$ are theoretically detectable. This can allow detection of binding of extremely small objects to the cantilever and has been applied to detection and enumeration of prokaryotic and eukaryotic cells, as well as small numbers of macromolecules [10.82]. The incorporation of biological receptors or affinity reagents on the cantilever surface can drive specific binding events for particular sensing tasks. Microcantilevers are also highly sensitive to temperature, detecting changes as low as 10^{-5} K; they can also detect small changes in pH.

Field Effect Transistor Biosensors

Field effect transistor (FET) architectures are another sensing architecture that can be conveniently produced by micro-nanofabrication. FETs consist of a current source, a current drain, a conductive path (sensing channel) between them, and a sensing gate to which a bias can be applied. Analyte binding to the sensing channel induces a charge transfer resulting in a dipole between the surface and the underlying depletion region of the semiconductor: current that passes between the source and drain of a semiconductor FET is quite sensitive to the charge state and potential of the surface in the connecting channel region. Moving a standard silicon FET from depletion to strong inversion (i. e., shifting the surface potential by $> \sim 0.5\,\mathrm{eV}$) requires less than $\sim 10^{-7}\,\mathrm{C/cm^2}$ or $\sim 6 \times 10^{12}$ charges/cm^2, corresponding to transfer of 6.25×10^{11} e/cm^2. With FETs of 2,000 square micrometers, detection of biological analytes in sub-nanomolar concentrations is easily feasible. Specificity for binding of macromolecular analytes of interest can be provided by deployment of biological affinity reagents in the FET sensing channel. Submicron FETs are routinely manufactured; use of carbon nanotubes in FETS will offer still greater miniaturization [10.43, 83].

Carbon nanotubes also have excellent mechanical properties and chemical stability in addition to potentially tunable electrical properties, making them highly desirable electrode/nanoelectrical materials for any number of nanoelectrical applications [10.84]. Biomolecules can be bound to carbon nanotubes, particularly in FET and nanoelectrode applications. Most biomolecules bound to carbon nanotubes are not covalently bound (as discussed above) and do not exhibit direct electrical communication with the nanotube, though redox enzymes bound to nanotubes and other conductive nanomaterials may [10.84, 85]. Flavin adenine dinucleotide (FAD) and flavoenyzme glucose oxidase (Gox) both display quasi-reversible one electron transfer when absorbed onto unannealed carbon nanotubes in glassy carbon electrodes. Gox so immobilized retains its substrate-specific (glucose) oxidative activity, leading to applications in sensing circulating glucose for diabetes and, perhaps, to a strategy of harvesting electrical power from metabolic energy.

Conducting Polymers and Sensor Biocompatibility

Biocompatibility of most metallic structures (as might be used in the bioelectrical sensors described) is limited at best; metal structures rapidly foul with serum proteins (i. e., become opsonized), undergo electrochemical degradation, or have other problematic properties. Polymer chemistry, however, has the capacity to tune composition to enhance biocompatibility properties and is commonly used to make synthetic surfaces more biologically tolerable. Electrically conductive polymers are potentially attractive in this context.

Polymeric materials are available with intrinsic conductivities comparable to that of metals (up to $1.5 \times 10^7\ (\Omega\,\mathrm{m})^{-1}$, which, by weight, is about twice that of copper [10.86]). Significant conductivity has been documented for a dozen or so polymers, including polyacetylene, polyparaphenylene, polypyrrole, and polyaniline, doped with various impurities. Careful control of doping can tune electrical conductivity properties over several orders of magnitude [10.87].

Conductive polymeric materials may be extremely well suited to biosensing applications. The polymeric materials themselves are often compatible with proteins and other biomolecules in solution. Furthermore, polymers are amenable to very simple assembly of sensor transducer-interface components by deposition of the polymer and trapped protein (sensor interface) directly on a metallic micro- or nanoelectrode surface [10.87,88]. Combined with a facile nanoelectrode array microfabrication method [10.89], simultaneous conducting polymer-interface protein deposition may offer an extremely simple way to fabricate multiplexed sensor arrays.

These electrochemical and electrophysical sensing modalities are of little use in and of themselves: they must communicate with either other device components (such as drug-dispensing effector components) or with external observers or operators. Sensor coupling in autonomously operating devices produced by microfabrication can be done directly, and the coupling linkages incorporated into the fabrication protocol. Coupling with biological device components can also be direct, as when conductive materials are conjugated to biomolecules, and can directly modulate their activity [10.73].

Sensor-device coupling can also be indirect, through electrochemically produced mediator molecules [10.85]. Sensors might be independent of nanotherapeutics and report conditions at the site of therapeutic action to an external operator, who would use any one of the external triggering strategies discussed above to engage therapy when and where appropriate. Communication/sensor interrogation might be accomplished most crudely by direct electrical wiring of sensors to an external observation station. Alternatively, if the event to be detected is transduced optically, as in colorimetric smart polymers that change optical properties in the presence of analyte [10.90], sensors might be interrogated by fiber optics. These modalities are most applicable to sensor arrays delivered to the site of interest by a catheter. The use of a catheter may be justified in some therapeutic applications, but it is an invasive procedure and is not optimal.

We have already seen multiple examples of prodrugs that are activated by cleavage of an inhibitory domain from the complex. One noninvasive approach to communication with external operators could exploit this phenomenon by detecting the cleaved fragment in bodily fluids. If the cleaved moiety cleared through urine, the extent of drug activation could be monitored noninvasively via urinalysis. There is no a priori need to connect the cleavage event to drug activation. For instance, an operator might administer a catalyst that cleaves a detectable material from a nanotherapeutic. If this secondary signaling moeity was independently targeted to the desired site of therapy, presence of the detectable cleaved product would provide information regarding the bodily location of the therapeutic nanodevice. The cleaved product would not be detectable unless the therapeutic and secondary signaling moiety co-localized at a single site. Other sophisticated communication involves ultrasound or electro-magnetic radiation to carry information. Application of these sorts of modalities currently occurs in in vivo imaging approaches.

10.3.5 Imaging Using Nanotherapeutic Contrast Agents

Imaging is a minimally invasive procedure that allows visualization of organs and tissues following the administration of a detectable moiety (contrast agent). The contrast agent is then exposed to some condition that interacts with the contrast agent so as to produce an emission or response detectable to an external monitoring device. Nano-sized particles (5–100 nm in diameter) have found application as contrast-enhancing agents for medical imaging modalities such as magnetic resonance imaging (MRI, our primary topic, reviewed in [10.91, 92]). MRI currently provides cross-sectional and volumetric images with high spatial resolution (< 1 mm) and is potentially applicable to many clinical purposes, though enhanced imaging capabilities are desirable. For instance, blood flow measurements of healthy and diseased arteries can be quantified better by the aid of improved contrast agents that highlight blood flow at the vessel wall. Similarly, some tissues (certain tumors) do not exhibit strong contrast within the MRI field and cannot be readily identified or characterized at present. It is of great interest, therefore, to develop nanoscale particles that provide enhanced contrast for many applications.

Magnetic Resonance Imaging (MRI): the Basics

Objects to be imaged are exposed to a strong magnetic field and a well-defined radio frequency pulse. The external magnetic field (B_0) serves to loosely align protons either with (lower energy level) or against (high energy level) the field, the difference between the two energy levels being proportional to B_0. Once the protons are separated into these two populations, a short multi-wavelength burst (or pulse) of radio frequency energy is applied. Any particular proton will absorb only the frequency that matches its particular energy (the Larmor frequency). This *resonance* absorption is followed by the excitation of protons from the low to high energy level and of equivalent protons moving from high to low energy levels. After the radio frequency pulse, protons rapidly return to their original equilibrium energy levels. This process is called relaxation and involves the release of absorbed energy. Once equilibrium is again established, another pulse can be applied.

Data is collected by positioning a receiver perpendicular to the transmitter: relaxation energy release induces a detectable, quantifiable signal (i. e., in amplitude, phase, and frequency) at the receiver coil. Since multiple protons in multiple chemical environments are involved, the signal at the receiver includes many frequencies. The received signal consists of multiple, superimposed signals (called the free induction decay or FID) signal, resulting from the relaxation of multiple, chemically distinct protons. FID is converted from the time domain to frequency domain (by Fourier transformation), within which individual proton types can be identified. Iterations of this procedure in two or three dimensions can create a high-resolution image of anatomical cross section or volume.

Intrinsic factors affecting image quality include the proton density of the tissues, local blood flow, and two relaxation time constants [10.93]: longitudinal relaxation time (T_1) and transverse relaxation time (T_2). Control of T_1 and T_2 relaxation effects are most critical for high-resolution MR images. T_1 relaxation measures energy transfer from an excited proton to its environment. In tissues, protons of fats and cholesterol molecules (relatively movement-constrained macromolecules) relax efficiently after a pulse and exhibit a short T_1 time. Water in solutions (a small molecule tumbling relatively freely in solution) has a much longer T_1 time. T_2 relaxation measures the duration of coherency between resonating protons after a pulse, prior to their return to equilibrium. Tightly packed, solid tissues with closely interacting hydrogen nuclei relax more quickly than loosely structured liquids, so tissues such as skeletal muscle have a short T_2s, while cerebrospinal fluid has a very long T_2. Intrinsic factors are manipulated through extrinsic factors, such as the external magnetic field strength, the specific pulse sequence, etc., allowing the collection of meaningful MR images.

Nanoparticle Contrast Agents

Signal intensity in tissue is influenced linearly by proton density, while changes in T_1 or T_2 result in exponential changes in signal intensity. T_1 and T_2, therefore, are manipulated to enhance imaging by administration of exogenous contrast-enhancing agents. MRI contrast agents are divided into paramagnetic, ferromagnetic, or superparamagnetic materials. Metal ion toxicity is an unfortunate consequence of physiologic administration of contrast agents but can be mitigated somewhat by complexation of the metals with organic molecules.

Paramagnetic metals used for enhanced MRI contrast (gadolinium, Gd, iron, Fe, chromium, Cr, and manganese, Mn) have permanent magnetic fields, though the magnetic moments of individual domains are unaligned [10.94]. Upon exposure to an external magnetic field, individual domain moments become aligned, generating a strong local field (up to 10^4 gauss [10.95]). Paramagnetic metal ions interact with water molecules, causing an enhanced relaxation of the water molecules via tumbling of the water-metal complex, dramatically decreasing the T_1 value for the water molecules and enhancing the proton signal [10.94]. Contrast enhancement by paramagnetics is thus due to the indirect effect the contrast agent has on water and its magnetic resonance properties.

Ferromagnetic and superparamagnetic materials both contain iron (Fe) clusters, which generate magnetic moments 10 to 1,000 times greater than do individual iron ions. Clusters greater than 30 nm in diameter are ferromagnetic, whereas smaller particles are superparamagnetic [10.93]. Ferromagnetic materials maintain their magnetic moment after the external field is removed, but superparamagnetic materials lose their magnetic field after the field is removed, as do paramagnetics. Both ferromagnetic and superparamagnetic substances minimize the proton signal by shortening T_2 [10.96], resulting in negative contrast (i. e., darkening of the image [10.97]).

Nanobiotechnological Contrast Agent Design

First generation contrast agents often contained a single metal ion/complex, whereas emerging agents incorporate nanoscale metal clusters, crystals, or aggregates, sometimes encapsulated within a synthetic or biopolymer matrix or shell [10.98–100]. These metal cluster agents improve contrast effects and, hence, output MR images profoundly. Furthermore, surface chemical groups (from the matrix or shell) can be derivatized to improve biocompatibility or allow targeting to a tissue or site of interest.

Typically particles are prepared from colloidal suspension where metallic cores are thoroughly mixed with the matrix material before being aggregated out of solution with a non-solvent. Dextran (a polymer of 1,6-β-D-glucose) is a typical matrix material used in commercial imaging reagents: Combidex is coated with 10,000 molecular weight dextran [10.99, 101, 102], Feridex has an incomplete, variable dextran coating [10.102], and Resovist is coated with carboxydextran [10.97]. Other polymeric materials are also used (oxidized starch [10.98, 100]), and matrix-less particles are also produced [10.103].

Nanoparticle contrast agents must be purified under tightly controlled conditions (generally by centrifugation or high pressure liquid chromatography [10.104]) and accurately characterized (for size dispersity by light scattering, chromatography, photon correlation, or electron microscopy [10.100, 104]) to assure the reproducibility of imaging agent production lots. Elemental analysis, X-ray powder diffraction, and Mössbauer spectroscopy have also been used to characterize metallic cores [10.103, 105]. Tight definition of the finished particles ensures accurate correlation between structural properties of imaged materials and prior in vitro and in vivo studies, allowing collection and interpretation of meaningful images. Metallic cores generally range from 4 to 20 nm in diameter [10.106], while coated particles can be up to 100 nm or more in diameter [10.105]. Compared to larger cores, however, nanoparticles less than 20 nm in diameter exhibit considerably longer blood half-life and improved T_1 and T_2 relaxivity effects [10.107].

As previously discussed, clearance of nanoparticles via the RES is a critical problem usually approached by surface modifications to mitigate nonspecific adsorption of proteins to the biomaterial surface (i. e., the opsonization of synthetic materials). Neutral, hydrophilic surfaces tend to adsorb less serum protein than hydrophobic or charged surfaces. Bisphosphonate and phosphorylcholine-derived thin film coatings have been applied to nanoparticles to stabilize iron oxide particles against pH, opsonization, and aggregation [10.108]. Such thin films do not fully eliminate protein adsorption, and dense layers or thick brushes of polysaccharides or hydrophilic polymers may more effectively avoid opsonization [10.109].

Other, as yet incompletely understood, biological factors influence the use of nanoparticles in vivo. For instance, a direct correlation between the circulating half-life of nanoparticles (i. e., their $T_{1/2}$s) and age of animals used has been reported [10.106]. The observed increase in $T_{1/2}$ may be correlated to age-related changes in phagocytic activity [10.106]. Local environments also influence particle stability: iron oxide particles are degraded at a pH of 4.5 or less [10.100], a condition sometimes attained in some intracellular vesicles.

First generation contrast agents were primarily blood-pool agents that moved freely through the entire vasculature. Targeting contrast-enhancing nanoparticles to sites of interest can reduce heavy metal toxicity associated with the commonly used agents by diminishing the dose required to obtain an acceptable image. Contrast agent targeting can also provide enhanced diagnostic information. For instance, nanoparticles that bind to molecular fibrin at a clot site on a vessel wall have been developed [10.110], potentially allowing differentiation between vulnerable and stable atherosclerotic plaques. Similarly prognostically valuable data regarding disruptions of the blood–brain barrier (BBB) have been visualized with MRI as the result of delivery of contrast-enhancing nanoparticles to the affected site [10.102].

10.4 Applications for Nanotherapeutic Devices

As discussed above, nanotherapeutic devices are novel, emerging therapeutics with properties not fully understood or predictable. Nanotherapeutics, therefore, must be justifiable on at least two levels. As we have seen, the nature of the therapeutic task and the state of current nanoscale-materials technology make the incorporation of biological macromolecules unavoidable for many nanotherapeutics. Proteins, for example, typically are substantially more expensive than small molecule therapeutics, and precise nanostructures containing proteins will be more costly still. Nanotherapeutics must justify their high COGs. Secondly, as new therapeutic modalities, nanotherapeutics may carry significantly larger risks than those associated with more conventional therapies. Expensive, novel moieties, such as nanobiotechnological therapeutic devices, are therefore most likely to be accepted for treatment of conditions that not only are accessible to intervention at the nanoscale but also for which existing therapeutic modalities have acknowledged shortcomings in patient morbidity or mortality. We have selected two disease states sufficiently grave and sufficiently unserved to warrant nanotherapy: cancer and cardiovascular disease. Modulation of immune responses and vaccination is our third application area.

10.4.1 Nanotherapeutic Devices in Oncology

The economic burden imposed by cancer is immense, measuring in the billions of dollars annually in the United States alone. Existing therapies such as surgical resection, radiotherapy, and chemotherapy have profoundly limited efficacy and frequently provide unfavorable outcomes as the result of catastrophic therapeutic side effects. Additionally, the biology, chemistry, and physics of cancer, in general, and solid tumors in particular, provide therapeutic avenues accessible only by nanoscale therapeutics. Oncology is thus an ideal arena for emerging nanotechnological therapies.

Tumor Architecture and Properties

Tumors as tissues are relatively chaotic structures exhibiting vast structural heterogeneity as a function of both time and space [10.9, 77, 111, 112]. In healthy tissues, vasculature resembles a regular mesh in which the mean distance of tissue spaces to the nearest vessel is tightly controlled and highly uniform. On the other hand, the vasculature of tumors resembles a percolation network containing regions experiencing vastly different levels of perfusion. Tumors of 1 mm^3 or larger typically contain measurably hypoxic domains, with pO2 values as much as two- to threefold lower than in normal tissue. High levels of hypoxia are characteristic of enhanced metastatic potential and tumor progression. Also due to insufficiency of perfusion, tumors frequently contain necrotic domains.

The average torturosity of vascular flow paths in tumors is also much greater than in healthy tissue, and transient thrombotic events lead to enhanced resistance to flow and ongoing vascular remodeling. Aside from its plasticity, tumor vasculature itself is highly irregular, may be incompletely lined with endothelial cells, and often exhibits significantly higher extravasation limits (the highest molecular weight of materials that can leave the vasculature and diffuse into the interstitial spaces) than normal vasculature. Tumor tissue is also poorly drained by lymphatics, so extravasated materials tend to remain in situ in tumors and are not cleared efficiently.

These biological phenomena all differentiate tumor tissue from normal tissue and can be exploited in therapy. For instance, the special vascular integrity and lymphatic drainage properties of tumors constitute the Enhanced Permeability and Retention effect (EPR) [10.11, 12, 80, 113]. EPR presents an obvious opportunity for intervention with nanoscale therapeutics (Fig. 10.3). Extravasation limits for normal tissues are variable, but structures larger than a few nanometers in diameter do not leave circulation efficiently in most tissues, whereas tumor vasculature frequently allows egress of materials in the tens to hundreds of nanometer range. Further, nanomaterials, once extravasated, are not cleared by lymphatic drainage. EPR provides tumor targeting that does not depend on biological affinity reagents: tumor tissue provides preferential depot sites for extravasated drug delivery devices. Targeting to a desired site of action is highly desirable for cytotoxic therapeutics, and EPR provides the basis for a growing class of polymer therapeutics [10.11, 12, 80, 113]. That said, EPR and targeting by biological affinity are not necessarily mutually exclusive. A number of antigens more or less specifically related to tumors are known (tumor associated antigens or TAAs), and as discussed above tumor-/organ-specific vascular addresses might be exploited for delivery of therapeutics [10.65, 66]. For instance, various biological reagents that recognize TAAs (i. e., antibody to carcinoembryonic antigen, transferrin) have been conjugated to nanoscale contrast agents to enhance contrast agent localization to tumoral sites [10.104].



Fig. 10.16a–c Therapeutic nanodevices can be specifically delivered to tumors by virtue of their size [10.11, 12, 80, 113]. **(a)** An illustration of the relatively low integrity of tumor vasculature. Therapeutic nanodevices (in this case, micelles carrying cytotoxins) cannot leave (i. e., extravasate from) the vasculature of normal tissue, but the vasculature of tumors is sufficiently leaky to allow specific delivery to tumoral interstitial spaces. This is the basis of size-dependent targeting to tumors by the enhanced permeability and retention, or EPR effect. **(b)** A polymer nanotherapeutic (PK1, [10.80]) that exploits EPR effect to deliver a cytotoxin (doxorubicin) to tumors. The overall mass of the complex is tuned by control of the mass of the N-2-(hydroxypropyl) methacrylimide backbone, so as to be above extravasation limits for normal tissues but below both tumor extravasation limits and the size limit for excretion through the kidney. A final feature of the device that favors delimiting doxorubicin cytotoxicity to tumoral sites is the fact that the device is a prodrug. The cytotoxicity of doxorubicin is severely curtailed when the doxorubicin is covalently linked to the polymer therapeutic, though it manifests its full toxicity when it is released from the complex by cleavage of the labile (peptidic) linker. The labile linker contains a cleavage site recognized by a protease known to be over-expressed in the target tumor type. Thus, the device produces a depot of inactive doxorubicin in tumors that is activated preferentially to full toxicity by conditions prevalent in the tumor. **(c)** EPR can drive localization of appropriately sized therapeutics to tumoral sites [10.113]. The polymer therapeutic SMANCS accumulates rapidly in murine tumors, whereas the NCS, the parent therapeutic (not engineered for EPR delivery), does not

Tumor (EPR) Properties and Nanotherapeutics

PK1 (Fig. 10.16) is an early example of a growing and increasingly sophisticated class of polymer therapeutics [10.11, 12, 80, 113]. It is a nanoscale molecular therapeutic device wherein the therapeutic moiety (doxorubicin) is covalently linked to the polymeric backbone. As we will see, each component of the polymer therapeutic fulfills a discrete function, so the device rubric is warranted [10.6].

PK1 consists of a polymeric backbone (HPMA, hydroxyl polymethacrylamide) which, as discussed below, targets desired sites by virtue of its specific nanoscale size (by EPR effect) and a cytotoxin (doxorubicin), covalently linked together by a peptide. PK1 exhibits multiple design features that allow it to preferentially deliver doxorubicin to tumors. The size of the complex is tuned to be too large to extravasate in healthy tissue but still small enough for renal clearance. Effectively, tumors and the excretory system compete for PK1. This aspect of the relationship between therapeutic size and systemic tolerability is illustrated in Fig. 10.16. The therapeutic device has to be sufficiently large to have limited access to healthy tissues but must have relatively unimpaired access to tumors and the excretory system via the kidneys.

A second engineered feature of PK1 relates to tumor-specific release of cytotoxin. Doxorubicin is toxic as a free molecule but is nontoxic as a part of a polymer complex. In PK1, doxorubicin is linked covalently to the polymeric backbone by a peptide chosen specifically because it is the substrate for a highly expressed protease in the target tumor. Thus PK1 deposits cytotoxin to tumors in an inactive form that is processed to an active form preferentially by tumoral metabolic activity. In all, the design features of PK1 act to minimize systemic exposure to cytotoxin and augment tumoral exposure, thereby enhancing therapeutic benefit and diminishing undesired side effects.

Therapeutics need not be covalently linked complexes to be delivered by EPR. In some cases, bioactives can be engineered to interact with blood constituents non-covalently so as to bring the apparent size of the complex into a range that allows preferential tumor deposition. This is the mechanism of delivery for the oldest EPR-exploiting therapeutic in clinical use, SMANCS (S-Methacryl-neocarzinostatin) [10.113]. Neocarzinostatin (NCS) is a small (12 kDa, a few nm in diameter), cytotoxic protein that elicits its toxicity by generating intracellular superoxide radicals enzymatically, which in turn damage DNA. Unmodified NCS is cleared rapidly and exhibits dose-limiting bone-marrow toxicity. Both problems are mitigated by the site-specific conjugation of two small (about 2 kDa and less than 1 nm in length) styrene-comaleic acid polymer chains, resulting in SMANCS. The $T_{1/2}$ of SMANCS is about ten-fold higher than that of NCS, though SMANCS itself is too small to accumulate preferentially in tumors by EPR. This is mitigated by the fact that SMANCS (but not NCS) is efficiently bound by serum albumin. The resulting non-covalent complex is sufficiently large not to extravasate into normal tissue, though it still partitions efficiently into many tumors. The EPR-driven partitioning of the non-covalent SMANCS-albumin complexes into tumors suggests that other non-covalent complexes (such as the multi-dendrimer device of Fig. 10.3, were it pre-assembled prior to administration) might also target to tumors via EPR.



Fig. 10.17 Antibody responses [10.1] are efficiently triggered by antigens that contain both B-cell epitopes (diamond) and helper T-cell epitopes (rectangle). The B-cell epitope binds a receptor on the B-cell surface (the Y shape shown interacting with the B-cell epitope) that is essentially a membrane-bound form of the antibody species that the particular B-cell can produce. The peptidic T-helper epitope engages another receptor complex on the B-cell surface (class II MHC, the two part receptor schematically depicted as interacting with the T-helper epitope, see text). When presented in the context of the class II MHC complex of the B-cell, the T-helper epitope can be recognized by a cognate T-cell receptor on the helper T-cell surface (shown as a receptor on the T-cell surface interacting with the T-helper epitope/class II MHC complex). In response to recognition of its appropriately presented, cognate T-helper antigen, the helper T-cell provides multiple stimulatory signals that cause the B-cell to proliferate, secrete antibody, and differentiate. This is a classical hapten-carrier configuration of an immunogen [10.1], in which a synthetic B-cell epitope is the hapten (in our cases, a PAMAM dendrimer or SWCNT epitope), and the protein covalently linked to the hapten is the carrier, providing the T-helper epitope. Note that the antibody produced recognizes *only* the B-cell epitope and *not* the T-helper epitope. The T-helper epitope also need not be present for antibody recognition of carrier epitopes, nor is its presence necessary to maintain the ongoing antibody response once antibody production is triggered. Note that whether the T-helper epitope remains covalently linked to the B-cell epitope during antigen presentation (here, the intact carrier protein is shown linked to the B-cell epitope) is debatable. Proximity of the B-cell epitope/receptor complex and T-helper epitope/class II MHC complex on the B-cell surface may be sufficient to trigger a robust antibody response

Delivery of antitumor agents using EPR can be highly efficacious. As shown in Fig. 10.17, conjugation of therapeutics to produce controlled-size delivery complexes can enhance tumoral accumulation by multiple orders of magnitude relative to free therapeutics [10.11, 12, 80, 113]. In effect, EPR targeting broadens the therapeutic window (the range of concentration between the lowest effective and highest tolerable dose), allowing more intensive therapy. Increased therapeutic intensity allowed by EPR strategies also produces significantly enhanced clinical outcomes [10.11, 12, 80, 113]. The benefits of EPR strategies seem to be general in that a broad range of materials can be targeted to tumors and almost any particulate material falling within the appropriate size range will partition into tumor tissue via EPR. This includes not only linear and dendritic polymers but also higher-order, self-assembled structures such as micelles or shell cross-linked structures and inorganic materials such as ferromagnetic particles. In addition to EPR tumor targeting, each of these structures has intrinsic properties that might be exploited in therapeutic nanodevices (see the discussion of imaging above). Targeted contrast agents may be particularly important for early tumor detection.

10.4.2 Cardiovascular Applications of Nanotherapeutics

The cardiovascular system is one of the most dynamic and vital systems of the body. In principle, every cell in the body is accessible to the bloodstream via the vasculature. If controlled navigation of, and extravasation from, the vasculature can be accomplished, therefore, the potential of nanotherapeutic devices is virtually unlimited. But as mentioned throughout this chapter, opsonization and immune clearance, as well as targeting and triggering of therapeutics, remain key issues to address in order to facilitate wide application of nanotherapeutic devices to cardiovascular disease. In this section we provide a brief overview of categories and examples of nanotherapeutic devices used in blood-contacting applications.

Cardiovascular Tissue Engineering

A usable, immunologically compatible artery for coronary bypass is not always available, so synthetic or semi-synthetic artery substitutes are highly valuable. Tissue engineering approaches might mitigate the lack of acceptable homologous artery, as long as an acceptable artery substitute can be produced. Current tissue engineering approaches involve synthesis of three-dimensional, porous scaffolds that allow adhesion, growth, and proliferation of seeded cells to generate a functional vessel. Cellular organization and growth in synthetic scaffolds are often chaotic and random, and sufficient blood supply is seldom achieved within the scaffold. These conditions often result in death of the seeded cells and compromise the integrity of the vascular prosthesis.

Microfabrication techniques have allowed miniaturization of the tissue engineering scaffolds. These techniques allow the molecular-level control of cellular adhesion and propagation by control of surface topography, surface chemistry, and arrangement of morphogenic and proliferative signaling ligands and cytokines. Microfabrication schemes are being developed for the elucidation of parameters necessary for cellular attachment and orientation on well-defined silicon- and polymer-based surfaces. One particularly powerful application of controlled cellular growth is for the development of artificial capillaries to remediate vascular disease [10.114] (Moldovan, unpublished). Micro-machined silicon or polymer channels of the dimensions of capillaries have shown promise as effective conduits to direct endothelial cells to form tubes through which a fluid (blood) could eventually flow.

MEMS technology and nanoscale control of molecular events and interactions has also been applied to the development of cardiovascular sensors. For instance, blood cell counters have successfully detected red and white blood cells and show promise for quick, reliable blood cell analysis [10.115]. Additionally, force transducers have been developed to measure the contractile force of a single cardiac myocyte [10.116]. Basic research into cellular function and response to stimuli such as these will eventually support more efficacious and robust cardiovascular tissue engineering approaches.

Nanoparticulate Carriers for Therapy and Imaging

Two major cardiovascular applications of nanoparticles are targeted contrast agents for imaging (MRI, CT, X-ray, etc.) and targeted drug delivery vehicles to address vascular lesions (atherosclerotic plaques) and other vascular disease states. In either application, nanoparticle surfaces must be appropriately modified to avoid RES clearance and to drive interaction with the desired effector cells. Decades of research in the area of molecular and cell biology have provided researchers with many tools to make the appropriate protein component selection for nanotherapeutic contrast agents. For instance, knowing that the procoagulant protein tissue factor is expressed only at the surface of injured endothelial cells provides a means to differentiate healthy from diseased vasculature. It also provides a method to target disease sites. Similar sorts of information regarding disease and normal vasculature at specific tissue sites can be critically important for targeting specialized vascular beds, such as that which occurs at the BBB. Several groups have begun efforts to develop nanoparticles that selectively pass across the BBB to deliver chemotherapeutic or other drugs to the brain [10.117, 118], and this may improve outcomes from stroke.

With regard to MRI approaches, particles used for targeted contrast enhancement in specific tissues or vascular beds may be quite powerful for detection of unstable atherosclerotic plaques and quantitative analysis of blood flow. For instance, nonspecific accumulation of nanoparticles within human atherosclerotic plaques has been reported [10.119, 120] and may ultimately provide a way to distinguish vulnerable and stable plaques. Such data might be used to direct therapy, with the intent, as always, to improve therapeutic outcome. Furthermore, nanotherapeutic devices have been designed to include both contrast and drug delivery functions (Fig. 10.3). Single-platform, multifunctional particles for cardiovascular therapy represent a cutting edge in the cardiovascular field. These delivery vehicles are being designed and improved continual for longer circulation time, more efficient targeting [10.66, 121], degradability, and biocompatibility [10.122].

10.4.3 Nanotherapeutics and Specific Host Immune Responses

Immune responses directed to immunogens (molecules or structures capable of eliciting specific immune responses, also called antigens) are a pervasive aspect of the responses of vertebrates to exposure to foreign macromolecules, proteins, particles, and organisms (for overviews, see [10.1, 123, 124]). Undesired antibody responses, in particular, are the single most important hurdle for clinical use of recombinant proteins. On the other hand, undesired cellular immune responses are key mediators of frequently devastating disorders for patients, whether the responses are directed to self (as in autoimmune disease) or to foreign antigens (as in transplant rejection). As we shall see, host immune responses to nanotherapeutic devices are a critical determinant of their efficacy. Any strategy (including the biotechnological strategies) that allows controlled manipulation of immune responses either to augment desirable responses, as in vaccines, or to mitigate deleterious responses holds substantial potential benefit.

Basic Immunology

Specific immune responses are directed to individual macromolecules or assemblages of them and can be categorized into cellular responses, mediated by cytotoxic T-lymphocytes (CTLs), and humeral responses, mediated by soluble proteins (found in blood serum and other biological fluids) secreted by B-cells (antibodies). Regardless of the effector (CTLs or antibodies), specific responses are directed to individual molecular features of antigens called epitopes. The three types of epitopes are: cytotoxic T-cell (CTL) epitopes, helper T-cell epitopes, and B-cell epitopes. The first two types are peptides that must be presented on cell surfaces in the context of the class I (in the case of CTL epitopes for CTL responses) or class II (in the case of T-helper epitomes, involved in both antibody and CTL responses) major histocompatibility complex (MHC) molecules. B-cell epitopes are a chemically and structurally heterogeneous group of epitopes and include synthetic molecules as well as peptides. In addition to CTL and B-cell epitopes, which are recognized by immune effectors, T-helper epitopes are recognized by regulatory components of the immune system (helper T-cells). Vibrant CTL and antibody responses require immunogens containing T-helper epitopes along with either B-cell or CTL epitopes.

While epitope-presenting MHC class I and class II complexes must be present on cell surfaces to trigger immune responses, the machinery for antigen processing and loading of MHC class I or class II proteins for antigen presentation reside in distinct membrane-bound compartments in the cell [10.1]. For instance, processing for class I presentation (to trigger CTL responses) occurs through the cytosol, but charging of MHC class I complexes is accomplished in the endoplasmic reticulum. On the other hand, processing for class II presentation (to augment antibody and CTL responses), as well as the loading of class II, occur in endosomal compartments. Although these are membrane bounded compartments in the cytosol, topographically the interiors of endosomal compartments are part of the extracellular environment and are not inside the cell at all.

In the case of both class I and class II, the antigen presenting complexes are moved to the cell surface after charging. The moving of molecules between different cellular locations (called trafficking) is tightly regulated by and driven by specific cellular proteins, systems, and structures. Proper trafficking is essential to assure that all cellular components assume their correct position in the cellular organization, which in this case, is to assure antigens are directed to the compartments that will (most often) produce most protective immune responses. These complex antigen processing and presentation systems can be perturbed and exploited to offer novel opportunities in vaccine design.

Nanotherapeutic Vaccines: Eliciting Desired Host Immune Responses

Both therapeutic and prophylactic vaccines are naturals for nanobiological approaches. Therapeutics that modulate immune responses (antibody, CTL responses, or both), vaccines typically produce desired immunity to disease or pathogens. Ideally they are chemically well defined, safe, and induce long term (preferably, multiyear) protective immune responses [10.125]. Recent developments in immunobiology have opened opportunities for nanobiological vaccine design [10.126, 127].

Particulate Vaccines

The immune system, through dendritic cells (DCs), other antigen presenting cells (APCs), and immune effectors, performs ongoing surveillance for non-self antigens using the MHC antigen presentation system described above [10.1]. It has long been known that APCs sample serum for antigens that they process and present using the MHC class II pathway for antibody production [10.1]. Research of the last few years has shown that DCs, macrophages, and other APCs also take up particulate materials and process and present the constituent peptide epitopes via the MHC class I pathway to trigger specific CTL responses. Previous dogma held that only endogenous antigens (such as those produced in virally infected cells) could be presented through the class I MHC pathway. Both soluble and particulate antigens can be presented via the class I pathway, but particulate antigens are orders of magnitude more potent than the same immunogens formulated in soluble form [10.125–128].

APCs are not particularly fastidious regarding chemical composition of the particles they take up: latex beads [10.126, 128] as well as iron beads [10.126] have been used. Self-assembled nanoparticles made of lipidated epitope peptides also deliver orders of magnitude of better immunization than do soluble formulations of the same peptides [10.129]. The specific size for optimal CTL responses is not fully defined but clearly is in the nanometer to micrometer size range [10.125, 126, 128, 129]. One could imagine a systematic exploration of optimum size and compositional preferences for uptake by APCs using such chemically and morphologically tunable polymeric nanomaterials as dendrimers and tectodendrimers.

Nanobiological Design of Nanotherapeutic Vaccines

As mentioned earlier, antigen trafficking determines which specific MHC complex (class I or class II) epitopes are presented on and, therefore, which immune effectors are produced in the subsequent response. The process, while tightly regulated, is amenable to intervention using nanotherapeutic vaccines. Nanobiological design strategies (discussed above) can take advantage of the numerous proteins and peptides now known to mediate the trafficking of carried materials to specific sites. In the device context, these trafficking moieties might assure delivery of antigens to the appropriate cellular compartments to trigger desired class I- or class II-mediated responses.

Vaccine polypeptides, for instance, might be fused or formulated with pathogen polypeptides that will deliver them across epithelium from outside the host for use in mucosal vaccination [10.130]. Still other peptides are known to carry injected materials across the cell envelope into the cytosol [10.131]. Alternatively, vaccine entities taken up by receptor-mediated endocytosis (into endosomal vesicles, the traditional site of uptake for antigens destined for MHC class II presentation) could be shuttled into the cytosol (and hence to the class I MHC pathway) by the incorporation of peptide domains of bacterial toxins that mediate endosomal escape to cytoplasm [10.132]. Potentially, nanobiological therapeutic design strategies [10.5, 13, 15] can combine knowledge of polymer chemistry, nanomaterials, chemistry, cell, molecular, and immunobiology to generate highly effective nanotherapeutic vaccines.

Nanotechnology and Modulation of Immune Responses

On the other hand, protein immunogenicity represents a critical limitation to the therapeutic use of recombinant proteins, particularly when specific antibody responses to the therapeutics are engendered [10.32]. The consequences of antibody responses to proteins are variable, ranging from no effect to decidedly negative consequences to the host. Antibodies can neutralize therapeutic bioactivity, rendering drug entities inactive in repeated rounds of therapy, distort drug $\mathrm{P_k}$ and $\mathrm{B_d}$ properties, and, in the worst case, trigger autoimmune responses with cross-reactive host antigens (host antigens that share some identity with the immunizing epitopes).

Antibody Responses to Nanotherapeutic Devices

Antibody responses to protein components are a major challenge for nanobiological therapeutic devices in vivo. We, and others [10.6, 14, 21, 133–136], have demonstrated that protein components of bioconjugates to diverse nanomaterials can not only retain their intrinsic immunogenicity but, worse, can render the otherwise non-immunogenic synthetic nanomaterials to which they are linked capable of inducing antibody responses [10.6, 7, 14, 21, 126, 133–135]. The mechanism of immunogenicity seems to be haptenization, a well-known phenomenon in immunology. Haptenization occurs when antigens containing only B-cell epitopes are covalently linked to proteins containing T-helper epitopes, thereby creating hybrid antigens that are fully immunogenic with respect to antibody responses. The process is illustrated in Fig. 10.17.

As a result of the chemically repetitive structure of many synthetic nanomaterials, the antibodies directed to them have interesting properties. Most notably, antibodies generated to nanostructures are often cross-reactive to other chemically similar nanostructures. For example, antibodies raised using haptenized fullerenes also recognize carbon nanotubes [10.133], and antibodies raised to haptenized generation 0 (G_0) PAMAM dendrimers also recognize higher generation PAMAM dendrimers (G_1, G_2, G_3, etc. [10.14, 21, 133–136]. Presumably, cross-reactivity results from the presence of common B-cell epitopes in the immunogen used and in structurally similar cross-reactive antigens. Thus, patients immunized with any therapeutic containing one haptenized nanostructure could potentially raise antibodies that would recognize any nanotherapeutic containing a material structurally similar to the haptenized nanomaterial.

This is a potentially serious problem, in light of the documented ability of antibody responses to interfere with therapy by neutralizing drug or distorting P_k and B_d properties. As discussed before, molecular weights of serum antibodies are around 150,000 AMU with an effective diameter in excess of 10 nm [10.1, 123, 124]. Many of the desirable properties of nanotherapeutics derive from their precisely controlled sizes, and size-dependent properties like EPR targeting could be jeopardized if the therapeutic to be delivered were non-covalently complexed with antibodies directed to its synthetic components. Due to long-term persistence of memory immune responses, exposure to haptenized nanotherapeutics could endanger patient responsiveness to structurally similar materials for the duration of their lives. Obviously, immunogenicity is a critical challenge to the nanobiological therapeutic paradigm that has yet to be satisfactorily addressed.

Polymer Conjugation to Mitigate Immune Responses

There are multiple approaches to mitigating immunogenicity, some of which are applicable to nanobiotechnological therapeutic devices. Polymer conjugation, particularly conjugation of proteins to poly (ethylene glycol) (PEG, a flexible, biologically well-tolerated hydrophilic polymer) has been used to control immunogenicity of a broad class of proteins and synthetic molecules since the mid-1970s [10.19, 137]. Typically, pegylation involves covalent linkage (often by promiscuous conjugation chemistry) of variable numbers (usually two to six polymer molecules) of size-polydisperse (usually 3,000 to 10,000 AMU) linear or branched PEG chains to the potential immunogen. This approach results in polydisperse bioconjugates, which flies in the face of the molecular level-structural precision often considered essential for nanotechnology. Still, pegylation may be useful in some limited nanobiological applications.

The mechanism of molecule-specific immunosuppression remains obscure, despite almost 30 years of research. The flexibility of the PEG strands allows them to wrap around the molecules they are conjugated to, perhaps delimiting access of immune effectors and immune processing machinery to the potential immunogens. Pegylated molecules exhibit dramatically enhanced apparent diameters and vastly enhanced solubility in aqueous buffer. Both of these phenomena result in substantially diminished clearance of pegylated molecules by the RES and may account for the retention of in vivo bioactivity despite the apparent steric hindrance that may result from wrapping PEG moieties around their protein bioconjugate partners. Pegylation-related, bioconjugate-specific immunosuppressive phenomena cannot be fully accounted for by sterics, though. Immunological experiments in syngeneic mice show that the protein-specific immunosuppression associated with pegylated proteins is transmissible from one animal to another by surgically harvested splenocytes. This finding is more consistent with a mechanism of suppression involving immunologically induced tolerance of foreign antigens as opposed to one caused by simple steric considerations [10.137].

Synthetic Nanoporous Membranes for Immunoisolation

A second approach to avoiding immune responses to nanodevices or biocomponents is immunoisolation by encapsulation [10.16, 17]. In this strategy, potentially immunogenic structures (nanodevices, cells, macromolecules) are sequestered from high molecular weight, large host immune effectors, and immunosurveillance, while small molecules, such as glucose and small proteins, diffuse freely (Fig. 10.18). While conceptually simple, immunoisolation is technically challenging in that the number of pores must be high to maximize



Fig. 10.18 Biological components can be protected from unfavorable environments by encapsulation [10.16–18]. Shown is an immunoisolation capsule containing heterologous (immunogenic) cells producing insulin (a four helical bundle protein, see text). The cells are protected from immune responses by membranes with 10 nm pores that allow free diffusion of small molecules (oxygen, nutrients) into the capsule and small proteins (insulin, shown here not to scale) out of it. However, immune effectors with diameters greater than pore size (immune cells like CTLs and APCs, antibodies, other effectors) don't access the capsule interior, protecting the xenograft from immune rejection. The structure integrates both micro- and nanoscale components (including the nanoporous membranes of Fig. 10.4) into a macroscale construct

flux, and the pores must be highly uniform in dimension.

Because of the exquisite sensitivity of the immune system, immunoisolation must be nearly perfect if it is to work at all. Particularly in the case of immunoisolation of cells for xenografts, if only a tiny fraction (as few as 1%) of the pores of an immunoisolation capsule are large enough to admit immune effectors (for instance, antibodies and complement components, exclusion of which requires pores of 50 nm or less), or the viability of the graft will be compromised [10.16, 17, 138]. Thus, the strategy requires fabrication of membranes with pores that have very tightly controlled dispersities in terms of their maximum diameters. Until recently, immunoisolation for xenografts has failed for lack of such membranes.

The technological innovations that made the synthesis of these high-quality nanoporous membranes were described above and in Fig. 10.4. The nanoporous membranes can be used to form immunoisolation capsules when either two such membranes are joined so that they bind an enclosed space or that a nanoporous membrane is used to enclose a compartment of some sort in a therapeutic structure. The enclosed spaces can be charges with functional nanodevices or, for that matter, living cells. Such immunoisolation capsules charged with heterologous pancreatic islet cells have demonstrated immense promise for regulating normoglycemia in diabetic animal models [10.16–18].

Biogenic, Nanoporous, Immunoisolation Membranes

The novel microfabrication strategy has made it possible to make these highly defined membranes in an industrial process, and they are applicable to numerous biomedical applications beyond immunoisolation [10.16, 17]. Still the fabrication process is rigorous, and an alternative biogenic method to derive selectively porous silicon capsules has been proposed [10.139, 140]. Diatoms are encapsulated in biogenic amorphous silicon shells (called frustules), which the living cells secrete. Frustules must necessarily be porous to allow the cells to take on nutrients and excrete wastes, and the porosity, pore dimensions, and other micro- and nanoscale morphological frustule features are tightly controlled at genetic and physiological levels. Using techniques well known to microbiologists (manipulation of culture conditions), geneticists (mutagenesis), and cell biologists (optically driven cell sorting in flow systems), it is theoretically possible to select and propagate diatoms whose frustule morphology, size, and pore characteristics fall within pre-selected limits [10.139, 140]. Frustules can be isolated intact from diatom cultures, so biogenic production of silicon membranes with porosity characteristics similar to the microfabricated membranes discussed above may be feasible. Though they have yet to be realized, immunoisolation capsules made from genetically/physiologically tuned frustules have been proposed [10.140]: one wonders what other biomineralized structures eventually might also be put to nanobiotechnological use.

10.5 Concluding Remarks: Barriers to Practice and Prospects

The effort to produce nanoscale therapeutic devices is clearly highly interdisciplinary. As we have seen, it touches on numerous established disciplines, encompassing elements of physiology, biotechnology, bioconjugate chemistry, electrical engineering, and materials science, to name just a few of the fields involved. Obviously, this broad sweep of knowledge is difficult for any one investigator to master fully. The breadth of the effort constitutes just one of the major barriers to entry in the field. Other challenges include the raw complexity of biology, the fashion in which biologists hold and distribute information, and cultural differences between engineers and biological scientists.

10.5.1 Complexity in Biology

Biology is characterized by particularity: nuances of biological systems are often unique to the system at hand and highly idiosyncratic. This follows from the fact that biological systems are not purpose-built, as are designed devices (although they can give that appearance, as seen in Fig. 10.1), but rather arose as the consequence of evolutionary processes. Evolution is a highly chaotic business, with the outcome of any given evolutionary process highly sensitive to initial conditions (populations of organisms subjected to selection, other organisms in the environment, biology of all organisms involved, resource availability, other environmental factors, etc.). Moreover, many of the variables affecting natural selection processes are nonstatic and change, as a function of time or space or both, *while* selection is exerted against a population of organisms. Conditions leading to one evolutionary adaptation or another are therefore seldom duplicated exactly, so that individual adaptive features are idiosyncratic, with elements relating not only to their biological functions but also to their evolutionary history. Individual systems and adaptive features thereof can be almost baroquely complex because the structures themselves arose under unique conditions, under unique selective pressures, and from unique initial biological systems. The extent of the complexity of biological systems is apparent even in individual macromolecular constituents of biological systems and can be made clear by comparison of synthetic nanostructures to biological nanostructures with similar dimensional aspects.

SWCNT (single wall carbon nanotubes) have a minimal diameter of about 1.3 nm, and many proteins likewise have diameters of few nms. SWCNTs are regular and homogeneous polymeric structures composed entirely of carbon atoms (Fig. 10.6). Proteins, on the other hand, are not polymers of one repeating subunit, but rather are nonrandom copolymers of 20 chemically distinct amino acids (aas). The order of the aas drives specific folding events that produce three-dimensional structures that, in turn, present specific aas and their side chains at specific positions in space (Fig. 10.10). This control of aa position in space drives protein activity: small changes in aa sequence can perturb structure and function profoundly. Therefore, though they fall within the same broad size regime, proteins are structurally and functionally much more complex than SWCNTs. The extent of biological complexity can be glimpsed when one considers that individual living things are ordered aggregates of multiple macromolecules and supramolecular structures (potentially, billions and billions of them), belonging to distinct chemical classes (lipids, proteins, nucleic acids, etc.), with each individual macromolecule being at least as complex in structure and function as the protein of Fig. 10.10. The nearly irreducible complexity of biological systems is a central fact of practice in the biological sciences and drives the way biologists gather and disseminate information. It is the key informant of the culture of biologists.

10.5.2 Dissemination of Biological Information

Biologists typically consider themselves primarily as scientists, as opposed to being engineers or technology developers. The product biologists generate, then, is information rather than devices or structures. Their interest in technological application of the knowledge they produce is typically secondary to their desire to develop the information itself. Additionally, as we have just seen, biology is a ferociously complex discipline.

As a practical matter, biological data itself is often much more rich (and often more ambiguous) than data from harder scientific endeavors. The data can be so very rich that biologists must make choices as to what data is relevant to a given phenomena and, therefore, what data they will publish. With absolutely no intent to conceal or mislead, biologists are often driven to publish only a small fraction of the data they gather.

Since they see themselves primarily as scientists, biologists tend to publish data they believe to be of broad scientific significance. Typically, the chosen information does not include data that might be critical to technology development, frequently making the biological literature an inadequate resource for engineers. The omitted information thus becomes lore. That is to say, the infomation is critical for the practice or development of a given technology but usually is not accessible to persons outside the field (as many nanotherapeutic device producers may be). This can be illustrated by recent experiences around phage display-mediated affinity maturation of four helical bundle proteins [10.141–143].

Four helical bundle proteins are loosely related small proteins consisting of four α helices arranged in a specific configuration (see the dynamite stick representation of insulin that occurs in Fig. 10.18). They include insulin, growth hormone, most cytokines, and various other molecules involved in cell to cell signaling. They have a wide range of therapeutically valuable properties that might be made even more desirable if their potencies could be enhanced. There is thus significant interest in variant four-helical bundle proteins with improved bioactivities.

Phage display [10.67] is a method that can be used to sort protein variant libraries for variants with enhanced affinity for a target receptor. This is usually accomplished by iterative rounds of affinity selection on the receptor followed by propagation of selected phage. As rounds of selection and propagation proceed, the mean affinity of the selected variants for the receptor increases (so-called affinity maturation). A phage display method is depicted in Fig. 10.11.

Affinity maturation by phage display can be used to identify variant proteins from libraries that have enhanced biological activities, providing that affinity for receptor is limiting in the overall activity of the parent protein [10.134]. Phage display affinity maturation has been successfully used to select some enhanced activity variants of four helical bundle proteins [10.144, 145] but is *not* applicable to engineering increased activity for *all* four helical bundle proteins [10.134]. The reason for the inapplicability of display methods to engineer high-activity human growth hormone (hGH) variants became apparent in a recent publication from Genentech [10.142].

In the case of hGH, the affinity of the parent molecule for receptor is in excess of that required to drive maximal biological responses [10.142]. This fact was inferred after a multiyear effort (beginning in the late 1980s and culminating in 1999) to derive more active hGH proteins, involving literally thousands of hGH variants. Many of the variants did indeed exhibit enhanced affinity for the hGH binding protein (receptor), but none exhibited significantly enhanced biological activity. Each data point (i. e., the biological activity of each individual variant) essentially constituted a failure of a technology to provide a desired result and was therefore seen, not unreasonably, as negative (and therefore uninteresting) data by the investigators. Consequently, the information was not broadly disseminated until a significant conclusion could be presented (i. e., that biological responses to hGH are not limited by ligand-receptor affinity). Thus, between the late 1980s and the 1999 publication, this information was known primarily and unambiguously only to the investigators involved, even though it would have been critical to any technologist planning to affinity mature hGH by phage display for enhanced activity [10.134].

10.5.3 Cultural Differences Between Technologists and Biologists

Biology is the realm of particularity, whereas more physical sciences are realms within which general rules can be derived and broadly applied. The vast complexity of biology usually drives biologists to be highly specialized, perhaps making a career from the study of particular macromolecules (specific enzymes, growth factors, genetic elements, etc.) or biological systems. Biologists are, therefore, neither trained nor encouraged by funding agencies to see themselves as fungible, and frequently they are very reluctant to step away from their primary research focuses into new areas. Doing so is a major undertaking, and a substantial risk, for most biologists.

Engineers, on the other hand, often see themselves as operating from first principles and are more (if not entirely) willing to step into new areas. After all, crossing disciplines is feasible for engineers working in the physical sciences, whereas it is much more difficult, not only for reasons of training but also because of the biological realities discussed above, for biologists. Also by reason of their training and experience, engineers often vastly underestimate the complexity of biological systems and sometimes exhibit what biologists perceive as naïveté in their approach to biological systems. Unfortunately, or fortunately, depending on your perspective, therapeutic nanodevices require both biological and engineering expertise. An often bruising debate as to how best to prepare students for practice in this extremely challenging field is currently playing out in biomedical engineering and other related academic departments across the country.

The traditional approach for training biomedical engineers has been to train conventional engineers with a smattering of biological knowledge. This "primarily engineers" model of biomedical engineering has been reasonably successful in multiple endeavors (orthopedics, imaging technologies, etc.), but it seems unlikely in the extreme that it will suffice for robust practice in nanotherapeutic devices. As this chapter shows, the role of biology is pivotal to success in the field, and sophisticated nanotherapeutics are virtually impossible to design without deep knowledge of the biology involved. A reasonable argument can be made that successful engineering of therapeutic nanostructures will demand intense focus on biology and a smattering of engineering knowledge (a "primarily biologists" approach, as opposed to the historically prevalent "primarily engineers" training model). This view is often strongly and passionately resisted in colleges of engineering, which are the usual homes of biomedical engineering and related efforts. The outcome of the debate is not finalized, but it is critically important: it will determine whether or not a ready cadre of researchers is prepared for a career in the area. If not, the field will progress much as it has, very slowly bringing the benefits of the research to patients. It seems apparent to us, and it also seems that experience to date shows, that a substantial biological component of training for the discipline is simply unavoidable if we are committed to realizing the vast potential of nanotechnology in human therapy.

References

10.1 C. A. Janeway, P. Travers, M. Walport, J. D. Capra: *Immunobiology* (Elsevier, London 1999)

10.2 S. C. Lee: Biotechnology for nanotechnology, Trends Biotechnol. **16** (1998) 239–240

10.3 S. C. Lee: Engineering the protein components of nanobiological devices. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 67–74

10.4 S. C. Lee: How a molecular biologist can wind up organizing nanotechnology meetings. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998)

10.5 S. C. Lee: The nanobiological strategy for construction of nanodevices. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 3–14

10.6 S. C. Lee: A biological nanodevice for drug delivery. In: *National Science and Technology Council. IWGN Workshop Report: Nanotechnology Research Directions. International Technology Research Institute, World Technology Division* (Kluwer, Baltimore 1999) pp. 91–92

10.7 S. C. Lee, R. Parthasarathy, K. Botwin: Protein-polymer conjugates: Synthesis of simple nanobiotechnological devices, Polymer Preprints **40** (1999) 449–450

10.8 L. Jelinski: Biologically related aspects of nanoparticles, nanostructured materials and nanodevices. In: *Nanostructure Science and Technology*, ed. by R. W. Siegel, E. Hu, M. C. Roco (Kluwer, Dordrecht 1999) pp. 113–130

10.9 J. Baish, Y. Gazit, D. Berk, M. Nozue, L. T. Baxter: Role of tumor vascular architecture in nutrient and drug delivery: An invasion percolation-based network model, Microvasc. Res. **51** (1996) 327–346

10.10 J. R. Baker Jr.: Therapeutic nanodevices. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 173–183

10.11 R. Duncan: Drug targeting: Where are we now and where are we heading?, J. Drug Targeting **5** (1997) 1–4

10.12 R. Duncan, S. Gac-Breton, R. Keane, Y. N. Sat, R. Satchi, F. Searle: Polymer-drug conjugates, PDEPT and PELT: Basic principles for design and transfer from the laboratory to clinic, J. Cont. Release **74** (2001) 135–146

10.13 D. S. Goldin, C. A. Dahl, K. L. Olsen, L. H. Ostrach, R. D. Klausner: Biomedicine. The NASA-NCI collaboration on biomolecular sensors, Science **292** (2001) 443–444

10.14 S. C. Lee: Dendrimers in nanobiological devices. In: *Dendrimers and other Dendritic Polymers*, ed. by D. Tomalia, J. Frechet (Wiley, London 2001) pp. 548–557

10.15 J. R. Baker Jr., A. Quintana, L. Piehler, M. Banazak-Holl, D. Tomalia, E. Racka: The synthesis and testing of anti-cancer therapeutic nanodevices, Biomed. Microdevices **3** (2001) 61–69

10.16 T. Desai, D. Hansford, L. Kulinsky, A. Nashat, G. Rasi, J. Tu, Y. Wang, M. Zhang, M. Ferrari: Nanopore technology for biomedical applications, Biomed. Microdevices **21** (1999) 11–40

10.17 T. A. Desai, W. H. Chu, J. K. Tu, G. M. Beattie, A. Hayek, M. Ferrari: Microfabricated immunoisolating biocapsules, Biotechnol. Bioeng. **57** (1998) 118–120

10.18 M. Ferrari, W. H. Chu, T. A, Desai, J. Tu: *Microfabricated silicon biocapsule for immunoisolation of pancreatic islets*, Advanced Manufacturing Systems, CISM Courses and Lectures, Vol. 372, ed. by E. Kuljanic (Springer, Wien 1996) pp. 559–568

10.19 J. M. Harris, N. E. Martin, M. Modi: Pegylation: A novel process for modifying pharmacokinetics, Clin. Pharmacokin. **40** (2001) 539–551

10.20 S. B. H. Kent: Building proteins through chemistry: Total chemical synthesis of protein molecules by chemical ligation of unprotected protein segments. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 75–92

10.21 S. C. Lee, R. Parthasarathy, T. Duffin, K. Botwin, T. Beck, G. Lange, J. Zobel, D. Jansson, D. Kunneman, E. Rowold, C. F. Voliva: Antibodies to PAMAM dendrimers: Reagents for immune detection assembly and patterning of dendrimers. In: *Dendrimers and other Dendritic Polymers*, ed. by D. Tomalia, J. Frechet (Wiley, London 2001) pp. 559–566

10.22 S. C. Lee, M. S. Leusch, V. A. Luckow, P. Olins: Method of producing recombinant viruses in bacteria, (1993) US Patent 5,348,886

10.23 M. S. Leusch, S. C. Lee, P. O. Olins: A novel host-vector system for direct selection of recombinant baculoviruses (bacmids) in *Escherichia coli*, Gene. **160** (1995) 191–194

10.24 V. A. Luckow, S. C. Lee, G. F. Barry, P. O. Olins: Efficient generation of infectious recombinant baculoviruses by site-specific, transposon-mediated insertion of foreign DNA into a baculovirus genome propagated in *E. coli*, J. Virol. **67** (1993) 4566–4579

10.25 T. Gardner, C. R. Cantor, J. J. Collins: Construction of a genetic toggle switch in *Escherichia coli*, Nature **403** (2000) 339–342

10.26 J. Hasty, F. Isaacs, M. Dolnik, D. McMillen, J. J. Collins: Designer gene networks: Towards fundamental cellular control, Chaos **11** (2001) 107–220

10.27 E. Di Fabrisio, A. Nucara, M. Gentili, R. Cingolani: Design of a beamline for soft and deep lithography on third generation synchrotron radiation source, Rev. Sci. Instrum. **70** (1999) 1605–1613

10.28 G. M. Dykes: Dendrimers: A review of their appeal and applications, J. Chem. Tech. Biotech. **76** (2001) 903–918

10.29 R. Spindler: PAMAM starburst dendrimers: Designed nanoscopic reagents for biological applications. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 15–32

10.30 D. Tomalia, H. M. Brothers II: Regiospecific conjugation to dendritic polymers to produce nanodevices. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 107–120

10.31 B. I. Yacobson, R. E. Smalley: Fullerene nanotubes: C1000000 and beyond, Amer. Scient. **85** (1997) 324–337

10.32 D. J. A. Crommelin, R. D. Sindelar: *Pharmaceutical Biotechnology* (Harwood Academic Publishers, Amsterdam 1997)

10.33 L. J. Lee: BioMEMS and micro-/nano-processing of polymers – An overview, Chin. J. Chem. Eng. **34** (2003) 25–46

10.34 T. R. Groves, D. Pickard, B. Rafferty, N. Crosland, D. Adam, G. Schubert: Maskless electron beam lithography: Propects, progress and challenges, Microelectron. Eng. **61** (2002) 285–293

10.35 M. Guthold, R. Superfine, R. Taylor: The rules are changing: Force measurements on single molecules and how they relate to bulk reaction kinetics and energies, Biomed. Microdevices **3** (2001) 9–18

10.36 L. M. Demers, D. S. Ginger, S.-J. Park, Z. Li, S.-W. Chung, C. A. Mirkin: Direct patterning of modified oligonucleotides on metals and insulatos by dip-pen nanolithography, Science **296** (2002) 1836–1838

10.37 K.-B. Lee, S.-J. Park, C. A. Mirkin, J. C. Smith, M. Mrksich: Protein nanoarrays generated by dip-pen nanolithography, Science **295** (2002) 1702–1705

10.38 M. Ferrari, J. Liu: The engineered course of treatment, Mech. Eng. **123** (2001) 44–47

10.39 H. W. Rohrs, R. S. Ruoff: The use of carbon nanotubes in hybrid nanometer-scale devices. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 33–38

10.40 K. E. Drexler: *Engines of Creation: The Coming Era of Nanotechnology* (Anchor Books, New York 1986)

10.41 J. Cumings, A. Zetti: Low-friction nanoscale linear bearing realized from multiwall carbon nanotubes, Science **289** (2000) 602–604

10.42 D. J. Hornbaker, S.-J. Kahng, S. Mirsa, B. W. Smith, A. T. Johnson, E. J. Mele, D. E. Luzzi, A. Yazdoni: Mapping the one-dimensional electronic states of nanotube peapod structures, Science **295** (2002) 828–831

10.43 C. Dekker: Carbon nanotubes as molecular quantum wires, Phys. Today **28** (1999) 22–28

10.44 M.-C. Jones, J.-C. Leroux: Polymeric micelles-a new generation of colloidal drug carriers, Eur. J. Pharma. Biopharma. **48** (1999) 101–111

10.45 I. Uchegbu: Parenteral drug delivery: 1, Pharma. J. **263** (1999) 309–318

10.46 I. Uchegbu: Parenteral drug delivery: 2, Pharma. J. **263** (1999) 355–359

10.47 K. B. Thurmond II, H. Huang, K. L. Wooley: Stabilized micellar structures in nanodevices. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 39–43

10.48 S. Uppuluri, D. R. Swanson, L. T. Peihler, J. Li, G. Hagnauer, D. A. Tomalia: Core shell tecto(dendrimers). I. Synthesis and characterization of saturated shell models, Adv. Mater. **12** (2000) 796–800

10.49 A. K. Patri, I. J. Majoros, J. R. Baker Jr.: Dendritic polymer macromolecular carriers for drug delivery, Curr. Opin. Chem. Biol. **6** (2002) 466–471

10.50 S. Fernandez-Lopez, H.-S. Kim, E. C. Choi, M. Delgado, J. R. Granja, A. Khasanov, K. Kraehenbuehl, G. Long, D. A. Weinberger, K. M. Wilcoxen, M. Ghardiri: Antibacterial agents based on the cyclic D,L-alpha-peptide architecture, Nature **412** (2001) 452–455

10.51 A. Saghatelian, Y. Yokobayashi, K. Soltani, M. R. Ghadiri: A chiroselective peptide replicator, Nature **409** (2001) 777–778

10.52 J. Davies: Aminoglycoside-aminocyclitol antibiotics and their modifying enzymes. In: *Antibiotics in Laboratory Medicine*, ed. by V. Lorian (Williams and Wilkins, Baltimore 1984) pp. 474–489

10.53 T. Hamouda, A. Myc, B. Donovan, A. Y. Shih, J. D. Reuter, J. R. Baker Jr.: A novel surfactant nanoemulsion with a unique non-irritant topical antimicrobial activity against bacteria, enveloped viruses and fungi, Microbiol. Res. **156** (2001) 1–7

10.54 M. J. Heller: Utilization of synthetic DNA for molecular electronic and photonic-based device applications. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 59–66

10.55 Z. Ma, S. Taylor: Nucleic acid triggered catalytic drug release, Proc. Nat. Acad. Sci. USA **97** (2000) 11159–11163

10.56 R. C. Merkle: Biotechnology as a route to nanotechnology, Trends Biotechnol. **17** (1999) 271–274

10.57 N. C. Seeman, J. Chen, Z. Zhang, B. Lu, H. Qiu, T.-J. Fu, Y. Wang, X. Li, J. Qi, F. Liu, L. A. Wenzler, S. Du, J. E. Mueller, H. Wang, C. Mao, W. Sun, Z. Shen, M. H. Wong, R. Sha: A bottom-up approach to nanotechnology using DNA. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 45–58

10.58 G. Lemieux, C. Bertozzi: Chemoselective ligation reactions with proteins, oligosaccharides and cells, Trends Biotechnol. **16** (1998) 506–512

10.59 R. Offord, K. Rose: Multicomponent synthetic constructs. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology, Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 93–105

10.60 G. T. Hermanson: *Bioconjugate Chemistry* (Academic, San Diego 1996)

10.61 S. S. Davis: Biomedical applications of nanotechnology-implications for drug targeting and gene therapy, Trends Biotechnol. **15** (1997) 217–224

10.62 J. C. Roberts, M. K. Bhalgat, R. T. Zera: Preliminary biological evaluation of polyamidoamine (PAMAM) starburst dendrimers, J. Biomed. Mater. Res. **30** (1996) 53–65

10.63 N. S. Nahman, T. Drost, U. Bhatt, T. Sferra, A. Johnson, P. Gamboa, G. Hinkle, A. Haynam, V. Bergdall, C. Hickey, J. D. Bonagura, L. Brannon-Pappas, J. Ellison, A. Mansfield, S. Shiwe, N. Shen: Biodegradable microparticles for in vivo glomerular targeting: Implications for gene therapy of glomerular disease, Biomed. Microdevices **4** (2002) 189–196

10.64 W. Arap, M. Kolonin, M. Trepel, J. Lahdenranta, M. Cardo-Vila, R. Giordano, P. J. Mintz, P. Ardelt, V. Yao, C. Vidal, L. Chen, A. Flamm, H. Valtanen, L. M. Weavind, M. E. Hicks, R. Pollock, G. H. Botz, C. D. Bucana, E. Koivunen, D. Cahil, P. Troncosco, K. A. Baggerly, R. D. Pentz, K.-A. Do, C. Logothetis, R. Pasqualini: Steps towards mapping the human vasculature by phage display, Nature Med. **8** (2002) 121–127

10.65 M. Kolonin, R. Pasqualini, W. Arap: Molecular addresses in blood vessels as targets for therapy, Curr. Opin. Chem. Biol. **5** (2001) 308–313

10.66 E. Ruoslahti: Special delivery of drugs by targeting to tissue-specific receptors in vasculature, Pharmaceutical News **7** (2000) 35–40

10.67 B. K. Kay, J. Winter, J. McCofferty: *Phage Display of Peptides and Proteins* (Academic, San Diego 1996)

10.68 W. Arap, W. Haedicke, M. Bernasconi, R. Kain, D. Rajotte, S. Krajewski, M. Ellerby, R. Pasqualini, E. Ruoslahti: Targeting the prostate for destruction through a vascular address, Proc. Nat. Acad. Sci. USA **99** (2002) 1527–1531

10.69 M. Essier, E. Ruoslahti: Molecular specialization of breast vasculature: A breast homing phage displayed peptide binds to aminopeptidase P in breast vasculature, Proc. Nat. Acad. Sci. USA **99** (2002) 2252–2257

10.70 G. A. Husseini, G. D. Myrup, W. G. Pitt, D. Christensen, N. Y. Rapoport: Factors affecting acoustically triggered release of drugs from polymeric micelles, J. Cont. Release **69** (2000) 43–52

10.71 A. Quintana, E. Raczka, L. Piehler, I. Lee, A. Myc, I. Majoros, A. K. Patri, T. Thomas, J. Mule, J. R. Baker Jr.: Design and function of a dendrimer-based therapeutic nanodevice targeted to tumor cells through the folate receptor, Pharma. Res. **19** (2002) 1310–1316

10.72 P. Shum, J.-M. Kim, D. H. Thompson: Phototriggering of liposomal delivery systems, Adv. Drug Deliv. Rev. **53** (2001) 273–284

10.73 K. Hamad-Schifferli, J. J. Schwartz, A. T. Santos, S. Zhang, J. M. Jacobson: Remote electronic control of DNA hybridization through inductive coupling to an attached metal nanocrystal antenna, Nature **415** (2002) 152–155

10.74 P. Meers: Enzyme-activated targeting of liposomes, Adv. Drug Deliv. Rev. **53** (2001) 265–272

10.75 V. Raso, M. Brown, J. McGrath: Intracellular triggering with low pH-triggered bispecific antibodies, J. Biol. Chem. **272** (1997) 27623–27628

10.76 W. A. Denny: The role of hypoxia activated prodrugs in cancer therapy, The Lancet Oncol. **1** (2000) 25–29

10.77 P. Vaupel, D. K. Kelleher, O. Thews: Modulation of tumor oxygenation, Int. J. Radiation Oncology Biol. Phys. **42** (1998) 843–848

10.78 P. D. Senter, C. J. Springer: Selective activation of anticancer prodrugs by monoclonal antibody-enzyme conjugates, Adv. Drug Deliv. Rev. **53** (2001) 247–264

10.79 H. Wang, H. Song, V. C. Yang: A recombinant prodrug type approach for triggered delivery of streptokinase, J. Cont. Release **59** (1999) 119–122

10.80 R. Duncan: Polymer therapeutics for tumor specific delivery, Chem. Industry **7** (1997) 262–264

10.81 K. Rogers: Principles of affinity-based biosensors, Mol. Biotechnol. **14** (2000) 109–129

10.82 R. Raiteri, M. Grattarola, H.-J. Butt, P. Skladl: Micromechanical cantilever-based biosensors, Sensors Actuat. B **79** (2001) 115–126

10.83 R. Martel, T. Schmidt, H. R. Shea, T. Hertel, P. Avouris: Single and multiwall carbon nanotube field-effect transistors, Appl. Phys. Lett. **73** (1998) 2447–2449

10.84 A. Guiseppi-Elie, C. Lei, R. H. Baughman: Direct electron transfer of glucose oxidase on carbon nanotubes, Nanotechnology **13** (2002) 559–564

10.85 C. N. Campbell: How far are we from detecting single bioconjugation events?. In: *Biological Molecules in Nanotechnology: The Convergence of Biotechnology Polymer Chemistry and Materials Science*, ed. by S. C. Lee, L. Savage (IBC, Southborough 1998) pp. 163–171

10.86 W. D. Callister Jr.: *Material Science and Engineering: an Introduction* (Wiley, New York 1997)

10.87 M. Gerard, A. Chaubey, B. D. Malhotra: Applications of conducting polymers to biosensors, Biosens. Bioelectron. **17** (2002) 345–349

10.88 P. N. Bartlett, Y. Astier: Microelectrochemical enzyme transistors, Chem. Commun. **2** (2000) 105–112

10.89 I. Kleps, A. Angelscu, R. Valisco, D. Dascalu: New micro and nanoelectrode arrays for biomedical applications, Biomed. Microdevices **3** (2001) 29–33

10.90 J. Song, Q. Cheng, S. Zhu, R. C. Stevens: "smart" materials for biosensing devices: cell-mimicking supramolecular assemblies and colorometric detection of pathogenic agents, Biomed. Microdevices **4** (2002) 213–222

10.91 M. Brown, R. Semelka: *MRI: Basic Principles and Applications* (Wiley, New York 1999)

10.92 A. Elster, S. Handel, A. Goldman: *Magnetic Resonance Imaging: A Reference Guide and Atlas* (Lippincott, Philadelphia 1997)

10.93 H. Paajanen, M. Kormano: Contrast agents in magnetic resonance imaging. In: *Radiographic Contrast Agents*, ed. by J. Skucas (Aspen, Rockville 1989) pp. 377–406

10.94 L. Thunus, R. Lejeune: Overview of transition metal and lanthanide complexes as diagnostic tools, Coord. Chem. Rev. **184** (1999) 125–155

10.95 M. Mendoca-Dias, E. Gaggelli, P. Lauterbur: Paramagnetic contrast agents in nuclear magnetic resonance medical imaging, Sem. Nuclear Med. **13** (1983) 364–376

10.96 M. Ollsen, B. Persson, L. Salford: Ferromagnetic particles as contrast agent in T2 NMR imaging, Magn. Reson. Imag. **4** (1986) 437–440

10.97 D. Kehagias, A. Gouliamos, V. Smyrniotis, L. Vlahos: Diagnostic efficacy and safety of MRI of the liver with superparamagnetic iron oxide particles (SH U 555 A), J. Magn. Reson. Im. **14** (2001) 595–601

10.98 C. Nolte-Ernsting, G. Adam, A. Bucker, S. Berges, A. Bjornerud, R. Gunther: Abdominal MR angiography performed using blood pool contrast agents, Am. J. Roentgenol. **171** (1998) 107–113

10.99 F. Rety, O. Clement, N. Siauve, C.-A. Cuenod, F. Carnot, M. Sich, A. Buisine, G. Frija: MR lymphography using iron oxide nanoparticles in rats: pharmacokinetics in the lymphatic system after intravenous injection, J. Magn. Reson. Im. **12** (2000) 734–739

10.100 T. Skotland, P. Sontum, I. Oulie: In vitro stability analyses as a model for metabolism of ferromagnetic particles (Clariscan^{TM}), a contrast agent for magnetic resonance imaging, J. Pharm. Biomed. Anal. **28** (2002) 323–329

10.101 D. Hogemann, L. Josephson, R. Weissleder, J. Basilion: Improvement of MRI probes to allow efficient detection of gene expression, Bioconjugate Chem. **11** (2000) 941–946

10.102 L. L. Muldoon, M. A. Pagel, R. A. Kroll, S. Roman-Goldstein, R. S. Jones, E. A. Neuwelt: A physiological barrier distal to the anatomic blood-brain barrier in a model of transvascular delivery, AJNR Am. J. Neuroradial. **20** (1999) 217–222

10.103 G. Biddlecombe, Y. Gun'ko, J. Kelly, S. Pillai, J. Coey, M. Ventatesan, A. Douvalis: Preparation of magnetic nanoparticles and their assemblies using a new Fe(II) alkoxide precursor, J. Mater. Chem. **11** (2001) 2937–2939

10.104 L. Tiefenauer, G. Kuhne, R. Andres: Antibody-magnetite nanoparticles: in vitro characterization of a potential tumor-specific contrast agent for magnetic resonance imaging, Bioconjugate Chem. **4** (1993) 347–352

10.105 C. Liu, Z. Zhang: Size-dependent superparamagnetic properties of Mn spinel ferrite nanoparticles synthesized from reverse micelles, Chem. Mater. **13** (2001) 2092–2096

10.106 J. Schnorr, M. Taupitz, S. Wagner, H. Pilgrimm, J. Hansel, B. Hamm: Age-related blood half-life of particulate contrast materials: Experimental results with a USPIO in rats, J. Magn. Reson. Im. **12** (2000) 740–744

10.107 R. Weissleder, G. Elizondo, J. Wittenberg, C. Rabito, H. Bengele, L. Josephson: Ultrasmall superparamagnetic iron oxide: Characterization of a new class of contrast agents for MR imaging, Radiology **175** (1990) 489–493

10.108 D. Portet, B. Denizot, E. Rump, J.-J. Lejeune, P. Jallet: Nonpolymeric coatings of iron oxide colloids for biological use as magnetic resonance imaging contrast agents, J. Coll. Inter. Sci. **238** (2001) 37–42

10.109 M. Ruegsegger, R. Marchant: Reduced protein adsorption and platelet adhesion by controlled variation of oligomaltose surfactant polymer coatings, J. Biomed. Mater. Res. **56** (2001) 159–167

10.110 S. Flack, S. Fischer, M. Scott, R. Fuhrhop, J. Allen, M. McLean, P. Winter, G. Sicard, P. Gaffney, S. Wickline, G. Lanza: Novel MRI contrast agent for molecular fibrin, Circulation **104** (2001) 1280–1285

10.111 D. F. Baban, L. W. Seymour: Control of tumor vascular permeability, Adv. Drug Deliv. Rev. **34** (1998) 109–119

10.112 R. K. Jain: Delivery of molecular and cellular medicine to tumors, J. Cont. Release **53** (1998) 49–67

10.113 H. Maeda, T. Sawa, T. Konno: Mechanism of tumor-targeted delivery of macromolecular drugs, including the EPR effect in solid tumor and clinical overview of the prototype polymeric drug SMANCS, J. Cont. Release **74** (2001) 47–61

10.114 J. Borenstein, H. Terai, K. King, E. Weinberg, M. Kaazempour-Mofrad, J. Vacanti: Microfabrication technology for vascularized tissue engineering, Biomed. Microdevices **4** (2002) 167–175

10.115 D. Satake, H. Ebi, N. Oku, K. Matsuda, H. Takao, M. Ashiki, M. Ishida: A sensor for blood cell counters using MEMS technology, Sensors Actuat. B – Chem. **83** (2002) 77–81

10.116 G. Lin, R. Palmer, K. Pister, K. Roos: Miniature heart cell force transducer system implemented in MEMS technology, IEEE Trans. Biomed. Engin. **48** (2001) 996–1006

10.117 J. Kreuter, D. Shamenkov, V. Petrov, P. Ramge, K. Cychutek, C. Koch-Brandt, R. Alyautdin: Apolipoprotein-mediated transport of nanoparticle-bound drugs across the blood-brain barrier, J. Drug Target **10** (2002) 317–325

10.118 P. Lockman, R. Mumper, M. Khan, D. Allen: Nanoparticle technology for drug delivery across the blood-brain barrier, Drug Devel. Indust. Pharm. **28** (2002) 1–13

10.119 H. Quick, J. Debatin, M. Ladd: MR imaging of the vessel wall, Eur. Radiol. **12** (2002) 889–900

10.120 S. Schmitz, M. Taupitz, S. Wagner, K.-J. Wolf, D. Beyersdorff, D. Hamm: Magnetic resonance imaging of atherosclerotic plaques using supermagnetic iron oxide particles, J. Magn. Reson. Im. **14** (2001) 355–361

10.121 D. Ranney: Biomimetic transport and rational drug delivery, Biochem. Pharm. **59** (2000) 105–114

10.122 K. Soppimath, T. Aminabhavi, A. Kulkarni, W. Rudzinski: Biodegradable polymeric nanoparticles as drug delivery devices, J. Cont. Release **70** (2001) 1–20

10.123 F. Breitling, S. Dubel: *Recombinant Antibodies* (Wiley, London 1998)

10.124 E. Harlow, D. Lane: *Antibodies: A Laboratory Manual* (Cold Spring Harbor Press, Cold Spring Harbor 1988)

10.125 S. Raychanduri, K. L. Rock: Fully mobilizing host defense: Building better vaccines, Nature Biotech. **16** (1998) 1025–1031

10.126 M. Kovasovics-Bankowski, K. Clark, B. Benacerraf, K. L. Rock: Efficient major histocompatibility complex class I presentation of exogenous antigen upon phagocytosis by macrophages, Proc. Nat. Acad. Sci. USA **90** (1993) 4942–4946

10.127 K. Rock, S. Gamble, L. Rothstein: Presentation of exogenous antigen with class I major histocompatibility complex molecules, Science **249** (1990) 918–921

10.128 C. V. Harding, R. Song: Phagocytic processing of exogenous particulate antigens by macrophages for presentation by class I MHC molecules, J. Immunol. **152** (1994) 4925–4933

10.129 C. Oseroff, A. Sette, P. Wentworth, E. Celis, A. Maewal, C. Dahlberg, J. Fikes, R. T. Kubo, R. W. Chestnut, H. M. Grey, J. Alexander: Pools of lapidated HTL-CTL constructs prime for multiple HBV and HCV CTL epitope responses, Vaccine **16** (1998) 823–833

10.130 R. Mrsny, A. L. Daughtery, M. Mckee, D. Fitzgerald: Bacterial toxins as tools for mucosal vaccination, Drug Disc. Today **7** (2000) 247–257

10.131 S. Fawell, J. Seery, Y. Daikh, C. Moore, L. L. Chen, B. Pepinsky, J. Barsoum: Tat-mediated delivery of heterologous proteins to cells, Proc. Nat. Acad. Sci. USA **91** (1994) 664–668

10.132 T. J. Golentz, K. Klimpel, S. Leppla, J. M. Keith, J. A. Berzofsky: Delivery of antigens to the MHC class I pathway using bacterial toxins, Hum. Immunol. **54** (1997) 129–136

10.133 B.-X. Chen, S.R. Wilson, M. Das, D.J. Coughlin, B.F. Erlanger: Antigenicity of fullerenes: antibodies specific for fullerenes and their characteristics, Proc. Nat. Acad. Sci. USA **95** (1998) 10809–10813

10.134 S.C. Lee, R. Ibdah, C.D. van Valkenburgh, E. Rowold, A. Donelly, A. Abegg, J. Klover, S. Merlin, J. McKearn: Phage display mutagenesis of the chimeric dual cytokine receptor agonist myelopoietin, Leukemia **15** (2001) 1277–1285

10.135 S.C. Lee, R. Parthasarathy, K. Botwin, D. Kunneman, E. Rowold, G. Lange, J. Zobel, T. Beck, T. Miller, C.F. Voliva: Humeral immune responses to polymeric nanomaterials. In: *Functional Condensation Polymers*, ed. by C. Carraher, G. Swift (Kluwer, New York 2002) pp. 31–41

10.136 S.C. Lee, R. Parthasarathy, T. Duffin, K. Botwin, T. Beck, G. Lange, J. Zobel, D. Kunneman, E. Rowold, C.F. Voliva: Recognition properties of antibodies to PAMAM dendrimers and their use in immune detection of dendrimers, Biomed. Microdevices **3** (2001) 51–57

10.137 A.H. Sehon: Suppression of antibody responses by conjugates of antigens and monomethoxypoly(ethylene glycol). In: *Poly(ethylene glycol) Chemistry*, ed. by J.M. Harris (Plenum, New York 1992) pp. 139–151

10.138 R.P. Lanza, S.J. Sullivan, W.L. Chick: Perspectives in diabetes. Islet transplantation with immunoisolation, Diabetes **41** (1992) 1503–1510

10.139 R. Gordon: Computer controlled evolution of diatoms: Design for a compustat, Nova Hedwigia **112** (1996) 215–219

10.140 J. Parkinson, R. Gordon: Beyond micromachining: The potential of diatoms, Trends Biotechnol. **17** (1999) 190–196

10.141 S. C. Lee: Antibody responses to nanomaterials. In: *Nanospace 2001: Exploring Interdisciplinary Frontiers*, ed. by T. Nicodemus (Institute for Advanced Interdisciplinary Research, Houston 2002)

10.142 K. Pearce, B. Cunningham, G. Fuh, T. Teeri, J.A. Wells: Growth hormone affinity for its receptor surpasses the requirements for cellular activity, Biochem. **38** (1999) 81–89

10.143 T.L. Ciardelli: Reengineering growth factors through the looking glass, Nat. Biotechnol. **14** (1996) 1652

10.144 P.J. Buchli, Z. Wu, T.L. Ciardelli: Functional display of interleukin-2 on filamentous phage, Arch. Biochem. Biophys. **339** (1997) 79–84

10.145 I. Saggio, I. Gloaguen, R. Laufer: Functional phage display of cilliary neurotropic factor, Gene **152** (1995) 35–39

Part B
Scanning

Part B Scanning Probe Microscopy

11 Scanning Probe Microscopy – Principle of Operation, Instrumentation, and Probes
Bharat Bhushan, Columbus, USA
Othmar Marti, Ulm, Germany

12 Probes in Scanning Microscopies
Jason H. Hafner, Houston, USA

13 Noncontact Atomic Force Microscopy and Its Related Topics
Seizo Morita, Suita-Citiy, Osaka, Japan
Franz J. Giessibl, Augsburg, Germany
Yasuhiro Sugawara, Suita, Japan
Hirotaka Hosoi, Sapporo, Japan
Koichi Mukasa, Sapporo, Japan
Akira Sasahara, Kanagawa, Japan
Hiroshi Onishi, Kanagawa, Japan

14 Low Temperature Scanning Probe Microscopy
Markus Morgenstern, Hamburg, Germany
Alexander Schwarz, Hamburg, Germany
Udo D. Schwarz, New Haven, USA

15 Dynamic Force Microscopy
A. Schirmeisen, Münster, Germany
B. Anczykowski, Münster, Germany
Harald Fuchs, Münster, Germany

16 Molecular Recognition Force Microscopy
Peter Hinterdorfer, Linz, Austria

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

11. Scanning Probe Microscopy – Principle of Operation, Instrumentation, and Probes

Scanning Pro

Since the introduction of the STM in 1981 and AFM in 1985, many variations of probe based microscopies, referred to as SPMs, have been developed. While the pure imaging capabilities of SPM techniques is dominated by the application of these methods at their early development stages, the physics of probe–sample interactions and the quantitative analyses of tribological, electronic, magnetic, biological, and chemical surfaces have now become of increasing interest. Nanoscale science and technology are strongly driven by SPMs which allow investigation and manipulation of surfaces down to the atomic scale. With growing understanding of the underlying interaction mechanisms, SPMs have found applications in many fields outside basic research fields. In addition, various derivatives of all these methods have been developed for special applications, some of them targeted far beyond microscopy.

This chapter presents an overview of STM and AFM and various probes (tips) used in these instruments, followed by details on AFM instrumentation and analyses.

11.1 **Scanning Tunneling Microscope** 327
- 11.1.1 Binnig et al.'s Design.................... 327
- 11.1.2 Commercial STMs.......................... 328
- 11.1.3 STM Probe Construction 330

11.2 **Atomic Force Microscope** 331
- 11.2.1 Binnig et al.'s Design.................... 333
- 11.2.2 Commercial AFM.......................... 333
- 11.2.3 AFM Probe Construction 338
- 11.2.4 Friction Measurement Methods...... 342
- 11.2.5 Normal Force and Friction Force Calibrations of Cantilever Beams...................... 346

11.3 **AFM Instrumentation and Analyses** 347
- 11.3.1 The Mechanics of Cantilevers 347
- 11.3.2 Instrumentation and Analyses of Detection Systems for Cantilever Deflections 350
- 11.3.3 Combinations for 3-D-Force Measurements 358
- 11.3.4 Scanning and Control Systems 359

References 364

The Scanning Tunneling Microscope (STM) developed by *Dr. Gerd Binnig* and his colleagues in 1981 at the IBM Zurich Research Laboratory, Rueschlikon, Switzerland, is the first instrument capable of directly obtaining three-dimensional (3-D) images of solid surfaces with atomic resolution [11.1]. *Binnig* and *Rohrer* received a Nobel Prize in Physics in 1986 for their discovery. STMs can only be used to study surfaces which are electrically conductive to some degree. Based on their design of the STM, in 1985, *Binnig* et al. developed an Atomic Force Microscope (AFM) to measure ultrasmall forces (less than $1\,\mu\text{N}$) present between the AFM tip surface and the sample surface [11.2] (also see [11.3]). AFMs can be used for measurement of all engineering surfaces which may be either electrically conductive or insulating. The AFM has become a popular surface profiler for topographic and normal force measurements on the micro to nanoscale [11.4]. AFMs modified in order to measure both normal and lateral forces, are called Lateral Force Microscopes (LFMs) or Friction Force Microscopes (FFMs) [11.5–11]. FFMs have been further modified to measure lateral forces in two orthogonal directions [11.12–16]. A number of researchers have continued to improve the AFM/FFM designs and used them to measure adhesion and friction of solid and liquid surfaces on micro- and nanoscales [11.4, 17–30]. AFMs have been used for scratching, wear, and measurement of elastic/plastic mechanical properties (such as indentation hardness and the modulus of elasticity) [11.4,10,11,21,23,26–29,31–36]. AFMs have been used for manipulation of individual atoms of Xenon [11.37], molecules [11.38], silicon surfaces [11.39], and polymer surfaces [11.40]. STMs have been used for formation of nanofeatures by localized heating or by inducing chemical reactions under the STM tip [11.41–43] and nanomachining [11.44]. AFMs

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Table 11.1 Comparison of Various Conventional Microscopes with SPMs

	Optical	SEM/TEM	Confocal	SPM
Magnification	10^3	10^7	10^4	10^9
Instrument Price (U.S. $)	$10 k	$250 k	$30 k	$100 k
Technology Age	200 yrs	40 yrs	20 yrs	20 yrs
Applications	Ubiquitous	Science and technology	New and unfolding	Cutting edge
Market 1993	$800 M	$400 M	$80 M	$100 M
Growth Rate	10%	10%	30%	70%

have been used for nanofabrication [11.4, 10, 45–47] and nanomachining [11.48].

STMs and AFMs are used at extreme magnifications ranging from 10^3 to 10^9 in x, y and z directions for imaging macro to atomic dimensions with high resolution information and for spectroscopy. These instruments can be used in any environment such as ambient air [11.2, 49], various gases [11.17], liquid [11.50–52], vacuum [11.1, 53], at low temperatures (lower than about 100 K) [11.54–58] and high temperatures [11.59, 60]. Imaging in liquid allows the study of live biological samples and it also eliminates water capillary forces present in ambient air present at the tip–sample interface. Low temperature (liquid helium temperatures) imaging is useful for the study of biological and organic materials and the study of low-temperature phenomena such as superconductivity or charge-density waves. Low-temperature operation is also advantageous for high-sensitivity force mapping due to the reduction in thermal vibration. They also have been used to image liquids such as liquid crystals and lubricant molecules on graphite surfaces [11.61–64]. While the pure imaging capabilities of SPM techniques dominated the application of these methods at their early development stages, the physics and chemistry of probe–sample interactions and the quantitative analyses of tribological, electronic, magnetic, biological, and chemical surfaces have now become of increasing interest. Nanoscale science and technology are strongly driven by SPMs which allow investigation and manipulation of surfaces down to the atomic scale. With growing understanding of the underlying interaction mechanisms, SPMs have found applications in many fields outside basic research fields. In addition, various derivatives of all these methods have been developed for special applications, some of them targeting far beyond microscopy.

Families of instruments based on STMs and AFMs, called Scanning Probe Microscopes (SPMs), have been developed for various applications of scientific and industrial interest. These include – STM, AFM, FFM (or LFM), scanning electrostatic force microscopy (SEFM) [11.65, 66], scanning force acoustic microscopy (SFAM) (or atomic force acoustic microscopy (AFAM)) [11.21, 22, 36, 67–69], scanning magnetic microscopy (SMM) (or magnetic force microscopy (MFM)) [11.70–73], scanning near field optical microscopy (SNOM) [11.74–77], scanning thermal microscopy (SThM) [11.78–80], scanning electrochemical microscopy (SEcM) [11.81], scanning Kelvin Probe microscopy (SKPM) [11.82–86], scanning chemical potential microscopy (SCPM) [11.79], scanning ion conductance microscopy (SICM) [11.87, 88], and scanning capacitance microscopy (SCM) [11.82, 89–91]. Families of instruments which measure forces (e.g., AFM, FFM, SEFM, SFAM, and SMM) are also referred to as scanning force microscopy (SFM). Although these instruments offer atomic resolution and are ideal for basic research, they are used for cutting edge industrial applications which do not require atomic resolution. Commercial production of SPMs started with the STM in 1987 and the AFM in 1989 by Digital Instruments Inc. For comparisons of SPMs with other microscopes, see Table 11.1 (Veeco Instruments, Inc.). Numbers of these instruments are equally divided between the U.S., Japan and Europe, with the following industry/university and Government labs. splits: 50/50, 70/30, and 30/70, respectively. It is clear that research and industrial applications of SPMs are rapidly expanding.

11.1 Scanning Tunneling Microscope

The principle of electron tunneling was proposed by *Giaever* [11.92]. He envisioned that if a potential difference is applied to two metals separated by a thin insulating film, a current will flow because of the ability of electrons to penetrate a potential barrier. To be able to measure a tunneling current, the two metals must be spaced no more than 10 nm apart. *Binnig* et al. [11.1] introduced vacuum tunneling combined with lateral scanning. The vacuum provides the ideal barrier for tunneling. The lateral scanning allows one to image surfaces with exquisite resolution, lateral-less than 1 nm and vertical-less than 0.1 nm, sufficient to define the position of single atoms. The very high vertical resolution of the STM is obtained because the tunnel current varies exponentially with the distance between the two electrodes, that is, the metal tip and the scanned surface. Typically, tunneling current decreases by a factor of 2 as the separation is increased by 0.2 nm. Very high lateral resolution depends upon sharp tips. *Binnig* et al. overcame two key obstacles for damping external vibrations and for moving the tunneling probe in close proximity to the sample. Their instrument is called the scanning tunneling microscope (STM). Today's STMs can be used in the ambient environment for atomic-scale image of surfaces. Excellent reviews on this subject are presented by *Hansma* and *Tersoff* [11.93], *Sarid* and *Elings* [11.94], *Durig* et al. [11.95]; *Frommer* [11.96], *Güntherodt* and *Wiesendanger* [11.97], *Wiesendanger* and *Güntherodt* [11.98], *Bonnell* [11.99], *Marti* and *Amrein* [11.100], *Stroscio* and *Kaiser* [11.101], and *Güntherodt* et al. [11.102].

The principle of the STM is straightforward. A sharp metal tip (one electrode of the tunnel junction) is brought close enough (0.3–1 nm) to the surface to be investigated (the second electrode) that, at a convenient operating voltage (10 mV–1 V), the tunneling current varies from 0.2 to 10 nA which is measurable. The tip is scanned over a surface at a distance of 0.3–1 nm, while the tunneling current between it and the surface is measured. The STM can be operated in either the constant current mode or the constant height mode, Fig. 11.1. The left-hand column of Fig. 11.1 shows the basic constant current mode of operation. A feedback network changes the height of the tip z to keep the current constant. The displacement of the tip given by the voltage applied to the piezoelectric drives then yields a topographic map of the surface. Alternatively, in the constant height mode, a metal tip can be scanned across a surface at nearly constant height and constant voltage while the current is monitored, as shown in the right-hand column of Fig. 11.1. In this case, the feedback network responds only rapidly enough to keep the average current constant. A current mode is generally used for atomic-scale images. This mode is not practical for rough surfaces. A three-dimensional picture $[z(x, y)]$ of a surface consists of multiple scans $[z(x)]$ displayed laterally from each other in the y direction. It should be noted that if different atomic species are present in a sample, the different atomic species within a sample may produce different tunneling currents for a given bias voltage. Thus the height data may not be a direct representation of the topography of the surface of the sample.



Fig. 11.1 STM can be operated in either the constant-current or the constant-height mode. The images are of graphite in air [11.93]

11.1.1 Binnig et al.'s Design

Figure 11.2 shows a schematic of one of Binnig and Rohrer's designs for operation in ultrahigh vacuum [11.1, 103]. The metal tip was fixed to rectangular piezodrives P_x, P_y, and P_z made out of commercial piezoceramic material for scanning. The sample is mounted via either superconducting magnetic levitation or a two-stage spring system to achieve a stability of the gap width of about 0.02 nm. The tunnel current J_T is a sensitive function of the gap width d that is $J_\mathrm{T} \propto V_\mathrm{T} \exp(-A\phi^{1/2}d)$, where V_T is the bias voltage, ϕ is the average barrier height (work function) and the constant $A = 1.025\,\mathrm{eV}^{-1/2}\,\text{Å}^{-1}$. With a work function of a few eV, J_T changes by an order of magnitude for



Fig. 11.2 Principle of operation of the STM made by *Binnig* and *Rohrer* [11.103]



Fig. 11.3 Principle of operation of a commercial STM, a sharp tip attached to a piezoelectric tube scanner is scanned on a sample

every angstrom change of d. If the current is kept constant to within, for example, 2%, then the gap d remains constant to within 1 pm. For operation in the constant current mode, the control unit CU applies a voltage V_z to the piezo P_z such that J_T remains constant when scanning the tip with P_y and P_x over the surface. At constant work function ϕ, $V_z(V_x, V_y)$ yields the roughness of the surface $z(x, y)$ directly, as illustrated at a surface step at A. Smearing the step, δ (lateral resolution) is on the order of $(R)^{1/2}$, where R is the radius of the curvature of the tip. Thus, a lateral resolution of about 2 nm requires tip radii on the order of 10 nm. A 1-mm-diameter solid rod ground at one end at roughly 90° yields overall tip radii of only a few hundred nm, but with closest protrusion of rather sharp microtips on the relatively dull end yields a lateral resolution of about 2 nm. In-situ sharpening of the tips by gently touching the surface brings the resolution down to the 1-nm range; by applying high fields (on the order of 10^8 V/cm) during, for example, half an hour, resolutions considerably below 1 nm could be reached. Most experiments were done with tungsten wires either ground or etched to a radius typically in the range of 0.1–10 µm. In some cases, in-situ processing of the tips was done for further reduction of tip radii.

11.1.2 Commercial STMs

There are a number of commercial STMs available on the market. Digital Instruments, Inc. located in Santa Barbara, CA introduced the first commercial STM, the Nanoscope I, in 1987. In a recent Nanoscope IV STM for operation in ambient air, the sample is held in position while a piezoelectric crystal in the form of a cylindrical tube (referred to as PZT tube scanner) scans the sharp metallic probe over the surface in a raster pattern while sensing and outputting the tunneling current to the control station (Fig. 11.3). The digital signal processor (DSP) calculates the desired separation of the tip from the sample by sensing the tunneling current flowing between the sample and the tip. The bias voltage applied between the sample and the tip encourages the tunneling current to flow. The DSP completes the digital feedback loop by outputting the desired voltage to the piezoelectric tube. The STM operates in both the "constant height" and "constant current" modes depending on a parameter selection in the control panel. In the constant current mode, the feedback gains are set high, the tunneling tip closely tracks the sample surface, and the variation in the tip height required to maintain constant tunneling current is measured by the change in the voltage applied to the piezo tube. In the constant height mode, the feedback gains are set low, the tip remains at a nearly constant height as it sweeps over the sample surface, and the tunneling current is imaged.

Physically, the Nanoscope STM consists of three main parts: the head which houses the piezoelectric tube scanner for three dimensional motion of the tip and the preamplifier circuit (FET input amplifier) mounted on top of the head for the tunneling current, the base on which the sample is mounted, and the base support, which supports the base and head [11.4]. The base accommodates samples up to 10 mm by 20 mm and 10 mm in thickness. Scan sizes available for the STM are 0.7 µm (for atomic resolution), 12 µm, 75 µm and 125 µm square.

The scanning head controls the three dimensional motion of the tip. The removable head consists of a piezo tube scanner, about 12.7 mm in diameter, mounted into an invar shell used to minimize vertical thermal drifts because of a good thermal match between the piezo tube and the Invar. The piezo tube has separate electrodes for X, Y and Z which are driven by separate drive circuits.

The electrode configuration (Fig. 11.3) provides x and y motions which are perpendicular to each other, minimizes horizontal and vertical coupling, and provides good sensitivity. The vertical motion of the tube is controlled by the Z electrode which is driven by the feedback loop. The x and y scanning motions are each controlled by two electrodes which are driven by voltages of the same magnitude, but opposite signs. These electrodes are called $-Y$, $-X$, $+Y$, and $+X$. Applying complimentary voltages allows a short, stiff tube to provide a good scan range without large voltages. The motion of the tip due to external vibrations is proportional to the square of the ratio of vibration frequency to the resonant frequency of the tube. Therefore, to minimize the tip vibrations, the resonant frequencies of the tube are high at about 60 kHz in the vertical direction and about 40 kHz in the horizontal direction. The tip holder is a stainless steel tube with a 300 µm inner diameter for 250 µm diameter tips, mounted in ceramic in order to keep the mass on the end of the tube low. The tip is mounted either on the front edge of the tube (to keep mounting mass low and resonant frequency high) (Fig. 11.3) or the center of the tube for large range scanners, namely 75 and 125 µm (to preserve the symmetry of the scanning). This commercial STM accepts any tip with a 250 µm diameter shaft. The piezotube requires X-Y calibration which is carried out by imaging an appropriate calibration standard. Cleaved graphite is used for the small-scan length head while two dimensional grids (a gold plated ruling) can be used for longer range heads.

The Invar base holds the sample in position, supports the head, and provides coarse X-Y motion for the sample. A spring-steel sample clip with two thumb screws holds the sample in place. An x-y translation stage built into the base allows the sample to be repositioned under the tip. Three precision screws arranged in a triangular pattern support the head and provide coarse and fine adjustment of the tip height. The base support consists of the base support ring and the motor housing. The stepper motor enclosed in the motor housing allows the tip to be engaged and withdrawn from the surface automatically.

Samples to be imaged with the STM must be conductive enough to allow a few nanoamperes of current to flow from the bias voltage source to the area to be scanned. In many cases, nonconductive samples can be coated with a thin layer of a conductive material to facilitate imaging. The bias voltage and the tunneling current depend on the sample. Usually they are set at a standard value for engagement and fine tuned to enhance the quality of the image. The scan size depends on the sample and the features of interest. A maximum scan rate of 122 Hz can be used. The maximum scan rate is usually related to the scan size. Scan rates above 10 Hz are used for small scans (typically 60 Hz for atomic-scale imaging with a 0.7 µm scanner). The scan rate should be lowered for large scans, especially if the sample surfaces are rough or contain large steps. Moving the tip quickly along the sample surface at high scan rates with large scan sizes will usually lead to a tip crash. Essentially, the scan rate should be inversely proportional to the scan size (typically 2–4 Hz for 1 µm, 0.5–1 Hz for 12 µm, and 0.2 Hz for 125 µm scan sizes). Scan rate in length/time, is equal to scan length divided by the scan rate in Hz. For example, for 10 µm × 10 µm scan size scanned at 0.5 Hz, the scan rate is 10 µm/s. Typically, 256×256 data formats are most commonly used. The lateral resolution at larger scans is approximately equal to scan length divided by 256.



Fig. 11.4 STM images of evaporated C$_{60}$ film on a gold-coated freshly-cleaved mica using a mechanically sheared Pt-Ir (80-20) tip in constant height mode [11.104]

Figure 11.4 shows an example of STM images of an evaporated C_{60} film on a gold-coated freshly-cleaved mica taken at room temperature and ambient pressure [11.104]. Images with atomic resolution at two scan sizes are obtained. Next we describe STM designs which are available for special applications.

Electrochemical STM

The electrochemical STM is used to perform and monitor the electrochemical reactions inside the STM. It includes a microscope base with an integral potentiostat, a short head with a 0.7 µm scan range and a differential preamp and the software required to operate the potentiostat and display the result of the electrochemical reaction.

Standalone STM

The stand alone STMs are available to scan large samples which rest directly on the sample. From Digital instruments, it is available in 12 and 75 µm scan ranges. It is similar to the standard STM except the sample base has been eliminated.

11.1.3 STM Probe Construction

The STM probe should have a cantilever integrated with a sharp metal tip with a low aspect ratio (tip length/tip shank) to minimize flexural vibrations. Ideally, the tip should be atomically sharp, but in practice most tip preparation methods produce a tip with a rather ragged profile that consists of several asperities with the one closest to the surface responsible for tunneling. STM cantilevers with sharp tips are typically fabricated from metal wires of tungsten (W), platinum-iridium (Pt-Ir), or gold (Au) and sharpened by grinding, cutting with a wire cutter or razor blade, field emission/evaporator, ion milling, fracture, or electrochemical polishing/etching [11.105, 106]. The two most commonly used tips are made from either a Pt-Ir (80/20) alloy or tungsten wire. Iridium is used to provide stiffness. The Pt-Ir tips are generally mechanically formed and are readily available. The tungsten tips are etched from tungsten wire with an electrochemical process, for example by using 1 molar KOH solution with a platinum electrode in a electrochemical cell at about 30 V. In general, Pt-Ir tips provide better atomic resolution than tungsten tips, probably due to the lower reactivity of Pt. But tungsten tips are more uniformly shaped and may perform better on samples with steeply sloped features. The tungsten wire diameter used for the cantilever is typically 250 µm with the radius of curvature ranging from 20 to 100 nm and a cone angle ranging from 10 to 60° (Fig. 11.5). The wire can be bent in an L shape, if so required, for use in the instrument. For calculations of normal spring constant and natural frequency of round cantilevers, see *Sarid* and *Elings* [11.94].



Fig. 11.5 Schematic of a typical tungsten cantilever with a sharp tip produced by electrochemical etching

For imaging of deep trenches, high-aspect-ratio, controlled geometry (CG) Pt-Ir probes are commercially available (Fig. 11.6). These probes are electrochemically etched from Pt-Ir (80/20) wire and polished to a specific shape which is consistent from tip to tip. Probes have a full cone angle of approximately 15°, and a tip radius of less than 50 nm. For imaging of very deep trenches (> 0.25 µm) and nanofeatures, focused ion beam (FIB) milled CG probes with an extremely sharp tip (radius < 5 nm) are used. For electrochemistry, Pt/Ir probes are coated with a nonconducting film (not shown in the figure). These probes are available from Materials Analytical Services, Raleigh, North Carolina.

Pt alloy and W tips are very sharp and have high resolution, but are fragile and sometimes break when contacting a surface. Diamond tips have been used by *Kaneko* and *Oguchi* [11.107]. The diamond tip made conductive by boron ion implantation is found to be chip resistant.



Fig. 11.6a,b Schematics of **(a)** CG Pt-Ir probe, and **(b)** CG Pt-Ir FIB milled probe

11.2 Atomic Force Microscope

Like the STM, the AFM relies on a scanning technique to produce very high resolution, 3-D images of sample surfaces. The AFM measures ultrasmall forces (less than 1 nN) present between the AFM tip surface and a sample surface. These small forces are measured by measuring the motion of a very flexible cantilever beam having an ultrasmall mass. While STMs require that the surface to be measured be electrically conductive, AFMs are capable of investigating surfaces of both conductors and insulators on an atomic scale if suitable techniques for measurement of cantilever motion are used. In the operation of a high resolution AFM, the sample is generally scanned instead of the tip as with the STM, because the AFM measures the relative displacement between the cantilever surface and reference surface and any cantilever movement would add vibrations. For measurements of large samples, AFMs are available where the tip is scanned and the sample is stationary. As long as the AFM is operated in the so-called contact mode, little if any vibration is introduced.

The AFM combines the principles of the STM and the stylus profiler (Fig. 11.7). In an AFM, the force between the sample and tip is detected, rather than the tunneling current, to sense the proximity of the tip to the sample. The AFM can be used either in a static or dynamic mode. In the static mode, also referred to as repulsive mode or contact mode [11.2], a sharp tip at the end of a cantilever is brought in contact with a sample surface. During initial contact, the atoms at the end of the tip experience a very weak repulsive force due to electronic orbital overlap with the atoms in the sample surface. The force acting on the tip causes a cantilever deflection which is measured by tunneling, capacitive, or optical detectors. The deflection can be measured to within 0.02 nm, so for typical cantilever spring constant of 10 N/m a force as low as 0.2 nN (corresponding normal pressure ∼ 200 MPa for a Si_3N_4 tip with radius of about 50 nm against single-crystal silicon) can be detected. (To put these number in perspective, individual atoms and human hair are typically a fraction of a nanometer and about 75 µm in diameter, respectively, and a drop of water and an eyelash have a mass of about 10 µN and 100 nN, respectively.) In the dynamic mode of operation for the AFM, also referred to as attractive force imaging or noncontact imaging mode, the tip is brought in close proximity (within a few nm) to, and not in contact with the sample. The cantilever is deliberately vibrated either in amplitude modulation (AM) mode [11.65] or frequency modulation (FM) mode [11.65, 94, 108, 109]. Very weak van der Waals attractive forces are present at the tip–sample interface. Although in this technique, the normal pressure exerted at the interface is zero (desirable to avoid any surface deformation), it is slow, and is difficult to use, and is rarely used outside research environments. In the two modes, surface topography is measured by laterally scanning the sample under the tip while simultaneously measuring the separation-dependent force or force gradient (derivative) between the tip and the surface (Fig. 11.7). In the contact (static) mode, the interaction force between tip and sample is measured by measuring the cantilever deflection. In the noncontact (or dynamic) mode, the force gradient is obtained by vibrating the cantilever and measuring the shift of resonant frequency of the cantilever. To obtain topographic information, the interaction force is either recorded directly, or used as a control parameter for a feedback circuit that maintains the force or force derivative at a constant value. With an AFM operated in the contact mode, topographic images with a vertical resolution of less than 0.1 nm (as low as 0.01 nm) and a lateral resolution of about 0.2 nm have been obtained [11.3, 50, 110–114]. With a 0.01 nm displacement sensitivity, 10 nN to 1 pN forces are measurable. These forces are comparable to the forces associated with chemical bonding, e.g., 0.1 µN for an ionic bond and 10 pN for a hydrogen bond [11.2]. For further reading, see [11.94–96, 100, 102, 115–119].



Fig. 11.7 Principle of operation of the AFM. Sample mounted on a piezoelectric tube scanner is scanned against a short tip and the cantilever deflection is measured, mostly, using a laser deflection technique. Force (contact mode) or force gradient (noncontact mode) is measured during scanning

Lateral forces being applied at the tip during scanning in the contact mode, affect roughness measurements [11.120]. To minimize the effects of friction and other lateral forces in the topography measurements in the contact-mode, and to measure the topography of soft surfaces, AFMs can be operated in the so called tapping mode or force modulation mode [11.32, 121].

The STM is ideal for atomic-scale imaging. To obtain atomic resolution with the AFM, the spring constant of the cantilever should be weaker than the equivalent spring between atoms. For example, the vibration frequencies ω of atoms bound in a molecule or in a crystalline solid are typically 10^{13} Hz or higher. Combining this with the mass of the atoms m, on the order of 10^{-25} kg, gives an interatomic spring constants k, given by $\omega^2 m$, on the order of 10 N/m [11.115]. (For comparison, the spring constant of a piece of household aluminum foil that is 4 mm long and 1 mm wide is about 1 N/m.) Therefore, a cantilever beam with a spring constant of about 1 N/m or lower is desirable. Tips have to be as sharp as possible. Tips with a radius ranging from 5 to 50 nm are commonly available.

Atomic resolution cannot be achieved with these tips at the normal load in the nN range. Atomic structures at these loads have been obtained from lattice imaging or by imaging of the crystal periodicity. Reported data show either perfectly ordered periodic atomic structures or defects on a larger lateral scale, but no well-defined, laterally resolved atomic-scale defects like those seen in images routinely obtained with a STM. Interatomic forces with one or several atoms in contact are 20–40 or 50–100 pN, respectively. Thus, atomic resolution with an AFM is only possible with a sharp tip on a flexible cantilever at a net repulsive force of 100 pN or lower [11.122]. Upon increasing the force from 10 pN, *Ohnesorge* and *Binnig* [11.122] observed that monoatomic steplines were slowly wiped away and a perfectly ordered structure was left. This observation explains why mostly defect-free atomic resolution has been observed with AFM. Note that for atomic-resolution measurements, the cantilever should not be too soft to avoid jumps. Further note that measurements in the noncontact imaging mode may be desirable for imaging with atomic resolution.

The key component in an AFM is the sensor for measuring the force on the tip due to its interaction with the sample. A cantilever (with a sharp tip) with extremely low spring constant is required for high vertical and lateral resolutions at small forces (0.1 nN or lower) but at the same time a high resonant frequency is desirable (about 10 to 100 kHz) in order to minimize the sensitivity to vibration noise from the building which is near 100 Hz. This requires a spring with extremely low vertical spring constant (typically 0.05 to 1 N/m) as well as low mass (on the order of 1 ng). Today, the most advanced AFM cantilevers are microfabricated from silicon or silicon nitride using photolithographic techniques. (For further details on cantilevers, see a later section). Typical lateral dimensions are on the order of 100 µm, with the thicknesses on the order of 1 µm. The force on the tip due to its interaction with the sample is sensed by detecting the deflection of the compliant lever with a known spring constant. This cantilever deflection (displacement smaller than 0.1 nm) has been measured by detecting a tunneling current similar to that used in the STM in the pioneering work of *Binnig* et al. [11.2] and later used by *Giessibl* et al. [11.56], by capacitance detection [11.123, 124], piezoresistive detection [11.125, 126], and by four optical techniques namely (1) by optical interferometry [11.5, 6, 127, 128] with the use of optical fibers [11.57, 129] (2) by optical polarization detection [11.72, 130], (3) by laser diode feedback [11.131] and (4) by optical (laser) beam deflection [11.7, 8, 53, 111, 112]. Schematics of the four more commonly used detection systems are shown in Fig. 11.8. The tunneling method originally used by *Binnig* et al. [11.2] in the first version of the AFM, uses a second tip to monitor the deflection of the cantilever with its force sensing tip. Tunneling is rather sensitive to contaminants and the interaction between the tunneling tip and the rear side of the cantilever can become comparable to the interaction between the tip and sample. Tunneling is rarely used and is mentioned first for historical purposes. *Giessibl* et al. [11.56] have used it for a low temperature AFM/STM design. In contrast to tunneling, other deflection sensors are far



Fig. 11.8 Schematics of the four more commonly used detection systems for measurement of cantilever deflection. In each set up, the sample mounted on piezoelectric body is shown on the right, the cantilever in the middle, and the corresponding deflection sensor on the left [11.118]

away from the cantilever at distances of microns to tens of mm. The optical techniques are believed to be more sensitive, reliable and easily implemented detection methods than others [11.94, 118]. The optical beam deflection method has the largest working distance, is insensitive to distance changes and is capable of measuring angular changes (friction forces), therefore, it is most commonly used in the commercial SPMs.

Almost all SPMs use piezo translators to scan the sample, or alternatively, to scan the tip. An electric field applied across a piezoelectric material causes a change in the crystal structure, with expansion in some directions and contraction in others. A net change in volume also occurs [11.132]. The first STM used a piezo tripod for scanning [11.1]. The piezo tripod is one way to generate three-dimensional movement of a tip attached to its center. However, the tripod needs to be fairly large ($\sim 50\,\mathrm{mm}$) to get a suitable range. Its size and asymmetric shape makes it susceptible to thermal drift. The tube scanners are widely used in AFMs [11.133]. These provide ample scanning range with a small size. Control electronics systems for AFMs can use either analog or digital feedback. Digital feedback circuits are better suited for ultra low noise operation.

Images from the AFMs need to be processed. An ideal AFM is a noise free device that images a sample with perfect tips of known shape and has a perfectly linear scanning piezo. In reality, scanning devices are affected by distortions and these distortions must be corrected for. The distortions can be linear and nonlinear. Linear distortions mainly result from imperfections in the machining of the piezo translators causing cross talk between the Z-piezo to the X- and Y-piezos, and vice versa. Nonlinear distortions mainly result because of the presence of a hysteresis loop in piezoelectric ceramics. These may also result if the scan frequency approaches the upper frequency limit of the X- and Y-drive amplifiers or the upper frequency limit of the feedback loop (z-component). In addition, electronic noise may be present in the system. The noise is removed by digital filtering in real space [11.134] or in the spatial frequency domain (Fourier space) [11.135].

Processed data consists of many tens of thousand of points per plane (or data set). The output of the first STM and AFM images were recorded on an X-Y chart recorder, with z-value plotted against the tip position in the fast scan direction. Chart recorders have slow response so computers are used to display the data. The data are displayed as a wire mesh display or gray scale display (with at least 64 shades of gray).

11.2.1 Binnig et al.'s Design

In the first AFM design developed by *Binnig* et al. [11.2], AFM images were obtained by measurement of the force on a sharp tip created by the proximity to the surface of the sample mounted on a 3-D piezoelectric scanner. Tunneling current between STM tip and the backside of the cantilever beam with attached tip was measured to obtain the normal force. This force was kept at a constant level with a feedback mechanism. The STM tip was also mounted on a piezoelectric element to maintain the tunneling current at a constant level.

11.2.2 Commercial AFM

A review of early designs of AFMs is presented by *Bhushan* [11.4]. There are a number of commercial AFMs available on the market. Major manufacturers of AFMs for use in an ambient environment are: Digital Instruments Inc., a subsidiary of Veeco Instruments, Inc., Santa Barbara, California; Topometrix Corp., a subsidiary of Veeco Instruments, Inc., Santa Clara, California; other subsidiaries of Veeco Instruments Inc., Woodbury, New York; Molecular Imaging Corp., Phoenix, Arizona; Quesant Instrument Corp., Agoura Hills, California; Nanoscience Instruments Inc., Phoenix, Arizona; Seiko Instruments, Japan; and Olympus, Japan. AFM/STMs for use in UHV environments are manufactured by Omicron Vakuumphysik GMBH, Taunusstein, Germany.

We describe here two commercial AFMs – small sample and large sample AFMs – for operation in the contact mode, produced by Digital Instruments, Inc., Santa Barbara, CA, with scanning lengths ranging from about 0.7 μm (for atomic resolution) to about 125 μm [11.9, 111, 114, 136]. The original design of these AFMs comes from *Meyer* and *Amer* [11.53]. Basically the AFM scans the sample in a raster pattern while outputting the cantilever deflection error signal to the control station. The cantilever deflection (or the force) is measured using laser deflection technique (Fig. 11.9). The DSP in the workstation controls the z position of the piezo based on the cantilever deflection error signal. The AFM operates in both the "constant height" and "constant force" modes. The DSP always adjusts the height of the sample under the tip based on the cantilever deflection error signal, but if the feedback gains are low the piezo remains at a nearly "constant height" and the cantilever deflection data is collected. With the high gains the piezo height changes to keep the cantilever deflection nearly constant (therefore the force is


a)
Mirrored prism
Diode laser & lens
AFM signal (A+B) – (C+D)
Mirror
A
B
C
D
FFM signal (A+C) – (B+D)
Split-diode photo-detector
Cantilever & substrate
Sample
z
y
x
xyz PZT tube scanner
b)
Split-diode photo-detector
Laser diode, collimator & lens
Adjust-able mirror
Laser path
Fixed Mirror
Lens
Mirror
Lens
Camera objective lens
y
x
z
xyz PZT tube scanner
Cantilever holder
Sample
Motorized stage
x
y

Fig. 11.9a,b Principles of operation of **(a)** a commercial small sample AFM/FFM, and **(b)** a large sample AFM/FFM

constant) and the change in piezo height is collected by the system.

To further describe the principle of operation of the commercial small sample AFM shown in Fig. 11.9a, the sample, generally no larger than 10 mm × 10 mm, is mounted on a PZT tube scanner which consists of separate electrodes to scan precisely the sample in the x-y plane in a raster pattern and to move the sample in the vertical (z) direction. A sharp tip at the free end of a flexible cantilever is brought in contact with the sample. Features on the sample surface cause the cantilever to deflect in the vertical and lateral directions as the sample moves under the tip. A laser beam from a diode laser (5 mW max peak output at 670 nm) is directed by a prism onto the back of a cantilever near its free end, tilted downward at about 10° with respect to the horizontal plane. The reflected beam from the vertex of the cantilever is directed through a mirror onto a quad photodetector (split photodetector with four quadrants) (commonly called position-sensitive detector or PSD, produced by Silicon Detector Corp., Camarillo, California). The differential signal from the top and bottom photodiodes provides the AFM signal which is a sensitive measure of the cantilever vertical deflection. Topographic features of the sample cause the tip to deflect in the vertical direction as the sample is scanned under the tip. This tip deflection will change the direction of the reflected laser beam, changing the intensity difference between the top and bottom sets of photodetectors (AFM signal). In the AFM operating mode called the height mode, for topographic imaging or for any other operation in which the applied normal force is to be kept a constant, a feedback circuit is used to modulate the voltage applied to the PZT scanner to adjust the height of the PZT, so that the cantilever vertical deflection (given by the intensity difference between the top and bottom detector) will remain constant during scanning. The PZT height variation is thus a direct measure of the surface roughness of the sample.

In a large sample AFM, both force sensors using optical deflection methods and scanning unit are mounted on the microscope head (Fig. 11.9b). Because of vibrations added by cantilever movement, lateral resolution of this design is somewhat poorer than the design in Fig. 11.9a in which the sample is scanned instead of the cantilever beam. The advantage of the large sample AFM is that large samples can be measured readily.

Most AFMs can be used for topography measurements in the so-called tapping mode (intermittent contact mode), also referred to as dynamic force microscopy. In the tapping mode, during scanning over the surface, the cantilever/tip assembly is sinusoidally vibrated by a piezo mounted above it, and the oscillating tip slightly taps the surface at the resonant frequency of the cantilever (70–400 Hz) with a constant (20–100 nm) oscillating amplitude introduced in the vertical direction with a feedback loop keeping the average normal force constant (Fig. 11.10). The oscillating amplitude is kept



Fig. 11.10 Schematic of tapping mode used for surface roughness measurements

large enough so that the tip does not get stuck to the sample because of adhesive attractions. The tapping mode is used in topography measurements to minimize effects of friction and other lateral forces to measure the topography of soft surfaces.

Topographic measurements are made at any scanning angle. At a first instance, scanning angle may not appear to be an important parameter. However, the friction force between the tip and the sample will affect the topographic measurements in a parallel scan (scanning along the long axis of the cantilever). Therefore a perpendicular scan may be more desirable. Generally, one picks a scanning angle which gives the same topographic data in both directions; this angle may be slightly different than that for the perpendicular scan.

For measurement of the friction force being applied at the tip surface during sliding, the left hand and right hand sets of quadrants of the photodetector are used. In the so-called friction mode, the sample is scanned back and forth in a direction orthogonal to the long axis of the cantilever beam. A friction force between the sample and the tip will produce a twisting of the cantilever. As a result, the laser beam will be reflected out of the plane defined by the incident beam and the beam reflected vertically from an untwisted cantilever. This produces an intensity difference of the laser beam received in the left hand and right hand sets of quadrants of the photodetector. The intensity difference between the two sets of detectors (FFM signal) is directly related to the degree of twisting and hence to the magnitude of the friction force. This method provides three-dimensional maps of the friction force. One problem associated with this method is that any misalignment between the laser beam and the photodetector axis would introduce error in the measurement. However, by following the procedures developed by *Ruan* and *Bhushan* [11.136], in which the average FFM signal for the sample scanned in two opposite directions is subtracted from the friction profiles of each of the two scans, the misalignment effect is eliminated. By following the friction force calibration procedures developed by *Ruan* and *Bhushan* [11.136], voltages corresponding to friction forces can be converted to force units. The coefficient of friction is obtained from the slope of friction force data measured as a function of normal loads typically ranging from 10 to 150 nN. This approach eliminates any contributions due to the adhesive forces [11.10]. For calculation of the coefficient of friction based on a single point measurement, friction force should be divided by the sum of applied normal load and intrinsic adhesive force. Furthermore, it should be pointed out that for a single asperity contact, the coefficient of friction is not independent of load. For further details, refer to a later section.

The tip is scanned in such a way that its trajectory on the sample forms a triangular pattern (Fig. 11.11). Scanning speeds in the fast and slow scan directions depend on the scan area and scan frequency. Scan sizes ranging from less than 1 nm × 1 nm to 125 µm × 125 µm and scan rates from less than 0.5 to 122 Hz typically can be used. Higher scan rates are used for smaller scan lengths. For example, scan rates in the fast and slow scan directions for an area of 10 µm × 10 µm scanned at 0.5 Hz are 10 µm/s and 20 nm/s, respectively.

We now describe the construction of a small sample AFM in more detail. It consists of three main parts: the optical head which senses the cantilever deflection, a PZT tube scanner which controls the scanning motion of the sample mounted on its one end, and the base



Fig. 11.11 Schematic of triangular pattern trajectory of the AFM tip as the sample is scanned in two dimensions. During imaging, data are recorded only during scans along the solid scan lines


a)
AFM photodiode positioner
Laser diode y positioner
Laser diode x positioner
Optical head
FFM photodiode positioner
Preamp housing
Cantilever mount
x–y Positioning stage
Scanner
Scanner support ring
Coarse adjust screws
Motor drive shaft
Motor control switch
Motor housing
Base
Laser
Power
AFM voltmeter
AFM DVM control switch
FFM DVM control switch
FFM voltmeter
b)
Laser diode y positioner
Viewing window
Laser diode x positioner
AFM photo-diode positioner
FFM photodiode positioner
Preamp housing
Beam path
Holding arm
Photo-diode housing
Cantilever mount
Cantilever
x–y Positioning stage
Interlock sensor
c)
Electrical connectors
Head stabilizing springs
Scanner support ring
Drive shaft
Stepper motor control switch
Laser power indicator
AFM DVM display
AFM DVM Control switch
FFM DVM display
FFM DVM Control switch
d)
Cantilever mount
Cantilever clip
Ledges
Substrate
Cantilever
Sample

Fig. 11.12a–d Schematics of a commercial AFM/FFM made by Digital Instruments Inc. **(a)** front view, **(b)** optical head, **(c)** base, and **(d)** cantilever substrate mounted on cantilever mount (not to scale)

which supports the scanner and head and includes circuits for the deflection signal (Fig. 11.12a). The AFM connects directly to a control system. The optical head consists of laser diode stage, photodiode stage preamp board, cantilever mount and its holding arm, and deflection beam reflecting mirror (Fig. 11.12b). The laser diode stage is a tilt stage used to adjust the position of the laser beam relative to the cantilever. It consists of the laser diode, collimator, focusing lens, baseplate, and the *X* and *Y* laser diode positioners. The positioners are used to place the laser spot on the end of the cantilever. The photodiode stage is an adjustable stage used to position the photodiode elements relative to the reflected laser beam. It consists of the split photodiode, the base plate, and the photodiode positioners. The deflection beam reflecting mirror is mounted on the upper left in the interior of the head which reflects the deflected beam toward the photodiode. The cantilever mount is a metal (for operation in air) or glass (for operation in water) block which holds the cantilever firmly at the proper angle (Fig. 11.12d). Next, the tube scanner consists of an Invar cylinder holding a single tube made of piezoelectric crystal which provides the necessary three-dimensional motion to the sample. Mounted on top of the tube is a magnetic cap on which the steel sample puck is placed. The tube is rigidly held at one end with the sample mounted on the other end of the tube. The scanner also contains three fine-pitched screws which form the mount for the optical head. The optical head rests on the tips of the screws which are used to adjust the position of the head relative to the sample. The scanner fits into the scanner support ring mounted on the base of the microscope (Fig. 11.12c). The stepper motor is controlled manually with the switch on the upper surface of the base and automatically by the computer during the tip engage and tip-withdraw processes.

The scan sizes available for these instruments are $0.7\,\mu m$, $12\,\mu m$ and $125\,\mu m$. The scan rate must be decreased as the scan size is increased. A maximum scan rate of 122 Hz can be used. Scan rates of about 60 Hz should be used for small scan lengths ($0.7\,\mu m$). Scan rates of 0.5 to 2.5 Hz should be used for large scans on samples with tall features. High scan rates help reduce drift, but they can only be used on flat samples with small scan sizes. Scan rate, or scanning speed in length/time in the fast scan direction, is equal to twice the scan length times the scan rate in Hz, and in the slow direction, it is equal to scan length times the scan rate in Hz divided by number of data points in the transverse direction. For example, for $10\,\mu m \times 10\,\mu m$ scan size scanned at 0.5 Hz, the scan rates in the fast and slow scan directions are $10\,\mu m/s$ and 20 nm/s, respectively. Normally 256 × 256 data points are taken for each image. The lateral resolution at larger scans is approximately equal to scan length divided by 256. The piezo tube requires x-y calibration which is carried out by imaging an appropriate calibration standard. Cleaved graphite is used for small scan heads while two-dimensional grids (a gold plating ruling) can be used for longer range heads.

Examples of AFM images of freshly-cleaved highly-oriented pyrolytic (HOP) graphite and mica surfaces are shown in Fig. 11.13 [11.50, 110, 114]. Images with near atomic resolution are obtained.

The force calibration mode is used to study interactions between the cantilever and the sample surface. In the force calibration mode, the X and Y voltages applied to the piezo tube are held at zero and a sawtooth voltage is applied to the Z electrode of the piezo tube, Fig. 11.14a. The force measurement starts with the sample far away and the cantilever in its rest position. As a result of the applied voltage, the sample is moved up and down relative to the stationary cantilever tip. As the



Fig. 11.13a,b Typical AFM images of freshly-cleaved **(a)** highly-oriented pyrolytic graphite and **(b)** mica surfaces taken using a square pyramidal Si_3N_4 tip



Fig. 11.14 **(a)** Force calibration Z waveform, and **(b)** a typical force-distance curve for a tip in contact with a sample. Contact occurs at point B; tip breaks free of adhesive forces at point C as the samples moves away from the tip

piezo moves the sample up and down, the cantilever deflection signal from the photodiode is monitored. The force–distance curve, a plot of the cantilever tip deflection signal as a function of the voltage applied to the piezo tube, is obtained. Figure 11.14b shows a typical force–distance curve showing the various features of the curve. The arrow heads reveal the direction of piezo travel. As the piezo extends, it approaches the tip, which is at this point in free air and hence shows no deflection. This is indicated by the flat portion of the curve. As the tip approaches the sample within a few nanometers (point A), an attractive force exists between the atoms of the tip surface and the atoms of the sample surface. The tip is pulled towards the sample and contact occurs at point B on the graph. From this point on, the tip is in contact with the surface and as the piezo further extends, the tip gets further deflected. This is represented by the sloped portion of the curve. As the piezo retracts, the tip goes beyond the zero deflection (flat) line because of attractive forces (van der Waals forces and long range meniscus forces), into the adhesive regime. At point C in the graph, the tip snaps free of the adhesive forces, and is again in free air. The horizontal distance between point B and C along the retrace line gives the distance moved by the tip in the adhesive regime. This distance multiplied by the stiffness of the cantilever gives the adhesive force. Incidentally, the horizontal shift between the loading and unloading curves results from the hysteresis in the PZT tube [11.4].

Multimode Capabilities

The multimode AFM can be used for topography measurements in the contact mode and tapping mode, described earlier, and for measurements of lateral (friction) force, electric force gradients and magnetic force gradients.

The multimode AFM, used with a grounded conducting tip, can measure electric field gradients by oscillating the tip near its resonant frequency. When the lever encounters a force gradient from the electric field, the effective spring constant of the cantilever is altered, changing its resonant frequency. Depending on which side of the resonance curve is chosen, the oscillation amplitude of the cantilever increases or decreases due to the shift in the resonant frequency. By recording the amplitude of the cantilever, an image revealing the strength of the electric field gradient is obtained.

In the magnetic force microscope (MFM) used with a magnetically-coated tip, static cantilever deflection is detected which occurs when a magnetic field exerts a force on the tip and the MFM images of magnetic materials can be produced. MFM sensitivity can be enhanced by oscillating the cantilever near its resonant frequency. When the tip encounters a magnetic force gradient, the effective spring constant, and hence the resonant frequency, is shifted. By driving the cantilever above or below the resonant frequency, the oscillation amplitude varies as the resonance shifts. An image of magnetic field gradients is obtained by recording the oscillation amplitude as the tip is scanned over the sample.

Topographic information is separated from the electric field gradients and magnetic field images by using a so-called lift mode. Measurements in lift mode are taken in two passes over each scan line. On the first pass, topographical information is recorded in the standard tapping mode where the oscillating cantilever lightly taps the surface. On the second pass, the tip is lifted to a user-selected separation (typically 20–200 nm) between the tip and local surface topography. By using the stored topographical data instead of the standard feedback, the separation remains constant without sensing the surface. At this height, cantilever amplitudes are sensitive to electric field force gradients or relatively weak but long-range magnetic forces without being influenced by topographic features. Two-pass measurements are taken for every scan line, producing separate topographic and magnetic force images.

Electrochemical AFM

This option allows one to perform electrochemical reactions on the AFM. It includes a potentiostat, a fluid cell with a transparent cantilever holder and electrodes, and the software required to operate the potentiostat and display the results of the electrochemical reaction.

11.2.3 AFM Probe Construction

Various probes (cantilevers and tips) are used for AFM studies. The cantilever stylus used in the AFM should meet the following criteria: (1) low normal spring constant (stiffness), (2) a high resonant frequency, (3) a high quality factor of the cantilever Q, (4) high lateral spring constant (stiffness), (5) short cantilever length, (6) incorporation of components (such as mirror) for deflection sensing, and (7) a sharp protruding tip [11.137]. In order to register a measurable deflection with small forces, the cantilever must flex with a relativly low force (on the order of few nN) requiring vertical spring constants of 10^{-2} to 10^{2} N/m for atomic resolution in the contact profiling mode. The data rate or imaging rate in the AFM is limited by the mechanical resonant frequency

Table 11.2 Relevant properties of materials used for cantilevers

Property	Young's Modulus (E) (GPa)	Density (ρg) (kg/m^3)	Microhardness (GPa)	Speed of sound ($\sqrt{E/\rho}$) (m/s)
Diamond	900–1,050	3,515	78.4–102	17,000
Si_3N_4	310	3,180	19.6	9,900
Si	130–188	2,330	9–10	8,200
W	350	19,310	3.2	4,250
Ir	530	–	~ 3	5,300

of the cantilever. To achieve a large imaging bandwidth, the AFM cantilever should have a resonant frequency greater than about 10 kHz (30–100 kHz is preferable) in order to make the cantilever the least sensitive part of the system. Fast imaging rates are not just a matter of convenience, since the effects of thermal drifts are more pronounced with slow-scanning speeds. The combined requirements of a low spring constant and a high resonant frequency is met by reducing the mass of the cantilever. The quality factor Q $(= \omega_R/(c/m)$, where ω_R is the resonant frequency of the damped oscillator and c is the damping constant and m is the mass of the oscillator) should have a high value for some applications. For example, resonance curve detection is a sensitive modulation technique for measuring small force gradients in noncontact imaging. Increasing the Q increases the sensitivity of the measurements. Mechanical Q values of 100–1,000 are typical. In contact modes, the Q is of less importance. High lateral spring constant in the cantilever is desirable to reduce the effect of lateral forces in the AFM as frictional forces can cause appreciable lateral bending of the cantilever. Lateral bending results in error in the topography measurements. For friction measurements, cantilevers with less lateral rigidity is preferred. A sharp protruding tip must be formed at the end of the cantilever to provide a well defined interaction with sample over a small area. The tip radius should be much smaller than the radii of corrugations in the sample in order for these to be measured accurately. The lateral spring constant depends critically on the tip length. Additionally, the tip should be centered at the free end.

In the past, cantilevers have been cut by hand from thin metal foils or formed from fine wires. Tips for these cantilevers were prepared by attaching diamond fragments to the ends of the cantilevers by hand, or in the case of wire cantilevers, electrochemically etching the wire to a sharp point. Several cantilever geometries for wire cantilevers have been used. The simplest geometry is the L-shaped cantilever, usually made by bending a wire at a 90° angle. Other geometries include single-V and double-V geometries with a sharp tip attached at the apex of V, and double-X configuration with a sharp tip attached at the intersection [11.31, 138]. These cantilevers can be constructed with high vertical spring constants. For example, double-cross cantilever with an effective spring constant of 250 N/m was used by *Burnham* and *Colton* [11.31]. The small size and low mass needed in the AFM make hand fabrication of the cantilever a difficult process with poor reproducibility. Conventional microfabrication techniques are ideal for constructing planar thin-film structures which have submicron lateral dimensions. The triangular (V-shaped) cantilevers have improved (higher) lateral spring constant in comparison to rectangular cantilevers. In terms of spring constants, the triangular cantilevers are approximately equivalent to two rectangular cantilevers in parallel [11.137]. Although the macroscopic radius of a photolithographically patterned corner is seldom much less than about 50 nm, microscopic asperities on the etched surface provide tips with near atomic dimensions.

Cantilevers have been used from a whole range of materials. Most commonly are cantilevers made of Si_3N_4, Si, and diamond. Young's modulus and the density are the material parameters which determine the resonant frequency, besides the geometry. Table 11.2 shows the relevant properties and the speed of sound, indicative of the resonant frequency for a given shape. Hardness is important to judge the durability of the cantilevers, and is also listed in the table. Materials used for STM cantilevers are also included.

Silicon nitride cantilevers are less expensive than those made of other materials. They are very rugged and well suited to imaging in almost all environments. They are especially compatible to organic and biological materials. Microfabricated silicon nitride triangular beams with integrated square pyramidal tips made of plasma-enhanced chemical vapor deposition (PECVD) are most commonly used [11.137]. Four cantilevers with different


a)
Top view
Side view
21 µm
36 µm
0.6 µm
15 nm Au on this surface
0.55 mm
1.05 mm
0.55 mm
3.6 mm
Pyrex
1.6 mm
Square pyramidal tip (111) face
35°
205 µm
122µm
115 µm
193 µm
20 µm
15 µm
Si$_3$N$_4$
4 µm


b)
10–15 µm
35°
450 µm
40 µm
Contact AFM Cantilevers
Length = 450 µm
Width = 40 µm
Thickness = 1–3 µm
Resonance frequency = 6–20 kHz
Spring constant = 0.22–0.66 N/m
125 µm
30 µm
Tapping mode AFM Cantilevers
Length = 125 µm
Width = 30 µm
Thickness = 3–5 µm
Resonance frequency = 250–400 kHz
Spring constant = 17–64 N/m
Material: Etched single-crystal n-type silicon;
resistivity = 0.01–0.02 Ω/cm
Tip shape: 10 nm radius of curvature, 35° interior angle


c)
Diamond tip bonded with epoxy
0.2–0.4 mm
0.2 mm
20 µm
0.15 mm
20 mm
Gold-plated 304 stainless steel cantilever

Fig. 11.15a–c Schematics of **(a)** triangular cantilever beam with square pyramidal tips made of PECVD Si$_3$N$_4$, **(b)** rectangular cantilever beams with square pyramidal tips made of etched single-crystal silicon, and **(c)** rectangular cantilever stainless steel beam with three-sided pyramidal natural diamond tip


a)
2 µm
b)
5 µm
c)
10 µm

Fig. 11.16a–c SEM micrographs of a square-pyramidal PECVD Si$_3$N$_4$ tip **(a)**, a square pyramidal etched single-crystal silicon tip **(b)**, and a three-sided pyramidal natural diamond tip **(c)**

sizes and spring constants on each cantilever substrate made of boron silicate glass (Pyrex), marketed by Digital Instruments, are shown in Figs. 11.15a and 11.16. Two pairs of the cantilevers on each substrate measure about 115 and 193 µm from the substrate to the apex of the triangular cantilever with base widths of 122 and 205 µm, respectively. Both cantilever legs, with the same thickness (0.6 µm) of all the cantilevers, are available with wide and narrow legs. Only one cantilever is selected and used from each substrate. Calculated spring constant and measured natural frequencies for each of the configurations are listed in Table 11.3. The most commonly used cantilever beam is the 115-µm long, wide-legged cantilever (vertical spring constant = 0.58 N/m). Cantilevers with smaller spring constants should be used on softer samples. The pyramidal tips are highly symmetric with its end having a radius of about 20–50 nm. The

Table 11.3 Measured vertical spring constants and natural frequencies of triangular (V-shaped) cantilevers made of PECVD Si_3N_4 (Data provided by Digital Instruments, Inc.)

Cantilever dimension	Spring constant (k_z) (N/m)	Natural frequency (ω_0) (kHz)
115-μm long, narrow leg	0.38	40
115-μm long, wide leg	0.58	40
193-μm long, narrow leg	0.06	13–22
193-μm long, wide leg	0.12	13–22

Table 11.4 Vertical (k_z), lateral (k_y), and torsional (k_{yT}) spring constants of rectangular cantilevers made of Si (IBM) and PECVD Si_3N_4 (Veeco Instruments, Inc.)

Dimensions/stiffness	Si cantilever	Si_3N_4 cantilever
Length (L) (μm)	100	100
Width (b) (μm)	10	20
Thickness (h) (μm)	1	0.6
Tip length (ℓ) (μm)	5	3
k_z (N/m)	0.4	0.15
k_y (N/m)	40	175
k_{yT} (N/m)	120	116
ω_0 (kHz)	~ 90	~ 65

Note: $k_z = Ebh^3/4L^3$, $k_y = Eb^3h/4\ell^3$, $k_{yT} = Gbh^3/3L\ell^2$, and $\omega_0 = [k_z/(m_c + 0.24bhL\rho)]^{1/2}$, where E is Young's modulus, G is the modulus of rigidity [$= E/2(1+\nu)$, ν is Poisson's ratio], ρ is the mass density of the cantilever, and m_c is the concentrated mass of the tip (~ 4 ng) [11.94]. For Si, $E = 130$ GPa, $\rho g = 2{,}300\,kg/m^3$, and $\nu = 0.3$. For Si_3N_4, $E = 150$ GPa, $\rho g = 3{,}100\,kg/m^3$, and $\nu = 0.3$

tip side walls have a slope of 35 deg and the length of the edges of the tip at the cantilever base is about 4 μm.

An alternative to silicon nitride cantilevers with integrated tips are microfabricated single-crystal silicon cantilevers with integrated tips. Si tips are sharper than Si_3N_4 tips because they are directly formed by the anisotropic etch in single-crystal Si rather than using an etch pit as a mask for deposited materials [11.139]. Etched single-crystal *n*-type silicon rectangular cantilevers with square pyramidal tips with a lower radius of less than 10 nm for contact and tapping mode (tapping-mode etched silicon probe or TESP) AFMs are commercially available from Digital Instruments and Nanosensors GmbH, Aidlingen, Germany, Figs. 11.15b and 11.16. Spring constants and resonant frequencies are also presented in the Fig. 11.15b.

Commercial triangular Si_3N_4 cantilevers have a typical width-thickness ratio of 10 to 30 which results in 100 to 1000 times stiffer spring constants in the lateral direction compared to the normal direction. Therefore these cantilevers are not well suited for torsion. For friction measurements, the torsional spring constant should be minimized in order to be sensitive to the lateral forces. Rather long cantilevers with small thickness and large tip length are most suitable. Rectangular beams have lower torsional spring constants in comparison to the triangular (V-shaped) cantilevers. Table 11.4 lists the spring constants (with full length of the beam used) in three directions of the typical rectangular beams. We note that lateral and torsional spring constants are about two orders of magnitude larger than the normal spring constants. A cantilever beam required for the tapping mode is quite stiff and may not be sensitive enough for friction measurements. *Meyer* et al. [11.140] used a specially designed rectangular silicon cantilever with length = 200 μm, width = 21 μm, thickness = 0.4 μm, tip length = 12.5 μm, and shear modulus = 50 GPa, giving a normal spring constant of 0.007 N/m and torsional spring constant of 0.72 N/m which gives a lateral force sensitivity of 10 pN and an angle of resolution of 10^{-7} rad. With this particular geometry, sensitivity to lateral forces could be improved by about a factor of 100 compared with commercial V-shaped Si_3N_4 or rectangular Si or Si_3N_4 cantilevers used by *Meyer* and *Amer* [11.8] with torsional spring constant of ~ 100 N/m. *Ruan* and *Bhushan* [11.136] and *Bhushan* and *Ruan* [11.9] used 115-μm long, wide-legged V-shaped cantilevers made of Si_3N_4 for friction measurements.

For scratching, wear, and indentation studies, single-crystal natural diamond tips ground to the shape of a three-sided pyramid with an apex angle of either 60° or 80° whose point is sharpened to a radius of about 100 nm are commonly used [11.4, 10] (Figs. 11.15c and 11.16). The tips are bonded with conductive epoxy to a gold-plated 304 stainless steel spring sheet (length = 20 mm, width = 0.2 mm, thickness = 20 to 60 μm) which acts as a cantilever. The free length of the spring is varied to change the beam stiffness. The normal spring con-



Fig. 11.17a,b Schematics of **(a)** HART Si_3N_4 probe, and **(b)** FIB milled Si_3N_4 probe

stant of the beam ranges from about 5 to 600 N/m for a 20 μm thick beam. The tips are produced by R-DEC Co., Tsukuba, Japan.

For imaging within trenches by an AFM, high aspect ratio tips are used. Examples of the two probes are shown in Fig. 11.17. The high-aspect ratio tip (Hart) probes are produced by starting with a conventional Si_3N_4 pyramidal probe. Through a combination of focused ion beam (FIB) and high resolution scanning electron microscopy (SEM) techniques, a thin filament is grown at the apex of the pyramid. The probe filament is approximately 1 μm long and 0.1 μm in diameter. It tapers to an extremely sharp point (radius better than the resolution of most SEMs). The long thin shape and sharp radius make it ideal for imaging within "vias" of microstructures and trenches (> 0.25 μm). Because of flexing of the probe, it is unsuitable for imaging structures at the atomic level since the flexing of the probe can create image artifacts. For atomic-scale imaging, a FIB-milled probe is used which is relatively stiff yet allows for closely spaced topography. These probes start out as conventional Si_3N_4 pyramidal probes but the pyramid is FIB milled until a small cone shape is formed which has a high aspect ratio with 0.2–0.3 μm in length. The milled probes allow nanostructure resolution without sacrificing rigidity. These types of probes are manufactured by various manufacturers including Materials Analytical Services, Raleigh, North Carolina.



Fig. 11.18 SEM micrograph of a multi-walled carbon nanotube (MWNT) tip physically attached on the single-crystal silicon, square-pyramidal tip (Courtesy Piezomax Technologies, Inc.)

Carbon nanotube tips having small diameter and high aspect ratio are used for high resolution imaging of surfaces and of deep trenches, in the tapping mode or noncontact mode. Single-walled carbon nanotubes (SWNT) are microscopic graphitic cylinders that are 0.7 to 3 nm in diameter and up to many microns in length. Larger structures called multi-walled carbon nanotubes (MWNT) consist of nested, concentrically arranged SWNT and have diameters ranging from 3 to 50 nm. MWNT carbon nanotube AFM tips are produced by manual assembly [11.141], chemical vapor deposition (CVD) synthesis, and hybrid fabrication process [11.142]. Figure 11.18 shows TEM micrograph of a carbon nanotube tip, ProbeMax^{TM}, commercially produced by mechanical assembly by Piezomax Technologies, Inc., Middleton, Wisconsin. For production of these tips, MWNT nanotubes are produced by carbon arc. They are physically attached on the single-crystal silicon, square-pyramidal tips in the SEM using a manipulator and the SEM stage to control the nanotubes and the tip independently. Once the nanotube is attached to the tip, it is usually too long to image with. It is shortened by using an AFM and applying voltage between the tip and the sample. Nanotube tips are also commercially produced by CVD synthesis by NanoDevices, Santa Barbara, California.

11.2.4 Friction Measurement Methods

Based on the work by *Ruan* and *Bhushan* [11.136], the two methods for friction measurements are now described in more detail. (Also see [11.8].) A scanning angle is defined as the angle relative to the *y*-axis in Fig. 11.19a. This is also the long axis of the cantilever.

A zero degree scanning angle corresponds to the sample scanning in the y direction, and a 90 degree scanning angle corresponds to the sample scanning perpendicular to this axis in the xy plane (along x axis). If the scanning direction is in both the y and $-y$ directions, we call this "parallel scan". Similarly, a "perpendicular scan" means the scanning direction is in the x and $-x$ directions. The sample traveling direction for each of these two methods is illustrated in Fig. 11.19b.


a)
Laser beam spot
y
x
Cantilever substrate
Flexible cantilever
Sample traveling direction in method 1
Sample traveling direction in method 2
b)
Method 1
Photodetector
Cantilever normal direction
Incident beam
T
L
R
B
Cantilever substrate
Reflected beam
Tip
Cantilever
Traveling direction of the sample (y)
Method 2
T
L
R
B
Tip
Twisted Cantilever
Traveling direction of the sample (x)

Fig. 11.19 **(a)** Schematic defining the x- and y-directions relative to the cantilever, and showing the sample traveling direction in two different measurement methods discussed in the text, **(b)** schematic of deformation of the tip and cantilever shown as a result of sliding in the x- and y-directions. A twist is introduced to the cantilever if the scanning is in the x-direction (**(b)**, *lower part*) [11.136]

In method 1 (using "height" mode with parallel scans) in addition to topographic imaging, it is also possible to measure friction force when the scanning direction of the sample is parallel to the y direction (parallel scan). If there were no friction force between the tip and the moving sample, the topographic feature would be the only factor which cause the cantilever to be deflected vertically. However, friction force does exist on all contact surfaces where one object is moving relative to another. The friction force between the sample and the tip will also cause a cantilever deflection. We assume that the normal force between the sample and the tip is W_0 when the sample is stationary (W_0 is typically in the range of 10 nN to 200 nN), and the friction force between the sample and the tip is W_f as the sample scans against the tip. The direction of friction force (W_f) is reversed as the scanning direction of the sample is reversed from positive (y) to negative ($-y$) directions ($\overrightarrow{W}_{f(y)} = -\overrightarrow{W}_{f(-y)}$).

When the vertical cantilever deflection is set at a constant level, it is the total force (normal force and friction force) applied to the cantilever that keeps the cantilever deflection at this level. Since the friction force is in opposite directions as the traveling direction of the sample is reversed, the normal force will have to be adjusted accordingly when the sample reverses its traveling direction, so that the total deflection of the cantilever will remain the same. We can calculate the difference of the normal force between the two traveling directions for a given friction force W_f. First, by means of a constant deflection, the total moment applied to the cantilever is constant. If we take the reference point to be the point where the cantilever joins the cantilever holder (substrate), point P in Fig. 11.20, we have the following relationship:

$$(W_0 - \Delta W_1)L + W_f \ell = (W_0 + \Delta W_2)L - W_f \ell \qquad (11.1)$$

or

$$(\Delta W_1 + \Delta W_2)L = 2W_f \ell \,. \qquad (11.2)$$

Thus

$$W_f = (\Delta W_1 + \Delta W_2)L/(2\ell)\,, \qquad (11.3)$$

where ΔW_1 and ΔW_2 are the absolute value of the changes of normal force when the sample is traveling in $-y$ and y directions, respectively, as shown in Fig. 11.20; L is the length of the cantilever; ℓ is vertical distance between the end of the tip and point P. The coefficient of



Fig. 11.20 **(a)** Schematic showing an additional bending of the cantilever – due to friction force when the sample is scanned in the y- or $-y$-direction (*left*). **(b)** This effect will be canceled by adjusting the piezo height by a feedback circuit (*right*) [11.136]

friction (μ) between the tip and the sample is then given as

$$\mu = \frac{W_f}{W_0} = \left(\frac{(\Delta W_1 + \Delta W_2)}{W_0}\right)\left(\frac{L}{2\ell}\right) . \tag{11.4}$$

In all circumstances, there are adhesive and interatomic attractive forces between the cantilever tip and the sample. The adhesive force can be due to water from the capillary condensation and other contaminants present at the surface which form meniscus bridges [11.4, 143, 144] and the interatomic attractive force includes van der Waals attraction [11.18]. If these forces (and indentation effect as well, which is usually small for rigid samples) can be neglected, the normal force W_0 is then equal to the initial cantilever deflection H_0 multiplied by the spring constant of the cantilever. $(\Delta W_1 + \Delta W_2)$ can be measured by multiplying the same spring constant by the height difference of the piezo tube between the two traveling directions (y and $-y$ directions) of the sample. This height difference is denoted as $(\Delta H_1 + \Delta H_2)$, shown schematically in Fig. 11.21. Thus, (11.4) can be rewritten as

$$\mu = \frac{W_f}{W_0} = \left(\frac{(\Delta H_1 + \Delta H_2)}{H_0}\right)\left(\frac{L}{2\ell}\right) . \tag{11.5}$$

Since the piezo tube vertical position is affected by the surface topographic profile of the sample in addition to the friction force being applied at the tip, this difference has to be taken point by point at the same location on the sample surface as shown in Fig. 11.21. Subtraction of point by point measurements may introduce errors, particularly for rough samples. We will come back to this point later. In addition, precise measurement of L and ℓ (which should include the cantilever angle) are also required.


PZT height H
$(\Delta W_1 + \Delta W_2) = k(\Delta H_1 + \Delta H_2)$
ΔH_2
H_0
ΔH_1
$(\Delta H_1 + \Delta H_2)$
Sliding distance y

Fig. 11.21 Schematic illustration of the height difference of the piezoelectric tube scanner as the sample is scanned in y and $-y$ directions

If the adhesive forces between the tip and the sample are large enough that it can not be neglected, one should include it in the calculation. However, there could be a large uncertainty in determining this force, thus an uncertainty in using (11.5). An alternative approach is to make the measurements at different normal loads and to use $\Delta(H_0)$ and $\Delta(\Delta H_1 + \Delta H_2)$ from the measurements in (11.5). Another comment on (11.5) is that, since only the ratio between $(\Delta H_1 + \Delta H_2)$ and H_0 comes into this equation, the piezo tube vertical position H_0 and its position difference $(\Delta H_1 + \Delta H_2)$ can be in the units of volts as long as the vertical traveling distance of the piezo tube and the voltage applied to it has a linear relationship. However, if there is a large nonlinearity between the piezo tube traveling distance and the applied voltage, this nonlinearity must be included in the calculation.

It should also be pointed out that (11.4) and (11.5) are derived under the assumption that the friction force W_f is the same for the two scanning directions of the sample. This is an approximation since the normal force is slightly different for the two scans and there may also be a directionality effect in friction. However, this difference is much smaller than W_0 itself. We can ignore the second order correction.

Method 2 ("aux" mode with perpendicular scan) to measure friction was suggested by *Meyer* and *Amer* [11.8]. The sample is scanned perpendicular to the long axis of the cantilever beam (i. e., to scan along the x or $-x$ direction in Fig. 11.19a) and the output of the horizontal two quadrants of the photodiode-detector is measured. In this arrangement, as the sample moves under the tip, the friction force will cause the cantilever to twist. Therefore the light intensity between the left and right (L and R in Fig. 11.19b, right) detectors will be different. The differential signal between the left and right detectors is denoted as FFM signal $[(\mathrm{L}-\mathrm{R})/(\mathrm{L}+\mathrm{R})]$. This signal can be related to the degree of twisting, hence to the magnitude of friction force. Again, because of a possible error in determining normal force due to the presence of an adhesive force at the tip–sample interface, the slope of the friction data (FFM signal vs. normal load) needs to be taken for an accurate value of the coefficient of friction.

While friction force contributes to the FFM signal, friction force may not be the only contributing factor in commercial FFM instruments (for example, NanoScope IV). One can notice this fact by simply engaging the cantilever tip with the sample. Before engaging, the left and right detectors can be balanced by adjusting the position of the detectors so that the intensity difference between these two detectors is zero (FFM signal is zero). Once the tip is engaged with the sample, this signal is no longer zero even if the sample is not moving in the xy plane with no friction force applied. This would be a detrimental effect. It has to be understood and eliminated from the data acquisition before any quantitative measurement of friction force becomes possible.

One of the fundamental reasons for this observation is the following. The detectors may not have been properly aligned with respect to the laser beam. To be precise, the vertical axis of the detector assembly (the line joining T-B in Fig. 11.22) is not in the plane defined by the incident laser beam and the beam reflected from an untwisted cantilever (we call this plane the "beam plane"). When the cantilever vertical deflection changes due to a change of applied normal force (without having the sample scanned in the xy plane), the laser beam will be reflected up and down and form a projected trajectory on the detector. (Note that this trajectory is in the defined beam plane.) If this trajectory is not coincident with the vertical axis of the detector, the laser beam will not evenly bisect the left and right quadrants of the detectors, even under the condition of no torsional motion of the cantilever, see Fig. 11.22. Thus when the laser beam is reflected up and down due a change of the normal force, the intensity difference between the left and right detectors will also change. In other words, the FFM signal will change as the normal force applied to the tip is changed, even if the tip is not experiencing any friction force. This (FFM) signal is unrelated to friction force or to the actual twisting of the cantilever. We will call this part of FFM signal "$\mathrm{FFM_F}$", and the part which is truly related to friction force "$\mathrm{FFM_T}$".


Path of the laser beam on the photodetector
T
"Height" – AFM signal
L
R
"Aux" –FFM signal
B
Vertical axis of the photodetector

Fig. 11.22 The trajectory of the laser beam on the photodetectors in as the cantilever is vertically deflected (with no torsional motion) for a misaligned photodetector with respect to the laser beam. For a change of normal force (vertical deflection of the cantilever), the laser beam is projected at a different position on the detector. Due to a misalignment, the projected trajectory of the laser beam on the detector is not parallel with the detector vertical axis (the line joint T-B) [11.136]

The $\mathrm{FFM_F}$ signal can be eliminated. One way of doing this is as follows. First the sample is scanned in both x and $-x$ directions and the FFM signal for scans in each direction is recorded. Since friction force reverses its directions when the scanning direction is reversed from x to $-x$ direction, the $\mathrm{FFM_T}$ signal will have opposite signs as the scanning direction of the sample is reversed ($\mathrm{FFM_T}(x) = -\mathrm{FFM_T}(-x)$). Hence the $\mathrm{FFM_T}$ signal will be canceled out if we take the sum of the FFM signals for the two scans. The average value of the two scans will be related to $\mathrm{FFM_F}$ due to the misalignment,

$$\mathrm{FFM}(x) + \mathrm{FFM}(-x) = 2\mathrm{FFM_F} . \tag{11.6}$$

This value can therefore be subtracted from the original FFM signals of each of these two scans to obtain the true FFM signal ($\mathrm{FFM_T}$). Or, alternately, by taking the difference of the two FFM signals, one directly gets the $\mathrm{FFM_T}$ value

$$\begin{aligned}\mathrm{FFM}(x)-\mathrm{FFM}(-x)&=\mathrm{FFM}_\mathrm{T}(x)-\mathrm{FFM}_\mathrm{T}(-x)\\&=2\mathrm{FFM}_\mathrm{T}(x)\,.\end{aligned}\tag{11.7}$$

Ruan and *Bhushan* [11.136] have shown that the error signal (FFM_F) can be very large compared to the friction signal FFM_T, thus correction is required.

Now we compare the two methods. The method of using "height" mode and parallel scan (method 1) is very simple to use. Technically, this method can provide 3-D friction profiles and the corresponding topographic profiles. However, there are some problems with this method. Under most circumstances, the piezo scanner displays a hysteresis when the traveling direction of the sample is reversed. Therefore the measured surface topographic profiles will be shifted relative to each other along the y-axis for the two opposite (y and $-y$) scans. This would make it difficult to measure the local height difference of the piezo tube for the two scans. However, the average height difference between the two scans and hence the average friction can still be measured. The measurement of average friction can serve as an internal means of friction force calibration. Method 2 is a more desirable approach. The subtraction of FFM_F signal from FFM for the two scans does not introduce error to local friction force data. An ideal approach in using this method would be to add the average value of the two profiles in order to get the error component (FFM_F) and then subtract this component from either profiles to get true friction profiles in either directions. By making measurements at various loads, we can get the average value of the coefficient of friction which then can be used to convert the friction profile to the coefficient of friction profile. Thus any directionality and local variations in friction can be easily measured. In this method, since topography data are not affected by friction, accurate topography data can be measured simultaneously with friction data and a better localized relationship between the two can be established.

11.2.5 Normal Force and Friction Force Calibrations of Cantilever Beams

Based on *Ruan* and *Bhushan* [11.136], we now discuss normal force and friction force calibrations. In order to calculate the absolute value of normal and friction forces in Newtons using the measured AFM and FFM_T voltage signals, it is necessary to first have an accurate value of the spring constant of the cantilever (k_c). The spring constant can be calculated using the geometry and the physical properties of the cantilever material [11.8,94,137]. However, the properties of the PECVD $\mathrm{Si_3N_4}$ (used in fabricating cantilevers) could be different from those of the bulk material. For example, by using an ultrasonic measurement, we found the Young's modulus of the cantilever beam to be about 238 ± 18 GPa which is less than that of bulk $\mathrm{Si_3N_4}$ (310 GPa). Furthermore the thickness of the beam is nonuniform and difficult to measure precisely. Since the stiffness of a beam goes as the cube of thickness, minor errors in precise measurements of thickness can introduce substantial stiffness errors. Thus one should experimentally measure the spring constant of the cantilever. *Cleveland* et al. [11.145] measured the normal spring constant by measuring resonant frequencies of the beams.

For normal spring constant measurement, *Ruan* and *Bhushan* [11.136] used a stainless steel spring sheet of known stiffness (width = 1.35 mm, thickness = 15 μm, free hanging length = 5.2 mm). One end of the spring was attached to the sample holder and the other end was made to contact with the cantilever tip during the measurement, see Fig. 11.23. They measured the piezo traveling distance for a given cantilever deflection. For a rigid sample (such as diamond), the piezo traveling distance Z_t (measured from the point where the tip touches the sample) should equal the cantilever deflection. To keep the cantilever deflection at the same level using a flexible spring sheet, the new piezo traveling distance $Z_{\mathrm{t}'}$ would be different from Z_t. The difference between $Z_{\mathrm{t}'}$ and Z_t corresponds to the deflection of the spring



Fig. 11.23a,b Illustration showing the deflection of cantilever as it is pushed by **(a)** a rigid sample or by **(b)** a flexible spring sheet [11.136]

sheet. If the spring constant of the spring sheet is k_s, the spring constant of the cantilever k_c can be calculated by

$$(Z_{\mathrm{t}'} - Z_\mathrm{t})k_\mathrm{s} = Z_\mathrm{t} k_\mathrm{c}$$

or

$$k_\mathrm{c} = k_\mathrm{s}(Z_{\mathrm{t}'} - Z_\mathrm{t})/Z_\mathrm{t} \,. \tag{11.8}$$

The spring constant of the spring sheet (k_s) used in this study is calculated to be 1.54 N/m. For a wide-legged cantilever used in our study (length = 115 μm, base width = 122 μm, leg width = 21 μm, and thickness = 0.6 μm), k_c was measured to be 0.40 N/m instead of 0.58 N/m reported by its manufacturer – Digital Instruments Inc. To relate photodiode detector output to the cantilever deflection in nm, they used the same rigid sample to push against the AFM tip. Since for a rigid sample the cantilever vertical deflection equals the sample traveling distance measured from the point where the tip touches the sample, the photodiode output as the tip is pushed by the sample can be converted directly to cantilever deflection. For these measurements, they found the conversion factor to be 20 nm/V.

The normal force applied to the tip can be calculated by multiplying the cantilever vertical deflection by the cantilever spring constant for samples which have very small adhesive force with the tip. If the adhesive force between the sample and the tip is large, it should be included in the normal force calculation. This is particularly important in atomic-scale force measurement because in this region, the typical normal force that is measured is in the range of a few hundreds of nN to a few mN. The adhesive force could be comparable to the applied force.

The conversion of friction signal (from $\mathrm{FFM_T}$ to friction force) is not as straightforward. For example, one can calculate the degree of twisting for a given friction force using the geometry and the physical properties of the cantilever [11.53, 144]. One would need the information on the detectors such as the quantum efficiency of the detector, the laser power, the instrument's gain, etc. in order to be able convert the signal into the degree of twisting. Generally speaking, this procedure can not be accomplished without having some detailed information about the instrument. This information is not usually provided by the manufactures. Even if this information is readily available, error may still occur in using this approach because there will always be variations as a result of the instrumental set up. For example, it has been noticed that the measured $\mathrm{FFM_T}$ signal could be different for the same sample when different AFM microscopes of the same kind are used. The essence is that, one can not calibrate the instrument experimentally using this calculation. *O'Shea* et al. [11.144] did perform a calibration procedure in which the torsional signal was measured as the sample is displaced a known distance laterally while ensuring that the tip does not slide over the surface. However, it is difficult to verify that tip sliding does not occur.

Apparently, a new method of calibration is required. There is a more direct and simpler way of doing this. The first method described (method 1) to measure friction can directly provide an absolute value of the coefficient of friction. It can therefore be used just as an internal means of calibration for the data obtained using method 2. Or for a polished sample which introduces least error in friction measurement using method 1, method 1 can be used to obtain calibration for friction force for method 2. Then this calibration can be used for measurement on all samples using method 2. In method 1, the length of the cantilever required can be measured using an optical microscope; the length of the tip can be measured using a scanning electron microscope. The relative angle between the cantilever and the horizontal sample surface can be measured directly. Thus the coefficient of friction can be measured with few unknown parameters. The friction force can then be calculated by multiplying the coefficient of friction by the normal load. The $\mathrm{FFM_T}$ signal obtained using method 2 can then be converted into friction force. For their instrument, they found the conversion to be 8.6 nN/V.

11.3 AFM Instrumentation and Analyses

The performance of AFMs and the quality of AFM images greatly depend on the instrument available and the probes (cantilever and tips) in use. This section describes the mechanics of cantilevers, instrumentation and analysis of force detection systems for cantilever deflections, and scanning and control systems.

11.3.1 The Mechanics of Cantilevers

Stiffness and Resonances of Lumped Mass Systems

Any one of the building blocks of an AFM, be it the body of the microscope itself or the force measuring cantilevers, are mechanical resonators. These resonances can be excited either by the surroundings or by the rapid movement of the tip or the sample. To avoid problems due to building or air induced oscillations, it is of paramount importance to optimize the design of AFMs for high resonant frequencies. This usually means decreasing the size of the microscope [11.146]. By using cube-like or sphere-like structures for the microscope, one can considerably increase the lowest eigenfrequency. The fundamental natural frequency, ω_0, of any spring is given by

$$\omega_0 = \frac{1}{2\pi}\sqrt{\frac{k}{m_{\text{eff}}}} , \tag{11.9}$$

where k is the spring constant (stiffness) in the normal direction and m_{eff} is the effective mass. The spring constant k of a cantilever beam with uniform cross section (Fig. 11.24) is given by [11.147]

$$k = \frac{3EI}{L^3} , \tag{11.10}$$

where E is the Young's modulus of the material, L is the length of the beam and I is the moment of inertia of the cross section. For a rectangular cross section with a width b (perpendicular to the deflection) and a height h one obtains an expression for I

$$I = \frac{bh^3}{12} . \tag{11.11}$$

Combining (11.9), (11.10) and (11.11) we get an expression for ω_0

$$\omega_0 = \sqrt{\frac{Ebh^3}{4L^3 m_{\text{eff}}}} . \tag{11.12}$$

The effective mass can be calculated using Raleigh's method. The general formula using Raleigh's method for the kinetic energy T of a bar is

$$T = \frac{1}{2}\int_0^L \frac{m}{L}\left(\frac{\partial z(x)}{\partial t}\right)^2 \mathrm{d}x . \tag{11.13}$$

For the case of a uniform beam with a constant cross section and length L one obtains for the deflection $z(x) = z_{\max}\left[1-(3x/2L)+(x^3/2L^3)\right]$. Inserting $z_{\max}$ into (11.13) and solving the integral gives

$$\begin{aligned} T &= \frac{1}{2}\int_0^L \frac{m}{L}\left[\frac{\partial z_{\max}(x)}{\partial t}\left(1-\frac{3x}{2L}\right)+\left(\frac{x^3}{L^3}\right)\right]^2 \mathrm{d}x \\ &= \frac{1}{2} m_{\text{eff}} (z_{\max} t)^2 , \end{aligned}$$



Fig. 11.24 A typical AFM cantilever with length L, width b, and height h. The height of the tip is ℓ. The material is characterized by Young's modulus E, the shear modulus G and a mass density ρ. Normal (F_z), axial (F_x), and lateral (F_y) forces exist at the end of the tip

which gives

$$m_{\text{eff}} = \frac{9}{20} m . \tag{11.14}$$

Substituting (11.14) into (11.12) and noting that $m = \rho L b h$, where ρ is the mass density, one obtains the following expression

$$\omega_0 = \left(\frac{\sqrt{5}}{3}\sqrt{\frac{\mathrm{E}}{\rho}}\right)\frac{\mathrm{h}}{L^2} . \tag{11.15}$$

It is evident from (11.15), that one way to increase the natural frequency is to choose a material with a high ratio E/ρ; see Table 11.2 for typical values of $\sqrt{E/\rho}$ of various commonly used materials. Another way to increase the lowest eigenfrequency is also evident in (11.15). By optimizing the ratio h/L^2, one can increase the resonant frequency. However it does not help to make the length of the structure smaller than the width or height. Their roles will just be interchanged. Hence the optimum structure is a cube. This leads to the design rule, that long, thin structures like sheet metal should be avoided. For a given resonant frequency, the quality factor Q should be as low as possible. This means that an inelastic medium such as rubber should be in contact with the structure to convert kinetic energy into heat.

Stiffness and Resonances of Cantilevers

Cantilevers are mechanical devices specially shaped to measure tiny forces. The analysis given in the previous section is applicable. However, to understand better the intricacies of force detection systems we will discuss the example of a cantilever beam with uniform cross section, Fig. 11.24. The bending of a beam due to a normal load on the beam is governed by the Euler equation [11.147]

$$M = EI(x)\frac{\mathrm{d}^2 z}{\mathrm{d}x^2}\,, \tag{11.16}$$

where M is the bending moment acting on the beam cross section. $I(x)$ the moment of inertia of the cross section with respect to the neutral axis defined by

$$I(x) = \int_z \int_y z^2\,\mathrm{d}y\,\mathrm{d}z\,. \tag{11.17}$$

For a normal force F_z acting at the tip,

$$M(x) = (L - x)\,F_z \tag{11.18}$$

since the moment must vanish at the endpoint of the cantilever. Integrating (11.16) for a normal force F_z acting at the tip and observing that EI is a constant for beams with a uniform cross section, one gets

$$z(x) = \frac{L^3}{6EI}\left(\frac{x}{L}\right)^2\left(3 - \frac{x}{L}\right)F_z\,. \tag{11.19}$$

The slope of the of the beam is

$$z'(x) = \frac{Lx}{2EI}\left(2 - \frac{x}{L}\right)F_z\,. \tag{11.20}$$

From (11.19) and (11.20), at the end of the cantilever, i. e. for $x = L$, for a rectangular beam, and by using an expression for I in (11.11), one gets,

$$z(L) = \frac{4}{Eb}\left(\frac{L}{h}\right)^3 F_z\,, \tag{11.21}$$

$$z'(L) = \frac{3}{2}\left(\frac{z}{L}\right)\,. \tag{11.22}$$

Now the stiffness in the normal (z) direction, k_z, is

$$k_z = \frac{F_z}{z(L)} = \frac{Eb}{4}\left(\frac{h}{L}\right)^3\,. \tag{11.23}$$

and a change in angular orientation of the end of cantilever beam is

$$\Delta\alpha = \frac{3}{2}\frac{z}{L} = \frac{6}{Ebh}\left(\frac{L}{h}\right)^2 F_z\,. \tag{11.24}$$

Now we ask what will, to first order, happen if we apply a lateral force F_y to the end of the tip (Fig. 11.24). The cantilever will bend sideways and it will twist. The stiffness in the lateral (y) direction, k_y, can be calculated with (11.23) by exchanging b and h

$$k_y = \frac{Eh}{4}\left(\frac{b}{L}\right)^3\,. \tag{11.25}$$

Therefore the bending stiffness in lateral direction is larger than the stiffness for bending in the normal direction by $(b/h)^2$. The twisting or torsion on the other hand is more complicated to handle. For a wide, thin cantilever ($b \gg h$) we obtain torsional stiffness along y axis, k_{yT}

$$k_{yT} = \frac{Gbh^3}{3L\ell^2}\,, \tag{11.26}$$

where G is the modulus of rigidity ($= E/2(1+\nu)$, where ν is the Poisson's ratio). The ratio of the torsional stiffness to the lateral bending stiffness is

$$\frac{k_{yT}}{k_y} = \frac{1}{2}\left(\frac{\ell b}{hL}\right)^2\,, \tag{11.27}$$

where we assume $\nu = 0.333$. We see that thin, wide cantilevers with long tips favor torsion while cantilevers with square cross sections and short tips favor bending. Finally we calculate the ratio between the torsional stiffness and the normal bending stiffness,

$$\frac{k_{yT}}{k_z} = 2\left(\frac{L}{\ell}\right)^2\,. \tag{11.28}$$

Equations (11.26) to (11.28) hold in the case where the cantilever tip is exactly in the middle axis of the cantilever. Triangular cantilevers and cantilevers with tips not on the middle axis can be dealt with by finite element methods.

The third possible deflection mode is the one from the force on the end of the tip along the cantilever axis, F_x (Fig. 11.24). The bending moment at the free end of the cantilever is equal to the $F_x\ell$. This leads to the following modification of (11.18) for the case of forces F_z and F_x

$$M(x) = (L - x)\,F_z + F_x\ell\,. \tag{11.29}$$

Integration of (11.16) now leads to

$$z(x) = \frac{1}{2EI}\left[Lx^2\left(1 - \frac{x}{3L}\right)F_z + \ell x^2 F_x\right] \tag{11.30}$$

and

$$z'(x) = \frac{1}{EI}\left[\frac{Lx}{2}\left(2 - \frac{x}{L}\right)F_z + \ell x F_x\right]\,. \tag{11.31}$$

Evaluating (11.30) and (11.31) at the end of the cantilever, we get the deflection and the tilt

$$\begin{aligned} z(L) &= \frac{L^2}{EI}\left(\frac{L}{3}F_z - \frac{\ell}{2}F_x\right)\,, \\ z'(L) &= \frac{L}{EI}\left(\frac{L}{2}F_z + \ell F_x\right)\,. \end{aligned} \tag{11.32}$$

From these equations, one gets

$$F_z = \frac{12EI}{L^3}\left[z(L) - \frac{Lz'(L)}{2}\right] ,$$
$$F_x = \frac{2EI}{\ell L^2}\left[2Lz'(L) - 3z(L)\right] . \tag{11.33}$$

A second class of interesting properties of cantilevers is their resonance behavior. For cantilever beams one can calculate the resonant frequencies [11.147, 148]

$$\omega_n^{\text{free}} = \frac{\lambda_n^2}{2\sqrt{3}}\frac{h}{L^2}\sqrt{\frac{E}{\rho}} \tag{11.34}$$

with $\lambda_0 = (0.596864\ldots)\pi$, $\lambda_1 = (1.494175\ldots)\pi$, $\lambda_n \to (n+1/2)\pi$. The subscript n represents the order of the frequency, e.g., fundamental, second mode, and the nth mode.

A similar equation to (11.34) holds for cantilevers in rigid contact with the surface. Since there is an additional restriction on the movement of the cantilever, namely the location of its end point, the resonant frequency increases. Only the λ_n's terms change to [11.148]

$$\lambda'_0 = (1.2498763\ldots)\pi, \quad \lambda'_1 = (2.2499997\ldots)\pi,$$
$$\lambda'_n \to (n+1/4)\pi . \tag{11.35}$$

The ratio of the fundamental resonant frequency in contact to the fundamental resonant frequency not in contact is 4.3851.

For the torsional mode we can calculate the resonant frequencies as

$$\omega_0^{\text{tors}} = 2\pi\frac{h}{Lb}\sqrt{\frac{G}{\rho}} . \tag{11.36}$$

For cantilevers in rigid contact with the surface, we obtain the expression for the fundamental resonant frequency [11.148]

$$\omega_0^{\text{tors, contact}} = \frac{\omega_0^{\text{tors}}}{\sqrt{1+3(2L/b)^2}} . \tag{11.37}$$

The amplitude of the thermally induced vibration can be calculated from the resonant frequency using

$$\Delta z_{\text{therm}} = \sqrt{\frac{k_B T}{k}} , \tag{11.38}$$

where k_B is Boltzmann's constant and T is the absolute temperature. Since AFM cantilevers are resonant structures, sometimes with rather high Q, the thermal noise is not evenly distributed as (11.38) suggests. The spectral noise density below the peak of the response curve is [11.148]

$$z_0 = \sqrt{\frac{4k_B T}{k\omega_0 Q}} \quad (\text{in m}/\sqrt{\text{Hz}}) , \tag{11.39}$$

where Q is the quality factor of the cantilever, described earlier.

11.3.2 Instrumentation and Analyses of Detection Systems for Cantilever Deflections

A summary of selected detection systems was provided in Fig. 11.8. Here we discuss in detail pros and cons of various systems.

Optical Interferometer Detection Systems

Soon after the first papers on the AFM [11.2] appeared, which used a tunneling sensor, an instrument based on an interferometer was published [11.149]. The sensitivity of the interferometer depends on the wavelength of the light employed in the apparatus. Figure 11.25 shows the principle of such an interferometeric design. The light incident from the left is focused by a lens on the cantilever. The reflected light is collimated by the same lens and interferes with the light reflected at the flat. To separate the reflected light from the incident light a $\lambda/4$ plate converts the linear polarized incident light to circular polarization. The reflected light is made linear polarized again by the $\lambda/4$-plate, but with a polarization orthogonal to that of the incident light. The polarizing



Fig. 11.25 Principle of an interferometric AFM. The light of the laser light source is polarized by the polarizing beam splitter and focused on the back of the cantilever. The light passes twice through a quarter wave plate and is hence orthogonally polarized to the incident light. The second arm of the interferometer is formed by the flat. The interference pattern is modulated by the oscillating cantilever

beam splitter then deflects the reflected light to the photo diode.

Homodyne Interferometer. To improve the signal to noise ratio of the interferometer the cantilever is driven by a piezo near its resonant frequency. The amplitude Δz of the cantilever as a function of driving frequency Ω is

$$\Delta z\,(\Omega) = \Delta z_0 \frac{\Omega_0^2}{\sqrt{\left(\Omega^2-\Omega_0^2\right)^2 + \frac{\Omega^2\Omega_0^2}{Q^2}}}\,, \tag{11.40}$$

where Δz_0 is the constant drive amplitude and Ω_0 the resonant frequency of the cantilever. The resonant frequency of the cantilever is given by the effective potential

$$\Omega_0 = \sqrt{\left(k+\frac{\partial^2 U}{\partial z^2}\right)\frac{1}{m_{\mathrm{eff}}}}\,, \tag{11.41}$$

where U is the interaction potential between the tip and the sample. Equation (11.41) shows that an attractive potential decreases Ω_0. The change in Ω_0 in turn results in a change of the Δz (see (11.40)). The movement of the cantilever changes the path difference in the interferometer. The light reflected from the cantilever with the amplitude $A_{\ell,0}$ and the reference light with the amplitude $A_{r,0}$ interfere on the detector. The detected intensity $I(t) = [A_\ell(t) + A_r(t)]^2$ consists of two constant terms and a fluctuating term

$$\begin{aligned} &2A_\ell\,(t)\,A_r\,(t) = \\ &A_{\ell,0}A_{r,0}\sin\left[\omega t + \frac{4\pi\delta}{\lambda} + \frac{4\pi\Delta z}{\lambda}\sin\,(\Omega t)\right]\sin\,(\omega t)\;. \end{aligned} \tag{11.42}$$

Here ω is the frequency of the light, λ is the wavelength of the light, δ is the path difference in the interferometer, and Δz is the instantaneous amplitude of the cantilever, given according to (11.40) and (11.41) as a function of Ω, k, and U. The time average of (11.42) then becomes

$$\begin{aligned} \langle 2A_\ell\,(t)\,A_r\,(t)\rangle_T &\propto \cos\left[\frac{4\pi\delta}{\lambda} + \frac{4\pi\Delta z}{\lambda}\sin\,(\Omega t)\right] \\ &\approx \cos\left(\frac{4\pi\delta}{\lambda}\right) - \sin\left[\frac{4\pi\Delta z}{\lambda}\sin\,(\Omega t)\right] \\ &\approx \cos\left(\frac{4\pi\delta}{\lambda}\right) - \frac{4\pi\Delta z}{\lambda}\sin\,(\Omega t)\;. \end{aligned} \tag{11.43}$$

Here all small quantities have been omitted and functions with small arguments have been linearized. The amplitude of Δz can be recovered with a lock-in technique. However, (11.43) shows that the measured amplitude is also a function of the path difference δ in the interferometer. Hence this path difference δ must be very stable. The best sensitivity is obtained when $\sin(4\delta/\lambda) \approx 0$.

Heterodyne Interferometer. This influence is not present in the heterodyne detection scheme shown in Fig. 11.26. Light incident from the left with a frequency ω is split in a reference path (upper path in Fig. 11.26) and a measurement path. Light in the measurement path is shifted in frequency to $\omega_1 = \omega + \Delta\omega$ and focused on the cantilever. The cantilever oscillates at the frequency Ω, as in the homodyne detection scheme. The reflected light $A_\ell(t)$ is collimated by the same lens and interferes on the photo diode with the reference light $A_r(t)$. The fluctuating term of the intensity is given by

$$\begin{aligned} 2A_\ell\,(t)\,A_r\,(t) = A_{\ell,0}A_{r,0}\sin&\left[(\omega+\Delta\omega)\,t + \frac{4\pi\delta}{\lambda}\right. \\ &\left.+\frac{4\pi\Delta z}{\lambda}\sin\,(\Omega t)\right]\sin\,(\omega t)\;, \end{aligned} \tag{11.44}$$

where the variables are defined as in (11.42). Setting the path difference $\sin(4\pi\delta/\lambda) \approx 0$ and taking the time average, omitting small quantities and linearizing functions with small arguments we get

$$\begin{aligned} &\langle 2A_\ell\,(t)\,A_r\,(t)\rangle_T \\ &\propto \cos\left[\Delta\omega t + \frac{4\pi\delta}{\lambda} + \frac{4\pi\Delta z}{\lambda}\sin\,(\Omega t)\right] \end{aligned}$$



Fig. 11.26 Principle of a heterodyne interferometric AFM. Light with the frequency ω_0 is split into a reference path (upper path) and a measurement path. The light in the measurement path is frequency shifted to ω_1 by an acousto-optical modulator (or an electro-optical modulator) The light reflected from the oscillating cantilever interferes with the reference beam on the detector

$$
\begin{aligned}
&= \cos\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right)\cos\left[\frac{4\pi\Delta z}{\lambda}\sin(\Omega t)\right] \\
&\quad - \sin\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right)\sin\left[\frac{4\pi\Delta z}{\lambda}\sin(\Omega t)\right] \\
&\approx \cos\left(\frac{4\pi\delta}{\lambda}\right) - \sin\left[\frac{4\pi\Delta z}{\lambda}\sin(\Omega t)\right] \\
&\approx \cos\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right)\left[1 - \frac{8\pi^2\Delta z^2}{\lambda^2}\sin(\Omega t)\right] \\
&\quad - \frac{4\pi\Delta z}{\lambda}\sin\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right)\sin(\Omega t) \\
&= \cos\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right) - \frac{8\pi^2\Delta z^2}{\lambda^2}\cos\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right) \\
&\quad \times\sin(\Omega t) - \frac{4\pi\Delta z}{\lambda}\sin\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right)\sin(\Omega t) \\
&= \cos\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right) - \frac{4\pi^2\Delta z^2}{\lambda^2}\cos\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right) \\
&\quad + \frac{4\pi^2\Delta z^2}{\lambda^2}\cos\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right)\cos(2\Omega t) \\
&\quad - \frac{4\pi\Delta z}{\lambda}\sin\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right)\sin(\Omega t) \\
&= \cos\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right)\left(1 - \frac{4\pi^2\Delta z^2}{\lambda^2}\right) \\
&\quad + \frac{2\pi^2\Delta z^2}{\lambda^2}\left\{\cos\left[(\Delta\omega + 2\Omega)\,t + \frac{4\pi\delta}{\lambda}\right]\right. \\
&\quad \left. + \cos\left[(\Delta\omega - 2\Omega)\,t + \frac{4\pi\delta}{\lambda}\right]\right\} \\
&\quad + \frac{2\pi\Delta z}{\lambda}\left\{\cos\left[(\Delta\omega + \Omega)\,t + \frac{4\pi\delta}{\lambda}\right]\right. \\
&\quad \left. + \cos\left[(\Delta\omega - \Omega)\,t + \frac{4\pi\delta}{\lambda}\right]\right\} .
\end{aligned}
\tag{11.45}
$$

Multiplying electronically the components oscillating at $\Delta\omega$ and $\Delta\omega + \Omega$ and rejecting any product except the one oscillating at Ω we obtain

$$
\begin{aligned}
A &= \frac{2\Delta z}{\lambda}\left(1 - \frac{4\pi^2\Delta z^2}{\lambda^2}\right)\cos\left[(\Delta\omega + 2\Omega)\,t + \frac{4\pi\delta}{\lambda}\right] \\
&\quad \times\cos\left(\Delta\omega t + \frac{4\pi\delta}{\lambda}\right) \\
&= \frac{\Delta z}{\lambda}\left(1 - \frac{4\pi^2\Delta z^2}{\lambda^2}\right)\left\{\cos\left[(2\Delta\omega + \Omega)\,t + \frac{8\pi\delta}{\lambda}\right]\right. \\
&\quad \left. + \cos(\Omega t)\right\} \\
&\approx \frac{\pi\Delta z}{\lambda}\cos(\Omega t) .
\end{aligned}
\tag{11.46}
$$

Unlike in the homodyne detection scheme the recovered signal is independent from the path difference δ of the interferometer. Furthermore a lock-in amplifier with the reference set $\sin(\Delta\omega t)$ can measure the path difference δ independent of the cantilever oscillation. If necessary, a feedback circuit can keep $\delta = 0$.

Fiber-optical Interferometer. The fiber-optical interferometer [11.129] is one of the simplest interferometers to build and use. Its principle is sketched in Fig. 11.27. The light of a laser is fed into an optical fiber. Laser diodes with integrated fiber pigtails are convenient light sources. The light is split in a fiber-optic beam splitter into two fibers. One fiber is terminated by index matching oil to avoid any reflections back into the fiber. The end of the other fiber is brought close to the cantilever in the AFM. The emerging light is partially reflected back into the fiber by the cantilever. Most of the light, however, is lost. This is not a big problem since only 4% of the light is reflected at the end of the fiber, at the glass-air interface. The two reflected light waves interfere with each other. The product is guided back into the fiber coupler and again split into two parts. One half is analyzed by the photodiode. The other half is fed back into the laser. Communications grade laser diodes are sufficiently resistant against feedback to be operated in this environment. They have, however, a bad coherence length, which in this case does not matter, since the optical path difference is in any case no larger than 5 µm. Again the end of the fiber has to be positioned on a piezo drive to set the distance between the fiber and the cantilever to $\lambda(n + 1/4)$.



Fig. 11.27 A typical setup for a fiber optic interferometer readout

Nomarski-Interferometer. Another solution to minimize the optical path difference is to use the Nomarski interferometer [11.130]. Figure 11.28 shows a schematic of the microscope. The light of a laser is focused on the cantilever by lens. A birefringent crystal (for instance calcite) between the cantilever and the lens with its optical axis 45° off the polarization direction of the light



Fig. 11.28 Principle of Nomarski AFM. The circular polarized input beam is deflected to the left by a non-polarizing beam splitter. The light is focused onto a cantilever. The calcite crystal between the lens and the cantilever splits the circular polarized light into two spatially separated beams with orthogonal polarizations. The two light beams reflected from the lever are superimposed by the calcite crystal and collected by the lens. The resulting beam is again circular polarized. A Wollaston prism produces two interfering beams with $\pi/2$ phase shift between them. The minimal path difference accounts for the excellent stability of this microscope

splits the light beam into two paths, offset by a distance given by the length of the crystal. Birefringent crystals have varying indexes of refraction. In calcite, one crystal axis has a lower index than the other two. This means, that certain light rays will propagate at a different speed through the crystal than the others. By choosing a correct polarization, one can select the ordinary ray, the extraordinary ray or one can get any distribution of the intensity amongst those two rays. A detailed description of birefringence can be found in textbooks (e.g., [11.150]). A calcite crystal deflects the extraordinary ray at an angle of 6° within the crystal. By choosing a suitable length of the calcite crystal, any separation can be set.

The focus of one light ray is positioned near the free end of the cantilever while the other is placed close to the clamped end. Both arms of the interferometer pass through the same space, except for the distance between the calcite crystal and the lever. The closer the calcite crystal is placed to the lever, the less influence disturbances like air currents have.

Sarid [11.116] has given values for the sensitivity of the different interferometeric detection systems. Table 11.5 presents a summary of his results.

Optical Lever

The most common cantilever deflection detection system is the optical lever [11.53, 111]. This method, depicted in Fig. 11.29, employs the same technique as light beam deflection galvanometers. A fairly well collimated light beam is reflected off a mirror and projected to a receiving target. Any change in the angular position of the mirror will change the position, where the light ray hits the target. Galvanometers use optical path lengths of several meters and scales projected to the target wall as a read-out help.

For the AFM using the optical lever method a photodiode segmented into two (or four) closely spaced devices detects the orientation of the end of the cantilever. Initially, the light ray is set to hit the photodiodes in the middle of the two sub-diodes. Any deflection of

Table 11.5 Noise in Interferometers. F is the finesse of the cavity in the homodyne interferometer, P_i the incident power, P_d is the power on the detector, η is the sensitivity of the photodetector and RIN is the relative intensity noise of the laser. P_R and P_S are the power in the reference and sample beam in the heterodyne interferometer. P is the power in the Nomarski interferometer, $\delta\theta$ is the phase difference between the reference and the probe beam in the Nomarski interferometer. B is the bandwidth, e is the electron charge, λ is the wavelength of the laser, k the cantilever stiffness, ω_0 is the resonant frequency of the cantilever, Q is the quality factor of the cantilever, T is the temperature, and δi is the variation of current i

	Homodyne interferometer, fiber optic interferometer	**Heterodyne interferometer**	**Nomarski interferometer**
Laser noise $\langle \delta i^2 \rangle_\mathrm{L}$	$\frac{1}{4}\eta^2 F^2 P_i^2$ RIN	$\eta^2\left(P_R^2+P_S^2\right)$ RIN	$\frac{1}{16}\eta^2 P^2 \delta\theta$
Thermal noise $\langle \delta i^2 \rangle_\mathrm{T}$	$\frac{16\pi^2}{\lambda^2}\eta^2 F^2 P_i^2 \frac{4k_\mathrm{B}TBQ}{\omega_0 k}$	$\frac{4\pi^2}{\lambda^2}\eta^2 P_d^2 \frac{4k_\mathrm{B}TBQ}{\omega_0 k}$	$\frac{\pi^2}{\lambda^2}\eta^2 P^2 \frac{4k_\mathrm{B}TBQ}{\omega_0 k}$
Shot Noise $\langle \delta i^2 \rangle_\mathrm{S}$	$4e\eta P_\mathrm{d} B$	$2e\eta\left(P_\mathrm{R}+P_\mathrm{S}\right) B$	$\frac{1}{2}e\eta PB$



Fig. 11.29 The setup of optical lever detection microscope

the cantilever will cause an imbalance of the number of photons reaching the two halves. Hence the electrical currents in the photodiodes will be unbalanced too. The difference signal is further amplified and is the input signal to the feedback loop. Unlike the interferometeric AFMs, where often a modulation technique is necessary to get a sufficient signal to noise ratio, most AFMs employing the optical lever method are operated in a static mode. AFMs based on the optical lever method are universally used. It is the simplest method for constructing an optical readout and it can be confined in volumes smaller than 5 cm on the side.

The optical lever detection system is a simple yet elegant way to detect normal and lateral force signals simultaneously [11.7, 8, 53, 111]. It has the additional advantage that it is the fact that it is a remote detection system.

Implementations. Light from a laser diode or from a super luminescent diode is focused on the end of the cantilever. The reflected light is directed onto a quadrant diode that measures the direction of the light beam. A Gaussian light beam far from its waist is characterized by an opening angle β. The deflection of the light beam by the cantilever surface tilted by an angle α is 2α. The intensity on the detector then shifts to the side by the product of 2α and the separation between the detector and the cantilever. The readout electronics calculates the difference of the photocurrents. The photocurrents in turn are proportional to the intensity incident on the diode.

The output signal is hence proportional to the change in intensity on the segments

$$I_{\text{sig}} \propto 4\frac{\alpha}{\beta} I_{\text{tot}} . \tag{11.47}$$

For the sake of simplicity, we assume that the light beam is of uniform intensity with its cross section increasing proportional to the distance between the cantilever and the quadrant detector. The movement of the center of the light beam is then given by

$$\Delta x_{\text{Det}} = \Delta z \frac{D}{L} . \tag{11.48}$$

The photocurrent generated in a photodiode is proportional to the number of incoming photons hitting it. If the light beam contains a total number of N_0 photons then the change in difference current becomes

$$\Delta\left(I_{\text{R}} - I_{\text{L}}\right) = \Delta I = \text{const}\, \Delta z\, D\, N_0 . \tag{11.49}$$

Combining (11.48) and (11.49), one obtains that the difference current ΔI is independent of the separation of the quadrant detector and the cantilever. This relation is true, if the light spot is smaller than the quadrant detector. If it is greater, the difference current ΔI becomes smaller with increasing distance. In reality the light beam has a Gaussian intensity profile. For small movements Δx (compared to the diameter of the light spot at the quadrant detector), (11.49) still holds. Larger movements Δx, however, will introduce a nonlinear response. If the AFM is operated in a constant force mode, only small movements Δx of the light spot will occur. The feedback loop will cancel out all other movements.

The scanning of a sample with an AFM can twist the microfabricated cantilevers because of lateral forces [11.5, 7, 8] and affect the images [11.120]. When the tip is subjected to lateral forces, it will twist the cantilever and the light beam reflected from the end of the cantilever will be deflected perpendicular to the ordinary deflection direction. For many investigations this influence of lateral forces is unwanted. The design of the triangular cantilevers stems from the desire, to minimize the torsion effects. However, lateral forces open up a new dimension in force measurements. They allow, for instance, a distinction of two materials because of the different friction coefficient, or the determination of adhesion energies. To measure lateral forces the original optical lever AFM has to be modified. The only modification compared with Fig. 11.29 is the use of a quadrant detector photodiode instead of a two-segment photodiode and the necessary readout electronics, see Fig. 11.9a. The electronics calculates the following signals:

$$\begin{aligned} U_{\text{Normal Force}} &= \alpha\left[\left(I_{\text{Upper Left}} + I_{\text{Upper Right}}\right)\right. \\ &\qquad \left.- \left(I_{\text{Lower Left}} + I_{\text{Lower Right}}\right)\right] , \\ U_{\text{Lateral Force}} &= \beta\left[\left(I_{\text{Upper Left}} + I_{\text{Lower Left}}\right)\right. \\ &\qquad \left.- \left(I_{\text{Upper Right}} + I_{\text{Lower Right}}\right)\right] . \end{aligned} \tag{11.50}$$

The calculation of the lateral force as a function of the deflection angle does not have a simple solution for cross-sections other than circles. An approximate formula for the angle of twist for rectangular beams is [11.151]

$$\theta = \frac{M_t L}{\beta G b^3 h}\,, \tag{11.51}$$

where $M_t = F_y \ell$ is the external twisting moment due to lateral force, F_y, and β a constant determined by the value of h/b. For the equation to hold, h has to be larger than b.

Inserting the values for a typical microfabricated cantilever with integrated tips

$$\begin{aligned} b &= 6\times10^{-7}\,\text{m}\,,\\ h &= 10^{-5}\,\text{m}\,,\\ L &= 10^{-4}\,\text{m}\,,\\ \ell &= 3.3\times10^{-6}\,\text{m}\,,\\ G &= 5\times10^{10}\,\text{Pa}\,,\\ \beta &= 0.333 \end{aligned} \tag{11.52}$$

into (11.51) we obtain the relation

$$F_y = 1.1\times10^{-4}\,\text{N}\times\theta\,. \tag{11.53}$$

Typical lateral forces are of order 10^{-10} N.

Sensitivity. The sensitivity of this setup has been calculated in various papers [11.116, 148, 152]. Assuming a Gaussian beam the resulting output signal as a function of the deflection angle is dispersion like. Equation (11.47) shows that the sensitivity can be increased by increasing the intensity of the light beam I_{tot} or by decreasing the divergence of the laser beam. The upper bound of the intensity of the light I_{tot} is given by saturation effects on the photodiode. If we decrease the divergence of a laser beam we automatically increase the beam waist. If the beam waist becomes larger than the width of the cantilever we start to get diffraction. Diffraction sets a lower bound on the divergence angle. Hence one can calculate the optimal beam waist w_{opt} and the optimal divergence angle β [11.148, 152]

$$\begin{aligned} w_{\text{opt}} &\approx 0.36b\,,\\ \theta_{\text{opt}} &\approx 0.89\frac{\lambda}{b}\,. \end{aligned} \tag{11.54}$$

The optimal sensitivity of the optical lever then becomes

$$\varepsilon\,[\text{mW/rad}] = 1.8\frac{b}{\lambda} I_{\text{tot}}\ [\text{mW}]\ . \tag{11.55}$$

The angular sensitivity optical lever can be measured by introducing a parallel plate into the beam. A tilt of the parallel plate results in a displacement of the beam, mimicking an angular deflection.

Additional noise sources can be considered. Of little importance is the quantum mechanical uncertainty of the position [11.148, 152], which is, for typical cantilevers at room temperature

$$\Delta z = \sqrt{\frac{\hbar}{2m\omega_0}} = 0.05\,\text{fm}\,, \tag{11.56}$$

where $\hbar$ is the Planck constant ($= 6.626\times10^{-34}$ J s). At very low temperatures and for high frequency cantilevers this could become the dominant noise source. A second noise source is the shot noise of the light. The shot noise is related to the particle number. We can calculate the number of photons incident on the detector

$$n = \frac{I\tau}{\hbar\omega} = \frac{I\lambda}{2\pi B\hbar c} = 1.8\times10^{9}\,\frac{I[\text{W}]}{B[\text{Hz}]}\,, \tag{11.57}$$

where I is the intensity of the light, τ the measurement time, $B = 1/\tau$ the bandwidth, and c the speed of light. The shot noise is proportional to the square root of the number of particles. Equating the shot noise signal with the signal resulting for the deflection of the cantilever one obtains

$$\Delta z_{\text{shot}} = 68\frac{L}{w}\sqrt{\frac{B\,[\text{kHz}]}{I\,[\text{mW}]}}\,[\text{fm}]\ , \tag{11.58}$$

where w is the diameter of the focal spot. Typical AFM setups have a shot noise of 2 pm. The thermal noise can be calculated from the equipartition principle. The amplitude at the resonant frequency is

$$\Delta z_{\text{therm}} = 129\sqrt{\frac{B}{k\,[\text{N/m}]\,\omega_0 Q}}\,\left[\text{pm}\right]. \tag{11.59}$$

A typical value is 16 pm. Upon touching the surface, the cantilever increases its resonant frequency by a factor of 4.39. This results in a new thermal noise amplitude of 3.2 pm for the cantilever in contact with the sample.

Piezoresistive Detection

Implementation. An alternative detection system which is not as widely used as the optical detection schemes are piezoresistive cantilevers [11.125, 126, 132]. These cantilevers are based on the fact that the resistivity of certain materials, in particular of Si, changes with the applied stress. Figure 11.30 shows a typical implementation of a piezo-resistive cantilever. Four



Fig. 11.30 A typical setup for a piezoresistive readout



Fig. 11.31 Three possible arrangements of a capacitive readout. The *upper left* shows the cross section through a parallel plate capacitor. The *lower left* shows the geometry of sphere versus plane. The *right side* shows the more complicated, but linear capacitive readout

resistances are integrated on the chip, forming a Wheatstone bridge. Two of the resistors are in unstrained parts of the cantilever, the other two are measuring the bending at the point of the maximal deflection. For instance when an AC voltage is applied between terminals a and c one can measure the detuning of the bridge between terminals b and d. With such a connection the output signal varies only due to bending, but not due to changing of the ambient temperature and thus the coefficient of the piezoresistance.

Sensitivity. The resistance change is [11.126]

$$\frac{\Delta R}{R_0} = \Pi\delta\,, \tag{11.60}$$

where Π is the tensor element of the piezo-resistive coefficients, δ the mechanical stress tensor element and R_0 the equilibrium resistance. For a single resistor they separate the mechanical stress and the tensor element in longitudinal and transverse components

$$\frac{\Delta R}{R_0} = \Pi_t\delta_t + \Pi_l\delta_l\,. \tag{11.61}$$

The maximum value of the stress components are $\Pi_t = -64.0\times10^{-11}\,\mathrm{m^2/N}$ and $\Pi_l = -71.4\times10^{-11}\,\mathrm{m^2/N}$ for a resistor oriented along the (110) direction in silicon [11.126]. In the resistor arrangement of Fig. 11.30 two of the resistors are subject to the longitudinal piezoresistive effect and two of them are subject to the transversal piezo-resistive effect. The sensitivity of that setup is about four times that of a single resistor, with the advantage that temperature effects cancel to first order. The resistance change is then calculated as

$$\frac{\Delta R}{R_0} = \Pi\frac{3Eh}{2L^2}\Delta z = \Pi\frac{6L}{bh^2}F_z\,, \tag{11.62}$$

where $\Pi = 67.7\times10^{-11}\,\mathrm{m^2/N}$ is the averaged piezoresistive coefficient. Plugging in typical values for the dimensions (Fig. 11.24) ($L = 100\,\mu\mathrm{m}$, $b = 10\,\mu\mathrm{m}$, $h = 1\,\mu\mathrm{m}$) one obtains

$$\frac{\Delta R}{R_0} = \frac{4\times10^{-5}}{\mathrm{nN}}F_z\,. \tag{11.63}$$

The sensitivity can be tailored by optimizing the dimensions of the cantilever.

Capacitance Detection

The capacitance of an arrangement of conductors depends on the geometry. Generally speaking, the capacitance increases for decreasing separations. Two parallel plates form a simple capacitor (see Fig. 11.31, upper left), with the capacitance

$$C = \frac{\varepsilon\varepsilon_0 A}{x}\,, \tag{11.64}$$

where A is the area of the plates, assumed equal, and x is the separation. Alternatively one can consider a sphere versus an infinite plane (see Fig. 11.31, lower left). Here the capacitance is [11.116]

$$C = 4\pi\varepsilon_0 R\sum_{n=2}^{\infty}\frac{\sinh(\alpha)}{\sinh(n\alpha)} \tag{11.65}$$

where R is the radius of the sphere, and α is defined by

$$\alpha = \ln\left(1 + \frac{z}{R} + \sqrt{\frac{z^2}{R^2} + 2\frac{z}{R}}\right)\,. \tag{11.66}$$

One has to keep in mind that capacitance of a parallel plate capacitor is a nonlinear function of the separation. Using a voltage divider one can circumvent this problem.



Fig. 11.32a,b Measuring the capacitance. The *left side*, **(a)**, shows a low pass filter, the *right side*, **(b)**, shows a capacitive divider. C (*left*) or C_2 (*right*) are the capacitances under test

Figure 11.32a shows a low pass filter. The output voltage is given by

$$U_{\text{out}} = U_\approx \frac{\frac{1}{j\omega C}}{R+\frac{1}{j\omega C}} = U_\approx \frac{1}{j\omega CR+1} \cong \frac{U_\approx}{j\omega CR} . \tag{11.67}$$

Here C is given by (11.64), ω is the excitation frequency and j is the imaginary unit. The approximate relation in the end is true when $\omega CR \gg 1$. This is equivalent to the statement that C is fed by a current source, since R must be large in this setup. Plugging (11.64) into (11.67) and neglecting the phase information one obtains

$$U_{\text{out}} = \frac{U_\approx x}{\omega R\varepsilon\varepsilon_0 A} , \tag{11.68}$$

which is linear in the displacement x.

Figure 11.32b shows a capacitive divider. Again the output voltage U_{out} is given by

$$U_{\text{out}} = U_\approx \frac{C_1}{C_2+C_1} = U_\approx \frac{C_1}{\frac{\varepsilon\varepsilon_0 A}{x}+C_1} . \tag{11.69}$$

If there is a stray capacitance C_s then (11.69) is modified as

$$U_{\text{out}} = U_\approx \frac{C_1}{\frac{\varepsilon\varepsilon_0 A}{x}+C_s+C_1} . \tag{11.70}$$

Provided $C_s+C_1 \ll C_2$ one has a system which is linear in x. The driving voltage $U_\approx$ has to be large (more than 100 V) to have the output voltage in the range of 1 V. The linearity of the readout depends on the capacitance C_1 (Fig. 11.33).

Another idea is to keep the distance constant and to change the relative overlap of the plates (see Fig. 11.31, right side). The capacitance of the moving center plate versus the stationary outer plates becomes

$$C = C_s + 2\frac{\varepsilon\varepsilon_0 bx}{s} , \tag{11.71}$$



Fig. 11.33 Linearity of the capacitance readout as a function of the reference capacitor

where the variables are defined in Fig. 11.31. The stray capacitance comprises all effects, including the capacitance of the fringe fields. When the length x is comparable to the width b of the plates one can safely assume that the stray capacitance is constant and independent of x. The main disadvantage of this setup is that it is not as easily incorporated in a microfabricated device as the others.

Sensitivity. The capacitance itself is not a measure of the sensitivity, but its derivative is indicative of the signals one can expect. Using the situation described in Fig. 11.31, upper left, and in (11.64) one obtains for the parallel plate capacitor

$$\frac{\mathrm{d}C}{\mathrm{d}x} = -\frac{\varepsilon\varepsilon_0 A}{x^2} . \tag{11.72}$$

Assuming a plate area A of 20 µm by 40 µm and a separation of 1 µm one obtains a capacitance of 31 fF (neglecting stray capacitance and the capacitance of the connection leads) and a $\mathrm{d}C/\mathrm{d}x$ of $3.1\times10^{-8}\,\mathrm{F/m} = 31\,\mathrm{fF/\mu m}$. Hence it is of paramount importance to maximize the area between the two contacts and to minimize the distance x. The latter however is far from being trivial. One has to go to the limits of microfabrication to achieve a decent sensitivity.

If the capacitance is measured by the circuit shown in Fig. 11.32 one obtains for the sensitivity

$$\frac{\mathrm{d}U_{\text{out}}}{U_{\approx}} = \frac{\mathrm{d}x}{\omega R \varepsilon \varepsilon_0 A} \,. \tag{11.73}$$

Using the same value for A as above, setting the reference frequency to 100 kHz, and selecting $R = 1\,\mathrm{G\Omega}$, we get the relative change of the output voltage U_{out} to

$$\frac{\mathrm{d}U_{\text{out}}}{U_{\approx}} = \frac{22.5 \times 10^{-6}}{\text{Å}} \times \mathrm{d}x \,. \tag{11.74}$$

A driving voltage of 45 V then translates to a sensitivity of 1 mV/Å. A problem in this setup is the stray capacitances. They are in parallel to the original capacitance and decrease the sensitivity considerably.

Alternatively one could build an oscillator with this capacitance and measure the frequency. RC-oscillators typically have an oscillation frequency of

$$f_{\text{res}} \propto \frac{1}{RC} = \frac{x}{R \varepsilon \varepsilon_0 A} \,. \tag{11.75}$$

Again the resistance R must be of the order of $1\,\mathrm{G\Omega}$, when stray capacitances C_{s} are neglected. However C_{s} is of the order of 1 pF. Therefore one gets $R = 10\,\mathrm{M\Omega}$. Using these values the sensitivity becomes

$$\mathrm{d}f_{\text{res}} = \frac{C\,\mathrm{d}x}{R\,(C + C_{\mathrm{s}})^2\, x} \approx \frac{0.1\,\mathrm{Hz}}{\text{Å}}\,\mathrm{d}x \,. \tag{11.76}$$

The bad thing is that the stray capacitances have made the signal nonlinear again. The linearized setup in Fig. 11.31 has a sensitivity of

$$\frac{\mathrm{d}C}{\mathrm{d}x} = 2\frac{\varepsilon \varepsilon_0 b}{s} \,. \tag{11.77}$$

Substituting typical values, $b = 10\,\mu\mathrm{m}$, $s = 1\,\mu\mathrm{m}$ one gets $\mathrm{d}C/\mathrm{d}x = 1.8 \times 10^{-10}\,\mathrm{F/m}$. It is noteworthy that the sensitivity remains constant for scaled devices.

Implementations. The readout of the capacitance can be done in different ways [11.123, 124]. All include an alternating current or voltage with frequencies in the 100 kHz to the 100 MHz range. One possibility is to build a tuned circuit with the capacitance of the cantilever determining the frequency. The resonance frequency of a high quality Q tuned circuit is

$$\omega_0 = (LC)^{-1/2} \,. \tag{11.78}$$

where L is the inductance of the circuit. The capacitance C includes not only the sensor capacitance but also the capacitance of the leads. The precision of a frequency measurement is mainly determined by the ratio of L and C

$$Q = \left(\frac{L}{C}\right)^{1/2} \frac{1}{R} \,. \tag{11.79}$$

Here R symbolizes the losses in the circuit. The higher the quality the more precise the frequency measurement. For instance a frequency of 100 MHz and a capacitance of 1 pF gives an inductance of 250 μH. The quality becomes then 2.5×10^8. This value is an upper limit, since losses are usually too high.

Using a value of $\mathrm{d}C/\mathrm{d}x = 31\,\mathrm{fF}/\mu\mathrm{m}$ one gets $\Delta C/\text{Å} = 3.1\,\mathrm{aF}/\text{Å}$. With a capacitance of 1 pF one gets

$$\frac{\Delta\omega}{\omega} = \frac{1}{2}\frac{\Delta C}{C} \,,$$

$$\Delta\omega = 100\,\mathrm{MHz} \times \frac{1}{2}\frac{3.1\mathrm{aF}}{1\,\mathrm{pF}} = 155\,\mathrm{Hz} \,. \tag{11.80}$$

This is the frequency shift for 1 Å deflection. The calculation shows, that this is a measurable quantity. The quality also indicates that there is no physical reason why this scheme should not work.

11.3.3 Combinations for 3-D-Force Measurements

Three dimensional force measurements are essential if one wants to know all the details of the interaction between the tip and the cantilever. The straightforward attempt to measure three forces is complicated, since force sensors such as interferometers or capacitive sensors need a minimal detection volume, which often is too large. The second problem is that the force-sensing tip has to be held by some means. This implies that one of the three Cartesian axes is stiffer than the others.

However by the combination of different sensors one can achieve this goal. Straight cantilevers are employed for these measurements, because they can be handled analytically. The key observation is, that the optical lever method does not determine the position of the end of the cantilever. It measures the orientation. In the previous sections, one has always made use of the fact, that for a force along one of the orthogonal symmetry directions at the end of the cantilever (normal force, lateral force, force along the cantilever beam axis) there is a one to one correspondence of the tilt angle and the deflection. The problem is, that the force along the cantilever beam axis and the normal force create a deflection in the same direction. Hence what is called the normal force component is actually a mixture of two forces. The deflection of the cantilever is the third quantity, which is not considered in most of the AFMs. A fiber optic interferometer in parallel to the optical lever measures the deflection. Three measured quantities then allow the separation of the three orthonormal force directions, as is evident from (11.27) and (11.33) [11.12–16].

Alternatively one can put the fast scanning direction along the axis of the cantilever. Forward and backward scans then exert opposite forces F_x. If the piezo movement is linearized, both force components in AFM based on the optical lever detection can be determined. In this case, the normal force is simply the average of the forces in the forward and backward direction. The force, F_x, is the difference of the forces measured in forward and backward direction.

11.3.4 Scanning and Control Systems

Almost all SPMs use piezo translators to scan the tip or the sample. Even the first STM [11.1, 103] and some of the predecessor instruments [11.153, 154] used them. Other materials or setups for nano-positioning have been proposed, but were not successful [11.155, 156].

Piezo Tubes

A popular solution is tube scanners (Fig. 11.34). They are now widely used in SPMs due to their simplicity and their small size [11.133, 157]. The outer electrode is segmented in four equal sectors of 90 degrees. Opposite sectors are driven by signals of the same magnitude, but opposite sign. This gives, through bending, a two-dimensional movement on, approximately, a sphere. The inner electrode is normally driven by the z signal. It is possible, however, to use only the outer electrodes for scanning and for the z-movement. The main drawback of applying the z-signal to the outer electrodes is, that the applied voltage is the sum of both the x- or y-movement and the z-movement. Hence a larger scan size effectively reduces the available range for the z-control.



Fig. 11.34 Schematic drawing of a piezoelectric tube scanner. The piezo ceramic is molded into a tube form. The outer electrode is separated into four segments and connected to the scanning voltages. The z-voltage is applied to the inner electrode

Piezo Effect

An electric field applied across a piezoelectric material causes a change in the crystal structure, with expansion in some directions and contraction in others. Also, a net volume change occurs [11.132]. Many SPMs use the transverse piezo electric effect, where the applied electric field $\boldsymbol{E}$ is perpendicular to the expansion/contraction direction.

$$\Delta L = L\,(\boldsymbol{E}\cdot\boldsymbol{n})\,d_{31} = L\frac{V}{t}d_{31}\,, \tag{11.81}$$

where d_{31} is the transverse piezoelectric constant, V is the applied voltage, t is the thickness of the piezo slab or the distance between the electrodes where the voltage is applied, L is the free length of the piezo slab, and $\boldsymbol{n}$ is the direction of polarization. Piezo translators based on the transverse piezoelectric effect have a wide range of sensitivities, limited mainly by mechanical stability and breakdown voltage.

Scan Range

The calculation of the scanning range of a piezotube is difficult [11.157–159]. The bending of the tube depends on the electric fields and the nonuniform strain induced. A finite element calculation where the piezo tube was divided into 218 identical elements was used [11.158] to calculate the deflection. On each node the mechanical stress, stiffness, strain and piezoelectric stress was calculated when a voltage was applied on one electrode. The results were found to be linear on the first iteration and higher-order corrections were very small even for large electrode voltages. It was found that to first order the x- and z-movement of the tube could be reasonably well approximated by assuming that the piezo tube is a segment of a torus. Using this model one obtains

$$\mathrm{d}x = (V_+ - V_-)\,|d_{31}|\,\frac{L^2}{2t\,\mathrm{d}}\,, \tag{11.82}$$

$$\mathrm{d}z = (V_+ + V_- - 2V_z)\,|d_{31}|\,\frac{L}{2t}\,, \tag{11.83}$$

where $|d_{31}|$ is the coefficient of the transversal piezoelectric effect, L is tube's free length, t is tube's wall thickness, d is tube's diameter, V_+ is voltage on positive outer electrode while V_- is voltage of the opposite quadrant negative electrode, and V_z is voltage of the inner electrode.

The cantilever or sample mounted on the piezotube has an additional lateral movement because the point of

Springer Handbook of Nanotechnology
B. Bhushan • © Springer 2004

measurement is not in the end plane of the piezotube. The additional lateral displacement of the end of the tip is $\ell \sin\varphi \approx \ell\varphi$, where ℓ is the tip length and φ is the deflection angle of the end surface. Assuming that the sample or cantilever are always perpendicular to the end of the walls of the tube and calculating with the torus model one gets for the angle

$$\varphi = \frac{L}{R} = \frac{2\,\mathrm{d}x}{L}\,, \tag{11.84}$$

where R is the radius of curvature the piezo tube. Using the result of (11.84) one obtains for the additional x-movement

$$\begin{aligned} \mathrm{d}x_{\mathrm{add}} &= \ell\varphi = \frac{2\,\mathrm{d}x\ell}{L} \\ &= (V_+ - V_-)\,|d_{31}|\,\frac{\ell L}{td} \end{aligned} \tag{11.85}$$

and for the additional z-movement due to the x-movement

$$\begin{aligned} \mathrm{d}z_{\mathrm{add}} &= \ell - \ell\cos\varphi = \frac{\ell\varphi^2}{2} = \frac{2\ell\,(\mathrm{d}x)^2}{L^2} \\ &= (V_+ - V_-)^2\,|d_{31}|^2\,\frac{\ell L^2}{2t^2d^2}\,. \end{aligned} \tag{11.86}$$

Carr [11.158] assumed for his finite element calculations that the top of the tube was completely free to move and, as a consequence, the top surface was distorted, leading to a deflection angle about half that of the geometrical model. Depending on the attachment of the sample or the cantilever this distortion may be smaller, leading to a deflection angle in-between that of the geometrical model and the one of the finite element calculation.

Nonlinearities and Creep

Piezo materials with a high conversion ratio, i. e. a large d_{31} or small electrode separations, with large scanning ranges are hampered by substantial hysteresis resulting in a deviation from linearity by more than 10%. The sensitivity of the piezo ceramic material (mechanical displacement divided by driving voltage) decreases with reduced scanning range, whereas the hysteresis is reduced. A careful selection of the material for the piezo scanners, the design of the scanners, and of the operating conditions is necessary to get optimum performance.

Passive Linearization: Calculation. The analysis of images affected by piezo nonlinearities [11.160–163] shows that the dominant term is

$$x = AV + BV^2\,, \tag{11.87}$$

where x is the excursion of the piezo, V the applied voltage and A and B two coefficients describing the sensitivity of the material. Equation (11.87) holds for scanning from $V = 0$ to large V. For the reverse direction the equation becomes

$$x = \tilde{A}V - \tilde{B}\,(V - V_{\mathrm{max}})^2\,, \tag{11.88}$$

where $\tilde{A}$ and $\tilde{B}$ are the coefficients for the back scan and V_{max} is the applied voltage at the turning point. Both equations demonstrate that the true x-travel is small at the beginning of the scan and becomes larger towards the end. Therefore images are stretched at the beginning and compressed at the end.

Similar equations hold for the slow scan direction. The coefficients, however, are different. The combined action causes a greatly distorted image. This distortion can be calculated. The data acquisition systems record the signal as a function of V. However the data is measured as a function of x. Therefore we have to distribute the x-values evenly across the image this can be done by inverting an approximation of (11.87). First we write

$$x = AV\left(1 - \frac{B}{A}V\right)\,. \tag{11.89}$$

For $B \ll A$ we can approximate

$$V = \frac{x}{A}\,. \tag{11.90}$$

We now substitute (11.90) into the nonlinear term of (11.89). This gives

$$\begin{aligned} x &= AV\left(1 + \frac{Bx}{A^2}\right)\,, \\ V &= \frac{x}{A}\,\frac{1}{(1 + Bx/A^2)} \approx \frac{x}{A}\left(1 - \frac{Bx}{A^2}\right)\,. \end{aligned} \tag{11.91}$$

Hence an equation of the type

$$\begin{aligned} &x_{\mathrm{true}} = x\,(\alpha - \beta x/x_{\mathrm{max}}) \\ &\text{with} \quad 1 = \alpha - \beta \end{aligned} \tag{11.92}$$

takes out the distortion of an image. α and β are dependent on the scan range, the scan speed and on the scan history and have to be determined with exactly the same settings as for the measurement. x_{max} is the maximal scanning range. The condition for α and β guarantees that the image is transformed onto itself.

Similar equations as the empirical one shown above (11.92) can be derived by analyzing the movements of domain walls in piezo ceramics.

Passive Linearization: Measuring the Position. An alternative strategy is to measure the position of the piezo translators. Several possibilities exist.

1. The interferometers described above can be used to measure the elongation of the piezo elongation. The fiber optic interferometer is especially easy to implement. The coherence length of the laser only limits the measurement range. However the signal is of a periodic nature. Hence a direct use of the signal in a feedback circuit for the position is not possible. However as a measurement tool and, especially, as a calibration tool the interferometer is without competition. The wavelength of the light, for instance in a HeNe laser, is so well defined that the precision of the other components determines the error of the calibration or measurement.
2. The movement of the light spot on the quadrant detector can be used to measure the position of a piezo [11.164]. The output current changes by 0.5 A/cm $\times P(\text{W})/R(\text{cm})$. Typical values ($P = 1\,\text{mW}$, $R = 0.001\,\text{cm}$) give 0.5 A/cm. The noise limit is typically $0.15\,\text{nm} \times \sqrt{\Delta f(\text{Hz})/H(\text{W/cm}^2)}$. Again this means that the laser beam above would have a 0.1 nm noise limitation for a bandwidth of 21 Hz. The advantage of this method is that, in principle, one can linearize two axes with only one detector.
3. A knife-edge blocking part of a light beam incident on a photodiode can be used to measure the position of the piezo. This technique, commonly used in optical shear force detection [11.75, 165], has a sensitivity of better than 0.1 nm.
4. The capacitive detection [11.166, 167] of the cantilever deflection can be applied to the measurement of the piezo elongation. Equations (11.64) to (11.79) apply to the problem. This technique is used in some commercial instruments. The difficulties lie in the avoidance of fringe effects at the borders of the two plates. While conceptually simple, one needs the latest technology in surface preparation to get a decent linearity. The electronic circuits used for the readout are often proprietary.
5. Linear Variable Differential Transformers (LVDT) are a convenient means to measure positions down to 1 nm. They can be used together with a solid state joint setup, as often used for large scan range stages. Unlike the capacitive detection there are few difficulties in implementation. The sensors and the detection circuits LVDTs are available commercially.
6. A popular measurement technique is the use of strain gauges. They are especially sensitive when mounted on a solid state joint where the curvature is maximal. The resolution depends mainly on the induced curvature. A precision of 1 nm is attainable. The signals are low – a Wheatstone bridge is needed for the readout.

Active Linearization. Active linearization is done with feedback systems. Sensors need to be monotonic. Hence all the systems described above, with the exception of the interferometers are suitable. The most common solutions include the strain gauge approach, the capacitance measurement or the LVDT, which are all electronic solutions. Optical detection systems have the disadvantage that the intensity enters into the calibration.

Alternative Scanning Systems

The first STMs were based on piezo tripods [11.1]. The piezo tripod (Fig. 11.35) is an intuitive way to generate the three dimensional movement of a tip attached to its center. However, to get a suitable stability and scanning range, the tripod needs to be fairly large (about 50 mm). Some instruments use piezo stacks instead of monolithic piezoactuators. They are arranged in the tripod arrangement. Piezo stacks are thin layers of piezoactive materials glued together to form a device with up to 200 μm of actuation range. Preloading with a suitable metal casing reduces the nonlinearity.

If one tries to construct a homebuilt scanning system, the use of linearized scanning tables is recommended. They are built around solid state joints and actuated by piezo stacks. The joints guarantee that the movement is parallel with little deviation from the predefined scanning plane. Due to the construction it is easy to add measurement devices such as capacitive sensors, LVDTs



Fig. 11.35 An alternative type of piezo scanners: the tripod

or strain gauges which are essential for a closed loop linearization. Two-dimensional tables can be bought from several manufacturers. They have a linearity of better than 0.1% and a noise level of 10^{-4} to 10^{-5} of the maximal scanning range.

Control Systems

Basics. The electronics and software play an important role in the optimal performance of an SPM. Control electronics and software are supplied with commercial SPMs. Control electronic systems can use either analog or digital feedback. While digital feedback offers greater flexibility and the ease of configuration, analog feedback circuits might be better suited for ultralow noise operation. We will describe here the basic setups for AFMs.

Figure 11.36 shows a block schematic of a typical AFM feedback loop. The signal from the force transducer is fed into the feedback loop consisting mainly of a subtraction stage to get an error signal and an integrator. The gain of the integrator (high gain corresponds to short integration times) is set as high as possible without generating more than 1% overshoot. High gain minimizes the error margin of the current and forces the tip to follow the contours of constant density of states as well as possible. This operating mode is known as Constant Force Mode. A high voltage amplifier amplifies the outputs of the integrator. As AFMs using piezotubes usually require ±150 V at the output, the output of the integrator needs to be amplified by a high voltage amplifier.

In order to scan the sample, additional voltages at high tension are required to drive the piezo. For example, with a tube scanner, four scanning voltages are required, namely $+V_x$, $-V_x$, $+V_y$ and $-V_y$. The x- and y-scanning voltages are generated in a scan generator (analog or computer controlled). Both voltages are input to the two respective power amplifiers. Two inverting amplifiers generate the input voltages for the other two power amplifiers. The topography of the sample surface is determined by recording the input-voltage to the high voltage amplifier for the z-channel as a function of x and y (Constant Force Mode).



Fig. 11.36 Block schematic of the feedback control loop of an AFM

Another operating mode is the Variable Force Mode. The gain in the feedback loop is lowered and the scanning speed increased such that the force on the cantilever is no longer constant. Here the force is recorded as a function of x and y.

Force Spectroscopy. Four modes of spectroscopic imaging are in common use with force microscopes: measuring lateral forces, $\partial F/\partial z$, $\partial F/\partial x$ spatially resolved, and measuring force versus distance curves. Lateral forces can be measured by detecting the deflection of a cantilever in a direction orthogonal to the normal direction. The optical lever deflection method most easily does this. Lateral force measurements give indications of adhesion forces between the tip and the sample.

$\partial F/\partial z$ measurements probe the local elasticity of the sample surface. In many cases the measured quantity originates from a volume of a few cubic nanometers. The $\partial F/\partial z$ or local stiffness signal is proportional to Young's modulus, as far as one can define this quantity. Local stiffness is measured by vibrating the cantilever by a small amount in the z-direction. The expected signal for very stiff samples is zero: for very soft samples one gets, independent of the stiffness, also a constant signal. This signal is again zero for the optical lever deflection and equal to the driving amplitude for interferometeric measurements. The best sensitivity is obtained when the compliance of the cantilever matches the stiffness of the sample.

A third spectroscopic quantity is the lateral stiffness. It is measured by applying a small modulation in the x-direction on the cantilever. The signal is again optimal when the lateral compliance of the cantilever matches the lateral stiffness of the sample. The lateral stiffness is, in turn, related to the shear modulus of the sample.

Detailed information on the interaction of the tip and the sample can be gained by measuring force versus distance curves. It is necessary to have cantilevers with high enough compliance to avoid instabilities due to the attractive forces on the sample.

Using the Control Electronics as a Two-Dimensional Measurement Tool. Usually the control electronics of an AFM is used to control the x- and y-piezo signals while several data acquisition channels record the position dependent signals. The control electronics can be used in another way: it can be viewed as a two-dimensional function generator. What is normally the x- and y-signal can be used to control two independent variables of an experiment. The control logic of the AFM then ensures that the available parameter space is systematically probed at equally spaced points. An example is friction force curves measured along a line across a step on graphite.

Figure 11.37 shows the connections. The z-piezo is connected as usual, like the x-piezo. However the y-output is used to command the desired input parameter. The offset of the y-channel determines the position of the tip on the sample surface, together with the x-channel.



Fig. 11.37 Wiring of an AFM to measure friction force curves along a line

Some Imaging Processing Methods

The visualization and interpretation of images from AFMs is intimately connected to the processing of these images. An ideal AFM is a noise-free device that images a sample with perfect tips of known shape and has perfect linear scanning piezos. In reality, AFMs are not that ideal. The scanning device in AFMs is affected by distortions. The distortions are both linear and nonlinear. Linear distortions mainly result from imperfections in the machining of the piezotranslators causing crosstalk from the Z-piezo to the X- and Y-piezos, and vice versa. Among the linear distortions, there are two kinds which are very important. First, scanning piezos invariably have different sensitivities along the different scan axes due to the variation of the piezo material and uneven sizes of the electrode areas. Second, the same reasons might cause the scanning axes not to be orthogonal. Furthermore, the plane in which the piezoscanner moves for constant height z is hardly ever coincident with the sample plane. Hence, a linear ramp is added to the sample data. This ramp is especially bothersome when the height z is displayed as an intensity map.

The nonlinear distortions are harder to deal with. They can affect AFM data for a variety of reasons. First, piezoelectric ceramics do have a hysteresis loop, much like ferromagnetic materials. The deviations of piezoceramic materials from linearity increase with increasing amplitude of the driving voltage. The mechanical position for one voltage depends on the previously applied voltages to the piezo. Hence, to get the best positional accuracy, one should always approach a point on the sample from the same direction. Another type of nonlinear distortion of the images occurs when the scan frequency approaches the upper frequency limit of the X- and Y-drive amplifiers or the upper frequency limit of the feedback loop (z-component). This distortion, due to feedback loop, can only be minimized by reducing the scan frequency. On the other hand, there is a simple way to reduce distortions due to the X- and Y-piezo drive amplifiers. To keep the system as simple as possible, one normally uses a triangular waveform for driving the scanning piezos. However, triangular waves contain frequency components as multiples of the scan frequency. If the cutoff frequency of the X- and Y-drive electronics or of the feedback loop is too close to the scanning frequency (two or three times the scanning frequency), the triangular drive voltage is rounded off at the turning points. This rounding error causes, first, a distortion of the scan linearity and, second, through phase lags, the projection of part of the backward scan onto the forward scan. This type of distortion can be minimized by carefully selecting the scanning frequency and by using driving voltages for the X- and Y-piezos with waveforms like trapezoidal waves, which are closer to a sine wave. The values measured for X, Y, or Z piezos are affected by noise. The origin of this noise can be either electronic, some disturbances, or a property of the sample surface due to adsorbates. In addition to this incoherent noise, interference with main and other equipment nearby might be present. Depending on the type of noise, one can filter it in the real space or in Fourier space. The most important part of image processing is to visualize the measured data. Typical AFM data sets can consist of many thousands to over a million points per plane. There may be more than one image plane present.

The AFM data represents a topography in various data spaces.

Most commercial data acquisition systems use implicitly some kind of data processing. Since the original data is commonly subject to slopes on the surface, most programs use some kind of slope correction. The least disturbing way is to substrate a plane $z(x, y) = Ax + By + C$ from the data. The coefficients are determined by fitting $z(x, y)$ to the data. Another operation is to subtract a second order function such as $z(x, y) = Ax^2 + By^2 + Cxy + Dx + Ey + F$. Again, the parameters are determined with a fit. This function is appropriate for almost planar data, where the nonlinearity of the piezos caused such a distortion.

In the image processing software from Digital Instruments, up to three operations are performed on the raw data. First, a zero-order flatten is applied. The flatten operation is used to eliminate image bow in the slow scan direction (caused by a physical bow in the instrument itself), slope in the slow scan direction, bands in the image (caused by differences in the scan height from one scan line to the next). The flattening operation takes each scan line and subtracts the average value of the height along each scan line from each point in that scan line. This brings each scan line to the same height. Next, a first-order plane-fit is applied in the fast scan direction. The plane-fit operation is used to eliminate bow and slope in the fast scan direction. The plane-fit operation calculated a best-fit plane for the image and subtracts it from the image. This plane has a constant non-zero slope in the fast scan direction. In some cases, a higher-order polynomial "plane" may be required. Depending upon the quality of the raw data, the flattening operation and/or the planefit operation may not be required at all.

References

11.1 G. Binnig, H. Rohrer, Ch. Gerber, E. Weibel: Surface studies by scanning tunneling microscopy, Phys. Rev. Lett. **49** (1982) 57–61

11.2 G. Binnig, C. F. Quate, Ch. Gerber: Atomic force microscope, Phys. Rev. Lett. **56** (1986) 930–933

11.3 G. Binnig, Ch. Gerber, E. Stoll, T. R. Albrecht, C. F. Quate: Atomic resolution with atomic force microscope, Europhys. Lett. **3** (1987) 1281–1286

11.4 B. Bhushan: *Handbook of Micro/Nanotribology*, 2nd edn. (CRC, Boca Raton 1999)

11.5 C. M. Mate, G. M. McClelland, R. Erlandsson, S. Chiang: Atomic-scale friction of a tungsten tip on a graphite surface, Phys. Rev. Lett. **59** (1987) 1942–1945

11.6 R. Erlandsson, G. M. McClelland, C. M. Mate, S. Chiang: Atomic force microscopy using optical interferometry, J. Vac. Sci. Technol. A **6** (1988) 266–270

11.7 O. Marti, J. Colchero, J. Mlynek: Combined scanning force and friction microscopy of mica, Nanotechnol. **1** (1990) 141–144

11.8 G. Meyer, N. M. Amer: Simultaneous measurement of lateral and normal forces with an optical-beam-deflection atomic force microscope, Appl. Phys. Lett. **57** (1990) 2089–2091

11.9 B. Bhushan, J. Ruan: Atomic-scale friction measurements using friction force microscopy: Part II – Application to magnetic media, ASME J. Tribol. **116** (1994) 389–396

11.10 B. Bhushan, V. N. Koinkar, J. Ruan: Microtribology of magnetic media, Proc. Inst. Mech. Eng., Part J: J. Eng. Tribol. **208** (1994) 17–29

11.11 B. Bhushan, J. N. Israelachvili, U. Landman: Nanotribology: Friction, wear, and lubrication at the atomic scale, Nature **374** (1995) 607–616

11.12 S. Fujisawa, M. Ohta, T. Konishi, Y. Sugawara, S. Morita: Difference between the forces measured by an optical lever deflection and by an optical interferometer in an atomic force microscope, Rev. Sci. Instrum. **65** (1994) 644–647

11.13 S. Fujisawa, E. Kishi, Y. Sugawara, S. Morita: Fluctuation in 2-dimensional stick-slip phenomenon observed with 2-dimensional frictional force microscope, Jpn. J. Appl. Phys. **33** (1994) 3752–3755

11.14 S. Grafstrom, J. Ackermann, T. Hagen, R. Neumann, O. Probst: Analysis of lateral force effects on the topography in scanning force microscopy, J. Vac. Sci. Technol. B **12** (1994) 1559–1564

11.15 R. M. Overney, H. Takano, M. Fujihira, W. Paulus, H. Ringsdorf: Anisotropy in friction and molecular stick-slip motion, Phys. Rev. Lett. **72** (1994) 3546–3549

11.16 R. J. Warmack, X. Y. Zheng, T. Thundat, D. P. Allison: Friction effects in the deflection of atomic force microscope cantilevers, Rev. Sci. Instrum. **65** (1994) 394–399

11.17 N. A. Burnham, D. D. Domiguez, R. L. Mowery, R. J. Colton: Probing the surface forces of monolayer films with an atomic force microscope, Phys. Rev. Lett. **64** (1990) 1931–1934

11.18 N. A. Burham, R. J. Colton, H. M. Pollock: Interpretation issues in force microscopy, J. Vac. Sci. Technol. A **9** (1991) 2548–2556

11.19 C. D. Frisbie, L. F. Rozsnyai, A. Noy, M. S. Wrighton, C. M. Lieber: Functional group imaging by chemical force microscopy, Science **265** (1994) 2071–2074

11.20 V. N. Koinkar, B. Bhushan: Microtribological studies of unlubricated and lubricated surfaces using atomic force/friction force microscopy, J. Vac. Sci. Technol. A **14** (1996) 2378–2391

11.21 V. Scherer, B. Bhushan, U. Rabe, W. Arnold: Local elasticity and lubrication measurements using atomic force and friction force microscopy at ultrasonic frequencies, IEEE Trans. Mag. **33** (1997) 4077–4079

11.22 V. Scherer, W. Arnold, B. Bhushan: Lateral force microscopy using acoustic friction force microscopy, Surf. Interface Anal. **27** (1999) 578–587

11.23 B. Bhushan, S. Sundararajan: Micro/Nanoscale friction and wear mechanisms of thin films using atomic force and friction force microscopy, Acta Mater. **46** (1998) 3793–3804

11.24 U. Krotil, T. Stifter, H. Waschipky, K. Weishaupt, S. Hild, O. Marti: Pulse force mode: A new method for the investigation of surface properties, Surf. Interface Anal. **27** (1999) 336–340

11.25 B. Bhushan, C. Dandavate: Thin-film friction and adhesion studies using atomic force microscopy, J. Appl. Phys. **87** (2000) 1201–1210

11.26 B. Bhushan: *Micro/Nanotribology and its Applications* (Kluwer, Dordrecht 1997)

11.27 B. Bhushan: *Principles and Applications of Tribology* (Wiley, New York 1999)

11.28 B. Bhushan: *Modern Tribology Handbook Vol. 1: Principles of Tribology* (CRC, Boca Raton 2001)

11.29 B. Bhushan: *Introduction to Tribology* (Wiley, New York 2002)

11.30 M. Reinstaedtler, U. Rabe, V. Scherer, U. Hartmann, A. Goldade, B. Bhushan, W. Arnold: On the nanoscale measurement of friction using atomic force microscope cantilever torsional resonances, Appl. Phys. Lett. **82** (2003) 2604–2606

11.31 N. A. Burnham, R. J. Colton: Measuring the nanomechanical properties and surface forces of materials using an atomic force microscope, J. Vac. Sci. Technol. A **7** (1989) 2906–2913

11.32 P. Maivald, H. J. Butt, S. A. C. Gould, C. B. Prater, B. Drake, J. A. Gurley, V. B. Elings, P. K. Hansma: Using force modulation to image surface elasticities with the atomic force microscope, Nanotechnol. **2** (1991) 103–106

11.33 B. Bhushan, A. V. Kulkarni, W. Bonin, J. T. Wyrobek: Nano/Picoindentation measurements using capacitive transducer in atomic force microscopy, Philos. Mag. A **74** (1996) 1117–1128

11.34 B. Bhushan, V. N. Koinkar: Nanoindentation hardness measurements using atomic force microscopy, Appl. Phys. Lett. **75** (1994) 5741–5746

11.35 D. DeVecchio, B. Bhushan: Localized surface elasticity measurements using an atomic force microscope, Rev. Sci. Instrum. **68** (1997) 4498–4505

11.36 S. Amelio, A. V. Goldade, U. Rabe, V. Scherer, B. Bhushan, W. Arnold: Measurements of mechanical properties of ultra-thin diamond-like carbon coatings using atomic force acoustic microscopy, Thin Solid Films **392** (2001) 75–84

11.37 D. M. Eigler, E. K. Schweizer: Positioning single atoms with a scanning tunnelling microscope, Nature **344** (1990) 524–528

11.38 A. L. Weisenhorn, J. E. MacDougall, J. A. C. Gould, S. D. Cox, W. S. Wise, J. Massie, P. Maivald, V. B. Elings, G. D. Stucky, P. K. Hansma: Imaging and manipulating of molecules on a zeolite surface with an atomic force microscope, Science **247** (1990) 1330–1333

11.39 I. W. Lyo, Ph. Avouris: Field-induced nanometer-to-atomic-scale manipulation of silicon surfaces with the STM, Science **253** (1991) 173–176

11.40 O. M. Leung, M. C. Goh: Orientation ordering of polymers by atomic force microscope tip-surface interactions, Science **225** (1992) 64–66

11.41 D. W. Abraham, H. J. Mamin, E. Ganz, J. Clark: Surface modification with the scanning tunneling microscope, IBM J. Res. Dev. **30** (1986) 492–499

11.42 R. M. Silver, E. E. Ehrichs, A. L. de Lozanne: Direct writing of submicron metallic features with a scanning tunnelling microscope, Appl. Phys. Lett. **51** (1987) 247–249

11.43 A. Kobayashi, F. Grey, R. S. Williams, M. Ano: Formation of nanometer-scale grooves in silicon with a scanning tunneling microscope, Science **259** (1993) 1724–1726

11.44 B. Parkinson: Layer-by-layer nanometer scale etching of two-dimensional substrates using the scanning tunneling microscopy, J. Am. Chem. Soc. **112** (1990) 7498–7502

11.45 A. Majumdar, P. I. Oden, J. P. Carrejo, L. A. Nagahara, J. J. Graham, J. Alexander: Nanometer-scale lithography using the atomic force microscope, Appl. Phys. Lett. **61** (1992) 2293–2295

11.46 B. Bhushan: Micro/Nanotribology and its applications to magnetic storage devices and MEMS, Tribol. Int. **28** (1995) 85–96

11.47 L. Tsau, D. Wang, K. L. Wang: Nanometer scale patterning of silicon(100) surface by an atomic force microscope operating in air, Appl. Phys. Lett. **64** (1994) 2133–2135

11.48 E. Delawski, B. A. Parkinson: Layer-by-layer etching of two-dimensional metal chalcogenides with the atomic force microscope, J. Am. Chem. Soc. **114** (1992) 1661–1667

11.49 B. Bhushan, G. S. Blackman: Atomic force microscopy of magnetic rigid disks and sliders and its applications to tribology, ASME J. Tribol. **113** (1991) 452–458

11.50 O. Marti, B. Drake, P. K. Hansma: Atomic force microscopy of liquid-covered surfaces: atomic resolution images, Appl. Phys. Lett. **51** (1987) 484–486

11.51 B. Drake, C. B. Prater, A. L. Weisenhorn, S. A. C. Gould, T. R. Albrecht, C. F. Quate, D. S. Cannell, H. G. Hansma, P. K. Hansma: Imaging crystals, polymers and processes in water with the atomic force microscope, Science **243** (1989) 1586–1589

11.52 M. Binggeli, R. Christoph, H. E. Hintermann, J. Colchero, O. Marti: Friction force measurements on potential controlled graphite in an electrolytic environment, Nanotechnol. **4** (1993) 59–63

11.53 G. Meyer, N. M. Amer: Novel optical approach to atomic force microscopy, Appl. Phys. Lett. **53** (1988) 1045–1047

11.54 J. H. Coombs, J. B. Pethica: Properties of vacuum tunneling currents: Anomalous barrier heights, IBM J. Res. Dev. **30** (1986) 455–459

11.55 M. D. Kirk, T. Albrecht, C. F. Quate: Low-temperature atomic force microscopy, Rev. Sci. Instrum. **59** (1988) 833–835

11.56 F. J. Giessibl, Ch. Gerber, G. Binnig: A low-temperature atomic force/scanning tunneling microscope for ultrahigh vacuum, J. Vac. Sci. Technol. B **9** (1991) 984–988

11.57 T. R. Albrecht, P. Grutter, D. Rugar, D. P. E. Smith: Low temperature force microscope with all-fiber interferometer, Ultramicroscopy **42–44** (1992) 1638–1646

11.58 H. J. Hug, A. Moser, Th. Jung, O. Fritz, A. Wadas, I. Parashikor, H. J. Güntherodt: Low temperature magnetic force microscopy, Rev. Sci. Instrum. **64** (1993) 2920–2925

11.59 C. Basire, D. A. Ivanov: Evolution of the lamellar structure during crystallization of a semicrystalline-amorphous polymer blend: Time-resolved hot-stage SPM study, Phys. Rev. Lett. **85** (2000) 5587–5590

11.60 H. Liu, B. Bhushan: Investigation of nanotribological properties of self-assembled monolayers with alkyl and biphenyl spacer chains, Ultramicroscopy **91** (2002) 185–202

11.61 J. Foster, J. Frommer: Imaging of liquid crystal using a tunneling microscope, Nature **333** (1988) 542–547

11.62 D. Smith, H. Horber, C. Gerber, G. Binnig: Smectic liquid crystal monolayers on graphite observed by scanning tunneling microscopy, Science **245** (1989) 43–45

11.63 D. Smith, J. Horber, G. Binnig, H. Nejoh: Structure, registry and imaging mechanism of alkylcyanobiphenyl molecules by tunnelling microscopy, Nature **344** (1990) 641–644

11.64 Y. Andoh, S. Oguchi, R. Kaneko, T. Miyamoto: Evaluation of very thin lubricant films, J. Phys. D **25** (1992) A71–A75

11.65 Y. Martin, C. C. Williams, H. K. Wickramasinghe: Atomic force microscope-force mapping and profiling on a sub 100-A scale, J. Appl. Phys. **61** (1987) 4723–4729

11.66 J. E. Stern, B. D. Terris, H. J. Mamin, D. Rugar: Deposition and imaging of localized charge on insulator surfaces using a force microscope, Appl. Phys. Lett. **53** (1988) 2717–2719

11.67 K. Yamanaka, H. Ogisco, O. Kolosov: Ultrasonic force microscopy for nanometer resolution subsurface imaging, Appl. Phys. Lett. **64** (1994) 178–180

11.68 K. Yamanaka, E. Tomita: Lateral force modulation atomic force microscope for selective imaging of friction forces, Jpn. J. Appl. Phys. **34** (1995) 2879–2882

11.69 U. Rabe, K. Janser, W. Arnold: Vibrations of free and surface-coupled atomic force microscope: Theory and experiment, Rev. Sci. Instrum. **67** (1996) 3281–3293

11.70 Y. Martin, H. K. Wickramasinghe: Magnetic imaging by force microscopy with 1000 Å resolution, Appl. Phys. Lett. **50** (1987) 1455–1457

11.71 D. Rugar, H. J. Mamin, P. Guethner, S. E. Lambert, J. E. Stern, I. McFadyen, T. Yogi: Magnetic force microscopy – General principles and application to longitudinal recording media, J. Appl. Phys. **63** (1990) 1169–1183

11.72 C. Schoenenberger, S. F. Alvarado: Understanding magnetic force microscopy, Z. Phys. B **80** (1990) 373–383

11.73 U. Hartmann: Magnetic force microscopy, Annu. Rev. Mater. Sci. **29** (1999) 53–87

11.74 D. W. Pohl, W. Denk, M. Lanz: Optical stethoscopy-image recording with resolution lambda/20, Appl. Phys. Lett. **44** (1984) 651–653

11.75 E. Betzig, J. K. Troutman, T. D. Harris, J. S. Weiner, R. L. Kostelak: Breaking the diffraction barrier – optical microscopy on a nanometric scale, Science **251** (1991) 1468–1470

11.76 E. Betzig, P. L. Finn, J. S. Weiner: Combined shear force and near-field scanning optical microscopy, Appl. Phys. Lett. **60** (1992) 2484

11.77 P. F. Barbara, D. M. Adams, D. B. O'Connor: Characterization of organic thin film materials with near-field scanning optical microscopy (NSOM), Annu. Rev. Mater. Sci. **29** (1999) 433–469

11.78 C. C. Williams, H. K. Wickramasinghe: Scanning thermal profiler, Appl. Phys. Lett. **49** (1986) 1587–1589

11.79 C. C. Williams, H. K. Wickramasinghe: Microscopy of chemical-potential variations on an atomic scale, Nature **344** (1990) 317–319

11.80 A. Majumdar: Scanning thermal microscopy, Annu. Rev. Mater. Sci. **29** (1999) 505–585

11.81 O. E. Husser, D. H. Craston, A. J. Bard: Scanning electrochemical microscopy – high resolution deposition and etching of materials, J. Electrochem. Soc. **136** (1989) 3222–3229

11.82 Y. Martin, D. W. Abraham, H. K. Wickramasinghe: High-resolution capacitance measurement and potentiometry by force microscopy, Appl. Phys. Lett. **52** (1988) 1103–1105

11.83 M. Nonnenmacher, M. P. O'Boyle, H. K. Wickramasinghe: Kelvin probe force microscopy, Appl. Phys. Lett. **58** (1991) 2921–2923
11.84 J. M. R. Weaver, D. W. Abraham: High resolution atomic force microscopy potentiometry, J. Vac. Sci. Technol. B **9** (1991) 1559–1561
11.85 D. DeVecchio, B. Bhushan: Use of a nanoscale Kelvin probe for detecting wear precursors, Rev. Sci. Instrum. **69** (1998) 3618–3624
11.86 B. Bhushan, A. V. Goldade: Measurements and analysis of surface potential change during wear of single-crystal silicon (100) at ultralow loads using Kelvin probe microscopy, Appl. Surf. Sci. **157** (2000) 373–381
11.87 P. K. Hansma, B. Drake, O. Marti, S. A. C. Gould, C. B. Prater: The scanning ion-conductance microscope, Science **243** (1989) 641–643
11.88 C. B. Prater, P. K. Hansma, M. Tortonese, C. F. Quate: Improved scanning ion-conductance microscope using microfabricated probes, Rev. Sci. Instrum. **62** (1991) 2634–2638
11.89 J. Matey, J. Blanc: Scanning capacitance microscopy, J. Appl. Phys. **57** (1985) 1437–1444
11.90 C. C. Williams: Two-dimensional dopant profiling by scanning capacitance microscopy, Annu. Rev. Mater. Sci. **29** (1999) 471–504
11.91 D. T. Lee, J. P. Pelz, B. Bhushan: Instrumentation for direct, low frequency scanning capacitance microscopy, and analysis of position dependent stray capacitance, Rev. Sci. Instrum. **73** (2002) 3523–3533
11.92 I. Giaever: Energy gap in superconductors measured by electron tunneling, Phys. Rev. Lett. **5** (1960) 147–148
11.93 P. K. Hansma, J. Tersoff: Scanning tunneling microscopy, J. Appl. Phys. **61** (1987) R1–R23
11.94 D. Sarid, V. Elings: Review of scanning force microscopy, J. Vac. Sci. Technol. B **9** (1991) 431–437
11.95 U. Durig, O. Zuger, A. Stalder: Interaction force detection in scanning probe microscopy: Methods and applications, J. Appl. Phys. **72** (1992) 1778–1797
11.96 J. Frommer: Scanning tunneling microscopy and atomic force microscopy in organic chemistry, Angew. Chem. Int. Ed. Engl. **31** (1992) 1298–1328
11.97 H. J. Güntherodt, R. Wiesendanger (Eds.): *Scanning Tunneling Microscopy I: General Principles and Applications to Clean and Adsorbate-Covered Surfaces* (Springer, Berlin, Heidelberg 1992)
11.98 R. Wiesendanger, H. J. Güntherodt (Eds.): *Scanning Tunneling Microscopy, II: Further Applications and Related Scanning Techniques* (Springer, Berlin, Heidelberg 1992)
11.99 D. A. Bonnell (Ed.): *Scanning Tunneling Microscopy and Spectroscopy – Theory, Techniques, and Applications* (VCH, New York 1993)
11.100 O. Marti, M. Amrein (Eds.): *STM and SFM in Biology* (Academic, San Diego 1993)
11.101 J. A. Stroscio, W. J. Kaiser (Eds.): *Scanning Tunneling Microscopy* (Academic, Boston 1993)
11.102 H. J. Güntherodt, D. Anselmetti, E. Meyer (Eds.): *Forces in Scanning Probe Methods* (Kluwer, Dordrecht 1995)
11.103 G. Binnig, H. Rohrer: Scanning tunnelling microscopy, Surf. Sci. **126** (1983) 236–244
11.104 B. Bhushan, J. Ruan, B. K. Gupta: A scanning tunnelling microscopy study of fullerene films, J. Phys. D **26** (1993) 1319–1322
11.105 R. L. Nicolaides, W. E. Yong, W. F. Packard, H. A. Zhou: Scanning tunneling microscope tip structures, J. Vac. Sci. Technol. A **6** (1988) 445–447
11.106 J. P. Ibe, P. P. Bey, S. L. Brandon, R. A. Brizzolara, N. A. Burnham, D. P. DiLella, K. P. Lee, C. R. K. Marrian, R. J. Colton: On the electrochemical etching of tips for scanning tunneling microscopy, J. Vac. Sci. Technol. A **8** (1990) 3570–3575
11.107 R. Kaneko, S. Oguchi: Ion-implanted diamond tip for a scanning tunneling microscope, Jpn. J. Appl. Phys. **28** (1990) 1854–1855
11.108 F. J. Giessibl: Atomic resolution of the silicon(111)-(7×7) surface by atomic force microscopy, Science **267** (1995) 68–71
11.109 B. Anczykowski, D. Krueger, K. L. Babcock, H. Fuchs: Basic properties of dynamic force spectroscopy with the scanning force microscope in experiment and simulation, Ultramicroscopy **66** (1996) 251–259
11.110 T. R. Albrecht and C. F. Quate: Atomic resolution imaging of a nonconductor by atomic force microscopy, J. Appl. Phys. **62** (1987) 2599–2602
11.111 S. Alexander, L. Hellemans, O. Marti, J. Schneir, V. Elings, P. K. Hansma: An atomic-resolution atomic-force microscope implemented using an optical lever, J. Appl. Phys. **65** (1989) 164–167
11.112 G. Meyer, N. M. Amer: Optical-beam-deflection atomic force microscopy: The NaCl(001) surface, Appl. Phys. Lett. **56** (1990) 2100–2101
11.113 A. L. Weisenhorn, M. Egger, F. Ohnesorge, S. A. C. Gould, S. P. Heyn, H. G. Hansma, R. L. Sinsheimer, H. E. Gaub, P. K. Hansma: Molecular resolution images of Langmuir–Blodgett films and DNA by atomic force microscopy, Langmuir **7** (1991) 8–12
11.114 J. Ruan, B. Bhushan: Atomic-scale and microscale friction of graphite and diamond using friction force microscopy, J. Appl. Phys. **76** (1994) 5022–5035
11.115 D. Rugar, P. K. Hansma: Atomic force microscopy, Phys. Today **43** (1990) 23–30
11.116 D. Sarid: *Scanning Force Microscopy* (Oxford Univ. Press, Oxford 1991)
11.117 G. Binnig: Force microscopy, Ultramicroscopy **42–44** (1992) 7–15
11.118 E. Meyer: Atomic force microscopy, Surf. Sci. **41** (1992) 3–49
11.119 H. K. Wickramasinghe: Progress in scanning probe microscopy, Acta Mater. **48** (2000) 347–358

11.120 A.J. den Boef: The influence of lateral forces in scanning force microscopy, Rev. Sci. Instrum. **62** (1991) 88–92

11.121 M. Radmacher, R.W. Tillman, M. Fritz, H.E. Gaub: From molecules to cells: Imaging soft samples with the atomic force microscope, Science **257** (1992) 1900–1905

11.122 F. Ohnesorge, G. Binnig: True atomic resolution by atomic force microscopy through repulsive and attractive forces, Science **260** (1993) 1451–1456

11.123 G. Neubauer, S.R. Coben, G.M. McClelland, D. Horne, C.M. Mate: Force microscopy with a bidirectional capacitance sensor, Rev. Sci. Instrum. **61** (1990) 2296–2308

11.124 T. Goddenhenrich, H. Lemke, U. Hartmann, C. Heiden: Force microscope with capacitive displacement detection, J. Vac. Sci. Technol. A **8** (1990) 383–387

11.125 U. Stahl, C.W. Yuan, A.L. Delozanne, M. Tortonese: Atomic force microscope using piezoresistive cantilevers and combined with a scanning electron microscope, Appl. Phys. Lett. **65** (1994) 2878–2880

11.126 R. Kassing, E. Oesterschulze: Sensors for scanning probe microscopy. In: *Micro/Nanotribology and Its Applications*, ed. by B. Bhushan (Kluwer, Dordrecht 1997) pp. 35–54

11.127 C.M. Mate: Atomic-force-microscope study of polymer lubricants on silicon surfaces, Phys. Rev. Lett. **68** (1992) 3323–3326

11.128 S.P. Jarvis, A. Oral, T.P. Weihs, J.B. Pethica: A novel force microscope and point contact probe, Rev. Sci. Instrum. **64** (1993) 3515–3520

11.129 D. Rugar, H.J. Mamin, P. Guethner: Improved fiber-optical interferometer for atomic force microscopy, Appl. Phys. Lett. **55** (1989) 2588–2590

11.130 C. Schoenenberger, S.F. Alvarado: A differential interferometer for force microscopy, Rev. Sci. Instrum. **60** (1989) 3131–3135

11.131 D. Sarid, D. Iams, V. Weissenberger, L.S. Bell: Compact scanning-force microscope using laser diode, Opt. Lett. **13** (1988) 1057–1059

11.132 N.W. Ashcroft, N.D. Mermin: *Solid State Physics* (Holt Reinhart and Winston, New York 1976)

11.133 G. Binnig, D.P.E. Smith: Single-tube three-dimensional scanner for scanning tunneling microscopy, Rev. Sci. Instrum. **57** (1986) 1688

11.134 S.I. Park, C.F. Quate: Digital filtering of STM images, J. Appl. Phys. **62** (1987) 312

11.135 J.W. Cooley, J.W. Tukey: An algorithm for machine calculation of complex fourier series, Math. Computation **19** (1965) 297

11.136 J. Ruan, B. Bhushan: Atomic-scale friction measurements using friction force microscopy: Part I – General principles and new measurement techniques, ASME J. Tribol. **116** (1994) 378–388

11.137 T.R. Albrecht, S. Akamine, T.E. Carver, C.F. Quate: Microfabrication of cantilever styli for the atomic force microscope, J. Vac. Sci. Technol. A **8** (1990) 3386–3396

11.138 O. Marti, S. Gould, P.K. Hansma: Control electronics for atomic force microscopy, Rev. Sci. Instrum. **59** (1988) 836–839

11.139 O. Wolter, T. Bayer, J. Greschner: Micromachined silicon sensors for scanning force microscopy, J. Vac. Sci. Technol. B **9** (1991) 1353–1357

11.140 E. Meyer, R. Overney, R. Luthi, D. Brodbeck: Friction force microscopy of mixed Langmuir–Blodgett films, Thin Solid Films **220** (1992) 132–137

11.141 H.J. Dai, J.H. Hafner, A.G. Rinzler, D.T. Colbert, R.E. Smalley: Nanotubes as nanoprobes in scanning probe microscopy, Nature **384** (1996) 147–150

11.142 J.H. Hafner, C.L. Cheung, A.T. Woolley, C.M. Lieber: Structural and functional imaging with carbon nanotube AFM probes, Prog. Biophys. Mol. Biol. **77** (2001) 73–110

11.143 G.S. Blackman, C.M. Mate, M.R. Philpott: Interaction forces of a sharp tungsten tip with molecular films on silicon surface, Phys. Rev. Lett. **65** (1990) 2270–2273

11.144 S.J. O'Shea, M.E. Welland, T. Rayment: Atomic force microscope study of boundary layer lubrication, Appl. Phys. Lett. **61** (1992) 2240–2242

11.145 J.P. Cleveland, S. Manne, D. Bocek, P.K. Hansma: A nondestructive method for determining the spring constant of cantilevers for scanning force microscopy, Rev. Sci. Instrum. **64** (1993) 403–405

11.146 D.W. Pohl: Some design criteria in STM, IBM J. Res. Dev. **30** (1986) 417

11.147 W.T. Thomson, M.D. Dahleh: *Theory of Vibration with Applications*, 5th edn. (Prentice Hall, Upper Saddle River 1998)

11.148 J. Colchero: Reibungskraftmikroskopie. Ph.D. Thesis (University of Konstanz, Konstanz 1993)

11.149 G.M. McClelland, R. Erlandsson, S. Chiang: Atomic force microscopy: General principles and a new implementation. In: *Review of Progress in Quantitative Nondestructive Evaluation*, Vol. 6B, ed. by D.O. Thompson, D.E. Chimenti (Plenum, New York 1987) pp. 1307–1314

11.150 Y.R. Shen: *The Principles of Nonlinear Optics* (Wiley, New York 1984)

11.151 T. Baumeister, S.L. Marks: *Standard Handbook for Mechanical Engineers*, 7th edn. (McGraw-Hill, New York 1967)

11.152 J. Colchero, O. Marti, H. Bielefeldt, J. Mlynek: Scanning force and friction microscopy, Phys. Stat. Sol. **131** (1991) 73–75

11.153 R. Young, J. Ward, F. Scire: Observation of metal-vacuum-metal tunneling, field emission, and the transition region, Phys. Rev. Lett. **27** (1971) 922

11.154 R. Young, J. Ward, F. Scire: The topographiner: An instrument for measuring surface microtopography, Rev. Sci. Instrum. **43** (1972) 999

11.155 C. Gerber, O. Marti: Magnetostrictive positioner, IBM Tech. Disclosure Bull. **27** (1985) 6373

11.156 R. Garcìa Cantù, M. A. Huerta Garnica: Long-scan imaging by STM, J. Vac. Sci. Technol. A **8** (1990) 354

11.157 C. J. Chen: In situ testing and calibration of tube piezoelectric scanners, Ultramicroscopy **42–44** (1992) 1653–1658

11.158 R. G. Carr: J. Microscopy **152** (1988) 379

11.159 C. J. Chen: Electromechanical deflections of piezoelectric tubes with quartered electrodes, Appl. Phys. Lett. **60** (1992) 132

11.160 N. Libioulle, A. Ronda, M. Taborelli, J. M. Gilles: Deformations and nonlinearity in scanning tunneling microscope images, J. Vac. Sci. Technol. B **9** (1991) 655–658

11.161 E. P. Stoll: Restoration of STM images distorted by time-dependent piezo driver aftereffects, Ultramicroscopy **42–44** (1991) 1585–1589

11.162 R. Durselen, U. Grunewald, W. Preuss: Calibration and applications of a high precision piezo scanner for nanometrology, Scanning **17** (1995) 91–96

11.163 J. Fu: In situ testing and calibrating of Z-piezo of an atomic force microscope, Rev. Sci. Instrum. **66** (1995) 3785–3788

11.164 R. C. Barrett, C. F. Quate: Optical scan-correction system applied to atomic force microscopy, Rev. Sci. Instrum. **62** (1991) 1393

11.165 R. Toledo-Crow, P. C. Yang, Y. Chen, M. Vaez-Iravani: Near-field differential scanning optical microscope with atomic force regulation, Appl. Phys. Lett. **60** (1992) 2957–2959

11.166 J. E. Griffith, G. L. Miller, C. A. Green: A scanning tunneling microscope with a capacitance-based position monitor, J. Vac. Sci. Technol. B **8** (1990) 2023–2027

11.167 A. E. Holman, C. D. Laman, P. M. L. O. Scholte, W. C. Heerens, F. Tuinstra: A calibrated scanning tunneling microscope equipped with capacitive sensors, Rev. Sci. Instrum. **67** (1996) 2274–2280

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Probes in Sca

12. Probes in Scanning Microscopies

Scanning probe microscopy (SPM) provides nanometer-scale mapping of numerous sample properties in essentially any environment. This unique combination of high resolution and broad applicability has lead to the application of SPM to many areas of science and technology, especially those interested in the structure and properties of materials at the nanometer scale. SPM images are generated through measurements of a tip-sample interaction. A well-characterized tip is the key element to data interpretation and is typically the limiting factor.

Commercially available atomic force microscopy (AFM) tips, integrated with force sensing cantilevers, are microfabricated from silicon and silicon nitride by lithographic and anisotropic etching techniques. The performance of these tips can be characterized by imaging nanometer-scale standards of known dimension, and the resolution is found to roughly correspond to the tip radius of curvature, the tip aspect ratio, and the sample height. Although silicon and silicon nitride tips have a somewhat large radius of curvature, low aspect ratio, and limited lifetime due to wear, the widespread use of AFM today is due in large part to the broad availability of these tips. In some special cases, small asperities on the tip can provide resolution much higher than the tip radius of curvature for low-Z samples such as crystal surfaces and ordered protein arrays.

Several strategies have been developed to improve AFM tip performance. Oxide sharpening improves tip sharpness and enhances tip asperities. For high-aspect-ratio samples such as integrated circuits, silicon AFM tips can be modified by focused ion beam (FIB) milling. FIB tips reach three-degree cone angles over lengths of several microns and can be fabricated at arbitrary angles. Other high resolution and high-aspect-ratio tips are produced by electron beam deposition (EBD) in which a carbon spike is deposited onto the tip apex from the background gases in an electron microscope. Finally, carbon nanotubes have been employed as AFM tips. Their nanometer-scale diameter, long length, high stiffness, and elastic buckling properties make carbon nanotubes possibly the ultimate tip material for AFM. Nanotubes can be manually attached to silicon or silicon nitride AFM tips or "grown" onto tips by chemical vapor deposition (CVD), which should soon make them widely available. In scanning tunneling microscopy (STM), the electron tunneling signal decays exponentially with tip-sample separation, so that in principle only the last few atoms contribute to the signal. STM tips are, therefore, not as sensitive to the nanoscale tip geometry and can be made by simple mechanical cutting or electrochemical etching of metal wires. In choosing tip materials, one prefers hard, stiff metals that will not oxidize or corrode in the imaging environment.

12.1 **Atomic Force Microscopy** 372
  12.1.1 Principles of Operation 372
  12.1.2 Standard Probe Tips...................... 373
  12.1.3 Probe Tip Performance 374
  12.1.4 Oxide-Sharpened Tips.................. 375
  12.1.5 FIB tips 376
  12.1.6 EBD tips 376
  12.1.7 Carbon Nanotube Tips.................. 376

12.2 **Scanning Tunneling Microscopy** 382
  12.2.1 Mechanically Cut STM Tips............. 382
  12.2.2 Electrochemically Etched STM Tips 383

References 383

In scanning probe microscopy (SPM), an image is created by raster scanning a sharp probe tip over a sample and measuring some highly localized tip-sample interaction as a function of position. SPMs are based on several interactions, the major types including scanning tunneling microscopy (STM), which measures an electronic tunneling current; atomic force microscopy (AFM), which measures force interactions; and near-field scan-

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

ning optical microscopy (NSOM), which measures local optical properties by exploiting near-field effects (Fig. 12.1). These methods allow the characterization of many properties (structural, mechanical, electronic, optical) on essentially any material (metals, semiconductors, insulators, biomolecules) and in essentially any environment (vacuum, liquid, or ambient air conditions). The unique combination of nanoscale resolution, previously the domain of electron microscopy, *and broad applicability* has led to the proliferation of SPM into virtually all areas of nanometer-scale science and technology.

Several enabling technologies have been developed for SPM, or borrowed from other techniques. Piezoelectric tube scanners allow accurate, sub-angstrom positioning of the tip or sample in three dimensions. Optical deflection systems and microfabricated cantilevers can detect forces in AFM down to the picoNewton range. Sensitive electronics can measure STM currents less than 1 picoamp. High transmission fiber optics and sensitive photodetectors can manipulate and detect small optical signals of NSOM. Environmental control has been developed to allow SPM imaging in UHV, cryogenic temperatures, at elevated temperatures, and in fluids. Vibration and drift have been controlled such that a probe tip can be held over a single molecule for hours of observation. Microfabrication techniques have been developed for the mass production of probe tips, making SPMs commercially available and allowing the development of many new SPM modes and combinations with other characterization methods. However, of all this SPM development over the past 20 years, what has received the least attention is perhaps the most important aspect: the probe tip.



Fig. 12.1 A schematic of the components of a scanning probe microscope and the three types of signals observed: STM senses electron tunneling currents, AFM measures forces, and NSOM measures near-field optical properties via a sub-wavelength aperture

Interactions measured in SPMs occur at the tip-sample interface, which can range in size from a single atom to tens of nanometers. The size, shape, surface chemistry, electronic and mechanical properties of the tip apex will directly influence the data signal and the interpretation of the image. Clearly, the better characterized the tip the more useful the image information. In this chapter, the fabrication and performance of AFM and STM probes will be described.

12.1 Atomic Force Microscopy

AFM is the most widely used form of SPM, since it requires neither an electrically conductive sample, as in STM, nor an optically transparent sample or substrate, as in most NSOMs. Basic AFM modes measure the topography of a sample with the only requirement being that the sample is deposited on a flat surface and rigid enough to withstand imaging. Since AFM can measure a variety of forces, including van der Waals forces, electrostatic forces, magnetic forces, adhesion forces and friction forces, specialized modes of AFM can characterize the electrical, mechanical, and chemical properties of a sample in addition to its topography.

12.1.1 Principles of Operation

In AFM, a probe tip is integrated with a microfabricated force-sensing cantilever. A variety of silicon and silicon nitride cantilevers are commercially available with micron-scale dimensions, spring constants ranging from 0.01 to 100 N/m, and resonant frequencies ranging from 5 kHz to over 300 kHz. The cantilever deflection is detected by optical beam deflection, as illustrated in Fig. 12.2. A laser beam bounces off the back of the cantilever and is centered on a split photodiode. Cantilever deflections areproportional to the difference signal $V_A - V_B$. Sub-angstrom deflections can be deflected and, therefore, forces down to tens of picoNewtons can be measured. A more recently developed method of cantilever deflection measurement is through a piezoelectric layer on the cantilever that registers a voltage upon deflection [12.1].

A piezoelectric scanner rasters the sample under the tip while the forces are measured through deflections of the cantilever. To achieve more controlled imaging con-



Fig. 12.2 An illustration of the optical beam deflection system that detects cantilever motion in the AFM. The voltage signal $V_A - V_B$ is proportional to the deflection

ditions, a feedback loop monitors the tip-sample force and adjusts the sample Z-position to hold the force constant. The topographic image of the sample is then taken from the sample Z-position data. The mode described is called contact mode, in which the tip is deflected by the sample due to repulsive forces, or "contact". It is generally only used for flat samples that can withstand lateral forces during scanning. To minimize lateral forces and sample damage, two AC modes have been developed. In these, the cantilever is driven into AC oscillation near its resonant frequency (tens to hundreds of kHz) with amplitudes of 5 to tens of s. When the tip approaches the sample, the oscillation is damped, and the reduced amplitude is the feedback signal, rather than the DC deflection. Again, topography is taken from the varying Z-position of the sample required to keep the tip oscillation amplitude constant. The two AC modes differ only in the nature of the interaction. In intermittent contact mode, also called tapping mode, the tip contacts the sample on each cycle, so the amplitude is reduced by ionic repulsion as in contact mode. In non-contact mode, long-range van der Waals forces reduce the amplitude by effectively shifting the spring constant experienced by the tip and changing its resonant frequency.

12.1.2 Standard Probe Tips

In early AFM work, cantilevers were made by hand from thin metal foils or small metal wires. Tips were created by gluing diamond fragments to the foil cantilevers or electrochemically etching the wires to a sharp point. Since these methods were labor intensive and not highly reproducible, they were not amenable to large-scale production. To address this problem, and the need for smaller cantilevers with higher resonant frequencies, batch fabrication techniques were developed (see Fig. 12.3). Building on existing methods to batch fabricate Si_3N_4 cantilevers, *Albrecht* et al. [12.2] etched an array of small square openings in an SiO_2 mask layer over a (100) silicon surface. The exposed square (100) regions were etched with KOH, an anisotropic etchant that terminates at the (111) planes, thus creating pyramidal etch pits in the silicon surface. The etch pit mask was then removed and another was applied to define the cantilever shapes with the pyramidal etch pits at the end. The Si wafer was then coated with a low stress Si_3N_4 layer by LPCVD. The Si_3N_4 fills the etch pit, using it as a mold to create a pyramidal tip. The silicon was later removed by etching to free the cantilevers and tips. Further steps resulting in the attachment of the cantilever to a macroscopic piece of glass are not described here. The resulting pyramidal tips were highly symmetric and had a tip radius of less than 30 nm, as determined by scanning electron microscopy (SEM). This procedure has likely not changed significantly, since commercially available Si_3N_4 tips are still specified to have a curvature radius of 30 nm.

Wolter et al. [12.3] developed methods to batch fabricate single-crystal Si cantilevers with integrated tips. Microfabricated Si cantilevers were first prepared using previously described methods, and a small mask was formed at the end of the cantilever. The Si around the mask was etched by KOH, so that the mask was under cut. This resulted in a pyramidal silicon tip under the mask, which was then removed. Again, this partial description of the full procedure only describes tip fabrication. With some refinements the silicon tips were made



Fig. 12.3 A schematic overview of the fabrication of Si and Si_3N_4 tip fabrication as described in the text

in high yield with curvature radii of less than 10 nm. Si tips are sharper than Si_3N_4 tips, because they are directly formed by the anisotropic etch in single-crystal Si, rather than using an etch pit as a mask for deposited material. Commercially available silicon probes are made by similar refined techniques and provide a curvature typical radius of < 10 nm.

12.1.3 Probe Tip Performance

In atomic force microscopy the question of resolution can be a rather complicated issue. As an initial approximation, resolution is often considered strictly in geometrical terms that assume rigid tip-sample contact. The topographical image of a feature is broadened or narrowed by the size of the probe tip, so the resolution is approximately the width of the tip. Therefore, the resolution of AFM with standard commercially available tips is on the order of 5 to 10 nm. *Bustamante* and *Keller* [12.4] carried the geometrical model further by drawing an analogy to resolution in optical systems. Consider two sharp spikes separated by a distance d to be point objects imaged by AFM (see Fig. 12.4). Assume the tip has a parabolic shape with an end radius R. The tip-broadened image of these spikes will appear as inverted parabolas. There will be a small depression between the images of depth Δz. The two spikes are considered "resolved" if Δz is larger than the instrumental noise in the z direction. Defined in this manner, the resolution d, the minimum separation at which the spikes are resolved, is

$$d = 2\sqrt{2R\,(\Delta z)}\,, \qquad (12.1)$$

where one must enter a minimal detectable depression for the instrument (Δz) to determine the resolution. So for a silicon tip with radius 5 nm and a minimum detectable Δz of 0.5 nm, the resolution is about 4.5 nm. However, the above model assumes the spikes are of equal height. *Bustamante* and *Keller* [12.4] went on to point out that if the height of the spikes is not equal, the resolution will be affected. Assuming a height difference of Δh, the resolution becomes:

$$d = \sqrt{2R}\left(\sqrt{\Delta z} + \sqrt{\Delta z + \Delta h}\right)\,. \qquad (12.2)$$

For a pair of spikes with a 2 nm height difference, the resolution drops to 7.2 nm for a 5 nm tip and 0.5 nm minimum detectable Δz. While geometrical considerations are a good starting point for defining resolution, they ignore factors such as the possible compression and deformation of the tip and sample. *Vesenka* et al. [12.5] confirmed a similar geometrical resolution model by imaging monodisperse gold nanoparticles with tips characterized by transmission electron microscopy (TEM).



Fig. 12.4 The factors that determine AFM imaging resolution in contact mode (*top*) and noncontact mode (*bottom*), adapted from [12.4]

Noncontact AFM contrast is generated by long-range interactions such as van der Waals forces, so resolution will not simply be determined by geometry because the tip and sample are not in rigid contact. *Bustamante* and *Keller* [12.4] have derived an expression for the resolution in noncontact AFM for an idealized, infinitely thin "line" tip and a point particle as the sample (Fig. 12.4). Noncontact AFM is sensitive to the gradient of long-range forces, so the van der Waals force gradient was calculated as a function of position for the tip at height h above the surface. If the resolution d is defined as the full width at half maximum of this curve, the resolution is:

$$d = 0.8h\,. \tag{12.3}$$

This shows that even for an ideal geometry, the resolution is fundamentally limited in noncontact mode by the tip-sample separation. Under UHV conditions, the tip-sample separation can be made very small, so atomic resolution is possible on flat, crystalline surfaces. Under ambient conditions, however, the separation must be larger to keep the tip from being trapped in the ambient water layer on the surface. This larger separation can lead to a point where further improvements in tip sharpness do not improve resolution. It has been found that imaging 5 nm gold nanoparticles in noncontact mode with carbon nanotube tips of 2 nm diameter leads to particle widths of 12 nm, larger than the 7 nm width one would expect assuming rigid contact [12.8]. However, in tapping mode operation, the geometrical definition of resolution is relevant, since the tip and sample come into rigid contact. When imaging 5 nm gold particles with 2 nm carbon nanotube tips in tapping mode, the expected 7 nm particle width is obtained [12.9].

The above descriptions of AFM resolution cannot explain the sub-nanometer resolution achieved on crystal surfaces [12.10] and ordered arrays of biomolecules [12.11] in contact mode with commercially available probe tips. Such tips have nominal radii of curvature ranging from 5 nm to 30 nm, an order of magnitude larger than the resolution achieved. A detailed model to explain the high resolution on ordered membrane proteins has been put forth by [12.6]. In this model, the larger part of the silicon nitride tip apex balances the tip-sample interaction through electrostatic forces, while a very small tip asperity interacts with the sample to provide contrast (see Fig. 12.5). This model is supported by measurements at varying salt concentrations to vary the electrostatic interaction strength and the observation of defects in the ordered samples. However, the existence of such asperities has never been confirmed by independent electron microscopy images of the tip. Another model, considered especially applicable to atomic resolution on crystal surfaces, assumes the tip is in contact with a region of the sample much larger than the resolution observed, and that force components matching the periodicity of the sample are transmitted to the tip, resulting in an "averaged" image of the periodic lattice. Regardless of the mechanism, the structures determined are accurate and make this a highly valuable method for membrane proteins. However, this level of resolution should not be expected for most biological systems.



Fig. 12.5 A tip model to explain the high resolution obtained on ordered samples in contact mode, from [12.6]

12.1.4 Oxide-Sharpened Tips

Both Si and Si_3N_4 tips with increased aspect ratio and reduced tip radius can be fabricated through oxide sharpening of the tip. If a pyramidal or cone-shaped silicon tip is thermally oxidized to SiO_2 at low temperature ($< 1{,}050\,°C$), Si-SiO_2 stress formation reduces the oxidation rate at regions of high curvature. The result is a sharper, higher-aspect-ratio cone of silicon at the high curvature tip apex inside the outer pyramidal layer of SiO_2 (see Fig. 12.6). Etching the SiO_2 layer with HF then leaves tips with aspect ratios up to 10:1 and radii down to 1 nm [12.7], although 5–10 nm is the nominal specification for most commercially available tips. This oxide sharpening technique can also be applied to Si_3N_4 tips by oxidizing the silicon etch pits that are used as molds. As with tip fabrication, oxide sharpening is not quite as effective for Si_3N_4. Si_3N_4 tips were reported to have an



Fig. 12.6 Oxide sharpening of silicon tips. The *left image* shows a sharpened core of silicon in an outer layer of SiO_2. The *right image* is a higher magnification view of such a tip after the SiO_2 is removed. Adapted from [12.7]

11 nm radius of curvature [12.12], while commercially available oxide-sharpened Si_3N_4 tips have a nominal radius of < 20 nm.

12.1.5 FIB tips

A common AFM application in integrated circuit manufacture and MEMs is to image structures with very steep sidewalls such as trenches. To accurately image these features, one must consider the micron-scale tip structure, rather than the nanometer-scale structure of the tip apex. Since tip fabrication processes rely on anisotropic etchants, the cone half-angles of pyramidal tips are approximately 20 degrees. Images of deep trenches taken with such tips display slanted sidewalls and may not reach the bottom of the trench due to the tip broadening effects. To image such samples more faithfully, high-aspect-ratio tips are fabricated by focused ion beam (FIB) machining a Si tip to produce a sharp spike at the tip apex. Commercially available FIB tips have half cone angles of < 3 degrees over lengths of several microns, yielding aspect ratios of approximately 10:1. The radius of curvature at the tip end is similar to that of the tip before the FIB machining. Another consideration for high-aspect-ratio tips is the tip tilt. To ensure that the pyramidal tip is the lowest part of the tip-cantilever assembly, most AFM designs tilt the cantilever about 15 degrees from parallel. Therefore, even an ideal "line tip" will not give an accurate image of high steep sidewalls, but will produce an image that depends on the scan angle. Due to the versatility of the FIB machining, tips are available with the spikes at an angle to compensate for this effect.

12.1.6 EBD tips

Another method of producing high-aspect-ratio tips for AFM is called electron beam deposition (EBD). First developed for STM tips [12.13, 14], EBD tips were introduced for AFM by focusing an SEM onto the apex of a pyramidal tip arranged so that it pointed along the electron beam axis (see Fig. 12.7). Carbon material was deposited by the dissociation of background gases in the SEM vacuum chamber. *Schiffmann* [12.15] systematically studied the following parameters and how they affected EBD tip geometry:

Deposition time :	0.5 to 8 min
Beam current :	3–300 pA
Beam energy :	1–30 keV
Working distance :	8–48 mm .



Fig. 12.7 A pyramidal tip before (*left*, 2-µm-scale bar) and after (*right*, 1-µm-scale bar) electron beam deposition, adapted from [12.13]

EBD tips were cylindrical with end radii of 20–40 nm, lengths of 1 to 5 µm, and diameters of 100 to 200 nm. Like FIB tips, EBD tips were found to achieve improved imaging of steep features. By controlling the position of the focused beam, the tip geometry can be further controlled. Tips were fabricated with lengths over 5 µm and aspect ratios greater than 100:1, yet these were too fragile to use as a tip in AFM [12.13].

12.1.7 Carbon Nanotube Tips

Carbon nanotubes are microscopic graphitic cylinders that are nanometers in diameter, yet many microns in length. Single-walled carbon nanotubes (SWNT) consist of single sp^2 hybridized carbon sheets rolled into seamless tubes and have diameters ranging from 0.7 to 3 nm.

Carbon Nanotube Structure

Larger structures called multiwalled carbon nanotubes (MWNT) consist of nested, concentrically arranged SWNT and have diameters ranging from 3 to 50 nm. Figure 12.8 shows a model of nanotube structure, as well as TEM images of a SWNT and a MWNT. The small diameter and high aspect ratio of carbon nanotubes suggests their application as high resolution, high-aspect-ratio AFM probes.

Carbon Nanotube Mechanical Properties

Carbon nanotubes possess exceptional mechanical properties that impact their use as probes. Their lateral stiffness can be approximated from that of a solid elastic rod:

$$k_{\text{lat}} = \frac{3\pi Y r^4}{4 l^3} , \qquad (12.4)$$



Fig. 12.8 The structure of carbon nanotubes, including TEM images of a MWNT (*left*) and a SWNT (*right*), from [12.16]

where the spring constant k_{lat} represents the restoring force per unit lateral displacement, r is the radius, l is the length, and Y is the Young's modulus (also called the elastic modulus) of the material. For the small diameters and extreme aspect ratios of carbon nanotube tips, the thermal vibrations of the probe tip at room temperature can become sufficient to degrade image resolution. These thermal vibrations can be approximated by equating $\frac{1}{2}k_{\mathrm{B}}T$ of thermal energy to the energy of an oscillating nanotube:

$$\frac{1}{2}k_{\mathrm{B}}T = \frac{1}{2}k_{\mathrm{lat}}a^2 \,, \tag{12.5}$$

where k_{B} is Boltzmann's constant, T is the temperature, and a is the vibration amplitude. Substituting for k_{lat} from (12.4) yields:

$$a = \sqrt{\frac{4k_{\mathrm{B}}Tl^3}{3\pi Yr^4}} \,. \tag{12.6}$$

The strong dependence on radius and length reveals that one must carefully control the tip geometry at this size scale. Equation (12.6) implies that the stiffer the material, i. e., the higher its Young's modulus, the smaller the thermal vibrations and the longer and thinner a tip can be. The Young's moduli of carbon nanotubes have been determined by measurements of the thermal vibration amplitude by TEM [12.18, 19] and by directly measuring the forces required to deflect a pinned carbon nanotube in an AFM [12.20]. These experiments revealed that the Young's modulus of carbon nanotubes is 1–2 TPa, in agreement with theoretical predictions [12.21]. This makes carbon nanotubes the stiffest known material and, therefore, the best for fabricating thin, high-aspect-ratio tips. A more detailed and accurate derivation of the thermal vibration amplitudes was derived for the Young's modulus measurements [12.18, 19].

Carbon nanotubes elastically buckle under large loads, rather than fracture or plastically deform like most materials. Nanotubes were first observed in the buckled state by transmission electron microscopy [12.17], as shown in Fig. 12.9. The first experimental evidence that nanotube buckling is elastic came from the application of nanotubes as probe tips [12.22], described in detail below. A more direct experimental observation of elastic buckling was obtained by deflecting nanotubes pinned to a low friction surface with an AFM tip [12.20]. Both reports found that the buckling force could be approximated with the macroscopic Euler buckling formula for an elastic column:

$$F_{\mathrm{Euler}} = \frac{\pi^3 Yr^4}{4l^2} \,. \tag{12.7}$$

The buckling force puts another constraint on the tip length: If the nanotube is too long the buckling force



Fig. 12.9 TEM images and a model of a buckled nanotube, adapted from [12.17]

will be too low for stable imaging. The elastic buckling property of carbon nanotubes has significant implications for their use as AFM probes. If a large force is applied to the tip inadvertently, or if the tip encounters a large step in sample height, the nanotube can buckle to the side, then snap back without degraded imaging resolution when the force is removed, making these tips highly robust. No other tip material displays this buckling characteristic.

Manually Assembled Nanotube Probes

The first carbon nanotube AFM probes [12.22] were fabricated by techniques developed for assembling single-nanotube field emission tips [12.23]. This process, illustrated in Fig. 12.10, used purified MWNT material synthesized by the carbon arc procedure. The raw material, which must contain at least a few percent of long nanotubes ($> 10\,\mu$m) by weight, purified by oxidation to approximately 1% of its original mass. A torn edge of the purified material was attached to a micromanipulator by carbon tape and viewed under a high power optical microscope. Individual nanotubes and nanotube bundles were visible as filaments under dark field illumination. A commercially available AFM tip was attached to another micromanipulator opposing the nanotube material. Glue was applied to the tip apex from high vacuum carbon tape supporting the nanotube material. Nanotubes were then manually attached to the tip apex by micromanipulation. As assembled, MWNT tips were often too long for imaging due to thermal vibrations and low buckling forces described in Sect. 12.1.7. Nanotubes tips were shortened by applying 10 V pulses to the tip while it was near a sputtered niobium surface. This process etched ~ 100 nm lengths of nanotube per pulse.

The manually assembled MWNT tips demonstrated several important nanotube tip properties [12.22]. First, the high aspect ratio of the MWNT tips allowed the accurate imaging of trenches in silicon with steep sidewalls, similar to FIB and EBD tips. Second, elastic buckling was observed indirectly through force curves (see Fig. 12.11). Note that as the tip taps the sample, the amplitude drops to zero and a DC deflection is observed, because the nanotube is unbuckled and is essentially rigid. As the tip moves closer, the force on the nanotube eventually exceeds the buckling force. The nanotube buckles, allowing the vibration amplitude to partially recover, and the deflection remains constant. Numeric tip trajectory simulations could only reproduce these force curves if elastic buckling was included in the nanotube response. Finally, the nanotube tips were highly robust. Even after "tip crashes" or hundreds of controlled buckling cycles, the tip retained its resolution and high aspect ratio.



Fig. 12.10 A schematic drawing of the setup for manual assembly of carbon nanotube tips (*top*) and optical microscopy images of the assembly process (the cantilever was drawn in for clarity)



Fig. 12.11 Nanotube tip buckling. *Top* diagrams correspond to labeled regions of the force curves. As the nanotube tip buckles, the deflection remains constant and the amplitude increases, from [12.16]

Manual assembly of carbon nanotube probe tips is straightforward, but has several limitations. It is labor intensive and not amenable to mass production. Although MWNT tips have been made commercially available by this method, they are about ten times more expensive than silicon probes. The manual assembly method has also been carried out in an SEM, rather than an optical microscope [12.24]. This eliminates the need for pulse-etching, since short nanotubes can be attached to the tip, and the "glue" can be applied by EBD. But this is still not the key to mass production, since nanotube tips are made individually. MWNT tips provided a modest improvement in resolution on biological samples, but typical MWNT radii are similar to that of silicon tips, so they cannot provide the ultimate resolution possible with a SWNT tip. SWNT bundles can be attached to silicon probes by manual assembly. Pulse etching at times produces very high resolution tips that likely result from exposing a small number of nanotubes from the bundle, but this is not reproducible [12.25]. Even if a sample could be prepared that consisted of individual SWNT for manual assembly, such nanotubes would not be easily visible by optical microscopy or SEM.



Fig. 12.12 CVD nanotube synthesis. Ethylene reacts with a nanometer-scale iron catalyst particle at high temperature to form a carbon nanotube. The *inset* in the upper right is a TEM image showing a catalyst particle at the end of a nanotube, from [12.16]

CVD Nanotube Probe Synthesis

The problems of manual assembly of nanotube probes discussed above can largely be solved by directly growing nanotubes onto AFM tips by metal-catalyzed chemical vapor deposition (CVD). The key features of the nanotube CVD process are illustrated in Fig. 12.12. Nanometer-scale metal catalyst particles are heated in a gas mixture containing hydrocarbon or CO. The gas molecules dissociate on the metal surface, and carbon is adsorbed into the catalyst particle. When this carbon precipitates, it nucleates a nanotube of similar diameter to the catalyst particle. Therefore, CVD allows control over nanotube size and structure, including the production of SWNTs [12.26] with radii as low as 3.5 Angstrom [12.27].

Several key issues must be addressed to grow nanotube AFM tips by CVD: (1) the alignment of the nanotubes at the tip, (2) the number of nanotubes that grow at the tip, and (3) the length of the nanotube tip. *Li* et al. [12.28] found that nanotubes grow perpendicular to a porous surface containing embedded catalyst. This approach was exploited to fabricate nanotube tips by CVD [12.29] with the proper alignment, as illustrated in Fig. 12.13. A flattened area of approximately 1–5 µm^2 was created on Si tips by scanning in contact mode at high load (1 µN) on a hard, synthetic diamond surface. The tip was then anodized in HF to create 100 nm-diameter pores in this flat surface [12.30]. It is important to only anodize the last 20–40 µm of the cantilever, which includes the tip, so that the rest



Fig. 12.13 Pore-growth CVD nanotube tip fabrication. The *left panel*, from top to bottom, shows the steps described in the text. The *upper right* is an SEM image of such a tip with a small nanotube protruding from the pores (scale bar is 1 µm). The *lower right* is a TEM of a nanotube protruding from the pores (scale bar is 20 nm), from [12.16]

of the cantilever is still reflective for use in the AFM. This was achieved by anodizing the tip in a small drop of HF under the view of an optical microscope. Next, iron was electrochemically deposited into the pores to form catalyst particles [12.31]. Tips prepared in this way were heated in low concentrations of ethylene at 800 °C, which is known to favor the growth of thin nanotubes [12.26]. When imaged by SEM, nanotubes were found to grow perpendicular to the surface from the pores as desired (Fig. 12.13). TEM revealed that the nanotubes were thin, individual, multiwalled nanotubes with typical radii ranging from 3–5 nm. If nanotubes did not grow in an acceptable orientation, the carbon could be removed by oxidation, and then CVD repeated to grow new nanotube tips.

These "pore-growth" CVD nanotube tips were typically several microns in length – too long for imaging – and were pulse-etched to a usable length of < 500 nm. The tips exhibited elastic buckling behavior and were very robust in imaging. In addition, the thin, individual nanotube tips enabled improved resolution [12.29] on isolated proteins. The pore-growth method demonstrated the potential of CVD to simplify the fabrication of nanotube tips, although there were still limitations. In particular, the porous layer was difficult to prepare and rather fragile.

An alternative approach for CVD fabrication of nanotube tips involves direct growth of SWNTs on the surface of a pyramidal AFM tip [12.32, 33]. In this "surface-growth" approach, an alumina/iron/molybdenum-powdered catalyst known to produce SWNT [12.26] was dispersed in ethanol at 1 mg/mL. Silicon tips were dipped in this solution and allowed to dry, leaving a sparse layer of ~ 100 nm catalyst clusters on the tip. When CVD conditions were applied, single-walled nanotubes grew along the silicon tip surface. At a pyramid edge, nanotubes can either bend to align with the edge, or protrude from the surface. If the energy required to bend the tube and follow the edge is less than the attractive nanotube-surface energy, then the nanotube will follow the pyramid edge to the apex. Therefore, nanotubes were effectively steered toward the tip apex by the pyramid edges. At the apex, the nanotube protruded from the tip, since the energetic cost of bending around the sharp silicon tip was too high. The high aspect ratio at the oxide-sharpened silicon tip apex was critical for good nanotube alignment. A schematic of this approach is shown in Fig. 12.14. Evidence for this model came from SEM investigations that show that a very high yield of tips contains nanotubes only at the apex, with very few protruding elsewhere from the pyramid. TEM analysis demonstrated that the tips typically consist of small SWNT bundles that are formed by nanotubes coming together from different edges of the pyramid to join at the apex, supporting the surface growth model described above (Fig. 12.14). The "surface growth" nanotube tips exhibit a high aspect ratio and high resolution imaging, as well as elastic buckling.



Fig. 12.14a–c Surface-growth nanotube tip fabrication. **(a)** Schematic represents the surface growth process in which nanotubes growing on the pyramidal tip are guided to the tip apex. **(b)**,**(c)** Images show **(b)** SEM (200-nm-scale bar) and **(c)** TEM (20-nm-scale bar) images of a surface growth tip, from [12.16]

The surface growth method has been expanded to include wafer-scale production of nanotube tips with yields of over 90% [12.34], yet one obstacle remains to the mass production of nanotube probe tips. Nanotubes protruding from the tip are several microns long, and since they are so thin, they must be etched to less than 100 nm. While the pulse-etching step is fairly reproducible, it must be carried out on nanotube tips in a serial fashion, so surface growth does not yet represent a true method of batch nanotube tip fabrication.

Hybrid Nanotube Tip Fabrication: Pick-up Tips

Another method of creating nanotube tips is something of a hybrid between assembly and CVD. The motivation was to create AFM probes that have an *individual* SWNT at the tip to achieve the ultimate imaging resolution. In order to synthesize isolated SWNT, they must be nucleated at sites separated farther than their typical length. The alumina-supported catalyst contains a high density of catalyst particles per 100 nm cluster, so nanotube bundles cannot be avoided. To fabricate completely isolated nanotubes, isolated catalyst particles were formed by dipping a silicon wafer in an isopropyl alcohol solution of Fe(NO$_3$)$_3$. This effectively left a submonolayer of iron on the wafer, so that when it was heated in a CVD furnace, the iron became mobile and aggregated to form isolated iron particles. During CVD conditions, these particles nucleated and grew SWNTs. By controlling the reaction time, the SWNT lengths were kept shorter than their typical separation, so that the nanotubes never had a chance to form bundles. AFM analysis of these samples revealed 1–3 nm-diameter SWNT and un-nucleated particles on the surface (Fig. 12.15). However, there were tall objects that were difficult to image at a density of about 1 per 50 µm^2. SEM analysis at an oblique angle demonstrated that these were SWNTs that had grown perpendicular to the surface (Fig. 12.15).



Fig. 12.15 Atomic force microscopy image (*top*) of a wafer with isolated nanotubes synthesized by CVD. The SEM view provides evidence that some of these nanotubes are arranged vertically

In the "pick-up tip" method, these isolated SWNT substrates were imaged by AFM with silicon tips in air [12.9]. When the tip encountered a vertical SWNT, the oscillation amplitude was damped, so the AFM pulled the sample away from the tip. This pulled the SWNT into contact with the tip along its length, so that it became attached to the tip. This assembly process happened automatically when imaging in tapping mode – no special tip manipulation was required. When imaging a wafer with the density shown in Fig. 12.15, one nanotube was attached per 8 µm × 8 µm scan at 512×512 and 2 Hz, so a nanotube tip could be made in about 5 min. Since the as-formed SWNT tip continued to image, there was usually no evidence in the topographic image that a nanotube had been attached. However, the pick-up event was identified when the Z-voltage suddenly stepped to larger tip-



Fig. 12.16 Pick-up tip assembly of nanotube probes. The *top* illustrates the nanotube pick-up process that occurs while imaging vertical nanotubes in an AFM, including a trace of the Z-position during a pick-up event. The *lower left* TEM images show single nanotubes (diameters 0.9 nm and 2.8 nm) on an AFM tip fabricated by this method, adapted from [12.9]



Fig. 12.17 The process by which nanotube tips can be shortened in AFM force curves. The hysteresis in the deflection trace (*bottom*) reveals that ∼ 17 nm were removed

sample separation due to the effective increase in tip length.

Individual SWNT tips must be quite short, typically less than 50 nm in length, for reasons outlined above. Pulse-etching, which removes 50–100 nm of nanotube length at a time, lacked the necessary precision for shortening pick-up tips, so the tips were shortened through force curves. A pick-up tip force curve is shown in Fig. 12.17. When the tip first interacted with the sample, the amplitude decreased to zero, and further approach generated a small deflection that ultimately saturated. However, this saturation was not due to buckling. Note that the amplitude did not recover, as in the buckling curves. This leveling was due to the nanotube sliding on the pyramidal tip, which was confirmed by the hysteresis in the amplitude and deflection curves. If the force curve was repeated, the tip showed no deflection or amplitude drop until further down, because the tip was essentially shorter.

Pick-up SWNT tips achieve the highest resolution of all nanotube tips, since they are always individuals rather than bundles. In tapping mode, they produce images of 5 nm gold particles that have a *full width* of ∼ 7 nm, the expected geometrical resolution for a 2 nm cylindrical probe [12.9]. Although the pick-up method is serial in nature, it may still be the key to the mass production of nanotube tips. Note that the original nanotube tip length can be measured electronically from the size of the Z-piezo step. The shortening can be electronically controlled through the hysteresis in the force curves. Therefore, the entire procedure (including tip exchange) can be automated by computer.

12.2 Scanning Tunneling Microscopy

Scanning tunneling microscopy (STM) was the original scanning probe microscopy and generally produces the highest resolution images, routinely achieving atomic resolution on flat, conductive surfaces. In STM, the probe tip consists of a sharpened metal wire that is held 0.3 to 1 nm from the sample. A potential difference of 0.1 V to 1 V between the tip and sample leads to tunneling currents on the order of 0.1 to 1 nA. As in AFM, a piezo-scanner rasters the sample under the tip, and the Z-position is adjusted to hold the tunneling current constant. The Z-position data represents the "topography", or in this case the surface, of constant electron density. As with other SPMs, the tip properties and performance greatly depend on the experiment being carried out. Although it is nearly impossible to prepare a tip with a known atomic structure, a number of factors are known to affect tip performance, and several preparation methods have been developed that produce good tips.

The nature of the sample being investigated and the scanning environment will affect the choice of the tip material and how the tip is fabricated. Factors to consider are mechanical properties – a hard material that will resist damage during tip-sample contact is desired. Chemical properties should also be considered – formation of oxides, or other insulating contaminants will affect tip performance. Tungsten is a common tip material because it is very hard and will resist damage, but its use is limited to ultrahigh vacuum (UHV) conditions, since it readily oxidizes. For imaging under ambient conditions an inert tip material such as platinum or gold is preferred. Platinum is typically alloyed with iridium to increase its stiffness.

12.2.1 Mechanically Cut STM Tips

STM tips can be fabricated by simple mechanical procedures such as grinding or cutting metal wires. Such tips are not formed with highly reproducible shapes and have a large opening angle and a large radius of curvature in the range of 0.1 to 1 μm (see Fig. 12.18a). They are not useful for imaging samples with surface roughness above a few nanometers. However, on atomically flat samples, mechanically cut tips can achieve atomic resolution due to the nature of the tunneling signal, which drops exponentially with tip-sample separation. Since mechanically cut tips contain many small asperities on the larger tip structure, atomic resolution is easily achieved as long as one atom of the tip is just a few angstroms lower than all of the others.



Fig. 12.18 A mechanically cut STM tip (*left*) and an electrochemically etched STM tip (*right*), from [12.35]

12.2.2 Electrochemically Etched STM Tips

For samples with more than a few nanometers of surface roughness, the tip structure in the nanometer-size range becomes an issue. Electrochemical etching can provide tips with reproducible and desirable shapes and sizes (Fig. 12.18), although the exact atomic structure of the tip apex is still not well controlled. The parameters of electrochemical etching depend greatly on the tip material and the desired tip shape. The following is an entirely general description. A fine metal wire (0.1–1 mm diameter) of the tip material is immersed in an appropriate electrochemical etchant solution. A voltage bias of 1–10 V is applied between the tip and a counterelectrode such that the tip is etched. Due to the enhanced etch rate at the electrolyte-air interface, a neck is formed in the wire. This neck is eventually etched thin enough so that it cannot support the weight of the part of the wire suspended in the solution, and it breaks to form a sharp tip. The widely varying parameters and methods will be not be covered in detail here, but many recipes are found in the literature for common tip materials [12.36–39].

References

12.1 R. Linnemann, T. Gotszalk, I. W. Rangelow, P. Dumania, E. Oesterschulze: Atomic force microscopy and lateral force microscopy using piezoresistive cantilevers, J. Vac. Sci. Technol. B **14**(2) (1996) 856–860
12.2 T. R. Albrecht, S. Akamine, T. E. Carver, C. F. Quate: Microfabrication of cantilever styli for the atomic force microscope, J. Vac. Sci. Technol. A **8**(4) (1990) 3386–3396
12.3 O. Wolter, T. Bayer, J. Greschner: Micromachined silicon sensors for scanning force microscopy, J. Vac. Sci. Technol. B **9**(2) (1991) 1353–1357
12.4 C. Bustamante, D. Keller: Scanning force microscopy in biology, Phys. Today **48**(12) (1995) 32–38
12.5 J. Vesenka, S. Manne, R. Giberson, T. Marsh, E. Henderson: Colloidal gold particles as an incompressible atomic force microscope imaging standard for assessing the compressibility of biomolecules, Biophys. J. **65** (1993) 992–997
12.6 D. J. Muller, D. Fotiadis, S. Scheuring, S. A. Muller, A. Engel: Electrostatically balanced subnanometer imaging of biological specimens by atomic force microscope, Biophys. J. **76**(2) (1999) 1101–1111
12.7 R. B. Marcus, T. S. Ravi, T. Gmitter, K. Chin, D. Liu, W. J. Orvis, D. R. Ciarlo, C. E. Hunt, J. Trujillo: Formation of silicon tips with <1 nm radius, Appl. Phys. Lett. **56**(3) (1990) 236–238
12.8 J. H. Hafner, C. L. Cheung, C. M. Lieber: unpublished results (2001)
12.9 J. H. Hafner, C. L. Cheung, T. H. Oosterkamp, C. M. Lieber: High-yield assembly of individual single-walled carbon nanotube tips for scanning probe microscopies, J. Phys. Chem. B **105**(4) (2001) 743–746
12.10 F. Ohnesorge, G. Binnig: True atomic resolution by atomic force microscopy through repulsive and attractive forces, Science **260** (1993) 1451–1456
12.11 D. J. Muller, D. Fotiadis, A. Engel: Mapping flexible protein domains at subnanometer resolution with the atomic force microscope, FEBS Lett. **430**(1–2 Special Issue SI) (1998) 105–111
12.12 S. Akamine, R. C. Barrett, C. F. Quate: Improved atomic force microscope images using microcantilevers with sharp tips, Appl. Phys. Lett. **57**(3) (1990) 316–318

12.13 D.J. Keller, C. Chih-Chung: Imaging steep, high structures by scanning force microscopy with electron beam deposited tips, Surf. Sci. **268** (1992) 333–339

12.14 T. Ichihashi, S. Matsui: In situ observation on electron beam induced chemical vapor deposition by transmission electron microscopy, J. Vac. Sci. Technol. B **6**(6) (1988) 1869–1872

12.15 K. I. Schiffmann: Investigation of fabrication parameters for the electron-beam-induced deposition of contamination tips used in atomic force microscopy, Nanotechnology **4** (1993) 163–169

12.16 J. H. Hafner, C. L. Cheung, A. T. Woolley, C. M. Lieber: Structural and functional imaging with carbon nanotube AFM probes, Prog. Biophys. Mol. Biol. **77**(1) (2001) 73–110

12.17 S. Iijima, C. Brabec, A. Maiti, J. Bernholc: Structural flexibility of carbon nanotubes, J. Chem. Phys. **104**(5) (1996) 2089–2092

12.18 M. M. J. Treacy, T. W. Ebbesen, J. M. Gibson: Exceptionally high Young's modulus observed for individual carbon nanotubes, Nature **381** (1996) 678–680

12.19 A. Krishnan, E. Dujardin, T. W. Ebbesen, P. N. Yianilos, M. M. J. Treacy: Young's modulus of single-walled nanotubes, Phys. Rev. B **58**(20) (1998) 14013–14019

12.20 E. W. Wong, P. E. Sheehan, C. M. Lieber: Nanobeam mechanics – elasticity, strength, and toughness of nanorods and nanotubes, Science **277**(5334) (1997) 1971–1975

12.21 J. P. Lu: Elastic properties of carbon nanotubes and nanoropes, Phys. Rev. Lett. **79**(7) (1997) 1297–1300

12.22 H. J. Dai, J. H. Hafner, A. G. Rinzler, D. T. Colbert, R. E. Smalley: Nanotubes as nanoprobes in scanning probe microscopy, Nature **384**(6605) (1996) 147–150

12.23 A. G. Rinzler, Y. H. Hafner, P. Nikolaev, L. Lou, S. G. Kim, D. Tomanek, D. T. Colbert, R. E. Smalley: Unraveling nanotubes: Field emission from atomic wire, Science **269** (1995) 1550

12.24 H. Nishijima, S. Kamo, S. Akita, Y. Nakayama, K. I. Hohmura, S. H. Yoshimura, K. Takeyasu: Carbon-nanotube tips for scanning probe microscopy: Preparation by a controlled process and observation of deoxyribonucleic acid, Appl. Phys. Lett. **74**(26) (1999) 4061–4063

12.25 S. S. Wong, A. T. Woolley, T. W. Odom, J. L. Huang, P. Kim, D. V. Vezenov , C. M. Lieber: Single-walled carbon nanotube probes for high-resolution nanostructure imaging, Appl. Phys. Lett. **73**(23) (1998) 3465–3467

12.26 J. H. Hafner, M. J. Bronikowski, B. R. Azamian, P. Nikolaev, A. G. Rinzler, D. T. Colbert, K. A. Smith, R. E. Smalley: Catalytic growth of single-wall carbon nanotubes from metal particles, Chem. Phys. Lett. **296**(1–2) (1998) 195–202

12.27 P. Nikolaev, M. J. Bronikowski, R. K. Bradley, F. Rohmund, D. T. Colbert, K. A. Smith, R. E. Smalley: Gas-phase catalytic growth of single-walled carbon nanotubes from carbon monoxide, Chem. Phys. Lett. **313**(1–2) (1999) 91–97

12.28 W. Z. Li, S. S. Xie, L. X. Qian, B. H. Chang, B. S. Zou, W. Y. Zhou, R. A. Zhao, G. Wang: Large-scale synthesis of aligned carbon nanotubes, Science **274**(5293) (1996) 1701–1703

12.29 J. H. Hafner, C. L. Cheung, C. M. Lieber: Growth of nanotubes for probe microscopy tips, Nature **398**(6730) (1999) 761–762

12.30 V. Lehmann: The physics of macroporous silicon formation, Thin Solid Films **255** (1995) 1–4

12.31 F. Ronkel, J. W. Schultze, R. Arensfischer: Electrical contact to porous silicon by electrodeposition of iron, Thin Solid Films **276**(1–2) (1996) 40–43

12.32 J. H. Hafner, C. L. Cheung, C. M. Lieber: Direct growth of single-walled carbon nanotube scanning probe microscopy tips, J. Am. Chem. Soc. **121**(41) (1999) 9750–9751

12.33 E. B. Cooper, S. R. Manalis, H. Fang, H. Dai, K. Matsumoto, S. C. Minne, T. Hunt, C. F. Quate: Terabit-per-square-inch data storage with the atomic force microscope, Appl. Phys. Lett. **75**(22) (1999) 3566–3568

12.34 E. Yenilmez, Q. Wang, R. J. Chen, D. Wang, H. Dai: Wafer scale production of carbon nanotube scanning probe tips for atomic force microscopy, Appl. Phys. Lett. **80**(12) (2002) 2225–2227

12.35 A. Stemmer, A. Hefti, U. Aebi, A. Engel: Scanning tunneling and transmission electron microscopy on identical areas of biological specimens, Ultramicroscopy **30**(3) (1989) 263

12.36 R. Nicolaides, L. Yong, W. E. Packard, W. F. Zhou, H. A. Blackstead, K. K. Chin, J. D. Dow, J. K. Furdyna, M. H. Wei, R. C. Jaklevic, W. J. Kaiser, A. R. Pelton, M. V. Zeller, J. J. Bellina: Scanning tunneling microscope tip structures, J. Vac. Sci. Technol. A **6**(2) (1988) 445–447

12.37 J. P. Ibe, P. P. Bey, S. L. Brandow, R. A. Brizzolara, N. A. Burnham, D. P. DiLella, K. P. Lee, C. R. K. Marrian, R. J. Colton: On the electrochemical etching of tips for scanning tunneling microscopy, J. Vac. Sci. Technol. A **8** (1990) 3570–3575

12.38 L. Libioulle, Y. Houbion, J.-M. Gilles: Very sharp platinum tips for scanning tunneling microscopy, Rev. Sci. Instrum. **66**(1) (1995) 97–100

12.39 A. J. Nam, A. Teren, T. A. Lusby, A. J. Melmed: Benign making of sharp tips for STM and FIM: Pt, Ir, Au, Pd, and Rh, J. Vac. Sci. Technol. B **13**(4) (1995) 1556–1559

13. Noncontact Atomic Force Microscopy and Its Related Topics

The scanning probe microscopy (SPM) such as the STM and the NC-AFM is the basic technology for the nanotechnology and also for the future bottom-up process. In Sect. 13.1, the principles of AFM such as operating modes and the frequency modulation method of the NC-AFM are fully explained. Then, in Sect. 13.2, applications of NC-AFM to semiconductors that make clear its potentials such as spatial resolution and functions are introduced. Next, in Sect. 13.3, applications of NC-AFM to insulators such as alkali halides, fluorides and transition metal oxides are introduced. At last, in Sect. 13.4, applications of NC-AFM to molecules such as carboxylate ($RCOO^-$) with $R = H$, CH_3, $C(CH_3)_3$ and CF_3 are introduced. Thus, the NC-AFM can observe atoms and molecules on various kinds of surfaces such as semiconductor, insulator and metal oxide with atomic/molecular resolutions. These sections are essential to understand the status of the art and the future possibility of NC-AFM that is the second generation of atom/molecule technology.

13.1 **Principles of Noncontact Atomic Force Microscope (NC-AFM)** 386
13.1.1 Imaging Signal in AFM 386
13.1.2 Experimental Measurement and Noise 387
13.1.3 Static AFM Operating Mode 387
13.1.4 Dynamic AFM Operating Mode 388
13.1.5 The Four Additional Challenges Faced by AFM 388
13.1.6 Frequency-Modulation AFM (FM-AFM) 389
13.1.7 Relation Between Frequency Shift and Forces 390
13.1.8 Noise in Frequency-Modulation AFM – Generic Calculation 391
13.1.9 Conclusion 391

13.2 **Applications to Semiconductors** 391
13.2.1 Si(111)7×7 Surface 392
13.2.2 Si(100)2×1 and Si(100)2×1:H Monohydride Surfaces 393
13.2.3 Metal-Deposited Si Surface 395

13.3 **Applications to Insulators** 397
13.3.1 Alkali Halides, Fluorides, and Metal Oxides 397
13.3.2 Atomically Resolved Imaging of a NiO(001) Surface 402
13.3.3 Atomically Resolved Imaging Using Noncoated and Fe-Coated Si Tips 402

13.4 **Applications to Molecules** 404
13.4.1 Why Molecules and What Molecules? 404
13.4.2 Mechanism of Molecular Imaging 404
13.4.3 Perspectives 407

References 407

The scanning tunneling microscope (STM) is an atomic tool based on an electric method that measures the tunneling current between a conductive tip and a conductive surface. It can electrically observe individual atoms/molecules. It can characterize or analyze the electronic nature around surface atoms/molecules. In addition, it can manipulate individual atoms/molecules. Hence, the STM is the first generation of atom/molecule technology. On the other hand, the atomic force microscope (AFM) is a unique atomic tool based on a mechanical method that can deal with even the insulator surface. Since the invention of noncontactAFM (NC-AFM) in 1995, the NC-AFM and the NC-AFM-based method have rapidly developed into a powerful surface tool on atomic/molecular scales, because the NC-AFM has the following characteristics: (1) it has true atomic resolution, (2) it can measure atomic force (so-called atomic force spectroscopy), (3) it can observe even insulators, and (4) it can measure mechanical responses such as elastic deformation. Thus, the NC-AFM is the second generation of atom/molecule technology. The scanning probe microscopy (SPM) such as the STM and the NC-AFM is the basic technology for nanotechnology and also for the future bottom-up process.

In Sect. 13.1, principles of NC-AFM will be fully introduced. Then, in Sect. 13.2, applications to semiconductors will be presented. Next, in Sect. 13.3, applications to insulators will be described. And, in Sect. 13.4, applications to molecules will be introduced. These sections are essential to understanding the status of the art and the future possibility of the NC-AFM.

13.1 Principles of Noncontact Atomic Force Microscope (NC-AFM)

The atomic force microscope (AFM), invented by *Binnig* [13.1] and introduced in 1986 by *Binnig*, *Quate*, and *Gerber* [13.2], is an offspring of the scanning tunneling microscope (STM) [13.3]. The STM is covered in books and review articles, e.g., [13.4–9]. Early on in the development of STM it became evident that relatively strong forces act between a tip in close proximity to a sample. It was found that these forces could be put to good use in the atomic force microscope (AFM). Detailed information about the noncontact AFM can be found in [13.10–12].

13.1.1 Imaging Signal in AFM

Figure 13.1 shows a sharp tip close to a sample. The potential energy between the tip and sample V_{ts} causes a z component of the tip-sample force $F_{ts} = -\partial V_{ts}/\partial z$. Depending on the mode of operation, the AFM uses F_{ts} or some entity derived from F_{ts} as the imaging signal.

Unlike the tunneling current, which has a very strong distance dependence, F_{ts} has long- and short-range contributions. We can classify the contributions by their range and strength. In vacuum, there are van der Waals, electrostatic, and magnetic forces with long-range (up to 100 nm) and short-range chemical forces (fractions of a nm).

The van der Waals interaction is caused by fluctuations in the electric dipole moment of atoms and their mutual polarization. For a spherical tip with radius R next to a flat surface (z is the distance between the plane connecting the centers of the surface atoms and the center of the closest tip atom), the van der Waals potential is given by [13.13]:

$$V_{\mathrm{vdW}} = -\frac{A_{\mathrm{H}}}{6z}\,. \tag{13.1}$$

The “Hamaker constant”, A_{H}, depends on the type of materials (atomic polarizability and density) of the tip and sample and is on the order of 1 eV for most solids [13.13].

When the tip and sample are both conductive and have an electrostatic potential difference, $U \neq 0$, electrostatic forces are important. For a spherical tip with radius R, the force is given by [13.14]:

$$F_{\mathrm{electrostatic}} = -\frac{\pi\varepsilon_0 R U^2}{z}\,. \tag{13.2}$$

Chemical forces are more complicated. Empirical model potentials for chemical bonds are the Morse potential (see e.g., [13.13]).

$$V_{\mathrm{Morse}} = -E_{\mathrm{bond}}\left(2\,\mathrm{e}^{-\kappa(z-\sigma)} - \mathrm{e}^{-2\kappa(z-\sigma)}\right) \tag{13.3}$$

and the Lennard-Jones potential [13.13]:

$$V_{\mathrm{Lennard\text{-}Jones}} = -E_{\mathrm{bond}}\left(2\frac{\sigma^6}{z^6} - \frac{\sigma^{12}}{z^{12}}\right)\,. \tag{13.4}$$

These potentials describe a chemical bond with bonding energy E_{bond} and equilibrium distance σ. The Morse potential has an additional parameter – a decay length κ.



Fig. 13.1 Schematic view of an AFM tip close to a sample

13.1.2 Experimental Measurement and Noise

Forces between the tip and sample are typically measured by recording the deflection of a cantilever beam that has a tip mounted to its end (see Fig. 13.2). Today's microfabricated silicon cantilevers were first created by the *Calvin F. Quate* group [13.15–17] and *Wolter* et al. at IBM [13.18].

The cantilever is characterized by its spring constant k, eigenfrequency f_0, and quality factor Q.

For a rectangular cantilever with dimensions w, t, and L (see Fig. 13.2), the spring constant k is given by [13.6]:

$$k = \frac{E_{\mathrm{Y}} w t^3}{4L^3}\,, \tag{13.5}$$

where E_{Y} is Young's modulus. The eigenfrequency f_0 is given by [13.6]:

$$f_0 = 0.162 \frac{t}{L^2} \sqrt{E_{\mathrm{Y}}/\rho}\,, \tag{13.6}$$

where ρ is the mass density of the cantilever material. The Q-factor depends on the damping mechanisms present in the cantilever. For micromachined cantilevers operated in air, Q is typically a few hundred but can reach hundreds of thousands in vacuum.

In the first AFM, the deflection of the cantilever was measured with an STM – the backside of the cantilever was metalized, and a tunneling tip was brought close to it to measure the deflection [13.2]. Today's designs use optical (interferometer, beam-bounce) or electrical methods (piezoresistive, piezoelectric) for measuring the cantilever deflection. A discussion of the various techniques can be found in [13.19], descriptions of piezoresistive detection schemes are found in [13.17, 20], and piezoelectric methods are explained in [13.21–24].



Fig. 13.2 Top view and side view of a microfabricated silicon cantilever (schematic)



Fig. 13.3 Schematic view of $1/f$ noise apparent in force detectors. Static AFMs operate in a frequency range from 0.01 Hz to a few hundred Hz, while dynamic AFMs operate at frequencies around 10 kHz to a few hundred kHz. The noise of the cantilever deflection sensor is characterized by the $1/f$ corner frequency f_c and the constant deflection noise density $n_{q'}$ for the frequency range where white noise is dominating

The quality of the cantilever deflection measurement can be expressed in a schematic plot of the deflection noise density versus frequency, as in Fig. 13.3.

The noise density has a $1/f$ dependence for low frequency and merges into a constant noise density ("white noise") above the "$1/f$ corner frequency".

13.1.3 Static AFM Operating Mode

In the static mode of operation, the force translates into a deflection $q' = F_{\mathrm{ts}}/k$ of the cantilever, yielding images as maps $z(x, y, F_{\mathrm{ts}} = \text{const.})$. The noise level of the force measurement is then given by the cantilever's spring constant k times the noise level of the deflection measurement. In this respect, a small value for k increases force sensitivity. On the other hand, instabilities are more likely to occur with soft cantilevers (see Sect. 13.1.5). Because the deflection of the cantilever should be significantly larger than the deformation of the tip and sample, the cantilever should be much softer than the bonds between the bulk atoms in the tip and sample. Inter-atomic force constants in solids are in a range from 10 N/m to about 100 N/m – in biological samples, they can be as small as 0.1 N/m. Thus, typical values for k in the static mode are 0.01–5 N/m.

Even though it has been demonstrated that atomic resolution is possible with static AFM, the method can only be applied in certain cases. The detrimental effects of $1/f$ noise can be limited by working at low temperatures [13.25], where the coefficients of thermal expansion are very small, or by building the AFM of a material with a low thermal expansion coefficient [13.26]. The long-range attractive forces have to be cancelled by immersing the tip and sample in a liquid [13.26], or by partly compensating the attractive force by pulling at the cantilever after jump-to-contact has occurred [13.27]. *Jarvis* et al. have cancelled the long-range attractive force with an electromagnetic force applied to the cantilever [13.28]. Even with these restrictions, static AFM does not produce atomic resolution on reactive surfaces like silicon, as the chemical bonding of the AFM tip and sample pose an unsurmountable problem [13.29, 30].

13.1.4 Dynamic AFM Operating Mode

In the dynamic operation modes, the cantilever is deliberately vibrated. There are two basic methods of dynamic operation: amplitude modulation (AM) and frequency modulation (FM) operation. In AM-AFM [13.31], the actuator is driven by a fixed amplitude A_{drive} at a fixed frequency f_{drive}, where f_{drive} is close to f_0. When the tip approaches the sample, elastic and inelastic interactions cause a change in both the amplitude and the phase (relative to the driving signal) of the cantilever. These changes are used as the feedback signal. While the AM mode was initially used in a noncontact mode, it was later implemented very successfully at a closer distance range in ambient conditions involving repulsive tip-sample interactions.



Fig. 13.4 Plot of tunneling current I_{t} and force F_{ts} (typical values) as a function of distance z between front atom and surface atom layer

The change in amplitude in AM mode does not occur instantaneously with a change in the tip-sample interaction, but on a time scale of $\tau_{\text{AM}} \approx 2Q/f_0$, and the AM mode is slow with high-Q cantilevers. However, the use of high Q-factors reduces noise. *Albrecht* et al. found a way to combine the benefits of high Q and high speed by introducing the frequency modulation (FM) mode [13.32], where the change in the eigenfrequency settles on a time scale of $\tau_{\text{FM}} \approx 1/f_0$.

Using the FM mode, the resolution was improved dramatically, and finally atomic resolution [13.33, 34] was obtained by reducing the tip-sample distance and working in vacuum. For atomic studies in vacuum, the FM mode (see Sect. 13.1.6) is now the preferred AFM technique. However, atomic resolution in vacuum can also be obtained with the AM mode, as demonstrated by *Erlandsson* et al. [13.35].

13.1.5 The Four Additional Challenges Faced by AFM

Some of the inherent AFM challenges are apparent by comparing the tunneling current and tip-sample force as a function of distance (Fig. 13.4).

The tunneling current is a monotonic function of the tip-sample distance and has a very sharp distance dependence. In contrast, the tip-sample force has long- and short-range components and is not monotonic.

Jump-to-Contact and Other Instabilities

If the tip is mounted on a soft cantilever, the initially attractive tip-sample forces can cause a sudden "jump-to-contact" when the tip approaches the sample. This instability occurs in the quasi-static mode if [13.36, 37]

$$k < \max\left(-\frac{\partial^2 V_{\text{ts}}}{\partial z^2}\right) = k_{\text{ts}}^{\max} . \tag{13.7}$$

Jump-to-contact can be avoided even for soft cantilevers by oscillating it at a large enough amplitude A [13.38]:

$$kA > \max\left(-F_{\text{ts}}\right) . \tag{13.8}$$

If hysteresis occurs in the $F_{\text{ts}}(z)$-relation, the energy ΔE_{ts} needs to be supplied to the cantilever for each oscillation cycle. If this energy loss is large compared to the intrinsic energy loss of the cantilever, amplitude control can become difficult. An additional approximate criterion for k and A is then

$$\frac{kA^2}{2} \geq \frac{\Delta E_{\text{ts}} Q}{2\pi} . \qquad (13.9)$$

Contribution of Long-Range Forces

The force between tip and sample is composed of many contributions: electrostatic, magnetic, van der Waals, and chemical forces in vacuum. All of these force types except for the chemical forces have strong long-range components that conceal the atomic-force components. For imaging by AFM with atomic resolution, it is desirable to filter out the long-range force contributions and only measure the force components that vary at the atomic scale. While there is no way to discriminate between long- and short-range forces in static AFM, it is possible to enhance the short-range contributions in dynamic AFM through the proper choice of the oscillation amplitude A of the cantilever.

Noise in the Imaging Signal

Measuring the cantilever deflection is subject to noise, especially at low frequencies ($1/f$ noise). In static AFM, this noise is particularly problematic because of the approximate $1/f$ dependence. In dynamic AFM, the low-frequency noise is easily discriminated when using a bandpass filter with a center frequency around f_0.

Non-monotonic Imaging Signal

The tip-sample force is not monotonic. In general, the force is attractive for large distances, and upon decreasing the distance between tip and sample, the force turns repulsive (see Fig. 13.4). Stable feedback is only possible on a monotonic subbranch of the force curve.

Frequency-modulation AFM (FM-AFM) helps to overcome challenges. The non-monotonic imaging signal in AFM is a remaining complication for FM-AFM.

13.1.6 Frequency-Modulation AFM (FM-AFM)

In FM-AFM, a cantilever with eigenfrequency f_0 and spring constant k is subject to controlled positive feedback such that it oscillates with a constant amplitude A [13.32], as shown in Fig. 13.5.

Experimental Setup

The deflection signal is phase shifted, routed through an automatic gain control circuit and fed back to the actuator. The frequency f is a function of f_0, its quality factor Q, and the phase shift ϕ between the mechanical excitation generated at the actuator and the deflection of the cantilever. If $\phi = \pi/2$, the loop oscillates at $f = f_0$.



Fig. 13.5 Block diagram of a frequency-modulation force sensor

Three physical observables can be recorded: 1) a change in resonance frequency, Δf, 2) the control signal of the automatic gain control unit as a measure of the tip-sample energy dissipation and 3) an average tunneling current (for conducting cantilevers and tips).

Applications

FM-AFM was introduced by *Albrecht* and coworkers in magnetic force microscopy [13.32]. The noise level and imaging speed were enhanced significantly compared to amplitude modulation techniques. Achieving atomic resolution on the Si(111)-(7×7) surface has been an important step in the development of the STM [13.39], and in 1994, this surface was imaged by AFM with true atomic resolution for the first time [13.33] (see Fig. 13.6).

The initial parameters that provided *true atomic resolution* (see caption of Fig. 13.6) were found empirically. Surprisingly, the amplitude necessary for obtaining good



Fig. 13.6 First AFM image of the Si(111)-(7×7) surface. Parameters $k = 17\,\text{Nm}$, $f_0 = 114\,\text{kHz}$, $Q = 28{,}000$, $A = 34\,\text{nm}$, $\Delta f = -70\,\text{Hz}$, $V_\text{t} = 0\,\text{V}$

results was very large compared to atomic dimensions. It turned out later that the amplitudes had to be that large in order to fulfill the stability criteria listed in Sect. 13.1.5. Cantilevers with $k \approx 2{,}000\,\mathrm{N/m}$ can be operated with amplitudes in the Å-range [13.24].

13.1.7 Relation Between Frequency Shift and Forces

The cantilever (spring constant k, effective mass m^*) is a macroscopic object and its motion can be described by classical mechanics. Figure 13.7 shows the deflection $q'(t)$ of the tip of the cantilever: It oscillates with an amplitude A at a distance $q(t)$ to a sample.

Generic Calculation

The Hamiltonian of the cantilever is:

$$H = \frac{p^2}{2m^*} + \frac{kq'^2}{2} + V_{\mathrm{ts}}(q)\,, \tag{13.10}$$

where $p = m^*\,\mathrm{d}q'/\mathrm{d}t$. The unperturbed motion is given by:

$$q'(t) = A\cos(2\square f_0 t)\,, \tag{13.11}$$

and the frequency is:

$$f_0 = \frac{1}{2\pi}\sqrt{\frac{k}{m^*}}\,. \tag{13.12}$$

If the force gradient $k_{\mathrm{ts}} = -\partial F_{\mathrm{ts}}/\partial z = \partial^2 V_{\mathrm{ts}}/\partial z^2$ is constant during the oscillation cycle, the calculation of the frequency shift is trivial:

$$\Delta f = \frac{f_0}{2k} k_{\mathrm{ts}}\,. \tag{13.13}$$

However, in classic FM-AFM, k_{ts} varies in orders of magnitude during one oscillation cycle, and a perturbation approach, as shown below, has to be employed for the calculation of the frequency shift.



Fig. 13.7 Schematic view of an oscillating cantilever and definition of geometric terms

Hamilton–Jacobi Method

The first derivation of the frequency shift in FM-AFM was achieved in 1997 [13.38] using canonical perturbation theory [13.40]. The result of this calculation is:

$$\begin{aligned}\Delta f &= -\frac{f_0}{kA^2}\left\langle F_{\mathrm{ts}} q'\right\rangle \\ &= -\frac{f_0}{kA^2}\int_0^{1/f_0} F_{\mathrm{ts}}(d+A+q'(t))q'(t)\,\mathrm{d}t\,.\end{aligned} \tag{13.14}$$

The applicability of first-order perturbation theory is justified, because in FM-AFM, E is typically in the range of several keVs, while V_{ts} is on the order of a few eVs. *Dürig* [13.41] has found a generalized algorithm that even allows the reconstruction of the tip-sample potential if not only the frequency shift, but the higher harmonics of the cantilever oscillation are known.

A Descriptive Expression for Frequency Shifts as a Function of the Tip-Sample Forces

With integration by parts, the complicated expression (13.14) transforms into a very simple expression that resembles (13.13) [13.42].

$$\Delta f = \frac{f_0}{2k}\int_{-A}^{A} k_{\mathrm{ts}}(z-q')\frac{\sqrt{A^2-q'^2}}{\frac{\pi}{2}kA^2}\,\mathrm{d}q'\,. \tag{13.15}$$

This expression is closely related to (13.13): The constant k_{ts} is replaced by a weighted average, where the weight function $w(q', A)$ is a semicircle with radius A divided by the area of the semicircle $\pi A^2/2$ (see Fig. 13.8). For $A \to 0$, $w(q', A)$ is a representation of Dirac's delta function and the trivial zero-amplitude result of (13.13) is immediately recovered. The frequency shift results from a convolution between the tip-sample force gradient and the weight function. This convolution can easily be reversed with a linear transformation, and the tip-sample force can be recovered from the frequency shift versus distance curve [13.42].

The dependence of the frequency shift with amplitude confirms an empirical conjecture: Small amplitudes increase the sensitivity to short-range forces! Adjusting the amplitude in FM-AFM resembles tuning an optical spectrometer to a passing wavelength. When short-range interactions are to be probed, the amplitude should be in the range of the short-range forces. While using amplitudes in the Å-range has been elusive with conventional cantilevers, because of the instability problems described in Sect. 13.1.5, cantilevers with a stiffness on the order of $1{,}000\,\mathrm{N/m}$ like the ones introduced in [13.23] are well suited for small-amplitude operation.

13.1.8 Noise in Frequency-Modulation AFM – Generic Calculation

The vertical noise in FM-AFM is given by the ratio between the noise in the imaging signal and the slope of the imaging signal with respect to z:

$$\delta z = \frac{\delta \Delta f}{\left|\frac{\partial \Delta f}{\partial z}\right|} . \qquad (13.16)$$

Figure 13.9 shows a typical frequency shift versus distance curve. Because the distance between the tip and sample is measured indirectly through the frequency shift, it is clearly evident from Fig. 13.9 that the noise in the frequency measurement $\delta \Delta f$ translates into vertical noise δz and is given by the ratio between $\delta \Delta f$ and the slope of the frequency shift curve $\Delta f(z)$ (13.16). Low vertical noise is obtained for a low-noise frequency measurement and a steep slope of the frequency shift curve.

The frequency noise $\delta \Delta f$ is typically inversely proportional to the cantilever amplitude A [13.32, 43]. The derivative of the frequency shift versus distance is constant for $A \ll \lambda$, where λ is the range of the tip-sample interaction and proportional to $A^{-1.5}$ for $A \gg \lambda$ [13.38]. Thus, minimal noise occurs if [13.44]

$$A_{\text{optimal}} \approx \lambda , \qquad (13.17)$$

for chemical forces, $\lambda \approx 1$ Å. However, for stability reasons (Sect. 13.1.5), extremely stiff cantilevers are needed for small amplitude operation. The excellent noise performance of the stiff cantilever and small amplitude technique has been verified experimentally [13.24].

13.1.9 Conclusion

Dynamic force microscopy, in particular frequency-modulation atomic force microscopy, has matured into a viable technique that allows true atomic resolution of conducting and insulating surfaces and spectroscopic measurements on individual atoms [13.10, 45]. Even true atomic resolution in lateral force microscopy is now possible [13.46]. Challenges remain in the chemical composition and structural arrangement of the AFM tip.



Fig. 13.8 Tip-sample force gradient k_{ts} and weight function for the calculation of the frequency shift



Fig. 13.9 Plot of frequency shift Δf as a function of tip-sample distance z. The noise in the tip-sample distance measurement is given by the noise of the frequency measurement $\delta \Delta f$ divided by the slope of the frequency shift curve

13.2 Applications to Semiconductors

For the first time, corner holes and adatoms on Si(111)7×7 surface have been observed at a very local area by *Giessibl* using the pure noncontact AFM in ultrahigh vacuum (UHV) [13.33]. It became the breakthrough for the true atomic resolution imaging on a well-defined clean surface using noncontact AFM. Then, Si(111)7×7 [13.34, 35, 45, 47], InP(110) [13.48], and Si(100)2×1 [13.34] surfaces were successively resolved with true atomic resolution. Furthermore, thermally induced motion of atoms or atomic-scale point defects on InP(110) surface have been observed at room temperature [13.48]. In this section, we will describe typical results of atomically resolved noncontact AFM imaging of semiconductor surfaces.

13.2.1 Si(111)7×7 Surface

Figure 13.10 shows the atomic resolution images of the Si(111)7×7 surface [13.49]. Here, Fig. 13.10a (TYPE I) was obtained using the Si tip without dangling, which is covered with an inert oxide layer. Fig. 13.10b (TYPE II) was obtained using the Si tip with dangling bond on which the Si atoms were deposited, due to the mechanical soft contact between the tip and the Si surface. The variable frequency shift mode was used. We can see not only adatoms and corner holes, but also missing adatoms described by the dimer-adatom-stacking fault (DAS) model. We can see that the image contrast in Fig. 13.10b is clearly stronger than that in Fig. 13.10a.

Interestingly, by using the Si tip with dangling bond, we observed contrast between inequivalent halves and between inequivalent adatoms of the 7×7 unit cell. Namely, as shown in Fig. 13.11a, the faulted halves surrounded with a solid line show brighter than the unfaulted halves surrounded with a broken line. Here, the positions of the faulted and unfaulted halves were decided from the step direction. From the cross-sectional profile along the long diagonal of the 7×7 unit cell in Fig. 13.11b, the heights of the corner adatoms are slightly higher than those of the adjacent center adatoms in the faulted and unfaulted halves of the unit cell. The measured corrugations are in the following decreasing order:

Co-F > Ce-F > Co-U > Ce-U ,

where Co-F and Ce-F indicate the corner and center adatoms in faulted halves, and Co-U and Ce-U indicate the corner and center adatoms in unfaulted halves, respectively. As averaging over several units, the corrugation height differences are estimated to be 0.25 Å, 0.15 Å, and 0.05 Å for Co-F, Ce-F, and Co-U, respectively, referring to Ce-U. This tendency, that the heights of the corner adatoms are higher than those of the center adatoms, is consistent with the experimental results using a silicon tip [13.47], although they could not determine faulted and unfaulted halves of the unit cell in the measured AFM images. However, this tendency is completely contrary to the experimental results using a tungsten tip [13.35]. This difference may originate from the difference in the materials of the tip, which seems to affect the interaction between the tip and the reactive sample surface. Another possibility is that the tip is in contact with the surface during the small fraction of the oscillating cycle in their experiments [13.35].

We consider that contrast between inequivalent adatoms is not caused by tip artifacts for the following reasons: 1) Each adatom, corner hole and defect were clearly observed; 2) the apparent heights of adatoms are the same whether they are located adjacent to defects or not; 3) the same contrast in several images for the different tips has been observed.

It should be noted that the corrugation amplitude of adatoms ∼ 1.4 Å in Fig. 13.11b is higher than that of 0.8–1.0 Å obtained with the STM, although the depth of corner holes obtained with noncontact AFM is almost the same as that observed with STM. Besides, in noncontact mode AFM images, the corrugation ampli-



Fig. 13.10a–c Noncontact mode AFM images of Si(111) 7×7 reconstructed surface obtained using the Si tips **(a)** without and **(b)** with dangling bond. The scan area is 99 Å×99 Å. **(c)** The cross sectional profiles along long diagonal of the 7×7 unit cell indicated by *white lines* in **(a)** and **(b)**

Springer Handbook of Nanotechnology
B. Bhushan • © Springer 2004

tude of adatoms was frequently larger than the depth of the corner holes. The origin of such a large corrugation of adatoms may be due to the effect of the chemical interaction, but that is yet unclear.

The atom positions, surface energies, dynamic properties, and chemical reactivities on the Si(111)7 × 7 reconstructed surface have been extensively investigated theoretically and experimentally. From these investigations, the possible origins of the contrast between inequivalent adatoms in AFM images are the following: the true atomic heights that correspond to the adatom core positions, the stiffness (spring constant) of inter-atomic bonding with the adatoms that corresponds to the frequencies of the surface mode, the amount of charge of adatom, and the chemical reactivity of adatoms. Table 13.1 summarizes the decreasing orders of the inequivalent adatoms for individual property. From Table 13.1, we can see that the calculated adatom heights and the stiffness of inter-atomic bonding cannot explain the AFM data, while the amount of charge of adatom and the chemical reactivity of adatoms can explain our data. The contrast due to the amount of charge of adatom means that the AFM image originated from the difference of the vdW, or the electrostatic physical interactions between the tip and the valence electrons at the adatoms. The contrast due to the chemical reactivity of adatoms means that the AFM image originated from the difference of covalent bonding chemical interaction between the atoms at the tip apex and the dangling bond of adatoms. Thus, we can see there are two possible interactions that explain the strong contrast between inequivalent adatoms of the 7 × 7 unit cell observed using the Si tip with dangling bond.

A weak contrast image in Fig. 13.10a is due to vdW and/or electrostatic force interactions. On the other hand, strong contrast images in Figs. 13.10b and 13.11a are due to a covalent bonding formation between the AFM tip with Si atoms and Si adatoms. These results signify the capability of the noncontact mode AFM to image the variation in chemical reactivity of Si adatoms. In the future, by controlling an atomic species at the tip apex, the study of chemical reactivity on an atomic scale will be possible using the noncontact AFM.



Fig. 13.11 **(a)** Noncontact mode AFM image with contrast of unequivalent adatoms and **(b)** a cross-sectional profile indicated by *white line*. The halves of the 7 × 7 unit cell surrounded with *solid line* and *broken line* correspond to faulted and unfaulted halves, respectively. The scan area is 89 Å × 89 Å

13.2.2 Si(100)2×1 and Si(100)2×1:H Monohydride Surfaces

In order to investigate the imaging mechanism of the noncontact AFM, a comparative study between a reactive surface and an insensitive surface using the same tip is very useful. Si(100)2 × 1:H monohydride surface is a Si(100)2 × 1 reconstructed surface that is terminated by a hydrogen atom. It does not reconstruct as metal is deposited on the semiconductor surface. The surface structure hardly changes. Thus, Si(100)2 × 1:H monohydride surface is one of most useful surfaces for a model system to investigate the imaging mechanism, experimentally and theoretically. Furthermore, whether the interaction between a very small atom such as hy-

Table 13.1 Comparison between the adatom heights observed in an AFM image and the variety of properties for inequivalent adatoms

	Decreasing order	Agreement
AFM image	Co−F > Ce−F > Co−U > Ce−U	–
Calculated height	Co−F > Co−U > Ce−F > Ce−U	×
Stiffness of inter-atomic bonding	Ce−U > Co−U > Ce−F > Co−F	×
Amount of charge of adatom	Co−F > Ce−F > Co−U > Ce−U	○
Calculated chemical reactivity	Faulted > Unfaulted	○
Experimental chemical reactivity	Co−F > Ce−F > Co−U > Ce−U	○



Fig. 13.12 **(a)** Noncontact AFM image of a Si(001)2 × 1 reconstructed surface. The scan area was 69 × 46 Å. One 2 × 1 unit cell is outlined with a *box*. *White rows* are superimposed to show the bright spots arrangement. The distance between bright spots on dimer row is 3.2 ± 0.1 Å. Into *white arc*, the alternative bright spots are shown. **(b)** Cross-sectional profile indicated by a *white dotted line*



Fig. 13.13 **(a)** Noncontact AFM image of Si(001)2 × 1-H surface. The scan area was 69 × 46 Å. One 2 × 1 unit cell is outlined with a *box*. *White rows* are superimposed to show the bright spots arrangement. The distance between bright spots on dimer row is 3.5 ± 0.1 Å. **(b)** Cross-sectional profile indicated by a *white dotted line*

drogen and a tip apex is observable with noncontact AFM is interesting. Here, we show noncontact AFM images measured on a Si(100)2 × 1 reconstructed surface with a dangling bond and a Si(100)2 × 1:H monohydride surface with a dangling bond that is terminated by a hydrogen atom [13.50].

Figure 13.12a shows the atomic resolution image of a Si(100)2 × 1 reconstructed surface. The paired bright spots arranged like rows with a 2 × 1 symmetry was observed with clear contrast. Missing pairs of bright spots were observed, as indicated by arrows. Further, pairs of bright spots are shown by the white dashed arc and appear to be the stabilize-buckled asymmetric dimer structure. The distance between paired bright spots is 3.2 ± 0.1 Å.

Figure 13.13a shows the atomic resolution image of a Si(100)2 × 1:H monohydride surface. Paired bright spots arranged like rows were observed. Missing paired bright spots, as well as those paired in rows and single bright spots were observed, as indicated by arrows. The distance between paired bright spots is 3.5 ± 0.1 Å. This distance is 0.2 Å larger than that of a Si(100)2 × 1 reconstructed surface. It was found that the distance between bright spots increases in size due to the hydrogen termination.

The bright spots in Fig. 13.12 do not merely image the silicon atom site, because the distance between bright spots forming the dimer structure of Fig. 13.12a (3.2 ± 0.1 Å) is larger than the distance between silicon atoms of every dimer structure model (2.9 Å is the maximum distance between upper silicons on asymmetric dimer structures). This seems to be due to the contribution to imaging of the chemical bonding interaction between the dangling bond out of the silicon tip apex and the dangling bond on the Si(100)2 × 1 reconstructed surface. The chemical bonding interaction works with strong direction dependence between the dangling bond out of the silicon dimer structure on the Si(100)2 × 1 reconstructed surface and the dangling bond out of the silicon tip apex, and the dimer structure is obtained with a larger distance than between silicons on the surface.

The bright spots of Fig. 13.13 seem to be located at hydrogen atom sites on a Si(100)2 × 1:H monohydride surface, because the distance between bright spots forming the dimer structures (3.5 ± 0.1 Å) agrees approximately with the distance between the hydrogen, i. e., 3.52 Å. Thus, noncontact AFM atomically resolves the individual hydrogen atoms on the topmost layer. On this surface, the dangling bond is terminated by a hydrogen atom, and the hydrogen atom on the topmost layer does not have a chemical reactivity. Therefore, the interaction between the hydrogen atom on the top most layer and the silicon tip apex does not contribute to the chemical bonding interaction with strong direction dependence as in a silicon surface, and the bright spots of a noncontact AFM image correspond to the hydrogen atom sites on the topmost layer.

13.2.3 Metal-Deposited Si Surface

In this section, we will introduce the comparative study of force interaction between a Si tip and a metal deposited Si surface and between a metal adsorbed Si tip and a metal-deposited Si surface [13.51, 52]. As for the metal-deposited Si surface, a Si(111)$\sqrt{3}\times\sqrt{3}$-Ag (hereafter referred to as $\sqrt{3}$-Ag) surface was used.

For the $\sqrt{3}$-Ag surface, the honeycomb-chained trimer (HCT) model has been accepted as the appropriate model. As shown in Fig. 13.14, this structure contains Si trimer at the second layer, 0.75 Å below the Ag trimer at the topmost layer. The topmost Ag atoms and the lower Si atoms form covalent bonds. The inter-atomic distances between the nearest neighbor Ag atoms forming Ag trimer and between lower Si atoms forming Si trimer are 3.43 Å and 2.31 Å, respectively. The apexes of Si trimers and Ag trimers face the $[11\bar{2}]$ direction and the direction tilted a little to the $[\bar{1}\bar{1}2]$ direction, respectively.

In Fig. 13.15, we show the noncontact AFM images measured using a normal Si tip at the frequency shift of (a) −37 Hz, (b) −43 Hz, and (c) −51 Hz, respectively. These frequency shifts correspond to the tip-sample distance of about 0–3 Å. We defined the zero position of tip-sample distance, i.e., the contact point, where the vibration amplitude began to decrease. The rhombus indicates the $\sqrt{3}\times\sqrt{3}$ unit cell. When the tip approached the surface, the contrast of the noncontact AFM images became strong and the pattern remarkably changed. That is, by moving the tip toward the sample surface, the hexagonal pattern, the trefoil-like pattern composed of three dark lines, and the triangle pattern can be observed sequentially. In Fig. 13.15a, the distance between the bright spots is 3.9 ± 0.2 Å. In Fig. 13.15c, the distance



Fig. 13.14 HCT model for the structure of the Si(111)$\sqrt{3}\times\sqrt{3}$-Ag surface. *Black closed circle*, *gray closed circle*, *open circle*, and *closed circle* with *horizontal line* indicate Ag atom at the topmost layer, Si atom at the second layer, Si atom at the third layer, and Si atom at the fourth layer, respectively. *Rhombus* indicates $\sqrt{3}\times\sqrt{3}$ unit cell. *Thick, large solid triangle* indicates an Ag trimer. *Thin, small, solid triangle* indicates a Si trimer



Fig. 13.15a–c Noncontact AFM images obtained at the frequency shifts of **(a)** −37 Hz, **(b)** −43 Hz, and **(c)** −51 Hz on a Si(111)$\sqrt{3}\times\sqrt{3}$-Ag surface. This distance dependence was obtained with the Si tip. Scan area is 38 Å × 34 Å. A *rhombus* indicates $\sqrt{3}\times\sqrt{3}$ unit cell



Fig. 13.16a–c Noncontact AFM images obtained at the frequency shifts of **(a)** −4.4 Hz, **(b)** −6.9 Hz, and **(c)** −9.4 Hz on a Si(111)$\sqrt{3}\times\sqrt{3}$-Ag surface. This distance dependence was obtained with the Ag adsorbed tip. Scan area is 38 Å × 34 Å

between the bright spots is 3.0 ± 0.2 Å, and the direction of the apex of all triangles composed of three bright spots is $[11\bar{2}]$.

In Fig. 13.16, we show the noncontact AFM images measured by using an Ag adsorbed tip at the frequency shift of (a) −4.4 Hz, (b) −6.9 Hz, and (c) −9.4 Hz, respectively. The tip-sample distances Z are roughly estimated to be $Z = 1.9$ Å, 0.6 Å, and ~ 0 Å (in noncontact region), respectively. When the tip approached the surface, the pattern of the noncontact AFM images didn't change, although the contrasts became clearer. A triangle pattern can be observed. The distance between the bright spots is 3.5 ± 0.2 Å. The direction of the apex of all triangles composed of three bright spots is tilted a little from the $[\bar{1}12]$ direction.

Thus, noncontact AFM images measured on a Si(111)$\sqrt{3}\times\sqrt{3}$-Ag surface showed two types of distance dependence of the image patterns, depending on the atom species on the tip apex.

By using the normal Si tip with dangling bond, as in Fig. 13.15a, the measured distance between the bright spot of 3.9 ± 0.2 Å agrees with the distance of 3.84 Å between the center of the Ag trimer in the HCT model within the experimental error. Furthermore, the hexagonal pattern composed of six bright spots also agrees with the honeycomb structure of the Ag trimer in the HCT model. So the most appropriate site corresponding to the bright spots in Fig. 13.15a is the site of the center of the Ag trimers. In Fig. 13.15c, the measured distance of 3.0 ± 0.2 Å between the bright spots forming the triangle pattern does not agree with either the distance between the Si trimer of 2.31 Å or the distance between the Ag trimer of 3.43 Å in the HCT model, while the direction of the apex of triangles composed of three bright spots agrees with the $[11\bar{2}]$ direction of the apex of the Si trimer in the HCT model. So the most appropriate site corresponding to the bright spots in Fig. 13.15c is the intermediate site between Si atoms and Ag atoms. On the other hand, by using the Ag adsorbed tip, the measured distance of 3.5 ± 0.2 Å between the bright spots in Fig. 13.16 agrees with the distance of 3.43 Å between the nearest neighbor Ag atoms forming the Ag trimer at the topmost layer in the HCT model within the experimental error. In addition, the direction of the apex of the triangles composed of three bright spots also agrees with the direction of the apex of the Ag trimer, i. e., tilted $[\bar{1}12]$, in the HCT model. So the most appropriate site corresponding to the bright spots in Fig. 13.16 is the site of individual Ag atoms forming the Ag trimer at the topmost layer.

It should be noted that by using the noncontact AFM with an Ag adsorbed tip the individual Ag atom on the $\sqrt{3}$-Ag surface could be resolved in real space for the first time, although it could not be resolved by using the noncontact AFM with a Si tip. So far, the $\sqrt{3}$-Ag surface has been observed by the scanning tunneling microscope (STM) with atomic resolution. However, the STM can measure the local charge density of state near Fermi level on the surface. From the first principle calculation, it was proven that the unoccupied surface state is densely distributed around the center of the Ag trimer. As a result, bright contrast is obtained at the center of the Ag trimer with the STM.

Finally, we consider the origin of the atomic resolution imaging of the individual Ag atoms on the $\sqrt{3}$-Ag surface. Here, we discuss the difference of the force interactions between the Si and the Ag adsorbed tips. As shown in Fig. 13.17a, by using the Si tip, there is the dangling bond out of the topmost Si atom on the Si tip apex. As a result, the force interaction is dominated by the physical bonding interaction such as Coulomb force far from the surface and by chemical bonding interaction very close to the surface. In other words, if the reactive Si tip with dangling bond approaches the surface, at the distance far from the surface, the Coulomb force acts between the electron localized at the dangling bond out of the topmost Si atom on the tip apex and the positive charge distributed around the center of the Ag trimer. At the distance very close to the surface, the chemical bonding interaction will occur due to the onset of the or-



Fig. 13.17a,b Schematic illustration of **(a)** the Si atom with dangling bond and **(b)** the Ag adsorbed tip above the Si-Ag covalent bond on Si(111)$\sqrt{3}\times\sqrt{3}$-Ag surface

bital hybridization between the dangling bond out of the topmost Si atom on the Si tip apex and the Si-Ag covalent bond on the surface. Hence, the individual Ag atoms will not be resolved, the image pattern will change depending on the tip-sample distance. On the other hand, as shown in Fig. 13.17b, by using an Ag adsorbed tip, the dangling bond localized out of the topmost Si atom on the Si tip apex is terminated by the adsorbed Ag atom. As a result, even at very close tip-sample distance, the force interaction is dominated by the physical bonding interaction such as the vdW force interaction. If the Ag adsorbed tip approaches the surface, the vdW force acts between the Ag atom on the tip apex and Ag or Si atom on the surface. Ag atoms at the topmost layer on the $\sqrt{3}$-Ag surface are located higher than the Si atoms at the lower layer. Hence, the individual Ag atoms (or nearly true topography) will be resolved, and the image pattern will not change even at very close tip-sample distance. It should be emphasized that there is a possibility to identify or recognize atom species on a sample surface using the noncontact AFM if we can control an atomic species at the tip apex.

13.3 Applications to Insulators

Insulators such as alkali halides, fluorides, and metal oxides are key materials in many applications, including optics, microelectronics, catalysis, and so on. Surface properties are important in these technologies, but they are usually poorly understood. This is due to their low conductivity, which makes it difficult to investigate them using electron- and ion-based measurement techniques such as low-energy electron diffraction, ion scattering spectroscopy, and scanning tunneling microscopy (STM). Surface imaging by noncontact atomic force microscopy (NC-AFM) does not require the sample to exhibit high conductivity, because NC-AFM detects a force between the tip on the cantilever and the surface of the sample. Since the first report of atomically resolved NC-AFM on a Si(111) 7×7 surface [13.33], several groups have succeeded in obtaining "true" atomic resolution images of insulators, including defects, and it has been shown that NC-AFM is a powerful new tool for the atomic-scale surface investigation of insulators.

In this section, we will describe typical results of atomically resolved NC-AFM imaging of insulators such as alkali halides, fluorides, and metal oxides. For alkali halides and fluorides, we will focus on the contrast formation, which is the most important issue for interpreting atomically resolved images of binary compounds on the basis of experimental and theoretical results. For the metal oxides, typical examples of atomically resolved imaging will be shown. Also, simultaneous imaging using STM and NC-AFM will be described, and the difference between the STM and NC-AFM images will be demonstrated. Finally, we will describe the results obtained when we imaged an antiferromagnetic NiO(001) surface with a ferromagnetic Fe-coated tip in order to explore the possibility of detecting short-range magnetic interaction using the NC-AFM.

13.3.1 Alkali Halides, Fluorides, and Metal Oxides

The surfaces of alkali halides were the first insulating materials to be imaged by NC-AFM with true atomic resolution [13.53]. Up until now, there have been reports on atomically resolved images of (001) cleaved surfaces for single crystal NaF, RbBr, LiF, KI, NaCl [13.54], KBr [13.55], and thin films of NaCl(001) on Cu(111) [13.56]. In this section, we describe the contrast formation of alkali halides surface on the basis of experimental and theoretical results.

Alkali Halides

In experiments of alkali halides, the symmetry of the observed topographic images indicates that the protrusions exhibit only one type of ions, either positively or negatively charged ions. This leads to the conclusion that the atomic contrast is dominantly caused by electrostatic interactions between a charged atom at the tip apex and the surface ions, i. e., the long-range forces between the macroscopic tip and the sample such as van der Waals force is modulated by an alternating short-range electrostatic interaction of the surface ions. Theoretical work employing the atomistic simulation technique has revealed the mechanism for contrast formation on an ionic surface [13.57]. A significant part of the contrast is due to the displacement of ions in the force field, not only enhancing the atomic corrugations, but also contributing to the electrostatic potential by forming dipoles at the surface. The experimentally observed atomic corrugation height is determined by the interplay of the long- and short-range forces. In the case of NaCl, it has been experimentally demonstrated that a more blunt tip produces a larger corrugation when the tip-sample distance is shorter [13.54]. This result shows that the increased long-range forces induced by a blunt tip allow for more stable imaging closer to the surface. The stronger electrostatic short-range interaction and the larger ion displacement produce a more pronounced atomic corrugation.

At steps and kinks of an NaCl thin film on Cu(111), the amplitude of the atomic corrugations has been observed to increase by up to a factor of two, as large as that of atomically flat terraces [13.56]. This increase in the contrast is due to the low coordination of the step-edge and the kinked ions. The low coordination of the ions results in an enhancement of the electrostatic potential over the site and an increase in the displacement induced by the interaction with the tip. These results demonstrate that the short-range interaction dominates the atomic contrast and leads to a considerable displacement of the surface ions from the ideal position.

Theoretical study predicts that the image contrast depends on the chemical species of the tip apex. *Bennewitz* et al. [13.56] have performed the calculations using an MgO tip terminated by oxygen, an Mg ion, and an OH. The magnitude of the atomic contrast for the Mg-terminated tip shows a slight increase in comparison with an oxygen-terminated tip. The atomic contrast with the oxygen-terminated tip is dominated by the attractive electrostatic interaction between the oxygen on the tip apex and the Na ion, but the Mg-terminated tip attractively interacts with the Cl ion. Also, it has been demonstrated that the magnitude of the contrast for an OH-terminated tip is almost an order of magnitude less than for the oxygen- and Mg-terminated tips.

In order to explore the imaging mechanism for the alkali halides, the heterogeneous surface of NaCl crystal containing $(\mathrm{OCN})^-$ molecules as impurities has been observed by NC-AFM [13.58]. In this case, the atomic periodicity of the NaCl lattice is imaged. However, high-resolution investigations of impurities are limited by the convolution between the tip apex and the molecules at the surface. *Bennewitz* et al. [13.59] reported on the heterogeneous surfaces of alkali halide crystals. In this experiment, which was designed to observe the chemically nonhomogeneous alkali halide surface, a mixed crystal composing of 60% KCl and 40% KBr was used as the sample. In this crystal, which is a so-called solid solution, the Cl and Br ions are mixed randomly. The image of the cleaved $\mathrm{KCl_{0.6}Br_{0.4}}(001)$ surface indicates that only one type of ion is imaged as protrusions as if it were a pure alkali halide crystal. However, there is a significant difference in comparison with the surface of a pure crystal. The amplitude of atomic corrugation varies strongly between the positions of the ions imaged as depressions. This variation in the corrugations corresponds to the constituents of the crystal, i. e., the Cl and Br ions, and it is concluded that the tip apex is negatively charged. Also, it is demonstrated that a comparison between the distribution of the deep depressions and the composition of the mixed crystal assigns the deep depressions to Br ions. Although an evaluation of the effect of the surface buckling induced by a random distribution of anions is needed in order to understand the contrast mechanism, this result demonstrates that NC-AFM measurement exhibits chemical sensitivity on an atomic scale. For applications to alkali halide surfaces, real space imaging with NC-AFM presents the possibility for chemical discrimination at the surface.

Fluorides

Fluorides are important materials for the progress of atomic-scale resolution NC-AFM imaging on insulators. There are reports in the literature of surface images for single crystal $\mathrm{BaF_2}$, $\mathrm{SrF_2}$ [13.60], and $\mathrm{CaF_2}$ [13.61–63]. Surfaces of fluorite-type crystals are prepared by cleaving along the (111) planes. Their structure is more complex than the structure of alkali halides with the NaCl structure. The complexity is of great interest for atomic-resolution imaging using an NC-AFM and also for theoretical predictions of the interpretation of atomic-scale contrast information.

The first atomically resolved images of a $CaF_2(111)$ surface have been obtained in topographic mode [13.62] in which the tip-sample distance is regulated by maintaining a constant frequency shift. In this imaging mode, the surface ions mostly appear as spherical caps. Similar measurements have been performed on the (111) surfaces of SrF_2 and BaF_2.

Barth et al. [13.64] have found that the $CaF_2(111)$ surface images obtained using the constant height mode, in which the frequency shift is recorded with a very low loop gain, can be categorized into two contrast patterns. In the first, the ions appear as triangles, and in the other, they have the appearance of circles, similar to the contrast obtained in a topographic image. These differences are revealed by comparing the cross sections along the [121] direction. Theoretical studies demonstrated that these two different contrast patterns could be explained as a result of imaging with tips of different polarity [13.64–66]. When imaging with a positively charged (cation-terminated) tip, the triangular pattern appears. In this case, the contrast is dominated by the strong short-range electrostatic attraction between the positive tip and the negative F ions. The cross section along the [121] direction of the triangular image shows two maxima: one is a larger peak over the F ions located in the topmost layer, and the other is a smaller peak at the position of the F ions in the third layer. The minima appear at the position of the Ca ions in the second layer. When imaging with a negatively charged (anion-terminated) tip, the spherical image contrast appears, and the main periodicity is created by the Ca ions in the second layer between the topmost and the third F ion layers. In the cross section along the [121] direction, the large maxima correspond to the Ca sites, because of the strong attraction of the negative tip, and the minima appear at the sites of maximum repulsion over the F ions in the first layer. At a position between two F ions, there are smaller maxima. This reflects the weaker repulsion over the third layer F ion sites compared to the protruding topmost F ion sites and a slower decay in the contrast on one side of the Ca ions. These results demonstrate that the image contrast of a $CaF_2(111)$ surface depends on the state of the tip apex.

The triangular pattern obtained with a positively charged tip appears at relatively large tip-sample distance, as shown in Fig. 13.18a. On the cross section along the [121] direction, experimental results and theoretical studies both demonstrate the large peak and small shoulder characteristic for the triangular pattern image (Fig. 13.18d). When the tip approaches the surface more closely, the triangular pattern of the experimental images is more vivid (Fig. 13.18b), just as predicted in the theoretical works. On the cross section along the [121] direction, as the tip approaches, the amplitude of the shoulder increases until it is equal to that of the main peak, and this feature gives rise to the honeycomb pattern image, as shown Fig. 13.18c. These results demonstrate that there is a more complex process of image contrast formation. Also, from detailed theoretical analysis of the electrostatic potential [13.67], it is suggested that the change in displacement of the ions due to the proximity of the tip plays an important role in the formation of the image contrast. Such a drastic change in image contrast, depending on both the polarity of the terminated tip atom and the tip-sample distance, is inherent in



Fig. 13.18 **(a)**–**(c)** $CaF_2(111)$ surface images obtained by using the constant height mode. From **(a)** to **(c)** the frequency shift was lowered. The *white lines* represent the positions of the cross section. **(d)**–**(f)** The cross section extracted from the Fourier-filtered images of **(a)**–**(c)**. The *white* and *black arrows* represent the scanning direction. The images and the cross sections are from [13.64]

the fluoride (111) surface, and this image contrast feature cannot be seen on the (001) surface of alkali halides with a simple crystal structure.

These results have demonstrated that there is good agreement between experiment and theory. However, the results of careful experiments show another feature: The cross sections in the forward and backward scan directions do not yield identical results [13.64]. Also, it is shown that the structures of cross sections taken along the three equivalent [121] directions are different. It is thought that this can be attributed to the asymmetry of the nano-cluster at the tip apex, which leads to different interactions in the equivalent directions. A better understanding of the asymmetric image contrast may require a more complicated modeling of the tip structure. However, the most desirable solution would be the development of the suitable techniques for well-defined tip preparation. In fact, it should be mentioned that perfect tips on an atomic scale can occasionally be obtained. These tips do yield identical results in forward and backward scanning, and cross sections in the three equivalent directions taken with this tip are almost identical [13.68].

The fluoride (111) surface is an excellent standard surface for calibrating tips on an atomic scale. The polarity of the tip-terminated atom can be determined from the image contrast pattern (spherical or triangular pattern). The irregularities in the tip structure can be detected, since the surface structure is highly symmetric. Therefore, once such a tip has been prepared, it can be used as a calibrated tip for imaging unknown surfaces.

The states of the tip apex play an important role in interpreting NC-AFM images of alkali halide and fluoride surfaces. It is expected that the achievement of a good correlation between experimental and theoretical studies will help advance surface imaging for insulators by NC-AFM.

Metal Oxides

Most of the metal oxides that have attracted strong interest for their technological importance are insulative. Therefore, in the case of atomically resolved imaging of metal oxide surfaces by STM, efforts to increase the conductivity of the sample are needed, for example, the introduction of defects of anions or cations, doping with other atoms, and surface observations during heating of the sample. However, in principle, NC-AFM provides the possibility of observing nonconductive metal oxides without these efforts. In cases where the conductivity of the metal oxides is high enough for a tunneling current to flow, it should be noted that most of the surface images obtained by NC-AFM and STM are not identical.

Since the first report of atomically resolved images on a $TiO_2(110)$ surface with oxygen point defects [13.69], they have also been reported on $TiO_2(100)$ [13.70–72], $SnO_2(110)$ [13.73], NiO(001) [13.74, 75], $SrTiO_3(100)$ [13.76], and $CeO_2(111)$ [13.77] surfaces. Also, *Barth* et al. [13.78] have succeeded in obtaining atomically resolved NC-AFM images of a clean α-$Al_2O_3(0001)$ surface, which is impossible to investigate using STM. In this section, we describe typical results of the imaging of metal oxides by NC-AFM.

The α-$Al_2O_3(0001)$ surface exists in several ordered phases that can be reversibly transformed into each other by thermal treatments and oxygen exposure. It is known that the high temperature phase has a large $(\sqrt{31}\times\sqrt{31})R\pm 9°$ unit cell. However, the details of the atomic structure of this surface have not been revealed, and two models are proposed from the results of low-energy electron diffraction and X-ray diffraction studies. Recently, *Barth* et al. [13.78] have directly observed this reconstructed α-$Al_2O_3(0001)$ surface by NC-AFM. They confirmed that the dominant contrast of the low magnification image corresponds to a rhombic grid representing a unit cell of $(\sqrt{31}\times\sqrt{31})R+9°$, as shown in Fig. 13.19a. Also, more details of atomic structures are determined from the higher magnification image (Fig. 13.19b), which was taken at a reduced tip-sample distance. In this atomically resolved image, it is revealed that each side of the rhombus is intersected by 10 atomic rows, and that a hexagonal arrangement of atoms exists in the center of the rhombi (Fig. 13.19c). This feature agrees with the proposed surface structure that predicts order in the center of hexagonal surface domains and disorder at the domain boundaries. Their result is an excellent demonstration of the capabilities of the NC-AFM as a powerful tool for the atomic-scale surface investigation of insulators.

In addition, *Barth* et al. [13.78] have performed observations of the $Al_2O_3(0001)$ surface when it is exposed to water and hydrogen. It is suggested that the region of atomic disorder has an extremely high reactivity. Such investigations of the surface structure of adsorbed insulator substrates can only be provided by NC-AFM. The NC-AFM imaging of metal growth on oxides [13.79] has also been reported. A description of the adsorbed molecular arrangement on a TiO_2 surface can be found in the next section.

The atomic structure of $SrTiO_3(100)$-$(\sqrt{5}\times\sqrt{5})$ $R26.6°$ surface, as well as that of $Al_2O_3(0001)$-$(\sqrt{31}\times\sqrt{31})R\pm 9°$ can be determined on the basis of



Fig. 13.19 **(a)** Image of the high temperature, reconstructed clean α-Al_2O_3 surface obtained by using the constant height mode. The *rhombus* represents the unit cell of the $(\sqrt{31}\times\sqrt{31})R+9°$ reconstructed surface. **(b)** Higher magnification image of **(a)**. Imaging was performed at a reduced tip-sample distance. **(c)** Schematic representation of the indicating regions of hexagonal order in the center of reconstructed rhombi. **(d)** Superposition of the hexagonal domain with reconstruction rhombi found by NC-AFM imaging. Atoms in *gray shaded regions* are well-ordered. The images and the schematic representations are from [13.78]

the results of NC-AFM imaging [13.76]. $SrTiO_3$ is one of the perovskite oxides and its (100) surface exhibits the many different kinds of reconstructed structures. In the case of the $(\sqrt{5}\times\sqrt{5})R26.6°$ reconstruction, the oxygen vacancy-Ti^{3+}-oxygen model (where the terminated surface is TiO_2 and the observed spots are related to oxygen vacancies) was proposed from the results of STM imaging. As shown in Fig. 13.20, *Kubo* et al. [13.76] have performed measurements using both STM and NC-AFM and have found that the size of the bright spots, as observed by NC-AFM, is always smaller than that for STM measurement and that the dark spots, which are not observed by STM, are arranged along the [001] and [010] directions in the NC-AFM image. A theoretical simulation of the NC-AFM image using first-principles calculations shows that the bright and dark spots correspond to Sr and oxygen atoms, respectively. It has been proposed that the structural model of the reconstructed surface consists of an ordered Sr adatom located at the oxygen fourfold site on the TiO_2-terminated layer (Fig. 13.20c).

Because STM images are related to the spatial distribution of the wave functions near the Fermi level, atoms, which do not have a local density of states near the Fermi level, are generally invisible even on the conductive materials. On the other hand, the NC-AFM image reflects the strength of the tip-sample interaction force originating from chemical, electrostatic interactions, and so on. Therefore, even STM and NC-AFM images obtained using an identical tip and sample will generally differ.

Simultaneous imaging of a $TiO_2(110)$ surface with STM and NC-AFM shows a typical result that differs in terms of the atoms that are visualized [13.72]. For simultaneous imaging, the tip-sample distance is controlled by keeping a constant frequency shift, and the tunneling current between the oscillating cantilever and the surface is measured. The two images show different atomic contrasts, i. e., the atomic corrugation of the



Fig. 13.20 **(a)** STM and **(b)** NC-AFM images of a $SrTiO_3(100)$ surface. **(c)** A proposed model of the $SrTiO_3(100)$-$(\sqrt{5}\times\sqrt{5})R26.6°$ surface reconstruction. The images and the schematic representations are from [13.76]

STM image is in antiphase in the (1×1) and in phase in the (1×2) with respect to the NC-AFM image. In the (1×1), the STM image shows that the dangling bond states at the tip apex overlap with the dangling bonds of the $3d$ states that are protruding from the Ti atom, while the NC-AFM primarily imaged the uppermost oxygen atom. The results of $SrTiO_3$ and TiO_2 surface imaging show that the information obtained by STM and NC-AFM differ, and that the simultaneous imaging of a metal oxide surface enables the investigation of a more detailed surface structure.

13.3.2 Atomically Resolved Imaging of a NiO(001) Surface

The transition metal oxides such as NiO, CoO, and FeO feature the simultaneous existence of an energy gap and unpaired electrons, which gives rise to magnetic properties. Such magnetic insulators are widely used for the exchange biasing in spin valve devices. The NC-AFM enables the direct surface imaging of magnetic insulators on an atomic scale. The forces detected by NC-AFM originate from several kinds of interaction between the surface and the tip, including magnetic interactions in some cases. Theoretical studies predict that short-range magnetic interactions such as the exchange interaction should enable the NC-AFM to image magnetic moments on an atomic scale. In this section, we will describe an imaging of the antiferromagnetic NiO(001) surface using a ferromagnetic Fe-coated tip in order to explore the detection of the short-range magnetic interaction. Also, theoretical studies of the exchange force interaction between a magnetic tip and a sample will be described.

Theoretical Studies of the Exchange Force

The NC-AFM measures various kinds of interaction between tip and sample such as van der Waals, and electrostatic and short-range chemical interactions. In the case of a magnetic tip and sample, the interaction detected by the NC-AFM includes the long-range magnetic dipole interaction and the short-range magnetic interaction. The short-range magnetic interaction between the atoms at the tip apex and the sample surface is governed by a combination of the Coulomb interaction and the Pauli exclusion principle and may be included among the short-range chemical interactions. The magnetic interaction energy depends on the electron spin state of the atoms, and the energy difference in spin alignments (parallel or anti-parallel) is referred to as the exchange interaction energy. Therefore, if the short-range magnetic interaction can be detected, an atomically resolved NC-AFM image, in which the short-range interaction contributes to the atomic protrusions, should reveal the local energy difference in the spin alignment.

In the past, extensive theoretical studies on the short-range magnetic interaction between a ferromagnetic tip and a ferromagnetic sample have been performed by a simple calculation [13.80], a tight-binding approximation [13.81], and first-principles calculations [13.82]. In the calculations performed by *Nakamura* et al. [13.82], three-atomic-layer Fe(001) films, which are separated by a vacuum gap, are used as a model for the tip and sample. The exchange force (F_{ex}) is defined as the difference of the forces (F_P, F_{AP}) in each spin configuration (parallel: P, anti-parallel: AP) of the tip and sample. The tip-sample distance dependency of the exchange force demonstrates that the amplitude of the exchange force is on the order of 10^{-10} N or above and is large enough to be detected by NC-AFM. Also, the site dependency of the exchange force indicates that the discrimination of the exchange force enables the direct imaging of the magnetic moments on an atomic scale. Recently, the interaction between a spin-polarized H atom and a Ni atom on a NiO(001) surface has been investigated theoretically [13.83]. *Foster* and *Shluger* demonstrated that the difference in magnitude of the exchange interaction between opposite spin Ni ions in a NiO surface could be sufficient to be measured in a low temperature NC-AFM experiment. Also, in order to investigate the effect of surface relaxation, they calculated the interaction of different metal tips with the MgO surface used as a model system. The results indicated that the interaction over the oxygen site is stronger than that over the Mg site, and it was pointed out that the tips should be coated in metals that interact weakly with the surface for the detection of the exchange interaction between the atom at the tip apex and the Ni atom on the NiO surface. However, we must take into account another possibility, that is, that a metal atom at the ferromagnetic tip apex may interact with a Ni atom on the second layer through a magnetic interaction mediated by the electrons in an oxygen atom on the surface.

13.3.3 Atomically Resolved Imaging Using Noncoated and Fe-Coated Si Tips

It is thought that the magnetic insulator NiO is one of the best candidates for detecting short-range magnetic interactions such as the exchange interaction, because an experimental configuration of a ferromagnetic tip and an antiferromagnetic sample minimizes the long-range magnetic dipole interaction that might hinder the detection of the short-range interaction.

Below the Néel temperature of 525 K, NiO is antiferromagnetic and has a rhombohedral structure contracted along the $\langle 111 \rangle$ axes. The direction of the spin on nickel atoms in the same $\{111\}$ plane is parallel, a so-called ferromagnetic sheet. The direction of spin in the adjacent $\{111\}$ planes is anti-parallel. As a result, the spins at the Ni atoms on the (001) surface are arranged in a checkerboard pattern, i. e., the spin alignment along the $\langle 111 \rangle$ direction is antiferromagnetic in order and that along the $\langle 1\,{-1}\,0 \rangle$ direction is ferromagnetic in order.

Figure 13.21a shows an atomically resolved image of a NiO(001) surface with a ferromagnetic Fe-coated tip [13.84]. The bright protrusions correspond to atoms spaced about 0.42 nm apart, consistent with the expected periodic arrangement of the NiO(001) surface. The corrugation amplitude is typically 30 pm, which is comparable to the value previously reported [13.74, 75], as shown in Fig. 13.21b. Also, because of the symmetry of the image, it was concluded that only one type of atom is visualized by NC-AFM. However, from this image, we think that it is difficult to distinguish which of the atoms are observed, oxygen or nickel. The theoretical works indicate that a metal tip interacts strongly with the oxygen atoms on the MgO(001) surface [13.83]. From this result, it is presumed that the bright protrusions correspond to the oxygen atoms. However, it is still questionable which of the atoms are visible with a Fe-coated tip.



Fig. 13.21 **(a)** Atomically resolved image obtained with an Fe-coated tip. **(b)** shows the cross sections of the middle part in **(a)**. Their corrugations are about 30 pm

If the short-range magnetic interaction is included in the interactions detected by NC-AFM, the corrugation amplitude of the atoms should depend on the direction of the spin at the atom-site. The results of a comparison of the corrugation amplitudes of the same species of atoms with opposite spin can reveal the difference in the short-range magnetic interaction, because the nonmagnetic interactions peculiar to a particular atomic species should be identical. From the results of first-principles calculations [13.82], the contribution of the short-range magnetic interaction to the measured corrugation amplitude is expected to be about a few percent of the total interaction. Discrimination of such small perturbations is therefore needed. In order to reduce the noise, the corrugation amplitude was added on the basis of the periodicity of the NC-AFM image. In addition, the topographical asymmetry, which is the index characterizing the difference in atomic corrugation amplitude, has been defined [13.85]. The result shows that the value of the topographical asymmetry calculated from the image obtained with an Fe-coated Si tip depends on the direction of summing of the corrugation amplitude, and that the dependency corresponds to the antiferromagnetic spin ordering of the NiO(001) surface. With a paramagnetic Si tip, no significant indication of a directional dependency of the topographical asymmetry can be seen. Therefore, it is believed that the results obtained using a Fe-coated tip support the conclusion that the dependency of the topographical asymmetry originates in the short-range magnetic interaction.

The measurements presented here demonstrate the possibility of imaging magnetic structures on an atomic scale by NC-AFM. However, the origin of the detected short-range magnetic interaction is under discussion. Therefore, further experiments such as the measurement of force-distance curves and a theoretical study of the interaction between the ferromagnetic tip and an antiferromagnetic sample are needed.

13.4 Applications to Molecules

In the future, it is expected that electronic, chemical, and medical devices will be downsized to a nanoscale. To achieve this, visualizing and assembling individual molecular components is of fundamental importance. Topographic imaging of nonconductive materials is a challenge for atomic force microscopy (AFM). Nanometer-sized domains of surfactants terminated with different functional groups have been identified by lateral force microscopy (LFM) [13.88] and chemical force microscopy (CFM) [13.89] as extensions of AFM. At a higher resolution, a periodic array of molecules, Langmuir–Blodgett films [13.90] for example, was recognized by AFM. However, it remains difficult to visualize an isolated molecule, molecule vacancy, or the boundary of different periodic domains with a microscope with the tip in contact.

13.4.1 Why Molecules and What Molecules?

The access to individual molecules has not been a trivial task even for noncontact atomic force microscopy (NC-AFM). The force pulling the tip into the surface is less sensitive to the gap width (r), especially when chemically stable molecules cover the surface. The attractive potential between two stable molecules is shallow and exhibits r^{-6} decay [13.13].



Fig. 13.23 The constant frequency-shift topography of a DNA helix on a mica surface based on [13.87]. Image size: $43 \times 43\,\text{nm}^2$. The image revealed features with a spacing of 3.3 nm, consistent with the helix turn of B-DNA

High-resolution topography of formate ($HCOO^-$) [13.91] was first reported in 1997 as a molecular adsorbate. The number of imaged molecules is now increasing because of the technological importance of molecular interfaces. To date, the following studies on molecular topography have been published: C_{60} [13.86, 92], DNAs [13.87, 93], adenine and thymine [13.94], alkanethiols [13.94, 95], a perylene-derivative (PTCDA) [13.96], a metal porphyrin (Cu-TBPP) [13.97], glycine sulfate [13.98], polypropylene [13.99], vinylidene fluoride [13.100], and a series of carboxylates ($RCOO^-$) [13.101–107]. Two of these are presented in Figs. 13.22 and 13.23 to demonstrate the current stage of achievement. The proceedings of the annual NC-AFM conference represent a convenient opportunity for us to update the list of molecules imaged.



Fig. 13.22 The constant frequency-shift topography of domain boundaries on a C_{60} multilayered film deposited on a Si(111) surface based on [13.86]. Image size: $35 \times 35\,\text{nm}^2$

13.4.2 Mechanism of Molecular Imaging

A systematic study on carboxylate ($RCOO^-$) with $R = H$, CH_3, $C(CH_3)_3$, $C \equiv CH$, and CF_3 revealed that the van der Waals force is responsible for the molecule-dependent microscope topography despite its long-range (r^{-6}) nature. Carboxylates adsorbed on the (110) sur-



Fig. 13.24a,b The carboxylates and TiO_2 substrate. **(a)** Top and side view ball model. *Small shaded* and *large shaded balls* represent Ti and O atoms in the substrate. Protons yielded in the dissociation reaction are not shown. **(b)** Atom geometry of formate, acetate, pivalate, propiolate, and trifluoroacetate adsorbed on the $TiO_2(110)$ surface. The O-Ti distance and O – C – O angle of the formate were determined in the quantitative analysis of photoelectron diffraction [13.109]

face of rutile TiO_2 have been extensively studied as a prototype of organic materials interfaced with an inorganic metal oxide [13.108]. A carboxylic acid molecule (RCOOH) dissociates on this surface to a carboxylate ($RCOO^-$) and a proton (H^+) at room temperature, as illustrated in Fig. 13.24. The pair of negatively charged oxygen atoms in $RCOO^-$ coordinate two positively charged Ti atoms at the surface. The adsorbed carboxylates create a long-range ordered monolayer. The lateral distances of the adsorbates in the ordered monolayer are regulated at 0.65 and 0.59 nm along the [1$\bar{1}$0] and [001] directions. By scanning a mixed monolayer containing different carboxylates, the microscope topography of the terminal groups can be quantitatively compared while minimizing tip-dependent artifacts.

Figure 13.25 presents the observed constant frequency-shift topography of four carboxylates terminated by different alkyl groups. On the formate-covered surface of panel (a) individual formates (R = H) were resolved as protrusions of a uniform brightness. The dark



Fig. 13.25a–d The constant frequency-shift topography of carboxylate monolayers prepared on the $TiO_2(110)$ surface based on [13.102, 104, 106]. Image size: $10 \times 10\,nm^2$. **(a)** Pure formate monolayer; **(b)** formate-acetate mixed layer; **(c)** formate-pivalate mixed layer; **(d)** formate-propiolate mixed layer. Cross sections determined on the *lines* are shown in the lower panel

holes represent unoccupied surface sites. The cross section in the lower panel shows that the accuracy of the height measurement was 0.01 nm or better. Brighter particles appeared in the image when the formate monolayer was exposed to acetic acid (CH_3COOH), as shown in panel (b). Some formates were exchanged with acetates ($R = CH_3$) impinging from the gas phase [13.110]. Because the number of brighter spots increased with exposure time to acetic acid, the brighter particle was assigned to the acetate [13.102]. Twenty-nine acetates and 188 formates were identified in the topography. An isolated acetate and its surrounding formates exhibited an image height difference of 0.06 nm. Pivalate is terminated by bulky $R = C(CH_3)_3$. Nine bright pivalates were surrounded by formates of ordinary brightness in the image of panel (c) [13.104]. The image height difference of an isolated pivalate over the formates was 0.11 nm. Propiolate with $C \equiv CH$ is a needle-like adsorbate of single-atom diameter. That molecule exhibited in panel (d) a microscope topography 0.20 nm higher than that of the formate [13.106].

The image topography of formate, acetate, pivalate, and propiolate followed the order of the size of the alkyl groups. Their physical topography can be assumed on the C−C and C−H bond lengths in the corresponding RCOOH molecules in the gas phase [13.111] and is illustrated in Fig. 13.24. The top hydrogen atom of the formate is located 0.38 nm above the surface plane containing the Ti atom pair, while three equivalent hydrogen atoms of the acetate are more elevated at 0.46 nm. The uppermost H atoms in the pivalate are raised by 0.58 nm relative to the Ti plane. The H atom terminating the triple-bonded carbon chain in the propiolate is at 0.64 nm. Figure 13.26 summarizes the observed image heights relative to the formate as a function of the physical height of the topmost H atoms given in the model. The straight line fitted the four observations [13.104]. When the horizontal axis was scaled with other properties (molecular weight, the number of atoms in a molecule, or the number of electrons in valence states), the correlation became poor.

On the other hand, if the tip apex traced the contour of a molecule composed of hard-sphere atoms, the image topography would reproduce the physical topography in a one-to-one ratio, as shown by the broken line in Fig. 13.26. However, the slope of the fitted line was 0.7. A slope of less than unity is interpreted with the long-range nature of the tip-molecule force. The observable frequency shift reflects the sum of the forces between the tip apex and individual molecules. When the tip passes above a tall molecule embedded in short molecules, it is pulled up to compensate for the increased force originating from the tall molecule. Forces between the lifted tip and the short molecules are reduced due to the increased tip-surface distance. Feedback regulation pushes down the probe to restore the lost forces.



Fig. 13.26 The constant frequency-shift topography of the alkyl-substituted carboxylates as a function of their physical topography given in the model of Fig. 13.3 based on [13.104]

This picture predicts that microscope topography is sensitive to the lateral distribution of the molecules, and that was in fact the case. Two-dimensionally clustered acetates exhibited enhanced image height over an isolated acetate [13.102]. The tip-molecule force, therefore, remained non-zero at distances over the lateral separation of the carboxylates on this surface (0.59–0.65 nm). Chemical bond interactions cannot be important across such a wide tip-molecule gap, whereas atom-scale images of Si(111)-(7×7) are interpreted with the fractional formation of tip-surface chemical bonds [13.24, 45, 49]. Instead, the attractive component of the van der Waals force is probable for the observed molecule-dependent topography. The absence of the tip-surface chemical bond is reasonable on the carboxylate-covered surface terminated with stable C−H bonds.

The attractive component of the van der Waals force contains electrostatic terms caused by permanent-dipole/permanent-dipole coupling, permanent-dipole/induced-dipole coupling, and induced-dipole/induced-dipole coupling (dispersion force). The four carboxylates examined are equivalent in terms of their permanent electric dipole, because the alkyl groups are nonpolar. The image contrast of one carboxylate relative to another is thus ascribed to the dispersion force and/or the force created by the coupling between the permanent dipole on the tip and the induced dipole on the molecule. If we further assume that the Si tip used exhibits the smallest permanent dipole, the dispersion force remains dominant to create the NC-AFM topography dependent on the nonpolar groups of atoms. A numerical simulation on this assumption [13.106] successfully reproduced the propiolate topography of Fig. 13.25d. A calculation that does not include quantum chemical treatments is expected to work, unless the tip approaches the surface too closely, or the molecule possesses a dangling bond.

In addition to the contribution of the dispersion force, the permanent dipole moment of molecules may perturb the microscope topography through electrostatic coupling with the tip. Its possible role was demonstrated by imaging a fluorine-substituted acetate. The strongly polarized C−F bonds were expected to perturb the electrostatic field over the molecule. The constant frequency-shift topography of acetate ($\mathrm{R} = \mathrm{CH_3}$) and trifluoroacetate ($\mathrm{R} = \mathrm{CF_3}$) was indeed sensitive to the fluorine substitution. The acetate was observed 0.05 nm higher than the trifluoroacetate [13.103], although the F atoms in the trifluoroacetate, as well as the H atoms in the acetate were lifted by 0.46 nm from the surface plane, as illustrated in Fig. 13.24.

13.4.3 Perspectives

Experimental results summarized in this section prove the feasibility of NC-AFM in identifying individual molecules. A systematic study on the constant frequency-shift topography of carboxylates with $\mathrm{R} = \mathrm{H}$, $\mathrm{CH_3}$, $\mathrm{C(CH_3)_3}$, $\mathrm{C{\equiv}CH}$, and $\mathrm{CF_3}$ has revealed the mechanism behind the high-resolution imaging of the chemically stable molecules. The dispersion force is primarily responsible for the molecule-dependent topography. The permanent dipole moment of the imaged molecule, if it exists, perturbs the topography through the electrostatic coupling with the tip. A tiny calculation containing empirical force fields works in simulating the microscope topography.

These results make us optimistic about analyzing physical and chemical properties of nanoscale supramolecular assemblies constructed on a solid surface. If the accuracy of topographic measurement is developed by one more order of magnitude, which is not an unrealistic concept, it may be possible to identify structural isomers, chiral isomers, and conformational isomers of a molecule. Kelvin probe force microscopy (KPFM), an extension of NC-AFM, provides a nanoscale analysis of molecular electronic properties [13.99, 100]. Force spectroscopy with chemically modified tips seems promising for the detection of a selected chemical force. Operation in a liquid atmosphere [13.112] is demanded to observe biochemical materials in the raw.

References

13.1 G. Binnig: Atomic force microscope and method for imaging surfaces with atomic resolution, US Patent 4,724,318 (1986)

13.2 G. Binnig, C. F. Quate, C. Gerber: Atomic force microscope, Phys. Rev. Lett. **56** (1986) 930–933

13.3 G. Binnig, H. Rohrer, C. Gerber, E. Weibel: Surface studies by scanning tunneling microscopy, Phys. Rev. Lett. **49** (1982) 57–61

13.4 G. Binnig, H. Rohrer: The scanning tunneling microscope, Sci. Am. **253** (1985) 50–56

13.5 G. Binnig, H. Rohrer: In touch with atoms, Rev. Mod. Phys. **71** (1999) S324–S320

13.6 C. J. Chen: *Introduction to Scanning Tunneling Microscopy* (Oxford Univ. Press, Oxford 1993)

13.7 H.-J. Güntherodt, R. Wiesendanger (Eds.): *Scanning Tunneling Microscopy I–III* (Springer, Berlin, Heidelberg 1991)

13.8 J. A. Stroscio, W. J. Kaiser (Eds.): *Scanning Tunneling Microscopy* (Academic, Boston 1993)

13.9 R. Wiesendanger: *Scanning Probe Microscopy and Spectroscopy: Methods and Applications* (Cambridge Univ. Press, Cambridge 1994)

13.10 S. Morita, R. Wiesendanger, E. Meyer (Eds.): *Noncontact Atomic Force Microscopy* (Springer, Berlin, Heidelberg 2002)

13.11 R. Garcia, R. Perez: Dynamic atomic force microscopy methods, Surf. Sci. Rep. **47** (2002) 197–301

13.12 F. J. Giessibl: Advances in atomic force microscopy, Rev. Mod. Phys. **75** (2003) 949–983

13.13 J. Israelachvili: *Intermolecular and Surface Forces*, 2nd edn. (Academic, London 1992)

13.14 L. Olsson, N. Lin, V. Yakimov, R. Erlandsson: A method for *in situ* characterization of tip shape in ac-mode atomic force microscopy using electrostatic interaction, J. Appl. Phys. **84** (1998) 4060–4064

13.15 S. Akamine, R. C. Barrett, C. F. Quate: Improved atomic force microscopy images using cantilevers with sharp tips, Appl. Phys. Lett. **57** (1990) 316–318

13.16 T. R. Albrecht, S. Akamine, T. E. Carver, C. F. Quate: Microfabrication of cantilever styli for the atomic force microscope, J. Vac. Sci. Technol. A **8** (1990) 3386–3396

13.17 M. Tortonese, R. C. Barrett, C. Quate: Atomic resolution with an atomic force microscope using piezoresistive detection, Appl. Phys. Lett. **62** (1993) 834–836

13.18 O. Wolter, T. Bayer, J. Greschner: Micromachined silicon sensors for scanning force microscopy, J. Vac. Sci. Technol. **9** (1991) 1353–1357

13.19 D. Sarid: *Scanning Force Microscopy*, 2nd edn. (Oxford Univ. Press, New York 1994)

13.20 F. J. Giessibl, B. M. Trafas: Piezoresistive cantilevers utilized for scanning tunneling and scanning force microscope in ultrahigh vacuum, Rev. Sci. Instrum. **65** (1994) 1923–1929

13.21 P. Güthner, U. C. Fischer, K. Dransfeld: Scanning near-field acoustic microscopy, Appl. Phys. B **48** (1989) 89–92

13.22 K. Karrai, R. D. Grober: Piezoelectric tip-sample distance control for near field optical microscopes, Appl. Phys. Lett. **66** (1995) 1842–1844

13.23 F. J. Giessibl: High-speed force sensor for force microscopy and profilometry utilizing a quartz tuning fork, Appl. Phys. Lett. **73** (1998) 3956–3958

13.24 F. J. Giessibl, S. Hembacher, H. Bielefeldt, J. Mannhart: Subatomic features on the silicon (111)-(7 × 7) surface observed by atomic force microscopy, Science **289** (2000) 422–425

13.25 F. Giessibl, C. Gerber, G. Binnig: A low-temperature atomic force/scanning tunneling microscope for ultrahigh vacuum, J. Vac. Sci. Technol., B **9** (1991) 984–988

13.26 F. Ohnesorge, G. Binnig: True atomic resolution by atomic force microscopy through repulsive and attractive forces, Science **260** (1993) 1451–1456

13.27 F. J. Giessibl, G. Binnig: True atomic resolution on KBr with a low-temperature atomic force microscope in ultrahigh vacuum, Ultramicroscopy **42-44** (1992) 281–286

13.28 S. P. Jarvis, H. Yamada, H. Tokumoto, J. B. Pethica: Direct mechanical measurement of interatomic potentials, Nature **384** (1996) 247–249

13.29 L. Howald, R. Lüthi, E. Meyer, P. Guthner, H.-J. Güntherodt: Scanning force microscopy on the Si(111)7 × 7 surface reconstruction, Z. Phys. B **93** (1994) 267–268

13.30 L. Howald, R. Lüthi, E. Meyer, H.-J. Güntherodt: Atomic-force microscopy on the Si(111)7 × 7 surface, Phys. Rev. B **51** (1995) 5484–5487

13.31 Y. Martin, C. C. Williams, H. K. Wickramasinghe: Atomic force microscope – force mapping and profiling on a sub 100 Å scale, J. Appl. Phys. **61** (1987) 4723–4729

13.32 T. R. Albrecht, P. Grutter, H. K. Horne, D. Rugar: Frequency modulation detection using high-Q cantilevers for enhanced force microscope sensitivity, J. Appl. Phys. **69** (1991) 668–673

13.33 F. J. Giessibl: Atomic resolution of the silicon (111)-(7 × 7) surface by atomic force microscopy, Science **267** (1995) 68–71

13.34 S. Kitamura, M. Iwatsuki: Observation of silicon surfaces using ultrahigh-vacuum noncontact atomic force microscopy, Jpn. J. Appl. Phys. **35** (1995) L668–L671

13.35 R. Erlandsson, L. Olsson, P. Martensson: Inequivalent atoms and imaging mechanisms in ac-mode atomic-force microscopy of Si(111)7 × 7, Phys. Rev. B **54** (1996) R8309–R8312

13.36 N. Burnham, R. J. Colton: Measuring the nanomechanical and surface forces of materials using an atomic force microscope, J. Vac. Sci. Technol. A **7** (1989) 2906–2913

13.37 D. Tabor, R. H. S. Winterton: Direct measurement of normal and retarded van der Waals forces, Proc. R. Soc. London A **312** (1969) 435

13.38 F. J. Giessibl: Forces and frequency shifts in atomic resolution dynamic force microscopy, Phys. Rev. B **56** (1997) 16010–16015

13.39 G. Binnig, H. Rohrer, C. Gerber, E. Weibel: 7 × 7 reconstruction on Si(111) resolved in real space, Phys. Rev. Lett. **50** (1983) 120–123

13.40 H. Goldstein: *Classical Mechanics* (Addison Wesley, Reading 1980)

13.41 U. Dürig: Interaction sensing in dynamic force microscopy, New J. Phys. **2** (2000) 5.1–5.12

13.42 F. J. Giessibl: A direct method to calculate tip-sample forces from frequency shifts in frequency-modulation atomic force microscopy, Appl. Phys. Lett. **78** (2001) 123–125

13.43 U. Dürig, H. P. Steinauer, N. Blanc: Dynamic force microscopy by means of the phase-controlled oscillator method, J. Appl. Phys. **82** (1997) 3641–3651

13.44 F. J. Giessibl, H. Bielefeldt, S. Hembacher, J. Mannhart: Calculation of the optimal imaging parameters for frequency modulation atomic force microscopy, Appl. Surf. Sci. **140** (1999) 352–357

13.45 M. A. Lantz, H. J. Hug, R. Hoffmann, P. J. A. van Schendel, P. Kappenberger, S. Martin, A. Baratoff, H.-J. Güntherodt: Quantitative measurement of short-range chemical bonding forces, Science **291** (2001) 2580–2583

13.46 F. J. Giessibl, M. Herz, J. Mannhart: Friction traced to the single atom, Proc. Nat. Acad. Sci. USA **99** (2002) 12006–12010

13.47 N. Nakagiri, M. Suzuki, K. Oguchi, H. Sugimura: Site discrimination of adatoms in Si(111)-7 × 7 by noncontact atomic force microscopy, Surf. Sci. Lett. **373** (1997) L329–L332

13.48 Y. Sugawara, M. Ohta, H. Ueyama, S. Morita: Defect motion on an InP(110) surface observed with noncontact atomic force microscopy, Science **270** (1995) 1646–1648

13.49 T. Uchihashi, Y. Sugawara, T. Tsukamoto, M. Ohta, S. Morita: Role of a covalent bonding interaction in noncontact-mode atomic-force microscopy on Si(111)7 × 7, Phys. Rev. B **56** (1997) 9834–9840

13.50 K. Yokoyama, T. Ochi, A. Yoshimoto, Y. Sugawara, S. Morita: Atomic resolution imaging on

Si(100)2 × 1 and Si(100)2 × 1-H surfaces using a noncontact atomic force microscope, Jpn. J. Appl. Phys. **39** (2000) L113–L115

13.51 Y. Sugawara, T. Minobe, S. Orisaka, T. Uchihashi, T. Tsukamoto, S. Morita: Non-contact AFM images measured on Si(111)$\sqrt{3} \times \sqrt{3}$-Ag and Ag(111) surfaces, Surf. Interface Anal. **27** (1999) 456–461

13.52 K. Yokoyama, T. Ochi, Y. Sugawara, S. Morita: Atomically resolved Ag imaging on Si(111)$\sqrt{3} \times \sqrt{3}$-Ag surface with noncontact atomic force microscope, Phys. Rev. Lett. **83** (1999) 5023–5026

13.53 M. Bammerlin, R. Lüthi, E. Meyer, A. Baratoff, J. Lü, M. Guggisberg, Ch. Gerber, L. Howald, H.-J. Güntherodt: True atomic resolution on the surface of an insulator via ultrahigh vacuum dynamic force microscopy, Probe Microsc. **1** (1997) 3–7

13.54 M. Bammerlin, R. Lüthi, E. Meyer, A. Baratoff, J. Lü, M. Guggisberg, C. Loppacher, Ch. Gerber, H.-J. Güntherodt: Dynamic SFM with true atomic resolution on alkali halide surfaces, Appl. Phys. A **66** (1998) S293–S294

13.55 R. Hoffmann, M. A. Lantz, H. J. Hug, P. J. A. van Schendel, P. Kappenberger, S. Martin, A. Baratoff, H.-J. Güntherodt: Atomic resolution imaging and force versus distance measurements on KBr(001) using low temperature scanning force microscopy, Appl. Surf. Sci. **188** (2002) 238–244

13.56 R. Bennewitz, A. S. Foster, L. N. Kantorovich, M. Bammerlin, Ch. Loppacher, S. Schär, M. Guggisberg, E. Meyer, A. L. Shluger: Atomically resolved edges and kinks of NaCl islands on Cu(111): experiment and theory, Phys. Rev. B **62** (2000) 2074–2084

13.57 A. I. Livshits, A. L. Shluger, A. L. Rohl, A. S. Foster: Model of noncontact scanning force microscopy on ionic surfaces, Phys. Rev. B **59** (1999) 2436–2448

13.58 R. Bennewitz, M. Bammerlin, Ch. Loppacher, M. Guggisberg, L. Eng, E. Meyer, H.-J. Güntherodt, C. P. An, F. Luty: Molecular impurities at the NaCl(100) surface observed by scanning force microscopy, Rad. Effects Defects Solids **150** (1998) 321–326

13.59 R. Bennewitz, O. Pfeiffer, S. Schär, V. Barwich, E. Meyer, L. N. Kantorovich: Atomic corrugation in NC-AFM of alkali halides, Appl. Surf. Sci. **188** (2002) 232–237

13.60 C. Barth, M. Reichling: Resolving ions and vacancies at step edges on insulating surfaces, Surf. Sci. **470** (2000) L99–L103

13.61 R. Bennewitz, M. Reichling, E. Matthias: Force microscopy of cleaved and electron-irradiated CaF_2(111) surfaces in ultra-high vacuum, Surf. Sci. **387** (1997) 69–77

13.62 M. Reichling, C. Barth: Scanning force imaging of atomic size defects on the CaF_2(111) surface, Phys. Rev. Lett. **83** (1999) 768–771

13.63 M. Reichling, M. Huisinga, S. Gogoll, C. Barth: Degradation of the CaF_2(111) surface by air exposure, Surf. Sci. **439** (1999) 181–190

13.64 C. Barth, A. S. Foster, M. Reichling, A. L. Shluger: Contrast formation in atomic resolution scanning force microscopy of CaF_2(111): experiment and theory, J. Phys. Condens. Matter **13** (2001) 2061–2079

13.65 A. S. Foster, C. Barth, A. L. Shluger, M. Reichling: Unambiguous interpretation of atomically resolved force microscopy images of an insulator, Phys. Rev. Lett. **86** (2001) 2373–2376

13.66 A. S. Foster, A. L. Rohl, A. L. Shluger: Imaging problems on insulators: what can be learnt from NC-AFM modeling on CaF_2?, Appl. Phys. A **72** (2001) S31–S34

13.67 A. S. Foster, A. L. Shluger, R. M. Nieminen: Quantitative modeling in scanning force microscopy on insulators, Appl. Surf. Sci. **188** (2002) 306–318

13.68 M. Reichling, C. Barth: Atomically resoluiton imaging on fluorides. In: *Noncontact Atomic Force Microscopy*, ed. by S. Morita, R. Wiesendanger, E. Meyer (Springer, Berlin, Heidelberg 2002)

13.69 K. Fukui, H. Ohnishi, Y. Iwasawa: Atom-resolved image of the TiO_2(110) surface by noncontact atomic force microscopy, Phys. Rev. Lett. **79** (1997) 4202–4205

13.70 H. Raza, C. L. Pang, S. A. Haycock, G. Thornton: Non-contact atomic force microscopy imaging of TiO_2(100) surfaces, Appl. Surf. Sci. **140** (1999) 271–275

13.71 C. L. Pang, H. Raza, S. A. Haycock, G. Thornton: Imaging reconstructed TiO_2(100) surfaces with noncontact atomic force microscopy, Appl. Surf. Sci. **157** (2000) 223–238

13.72 M. Ashino, T. Uchihashi, K. Yokoyama, Y. Sugawara, S. Morita, M. Ishikawa: STM and atomic-resolution noncontact AFM of an oxygen-deficient TiO_2(110) surface, Phys. Rev. B **61** (2000) 13955–13959

13.73 C. L. Pang, S. A. Haycock, H. Raza, P. J. Møller, G. Thornton: Structures of the 4 × 1 and 1 × 2 reconstructions of SnO_2(110), Phys. Rev. B **62** (2000) R7775–R7778

13.74 H. Hosoi, K. Sueoka, K. Hayakawa, K. Mukasa: Atomic resolved imaging of cleaved NiO(100) surfaces by NC-AFM, Appl. Surf. Sci. **157** (2000) 218–221

13.75 W. Allers, S. Langkat, R. Wiesendanger: Dynamic low-temperature scanning force microscopy on nickel oxide (001), Appl. Phys. A **72** (2001) S27–S30

13.76 T. Kubo, H. Nozoye: Surface structure of $SrTiO_3$(100)-$(\sqrt{5} \times \sqrt{5}) - R26.6°$, Phys. Rev. Lett. **86** (2001) 1801–1804

13.77 K. Fukui, Y. Namai, Y. Iwasawa: Imaging of surface oxygen atoms and their defect structures on CeO_2(111) by noncontact atomic force microscopy, Appl. Surf. Sci. **188** (2002) 252–256

13.78 C. Barth, M. Reichling: Imaging the atomic arrangements on the high-temperature reconstructed α-Al_2O_3 surface, Nature **414** (2001) 54–57

13.79 C. L. Pang, H. Raza, S. A. Haycock, G. Thornton: Growth of copper and palladium α-Al_2O_3(0001), Surf. Sci. **460** (2000) L510–L514

13.80 K. Mukasa, H. Hasegawa, Y. Tazuke, K. Sueoka, M. Sasaki, K. Hayakawa: Exchange interaction between magnetic moments of ferromagnetic sample and tip: Possibility of atomic-resolution images of exchange interactions using exchange force microscopy, Jpn. J. Appl. Phys. **33** (1994) 2692–2695

13.81 H. Ness, F. Gautier: Theoretical study of the interaction between a magnetic nanotip and a magnetic surface, Phys. Rev. B **52** (1995) 7352–7362

13.82 K. Nakamura, H. Hasegawa, T. Ohuchi, K. Sueoka, K. Hayakawa, K. Mukasa: First-principles calculation of the exchange interaction and the exchange force between magnetic Fe films, Phys. Rev. B **56** (1997) 3218–3221

13.83 A. S. Foster, A. L. Shluger: Spin-contrast in noncontact SFM on oxide surfaces: theoretical modeling of NiO(001) surface, Surf. Sci. **490** (2001) 211–219

13.84 H. Hosoi, K. Kimura, K. Sueoka, K. Hayakawa, K. Mukasa: Non-contact atomic force microscopy of an antiferromagnetic NiO(100) surface using a ferromagnetic tip, Appl. Phys. A **72** (2001) S23–S26

13.85 H. Hosoi, K. Sueoka, K. Hayakawa, K. Mukasa: Atomically resolved imaging of a NiO(001) surface. In: *Noncontact Atomic Force Microscopy*, ed. by S. Morita, R. Wiesendanger, E. Meyer (Springer, Berlin, Heidelberg 2002) pp. 125–134

13.86 K. Kobayashi, H. Yamada, T. Horiuchi, K. Matsushige: Structures and electrical properties of fullerene thin films on Si(111)-7 × 7 surface investigated by noncontact atomic force microscopy, Jpn. J. Appl. Phys. **39** (2000) 3821–3829

13.87 T. Uchihashi, M. Tanigawa, M. Ashino, Y. Sugawara, K. Yokoyama, S. Morita, M. Ishikawa: Identification of B-form DNA in an ultrahigh vacuum by noncontact-mode atomic force microscopy, Langmuir **16** (2000) 1349–1353

13.88 R. M. Overney, E. Meyer, J. Frommer, D. Brodbeck, R. Lüthi, L. Howald, H.-J. Güntherodt, M. Fujihira, H. Takano, Y. Gotoh: Friction measurements on phase-separated thin films with a modified atomic force microscope, Nature **359** (1992) 133–135

13.89 D. Frisbie, L. F. Rozsnyai, A. Noy, M. S. Wrighton, C. M. Lieber: Functional group imaging by chemical force microscopy, Science **265** (1994) 2071–2074

13.90 E. Meyer, L. Howald, R. M. Overney, H. Heinzelmann, J. Frommer, H.-J. Güntherodt, T. Wagner, H. Schier, S. Roth: Molecular-resolution images of Langmuir–Blodgett films using atomic force microscopy, Nature **349** (1992) 398–400

13.91 K. Fukui, H. Onishi, Y. Iwasawa: Imaging of individual formate ions adsorbed on TiO_2(110) surface by non-contact atomic force microscopy, Chem. Phys. Lett. **280** (1997) 296–301

13.92 K. Kobayashi, H. Yamada, T. Horiuchi, K. Matsushige: Investigations of $C_6$0 molecules deposited on Si(111) by noncontact atomic force microscopy, Appl. Surf. Sci. **140** (1999) 281–286

13.93 Y. Maeda, T. Matsumoto, T. Kawai: Observation of single- and double-strand DNA using non-contact atomic force microscopy, Appl. Surf. Sci. **140** (1999) 400–405

13.94 T. Uchihashi, T. Ishida, M. Komiyama, M. Ashino, Y. Sugawara, W. Mizutani, K. Yokoyama, S. Morita, H. Tokumoto, M. Ishikawa: High-resolution imaging of organic monolayers using noncontact AFM, Appl. Surf. Sci **157** (2000) 244–250

13.95 T. Fukuma, K. Kobayashi, T. Horiuchi, H. Yamada, K. Matsushige: Alkanethiol self-assembled monolayers on Au(111) surfaces investigated by non-contact AFM, Appl. Phys. A **72** (2001) S109–S112

13.96 B. Gotsmann, C. Schmidt, C. Seidel, H. Fuchs: Molecular resolution of an organic monolayer by dynamic AFM, Europ. Phys. J. B **4** (1998) 267–268

13.97 Ch. Loppacher, M. Bammerlin, M. Guggisberg, E. Meyer, H.-J. Güntherodt, R. Lüthi, R. Schlittler, J. K. Gimzewski: Forces with submolecular resolution between the probing tip and Cu-TBPP molecules on Cu(100) observed with a combined AFM/STM, Appl. Phys. A **72** (2001) S105–S108

13.98 L. M. Eng, M. Bammerlin, Ch. Loppacher, M. Guggisberg, R. Bennewitz, R. Lüthi, E. Meyer, H.-J. Güntherodt: Surface morphology, chemical contrast, and ferroelectric domains in TGS bulk single crystals differentiated with UHV non-contact force microscopy, Appl. Surf. Sci. **140** (1999) 253–258

13.99 S. Kitamura, K. Suzuki, M. Iwatsuki: High resolution imaging of contact potential difference using a novel ultrahigh vacuum non-contact atomic force microscope technique, Appl. Surf. Sci. **140** (1999) 265–270

13.100 H. Yamada, T. Fukuma, K. Umeda, K. Kobayashi, K. Matsushige: Local structures and electrical properties of organic molecular films investigated by non-contact atomic force microscopy, Appl. Surf. Sci **188** (2000) 391–398

13.101 K. Fukui, Y. Iwasawa: Fluctuation of acetate ions in the (2 × 1)-acetate overlayer on TiO_2(110)-(1 × 1) observed by noncontact atomic force microscopy, Surf. Sci. **464** (2000) L719–L726

13.102 A. Sasahara, H. Uetsuka, H. Onishi: Single-molecule analysis by non-contact atomic force microscopy, J. Phys. Chem. B **105** (2001) 1–4

13.103 A. Sasahara, H. Uetsuka, H. Onishi: NC-AFM topography of HCOO and CH_3COO molecules co-adsorbed on TiO_2(110), Appl. Phys. A **72** (2001) S101–S103

13.104 A. Sasahara, H. Uetsuka, H. Onishi: Image topography of alkyl-substituted carboxylates observed by noncontact atomic force microscopy, Surf. Sci. **481** (2001) L437–L442

13.105 A. Sasahara, H. Uetsuka, H. Onishi: Noncontact atomic force microscope topography dependent on permanent dipole of individual molecules, Phys. Rev. B **64** (2001) 121406(R)

13.106 A. Sasahara, H. Uetsuka, T. Ishibashi, H. Onishi: A needle-like organic molecule imaged by noncontact atomic force microscopy, Appl. Surf. Sci. **188** (2002) 265–271

13.107 H. Onishi, A. Sasahara, H. Uetsuka, T. Ishibashi: Molecule-dependent topography determined by noncontact atomic force microscopy: Carboxylates on TiO_2(110), Appl. Surf. Sci. **188** (2002) 257–264

13.108 H. Onishi: Carboxylates adsorbed on TiO_2(110). In: *Chemistry of Nano-molecular Systems*, ed. by T. Nakamura (Springer, Berlin, Heidelberg 2002) pp. 75–89

13.109 S. Thevuthasan, G. S. Herman, Y. J. Kim, S. A. Chambers, C. H. F. Peden, Z. Wang, R. X. Ynzunza, E. D. Tober, J. Morais, C. S. Fadley: The structure of formate on TiO_2(110) by scanned-energy and scanned-angle photoelectron diffraction, Surf. Sci. **401** (1998) 261–268

13.110 H. Uetsuka, A. Sasahara, A. Yamakata, H. Onishi: Microscopic identification of a bimolecular reaction intermediate, J. Phys. Chem. B **106** (2002) 11549–11552

13.111 D. R. Lide: *Handbook of Chemistry and Physics*, 81st edn. (CRC, Boca Raton 2000)

13.112 K. Kobayashi, H. Yamada, K. Matsushige: Dynamic force microscopy using FM detection in various environments, Appl. Surf. Sci. **188** (2002) 430–434

Springer Handbook of Nanotechnology
B. Bhushan • © Springer 2004

14. Low Temperature Scanning Probe Microscopy

This chapter is dedicated to scanning probe microscopy, one of the most important techniques in nanotechnology. In general, scanning probe techniques allow the measurement of physical properties down to the nanometer scale. Some techniques, such as the scanning tunneling microscope and the scanning force microscope even go down to the atomic scale. The properties that are accessible are various. Most importantly, one can image the arrangement of atoms on conducting surfaces by scanning tunneling microscopy and on insulating substrates by scanning force microscopy. But also the arrangement of electrons (scanning tunneling spectroscopy), the force interaction between different atoms (scanning force spectroscopy), magnetic domains (magnetic force microscopy), the local capacitance (scanning capacitance microscopy), the local temperature (scanning thermo microscopy), and local light-induced excitations (scanning near-field microscopy) can be measured with high spatial resolution. In addition, some techniques even allow the manipulation of atomic configurations.

Probably the most important advantage of the low-temperature operation of scanning probe techniques is that they lead to a significantly better signal-to-noise ratio than measuring at room temperature. This is why many researchers work below 100 K. However, there are also physical reasons to use low-temperature equipment. For example, the manipulation of atoms or scanning tunneling spectroscopy with high energy resolution can only be realized at low temperatures. Moreover, some physical effects such as superconductivity or the Kondo effect are restricted to low temperatures. Here, we describe the design criteria of low-temperature scanning probe equipment and summarize some of the most spectacular results achieved since the invention of the method about 20 years ago. We first focus on the scanning tunneling microscope, giving examples of atomic manipulation and the analysis of electronic properties in different material arrangements. Afterwards, we describe results obtained by scanning force microscopy, showing atomic-scale imaging on insulators, as well as force spectroscopy analysis. Finally, the magnetic force microscope, which images domain patterns in ferromagnets and vortex patterns in superconductors, is discussed. Although this list is far from complete, we feel that it gives an adequate impression of the fascinating possibilities of low-temperature scanning probe instruments.

In this chapter low temperatures are defined as lower than about 100 K and are normally achieved by cooling with liquid nitrogen or liquid helium. Applications in which SPMs are operated close to 0 °C are not covered in this chapter.

14.1 **Microscope Operation at Low Temperatures** 414
- 14.1.1 Drift 414
- 14.1.2 Noise 415
- 14.1.3 Stability 415
- 14.1.4 Piezo Relaxation and Hysteresis 415

14.2 **Instrumentation** 415
- 14.2.1 A Simple Design for a Variable Temperature STM 416
- 14.2.2 A Low Temperature SFM Based on a Bath Cryostat 417

14.3 **Scanning Tunneling Microscopy and Spectroscopy** 419
- 14.3.1 Atomic Manipulation 419
- 14.3.2 Imaging Atomic Motion 420
- 14.3.3 Detecting Light from Single Atoms and Molecules 421
- 14.3.4 High Resolution Spectroscopy 422
- 14.3.5 Imaging Electronic Wave Functions 427
- 14.3.6 Imaging Spin Polarization: Nanomagnetism 431

14.4 **Scanning Force Microscopy and Spectroscopy** 433
- 14.4.1 Atomic-Scale Imaging 434
- 14.4.2 Force Spectroscopy 436
- 14.4.3 Electrostatic Force Microscopy 438
- 14.4.4 Magnetic Force Microscopy 439

References 442

More than two decades ago, the first design of an experimental setup was presented where a sharp tip was systematically scanned over a sample surface in order to obtain local information on the tip-sample interaction down to the atomic scale. This original instrument used the tunneling current between a conducting tip and a conducting sample as a feedback signal and was named *scanning tunneling microscope* accordingly [14.1]. Soon after this historic breakthrough, it became widely recognized that virtually any type of tip-sample interaction can be used to obtain local information on the sample by applying the same general principle, provided that the selected interaction was reasonably short-ranged. Thus, a whole variety of new methods has been introduced, which are denoted collectively as *scanning probe methods*. An overview is given by *Wiesendanger* [14.2].

The various methods, especially the above mentioned scanning tunneling microscopy (STM) and scanning force microscopy (SFM) – which is often further classified into subdisciplines such as the topography-reflecting atomic force microscopy (AFM), the magnetic force microscopy (MFM), or the electrostatic force microscopy (EFM) – have been established as standard methods for surface characterization on the nanometer scale. The reason is that they feature extremely high resolution (often down to the atomic scale for STM and AFM), despite a principally simple, compact, and comparatively inexpensive design.

A side effect of the simple working principle and the compact design of many scanning probe microscopes (SPMs) is that they can be adapted to different environments such as air, all kinds of gaseous atmospheres, liquids, or vacuum with reasonable effort. Another advantage is their ability to work within a wide temperature range. A microscope operation at higher temperatures is chosen to study surface diffusion, surface reactivity, surface reconstructions that only manifest at elevated temperatures, high-temperature phase transitions, or to simulate conditions as they occur, e.g., in engines, catalytic converters, or reactors. Ultimately, the upper limit for the operation of an SPM is determined by the stability of the sample, but thermal drift, which limits the ability to move the tip in a controlled manner over the sample, as well as the depolarization temperature of the piezoelectric positioning elements might further restrict successful measurements.

On the other hand, low-temperature (LT) application of SPMs is much more widespread than operation at high temperatures. Essentially five reasons make researchers adapt their experimental setups to low-temperature compatibility. These are: (1) the reduced thermal drift, (2) lower noise levels, (3) enhanced stability of tip and sample, (4) the reduction in piezo hysteresis/creep, and (5) probably the most obvious, the fact that many physical effects are restricted to low temperature. Reasons (1) to (4) only apply unconditionally if the whole microscope body is kept at low temperature (typically in or attached to a bath cryostat, see Sect. 14.2). Setups in which only the sample is cooled may show considerably less favorable operating characteristics. As a result of (1) to (4), ultrahigh resolution and long-term stability can be achieved on a level that significantly exceeds what can be accomplished at room temperature even under the most favorable circumstances. Typical examples for (5) are superconductivity [14.3] and the Kondo effect [14.4].

14.1 Microscope Operation at Low Temperatures

Nevertheless, before we devote ourselves to a small overview of experimental LTSPM work, we will take a closer look at the specifics of microscope operation at low temperatures, including a discussion of the corresponding instrumentation.

14.1.1 Drift

Thermal drift originates from thermally activated movements of the individual atoms, which are reflected by the thermal expansion coefficient. At room temperature, typical values for solids are on the order of $(1-50)\times10^{-6}\,\mathrm{K}^{-1}$. If the temperature could be kept precisely constant, any thermal drift would vanish, regardless of the absolute temperature of the system. The close coupling of the microscope to a large temperature bath that keeps a constant temperature ensures a significant reduction in thermal drift and allows for distortion-free, long-term measurements. Microscopes that are efficiently attached to sufficiently large bath cryostats, therefore, show a one- to two-order-of-magnitude increase in thermal stability compared with non-stabilized setups operated at room temperature.

A second effect also helps suppress thermally induced drift of the probing tip relative to a specific location on the sample surface. The thermal expansion coefficients are at liquid helium temperature two or more orders of magnitude smaller than at room temperature. Consequently, the thermal drift during low-temperature operation decreases accordingly.

For some specific scanning probe methods, there may be additional ways a change in temperature can affect the quality of the data. In *frequency-modulation SFM* (FM-SFM), for example, the measurement principle relies on the accurate determination of the eigenfrequency of the cantilever, which is determined by its spring constant and its effective mass. However, the spring constant changes with temperature due to both thermal expansion (i. e., the resulting change in the cantilever dimensions) and the variation of Young's modulus with temperature. Assuming drift rates of about 2 mK/min, as is typical for room temperature measurements, this effect might have a significant influence on the obtained data.

14.1.2 Noise

The theoretically achievable resolution in SPMs often increases with decreasing temperature due to a decrease in thermally induced noise. An example is the thermal noise in SFMs, which is proportional to the square root of the temperature [14.5, 6]. Lowering the temperature from $T = 300\,\mathrm{K}$ to $T = 10\,\mathrm{K}$ thus results in a reduction of the thermal frequency noise of more than a factor of five. Graphite, e.g., has been imaged atomically resolved only at low temperatures due to its extremely low corrugation, which was below the room temperature noise level [14.7, 8].

Another, even more striking, example is the spectroscopic resolution in *scanning tunneling spectroscopy* (STS). It depends linearly on the temperature [14.2] and is consequently reduced even more at LT than the thermal noise in AFM. This provides the opportunity to study structures or physical effects not accessible at room temperature such as spin and Landau levels in semiconductors [14.9].

Finally, it might be worth mentioning that the enhanced stiffness of most materials at low temperatures (increased Young's modulus) leads to a reduced coupling to external noise. Even though this effect is considered small [14.6], it should not be ignored.

14.1.3 Stability

There are two major stability issues that considerably improve at low temperature. First, low temperatures close to the temperature of liquid helium inhibit most of the thermally activated diffusion processes. As a consequence, the sample surfaces show a significantly increased long-term stability, since defect motion or adatom diffusion is massively suppressed. Most strikingly, even single xenon atoms deposited on suitable substrates can be successfully imaged [14.10, 11], or even manipulated [14.12]. In the same way, the low temperatures also stabilize the atomic configuration at the tip end by preventing sudden jumps of the most loosely bound foremost tip atom(s). Second, the large cryostat that usually surrounds the microscope acts as an effective cryo pump. Thus samples can be kept clean for several weeks, which is a multiple of the corresponding time at room temperature (about 3–4 h).

14.1.4 Piezo Relaxation and Hysteresis

The last important benefit from low-temperature operation of SPMs is that artifacts given by the response of the piezoelectric scanners are substantially reduced. After applying a voltage ramp to one electrode of a piezoelectric scanner, its immediate initial deflection, l_0, is followed by a much slower relaxation, Δl, with a logarithmic time dependence. This effect, known as piezo relaxation or "creep", diminishes substantially at low temperatures, typically by a factor of ten or more. As a consequence, piezo nonlinearities and piezo hysteresis decrease accordingly. Additional information is given by *Hug* et al. [14.13].

14.2 Instrumentation

The two main design criteria for all vacuum-based scanning probe microscope systems are (1) to provide an efficient decoupling of the microscope from the vacuum system and other sources of external vibrations, and (2) to avoid most internal noise sources through a high mechanical rigidity of the microscope body itself. In vacuum systems designed for low-temperature applications, a significant degree of complexity is added, since, on the one hand, close thermal contact of the SPM and cryogen is necessary to ensure the (approximately) drift-free conditions described above, while, on the other hand, a good vibration isolation (both from the outside world, as well as from the boiling or flowing cryogen) has to be maintained.

Plenty of microscope designs have been presented in the last ten to 15 years, predominantly in the field of STM. Due to the variety of the different approaches, we will, somewhat arbitrarily, give two examples on different levels of complexity that might serve as illustrative model designs.

14.2.1 A Simple Design for a Variable Temperature STM

A simple design for a variable temperature STM system is presented in Fig. 14.1 (Similar systems are also offered by Omicron (Germany) or Jeol (Japan)). It should give an impression of what the minimum requirements are, if samples are to be investigated successfully at low temperatures. It features a single ultrahigh vacuum (UHV) chamber that houses the microscope in its center. The general idea to keep the setup simple is that only the sample is cooled by means of a flow cryostat that ends in the small liquid nitrogen (LN) reservoir. This reservoir is connected to the sample holder with copper braids. The role of the copper braids is to thermally attach the LN reservoir to the sample located on the sample holder in an effective manner, while vibrations due to the flow of the cryogen should be blocked as much as possible. In this way, a sample temperature of about 100 K is reached. Alternatively, with liquid helium


Linear motion feedthrough (6" travel)
Scan head manipulator
Sample holder on holders dock
Tip transfer holders on storage elevator
Sample holder on storage elevator
Copper braid
LN reservoir
Thermo-couple
Scan head
Transfer arm
Load-lock
Sample holder
Sample stage
Tip transfer holder on transfer fork
Wobble stick for sample and tip handling
Heating/ cooling Stage

Fig. 14.1 One chamber UHV system with variable temperature STM based on a flow cryostat design. (Courtesy of RHK Technology, USA)

operation, a base temperature of below 30 K can be achieved, while a heater that is integrated into the sample stage enables high-temperature operation up to 1,000 K.

A typical experiment would run as follows: First, the sample is brought into the system by placing it in the so-called *load-lock*. This small part of the chamber can be separated from the rest of the system by a valve, so that the main part of the system can remain under vacuum at all times (i. e., even if the load-lock is opened for introducing the sample). After vacuum is re-established, the sample is transferred to the main chamber using the transfer arm. A linear motion feedthrough enables the storage of sample holders or, alternatively, specialized holders that carry replacement tips for the STM. Extending the transfer arm further, the sample can be placed on the sample stage and subsequently cooled down to the desired temperature. The scan head, which carries the STM tip, is then lowered with the scan head manipulator onto the sample holder (see Fig. 14.2). The special design of the scan head (see [14.14] for details) allows not only a flexible positioning of the tip on any desired location on the sample surface, but also compensates to a certain degree for thermal drift that inevitably occurs in such a design due to temperature gradients.

In fact, thermal drift is often much more prominent in LT-SPM designs, where only the sample is cooled, than in room temperature designs. Therefore, to fully benefit from the high stability conditions described in the introduction, it is mandatory to keep the whole microscope at the exact same temperature. This is mostly realized by using bath cryostats, which add a certain degree of complexity.

14.2.2 A Low Temperature SFM Based on a Bath Cryostat

As an example for an LT-SPM setup based on a bath cryostat, let us take a closer look at the LT-SFM system sketched in Fig. 14.3, which has been used to acquire the images on graphite, xenon, NiO, and InAs presented in Sect. 14.4. The force microscope is


Scan head manipulator
Scan head
Copper braids
Sample holder
Tip
Heating/ cooling stage

Fig. 14.2 Photograph of the STM located inside the system sketched in Fig. 14.1. After the scan head has been lowered onto the sample holder, it is fully decoupled from the scan head manipulator and can be moved laterally using the three piezo legs it stands on. (Courtesy of RHK Technology, USA)


Electrical and fiber feedthroughs
Motor chain drive
Main chamber
Vertical chain transfer
Getter pumps
Analysis chamber
Preparation chamber
Getter pump
Turbo pump
Turbo pump
Table
Pneumatic leg
Dewar
Copper cone
Cryostat
SFM
Sand
Separate foundation with pit

Fig. 14.3 Three-chamber UHV and bath cryostat system for scanning force microscopy, front view



Fig. 14.4a,b The scanning force microscope incorporated into the system presented in Fig. 14.3. **(a)** Section along plane of symmetry. **(b)** Photo from the front

built into a UHV system that comprises three vacuum chambers: one for cantilever and sample preparation, which also serves as a transfer chamber, one for analysis purposes, and a main chamber that houses the microscope. A specially designed vertical transfer mechanism based on a double chain allows the lowering of the microscope into a UHV compatible bath cryostat attached underneath the main chamber. To damp the system, it is mounted on a table carried by pneumatic damping legs, which, in turn, stand on a separate foundation to decouple it from building vibrations. The cryostat and dewar are separated from the rest of the UHV system by a bellow. In addition, the dewar is surrounded by sand for acoustic isolation.

In this design, tip and sample are exchanged at room temperature in the main chamber. After the transfer into the cryostat, the SFM can be cooled by either liquid nitrogen or liquid helium, reaching temperatures down to 10 K. An all-fiber interferometer as the detection mechanism for the cantilever deflection ensures high resolution, while simultaneously allowing the construction of a comparatively small, rigid, and symmetric microscope.

Figure 14.4 highlights the layout of the SFM body itself. Along with the careful choice of materials, the symmetric design eliminates most of the problems with drift inside the microscope encountered when cooling or warming it up. The microscope body has an overall cylindrical shape with a 13 cm height and a 6 cm diameter and exact mirror symmetry along the cantilever axis. The main body is made of a single block of macor, a machinable glass ceramic, which ensures a rigid and stable design. For most of the metallic parts titanium was used, which has a temperature coefficient similar to macor. The controlled but stable accomplishment of movements, such as coarse approach and lateral positioning in other microscope designs, is a difficult task at low temperatures. The present design uses a special type of piezo motor that moves a sapphire prism (see the "fiber approach" and the "sample approach" signs in Fig. 14.3). It is described in detail in [14.15]. More information regarding this design is given in [14.16].

14.3 Scanning Tunneling Microscopy and Spectroscopy

In this section, we review some of the most important results achieved by LTSTM. After summarizing the results with emphasis on the necessity of LT equipment, we turn to details of the different experiments and the physical meaning of the obtained results.

As described in Sect. 14.1, the LT equipment has basically three advantages for scanning tunneling microscopy (STM) and spectroscopy (STS). First, the instruments are much more stable with respect to thermal drift and the coupling to external noise, allowing the establishment of new functionalities of the instrument. In particular, the LTSTM has been used to move atoms on a surface [14.12], cut molecules in pieces [14.17], reform bonds [14.18], and, consequently, establish new structures on the nanometer scale. Also, the detection of light resulting from tunneling into a particular atom [14.19] and the visualization of thermally induced atomic movements [14.20] partly require LT instrumentation.

Second, the spectroscopic resolution in STS depends linearly on temperature and is, therefore, considerably reduced at LT. This provides the opportunity to study physical effects unaccessible at room temperature. Obvious examples are the resolution of spin and Landau levels in semiconductors [14.9], or the investigation of lifetime broadening effects of particular electronic states on the nanometer scale [14.21]. More spectacular, electronic wave functions have been imaged for the first time in real space using an LTSTM [14.22], and vibrational levels giving rise to additional inelastic tunneling have been detected [14.23] and localized within particular molecules [14.24].

Third and most obvious, many physical effects, in particular, effects guided by electronic correlations, are restricted to low temperature. Typical examples are superconductivity [14.3], the Kondo effect [14.4], and many of the electron phases found in semiconductors [14.25]. Here, the LTSTM provides the possibility to study electronic effects on a local scale, and intensive work has been done in this field, the most elaborate with respect to high temperature superconductivity [14.26].

14.3.1 Atomic Manipulation

Although manipulation of surfaces on the atomic scale can be achieved at room temperature [14.27], only the use of LTSTMs allow the placement of individual atoms at desired atomic positions [14.28].

The usual technique to manipulate atoms is to increase the current above a certain atom, which reduces the tip-atom distance, then to move the tip with the atom to a desired position, and finally to reduce the current again in order to decouple atom and tip. The first demonstration of this technique was performed by Eigler and Schweizer (1990), who used Xe atoms on a Ni(110) surface to write the three letters "IBM" (their employer) on the atomic scale (Fig. 14.5a). Nowadays, many laboratories are able to move different kinds of atoms and molecules on different surfaces with high precision. An example featuring CO molecules on Cu(110) is shown in Fig. 14.5b–g. Basic modes of controlled motion, pushing, pulling, and sliding of the molecules have been established that depend on the tunneling current, i. e., the distance and the particular molecule-substrate combination [14.29]. It is believed that the electric field between tip and molecule is the strongest force moving the molecules, but other mechanisms such as electromigration caused by the high current density [14.28] or modifications of the surface potential due to the presence of the tip [14.30] have been put forth as important for some of the manipulation modes.

Meanwhile, other types of manipulation on the atomic scale have been developed. Some of them require inelastic tunneling into vibrational or rotational modes of molecules or atoms. They lead to controlled desorption [14.31], diffusion [14.32], pick-up of molecules by the tip [14.18], or rotation of individual entities [14.33, 34]. Also, dissociation of molecules by voltage pulses [14.17], conformational changes induced by dramatic change of tip-molecule distance [14.35], and association of pieces into larger molecules by reducing their lateral distance [14.18] have been shown. Fig. 14.5h–m shows the production of biphenyl from two iodobenzene molecules [14.36]. The iodine is abstracted by voltage pulses (Fig. 14.5i,j), then the iodine is moved to the terrace by the pulling mode (Fig. 14.5k,l), and finally the two phenyl parts are slid along the step edge until they are close enough to react (Fig. 14.5m). The chemical identification of the components is not deduced straightforwardly from STM images and partly requires detailed calculations of their apparent shape.

Low temperatures are not always required in these experiments, but they increase the reproducibility because of the higher stability of the instrument, as discussed in Sect. 14.1. Moreover, rotation or diffusion of entities could be excited at higher temperatures, making the intentionally produced configurations unstable.



Fig. 14.5 **(a)** STM image of single Xe atoms positioned on a Ni(110) surface in order to realize the letters IBM on the atomic scale (courtesy of Eigler, IBM); **(b)–(f)** STM images recorded after different positioning processes of CO molecules on a Cu(110) surface; **(g)** final artwork greeting the new millennium on the atomic scale (**(b)–(g)** courtesy of Meyer, Berlin). **(h)–(m)** Synthesis of biphenyl from two iodobenzene molecules on Cu(111): First, iodine is abstracted from both molecules **(i)**,**(j)**, then the iodine between the two phenyl groups is removed from the step **(k)**, and finally one of the phenyls is slid along the Cu-step **(l)** until it reacts with the other phenyl **(m)**; the line drawings symbolize the actual status of the molecules (**(h)–(m)** courtesy of Hla and Rieder, Ohio)

14.3.2 Imaging Atomic Motion

Since individual manipulation processes last seconds to minutes, they probably cannot be used to manufacture large and repetitive structures. A possibility to construct such structures is self-assembled growth. It partly relies on the temperature dependence of different diffusion processes on the surface. A detailed knowledge of the diffusion parameters is required, which can be deduced from sequences of STM images measured at temperatures close to the onset of the process of interest [14.37]. Since many diffusion processes set on at LT, LT are partly required [14.20]. Consecutive images of so-called HtBDC molecules on Cu(110) recorded at $T = 194\,\mathrm{K}$ are shown in Fig. 14.6a–c [14.38]. As indicated by the arrows, the position of the molecules changes with time,



Fig. 14.6 **(a)–(c)** Consecutive STM images of hexa-tert-butyl decacyclene molecules on Cu(110) imaged at $T = 194$ K; *arrows* indicate the direction of motion of the molecules between two images. **(d)** Arrhenius plot of the hopping rate h determined from images like **(a)–(c)** as a function of inverse temperature (*grey symbols*); the *brown symbols* show the corresponding diffusion constant D; *lines* are fit results revealing an energy barrier of 570 meV for molecular diffusion (**(a)–(d)** courtesy of M. Schuhnack and F. Besenbacher, Aarhus). **(e)** Arrhenius plot for D (*crosses*) and H (*circles*) on Cu(001). The constant hopping rate of H below 65 K indicates a non-thermal diffusion process, probably tunneling (courtesy of Ho, Irvine)

implying diffusion. Diffusion parameters are obtained from Arrhenius plots of the determined hopping rate h, as shown in Fig. 14.6d. Of course, one must make sure that the diffusion process is not influenced by the presence of the tip, since it is known from manipulation experiments that the presence of the tip can move a molecule. However, particularly at low tunneling voltages these conditions can be fulfilled.

Besides the determination of diffusion parameters, studies of the diffusion of individual molecules showed the importance of mutual interactions in diffusion, which can lead to concerted motion of several molecules [14.20], or, very interestingly, the influence of quantum tunneling [14.39]. The latter is deduced from the Arrhenius plot of hopping rates of H and D on Cu(001), as shown in Fig. 14.6e. The hopping rate of H levels off at about 65 K, while the hopping rate of the heavier D atom goes down to nearly zero, as expected from thermally induced hopping.

Other diffusion processes such as the movement of surface vacancies [14.40] or of bulk interstitials close to the surface [14.41], and the Brownian motion of vacancy islands [14.42] have also been displayed.

14.3.3 Detecting Light from Single Atoms and Molecules

It had already been realized in 1988 that STM experiments are accompanied by light emission [14.43]. The fact that molecular resolution in the light intensity was achieved at LT (Fig. 14.7a,b) [14.19] raised the hope of performing quasi-optical experiments on the molecular scale. Meanwhile, it is clear that the basic emission process observed on metals is the decay of a local plasmon induced in the area around the tip by inelastic tunneling processes [14.44, 45]. Thus, the molecular resolution is basically a change in the plasmon environment, largely given by the increased height of the tip with respect to the surface above the molecule [14.46]. However, the electron can, in principle, also decay via single-particle excitations. Indeed, signatures of single-particle levels are observed. Figure 14.7c shows light spectra measured at different tunneling voltage V above a nearly complete Na monolayer on Cu(111) [14.47]. The plasmon mode peak energy (arrow) is found, as usual, to be proportional to V, but an additional peak that does not move with V appears at 1.6 eV (p). Plotting the light intensity as a function of photon energy and V (Fig. 14.7d) clearly shows that this additional peak is fixed in photon energy and corresponds to the separation of quantum well levels of the Na ($E_n - E_m$).

Light has also been detected from semiconductors [14.48], including heterostructures [14.49]. There, the light is mostly caused by single-particle relaxation



Fig. 14.7 **(a)** STM image of C_{60} molecules on Au(110) imaged at $T = 50$ K. **(b)** STM-induced photon intensity map of the same area; all photons from 1.5 eV to 2.8 eV contribute to the image, tunneling voltage $V = -2.8$ V (**(a)**,**(b)** courtesy of Berndt, Kiel). **(c)** STM-induced photon spectrum measured on 0.6 monolayer of Na on Cu(111) at different tunneling voltages as indicated. Besides the shifting plasmon mode marked by an *arrow*, an energetically constant part named p is recognizable. **(d)** Greyscale map of photon intensity as a function of tunnelling voltage and photon energy measured on 2.0 monolayer Na on Cu(111). The energetically constant photons are identified with intersubband transitions of the Na quantum well, as marked by $E_n - E_m$ (**(c)**,**(d)** courtesy of Hoffmann, Hamburg)

of the injected electrons, allowing a very local source of electron injection.

14.3.4 High Resolution Spectroscopy

One of the most important modes of LTSTM is STS. It detects the differential conductivity $\mathrm{d}I/\mathrm{d}V$ as a function of the applied voltage V and the position (x, y). The $\mathrm{d}I/\mathrm{d}V$-signal is basically proportional to the local density of states (LDOS) of the sample, the sum over squared single-particle wave functions Ψ_i [14.2]

$$\frac{\mathrm{d}I}{\mathrm{d}V}(V, x, y) \propto \mathrm{LDOS}(E, x, y) = \sum_{\Delta E} |\Psi_i(E, x, y)|^2 , \qquad (14.1)$$

where ΔE is the energy resolution of the experiment. In simple terms, each state corresponds to a tunneling channel if it is located between the Fermi levels (E_F) of the tip and the sample. Thus, all states located in this energy interval contribute to I, while $\mathrm{d}I/\mathrm{d}V(V)$ detects only the states at the energy E corresponding to V. The local intensity of each channel depends further on the LDOS of the state at the corresponding surface position and its decay length into vacuum. For s-like tip states, *Tersoff* and *Hamann* have shown that it is simply proportional to the LDOS at the position of the tip [14.50]. Therefore, as long as the decay length is spatially constant, one measures the LDOS at the surface (14.1). Note that the contributing states are not only surface states, but also bulk states. However, surface states usually dominate if present. *Chen* has shown that higher orbital tip states lead to the so-called derivation rule [14.51]: p_z-type tip states detect $\mathrm{d(LDOS)}/\mathrm{d}z$, d_z^2-states detect $\mathrm{d}^2\mathrm{(LDOS)}/\mathrm{d}z^2$, and so on. As long as the decay into vacuum is exponential and spatially constant, this leads only to an additional factor in $\mathrm{d}I/\mathrm{d}V$. Thus, it is still the LDOS that is measured (14.1). The requirement of a spatially constant decay is usually fulfilled on larger length scales, but not on the atomic scale [14.51]. There, states located close to the atoms show a stronger decay into vacuum than the less localized states in the interstitial region. This effect can lead to corrugations that are larger than the real LDOS corrugations [14.52].

The voltage dependence of $\mathrm{d}I/\mathrm{d}V$ is sensitive to a changing decay length with V, which increases with V. Additionally, $\mathrm{d}I/\mathrm{d}V(V)$-curves might be influenced by possible structures in the DOS of the tip, which also contributes to the number of tunneling channels [14.53]. However, these structures can usually be identified, and only tips free of characteristic DOS structures are used for quantitative experiments.

Importantly, the energy resolution ΔE is largely determined by temperature. It is defined as the smallest energy distance of two δ-peaks in the LDOS that can still be resolved as two individual peaks in $\mathrm{d}I/\mathrm{d}V(V)$-curves and is $\Delta E = 3.3\,\mathrm{kT}$ [14.2]. The temperature dependence is nicely demonstrated in Fig. 14.8, where the tunneling gap of the superconductor Nb is measured at different temperatures [14.54]. The peaks at the rim of the gap get wider at temperatures well below the critical temperature of the superconductor ($T_\mathrm{c} = 9.2\,\mathrm{K}$).



Fig. 14.8 Differential conductivity curve $\mathrm{d}I/\mathrm{d}V(V)$ measured on a Au surface by a Nb tip (*symbols*). Different temperatures are indicated; the lines are fits according to the superconducting gap of Nb folded with the temperature broadened Fermi distribution of the Au (courtesy of Pan, Houston)

Lifetime Broadening

Besides ΔE, intrinsic properties of the sample lead to a broadening of spectroscopic features. Basically, the finite lifetime of the electron or hole in the corresponding state broadens its energetic width. Any kind of interaction such as electron-electron interaction can be responsible. Lifetime broadening has usually been measured by photoemission spectroscopy (PES), but it turned out that lifetimes of surface states on noble metal surfaces determined by STS (Fig. 14.9a,b) are up to a factor of three larger than the ones measured by PES [14.55]. The reason is probably that defects broaden the PES spectrum. Defects are unavoidable in a spatially integrating technique such as PES, thus, STS has the advantage of choosing a particularly clean area for lifetime measurements. The STS results can be successfully compared to theory, highlighting the dominating influence of intraband transitions for the surface state lifetime on Au(111) and Cu(111), at least close to the onset of the surface band [14.21].

With respect to band electrons, the analysis of the width of the band onset in $\mathrm{d}I/\mathrm{d}V(V)$-curves has the disadvantage of being restricted to the onset energy. Another method circumvents this problem by measuring the decay of standing electron waves scattered from a step edge as a function of energy [14.56]. Figure 14.9c,d shows the resulting oscillating $\mathrm{d}I/\mathrm{d}V$-signal measured for two different energies. To deduce the coherence length L_Φ, which is inversely proportional to the lifetime τ_Φ, one has to consider that the finite ΔE in the experiment also leads to a decay of the standing wave away from the step edge. The dotted fit line using $L_\Phi = \infty$ indicates this effect and, more importantly, shows a discrepancy with the measured curve. Only including a finite coherence length of 6.2 nm results in good agreement, which, in turn, determines L_Φ and thus τ_Φ, as displayed in Fig. 14.9c. The found $1/E^2$-dependence of τ_Φ points to a dominating influence of electron-electron interactions at higher energies in the surface band.

Landau and Spin Levels

Moreover, the increased energy resolution at LT allows the resolution of electronic states that are not resolvable at RT. For example, Landau and spin quantization appearing in magnetic field B have been probed on InAs(110) [14.9, 57]. The corresponding quantization



Fig. 14.9 **(a)**,**(b)** spatially averaged $\mathrm{d}I/\mathrm{d}V(V)$-curves of Ag(111) and Cu(111); both surfaces exhibit a surface state with parabolic dispersion starting at −65 meV and −430 meV, respectively. The lines are drawn to determine the energetic width of the onset of these surface bands (**(a)**,**(b)** courtesy of Berndt, Kiel); **(c)** $\mathrm{d}I/\mathrm{d}V$-intensity as a function of position away from a step edge of Cu(111) measured at the voltages ($E - E_F$), as indicated (*points*); the lines are fits assuming standing electron waves with a phase coherence length L_Φ as marked; **(d)** resulting phase coherence time as a function of energy for Ag(111) and Cu(111). *Inset* shows the same data on a double logarithmic scale evidencing the E^{-2}-dependence (*line*) (**(c)**,**(d)** courtesy of Brune, Lausanne)

energies are given by $E_{\text{Landau}} = \hbar eB/m_{\text{eff}}$ and $E_{\text{spin}} = g\mu B$. Thus InAs is a good choice, since it exhibits a low effective mass $m_{\text{eff}}/m_e = 0.023$ and a high g-factor of 14 in the bulk conduction band. The values in metals are $m_{\text{eff}}/m_e \approx 1$ and $g \approx 2$, resulting in energy splittings of only 1.25 meV and 1.2 meV at $B = 10$ T. This is obviously lower than the typical lifetime broadenings discussed in the previous section and also close to $\Delta E = 1.1$ meV achievable at $T = 4$ K.

Fortunately, the electron density in doped semiconductors is much lower, and thus the lifetime increases significantly. Figure 14.10a shows a set of spectroscopy curves obtained on InAs(110) in different magnetic fields [14.9]. Above E_F, oscillations with increasing intensity and energy distance are observed. They show the separation expected from Landau quantization. In turn, they can be used to deduce m_{eff} from the peak separation (Fig. 14.10b). An increase of m_{eff} with increasing E has been found as expected from theory. Also, at high fields spin quantization is observed (Fig. 14.10c). It is larger than expected from the bare g-factor due to contributions from exchange enhancement [14.58]. A detailed discussion of the peaks revealed that they belong to the so-called tip-induced quantum dot resulting from the work function difference between tip and sample.

Vibrational Levels

As discussed with respect to light emission in STM, inelastic tunneling processes contribute to the tunneling current. The coupling of electronic states to vibrational levels is one source of inelastic tunneling [14.23]. It provides additional channels contributing to $\mathrm{d}I/\mathrm{d}V(V)$ with final states at energies different from V. The final energy is simply shifted by the energy of the vibrational level. If only discrete vibrational energy levels couple to a smooth electronic DOS, one expects a peak in $\mathrm{d}^2I/\mathrm{d}V^2$ at the vibrational energy. This situation appears for molecules on noble metal surfaces. As usual, the isotope effect on the vibrational energy can be used



Fig. 14.10 **(a)** dI/dV-curves of n-InAs(110) at different magnetic fields as indicated; E_{BCBM} marks the bulk conduction band minimum; oscillations above E_{BCBM} are caused by Landau quantization; the double peaks at $B = 6\,T$ are caused by spin quantization. **(b)** Effective mass data deduced from the distance of adjacent Landau peaks ΔE according to $\Delta E = h e B/m_{eff}$ (*open symbols*); *filled symbols* are data from planar tunnel junctions (Tsui), the *solid line* is a mean-sqare fit of the data and the *dashed line* is the expected effective mass of InAs according to kp-theory. **(c)** Magnification of a dI/dV-curve at $B = 6\,T$ exhibiting spin splitting; the Gaussian curves marked by *arrows* are the fitted spin levels

to verify the vibrational origin of the peak. First indications of vibrational levels have been found for H_2O and D_2O on TiO_2 [14.59], and completely convincing work has been performed for C_2H_2 and C_2D_2 on Cu(001) [14.23] (Fig. 14.11a). The technique can be used to identify individual molecules on the surface by their characteristic vibrational levels. In particular, surface reactions, as described in Fig. 14.5h–m, can be directly verified. Moreover, the orientation of complexes with respect to the surface can be determined to a certain extent, since the vibrational excitation depends on the position of the tunneling current within the molecule. Finally, the excitation of certain molecular levels can induce such corresponding motions as hopping [14.32], rotation [14.34] (Fig. 14.11b–e), or desorption [14.31], leading to additional possibilities for manipulation on the atomic scale.

Kondo Resonance

A rather intricate interaction effect is the Kondo effect. It results from a second order scattering process between itinerate states and a localized state [14.60]. The two states exchange some degree of freedom back and forth, leading to a divergence of the scattering probability at the Fermi level of the itinerate states. Due to the divergence, the effect strongly modifies sample properties. For example, it leads to an unexpected increase in resistance with decreasing temperature for metals containing magnetic impurities [14.4]. Here, the exchanged degree of freedom is the spin. A spectroscopic signature of the Kondo effect is a narrow peak in the DOS at the Fermi level disappearing above a characteristic temperature (Kondo temperature). STS provides the opportunity to study this effect on the local scale [14.61, 62].

Figure 14.12a–d shows an example of Co clusters deposited on a carbon nanotube [14.63]. While a small dip at the Fermi level, which is probably caused by curvature influences on the π-orbitals, is observed without Co (Fig. 14.12b) [14.64], a strong peak is found around a Co cluster deposited on top of the tube (Fig. 14.12a, arrow). The peak is slightly shifted with respect to $V = 0\,mV$ due to the so-called Fano resonance [14.65], which results from interference of the tunneling processes into the localized Co-level and the itinerant nanotube levels. The resonance disappears within a several nanometer distance from the cluster, as shown in Fig. 14.12d.

The Kondo effect has also been detected for different magnetic atoms deposited on noble metal sur-



Fig. 14.11 **(a)** d^2I/dV^2-curves taken above a C_2H_2 and a C_2D_2 molecule on Cu(100); the peaks correspond to the C-H, respectively, C-D stretch mode energy of the molecule. **(b)** Sketch of O_2 molecule on Pt(111). **(c)** Tunnelling current above an O_2 molecule on Pt(111) during a voltage pulse of 0.15 V; the jump in current indicates rotation of the molecule. **(d)**, **(e)** STM image of an O_2 molecule on Pt(111) ($V = 0.05$ V) prior and after rotation induced by a voltage pulse to 0.15 V (**(a)–(e)** courtesy of Ho, Irvine)

faces [14.61,62]. There, it disappears at about 1 nm away from the magnetic impurity, and the effect of the Fano resonance is more pronounced, contributing to dips in $dI/dV(V)$-curves instead of peaks.



Fig. 14.12 **(a)** STM image of a Co cluster on a single-wall carbon nanotube (SWNT). **(b)** dI/dV-curves taken directly above the Co cluster (Co) and far away from the Co cluster (SWNT); the *arrow* marks the Kondo peak. **(c)** STM image of another Co cluster on a SWNT with *symbols* marking the positions where the dI/dV-curves displayed in **(d)** are taken. **(d)** dI/dV-curves taken at the positions marked in **(c)** (**(a)–(d)** courtesy of Lieber, Cambridge). **(e)** *Lower part:* STM image of a quantum corral of elliptic shape made from Co atoms on Cu(111); one Co atom is placed in one of the focii of the ellipse. *Upper part:* map of the strength of the Kondo signal in the corral; note that there is also a Kondo signal in the focus, which is not covered by a Co atom (**(e)** courtesy of Eigler, Almaden)



Fig. 14.13 **(a)** Low voltage STM image of Cu(111), including two defect atoms; the waves are electronic Bloch waves scattered at the defects. **(b)** Low voltage STM image of a rectangular quantum corral made from single atoms on Cu(111); the pattern inside the corral is the confined state of the corral close to E_F; (**(a)**,**(b)** courtesy of Eigler, Almaden). **(c)** STM image of GaAs(110) around a Si donor, $V = -2.5$ V; the line scan along A shown in **(d)** exhibits an additional oscillation around the donor caused by a standing Bloch wave; the grid like pattern corresponds to the atomic corrugation of the Bloch wave (**(c)**,**(d)** courtesy of van Kempen, Nijmegen). **(e)–(g)** STM images of an InAs/ZnSe-core/shell-nanocluster at different V. The image is measured in the so-called constant-height mode, i. e., the images display the tunneling current at constant height above the surface; the hill in **(e)** corresponds to the s-state of the cluster, the ring in **(f)** to the degenerate p_x- and p_y-state and the hill in **(g)** to the p_z-state (**(e)–(g)** courtesy of Millo, Jerusalem). **(h)** STM-image of a short-cut carbon nanotube. **(i)** Colour plot of the dI/dV intensity inside the short-cut nanotube as a function of position and tunneling voltage; four wavy patterns of different wavelength are visible in the voltage range from -0.1 to 0.15 V (**(h)**,**(i)** courtesy of Dekker, Delft)

A fascinating experiment has been performed by *Manoharan* et al. [14.66], who used manipulation to form an elliptic cage for the surface states of Cu(111) (Fig. 14.12e, bottom). This cage was constructed to have a quantized level at E_F. Then, a cobalt atom was placed in one focus of the elliptic cage, producing a Kondo resonance. Surprisingly, the same resonance reappeared in the opposite focus, but not away from the focus (Fig. 14.12e, top). This shows amazingly that complex local effects such as the Kondo resonance can be guided to remote points.

Orbital scattering as a source of the Kondo resonance has also been found around a defect on Cr(001) [14.67]. Here, it is believed that itinerate sp-levels scatter at a localized d-level to produce the Kondo peak.

14.3.5 Imaging Electronic Wave Functions

Since STS measures the sum of squared wave functions (14.1), it is an obvious task to measure the local appearance of the most simple wave functions in solids, namely, the Bloch waves.

Bloch Waves

The atomically periodic part of the Bloch wave is always measured if atomic resolution is achieved (inset of Fig. 14.14a). However, the long-range, wavy part requires the presence of scatterers. The electron wave impinges on the scatterer and gets reflected, leading to self-interference. In other words, the phase of the Bloch wave gets fixed by the scatterer.

Such self-interference patterns were first found on Graphite(0001) [14.68] and later on noble metal surfaces, where adsorbates or step edges scatter the surface states (Fig. 14.13a) [14.22]. Fourier transforms of the real-space images reveal the k-space distribution of the corresponding states [14.69], which may include additional contributions besides the surface state [14.70]. Using particular geometries as the so-called quantum corrals to form a cage for the electron wave, the scatter-



Fig. 14.14 **(a)** dI/dV-image of InAs(110) at $V = 50\,\mathrm{mV}$, $B = 0\,\mathrm{T}$; circular wave patterns corresponding to standing Bloch waves around each S donor are visible; inset shows a magnification revealing the atomically periodic part of the Bloch wave. **(b)** Same as **(a)**, but at $B = 6\,\mathrm{T}$; the stripe structures are drift states. **(c)** dI/dV-image of a 2-D electron system on InAs(110) induced by the deposition of Fe, $B = 0\,\mathrm{T}$. **(d)** Same as **(c)** but at $B = 6\,\mathrm{T}$; note that the contrast in **(a)** is increased by a factor of ten with respect to **(b)**–**(d)**

ing state can be rather complex (Fig. 14.13b). Anyway, it can usually be reproduced by simple calculations involving single-particle states [14.71].

Bloch waves in semiconductors scattered at charged dopants (Fig. 14.13c,d) [14.72], Bloch states confined in semiconductor quantum dots (Fig. 14.13e–g) [14.73], and Bloch waves confined in short-cut carbon nanotubes (Fig. 14.13h,i) [14.74, 75] have been visualized.

Drift States

More complex wave functions result from interactions. A nice playground to study such interactions are doped semiconductors. The reduced electron density with respect to metals increases the importance of electron interactions with potential disorder and other electrons. Applying a magnetic field quenches the kinetic energy, further enhancing the importance of interactions. A dramatic effect can be observed on InAs(110), where 3-D bulk states are displayed. While the usual scattering states around individual dopants are observed at $B = 0\,\mathrm{T}$ (Fig. 14.14a) [14.76], stripe structures are found in high magnetic field (Fig. 14.14b) [14.77]. They run along equipotential lines of the disorder potential. This can be understood by recalling that the electron tries to move in a cyclotron orbit, which is accelerated and decelerated in electrostatic potential, leading to a drift motion along an equipotential line [14.78].

The same effect has been found in 2-D electron systems (2-DES) of the same substrate, where the scattering states at $B = 0\,\mathrm{T}$ are, however, found to be more complex (Fig. 14.14c) [14.79]. The reason is the tendency of a 2-DES to exhibit closed scattering paths [14.80]. Consequently, the self-interference does not result from scattering at individual scatterers, but from complicated self-interference paths involving many scatterers. But drift states are also observed in the 2-DES at high magnetic fields (Fig. 14.14d) [14.81].

Charge Density Waves

Another interaction modifying the LDOS is the electron-phonon interaction. Phonons scatter electrons between different Fermi points. If the wave vectors connecting Fermi points exhibit a preferential orientation, a so-called Peierls instability occurs [14.82]. The corresponding phonon energy goes to zero, the atoms are slightly displaced with the periodicity of the corresponding wave vector, and a charge density wave (CDW) with the same periodicity appears. Essentially, the CDW increases the overlap of the electronic states with the phonon by phase fixing with respect to the atomic lattice. The Peierls transition naturally occurs in 1-D systems, where only two Fermi points are present, and, hence, preferential orientation is pathological. It can also occur in 2-D systems if large areas of the Fermi line run in parallel.

STS studies of CDWs are numerous (e.g., [14.83, 84]). Examples of a 1-D CDW on a quasi 1-D-like bulk material and of a 2-D CDW are shown in Fig. 14.15a–d and Fig. 14.15e, respectively [14.85, 86]. In contrast to usual scattering states where LDOS corrugations are only found close to the scatterer, the corrugations of CDWs are continous across the surface. Heating the substrate toward the transition temperature leads to a melting of the CDW lattice, as shown in Fig. 14.15f–h.

CDWs have also been found on monolayers of adsorbates such as a monolayer of Pb on Ge(111) [14.87]. These authors performed a nice temperature-dependent study revealing that the CDW is nucleated by scattering states around defects as one might expect [14.88]. 1-D systems have also been prepared on surfaces show-



Fig. 14.15 **(a)** STM image of the ab-plane of the organic quasi 1-D conductor TTF-TCNQ, $T = 300\,\mathrm{K}$; while the TCNQ chains are conducting, the TTF chains are insulating. **(b)** Stick and ball model of the ab-plane of TTF-TCNQ. **(c)** STM image taken at $T = 61\,\mathrm{K}$, the additional modulation due to the Peierls-transition is visible in the profile along line A shown in **(d)**; the *open triangles* mark the atomic periodicity and the *filled triangles* the expected CDW periodicity (**(a)–(d)** courtesy of Kageshima, Kanagawa). **(e)–(h)** Low voltage STM-images of the two-dimensional CDW-system 1 T-TaS_2 at $T = 242\,\mathrm{K}$ **(e)**, 298 K **(f)**, 349 K **(g)**, 357 K **(h)**. A long-range, hexagonal modulation is visible besides the atomic spots; its periodicity is highlighted by *big white dots* in **(e)**; the additional modulation obviously weakens with increasing T, but is still apparent in **(f)** and **(g)**, as evidenced in the lower magnification images in the insets (**(e)–(h)** courtesy of Lieber, Cambridge)

ing Peierls transitions [14.89,90]. Finally, the energy gap occurring at the transition has been studied by measuring $\mathrm{d}I/\mathrm{d}V(V)$-curves [14.91].

Superconductors

An intriguing effect resulting from electron-phonon interaction is superconductivity. Here, the attractive part of the electron-phonon interaction leads to the coupling of electronic states with opposite wave vector and mostly opposite spin [14.92]. Since the resulting Cooper pairs are bosons, they can condense at LT, forming a coherent many-particle phase, which can carry current without resistance. Interestingly, defect scattering does not influence the condensate if the coupling along the Fermi surface is homogeneous (s-wave superconductor). The reason is that the symmetry of the scattering of the two components of a Cooper pair effectively leads to a scattering from one Cooper pair state to another without affecting the condensate. This is different if the scatterer is magnetic, since the different spin components of the pair are scattered differently, leading to an effective pair breaking visible as a single-particle excitation within the superconducting gap. On a local scale, the effect has first been demonstrated by putting Mn, Gd, and Ag atoms on a Nb(110) surface [14.93]. While the nonmagnetic Ag does not modify the gap shown in Fig. 14.16a, it is modified in an asymmetric fashion close to Mn or Gd adsorbates, as shown in Fig. 14.16b. The asymmetry of the additional intensity is caused by the breaking of the particle-hole symmetry due to the exchange interaction between the localized Mn state and the itinerate Nb states.

Another important local effect is caused by the relatively large coherence length of the condensate. At a material interface, the condensate wave function cannot stop abruptly, but laps into the surrounding material (proximity effect). Consequently, a superconducting gap can be measured in areas of non-superconducting material. Several studies have shown this effect on the



Fig. 14.16 **(a)** $\mathrm{d}I/\mathrm{d}V$-curve of Nb(110) at $T = 3.8\,\mathrm{K}$ (*symbols*) in comparison with a BCS-fit of the superconducting gap of Nb (*line*). **(b)** Difference between the $\mathrm{d}I/\mathrm{d}V$-curve taken directly above a Mn-atom on Nb(110) and the $\mathrm{d}I/\mathrm{d}V$-curve taken above the clean Nb(110) (*symbols*) in comparison with a fit using the Bogulubov-de Gennes equations (*line*) (**(a)**,**(b)** courtesy of Eigler, Almaden). **(c)–(e)** $\mathrm{d}I/\mathrm{d}V$-images of a vortex core in the type-II superconductor 2H-NbSe$_2$ at 0 mV **(c)**, 0.24 mV **(d)**, and 0.48 mV **(e)** (**(c)–(e)** courtesy of H. F. Hess). **(f)–(h)** Corresponding calculated LDOS images within the Eilenberger framework (**(f)–(h)** courtesy of Machida, Okayama). **(i)** Overlap of an STM image at $V = -100\,\mathrm{mV}$ (backround 2-D image) and a $\mathrm{d}I/\mathrm{d}V$-image at $V = 0\,\mathrm{mV}$ (overlapped 3-D image) of optimally doped $\mathrm{Bi_2Sr_2CaCu_2O_{8+\delta}}$ containing 0.6% Zn impurities. The STM image shows the atomic structure of the cleavage plane, while the $\mathrm{d}I/\mathrm{d}V$-image shows a bound state within the superconducting gap, which is located around a single Zn impurity. The fourfold symmetry of the bound state reflects the d-like symmetry of the superconducting pairing function; **(j)** $\mathrm{d}I/\mathrm{d}V$-curves taken at different positions across the Zn impurity; the bound state close to 0 mV is visible close to the Zn atom; **(k)** LDOS in the vortex core of slightly overdoped $\mathrm{Bi_2Sr_2CaCu_2O_{8+\delta}}$, $B = 5\,\mathrm{T}$; the $\mathrm{d}I/\mathrm{d}V$-image taken at $B = 5\,\mathrm{T}$ is integrated over $V = 1{-}12\,\mathrm{mV}$, and the corresponding $\mathrm{d}I/\mathrm{d}V$-image at $B = 0\,\mathrm{T}$ is subtracted to highlight the LDOS induced by the magnetic field. The checkerboard pattern within the seven vortex cores exhibits a periodicity, which is fourfold with respect to the atomic lattice shown in **(i)** and is thus assumed to be a CDW (**(i)–(k)** courtesy of S. Davis, Cornell and S. Uchida, Tokyo)

local scale using metals and doped semiconductors as surrounding materials [14.94, 95].

While the classical type-I superconductors are ideal diamagnets, the so-called type-II superconductors can contain magnetic flux. The flux forms vortices, each containing one flux quantum. These vortices are accompanied by a disappearance of the superconducting gap and, therefore, can be probed by STS [14.96]. LDOS maps measured inside the gap lead to bright features in the area of the vortex core. Importantly, the length scale of these features is different from the length scale of the magnetic flux due to the difference between London's penetration depth and coherence length. Thus, STS probes another property of the vortex than the usual magnetic imaging techniques (see Sect. 14.4.4). Surprisingly, first measurements of the vortices on $NbSe_2$ revealed vortices shaped as a sixfold star [14.97] (Fig. 14.16c). With increasing voltage inside the gap, the orientation of the star rotates by 30° (Fig. 14.16d,e). The shape of these stars could finally be reproduced by theory, assuming an anisotropic pairing of electrons in the superconductor (Fig. 14.16f–h) [14.98]. Additionally, bound states inside the vortex core, which result from confinement by the surrounding superconducting material, are found [14.97]. Further experiments investigated the arrangement of the vortex lattice, including transitions between hexagonal and quadratic lattices [14.99], the influence of pinning centers [14.100], and the vortex motion induced by current [14.101].

An important topic is still the understanding of high temperature superconductivity (HTCS). An almost accepted property of HTCS is its d-wave pairing symmetry. In contrast to s-wave superconductors, scattering can lead to pair breaking, since the Cooper pair density vanishes in certain directions. Indeed, scattering states (bound states in the gap) around nonmagnetic Zn impurities have been observed in $Bi_2Sr_2CaCu_2O_{8+\delta}$ (BSCCO) (Fig. 14.16i,j) [14.26]. They reveal a d-like symmetry, but not the one expected from simple Cooper pair scattering. Other effects such as magnetic polarization in the environment probably have to be taken into account [14.102]. Moreover, it has been found that magnetic Ni impurities exhibit a weaker scattering structure than Zn impurities [14.103]. Thus, BSCCO shows exactly the opposite behavior of the Nb discussed above (Fig. 14.16a,b). An interesting topic is the importance of inhomogeneities in HTCS materials. Evidence for inhomogeneities has indeed been found in underdoped materials, where puddles of the superconducting phase are shown to be embedded in non-superconducting areas [14.104].

Of course, vortices have also been investigated in HTCS materials [14.105]. Bound states are found, but at energies that are in disagreement with simple models, assuming a BCS-like d-wave superconductor [14.106, 107]. Theory predicts, instead, that the bound states are magnetic-field-induced spin-density waves stressing the competition between anti-ferromagnetic order and superconductivity in HTCS materials [14.108]. Since the spin density wave is accompanied by a charge density wave of half wavelength, it can be probed by STS [14.109]. Indeed, a checkerboard pattern of the right periodicity has been found in and around vortex cores in BSCCO (Fig. 14.16k). It exceeds the width of an individual vortex core, implying that the superconducting coherence length is different from the anti-ferromagnetic one.

Complex Systems (Manganites)

Complex phase diagrams are not restricted to HTCS materials (cuprates). They exist with similar complexity for other doped oxides such as manganites. Only a few studies of these materials have been performed by STS, mainly showing the inhomogeneous evolution of metallic and insulating phases [14.110, 111]. Similarities to the granular case of an underdoped HTCS material are obvious. Since inhomogeneities seem to be crucial in many of these materials, a local method such as STS might continue to be important for the understanding of their complex properties.

14.3.6 Imaging Spin Polarization: Nanomagnetism

Conventional STS couples to the LDOS, i. e., the charge distribution of the electronic states. Since electrons also have spin, it is desirable to also probe the spin distribution of the states. This can be achieved if the tunneling tip is covered by a ferromagnetic material [14.112]. The coating acts as a spin filter or, more precisely, the tunneling current depends on the relative angle α_{ij} between the spins of the tip and the sample according to $\cos(\alpha_{ij})$. In ferromagnets, the spins mostly have one preferential orientation along the so-called easy axis, i. e., a particular tip is not sensitive to spin orientations of the sample perpendicular to the spin orientation of the tip. Different tips have to be prepared to detect different spin orientations of the sample. Moreover, the magnetic stray field of the tip can perturb the spin orientation of the sample. To avoid this, a technique



Fig. 14.17 (a)–(d) Spin-polarized STM images of 1.65 monolayer of Fe deposited on a stepped W(110) surface measured at different B-fields, as indicated. Double layer and monolayer Fe stripes are formed on the W substrate; only the double layer stripes exhibit magnetic contrast with an out-of-plane sensitive tip as used here. *White* and *grey areas* correspond to different domains. Note that more white areas appear with increasing field. **(e)** STM image of an antiferromagnetic Mn monolayer on W(110). **(f)** Spin-polarized STM-image of the same surface (in-plane tip). The insets in **(e)** and **(f)** show the calculated STM and spin-polarized STM images, respectively, and the stick and ball models symbolize the atomic and the magnetic unit cell (**(a)–(f)** courtesy of M. Bode, Hamburg). **(g)** Spin-polarized STM image of a 6-nm-high Fe island on W(110) (in-plane tip). Four different areas are identified as four different domains with domain orientations as indicated by the *arrows*. **(h)** Spin-polarized STM image of the central area of an island; the size of the area is indicated by the rectangle in **(g)**; the measurement is performed with an out-of-plane sensitive tip showing that the magnetization turns out-of-plane in the center of the island

using anti-ferromagnetic Cr as a tip coating material has been developed [14.113]. This avoids stray fields, but still provides a preferential spin orientation of the few atoms at the tip apex that dominate the tunneling current. Depending on the thickness of the Cr coating, spin orientations perpendicular or parallel to the sample surface are prepared.

So far, the described technique has been used to image the evolution of magnetic domains with increasing B-field(Fig. 14.17a–d) [14.114], the antiferromagnetic order of a Mn monolayer on W(110) (Fig. 14.17e,f) [14.115], and the out-of-plane orientation predicted for a magnetic vortex core as it exists in the center of a Fe island exhibiting four domains in the flux closure configuration (Fig. 14.17g,h) [14.116].

Besides the obvious strong impact on nanomagnetism, the technique might also be used to investigate other electronic phases such as the proposed spin density wave around a HTCS vortex core.

14.4 Scanning Force Microscopy and Spectroscopy

SFSThe examples discussed in the previous section show the wide variety of physical questions that have been tackled with the help of LTSTM. Here, we turn to the other prominent scanning probe method that is applied at low temperatures, namely, SFM, which gives complementary information on sample properties on the atomic scale.

The ability to sensitively detect *forces* with spatial resolution down to the atomic scale is of great interest, since force is one of the most fundamental quantities in physics. Mechanical force probes usually consist of a cantilever with a tip at its free end that is brought close to the sample surface. The cantilever can be mounted parallel or perpendicular to the surface (general aspects of force probe designs are described in Chapt. 12). Basically, two methods exist to detect forces with cantilever-based probes – the *static* and the *dynamic* mode (see Chapt. 11). They can be used to generate a laterally resolved image (*microscopy* mode) or determine its distance dependence (*spectroscopy* mode). One can argue about the terminology, since spectroscopy is usually related to energies and not to distance dependences. Nevertheless, we will use it throughout the text, because it avoids lenghty paraphrases and is established in this sense throughout the literature.

In the static mode, a force that acts on the tip bends the cantilever. By measuring its deflection Δz the tip-sample force F_{ts} can be directly calculated with Hooke's law: $F_{\text{ts}} = c_z \cdot \Delta z$, where c_z denotes the spring constant of the cantilever. In the various dynamic modes, the cantilever is oscillated with amplitude A at or near its eigenfrequency f_0, but in some applications also off resonance. At ambient pressures or in liquids, amplitude modulation (AM-SFM) is used to detect amplitude changes or the phase shift between driving force and cantilever oscillation. In vacuum, the frequency shift Δf of the cantilever due to a tip-sample interaction is measured by frequency modulation technique (FM-SFM). The nomenclature is not standardized. Terms like tapping mode or intermittent contact mode are used instead of AM-SFM, and NC-AFM (noncontact atomic force microscopy) or DFM (dynamic force microscopy) instead of FM-SFM or FM-AFM. However, all these modes are *dynamic*, i. e., they involve an oscillating cantilever and can be used in the noncontact, as well as in the contact regime. Therefore, we believe that the best and most consistent way is to distinguish them by their different detection schemes. Converting the measured quantity (amplitude, phase, or frequency shift) into a physically meaningful quantity, e.g., the tip-sample interaction force F_{ts} or the force gradient $\partial F_{\text{ts}}/\partial z$, is not always straightforward and requires an analysis of the equation of motion of the oscillating tip (see Chaps. 15, 13).

Whatever method is used, the resolution of a cantilever-based force detection is fundamentally limited by its intrinsic *thermomechanical* noise. If the cantilever is in thermal equilibrium at a temperature T, the equipartition theorem predicts a thermally induced *root mean square* (rms) motion of the cantilever in z direction of $z_{\text{rms}} = (k_{\text{B}}T/c_{\text{eff}})^{1/2}$, where k_{B} is the Boltzmann constant and $c_{\text{eff}} = c_z + \partial F_{\text{ts}}/\partial z$. Note that usually $\mathrm{d}F_{\text{ts}}/\mathrm{d}z \gg c_z$ in contact and $\mathrm{d}F_{\text{ts}}/\mathrm{d}z < c_z$ in noncontact. Evidently, this fundamentally limits the force resolution in the static mode, particularly if operated in noncontact. Of course, the same is true for the different dynamic modes, because the thermal energy $k_{\text{B}}T$ excites the eigenfrequency f_0 of the cantilever. Thermal noise is *white* noise, i. e., its spectral density is flat. However, if the cantilever transfer function is taken into account, one can see that the thermal energy mainly excites f_0. This explains the term "thermo" in thermomechanical noise, but what is the "mechanical" part?

A more detailed analysis reveals that the thermally induced cantilever motion is given by

$$z_{\text{rms}} = \sqrt{\frac{2k_{\text{B}}TB}{\pi c_z f_0 Q}}\,, \tag{14.2}$$

where B is the measurement bandwidth and Q is the quality factor of the cantilever. Analog expressions can be obtained for all quantities measured in dynamic modes, because the deflection noise translates, e.g., into frequency noise [14.5]. Note that f_0 and c_z are correlated with each other via $2\pi f_0 = (c_z/m_{\text{eff}})^{1/2}$, where the effective mass m_{eff} depends on the geometry, density, and elasticity of the material. The Q-factor of the cantilever is related to the external damping of the cantilever motion in a medium and on the intrinsic damping within the material. This is the "mechanical" part of the fundamental cantilever noise.

It is possible to operate a low temperature force microscope directly immersed in the cryogen [14.117, 118] or in the cooling gas [14.119], whereby the cooling is simple and very effective. However, it is evident from (14.2) that the smallest fundamental noise is achievable in vacuum, where the Q-factors are more than 100 times larger than in air, and at low temperatures.

The best force resolution up to now, which is better than $1 \times 10^{-18}\,\mathrm{N/Hz}^{1/2}$, has been achieved by *Mamin* et al. [14.120] in vacuum at a temperature below 300 mK. Due to the reduced thermal noise and the lower thermal drift, which results in a higher stability of the tip-sample gap and a better signal-to-noise ratio, the highest resolution is possible at low temperatures in ultrahigh vacuum with FM-SFM. A vertical rms-noise below 2 pm [14.121, 122] and a force resolution below 1 aN [14.120] have been reported.

Besides the reduced noise, the application of force detection at low temperatures is motivated by the increased stability and the possibility to observe phenomena, which appear below a certain critical temperature T_c, as outlined at page 414. The experiments, which have been performed at low temperatures up until now, were motivated by at least one of these reasons and can be roughly divided into four groups: (i) atomic-scale imaging, (ii) force spectroscopy, (iii) investigation of quantum phenomena by measuring electrostatic forces, and (iv) utilizing magnetic probes to study ferromagnets, superconductors, and single spins. In the following, we describe some exemplary results.

14.4.1 Atomic-Scale Imaging

In a simplified picture, the dimensions of the tip end and its distance to the surface limit the lateral resolution of force microscopy, since it is a near-field technique. Consequently, atomic resolution requires a stable single atom at the tip apex that has to be brought within a distance of some tenths of a nanometer to an atomically flat surface. Both conditions can be fulfilled by FM-AFM, and nowadays *true* atomic resolution is routinely obtained (see Chapt. 13). However, the above statement says nothing about the nature and the underlying processes of imaging with atomic resolution. Si(111)-(7×7) was the first surface on which true atomic resolution was achieved [14.123], and several studies have been performed at low temperatures on this well-known material [14.124–126]. First principle simulations performed on semiconductors with a silicon tip revealed that *chemical* interactions, i. e., a significant charge redistribution between the dangling bonds of tip and sample, dominate the atomic-scale contrast [14.127–129]. On V-III semiconductors, it was found that only one atomic species, the group V atoms, is imaged as protrusions with a silicon tip [14.128, 129]. Furthermore, these simulations revealed that the sample, as well as the tip atoms are noticeably displaced from their equilibrium position due to the interaction forces. At low temperatures, both aspects could be observed with silicon tips on indium arsenide [14.121, 130].

Chemical Sensitivity of Force Microscopy

The (110) surface of the III-V semiconductor indium arsenide exhibits both atomic species in the top layer (see Fig. 14.18a). Therefore, this sample is well suited to study the chemical sensitivity of force microscopy [14.121]. In Fig. 14.18b, the usually observed atomic-scale contrast on InAs(110) is displayed. As predicted, the arsenic atoms, which are shifted by 80 pm above the indium layer due to the (1×1) relaxation, are imaged as protrusions. While this general appearance was similar for most tips, two other distinctively different contrasts were also observed: a second protru-



Fig. 14.18a–d The structure of InAs(110) as seen from top **(a)** and three FM-AFM images of this surface obtained with different tips at 14 K **(b)–(d)**. In **(b)**, only the arsenic atoms are imaged as protrusions, as predicted for a silicon tip. The two features in **(c)** and **(d)** corresponds to the zigzag arrangement of the indium and arsenic atoms. Since force microscopy is sensitive to short-range chemical forces, the appearance of the indium atoms can be associated with a chemically different tip apex

sion (c) and a sharp depression (d). The arrangement of these two features corresponds well to the zigzag configuration of the indium and arsenic atoms along the [1$\bar{1}$0]-direction. A sound explanation would be as follows: The contrast usually obtained with one feature per surface unit cell corresponds to a silicon-terminated tip, as predicted by simulations. A different atomic species at the tip apex, however, can result in a very different charge redistribution. Since the atomic-scale contrast is due to a chemical interaction, the two other contrasts would then correspond to a tip that has been accidentally contaminated with sample material (arsenic or indium-terminated tip apex). Nevertheless, this explanation has not yet been verified by simulations for this material.



Fig. 14.19a,b Two FM-AFM images of the identical indium-site point defect (presumably an indium vacancy) recorded at 14 K. If the tip is relatively far away, the theoretically predicted inward relaxation of two arsenic atoms adjacent to an indium vacancy is visible **(a)**. At a closer tip-sample distance **(b)**, the two arsenic atoms are pulled farther toward the tip compared to the other arsenic atoms, since they have only two instead of three bonds

Tip-Induced Atomic Relaxation

Schwarz et al. [14.121] were able to directly visualize the predicted tip-induced relaxation during atomic-scale imaging near a point defect. Figure 14.19 shows two FM-AFM images of the same point defect recorded with different constant frequency shifts on InAs(110), i. e., the tip was closer to the surface in (b) compared to (a). The arsenic atoms are imaged as protrusions with the used silicon tip. From the symmetry of the defect, an indium-site defect can be inferred, since the distance-dependent contrast is consistent with what has to be expected for an indium vacancy. This expectation is based on calculations performed for the similar III-V semiconductor GaP(110), where the two surface gallium atoms around a P-vacancy were found to relax downward [14.131]. This corresponds to the situation in Fig. 14.19a, where the tip is relatively far away and an inward relaxation of the two arsenic atoms is observed. The considerably larger attractive force in Fig. 14.19b, however, pulls the two arsenic atoms toward the tip. All other arsenic atoms are also pulled, but they are less displaced, because they have three bonds to the bulk, while the two arsenic atoms in the neighborhood of an indium vacancy have only two bonds. This direct experimental proof of the presence of tip-induced relaxations is also relevant for STM measurements, because the tip-sample distances are similar during atomic resolution imaging. Moreover, the result demonstrates that FM-AFM can probe elastic properties on an atomic level.

Imaging of Weakly Interacting van der Waals Surfaces

For weakly interacting van der Waals surfaces like the (0001) surface of graphite, much smaller atomic corrugation amplitudes are expected compared to strongly interacting surfaces such as semiconductors. In graphite, a layered material, the carbon atoms are covalently bonded and arranged in a honeycomb structure within the (0001) plane. Individual layers of (0001) planes (*ABA* . . . stacking) stick together only by weak van der Waals forces. Three distinctive sites exist on the surface: carbon atoms with (*A*-type) and without (*B*-type) a neighbor in the next graphite layer and the *hollow site* (H-site) in the hexagon center. Neither static contact force microscopy nor STM can resolve the three different sites. For both methods, the contrast is well understood and exhibits protrusions with a sixfold symmetry and a periodicity of 246 pm. In high resolution FM-AFM images acquired at low temperatures, a large maximum and two different minima have been resolved (see Fig. 14.20a). A simulation using the Lennard-Jones potential, in which the attractive part is given by the short-range interatomic van der Waals force, reproduced these three features very well. By comparison with the experimental data (cf. the solid and the dotted line in the section of Fig. 14.20a), the large maximum could be assigned to the hollow site, while the two different minima represent A- and B-type carbon atoms [14.132]. Note that the image contrast is inverted with respect the arrangement of the atoms, i. e., the minima correspond to the position of the carbon atoms. The carbon-carbon distance of only 142 pm is the smallest interatomic distance that has been resolved with FM-AFM so far. Moreover, the weak tip-sample interaction results in typical corrugation amplitudes around 10 pm peak-to-peak, i. e., just above the noise level [14.7].

While experiments on graphite basically gain advantages from the increased stability and signal-to-noise ratio at low temperatures, solid xenon (melting temperature $T_{\mathrm{m}} = 161$ K) can only be observed at sufficiently low temperatures [14.8]. In addition, xenon is a pure van der Waals crystal, and since it is an insulator, FM-AFM is the only real space method available today that allows the study of solid xenon on the atomic scale.



Fig. 14.20a,b FM-AFM images of graphite(0001) **(a)** and Xe(111) **(b)** recorded at 22 K. On the right side, line sections taken from the experimental data (*solid lines*) are compared to simulations (*dotted lines*). A- and B-type carbon atoms, as well as the hollow site (H-site) on graphite can be distinguished, but are imaged with inverted contrast, i. e., the carbon sites are displayed as minima. Such an inversion does not occur on Xe(111)

Allers et al. [14.8] adsorbed a well-ordered xenon film on cold graphite(0001) ($T < 55$ K) and subsequently studied it at 22 K by FM-AFM (see Fig. 14.20b). The sixfold symmetry and the distance between the protrusions correspond well with the nearest neighbor distance in the closed, packed (111) plane of bulk xenon, which crystallizes in the face-centered cubic structure. A comparison between experiment and simulation confirmed that the protrusions correspond to the position of the xenon atoms [14.133]. However, the simulated corrugation amplitudes do not fit as well as for graphite (see sections in Fig. 14.20b). A possible reason is that tip-induced relaxations, which were not considered in the simulations, are more important for this pure van der Waals crystal xenon than they are for graphite, because in-plane graphite exhibits strong covalent bonds. Nevertheless, the results demonstrated that a weakly bonded van der Waals crystal could be imaged nondestructively on the atomic scale for the first time.

14.4.2 Force Spectroscopy

A wealth of information about the nature of the tip-sample interaction can be obtained by measuring its distance dependence. This is usually done by recording the measured quantity (deflection, frequency shift, amplitude change, phase shift) and applying an appropriate voltage ramp to the z-electrode of the scanner piezo, while the z-feedback is switched off. According to (14.2), low temperatures and high Q-factors (vacuum) considerably increase the force resolution. In the static mode, long-range forces and contact forces can be examined. Force measurements at small tip-sample distances are inhibited by the *jump-to-contact* phenomenon: If the force gradient $\partial F_{\mathrm{ts}}/\partial z$ becomes larger than the spring constant c_z, the cantilever cannot resist the attractive tip-sample forces and the tip snaps onto the surface. Sufficiently large spring constants prevent this effect, but reduce the force resolution. In the dynamic modes, the jump-to-contact can be avoided due to the additional restoring force ($c_z A$) at the lower turnaround point. The highest sensitivity can be achieved in vacuum by using the FM technique, i. e., by recording $\Delta f(z)$-curves. An alternative FM spectroscopy method, the recording of $\Delta f(A)$-curves, has been suggested by *Hölscher* et al. [14.134]. Note that if the amplitude is much larger than the characteristic decay length of the tip-sample force, the frequency shift cannot simply be converted into force gradients by using $\partial F_{ts}/\partial z = 2c_z \cdot \Delta f/f_0$ [14.135]. Several methods have been published to convert $\Delta f(z)$ data into the tip-sample potential $V_{ts}(z)$ and tip-sample force $F_{ts}(z)$ (see, e.g., [14.136, 137]).

Measurement of Interatomic Forces at Specific Atomic Sites

FM force spectroscopy has been successfully used to measure and determine quantitatively the short-range chemical force between the foremost tip atom and specific surface atoms [14.109, 138, 139]. Figure 14.21 displays an example for the quantitative determination of the short-range force. Figure 14.21a shows two $\Delta f(z)$-curves measured with a silicon tip above a corner hole and above an adatom. Their position is indicated by arrows in the inset, which displays the atomically resolved Si(111)-(7×7) surface. The two curves differ from each other only for small tip-sample distances, because the long-range forces do not contribute to the atomic-scale contrast. The low, thermally induced lateral drift and the high stability at low temperatures were required to precisely address the two specific sites. To extract the short-range force, the long-range van der Waals and/or electrostatic forces can be subtracted from the total force. The grey curve in Fig. 14.21b has been reconstructed from the $\Delta f(z)$-curve recorded above an adatom and represents the total force. After removing the long-range contribution from the data, the much steeper black line is obtained, which corresponds to the short-range force between the adatom and the atom at the tip apex. The measured maximum attractive force (-2.1 nN) agrees well with first principle calculations (-2.25 nN).



Fig. 14.21a,b FM force spectroscopy on specific atomic sites at 7.2 K. In **(a)**, an FM-SFM image of the Si(111)-(7×7) surface is displayed together with two $\Delta f(z)$-curves, which have been recorded at the positions indicated by the *arrows*, i. e., above the cornerhole (*brown*) and above an adatom (*black*). In **(b)**, the total force above an adatom (*brown line*) has been recovered from the $\Delta f(z)$-curve. After subtraction of the long-range part, the short-range force can be determined (*black line*) (courtesy of H. J. Hug; cf. [14.138])

Three-dimensional Force Field Spectroscopy

Further progress with the FM technique has been made by *Hölscher* et al. [14.140]. They acquired a complete 3-D force field on NiO(001) with atomic resolution (*3-D force field spectroscopy*). In Fig. 14.22a, the atomically resolved FM-AFM image of NiO(001) is shown together with the used coordinate system and the tip to illustrate the measurement principle. NiO(001) crystallizes in the rock salt structure. The distance between the protrusions corresponds to the lattice constant of 417 pm, i. e., only one type of atom (most likely the oxygen) is imaged as protrusion. In an area of 1 nm × 1 nm, 32 × 32 individual $\Delta f(z)$-curves have been recorded at every (x, y) image point and converted into $F_{ts}(z)$-curves. The $\Delta f(x, y, z)$ data set is thereby converted into the 3-D force field $F_{ts}(x, y, z)$. Figure 14.22b, where a specific x-z-plane is displayed, demonstrates that atomic resolution is achieved. It represents a 2-D cut $F_{ts}(x, y = \text{const}, z)$ along the [100]-direction (corresponding to the shaded slice marked in Fig. 14.22a). Since a large number of curves have been recorded, *Langkat* et al. [14.139] could evaluate the whole data set by standard statistical means to extract the long- and short-range forces. A possible future application of 3-D force field spectroscopy could be to map the short-range forces of complex molecules with functionalized tips in order to locally resolve their chemical reactivity.



Fig. 14.22a,b Principle of the 3-D force filed spectroscopy method **(a)** and a 2-D cut through the 3-D force field$F_{\mathrm{ts}}(x,y,z)$ recorded at 14 K **(b)**. At all 32 × 32 image points of the 1 nm × 1 nm large scan area on NiO(001), a $\Delta f(z)$-curve has been recorded. The obtained $\Delta f(x, y, z)$ data set is then converted into the 3-D tip-sample force field $F_{\mathrm{ts}}(x, y, z)$. The *shaded slice* $F_{\mathrm{ts}}(x, y = \text{const}, z)$ in **(a)** corresponds to a cut along the [100]-direction and demonstrates that atomic resolution has been obtained, because the distance between the protrusions corresponds well to the lattice constant of nickel oxide

Noncontact Friction

Another approach to achieve small tip-sample distances in combination with high force sensitivity is to use soft springs in a perpendicular configuration. The much higher cantilever stiffness along the cantilever axis prevents the jump-to-contact, but the lateral resolution is limited by the magnitude of the oscillation amplitude. However, with such a setup at low temperatures, *Stipe* et al. [14.141] measured the distance dependence of the very small force due to noncontact friction between tip and sample in vacuum. The effect was attributed to electric charges, which are moved parallel to the surface by the oscillating tip. Since the topography was not recorded in situ, the influence of contaminants or surface steps remained unknown.

14.4.3 Electrostatic Force Microscopy

Electrostatic forces are readily detectable by a force microscope, because tip and sample can be regarded as two electrodes of a capacitor. If they are electrically connected via their back sides and have different work functions, electrons will flow between tip and sample until their Fermi levels are equalized. As a result, an electric field and, consequently, an attractive electrostatic force exists between them at zero bias. This *contact potential difference* can be balanced by applying an appropriate bias voltage. It has been demonstrated that individual doping atoms in semiconducting materials can be detected by electrostatic interactions due to the local variation of the surface potential around them [14.142, 143].

Detection of Edge Channels in the Quantum Hall Regime

At low temperatures, electrostatic force microscopy has been used to measure the electrostatic potential in the quantum Hall regime of a *two-dimensional electron gas* (2-DEG) buried in epitaxially grown GaAs/AlGaAs heterostructures [14.144–147]. In the 2-DEG, electrons can move freely in the x-y-plane, but they cannot move in z-direction. Electrical transport properties of a 2-DEG are very different compared to normal metallic conduction. Particularly, the Hall resistance $R_{\mathrm{H}} = h/ne^2$ (where h represents Planck's constant, e is the electron charge, and $n = 1, 2, \ldots$) is quantized in the quantum Hall regime, i. e., at sufficiently low temperatures ($T < 4\,\mathrm{K}$) and high magnetic fields (up to 20 T). Under these conditions, theoretical calculations predict the existence of *edge channels* in a Hall bar. A Hall bar is a strip conductor that is contacted in a specific way to allow longitudinal and transversal transport measurements in a perpendicular magnetic field. The current is not evenly distributed over the cross section of the bar, but passes mainly along rather thin paths close to the edges. This prediction has been verified by measuring profiles of the electrostatic potential across a Hall bar in different perpendicular external magnetic fields [14.144–146].

Figure 14.23a shows the experimental setup used to observe these edge channels on top of a Hall bar with a force microscope. The tip is positioned above the surface of a Hall bar under which the 2-DEG is buried. The direction of the magnetic field is oriented perpendicular to the 2-DEG. Note that although the 2-DEG is located several tens of nanometers below the surface, its influence on the electrostatic surface potential can be detected. In Fig. 14.23b, the results of scans perpendicular to the Hall bar are plotted against the magnitude of the external magnetic field. The value of the electrostatic potential is grey-coded in arbitrary units. In certain field ranges, the potential changes linearly across the Hall bar, while in other field ranges the potential drop is confined to the edges of the Hall bar. The predicted edge channels can explain this behavior. The periodicity of the phenomenon is related to the filling factor ν, i. e., the number of Landau levels that are filled with electrons (see also Sect. 14.3.4). Its value depends on $1/B$



Fig. 14.23a,b Configuration of the Hall bar within a low temperature ($T < 1$ K) force microscope **(a)** and profiles (y-axis) at different magnetic field (x-axis) of the electrostatic potential across a 14-µm-wide Hall bar in the quantum Hall regime **(b)**. The external magnetic field is oriented perpendicular to the 2-DEG, which is buried below the surface. *Bright* and *dark regions* reflect the characteristic changes of the electrostatic potential across the Hall bar at different magnetic fields and can be explained by the existence of the theoretically predicted edge channels (courtesy of E. Ahlswede; cf. [14.146])

and is proportional to the electron concentration n_e in the 2-DEG ($\nu = n_e h/eB$, where h represents Planck's constant and e the electron charge).

14.4.4 Magnetic Force Microscopy

To detect magnetostatic tip-sample interactions with magnetic force microscopy (MFM), a ferromagnetic probe has to be used. Such probes are readily prepared by evaporating a thin magnetic layer, e.g., 10 nm iron, onto the tip. Due to the in-plane shape anisotropy of thin films, the magnetization of such tips lies predominantly along the tip axis, i. e., perpendicular to the surface. Since magnetostatic interactions are long-range, they can be separated from the topography by scanning in a certain constant height (typically around 20 nm) above the surface, where the z-component of the sample stray field is probed (see Fig. 14.24a). Therefore, MFM is always operated in noncontact. The signal from the cantilever is directly recorded while the z-feedback is switched off. MFM can be operated in the static mode or in the dynamic modes (AM-MFM at ambient pressures and FM-MFM in vacuum). A lateral resolution below 50 nm can be routinely obtained.

Observation of Domain Patterns

MFM is widely used to visualize domain patterns of ferromagnetic materials. At low temperatures, *Moloni* et al. [14.148] observed the domain structure of magnetite below its Verwey transition temperature ($T_V = 122$ K), but most of the work concentrated on thin films of $La_{1-x}Ca_xMnO_3$ [14.149–151]. Below T_V, the conductivity decreases by two orders of magnitude and a small structural distortion is observed. The domain structure of this mixed valence manganite is of great interest, because its resistivity strongly depends on the external magnetic field, i. e., it exhibits a large colossal magneto resistive effect. To investigate the field dependence of domain patterns in ambient conditions, electromagnets have to be used. They can cause severe thermal drift problems due to Joule-heating of the coils by large currents. Field on the order of 100 mT can be achieved. In contrast, much larger fields (more than 10 T) can be rather easily produced by implementing a superconducting magnet in low temperature setups. With such a design, *Liebmann* et al. [14.151] recorded the domain structure along the major hysteresis loop of $La_{0.7}Ca_{0.3}MnO_3$ epitaxially grown on $LaAlO_3$ (see Fig. 14.24b–f). The film geometry (thickness is 100 nm) favors an in-plane magnetization, but the lattice mismatch with the substrate induces an out-of-plane anisotropy. Thereby, an irregular pattern of strip domains appears in zero field. If the external magnetic field is increased, the domains with anti-parallel orientation shrink and finally disappear in saturation (see Fig. 14.24b,c). The residual contrast in saturation (d) reflects topographic features. If the field is decreased after saturation (see Fig. 14.24e,f), cylindrical domains first nucleate and then start to grow. At zero field, the maze-type domain pattern has been evolved again.



Fig. 14.24a–f Principle of MFM operation **(a)** and field-dependent domain structure of a ferromagnetic thin film **(b)–(f)** recorded at 5.2 K with FM-MFM. All images were recorded on the same 4 µm × 4 µm large scan area. The $La_{0.7}Ca_{0.3}MnO_3/LaAlO_3$ system exhibits a substrate-induced out-of-plane anisotropy. *Bright* and *dark areas* are visible and correspond to attractive and repulsive magnetostatic interactions, respectively. The series shows how the domain pattern evolves along the major hysteresis loop from, i. e., zero field to saturation at 600 mT and back to zero field

Such data sets can be used to analyze domain nucleation and the domain growth mode. Moreover, due to the negligible drift, domain structure and surface morphology can be directly compared, because every MFM can be used as a regular topography-imaging force microscope.

Detection of Individual Vortices in Superconductors

Numerous low temperature MFM experiments have been performed on superconductors [14.152–159]. Some basic features of superconductors have been mentioned already in Sect. 14.3.5. The main difference of STM/STS compared to MFM is the high sensitivity to the electronic properties of the surface. Therefore, careful sample preparation is a prerequisite. This is not so important for MFM experiments, since the tip is scanned at a certain distance above the surface.

Superconductors can be divided into two classes with respect to their behavior in an external magnetic field. For type-I superconductors, any magnetic flux is entirely excluded below their critical temperature T_c (Meissner effect), while for type-II superconductors, cylindrical inclusions (*vortices*) of normal material exist in a superconducting matrix (*vortex* state). The radius of the vortex *core*, where the Cooper pair density decreases to zero, is on the order of the coherence length ξ. Since the superconducting gap vanishes in the core, they can be detected by STS (see Sect. 14.3.5). Additionally, each vortex contains one magnetic quantum flux $\Phi = h/2e$ (where h represents Planck's constant and e the electron charge). Circular supercurrents around the core screen the magnetic field associated with a vortex; their radius is given by the London penetration depth λ of the material. This magnetic field of the vortices can be detected by MFM. Investigations have been performed on the two most popular copper oxide high-T_c superconductors, $YBa_2Cu_3O_7$ [14.152, 153, 155] and $Bi_2Sr_2CaCu_2O_8$ [14.153, 159], on the only elemental conventional type-II superconductor Nb [14.156, 157], and on the layered compound crystal $NbSe_2$ [14.154, 156].

Most often, vortices have been generated by cooling the sample from the normal state to below T_c in an external magnetic field. After such a *field cooling* procedure, the most energetically favorable vortex arrangement is a regular triangular Abrikosov lattice. *Volodin* et al. [14.154] were able to observe such an Abrikosov lattice on $NbSe_2$. The intervortex distance d is related to the external field during B cool down



Fig. 14.25a,b Two $5\,\mu\mathrm{m}\times5\,\mu\mathrm{m}$ FM-MFM images of vortices in a niobium thin film after field-cooling at 0.5 mT **(a)** and -0.5 mT **(b)**, respectively. Since the external magnetic field was parallel in **(a)** and antiparallel in **(b)** with respect to the tip magnetization, the vortices exhibit reversed contrast. Strong pinning dominates the position of the vortices, since they appear at identical locations in **(a)** and **(b)** and are not arranged in a regular Abrikosov lattice (courtesy of P. Grütter; cf. [14.157])

via $d=(4/3)^{1/4}(\Phi/B)^{1/2}$. Another way to introduce vortices into a type-II superconductor is vortex penetration from the edge by applying a magnetic field at temperatures below T_c. According to the Bean model, a vortex density gradient exists under such conditions within the superconducting material. *Pi* et al. [14.159] slowly increased the external magnetic field until the vortex front approaching from the edge reached the scanning area.

If the vortex configuration is dominated by the *pinning* of vortices at randomly distributed structural defects, no Abrikosov lattice emerges. The influence of pinning centers can be studied easily by MFM, because every MFM can be used to scan the topography in its AFM mode. This has been done for natural growth defects by *Moser* et al. [14.155] on $YBa_2Cu_3O_7$ and for $YBa_2Cu_3O_7$ and niobium thin films, respectively, by *Volodin* et al. [14.158]. *Roseman* et al. [14.160] investigated the formation of vortices in the presence of an artificial structure on niobium films, while *Pi* et al. [14.159] produced columnar defects by heavy ion bombardment in a $Bi_2Sr_2CaCu_2O_8$ single crystal to study the strong pinning at these defects.

Figure 14.25 demonstrates that MFM is sensitive to the polarity of vortices. In Fig. 14.25a, six vortices have been produced in a niobium film by field cooling in $+0.5$ mT. External magnetic field and tip magnetization are parallel, and, therefore, the tip-vortex interaction is attractive (bright contrast). To remove the vortices, the niobium was heated above T_c (≈ 9 K). Thereafter, vortices of opposite polarity were produced by field cooling in -0.5 mT, which appear dark in Fig. 14.25b. The vortices are probably bound to strong pinning sites, because the vortex positions are identical in both images of Fig. 14.25. By imaging the vortices at different scanning heights, *Roseman* et al. [14.157] tried to extract values for the London penetration depth from the scan height dependence of their profiles. While good qualitative agreement with theoretical predictions has been found, the absolute values do not agree with published literature values. The disagreement was attributed to the convolution between tip and vortex stray field. Better values might be obtained with calibrated tips.

Toward Single Spin Detection

So far, only collective magnetic phenomena like ferromagnetic domains have been observed via magnetostatic tip-sample interactions detected by MFM. However, magnetic ordering exists due to the exchange interaction between the electron spins of neighboring atoms in a solid. The most energetically favorable situation can be either ferromagnetic (parallel orientation) or anti-ferromagnetic (anti-parallel orientation) ordering. It has been predicted that the exchange force between an individual spin of a magnetically ordered sample and the spin of the foremost atom of a magnetic tip can be detected at sufficiently small tip-sample distances [14.161, 162].

The experimental realization, however, is very difficult, because the exchange force is about a factor of ten weaker and of even shorter range than the chemical interactions that are responsible for the atomic-scale contrast. FM-AFM experiments with a ferromagnetic tip have been performed on the anti-ferromagnetic NiO(001) surface at room temperature [14.163] and with a considerable better signal-to-noise ratio at low temperatures [14.122]. Although it was possible to achieve atomic resolution, a periodic contrast that could be attributed to the anti-ferromagnetically ordered spins of the nickel atoms could not be observed.

Even more ambitious is the proposed detection of individual nuclear spins by magnetic resonance force microscopy (MRFM) using a magnetic tip [14.164, 165]. The interest in this technique is driven by the possibility of reaching subsurface true 3-D imaging with atomic resolution and chemical specificity. The idea of MRFM is to combine aspects of force microscopy (atomic resolution capability) with nuclear magnetic resonance (3-D imaging and elemental selectivity). Low temperatures are required, because the forces are extremely small.

Up until now, no individual spins have been detected by MRFM. However, electron spin resonance [14.166, 167], nuclear magnetic resonance [14.168], and ferromagnetic resonance [14.169] experiments of spin ensembles have been performed with micrometer resolution. On the way toward single spin detection, the design of ultrasensitive cantilevers made considerable progress, and the detection of forces below 1×10^{-18} N has been achieved [14.120].

References

14.1 G. Binnig, H. Rohrer, Ch. Gerber, E. Weibel: Surface studies by scanning tunneling microscopy, Phys. Rev. Lett. **49** (1982) 57–61

14.2 R. Wiesendanger: *Scanning Probe Microscopy and Spectroscopy* (Cambridge Univ. Press, Cambridge 1994)

14.3 M. Tinkham: *Introduction to Superconductivity* (McGraw-Hill, New York 1996)

14.4 J. Kondo: Theory of dilute magnetic alloys, Solid State Phys. **23** (1969) 183–281

14.5 T. R. Albrecht, P. Grütter, H. K. Horne, D. Rugar: Frequency modulation detection using high-Q cantilevers for enhanced force microscope sensitivity, J. Appl. Phys. **69** (1991) 668–673

14.6 F. J. Giessibl, H. Bielefeld, S. Hembacher, J. Mannhart: Calculation of the optimal imaging parameters for frequency modulation atomic force microscopy, Appl. Surf. Sci. **140** (1999) 352–357

14.7 W. Allers, A. Schwarz, U. D. Schwarz, R. Wiesendanger: Dynamic scanning force microscopy at low temperatures on a van der Waals surface: graphite(0001), Appl. Surf. Sci. **140** (1999) 247–252

14.8 W. Allers, A. Schwarz, U. D. Schwarz, R. Wiesendanger: Dynamic scanning force microscopy at low temperatures on a noble-gas crystal: atomic resolution on the xenon(111) surface, Europhys. Lett. **48** (1999) 276–279

14.9 M. Morgenstern, D. Haude, V. Gudmundsson, C. Wittneven, R. Dombrowski, R. Wiesendanger: Origin of Landau oscillations observed in scanning tunneling spectroscopy on *n*-InAs(110), Phys. Rev. B **62** (2000) 7257–7263

14.10 D. M. Eigler, P. S. Weiss, E. K. Schweizer, N. D. Lang: Imaging Xe with a low-temperature scanning tunneling microscope, Phys. Rev. Lett. **66** (1991) 1189–1192

14.11 P. S. Weiss, D. M. Eigler: Site dependence of the apparent shape of a molecule in scanning tunneling micoscope images: Benzene on Pt{111}, Phys. Rev. Lett. **71** (1992) 3139–3142

14.12 D. M. Eigler, E. K. Schweizer: Positioning single atoms with a scanning tunneling microscope, Nature **344** (1990) 524–526

14.13 H. Hug, B. Stiefel, P. J. A. van Schendel, A. Moser, S. Martin, H.-J. Güntherodt: A low temperature ultrahigh vacuum scanning force microscope, Rev. Sci. Instrum. **70** (1999) 3627–3640

14.14 S. Behler, M. K. Rose, D. F. Ogletree, F. Salmeron: Method to characterize the vibrational response of a beetle type scanning tunneling microscope, Rev. Sci. Instrum. **68** (1997) 124–128

14.15 C. Wittneven, R. Dombrowski, S. H. Pan, R. Wiesendanger: A low-temperature ultrahigh-vacuum scanning tunneling microscope with rotatable magnetic field, Rev. Sci. Instrum. **68** (1997) 3806–3810

14.16 W. Allers, A. Schwarz, U. D. Schwarz, R. Wiesendanger: A scanning force microscope with atomic resolution in ultrahigh vacuum and at low temperatures, Rev. Sci. Instrum. **69** (1998) 221–225

14.17 G. Dujardin, R. E. Walkup, Ph. Avouris: Dissociation of individual molecules with electrons from the tip of a scanning tunneling microscope, Science **255** (1992) 1232–1235

14.18 H. J. Lee, W. Ho: Single-bond formation and characterization with a scanning tunneling microscope, Science **286** (1999) 1719–1722

14.19 R. Berndt, R. Gaisch, J. K. Gimzewski, B. Reihl, R. R. Schlittler, W. D. Schneider, M. Tschudy: Photon emission at molecular resolution induced by a scanning tunneling microscope, Science **262** (1993) 1425–1427

14.20 B. G. Briner, M. Doering, H. P. Rust, A. M. Bradshaw: Microscopic diffusion enhanced by adsorbate interaction, Science **278** (1997) 257–260

14.21 J. Kliewer, R. Berndt, E. V. Chulkov, V. M. Silkin, P. M. Echenique, S. Crampin: Dimensionality effects in the lifetime of surface states, Science **288** (2000) 1399–1401

14.22 M. F. Crommie, C. P. Lutz, D. M. Eigler: Imaging standing waves in a two-dimensional electron gas, Nature **363** (1993) 524–527

14.23 B. C. Stipe, M. A. Rezaei, W. Ho: Single-molecule vibrational spectroscopy and microscopy, Science **280** (1998) 1732–1735

14.24 H. J. Lee, W. Ho: Structural determination by single-molecule vibrational spectroscopy and microscopy: Contrast between copper and iron carbonyls, Phys. Rev. B **61** (2000) R16347–R16350

14.25 C. W. J. Beenakker, H. van Houten: Quantum transport in semiconductor nanostructures, Solid State Phys. **44** (1991) 1–228

14.26 S. H. Pan, E. W. Hudson, K. M. Lang, H. Eisaki, S. Uchida, J. C. Davis: Imaging the effects of individual zinc impurity atoms on superconductivity in $Bi_2Sr_2CaCu_2O_{8+\delta}$, Nature **403** (2000) 746–750

14.27 R. S. Becker, J. A. Golovchenko, B. S. Swartzentruber: Atomic-scale surface modifications using a tunneling microscope, Nature **325** (1987) 419–42

14.28 J. A. Stroscio, D. M. Eigler: Atomic and molecular manipulation with the scanning tunneling microscope, Science **254** (1991) 1319–1326

14.29 L. Bartels, G. Meyer, K. H. Rieder: Basic steps of lateral manipulation of single atoms and diatomic clusters with a scanning tunneling microscope, Phys. Rev. Lett. **79** (1997) 697–700

14.30 J. J. Schulz, R. Koch, K. H. Rieder: New mechanism for single atom manipulation, Phys. Rev. Lett. **84** (2000) 4597–4600

14.31 T. C. Shen, C. Wang, G. C. Abeln, J. R. Tucker, J. W. Lyding, Ph. Avouris, R. E. Walkup: Atomic-scale desorption through electronic and vibrational excitation mechanisms, Science **268** (1995) 1590–1592

14.32 T. Komeda, Y. Kim, M. Kawai, B. N. J. Persson, H. Ueba: Lateral hopping of molecules induced by excitations of internal vibration mode, Science **295** (2002) 2055–2058

14.33 Y. W. Mo: Reversible rotation of antimony dimers on the silicon(001) surface with a scanning tunneling microscope, Science **261** (1993) 886–888

14.34 B. C. Stipe, M. A. Rezaei, W. Ho: Inducing and viewing the rotational motion of a single molecule, Science **279** (1998) 1907–1909

14.35 F. Moresco, G. Meyer, K. H. Rieder, H. Tang, A. Gourdon, C. Joachim: Conformational changes of single molecules by scanning tunneling microscopy manipulation: a route to molecular switching, Phys. Rev. Lett. **86** (2001) 672–675

14.36 S. W. Hla, L. Bartels, G. Meyer, K. H. Rieder: Inducing all steps of a chemical reaction with the scanning tunneling microscope tip: Towards single molecule engineering, Phys. Rev. Lett. **85** (2000) 2777–2780

14.37 E. Ganz, S. K. Theiss, I. S. Hwang, J. Golovchenko: Direct measurement of diffusion by hot tunneling microscopy: Activations energy, anisotropy, and long jumps, Phys. Rev. Lett. **68** (1992) 1567–1570

14.38 M. Schuhnack, T. R. Linderoth, F. Rosei, E. Laegsgaard, I. Stensgaard, F. Besenbacher: Long jumps in the surface diffusion of large molecules, Phys. Rev. Lett. **88** (2002) 156102, 1–4

14.39 L. J. Lauhon, W. Ho: Direct observation of the quantum tunneling of single hydrogen atoms with a scanning tunneling microscope, Phys. Rev. Lett. **85** (2000) 4566–4569

14.40 N. Kitamura, M. Lagally, M. B. Webb: Real-time observation of vacancy diffusion on Si(001)-(2 × 1) by scanning tunneling microscopy, Phys. Rev. Lett. **71** (1993) 2082–2085

14.41 M. Morgenstern, T. Michely, G. Comsa: Onset of interstitial diffusion determined by scanning tunneling microscopy, Phys. Rev. Lett. **79** (1997) 1305–1308

14.42 K. Morgenstern, G. Rosenfeld, B. Poelsema, G. Comsa: Brownian motion of vacancy islands on Ag(111), Phys. Rev. Lett. **74** (1995) 2058–2061

14.43 B. Reihl, J. H. Coombs, J. K. Gimzewski: Local inverse photoemission with the scanning tunneling microscope, Surf. Sci. **211–212** (1989) 156–164

14.44 R. Berndt, J. K. Gimzewski, P. Johansson: Inelastic tunneling excitation of tip-induced plasmon modes on noble-metal surfaces, Phys. Rev. Lett. **67** (1991) 3796–3799

14.45 P. Johansson, R. Monreal, P. Apell: Theory for light emission from a scanning tunneling microscope, Phys. Rev. B **42** (1990) 9210–9213

14.46 J. Aizpurua, G. Hoffmann, S. P. Apell, R. Berndt: Electromagnetic coupling on an atomic scale, Phys. Rev. Lett. **89** (2002) 156803, 1–4

14.47 G. Hoffmann, J. Kliewer, R. Berndt: Luminescence from metallic quantum wells in a scanning tunneling microscope, Phys. Rev. Lett. **78** (2001) 176803, 1–4

14.48 A. Downes, M. E. Welland: Photon emission from Si(111)-(7 × 7) induced by scanning tunneling microscopy: atomic scale and material contrast, Phys. Rev. Lett. **81** (1998) 1857–1860

14.49 M. Kemerink, K. Sauthoff, P. M. Koenraad, J. W. Geritsen, H. van Kempen, J. H. Wolter: Optical detection of ballistic electrons injected by a scanning-tunneling microscope, Phys. Rev. Lett. **86** (2001) 2404–2407

14.50 J. Tersoff, D. R. Hamann: Theory and application for the scanning tunneling microscope, Phys. Rev. Lett. **50** (1983) 1998–2001

14.51 C. J. Chen: *Introduction to Scanning Tunneling Microscopy* (Oxford Univ. Press, Oxford 1993)

14.52 J. Winterlin, J. Wiechers, H. Brune, T. Gritsch, H. Hofer, R. J. Behm: Atomic-resolution imaging of close-packed metal surfaces by scanning tunneling microscopy, Phys. Rev. Lett. **62** (1989) 59–62

14.53 A. L. Vazquez de Parga, O. S. Hernan, R. Miranda, A. Levy Yeyati, N. Mingo, A. Martin-Rodero, F. Flores: Electron resonances in sharp tips and their role in tunneling spectroscopy, Phys. Rev. Lett. **80** (1998) 357–360

14.54 S. H. Pan, E. W. Hudson, J. C. Davis: Vacuum tunneling of superconducting quasiparticles from atomically sharp scanning tunneling microscope tips, Appl. Phys. Lett. **73** (1998) 2992–2994

14.55 J. T. Li, W. D. Schneider, R. Berndt, O. R. Bryant, S. Crampin: Surface-state lifetime measured by scanning tunneling spectroscopy, Phys. Rev. Lett. **81** (1998) 4464–4467

14.56 L. Bürgi, O. Jeandupeux, H. Brune, K. Kern: Probing hot-electron dynamics with a cold scanning tunneling microscope, Phys. Rev. Lett. **82** (1999) 4516–4519

14.57 J. W. G. Wildoer, C. J. P. M. Harmans, H. van Kempen: Observation of Landau levels at the InAs(110) surface by scanning tunneling spectroscopy, Phys. Rev. B **55** (1997) R16013–R16016

14.58 M. Morgenstern, V. Gudmundsson, C. Wittneven, R. Dombrowski, R. Wiesendanger: Nonlocality of the exchange interaction probed by scanning tunneling spectroscopy, Phys. Rev. B **63** (2001) 201301(R), 1–4

14.59 M. V. Grishin, F. I. Dalidchik, S. A. Kovalevskii, N. N. Kolchenko, B. R. Shub: Isotope effect in the vibrational spectra of water measured in experiments with a scanning tunneling microscope, JETP Lett. **66** (1997) 37–40

14.60 A. Hewson: *From the Kondo Effect to Heavy Fermions* (Cambridge Univ. Press, Cambridge 1993)

14.61 V. Madhavan, W. Chen, T. Jamneala, M. F. Crommie, N. S. Wingreen: Tunneling into a single magnetic atom: Spectroscopic evidence of the Kondo resonance, Science **280** (1998) 567–569

14.62 J. Li, W. D. Schneider, R. Berndt, B. Delley: Kondo scattering observed at a single magnetic impurity, Phys. Rev. Lett. **80** (1998) 2893–2896

14.63 T. W. Odom, J. L. Huang, C. L. Cheung, C. M. Lieber: Magnetic clusters on single-walled carbon nanotubes: the Kondo effect in a one-dimensional host, Science **290** (2000) 1549–1552

14.64 M. Ouyang, J. L. Huang, C. L. Cheung, C. M. Lieber: Energy gaps in metallic single-walled carbon nanotubes, Science **292** (2001) 702–705

14.65 U. Fano: Effects of configuration interaction on intensities and phase shifts, Phys. Rev. **124** (1961) 1866–1878

14.66 H. C. Manoharan, C. P. Lutz, D. M. Eigler: Quantum mirages formed by coherent projection of electronic structure, Nature **403** (2000) 512–515

14.67 O. Y. Kolesnychenko, R. de Kort, M. I. Katsnelson, A. I. Lichtenstein, H. van Kempen: Real-space observation of an orbital Kondo resonance on the Cr(001) surface, Nature **415** (2002) 507–509

14.68 H. A. Mizes, J. S. Foster: Long-range electronic perturbations caused by defects using scanning tunneling microscopy, Science **244** (1989) 559–562

14.69 P. T. Sprunger, L. Petersen, E. W. Plummer, E. Laegsgaard, F. Besenbacher: Giant Friedel oscillations on beryllium (0001) surface, Science **275** (1997) 1764–1767

14.70 P. Hofmann, B. G. Briner, M. Doering, H. P. Rust, E. W. Plummer, A. M. Bradshaw: Anisotropic two-dimensional Friedel oscillations, Phys. Rev. Lett. **79** (1997) 265–268

14.71 E. J. Heller, M. F. Crommie, C. P. Lutz, D. M. Eigler: Scattering and adsorption of surface electron waves in quantum corrals, Nature **369** (1994) 464–466

14.72 M. C. M. M. van der Wielen, A. J. A. van Roij, H. van Kempen: Direct observation of Friedel oscillations around incorporated $\mathrm{Si_{Ga}}$ dopants in GaAs by low-temperature scanning tunneling microscopy, Phys. Rev. Lett. **76** (1996) 1075–1078

14.73 O. Millo, D. Katz, Y. W. Cao, U. Banin: Imaging and spectroscopy of artificial-atom states in core/shell nanocrystal quantum dots, Phys. Rev. Lett. **86** (2001) 5751–5754

14.74 L. C. Venema, J. W. G. Wildoer, J. W. Janssen, S. J. Tans, L. J. T. Tuinstra, L. P. Kouwenhoven, C. Dekker: Imaging electron wave functions of quantized energy levels in carbon nanotubes, Nature **283** (1999) 52–55

14.75 S. G. Lemay, J. W. Jannsen, M. van den Hout, M. Mooij, M. J. Bronikowski, P. A. Willis, R. E. Smalley, L. P. Kouwenhoven, C. Dekker: Two-dimensional imaging of electronic wavefunctions in carbon nanotubes, Nature **412** (2001) 617–620

14.76 C. Wittneven, R. Dombrowski, M. Morgenstern, R. Wiesendanger: Scattering states of ionized dopants probed by low temperature scanning tunneling spectroscopy, Phys. Rev. Lett. **81** (1998) 5616–5619

14.77 D. Haude, M. Morgenstern, I. Meinel, R. Wiesendanger: Local density of states of a three-dimensional conductor in the extreme quantum limit, Phys. Rev. Lett. **86** (2001) 1582–1585

14.78 R. Joynt, R. E. Prange: Conditions for the quantum Hall effect, Phys. Rev. B **29** (1984) 3303–3317

14.79 M. Morgenstern, J. Klijn, C. Meyer, M. Getzlaff, R. Adelung, R. A. Römer, K. Rossnagel, L. Kipp, M. Skibowski, R. Wiesendanger: Direct comparison between potential landscape and local density of states in a disordered two-dimensional electron system, Phys. Rev. Lett. **89** (2002) 136806, 1–4

14.80 E. Abrahams, P. W. Anderson, D. C. Licciardello, T. V. Ramakrishnan: Scaling theory of localization: absence of quantum diffusion in two dimensions, Phys. Rev. Lett. **42** (1979) 673–676

14.81 M. Morgenstern, J. Klijn, R. Wiesendanger: Real space observation of drift states in a two-dimensional electron system at high magnetic fields, Phys. Rev. Lett. **90** (2003) 056804, 1–4

14.82 R. E. Peierls: *Quantum Theory of Solids* (Clarendon, Oxford 1955)

14.83 C. G. Slough, W. W. McNairy, R. V. Coleman, B. Drake, P. K. Hansma: Charge-density waves studied with the use of a scanning tunneling microscope, Phys. Rev. B **34** (1986) 994–1005

14.84 X. L. Wu, C. M. Lieber: Hexagonal domain-like charge-density wave of $\mathrm{TaS_2}$ determined by scanning tunneling microscopy, Science **243** (1989) 1703–1705

14.85 T. Nishiguchi, M. Kageshima, N. Ara-Kato, A. Kawazu: Behaviour of charge density waves in a one-dimensional organic conductor visualized by scanning tunneling microscopy, Phys. Rev. Lett. **81** (1998) 3187–3190

14.86 X. L. Wu, C. M. Lieber: Direct observation of growth and melting of the hexagonal-domain charge-density-wave phase in 1T-TaS$_2$ by scanning tunneling microscopy, Phys. Rev. Lett. **64** (1990) 1150–1153

14.87 J. M. Carpinelli, H. H. Weitering, E. W. Plummer, R. Stumpf: Direct observation of a surface charge density wave, Nature **381** (1996) 398–400

14.88 H. H. Weitering, J. M. Carpinelli, A. V. Melechenko, J. Zhang, M. Bartkowiak, E. W. Plummer: Defect-mediated condensation of a charge density wave, Science **285** (1999) 2107–2110

14.89 H. W. Yeom, S. Takeda, E. Rotenberg, I. Matsuda, K. Horikoshi, J. Schäfer, C. M. Lee, S. D. Kevan, T. Ohta, T. Nagao, S. Hasegawa: Instability and charge density wave of metallic quantum chains on a silicon surface, Phys. Rev. Lett. **82** (1999) 4898–4901

14.90 K. Swamy, A. Menzel, R. Beer, E. Bertel: Charge-density waves in self-assembled halogen-bridged metal chains, Phys. Rev. Lett. **86** (2001) 1299–1302

14.91 J. J. Kim, W. Yamaguchi, T. Hasegawa, K. Kitazawa: Observation of Mott localization gap using low temperature scanning tunneling spectroscopy in commensurate 1T-TaSe$_2$, Phys. Rev. Lett. **73** (1994) 2103–2106

14.92 J. Bardeen, L. N. Cooper, J. R. Schrieffer: Theory of superconductivity, Phys. Rev. **108** (1957) 1175–1204

14.93 A. Yazdani, B. A. Jones, C. P. Lutz, M. F. Crommie, D. M. Eigler: Probing the local effects of magnetic impurities on superconductivity, Science **275** (1997) 1767–1770

14.94 S. H. Tessmer, M. B. Tarlie, D. J. van Harlingen, D. L. Maslov, P. M. Goldbart: Probing the superconducting proximity effect in NbSe$_2$ by scanning tunneling micrsocopy, Phys. Rev. Lett **77** (1996) 924–927

14.95 K. Inoue, H. Takayanagi: Local tunneling spectroscopy of Nb/InAs/Nb superconducting proximity system with a scanning tunneling microscope, Phys. Rev. B **43** (1991) 6214–6215

14.96 H. F. Hess, R. B. Robinson, R. C. Dynes, J. M. Valles, J. V. Waszczak: Scanning-tunneling-microscope observation of the Abrikosov flux lattice and the density of states near and inside a fluxoid, Phys. Rev. Lett. **62** (1989) 214–217

14.97 H. F. Hess, R. B. Robinson, J. V. Waszczak: Vortex-core structure observed with a scanning tunneling microscope, Phys. Rev. Lett. **64** (1990) 2711–2714

14.98 N. Hayashi, M. Ichioka, K. Machida: Star-shaped local density of states around vortices in a type-II superconductor, Phys. Rev. Lett. **77** (1996) 4074–4077

14.99 H. Sakata, M. Oosawa, K. Matsuba, N. Nishida: Imaging of vortex lattice transition in YNi$_2$B$_2$C by scanning tunneling spectroscopy, Phys. Rev. Lett. **84** (2000) 1583–1586

14.100 S. Behler, S. H. Pan, P. Jess, A. Baratoff, H.-J. Güntherodt, F. Levy, G. Wirth, J. Wiesner: Vortex pinning in ion-irrediated NbSe$_2$ studied by scanning tunneling microscopy, Phys. Rev. Lett. **72** (1994) 1750–1753

14.101 R. Berthe, U. Hartmann, C. Heiden: Influence of a transport current on the Abrikosov flux lattice observed with a low-temperature scanning tunneling microscope, Ultramicroscopy **42–44** (1992) 696–698

14.102 A. Polkovnikov, S. Sachdev, M. Vojta: Impurity in a d-wave superconductor: Kondo effect and STM spectra, Phys. Rev. Lett. **86** (2001) 296–299

14.103 E. W. Hudson, K. M. Lang, V. Madhavan, S. H. Pan, S. Uchida, J. C. Davis: Interplay of magnetism and high-T_c superconductivity at individual Ni impurity atoms in Bi$_2$Sr$_2$CaCu$_2$O$_{8+\delta}$, Nature **411** (2001) 920–924

14.104 K. M. Lang, V. Madhavan, J. E. Hoffman, E. W. Hudson, H. Eisaki, S. Uchida, J. C. Davis: Imaging the granular structure of high-T_c superconductivity in underdoped Bi$_2$Sr$_2$CaCu$_2$O$_{8+\delta}$, Nature **415** (2002) 412–416

14.105 I. Maggio-Aprile, C. Renner, E. Erb, E. Walker, Ø. Fischer: Direct vortex lattice imaging and tunneling spectroscopy of flux lines on YBa$_2$Cu$_3$O$_{7-\delta}$, Phys. Rev. Lett. **75** (1995) 2754–2757

14.106 C. Renner, B. Revaz, K. Kadowaki, I. Maggio-Aprile, Ø. Fischer: Observation of the low temperature pseudogap in the vortex cores of Bi$_2$Sr$_2$CaCu$_2$O$_{8+\delta}$, Phys. Rev. Lett. **80** (1998) 3606–3609

14.107 S. H. Pan, E. W. Hudson, A. K. Gupta, K. W. Ng, H. Eisaki, S. Uchida, J. C. Davis: STM studies of the electronic structure of vortex cores in Bi$_2$Sr$_2$CaCu$_2$O$_{8+\delta}$, Phys. Rev. Lett. **85** (2000) 1536–1539

14.108 D. P. Arovas, A. J. Berlinsky, C. Kallin, S. C. Zhang: Superconducting vortex with antiferromagnetic core, Phys. Rev. Lett. **79** (1997) 2871–2874

14.109 J. E. Hoffmann, E. W. Hudson, K. M. Lang, V. Madhavan, H. Eisaki, S. Uchida, J. C. Davis: A four unit cell periodic pattern of quasi-particle states surrounding vortex cores in Bi$_2$Sr$_2$CaCu$_2$O$_{8+\delta}$, Science **295** (2002) 466–469

14.110 M. Fäth, S. Freisem, A. A. Menovsky, Y. Tomioka, J. Aaarts, J. A. Mydosh: Spatially inhomogeneous metal–insulator transition in doped manganites, Science **285** (1999) 1540–1542

14.111 C. Renner, G. Aeppli, B. G. Kim, Y. A. Soh, S. W. Cheong: Atomic-scale images of charge ordering in a mixed-valence manganite, Nature **416** (2000) 518–521

14.112 M. Bode, M. Getzlaff, R. Wiesendanger: Spin-polarized vacuum tunneling into the exchange-split surface state of Gd(0001), Phys. Rev. Lett. **81** (1998) 4256–4259

14.113 A. Kubetzka, M. Bode, O. Pietzsch, R. Wiesendanger: Spin-polarized scanning tunneling microscopy with antiferromagnetic probe tips, Phys. Rev. Lett. **88** (2002) 057201, 1–4

14.114 O. Pietzsch, A. Kubetzka, M. Bode, R. Wiesendanger: Observation of magnetic hysteresis at the nanometer scale by spin-polarized scanning tunneling spectroscopy, Science **292** (2001) 2053–2056

14.115 S. Heinze, M. Bode, A. Kubetzka, O. Pietzsch, X. Xie, S. Blügel, R. Wiesendanger: Real-space imaging of two-dimensional antiferromagnetism on the atomic scale, Science **288** (2000) 1805–1808

14.116 A. Wachowiak, J. Wiebe, M. Bode, O. Pietzsch, M. Morgenstern, R. Wiesendanger: Internal spin-structure of magnetic vortex cores observed by spin-polarized scanning tunneling microscopy, Science **298** (2002) 577–580

14.117 M. D. Kirk, T. R. Albrecht, C. F. Quate: Low-temperature atomic force microscopy, Rev. Sci. Instrum. **59** (1988) 833–835

14.118 D. Pelekhov, J. Becker, J. G. Nunes: Atomic force microscope for operation in high magnetic fields at milliKelvin temperatures, Rev. Sci. Instrum. **70** (1999) 114–120

14.119 J. Mou, Y. Jie, Z. Shao: An optical detection low temperature atomic force microscope at ambient pressure for biological research, Rev. Sci. Instrum. **64** (1993) 1483–1488

14.120 H. J. Mamin, D. Rugar: Sub-attoNewton force detection at milliKelvin temperatures, Appl. Phys. Lett. **79** (2001) 3358–3360

14.121 A. Schwarz, W. Allers, U. D. Schwarz, R. Wiesendanger: Dynamic mode scanning force microscopy of n-InAs(110)-(1×1) at low temperatures, Phys. Rev. B **61** (2000) 2837–2845

14.122 W. Allers, S. Langkat, R. Wiesendanger: Dynamic low-temperature scanning force microscopy on nickel oxide(001), Appl. Phys. A **72** (2001) S27–S30

14.123 F. J. Giessibl: Atomic resolution of the silicon(111)-(7×7) surface by atomic force microscopy, Science **267** (1995) 68–71

14.124 M. A. Lantz, H. J. Hug, P. J. A. van Schendel, R. Hoffmann, S. Martin, A. Baratoff, A. Abdurixit, H.-J. Güntherodt: Low temperature scanning force microscopy of the Si(111)-(7×7) surface, Phys. Rev. Lett. **84** (2000) 2642–2465

14.125 K. Suzuki, H. Iwatsuki, S. Kitamura, C. B. Mooney: Development of low temperature ultrahigh vacuum force microscope/scanning tunneling microscope, Jpn. J. Appl. Phys. **39** (2000) 3750–3752

14.126 N. Suehira, Y. Sugawara, S. Morita: Artifact and fact of Si(111)-(7×7) surface images observed with a low temperature noncontact atomic force microscope (LT-NC-AFM), Jpn. J. Appl. Phys. **40** (2001) 292–294

14.127 R. Peréz, M. C. Payne, I. Štich, K. Terakura: Role of covalent tip-surface interactions in noncontact atomic force microscopy on reactive surfaces, Phys. Rev. Lett. **78** (1997) 678–681

14.128 S. H. Ke, T. Uda, R. Pérez, I. Štich, K. Terakura: First principles investigation of tip-surface interaction on GaAs(110): Implication for atomic force and tunneling microscopies, Phys. Rev. B **60** (1999) 11631–11638

14.129 J. Tobik, I. Štich, R. Peréz, K. Terakura: Simulation of tip-surface interactions in atomic force microscopy of an InP(110) surface with a Si tip, Phys. Rev. B **60** (1999) 11639–11644

14.130 A. Schwarz, W. Allers, U. D. Schwarz, R. Wiesendanger: Simultaneous imaging of the In and As sublattice on InAs(110)-(1×1) with dynamic scanning force microscopy, Appl. Surf. Sci. **140** (1999) 293–297

14.131 G. Schwarz, A. Kley, J. Neugebauer, M. Scheffler: Electronic and structural properties of vacancies on and below the GaP(110) surface, Phys. Rev. B **58** (1998) 1392–1499

14.132 H. Hölscher, W. Allers, U. D. Schwarz, A. Schwarz, R. Wiesendanger: Interpretation of 'true atomic resolution' images of graphite (0001) in noncontact atomic force microscopy, Phys. Rev. B **62** (2000) 6967–6970

14.133 H. Hölscher, W. Allers, U. D. Schwarz, A. Schwarz, R. Wiesendanger: Simulation of NC-AFM images of xenon(111), Appl. Phys. A **72** (2001) S35–S38

14.134 H. Hölscher, W. Allers, U. D. Schwarz, A. Schwarz, R. Wiesendanger: Determination of tip-sample interaction potentials by dynamic force spectroscopy, Phys. Rev. Lett. **83** (1999) 4780–4783

14.135 H. Hölscher, U. D. Schwarz, R. Wiesendanger: Calculation of the frequency shift in dynamic force microscopy, Appl. Surf. Sci. **140** (1999) 344–351

14.136 B. Gotsman, B. Anczykowski, C. Seidel, H. Fuchs: Determination of tip-sample interaction forces from measured dynamic force spectroscopy curves, Appl. Surf. Sci. **140** (1999) 314–319

14.137 U. Dürig: Extracting interaction forces and complementary observables in dynamic probe microscopy, Appl. Phys. Lett. **76** (2000) 1203–1205

14.138 M. A. Lantz, H. J. Hug, R. Hoffmann, P. J. A. van Schendel, P. Kappenberger, S. Martin, A. Baratoff, H.-J. Güntherodt: Quantitative measurement of short-range chemical bonding forces, Science **291** (2001) 2580–2583

14.139 S. M. Langkat, H. Hölscher, A. Schwarz, R. Wiesendanger: Determination of site specific forces between an iron coated tip and the NiO(001) surface by force field spectroscopy, Surf. Sci. (2002) in press

14.140 H. Hölscher, S. M. Langkat, A. Schwarz, R. Wiesendanger: Measurement of three-dimensional force fields with atomic resolution using dynamic force spectroscopy, Appl. Phys. Lett. (2002) in press

14.141 B. C. Stipe, H. J. Mamin, T. D. Stowe, T. W. Kenny, D. Rugar: Noncontact friction and force fluctuations between closely spaced bodies, Phys. Rev. Lett. **87** (2001)

14.142 C. Sommerhalter, T. W. Matthes, T. Glatzel, A. Jäger-Waldau, M. C. Lux-Steiner: High-sensitivity quantitative Kelvin probe microscopy by noncontact ultra-high-vacuum atomic force microscopy, Appl. Phys. Lett. **75** (1999) 286–288

14.143 A. Schwarz, W. Allers, U. D. Schwarz, R. Wiesendanger: Dynamic mode scanning force microscopy of *n*-InAs(110)-(1 × 1) at low temperatures, Phys. Rev. B **62** (2000) 13617–13622

14.144 K. L. McCormick, M. T. Woodside, M. Huang, M. Wu, P. L. McEuen, C. Duruoz, J. S. Harris: Scanned potential microscopy of edge and bulk currents in the quantum Hall regime, Phys. Rev. B **59** (1999) 4656–4657

14.145 P. Weitz, E. Ahlswede, J. Weis, K. v. Klitzing, K. Eberl: Hall-potential investigations under quantum Hall conditions using scanning force microscopy, Physica E **6** (2000) 247–250

14.146 E. Ahlswede, P. Weitz, J. Weis, K. v. Klitzing, K. Eberl: Hall potential profiles in the quantum Hall regime measured by a scanning force microscope, Physica B **298** (2001) 562–566

14.147 M.T. Woodside, C. Vale, P. L. McEuen, C. Kadow, K. D. Maranowski, A. C. Gossard: Imaging interedge-state scattering centers in the quantum Hall regime, Phys. Rev. B **64** (2001) 041310-1–041310-4

14.148 K. Moloni, B. M. Moskowitz, E. D. Dahlberg: Domain structures in single crystal magnetite below the Verwey transition as observed with a low-temperature magnetic force microscope, Geophys. Res. Lett. **23** (1996) 2851–2854

14.149 Q. Lu, C. C. Chen, A. de Lozanne: Observation of magnetic domain behavior in colossal magnetoresistive materials with a magnetic force microscope, Science **276** (1997) 2006–2008

14.150 G. Xiao, J. H. Ross, A. Parasiris, K. D. D. Rathnayaka, D. G. Naugle: Low-temperature MFM studies of CMR manganites, Physica C **341–348** (2000) 769–770

14.151 M. Liebmann, U. Kaiser, A. Schwarz, R. Wiesendanger, U. H. Pi, T. W. Noh, Z. G. Khim, D. W. Kim: Domain nucleation and growth of $La_{07}Ca_{0.3}MnO_{3-\delta}$/ $LaAlO_3$ films studied by low temperature MFM, J. Appl. Phys. **93** (2003) 8319–8321

14.152 A. Moser, H. J. Hug, I. Parashikov, B. Stiefel, O. Fritz, H. Thomas, A. Baratoff, H. J. Güntherodt, P. Chaudhari: Observation of single vortices condensed into a vortex-glass phase by magnetic force microscopy, Phys. Rev. Lett. **74** (1995) 1847–1850

14.153 C.W. Yuan, Z. Zheng, A. L. de Lozanne, M. Tortonese, D. A. Rudman, J. N. Eckstein: Vortex images in thin films of $YBa_2Cu_3O_{7-x}$ and $Bi_2Sr_2Ca_1Cu_2O_{8-x}$ obtained by low-temperature magnetic force microscopy, J. Vac. Sci. Technol. B **14** (1996) 1210–1213

14.154 A. Volodin, K. Temst, C. van Haesendonck, Y. Bruynseraede: Observation of the Abrikosov vortex lattice in $NbSe_2$ with magnetic force microscopy, Appl. Phys. Lett. **73** (1998) 1134–1136

14.155 A. Moser, H. J. Hug, B. Stiefel, H. J. Güntherodt: Low temperature magnetic force microscopy on $YBa_2Cu_3O_{7-\delta}$ thin films, J. Magn. Magn. Mater. **190** (1998) 114–123

14.156 A. Volodin, K. Temst, C. van Haesendonck, Y. Bruynseraede: Imaging of vortices in conventional superconductors by magnetic force microscopy images, Physica C **332** (2000) 156–159

14.157 M. Roseman, P. Grütter: Estimating the magnetic penetration depth using constant-height magnetic force microscopy images of vortices, New J. Phys. **3** (2001) 24.1–24.8

14.158 A. Volodin, K. Temst, C. van Haesendonck, Y. Bruynseraede, M. I. Montero, I. K. Schuller: Magnetic force microscopy of vortices in thin niobium films: Correlation between the vortex distribution and the thickness-dependent film morphology, Europhys. Lett. **58** (2002) 582–588

14.159 U. H. Pi, T. W. Noh, Z. G. Khim, U. Kaiser, M. Liebmann, A. Schwarz, R. Wiesendanger: Vortex dynamics in $Bi_2Sr_2CaCu_2O_8$ single crystal with low density columnar defects studied by magnetic force microscopy, J. Low Temp. Phys. **131** (2003) 993–1002

14.160 M. Roseman, P. Grütter, A. Badia, V. Metlushko: Flux lattice imaging of a patterned niobium thin film, J. Appl. Phys. **89** (2001) 6787–6789

14.161 K. Nakamura, H. Hasegawa, T. Oguchi, K. Sueoka, K. Hayakawa, K. Mukasa: First-principles calculation of the exchange interaction and the exchange force between magnetic Fe films, Phys. Rev. B **56** (1997) 3218–3221

14.162 A. S. Foster, A. L. Shluger: Spin-contrast in non-contact AFM on oxide surfaces: Theoretical modeling of NiO(001) surface, Surf. Sci. **490** (2001) 211–219

14.163 H. Hoisoi, M. Kimura, K. Hayakawa, K. Sueoka, K. Mukasa: Non-contact atomic force microscopy of an antiferromagnetic NiO(100) surface using a ferromagnetic tip, Appl. Phys. A **72** (2001) S23–S26

14.164 J. A. Sidles, J. L. Garbini, G. P. Drobny: The theory of oscillator-coupled magnetic resonance with potential applications to molecular imaging, Rev. Sci. Instrum. **63** (1992) 3881–3899

14.165 J. A. Sidles, J. L. Garbini, K. J. Bruland, D. Rugar, O. Züger, S. Hoen, C. S. Yannoni: Magnetic resonance force microscopy, Rev. Mod. Phys. **67** (1995) 249–265

14.166 D. Rugar, C. S. Yannoni, J. A. Sidles: Mechanical detection of magnetic resonance, Nature **360** (1992) 563–566

14.167 K. Wago, D. Botkin, O. Züger, R. Kendrick, C. S. Yannoni, D. Rugar: Force-detected electron spin resonance: Adiabatic inversion, nutation and spin echo, Phys. Rev. B **57** (1998) 1108–1114

14.168 D. Rugar, O. Züger, S. Hoen, C. S. Yannoni, H. M. Vieth, R. D. Kendrick: Force detection of nuclear magnetic resonance, Science **264** (1994) 1560–1563

14.169 Z. Zhang, P. C. Hammel, P. E. Wigen: Observation of ferromagnetic resonance in a microscopic sample using magnetic resonance force microscopy, Appl. Phys. Lett. **68** (1996) 2005–2007

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

15. Dynamic Force Microscopy

This chapter presents an introduction to the concept of the dynamic operational mode of the atomic force microscope (dynamic AFM). While the static, or contact mode AFM is a widespread technique to obtain nanometer resolution images on a wide variety of surfaces, true atomic resolution imaging is routinely observed only in the dynamic mode. We will explain the jump-to-contact phenomenon encountered in static AFM and present the dynamic operational mode as a solution to overcome this effect. The dynamic force microscope is modeled as a harmonic oscillator to gain a basic understanding of the underlying physics in this mode.

Dynamic AFM comprises a whole family of operational modes. A systematic overview of the different modes typically encountered in force microscopy is presented, and special care is taken to explain the distinct features of each mode. Two modes of operation dominate the application of dynamic AFM. First, the amplitude modulation mode (also called tapping mode) is shown to exhibit an instability, which separates the purely attractive force interaction regime from the attractive–repulsive regime. Second, the self-excitation mode is derived and its experimental realization is outlined. While the first is primarily used for imaging in air and liquid, the second dominates imaging in UHV (ultrahigh vacuum) for atomic resolution imaging. In particular, we explain the influence of different forces on spectroscopy curves obtained in dynamic force microscopy. A quantitative link between the measurement values and the interaction forces is established.

Force microscopy in air suffers from small quality factors of the force sensor (i.e., the cantilever beam), which are shown to limit the achievable resolution. Also, the above mentioned instability in amplitude modulation mode often hinders imaging of soft and fragile samples. A combination of the amplitude modulation with the self-excitation mode is shown to increase the quality, or Q-factor, and extend the regime of stable operation, making the so-called Q-control module a valuable tool. Apart from the advantages of dynamic force microscopy as a nondestructive, high-resolution imaging method, it can also be used to obtain information about energy dissipation phenomena at the nanometer scale. This measurement channel can provide crucial information on electric and magnetic surface properties. Even atomic resolution imaging has been obtained in the dissipation mode. Therefore, in the last section, the quantitative relation between the experimental measurement values and the dissipated power is derived.

15.1 **Motivation: Measurement of a Single Atomic Bond** 450

15.2 **Harmonic Oscillator: A Model System for Dynamic AFM** 454

15.3 **Dynamic AFM Operational Modes**............ 455
- 15.3.1 Amplitude-Modulation/Tapping-Mode AFMs 456
- 15.3.2 Self-Excitation Modes 461

15.4 ***Q*-Control**.. 464

15.5 **Dissipation Processes Measured with Dynamic AFM** 468

15.6 **Conclusion** 471

References 471

Springer Handbook of Nanotechnology
B. Bhushan • © Springer 2004

15.1 Motivation: Measurement of a Single Atomic Bond

The direct measurement of the force interaction between two distinct molecules has been the motivation for scientists for many years now. The fundamental forces responsible for the solid state of matter can be directly investigated, ultimately between defined single molecules. But it has not been until very recently that the chemical forces could be quantitatively measured for a single atomic bond [15.1]. How can we reliably measure forces that may be as small as one billionth of 1 N? How can we identify one single pair of atoms as the source of the force interaction?

The same mechanical principle that is used to measure the gravitational force exerted by your body weight (e.g., with the scale in your bathroom) can be employed to measure the forces between single atoms. A spring with a defined elasticity is compressed by an arbitrary force (e.g., your weight). The compression Δz of the spring (with spring constant k) is a direct measure of the force F exerted, which in the regime of elastic deformation obeys Hooke's law:

$$F = k\Delta z \,. \tag{15.1}$$

The only difference with regard to your bathroom scale is the sensitivity of the measurement. Typically springs with a stiffness of 0.1 N/m to 10 N/m are used, which will be deflected by 0.1 nm to 10 nm upon application of an interatomic force of some nN. Experimentally, a laser deflection technique is used to measure the movement of the spring. The spring is a bendable cantilever microfabricated from silicon wafers. If a sufficiently sharp tip, usually directly attached to the cantilever, is approached toward a surface within some nanometers, we can measure the interacting forces through changes in the deflected laser beam. This is a static measurement; hence it is called *static AFM*. Alternatively, the cantilever can be excited to vibrate at its resonant frequency. Under the influence of tip-sample forces the resonant frequency (and consequently also amplitude and phase) of the cantilever will change and serve as measurement parameters. This is called the *dynamic AFM*. Due to the multitude of possible operational modes, expressions like noncontact mode, intermittent-contact mode, tapping mode, FM-mode, AM-mode, self-excitation, constant-excitation, or constant-amplitude mode AFM are found in the literature, which will be systematically categorized in the following paragraphs.

In fact, the first AFMs were operated in the dynamic mode. In 1986, *Binnig*, *Quate* and *Gerber* presented the concept of the atomic force microscope [15.2]. The deflection of the cantilever with the tip was measured with sub-angstrom precision by an additional scanning tunneling microscope (STM). While the cantilever was externally oscillated close to its resonant frequency, the amplitude and phase of the oscillation were measured. If the tip is approached toward the surface, the oscillation parameters, amplitude and phase, are influenced by the tip-surface interaction, and can, therefore, be used as feedback channels. A certain set-point, for example, the amplitude, is given, and the feedback loop will adjust the tip-sample distance such that the amplitude remains constant. The controller parameter is recorded as a function of the lateral position of the tip with respect to the sample, and the scanned image essentially represents the surface topography.

What then is the difference between the static and the dynamic mode of operation for the AFM? The static deflection AFM directly gives the interaction force between tip and sample using (15.1). In the dynamic mode, we find that the resonant frequency, amplitude, and phase of the oscillation change as a consequence of the interaction forces (and also dissipative processes, as discussed in the last section).

In order to get a basic understanding of the underlying physics, it is instructive to consider a very simplified case. Assume that the vibration amplitude is small compared to the range of force interaction. Since van der Waals forces range over typical distances of 10 nm, the vibration amplitude should be less than 1 nm. Furthermore, we require that the force gradient $\partial F_{\mathrm{ts}}/\partial z$ does not vary significantly over one oscillation cycle.

We can view the AFM setup as a coupling of two springs (see Fig. 15.1). Whereas the cantilever is represented by a spring with spring constant k, the force interaction between tip and surface can be modeled by



Fig. 15.1 Model of the AFM tip while experiencing tip-sample forces. The tip is attached to a cantilever with spring constant k, and the force interaction is modeled by a spring with a stiffness k_{ts} equal to the force gradient. Note that the force interaction spring is not constant, but depends on the tip-sample distance z

a second spring. The derivative of the force with respect to tip-sample distance is the force gradient and represents the spring constant k_{ts} of the interaction spring. This spring constant k_{ts} is constant only with respect to one oscillation cycle, but varies with the average tip-sample distance as the probe is approached to the sample. The two springs are coupled in series. Therefore, we can write for the total spring constant of the AFM system:

$$k_{\text{total}} = k + k_{ts} = k - \frac{\partial F_{ts}}{\partial z} . \tag{15.2}$$

From the simple harmonic oscillator (neglecting any damping effects) we find that the resonant frequency ω of the system is shifted by $\Delta\omega$ from the free resonant frequency ω_0 due to the force interaction:

$$\begin{aligned} \omega^2 &= (\omega_0 + \Delta\omega)^2 \\ &= k_{\text{total}}/m^* = \left(k + \frac{\partial F_{ts}}{\partial z}\right)/m^* . \end{aligned} \tag{15.3}$$

Here m^* represents the effective mass of the cantilever. A detailed analysis of how m^* is related to the geometry and total mass of the cantilever can be found in the literature [15.3]. In the approximation that $\Delta\omega$ is much smaller than ω_0, we can write:

$$\frac{\Delta\omega}{\omega_0} \cong -\frac{1}{2k}\frac{\partial F_{ts}}{\partial z} . \tag{15.4}$$

Therefore, we find that the frequency shift of the cantilever resonance is proportional to the force gradient of the tip-sample interaction.

Although the above consideration is based on a very simplified model, it shows qualitatively that in dynamic force microscopy we will find that the oscillation frequency depends on the force gradient, while static force microscopy measures the force itself. In principle, we can calculate the force curve from the force gradient and vice versa (neglecting a constant offset). It seems, therefore, that the two methods are equivalent, and our choice will depend on whether we can measure the beam deflection or the frequency shift with better precision at the cost of technical effort.

However, we have neglected one important issue for the operation of the AFM thus far: the mechanical stability of the measurement. In static AFM, the tip is slowly approached toward the surface. The force between the tip and the surface will always be counteracted by the restoring force of the cantilever. In Fig. 15.2, you can see a typical force-distance curve. Upon approach of the tip toward the sample, the negative attractive forces, representing, e.g., van der Waals or chemical interaction forces, increase until a maximum is reached. This turnaround point is due to the onset of repulsive forces caused by coulomb repulsion, which will start to dominate upon further approach. The spring constant of the cantilever is represented by the slope of the straight line. The position of the z-transducer (typically a piezo element), which moves the probe, is at the intersection of the line with the horizontal axis. The position of the tip, shifted from the probe's base due to the lever bending, can be found at the intersection of the cantilever line with the force curve. Hence, the total force is zero, i. e., the cantilever is in its equilibrium position (note that the spring constant line here shows attractive forces, although in reality the forces are repulsive, i. e., pulling back the tip from the surface). As soon as the position A in Fig. 15.2 is reached, we find two possible intersection points, and upon further approach there are even three force equilibrium points. However, between point A to B the tip is at a local energy minimum and, therefore, will still follow the force curve. But at



Fig. 15.2 Force-distance curve of a typical tip-sample interaction. In static mode AFM, the tip would follow the force curve until point B is reached. If the slope of the force curve becomes larger than the spring constant of the cantilever (*dashed line*), the tip will suddenly jump to position C. Upon retraction, a different path will be followed along D and A again. In dynamic AFM, the cantilever oscillates with amplitude A. Although the equilibrium position of the oscillation is far from the surface, the tip will experience the maximum attractive force at point D during some parts of the oscillation cycle. However, the total force is always pointing away from the surface, therefore, avoiding an instability

point B, when the adhesion force upon further approach would become larger than the spring restoring force, the tip will suddenly jump to point C. We can then probe the predominantly repulsive force interaction by further reducing the tip-sample distance. Then, while retracting the tip, we will pass point C, because the tip is still in a local energy minimum. At position D the tip will jump suddenly to point A again, since the restoring force now exceeds the adhesion. From Fig. 15.2 we can see that the sudden instability will happen at exactly the point where the slope of the adhesion force exceeds the slope of the spring constant. Therefore, if the negative force gradient of the tip-sample interaction will at any point exceed the spring constant, a mechanical instability occurs. Mathematically speaking, we demand that for a stable measurement:

$$\left.\frac{\partial F_{\mathrm{ts}}}{\partial z}\right|_{z} > k \quad \text{for all points } z\,. \tag{15.5}$$

The phenomenon of mechanical instability is often referred to as the "jump-to-contact".

Looking at Fig. 15.2, we realize that large parts of the force curve cannot be measured if the jump-to-contact phenomenon occurs. We will not be able to measure the point at which the attractive forces reach their maximum, representing the temporary chemical bonding of the tip and the surface atoms. Secondly, the sudden instability, the jump-to-contact, will often cause the tip to change the very last tip or surface atoms. A smooth, careful approach needed to measure the full force curve does not seem feasible. Our goal of measuring the chemical interaction forces of two single molecules may become impossible.

There are several solutions to the jump-to-contact problem: On the one hand, we can simply choose a sufficiently stiff spring, so that (15.5) is fulfilled at all points of the force curve. On the other hand, we can resort to a trick to enhance the counteracting force of the cantilever: We can oscillate the cantilever with large amplitude, thereby making it virtually stiffer at the point of strong force interaction.

Consider the first solution, which seems simpler at first glance. Chemical bonding forces extend over a distance range of about 0.1 nm. Typical binding energies of a couple of eV will lead to adhesion forces on the order of some nN. Force gradients will, therefore, reach values of some 10 N/m. A spring for stable force measurements will have to be as stiff as 100 N/m to ensure that no instability occurs (a safety factor of ten seems to be a minimum requirement, since usually one cannot be sure a priori that only one atom will dominate the interaction). In order to measure the nN interaction force, a static cantilever deflection of 0.01 nm has to be detected. With standard beam deflection AFM setups this becomes a challenging task.

This problem was solved [15.4, 5] using an in situ optical interferometer measuring the beam deflection at liquid nitrogen temperature in a UHV environment. In order to ensure that the force gradients are smaller than the lever spring constant (50 N/m), the tips were fabricated to terminate in only three atoms, therefore, minimizing the total force interaction. The only tool known to be able to engineer SPM tips down to atomic dimensions is the field ion microscope (FIM). This technique not only allows imaging of the tip apex with atomic precision, but also can be used to manipulate the tip atoms by field evaporation [15.6], as shown in Fig. 15.3. Atomic interaction forces were measured with sub-nanonewton precision, revealing force curves of only a few atoms interacting without mechanical hysteresis. However, the technical effort to achieve this type of measurement is considerable, and most researchers today have resorted to the second solution.



Fig. 15.3 Manipulation of the apex atoms of an AFM tip using field ion microscopy (FIM). Images are obtained at a tip bias of 4.5 kV. The last six atoms of the tip can be inspected in this example. Field evaporation to remove single atoms is performed by increasing the bias voltage for a short time to 5.2 kV. Each of the outer three atoms can be consecutively removed, eventually leaving a trimer tip apex

The alternative solution can be visualized in Fig. 15.2. The straight, dashed line now represents the force values of the oscillating cantilever, with amplitude *A* assuming Hooke's law is valid. This is the tensile force of the cantilever spring pulling the tip away from the sample. The restoring force of the cantilever is at all points stronger than the adhesion force. For example, the total force at point D is still pointing away from the sample, although the spring has the same stiffness as before. Mathematically speaking, the measurement is stable as long as the cantilever spring force $F_{\mathrm{cb}} = kA$ is larger than the attractive tip-sample force F_{ts} [15.7]. In the static mode we would already experience an instability at that point. However, in the dynamic mode, the spring is pre-loaded with a force stronger than the attractive tip-sample force. The equilibrium point of the oscillation is still far away from the point of closest contact of the tip and surface atoms. The total force curve can be probed by varying the equilibrium point of the oscillation, i. e., by adjusting the *z*-piezo.

The diagram also shows that the oscillation amplitude has to be quite large if fairly soft cantilevers are to be used. With lever spring constants of 10 N/m, the amplitude must be at least 1 nm to ensure forces of 1 nN can be reliably measured. In practical applications, amplitudes of 10–100 nm are used to stay on the safe side. This means that the oscillation amplitude is much larger than the force interaction range. The above simplification, that the force gradient remains constant within one oscillation cycle, does not hold anymore. Measurement stability is gained at the cost of a simple quantitative analysis of the experiments. In fact, dynamic AFM was first used to obtain atomic resolution images of clean surfaces [15.8], and it took another six years [15.1] before quantitative measurements of single bond forces were obtained.

The technical realization of dynamic mode AFMs is based on the same key components as a DC-AFM setup. The most common principle is the method of laser deflection sensing (see, e.g., Fig. 15.4). A laser beam is focused on the back side of a microfabricated cantilever. The reflected laser spot is detected with a positional sensitive diode (PSD). This photodiode is sectioned into two parts that are read-out separately (usually even a four-quadrant diode is used to detect torsional movements of the cantilever for lateral friction measurements). With the cantilever at equilibrium, the spot is adjusted such that the two sections show the same intensity. If the cantilever bends up or down, the spot moves, and the difference signal between the upper and lower sections is a measure of the bending.



Fig. 15.4 Representation of an AFM setup with the laser beam deflection method. Cantilever and tip are microfabricated from silicon wafers. A laser beam is deflected from the back side of the cantilever and again focused on a photosensitive diode. The diode is segmented into four quadrants, which allows the measurement of vertical and torsional bending of the cantilever (artwork from *Jörg Heimel* rendered with POV-Ray 3.0)

In order to enhance sensitivity, several groups have adopted an interferometer system to measure the cantilever deflection. A thorough comparison of different measurement methods with analysis of sensitivity and noise level is given by [15.3].

The cantilever is mounted on a device that allows oscillation of the beam. Often a piezo-element serves this purpose. The reflected laser beam is analyzed for oscillation amplitude, frequency, and phase difference between excitation and vibration. Depending on the mode of operation, a feedback mechanism will adjust oscillation parameters and/or tip-sample distance during the scanning. The setup can be operated in air, UHV, and even in fluids. This allows measurement of a wide range of surface properties from atomic resolution imaging [15.8] up to studying biological processes in liquid [15.9, 10].

15.2 Harmonic Oscillator: A Model System for Dynamic AFM

The oscillating cantilever has three degrees of freedom: the amplitude, the frequency, and the phase difference between excitation and oscillation. Let us consider the damped driven harmonic oscillator. The cantilever is mounted on a piezoelectric element that is oscillating with amplitude A_d at frequency ω:

$$z_\text{d}(t) = A_\text{d} \cos(\omega t) . \quad (15.6)$$

We assume that the cantilever spring obeys Hooke's law. Secondly, we introduce a friction force that is proportional to the speed of the cantilever motion, whereas α denotes the damping coefficient (Amontons's law). With Newton's first law we find for the oscillating system the following equation of motion for the position $z(t)$ of the cantilever tip (see also Fig. 15.1):

$$m\ddot{z}(t) = -\alpha\dot{z}(t) - kz(t) - kz_\text{d}(t) . \quad (15.7)$$

We define $\omega_0^2 = k/m^*$, which turns out to be the resonant frequency of the free (undamped, i. e., $\alpha = 0$) oscillating beam. We further define the dimensionless quality factor $Q = m^*\omega_0/\alpha$, antiproportional to the damping coefficient. The quality factor describes the number of oscillation cycles, after which the damped oscillation amplitude decays to 1/e of the initial amplitude with no external excitation ($A_\text{d} = 0$). After some basic math, this results in the following differential equation:

$$\ddot{z}(t) + \frac{\omega_0}{Q}\dot{z}(t) + \omega_0^2 z(t) = A_\text{d}\omega_0^2 \cos(\omega t) . \quad (15.8)$$

The solution is a linear combination of two regimes [15.11]. Starting from rest and switching on the piezo-excitation at $t = 0$, the amplitude will increase from zero to the final magnitude and reach a steady state, where amplitude, phase, and frequency of the oscillation stay constant over time. The steady-state solution $z_1(t)$ is reached after $2Q$ oscillation cycles and follows the external excitation with amplitude A_0 and phase difference φ:

$$z_1(t) = A_0 \cos(\omega t + \varphi) . \quad (15.9)$$

The oscillation amplitude in the transient regime during the first $2Q$ cycles follows:

$$z_2(t) = A_\text{t} \text{e}^{-\omega_0 t/2Q} \sin(\omega_0 t + \varphi_\text{t}) . \quad (15.10)$$

We emphasize the important fact that the exponential term causes $z_2(t)$ to diminish exponentially with time constant τ:

$$\tau = 2Q/\omega_0 . \quad (15.11)$$

In vacuum conditions, only the internal dissipation due to bending of the cantilever is present, and Q reaches values of 10,000 at typical resonant frequencies of 100,000 Hz. This results in a relatively long transient regime of $\tau \cong 30$ ms, which limits the possible operational modes for dynamic AFM (detailed analysis by [15.11]). Changes in the measured amplitude, which reflect a change of atomic forces, will have a time lag of 30 ms, which is very slow considering one wants to scan a 200 × 200 point image within a few minutes. In air, however, viscous damping due to air friction dominates and Q goes down to less than 1,000, resulting in a time constant below the millisecond level. This response time is fast enough to use the amplitude as a measurement parameter.

If we evaluate the steady state solution $z_1(t)$ in the differential equation, we find the following well-known



Fig. 15.5 Amplitude and phase versus excitation frequency curves for the damped harmonic oscillator with a quality factor of $Q = 4$

solution for amplitude and phase of the oscillation as a function of the excitation frequency ω:

$$A_0 = \frac{A_\mathrm{d} Q \omega_0^2}{\sqrt{\omega^2\omega_0^2 + Q^2\left(\omega_0^2 - \omega^2\right)^2}} \qquad (15.12)$$

$$\varphi = \arctan\left(\frac{\omega\omega_0}{Q\left(\omega_0^2 - \omega^2\right)}\right) . \qquad (15.13)$$

Amplitude and phase diagrams are depicted in Fig. 15.5. As can be seen from (15.12), the amplitude will reach its maximum at a frequency different from ω_0, if Q has a finite value. The damping term of the harmonic oscillator causes the resonant frequency to shift from ω_0 to ω_0^*:

$$\omega_0^* = \omega_0\sqrt{1 - \frac{1}{2Q^2}} . \qquad (15.14)$$

The shift is negligible for Q-factors of 100 and above, which is the case for most applications in vacuum or air. However, for measurements in liquids, Q can be smaller than 10 and ω_0 differs significantly from ω_0^*. As we will discuss later, it is also possible to enhance Q by using a special excitation method.

In the case that the excitation frequency is equal to the resonant frequency of the undamped cantilever, $\omega = \omega_0$, we find the useful relation:

$$A_0 = Q A_\mathrm{d} \quad \text{for } \omega = \omega_0 . \qquad (15.15)$$

Since $\omega_0^* \approx \omega_0$ for most cases, we find that (15.15) holds true for exciting the cantilever at its resonance. From a similar argument, the phase becomes approximately 90 deg for the resonance case. We also see that in order to reach vibration amplitudes of some 10 nm, the excitation only has to be as small as 1 pm for typical cantilevers operated in vacuum.

So far, we have not considered an additional force term, describing the interaction between the probing tip and the sample. For typical, large vibration amplitudes of 10–100 nm no general solution for this analytical problem has been found yet. The cantilever tip will experience a whole range of force interactions during one single oscillation cycle, rather than one defined tip-sample force. Only in the special case of a self-excited cantilever oscillation has the problem been solved semi-analytically, as we will see later.

15.3 Dynamic AFM Operational Modes

While the quantitative interpretation of force curves in contact AFM is straightforward using (15.1), we explained in the previous paragraphs that its application to assess short-range attractive interatomic forces is rather limited. The dynamic mode of operation seems to open a viable direction toward achieving this task. However interpretation of the measurements generally appears to be more difficult. Different operational modes are employed in dynamic AFM, and the following paragraphs are intended to distinguish these modes and categorize them in a systematic way.

The oscillation trajectory of a dynamically driven cantilever is determined by three parameters: the amplitude, the phase, and the frequency. Tip-sample interactions can influence all three parameters, in the following, termed the internal parameters. The oscillation is driven externally, with excitation amplitude A_d and excitation frequency ω. These variables will be referred to as the external parameters. The external parameters are set by the experimentalist, whereas the internal parameters are measured and contain the crucial information about the force interaction. In scanning probe applications, it is common to control the probe-surface distance z_0 in order to keep an internal parameter constant (i. e., the tunneling current in STM or the beam deflection in contact AFM), which represents a certain tip-sample interaction. In z-spectroscopy mode, the distance is varied in a certain range, and the change of the internal parameters are measured as a fingerprint of the tip-sample interactions.

In dynamic AFM the situation is rather complex. Any of the internal parameters can be used for feedback of the tip-sample distance z_0. However, we already realized that, in general, the tip-sample forces could only be fully assessed by measuring all three parameters. This makes it difficult to obtain images where the distance z_0 is representative of the surface at one force set-point. A solution to this problem is to establish additional feedback loops, which keep the internal parameters constant by adjusting the external variables.

In the simplest setup, the excitation frequency is set to a predefined value, and the excitation amplitude remains constant by a feedback loop. This is called the AM mode (amplitude modulation), or tapping mode (TM). As stated before, in principle, any of the internal parameters can be used for feedback to the tip-sample distance – in AM mode the amplitude signal is used. A certain amplitude (smaller than the free oscillation amplitude) at a frequency close to the resonance of the cantilever is chosen, the tip is approached toward the surface under investigation, and the approach is stopped as soon as the set-point amplitude is reached. The oscillation-phase is usually recorded during the scan, however, the shift of the resonant frequency of the cantilever cannot be directly accessed, since this degree of freedom is blocked by the external excitation at a fixed frequency. It turns out that this mode is simple to operate from a technical perspective, but quantitative information about the tip-sample interaction forces has so far not been reliably extracted from AM-mode AFM. Still, it is one of the most commonly used modes in dynamic AFM operated in air, and even in liquid. The strength of this mode is the qualitative imaging of a large variety of surfaces.

It is interesting to discuss the AM mode in the extreme situation that the external excitation frequency is much lower than the resonant frequency [15.12,13]. This results in a quasi-static measurement, although a dynamic oscillation force is applied, and, therefore, this mode can be viewed as a hybrid between static and dynamic AFM. Unfortunately, it has the drawbacks of the static mode, namely, that stiff spring constants must be used and, therefore, the sensitivity of the deflection measurement must be very good, typically employing a high resolution interferometer. Still, it has the advantage of the static measurement in quantitative interpretation, since in the regime of small amplitudes (< 0.1 nm) a direct interpretation of the experiments is possible. In particular, the force gradient at tip-sample distance z_0 is given by the change of the amplitude A and the phase angle φ:

$$\left.\frac{\partial F_{\mathrm{ts}}}{\partial z}\right|_{z_0} = k\left(1-\frac{A_0}{A}\cos\varphi\right) . \tag{15.16}$$

In effect, the modulated AFM, in contrast to the purely static AFM, can enhance sensitivity due to the use of lock-in techniques, which allows the measurement of the amplitude and phase of the oscillation signal with high precision.

As stated before, the internal parameters can be fed back to the external excitation variables. One of the most useful applications in this direction is the self-excitation system. Here the resonant frequency of the cantilever is detected and selected again as the excitation frequency. In a typical setup, this is done with a phase shift of 90 deg by feeding back the detector signal to the excitation piezo, i. e., the cantilever is always excited in resonance. Influences of the tip-sample interaction forces on the resonant frequency do not change the two other parameters of the oscillation, i. e., amplitude and phase; only the oscillation frequency is shifted. Therefore, it is sufficient to measure the frequency shift between the free oscillation and the oscillation with tip-sample interaction. Since the phase remains at a fixed value, the oscillating system is much better defined than before, and the degrees of freedom for the oscillation are reduced. To even reduce the last degree of freedom, the oscillation amplitude, another feedback loop can be established to keep the oscillation amplitude A constant by varying the excitation amplitude A_{d}. Now, all internal parameters have a fixed relation to the external excitation variables, the system is well-defined, and all parameters can be assessed during the measurement. As it turns out, this mode is the only dynamic mode in which a quantitative relation between tip-sample forces and the change of the resonant frequency can be established.

In the following section we want to discuss the two most popular operational modes, tapping mode and self-excitation mode, in more detail.

15.3.1 Amplitude-Modulation/Tapping-Mode AFMs

In tapping mode, or AM-AFM, the cantilever is excited externally at a constant frequency close to its resonance. Oscillation amplitude and phase during approach of tip and sample serve as the experimental observation channels. Figure 15.6 shows a diagram of a typical tapping-mode AFM setup. The oscillation amplitude and the phase (not shown in diagram) detected with the photodiode are analyzed with a lock-in amplifier. The amplitude is compared to the set-point, and the difference or error signal is used to adjust the z-piezo, i. e., the probe-sample distance. The external modulation unit supplies the signal for the excitation piezo, and, at the same time, the oscillation signal serves as the reference for the lock-in amplifier.

During one oscillation cycle with amplitudes of 10–100 nm, the tip-sample interaction will range over a wide distribution of forces, including attractive, as well as repulsive forces. We will, therefore, measure a convolution of the force-distance curve with the oscillation trajectory. This complicates the interpretation of AM-AFM measurements appreciably.



Fig. 15.6 Setup of a dynamic force microscope operated in the AM or tapping mode. A laser beam is deflected by the back side of the cantilever, and the deflection is detected by a split photodiode. The excitation frequency is chosen externally with a modulation unit, which drives the excitation piezo. A lock-in amplifier analyzes phase and amplitude of the cantilever oscillation. The amplitude is used as the feedback signal for the probe-sample distance control



Fig. 15.7 Simplified model showing the oscillation amplitude in tapping-mode AFM for various probe-sample distances

At the same time, the resonant frequency of the cantilever will change due to the appearing force gradients, as could already be seen in the simplified model from (15.4). If the cantilever is excited exactly at its resonant frequency before, it will be excited off-resonance after interaction forces are encountered. This, in turn, changes amplitude and phase (15.12, 15.13), which serve as the measurement signals. Consequently, a different amplitude will cause a change in the encountered effective force. We can see already from this simple *gedanken*-experiment that the interpretation of force curves will be highly complicated. In fact, there is no quantitative theory for AM-AFM available, which allows the experimentalist to unambiguously convert the experimental data to a force-distance relationship.

The qualitative behavior for amplitude versus z_0-position curves is depicted in Fig. 15.7. At large distances, where the forces between tip and sample are negligible, the cantilever oscillates with its free oscillation amplitude. Upon approach of the probe toward the surface the interaction forces cause the amplitude to change, resulting typically in an amplitude getting smaller with continuously decreased tip-sample distance. This is expected, since the force-distance curve will eventually reach the repulsive part and the tip is hindered from indenting further into the sample, resulting in smaller oscillation amplitudes.

However, in order to gain some qualitative insight into the complex relationship between forces and oscillation parameters, we resort to numerical simulations. *Anczykowski* et al. [15.14, 15] have calculated the oscillation trajectory of the cantilever under the influence of a given force model. Van der Waals interactions were considered the only effective, attractive forces, and the total interaction resembled a Lennard-Jones-type potential. Mechanical relaxations of the tip and sample surface were treated in the limits of continuum theory with the numerical MYD/BHW [15.16, 17] approach, which allows the simulations to be compared to corresponding experiments. Figure 15.8 shows the force-distance curves for different tip radii underlying the dynamic AFM simulations.

The cantilever trajectory was analyzed by solving the differential equation (15.7) extended by the force-distance relations from Fig. 15.8 using the numerical Verlet algorithm [15.18, 19]. The results of the simulation for the amplitude and phase of the tip oscillation as a function of z-position of the probe are presented in Fig. 15.9. One has to keep in mind that the z-position



Fig. 15.8 Force curves and corresponding contact radius calculated with the MYD/BHW-model as a function of tip radius for a Si–Si contact. These force curves are used for the tapping-mode AFM simulations

of the probe is not equivalent to the real tip-sample distance at equilibrium position, since the cantilever might bend statically due to the interaction forces. The behavior of the cantilever can be subdivided into three different regimes. We distinguish the cases in which the beam is oscillated below its resonant frequency ω_0, exactly at ω_0, and above ω_0. In the following, we will refer to ω_0 as the resonant frequency, although the correct resonant frequency is ω_0^* if taking into account the finite Q-value.

Clearly, Fig. 15.9 exhibits more features than were anticipated from the initial, simple arguments. Amplitude and phase seem to change rather abruptly at certain points when the z_0-position is decreased. Besides, the amplitude or phase-distance curves don't resemble the force-distance curves from Fig. 15.8 in a simple, direct manner. Additionally, we find a hysteresis between approach and retraction.

As an example, let us start by discussing the discontinuous features in the AFM spectroscopy curves of the first case, where the excitation frequency is smaller than ω_0. Consider the oscillation amplitude as a function of excitation frequency in Fig. 15.5 in conjunction with a typical force curve, as depicted in Fig. 15.8. Upon approach of probe and sample, attractive forces will lower the effective resonant frequency of the oscillator. Therefore, the excitation frequency will now be closer to the resonant frequency, causing the vibration amplitude to increase. This, in turn, reduces the tip-sample distance, which again gives rise to a stronger attractive force. The system becomes unstable until the point $z_0 = d_{\mathrm{app}}$ is reached, where repulsive forces stop the self-enhancing instability. This can be clearly observed in Fig. 15.9. Large parts of the force-distance curve cannot be measured due to this instability.

In the second case, where the excitation equals the free resonant frequency, only a small discontinuity is observed upon reduction of the z-position. Here, a shift of the resonant frequency toward smaller values, induced by the attractive force interaction, will reduce the oscillation amplitude. The distance between tip and sample is, therefore, reduced as well, and the self-amplifying effect with the sudden instability does not occur as long as repulsive forces are not encountered. However, at closer tip-sample distances, repulsive forces will cause the resonant frequency to shift again toward higher values, increasing the amplitude with decreasing tip-sample distance. Therefore, a self-enhancing instability will also occur in this case, but at the crossover from purely attractive forces to the regime where repulsive forces occur. Correspondingly, a small kink in the amplitude curve can be observed in Fig. 15.9. An even clearer indication of this effect is manifested by the sudden change in the phase signal at d_{app}.

In the last case, with $\omega > \omega_0$, the effect of amplitude reduction due to the resonant frequency shift is even larger. Again, we find no instability in the amplitude signal during approach in the attractive force regime. However, as soon as the repulsive force regime is reached, the instability occurs due to the induced positive frequency shift. Consequently, a large jump in the phase curve from values smaller than 90 deg to values larger than 90 deg is observed. The small change in the amplitude curve is not resolved in the simulated curves in Fig. 15.9, however, it can be clearly seen in the experimental curves in Fig. 15.10.

Figure 15.10 depicts the corresponding experimental amplitude and phase curves. The measurements were performed in air with a Si cantilever approaching



Fig. 15.9a–c Amplitude and phase diagrams with excitation frequency **(a)** below, **(b)** exactly at, and **(c)** above the resonant frequency for tapping-mode AFM from the numerical simulations. Additionally, the bottom diagrams show the interaction forces at the point of closest tip–sample distance, i. e., the lower turnaround point of the oscillation

a Si wafer, with a cantilever resonant frequency of 299.95 kHz. Qualitatively, all prominent features of the simulated curves can also be found in the experimental data sets. Hence, the above model seems to capture the important factors necessary for an appropriate description of the experimental situation.

But what is the reason for this unexpected behavior? We have to turn to the numerical simulations again, where we have access to all physical parameters, in order to understand the underlying processes. The lower part of Fig. 15.9 also shows the interaction force between the tip and the sample at the point of closest approach, i. e., the sample-sided turnaround point of the oscillation. We see that exactly at the points of the discontinuities the total interaction force changes from the net-attractive regime to the attractive-repulsive regime, also termed the intermittent contact regime. The term net-attractive is used to emphasize that the total force is attractive, despite the fact that some minor contributions might still originate from repulsive forces. As soon as a minimum distance is reached, the tip also starts to experience repulsive forces, which completely changes the oscillation behavior. In other words, the dynamic system switches between two oscillatory states.

Directly related to this fact is the second phenomenon: the hysteresis effect. We find separate curves for the approach of the probe toward the surface and the retraction. This seems to be somewhat counterintuitive, since the tip is constantly approaching and retracting from the surface, and the average values of amplitude and phase should be independent of the direction of the average tip-sample distance movement. A hysteresis between approach and retraction within one oscillation due to dissipative processes should directly influence amplitude and phase. However, no dissipation models were included in the simulation. In this case, the hysteresis in Fig. 15.9 is due to the fact that the oscillation jumps into different modes, the system exhibits bistability. This effect is often observed



Fig. 15.10a–c Amplitude and phase diagrams with excitation frequency **(a)** below, **(b)** exactly at, and **(c)** above the resonant frequency for tapping-mode AFM from experiments with a Si cantilever on a Si wafer in air

in oscillators under the influence of nonlinear forces [15.20].

For the interpretation of these effects it is helpful to look at Fig. 15.11, which shows the behavior of the simulated tip vibration and force during one oscillation cycle over time. The data is recorded at the same z-position at a point where hysteresis is observed, while a) was taken during the approach and b) during the retraction. Excitation is in resonance, representing case 2, where the amplitude shows a small hysteresis. Also note that the amplitude is almost exactly the same in a) and b). We see that the oscillation at the same z-position exhibits two different modes: While in a) the experienced force is net-attractive, in b) the tip is exposed to attractive and repulsive interactions. Experimental and simulated data show that the change between the net-attractive and intermittent contact mode takes place at different z-positions (d_{app} and d_{ret}) for approach and retraction. Between d_{app} and d_{ret} the system is in a bistable mode. Depending on the history of the measurement, e.g., whether the position d_{app} during the approach (or d_{ret} during retraction) has been reached, the system flips to the other oscillation mode. While the amplitude might not be influenced strongly (case 2), the phase is a clear indicator of the mode switch. On the other hand, if point d_{app} is never reached during the approach, the system will stay in the net-attractive regime and no hysteresis is observed, i. e., the system remains stable.



Fig. 15.11a,b Simulation of the tapping-mode cantilever oscillation in the **(a)** net-attractive and **(b)** the intermittent contact regime. The *dashed line* represents the excitation amplitude and the *solid line* is the oscillation amplitude

In conclusion, we find that although a qualitative interpretation of the interaction forces is possible, the AM- nor tapping-mode AFM is not suitable to gain direct quantitative knowledge of tip-sample force interactions. However, it is a very useful tool for imaging nanometer-sized structures in a wide variety of setups, in air or even in liquid. We find that two distinct modes exist for the externally excited oscillation – the net-attractive and the intermittent contact mode – which describe what kind of forces the tip-sample interaction is governed by. The phase can be used as an indicator of which mode the system is running in.

In particular, it can be easily seen that if the free resonant frequency of the cantilever is higher than the excitation frequency, the system cannot stay in the net-attractive regime due to a self-enhancing instability. Since in many applications involving soft and delicate biological samples strong repulsive forces should be avoided, the tapping-mode AFM should be operated at frequencies equal to or above the free resonant frequency [15.21]. Even then, statistical changes of tip-sample forces during the scan might induce a sudden jump into the intermittent contact mode, and the previously explained hysteresis will tend to keep the system in this mode. It is, therefore, of high importance to tune the oscillation parameters in such a way that the AFM stays in the net-attractive regime [15.22]. A concept that achieves this task is the Q-control system, which will be discussed in some detail in the forthcoming paragraphs.

A last word concerning the overlap of simulation and experimental data: While the qualitative agreement down to the detailed shape of hysteresis and instabilities is rather striking, we still find some quantitative discrepancies between the positions of the instabilities d_{app} and d_{ret}. This is probably due to the simplified force model, which only takes into account van der Waals and repulsive forces. Especially at ambient conditions, an omnipresent water meniscus between tip and sample will give rise to much stronger attractive and also dissipative forces than considered in the model. A very interesting feature is that the simulated phase curves in the intermittent contact regime tend to have a steeper slope in the simulation than in the experiments (see also Fig. 15.12). We will later show that this effect is a fingerprint of an effect that had not been included in the above simulation at all: dissipative processes during the oscillation, giving rise to an additional loss of oscillation energy.



Fig. 15.12 Phase shift in tapping mode as a function of tip-sample distance

15.3.2 Self-Excitation Modes

Despite the wide range of technical applications of the AM or tapping mode of dynamic AFM, it has been found unsuitable for measurements in an environment extremely useful for scientific research: vacuum or ultrahigh vacuum (UHV) with pressures reaching 1×10^{-10} mbar. The STM has already shown how much insight can be gained from some highly defined experiments under those conditions. Consider (15.11) from the above section. The time constant τ for the amplitude to adjust to a different tip-sample force scales with $1/Q$. In vacuum applications, Q of the cantilever is on the order of 10,000, which means that τ is in the range of some 10 ms. This is clearly too long for a scan of at least (100×100) data points. The temperature-induced drift of the sample will render useful interpretation of images an impossible task. However, the resonant frequency of the system will react instantaneously to tip-sample forces. This has led *Albrecht* et al. [15.11] to use a modified excitation scheme.

The system is always oscillated at its resonant frequency. This is achieved by feeding back the oscillation signal from the cantilever into the excitation piezoelement. Figure 15.13 pictures the method in a block diagram. The signal from the PSD is phase shifted by 90 deg (and, therefore, always exciting in resonance) and used as the excitation signal of the cantilever. An additional feedback loop adjusts the excitation amplitude in such a way that the oscillation amplitude remains constant. This ensures that the tip-sample distance is not influenced by changes in the oscillation amplitude. The only degree of freedom of the oscillation system that can react to the tip-sample forces is the change of the resonant frequency. This shift of the frequency is detected and used as the set-point signal for surface scans. Therefore, this mode is also called the FM (frequency modulated) mode.

Let us take a look at the sensitivity of the dynamic AFM. If electronic noise, laser noise, and thermal drift



Fig. 15.13 Dynamic AFM operated in the self-excitation mode, where the oscillation signal is directly feedbacked to the excitation piezo. The detector signal is amplified with the variable gain G and phase shifted by phase ϕ. The frequency demodulator detects the frequency shift due to tip-sample interactions, which serves as the control signal for the probe-sample distance

can be neglected, the main noise contribution will come from thermal excitation of the cantilever. A detailed analysis of a dynamic system yields for the minimum detectable force gradient the following relation [15.11]:

$$\left.\frac{\partial F}{\partial z}\right|_{\mathrm{MIN}} = \sqrt{\frac{4k_{\mathrm{B}}TB\cdot k}{\omega_0 Q\langle z_{\mathrm{osc}}^2\rangle}}\,. \qquad (15.17)$$

Here B is the bandwidth of the measurement, T the temperature, and $\langle z_{\mathrm{osc}}^2\rangle$ is the mean-square amplitude of the oscillation. Please note that this sensitivity limit was deliberately calculated for the FM mode. A similar analysis of the AM mode, however, yields virtually the same result [15.23]. We find that the minimum detectable force gradient, i. e., the measurement sensitivity, is inversely proportional to the square root of the Q-factor of the cantilever. This means that it should be possible to achieve very high-resolution imaging in vacuum conditions. In contrast, AM- or tapping-mode AFM cannot be usefully pursued with large Q. Only the FM mode makes it possible to take practical advantage of (15.17).

A breakthrough in high-resolution AFM application was the atomic resolution imaging of the Si(111)-(7×7) surface reconstruction by Giessibl [15.8] under UHV conditions. Today, atomic resolution imaging has become a standard feature guaranteed by industrially produced dynamic AFM systems. While STM has already proven to be an indispensable tool to gain detailed insight into surface structures of conductors with atomic resolution, the dynamic AFM has opened up the avenue into investigating nonconductive surfaces with equal precision (for example, on aluminium oxide by *Barth* et al. [15.24]).

However, we are concerned with measuring atomic force potentials of a single pair of molecules. Clearly, FM-mode AFM will allow us to identify single atoms, and with sufficient care we will be able to ensure that only one atom from the tip contributes to the total force interaction. Can we, therefore, fill in the last bit of information and find a quantitative relation between the oscillation parameters and the force?

Gotsmann et al. [15.25] investigated this relation by employing a numerical approach. During each oscillation cycle the tip experiences a whole range of forces. For each step during the approach the differential equation for the whole oscillation loop (including also the feedback system) was evaluated and the relation between force and frequency shift revealed. It was possible to determine the quantitative interaction forces of a metallic contact of nanometer dimensions.

However, it was shown that there also exists an analytical relationship if some approximations are accepted [15.7, 26, 27]. Here, we will follow the route indicated by *Dürig* [15.27], although different alternative ways have also proven successful. Consider the tip oscillation trajectory reaching over a large part of the force gradient curve in Fig. 15.2. We model the tip-sample interaction as a spring constant of stiffness $k_{\mathrm{ts}}(z) = \partial F/\partial z|_{z_0}$, as in Fig. 15.1. For small oscillation amplitudes, we already found that the frequency shift is proportional to the force gradient in (15.4). For large amplitudes, we can calculate an effective force gradient k_{eff} as a convolution of the force and the fraction of time the tip spends between the positions x and $x + \mathrm{d}x$:

$$k_{\mathrm{eff}}(z) = \frac{2}{\pi A^2}\int_{z}^{z+2A} F(x)g\left(\frac{x-z}{A}-1\right)\mathrm{d}x$$
$$\text{with } g(u) = -\frac{u}{\sqrt{1-u^2}}\,. \qquad (15.18)$$

In the approximation that the vibration amplitude is much larger than the range of the tip-sample forces, the above equation can be simplified to:

$$k_{\text{eff}}(z) = \frac{\sqrt{2}}{\pi} A^{3/2} \int\limits_z^{\infty} \frac{F(x)}{\sqrt{x-z}}\,\mathrm{d}x\,. \tag{15.19}$$

This effective force gradient can now be used in (15.4), the relation between frequency shift and force gradient. We find:

$$\Delta f = \frac{f_0}{\sqrt{2}\pi k A^{3/2}} \int\limits_z^{\infty} \frac{F(x)}{\sqrt{x-z}}\,\mathrm{d}x\,. \tag{15.20}$$

If we separate the integral from other parameters, we can define:

$$\Delta f = \frac{f_0}{kA^{3/2}}\gamma(z)$$

$$\text{with } \gamma(z) = \frac{1}{\sqrt{2}\pi} \int\limits_z^{\infty} \frac{F(x)}{\sqrt{x-z}}\,\mathrm{d}x\,. \tag{15.21}$$

This means we can define $\gamma(z)$, which is only dependent on the shape of the force curve $F(z)$ but independent of the external parameters of the oscillation. The function $\gamma(z)$ is also referred to as the "normalized frequency shift" [15.7], a very useful parameter, which allows us to compare measurements independent of resonant frequency, amplitude and spring constant of the cantilever.

The dependence of the frequency shift on the vibration amplitude is an especially useful relation, since this parameter can be easily varied during one experiment. A nice example is depicted in Fig. 15.14, where frequency shift curves for different amplitudes were found to coincide very well in the $\gamma(z)$ diagrams [15.28].

This relationship has been nicely exploited for the calibration of the vibration amplitude by *Guggisberg* [15.29], which is a problem often encountered in dynamic AFM operation and worthwhile discussing. One approaches tip and sample and takes frequency shift curves versus distance, which show a reproducible shape. Then, the z-feedback is permanently turned off, and several curves with different amplitudes are taken. The amplitudes are typically chosen by adjusting the amplitude set-point in volts. One has to take care that drift in the z-direction is negligible. An analysis of the corresponding $\gamma(z)$-curves will show the same curves (as in Fig. 15.14), but the curves will be shifted in the horizontal axis. These shifts correspond to the change in amplitude, allowing one to correlate the voltage values with the z-distances.

For the oft-encountered force contributions from electrostatic, van der Waals, and chemical binding forces the frequency shift has been calculated from the force laws. In the approximation that the tip radius R is larger than the tip-sample distance z, an electrostatic potential V will yield a normalized frequency shift of (adapted from [15.30]):

$$\gamma(z) = \frac{\pi\varepsilon_0 R V^2}{\sqrt{2}} z^{-1/2}\,. \tag{15.22}$$



Fig. 15.14 **(a)** Frequency-shift curves for different oscillation amplitudes for a silicon tip on a graphite surface in UHV, **(b)** γ-curves calculated from the Δf-curves in **(a)**. (After [15.28] with permission, Copyright (2000) by The American Physical Society)

For van der Waals forces with Hamaker constant H and with R larger than z, we find accordingly:

$$\gamma(z) = \frac{HR}{12\sqrt{2}} z^{-3/2} \,. \tag{15.23}$$

Finally, short-range chemical forces represented by the well-known Morse potential (with the parameters binding energy U_0, decay length λ, and equilibrium distance z_{equ}) yield:

$$\gamma(z) = \frac{U_0\sqrt{2}}{\sqrt{\pi\lambda}} \exp\left(-\frac{(z - z_{\text{equ}})}{\lambda}\right) \,. \tag{15.24}$$

These equations allow the experimentalist to directly interpret the spectroscopic measurements. For example, the contributions of the electrostatic and van der Waals forces can be easily distinguished by their slope in a log-log plot (for an example, see [15.30]).

Alternatively, if the force law is not known beforehand, the experimentalist wants to analyze the experimental frequency-shift data curves and extract the force or energy potential curves. We, therefore, have to invert the integral in (15.21) to find the tip-sample interaction potential V_{ts} from the $\gamma(z)$-curves [15.27]:

$$V_{\text{ts}}(z) = \sqrt{2} \int_z^\infty \frac{\gamma(x)}{\sqrt{x - z}} \, \mathrm{d}x \,. \tag{15.25}$$

Using this method, quantitative force curves were extracted from Δf-spectroscopy measurements on different, atomically resolved sites of the Si(111)-(7×7) reconstruction [15.1]. Comparison to theoretical MD simulations showed good quantitative agreement with theory and confirmed the assumption that force interactions were governed by a single atom at the tip apex. Our initially formulated goal seems to be achieved: With FM-AFM we have found a powerful method that allows us to measure the chemical bond formation of single molecules. The last uncertainty, the exact shape and identity of the tip apex atom, can possibly be resolved by employing the FIM technique to characterize the tip surface in combination with FM-AFM.

All the above equations are strictly valid only in the approximation that the oscillation amplitudes are much larger than the distance range of the encountered forces. For amplitudes of 10 nm and long-range forces like electrostatic interactions this approximation may not be valid. An iterative approach has been presented by *Dürig* [15.31] to overcome this problem. The interaction force is calculated from the frequency shift curves [gradient of (15.25)]. This force curve again is used to calculate the frequency shift with the exact relation from (15.18). The difference between the experimental Δf-curve and the reconstructed Δf-curve can now be used to calculate a first-order correction term to the interaction force. This procedure can be iteratively followed until sufficient agreement is found.

In this context it is worthwhile to point out a slightly different dynamic AFM method. While in the typical FM-AFM setup the oscillation amplitude is controlled to stay constant by a dedicated feedback circuit, one could simply keep the excitation amplitude constant (this has been termed *CA = constant amplitude*, as opposed to the *CE = constant excitation* mode). It is expected that this mode is more gentle to the surface, because any dissipative interaction will reduce the amplitude and therefore increase the tip-sample distance. The tip is prevented from deeply indenting the surface. This mode has been employed to image soft biological molecules like DNA or thiols in UHV [15.32]. However, quantitative interpretation of the obtained frequency spectra is more complicated, since the amplitude and tip-sample distance are altered during the measurement. Until now, we have always associated the self-excitation scheme with vacuum applications. Although it is difficult to operate the FM-AFM in constant amplitude mode in air, since large dissipative effects make it difficult to ensure a constant amplitude, it is indeed possible to use the constant-excitation FM-AFM in air or even in liquid. Still, only a few applications of FM-AFM under ambient or liquid conditions have been reported so far. In fact, a low budget construction set (employing a tuning-fork force sensor) for a CE-mode dynamic AFM setup has been published on the Internet (*http://www.sxm4.uni-muenster.de*).

15.4 *Q*-Control

We have already discussed the virtues of a high Q value for high sensitivity measurements: The minimum detectable force gradient was inversely proportional to the square root of Q. In vacuum, Q mainly represents the internal dissipation of the cantilever during oscillation, an internal damping factor. Little damping is obtained by using high quality cantilevers, which are cut (or etched) from defect-free, single-crystal silicon wafers. Under ambient or liquid conditions, the quality factor is dominated by dissipative interactions between the cantilever and the surrounding medium, and Q values can be as low as 100 for air or even 5 in liquid. Still, we ask if it is somehow possible to compensate for the damping effect by exciting the cantilever in a sophisticated way?

It turns out that the shape of the resonance curves in Fig. 15.15 can be influenced toward higher (or lower) Q values by an amplitude feedback loop. In principle, there are several mechanisms to couple the amplitude signal back to the cantilever, by the photothermal effect [15.33] or capacitive forces [15.34]. Figure 15.16 shows a method in which the amplitude feedback is mediated directly by the excitation piezo [15.35]. This has the advantage that no additional mechanical setups are necessary.



Fig. 15.16 Schematic diagram of operating a Q-Control feedback circuit with an externally driven dynamic AFM. The tapping mode setup is in effect extended by an additional feedback loop

The working principle of the feedback loop can be understood by analyzing the equation of motion of the modified dynamic system:

$$m^* \ddot{z}(t) + \alpha \dot{z}(t) + k z(t) - F_{\text{ts}}\,(z_0 + z(t)) = F_{\text{ext}} \cos(\omega t) + G\,\mathrm{e}^{\mathrm{i}\phi} z(t)\,. \qquad (15.26)$$

This ansatz takes into account the feedback of the detector signal through a phase shifter, amplifier, and adder as an additional force, which is linked to the cantilever deflection $z(t)$ through the gain G and the phase shift $\mathrm{e}^{\mathrm{i}\phi}$. To a good approximation, we assume that the oscillation can be described by a harmonic trajectory. With a phase



Fig. 15.15 Amplitude and phase diagrams measured in air with a Si cantilever far away from the sample. The quality factor can be increased from 450 to 20,000 by using the Q-Control feedback method



Fig. 15.17 Enhancement of the contrast in the phase channel due to Q-Control on a magnetic hard disk measured with a magnetic tip in tapping-mode AFM in air. Scan size $5 \times 5\,\mu\text{m}$, phase range 10 deg (www.nanoanalytics.com)

shift of $\phi = \pm\pi/2$ we find:

$$e^{\pm i\pi/2} z(t) = \pm \frac{1}{\omega} \dot{z}(t)\,. \qquad (15.27)$$

This means that the additional feedback force signal $G e^{i\phi} z(t)$ is proportional to the velocity of the cantilever, just like the damping term in the equation of motion. We can define an effective damping constant α_{eff}, which combines the two terms:

$$\begin{aligned} & m^* \ddot{z}(t) + \alpha_{\text{eff}} \dot{z}(t) + kz(t) - F_{\text{ts}}(z_0 + z(t)) \\ & \quad = F_{\text{ext}} \cos(\omega t) \\ & \quad \text{with } \alpha_{\text{eff}} = \alpha \mp \frac{1}{\omega} G \quad \text{for } \phi = \pm \frac{\pi}{2}\,. \end{aligned} \qquad (15.28)$$

Equation (15.28) shows that the dampening of the oscillator can be enhanced or weakened by the choice of G, $\phi = +\pi/2$ or $\phi = -\pi/2$, respectively. The feedback loop, therefore, allows us to vary the effective quality factor $Q_{\text{eff}} = m\omega_0/\alpha_{\text{eff}}$ of the complete dynamic system. Hence, we term this system Q-Control. Figure 15.15 shows experimental data on the effect of Q-Control on the amplitude and phase as a function of the external excitation frequency [15.35]. While $Q = 449$, without Q-Control the quality factor of the system operated in air is enhanced by a factor of more than 40 by applying the feedback loop.

The effect of improved image contrast is demonstrated in Fig. 15.17. Here, a computer hard disk was analyzed with a magnetic tip in tapping mode, where the magnetic contrast is observed in the phase image. The upper part shows the recorded magnetic data structures in standard mode, whereas in the lower part of the image Q-Control feedback was activated, giving rise to an improved signal, i. e., magnetic contrast. A more detailed analysis of measurements on a magnetic tape shows that the signal amplitude (upper diagrams in Fig. 15.18), i. e.,



Fig. 15.18 Signal-to-noise analysis with a magnetic tip in tapping-mode AFM on a magnetic tape sample with Q-Control

the image contrast, was increased by a factor of 12.4 by the Q-Control feedback. The lower image shows a noise analysis of the signal, indicating an increase of the signal-to-noise ratio by a factor of 2.3.

Note that the diagrams represent measurements in air with an AFM operated in AM mode. Only then can we make a distinction between excitation and vibration frequency, since in the FM mode these two frequencies are equal by definition. Although the relation between sensitivity and Q-factor in (15.17) is the same for AM and FM mode, it must be critically investigated to see whether the enhanced quality factor by Q-Control can be inserted in the equation for FM-mode AFM. In vacuum applications, Q is already very high, which makes it oblique to operate an additional Q-Control module.

As stated before, we can also use Q-Control to enhance the dampening in the oscillating system. This would decrease the sensitivity of the system. But on the other hand, the response time of the amplitude change is decreased as well. For tapping-mode applications, where high speed scanning is the goal, Q-Control will be able to reduce the relaxation time [15.36].

A large quality factor Q does not only have the virtue of increasing the force sensitivity of the instrument. It also has the advantage of increasing the parameter space of stable AFM operation in tapping- or AM-mode AFM. Consider the resonance curve of Fig. 15.5. When approaching the tip toward the surface there are two competing mechanisms: On the one hand, we bring the tip closer to the sample, which results in an increase in attractive forces (see Fig. 15.2). On the other hand, for the case $\omega > \omega_0$, the resonant frequency of the cantilever is shifted toward smaller values due to the attractive forces, which causes the amplitude to become smaller, preventing a tip-sample contact. This is the desirable regime, where stable operation of the AFM is possible in the net-attractive regime. But as explained before, below a certain tip-sample separation d_{app}, the system switches suddenly into intermittent contact mode, where surface modifications are likely due to the onset of strong repulsive forces. The steeper the amplitude curve the larger the regime of stable, net-attractive AFM operation. Looking at Fig. 15.5 we find that the slope of the amplitude curve is governed by the quality factor Q. A high Q, therefore, facilitates stable operation of the AM-AFM in the net-attractive regime.



Fig. 15.19 Imaging of a delicate organic surface with Q-Control. Sample was a Langmuir-Blodgett film (ethyl-2,3-dihydroxyoctadecanoate) on a mica substrate. The topographical image clearly shows that the highly sensitive sample surface can only be imaged non-destructively with active Q-Control, whereas the periodic repulsive contact with the probe in standard operation without Q-Control leads to a significant modification or destruction of the surface structure. (Data courtesy of *Lifeng Chi* and coworkers, Westfälische Wilhelms-Universität, Münster, Germany)

An example can be found in Fig. 15.19. Here, a surface scan of an ultrathin organic film is acquired in tapping mode under ambient conditions. First, the inner square is scanned without the Q enhancement, and then a wider surface area was scanned with applied Q-Control. The high quality factor provides a larger parameter space for operating the AFM in the net-attractive regime, allowing good resolution of the delicate organic surface structure. Without the Q-Control the surface structures are deformed and even destroyed due to the strong repulsive tip-sample interactions [15.37–39]. This also allowed imaging of DNA structures without predominantly depressing the soft material during imaging. It was then possible to observe a DNA diameter close to the theoretical value with the Q-Control feedback [15.40].

In conclusion, we have shown that by applying an additional feedback circuit to the dynamic AFM system it is possible to influence the quality factor Q of the oscillator system. High-resolution, high-speed, or low-force scanning is then possible.

15.5 Dissipation Processes Measured with Dynamic AFM

Dynamic AFM methods have proven their great potential for imaging surface structures at the nanoscale, and we have also discussed methods that allow the assessment of forces between distinct single molecules. However, there is another physical mechanism that can be analyzed with the dynamic mode and has been mentioned in some previous paragraphs: energy dissipation. In Fig. 15.12, we have already shown an example, where the phase signal in tapping mode cannot be explained by conservative forces alone; dissipative processes must also play a role. In constant-amplitude FM mode, where the quantitative interpretation of experiments has proven to be less difficult, an intuitive distinction between conservative and dissipative tip-sample interaction is possible. While we have shown the correlation between forces and frequency shifts of the oscillating system, we have neglected one experimental input channel. The excitation amplitude, which is necessary to keep the oscillation amplitude constant, is a direct indication of the energy dissipated during one oscillation cycle. *Dürig* [15.41] has shown that in self-excitation mode (with an excitation-oscillation phase difference of 90 deg), conservative and dissipative interactions can be strictly separated. Part of this energy is dissipated in the cantilever itself, another part is due to external viscous forces in the surrounding medium. But more interestingly, some energy is dissipated at the tip-sample junction. This is the focus of the following paragraphs.

In contrast to conservative forces acting at the tip-sample junction, which at least in vacuum can be understood in terms of van der Waals, electrostatic, and chemical interactions, the dissipative processes are poorly understood. *Stowe* et al. [15.42] have shown that if a voltage potential is applied between tip and sample, charges are induced in the sample surface, which will follow the tip motion (here the oscillation is parallel to the surface). Due to the finite resistance of the sample material, energy will be dissipated during the charge movement. This effect has been exploited to image the doping level of semiconductors. Energy dissipation has also been observed in imaging magnetic materials. *Liu* et al. [15.43] found that energy dissipation due to magnetic interactions was enhanced at the boundaries of magnetic domains, which was attributed to domain wall oscillations. But also in the absence of external electromagnetic fields, energy dissipation was observed in close proximity of tip and sample, within 1 nm. Clearly, mechanical surface relaxations must give rise to energy losses. One could model the AFM tip as a small hammer, hitting the surface at high frequency, possibly resulting in phonon excitations. From a contiuum mechanics point of view, we assume that the mechanical relaxation of the surface is not only governed by elastic responses. Viscoelastic effects of soft surfaces will also render a significant contribution to energy dissipation. The whole area of phase imaging in tapping mode is concerned with those effects [15.44–47].

In the atomistic view, the last tip atom can be envisaged to change position while yielding to the tip-sample force field. A strictly reversible change of position would not result in a loss of energy. Still, it has been pointed out by *Sasaki* et al. [15.48] that a change in atom position would result in a change in the force interaction itself. Therefore, it is possible that the tip atom changes position at different tip-surface distances during approach and retraction, effectively causing an atomic-scale hysteresis to develop. In fact, *Hoffmann* et al. [15.13] have measured short-range energy dissipation for a tungsten tip on silicon in UHV. A theoretical model explaining this effect on the basis of a two-energy-state system was developed. However, a clear understanding of the underlying physical mechanism is still lacking.

Nonetheless, the dissipation channel has been used to image surfaces with atomic resolution [15.49]. Instead of feedbacking the distance on the frequency shift, the excitation amplitude in FM mode has been used as the control signal. The Si(111)-(7×7) reconstruction was successfully imaged in this mode. The step edges of monoatomic NaCl islands on single-crystalline copper have also rendered atomic resolution contrast in the dissipation channel [15.50]. The dissipation processes discussed so far are mostly in the configuration in which the tip is oscillated perpendicular to the surface. Friction is usually referred to as the energy loss due to lateral movement of solid bodies in contact. It is interesting to note in this context that *Israelachivili* [15.51] has pointed out a quantitative relationship between lateral and vertical (with respect to the surface) dissipation. He states that the hysteresis in vertical force-distance curves should equal the energy loss in lateral friction. An experimental confirmation of this conjecture at the molecular level is still missing.

Physical interpretation of energy dissipation processes at the atomic scale seems to be a daunting task at this point. Notwithstanding, we can find a quantitative relation between the energy loss per oscillation cycle and the experimental parameters in dynamic AFM, as will be shown in the following section.

In static AFM it was found that permanent changes of the sample surface by indentations can cause a hysteresis between approach and retraction (e.g., [15.5]). The area between the approach and retraction curves in a force-distance diagram represents the lost or dissipated energy caused by the irreversible change of the surface structure. In dynamic-mode AFM, the oscillation parameters like amplitude, frequency, and phase must contain the information about the dissipated energy per cycle. So far, we have resorted to a treatment of the equation of motion of the cantilever vibration in order to find a quantitative correlation between forces and the experimental parameters. For the dissipation it is useful to treat the system from the energy conservation point of view.

Assuming a dynamic system is in equilibrium, the average energy input must equal the average energy output or dissipation. Applying this rule to an AFM running in a dynamic mode means that the average power fed into the cantilever oscillation by an external driver, denoted $\bar{P}_{\text{in}}$, must equal the average power dissipated by the motion of the cantilever beam $\bar{P}_0$ and by tip-sample interaction $\bar{P}_{\text{tip}}$:

$$\bar{P}_{\text{in}} = \bar{P}_0 + \bar{P}_{\text{tip}}\,. \tag{15.29}$$

The term $\bar{P}_{\text{tip}}$ is what we are interested in, since it gives us a direct physical quantity to characterize the tip-sample interaction. Therefore, we have first to calculate and then measure the two other terms in (15.29) in order to determine the power dissipated when the tip periodically probes the sample surface. This requires an appropriate rheological model to describe the dynamic system. Although there are investigations in which the complete flexural motion of the cantilever beam has been considered [15.52], a simplified model, comprising a spring and two dashpots (Fig. 15.20), represents a good approximation in this case [15.53].

The spring, characterized by the constant k according to Hooke's law, represents the only channel through which power P_{in} can be delivered to the oscillating tip $z(t)$ by the external driver $z_{\text{d}}(t)$. Therefore, the instantaneous power fed into the dynamic system is equal to the force exerted by the driver times the velocity of the driver (the force that is necessary to move the base side of the dashpot can be neglected, since this power is directly dissipated and, therefore, does not contribute to the power delivered to the oscillating tip):

$$P_{\text{in}}(t) = F_{\text{d}}(t)\dot{z}_{\text{d}}(t) = k\,[z(t) - z_{\text{d}}(t)]\,\dot{z}_{\text{d}}(t)\,. \tag{15.30}$$

Assuming a sinusoidal steady state response and that the base of the cantilever is driven sinusoidally (see (15.6)) with amplitude A_{d} and frequency ω, the deflection from equilibrium of the end of the cantilever follows (15.9), where A and $0 \le \varphi \le \pi$ are the oscillation amplitude and phase shift, respectively. This allows us to calculate the average power input per oscillation cycle by integrating (15.30) over one period $T = 2\pi/\omega$:

$$\bar{P}_{\text{in}} = \frac{1}{T}\int_0^T P_{\text{in}}(t)\;\mathrm{d}t = \frac{1}{2}k\omega A_{\text{d}} A\sin\varphi\,. \tag{15.31}$$



Fig. 15.20 Rheological model applied to describe the dynamic AFM system, comprising the oscillating cantilever and tip interacting with the sample surface. The movement of the cantilever base and the tip is denoted as $z_{\text{d}}(t)$ and $z(t)$, respectively. The cantilever is characterized by the spring constant k and the damping constant α. In a first approach, damping is broken into two pieces, α_1 and α_2. First, intrinsic damping caused by the movement of the cantilever's tip relative to its base. Second, damping related to the movement of the cantilever body in a surrounding medium, e.g., air damping

This contains the familiar result that the maximum power is delivered to an oscillator when the response is 90 deg out of phase with the drive.

The simplified rheological model, as it is depicted in Fig. 15.20, exhibits two major contributions to the damping term $\bar{P}_0$. Both are related to the motion of the cantilever body and assumed to be well modeled by viscous damping with coefficients α_1 and α_2. The dominant damping mechanism in UHV conditions is intrinsic damping caused by the deflection of the cantilever beam, i. e., the motion of the tip relative to the cantilever base. Therefore, the instantaneous power dissipated by such a mechanism is given by

$$P_{01}(t) = |F_{01}(t)\dot{z}(t)| = |\alpha_1\,[\dot{z}(t) - \dot{z}_{\text{d}}(t)]\,\dot{z}(t)|\,. \tag{15.32}$$

Note that the absolute value has to be calculated, since all dissipated power is "lost" and, therefore, cannot be returned to the dynamic system.

However, when running an AFM in ambient conditions an additional damping mechanism has to be considered. Damping due to the motion of the cantilever body in the surrounding medium, e.g., air damping, is in most cases the dominant effect. The corresponding instantaneous power dissipation is given by

$$P_{02}(t) = |F_{02}(t)\dot{z}(t)| = \alpha_2 \dot{z}^2(t) . \qquad (15.33)$$

In order to calculate the average power dissipation, (15.32) and (15.33) have to be integrated over one complete oscillation cycle. This yields

$$\begin{aligned} \bar{P}_{01} &= \frac{1}{T}\int_0^T P_{01}(t)\,\mathrm{d}t \\ &= \frac{1}{\pi}\alpha_1\omega^2 A \Bigg[(A - A_\mathrm{d}\cos\varphi) \\ &\quad \times \arcsin\left(\frac{A - A_\mathrm{d}\cos\varphi}{\sqrt{A^2 + A_\mathrm{d}^2 - 2AA_\mathrm{d}\cos\varphi}}\right) \\ &\quad + A_\mathrm{d}\sin\varphi \Bigg] , \end{aligned} \qquad (15.34)$$

and

$$P_{02}(t) = \frac{1}{T}\int_0^T P_{02}(t)\,\mathrm{d}t = \frac{1}{2}\alpha_2\omega^2 A^2 . \qquad (15.35)$$

Considering the fact that commonly used cantilevers exhibit a quality factor of at least several hundreds (in UHV several tens of thousands), we can assume that the oscillation amplitude is significantly larger than the drive amplitude when the dynamic system is driven at or near its resonance frequency: $A \gg A_\mathrm{d}$. Therefore, (15.34) can be simplified in first order approximation to an expression similar to (15.35). Combining the two equations yields the total average power dissipated by the oscillating cantilever

$$\bar{P}_0 = \frac{1}{2}\alpha\omega^2 A^2 \quad \text{with } \alpha = \alpha_1 + \alpha_2 , \qquad (15.36)$$

where α denotes the overall effective damping constant.

We can now solve (15.29) for the power dissipation localized to the small interaction volume of the probing tip with the sample surface, represented by the question mark in Fig. 15.20. Furthermore, by expressing the damping constant α in terms of experimentally accessible quantities such as the spring constant k, the quality factor Q, and the natural resonant frequency ω_0 of the free oscillating cantilever, $\alpha = \frac{k}{Q\omega_0}$, we obtain:

$$\begin{aligned} \bar{P}_\mathrm{tip} &= \bar{P}_\mathrm{in} - \bar{P}_0 \\ &= \frac{1}{2}\frac{k\omega}{Q}\left(Q_\mathrm{cant}A_\mathrm{d}A\sin\varphi - A^2\frac{\omega}{\omega_0}\right) . \end{aligned} \qquad (15.37)$$

Note that so far no assumptions have been made regarding how the AFM is operated, except that the motion of the oscillating cantilever has to remain sinusoidal to a good approximation. Therefore, (15.37) is applicable to a variety of different dynamic AFM modes.

For example, in FM-mode AFM the oscillation frequency ω changes due to tip-sample interaction, while at the same time the oscillation amplitude A is kept constant by adjusting the drive amplitude A_d. By measuring these quantities, one can apply (15.37) to determine the average power dissipation related to tip-sample interaction. In spectroscopy applications, usually $A_\mathrm{d}(d)$ is not measured directly, but a signal $G(d)$ proportional to $A_\mathrm{d}(d)$ is acquired representing the gain factor applied to the excitation piezo. With the help of (15.15) we can write:

$$A_\mathrm{d}(d) = \frac{A_0 G(d)}{QG_0} , \qquad (15.38)$$

while A_0 and G_0 are the amplitude and gain at large tip-sample distances, where the tip-sample interactions are negligible.

Now let us consider the tapping-mode, or AM-AFM. In this case, the cantilever is driven at a fixed frequency and with constant drive amplitude, while the oscillation amplitude and phase shift may change when the probing tip interacts with the sample surface. Assuming that the oscillation frequency is chosen to be ω_0, (15.37) can be further simplified by again employing (15.15) for the free oscillation amplitude A_0. This yields

$$\bar{P}_\mathrm{tip} = \frac{1}{2}\frac{k\omega_0}{Q}\left(A_0 A\sin\varphi - A^2\right) . \qquad (15.39)$$

Equation (15.39) implies that if the oscillation amplitude A is kept constant by a feedback loop, like it is commonly done in tapping mode, simultaneously acquired phase data can be interpreted in terms of energy dissipation [15.45, 47, 54, 55]. When analyzing such phase images [15.56–58], one has also to consider the fact that the phase may also change due to the transition from net-attractive ($\varphi > 90°$) to intermittent contact ($\varphi < 90°$) interaction between the tip and the sample [15.15, 35, 59, 60]. For example, consider the phase shift in tapping mode as a function of z-position, Fig. 15.12. If phase measurements are performed close to the point where the oscillation switches from the net-attractive to the intermittent contact regime, a large contrast in the phase channel is observed. However, this contrast is not due to dissipative processes. Only a variation of the phase signal within the intermittent contact regime will give information of the tip-sample dissipative processes.

An example of a dissipation measurement is depicted in Fig. 15.21. The surface of a polymer blend was imaged in air, simultaneously acquiring the topography and dissipation. The dissipation on the softer polyurethane-matrix is significantly larger than on the embedded, mechanically stiffer polypropylene particles.



Topography
x,y,z-range: 5 µm × 5 µm × 546 nm

Dissipation
Data range: 3.0 pW or 257 eV

Fig. 15.21 Topography and phase image in tapping-mode AFM of a polymer blend composed of polypropylene (PP) particles embedded in a polyurethane (PUR) matrix. The dissipation image shows a strong contrast between the harder PP (little dissipation, *dark*) to the softer PUR (large dissipation, *bright*) surface

15.6 Conclusion

Dynamic force microscopy is a powerful tool that is capable of imaging surfaces with atomic precision. It also allows us to look at surface dynamics, and it can operate in vacuum, air, or even in liquid. However, the oscillating cantilever system introduces a level of complexity that disallows a straightforward interpretation of acquired images. An exception is the self-excitation mode, where tip-sample forces can be successfully extracted from spectroscopic experiments. However, not only conservative forces can be investigated with dynamic AFM; energy dissipation also influences the cantilever oscillation and can, therefore, serve as a new information channel.

Open questions still exist concerning the exact geometric and chemical identity of the probing tip, which significantly influences the imaging and spectroscopic results. Using predefined tips like single-walled nanotubes or atomic resolution techniques like field ion microscopy to image the tip itself are possible approaches to addressing this issue. Furthermore, little is known about the dissipative processes at the scale where only a few atoms between tip and sample interact. It is also desirable to learn more about the interpretation of images acquired in tapping mode.

References

15.1 M. A. Lantz, H. J. Hug, R. Hoffmann, P. J. A. van Schendel, P. Kappenberger, S. Martin, A. Baratoff, H.-J. Güntherodt: Quantitative measurement of short-range chemical bonding forces, Science **291** (2001) 2580–2583

15.2 G. Binnig, C. F. Quate, Ch. Gerber: Atomic force microscope, Phys. Rev. Lett. **56** (1986) 930–933

15.3 O. Marti: AFM instrumentation and tips. In: *Handbook of Micro/Nanotribology*, 2nd edn., ed. by B. Bhushan (CRC, Boca Raton 1999) pp. 81–144

15.4 G. Cross, A. Schirmeisen, A. Stalder, P. Grütter, M. Tschudy, U. Dürig: Adhesion interaction between atoically defined tip and sample, Phys. Rev. Lett. **80** (1998) 4685–4688

15.5 A. Schirmeisen, G. Cross, A. Stalder, P. Grütter, U. Dürig: Metallic adhesion and tunneling at the atomic scale, New J. Phys. **2** (2000) 29.1–29.10

15.6 A. Schirmeisen: Metallic adhesion and tunneling at the atomic scale. Ph.D. Thesis (McGill University, Montréal 1999) pp. 29–38

15.7 F. J. Giessibl: Forces and frequency shifts in atomic-resolution dynamic-force microscopy, Phys. Rev. B **56** (1997) 16010–16015

15.8 F. J. Giessibl: Atomic resolution of the silicon (111)-(7×7) surface by atomic force microscopy, Science **267** (1995) 68–71

15.9 M. Bezanilaa, B. Drake, E. Nudler, M. Kashlev, P. K. Hansma, H. G. Hansma: Motion and enzymatic degradation of DNA in the atomic force microscope, Biophys. J. **67** (1994) 2454–2459

15.10 Y. Jiao, D. I. Cherny, G. Heim, T. M. Jovin, T. E. Schäffer: Dynamic interactions of p53 with DNA in solution by time-lapse atomic force microscopy, J. Mol. Biol. **314** (2001) 233–243

15.11 T. R. Albrecht, P. Grütter, D. Horne, D. Rugar: Frequency modulation detection using high-Q cantilevers for enhanced force microscopy sensitivity, J. Appl. Phys. **69** (1991) 668–673

15.12 S. P. Jarvis, M. A. Lantz, U. Dürig, H. Tokumoto: Off resonance AC mode force spectroscopy and imaging with an atomic force microscope, Appl. Surf. Sci. **140** (1999) 309–313

15.13 P. M. Hoffmann, S. Jeffery, J. B. Pethica, H. Ö. Özer, A. Oral: Energy dissipation in atomic force microscopy and atomic loss processes, Phys. Rev. Lett. **87** (2001) 265502–265505

15.14 B. Anczykowski, D. Krüger, H. Fuchs: Cantilever dynamics in quasinoncontact force microscopy: Spectroscopic aspects, Phys. Rev. B **53** (1996) 15485–15488

15.15 B. Anczykowski, D. Krüger, K. L. Babcock, H. Fuchs: Basic properties of dynamic force spectroscopy with the scanning force microscope in experiment and simulation, Ultramicroscopy **66** (1996) 251–259

15.16 V. M. Muller, V. S. Yushchenko, B. V. Derjaguin: On the influence of molecular forces on the deformation of an elastic sphere and its sticking to a rigid plane, J. Coll. Interf. Sci. **77** (1980) 91–101

15.17 B. D. Hughes, L. R. White: 'Soft' contact problems in linear elasticity, Quart. J. Mech. Appl. Math. **32** (1979) 445–471

15.18 L. Verlet: Computer "experiments" on classical fluids. I. Thermodynamical properties of Lennard–Jones molecules, Phys. Rev. **159** (1967) 98–103

15.19 L. Verlet: Computer "experiments" on classical fluids. II. Equilibrium correlation functions, Phys. Rev. **165** (1968) 201–214

15.20 P. Gleyzes, P. K. Kuo, A. C. Boccara: Bistable behavior of a vibrating tip near a solid surface, Appl. Phys. Lett. **58** (1991) 2989–2991

15.21 A. San Paulo, R. García: High-resolution imaging of antibodies by tapping-mode atomic force microscopy: Attractive and repulsive tip-sample interaction regimes, Biophys. J. **78** (2000) 1599–1605

15.22 D. Krüger, B. Anczykowski, H. Fuchs: Physical properties of dynamic force microscopies in contact and noncontact operation, Ann. Phys. **6** (1997) 341–363

15.23 Y. Martin, C. C. Williams, H. K. Wickramasinghe: Atomic force microscope – force mapping and profiling on a sub 100-Å scale, J. Appl. Phys. **61** (1987) 4723–4729

15.24 C. Barth, M. Reichling: Imaging the atomic arrangement on the high-temperature reconstructed α-Al$_2$O$_3$(0001) surface, Nature **414** (2001) 54–57

15.25 B. Gotsmann, H. Fuchs: Dynamic force spectroscopy of conservative and dissipative forces in an Al-Au(111) tip-sample system, Phys. Rev. Lett. **86** (2001) 2597–2600

15.26 H. Hölscher, W. Allers, U. D. Schwarz, A. Schwarz, R. Wiesendanger: Determination of tip-sample interaction potentials by dynamic force spectroscopy, Phys. Rev. Lett. **83** (1999) 4780–4783

15.27 U. Dürig: Relations between interaction force and frequency shift in large-amplitude dynamic force microscopy, Appl. Phys. Lett. **75** (1999) 433–435

15.28 H. Hölscher, A. Schwarz, W. Allers, U. D. Schwarz, R. Wiesendanger: Quantitative analysis of dynamic-force-spectroscopy data on graphite(0001) in the contact and noncontact regime, Phys. Rev. B **61** (2000) 12678–12681

15.29 M. Guggisberg: Lokale Messung von atomaren Kräften. Ph.D. Thesis (University Basel, Basel 2000) pp. 9–11

15.30 M. Guggisberg, M. Bammerlin, E. Meyer, H.-J. Güntherodt: Separation of interactions by noncontact force microscopy, Phys. Rev. B **61** (2000) 11151–11155

15.31 U. Dürig: Extracting interaction forces and complementary observables in dynamic probe microscopy, Appl. Phys. Lett. **76** (2000) 1203–1205

15.32 T. Uchihasi, T. Ishida, M. Komiyama, M. Ashino, Y. Sugawara, W. Mizutani, K. Yokoyama, S. Morita, H. Tokumoto, M. Ishikawa: High-resolution imaging of organic monolayers using noncontact AFM, Appl. Surf. Sci. **157** (2000) 244–250

15.33 J. Mertz, O. Marti, J. Mlynek: Regulation of a microcantilever response by force feedback, Appl. Phys. Lett. **62** (1993) 2344–2346

15.34 D. Rugar, P. Grütter: Mechanical parametric amplification and thermomechanical noise squeezing, Phys. Rev. Lett. **67** (1991) 699–702

15.35 B. Anczykowski , J. P. Cleveland, D. Krüger, V. B. Elings, H. Fuchs: Analysis of the interaction mechanisms in dynamic mode SFM by means of experimental data and computer simulation, Appl. Phys. A **66** (1998) 885–889

15.36 T. Sulchek, G. G. Yaralioglu, C. F. Quate, S. C. Minne: Characterization and optimisation of scan speed for tapping-mode atomic force microscopy, Rev. Sci. Instrum. **73** (2002) 2928–2936

15.37 L. F. Chi, S. Jacobi, B. Anczykowski, M. Overs, H.-J. Schäfer, H. Fuchs: Supermolecular periodic structures in monolayers, Adv. Mater. **12** (2000) 25–30

15.38 S. Gao, L. F. Chi, S. Lenhert, B. Anczykowski, C. Niemeyer, M. Adler, H. Fuchs: High-quality mapping of DNA-protein complexes by dynamic scanning force microscopy, ChemPhysChem **6** (2001) 384–388

15.39 B. Zou, M. Wang, D. Qiu, X. Zhang, L. F. Chi, H. Fuchs: Confined supramolecular nanostructures of mesogen-bearing amphiphiles, Chem. Commun. **9** (2002) 1008–1009

15.40 B. Pignataro, L. F. Chi, S. Gao, B. Anczykowski, C. Niemeyer, M. Adler, H. Fuchs: Dynamic scanning force microscopy study of self-assembled DNA-protein nanostructures, Appl. Phys. A **74** (2002) 447–452

15.41 U. Dürig: Interaction sensing in dynamic force microscopy, New J. Phys. **2** (2000) 5.1–5.2

15.42 T. D. Stowe, T. W. Kenny, D. J. Thomson, D. Rugar: Silicon dopant imaging by dissipation force microscopy, Appl. Phys. Lett. **75** (1999) 2785–2787

15.43 Y. Liu, P. Grütter: Magnetic dissipation force microscopy studies of magnetic materials, J. Appl. Phys. **83** (1998) 7333–7338

15.44 J. Tamayo, R. García: Effects of elastic and inelastic interactions on phase contrast images in tapping-mode scanning force microscopy, Appl. Phys. Lett. **71** (1997) 2394–2396

15.45 J. P. Cleveland, B. Anczykowski, A. E. Schmid, V. B. Elings: Energy dissipation in tapping-mode atomic force microscopy, Appl. Phys. Lett. **72** (1998) 2613–2615

15.46 R. García, J. Tamayo, M. Calleja, F. García: Phase contrast in tapping-mode scanning force microscopy, Appl. Phys. A **66** (1998) 309–312

15.47 B. Anczykowski, B. Gotsmann, H. Fuchs, J. P. Cleveland, V. B. Elings: How to measure energy dissipation in dynamic mode atomic force microscopy, Appl. Surf. Sci. **140** (1999) 376–382

15.48 N. Sasaki, M. Tsukada: Effect of microscopic nonconservative process on noncontact atomic force microscopy, Jpn. J. Appl. Phys. **39** (2000) L1334–L1337

15.49 R. Lüthi, E. Meyer, M. Bammerlin, A. Baratoff, L. Howald, C. Gerber, H.-J Güntherodt: Ultrahigh vacuum atomic force microscopy: true atomic resolution, Surf. Rev. Lett. **4** (1997) 1025–1029

15.50 R. Bennewitz, A. S. Foster, L. N. Kantorovich, M. Bammerlin, Ch. Loppacher, S. Schär, M. Guggisberg, E. Meyer, A. L. Shluger: Atomically resolved edges and kinks of NaCl islands on Cu(111): experiment and theory, Phys. Rev. B **62** (2000) 2074–2084

15.51 J. Israelachvili: *Intermolecular and Surface Forces* (Academic, London 1992)

15.52 U. Rabe, J. Turner, W. Arnold: Analysis of the high-frequency response of atomic force microscope cantilevers, Appl. Phys. A **66** (1998) 277–282

15.53 T. R. Rodríguez, R. García: Tip motion in amplitude modulation (tapping-mode) atomic-force microscopy: Comparison between continuous and point-mass models, Appl. Phys. Lett. **80** (2002) 1646–1648

15.54 J. Tamayo, R. García: Relationship between phase shift and energy dissipation in tapping-mode scanning force microscopy, Appl. Phys. Lett. **73** (1998) 2926–2928

15.55 R. García, J. Tamayo, A. San Paulo: Phase contrast and surface energy hysteresis in tapping mode scanning force microsopy, Surf. Interface Anal. **27** (1999) 312–316

15.56 S. N. Magonov, V. B. Elings, M. H. Whangbo: Phase imaging and stiffness in tapping-mode atomic force microscopy, Surf. Sci. **375** (1997) L385–L391

15.57 J. P. Pickering, G. J. Vancso: Apparent contrast reversal in tapping mode atomic force microscope images on films of polystyrene-b-polyisoprene-b-polystyrene, Polymer Bull. **40** (1998) 549–554

15.58 X. Chen, S. L. McGurk, M. C. Davies, C. J. Roberts, K. M. Shakesheff, S. J. B. Tendler, P. M. Williams, J. Davies, A. C. Dwakes, A. Domb: Chemical and morphological analysis of surface enrichment in a biodegradable polymer blend by phase-detection imaging atomic force microscopy, Macromolecules **31** (1998) 2278–2283

15.59 A. Kühle, A. H. Sørensen, J. Bohr: Role of attractive forces in tapping tip force microscopy, J. Appl. Phys. **81** (1997) 6562–6569

15.60 A. Kühle, A. H. Sørensen, J. B. Zandbergen, J. Bohr: Contrast artifacts in tapping tip atomic force microscopy, Appl. Phys. A **66** (1998) 329–332

16. Molecular Recognition Force Microscopy

Atomic force microscopy (AFM), developed in the late eighties to explore atomic details on hard material surfaces, has evolved to an imaging method capable of achieving fine structural details on biological samples. Its particular advantage in biology is that the measurements can be carried out in aqueous and physiological environment, which opens the possibility to study the dynamics of biological processes in vivo. The additional potential of the AFM to measure ultra-low forces at high lateral resolution has paved the way for measuring inter- and intra-molecular forces of bio-molecules on the single molecule level. Molecular recognition studies using AFM open the possibility to detect specific ligand–receptor interaction forces and to observe molecular recognition of a single ligand–receptor pair. Applications include biotin–avidin, antibody–antigen, NTA nitrilotriacetate–hexahistidine 6, and cellular proteins, either isolated or in cell membranes.

The general strategy is to bind ligands to AFM tips and receptors to probe surfaces (or vice versa), respectively. In a force–distance cycle, the tip is first approached towards the surface whereupon a single receptor–ligand complex is formed, due to the specific ligand receptor recognition. During subsequent tip–surface retraction a temporarily increasing force is exerted to the ligand–receptor connection thus reducing its lifetime until the interaction bond breaks at a critical force (unbinding force). Such experiments allow for estimation of affinity, rate constants, and structural data of the binding pocket. Comparing them with values obtained from ensemble-average techniques and binding energies is of particular interest. The dependences of unbinding force on the rate of load increase exerted to the receptor–ligand bond reveal details of the molecular dynamics of the recognition process and energy landscapes. Similar experimental strategies were also used for studying intra-molecular force properties of polymers and unfolding–refolding kinetics of filamentous proteins. Recognition imaging, developed by combing dynamic force microscopy with force spectroscopy, allows for localization of receptor sites on surfaces with nanometer positional accuracy.

16.1 **Ligand Tip Chemistry** 476
16.2 **Fixation of Receptors to Probe Surfaces** .. 478
16.3 **Single-Molecule Recognition Force Detection** 479
16.4 **Principles of Molecular Recognition Force Spectroscopy** 482
16.5 **Recognition Force Spectroscopy: From Isolated Molecules to Biological Membranes** 484
  16.5.1 Forces, Energies, and Kinetic Rates. 484
  16.5.2 Complex Bonds and Energy Landscapes 486
  16.5.3 Live Cells and Membranes 489
16.6 **Recognition Imaging** 489
16.7 **Concluding Remarks** 491
References 492

Macromolecular interactions play a key role in cellular regulation and biological function. Molecular recognition is one of the most important regulatory elements, as it is often the initiating step in reaction pathways and cascades. Since the immune system has evolved recognition molecules that are both highly specific and versatile, antibody-antigen interaction is often used as a paradigm for molecular recognition. However, molecular recognition also plays fundamental roles in the regulation of gene expression, cellular metabolism, and drug design.

Molecular recognition studies emphasize specific biological interactions between receptors and their cog-

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

nitive ligands. Despite a growing literature on the structure and function of receptor-ligand complexes, it is still not possible to predict reaction kinetics or energetics for any given complex formation, even when the structures are known. Additional insights, in particular about the molecular dynamics within the complex during the association and dissociation process, are needed. The high-end strategy is to probe quantitatively the science that underlies a specific biological recognition in which the chemical structures can be defined at atomic resolution, and genetic or chemical means are available to vary the structure of the interacting partners.

Receptor-ligand complexes are usually formed by a few tens of parallel weak interactions of contacting chemical groups in complementary determining regions supported by framework residues providing structurally conserved scaffolding. Both the complementary determining regions and the framework have a considerable amount of plasticity and flexibility resulting in conformational changes upon association and dissociation (induced fit). In addition to what is known about structure, energies, and kinetic constants, information about conformational movements is required for the understanding of the recognition process. It is likely that insight into the temporal and spatial action of the many weak interactions, in particular the cooparativity of bond formation, is the key to understanding receptor-ligand recognition.

For this, experiments on the single-molecule level at time scales typical for receptor-ligand complex formation and dissociation appear to be required. The potential of the atomic force microscope (AFM) [16.1] to measure ultralow forces at high lateral resolution has paved the way for single-molecule recognition force microscopy studies. The particular advantage of AFM in biology is that the measurements can be carried out in aqueous and physiological environments, which opens the possibility for studying biological processes in vivo. The methodology for investigating the molecular dynamics of receptor-ligand interactions described in this chapter, *Molecular Recognition Force Microscopy* (MRFM) [16.2–4], was developed from scanning probe microscopy (SPM) [16.1]. A force is exerted on a receptor-ligand complex, and the dissociation process is followed over time. Dynamic aspects of recognition are addressed in force spectroscopy (FS) experiments, in which distinct force-time profiles are applied to give insight into the changes in conformations and states during receptor-ligand dissociation. It will be shown that MRFM is a versatile tool to explore kinetic and structural details of receptor-ligand recognition.

16.1 Ligand Tip Chemistry

In MRFM experiments, the binding of ligands on AFM tips to surface-bound receptors (or vice versa) is studied by applying a force to the receptor-ligand complex that reduces its lifetime until the bond breaks at a measurable unbinding force. This requires a careful AFM tip sensor design, including tight attachment of the ligands to the tip surface. In the first pioneering demonstrations of single-molecule recognition force measurements [16.2, 3], strong physical adsorption of bovine serum albumin (BSA) was used to directly coat the tip [16.3] or, alternatively, a glass bead glued to it [16.2]. This physisorbed protein layer may then serve as a functional matrix for the biochemical modification with chemically active ligands (Fig. 16.1). In spite of the large number of probe molecules on the tip ($10^3-10^4/\mu m^2$), the low fraction of properly oriented molecules, or internal blocks of most reactive sites (see Fig. 16.1), allowed the measurement of single receptor-ligand unbinding forces. Nevertheless, parallel breakage of multiple bonds was predominately observed with this configuration.

For measuring interactions between isolated receptor-ligand pairs, strictly defined conditions need to be fulfilled. Covalently coupling ligands to gold-coated tip surfaces via freely accessible SH-groups guarantees a sufficiently stable attachment, because these bonds are about ten times stronger than typical ligand-receptor interactions [16.5]. This chemistry has been used to detect the forces between complementary DNA strands [16.6] and single nucleotides [16.7]. Self-assembled monolayers of dithio-bis(succinimidylundecanoate) were formed to enable covalent coupling of biomolecules via amines [16.8], and were used to study the binding strength between cell adhesion proteoglycans [16.9] and between biotin-directed IgG antibodies and biotin [16.10]. A vectorial orientation of Fab molecules on gold tips was achieved by a firsthand site-directed chemical binding via their SH-groups [16.11], without the need of additional linkers. For this, antibodies were



Fig. 16.1 Avidin-functionalized AFM tip. A dense layer of biotinylated BSA was adsorbed to the tip and subsequently saturated with avidin. The biotinylated agarose bead opposing the tip also contained a high surface density of reactive sites, which were, therefore, partly blocked with avidin to achieve single-molecule binding events (after [16.3])

digested with papain and subsequently purified to generate Fab fragments with freely accessible SH-groups in the hinge region.

Gold surfaces provide a unique and selective affinity for thiols, although the adhesion strength of the formed bond is weaker than that of other covalent bonds [16.5]. Since all commercially available AFM tips are etched of silicon nitride or silicon oxide material, deposition of a gold layer onto the tip surface is required prior to using this chemistry. Therefore, designing a sensor with covalent attachments of the biomolecules to the silicon surface may be more straightforward. Amine-functionalization procedures, a strategy widely used in surface bio-chemistry, were applied using ethanolamine [16.4, 12] and various silanization methods [16.13–15] as a first step in thoroughly developed surface anchoring protocols suitable for single molecule experiments. Since the amine density achieved in these procedures often determines the number of ligands on the tip that can specifically bind to the receptors on the surface, it has to be sufficiently low to guarantee single molecule detection [16.4, 12]. One molecule per tip apex ($\sim 5-20$ nm) corresponds to a macroscopic density of about 500 molecules per μm^2. A most striking example of a single ligand molecule tip was realized by gluing a single nanotube to the cantilever, thus minimizing the contact between tip and surface with a chemically well-defined and extremely small tip apex [16.16]. The ligand molecule was reacted to an activated chemical site at the open end of the nanotube.

In a number of laboratories, a distensible and flexible linker was used to space the ligand molecule from the tip surface (e.g., [16.4, 14]) (Fig. 16.2). At a given low number of spacer molecules per tip, the ligand can freely orient and diffuse within a certain volume provided by the length of the tether to achieve unconstrained binding to its receptor. The unbinding process occurs with little torque, and the ligand molecule escapes the danger of being squeezed between the tip and the surface. It also opens the possibility of site-directed coupling for a defined orientation of the ligand relative to the receptor at receptor-ligand unbinding. As a crosslinking element, poly(ethylene glycol) (PEG), a water soluble, nontoxic polymer with a wide range of applications in surface technology and clinical research, was often used [16.17]. PEG is known to prevent surface adsorption of proteins and lipid structures and therefore appears ideally suited for this purpose. Gluteraldehyde [16.13] and DNA [16.6] were also successfully applied in recognition force studies. Crosslinker lengths, ideally arriving at a good compromise between high tip molecule mobility and narrow lateral resolution of the target recognition site, varied from 2 to 100 nm.

For coupling to the tip surface and to the ligands, respectively, the crosslinker is mostly equipped with two different functional ends, e.g., an N-hydroxy-



Fig. 16.2 Linkage of ligands to AFM tips. Ligands were covalently coupled to AFM tips via a heterobifunctional polyethylene glycol (PEG) derivative of 8 nm length. Silicon tips were first functionalized with ethanolamine ($NH_2-C_2H_4OH \cdot HCl$). Then, the NHS (N-hydroxysuccinimide) end of the PEG linker was covalently bound to amines on the tip surface before ligands were attached to the PDP (Pyridoyldithiopropionate) end via a free thiol or cysteine

succinimidyl (NHS) residue on the one end is reactive to amines on the tip and a 2-pyridyldithiopropionyl (PDP) [16.18] or a vinyl sulfon [16.19] residue on the other end, can be covalently bound to thiols of ligands (Fig. 16.2). This sulfur chemistry is highly advantageous, since it is very reactive and renders site-directed coupling possible. However, free thiols are hardly available on native ligands and must, therefore, be generated.

Different strategies were used to achieve this goal. Lysins of protein-ligands were derived from the short heterobifunctional linker N-succinnimidyl-3-(S-acethylthio)propionate (SATP) and subsequent deprotection with NH_2OH led to reactive SH groups [16.18]. Since it is very delicate to react distinct lysins with this method, the coupling to the crosslinker is often not specifically site directed. Several protocols are commercially available (Pierce, Rockford, IL) to generate active antibody fragments with free cysteines. Half-antibodies are produced by cleaving the two disulfides in the central region of the heavy chain using 2-mercaptoethylamine HCl [16.20] and Fab fragments are generated from digestion using papain [16.11]. The most elegant methods are to mutate a cysteine into the primary sequence of proteins and to append a thiol to the end of synthesized DNA strands [16.6], because they allow for a defined, sequence-specific coupling of the ligand to the crosslinker.

A nice alternative for a most common, strong but noncovalent site-directed anchor on the spacer has been introduced recently. The binding strength of the NTA (nitrilotriacetate) - His_6 (histidine 6) system, routinely used on chromatographic and biosensor matrices for the binding of recombinant proteins to which a His_6 tag is appended to the primary sequence, was found to be significantly larger than typical values of other ligand-receptor systems [16.21–23]. Therefore, a crosslinker containing an NTA residue is ideally suited for coupling a recombinant ligand carrying a His_6 in its sequence to the AFM tip. This general, site-directed, and oriented coupling strategy also allows rigid and fast control of the specificity of ligand-receptor recognition by using Ni^{++} as a molecular switch of the NTA-His_6 bond.

16.2 Fixation of Receptors to Probe Surfaces

For the recognition by ligands on the AFM tip, receptors should be tightly attached to probe surfaces. Loose receptor fixation could lead to a pull-off of the receptor from the surface by the ligand on the tip, which would consequently block ligand-receptor recognition and obscure the recognition force experiments.

Freshly cleaved muscovite mica is a perfectly pure and atomically flat surface and, therefore, ideally suited for MRFM studies. Moreover, the strong negative charge of mica accomplishes very tight electrostatic binding of certain types of biomolecules. Some receptor proteins such as lysozyme [16.20] or avidin [16.24] strongly adhere to mica due to the strong positive charge of these highly basic proteins at $pH < 8$. In this case, it is safe to purely adsorb the receptors from the solution, since the unspecific attachment to the surface is sufficiently strong for recognition force experiments. Nucleic acids are firmly bound to mica via Zn^{2+}, Ni^{2+}, or Mg^{2+} bridges [16.25]. Electrostatic interaction has also been used to adsorb the strongly acidic sarcoplasmic domain of the Ca^{2+} release channel via Ca^{2+}-bridges to probe the cytoplasmic surface [16.26]. Similarly, protein crystals and bacterial layers have been deposited onto mica in defined orientations with an appropriate choice of buffer conditions [16.27, 28].

In many cases, however, one cannot rely on electrostatic binding toward surfaces. Ideally, water-soluble receptors like globular antigenic proteins or extracellular protein chimeras are then anchored covalently. When glass, silicon, or mica is used as the probe surface, exactly the same surface chemistry described for the silicon AFM tips applies (see above). The number of reactive SiOH groups of the relatively chemically inert mica can be optionally increased by water plasma treatment [16.29]. Frequently, crosslinkers were also used on probe surfaces to provide the receptors with motional freedom, too [16.4]. Protein binding to photo-crosslinkers thereby enables rigid temporal control of the reaction [16.30].

A major limitation of the silicon chemistry is the impossibility of reaching a high surface density of functional sites ($< 1{,}000/\mu m^2$). By comparison, a monolayer of streptavidin would consist of 60,000 molecules per μm^2 and a phospholipid monolayer would consist of 1.7×10^6 molecules per μm^2. The latter density is also achieved by chemisorption of alkanethiols to gold. Tightly bound, ordered, self-assembled monolayers are formed on ultraflat gold surfaces and display excellent probes for AFM [16.10]. Alkanethiols can carry reactive groups at the free end that allow for covalent attachment of biomolecules [16.10, 31] (Fig. 16.3).

A recently developed anchoring strategy to gold uses dithio-phospholipids consisting of a propyldithio group at their hydrophobic end and either a phosphocholine head group (as host lipid) or a phosphethanolamine head group [16.32]. The latter head group is chemically reactive and was derived from a long chain biotin for the molecular recognition of streptavidin molecules in an initial study [16.32]. This phospholipid layer closely mimicks a cell surface and has been optimized by nature to afford little nonspecific adsorption. Additionally, it can be spread as an insoluble monolayer at an air-water interface. Thereby, the ratio of functionalized thio-lipids in host thio-lipids accurately defines the surface density of bio-reactive sites in the monolayer. Subsequent transfer onto gold substrates leads to covalent and, therefore, tight attachment of the monolayer, and thus it is suited for recognition force studies.

Immobilization of cells mainly depends on the type of cell. Cells with adherent growth are readily usable for MRFM, whereas cells that grow in solution without contact to a surface have to be adsorbed. Various protocols for a tight cell anchoring are available. The easiest way is to grow the cells directly on glass or other surfaces in their cell culture medium [16.33]. Various adhesive coatings like Cell-Tak [16.34], gelatin, and poly-lysin increase the strength of adhesion and/or display appropriate surfaces to immobilize spherical cells. Other hydrophilic surfaces like gold or carbon are suitable matrices as well [16.35]. Covalent binding of cells to surfaces can be accomplished by using PEG crosslinkers as the one described for the tip chemistry, since they react with free thiols on the cell surface [16.34]. Alternatively, PEG crosslinkers carrying a fatty acid penetrate into the interior of the cell membrane, which guarantees a sufficiently strong fixation without interference with membrane proteins [16.34].



Fig. 16.3 AFM image of hisRNAP molecules specifically bound to nickel-NTA domains on a functionalized gold surface. Alkanethiols terminated with ethylene glycol groups to resist unspecific protein adsorption served as host matrices and were doped with 10% nickel-NTA alkenthiols. The sample was prepared to achieve full monolayer coverage. Ten individual hisRNAP molecules can be clearly seen bound to the surface. The more abundant, smaller, lower features are NTA islands with no bound molecules. The underlying morphology of the gold can also be distinguished (after [16.31])

16.3 Single-Molecule Recognition Force Detection

Quantification of recognition forces goes back to ensemble techniques such as shear flow detachment measurements (SFD) [16.36] and the surface force apparatus (SFA) [16.37]. In SFD, receptors are fixed to a surface to which beads or cells containing ligands attach via their specific bonds. A fluid shear stress is applied to the surface-bound particles by a flow of given velocity that disrupts the ligand-receptor-bonds at a critical force. However, the unbinding force per single bond can only be estimated, because the calculation of the net force on the particle is complicated by the stress distribution and the number of bonds per particle is assumed from the geometry of the contact area.

SFA directly measures the vertical forces between two macroscopic surfaces containing receptors and ligands, respectively, using a spring as a force prober and interferometry for detection. Although SFA does not have a great sensitivity in measuring absolute forces and requires assumptions to be made for down-scaling to



Fig. 16.4 Experimental setup of the biomembrane force probe (BFP). The spring in the BFP is a pressurized membrane capsule. Its spring constant is set by the membrane tension, which is controlled by micropipette suction. The BFP tip, a glass microbead of 1–2 µm diameter, was chemically glued to the membrane. Operated on the stage of an inverted microscope, the BFP (on the *left*) was kept stationary and the microbead test surface (on the *right*) was translated to/from contact with the BFP tip by precision piezo control (after [16.38])

single bonds, its z-resolution is highly accurate (better than 1 Å) over a long range. Adhesion and compression forces, as well as rapid transient effects can be followed in real time.

The bio force probe (BFP) technique (for a recent paper see [16.38]) (Fig. 16.4) uses soft membranes as the force transducer, rather than a mechanical spring. A single cell or giant vesicle is held by suction at the tip of a glass micropipette and its spring constants are adjusted by the aspiration pressure and can be varied over several orders of magnitude. Interaction forces with opposing cells, vesicles, or functionalized beads are obtained from the micromechanical analysis of the deformations of the membranes and/or via interference contrast microscopy. A force range from 0.1 pN to 1 nN is accessible with high force sensitivity down to the single-bond level.

In optical tweezers (OT) small particles are manipulated by optical traps [16.39]. Three-dimensional light intensity gradients of a focused laser beam are used to pull or push the particles against another one. Particle displacements can be followed with nanometer resolution. Movements of single molecular motors [16.40] and force-extension profiles of single extensible molecules such as titin [16.41] and DNA [16.42] were measured. Defined, force-controlled twisting of DNA using rotating, magnetically manipulated particles gave even further insights into DNA viscoelastic properties [16.43].

The atomic force microscope (AFM) is the force measuring method with the smallest-sized force sensor and therefore achieves the highest lateral resolution. Radii of commercially available AFM tips vary between 2 and 50 nm. In contrast, the sensing particles in SFD, BFP, and OT are in the 1 to 10 µm range, and the surfaces used in SFA exceed millimeter extensions. The small apex of the AFM tip allows for the probing of single biomolecules. Originally designed to explore the topography of rigorous surfaces with atomic resolution [16.1] in area scans, the AFM was used in biology to image the secondary structures of nucleotides [16.25], as well as polar lipid head groups and subunits of proteins embedded in membranes in liquid environments [16.27, 28].

The additional potential of the AFM to detect ultralow forces has been successfully applied to the detection of interaction forces of single receptor-ligand pairs [16.2–4]. These forces are measured in so called force-distance cycles using a ligand-carrying tip mounted to a cantilever and a probe surface with receptors firmly attached. A force-distance cycle, where a distensible tether was used to couple ligands to tips and receptors to surfaces is shown in Fig. 16.5 (from [16.4]). At a fixed lateral position the tip approaches the probe surface and is subsequently retracted, and the cantilever deflection Δx is measured in dependence of the tip-surface separation Δz. Cantilever deflections are detected by reflecting a laser beam off the back of the cantilever onto a split photodiode. Bending of the cantilever causes a change in the position where the laser beam strikes the photodiode and, therefore, a change in the output voltage of the photodiode.

The force F acting on the cantilever directly relates to the cantilever deflection Δx according to Hook's law $F = k\Delta x$, where k is the cantilever spring constant. During tip-surface approach (trace, and line 1 to 5), the cantilever deflection remains zero far away from the surface (1 to 4), because there is no detectable tip-surface interaction. Upon tip-surface contact (4), the cantilever bends upward (4 to 5), consistent with a repulsive force that increases linearly with z the harder the tip is pushed into the surface. Subsequent tip-surface retraction (retrace, 5 to 7) first leads to relaxation of the cantilever bending and the repulsive force drops back down to zero (5 to 4).

When ligand-receptor binding has occurred, the cantilever bends downward upon retraction, reflecting an attractive force (retrace, 4 to 7) that increases with increasing tip-surface separation. Since the cognitive molecules were tethered to the surfaces via flexible and distensible crosslinkers, the shape of the attractive force-distance profile is, in contrast to the repulsive force-distance profile of the contact region



Fig. 16.5 Single-molecule recognition event detected with AFM. Raw data from a force-distance cycle with 100 nm z-amplitude at 1 Hz sweep frequency measured in PBS. Binding of the antibody on the tip to the antigen on the surface during approach (trace points 1 to 5) physically connects tip to probe. This causes a distinct force signal of distinct shape (points 6 to 7) during tip retraction, reflecting extension of the distensible crosslinker-antibody-antigen connection. The force increases until unbinding occurs at an unbinding force of 268 pN (points 7 to 2). (After [16.4])

(4 to 7), nonlinear. Its shape is determined by the elastic properties of the flexible PEG crosslinker [16.17,44] and shows parabolic-like characteristics, which reflects the increase of the spring constant of the crosslinker during extension. The force attractive profile contains the features of a single-molecule recognition event.

The physical connection between the tip and surface sustains the increasing force until the ligand-receptor complex dissociates at a certain critical force (unbinding force, 7), and the cantilever finally jumps back to the resting position (7 to 2). The quantitative force measure of the unbinding force f of a single receptor-ligand pair is directly given by the force at the moment of unbinding (7).

If the ligand on the tip does not form a specific bond with one of the receptors on the probe surface, the recognition event is missing and retrace looks like trace. Also, the specificity of the ligand-receptor binding is usually demonstrated in block experiments. Free ligands are injected in solution so as to block receptor sites on the surfaces. As a further consequence, recognition signals completely disappear, because the receptor sites on the surface are blocked by the ligand of the solution and, thus, prevent recognition by the ligand on the tip.

The force resolution of the AFM is limited by the thermal noise of the cantilever that is determined by its spring constant. According to the equipartition theorem, the cantilever has on average a thermal energy of $0.5\,k_{\mathrm{B}}T$, therefore, $0.5\,k\Delta z^2 = 0.5\,k_{\mathrm{B}}T$, where k_{B} is Boltzmann's constant and T the absolute temperature. Since $F = k\Delta x$, the force sensitivity is given by $\Delta F = (k_{\mathrm{B}}Tk)^{1/2}$ and is, therefore, better the softer the cantilever. The smallest force that can be detected with commercially available cantilevers is in the few picoNewton range. For thinner levers with low spring constants, the force resolution decreases by an order of magnitude [16.45]. Due to their smaller mass, they have a higher resonance frequency (30–100 kHz in liquid). When deflection is recorded at a typical bandwidth of 10 kHz, only a fraction of the thermal noise is included and fast movements of the tip can still be detected [16.45]. An alternative route for improving the force resolution was found by electronically increasing the apparent damping constant, which results in the reduction of thermal noise [16.46].

Besides the detection of intermolecular forces between receptors and ligands, the AFM also shows great potential in measuring intramolecular force profiles of single molecules. The molecule is clamped in between the tip and the probe surface and its visco-elastic properties are studied in force-distance cycles. The detailed force extension profile of the recognition event shown in Fig. 16.5 contains, for example, the elastic features of the crosslinker (PEG in this particular case) [16.44] with which the ligand is tethered to the tip of the AFM.

16.4 Principles of Molecular Recognition Force Spectroscopy

Specific interactions underlying molecular recognition are a distinct class of highly complementary, noncovalent bonds between biological macromolecules composed typically of a few tens of weak interactions such as electrostatic, polar, van der Waals, hydrophobic, and hydrogen bonds. The energy of each single bond is just slightly higher than the thermal energy k_BT. Due to the power law dependence of each weak interaction potential and the directionality of the hydrogen bonds, the attractive forces between the receptors and their cognitive ligands are extremely short-range. Therefore, a close geometrical and chemical fit within the binding pocket is a prerequisite for molecular recognition.

Conformational flexibility of at least one of the two binding partners is required for their structural adaptation. The weak interaction bonds are believed to be formed in a spatially and temporarily correlated fashion, thus creating a strong and highly specific molecular interaction. Recognition binding sites are structurally and chemically unique and selective for distinct receptor/ligand combinations. The overall affinity or binding energy of a receptor-ligand bond of a few tens of k_BT is typically sufficient to effect chemical or physical changes of the binding partners, which often initiate biochemical reaction cascades or cellular metabolic pathways.

The binding energy E_B, given by the free energy difference between the bound and the free state, is the common parameter to describe the strength of a bond and can be determined in ensemble average calorimetric experiments. E_B determines the ratio of bound complexes, [RL], to the product of free reactants, [R] [L], at equilibrium in solution and is related to the equilibrium dissociation constant K_D, the affinity parameter, according to $E_B\alpha - \log(K_D)$. At thermodynamic equilibrium, the number of complexes that form per unit of time, k_{on} [R] [L], equals the number of complexes that dissociate per time unit, k_{off} [RL]. The empirical kinetic rate constants, on-rate k_{on} and off-rate k_{off}, are related to the equilibrium dissociation constant K_D through $K_D = k_{off}/k_{on}$.

In order to get an estimate for the interaction forces f from binding energies E_B, the dimension of the binding pocket may be used as the characteristic length dimension l; thus $f = E_B/l$. Typical values of $E_B = 20\,k_BT$ and $l = 0.5\,\text{nm}$ yields $f \sim 170\,\text{pN}$ as an order of magnitude feeling for the strength of a single receptor-ligand bond. Classical mechanics describes the force required to separate interacting molecules as the gradient in energy along the interaction potential. The complexed molecules would, therefore, dissociate when force exceeds the steepest gradient in energy. However, activation barriers, temperature, time scales, and the detailed characteristics of the energy landscape, all known to be essential for the understanding of receptor-ligand dissociation, are not considered in this purely mechanical picture.

Ligand-receptor binding is generally a reversible reaction. Viewed on the single-molecule level, the average lifetime of a ligand-receptor bond, $\tau(0)$, is given by the inverse of the kinetic off-rate, k_{off}, so $\tau(0) = k_{off}^{-1}$. Therefore, ligands will dissociate from receptors without any force applied to the bond at times larger than $\tau(0)$ (covering a range from milliseconds to days for different receptor-ligand combinations). In contrast, if molecules are pulled faster than $\tau(0)$, the bond will resist and require a force for detachment. The size of the unbinding force may vary over more than one order of magnitude, and even exceed the adiabatic limit given by the steepest energy gradient of the interaction potential if bond breakage occurs faster than diffusive relaxation (nanosecond range for biomolecules in viscous aqueous medium) and friction effects become dominant [16.47]. Therefore, unbinding forces do not resemble unitary values, and the dynamics of the experiment defines the physics underlying the unbinding process.

At the millisecond to second time scale of AFM experiments, thermal impulses govern the unbinding process. In the thermal activation model, the lifetime of a complex in solution is described by a Boltzmann ansatz, $\tau(0) = \tau_{osc} \exp(E_b/k_BT)$ [16.48], where τ_{osc} is the inverse of the natural oscillation frequency and E_b the energy barrier for dissociation. Hence, due to the thermal energy there is a finite probability of overcoming the energy barrier E_b, which leads to the separation of the receptor-ligand complex. The mean complex lifetime in solution is, therefore, determined by the ratio of E_b over the thermal energy.

A force acting on a binding complex deforms the interaction energy landscape and lowers the activation energy barrier, very similar to the mode of operation of an enzyme (Fig. 16.6). Thus the input of thermal energy by forces acting in this time regime reduces the bond lifetime. The lifetime $\tau(f)$ of a bond loaded with a constant force f is given as $\tau(f) = \tau_{osc} \exp[(E_b - x_\beta f)/k_BT]$ [16.48], x_β being interpreted as the distance of the energy barrier E_b from the energy minimum along the direction of the



Fig. 16.6 Dissociation over a single sharp energy barrier. Under a constant force, the barrier is linearly decreased by the applied force F, giving rise to a characteristic length scale x that is interpreted as the distance of the energy barrier from the energy minimum along the projection of the force (after [16.50])

applied force. In this model, the energy barrier decreases linearly with the force applied. A detailed physical basis for Bell's theory has been derived in [16.49], where the strength of weak non-covalent bonds was studied in liquid using Kramer's theory for reaction kinetics in liquids under the influence of force.

The lifetime $\tau(f)$ under constant force f compares to the lifetime at zero force, $\tau(0)$, according to $\tau(f) = \tau(0)\exp(-x_\beta f/k_\mathrm{B}T)$ [16.4] for a single sharp energy barrier for which a mono-exponential dependence is characteristic. Using AFM, receptor-ligand unbinding is commonly measured in force-distance cycles (cf. previous chapter), during which the applied force to the complex does not remain constant. Rather, it increases in a complex fashion at a nonlinear rate determined by the pulling velocity, the spring constant of the cantilever, and the force-distance profile of the complexed biomolecules. The main contribution of the thermal activation, however, comes from the part of the force curve, which is close to unbinding. Therefore, an effective force increase or loading rate r can be deduced from $r = \mathrm{d}f/\mathrm{d}t =$ pulling velocity times effective spring constant at the end of the force curve just before unbinding occurs. The approximation of a constant loading rate using force-distance cycles with AFM is sound with a properly defined effective loading rate [16.51].

The dependence of the unbinding force on a linear loading rate in the thermally activated regime was first derived in [16.49] and further described in [16.50]. Force-induced dissociation of receptor-ligand complexes using AFM or BFP can be regarded as an irreversible process, because the two binding partners are further separated after dissociation has occurred. Therefore, rebinding and back-reactions are negligible. The unbinding process itself is of a stochastic nature, and the likelihood of bond survival is expressed in the master equation as time-dependent probability $N(t)$ to be in the bound state under a linearly increasing force $f = rt$, thus $\mathrm{d}N(t) = -k_\mathrm{off}(rt)N(t)$ [16.50].

Rewriting Bell's formula using $\tau(f) = k_\mathrm{off}^{-1}(f)$ relates the kinetic off-rate at a given force f, $k_\mathrm{off}(f)$, to the off-rate at zero force, $k_\mathrm{off}(0)$: $k_\mathrm{off}(f) = k_\mathrm{off}(0)\exp(l_\mathrm{r} f/k_\mathrm{B}T)$. The master equation combined with Bell's formula results in a spectrum of Gaussian-like distributions of unbinding forces (frequency of occurrence versus force) parameterized by the loading rate r [16.50]. Thus the maximum of each force distribution, $f^*(r)$, reflects the most probable force of unbinding for the respective loading rate r. f^* is related to r through $f^* = f_\beta \log_\mathrm{e}(r k_\mathrm{off}^{-1}/f_\beta)$, where the slope is governed by f_β, a force scale set by the ratio of the thermal energy $k_\mathrm{B}T$ to the length scale x_β, which marks the thermally averaged position of the energy barrier along the direction of the force [16.49, 50]. Apparently, the unbinding force f^* scales linearly with the logarithm of the loading rate. For a single barrier, this would give rise to a simple, linear dependence of the force versus log loading rate. In cases where more barriers are involved along the escape path, the curve will follow a sequence of linear regimes, each of which marks a particular barrier [16.38]. Hence, transition from one regime to the other is associated with an abrupt change of slope determined by the characteristic barrier length scale.

In force spectroscopy experiments, the dynamics of pulling on specific receptor-ligand bonds is varied, which leads to detailed structural and kinetic information of the bond breakage, as discussed above and shown in the following chapter on explicit examples. Length scales of energy barriers are obtained from the slope of the spectroscopy plot (force versus loading rate) and their relative heights may be gained from the force shifts [16.38]. Extrapolation to zero forces yields the kinetic off-rate constant for the dissociation of the complex in solution [16.52].

16.5 Recognition Force Spectroscopy: From Isolated Molecules to Biological Membranes

In the early pioneering AFM studies receptor-ligand bond strengths were only measured at one loading rate. Therefore, only a single point in the spectrum of forces, that depend on the dynamics of the experiment, was determined. Avidin–biotin is often regarded as the prototype of receptor-ligand interaction due to its enormously high affinity ($K_D = 10^{-13}$ M) and long bond lifetime ($\tau(0) = 80$ days). Hence, it may not be too surprising that the first realizations of single-molecule recognition force detections were made with biotin and its cognitive receptors, streptavidin [16.2], the succinilated form of avidin, and avidin [16.3]. Unbinding forces of 250–300 pN and 160 pN were found for streptavidin and avidin, respectively. It was also shown [16.53] that the forces vary with the spring constant of the cantilever using the same pulling velocity, which is consistent with the loading rate dependency of the unbinding force discussed above. The recognition forces of various biotin analogs with avidin and streptavidin [16.53], as well as with site-directed streptavidin mutants [16.54] were related to their energies and found to be correlated with the equilibrium binding enthalpy [16.53] and the enthalpic activation barrier [16.54] but independent of free energy parameters. It was suggested that internal energies of the bond breakage, rather than entropic changes were probed by the force measurements [16.54].

16.5.1 Forces, Energies, and Kinetic Rates

In first measurements of inter- and intramolecular forces of the DNA double helix [16.6], complementary single-strand DNA oligonucleotides covalently attached to the AFM tip and the probe surface, respectively, were probed. The multimodal force distributions obtained (three distinct, separated force peaks) were associated with interchain interactions of single pairs of 12, 16, and 20 base sequence length. A long strain single-strand DNA with cohesive ends was sandwiched in between tip and substrate and its intramolecular force pattern revealed elastic properties comparable to polymeric molecules [16.6]. Single molecule interactions between all possible 16 combinations of the four bases were also studied [16.7] and yielded specific binding only when complemetary bases were present on the tip and the probe surface, indicating that AFM is capable of following Watson-Crick base pairing.

Anibody-antigen interactions are of key importance for the function of the immune system. Their affinities are known to vary over orders of magnitudes. For single-molecule recognition AFM studies, the molecules were surface-coupled via flexible and distensible crosslinkers [16.4, 10, 13, 14] to provide them with sufficient motional freedom, so that problems of misorientation and steric hindrance that can obscure specific recognition are avoided. In [16.4, 12], the tips were functionalized with a low antibody density, so that on the average only a single antibody on the tip end could access the antigens on the surface. Hence, isolated single molecular antibody-antigen complexes could be examined. It was observed that the interaction sites of the two Fab fragments of the antibody (the antibody consists of two antigen-active Fab-fragments and one Fc-portion) are able to bind simultaneously and independently with equal binding probability. Single antibody-antigen binding events were also studied with tip-bound antigens [16.10] using an antibody biosensor probe surface [16.13], or single chain antibody-fragments attached to gold via freely accessible sulfhidryl groups [16.14]. In the latter study, the unbinding forces of two mutant single-chain antibodies, varying by an order of magnitude in their affinity, were compared. The mutant of ten times lower affinity (consistent with 12% lower free energy due to the logarithmic dependence of the affinity on free energy) showed 20% lower unbinding force.

All these studies describe detection of intermolecular forces between single receptors and their cognitive ligands. However, the AFM can also be used to characterize single-molecule intramolecular forces, e.g., interactions responsible for stabilizing the conformations and tertiary structures of polymers and proteins. The force-extension profile (cf. also stretching of PEG in Fig. 16.5) of polysaccharide dextran revealed multiple elastic regimes dominated by entropic effects, internal bond angle twistings, and conformational changes [16.55, 56]. The complex quantities of elastic and viscous force contributions upon stretching a single dextran molecule were resolved by resonant energy tracking using dynamic force spectroscopy [16.57]. Titin, a fibrillose muscle protein, contains a large number of repetitive IgG domains that shows a characteristic sawtooth pattern in the force profile, reflecting their sequential unfolding (Fig. 16.7) [16.58]. Unfolding and refolding kinetics and energetics of proteins



Fig. 16.7 Force extension profile of a single titin molecule. The periodic sawtooth-like pattern reflects domain unfolding in the peptide chain consistent with its modular construction and can be explained as a stepwise increase of the molecule's length upon each unfolding event (after [16.58])

were studied in pull-hold-release cycles [16.59] by carefully handling the molecule between tip and surface. These studies yield crucial information on the relation between structure and function of single molecules.

Besides the investigation of forces, single-molecule recognition force microscopy studies allow for the estimation of association and dissociation rates [16.4, 12, 22, 52, 60, 61], energies [16.38], and structural parameters of the binding pocket [16.4, 12, 15, 60, 61]. For single molecule studies, quantification of the on-rate constant k_{on} for the association of the ligand on the tip to a receptor on the surface requires determination of the interaction time $t_{0.5}$ needed for half-maximal probability of binding. This value is obtained from an experiment in which the encounter duration of the ligand-coated tip on the receptor-containing surface is varied until a range of the unbinding activity from zero to saturation is achieved [16.60]. With the knowledge of the effective ligand concentration c_{eff} on the tip available for receptor interaction, k_{on} is given by $k_{\mathrm{on}} = t_{0.5}^{-1} c_{\mathrm{eff}}^{-1}$. The effective concentration c_{eff} is described by the effective volume V_{eff} the tip-tethered ligand diffuses about the tip, which yields $c_{\mathrm{eff}} = N_{\mathrm{A}}^{-1} V_{\mathrm{eff}}^{-1}$, where N_{A} is the Avogadro's number. V_{eff} is essentially a half-sphere with a radius of the effective tether length, and the kinetic on-rate can, therefore, be calculated from $k_{\mathrm{on}} = t_{0.5}^{-1} N_{\mathrm{A}} 2\pi/3r^3$. However, since k_{on} critically depends on the tether length r, only order of magnitude estimates are gained [16.60].

Additional information about the unbinding process is contained in the unbinding force distributions. Not only the maximum f^*, but also its intrinsic width σ increases with increasing loading rate [16.22, 38]. Apparently, at slower loading rates the systems adjust closer to equilibrium, which leads to smaller values of both the force f^* and its variation σ. This is another indication that dynamics is an important issue when studying recognition forces. An effective lifetime $\tau(f)$ of the bond under an applied force f was estimated by the time the cantilever spends in the force window spanned by the standard deviation σ of the f distribution [16.4]. The time the force increases from $f^* - \sigma$ to $f^* + \sigma$ is thus given by $\tau(f) \approx 2\sigma/\mathrm{d}f/\mathrm{d}t$ [16.4]. In an example of the Ni^{2+}-chelating ligand/receptor interaction nitrotrilacetate/hexa-histidin [16.22], the lifetime $\tau(f)$ decreased with increasing pulling force f from 17 ms at 150 pN to 2.5 ms at 194 pN. The data were fitted with Bell's formula, confirming the theoretically predicted exponential lifetime-force relation for the reduction of the lifetime $\tau(f)$ by the applied force f and, thus yielding a lifetime at zero force, $\tau_0 = 15$ s. Direct measurements of lifetimes are only possible by using a force clamp, where a constant adjustable force is applied to the complex via a feedback loop and the time duration of bond survival is detected. This configuration has been developed recently to study the force dependence of the unfolding probability of the filament muscle protein titin [16.62].

Theory predicts (cf. previous chapter) that the unbinding force of specific and reversible ligand-receptor bonds is dependent on the rate of the increasing force [16.47, 49, 63] during force-distance cycles. Indeed, in experiments unbinding forces were found to assume not a unitary value, but rather were dependent on both the pulling velocity [16.52, 60] and the cantilever spring constant [16.2]. The theoretical findings were confirmed by experimental studies and revealed a logarithmic dependence of the unbinding force on the loading rate [16.15, 22, 38, 52, 60, 61], consistent with the exponential lifetime-force relation described above. On a half-logarithmic plot, a single linear slope is characteristic for a single energy barrier probed in the thermally activated regime [16.38]. The same relation was also found for unfolding forces of proteins [16.55]. The slope of the force spectroscopy curve contains the length scale of the energy barrier, which may be connected to the length dimension of the interaction binding pocket [16.60]. The kinetic off-rate k_{off} at zero force is gained from the extrapolation to zero force [16.52, 60]. Combining k_{off} with k_{on} leads to a value for the equilibrium dissociation constant K_{D}, according to $K_{\mathrm{D}} = k_{\mathrm{off}}/k_{\mathrm{on}}$.

A simple correlation between unbinding force and solution kinetics was found for nine different single-chain Fv fragments constructed from point mutations of three unrelated anti-fluorescein antibodies [16.61]. These molecules provide a good model system because they are monovalent and follow a 1:1 binding model without allosteric effects, and the ligand (fluoerscein) is inert and rigid. For each mutant, the affinity K_{D}, the kinetic rate constants k_{on} and k_{off}, and the temperature dependence of k_{off} yielding the activation barrier E_{b}, were determined in solution. In a series of single-molecule AFM recognition events, the loading rate (r) dependence of the unbinding forces (f) was measured. The maxima of the force distributions f^* scaled linearly with $\log r$. Therefore, unbinding was dictated by a single energy barrier along the reaction path (Fig. 16.8). Since the measured unbinding forces of all mutants precisely correlated with k_{off}, the unbinding path followed and the transition state crossed cannot be too dissimilar in spontaneous and forced unbinding. Interestingly, the distance of the energy barrier along the unbinding pathway determined from the force spectroscopy curve was found to be proportional to the barrier height and, thus, most likely includes elastic stretching of the antibody construct during the unbinding process.

16.5.2 Complex Bonds and Energy Landscapes

More complex force spectra were found from unbinding force measurements between complementary DNA strands of different lengths [16.15]. DNA duplexes with 10, 20, and 30 base pairs, were investigated to reveal unbinding forces from 20 to 50 pN of single duplexes, depending on the loading rate and sequence length. The unbinding force of the respective duplexes scaled



Fig. 16.8 Loading rate dependence of the unbinding force dependence of two anti-fluoresceins. For both FITC-E2 w.t. and 4D5-Flu, a strictly mono-logarithmic dependence was found in the range accessed, indicating that only a single energy barrier was probed. The same energy barrier dominates dissociation without forces applied, because extrapolation to zero force matches kinetic off-rates determined in solution (indicated by *arrow*) (after [16.61])



Fig. 16.9 Dependence of the unbinding force between DNA single-strand duplexes on the retract velocity. Besides the mono-logarithmic behavior, the unbinding force scales with the length of the strands, increasing from the 10- to 20- to 30-base-pair duplexes (after [16.15])

with the logarithm of the loading rate, however, each of them with a different slope (Fig. 16.9). The distance of the energy barrier along the separation path and the logarithm of the kinetic off-rate, both obtained from the force spectroscopy plot as parameters describing the energy landscape, were found to be proportional to the number of DNA complexes per duplex. This defined scaling leads to a model of fully cooperative bonds in a series for the unbinding of the base pairs in the duplex, described by one distinct length and time scale for each duplex length, where each single bond contributes a defined increment [16.15]. A temperature study revealed that entropic contributions also play a role in the unbinding between complementary DNA strands [16.64].

Energy landscapes of receptor-ligand bonds in biology can be rugged terrains with more than one prominent energy barrier. The inner barriers are undetectable in solution assays, but can become predominant for certain time scales in force-induced unbinding. Therefore, force spectroscopy appears to be a proper tool to discover hidden activation barriers and explore the energy landscape in greater detail. In initial AFM studies [16.53, 54], it was concluded that the interaction strength of biotin-streptavidin is in the range of 200–300 pN and the strength of biotin-avidin is somewhat lower (~ 150 pN). However, using BFP, the loading rate was varied over eight orders of magnitude (from 10^{-2} to 10^{6} pN/s) and gained a detailed picture of the force spectroscopy curve with forces increasing from 5 to 200 pN (Fig. 16.10) [16.38].

Distinct linear regimes that demonstrate the thermally activated nature of the bond breakage are visible, abrupt changes in slope imply a number of sharp barriers along the dissociation pathway. Above 85 pN, there is a common high strength regime for both biotin-streptavidin and biotin-avidin with a slope of $f_\beta = 34$ pN, locating a barrier deep in the binding pocket at $x_\beta = 0.12$ nm. Below 85 pN, the slopes for biotin-streptavidin and biotin-avidin are different. $f_\beta = 8$ pN for biotin-strepavidin marks a barrier at $x_\beta = 0.5$ nm, whereas the steeper slope $f_\beta = 13–14$ pN between 38 and 85 pN in the biotin-avidin spectrum indicates that its next barrier is located at 0.3 nm. Below 11 pN, the biotin-avidin spectrum exhibits a very low strength regime with a slope of $f_\beta = 1.4$ pN that maps to $x_\beta = 3$ nm. In addition to the map of barrier locations, the logarithmic intercepts found by extrapolation of each linear regime to zero force also yield estimates of the energy differences between the activation barriers (Fig. 16.10).

A meticulous picture of the biotin-avidin bond rupture process with amino acid resolution was obtained



Fig. 16.10a–c Unbinding force distributions and energy landscape of a complex molecular bond. **(a)** Force histograms of single biotin-streptavidin bonds recorded at different loading rates. The shift in peak location and the increase in width with increasing loading rate is clearly demonstrated. **(b)** Dynamic force spectra for biotin-streptavidin (*circles*) and biotin-avidin (*triangles*). The slopes of the linear regimes mark distinct activation barriers along the direction of force. **(c)** Conceptual energy landscape traversed along a reaction coordinate under force under an angle θ to the molecular coordinate. The external force f adds a mechanical potential that tilts the energy landscape and lowers the barriers. The inner barrier starts to dominate when the outer has fallen below it due to the applied force (after [16.38])

with molecular dynamics simulation (MDS) [16.47,63]. Although the time scales of MDS for AFM pulling experiments are orders of magnitudes faster, forces in laboratory speeds were approximated. By reconstructing the interaction potential, the experimentally found transition states were readily identified. Simulations of antibody-antigen unbinding, however, revealed a large heterogeneity of enforced unbinding pathways and a correspondingly large flexibility of the binding pocket region, which exhibited significant induced fit motions [16.65].

The velocity dependence of rupture forces and adhesion probability of the receptor/ligand system P-selectin/P-selectin glycoprotein ligand-1 (PSGL-1) and their relation to kinetic and thermodynamic parameters obtained in ensemble average assays were analyzed in detail in [16.52]. The adhesive interactions of this system play a central immunogenic role in directing the PSGLT-1-containing leukocytes out of the blood stream and into sites of inflammation on cell layers via P-selectin. The high molecular elasticity of the P-selectin/PSGL-1 complex was determined from the force extension profile gained in force-distance cycles and described by the freely jointed chain, a polymer model that yields the Contour length (overall maximum extension), the persistence length (effective segment dimension), and the molecular spring constant. Rupture forces of single complex unbinding increased logarithmically with the loading rate (spring constant times pulling velocity), as expected from theory, and yielded $k_{\mathrm{off}} = 0.02\,\mathrm{s}^{-1}$ and $l = 0.25\,\mathrm{nm}$.

Another characteristic of the P-selectin/PSGL-1 relevant to its biological function was found by investigating the adhesion probability, defined as the ratio between the force-distance cycles showing an adhesion event and the total number of cycles, on the pulling velocity. Counterintuitively and in contrast to experiments with antibody-antigen [16.4], cell adhesion proteins [16.9] and cadherins [16.60], the adhesion probability increased with increasing velocities [16.52]. Since the adhesion probability approaches 1.0 at fast velocities, P-selectin/PSGL-1 complex formation must occur as soon as the tip reaches the surface, thus reflecting a fast kinetic on-rate. Upon the increase in force during pulling, the complexes only dissociate under a measurable force when pulled at fast velocities. No force will be detected at low velocities because the complex has already dissociated by the pure thermal energy and/or a force beneath the noise limit. A quantitative analysis revealed a fast kinetic off-rate of $k_{\mathrm{off}} = 15 \pm 2\,\mathrm{s}^{-1}$. The fast kinetic rates and high chain-like elasticity of the PSGL-1 system guarantee a rapid exchange of the leukocytes on endothelial cell surfaces and therefore provide the basis of the physiological leukocyte *rolling* process [16.52].

PSGL-1 recognition to another member of the selectin family, L-selectin, was studied using BFP [16.66]. The loading rate was varied over three orders of magnitude, thereby gaining rupture forces from a few to 200 pN. Plotted on a logarithmic scale of loading rates, the rupture forces reveal two prominent energy barriers along the unbinding pathway. Strengths above 75 pN arise from rapid detachment ($< 0.01\,\mathrm{s}$) impeded by an inner barrier that requires Ca^{2+}, whereas strengths below 75 pN occur under slow detachment ($> 0.01\,\mathrm{s}$) impeded by an outer barrier, most likely constituted by an array of weak hydrogen bonds. It was speculated that a complex hierarchy of inner and outer barriers is significant in selectin-mediated function [16.66].

Single molecule recognition was also used to investigate the mechanism of the cadherin-mediated adhesion process of vascular endothelial cells. A monolayer of these cells constitutes the major barrier of the body that separates the blood compartment from the extracellular space of tissues. Homophilic cadherin adhesion acting within the cell junctions allows fast dynamic cellular remodeling to change the barrier properties of the cell layers. Recordings of force-distance cycles showed specific recognition events between tip- and surface-bound chimeric VE-cadherin dimers. Measuring the binding activity in dependence of the free Ca^{2+} concentration [16.60] revealed an apparent K_{D} of 1.15 mM with a Hill coefficient of $n_{\mathrm{H}} = 5.04$, indicating high cooperativity and steep dependency. It might be of physiological relevance that a local drop of free Ca^{2+} in the narrow intercellular cleft weakens intercellular adhesion and is, therefore, involved in facilitating cellular remodeling.

The rather low trans-interaction force of a single bond between two cadherin strand dimers was found to be amplified by complexes of cumulative binding strength, visible as distinct force quanta in the adhesion force distributions. These associates were formed by time-controlled lateral and trans-oligomerization, suggesting that cadherins from opposing cells associate to form complexes and, thus, increase the intercellular binding strength. The rather low values for the kinetic rates and the adhesive binding activity determined as described above, make cadherins ideal candidates for adhesion regulation by cytoskeletal tethering, thereby setting the kinetic rate of lateral self-association [16.60].

16.5.3 Live Cells and Membranes

So far, there have been only a few attempts to apply recognition force microscopy to living cells. Recently, *Lehenkari* et al. [16.67] measured the binding forces between integrin receptors in intact cells and Arg-Gly-Asp (RGD) amino acid sequence containing extracellular matrix protein ligands. Ligands, which had a higher predicted affinity for the receptor, gave greater unbinding forces, and the amino acid sequence/pH/divalent cation dependency of the receptor-ligand interaction examined by AFM was similar to the one observed under bulk measurement conditions using other techniques. In another study [16.68], the AFM was used to detect the adhesive strength between concavalin A (con A) coupled to an AFM tip and Con A receptors on the surface of NIH3T3 fibroblast cells. Crosslinking of receptors led to an increase in adhesion that could be attributed to enhanced cooperativity among adhesion complexes, which has been proposed as a physiological mechanism for modulating cell adhesion.

The sidedness and accessability of protein epitopes of the Na^{2+}/D-glucose co-transporter in intact brush border membrane vesicles was sensed with an AFM tip containing an antibody directed against an a sequence close to the glucose binding site [16.35]. Orientations and conformations of the transporter molecule were found to change during glucose binding and transmembrane transport, as evident from the observation of three distinct states discernable in interaction strength and binding activity. Force spectroscopy experiments between leukocyte function-associated antigen-1 (LFA-1) on the tip and intercellular adhesion molecule-1 (ICAM-1) expressed on cell surfaces [16.69] revealed a bilinear behavior in the force vs. log loading rate curve, marking a steep inner activation barrier and a wide outer activation barrier. Since addition of Mg^{2+}, a co-factor that stabilizes the LFA-1/ICAM-1 interaction, elevated the unbinding force of the complex in the slow loading regime and EDTA suppressed the inner barrier, it was suggested that the equilibrium dissociation constant is regulated by the energetics of the outer barrier, whereas the inner barrier determines the ability to resist an external force.

Forces about ten times higher (3 nN) were achieved when whole cells were used to modify the tip instead of single molecules, as shown in measurements of inter-cell force detections between trophoplasts and uterine pithelium cells [16.70]. In a similar configuration but with defined control of the interaction, de-adhesion forces at the resolution of individual cell adhesion molecules in cell membranes were detected and the expression of a gene was quantitatively linked to the function of its product in cell adhesion [16.71].

16.6 Recognition Imaging

Besides studying ligand-receptor recognition processes, the identification and localization of receptor binding sites on bio-surfaces such as cells and membranes are of particular interest. For this, high resolution imaging must by combined with force detection, so that binding sites can be assigned to structures.

A method for imaging functional groups using chemical force microscopy was developed in [16.72]. Both tip and surface were chemically modified, and the adhesive interactions between tip and surface directly correlated with friction images of the patterned sample surfaces. Simultaneous information for topography and recognition forces on a µm-sized streptavidin pattern was obtained by lateral force mapping on a µm-sized streptavidin pattern with a biotinylated AFM tip. An approach-retract cycle was performed in every pixel of the image, and the information for topography was gained from the contact region, whereas a recognition image was constructed from the recognition forces of the force curve [16.72]. This method was also used to map functional receptors on living cells [16.73] and differentiate red blood cells of different blood groups within a mixed population using AFM tips conjugated with a blood group A specific lectin [16.74].

A first identification and localization of single-molecule antigenic sites was realized by laterally scanning an AFM tip containing antibodies in one dimension across a surface containing a low density of antigens during recording force-distance cycles. The binding probability was determined in dependence of the lateral position, resulting in Gaussian-like profiles [16.4, 12]. The position of the antigen could be determined from the position of the maximum, yielding a positional accuracy of 1.5 nm. The width of the binding profile of 6 nm reflects the dynamical reach of the antibody on the tip, provided by the crosslinker used for coupling the antibody to the tip, and can be considered the lateral resolution obtained by this technique [16.4]. With a similar configuration, height and adhesion force images were simultaneously obtained with resolution approaching the single-molecule level as well [16.75].

The strategies of force mapping, however, lack high lateral resolution [16.72] and/or are much slower in data acquisition [16.4, 12, 75] than topography imaging, since the frequency of the retract-approach cycles performed in every pixel is limited by hydrodynamic forces in the aqueous solution. In addition, obtaining the force image requires the ligand to be disrupted from the receptor in each retract-approach cycle. For this, the z-amplitude of the retract-approach cycle must be at least 50 nm and, therefore, the ligand on the tip is without access to the receptor on the surface for most of the experiment. The development of shorter cantilevers [16.45], however, increases the speed for force mapping, because the hydrodynamic forces are significantly reduced and the resonance frequency is higher than that of commercially available cantilevers. The short cantilevers were also recently applied to follow the association and dissociation of individual chaperonin proteins GroES to GroEL in real time using dynamic force microscopy topography imaging [16.76].

An imaging method for the mapping of antigenic sites on surfaces was recently developed [16.20] by combining molecular recognition force spectroscopy [16.4] with dynamic force microscopy (DFM) [16.25, 77]. In DFM, the AFM tip is oscillated across a surface and the amplitude reduction arising from tip-surface interactions is held constant by a feedback loop that lifts or lowers the tip according to the detected amplitude signal. Since the tip only intermittently contacts the surface, this technique provides very gentle tip-surface interactions, and the specific interaction of the antibody on the tip with the antigen on the surface can be used to localize antigenic sites for recording recognition images. The principles of this method are described in detail below and in Fig. 16.11. A magnetically coated tip is oscillated by an alternating magnetic field at an ampli-



Fig. 16.11a–e Topography and recognition image. **(a)** AFM tip-lysozyme interaction during topography imaging. The *brown line* indicates the height profile obtained from a single lysozyme molecule with the AFM using a bare tip. **(b)** AFM tip-lysozyme interaction during recognition imaging. Half-antibodies are bound to the AFM tip via a flexible tether (*jagged line*) for the recognition of lysozyme on the surface. Imaging results in a height profile, as indicated (*brown line*). **(c)** Topography image. Single lysozyme molecules can be clearly resolved. Sometimes small lysozyme aggregates are observed. Image size was 500 nm. False color bar for heights from 0 (*dark*) to 5 (*bright*) nm. **(d)** Height profiles. Cross-sectional profiles of single lysozyme molecules obtained from the topography (*black line*) and the recognition (*brown line*) image. **(e)** Recognition image. The *bright dots* represent recognition profiles of single lysozyme molecules. Imaging was performed using an AFM tip carrying one half-antibody with access to the antigens on the surface. Conditions were exactly the same as in **(c)**. (After [16.20])

tude of 5 nm while being scanned along the surface. Since the tether has a length of 8 nm, the antibody on the tip always has a chance of recognition when passing an antigenic site, which increases the binding probability enormously. Since the oscillation frequency is more than 100 times faster than typical frequencies in conventional force mapping, the data acquisition rate is much higher.

Half-antibodies were used to provide a monovalent ligand on the tip. The antigen, lysozyme, was tightly adsorbed to mica in conditions that yielded a low surface coverage (for details see [16.20]). A topographic image of this preparation was first recorded in buffer using a bare AFM tip as a control (Fig. 16.11c). Single lysozyme molecules were clearly resolved (Fig. 16.11c). A cross-sectional analysis (Fig. 16.11d, profile in black) reveals that the molecules appear 8 to 12 nm in diameter and 2.0 to 2.5 nm in height. Imaging with a half-antibody tethered to the tip in conditions identical to those used to obtain the topographical image gave strikingly different images (Fig. 16.11e). They differ significantly both in height and diameter compared to the topography image (Fig. 16.11c). Cross-sectional analysis (Fig. 16.11d, trace in red) reveals a height of 3.0 to 3.5 nm and a diameter of 20 to 25 nm. Therefore, profiles obtained from the recognition image appear at least 1 nm higher and 10 nm broader than profiles from the topography image.

The antibody-antigen recognition process during imaging is depicted in Fig. 16.11b. Approaching the antigen in a lateral scan from the left, the antibody on the tip binds to the antigen about 10 nm before the tip end is above the antigenic site (Fig. 16.11b, left tip), due to the flexible tethering provided by the crosslinker. In the bound state, the z-oscillation of the cantilever is further reduced by the attractive force of the crosslinker-antibody-antigen connection, which is acting as a nonlinear spring. Since the AFM detects the z-projection of the force, the amount of the attractive force measured increases when the tip moves further to the right and reaches its maximum just above the position of the antigenic site (Fig. 16.11b, tip in middle). At lateral distances comparable to the length of the antibody-crosslinker connection, the antibody on the tip dissociates from the antibody on the surface and the attractive force goes to zero.

The diameter of cross-sectional profiles obtained from the recognition image (Fig. 16.11d, brown trace) corresponds to about twice the length of the crosslinker (6 nm) plus antibody (6 nm). Increased heights detected in comparison to profiles of the topography image (Fig. 16.11d, black trace) reflect the amplitude reduction owing to antibody-antigen recognition. The maxima of the cross-sectional profiles of the recognition image, as shown in Fig. 16.11d (brown trace), indicate the position of the antigenic site. The accuracy of maximum determination, which in turn reflects the positional accuracy of determining the position of the antigenic site, was 3 nm. The specific nature of the antibody-antigen interaction was tested by injecting free antibody into the liquid cell, so as to block the antigenic sites on the surface, and subsequent images showed a reduction in apparent height.

With this methodology, topography and recognition images can be obtained at the same time and distinct receptor sites in the recognition image can be assigned to structures from the topography image. The described methodology [16.20] is applicable to any ligand and, therefore, it should prove possible to recognize many types of proteins or protein layers and carry out epitope mapping on a nanometer scale on membranes and cells.

16.7 Concluding Remarks

Atomic force microscopy has evolved into the imaging method that yields the greatest structural details on live, biological samples like proteins, nucleotides, membranes and cells in their native, aqueous environment at ambient conditions. Due to its high lateral resolution and sensitive force detection capability, the exciting possibility of measuring inter- and intramolecular forces of biomolecules on the single-molecule level has become possible. The proof-of-principle stage of the pioneering experiments has already developed into a high-end analysis method for exploring kinetic and structural details of interactions underlying protein folding and molecular recognition by taking the advantages of single molecule studies. The information obtained from force spectroscopy includes physical parameters unachievable by other methods and opens new perspectives in exploring the regulation of the dynamics of biological processes such as molecular recognition. With ongoing instrumental developments to increase sensitivity and speed, exciting new fields may also open up in drug and cell screening technologies.

References

16.1 G. Binnig, C.F. Quate, Ch. Gerber: Atomic force microscope, Phys. Rev. Lett. **56** (1986) 930–933

16.2 G.U. Lee, D.A. Kidwell, R.J. Colton: Sensing discrete streptavidin-biotin interactions with atomic force microscopy, Langmuir **10** (1994) 354–357

16.3 E.L. Florin, V.T. Moy, H.E. Gaub: Adhesion forces between individual ligand receptor pairs, Science **264** (1994) 415–417

16.4 P. Hinterdorfer, W. Baumgartner, H.J. Gruber, K. Schilcher, H. Schindler: Detection and localization of individual antibody-antigen recognition events by atomic force microscopy, Proc. Nat. Acad. Sci. USA **93** (1996) 3477–3481

16.5 M. Grandbois, W. Dettmann, M. Benoit, H.E. Gaub: How strong is a covalent bond?, Science **283** (1999) 1727–1730

16.6 G.U. Lee, A.C. Chrisey, J.C. Colton: Direct measurement of the forces between complementary strands of DNA, Science **266** (1994) 771–773

16.7 T. Boland, B.D. Ratner: Direct measurement of hydrogen bonding in DNA nucleotide bases by atomic force microscopy, Proc. Nat. Acad. Sci. USA **92** (1995) 5297–5301

16.8 P. Wagner, M. Hegner, P. Kernen, F. Zaugg, G. Semenza: Covalent immobilization of native biomolecules onto Au(111) via N-hydroxysuccinimide ester functionalized self assembled monolayers for scanning probe microscopy, Biophys. J **70** (1996) 2052–2066

16.9 U. Dammer, O. Popescu, P. Wagner, D. Anselmetti, H.-J. Güntherodt, G.M. Misevic: Binding strength between cell adhesion proteoglycans measured by atomic force microscopy, Science **267** (1995) 1173–1175

16.10 U. Dammer, M. Hegner, D. Anselmetti, P. Wagner, M. Dreier, W. Huber, H.-J. Güntherodt: Specific antigen/antibody interactions measured by force microscopy, Biophys. J. **70** (1996) 2437–2441

16.11 Y. Harada, M. Kuroda, A. Ishida: Specific and quantized antibody-antigen interaction by atomic force microscopy, Langmuir **16** (2000) 708–715

16.12 P. Hinterdorfer, K. Schilcher, W. Baumgartner, H.J. Gruber, H. Schindler: A mechanistic study of the dissociation of individual antibody-antigen pairs by atomic force microscopy, Nanobiology **4** (1998) 39–50

16.13 S. Allen, X. Chen, J. Davies, M.C. Davies, A.C. Dawkes, J.C. Edwards, C.J. Roberts, J. Sefton, S.J.B. Tendler, P.M. Williams: Spatial mapping of specific molecular recognition sites by atomic force microscopy, Biochemistry **36** (1997) 7457–7463

16.14 R. Ros, F. Schwesinger, D. Anselmetti, M. Kubon, R. Schäfer, A. Plückthun, L. Tiefenauer: Antigen binding forces of individually addressed single-chain Fv antibody molecules, Proc. Nat. Acad. Sci. USA **95** (1998) 7402–7405

16.15 T. Strunz, K. Oroszlan, R. Schäfer, H.-J. Güntherodt: Dynamic force spectroscopy of single DNA molecules, Proc. Nat. Acad. Sci. USA **96** (1999) 11 277–11 282

16.16 S.S. Wong, E. Joselevich, A.T. Woolley, C.L. Cheung, C.M. Lieber: Covalently functionalyzed nanotubes as nanometre-sized probes in chemistry and biology, Nature **394** (1998) 52–55

16.17 P. Hinterdorfer, F. Kienberger, A. Raab, H.J. Gruber, W. Baumgartner, G. Kada, C. Riener, S. Wielert-Badt, C. Borken, H. Schindler: Poly-(ethylene glycol): an ideal spacer for molecular recognition force microscopy/spectroscopy, Single Mol. **1** (2000) 99–103

16.18 Th. Haselgrübler, A. Amerstorfer, H. Schindler, H.J. Gruber: Synthesis and applications of a new poly(ethylene glycol) derivative for the crosslinking of amines with thiols, Bioconj. Chem. **6** (1995) 242–248

16.19 C.K. Riener, G. Kada, C. Borken, F. Kienberger, P. Hinterdorfer, H. Schindler, G.J. Schütz, T. Schmidt, C.D. Hahn, H.J. Gruber: Bioconjugation for biospecific detection of single molecules in atomic force microscopy (AFM) and in single dye tracing (SDT), Recent Res. Devel. Bioconj. Chem. **1** (2002) 133–149

16.20 A. Raab, W. Han, D. Badt, S.J. Smith-Gill, S.M. Lindsay, H. Schindler, P. Hinterdorfer: Antibody recognition imaging by force microscopy, Nature Biotech. **17** (1999) 902–905

16.21 M. Conti, G. Falini, B. Samori: How strong is the coordination bond between a histidine tag and Ni-Nitriloacetate? An experiment of mechanochemistry on single molecules, Angew. Chem. **112** (2000) 221–224

16.22 F. Kienberger, G. Kada, H.J. Gruber, V.Ph. Pastushenko, C. Riener, M. Trieb, H.-G. Knaus, H. Schindler, P. Hinterdorfer: Recognition force spectroscopy studies of the NTA-His6 bond, Single Mol. **1** (2000) 59–65

16.23 L. Schmitt, M. Ludwig, H.E. Gaub, R. Tampe: A metal-chelating microscopy tip as a new toolbox for single-molecule experiments by atomic force microscopy, Biophys. J. **78** (2000) 3275–3285

16.24 C. Yuan, A. Chen, P. Kolb, V.T. Moy: Energy landscape of avidin-biotin complexes measured by atomic force microscopy, Biochemistry **39** (2000) 10 219–10 223

16.25 W. Han, S.M. Lindsay, M. Dlakic, R.E. Harrington: Kinked DNA, Nature **386** (1997) 563

16.26 G. Kada, L. Blaney, L.H. Jeyakumar, F. Kienberger, V.Ph. Pastushenko, S. Fleischer, H. Schindler,

F. A. Lai, P. Hinterdorfer: Recognition force microscopy/spectroscopy of ion channels: applications to the skeletal muscle Ca^{2+} release channel (RYR1), Ultramicroscopy **86** (2001) 129–137
16.27 D. J. Müller, W. Baumeister, A. Engel: Controlled unzipping of a bacterial surface layer atomic force microscopy, Proc. Nat. Acad. Sci. USA **96** (1999) 13170–13174
16.28 F. Oesterhelt, D. Oesterhelt, M. Pfeiffer, A. Engle, H. E. Gaub, D. J. Müller: Unfolding pathways of individual bacteriorhodopsins, Science **288** (2000) 143–146
16.29 E. Kiss, C.-G. Gölander: Chemical derivatization of muscovite mica surfaces, Coll. Surf. **49** (1990) 335–342
16.30 S. Karrasch, M. Dolder, F. Schabert, J. Ramsden, A. Engel: Covalent binding of biological samples to solid supports for scanning probe microscopy in buffer solution, Biophys. J. **65** (1993) 2437–2446
16.31 N. H. Thomson, B. L. Smith, N. Almquist, L. Schmitt, M. Kashlev, E. T. Kool, P. K. Hansma: Oriented, active *escherichia coli* RNA polymerase: an atomic force microscopy study, Biophys. J. **76** (1999) 1024–1033
16.32 G. Kada, C. K. Riener, P. Hinterdorfer, F. Kienberger, C. M. Stroh, H. J. Gruber: Dithio-phospholipids for biospecific immobilization of proteins on gold surfaces, Single Mol. **3** (2002) 119–125
16.33 C. Le Grimellec, E. Lesniewska, M. C. Giocondi, E. Finot, V. Vie, J. P. Goudonnet: Imaging of the surface of living cells by low-force contact-mode atomic force microscopy, Biophys. J. **75**(2) (1998) 695–703
16.34 K. Schilcher, P. Hinterdorfer, H. J. Gruber, H. Schindler: A non-invasive method for the tight anchoring of cells for scanning force microscopy, Cell. Biol. Int. **21** (1997) 769–778
16.35 S. Wielert-Badt, P. Hinterdorfer, H. J. Gruber, J.-T. Lin, D. Badt, H. Schindler, R. K.-H. Kinne: Single molecule recognition of protein binding epitopes in brush border membranes by force microscopy, Biophys. J. **82** (2002) 2767–2774
16.36 P. Bongrand, C. Capo, J.-L. Mege, A.-M. Benoliel: Use of hydrodynamic flows to study cell adhesion. In: *Physical Basis of Cell Adhesion*, ed. by P. Bongrand (CRC Press, Boca Raton 1988) pp. 125–156
16.37 J. N. Israelachvili: *Intermolecular and Surface Forces*, 2nd edn. (Academic Press, London 1991)
16.38 R. Merkel, P. Nassoy, A. Leung, K. Ritchie, E. Evans: Energy landscapes of receptor–ligand bonds explored with dynamic force spectroscopy, Nature **397** (1999) 50–53
16.39 A. Askin: Optical trapping and manipulation of neutral particles using lasers, Proc. Nat. Acad. Sci. USA **94** (1997) 4853–4860
16.40 K. Svoboda, C. F. Schmidt, B. J. Schnapp, S. M. Block: Direct observation of kinesin stepping by optical trapping interferometry, Nature **365** (1993) 721–727
16.41 M. S. Z. Kellermayer, S. B. Smith, H. L. Granzier, C. Bustamante: Folding-unfolding transitions in single titin molecules characterized with laser tweezers, Science **276** (1997) 1112–1216
16.42 S. Smith, Y. Cui, C. Bustamante: Overstretching B-DNA: the elastic response of individual double-stranded and single-stranded DNA molecules, Science **271** (1996) 795–799
16.43 T. R. Strick, J. F. Allemend, D. Bensimon, A. Bensimon, V. Croquette: The elasticity of a single supercoiled DNA molecule, Biophys. J. **271** (1996) 1835–1837
16.44 F. Kienberger, V. Ph. Pastushenko, G. Kada, H. J. Gruber, C. Riener, H. Schindler, P. Hinterdorfer: Static and dynamical properties of single poly(ethylene glycol) molecules investigated by force spectroscopy, Single Mol. **1** (2000) 123–128
16.45 B. V. Viani, T. E. Schäffer, A. Chand, M. Rief, H. E. Gaub, P. K. Hansma: Small cantilevers for force spectroscopy of single molecules, J. Appl. Phys. **86** (1999) 2258–2262
16.46 S. Liang, D. Medich, D. M. Czajkowsky, S. Sheng, J.-Y. Yuan, Z. Shao: Thermal noise reduction of mechanical oscillators by actively controlled external dissipative forces, Ultramicroscopy **84** (2000) 119–125
16.47 H. Grubmüller, B. Heymann, P. Tavan: Ligand binding: molecular mechanics calculation of the streptavidin-biotin rupture force, Science **271** (1996) 997–999
16.48 G. I. Bell: Models for the specific adhesion of cells to cells, Science **200** (1978) 618–627
16.49 E. Evans, K. Ritchie: Dynamic strength of molecular adhesion bonds, Biophys. J. **72** (1997) 1541–1555
16.50 T. Strunz, K. Oroszlan, I. Schumakovitch. H.-J. Güntherodt, M. Hegner: Model energy landscapes and the force-induced dissociation of ligand-receptor bonds, Biophys. J. **79** (2000) 1206–1212
16.51 E. Evans, K. Ritchie: Strength of weak bondconnecting flexible polymer chains, Biophys. J. **76** (1999) 2439–2447
16.52 J. Fritz, A. G. Katopidis, F. Kolbinger, D. Anselmetti: Force-mediated kinetics of single P-selectin/ligand complexes observed by atomic force microscopy, Proc. Nat. Acad. Sci. USA **95** (1998) 12 283–12 288
16.53 V. T. Moy, E.-L. Florin, H. E. Gaub: Adhesive forces between ligand and receptor measured by AFM, Science **266** (1994) 257–259
16.54 A. Chilkoti, T. Boland, B. Ratner, P. S. Stayton: The relationship between ligand-binding thermodynamics and protein-ligand interaction forces measured by atomic force microscopy, Biophys. J. **69** (1995) 2125–2130

16.55 M. Rief, F. Oesterhelt, B. Heymann, H.E. Gaub: Single molecule force spectroscopy on polysaccharides by atomic force microscopy, Science **275** (1997) 1295–1297

16.56 P.E. Marzsalek, A.F. Oberhauser, Y.-P. Pang, J.M. Fernandez: Polysaccharide elasticity governed by chair-boat transitions of the glucopyranose ring, Nature **396** (1998) 661–664

16.57 A.D.L. Humphries, J. Tamayo, M.J. Miles: Active quality factor control in liquids for force spectroscopy, Langmuir **16** (2000) 7891–7894

16.58 M. Rief, M. Gautel, F. Oesterhelt, J.M. Fernandez, H.E. Gaub: Reversible unfolding of individual titin immunoglobulin domains by AFM, Science **276** (1997) 1109–1112

16.59 A.F. Oberhauser, P.E. Marzsalek, H.P. Erickson, J.M. Fernandez: The molecular elasticity of the extracellular matrix tenascin, Nature **393** (1998) 181–185

16.60 W. Baumgartner, P. Hinterdorfer, W. Ness, A. Raab, D. Vestweber, H. Schindler, D. Drenckhahn: Cadherin interaction probed by atomic force microscopy, Proc. Nat. Acad. Sci. USA **97** (2000) 4005–4010

16.61 F. Schwesinger, R. Ros, T. Strunz, D. Anselmetti, H.-J. Güntherodt, A. Honegger, L. Jermutus, L. Tiefenauer, A. Plückthun: Unbinding forces of single antibody-antigen complexes correlate with their thermal dissociation rates, Proc. Nat. Acad. Sci. USA **29** (2000) 9972–9977

16.62 A.F. Oberhauser, P.K. Hansma, M. Carrion-Vazquez, J.M. Fernandez: Stepwise unfolding of titin under force-clamp atomic force microscopy, Proc. Nat. Acad. Sci. USA **98** (2001) 468–472

16.63 S. Izraelev, S. Stepaniants, M. Balsera, Y. Oono, K. Schulten: Molecular dynamics study of unbinding of the avidin-biotin complex, Biophys. J. **72** (1997) 1568–1581

16.64 I. Schumakovitch, W. Grange, T. Strunz, P. Bertoncini, H.-J. Güntherodt, M. Hegner: Temperature dependence of unbinding forces between complementary DNA strands, Biophys. J. **82** (2002) 517–521

16.65 B. Heymann, H. Grubmüller: Molecular dynamics force probe simulations of antibody/antigen unbinding: entropic control and non additivity of unbinding forces, Biophys. J. **81** (2001) 1295–1313

16.66 E. Evans, E. Leung, D. Hammer, S. Simon: Chemically distinct transition states govern rapid dissociation of single L-selectin bonds under force, Proc. Nat. Acad. Sci. USA **98** (2001) 3784–3789

16.67 P.P. Lehenkari, M.A. Horton: Single integrin molecule adhesion forces in intact cells measured by atomic force microscopy, Biochem. Biophys. Res. Com. **259** (1999) 645–650

16.68 A. Chen, V.T. Moy: Cross-linking of cell surface receptors enhances cooperativity of molecular adhesion, Biophys. J. **78** (2000) 2814–2820

16.69 X. Zhang, E. Woijcikiewicz, V.T. Moy: Force spectroscopy of the leukocyte function-associated antigen-1/intercellular adhesion molecule-1 interaction, Biophys. J. **83** (2002) 2270–2279

16.70 M. Thie, R. Rospel, W. Dettmann, M. Benoit, M. Ludwig, H.E. Gaub, H.W. Denker: Interactions between trophoblasts and uterine epithelium: monitoring of adhesive forces, Hum. Reprod. **13** (1998) 3211–3219

16.71 M. Benoit, D. Gabriel, G. Gerisch, H.E. Gaub: Discrete interactions in cell adhesion measured by single molecule force spectroscopy, Nature Cell Biol. **2** (2000) 313–317

16.72 M. Ludwig, W. Dettmann, H.E. Gaub: Atomic force microscopy imaging contrast based on molecular recognition, Biophys. J. **72** (1997) 445–448

16.73 P.P. Lehenkari, G.T. Charras, G.T. Nykänen, M.A. Horton: Adapting force microscopy for cell biology, Ultramicroscopy **82** (2000) 289–295

16.74 M. Grandbois, M. Beyer, M. Rief, H. Clausen-Schaumann, H.E. Gaub: Affinity imaging of red blood cells using an atomic force microscope, J. Histochem. Cytochem. **48** (2000) 719–724

16.75 O.H. Willemsen, M.M.E. Snel, K.O. van der Werf, B.G. de Grooth, J. Greve, P. Hinterdorfer, H.J. Gruber, H. Schindler, Y. van Kyook, C.G. Figdor: Simultaneous height and adhesion imaging of antibody antigen interactions by atomic force microscopy, Biophys. J. **57** (1998) 2220–2228

16.76 B.V. Viani, L.I. Pietrasanta, J.B. Thompson, A. Chand, I.C. Gebeshuber, J.H. Kindt, M. Richter, H.G. Hansma, P.K. Hansma: Probing protein-protein interactions in real time, Nature Struct. Biol. **7** (2000) 644–647

16.77 W. Han, S.M. Lindsay, T. Jing: A magnetically driven oscillating probe microscope for operation in liquid, Appl. Phys. Lett. **69** (1996) 1–3

Part C

Nanotribo

Part C Nanotribology and Nanomechanics

17 Micro/Nanotribology and Materials Characterization Studies Using Scanning Probe Microscopy
Bharat Bhushan, Columbus, USA

18 Surface Forces and Nanorheology of Molecularly Thin Films
Marina Ruths, Åbo, Finland
Alan D. Berman, Los Angeles, USA
Jacob N. Israelachvili, Santa Barbara, USA

19 Scanning Probe Studies of Nanoscale Adhesion Between Solids in the Presence of Liquids and Monolayer Films
Robert W. Carpick, Madison, USA
James D. Batteas, Gaithersburg, USA

20 Friction and Wear on the Atomic Scale
Enrico Gnecco, Basel, Switzerland
Roland Bennewitz, Montreal, Canada
Oliver Pfeiffer, Basel, Switzerland
Anisoara Socoliuc, Basel, Switzerland
Ernst Meyer, Basel, Switzerland

21 Nanoscale Mechanical Properties – Measuring Techniques and Applications
Andrzej J. Kulik, Lausanne, Switzerland
András Kis, Lausanne, Switzerland
Gérard Gremaud, Lausanne, Switzerland
Stefan Hengsberger, Fribourg, Switzerland
Philippe K. Zysset, Wien, Austria
Lásló Forró, Lausanne, Switzerland

22 Nanomechanical Properties of Solid Surfaces and Thin Films
Adrian B. Mann, Piscataway, USA

23 Atomistic Computer Simulations of Nanotribology
Martin H. Müser, London, Canada
Mark O. Robbins, Baltimore, USA

24 Mechanics of Biological Nanotechnology
Rob Phillips, Pasadena, USA
Prashant K. Purohit, Pasadena, USA
Jané Kondev, Waltham, USA

25 Mechanical Properties of Nanostructures
Bharat Bhushan, Columbus, USA

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

17. Micro/Nanotribology and Materials Characterization Studies Using Scanning Probe Microscopy

A sharp AFM/FFM tip sliding on a surface simulates just one asperity contact. However, asperities come in all shapes and sizes. The effect of radius of a single asperity (tip) on the friction/adhesion performance can be studied using tips of different radii. AFM/FFM are used to study the various tribological phenomena, which include surface/roughness, adhesion, friction, scratching, wear, indentation, detection of material transfer, and boundary lubrication.

Directionality in the friction is observed on both micro- and macroscales and results from the surface roughness and surface preparation. Microscale friction is generally found to be smaller than the macrofriction, as there is less plowing contribution in microscale measurements. The mechanism of material removal on the microscale is studied. Evolution of wear has also been studied using AFM. Wear is found to be initiated at nanoscratches. For a sliding interface requiring near-zero friction and wear, contact stresses should be below the hardness of the softer material to minimize plastic deformation, and surfaces should be free of nanoscratches. Wear precursors can be detected at early stages of wear by using surface potential measurements. Detection of material transfer on a nanoscale is possible with AFM. In situ surface characterization of local deformation of materials and thin coatings can be carried out using a tensile stage inside an AFM.

Boundary lubrication studies can be conducted using AFM. Chemically bonded lubricant films and self-assembled monolayers are superior in friction and wear resistance. For chemically bonded lubricant films, the adsorption of water, the formation of meniscus and its change during sliding, viscosity, and surface properties play an important role on the friction, adhesion, and durability of these films. For SAMs, their friction mechanism is explained by a so-called "molecular spring" model.

17.1 Description of AFM/FFM and Various Measurement Techniques 499
17.1.1 Surface Roughness and Friction Force Measurements ... 500
17.1.2 Adhesion Measurements 502
17.1.3 Scratching, Wear and Fabrication/Machining............ 503
17.1.4 Surface Potential Measurements 503
17.1.5 In Situ Characterization of Local Deformation Studies 504
17.1.6 Nanoindentation Measurements 504
17.1.7 Localized Surface Elasticity and Viscoelasticity Mapping 505
17.1.8 Boundary Lubrication Measurements 507

17.2 Friction and Adhesion 507
17.2.1 Atomic-Scale Friction.................. 507
17.2.2 Microscale Friction....................... 507
17.2.3 Directionality Effect on Microfriction 511
17.2.4 Velocity Dependence on Microfriction 513
17.2.5 Effect of Tip Radii and Humidity on Adhesion and Friction 515
17.2.6 Scale Dependence on Friction 518

17.3 Scratching, Wear, Local Deformation, and Fabrication/Machining.................. 518
17.3.1 Nanoscale Wear 518
17.3.2 Microscale Scratching.................. 519
17.3.3 Microscale Wear 520
17.3.4 In Situ Characterization of Local Deformation 524
17.3.5 Nanofabrication/Nanomachining ... 526

17.4 Indentation 526
17.4.1 Picoindentation 526
17.4.2 Nanoscale Indentation................. 527
17.4.3 Localized Surface Elasticity and Viscoelasticity Mapping 528

17.5 Boundary Lubrication 530
17.5.1 Perfluoropolyether Lubricants........ 530
17.5.2 Self-Assembled Monolayers........... 536
17.5.3 Liquid Film Thickness Measurements 537

17.6 Closure 538

References 539

Springer Handbook of Nanotechnology
B. Bhushan © Springer 2004

The mechanisms and dynamics of the interactions of two contacting solids during relative motion ranging from atomic- to microscale need to be understood in order to develop a fundamental understanding of adhesion, friction, wear, indentation, and lubrication processes. At most solid-solid interfaces of technological relevance contact occurs at many asperities. Consequently, the importance of investigating single asperity contacts in studies of the fundamental micro/nanomechanical and micro/nanotribological properties of surfaces and interfaces has long been recognized. The recent emergence and proliferation of proximal probes, including scanning probe microscopies (the scanning tunneling microscope and the atomic force microscope), the surface force apparatus, and computational techniques for simulating tip-surface interactions and interfacial properties, have allowed systematic investigations of interfacial problems with high resolution, as well as ways and means of modifying and manipulating nanoscale structures. These advances have led to the appearance of the new field of micro/nanotribology, which pertains to experimental and theoretical investigations of interfacial processes on scales ranging from the atomic- and molecular- to the microscale, occurring during adhesion, friction, scratching, wear, indentation, and thin-film lubrication at sliding surfaces [17.1–12].

Micro/nanotribological studies are needed to develop a fundamental understanding of interfacial phenomena on a small scale and study interfacial phenomena in micro/nanostructures used in magnetic storage systems, micro/nanoelectromechanical systems (MEMS/NEMS), and other applications [17.3, 7–9, 13, 14]. Friction and wear of lightly loaded micro/nanocomponents are highly dependent on the surface interactions (few atomic layers). These structures are generally lubricated with molecularly thin films. Micro/nanotribological studies are also valuable in understanding interfacial phenomena in macrostructures and provide a bridge between science and engineering.

The surface force apparatus (SFA), the scanning tunneling microscopes (STM), atomic force and friction force microscopes (AFM and FFM) are widely used in micro/nanotribological studies. Typical operating parameters are compared in Table 17.1. The SFA was developed in 1968 and is commonly employed to study both static and dynamic properties of molecularly thin films sandwiched between two molecularly smooth surfaces. The STM, developed in 1981, allows imaging of electrically conducting surfaces with atomic resolution and has been used for the imaging of clean surfaces, as well as of lubricant molecules. The introduction of the atomic force microscope in 1985 provided a method for measuring ultra-small forces between a probe tip and an engineering (electrically conducting or insulating) surface and has been used for topographical measurements of surfaces on the nanoscale, as well as for adhesion and electrostatic force measurements. Subsequent modifications of the AFM led to the development of the friction

Table 17.1 Comparison of typical operating parameters in SFA, STM, and AFM/FFM used for micro/nanotribological studies

Operating parameter	SFA	STM[a]	AFM/FFM
Radius of mating surface/tip	∼ 10 mm	5–100 nm	5–100 nm
Radius of contact area	10–40 µm	N/A	0.05–0.5 nm
Normal load	10–100 mN	N/A	< 0.1 nN – 500 nN
Sliding velocity	0.001–100 µm/s	0.02–200 µm/s (scan size ∼ 1 nm ×1 nm to 125 µm ×125 µm; scan rate < 1–122 Hz)	0.02–200 µm/s (scan size ∼ 1 nm ×1 nm to 125 µm ×125 µm; scan rate < 1–122 Hz)
Sample limitations	Typically atomically smooth, optically transparent mica; opaque ceramic, smooth surfaces can also be used	Electrically conducting samples	None

[a] Can only be used for atomic-scale imaging

Springer Handbook of Nanotechnology
B. Bhushan • © Springer 2004

force microscope (FFM), designed for atomic-scale and microscale studies of friction. This instrument measures forces in the scanning direction. The AFM is also used in investigations of scratching, wear, indentation, detection of transfer of material, boundary lubrication, and fabrication and machining. Meanwhile, significant progress in understanding the fundamental nature of bonding and interactions in materials, combined with advances in computer-based modeling and simulation methods, have allowed theoretical studies of complex interfacial phenomena with high resolution in space and time. Such simulations provide insights into atomic-scale energetics, structure, dynamics, thermodynamics, transport and rheological aspects of tribological processes.

The nature of interactions between two surfaces brought close together and those between two surfaces in contact as they are separated have been studied experimentally with the surface force apparatus. This has led to a basic understanding of the normal forces between surfaces and the way in which these are modified by the presence of a thin liquid or a polymer film. The frictional properties of such systems have been studied by moving the surfaces laterally, and such experiments have provided insights into the molecular-scale operation of lubricants such as thin liquid or polymer films. Complementary to these studies are those in which the AFM or FFM is used to provide a model asperity in contact with a solid or lubricated surface, Fig. 17.1. These experiments have demonstrated that the relationship between friction and surface roughness is not always simple or obvious. AFM studies have also revealed much about the nanoscale nature of intimate contact during wear and indentation.


Engineering interface
Scanning probe microscope tip on a surface
Simulation of a single asperity contact

Fig. 17.1 Schematics of an engineering interface and scanning probe microscope tip in contact with an engineering interface

In this chapter, we present a review of significant aspects of micro/nanotribological studies conducted using AFM/FFM.

17.1 Description of AFM/FFM and Various Measurement Techniques

An atomic force microscope (AFM) was developed by *Binnig* et al. in 1985. It is capable of investigating surfaces of scientific and engineering interest on an atomic scale [17.15, 16]. The AFM relies on a scanning technique to produce very high resolution, 3-D images of sample surfaces. It measures ultrasmall forces (less than 1 nN) present between the AFM tip surface mounted on a flexible cantilever beam and a sample surface. These small forces are determined by measuring the motion of a very flexible cantilever beam with an ultra-small mass by a variety of measurement techniques including optical deflection, optical interference, capacitance, and tunneling current. The deflection can be measured to within 0.02 nm, so for a typical cantilever spring constant of 10 N/m, a force as low as 0.2 nN can be detected. To put these numbers in perspective, individual atoms and human hair are typically a fraction of a nanometer and about 75 μm in diameter, respectively, and a drop of water and an eyelash have a mass of about 10 μN and 100 nN, respectively. In the operation of high resolution AFM, the sample is generally scanned, rather than the tip, because any cantilever movement would add vibrations. AFMs are available for measurement of large samples where the tip is scanned and the sample is stationary. To obtain atomic resolution with the AFM, the spring constant of the cantilever should be weaker than the equivalent spring between atoms. A cantilever beam with a spring constant of about 1 N/m or lower is desirable. For high lateral resolution, tips should be as sharp as possible. Tips with a radius ranging from 10–100 nm are commonly available.

A modification to AFM, providing a sensor to measure the lateral force, led to the development of the friction force microscope (FFM), or the lateral force microscope (LFM), designed for atomic-scale and microscale studies of friction [17.3–5, 7, 8, 11, 17–25] and lubrication [17.26–30]. This instrument measures lateral or friction forces (in the plane of sample surface and in the scanning direction). By using a standard or a sharp diamond tip mounted on a stiff cantilever beam, AFM is also used in investigations of scratching and wear [17.6, 9, 11, 22, 31–33], indentation [17.6, 9, 11, 22, 34, 35], and fabrication/machining [17.4, 11, 22].


a)
Mirrored prism
Diode laser and lens
AFM signal (A+B) – (C+D)
Mirror
A
B
C
D
FFM signal (A+C) – (B+D)
Split-diode photo-detector
Cantilever and substrate
Sample
z
y
x
xyz PZT tube scanner
b)
Split-diode photo-detector
Laser diode, collimator, and lens
Adjust-able mirror
Laser path
Fixed Mirror
Lens
Mirror
Lens
y
x
z
xyz PZT tube scanner
Camera objective lens
Cantilever holder
Sample
Motorized stage
x
y

Fig. 17.2a,b Schematics **(a)** of a commercial small sample atomic force microscope/friction force microscope (AFM/FFM) and **(b)** a large sample AFM/FFM

Surface roughness, including atomic-scale imaging, is routinely measured using the AFM, Fig. 17.2. Adhesion, friction, wear, and boundary lubrication at the interface between two solids with and without liquid films are studied using AFM and FFM. Nanomechanical properties are also measured using an AFM. In situ surface characterization of local deformation of materials and thin coatings has been carried out by imaging the sample surfaces using an AFM during tensile deformation using a tensile stage.

17.1.1 Surface Roughness and Friction Force Measurements

Simultaneous measurements of surface roughness and friction force can be made with a commercial AFM/FFM. These instruments are available for the measurement of small samples and large samples. In a small sample AFM, shown in Fig. 17.2a, the sample, generally no larger than 10 mm × 10 mm, is mounted on a PZT tube scanner that consists of separate electrodes to scan precisely the sample in the x-y plane in a raster pattern and move it in the vertical (z) direction. A sharp tip at the free end of a flexible cantilever is brought in contact with the sample. Normal and frictional forces being applied at the tip-sample interface are measured using a laser beam deflection technique. A laser beam from a diode laser is directed by a prism onto the back of a cantilever near its free end, which is tilted downward at about 10° with respect to the horizontal plane. The reflected beam from the vertex of the cantilever is directed through a mirror onto a quad photodetector (split photodetector with four quadrants). The differential signal from the top and bottom photodiodes provides the AFM signal, which is a sensitive measure of the cantilever vertical deflection. Topographic features of the sample cause the tip to deflect in the vertical direction as the sample is scanned under the tip. This tip deflection will change the direction of the reflected laser beam, changing the intensity difference between the top and bottom sets of photodetectors (AFM signal). In the AFM operating mode, called the height mode, for topographic imaging, or for any other operation in which the applied normal force is to be kept a constant, a feedback circuit is used to modulate the voltage applied to the PZT scanner to adjust the height of the PZT, so that the cantilever vertical deflection (given by the intensity difference between the top and bottom detector) will remain constant during scanning. The PZT height variation is thus a direct measure of the surface roughness of the sample.

In a large sample AFM both force sensors using optical deflection method and scanning unit are mounted on the microscope head, Fig. 17.2b. Because of vibrations added by cantilever movement, lateral resolution of this design is somewhat poorer than the design in Fig. 17.2a in which the sample is scanned instead of cantilever beam. The advantage of the large sample AFM is that large samples can be measured readily.

Most AFMs can be used for topography measurements in the so-called tapping mode (intermittent contact mode), also referred to as dynamic force microscopy. In the tapping mode, during scanning over the surface, the cantilever/tip assembly is sinusoidally vibrated by a piezo mounted above it, and the oscillating tip slightly taps the surface at the resonant frequency of the cantilever (70–400 Hz) with a constant (20–100 nm) oscillating amplitude introduced in the vertical direction with a feedback loop keeping the average normal force constant, Fig. 17.3. The oscillating amplitude is kept large enough so that the tip does not get stuck to the sample because of adhesive attractions. The tapping mode is used in topography measurements to minimize the effects of friction and other lateral forces and to measure topography of soft surfaces.

For measurement of friction force being applied at the tip surface during sliding, left-hand and right-hand sets of quadrants of the photodetector are used. In the so-called friction mode, the sample is scanned back and forth in a direction orthogonal to the long axis of the cantilever beam. A friction force between the sample and the tip will produce a twisting of the cantilever. As a result, the laser beam will be reflected out of the plane defined by the incident beam and the beam reflected vertically from an untwisted cantilever. This produces an intensity difference of the laser beam received in the left-hand and right-hand sets of quadrants of the photodetector. The intensity difference between the two sets of detectors (FFM signal) is directly related to the degree of twisting and, hence, to the magnitude of the friction force. One problem associated with this method is that any misalignment between the laser beam and the photodetector axis would introduce error in the measurement. However, by following the procedures developed by *Ruan* and *Bhushan* [17.19], in which the average FFM signal for the sample scanned in two opposite directions is subtracted from the friction profiles of each of the two scans, the misalignment effect is eliminated. This method provides three-dimensional maps of friction force. By following the friction force calibration procedures developed by *Ruan* and *Bhushan* [17.19], voltages corresponding to friction forces can be converted to force units. The coefficient of friction is obtained from the slope of friction force data measured as a function of normal loads typically ranging from 10–150 nN. This approach eliminates any contributions due to the adhesive forces [17.22]. For calculation of the coefficient of friction based on a single point measurement, friction force should be divided by the sum of applied normal load and intrinsic adhesive force. Furthermore, it should be pointed out that for a single asperity contact, the coefficient of friction is not independent of load. This will be discussed in greater detail later in the chapter.



Fig. 17.3 Schematic of tapping mode used for surface topography measurements

Topographic measurements in the contact mode are typically made using a sharp, microfabricated square-pyramidal Si_3N_4 tip with a radius of 30–50 nm on a triangular cantilever beam (Fig. 17.4a) with normal stiffness on the order of 0.5 N/m at a normal load of about 10 nN, and friction measurements are carried out in the load range of 10–150 nN. Topography measurements in the tapping mode utilize a stiff cantilever with high resonant frequency; typically, a square-pyramidal, etched, single-crystal silicon tip with a tip radius of 5–10 nm mounted on a stiff rectangular silicon cantilever beam (Fig. 17.4a) with a normal stiffness on the order of 50 N/m is used. Carbon nanotube tips with small diameters (few nm) and high aspect ratios attached on the single-crystal silicon, square pyramidal tips are used for high resolution imaging of surfaces and deep trenches in the tapping mode or noncontact mode (Fig. 17.4b). To study the effect of the radius of a single asperity (tip) on adhesion and friction, microspheres of silica with radii ranging from about 4–15 μm are attached with epoxy at the ends of tips of Si_3N_4 cantilever beams. Optical micrographs of two of the microspheres mounted at the ends of triangular cantilever beams are shown in Fig. 17.4c.

The tip is scanned in such a way that its trajectory on the sample forms a triangular pattern, Fig. 17.5.



Fig. 17.4 **(a)** SEM micrographs of a square-pyramidal PECVD Si_3N_4 tip with a triangular cantilever beam (*top*), a square-pyramidal etched single-crystal silicon tip with a rectangular silicon cantilever beam (*middle*), and a three-sided pyramidal natural diamond tip with a square stainless steel cantilever beam (*bottom*), **(b)** SEM micrograph of a multiwalled carbon nanotube (MWNT) physically attached on the single-crystal silicon, square-pyramidal tip, and **(c)** optical micrographs of a commercial Si_3N_4 tip and two modified tips showing SiO_2 spheres mounted over the sharp tip and at the end of the triangular Si_3N_4 cantilever beams. (Radii of the tips are given in the figure)



Fig. 17.5 Schematic of triangular pattern trajectory of the tip as the sample (or the tip) is scanned in two dimensions. During scanning, data are recorded only during scans along the solid scan lines

Scanning speeds in the fast and slow scan directions depend on the scan area and scan frequency. Scan sizes ranging from less than 1 nm × 1 nm to 125 µm × 125 µm and scan rates from less than 0.5 to 122 Hz typically can be used. Higher scan rates are used for smaller scan lengths. For example, scan rates in the fast and slow scan directions for an area of 10 µm × 10 µm scanned at 0.5 Hz are 10 µm/s and 20 nm/s, respectively.

17.1.2 Adhesion Measurements

Adhesive force measurements are performed in the so-called force calibration mode. In this mode, force-distance curves are obtained, for an example, see Fig. 17.6. The horizontal axis gives the distance the piezo (and hence the sample) travels, and the vertical axis gives the tip deflection. As the piezo extends, it approaches the tip, which is at this point in free air and hence shows no deflection. This is indicated by the flat portion of the curve. As the tip approaches within a few nanometers of the sample (point A), an attractive force exists between the atoms of the tip surface and the atoms of the sample surface. The tip is pulled toward the sample and contact occurs at point B on the graph. From this point on, the tip is in contact with the surface, and as the piezo extends farther, the tip gets deflected farther. This is represented by the sloped portion of the curve. As the piezo retracts, the tip goes beyond the zero deflection (flat) line, due to attractive forces (van der Waals forces and long-range meniscus forces), into the adhesive regime. At point C in the graph, the tip snaps free of the adhesive forces and is again in free air. The horizontal distance between points B and C along the retrace line gives the distance the tip moved in the adhesive regime. This distance multiplied by the stiffness of the cantilever gives the adhesive force. Incidentally, the horizontal shift between the loading and unloading curves results from the hysteresis in the PZT tube [17.4, 36].



Fig. 17.6 Typical force-distance curve for a contact between Si_3N_4 tip and single-crystal silicon surface in measurements made in the ambient environment. Contact between the tip and silicon occurs at point B; tip breaks free of adhesive forces at point C as the sample moves away from the tip

17.1.3 Scratching, Wear and Fabrication/Machining

For microscale scratching, microscale wear, nanofabrication/nanomachining, and nanoindentation hardness measurements, an extremely hard tip is required. A three-sided pyramidal single-crystal natural diamond tip with an apex angle of 80° and a radius of about 100 nm mounted on a stainless steel cantilever beam with normal stiffness of about 25 N/m is used at relatively higher loads (1–150 μN), Fig. 17.4a. For scratching and wear studies, the sample is generally scanned in a direction orthogonal to the long axis of the cantilever beam (typically at a rate of 0.5 Hz), so that friction can be measured during scratching and wear. The tip is mounted on the cantilever such that one of its edges is orthogonal to the long axis of the beam. Therefore, wear during scanning along the beam axis is higher (about two to three times) than during scanning orthogonal to the beam axis. For wear studies, an area on the order of 2 μm × 2 μm is scanned at various normal loads (ranging from 1 to 100 μN) for a selected number of cycles [17.4, 22].

Scratching can also be performed at ramped loads and the coefficient of friction can be measured during scratching [17.33]. A linear increase in the normal load approximated by a large number of normal load increments of small magnitude is applied using a software interface (lithography module in Nanoscope III) that allows the user to generate controlled movement of the tip with respect to the sample. The friction signal is tapped out of the AFM and is recorded on a computer. A scratch length on the order of 25 μm and a velocity on the order of 0.5 μm/s are used and the number of loading steps is usually 50.

Nanofabrication/nanomachining is conducted by scratching the sample surface with a diamond tip at specified locations and scratching angles. The normal load used for scratching (writing) is on the order of 1–100 μN with a writing speed on the order of 0.1–200 μm/s [17.4, 5, 11, 22, 37].

17.1.4 Surface Potential Measurements

To detect wear precursors and study the early stages of localized wear, the multimode AFM can be used to measure the potential difference between the tip and the sample by applying a DC bias potential and an oscillating (AC) potential to a conducting tip over a grounded substrate in a Kelvin probe microscopy, or so-called "nano-Kelvin probe" technique [17.38–40].

Mapping of the surface potential is made in the so-called "lift mode" (Fig. 17.7). These measurements are made simultaneously with the topography scan in the



Fig. 17.7 Schematic of lift mode used to make surface potential measurement. The topography is collected in tapping mode in the primary scan. The cantilever piezo is deactivated. Using topography information of the primary scan, the cantilever is scanned across the surface at a constant height above the sample. An oscillating voltage at the resonant frequency is applied to the tip and a feedback loop adjusts the DC bias of the tip to maintain the cantilever amplitude at zero. The output of the feedback loop is recorded by the computer and becomes the surface potential map [17.4]

tapping mode using an electrically conducting (nickel-coated single-crystal silicon) tip. After each line of the topography scan is completed, the feedback loop controlling the vertical piezo is turned off, and the tip is lifted from the surface and traced over the same topography at a constant distance of 100 nm. During the lift mode, a DC bias potential and an oscillating potential (3–7 V) is applied to the tip. The frequency of oscillation is chosen to be equal to the resonant frequency of the cantilever (~ 80 kHz). When a DC bias potential equal to the negative value of surface potential of the sample (on the order of ±2 V) is applied to the tip, it does not vibrate. During scanning, a difference between the DC bias potential applied to the tip and the potential of the surface will create DC electric fields that interact with the oscillating charges (as a result of the AC potential), causing the cantilever to oscillate at its resonant frequency, as in tapping mode. However, a feedback loop is used to adjust the DC bias on the tip to exactly nullify the electric field and, thus, the vibrations of the cantilever. The required bias voltage follows the localized potential of the surface. The surface potential was obtained by reversing the sign of the bias potential provided by the electronics [17.39, 40]. Surface and subsurface changes of structure and/or chemistry can cause changes in the measured potential of a surface. Thus, the mapping of the surface potential after sliding can be used for detecting wear precursors and studying the early stages of localized wear.

17.1.5 In Situ Characterization of Local Deformation Studies

In situ characterization of local deformation of materials can be carried out by performing tensile, bending, or compression experiments inside an AFM and by observing nanoscale changes during the deformation experiment [17.6]. In these experiments, small deformation stages are used to deform the samples inside an AFM. In tensile testing of the polymeric films carried out by *Bobji* and *Bhushan* [17.41, 42], a tensile stage was used (Fig. 17.8). The stage with a left-right combination lead screw (which helps to move the slider in the opposite direction) was used to stretch the sample and minimize the movement of the scanning area, which was kept close to the center of the tensile specimen. One end of the sample was mounted on the slider via a force sensor to monitor the tensile load. The samples were stretched for various strains using a stepper motor, and the same control area at different strains was imaged. In order to better locate the control area for imaging, a set of four markers was created at the corners of a 30 µm × 30 µm square at the center of the sample by scratching the sample with a sharp silicon tip. The scratching depth was controlled such that it did not affect cracking behavior of the coating. A minimum displacement of 1.6 µm could be obtained. This corresponded to a strain increment of 8×10^{-3}% for a sample length of 38 mm. The maximum travel was about 100 mm. The resolution of the force sensor was 10 mN with a capacity of 45 N. During stretching, a stress-strain curve was obtained during the experiment to study any correlation between the degree of plastic strain and propensity of cracks.

17.1.6 Nanoindentation Measurements

For nanoindentation hardness measurements, the scan size is set to zero, and a normal load is then applied to make the indents using the diamond tip. During this procedure, the tip is continuously pressed against the sample surface for about two seconds at various indentation loads. The sample surface is scanned before and after the scratching, wear, or indentation to obtain the



Fig. 17.8 Schematic of the tensile stage to conduct in situ tensile testing of the polymeric films in AFM [17.42]

initial and final surface topographies at a low normal load of about 0.3 μN using the same diamond tip. An area larger than the indentation region is scanned to observe the indentation marks. Nanohardness is calculated by dividing the indentation load by the projected residual area of the indents [17.34].

Direct imaging of the indent allows one to quantify piling up of ductile material around the indenter. However, it becomes difficult to identify the boundary of the indentation mark with great accuracy. This makes the direct measurement of contact area somewhat inaccurate. A technique with the dual capability of depth-sensing, as well as in situ imaging, which is most appropriate in nanomechanical property studies, is used for accurate measurement of hardness with shallow depths [17.4, 35]. This indentation system is used to make load-displacement measurement and, subsequently, carry out in situ imaging of the indent, if required. The indentation system consists of a three-plate transducer with electrostatic actuation hardware used for direct application of normal load and a capacitive sensor used for measurement of vertical displacement. The AFM head is replaced with this transducer assembly while the specimen is mounted on the PZT scanner, which remains stationary during indentation experiments. Indent area and, consequently, hardness value can be obtained from the load-displacement data. The Young's modulus of elasticity is obtained from the slope of the unloading curve.

17.1.7 Localized Surface Elasticity and Viscoelasticity Mapping

Indentation experiments provide a single-point measurement of the Young's modulus of elasticity calculated from the slope of the indentation curve during unloading. Localized surface elasticity maps can be obtained using dynamic force microscopy in which an oscillating tip is scanned over the sample surface in contact under steady and oscillating load. Lower frequency operation mode in the kHz range such as force modulation microscopy [17.43–45] and pulsed force microscopy [17.46] are well suited for soft samples such as polymers. However, if the tip-sample contact stiffness becomes significantly higher than the cantilever stiffness, the sensitivity of these techniques strongly decreases. In this case, sensitivity of the measurement of stiff materials can be improved by using high-frequency operation modes in the MHz range such as acoustic (ultrasonic) force microscopy [17.47]. We only describe here the force modulation technique.

In the force modulation technique, the oscillation is applied to the cantilever substrate with a cantilever piezo (bimorph), Fig. 17.9a. For measurements, an etched silicon tip is first brought in contact with a sample under a static load of 50–300 nN. In addition to the static load applied by the sample piezo, a small oscillating (modulating) load is applied by a bimorph, generally at a frequency (about 8 kHz) far below that of the natural resonance of the cantilever (70–400 kHz). When the


a)
Tip substrate holder
Cantilever piezo
d_b
Cantilever substrate
Sample
b)
$d_s \simeq 0$
$d_c \simeq d_b$
d_b
Infinitely stiff sample
$d_c \simeq 0$
$d_s \simeq d_b$
d_b
d_s
Infinitely compliant sample
$d_b \simeq d_c + d_s$
d_s
d_b
d_b
d_c
Intermediately compliant sample

Fig. 17.9a,b Schematics **(a)** of the bimorph assembly and **(b)** of the motion of the cantilever and tip as a result of the oscillations of the bimorph for an infinitely stiff sample, an infinitely compliant sample, and an intermediate sample. The *thin line* represents the cantilever at the top cycle, and the *thick line* corresponds to the bottom of the cycle. The *dashed line* represents the position of the tip if the sample was not present or was infinitely compliant. d_c, d_s and d_b are the oscillating (AC) deflection amplitude of the cantilever, penetration depth, and oscillating (AC) amplitude of the bimorph, respectively [17.44]

tip is brought into contact with the sample, the surface resists the oscillations of the tip, and the cantilever deflects. Under the same applied load, a stiff area on the sample would deform less than a soft one; i. e., stiffer areas cause greater deflection amplitudes of the cantilever, Fig. 17.9b. The variations in the deflection amplitudes provide a measure of the relative stiffness of the surface. Contact analyses can be used to obtain a quantitative measure of localized elasticity of soft surfaces [17.44]. The elasticity data are collected simultaneously with


Tapping mode phase imaging
Extender electronics
Controller
Phase data
Computer
Height data
Laser
Photo-detector
Substrate holder
Canti-lever piezo
Cantilever substrate
Material 1
Sample
Material 2
z control
x-y-z piezo
xy control
Cantilever response
Cantilever in free air
phase angle
Viscoelastic material
Nearly elastic material
AFM setting definitions
Before engagement
2 × free amplitude
During engagement
2 × set-point

Fig. 17.10 Schematic of tapping mode used to obtain height and phase data and definitions of tapping amplitude and set point. During scanning the cantilever is vibrated at its resonant frequency and the sample x-y-z piezo is adjusted by feedback control in the z-direction to maintain a constant set point. The computer records height and phase angle (which is a function of the viscoelastic properties of the sample materials) data

the surface height data using a so-called negative lift mode technique. In this mode, each scan line of each topography image (obtained in tapping mode) is replaced with the tapping action disabled and the tip lowered into steady contact with the surface.

Another form of dynamic force microscopy, phase contrast microscopy, is used to detect the contrast in viscoelastic (viscous energy dissipation) properties of the different materials across the surface [17.48–52]. In this technique, both deflection amplitude and phase angle contrasts are measured, which are the measures of the relative stiffness and viscoelastic properties, respectively. Tapping mode is utilized. For tapping mode during scanning, the cantilever/tip assembly is sinusoidally vibrated at its resonant frequency, and the sample X-Y-Z piezo is adjusted using feedback control in the z-direction to maintain a constant set point. As shown in Fig. 17.10, the cantilever/tip assembly is vibrated at some amplitude, here referred to as the tapping amplitude, by a cantilever piezo before the tip engages the sample. The tip engages the sample at some set point, which may be thought of as the amplitude of the cantilever as influenced by contact with the sample. A lower set point gives a reduced amplitude and closer mean tip-to-sample distance. This is also depicted in Fig. 17.10. The feedback signal to the z-direction sample piezo (to keep the set point constant) is a measure of topography. This height data is recorded on a computer. The extender electronics is used to measure the phase angle lag between the cantilever piezo drive signal and the cantilever response during sample engagement. As illustrated in Fig. 17.10, the phase angle lag is (at least partially) a function of the viscoelastic properties of the sample material. A range of tapping amplitudes and set points can be used for measurements. A commercially etched single-crystal silicon tip (DI TESP) used for tapping mode, with a radius of 5–10 nm, a stiffness of 20–100 N/m, and a natural frequency of 350–400 kHz is normally used. Scanning is normally set to a rate of 1 Hz along the fast axis.

17.1.8 Boundary Lubrication Measurements

To study nanoscale boundary lubrication, adhesive forces are measured in the force calibration mode, as previously described. The adhesive forces are also calculated from the horizontal intercept of friction versus normal load curves at a zero value of friction force. For friction measurements, the samples are typically scanned using an Si_3N_4 tip over an area of $2 \times 2\,\mu m$ at the normal load ranging from 5 to 130 nN. The samples are generally scanned with a scan rate of 0.5 Hz resulting in a scanning speed of 2 μm/s. Velocity effects on friction are studied by changing the scan frequency from 0.1 to 60 Hz while the scan size is maintained at $2 \times 2\,\mu m$, which allows the velocity to vary from 0.4 to 240 μm/s. To study the durability properties, the friction force and coefficient of friction are monitored during scanning at a normal load of 70 nN and a scanning speed of 0.8 μm/s for a desired number of cycles [17.27, 28, 30].

17.2 Friction and Adhesion

17.2.1 Atomic-Scale Friction

To study friction mechanisms on an atomic scale, a well characterized, freshly cleaved surface of highly oriented pyrolytic graphite (HOPG) has been used by *Mate* et al. [17.17] and *Ruan* and *Bhushan* [17.20].

The atomic-scale friction force of HOPG exhibited the same periodicity as that of the corresponding topography (Fig. 17.11a), but the peaks in friction and those in topography are displaced relative to each other (Fig. 17.11b). A Fourier expansion of the interatomic potential was used to calculate the conservative interatomic forces between atoms of the FFM tip and those of the graphite surface. Maxima in the interatomic forces in the normal and lateral directions do not occur at the same location, which explains the observed shift between the peaks in the lateral force and those in the corresponding topography. Furthermore, the observed local variations in friction force were explained by variation in the intrinsic lateral force between the sample and the FFM tip resulting from an atomic-scale stick-slip process [17.17, 20].

17.2.2 Microscale Friction

Local variations in the microscale friction of cleaved graphite have been observed (Fig. 17.12). These arise from structural changes that occur during the cleaving process [17.21]. The cleaved HOPG surface is largely atomically smooth, but exhibits line-shaped regions in which the coefficient of friction is more than an order of magnitude larger. Transmission electron microscopy indicates that the line-shaped regions consist of graphite planes of different orientation, as well as of amorphous





Fig. 17.11 **(a)** Gray-scale plots of surface topography and friction force maps of a 1 nm × 1 nm area of freshly cleaved HOPG showing the atomic-scale variation of topography and friction and **(b)** schematic of superimposed topography and friction maps from **(a)**; the symbols correspond to maxima. Note the spatial shift between the two plots [17.20]

carbon. Differences in friction have also been observed for multiphase ceramic materials [17.53]. Figure 17.13 shows the surface roughness and friction force maps of Al_2O_3-TiC (70–30 wt%). TiC grains have a Knoop hardness of about 2,800 kg/mm^2. Therefore, they do not polish as much and result in a slightly higher elevation (about 2–3 nm higher than that of Al_2O_3 grains). TiC grains exhibit higher friction force than Al_2O_3 grains. The coefficients of friction of TiC and Al_2O_3 grains are 0.034 and 0.026, respectively, and the coefficient of friction of Al_2O_3-TiC composite is 0.03. Local variation in friction force also arises from the scratches present on the Al_2O_3-TiC surface. *Meyer* et al. [17.54] also used FFM to measure structural variations of organic mono- and multilayer films. All of these measurements suggest that the FFM can be used for structural mapping of the



Fig. 17.12 **(a)** Surface roughness and **(b)** friction force maps at a normal load of 42 nN of freshly cleaved HOPG surface against an Si_3N_4 FFM tip. Friction in the *line-shaped region* is over an order of magnitude larger than the *smooth areas* [17.20]



Fig. 17.13 Gray-scale surface roughness ($\sigma = 0.80$ nm) and friction force maps (mean = 7.0 nN, $\sigma = 0.90$ nN) for Al_2O_3-TiC (70–30 wt%) at a normal load of 138 nN [17.53]



Fig. 17.14 Surface roughness map ($\sigma = 4.4$ nm); surface slope map taken in the sample sliding direction, the horizontal axis, (mean = 0.023, $\sigma = 0.197$); and friction force map (mean = 6.2 nN, $\sigma = 2.1$ nN) for a lubricated thin-film magnetic rigid disk for a normal load of 160 nN [17.22]

surfaces. FFM measurements can be used to map chemical variations, as indicated by the use of the FFM with a modified probe tip to map the spatial arrangement of chemical functional groups in mixed organic monolayer films [17.55]. Here, sample regions that had stronger interactions with the functionalized probe tip exhibited larger friction.

Local variations in the microscale friction of nominally rough, homogeneous surfaces can be significant and are seen to depend on the local surface slope, rather than the surface height distribution, Fig. 17.14. This dependence was first reported by *Bhushan* and *Ruan* [17.18], *Bhushan* et al. [17.22], and *Bhushan* [17.37] and later discussed in more detail in [17.56] and [17.57]. In order to show elegantly any correlation between local values of friction and surface roughness, surface roughness and friction force maps of a gold-coated ruling with somewhat rectangular grids and a silicon grid with square pits were obtained, see Fig. 17.15 [17.57]. Figures 17.14 and 17.15 show the surface roughness map, the slopes of the roughness map taken along the sliding direction (surface slope map), and the friction force map for various samples. There is a strong correlation between the surface slopes and friction forces. For example, in Fig. 17.15, friction force is high locally at the edge of the grids and pits with a positive slope and is low at the edges with a negative slope.

We now examine the mechanism of microscale friction, which may explain the resemblance between the slope of surface roughness maps and the corresponding friction force maps [17.4, 5, 18, 20–22, 56, 57]. There are three dominant mechanisms of friction: adhesive, adhesive and roughness (ratchet), and plowing [17.10, 57]. First, we may assume these to be additive. The adhesive mechanism cannot explain the local variation in friction. Next, we consider the ratchet mechanism. We consider a small tip sliding over an asperity making an angle θ with the horizontal plane, Fig. 17.16. The normal force W (normal to the general surface) applied by the tip to the sample surface is constant. The friction force F on the sample would be a constant for a smooth surface if the friction mechanism does not change. For a rough surface, as shown in Fig. 17.16, if the adhesive mechanism does not change during sliding, the local value of coefficient of friction remains constant,

$$\mu_0 = S/N \,, \tag{17.1}$$





Fig. 17.15a,b Surface roughness map, surface slope map taken in the sample sliding direction (the horizontal axis), and friction force map for **(a)** a gold-coated ruling (with somewhat rectangular grids with a pitch of 1 µm and a ruling step height of about 70 nm) at a normal load of 25 nN and **(b)** a silicon grid (with 5 µm square pits of 180-nm depth and a pitch of 10 µm) [17.57]



Fig. 17.16 Schematic illustration showing the effect of an asperity (making an angle θ with the horizontal plane) on the surface in contact with the tip on local friction in the presence of adhesive friction mechanism. W and F are the normal and friction forces, respectively, and S and N are the force components along and perpendicular to the local surface of the sample at the contact point, respectively

where S is the local friction force and N is the local normal force. However, the friction and normal forces are measured with respect to global horizontal and normal axes, respectively. The measured local coefficient of friction μ_1 in the ascending part is

$$\begin{aligned}\mu_1 &= F/W\\ &= (\mu_0 + \tan\theta)\,/\,(1-\mu_0\tan\theta) \sim \mu_0 + \tan\theta\,,\\ &\text{for small } \mu_0\tan\theta\,,\end{aligned} \tag{17.2}$$

indicating that in ascending part of the asperity one may simply add the friction force and the asperity slope to one another. Similarly, on the right-hand side (descending part) of the asperity,

$$\begin{aligned}\mu_2 &= (\mu_0 - \tan\theta)\,/\,(1+\mu_0\tan\theta) \sim \mu_0 - \tan\theta\,,\\ &\text{for small } \mu_0\tan\theta\,.\end{aligned} \tag{17.3}$$

For a symmetrical asperity, the average coefficient of friction experienced by the FFM tip traveling across the whole asperity is

$$\begin{aligned}\mu_{\text{ave}} &= (\mu_1+\mu_2)\,/2\\ &= \mu_0\left(1+\tan^2\theta\right)/\left(1-\mu_0^2\tan^2\theta\right)\\ &\sim \mu_0\left(1+\tan^2\theta\right)\,,\\ &\text{for small } \mu_0\tan\theta\,.\end{aligned} \tag{17.4}$$

Finally, we consider the plowing component of friction with tip sliding in either direction, which is [17.10, 58]

$$\mu_\text{p} \sim \tan\theta\,. \tag{17.5}$$

Because we notice little damage of the sample surface in FFM measurements, the contribution by plowing is expected to be small and the ratchet mechanism is believed to be the dominant mechanism for the local variations in the friction force map. With the tip sliding over the leading (ascending) edge of an asperity, the surface slope is positive; it is negative during sliding over the trailing (descending) edge of an asperity. Thus, measured friction is high at the leading edge of asperities and low at the trailing edge. In addition to the slope effect, the collision of the tip when encountering an asperity with a positive slope produces additional torsion of the cantilever beam, leading to higher measured friction force. When encountering an asperity with the same negative slope, however, there is no collision effect and hence no effect on torsion. This effect also contributes to the difference in friction forces when the tip scans up and down on the same topography feature. The ratchet mechanism and the collision effects thus explain semiquantitatively the correlation between the slopes of the roughness maps and friction force maps observed in Figs. 17.14 and 17.15. We note that in the ratchet mechanism, the FFM tip is assumed to be small compared to the size of asperities. This is valid since the typical radius of curvature of the tips is about 10–50 nm. The radii of curvature of samples, the asperities measured here (the asperities that produce most of the friction variation) are found to typically be about 100–200 nm, which is larger than that of the FFM tip [17.59]. It is important to note that the measured local values of friction and normal forces are measured with respect to global (and not local) horizontal and vertical axes, which are believed to be relevant in applications.

17.2.3 Directionality Effect on Microfriction

During friction measurements, the friction force data from both the forward (trace) and backward (retrace) scans are useful in understanding the origins of the observed friction forces. Magnitudes of material-induced effects are independent of the scanning direction, whereas topography-induced effects are different between forward and backward scanning directions. Since the sign of the friction force changes as the scanning direction is reversed (because of the reversal of torque applied to the end of the tip), addition of the friction force data of the forward and backward scan eliminates the material-induced effects, while topography-induced effects still remain. Subtraction of the data between forward and backward scans does not eliminate either effect, see Fig. 17.17 [17.57].



Fig. 17.17 Schematic of friction forces expected when a tip traverses a sample that is composed of different materials and sharp changes in topography. A schematic of surface slope is also shown (T = Trace, R = Retrace)

Owing to the reversal of the sign of the retrace (R) friction force with respect to the trace (T) data, the friction force variations due to topography are in the same direction (peaks in trace correspond to peaks in retrace). However, the magnitudes of the peaks in trace and retrace at a given location are different. An increase in the friction force experienced by the tip when scanning up a sharp change in topography is more than the decrease in the friction force experienced when scanning down the same topography change, partly due to the collision effects discussed earlier. Asperities on engineering surfaces are asymmetrical, which also affect the magnitude of friction force in the two directions. In addition, asymmetry in tip shape may have an effect on the directionality effect of friction. We will later note that the magnitude of surface slopes are virtually identical. Therefore, the tip shape asymmetry should not have much effect.

Figure 17.18 shows surface height and friction force data for gold ruler and a silicon grid in the trace and retrace directions. Subtraction of two friction data yields a residual peak, because of the differences in the magnitudes of friction forces in the two directions. This effect is observed at all locations of significant changes in topography.

In order to facilitate comparison of directionality effect on friction, it is important to take into account the sign change of the surface slope and friction force in



Fig. 17.18 **(a)** Gray-scale images and two-dimensional profiles of surface height and friction forces across a single ruling of the gold-coated ruling and **(b)** (*see next page*) two-dimensional profiles of surface height and friction forces across a silicon grid pit. Friction force data in trace (T) and retrace (R) directions and substrated force data are presented

the trace and retrace directions. Figure 17.19 shows surface height, surface slope, and friction force data for the two samples in the trace and retrace directions. The correlation between surface slope and friction forces is clear. The third column in the figures shows retrace slope and friction data with an inverted sign (−retrace). Now we can compare trace data with −retrace data. It is clear that the friction experienced by the tip is dependent upon the scanning direction because of surface topography. In addition to the effect of topographical changes discussed earlier, during surface-finishing processes, material can be transferred preferentially onto one side of the asperities, which also causes asymmetry and direction dependence. Reduction in local variations and in directionality of friction properties requires careful optimization of surface roughness distributions and of surface-finishing processes.



Fig. 17.18 b

The directionality as a result of surface asperities effect will also be manifested in macroscopic friction data, i. e., the coefficient of friction may be different in one sliding direction than in the other direction. Asymmetrical shape of asperities accentuates this effect. The frictional directionality can also exist in materials with particles with a preferred orientation. The directionality effect in friction on a macroscale is observed in some magnetic tapes. In a macroscale test, a 12.7-mm wide polymeric magnetic tape was wrapped over an aluminum drum and slid in a reciprocating motion with a normal load of 0.5 N and a sliding speed of about 60 mm/s [17.3]. The coefficient of friction as a function of sliding distance in either direction is shown in Fig. 17.20. We note that the coefficient of friction on a macroscale for this tape varies in different directions. Directionality in friction is sometimes observed on the macroscale; on the microscale this is the norm [17.4, 13]. On the macroscale, the effect of surface asperities is normally averaged out over a large number of contacting asperities.

17.2.4 Velocity Dependence on Microfriction

AFM/FFM experiments are generally conducted at relative velocities as high as a few tens of µm/s. To simulate applications, it is of interest to conduct friction experiments at higher velocities. High velocities can be achieved by mounting either the sample or the cantilever beam on a shear wave transducer (ultrasonic transducer) to produce surface oscillations at MHz frequencies [17.24, 25, 60]. The velocities on the order of a few mm/s can thus be achieved. The effect of in-plane and out-of-plane sample vibration amplitude on the coefficient of friction is shown in Fig. 17.21. Vibration of a sample at ultrasonic frequencies (> 20 kHz) can substantially reduce the coefficient of friction, known as ultrasonic lubrication or sonolubrication. When the surface is vibrated in-plane, classical hydrodynamic lubrication develops hydrodynamic pressure, which supports the tip and reduces friction. When the surface is vibrated out-of-plane, a lift-off caused by the squeeze-film lubrication (a form of hydrodynamic lubrication), reduces friction.



Fig. 17.19 **(a)** Gray-scale images of surface heights, surface slopes, and friction forces for scans across a gold-coated ruling, and **(b)** two-dimensional profiles of surface heights, surface slopes, and friction forces for scans across the silicon grid pit. *Arrows* indicate the tip sliding direction [17.57]



Fig. 17.20 Coefficient of macroscale friction as a function of drum passes for a polymeric magnetic tape sliding over an aluminum drum in a reciprocating mode in both directions. Normal load = 0.5 N over 12.7-mm wide tape, sliding speed = 60 mm/s [17.37]



Fig. 17.21a,b Reduction of coefficient of friction measured at a normal load of 100 nN and average tip separation as a function of surface amplitude on a single-crystal silicon subjected to **(a)** in-plane and **(b)** out-of-plane vibrations at about 1 MHz against a silicon nitride tip [17.24]

17.2.5 Effect of Tip Radii and Humidity on Adhesion and Friction

The tip radius and relative humidity affect adhesion and friction for dry and lubricated surfaces [17.23, 36].

Experimental Observations

Figure 17.22 shows the variation of single-point adhesive-force measurements as a function of tip radius on a Si(100) sample for several humidities. The adhesive force data are also plotted as a function of relative humidity for several tip radii. The general trend at humidities up to the ambient is that a 50-nm radius Si_3N_4 tip exhibits a slightly lower adhesive force compared to the other microtips of larger radii; in the latter case, values are similar. Thus, for the microtips there is no appreciable variation in adhesive force with tip radius at a given humidity up to the ambient. The adhesive force increases as relative humidity increases for all tips.

Sources of adhesive force between a tip and a sample surface are van der Waals attraction and meniscus formation [17.10, 58]. Relative magnitudes of the forces from the two sources are dependent upon various factors, including the distance between the tip and the sample surface, their surface roughness, their hydrophobicity, and relative humidity [17.61]. For most rough surfaces, meniscus contribution dominates at moderate to high humidities, which arise from capillary condensation of water vapor from the environment. If enough liquid is present to form a meniscus bridge, the meniscus force should increase with an increase in tip radius (proportional to tip radius for a spherical tip). In addition, an increase in tip radius results in increased contact area leading to higher values of van der Waals forces. However, if nanoasperities on the tip and the sample are considered, then the number of contacting and near-contacting asperities forming meniscus bridges increases with an increase of humidity leading to an increase in meniscus forces. These explain the trends observed in Fig. 17.22. From the data, the tip radius has little effect on the adhesive forces at low humidities, but increases with tip radius at high humidity. Adhesive force also increases with an increase in humidity for all tips. This observation suggests that thickness of the liquid film at low humidities is insufficient to form continuous meniscus bridges to affect adhesive forces in the case of all tips.

Figure 17.22 also shows the variation in coefficient of friction as a function of tip radius at a given humidity and as a function of relative humidity for a given tip radius for Si(100). It can be observed that for 0% RH, the coefficient of friction is about the same for the tip radii except for the largest tip, which shows a higher value. At all other humidities, the trend consistently shows that the coefficient of friction increases with tip radius. An increase in friction with tip radius at low to moderate humidities arises from increased contact area (higher van der Waals forces) and higher values of shear forces required for larger contact area. At high humidities, similar to adhesive force data, an increase with tip radius occurs due to both contact area and meniscus effects. Although AFM/FFM measurements are able to measure the combined effect of the contribution of van der Waals



Fig. 17.22 Adhesive force and coefficient of friction as a function of tip radius at several humidities and as a function of relative humidity (RH) at several tip radii on Si(100) [17.23]

and meniscus forces toward friction force or adhesive force, it is difficult to measure their individual contributions separately. It can be seen that for all tips, the coefficient of friction increases with humidity to about ambient, beyond which it starts to decrease. The initial increase in the coefficient of friction with humidity arises from the fact that the thickness of the water film increases with an increase in the humidity, which results in a larger number of nanoasperities forming meniscus bridges and leads to higher friction (larger shear force). The same trend is expected with the microtips beyond 65% RH. This is attributed to the fact that at higher humidities, the adsorbed water film on the surface acts as a lubricant between the two surfaces. Thus the interface is changed at higher humidities, resulting in lower shear strength and, hence, lower friction force and coefficient of friction.

Adhesion and Friction Force Expressions for a Single-Asperity Contact

We now obtain the expressions for the adhesive force and coefficient of friction for a single-asperity contact with a meniscus formed at the interface. For a spherical asperity of radius R in contact with a flat and smooth surface with the composite modulus of elasticity E^* and with a concave meniscus, the attractive meniscus force (adhesive force) W_{ad} is given as [17.10, 58]

$$W_{ad} = 2\pi R \gamma_1 (\cos\theta_1 + \cos\theta_2) \ . \tag{17.6}$$

For an elastic contact for both extrinsic (W) and intrinsic (W_{ad}) normal load, the friction force is given as

$$F_e = \pi\tau \left(\frac{3\,(W + W_{ad})\,R}{4E^*}\right)^{2/3} , \tag{17.7}$$

where γ_1 is the surface tension of the liquid in air, θ_1 and θ_2 are the contact angles between the liquid and the two surfaces, W is the external load, and τ is the average shear strength of the contacts. (Surface energy effects are not considered here.) Note that adhesive force increases linearly with an increase in the tip radius, and the friction force increases with an increase in tip radius as $R^{2/3}$ and with normal load as $(W + W_{ad})^{2/3}$. The experimental data in support of $W^{2/3}$ dependence on the friction force can be found in various references (see, for example, [17.62]). The coefficient of friction μ_e is obtained from (17.7) as

$$\begin{aligned}\mu_e &= \frac{F_e}{(W + W_{ad})} \\ &= \pi\tau \left(\frac{3R}{4E^*}\right)^{2/3} \frac{1}{(W + W_{ad})^{1/3}} \ .\end{aligned} \tag{17.8}$$

In the plastic contact regime [17.58], the coefficient of friction μ_p is obtained as

$$\mu_p = \frac{F_p}{(W + W_{ad})} = \frac{\tau}{H_s} , \tag{17.9}$$

where H_s is the hardness of the softer material. Note that in the plastic contact regime, the coefficient of friction is independent of external load, adhesive contributions, and surface geometry.

In comparison, for multiple-asperity contacts in the elastic contact regime, the total adhesive force W_{ad} is the summation of adhesive forces at n individual contacts,

$$W_{ad} = \sum_{i=1}^{n} (W_{ad})_i \quad \text{and}$$

$$\mu_e \approx \frac{3.2\tau}{E^* \left(\sigma_p / R_p\right)^{1/2} + W_{ad}/W} , \tag{17.10}$$

where σ_p and R_p are the standard deviation of summit heights and average summit radius, respectively. Note that the coefficient of friction depends upon the surface roughness. In the plastic contact regime, the expression for μ_p in (17.9) does not change.

The source of the adhesive force, in a wet contact in the AFM experiments being performed in an ambient environment, includes mainly attractive meniscus force due to capillary condensation of water vapor from the environment. The meniscus force for a single contact increases with an increase in tip radius. A sharp AFM tip in contact with a smooth surface at low loads (on the order of a few nN) for most materials can be simulated as a single-asperity contact. At higher loads, for rough and soft surfaces, multiple contacts would occur. Furthermore, at low loads (nN range) for most materials, the local deformation would be primarily elastic. Assuming that shear strength of contacts does not change, the adhesive force for smooth and hard surfaces at low normal load (on the order of few nN) (for a single-asperity contact in the elastic contact regime) would increase with an increase in tip radius, and the coefficient of friction would decrease with an increase in total normal load as $(W + W_{ad})^{-1/3}$ and would increase with an increase of tip radius as $R^{2/3}$. In this case, the Amontons law of friction, which states that the coefficient of friction is independent of normal load and is independent of apparent area of contact, does not hold. For a single-asperity plastic contact and multiple-asperity plastic contacts, neither the normal load nor tip radius come into play in the calculation of the coefficient of friction. In the case of multiple-asperity contacts, the number of contacts increase with an increase of normal load. Therefore, adhesive force increases with an increase in load.

In the data presented earlier in this section, the effect of tip radius and humidity on the adhesive forces and coefficient of friction is investigated for experiments with Si(100) surface at loads in the range of 10–100 nN. The multiple-asperity elastic contact regime is relevant for this study. An increase in humidity generally results in an increase in the number of meniscus bridges that would increase the adhesive force. As suggested earlier, that increase in humidity may also decrease the shear strength of contacts. A combination of an increase in adhesive



Fig. 17.23 (a) Coefficient of friction as a function of normal load and **(b)** corresponding wear depth as a function of normal load for silicon, SiO_2 coating, and natural diamond. Inflections in the curves for silicon and SiO_2 correspond to the contact stresses equal to the hardnesses of these materials [17.63]

Table 17.2 Surface roughness (standard deviation of surface heights or σ) and coefficients of friction on nano- and macroscales of various samples in air

Material	σ (nm)	Coefficient of nanoscale friction versus Si_3N_4 tip[a]	Coefficient of macroscale friction versus Si_3N_4 ball[b]
Graphite (HOPG)	0.09	0.006	0.1
Natural diamond	2.3	0.04	0.2
Si(100)	0.14	0.07	0.4

[a] Tip radius of about 50 nm in the load range of 10–150 nN (2.5–6.1 GPa) and a scanning speed of 0.5 nm/s and scan area of 1 nm × 1 nm for HOPG and a scanning speed of 4 µm/s and scan area of 1 µm × 1 µm for diamond and Si(100)

[b] Ball radius of 3 mm at a normal load of 1 N (0.6 GPa) and average sliding speed of 0.8 mm/s

force and a decrease in shear strength would affect the coefficient of friction. An increase in tip radius would increase the meniscus force (adhesive force). A substantial increase in the tip radius may also increase interatomic forces. These effects influence the coefficient of friction with an increase in the tip radius.

17.2.6 Scale Dependence on Friction

Table 17.2 shows the coefficient of friction measured for various materials on nano- and macroscales [17.19]. It is clearly observed that friction values are scale-dependent. The values on the nano/microscale are much lower than those on the macroscale. There can be the following four, and possibly more, differences in the operating conditions responsible for these differences. First, the contact stresses at AFM conditions, in spite of small tip radii, generally do not exceed the sample hardness that minimizes plastic deformation. Average contact stresses in macrocontacts are generally lower than in AFM contacts, however, a large number of asperities come into contact that go through some plastic deformation. Second, when measured for the small contact areas and very low loads used in microscale studies, indentation hardness is higher than at the macroscale, as will be discussed later [17.11, 34, 35]. Lack of plastic deformation and improved mechanical properties reduce the degree of wear and friction. Third, the small apparent area of contact reduces the number of particles trapped at the interface, and thus minimizes the third-body plowing contribution to the friction force [17.11]. As a fourth and final difference, we have seen in the previous section that coefficient of friction increases with an increase in the AFM tip radius. AFM data are taken with a sharp tip, whereas asperities coming in contact in macroscale tests range from nanoasperities to much larger asperities, which may be responsible for larger values of friction force on the macroscale.

To demonstrate the load dependence on the coefficient of friction, stiff cantilevers were used to conduct friction experiments at high loads, see Fig. 17.23 [17.63]. At higher loads (with contact stresses exceeding the hardness of the softer material), as anticipated, the coefficient of friction for microscale measurements increases toward values comparable to those obtained from macroscale measurements, and surface damage also increases. At high loads, plowing is a dominant contributor to the friction force. Based on these results, Amontons rule of friction, which states that the coefficient of friction is independent of apparent area and normal load, does not hold for microscale measurements. These findings also suggest that microcomponents sliding under lightly loaded conditions should experience ultralow friction and near-zero wear [17.11].

17.3 Scratching, Wear, Local Deformation, and Fabrication/Machining

17.3.1 Nanoscale Wear

Bhushan and *Ruan* [17.18] conducted nanoscale wear tests on polymeric magnetic tapes using conventional silicon nitride tips at two different loads of 10 and 100 nN (Fig. 17.24). For a low normal load of 10 nN, measurements were made twice. There was no discernible difference between consecutive measurements for this load. However, as the load was increased from 10 nN to 100 nN, topographical changes were ob-



Fig. 17.24 Surface roughness maps of a polymeric magnetic tape at the applied normal load of 10 nN and 100 nN. Location of the change in surface topography as a result of nanowear is indicated by *arrows* [17.18]



Fig. 17.25a,b Surface plots of **(a)** Si(111) scratched for 10 cycles at various loads and a scanning velocity of 2 µm/s. Note that x and y axes are in µm and z axis is in nm. **(b)** Si(100) scratched in one unidirectional scan cycle at a normal force of 80 µN and different scanning velocities

served during subsequent scanning at a normal load of 10 nN; material was pushed in the sliding direction of the AFM tip relative to the sample. The material movement is believed to occur as a result of plastic deformation of the tape surface. Thus, deformation and movement of the soft materials on a nanoscale can be observed.

17.3.2 Microscale Scratching

The AFM can be used to investigate how surface materials can be moved or removed on micro- to nanoscales, for example, in scratching and wear [17.4] (where these things are undesirable), and nanofabrication/nanomachining (where they are desirable). Figure 17.25a shows microscratches made on Si(111) at various loads and scanning velocity of 2 µm/s after 10 cycles [17.22]. As expected, the scratch depth increases linearly with load. Such microscratching measurements can be used to study failure mechanisms on the microscale and evaluate the mechanical integrity (scratch resistance) of ultrathin films at low loads.

To study the effect of scanning velocity, unidirectional scratches, 5 µm in length, were generated at scanning velocities ranging from 1–100 µm/s at various normal loads ranging from 40–140 µN. There is no effect of scanning velocity obtained at a given normal load. (For representative scratch profiles at 80 µN, see Fig. 17.25b.) This may be because of a small effect of frictional heating with the change in scanning velocity used here. Furthermore, for a small change in interface temperature, there is a large underlying volume to dissipate the heat generated during scratching.

Scratching can be performed under ramped loading to determine the scratch resistance of materials and



Fig. 17.26 **(a)** Applied normal load and friction signal measured during the microscratch experiment on Si(100) as a function of scratch distance, **(b)** friction data plotted in the form of coefficient of friction as a function of normal load, and **(c)** AFM surface height image of scratch obtained in tapping mode [17.33]

coatings. The coefficient of friction is measured during scratching, and the load at which the coefficient of friction increases rapidly is known as the "critical load", which is a measure of scratch resistance. In addition, post-scratch imaging can be performed in situ with the AFM in tapping mode to study failure mechanisms. Figure 17.26 shows data from a scratch test on Si(100) with a scratch length of 25 µm and a scratching velocity of 0.5 µm/s. At the beginning of the scratch, the coefficient of friction is 0.04, which indicates a typical value for silicon. At about 35 µN (indicated by the arrow in the figure), there is a sharp increase in the coefficient of friction, which indicates the critical load. Beyond the critical load, the coefficient of friction continues to increase steadily. In the post-scratch image, we note that at the critical load, a clear groove starts to form. This implies that Si(100) was damaged by plowing at the critical load, associated with the plastic flow of the material. At and after the critical load, small and uniform debris is observed and the amount of debris increases with increasing normal load. *Sundararajan* and *Bhushan* [17.33] have also used this technique to measure the scratch resistance of diamond-like carbon coatings ranging in thickness from 3.5–20 nm.

17.3.3 Microscale Wear

By scanning the sample in two dimensions with the AFM, wear scars are generated on the surface. Figure 17.27 shows the effect of normal load on wear depth. We note that wear depth is very small below 20 µN of normal load [17.64, 65]. A normal load of 20 µN corresponds to contact stresses comparable



Fig. 17.27 Wear depth as a function of normal load for Si(100) after one cycle [17.65]

to the hardness of the silicon. Elastic deformation at loads below 20 µN is primarily responsible for low wear [17.63].

A typical wear mark, of the size 2 µm × 2 µm, generated at a normal load of 40 µN for one scan cycle and imaged using AFM with scan size of 4 µm × 4 µm at 300 nN load is shown in Fig. 17.28a [17.64]. The inverted map of wear marks shown in Fig. 17.28b indicates the uniform material removal at the bottom of the wear mark. An AFM image of the wear mark shows small debris at the edges, swiped during AFM scanning. Thus, the debris is loose (not sticky) and can be removed during the AFM scanning.

Next, we examine the mechanism of material removal on a microscale in AFM wear experiments [17.23, 64, 65]. Figure 17.29 shows a secondary electron image of the wear mark and associated wear particles. The specimen used for the scanning electron microscope (SEM) was not scanned with the AFM after initial wear, in order to retain wear debris in the wear region. Wear debris is clearly observed. In the SEM micrographs, the wear debris appear to be agglomerated because of high surface energy of the fine particles. Particles appear to be a mixture of rounded and so-called cutting type (feather-like or ribbon-like material). *Zhao* and *Bhushan* [17.65] reported an increase in the number and size of cutting-type particles with the normal load. The presence of cutting-type particles indicates that the material is removed primarily by plastic deformation.



Fig. 17.28 **(a)** Typical gray-scale and **(b)** inverted AFM images of wear mark created using a diamond tip at a normal load of 40 µN and one scan cycle on Si(100) surface



Fig. 17.29 Secondary electron image of wear mark and debris for Si(100) produced at a normal load of 40 µN and one scan cycle

To better understand the material removal mechanisms, transmission electron microscopy (TEM) has been used. The TEM micrograph of the worn region and associated diffraction pattern are shown in Fig. 17.30a,b. The bend contours are observed to pass through the wear mark in the micrograph. The bend contours around and inside the wear mark are indicative of a strain field, which, in the absence of applied stresses, can be interpreted as plastic deformation and/or elastic residual stresses. Often, localized plastic deformation during loading would lead to residual stresses during unloading; therefore, bend contours reflect a mix of elastic and plastic strains. The wear debris is observed outside the wear mark. The enlarged view of the wear debris in Fig. 17.30c shows that much of the debris is ribbon-like, indicating that material is removed by a cutting process via plastic deformation, which is consistent with the SEM observations. The diffraction pattern from inside the wear mark is similar to that of virgin silicon, showing no evidence of any phase transformation (amorphization) during wear. A selected area diffraction pattern of the wear debris shows some diffuse rings, which indicates the existence of amorphous



Fig. 17.30a–d Bright field TEM micrographs (*left*) and diffraction patterns (*right*) of wear mark **(a)**,**(b)** and wear debris **(c)**,**(d)** in Si(100) produced at a normal load of 40 µN and one scan cycle. Bend contours around and inside wear mark are observed



Fig. 17.31 **(a)** Bright field and **(b)** weak beam TEM micrographs of wear mark in Si(100) produced at a normal load of 80 µN and one scan cycle showing bend contours and dislocations [17.65]

material in the wear debris, confirmed as silicon oxide products from chemical analysis. It is known that plastic deformation occurs by generation and propagation of dislocations. No dislocation activity or cracking was observed at 40 µN. However, dislocation arrays could be observed at 80 µN. Figure 17.31 shows the TEM micrographs of the worn region at 80 µN; for better observation of the worn surface, wear debris was moved out of the wear mark using AFM with a large area scan at 300 nN after the wear test. The existence of dislocation arrays confirms that material removal occurs by plastic deformation. This corroborates the observations made in scratch tests at ramped load in the previous section. It is concluded that the material on microscale at high loads is removed by plastic deformation with a small contribution from elastic fracture [17.65].

To understand wear mechanisms, evolution of wear can be studied using AFM. Figure 17.32 shows evolution of wear marks of a DLC-coated disk sample. The data illustrate how the microwear profile for a load of 20 µN develops as a function of the number of scanning cycles [17.22]. Wear is not uniform, but is initiated at the nanoscratches. Surface defects (with high surface energy) present at nanoscratches act as initiation sites for wear. Coating deposition also may not be uniform on and near nanoscratches, which may lead to coating delamination. Thus, scratch-free surfaces will be relatively resistant to wear.

Wear precursors (precursors to measurable wear) can be studied by making surface potential measurements [17.38–40]. The contact potential difference, or simply surface potential between two surfaces, depends on a variety of parameters such as electronic work function, adsorption, and oxide layers. The surface potential map of an interface gives a measure of changes in the work function, which is sensitive to both physical and chemical conditions of the surfaces, including structural and chemical changes. Before material is actually removed in a wear process, the surface experiences stresses that result in surface and subsurface changes of structure and/or chemistry. These can cause changes in the measured potential of a surface. An AFM tip allows mapping of surface potential with nanoscale resolution. Surface height and change in surface potential maps of a polished single-crystal aluminum (100) sample abraded using a diamond tip at loads of 1 µN and 9 µN are shown in Fig. 17.33a. (Note that the sign of the change in surface potential is reversed here from that in [17.38].) It is evident that both abraded regions show a large potential contrast (∼ 0.17 V) with respect



Fig. 17.32 Surface plots of diamond-like carbon-coated thin-film disk showing the worn region; the normal load and number of test cycles are indicated [17.22]

to the non-abraded area. The black region in the lower right-hand part of the topography scan shows a step that was created during the polishing phase. There is no potential contrast between the high region and the low region of the sample, indicating that the technique is independent of surface height. Figure 17.33b shows a close-up scan of the upper (low load) wear region in Fig. 17.33a. Notice that while there is no detectable change in the surface topography, there is, nonetheless, a large change in the potential of the surface in the worn region. Indeed, the wear mark of Fig. 17.33b might not have been visible at all in the topography map were it not for the noted absence of wear debris generated nearby and then swept off during the low load scan. Thus, even in the case of zero wear (no mea-



Fig. 17.33 **(a)** Surface height and change in surface potential maps of wear regions generated at 1 µN (*top*) and 9 µN (*bottom*) on a single-crystal aluminum sample showing bright contrast in the surface potential map on the worn regions. **(b)** Close up of upper (low load) wear region [17.38]

surable deformation of the surface using AFM), there can be a significant change in the surface potential inside the wear mark, which is useful for the study of wear precursors. It is believed that the removal of the thin contaminant layer including the natural oxide layer gives rise to the initial change in surface potential. The structural changes, which precede generation of wear debris and/or measurable wear scars, occur under ultralow loads in the top few nanometers of the sample and are primarily responsible for the subsequent changes in surface potential.

17.3.4 In Situ Characterization of Local Deformation

In situ surface characterization of local deformation of materials and thin films is carried out using a tensile stage inside an AFM. Failure mechanisms of polymeric thin films were studied by *Bobji* and *Bhushan* [17.41, 42]. The specimens were strained at a rate of $4\times10^{-3}\%$ per second, and AFM images were captured at different strains up to about 10% to monitor generation and propagation of cracks and deformation bands.

Bobji and *Bhushan* [17.41, 42] studied three magnetic tapes with thickness ranging from 7 to 8.5 µm. One of these was with acicular-shaped metal particle (MP) coating, and the other two with metal-evaporated (ME) coating and with and without a thin diamond-like carbon (DLC) overcoat, both on a polymeric substrate and all with particulate back coating [17.13]. They also studied the polyethylene terephthalate (PET) substrate with 6 µm thickness. They reported that cracking of the coatings started at about 1% strain for all tapes, much before the substrate starts to yield at about 2% strain. Figure 17.34 shows the topographical images of the MP tape at different strains. At 0.83% strain, a crack can be seen originating at the marked point. As the tape is further stretched along the direction, as shown in Fig. 17.34, the crack propagates along the shorter boundary of the ellipsoidal particle. However, the general direction of the crack propagation remains perpendicular to the direction of the stretching. The length, width, and depth of the cracks increase with strain, and at the same time, newer cracks keep on nucleating and propagating with reduced crack spacing. At 3.75% strain, another crack can be seen nucleating. This crack continues to grow parallel to the first. When the tape is unloaded after stretching up to a strain of about 2%, i. e., within the elastic limit of the substrate, the cracks rejoin perfectly and it is impossible to determine the difference from the unstrained tape.



Fig. 17.34 Topographical images of the MP magnetic tape at different strains [17.41]

Figure 17.35 shows topographical images of the three magnetic tapes and the PET substrate after being strained to 3.75%, which is well beyond the elastic limit of the substrate. MP tape develops short and numerous cracks perpendicular to the direction of loading. In tapes with metallic coating, the cracks extend throughout the tape width. In ME tape with DLC coating, there is a bulge in the coating around the primary cracks that are initiated when the substrate is still elastic, like crack A in the figure. The white band on the right-hand side of the figure is the bulge of another crack. The secondary cracks like B and C are generated at higher strains and are straighter compared to the primary cracks. In ME tape, which has a Co-O film on PET substrate, with a thickness ratio of 0.03, both with and without DLC coating, no difference is observed in the rate of growth between primary and secondary cracks. The failure is cohesive with no



Fig. 17.35 Comparison of crack morphologies at 3.75% strain in three magnetic tapes and PET substrate. Cracks B and C, nucleated at higher strains, are more linear than crack A [17.42]

bulging of the coating. This seems to suggest that the DLC coating has residual stresses that relax when the coating cracks, causing delamination. Since the stresses are already relaxed, the secondary crack does not result in delamination. The presence of the residual stress is confirmed by the fact that a freestanding ME tape curls up (in a cylindrical form with its axis perpendicular to the tape length) with a radius of curvature of about 6 mm; the ME tape without the DLC does not curl. The magnetic coating side of PET substrate is much smoother at smaller scan lengths. However, in 20 µm scans it has a lot of bulging out, which appears as white spots in the figure. These spots change shape even while scanning the samples in tapping mode at very low contact forces.

The variation of average crack width and average crack spacing with strain is plotted in Fig. 17.36. The crack width is measured at a spot along a given crack over a distance of 1 µm in the 5 µm scan image at different strains. The crack spacing is obtained by averaging the inter-crack distance measured in five separate 50 µm scans at each strain. It can be seen that the cracks nucleate at a strain of about 0.7–1.0%, well within the elastic limit of the substrate. There is a definite change in the slope of the load-displacement curve at the strain where cracks nucleate, and the slope after that is closer to the slope of the elastic portion of the substrate. This would mean that most of the load is supported by the substrate once the coating fails by cracking.

In situ surface characterization of unstretched and stretched films has been used to measure Poisson's ratio of polymeric thin films [17.66]. Uniaxial tension is applied by the tensile stage. Surface height profiles obtained from the AFM images of unstretched and stretched samples are used to monitor simultaneously the changes in displacements of the polymer films in the longitudinal and lateral directions.



Fig. 17.36 Variation of stress, crack width, and crack spacing with strain in three magnetic tapes and PET substrate [17.41]



Fig. 17.37 **(a)** Trim and **(b)** spiral patterns generated by scratching a Si(100) surface using a diamond tip at a normal load of 15 µN and writing speed of 0.5 µm/s

17.3.5 Nanofabrication/Nanomachining

An AFM can be used for nanofabrication/nanomachining by extending the microscale scratching operation [17.4, 11,22,37]. Figure 17.37 shows two examples of nanofabrication. The patterns were created on a single-crystal silicon (100) wafer by scratching the sample surface with a diamond tip at specified locations and scratching angles. Each line is scribed manually at a normal load of 15 µN and a writing speed of 0.5 µm/s. The separation between lines is about 50 nm, and the variation in line width is due to the tip asymmetry. Nanofabrication parameters – normal load, scanning speed, and tip geometry – can be controlled precisely to control the depth and length of the devices.

Nanofabrication using mechanical scratching has several advantages over other techniques. Better control over the applied normal load, scan size, and scanning speed can be used for nanofabrication of devices. Using the technique, nanofabrication can be performed on any engineering surface. Use of chemical etching or reactions is not required, and this dry nanofabrication process can be used where use of chemicals and electric field is prohibited. One disadvantage of this technique is the formation of debris during scratching. At light loads, debris formation is not a problem compared to high-load scratching. However, debris can be removed easily from the scan area at light loads during scanning.

17.4 Indentation

Mechanical properties such as hardness and Young's modulus of elasticity can be determined on micro- to picoscales using the AFM [17.18,22,31,34] and a depth-sensing indentation system used in conjunction with an AFM [17.35,67–69].

17.4.1 Picoindentation

Indentability on the scale of subnanometers of soft samples can be studied in the force calibration mode (Fig. 17.6) by monitoring the slope of cantilever deflection as a function of sample traveling distance after the tip is engaged and the sample is pushed against the tip. For a rigid sample, cantilever deflection equals the sample traveling distance, but the former quantity is smaller if the tip indents the sample. In an example of a polymeric magnetic tape shown in Fig. 17.38, the line in the left portion of the figure is curved with a slope of less than 1 shortly after the sample touches the tip, which suggests that the tip has indented the sample [17.18]. Later, the slope is equal to 1, suggesting that the tip no longer indents the sample. This observation indicates that the tape surface is soft locally (polymer-rich) but hard (as a result of magnetic particles) underneath. Since



Fig. 17.38 Tip deflection (normal load) as a function of the Z (separation distance) curve for a polymeric magnetic tape [17.18]

the curves in extending and retracting modes are identical, the indentation is elastic up to a maximum load of about 22 nN used in the measurements.

Detection of transfer of material on a nanoscale is possible with the AFM. Indentation of C_{60}-rich fullerene films with an AFM tip has been shown [17.70] to result in the transfer of fullerene molecules to the AFM tip, as indicated by discontinuities in the cantilever deflection as a function of sample traveling distance in subsequent indentation studies.

17.4.2 Nanoscale Indentation

The indentation hardness of surface films with an indentation depth as small as about 1 nm can be measured using an AFM [17.11, 34, 35]. Figure 17.39 shows the gray-scale plots of indentation marks made on Si(111) at normal loads of 60, 65, 70, and 100 µN. Triangular indents can be clearly observed with very shallow depths. At a normal load of 60 µN, indents are observed and the depth of penetration is about 1 nm. As the normal load is increased, the indents become clearer and indentation depth increases. For the case of hardness measurements at shallow depths on the same order as variations in surface roughness, it is desirable to subtract the original (unindented) map from the indent map for accurate measurement of the indentation size and depth [17.22].


60 µN,
1.0 nm
40.0 nm
20.0
0
0
250
500 nm
0
250
500
20.0 nm
10.0 nm
0.0 nm
65 µN,
2.5 nm,
16.6 GPa
40.0 nm
20.0
0
0
250
500 nm
0
250
500
20.0 nm
10.0 nm
0.0 nm
70 µN,
3.0 nm,
15.8 GPa
40.0 nm
20.0
0
0
250
500 nm
0
250
500
20.0 nm
10.0 nm
0.0 nm
100 µN,
7.0 nm,
11.7 GPa
40.0 nm
20.0
0
0
250
500 nm
0
250
500
20.0 nm
10.0 nm
0.0 nm

Fig. 17.39 Gray-scale plots of indentation marks on the Si(111) sample at various indentation loads. Loads, indentation depths, and hardness values are listed in the figure [17.34]

To make accurate measurements of hardness at shallow depths, a depth-sensing indentation system is used [17.35]. Figure 17.40 shows the load-displacement curves at different peak loads for Si(100). Loading/unloading curves often exhibit sharp discontinuities, particularly at high loads. Discontinuities, referred to as pop-ins, during the initial loading part of the curve mark a sharp transition from pure elastic loading to a plastic deformation of the specimen surface, thus correspond-



Fig. 17.40 Load-displacement curves at various peak loads for Si(100) [17.35]

ing to an initial yield point. The sharp discontinuities in the unloading part of the curves are believed to be due to the formation of lateral cracks that form at the base of the median crack, which results in the surface of the specimen being thrust upward. Load-displacement data at residual depths as low as about 1 nm can be obtained, and the indentation hardness of surface films has been measured for Si(100) [17.35, 67–69]. The hardness of silicon on a nanoscale is found to be higher than on a microscale (Fig. 17.41). Microhardness has also been reported to be higher than on the millimeter scale by several investigators. The data reported to date show that hardness exhibits size effect. According to the strain gradient plasticity theory advanced by *Fleck* et al. [17.71], large strain gradients inherent in small indentations lead to the accumulation of geometrically necessary dislocations for strain compatibility reasons that cause enhanced hardening. In addition, the decrease in hardness with an increase in indentation depth can possibly be rationalized on the basis that as the volume of deformed material increases, there is a higher probability of encountering material defects.



Fig. 17.41 Indentation hardness as a function of residual indentation depth for Si(100) [17.35]

Bhushan and *Koinkar* [17.31] have used AFM measurements to show that ion implantation of silicon surfaces increases their hardness and thus their wear resistance. Formation of surface alloy films with improved mechanical properties by ion implantation is of growing technological importance as a means of improving the mechanical properties of materials. Hardness of 20 nm-thick diamond-like carbon films has been measured by *Kulkarni* and *Bhushan* [17.69].

The creep and strain-rate effects (viscoelastic effects) of ceramics can be studied using a depth-sensing indentation system. *Bhushan* et al. [17.35] and *Kulkarni* and *Bhushan* [17.67–69] have reported that ceramics exhibit significant plasticity and creep on a nanoscale. Figure 17.42a shows the load-displacement curves for single-crystal silicon at various peak loads held at 180 s. To demonstrate the creep effects, the load-displacement curves for a 500 µN peak load held at 0 and 30 s are also shown as an inset. Note that significant creep occurs at room temperature. Nanoindenter experiments conducted by *Li* et al. [17.72] exhibited significant creep only at high temperatures (greater than or equal to 0.25 times the melting point of silicon). The mechanism of dislocation glide plasticity is believed to dominate the indentation creep process on the macroscale. To study the strain-rate sensitivity of silicon, data at two different (constant) rates of loading are presented in Fig. 17.42b. Note that a change in the loading rate by a factor of about five results in a significant change in the load-displacement data. The viscoelastic effects observed here for silicon at ambient temperature could arise from size effects mentioned earlier. Most likely, creep and strain rate experiments are being conducted on the hydrated films present on the silicon surface in ambient environment, and these films are expected to be viscoelastic.

17.4.3 Localized Surface Elasticity and Viscoelasticity Mapping

The Young's modulus of elasticity is calculated from the slope of the indentation curve during unloading. However, these measurements provide a single-point measurement. By using the force modulation technique, it is possible to get localized elasticity maps of soft and



Fig. 17.42 **(a)** Creep behavior and **(b)** strain-rate sensitivity of Si(100) [17.35]

compliant materials with penetration depths of less than 100 nm. This technique has been successfully used for polymeric magnetic tapes, which consist of magnetic and nonmagnetic ceramic particles in a polymeric matrix. Elasticity maps of a tape can be used to identify relative distribution of hard magnetic and nonmagnetic ceramic particles on the tape surface, which has an effect on friction and stiction at the head-tape interface [17.13]. Figure 17.43 shows surface height and elasticity maps on a polymeric magnetic tape [17.44]. The elasticity image reveals sharp variations in surface elasticity due to the composite nature of the film. As can be clearly seen, regions of high elasticity do not always correspond to high or low topography. Based on a Hertzian elastic-contact analysis, the static indentation depth of these samples during the force modulation scan is estimated to be about 1 nm. We conclude that the contrast seen is influenced most strongly by material properties in the top few nanometers, independent of the composite structure beneath the surface layer.

By using phase contrast microscopy, it is possible to get phase contrast maps or the contrast in viscoelastic properties of near surface regions. This technique has been used successfully for polymeric films and magnetic tapes that consist of ceramic particles in a polymeric matrix [17.51, 52]. Figure 17.44 shows topography, phase angle, and friction force images for polyethylene terephthalate (PET) film. Three particles, which show up as approximately circular, lightly shaded (high points) regions, are seen in the topography image. In the phase angle images, the particles show up dark against the film background. A combination of high tapping amplitude and low set point was found to maximize contrast in phase images. This result may be explained by the degree to which the tip is able to penetrate and thus deform the sample. A high tapping amplitude and low set point should maximize the force with which the tip strikes the sample. This should give more penetration. So the mater-



Fig. 17.43 Surface height and elasticity maps on a polymeric magnetic tape ($\sigma = 6.72$ nm and P-V $= 31.7$ nm; σ and P-V refer to standard deviation of surface heights and peak-to-valley distance, respectively). The gray scale on the elasticity map is arbitrary [17.44]



Fig. 17.44 Tapping mode height and phase angle images acquired using a TESP tip at a tapping amplitude of 190 nm and a setpoint of 40% (74 nm), and contact mode height and friction force (trace) images using an MESP tip with a normal load between 9 and 47 nN for PET film with embedded ceramic particles [17.51]

ial or viscoelastic contribution, as opposed to the surface force and adhesion hysteresis contributions, should be more dominant for this tapping condition. The phase angle image shown in Fig. 17.44 was acquired using tapping mode with a relatively high tapping amplitude of 190 nm and a relatively low set point of 40% (of the tapping amplitude) to emphasize viscoelastic properties. Very little correlation is found between the phase angle and friction force images. Friction force images were obtained using an etched single-crystal silicon tip (DI MESP) with a radius of 20–50 nm, a stiffness of 1–5 N/m, and a natural frequency of 60–70 kHz. A lack of correlation may be a further indication that something other than adhesion, which should correlate to friction force, causes the phase angle contrast; this may imply that viscoelastic properties may be dominant. These results also indicate that phase angle imaging yields information that cannot be obtained using other, more conventional AFM modes.

17.5 Boundary Lubrication

17.5.1 Perfluoropolyether Lubricants

The classical approach to lubrication uses freely supported multimolecular layers of liquid lubricants [17.10, 13, 58, 73]. The liquid lubricants are sometimes chemically bonded to improve their wear resistance [17.10, 13, 58]. Partially chemically bonded, molecularly thick perfluoropolyether (PFPE) films are used for lubrication of magnetic storage media [17.13]. These are considered potential candidate lubricants for micro/nanoelectromechanical systems (MEMS/NEMS). Molecularly thick PFPEs are well suited because of the following properties: low surface tension and low contact angle, which allow easy spreading on surfaces and provide hydrophobic properties; chemical and thermal stability, which minimize degradation under use; low vapor pressure, which provides low out-gassing; high adhesion to substrate via organic functional bonds; and good lubricity, which reduces contact surface wear.

For boundary lubrication studies, friction, adhesion, and durability experiments have been performed on virgin Si(100) surfaces and silicon surfaces lubricated with two PFPE lubricants – Z-15 (with $-\mathrm{CF_3}$ nonpolar end groups) and Z-DOL (with −OH polar end groups) [17.27, 28, 30]. Z-DOL film was thermally bonded at 150 °C for 30 minutes and an unbonded fraction was removed by a solvent (BW) [17.13]. The thicknesses of Z-15 and Z-DOL films were 2.8 nm and 2.3 nm, respectively.

The adhesive forces of Si(100), Z-15, and Z-DOL (BW) measured by force calibration plot and friction force versus normal load plot are summarized in Fig. 17.45. The results measured by these two methods are in good agreement. Figure 17.45 shows that the presence of mobile Z-15 lubricant film increases the adhesive force as compared to that of Si(100) by meniscus formation. The presence of solid phase Z-DOL (BW) film reduces the adhesive force as compared to that of

Si(100) because of the absence of mobile liquid. The schematic (bottom) in Fig. 17.45 shows relative size and sources of meniscus. It is well-known that the native oxide layer (SiO_2) on the top of a Si(100) wafer exhibits hydrophilic properties, and some water molecules can be adsorbed on this surface. The condensed water will form meniscus as the tip approaches the sample surface. The larger adhesive force in Z-15 is not only caused by the Z-15 meniscus; the nonpolarized Z-15 liquid does not have good wettability and strong bonding with Si(100). In the ambient environment, the condensed water molecules from the environment will permeate through the liquid Z-15 lubricant film and compete with the lubricant molecules present on the substrate. The interaction of the liquid lubricant with the substrate is weakened, and a boundary layer of the liquid lubricant forms puddles [17.27,28]. This de-wetting allows water molecules to be adsorbed on the Si(100) surface as aggregates along with Z-15 molecules. And both of them can form meniscus while the tip approaches the surface. Thus, the de-wetting of liquid Z-15 film results in higher adhesive force and poorer lubrication performance. In addition, as the Z-15 film is pretty soft compared to the solid Si(100) surface, and penetration of the tip in the film occurs while pushing the tip down. This leads the large area of the tip involved to form the meniscus at the tip-liquid (mixture of Z-15 and water) interface. It should also be noted that Z-15 has a higher viscosity compared to water and, therefore, Z-15 film provides higher resistance to motion and coefficient of friction. In the case of Z-DOL (BW) film, both of the active groups of Z-DOL molecules are mostly bonded on Si(100) substrate. Thus, the Z-DOL (BW) film has low free surface energy and cannot be displaced readily by water molecules or readily adsorb water molecules. Therefore, the use of Z-DOL (BW) can reduce the adhesive force.



Fig. 17.45 Summary of the adhesive forces of Si(100) and Z-15 and Z-DOL (BW) films measured by force calibration plots and friction force versus normal load plots in ambient air. The schematic (*bottom*) showing the effect of meniscus formed between the AFM tip and surface sample on the adhesive and friction forces [17.30]

To study the velocity effect on friction and adhesion, the variation of friction force, adhesive force, and coefficient of friction of Si(100), Z-15 and Z-DOL (BW) as a function of velocity are summarized in Fig. 17.46. It indicates that for silicon wafer the friction force decreases logarithmically with increasing velocity. For Z-15, the friction force decreases with increasing velocity up to 10 μm/s, after which it remains almost constant. The velocity has very small effect on the friction force of Z-DOL (BW): It reduced slightly only at very high velocity. Figure 17.46 also indicates that the adhesive force of Si(100) increases when the velocity is higher than 10 μm/s. The adhesive force of Z-15 is reduced dramatically with a velocity increase up to 20 μm/s, after which it is reduced slightly. And the adhesive force of Z-DOL (BW) also decreases at high velocity. In the testing range of velocity, only the coefficient of friction of Si(100) decreases with velocity, but the coefficients of friction of Z-15 and Z-DOL (BW) almost remain constant. This implies that the friction mechanisms of Z-15 and Z-DOL (BW) do not change with the variation of velocity.

The mechanisms of the effect of velocity on the adhesion and friction are explained based on schematics shown in Fig. 17.46 (right). For Si(100), tribochemical reaction plays a major role. Although at high velocity the meniscus is broken and does not have enough time to rebuild, the contact stresses and high velocity lead to tribochemical reactions of Si(100) wafer (which has native oxide (SiO_2)) and a Si_3N_4 tip with water molecules and form $Si(OH)_4$. The $Si(OH)_4$ is removed and continuously replenished during sliding. The $Si(OH)_4$ layer between the tip and Si(100) surface is known to be of low shear strength and causes a decrease in friction force and



Fig. 17.46 The influence of velocity on the friction force, adhesive force, and coefficient of friction of Si(100) and Z-15 and Z-DOL (BW) films at 70 nN, in ambient air. The schematic (*right*) shows the change of surface composition (by tribochemical reaction) and formation of meniscus while increasing the velocity [17.30]

coefficient of friction [17.10,58]. The chemical bonds of Si−OH between the tip and Si(100) surface induce large adhesive force. For Z-15 film, at high velocity the meniscus formed by condensed water and Z-15 molecules is broken and does not have enough time to rebuild. Therefore, the adhesive force and, consequently, friction force are reduced. The friction mechanism for Z-15 film still is shearing the same viscous liquid even at high velocity range, thus, the coefficient of friction of Z-15 does not change with velocity. For Z-DOL (BW) film, the surface can adsorb few water molecules in ambient condition, and at high velocity these molecules are displaced, which causes a slight decrease in friction and adhesive forces. *Koinkar* and *Bhushan* [17.27,28] have suggested that in the case of samples with mobile films such as condensed water and Z-15 films, alignment of liquid molecules (shear thinning) is responsible for the drop in friction force with an increase in scanning velocity. This could be another reason for the decrease in friction force for Si(100) and Z-15 film with velocity in this study.

To study the relative humidity effect on friction and adhesion, the variations of friction force, adhesive force,



Fig. 17.47 The influence of relative humidity (RH) on the friction force, adhesive force, and coefficient of friction of Si(100) and Z-15 and Z-DOL (BW) films at 70 nN, 2 µm/s, and in 22 °C air. Schematic (*right*) shows the change of meniscus while increasing the relative humidity. In this figure, the thermally treated Si(100) represents the Si(100) wafer that was baked at 150 °C for 1 hour in an oven (in order to remove the adsorbed water) just before it was placed in the 0% RH chamber [17.30]

and coefficient of friction of Si(100), Z-15, and Z-DOL (BW) as a function of relative humidity are shown in Fig. 17.47. It shows that for Si(100) and Z-15 film, the friction force increases with a relative humidity increase of up to 45%, and then slightly decreases with a further increase in the relative humidity. Z-DOL (BW) has a smaller friction force than Si(100) and Z-15 in the whole testing range. And its friction force shows a relative apparent increase when the relative humidity is higher than 45%. For Si(100), Z-15, and Z-DOL (BW), their adhesive forces increase with relative humidity, and their coefficients of friction increase with relative humidity up to 45%, after which they decrease with further increasing of the relative humidity. It is also observed that the humidity effect on Si(100) really depends on the history of the Si(100) sample. As the surface of Si(100) wafer readily adsorbs water in air, without any pre-treatment the Si(100) used in our study almost



Fig. 17.48 The influence of temperature on the friction force, adhesive force, and coefficient of friction of Si(100) and Z-15 and Z-DOL (BW) films at 70 nN, at 2 µm/s, and in RH 40–50% air. The schematic (*right*) shows that at high temperature desorption of water decreases the adhesive forces. And the reduced viscosity of Z-15 leads to the decrease of the coefficient of friction. High temperature facilitates orientation of molecules in Z-DOL (BW) film, which results in lower coefficient of friction [17.30]

reaches to its saturate stage of adsorbed water and is responsible for less effect during increasing relative humidity. However, once the Si(100) wafer was thermally treated by baking at 150 °C for 1 hour, a bigger effect was observed.

The schematic in Fig. 17.47 (right) shows that Si(100), because its high free surface energy, can adsorb more water molecules with increasing relative humidity. As discussed earlier, for Z-15 film in the humid environment, the condensed water from the humid environment competes with the lubricant film present on the sample surface, interaction of the liquid lubricant film with the silicon substrate is weakened, and a boundary layer of the liquid lubricant forms puddles. This dewetting allows water molecules to be adsorbed on the Si(100) substrate mixed with Z-15 molecules [17.27, 28]. Obviously, more water molecules can be adsorbed on Z-15 surface while increasing relative humidity. The more adsorbed water molecules in the case of Si(100), along with lubricant molecules in Z-15 film case, form bigger water meniscus which leads to an increase of friction force, adhesive force, and coefficient of friction of Si(100) and Z-15 with humidity. But at a very high humidity of 70%, large quantities of adsorbed water can form a water layer that separates the tip and sample surface and act as a kind of lubricant, which causes a decrease in the friction force and coefficient of friction. For Z-DOL (BW) film, because of its hydrophobic surface properties, water molecules can be adsorbed at a humidity higher than 45% and causes an increase in the adhesive and friction forces.

To study the temperature effect on friction and adhesion, the variations of friction force, adhesive force, and coefficient of friction of Si(100), Z-15, and Z-DOL (BW) as a function of temperature are summarized in Fig. 17.48. It shows that the increasing temperature causes a decrease in friction force, adhesive force, and coefficient of friction of Si(100), Z-15, and Z-DOL (BW). The schematic (right) in Fig. 17.48 indicates that at high temperature, desorption of water leads to the decrease of friction force, adhesive forces, and coefficient of friction for all of the samples. For Z-15 film, the reduction of viscosity at high temperature also contributes to the decrease of friction force and coefficient of friction. In the case of Z-DOL (BW) film, molecules are more easily oriented at high temperature, which may be partly responsible for the low friction force and coefficient of friction.

To study the durability of lubricant films at the nanoscale, the friction of Si(100), Z-15, and Z-DOL (BW) as a function of the number of scanning cycles is shown in Fig. 17.49. As observed earlier, friction force and coefficient of friction of Z-15 is higher than that of Si(100) with the lowest values for Z-DOL (BW). During cycling, friction force and coefficient of friction of Si(100) show a slight decrease during the initial few cycles then remain constant. This is related to the removal of the top adsorbed layer. In the case of Z-15 film, the friction force and coefficient of friction show an increase during the initial few cycles, and then approach higher and stable values. This is believed to be caused by the attachment of the Z-15 molecules to the tip. The molecular interaction between these attached molecules to the tip and molecules on the film surface is responsible for an increase in friction. But after several scans, this molecular interaction reaches the equilibrium, and after that, friction force and coefficient of friction remain constant. In the case of Z-DOL (BW) film, the friction force and coefficient of friction start out low and remain



Fig. 17.49 Friction force and coefficient of friction versus number of sliding cycles for Si(100) and Z-15 and Z-DOL (BW) films at 70 nN, 0.8 µm/s, and in ambient air. Schematic (*bottom*) shows that some liquid Z-15 molecules can be attached to the tip. The molecular interaction between the attached molecules to the tip with the Z-15 molecules in the film results in an increase of the friction force with multiple scanning [17.30]

low during the entire test for 100 cycles, suggesting that Z-DOL (BW) molecules do not get attached or displaced as readily as Z-15 molecules.

As a brief summary, the influence of velocity, relative humidity, and temperature on the friction force of mobile Z-15 film is presented in Fig. 17.50. The changing trends are also addressed in this figure.



Fig. 17.50 Schematic shows the change of friction force of molecularly thick Z-15 films with log velocity, relative humidity, and temperature. The changing trends are also addressed in this figure [17.30]

17.5.2 Self-Assembled Monolayers

For lubrication of MEMS/NEMS, another effective approach involves the deposition of organized and dense molecular layers of long-chain molecules. Two common methods to produce monolayers and thin films are the Langmuir–Blodgett (L-B) deposition and self-assembled monolayers (SAMs) by chemical grafting of molecules. L-B films are physically bonded to the substrate by weak van der Waals attraction, while SAMs are chemically bonded via covalent bonds to the substrate. Because of the choice of chain length and terminal linking group that SAMs offer, they hold great promise for boundary lubrication of MEMS/NEMS. A number of studies have been conducted to study tribological properties of various SAMs [17.26, 29, 74–76]. It has been reported that SAMs with high-compliance long carbon chains exhibit low friction; chain compliance is desirable for low friction. Based on [17.29], the friction mechanism of SAMs is explained by a so-called "molecular spring" model (Fig. 17.51). According to this model, the chemically adsorbed self-assembled molecules on a substrate are just like assembled molecular springs anchored to the substrate. An asperity sliding on the surface of SAMs is like a tip sliding on the top of "molecular springs or brush". The molecular spring assembly has compliant features and can experience orientation and compression under load. The orientation of the molecular springs or brush under normal load reduces the shearing force at the interface, which, in turn, reduces the friction force.

The SAMs with high-compliance long carbon chains also exhibit the best wear resistance [17.29, 75]. In wear experiments, the wear depth as a function of normal load curves shows critical normal loads (Fig. 17.52). Below the critical normal load SAMs undergo orien-



Fig. 17.51 Molecular spring model of SAMs. In this figure, $\alpha_1 < \alpha_2$, which is caused by the further orientation under the normal load applied by an asperity tip [17.29]



Fig. 17.52 Illustration of the wear mechanism of SAMs with increasing normal load [17.75]



Fig. 17.53 Gray-scale plots of the surface topography and friction force obtained simultaneously for unbonded Demnum-type perfluoropolyether lubricant film on silicon [17.27]

tation, at the critical load SAMs wear away from the substrate due to weak interface bond strengths, while above the critical normal load severe wear takes place on the substrate.

17.5.3 Liquid Film Thickness Measurements

Liquid film thickness measurement of thin lubricant films (on the order of 10 nm or thicker) with nanometer lateral resolution can be made with the AFM [17.4, 59]. The lubricant thickness is obtained by measuring the force on the tip as it approaches, contacts, and pushes through the liquid film and ultimately contacts the substrate. The distance between the sharp snap-in (owing to the formation of a liquid meniscus between the film and the tip) at the liquid surface and the hard repulsion at the substrate surface is a measure of the liquid film thickness.

Lubricant film thickness mapping of ultrathin films (on the order of 2 nm) can be obtained using friction force microscopy [17.27] and adhesive force mapping [17.36]. Figure 17.53 shows gray-scale plots of the surface topography and friction force obtained simultaneously for unbonded Demnum-type PFPE lubricant film on silicon. The friction force plot shows well distinguished low and high friction regions roughly corresponding to high and low regions in surface topography (thick and thin lubricant regions). A uniformly lubricated sample does not show such a variation in the friction. Friction force imaging can thus be used to measure the lubricant uniformity on the sample surface, which cannot be identified by surface topography alone. Figure 17.54 shows the gray-scale plots of the adhesive force distribution for silicon samples coated uniformly and nonuniformly with Z-DOL type PFPE lubricant. It can be clearly seen that a region exists that has an adhesive force distinctly different from the other region for the nonuniformly coated sample. This implies that the liquid film thickness is nonuniform, giving rise to a difference in the meniscus forces.



Fig. 17.54 Gray-scale plots of the adhesive force distribution of a uniformly coated, 3.5-nm thick unbonded Z-DOL film on silicon and 3- to 10-nm thick unbonded Z-DOL film on silicon that was deliberately coated nonuniformly by vibrating the sample during the coating process [17.36]

17.6 Closure

At most solid-solid interfaces of technological relevance, contact occurs at many asperities. A sharp AFM/FFM tip sliding on a surface simulates just one such contact. However, asperities come in all shapes and sizes. The effect of radius of a single asperity (tip) on the friction/adhesion performance can be studied using tips of different radii. AFM/FFM are used to study various tribological phenomena, including surface roughness, adhesion, friction, scratching, wear, indentation, detection of material transfer, and boundary lubrication. Measurement of atomic-scale friction of a freshly cleaved, highly oriented pyrolytic graphite exhibits the same periodicity as that of the corresponding topography. However, the peaks in friction and those in the corresponding topography are displaced relative to one another. Variations in atomic-scale friction and the observed displacement can be explained by the variation in interatomic forces in the normal and lateral directions. Local variations in microscale friction occur and are found to correspond to the local slopes, suggesting that a ratchet mechanism and collision effects are responsible for this variation. Directionality in the friction is observed on both micro- and macroscales, resulting from the surface roughness and surface preparation. Anisotropy in surface roughness accentuates this effect. Microscale friction is generally found to be smaller than the macrofriction, as there is less plowing contribution in microscale measurements. Microscale friction is load-dependent, and friction values increase with an increase in the normal load, approaching the macrofriction at contact stresses higher than the hardness of the softer material. The tip radius also affects adhesion and friction.

Mechanism of material removal on the microscale is studied. Wear rate for single-crystal silicon is negligible below 20 μN and is much higher and remains approximately constant at higher loads. Elastic deformation at low loads is responsible for negligible wear. Most of the wear debris is loose. SEM and TEM studies of the wear region suggest that the material on the microscale is removed by plastic deformation with a small contribution from elastic fracture; this observation corroborates the scratch data. Evolution of wear has also been studied using AFM. Wear is found to be initiated at nanoscratches. For a sliding interface requiring near-zero friction and wear, contact stresses should be below the hardness of the softer material to minimize plastic deformation, and surfaces should be free of nanoscratches. Furthermore, wear precursors can be detected at early stages of wear by using surface potential measurements. It is found that even in the case of zero wear (no measurable deformation of the surface using AFM), there can be a significant change in the surface potential inside the wear mark, which is useful for study of wear precursors. Detection of material transfer on a nanoscale is possible with AFM.

In situ surface characterization of local deformation of materials and thin coatings can be carried out using a tensile stage inside an AFM. An AFM can also be used for nanofabrication/nanomachining.

By using the force modulation technique, localized surface elasticity maps of composite materials with penetrating depths of less than 100 nm can be obtained. It is possible using phase contrast microscopy to get phase contrast maps or the contrast in viscoelastic properties of near surface regions. Scratching and indentation on nanoscales are powerful ways to screen for adhesion and resistance to deformation of ultrathin films. Modified AFM can be used to obtain load-displacement curves and for measurement of nanoindentation hardness and Young's modulus of elasticity, with depth of indentation as low as 1 nm. Hardness of ceramics on the nanoscale is found to be higher than that on the microscale. Ceramics exhibit significant plasticity and creep on a nanoscale.

Boundary lubrication studies and measurement of lubricant-film thickness with a lateral resolution on a nanoscale can be conducted using AFM. Chemically bonded lubricant films and self-assembled monolayers are superior in friction and wear resistance. For chemically bonded lubricant films, the adsorption of water, the formation of meniscus, and its change during sliding, viscosity, and surface properties play an important role on the friction, adhesion, and durability of these films. For SAMs, their friction mechanism is explained by a so-called "molecular spring" model. The films with high-compliance long carbon chains exhibit low friction and wear.

Investigations of wear, scratching, and indentation on the nanoscale using the AFM can provide insights into failure mechanisms of materials. Coefficients of friction, wear rates, and mechanical properties such as hardness have been found to be different on the nanoscale than on the macroscale; generally, coefficients of friction and wear rates on micro- and nanoscales are smaller, whereas hardness is greater. Therefore, micro/nanotribological studies may help define the regimes for ultralow friction and near-zero wear. These studies also provide insight into the atomic origins of adhesion, friction, wear, and lubrication mechanisms.

References

17.1 I. L. Singer, H. M. Pollock: *Fundamentals of Friction: Macroscopic and Microscopic Processes*, Nato Sci. Ser. E, Vol. 220 (Kluwer, Dordrecht 1992)

17.2 B. N. J. Persson, E. Tosatti: *Physics of Sliding Friction*, Nato Sci. Ser. E, Vol. 311 (Kluwer, Dordrecht 1996)

17.3 B. Bhushan: *Micro/Nanotribology and Its Applications*, Nato Sci. Ser. E, Vol. 330 (Kluwer, Dordrecht 1997)

17.4 B. Bhushan: *Handbook of Micro/Nanotribology*, 2nd edn. (CRC, Boca Raton 1999)

17.5 B. Bhushan: Nanoscale tribophysics and tribomechanics, Wear **225–229** (1999) 465–492

17.6 B. Bhushan: Wear and mechanical characterisation on micro- to picoscales using AFM, Int. Mat. Rev. **44** (1999) 105–117

17.7 B. Bhushan: *Modern Tribology Handbook, Vol. 1: Principles of Tribology* (CRC, Boca Raton 2001)

17.8 B. Bhushan: *Fundamentals of tribology and bridging the gap between the macro- and micro/nanoscales*, NATO Sci. Ser. E, Vol. 10 (Kluwer, Dordrecht 2001)

17.9 B. Bhushan: Nano- to microscale wear and mechanical characterization studies using scanning probe microscopy, Wear **251** (2001) 1105–1123

17.10 B. Bhushan: *Introduction to Tribology* (Wiley, New York 2002)

17.11 B. Bhushan, J. N. Israelachvili, U. Landman: Nanotribology: Friction, wear and lubrication at the atomic scale, Nature **374** (1995) 607–616

17.12 H. J. Guntherodt, D. Anselmetti, E. Meyer: *Forces in Scanning Probe Methods*, Nato Sci. Ser. E, Vol. 286 (Kluwer, Dordrecht 1995)

17.13 B. Bhushan: *Tribology and Mechanics of Magnetic Storage Devices*, 2nd edn. (Springer, New York 1996)

17.14 B. Bhushan: *Tribology Issues and Opportunities in MEMS* (Kluwer, Dordrecht 1998)

17.15 G. Binnig, C. F. Quate, Ch. Gerber: Atomic force microscopy, Phys. Rev. Lett. **56** (1986) 930–933

17.16 G. Binnig, Ch. Gerber, E. Stoll, T. R. Albrecht, C. F. Quate: Atomic resolution with atomic force microscope, Europhys. Lett. **3** (1987) 1281–1286

17.17 C. M. Mate, G. M. McClelland, R. Erlandsson, S. Chiang: Atomic-scale friction of a tungsten tip on a graphite surface, Phys. Rev. Lett. **59** (1987) 1942–1945

17.18 B. Bhushan, J. Ruan: Atomic-scale friction measurements using friction force microscopy: part II – application to magnetic media, ASME J. Tribol. **116** (1994) 389–396

17.19 J. Ruan, B. Bhushan: Atomic-scale friction measurements using friction force microscopy: part I – general principles and new measurement techniques, ASME J. Tribol. **116** (1994) 378–388

17.20 J. Ruan, B. Bhushan: Atomic-scale and microscale friction of graphite and diamond using friction force microscopy, J. Appl. Phys. **76** (1994) 5022–5035

17.21 J. Ruan, B. Bhushan: Frictional behavior of highly oriented pyrolytic graphite, J. Appl. Phys. **76** (1994) 8117–8120

17.22 B. Bhushan, V. N. Koinkar, J. Ruan: Microtribology of magnetic media, Proc. Inst. Mech. Eng., Part J: J. Eng. Tribol. **208** (1994) 17–29

17.23 B. Bhushan, S. Sundararajan: Micro/nanoscale friction and wear mechanisms of thin films using atomic force and friction force microscopy, Acta Mater. **46** (1998) 3793–3804

17.24 V. Scherer, W. Arnold, B. Bhushan: Active friction control using ultrasonic vibration. In: *Tribology Issues and Opportunities in MEMS*, ed. by B. Bhushan (Kluwer, Dordrecht 1998) pp. 463–469

17.25 V. Scherer, W. Arnold, B. Bhushan: Lateral force microscopy using acoustic friction force microscopy, Surf. Interface Anal. **27** (1999) 578–587

17.26 B. Bhushan, A. V. Kulkarni, V. N. Koinkar, M. Boehm, L. Odoni, C. Martelet, M. Belin: Microtribological characterization of self-assembled and Langmuir–Blodgett monolayers by atomic and friction force microscopy, Langmuir **11** (1995) 3189–3198

17.27 V. N. Koinkar, B. Bhushan: Micro/nanoscale studies of boundary layers of liquid lubricants for magnetic disks, J. Appl. Phys. **79** (1996) 8071–8075

17.28 V. N. Koinkar, B. Bhushan: Microtribological studies of unlubricated and lubricated surfaces using atomic force/friction force microscopy, J. Vac. Sci. Technol. A. **14** (1996) 2378–2391

17.29 B. Bhushan, H. Liu: Nanotribological properties and mechanisms of alkylthiol and biphenyl thiol self-assembled monolayers studied by AFM, Phys. Rev. B **63** (2001) 245412-1–245412-11

17.30 H. Liu, B. Bhushan: Nanotribological characterization of molecularly-thick lubricant films for applications to MEMS/NEMS by AFM, Ultramicroscopy **97** (2003) 321–340

17.31 B. Bhushan, V. N. Koinkar: Tribological studies of silicon for magnetic recording applications, J. Appl. Phys. **75** (1994) 5741–5746

17.32 V. N. Koinkar, B. Bhushan: Microtribological properties of hard amorphous carbon protective coatings for thin film magnetic disks and heads, Proc. Inst. Mech. Eng. Part J: J. Eng. Tribol. **211** (1997) 365–372

17.33 S. Sundararajan, B. Bhushan: Development of a continuous microscratch technique in an atomic force microscope and its application to study scratch resistance of ultra-thin hard amorphous carbon coatings, J. Mater. Res. **16** (2001) 75–84

17.34 B. Bhushan, V. N. Koinkar: Nanoindentation hardness measurements using atomic force microscopy, Appl. Phys. Lett. **64** (1994) 1653–1655
17.35 B. Bhushan, A. V. Kulkarni, W. Bonin, J. T. Wyrobek: Nano/picoindentation measurement using a capacitance transducer system in atomic force microscopy, Philos. Mag. **74** (1996) 1117–1128
17.36 B. Bhushan, C. Dandavate: Thin-film friction and adhesion studies using atomic force microscopy, J. Appl. Phys. **87** (2000) 1201–1210
17.37 B. Bhushan: Micro/nanotribology and its applications to magnetic storage devices and MEMS, Tribol. Int. **28** (1995) 85–95
17.38 D. DeVecchio, B. Bhushan: Use of a nanoscale Kelvin probe for detecting wear precursors, Rev. Sci. Instrum. **69** (1998) 3618–3624
17.39 B. Bhushan, A.V. Goldade: Measurements and analysis of surface potential change during wear of single crystal silicon (100) at ultralow loads using Kelvin probe microscopy, Appl. Surf. Sci **157** (2000) 373–381
17.40 B. Bhushan, A.V. Goldade: Kelvin probe microscopy measurements of surface potential change under wear at low loads, Wear **244** (2000) 104–117
17.41 M.S. Bobji, B. Bhushan: Atomic force microscopic study of the micro-cracking of magnetic thin films under tension, Scripta Mater. **44** (2001) 37–42
17.42 M.S. Bobji, B. Bhushan: In-situ microscopic surface characterization studies of polymeric thin films during tensile deformation using atomic force microscopy, J. Mater. Res. **16** (2001) 844–855
17.43 P. Maivald, H.J. Butt, S.A.C. Gould, C.B. Prater, B. Drake, J.A. Gurley, V.B. Elings, P.K. Hansma: Using force modulation to image surface elasticities with the atomic force microscope, Nanotechnol. **2** (1991) 103–106
17.44 D. DeVecchio, B. Bhushan: Localized surface elasticity measurements using an atomic force microscope, Rev. Sci. Instrum. **68** (1997) 4498–4505
17.45 V. Scherer, B. Bhushan, U. Rabe, W. Arnold: Local elasticity and lubrication measurements using atomic force and friction force microscopy at ultrasonic frequencies, IEEE Trans. Mag. **33** (1997) 4077–4079
17.46 H. U. Krotil, T. Stifter, H. Waschipky, K. Weishaupt, S. Hild, O. Marti: Pulse force mode: A new method for the investigation of surface properties, Surf. Interface Anal. **27** (1999) 336–340
17.47 S. Amelio, A.V. Goldade, U. Rabe, V. Scherer, B. Bhushan, W. Arnold: Measurements of elastic properties of ultra-thin diamond-like carbon coatings using atomic force acoustic microscopy, Thin Solid Films **392** (2001) 75–84
17.48 B. Anczykowski, D. Kruger, K. L. Babcock, H. Fuchs: Basic properties of dynamic force microscopy with the scanning force microscope in experiment and simulation, Ultramicroscopy **66** (1996) 251–259
17.49 J. Tamayo, R. Garcia: Deformation, contact time, and phase contrast in tapping mode scanning force microscopy, Longmuir **12** (1996) 4430–4435
17.50 R. Garcia, J. Tamayo, M. Calleja, F. Garcia: Phase contrast in tapping-mode scanning force microscopy, Appl. Phys. A **66** (1998) 309–312
17.51 W.W. Scott, B. Bhushan: Use of phase imaging in atomic force microscopy for measurement of viscoelastic contrast in polymer nanocomposites and molecularly-thick lubricant films, Ultramicroscopy **97** (2003) 151–169
17.52 B. Bhushan, J. Qi: Phase contrast imaging of nanocomposites and molecularly- thick lubricant films in magnetic media, Nanotechnol. **14** (2003) 886–895
17.53 V. N. Koinkar, B. Bhushan: Microtribological studies of Al_2O_3-TiC, polycrystalline and single-crystal Mn-Zn ferrite and SiC head slider materials, Wear **202** (1996) 110–122
17.54 E. Meyer, R. Overney, R. Luthi, D. Brodbeck, L. Howald, J. Frommer, H.J. Guntherodt, O. Wolter, M. Fujihira, T. Takano, Y. Gotoh: Friction force microscopy of mixed Langmuir–Blodgett films, Thin Solid Films **220** (1992) 132–137
17.55 C. D. Frisbie, L. F. Rozsnyai, A. Noy, M.S. Wrighton, C.M. Lieber: Functional group imaging by chemical force microscopy, Science **265** (1994) 2071–2074
17.56 V.N. Koinkar, B. Bhushan: Effect of scan size and surface roughness on microscale friction measurements, J. Appl. Phys. **81** (1997) 2472–2479
17.57 S. Sundararajan, B. Bhushan: Topography-induced contributions to friction forces measured using an atomic force/friction force microscope, J. Appl. Phys. **88** (2000) 4825–4831
17.58 B. Bhushan: *Principles and Applications of Tribology* (Wiley, New York 1999)
17.59 B. Bhushan, G.S. Blackman: Atomic force microscopy of magnetic rigid disks and sliders and its applications to tribology, ASME J. Tribol. **113** (1991) 452–458
17.60 M. Reinstaedtler, U. Rabe, V. Scherer, U. Hartmann, A. Goldade, B. Bhushan, W. Arnold: On the nanoscale measurement of friction using atomic-force microscope cantilever torsional resonances, Appl. Phys. Lett. **82** (2003) 2604–2606
17.61 T. Stifter, O. Marti, B. Bhushan: Theoretical investigation of the distance dependence of capillary and van der Waals forces in scanning probe microscopy, Phys. Rev. B **62** (2000) 13667–13673
17.62 U. D. Schwarz, O. Zwoerner, P. Koester, R. Wiesendanger: Friction force spectroscopy in the low-load regime with well-defined tips. In: *Micro/Nanotribology and Its Applications*, ed. by B. Bhushan (Kluwer, Dordrecht 1997) pp. 233–238

17.63 B. Bhushan, A. V. Kulkarni: Effect of normal load on microscale friction measurements, Thin Solid Films **278** (1996) 49–56; Errata: **293** 333

17.64 V. N. Koinkar, B. Bhushan: Scanning and transmission electron microscopies of single-crystal silicon microworn/machined using atomic force microscopy, J. Mater. Res. **12** (1997) 3219–3224

17.65 X. Zhao, B. Bhushan: Material removal mechanism of single-crystal silicon on nanoscale and at ultralow loads, Wear **223** (1998) 66–78

17.66 B. Bhushan, P. S. Mokashi, T. Ma: A new technique to measure Poisson's ratio of ultrathin polymeric films using atomic force microscopy, Rev. Sci. Instrumen. **74** (2003) 1043–1047

17.67 A. V. Kulkarni, B. Bhushan: Nanoscale mechanical property measurements using modified atomic force microscopy, Thin Solid Films **290–291** (1996) 206–210

17.68 A. V. Kulkarni, B. Bhushan: Nano/picoindentation measurements on single-crystal aluminum using modified atomic force microscopy, Mater. Lett. **29** (1996) 221–227

17.69 A. V. Kulkarni, B. Bhushan: Nanoindentation measurement of amorphous carbon coatings, J. Mater. Res. **12** (1997) 2707–2714

17.70 J. Ruan, B. Bhushan: Nanoindentation studies of fullerene films using atomic force microscopy, J. Mater. Res. **8** (1993) 3019–3022

17.71 N. A. Fleck, G. M. Muller, M. F. Ashby, J. W. Hutchinson: Strain gradient plasticity: Theory and experiment, Acta Metall. Mater. **42** (1994) 475–487

17.72 W. B. Li, J. L. Henshall, R. M. Hooper, K. E. Easterling: The mechanism of indentation creep, Acta Metall. Mater. **39** (1991) 3099–3110

17.73 F. P. Bowden, D. Tabor: *The Friction and Lubrication of Solids*, Vol. 1 (Clarendon, Oxford 1950)

17.74 H. Liu, B. Bhushan: Investigation of the adhesion, friction, and wear properties of biphenyl thiol self-assembled monolayers by atomic force microscopy, J. Vac. Sci. Technol. A **19** (2001) 1234–1240

17.75 H. Liu, B. Bhushan: Investigation of nanotribological properties of self-assembled monolayers with alkyl and biphenyl spacer chains, Ultramicroscopy **91** (2002) 185–202

17.76 B. Bhushan: Self-assembled monolayers for controlling hydrophobicity and/or friction and wear. In: *Modern Tribology Handbook, Vol. 2: Materials, Coatings, and Industrial Applications*, ed. by B. Bhushan (CRC, Boca Raton 2001) pp. 909–929

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

18. Surface Forces and Nanorheology of Molecularly Thin Films

In this chapter, we describe the static and dynamic normal forces that occur between surfaces in vacuum or liquids and the different modes of friction that can be observed between (i) bare surfaces in contact (dry or interfacial friction), (ii) surfaces separated by a thin liquid film (lubricated friction), and (iii) surfaces coated with organic monolayers (boundary friction).

Experimental methods suitable for measuring normal surface forces, adhesion and friction (lateral or shear) forces of different magnitude at the molecular level are described. We explain the molecular origin of van der Waals, electrostatic, solvation and polymer mediated interactions, and basic models for the contact mechanics of adhesive and nonadhesive elastically deforming bodies. The effects of interaction forces, molecular shape, surface structure and roughness on adhesion and friction are discussed.

Simple models for the contributions of the adhesion force and external load to interfacial friction are illustrated with experimental data on both unlubricated and lubricated systems, as measured with the surface forces apparatus. We discuss rate-dependent adhesion (adhesion hysteresis) and how this is related to friction. Some examples of the transition from wearless friction to friction with wear are shown.

Lubrication in different lubricant thickness regimes is described together with explanations of nanorheological concepts. The occurrence of and transitions between smooth and stick–slip sliding in various types of dry (unlubricated and solid boundary lubricated) and liquid lubricated systems are discussed based on recent experimental results and models for stick–slip involving memory distance and dilatency.

18.1 **Introduction: Types of Surface Forces** 544

18.2 **Methods Used to Study Surface Forces** 546
  18.2.1 Force Laws 546
  18.2.2 Adhesion Forces 547
  18.2.3 The SFA and AFM 547
  18.2.4 Some Other Force-Measuring Techniques 549

18.3 **Normal Forces Between Dry (Unlubricated) Surfaces** 550
  18.3.1 Van der Waals Forces in Vacuum and Inert Vapors 550
  18.3.2 Charge Exchange Interactions 552
  18.3.3 Sintering and Cold Welding 553

18.4 **Normal Forces Between Surfaces in Liquids** 554
  18.4.1 Van der Waals Forces in Liquids 554
  18.4.2 Electrostatic and Ion Correlation Forces........... 554
  18.4.3 Solvation and Structural Forces 557
  18.4.4 Hydration and Hydrophobic Forces 559
  18.4.5 Polymer-Mediated Forces............ 561
  18.4.6 Thermal Fluctuation Forces.......... 563

18.5 **Adhesion and Capillary Forces**................ 564
  18.5.1 Capillary Forces 564
  18.5.2 Adhesion Mechanics 566
  18.5.3 Effects of Surface Structure, Roughness, and Lattice Mismatch.................. 566
  18.5.4 Nonequilibrium and Rate-Dependent Interactions: Adhesion Hysteresis.................... 567

18.6 **Introduction: Different Modes of Friction and the Limits of Continuum Models** 569

18.7 **Relationship Between Adhesion and Friction Between Dry (Unlubricated and Solid Boundary Lubricated) Surfaces** 571
  18.7.1 Amontons' Law and Deviations from It Due to Adhesion: The Cobblestone Model 571
  18.7.2 Adhesion Force and Load Contribution to Interfacial Friction 572
  18.7.3 Examples of Experimentally Observed Friction of Dry Surfaces... 576
  18.7.4 Transition from Interfacial to Normal Friction with Wear........ 579

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

18.8 **Liquid Lubricated Surfaces** 580
18.8.1 Viscous Forces and Friction of Thick Films: Continuum Regime 580
18.8.2 Friction of Intermediate Thickness Films 582
18.8.3 Boundary Lubrication of Molecularly Thin Films: Nanorheology 584
18.9 **Role of Molecular Shape and Surface Structure in Friction** 591
References 594

18.1 Introduction: Types of Surface Forces

In this chapter, we discuss the most important types of surface forces and the relevant equations for the force and friction laws. Several different attractive and repulsive forces operate between surfaces and particles. Some forces occur in vacuum, for example, attractive van der Waals and repulsive hard-core interactions. Other types of forces can arise only when the interacting surfaces are separated by another condensed phase, which is usually a liquid. The most common types of surface forces and their main characteristics are listed in Table 18.1.

In *vacuum*, the two main long-range interactions are the attractive van der Waals and electrostatic (Coulomb) forces. At smaller surface separations (corresponding to molecular contact at surface separations of $D \approx 0.2\,\mathrm{nm}$), additional attractive interactions can be found such as covalent or metallic bonding forces. These attractive forces are stabilized by the hard-core repulsion. Together they determine the surface and interfacial energies of planar surfaces, as well as the strengths of materials and adhesive junctions. Adhesion forces are often strong enough to elastically or plastically deform bodies or particles when they come into contact.

In *vapors* (e.g., atmospheric air containing water and organic molecules), solid surfaces in or close to contact will generally have a surface layer of chemisorbed or physisorbed molecules, or a capillary condensed liquid bridge between them. A surface layer usually causes the adhesion to decrease, but in the case of capillary condensation, the additional Laplace pressure or attractive "capillary" force may make the adhesion between the surfaces stronger than in inert gas or vacuum.

When totally immersed in a *liquid*, the force between particles or surfaces is completely modified from that in vacuum or air (vapor). The van der Waals attraction is generally reduced, but other forces can now arise that can qualitatively change both the range and even the sign of the interaction. The attractive force in such a system can be either stronger or weaker than in the absence of the intervening liquid. For example, the overall attraction can be stronger in the case of two hydrophobic surfaces separated by water, but weaker for two hydrophilic surfaces. Depending on the different forces that may be operating simultaneously in solution, the overall force law is not generally monotonically attractive even at long range; it can be repulsive, or the force can change sign at some finite surface separation. In such cases, the potential energy minimum, which determines the adhesion force or energy, occurs not at true molecular contact between the surfaces, but at some small distance farther out.

The forces between surfaces in a liquid medium can be particularly complex at *short range*, i. e., at surface separations below a few nanometers or 4–10 molecular diameters. This is partly because with increasing confinement, a liquid ceases to behave as a structureless continuum with bulk properties; instead, the size and shape of its molecules begin to determine the overall interaction. In addition, the surfaces themselves can no longer be treated as inert and structureless walls (i. e., mathematically flat) and their physical and chemical properties at the atomic scale must now be taken into account. The force laws will then depend on whether the surfaces are amorphous or crystalline (and whether the lattices of crystalline surfaces are matched or not), rough or smooth, rigid or soft (fluid-like), and hydrophobic or hydrophilic.

It is also important to distinguish between *static* (i. e., equilibrium) interactions and *dynamic* (i. e., nonequilibrium) forces such as viscous and friction forces. For example, certain liquid films confined between two contacting surfaces may take a surprisingly long time to equilibrate, as may the surfaces themselves, so that the short-range and adhesion forces appear to be time-dependent, resulting in "aging" effects.

Table 18.1 Types of surface forces in vacuum vs. in liquid (colloidal forces)

Type of force	Subclasses or alternative names	Main characteristics
	Attractive forces	
van der Waals	Debye induced dipole force (v & s) London dispersion force (v & s) Casimir force (v & s)	Ubiquitous, occurs both in vacuum and in liquids
Electrostatic	Ionic bond (v) Coulombic force (v & s) Hydrogen bond (v) Charge-exchange interaction (v & s) Acid–base interaction (s) “Harpooning” interaction (v)	Strong, long-range, arises in polar solvents; requires surface charging or charge-separation mechanism
Ion correlation	van der Waals force of polarizable ions (s)	Requires mobile charges on surfaces in a polar solvent
Quantum mechanical	Covalent bond (v) Metallic bond (v) Exchange interaction (v)	Strong, short-range, responsible for contact binding of crystalline surfaces
Solvation	Oscillatory force (s) Depletion force (s)	Mainly entropic in origin, the oscillatory force alternates between attraction and repulsion
Hydrophobic	Attractive hydration force (s)	Strong, apparently long-range; origin not yet understood
Specific binding	“Lock-and-key” or complementary binding (v & s) Receptor–ligand interaction (s) Antibody–antigen interaction (s)	Subtle combination of different non-covalent forces giving rise to highly specific binding; main recognition mechanism of biological systems
	Repulsive forces	
van der Waals	van der Waals disjoining pressure (s)	Arises only between dissimilar bodies interacting in a medium
Electrostatic	Coulombic force (v & s)	Arises only for certain constrained surface charge distributions
Quantum mechanical	Hard-core or steric repulsion (v) Born repulsion (v)	Short-range, stabilizing attractive covalent and ionic binding forces, effectively determine molecular size and shape
Solvation	Oscillatory solvation force (s) Structural force (s) Hydration force (s)	Monotonically repulsive forces, believed to arise when solvent molecules bind strongly to surfaces
Entropic	Osmotic repulsion (s) Double-layer force (s) Thermal fluctuation force (s) Steric polymer repulsion (s) Undulation force (s) Protrusion force (s)	Due to confinement of molecular or ionic species; requires mechanism that keeps trapped species between the surfaces
	Dynamic interactions	
Non-equilibrium	Hydrodynamic forces (s) Viscous forces (s) Friction forces (v & s) Lubrication forces (s)	Energy-dissipating forces occurring during relative motion of surfaces or bodies

Note: (v) applies only to interactions in vacuum, (s) applies only to interactions in solution (or to surfaces separated by a liquid), and (v & s) applies to interactions occurring both in vacuum and in solution.

18.2 Methods Used to Study Surface Forces

18.2.1 Force Laws

The full force law $F(D)$ between two surfaces, i. e., the force F as a function of surface separation D, can be measured in a number of ways [18.2–6]. The simplest is to move the base of a spring by a known amount, ΔD_0. Figure 18.1 illustrates this method when applied to the interaction of two magnets. However, the method is applicable also at the microscopic or molecular level, and it forms the basis of all direct force-measuring apparatuses such as the surface forces apparatus (SFA; [18.3, 7]) and the atomic force microscope (AFM; [18.8–10]). If there is a detectable force between the surfaces, this will cause the force-measuring spring to deflect by ΔD_s, while the surface separation changes by ΔD. These three displacements are related by

$$\Delta D_\mathrm{s} = \Delta D_0 - \Delta D\,. \tag{18.1}$$



Fig. 18.1 Schematic attractive force law between two macroscopic objects such as two magnets, or between two microscopic objects such as the van der Waals force between a metal tip and a surface. On lowering the base supporting the spring, the latter will expand or contract such that at any equilibrium separation D the attractive force balances the elastic spring restoring force. If the gradient of the attractive force $\mathrm{d}F/\mathrm{d}D$ exceeds the gradient of the spring's restoring force (defined by the spring constant k_s), the upper surface will jump from A into contact at A′ (A for "advancing"). On separating the surfaces by raising the base, the two surfaces will jump apart from R to R′ (R for "receding"). The distance R–R′ multiplied by k_s gives the adhesion force, i. e., the value of F at the point R (after [18.1] with permission)

The difference in force, ΔF, between the initial and final separations is given by

$$\Delta F = k_\mathrm{s} \Delta D_\mathrm{s}\,, \tag{18.2}$$

where k_s is the spring constant. The equations above provide the basis for measurements of the force difference between any two surface separations. For example, if a force-measuring apparatus with a known k_s can measure D (and thus ΔD), ΔD_0, and ΔD_s, the force difference ΔF can be measured between a large initial or reference separation D, where the force is zero ($F = 0$), and another separation $D - \Delta D$. By working one's way in increasing increments of $\Delta D = \Delta D_0 - \Delta D_\mathrm{s}$, the full force law $F(D)$ can be constructed over any desired distance regime.

In order to measure an equilibrium force law, it is essential to establish that the two surfaces have stopped moving before the displacements are measured. When displacements are measured while two surfaces are still in relative motion, one also measures a viscous or frictional contribution to the total force. Such dynamic force measurements have enabled the viscosities of liquids near surfaces and in thin films to be accurately determined [18.11–13].

In practice, it is difficult to measure the forces between two perfectly flat surfaces, because of the stringent requirement of perfect alignment for making reliable measurements at distances of a few tenths of a nanometer. It is far easier to measure the forces between curved surfaces, e.g., two spheres, a sphere and a flat surface, or two crossed cylinders. Furthermore, the force $F(D)$ measured between two curved surfaces can be directly related to the energy per unit area $E(D)$ between two flat surfaces at the same separation, D, by the so-called Derjaguin approximation [18.14]:

$$E(D) = \frac{F(D)}{2\pi R}\,, \tag{18.3}$$

where R is the radius of the sphere (for a sphere and a flat surface) or the radii of the cylinders (for two crossed cylinders).

18.2.2 Adhesion Forces

The most direct way to measure the adhesion of two solid surfaces (such as two spheres or a sphere on a flat) is to suspend one of them on a spring and measure the adhesion or "pull-off" force needed to separate the two bodies from its deflection. If k_s is the stiffness of the force-measuring spring and ΔD the distance the two surfaces jump apart when they separate, then the adhesion force F_s is given by

$$F_s = F_{max} = k_s \Delta D \,, \tag{18.4}$$

where we note that in liquids, the maximum or minimum in the force may occur at some nonzero surface separation (see Fig. 18.7). From F_s and a known surface geometry, and assuming that the surfaces were everywhere in molecular contact, one may also calculate the surface or interfacial energy γ. For an elastically deformable sphere of radius R on a flat surface, or for two crossed cylinders of radius R, we have [18.3, 15]

$$\gamma = \frac{F_s}{3\pi R} \,, \tag{18.5}$$

while for two spheres of radii R_1 and R_2

$$\gamma = \frac{F_s}{3\pi}\left(\frac{1}{R_1} + \frac{1}{R_2}\right) \,, \tag{18.6}$$

where γ is in units of $\mathrm{J\,m^{-2}}$ (see Sect. 18.5.2).

18.2.3 The SFA and AFM

In a typical force-measuring experiment, at least two of the above displacement parameters – ΔD_0, ΔD, and ΔD_s – are directly or indirectly measured, and from these the third displacement and the resulting force law $F(D)$ are deduced using (18.1) and (18.2) together with a measured value of k_s. For example, in SFA experiments, ΔD_0 is changed by expanding or contracting a piezoelectric crystal by a known amount or by moving the base of the spring with sensitive motor-driven mechanical stages. The resulting change in surface separation ΔD is measured optically, and the spring deflection ΔD_s can then be obtained according to (18.1). In AFM experiments, ΔD_0 and ΔD_s are measured using a combination of piezoelectric, optical, capacitance or magnetic techniques, from which the change in surface separation ΔD is deduced. Once a force law is established, the geometry of the two surfaces (e.g., their radii) must also be known before the results can be compared with theory or with other experiments.

The SFA (Fig. 18.2) is used for measurements of adhesion and force laws between two curved molecularly smooth surfaces immersed in liquids or controlled vapors [18.3, 7, 16]. The surface separation is measured by multiple beam interferometry with an accuracy of ± 0.1 nm. From the shape of the interference fringes one also obtains the radius of the surfaces, R, and any surface deformation that arises during an interaction [18.17–19]. The resolution in the lateral direction is about 1 μm. The surface separation can be independently controlled to within 0.1 nm, and the force sensitivity is about 10^{-8} N. For a typical surface radius of $R \approx 1$ cm, γ values can be measured to an accuracy of about $10^{-3}\ \mathrm{mJ\,m^{-2}}$.

Several different materials have been used to form the surfaces in the SFA, including mica [18.20, 21], silica [18.22], sapphire [18.23], and polymer sheets [18.24]. These materials can also be used as supporting substrates in experiments on the forces between adsorbed or chemically bound polymer layers [18.13, 25–30], surfactant and lipid monolayers and bilayers [18.31–34], and metal and metal oxide layers [18.35–42]. The range of liquids and vapors that can be used is almost endless, and have thus far included aqueous solutions, organic liquids and solvents, polymer melts, various petroleum oils and lubricant liquids, and liquid crystals.

Friction attachments for the SFA [18.43–47] allow for the two surfaces to be sheared laterally past each other at varying sliding speeds or oscillating frequencies, while simultaneously measuring both the transverse (frictional or shear) force and the normal force (load) between them. The ranges of friction forces and sliding speeds that can be studied with such methods are currently 10^{-7}–10^{-1} N and 10^{-13}–$10^{-2}\ \mathrm{m\,s^{-1}}$, respectively [18.48]. The externally applied load, L, can be varied continuously, and both positive and negative loads can be applied. The distance between the surfaces, D, their true molecular contact area, their elastic (or viscoelastic or elastohydrodynamic) deformation, and their lateral motion can all be monitored simultaneously by recording the moving interference fringe pattern.

In the atomic force microscope (Fig. 18.3), the force is measured by monitoring the deflection of a soft cantilever supporting a sub-microscopic tip ($R \approx 10$–200 nm) as this is interacting with a flat, macroscopic surface [18.8, 49, 50]. The measurements can be done in a vapor or liquid. The normal (bending) spring stiffness of the cantilever can be as small as $0.01\ \mathrm{N\,m^{-1}}$, allowing measurements of normal forces as small as 1 pN (10^{-12} N), which corresponds to the bond strength


5 cm
White light
(to spectrometer/
camera)
Differential
micrometer
Micrometer
Motor/encoder
Micrometer for
differential spring
Microscope tube
Clamp
Wire
Piezoelectric
tube
Air outlet
Wheel
Upper
(control)
chamber
Lever
Shaft
Bellows
Surfaces
Windows and
side ports
Clamp
Springs
Lower
chamber
Inlet hole
Hinge
Spring mount
Base
10
0
40

Fig. 18.2 A surface forces apparatus (SFA) where the intermolecular forces between two macroscopic, cylindrical surfaces of local radius R can be directly measured as a function of surface separation over a large distance regime from tenths of a nanometer to micrometers. Local or transient surface deformations can be detected optically. Various attachments for moving one surface laterally with respect to the other have been developed for friction measurements in different regimes of sliding velocity and sliding distance (after [18.16] with permission)

of single molecules [18.51, 52]. Distances can be inferred with an accuracy of about 1 nm, and changes in distance can be measured to about 0.1 nm. Since the contact area is small, different interaction regimes can be resolved on samples with a heterogeneous composition on lateral scales of about ten nanometers. Height differences and the roughness of the sample can be measured directly from the cantilever deflection or, alternatively, by using a feedback system to raise or lower the sample so that the deflection (the normal force) is kept constant during a scan over the area of interest. Weak interaction forces and larger (microscopic) interaction areas can be investigated by replacing the tip with a micrometer-sized sphere to form a "colloidal probe" [18.9].

The atomic force microscope can also be used for friction measurements (lateral force microscopy, LFM) by monitoring the torsion of the cantilever as the sample is scanned in the direction perpendicular to the long axis of the cantilever [18.10, 50, 53, 54]. Typically, the stiffness of the cantilever to lateral bending is much larger than to bending in the normal direction and to torsion, so that these signals are decoupled and height and friction can be detected simultaneously. The torsional spring constant can be as low as $0.1\,\mathrm{N\,m^{-1}}$, giving a lateral (friction) force sensitivity of 10^{-11} N.

Rapid technical developments have facilitated the calibrations of the normal [18.55, 56] and lateral spring constants [18.54, 57], as well as in situ measurements of



Fig. 18.3 Schematic drawing of an atomic force microscope (AFM) tip supported on a triangular cantilever interacting with an arbitrary solid surface. The normal force and topology are measured by monitoring the calibrated deflection of the cantilever as the tip is moved across the surface by means of a piezoelectric transducer. Various designs have been developed that move either the sample or the cantilever during the scan. Friction forces can be measured from the torsion of the cantilever when the scanning is in the direction perpendicular to its long axis (after [18.62] with permission)

the macroscopic tip radius [18.58]. Cantilevers of different shapes with a large range of spring constants, tip radii, and surface treatments (inorganic or organic coatings) are commercially available. The flat surface, and also the particle in the colloidal probe technique, can be any material of interest. However, remaining difficulties with this technique are that the distance between the tip and the substrate, D, and the deformations of the tip and sample are not directly measurable. Another important difference between the AFM/LFM and SFA techniques is the different size of the contact area, and the related observation that even when a cantilever with a very low spring constant is used in the AFM, the pressure in the contact zone is typically much higher than in the SFA. Hydrodynamic effects in liquids also affect the measurements of normal forces differently on certain time scales [18.59–61].

18.2.4 Some Other Force-Measuring Techniques

A large number of other techniques are available for the measurements of the normal forces between solid or fluid surfaces (see [18.5, 62]). The techniques discussed in this section are not used for lateral (friction) force measurements, but are commonly used to study normal forces, particularly in biological systems.

Micropipette aspiration is used to measure the forces between cells or vesicles, or between a cell or vesicle and another surface [18.63–65]. The cell or vesicle is held by suction at the tip of a glass micropipette and deforms elastically in response to the net interactions with another surface and to the applied suction. The shape of the deformed surface (cell membrane) is measured and used to deduce the force between the surfaces and the membrane tension [18.64]. The membrane tension, and thus the stiffness of the cell or vesicle, is regulated by applying different hydrostatic pressures. Forces can be measured in the range of 0.1 pN to 1 nN, and the distance resolution is a few nanometers. The interactions between a colloidal particle and another surface can be studied by attaching the particle to the cell membrane [18.66].

In the osmotic stress technique, pressures are measured between colloidal particles in aqueous solution, membranes or bilayers, or other ordered colloidal structures (viruses, DNA). The separation between the particle surfaces and the magnitude of membrane undulations are measured by X-ray or neutron scattering techniques. This is combined with a measurement of the osmotic pressure of the solution [18.67–70]. The technique has been used to measure repulsive forces, such as DLVO interactions, steric forces, and hydration forces [18.71]. The sensitivity in pressure is $0.1\,\mathrm{mN\,m^{-2}}$, and distances can be resolved to 0.1 nm.

The optical tweezers technique is based on the trapping of dielectric particles at the center of a focused laser beam by restoring forces arising from radiation pressure and light intensity gradients [18.72, 73]. The forces experienced by particles as they are moved toward or away from one another can be measured with a sensitivity in the pN range. Small biological molecules are typically attached to a larger bead of a material with suitable refractive properties. Recent development allows determinations of position with nanometer resolution [18.74], which makes this technique useful for studying the forces during extension of single molecules.

In total internal reflection microscopy (TIRM), the potential energy between a micrometer-sized colloidal particle and flat surface in aqueous solution is deduced from the average equilibrium height of the particle above the surface, measured from the intensity of scattered light. The average height ($D \approx 10-100$ nm) results from a balance of gravitational force, radiation pressure from a laser beam focused at the particle from below, and intermolecular forces [18.75]. The technique is particularly suitable for measuring weak forces (sensitivity ca. 10^{-14} N), but is more difficult to use for systems with strong interactions. A related technique is reflection interference contrast microscopy (RICM), where optical interference is used to also monitor changes in the shape of the approaching colloidal particle or vesicle [18.76].

An estimate of bond strengths can be obtained from the hydrodynamic shear force exerted by a fluid on particles or cells attached to a substrate [18.77, 78]. At a critical force, the bonds are broken and the particle or cell will be detached and move with the velocity of the fluid. This method requires knowledge of the contact area and the flow velocity profile of the fluid. Furthermore, a uniform stress distribution in the contact area is generally assumed. At low bond density, this technique can be used to determine the strength of single bonds (1 pN).

18.3 Normal Forces Between Dry (Unlubricated) Surfaces

18.3.1 Van der Waals Forces in Vacuum and Inert Vapors

Forces between macroscopic bodies (such as colloidal particles) across vacuum arise from interactions between the constituent atoms or molecules of each body across the gap separating them. These intermolecular interactions are electromagnetic forces between permanent or induced dipoles (van der Waals forces), and between ions (electrostatic forces). In this section, we describe the van der Waals forces, which occur between all atoms and molecules and between all macroscopic bodies (see [18.3]).

The interaction between two permanent dipoles with a fixed relative orientation can be attractive or repulsive. For the specific case of two freely rotating permanent dipoles in a liquid or vapor (orientational or Keesom interaction), and for a permanent dipole and an induced dipole in an atom or polar or nonpolar molecule (induction or Debye interaction), the interaction is on average always attractive. The third type of van der Waals interaction, the fluctuation or London dispersion interaction, arises from instantaneous polarization of one nonpolar or polar molecule due to fluctuations in the charge distribution of a neighboring nonpolar or polar molecule (Fig. 18.4a). Correlation between these fluctuating induced dipole moments gives an attraction that is present between any two molecules or surfaces across vacuum. At very small separations, the interaction will ultimately be repulsive as the electron clouds of atoms and molecules begin to overlap. The total interaction is thus a combination of a short-range repulsion and a relatively long-range attraction.

Except for in highly polar materials such as water, London dispersion interactions give the largest contribution (70–100 %) to the van der Waals attraction. The interaction energy of the van der Waals force between atoms or molecules depends on the separation r as

$$E(D) = \frac{-C_{\mathrm{vdW}}}{r^6}\,, \tag{18.7}$$

where the constant C_{vdW} depends on the dipole moments and polarizabilities of the molecules. At large separations (>10 nm), the London interaction is weakened by a randomizing effect caused by the rapid fluctuations. That is, the induced temporary dipole moment of one molecule may have changed during the time needed for the transmission of the electromagnetic wave (photon) generated by its fluctuating charge density to another molecule and the return of the photon generated by the induced fluctuation in this second molecule. This phenomenon is called retardation and causes the interaction energy to decay as r^{-7} at large separations [18.79].

Dispersion interactions are to a first approximation additive, and their contribution to the interaction energy between two macroscopic bodies (such as colloidal particles) across vacuum can be found by summing the pair-wise interactions [18.80]. The interaction is generally described in terms of the Hamaker constant, A_H. Another approach is to treat the interacting bodies and an intervening medium as continuous phases and determine the strength of the interaction from bulk dielectric properties of the materials [18.81, 82]. Unlike the pair-wise summation, this method takes into account the screening of the interactions between molecules inside the bodies by the molecules closer to the surfaces and the effects of the intervening medium. For the interaction between material 1 and material 3 across material 2, the non-retarded Hamaker constant given by the Lifshitz theory

Table 18.2 Van der Waals interaction energy and force between macroscopic bodies of different geometries

Geometry of bodies with surfaces D apart ($D \ll R$)			van der Waals interaction	
			Energy, E	Force, F
Two atoms or small molecules		$r \gg \sigma$	$\frac{-C_{\mathrm{vdW}}}{r^6}$	$\frac{-6C_{\mathrm{vdW}}}{r^7}$
Two flat surfaces (per unit area)		$r \gg D$	$\frac{-A_H}{12\pi D^2}$	$\frac{-A_H}{6\pi D^3}$
Two spheres or macromolecules of radii R_1 and R_2		$R_1, R_2 \gg D$	$\frac{-A_H}{6D}\left(\frac{R_1R_2}{R_1+R_2}\right)$	$\frac{-A_H}{6D^2}\left(\frac{R_1R_2}{R_1+R_2}\right)$
Sphere or macromolecule of radius R near a flat surface		$R \gg D$	$\frac{-A_H R}{6D}$	$\frac{-A_H R}{6D^2}$
Two parallel cylinders or rods of radii R_1 and R_2 (per unit length)		$R_1, R_2 \gg D$	$\frac{-A_H}{12\sqrt{2}\,D^{3/2}}\left(\frac{R_1R_2}{R_1+R_2}\right)^{1/2}$	$\frac{-A_H}{8\sqrt{2}\,D^{5/2}}\left(\frac{R_1R_2}{R_1+R_2}\right)^{1/2}$
Cylinder of radius R near a flat surface (per unit length)		$R \gg D$	$\frac{-A_H\sqrt{R}}{12\sqrt{2}\,D^{3/2}}$	$\frac{-A_H\sqrt{R}}{8\sqrt{2}\,D^{5/2}}$
Two cylinders or filaments of radii R_1 and R_2 crossed at 90°		$R_1, R_2 \gg D$	$\frac{-A_H\sqrt{R_1R_2}}{6D}$	$\frac{-A_H\sqrt{R_1R_2}}{6D^2}$

A negative force (A_H positive) implies attraction, a positive force means repulsion (A_H negative)
(after [18.62] with permission)

is approximately [18.3]:

$$\begin{aligned}A_{\mathrm{H},123} &= A_{\mathrm{H},\nu=0} + A_{\mathrm{H},\nu>0}\\ &\approx \tfrac{3}{4} k_{\mathrm{B}} T \left(\tfrac{\varepsilon_1-\varepsilon_2}{\varepsilon_1+\varepsilon_2}\right)\left(\tfrac{\varepsilon_3-\varepsilon_2}{\varepsilon_3+\varepsilon_2}\right)\\ &+ \tfrac{3h\nu_{\mathrm{e}}}{8\sqrt{2}} \tfrac{(n_1^2-n_2^2)(n_3^2-n_2^2)}{\sqrt{(n_1^2+n_2^2)}\sqrt{(n_3^2+n_2^2)}\left(\sqrt{(n_1^2+n_2^2)}+\sqrt{(n_3^2+n_2^2)}\right)}\,, \end{aligned} \tag{18.8}$$

where the first term ($\nu = 0$) represents the permanent dipole and dipole–induced dipole interactions and the second ($\nu > 0$) the London (dispersion) interaction. ε_i and n_i are the static dielectric constants and refractive indexes of the materials, respectively. ν_{e} is the frequency of the lowest electron transition (around $3 \times 10^{15}\,\mathrm{s}^{-1}$). Either one of the materials 1, 2, or 3 in (18.8) can be vacuum or air ($\varepsilon = n = 1$). A_{H} is typically 10^{-20}–10^{-19} J (the higher values are found for metals) for interactions between solids and liquids across vacuum or air.

The interaction energy between two macroscopic bodies is dependent on the geometry and is always attractive between two bodies of the same material [A_{H} positive, see (18.8)]. The van der Waals interaction energy and force laws ($F = -\mathrm{d}E(D)/\mathrm{d}D$) for some common geometries are given in Table 18.2. Because of the retardation effect, the equations in Table 18.2 will lead to an overestimation of the dispersion force at large separations. It is, however, apparent that the interaction energy between macroscopic bodies decays more slowly with separation (i. e., has a longer range) than between two molecules.

For inert nonpolar surfaces, e.g., consisting of hydrocarbons or van der Waals solids and liquids, the Lifshitz theory has been found to apply even at molecular contact, where it can be used to predict the surface energies (surface tensions) of such solids and liquids. For example, for hydrocarbon surfaces, $A_{\mathrm{H}} = 5 \times 10^{-20}$ J. Inserting this value into the equation for two flat surfaces (Table 18.2) and using a "cut-off" distance of $D_0 \approx 0.165$ nm as an effective separation when the surfaces are in contact [18.3], we obtain for the surface energy γ (which is defined as half the interaction energy)

$$\gamma = \frac{E}{2} = \frac{A_{\mathrm{H}}}{24\pi D_0^2} \approx 24\,\mathrm{mJ\,m^{-2}}\,, \tag{18.9}$$

a value that is typical for hydrocarbon solids and liquids [18.83].

If the adhesion force is measured between a spherical surface of radius $R = 1$ cm and a flat surface using an SFA, we expect the adhesion force to be (see Table 18.2) $F = A_{\mathrm{H}}R/(6D_0^2) = 4\pi R\gamma \approx 3.0$ mN. Using a spring constant of $k_{\mathrm{s}} = 100\,\mathrm{N\,m^{-1}}$, such an adhesive force will cause the two surfaces to jump apart by $\Delta D = F/k_{\mathrm{s}} = 30\,\mu\mathrm{m}$, which can be accurately measured. (For elastic bodies that deform in adhesive contact, R changes during the interaction and the measured adhesion force is 25% lower, see Sect. 18.5.2). Surface energies of solids can thus be directly measured with the SFA and, in principle, with the AFM if the contact geometry can be quantified. The measured values are in good agreement with calculated values based on the known surface energies γ of the materials, and for nonpolar low-energy solids they are well accounted for by the Lifshitz theory [18.3].

18.3.2 Charge Exchange Interactions

Electrostatic interactions are present between ions (Coulomb interactions), between ions and permanent dipoles, and between ions and nonpolar molecules in which a charge induces a dipole moment. The interaction energy between ions or between a charge and a fixed permanent dipole can be attractive or repulsive. For an induced dipole or a freely rotating permanent dipole in vacuum or air, the interaction energy with a charge is always attractive.

Spontaneous charge transfer may occur between two dissimilar materials in contact [18.84]. The phenomenon is especially prominent in contacts between a metal, for example, mercury, and a material with low conductivity, but is also observed, for example, between two different polymer layers. During separation, rolling or sliding of one body over the other, the surfaces experience both charge transition from one surface to the other and charge transfer (conductance) along each surface (Fig. 18.4b). The latter process is typically slower, and, as a result, charges remain on the surfaces as they are separated in vacuum or dry nitrogen gas. The charging gives rise to a strong adhesion with adhesion energies of over 1,000 $\mathrm{mJ\,m^{-2}}$, similar to fracture or cohesion energies of the solid bodies themselves [18.84, 85]. Upon separating the surfaces farther apart, a strong, long-range electrostatic attraction is observed. The charging can be decreased through discharges across the gap between the surfaces (which requires a high charging) or through conducting in the solids. It has been suggested that charge exchange interactions are particularly important in rolling friction between dry surfaces (which can simplistically be thought of as an adhesion–separation process), where the distance dependence of forces acting normally to the surfaces plays a larger role than in sliding friction. Recent experiments on the sliding friction between metal–insulator surfaces indicate that stick–slip would be accompanied by charge transfer events [18.86].

Photo-induced charge transfer, or harpooning, involves the transfer of an electron between an atom in a molecular beam or at a solid surface (typically alkali or transition metal) to an atom or molecule in a gas (typically halides) to form a negatively charged molecular ion in a highly excited vibrational state. This transfer process can occur at atomic distances of 0.5–0.7 nm, which is far from molecular contact. The formed molecular ion is attracted to the surface and chemisorbs onto it. Photo-induced charge transfer processes also occur in the photosynthesis in green plants and in photoelectrochemical cells (solar cells) at the junction between two semiconductors or between a semiconductor and an electrolyte solution [18.87].

18.3.3 Sintering and Cold Welding

When macroscopic particles in a powder or in a suspension come into molecular contact, they can bond together to form a network or solid body with very different density and shear strength compared to the powder (a typical example is porcelain). The rate of bonding is dependent on the surface energy (causing a stress at the edge of the contact) and the atomic mobility (diffusion rate) of the contacting materials. To increase the diffusion rate, objects formed from powders are heated to about one-half of the melting temperature of the components in a process called sintering, which can be done in different atmospheres or in a liquid.

In the sintering process, the surface energy of the system is lowered due to the reduction of total surface area (Fig. 18.4c). In metal and ceramic systems, the most important mechanism is solid-state diffusion, initially surface diffusion. As the surface area decreases and the grain boundaries increase at the contacts, grain boundary diffusion and diffusion through the crystal lattice become more important. The grain boundaries will eventually migrate, so that larger particles are formed (coarsening). Mass can also be transferred through evaporation and condensation, and through viscous and plastic flow. In liquid-phase sintering, the materials can melt, which increases the mass transport. Amorphous materials like polymers and glasses do not have real grain boundaries and sinter by viscous flow [18.88].

Some of these mechanisms (surface diffusion and evaporation–condensation) reduce the surface area and increase the grain size (coarsening) without densification, in contrast to bulk transport mechanisms like grain boundary diffusion and plastic and viscous flow. As the material becomes denser, elongated pores collapse to form smaller, spherical pores with a lower surface energy. Models for sintering typically consider the size and growth rate of the grain boundary (the “neck”) formed between two spherical particles. At a high stage of densification, the sintering stress σ at the curved neck between two particles is given by [18.88]

$$\sigma = \frac{2\gamma_{\mathrm{SS}}}{G} + \frac{2\gamma_{\mathrm{SV}}}{r_{\mathrm{p}}}\,, \tag{18.10}$$

where γ_{SS} is the solid–solid grain boundary energy, γ_{SV} is the solid–vapor surface energy, G is the grain size, and r_{p} is the radius of the pore.

A related phenomenon is cold welding, which is the spontaneous formation of strong junctions between clean (unoxidized) metal surfaces with a mutual solubility when they are brought in contact with or without an applied pressure. The plastic deformations accompanying the formation and breaking of such contacts on a molecular scale during motion of one surface normally (see Fig. 18.10c,d) or laterally (shearing) with respect to the other have been studied both experimentally [18.89] and theoretically [18.90–95]. The breaking of a cold welded contact is generally associated with damage or deformation of the surface structure.



Fig. 18.4a–c Schematic representation of **(a)** van der Waals interaction (dipole–induced dipole interaction), **(b)** charge exchange, which acts to increase adhesion and friction forces, and **(c)** sintering between two surfaces

18.4 Normal Forces Between Surfaces in Liquids

18.4.1 Van der Waals Forces in Liquids

The dispersion interaction in a medium will be significantly lower than in vacuum, since the attractive interaction between two solute molecules in a medium (solvent) involves displacement and reorientation of the nearest-neighbor solvent molecules. Even though the surrounding medium may change the dipole moment and polarizability from that in vacuum, the interaction between two identical molecules remains attractive in a binary mixture. The extension of the interactions to the case of two macroscopic bodies is the same as described in Sect. 18.3.1. Typically, the Hamaker constants for interactions in a medium are an order of magnitude lower than in vacuum. Between macroscopic surfaces in liquids, van der Waals forces become important at distances below 10–15 nm and may at these distances start to dominate interactions of different origin that have been observed at larger separations.

Figure 18.5 shows the measured van der Waals forces between two crossed cylindrical mica surfaces in water and various salt solutions. Good agreement is obtained between experiment and theory. At larger surface separations, above about 5 nm, the measured forces fall off more rapidly than as D^{-2}. This retardation effect (see Sect. 18.3.1) is also predicted by Lifshitz theory and is due to the time needed for propagation of the induced dipole moments over large distances.



Fig. 18.5 Attractive van der Waals force F between two curved mica surfaces of radius $R \approx 1$ cm measured in water and various aqueous electrolyte solutions. The electrostatic interaction has been subtracted from the total measured force. The measured non-retarded Hamaker constant is $A_H = 2.2 \times 10^{-20}$ J. Retardation effects are apparent at distances larger than 5 nm, as expected theoretically. (After [18.3]. Copyright 1991, with permission from Elsevier Science)

From Fig. 18.5, we may conclude that at separations above about 2 nm, or 8 molecular diameters of water, the *continuum* Lifshitz theory is valid. This would mean that water films as thin as 2 nm may be expected to have bulk-like properties, at least as far as their interaction forces are concerned. Similar results have been obtained with other liquids, where in general continuum properties are manifested, both as regards their interactions and other properties such as viscosity, at a film thickness larger than 5 or 10 molecular diameters. In the absence of a solvent (in vacuum), the agreement of measured van der Waals forces with the continuum Lifshitz theory is generally good at all separations down to molecular contact ($D = D_0$).

Van der Waals interactions in a system of three or more different materials (see (18.8)) can be attractive or repulsive, depending on their dielectric properties. Numerous experimental studies show the attractive van der Waals forces in various systems [18.3], and also repulsive van der Waals forces have been measured directly [18.96]. A practical consequence of the repulsive interaction obtained across a medium with intermediate dielectric properties is that the van der Waals forces will give rise to preferential, nonspecific adsorption of molecules with an intermediate dielectric constant. This is commonly seen as adsorption of vapors or solutes to a solid surface. It is also possible to diminish the attractive interaction between dispersed colloidal particles by adsorption of a thin layer of material with dielectric properties close to those of the surrounding medium (matching of refractive index), or by adsorption of a polymer that gives a steric repulsive force that keeps the particles separated at a distance where the magnitude of the van der Waals attraction is negligible. Thermal motion will then keep the particles dispersed.

18.4.2 Electrostatic and Ion Correlation Forces

Most surfaces in contact with a highly polar liquid (such as water) acquire a surface charge, either by dissociation of ions from the surface into the solution or by preferential adsorption of certain ions from the solution.

The surface charge is balanced by a layer of oppositely charged ions (counterions) in the solution at some small distance from the surface (see [18.3]). In dilute solution, this distance is the Debye length, κ^{-1}, which is purely a property of the electrolyte *solution*. The Debye length falls with increasing ionic strength (i. e., with the molar concentration M_i and valency z_i) of the ions in solution:

$$\kappa^{-1} = \left(\frac{\varepsilon\varepsilon_0 k_\mathrm{B} T}{e^2 N_\mathrm{A} \sum_i z_i^2 M_i} \right)^{1/2} , \tag{18.11}$$

where e is the electronic charge. For example, for 1:1 electrolytes at 25 °C, $\kappa^{-1} = 0.304\,\mathrm{nm}/\sqrt{M_{1:1}}$, where M_i is given in M ($\mathrm{mol\,dm^{-3}}$). κ^{-1} is thus ca. 10 nm in a 1 mM NaCl solution and 0.3 nm in a 1 M solution. In totally pure water at pH 7, where $M_i = 10^{-7}$ M, κ^{-1} is 960 nm, or about 1 µm. The Debye length also relates the surface charge density σ of a surface to the electrostatic surface potential ψ_0 via the Grahame equation, which for 1:1 electrolytes can be expressed as:

$$\sigma = \sqrt{8\varepsilon\varepsilon_0 k_\mathrm{B} T}\,\sinh\left(e\psi_0/2k_\mathrm{B}T\right) \times \sqrt{M_{1:1}} \,. \tag{18.12}$$

Since the Debye length is a measure of the thickness of the diffuse atmosphere of counterions near a charged surface, it also determines the range of the electrostatic "double-layer" interaction between two charged surfaces. The electrostatic double-layer interaction is an entropic effect that arises upon decreasing the thickness of the liquid film containing the dissolved ions. Because of the attractive force between the dissolved ions and opposite charges on the surfaces, the ions stay between the surfaces, but an osmotic repulsion arises as their concentration increases. The long-range electrostatic interaction energy at large separations (weak overlap) between two similarly charged molecules or surfaces is typically repulsive and is roughly an exponentially decaying function of D:

$$E(D) \approx +C_\mathrm{ES}\,\mathrm{e}^{-\kappa D} , \tag{18.13}$$

where C_ES is a constant that depends on the geometry of the interacting surfaces, on their surface charge density, and the solution conditions (Table 18.3). We see that the Debye length is the decay length of the interaction energy between two surfaces (and of the mean potential away from one surface). C_ES can be determined by solving the so-called Poisson–Boltzmann equation or by using other theories [18.97, 98]. The equations in Table 18.3 are expressed in terms of a constant, Z, defined as

$$Z = 64\pi\varepsilon\varepsilon_0 (k_\mathrm{B}T/e)^2 \tanh^2\left[ze\psi_0/(4k_\mathrm{B}T)\right] , \tag{18.14}$$

which depends only on the properties of the *surfaces*.

The above approximate expressions are accurate only for surface separations larger than about one Debye length. At smaller separations one must use numerical solutions of the Poisson–Boltzmann equation to obtain the exact interaction potential, for which there are no simple expressions. In the limit of small D, it can be shown that the interaction energy depends on whether the surfaces remain at constant potential ψ_0 (as assumed in the above equations) or at constant charge σ (when the repulsion exceeds that predicted by the above equations), or somewhere between these limits. In the "constant charge limit" the total *number* of counterions in the compressed film does not change as D is decreased, whereas at constant potential, the *concentration* of counterions is constant.The limiting pressure (or force per unit area) at constant charge is the osmotic pressure of the confined ions:

$$\begin{aligned} F &= k_\mathrm{B}T \times \text{ion number density} \\ &= 2\sigma k_\mathrm{B}T/(zeD), \quad \text{for } D \ll \kappa^{-1} . \end{aligned} \tag{18.15}$$

That is, as $D \to 0$ the double-layer pressure at constant surface charge becomes infinitely repulsive and independent of the salt concentration (at constant potential the force instead becomes a constant at small D). However, at small separations, the van der Waals attraction (which goes as D^{-2} between two spheres or as D^{-3} between two planar surfaces, see Table 18.2) wins out over the double-layer repulsion, unless some other short-range interaction becomes dominant (see Sect. 18.4.4). This is the theoretical prediction that forms the basis of the so-called Derjaguin–Landau–Verwey–Overbeek (DLVO) theory [18.97, 99], illustrated in Fig. 18.6.

Because of the different distance dependence of the van der Waals and electrostatic interactions, the total force law, as described by the DLVO theory, can show several minima and maxima. Typically, the depth of the outer (secondary) minimum is a few $k_\mathrm{B}T$, enough to cause reversible flocculation of particles from an aqueous dispersion. If the force barrier between the secondary and primary minimum is lowered, for example, by increasing the electrolyte concentration, particles can be irreversibly coagulated in the primary minimum. In practice, other forces (described

Table 18.3 Electrical "double-layer" interaction energy $E(D)$ and force ($F = -\mathrm{d}E/\mathrm{d}D$) between macroscopic bodies

Geometry of bodies with surfaces D apart ($D \ll R$)			**Electric "double-layer" interaction**	
			Energy, E	**Force, F**
Two ions or small molecules	 z_1e r z_2e Solvent ε σ	$r \gg \sigma$	$\dfrac{+z_1z_2e^2}{4\pi\varepsilon\varepsilon_0 r}\dfrac{e^{-\kappa(r-\sigma)}}{(1+\kappa\sigma)}$	$\dfrac{+z_1z_2e^2}{4\pi\varepsilon\varepsilon_0 r^2}\dfrac{(1+\kappa r)}{(1+\kappa\sigma)}e^{-\kappa(r-\sigma)}$
Two flat surfaces (per unit area)		$r \gg D$	$(\kappa/2\pi)\,Z\mathrm{e}^{-\kappa D}$	$\left(\kappa^2/2\pi\right)Z\mathrm{e}^{-\kappa D}$
Two spheres or macromolecules of radii R_1 and R_2		$R_1,\, R_2 \gg D$	$\left(\dfrac{R_1R_2}{R_1+R_2}\right)Z\mathrm{e}^{-\kappa D}$	$\kappa\left(\dfrac{R_1R_2}{R_1+R_2}\right)Z\mathrm{e}^{-\kappa D}$
Sphere or macromolecule of radius R near a flat surface		$R \gg D$	$RZ\mathrm{e}^{-\kappa D}$	$\kappa RZ\mathrm{e}^{-\kappa D}$
Two parallel cylinders or rods of radii R_1 and R_2 (per unit length)		$R_1,\, R_2 \gg D$	$\dfrac{\kappa^{1/2}}{\sqrt{2\pi}}\left(\dfrac{R_1R_2}{R_1+R_2}\right)^{1/2}Z\mathrm{e}^{-\kappa D}$	$\dfrac{\kappa^{3/2}}{\sqrt{2\pi}}\left(\dfrac{R_1R_2}{R_1+R_2}\right)^{1/2}Z\mathrm{e}^{-\kappa D}$
Cylinder of radius R near a flat surface (per unit length)		$R \gg D$	$\kappa^{1/2}\sqrt{\dfrac{R}{2\pi}}Z\mathrm{e}^{-\kappa D}$	$\kappa^{3/2}\sqrt{\dfrac{R}{2\pi}}Z\mathrm{e}^{-\kappa D}$
Two cylinders or filaments of radii R_1 and R_2 crossed at 90°		$R_1,\, R_2 \gg D$	$\sqrt{R_1R_2}Z\mathrm{e}^{-\kappa D}$	$\kappa\sqrt{R_1R_2}Z\mathrm{e}^{-\kappa D}$

The interaction energy and force for bodies of different geometries is based on the Poisson–Boltzmann equation (a continuum, mean-field theory). Equation (18.14) gives the interaction constant Z (in terms of surface potential ψ_0) for the interaction between similarly charged (ionized) surfaces in aqueous solutions of monovalent electrolyte. It can also be expressed in terms of the surface charge density σ by applying the Grahame equation (18.12) (after [18.62] with permission)

in the following sections) often appear at very small separations, so that the full force law between two surfaces or colloidal particles in solution can be more complex than might be expected from the DLVO theory.

There are situations when the double-layer interaction can be attractive at short range even between surfaces of similar charge, especially in systems with charge regulation due to dissociation of chargeable groups on the surfaces [18.100]; ion condensa-



Fig. 18.6 Schematic plots of the DLVO interaction potential energy E between two flat, charged surfaces (or, according to the Derjaguin approximation, (18.3), the force F between two curved surfaces) as a function of the surface separation normalized by the Debye length, κ^{-1}. The van der Waals attraction (inverse power-law dependence on D) together with the repulsive electrostatic "double-layer" force (roughly exponential) at different surface charge σ (or potential, see (18.12)) determine the net interaction potential in aqueous electrolyte solution (after [18.62] with permission)

tion [18.101], which may lower the effective surface charge density in systems containing di-and trivalent counterions; or ion correlation, which is an additional van der Waals-like attraction due to mobile and therefore highly polarizable counterions located at the surface [18.102]. The ion correlation (or charge fluctuation) force becomes significant at separations below 4 nm and increases with the surface charge density σ and the valency z of the counterions. Computer simulations have shown that at high charge density and monovalent counterions, the ion correlation force can reduce the effective double-layer repulsion by 10–15 %. With divalent counterions, the ion correlation force was found to exceed the double-layer repulsion and the total force then became attractive at a separation below 2 nm even in dilute electrolyte solution [18.103]. Experimentally, such short-range attractive forces have been found in charged bilayer systems [18.104, 105].

18.4.3 Solvation and Structural Forces

When a liquid is confined within a restricted space, for example, a very thin film between two surfaces, it ceases to behave as a structureless continuum. At small surface separations (below about 10 molecular diameters), the van der Waals force between two surfaces or even two solute molecules in a liquid (solvent) is no longer a smoothly varying attraction. Instead, there arises an additional "solvation" force that generally oscillates between attraction and repulsion with distance, with a periodicity equal to some mean dimension σ of the liquid molecules [18.106]. Figure 18.7a shows the force law between two smooth mica surfaces across the hydrocarbon liquid tetradecane, whose inert, chain-like molecules have a width of $\sigma \approx 0.4$ nm.

The short-range oscillatory force law is related to the "density distribution function" and "potential of mean force" characteristic of intermolecular interactions in liquids. These forces arise from the confining effects two surfaces have on liquid molecules, forcing them to order into quasi-discrete layers. Such layers are energetically or entropically favored and correspond to the minima in the free energy, whereas fractional layers are disfavored (energy maxima). This effect is quite general and arises in all simple liquids when they are confined between two smooth, rigid surfaces, both flat and curved. Oscillatory forces do not require any attractive liquid–liquid or liquid–wall interaction, only two hard walls confining molecules whose shape is not too irregular and that are free to exchange with molecules in a bulk liquid reservoir. In the absence of any attractive pressure between the molecules, the bulk liquid density could be maintained by an external hydrostatic pressure – in real liquids attractive van der Waals forces play the role of such an external pressure.

Oscillatory forces are now well understood theoretically, at least for simple liquids, and a number of theoretical studies and computer simulations of various confined liquids (including water) that interact via some form of Lennard-Jones potential have invariably led to an oscillatory solvation force at surface separations below a few molecular diameters [18.107–114]. In a first approximation, the oscillatory force law may be described by an exponentially decaying cosine function of the form

$$E \approx E_0 \cos(2\pi D/\sigma)\,\mathrm{e}^{-D/\sigma}\,, \tag{18.16}$$

where both theory and experiments show that the oscillatory period and the characteristic decay length of the envelope are close to σ.



Fig. 18.7 **(a)** *Solid curve:* Forces measured between two mica surfaces across saturated linear chain alkanes such as *n*-tetradecane and *n*-hexadecane [18.115, 116]. The 0.4 nm periodicity of the oscillations indicates that the molecules are preferentially oriented parallel to the surfaces, as shown schematically in the *upper insert*. The theoretical continuum van der Waals attraction is shown as a *dotted curve*. *Dashed curve:* Smooth, non-oscillatory force law exhibited by irregularly shaped alkanes (such as 2-methyloctadecane) that cannot order into well-defined layers (*lower insert*) [18.116, 117]. Similar non-oscillatory forces are also observed between "rough" surfaces, even when these interact across a saturated linear chain liquid. This is because the irregularly shaped surfaces (rather than the liquid) now prevent the liquid molecules from ordering in the gap. **(b)** Forces measured between charged mica surfaces in KCl solutions of varying concentrations [18.20]. In dilute solutions (10^{-5} and 10^{-4} M), the measured forces are excellently described by the DLVO theory, based on exact solutions to the nonlinear Poisson–Boltzmann equation for the electrostatic forces and the Lifshitz theory for the van der Waals forces (using a Hamaker constant of $A_\mathrm{H} = 2.2\times10^{-20}$ J). At higher concentrations, as more hydrated K^+ cations adsorb onto the negatively charged surfaces, an additional hydration force appears superimposed on the DLVO interaction at distances below 3–4 nm. This force has both an oscillatory and a monotonic component. *Insert:* Short-range hydration forces between mica surfaces shown as pressure versus distance. The lower and upper curves show surfaces 40% and 95% saturated with K^+ ions. At larger separations, the forces are in good agreement with the DLVO theory. (After [18.3]. Copyright 1991, with permission from Elsevier Science)

Once the solvation zones of the two surfaces overlap, the mean liquid density in the gap is no longer the same as in the bulk liquid. Since the van der Waals interaction depends on the optical properties of the liquid, which in turn depends on the density, the van der Waals and the oscillatory solvation forces are not strictly additive. It is more correct to think of the solvation force as *the* van der Waals force at small separations with the molecular properties and density variations of the medium taken into account. It is also important to appreciate that solvation forces do not arise simply because liquid molecules tend to structure into semi-ordered layers at surfaces. They arise because of the disruption or *change* of this ordering during the approach of a second surface. The two effects are related; the greater the tendency toward structuring at an isolated surface the greater the solvation force between two such surfaces, but there is a real distinction between the two phenomena that should be borne in mind.

Oscillatory forces lead to different adhesion values depending on the energy minimum from which two surfaces are being separated. For an interaction energy described by (18.16), "quantized" adhesion energies will be E_0 at $D = 0$ (primary minimum), E_0/e at $D = \sigma$, E_0/e^2 at $D = 2\sigma$, etc. E_0 can be thought of as a depletion force (see Sect. 18.4.5) that is approximately given by the osmotic limit $E_0 \approx -k_\mathrm{B}T/\sigma^2$, which can exceed the contribution to the adhesion energy in contact from the van der Waals forces (at $D_0 \approx 0.15$–0.20 nm, as discussed in Sect. 18.3.1, keeping in mind that the

Lifshitz theory fails to describe the force law at *intermediate* distances). Such multivalued adhesion forces have been observed in a number of systems, including the interactions of fibers.

Measurements of oscillatory forces between different surfaces across both aqueous and nonaqueous liquids have revealed their richness of properties [18.118–121], for example, their great sensitivity to the shape and rigidity of the solvent molecules, to the presence of other components, and to the structure of the confining surfaces (see Sects. 18.5.3 and 18.9). In particular, the oscillations can be smeared out if the molecules are irregularly shaped (e.g., branched) and therefore unable to pack into ordered layers, or when the interacting surfaces are rough or fluid-like (see Sect. 18.4.6).

It is easy to understand how oscillatory forces arise between two flat, plane parallel surfaces. Between two curved surfaces, e.g., two spheres, one might imagine the molecular ordering and oscillatory forces to be smeared out in the same way that they are smeared out between two randomly rough surfaces (see Sect. 18.5.3); however, this is not the case. Ordering can occur so long as the curvature or roughness is itself regular or uniform, i. e., not random. This is due to the Derjaguin approximation (18.3). If the energy between two flat surfaces is given by a decaying oscillatory function (for example, a cosine function as in (18.16)), then the force (and energy) between two curved surfaces will also be an oscillatory function of distance with some phase shift. Likewise, two surfaces with regularly curved regions will also retain their oscillatory force profile, albeit modified, as long as the corrugations are truly regular, i. e., periodic. On the other hand, surface roughness, even on the nanometer scale, can smear out oscillations if the roughness is random and the confined molecules are smaller than the size of the surface asperities [18.122, 123]. If an organic liquid contains small amounts of water, the expected oscillatory force can be replaced by a strongly attractive capillary force (see Sect. 18.5.1).

18.4.4 Hydration and Hydrophobic Forces

The forces occurring in water and electrolyte solutions are more complex than those occurring in nonpolar liquids. According to continuum theories, the attractive van der Waals force is always expected to win over the repulsive electrostatic "double-layer" force at small surface separations (Fig. 18.6). However, certain surfaces (usually oxide or hydroxide surfaces such as clays or silica) swell spontaneously or repel each other in aqueous solution, even at high salt concentrations. Yet in all these systems one would expect the surfaces or particles to remain in strong adhesive contact or coagulate in a primary minimum if the only forces operating were DLVO forces.

There are many other aqueous systems in which the DLVO theory fails and where there is an additional short-range force that is not oscillatory but monotonic. Between hydrophilic surfaces this force is exponentially repulsive and is commonly referred to as the *hydration*, or *structural*, force. The origin and nature of this force has long been controversial, especially in the colloidal and biological literature. Repulsive hydration forces are believed to arise from strongly hydrogen-bonding surface groups, such as hydrated ions or hydroxyl (−OH) groups, which modify the hydrogen-bonding network of liquid water adjacent to them. Because this network is quite extensive in range [18.124], the resulting interaction force is also of relatively long range.

Repulsive hydration forces were first extensively studied between clay surfaces [18.125]. More recently, they have been measured in detail between mica and silica surfaces [18.20–22], where they have been found to decay exponentially with decay lengths of about 1 nm. Their effective range is about 3 to 5 nm, which is about twice the range of the oscillatory solvation force in water. Empirically, the hydration repulsion between two hydrophilic surfaces appears to follow the simple equation

$$E = E_0\,\mathrm{e}^{-D/\lambda_0}\,, \tag{18.17}$$

where $\lambda_0 \approx 0.6{-}1.1\,\mathrm{nm}$ for 1:1 electrolytes and $E_0 = 3{-}30\,\mathrm{mJ\,m^{-2}}$ depending on the hydration (hydrophilicity) of the surfaces, higher E_0 values generally being associated with lower λ_0 values.

The interactions between molecularly smooth mica surfaces in dilute electrolyte solutions obey the DLVO theory (Fig. 18.7b). However, at higher salt concentrations, specific to each electrolyte, hydrated cations bind to the negatively charged surfaces and give rise to a repulsive hydration force [18.20, 21]. This is believed to be due to the energy needed to dehydrate the bound cations, which presumably retain some of their water of hydration on binding. This conclusion was arrived at after noting that the strength and range of the hydration forces increase with the known hydration numbers of the electrolyte cations in the order: $\mathrm{Mg^{2+} > Ca^{2+} > Li^{+} \sim Na^{+} > K^{+} > Cs^{+}}$. Similar trends are observed with other negatively charged colloidal surfaces.

While the hydration force between two mica surfaces is overall repulsive below a distance of 4 nm, it is not always monotonic below about 1.5 nm but exhibits oscillations of mean periodicity of 0.25 ± 0.03 nm, roughly equal to the diameter of the water molecule. This is shown in the insert in Fig. 18.7b, where we may note that the first three minima at $D = 0$, 0.28, and 0.56 nm occur at negative energies, a result that rationalizes observations on certain colloidal systems. For example, clay platelets such as montmorillonite often repel each other increasingly strongly as they come closer together, but they are also known to stack into stable aggregates with water interlayers of typical thickness 0.25 and 0.55 nm between them [18.126,127], suggestive of a turnabout in the force law from a monotonic repulsion to discretized attraction. In chemistry we would refer to such structures as stable hydrates of fixed stoichiometry, whereas in physics we may think of them as experiencing an oscillatory force.

Both surface force and clay swelling experiments have shown that hydration forces can be modified or "regulated" by exchanging ions of different hydration on surfaces, an effect that has important practical applications in controlling the stability of colloidal dispersions. It has long been known that colloidal particles can be precipitated (coagulated or flocculated) by increasing the electrolyte concentration, an effect that was traditionally attributed to the reduced screening of the electrostatic double-layer repulsion between the particles due to the reduced Debye length. However, there are many examples where colloids are stabilized at high salt concentrations, not at low concentrations. This effect is now recognized as being due to the increased hydration repulsion experienced by certain surfaces when they bind highly hydrated ions at higher salt concentrations. Hydration regulation of adhesion and interparticle forces is an important practical method for controlling various processes such as clay swelling [18.126, 127], ceramic processing and rheology [18.128, 129], material fracture [18.128], and colloidal particle and bubble coalescence [18.130].

Water appears to be unique in having a solvation (hydration) force that exhibits both a monotonic and an oscillatory component. Between hydrophilic surfaces the monotonic component is repulsive (Fig. 18.7b), but between hydrophobic surfaces it is attractive and the final adhesion is much greater than expected from the Lifshitz theory.

A hydrophobic surface is one that is inert to water in the sense that it cannot bind to water molecules via ionic or hydrogen bonds. Hydrocarbons and fluorocarbons are hydrophobic, as is air, and the strongly attractive hydrophobic force has many important manifestations and consequences such as the low solubility or miscibility of water and oil molecules, micellization, protein folding, strong adhesion and rapid coagulation of hydrophobic surfaces, non-wetting of water on hydrophobic surfaces, and hydrophobic particle attachment to rising air bubbles (the basic principle of froth flotation).

In recent years, there has been a steady accumulation of experimental data on the force laws between various hydrophobic surfaces in aqueous solution [18.131–143]. These studies have found that the hydrophobic force law between two macroscopic surfaces is of surprisingly long range, decaying exponentially with a characteristic decay length of 1 to 2 nm in the separation range of 0 to 10 nm, and then more gradually further out. The hydrophobic force can be far stronger than the van der Waals attraction, especially between hydrocarbon surfaces in water, for which the Hamaker constant is quite small. The magnitude of the hydrophobic attraction has been found to decrease with the decreasing hydrophobicity (increasing hydrophilicity) of lecithin lipid bilayer surfaces [18.31] and silanated surfaces [18.139], whereas examples of the opposite trend have been shown for some Langmuir–Blodgett-deposited monolayers [18.144].

For two surfaces in water the purely hydrophobic interaction energy (ignoring DLVO and oscillatory forces) in the range of 0 to 10 nm is given by

$$E = -2\gamma\, \mathrm{e}^{-D/\lambda_0}\,, \tag{18.18}$$

where typically $\lambda_0 = 1{-}2$ nm, and $\gamma = 10{-}50\,\mathrm{mJ\,m^{-2}}$. The higher value corresponds to the interfacial energy of a pure hydrocarbon–water interface.

At a separation below 10 nm, the hydrophobic force appears to be insensitive or only weakly sensitive to changes in the type and concentration of electrolyte ions in the solution. The absence of a "screening" effect by ions attests to the non-electrostatic origin of this interaction. In contrast, some experiments have shown that at separations greater than 10 nm, the attraction does depend on the intervening electrolyte, and that in dilute solutions, or solutions containing divalent ions, it can continue to exceed the van der Waals attraction out to separations of 80 nm [18.136, 145].

The long-range nature of the hydrophobic interaction has a number of important consequences. It accounts for the rapid coagulation of hydrophobic particles in water and may also account for the rapid folding of proteins. It also explains the ease with which water films rupture on hydrophobic surfaces. In this case, the van der Waals force across the water film is repulsive and therefore favors wetting, but this is more than offset by the attractive hydrophobic interaction acting between the two hydrophobic phases across water. Hydrophobic forces are increasingly being implicated in the adhesion and fusion of biological membranes and cells. It is known that both osmotic and electric field stresses enhance membrane fusion, an effect that may be due to the concomitant increase in the hydrophobic area exposed between two adjacent surfaces.

From the previous discussion we can infer that hydration and hydrophobic forces are not of a simple nature. These interactions are probably the most important, yet the least understood of all the forces in aqueous solutions. The unusual properties of water and the nature of the surfaces (including their homogeneity and stability) appear to be equally important. Some particle surfaces can have their hydration forces regulated, for example, by ion exchange. Others appear to be intrinsically hydrophilic (e.g., silica) and cannot be coagulated by changing the ionic condition, but can be rendered hydrophobic by chemically modifying their surface groups. For example, on heating silica to above 600 °C, two adjacent surface silanol (−OH) groups release a water molecule and form a hydrophobic siloxane (−O−) group, whence the repulsive hydration force changes into an attractive hydrophobic force.

How do these exponentially decaying repulsive or attractive forces arise? Theoretical work and computer simulations [18.109, 111, 146, 147] suggest that the solvation forces in water should be purely oscillatory, whereas other theoretical studies [18.148–153] suggest a monotonically exponential repulsion or attraction, possibly superimposed on an oscillatory force. The latter is consistent with experimental findings, as shown in the inset to Fig. 18.7b, where it appears that the oscillatory force is simply additive with the monotonic hydration and DLVO forces, suggesting that these arise from essentially different mechanisms.

It is probable that the short-range hydration force between all smooth, rigid, or crystalline surfaces (e.g., mineral surfaces such as mica) has an oscillatory component. This may or may not be superimposed on a monotonic force due to image interactions [18.150] and/or structural or hydrogen bonding interactions [18.148, 149].

Like the repulsive hydration force, the origin of the hydrophobic force is still unknown. *Luzar* et al. [18.152] carried out a Monte Carlo simulation of the interaction between two hydrophobic surfaces across water at separations below 1.5 nm. They obtained a decaying oscillatory force superimposed on a monotonically attractive curve. In more recent work [18.154, 155], it has been suggested that hydrophobic surfaces generate a depleted region of water around them, and that a long-range attractive force due to depletion arises between two such surfaces.

It is questionable whether the hydration or hydrophobic force should be viewed as an ordinary type of solvation or structural force that is reflecting the packing of water molecules. The energy (or entropy) associated with the hydrogen bonding network, which extends over a much larger region of space than the molecular correlations, is probably at the root of the long-range interactions of water. The situation in water appears to be governed by much more than the molecular packing effects that dominate the interactions in simpler liquids.

18.4.5 Polymer-Mediated Forces

Polymers or macromolecules are chain-like molecules consisting of many identical segments (monomers or repeating units) held together by covalent bonds. The size of a polymer coil in solution or in the melt is determined by a balance between van der Waals attraction (and hydrogen bonding, if present) between polymer segments, and the entropy of mixing, which causes the polymer coil to expand. In polymer melts above the glass transition temperature, and at certain conditions in solution, the attraction between polymer segments is exactly balanced by the entropy effect. The polymer solution will then behave virtually ideally, and the density distribution of segments in the coil is Gaussian. This is called the theta (θ) condition, and it occurs at the theta or Flory temperature for a particular combination of polymer and solvent or solvent mixture. At lower temperatures (in a poor or bad solvent), the polymer–polymer interactions dominate over the entropic, and the coil will shrink or precipitate. At higher temperatures (good solvent conditions), the polymer coil will be expanded.

High molecular weight polymers form large coils, which significantly affect the properties of a solution even when the total mass of polymer is very low. The radius of the polymer coil is proportional to the segment length, a, and the number of segments, n. At theta conditions, the hydrodynamic radius of the polymer coil (the root-mean-square separation of the ends of one polymer chain) is theoretically given by $R_\mathrm{h} = a\,n^{1/2}$, and the unperturbed radius of gyration (the average root-mean-square distance of a segment from the center of mass of the molecule) is $R_\mathrm{g} = a\ (n/6)^{1/2}$. In a good solvent the perturbed size of the polymer coil, the Flory radius R_F, is proportional to $n^{3/5}$.

Polymers interact with surfaces mainly through van der Waals and electrostatic interactions. The physisorption of polymers containing only one type of segment is reversible and highly dynamic, but the rate of exchange of adsorbed chains with free chains in the solution is low, since the polymer remains bound to the surface as long as one segment along the chain is adsorbed. The adsorption energy per segment is on the order of k_BT. In a good solvent, the conformation of a polymer on a surface is very different from the coil conformation in bulk solution. Polymers adsorb in "trains", separated by "loops" extending into solution and dangling "tails" (the ends of the chain). Compared to adsorption at lower temperatures, good solvent conditions favor more of the polymer chain being in the solvent, where it can attain its optimum conformation. As a result, the extension of the polymer is longer, even though the total amount of adsorbed polymer is lower. In a good solvent, the polymer chains can also be effectively repelled from a surface, if the loss in conformational entropy close to the surface is not compensated for by a gain in enthalpy from adsorption of segments. In this case, there will be a layer of solution (thickness $\approx R_g$) close to the surfaces that is depleted of polymer.

The interaction forces between two surfaces across a polymer solution will depend on whether the polymer is adsorbing onto the surfaces or is repelled from them, and also on whether the interaction occurs at "true" or "restricted" thermodynamic equilibrium. At true or full equilibrium, the polymer between the surfaces can equilibrate (exchange) with polymer in the bulk solution at all surface separations. Some theories [18.156, 157] predict that at full equilibrium, the polymer chains would move from the confined gap into the bulk solution where they could attain entropically more favorable conformations, and that a monotonic attraction at all distances would result from bridging and depletion interactions (which will be discussed below). Other theories suggest that the interaction at small separations would be ultimately repulsive, since some polymer chains would remain in the gap due to their attractive interactions with many sites on the surface (enthalpic) – more sites would be available to the remaining polymer chains if some others desorbed and diffused out from the gap [18.64, 158, 159].

At restricted equilibrium, the polymer is kinetically trapped, and the adsorbed amount is thus constant as the surfaces are brought toward each other, but the chains can still rearrange on the surfaces and in the gap. Experimentally, the true equilibrium situation is very difficult to attain, and most experiments are done at restricted equilibrium conditions. Even the equilibration of conformations assumed in theoretical models for restricted equilibrium conditions can be so slow that this condition is difficult to reach.

In systems of adsorbing polymer, bridging of chains from one surface to the other can give rise to a long-range attraction, since the bridging chains would gain conformational entropy if the surfaces were closer together. In poor solvents, both bridging and intersegment interactions contribute to an attraction [18.26]. However, regardless of solvent and equilibrium conditions, a strong repulsion due to the osmotic interactions is seen as small surface separations in systems of adsorbing polymers at restricted equilibrium.

In systems containing high concentrations of non-adsorbing polymer, the difference in solute concentration in the bulk and between the surfaces at separations smaller than the approximate polymer coil diameter ($2R_g$, i. e., when the polymer has been squeezed out from the gap between the surfaces) may give rise to an attractive osmotic force ("depletion attraction") [18.160–164]. In addition, if the polymer coils become initially compressed as the surfaces approach each other, this can give rise to a repulsion ("depletion stabilization") at large separations [18.163]. For a system of two cylindrical surfaces or radius R, the maximum depletion force, F_{dep}, is expected to occur when the surfaces are in contact and is given by multiplying the depletion (osmotic) pressure, $P_{dep} = \rho k_B T$, by the contact area πr^2, where r is given by the chord theorem: $r^2 = (2R - R_g)R_g \approx 2RR_g$ [18.3]:

$$F_{dep}/R = -2\pi R_g \rho k_B T \ , \qquad (18.19)$$

where ρ is the number density of the polymer in the bulk solution.

If a part of the polymer (typically an end group) is different from the rest of the chain, this part may preferentially adsorb to the surface. End-adsorbed polymer is attached to the surface at only one point, and the extension of the chain is dependent on the grafting density, i. e., the average distance, s, between adsorbed end groups on the surface (Fig. 18.8). One distinguishes between different regions of increasing overlap of the chains (stretching) called pancake, mushroom, and brush regimes [18.165]. In the mushroom regime, where the coverage is sufficiently low so that there is no overlap between neighboring chains, the thickness of the adsorbed layer is proportional to $n^{1/2}$ (i. e., to R_g) at theta conditions and to $n^{3/5}$ in a good solvent.



Fig. 18.8a,b Experimentally determined forces in systems of two interacting polymer brushes: **(a)** Polystyrene brush layers grafted via an adsorbing chain-end group onto mica surfaces in toluene (a good solvent for polystyrene). *Left curve:* MW = 26,000 g/mol, $R_F = 12$ nm. *Right curve*: MW = 140,000 g/mol, $R_F = 32$ nm. Both force curves were reversible on approach and separation. The *solid curves* are theoretical fits using the Alexander–de Gennes theory with the following measured parameters: spacing between attachments sites: $s = 8.5$ nm, brush thickness: $L = 22.5$ nm and 65 nm, respectively. (Adapted from [18.171]). **(b)** Polyethylene oxide layers physisorbed onto mica from 150 μg/ml solution in aqueous 0.1 M KNO_3 (a good solvent for polyethylene oxide). *Main figure:* Equilibrium forces at full coverage after ∼ 16 h adsorption time. *Left curve:* MW = 160,000 g/mol, $R_g = 32$ nm. *Right curve:* MW = 1,100,000 g/mol, $R_g = 86$ nm. Note the hysteresis (irreversibility) on approach and separation for this *physisorbed* layer, in contrast to the absence of hysteresis with *grafted* chains in case **(a)**. The *solid curves* are based on a modified form of the Alexander–de Gennes theory. *Inset* in **(b)**: Evolution of the forces with the time allowed for the higher MW polymer to adsorb from solution. Note the gradual reduction in the attractive bridging component. (Adapted from [18.172–174]. After [18.3]. Copyright 1991, with permission from Elsevier Science)

Several models [18.165–170] have been developed for the extension and interactions between two brushes (strongly stretched grafted chains). They are based on a balance between osmotic pressure within the brush layers (uncompressed and compressed) and elastic energy of the chains and differ mainly in the assumptions of the segment density profile, which can be a step function or parabolic. At high coverage (in the brush regime),where the chains will avoid overlapping each other, the thickness of the layer is proportional to n.

Experimental work on both monodisperse [18.27,28, 171, 175] and polydisperse [18.30] systems at different solvent conditions has confirmed the expected range and magnitude of the repulsive interactions resulting from compression of densely packed grafted layers.

18.4.6 Thermal Fluctuation Forces

If a surface is not rigid but very soft or even fluid-like, this can act to smear out any oscillatory solvation force. This is because the thermal fluctuations of such interfaces make them dynamically “rough” at any instant, even though they may be perfectly smooth on a time average. The types of surfaces that fall into this category are fluid-like amphiphilic surfaces of micelles, bilayers, emulsions, soap films, etc., but also solid colloidal particle surfaces that are coated with surfactant monolayers, as occurs in lubricating oils, paints, toners, etc.

These thermal fluctuation forces (also called entropic or steric forces) are usually short-range and repulsive and are very effective at stabilizing the attractive van der Waals forces at some small but finite separation. This can reduce the adhesion energy or force by up to three orders of magnitude. It is mainly for this reason that fluid-like micelles and bilayers, biological membranes, emulsion droplets, or gas bubbles adhere to each other only very weakly.

Because of their short range it was, and still is, commonly believed that these forces arise from water ordering or "structuring" effects at surfaces, and that they reflect some unique or characteristic property of water. However, it is now known that these repulsive forces also exist in other liquids. Moreover, they appear to become stronger with increasing temperature, which is unlikely if the force would originate from molecular ordering effects at surfaces. Recent experiments, theory, and computer simulations [18.176–178] have shown that these repulsive forces have an entropic origin arising from the osmotic repulsion between exposed thermally mobile surface groups once these overlap in a liquid. These phenomena include undulating and peristaltic forces between membranes or bilayers, and, on the molecular scale, protrusion and head group overlap forces where the interactions also are influenced by hydration forces.

18.5 Adhesion and Capillary Forces

18.5.1 Capillary Forces

When considering the adhesion of two solid surfaces or particles in air or in a liquid, it is easy to overlook or underestimate the important role of capillary forces, i. e., forces arising from the Laplace pressure of curved menisci formed by condensation of a liquid between and around two adhering surfaces (Fig. 18.9).



Fig. 18.9a–c Adhesion and capillary forces: **(a)** a non-deforming sphere on a rigid, flat surface in an inert atmosphere and **(b)** in a vapor that can "capillary condense" around the contact zone. At equilibrium, the concave radius, r, of the liquid meniscus is given by the Kelvin equation. For a concave meniscus to form, the contact angle θ has to be less than 90°. In the case of hydrophobic surfaces surrounded by water, a vapor cavity can form between the surfaces. As long as the surfaces are perfectly smooth, the contribution of the meniscus to the adhesion force is independent of r. (After [18.1] with permission.) **(c)** Elastically deformable sphere on a rigid flat surface in the absence (Hertz) and presence (JKR) of adhesion [**(a)** and **(c)** after [18.3]. Copyright 1991, with permission from Elsevier Science]

The adhesion force between a non-deformable spherical particle of radius R and a flat surface in an inert atmosphere (Fig. 18.9a) is

$$F_s = 4\pi R \gamma_{SV} \ . \qquad (18.20)$$

But in an atmosphere containing a condensable vapor, the expression above is replaced by

$$F_s = 4\pi R(\gamma_{LV} \cos\theta + \gamma_{SL}) \ , \qquad (18.21)$$

where the first term is due to the Laplace pressure of the meniscus and the second is due to the direct adhesion of the two contacting solids within the liquid. Note that the above equation does not contain the radius of curvature, r, of the liquid meniscus (see Fig. 18.9b). This is because for smaller r the Laplace pressure γ_{LV}/r increases, but the area over which it acts decreases by the same amount, so the two effects cancel out. Experiments with inert liquids, such as hydrocarbons, condensing between two mica surfaces indicate that (18.21) is valid for values of r as small as 1–2 nm, corresponding to vapor pressures as low as 40% of saturation [18.121, 179, 180]. Capillary condensation also occurs in binary liquid systems, e.g., when water dissolved in hydrocarbon liquids condense around two contacting hydrophilic surfaces or when a vapor cavity forms in water around two hydrophobic surfaces. In the case of water condensing from vapor or from oil, it also appears that the bulk value of γ_{LV} is applicable for meniscus radii as small as 2 nm.

The capillary condensation of liquids, especially water, from vapor can have additional effects on the



Fig. 18.10a–d Experimental and computer simulation data on contact mechanics for ideal Hertz and JKR contacts. **(a)** Measured profiles of surfaces in nonadhesive contact (*circles*) compared with Hertz profiles (*continuous curves*). The system was mica surfaces in a concentrated KCl solution in which they do not adhere. When not in contact, the surface shape is accurately described by a sphere of radius $R = 1.55$ cm (*inset*). The applied loads were 0.01, 0.02, 0.05, and 0.21 N. The last profile was measured in a different region of the surfaces where the local radius of curvature was 1.45 cm. The Hertz profiles correspond to central displacements of $\delta = 66.5$, 124, 173, and 441 nm. The *dashed line* shows the shape of the undeformed sphere corresponding to the curve at a load of 0.05 N; it fits the experimental points at larger distances (not shown). **(b)** Surface profiles measured with adhesive contact (mica surfaces adhering in dry nitrogen gas) at applied loads of -0.005, 0.01, and 0.12 N. The continuous lines are JKR profiles obtained by adjusting the central displacement in each case to get the best fit to points at larger distances. The values are $\delta = -4.2$, 75.6, and 256 nm. Note that the scales of this figure exaggerate the apparent angle at the junction of the surfaces. This angle, which is insensitive to load, is only about 0.25°. **(c)** and **(d)** Molecular dynamics simulation illustrating the formation of a connective neck between an Ni tip (topmost eight layers) and an Au substrate. The figures show the atomic configuration in a slice through the system at indentation **(c)** and during separation **(d)**. Note the crystalline structure of the neck. Distances are given in units of x and z, where $x = 1$ and $z = 1$ correspond to 6.12 nm. [**(a)** and **(b)** after [18.181]. Copyright 1987, with permission from Elsevier Science. **(c)** and **(d)** after [18.91], with kind permission from Kluwer Academic Publishers]

physical state of the contact zone. For example, if the surfaces contain ions, these will diffuse and build up within the liquid bridge, thereby changing the chemical composition of the contact zone, as well as influencing the adhesion. In the case of surfaces covered with surfactant or polymer molecules (amphiphilic surfaces), the molecules can overturn on exposure to humid air, so that the surface nonpolar groups become replaced by polar groups, which renders the surfaces hydrophilic. When two such surfaces come into contact, water will condense around the contact zone and the adhesion force will also be affected – generally increasing well above the value expected for inert hydrophobic surfaces. It is apparent that the adhesion in vapor or a solvent is often largely determined by capillary forces arising from the condensation of liquid that may be present only in very small quantities, e.g., 10–20 % of saturation in the vapor, or 20 ppm in the solvent.

18.5.2 Adhesion Mechanics

Two bodies in contact deform as a result of surface forces and/or applied normal forces. For the simplest case of two interacting elastic spheres (a model that is easily extended to an elastic sphere interacting with an undeformable surface (or vice versa)) and in the absence of attractive surface forces, the vertical central displacement (compression) was derived by *Hertz* [18.182]. In this model, the displacement and the contact area are equal to zero when no external force (load) is applied, i. e., at the points of contact and of separation.

In systems where attractive surface forces are present between the surfaces, the deformations are more complicated. Modern theories of the adhesion mechanics of two contacting solid surfaces are based on the Johnson–Kendall–Roberts (JKR) theory [18.15, 183], or on the Derjaguin–Muller–Toporov (DMT) theory [18.184–186]. The JKR theory is applicable to easily deformable, large bodies with high surface energy, whereas the DMT theory better describes very small and hard bodies with low surface energy [18.187].

In the JKR theory, two spheres of radii R_1 and R_2, bulk elastic modulus K, and surface energy γ will flatten due to attractive surface forces when in contact at no external load. The contact area will increase under an external load or normal force F, such that at mechanical equilibrium the radius of the contact area, r, is given by

$$r^3 = \frac{R}{K}\left[F + 6\pi R\gamma + \sqrt{12\pi R\gamma F + (6\pi R\gamma)^2}\right] , \tag{18.22}$$

where $R = R_1 R_2/(R_1 + R_2)$. In the absence of surface energy, γ, equation (18.22) is reduced to the expression for the radius of the contact area in the Hertz model. Another important result of the JKR theory gives the adhesion force or "pull-off" force:

$$F_\mathrm{S} = -3\pi R\gamma_\mathrm{S} , \tag{18.23}$$

where the surface energy, γ_S, is defined as $W = 2\gamma_\mathrm{S}$, where W is the reversible work of adhesion. Note that according to the JKR theory a finite elastic modulus, K, while having an effect on the load–area curve, has no effect on the adhesion force, an interesting and unexpected result that has nevertheless been verified experimentally [18.15, 181, 188, 189].

Equation (18.22) and (18.23) provide the framework for analyzing results of adhesion measurements of contacting solids, known as contact mechanics [18.183, 190], and for studying the effects of surface conditions and time on adhesion energy hysteresis (see Sect. 18.5.4).

18.5.3 Effects of Surface Structure, Roughness, and Lattice Mismatch

In a contact between two rough surfaces, the real area of contact varies with the applied load in a different manner than between smooth surfaces [18.191, 192]. For a Hertzian contact, it has been shown that the contact area for rough surfaces increases approximately linearly with the applied normal force (load), F, instead of as $F^{2/3}$ for smooth surfaces. In systems with attractive surface forces, there is a competition between this attraction and repulsive forces arising from compression of high asperities. As a result, the adhesion in such systems can be very low, especially if the surfaces are not easily deformed [18.193–195]. The opposite is possible for soft (viscoelastic) surfaces where the real (molecular) contact area might be larger than for two perfectly smooth surfaces.

Adhesion forces may also vary depending on the commensurability of the crystallographic lattices of the interacting surfaces. *McGuiggan* and *Israelachvili* [18.196] measured the adhesion between two mica surfaces as a function of the orientation (twist angle) of their surface lattices. The forces were measured in air, water, and an aqueous salt solution where oscillatory structural forces were present. In humid air, the adhesion was found to be relatively independent of the twist angle θ due to the adsorption of a 0.4-nm-thick amorphous layer of organics and water at the interface. In contrast, in water, sharp adhesion peaks (energy minima) occurred at $\theta = 0°, \pm 60°, \pm 120°$ and 180°, corresponding to the "coincidence" angles of the surface lattices (Fig. 18.11). As little as ±1° away from these peaks, the energy decreased by 50%. In aqueous KCl solution, due to potassium ion adsorption the water between the surfaces becomes ordered, resulting in an oscillatory force profile where the adhesive minima occur at discrete separations of about 0.25 nm, corresponding to integral numbers of water layers. The whole interaction potential was now found to depend on the orientation of



Fig. 18.11 Adhesion energy for two mica surfaces in contact in water (in the primary minimum of an oscillatory force curve) as a function of the mismatch angle θ about $\theta = 0°$ and 180° between the mica surface lattices. (After [18.197] with permission)

the surface lattices, and the effect extended at least four molecular layers.

It has also been appreciated that the structure of the confining surfaces is just as important as the nature of the liquid for determining the solvation forces [18.90, 122, 123, 198–202]. Between two surfaces that are completely flat but "unstructured", the liquid molecules will order into layers, but there will be no lateral ordering within the layers. In other words, there will be positional ordering normal but not parallel to the surfaces. If the surfaces have a crystalline (periodic) lattice, this may induce ordering parallel to the surfaces, as well, and the oscillatory force then also depends on the structure of the surface lattices. Further, if the two lattices have different dimensions ("mismatched" or "incommensurate" lattices), or if the lattices are similar but are not in register relative to each other, the oscillatory force law is further modified [18.196, 203] and the tribological properties of the film are also influenced, as discussed in Sect. 18.9 [18.203, 204].

As shown by the experiments, these effects can alter the magnitude of the adhesive minima found at a given separation within the last one or two nanometers of a thin film by a factor of two. The force barriers (maxima) may also depend on orientation. This could be even more important than the effects on the minima. A high barrier could prevent two surfaces from coming closer together into a much deeper adhesive well. Thus the maxima can effectively contribute to determining not only the final separation of two surfaces, but also their final adhesion. Such considerations should be particularly important for determining the thickness and strength of intergranular spaces in ceramics, the adhesion forces between colloidal particles in concentrated electrolyte solution, and the forces between two surfaces in a crack containing capillary condensed water.

For surfaces that are *randomly* rough, oscillatory forces become smoothed out and disappear altogether, to be replaced by a purely monotonic solvation force [18.116, 122, 123]. This occurs even if the liquid molecules themselves are perfectly capable of ordering into layers. The situation of *symmetric* liquid molecules confined between *rough* surfaces is therefore not unlike that of *asymmetric* molecules between *smooth* surfaces (see Sect. 18.4.3 and Fig. 18.7a). To summarize, for there to be an oscillatory solvation force, the liquid molecules must be able to be correlated over a reasonably long range. This requires that both the liquid molecules and the surfaces have a high degree of order or symmetry. If either is missing, so will the oscillations. A roughness of only a few tenths of a nanometer is often sufficient to eliminate any oscillatory component of the force law.

18.5.4 Nonequilibrium and Rate-Dependent Interactions: Adhesion Hysteresis

Under ideal conditions the adhesion energy is a well-defined thermodynamic quantity. It is normally denoted by E or W (the work of adhesion) or γ (the surface tension, where $W = 2\gamma$) and gives the reversible work done on bringing two surfaces together or the work needed to separate two surfaces from contact. Under ideal, equilibrium conditions these two quantities are the same, but under most realistic conditions they are not: The work needed to separate two surfaces is always greater than that originally gained by bringing them together. An understanding of the molecular mechanisms underlying this phenomenon is essential for understanding many adhesion phenomena, energy dissipation during loading–unloading cycles, contact angle hysteresis, and



Fig. 18.12 **(a)** Schematic representation of interpenetrating chains. **(b)** and **(c)**: JKR plots (contact radius r as a function of applied load L) showing small adhesion hysteresis for uncrosslinked polystyrene and larger adhesion hysteresis after chain scission at the surfaces after 18 h irradiation with ultraviolet light in an oxygen atmosphere. The adhesion hysteresis continues to increase with the irradiation time. **(d)** Rate-dependent adhesion of CTAB surfactant monolayers. The *solid curves* [18.205] are fits to experimental data on CTAB adhesion after different contact times [18.206] using an approximate analytical solution for a JKR model, including crack tip dissipation. Due to the limited range of validity of the approximation, the fits rely on the low effective adhesion energy part of the experimental data only. From the fits one can determine the thermodynamic adhesion energy, the characteristic dissipation velocity, and the intrinsic dissipation exponent of the model. [**(a)** after [18.207]. Copyright 1993 American Chemical Society. **(b)** and **(c)** after [18.208]. Copyright 2002 American Association for the Advancement of Science. **(d)** after [18.205]. Copyright 2000 American Chemical Society]

the molecular mechanisms associated with many frictional processes.

It is wrong to think that hysteresis arises because of some imperfection in the system such as rough or chemically heterogeneous surfaces, or because the supporting material is viscoelastic. Adhesion hysteresis can arise even between perfectly smooth and chemically homogenous surfaces supported by perfectly elastic materials. It can be responsible for such phenomena as rolling friction and elastoplastic adhesive contacts [18.190, 209–212] during loading–unloading and adhesion–decohesion cycles.

Adhesion hysteresis may be thought of as being due to mechanical effects such as instabilities, or chemical effects such as interdiffusion, interdigitation, molecular reorientations and exchange processes occurring at an interface after contact, as illustrated in Fig. 18.12. Such processes induce roughness and chemical heterogeneity even though initially (and after separation and re-equilibration) both surfaces are perfectly smooth and chemically homogeneous. In general, if the energy change, or work done, on separating two surfaces from adhesive contact is not fully recoverable on bringing the two surfaces back into contact again, the adhesion hysteresis may be expressed as

$$\underset{\text{Receding}}{W_{\mathrm{R}}} > \underset{\text{Advancing}}{W_{\mathrm{A}}}$$

or

$$\Delta W = (W_{\mathrm{R}} - W_{\mathrm{A}}) > 0\,, \tag{18.24}$$

where W_{R} and W_{A} are the adhesion or surface energies for receding (separating) and advancing (approaching) two solid surfaces, respectively.

Hysteresis effects are also commonly observed in wetting/dewetting phenomena [18.213]. For example, when a liquid spreads and then retracts from a surface the advancing contact angle θ_{A} is generally larger than the receding angle θ_{R}. Since the contact angle, θ, is related to the liquid–vapor surface tension, γ_{L}, and the solid–liquid adhesion energy, W, by the Dupré equation,

$$(1+\cos\theta)\gamma_{\mathrm{L}} = W\,, \tag{18.25}$$

we see that *wetting hysteresis* or *contact angle hysteresis* ($\theta_{\mathrm{A}} > \theta_{\mathrm{R}}$) actually implies adhesion hysteresis, $W_{\mathrm{R}} > W_{\mathrm{A}}$, as given by (18.24).

Energy dissipating processes such as adhesion and contact angle hysteresis arise because of practical constraints of the *finite time* of measurements and the *finite elasticity* of materials. This prevents many loading–unloading or approach–separation cycles from being thermodynamically reversible, even though if carried out infinitely slowly they would be. By thermodynamically irreversible one simply means that one cannot go through the approach–separation cycle via a continuous series of equilibrium states, because some of these are connected via spontaneous – and therefore thermodynamically irreversible – instabilities or transitions where energy is liberated and therefore "lost" via heat or phonon release [18.214]. This is an area of much current interest and activity, especially regarding the fundamental molecular origins of adhesion and friction in polymer and surfactant systems, and the relationships between them [18.190, 205, 206, 208, 210, 215–218].

18.6 Introduction: Different Modes of Friction and the Limits of Continuum Models

Most frictional processes occur with the sliding surfaces becoming damaged in one form or another [18.209]. This may be referred to as "normal" friction. In the case of brittle materials, the damaged surfaces slide past each other while separated by relatively large, micron-sized wear particles. With more ductile surfaces, the damage remains localized to nanometer-sized, plastically deformed asperities. Some features of the friction between damaged surfaces will be described in Sect. 18.7.4.

There are also situations in which sliding can occur between two perfectly smooth, undamaged surfaces. This may be referred to as "interfacial" sliding or



Fig. 18.13 Stribeck curve: an empirical curve giving the trend generally observed in the friction forces or friction coefficients as a function of sliding velocity, the bulk viscosity of the lubricating fluid, and the applied load. The three friction/lubrication regimes are known as the boundary lubrication regime (see Sect. 18.7), the intermediate or mixed lubrication regime (Sect. 18.8.2), and thick film or elastohydrodynamic (EHD) lubrication regime (Sect. 18.8.1). The film thicknesses believed to correspond to each of these regimes are also shown. For thick films, the "friction" force is purely viscous, e.g., Couette flow at low shear rates, but may become complicated at higher shear rates where EHD deformations of surfaces can occur during sliding. (After [18.1] with permission)

Table 18.4 The three main tribological regimes characterizing the changing properties of liquids subjected to an increasing confinement between two solid surfaces[a]

Regime	Conditions for getting into this regime	Static/equilibrium properties[b]	Dynamic properties[c]
Bulk	• Thick films (> 10 molecular diameters, $\gg R_g$ for polymers) • Low or zero loads • High shear rates	Bulk (continuum) properties: • Bulk liquid density • No long-range order	Bulk (continuum) properties: • Newtonian viscosity • Fast relaxation times • No glass temperature • No yield point • Elastohydrodynamic lubrication
Intermediate mixed	• Intermediately thick films (4–10 molecular diameters, $\sim R_g$ for polymers) • Low loads or pressure	Modified fluid properties include: • Modified positional and orientational order[a] • Medium to long-range molecular correlations • Highly entangled states	Modified rheological properties include: • Non-Newtonian flow • Glassy states • Long relaxation times • Mixed lubrication
Boundary	• Molecularly thin films (< 4 molecular diameters) • High loads or pressure • Low shear rates • Smooth surfaces or asperities	Onset of non-fluidlike properties: • Liquid-like to solid-like phase transitions • Appearance of new liquid-crystalline states • Epitaxially induced long-range ordering	Onset of tribological properties: • No flow until yield point or critical shear stress reached • Solid-like film behavior characterized by defect diffusion, dislocation motion, shear melting • Boundary lubrication

Based on work by *Granick* [18.219], *Hu* and *Granick* [18.220], and others [18.38, 207, 221] on the dynamic properties of short chain molecules such as alkanes and polymer melts confined between surfaces

[a] Confinement can lead to an increased or decreased order in a film, depending both on the surface lattice structure and the geometry of the confining cavity

[b] In each regime both the static and dynamic properties change. The static properties include the film density, the density distribution function, the potential of mean force, and various positional and orientational order parameters

[c] Dynamic properties include viscosity, viscoelastic constants, and tribological yield points such as the friction coefficient and critical shear stress

"boundary" friction and is the focus of the following sections. The term "boundary lubrication" is more commonly used to denote the friction of surfaces that contain a thin protective lubricating layer such as a surfactant monolayer, but here we shall use the term more broadly to include any molecularly thin solid, liquid, surfactant, or polymer film.

Experiments have shown that as a liquid film becomes progressively thinner, its physical properties change, at first quantitatively and then qualitatively [18.44, 47, 219, 220, 222, 223]. The quantitative changes are manifested by an increased viscosity, non-Newtonian flow behavior, and the replacement of normal melting by a glass transition, but the film remains recognizable as a liquid (Fig. 18.13). In tribology, this regime is commonly known as the "mixed lubrication" regime, where the rheological properties of a film are intermediate between the bulk and boundary properties. One may also refer to it as the "intermediate" regime (Table 18.4).

For even thinner films, the changes in behavior are more dramatic, resulting in a qualitative change in properties. Thus first-order phase transitions can now occur to solid or liquid-crystalline phases [18.46,201,207,221, 224–227], whose properties can no longer be characterized even qualitatively in terms of bulk or continuum liquid properties such as viscosity. These films now exhibit yield points (characteristic of fracture in solids) and their molecular diffusion and relaxation times can be ten orders of magnitude longer than in the bulk liquid or even in films that are just slightly thicker. The three friction regimes are summarized in Table 18.4.

18.7 Relationship Between Adhesion and Friction Between Dry (Unlubricated and Solid Boundary Lubricated) Surfaces

18.7.1 Amontons' Law and Deviations from It Due to Adhesion: The Cobblestone Model

Early theories and mechanisms for the dependence of friction on the applied normal force or load, L, were developed by *da Vinci*, *Amontons*, *Coulomb* and *Euler* [18.228]. For the macroscopic objects investigated, the friction was found to be directly proportional to the load, with no dependence on the contact area. This is described by the so-called Amontons' law:

$$F = \mu L \,, \tag{18.26}$$

where F is the shear or friction force and μ is a constant defined as the coefficient of friction. This friction law has a broad range of applicability and is still the principal means of quantitatively describing the friction between surfaces. However, particularly in the case of adhering surfaces, Amontons' law does not adequately describe the friction behavior with load, because of the finite friction force measured at zero and even negative applied loads.

When a lateral force, or shear stress, is applied to two surfaces in adhesive contact, the surfaces initially remain "pinned" to each other until some critical shear force is reached. At this point, the surfaces begin to slide past each other either smoothly or in jerks. The frictional force needed to initiate sliding from rest is known as the *static* friction force, denoted by F_s, while the force needed to maintain smooth sliding is referred to as the *kinetic* or *dynamic* friction force, denoted by F_k. In general, $F_s > F_k$. Two sliding surfaces may also move in regular jerks, known as stick–slip sliding, which is discussed in more detail in Sect. 18.8.3. Such friction forces cannot be described by models used for thick films that are viscous (see Sect. 18.8.1) and, therefore, shear as soon as the smallest shear force is applied.

Experimentally, it has been found that during both smooth and stick–slip sliding the local geometry of the contact zone remains largely unchanged from the static geometry. In an adhesive contact, the contact area as a function of load is thus generally well described by the JKR equation, (18.22). The friction force between two molecularly smooth surfaces sliding in adhesive contact is not simply proportional to the applied load, L, as might be expected from Amontons' law. There is an additional adhesion contribution that is proportional to the area of contact, A. Thus, in general, the interfacial friction force of dry, unlubricated surfaces sliding smoothly past each other in adhesive contact is given by

$$F = F_k = S_c A + \mu L \,, \tag{18.27}$$

where S_c is the "critical shear stress" (assumed to be constant), $A = \pi r^2$ is the contact area of radius r given by (18.22), and μ is the coefficient of friction. For low loads we have:

$$\begin{aligned} F &= S_c A = S_c \pi r^2 \\ &= S_c \pi \left[\frac{R}{K}\left(L + 6\pi R\gamma + \sqrt{12\pi R\gamma L + (6\pi R\gamma)^2}\right)\right]^{2/3} ; \end{aligned} \tag{18.28}$$

whereas for high loads (or high μ), (18.27) reduces to Amontons' law: $F = \mu L$. Depending on whether the friction force in (18.27) is dominated by the first or second term, one may refer to the friction as *adhesion-controlled* or *load-controlled*, respectively.

The following friction model, first proposed by *Tabor* [18.229] and developed further by *Sutcliffe* et al. [18.230], *McClelland* [18.231], and *Homola* et al. [18.45], has been quite successful at explaining the interfacial and boundary friction of two solid crystalline surfaces sliding past each other in the absence of wear. The surfaces may be unlubricated, or they may be separated by a monolayer or more of some boundary lubricant or liquid molecules. In this model, the values of the critical shear stress S_c, and coefficient of friction μ, of (18.27) are calculated in terms of the energy needed to overcome the attractive intermolecular forces and compressive externally applied load as one surface is raised and then slid across the molecular-sized asperities of the other.

This model (variously referred to as the *interlocking asperity model*, *Coulomb friction*, or the *cobblestone model*) is similar to pushing a cart over a road of cobblestones where the cartwheels (which represent the molecules of the upper surface or film) must be made to roll over the cobblestones (representing the molecules of the lower surface) before the cart can move. In the case of the cart, the downward force of gravity replaces the attractive intermolecular forces between two material surfaces. When at rest, the cartwheels find grooves between the cobblestones where they sit in potential energy minima, and so the cart is at some stable mechanical equilibrium. A certain lateral force (the "push") is required to raise the cartwheels against the force of gravity in order to initiate motion. Motion will continue as long as the cart is pushed, and rapidly stops once it is no longer pushed. Energy is dissipated by the liberation of heat (phonons, acoustic waves, etc.) every time a wheel hits the next cobblestone. The cobblestone model is not unlike the *Coulomb* and *interlocking asperity* models of friction [18.228] except that it is being applied at the molecular level and for a situation where the external load is augmented by attractive intermolecular forces.

There are thus two contributions to the force pulling two surfaces together: the externally applied load or pressure, and the (internal) attractive intermolecular forces that determine the adhesion between the two surfaces. Each of these contributions affects the friction force in a different way, which we will discuss in more detail below.



Fig. 18.14 Schematic illustration of how one molecularly smooth surface moves over another when a lateral force F is applied (the "cobblestone model"). As the upper surface moves laterally by some fraction of the lattice dimension $\Delta\sigma$, it must also move up by some fraction of an atomic or molecular dimension ΔD before it can slide across the lower surface. On impact, some fraction ε of the kinetic energy is "transmitted" to the lower surface, the rest being "reflected" back to the colliding molecule (upper surface). (After [18.232] with permission)

18.7.2 Adhesion Force and Load Contribution to Interfacial Friction

Adhesion Force Contribution

Consider the case of two surfaces sliding past each other, as shown in Fig. 18.14. When the two surfaces are initially in adhesive contact, the surface molecules will adjust themselves to fit snugly together [18.233], in an analogous manner to the self-positioning of the cartwheels on the cobblestone road. A small tangential force applied to one surface will therefore not result in the sliding of that surface relative to the other. The attractive van der Waals forces between the surfaces must first be overcome by having the surfaces separate by a small amount. To initiate motion, let the separation between the two surfaces increase by a small amount ΔD, while the lateral distance moved is $\Delta\sigma$. These two values will be related via the geometry of the two surface lattices. The energy put into the system by the force F acting over a lateral distance $\Delta\sigma$ is

$$\text{Input energy: } F\times\Delta\sigma\,. \qquad (18.29)$$

This energy may be equated with the change in interfacial or surface energy associated with separating the surfaces by ΔD, i. e., from the equilibrium separation $D = D_0$ to $D = (D_0 + \Delta D)$. Since $\gamma \propto D^{-2}$ for two flat surfaces, the energy cost may be approximated by:

$$\text{Surface energy change}\times\text{area:}$$
$$2\gamma A\left[1-D_0^2/(D_0+\Delta D)^2\right]\approx 4\gamma A(\Delta D/D_0)\,, \qquad (18.30)$$

where γ is the surface energy, A the contact area, and D_0 the surface separation at equilibrium. During steady state sliding (kinetic friction), not all of this energy will be "lost" or absorbed by the lattice every time the surface molecules move by one lattice spacing: Some fraction will be reflected during each impact of the "cartwheel" molecules [18.231]. Assuming that a fraction ε of the above surface energy is "lost" every time the surfaces move across the characteristic length $\Delta\sigma$ (Fig. 18.14), we obtain after equating (18.29) and (18.30)

$$S_c = \frac{F}{A} = \frac{4\gamma\varepsilon\Delta D}{D_0\Delta\sigma} . \qquad (18.31)$$

For a typical hydrocarbon or a van der Waals surface, $\gamma \approx 25\,\mathrm{mJ\,m^{-2}}$. Other typical values would be: $\Delta D \approx 0.05\,\mathrm{nm}$, $D_0 \approx 0.2\,\mathrm{nm}$, $\Delta\sigma \approx 0.1\,\mathrm{nm}$, and $\varepsilon \approx 0.1$–0.5. Using the above parameters, (18.31) predicts $S_c \approx (2.5$–$12.5)\times 10^7\,\mathrm{N\,m^{-2}}$ for van der Waals surfaces. This range of values compares very well with typical experimental values of $2\times 10^7\,\mathrm{N\,m^{-2}}$ for hydrocarbon or mica surfaces sliding in air (see Fig. 18.16) or separated by one molecular layer of cyclohexane [18.45].

The above model suggests that all interfaces, whether dry or lubricated, dilate just before they shear or slip. This is a small but important effect: The dilation provides the crucial extra space needed for the molecules to slide across each other or flow. This dilation has been computed by *Thompson* and *Robbins* [18.201] and *Zaloj* et al. [18.234] and measured by *Dhinojwala* et al. [18.235].

This model may be extended, at least semi-quantitatively, to lubricated sliding, where a thin liquid film is present between the surfaces. With an increase in the number of liquid layers between the surfaces, D_0 increases while ΔD decreases, hence the lower the friction force. This is precisely what is observed, but with more than one liquid layer between two surfaces the situation becomes too complex to analyze analytically (actually, even with one or no interfacial layers, the calculation of the fraction of energy dissipated per molecular collision ε is not a simple matter). Furthermore, even in systems as simple as linear alkanes, interdigitation and interdiffusion have been found to contribute strongly to the properties of the system [18.114, 236]. Sophisticated modeling based on computer simulations is now required, as described in the following section.

Relation Between Boundary Friction and Adhesion Energy Hysteresis

While the above equations suggest that there is a direct correlation between friction and adhesion, this is not the case. The correlation is really between friction and adhesion hysteresis, described in Sect. 18.5.4. In the case of friction, this subtle point is hidden in the factor ε, which is a measure of the amount of energy absorbed (dissipated, transferred, or "lost") by the lower surface when it is impacted by a molecule from the upper surface. If $\varepsilon = 0$, all the energy is reflected, and there will be no kinetic friction force nor any adhesion hysteresis, but the absolute magnitude of the adhesion force or energy will remain finite and unchanged. This is illustrated in Figs. 18.17 and 18.19.

The following simple model shows how adhesion hysteresis and friction may be quantitatively related. Let $\Delta\gamma = \gamma_R - \gamma_A$ be the adhesion energy hysteresis per unit area, as measured during a typical loading–unloading cycle (see Figs. 18.17a and 18.19c,d). Now consider the same two surfaces sliding past each other and assume that frictional energy dissipation occurs through the same mechanism as adhesion energy dissipation, and that both occur over the same characteristic molecular length scale σ. Thus, when the two surfaces (of contact area $A = \pi r^2$) move a distance σ, equating the frictional energy $(F\times\sigma)$ to the dissipated adhesion energy $(A\times\Delta\gamma)$, we obtain

$$\text{Friction force: } F = \frac{A\times\Delta\gamma}{\sigma} = \frac{\pi r^2}{\sigma}(\gamma_R - \gamma_A) , \qquad (18.32)$$

$$\text{or} \quad \text{Critical shear stress: } S_c = F/A = \Delta\gamma/\sigma , \qquad (18.33)$$

which is the desired expression and has been found to give order of magnitude agreement between measured friction forces and adhesion energy hysteresis [18.207]. If we equate (18.33) with (18.31), since $4\Delta D/(D_0\Delta\sigma) \approx 1/\sigma$, we obtain the intuitive relation

$$\varepsilon = \frac{\Delta\gamma}{\gamma} . \qquad (18.34)$$

External Load Contribution to Interfacial Friction

When there is no interfacial adhesion, S_c is zero. Thus, in the absence of any adhesive forces between two surfaces, the only "attractive" force that needs to be overcome for sliding to occur is the externally applied load or pressure.

For a preliminary discussion of this question, it is instructive to compare the magnitudes of the *externally* applied pressure to the *internal* van der Waals pressure between two smooth surfaces. The internal van der Waals pressure between two flat surfaces is given (see Table 18.2) by $P = A_H/6\pi D_0^3 \approx 1\,\mathrm{GPa}$ (10^4 atm), using a typical Hamaker constant of $A_H = 10^{-19}\,\mathrm{J}$, and assuming $D_0 \approx 2\,\mathrm{nm}$ for the equilibrium interatomic spacing. This implies that we should not expect the externally applied load to affect the interfacial friction force F, as defined by (18.27), until the externally applied pressure L/A begins to exceed $\sim 100\,\mathrm{MPa}$ (10^3 atm). This is in agreement with experimental data [18.237] where the effect of load became dominant at pressures in excess of 10^3 atm.

For a more general semiquantitative analysis, again consider the cobblestone model used to derive (18.31), but now include an additional contribution to the surface energy change of (18.30) due to the work done against the external load or pressure, $L\Delta D = P_{\mathrm{ext}} A \Delta D$ (this is equivalent to the work done against gravity in the case of a cart being pushed over cobblestones). Thus:

$$S_{\mathrm{c}} = \frac{F}{A} = \frac{4\gamma\varepsilon\Delta D}{D_0\Delta\sigma} + \frac{P_{\mathrm{ext}}\varepsilon\Delta D}{\Delta\sigma}\,, \tag{18.35}$$

which gives the more general relation

$$S_{\mathrm{c}} = F/A = C_1 + C_2 P_{\mathrm{ext}}\,, \tag{18.36}$$

where $P_{\mathrm{ext}} = L/A$ and C_1 and C_2 are constants characteristic of the surfaces and sliding conditions. The constant $C_1 = 4\gamma\varepsilon\Delta D/(D_0\Delta\sigma)$ depends on the mutual adhesion of the two surfaces, while both C_1 and $C_2 = \varepsilon\Delta D/\Delta\sigma$ depend on the topography or atomic bumpiness of the surface groups (Fig. 18.14). The smoother the surface groups the smaller the ratio $\Delta D/\Delta\sigma$ and hence the lower the value of C_2. In addition, both C_1 and C_2 depend on ε (the fraction of energy dissipated per collision), which depends on the relative masses of the shearing molecules, the sliding velocity, the temperature, and the characteristic molecular relaxation processes of the surfaces. This is by far the most difficult parameter to compute, and yet it is the most important since it represents the energy transfer mechanism in any friction process, and since ε can vary between 1 and 0, it determines whether a particular friction force will be large or close to zero. Molecular simulations offer the best way to understand and predict the magnitude of ε, but the complex multi-body nature of the problem makes simple conclusions difficult to draw [18.239–241]. Some of the basic physics of the energy transfer and dissipation of the molecular collisions can be drawn from simplified models such as a 1-D three-body system [18.214].

Finally, the above equation may also be expressed in terms of the friction force F:

$$F = S_{\mathrm{c}} A = C_1 A + C_2 L\,. \tag{18.37}$$

Equations similar to (18.36) and (18.37) were previously derived by *Derjaguin* [18.242,243] and by *Briscoe*



Fig. 18.15 Friction as a function of load for smooth surfaces. At low loads, the friction is dominated by the $C_1 A$ term of (18.37). The adhesion contribution (JKR curve) is most prominent near zero load where the Hertzian and Amontons' contributions to the friction are minimal. As the load increases, the adhesion contribution becomes smaller as the JKR and Hertz curves converge. In this range of loads, the linear $C_2 L$ contribution surpasses the area contribution to the friction. At much higher loads the explicit load dependence of the friction dominates the interactions, and the observed behavior approaches Amontons' law. It is interesting to note that for smooth surfaces the pressure over the contact area does not increase as rapidly as the load. This is because as the load is increased, the surfaces deform to increase the surface area and thus moderate the contact pressure. (After [18.238] with permission of Kluwer Academic Publishers)

and *Evans* [18.244], where the constants C_1 and C_2 were interpreted somewhat differently than in this model.

In the absence of any attractive interfacial force, we have $C_1 \approx 0$, and the second term in (18.36) and (18.37) should dominate (Fig. 18.15). Such situations typically arise when surfaces repel each other across the lubricating liquid film. In such cases, the total frictional force should be low and should increase *linearly* with the external load according to

$$F = C_2 L \, . \tag{18.38}$$

An example of such lubricated sliding occurs when two mica surfaces slide in water or in salt solution (see Fig. 18.20), where the short-range "hydration" forces between the surfaces are repulsive. Thus, for sliding in 0.5 M KCl it was found that $C_2 = 0.015$ [18.245]. Another case where repulsive surfaces eliminate the adhesive contribution to friction is for polymer chains attached to surfaces at one end and swollen by a good solvent [18.175]. For this class of systems, $C_2 < 0.001$ for a finite range of polymer layer compressions (normal loads, L). The low friction between the surfaces in this regime is attributed to the entropic repulsion between the opposing brush layers with a minimum of entanglement between the two layers. However, with higher normal loads, the brush layers become compressed and begin to entangle, which results in higher friction (see [18.246]).

It is important to note that (18.38) has exactly the same form as Amontons' Law

$$F = \mu L \, , \tag{18.39}$$

where μ is the coefficient of friction.

At the molecular level a thermodynamic analog of the Coulomb or cobblestone models (see Sect. 18.7.1) based on the "contact value theorem" [18.3, 238, 245] can explain why $F \propto L$ also holds at the microscopic or molecular level. In this analysis we consider the surface molecular groups as being momentarily compressed and decompressed as the surfaces move along. Under irreversible conditions, which always occur when a cycle is completed in a finite amount of time, the energy "lost" in the compression–decompression cycle is dissipated as heat. For two non-adhering surfaces, the stabilizing pressure P_i acting locally between any two elemental contact points i of the surfaces may be expressed by the contact value theorem [18.3]:

$$P_i = \rho_i k_\mathrm{B} T = k_\mathrm{B} T / V_i \, , \tag{18.40}$$



Fig. 18.16 Friction force F and contact area A vs. load L for two mica surfaces sliding in adhesive contact in dry air. The contact area is well described by the JKR theory, (18.22), even during sliding, and the friction force is found to be directly proportional to this area, (18.28). The *vertical dashed line* and *arrow* show the transition from interfacial to normal friction with the onset of wear (*lower curve*). Sliding velocity is 0.2 µm s^{-1}. (After [18.45] with permission, copyright 1989 American Society of Mechanical Engineers)

where $\rho_i = V_i^{-1}$ is the local number density (per unit volume) or activity of the interacting entities, be they molecules, atoms, ions or the electron clouds of atoms. This equation is essentially the osmotic or entropic pressure of a gas of confined molecules. As one surface moves across the other, local regions become compressed and decompressed by a volume ΔV_i. The work done per cycle can be written as $\varepsilon P_i \Delta V_i$, where ε ($\varepsilon \leq 1$) is the fraction of energy per cycle "lost" as heat, as defined earlier. The energy balance shows that for each compression–decompression cycle, the dissipated energy is related to the friction force by

$$F_i x_i = \varepsilon P_i \Delta V_i \, , \tag{18.41}$$

where x_i is the lateral distance moved per cycle, which can be the distance between asperities or the distance between surface lattice sites. The pressure at each contact junction can be expressed in terms of the local normal load L_i and local area of contact A_i as $P_i = L_i / A_i$. The volume change over a cycle can thus be expressed as $\Delta V_i = A_i z_i$, where z_i is the vertical distance of confinement. Inserting these into (18.41), we get

$$F_i = \varepsilon L_i (z_i / x_i) \, , \tag{18.42}$$



Fig. 18.17 **(a)** Contact radius r versus externally applied load L for loading and unloading of two hydrophilic silica surfaces exposed to dry and humid atmospheres. Note that while the adhesion is higher in humid air, the *hysteresis* in the adhesion is higher in dry air. **(b)** Effect of velocity on the static friction force F_s for hydrophobic (heat-treated electron beam evaporated) silica in dry and humid air. The effects of humidity, load, and sliding velocity on the friction forces, as well as the stick–slip friction of the hydrophobic surfaces, are qualitatively consistent with a "friction" phase diagram representation as in Fig. 18.28. (After [18.41]. Copyright 1994, with permission from Elsevier Science)

which is independent of the local contact area A_i. The total friction force is thus

$$\begin{aligned} F &= \sum F_i = \sum \varepsilon L_i (z_i/x_i) \\ &= \varepsilon \langle z_i/x_i \rangle \sum L_i = \mu L \,, \end{aligned} \qquad (18.43)$$

where it is assumed that on average the local values of L_i and P_i are independent of the local "slope" z_i/x_i. Therefore, the friction coefficient μ is a function only of the average surface topography and the sliding velocity, but is independent of the local (real) or macroscopic (apparent) contact areas.

While this analysis explains non-adhering surfaces, there is still an additional explicit contact area contribution for the case of adhering surfaces, as in (18.37). The distinction between the two cases arises because the initial assumption of the contact value theorem, (18.40), is incomplete for adhering systems. A more appropriate starting equation would reflect the full intermolecular interaction potential, including the attractive interactions, in addition to the purely repulsive contributions of (18.40), much as the van der Waals equation of state modifies the ideal gas law.

18.7.3 Examples of Experimentally Observed Friction of Dry Surfaces

Numerous model systems have been studied with a surface forces apparatus (SFA) modified for friction experiments (see Sect. 18.2.3). The apparatus allows for control of load (normal force) and sliding speed, and simultaneous measurement of surface separation, surface shape, true (molecular) area of contact between smooth surfaces, and friction forces. A variety of both unlubricated and solid and liquid lubricated surfaces have been studied both as smooth single-asperity contacts and after they have been roughened by shear-induced damage.

Figure 18.16 shows the contact area, A, and friction force, F, both plotted against the applied load, L, in an experiment in which two molecularly smooth surfaces of mica in adhesive contact were slid past each other in an atmosphere of dry nitrogen gas. This is an example of the low load, adhesion controlled limit, which is excellently described by (18.28). In a number of different experiments, S_c was measured to be $2.5 \times 10^7\,\mathrm{N\,m^{-2}}$ and to be independent of the sliding velocity [18.45, 247]. Note that there is a friction force even at negative loads, where the surfaces are still sliding in adhesive contact.

Figure 18.17 shows the correlation between adhesion hysteresis and friction for two surfaces consisting of silica films deposited on mica substrates [18.41].



Fig. 18.18 Sliding of mica surfaces, each coated with a 2.5-nm-thick monolayer of calcium stearate surfactant, in the absence of damage (obeying JKR type boundary friction) and in the presence of damage (obeying Amontons' type normal friction). Note that both for this system and for the bare mica in Figs. 18.16 and 18.20, the friction force obeys Amontons' law with a friction coefficient of $\mu \approx 0.3$ after damage occurs. At much higher applied loads, the undamaged surfaces also follow Amontons' type sliding, but for a different reason: The dependence on adhesion becomes smaller. *Lower line:* Interfacial sliding with a monolayer of water between the mica surfaces, shown for comparison. (After [18.247]. Copyright 1990, with permission from Elsevier Science)

The friction between undamaged hydrophobic silica surfaces showed stick–slip both at dry conditions and at 100% relative humidity. Similar to the mica surfaces in Figs. 18.16, 18.18, and 18.20, the friction of damaged silica surfaces obeyed Amontons' law with a friction coefficient of 0.25 both at dry conditions and at 55% relative humidity.

The high friction force of unlubricated sliding can often be reduced by treating the solid surface with a boundary layer of some other solid material that exhibits lower friction such as a surfactant monolayer, or by ensuring that during sliding, a thin liquid film remains between the surfaces (as will be discussed in Sect. 18.8). The effectiveness of a solid boundary lubricant layer on reducing the forces of friction is illustrated in Fig. 18.18. Comparing this with the friction of the unlubricated/untreated surfaces (Fig. 18.16) shows that the critical shear stress has been reduced by a factor of about ten: from 2.5×10^7 to $3.5\times10^6\,\mathrm{N\,m^{-2}}$. At much higher applied loads or pressures, the friction force is proportional to the load, rather than the area of contact [18.237], as expected from (18.27).

Yamada and *Israelachvili* [18.248] studied the adhesion and friction of fluorocarbon surfaces (surfactant-coated boundary lubricant layers), which were compared to those of hydrocarbon surfaces. They concluded that well-ordered fluorocarbon surfaces have a high friction, in spite of their lower adhesion energy (in agreement with previous findings). The low friction coefficient of PTFE (Teflon) must, therefore, be due to some effect other than a low adhesion. For example, the softness of PTFE, which allows material to flow at the interface, which thus behaves like a fluid lubricant. On a related issue, *Luengo* et al. [18.249] found that C_{60} surfaces also exhibited low adhesion but high friction. In both cases the high friction appears to arise from the bulky surface groups – fluorocarbon compared to hydrocarbon groups in the former, large fullerene spheres in the latter. Apparently, the fact that C_{60} molecules rotate *in their lattice* does not make them a good lubricant: The molecules of the opposing surface must still climb over them in order to slide, and this requires energy that is independent of whether the surface molecules are fixed or freely rotating. Larger particles such as ~ 25 nm-sized nanoparticles (also known as "inorganic fullerenes") do appear to produce low friction by behaving like molecular ball bearings, but the potential of this promising new class of solid lubricant has still to be explored [18.250].

Figure 18.19 illustrates the relationship between adhesion hysteresis and friction for surfactant-coated surfaces under different conditions. This effect, however, is much more general and has been shown to hold for other surfaces as well [18.41, 232, 251].

Direct comparisons between absolute adhesion energies and friction forces show little correlation. In some cases, higher adhesion energies for the same system under different conditions correspond with lower friction forces. For example, for hydrophilic silica surfaces (Fig. 18.17) it was found that with increasing relative humidity the adhesion energy *increases*, but the adhesion energy hysteresis measured in a loading–unloading cycle *decreases*, as does the friction force [18.41]. For hydrophobic silica surfaces under dry conditions, the friction at load $L = 5.5\,\mathrm{mN}$ was $F = 75\,\mathrm{mN}$. For the same sample, the adhesion energy hysteresis was $\Delta\gamma = 10\,\mathrm{mJ\,m^{-2}}$, with a contact area of $A \approx 10^{-8}\,\mathrm{m}^2$ at the same load. Assuming a value for the characteristic distance σ on the order of one lattice spacing, $\sigma \approx 1\,\mathrm{nm}$, and inserting these values into (18.32), the friction force is predicted to be $F \approx 100\,\mathrm{mN}$ for the kinetic friction force, which is close to the measured value of 75 mN. Alternatively, we may conclude that the dissipation factor is $\varepsilon = 0.75$, i. e., that almost all the energy is dissipated as heat at each molecular collision.

A liquid lubricant film (Sect. 18.8.3) is usually much more effective at lowering the friction of two surfaces than a solid boundary lubricant layer. However, to successfully use a liquid lubricant, it must “wet” the surfaces, that is, it should have a high affinity for the surfaces, so that not all the liquid molecules become squeezed out when the surfaces come close together, even under a large compressive load. Another important requirement is that the liquid film remains a liquid under tribological conditions, i. e., that it does not epitaxially solidify between the surfaces.

Effective lubrication usually requires that the lubricant be injected between the surfaces, but in some cases the liquid can be made to condense from the vapor. This is illustrated in Fig. 18.20 for two untreated mica surfaces sliding with a thin layer of water between them. A monomolecular film of water (of thickness 0.25 nm per surface) has reduced S_c from its value for dry surfaces (Fig. 18.16) by a factor of more than 30, which



Fig. 18.19a–d *Top:* Friction traces for two fluid-like calcium alkylbenzene sulfonate monolayer-coated surfaces at 25 °C showing that the friction force is much higher between dry monolayers **(a)** than between monolayers whose fluidity has been enhanced by hydrocarbon penetration from vapor **(b)**. *Bottom:* Contact radius vs. load (r^3 vs. L) data measured for the same two surfaces as above and fitted to the JKR equation (18.22), shown by the *solid curves*. For dry monolayers **(c)** the adhesion energy on unloading ($\gamma_\mathrm{R} = 40\,\mathrm{mJ\,m^{-2}}$) is greater than that on loading ($\gamma_\mathrm{R} = 28\,\mathrm{mJ\,m^{-2}}$), indicative of an adhesion energy hysteresis of $\Delta\gamma = \gamma_\mathrm{R} - \gamma_\mathrm{A} = 12\,\mathrm{mJ\,m^{-2}}$. For monolayers exposed to saturated decane vapor **(d)** their adhesion hysteresis is zero ($\gamma_\mathrm{A} = \gamma_\mathrm{R}$), and both the loading and unloading data are well fitted by the thermodynamic value of the surface energy of fluid hydrocarbon chains, $\gamma = 24\,\mathrm{mJ\,m^{-2}}$. (After [18.207] with permission. Copyright 1993 American Chemical Society)



Fig. 18.20 Two mica surfaces sliding past each other while immersed in a 0.01 M KCl salt solution (nonadhesive conditions). The water film is molecularly thin, 0.25 to 0.5 nm thick, and the interfacial friction force is very low: $S_c \approx 5 \times 10^5\,\mathrm{N\,m^{-2}}$, $\mu \approx 0.03$ (before damage occurs). After the surfaces have become damaged, the friction coefficient is ca. 0.3. (After [18.247]. Copyright 1990, with permission from Elsevier Science)

may be compared with the factor of ten attained with the boundary lubricant layer (of thickness 2.5 nm per surface) in Fig. 18.18. Water appears to have unusual lubricating properties and usually gives wearless friction with no stick–slip.

The effectiveness of a water film only 0.25 nm thick to lower the friction force by more than an order of magnitude is attributed to the "hydrophilicity" of the mica surface (mica is "wetted" by water) and to the existence of a strongly repulsive short-range hydration force between such surfaces in aqueous solutions, which effectively removes the adhesion-controlled contribution to the friction force [18.245]. It is also interesting that a 0.25-nm-thick water film between two mica surfaces is sufficient to bring the coefficient of friction down to 0.01–0.02, a value that corresponds to the unusually low friction of ice. Clearly, a single monolayer of water can be a very good lubricant – much better than most other monomolecular liquid films – for reasons that will be discussed in Sect. 18.9.

Dry polymer layers (Fig. 18.21) typically show a high initial static friction ("stiction") as sliding commences from rest in adhesive contact. The development of the friction force after a change in sliding direction, a gradual transition from stick–slip to smooth sliding, is shown in Fig. 18.21. A correlation between adhesion hysteresis and friction similar to the one observed for silica surfaces in Fig. 18.17 can be seen for dry polymer layers below their glass transition temperature. As shown in Fig. 18.12b,c, the adhesion hysteresis for polystyrene surfaces can be increased by irradiation to induce scission of chains, and it has been found that the steady state friction force (kinetic friction) shows a similar increase with irradiation time [18.208].

Figure 18.22 shows an example of a computer simulation of the sliding of two unlubricated silicon surfaces (modeled as a tip sliding over a planar surface) [18.91]. The sliding proceeds through a series of stick–slip events, and information on the friction force and the local order of the initially crystalline surfaces can be obtained. Similar studies for cold welding systems [18.91] have demonstrated the occurrence of shear or friction damage within the sliding surface (tip) as the lowest layer of it adheres to the bottom surface.

18.7.4 Transition from Interfacial to Normal Friction with Wear

Frictional damage can have many causes such as adhesive tearing at high loads or overheating at high sliding speeds. Once damage occurs, there is a transition from "interfacial" to "normal" or load-controlled friction as the surfaces become forced apart by the torn-out as-



Fig. 18.21a,b Typical friction traces showing how the friction force varies with the sliding time for two symmetric, glassy polymer films at dry conditions. Qualitative features that are common to both polystyrene and polyvinyl benzyl chloride: **(a)** Decaying stick–slip motion is observed until smooth sliding is attained if the motion continues for a sufficiently long distance. **(b)** Smooth sliding observed at sufficiently high speeds. Similar observations have been made by *Berthoud* et al. [18.252] in measurements on polymethyl methacrylate. (After [18.208] with permission. Copyright 2002 American Association for the Advancement of Science)



Fig. 18.22a,b Computer simulation of the sliding of two contacting Si surfaces (a tip and a flat surface). Shown are particle trajectories in a constant-force simulation, $F_{z,\text{external}} = -2.15 \times 10^{-8}$ N, viewed along the (10$\bar{1}$) direction just before **(a)** and after **(b)** a stick–slip event for a large, initally ordered, dynamic tip. (After [18.91] with permission of Kluwer Academic Publishers)

perities (wear particles). For low loads, the friction changes from obeying $F = S_c A$ to obeying Amontons' law, $F = \mu L$, as shown in Figs. 18.16 and 18.18, and sliding now proceeds smoothly with the surfaces separated by a 10–100 nm forest of wear debris (in this case, mica flakes). The wear particles keep the surfaces apart over an area that is much greater than their size, so that even one submicroscopic particle or asperity can cause a significant reduction in the area of contact and, therefore, in the friction [18.247]. For this type of frictional sliding, one can no longer talk of the molecular contact area of the two surfaces, although the macroscopic or "apparent" area is still a useful parameter.

One remarkable feature of the transition from interfacial to normal friction of brittle surfaces is that while the strength of interfacial friction, as reflected in the values of S_c, is very dependent on the type of surface and on the liquid film between the surfaces, this is not the case once the transition to normal friction has occurred. At the onset of damage, the material properties of the underlying substrates control the friction. In Figs. 18.16, 18.18, and 18.20 the friction for the damaged surfaces is that of any damaged mica–mica system, $\mu \approx 0.3$, *independent of the initial surface coatings or liquid films between the surfaces*. A similar friction coefficient was found for damaged silica surfaces [18.41].

In order to practically modify the frictional behavior of such brittle materials, it is important to use coatings that will both alter the interfacial tribological character and remain intact and protect the surfaces from damage during sliding. *Berman* et al. [18.253] found that the friction of a strongly bound octadecyl phosphonic acid monolayer on alumina surfaces was higher than for untreated, undamaged α-alumina surfaces, but the bare surfaces easily became damaged upon sliding, resulting in an ultimately higher friction system with greater wear rates than the more robust monolayer-coated surfaces.

Clearly, the mechanism and factors that determine *normal* friction are quite different from those that govern *interfacial* friction (Sects. 18.7.1–18.7.2). This effect is not general and may only apply to brittle materials. For example, the friction of ductile surfaces is totally different and involves the continuous plastic deformation of contacting surface asperities during sliding, rather than the rolling of two surfaces on hard wear particles [18.209]. Furthermore, in the case of ductile surfaces, water and other surface-active components do have an effect on the friction coefficients under "normal" sliding conditions.

18.8 Liquid Lubricated Surfaces

18.8.1 Viscous Forces and Friction of Thick Films: Continuum Regime

Experimentally, it is usually difficult to unambiguously establish which type of sliding mode is occurring, but an empirical criterion, based on the Stribeck curve (Fig. 18.13), is often used as an indicator. This curve shows how the friction force or the coefficient of friction is expected to vary with sliding speed, depending on which type of friction regime is operating. For thick liquid lubricant films whose behavior can be described by bulk (continuum) properties, the friction forces are essentially the hydrodynamic or viscous drag forces. For example, for two plane parallel surfaces of area A separated by a distance D and moving laterally relative to each other with velocity v, if the intervening liquid is *Newtonian*, i. e., if its viscosity η is independent of the shear rate, the frictional force experienced by the surfaces is given by

$$F = \frac{\eta A v}{D}\,, \qquad (18.44)$$

where the shear rate $\dot{\gamma}$ is defined by

$$\dot{\gamma} = \frac{v}{D} . \tag{18.45}$$

At higher shear rates, two additional effects often come into play. First, certain properties of liquids may change at high $\dot{\gamma}$ values. In particular, the effective viscosity may become non-Newtonian, one form given by

$$\eta = \dot{\gamma}^n , \tag{18.46}$$

where $n = 0$ (i. e., $\eta_{\text{eff}} = \text{constant}$) for Newtonian fluids, $n > 0$ for shear thickening (dilatent) fluids, and $n < 0$ for shear thinning (pseudoplastic) fluids (the latter become less viscous, i. e., flow more easily, with increasing shear rate). An additional effect on η can arise from the higher local stresses (pressures) experienced by the liquid film as $\dot{\gamma}$ increases. Since the viscosity is generally also sensitive to the pressure (usually increasing with P), this effect also acts to increase η_{eff} and thus the friction force.

A second effect that occurs at high shear rates is surface deformation, arising from the large hydrodynamic forces acting on the sliding surfaces. For example, Fig. 18.23 shows how two surfaces deform elastically when the sliding speed increases to a high value. These deformations alter the hydrodynamic friction forces, and this type of friction is often referred to as *elastohydrodynamic lubrication* (EHD or EHL), as mentioned in Table 18.4.

How thin can a liquid film be before its dynamic, e.g., viscous flow, behavior ceases to be described by bulk properties and continuum models? Concerning the static properties, we have already seen in Sect. 18.4.3 that films composed of simple liquids display continuum behavior down to thicknesses of 4–10 molecular diameters. Similar effects have been found to apply to the dynamic properties, such as the viscosity, of simple liquids in thin films. Concerning viscosity measurements, a number of dynamic techniques were recently developed [18.11–13, 43, 254, 255] for directly measuring the viscosity as a function of film thickness and shear rate across very thin liquid films between two surfaces. By comparing the results with theoretical predictions of fluid flow in thin films, one can determine the effective positions of the shear planes and the onset of non-Newtonian behavior in very thin films.



Fig. 18.23 *Top:* Stationary surfaces (one more deformable and one rigid) separated by a thick liquid film. *Bottom:* Elastohydrodynamic deformation of the upper surface during sliding. (After [18.1] with permission)

The results show that for simple liquids, including linear chain molecules such as alkanes, the viscosity in thin films is the same, within 10%, as the bulk even for films as thin as 10 molecular diameters (or segment widths) [18.11–13,254,255]. This implies that the shear plane is effectively located within one molecular diameter of the solid–liquid interface, and these conclusions were found to remain valid even at the highest shear rates studied (of $\sim 2\times10^5\ \text{s}^{-1}$). With water between two mica or silica surfaces [18.22, 254–256] this has been found to be the case (to within ±10%) down to surface separations as small as 2 nm, implying that the shear planes must also be within a few tenths of a nanometer of the solid–liquid interfaces. These results appear to be independent of the existence of electrostatic “double-layer” or “hydration” forces. For the case of the simple liquid toluene confined between surfaces with adsorbed layers of C_{60} molecules, this type of viscosity measurement has shown that the traditional no-slip assumption for flow at a solid interface does not always hold [18.257]. The C_{60} layer at the mica–toluene interface results in a “full slip” boundary, which dramatically lowers the viscous drag or effective viscosity for regular Couette or Poiseuille flow.

With polymeric liquids (polymer melts) such as polydimethylsiloxanes (PDMS) and polybutadienes (PBD), or with polystyrene (PS) adsorbed onto surfaces from solution, the far-field viscosity is again equal to the bulk value, but with the non-slip plane (hydrodynamic layer thickness) being located at $D = 1–2R_\text{g}$ away from each surface [18.11, 47], or at $D = L$ or less for polymer brush layers of thickness L per surface [18.13, 258]. In contrast, the same technique was used to show that for non-adsorbing polymers in solution, there is actually a depletion layer of nearly pure solvent that exists at the surfaces that affects the confined solution flow properties [18.256]. These effects are observed from near contact to surface separations in excess of 200 nm.



Further experiments with surfaces closer than a few molecular diameters ($D < 2$–4 nm for simple liquids, or $D < 2$–$4R_g$ for polymer fluids) indicate that large deviations occur for thinner films, described below. One important conclusion from these studies is, therefore, that the dynamic properties of simple liquids, including water, near an *isolated* surface are similar to those of the bulk liquid *already within the first layer of molecules adjacent to the surface*, only changing when another surface approaches the first. In other words, the viscosity and position of the shear plane near a surface are not simply a property of that surface, but of how far that surface is from another surface. The reason for this is because when two surfaces are close together, the constraining effects on the liquid molecules between them are much more severe than when there is only one surface. Another obvious consequence of the above is that one should not make measurements on a single, isolated solid–liquid interface and then draw conclusions about the state of the liquid or its interactions in a thin film *between* two surfaces.

18.8.2 Friction of Intermediate Thickness Films

For liquid films in the thickness range between 4 and 10 molecular diameters, the properties can be significantly different from those of bulk films. Still, the fluids remain recognizable as fluids; in other words, they do not undergo a phase transition into a solid

◂ Fig. 18.24a–d Typical rheological behavior of liquid films in the mixed lubrication regime. **(a)** Increase in effective viscosity of dodecane film between two mica surfaces with decreasing film thickness. At distances larger than 4–5 nm, the effective viscosity η_{eff} approaches the bulk value η_{bulk} and does not depend on the shear rate $\dot{\gamma}$. (After [18.219]. Copyright 1991 American Association for the Advancement of Science.) **(b)** Non-Newtonian variation of η_{eff} with shear rate of a 2.7-nm-thick dodecane film at a net normal pressure of 0.12 MPa and at 28 °C. The effective viscosity decays as a power law, as in (18.46). In this example, $n = 0$ at the lowest $\dot{\gamma}$ and changes to $n = -2/3$ and -1 at higher $\dot{\gamma}$. For films of bulk thickness, dodecane is a low viscosity Newtonian fluid ($n = 0$). **(c)** Proposed general friction map of effective viscosity η_{eff} (arbitrary units) as a function of effective shear rate $\dot{\gamma}$ (arbitrary units) on logarithmic scales. Three main classes of behavior emerge: (i) Thick films: elastohydrodynamic sliding. At $L = 0$, approximating bulk conditions, η_{eff} is independent of shear rate except when shear thinning might occur at sufficiently large $\dot{\gamma}$. (ii) Boundary layer films, intermediate regime. A Newtonian regime is again observed [$\eta_{\mathrm{eff}} =$ constant, $n = 0$ in (18.46)] at low loads and low shear rates, but η_{eff} is much higher than the bulk value. As the shear rate $\dot{\gamma}$ increases beyond $\dot{\gamma}_{\mathrm{min}}$, the effective viscosity starts to drop with a power-law dependence on the shear rate [see panel **(b)**], with n in the range $-1/2$ to -1 most commonly observed. As the shear rate $\dot{\gamma}$ increases still more, beyond $\dot{\gamma}_{\mathrm{max}}$, a second Newtonian plateau is encountered. (iii) Boundary layer films, high load. The η_{eff} continues to grow with load and to be Newtonian provided that the shear rate is sufficiently low. Transition to sliding at high velocity is discontinuous ($n < -1$) and usually of the stick–slip variety. **(d)** Proposed friction map of friction force as a function of sliding velocity in various tribological regimes. With increasing load, Newtonian flow in the elastohydrodynamic (EHD) regimes crosses into the boundary regime of lubrication. Note that even EHD lubrication changes, at the highest velocities, to limiting shear stress response. At the highest loads (L) and smallest film thickness (D), the friction force goes through a maximum (the static friction, F_{s}), followed by a regime where the friction coefficient (μ) is roughly constant with increasing velocity (meaning that the kinetic friction, F_{k}, is roughly constant). Non-Newtonian shear thinning is observed at somewhat smaller load and larger film thickness; the friction force passes through a maximum at the point where $De = 1$. De, the Deborah number, is the point at which the applied shear rate exceeds the natural relaxation time of the boundary layer film. The velocity axis from 10^{-10} to 10^{10} (arbitrary units) indicates a large span. (Panels **(b)–(d)** after [18.259]. Copyright 1996, with permission from Elsevier Science)

or liquid-crystalline phase. This regime has recently been studied by *Granick* et al. [18.44, 219, 220, 222, 223], who used a friction attachment [18.43, 44] to the SFA where a sinusoidal input signal to a piezoelectric device makes the two surfaces slide back and forth laterally past each other at small amplitudes. This method provides information on the real and imaginary parts (elastic and dissipative components, respectively) of the shear modulus of thin films at different shear rates and film thickness. *Granick* [18.219] and *Hu* et al. [18.223] found that films of simple liquids become non-Newtonian in the 2.5–5 nm regime (about 10 molecular diameters, see Fig. 18.24). Polymer melts become non-Newtonian at much larger film thicknesses, depending on their molecular weight [18.47].

Klein and *Kumacheva* [18.46, 226, 260] studied the interaction forces and friction of small quasi-spherical liquid molecules such as cyclohexane between molecularly smooth mica surfaces. They concluded that surface epitaxial effects can cause the liquid film to already solidify at 6 molecular diameters, resulting in a sudden (discontinuous) jump to high friction at low shear rates. Such dynamic first-order transitions, however, may depend on the shear rate.

A generalized friction map (Fig. 18.24c,d) has been proposed by *Luengo* et al. [18.259] that illustrates the changes in η_{eff} from bulk Newtonian behavior ($n = 0$, $\eta_{\mathrm{eff}} = \eta_{\mathrm{bulk}}$) through the transition regime where n reaches a minimum of -1 with decreasing shear rate to the solid-like creep regime at very low $\dot{\gamma}$ where n returns to 0. A number of results from experimental, theoretical, and computer simulation work have shown values of n from $-1/2$ to -1 for this transition regime for a variety of systems and assumptions [18.219,220,239,261–267].

The intermediate regime appears to extend over a narrow range of film thickness, from about 4 to 10 molecular diameters or polymer radii of gyration. Thinner films begin to adopt "boundary" or "interfacial" friction properties (described below, see also Table 18.5). Note that the intermediate regime is actually a very narrow one when defined in terms of film thickness, for example, varying from about $D = 2$ to 4 nm for hexadecane films [18.219].

A fluid's effective viscosity η_{eff} in the intermediate regime is usually higher than in the bulk, but η_{eff} usu-



Fig. 18.25 Transition from smooth sliding to "inverted" stick–slip and to a second smooth sliding regime with increasing driving velocity during shear of two adsorbed surfactant monolayers in aqueous solution at a load of $L = 4.5$ mN and $T = 20\,°$C. The smooth sliding (*open circles*) to inverted stick–slip (*squares*) transition occurs at $v_c \sim 0.3$ µm/s. Prior to the transition, the kinetic stress levels off at after a logarithmic dependence on velocity. The quasi-smooth regime persists up to the transition at v_c. At high driving velocities (*filled circles*), a new transition to a smooth sliding regime is observed between 14 and 17 µm/s. (After [18.268] with permission)



Fig. 18.26a–d Idealized schematic illustration of molecular rearrangements occurring in a molecularly thin film of spherical or simple chain molecules between two solid surfaces during shear. Depending on the system, a number of different molecular configurations within the film are possible during slipping and sliding, shown here as stages **(c)**: total disorder as the whole film melts; **(c')**: partial disorder; and **(c'')**: order persists even during sliding with slip occurring at a single slip plane either within the film or at the walls. A dilation is predicted in the direction normal to the surfaces. (After [18.224] with permission)

ally *decreases* with increasing sliding velocity, v (known as *shear thinning*). When two surfaces slide in the intermediate regime, the motion tends to thicken the film (dilatancy). This sends the system into the bulk EHL regime where, as indicated by (18.44), the friction force now *increases* with velocity. This initial decrease, followed by an increase, in the frictional forces of many lubricant systems is the basis for the empirical Stribeck curve of Fig. 18.13. In the transition from bulk to boundary behavior there is first a quantitative change in the material properties (viscosity and elasticity), which can be continuous, to discontinuous qualitative changes that result in yield stresses and non-liquidlike behavior.

The rest of this section is devoted to friction in the boundary regime. Boundary friction may be thought of as applying to the case where a lubricant film is present, but where this film is of molecular dimensions – a few molecular layers or less.

18.8.3 Boundary Lubrication of Molecularly Thin Films: Nanorheology

When a liquid is confined between two surfaces or within any narrow space whose dimensions are less than 4 to 10 molecular diameters, both the static (equilibrium) and dynamic properties of the liquid, such as its compressibility and viscosity, can no longer be described even qualitatively in terms of the bulk properties. The molecules confined within such molecularly thin films become ordered into layers ("out-of-plane" ordering), and within each layer they can also have lateral order ("in-plane" ordering). Such films may be thought of as behaving more like a liquid crystal or a solid than a liquid.

As described in Sect. 18.4.3, the measured *normal* forces between two solid surfaces across molecularly thin films exhibit exponentially decaying oscillations, varying between attraction and repulsion with a periodicity equal to some molecular dimension of the solvent molecules. Thus most liquid films can sustain a finite normal stress, and the adhesion force between two surfaces across such films is "quantized", depending on the thickness (or number of liquid layers) between the surfaces. The structuring of molecules in thin films and the oscillatory forces it gives rise to are now reasonably well understood, both experimentally and theoretically, at least for simple liquids.

Work has also recently been done on the dynamic, e.g., viscous or shear, forces associated with molecularly thin films. Both experiments [18.38, 46, 203, 221, 226,227,269,270] and theory [18.200,201,261,271] indicate that even when two surfaces are in steady state sliding they still prefer to remain in one of their stable potential energy minima, i. e., a sheared film of liquid can retain its basic layered structure. Thus even during motion the film does not become totally liquid-like. Indeed, if there is some "in-plane" ordering within a film, it will exhibit a yield-point before it begins to flow. Such films can therefore sustain a finite shear stress, in addition to a finite normal stress. The value of the yield stress depends on the number of layers comprising the film and represents another "quantized" property of molecularly thin films [18.200].

The dynamic properties of a liquid film undergoing shear are very complex. Depending on whether the film is more liquid-like or solid-like, the motion will be smooth or of the stick–slip type. During sliding, transitions can occur between n layers and $(n-1)$ or $(n+1)$ layers (see Fig. 18.27). The details of the motion depend critically on the externally applied load, the temperature, the sliding velocity, the twist angle between the two surface lattices, and the sliding direction relative to the lattices.

Smooth and Stick–Slip Sliding

Recent advances in friction-measuring techniques have enabled the interfacial friction of molecularly thin films to be measured with great accuracy. Some of these advances have involved the surface forces apparatus technique [18.38, 45, 47, 221, 247, 269, 270], while others have involved the atomic force microscope [18.10, 53, 231, 272]. In addition, computer simulations [18.90,200,201,271,273,274] have become sufficiently sophisticated to enable fairly complex tribological systems to be studied. All these advances are necessary if one is to probe such subtle effects as smooth or stick–slip friction, transient and memory effects, and ultralow friction mechanisms at the molecular level.

The theoretical models presented in this section will be concerned with a situation commonly observed experimentally: Stick–slip occurs between a static state with high friction and a low-friction kinetic state, and a transition from this sliding regime to smooth sliding can be induced by an increase in velocity. Experimental data on various systems showing this behavior are shown in Figs. 18.27, 18.30b, and 18.31a. Recent studies on adhesive systems have revealed the possibility of other dynamic responses such as "inverted" stick–slip between two kinetic states of higher and lower friction and with a transition from smooth sliding to stick–slip with increasing velocity, as shown in Fig. 18.25 [18.268].



Fig. 18.27 Measured change in friction during interlayer transitions of the silicone liquid octamethylcyclotetrasiloxane (OMCTS), an inert liquid whose quasispherical molecules have a diameter of 0.8 nm. In this system, the shear stress $S_c = F/A$ was found to be constant as long as the number of layers, n, remained constant. Qualitatively similar results have been obtained with other quasi-spherical molecules such as cyclohexane [18.269]. The shear stresses are only weakly dependent on the sliding velocity v. However, for sliding velocities above some critical value, v_c, the stick–slip disappears and sliding proceeds smoothly at the kinetic value. (After [18.221] with permission)



Fig. 18.28 Schematic friction phase diagram representing the trends observed in the boundary friction of a variety of different surfactant monolayers. The characteristic bell-shaped curve also correlates with the adhesion energy hysteresis of the monolayers. The *arrows* indicate the direction in which the whole curve is dragged when the load, velocity, etc., is increased. (After [18.232] with permission)



Fig. 18.29a–c Different dynamic phase states of boundary monolayers during adhesive contact and/or frictional sliding. Solid-like **(a)** and liquid-like monolayers **(c)** exhibit low adhesion hysteresis and friction. Increasing the temperature generally shifts a system from the left to the right. Changing the load, sliding velocity, or other experimental conditions can also change the dynamic phase state of surface layers, as shown in Fig. 18.28. (After [18.232] with permission)

With the added insights provided by computer simulations, a number of distinct molecular processes have been identified during smooth and stick–slip sliding in model systems for the more familiar static-to-kinetic stick–slip and transition from stick–slip to smooth sliding. These are shown schematically in Fig. 18.26 for the case of spherical liquid molecules between two solid crystalline surfaces. The following regimes may be identified:

Surfaces at rest (Fig. 18.26a): Even with no externally applied load, solvent–surface epitaxial interactions can cause the liquid molecules in the film to attain a solid-like state. Thus at rest the surfaces are stuck to each other through the film.

Sticking regime (frozen, solid-like film) (Fig. 18.26b): A progressively increasing lateral shear stress is applied. The solid-like film responds elastically with a small lateral displacement and a small increase or "dilatancy" in film thickness (less than a lattice spacing or molecular dimension, σ). In this regime the film retains its frozen, solid-like state: All the strains are elastic and reversible, and the surfaces remain effectively stuck to each other. However, slow creep may occur over long time periods.

Slipping and sliding regimes (molten, liquid-like film) (Fig. 18.26c,c$'$,c$''$): When the applied shear stress or force has reached a certain critical value, the *static* friction force, F_s, the film suddenly melts (known as "shear melting") or rearranges to allow for wall-slip or slip within the film to occur at which point the two surfaces begin to slip rapidly past each other. If the applied stress is kept at a high value, the upper surface will continue to slide indefinitely.

Refreezing regime (resolidification of film) (Fig. 18.26d): In many practical cases, the rapid slip of the upper surface relieves some of the applied force, which eventually falls below another critical value, the *kinetic* friction force F_k, at which point the film resolidifies and the whole stick–slip cycle is repeated. On the other hand, if the slip rate is smaller than the rate at which the external stress is applied, the surfaces will continue to slide smoothly in the kinetic state and there will be no more stick–slip. The critical velocity at which stick–slip disappears is discussed in more detail in Sect. 18.8.3.

Experiments with linear chain (alkane) molecules show that the film thickness remains quantized during sliding, so that the structure of such films is probably more like that of a nematic liquid crystal where the liquid molecules have become shear aligned in some direction, enabling shear motion to occur while retaining some order within the film. Experiments on the friction of two molecularly smooth mica surfaces separated by three molecular layers of the liquid OMCTS (Fig. 18.27) show how the friction increases to higher values in a quantized way when the number of layers falls from $n = 3$ to $n = 2$ and then to $n = 1$.

Computer simulations for simple spherical molecules [18.201] further indicate that during the slip the film thickness is roughly 15% higher than at rest (i. e., the film density falls), and that the order parameter within the film drops from 0.85 to about 0.25. Such dilatancy has been investigated both experimentally [18.235] and in further computer simulations [18.234]. The changes in thickness and in order parameter are consistent with a disorganized state for the whole film during the slip [18.271], as illustrated schematically in Fig. 18.26c. At this stage, we can only speculate on other possible configurations of molecules in the slipping and sliding regimes. This probably depends on the shapes of the molecules (e.g., whether spherical or linear or branched), on the atomic structure of the surfaces, on the sliding velocity, etc. [18.275]. Figure 18.26c,c$'$,c$''$ shows three possible sliding modes wherein the shearing film either totally melts, or where the molecules retain their layered structure and where slip occurs between two or more layers. Other sliding modes, for example, involving the movement of dislocations or disclinations are also possible, and it is unlikely that one single mechanism applies in all cases.

Both friction and adhesion hysteresis vary nonlinearly with temperature, often peaking at some



Fig. 18.30 **(a)** "Phase transitions" model of stick–slip where a thin liquid film alternately freezes and melts as it shears, shown here for 22 spherical molecules confined between two solid crystalline surfaces. In contrast to the velocity-dependent friction model, the intrinsic friction force is assumed to change abruptly (at the transitions), rather than smooth or continuously. The resulting stick–slip is also different, for example, the peaks are sharper and the stick–slip disappears above some critical velocity v_c. Note that while the slip displacement is here shown to be only two lattice spacings, in most practical situations it is much larger, and that freezing and melting transitions at surfaces or in thin films may not be the same as freezing or melting transitions between the bulk solid and liquid phases. **(b)** Exact reproduction of a chart-recorder trace of the friction force for hexadecane between two untreated mica surfaces at increasing sliding velocity v, plotted as a function of time. In general, with increasing sliding speed, the stick–slip spikes increase in frequency and decrease in magnitude. As the critical sliding velocity v_c is approached, the spikes become erratic, eventually disappearing altogether at $v = v_c$. At higher sliding velocities the sliding continues smoothly in the kinetic state. Such friction traces are fairly typical for simple liquid lubricants and dry boundary lubricant systems (see Fig. 18.31a) and may be referred to as the "conventional" type of static–kinetic friction (in contrast to Fig. 18.25). Experimental conditions: contact area $A = 4 \times 10^{-9}\,\mathrm{m}^2$, load $L = 10\,\mathrm{mN}$, film thickness $D = 0.4$–$0.8\,\mathrm{nm}$, $v = 0.08$–$0.4\,\mu\mathrm{m\,s}^{-1}$, $v_c \approx 0.3\,\mu\mathrm{m\,s}^{-1}$, atmosphere: dry N_2 gas, $T = 18\,°\mathrm{C}$. [**(a)** and **(b)** after [18.276] with permission. Copyright 1993 American Chemical Society.] **(c)** Friction response of a thin squalane (a branched hydrocarbon) film at different loads and a constant sliding velocity $v = 0.08\,\mu\mathrm{m\,s}^{-1}$, slightly above the critical velocity for this system at low loads. Initally, with increasing load, the stick–slip amplitude and the mean friction force decrease with sliding time or sliding distance. However, at high loads or pressures, the mean friction force increases with time, and the stick–slip takes on a more symmetrical, sinusoidal shape. At all loads investigated, the stick–slip component gradually decayed as the friction proceeded towards smooth sliding. (*Gourdon* and *Israelachvili*, unpublished data)

particular temperature, T_0. The temperature dependence of these forces can, therefore, be represented on a friction phase diagram such as the one shown in Fig. 18.28. Experiments have shown that T_0, and the whole bell-shaped curve, are shifted along the temperature-axis (as well as in the vertical direction) in a systematic way when the load, sliding velocity, etc., are varied. These shifts also appear to be highly correlated with one another, for example, an increase in temperature producing effects that are similar to *decreasing* the sliding speed or load.

Such effects are also commonly observed in other energy dissipating phenomena such as polymer viscoelasticity [18.277], and it is likely that a similar physical mechanism is at the heart all of such phenomena. A possible molecular process underlying the energy dissipation of chain molecules during boundary layer sliding is illustrated in Fig. 18.29, which shows the three main dynamic phase states of boundary monolayers.

In contrast to the characteristic relaxation time associated with fluid lubricants, it has been established



Fig. 18.31 **(a)** Exact reproduction of chart-recorder trace for the friction of closely packed surfactant monolayers (L-α-dimirystoyl-phosphatidyl-ethanolamine, DMPE) on mica (dry boundary friction) showing qualitatively similar behavior to that obtained with a liquid hexadecane film (Fig. 18.30b). In this case, $L = 0$, $v_c \approx 0.1\,\mu\mathrm{m\,s}^{-1}$, atmosphere: dry N_2 gas, $T = 25\,°\mathrm{C}$. **(b)** Sliding typical of liquid-like monolayers, here shown for calcium alkylbenzene sulfonate in dry N_2 gas at $T = 25\,°\mathrm{C}$ and $L = 0$. (After [18.207] with permission. Copyright 1993 American Chemical Society)

that for unlubricated (dry, solid, rough) surfaces, there is a characteristic memory distance that must be exceeded before the system looses all memory of its initial state (original surface topography). The underlying mechanism for a characteristic distance was first used to successfully explain rock mechanics and earthquake faults [18.278] and, more recently, the tribological behavior of unlubricated surfaces of ceramics, paper and elastomeric polymers [18.252, 279]. Recent experiments [18.275, 280, 281] suggest that fluid lubricants composed of complex branched-chained or polymer molecules may also have characteristic distances (in addition to characteristic relaxation times) associated with their tribological behavior – the characteristic distance being the total sliding distance that must be exceeded before the system reaches its steady-state tribological conditions (see Sect. 18.8.3).

Abrupt vs. Continuous Transitions Between Smooth and Stick–Slip Sliding

An understanding of stick–slip is of great practical importance in tribology [18.282], since these spikes are the major cause of damage and wear of moving parts. Stick–slip motion is a very common phenomenon and is also the cause of sound generation (the sound of a violin string, a squeaking door, or the chatter of machinery), sensory perception (taste texture and feel), earthquakes, granular flow, nonuniform fluid flow such as the spurting flow of polymeric liquids, etc. In the previous section, the stick–slip motion arising from freezing–melting transitions in thin interfacial films was described. There are other mechanisms that can give rise to stick–slip friction, which will now be considered. However, before proceeding with this, it is important to clarify exactly what one is measuring during a friction experiment.

Most tribological systems and experiments can be described in terms of an equivalent mechanical circuit with certain characteristics. The friction force F_0, which is generated at the surfaces, is generally measured as F at some other place in the setup. The mechanical coupling between the two may be described in terms of a simple elastic stiffness or compliance, K, or as more complex nonelastic coefficients, depending on the system. The distinction between F and F_0 is important because in almost all practical cases, the applied, measured, or detected force, F, is *not* the same as the "real" or "intrinsic" friction force, F_0, generated at the surfaces. F and F_0 are coupled in a way that depends on the mechanical construction of the system, for example, the axle of a car wheel that connects it to the engine. This coupling can be modeled as an elastic spring of stiffness K and mass m. This is the simplest type of mechanical coupling and is also the same as in SFA and AFM type experiments. More complicated real systems can be reduced to a system of springs and dashpots, as described by *Peachey* et al. [18.283] and *Luengo* et al. [18.47].

We now consider four different models of stick–slip friction, where the mechanical couplings are assumed to be of the simple elastic spring type. The first three mechanisms may be considered traditional or classical mechanisms or models [18.282], the fourth is essentially the same as the freezing–melting phase-transition model described in Sect. 18.8.3.

Rough Surfaces or Surface Topology Model. Rapid slips can occur whenever an asperity on one surface goes over the top of an asperity on the other surface. The extent of the slip will depend on asperity heights and slopes, on the speed of sliding, and on the elastic compliance of the surfaces and the moving stage. As in all cases of stick–slip motion, the driving velocity v may be constant, but the resulting motion at the surfaces v_0 will display large slips. This type of stick–slip has been described by *Rabinowicz* [18.282]. It will not be of much concern here since it is essentially a noise-type fluctuation, resulting from surface imperfections rather than from the intrinsic interaction between two surfaces. Actually, at the atomic level, the regular atomic-scale corrugations of surfaces can lead to periodic stick–slip motion of the type shown here. This is what is sometimes measured by AFM tips [18.10, 53, 231, 272].

Distance-Dependent or Creep Model. Another theory of stick–slip, observed in solid-on-solid sliding, is one that involves a characteristic *distance*, but also a characteristic time, τ_s, this being the characteristic time required for two asperities to increase their adhesion strength after coming into contact. Originally proposed by *Rabinowicz* [18.282, 284], this model suggests that two rough macroscopic surfaces adhere through their microscopic asperities of characteristic length. During shearing, each surface must first creep this distance (the size of the contacting junctions) after which the surfaces continue to slide, but with a lower (kinetic) friction force than the original (static) value. The reason for the decrease in the friction force is that even though, on average, new asperity junctions should form as rapidly as the old ones break, the time-dependent adhesion and friction of the new ones will be lower than the old ones.

The friction force, therefore, remains high during the creep stage of the slip. But once the surfaces have moved the characteristic distance, the friction rapidly drops to the kinetic value. For any system where the kinetic friction is less than the static force (or one that has a negative slope over some part of its F_0 versus v_0 curve) will exhibit regular stick–slip sliding motion for certain values of K, m, and driving velocity, v.

This type of friction has been observed in a variety of dry (unlubricated) systems such as paper-on-paper [18.285, 286] and steel-on-steel [18.284, 287, 288]. This model is also used extensively in geologic systems to analyze rock-on-rock sliding [18.289, 290]. While originally described for adhering macroscopic asperity junctions, the distance-dependent model may also apply to molecularly smooth surfaces. For example, for polymer lubricant films, the characteristic length would now be the chain–chain entanglement length, which could be much larger in a confined geometry than in the bulk.

Velocity-Dependent Friction Model. In contrast to the two friction models mentioned above, which apply mainly to unlubricated, solid-on-solid contacts, the stick–slip of surfaces with thin liquid films between them is better described by other mechanisms. The velocity-dependent friction model is the most studied mechanism of stick–slip and, until recently, was considered to be the only cause of intrinsic stick–slip. If a friction force decreases with increasing sliding velocity, as occurs with boundary films exhibiting shear thinning, the force (F_s) needed to initiate motion will be higher than the force (F_k) needed to maintain motion.

A decreasing intrinsic friction force F_0 with sliding velocity v_0 results in the sliding surface or stage moving in a periodic fashion, where during each cycle rapid acceleration is followed by rapid deceleration. So long as the drive continues to move at a fixed velocity v, the surfaces will continue to move in a periodic fashion punctuated by abrupt stops and starts whose frequency and amplitude depend not only on the function $F_0(v_0)$, but also on the stiffness K and mass m of the moving stage, and on the starting conditions at $t = 0$.

More precisely, the motion of the sliding surface or stage can be determined by solving the following differential equation:

$$\begin{aligned} & m\ddot{x} = (F_0 - F) = F_0 - (x_0 - x)K \\ \text{or} \quad & m\ddot{x} + (x_0 - x)K - F_0 = 0\,, \end{aligned} \tag{18.47}$$

where $F_0 = F_0(x_0, v_0, t)$ is the intrinsic or "real" friction force at the shearing surfaces, F is the force on the spring (the externally applied or measured force), and $(F_0 - F)$ is the force on the stage. To fully solve (18.47), one must also know the initial (starting) conditions at $t = 0$, and the driving or steady-state conditions at finite t. Commonly, the driving condition is: $x = 0$ for $t < 0$ and $x = vt$ for $t > 0$, where $v =$ constant. In other systems, the appropriate driving condition may be $F =$ constant.

Various, mainly phenomenological, forms for $F_0 = F_0(x_0, v_0, t)$ have been proposed to explain various kinds of stick–slip phenomena. These models generally assume a particular functional form for the friction as a function of velocity only, $F_0 = F_0(v_0)$, and they may also contain a number of mechanically coupled elements comprising the stage [18.291, 292]. One version is a two-state model characterized by two friction forces, F_s and F_k, which is a simplified version of the phase transitions model described below. More complicated versions can have a rich F–v spectrum, as proposed by *Persson* [18.293]. Unless the experimental data is very detailed and extensive, these models cannot generally distinguish between different types of mechanisms.

Neither do they address the basic question of the *origin* of the friction force, since this is assumed to begin with.

Experimental data has been used to calculate the friction force as a function of velocity *within* an individual stick–slip cycle [18.294]. For a macroscopic granular material confined between solid surfaces, the data shows a velocity-weakening friction force during the first half of the slip. However, the data also shows a hysteresis loop in the friction–velocity plot, with a different behavior in the deceleration half of the slip phase. Similar results were observed for a 1–2 nm liquid lubricant film between mica surfaces [18.275]. These results indicate that a purely velocity-dependent friction law is insufficient to describe such systems, and an additional element such as the *state* of the confined material must be considered.

Phase Transitions Model. In recent molecular dynamics computer simulations it has been found that thin interfacial films undergo first-order phase transitions between solid-like and liquid-like states during sliding [18.201, 273]. It has been suggested that this is responsible for the observed stick–slip behavior of simple isotropic liquids between two solid crystalline surfaces. With this interpretation, stick–slip is seen to arise because of the abrupt change in the flow properties of a film at a transition [18.224,225,261], rather than the gradual or continuous change, as occurs in the previous example. Other computer simulations indicate that it is the stick–slip that induces a disorder ("shear-melting") in the film, not the other way around [18.295].

An interpretation of the well-known phenomenon of decreasing coefficient of friction with increasing sliding velocity has been proposed by *Thompson* and *Robbins* [18.201] based on their computer simulation. This postulates that it is not the friction that changes with sliding speed v, but rather the time various parts of the system spend in the sticking and sliding modes. In other words, at any instant during sliding, the friction at any local region is always F_s or F_k, corresponding to the "static" or "kinetic" values. The measured frictional force, however, is the sum of all these discrete values averaged over the whole contact area. Since as v increases each local region spends more time in the sliding regime (F_k) and less in the sticking regime (F_s), the overall friction coefficient falls. One may note that this interpretation reverses the traditional way that stick–slip has been explained. Rather than invoking a decreasing friction with velocity to explain stick–slip, it is now the more fundamental stick–slip phenomenon that is producing the apparent decrease in the friction force with increasing sliding velocity. This approach has been studied analytically by *Carlson* and *Batista* [18.296], with a comprehensive rate- and state- dependent friction force law. This model includes an analytic description of the freezing–melting transitions of a film, resulting in a friction force that is a function of sliding velocity in a natural way. This model predicts a full range of stick–slip behavior observed experimentally.

An example of the rate- and state-dependent model is observed when shearing thin films of OMCTS between mica surfaces [18.297, 298]. In this case, the static friction between the surfaces is dependent on the time that the surfaces are at rest with respect to each other, while the intrinsic kinetic friction $F_{k,0}$ is relatively constant over the range of velocities. At slow driving velocities, the system responds with stick–slip sliding with the surfaces reaching maximum static friction before each slip event, and the amplitude of the stick–slip, $F_s - F_k$, is relatively constant. As the driving velocity increases, the static friction decreases as the time at relative rest becomes shorter with respect to the characteristic time of the lubricant film. As the static friction decreases with increasing drive velocity, it eventually equals the intrinsic kinetic friction $F_{k,0}$, which defines the critical velocity v_c, above which the surfaces slide smoothly without the jerky stick–slip motion.

The above classifications of stick–slip are not exclusive, and molecular mechanisms of real systems may exhibit aspects of different models simultaneously. They do, however, provide a convenient classification of existing models and indicate which experimental parameters should be varied to test the different models.

Critical Velocity for Stick–Slip. For any given set of conditions, stick–slip disappears above some critical sliding velocity v_c, above which the motion continues smoothly in the liquid-like or kinetic state. The critical velocity is well described by two simple equations. Both are based on the phase transition model, and both include some parameter associated with the inertia of the measuring instrument. The first equation is based on both experiments and simple theoretical modeling [18.276]:

$$v_c \approx \frac{(F_s - F_k)}{5K\tau_0}\,, \tag{18.48}$$

where τ_0 is the *characteristic nucleation time* or freezing time of the film. For example, inserting the following typically measured values for a ~1-nm-thick hexadecane film between mica: $(F_s - F_k) \approx 5\,\text{mN}$, spring constant $K \approx 500\,\text{N}\,\text{m}^{-1}$, and nucleation time [18.276]

$\tau_0 \approx 5\,\mathrm{s}$, we obtain $v_c \approx 0.4\,\mu\mathrm{m\,s}^{-1}$, which is close to typically measured values (Fig. 18.30b).

The second equation is based on computer simulations [18.273]:

$$v_c \approx 0.1\sqrt{\frac{F_s\sigma}{m}}\,, \tag{18.49}$$

where σ is a molecular dimension and m is the mass of the stage. Again, inserting typical experimental values into this equation, viz., $m \approx 20\,\mathrm{g}$, $\sigma \approx 0.5\,\mathrm{nm}$, and $(F_s - F_k) \approx 5\,\mathrm{mN}$ as before, we obtain $v_c \approx 0.3\,\mu\mathrm{m\,s}^{-1}$, which is also close to measured values.

Stick–slip also disappears above some critical temperature T_c, which is not the same as the melting temperature of the bulk fluid. Certain correlations have been found between v_c and T_c and between various other tribological parameters that appear to be consistent with the principle of time–temperature superposition (see Sect. 18.8.3), similar to that occurring in viscoelastic polymer fluids [18.277, 299, 300].

Recent work on the coupling between the mechanical resonances of the sliding system and molecular-scale relaxations [18.234, 301–303] has resulted in a better understanding of a phenomenon previously noted in various engineering applications: the vibrating of one of the sliding surfaces perpendicularly to the sliding direction can lead to a significant reduction of the friction. At certain oscillation amplitudes and a frequency higher than the molecular-scale relaxation frequency, stick–slip friction can be eliminated and replaced by an ultralow kinetic friction state.

18.9 Role of Molecular Shape and Surface Structure in Friction

The above scenario is already quite complicated, and yet this is the situation for the simplest type of experimental system. The factors that appear to determine the critical velocity v_c depend on the type of liquid between the surfaces (as well as on the surface lattice structure). Small spherical molecules such as cyclohexane and OMCTS have been found to have very high v_c, which indicates that these molecules can rearrange relatively quickly in thin films. Chain molecules and especially branched chain molecules have been found to have much lower v_c, which is to be expected, and such liquids tend to slide smoothly or with erratic stick–slip [18.275], rather than in a stick–slip fashion (see Table 18.5). With highly asymmetric molecules, such as multiply branched isoparaffins and polymer melts, no regular spikes or stick–slip behavior occurs at any speed, since these molecules can never order themselves sufficiently to solidify. Examples of such liquids are some perfluoropolyethers and polydimethylsiloxanes (PDMS).

Recent computer simulations [18.274, 304, 305] of the structure, interaction forces, and tribological behavior of chain molecules between two shearing surfaces indicate that both linear *and* singly or doubly branched chain molecules order between two flat surfaces by aligning into discrete layers parallel to the surfaces. However, in the case of the weakly branched molecules, the expected oscillatory forces do not appear because of a complex cancellation of entropic and enthalpic contributions to the interaction free energy, which results in a monotonically smooth interaction, exhibiting a weak energy minimum rather than the oscillatory force profile that is characteristic of linear molecules. During sliding, however, these molecules can be induced to further align, which can result in a transition from smooth to stick–slip sliding.

Table 18.5 shows the trends observed with some organic and polymeric liquid between smooth mica surfaces. Also listed are the bulk viscosities of the liquids. From the data of Table 18.5 it appears that there is a direct correlation between the shapes of molecules and their coefficient of friction or effectiveness as lubricants (at least at low shear rates). Small spherical or chain molecules have high friction with stick–slip, because they can pack into ordered solid-like layers. In contrast, longer chained and irregularly shaped molecules remain in an entangled, disordered, fluid-like state even in very thin films, and these give low friction and smoother sliding. It is probably for this reason that irregularly shaped branched chain molecules are usually better lubricants. It is interesting to note that the friction coefficient generally decreases as the bulk viscosity of the liquids *increases*. This unexpected trend occurs because the factors that are conducive to low friction are generally conducive to high viscosity. Thus molecules with side groups such as branched alkanes and polymer melts usually have higher bulk viscosities than their linear homologues for obvious reasons. However, in thin films the linear molecules have higher shear stresses, because of their ability to become ordered. The only exception to the

Table 18.5 Effect of molecular shape and short-range forces on tribological properties[a]

Liquid	Short-range force	Type of friction	Friction coefficient	Bulk liquid viscosity (cP)
Organic (water-free)				
Cyclohexane	Oscillatory	Quantized stick–slip	$\gg 1$	0.6
OMCTS[b]	Oscillatory	Quantized stick–slip	$\gg 1$	2.3
Octane	Oscillatory	Quantized stick–slip	1.5	0.5
Tetradecane	Oscillatory ↔ smooth	stick–slip ↔ smooth	1.0	2.3
Octadecane (branched)	Oscillatory ↔ smooth	stick–slip ↔ smooth	0.3	5.5
PDMS[b] ($M = 3{,}700\,\mathrm{g\,mol^{-1}}$, melt)	Oscillatory ↔ smooth	Smooth	0.4	50
PBD[b] ($M = 3{,}500\,\mathrm{g\,mol^{-1}}$, branched)	Smooth	Smooth	0.03	800
Water				
Water (KCl solution)	Smooth	Smooth	0.01–0.03	1.0

[a] For molecularly thin liquid films between two shearing mica surfaces at 20 °C

[b] OMCTS: Octamethylcyclotetrasiloxane, PDMS: Polydimethylsiloxane, PBD: Polybutadiene



Fig. 18.32a–c Schematic view of interfacial film composed of spherical molecules under a compressive pressure between two solid crystalline surfaces. **(a)** If the two surface lattices are free to move in the x-y-z directions, so as to attain the lowest energy state, they could equilibrate at values of x, y, and z, which induce the trapped molecules to become "epitaxially" ordered into a "solid-like" film. **(b)** Similar view of trapped molecules between two solid surfaces that are not free to adjust their positions, for example, as occurs in capillary pores or in brittle cracks. **(c)** Similar to **(a)**, but with chain molecules replacing the spherical molecules in the gap. These may not be able to order as easily as do spherical molecules even if x, y, and z can adjust, resulting in a situation that is more akin to **(b)**. (After [18.276] with permission. Copyright 1993 American Chemical Society)

above correlations is water, which has been found to exhibit both low viscosity *and* low friction (see Fig. 18.20, and Sect. 18.7.3). In addition, the presence of water can drastically lower the friction and eliminate the stick–slip of hydrocarbon liquids when the sliding surfaces are hydrophilic.



Fig. 18.33a–f Schematic representation of the film under shear. **(a)** The lubricant molecules are just confined, but not oriented in any particular direction. Because of the need to shear, the film dilates **(b)**. The molecules disentangle **(c)** and get oriented in a certain direction related to the shear direction **(d)**. **(e)** Slowly evolving domains grow inside the contact region. These macroscopic domains are responsible for the long relaxation times. **(f)** At the steady-state, a continuous gradient of confinement time and molecular order is established in the contact region, which is different for molecules adsorbed on the upper and lower surfaces. Molecules entering into the contact are not oriented or ordered. The required sliding distance to modify their state defines a characteristic distance. Molecules leaving the contact region need some (short) characteristic time to regain their bulk, unconfined configuration. (After [18.281] with permission. Copyright 2000 American Chemical Society)

If an "effective" viscosity, η_{eff}, were to be calculated for the liquids of Table 18.5, the values would be many orders of magnitude higher than those of the bulk liquids. This can be demonstrated by the following simple calculation based on the usual equation for Couette flow (see (18.44)):

$$\eta_{\text{eff}} = F_{\text{k}} D/Av\,, \tag{18.50}$$

where F_{k} is the kinetic friction force, D is the film thickness, A the contact area, and v the sliding velocity. Using typical values for experiments with hexadecane [18.276]: $F_{\text{k}} = 5\,\text{mN}$, $D = 1\,\text{nm}$, $A = 3 \times 10^{-9}\,\text{m}^2$, and $v = 1\,\mu\text{m}\,\text{s}^{-1}$, one gets $\eta_{\text{eff}} \approx 2{,}000\,\text{Ns}\,\text{m}^{-2}$, or 20,000 Poise, which is $\sim 10^6$ times higher than the bulk viscosity, η_{bulk}, of the liquid. It is instructive to consider that this very high effective viscosity nevertheless still produces a low friction force or friction coefficient μ of about 0.25. It is interesting to speculate that if a 1 nm film were to exhibit bulk viscous behavior, the friction coefficient under the same sliding conditions would be as low as 0.000001. While such a low value has never been reported for any tribological system, one may consider it a theoretical lower limit that could conceivably be attained under certain experimental conditions.

Various studies [18.44, 219, 220, 222] have shown that confinement and load generally increase the effective viscosity and/or relaxation times of molecules, suggestive of an increased glassiness or solid-like behavior (Figs. 18.32 and 18.33). This is in marked contrast to studies of liquids in small confining capillaries where the opposite effects have been observed [18.306, 307]. The reason for this is probably because the two modes of confinement are different. In the former case (confinement of molecules between two structured solid surfaces), there is generally little opposition to any lateral or vertical displacement of the two surface lattices relative to each other. This means that the two lattices can shift in the x-y-z plane (Fig. 18.32a) to accommodate the trapped molecules in the most crystallographically commensurate or epitaxial way, which would favor an ordered, solid-like state. In contrast, the walls of capillaries are rigid and cannot easily move or adjust to accommodate the confined molecules (Fig. 18.32b), which will therefore be forced into a more disordered, liquid-like state (unless the capillary wall geometry and lattice are *exactly* commensurate with the liquid molecules, as occurs in certain zeolites [18.307]).

Experiments have demonstrated the effects of surface lattice mismatch on the friction between surfaces [18.203, 204, 308]. Similar to the effects of lattice mismatch on adhesion (Fig. 18.11), the static friction of a confined liquid film is maximum when the lattices of the confining surfaces are aligned. For OMCTS confined between mica surfaces [18.204] the static friction was found to vary by more than a factor of 4, while for bare mica surfaces the variation was by a factor of 3.5 [18.308]. In contrast to the sharp variations in adhesion energy over small twist angles, the variations in friction as a function of twist angle were much more broad both in magnitude and angular spread. Similar variations in friction as a function of twist or misfit angles have also been observed in computer simulations [18.309].

Robbins et al. [18.274] computed the friction forces of two clean crystalline surfaces as a function of the angle between their surface lattices. They found that for all non-zero angles (finite "twist" angles) the friction forces fell to zero due to incommensurability effects. They further found that submonolayer amounts of organic or other impurities trapped between two incommensurate surfaces can generate a finite friction force. They, therefore, concluded that any finite friction force measured between incommensurate surfaces is probably due to such "third body" effects.

With rough surfaces, i. e., those that have *random* protrusions rather than being periodically structured, we expect a smearing out of the correlated intermolecular interactions that are involved in film freezing and melting (and in phase transitions in general). This should effectively eliminate the highly regular stick–slip and may also affect the location of the slipping planes [18.123, 252, 279]. The stick–slip friction of "real" surfaces, which are generally rough, may, therefore, be quite different from those of perfectly smooth surfaces composed of the same material. We should note, however, that even between rough surfaces, most of the contacts occur between the tips of microscopic asperities, which may be smooth over their microscopic contact area.

References

18.1 J. N. Israelachvili: Surface Forces and Microrheology of Molecularly Thin Liquid Films. In: *Handbook of Micro/Nanotribology*, ed. by B. Bhushan (CRC Press, Boca Raton 1995) pp. 267–319

18.2 K. B. Lodge: Techniques for the measurement of forces between solids, Adv. Colloid Interface Sci. **19** (1983) 27–73

18.3 J. N. Israelachvili: *Intermolecular and Surface Forces*, 2nd edn. (Academic Press, London 1991)

18.4 P. F. Luckham, B. A. de L. Costello: Recent developments in the measurement of interparticle forces, Adv. Colloid Interface Sci. **44** (1993) 183–240

18.5 P. M. Claesson, T. Ederth, V. Bergeron, M. W. Rutland: Techniques for measuring surface forces, Adv. Colloid Interface Sci. **67** (1996) 119–183

18.6 V. S. J. Craig: An historical review of surface force measurement techniques, Colloids Surf. A **129–130** (1997) 75–94

18.7 J. N. Israelachvili, G. E. Adams: Measurements of forces between two mica surfaces in aqueous electrolyte solutions in the range 0–100 nm, J. Chem. Soc. Faraday Trans. I **74** (1978) 975–1001

18.8 G. Binnig, C. F. Quate, C. Gerber: Atomic force microscope, Phys. Rev. Lett. **56** (1986) 930–933

18.9 W. A. Ducker, T. J. Senden, R. M. Pashley: Direct measurement of colloidal forces using an atomic force microscope, Nature **353** (1991) 239–241

18.10 E. Meyer, R. M. Overney, K. Dransfeld, T. Gyalog: *Nanoscience: Friction and Rheology on the Nanometer Scale* (World Scientific, Singapore 1998)

18.11 J. N. Israelachvili: Measurements of the viscosity of thin fluid films between two surfaces with and without adsorbed polymers, Colloid Polym. Sci. **264** (1986) 1060–1065

18.12 J. P. Montfort, G. Hadziioannou: Equilibrium and dynamic behavior of thin films of a perfluorinated polyether, J. Chem. Phys. **88** (1988) 7187–7196

18.13 A. Dhinojwala, S. Granick: Surface forces in the tapping mode: Solvent permeability and hydrodynamic thickness of adsorbed polymer brushes, Macromolecules **30** (1997) 1079–1085

18.14 B. V. Derjaguin: Untersuchungen über die Reibung und Adhäsion, IV. Theorie des Anhaftens kleiner Teilchen, Kolloid Z. **69** (1934) 155–164

18.15 K. L. Johnson, K. Kendall, A. D. Roberts: Surface energy and the contact of elastic solids, Proc. R. Soc. London A **324** (1971) 301–313

18.16 J. N. Israelachvili, P. M. McGuiggan: Adhesion and short-range forces between surfaces. Part 1: New apparatus for surface force measurements, J. Mater. Res. **5** (1990) 2223–2231

18.17 J. N. Israelachvili: Thin film studies using multiple-beam interferometry, J. Colloid Interface Sci. **44** (1973) 259–272

18.18 Y. L. Chen, T. Kuhl, J. Israelachvili: Mechanism of cavitation damage in thin liquid films: Collapse damage vs. inception damage, Wear **153** (1992) 31–51

18.19 M. Heuberger, G. Luengo, J. Israelachvili: Topographic information from multiple beam interferometry in the surface forces apparatus, Langmuir **13** (1997) 3839–3848

18.20 R. M. Pashley: DLVO and hydration forces between mica surfaces in Li^+, Na^+, K^+, and Cs^+ electrolyte solutions: A correlation of double-layer and hydration forces with surface cation exchange properties, J. Colloid Interface Sci. **83** (1981) 531–546

18.21 R. M. Pashley: Hydration forces between mica surfaces in electrolyte solution, Adv. Colloid Interface Sci. **16** (1982) 57–62

18.22 R. G. Horn, D. T. Smith, W. Haller: Surface forces and viscosity of water measured between silica sheets, Chem. Phys. Lett. **162** (1989) 404–408

18.23 R. G. Horn, D. R. Clarke, M. T. Clarkson: Direct measurements of surface forces between sapphire crystals in aqueous solutions, J. Mater. Res. **3** (1988) 413–416

18.24 W. W. Merrill, A. V. Pocius, B. V. Thakker, M. Tirrell: Direct measurement of molecular level adhesion forces between biaxially oriented solid polymer films, Langmuir **7** (1991) 1975–1980

18.25 J. Klein: Forces between mica surfaces bearing adsorbed macromolecules in liquid media, J. Chem. Soc. Faraday Trans. I **79** (1983) 99–118

18.26 S. S. Patel, M. Tirrell: Measurement of forces between surfaces in polymer fluids, Annu. Rev. Phys. Chem. **40** (1989) 597–635

18.27 H. Watanabe, M. Tirrell: Measurements of forces in symmetric and asymmetric interactions between diblock copolymer layers adsorbed on mica, Macromolecules **26** (1993) 6455–6466

18.28 T. L. Kuhl, D.E. Leckband, D. D. Lasic, J. N. Israelachvili: Modulation and modeling of interaction forces between lipid bilayers exposing terminally grafted polymer chains. In: *Stealth Liposomes*, ed. by D. Lasic, F. Martin (CRC Press, Boca Raton 1995) pp. 73–91

18.29 J. Klein: Shear, friction, and lubrication forces between polymer-bearing surfaces, Annu. Rev. Mater. Sci. **26** (1996) 581–612

18.30 M. Ruths, D. Johannsmann, J. Rühe, W. Knoll: Repulsive forces and relaxation on compression of entangled, polydisperse polystyrene brushes, Macromolecules **33** (2000) 3860–3870

18.31 C. A. Helm, J. N. Israelachvili, P. M. McGuiggan: Molecular mechanisms and forces involved in the adhesion and fusion of amphiphilic bilayers, Science **246** (1989) 919–922

18.32 Y. L. Chen, C. A. Helm, J. N. Israelachvili: Molecular mechanisms associated with adhesion and contact angle hysteresis of monolayer surfaces, J. Phys. Chem. **95** (1991) 10736–10747

18.33 D. E. Leckband, J. N. Israelachvili, F.-J. Schmitt, W. Knoll: Long-range attraction and molecular rearrangements in receptor-ligand interactions, Science **255** (1992) 1419–1421

18.34 J. Peanasky, H. M. Schneider, S. Granick, C. R. Kessel: Self-assembled monolayers on mica for experiments utilizing the surface forces apparatus, Langmuir **11** (1995) 953–962

18.35 C. J. Coakley, D. Tabor: Direct measurement of van der Waals forces between solids in air, J. Phys. D **11** (1978) L77–L82

18.36 J. L. Parker, H. K. Christenson: Measurements of the forces between a metal surface and mica across liquids, J. Chem. Phys. **88** (1988) 8013–8014

18.37 C. P. Smith, M. Maeda, L. Atanasoska, H. S. White, D. J. McClure: Ultrathin platinum films on mica and the measurement of forces at the platinum/water interface, J. Phys. Chem. **92** (1988) 199–205

18.38 S. J. Hirz, A. M. Homola, G. Hadziioannou, C. W. Frank: Effect of substrate on shearing properties of ultrathin polymer films, Langmuir **8** (1992) 328–333

18.39 J. M. Levins, T. K. Vanderlick: Reduction of the roughness of silver films by the controlled application of surface forces, J. Phys. Chem. **96** (1992) 10405–10411

18.40 S. Steinberg, W. Ducker, G. Vigil, C. Hyukjin, C. Frank, M. Z. Tseng, D. R. Clarke, J. N. Israelachvili: Van der Waals epitaxial growth of α-alumina nanocrystals on mica, Science **260** (1993) 656–659

18.41 G. Vigil, Z. Xu, S. Steinberg, J. Israelachvili: Interactions of silica surfaces, J. Colloid Interface Sci. **165** (1994) 367–385

18.42 M. Ruths, M. Heuberger, V. Scheumann, J. Hu, W. Knoll: Confinement-induced film thickness transitions in liquid crystals between two alkanethiol monolayers on gold, Langmuir **17** (2001) 6213–6219

18.43 J. Van Alsten, S. Granick: Molecular tribometry of ultrathin liquid films, Phys. Rev. Lett. **61** (1988) 2570–2573

18.44 J. Van Alsten, S. Granick: Shear rheology in a confined geometry: Polysiloxane melts, Macromolecules **23** (1990) 4856–4862

18.45 A. M. Homola, J. N. Israelachvili, M. L. Gee, P. M. McGuiggan: Measurements of and relation between the adhesion and friction of two surfaces separated by molecularly thin liquid films, J. Tribol. **111** (1989) 675–682

18.46 J. Klein, E. Kumacheva: Simple liquids confined to molecularly thin layers. I. Confinement-induced liquid-to-solid phase transitions, J. Chem. Phys. **108** (1998) 6996–7009

18.47 G. Luengo, F.-J. Schmitt, R. Hill, J. Israelachvili: Thin film rheology and tribology of confined polymer melts: Contrasts with bulk properties, Macromolecules **30** (1997) 2482–2494

18.48 E. Kumacheva: Interfacial friction measurements in surface force apparatus, Prog. Surf. Sci. **58** (1998) 75–120

18.49 A. L. Weisenhorn, P. K. Hansma, T. R. Albrecht, C. F. Quate: Forces in atomic force microscopy in air and water, Appl. Phys. Lett. **54** (1989) 2651–2653

18.50 G. Meyer, N. M. Amer: Simultaneous measurement of lateral and normal forces with an optical-beam-deflection atomic force microscope, Appl. Phys. Lett. **57** (1990) 2089–2091

18.51 E. L. Florin, V. T. Moy, H. E. Gaub: Adhesion forces between individual ligand–receptor pairs, Science **264** (1994) 415–417

18.52 G. U. Lee, D. A. Kidwell, R. J. Colton: Sensing discrete streptavidin–biotin interactions with atomic force microscopy, Langmuir **10** (1994) 354–357
18.53 C. M. Mate, G. M. McClelland, R. Erlandsson, S. Chiang: Atomic-scale friction of a tungsten tip on a graphite surface, Phys. Rev. Lett. **59** (1987) 1942–1945
18.54 R. W. Carpick, M. Salmeron: Scratching the surface: Fundamental investigations of tribology with atomic force microscopy, Chem. Rev. **97** (1997) 1163–1194
18.55 J. P. Cleveland, S. Manne, D. Bocek, P. K. Hansma: A nondestructive method for determining the spring constant of cantilevers for scanning force microscopy, Rev. Sci. Instrum. **64** (1993) 403–405
18.56 J. E. Sader, J. W. M. Chon, P. Mulvaney: Calibration of rectangular atomic force microscope cantilevers, Rev. Sci. Instrum. **70** (1999) 3967–3969
18.57 Y. Liu, T. Wu, D. F. Evans: Lateral force microscopy study on the shear properties of self-assembled monolayers of dialkylammonium surfactant on mica, Langmuir **10** (1994) 2241–2245
18.58 C. Neto, V. S. J. Craig: Colloid probe characterization: Radius and roughness determination, Langmuir **17** (2001) 2097–2099
18.59 R. G. Horn, J. N. Israelachvili: Molecular organization and viscosity of a thin film of molten polymer between two surfaces as probed by force measurements, Macromolecules **21** (1988) 2836–2841
18.60 R. G. Horn, S. J. Hirz, G. Hadziioannou, C. W. Frank, J. M. Catala: A reevaluation of forces measured across thin polymer films: Nonequilibrium and pinning effects, J. Chem. Phys. **90** (1989) 6767–6774
18.61 O. I. Vinogradova, H.-J. Butt, G. E. Yakubov, F. Feuillebois: Dynamic effects on force measurements. I. Viscous drag on the atomic force microscope cantilever, Rev. Sci. Instrum. **72** (2001) 2330–2339
18.62 D. Leckband, J. Israelachvili: Intermolecular forces in biology, Quart. Rev. Biophys. **34** (2001) 105–267
18.63 E. Evans, D. Needham: Physical properties of surfactant bilayer membranes: Thermal transitions, elasticity, rigidity, cohesion, and colloidal interactions, J. Phys. Chem. **91** (1987) 4219–4228
18.64 E. Evans, D. Needham: Attraction between lipid bilayer membranes in concentrated solutions of nonadsorbing polymers: Comparison of mean-field theory with measurements of adhesion energy, Macromolecules **21** (1988) 1822–1831
18.65 S. E. Chesla, P. Selvaraj, C. Zhu: Measuring two-dimensional receptor-ligand binding kinetics by micropipette, Biophys. J. **75** (1998) 1553–1572
18.66 E. Evans, K. Ritchie, R. Merkel: Sensitive force technique to probe molecular adhesion and structural linkages at biological interfaces, Biophys. J. **68** (1995) 2580–2587
18.67 D. M. LeNeveu, R. P. Rand, V. A. Parsegian: Measurements of forces between lecithin bilayers, Nature **259** (1976) 601–603
18.68 A. Homola, A. A. Robertson: A compression method for measuring forces between colloidal particles, J. Colloid Interface Sci. **54** (1976) 286–297
18.69 V. A. Parsegian, N. Fuller, R. P. Rand: Measured work of deformation and repulsion of lecithin bilayers, Proc. Nat. Acad. Sci. USA **76** (1979) 2750–2754
18.70 R. P. Rand, V. A. Parsegian: Hydration forces between phospholipid bilayers, Biochim. Biophys. Acta **988** (1989) 351–376
18.71 S. Leikin, V. A. Parsegian, D. C. Rau, R. P. Rand: Hydration forces, Annu. Rev. Phys. Chem. **44** (1993) 369–395
18.72 S. Chu, J. E. Bjorkholm, A. Ashkin, A. Cable: Experimental observation of optically trapped atoms, Phys. Rev. Lett. **57** (1986) 314–317
18.73 A. Ashkin: Optical trapping and manipulation of neutral particles using lasers, Proc. Nat. Acad. Sci. USA **94** (1997) 4853–4860
18.74 K. Visscher, S. P. Gross, S. M. Block: Construction of multiple-beam optical traps with nanometer-resolution positioning sensing, IEEE J. Sel. Top. Quantum Electron. **2** (1996) 1066–1076
18.75 D. C. Prieve, N. A. Frej: Total internal reflection microscopy: A quantitative tool for the measurement of colloidal forces, Langmuir **6** (1990) 396–403
18.76 J. Rädler, E. Sackmann: On the measurement of weak repulsive and frictional colloidal forces by reflection interference contrast microscopy, Langmuir **8** (1992) 848–853
18.77 P. Bongrand, C. Capo, J.-L. Mege, A.-M. Benoliel: Use of hydrodynamic flows to study cell adhesion. In: *Physical Basis of Cell–Cell Adhesion*, ed. by P. Bongrand (CRC Press, Boca Raton 1988) pp. 125–156
18.78 G. Kaplanski, C. Farnarier, O. Tissot, A. Pierres, A.-M. Benoliel, A.-C. Alessi, S. Kaplanski, P. Bongrand: Granulocyte–endothelium initial adhesion: Analysis of transient binding events mediated by E-selectin in a laminar shear flow, Biophys. J. **64** (1993) 1922–1933
18.79 H. B. G. Casimir, D. Polder: The influence of retardation on the London–van der Waals forces, Phys. Rev. **73** (1948) 360–372
18.80 H. C. Hamaker: The London–van der Waals attraction between spherical particles, Physica **4** (1937) 1058–1072
18.81 E. M. Lifshitz: The theory of molecular attraction forces between solid bodies, Sov. Phys. JETP (English translation) **2** (1956) 73–83
18.82 I. E. Dzyaloshinskii, E. M. Lifshitz, L. P. Pitaevskii: The general theory of van der Waals forces, Adv. Phys. **10** (1961) 165–209
18.83 H. W. Fox, W. A. Zisman: The spreading of liquids on low-energy surfaces. III. Hydrocarbon surfaces, J. Colloid Sci. **7** (1952) 428–442

18.84 B. V. Derjaguin, V. P. Smilga: Electrostatic component of the rolling friction force moment, Wear **7** (1964) 270–281
18.85 R. G. Horn, D. T. Smith: Contact electrification and adhesion between dissimilar materials, Science **256** (1992) 362–364
18.86 R. Budakian, S. J. Putterman: Correlation between charge transfer and stick–slip friction at a metal–insulator interface, Phys. Rev. Lett. **85** (2000) 1000–1003
18.87 M. Grätzel: Photoelectrochemical cells, Nature **414** (2001) 338–344
18.88 R. M. German: *Sintering Theory and Practice* (Wiley, New York 1996)
18.89 R. Budakian, S. J. Putterman: Time scales for cold welding and the origins of stick–slip friction, Phys. Rev. B **65** (2002) 235429/1–5
18.90 U. Landman, W. D. Luedtke, N. A. Burnham, R. J. Colton: Atomistic mechanisms and dynamics of adhesion, nanoindentation, and fracture, Science **248** (1990) 454–461
18.91 U. Landman, W. D. Luedtke, E. M. Ringer: Molecular dynamics simulations of adhesive contact formation and friction, NATO Science Ser. E **220** (1992) 463–510
18.92 W. D. Luedtke, U. Landman: Solid and liquid junctions, Comput. Mater. Sci. **1** (1992) 1–24
18.93 U. Landman, W. D. Luedtke: Interfacial junctions and cavitation, MRS Bull. **18** (1993) 36–44
18.94 B. Bhushan, J. N. Israelachvili, U. Landman: Nanotribology: Friction, wear and lubrication at the atomic scale, Nature **374** (1995) 607–616
18.95 M. R. Sørensen, K. W. Jacobsen, P. Stoltze: Simulations of atomic-scale sliding friction, Phys. Rev. B **53** (1996) 2101–2113
18.96 A. Meurk, P. F. Luckham, L. Bergström: Direct measurement of repulsive and attractive van der Waals forces between inorganic materials, Langmuir **13** (1997) 3896–3899
18.97 E. J. W. Verwey, J. T. G. Overbeek: *Theory of the Stability of Lyophobic Colloids*, 1st edn. (Elsevier, Amsterdam 1948)
18.98 D. Y. C. Chan, R. M. Pashley, L. R. White: A simple algorithm for the calculation of the electrostatic repulsion between identical charged surfaces in electrolyte, J. Colloid Interface Sci. **77** (1980) 283–285
18.99 B. Derjaguin, L. Landau: Theory of the stability of strongly charged lyophobic sols and of the adhesion of strongly charged particles in solutions of electrolytes, Acta Physicochim. URSS **14** (1941) 633–662
18.100 D. Chan, T. W. Healy, L. R. White: Electrical double layer interactions under regulation by surface ionization equilibriums – dissimilar amphoteric surfaces, J. Chem. Soc. Faraday Trans. 1 **72** (1976) 2844–2865
18.101 G. S. Manning: Limiting laws and counterion condensation in polyelectrolyte solutions. I. Colligative properties, J. Chem. Phys. **51** (1969) 924–933
18.102 L. Guldbrand, V. Jönsson, H. Wennerström, P. Linse: Electrical double-layer forces: A Monte Carlo study, J. Chem. Phys. **80** (1984) 2221–2228
18.103 H. Wennerström, B. Jönsson, P. Linse: The cell model for polyelectrolyte systems. Exact statistical mechanical relations, Monte Carlo simulations, and the Poisson–Boltzmann approximation, J. Chem. Phys. **76** (1982) 4665–4670
18.104 J. Marra: Effects of counterion specificity on the interactions between quaternary ammonium surfactants in monolayers and bilayers, J. Phys. Chem. **90** (1986) 2145–2150
18.105 J. Marra: Direct measurement of the interaction between phosphatidylglycerol bilayers in aqueous-electrolyte solutions, Biophys. J. **50** (1986) 815–825
18.106 R. G. Horn, J. N. Israelachvili: Direct measurement of structural forces between two surfaces in a nonpolar liquid, J. Chem. Phys. **75** (1981) 1400–1411
18.107 I. K. Snook, W. van Megen: Solvation forces in simple dense fluids I, J. Chem. Phys. **72** (1980) 2907–2913
18.108 W. J. van Megen, I. K. Snook: Solvation forces in simple dense fluids II. Effect of chemical potential, J. Chem. Phys. **74** (1981) 1409–1411
18.109 R. Kjellander, S. Marcelja: Perturbation of hydrogen bonding in water near polar surfaces, Chem. Phys. Lett. **120** (1985) 393–396
18.110 P. Tarazona, L. Vicente: A model for the density oscillations in liquids between solid walls, Mol. Phys. **56** (1985) 557–572
18.111 D. Henderson, M. Lozada-Cassou: A simple theory for the force between spheres immersed in a fluid, J. Colloid Interface Sci. **114** (1986) 180–183
18.112 J. E. Curry, J. H. Cushman: Structure in confined fluids: Phase separation of binary simple liquid mixtures, Tribol. Lett. **4** (1998) 129–136
18.113 M. Schoen, T. Gruhn, D. J. Diestler: Solvation forces in thin films confined between macroscopically curved substrates, J. Chem. Phys. **109** (1998) 301–311
18.114 F. Porcheron, B. Rousseau, M. Schoen, A. H. Fuchs: Structure and solvation forces in confined alkane films, Phys. Chem. Chem. Phys. **3** (2001) 1155–1159
18.115 H. K. Christenson, D. W. R. Gruen, R. G. Horn, J. N. Israelachvili: Structuring in liquid alkanes between solid surfaces: Force measurements and mean-field theory, J. Chem. Phys. **87** (1987) 1834–1841
18.116 M. L. Gee, J. N. Israelachvili: Interactions of surfactant monolayers across hydrocarbon liquids, J. Chem. Soc. Faraday Trans. **86** (1990) 4049–4058
18.117 J. N. Israelachvili, S. J. Kott, M. L. Gee, T. A. Witten: Forces between mica surfaces across hydrocarbon liquids: Effects of branching and polydispersity, Macromolecules **22** (1989) 4247–4253

18.118 H. K. Christenson: Forces between solid surfaces in a binary mixture of non-polar liquids, Chem. Phys. Lett. **118** (1985) 455–458
18.119 H. K. Christenson, R. G. Horn: Solvation forces measured in non-aqueous liquids, Chem. Scr. **25** (1985) 37–41
18.120 J. Israelachvili: Solvation forces and liquid structure, as probed by direct force measurements, Acc. Chem. Res. **20** (1987) 415–421
18.121 H. K. Christenson: Non-DLVO forces between surfaces – solvation, hydration and capillary effects, J. Disp. Sci. Technol. **9** (1988) 171–206
18.122 L. J. D. Frink, F. van Swol: Solvation forces between rough surfaces, J. Chem. Phys. **108** (1998) 5588–5598
18.123 J. Gao, W. D. Luedtke, U. Landman: Structures, solvation forces and shear of molecular films in a rough nano-confinement, Tribol. Lett. **9** (2000) 3–13
18.124 H. E. Stanley, J. Teixeira: Interpretation of the unusual behavior of H_2O and D_2O at low temperatures: Tests of a percolation model, J. Chem. Phys. **73** (1980) 3404–3422
18.125 H. van Olphen: *An Introduction to Clay Colloid Chemistry*, 2nd edn. (Wiley, New York 1977) Chap. 10
18.126 U. Del Pennino, E. Mazzega, S. Valeri, A. Alietti, M. F. Brigatti, L. Poppi: Interlayer water and swelling properties of monoionic montmorillonites, J. Colloid Interface Sci. **84** (1981) 301–309
18.127 B. E. Viani, P. F. Low, C. B. Roth: Direct measurement of the relation between interlayer force and interlayer distance in the swelling of montmorillonite, J. Colloid Interface Sci. **96** (1983) 229–244
18.128 R. G. Horn: Surface forces and their action in ceramic materials, J. Am. Ceram. Soc. **73** (1990) 1117–1135
18.129 B. V. Velamakanni, J. C. Chang, F. F. Lange, D. S. Pearson: New method for efficient colloidal particle packing via modulation of repulsive lubricating hydration forces, Langmuir **6** (1990) 1323–1325
18.130 R. R. Lessard, S. A. Zieminski: Bubble coalescence and gas transfer in aqueous electrolytic solutions, Ind. Eng. Chem. Fundam. **10** (1971) 260–269
18.131 J. Israelachvili, R. Pashley: The hydrophobic interaction is long range, decaying exponentially with distance, Nature **300** (1982) 341–342
18.132 R. M. Pashley, P. M. McGuiggan, B. W. Ninham, D. F. Evans: Attractive forces between uncharged hydrophobic surfaces: Direct measurements in aqueous solutions, Science **229** (1985) 1088–1089
18.133 P. M. Claesson, C. E. Blom, P. C. Herder, B. W. Ninham: Interactions between water-stable hydrophobic Langmuir–Blodgett monolayers on mica, J. Colloid Interface Sci. **114** (1986) 234–242
18.134 Ya. I. Rabinovich, B. V. Derjaguin: Interaction of hydrophobized filaments in aqueous electrolyte solutions, Colloids Surf. **30** (1988) 243–251
18.135 J. L. Parker, D. L. Cho, P. M. Claesson: Plasma modification of mica: Forces between fluorocarbon surfaces in water and a nonpolar liquid, J. Phys. Chem. **93** (1989) 6121–6125
18.136 H. K. Christenson, J. Fang, B. W. Ninham, J. L. Parker: Effect of divalent electrolyte on the hydrophobic attraction, J. Phys. Chem. **94** (1990) 8004–8006
18.137 K. Kurihara, S. Kato, T. Kunitake: Very strong long range attractive forces between stable hydrophobic monolayers of a polymerized ammonium surfactant, Chem. Lett. (1990) 1555–1558
18.138 Y. H. Tsao, D. F. Evans, H. Wennerstrom: Long-range attractive force between hydrophobic surfaces observed by atomic force microscopy, Science **262** (1993) 547–550
18.139 Ya. I. Rabinovich, R.-H. Yoon: Use of atomic force microscope for the measurements of hydrophobic forces between silanated silica plate and glass sphere, Langmuir **10** (1994) 1903–1909
18.140 V. S. J. Craig, B. W. Ninham, R. M. Pashley: Study of the long-range hydrophobic attraction in concentrated salt solutions and its implications for electrostatic models, Langmuir **14** (1998) 3326–3332
18.141 P. Kékicheff, O. Spalla: Long-range electrostatic attraction between similar, charge-neutral walls, Phys. Rev. Lett. **75** (1995) 1851–1854
18.142 H. K. Christenson, P. M. Claesson: Direct measurements of the force between hydrophobic surfaces in water, Adv. Colloid Interface Sci. **91** (2001) 391–436
18.143 P. Attard: Nanobubbles and the hydrophobic attraction, Adv. Colloid Interface Sci. **104** (2003) 75–91
18.144 M. Hato: Attractive forces between surfaces of controlled "hydrophobicity" across water: A possible range of "hydrophobic interactions" between macroscopic hydrophobic surfaces across water, J. Phys. Chem. **100** (1996) 18530–18538
18.145 H. K. Christenson, P. M. Claesson, J. Berg, P. C. Herder: Forces between fluorocarbon surfactant monolayers: Salt effects on the hydrophobic interaction, J. Phys. Chem. **93** (1989) 1472–1478
18.146 N. I. Christou, J. S. Whitehouse, D. Nicholson, N. G. Parsonage: A Monte Carlo study of fluid water in contact with structureless walls, Faraday Symp. Chem. Soc. **16** (1981) 139–149
18.147 B. Jönsson: Monte Carlo simulations of liquid water between two rigid walls, Chem. Phys. Lett. **82** (1981) 520–525
18.148 S. Marcelja, D. J. Mitchell, B. W. Ninham, M. J. Sculley: Role of solvent structure in solution theory, J. Chem. Soc. Faraday Trans. II **73** (1977) 630–648
18.149 D. W. R. Gruen, S. Marcelja: Spatially varying polarization in water: A model for the electric double layer and the hydration force, J. Chem. Soc. Faraday Trans. 2 **79** (1983) 225–242

18.150 B. Jönsson, H. Wennerström: Image-charge forces in phospholipid bilayer systems, J. Chem. Soc. Faraday Trans. 2 **79** (1983) 19–35

18.151 D. Schiby, E. Ruckenstein: The role of the polarization layers in hydration forces, Chem. Phys. Lett. **95** (1983) 435–438

18.152 A. Luzar, D. Bratko, L. Blum: Monte Carlo simulation of hydrophobic interaction, J. Chem. Phys. **86** (1987) 2955–2959

18.153 P. Attard, M.T. Batchelor: A mechanism for the hydration force demonstrated in a model system, Chem. Phys. Lett. **149** (1988) 206–211

18.154 K. Leung, A. Luzar: Dynamics of capillary evaporation. II. Free energy barriers, J. Chem. Phys. **113** (2000) 5845–5852

18.155 D. Bratko, R. A. Curtis, H. W. Blanch, J. M. Prausnitz: Interaction between hydrophobic surfaces with metastable intervening liquid, J. Chem. Phys. **115** (2001) 3873–3877

18.156 P. G. de Gennes: Polymers at an interface. 2. Interaction between two plates carrying adsorbed polymer layers, Macromolecules **15** (1982) 492–500

18.157 J. M. H. M. Scheutjens, G. J. Fleer: Interaction between two adsorbed polymer layers, Macromolecules **18** (1985) 1882–1900

18.158 E. A. Evans: Force between surfaces that confine a polymer solution: Derivation from self-consistent field theories, Macromolecules **22** (1989) 2277–2286

18.159 H. J. Ploehn: Compression of polymer interphases, Macromolecules **27** (1994) 1627–1636

18.160 S. Asakura, F. Oosawa: Interaction between particles suspended in solutions of macromolecules, J. Polym. Sci. **33** (1958) 183–192

18.161 J. F. Joanny, L. Leibler, P. G. de Gennes: Effects of polymer solutions on colloid stability, J. Polym. Sci. Polym. Phys. **17** (1979) 1073–1084

18.162 B. Vincent, P. F. Luckham, F. A. Waite: The effect of free polymer on the stability of sterically stabilized dispersions, J. Colloid Interface Sci. **73** (1980) 508–521

18.163 R. I. Feigin, D. H. Napper: Stabilization of colloids by free polymer, J. Colloid Interface Sci. **74** (1980) 567–571

18.164 P. G. de Gennes: Polymer solutions near an interface. 1. Adsorption and depletion layers, Macromolecules **14** (1981) 1637–1644

18.165 P. G. de Gennes: Polymers at an interface; a simplified view, Adv. Colloid Interface Sci. **27** (1987) 189–209

18.166 S. Alexander: Adsorption of chain molecules with a polar head. A scaling description, J. Phys. (France) **38** (1977) 983–987

18.167 P. G. de Gennes: Conformations of polymers attached to an interface, Macromolecules **13** (1980) 1069–1075

18.168 S. T. Milner, T. A. Witten, M. E. Cates: Theory of the grafted polymer brush, Macromolecules **21** (1988) 2610–2619

18.169 S. T. Milner, T. A. Witten, M. E. Cates: Effects of polydispersity in the end-grafted polymer brush, Macromolecules **22** (1989) 853–861

18.170 E. B. Zhulina, O. V. Borisov, V. A. Priamitsyn: Theory of steric stabilization of colloid dispersions by grafted polymers, J. Colloid Interface Sci. **137** (1990) 495–511

18.171 H. J. Taunton, C. Toprakcioglu, L. J. Fetters, J. Klein: Interactions between surfaces bearing end-adsorbed chains in a good solvent, Macromolecules **23** (1990) 571–580

18.172 J. Klein, P. Luckham: Forces between two adsorbed poly(ethylene oxide) layers immersed in a good aqueous solvent, Nature **300** (1982) 429–431

18.173 J. Klein, P. F. Luckham: Long-range attractive forces between two mica surfaces in an aqueous polymer solution, Nature **308** (1984) 836–837

18.174 P. F. Luckham, J. Klein: Forces between mica surfaces bearing adsorbed homopolymers in good solvents, J. Chem. Soc. Faraday Trans. **86** (1990) 1363–1368

18.175 J. Klein, E. Kumacheva, D. Mahalu, D. Perahia, L. J. Fetters: Reduction of frictional forces between solid surfaces bearing polymer brushes, Nature **370** (1994) 634–636

18.176 J. N. Israelachvili, H. Wennerström: Hydration or steric forces between amphiphilic surfaces?, Langmuir **6** (1990) 873–876

18.177 J. N. Israelachvili, H. Wennerström: Entropic forces between amphiphilic surfaces in liquids, J. Phys. Chem. **96** (1992) 520–531

18.178 M. K. Granfeldt, S. J. Miklavic: A simulation study of flexible zwitterionic monolayers. Interlayer interaction and headgroup conformation, J. Phys. Chem. **95** (1991) 6351–6360

18.179 L. R. Fisher, J. N. Israelachvili: Direct measurements of the effect of meniscus forces on adhesion: A study of the applicability of macroscopic thermodynamics to microscopic liquid interfaces, Colloids Surf. **3** (1981) 303–319

18.180 H. K. Christenson: Adhesion between surfaces in unsaturated vapors – a reexamination of the influence of meniscus curvature and surface forces, J. Colloid Interface Sci. **121** (1988) 170–178

18.181 R. G. Horn, J. N. Israelachvili, F. Pribac: Measurement of the deformation and adhesion of solids in contact, J. Colloid Interface Sci. **115** (1987) 480–492

18.182 H. Hertz: Über die Berührung fester elastischer Körper, J. Reine Angew. Math. **92** (1881) 156–171

18.183 H. M. Pollock, D. Maugis, M. Barquins: The force of adhesion between solid surfaces in contact, Appl. Phys. Lett. **33** (1978) 798–799

18.184 B. V. Derjaguin, V. M. Muller, Yu. P. Toporov: Effect of contact deformations on the adhesion of particles, J. Colloid Interface Sci. **53** (1975) 314–326

18.185 V. M. Muller, V. S. Yushchenko, B. V. Derjaguin: On the influence of molecular forces on the deforma-

tion of an elastic sphere and its sticking to a rigid plane, J. Colloid Interface Sci. **77** (1980) 91–101
18.186 V. M. Muller, B. V. Derjaguin, Y. P. Toporov: On 2 methods of calculation of the force of sticking of an elastic sphere to a rigid plane, Colloids Surf. **7** (1983) 251–259
18.187 D. Maugis: Adhesion of spheres: The JKR–DMT transition using a Dugdale model, J. Colloid Interface Sci. **150** (1992) 243–269
18.188 V. Mangipudi, M. Tirrell, A. V. Pocius: Direct measurement of molecular level adhesion between poly(ethylene terephthalate) and polyethylene films: Determination of surface and interfacial energies, J. Adh. Sci. Technol. **8** (1994) 1251–1270
18.189 H. K. Christenson: Surface deformations in direct force measurements, Langmuir **12** (1996) 1404–1405
18.190 M. Barquins, D. Maugis: Fracture mechanics and the adherence of viscoelastic bodies, J. Phys. D: Appl Phys. **11** (1978) 1989–2023
18.191 J. A. Greenwood, J. B. P. Williamson: Contact of nominally flat surfaces, Proc. R. Soc. London A **295** (1966) 300–319
18.192 B. N. J. Persson: Elastoplastic contact between randomly rough surfaces, Phys. Rev. Lett. **87** (2001) 116101/1–4
18.193 K. N. G. Fuller, D. Tabor: The effect of surface roughness on the adhesion of elastic solids, Proc. R. Soc. London A **345** (1975) 327–342
18.194 D. Maugis: On the contact and adhesion of rough surfaces, J. Adh. Sci. Technol. **10** (1996) 161–175
18.195 B. N. J. Persson, E. Tosatti: The effect of surface roughness on the adhesion of elastic solids, J. Chem. Phys. **115** (2001) 5597–5610
18.196 P. M. McGuiggan, J. N. Israelachvili: Adhesion and short-range forces between surfaces. Part II: Effects of surface lattice mismatch, J. Mater. Res. **5** (1990) 2232–2243
18.197 P. M. McGuiggan, J. Israelachvili: Measurements of the effects of angular lattice mismatch on the adhesion energy between two mica surfaces in water, Mat. Res. Soc. Symp. Proc. **138** (1989) 349–360
18.198 C. L. Rhykerd, Jr., M. Schoen, D. J. Diestler, J. H. Cushman: Epitaxy in simple classical fluids in micropores and near-solid surfaces, Nature **330** (1987) 461–463
18.199 M. Schoen, D. J. Diestler, J. H. Cushman: Fluids in micropores. I. Structure of a simple classical fluid in a slit-pore, J. Chem. Phys. **87** (1987) 5464–5476
18.200 M. Schoen, C. L. Rhykerd, Jr., D. J. Diestler, J. H. Cushman: Shear forces in molecularly thin films, Science **245** (1989) 1223–1225
18.201 P. A. Thompson, M. O. Robbins: Origin of stick–slip motion in boundary lubrication, Science **250** (1990) 792–794
18.202 K. K. Han, J. H. Cushman, D. J. Diestler: Grand canonical Monte Carlo simulations of a Stockmayer fluid in a slit micropore, Mol. Phys. **79** (1993) 537–545
18.203 M. Ruths, S. Granick: Influence of alignment of crystalline confining surfaces on static forces and shear in a liquid crystal, 4′-*n*-pentyl-4-cyanobiphenyl (5CB), Langmuir **16** (2000) 8368–8376
18.204 A. D. Berman: Dynamics of molecules at surfaces. Ph.D. Thesis (Univ. of California, Santa Barbara 1996)
18.205 E. Barthel, S. Roux: Velocity dependent adherence: An analytical approach for the JKR and DMT models, Langmuir **16** (2000) 8134–8138
18.206 M. Ruths, S. Granick: Rate-dependent adhesion between polymer and surfactant monolayers on elastic substrates, Langmuir **14** (1998) 1804–1814
18.207 H. Yoshizawa, Y. L. Chen, J. Israelachvili: Fundamental mechanisms of interfacial friction. 1: Relation between adhesion and friction, J. Phys. Chem. **97** (1993) 4128–4140
18.208 N. Maeda, N. Chen, M. Tirrell, J. N. Israelachvili: Adhesion and friction mechanisms of polymer-on-polymer surfaces, Science **297** (2002) 379–382
18.209 F. P. Bowden, D. Tabor: *The Friction and Lubrication of Solids* (Clarendon, London 1971)
18.210 J. A. Greenwood, K. L. Johnson: The mechanics of adhesion of viscoelastic solids, Phil. Mag. A **43** (1981) 697–711
18.211 D. Maugis: Subcritical crack growth, surface energy, fracture toughness, stick–slip and embrittlement, J. Mater. Sci. **20** (1985) 3041–3073
18.212 F. Michel, M. E. R. Shanahan: Kinetics of the JKR experiment, C. R. Acad. Sci. II (Paris) **310** (1990) 17–20
18.213 C. A. Miller, P. Neogi: *Interfacial Phenomena: Equilibrium and Dynamic Effects* (Dekker, New York 1985)
18.214 J. Israelachvili, A. Berman: Irreversibility, energy dissipation, and time effects in intermolecular and surface interactions, Israel J. Chem. **35** (1995) 85–91
18.215 A. N. Gent, A. J. Kinloch: Adhesion of viscoelastic materials to rigid substrates. III. Energy criterion for failure, J. Polym. Sci. A-2 **9** (1971) 659–668
18.216 A. N. Gent: Adhesion and strength of viscoelastic solids. Is there a relationship between adhesion and bulk properties?, Langmuir **12** (1996) 4492–4496
18.217 H. R. Brown: The adhesion between polymers, Annu. Rev. Mater. Sci. **21** (1991) 463–489
18.218 M. Deruelle, M. Tirrell, Y. Marciano, H. Hervet, L. Léger: Adhesion energy between polymer networks and solid surfaces modified by polymer attachment, Faraday Discuss. **98** (1995) 55–65
18.219 S. Granick: Motions and relaxations of confined liquids, Science **253** (1991) 1374–1379
18.220 H. W. Hu, S. Granick: Viscoelastic dynamics of confined polymer melts, Science **258** (1992) 1339–1342
18.221 M. L. Gee, P. M. McGuiggan, J. N. Israelachvili, A. M. Homola: Liquid to solidlike transitions of

molecularly thin films under shear, J. Chem. Phys. **93** (1990) 1895–1906
18.222 J. Van Alsten, S. Granick: The origin of static friction in ultrathin liquid films, Langmuir **6** (1990) 876–880
18.223 H.-W. Hu, G. A. Carson, S. Granick: Relaxation time of confined liquids under shear, Phys. Rev. Lett. **66** (1991) 2758–2761
18.224 J. Israelachvili, M. Gee, P. McGuiggan, P. Thompson, M. Robbins: Melting–freezing transitions in molecularly thin liquid films during shear, Fall Meeting of the Mater. Res. Soc., Boston, MA. 1990, ed. by J. M. Drake, J. Klafter, R. Kopelman (MRS Publications, Pittsburgh, PA1990) 3–6
18.225 J. Israelachvili, P. McGuiggan, M. Gee, A. Homola, M. Robbins, P. Thompson: Liquid dynamics in molecularly thin films, J. Phys.: Condens. Matter **2** (1990) SA89–SA98
18.226 J. Klein, E. Kumacheva: Confinement-induced phase transitions in simple liquids, Science **269** (1995) 816–819
18.227 A. L. Demirel, S. Granick: Glasslike transition of a confined simple fluid, Phys. Rev. Lett. **77** (1996) 2261–2264
18.228 D. Dowson: *History of Tribology*, 2nd edn. (Professional Engineering Publishing, London 1998)
18.229 D. Tabor: The role of surface and intermolecular forces in thin film lubrication, Tribol. Ser. **7** (1982) 651–682
18.230 M. J. Sutcliffe, S. R. Taylor, A. Cameron: Molecular asperity theory of boundary friction, Wear **51** (1978) 181–192
18.231 G. M. McClelland: Friction at weakly interacting interfaces. In: *Adhesion and Friction*, ed. by M. Grunze, H. J. Kreuzer (Springer, Berlin, Heidelberg 1989) pp. 1–16
18.232 J. N. Israelachvili, Y.-L. Chen, H. Yoshizawa: Relationship between adhesion and friction forces, J. Adh. Sci. Technol. **8** (1994) 1231–1249
18.233 D. H. Buckley: The metal-to-metal interface and its effect on adhesion and friction, J. Colloid Interface Sci. **58** (1977) 36–53
18.234 V. Zaloj, M. Urbakh, J. Klafter: Modifying friction by manipulating normal response to lateral motion, Phys. Rev. Lett. **82** (1999) 4823–4826
18.235 A. Dhinojwala, S. C. Bae, S. Granick: Shear-induced dilation of confined liquid films, Tribol. Lett. **9** (2000) 55–62
18.236 L. M. Qian, G. Luengo, E. Perez: Thermally activated lubrication with alkanes: The effect of chain length, Europhys. Lett. **61** (2003) 268–274
18.237 B. J. Briscoe, D. C. B. Evans, D. Tabor: The influence of contact pressure and saponification on the sliding behavior of steric acid monolayers, J. Colloid Interface Sci. **61** (1977) 9–13
18.238 A. Berman, J. Israelachvili: Control and minimization of friction via surface modification, NATO ASI Ser. E: Appl. Sci. **330** (1997) 317–329
18.239 M. Urbakh, L. Daikhin, J. Klafter: Dynamics of confined liquids under shear, Phys. Rev. E **51** (1995) 2137–2141
18.240 M. G. Rozman, M. Urbakh, J. Klafter: Origin of stick-slip motion in a driven two-wave potential, Phys. Rev. E **54** (1996) 6485–6494
18.241 M. G. Rozman, M. Urbakh, J. Klafter: Stick–slip dynamics as a probe of frictional forces, Europhys. Lett. **39** (1997) 183–188
18.242 B. V. Derjaguin: Molekulartheorie der äußeren Reibung, Z. Physik **88** (1934) 661–675
18.243 B. V. Derjaguin: Mechanical properties of the boundary lubrication layer, Wear **128** (1988) 19–27
18.244 B. J. Briscoe, D. C. B. Evans: The shear properties of Langmuir–Blodgett layers, Proc. R. Soc. London A **380** (1982) 389–407
18.245 A. Berman, C. Drummond, J. Israelachvili: Amontons' law at the molecular level, Tribol. Lett. **4** (1998) 95–101
18.246 P. F. Luckham, S. Manimaaran: Investigating adsorbed polymer layer behaviour using dynamic surface force apparatuses – a review, Adv. Colloid Interface Sci. **73** (1997) 1–46
18.247 A. M. Homola, J. N. Israelachvili, P. M. McGuiggan, M. L. Gee: Fundamental experimental studies in tribology: The transition from "interfacial" friction of undamaged molecularly smooth surfaces to "normal" friction with wear, Wear **136** (1990) 65–83
18.248 S. Yamada, J. Israelachvili: Friction and adhesion hysteresis of fluorocarbon surfactant monolayer-coated surfaces measured with the surface forces apparatus, J. Phys. Chem. B **102** (1998) 234–244
18.249 G. Luengo, S. E. Campbell, V. I. Srdanov, F. Wudl, J. N. Israelachvili: Direct measurement of the adhesion and friction of smooth C_{60} surfaces, Chem. Mater. **9** (1997) 1166–1171
18.250 L. Rapoport, Y. Bilik, Y. Feldman, M. Homyonfer, S. R. Cohen, R. Tenne: Hollow nanoparticles of WS_2 as potential solid-state lubricants, Nature **387** (1997) 791–793
18.251 J. Israelachvili, Y.-L. Chen, H. Yoshizawa: Relationship between adhesion and friction forces. In: *Fundamentals of Adhesion and Interfaces*, ed. by D. S. Rimai, L. P. DeMejo, K. L. Mittal (VSP, Utrecht, The Netherlands 1995) pp. 261–279
18.252 P. Berthoud, T. Baumberger, C. G'Sell, J. M. Hiver: Physical analysis of the state- and rate-dependent friction law: Static friction, Phys. Rev. B **59** (1999) 14313–14327
18.253 A. Berman, S. Steinberg, S. Campbell, A. Ulman, J. Israelachvili: Controlled microtribology of a metal oxide surface, Tribol. Lett. **4** (1998) 43–48

18.254 D. Y. C. Chan, R. G. Horn: The drainage of thin liquid films between solid surfaces, J. Chem. Phys. **83** (1985) 5311–5324

18.255 J. N. Israelachvili, S. J. Kott: Shear properties and structure of simple liquids in molecularly thin films: The transition from bulk (continuum) to molecular behavior with decreasing film thickness, J. Colloid Interface Sci. **129** (1989) 461–467

18.256 T. L. Kuhl, A. D. Berman, S. W. Hui, J. N. Israelachvili: Part 1: Direct measurement of depletion attraction and thin film viscosity between lipid bilayers in aqueous polyethylene glycol solutions, Macromolecules **31** (1998) 8250–8257

18.257 S. E. Campbell, G. Luengo, V. I. Srdanov, F. Wudl, J. N. Israelachvili: Very low viscosity at the solid–liquid interface induced by adsorbed C_{60} monolayers, Nature **382** (1996) 520–522

18.258 J. Klein, Y. Kamiyama, H. Yoshizawa, J. N. Israelachvili, G. H. Fredrickson, P. Pincus, L. J. Fetters: Lubrication forces between surfaces bearing polymer brushes, Macromolecules **26** (1993) 5552–5560

18.259 G. Luengo, J. Israelachvili, A. Dhinojwala, S. Granick: Generalized effects in confined fluids: New friction map for boundary lubrication, Wear **200** (1996) 328–335

18.260 E. Kumacheva, J. Klein: Simple liquids confined to molecularly thin layers. II. Shear and frictional behavior of solidified films, J. Chem. Phys. **108** (1998) 7010–7022

18.261 P. A. Thompson, G. S. Grest, M. O. Robbins: Phase transitions and universal dynamics in confined films, Phys. Rev. Lett. **68** (1992) 3448–3451

18.262 Y. Rabin, I. Hersht: Thin liquid layers in shear: Non-Newtonian effects, Physica A **200** (1993) 708–712

18.263 P. A. Thompson, M. O. Robbins, G. S. Grest: Structure and shear response in nanometer-thick films, Israel J. Chem. **35** (1995) 93–106

18.264 M. Urbakh, L. Daikhin, J. Klafter: Sheared liquids in the nanoscale range, J. Chem. Phys. **103** (1995) 10707–10713

18.265 A. Subbotin, A. Semenov, E. Manias, G. Hadziioannou, G. ten Brinke: Rheology of confined polymer melts under shear flow: Strong adsorption limit, Macromolecules **28** (1995) 1511–1515

18.266 A. Subbotin, A. Semenov, E. Manias, G. Hadziioannou, G. ten Brinke: Rheology of confined polymer melts under shear flow: Weak adsorption limit, Macromolecules **28** (1995) 3901–3903

18.267 J. Huh, A. Balazs: Behavior of confined telechelic chains under shear, J. Chem. Phys. **113** (2000) 2025–2031

18.268 C. Drummond, J. Elezgaray, P. Richetti: Behavior of adhesive boundary lubricated surfaces under shear: A new dynamic transition, Europhys. Lett. **58** (2002) 503–509

18.269 J. N. Israelachvili, P. M. McGuiggan, A. M. Homola: Dynamic properties of molecularly thin liquid films, Science **240** (1988) 189–191

18.270 A. M. Homola, H. V. Nguyen, G. Hadziioannou: Influence of monomer architecture on the shear properties of molecularly thin polymer melts, J. Chem. Phys. **94** (1991) 2346–2351

18.271 M. Schoen, S. Hess, D. J. Diestler: Rheological properties of confined thin films, Phys. Rev. E **52** (1995) 2587–2602

18.272 G. M. McClelland, S. R. Cohen: *Chemistry and Physics of Solid Surfaces VIII* (Springer, Berlin, Heidelberg 1990) pp. 419–445

18.273 M. O. Robbins, P. A. Thompson: Critical velocity of stick–slip motion, Science **253** (1991) 916

18.274 G. He, M. Müser, M. Robbins: Adsorbed layers and the origin of static friction, Science **284** (1999) 1650–1652

18.275 C. Drummond, J. Israelachvili: Dynamic phase transitions in confined lubricant fluids under shear, Phys. Rev. E. **63** (2001) 041506/1–11

18.276 H. Yoshizawa, J. Israelachvili: Fundamental mechanisms of interfacial friction. 2: Stick–slip friction of spherical and chain molecules, J. Phys. Chem. **97** (1993) 11300–11313

18.277 J. D. Ferry: *Viscoelastic Properties of Polymers*, 3rd edn. (Wiley, New York 1980)

18.278 A. Ruina: Slip instability and state variable friction laws, J. Geophys. Res. **88** (1983) 10359–10370

18.279 T. Baumberger, P. Berthoud, C. Caroli: Physical analysis of the state- and rate-dependent friction law. II. Dynamic friction, Phys. Rev. B **60** (1999) 3928–3939

18.280 J. Israelachvili, S. Giasson, T. Kuhl, C. Drummond, A. Berman, G. Luengo, J.-M. Pan, M. Heuberger, W. Ducker, N. Alcantar: Some fundamental differences in the adhesion and friction of rough versus smooth surfaces, Tribol. Ser. **38** (2000) 3–12

18.281 C. Drummond, J. Israelachvili: Dynamic behavior of confined branched hydrocarbon lubricant fluids under shear, Macromolecules **33** (2000) 4910–4920

18.282 E. Rabinowicz: *Friction and Wear of Materials*, 2nd edn. (Wiley, New York 1995) Chap. 4

18.283 J. Peachey, J. Van Alsten, S. Granick: Design of an apparatus to measure the shear response of ultrathin liquid films, Rev. Sci. Instrum. **62** (1991) 463–473

18.284 E. Rabinowicz: The intrinsic variables affecting the stick–slip process, Proc. Phys. Soc. **71** (1958) 668–675

18.285 T. Baumberger, F. Heslot, B. Perrin: Crossover from creep to inertial motion in friction dynamics, Nature **367** (1994) 544–546

18.286 F. Heslot, T. Baumberger, B. Perrin, B. Caroli, C. Caroli: Creep, stick–slip, and dry-friction dynamics: Experiments and a heuristic model, Phys. Rev. E **49** (1994) 4973–4988

18.287 J. Sampson, F. Morgan, D. Reed, M. Muskat: Friction behavior during the slip portion of the stick–slip process, J. Appl. Phys. **14** (1943) 689–700

18.288 F. Heymann, E. Rabinowicz, B. Rightmire: Friction apparatus for very low-speed sliding studies, Rev. Sci. Instrum. **26** (1954) 56–58

18.289 J. H. Dieterich: Time-dependent friction and the mechanics of stick–slip, Pure Appl. Geophys. **116** (1978) 790–806

18.290 J. H. Dieterich: Modeling of rock friction. 1. Experimental results and constitutive equations, J. Geophys. Res. **84** (1979) 2162–2168

18.291 G. A. Tomlinson: A molecular theory of friction, Phil. Mag. **7** (1929) 905–939

18.292 J. M. Carlson, J. S. Langer: Mechanical model of an earthquake fault, Phys. Rev. A **40** (1989) 6470–6484

18.293 B. N. J. Persson: Theory of friction: The role of elasticity in boundary lubrication, Phys. Rev. B **50** (1994) 4771–4786

18.294 S. Nasuno, A. Kudrolli, J. P. Gollub: Friction in granular layers: Hysteresis and precursors, Phys. Rev. Lett. **79** (1997) 949–952

18.295 P. Bordarier, M. Schoen, A. Fuchs: Stick–slip phase transitions in confined solidlike films from an equilibrium perspective, Phys. Rev. E **57** (1998) 1621–1635

18.296 J. M. Carlson, A. A. Batista: Constitutive relation for the friction between lubricated surfaces, Phys. Rev. E **53** (1996) 4153–4165

18.297 A. D. Berman, W. A. Ducker, J. N. Israelachvili: Origin and characterization of different stick–slip friction mechanisms, Langmuir **12** (1996) 4559–4563

18.298 A. D. Berman, W. A. Ducker, J. N. Israelachvili: Experimental and theoretical investigations of stick–slip friction mechanisms, NATO ASI Ser. E: Appl. Sci. **311** (1996) 51–67

18.299 K G. McLaren, D. Tabor: Viscoelastic properties and the friction of solids. Friction of polymers and influence of speed and temperature, Nature **197** (1963) 856–858

18.300 K. A. Grosch: Viscoelastic properties and friction of solids. Relation between friction and viscoelastic properties of rubber, Nature **197** (1963) 858–859

18.301 J. Gao, W. D. Luedtke, U. Landman: Friction control in thin-film lubrication, J. Phys. Chem. B **102** (1998) 5033–5037

18.302 M. Heuberger, C. Drummond, J. Israelachvili: Coupling of normal and transverse motions during frictional sliding, J. Phys. Chem. B **102** (1998) 5038–5041

18.303 L. Bureau, T. Baumberger, C. Caroli: Shear response of a frictional interface to a normal load modulation, Phys. Rev. E **62** (2000) 6810–6820

18.304 J. P. Gao, W. D. Luedtke, U. Landman: Structure and solvation forces in confined films: Linear and branched alkanes, J. Chem. Phys. **106** (1997) 4309–4318

18.305 J. Gao, W. D. Luedtke, U. Landman: Layering transitions and dynamics of confined liquid films, Phys. Rev. Lett. **79** (1997) 705–708

18.306 J. Warnock, D. D. Awschalom, M. W. Shafer: Orientational behavior of molecular liquids in restricted geometries, Phys. Rev. B **34** (1986) 475–478

18.307 D. D. Awschalom, J. Warnock: Supercooled liquids and solids in porous glass, Phys. Rev. B **35** (1987) 6779–6785

18.308 M. Hirano, K. Shinjo, R. Kaneko, Y. Murata: Anisotropy of frictional forces in muscovite mica, Phys. Rev. Lett. **67** (1991) 2642–2645

18.309 T. Gyalog, H. Thomas: Friction between atomically flat surfaces, Europhys. Lett. **37** (1997) 195–200

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

19. Scanning Probe Studies of Nanoscale Adhesion Between Solids in the Presence of Liquids and Monolayer Films

Adhesion between solids is a ubiquitous phenomenon whose importance is magnified at the micrometer and nanometer scales, where the surface-to-volume ratio diverges as we approach the single atom.

Numerous techniques for measuring adhesion at the atomic scale have been developed. Yet significant limitations exist. Instrumental improvements and reliable quantification are still needed.

Recent studies have highlighted the unique and important effect of liquid capillaries, particularly water, at the nanometer scale. The results demonstrate that macroscopic considerations of classic meniscus theory must be, at the very least, corrected to take into account new scaling and geometric relationships unique to the nanometer scale. More generally, a molecular-scale description of wetting and capillary condensation as it applies to nanometer-scale interfaces is clearly desirable, but remains an important challenge.

The measurement of adhesion between self-assembled monolayers has proven to be a reliable means for probing the influence of surface chemistry and local environment on adhesion. To date, however, few systems have been investigated quantitatively in detail. The molecular origins of adhesion down to the single bond level remain to be fully investigated. The most recent studies illustrate that although new information about adhesion in these systems has been revealed, further enhancements of current techniques, as well as the development of new methodologies, coupled with accurate theoretical modeling, are required to adequately tackle these complex measurements.

19.1 **The Importance of Adhesion at the Nanoscale** 605
19.2 **Techniques for Measuring Adhesion** 606
19.3 **Calibration of Forces, Displacements, and Tips** 610
  19.3.1 Force Calibration 610
  19.3.2 Probe Tip Characterization............ 611
  19.3.3 Displacement Calibration 612
19.4 **The Effect of Liquid Capillaries on Adhesion**....................................... 612
  19.4.1 Theoretical Background 612
  19.4.2 Experimental and Theoretical Studies of Capillary Formation with Scanning Probes 614
  19.4.3 Future Directions......................... 618
19.5 **Self-Assembled Monolayers** 618
  19.5.1 Adhesion at SAM Interfaces........... 618
  19.5.2 Chemical Force Microscopy: General Methodology 619
  19.5.3 Adhesion at SAM-Modified Surfaces in Liquids.................................. 620
  19.5.4 Impact of Intra- and Inter-Chain Interactions on Adhesion 621
  19.5.5 Adhesion at the Single-Bond Level. 622
  19.5.6 Future Directions......................... 623
19.6 **Concluding Remarks** 624
References 624

19.1 The Importance of Adhesion at the Nanoscale

The mutual attraction and bonding of two surfaces, which can occur with or without an intervening medium, is a commonly observed phenomenon with far-reaching manifestations and applications in society. The adherence between a raindrop and a window pane, the climbing of a gecko up a vine, the sticking of multiple adhesive note pads to a professor's wall, the force required to separate hook-and-eye (Velcro^{TM}) strips, the building

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

of a sand castle, and the book page turned by a wetted finger are all examples in which adhesion is important. Within the complexity of these examples and others lies a central theme: The mechanical forces between a pair of materials can be fundamentally affected not just by the macroscopic or microscopic structure of the surfaces, but also by the interatomic and intermolecular forces between them.

Adhesion and intermolecular forces have been studied for many years dating back to ancient times [19.1], and active research continues today of topics as broad as insect and reptile locomotion [19.2], interactions between cells in the body [19.3], and the design of self-healing composites [19.4], to name a few. While adhesion is clearly of interest for a wide range of macroscopic applications, its importance becomes dominant at the micrometer and nanometer scales. This is primarily due to the dramatic increase in the surface-to-volume ratio of materials at these scales, an effect that renders friction and interfacial wear critical phenomena [19.5]. For example, the dominating effect of adhesion at this scale has affected the development of microelectromechanical systems (MEMS), in which interfacial forces can prevent devices from functioning properly, since the small flexible parts often emerge from the fabrication line stuck together. Studies of adhesion in MEMS are ongoing, and commercially deployed MEMS devices rely upon sophisticated surface treatments to reduce and control adhesion [19.6–8].

Detailed control of adhesion at the molecular level will be essential for the proposed design of the smaller nanoelectromechanical systems (NEMS). Much has been written about the possibilities for nanoscale machines, sensors, and actuators, etc. It is crucial to understand that a molecule is *all* surface, and, therefore, molecular and nanoscale devices cannot be properly designed, implemented, or characterized unless an understanding of atomic-scale adhesion is thoroughly presented, particularly if these devices are to involve any moving parts that will come into and out of contact with each other. Studying adhesion at the nanoscale is important for other reasons. The protruding asperities in most MEMS materials often have nanoscale dimensions, and, therefore, a complete understanding of adhesion in MEMS requires the investigation of the adhesive properties of the individual nanoscale asperities. In addition, the experimental study of adhesion at the nanoscale is required for the development of detailed atomic-scale models of adhesion. Such progress requires close collaboration between experiment and theory.

There has been significant progress in the experimental study of adhesion at the nanometer scale using scanning probe methods, but numerous challenges exist. A discussion of solid-solid adhesion without an intervening medium is provided in part B and C of this book. This chapter focuses on how adhesion is affected by the ubiquitous presence of water, and how it can be controlled through the application of self-assembled monolayer (SAM) coatings, again in the presence of a liquid medium. In addition, we discuss specific instrumental challenges that are inherent to adhesion measurements. We do not delve into the realm of atomic-scale modeling of adhesion, nor do we discuss the role of more complex coatings such as polymer brushes and blends. Rather, we will focus on critically evaluating the relevant experimental techniques and critically reviewing recent results from studies of water and SAM films, which are perhaps the two most commonly encountered media in nanoscale adhesion applications.

19.2 Techniques for Measuring Adhesion

The experimental study of adhesion at the nanoscale has experienced two renaisances in this century. The first occurred with the development of the surface forces apparatus (SFA) [19.9, 10], and the second with the later development of the AFM [19.11] and other related scanning force techniques.

SFA experiments have contributed profoundly to our understanding of adhesion. The SFA consists of a pair of atomically smooth surfaces, usually mica sheets, mounted on crossed cylinders that can be pressed together to form a controlled circular contact. The applied load, normal displacement, surface separation, contact area, and shear force (if applied) can all be controlled and/or measured [19.9, 12–14]. The SFA can be operated in air, a controlled environment, or under liquid conditions. The surfaces are often treated to attach molecules whose behavior under confinement can be studied. Alternately, the behavior of a confined fluid layer can be observed. The surface separation can be measured and controlled in the Ångstrom (Å) regime. The lateral resolution is limited to the range of several tens of micrometers. However, the true contact area between the interfaces can be directly measured, which is a key advantage since it allows an adhesive force to be converted to a force (or energy) per unit area (or per molecule), thus separating geometrical contributions to adhesion from chemical contributions. In this chapter, we will refer to relevant results in the context of the scanning probe experiments. As a very brief summary, some of the most important results pertaining to adhesion include: the observation of capillary effects on adhesion [19.15, 16], the presence of hysteresis in adhesion due to pressure-induced restructuring of the interface [19.17], and numerous studies of how interfacial chemistry (hydrophilicity, surface charge, specific chemical groups, etc.) affect adhesive forces [19.1, 18, 19].

AFM instrumentation is described in part B of this book. Key ways in which the AFM differs from the SFA are: (1) the lateral contact size is nm, not μm, due to the fact that the tip is usually < 100 nm in radius, and the contact area at low applied loads will be a fraction of this radius [19.20]; (2) the force resolution is as good as 10^{-10} N or better, as opposed to $\sim 10^{-6}$ N with the SFA; (3) the contact area is not directly observable, although it may be derived through other means; (4) the actual separation between the tip and sample are not directly observable, which is a key disadvantage; (5) the relative separation between the sample and the *cantilever* (not the tip) is controlled in the 0.1 nm range or better; (6) the measurement bandwidth is typically in the kHz regime, but can extend into the MHz regime depending on the data acquisition technique; (7) the operating environment includes ultrahigh vacuum (UHV) and cryogenic to elevated temperatures; (8) there is virtually no limit to the range of materials that can be probed by the AFM; and (9) half of the interface (the tip) is essentially unknown or uncontrolled, whereas with the SFA, both surfaces are well-defined, which is another key challenge for AFM that has yet to be consistently addressed.

The general setup of the AFM is as follows. A small sharp tip (with a radius typically between 10–100 nm) is attached to the end of a compliant cantilever (see Fig. 19.1). The tip is brought into close proximity with a sample surface in a fashion that is identical to STM tip–sample approach mechanisms. Forces acting between the AFM tip and the sample will result in deflections of the cantilever (Fig. 19.2). The cantilever bends vertically (i. e., toward the sample) in response to attractive and/or repulsive forces acting on the tip. The deflection of the cantilever from its equilibrium position is proportional to the normal load applied to the tip by the cantilever. Lateral forces result in a twisting of the cantilever from its equilibrium position. These measurements can be performed in a variety of environments: ambient air, controlled atmosphere, liquids [19.21], or UHV [19.22–24].



Fig. 19.1 Diagram of the AFM setup for the optical beam deflection method. The tip is in contact with a sample surface. A laser beam is focused on the back of the cantilever and reflects into a four-quadrant photodetector. Normal forces deflect the cantilever up or down, lateral forces twist the cantilever left and right. These deflections are simultaneously and independently measured by monitoring the deflection of the reflected laser beam

The simplest way (perhaps deceptively so) to measure adhesion with the AFM is through so-called force–displacement plots (also referred to in the literature as force curves and force–distance curves or plots). A force-displacement plot displays the vertical cantilever bending (i. e., the cantilever deflection, which can be calibrated to give the tip–sample interaction force) vs. lever–sample displacement. This displacement is measured between the sample and the rigidly held back end of the cantilever (as opposed to the front end with the tip, which will bend in response to interaction forces). This displacement is altered by varying the vertical position of the piezo tube, which, depending on the type of AFM, displaces the tip or the sample in the direction normal to the sample. Referring to Fig. 19.2a, the stages of acquisition of the force curve are as follows: (a) The lever and sample are initially far apart and no forces act. (b) As the lever is brought close to the sample, the tip senses attractive forces that cause the tip end of the lever to bend downward, thus signifying a negative (attractive) force. These forces may be of electrostatic, van der



Fig. 19.2 **(a)** A "force-displacement" curve displays the vertical cantilever deflection vs. lever–sample displacement. This displacement is measured between the sample and the rigidly held back end of the cantilever (as opposed to the front end with the tip that will bend in response to interaction forces). **(b)** The true tip–sample interaction as a function of tip–sample separation. **(c)** Tip–sample interaction energy, lever strain energy, and total energy as a function of tip–sample separation

Waals, or other origin. (c) At this point, the attractive force gradient (slope) of the tip-sample interaction force exceeds the spring constant k of the lever, and this instability causes the tip to snap into contact (d) with the sample. The lever-sample displacement can continue to be reduced and eventually crosses the force axis (e), which corresponds to zero externally applied load. As this tip is in repulsive contact with the sample, the front end of the lever is pushed further and further upward, and the force corresponds to the externally applied load. (f) The displacement direction is reversed at a point chosen by the user. As the lever-sample distance is reduced, the force becomes negative. Adhesion between the tip and sample maintains the contact, although there is now a net negative (tensile) load. Eventually the tip passes through the point of maximum adhesion (g), which is not distinguishable on this plot (see Fig. 19.2b). Finally, an unstable point is reached at which the cantilever stiffness exceeds the force gradient of the tip-sample interaction, and the tip snaps out of contact with the sample (h–i). The resulting force relaxation is usually called the pull-off force. Note that the forces and distances are not drawn to scale, and, in particular, the attractive part of the interaction is exaggerated beyond that which often occurs for inert, neutral surfaces.

The force-displacement curve can be measured at a single point, or a series of measurements can be carried out over an area of interest. The so-called adhesion mapping techniques allow for spatially resolved adhesion measurements to be correlated with other sample properties such as friction, chemical termination, and other types of material heterogeneity.

In order to properly derive adhesion measurements from the AFM, it is critical to understand the nature of the mechanical instability of both the snap-in and pull-off processes. The fundamental point to comprehend is that *the pull-off force is* not *the adhesive bond strength*. In other words, *it is not a direct measure of the actual adhesive forces that were acting between the tip and sample in the absence of applied load*. This important point is often overlooked or misunderstood, and so we discuss it here in some detail.

A cartoon of the interaction force (F_{ts}) between the tip and sample is sketched (not to any particular scale) as a function of the true tip-sample separation in Fig. 19.2b. Superimposed on this is the force-distance relation of the cantilever: a straight line with slope k (N/m), the cantilever stiffness (diagonal dashed lines). Points of instability are shown as gray dots, labels, and arrows, as opposed to stable points, shown as black dots, labels, and arrows. Snap-in occurs when the attractive force gradient $\mathrm{d}F_{\mathrm{ts}}/\mathrm{d}z$ just exceeds k, in other words, when the dashed line is tangent to the tip-sample force curve, as shown for point c. This instability is a direct consequence of Newton's 2^{nd} law and is explained further below. Similarly, the pull-off occurs during retraction when k finally just exceeds $\mathrm{d}F_{\mathrm{ts}}/\mathrm{d}z$, as shown for point h, where once again, the diagonal line is just tangent to the tip-sample force curve. By definition, since k is finite, this point *cannot* correspond to the point of maximum attractive force (or adhesive force), g. Thus, the force at which pull-off occurs is *not* precisely equal to the true adhesion force. The significance of this deviation is discussed below.

This can also be illustrated from an energetic perspective. In Fig. 19.2c, we show separately the tip-sample interaction energy, E_{ts}, as a function of tip-sample separation (top), followed by the quadratic elastic strain energy, E_{lever}, of the cantilever (middle) and the sum, E_{total}, of the two (bottom). As the lever-sample displacement is varied, the elastic energy curve is shifted to the appropriate position, which, for this example, is represented on the tip-sample separation axis. Far away from the sample, the system resides in a deep minimum, points a and b (not shown). As the tip-sample separation is reduced, this minimum becomes more and more shallow (evolving along the dashed arrow). At the snap-in point c, the minimum is eliminated, since the attractive energy of the tip-sample interaction has overwhelmed the energy minimum of the cantilever. Mathematically this is described as an inflection point, where:

$$\frac{\mathrm{d}^2 E_{\mathrm{tot}}}{\mathrm{d}z^2} = 0 \,.$$

Now,

$$E_{\mathrm{tot}} = E_{\mathrm{ts}} + E_{\mathrm{lever}} = E_{\mathrm{ts}} + \tfrac{1}{2}k(z - z_0)^2 \qquad (19.1)$$

$\therefore$ snap-in occurs when

$$\frac{\mathrm{d}^2 E_{\mathrm{ts}}}{\mathrm{d}z^2} = -\frac{\mathrm{d}F_{\mathrm{ts}}}{\mathrm{d}z} = -k \,.$$

This explains why the instability is described by the line of slope k being tangent to the tip-sample force curve, as shown in Fig. 19.2b. The system now rapidly finds the new minimum by following the gray arrow to point d, where a mechanical contact between the tip and sample is now formed.

Note that once the contact is formed, the tip and sample elastically deform, and so, strictly speaking, the tip-sample potential will be distinct from the potential shown before contact occurs. For simplicity, we have left out this change and instead have drawn the potential as a single-valued function. However, such changes in the energy landscape should be considered in a complete description of the problem [19.25].

Nevertheless, it will also hold true that upon retracting the tip from the surface, the stable minimum seen at e, f, and then g becomes more shallow, and eventually disappears as it is overwhelmed by the strain energy of the cantilever. Again, an inflection point is created when

$$\frac{\mathrm{d}^2 E_{\mathrm{attr}}}{\mathrm{d}z^2} = -k \,, \qquad (19.2)$$

in other words, when again

$$\frac{\mathrm{d}F_{\mathrm{ts}}}{\mathrm{d}z} = k \,. \qquad (19.3)$$

This second instability occurs at point h, the pull-off point. The system then follows the gray arrow to point i, whereby the tip is now out of contact with the sample.

If the spring is sufficiently compliant (low k), or the potential sufficiently stiff (large $\mathrm{d}F/\mathrm{d}z$ shortly past the minimum at g), then the pull-off force *does* nearly correspond to the attractive force minimum F_{min}. In other words, point h would occur very close to point g. But if the cantilever is somewhat stiff, or if the potential is rather compliant (which may be the case for organic, polymeric, biological, or liquid systems), then the pull-off force may differ substantially from F_{min}. For such cases, this distinction between pull-off force and true adhesion is important, and the limitations imposed by the AFM's intrinsic instabilities become apparent. Of course, if a cantilever is used whose stiffness exceeds the attractive force gradient at all points, one will avoid the instabilities. But since it is the deflection of the cantilever that is used to sense the force, one would have to trade force sensitivity for stability, which is usually an unsuitable compromise.

When a compliant spring or holder is used to manipulate a probe, as is the case for AFM, the technique is generally referred to as being "load-controlled", since the load can be prescribed, but the actual displacement of the probe with respect to the sample cannot (as illustrated by the jump in displacement that occurs during snap-in or pull-off).

In contrast, "displacement-controlled" techniques avoid this instability by effectively eliminating the compliance of the spring or holder. This has been carried out for decades in the mechanical testing community, and over the past 10 years, displacement-controlled scanning probe, have been developed. This is accomplished by displacing the tip by applying force to the tip itself. *Pethica* et al. [19.26,27] use a magnetic coating on the tip and external coils to apply forces to the tip. They refer to the instrument as a "force-controlled microscope". *Houston* et al. [19.28,29] control the force electrostatically and refer to the instrument as an "interfacial force microscope" (IFM). *Lieber* et al. use a variation on Pethica's method, whereby a magnetic coil is used to apply a force to the cantilever [19.30], and adapted it to work in solution.

An example of an adhesion measurement with the IFM is shown in [19.31]. which shows that the instrument is able to measure the entire interaction force curve without instabilities. Thus, this provides a *direct* measurement of the minimum interaction force (as well as forces at all other tip-sample separations) and is a more reliable measure of adhesion. The disadvantage with these techniques is primarily one of inconvenience: The probes require extra manufacturing steps and control electronics. However, given the importance of adhesion in nanoscale science and technology, the extra information gained makes these techniques clearly worth the effort.

Pull-off instabilities can occur even in a displacement-controlled experiment. In this case, the instability is an "intrinsic" instability, whereby the adhesive force gradient competes with the stiffness of the *contact itself* [19.32, 33]. Adhesive materials with low stiffness, such as polymers, may show this behavior.

Finally, the pull-off force may show a time dependence that arises from intrinsic viscoelasticity of the tip or sample materials [19.34], or kinetic effects due to adsorption or reaction of materials at the interface [19.35]. These regimes remain relatively unexplored, but certainly, to compare adhesion measurements between labs, the velocity of approach and retraction, as well as the time in contact ought to be reported for any published experimental results.

A quantitative and reliable examination of adhesion, therefore, requires careful consideration of the mechanics of the contact and the cantilever. For an AFM experiment in which instabilities occur, one can conclude that the pull-off force is a good measure of adhesion only if

1. the materials are fully elastic with little or no viscoelastic character,
2. the interface is chemically stable,
3. the cantilever stiffness is sufficiently low compared with the adhesive force gradient, and
4. the contact stiffness is sufficiently high compared with the adhesive force gradient. Otherwise, a more thorough investigation is required.

19.3 Calibration of Forces, Displacements, and Tips

Whether the forces are to be measured with load-controlled or displacement-controlled techniques, measurements cannot be compared between laboratories unless the forces are properly calibrated. Unfortunately, this can be a rather involved task, and adoption of standards has yet to become widespread and robust. Here we provide a summary of the pertinent issues with references to other work for further reading; these issues are also discussed in part B and C of this book.

19.3.1 Force Calibration

Commercially available AFM cantilevers often come in two forms: V-shaped and rectangular. Silicon and silicon nitride are the typical materials, and reflective coatings are often applied to enhance the reflectivity of the laser beam. The normal force constant of a monolithic rectangular cantilever beam is well-defined [19.36], but it relies on knowledge of all lever dimensions and its modulus. For a rectangular beam of length L, width w, thickness t, Young's modulus E, the stiffness k is given by:

$$k = \frac{Ewt^3}{4L^3} \,. \tag{19.4}$$

The cubic dependence on thickness is particularly problematic since in microfabrication processes t is usually determined by an etching process that is not precisely controlled, and is, therefore, difficult and cumbersome to measure experimentally. Variations in E can also occur depending on the type of cantilever, particularly for silicon nitride cantilevers, although the dependence on E is clearly not as critical. If a bulk value for E is used, the thickness can be determined by measuring the resonance frequency of the cantilever [19.37]. However, this method only works for uncoated monolithic cantilevers, since the metal coatings applied to enhance reflectivity, or for other purposes, will also alter substantially the spring constant [19.38]. In addition, formulae for V-shaped levers are substantially more complicated. Uncoated, single-crystal silicon cantilevers are perhaps the only ones for which the force constant can be reliably determined by using (19.4) and the resonance frequency [19.39]. Otherwise, an experimental, preferably in situ calibration method is strongly encouraged.

Experimental methods to calibrate the force constant of AFM cantilevers have been discussed extensively [19.37, 40–50]. It has been shown repeatedly that the manufacturer's quoted spring constants can be in error by large factors and should simply not be used in any quantitative research effort. We will not delve into the details of these calibration methods, but we do make note of one particularly recent method proposed by *Sader* et al. [19.51] that appears to be reliable and simple to carry out for rectangular levers. It relies on measuring the resonance frequency and the quality factor of the cantilever in air. Use of the hydrodynamic function relates the damping of air to the quality factor, and the dependence of E and t is eliminated from the resulting formula for the force constant.

19.3.2 Probe Tip Characterization

A problem of quite a different nature is that the geometry of the contact formed between the AFM tip and sample surface is not defined if the tip shape and composition is not known. This issue is of crucial importance since one is trying to understand the properties of an interface, and the tip is half of that interface.

The adhesion force between the tip and sample is a meaningless quantity in the absence of any knowledge of the tip shape [19.20]. The only use for such measurements is in cases where the *same* tip is used to compare different samples or different conditions, and verification by cyclic repetition of the experiments is carried out to ensure that the tip itself did not change during the experiment.

There are several in situ methods to characterize the tip shape. A topographic AFM image is actually a convolution of the tip and sample geometry [19.52]. Separation of the tip and sample contributions by contact imaging of known, or at least sharp, sample features allows determination of the tip shape to a significant extent [19.53–64]. Ex-situ tip imaging by transmission electron microscopy has also been performed [19.61, 65]. Some of these measurements have revealed that a *majority* of microfabricated cantilevers possess double tips and other unsuitable tip structures [19.56, 60, 64]. This convincingly demonstrates that tip characterization is absolutely necessary for useful nanotribological measurements with AFM. Thin film coatings applied to microfabricated levers can provide robust, smooth, and even conductive coatings [19.65–67]. Further work in this direction would be useful so as to provide a wider array of dependable tip structures and materials.

In addition to the shape of the tip, its chemical composition is equally important, but is also challenging to determine or control. *Xiao* et al. have shown that the AFM tip is readily chemically modified when scanned in contact with various materials [19.68], even tips that have been coated with self-assembled monolayers in order to control their chemistry. They recommend "running in" the tip with a standard sample to give reproducible results. The stresses that take place in a nano-contact can be very large [19.5], and so modification of both the chemistry and structure of the tip is important to consider.

One class of experiments for which the tip shape and chemistry is not as critical is when a molecule or nanostructure is tethered to the end of the tip and specific interactions are probed [19.69–73]. Another alternative method is to use colloid probes [19.74,75], whereby colloidal particles are attached to the cantilever on top of (or in place of) the tip. This method requires a unique calibration procedure [19.76], but provides particles whose structure and chemistry can be measured and perhaps controlled prior to attachment to the lever.

19.3.3 Displacement Calibration

Proper signal and spatial calibration also requires knowing the sensitivity of the piezoelectric scanning elements. This can involve complications due to instrumental drift [19.77] and inherent piezoelectric effects, namely nonlinearity, hysteresis, creep, and variations of sensitivity with applied voltage [19.78–82]. Caution must be exercised when determining and relying upon these parameters. Techniques such as laser interferometry [19.83], scanning sloped samples [19.45, 78], scanning known surface step heights [19.84], or the use of pre-calibrated piezoelectrics [19.85] can facilitate piezo calibration.

19.4 The Effect of Liquid Capillaries on Adhesion

The adsorption of water and other liquids onto surfaces, and their subsequent behavior at interfaces, continue to be a vibrant area of research. The importance of liquid-solid interface behavior is massive, encompassing topics as broad as paints, textiles, lubricants, geology, and environmental chemistry, and covering all corners of biology.

19.4.1 Theoretical Background

The ability to measure forces at the nanoscale using scanning probe microscopy has generated much interest in these fields. For any force measurement carried out in ambient laboratory conditions, one must consider the possibility of a capillary neck forming between the tip and sample. The study of such necks may, in turn, provide insight into the behavior of the liquid, which is discussed in other chapters in this book. In order to provide background for these emerging areas, we consider here the fundamental mechanical and chemical aspects of adhesion in the presence of a liquid meniscus. By way of introduction, *Israelachvili* [19.17] and *de Gennes* [19.87] provide rigorous coverage of the terminology, physics, and chemistry of liquid films and their wetting properties.

Water readily adsorbs at many surfaces. At a crack or sharp corner it can condense to form a meniscus if its contact angle is small enough. The small gap between an AFM tip and a surface is, therefore, an ideal occasion for such condensation. Early on, it was realized that liquid condensation plays a significant role in tip-sample interactions [19.88, 89].

The classic theory of capillary condensation starts by considering the thermodynamics of capillary formation. The general geometry of the capillary is shown in Fig. 19.3, adapted from [19.86], with hydrophobic surfaces sketched on the left half ($r_1 > 0$) and hydrophilic surfaces on the right half ($r_1 < 0$). The tip is idealized as a sphere of radius R. The water contact angles with the sample and tip respectively are θ_1 and θ_2. D represents the separation of the tip and sample. The angle ϕ is referred to as the "filling angle". The pressure difference, or Laplace pressure, across a curved interface is given by the Young–Laplace equation [19.17, 86]:

$$\Delta p = \gamma \left(\frac{1}{r_1} + \frac{1}{r_2} \right) , \tag{19.5}$$

where r_1 and r_2 are defined in Fig. 19.3 and γ is the surface tension of the liquid. The resulting force is attractive if $\Delta p < 0$. Note that $r_1 > 0$ and $r_2 < 0$. If the capillary formation is isothermal, then one can derive the Kelvin equation:

$$RT \ln \frac{p}{p_0} = \gamma V \left(\frac{1}{r_1} + \frac{1}{r_2} \right) , \tag{19.6}$$

where p_0 is the saturation pressure of the liquid, V is the molar volume of the liquid, T is the temperature, and R the molar gas constant. The ratio p/p_0 simply corresponds to the relative vapor pressure of the liquid,



Fig. 19.3 The AFM tip considered as a sphere at a distance *D* from the sample. The liquid film in between may form a concave (*right*) or convex (*left*) shaped meniscus in the plane shown (adapted after [19.86])

which in the case of water is just the relative humidity (RH). This is often rewritten in terms of the Kelvin radius r_k:

$$r_k^{-1} = \left(\frac{1}{r_1} + \frac{1}{r_2}\right) = \frac{R_M T}{\gamma V} \ln \frac{p}{p_0} \,. \qquad (19.7)$$

The Kelvin radius varies logarithmically with the partial pressure of the liquid and is by definition less than zero (negative values correspond to convex curvature). For water at 20 °C, $\gamma V/RT = 0.54\,\mathrm{nm}$. A graph of r_k vs. p/p_0 is shown in Fig. 19.4. Of particular note is the fact that starting from $p/p_0 = 0.35$ and higher, we find $|r_k| < 2\,\mathrm{nm}$. The application of this classic theory to capillaries with such small curvature radii is certainly a question to be considered carefully, and we will address it below.

A simple equation for the maximum attractive capillary force F_c between the tip and sample that is commonly used is:

$$F_c = -4\pi\gamma R \cos\theta \,. \qquad (19.8)$$

This equation is calculated by considering the Laplace pressure only. The adhesion force is predicted to be independent of RH. Notice that an immediate problem arises, which is that it predicts a finite force even at 0% RH, where there can be no capillary formation. Derivations of (19.8) are presented in several other publications [19.17, 86, 90, 91]. Significantly, this equation and its use with AFM experiments contain several assumptions, *many of which may not be valid for an AFM experiment*:

1. $|r_1| \ll R$, which is equivalent to saying ϕ is small,
2. $|r_1| \ll |r_2|$,
3. $\theta_1 = \theta_2$,
4. $D \ll |r_1|, |r_2|$,
5. the tip is shaped like a perfect sphere,
6. the effect of solid-solid adhesion is negligible with respect to the meniscus force,
7. the meniscus cross sections are perfect, circular arcs,
8. the force from the Laplace pressure dominates the force due to the resolved surface tension of the meniscus,
9. the surface tension γ is independent of the meniscus size,
10. the meniscus volume remains constant as the tip is retracted,
11. the maximum force of attraction is equal to the pull-off force,
12. the tip and sample are perfectly rigid.



Fig. 19.4 The Kelvin radius of water at 20 °C plotted as a function of the relative humidity

Assumption 1 may not be true, since the tip radius may indeed be small and comparable to the meniscus curvature radii. Assumption 2 may not be true since the small tip geometry may lead the two meniscus curvature radii to be similar. Assumption 3 is by no means true if the tip and sample are made of different materials. Assumption 4 may not be true since both the separation of the tip and sample, as well as the radii r_1 and r_2 may be in the nanometer range. Assumption 5 may be slightly or grossly in error and is a particularly dubious assumption in the absence of tip characterization. In addition, for large menisci, the capillary will grow beyond the end of the tip and start climbing up its shank, which may be pyramidal or conical in shape. Assumption 6 may also be inaccurate if van der Waals or other adhesive forces are significant (this is discussed further in the next section). Assumption 7 is not correct [19.90], and the regimes where it is a reasonable approximation require close scrutiny. Assumption 8 will be inaccurate at high relative vapor pressures [19.17, 91]. The nature of assumptions 1 to 8 and corrections to the theory to account for their violation are presented in the work of *Orr* and *Scriven* [19.90]. This theory remains within the bounds of the classical picture of capillary formation.

Assumption 9 concerns an important scientific question that has not been fully resolved and represents the possible violation of the classical framework of molecular effects at the nanoscale. SFA measurements by *Israelachvili* have indicated that for cyclohexane and other inert organic liquids, γ remains nearly equal to its macroscopic value even for Kelvin radii that, remarkably, correspond to one or two molecular diameters. However, for water, the adhesion force comes to within

10% of the bulk prediction only when $p/p_0 > 0.9$, which corresponds to a Kelvin radius greater than ~ 5 nm in magnitude [19.16]. This deviation from macroscopic thermodynamic predictions alone calls the use of (19.8) into serious question for AFM measurements. Rather, the exploration of this deviation at the molecular scale presents a unique opportunity for scanning probe measurements.

Assumptions 10 and 11 are not assumptions of (19.8) itself, but rather are assumptions that are often used when applying (19.8) to AFM measurements. Equation (19.8) simply gives the maximum force of attraction between the tip and sample. As discussed above, an AFM does *not* measure this quantity. Rather, it measures the force at which an instability occurs. If a capillary has formed between the tip and sample, then the force as a function of distance can be calculated. Calculating this force requires making one of two assumptions: Either the volume of the capillary is conserved (i. e., the rate of displacement is large with respect to the adsorption or desorption kinetics of the liquid), or the Kelvin radius is conserved (i. e., the rate of displacement is slow with respect to the adsorption or desorption kinetics of the liquid, and so the capillary remains in equilibrium). The constant volume assumption 10 has been used in every paper we have reviewed. *Israelachvili*, however, pointed out the difference between these two approaches in his book [19.17] and left the solution of the problem as an exercise to the reader! As with the problem of scale-dependent surface tension mentioned above, the kinetics of capillary formation and dissolution is a relatively unexplored problem and is therefore worthy of further investigation. A recent study of the humidity dependence of friction as a function of sliding speed is an example where this issue is raised [19.92].

Once an assumption about how the meniscus changes with displacement has been made, one still needs to consider the nature of the instability in order to relate the AFM pull-off measurement to the capillary's properties. As stated above and shown in Fig. 19.2, a low lever stiffness k or a strongly varying adhesive force will lead to a pull-off force that is nearly equal to the adhesive force, and so assumption 11 would be valid. However, if k is sufficiently large, or the capillary stiffness sufficiently weak, this assumption will fail. As we shall see below, experimental efforts to investigate this point, and theoretical work to predict it, have yet to be carried out.

Finally, assumption 12, if violated, requires a substantially more complex analysis. The question has been addressed independently by *Maugis* [19.93] and *Fogden* and *White* [19.94]. Both papers provide a nondimensional parameter that allows one to determine the severity of the effect. In the limit of small tips, stiff materials, large (in magnitude) Kelvin radii, and low surface tensions, the effect of elastic deformation is negligible. However, for relatively compliant materials, large tips, and small Kelvin radii, the meniscus can appreciably deform the contact in the immediate vicinity of the meniscus. This can substantially alter the mechanics of adhesion, as well as significantly affect the stresses. The dependence on the Kelvin radius is particularly critical. This effect may be of particular concern with soft materials like polymers or biological specimens. According to *Maugis*, the problem is analogous to the adhesive contact problem for solids, discussed by *Johnson* et al. [19.95] and studied further in many papers since [19.25, 96, 97].

19.4.2 Experimental and Theoretical Studies of Capillary Formation with Scanning Probes

There have been several experimental and theoretical investigations of how pull-off forces are affected by liquid capillaries. These studies have mostly focused on the effect of relative humidity. We do not present an exhaustive review here, but rather summarize a few key results that highlight the important trends observed and the outstanding questions that remain.

Early on, it was realized that water capillary formation occurred readily if at least one of the two surfaces in contact was hydrophilic. Higher adhesion will lead to higher contact forces and therefore larger elastic contact areas, and this can degrade the lateral spatial resolution of the AFM, as observed by *Thundat* et al. [19.98]. Furthermore, several observations have confirmed the expected result that capillary formation was readily prevented for hydrophobic surfaces. For example, *Binggeli* and *Mate* [19.88, 99] showed that tungsten tips in contact with clean silicon wafers with a hydrophilic native oxide exhibited strong adhesion and long pull-off lengths, whereas surfaces treated with a hydrophobic perfluoropolyether (such as Z-dol) showed pull-off forces reduced by a factor of 2 to 3. These results were confirmed by *Bhushan* and *Sundararajan* [19.100] who investigated the pull-off force between silicon nitride tips and Si(100) with and without Z-dol coatings for a range of relative humidities. As another example, MoO_3 films, likely hydrophilic, showed a sixfold increase in pull-off force measured with silicon tips from 0 to 50% RH [19.101].

While these examples illustrate some basic trends, the need for more finely resolved measurements as



Fig. 19.5 Pull-off force between a silicon nitride tip and the muscovite mica surface as a function of RH. Two sets of data are shown: increasing (*grey circles*) and decreasing (*brown circles*) humidity (after [19.35])



Fig. 19.6 Scanning polarization for microscopy image of water structures on the muscovite mica surface. A degree of polygonal shape to the boundaries is seen. The signal represents two distinct phases of water that are present as a molecular film below 45% RH (after [19.35])

a function of humidity has been addressed only quite recently. For example, *Xu* et al. measured adhesion between a silicon nitride tip and (hydrophilic) muscovite mica in ∼ 5% RH increments. The result is shown in Fig. 19.5. There are three identifiable regions: constant adhesion at low RH ($< 20\%$), increasing adhesion, and then decreasing adhesion. Some hysteresis is seen between experiments conducted with increasing and decreasing RH, but the overall trend is preserved. *Xu* et al. correlated their measurements with detailed studies of the growth of molecular water films on the mica surface, which they could image directly using scanning polarization force microscopy (Fig. 19.6). They proposed that below 20%, capillary condensation does not occur, and, indeed, they saw no evidence of a water film at these low humidities. Above 20% RH, a strongly bound molecular water layer was formed on the bare mica surface (Fig. 19.6). In the presence of the tip, a capillary meniscus condensed. Above 40% RH, the pull-off force decreased. Recognizing one of the limitations of (19.8), *Xu* et al. attribute this to the violation of assumption 5, listed above. They argue that for a pyramidal AFM tip, r_1 and r_2 become comparable in magnitude (and remain opposite in sign) once the capillary reaches the shank of the tip, leading to a near cancellation of the Laplace pressure given in (19.5). This argument is certainly plausible, although a rigorous proof is not provided, and the other limitations of (19.8) are not discussed in relation to this issue. Nevertheless, the correlation between the onset of adhesion increase and the formation of the molecular water film, as seen directly in their dramatic images, is an extremely convincing case where the classical assumptions of (19.8) must be modified to account for the molecular structure of the water film.

Further considerations of the limitations to the (19.8) were measured, discussed, and modeled in a detailed paper by *Xiao* and *Qian* [19.91]. Adhesion measurements, collected in large numbers for good statistics, were carried out with the same silicon nitride tip on two different surfaces: hydrophilic SiO_2 and a hydrophobic layer of *n*-octadecyltrimethoxysilane (OTE) on SiO_2. Contact angle measurements to confirm the assertion of hydrophilicity were not presented, however, the OTE surface was confirmed to be hydrophobic with a water contact angle of 108°. The results are shown in Fig. 19.7. The hydrophobic surface shows no dependence on RH, whereas the hydrophilic bare SiO_2 surface



Fig. 19.7 Pull-off force as a function of RH for adhesion between a silicon nitride tip and SiO_2 (*brown circles*) and OTE/SiO_2 (*grey circles*) samples (after [19.91])



Fig. 19.8 Contributions to the adhesion force as a function of humidity: a) resolved surface tension force; b) Laplace pressure force; c) total capillary force (Laplace + surface tension); d) van der Waals force; e) total adhesion force. (After [19.91])

shows three regimes similar to the result of *Xu* et al.: constant pull-off force (>∼ 30% RH), increasing pull-off force (30%–70% RH), and then decreasing pull-off force. *Xiao* and *Qian* discuss the limitations of (19.8) in substantial detail. In particular, they consider the violation of assumptions 1 through 8 listed above. This includes a treatment of van der Waals adhesion, taking into consideration the effect of electrostatic screening of this force by the water itself. Equations for this more general case are presented. With all these aspects taken into account, they are only able to fit the model to their data qualitatively (Fig. 19.8). At low RH (< 10%), the van der Waals force dominates and the adhesion is initially constant. At intermediate values, the Laplace pressure contribution increases and then begins to saturate. The contribution from the resolved surface tension becomes significant at high RH (above ∼ 80%), and the contribution from the Laplace pressure begins to drop strongly around this same point. Qualitatively, this reproduces their results (and the aforementioned ones) by producing regimes of constant, increasing, and then decreasing adhesion. However, the humidities at which the transitions occur, and the relative changes in adhesion, do not match the data. Somewhat better agreement at high RH (> 70%) is found by considering alternate (blunt) tip shapes. Nevertheless, the most significant discrepancy occurs for low RH, where the extent of the constant adhesion force is underestimated by the classical theory. The authors attribute this to the failure of the classical continuum theory to properly describe the properties of a molecular-scale meniscus. Another interesting point of this study is that at low RH, the adhesion is very similar for both samples, a fact that the authors attribute to the dominance of the van der Waals force for both samples (which is largely determined by the substrate and not affected significantly by the OTE film).

Slightly more recently, *He* et al. have studied capillary forces for a variety of tip-sample pairs [19.102]. Hydrophilic tips (silicon and silicon nitride with no surface treatment) and hydrophobic tips (coated with *n*-octadecyltricholorsilane) were used. The hydrophobic character of the tip was asserted based on a water contact angle measurement of 105.5°, presumably taken on



Fig. 19.9 **(a)** Pull-off force vs. RH measured between a hydrophilic tip and a flat silicon sample. *Circles*: measured when increasing RH. *Triangles*: measured when decreasing RH. **(b)** Pull-off force vs. RH measured between a sharp SFM tip coated with OTS and a flat silicon sample. The pull-off force is independent of humidity. (After [19.102])

a different region of the cantilever chip. Solvent-cleaned silicon samples and calcium fluoride films were used as hydrophilic substrates. As with the measurements of Xiao and Qian, contact angle measurements for the hydrophilic samples and tips were not presented. Results for hydrophobic and hydrophilic tips are shown in Fig. 19.9.

These results, which were carried out independently and without knowledge of Xiao and Qian's work, show impressive agreement. This is particularly interesting given that here the tip was varied from hydrophilic to hydrophobic (while the sample stayed hydrophilic), whereas in Xiao and Qian's work, the tip presumably remained hydrophilic and the sample was varied from hydrophilic to hydrophobic. For the hydrophobic tip, the pull-off force remains constant, indicating once again that capillary formation was suppressed. However, for the hydrophilic tip, three regimes of adhesion are found (Fig. 19.9). Similar results are found when a hydrophilic glass microsphere is used as a tip. The authors refer to these three regimes as the van der Waals regime, the mixed van der Waals–capillary regime, and the capillary regime. In agreement with Xiao and Qian's assessment, the authors propose that at low RH ($<\sim 35\%$ in this case), the formation of the water meniscus is suppressed and the adhesion is dominated by solid-solid (presumably van der Waals) interactions. They propose, based on the work of *de Gennes* on the theory of spreading [19.87], that a minimum precursor film thickness is required to form the meniscus. The authors also present a calculation of the adhesion force when assumptions 1 and 2 are relaxed.

Note that the results discussed above consistently indicate that only one hydrophilic surface is required to form the water film. This means that should meniscus formation be undesirable in a nanoscale application (as is the case for MEMS), then hydrophobic treatment of *both* contacting surfaces is likely required.

Practical guidance for discerning the dependence of capillary and van der Waals force is provided by *Stifter* et al. [19.86], who have produced a detailed theoretical model of the meniscus as a function of contact angles, tip size, relative humidity, separation, and surface tension (to represent liquids other than water). An example is shown in Fig. 19.11. The model relaxes assumptions



Fig. 19.10 Figure illustrating the distinct regimes of the pull-off force as a function of RH. Regimes A, B, and C are referred to as the van der Waals regime, mixed van der Waals–capillary regime, and capillary regime, respectively. (After [19.102])



Fig. 19.11 *Top*: geometric shape of the meniscus for a range of RH values. *Bottom*: the meniscus force between the tip and the surface due to the Laplace pressure. The *dashed line* represents a cantilever with force constant 1 N/m. This relatively stiff value is still less stiff than the capillary force curve and suggests that the pull-off force would be very close to the true adhesion force. Of course, summation of the van der Waals and other contributions are necessary to make a full comparison of this sort. (After [19.86])

1 through 4 and 6. These studies show regimes where either van der Waals force or Laplace pressure forces dominate and provide guidance for actual values of the tip geometry and contact angles that minimize the capillary forces. It is not clear how much of an effect the resolved surface tension would have, as that is not included in this particular calculation. Another practical result is that for most of the plots of force vs. displacement, the "stiffness" (gradient) of the curve rarely drops below 1 N/m. This indicates that, within the assumptions of this paper, using cantilevers with force constants of 0.1 N/m will give pull-off forces that are reasonably accurate measurements of the adhesion force. This is consistent with the results of *He* et al., who found no dependence of their measurements when using cantilevers whose nominal force constants ranged from 0.032–0.5 N/m.

19.4.3 Future Directions

The results and modeling so far indicate the possibility of two trends. Hydrophobic surfaces will exhibit little dependence of adhesion on RH, whereas if one surface is hydrophilic, three regimes of behavior occur: constant solid-solid adhesion at low RH, increasing adhesion at intermediate RH, and decreasing adhesion at the highest RH. Some insight into the physical mechanisms behind these regimes has been presented, but it would be desirable to pursue further work in this area.

Perhaps most critically needed is an atomic-scale picture of the menisci and water films present under low partial pressures. This could address the question of why adhesion is initially independent of RH, and when the meniscus itself would start to form. Further theoretical developments that address the assumptions laid out above would help to clarify the picture. It is also important to extend these studies beyond simply the case of water, as the properties of other liquids are also of great interest and could be compared to previous experiments with the SFA and other tools.

Studies that clarify the kinetics of meniscus formation are also needed. There should be a noticeable transition in behavior once the rate of displacement becomes comparable to the appropriate kinetic rates, and this could provide valuable information about these kinetic processes at the nanometer scale.

Finally, as mentioned before, there continues to be a gap in reproducibility and comparability between laboratories that will only be bridged when standard techniques for tip characterization and force and displacement calibration are addressed. Efforts that take these considerations into account are worthy of support.

19.5 Self-Assembled Monolayers

When thinking about adhesion and the related phenomenon of friction, it is important to realize that the interfaces of real surfaces in contact are rarely atomically smooth. Surfaces that appear smooth on the macroscopic scale, upon closer inspection are found to consist of nanometer-scaled asperities (typically on the order of 10 nanometers) whose intentional or accidental interactions ultimately control adhesion, friction, and wear at contacts [19.6, 7, 103–105]. The size of these asperities becomes particularly important when one considers that the true contact area between interfaces for the load distribution is localized through these asperity-asperity interactions in wich extremely high pressures can be produced, sharply increasing local stress fields that can cause materials to yield and shear as they encounter each other during sliding and intermittent contact. In addition to load distribution at nanoscale asperity-asperity contacts, their size will influence surface wetting and adhesion due to capillary forces localized at the contacts [19.7, 104, 105]. The structure of applied lubricant films at such asperities will be highly dependent upon asperity curvature, and defects in lubricant film structure may form more readily here than on atomically flat surfaces.

19.5.1 Adhesion at SAM Interfaces

The minimization of adhesion at such asperity-asperity contacts is a critical issue in MEMS devices [19.6, 7, 104, 105]. In fact, the intentional introduction of surface roughness (on the order of 10 nm RMS) can be employed to lead to reduced stiction during post–processing feature release. These same asperities, however, must later resist wear during controlled or accidental contact during device operation. Thus, the specific details of adhesion and energy dissipation at such asperity-asperity contacts are required for the rational design of such systems.

To function as a protective lubricant layer in such systems, self-assembled monolayers (SAMs) of alkylsilane and fluorosilane compounds with chain lengths ranging from C_{10} to C_{18} have been useful in the reduction of friction and adhesion in MEMS [19.7, 104–106]. Such direct applications of SAMs as lubricant films, combined with the ease of sample preparation and the ability to generate model surfaces with well-defined film chemistry and structure, have made nanotribological and adhesion studies of SAMs a rich area of research [19.5]. Many of these nanotribological studies have used AFM to examine either SAMs of alkylsilane films on atomically smooth Si wafers, glass, or mica surfaces. Alternatively, many researchers have examined alkanethiol films on atomically smooth Au(111) surfaces. Using this approach, many molecular level details, such as the influence of film chemistry and molecular organization on friction, and the adhesion and wear of SAMs, can be obtained. Developing a clear understanding of the details of adhesion at SAM-modified surfaces allows for the complex links between surface chemistry, adhesion, and friction to be understood at the molecular level. In this section, we overview AFM studies of adhesion on SAM-modified surfaces.

19.5.2 Chemical Force Microscopy: General Methodology

In order to probe adhesion between chemically modified surfaces using AFM, the probe tips and sample surfaces are typically modified via self-assembly of monolayers using organosilanes on such surfaces as mica, glass, or oxidized Si or Si_3N_4 (the latter two being the typical materials of which AFM tips are made), or formed from thiols on Au-coated AFM tips and surfaces (Fig. 19.12) [19.107, 108]. While this has been shown to be a facile method for the modification of AFM tips for chemical force measurements, it should be noted that the details of the packing densities of the monolayers formed on the AFM tips are generally not known. This lack of detail regarding molecular overlayers on AFM probe tips can be a problem that requires careful consideration when using such chemically modified tips for the quantitative determination of adhesion forces and molecular interactions, as the number density of species in the tip sample contact is related to the measured adhesion.

Details of the environment in which the adhesion measurements are carried out are also an important consideration. Under ambient environmental lab conditions, surfaces are contaminated with organic compounds from the air, as well as with a layer of condensed water vapor, which varies with humidity. The condensed water layer can form a contact meniscus between the tip and sample, introducing a capillary force into the measured adhesion [19.109]. The presence of this capillary force can overwhelm the details of the adhesion from the SAM-terminated surfaces to be probed. To eliminate capillary forces, many studies are performed under liquid environments or ultrahigh vacuum. Under liquids, the nature of the solvent will of course impact the measured adhesion for a given pair of interacting surfaces, as solvent exclusion plays an important role. Also, in the case of water, the pH and ionic strength of the water environment can influence the measured adhesion in the presence of any surface-bound charges.



Fig. 19.12 The modification of AFM tips for chemical force microscopy is frequently carried out by chemical functionalization by alkylsilane monolayers on the oxidized surfaces of Si- or Si_3N_4-based tips, or by alkylthiol monolayers assembled on Au-coated (∼ 50 nm) AFM tips. The Au tips also typically have a Cr binding layer (∼ 5 nm) placed on before Au coating

In quantifying adhesion energies from AFM measurements, the contact mechanics model developed by Johnson, Kendall, and Roberts (JKR model) [19.20, 95] is often employed in the analysis of the adhesion data acquired by force-distance spectroscopy, whereby the number of interacting species (and consequently the average "unit" interaction force or energy) can be derived from the estimated contact area and the average molecular packing density. Using the JKR model, the force of adhesion (AFM pull-off force) is related to the work of adhesion, W_{adh}, and the reduced radius, R, of the tip-surface contact:

$$F_{adh} = -\frac{3}{2}\pi R W_{adh} \,. \tag{19.9}$$

The work of adhesion is a combination of the tip-surface (γ_{ts}), tip-solvent (γ_{tl}) and surface-solvent (γ_{sl}) interfacial energies ($W_{adh} = \gamma_{sl} + \gamma_{tl} - \gamma_{ts}$), and for tip-surface combinations that have the same chemical composition, the surface energy may be estimated directly from the adhesion measurement as W_{adh}. The effective contact radius at separation, r_s, from the JKR model is given as:

$$r_{\mathrm{s}} = \left(\frac{3\pi W_{\mathrm{adh}} R^2}{2K}\right)^{1/3} , \tag{19.10}$$

where K is the reduced elastic moduli of the tip and surface. Using the contact area at separation and the assumed packing density of the molecules at the surfaces in contact, an estimate of the adhesion force or interaction energy on a per molecule basis can be made.

The accuracy of the interfacial energies and per molecule values obtained using this approach, however, must be carefully considered, due to the accumulation of error carried by the imprecise knowledge of the contact, including the tip radius, molecular packing densities of the modified surfaces, as well as the associated elastic properties of the contact at the monolayer level. As the details of the elastic properties of self-assembled monolayers are generally not known, the elastic properties of the contacts are typically assumed to be dominated by those of the underlying substrate, and the bulk values of the surface and/or tip materials (Au, Si, mica, Si_3N_4, SiO_2) are often employed in these calculations. Moreover, as mentioned above, if the molecular packing densities of the monolayers being evaluated are not known (as is the case with a typical AFM tip), then estimations must be used. For contact areas at pull-off approaching 1 nm^2, if the error in packing density is as much as 1 molecule per nm^2, this can lead to an error as high as 25% for a typical alkanethiol, or more in the reported per molecule adhesion force. Such details should be taken into consideration when describing quantitative measurements.

Table 19.1 List of various interactions evaluated by atomic force microscopy adhesion measurements

Chemical Contacts	References
$-CH_3/-CH_3$	[19.110–119]
$-CH_3/-COOH$	[19.110, 114, 116, 118]
$-CH_3/-CONH_2$	[19.118]
$-CH_3/-NH_2$	[19.118]
$-CH_3/-OH$	[19.118]
$-CF_3/-CF_3$	[19.113]
$-CF_3/-CH_3$	[19.113]
$-OH/-OH$	[19.30, 115, 117–121]
$-OH/NH_2$	[19.118]
$-OH/-COOH$	[19.117, 118]
$-OH/-CONH_2$	[19.118]
$-COOH/-COOH$	[19.30, 111, 114, 115, 117, 118, 122]
$-CONH_2/-CONH_2$	[19.118]
$-CONH_2/-COOH$	[19.118]
$-NH_2/-NH_2$	[19.116–118, 123]
$-CH_3/-NH_2$	[19.118, 123]
$-NH_2/-COOH$	[19.118]
$-NH_2/-CONH_2$	[19.118]
$-SO_3H/-SO_3H$	[19.123]
$-CH_3/-SO_3H$	[19.123]
$-NH_2/-SO_3H$	[19.123]
$-PO_3H_2/-PO_3H_2$	[19.116]
$-SH/-SH$	[19.119]

An alternative approach to the measure of adhesive interactions based on Poisson statistics has been promoted by *Beebe* et al. for the statistical evaluation of single bond forces without a priori knowledge of the tip-surface contact details involved [19.119, 121, 122]. A principal limitation of this approach, however, is that a completely homogeneous chemical system is assumed, i. e., that there is only one type of discrete interaction present that gives rise to the observed adhesion. Unfortunately, for many solution phase systems a number of different interactions are typically operative, including energetic exchange with and reorganization of solvent molecules, depending on the solution conditions. These issues have never been thoroughly addressed in any molecular-level measurement of adhesion.

19.5.3 Adhesion at SAM-Modified Surfaces in Liquids

A number of researchers have used AFM to probe interfacial adhesion for a variety of different chemical systems. Most notably, *Lieber* et al. promoted the use of chemically modified substrates and AFM tips to study selective molecular interactions [19.73, 107, 110, 114, 117, 124]. A number of other researchers have adopted a similar methodology, leading to the measurement of adhesion forces and interfacial energies for the interactions of a variety of molecular functional groups in various environments, although to date few specific types of interactions have been thoroughly investigated (Table 19.1) [19.30, 107, 110–115, 120, 122, 125–129].

As described above, measurements in air suffer from difficulties of water vapor, thus, the adhesion of many SAM-terminated surfaces have been evaluated under liquids, and it is these systems that we shall focus on here. The value of the adhesion is of course modified depending on the solvent. For example, the interaction of methyl-terminated interfaces is much stronger in water than in nonpolar solvents, in agreement with the general concept that upon separation the generation of hydrophobic interfaces in a polar solvent is highly energetically unfavorable. The impact of solvent on adhesion can be addressed basically as a variation on the Hamaker constant.

When ionizable end groups are studied in water, the details of the adhesion measurements and results become more complicated, as the chemical nature of the surfaces are now dependent on the pH and ionic strength of the solution. In these circumstances, multiple interactions, including ionic, van der Waals and double-layer forces, come into play simultaneously. Under these conditions, the general form for the JKR adhesion force may be modified to include the following additional forces:

$$F_{\text{adh}} = -\frac{3}{2}\pi R W_{\text{adh}} - \frac{AR}{6D} + 6\pi R W_{\text{dl}} , \qquad (19.11)$$

where the second term now includes the attractive van der Waals component and the third term is the repulsive double layer.

Several groups have utilized the ability of AFM to function as a local probe of ionicity and to carry out local force titration measurements on several functional groups, including $-\text{COOH}$ [19.30, 114–118, 122], $-\text{NH}_2$ [19.116–118, 123], $-\text{SO}_3\text{H}$ [19.123] and $-\text{PO}_3\text{H}_2$ [19.116, 130] (see Table 19.1). The force-distance curves can give a general sense of the local chemical state based on whether the approach curve is attractive or repulsive. In force titrations, the adhesion is measured as a function of pH, and the change in force is dependent upon the equilibrium mixture of charged species within the tip-samples contact at the time of measurement. Peaks in the adhesion force vs. pH allow for the determination of the local pK values for the ionized species, which are shown to be dependent on ionic strength. A force titration of a diprotic acid (11-thioundecyl-1-phosphonic acid) is shown in Fig. 19.13. Shifts in the pK values from those measured in free solution have been ascribed to a variety of factors, including buildup of excess surface charge and solvation effects of the surface-bound ionic species. The localization of charge and change migration are effects that have yet to be fully explored in these systems, however.

19.5.4 Impact of Intra- and Inter-Chain Interactions on Adhesion

Several studies of the effects of chain length on friction and adhesion have found that, in general, adhesion decreases with increasing chain length, due to increased stability from lateral chain–chain van der Waals interactions within the film, which increases the overall film stiffness. The increased stiffness of the films acts to reduce the effective contact area that develops under compression, consequently reducing adhesion and friction [19.126,127,131]. In alkyl chain-based monolayers, the end-group orientation, however, is also dependent on chain length. This results in an "odd-even" effect on the measured adhesion/friction of the monolayer. With $-\text{CH}_3$-terminated films, the methyl group orientation differs for odd and even length molecules. This impacts the orientation of the methyl group net dipole and, hence, the local surface free energy [19.73]. In circumstances where interchain hydrogen bonding can occur, additional film stability can be introduced, also yielding an odd–even effect, as observed by *Houston* et al. [19.111, 125].



Fig. 19.13a,b Adhesion vs. pH for 11-thioundecyl-1-phosphonic acid in buffer illustrating the impact of pH and ionic strength, **(a)** 10^{-4} M and **(b)** 10^{-1} M on the measured adhesion. The peaks in adhesion provide local measures of the surface pK (adapted after [19.130])

Studies by AFM of alkanethiol films on Au surfaces have shown that, depending upon the tip size, under varying loads, the tip can readily penetrate the SAM film, displacing the thiol layer from the tip-sample contact [19.132–134]. Upon reduction of the force, the tip again moves out of the SAM film and the surface structure is returned to its original condition. Of key importance in such studies is the mechanism by which the film is displaced. Recently, this has been modeled by *Harrison* using molecular dynamics simulations [19.135]. These studies have clearly demonstrated that in the initial stages of film compression and penetration by an asperity, gauche defects within the typically all-trans configurations of molecules in the SAM layers appear and propagate. The introduction of such defects is the catalyst for the weakening of the chain-chain lateral interactions that help stabilize and maintain film integrity. As this is lost, the asperity can rapidly penetrate the film, and alkanethiol displacement can occur either via chain collapse or bond scission from the surface. *Salmeron* et al. demonstrated that the prevalence of molecular displacement versus film compression depends heavily on the AFM tip size, with sharp tips readily penetrating and displacing surface-bound thiols, while large tips spread the load over more molecules and induce compression over displacement (Fig. 19.14).

The inherent stability of the film structure has also been confirmed by sum-frequency generation spectroscopic studies that have indicated that without the presence of lateral chain-chain interactions, gauche defects appear within the chain structure that reduce overall order and lateral interactions within films [19.136]. The ability to form these defects through poor film order will consequently increase adhesion, friction, and wear of the film. This same spectroscopic study further demonstrated that the appearance of gauche defects can be induced by controlling the local environment, i. e., with the presence of water, causing chains to collapse back upon themselves.



Fig. 19.14 Schematic illustrating the compression of a model lubricant layer under an AMF tip. At low pressures, the gauche defects can form at the tip–sample junction, but the molecules remain in place. Depending on tip size and load, displacement (for sharp tips) or trapping of monolayer molecules (for blunt tips) can occur (adapted after [19.5])

As molecular structure in SAMs moves away from ideally organized layers, chain-chain interactions between the contacting surfaces can also result in entanglements. A recent study of the adhesive interactions of Au(111) surfaces modified with dialkylsulfides [$CH_3(CH_2)_n{-}S{-}(CH_2)_9CH_3$; $n = 9, 11, 13, 15, 17$] with varying chain arm lengths probed the combined effect of chain length, solvent, and inter-surface chain entanglement on friction and adhesion using simultaneously modified surfaces and AFM tips [19.137]. This study found that chain-chain interpenetration produced the reverse dependence on chain length on the measured adhesion mentioned above. This work points to the need to examine the nature of inter-surface chain entanglements in nanoscaled systems. Such entanglements should be more prevalent in asperity-asperity contacts where ideal film structure will not be feasible.

19.5.5 Adhesion at the Single-Bond Level

The ability to resolve the discrete components of interactions is highly desirable. There have been few reports of the direct observation of discrete force components observed with the separation of an AFM tip from a surface. *Beebe* et al., have utilized a statistical method (as described above) for the direct determination of single-bond forces for a variety of interactions [19.119, 121, 122], including biological systems such as biotin-avidin [19.138, 139]. The first report of quantized force measurements was described by *Hoh* et al., which lead to the estimation of single hydrogen bonding forces from studies of glass surfaces in water to be on the order of 10 pN [19.140]. The use of AFM for the study of the energetics of true single chemical bond cleavage has also received little attention. One previous report described discrete covalent bond scission using AFM. In that case, it was proposed that the jumps in the observed pull-off curves were due to sequential scission of chemical bonds contained in a large,



Fig. 19.15 Pull-off force distribution for Au atom abstraction in ethanol. The 100 pN peaks in the distribution represent quantized numbers of Au atoms being abstracted from the sample surface (adapted after [19.129])

multifunctional, polymeric species as it progressively detached from the substrate [19.141]. However, the identification of the relevant chemical bonds involved at each stage was largely based on the known (gas phase) bond strengths of the potentially active functional groups such that solvation effects on the bond energies were ignored – a simplification that profoundly affects the estimated energetics, as energetic exchange with the solvent must be included. More recently, the measurement of discrete bond scission was reported by *Frisbie* et al. for Au-thiol complexes (Fig. 19.15). Here the details of Au atom abstraction were reported with a quantized value of 100 pN (estimated at ∼ 10 kJ/mol, based on an assumed bond rupture length of 1 Å) [19.129]. These studies have demonstrated the feasibility of probing local single bond energetics and have suggested some general requirements for the measurement of adhesion quantization in SAM layers, including the need for a significant negative tip-surface interfacial energy coupled with minimal solvent surface tension [19.129, 142].

19.5.6 Future Directions

Extending AFM adhesion measurements to reactive systems in which chemical bonds can form between the tip and surface affords an expansion of chemical reaction dynamics to solution-based chemistries, whereby the energetic details of single reaction events, previously only accessible for gas phase scattering experiments, may be obtained. Studies of such complex heterogeneous systems will open the door to the evaluation of the energetic pathways of solution-based chemistries for any system in which the appropriate functionalization of surfaces can be exploited. Adhesion has already been demonstrated as a reasonable local probe of surface reaction kinetics, whereby the local changes in the chemical forces may be followed as a function of time during surface chemical reactions [19.143, 144]. In addition to advances in measurements of reactive systems by AFM, complete insight into the operative molecular mechanisms can only be gained when combined with detailed theory that takes into account not only the specific types of interactions present between the surfaces, but also the requisite energetic exchange with local solvent molecules. Advances in computer technologies and in computational theory have made this realistic [19.128].

To advance the area of adhesion measurements at the molecular level, energetic barriers for specific interactions also need to be evaluated, with attention given to the nature of the molecular interactions being probed, *including* the details of energetic exchange with the solvent surrounding the interacting molecules. Studies by AFM of molecular interactions within sharply confined geometries (i. e., ∼ 1 nm^2 contact area) provide an opportunity to evaluate such contributions with molecular detail. Here again, *Lieber* et al. have been advancing the approach of chemically functionalizing carbon nanotubes to reduce both the type and number of specific interacting species [19.73]. This approach may hold some promise for probing well-defined, specific chemical interactions and/or reactions, as long as the nanotubes can be sufficiently stabilized against buckling [19.135, 145, 146].

In addition to the modification of probe geometries to improve localization of interactions for adhesion measurements, one of the principle difficulties in performing AFM measurements of adhesion at SAM surfaces is the unavoidable snap to contact. This makes the details of the long-range interaction potential almost completely inaccessible. To address this issue, *Lieber* et al. have developed a modified AFM system in which the cantilever is magnetized, providing an additional feedback mechanism to aid in avoiding snap-in [19.30]. When used, this approach provides a smooth approach and retract curve. Similarly, the capacitive coupling feedback mechanism of the interfacial force microscope (IFM) also affords measurements of this transition without snap-in [19.125].

19.6 Concluding Remarks

Scanning probes are powerful tools for determining the fundamental molecular basis of adhesion. Continuum models of adhesion and capillary condensations are useful, but careful attention must be paid to their limits and assumptions. Further progress in these areas requires detailed analysis of the structure and chemistry of both the tip and sample, as well as their environment (solvent, humidity, etc.).

The ability to determine the effects of molecular-scale water menisci or single bond energetics are truly spectacular accomplishments that continue to inspire researchers worldwide to pursue these measurements. With attention paid to previous literature and consideration of issues raised in this chapter, many more discoveries are sure to be made.

References

19.1 I. L. Singer, H. M. Pollock (Eds.): *Fundamentals of Friction* (Kluwer, Dordrecht 1992) p. 351

19.2 K. Autumn, Y. A. Liang, S. T. Hsieh, W. Zesch et al.: Adhesive force of a single gecko foot-hair, Nature **405** (2000) 681–685

19.3 A. L. Baldwin, G. Thurston: Mechanics of endothelial cell architecture and vascular permeability, Critical Rev. Biomed. Eng. **29** (2001) 247–278

19.4 S. R. White, N. R. Sottos, P. H. Guebelle, J. S. Moore et al.: Autonomic healing of polymer composites, Nature **409** (2001) 794–797

19.5 R. W. Carpick, M. Salmeron: Scratching the surface: Fundamental investigations of tribology with atomic force microscopy, Chem. Rev. **97** (1997) 1163–1194

19.6 R. Maboudian: Adhesion and friction issues associated with reliable operation of MEMS, MRS Bull. **23** (1998) 47–51

19.7 R. Maboudian, W. R. Ashurst, C. Caffaro: Tribological challenges in micromechanical systems, Tribol. Lett. **12** (2002) 95–100

19.8 R. Maboudian, R. T. Howe: Critical review: Adhesion in surface micromechanical structures, J. Vac. Sci. Technol. **15** (1997) 1

19.9 J. N. Israelachvili: Thin film studies using multiple-beam interferometry, J. Colloid Interface Sci. **44** (1973) 259–272

19.10 J. N. Israelachvili, D. Tabor: The measurement of van der Waals dispersion forces in the range 1.5 to 130 nm, Proc. R. Soc. London A **331** (1972) 19–38

19.11 G. Binnig, C. F. Quate, C. Gerber: Invention of AFM, Phys. Rev. Lett. **56** (1986) 930

19.12 P. Frantz, N. Agraït, M. Salmeron: SFA w/ capacitance, Langmuir **12** (1996) 3289–3294

19.13 J. N. Israelachvili, P. M. McGuiggan, A. M. Homola: Dynamic properties of molecularly thin liquid films, Science **240** (1988) 189–191

19.14 J. Peachey, J. Van Alsten, S. Granick: Design of an apparatus to measure the shear response of ultrathin liquid, Rev. Sci. Instrum. **62** (1991) 463–473

19.15 L. R. Fisher, J. N. Israelachvili: Direct measurement of the effect of meniscus forces on adhesion: A study of the applicability of macroscopic thermodynamics to microscopic liquid interfaces, Colloids Surf. **3** (1981) 303–319

19.16 L. R. Fisher, J. N. Israelachvili: Experimental studies on the applicability of the Kelvin equation to highly curved concave menisci, J. Colloid Interface Sci. **80** (1981) 528–541

19.17 J. N. Israelachvili: *Intermolecular and Surface Forces* (Academic Press, London 1992)

19.18 S. Granick: Molecular tribology of fluids. In: *Fundamentals of Friction*, ed. by I. L. Singer, H. M. Pollock (Kluwer, Dordrecht 1992) p. 387

19.19 G. Reiter, A. L. Demirel, J. Peanasky, L. L. Cai et al.: Stick to slip transition and adhesion of lubricated surfaces in moving contact, J. Chem. Phys. **101** (1994) 2606

19.20 K. L. Johnson: *Contact Mechanics* (Cambridge Univ. Press, Cambridge 1987)

19.21 O. Marti, B. Drake, P. K. Hansma: Atomic force microscopy of liquid-covered surfaces: Atomic resolution images, Appl. Phys. Lett. **51** (1987) 484–486

19.22 G. J. Germann, S. R. Cohen, G. Neubauer, G. M. McClelland et al.: Atomic scale friction of a diamond tip on diamond (100) and (111) surfaces, J. Appl. Phys. **73** (1993) 163

19.23 L. Howald, E. Meyer, R. Lüthi, H. Haefke et al.: UHV AFM design, Appl. Phys. Lett. **63** (1993) 117

19.24 M. Kageshima, H. Yamada, K. Nakayama, H. Sakama et al.: Development of an ultrahigh vacuum atomic force microscope for investigations of semiconductor surfaces, J. Vac. Sci. Technol. B **11** (1993) 1987–1991

19.25 J. A. Greenwood: Adhesion of elastic spheres, Proc. R. Soc. London A **453** (1997) 1277–1297

19.26 S. P. Jarvis, A. Oral, T. P. Weihs, J. B. Pethica: A novel force microscope and point contact probe, Rev. Sci. Instrum. **64** (1993) 3515

19.27 S. P. Jarvis, H. Yamada, S.-I. Yamamoto, H. Tokumoto: A new force controlled atomic force microscope for use in ultrahigh vacuum, Rev. Sci. Instrum. **67** (1996) 2281

19.28 S. A. Joyce, J. E. Houston: A new force sensor incorporating force-feedback control for interfacial force microscopy, Rev. Sci. Instrum. **62** (1991) 710–715

19.29 S. A. Joyce, J. E. Houston, T. A. Michalske: Differentiation of topographical and chemical structures using an interfacial force microscope, Appl. Phys. Lett. **60** (1992) 1175

19.30 P. D. Ashby, L. W. Chen, C. M. Lieber: Probing intermolecular forces and potentials with magnetic feedback chemical force microscopy, J. Am. Chem. Soc. **122** (2000) 9467–9472

19.31 H. I. Kim, V. Boiadjiev, J. E. Houston, X.-Y. Zhu, J. D. Kiely: Tribological properties of self-assembled monolayers on Au, SiO_x and Si surfaces, Tribol. Lett. **10**(1–2) (2001) 97–101

19.32 J. S. Nelson, B. W. Dodson, P. A. Taylor: Adhesive avalanche in covalently bonded materials, Phys. Rev. B **45** (1992) 4439–4444

19.33 P. A. Taylor, J. S. Nelson, B. W. Dodson: Adhesion between atomically flat metallic surfaces, Phys. Rev. B **44** (1991) 5834–5841

19.34 K. R. Shull: Contact mechanics and the adhesion of soft solids, Mater. Sci. Eng. R: Rep. **R 36** (2002) 1–45

19.35 L. Xu, A. Lio, J. Hu, D. F. Ogletree et al.: Wetting and capillary phenomena of water on mica, J. Phys. Chem. B **102** (1998) 540–548

19.36 S. P. Timoshenko, J. N. Goodier: *Theory of Elasticity* (McGraw Hill, New York 1987)

19.37 J. P. Cleveland, S. Manne, D. Bocek, P. K. Hansma: A nondestructive method for determining the spring constant of cantilevers for scanning force microscopy, Rev. Sci. Instrum. **64** (1993) 403

19.38 J. E. Sader: Parallel beam approximation for V-shaped atomic force microscope cantilevers, Rev. Sci. Instrum. **66** (1995) 4583

19.39 M. Tortonese, M. Kirk: Characterization of application specific probes for SPMs, Proc. SPIE **3009** (1997) 53–60

19.40 T. R. Albrecht, S. Akamine, T. E. Carver, C. F. Quate: Microfabrication of cantilever styli for the atomic force microscope, J. Vac. Sci. Technol. A **8** (1990) 3386–3396

19.41 H.-J. Butt, P. Siedle, K. Seifert, K. Fendler et al.: Scan speed limit in atomic force microscopy, J. Microsc. **169** (1993) 75–84

19.42 Y. Q. Li, N. J. Tao, J. Pan, A. A. Garcia et al.: Direct measurement of interaction forces between colloidal particles using the scanning force microscope, Langmuir **9** (1993) 637–641

19.43 R. Lüthi, E. Meyer, H. Haefke, L. Howald et al.: Nanotribology: An UHV-SFM study on thin films of C_{60} and AgBr, Surf. Sci. **338** (1995) 247–260

19.44 J. M. Neumeister, W. A. Ducker: Lateral, normal, and longitudinal spring constants of atomic force microscopy cantilevers, Rev. Sci. Instrum. **65** (1994) 2527–2531

19.45 D. F. Ogletree, R. W. Carpick, M. Salmeron: Calibration of frictional forces in atomic force microscopy, Rev. Sci. Instrum. **67** (1996) 3298–3306

19.46 J. A. Ruan, B. Bhushan: Atomic-scale friction measurements using friction force microscopy: Part I – general principles and new measurement techniques, Trans. ASME J. Tribol. **116** (1994) 378

19.47 J. E. Sader, I. Larson, P. Mulvaney, L. R. White: Method for the calibration of atomic force microscope cantilevers, Rev. Sci. Instrum. **66** (1995) 3789

19.48 U. D. Schwarz, P. Koster, R. Wiesendanger: Quantitative analysis of lateral force microscopy experiments, Rev. Sci. Instrum. **67** (1996) 2560

19.49 T. J. Senden, W. A. Ducker: Experimental determination of spring constants in atomic force microscopy, Langmuir **10** (1994) 1003

19.50 A. Torii, M. Sasaki, K. Hane, S. Okuma: A method for determining the spring constant of cantilevers for atomic force microscopy, Meas. Sci. Technol. **7** (1996) 179–184

19.51 J. E. Sader, J. W. M. Chon, P. Mulvaney: Calibration of rectangular atomic force microscope cantilevers, Rev. Sci. Instrum. **70** (1999) 3967–3969

19.52 J. S. Villarrubia: Morphological estimation of tip geometry for scanned probe microscopy, Surf. Sci. **321** (1994) 287–300

19.53 F. Atamny, A. Baiker: Direct imaging of the tip shape by AFM, Surf. Sci. **323** (1995) L314

19.54 R. W. Carpick, N. Agraït, D. F. Ogletree, M. Salmeron: Measurement of interfacial shear (friction) with an ultrahigh vacuum atomic force microscope, J. Vac. Sci. Technol. B **14** (1996) 1289–1295

19.55 R. Dixson, J. Schneir, T. McWaid, N. Sullivan et al.: Toward accurate linewidth metrology using atomic force microscopy and tip characterization, Proc. SPIE **2725** (1996) 589–607

19.56 L. S. Dongmo, J. S. Villarrubia, S. N. Jones, T. B. Renegar et al.: Experimental test of blind tip reconstruction for scanning probe microscopy, Ultramicroscopy **85** (2000) 141–153
19.57 K. F. Jarausch, T. J. Stark, P. E. Russell: Silicon structures for in situ characterization of atomic force microscope probe geometry, J. Vac. Sci. Technol. B **14** (1996) 3425–3430
19.58 P. Markiewicz, M. C. Goh: Atomic force microscope tip deconvolution using calibration arrays, Rev. Sci. Instrum. **66** (1995) 3186–3190
19.59 C. Odin, J. P. Aimé, Z. El Kaakour, T. Bouhacina: Tip's finite size effects on atomic force microscopy in the contact mode: Simple geometrical considerations for rapid estimation of apex radius and tip angle based on the study of polystyrene latex balls, Surf. Sci. **317** (1994) 321–340
19.60 S. S. Sheiko, M. Moller, E. M. C. M. Reuvekamp, H. W. Zandbergen: Evaluation of the probing profile of scanning force microscopy tips, Ultramicroscopy **53** (1994) 371–380
19.61 P. Siedle, H.-J. Butt, E. Bamberg, D. N. Wang et al.: Determining the form of atomic force microscope tips. In: *X-Ray Optics and Microanalysis*, ed. by P. B. Kenway, P. J. Duke, G. W. Lorimer et al. (Iop, Manchester 1992) pp. 361–364
19.62 J. S. Villarrubia: Algorithms for scanned probe microscope image simulation, surface reconstruction, and tip estimation, J. Res. Nat. Inst. Stand. Technol. **102** (1997) 425–454
19.63 K. L. Westra, D. J. Thomson: Atomic force microscope tip radius needed for accurate imaging of thin film surfaces, J. Vac. Sci. Technol. B **12** (1994) 3176–3181
19.64 S. Xu, M. F. Arnsdorf: Calibration of the scanning (atomic) force microscope with gold particles, J. Microsc. **3** (1994) 199–210
19.65 U. D. Schwarz, O. Zwörner, P. Köster, R. Wiesendanger: Friction force spectroscopy in the low-load regime with well-defined tips. In: *Micro/Nanotribology and Its Applications*, ed. by B. Bhushan (Kluwer, Dordrecht 1997)
19.66 P. Niedermann, W. Hanni, N. Blanc, R. Christoph et al.: Chemical vapor deposition diamond for tips in nanoprobe experiments, J. Vac. Sci. Technol. A **14** (1995) 1233–1236
19.67 S. J. O'Shea, R. N. Atta, M. E. Welland: Characterization of tips for conducting atomic force microscopy, Rev. Sci. Instrum. **66** (1995) 2508–2512
19.68 L. M. Qian, X. D. Xiao, S. Z. Wen: Tip in situ chemical modification and its effects on tribological measurements, Langmuir **16** (2000) 662–670
19.69 E. L. Florin, V. T. Moy, H. E. Gaub: Adhesion forces between individual ligand-receptor pairs, Science **264** (1994) 415–417
19.70 G. U. Lee, L. A. Chrisey, R. J. Colton: Direct measurement of the forces between complementary strands of DNA, Science **266** (1994) 771–773
19.71 V. T. Moy, E. L. Florin, H. E. Gaub: Intermolecular forces and energies between ligands and receptors, Science **266** (1994) 257–259
19.72 O. H. Willemsen, M. M. E. Snel, K. O. van der Werf, B. G. de Grooth et al.: Simultaneous height and adhesion imaging of antibody-antigen interactions by atomic force microscopy, Biophys. J. **75** (1998) 2220–2228
19.73 S.-S. Wong, H. Takano, M. D. Porter: Mapping orientation differences of terminal functional groups by friction force microscopy, Anal. Chem. **70** (1998) 5209–5212
19.74 H. J. Butt: Measuring electrostatic, van der Waals, and hydration forces in electrolyte solutions with an atomic force microscope, Biophys. J. **60** (1991) 1438–1444
19.75 W. A. Ducker, T. J. Senden, R. M. Pashley: Direct measurement of colloidal forces using an atomic force microscope, Nature **353** (1991) 239–241
19.76 V. S. J. Craig, C. Neto: In situ calibration of colloid probe cantilevers in force microscopy: Hydrodynamic drag on a sphere approaching a wall, Langmuir **17** (2001) 6018–6022
19.77 R. Staub, D. Alliata, C. Nicolini: Drift elimination in the calibration of scanning probe microscopes, Rev. Sci. Instrum. **66** (1995) 2513–2516
19.78 J. Fu: In situ testing and calibrating of z-piezo of an atomic force microscope, Rev. Sci. Instrum. **66** (1995) 3785–3788
19.79 J. Garnaes, L. Nielsen, K. Dirscherl, J. F. Jorgensen et al.: Two-dimensional nanometer-scale calibration based on one-dimensional gratings, Appl. Phys. A **66** (1998) 831–835
19.80 S. M. Hues, C. F. Draper, K. P. Lee, R. J. Colton: Effect of PZT and PMN actuator hysteresis and creep on nanoindentation measurements using force microscopy, Rev. Sci. Instrum. **65** (1994) 1561
19.81 J. F. Jorgensen, K. Carneiro, L. L. Madsen, K. Conradsen: Hysteresis correction of scanning tunneling microscope images, J. Vac. Sci. Technol. B **12** (1994) 1702–1704
19.82 J. F. Jorgensen, L. L. Madsen, J. Garnaes, K. Carneiro et al.: Calibration, drift elimination, and molecular structure analysis, J. Vac. Sci. Technol. B **12** (1994) 1698–1701
19.83 M. Jaschke, H. J. Butt: Height calibration of optical lever atomic force microscopes by simple laser interferometry, Rev. Sci. Instrum. **66** (1995) 1258
19.84 L. A. Nagahara, K. Hashimoto, A. Fujishima, D. Snowden-Ifft et al.: Mica etch pits as a height calibration source for atomic force microscopy, J. Vac. Sci. Technol. B **12** (1993) 1694–1697
19.85 H. M. Brodowsky, U.-C. Boehnke, F. Kremer: Wide range standard for scanning probe microscopy height calibration, Rev. Sci. Instrum. **67** (1996) 4198–4200
19.86 T. Stifter, O. Marti, B. Bhushan: Theoretical investigation of the distance dependence of capillary and

van der Waals forces in scanning force microscopy, Phys. Rev. B **62** (2000) 13667–13673
19.87 P. G. de Gennes: Wetting: Statistics and dynamics, Rev. Mod. Phys. **57** (1985) 827–863
19.88 M. Binggeli, C. M. Mate: Influence of capillary condensation of water on nanotribology studied by force microscopy, Appl. Phys. Lett. **65** (1994) 415
19.89 Y. Sugawara, M. Ohta, T. Konishi, S. Morita et al.: Effects of humidity and tip radius on the adhesive force measured with atomic force microscopy, Wear **168** (1993) 13–16
19.90 F. M. Orr, L. E. Scriven, A. P. Rivas: Pendular rings between solids: Meniscus properties and capillary force, J. Fluid Mech. **67** (1975) 723–742
19.91 X. Xiao, Q. Linmao: Investigation of humidity-dependent capillary force, Langmuir **16** (2000) 8153–8158
19.92 E. Riedo, F. Levy, H. Brune: Kinetics of capillary condensation in nanoscopic sliding friction, Phys. Rev. Lett. **88** (2002) 185505/1–4
19.93 D. Maugis, B. Gauthiermanuel: JKR-DMT transition in the presence of a liquid meniscus, J. Adhes. Sci. Technol. **8** (1994) 1311–1322
19.94 A. Fogden, L. R. White: Contact elasticity in the presence of capillary condensation. 1. The nonadhesive Hertz problem, J. Colloid Interface Sci. **138** (1990) 414
19.95 K. L. Johnson, K. Kendall, A. D. Roberts: Surface energy and the contact of elastic solids, Proc. R. Soc. London A **324** (1971) 301–313
19.96 K. Johnson, J. Greenwood: An adhesion map for the contact of elastic spheres, J. Colloid Interface Sci. **192** (1997) 326–333
19.97 K. L. Johnson: Adhesion and friction between a smooth elastic asperity and a plane surface, Proc. R. Soc. London A **453** (1997) 163
19.98 T. Thundat, X. Y. Zheng, G. Y. Chen, R. J. Warmack: Role of relative humidity in atomic force microscopy imaging, Surf. Sci. **294** (1993) 939–943
19.99 M. Binggeli, R. Christoph, H.-E. Hintermann: Observation of controlled, electrochemically induced friction force modulations in the nano-Newton range, Tribol. Lett. **1** (1995) 13
19.100 B. Bhushan, S. Sundararajan: Micro/nanoscale friction and wear mechanisms of thin films using atomic force and friction force microscopy, Acta Mater. **46** (1998) 3793–3804
19.101 W. Gulbinski, D. Pailharey, T. Suszko, Y. Mathey: Study of the influence of adsorbed water on AFM friction measurements on molybdenum trioxide thin films, Surf. Sci. **475** (2001) 149–158
19.102 M. He, A. S. Blum, D. E. Aston, C. Buenviaje et al.: Critical phenomena of water bridges in nanoasperity contacts, J. Chem. Phys. **114** (2001) 1355–1360
19.103 J. A. Greenwood, J. B. P. Williamson: Contact of nominally flat surfaces, Proc. R. Soc. London A **295** (1966) 300
19.104 K. Komvopoulous: Surface engineering and microtribology for microelectromechanical systems, Wear **200** (1996) 305–327
19.105 R. Maboudian, W. R. Ashurst, C. Carraro: Self-assembled monolayers as anti-stiction coatings for MEMS: Characteristics and recent developments, Sens. Actuators A **82** (2000) 219
19.106 R. Maboudian: Surface processes in MEMS technology, Surf. Sci. Rep. **30** (1998) 207–270
19.107 A. Noy, D. V. Vezenov, C. M. Lieber: Chemical force microscopy, Annu. Rev. Mater. Sci. **27** (1997) 381–421
19.108 H. Takano, J. R. Kenseth, S.-S. Wong, J. C. O'Brien et al.: Chemical and biochemical analysis using scanning force microscopy, Chem. Rev. **99** (1999) 2845
19.109 D. L. Sedin, K. L. Rowlen: Adhesion forces measured by atomic force microscopy in humid air, Anal. Chem. **72** (2000) 2183–2189
19.110 C. D. Frisbie, L. F. Rozsnyai, A. Noy, M. S. Wrighton et al.: Functional group imaging by chemical force microscopy, Science **265** (1994) 2071–2074
19.111 H. I. Kim, J. E. Houston: Separating mechanical and chemical contributions to molecular-level friction, J. Am. Chem. Soc. **122** (2000) 12045–12046
19.112 T. Nakagawa, K. Ogawa, T. Kurumizawa: Discriminating molecular length of chemically adsorbed molecules using an atomic force microscope having a tip covered with sensor molecules (an atomic force microscope having chemical sensing function), Jpn. J. Appl. Phys. **32** (1993) 294–296
19.113 T. Nakagawa, K. Ogawa, T. Kurumizawa: Atomic force microscope for chemical sensing, J. Vac. Sci. Techol. **B 12** (1994) 2215–2218
19.114 A. Noy, C. D. Frisbie, L. F. Rozsnyai, M. S. Wrighton et al.: Chemical force microscopy: Exploiting chemically-modified tips to quantify adhesion, friction, and functional group distributions in molecular assemblies, J. Am. Chem. Soc. **117** (1995) 7943–7951
19.115 S. K. Sinniah, A. B. Steel, C. J. Miller, J. E. Reutt-Robey: Solvent exclusion and chemical contrast in scanning force microscopy, J. Am. Chem. Soc. **118** (1996) 8925–8931
19.116 E. W. v.d. Vegte, G. Hadziioannou: Acid-base properties and the chemical imaging of surface-bound functional groups with scanning force microscopy, J. Phys. Chem. **B 101** (1997) 9563–9569
19.117 D. V. Vezenov, A. Noy, L. F. Rozsnyai, C. M. Lieber: Force titrations and ionization state sensitive imaging of functional group distributions in molecular assemblies, J. Am. Chem. Soc. **119** (1997) 2006–2015
19.118 E. W. v.d. Vegte, G. Hadziioannou: Scanning force microscopy with chemical specificity: An extensive study of chemically specific tip-surface interactions and the chemical imaging of surface functional groups, Langmuir **13** (1997) 4357–4368

19.119 L. A. Wenzler, G. L. Moyes, L. G. Olson, J. M. Harris et al.: Single-molecule bond rupture force analysis of interactions between AFM tips and substrates modified with organosilanes, Anal. Chem. **69** (1997) 2855–2861

19.120 T. Ito, M. Namba, P. Buhlmann, Y. Umezawa: Modification of silicon nitride tips with trichlorosilane self-assembled monolayers (SAMs) for chemical force microscopy, Langmuir **13** (1997) 4323–4332

19.121 L. A. Wenzler, G. L. Moyes, G. N. Raikar, R. L. Hansen et al.: Measurements of single-molecule bond rupture forces between self-assembled monolayers of organosilanes with the atomic force microscope, Langmuir **13** (1997) 3761–3768

19.122 T. Han, J. M. Williams, T. P. Beebe: Chemical bonds studied with functionalized atomic force microscopy tips, Anal. Chim. Acta **307** (1995) 365–376

19.123 V. Tsukruk, V. N. Bliznyuk: Adhesive and friction forces between chemically modified silicon and silicon nitride surfaces, Langmuir **14** (1998) 446–455

19.124 D. V. Vezenov, A. V. Zhuk, G. M. Whitesides, C. M. Likeber: Chemical force spectroscopy in heterogeneous systems: Intermolecular interactions involving epoxy polymer, mixed monolayers, and polar solvents, J. Am. Chem. Soc. **124** (2002) 10578–10588

19.125 J. E. Houston, H. I. Kim: Adhesion, friction, and mechanical properties of functionalized alkanethiol self-assembled monolayers, Accounts Chem. Res. **35** (2002) 547–553

19.126 H. I. Kim, M. Graupe, O. Oloba, T. Koini et al.: Molecularly specific studies of the frictional properties of monolayer films: A systematic comparison of CF_3–, (CH3)$_2$(CH)–, and CH_3– terminated films, Langmuir **15** (1999) 3179–3185

19.127 S. Lee, Y. S. Shon, R. Colorado, R. L. Guenard et al.: The influence of packing densities and surface order on the frictional properties of alkanethiol self-assembled monolayers (SAMs) on gold: A comparison of SAMs derived from normal and spiroalkanedithiols, Langmuir **16** (2000) 2220–2224

19.128 Y. Leng, S. Jiang: Dynamic simulations of adhesion and friction in chemical force microscopy, J. Am. Chem. Soc. **124** (2002) 11764–11770

19.129 H. Skulason, C. D. Frisbie: Detection of discrete interactiuons upon rupture of Au microcontacts to self-assembled monolayers terminated with –S(CO)CH_3 or –SH, J. Am. Chem. Soc. **122** (2000) 9750–9760

19.130 J. Zhang, J. Kirkham, C. Robinson, M. L. Wallwork et al.: Determination of the ionization state of 11-thioundecyl-1-phosphonic acid in self-assembled monolayers by chemical force microscopy, Anal. Chem. **72** (2000) 1973–1978

19.131 A. Lio, D. H. Charych, M. Salmeron: Comparative atomic force microscopy study of the chain length dependence of frictional properties of alkanethiols on gold and alkylsilanes on mica, J. Phys. Chem. **B 101** (1997) 3800

19.132 A. Lio, C. Morant, D. F. Ogletree, M. Salmeron: Atomic force microscopy study of the pressure-dependent structural and frictional properties of n-alkanethiols on gold, J. Phys. Chem. B **101** (1997) 4767–4773

19.133 G.-Y. Liu, M. Salmeron: Reversible displacement of chemisorbed n-alkane thiol molecules on Au(111) surface: An atomic force microscopy study, Langmuir **10** (1994) 367–370

19.134 X. Xiao, J. Hu, D. H. Charych, M. Salmeron: Chain length dependence of the frictional properties of alkylsilane molecules self-assembled on mica studied by atomic force microscopy, Langmuir **12** (1996) 235

19.135 A. B. Tutein, S. J. Stuart, J. A. Harrison: Indentation analysis of linear-chain hydrocarbon monolayers anchored to diamond, J. Phys. Chem. **B 103** (1999) 11357

19.136 R. L. Pizzolatto, Y. J. Yang, L. K. Wolf, M. C. Messmer: Conformational aspects of model chromatographic surfaces studied by sum-frequency generation, Anal. Chim. Acta **397** (1999) 81

19.137 E. W. v.d. Vegte, A. Subbotin, G. Hadziioannou: Nanotribological properties of unsymmetrical n-dialkyl sulfide monolayers on gold: Effect of chain length on adhesion, friction and imaging, Langmuir **16** (2000) 3249–3256

19.138 Y.-S. Lo, N. D. Huefner, W. S. Chan, F. Stevebs et al.: Specific interactions between biotin and avidin studies by atomic force microscopy using the poisson statistical analysis method, Langmuir **15** (1999) 1373–1382

19.139 Y.-S. Lo, J. Simons, T. P. Beebe, Jr.: Temperature dependence of the biotin–avidin bond rupture force studied by atomic force microscopy, J. Phys. Chem. **B 106** (2002) 9847–9857

19.140 J. H. Hoh, J. P. Cleavland, C. B. Prater, J.-P. Revel et al.: Quantitized adhesion detected with the atomic force microscope, J. Am. Chem. Soc. **114** (1992) 4917–4918

19.141 M. Grandbois, M. Beyer, M. Rief, H. Clausen-Schaumann et al.: How strong is a covalent bond?, Science **283** (1999) 1727–1730

19.142 H. Skulason, C. D. Frisbie: Contact mechanics modeling of pull-off measurements: Effect of solvent, probe radius, and chemical binding probability on the detection of single-bond rupture forces by atomic force microscopy, Anal. Chem. **74** (2002) 3096–3104

19.143 H. Schonherr, V. Chechik, C. J. M. Stirling, G. J. Vancso: Monitoring surface reactions at an AFM tip: An approach to following reaction kinetics in self-assembled monolayers on the nanometer scale, J. Am. Chem. Soc. **122** (2000) 3679–3687

19.144 M. P. L. Werts, E. W. v.d. Vegte, G. Hadziioannou: Surface chemical reactions probed with scanning force microscopy, Langmuir **13** (1997) 4939–4942

19.145 S. S. Wong, E. Joselevich, A. T. Woolley, C. Chin Li et al.: Covalently functionalized nanotubes as nanometre-sized probes in chemistry and biology, Nature **394** (1998) 52–55

19.146 S. S. Wong, A. T. Woolley, E. Joselevich, C. L. Cheung et al.: Covalently-functionalized single-walled carbon nanotube tips for chemical force microscopy, J. Am. Chem. Soc. **120** (1998) 8557–8558

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

20. Friction and Wear on the Atomic Scale

Friction is an old subject of research: the empirical da Vinci–Amontons laws are common knowledge. Macroscopic experiments systematically performed by the school of *Bowden* and *Tabor* have revealed that macroscopic friction can be related to the collective action of small asperities. During the last 15 years, experiments performed with the atomic force microscope gave new insight into the physics of single asperities sliding over surfaces. This development, together with complementary experiments by means of surface force apparatus and quartz microbalance, established the new field of nanotribology. At the same time, increasing computing power allowed for the simulation of the processes in sliding contacts consisting of several hundred atoms. It became clear that atomic processes cannot be neglected in the interpretation of nanotribology experiments. Experiments on even well-defined surfaces directly revealed atomic structures in friction forces. This chapter will describe friction force microscopy experiments that reveal, more or less directly, atomic processes in the sliding contact.

We will begin by introducing friction force microscopy, including the calibration of cantilever force sensors and special aspects of the ultra-high vacuum environment. The empirical Tomlinson model largely describes atomic stick-slip results and is therefore presented in detail. We review experimental results regarding atomic friction. These include thermal activation, velocity dependence, as well as temperature dependence. The geometry of the contact plays a crucial role in the interpretation of experimental results, as we will demonstrate, for example, for the calculation of the lateral contact stiffness. The onset of wear on atomic scale has recently come into the scope of experimental studies and is described here. In order to compare the respective results, we present molecular dynamics simulations that are directly related to atomic friction experiments. We close the chapter with a discussion of dissipation measurements performed in noncontact force microscopy, which may become an important complementary tool for the study of mechanical dissipation in nanoscopic devices.

20.1 **Friction Force Microscopy in Ultra-High Vacuum** 632
  20.1.1 Friction Force Microscopy 632
  20.1.2 Force Calibration 632
  20.1.3 The Ultra-high Vacuum Environment 635
  20.1.4 A Typical Microscope in UHV 635

20.2 **The Tomlinson Model** 636
  20.2.1 One-dimensional Tomlinson Model 636
  20.2.2 Two-dimensional Tomlinson Model 637
  20.2.3 Friction Between Atomically Flat Surfaces ... 637

20.3 **Friction Experiments on Atomic Scale** 638
  20.3.1 Anisotropy of Friction 642

20.4 **Thermal Effects on Atomic Friction** 642
  20.4.1 The Tomlinson Model at Finite Temperature 642
  20.4.2 Velocity Dependence of Friction 644
  20.4.3 Temperature Dependence of Friction 645

20.5 **Geometry Effects in Nanocontacts** 646
  20.5.1 Continuum Mechanics of Single Asperities 646
  20.5.2 Load Dependence of Friction 647
  20.5.3 Estimation of the Contact Area 647

20.6 **Wear on the Atomic Scale** 649
  20.6.1 Abrasive Wear on the Atomic Scale . 649
  20.6.2 Wear Contribution to Friction 650

20.7 **Molecular Dynamics Simulations of Atomic Friction and Wear** 651
  20.7.1 Molecular Dynamics Simulation of Friction Processes 651
  20.7.2 Molecular Dynamics Simulations of Abrasive Wear 652

20.8 **Energy Dissipation in Noncontact Atomic Force Microscopy** .. 654

20.9 **Conclusion** 656

References 657

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

20.1 Friction Force Microscopy in Ultra-High Vacuum

The *friction force microscope* (FFM, also called lateral force microscope, LFM) exploits the interaction of a sharp tip sliding on a surface to quantify dissipative processes down to the atomic scale (Fig. 20.1).

20.1.1 Friction Force Microscopy

The relative motion of tip and surface is realized by a *scanner* formed by piezoelectric elements, which moves the surface perpendicularly to the tip with a certain periodicity. The scanner can be also extended or retracted in order to vary the normal force, F_{N}, which is applied on the surface. This force is responsible for the deflection of the *cantilever* that supports the tip. If the normal force F_{N} increases while scanning due to the local slope of the surface, the scanner is retracted by a feedback loop. On the other hand, if F_{N} decreases, the surface is brought closer to the tip by extending the scanner. In such way, the surface topography can be determined line by line from the vertical displacement of the scanner. An accurate control of such vertical movement is made possible by a light beam, which is reflected from the rear of the lever into a photodetector. When the bending of the cantilever changes, the light spot on the detector moves up or down and causes a variation of the photocurrent that corresponds to the normal force F_{N} to be controlled.

Usually the relative sliding of tip and surface is also accompanied by *friction*. A lateral force, F_{L}, with the opposite direction of the scan velocity, v, hinders the motion of the tip. This force provokes the torsion of the cantilever, and it can be observed with the topography if the photodetector can reveal not only the normal deflection but also the lateral movement of the lever while scanning. In practice this is realized by four-quadrants photodetectors, as shown in Fig. 20.1. We should notice that friction forces also cause the lateral bending of the cantilever, but this effect is negligible if the thickness of the lever is much less than the width.

The FFM was first used by *Mate* et al. in 1987 to reveal friction with atomic features [20.1], i. e. just one year after *Binnig*, *Quate*, and *Gerber* introduced the atomic force microscope [20.2]. In their experiment, Mate used a tungsten wire and a slightly different technique to detect lateral forces (non-fiber interferometry). The optical beam deflection was introduced later by *Marti* et al., and *Meyer* et al. [20.3, 4]. Other methods to measure the forces between tip and surface are given by capacitance detection [20.5], dual fiber interferometry [20.6], and piezolevers [20.7]. In the first method, two plates close to the cantilever reveal capacitance while scanning. The second technique uses two optical fibers to detect the cantilever deflection along two orthogonal directions angled 45° with respect to the surface normal. Finally, in the third method, cantilevers with two Wheatstone bridges at their base reveal normal and lateral forces, which are respectively proportional to the sum and the difference of both bridge signals.



Fig. 20.1 Schematic diagram of a beam-deflection friction force microscope

20.1.2 Force Calibration

The force calibration is relatively simple if rectangular cantilevers are used. Due to possible discrepancies with the geometric values provided by manufacturers, one should use optical and electron microscopes to determine the width, thickness, and length of cantilever, w, t, l, the tip height, h, and the position of the tip with respect to the cantilever. The thickness of the cantilever can also be determined from the resonance frequency of the lever, f_0, using the relation [20.8]:

$$t = \frac{2\sqrt{12}\pi}{1.875^2}\sqrt{\frac{\rho}{E}}f_0 l^2 , \tag{20.1}$$

In (20.1) ρ is the density of the cantilever and E is its Young's modulus. The normal spring constant, c_N, and the lateral spring constant, c_L, of the lever are given by

$$c_\mathrm{N} = \frac{Ewt^3}{4l^3} , \quad c_\mathrm{L} = \frac{Gwt^3}{3h^2 l} , \tag{20.2}$$

where G is the shear modulus. Figure 20.2 shows some SEM images of rectangular silicon cantilevers used for FFM. In the case of silicon, $\rho = 2.33\times10^3\,\mathrm{kg/m^3}$, $E = 1.69\times10^{11}\,\mathrm{N/m^2}$ and $G = 0.5\times10^{11}\mathrm{N/m^2}$. Thus, for the cantilever in Fig. 20.2, $c_\mathrm{N} = 1.9\,\mathrm{N/m}$ and $c_\mathrm{L} = 675\,\mathrm{N/m}$.

The next step in force calibration consists of measuring the sensitivity of the photodetector, S_z (nm/V). For beam-deflection FFMs, the sensitivity S_z can be determined by force vs. distance curves measured on hard surfaces (e.g., $\mathrm{Al_2O_3}$), where elastic deformations are negligible and the vertical movement of the scanner equals the deflection of the cantilever. A typical relation between the difference of the vertical signals on the four-quadrant detector, V_N, and the distance from the surface, z, is sketched in Fig. 20.3. When the tip is approached, no signal is revealed until the tip jumps into contact at $z = z_1$. Further extension or retraction of the scanner results in an elastic behavior until the tip jumps again out of contact at a distance $z_2 > z_1$. The slope of the elastic part of the curve gives the required sensitivity, S_z.

The normal and lateral forces are related to the voltage V_N, and the difference between the horizontal signals, V_L, as follows:

$$F_\mathrm{N} = c_\mathrm{N} S_z V_\mathrm{N} , \quad F_\mathrm{L} = \frac{3}{2} c_\mathrm{L} \frac{h}{l} S_z V_\mathrm{L} , \tag{20.3}$$

in which it is assumed that the light beam is positioned above the probing tip.



Fig. 20.3 Sketch of a typical force vs. distance curve

The normal spring constant c_N can also be calibrated with alternative methods. *Cleveland* et al. [20.10] attached tungsten spheres to the tip, which changes the resonance frequency f_0 according to the formula

$$f_0 = \frac{1}{2\pi}\sqrt{\frac{c_\mathrm{N}}{M + m^*}} . \tag{20.4}$$

M is the mass of the added object, and m^* is an effective mass of the cantilever, which depends on its geometry [20.10]. The spring constant can be extrapolated from the frequency shifts corresponding to the different masses attached.

As an alternative, *Hutter* et al. observed that the spring constant c_N can be related to the area of the power spectrum of the thermal fluctuations of the cantilever, P [20.11]. The correct relation is $c_\mathrm{N} = 4k_\mathrm{B}T/3P$, where $k_\mathrm{B} = 1.38\times10^{-3}\,\mathrm{J/K}$ is the Boltzmann's constant and T is the temperature [20.12].



Fig. 20.2 SEM images of a rectangular cantilever. The relevant dimensions are $l = 445\,\mu\mathrm{m}$, $w = 43\,\mu\mathrm{m}$, $t = 4.5\,\mu\mathrm{m}$, $h = 14.75\,\mu\mathrm{m}$. Note that h is given by the sum of the tip height and half of the cantilever thickness. (After [20.9])

Cantilevers with different shape require finite element analysis, although in few cases analytical formulas can be derived. For V-shaped cantilevers, *Neumeister* et al. found the following approximation for the lateral spring constant c_{L} [20.13]:

$$c_{\mathrm{L}} = \frac{Et^3}{3(1+\nu)h^2} \times \left(\frac{1}{\tan\alpha} \ln \frac{w}{d \sin\alpha} + \frac{L\cos\alpha}{w} - \frac{3\sin 2\alpha}{8} \right)^{-1} , \tag{20.5}$$

where the geometrical quantities L, w, α, d, t, and h are defined in Fig. 20.4. The expression for the normal constant is more complex and can be found in the cited reference.



Fig. 20.5 Silicon grating formed by alternated faces angled ±55° (courtesy Silicon-MDT Ltd., POB 50, 103305, Moscow, Russia)

Surfaces with well-defined profiles provide an alternative in situ calibration of lateral forces [20.14]. We present a slightly modified version of the method [20.15]. Figure 20.5 shows a commercial grating formed by alternated faces with opposite inclinations with respect to the scan direction. When the tip slides on the inclined planes, the normal force, F_{N}, and the lateral force, F_{L}, with respect to the surface, are different from the two components $F_{\perp}$ and $F_{\parallel}$, which are separated by the photodiode (see Fig. 20.6a).



Fig. 20.4 Geometry of a V-shaped cantilever. (After [20.13])

If the linear relation $F_{\mathrm{L}} = \mu F_{\mathrm{N}}$ holds (see Sect. 20.5), the component $F_{\parallel}$ can be expressed in terms of $F_{\perp}$:

$$F_{\parallel} = \frac{\mu + \tan\theta}{1 - \mu\tan\theta} F_{\perp} . \tag{20.6}$$

The component $F_{\perp}$ is kept constant by the feedback loop. The sum and the difference of $F_{\parallel}$ on the two planes (1) and (2) are given by

$$F_{+} \equiv F_{\parallel}^{(1)} + F_{\parallel}^{(2)} = \frac{2\mu\left(1+\tan^2\theta\right)}{1-\mu^2\tan^2\theta} F_{\perp}$$

$$F_{-} \equiv F_{\parallel}^{(1)} - F_{\parallel}^{(2)} = \frac{2\left(1+\mu^2\right)\tan\theta}{1-\mu^2\tan^2\theta} F_{\perp} . \tag{20.7}$$

The values of F_{+} and F_{-} (in volts) can be measured by scanning the profile back and forth (Fig. 20.6b). If F_{+} and F_{-} are recorded with different values of $F_{\perp}$, one can determine the conversion ratio between volts and nanonewtons as well as the coefficient of friction, μ.



Fig. 20.6 **(a)** Forces acting on a FFM tip sliding on the grating in Fig. 20.5; **(b)** Friction loops acquired on the two faces

An accurate analysis of the errors in lateral force calibration was given by *Schwarz* et al., who revealed the important role of the cantilever's oscillations induced by the feedback loop and of the so-called pull-off force (Sect. 20.5) in friction measurements, aside from the geometrical setting of cantilevers and laser beams [20.16].

For some applications, an adequate estimation of the radius of curvature of the tip, R, is important (Sect. 20.5.2). This quantity can be evaluated with a scanning electron microscope. Otherwise, well-defined structures as step sites [20.17, 18] or whiskers [20.19] can be imaged. The image of these high-aspect ratio structures is a convolution with the tip structure. A deconvolution algorithm that allows for the extraction of the probing tip's radius of curvature was suggested by *Villarrubia* [20.21].

20.1.3 The Ultra-high Vacuum Environment

Atomic friction studies require well-defined surfaces and – whenever possible – tips. For the surfaces, the established methods of surface science can be employed working in ultra-high vacuum (UHV). Ionic crystals such as NaCl have become standard materials for friction force microscopy on atomic scale. Atomically clean and flat surfaces can be prepared by cleavage in UHV. The crystal has to be heated to about 150 °C for 1 h in order to remove charging after the cleavage process. Metal surfaces can be cleaned and flattened by cycles of sputtering with argon ions and annealing. Even surfaces prepared in air or liquids like self-assembled molecular monolayers can be transferred into the vacuum and studied after careful heating procedures, which remove water layers.

Tip preparation in UHV is a more difficult subject. Most force sensors for friction studies have silicon nitride or pure silicon tips. Tips can be cleaned and oxide layers removed by sputtering with argon ions. But the sharpness of the tip is normally reduced by sputtering. As an alternative, tips can be etched in fluoric acid directly before transfer to the UHV. The significance of tip preparation is limited by the fact that the chemical and geometrical structure of the tip can undergo significant changes when sliding over the surface.

The implementation of the friction force microscope into UHV requires some additional efforts. First of all, only materials with a low vapor pressure can be used, thereby excluding most plastics and lubricants. Beam-deflection type force microscopes employ either a light source in the vacuum chamber or an optical fiber guiding the light into the chamber. The positioning of the light beam onto the cantilever and of the reflected beam onto the position-sensitive detector is performed by motorized mirrors [20.20] or by moving light source or detector [20.22]. Furthermore, a motorized sample approach has to be realized.

The quality force sensor's electrical signal can seriously deteriorate on the way out of the vacuum chamber. Low noise and high bandwidth can be preserved by implementing a pre-amplifier into the vacuum. Again the choice of materials for print and devices is limited by the condition of low vapor pressure. Stronger heating of the electrical circuitry in vacuum, therefore, must be considered.

20.1.4 A Typical Microscope in UHV

A typical AFM for UHV application is shown in Fig. 20.7. The housing (1) contains the light source and a set of lenses that focus the light onto the cantilever. Alternatively, the light can be guided via an optical fiber into the vacuum. By using light emitting diodes with low coherency you avoid disturbing interference effects often found in instruments equipped with lasers as light source. A plane mirror fixed on the spherical rotor of a first stepping motor (2) can be rotated



Fig. 20.7 Schematic view of the UHV-AVM realized at the University of Basel. (After [20.20])

around a vertical and horizontal axis to guide the light beam onto the rear of the cantilever, mounted on a removable carrier plate (3). The light is reflected off the cantilever toward a second motorized mirror (4) that guides the beam to the center of the quadrant photodiode (5), where the light is then converted into four photo-currents. Four pre-amplifiers in close vicinity to the photodiode allow low-noise measurements with 3 MHz bandwidth.

The two motors with spherical rotors, used to realign the light path after exchange of the cantilever, work as *inertial stepping motors*: the sphere is resting on three piezoelectric legs that can be moved by a small amount tangentially to the sphere. Each step of the motor consists of a slow forward motion of two legs followed by an abrupt jump backwards. During the slow forward motion the sphere follows the legs due to friction, whereas it cannot follow the sudden jump due to its inertia. A series of such tiny steps rotates the sphere macroscopically.

The sample, also on an exchangeable carrier plate, is mounted on the end of a tube scanner (6), which can move the sample in three dimensions over several micrometers. The whole scanning head (7) is the slider of a third inertial stepping motor for coarse positioning of the sample. It rests with its flat and polished bottom on three supports. Two of them are symmetrically placed piezoelectric legs (8), whereas the third central support is passive. The slider (7) can be translated in two dimensions and rotated about a vertical axis by several millimeters (rotation is achieved by antiparallel operation of the two legs). The slider is held down by two magnets, close to the active supports, and its travel is limited by two fixed posts (9) that also serve as cable attachments. The whole platform is suspended by four springs. A ring of radial copper lamellae (10), floating between a ring of permanent magnets (11) on the base flange, acts as efficient eddy current damping.

20.2 The Tomlinson Model

In Sect. 20.3, we will show that the FFM can reveal friction forces down to the atomic scale, which are characterized by a typical sawtooth pattern. This phenomenon can be seen as a consequence of a *stick-slip* mechanism, first discussed by *Tomlinson* in 1929 [20.23].

20.2.1 One-dimensional Tomlinson Model

In the Tomlinson model the motion of the tip is influenced by both the interaction with the atomic lattice of the surface and the elastic deformations of the cantilever. The shape of the tip-surface potential, $V(\boldsymbol{r})$, depends on several factors, such as the chemical composition of the materials in contact and the atomic arrangement at the tip end. For the sake of simplicity, we will start the analysis in the one-dimensional case considering a sinusoidal profile with the periodicity of the atomic lattice, a, and a peak-to-peak amplitude E_0. In Sect. 20.5, we will show how the elasticity of the cantilever and of the contact area are described in a unique framework by introducing an effective lateral spring constant, k_{eff}. If the cantilever moves with a constant velocity v along the x direction, the total energy of the system is

$$E_{\text{tot}}(x,t) = -\frac{E_0}{2}\cos\frac{2\pi x}{a} + \frac{1}{2}k_{\text{eff}}(vt-x)^2 \,. \quad (20.8)$$

Figure 20.8 shows the energy profile $E_{\text{tot}}(x,t)$ at two different instants. When $t = 0$ the tip is localized in the absolute minimum of E_{tot}. This minimum increases with time due to the cantilever motion, until the tip position becomes unstable when $t = t^*$.

At a given time t the position of the tip can be determined by equating to zero the first derivative of $E_{\text{tot}}(x,t)$ with respect to x:

$$\frac{\partial E_{\text{tot}}}{\partial x} = \frac{\pi E_0}{a}\sin\frac{2\pi x}{a} - k_{\text{eff}}(vt-x) = 0 \,. \quad (20.9)$$

The critical position x^* corresponding to $t = t^*$ is determined by equating to zero the second derivative



Fig. 20.8 Energy profile experienced by the FFM tip (*black circle*) at $t = 0$ (*dotted line*) and $t = t^*$ (*continuous line*)

$\partial^2 E_{\text{tot}}(x,t)/\partial x^2$, which gives

$$x^* = \frac{a}{4}\arccos\left(-\frac{1}{\gamma}\right), \quad \gamma = \frac{2\pi^2 E_0}{k_{\text{eff}} a^2} . \tag{20.10}$$

The coefficient γ compares the strength of interaction between tip and surface with the stiffness of the system. When $t = t^*$ the tip suddenly *jumps* into the next minimum of the potential profile. The lateral force $F^* = k_{\text{eff}}(vt - x^*)$, which induces the jump, can be evaluated from (20.9) and (20.10):

$$F^* = \frac{k_{\text{eff}}\, a}{2\pi}\sqrt{\gamma^2 - 1} . \tag{20.11}$$

Thus the stick-slip is observed only if $\gamma > 1$, i. e. when the system is not too stiff or the tip–surface interaction is strong enough. Figure 20.9 shows the lateral force F_L as a function of the cantilever position, X. When the cantilever is moved rightward, the lower part of the curve in Fig. 20.9 is obtained. If, at a certain point, the cantilever's direction of motion is suddenly inverted, the force has the profile in the upper part of the curve. The area of the *friction loop* obtained by scanning back and forth gives the total energy dissipated.

20.2.2 Two-dimensional Tomlinson Model

In two dimensions, the energy of our system is given by

$$E_{\text{tot}}(\boldsymbol{r}, t) = U(\boldsymbol{r}) + \frac{k_{\text{eff}}}{2}(\boldsymbol{v}t - \boldsymbol{r})^2 , \tag{20.12}$$

where $\boldsymbol{r} \equiv (x, y)$ and $\boldsymbol{v}$ is arbitrarily oriented on the surface (note that $\boldsymbol{v} \neq \mathrm{d}\boldsymbol{r}/\mathrm{d}t$!). Figure 20.10 shows the total energy corresponding to a periodic potential of the form

$$U(x, y, t) = -\frac{E_0}{2}\left(\cos\frac{2\pi x}{a} + \cos\frac{2\pi y}{a}\right) + E_1 \cos\frac{2\pi x}{a}\cos\frac{2\pi y}{a} . \tag{20.13}$$



Fig. 20.9 Friction loop obtained by scanning back and forth in the 1-D Tomlinson model. The effective spring constant k_{eff} is the slope of the sticking part of the loop (if $\gamma \gg 1$)

The equilibrium condition becomes

$$\nabla E_{\text{tot}}(\boldsymbol{r}, t) = \nabla U(\boldsymbol{r}) + k_{\text{eff}}(\boldsymbol{r} - \boldsymbol{v}t) = 0 . \tag{20.14}$$

The stability of the equilibrium can be discussed introducing the Hessian matrix

$$H = \begin{pmatrix} \dfrac{\partial^2 U}{\partial x^2} + k_{\text{eff}} & \dfrac{\partial^2 U}{\partial x \partial y} \\ \dfrac{\partial^2 U}{\partial y \partial x} & \dfrac{\partial^2 U}{\partial y^2} + k_{\text{eff}} \end{pmatrix} . \tag{20.15}$$

When both eigenvalues $\lambda_{1,2}$ of the Hessian are positive, the position of the tip is stable. Figure 20.11 shows such regions for a potential of the form (20.13). The tip follows the cantilever adiabatically as long as it remains in the (++)-region. When the tip is dragged to the border of the region, it suddenly jumps into the next (++)-region. A comparison between a theoretical friction map deduced from the 2-D Tomlinson model and an experimental map acquired by UHV-FFM is given in the next section.

20.2.3 Friction Between Atomically Flat Surfaces

So far we have implicitly assumed that the tip is terminated by only one atom. It is also instructive to consider the case of a periodic surface sliding on another periodic surface. In the Frenkel–Kontorova–Tomlinson (FKT) model, the atoms of one surface are harmonically coupled with their nearest neighbors. We will restrict ourselves to the case of quadratic symmetries, with lattice constants a_1 and a_2 for the upper and lower surface, respectively (Fig. 20.12). In such context the role of *commensurability* is essential. It is well known that any real number z can be represented as a continued



Fig. 20.10 Energy landscape experienced by the FFM tip in 2-D



Fig. 20.11 Regions on the tip plane labeled according to the signs of the eigenvalues of the Hessian matrix. (After [20.24])



Fig. 20.12 The FKT model in 2-D. (After [20.25])



Fig. 20.13 Friction as a function of the sliding angle φ in the 2-D FKT model. (After [20.25])

fraction:

$$z = N_0 + \frac{1}{N_1 + \frac{1}{N_2 + \dots}} \, . \qquad (20.16)$$

The sequence that converges most slowly is obtained when all $N_i = 1$, which corresponds to the *golden mean* $\bar{z} = (\sqrt{5} - 1)/2$. In 1-D *Weiss* and *Elmer* predicted that friction should decrease with decreasing commensurability, the minimum of friction being reached when $a_1/a_2 = \bar{z}$ [20.26].

In 2-D *Gyalog* and *Thomas* studied the case $a_1 = a_2$, with a misalignment between the two lattices given by an angle θ [20.25]. When the sliding direction changes, friction also varies from a minimum value corresponding to the sliding angle $\varphi = \theta/2$ to a maximum value, which is reached when $\varphi = \theta/2 + \pi/4$ (Fig. 20.13). The misfit angle θ is related with commensurability. Since the misfit angles giving rise to commensurate structure form a dense subset, the dependence of friction on θ should be discontinuous. The numerical simulations performed by Gyalog are in agreement with this conclusion.

20.3 Friction Experiments on Atomic Scale

Figure 20.14 shows the first friction map observed by Mate on atomic scale. The periodicity of the lateral force is the same as of the atomic lattice of graphite. The series of friction loops in Fig. 20.15 reveals the stick-slip effect discussed in the previous section. The applied loads are in the range of tens of μN. According to the continuum models discussed in Sect. 20.5 these values correspond to contact diameters of 100 nm. A possible explanation for the atomic features observed at such high loads is that graphite flakes might have been detached from the surface and adhered on the tip [20.27]. Another explanation is that the contact between tip and surface consisted of few nm-scale asperities and the corrugation was not entirely averaged out while sliding. The load dependence of friction found by Mate is rather linear, with a small friction coefficient $\mu = 0.01$ (Fig. 20.16).

The UHV environment reduces the influence of contaminants on the surface and leads to more precise and reproducible results. *Meyer* et al. [20.28] obtained



Fig. 20.14 First atomic friction map acquired on graphite with a normal force $F_N = 56\,\mu N$. Frame size: 2 nm. (After [20.1])



Fig. 20.15a–c Friction loops on graphite acquired with **(a)** $F_N = 7.5\,\mu N$, **(b)** $24\,\mu N$ and **(c)** $75\,\mu N$. (After [20.1])



Fig. 20.16 Load dependence of friction on graphite. (After [20.1])

a series of interesting results on ionic crystals using the UHV-FFM apparatus described in Sect. 20.1.4. In Fig. 20.17 a friction map recorded on KBr(100) is compared with a theoretical map, which was obtained with the 2-D-Tomlinson model. The periodicity $a = 0.47$ nm corresponds to the spacing between equally charged ions. No individual defects were observed. One possible reason is that the contact realized by the FFM tip is always formed by many atoms, which superimpose and average their effects. Molecular dynamics (MD) calculations (Sect. 20.7) show that even a single-atom contact may cause rather large stresses in the sample, which lead to the motion of defects far away from the contact area. In a picturesque frame, we can say that "defects behave like dolphins that swim away in front of an ocean cruiser" [20.28].

Lüthi et al. [20.29] detected atomic-scale friction even on the reconstructed Si(111)7×7 surface. But uncoated Si-tips and tips coated with Pt, Au, Ag, Cr, Pt/C damaged the sample irreversibly, and the observation of atomic features was achieved only after coating the tips with polytetrafluoroethylene (PTFE), which has lubricant properties and does not react with the dangling bonds of Si(111)7×7 (Fig. 20.18).

Recently friction could be resolved on atomic scale even on metallic surfaces in UHV [20.30]. In Fig. 20.19a a reproducible stick-slip process on Cu(111) is shown.



Fig. 20.17 **(a)** Measured and **(b)** theoretical friction map on KBr(100). (After [20.31])



Fig. 20.18 **(a)** Topography and **(b)** friction image of Si(111)7×7 measured with a PTFE coated Si-tip. (After [20.29])



Fig. 20.19a,b Friction images of **(a)** Cu(111) and **(b)** Cu(100). Frame size: 3 nm. (After [20.34])

Sliding on the (100) surface of copper produced irregular patterns, although atomic features were recognized even in this case (Fig. 20.19b). Molecular dynamics suggests that wear should occur more easily on the Cu(100) surface than on the closed packed Cu(111) (Sect. 20.7). This conclusion was achieved by adopting copper tips in computer simulations. The assumption that the FFM tip used in the experiments was covered by copper is supported by current measurements performed at the same time.

Atomic stick-slip on diamond was observed by *Germann* et al. with an apposite diamond tip prepared by chemical vapor deposition [20.32] and, a few years later, by *van der Oetelaar* et al. [20.33] with standard silicon tips. The values of friction have huge discrepancies corresponding to the presence or absence of hydrogen on the surface.

Fujisawa et al. [20.35] measured friction on mica and on MoS_2 with a 2-D-FFM apparatus, which could also reveal forces perpendicular to the scan direction. The features in Fig. 20.20 correspond to a zig-zag walk of the tip, which is predicted by the 2-D-Tomlinson model [20.36]. The 2-D stick-slip on NaF was detected with normal forces below 14 nN, whereas loads up to 10 µN could be applied on layered materials. The contact between tip and NaF was thus formed by one or a few atoms. The zig-zag walk on mica was also observed by *Kawakatsu* et al. using an original 2-D-FFM with two laser beams and two quadrant photodetectors [20.37].



Fig. 20.20 **(a)** Friction force on MoS_2 acquired by scanning along the cantilever and **(b)** across the cantilever. **(c)** Motion of the tip on the sample. (After [20.35])


a)
– 0.5
– 0.7
– 0.9
– 1.1
θ
Scan
direction
b)
– 0.5
– 0.7
– 0.9
– 1.1

Fig. 20.21 Friction images of a thiolipid monolayer on a mica surface. (After [20.38])

Fig. 20.22 Sequence of topography images of C_{60} islands on NaCl(100). (After [20.39])


a)
[10]
[100]
[1$\bar{1}$0]
I
200 nm
b)
c)
d)
e)
f)
g)
h)

20.3.1 Anisotropy of Friction

The importance of the misfit angle in the reciprocal sliding of two flat surfaces was first observed experimentally by *Hirano* et al. in the contact of two mica sheets [20.41]. Friction increased when the two surfaces formed commensurate structures, in agreement with the discussion in Sect. 20.2.3. In more recent measurements with a monocrystalline tungsten tip on Si(001), *Hirano* et al. observed *superlubricity* in the incommensurate case [20.42].

Overney et al. [20.43] studied the effects of friction anisotropy on a bilayer lipid film. In such case different molecular alignments resulted in significant variation of friction. Other measurements of friction anisotropy on stearic acid single crystals were reported by *Takano* and *Fujihira* [20.44].

Liley et al. [20.38] observed flower-shaped islands of a lipid monolayer on mica, which consisted of domains with different molecular orientation (Fig. 20.21). The angular dependence of friction reflects the tilt direction of the alkyl chains of the monolayer, which was revealed by other techniques.

Lüthi et al. [20.39] used the FFM tip to move C_{60} islands, which slided on sodium chloride in UHV without disruption (Fig. 20.22). In this experiment friction was found to be independent of the sliding direction. This was not the case in other experiments performed by *Sheehan* and *Lieber*, who observed that the misfit angle is relevant when MoO_3 islands are dragged on the MoS_2 surface [20.45]. In these experiments, sliding was possible only along low index directions. The weak orientation dependence found by *Lüthi* et al. [20.39] is probably due to the large mismatch of C_{60} on NaCl.



Fig. 20.23 Friction force experienced as a carbon nanotube is rotated into (*left trace*) and out of (*right trace*) commensurate contact. (After [20.40])

A recent example of friction anisotropy is related to carbon nanotubes. *Falvo* et al. [20.40] manipulated nanotubes on graphite using a FFM tip (Fig. 20.23). A dramatic increase of the lateral force was found in the directions corresponding to commensurate contact. At the same time, the nanotube motion changed from sliding/rotating to stick-roll.

20.4 Thermal Effects on Atomic Friction

Although the Tomlinson model gives a good interpretation of the basic mechanism of the atomic stick-slip discussed in Sect. 20.2, it cannot explain some minor features observed in the atomic friction. For example, Fig. 20.24 shows a friction loop acquired on NaCl(100). The peaks in the sawtooth profile have different heights, which is in contrast to the result in Fig. 20.9. Another effect is observed if the scan velocity v is varied: the mean friction force increases with the logarithm of v (Fig. 20.25). This effect cannot be interpreted within the mechanical approach in Sect. 20.2 without further assumptions.

20.4.1 The Tomlinson Model at Finite Temperature

Let us focus again on the energy profile discussed in Sect. 20.2.1. For sake of simplicity, we will assume that $\gamma \gg 1$. At a given time $t < t^*$, the tip jump is prevented by the energy barrier $\Delta E = E(x_{\max}, t) - E(x_{\min}, t)$, where $x_{\max}$ corresponds to the first maximum observed in the energy profile and $x_{\min}$ is the actual position of the tip (Fig. 20.26). The quantity ΔE decreases with time or, equivalently, with the frictional force F_L until it vanishes when $F_L = F^*$ (Fig. 20.27). Close to the critical



Fig. 20.24 Friction loop on NaCl(100). (After [20.46])



Fig. 20.25 Mean friction force vs. scanning velocity on NaCl(100) at $F_N = 0.44$nN (+) and $F_N = 0.65$nN (×). (After [20.46])

point the energy barrier can be written approximately as

$$\Delta E = \lambda(\tilde{F} - F_L) , \tag{20.17}$$

where $\tilde{F}$ is close to the critical value $F^* = \pi E_0/a$.

At finite temperature T, the lateral force required to induce a jump is lower than F^*. To estimate the most probable value of F_L at this point, we first consider the probability p that the tip does *not* jump. The probability p changes with time t according to the master equation

$$\frac{\mathrm{d}p(t)}{\mathrm{d}t} = -f_0 \exp\left(-\frac{\Delta E(t)}{k_B T}\right) p(t) , \tag{20.18}$$



Fig. 20.26 Energy barrier that hinders the tip jump in the Tomlinson model



Fig. 20.27 Energy barrier ΔE as a function of the lateral force F_L. The *dashed line* close to the critical value corresponds to the linear approximation (20.17)

where f_0 is a characteristic frequency of the system. The physical meaning of this frequency is discussed in Sect. 20.4.2. We should note that the probability of a reverse jump is neglected, since in this case the energy barrier to overcome is much higher than ΔE. If time is replaced by the corresponding lateral force, the master equation becomes

$$\frac{\mathrm{d}p(F_L)}{\mathrm{d}F_L} = -f_0 \exp\left(-\frac{\Delta E(F_L)}{k_B T}\right)\left(\frac{\mathrm{d}F_L}{\mathrm{d}t}\right)^{-1} p(F_L) . \tag{20.19}$$

At this point, we substitute

$$\frac{\mathrm{d}F_L}{\mathrm{d}t} = \frac{\mathrm{d}F_L}{\mathrm{d}X}\frac{\mathrm{d}X}{\mathrm{d}t} = k_{\mathrm{eff}} v \tag{20.20}$$

and use the approximation (20.17). The maximum probability transition condition $\mathrm{d}^2 p(F)/\mathrm{d}F^2 = 0$ then yields

$$F_L(v) = F^* - \frac{k_B T}{\lambda} \ln \frac{v_c}{v} \tag{20.21}$$

with

$$v_c = \frac{f_0 k_B T}{k_{\mathrm{eff}} \lambda} . \tag{20.22}$$

Thus the lateral force depends logarithmically on the sliding velocity, as observed experimentally. But the approximation (20.17) does not hold when the tip jump occurs very close to the critical point $x = x^*$, which is the case at high velocities. In this instance, the factor $(\mathrm{d}F_\mathrm{L}/\mathrm{d}t)^{-1}$ in (20.19) is small and, consequently, the probability $p(t)$ does not change significantly until it suddenly approaches 1 when $t \to t^*$. Thus friction is constant at high velocities, in agreement with the classical Coulomb's law of friction [20.28].

Sang et al. [20.48] observed that the energy barrier close to the critical point is better approximated by a relation like

$$\Delta E = \mu (F^* - F_\mathrm{L})^{3/2} . \tag{20.23}$$

The same analysis performed using the approximation (20.23) instead of (20.17) leads to the expression [20.49]

$$\frac{\mu (F^* - F_\mathrm{L})^{3/2}}{k_\mathrm{B} T} = \ln \frac{v_\mathrm{c}}{v} - \ln \sqrt{1 - \frac{F^*}{F_\mathrm{L}}} , \tag{20.24}$$

where the critical velocity v_c is now

$$v_\mathrm{c} = \frac{\pi\sqrt{2}}{2} \frac{f_0 k_\mathrm{B} T}{k_\mathrm{eff} a} . \tag{20.25}$$

The velocity v_c discriminates between two different regimes. If $v \ll v_\mathrm{c}$ the second logarithm in (20.24) can be neglected, which leads to the logarithmic dependence

$$F_\mathrm{L}(v) = F^* - \left(\frac{k_\mathrm{B} T}{\mu}\right)^{2/3} \left(\ln \frac{v_\mathrm{c}}{v}\right)^{2/3} . \tag{20.26}$$

In the opposite case, $v \gg v_\mathrm{c}$, the term on the left in (20.23) is negligible and

$$F_\mathrm{L}(v) = F^* \left(1 - \frac{v_\mathrm{c}}{v}\right)^2 . \tag{20.27}$$

In such a case, the lateral force F_L tends to F^*, as expected.

20.4.2 Velocity Dependence of Friction

The velocity dependence of friction was studied by FFM only recently. *Zwörner* et al. observed that friction between silicon tips and diamond, graphite or amorphous carbon is constant with scan velocities of few µm/s [20.50]. Friction decreased when v is reduced below 1 µm/s. In their experiment on lipid films on mica (Sect. 20.3.1), *Gourdon* et al. [20.47] explored a range of velocities from 0.01 to 50 µm/s and found a critical velocity $v_\mathrm{c} = 3.5$ µm/s, which discriminates between an increasing friction and a constant friction regime (Fig. 20.28). Although these results were not explained with thermal activation, we argue that the previous theoretical discussion gives the correct interpretative key. A clear observation of a logarithmic dependence of friction on the micrometer scale was reported by *Bouhacina* et al., who studied friction on triethoxysilane molecules and polymers grafted on silica with sliding velocity up to $v = 300$ µm/s [20.51]. The result was explained with a thermally activated Eyring model, which does not differ significantly from the model discussed in the previous subsection [20.52, 53].



Fig. 20.28 Velocity dependence of friction on mica and on lipid films with different orientation (arms 4 and 5) and in a fluid phase. (After [20.47])

The first measurements on the atomic scale were performed by *Bennewitz* et al. on copper and sodium chloride [20.30, 46]; in both cases a logarithmic dependence of friction was revealed up to $v < 1$ µm/s (Fig. 20.25), in agreement with (20.21). Higher values of velocities were not explored, due to the limited range of the scan frequencies applicable by FFM on atomic scale. The same limitation does not allow a clear distinction between (20.21) and (20.26) in the interpretation of the experimental results.

At this point we would like to discuss the physical meaning of the characteristic frequency f_0. With lattice constants a of a few angstroms and effective spring



Fig. 20.29a,b Torsional modes of cantilever oscillations **(a)** when the tip is free and **(b)** when the tip is in contact with a surface. (After [20.54])



Fig. 20.31 Temperature dependence of friction on n-hexadecane and octamethylcyclotetrasiloxane. (After [20.56])

constants k_{eff} of about 1 N/m, which is typical in FFM experiments, (20.25) gives values of few hundreds of kHz for f_0. This is the characteristic range in which the torsional eigenfrequencies of the cantilevers are located in both contact and noncontact modes (Fig. 20.29). Future work might clarify whether or not f_0 has to be identified with these frequencies.

To conclude this paragraph, we should emphasize that the increase of friction with increasing velocity is ultimately related to the materials and the environment in which the measurements are realized. In humid environment, *Riedo* et al. observed that the surface wettability has an important role [20.55]. Friction *decreases* with increasing velocity on hydrophilic surfaces, and the rate of such decrease depends drastically on humidity. On partially hydrophobic surfaces, a logarithmic increase is found again (Fig. 20.30). These results were interpreted considering the thermally activated nucleation of water bridges between tip and sample asperities, as discussed in the cited reference.

20.4.3 Temperature Dependence of Friction

Thus far we have used thermal activation to explain the velocity dependence of friction. The same mechanism also predicts that friction should change with temperature. Master equation (20.18) shows that the probability of a tip jump is reduced at low temperatures T until it vanishes when $T = 0$. Within this limit case, thermal ac-



Fig. 20.30a,b Friction vs. sliding velocity **(a)** on hydrophobic surfaces and **(b)** on hydrophilic surfaces (After [20.55])

tivation is excluded, and the lateral force F_L is equal to F^*, independently of the scanning velocity v.

To our knowledge stick-slip processes at low temperatures have not been reported. A significant increase of the mean friction with decreasing temperature was recently measured by *He* et al. [20.56] by FFM (Fig. 20.31). Neglecting the logarithmic contributions (20.21) and (20.26) predict $(F^* - F_L) \sim T$ and $(F^* - F_L) \sim T^{2/3}$ respectively for the temperature dependence of friction. Although He et al. applied a linear fit to their data, the range of 30 K they considered is again not large enough to prove that a $T^{2/3}$ fit would be preferable.

20.5 Geometry Effects in Nanocontacts

Friction is ultimately related to the real shape of the contact between the sliding surfaces. On macroscopic scale the contact between two bodies is studied within continuum mechanics, which are all based on the elasticity theory developed by Hertz in 19th century. Various FFM experiments showed that continuum mechanics is still valid down to contact areas a few nanometers in size. Only when contact is reduced to few atoms does the continuum frame become unsuitable, and other approaches like molecular dynamics are necessary. This section will deal with continuum mechanics theory; molecular dynamics will be discussed in Sect. 20.7.

20.5.1 Continuum Mechanics of Single Asperities

The lateral force F_L between two surfaces in reciprocal motion depends on the size of the real area of contact, A, which can be a few orders of magnitude smaller than the apparent area of contact. The simplest assumption is that friction is proportional to A; the proportionality factor is called *shear strength* σ [20.57]:

$$F_L = \sigma A \,. \tag{20.28}$$

In case of plastic deformation, the asperities are compressed until the pressure, p, equals a certain yield value, p^*. The resulting contact area is thus $A = F_N/p^*$, and the well-known Amontons' law is obtained: $F_L = \mu F_N$, where $\mu = \sigma/p^*$ is the *coefficient of friction*. The same idea can be extended to contacts formed by many asperities, and it leads again to the Amontons' law. The simplicity of this analysis explains why most of the friction processes were related to plastic deformation for a long time. Such mechanism, however, should provoke a quick disruption of the surfaces, which is not observed in practice.

Elastic deformation can be easily studied in the case of a sphere of radius R pressed against a flat surface. In such case the contact area is

$$A(F_N) = \pi \left(\frac{R}{K}\right)^{2/3} F_N^{2/3} \,, \tag{20.29}$$

where $K = 3E^*/4$ and E^* is an effective Young's modulus, related to the Young's moduli, E_1 and E_2, and the Poisson's numbers, ν_1 and ν_2, of sphere and plane, by the following relation [20.58]:

$$\frac{1}{E^*} = \frac{1-\nu_1^2}{E_1} + \frac{1-\nu_2^2}{E_2} \,. \tag{20.30}$$

The result $A \propto F_N^{2/3}$ is in contrast with the Amontons' law. But a linear relation between F_L and F_N can be obtained for contacts formed by several asperities in particular cases. For example, the area of contact between a flat surface and a set of asperities with an exponential height distribution and the same radius of curvature R depends linearly on the normal force F_N [20.59]. The same conclusion holds approximately even for a Gaussian height distribution. But the hypothesis that the radii of curvature are the same for all asperities is not realistic. A general model was recently proposed by *Persson*, who derived analytically the proportionality between contact area and load for a large variety of elastoplastic contacts formed by surfaces with arbitrary roughness [20.60]. The discussion is not straightforward and goes beyond the purposes of this section.

Further effects are observed if adhesive forces between the asperities are taken into account. If the range of action of these forces is smaller than the elastic deformation, (20.29) is extended to the Johnson–Kendall–Roberts (JKR) relation

$$A(F_N) = \pi \left(\frac{R}{K}\right)^{2/3} \times \left(F_N + 3\pi\gamma R + \sqrt{6\pi\gamma R F_N + (3\pi\gamma R)^2}\right)^{2/3} \,, \tag{20.31}$$

where γ is the surface tension of sphere and plane [20.61]. The real contact area at zero load is finite and the sphere can be detached only by pulling it away with a certain force. This is also true in the opposite case, in which the range of action of adhesive forces is larger than the elastic deformation. In such a case, the relation between contact area and load has the simple form

$$A(F_{\mathrm{N}}) = \pi \left(\frac{R}{K}\right)^{2/3} (F_{\mathrm{N}} - F_{\mathrm{off}})^{2/3} , \tag{20.32}$$

where F_{off} is the negative load required to break the contact. The Hertz-plus-offset relation (20.32) can be derived from the Derjaguin–Muller–Toporov (DMT) model [20.63]. To discriminate between the JKR or DMT models *Tabor* introduced a nondimensional parameter

$$\Phi = \left(\frac{9R\gamma^2}{4K^2 z_0^3}\right)^{1/3} , \tag{20.33}$$

where z_0 is the equilibrium distance in contact. The JKR model can be applied if $\Phi > 5$; the DMT model holds when $\Phi < 0.1$ [20.64]. For intermediate values of Φ, the Maugis–Dugdale model [20.65] could reasonably explain experimental results (Sect. 20.5.3).

20.5.2 Load Dependence of Friction

The FFM tip represents a single asperity sliding on a surface. The previous discussion suggests a nonlinear dependence of friction on the applied load, provided that continuum mechanics is applicable. Schwarz et al. observed the Hertz-plus-offset relation (20.32) on graphite, diamond, amorphous carbon and C_{60} in argon atmosphere (Fig. 20.32). In their measurements they used well-defined spherical tips with radii of curvature of tens of nanometers, obtained by contaminating silicon tips with amorphous carbon in a transmission electron microscope. In order to compare the tribological behavior of different materials, *Schwarz* et al. suggested the introduction of an effective coefficient of friction, $\tilde{C}$, which is independent of the tip curvature [20.62].

Meyer et al., *Carpick* et al., and *Polaczyc* et al. performed friction measurements in UHV in agreement with JKR theory [20.17, 66, 67]. In these experiments different materials were considered, i. e. ionic crystals, mica and metals. In order to correlate lateral and normal forces with improved statistics, Meyer et al. applied an original 2-D-histogram technique (Fig. 20.33). Carpick et al. extended the JKR relation (20.32) to include nonspherical tips. In the case of axisymmetric tip profile $z \propto r^{2n}$ $(n > 1)$, it can be proven analytically that the increase of friction becomes less pronounced with increasing n (Fig. 20.34).



Fig. 20.32a–d Friction vs. load curve on amorphous carbon in argon atmosphere. Curves **(a)**–**(d)** refer to tips with different radii of curvature. (After [20.62])

20.5.3 Estimation of the Contact Area

In contrast to other tribological instruments, such as the surface force apparatus [20.68], the contact area cannot be directly measured by FFM. Indirect methods are provided by contact stiffness measurements. The contact between the FFM tip and the sample can be modeled by a series of two springs (Fig. 20.35). The effective constant k^z_{eff} of the series is given by

$$\frac{1}{k^z_{\mathrm{eff}}} = \frac{1}{k^z_{\mathrm{contact}}} + \frac{1}{c_{\mathrm{N}}} , \tag{20.34}$$

where c_{N} is the normal spring constant of the cantilever and k^z_{contact} is the normal stiffness of the contact. This quantity is related to the radius of the contact area a, by the simple relation

$$k^z_{\mathrm{contact}} = 2aE^* , \tag{20.35}$$



Fig. 20.33 **(a)** Friction force map on NaCl(100). The load is decreased from 140 to 0 nN (jump-off point) during imaging. **(b)** 2-D-hystogram of **(a)**. (After [20.17])



Fig. 20.34a,b Friction vs. load curves **(a)** for a spherical tip and **(b)** for a blunted tip. The *solid curves* are determined with the JKR theory. (After [20.66])



Fig. 20.35 Sketch of normal and lateral stiffness of the contact between tip and surface. (After [20.70])

where E^* is the effective Young's modulus previously introduced [20.69]. Typical values of k^z_{contact} are order of magnitude larger than c_N, however, and a practical application of (20.34) is not possible.

Carpick et al. suggested an alternative method independently [20.70, 71]. According to various models, the *lateral* contact stiffness of the contact between a sphere and a flat surface is [20.72]

$$k^x_{\text{contact}} = 8aG^* \,, \tag{20.36}$$

where the effective shear stress G^* is defined by

$$\frac{1}{G^*} = \frac{2-\nu_1^2}{G_1} + \frac{2-\nu_2^2}{G_2} \tag{20.37}$$

(G_1, G_2 are the shear moduli of sphere and plane). The contact between the FFM tip and the sample can be modeled again by a series of springs (Fig. 20.35). The effective constant k^x_{eff} of the series is given by

$$\frac{1}{k^x_{\text{eff}}} = \frac{1}{k^x_{\text{contact}}} + \frac{1}{k^x_{\text{tip}}} + \frac{1}{c_L} \,, \tag{20.38}$$

where c_L is the lateral spring constant of the cantilever and k^x_{contact} is the lateral stiffness of the contact. As suggested by Lantz, (20.38) includes also the lateral stiffness of the tip, k^x_{tip}, which can be comparable to the lateral spring constant. The effective spring constant k^x_{eff} is simply given by the slope $\mathrm{d}F_L/\mathrm{d}x$ of the friction loops (Sect. 20.2.1). Once k^x_{contact} is determined, the contact radius a is easily estimated by (20.36).

The lateral stiffness method was applied to contacts between silicon nitride and muscovite mica in air and between $NbSe_2$ and graphite in UHV. Both the spring constant k^x_{eff} and the lateral force F_L dependence on the load F_N were explained within the same models (JKR and Maugis–Dugdale, respectively), which confirms that friction is proportional to the contact area in the applied range of loads (up to $F_N = 40$ nN in both experiments).

Enachescu et al. estimated the contact area by measuring the contact conductance on diamond as a function of the applied load [20.73, 74]. Their experimental data were fitted with the DMT model, which was also used to explain the dependence of friction vs. load. Since the contact conductance is proportional to the contact area, the validity of the hypothesis (20.28) was confirmed again.

20.6 Wear on the Atomic Scale

If the normal force F_N applied with the FFM exceeds a critical value, which depends on the tip shape and on the material under investigation, the surface topography is permanently modified. In some cases wear is exploited to create patterns with well-defined shape. Here we will focus on the mechanisms acting on the nanometer scale, where recent experiments have proven the unique capability of the FFM in both scratching and imaging surfaces down to the atomic scale.

20.6.1 Abrasive Wear on the Atomic Scale

In the case of ionic crystals, *Lüthi* et al. observed the appearance of wear at very low loads, i. e. $F_N = 3$ nN [20.31]. Atomically resolved images of the damage produced by scratching the FFM tip areas on potassium bromide were obtained very recently by *Gnecco* et al. [20.75]. In Fig. 20.36 a small mound grown up at the end of a groove on KBr(100) is shown under different magnifications. The groove was created a few minutes before imaging by repeated scanning with the normal force $F_N = 21$ nN. The image shows a lateral force map acquired with a load of about 1 nN; no atomic features were observed in the corresponding topography signal. Figure 20.36a,b shows that the debris extracted from the groove recrystallized with the same atomic arrangement of the undamaged surface, which suggests that the wear process occurred like an epitaxial growth assisted by the microscope tip.

Although it is not straightforward to understand how wear is initiated and how the tip transports the debris, important indications are given by the profile of the lateral force F_L recorded while scratching. Figure 20.37 shows some friction loops acquired when the tip was scanned laterally on 5×5 nm^2 areas. The mean lateral force multiplied by the scanned length gives the total energy dissipated in the process. The result of the tip movement are the pits in Fig. 20.38a. Thanks to the pseudo-atomic



Fig. 20.36a,b Lateral force images acquired at the end of a groove scratched 256 times with a normal force $F_N = 21$nN. Frame sizes: **(a)** 39 nm, **(b)** 25 nm



Fig. 20.37 Friction loops acquired while scratching the KBr surface on 5 nm long lines with different loads $F_N = 5.7$ to 22.8 nN. (After [20.75])



Fig. 20.38 **(a)** Lateral force images of the pits produced with $F_N = 5.7$ to 22.8 nN. Frame size: 150 nm; **(b)** Detailed image of the fourth pit from the top with psuedo-atomic resolution. Frame size: 20 nm

resolution obtained by FFM (Fig. 20.38b), the number of removed atoms could be determined from the lateral force images, which allowed estimating that 70% of the dissipated energy went into wear-less friction [20.75]. Figures 20.37 and 20.38 clearly show that the damage increases with increasing load. On the other hand, changing the scan velocity v between 25 and 100 nm/s did not produce any significant variation in the wear process.

A different kind of wear was observed on layered materials. *Kopta* et al. [20.76] could remove layers from a muscovite mica surface by scratching with the normal force $F_N = 230$ nN (Fig. 20.39a). Fourier filtered images acquired on very small areas revealed the different periodicities of the underlying layers, which reflect the complex structure of the muscovite mica (Fig. 20.39b,c).

20.6.2 Wear Contribution to Friction

In Fig. 20.40 the mean lateral force detected while scratching the KBr(100) surface with a fixed load $F_N = 11$ nN is shown. A rather continuous increase of "friction" with the number of scratches N is observed, which can be approximated with the following exponential law:

$$F_L = F_0\,\mathrm{e}^{-N/N_0} + F_\infty\left(1 - \mathrm{e}^{-N/N_0}\right) . \tag{20.39}$$

Equation (20.39) is easily interpreted assuming that friction is proportional to the contact area $A(N)$, and that time evolution of $A(N)$ can be described by

$$\frac{\mathrm{d}A}{\mathrm{d}N} = \frac{A_\infty - A(N)}{N_0} , \tag{20.40}$$

A_∞ being the limit area in which the applied load can be balanced without scratching.



Fig. 20.39 **(a)** Topography image of an area scratched on muscovite mica with $F_N = 230$ nN; **(b)**,**(c)** Fourier filtered images of different regions. (After [20.76])

To interpret their experiment on mica, Kopta et al. assumed that wear is initiated by atomic defects. When the defects accumulate beyond a critical concentration, they grow to form the scars shown in Fig. 20.39. Such process was once again related to thermal activation. The number of defects created in the contact area $A(F_N)$ is

$$N_{\mathrm{def}}(F_N) = t_{\mathrm{res}} n_0 A(F_N) f_0 \exp\left(-\frac{\Delta E}{k_B T}\right) , \tag{20.41}$$



Fig. 20.40 Mean value of the lateral force during repeated scratching with $F_N = 11$ nN on a 500 nm line. (After [20.75])

where t_{res} is the residence time of the tip, n_0 is the surface density of atoms, and f_0 is the attempt frequency to overcome the energy barrier ΔE to break a Si–O bond, which depends on the applied load. When the defect density reaches a critical value, a hole is nucleated. The friction force during the creation of a hole could also be estimated with thermal activation by Kopta et al., who derived the formula

$$F_L = c(F_N - F_{off})^{2/3} + \gamma F_N^{2/3} \exp\left(B_0 F_N^{2/3}\right) . \tag{20.42}$$

The first term on the right gives the wearless dependence of friction in the Hertz-plus-offset model (Sect. 20.5.1); the second term is the contribution of the defect production. The agreement between (20.42) and the experiment can be observed in Fig. 20.41.



Fig. 20.41 Friction vs. load curve during the creation of a hole in the muscovite mica. (After [20.76])

20.7 Molecular Dynamics Simulations of Atomic Friction and Wear

Section 20.5 has introduced how small sliding contacts can be modeled by continuum mechanics. This modeling has several limitations. The first, most obvious, is that continuum mechanics cannot account for atomic-scale processes like atomic stick-slip. While this limit can be overcome by semiclassical descriptions like the Tomlinson model, a definite limit is the determination of contact stiffness for contacts with a radius of a few nanometers. Interpretation of experimental results with the methods introduced in Sect. 20.5.3 regularly yields contact radii of atomic or even smaller size, in clear contradiction to the minimal contact size given by adhesion forces. Such macroscopic quantities as shear modulus or pressure fail to describe the mechanical behavior of these contacts. A microscopic modeling including the atomic structure of the contact is therefore required. This is usually done by a *molecular dynamics* (MD) simulation of the contact. In such simulations, the sliding contact is set up by boundaries of fixed atoms in relative motion and the atoms of the contact, which are allowed to relax their positions according to interactions between each pair of atoms. The methods of computer simulations in tribology are discussed elsewhere in this book. In Sect. 20.7.1 we will discuss such simulations, which can be directly compared to experimental results showing atomic friction processes. The major outcome of the simulations beyond the inclusion of the atomic structure is the importance of displacement of atoms for a correct prediction of forces. In the following Sect. 20.7.2, we will present simulation studies including wear of tip or surface.

20.7.1 Molecular Dynamics Simulation of Friction Processes

The first experiments that exhibited atomic friction features were performed on layered materials, often graphite. A theoretical study of forces between an atomically sharp diamond tip and the graphite surface has been reported by *Tang* et al. [20.77]. The authors found a significant distance dependence of forces, in which the strongest contrast appeared at different distances for normal and lateral forces due to the strong displacement of surface atoms. The order of magnitude found in this study was one nanonewton, much less than in most experimental reports, which indicated that in such experiments a contact area of far larger dimension was realized. Tang et al. already determined that the distance dependence of forces could even change the symmetry appearance of the observed lateral forces. The experimental situation has also been studied in numerical simulations using simplified one-atom potential for the tip–surface interaction but including the spring potential of the probing force sensor [20.36]. The motivation for these studies was the observation of a hexagonal pattern in the friction force, while the surface atoms of graphite are ordered in a honeycomb structure. The simulations revealed how the jump path of the tip under lateral force is dependent on the force constant of the probing force sensor.

Surfaces of ionic crystals have become model systems for studies in atomic friction. Atomic stick-slip behavior has been observed by several groups with a lateral force modulation of the order of 1 nN. Pioneering work in atomistic simulation of sliding contacts has been done by *Landman* et al.. The first ionic system studied was a CaF_2 tip sliding over a $CaF_2(111)$ surface [20.78]. In MD calculation with controlled temperature, the tip was first approached toward the surface up to the point at which an attractive normal force of −3 nN acted on the tip. Then the tip was laterally moved, and the lateral force determined. An oscillation with the atomic periodicity of the surface and with an amplitude decreasing from 8 nN was found. Inspection of the atomic positions revealed a wear process by shear cleavage of the tip. Such transfer of atoms between tip and surface plays a crucial role in atomic friction studies as was shown by *Shluger* et al. [20.79]. These authors simulated a MgO tip scanning laterally over a LiF(100) surface. Initially an irregular oscillation of the system's energy is found together with transfer of atoms between surface and tip. After a while, the tip apex structure is changed by adsorption of Li and F ions in such a way that nondestructive sliding with perfectly regular oscillation of the energy with the periodicity of the surface could be observed. The authors called this effect self-lubrication and speculate that generally a dynamic self-organization of the surface material on the tip might promote the observation of periodic forces. In a less costly approach of a molecular mechanics study, in which the forces are calculated for each fixed tip–sample configuration, *Tang* et al. produced lateral and normal force maps for a diamond tip over a NaCl(100) surface including such defects as vacancies and a step [20.80]. In accordance with the studies mentioned before, they found that significant atomic force contrast can be expected for tip–sample distances below 0.35 nm, while distances below 0.15 nm result in destructive forces. For the idealized conditions of scanning at constant height in this regime, the authors predict that even atomic-sized defects could be imaged. Experimentally, these conditions cannot be stabilized in static modes, which so far have been used in lateral force measurements. But dynamic modes of force microscopy have proven atomic resolution of defects when entering the distance regime between 0.2 and 0.4 nm [20.81]. Recent experimental progress in atomic friction studies of surfaces of ionic crystals include the velocity dependence of lateral forces and atomic-scale wear processes. Such phenomena are not yet accessible by MD studies: the experimentally realized scanning time scale is too far from the atomic relaxation time scales that govern MD simulations. Furthermore, the number of freely transferable atoms that can be included in a simulation is simply limited by meaningful calculation time.

Landman et al. also simulated a system of high reactivity, namely a silicon tip sliding over a silicon surface [20.82]. A clear stick-slip variation of the lateral force was observed for this situation. Strong atom displacements created an interstitial atom under the influence of the tip, which was annealed as the tip moved on. Permanent damage was predicted, however, in the case that the tip enters the repulsive force regime. Although the simulated Si(111) surface is experimentally not accessible, it should be mentioned that on the Si(111)7×7 reconstructed surface the tip had to be passivated by a Teflon layer before nondestructive contact-mode measurements became possible (Sect. 20.3). It is worth noting that the simulations for the Cu(111) surface revealed a linear relation between contact area and mean lateral force, similar to classical macroscopic laws.

For metallic sliding over metallic surfaces, wear processes are predicted by several MD studies, which will be discussed in the following section. For a (111)-terminated copper tip over the Cu(111) surface, however, *Sørensen* et al. found that nondestructive sliding is possible while the lateral force exhibits the sawtooth-like shape characteristic of atomic stick-slip (Fig. 20.42). In contrast, a Cu(100) surface would be disordered by a sliding contact (Fig. 20.43). This difference between the (100) and (111) plane as well as the absolute lateral forces has been confirmed experimentally (Sect. 20.3).

20.7.2 Molecular Dynamics Simulations of Abrasive Wear

The long time scales characteristic of the wear processes and the large amount of material involved make any attempt to simulate these mechanisms on a computer a tremendous challenge. Despite these premises, MD can provide useful insight on the mechanism of removal and deposition of single atoms operated by the FFM tip, which is a kind of information not directly observable in the experiments. Complex processes like



Fig. 20.42 Lateral force acting on a Cu(111) tip in matching contact with a Cu(111) substrate as a function of the sliding distance at different loads. (After [20.83])



Fig. 20.43a–d Snapshot of a Cu(100) tip on a Cu(100) substrate during sliding. **(a)** Starting configuration; **(b)**–**(d)** snapshots after 2, 4, and 6 slips. (After [20.83])



Fig. 20.44a–f Snapshot of a Cu(100) neck during shearing starting from the configuration **(a)**. The upper substrate has been displaced 4.2 Å between subsequent pictures. (After [20.83])

abrasive wear and nanolithography can be investigated only within approximate classical mechanics.

The observation made by *Livshits* and *Shluger* that the FFM tip undergoes a process of self-lubrication when scanning ionic surfaces (Sect. 20.7.1) proves that friction and wear are strictly related phenomena. In their MD simulations on copper, *Sørensen* et al. considered not only ordered (111) and (100) terminated tips but even amorphous structures obtained by "heating" the tip at high temperatures [20.83]. The lateral motion of the neck thus formed revealed a stick-slip behavior due to combined sliding and stretching, and also ruptures, accompanied by deposition of debris on the surface (Fig. 20.44).

To our knowledge, only a few examples of abrasive wear simulations on the atomic scale have been reported. *Buldum* and *Ciraci*, for instance, studied nanoindentation and sliding of a sharp Ni(111) tip on Cu(110) and of a blunt Ni(001) tip on Cu(100) [20.84]. In the case of the sharp tip quasiperiodic variations of the lateral force were observed, due to stick-slip involving phase-transition. One layer of the asperity was deformed to match the substrate during the first slip and then two asperity layers merged into one through structural transition during the second slip. In the case of the blunt tip, the stick-slip was less regular.

Different results have been reported in which the tip is harder than the underlying sample. *Komanduri* et al. considered an infinitely hard Ni indenter scratching single crystal aluminum at extremely low depths (Fig. 20.45) [20.85]. In this case a linear relation between friction and load was found, with a high coefficient of friction $\mu = 0.6$, independent of the scratch depth. Nanolithography simulations were recently performed by *Fang* et al. [20.86], who investigated the role of the displacement of the FFM tip along the direction of slow motion between a scan line and the next one. They found a certain correlation with FFM experiments on silicon films coated with aluminum.



Fig. 20.45 MD simulation of a scratch realized with an infinitely hard tool. (After [20.85])

20.8 Energy Dissipation in Noncontact Atomic Force Microscopy

Historically, the measurement of energy dissipation induced by tip–sample interaction has been the domain of friction-force microscopy, where the sharp AFM-tip is sliding in gentle contact over a sample. The origins of dissipation in friction are related to phonon excitation, electronic excitation, and irreversible changes of the surface. In a typical stick-slip experiment, the energy dissipated in a single atomic slip event is of the order of 1 eV.

But the lateral resolution of force microscopy in the contact mode is limited by a minimum contact area containing several atoms due to adhesion between tip and sample.

This problem has been overcome in noncontact dynamic force microscopy. In the dynamic mode, the tip is oscillating with a constant amplitude A of typically 1–20 nm at the eigenfrequency f of the cantilever, which shifts by Δf due to interaction forces between tip and sample. This technique has been described in detail in Part B of this book.

Dissipation also occurs in noncontact mode of force microscopy, where the atomic structure of tip and sample are reliably preserved. In this dynamic mode, the damping of the cantilever oscillation can be deduced from the excitation amplitude A_{exc} required to maintain the constant tip oscillation amplitude on resonance.

Compared to friction force microscopy, the interpretation of noncontact-AFM (nc-AFM) experiments is complicated due to the perpendicular oscillation of the tip, typically with an amplitude that is large compared to the minimum tip–sample separation. Another problem is to relate the measured damping of the cantilever to the different origins of dissipation.

In all dynamic force microscopy measurements a power dissipation P_0 caused by internal friction of the freely oscillating cantilever is observed, which is proportional to the eigenfrequency ω_0 and to the square of the amplitude A and inverse proportional to the known Q-value of the cantilever. When the tip–sample distance is reduced, the tip interacts with the sample and therefore an additional damping of the oscillation is encountered. This extra dissipation P_{ts} caused by tip–sample interaction can be calculated from the excitation signal A_{exc} [20.87].

The observed energy losses per oscillation cycle (100 meV) [20.88] are roughly similar to the 1 eV energy loss in the contact slip-process. When estimating the contact area in the contact-mode to a few atoms, the energy dissipation per atom that can be associated with a bond being broken and reformed is also around 100 meV.

The idea to relate additional damping of the tip oscillation to dissipative tip–sample interaction has recently attracted much attention [20.89]. The origin of this additional dissipation are manifold: one may distinguish between apparent energy dissipation (for example from an inharmonic cantilever-motion, artifacts from the phase-controller, or slow fluctuations round the steady-state solution [20.89, 90]), velocity dependent dissipation (for example electric- and magnetic-field mediated Joule dissipation [20.91, 92]) and hysteresis-related dissipation (due to atomic instabilities [20.93, 94] or hysteresis due to adhesion [20.95]).

By recording Δf and A_{exc} simultaneously during a typical AFM-experiment, forces and dissipation can be measured. Many experiments show true atomic contrast in topography (controlled by Δf) and in the dissipation-signal A_{exc} [20.96]; however, the origin of the atomic energy dissipation process is still not completely resolved.

To prove that the observed atomic-scale variation of the damping is indeed due to atomic-scale energy dissipation and not an artefact of the distance feedback, *Loppacher* et al. [20.88] carried out an nc-AFM experiment on Si(111)-7 × 7 at constant height, i. e. with stopped distance feedback. Frequency-shift and dissipation exhibit an atomic-scale contrast, demonstrating a true atomic-scale variation of force and dissipation.

A strong atomic-scale dissipation contrast at step edges has been demonstrated in a few experiments (NaCl on Cu [20.81]; or measurements on KBr [20.97]). In Fig. 20.46 ultrathin NaCl islands grown on Cu(111) are shown. As it is shown in Fig. 20.46a, the island edges have a higher contrast compared to the NaCl-terrace and show an atomically resolved corrugation. The strongly enhanced contrast of the step edges and kink sites could be attributed to a slower decay of the electric field and to easier relaxation of theses positions of the ions at these locations. The dissipation image shown in Fig. 20.46b was recorded simultaneously. To establish a direct spatial correspondence between the excitation and the topography-signal, the match between topography and A_{exc} on many images has been studied. Sometimes topography and A_{exc} are in phase, sometimes they are shifted a little bit, and sometimes A_{exc} is at a minimum when topography is at a maximum. The local contrast formation thus depends strongly on the atomic tip structure. In fact, the strong dependence of the dissipation contrast on the atomic state of the tip apex is impressively confirmed by the tip change observed in the experimental images shown in Fig. 20.46b. The dissipation contrast is seriously enhanced, while the topography contrast remains nearly unchanged. Clearly, the dissipation depends strongly on the state of the tip and exhibits more short-range character than the frequency shift.



Fig. 20.46 **(a)** Topography and **(b)** A_{exc} images of a NaCl island on Cu(111). The tip changes after 1/4 of the scan, thereby changing the contrast in the topography and enhancing the contrast in A_{exc}. After 2/3 of the scan, the contrast from the *lower part* of the image is reproduced, indicating that the tip change was reversible. (After [20.81])

More directly related to friction measurements, where the tip is sliding in contact over the sample, are nc-AFM experiments, where the tip is oscillating parallel to the surface. *Stowe* et al. [20.98] oriented cantilever beams with in-plane tips perpendicular to the surface, so that the tip motion was approximately parallel to the surface. The noncontact damping of the lever was used to measure localized electrical Joule dissipation. They were able to image the dopant density for n- and p-type silicon samples with 150 nm spatial resolution. An U_{ts}^2 dependence on the tip–sample voltage for the dissipation was found, as proposed by *Denk* and *Pohl* [20.91] for electric-field Joule-dissipation.

Stipe et al. [20.99] measured the noncontact friction between a Au(111)-surface and a gold-coated tip with the same setup. They observed the same U_{ts}^2 dependence of the Bias-voltage and a distance dependence that follows a power law $1/d^n$, where n is between 1.3 and 3 [20.99, 100]. Even when the external Bias-voltage is zero, a substantial electric-field is present. The presence of inhomogeneous tip–sample electric fields is difficult to avoid, even under the best experimental conditions. Although this dissipation is electrical in origin, the detailed mechanism is not totally clear. The most straightforward mechanism is to assume that inhomogeneous fields emanating from the tip and the sample induce surface charges in the nearby metallic sample. When the tip moves, currents are induced, causing Ohmic dissipation [20.91, 98]. But in metals with good electrical conductivity, Ohmic dissipation is insufficient to account for the observed effect [20.101]. Thus the tip–sample electric field must have an additional effect, such as driving the motion of adsorbates and surface defects.

When exciting the torsional oscillation of commercial, rectangular AFM cantilevers, the tip is oscillating approximately parallel to the surface. In this mode, lateral forces acting on the tip at step edges and near impurities could be measured quantitatively [20.54]. An enhanced energy-dissipation was observed at the impurities as well. When the tip is further approached toward the sample, contact formation transforms the nearly free torsional oscillation of the cantilever into a different mode with the tip–sample contact acting as a hinge. When this contact is formed, a rapid increase of the power required to maintain a constant tip oscillation amplitude and a positive frequency shift are found. The onset of the simultaneously recorded damping and positive frequency shift are sharp and essentially coincide. It is assumed that these changes indicate the formation of a tip–sample contact. Two recent studies [20.102, 103] report on the use of the torsional eigenmode for measuring the elastic properties of the tip–sample contact, where the tip is in contact with the sample and the shear stiffness depends on the normal load.

Kawagishi et al. [20.104] scanned with lateral amplitudes in the order of 10 pm to 3 nm; their imaging technique gave contrast between graphite terraces, silicon and silicon dioxide, graphite and mica. Torsional self-excitation showed nanometric features of self-assembled monolayer islands due to different lateral dissipation.

Recently *Giessibl* et al. [20.105] established true atomic resolution of both conservative and dissipative forces by lateral force microscopy. The interaction between a single-tip atom oscillated parallel to an Si(111)-7 × 7 surface is measured. A dissipation energy of up to 4 eV per oscillation cycle is found, which is explained by a plucking action of one atom on to the other as described by *Tomlinson* in 1929 [20.23].

A detailed review of dissipation phenomena in noncontact force microscopy has been given by *Hug* [20.106].

20.9 Conclusion

Over the last 15 years, two instrumental developments have stimulated scientific activities in the field of nanotribology. On the one hand, the invention and development of friction force microscopy allows us to quantitatively study friction of a single asperity. As we have discussed in this chapter, atomic processes are observed by forces on the order of 1 nN, i. e. forces related to single chemical bonds. On the other hand, the enormous increase of achievable computing power provides the basis for molecular dynamics simulations of systems containing several hundred atoms. Therewithin, the development of the atomic structure in a sliding contact can be analyzed and forces predicted.

The most prominent observation of atomic friction is a stick-slip behavior with the periodicity of the surface atomic lattice. Semiclassical models can explain the experimental findings including the velocity dependence, which is a consequence of thermal activation of slip events. Classical continuum mechanics can also describe the load dependence of friction in contacts with an extension of several ten nanometers. But when trying to apply continuum mechanics to contacts formed at just ten atoms, obviously wrong numbers result, such as, for example, for the contact radius. Only a comparison with atomistic simulations can provide a full meaningful picture of the physical parameters of such sliding contacts. These simulations predict a close connection between wear and friction, in particular a transfer of atoms between surface and tip, which in some case can even lower friction in a process of self-lubrication.

First experiments have succeeded in studying the onset of wear with atomic resolution. The research in microscopic wear processes will certainly grow in importance as nanostructures are produced and their mechanical properties exploited. Simulation of such processes involving transfer of thousands of atoms will become feasible with further increase of computing power. Another perspective of nanotribology is the expansion of atomic friction experiments toward surfaces with a well-defined roughness. In general, the problem of bridging the gap between single asperity experiments on well-defined surfaces and macroscopic friction should be approached, both experimentally and in modeling.

© Springer 2004

References

20.1 C. M. Mate, G. M. McClelland, R. Erlandsson, S. Chiang: Atomic-scale friction of a tungsten tip on a graphite surface, Phys. Rev. Lett. **59** (1987) 1942–1945

20.2 G. Binnig, C. F. Quate, Ch. Gerber: Atomic force microscope, Phys. Rev. Lett. **56** (1986) 930–933

20.3 O. Marti, J. Colchero, J. Mlynek: Combined scanning force and friction microscopy of mica, Nanotechnology **1** (1990) 141–144

20.4 G. Meyer, N. Amer: Simultaneous measurement of lateral and normal forces with an optical-beam-deflection atomic force microscope, Appl. Phys. Lett. **57** (1990) 2089–2091

20.5 G. Neubauer, S. R. Cohen, G. M. McClelland, D. E. Horn, C. M. Mate: Force microscopy with a bidirectional capacitance sensor, Rev. Sci. Instrum. **61** (1990) 2296–2308

20.6 G. M. McClelland, J. N. Glosli: Friction at the atomic scale. In: *NATO ASI Series E*, Vol. 220, ed. by L. Singer, H. M. Pollock (Kluwer, Dordrecht 1992) pp. 405–425

20.7 R. Linnemann, T. Gotszalk, I. W. Rangelow, P. Dumania, E. Oesterschulze: Atomic force microscopy and lateral force microscopy using piezoresistive cantilevers, J. Vac. Sci. Technol. B **14** (1996) 856–860

20.8 M. Nonnenmacher, J. Greschner, O. Wolter, R. Kassing: Scanning force microscopy with micromachined silicon sensors, J. Vac. Sci. Technol. B **9** (1991) 1358–1362

20.9 R. Lüthi: Untersuchungen zur Nanotribologie und zur Auflösungsgrenze im Ultrahochvakuum mittels Rasterkraftmikroskopie. Ph.D. Thesis (Univ. of Basel, Basel 1996)

20.10 J. Cleveland, S. Manne, D. Bocek, P. K. Hansma: A nondestructive method for determining the spring constant of cantilevers for scanning force microscopy, Rev. Sci. Instrum. **64** (1993) 403–405

20.11 J. L. Hutter, J. Bechhoefer: Calibration of atomic-force microscope tips, Rev. Sci. Instrum. **64** (1993) 1868–1873

20.12 H. J. Butt, M. Jaschke: Calculation of thermal noise in atomic-force microscopy, Nanotechnology **6** (1995) 1–7

20.13 J. M. Neumeister, W. A. Ducker: Lateral, normal, and longitudinal spring constants of atomic-force microscopy cantilevers, Rev. Sci. Instrum. **65** (1994) 2527–2531

20.14 D. F. Ogletree, R. W. Carpick, M. Salmeron: Calibration of frictional forces in atomic force microscopy, Rev. Sci. Instrum. **67** (1996) 3298–3306

20.15 E. Gnecco: AFM study of friction phenomena on the nanometer scale. Ph.D. Thesis (Univ. of Genova, Genova 2001)

20.16 U. D. Schwarz, P. Köster, R. Wiesendanger: Quantitative analysis of lateral force microscopy experiments, Rev. Sci. Instrum. **67** (1996) 2560–2567

20.17 E. Meyer, R. Lüthi, L. Howald, M. Bammerlin, M. Guggisberg, H.-J. Güntherodt: Site-specific friction force spectroscopy, J. Vac. Sci. Technol. B **14** (1996) 1285–1288

20.18 S. S. Sheiko, M. Möller, E. M. C. M. Reuvekamp, H. W. Zandberger: Calibration and evaluation of scanning-force-microscopy probes, Phys. Rev B **48** (1993) 5675

20.19 F. Atamny, A. Baiker: Direct imaging of the tip shape by AFM, Surf. Sci. **323** (1995) L314

20.20 L. Howald, E. Meyer, R. Lüthi, H. Haefke, R. Overney, H. Rudin, H.-J. Güntherodt: Multifunctional probe microscope for facile operation in ultrahigh vacuum, Appl. Phys. Lett. **63** (1993) 117–119

20.21 J. S. Villarrubia: Algorithms for scanned probe microscope image simulation, surface reconstruction, and tip estimation, J. Res. Natl. Inst. Stand. Technol. **102** (1997) 425–454

20.22 Q. Dai, R. Vollmer, R. W. Carpick, D. F. Ogletree, M. Salmeron: A variable temperature ultrahigh vacuum atomic force microscope, Rev. Sci. Instrum. **66** (1995) 5266–5271

20.23 G. A. Tomlinson: A molecular theory of friction, Philos. Mag. Ser. **7** (1929) 905

20.24 T. Gyalog, M. Bammerlin, R. Lüthi, E. Meyer, H. Thomas: Mechanism of atomic friction, Europhys. Lett. **31** (1995) 269–274

20.25 T. Gyalog, H. Thomas: Friction between atomically flat surfaces, Europhys. Lett. **37** (1997) 195–200

20.26 M. Weiss, F. J. Elmer: Dry friction in the Frenkel–Kontorova–Tomlinson model: Static properties, Phys. Rev. B **53** (1996) 7539–7549

20.27 J. B. Pethica: Comment on "Interatomic forces in scanning tunneling microscopy: Giant corrugations of the graphite surface", Phys. Rev. Lett. **57** (1986) 3235

20.28 E. Meyer, R. M. Overney, K. Dransfeld, T. Gyalog: *Nanoscience, Friction and Rheology on the Nanometer Scale* (World Scientific, Singapore 1998)

20.29 L. Howald, R. Lüthi, E. Meyer, H.-J. Güntherodt: Atomic-force microscopy on the Si(111)7 × 7 surface, Phys. Rev. B **51** (1995) 5484–5487

20.30 R. Bennewitz, T. Gyalog, M. Guggisberg, M. Bammerlin, E. Meyer, H.-J. Güntherodt: Atomic-scale stick-slip processes on Cu(111), Phys. Rev. B **60** (1999) R11301–R11304

20.31 R. Lüthi, E. Meyer, M. Bammerlin, L. Howald, H. Haefke, T. Lehmann, C. Loppacher, H.-J. Güntherodt, T. Gyalog, H. Thomas: Friction on the atomic scale: An ultrahigh vacuum atomic force microscopy study on ionic crystals, J. Vac. Sci. Technol. B **14** (1996) 1280–1284

20.32 G. J. Germann, S. R. Cohen, G. Neubauer, G. M. McClelland, H. Seki: Atomic scale friction of a diamond tip on diamond (100) and (111) surfaces, J. Appl. Phys. **73** (1993) 163–167

20.33 R. J. A.van den Oetelaar, C. F. J. Flipse: Atomic-scale friction on diamond(111) studied by ultra-high vacuum atomic force microscopy, Surf. Sci. **384** (1997) L828–L835

20.34 R. Bennewitz, E. Gnecco, T. Gyalog, E. Meyer: Atomic friction studies on well-defined surfaces, Tribol. Lett. **10** (2001) 51–56

20.35 S. Fujisawa, E. Kishi, Y. Sugawara, S. Morita: Atomic-scale friction observed with a two-dimensional frictional-force microscope, Phys. Rev. B **51** (1995) 7849–7857

20.36 N. Sasaki, M. Kobayashi, M. Tsukada: Atomic-scale friction image of graphite in atomic-force microscopy, Phys. Rev. B **54** (1996) 2138–2149

20.37 H. Kawakatsu, T. Saito: Scanning force microscopy with two optical levers for detection of deformations of the cantilever, J. Vac. Sci. Technol. B **14** (1996) 872–876

20.38 M. Liley, D. Gourdon, D. Stamou, U. Meseth, T. M. Fischer, C. Lautz, H. Stahlberg, H. Vogel, N. A. Burnham, C. Duschl: Friction anisotropy and asymmetry of a compliant monolayer induced by a small molecular tilt, Science **280** (1998) 273–275

20.39 R. Lüthi, E. Meyer, H. Haefke, L. Howald, W. Gutmannsbauer, H.-J. Güntherodt: Sled-type motion on the nanometer scale: Determination of dissipation and cohesive energies of C_{60}, Science **266** (1994) 1979–1981

20.40 M. R. Falvo, J. Steele, R. M. Taylor, R. Superfine: Evidence of commensurate contact and rolling motion: AFM manipulation studies of carbon nanotubes on HOPG, Tribol. Lett. **9** (2000) 73–76

20.41 M. Hirano, K. Shinjo, R. Kaneko, Y. Murata: Anisotropy of frictional forces in muscovite mica, Phys. Rev. Lett. **67** (1991) 2642–2645

20.42 M. Hirano, K. Shinjo, R. Kaneko, Y. Murata: Observation of superlubricity by scanning tunneling microscopy, Phys. Rev. Lett. **78** (1997) 1448–1451

20.43 R. M. Overney, H. Takano, M. Fujihira, W. Paulus, H. Ringsdorf: Anisotropy in friction and molecular stick-slip motion, Phys. Rev. Lett. **72** (1994) 3546–3549

20.44 H. Takano, M. Fujihira: Study of molecular scale friction on stearic acid crystals by friction force microscopy, J. Vac. Sci. Technol. B **14** (1996) 1272–1275

20.45 P. E. Sheehan, C. M. Lieber: Nanotribology and nanofabrication of MoO_3 structures by atomic force microscopy, Science **272** (1996) 1158–1161

20.46 E. Gnecco, R. Bennewitz, T. Gyalog, Ch. Loppacher, M. Bammerlin, E. Meyer, H.-J. Güntherodt: Velocity dependence of atomic friction, Phys. Rev. Lett. **84** (2000) 1172–1175

20.47 D. Gourdon, N. A. Burnham, A. Kulik, E. Dupas, F. Oulevey, G. Gremaud, D. Stamou, M. Liley, Z. Dienes, H. Vogel, C. Duschl: The dependence of friction anisotropies on the molecular organization of LB films as observed by AFM, Tribol. Lett. **3** (1997) 317–324

20.48 Y. Sang, M. Dubé, M. Grant: Thermal effects on atomic friction, Phys. Rev. Lett. **87** (2001) 174301

20.49 E. Riedo, E. Gnecco, R. Bennewitz, E. Meyer, H. Brune: Interaction potential and hopping dynamics governing sliding friction, Phys. Rev. Lett. **91** (2003) 084502

20.50 O. Zwörner, H. Hölscher, U. D. Schwarz, R. Wiesendanger: The velocity dependence of frictional forces in point-contact friction, Appl. Phys. A **66** (1998) 263–267

20.51 T. Bouhacina, J. P. Aimé, S. Gauthier, D. Michel, V. Heroguez: Tribological behavior of a polymer grafted on silanized silica probed with a nanotip, Phys. Rev. B **56** (1997) 7694–7703

20.52 H. J. Eyring: The activated complex in chemical reactions, J. Chem. Phys. **3** (1937) 107

20.53 J. N. Glosli, G. M. McClelland: Molecular dynamics study of sliding friction of ordered organic monolayers, Phys. Rev. Lett. **70** (1993) 1960–1963

20.54 O. Pfeiffer, R. Bennewitz, A. Baratoff, E. Meyer, P. Grütter: Lateral-force measurements in dynamic force microscopy, Phys. Rev. B **65** (2002) 161403

20.55 E. Riedo, F. Lévy, H. Brune: Kinetics of capillary condensation in nanoscopic sliding friction, Phys. Rev. Lett. **88** (2002) 185505

20.56 M. He, A. S. Blum, G. Overney, R. M. Overney: Effect of interfacial liquid structuring on the coherence length in nanolubrucation, Phys. Rev. Lett. **88** (2002) 154302

20.57 F. P. Bowden, F. P. Tabor: *The Friction and Lubrication of Solids* (Oxford Univ. Press, Oxford 1950)

20.58 L. D. Landau, E. M. Lifshitz: *Introduction to Theoretical Physics* (Nauka, Moscow 1998) Vol. 7

20.59 J. A. Greenwood, J. B. P. Williamson: Contact of nominally flat surfaces, Proc. R. Soc. Lond. A **295** (1966) 300

20.60 B. N. J. Persson: Elastoplastic contact between randomly rough surfaces, Phys. Rev. Lett. **87** (2001) 116101

20.61 K. L. Johnson, K. Kendall, A. D. Roberts: Surface energy and contact of elastic solids, Proc. R. Soc. Lond. A **324** (1971) 301

20.62 U. D. Schwarz, O. Zwörner, P. Köster, R. Wiesendanger: Quantitative analysis of the frictional properties of solid materials at low loads, Phys. Rev. B **56** (1997) 6987–6996

20.63 B. V. Derjaguin, V. M. Muller, Y. P. Toporov: Effect of contact deformations on adhesion of particles, J. Colloid Interface Sci. **53** (1975) 314–326

20.64 D. Tabor: Surface forces and surface interactions, J. Colloid Interface Sci. **58** (1977) 2–13

20.65 D. Maugis: Adhesion of spheres: the JKR-DMT transition using a Dugdale model, J. Colloid Interface Sci. **150** (1992) 243–269

20.66 R.W. Carpick, N. Agraït, D.F. Ogletree, M. Salmeron: Measurement of interfacial shear (friction) with an ultrahigh vacuum atomic force microscope, J. Vac. Sci. Technol. B **14** (1996) 1289–1295

20.67 C. Polaczyk, T. Schneider, J. Schöfer, E. Santner: Microtribological behavior of Au(001) studied by AFM/FFM, Surf. Sci. **402** (1998) 454–458

20.68 J.N. Israelachvili, D. Tabor: Measurement of van der Waals dispersion forces in range 1.5 to 130 nm, Proc. R. Soc. Lond. A **331** (1972) 19

20.69 S.P. Jarvis, A. Oral, T.P. Weihs, J.B. Pethica: A novel force microscope and point-contact probe, Rev. Sci. Instrum. **64** (1993) 3515–3520

20.70 R.W. Carpick, D.F. Ogletree, M. Salmeron: Lateral stiffness: A new nanomechanical measurement for the determination of shear strengths with friction force microscopy, Appl. Phys. Lett. **70** (1997) 1548–1550

20.71 M.A. Lantz, S.J. O'Shea, M.E. Welland, K.L. Johnson: Atomic-force-microscope study of contact area and friction on $NbSe_2$, Phys. Rev. B **55** (1997) 10776–10785

20.72 K.L. Johnson: *Contact Mechanics* (Cambridge Univ. Press, Cambridge 1985)

20.73 M. Enachescu, R.J.A. van den Oetelaar, R.W. Carpick, D.F. Ogletree, C.F.J. Flipse, M. Salmeron: Atomic force microscopy study of an ideally hard contact: the diamond(111)/tungsten carbide interface, Phys. Rev. Lett. **81** (1998) 1877–1880

20.74 M. Enachescu, R.J.A. van den Oetelaar, R.W. Carpick, D.F. Ogletree, C.F.J. Flipse, M. Salmeron: Observation of proportionality between friction and contact area at the nanometer scale, Tribol. Lett. **7** (1999) 73–78

20.75 E. Gnecco, R. Bennewitz, E. Meyer: Abrasive wear on the atomic scale, Phys. Rev. Lett. **88** (2002) 215501

20.76 S. Kopta, M. Salmeron: The atomic scale origin of wear on mica and its contribution to friction, J. Chem. Phys. **113** (2000) 8249–8252

20.77 H. Tang, C. Joachim, J. Devillers: Interpretation of AFM images – the graphite surface with a diamond tip, Surf. Sci. **291** (1993) 439–450

20.78 U. Landman, W.D. Luedtke, E.M. Ringer: Atomistic mechanisms of adhesive contact formation and interfacial processes, Wear **153** (1992) 3–30

20.79 A.I. Livshits, A.L. Shluger: Self-lubrication in scanning-force-microscope image formation on ionic surfaces, Phys. Rev. B **56** (1997) 12482–12489

20.80 H. Tang, X. Bouju, C. Joachim, C. Girard, J. Devillers: Theoretical study of the atomic-force-microscopy imaging process on the NaCl(100) surface, J. Chem. Phys. **108** (1998) 359–367

20.81 R. Bennewitz, A.S. Foster, L.N. Kantorovich, M. Bammerlin, Ch. Loppacher, S. Schär, M. Guggisberg, E. Meyer, A.L. Shluger: Atomically resolved edges and kinks of NaCl islands on Cu(111): Experiment and theory, Phys. Rev. B **62** (2000) 2074–2084

20.82 U. Landman, W.D. Luetke, M.W. Ribarsky: Structural and dynamical consequences of interactions in interfacial systems, J. Vac. Sci. Technol. A **7** (1989) 2829–2839

20.83 M.R. Sørensen, K.W. Jacobsen, P. Stoltze: Simulations of atomic-scale sliding friction, Phys. Rev. B **53** (1996) 2101–2113

20.84 A. Buldum, C. Ciraci: Contact, nanoindentation, and sliding friction, Phys. Rev. B **57** (1998) 2468–2476

20.85 R. Komanduri, N. Chandrasekaran, L.M. Raff: Molecular dynamics simulation of atomic-scale friction, Phys. Rev. B **61** (2000) 14007–14019

20.86 T.H. Fang, C.I. Weng, J.G. Chang: Molecular dynamics simulation of nanolithography process using atomic force microscopy, Surf. Sci. **501** (2002) 138–147

20.87 B. Gotsmann, C. Seidel, B. Anczykowski, H. Fuchs: Conservative and dissipative tip-sample interaction forces probed with dynamic AFM, Phys. Rev. B **60** (1999) 11051–11061

20.88 C. Loppacher, R. Bennewitz, O. Pfeiffer, M. Guggisberg, M. Bammerlin, S. Schär, V. Barwich, A. Baratoff, E. Meyer: Experimental aspects of dissipation force microscopy, Phys. Rev. B **62** (2000) 13674–13679

20.89 M. Gauthier, M. Tsukada: Theory of noncontact dissipation force microscopy, Phys. Rev. B **60** (1999) 11716–11722

20.90 J.P. Aimé, R. Boisgard, L. Nony, G. Couturier: Nonlinear dynamic behavior of an oscillating tip-microlever system and contrast at the atomic scale, Phys. Rev. Lett. **82** (1999) 3388–3391

20.91 W. Denk, D.W. Pohl: Local electrical dissipation imaged by scanning force microscopy, Appl. Phys. Lett. **59** (1991) 2171–2173

20.92 S. Hirsekorn, U. Rabe, A. Boub, W. Arnold: On the contrast in eddy current microscopy using atomic force microscopes, Surf. Interface Anal. **27** (1999) 474–481

20.93 U. Dürig: Forces in scanning probe methods. In: *NATO ASI*, Ser. E, Vol. 286, ed. by H.J. Güntherodt, D. Anselmetti, E. Meyer (Kluwer, Dordrecht 1995) pp. 353–366

20.94 N. Sasaki, M. Tsukada: Effect of microscopic nonconservative process on noncontact atomic force microscopy, Jpn. J. of Appl. Phys. **39** (2000) L1334–L1337

20.95 B. Gotsmann, H. Fuchs: The measurement of hysteretic forces by dynamic AFM, Appl. Phys. A **72** (2001) 55–58

20.96 M. Guggisberg, M. Bammerlin, A. Baratoff, R. Lüthi, C. Loppacher, F.M. Battiston, J. Lü, R. Bennewitz,

E. Meyer, H.J. Güntherodt: Dynamic force microscopy across steps on the Si(111)-(7 × 7) surface, Surf. Sci. **461** (2000) 255–265
20.97 R. Bennewitz, S. Schär, V. Barwich, O. Pfeiffer, E. Meyer, F. Krok, B. Such, J. Kolodzej, M. Szymonski: Atomic-resolution images of radiation damage in KBr, Surf. Sci. **474** (2001) 197–202
20.98 T.D. Stowe, T.W. Kenny, J. Thomson, D. Rugar: Silicon dopant imaging by dissipation force microscopy, Appl. Phys. Lett **75** (1999) 2785–2787
20.99 B.C. Stipe, H.J. Mamin, T.D. Stowe, T.W. Kenny, D. Rugar: Noncontact friction and force fluctuations between closely spaced bodies, Phys. Rev. Lett **87** (2001) 96801
20.100 B. Gotsmann, H. Fuchs: Dynamic force spectroscopy of conservative and dissipative forces in an Al-Au(111) tip-sample system, Phys. Rev. Lett. **86** (2001) 2597–2600
20.101 B.N.J. Persson, A.I. Volokitin: Comment on "Brownian motion of microscopic solids under the action of fluctuating electromagnetic fields", Phys. Rev. Lett. **84** (2000) 3504
20.102 K. Yamanaka, A. Noguchi, T. Tsuji, T. Koike, T. Goto: Quantitative material characterization by ultrasonic AFM, Surf. Interface Anal. **27** (1999) 600–606
20.103 T. Drobek, R.W. Stark, W.M. Heckl: Determination of shear stiffness based on thermal noise analysis in atomic force microscopy: Passive overtone microscopy, Phys. Rev. B **64** (2001) 045401
20.104 T. Kawagishi, A. Kato, Y. Hoshi, H. Kawakatsu: Mapping of lateral vibration of the tip in atomic force microscopy at the torsional resonance of the cantilever, Ultramicroscopy **91** (2002) 37–48
20.105 F.J. Giessibl, M. Herz, J. Mannhart: Friction traced to the single atom, PNAS **99** (2002) 12006–12010
20.106 H.-J. Hug, A. Baratoff: Measurement of dissipation induced by tip-sample interactions. In: *Noncontact Atomic Force Microscopy*, ed. by S. Morita, R. Wiesendanger, E. Meyer (Springer, Berlin, Heidelberg 2002) p. 395

21. Nanoscale Mechanical Properties – Measuring Techniques and Applications

The first part of this chapter describes local (at the scale of nanometers) measurements of mechanical properties. It includes detailed state-of-the-art presentation and in-depth analysis of experimental techniques, results, and interpretations.

After a short introduction, the second part describes local mechanical spectroscopy using coupled Atomic Force Microscopy and ultrasound. This technique allows us to map quickly not only spatial distribution of the elasticity but anelastic properties as well. At one point in the sample, semi-quantitative measurements can be made as a function of the temperature. On the nanometer scale, results have close similitudes to bulk measurements and interpretable differences. Local elasticity and damping were measured during phase transition of polymer samples and shape-memory alloys.

The third part describes the "nano-Swiss cheese" method of measuring the elastic properties of such tubular nanometer size objects as carbon nanotubes and microtubules. It is probably the only experiment in which properties of single-wall nanotube ropes were measured as a function of the rope diameter. We extended this idea to biological objects, microtubules, and successfully solved major experimental difficulties. We not only measured the temperature dependency of microtubule modulus in pseudo-physiological conditions but also estimated shear modulus using the same microtubule with several lengths of suspended segments.

The fourth section demonstrates the scanning nanoindentation technique as applied to human bone tissue. This instrument allows performing topography scans and indentation tests using the identical tip. The available surface scan allows a high positioning precision of the indenter tip on the structure of interest. For very inhomogeneous samples, such as bone tissue, this tool provides a probe to detect local variations of the mechanical properties. The indentation test supplies quantitative parameters like elastic modulus and hardness on the submicron level. Local mechanical properties of compact and trabecular bone lamellae were tested under both dry and pseudo-physiological conditions.

Finally, last part is given to a discussion of future prospects and conclusions.

21.1 **Local Mechanical Spectroscopy by Contact AFM** 662
  21.1.1 The Variable-Temperature SLAM (T-SLAM) 663
  21.1.2 Example One: Local Mechanical Spectroscopy of Polymers 664
  21.1.3 Example Two: Local Mechanical Spectroscopy of NiTi 665

21.2 **Static Methods – Mesoscopic Samples** 667
  21.2.1 Carbon Nanotubes – Introduction to Basic Morphologies and Production Methods 667
  21.2.2 Measurements of the Mechanical Properties of Carbon Nanotubes by SPM 668
  21.2.3 Microtubules and Their Elastic Properties 673

21.3 **Scanning Nanoindentation: An Application to Bone Tissue** 674
  21.3.1 Scanning Nanoindentation 674
  21.3.2 Application of Scanning Nanoindentation 674
  21.3.3 Example: Study of Mechanical Properties of Bone Lamellae Using SN 675
  21.3.4 Conclusion 681

21.4 **Conclusions and Perspectives** 682

References 682

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Experiments measuring the mechanical properties at nanoscale are key to understanding mesoscopic materials and inhomogeneous materials.

The most prominent technique for such local measurements implements an Atomic Force Microscopy in static mode to obtain force–distance curves (f-d). Ideally this provides the force applied to the tip and the tip–sample distance allowing the local reduced Young's modulus to be determined. In practice, however, these values are not measured directly. Instead, the applied force is offset by adhesive and capillary forces. Furthermore, the tip–sample distance must be obtained by subtraction of the sample (Z-piezo) displacement and the deflection of the cantilever, neither of which are calibrated on most commercial instruments. Usually only the voltage applied to nonlinear and hysteretic Z-piezo and the uncalibrated cantilever deflection is available. These available data must be tediously calibrated and converted to real displacements and forces. The calibration procedure given by *Radmacher* [21.1] works well but only when applied to very compliant materials such as biological or polymer samples. An additional difficulty is that since one end of the cantilever is fixed, neither the orientation of the tip nor its position on the sample surface remains constant during f-d curve acquisition. Movement of the tip on the sample surface, therefore occurs not only vertically but also along the cantilever axis. As a result, applied contact mechanics may not be valid. Finally, uncertainty about the exact tip shape and radius complicate the procedure even further. Instrumental challenges are so significant that applying static AFM to obtain absolute values of the elastic modulus using commercial instruments is difficult at best, especially on stiff surfaces. And this, of course, is the motivation for developing of other techniques.

Although absolute values of mechanical properties are difficult to measure, relative measurements or maps (images of physical properties) are still very interesting. Using acoustic vibrations of the AFM sample surface one can access local elastic and anelastic properties. The first part of this chapter describes these techniques and applications.

Studies of mesoscopic specimens are even more challenging: it is difficult and time consuming to locate a sample, specially properly positioned. In the second part of the chapter, we used 'nano Swiss cheese' technique to get insight into the axial and shear modulus of several species of carbon nanotubes. The method was further extended to biological microtubules, where The experiment was performed in liquid and as a function of the temperature.

Reliable mechanical measurements can be obtained by combining the best of two worlds, AFM and nanoindenter. Classical nanoindenters use optical tip positioning, which are inadequate in the nanoworld. Scanning nanoindenter uses the same diamond tip for imaging (with microNewton forces) and measuring. Its application to human bones in liquid and 37 °C is described in the third part of this chapter.

One should underline the importance of AFM linearity and stability for such experiments: only good designs may limit frustration and experiment time of courageous PhD students, and lot of improvements are still lacking.

21.1 Local Mechanical Spectroscopy by Contact AFM

Mechanical properties of solids (elasticity, anelasticity, plasticity) are generally measured on macroscopic samples. But many phenomena in materials science require measurements of mechanical properties at the surface of a material or at the interfaces between thin layers deposited on a surface. High spatial resolution is also important, for example in the cases of multiphased materials or composite materials, phase transitions, lattice softening in shape-memory alloys, precipitation in light alloys, and glass transition of amorphous materials.

In the case of multiphased materials, such as nanomaterials, composites, alloys, or polymer blends, the location of the dissipative mechanism in one phase must be determined either through modeling or by separately studying each phase, when possible, without changing its behavior. The latter is only possible in a limited number of cases due to the interactions between the different phases within a material. To give an example, the global behavior of a composite is mostly driven by the stress transfer properties between the reinforcement and the matrix, which are controlled by the local mechanical properties in the interface region and in particular the dynamics of the structural defects in this area. It is obviously impossible to prepare a sample only composed of interface regions. Therefore a method for locally studying the dynamics of the structural defects will thus provide important steps in the understanding and the improvement of such materials.

Different techniques based on Scanning Probe Microscopies (SPM) have been developed to probe the elastic and anelastic properties of surfaces, interfaces, or phases of inhomogeneous materials at the micrometer and the nanometer scales. Scanning Acoustic Microscopy (SAM), first developped in the mid-1970s, allows one to study the materials properties at the micrometer scale.

Among the different ways explored to study local mechanical properties of materials, several groups have recently used techniques based on Scanning Force Microscopy (SFM) [21.2]. For most of these, the focus has been placed on "elasticity," using the so-called Force Modulation Mode (FMM) at low frequencies [21.3]. Force modulation mode generally uses a large amplitude (greater than 10 nm), low frequency (some kHz) vibration of the sample underneath the SFM tip. The component of the tip motion at the excitation frequency and the tip mean position are simultaneously recorded, giving several images of the sample surface. In particular, the in-phase and out-of-phase components of force modulation mode at room temperatures have been interpreted in terms of stiffness ("elasticity") and damping ("viscoelasticity") [21.4, 5]. But, it has been recently shown by *Mazeran* et al. [21.6] that the contrast of force modulation mode is dominated by friction properties, giving only little information on the elasticity. Consequently, some care has to be taken in the interpretation of these low-frequency studies. A way to suppress the influence of friction on the contrast is to use smaller amplitudes (some Å) at higher frequencies [21.7]. Scanning Local-Acceleration Microscopy (SLAM) implements this idea [21.8]: SLAM is a modification of contact-mode scanning force microscopy. Its principle is to vibrate the sample at a frequency just above the resonance of the tip–sample system. In this case, the inertia of the tip prevents it from completely following the imposed high frequency displacement, inducing nonnegligible forces and giving rise to elastic deformation of the sample. Contact stiffness is obtained from the measure of the residual displacement of the tip. Mapping the contact stiffness at different temperatures with SLAM [21.9] has allowed local mechanical spectroscopy. Some other techniques also use high frequencies but with different approaches to image elasticity at room temperature [21.7, 10, 11]. Each of these high-frequency techniques is capable of mapping properties such as stiffness or adhesion at constant temperature with a very high lateral resolution.

21.1.1 The Variable-Temperature SLAM (T-SLAM)

The technique described here combines the lateral resolution of scanning force microscopy with the physical information available from temperature ramps. It is the variable-temperature SLAM (T-SLAM) [21.12, 13]. Ramping the temperature of the sample during a SLAM measurement and acquiring both the amplitude and the phase of the tip's motion allows one to obtain local mechanical spectroscopy data. A simple model enables the interpretation of the measurement in terms of material properties.

T-SLAM is based on SLAM [21.8, 14], using a variable temperature sample holder [21.9, 15]. An ultrasonic transducer is placed beneath the sample in a commercial scanning force microscope (Fig. 21.1) and excited by means of a function generator. The ultrasound is



Fig. 21.1 *Schematic diagram of T-SLAM*. Ultrasound is generated with a transducer connected to a function generator and placed beneath the sample. The motion of the scanning force microscope tip is detected optically. The detection signal is fed to a lock-in amplifier, which extracts amplitude and phase relative to the transducer's motion. The temperature is controlled with a small resistive heater and measured with a thermocouple. The rest of the microscope head, to which the tip, the laser and the photodiode are attached, is not represented in this diagram

transmitted through the sample, forcing periodic local deformation of the sample's surface underneath the tip. The motion of the scanning force microscopy tip is detected optically by laser beam deflection from the backside of the cantilever. The detection signal is then fed to a lock-in amplifier, which extracts the tip's amplitude (related to elasticity) and phase (related to viscoelasticity) relative to the transducer's motion. The transducer's typical frequency is 825 kHz. This installation can operate in two ways, either by mapping the amplitude and phase of the signal as a function of position at fixed temperature or by recording the amplitude and phase as a function of temperature at a "fixed" location. The first method is known as "SLAM imaging," where the output signal of the lock-in is fed into an auxiliary data acquisition channel of the microscope. An extra computer is used to store local mechanical spectroscopy data as a function of the temperature at a fixed location and to control temperature. The heat is produced with a small resistive heater below the transducer, and the temperature is measured with a thermocouple. The sample must be prepared with a sufficiently low surface roughness in order to avoid artifacts in the measurements due to the sample's topography. Due to the geometry of the contact, SLAM measures only a small volume near the surface. Viewing SLAM as a very fast indentation measurement, the probed volume is approximately a half-sphere with a radius of $10a$, where a is the contact radius between tip and sample [21.16]. The typical value of a is some nm. So even if the sample is a thick film, T-SLAM gives access to the near-surface mechanical properties that may differ from bulk.

The mechanical properties of the deformed region are obtained from the measure of the residual displacement of the tip. The tip vibration amplitude d_1 is related to the contact stiffness, proportional to the dynamic elastic modulus, while the phase lag φ between the tip motion and the surface motions is related to the internal friction (energy dissipation inside the deformed volume). Mapping d_1 and φ at different temperatures with T-SLAM allows the study of the homogeneity of mechanical relaxations or of phase transitions. By recording d_1 and φ as a function of temperature at a fixed location, local mechanical spectroscopy can be performed.

When used just above the first resonance of the tip–sample system, the SLAM system can be described and analyzed using a point mass rheological model [21.9, 12], which allows one to obtain the equation relating the damping (loss factor η') to the measured parameters

$$\eta' = \left(\frac{1}{2}\frac{k_e}{k_c - m\omega^2}\right)\frac{\sin\varphi}{d_1/z_1}\,, \tag{21.1}$$

where ω is the measurement frequency, k_c is a parameter related to the elastic modulus of the AFM cantilever and k_e to the elastic modulus of the sample, z_1 is the transducer vibration amplitude, and $m = k_c/\omega_c^2$ is the equivalent point mass of the tip, where ω_c is the free resonant frequency of the cantilever.

The principal limitation of (21.1) comes from the model assumption that the cantilever is a point mass restricted to vertical displacements. Due to the possible lateral displacements of the tip [21.6] or the existence of other vibrational modes of the cantilever, which are not described by the point mass model, (21.1) is only reliable for the measurement of the damping just above the first resonance of the tip–sample system. In order to obtain a quantitative measurement of this quantity in a larger frequency spectrum, it is necessary to develop a more realistic model of the cantilever interacting with the sample surface such as, for example, the model presented by *Dupas* et al. [21.17], in which the cantilever is modeled as a beam.

21.1.2 Example One: Local Mechanical Spectroscopy of Polymers

Figure 21.2 shows local mechanical spectra [21.13, 18] obtained in bulk technical PVC (including plasticizer and pigments and taken off-the-shelf) as a function of temperature (Fig. 21.2a) and a Differential Scanning Calorimetry (DSC) measurement of the same sample (Fig. 21.2b). The mechanical measurement (Fig. 21.2a) displays the amplitude of vibration of the SLAM tip (thin line) and its phase lag (thick line) as a function of temperature. Four temperature domains can be identified. At lower temperatures (1), the first domain shows a phase lag peak associated with a decrease of amplitude. The second temperature (2) domain corresponds to a zone where the vibration amplitude increases, without any variation in the phase lag. The third temperature domain (3) is characterized by a large phase lag peak and a significant decrease of vibration amplitude. The last temperature domain (4) shows a slow increase in the phase lag without variation of the vibration amplitude.

The calorimetry curves (b) display the heat flow as a function of temperature for the same material but at a larger size scale. For clarity, the same temperature do-



Fig. 21.2 **(a)** *Local mechanical spectroscopy spectra as a function of temperature of a technical PVC*: The vibration amplitude is displayed as a *thin line* and the phase lag as a *thick line*. Four temperature domains can be distinguished: From left to right, a small "vibration amplitude" decrease is associated with a first "phase lag" peak (1), in the next domain, "vibration amplitude" increases (2), then a large decrease of "vibration amplitude" is associated with a large "phase lag" peak (3) and finally "phase lag" increases slowly (4). **(b)** *DSC measurements of the same sample*. For clarity, the temperature domains observed on Fig. 21.5a have been reported. The graph displays the first (*dashed line*) and the second (*solid line*) heating. The glass transition can easily be recognized around 340 K (labeled *A*), slightly below the temperature range of domain 3. An irreversible endothermic relaxation takes place in the same temperature range (only visible on the first run). A reversible endothermic event occurs around 380 K

mains have been reported on the graph. The dashed line displays the first heating, where both reversible and irreversible events are present; the solid line shows the second heating, where only reversible events are still present. On the solid line, an endothermic event (labeled A) can be observed near the border between temperature domains 2 and 3. An irreversible endothermic relaxation is superimposed with (A) on the first heating. A reversible endothermic peak is observed around 380 K, in domain 4. The endothermic event (A) has the characteristics of a glass transition: the specific heat goes from one value to another without a peak [21.19]. The glass transition temperature of this PVC is, therefore, approximately 340 K. The irreversible relaxation occurring in the same temperature range is certainly associated with physical aging or structural relaxation. The reversible peak at higher temperature is associated with the melting of the small crystalline volume fraction.

These local mechanical spectroscopy results are in good qualitative agreement with macroscopic global measurements [21.13, 18]. They yield the same information as the macroscopic global measurements, but from a much smaller volume, and allow as a consequence the location of the different mechanisms. Both measurements (local and global) show a peak in phase for the primary and secondary relaxations, connected with a large decrease of the stiffness for the primary relaxation and a much smaller one for the secondary relaxation. Plasticity induces an increase of the phase lag in both cases. The temperatures observed for the relaxation related to the glass transition compare well with the calorimetric data. Based on all these examples, there is no doubt that the amplitude and phase lag of T-SLAM are functions of the stiffness and damping. In this regard, T-SLAM provides an extension of the global method, allowing location of dissipative phenomena and study of the spatial homogeneity of phase transitions or of relaxations. This will bring new insight into the field of inhomogeneous or composite materials. In addition, T-SLAM measures only a small volume near the surface. So even if the sample is a thick film, T-SLAM gives access to the near-surface mechanical properties, which may differ from bulk properties. This will bring interesting perspectives to the still debated field of surface dynamics.

21.1.3 Example Two: Local Mechanical Spectroscopy of NiTi

Near-stoichiometric NiTi alloys exhibit a martensitic phase transformation between a low-temperature monoclinic phase, called martensite, and a high temperature cubic phase with B2 structure, called austenite (1). This transformation is responsible for the shape memory and pseudo-elastic effects in deformed NiTi alloys. Upon transformation to the martensitic phase, an intermediate rhombohedral (R) phase can be formed [21.20, 21]. Although *Bataillard* [21.21] tends to demonstrate that the R phase is finely dispersed inside the material, a controversy remains over the spatial scale at which the decomposition of the transformation occurs. Another puzzling question concerns the transformation itself. Optical microscopy observation suggests that the transformation occurs very suddenly inside an austenite grain. This has led to the concept of "military transformation." The width of the globally measured transformation would then be a sum of different narrow contributions coming from different places inside the sample. This image is, however, not universally accepted.

A measurement inside one single grain of a polycrystal would be a way to address these questions. Both the spatial scale of the R phase distribution and the "military" character of the transformation will have an effect on the result of such a measurement. This is the reason for which local mechanical spectroscopy measurements of the martensitic phase transition of NiTi by T-SLAM have been performed [21.12, 22]. They are presented in Fig. 21.3. The global transformation behavior of NiTi is defined by calorimetry spectra (Fig. 21.3b, temperature scanning rate 10 K/min).

The vibration amplitude ("elasticity") and the phase lag ("internal friction") are shown in the top and bottom curves, respectively. The presented data is incomplete due to experimental limitations. A phase lag peak can be observed upon heating at approximately 370 K, associated with a change in the vibration amplitude level. This event can be correlated with the phase transformation from martensite to austenite observed by calorimetry (Fig. 21.3b). Upon cooling, no event is observed around 370 K: the vibration amplitude is stable and the phase lag curve does not exhibit any peak. But, an intense phase lag peak can be observed upon cooling near 330 K, associated with a restoration of the vibration amplitude level characteristic of the martensite. This event correlates with the phase transformation from austenite to martensite observed by calorimetry. A change in the vibration amplitude spectrum is correlated with each event on the phase lag spectrum. Two main features should be noted. First, the transformation peaks observed with the SLAM method are narrower than those observed with the (global) calorimetry measurement. Second, the measured temperatures for the local peak are located on the high temperature side of the peaks measured by calorimetry. Details of the two transformation peaks are displayed in Figs. 21.3c and 21.3d. The reverse transformation (Fig. 21.3c) is characterized by a change in the vibration amplitude level and a phase lag peak. This peak (A1) may have a shoulder on the low temperature



Fig. 21.3 **(a)–(b)** *Comparison of the local mechanical spectroscopy measurements of* NiTi *with calorimetric experiment*. **(a)** Both the reverse and direct transformation are associated with a phase lag peak and a modulus variation. **(b)** Calorimetric measurement of the same sample. **(c)–(d)** *Zoom on the reverse* **(c)** *and direct* **(d)** *transformation's temperature ranges*. The peak (A1) may exhibit a shoulder on the low temperature side (A2). The direct transformation is characterized by a recovery of the original vibration amplitude and a complex phase lag spectrum, formed of two main maxima, noted R and M. Peaks a,b,c,d,e are a substructure of the M peak

side (A2). A small decrease of the vibration amplitude may precede this increase. But, the magnitude of this softening and the very low intensity of peak A2 are too small to exclude experimental artifacts. The direct transformation (Fig. 21.3d) displays a recovery of the original vibration amplitude and a complicated phase lag maximum.

The correlation of the transition temperatures measured by calorimetry and the local mechanical spectroscopy lead to the conclusion that the peaks observed in phase lag and the change in vibration amplitude originate from the martensitic phase transition. At the scale of the observation, the martensite transforms into austenite around 370 K (A1 peak) and the austenite transforms into martensite close to 332 K (M peak), with the formation of the rhombohedral R phase at 337 K (R peak). The peaks A2 and e could be linked to the presence of two different types of martensite as already observed elsewhere [21.20, 21]. It is striking to note that all the events observed in macroscopic experiments seem to be reproducible at the scale of observation, namely less than $10^{-3}\ \mu m^3$. In particular, this would confirm that the R phase precipitates are very finely distributed in the austenite matrix as observed by Bataillard [21.21]. Otherwise the R peak could not be observed reproducibly using such a technique. The local measurement differs from global ones in at least two aspects: first, the width of the transformation temperature range is smaller; second, the M peak exhibits a substructure.

Global internal friction measurements on these materials have given spectra with peaks having a similar breadth as the calorimetry peaks [21.23], whereas the peaks measured locally are narrower. This is easy to understand if the martensitic transformation occurs inhomogeneously inside the sample. Grains tend to transform at different temperatures depending on their stress state. As the local measurement has sufficient spatial resolution to probe a single grain inside the material, it is logical that the transformation occurs over a narrower temperature range than in a global experiment probing a large number of grains.

The substructure in the M peak could have three origins: (i) the technique is sensitive to the mechanical relaxation inside newly formed plates, such as stress relaxation by twin motion; (ii) the probed volume contains several martensite plates that grow one by one, each with its own, distinct "elementary" peak (a, b, etc.); (iii) the analyzed region of the sample surface changes due to thermal drifts, therefore probing the transformation of several growing martensite plates, leading to multiple "elementary" peaks.

21.2 Static Methods – Mesoscopic Samples

21.2.1 Carbon Nanotubes – Introduction to Basic Morphologies and Production Methods

Carbon nanotubes (CNTs) are the newest form of carbon, found in 1991 by *Iijima* [21.24]. Because of their remarkable properties, this discovery has opened whole new fields of study in physics, chemistry, and material science. They possess a unique combination of small size (diameters ranging from ∼ 1 to 50 nm with lengths up to ∼ 10 µm), low density (similar to that of graphite), high stiffness, high strength, and a broad range of electronic properties from metallic to p- and n-doped semiconducting. Their potential field of application is immense and includes reinforcing elements in high strength composites, electron sources in field emission displays and small X-ray sources, ultra-sharp and resistant AFM tips with high aspect ratios, gas sensors, and components of future, nanoscale electronics. In addition, they represent a widely used system for studying fundamental physical phenomena on the mesoscopic scale. Following advances in manufacturing and processing they are likely to be integral to many devices we use in our everyday life.

From the structural point of view, carbon nanotubes can be thought of as rolled up single sheets of graphite, *graphene*. They can be divided in two distinct groups. The first, multiwalled carbon nanotubes (MWNT), exhibit a Russian doll-like structure of nested, concentric tubes, Fig. 21.4a and b. They were also the first CNT to be discovered experimentally. The interlayer spacing can range from 0.342 to 0.375 nm, depending on the diameter and number of shells comprising the tube [21.25]. For comparison, the interlayer spacing in graphite is 0.335 nm, suggesting relatively weak interaction between individual shells. This fact has been corroborated by studies of mechanical and electronic properties of CNTs.



Fig. 21.4a–d TEM images and schematic drawings of cross sections for different morphologies of carbon nanotubes. **(a)** and **(b)** Multiwalled carbon nanotubes, consisting of concentric, nested tubes (MWNT). **(c)** and **(d)** ropes of single-walled carbon nanotubes, consisting of single carbon nanotubes bundled up in ropes and held together by van der Waals interaction

The second type of carbon nanotubes is in the basic form of a rolled-up graphitic sheet: a single-walled CNT (SWNT). During the production, their diameter distribution is relatively narrow so they often bundle in the form of crystalline "ropes" [21.26], Fig. 21.4c and d, in which the single tubes are held together by van der Waals interaction.

There are several distinct classes of production methods. The earliest is based on the cooling of carbon plasma. When voltage is applied between two graphitic electrodes in an inert atmosphere, they gradually evaporate and form plasma. On cooling, soot containing multiwalled nanotubes is formed [21.24]. If the anode is filled with catalysts such as, for example, cobalt of iron particles, SWNT ropes form. Another way of producing CNTs from carbon plasma is by laser ablation of a graphitic target [21.26]. It is considered that, in general, these methods produce CNTs of higher quality albeit in very small quantities and without the possibility of scale-up to industrial production. Other methods are based on chemical vapor deposition (CVD), a catalytic decomposition of various hydrocarbons, e.g. methane or acetylene mixed with nitrogen or hydrogen in the presence of catalysts [21.27]. This method offers the possibility of controlling the growth of nanotubes by patterning the catalyst [21.28] and is therefore more suitable for producing nanoscale structures with integrated CNTs. This method is also capable of producing CNTs in industrial quantities. Their main disadvantage is the higher concentration of defects, which as a consequence diminish their mechanical properties.

21.2.2 Measurements of the Mechanical Properties of Carbon Nanotubes by SPM

Mechanical measurements on CNTs performed with the AFM have confirmed theoretical expectations [21.29] of their superior mechanical properties. They involve measurements of deformations under controlled forces by bending immobilized carbon nanotubes either in the lateral [21.30] or normal direction [21.31] and also tensile stretching of CNTs fixed on their two ends to AFM tips observed in an electron microscope [21.32].

It is not obvious that continuum mechanics and its concepts like Young's, shear moduli, and tensile strength should work on the nanoscale. In order to apply them, one should also define the "thickness" of the nanotube's walls, a graphene sheet, in the frame of the continuous beam approximation. Most scientists working in this field are using the value 0.34 nm, close to the interlayer separation in graphite as the thickness of a nanotube. When comparing different results, however, one has to bear in mind that to convert relatively precise force–displacement measurements into macroscopic quantities like Young's or shear modulus, one has to introduce various geometrical factors, including diameter and length. Even a small imprecision in their determination is very unforgiving because the diameter d enters into equations for beam deformation as d^4 and length l as l^3, leading to large uncertainty in final results.

The first quantitative measurement of the Young's modulus of carbon nanotubes was reported by *Wong* et al. [21.30] in which they laterally bent MWNTs and SiC nanorods (similar in dimensions to MWNTs) deposited on flat surfaces. MWNTs were first randomly dispersed on a flat surface of MoS_2 single crystals that were used because of their low friction coefficient and exceedingly flat surface. Friction between the tubes and substrate was further reduced by performing the measurements in water. Tubes were then pinned on one side to this substrate by a deposition of an array of square pads through a shadow mask, Fig. 21.5a–c. AFM was used to locate and characterize the dimensions of protruding tubes. The beam was deformed laterally by the AFM tip, until at a certain deformation the tip would pass over the tube, allowing the tube to snap back to its relaxed position. During measurements, the force–distance curves were acquired at different positions along the chosen beam, Fig. 21.5d–e. Maximum



Fig. 21.5a–e Schematic of the experiment performed by *Wong* et al. [21.30] **(a)** nanotubes were dispersed on a substrate and pinned down by a deposition of SiO pads. **(b)** Optical micrograph showing the pads (*light*) and MoS_2 substrate (*dark*). The scale bar is 8 µm long. **(c)** AFM image of a SiC nanorod protruding from the pad. The scale bar is 500 nm long. The same experimental setup was used for elastically deforming MWNTs. **(d)** The tip shown as a triangle moves in the direction of the arrow. The lateral force is indicated by the trace at the bottom. Before the tip contacts the beam, the lateral force remains constant and equal to the friction force. During the bending a linear increase in the lateral force with deflection is measured. After the tip has passed over the beam the lateral force drops to its initial value and the beam snaps back to its equilibrium position. **(e)** Schematic of a pinned beam with a free end. The beam of length L is subjected to a point load P at $x = a$ and friction force f (abstracted with permission from [21.30] © American Association for the Advancement of Science)



Fig. 21.6 **(a)** A series of lateral force distance curves acquired by *Wong* et al. [21.30] for different positions along a MWNT. **(b)** The lateral spring constant as a function of position on the beam. The curve is a fit to (21.3) (abstracted with permission from [21.30] © American Association for the Advancement of Science)

deflection of the nanobeam can be controlled to a certain degree by the applied normal load, and in this way tube breaking can be avoided or achieved in a controlled manner. The applied lateral load P in terms of lateral displacement y at the position x along the beam is given by the equation:

$$P(x,y) = 3EI\frac{y}{x^3} + \frac{f}{8}\left(x - 4L - 6\frac{L^2}{x}\right)\,, \tag{21.2}$$

where E is the Young's modulus of the beam, I the second moment of the cross section, equal to $\pi d^4/64$ for a solid cylinder of diameter d and f the unknown friction force, presumably small due to the experimental design. The lateral force, Fig. 21.6a, is known only up to a factor of proportionality because the AFM lever's lateral force constant wasn't calibrated for these measurements. This uncertainty and the effect of friction were eliminated by calculating the nanobeam lateral force constant:

$$\frac{\mathrm{d}P}{\mathrm{d}y} \equiv k = \frac{3\pi d^4}{64x^3}E \tag{21.3}$$

shown in Fig. 21.6b.

The mean value for the Young's modulus of MWNTs was $E = 1.3 \pm 0.6\,\mathrm{TPa}$, similar to that of diamond ($E = 1.2\,\mathrm{TPa}$). For larger deformations, discontinuities in bending curves were also observed, attributed to elastic buckling of nanotubes [21.33].

In another series of experiments, *Salvetat* et al. measured the Young's modulus of isolated SWNTs and SWNT ropes [21.31], MWNTs produced using different methods [21.34], and the shear modulus of SWNT ropes [21.35]. The experimental setup that enabled them to perform measurements on such a wide range of CNT morphologies involved measuring the vertical deflection of nanotubes bridging holes in a porous membrane.

In their measurement method, they suspended CNTs in ethanol and deposited them on the surface of a well-polished alumina Al_2O_3 ultrafiltration membrane. Tubes adhered to the surface due to the van der Waals interaction occasionally spanning holes, Fig. 21.7a. After a suitable nanotube had been found, a series of AFM images was taken under different loads, in which every image would thus correspond to the surface (and the tube) under a given normal load. Extracted linescans across the tube revealed the vertical deformation, Fig. 21.7b. For the range of applied normal loads, the deflection of a thin, long nanotube at the midpoint δ as



Fig. 21.7 **(a)** An AFM image of a CNT lying on a porous alumina [21.35] filter. **(b)** Measured dependence of vertical deflection on the applied nominal force. The inset shows a comparison between linescans taken on the tube and over a hole [21.34] (abstracted with permission **(a)** from [21.35] © 1999 American Physical Society, **(b)** from [21.34] © 1999 Wiley)

a function of the normal force F can be fitted using the clamped beam formula [21.36]:

$$\delta = \frac{FL^3}{192EI} , \tag{21.4}$$

where L is the suspended length.

The fitted line does not pass through the origin because the force acting on the nanotube is not equal to the nominal force alone; it contains a constant term arising from the attractive force between the AFM tip and the tube. The tube's deflection should also contain a term corresponding to the interaction between the tube and the substrate, but this is generally regarded as negligible.

This variable load imaging technique is advantageous for obtaining quantitative information as one is assured that the AFM tip is in the desired location when deforming the tube. Equation (21.4) is valid only if the tubes adhere well to the substrate, confirmed by the fact that the images reveal no displacement of the parts of the tube in contact with the membrane.

Using this technique, Young's modulus of 1 TPa was found for SWNTs. Values for the MWNTs show a strong dependence on the amount of disorder in the graphitic layers: an average value of $E = 870$ GPa was found for the arc-discharge grown tubes, while the catalytically grown MWNTs, known to include a high concentration of deffects, can have a Young's modulus as low as 12 GPa.

For the deflection of SWNT ropes, an additional term in the bending formula has to be taken into account because of the influence of shearing between the tubes comprising the rope. Single CNTs are held together in the tube only by weak, van der Waals interactions. Ropes, therefore, behave as an assembly of individual tubes rather than as a thick beam. The deflection can be modeled as a sum of deflections due to bending and shearing [21.36]:

$$\begin{aligned}\delta &= \delta_{\text{bending}} + \delta_{\text{shearing}}\\ &= \frac{FL^3}{192EI} + f_s \frac{FL}{4GA} = \frac{FL^3}{192E_{\text{bending}}I} ,\end{aligned} \tag{21.5}$$

where f_s is a shape factor, equal to $10/9$ for a cylinder, G the shear modulus and A the area of the beam's cross section. E_{bending} is the effective, bending modulus, equal to Young's modulus in the case in which the influence of shearing can be neglected (for thin, long ropes).

The Young's and the shear modulus can thus be extrapolated by measuring the E_{bending} of an ensemble of ropes with different diameter to length ratios: for thin ropes one obtains the value of the Young's modulus, while for the thick ones, the E_{bending} approaches the value of G on the order of 10 GPa (see Fig. 21.8).

Walters et al. pinned ropes of single-wall nanotubes beneath metal pads on an oxidized silicon surface, then released them by wet etching, Fig. 21.9a. The SWNT rope was deflected in the lateral direction using an AFM tip, Fig. 21.9b. As the suspended length is on the order of μm, the SWNT rope can be modeled as an elastic string stretched between the pads. Upon deformation all of the strain goes into stretching. In the simple case of a tube lying perpendicular to the trench and the AFM tip deforming the tube in the middle, the force F exerted on



Fig. 21.8 Values of the shear modulus for 12 SWNT ropes of different diameters. The measured E_{bending} of thin ropes corresponds to E, while for thick ropes one obtains the value of shear modulus G (abstracted with permission from [21.35] © 1999 American Physical Society)



Fig. 21.9 **(a)** SEM image of a SWNT rope suspended over trench in silicon before and **(b)** after being deformed past its elastic limit. **(c)** Lateral force on a single-wall nanotube rope as a function of AFM tip displacement (abstracted with permission from [21.37] © American Institute of Physics)

the tube by the AFM tip is given by the expression:

$$F = 2T\sin\theta = 2T\frac{2x}{L} \approx \frac{8kx^3}{L_0}\,, \qquad (21.6)$$

where T is the tension in the string, L_0 its equilibrium length, k the spring constant and x the lateral deflection in the middle. Using this setup, they deformed SNWT ropes to the maximal strain of $5.8 \pm 0.9\,\%$ and determined a lower bound of 45 ± 7 GPa on the tensile strength, assuming a value of 1.2 TPa for the Young's modulus.

Kim et al. used a setup in which the SWNT rope was embedded in metallic electrodes deposited on a silicon substrate coated with poly(methylmethacrylate) (PMMA). In their experiment the tube can also be modeled as an elastic string. Using an AFM tip, they vertically deformed the rope and obtained an estimate of $E = 0.4$ TPa for the Young's modulus of an SWNT rope.

Finally, the first direct measurements of the elastic properties of CNTs that haven't relied on the beam or stretching string setup involved deforming MWNTs [21.38] and SWNT ropes [21.32] under axial strain. This was achieved by identifying and attaching opposite ends of MWNTs or SWNT ropes to two AFM tips, all inside a SEM. The AFM tips were integrated with different cantilevers, one rigid with a spring constant above 20 N/m and the other compliant with a spring constant of 0.1 N/m, Fig. 21.10. The rigid lever was then driven using a linear piezomotor. On the other end, the compliant lever bent under the applied tensile load. The deflection of the compliant cantilever – corresponding to the force applied on the nanotube – and the strain of the nanotube were simultaneously measured. The force F is calculated as $F = kd$ where k is the spring constant of the flexible AFM lever and d its displacement in the vertical direction. The strain of the nanotube is $\delta L/L$, Fig. 21.11. From the stress–strain curves obtained in this fashion, Fig. 21.11b, Young's moduli ranging from 270–950 GPa were found. Exami-



Fig. 21.10 **(a)** A SEM image of a MWNT mounted between two opposing AFM tips. **(b)** A close-up of the region indicated by a rectangle in **(a)** (abstracted with permission from [21.38] © 1999 American Association for the Advancement of Science)



Fig. 21.11 **(a)** The principle of the experiment performed by *Yu* et al. As the rigid cantilever is driven upward, the lower, compliant cantilever bends by the amount d and the nanotube is stretched by δL. As a result, the nanotube is strained by $\delta L/L$ under the action of force $F = kd$, where k is the elastic constant of the lower AFM lever. **(b)** Plot of stress vs. strain curves for different individual MWNTs (abstracted with permission from [21.38] © 1999 American Association for the Advancement of Science)

nations of the same broken tubes inside a TEM revealed that nanotubes break with the "sword in sheath" mechanism, where only the outer layer appears to have carried the load. After it breaks, pullout of inner shells follows. An average bending strength of 14 GPa and axial strengths up to 63 GPa were found.

Firm attachment of nanotubes to AFM tips was ensured by a deposition of carbonaceous material induced by the electron beam concentrated in the contact area [21.40].

All these measurements of the elastic properties of carbon nanotubes are summarized in Table 21.1.

Before comparing them, it should be noted that the absolute values of these mechanical constants have relatively large uncertainties because of the huge influence of the precision of determining tube diameters and lengths on the final result. Also, the cited values represent mean values of results obtained on several tubes, with the exceptions of the lowest value given for catalytically grown MWNTs by Salvetat et al. [21.31], a single value for an individual SWNT rope from *Kim* et al. [21.39], and the lowest and highest values from *Yu* et al. [21.38]. One also has to bear in mind that concepts

Table 21.1 Summary of the mechanical properties of carbon nanotubes measured using SPM methods

Young's modulus *E* (GPa)	Shear modulus *G* (GPa)	Tensile strength σ (GPa)	Nanotube type	Deformation method	Reference
1,300±600	–	–	MWNTs arc grown	Lateral bending	[21.30]
1,000±600	–	–	SWNTs	Normal bending	[21.31]
1,000±600	∼ 1 GPa		SWNT ropes	Normal bending	[21.35]
870±400	–	–	MWNT arc-grown	Normal bending	[21.31]
12±6	–	–	MWNT catalytic	Normal bending	[21.31]
–	–	45±7	SWNT rope	Lateral bending	[21.37]
400	–	–	SWNT rope	Normal bending	[21.39]
1,020	–	30	SWNT ropes	Tensile loading	[21.32]
270–950	–	11–63	MWNTs arc-grown	Tensile loading	[21.38]

like Young's and shear moduli and tensile strength were introduced for describing macroscopic and continuous structures. Their application for describing mesoscopic objects like nanotubes, therefore, has its limitations.

The methods presented above are all in their nature "single-molecule" methods, in the sense that they measure properties of individual objects. A result of a single experiment, therefore, represents properties of a particular object and differs from case to case because of, for example, defects coming from production and purification, or for more prosaic reasons such as experimental errors. In order to perform comparisons, therefore, it is more practical to deal with values averaged for multiple tubes. The average values for the Young's modulus of high quality tubes are, within the experimental error, all on the order of 1 TPa, close to that of diamond (1.2 TPa), while the tensile strength can be 30 times higher than that of steel (1.9 GPa). Catalytically grown MWNTs with the Young's modulus that can be as low as 12±6 GPa are definitely disappointing and show that the production method plays an important role in the quality of carbon nanotubes from the point of view of their mechanical properties.

Future improvements in large scale production and processing are therefore necessary before applying them as the ultimate reinforcement fiber. Even so, the progress in measuring the mechanical properties of CNTs will continue to be closely related to, and often motivate, the progress in nanoscale manipulation in general.

21.2.3 Microtubules and Their Elastic Properties

Microtubules are a vital biological nanostructure, similar in dimension and shape to carbon nanotubes. In fact, the first name given to carbon nanotubes by their discoverer Iijima was "microtubules of graphitic carbon." From the structural point of view, they are much more complicated, as is common for biological structures. They self-assemble in buffers maintained at the physiological temperature of 37 °C out of protein subunits, α and β-tubulin, each having a molecular weight of 40 kDa. These protein subunits are bound laterally into protofilaments, which in turn are arranged in a shape of a hollow cylinder with an external diameter of 25 nm and an internal diameter of 15 nm. Microtubules are a remarkable material: inside living cells, their length incessantly fluctuates; they can even completely disassemble and consume energy in the form of GTP.

Together with actin and intermediate filaments, microtubules constitute the cellular cytoskeleton. In addition, they perform various unique vital functions: they act as tracks along which molecular motors move, they help pull apart chromosomes during cell division and form bundles that propel sperm and some bacteria. All these roles are determined by their structure and mechanical properties. Yet, after more than a decade, there is still a large discrepancy in the values of their Young's modulus reported in the literature. Several methods have been applied, such as bending or buckling microtubules using optical tweezers [21.42], hydrodynamic flow [21.43], thermally induced vibrations or shape fluctuations [21.44], buckling in vesicles [21.45], or squashing with an AFM tip [21.46]. These methods yielded results ranging from 1 MPa [21.46] to several GPa [21.42].

Since microtubules are geometrically similar to nanotubes, *Kis* et al. [21.41] used the suspended tube configuration. Microtubules were deposited on porous membranes, and AFM images were acquired under different nominal normal loads. All the measurements were performed in liquid and at controlled temperatures, in order to prevent the degradation of proteins, so the substrate had to be functionalized in order to ensure good adhesion between the tubes and the support. They used



Fig. 21.12 **(a)** A pseudo 3-D rendering of a single microtubule suspended over four different-sized holes in PMMA. **(b)** From the variation of the $E_{bending}$ with varying length, the shear and the Young's modulus have been determined for the microtubule displayed in **(a)** (abtracted with permission from [21.41] © 2002 American Physical Society)

silicon with a layer of PMMA as a support. Slits were prepared in PMMA using electron-beam lithography, providing the possibility to measure the elastic response of individual microtubules lying over four different-sized holes ranging from 80–200 nm across and 400 nm deep, Fig. 21.12.

Clearly the results are dependent on the hole diameter, which could only result from a shear component within the microtubules. Simplifying (21.5), the deformation of microtubules can be modeled as:

$$\frac{1}{E_{\text{bending}}} = \frac{1}{E} + \frac{10}{3} \frac{D_{\text{ext}}^2 + D_{\text{int}}^2}{L^2} \frac{1}{G} , \tag{21.7}$$

where and D_{int} represent the external and internal MT's diameter. From the plot of $1/E_{\text{bending}}$ vs. the $\left(D_{\text{ext}}^2 + D_{\text{int}}^2\right)/L^2$ the shear modulus can be calculated from the slope of the fit, and the inverse Young's modulus will be equal to the intercept on the y-axis. In this way the shear modulus of $G = 1.4 \pm 0.3\,\text{GPa}$ and a lower limit of $E = 150\,\text{MPa}$ were simultaneously obtained from a measurement on an individual microtubule.

This anisotropy comes from the fact that microtubules are built of monomers that are strongly bound in the longitudinal direction, along single protofilaments. The link between neighboring protofilaments is much weaker. Microtubules, therefore, have to be considered as anisotropic beams, having an E_{bending} that depends on the scale on which they are deformed [21.41]. This is in all respects analogous to the situation in SWNT ropes that are built of stiff individual SWNTs, held together in bundles by a weak van der Waals interaction. This conclusion may explain the large discrepancy in the value of Young's moduli reported in the literature over the past ten years using inadequate modeling.

As in the case of carbon nanotubes, measuring the mechanical properties of microtubules can provide valuable insight into their structure and provide deeper understanding about the functioning of these remarkable structures.

21.3 Scanning Nanoindentation: An Application to Bone Tissue

In the following section we discuss nanoindentation as a tool to determine nanomechanical properties. This method was developed in the early 1980s evolving from traditional Vicker hardness testing devices. The latter is based on the concept that a pyramidal tip is loaded into a material applying a known force. After the test, the size of the remaining imprint is measured under an optical microscope. The ratio of the employed force and the imprint area after load removal was defined as hardness that represents a mean pressure the material can resist. Unfortunately this mechanical parameter is a complex combination of elastic and postyield properties and can't be easily explained on the level of continuum mechanics. This point raised important concerns for determining elastic constants such as the Young modulus from an indentation test. Further improvements on the transducer sensitivity were necessary to provide continuous acquisition of the employed load and the resulting indentation depth. Nanoindentation represents the state of the art of this development allowing mechanical tests on the nanometer scale.

21.3.1 Scanning Nanoindentation

Based on this continuous force–displacement data, an elastic modulus of volumes in the submicron regime can be quantified. To investigate features down to the micrometer regime, classical nanoindentation tools are combined with an optical microscope for positioning the indenter tip on the region of interest. But to defeat the limits of optical resolution, indentation and scanning probe microscopy were combined using the same tip to allow nanoscale control of the indenting tip position [21.47]. This instrument allows for scanning the material topography in an AFM mode and performing nanoindentation tests employing the same tip. The mechanical tests are restricted to the scanned area ($100\,\mu\text{m} \times 100\,\mu\text{m}$ maximum) where the indenter can be positioned with a precision of better than 100 nm. The surface roughness can be measured, which is helpful for choosing the area to be indented. Furthermore the available in situ scan of the indented region can provide information about the piling-up or sink-in behavior of the material. *Kulkarni* and *Bhushan* [21.48,49] introduced this device and demonstrated that measurements on aluminum and silicon were similar to results of non-scanning indentation systems.

21.3.2 Application of Scanning Nanoindentation

The development of the scanning nanoindentation (SN) technique has led to a variety of studies, primarily characterizing thin layers. Applications range from the mechanical characterization of corrosion-free film apposition on single-crystalline iron [21.50] to indentation and microscratch tests on Fe-N/Ti-N multilayers [21.51]. One author included nanoindentation to discuss two different electrochemical deposition techniques of thin Ni-P layers on pure Ni [21.52]. *Rar* et al. [21.53] reported studies on the growth of thin gold layer on native oxides of silicium while other investigations focussed on wear-resistant TiB$_2$(N) coatings [21.54].

Studies of heterogeneous materials clearly demonstrate the advantage of the available surface scanning. *Malkow* and *Bull* [21.55] investigated the elastic/plastic behaviour of carbon-nitride films deposited on silicon. Therefore they determined the load-on and load-off hardness, the latter being accessible by scanning the remaining indent impression. *Shima* et al. [21.56] studied silicon oxynitride films on pure silicon and demonstrated hardness as a function of the employed deposition temperature. *Göken* et al. [21.57] used the high positioning precision to characterize individual lamellae of a TiAl alloy that consists of a two-phase structure and also to study the mechanical properties of nanometer-size precipitates of nickel-based super-alloys [21.58]. Performing in situ electrochemical treatments of iron single crystals, *Seo* et al. [21.59] used SN to study the variation of the remaining imprint shape with time.

In the field of biomechanics, work was done on bone tissue in wild-type and gene-mutated zebrafish. The characterization of the residual indentations in AFM mode supported the statement that gene mutation can change bone brittleness [21.60]. Other investigations focussed on the demineralising effects of soft drinks on tooth enamel by studying changes of elastic properties and surface topography [21.61]. *Habelitz* et al. [21.62] and *Marshall* et al. [21.63] characterized the junction between human tooth enamel and the mechanically different dentin.

Hengsberger et al. [21.64] took advantage of the nanometer positioning capability of the SN to investigate the elastic and plastic properties of individual human bone lamellae. Related work is presented in greater detail below to demonstrate the use and benefits of the SN technique at this example.

21.3.3 Example: Study of Mechanical Properties of Bone Lamellae Using SN



Fig. 21.13 Hierarchy of the human femoral neck (from left to the right) the far left figure shows a cut through a frontal plane of the femoral neck. The outer shell is constituted of compact bone while the inside is made of the spongier trabecular bone. The left pair of images shows the trabecular structure (*top*) and a transverse cut of the compact shell that shows vascular canals (*bottom*).
The right pair of images shows packets of trabecular bone lamellae (*top*) and a single osteon (*bottom*), a vascular canal surrounded by concentric lamellae. Packets of trabecular bone lamellae and osteons represent a structural unit (BSU). Note the alternation of bright (*thick*) and dark (*thin*) lamellae.
The figure far right shows three bone lamellae, structures that are similar for trabecular and compact bone. The bone matrix within the lamellae are mainly constituted of collagen fibers and hydroxyapatite crystals

Before we discuss nanomechanical properties of bone lamellae, it is useful to know the structure on the macroscopic level. Figure 21.13 presents the hierarchy of human bone tissue at the example of the femoral neck. The outer shell is constituted of cortical bone while the porous trabecular bone structure gives inner support. On the next lower level, both bone types show structural units (BSU, after [21.65]) constituted of some tens of lamellae. For compact bone the lamellae have a concentric organization while for trabecular bone these lamellae are parallel. The nomenclature "BSU" was motivated by its underlying cellular process. The formation of such an individual structural unit occurs within a single cellular process. The optical contrast shows two alternating types of lamellae, thin lamellae that appear dark, and thick lamellae that appear bright. These bone lamellae show widths ranging from 1 to 3 μm for thin and 2 to 4 μm for thick lamellae [21.64]. On the next lower level the bone matrix is constituted of a complex collagen and mineral structure. It is still not entirely understood what type of variations in the collagen/mineral meshwork are responsible for the lamellar structure.

The mechanical properties on these different levels of bone hierarchy are increasingly well understood. But, little is known about how the macroscopic mechanical properties of the whole bone relate to its nanomechanical properties. The possibility that factors such as fracture risk might be better understood with an analysis of small bone volumes motivates the application of nanoindentation in this field.

A set of nanoindentation studies is available (mainly employing the device combined with an optical microscope) that presents the intrinsic mechanical properties of bone tissue. Among recent work, differences were reported between donors, anatomical sites, BSU, and thin and thick lamellae [21.64, 66–69]. Due to technical constraints of this sensitive nanomechanical device, the majority of these studies present dehydrated or dried tissue properties measured at ambient temperature [21.70–73]. But, removal of the water content may lead to anisotropic shrinking of the matrix that creates microcracks and alters the mechanical properties of the bone constituents. For an accurate characterization of the in vivo properties, the nanomechanical tests should therefore be done under physiological conditions.

There have been a few attempts to characterize the in vivo bone properties [21.66, 68, 74]. This was achieved by studying fresh bone samples that are kept moist with a thin layer of liquid (less than a hundred microns) on the surface or with subsurface water irrigation. But, local evaporation of the thin liquid layer may have led to indents on areas that were partially dried during the test. One possible solution to such local drying might be to conduct measurements in which the indentation tip and tissue sample are both fully immersed in a liquid cell and simultaneously heated to body temperature.

Practical limitations on temperature stability and inaccuracy in contact force detection due to liquid on the surface make such measurements extraordinarily difficult, however. For statistically powerful studies it seems unavoidable to dry the samples.

The objective of this study was to use SN to determine the effect of drying on the stiffness of single bone lamellae. The goal was to determine a conversion factor that allows dry tissue properties to be recalculated into their in vivo properties.

For this purpose, we measured the identical set of lamellae selected from human trabecular and compact bone at first under physiological and then under dry conditions.

Experimental Setup and Technical Features:

Figure 21.14 demonstrates an optical picture and a sketch of the combined AFM and nanoindenter device (Hysitron Inc. Minneapolis, MN). The transducer consists of a three-plate capacitor on whose central plate a Berkovich (three-sided pyramid) diamond tip is mounted. The transducer provides a contact force feedback between the tip and the sample surface. The sample is mounted on a piezoelectric scanner that allows moving in the x, y and z-directions. During x, y-surface scanning, the piezoelectric scanner keeps this feedback signal constant by correcting the z-height. The movement of the piezoelectric scanner, therefore, describes the negative surface of constant contact force, commonly called an AFM-scan. For the liquid cell tests, the sample was glued in a plexiglass cup for the addition of a several millimeter high liquid layer. A commercially available liquid cell tip (Hysitron Inc. Minneapolis, MN) was used, which contains an additional shaft of approximately 300 μm diameter and 5 mm length to protect the transducer from the fluid. A small layer of latex was placed between the sample holder and the magnetic stick of the piezoelectric scanner to protect the latter from liquid. The additional shaft of the indenter tip and the latex layer



Fig. 21.14 Optical picture (*top*) and sketch (*bottom*) of the scanning nanoindentation device for measurements under physiological conditions. For this purpose the sample was installed in a plexiglass cup for addition of liquid. The entire instrument was heated in a custom-made thermal chamber

represent elastic components that increased the machine compliance ($C_m = 7\,\text{nm/mN}$ instead of $3\,\text{nm/mN}$). This variable corrects the deformation of all the machine components while indentation data are recorded and can be determined from the tip shape calibration curve (Hysitron, Minneapolis). The nanoindentation device was installed in a custom-made thermal chamber to allow sample heating to 37 °C. Note that the increased temperature and humidity also changed the value of the electrostatic force constant (EFC). The latter corrects the force due to the springs that support the central plate on which the indenter tip is mounted. The EFC can be calibrated doing out-of-contact indents and varying this value until a zero-line in the force–displacement curve is measured.

Based on an image acquired in AFM mode, the indentation area can be selected with a high spatial resolution ($< 0.1\,\mu\text{m}$). Figure 21.15 shows the force–displacement data of a typical nanoindentation curve. In the first step, the tip is pressed into the material, resulting in indistinguishable elastic and plastic deformation. Then the tip is held at maximum force resulting in creep of the material under the tip. In a third step, unloading is done that leads to elastic recovery of the material. Typically each indent requires between 15 seconds to several minutes, representing a compromise between a desired quasistatic strain rate and the thermal drift of the instrument (possibly below 0.1 nm/second). This device is load-controlled, and linearly increasing and decreasing loading protocols were therefore applied. The loading rate corresponds to



Fig. 21.15 Force–displacement curve obtained during a nanoindentation test that consists of three parts (see text). Hardness is determined at maximum load. The elastic indentation modulus is calculated with the slope at the point of initial unloading $S(h_{\max})$

$$\frac{\mathrm{d}P}{\mathrm{d}t} = \frac{P_{\max}}{T} \tag{21.8}$$

with $P_{\max}$ as the maximum load and T as the (un)loading time.

The elastic constants of the sample were determined using the unloading part (step 3) of the nanoindentation curve. Based on the analytical work by *Sneddon* [21.75], *Oliver* and *Pharr* [21.76] derived the following equation for an indenter of revolution pressed into an isotropic elastic material:

$$S(h_{\max}) = \frac{\mathrm{d}P}{\mathrm{d}h}(h_{\max}) = \frac{2}{\sqrt{\pi}} E_r \sqrt{A_c(h_{\max})}\,. \tag{21.9}$$

Pharr et al. [21.77] showed that this equation is a good approximation for a Berkovich indenter tip. P represents the applied load, $S(h_{\max})$ is the derivative of the unloading curve at the point of initial unloading $h_{\max}$. This variable is determined by fitting typically 40% to 95% of the unloading curve to avoid the influence of viscoelastic effects at initial unloading when a singularity in the strain rate occurs. $A_c(h)$ is the contact area over which the material and the indenter are in instantaneous contact. The latter function has to be calibrated by performing indents with increasing depth in a standard material, typically fused silica. The latter has a known reduced modulus of $E_r = 69.9\,\text{GPa}$ that allows calibration of the contact area $A_c(h)$ using the measured contact stiffness $S(h)$ and (21.9). The reduced modulus E_r combines the deformation of the material and the diamond tip as follows [21.78]:

$$\frac{1}{E_r} = \frac{1-\nu_{\text{specimen}}^2}{E_{\text{specimen}}} + \frac{1-\nu_{\text{tip}}^2}{E_{\text{tip}}}\,. \tag{21.10}$$

We use the indentation modulus

$$E_{\text{ind}} = \left(\frac{1}{E_r} - \frac{1-\nu_{\text{tip}}^2}{E_{\text{tip}}}\right)^{-1} \tag{21.11}$$

that can be calculated with the reduced modulus and the elastic properties of the diamond indenter tip $\nu_{\text{tip}} = 0.07$ and $E_{\text{tip}} = 1{,}140\,\text{GPa}$. This variable combines with

$$E_{\text{ind}} = \frac{E_{\text{specimen}}}{1-\nu_{\text{specimen}}^2} \tag{21.12}$$

the local Young's modulus E_{specimen} and Poisson ratio ν_{specimen} of the specimen.

It is important to note that this theory assumes an isotropic material. For an anisotropic material the indentation modulus represents some average of the elastic properties in all directions. The latter strongly depends on the geometry of the indenter. For indents with a blunt indenter (such as Berkovich with an opening angle of 143°) nonnegligible deformations will occur in the plane perpendicular to the loading direction. In this context it is useful to present an approximation of the volume ganged by the indentation test.

The stress field generated by the indentation process is heterogeneous and leads to plastic deformation and damage in the vicinity of the tip. Using Hertz's theory [21.78], the spatial dependence of the stress components during indentation can be estimated by considering the elastic contact of a spherical indenter with a semi-infinite half space. In the direction of loading (z-axis), the stress component below the indenter decreases according to

$$\frac{\sigma_{zz}}{p_0} = -\left(1 + \frac{z^2}{a^2}\right) , \tag{21.13}$$

where p_0 indicates the maximum pressure below the indenter and a the contact radius.

In a horizontal plane at the surface ($z = 0$), the radial and circumferential components of the stress field next to the contact area obey

$$\frac{\sigma_{rr}}{p_0} = -\frac{\sigma_{\theta\theta}}{p_0} = \frac{(1-2\nu)\,a^2}{3r^2} , \tag{21.14}$$

where θ and r are the cylindrical coordinates of the periphery of the indenter and ν is the Poisson ratio. For $\nu = 0.3$ the stress field components reach their 10%-boundary defined by $\sigma_{zz} = -0.1p_0$ and $\sigma_{rr} = -\sigma_{\theta\theta} = 0.1p_0$ at a depth of $z \cong 3a$ or in lateral direction at $r \cong 2/\sqrt{3}a$. For a Berkovich tip, the ratio between maximum indentation depth and contact radius is approximately $a \cong 3h_{\max}$. The mechanical properties measured by nanoindentation, therefore, correspond to a semi-ellipsoidal volume extending to about nine times the employed indentation depth ($z \cong 3a \cong 9h_{\max}$) in the vertical direction (z) and about seven times this same depth ($2r \cong 4/\sqrt{3}a \cong 7h_{\max}$) in the radial direction (r).

The load-on hardness is determined with

$$H = \frac{P\,(h_{\max})}{A_{\mathrm{c}}\,(h_{\max})} \tag{21.15}$$

as the ratio of the maximum load and the ("on load") contact area at maximum load. This is different from Vicker hardness in which the contact area is characterized by the remaining imprint after load removal. Differences between nanoindentation and Vicker, therefore, occur for materials with nonnegligible elastic recovery. After unloading, such materials may expose an imprint smaller than the area of contact at maximum load. Since the SN tool can be used to image the remaining imprint after unloading, hardness values using both definitions may thus be compared.

For fused silica the literature provides a hardness range between 8.3 to 9.5 GPa while an intercomparison of SN-users showed an average of 8.96 GPa (Surface, Hückelhoven). Conveniently, the hardness value also represents a possibility to check the area function of the tip based on the reduced modulus of the calibration material.

Tests of Bone Tissue Under Pseudo-physiological Conditions

Samples containing trabecular and compact bone lamellae were dissected from the medial part of the femoral neck of an 86-year-old female. After embedding in PMMA, the samples were polished with successive grades of carbide paper and finished with 0.05 µm alumina solution. Polishing represents an important preparation step since the here-employed theory assumes an infinitely flat surface. The mean surface roughness of the indented area should, therefore, be far below the employed indentation depth. Unfortunately no objective criteria that determines the maximum allowable surface roughness as a function of the indentation depth has been formulated so far.

Thin and thick lamellae of trabecular and compact bone were first characterized under physiological conditions, i. e. fully wet and at 37 °C. Then the specimens were dried for 24 h at 50 °C and identical tests were carried out again but under dry conditions.

In both cases 16 indentation tests were performed to maximum depths of 100 nm and 500 nm. Each test consisted of 10 s loading, 10 s holding, and 10 s unloading. The maximum allowable thermal drift was set 0.1 nm/s. To avoid proximity effects of neighbouring indents, an adjacent testing area in the identical lamellae was chosen after changing the testing conditions.

The tests under fully wet conditions at body temperature were found to be very sensitive with respect to thermal stability. The nanoindentation device was heated for several days to reach stable thermal conditions of the instrument components before the sample could be installed. The electrostatic force constant (EFC) was checked daily before beginning data acquisition. The approach of the indenter tip in the liquid environment was performed employing a contact force of 7 µN. This



Fig. 21.16 Surface topography of a trabecular bone structural unit that shows the lamellar structure. Thick (*bright*) lamellae correspond to the tops in the topography. Note, the two holes are not remaining indents but are ellipsoidal lacunae that embed bone cells

value is offset by approximately 1 µN per mm of water penetration, however, due to Archimedes force acting on the fluid cell tip. Such additional effects as water surface tension may also have a repulsive force on the tip.

AFM-scans as in Fig. 21.16, which shows the topography of trabecular bone lamellae under dry conditions, allowed the two lamella types to be identified. Thick lamellae correspond to the tops (bright contrast) and thin lamellae to the valleys (dark contrast) where the surface relief results from preferential polishing.

Indentation Modulus

Trabecular bone showed under wet conditions a mean indentation modulus of 12.5 ± 4.0 GPa when the data of both lamella types and indentation depths were combined. Under dry conditions the results showed a mean of 19.6 ± 2.6 GPa, an increase of 57%. Lamellae of compact bone increased their mean stiffness by 76.5% from 14.9 ± 4.5 GPa to 26.4 ± 3.8 GPa.

These determined conversion factors between dried and fully wet tissue properties should be compared with other studies. *Rho* [21.74] has reported an increase of indentation modulus of bovine compact bone by 15.8%. Our study demonstrates a change of +76.5% for human compact bone. This high discrepancy may be attributed to different preparation and testing protocols. Rho tested the bone samples at ambient temperature while kept moist by a thin film of deionized water. In our study the tissue properties were determined under fully wet conditions and at body temperature. Furthermore, Rho dried for 14 days at ambient temperature while in our study the drying process occurred during 24 h at 50 °C. These points may explain the different relative change of mechanical properties we detected.

Figure 21.17 presents the indentation moduli (combining both depths) normalized with respect to their initial wet values under physiological conditions. It is interesting that the increase of this elastic parameter after drying was significantly ($p < 0.00001$) higher for thin than for thick lamellae. The relative change of stiffness due to drying was +44% for thick lamellae and +109% for thin lamellae of compact bone. For trabecular bone the corresponding values were +37% and +78% for thick and thin lamellae, respectively.

Table 21.2 shows the results for both indentation depths. The differences are likely related to the volume sampled during the indentation, a semi-ellipsoid following the approximations of (21.13) and (21.14) with 0.7 µm diameter and 0.9 µm height for 100 nm indents (and 3.5 µm × 4.5 µm for 500 nm indents). Given the typical lamellae dimensions of 1–4 µm, the shallow indentation measurements, therefore, represent properties of single lamellae whereas the deeper indents include neighboring lamellae. It is also worth noting that thin lamellae showed a greater effect of drying when only the shallow indents were considered.

This important result should be discussed in the frame of published models that address the phenomenon of bone lamellation. *Marotti* [21.79] proposed that bone lamellae are the result of alternating changes of the collagen fiber density. According to his SEM-results the density of collagen is higher in thin lamellae than in thick lamellae. Collagen fibers are long chains of proteins and contain adsorption sites for polar water



Fig. 21.17 Relative increase of indentation modulus for compact and trabecular bone lamellae after drying. The results are normalized with respect to their initial value under wet conditions. Note that thin lamellae are more affected by drying for both types of bone

Table 21.2 Absolute and relative changes of the indentation modulus with respect to the initial values under wet conditions. Note the greater increase for the thin lamellae after drying. Indents to 100 nm depth represent properties of single lamellae while 500 nm indents are also influenced by neighboring lamellae

Indentation modulus	Lamella	Ind. depth (nm)	Wet (GPa)	Dry (GPa)	Rel. change (%)
Trabecular bone	Thin	100	11.6 ± 4.1	20.5 ± 4.3	+76
		500	9.8 ± 1.9	18.1 ± 3.2	+84
	Thick	100	12.4±5	19.1 ± 1.11	+54
		500	15.6 ± 1.3	19.0 ± 1.1	+22
Compact bone	Thin	100	10.4 ± 0.2	23.4 ± 3.6	+124
		500	13.9 ± 2.0	27.1 ± 3.1	+95
	Thick	100	19.9 ± 4.8	27.9 ± 4.6	+40
		500	15.5 ± 2.6	23.0 ± 0.8	+49

molecules. A higher density of the collagen fibers in the thinner lamellae results in a higher water binding capacity that may explain the higher relative influence of drying.

Giraud-Guille [21.80], on the other hand, proposed a nested-arc structure for bone lamellae with smooth orientation changes between adjacent collagen fibers. According to this model indents on thick lamellae load into the longitudinal direction of the fibers, whereas the load is perpendicular to the long axis for thin lamellae. Removal of the liquid phase leads to packaging of the collagen fibers, an effect that is intuitively anisotropic and that may explain why the effect of drying was different for both lamella types. In addition, drying leads to microfracture initiation within thick lamellae [21.64], possibly explaining the diminished effect of drying on these structure.



Fig. 21.18 SEM-scan of bone lamellae adjacent to the spot characterized by nanoindentation. This SEM-scan gives support for the bone lamellation model that is based on a smooth orientation change of collagen fibers [21.80]



Fig. 21.19 Bone lamellation model proposed by this study. This model represents a combination of a smooth orientation change and density variations of the collagen fibers. Note also the spots where the indentations were done. For thin lamellae a greater change of mechanical properties was detected after drying

Figure 21.18 presents a SEM-image from a bone sample used in this study. This scan confirms the nested-arc structure Giraud-Guille observed with TEM.

Our results are, therefore, in agreement with both the Marotti and the Giraud-Guille models. This implies a model that combines smooth orientation changes of the collagen fibers with density changes. Such an architecture is sketched in Fig. 21.19. Note also the spots where the indentations were done.

Hardness

Compact bone revealed a mean hardness of 0.46 GPa under wet conditions that increased by 74% to 0.80 GPa after drying. Due to drying trabecular bone lamellae showed a mean hardness change of 76% from 0.41 up to 0.72 GPa.



Fig. 21.20 Indentation modulus and hardness under dry and wet conditions using raw data from *Hengsberger* et al. [21.64]. Drying does not change the correlation coefficient and changes slightly but significantly the slope of the regression curve

For compact bone the effect of drying was again significantly ($p = 0.0006$) greater for thin lamellae (+108%) than for thick lamellae (+44%). Similar results were found for trabecular bone lamellae with a +99% increase for thin and a +56% increase for thick lamellae.

The results for hardness, therefore, appear to similar trends as the indentation modulus. This motivates us to discuss a further point, the correlation between indentation modulus and hardness. These mechanical parameters show an empirically proven relationship [21.81] that may change as a result of drying. For this purpose we related the data of the indentation modulus of Hengsberger et al. [21.64] with the corresponding unpublished hardness results. The correlation between hardness and indentation modulus is similar under wet ($R^2 = 0.61$) and under dry ($R^2 = 0.67$) conditions (Fig. 21.20). The slopes of the linear regression, however, show close but significantly different values ($p < 0.0001$) for the wet and dry samples. Hardness and indentation modulus show a similar but significantly different relative shift as a result of drying.

21.3.4 Conclusion

Modern scanning nanoindentation has clearly solved two problems: indentations in the nanometer scale can be performed with high force and displacement resolution, and nanometer lateral control of the indentation position allows the characterization of small structures of heterogeneous materials. Interfaces in composites, local density or composition variations of chemical products, or biological structures can then be investigated using the SN tool.

Based on recent theoretical progress [21.82], the nanoindentation technique can also be used to characterize anisotropic materials by indenting in different directions. Other parameters can also be determined. For instance, creep behavior is accessible when the indentation load is held constant at a maximum load. Hysteresis of the force–displacement curve represents the energy dissipated during an indentation providing information about post-elastic behavior of a sample. Such dynamical variables as viscoelastic properties are also accessible by including sinusoidal oscillations of different frequencies to the loading history.

Future interests of the nanotechnology community may direct the work towards tests on lower levels of structural organization like the molecular or atomic level. This would require strong improvements of the transducer sensitivity and of the indenter tip machining. New concepts to reduce the thermal drifting properties would also be necessary for the next generation of this device.

21.4 Conclusions and Perspectives

We have demonstrated that AFM is an ideal tool for investigating variations in local properties of bulk materials, like bone, and also for performing physical measurements on individual nanometer scale objects such as, for example, carbon nanotubes and protein polymers. In the latter case, the technique provides previously inaccessible quantities in living matter such as, for instance, the shear modulus. It should be emphasized that shear is omnipresent since biostructures are "composite" materials, with strong anisotropic interactions between their constituents. In the case of proteins, we have explored the mechanical properties as a function of temperature, as well. Interactions can vary remarkably even over a range of a few tens of degrees, providing deeper insight in the functioning of these structures. One task, which seems very difficult for the time being, is the frequency dependent response of nano and biostructures. In the latter case it is limited to a few kilohertz, mainly because of the surrounding liquid, but for a meaningful analysis one requires several decades in frequency.

Regarding the scanning probe tips themselves, improvements are necessary to provide better resolution, longer lifetimes, and easy functionalization for sensing different chemical environments. This might be achieved by carbon nanotube tips (Fig. 21.21), which have a Young's modulus of 1 TPa, a very well-defined and sharp tip structure, and pentagon "defects" at the apex providing a site for functionalization. It is generally agreed upon by the scanning probe community that carbon nanotubes will open new avenues for the study of living matter.



Fig. 21.21 SEM picture of an AFM tip with attached multiwall Carbon nanotube

Finally the development of the photonic force microscope in Heidelberg has allowed imaging of bio-structures with unprecedented three-dimensional resolution, even including features that are otherwise inaccessible to AFM tips. In the future, this instrument will certainly provide radical new insight in biological functioning.

References

21.1 M. Radmacher: Measuring the elastic properties of biological samples with the AFM, IEEE Eng. Med. Biol. Mag. **16**(2) (1997) 47–57

21.2 G. Binnig, C. F. Quate, C. Gerber: Atomic force microscope, Phys. Rev. Lett. **56** (1986) 930–933

21.3 P. Maivald, H. J. Butt, S. A. C. Gould, C. B. Prater, B. Drake, J. A. Gurley, V. B. Elings, P. K. Hansma: Using force modulation to image surface elasticities with the atomic force microscope, Nanotechnology **2** (1991) 103–106

21.4 T. Kajiyama, K. Takata, I. Ohki, S.-R. Ge, J.-S. Yoon, A. Takahara: Imaging of dynamic viscoelstic properties of a phase-separated polymer by forced oscillation atomic force microscopy, Macromolecules **27** (1994) 7932–7934

21.5 B. Nysten, R. Legras, J.-L. Costa: Atomic force microscopy imaging of viscoelastic properties in toughened polypropylene resins, J. Appl. Phys. **78** (1995) 5953–5958

21.6 P.-E. Mazeran, J.-L. Loubet: Normal and lateral modulation with a scanning force microscope, an analysis: Implication in quantitative elastic and friction imaging, Tribol. Lett. **3** (1997) 125–129

21.7 B. Cretin, F. Sthal: Scanning microdeformation microscopy, Appl. Phys. Lett. **62** (1993) 829–831

21.8 N. A. Burnham, A. J. Kulik, G. Gremaud, P.-J. Gallo, F. Oulevey: Scanning local-acceleration microscopy, J. Vac. Sci. Technol. B **14** (1996) 794–799

21.9 F. Oulevey, N. A. Burnham, A. J. Kulik, G. Gremaud, W. Benoit: Mechanical properties studied at the nanoscale using scanning local-acceleration microscopy (SLAM), J. Phys. **IV** (1996) C8-731–734

21.10 U. Rabe, W. Arnold: Acoustic microscopy by atomic force microscopy, Appl.Phys. Lett **64** (1994) 1493–1495

21.11 O. Kolosov, K. Yamanaka: Nonlinear detection of ultrasonic vibrations in an atomic force microscope, Jpn. J. Appl. Phys. **32** (1993) 22–25

21.12 F. Oulevey: Cartographie et spectrométrie des propriétés mécaniques à l'échelle nanométrique par microscopie acoustique en champ proche. Ph.D. Thesis (EPFL, Lausanne 1999)

21.13 F. Oulevey, G. Gremaud, A. Semoroz, A.J. Kulik, N.A. Burnham, E. Dupas, D. Gourdon: Local mechanical spectroscopy with nanometer-scale lateral resolution, Rev. Sci. Instrum. **69** (1998) 2085–2094

21.14 N. A. Burnham, G. Gremaud, A. J. Kulik, P.-J. Gallo, F. Oulevey: Materials' properties measurements: Choosing the optimal scanning probe microscope configuration, J. Vac. Sci. Technol. B **14** (1996) 1308–1312

21.15 F. Oulevey, G. Gremaud, A.J. Kulik, B. Guisolan: Simple low-drift heating stage for scanning probe microscopes, Rev. Sci. Instrum. **70** (1999) 1889–1890

21.16 H. M. Pollock: Nanoindentation. In: *Friction lubrication and wear technology*, AMS Handbook, Vol. 18 (AMS, Ohio 1992) p. 419

21.17 E. Dupas, G. Gremaud, A. Kulik, J.-L. Loubet: High-frequency mechanical spectroscopy with an atomic force microscope, Rev. Sci. Instrum. **72**(10) (2001) 3891–3897

21.18 F. Oulevey, N. A. Burnham, G. Gremaud, A. J. Kulik, H. M. Pollock, A. Hammiche, M. Reading, M. Song, D. J. Hourston: Dynamic mechanical analysis at the submicron scale, Polymer **41** (2000) 3087–3092

21.19 W. Wm. Wendlandt: *Thermal Analysis in Chemical Analysis*, Vol. 19, 3rd edn. (Wiley, New York 1996) p. 360

21.20 D. Mari, D. C. Dunand: NiTi and NiTi-TiC composites: Part I. Transformation and thermal cycling behavior, Metall. Mater. Trans. A **26A** (1995) 2833–2847

21.21 L. Bataillard: Transformation martensitique multiple dans un alliage à mémoire de forme Ni-Ti. Ph.D. Thesis (EPF, Lausanne 1996)

21.22 F. Oulevey, G. Gremaud, D. Mari, A.J. Kulik, N. A. Burnham, W. Benoit: Martensitic transformation of NiTi studied at the nanometer scale by local mechanical spectroscopy, Scripta Mater. **42** (2000) 31–36

21.23 D. Mari, L. Bataillard, D. C. Dunand, R. Gotthardt: Martensitic transformation of NiTi and NiTi-TiC composites, J. Phys. (France) **IV** (1995) C8–659–664

21.24 S. Iijima: Helical microtubules of graphitic carbon, Nature **354** (1991) 56–58

21.25 C.-H. Kiang, M. Endo, P. M. Ajayan, G. Dresselhaus, M. S. Dresselhaus: Size effects in carbon nanotubes, Phys. Rev. Lett. **81** (1998) 1869–1872

21.26 A. Thess, R. Lee, P. Nikolaev, H. Dai, P. Petit, J. Robert, C. Xu, Y. H. Lee, S. G. Kim, A. G. Rinzler, Daniel T. Colbert, G. U. Scuseria, D. Tománek, J. E. Fischer, R. E. Smalley: Crystalline ropes of metallic carbon nanotubes, Science **273** (1996) 483–487

21.27 W. Z. Li, S. S. Xie, L. X. Qian, B. H. Chang, B. S. Zou, W. Y. Zhou, R. A. Zhao, G. Wang: Large-scale synthesis of aligned carbon nanotubes, Science **274** (1996) 1701–1703

21.28 J. Kong, H. T. Soh, A. M. Cassell, C. F. Quate, H. J. Dai: Synthesis of individual single-walled carbon nanotubes on patterned silicon wafers, Nature **395** (1998) 878–881

21.29 J. P. Lu: Elastic properties of carbon nanotubes and nanoropes, Phys. Rev. Lett. **79** (1997) 1297–1300

21.30 E. W. Wong, P. E. Sheehan, C. M. Lieber: Nanobeam mechanics: Elasticity, strength and toughness of nanorods and nanotubes, Science **277** (1997) 1971–1975

21.31 J.-P. Salvetat, J. M. Bonard, N. H. Thomson, A. J. Kulik, L. Forró, W. Benoit, L. Zuppiroli: Mechanical properties of carbon nanotubes, Appl. Phys. A **69** (1999) 255–260

21.32 M.-F. Yu, B. S. Files, S. Arepalli, R. S. Ruoff: Tensile loading of ropes of single wall carbon nanotubes and their mechanical properties, Phys. Rev. Lett. **84** (2000) 5552–5555

21.33 S. Iijima, C. Brabec, A. Maiti, J. Bernholc: Structural flexibility of carbon nanotubes, J. Chem. Phys. **104** (1996) 2089–2092

21.34 J.-P. Salvetat, A. J. Kulik, J.-M. Bonard, G. A. D. Briggs, T. Stöckli, K. Méténier, S. Bonnamy, F. Béguin, N. A. Burnham, L. Forró: Elastic modulus of ordered and disordered multiwalled carbon nanotubes, Adv. Mater. **11** (1999) 161–165

21.35 J.-P. Salvetat, G. A. D. Briggs, J.-M. Bonard, R. R. Bacsa, A. J. Kulik, T. Stöckli, N. Burnham, L. Forró: Elastic and shear moduli of single-walled carbon nanotube ropes, Phys. Rev. Lett. **82** (1999) 944–947

21.36 J. M. Gere, S. P. Timoshenko: *Mechanics of Materials* (PWS-Kent, Boston 1990)

21.37 D. A. Walters, L. M. Ericson, M. J. Casavant, J. Liu, D. T. Colbert, K. A. Smith, R. E. Smalley: Elastic strain of freely suspended single-wall carbon nanotube ropes, Appl. Phys. Lett. **74** (1999) 3803–3805

21.38 M.-F. Yu, O. Lourie, M. J. Dyer, K. Moloni, T. F. Kelly, R. S. Ruoff: Strength and breaking mechanism of multiwalled carbon nanotubes under tensile load, Science **287** (2000) 637–640

21.39 G.-T. Kim, G. Gu, U. Waizmann, S. Roth: Simple method to prepare individual suspended nanofibers, Appl. Phys. Lett. **80** (2002) 1815–1817

21.40 T. Fujii, M. Suzuki, M. Miyashita, M. Yamaguchi, T. Onuki, H. Nakamura, T. Matsubara, H. Yamada, K. Nakayama: Micropattern measurement with an atomic force microscope, J. Vac. Sci. Technol. B **9** (1991) 666–669

21.41 A. S. K. Kis, B. Babic, A. J. Kulik, W. Benoît, G. A. D. Briggs, C. Schönenberger, S. Catsicas, L. Forró: Nanomechanics of microtubules, Phys. Rev. Lett. **89** (2002) 248101

21.42 M. Kurachi, M. Hoshi, H. Tashiro: Buckling of a single microtubule by optical trapping forces: Direct measurement of microtubule rigidity, Cell. Motil. Cyt. **30** (1995) 221–228

21.43 R. B. Dye, S. P. Fink, R. C. Williams: Taxol-induced flexibillity of microtubules and its reversal by Map-2 and Tau, J. Biol. Chem. **268** (1993) 6847–6850

21.44 F. Gittes, B. Mickey, J. Nettleton, J. Howard: Flexual rigidity of microtubules and actin filaments measured from thermal fluctuations in shape, J. Cell Biol. **120** (1993) 923–934

21.45 M. Elbaum, D. K. Fygenson, A. Libchaber: Buckling microtubules in vesicles, Phys. Rev. Lett. **76** (1996) 4078–4081

21.46 A. Vinckier, C. Dumortier, Y. Engelborghs, L. Hellemans: Dynamical and mechanical study of immobilized microtubules with atomic force microscopy, J. Vac. Sci. Technol. B **14** (1996) 1427–1431

21.47 Hysitron, Incorporated 2010 East Hennepin Avenue Minneapolis, MN 55413,

21.48 A. V. Kulkarni, B. Bhushan: Nanoscale mechanical property measurements using modified atomic force microscopy, Thin Solid Films **290-291** (1996) 206–210

21.49 A. V. Kulkarni, B. Bhushan: Nano/picoindentation measurements on single-crystal aluminum using modified atomic force microscopy, Mater. Lett. **29** (1996) 221–227

21.50 M. Chiba, M. Seo: Effects of dichromate treatment on mechanical properties of passivated single crystal iron (100) and (110) surfaces, Corros. Sci. **44** (2002) 2379–2391

21.51 X. C. Lu, B. Shi, L. K. Y. Li, J. Luo, X. Chang, Z. Tian, J. I. Mou: Nanoindentation and microtribological behavior of Fe-N/Ti-N multilayers with different thickness of Ti-N layers, Wear **251** (2001) 1144–1149

21.52 P. Peeters, Gvd. Horn, T. Daenen, A. Kurowski, G. Staikov: Properties of electroless and electroplated Ni-P and its application in microgalvanics, Electrochim. Acta **47** (2001) 161–169

21.53 A. Rar, J. N. Zhou, W. J. Liu, J. A. Barnard, A. Bennett, S. C. Street: Dendrimer-mediated growth of very flat ultrathin Au films, Appl. Surf. Sci. **175-176** (2001) 134–139

21.54 R. D. Ott, C. Ruby, F. Huang, M. L. Weaver, J. A. Barnard: Nanotribology and surface chemistry of reactively sputtered Ti-B-N hard coatings, Thin Solid Films **377-378** (2000) 602–606

21.55 T. Malkow, S. J. Bull: Hardness measurements on thin IBAD CN_x films – a comparative study, Surf. Coat. Technol. **137** (2001) 197–204

21.56 Y. Shima, H. Hasuyama, T. Kondoh, Y. Imaoka, T. Watari, K. Baba, R. Hatada: Mechanical properties of silicon oxynitride thin films prepared by low energy ion beam assisted deposition, Nucl. Instrum. Methods Phys. Res., Sect. B **148** (1999) 599–603

21.57 M. Göken, M. Kempf, W. D. Nix: Hardness and modulus of the lamellar microstructure in PST-TiAl studied by nanoindentations and AFM, Acta Mater. **49** (2001) 903–911

21.58 M. Göken, M. Kempf: Microstructural properties of superalloys investigated by nanoindentations in an atomic force microscope, Acta Mater. **47** (1999) 1043–1052

21.59 M. Seo, M. Chiba, K. Suzuki: Nano-mechano-electrochemistry of the iron (100) surface in solution, J. Electroanal. Chem. **473** (1999) 49–53

21.60 Y. Zhang, F. Z. Cui, X. M. Wang, Q. L. Feng, X. D. Zhu: Mechanical properties of skeletal bone in gene-mutated *stöpsel*^{dtl28d} and wild-type zebrafish (*Danio rerio*) measured by atomic force microscopy-based nanoindentation, Bone **30** (2002) 541–546

21.61 M. Finke, J. A. Hughes, D. M. Parker, K. D. Jandt: Mechanical properties of in situ demineralised human enamel measured by AFM nanoindentation, Surf. Sci. **491** (2001) 456–467

21.62 S. Habelitz, S. J. Marshall, G. W. Marshall, J. R. Balooch, M. Balooch: The functional width of the dentino-enamel junction determined by AFM-based nanoscratching, J. Struct. Biol. **135** (2001) 294–301

21.63 G. W. Marshall Jr., M. Balooch, R. R. Gallagher, S. A. Gansky, S. J. Marshall: Mechanical properties of the dentinoenamel junction: AFM studies of nanohardness, elastic modulus, and fracture, J. Biomed. Mater. Res. **54** (2001) 87–95

21.64 S. Hengsberger, A. Kulik: Nanoindentation discriminates the elastic properties of individual human bone lamellae under dry and physiological conditions, Bone **30** (2002) 178–184

21.65 E. F. Eriksen, D. W. Axelrod, F. M. Melsen: *Bone Histomorphometry*, 1st edn. (Raven, New York 1994)

21.66 C. E. Hoffler, K. E. Moore, K. Kozloff, P. K. Zysset, M. B. Brown, S. A. Goldstein: Heterogeneity of bone lamellar-level elastic moduli, Bone **26** (2000) 603–609

21.67 C. E. Hoffler, K. E. Moore, K. Kozloff, P. K. Zysset, S. A. Goldstein: Age, gender, and bone lamellae elastic moduli, J. Orth. Res. **18** (2000) 432–437

21.68 P. K. Zysset, X. E. Guo, C. E. Hoffler, K. E. Moore, S. A. Goldstein: Elastic modulus and hardness of cortical and trabecular bone lamellae measured by nanoindentation in the human femur, J. Biomech. **32** (1999) 1005–1012

21.69 J. Y. Rho, P. Zioupos, J. D. Currey, G. M. Pharr: Variations in the individual thick lamellar properties within osteons by nanoindentation, Bone **25** (1999) 295–300

21.70 J. Y. Rho, M. E. Roy, T. Y. Tsui, G. M. Pharr: Elastic properties of microstructural components of human bone tissue as measured by nanoindentation, J. Biomed. Mater. Res. **45** (1999) 48–54

21.71 S. Hengsberger, A. Kulik, P. Zysset: A combined atomic force microscopy and nanoindentation technique to investigate the elastic properties of bone structural units, Europ. Cells Mater. **1** (2001) 12–16

21.72 C.H. Turner, J.Y. Rho, Y. Takano, T.Y. Tsui, G. M. Pharr: The elastic properties of trabecular and cortical bone tissues are similar: Results from two microscopic measurement techniques, J. Biomech. **32** (1999) 437–441

21.73 M.E. Roy, J.Y. Rho, T.Y. Tsui, N.S. Evans, G. M. Pharr: Mechanical and morphological variation of the human lumbar vertebral cortical and trabecular bone, J. Biomed. Mater. Res. **44** (1999) 191–199

21.74 J.Y. Rho, G.M. Pharr: Effects of drying on the mechanical properties of bovine femur measured by nanoindentation, J. Mater. Sci.: Mater. Med. **10** (1999) 485–488

21.75 I. N. Sneddon: The relation between load and penetration in the axisymmetric Boussinesq problem for a punch of arbitrary profile, Int. J. Eng. Sci. **3** (1965) 47–57

21.76 W.C. Oliver, G.M. Pharr: An improved technique for determining hardness and elastic modulus using load and displacement sensing indentation experiments, Mat. Res. Soc. **7/6** (1992) 1564–1583

21.77 G. M. Pharr, W. C. Oliver, F. R. Brotzen: On the generality of the relationship among contact stiffness, contact area, and elastic modulus during indentation, J. Mater. Res. **7/3** (1992) 613–617

21.78 K. L. Johnson: *Contact Mechanics*, 1st edn. (Cambridge Univ. Press, Cambridge 1985) pp. 84–106

21.79 G. Marotti: A new theory of bone lamellation, Calcif Tissue Int. **53** (1993) 47–56

21.80 M. M. Giraud-Guille: Plywood structures in nature, Curr. Op. Solid State Mater. Sci. **3** (1998) 221–227

21.81 G. P. Evans, J. C. Behiri, J. D. Currey, W. Bonfield: Microhardness and Young's modulus in cortical bone exhibiting a wide range of mineral volume fractions, and in a bone analogue, J. Mater. Sci.: Mater. Med. **1** (1990) 38–43

21.82 J. G. Swadener, G. M. Pharr: Indentation of elastically anisotropic half-spaces by cones and parabolae of revolution, Philos. Mag. A **81** (2001) 447–466

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

22. Nanomechanical Properties of Solid Surfaces and Thin Films

Instrumentation for the testing of mechanical properties on the submicron scale has developed enormously in recent years. This has enabled the mechanical behavior of surfaces, thin films, and coatings to be studied with unprecedented accuracy. In this chapter, the various techniques available for studying nanomechanical properties are reviewed with particular emphasis on nanoindentation. The standard methods for analyzing the raw data obtained using these techniques are described, along with the main sources of error. These include residual stresses, environmental effects, elastic anisotropy, and substrate effects. The methods that have been developed for extracting thin-film mechanical properties from the often convoluted mix of film and substrate properties measured by nanoindentation are discussed. Interpreting the data is frequently difficult, as residual stresses can modify the contact geometry and, hence, invalidate the standard analysis routines. Work hardening in the deformed region can also result in variations in mechanical behavior with indentation depth. A further unavoidable complication stems from the ratio of film to substrate mechanical properties and the depth of indentation in comparison to film thickness. Even very shallow indentations may be influenced by substrate properties if the film is hard and very elastic but the substrate is compliant. Under these circumstances nonstandard methods of analysis must be used. For multilayered systems many different mechanisms affect the nanomechanical behavior, including Orowan strengthening, Hall–Petch behavior, image force effects, coherency and thermal stresses, and composition modulation.

The application of nanoindentation to the study of phase transformations in semiconductors, fracture in brittle materials, and mechanical properties in biological materials are described. Recent developments such as the testing of viscoelasticity using nanoindentation methods are likely to be particularly important in future studies of polymers and biological materials. The importance of using a range of complementary methods such as electron microscopy, in situ AFM imaging, acoustic monitoring, and electrical contact measurements is emphasized. These are especially important on the nanoscale because so many different physical and chemical processes can affect the measured mechanical properties.

22.1 **Instrumentation** ... 688
  22.1.1 AFM and Scanning Probe Microscopy ... 688
  22.1.2 Nanoindentation ... 689
  22.1.3 Adaptations of Nanoindentation ... 690
  22.1.4 Complimentary Techniques ... 691
  22.1.5 Bulge Tests ... 691
  22.1.6 Acoustic Methods ... 692
  22.1.7 Imaging Methods ... 693

22.2 **Data Analysis** ... 694
  22.2.1 Elastic Contacts ... 694
  22.2.2 Indentation of Ideal Plastic Materials ... 694
  22.2.3 Adhesive Contacts ... 695
  22.2.4 Indenter Geometry ... 696
  22.2.5 Analyzing Load/Displacement Curves ... 696
  22.2.6 Modifications to the Analysis ... 699
  22.2.7 Alternative Methods of Analysis ... 700
  22.2.8 Measuring Contact Stiffness ... 701
  22.2.9 Measuring Viscoelasticity ... 702

22.3 **Modes of Deformation** ... 702
  22.3.1 Defect Nucleation ... 702
  22.3.2 Variations with Depth ... 704
  22.3.3 Anisotropic Materials ... 704
  22.3.4 Fracture and Delamination ... 704
  22.3.5 Phase Transformations ... 705

22.4 **Thin Films and Multilayers** ... 707
  22.4.1 Thin Films ... 707
  22.4.2 Multilayers ... 709

22.5 **Developing Areas** ... 711

References ... 712

When two bodies come into contact their surfaces experience the first and usually largest mechanical loads. Hence, characterizing and understanding the mechanical properties of surfaces is of paramount importance in a wide range of engineering applications. Obvious examples of where surface mechanical properties are important are in wear-resistant coatings on reciprocating surfaces and hard coatings for machine tool bits. This chapter details the current methods for measuring the mechanical properties of surfaces and highlights some of the key experimental results that have been obtained.

The experimental technique that is highlighted in this chapter is nanoindentation. This is for the simple reason that it is now recognized as the preferred method for testing thin film and surface mechanical properties. Despite this recognition, there are still many pitfalls for the unwary researcher when performing nanoindentation tests. The commercial instruments that are currently available all have attractive, user-friendly software, which makes the performance and analysis of nanoindentation tests easy. Hidden within the software, however, are a myriad of assumptions regarding the tests that are being performed and the material that is being examined. Unless the researcher is aware of these, there is a real danger that the results obtained will say more about the analysis routines than they do about the material being tested.

22.1 Instrumentation

The instruments used to examine nanomechanical properties of surfaces and thin films can be split into those based on point probes and those complimentary methods that can be used separately or in conjunction with point probes. The complimentary methods include a wide variety of techniques ranging from optical tests such as micro-Raman spectroscopy to high-energy diffraction studies using X-rays, neutrons, or electrons to mechanical tests such as bulge or blister testing.

Point-probe methods have developed from two historically different methodologies, namely, scanning probe microscopy [22.1] and microindentation [22.2]. The two converge at a length scale between 10–1,000 nm. Point-probe mechanical tests in this range are often referred to as nanoindentation.

22.1.1 AFM and Scanning Probe Microscopy

Atomic force microscopy (AFM) and other scanning probe microscopies are covered in detail elsewhere in this volume, but it is worth briefly highlighting the main features in order to demonstrate the similarities to nanoindentation. There are now a myriad of different variants on the basic scanning probe microscope. All use piezoelectric stacks to move either a probe tip or the sample with subnanometer precision in the lateral and vertical planes. The probe itself can be as simple as a tungsten wire electrochemically polished to give a single atom at the tip, or as complex as an AFM tip that is bio-active with, for instance, antigens attached. A range of scanning probes have been developed with the intention of measuring specific physical properties such as magnetism and heat capacity.

To measure mechanical properties with an AFM, the standard configuration is a hard probe tip (such as silicon nitride or diamond) mounted on a cantilever (see Fig. 22.1). The elastic deflection of the cantilever is monitored either directly or via a feedback mechanism



Fig. 22.1 Diagram of a commercial AFM. The AFM tip is mounted on a compliant cantilever, and a laser light is reflected off the back of the cantilever onto a position-sensitive detector (4-quadrant detector). Any movements of the cantilever beam cause a deflection of the laser light that the detector senses. The sample is moved using piezoelectric stack, and forces are calculated from the cantilever's stiffness and the measured deflection

to measure the forces acting on the probe. In general, the forces experienced by the probe tip split into attractive or repulsive forces. As the tip approaches the surface, it experiences intermolecular forces that are attractive, although they can be repulsive under certain circumstances [22.3]. Once in contact with the surface the tip usually experiences a combination of attractive intermolecular forces and repulsive elastic forces. Two schools of thought exist regarding the attractive forces when the tip is in contact with the surface. The first is often referred to as the DMT or Bradley model. It holds that attractive forces only act outside the region of contact [22.4–7]. The second theory, usually called the JKR model, assumes that all the forces experienced by the tip, whether attractive or repulsive, act in the region of contact [22.8]. Most real nanoscale contacts lie somewhere between these two theoretical extremes.

22.1.2 Nanoindentation

The fundamental difference between AFM and nanoindentation is that during a nanoindentation experiment an external load is applied to the indenter tip. This load enables the tip to be pushed into the sample, creating a nanoscale impression on the surface, otherwise referred to as a nanoindentation or nanoindent.

Conventional indentation or microindentation tests involve pushing a hard tip of known geometry into the sample surface using a fixed peak load. The area of indentation that is created is then measured, and the mechanical properties of the sample, in particular its hardness, is calculated from the peak load and the indentation area. Various types of indentation testing are used in measuring hardness, including Rockwell, Vickers, and Knoop tests. The geometries and definitions of hardness used in these tests are shown by Fig. 22.2.

When indentations are performed on the nanoscale there is a basic problem in measuring the size of the indents. Standard optical techniques cannot easily be used to image anything smaller than a micron, while electron microscopy is simply impractical due to the time involved in finding and imaging small indents. To overcome these difficulties, nanoindentation methods have been developed that continuously record the load, displacement, time, and contact stiffness throughout the indentation process. This type of continuously recording indentation testing was originally developed in the former Soviet Union [22.9–13] as an extension of microindentation tests. It was applied to nanoscale indentation testing in the early 1980s [22.14, 15], hence, giving rise to the field of nanoindentation testing.



Fig. 22.2 **(a)** The standard Rockwell hardness test involves pushing a ball into the sample with a minor load, recording the depth, d_1, then applying a major load and recording the depth, d_2, then returning to the lower load and recording the depth, d_3. Using the depths, the hardness is calculated. **(b)** Vickers hardness testing uses a four-sided pyramid pushed into the sample with a known load. The area of the resulting indentation is measured optically and the hardness calculated as the load is divided by area. **(c)** Knoop indentation uses the same definition of hardness as the Vickers test, load divided by area, but the indenter geometry has one long diagonal and one short diagonal

In general, nanoindentation instruments include a loading system that may be electrostatic, electromagnetic, or mechanical, along with a displacement measuring system that may be capacitive or optical. Schematics of several commercial nanoindentation instruments are shown in Fig. 22.3a–c.

Among the many advantages of nanoindentation over conventional microindentation testing is the ability to measure the elastic, as well as the plastic properties of the test sample. The elastic modulus is obtained from the contact stiffness (S) using the following equation that



Fig. 22.3a–c Schematics of three commercial nanoindentation devices made by **(a)** MTS Nanoinstruments, Oak Ridge, Tennessee, **(b)** Hysitron Inc., Minneapolis, Minnesota, **(c)** Micro Materials Limited, Wrexham, UK. Instruments **(a)** and **(c)** use electromagnetic loading, while **(b)** uses electrostatic loads

appears to be valid for all elastic contacts [22.16, 17]:

$$S = \frac{2}{\sqrt{\pi}} E_r \sqrt{A} \,. \tag{22.1}$$

A is the contact area and E_r is the reduced modulus of the tip and sample as given by:

$$\frac{1}{E_r} = \frac{\left(1-\nu_t^2\right)}{E_t} + \frac{\left(1-\nu_s^2\right)}{E_s} \,, \tag{22.2}$$

where E_t, ν_t and E_s, ν_s are the elastic modulus and Poissons ratio of the tip and sample, respectively.

22.1.3 Adaptations of Nanoindentation

Several adaptations to the basic nanoindentation setup have been used to obtain additional information about the processes that occur during nanoindentation testing, for example, in situ measurements of acoustic emissions and contact resistance. Environmental control has also been used to examine the effects of temperature and surface chemistry on the mechanical behavior of nanocontacts. In general, it is fair to say that the more information that can be obtained and the greater the control over the experimental parameters the easier it will be to understand the nanoindentation results. Load-displacement curves provide a lot of information, but they are only part of the story.

During nanoindentation testing discontinuities are frequently seen in the load–displacement curve. These are often called "pop-ins" or "pop-outs", depending on their direction. These sudden changes in the indenter displacement, at a constant load (see Fig. 22.4), can be caused by a wide range of events, including fracture, delamination, dislocation multiplication, or nucleation and phase transformations. To help distinguish between the various sources of discontinuities, acoustic transducers have been placed either in contact with the sample or immediately behind the indenter tip. For example, the results of nanoindentation tests that monitor acoustic emissions have shown that the phase transformations seen in silicon during nanoindentation are not the sudden events that they would appear to be from the load–displacement curve. There is no acoustic emission associated with the pop-out seen in the unloading curve of silicon [22.18]. An acoustic emission would be expected if there were a very rapid phase transformation causing a sudden change in volume. Fracture and delamination of films, however, give very strong acoustic signals [22.19],



Fig. 22.4 Sketch of a load/displacement curve showing a pop-in and a pop-out

but the exact form of the signal appears to be more closely related to the sample geometry than to the event [22.20].

Additional information about the nature of the deformed region under the nanoindentation can be obtained by performing in situ measurements of contact resistance. The basic setup for this type of testing is shown in Fig. 22.5. An electrically conductive tip is needed to study contact resistance. Consequently, a conventional diamond tip is of limited use. Elastic, hard, and metallically conductive materials such as vanadium carbide can be used as substitutes for diamond [22.21, 22], or a thin conductive film (e.g., Ag) can be deposited on the diamond's surface (such a film is easily transferred to the indented surface so great care must be taken if multiple indents are performed). Measurements of contact resistance have been most useful for examining phase transformations in semiconductors [22.21, 22] and the dielectric breakdown of oxide films under mechanical loading [22.23].

One factor that is all too frequently neglected during nanoindentation testing is the effect of the experimental environment. Two obvious ways in which the environment can affect the results of nanoindentation tests are increases in temperature, which give elevated creep rates, and condensation of water vapor, which modifies the tip-sample interactions. Both of these environmental effects have been shown to significantly affect the measured mechanical properties and the modes of deformation that occur during nanoindentation [22.24–27]. Other environmental effects, for instance, those due to photoplasticity or hydrogen ion absorption, are also possible, but they are generally less troublesome than temperature fluctuations and variations in atmospheric humidity.



Fig. 22.5 Schematic of the basic setup for making contact resistance measurements during nanoindentation testing

22.1.4 Complimentary Techniques

Nanoindentation testing is probably the most important technique for characterizing the mechanical properties of thin films and surfaces, but there are many alternative or additional techniques that can be used. One of the most important alternative methods for measuring the mechanical properties of thin films uses bulge or blister testing [22.28]. Bulge tests are performed on thin films mounted on supporting substrates. A small area of the substrate is removed to give a window of unsupported film. A pressure is then applied to one side of the window causing it to bulge. By measuring the height of the bulge, the stress-strain curve and the residual stress are obtained. The basic configuration for bulge testing is shown in Fig. 22.6.

22.1.5 Bulge Tests

The original bulge tests used circular windows because they are easier to analyze mathematically, but now square and rectangular windows have become common [22.29]. These geometries tend to be easier to fabricate. Unfortunately, there are several sources of errors in bulge testing that can potentially lead to large errors in the measured mechanical properties. These errors at one time led to the belief that multilayer films can show a "super modulus" effect, where the elastic modulus of the multilayer is several times that of its constituent



Fig. 22.6 Schematic of the basic setup for bulge testing. The sample is prepared so that it is a thin membrane, and then a pressure is applied to the back of the membrane to make it bulge upwards. The height of the bulge is measured using an interferometer

layers [22.30]. It is now accepted that any enhancement to the elastic modulus in multilayer films is small, on the order of 15% [22.31]. The main sources of error stem from compressive stresses in the film (tensile stress is not a problem), small variations in the dimensions of the window, and uncertainty in the exact height of the bulge. Despite these difficulties, one advantage of bulge testing over nanoindentation testing is that the stress state is biaxial, so that only properties in the plane of the film are measured. In contrast, nanoindentation testing measures a combination of in-plane and out-of-plane properties.

22.1.6 Acoustic Methods

Acoustic and ultrasonic techniques have been used for many years to study the elastic properties of materials. Essentially, these techniques take advantage of the fact that the velocity of sound in a material is dependent on the inter-atomic or inter-molecular forces in the material. These, of course, are directly related to the material's elastic constants. In fact, any nonlinearity of inter-atomic forces enables slight variations in acoustic signals to be used as a measure of residual stress.

An acoustic method ideally suited to studying surfaces is scanning acoustic microscopy (SAM) [22.32]. There are also several other techniques that have been used to study surface films and multilayers, but we will first consider SAM in detail. In a SAM, a lens made of sapphire is used to bring acoustic waves to focus via a coupling fluid on the surface. A small piezoelectric transducer at the top of the lens generates the acoustic signal. The same transducer can be used to detect the signal when the SAM is used in reflection mode. The use of a transducer as both generator and detector, a common imaging mode, necessitates the use of a pulsed rather than a continuous acoustic signal. Continuous waves can be used if phase changes are used to build up the image. The transducer lens generates two types of acoustic waves in the material: longitudinal and shear. The ability of a solid to sustain both types of wave (liquids can only sustain longitudinal waves) gives rise to a third type of acoustic wave called a Rayleigh, or surface, wave. These waves are generated as a result of superposition of the shear and longitudinal waves with a common phase velocity. The stresses and displacements associated with a Rayleigh wave are only of significance to a depth of ≈ 0.6 Rayleigh wavelengths below the solid surface. Hence, using SAM to examine Rayleigh waves in a material is a true surface characterization technique.

Using a SAM in reflection mode gives an image where the contrast is directly related to the Rayleigh wave velocity, which is in turn a function of the material's elastic constants. The resolution of the image depends on the frequency of the transducer used, i. e., for a 2 GHz signal a resolution better than 1 μm is achievable. The contrast in the image results from the interference of two different waves in the coupling fluid. Rayleigh waves that are excited in the surface "leak" into the coupling fluid and interfere with the acoustic signal that is directly reflected back from the surface. It is usually assumed that the properties of the coupling fluid are well characterized. The interference of the two waves gives a characteristic $V(z)$ curve, as illustrated by Fig. 22.7, where z is the separation between the lens and the surface. Analyzing the periodicity of the $V(z)$ curves provides information on the Rayleigh wave velocity. As with other acoustic waves, the Rayleigh velocity is related to the elastic constants of the material. When using the SAM for a material's characterization, the lens is usually held in a fixed position on the surface. By using a lens designed specifically to give a line-focus beam, rather than the standard spherical lens, it is possible to use SAM to look at anisotropy in the wave velocity [22.33] and hence in elastic properties by producing waves with a specific direction.

One advantage of using SAM in conjunction with nanoindentation to characterize a surface is that the measurements obtained with the two methods have a slightly different dependence on the test material's elastic properties, E_s and ν_s (the elastic modulus and Poisson's ratio). As a result, it is possible to use SAM



Fig. 22.7 A typical $V(z)$ curve obtained with a SAM when testing fused silica

and nanoindentation combined to find both E_s and ν_s, as illustrated by Fig. 22.8 [22.34]. This is not possible when using only one of the techniques alone.

In addition to measuring surface properties, SAM has been used to study thin films on a surface. However, the Rayleigh wave velocity can be dependent on a complex mix of the film and substrate properties. Other acoustic methods have been utilized to study freestanding films. A freestanding film can be regarded as a plate, and, therefore, it is possible to excite Lamb waves in the film. Using a pulsed laser to generate the waves and a heterodyne interferometer to detect the arrival of the Lamb wave, it is possible to measure the flexural modulus of the film [22.35]. This has been successfully demonstrated for multilayer films with a total thickness $< 10\,\mu\mathrm{m}$. In the plate configuration, due to the nonlinearity of elastic properties, it is also possible to measure stress. This has been demonstrated for horizontally polarized shear waves in plates [22.36], but thin plates require very high frequency transducers or laser sources.



Fig. 22.8 Because SAM and nanoindentation have different dependencies on Young's modulus, E, and Poissons ratio, ν, it is possible to use the two techniques in combination to find E and ν [22.34]. On the graph, the intersection of the curves gives E and ν

22.1.7 Imaging Methods

When measuring the mechanical properties of a surface or thin film using nanoindentation, it is not always easy to visualize what is happening. In many instances there is a risk that the mechanical data can be completely misinterpreted if the geometry of the test is not as expected. To expedite the correct interpretation of the mechanical data, it is generally worthwhile to use optical, electron, or atomic force microscopy to image the nanoindentations. Obviously, optical techniques are only of use for larger indentations, but they will often reveal the presence of median or lateral cracks [22.37]. Electron microscopy and AFM, however, can be used to examine even the smallest nanoindentations. The principle problem with these microscopy techniques is the difficulty in finding the nanoindentations. It is usually necessary to make large, "marker" indentations in the vicinity of the nanoindentations to be examined in order to find them [22.38].

It is possible to see features such as extrusions with a scanning electron microscope (SEM) [22.39], as well as pile-up and sink-in around the nanoindents, though AFM is generally better for this. Transmission electron microscopy (TEM) is useful for examining what has happened subsurface, for instance, the indentation induced dislocations in a metal [22.40] or the phases present under a nanoindent in silicon [22.21]. However, with TEM there is the added difficulty of sample preparation and the associated risk of observing artifacts. Recently, there has been considerable interest in the use of focused ion beams to cut cross sections through nanoindents [22.41]. When used in conjunction with SEM or TEM this provides an excellent means to see what has happened in the subsurface region.

One other technique that has proved to be useful in studying nanoindents is micro-Raman spectroscopy. This involves using a microscope to focus a laser on the sample surface. The same microscope is also used to collect the scattered laser light, which is then fed into a spectroscope. The Raman peaks in the spectrum provide information on the bonding present in a material, while small shifts in the wave number of the peaks can be used as a measure of strain. Micro-Raman has proven to be particularly useful for examining the phases present around nanoindentations in silicon [22.42].

22.2 Data Analysis

The analysis of nanoindentation data is far from simple. This is mostly due to the lack of effective models that are able to combine elastic and plastic deformation under a contact. However, provided certain precautions are taken, the models for perfectly elastic deformation and ideal plastic materials can be used in the analysis of nanoindentation data. For this reason, it is worth briefly reviewing the models for perfect contacts.



Fig. 22.9 Hertzian contact of a sphere, radius R, on a semi-infinite, flat surface. The contact in this case is a circular region of radius a

22.2.1 Elastic Contacts

The theoretical modeling of elastic contacts can be traced back many years, at least to the late nineteenth century and the work of *Hertz* (1882) [22.43] and *Boussinesq* (1885) [22.44]. These models, which are still widely used today, consider two axisymmetric curved surfaces in contact over an elliptical region (see Fig. 22.9). The contact region is taken to be small in comparison to the radius of curvature of the contacting surfaces, which are treated as elastic half-spaces. For an elastic sphere, radius R, in contact with a flat, elastic half-space, the contact region will be circular and the Hertz model gives the following relationships:

$$a = \sqrt[3]{\frac{3PR}{4E_\mathrm{r}}} , \qquad (22.3)$$

$$\delta = \sqrt[3]{\frac{9P^2}{16RE_\mathrm{r}^2}} , \qquad (22.4)$$

$$P_0 = \sqrt[3]{\frac{6PE_\mathrm{r}^2}{\pi^3 R^2}} , \qquad (22.5)$$

where a is the radius of the contact region, E_r is given by (22.2), δ is the displacement of the sphere into the surface, P is the applied load and P_0 is the maximum pressure under the contact (in this case at the center of the contact).

The work of *Hertz* and *Boussinesq* was extended by *Love* [22.45, 46] and later by *Sneddon* [22.47], who simplified the analysis using Hankel transforms. *Love* showed how *Boussinesq*'s model could be used for a flat-ended cylinder and a conical indenter, while *Sneddon* produced a generalized relationship for any rigid axisymmetric punch pushed into an elastic half-space. *Sneddon* applied his new analysis to punches of various shapes and derived the following relationships between the applied load, P, and displacement, δ, into the elastic half-space for, respectively, a flat-ended cylinder, a cone of semi-vertical angle ϕ, and a parabola of revolution where $a^2 = 2k\delta$:

$$P = \frac{4\mu a\delta}{1-\nu} , \qquad (22.6)$$

$$P = \frac{4\mu \cot\phi}{\pi\,(1-\nu)}\delta^2 , \qquad (22.7)$$

$$P = \frac{8\mu}{3\,(1-\nu)}\left(2k\delta^3\right)^{1/2} , \qquad (22.8)$$

where μ and ν are the shear modulus and Poisson's ratio of the elastic half-space, respectively.

The key point to note about (22.6), (22.7), and (22.8) is that they all have the same basic form, namely:

$$P = \alpha\delta^m , \qquad (22.9)$$

where α and m are constants for each geometry.

Equation (22.9) and the relationships developed by Hertz and his successors, (22.3–22.8), form the foundation for much of the current nanoindentation data analysis routines.

22.2.2 Indentation of Ideal Plastic Materials

Plastic deformation during indentation testing is not easy to model. However, the indentation response of ideal plastic metals was considered by *Tabor* in his classic text, "The Hardness of Metals" [22.48]. An ideal plastic material (or more accurately an ideal elastic-plastic material) has a linear stress-strain curve until it reaches its elastic limit and then yields plastically at a yield stress,Y_0, that remains constant even after deformation has commenced. In a 2-D problem, the yielding occurs because the Huber-Mises [22.49] criterion has been reached. In other words, the maximum shear stress acting on the material is around $1.15Y_0/2$.

First, we consider a 2-D flat punch pushed into an ideal plastic material. By using the method of slip lines it is found that the mean pressure, P_m, across the end of the punch is related to the yield stress by:

$$P_m = 3Y_0 . \qquad (22.10)$$

If the *Tresca* criterion [22.50] is used, then P_m is closer to $2.6Y_0$. In general, for both 2-D and three-dimensional punches pushed into ideal plastic materials, full plasticity across the entire contact region can be expected when $P_m = 2.6$ to $3.0Y_0$. However, significant deviations from this range can be seen if, for instance, the material undergoes work-hardening during indentation, or the material is a ceramic, or there is friction between the indenter and the surface.

The apparently straightforward relationship between P_m and Y_0 makes the mean pressure a very useful quantity to measure. In fact, P_m is very similar to the Vickers hardness, H_V, of a material:

$$H_V = 0.927P_m . \qquad (22.11)$$

During nanoindentation testing it is the convention to take the mean pressure as the nanohardness. Thus, the “nanohardness”, H, is defined as the peak load, P, applied during a nanoindentation divided by the projected area, A, of the nanoindentation in the plane of the surface, hence:

$$H = \frac{P}{A} . \qquad (22.12)$$

22.2.3 Adhesive Contacts

During microindentation testing and even most nanoindentation testing the effects of intermolecular and surface forces can be neglected. Very small nanoindentations, however, can be influenced by the effects of intermolecular forces between the sample and the tip. These adhesive effects are most readily seen when testing soft polymers, but there is some evidence that forces between the tip and sample may be important in even relatively strong materials [22.51, 52].

Contact adhesion is usually described by either the JKR or DMT model, as discussed earlier in this chapter. Both the models consider totally elastic spherical contacts under the influence of attractive surface forces. The JKR model considers the surface forces in terms of the associated surface energy, whereas the DMT model considers the effects of adding van der Waals forces to the Hertzian contact model. The differences between the two models are illustrated by Fig. 22.10.


DMT
Only compressive elastic forces in region of contact
Van der Waals forces outside region of contact
JKR
All compressive and tensile forces act in region of contact
No forces outside region of contact

Fig. 22.10 The contact geometry for the DMT and JKR models for adhesive contact. Both models are based on the Hertzian model. In the DMT, model van der Waals forces outside the region of contact introduce an additional load in the Hertz model. But for the JKR model, it is assumed that tensile, as well as compressive stresses can be sustained within the region of contact

For nanoindentation tests conducted in air the condensation of water vapor at the tip-sample interface usually determines the size of the adhesive force acting during unloading. The effects of water vapor on a single nanoasperity contact have been studied using force-controlled AFM techniques [22.53] and, more recently, nanoindentation methods [22.26]. Unsurprisingly, it has also been found that water vapor can affect the deformation of surfaces during nanoindentation testing [22.27].

In addition to water vapor, other surface adsorbates can cause dramatic changes in the nanoscale mechanical behavior. For instance, oxygen on a clean metal surface can cause an increase in the apparent strength of the metal [22.54]. These effects are likely to be related to, firstly, changes in the surface and intermolecular forces acting between the tip and the sample and, secondly, changes in the mechanical stability of surface nanoasperities and ledges. Adsorbates can help stabilize atomic-scale variations in surface morphology, thereby making defect generation at the surface more difficult.

22.2.4 Indenter Geometry

All of the indenter geometries considered up to this point have been axisymmetric, largely because they are easier to deal with theoretically. Unfortunately, fabricating axisymmetric nanoindentation tips is extremely difficult, because shaping a hard tip on the scale of a few nanometers is virtually impossible. Despite these problems, there has been considerable effort put into the use of spherical nanoindentation tips [22.55]. This clearly demonstrates that the spherical geometry can be useful at larger indentation depths.

Because of the problems associated with creating axisymmetric nanoindentation tips, pyramidal indenter geometries have now become standard during nanoindentation testing. The most common geometries are the three-sided Berkovich pyramid and cube-corner (see Fig. 22.11). The Berkovich pyramid is based on the four-sided Vickers pyramid, the opposite sides of which make an 136° angle. For both the Vickers and Berkovich pyramids the cross-sectional area of the pyramid's base, A, is related to the pyramid's height, D, by:

$$A = 24.5D^2 \,. \tag{22.13}$$

The cube-corner geometry is now widely used for making very small nanoindentations, because it is much sharper than the Berkovich pyramid. This makes it easier to initiate plastic deformation at very light loads, but great care should be taken when using the cube-corner geometry. Sharp cube-corners can wear down quickly and become blunt, hence the cross-sectional area as a function of depth can change over the course of several indentations. There is also a potential problem with the standard analysis routines [22.56], which were developed for much blunter geometries and are based on the elastic contact models outlined earlier. The elastic contact models all assume the displacement into the surface is small compared to the tip radius. For the cube-corner geometry this is probably only the case for nanoindentations that are no more than a few nanometers deep.



Fig. 22.11 The ideal geometry for the three-sided Berkovich pyramid and cube corner tips

22.2.5 Analyzing Load/Displacement Curves

The load/displacement curves obtained during nanoindentation testing are deceptively simple. Most newcomers to the area will see the curves as being somewhat akin to the stress/strain curves obtained during tensile testing. There is also a real temptation just to use the values of hardness, H, and elastic modulus, E, obtained from standard analysis software packages as the "true" values. This may be the case in many instances, but for very shallow nanoindents and tests on thin films the geometry of the contact can differ significantly from the geometry assumed in the analysis routines. Consequently, experimentalists should think very carefully about the test itself before concluding that the values of H and E are correct.

The basic shape of a load/displacement curve can reveal a great deal about the type of material being tested. Figure 22.12 shows some examples of ideal curves for materials with different elastic moduli and yield stresses. Discontinuities in the load/displacement curve can also provide information on such processes as fracture, dislocation nucleation, and phase transformations. Initially,



Fig. 22.12 Examples of load/displacement curves for idealized materials with a range of hardness and elastic properties

though, we will consider ideal situations such as those illustrated by Fig. 22.12.

The loading section of the load/displacement curve approximates a parabola [22.60] whose width depends on a combination of the material's elastic and plastic properties. The unloading curve, however, has been shown to follow a more general relationship [22.56] of the form:

$$P = \alpha\,(\delta - \delta_i)^m\ , \tag{22.14}$$

where δ is the total displacement and δ_i is the intercept of the unloading curve with the displacement axis shown in Fig. 22.13.

Equation (22.14) is essentially the same as (22.9) but with the origin displaced. Since (22.9) is obtained by considering purely elastic deformation, it follows that the unloading curve is exhibiting purely elastic behavior. Since the shape of the unloading curve is determined by the elastic recovery of the indented region, it is not entirely surprising that its shape resembles that found for purely elastic deformation. What is fortuitous is that the elastic analysis used for an elastic half-space seems to be valid for a surface where there is a plastically formed indentation crater present under the contact. However, the validity of this analysis may only hold when the crater is relatively shallow and the geometry of the surface does not differ significantly from that of a flat, elastic half-space. For nanoindentations with a Berkovich pyramid, this is generally the case.



Fig. 22.13a,b Analysis of the load/displacement curve gives the contact stiffness, S, and the contact depth, δ_c. These can then be used to find the hardness, H, and elastic, or Young's modulus, E. **(a)** The first method of analysis [22.57–59] assumed the unloading curve could be approximated by a flat punch on an elastic half-space. **(b)** A more refined analysis [22.56] uses a paraboloid on an elastic half-space

Before *Oliver* and *Pharr* [22.56] proposed their now standard method for analyzing nanoindentation data, the analysis had been based on the observation that the initial part of the unloading curve is almost linear. A linear unloading curve, equivalent to $m = 1$ in (22.14), is expected when a flat punch is used on an elastic half-space. The flat punch approximation for the unloading curve was used in [22.57–59] to analyze nanoindentation data. When Oliver and Pharr looked at a range of materials they found m was typically larger than 1, and that $m = 1.5$, or a paraboloid, was a better approximation than a flat punch. Oliver and Pharr used (22.1) and (22.12) to obtain the values for a material's elastic modulus and hardness. Equation (22.1) relates the contact stiffness during the initial part of the unloading curve (see Fig. 22.13) to the reduced elastic modulus and the contact area at the peak load. Equation (22.12) gives the hardness as the peak load divided by the contact area. It is immediately obvious that the key to measuring the mechanical properties of a material is knowing the contact area at the peak load. This is the single most important factor in analyzing nanoindentation data. Most mistakes in the analysis come from incorrect assumptions about the contact area.

To find the contact area, a function relating the contact area, A_c, to the contact depth, δ_c, is needed. For a perfect Berkovich pyramid this would be the same as (22.13). But since making a perfect nanoindenter tip is impossible, an expanded equation is used:

$$A_c\,(\delta_c) = 24.5\delta_c^2 + \sum_{j=1}^{7} C_j \sqrt[2^j]{\delta_c}\ , \tag{22.15}$$

where C_j are calibration constants of the tip.

There is a crucial step in the analysis before A_c can be calculated, namely, finding δ_c. The contact depth is not the same as the indentation depth, because the surface around the indentation will be elastically deflected during loading, as illustrated by Fig. 22.14. Sneddon's analysis [22.47] provides a way to calculate the deflection of the surface at the edge of an axisymmetric



Fig. 22.14 Profile of surface under load and unloaded showing how δ_c compares to δ_i and δ_{max}

contact. Subtracting the deflection from the total indentation depth at peak load gives the contact depth. For a paraboloid, as used by *Oliver* and *Pharr* [22.56] in their analysis, the elastic deflection at the edge of the contact is given by:

$$\delta_s = \varepsilon \frac{P}{S} = 0.75 \frac{P}{S} \, , \tag{22.16}$$

where S is the contact stiffness and P the peak load. The constant ε is 0.75 for a paraboloid, but ranges between 0.72 (conic indenter) and 1 (flat punch). Figure 22.15 shows how the contact depth depends on the value of ε. The contact depth at the peak load is, therefore:

$$\delta_c = \delta - \delta_s \, . \tag{22.17}$$

Using the load/displacement data from the unloading curve and (22.1), (22.2), (22.12), (22.14–22.17), the hardness and reduced elastic modulus for the test sample can be calculated. To find the elastic modulus of the sample, E_s, it is also necessary to know Poisson's ratio, ν_s, for the sample, as well as the elastic modulus, E_t, and Poisson's ratio, ν_t, of the indenter tip. For diamond these are 1,141 GPa and 0.07, respectively.

There also remains the issue of calibrating the tip shape, or finding the values for C_j in (22.15). Knowing the exact expansion of $A_c(\delta_c)$ is vital if the values for E_s and H are to be accurate. Several methods for calibrating the tip shape have been used, including imaging the tip with an electron microscope, measuring the size of nanoindentations using SEM or TEM of negative replicas, and using scanning probes to examine either the tip itself or the nanoindentations made with the tip. There are strengths and weaknesses to each of these methods. In general, however, the accuracy and usefulness of the methods depends largely on how patient and rigorous the experimentalist is in performing the calibration.



Fig. 22.15 Load-displacement curve showing how δ_c varies with ε

Because of the experimental difficulties and time involved in calibrating the tip shape by these methods, *Oliver* and *Pharr* [22.56] developed a method for calibration based on standard specimens. With a standard specimen that is mechanically isotropic and has a known E and H that does not vary with indentation depth, it should be possible to perform nanoindentations to a range of depths, and then use the analysis routines in reverse to deduce the tip area function, $A_c(\delta_c)$. In other words, if you perform a nanoindentation test, you can find the contact stiffness, S, at the peak load, P, and the contact depth, δ_c, from the unloading curve. Then if you know E a priori, (22.1) can be used to calculate the contact area, A, and, hence, you have a value for A_c at a depth δ_c. Repeating this procedure for a range of depths will give a numerical version of the function $A_c(\delta_c)$. Then, it is simply a case of fitting (22.15) to the numerical data. If the hardness, H, is known and not a function of depth, and the calibration specimen was fully plastic during testing, then essentially the same approach could be used but based on (22.12). Situations where a constant H is used to calibrate the tip are extremely rare.

In addition to the tip shape function, the machine compliance must be calibrated. Basic Newtonian mechanics tells us that for the tip to be pushed into a surface the tip must be pushing off of another body. During nanoindentation testing the other body is the machine frame. As a result, during a nanoindentation test it is not just the sample, but the machine frame that is being loaded. Consequently, a very small elastic deformation of the machine frame contributes to the total stiffness obtained from the unloading curve. The machine frame is usually very stiff, $> 10^6$ N/m, so the effect is only important at relatively large loads.

To calibrate the machine frame stiffness or compliance, large nanoindentations are made in a soft material such as aluminum with a known, isotropic elastic modulus. For very deep nanoindentations made with a Berkovich pyramid, the contact area, $A_c(\delta_c)$, can be reasonably approximated to $24.5\delta_c^2$, thus (22.1) can be used to find the expected contact stiffness for the material. Any difference between the expected value of S

and the value measured from the unloading curve will be due to the compliance of the machine frame. Performing a number of deep nanoindentations enables an accurate value for the machine frame compliance to be obtained.

Currently, because of its ready availability and predictable mechanical properties, the most popular calibration material is fused silica ($E = 72\,\mathrm{GPa}$, $\nu = 0.17$), though aluminum is still used occasionally.

22.2.6 Modifications to the Analysis

Since the development of the analysis routines in the early 1990s, it has become apparent that the standard analysis of nanoindentation data is not applicable in all situations, usually because errors occur in the calculated contact depth or contact area. *Pharr* et al. [22.61–64] have used finite element modeling (FEM) to help understand and overcome the limitations of the standard analysis. Two important sources of errors have been identified in this way. The first is residual stress at the sample surface. The second is the change in the shape of nanoindents after elastic recovery.

The effect of residual stresses at a surface on the indentation properties has been the subject of debate for many years [22.65–67]. The perceived effect was that compressive stresses increased hardness, while tensile stresses decreased hardness. Using FEM it is possible to model a pointed nanoindenter being pushed into a model material that is in residual tension or compression. An FEM model of nanoindentation into aluminum alloy 8009 [22.61] has confirmed earlier experimental observations [22.68] indicating that the contact area calculated from the unloading curve is incorrect if there are residual stresses. In the FEM model of an aluminum alloy the mechanical behavior of the material is modeled using a stress-strain curve, which resembles that of an elastic-perfectly-plastic metal with a flow stress of 425.6 MPa. Yielding starts at 353.1 MPa and includes a small amount of work hardening. The FEM model was used to find the contact area directly and using the simulated unloading curve in conjunction with Oliver and Pharr's method. The results as a function of residual stress are illustrated in Fig. 22.16. Note that the differences between the two measured contact areas lead to miscalculations of E and H.

Errors in the calculated contact area stem from incorrect assumptions about the pile-up and sink-in at the edge of the contact, as illustrated by Fig. 22.17. The Oliver and Pharr analysis assumes the geometry of the sample surface is the same as that given by *Sneddon* [22.47] in his analytical model for the indentation of elastic surfaces. Clearly, for materials where there is significant plastic deformation, it is possible that there will be large deviations from the surface geometry found using Sneddon's elastic model. In reality, the error in the contact area depends on how much the geometry of the test sample surface differs from that of the calibration material (typically fused silica). It is possible that a test sample, even without a residual stress, will have a different surface geometry and, hence, contact area at a given depth, when compared to the calibration material. This is often seen for thin films on a substrate (e.g., *Tsui* et al. [22.69, 70]). Residual stresses increase the likelihood that the contact area calculated using Oliver and Pharr's method will be incorrect.



Fig. 22.16 When a surface is in a state of stress there is a significant difference between the contact area calculated using the Oliver and Pharr method and the actual contact area [22.61]. For an aluminum alloy this can lead to significant errors in the calculated hardness and elastic modulus



Fig. 22.17 Pile-up and sink-in are affected by residual stresses, and, hence, errors are introduced into standard Oliver and Pharr analysis

The issue of sink-in and pile-up is always a factor in nanoindentation testing. However, there is still no effective way to deal with these phenomena other than reverting to imaging of the indentations to identify the true contact area. Even this is difficult, as the edge of an indentation is not easy to identify using AFM or electron microscopy. One approach that has been used [22.71] with some success is measuring the ratio E_r^2/H, rather than E_r and H separately. Because E_r is proportional to $1/\sqrt{A}$ and H is proportional to $1/A$, E_r^2/H should be independent of A and, hence, unaffected by pile-up or sink-in. While this does not provide quantitative values for mechanical properties, it does provide a way to identify any variations in mechanical properties with indentation depth or between similar samples with different residual stresses.

Another source of error in the Oliver and Pharr analysis is due to incorrect assumptions about the nanoindentation geometry after unloading [22.63]. Once again, this is due to differences between the test sample and the calibration material. The exact shape of an unloaded nanoindentation on a material exhibiting elastic recovery is not simply an impression of the tip shape; rather, there is some elastic recovery of the nanoindentation sides giving them a slightly convex shape (see Fig. 22.18). The shape actually depends on Poisson's ratio, so the standard Oliver and Pharr analysis will only be valid for a material where $\nu = 0.17$, the value for fused silica, assuming it is used for the calibration.

To deal with the variations in the recovered nanoindentation shape, it has been suggested [22.63] that a modified nanoindenter geometry with a slightly concave side be used in the analysis (see Fig. 22.18). This requires a modification to (22.1):



Fig. 22.18 **(a)** *Hay* et al. [22.63] found from experiments and FEM simulations that the actual shape of an indentation after unloading is not as expected. **(b)** They introduced a γ term to correct for this effect. This assumes the indenter has slightly concave sides



Fig. 22.19 For a real Berkovich tip the γ corrected area [22.63] is less at a given depth than the area calculated using the Oliver and Pharr method

$$S = \gamma 2E_r\sqrt{\frac{A}{\pi}} , \tag{22.18}$$

where γ is a correction term dependent on the tip geometry. For a Berkovich pyramid the best value is:

$$\gamma = \frac{\frac{\pi}{4} + 0.15483073 \cot \Phi \left(\frac{(1-2\nu_s)}{4(1-\nu_s)}\right)}{\left[\frac{\pi}{2} - 0.83119312 \cot \Phi \left(\frac{(1-2\nu_s)}{4(1-\nu_s)}\right)\right]^2} , \tag{22.19}$$

where $\Phi = 70.32°$. For a cube corner the correction can be even larger and γ is given by:

$$\gamma = 1 + \left(\frac{(1-2\nu_s)}{4(1-\nu_s)\tan\Phi}\right) , \tag{22.20}$$

where $\Phi = 42.28°$. Figure 22.19 shows how the modified contact area varies with depth for a real diamond Berkovich pyramid.

The validity of the γ-modified geometry is questionable from the perspective of contact mechanics since it relies on assuming an incorrect geometry for the nanoindenter tip to correct for an error in the geometry of the nanoindentation impression. The values for E and H obtained using the γ-modification are, however, good and can be significantly different to the values obtained with the standard Oliver and Pharr analysis.

22.2.7 Alternative Methods of Analysis

All of the preceding discussion on the analysis of nanoindentation curves has focused on the unloading curve, virtually ignoring the loading curve data. This is for the simple reason that the unloading curve can in many cases be regarded as purely elastic, whereas the shape of the loading curve is determined by a complex mix of elastic and plastic properties.

It is clear that there is substantially more data in the loading curve if it can be extracted. *Page* et al. [22.60, 72] have explored the possibility of curve fitting to the loading data using a combination of elastic and plastic properties. By a combination of analysis and empirical fitting to experimental data, it was suggested that the loading curve is of the following form:

$$P = E\left(\psi\sqrt{\frac{H}{E}}+\phi\sqrt{\frac{E}{H}}\right)^{-2}\delta^2\,, \tag{22.21}$$

where ψ and ϕ are determined experimentally to be 0.930 and 0.194, respectively. For homogenous samples this equation gives a linear relationship between P and δ^2. Coatings, thin film systems, and samples that strain-harden can give significant deviations from linearity. Analysis of the loading curve has yet to gain popularity as a standard method for examining nanoindentation data, but it should certainly be regarded as a prime area for further investigation.

Another alternative method of analysis is based on the work involved in making an indentation. In essence, the nanoindentation curve is a plot of force against distance indicating integration under the loading curve will give the total work of indentation, or the sum of the elastic strain energy and the plastic work of indentation. Integrating under the unloading curve should give only the elastic strain energy. Thus, the work involved in both elastic and plastic deformation during nanoindentation can be found. *Cheng* and *Cheng* [22.73] combined measurements of the work of indentation with a dimensional analysis that deals with the effects of scaling in a material that work-hardens to estimate H/E_r. They subsequently evaluated H and E using the Oliver and Pharr approach to find the contact area.



Fig. 22.20 A small AC load can be added to the DC load. This enables the contact stiffness, S, to be calculated throughout the indentation cycle

22.2.8 Measuring Contact Stiffness

As discussed earlier, it is possible to add a small AC load on top of the DC load used during nanoindentation testing, providing a way to measure the contact stiffness throughout the entire loading and unloading cycle [22.74, 75]. The AC load is typically at a frequency of ≈ 60 Hz and creates a dynamic system, with the sample acting as a spring with stiffness S (the contact stiffness), and the nanoindentation system acting as a series of springs and dampers. Figure 22.20 illustrates how the small AC load is added to the DC load. Figure 22.21 shows how the resulting dynamic system can be modeled. An analysis of the dynamic system gives the following relationships for S based on the amplitude of the AC displacement oscillation and the phase difference between the AC load and displacement signals:

$$\left|\frac{P_\mathrm{os}}{\delta(\omega)}\right| = \sqrt{\left[\left(S^{-1}+C_\mathrm{f}\right)^{-1}+K_\mathrm{s}-m\omega^2\right]^2+\omega^2D^2}\,, \tag{22.22}$$

$$\tan(\chi) = \frac{\omega D}{\left(S^{-1}+C_\mathrm{f}\right)^{-1}+K_\mathrm{s}-m\omega^2}\,, \tag{22.23}$$

where C_f is the load frame compliance (the reciprocal of the load frame stiffness), K_s is the stiffness of the support springs (typically in the region of 50–100 N/m), D is the damping coefficient, P_os is the magnitude of the load oscillation, $\delta(\omega)$ is the magnitude of the displacement oscillation, ω is the oscillation frequency, m is the mass of the indenter, and χ is the phase angle between the force and the displacement.

In order to find S using either (22.22) or (22.23), it is necessary to calibrate the dynamic response of the system when the tip is not in contact with a sample ($S^{-1}=0$). This calibration combined with the standard



Fig. 22.21 The dynamic model used in the analysis of the AC response of a nanoindentation device

DC calibrations will provide the values for all of the constants in the two equations. All that needs to be measured in order to obtain S is either $\delta(\omega)$ or χ, both of which are measured by the lock-in amplifier used to generate the AC signal. Since the S obtained is the same as the S in (22.1), it follows that the Oliver and Pharr analysis can be applied to obtain E_r and H throughout the entire nanoindentation cycle.

The dynamic analysis detailed here was developed for the MTS Nanoindenter$^{\text{TM}}$ (Oakridge, Tennessee), but a similar analysis has been applied to other commercial instruments such as the Hysitron Triboscope$^{\text{TM}}$ (Minneapolis, Minnesota) [22.76]. For all instruments, an AC oscillation is used in addition to the DC voltage, and a dynamic model is used to analyze the response.

22.2.9 Measuring Viscoelasticity

Using an AC oscillation in addition to the DC load introduces the possibility of measuring viscoelastic properties during nanoindentation testing. This has recently been the subject of considerable interest with researchers looking at the loss modulus, storage modulus, and loss tangent of various polymeric materials [22.25, 77]. Recording the displacement response to the AC force oscillation enables the complex modulus (including the loss and storage modulus) to be found. If the modulus is complex, it is clear from (22.1) that the stiffness also becomes complex. In fact, the stiffness will have two components: S', the component in phase with the AC force and S'', the component out of phase with the AC force.



Fig. 22.22 The simplified dynamic model used when the sample is viscoelastic. It is assumed that the load frame compliance is negligible

The dynamic model illustrated in Fig. 22.21 is no longer appropriate for this situation, as the contact on the test sample also includes a damping term, shown in Fig. 22.22. Equations (22.22) and (22.23) must also be revised. Neglecting the load frame compliance, C_f, which in most real situations is negligible, (22.22) and (22.23) when the sample damping, D_s, is included become:

$$\left|\frac{P_{os}}{\delta(\omega)}\right| = \sqrt{\left\{S+K_s-m\omega^2\right\}^2+\omega^2(D+D_s)^2}\,, \tag{22.24}$$

$$\tan(\chi) = \frac{\omega(D+D_s)}{S+K_s-m\omega^2}\,. \tag{22.25}$$

In order to find the loss modulus and storage modulus, (22.1) is used to relate S' (storage component) and S'' (loss component) to the complex modulus.

This method for measuring viscoelastic properties using nanoindentation has now been proven in principal, but has still only been applied to a very small range of polymers and remains an area of future growth.

22.3 Modes of Deformation

As described earlier, the analysis of nanoindentation data is based firmly on the results of elastic continuum mechanics. In reality, this idealized, purely elastic situation rarely occurs. For very shallow contacts on metals with thin surface films such as oxides, carbon layers, or organic layers [22.78, 79], the contact can initially be very similar to that modeled by Hertz and, later, Sneddon. It is very important to realize that this in itself does not constitute proof that the contact is purely elastic, because in many cases a small number of defects are present. These may be preexisting defects that move in the strain-field generated beneath the contact. Alternatively, defects can be generated either when the contact is first made or during the initial loading [22.52, 80]. When defects such as short lengths of dislocation are present the curves may still appear to be elastic even though inelastic processes like dislocation glide and cross-slip are taking place.

22.3.1 Defect Nucleation

Nucleation of defects during nanoindentation testing has been the subject of many experimental [22.81, 82] and theoretical studies [22.83, 84]. This is probably because nanoindentation is seen as a way to deform a small, defect-free volume of material to its elastic limit and beyond in a highly controlled geometry. There are, unfortunately, problems in comparing experimental results with theoretical predictions, largely because the kinetic processes involved in defect nucleation are difficult to model. Simulations conducted at 0 K do not permit kinetic processes, and molecular dynamics simulations are too fast (nanoseconds or picoseconds). Real nanoindentation experiments take place at ≈ 293 K and last for seconds or even minutes.

Kinetic effects appear in many forms, for instance, during the initial contact between the indenter tip and the surface when defects can be generated by the combined action of the impact velocity and surface forces [22.51]. A second example of a kinetic effect occurs during hold cycles at large loads when what appears to be an elastic contact can suddenly exhibit a large discontinuity in the displacement data [22.80]. Figure 22.23 shows how these kinetic effects can affect the nanoindentation data and the apparent yield point load.

During the initial formation of a contact, the deformation of surface asperities [22.51] and ledges [22.85] can create either point defects or short lengths of dislocation line. During the subsequent loading, the defects can help in the nucleation and multiplication of dislocations. The large strains present in the region surrounding the contact, coupled with the existence of defects generated on contact, can result in the extremely rapid multiplication of dislocations and, hence, pronounced discontinuities in the load-displacement curve. It is important to realize that the discontinuities are due to the rapid multiplication of dislocations, which may or may not occur at the same time that the first dislocation is nucleated. Dislocations may have been present for some time with the discontinuity only occurring when the existing defects are configured appropriately, as a Frank-Read source, for instance. Even under large strains, the time taken for a dislocation source to form from preexisting defects may be long. It is, therefore, not surprising that large discontinuities can be seen during hold cycles or unloading.

The generation of defects at the surface and the initiation of yielding is a complex process that is extremely dependent on surface asperities and surface forces. These, in turn, are closely related to the surface chemistry. It is not only the magnitude of surface forces, but also their range in comparison to the height of surface asperities that determines whether defects are generated on contact. Small changes in the surface chemistry or the velocity of the indenter tip when it first contacts the surface, can cause a transition from a situation in which defects are generated on contact to one where the contact is purely elastic [22.52].



Fig. 22.23a,b Load-displacement curves for W(100) showing how changes in the impact velocity can cause a transition from perfectly elastic behavior to yielding during unloading

When the generation of defects during the initial contact is avoided and the deformed region under the contact is truly defect free, then the yielding of the sample should occur at the yield stress of a perfect crystal lattice. The load at which plastic deformation commences under these circumstances becomes very reproducible [22.86]. Unfortunately, nanoindenter tips on the near-atomic scale are not perfectly smooth or axisymmetric. As a result, accurately measuring the yield stress is very difficult. In fact, a slight rotation in the plane of the surface of either the sample or the tip can give a substantial change in the observed yield point load. Coating the surface in a cushioning self-assembled monolayer [22.87] can alleviate some of these variations, but it also introduces a large uncertainty in the contact area. Surface oxide layers, which may be several nanometers thick, have also been found to enhance the elastic behavior seen for very shallow nanoindentations on metallic surfaces [22.78]. Removal of the oxide has been shown to alleviate the initial elastic response.

While nanoindentation testing is ideal for examining the mechanical properties of defect-free volumes and looking at the generation of defects in perfect crystal lattices, it should be clear from the preceding discussion that great care must be taken in examining how the surface properties and the loading rate affect the results, particularly when comparisons are being made to theoretical models for defect generation.

22.3.2 Variations with Depth

Ideal elastic-plastic behavior, as described by *Tabor* [22.48], can be seen during indentation testing, provided the sample has been work-hardened so that the flow stress is a constant. However, it is often the case that the mechanical properties appear to change as the load (or depth) is increased. This apparent change can be a result of several processes, including work-hardening during the test. This is a particularly important effect for soft metals like copper. These metals usually have a high hardness at shallow depths, but it decreases asymptotically with increasing indentation depth to a hardness value that may be less than half that observed at shallow depths. This type of behavior is due to the increasing density of geometrically necessary dislocations at shallow depths [22.88]. Hence the effects of work-hardening are most pronounced at shallow depths. For hard materials the effect is less obvious.

Work-hardening is one of the factors that contribute to the so-called indentation size effect (ISE), whereby at shallow indentation depths the material appears to be harder. The ISE has been widely observed during microindentation testing, with at least part of the effect appearing to result from the increased difficulty in optically measuring the area of an indentation when it is small. During nanoindentation testing the ISE can also be observed, but it is often due to the tip area function, $A_c(\delta_c)$, being incorrectly calibrated. However, there are physical reasons other than work-hardening for expecting an increase in mechanical strength in small volumes. As described in the previous section, small volumes of crystalline materials can have either no defects or only a small number of defects present, making plastic yielding more difficult. Also, because of dislocation line tension, the shear stress required to make a dislocation bow out increases as the radius of the bow decreases. Thus, the shear stress needed to make a dislocation bow out in a small volume is greater than it is in a large volume. These physical reasons for small volumes appearing stronger than large volumes are particularly important in thin film systems, as will be discussed later. Note, however, that these physical reasons for increased hardness do not apply for an amorphous material such as fused silica, which partially explains its value as a calibration material.

22.3.3 Anisotropic Materials

The analysis methods detailed earlier were concerned primarily with the interpretation of data from nanoindentations in isotropic materials where the elastic modulus is assumed to be either independent of direction or a polycrystalline average of a material's elastic constants. Many crystalline materials exhibit considerable anisotropy in their elastic constants, hence, these analysis techniques may not always be appropriate. The theoretical problem of a rigid indenter pressed into an elastic, anisotropic half-space has been considered by *Vlassak* and *Nix* [22.89]. Their aim was to identify the feasibility of interpreting data from a depth-sensing indentation apparatus for samples with elastic constants that are anisotropic. Nanoindentation experiments [22.90] have shown the validity of the elastic analysis for crystalline zinc, copper, and beta-brass. The observed indentation modulus for zinc, as predicted, varied by as much as a factor of 2 between different orientations. The variations in the observed hardness values for the same materials were smaller, with a maximum variation with orientation of 20% detected in zinc. While these variations are clearly detectable with nanoindentation techniques, the variations are small in comparison to the actual anisotropy of the test material's elastic properties. This is because the indentation modulus is a weighted average of the stiffness in all directions.

At this time the effects of anisotropy on the hardness measured using nanoindentation have not been fully explored. For materials with many active slip planes it is likely that the small anisotropy observed by *Vlassak* and *Nix* is correct once plastic flow has been initiated. It is possible, however, that for defect-free crystalline specimens with a limited number of active slip planes that very shallow nanoindentations may show a much larger anisotropy in the observed hardness and initial yield point load.

22.3.4 Fracture and Delamination

Indentation testing has been widely used to study fracture in brittle materials [22.91], but the lower loads and smaller deformation regions of nanoindentation tests make it harder to initiate cracks and, hence, less useful as a way to evaluate fracture toughness. To overcome these problems the cube corner geometry, which generates larger shear stresses than the Berkovich pyramid, has been used with nanoindentation testing to study fracture [22.92]. These studies have had mixed success, because the cube corner geometry blunts very quickly when used on hard materials. In many cases, brittle materials are very hard.

Depth sensing indentation is better suited to studying delamination of thin films. Recent work extends the research conducted by *Marshall* et al. [22.93, 94], who examined the deformation of residually stressed films by indentation. A schematic of their analysis is given by Fig. 22.24. Their indentations were several microns deep, but the basic analysis is valid for nanoindentations. The analysis has been extended to multilayers [22.95], which is important since it enables a quantitative assessment of adhesion energy when an additional stressed film has been deposited on top of the film and substrate of interest. The additional film limits the plastic deformation of the film of interest and also applies extra stress that aids in the delamination. After indentation, the area of the delaminated film is measured optically or with an AFM to assess the extent of the delamination. This measurement, coupled with the load-displacement data, enables quantitative assessment of the adhesion energy to be made for metals [22.96] and polymers [22.97].



Fig. 22.24a–e To model delamination *Kriese* et al. [22.95] adapted the model developed by *Marshall* and *Evans* [22.93]. The model considers a segment of removed stressed film that is allowed to expand and then indented, thereby expanding it further. Replacing the segment in its original position requires an additional stress, and the segment bulges upwards

22.3.5 Phase Transformations

The pressure applied to the surface of a material during indentation testing can be very high. Equation (22.10) indicates that the pressure during plastic yielding is about three times the yield stress. For many materials, high hydrostatic pressures can cause phase transformations, and provided the transformation pressure is less than the pressure required to cause plastic yielding, it is possible during indentation testing to induce a phase transformation. This was first reported for silicon [22.98], but it has also been speculated [22.99] that many other materials may show the same effects. Most studies still focus on silicon because of its enormous technological importance, although there is some evidence that germanium also undergoes a phase transformation during the nanoindentation testing [22.100].

Recent results [22.21, 22, 41, 101, 102] indicate that there are actually multiple phase transformations during the nanoindentation of silicon. TEM of nanoindenta-



Fig. 22.25a,b Bright-field and dark-field TEM of **(a)** small and **(b)** large nanoindentations in Si. In small nanoindents the metastable phase BC-8 is seen in the center, but for large nanoindents BC-8 is confined to the edge of the indent, while the center is amorphous



Fig. 22.26 Micro-Raman generally shows the BC-8 and R-8 Si phases that are at the edge of the nanoindents, but the amorphous phase in the center is not easy to detect, as it is often subsurface and the Raman peak is broad



Fig. 22.27 Nanoindentation curves for deep indents on Si show a discontinuity during unloading and simultaneously a large drop in contact resistance

tions in diamond cubic silicon have shown the presence of amorphous-Si and the body-centered cubic BC-8 phase (see Fig. 22.25). Micro-Raman spectroscopy has indicated the presence of a further phase, the rhombhedral R-8 (see Fig. 22.26). For many nanoindentations on silicon there is a characteristic discontinuity in the unloading curve (see Fig. 22.27), which seems to correlate with a phase transformation. The exact sequence in which the phases form is still highly controversial with some [22.42], suggesting that the sequence during loading and unloading is:

Increasing load →
Diamond cubic Si → β-Sn Si

← Decreasing load
BC-8 Si and R-8 Si ← β-Sn Si

Other groups [22.21,22] suggest that the above sequence is only valid for shallow nanoindentations that do not exhibit an unloading discontinuity. For large nanoindentations that show an unloading discontinuity, they suggest the sequence will be:

Increasing load →
Diamond cubic Si → β-Sn Si

← Decreasing load
α-Si ← BC-8 Si and R-8 Si ← β-Sn Si

The disagreement is over the origin of the unloading discontinuity. *Mann* et al. [22.21] suggest it is due to the formation of amorphous silicon, while *Gogotsi* et al. [22.42] believe it is the β-Sn Si to BC-8 or R-8 transformation. Mann et al. argue that the high contact resistance before the discontinuity and the low contact resistance afterwards rule out the discontinuity being the metallic β-Sn Si transforming to the more resistive BC-8 or R-8. The counterargument is that amorphous Si is only seen with micro-Raman spectroscopy when the unloading is very rapid or there is a large nanoindentation with no unloading discontinuity. The importance of unloading rate and cracking in determining the phases present are further complications. The controversy will remain until in situ characterization of the phases present is undertaken.

22.4 Thin Films and Multilayers

In almost all real applications, surfaces are coated with thin films. These may be intentionally added such as hard carbide coatings on a tool bit, or they may simply be native films such as an oxide layer. It is also likely that there will be adsorbed films of water and organic contaminants that can range from a single molecule in thickness up to several nanometers. All of these films, whether native or intentionally placed on the surface, will affect the surface's mechanical behavior on the nanoscale. Adsorbates can have a significant impact on the surface forces [22.3] and, hence, the geometry and stability of asperity contacts. Oxide films can have dramatically different mechanical properties to the bulk and will also modify the surface forces. Some of the effects of native films have been detailed in the earlier sections on dislocation nucleation and adhesive contacts.

The importance of thin films in enhancing the mechanical behavior of surfaces is illustrated by the abundance of publications on thin film mechanical properties (see for instance *Nix* [22.88] or *Cammarata* [22.31] or *Was* and *Foecke* [22.103]). In the following sections, the mechanical properties of films intentionally deposited on the surface will be discussed.

22.4.1 Thin Films

Measuring the mechanical properties of a single thin surface film has always been difficult. Any measurement performed on the whole sample will inevitably be dominated by the bulk substrate. Nanoindentation, since it looks at the mechanical properties of a very small region close to the surface, offers a possible solution to the problem of measuring thin film mechanical properties. However, there are certain inherent problems in using nanoindentation testing to examine the properties of thin films. The problems stem in part from the presence of an interface between the film and substrate. The quality of the interface can be affected by many variables, resulting in a range of effects on the apparent elastic and plastic properties of the film. In particular, when the deformation region around the indent approaches the interface, the indentation curve may exhibit features due to the thin film, the bulk, the interface, or a combination of all three. As a direct consequence of these complications, models for thin-film behavior must attempt to take into account not only the properties of the film and substrate, but also the interface between them.

If, initially, the effect of the interface is neglected, it is possible to divide thin-coated systems into a number of categories that depend on the values of E (elastic modulus) and Y (the yield stress) of the film and substrate. These categories are typically [22.104, 105]:

1. coatings with high E and high Y, substrates with high E and high Y;
2. coatings with high E and high Y, substrates with high or low E and low Y;
3. coatings with high or low E and low Y, substrates with high E and high Y;
4. coatings with high or low E and low Y, substrates with high or low E and low Y.

The reasons for splitting thin film systems into these different categories have been amply demonstrated experimentally by *Whitehead* and *Page* [22.104, 105] and theoretically by *Fabes* et al. [22.106]. Essentially, hard, elastic materials (high E and Y) will possess smaller plastic zones than soft, inelastic (low E and Y) materials. Thus, when different combinations of materials are used as film and substrate, the overall plastic zone will differ significantly. In some cases, the plasticity is confined to the film, and in other cases, it is in both the film and substrate, as shown by Fig. 22.28. If the standard nanoindentation analysis routines are to be used, it is essential that the plastic zone and the elastic strain field are



Fig. 22.28a–d Variations in the plastic zone for indents on films and substrates of different properties. **(a)** Film and substrate have high E and Y, **(b)** film has a high E and Y, substrate has a high or low E and low Y, **(c)** film has a high or low E and a low Y, and substrate has a high E and Y, **(d)** film has a high or low E and a low Y, and substrate has a high or low E and a low Y

both confined to the film and do not reach the substrate. Clearly, this is difficult to achieve unless extremely shallow nanoindentations are used. There is an often quoted 10% rule, that says nanoindents in a film must have a depth of less than 10% of the film's thickness if only the film properties are to be measured. This has no real validity [22.107]. There are film/substrate combinations for which 10% is very conservative, while for other combinations even 5% may be too deep. The effect of the substrate for different combinations of film and substrate properties has been studied using FEM [22.108], which has shown that the maximum nanoindentation depth to measure film only properties decreases in moving from soft on hard to hard on soft combinations. For a very soft film on a hard substrate, nanoindentations of 50% of the film thickness are alright, but this drops to $< 10\%$ for a hard film on a soft substrate. For a very strong film on a soft substrate, the surface film behaves like an elastic membrane or a bending plate.

Theoretical analysis of thin-film mechanical behavior is difficult. One theoretical approach that has been adopted uses the volumes of plastically deformed material in the film and substrate to predict the overall hardness of the system. However, it should be noted that this method is only really appropriate for soft coatings and indentation depths below the thickness of the coating (see cases c and d of Fig. 22.28), otherwise the behavior will be closer to that detailed later and shown by Fig. 22.29.

The technique of combining the mechanical properties of the film and substrate to evaluate the overall hardness of the system is generally referred to as the rule of mixtures. It stems from work by *Burnett* et al. [22.109–111] and *Sargent* [22.112], who derived a weighted average to relate the "composite" hardness (H) to the volumes of plastically deformed material in the film (V_f) and substrate (V_s) and their respective values of hardness, H_f and H_s. Thus,

$$H = \frac{H_\mathrm{f} V_\mathrm{f} + H_\mathrm{s} V_\mathrm{s}}{V_\mathrm{total}} \,, \tag{22.26}$$

where V_total is $V_\mathrm{f} + V_\mathrm{s}$.

Equation (22.26) was further developed by *Burnett* and *Page* [22.109] to take into account the indentation size effect. They replaced H_s with $K\delta_\mathrm{c}^{n-2}$, where K and n are experimentally determined constants dependent on the indenter and sample, and δ_c is the contact depth. This expression is derived directly from Meyer's law for spherical indentations, which gives the relationship $P = Kd^n$ between load, P, and the indentation dimension, d. Burnett and Page also employed a further refinement to enable the theory to fit experimental results from a specific sample, ion-implanted silicon. This particular modification essentially took into account the different sizes of the plastic zones in the two materials by multiplying H_s by a dimensionless factor ($V_\mathrm{s}/V_\mathrm{total}$). While this seems to be a sensible approach, it is mostly empirical, and the physical justification for using this particular factor is not entirely clear. Later, *Burnett* and *Rickerby* [22.110, 111] took this idea further and tried to generalize the equations to take into account all of the possible scenarios. Thus, the following equations were suggested:

$$H = \frac{H_\mathrm{f}\left(\Omega^3\right) V_\mathrm{f} + H_\mathrm{s} V_\mathrm{s}}{V_\mathrm{total}} \,, \tag{22.27}$$

$$H = \frac{H_\mathrm{f} V_\mathrm{f} + H_\mathrm{s}\left(\Omega^3\right) V_\mathrm{s}}{V_\mathrm{total}} \,. \tag{22.28}$$

The first of these, (22.27), deals with the case of a soft film on a hard substrate, and the second, (22.28), with a hard film on a soft substrate. The Ω term expresses the variation of the total plastic zone from the ideal hemispherical shape. This was taken still further by *Bull* and *Rickerby* [22.113], who derived an approximation for Ω based on the film and substrate zone radii being related to their respective hardness and elastic modulii [22.114, 115]. Hence:

$$\Omega = \left(E_\mathrm{f} H_\mathrm{s} / E_\mathrm{s} H_\mathrm{f}\right)^l \,, \tag{22.29}$$

where l is determined empirically. E_f and H_f and E_s and H_s are the elastic modulus and hardness of the film and substrate, respectively.

Experimental data [22.116] indicate that the effect of the substrate on the elastic modulus of the film can be quite different than the effect on hardness, due to



Fig. 22.29a,b Two different modes of deformation during nanoindentation of films. In **(a)** materials move upwards and outwards, while in **(b)** the film acts like a membrane and the substrate deforms

the zones of the elastic and plastic strain fields being different sizes.

Chechechin et al. [22.117] have recently studied the behavior of Al_2O_3 films of various thicknesses on different substrates. Their results indicate that many of the models correctly predict the transition between the properties of the film and those of the substrate, but do not always fit the observed hardness against depth curves. This group have also studied the pop-in behavior of Al_2O_3 films [22.118] and have attempted to model the range of loads and depths at which they occur via a Weibull-type distribution, as utilized in fracture analysis.

A point raised by Burnett and Rickerby should be emphasized. They state that there are two very distinct modes of deformation during nanoindentation testing. The first, referred to as *Tabor*'s [22.48] model for low Y/E materials, involves the buildup of material at the side of the indenter through movement of material at slip lines. The second, for materials with large Y/E does not result in surface pile-up. The displaced material is then accommodated by radial displacements [22.115]. The point is that a thin, strong, and well-bonded surface film can cause a substrate that would normally deform by Tabor's method to behave more like a material with high Y/E (see Fig. 22.29). It should be noted that this only applies as long as the film does not fail.

In recent theoretical and experimental studies the importance of material pile-up and sink-in has been investigated extensively. As discussed in an earlier section, pile-up can be increased by residual compressive stresses, but even in the absence of residual stresses pile-up can introduce a significant error in the calculated contact area. This is most pronounced in materials that do not work-harden [22.62]. For these materials using the Oliver and Pharr method fails to account for the pile-up and results in a large error in the values for E and H. For thin films *Tsui* et al. have used a focused ion beam to section through Knoop indentations in both soft films on hard substrates [22.69] and hard films on soft substrates [22.70]. The soft films, as expected, exhibit pile-up, while the hard film acts more like a membrane and the indentation exhibits sink-in with most of the plasticity in the substrate. Thus, there are three clearly identifiable factors affecting the pile-up and sink-in around nanoindents during testing of thin films:

1. Residual stresses
2. Degree of work-hardening
3. Ratio of film and substrate mechanical properties.

The bonding or adhesion between the film and substrate could also be added to this list. And it should not be forgotten that the depth of the nanoindentation relative to the film thickness also affects pile-up. For a very deep nanoindentation into a thin, soft film on a hard substrate pile-up is reduced, due to the combined constraints on the film of the tip and substrate [22.119]. Due to all of these complications, using nanoindentation to study thin film mechanical properties is fraught with danger. Many unprepared researchers have misguidedly taken the values of E and H obtained during nanoindentation testing to be absolute values only to find out later that the values contain significant errors.

Many of the problems associated with nanoindentation testing are related to incorrectly calculating the contact area, A. The *Joslin* and *Oliver* method [22.71] is one way that A can be removed from the calculations. This approach has been used with some success to look at strained epitaxial II/VI semiconductor films [22.120], but there is evidence that the lattice mismatch in these films can cause dramatic changes in the mechanical properties of the films [22.121]. This may be due to image forces and the film/substrate interface acting as a barrier to dislocation motion. Recently, it has been shown that using films and substrates with known matching elastic moduli, it is possible to use the assumption of constant elastic modulus with depth to evaluate H [22.122]. In effect, this is using (22.1) to evaluate A from the contact stiffness data, and then substituting the value for A into (22.12). The value of E is measured independently, for instance, using acoustic techniques.

22.4.2 Multilayers

Multilayered materials with individual layers that are a micron or less in thickness, sometimes referred to as superlattices, can exhibit substantial enhancements in hardness or strength. This should be distinguished from the super modulus effect discussed earlier, which has been shown to be largely an artifact. The enhancements in hardness can be as much as 100% when compared to the value expected from the rule of mixtures, which is essentially a weighted average of the hardness for the constituents of the two layers [22.123]. Table 22.1 shows how the properties of isostructural multilayers can show a substantial increase in hardness over that for fully interdiffused layers. The table also shows how there can be a substantial enhancement in hardness for non-isostructural multilayers compared to the values for the same materials when they are homogeneous.

Table 22.1 Results for some experimental studies of multilayer hardness

Study	Multilayer	Maximum hardness and multilayer repeat length	Reference hardness value	Range of hardness values for multilayers
Isostructural Knoop hardness [22.124]	Cu/Ni	524 at 11.6 nm	284 (interdiffused)	295–524
Non-isostructural Nanoindentation [22.125]	Mo/NbN	33 GPa at 2 nm	NbN – 17 GPa Mo – 2.7 GPa Wo – 7 GPa	12–33 GPa
	W/NbN	29 GPa at 3 nm	(individual layer materials)	23–29 GPa

There are many factors that contribute to enhanced hardness in multilayers. These can be summarized as [22.103]:

1. Hall-Petch behavior
2. Orowan strengthening
3. Image effects
4. Coherency and thermal stresses
5. Composition modulation

Hall-Petch behavior is related to dislocations piling-up at grain boundaries. (Note that pile-up is used to describe two distinct effects: One is material building up at the side of an indentation, the other is an accumulation of dislocations on a slip-plane.) The dislocation pile-up at grain boundaries impedes the motion of dislocations. For materials with a fine grain structure there are many grain boundaries, and, hence, dislocations find it hard to move. In polycrystalline multilayers, it is often the case that the size of the grains within a layer scales with the layer thickness so that reducing the layer thickness reduces the grain size. Thus, the Hall-Petch relationship (below) should be applicable to polycrystalline multilayer films with the grain size, d_g, replaced by the layer thickness.

$$Y = Y_0 + k_{HP}\, d_g^{-0.5} \,, \qquad (22.30)$$

where Y is the enhanced yield stress, Y_0 is the yield stress for a single crystal, and k_{HP} is a constant.

There is an ongoing argument about whether Hall-Petch behavior really takes place in nanostructured multilayers. The basic model assumes many dislocations are present in the pile-up, but such large dislocation pile-ups are not seen in small grains [22.126] and are unlikely to be present in multilayers. As a direct consequence, studies have found a range of values, between 0 and -1, for the exponent in (22.30), rather than the -0.5 predicted for Hall-Petch behavior.

Orowan strengthening is due to dislocations in layered materials being effectively pinned at the interfaces. As a result, the dislocations are forced to bow out along the layers. In narrow films, dislocations are pinned at both the top and bottom interfaces of a layer and bow out parallel to the plane of the interface [22.127, 128]. Forcing a dislocation to bow out in a layered material requires an increase in the applied shear stress beyond that required to bow out a dislocation in a homogeneous sample. This additional shear stress would be expected to increase as the film thickness is reduced.

Image effects were suggested by *Koehler* [22.129] as a possible source of enhanced yield stress in multilayered materials. If two metals, A and B, are used to make a laminate and one of them, A, has a high dislocation line energy, but the other, B, has a low dislocation line energy, then there will be an increased resistance to dislocation motion due to image forces. However, if the individual layers are thick enough that there may be a dislocation source present within the layer, then dislocations could pile-up at the interface. This will create a local stress concentration point and the enhancement to the strength will be very limited. If the layers are thin enough that there will be no dislocation source present, the enhanced mechanical strength may be substantial. In Koehler's model only nearest neighbor layers were taken to contribute to the image forces. However, this was extended to include more layers [22.130] without substantial changes in the results. The consequence on image effects of reducing the thickness of the individual layers in a multilayer is that it prevents dislocation sources from being active within the layer.

For many multilayer systems there is an increase in strength as the bilayer repeat length is reduced, but there is often a critical repeat length (e.g., 3 nm for the W/NbN multilayer of Table 22.1) below which the strength falls. One explanation for the fall in strength involves the effects of coherency and thermal stresses on dislocation energy. Unlike image effects where the energy of dislocations are a maximum or minimum in the center of layers, the energy maxima and minima are at the interfaces for coherency stresses. Combining the effects of varying moduli and coherency stresses shows that the dependence of strength on layer thickness has a peak near the repeat period where coherency strains begin decreasing [22.131].

Another source of deviations in behavior at very small repeat periods is the imperfect nature of interfaces. With the exception of atomically perfect epitaxial films, interfaces are generally not atomically flat and there is some interdiffusion. For the Cu/Ni film of Table 22.1, the effects of interdiffusion on hardness were examined [22.124] by annealing the multilayers. The results were in agreement with a model by *Krzanowski* [22.132] that predicted the variations in hardness would be proportional to the amplitude of the composition modulation.

It is interesting to note that the explanations for enhanced mechanical properties in multilayered materials are all based on dislocation mechanisms. So it would seem natural to assume that multilayered materials that do not contain dislocations will show no enhanced hardness over their rule of mixtures values. This has been verified by studies on amorphous metal multilayers [22.133], which shows that the hardness of the multilayers, firstly, lies between that of the two individual materials and, secondly, has almost no variation with repeat period.

22.5 Developing Areas

Over the past 20 to 30 years, the driving force for studying nanomechanical behavior of surfaces and thin films has been largely, though not exclusively, the microelectronics industry. The importance of electronics to the modern world is only likely to grow in the foreseeable future, but other technological areas may overtake microelectronics as the driving force for research, including the broad fields of biomaterials and nanotechnology. In several places in this chapter, a number of developing areas have been mentioned. These include nanoscale measurements of viscoelasticity and the study of environmental effects (temperature and surface chemistry) on nanomechanical properties. Both of these topics will be vital in the study of biological systems and, as a result, will be increasingly important from a research point of view.

We still have a relatively rudimentary understanding of the nanomechanics of complex biological systems such as bone cells (osteoblasts and osteoclasts) and skin cells (fibroblasts), or even, for that matter, simpler biological structures such as dental enamel. For example, Fig. 22.30 shows how the mechanical properties of dental enamel can vary within a single tooth [22.134]. But this is still a relatively large-scale measure of mechanical behavior. The prismatic structure of enamel means that there are variations in mechanical properties on a range of scales from millimeters down to nanometers.

In terms of data analysis, there remains much to be done. If an analysis method can be developed that deals with the problems of pile-up and sink-in, the utility of nanoindentation testing will be greatly enhanced.



Fig. 22.30 Variations in E and H across human dental enamel. The sample is an upper 2nd molar cut in cross section from the lingual to the buccal side. Nanoindentations are performed across the surface to examine how the mechanical properties vary

References

22.1 G. Binnig, C. F. Quate, C. Gerber: Atomic force microscope, Phys. Rev. Lett. **56** (1986) 930–933

22.2 P. J. Blau, B. R. Lawn (Eds.): *Microindentation Techniques in Materials Science and Engineering* (ASTM, Pennsylvannia 1986)

22.3 J. N. Israelachvili: *Intermolecular and Surface Forces* (Academic, London 1992)

22.4 R. S. Bradley: The cohesive force between solid surfaces and the surface energy of solids, Philos. Mag. **13** (1932) 853–862

22.5 B.V. Derjaguin, V.M. Muller, Yu.P. Toporov: Effect of contact deformations on the adhesion of particles, J. Coll. Interface Sci. **53** (1975) 314–326

22.6 V.M. Muller, V.S. Yuschenko, B.V. Derjaguin: On the influence of molecular forces on the deformation of an elastic sphere and its sticking to a rigid plane, J. Coll. Interface Sci. **77** (1980) 91–101

22.7 V. M. Muller, B. V. Derjaguin, Yu. P. Toporov: On two methods of calculation of the force of sticking of an elastic sphere to a rigid plane, Coll. Surf. **7** (1983) 251–259

22.8 K. L. Johnson, K. Kendal, A. D. Roberts: Surface energy and the contact of elastic solids, Proc. R. Soc. A **324** (1971) 301–320

22.9 A. P. Ternovskii, V. P. Alekhin, M. Kh. Shorshorov, M. M. Khrushchov, V. N. Skvortsov: Zavod Lab. **39** (1973) 1242

22.10 S. I. Bulychev, V. P. Alekhin, M. Kh. Shorshorov, A. P. Ternovskii, G. D. Shnyrev: Determining Young's modulus from the indentor penetration diagram, Zavod Lab. **41** (1975) 1137

22.11 S. I. Bulychev, V. P. Alekhin, M. Kh. Shorshorov, A. P. Ternovskii: Mechanical properties of materials studied from kinetic diagrams of load versus depth of impression during microimpression, Prob. Prochn. **9** (1976) 79

22.12 S. I. Bulychev, V. P. Alekhin: Zavod Lab. **53** (1987) 76

22.13 M. Kh. Shorshorov, S. I. Bulychev, V. P. Alekhin: Sov. Phys. Doklady **26** (1982) 769

22.14 J. B. Pethica: Microhardness tests with penetration depths less than ion implanted layer thickness. In: *Ion Implantation into Metals*, ed. by V. Ashworth, W. Grant, R. Procter (Pergamon, Oxford 1982) p. 147

22.15 D. Newey, M. A. Wilkens, H. M. Pollock: An ultralow-load penetration hardness tester, J. Phys. E: Sci. Instrum. **15** (1982) 119

22.16 D. Kendall, D. Tabor: An ultrasonic study of the area of contact between stationary and sliding surfaces, Proc. R. Soc. A **323** (1971) 321–340

22.17 G. M. Pharr, W. C. Oliver, F. R. Brotzen: On the generality of the relationship among contact stiffness, contact area and elastic-modulus during indentation, J. Mater. Res. **7** (1992) 613

22.18 T. P. Weihs, C. W. Lawrence, B. Derby, C. B. Scruby, J. B. Pethica: Acoustic emissions during indentation tests, MRS Symp. Proc. **239** (1992) 361–366

22.19 D. F. Bahr, J. W. Hoehn, N. R. Moody, W. W. Gerberich: Adhesion and acoustic emission analysis of failures in nitride films with 14 metal interlayer, Acta Mater. **45** (1997) 5163

22.20 D. F. Bahr, W. W. Gerberich: Relationships between acoustic emission signals and physical phemomena during indentation, J. Mat. Res. **13** (1998) 1065

22.21 A. B. Mann, D. van Heerden, J. B. Pethica, T. P. Weihs: Size-dependent phase transformations during point-loading of silicon, J. Mater. Res. **15** (2000) 1754

22.22 A. B. Mann, D. van Heerden, J. B. Pethica, P. Bowes, T. P. Weihs: Contact resistance and phase transformations during nanoindentation of silicon, Philos. Mag. A **82** (2002) 1921

22.23 S. Jeffery, C. J. Sofield, J. B. Pethica: The influence of mechanical stress on the dielectric breakdown field strength of SiO_2 films, Appl. Phys. Lett. **73** (1998) 172

22.24 B. N. Lucas, W. C. Oliver: Indentation power-law creep of high-purity indium, Metall. Trans. A **30** (1999) 601

22.25 S. A. Syed Asif: Time dependent micro deformation of materials. Ph.D. Thesis (Oxford Univ., Oxford 1997)

22.26 S. A. Syed Asif, R.J. Colton, K.J. Wahl: Nanoscale Surface Mechanical Property Measurements: Force Modulation Techniques Applied to Nanoindentation. In: *Interfacial Properties on the Submicron Scale*, ed. by J. Frommer, R. Overney (ACS Books, Whashington 2000)

22.27 A. B. Mann, J. B. Pethica: Nanoindentation studies in a liquid environment, Langmuir **12** (1996) 4583

22.28 J. W. Beams: Mechanical properties of thin films of gold and silver. In: *Structure and Properties of Thin Films*, ed. by C.A. Neugebauer, J. B. Newkirk, D. A. Vermilyea (Wiley, New York 1959) pp. 183–192

22.29 J. J. Vlassak, W. D. Nix: A new bulge test technique for the determination of Youngs modulus and Poissons ratio of thin-films, J. Mater. Res. **7** (1992) 3242

22.30 W. M. C. Yang, T. Tsakalakos, J. E. Hilliard: Enhanced elastic modulus in composition modulated gold-nickel and copper-palladium foils, J. Appl. Phys. **48** (1977) 876

22.31 R. C. Cammarata: Mechanical properties of nanocomposite thin-films, Thin Solid Films **240** (1994) 82

22.32 G. A. D. Briggs: *Acoustic Microscopy* (Clarendon, Oxford 1992)

22.33 J. Kushibiki, N. Chubachi: Material characterization by line-focus-beam acoustic microscope, IEEE Trans. Sonics Ultrasonics **32** (1985) 189–212

22.34 M.J. Bamber, K.E. Cooke, A.B. Mann, B. Derby: Accurate determination of Young's modulus and Poisson's ratio of thin films by a combination of acoustic microscopy and nanoindentation, Thin Solid Films **398** (2001) 299–305

22.35 S.E. Bobbin, R.C. Cammarata, J.W. Wagner: Determination of the flexural modulus of thin-films from measurement of the 1st arrival of the symmetrical Lamb wave, Appl. Phys. Lett. **59** (1991) 1544–1546

22.36 R.B. King, C.M. Fortunko: Determination of inplane residual-stress state in plates using horizontally polarized shear waves, J. Appl. Phys. **54** (1983) 3027–3035

22.37 R.F. Cook, G.M. Pharr: Direct observation and analysis of indentation cracking in glasses and ceramics, J. Am. Ceram. Soc. **73** (1990) 787–817

22.38 T.F. Page, W.C. Oliver, C.J. McHargue: The deformation-behavior of ceramic crystals subjected to very low load (nano)indentations, J. Mater. Res. **7** (1992) 450–473

22.39 G.M. Pharr, W.C. Oliver, D.S. Harding: New evidence for a pressure-induced phase-transformation during the indentation of silicon, J. Mater. Res. **6** (1991) 1129–1130

22.40 C.F. Robertson, M.C. Fivel: The study of submicron indent-induced plastic deformation, J. Mater. Res. **14** (1999) 2251–2258

22.41 J.E. Bradby, J.S. Williams, J. Wong-Leung, M.V. Swain, P. Munroe: Transmission electron microscopy observation of deformation microstructure under spherical indentation in silicon, Appl. Phys. Lett. **77** (2000) 3749–3751

22.42 Y.G. Gogotsi, V. Domnich, S.N. Dub, A. Kailer, K.G. Nickel: Cyclic nanoindentation and Raman microspectroscopy study of phase transformations in semiconductors, J. Mater. Res. **15** (2000) 871–879

22.43 H. Hertz: Über die Berührung fester elastischer Körper, J. reine angew. Math. **92** (1882) 156–171

22.44 J. Boussinesq: *Application des potentiels à l'étude de l'équilibre et du mouvement des solides élastiques* (Blanchard, Paris 1885) Reprint (1996)

22.45 A.E.H. Love: The stress produced in a semi-infinite solid by pressure on part of the boundary, Philos. Trans. R. Soc. **228** (1929) 377–420

22.46 A.E.H. Love: Boussinesq's problem for a rigid cone, Quarter. J. Math. **10** (1939) 161

22.47 I.N. Sneddon: The relationship between load and penetration in the axisymmetric Boussinesq problem for a punch of arbitrary profile, Int. J. Eng. Sci. **3** (1965) 47–57

22.48 D. Tabor: *Hardness of Metals* (Oxford Univ. Press, Oxford 1951)

22.49 R. von Mises: Mechanik der festen Körper in plastisch deformablen Zustand, Goettinger Nachr. Math.-Phys. **K1** (1913) 582–592

22.50 H. Tresca: Sur l'ecoulement des corps solids soumis s fortes pression, Compt. Rend. **59** (1864) 754

22.51 A.B. Mann, J.B. Pethica: The role of atomic-size asperities in the mechanical deformation of nanocontacts, Appl. Phys. Lett. **69** (1996) 907–909

22.52 A.B. Mann, J.B. Pethica: The effect of tip momentum on the contact stiffness and yielding during nanoindentation testing, Philos. Mag. A **79** (1999) 577–592

22.53 S.P. Jarvis: Atomic force microscopy and tip-surface interactions. Ph.D. Thesis (Oxford Univ., Oxford 1993)

22.54 J.B. Pethica, D. Tabor: Contact of characterised metal surfaces at very low loads: Deformation and adhesion, Surf. Sci. **89** (1979) 182

22.55 J.S. Field, M.V. Swain: Determining the mechanical-properties of small volumes of materials from submicrometer spherical indentations, J. Mater. Res. **10** (1995) 101–112

22.56 W.C. Oliver, G.M. Pharr: An improved technique for determining hardness and elastic-modulus using load and displacement sensing indentation experiments, J. Mater. Res. **7** (1992) 1564–1583

22.57 J.L. Loubet, J.M. Georges, O. Marchesini, G. Meille: Vickers indentation curves of magnesium oxide (MgO), Mech. Eng. **105** (1983) 91–92

22.58 J.L. Loubet, J.M. Georges, O. Marchesini, G. Meille: Vickers indentation curves of magnesium oxide (MgO), J. Tribol. Trans. ASME **106** (1984) 43–48

22.59 M.F. Doerner, W.D. Nix: A method for interpreting the data from depth sensing indentation experiments, J. Mater. Res. **1** (1986) 601–609

22.60 S.V. Hainsworth, H.W. Chandler, T.F. Page: Analysis of nanoindentation load-displacement loading curves, J. Mater. Res. **11** (1996) 1987–1995

22.61 A. Bolshakov, W.C. Oliver, G.M. Pharr: Influences of stress on the measurement of mechanical properties using nanoindentation. 2. Finite element simulations, J. Mater. Res. **11** (1996) 760–768

22.62 A. Bolshakov, G.M. Pharr: Influences of pileup on the measurement of mechanical properties by load and depth sensing instruments, J. Mater. Res. **13** (1998) 1049–1058

22.63 J.C. Hay, A. Bolshakov, G.M. Pharr: A critical examination of the fundamental relations used in the analysis of nanoindentation data, J. Mater. Res. **14** (1999) 2296–2305

22.64 G.M. Pharr, T.Y. Tsui, A. Bolshakov, W.C. Oliver: Effects of residual-stress on the measurement of hardness and elastic-modulus using nanoindentation, MRS Symp. Proc. **338** (1994) 127–134

22.65 T.R. Simes, S.G. Mellor, D.A. Hills: A note on the influence of residual-stress on measured hardness, J. Strain Anal. Eng. Des. **19** (1984) 135–137

22.66 W.R. Lafontaine, B. Yost, C.Y. Li: Effect of residual-stress and adhesion on the hardness of copper-films deposited on silicon, J. Mater. Res. **5** (1990) 776–783

22.67 W.R. Lafontaine, C.A. Paszkiet, M.A. Korhonen, C.Y. Li: Residual stress measurements of thin aluminum metallizations by continuous indentation and X-ray stress measurement techniques, J. Mater. Res. **6** (1991) 2084–2090

22.68 T. Y. Tsui, W. C. Oliver, G. M. Pharr: Influences of stress on the measurement of mechanical properties using nanoindentation. 1. Experimental studies in an aluminum alloy, J. Mater. Res. **11** (1996) 752–759

22.69 T. Y. Tsui, J. Vlassak, W. D. Nix: Indentation plastic displacement field: Part I. The case of soft films on hard substrates, J. Mater. Res. **14** (1999) 2196–2203

22.70 T. Y. Tsui, J. Vlassak, W. D. Nix: Indentation plastic displacement field: Part II. The case of hard films on soft substrates, J. Mater. Res. **14** (1999) 2204–2209

22.71 D. L. Joslin, W. C. Oliver: A new method for analyzing data from continuous depth-sensing microindentation tests, J. Mater. Res. **5** (1990) 123–126

22.72 M. R. McGurk, T. F. Page: Using the P-delta(2) analysis to deconvolute the nanoindentation response of hard-coated systems, J. Mater. Res. **14** (1999) 2283–2295

22.73 Y. T. Cheng, C. M. Cheng: Relationships between hardness, elastic modulus, and the work of indentation, Appl. Phys. Lett. **73** (1998) 614–616

22.74 J. B. Pethica, W. C. Oliver: Mechanical properties of nanometer volumes of material: Use of the elastic response of small area indentations, MRS Symp. Proc. **130** (1989) 13–23

22.75 W. C. Oliver, J. B. Pethica: Method for continuous determination of the elastic stiffness of contact between two bodies, United States Patent Number 4,848,141, (1989)

22.76 S. A. S. Asif, K. J. Wahl, R. J. Colton: Nanoindentation and contact stiffness measurement using force modulation with a capacitive load-displacement transducer, Rev. Sci. Instrum. **70** (1999) 2408–2413

22.77 J. L. Loubet, W. C. Oliver, B. N. Lucas: Measurement of the loss tangent of low-density polyethylene with a nanoindentation technique, J. Mater. Res. **15** (2000) 1195–1198

22.78 W. W. Gerberich, J. C. Nelson, E. T. Lilleodden, P. Anderson, J. T. Wyrobek: Indentation induced dislocation nucleation: The initial yield point, Acta Mater. **44** (1996) 3585–3598

22.79 J. D. Kiely, J. E. Houston: Nanomechanical properties of Au(111), (001), and (110) surfaces, Phys. Rev. B **57** (1998) 12588–12594

22.80 D. F. Bahr, D. E. Wilson, D. A. Crowson: Energy considerations regarding yield points during indentation, J. Mater. Res. **14** (1999) 2269–2275

22.81 D. E. Kramer, K. B. Yoder, W. W. Gerberich: Surface constrained plasticity: Oxide rupture and the yield point process, Philos. Mag. A **81** (2001) 2033–2058

22.82 S. G. Corcoran, R. J. Colton, E. T. Lilleodden, W. W. Gerberich: Anomalous plastic deformation at surfaces: Nanoindentation of gold single crystals, Phys. Rev. B **55** (1997) 16057–16060

22.83 E. B. Tadmor, R. Miller, R. Phillips, M. Ortiz: Nanoindentation and incipient plasticity, J. Mater. Res. **14** (1999) 2233–2250

22.84 J. A. Zimmerman, C. L. Kelchner, P. A. Klein, J. C. Hamilton, S. M. Foiles: Surface step effects on nanoindentation, Phys. Rev. Lett. **87** (2001) article 165507 (1–4)

22.85 J. D. Kiely, R. Q. Hwang, J. E. Houston: Effect of surface steps on the plastic threshold in nanoindentation, Phys. Rev. Lett. **81** (1998) 4424–4427

22.86 A. B. Mann, P. C. Searson, J. B. Pethica, T. P. Weihs: The relationship between near-surface mechanical properties, loading rate and surface chemistry, Mater. Res. Soc. Symp. Proc. **505** (1998) 307–318

22.87 R. C. Thomas, J. E. Houston, T. A. Michalske, R. M. Crooks: The mechanical response of gold substrates passivated by self-assembling monolayer films, Science **259** (1993) 1883–1885

22.88 W. D. Nix: Elastic and plastic properties of thin films on substrates: Nanoindentation techniques, Mater. Sci. Eng. A **234** (1997) 37–44

22.89 J. J. Vlassak, W. D. Nix: Indentation modulus of elastically anisotropic half-spaces, Philos. Mag. A **67** (1993) 1045–1056

22.90 J. J. Vlassak, W. D. Nix: Measuring the elastic properties of anisotropic materials by means of indentation experiments, J. Mech. Phys. Solids **42** (1994) 1223–1245

22.91 B. R. Lawn: *Fracture of Brittle Solids* (Cambridge Univ. Press, Cambridge 1993)

22.92 G. M. Pharr: Measurement of mechanical properties by ultra-low load indentation, Mater. Sci. Eng. A **253** (1998) 151–159

22.93 D. B. Marshall, A. G. Evans: Measurement of adherence of residually stressed thin-films by indentation. 1. Mechanics of interface delamination, J. Appl. Phys. **56** (1984) 2632–2638

22.94 C. Rossington, A. G. Evans, D. B. Marshall, B. T. Khuriyakub: Measurement of adherence of residually stressed thin-films by indentation. 2. Experiments with ZnO/Si, J. Appl. Phys. **56** (1984) 2639–2644

22.95 M. D. Kriese, W. W. Gerberich, N. R. Moody: Quantitative adhesion measures of multilayer films: Part I. Indentation mechanics, J. Mater. Res. **14** (1999) 3007–3018

22.96 M. D. Kriese, W. W. Gerberich, N. R. Moody: Quantitative adhesion measures of multilayer films: Part II. Indentation of W/Cu, W/W, Cr/W, J. Mater. Res. **14** (1999) 3019–3026

22.97 M. Li, C. B. Carter, M. A. Hillmyer, W. W. Gerberich: Adhesion of polymer-inorganic interfaces by nanoindentation, J. Mater. Res. **16** (2001) 3378–3388

22.98 D. R. Clarke, M. C. Kroll, P. D. Kirchner, R. F. Cook, B. J. Hockey: Amorphization and conductivity of

silicon and germanium induced by indentation, Phys. Rev. Lett. **60** (1988) 2156–2159
22.99 J. J. Gilman: Insulator-metal transitions at microindentation, J. Mater. Res. **7** (1992) 535–538
22.100 G. M. Pharr, W. C. Oliver, R. F. Cook, P. D. Kirchner, M. C. Kroll, T. R. Dinger, D. R. Clarke: Electrical-resistance of metallic contacts on silicon and germanium during indentation, J. Mater. Res. **7** (1992) 961–972
22.101 A. Kailer, Y. G. Gogotsi, K. G. Nickel: Phase transformations of silicon caused by contact loading, J. Appl. Phys. **81** (1997) 3057–3063
22.102 J. E. Bradby, J. S. Williams, J. Wong-Leung, M. V. Swain, P. Munroe: Mechanical deformation in silicon by micro-indentation, J. Mater. Res. **16** (2000) 1500–1507
22.103 G. S. Was, T. Foecke: Deformation and fracture in microlaminates, Thin Solid Films **286** (1996) 1–31
22.104 A. J. Whitehead, T. F. Page: Nanoindentation studies of thin-film coated systems, Thin Solid Films **220** (1992) 277–283
22.105 A. J. Whitehead, T. F. Page: Nanoindentation studies of thin-coated systems, NATO ASI Ser. E **233** (1993) 481–488
22.106 B. D. Fabes, W. C. Oliver, R. A. McKee, F. J. Walker: The determination of film hardness from the composite response of film and substrate to nanometer scale indentations, J. Mater. Res. **7** (1992) 3056–3064
22.107 T. F. Page, S. V. Hainsworth: Using nanoindentation techniques for the characterization of coated systems – a critique, Surface Coat. Technol. **61** (1993) 201–208
22.108 X. Chen, J. J. Vlassak: Numerical study on the measurement of thin film mechanical properties by means of nanoindentation, J. Mater. Res. **16** (2001) 2974–2982
22.109 P. J. Burnett, T. F. Page: Surface softening in silicon by ion-implantation, J. Mater. Sci. **19** (1984) 845–860
22.110 P. J. Burnett, D. S. Rickerby: The mechanical-properties of wear resistant coatings. 1. Modeling of hardness behavior, Thin Solid Films **148** (1987) 41–50
22.111 P. J. Burnett, D. S. Rickerby: The mechanical-properties of wear resistant coatings. 2. Experimental studies and interpretation of hardness, Thin Solid Films **148** (1987) 51–65
22.112 P. M. Sargent: A better way to present results from a least-squares fit to experimental-data – an example from microhardness testing, J. Test. Eval. **14** (1986) 122–127
22.113 S. J. Bull, D. S. Rickerby: Evaluation of coatings, Brit. Ceram. Trans. J. **88** (1989) 177–183
22.114 B. R. Lawn, A. G. Evans, D. B. Marshall: Elastic/plastic indentation damage in ceramics: The median/radial crack system, J. Am. Ceram. Soc. **63** (1980) 574–581
22.115 R. Hill: *The Mathematical Theory of Plasticity* (Clarendon, Oxford 1950)
22.116 W. C. Oliver, C. J. McHargue, S. J. Zinkle: Thin-film characterization using a mechanical-properties microprobe, Thin Solid Films **153** (1987) 185–196
22.117 N. G. Chechechin, J. Bottiger, J. P. Krog: Nanoindentation of amorphous aluminum oxide films. 1. Influence of the substrate on the plastic properties, Thin Solid Films **261** (1995) 219–227
22.118 N. G. Chechechin, J. Bottiger, J. P. Krog: Nanoindentation of amorphous aluminum oxide films. 2. Critical parameters for the breakthrough and a membrane effect in thin hard films on soft substrates, Thin Solid Films **261** (1995) 228–235
22.119 D. E. Kramer, A. A. Volinsky, N. R. Moody, W. W. Gerberich: Substrate effects on indentation plastic zone development in thin soft films, J. Mater. Res. **16** (2001) 3150–3157
22.120 A. B. Mann: Nanomechanical measurements: Surface and environmental effects. Ph.D. Thesis (Oxford Univ., Oxford 1995)
22.121 A. B. Mann, J. B. Pethica, W. D. Nix, S. Tomiya: Nanoindentation of epitaxial films: A study of pop-in events, Mater. Res. Soc. Symp. Proc. **356** (1995) 271–276
22.122 R. Saha, W. D. Nix: Effects of the substrate on the determination of thin film mechanical properties by nanoindentation, Acta Mater. **50** (2002) 23–38
22.123 S. A. Barnett: Deposition and mechanical properties of superlattice thin films. In: *Physics of Thin Films*, ed. by M. H. Francombe, J. L. Vossen (Academic, New York 1993)
22.124 R. R. Oberle, R. C. Cammarata: Dependence of hardness on modulation amplitude in electrodeposited Cu-Ni compositionally modulated thin-films, Scripta Metall. **32** (1995) 583–588
22.125 A. Madan, Y. Y. Wang, S. A. Barnett, C. Engstrom, H. Ljungcrantz, L. Hultman, M. Grimsditch: Enhanced mechanical hardness in epitaxial nonisostructural Mo/NbN and W/NbN superlattices, J. Appl. Phys. **84** (1998) 776–785
22.126 R. Venkatraman, J. C. Bravman: Separation of film thickness and grain-boundary strengthening effects in Al thin-films on Si, J. Mater. Res. **7** (1992) 2040–2048
22.127 J. D. Embury, J. P. Hirth: On dislocation storage and the mechanical response of fine-scale microstructures, Acta Mater. **42** (1994) 2051–2056
22.128 D. J. Srolovitz, S. M. Yalisove, J. C. Bilello: Design of multiscalar metallic multilayer composites for high-strength, high toughness, and low CTE

mismatch, Metall. Trans. A **26** (1995) 1805–1813

22.129 J. S. Koehler: Attempt to design a strong solid, Phys. Rev. B **2** (1970) 547–551

22.130 S. V. Kamat, J. P. Hirth, B. Carnahan: Image forces on screw dislocations in multilayer structures, Scripta Metall. **21** (1987) 1587–1592

22.131 M. Shinn, L. Hultman, S. A. Barnett: Growth, structure, and microhardness of epitaxial TiN/NbN superlattices, J. Mater. Res. **7** (1992) 901–911

22.132 J. E. Krzanowski: The effect of composition profile on the strength of metallic multilayer structures, Scripta Metall. **25** (1991) 1465–1470

22.133 J. B. Vella, R. C. Cammarata, T. P. Weihs, C. L. Chien, A. B. Mann, H. Kung: Nanoindentation study of amorphous metal multilayered thin films, MRS Symp. Proc. **594** (2000) 25–29

22.134 J. L. Cuy, A. B. Mann, K. J. Livi, M. F. Teaford, T. P. Weihs: Nanoindentation mapping of the mechanical properties of human molar tooth enamel, Arch. Oral Biol. **47** (2002) 281–291

23. Atomistic Computer Simulations of Nanotribology

Atomistic Com

Molecular dynamics (MD) and related simulation techniques are powerful tools for improving our understanding of nanotribology. In simulations, materials properties and boundary conditions can be varied at will, and the resulting changes in both macroscopic variables and the dynamics of individual atoms can be observed. This allows one to study systematically the effects of many different factors on friction and wear at the nano-scale. Some examples that are considered in this chapter are (i) the symmetry of contacting surfaces (disordered vs. crystalline and with or without common periods), (ii) surface elasticity, (iii) surface curvature or topology, (iv) interfacial adhesion, and (v) lubricant and/or contaminant molecules present at the interface. Results from simulations and experiments on isolated nano-scale contacts often contradict our experience from macroscopic systems. Kinetic friction coefficients can be orders of magnitude smaller than those observed in macroscopic experiments. Detailed calculations even suggest that there should be no static friction between most pairs of clean, chemically passivated surfaces unless the load is large enough to produce wear. Simulations that test a series of possible mechanisms for static friction are described. Geometrical interlocking can produce static friction in contacts containing only a few atoms, such as an atomic force microscope tip. Larger contacts only exhibit static friction when there is wear, or when the surfaces are separated by a glassy contaminant layer that locks them together. Most surfaces are coated by such films and they are shown to yield friction forces that agree with both nanoscale and macroscopic experiments.

23.1 **Molecular Dynamics** 718
23.1.1 Model Potentials 719
23.1.2 Maintaining Constant Temperature. 720
23.1.3 Imposing Load and Shear............. 721
23.1.4 The Time-Scale and Length-Scale Gaps 721
23.1.5 A Summary of Possible Traps......... 722

23.2 **Friction Mechanisms at the Atomic Scale**. 723
23.2.1 Geometric Interlocking 723
23.2.2 Elastic Instabilities 724
23.2.3 Role of Dimensionality and Disorder 727
23.2.4 Elastic Instabilities vs. Wear in Atomistic Models 727
23.2.5 Hydrodynamic Lubrication and Its Confinement-Induced Breakdown . 729
23.2.6 Submonolayer Films 731

23.3 **Stick-Slip Dynamics** 732

23.4 **Conclusions**... 734

References 735

One of the main barriers to the design of nanodevices with moving parts is our limited understanding of nanotribology; friction, lubrication and wear at the nanometer scale. New experimental methods such as the atomic force microscope (AFM) [23.1,2], quartz-crystal microbalance (QCM) [23.3], and surface forces apparatus (SFA) [23.4, 5] have revolutionalized our ability to measure friction in systems with atomic scale dimensions. However, the results are often qualitatively different than in macroscopic systems. For example, solids may slide more easily than fluids [23.3, 6] and fluids may behave like solids [23.4, 7]. These results have also revealed that there are gaps in our understanding of the molecular underpinnings of macroscopic tribology. There is a growing recognition that the behavior of nanometer-thick interfacial layers is crucial to tribology in systems of all scales, which has led to a fruitful convergence of researchers from many disciplines.

Understanding friction is an interesting and challenging scientific task, owing to the many factors that come into play: elastic and plastic properties of the two solids in relative sliding motion, surface roughness in multi-asperity contacts and tip geometry in single asperity contacts, geometric correlation between the solids in a microcontact, the amount of lubricant between the two solids, the physical nature of the lubricants, chemical

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

properties and reactions, adhesion, thermal fluctuations and aging, heat conductivity, etc.

Computer simulations have played an increasingly important role in improving our understanding of tribological phenomena. Unlike experiments, they allow us to perfectly control the geometry, the chemical composition, the sliding conditions, etc. and thus make it possible to explore the effect of each variable on friction, lubrication, and wear. Moreover, theorists have no other general approach to analyze processes like friction and wear. There is no known principle like minimization of free energy that determines the steady state of nonequilibrium systems. Even if there were, simulations would be needed to address the complex systems of interest, just as in many equilibrium problems.

Two different types of friction are commonly defined. Static friction, F_s, is the lateral force that must be applied to initiate sliding of one object over another, while kinetic friction, F_k, is the lateral force that must be applied to maintain sliding. At the macroscopic scale both forces usually obey Amontons's laws, which state that friction is proportional to the load pushing the surfaces together and is independent of area. However, there are obvious exceptions, such as tape, where friction occurs at zero load.

Despite significant experimental, theoretical, and computational efforts, no consensus has yet been reached on the relevant atomistic origins of friction between two solid bodies. Strictly speaking, static friction is not a force but a threshold. Its presence implies that the objects have locked together into a local energy minimum that must be overcome by the external force. This threshold force is observed between all the objects around us, yet its molecular origins have remained baffling. How does almost every pair of surfaces manage to lock together, and why does the friction usually obey Amontons's laws? Why does F_k not vanish linearly at small sliding velocities as it would if sliding occurred adiabatically? Different mechanisms have been suggested, such as geometric interlocking, elastic instabilities, interlocking mediated by so-called third bodies, plastic deformation, and crack propagation, to name a few. All these mechanisms may well be applicable, although each one under different circumstances.

In the following, we present a selected overview of the major results from the growing simulation literature. The emphasis is on providing a coherent picture of the key issues in the field, rather than a historical or a complete review. A much more detailed review of tribological computer simulations, including the sliding of adsorbed layers on surfaces, stick-slip motion, tribochemistry, cutting, high-velocity friction between metals, etc. has been given recently by *Robbins* et al. [23.8], and a review of the theoretical foundations of nanotribological issues is given in *Müser* et al. [23.9]. Reviews emphasizing the importance of surface chemistry and the role of self-assembled monolayers have been provided by *Harrison* et al. [23.10, 11].

23.1 Molecular Dynamics

The simulations described in this chapter all use an approach called classical molecular dynamics (MD), which is described extensively in a number of review articles and books [23.12, 13]. The basic outline of the method is straightforward. One begins by defining the interaction potentials. These produce forces on the individual particles whose dynamics will be followed, typically atoms or molecules. Next, the geometry and boundary conditions are specified, and initial coordinates and velocities are given to each particle. Then, the equations of motion for the particles are integrated numerically, stepping forward in time by discrete steps of size Δt. Quantities such as forces, velocities, work, heat flow, and correlation functions are calculated as a function of time to determine their steady-state values and dynamic fluctuations. The relation between changes in these quantities and the motion of individual molecules is also explored.

When designing a simulation, care must be taken to choose interaction potentials and ensembles that capture the essential physics that is to be addressed. The potentials may be as simple as ideal spring constants for studies of general phenomena, or as complex as electronic density-functional calculations in quantitative simulations. The ensemble can also be tailored to the problem of interest. Solving Newton's equations yields a constant energy and volume, or microcanonical, ensemble. By adding terms in the equation of motion that simulate heat baths or pistons, simulations can be done at constant temperature, pressure, lateral force, or velocity. Constant chemical potential can also be maintained by adding or removing particles using Monte Carlo methods or explicit particle baths.

The amount of computational effort typically grows linearly with both the number of particles, N, and the number of time-steps, M. The prefactor increases rapidly with the complexity of the interactions, and substantial ingenuity is required to achieve linear scaling with N for long-range interactions or density-functional approaches. Complex interactions also lead to a wide range of characteristic frequencies such as fast bond-stretching and slow bond-bending modes. Unfortunately, the time step Δt must be small compared to the period of the slowest mode ($\lessapprox 5\%$). This means that many time steps are needed before one obtains information about the slow modes.

The maximum feasible simulation size has increased continuously with advances in computer technology, but remains relatively limited. The product of N times M in the largest simulations described below is about 10^{12}. A cubic region of 10^6 atoms would have a side of about 50 nm. Such linear dimensions allow reasonable models of an atomic force microscope tip, the boundary lubricant in a surface force apparatus, or an individual asperity contact on a rough surface. However, 10^6 time steps is only about 10 ns, which is much shorter than experimental measurement times. This requires intelligent choices in the problems that are attacked and how results are extrapolated to experiments. It also limits sliding velocities to relatively high values, typically meters per second or above.

A number of efforts are underway to increase the accessible time scale, but the problem remains unsolved. Current algorithms attempt to follow the deterministic equations of motion, usually with the Verlet or predictor-corrector algorithms [23.12]. One alternative approach is to make stochastic steps. This would be a nonequilibrium generalization of the Monte Carlo approach that is commonly used in equilibrium systems. The difficulty is that there is no general principle for determining the appropriate probability distribution of steps in a nonequilibrium system.

In the following subsection, we describe some of the potentials that are commonly used and the situations where they are appropriate. The next two subsections describe methods for maintaining constant temperature and constant load. The section concludes with discussions of the challenges associated with the wide range of relevant time and length scales, and common pitfalls in simulations.

23.1.1 Model Potentials

A wide range of potentials has been employed in studies of tribology. Many of the studies described in the next section use simple ideal springs and sine-wave potentials. The Lennard-Jones potential gives a more realistic representation of typical interatomic interactions and is also commonly used in studies of general behavior. In order to model specific materials, more detail must be built into the potential. Simulations of metals frequently use the embedded atom method, while studies of hydrocarbons use potentials that include bond-stretching, bending, torsional forces, and even chemical reactivity. In this section, we give a brief definition of the most commonly used models. The reader may consult the original literature for more detail.

The Lennard-Jones (LJ) potential is a two-body potential that is commonly used for interactions between atoms or molecules with closed electron shells. It is applied not only to the interaction between noble gases, but also to the interaction between different segments on polymers. In the latter case, one LJ particle may reflect a single atom on the chain (explicit atom model), a CH_2 segment (united atom model), or even a Kuhn's segment consisting of several CH_2 units (coarse-grained model). United atom models [23.14] have been shown by *Paul* et al. [23.15] to successfully reproduce explicit atom results for polymer melts. Significant progress has been made recently to map back from the coarse-grained models to more detailed models [23.16, 17].

The 12-6 LJ potential has the form

$$U(r_{ij}) = 4\epsilon \left[\left(\frac{\sigma}{r_{ij}} \right)^{12} - \left(\frac{\sigma}{r_{ij}} \right)^{6} \right] , \tag{23.1}$$

where r_{ij} is the distance between particles i and j, ϵ is the LJ interaction energy, and σ is the LJ diameter. The exponents 12 and 6 used above are very common, but other values may be chosen depending on the system of interest. Many of the simulation results discussed in subsequent sections are expressed in units derived from ϵ, σ, and a characteristic mass of the particles. For example, the standard LJ time unit is defined as $t_{\text{LJ}} = \sqrt{m\sigma^2/\epsilon}$ and would typically correspond to a few picoseconds. A convenient time step is $\Delta t = 0.005 t_{\text{LJ}}$ for a LJ liquid or solid at external pressures and temperatures that are not too large.

Most realistic atomic potentials cannot be expressed as two-body potentials. For example, bond angle potentials in a polymer are effectively three-body interactions and torsional potentials correspond to four-body interactions. Classical models of these interactions [23.18, 19] assume that a polymer is chemically inert and interactions between different molecules are modeled by two-body potentials. In the most sophisticated models, bond-stretching, bending, and torsional energies depend on the position of neighboring molecules and bonds are allowed to rearrange [23.20, 21]. Such generalized model potentials are needed to model friction-induced chemical interactions.

For the interaction between metals, a different approach has proven fruitful. The embedded atom method (EAM) developed by *Daw* et al. [23.22] includes a contribution in the potential energy associated with the cost of "embedding" an atom in the local electron density ρ_i produced by surrounding atoms. The total potential energy U is approximated by

$$U = \sum_i \tilde{F}_i(\rho_i) + \sum_i \sum_{j<i} \phi_{ij}(r_{ij}) \, , \tag{23.2}$$

where $\tilde{F}_i$ is the embedding energy, whose functional form depends on the particular metal. The pair potential $\phi_{ij}(r_{ij})$ is a doubly screened short-range potential reflecting core-core repulsion. The computational cost of the EAM is not substantially greater than pair potential calculations, because the density ρ_i is approximated by a sum of independent atomic densities. When compared to simple two-body potentials such as Lennard–Jones or Morse potentials, the EAM has been particularly successful in reproducing experimental vacancy formation energies and surface energies, even though the potential parameters were only adjusted to reproduce bulk properties. This feature makes the EAM an important tool in tribological applications, where surfaces and defects play a major role.

23.1.2 Maintaining Constant Temperature

An important issue for tribological simulations is temperature regulation. The work done when two walls slide past each other is ultimately converted into random thermal motion. The temperature of the system would increase indefinitely if there was no way for this heat to flow out of the system. In an experiment, heat flows away from the sliding interface into the surrounding solid. In simulations, the effect of the surrounding solid must be mimicked by coupling the particles to a heat bath.

Techniques for maintaining constant temperature T in equilibrium systems are well developed. Equipartition guarantees that the average kinetic energy of each particle along each Cartesian coordinate is $k_\mathrm{B}T/2$, where k_B is Boltzmann's constant. To thermostat the system, the equations of motion are modified, so that the average kinetic energy stays at this equilibrium value. This approach assumes that T is not too small compared to the Debye temperature, so that quantum statistics are not important. The applicability of classical MD decreases at lower T.

One class of approaches removes or adds kinetic energy to the system by multiplying the velocities of all particles by the same global factor. In the simplest version, velocity rescaling, the factor is chosen to keep the kinetic energy exactly constant at each time step. However, in a true constant temperature ensemble there are fluctuations in the kinetic energy. Improvements such as the Berendsen and Nosé–Hoover methods [23.23] add equations of motion that gradually scale the velocities to maintain the correct average kinetic energy over a longer time scale.

Another approach is to couple each atom to its own local thermostat [23.24, 25]. The exchange of energy with the outside world is modeled by a Langevin equation that includes a damping coefficient γ and a random force $f_i(t)$ on each atom i. The equations of motion for the α component of the position $x_{i\alpha}$ become:

$$m_i \frac{\mathrm{d}^2 x_{i\alpha}}{\mathrm{d}t^2} = -\frac{\partial}{\partial x_{i\alpha}} U - m_i \gamma \frac{\mathrm{d}x_{i\alpha}}{\mathrm{d}t} + f_{i\alpha}(t) \, , \tag{23.3}$$

where U is the total potential energy and m_i is the mass of the atom. To produce the appropriate temperature, the forces must be completely random, have zero mean, and have a second moment given by

$$\langle \delta f_{i\alpha}(t)^2 \rangle = 2 k_\mathrm{B} T m_i \gamma / \Delta t \, . \tag{23.4}$$

The damping coefficient γ must be large enough that energy can be removed from the atoms without substantial temperature increases. However, it should be small enough that the trajectories of individual particles are not perturbed too strongly.

The first issue in nonequilibrium simulations is what temperature means. Near equilibrium hydrodynamic theories define a local temperature in terms of the equilibrium equipartition formula and the kinetic energy relative to the local rest frame [23.26]. In d dimensions, the definition is

$$k_\mathrm{B} T = \frac{1}{dN} \sum_i m_i \left[\frac{\mathrm{d}\boldsymbol{x}_i}{\mathrm{d}t} - \langle \boldsymbol{v}(\boldsymbol{x}) \rangle \right]^2 \, , \tag{23.5}$$

where the sum is over all N particles and $\langle \boldsymbol{v}(\boldsymbol{x}) \rangle$ is the mean velocity in a region around $\boldsymbol{x}$. As long as the change in mean velocity with position is sufficiently slow, $\langle \boldsymbol{v}(\boldsymbol{x}) \rangle$ is well-defined and this definition of temperature is on solid theoretical ground.

When the mean velocity difference between neighboring molecules becomes comparable to the random thermal velocities, temperature is not well-defined. An important consequence is that different strategies for defining and controlling temperature give very different structural order and shear forces [23.27–29]. In addition, the distribution of velocities may become non-Gaussian, and different directions, α, may have different effective temperatures. Care should be taken in drawing conclusions from simulations in this extreme regime. Fortunately, the above condition typically implies that the velocities of neighboring atoms differ by something approaching 10% of the speed of sound. This is generally higher than any experimental velocity and would certainly lead to heat buildup and melting at the interface.

In order to mimic experiments, the thermostat is often applied only to those atoms that are at the outer boundary of the simulation cell. This models the flow of heat into surrounding material that is not included explicitly in the simulation. The resulting temperature profile is peaked at the shearing interface (e.g., *Bowden* et al. [23.30], *Khare* et al. [23.31]). In some cases the temperature rise may lead to undesirable changes in the structure and dynamics, even at the lowest velocity, that can be treated in the available simulation time. In this case, a weak thermostat applied throughout the system may maintain the correct temperature and yield the dynamics that would be observed in longer simulations at lower velocities. The safest course is to couple the thermostat only to those velocity components that are perpendicular to the mean flow.

There may be a marginal advantage to local Langevin methods in nonequilibrium simulations, because they remove heat only from atoms that are too hot. Global methods like Nosé–Hoover remove heat everywhere. This can leave high temperatures in the region where heat is generated, while other regions are at an artificially low temperature.

23.1.3 Imposing Load and Shear

The magnitude of the friction that is measured in an experiment or simulation may be strongly influenced by the way in which the normal load and tangential motion are imposed [23.32]. Experiments almost always impose a constant normal load. The mechanical system applying shear can usually be described as a spring attached to a stage moving at controlled velocity. The effective spring constant includes the compliance of all elements of the loading device, including the material on either side of the interface. Very compliant springs apply a nearly constant force, while very stiff springs apply a nearly constant velocity.

In simulations, it is easiest to treat the boundary of the system as rigid and to translate atoms in this region at a constant height and tangential velocity. However, this does not allow atoms to move around or up and over atoms on the opposing surface. Even the atomic-scale roughness of a crystalline surface can lead to order of magnitude variations in normal and tangential force with lateral position when sliding is imposed in this way [23.33]. The difference between constant separation and pressure simulations of thin films can be arbitrarily large, since they produce different power law relations between viscosity and sliding velocity [23.34].

One way of minimizing the difference between constant separation and pressure ensembles is to include a large portion of the elastic solids that bound the interface. This extra compliance allows the surfaces to slide at a more uniform normal and lateral force. However, the extra atoms greatly increase the computational effort.

To simulate the usual experimental ensemble more directly, one can add equations of motion that describe the position of the boundary [23.34–36], much as equations are added to maintain constant temperature. The boundary is given an effective mass that moves in response to the net force from interactions with mobile atoms and from the external pressure and lateral spring. The mass of the wall should be large enough that its dynamics are slower than those of individual atoms, but not too much slower or the response time will be long compared to the simulation time. The spring constant should also be chosen to produce an appropriate response time and ensemble.

23.1.4 The Time-Scale and Length-Scale Gaps

One important motivation of tribological computer simulations is to find the relevant atomistic processes that occur in a single, well-defined sliding contact such as in the SFA or in the AFM. While it has become computationally feasible to study atomistically the core of a nanometer-scale AFM contact, the sliding speeds, v_{sl}, employed in the simulations are still about ten decades larger than in experiments. The use of clever new algorithms such as kinetic Monte Carlo might prove fruitful to overcome this time-scale gap in a brute-force way. However, such an approach is not necessarily required in order to make a meaningful comparison between experiment and simulation. Instead, one can try to find out what the relevant time scales are and what parameters define them, e.g., by studying a phenomenological description of an embedded system under shear. In such an analysis, *Porto* et al. [23.37] found that the motion of the top plate/tip is not sensitive to the characteristic atomic frequencies ω_{mic} – as long as there is a reasonable time-scale separation between ω_{mic} and the characteristic frequency of the tip Ω_{tip}. The experimentally relevant time scale Ω_{tip} is given by $\sqrt{K/M}$, where K is a restoring spring constant (defined by the tip's elasticity and/or the tip-substrate interactions) and M is the tip's inertia, eventually including the cantilever's mass. The experimental value of M will be about 20 decades larger than in the simulation, so values of the relevant parameter $v_{\text{sl}}\Omega_{\text{tip}}$ end up being similar in simulation and experiment. However, there is controvery over whether the tip can be treated as a mass point, or whether long-range elastic deformations in the tip are important [23.35], [23.38, Chap. 9.9].

Another way to overcome the gap in time scales is to alter interaction strengths, temperature, or other variables in order to accelerate the processes of interest. One such example is the cold welding study of *Müser* [23.40], where two dissimilar solids were placed on top of each other in vacuum. It would have been by no means desirable to base the calculations on interfacial interactions that correspond to typical experimental values, because the resulting time scales would be too long. By increasing the magnitude of the mixing energy, one drives the mixing process toward the same ground state on simulation time scales. This simple trick makes it possible to indirectly bridge several orders of magnitude in time scale between experiment and simulation.

Some open issues appear to require the explicit treatment of many different length scales. For example, the distribution of contacts and total contact area depend on both atomic-scale interactions at the surface and long-range elastic deformation of the bounding solid. Of particular interest is whether different contacting asperities can move independently, or whether those within an elastic coherence length l_e move in lock-step. Estimates of l_e range from the size of a single asperity [23.41] to many times the linear dimension of most objects of interest [23.42]. The correct value is of great importance to the question of whether clean, corrugated (macroscopic) surfaces have the potential to show elastic pinning and, hence, wearless friction. In order to address such issues, it will be necessary to do simulations that incorporate both atomistic and finite element methods (e.g., *Abraham* et al. [23.43]).

23.1.5 A Summary of Possible Traps

There are many possible traps that may render a well-done simulation useless or applicable only to highly idealized situations. In some aspects more care has to be taken than in equilibrium simulations, in other aspects one gets away with less care. We hope that this section helps to create some sensitivity as to what "ingredients" are relevant. For example, if we calculate the static friction force between two solids separated by a boundary lubricant in a MD simulation, the results will be fairly insensitive to the thermostat and to whether or not the thermostat is applied to the boundary lubricant. One should also avoid moves in which a "stuck" atom magically disappears from the contact through a grand canonical-type Monte Carlo move. The results depend more strongly on the thermostat if the lubricant is thick and the heating effects are of interest. In such a case, only the outermost atoms in the confining solids should be thermostated.

The typical situation in experiment is constant load, *not* constant separation. In some cases, there is something like a correspondence between these two "ensembles", but often there are *qualitative* differences between them, in particular, when strongly irreversible processes take place such as the production of wear particles [23.40]. Contacting experimental surfaces are also likely to have different geometry and chemistry – or at least different crystallographic orientations. However, most simulations consider the artificial case of contact



Fig. 23.1 Kinetic friction force F_k divided by load L as a function of spring constant k for commensurate and incommensurate walls lubricated by a quarter monolayer of LJ atoms. A schematic of the simulation is shown as well. The data shown was produced at a normal pressure of 0.4 GPa and a velocity of about 1 m/s. (After [23.39])

between identical, aligned crystals. This is the simplest example of a commensurate system, where the two surfaces share a common spatial period. As discussed below, the tribological behavior of commensurate systems is dramatically different than the more realistic case of incommensurate surfaces – even in the presence of a few layers of lubricant. One example of this is shown in Fig. 23.1 [23.39].

Another issue is the curvature of the surfaces. Real contacts typically take place between two curved surfaces or a curved and a flat surface. The pressure profiles differ from those in "flat" contacts, and that discrepancy can be relevant in certain circumstances. If we want to incorporate curvature effects, care should be taken that the resulting pressure profiles resemble a realistic profile, as was done by *Wenning* et al. [23.44].

23.2 Friction Mechanisms at the Atomic Scale

As noted in the introduction, static friction implies that the contacting surfaces have locked into a local free energy minimum. There have been many suggestions for how this can happen between nearly every pair of surfaces, whether macroscopic or nanoscale. The purpose of this section is to review some of these mechanisms and discuss their relevance to nanotribological experiments.

One obvious way that surfaces can interlock is through plastic deformation that brings the surfaces into conformity. A classic example is called plowing friction [23.30]. In this case a sharp feature on one surface penetrates into the opposing surface, causing permanent plastic deformation. The static friction represents the force needed to plow a groove through the surface. This type of motion has been observed in simulations [23.8, 9, 45]. and experiments (Sect. 20.6.1) using AFM probes with hard tips Because it leads to rapid wear, it is only desirable when one wants to remove material by abrasion or cutting.

Many nanotribological studies show friction without measurable wear, and this is the desirable mode of operation in most applications. For this reason, the following subsections focus on mechanisms that lock surfaces together without plastic deformation. We begin by discussing contact between rigid surfaces (Sect. 23.2.1), and then explore the ability of elastic deformations at the atomic scale (Sect. 23.2.2) or between contacts (Sect. 23.2.3) to lock surfaces together. We then describe one of the simulations that shows how unlikely these mechanisms are to yield static friction without wear unless the contact contains only a few tens of atoms (Sect. 23.2.4). The final two subsections consider the role of contaminants or "third bodies" that are present in the contacts between nearly all surfaces. First, changes in the behavior of lubricants with film thickness are discussed. Then molecularly thin films are shown to produce static and kinetic friction that is consistent with both nanoscale experiments and macroscopic observations.

23.2.1 Geometric Interlocking

Early theories of friction were based on the purely geometric argument that friction is caused by the interlocking of impenetrable and rigid surface asperities [23.30, 46]. The idea (Fig. 23.2) is that the top solid must be lifted up a typical slope, $\tan\alpha$, determined by roughness on the bottom surface. If there is no microscopic friction between the surfaces, then the minimum force to initiate sliding is

$$F_s = \mu_s L \tag{23.6}$$

with $\mu_s = \tan\alpha$. This result satisfies Amontons's laws with a constant coefficient of friction $\mu_s \equiv F_s/L = \tan\alpha$. In 1737, Bélidor obtained a typical experimental value of $\mu_s \approx 0.35$ by modeling rough surfaces as spherical asperities arranged to form commensurate crystalline walls [23.46]. However, asperities on real surfaces do not match as well as envisioned in these models or as sketched in Fig. 23.2. In most cases the average force vanishes because for every asperity or atom going up a ramp, there is another going down.

The sum of forces between crystalline surfaces is considered explicitly in the next subsection, and shown



Fig. 23.2 Sketch of two surfaces with interlocking asperities. The top surface experiences a normal load L and a lateral force F, which attempts to pull the top surface up the slope $\tan\alpha$. The bottom wall is fixed

to vanish except in the unusual case where the surfaces have the same periodicity. In the case were one or both surfaces are random, simple analytic arguments show that μ_s will fall as $\mathcal{L}^{-d_{\text{int}}/2}$ when the linear size $\mathcal{L}$ of the contact goes to infinity [23.47], provided that the surface roughnesses are small and the solids are completely rigid. Here, d_{int} is the dimension of the contact and the pressure normal to the interface is assumed to be kept constant. This result is in contradiction with one of Amontons's laws, namely, the independence of F_s on the area of contact A. Nevertheless, the linear relation between F_s and L at fixed A is maintained if one assumes that the surfaces are not completely impenetrable but repel via an energy penalty that increases exponentially fast with increasing overlap of the two solids [23.47]. The resulting theoretical prediction that $F_s \propto L/\sqrt{A}$ between rigid, flat, disordered walls also holds reasonably well for more general interactions between the solids, as tested explicitly by atomistic computer simulations.

Most real surfaces are rough and disordered. The minimal model that includes the effect of roughness consists of a single asperity contact, for instance the curved tip of an AFM [23.2] on a flat substrate. The tip is usually assumed to be disordered. Moreover, the contact mechanics of a nanoscale tip and a substrate in vacuum can best be described by the so-called Derjaguin–Müller–Toporov (DMT) limit [23.48]. DMT is similar to Hertzian contact mechanics, but it includes an additional adhesive off-set load L_{adh} that is incorporated into the effective load $L_{\text{eff}} = L + L_{\text{adh}}$. The area of contact is then given by $A \propto L_{\text{eff}}^{2/3}$, Substituting this proportionality into the relation $F_s \propto L_{\text{eff}}/\sqrt{A}$ discussed above, *Wenning* et al. [23.44] found

$$F_s \propto L^{2/3} . \tag{23.7}$$

This relationship is indeed observed experimentally in ultrahigh vacuum (UHV) [23.49, 50], as well as in atomistic computer simulations [23.44]. Of course, when the contacts are commensurate, we can expect the effective friction coefficient $\mu_{\text{eff}} = F_s/L_{\text{eff}}$ to be independent of L_{eff}, while for amorphous systems and in particular incommensurate systems, μ_{eff} decreases with increasing L_{eff}. The scaling with load in Fig. 23.3 confirms this expectation.

As noted above, the discussion thus far only deals with atomic/geometric interlocking. From Fig. 23.2 and the discussion above, one can understand how this interlocking leads to static friction, which is the threshold force to initiate sliding. However, kinetic friction $F_k(v)$ may nevertheless vanish in the limit of zero sliding velocity v, since in principle the energy that is gained when the system slides "downhill" can be stored and used later to make the slider go "uphill" again. Such a process would require that we can drive the system adiabatically. In the following, we will discuss atomistic processes (instabilities) that make it impossible to drive the system adiabatically. The presence of instabilities automatically leads to finite kinetic and static friction even in the absence of geometric interlocking.

23.2.2 Elastic Instabilities

In principle, elastic deflections of atoms can be large enough to prevent the interfacial forces from averaging to zero. Two simple ball and spring models are useful in illustrating how such motion can affect static and kinetic friction in principle as well as in understanding the results of detailed simulations or laboratory experiments. Both models consider two clean, flat, crystalline surfaces in direct contact (Fig. 23.4a). The bottom solid is assumed to be rigid, so that it can be treated as a fixed periodic substrate potential acting on the



Fig. 23.3 Static friction force F_s vs. normal load L for a commensurate tip, an incommensurate tip, and an amorphous tip. In all three cases, the radius of curvature was $R_c = 70$ Å and contacts were nonadhesive. Straight lines are fits according to $F_s \propto L^{\beta}$ with the results $\beta = 0.97 \pm 0.005$ (commensurate) and $\beta = 0.63 \pm 0.01$ (amorphous). [After [23.44] plus new data from L. *Wenning* (*open diamonds*)]



Fig. 23.4 **(a)** Two ideal, flat crystals making contact at the plane indicated by the *dashed line*. The nearest-neighbor spacings in the bottom and top walls are a and b, respectively. The Prandtl–Tomlinson model **(b)** and Frenkel–Kontorova model **(c)** replace the bottom surface by a periodic potential. The former model keeps elastic forces between atoms on the top surface and the center of mass of the top wall, and the latter includes springs of stiffness k between neighbors in the top wall. (After [23.56])

top solid. In order to make the problem analytically tractable, only the bottom layer of atoms from the top solid is retained, and the interactions within the top wall are simplified. In the Prandtl–Tomlinson model (Fig. 23.4b), the atoms are coupled to the center of mass of the top wall by springs of stiffness k, and coupling between neighboring atoms is ignored [23.51–53]. In the Frenkel–Kontorova model (Fig. 23.4c), the atoms are coupled to nearest-neighbors by springs, and the coupling to the atoms above is ignored [23.54, 55]. Due to their simplicity, these models arise in a number of different problems and a great deal is known about their properties.

Many features of the Prandtl–Tomlinson and Frenkel–Kontorova models can be understood from their 1-D versions. One important parameter is the ratio η between the lattice constants of the two surfaces $\eta \equiv b/a$. The other is the strength of the periodic potential from the substrate relative to the spring stiffness k that represents interactions within the top solid. If the substrate potential has a single Fourier component, then the periodic force can be written as

$$f(x) = -f_1 \sin\left(\frac{2\pi}{a}x\right) . \qquad (23.8)$$

The relative strength of the potential and springs can be characterized by the dimensionless constant $\lambda \equiv 2\pi f_1/ka$.

In the limit of infinitely strong springs ($\lambda \to 0$), both models represent rigid solids. The atoms of the top wall are confined to lattice sites $x_l^0 = x_{\mathrm{CM}} + lb$, where the integer l labels successive atoms and x_{CM} represents a rigid translation of the entire wall. The total lateral or friction force is given by summing (23.8):

$$F = -f_1 \sum_{l=1}^{N} \sin\left[\frac{2\pi}{a}(lb + x_{\mathrm{CM}})\right] , \qquad (23.9)$$

where N is the number of atoms in the top wall. In the special case of equal lattice constants ($\eta = b/a = 1$), the forces on all atoms add in phase and $F = -Nf_1 \sin(2\pi x_{\mathrm{CM}}/a)$. The maximum of this restraining force gives the static friction $F_{\mathrm{s}} = Nf_1$.

As noted above, the case of equal lattice constants is artificial and for real surfaces η is most likely to be an irrational number. Such surfaces are called incommensurate, while surfaces with a rational value of η are commensurate. When η is irrational, atoms on the top surface sample all phases of the periodic force with equal probability and the net force (23.9) vanishes exactly. When η is a rational number, it can be expressed as p/q, where p and q are integers with no common factors. In this case, atoms only sample q different phases. The net force from (23.9) still vanishes, because the force is a pure sine wave and the phases are equally spaced. However, the static friction is finite if the potential has higher harmonics. A Fourier component with wave vector $q2\pi/a$ and magnitude f_q contributes Nf_q to F_{s}. Studies of surface potentials [23.57] show that f_q drops exponentially with increasing q and thus imply that F_{s} will only be significant for small q.

As the springs become weaker, the top wall deforms more easily into a configuration that lowers the potential energy. The Prandtl–Tomlinson model is the simplest case to consider, because each atom can be treated as an independent oscillator within the upper surface. The equations of motion for the position x_l of the l^{th} atom can be written as

$$m\ddot{x}_l = -\gamma \dot{x}_l - f_1 \sin\left(\frac{2\pi}{a}x_l\right) - k(x_l - x_l^0) , \qquad (23.10)$$

where m is the atomic mass and x_l^0 is the position of the lattice site. Here γ is a phenomenological damping coefficient, like that in a Langevin thermostat, that allows work done on the atom to be dissipated as heat. It represents the coupling to external degrees of freedom such as lattice vibrations in the solids.

In any steady state of the system, the total friction can be determined either from the sum of the forces exerted by the springs on the top wall, or from the sum of the periodic potentials acting on the atoms (23.9). If the time average of these forces differed, there would be a net force on the atoms and a steady acceleration. The static friction is related to the force in metastable states of the system where $\ddot{x}_l = \dot{x}_l = 0$. This requires that spring and substrate forces cancel for each l,

$$k(x_l - x_l^0) = -f_1 \sin\left(\frac{2\pi}{a} x_l\right) . \tag{23.11}$$

As shown graphically in Fig. 23.5a, there is only one solution for weak interfacial potentials and stiff solids ($\lambda < 1$). In this limit, the behavior is essentially the same as for infinitely rigid solids. There is static friction for $\eta = 1$, but not for incommensurate cases. Even though incommensurate potentials displace atoms from lattice sites, there are exactly as many displaced to the right as to the left, and the force sums to zero.

A new type of behavior sets in when λ exceeds unity. The interfacial potential is now strong enough compared to the springs that multiple metastable states are possible. These states must satisfy both (23.11) and the condition that the second derivative of the potential energy is positive: $1 + \lambda \cos(2\pi x_l / a) > 0$. The number of metastable solutions increases as λ increases. As illustrated in Fig. 23.5b, once an atom is in a given metastable minimum it is trapped there until the center of mass moves far enough away that the second derivative of the potential vanishes and the minimum becomes unstable. The atom then pops forward very rapidly to the nearest remaining metastable state. Such motion, where a system is stuck for a long time and then suddenly jumps forward by an atomic spacing, is called atomic-scale stick-slip motion. During the pops, atoms reach large velocities and hence dissipate a large amount of energy into the lattice vibrations. This makes it possible to have a finite kinetic friction that does not vanish linearly with sliding velocity even when the surfaces are incommensurate [23.8, 9].

A similar analysis can be done for the 1-D Frenkel–Kontorova model [23.55, 58, 59]. The main difference is that the static friction and ground state depend strongly on η. For any given irrational value of η, there is a threshold potential strength λ_c. For weaker potentials, the static friction vanishes. For stronger potentials, elastic metastability produces a finite static friction. The transition to the onset of static friction was termed a breaking of analyticity by *Aubry* [23.59] and is often called the Aubry transition. The metastable states for $\lambda > \lambda_c$ take the form of locally commensurate regions that are separated by domain walls where the two crystals are out of phase. Within the locally commensurate regions the ratio of the periods is a rational number p/q that is close to η. The range of η where locking occurs grows with increasing potential strength (λ) until it spans all values. At this point there is an infinite number of different metastable ground states that form a fascinating "Devil's staircase" as η varies [23.55, 59].



Fig. 23.5a,b Graphical solution for metastability of an atom in the Prandtl–Tomlinson model for **(a)** $\lambda = 0.5$ and **(b)** $\lambda = 3$. The *straight dashed lines* show the force from the spring, $k(x_l - x_l^0)$, at different x_l^0, and the *curved lines* show the periodic substrate potential. For $\lambda < 1$, there is a single intersection of the *dashed lines* with the substrate potential for each value of x_l^0, and thus a single metastable state. For $\lambda > 1$, there are multiple intersections with the substrate potential. *Dotted portions* of the potential curve indicate unstable maxima, and *solid regions* indicate metastable solutions. Fast pops with concurrent energy dissipation cannot be avoided for $\lambda > 1$ even when the slider moves slowly. (After [23.56])

Although elastic instabilities can, in principle, induce finite static friction at the atomic scale, this appears to be rare. There have been a significant number of computer simulations showing that the *wearless* static friction between crystalline surfaces is extremely small, except in the artificial case of identical and perfectly aligned walls [23.8, 10]. Studies of iron on iron [23.60], a blunt pyramidal diamond tip on a metal surface [23.61], a blunt pyramidal copper tip on incommensurate copper substrates [23.62], interlayer sliding in multiwalled carbon nanotubes [23.63], and Lennard-Jonesium on Lennard-Jonesium [23.40] all confirm the simple prediction that lateral forces cancel out. These simulations have in common that the solids were treated truly three-dimensionally and that the atoms (interacting via microscopic interaction potentials) were allowed to relax, thus making long-range elastic deformations possible. Significant lateral forces were only observed in combination with strongly irreversible processes such as production of wear debris, plastic deformation, material mixing, or cold welding and not due to geometric interlocking or elastic instabilities alone.

23.2.3 Role of Dimensionality and Disorder

The previous section considered whether local atomic displacements could lead to static friction. Long-range deformations between individual contacts could also allow surfaces to lock together [23.41, 42] Although we are concerned with the friction between two 3-D solid bodies, it is instructive to analyze the role of dimensionality in determining the effect of disorder. To do this, let us consider a d_{obj}-dimensional elastic solid, for example, a generalization of the elastic Frenkel–Kontorova chain to higher dimensions. We may safely assume the free elastic solid to be mechanically stable, meaning that the tensor of the elastic constants is positive definite. The dimension of the interface between the slider and disordered substrate is denoted by d_{int}.

In such a situation, there will be a competition between the random substrate-slider interactions and the elastic coupling within the solids. An important question to ask is how the interactions change when we change the scale of the system, for example, how strong are the random and the elastic interactions on a length scale $2\mathcal{L}$ if we know their respective strengths on a scale $\mathcal{L}$. Here $\mathcal{L}$ gives the linear dimension of the solids in all directions, that is to say, parallel and normal to the interface. As discussed above, the random forces between substrate and slider add incoherently and thus their sum scales as the square root of the interface area $\sim \mathcal{L}^{d_{\text{int}}/2}$. The elastic forces, on the other hand, scale as $\mathcal{L}^{d_{\text{obj}}-2}$. A linear chain can be more easily compressed if we replace one spring with two springs coupled in series. In two dimensions, springs are not only coupled in series but also in parallel, so that the elastic coupling remains invariant to a "block transformation". Each additional dimension strengthens the effect of "parallel" coupling.

In the thermodynamic limit $\mathcal{L} \to \infty$, the effect of disorder will always dominate the elastic interactions or vice versa, except in the special case where

$$\mathcal{L}^{d_{\text{int}}/2} \propto \mathcal{L}^{d_{\text{obj}}-2} . \tag{23.12}$$

For $\lim_{\mathcal{L}\to\infty} \mathcal{L}^{d_{\text{int}}/2}/\mathcal{L}^{d_{\text{obj}}-2} \gg 1$, the random interactions will dominate, and hence pinning via elastic instabilities cannot be avoided. This disorder-induced elastic pinning is similar to the pinning of compliant, ordered systems, as discussed above within the context of the Prandtl–Tomlinson and the Frenkel–Kontorova models. For $\lim_{\mathcal{L}\to\infty} \mathcal{L}^{d_{\text{int}}/2}/\mathcal{L}^{d_{\text{obj}}-2} \ll 1$, the long-range elastic forces dominate the long-range random forces. The slider's motion can only be opposed by elastic instabilities if the elastic coupling is sufficiently weak at finite $\mathcal{L}$ in order to make local pinning possible, again akin to the case of $\lambda > 1$ in the Prandtl–Tomlinson model.

The so-called *marginal* dimension, in which both contributions scale with the same exponent, $d_{\text{int}}/2 = d_{\text{obj}} - 2$, occurs in the important case of 3-D solid bodies with 2-D surfaces. In the marginal dimension, the friction force can stay finite, however, detailed analysis [23.42, 64] shows the friction force per unit area, and hence the friction coefficient, to be exponentially small. Even for objects with a dimensionality d_{mar} less than their marginal dimension $d_{\text{mar}} = 2 + d_{\text{int}}/2$ (see (23.12)), friction forces may turn out to be small. One example is an experimental quartz crystal microbalance study [23.65] of solid and liquid krypton films on disordered gold surfaces for which the pinning forces were undetectably small. For adsorbed layers, which satisfy $d_{\text{obj}} = d_{\text{int}}$, the marginal dimension would be $d_{\text{mar}} = 4$.

23.2.4 Elastic Instabilities vs. Wear in Atomistic Models

As mentioned in Sect. 23.2.2, there is no published computer simulation study known to us in which the solids were treated truly atomistically in three dimensions and where the interfacial interactions lead to elastic pinning according to Prandtl–Tomlinson or Frenkel–Kontorova. In this context, we want to discuss exemplarily computer simulations of a copper tip on copper by *Sørensen* et al. [23.62]. We consider their study to be rather generic and also well-done from a technical point of view for a variety of reasons: The effects of commensurability and finite contact area were examined in detail, the simulations were done at constant normal load instead of constant separation, the interaction potentials were realistic, and initial and boundary conditions were chosen such that the tip had the possibility to deform. Snapshots of one of their sliding simulations are shown in Fig. 23.6. Note that one must keep in mind that the simulation only addresses the tribological properties in UHV.

Flat, clean tips with (111) or (100) surfaces were brought into contact with corresponding crystalline substrates [23.62]. The two exterior layers of tip and surface were treated as rigid units, and the dynamics of the remaining mobile layers was followed. Interatomic forces and energies were calculated using semi-empirical potentials derived from effective medium theory [23.66]. At finite temperatures, the outer mobile layers of both tip and surface were coupled to a Langevin thermostat. Zero temperature simulations gave similar results.

In the commensurate Cu(111) case, *Sørensen* et al. [23.62] observed atomic-scale stick-slip motion of the tip like that described above for the Tomlinson model. The trajectory was of zigzag form, which could be related to jumps of the tip's surface between fcc and hcp positions. Detailed analysis of the slips showed that they occurred via a dislocation mechanism. Dislocations were nucleated at the corner of the interface, and then moved rapidly through the contact region. Adhesion led to a large static friction at zero load: The static friction per unit area, or critical yield stress, dropped from 3.0 GPa to 2.3 GPa as T increased from 0 to 300 K. The kinetic friction increased linearly with load with a surprisingly small differential friction coefficient $\tilde{\mu}_k \equiv \partial F_k/\partial L \approx 0.03$. In the load regime investigated, $\tilde{\mu}_k$ was independent of temperature and load. No velocity dependence was detectable up to sliding velocities of $v = 5\,\text{m/s}$. At higher velocities, the friction decreased. Even though the interactions between the surfaces are identical to those within the surfaces, no wear was observed. This was attributed to the fact that (111) surfaces are the preferred slip planes in fcc metals.



Fig. 23.6 Snapshots showing the evolution of a Cu(100) tip on a Cu(100) substrate during sliding to the left. (After [23.62])

Adhesive wear was observed between a commensurate (100) tip and substrate (Fig. 23.6). Sliding in the (011) direction at either constant height or constant load led to inter-plane sliding between (111) planes inside the tip. As shown in Fig. 23.6, this plastic deformation led to wear of the tip, which left a trail of atoms in its wake. The total energy was an increasing function of sliding distance due to the extra surface area. The constant evolution of the tip kept the motion from being periodic, but the sawtoothed variation of force with displacement that is characteristic of atomic-scale stick-slip was still observed.

Sørensen et al. [23.62] also examined the effect of incommensurability. An incommensurate Cu(111) system was obtained by rotating the tip by 16.1° about the axis perpendicular to the substrate. For a small tip (5 × 5 atoms), they observed an Aubry transition from smooth sliding with no static friction at low loads to atomic-scale stick-slip motion at larger loads. Further increases in load led to sliding within the tip and plastic deformation. Finite systems are never truly incommensurate, and pinning was found to occur at the corners of the contact, suggesting it was a finite-size effect. Larger tips (19 × 19) slid without static friction at all loads. Similar behavior was observed for incommensurate Cu(100) systems.

These results confirm the conclusions of *Hirano* et al. [23.60] that even bare metal surfaces of the same material will not exhibit static friction if the surfaces are incommensurate. They also indicate that contact areas as small as a few hundred atoms are large enough to exhibit this effect. Similar results were obtained for Lennard Jonesium [23.6, 40, 67]: The interbulk interactions between unlike atoms (each solid is initially composed of one Lennard-Jones species) have to be distinctly larger than the intrabulk interactions between identical atoms in order to induce elastic instability. However, as soon as the interactions between unlike atoms are larger than those between like atoms, there is a mixing instability leading to a cold welded junction.

Lancon [23.69] reported that there is the possibility for elastic instabilities under carefully designed conditions between two incommensurate gold surfaces. The importance of the interfacial interactions with respect to the intrabulk interactions was increased through the application of a pressure normal to the interface. At 4 GPa, an elastic Aubry transition was observed concurrently with finite static friction. The normal pressures employed in those simulations were well above the yield strength of gold. However, plastic flow at the contact's circumference could be avoided by the use of flat surfaces that filled out the whole simulation cell parallel to the interface. Additional examples of elastic instabilities may be found for very compliant solids, but the majority of simple solids will not pin elastically on an atomic scale. Note, however, that cold welding may still occur on long time scales due to diffusion. On such time scales, the interface geometry may rearrange to produce locally commensurate regions that lower the interfacial free energy and allow geometrical pinning.

23.2.5 Hydrodynamic Lubrication and Its Confinement-Induced Breakdown

So far, we have been concerned with dry friction. However, most surfaces are covered by dirt and/or lubricants. Hydrodynamics and elasto-hydrodynamics have been very successful in describing lubrication by micron-thick films [23.70]. These continuum theories begin to break down as atomic structure becomes important. Experiments and simulations reveal a sequence of dramatic changes in the static and dynamic properties of fluid films as their thickness decreases from microns down to molecular scales. These changes have important implications for the function of boundary lubricants and the origins of static friction.

Let us consider two flat, lubricated walls separated by a distance d and sliding with a relative parallel velocity v. Let us further assume that the lubricant's viscosity μ in the center of the contact equals that of the bulk fluid phase. The shear stress must be uniform in steady state, because any imbalance would lead to accelerations. Since the velocity gradient times the viscosity μ gives the stress in the fluid, the kinetic friction per unit area is

$$F_\mathrm{k} = \frac{v\mu}{d+\mathcal{S}} \,, \tag{23.13}$$

where we introduce the so-called slip length $\mathcal{S}$. It represents the distance into the wall at which the velocity gradient would extrapolate to zero; see Fig. 23.7f for a graphical illustration of $\mathcal{S}$. The calculation of slip length from velocity profiles has some ambiguity, and we refer to work by *Bocquet* et al. [23.71] for the least ambiguous resolution to the definition of the slip length known to us.

Macroscopic experiments are generally well-described by a "no-slip" boundary condition (BC), where $\mathcal{S} = 0$ and the tangential component of the fluid velocity equals that of the solid at the surface. The one prominent exception is contact-line motion, where an interface between two fluids moves along a solid surface. This motion would require an infinite force in hydrodynamic theory, unless slip occurred near the contact line.

As d decreases, any deviation from $\mathcal{S} = 0$ becomes more evident in (23.13). Studies of confined films show



Fig. 23.7a–f Panels **(a)–(c)** show density as a function of position z relative to two walls whose atoms are centered at $z/\sigma = \pm 6.4$. Values of ϵ_wf are indicated. *Solid lines* are for equal wall and fluid densities ($\rho = 0.81\sigma^{-3}$), and *dotted lines* are for $\rho_w = 2.52\rho$. *Squares* in panels **(d)–(f)** show the average velocity in each layer as a function of z, and *solid* and *dotted lines* are fits through these values for low and high density walls, respectively. For this data, the walls were moved in opposite directions at speed $U = 1\sigma/t_\mathrm{LJ}$. The *dashed line* in **(e)** represents the flow expected from hydrodynamics with a no-slip BC ($\mathcal{S} = 0$). As shown in **(f)**, the slope (*dashed line*) far from the walls is used to define $\mathcal{S}$. (From [23.8] after [23.68])

that slip may occur ($\mathcal{S} > 0$) or layers may stick onto the solid ($\mathcal{S} < 0$) [23.68, 71–73]. These deviations from the no-slip BC have been correlated with structural changes in the fluid near the walls. The first observation was that layering occurs in planes parallel to the walls. It is induced by the sharp cutoff in fluid density at the wall and the pair correlation function $g(r)$ between fluid atoms. An initial fluid layer forms at the preferred wall-fluid spacing. Additional fluid molecules tend to lie in a second layer, at the preferred fluid-fluid spacing. This layer induces a third, and so on. Layering can alter the BC and the viscosity of the confined fluid. As suggested by the contrasting behavior of commensurate and incommensurate solids, the BC depends sensitively on the degree to which the walls imprint their in-plane density modulations into the lubricant.

Some of the trends that are observed in the degree and extent of layering are illustrated in Fig. 23.7 [23.68, 72]. The fluid density is plotted as a function of the distance between walls for a model that is also considered in almost all of the other studies of flow BCs described below. The fluid consists of spherical molecules interacting through a Lennard-Jones potential (23.1) with characteristic energy and length scales ϵ and σ. They are confined by crystalline walls containing discrete atoms. In this case, the walls were planar (001) surfaces of an fcc crystal. Wall and fluid atoms also interact with a Lennard-Jones potential, but with a different binding energy ϵ_{wf}.

The net adsorption potential from the walls can be increased by raising ϵ_{wf}, or by increasing the density of the walls ρ_w, so that more wall atoms attract the fluid. Figure 23.7 shows that both increases lead to increases in the height of the first density peak. The height also increases with the pressure in the fluid [23.73], since that forces atoms into steeper regions of the adsorption potential. The height of subsequent density peaks decreases smoothly with distance from the wall, and only four or five well-defined layers are seen near each wall in Fig. 23.7. The rate at which the density oscillations decay is determined by the decay length of structure in the bulk pair-correlation function of the fluid. Since all panels of Fig. 23.7 have the same conditions in the bulk, the decay rate is the same. The adsorption potential only determines the initial height of the peaks.

As mentioned above, solid surfaces also induce density modulations within the plane of the layers [23.7]. These modulations can be quantified by the 2-D static structure factor at the shortest reciprocal lattice vector Q of the substrate [23.35, 68]. When normalized by the number of atoms in the layer, N_l, this becomes an intensive variable that would correspond to the Debye–Waller factor in a crystal. The maximum possible value, $S(Q)/N_l = 1$, corresponds to fixing all atoms exactly at crystalline lattice sites. In a strongly ordered case such as $\rho_w = \rho$ in Fig. 23.7c, the small oscillations about lattice sites in the first layer only decrease $S(Q)/N_l$ to 0.71. This is well above the value of 0.6 that is typical of bulk 3-D solids at their melting point [23.74] and indicates that the first layer has crystallized onto the wall. The values of $S(Q)/N_l$ in the second and third layers are 0.31 and 0.07, respectively, and atoms in these layers exhibit typical fluid diffusion.

There is some correlation between the factors that produce strong layering and those that produce strong in-plane modulations. For example, chain molecules have several conflicting length scales that tend to frustrate both layering and in-plane order [23.36, 75, 76]. However, the dependence of in-plane order on the density of substrate atoms is more complicated than for layering. When $\rho_w = \rho$, the fluid atoms can naturally sit on the sites of a commensurate lattice, and $S(Q)$ is large. When the substrate density ρ_w is increased by a factor of 2.52, the fluid atoms no longer fit easily into the corrugation potential. The degree of induced in-plane order drops sharply, although the layering becomes stronger (Fig. 23.7). Sufficiently strong adsorption potentials may eventually lead to crystalline order in the first layers and stronger layering. However, this may actually increase slip.

Thompson et al. [23.68] found that all of their results for $\mathcal{S}$ collapsed onto a universal curve when plotted against the structure factor $S(Q)/N_l$. When one or more layers crystallized onto the wall, the same collapse could be applied as long as the effective wall position was shifted by a layer and the Q for the outer wall layer was used. The success of this collapse at small $S(Q)/N_l$ can be understood from a perturbation theory [23.6, 77] developed to quantitatively explain the kinetic friction on adsorbed monolayers [23.3].

One of the surprising features of Fig. 23.7 is that the viscosity remains the same even in regions near the wall where there is pronounced layering. Any change in viscosity would produce a change in the velocity gradient, since the stress is constant. However, the flow profiles in panel (d) remain linear throughout the cell. The profile for the dense walls in panel (f) is linear up to the last layer, which has crystallized onto the wall. From Fig. 23.7 it is apparent that local density variations by at least a factor of seven can be accommodated without a viscosity change.

Bitsanis et al. [23.78] examined the change in viscosity with film thickness. They found that results for film thicknesses $h > 4\sigma$ could be fit using the bulk viscosity for the average density. However, as h decreased below 4σ, the viscosity diverged much more rapidly than any model based on bulk viscosity could explain. These observations were consistent with surface force apparatus (SFA) experiments on nanometer thick films of a wide variety of small molecules [23.4, 5]. Layering in molecularly thin films gave rise to oscillations in the energy, normal force, and effective viscosity as the film thickness decreased. Most films of one to three molecular layers exhibited a yield stress characteristic of solid-like behavior, even though the molecules form a simple Newtonian fluid in the bulk. Deviations from the no-slip condition might cause μ_{eff} to differ from the bulk viscosity by an order of magnitude. However, they could not explain the observed changes of μ_{eff} by more than five orders of magnitude, or the even more dramatic changes by 10 to 12 orders of magnitude in the characteristic viscoelastic relaxation time determined from the shear rate dependence of μ_{eff} [23.5].

More recent experimental and theoretical studies confirm that most fluids exhibit a glass transition when confined to channels less than 3 to 10 molecular diameters [23.33, 79]. *Thompson* et al. [23.34, 36] considered changes in flow with film thickness in a wide range of model systems. As in experiment, they found dramatic divergences in the viscosity and relaxation time that suggested confinement induced a glass transition. Later work by *Baljon* et al. [23.33, 80] indicates that the same glass transition is produced by changes in thickness, pressure, or temperature. In particular, the shear-rate-dependent viscoelastic response of systems of all sizes, pressures, and temperatures can be collapsed onto the same universal curve above the glass transition [23.33].

23.2.6 Submonolayer Films

Physisorbed molecules such as short hydrocarbon chains can be expected to sit on any surface exposed to atmospheric conditions. Even in ultrahigh vacuum, special surface treatments are needed to remove strongly physisorbed species from surfaces. Given the generic observation of glassy behavior in thin films, *Robbins* et al. [23.81] suggested that these submonolayer contaminants could provide a general explanation for the universal observation of static friction. Subsequent simulations have confirmed that physisorbed molecules qualitatively alter tribological behavior. For example, they lead to static friction between two incommensurate walls [23.67, 82] or two disordered walls [23.47] that would slide without friction if they were clean. The theoretical explanation of this effect can be understood from a simple analytical model considered by *Müser* et al. [23.47]. In order to make two surfaces pin, a nonvanishing fraction of the density modulations must share the same period and lock into phase. This happens automatically for commensurate surfaces, but not for incommensurate surfaces unless they are unrealistically compliant. However, a submonolayer of atoms or molecules that does not form strong covalent bonds with the confining solids can simultaneously lock to the density modulations of two incommensurate walls and hence give rise to a finite friction coefficient.

Simulation results for the friction due to physisorbed layers are consistent with a large number of experimental observations. While Amontons's laws state that the friction is independent of the macroscopic area, it is well established that the friction is proportional to the real area of molecular contact A_{real} [23.30, 83, 84]. Experiments where both the friction and molecular area can be measured [23.4, 85–89] show that the local shear stress τ_{s} needed to initiate sliding rises linearly with the normal pressure P:

$$\tau_{\text{s}} = \tau_0 + \alpha P \; . \tag{23.14}$$

This gives a macroscopic friction force $F_{\text{s}} = \tau_0 A_{\text{real}} + \mu L$, where the total load is just $L = P A_{\text{real}}$. This friction law is actually more general than Amontons's laws, reducing to it at large loads and small areas, but explaining why the friction between adhesive surfaces (like tape) does not vanish at zero load.

For a wide range of parameters [23.82, 90], the friction calculated for physisorbed monolayers follows (23.14) up to the gigapascal pressures that are present in real contacts. Moreover, the results are remarkably insensitive to parameters that are not controlled in experiments such as the crystallographic orientation of the solids, the thickness of the adsorbed layer, and the direction of sliding. The only exceptions occur for the unlikely case of commensurate walls [23.90, 91], as discussed further below. Subsequent studies of kinetic friction [23.39, 92] explain both the close relation between experimental values of static friction and the slow variation with velocity. In particular, the logarithmic rate dependence seen in τ for many systems [23.83] can be explained through thermally activated hopping of physisorbed molecules [23.92].

Müser et al. [23.47] have constructed a simple analytical theory that captures many of the results and conclusions from the above simulations. At the pressures of interest, the atoms act like hard spheres. In order to slide, the bounding surfaces must lift up over these spheres against the normal pressure. The situation is analogous to the simple cartoon in Fig. 23.2, but with atomic-scale ramps, and the required stress increases linearly with pressure for the same reason. The offset, τ_0, is related to adhesive interactions between the two surfaces that increase the effective load [23.90]. Unlike the original model of geometrical interlocking, the atomic-scale ramps rearrange during sliding. The dissipation during these rearrangements is responsible for kinetic friction [23.47, 92], which, as we now discuss, is very different for commensurate and incommensurate walls.

The characteristic motion of individual boundary lubricant atoms depends on the relative displacement for commensurate walls, because the distribution of metastable states depends on the relative alignment of the two walls [23.90, 92]. For example, no "pops" of the lubricant atoms are observed when the two commensurate solids are aligned directly above each other. This behavior is in contrast with that for incommensurate surfaces for which the distribution of metastable states does not change as the slider is translated with respect to the substrate. Stressing the analogy to the Prandtl–Tomlinson model, static and kinetic friction are related for incommensurate, boundary-lubricated solids, while they are not necessarily related for commensurate, boundary-lubricated solids. Indeed, commensurate, boundary-lubricated surfaces exhibit a dramatic decrease in friction at the transition from stick-slip motion to smooth sliding, while this dramatic decrease is absent for incommensurate, boundary-lubricated walls [23.39].

It has been noted recently, that dimensionality not only plays an important role for elastic objects, but also for boundary lubricants [23.39]. It was predicted that kinetic friction would be Stokes-like (i. e., vanish linearly with velocity) between incommensurate surfaces, if it were possible to confine lubricant particles into trenches of (sub)nanometer depth and width, so that the motion of the lubricant embedded between the surfaces becomes 1-D. At the same time, however, static friction would remain finite.

The above results suggest that adsorbed molecules and other "third-bodies" may prove key to understanding macroscopic friction measurements. It will be interesting to extend these studies to more realistic molecular potentials and to rough surfaces. To date, realistic potentials have only been used for "between-sorbed" particles between commensurate surfaces. This work is reviewed elsewhere [23.8, 10, 11].

23.3 Stick–Slip Dynamics

The dynamics of sliding systems can be very complex and depend on many factors, including the types of metastable states in the system, the times needed to transform between states, and the mechanical properties of the device that imposes the stress. At high rates or stresses, systems usually slide smoothly. At low rates, the motion often becomes intermittent, with the system alternately sticking and slipping forward [23.30, 32]. Everyday examples of such stick-slip motion include the squeak of hinges and the music of violins.

The alternation between stuck and sliding states of the system reflects changes in the way energy is stored. While the system is stuck, elastic energy is pumped into the system by the driving device. When the system slips, this elastic energy is released into kinetic energy and eventually dissipated as heat. The system then sticks once more, begins to store elastic energy, and the process continues. Both elastic and kinetic energy can be stored in all the mechanical elements that drive the system. The whole coupled assembly must be included in any analysis of the dynamics.

The simplest type of intermittent motion is the atomic-scale stick-slip that occurs in the multistable regime ($\lambda > 1$) of the Prandtl–Tomlinson model. Energy is stored in the springs while atoms are trapped in a metastable state, and converted to kinetic energy as they pop to the next metastable state. This phenomenon is quite general and has been observed in many simulations of wearless friction [23.8, 10], as well as in the motion of atomic force microscope tips [23.1, 2]. In these cases, motion involves a simple ratcheting over the surface potential through a regular series of hops between neighboring metastable states. The slip distance is determined entirely by the periodicity of the surface potential.

Many examples of stick-slip involve a rather different type of motion that can lead to intermittency and chaos [23.93–97]. Instead of jumping between neighboring metastable states, the system slips for very long distances before sticking. For example, *Gee* et al. [23.4] and *Yoshizawa* et al. [23.98] observed slip distances of many microns in their studies of confined films with the

SFA. This distance is much larger than any characteristic periodicity in the potential and varied with velocity, load, and the mass and stiffness of the SFA. The fact that the SFA does not stick after moving by a lattice constant indicates that sliding has changed the state of the system in some manner, so that it can continue sliding even at forces less than the yield stress.

One simple property that depends on past history is the amount of stored kinetic energy. This can carry a system over potential energy barriers even when the stress is below the yield stress. The simplest example is the underdamped Prandtl–Tomlinson model, which has been thoroughly studied in the mathematically equivalent case of an underdamped Josephson junction [23.99]. One finds a hysteretic response function, where static and moving steady-states coexist over a range of forces between $F_{\min}$ and the static friction F_s. There is a minimum stable steady-state velocity $v_{\min}$ corresponding to $F_{\min}$. At lower velocities, the only steady state is linearly unstable because $\partial v/\partial F < 0$ – pulling harder slows the system [23.30, 32]. If the top wall of the Tomlinson model is pulled at an average velocity less than $v_{\min}$ by a sufficiently compliant system, it will exhibit large-scale stick-slip motion.

Experimental systems typically have many other internal degrees of freedom that may depend on past history. Macroscopic models normally assume that a single unspecified state variable is relevant and add dynamical rules for this variable to create a phenomenological rate-state model [23.94, 100]. This approach has captured experimental behavior from a wide range of systems, including surface force apparatus experiments [23.38, 101], paper sliding on paper [23.93], and earthquakes [23.102]. However, in most cases, there is no microscopic model for the state variable and its time dependence.

One set of systems where microscopic pictures for the state variable have been considered are confined films in SFA experiments. Confined films have structural degrees of freedom that can change during sliding, and this provides an alternative mechanism for stick-slip motion [23.35]. Some of these structural changes are illustrated in Fig. 23.8, which shows stick-slip motion of a two-layer film of simple spherical molecules. The bounding walls were held together by a constant normal load. A lateral force was applied to the top wall through a spring k attached to a stage that moved with fixed velocity v in the x direction. The equilibrium configuration of the film at $v = 0$ is a commensurate crystal that resists shear. Thus at small times, the center of mass of the top wall remains pinned at $X = 0$. The force grows linearly with time, $F = kv$, as the stage advances ahead of the wall. When F exceeds F_s, the wall slips forward. The force drops rapidly because the slip velocity $\dot{X}$ is much greater than v. When the force drops sufficiently, the



Fig. 23.8a–d Time dependence of **(a)** force per unit area f, **(b)** lateral position of the top wall X, **(c)** wall spacing h, and **(d)** degree of crystallinity $S(G_1)/S(0)$ as a function of time during stick-slip motion of walls confining two layers of spherical molecules. (After [23.35])

film recrystallizes, the wall stops, and the force begins to rise once more.

One structural change that occurs during each slip event is dilation by about 10% (Fig. 23.8c). *Dhinojwala* et al. [23.103] have recently confirmed that dilation occurs during slip in SFA experiments. The increased volume makes it easier for atoms to slide past each other and is part of the reason the sliding friction is lower than F_s. The system may be able to keep sliding in this dilated state as long as it takes more time for the volume to contract than for the wall to advance by a lattice constant. Dilation of this type plays a crucial role in the yield, flow, and stick-slip dynamics of granular media [23.104–106]. In some simulations, the dilation is localized at a single plane – either a wall/film interface or a plane within the film [23.33, 107]. In some cases, there is also in-plane ordering of the film to enable it to slide more easily over the wall. This ordering remains after sliding stops and provides a mechanism for the long-term memory seen in some experiments [23.4, 98, 108].

The degree of crystallinity throughout the film may also change during sliding. Deviations from an ideal crystalline structure can be quantified by the Debye–Waller factor $S(G_1)/S(0)$ (Fig. 23.8d), where G_1 is one of the shortest reciprocal lattice vectors and $S(0) = N$ is the total number of atoms in the film. When the system is stuck, $S(G_1)/S(0)$ has a large value that is characteristic of a 3-D crystal. During each slip event, $S(G_1)/S(0)$ drops dramatically. The minimum values are characteristic of simple fluids that would show a no-slip boundary condition (Sect. 23.2.5). The atoms also exhibit rapid diffusion that is characteristic of a fluid. The periodic melting and freezing transitions that occur during stick-slip are induced by shear, not by the negligible changes in temperature. Shear-melting transitions at constant temperature have been observed in both theoretical and experimental studies of bulk colloidal systems [23.29, 109]. While the above simulations of confined films used a fixed number of particles, *Lupowski* et al. [23.110] found equivalent results at fixed chemical potential.

Very similar behavior has been observed in simulations of sand [23.104], chain molecules [23.33], incommensurate or amorphous walls [23.35], and minimal models with single molecules between surfaces [23.95–97]. These systems transform between glassy and fluid states during stick-slip motion. As in equilibrium, the structural differences between glass and fluid states are small. However, there are strong changes in the self-diffusion and other dynamic properties when the film goes from the static glassy to sliding fluid state. *Buldum* and *Ciraci* [23.111] found stick-slip motion due to periodic structural transformations in the bottom layers of a pyramidal Ni(111) tip sliding on an incommensurate Cu(110) surface.

23.4 Conclusions

The discussion of computer simulations in this chapter aimed to build a general atomistic understanding of tribological processes rather than to elucidate a specific sliding system. The advantage of studying simplified models, as opposed to chemically realistic systems, is that system properties can be varied at will. This allows the role of adhesion, surface curvature, contaminant layers and other factors to be isolated and explored. For example, to explore the effects of adhesion one can compare results from a simulation that includes the long-range attractive interactions between atoms with those from a simulation where all attractive interactions between surfaces are eliminated, leaving all other parameters unchanged. Care should be taken to avoid simplifications that are known to yield atypical results. In particular, the use of commensurate, perfectly aligned, crystalline surfaces has been shown to produce qualitatively different results, even in the presence of a lubricating film! Surface curvature must also be included in a way that properly models stress distributions from the bounding solids.

One central question is how contacting surfaces lock together to produce a static friction force. This is particularly perplexing in the context of many nanotribological systems where friction occurs without significant plastic deformation or wear. Many theories for wearless solid friction assume that surfaces deform elastically to conform to each other, and that atoms advance in a series of elastic instabilities during sliding. However, the simulations discussed above show that simple solids should hardly ever show elastic instabilities on an atomic scale without concurrent plastic flow or material transfer. Despite extensive efforts to design an atomistic system whose static friction mechanism is entirely elastic, no such model could be found as long as the ingredients were: three-dimensional incommensurate solids, flat or smoothly curved contacts, and two-body interactions between all atoms. Under these conditions the relative lateral motion is only opposed by a viscous-like force that goes to zero for small sliding velocities. When interfacial interactions are increased in an attempt to produce elastic instabilities, plastic flow is also observed.

Wearless friction between clean solid surfaces is only found in simulations of very small contacts. The geometric interlocking in such contacts is particularly relevant to AFM experiments. When only a few atoms on the tip make contact, the potential from the substrate does not average to zero. Static friction can then occur without elastic instabilities within the tip. The Prandtl–Tomlinson model can be applied to these systems with the cantilever stiffness replacing the internal stiffness of the material in the tip. As the diameter of the contact increases, due to blunting of the tip or increased load, the friction coefficient produced by geometric interlocking decreases. In the specific case of non-adhesive contacts, the friction between an amorphous tip and a clean crystalline substrate scales as $F \propto L^{2/3}$ and μ vanishes as $L^{-1/3}$. Thus geometric interlocking is not expected to yield significant friction when the contact area contains more than $\sim 10^3$ atoms.

Most contacting solids are separated by contaminant layers, or third bodies, that introduce many additional structural degrees of freedom. The intervening atoms can rearrange into a local free energy minimum for any geometry of the bounding solids without paying the large elastic energy cost that limits rearrangements within these solids. Simulations that include these layers reproduce many details of SFA experiments. They also provide an explanation for Amontons's laws, and exceptions to them, in larger contacts.

Many important problems remain to be addressed by simulations. Of particular interest are the roles of realistic, random surface roughness and subsurface plastic deformation. Studies of these phenomena will require new multiscale approaches that treat long-range elastic and plastic deformations in the solids. Other important problems will require extensions in the time available to simulations. Examples include cold-welding through inter-surface diffusion, wear, and fatigue. Addressing these problems will be a continuing challenge to the computer modeling community.

References

23.1 C. M. Mate, G. M. McClelland, R. Erlandsson, S. Chiang: Atomic-scale friction of a tungsten tip on a graphite surface, Phys. Rev. Lett. **59** (1987) 1942–1945

23.2 R. W. Carpick, M. Salmeron: Scratching the surface: Fundamental investigations of tribology with atomic force microscopy, Chem. Rev. **97** (1997) 1163–1194

23.3 J. Krim: Friction at the atomic scale, Sci. Am. **275**(4) (1996) 74–80

23.4 M. L. Gee, P. M. McGuiggan, J. N. Israelachvili, A. M. Homola: Liquid to solid transitions of molecularly thin films under shear, J. Chem. Phys. **93** (1990) 1895–1906

23.5 S. Granick: Motions and relaxations of confined liquids, Science **253** (1992) 1374–1379

23.6 M. Cieplak, E. D. Smith, M. O. Robbins: Molecular origins of friction: The force on adsorbed layers, Science **265** (1994) 1209–1212

23.7 M. Schoen, C. L. Rhykerd, D. J. Diestler, J. H. Cushman: Fluids in micropores: I. Structure of a simple classical fluid in a slit-pore, J. Chem. Phys. **87** (1987) 5464–5476

23.8 M. O. Robbins, M. H. Müser: Computer simulations of friction, lubrication and wear. In: *Modern Tribology Handbook*, ed. by B. Bhushan (CRC, Boca Raton 2001) pp. 717–765

23.9 M. H. Müser, M. Urbakh, M. O. Robbins: Statistical mechanics of static and low-velocity kinetic friction, Adv. Chem. Phys. **126** (2003) 187–272

23.10 J. A. Harrison, S. J. Stuart, D. W. Brenner: Atomic-scale simulation of tribological and related phenomena. In: *Handbook of Micro/Nanotribology*, ed. by B. Bhushan (CRC, Boca Raton 1999) pp. 525–594

23.11 J. A. Harrison, G. T. Gao, R. J. Harrison, G. M. Chateauneuf, P. T. Mikulski: The friction of model self-assembled monolayers. In: *Encyclopedia of Nanoscience and Nanotechnology*, ed. by H. S. Nalwa (American Scientific, Los Angeles 2004)

23.12 M. P. Allen, D. J. Tildesley: *Computer Simulation of Liquids* (Clarendon, Oxford 1987)

23.13 D. Frenkel, B. Smit: *Understanding Molecular Simulation: From Algorithms to Applications* (Academic, San Diego 1996)

23.14 J. P. Ryckaert, A. Bellemans: Molecular dynamics of liquid alkanes, Faraday Discuss. **66** (1978) 95–106

23.15 W. Paul, D. Y. Yoon, G. D. Smith: An optimized united atom model for simulations of polymethylene melts, J. Chem. Phys. **103** (1995) 1702–1709

23.16 W. Tschöp, K. Kremer, J. Batoulis, T. Bürger, O. Hahn: Simulation of polymer melts. I. Coarse graining procedure for polycarbonates, Acta Polym. **49** (1998) 61–74

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

23.17 W. Tschöp, K. Kremer, J. Batoulis, T. Bürger, O. Hahn: Simulation of polymer melts. II. From coarse grained models back to atomistic description, Acta Polym. **49** (1998) 75–79

23.18 P. Flory: *Statistical Mechanics of Chain Molecules* (Hanser, München 1988)

23.19 K. Binder: *Monte Carlo and Molecular Dynamics Simulations in Polymer Science* (Oxford, New York 1995)

23.20 D.W. Brenner, O.A. Shenderova, J.A. Harrison, S.J. Stuart, B. Ni, S.B. Sinnot: Second generation reactive empirical bond order (REBO) potential energy expression for hydrocarbons, J. Phys. C **14** (2002) 783–802

23.21 S.J. Stuart, A.B. Tutein, J.A. Harrison: A reactive potential for hydrocarbons with intermolecular interactions, J. Chem. Phys. **112** (2000) 6472–6486

23.22 M.S. Daw, M.I. Baskes: Embedded-atom method: Derivation and application to impurities, surfaces, and other defects in metals, Phys. Rev. B **29** (1984) 6443–6453

23.23 S. Nosé: Constant temperature molecular dynamics methods, Prog. Theor. Phys. Supp. **103** (1991) 1–46

23.24 T. Schneider, E. Stoll: Molecular dynamics study of a three-dimensional one-component model for distortive phase transitions, Phys. Rev. B **17** (1978) 1302–1322

23.25 G.S. Grest, K. Kremer: Molecular dynamics simulations for polymers in the presence of a heat bath, Phys. Rev. A **33** (1986) 3628–3631

23.26 S.S. Sarman, D.J. Evans, P.T. Cummings: Recent developments in non-Newtonian molecular dynamics, Phys. Rep. **305** (1998) 1–92

23.27 D.J. Evans, G.P. Morriss: Shear thickening and turbulence in simple fluids, Phys. Rev. Lett. **56** (1986) 2172–2175

23.28 W. Loose, G. Ciccotti: Temperature and temperature control in nonequilibrium-molecular-dynamics simulations of the shear flow of dense liquids, Phys. Rev. A **45** (1992) 3859–3866

23.29 M.J. Stevens, M.O. Robbins: Simulations of shear-induced melting and ordering, Phys. Rev. E **48** (1993) 3778–3792

23.30 F.P. Bowden, D. Tabor: *The Friction and Lubrication of Solids* (Clarendon, Oxford 1986)

23.31 R. Khare, J.J. de Pablo, A. Yethiraj: Rheology of confined polymer melts, Macromolecules **29** (1996) 7910–7918

23.32 E. Rabinowicz: *Friction and Wear of Materials* (Wiley, New York 1965)

23.33 M.O. Robbins, A.R.C. Baljon: Response of thin oligomer films to steady and transient shear. In: *Microstructure and Microtribology of Polymer Surfaces*, ed. by V.V. Tsukruk, K.J. Wahl (American Chemical Society, Washington 2000) pp. 91–117

23.34 P.A. Thompson, G.S. Grest, M.O. Robbins: Phase transitions and universal dynamics in confined films, Phys. Rev. Lett. **68** (1992) 3448–3451

23.35 P.A. Thompson, M.O. Robbins: Origin of stick-slip motion in boundary lubrication, Science **250** (1990) 792–794

23.36 P.A. Thompson, M.O. Robbins, G.S. Grest: Structure and shear response in nanometer-thick films, Israel J. Chem. **35** (1995) 93–106

23.37 M. Porto, V. Zaloj, M. Urbakh, J. Klafter: Macroscopic versus microscopic description of friction: From Tomlinson model to shearons, Tribol. Lett. **9** (2000) 45–54

23.38 B.N.J. Persson: *Sliding Friction: Physical Principles and Applications* (Springer, Berlin 1998)

23.39 M.H. Müser: Nature of mechanical instabilities and their effect on kinetic friction, Phys. Rev. Lett. **89** (2002) 224301: 1–4

23.40 M.H. Müser: Dry friction between flat surfaces: Wearless multistable elasticity vs. material transfer and plastic deformation, Tribol. Lett. **10** (2001) 15–22

23.41 J.B. Sokoloff: Static friction between elastic solids due to random asperities, Phys. Rev. Lett. **86** (2001) 3312–3315

23.42 B.N.J. Persson, E. Tosatti: Theory of friction: Elastic coherence length and earthquake dynamics, Solid State Commun. **109** (1999) 739–744

23.43 F.F. Abraham, N. Bernstein, J.Q. Broughton, D. Hess: Dynamic fracture of silicon: Concurrent simulation of quantum electrons, classical atoms, and the continuum solid, MRS Bull. **25** (2000) 27–32

23.44 L. Wenning, M.H. Müser: Friction laws for elastic nano-scale contacts, Europhys. Lett. **54** (2001) 693–699

23.45 U. Landman, W.D. Luedtke, N.A. Burnham, R.J. Colton: Atomistic mechanisms and dynamics of adhesion, nanoindentation, and fracture, Science **248** (1990) 454–461

23.46 D. Dowson: *History of Tribology* (Longman, New York 1979)

23.47 M.H. Müser, L. Wenning, M.O. Robbins: Simple microscopic theory of Amontons's laws for static friction, Phys. Rev. Lett. **86** (2001) 1295–1298

23.48 M. Enachescu, R.J.A. van den Oetelaar, R.W. Carpick, D.F. Ogletree, C.J.F. Flipse, M. Salmeron: An AFM study of an ideally hard contact: The diamond (111)/tungsten carbide interface, Phys. Rev. Lett. **81** (1998) 1877–1880

23.49 C.A.J. Putman, M. Igarashi, R. Kaneko: Single-asperity friction in friction force microscope: The composite model, Appl. Phys. Lett. **66** (1995) 3221–3223

23.50 P. Schwarz, O. Zwörner, P. Köster, R. Wiesendanger: Quantitative analysis of the frictional properties of solid materials at low loads. II. Mica and germanium sulfide, Phys. Rev. B **56** (1997) 6987–7000

23.51 L. Prandtl: Ein Gedankenmodell zur kinetischen Theorie der festen Körper, Z. Angew. Math. Mech. **8** (1928) 85–106

23.52 G. A. Tomlinson: A molecular theory of friction, Philos. Mag. Series **7** (1929) 905–939

23.53 G. M. McClelland, S. R. Cohen: Tribology at the atomic scale. In: *Chemistry and Physics of Solid Surfaces*, Vol. VII, ed. by R. Vanselow, R. Rowe (Springer, Berlin, Heidelberg 1990) pp. 419–445

23.54 Y. I. Frenkel, T. Kontorova: On the theory of plastic deformation and twinning, Zh. Eksp. Teor. Fiz. **8** (1938) 1340

23.55 O. M. Braun, Y. S. Kivshar: Nonlinear dynamics of the Frenkel–Kontorova model, Phys. Rep. **306** (1998) 1–108

23.56 M. O. Robbins: Jamming, friction, and unsteady rheology. In: *Jamming and Rheology: Constrained Dynamics on Microscopic and Macroscopic Scales*, ed. by A. J. Liu, S. R. Nagel (Taylor and Francis, London 2000)

23.57 L. W. Bruch, M. W. Cole, E. Zaremba: *Physical Adsorption: Forces and Phenomena* (Oxford, New York 1997)

23.58 F. C. Frank, J. H. van der Merwe: One-dimensional dislocations. I. Static theory, Proc. R. Soc. A **198** (1949) 205–225

23.59 S. Aubry: The new concept of transitions by breaking of analyticity in a crystallographic model. In: *Solitons and Condensed Matter Physics*, ed. by A. R. Bishop, T. Schneider (Springer, Berlin, Heidelberg 1979) pp. 264–290

23.60 M. Hirano, K. Shinjo: Atomistic locking and friction, Phys. Rev. B **41** (1990) 11837–11851

23.61 J. Belak, I. F. Stowers: The indentation and scraping of a metal surface: A molecular dynamics study. In: *Fundamentals of Friction: Macroscopic and Microscopic Processes*, ed. by I. L. Singer, H. M. Pollock (Kluwer, Dordrecht 1992) pp. 511–520

23.62 M. R. Sørensen, K. W. Jacobsen, P. Stoltze: Simulations of atomic-scale sliding friction, Phys Rev. B **53** (1996) 2101–2113

23.63 A. N. Kolmogorov, V. H. Crespi: Smoothest bearings: Interlayer sliding in multiwalled carbon nanotubes, Phys. Rev. Lett. **85** (2000) 4727–4730

23.64 A. Volmer, T. Natterman: Towards a statistical theory of solid dry friction, Z. Phys. B **104** (1997) 363–371

23.65 C. Mak, J. Krim: Quartz-crystal microbalance studies of disorder induced lubrication, Faraday Discuss. **107** (1997) 389–397

23.66 K. W. Jacobsen, J. K. Norskov, M. J. Puska: Interatomic interactions in the effective-medium theory, Phys. Rev. B **35** (1987) 7423–7442

23.67 M. H. Müser, M. O. Robbins: Conditions for static friction between flat crystalline surfaces, Phys. Rev. B **61** (2000) 2335–2342

23.68 P. A. Thompson, M. O. Robbins: Shear flow near solids: Epitaxial order and flow boundary conditions, Phys. Rev. A **41** (1990) 6830–6837

23.69 F. Lancon: Aubry transition in a real material: Prediction for its existence in an incommensurate gold/gold interface, Eur. Phys. Lett. **57** (2002) 74–79

23.70 D. Dowson, G. R. Higginson: *Elastohydrodynamic Lubrication* (Pergamon, Oxford 1968)

23.71 L. Bocquet, J.-L. Barrat: Hydrodynamic boundary conditions and correlation functions of confined fluids, Phys. Rev. Lett. **70** (1993) 2726–2729

23.72 P. A. Thompson, M. O. Robbins: Simulations of contact-line motion: Slip and the dynamic contact angle, Phys. Rev. Lett. **63** (1989) 766–769

23.73 J.-L. Barrat, L. Bocquet: Large slip effect at a nonwetting fluid-solid interface, Phys. Rev. Lett. **82** (1999) 4671–4674

23.74 M. J. Stevens, M. O. Robbins: Melting of Yukawa systems: A test of phenomenological melting criteria, J. Chem. Phys. **98** (1993) 2319–2324

23.75 J. Gao, W. D. Luedtke, U. Landman: Structure and solvation forces in confined films: Linear and branched alkanes, J. Chem. Phys. **106** (1997) 4309–4318

23.76 A. Koike, M. Yoneya: Chain length effects on frictional behavior of confined ultrathin films of linear alkanes under shear, J. Phys. Chem. B **102** (1998) 3669–3675

23.77 E. D. Smith, M. Cieplak, M. O. Robbins: The friction on adsorbed monolayers, Phys. Rev. B **54** (1996) 8252–8260

23.78 I. Bitsanis, S. A. Somers, H. T. Davis, M. Tirrell: Microscopic dynamics of flow in molecularly narrow pores, J. Chem. Phys. **93** (1990) 3427–3431

23.79 A. L. Demirel, S. Granick: Glasslike transition of a confined simple fluid, Phys. Rev. Lett. **77** (1996) 2261–2264

23.80 A. R. C. Baljon, M. O. Robbins: Energy dissipation during rupture of adhesive bonds, Science **271** (1996) 482–484

23.81 M. O. Robbins, E. D. Smith: Connecting molecular-scale and macroscopic tribology, Langmuir **12** (1996) 4543–4547

23.82 G. He, M. H. Müser, M. O. Robbins: Adsorbed layers and the origin of static friction, Science **284** (1999) 1650–1652

23.83 J. H. Dieterich, B. D. Kilgore: Direct observation of frictional contacts: New insights for state-dependent properties, Pure Appl. Geophys. **143** (1994) 238–302

23.84 P. Berthoud, T. Baumberger: Shear stiffness of a solid-solid multicontact interface, Proc. R. Soc. Lond. A **454** (1998) 1615–1634

23.85 A. L. Demirel, S. Granick: Transition from static to kinetic friction in a model lubricated system, J. Chem. Phys. **109** (1998) 6889–6897

23.86 I. L. Singer: Solid lubrication processes. In: *Fundamentals of Friction: Macroscopic and Microscopic Processes* (Elsevier, Amsterdam 1992) pp. 237–261

23.87 B. J. Briscoe: Friction and wear of organic solids and the adhesion model of friction, Philos. Mag. A **43** (1981) 511–527

23.88 B. J. Briscoe, A. C. Smith: The interfacial shear strength of molybdenum disulphide and graphite films, Trans. ASLE **25** (1982) 349–354
23.89 A. Berman, C. Drummond, J. N. Israelachvili: Amontons's law at the molecular level, Tribol. Lett. **4** (1998) 95–101
23.90 G. He, M. O. Robbins: Simulations of the static friction due to adsorbed molecules, Phys. Rev. B **64** (2001) 035413
23.91 J. Gao, X. C. Zeng, D. J. Diestler: Nonlinear effects of physisorption on static friction, J. Chem. Phys. **113** (2000) 11293–11296
23.92 G. He, M. O. Robbins: Simulations of the kinetic friction due to adsorbed molecules, Tribol. Lett. **10** (2001) 7–14
23.93 F. Heslot, T. Baumberger, B. Perrin, B. Caroli, C. Caroli: Creep, stick-slip, and dry-friction dynamics: Experiments and a heuristic model, Phys. Rev. E **49** (1994) 4973–4988
23.94 A. Ruina: Slip instability and state variable friction laws, J. Geophys. Res. **88** (1983) 10359–10370
23.95 M. G. Rozman, M. Urbakh, J. Klafter: Stick-slip motion and force fluctuations in a driven two-wave potential, Phys. Rev. Lett. **77** (1996) 683–686
23.96 M. G. Rozman, M. Urbakh, J. Klafter: Stick-slip dynamics as a probe of frictional forces, Europhys. Lett. **39** (1997) 183–188
23.97 M. G. Rozman, M. Urbakh, J. Klafter, F. J. Elmer: Atomic scale friction and different phases of motion of embedded systems, J. Phys. Chem. B **102** (1998) 7924–7930
23.98 H. Yoshizawa, J. N. Israelachvili: Fundamental mechanisms of interfacial friction. 1. Stick-slip friction of spherical and chain molecules, J. Phys. Chem. **97** (1993) 11300–11313
23.99 D. E. McCumber: Effect of ac impedance on the dc voltage-current characteristics of superconductor weak-link junctions, J. App. Phys. **39**(7) (1968) 3113–3118
23.100 J. H. Dieterich: Modeling of rock friction. 2. Simulation of pre-seismic slip, J. Geophys. Res. **84** (1979) 2169–2175
23.101 A. A. Batista, J. M. Carlson: Bifurcations from steady sliding to stick slip in boundary lubrication, Phys. Rev. E **57** (1998) 4986–4996
23.102 J. H. Dieterich, B. D. Kilgore: Implications of fault constitutive properties for earthquake prediction, Proc. Natl. Acad. Sci. USA **93** (1996) 3787–3794
23.103 A. Dhinojwala, S. C. Bae, S. Granick: Shear-induced dilation of confined liquid films, Tribol. Lett. **9** (2000) 55–62
23.104 P. A. Thompson, G. S. Grest: Granular flow: Friction and the dilatancy transition, Phys. Rev. Lett. **67** (1991) 1751–1754
23.105 H. M. Jaeger, S. R. Nagel, R. P. Behringer: Granular solids, liquids, and gases, Rev. Mod. Phys. **68** (1996) 1259–1273
23.106 S. Nasuno, A. Kudrolli, J. P. Gollub: Friction in granular layers: Hysteresis and precursors, Phys. Rev. Lett. **79** (1997) 949–952
23.107 A. R. C. Baljon, M. O. Robbins: Stick-slip motion, transient behavior, and memory in confined films. In: *Micro/Nanotribology and Its Applications*, ed. by B. Bhushan (Kluwer, Dordrecht 1997) pp. 533–553
23.108 A. L. Demirel, S. Granick: Friction fluctuations and friction memory in stick-slip motion, Phys. Rev. Lett. **77** (1996) 4330–4333
23.109 B. J. Ackerson, J. B. Hayter, N. A. Clark, L. Cotter: Neutron scattering from charge stabilized suspensions undergoing shear, J. Chem. Phys. **84** (1986) 2344–2349
23.110 M. Lupowski, F. van Swol: Ultrathin films under shear, J. Chem. Phys. **95** (1991) 1995–1998
23.111 A. Buldum, S. Ciraci: Interplay between stick-slip motion and structural phase transitions in dry sliding friction, Phys. Rev. B **55** (1997) 12892–12895

24. Mechanics of Biological Nanotechnology

Mechanics of

One of the most compelling areas to be touched by nanotechnology is biological science. Indeed, we will argue that there is a fascinating interplay between these two subjects, with biology as a key beneficiary of advances in nanotechnology as a result of a new generation of single molecule experiments that complement traditional assays involving statistical assemblages of molecules. This interplay runs in both directions, with nanotechnology continually receiving inspiration from biology itself. The goal of this chapter is to highlight some representative examples of the exchange between biology and nanotechnology and to illustrate the role of nanomechanics in this field and how mechanical models have arisen in response to the emergence of this new field. Primary attention will be given to the particular example of the processes that attend the life cycle of bacterial viruses. Viruses feature many of the key lessons of biological nanotechnology, including self assembly, as evidenced in the spontaneous formation of the protein shell (capsid) within which the viral genome is packaged, and a motor-mediated biological process, namely, the packaging of DNA in this capsid by a molecular motor that pushes the DNA into the capsid. We argue that these processes in viruses are a compelling real-world example of nature's nanotechnology and reveal the nanomechanical challenges that will continue to be confronted at the nanotechnology-biology interface.

24.1 Science at the Biology–Nanotechnology Interface 740
24.1.1 Biological Nanotechnology 740
24.1.2 Self-Assembly as Biological Nanotechnology 740
24.1.3 Molecular Motors as Biological Nanotechnology 740
24.1.4 Molecular Channels and Pumps as Biological Nanotechnology 741
24.1.5 Biologically Inspired Nanotechnology.......................... 742
24.1.6 Nanotechnology and Single Molecule Assays in Biology 743
24.1.7 The Challenge of Modeling the Bio-Nano Interface................. 744

24.2 Scales at the Bio-Nano Interface............ 746
24.2.1 Spatial Scales and Structures 747
24.2.2 Temporal Scales and Processes....... 749
24.2.3 Force and Energy Scales: The Interplay of Deterministic and Thermal Forces 750

24.3 Modeling at the Nano-Bio Interface....... 752
24.3.1 Tension Between Universality and Specificity 752
24.3.2 Atomic-Level Analysis of Biological Systems 753
24.3.3 Continuum Analysis of Biological Systems 753

24.4 Nature's Nanotechnology Revealed: Viruses as a Case Study.......................... 755

24.5 Concluding Remarks 760

References 761

Nanotechnology is the seat of a broad variety of interdisciplinary activity with applications as diverse as optoelectronics, microfluidics, and medicine. However, one of the richest interdisciplinary areas only now beginning to be harvested is the interface between the biological sciences and nanotechnology. The aim of the present chapter is threefold. First, we wish to illustrate the synergy that exists between biological nanotechnology (e.g., molecular motors, transmembrane pumps, etc.) and biologically inspired nanotechnology (e.g., synthetic proteins, artificial viruses aimed at delivering drugs, biofunctionalized cantilevers, etc.). Secondly, through a series of order-of-magnitude estimates and an associated examination of the units for describing spatial dimensions, temporal processes, forces at the nanoscale, and the energy budget in nanoscale systems, we aim to build an intuitive sense of the workings of nanotechnology in the biological set-

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

ting. Finally, through several specific case studies, we hope to illustrate some of the challenges faced in modeling the mechanical processes of biological nanotechnology and show how such challenges have been met thus far and how they might be met in the future.

24.1 Science at the Biology–Nanotechnology Interface

24.1.1 Biological Nanotechnology

Though the innovations leading to the adoption of the expression "nanotechnology" are indeed impressive, the perspective of this chapter is that one need only look inward to the way that our muscles move, to how we digest and synthesize molecules of dazzling complexity, to the way in which we think the thoughts that permit us to fill the shelves of libraries with scientific journals to realize that the greatest nanotechnology of all is that which is revealed in the living world. That is, one of the central thrusts is the idea that the microscopic workings of life offer an inspiring vision of nanotechnology. Clearly, the diversity of the examples of "nanotechnology" seen in the living world can (and do) fill the pages of learned texts. A guided tour of the machinery of the cell can be found in *Alberts* et al. [24.1], while a vision of the cell as an assemblage of "protein machines" has been argued for by *Alberts* [24.2]. The ambition of the present section is to provide several cursory examples of the nanotechnological marvels that power the living realm.

24.1.2 Self-Assembly as Biological Nanotechnology

One of the most intriguing nanotechnological tricks of the living world is the central role played by self-assembly in such systems. Whether we consider the spontaneous assembly of viruses, either in test tubes or in the interior of an infected cell, or the fusion of one membrane-bound region to another through vesicle fusion, spontaneous formation of functional "materials" is a key part of the biological repertoire. To be more concrete, we note that self-assembly in biological systems takes place in a number of different guises. First, the self-assembly of linear assemblies is a key part of the cytoskeletal assembly process with G-actin associating to form actin filaments and, similarly, tubulin monomers joining to form microtubules. This is also the process that is used by certain bacteria such as *Listeria* for locomotion. Both of these examples are described more fully in [24.3]. This same type of process is taken to the next level of sophistication in simple viruses such as tobacco mosaic virus that involve not only the assembly of protein monomers, but also the genetic message in the form of long RNA molecules. A second broad class of self-assembly processes is associated with the formation of containers such as liposomes or viral capsids. In the case of liposomes, lipid molecules such as phosphatidylcholine spontaneously organize in a way that sequesters the hydrophobic tails from the surrounding water. Similarly, protein subunits spontaneously assemble to form viral capsids [24.4]. These structures play a variety of roles in the biological realm, from serving as containers for different macromolecules to providing for concentration gradients of small ions that are maintained and utilized by molecular motors such as ATPsynthase [24.1].

Beyond the simplistic description of self-assembly advanced above, a second key feature of biological self-assembly must also be considered. In particular, a variety of self-assembly processes in the biological realm are templated (or coded). As is well-known, proteins are a hugely versatile class of molecules all based upon the same fundamental building blocks. Interestingly, the enormous diversity of protein action is founded upon 20 distinct amino acid building blocks, and the template for assembling a given protein is carried in the form of messenger RNA, which is then read and used as the basis for protein synthesis by the ribosome. One of the most exciting developments in modern nanotechnology is the attempt to exploit templated self-assembly processes for the purposes of creating new materials. An example in the context of protein-based materials can be found in the article of *van Hest* and *Tirrell* [24.5], where the machinery of the cell has been tricked into incorporating artificial amino acids into synthetic proteins.

24.1.3 Molecular Motors as Biological Nanotechnology

One of the hallmarks of life is change and motion. At the cellular level, such motion is effected through a dizzying variety of mechanisms, most of which when viewed at the molecular level are seen to be the result of the action of molecular motors [24.3]. For example, muscle contraction reflects the coherent action of huge numbers of myosin motor molecules as they march along actin filaments. Similarly, the motion of certain bacteria can be traced to the rotation of a rotary motor embedded in the cell wall, which is attached to filaments known as flagella [24.6]. In a similar vein, just as our modern society is replete with examples of systems aimed at allowing for communication and transport between widely separated geographic locations, so, too, has the living world had to answer these same challenges. As will be shown in the section of this chapter aimed at making estimates of various scales and processes in nanotechnology, one of the key mechanisms for communication and transport is diffusion. That is, a chemical concentration at one place can make its presence known at a distance x with a characteristic time, $t_{\text{diffusive}} \approx x^2/2D$, where D is the diffusion constant. However, as will be shown later in the chapter, there are many cellular processes that cannot wait as long as $t_{\text{diffusion}}$. As a result, a host of molecular motors and an associated transport system (the elements of the cytoskeleton) permit active transport. For example, kinesin is a motor molecule that transports material along long, relatively rigid polymeric assemblies known as microtubules [24.1].

Even more incredible are rotary machines like those associated with ATPsynthase and bacterial flagella. ATPsynthase is a membrane-embedded machine that rotates and, in so doing, synthesizes new ATP molecules (adenosine triphosphate, energy currency of the cell) [24.1, 7–9]. Similarly, the bacterial flagellar motor rotates with the result that the attached bacterial flagellum rotates and thereby induces motion of the cell [24.3, 6]. The exquisite details of the construction of these devices are themselves breathtaking. The rotary motors in bacteria are constructed from several components that are much like a rotor and stator and perform periodic motions by deriving energy from the flow of protons across a membrane [24.6]. These rotary motors are very powerful, as evidenced by F_1-ATPsynthase, which can generate a torque large enough to rotate a molecule of actin 100 times its own length [24.10]. In addition, bacterial motors have another layer of sophistication in that stimuli from the external environment, which are sensed by the bacteria through the pores on its membrane, can change the direction of rotation of the motor in a process known as chemotaxis [24.3]. Feedback and signal transmission are implemented in engineering devices by means of complex circuitry, whereas in the living world these functions are often accomplished by means of chemistry and conformational changes in large molecules.

All of these molecular machines involve a rich interplay between chemistry, thermodynamics, and mechanics. From a structural perspective, most molecular motors are proteins with different subunits performing different functions [24.11]. Often there is some region within the motor where chemical energy is derived from the hydrolysis of adenosine triphosphate (ATP). This chemical energy is then converted to mechanical energy through a conformational change in the protein. These examples serve to call the reader's attention to the importance and variety of motor molecules found throughout the living world and which almost any sensible definition of nanotechnology would have to include as particulary sophisticated examples.

24.1.4 Molecular Channels and Pumps as Biological Nanotechnology

From a structural perspective, one of the most intriguing features of cellular systems is their division into a number of separate membrane-bound compartments. We have already touched upon this compartmentalization in the context of self-assembly, and note that the role of membranes and the proteins bound within them is described clearly in *Alberts* et al. [24.1]. The presence of such compartments, often marked by large concentration gradients with respect to the surrounding medium, hints at another nanotechnological wonder of the living world, namely, the presence of a wide range of transmembrane channels that mediate the exchange of material between these different compartments. Certain passive versions of these channels are gated by various mechanisms such as the arrival of signaling molecules or tension in the membrane within which they are found [24.12–14]. Once the channel is in the open state, ions pass through passively, by diffusion. Active versions of ion channels that transfer ions such as Na^+ and Ca^{2+} are similarly critical for the functioning of a cell, both in the case of unicellular and multicellular organisms. For example, in the case of Na^+ ions, typical concentrations within the cell can be as much as a factor of 10–20 less than those in the extracellular milieu. Such concentration gradients imply the need for sophisticated active "devices" which can do work against such gradients. One of the most remarkable of machines of this type is the Na^+–K^+ pump [24.1]. This machine is powered by hydrolysis of ATP (i. e., the consumption of ATP fuel), and it can pump ions up a potential gradient. In particular, this pump hydrolyzes ATP and pumps Na^+ ions *out* of the cell against a very steep concentration gradient while pumping K^+ ions *in* again against a steep gradient.

The point of this brief discussion has been to illustrate the first of several perspectives that we will bring to bear on the question of the biology-nanotechnology interface. Thus far, we have noted that nature is replete with examples of macromolecules and macromolecular assemblies that perform nanotechnological tasks and in this capacity serve as examples of biological nanotechnology. Next, we wish to examine the ways in which biological phenomena can inspire nanotechnology itself.

24.1.5 Biologically Inspired Nanotechnology

As noted in the beginning of this chapter, biological systems are nanotechnologically relevant for several reasons. First, as shown above, the living world is full of examples of nanotechnological devices. However, a second key point is that nanotechnology has been driven and inspired by the example of biological systems and the need (for example, in medicine) to influence biological systems at the scale of a single cell. In addition, preliminary steps have been taken to harness the nanotechnology of biological systems and use it to perform useful functions.

One compelling example of a proof-of-principle, biologically inspired device emerged from work aimed at exploring the function of ATPsynthase, the rotary device already described above. Fluorescently labelled filamentous proteins from the cytoskeleton, known as actin, were attached to the putative rotary component of the F_1 subunit. The point of this exercise is that such filaments are observable using light microscopy. It was then observed that the long actin filament rotated like a propeller when the ATPsynthase performed ATP hydrolysis [24.15].



Fig. 24.1 Schematic of the experiment in which bacteriorhodopsin (*top of figure*) and ATPsynthase (*right of figure*) are artificially reconstituted in a liposome, and they act in unison to produce ATP molecules

A second example, also involving ATPsynthase, is suggested by a set of beautiful experiments done by *Racker* and others [24.16, 17]. The idea is illustrated schematically in Fig. 24.1. Two different protein machines are "reconstituted" in an artificial membrane-bound region known as a liposome. One of these devices is known as bacteriorhodopsin and has the capacity to pump hydrogen ions when it is exposed to light. Since both the bacteriorhodopsin and ATPsynthase are embedded in the same membrane, the ATPsynthase can then exploit the light-induced proton gradient to perform ATP synthesis. Again, these experiments were undertaken not for their role as possible devices, but rather to probe the nature of various molecular machines. Nevertheless, we view them as a provocative demonstration of both the manipulation and use of such machines in artificial environments. As such, they provide an inspiring vision of the possibilities for biologically inspired nanotechnology.

Another fascinating example of biologically inspired nanotechnology is that of biofunctionalized cantilevers (see Fig. 24.2). A typical example is provided by the experiments of *Wu* et al. [24.18], who have demonstrated the use of a biofunctionalized cantilever as a scheme for detecting small concentrations of biologically interesting molecules such as prostrate-specific antigen and single-stranded DNA. One surface of the cantilever is coated with an antibody, and then it is placed in environments containing different concentrations of the antigen. The key ideas from a mechanical perspective are: i) the difference in surface energy between the top and bottom surfaces of the cantilever induces spontaneous bending and ii) the binding of molecules of interest to target molecules initially present on the surface leads to surface energy differences and bending that can be detected by optical means. In this way the concentration of the molecules of interest can be measured. The specificity and sensitivity of the method makes it viable for use in the laboratory, as well as for commercial purposes. We return to this example in our discussion of the modeling challenges posed by problems at the interface between biology and nanotechnology.



Fig. 24.2 Schematic of the use of biofunctionalized cantilevers as a tool for detecting molecules of biological interest (figure courtesy of Arun Majumdar, Berkeley)

24.1.6 Nanotechnology and Single Molecule Assays in Biology

One of the key refrains of the nanotechnological era is Feynman's quip that "there is plenty of room at the bottom" [24.19]. The benefits of miniaturization are evident at every turn in applications ranging from our cars to our computers. Associated with the development of the inspiring new techniques made possible by nanotechnology has been the emergence of a host of scientific opportunities. One of the arenas to benefit from these new techniques is biology. As scientists and engineers have taken the plunge to the nanotechnological "bottom" foreseen by Feynman, opportunities have constantly arisen to manipulate biological systems in ways that were heretofore unimagined, culminating in a new era of single molecule biology. Single molecule experiments have, in fact, presented us with a view of Feynman's "room at the bottom" as being filled with very complicated machines whose functioning makes life possible.

Single molecule assays complement statistical/collective studies involving a large number of molecular actors by revealing the prominent role of fluctuations at the sub-cellular scale. For example, a photospectrometer measures the optical response of a huge collection of molecules, whereas optical tweezers pull on a single molecule of DNA and enable us to follow the changes in conformation or the breakage of bonds. In fact, experimental methods are so advanced that it is now possible to manipulate a single molecule even as we watch it on a screen as it jiggles around in different conformations. In what follows, we give several examples of how nanotechnology has reached out to help create single molecule biology and in the process has led to the advent of new quantitative opportunities to investigate biological systems.

Atomic-Force Microscopy

One of the tools that has revolutionized nanotechnology, in general, and single molecule biology, in particular, is the atomic-force microscope. The AFM has helped create the field of single molecule force spectroscopy [24.20]. We note that mechanics has a long tradition of using force-extension data (much like the electrical engineer uses current-voltage data) to probe the inner workings of various materials. It is now possible to apply forces of known magnitude on a macromolecule and study how it deforms under the force. This furnishes structural information and provides insights into the energy landscape the molecule needs to navigate as it undergoes force-induced conformational changes. The energy of deformation associated with such molecules is primarily determined by weak forces such as hydrogen bonds, van der Waals contacts, and hydration effects. On a more philosophical note, these experiments force us to think in terms of forces and not energy, complementing the traditional views held in molecular biology, and they can lead to many new insights about the relation between structure and function in proteins, polynucleotides, and other macromolecular entities.

The AFM has been used in a wide variety of single molecule experiments on many of the key classes of molecules found in the living world, including nucleic acids, proteins, and carbohydrates. One fascinating example is the use of atomic force microscopy to examine the mechanical properties of the muscle protein titin [24.21]. The experiment is illustrated schematically in Fig. 24.3, which shows that there is a series of force-extension signatures (increasing force and extension followed by a precipitous load drop) that correspond to the unbinding of the individual domains that make up this protein.



Fig. 24.3 Schematic illustrating the way that the AFM has been harnessed as a nanotechnological analogue of the Instron machine for the measurement of the force-extension properties of single molecules. Four snapshots in the life history of a globular protein subject to loading are shown, as well as the measured force-extension curve. Each sawtooth corresponds to the unfolding of a single protein domain. (Figure adapted from [24.22])

Optical Tweezers

Another instrument that has been used with great success in the realm of biophysics for the purposes of performing nanomechanical measurements on macromolecules and their assemblies is the optical tweezer [24.23, 24]. While the AFM is relatively stiff and applies large forces (on the order of 100–1,000 pN), optical tweezers are compliant and can measure smaller forces (on the order of 0.1–10 pN). Some of the most interesting experiments performed with optical tweezers concern the functioning of molecular motors, which by themselves are marvels of nanotechnology. For example, *Svoboda* et al. [24.25] attached kinesin to an optically trapped bead and observed its movement along a microtubule. An example of the type of data to emerge from such experiments is shown in Fig. 24.4. One of the conclusions to emerge from such experiments is that kinesin can exert forces on the order of 5–7 pN before it stalls. Such experiments also permit an examination of the effect of changing the concentration of ATP on the functioning of kinesin [24.26]. Similar experiments have been performed on RNA polymerase as it advances along DNA to deduce not only the stall force, but also its velocity as a function of the constraining force [24.27]. Such measurements provide a mechano-chemical basis of biological function and go a long way in revealing connections between chemical kinetics and mechanical processes at the molecular level.

As noted in the abstract, one of the most fascinating examples of the biology-nanotechnology interface is that of bacterial viruses, known as bacteriophages. The life cycle of a large class of bacteriophages is characterized by self-assembly processes that lead to the formation of the protein shell of the virus followed by active packaging of the viral DNA within this shell by a motor. The structure of this so-called "viral portal motor" has recently been solved using X-ray crystallography [24.28]. In a recent experiment, *Smith* et al. used optical tweezers to study the characteristics of the DNA packaging process of the ϕ-29 bacteriophage [24.29]. One of the conclusions of this experiment is that the motor has to act against an increasing resistive force as more and more of the DNA is packed inside the capsid. From a quantitative perspective, this experiment yields the force and the rate of packing as a function of the fraction of the genome packed. It is also important to note that bacteriophages are not only an obscure subject of quiet enquiry, but are also the basis of a huge range of cloning products (see, for example, the lambda ZAP vectors of Stratagene) used for doing experiments with recombinant DNA, and more generally, viruses are being explored as the basis of gene therapy.

Our discussion thus far has been aimed at providing a rough overview of the vast landscape that sits at the interface between biology and nanotechnology. It is hoped that the few representative case studies set forth above suffice to illustrate our basic thesis, namely, that biological nanotechnology represents nanotechnology at its best.

24.1.7 The Challenge of Modeling the Bio-Nano Interface

As highlighted in the previous two subsections, there have been huge advances at the interface between nanotechnology and biology. We have argued that there are two distinct representations of the interface between biology and nanotechnology, and each has its own associated set of modeling challenges. The argument of the present discussion is that another key part of the infrastructure that must attend these developments is that associated with the modeling of these systems. One of the intriguing ways in which modeling at the biology-nanotechnology interface is assuming greater importance is that with increasing regularity, experimental data on biological systems is of a quantitative character. As a result, the models that are put forth to greet these experiments must similarly be of a quantitative character [24.30].



Fig. 24.4 Schematic illustrating the use of optical tweezers to measure the speed of the molecular motor kinesin in its journey along a microtubule

As an example of the type of modeling challenges that must be faced in contemplating the types of problems described above, we return to the example of biofunctionalized cantilevers as a problem in nanomechanics [24.18, 31]. The basic physics behind the use of biofunctionalized cantilevers as sensors is a competition between elastic bending energy and the surface free energy difference between the upper and lower faces of the cantilever. The face with the lower free energy per unit area tends to increase its area by bending the cantilever. The amount of bending, on the other hand, is limited by the elastic energy cost. The utility of this device derives from the fact that the difference in the surface free energy is affected by specific binding of target molecules to probe molecules that are initially deposited on one side of the cantilever.

To provide a quantitative model of the biofunctionalized cantilever, we construct an energy functional that takes into account the elastic energy of beam bending and the surface energy. Both contributions to the total energy can be written as functionals of $u(x)$, the deflection of the cantilever. Note that in the case in which the two surfaces have the same free energy per unit area, $\gamma_{\text{up}} = \gamma_{\text{down}}$, the equilibrium configuration corresponds to $u(x) = 0$. The case of interest here is that in which the two surfaces have different energies.

We recall that the energy associated with beam bending is of the form [24.32]

$$E_{\text{bend}}\left[u(x)\right] = \frac{EI}{2}\int_0^L \left[u''(x)\right]^2 \,\mathrm{d}x\,, \qquad (24.1)$$

where E is Young's modulus, L is the length of the beam, and $I = wt^3/12$ is the areal moment of inertia; t and w are the beam thickness and width. The main approximation we have made in writing (24.1) is that the cross section of the beam remains unchanged by the bending process. The surface contribution to the total energy is associated with the changes of the areas of the upper and lower surfaces by virtue of the beam deforming. In particular, we have

$$\begin{aligned} E_{\text{surf}}[u(x)] = {} & \gamma_{\text{up}} w \left[L - \frac{t}{2}\int_0^L u''(x)\,\mathrm{d}x\right] \\ & + \gamma_{\text{down}} w \left[L + \frac{t}{2}\int_0^L u''(x)\,\mathrm{d}x\right]\,, \end{aligned} \qquad (24.2)$$

where the terms in parentheses are the arc lengths along the top and bottom surface of the beam, respectively. The physical content of this functional is the idea that if $u'' > 0$ (concave upward) then the upper surface area will shrink while the lower surface area will increase. Neglecting uninteresting constant terms, the total energy functional is

$$\begin{aligned} E_{\text{tot}}[u(x)] = {} & \frac{EI}{2}\int_0^L \left[u''(x)\right]^2 \,\mathrm{d}x \\ & + \frac{tw}{2}(\gamma_{\text{down}} - \gamma_{\text{up}})\int_0^L u''(x)\,\mathrm{d}x\,. \end{aligned} \qquad (24.3)$$

Our goal is to find the displacement profile $u(x)$ that yields the minimum value for the total energy. The general mathematical framework for effecting this minimization is the calculus of variations. For the functional in (24.3), a more direct route to the result can be obtained by completing the square. Namely, we note that the E_{tot} involves a term quadratic in $u''(x)$ and a second term that is linear in the same function. As a result, the total energy can be rewritten in the form

$$E_{\mathrm{tot}}[u(x)] = \frac{EI}{2} \int_0^L \mathrm{d}x \left[u''(x) + \frac{tw\Delta\gamma}{2EI} \right]^2 , \quad (24.4)$$

where we have introduced $\Delta\gamma = \gamma_{\mathrm{down}} - \gamma_{\mathrm{up}}$, and we neglect an uninteresting constant term. Clearly the $u(x)$ that minimizes the energy is one for which the integrand vanishes everywhere, or

$$u''(x) + \frac{tw\Delta\gamma}{2EI} = 0 . \quad (24.5)$$

At this point, we are left with a standard differential equation whose solution, given the boundary conditions $u(0) = 0$ and $u'(0) = 0$, is

$$u(x) = -\frac{tw}{4EI} \Delta\gamma x^2 . \quad (24.6)$$

The physical meaning of this solution is hinted at by observing that if $\gamma_{\mathrm{down}} > \gamma_{\mathrm{up}}$ then the beam curves downward with the result that the area of the lower surface is reduced.

Measurements of *Wu* et al. [24.31] indicate an upward cantilever deflection when single stranded DNA (ssDNA), up to 20 nucleotides in length, hybridizes with complementary strands of ssDNA, which were deposited initially so as to functionalize the beam. This effect might be attributed to the difference in elastic properties of ssDNA and its double stranded counterpart. Namely, under physiological conditions, ssDNA has a persistence length equal to two nucleotides, while dsDNA is much stiffer (due to hydrogen bonding and base stacking interactions between the two strands) and has a persistence length of 150 nucleotides. Therefore, deposition of the flexible ssDNA molecules initially leads to bending of the cantilever downward due to entropic repulsion between the ssDNA chains. After hybridization, rigid dsDNA strands are formed, there is no longer any entropy to be gained by increasing the area of the top surface, and the beam bends back upwards. Remarkably, *Wu* et al. demonstrate that their biofunctionalized cantilever is sensitive to ssDNA differing in length by a single nucleotide!

To gain further insight into the physics of the biofunctionalized cantilever, it is instructive to examine some quantitative aspects of the experiment using (24.6). Namely, *Wu* et al. find a deflection of $u(L) = 12\,\mathrm{nm}$ when a 20-nucleotide strand of ssDNA hybridizes with a 20-nucleotide-long complementary target. Using the quoted numbers for the cantilever, $E = 180\,\mathrm{GPa}$, $L = 200\,\mu\mathrm{m}$, $t = 0.5\,\mu\mathrm{m}$, $w = 20\,\mu\mathrm{m}$, leads to $\Delta\gamma = 4.5\,\mathrm{fJ}/\mu\mathrm{m}^2$. From this result we can estimate the change in surface free energy due to beam bending,

$$\Delta E_{\mathrm{surf}} \approx wL\Delta\gamma . \quad (24.7)$$

We find $\Delta E_{\mathrm{surf}} = -18\,\mathrm{pJ}$, which, given the quoted areal chain density of $6 \times 10^{12}\,\mathrm{cm}^{-2}$, leads to a decrease in free energy of 75 pN nm, or $18\,k_{\mathrm{B}}T$, per chain. This is comparable to the entropy of a 20 nt ssDNA, which is on the order of $10\,k_{\mathrm{B}}$, lending support to the idea that entropic repulsion between ssDNA strands is implicated in cantilever bending.

While this example gives a feel for the way in which quantitative models have been put forth to respond to biologically inspired nanotechnologies, the remainder of the chapter will emphasize attempts to construct nanomechanical models of biological nanotechnology itself. We turn first to a discussion of the various scales that arise in thinking about the biology-nanotechnology interface and then conclude with several modeling examples.

24.2 Scales at the Bio-Nano Interface

Every scientific discipline has a preferred set of units that lends itself to building intuition concerning the system at hand. For example, an astronomer thinks of distances between stars in light years, not kilometers. Though most of us have an intuitive sense of the meaning of a kilometer, by the time we add more than six zeros, all intuition is lost. At terrestrial scales, we talk of distances between cities in terms of the flying time or the driving time between them and usually not in terms of hundreds of miles. Similar choices must be faced in the biological setting. For example, a biologist might characterize the complexity of an organism by the size (in kilo basepairs) of the genome and not by the organism's physical size. The aim of the present section is to highlight some of the key scales and units that reveal themselves at the interface between biology and nanotechnology. Indeed, we go further and assert that as yet we are still in the process of searching for the most suitable units to characterize the biology-nanotechnology interface. Although our attempt to determine such units and scales might involve seemingly complicated interconversions, such as measuring distances in terms of time (via diffusion), or measuring concentrations in terms of distances, we hold that the approximate *numerical* characterization of the scales of interest is of crucial importance to the endeavor of considering nanomechanics at the biology-nanotechnology interface. In particular, the right choice of units can assist us in building intuition about these systems. Our goal in this section is to emphasize the scales in length, time, force, energy, and power that are relevant in contemplating the nanomechanics of biological systems.

24.2.1 Spatial Scales and Structures

We begin with a discussion of the length scales that arise in contemplating nanomechanics at the biology-nanotechnology interface. In this case, the prefix *nano* leads justifiably to a consideration of the nanometer as one possible choice as the fundamental unit of length. However, to prepare ourselves for the question of how best to describe the dimensions of the spatial structures of interest here, it is important to consider the *hierarchy* of length scales that arise in the nano-bio arena. After examining this hierarchy of structures, we reformulate these length scales in terms of the volumes of these structures measured in units of the volume of a typical bacterial cell, and conclude the present section with a discussion of the way that chemical concentrations can also be interpreted as determining a length scale.

As noted above, a first step in developing intuition concerning the spatial scales found at the biology-nanotechnology interface is through reference to the hierarchy of scales and structures that arise in this arena. The shortest distance in this hierarchy of scales that will interest us is that associated with the size of individual atoms. We recall that the size of a hydrogen atom is roughly 0.1 nm. The scale characterizing the linkage between atoms is that of typical bond lengths that range from roughly 0.1–0.3 nm. A step further in this hierarchy brings us to the basic building blocks of the biological world such as amino acids, nucleotides, individual sugars, lipid molecules, etc. A typical length scale that characterizes these building blocks is the nanometer itself. For example, we have already made reference to the importance of lipid-bilayer membranes in bounding different regions of the cell. Phosphatidylcholine is one of the molecular building blocks of many such membranes. It has a polar head group and a hydrocarbon tail with an overall dimension of 2–3 nm. Similarly, the dimensions of single amino acids and nucleotides are on the order of 1 nm as well.

As is well-known, individual nucleotides are assembled to form nucleic acids such as DNA, amino acids are assembled to form proteins, sugars combine to form polysaccharides, and lipids self-assemble to form membranes. One way of estimating the size of the resulting molecules is by taking the scale of the individual units and scaling up with the number of such units. The various molecular actors of relevance to the present discussion can also be characterized by a length, scale known as the persistence length, which gives a rough description of the length over which the molecule behaves as a stiff rod. For example, the persistence length of DNA is ≈ 50 nm, while that of the cytoskeletal filaments is in the range of 15 μm for actin and 6 mm for microtubules [24.11]. We note that in our later discussions of viruses as a profound example of biological nanotechnology, the ratio of the persistence length of DNA to the size of the viral capsid (the container within which the DNA is packaged) will serve as a measure of the energetic cost of packing the DNA within the capsid and will signal the need for molecular motors to take active part in the packaging process.

The next scale above that of the various macromolecular building blocks are assemblies of such molecules in the form of various molecular machines which are some of the most compelling examples of nature's nanotechnology. The ability to begin formulating mechanistic models of such machines is founded upon key advances in both X-ray crystallography and cryo-electron microscopy [24.33, 34]. Examples of such machines and their associated dimensions include: the machine responsible for making the message carried by DNA readable by the protein synthesis machinery, namely, RNA polymerase (≈ 15 nm) [24.35], the machine that produces ATP, the energy currency of the cell, namely, ATPsynthase (≈ 10 nm) [24.9], and the machine that carries out protein synthesis, namely, the ribosome (≈ 25 nm) [24.36]. A second class of assemblies of particular relevance to the present article are viruses, representative examples of which include lambda phage (≈ 27 nm), tobacco mosaic virus (≈ 250 nm in length), and the HIV virus (≈ 110–125 nm) [24.37].

From the standpoint of cellular function, the next level of structural organization is associated with the various organelles within the cell, structures such as the cell nucleus (3–10 μm), the mitochondria that serve as the power plant of the cell (≈ 1,000 nm), the Golgi apparatus wherein modifications are made to newly synthesized macromolecular components (≈ 1,000 nm), and so on [24.1]. These organelles should be thought of as factories in which many molecular motors of the type described earlier do their job simultaneously. At larger scales yet, and constituting a higher level of overall organization, life as nanotechnology is revealed as cells themselves, the fundamental unit of life that is self-replicating and self-sustaining. We will make special reference to one particular bacterial cell, namely, *E. coli* with typical dimensions of 1 µm. This should be contrasted with a typical eucaryotic cell such as yeast, which has linear dimensions roughly a factor of 10 larger than the *E. coli* cell.

We note that the various biological structures described above should be seen with reference to the sorts of man-made structures to which they are interfaced. For example, earlier in the chapter we mentioned the importance of optical tweezers as a means of communicating forces to macromolecules and their assemblies. Typical dimensions for the optical beads used in optical tweezers are on the scale of 500–1,000 nm. We note that though such dimensions are characteristic of organelles, they are much larger than the individual molecules they are used to study. A second way in which individual macromolecules are communicated with is through small tips such as those found on an AFM. In this case, the size of the tip can be understood through reference to its radius of curvature, which is typically of the order of 50 nm.

Our discussion thus far has centered on the use of a single characteristic length to describe the spatial extent of biological structures. In our quest to develop intuition about the typical spatial scales found at the biology-nanotechnology interface we note that a second way to evaluate such scales is through reference to the typical *volumes* of the various structures of interest. As noted in the introduction to this section, we claim that a key way to develop intuition is by making sure to use appropriate and revealing units. For the present purposes, we argue that one useful unit of volume is that of an *E. coli* bacterium, which if idealized as a cylinder with diameter 1 µm and height 2 µm, has a volume of $\approx 1.5 \times 10^9$ nm^3. In particular, we will measure the sizes of the various entities described above in terms of how many of them can fit into a single *E. coli* bacterium. Our estimates of the comparative sizes of various structures of interest are given in Table 24.1. Note that we do not claim that this is literally how many of each of these entities are found in an *E. coli* bacterium, but rather we seek to give an impression of the relative volumes of some of the different structures that arise when contemplating biological nanotechnology.

Table 24.1 Sizes of entities in comparison to the size of *E. coli*

Entity	Size (nm)	# fitting in an *E. coli*
Amino acid	1	5.0×10^9
Nucleotide	1	5.0×10^9
Monosaccharide	1	5.0×10^9
Phosphatidyl choline	2–3	2.0×10^8
Proteins	5–6	3.0×10^7
Ribosome	20	1.0×10^6
Mitochondria	500–1,000	3–4
T4 phage	100	5,000

The idea of counting the number of molecules that fit into a given volume is actually quite standard. This is exactly what chemists do when they invoke the notion of concentration: measuring the strength of an acid or base using pH amounts to expressing the concentration of H^+ ions in solution. Similarly, when we refer to the molarity of a given solution, it is a statement of how many copies of a given molecule will be found per liter of solution. These ideas are pertinent for our examination of the scales that arise in contemplating biological nanotechnology. As an example, we consider the action of molecular pumps such as that which maintains the concentration gradient in Ca^{2+} ions between the cellular interior and the extracellular medium. Note that this is described in detail in chapter 12 of *Alberts* et al. [24.1]. The Ca^{2+} pump is responsible for insuring that the intercellular concentration of Ca^{2+} ions is 10^{-7} smaller than that in the cellular exterior. One explanation for this low a concentration of Ca^{2+} in the cell is the role played by these ions in signaling other activities. The low concentration might serve as a scheme for increasing the signal-to-noise ratio. The reported intracellular concentration of such ions is roughly 10^{-7} mM. It is interesting to ask how many Ca^{2+} ions this corresponds to in a eucaryotic cell. The volume of a eucaryotic cell measuring 20 µm in diameter is about 4×10^{-12} liters, which translates into ≈ 250 Ca^{2+} ions in the cytoplasm. For the case of *E. coli*, which has a volume approximately 1,000 smaller, this concentration would correspond to one ion for every four cells. This number gives us far greater insight than the standard molar ($M = $ mol/liter) method of expressing concentrations. In a similar vein, we argue that distances between individual ions/molecules in solution are perhaps a better way of thinking about pH and molarity when using them in the context of biological nanosystems. To this end, Fig. 24.5 shows a plot of pH and molarity versus average distance d in nm between individual ions/molecules. Note that, in addition, we have also translated these concentrations into number of copies per *E. coli* cell and the time for an ion to diffuse over the average separation distance. For the time estimate we make use of the typical diffusion constant for small ions in water at 25 °C, $D = 2{,}000\,\mu\text{m}^2/\text{s}$.



Fig. 24.5 **(a)** Representations of pH in terms of average distance between ions (d in nm), the number of ions per one *E. coli* cell volume (N), and the typical time for an ion to diffuse over a distance equal to their average separation (t in 100 ns). **(b)** Concentration unit millimolar (mM) represented in terms of d (nm), N (millions of molecules), and t (10 ns)

We have seen that the world of biological nanotechnology utilizes length scales that span a rather wide range, from fractions of a nanometer to tens of microns. This provides a challenge to modeling, whereby methods with atomic-scale resolution need to be combined in a consistent and seamless way with coarse-grained continuum descriptions to provide a complete picture. An example of such modeling will be provided in later sections when we take up the mechanical aspect of the viral life cycle.

24.2.2 Temporal Scales and Processes

We have seen that a study of spatial scales is a first step in our quest to understand the units that are suited to characterizing the biology-nanotechnology interface. We note that our understanding of spatial structures both in the living world, as well as those used in intriguing man-made technologies such as microelectronics have been built around important advances such as electron microscopy, X-ray crystallography, nuclear magnetic resonance, etc. that have revolutionized structural biology and materials science alike. On the other hand, one of the key challenges that remain in really appreciating the structure-properties paradigm, which is as central to biology as it is to materials science, is the need to acknowledge the dynamical evolution of these structures.

We note that just as there is a hierarchy of spatial scales that are important to consider in describing biological nanotechnology, so too is there a hierarchy of *temporal processes* that also demand a careful consideration of relevant units. An impressive representation of the temporal hierarchy that must be faced in contemplating biological systems is given by *Chan* and *Dill* [24.38] in their Fig. 5. They organize their temporal hierarchy according to factors of 1,000, starting at the femtosecond time scale and ending with time scales representative of the cell cycle itself. One of the elementary dynamical processes undergone by all of the molecular actors of the living world is thermal vibration. Vibrations of atoms occur at the time scales of 10^{-15} to 10^{-12} s. As will be noted later, from a modeling perspective, this depressing fact manifests itself in the necessity of using time steps of the same order when integrating the equations of motion describing molecular dynamics. The reason that this is unfortunate is that almost everything of dynamical interest occurs at time scales much longer than the femtosecond time scale characteristic of molecular jiggling, thus making molecular dynamics investigations computationally very expensive.

We follow *Chan* and *Dill* [24.38] in examining how successive thousandfold increases in our temporal resolution smears out features such as vibrational motion and brings into focus more interesting processes characteristic of macromolecular function. Indeed, the side chains of amino acids rotate with a characteristic period on the order of 10^{-9} s. Another thousandfold increase in time scale begins to bring key biological processes such as polymerization into view. Just as a length scale on the order of 10–100 nm is perhaps most characteristic of the length scales of biological nanotechnology, the time scale that is most relevant for considering the processes associated with biological nanotechnology is something between a microsecond and a millisecond. To drive home this point, we reconsider the machines described in the previous section from the length scale perspective, but now with an eye toward how fast they perform their function. Several of the molecular machines considered in the previous section mediate polymerization reactions. For example, RNA polymerase produces messenger RNA molecules by the repeated addition of nucleotides to a chain of ever increasing length. Such messenger RNA molecules serve in turn as the template for synthesis of new proteins by the ribosome, which reads the message contained in the RNA and adds individual amino acids onto the protein. From the temporal perspective of the present section, it is of interest to examine the rate at which new monomers are added to these polymers – roughly 10 per s in the case of RNA polymerase [24.39], and 2 per s in the case of the ribosome in eucaryotic cells [24.1] (bacterial ribosomes are 10 times faster). Once proteins are synthesized, in order to assume their full cellular responsibilities, they must fold into their native state, a process that occurs on time scales on the order of a millisecond.

In addition to translational machines like RNA polymerase and the ribosome, there are a host of intriguing rotary machines such as ATP synthase and the flagellar rotary motor. The flagellar motor, which is the means of locomotion for several bacteria, rotates at about 100 rpm [24.6]. ATP synthase makes use of a proton gradient across a lipid bilayer to provide rotation at a rate of roughly 6,000 rpm [24.41], approaching that of turbojet engines.

Thus far, our discussion has emphasized the rate of a variety of active processes of importance to biological nanotechnology. It is of interest to contrast these scales with those pertaining to diffusion. We note that in many instances in the biological setting the time scale of interest is that determined by the time it takes for diffusive communication of two spatially separated regions. In particular, as noted earlier in the chapter, the operative time scale is given by $t_{\text{diffusive}} = x^2/2D$, where D is the diffusion constant and x is the distance over which the diffusion has taken place.

To get a sense for all of the time scales described in this section, Table 24.2 presents a variety of results considered above in tabular form, but now with all times measured in units of the time it takes for ATPsynthase to make one rotation (≈ 10 ms). Our reason for adopting ATPsynthase rotation as defining a unit of time is that it exhibits motions associated with one of the most important of life's processes, namely, the synthesis of new ATP molecules. In addition, our later discussion of units associated with both energy and power will once again appeal to the central role played by ATP in biological nanotechnology.

24.2.3 Force and Energy Scales: The Interplay of Deterministic and Thermal Forces

Another set of scales of great relevance and importance to the nano-bio interface concerns the nature of the forces that act in this setting. Thus far, we have examined the spatial extent and the cycle time of a variety of examples of biological nanotechnology. As a next step in our examination of scales, we consider the forces

Table 24.2 Time scales of various events in biological nanotechnology measured in units of the average time taken for ATPsynthase to make a single rotation

Process	Time scale (units of ATPase rotation)	Ref.
1/(frequency of amino acid addition) – eukaryotic ribosome	50	[24.1]
1/(frequency of monomer addition) – RNA polymerase	10	[24.39]
Time between motion reset of *E. coli*	10	[24.6]
Kinesin step	1	[24.26]
Diffusion time for protein (ion) to cross an *E. coli*	0.5 (0.02)	[24.11]
Vibrational period of nanocantilever	10^{-3}–10^{-5}	[24.40]

and energies associated with these structures. Two outstanding sources for developing a feel for the relevant numbers are the books of *Wrigglesworth* [24.42] and *Smil* [24.43]. Perhaps the most compelling feature when thinking about forces at these scales is the interplay between deterministic and thermal forces. To substantiate this claim, we note that at room temperature the fundamental energetic quantity is $k_BT \approx 4.1$ pN nm. The reason this number is of interest to the current endeavor is the realization that many of the molecular motors that have thus far been investigated act with forces on the piconewton scale over distances of nanometers.

The fact that the piconewton is the relevant unit of force can be gleaned from a simple estimate. Namely, consider a typical skeletal muscle in the human arm. The cross-sectional size of the muscle is of order 3 cm. The muscle consists of cylindrical rods of protein called myofibrils, which are roughly 2 μm in diameter, while the myofibrils themselves are made of strands of actin and myosin filaments, which total some 60 nm in diameter [24.1]. This gives 10^{12} myosin filaments per cross-sectional area of the muscle. As each myosin filament over the length of a single sarcomere (the contractile unit of myofibrils, some 2.5 μm long) contains some 300 myosin heads, lifting a 30 kg load corresponds to a force of 1 pN per myosin head. This is certainly an underestimate, since not all myosin heads are attached to the actin filament at the same time. Since our estimate leaves out many details, we might wonder how it compares to the measured forces exerted by molecular motors. Sophisticated experiments with optical tweezers have revealed that actin-myosin motors stall at a force of around 5 pN [24.44]; RNA polymerase stalls at a force of about 20 pN [24.39]; the portal motor of the ϕ-29 bacteriophage exerts forces up to 50 pN [24.29].

As noted earlier, RNA polymerase is a molecular motor that moves along DNA while transcribing genes into messenger RNA. The DNA itself is an elastic object that is deformed by forces exerted on it by various proteins. At forces less than 0.1 pN its response is that of an entropic spring with a stretch modulus of 0.1 pN, while at forces exceeding 10 pN its stretch modulus is determined by hydrogen bonding of the base pairs and is roughly 1,000 pN [24.45]. All the above mentioned data reinforces the argument that piconewton is the relevant unit of force in the nanomechanical world of the cell.

The concept of "stress" is closely related to that of force. Stress is a continuum mechanical concept of force per unit area, and it has been used with great success in solid and fluid mechanics. We extend the idea of stress to the nanomechanical level to see what numbers we arrive at. From the data above we can deduce that a single myosin fiber sustains a stress of about 10^{-2} pN/nm^2, which is the same as 10^{-2} MPa. Migratory animal cells such as fibroblasts, which are responsible for scavenging and destroying undesirable products in tissues, can generate a maximum stress on their substrate on the order of 3.0×10^{-2} MPa [24.46]. DNA can sustain stresses in the excess of 20 pN/nm^2, or 20 MPa, at which point an interesting structural transition accompanied by an overall increase of its contour length is observed [24.45]. Engineering materials such as steel and aluminium, on the other hand, can sustain stresses of about 100 MPa. This goes to show that nanotechnology in the context of biological systems is built from rather soft materials.

It is of interest to translate our intuition concerning piconewton forces into corresponding energetic terms. The kinesin motor advances 8 nm in each step against forces as high as 5 pN [24.25]. This translates to a work done on the order of 40 pN nm. A myosin motor suffers displacements of about 15 nm with forces in the piconewton range. ATP hydrolysis (to ADP) releases energy (at pH 7 and room temperature) of about 50 pN nm [24.1]. When a titin molecule is pulled, it unfolds under forces of 30–300 pN, causing discrete expansions of 10–30 nm [24.22], implying energies in the range of 300–9,000 pN nm. Experimental data provides a compelling argument in favor of thinking of the pN nm as a unit of energy for nanomechanics. However, the observation that $k_BT = 4.1$ pN nm at room temperature gives important insight, since it reveals that thermal forces and entropic effects play a competing role in biological nanomechanics. This provides nature with unique design challenges, whereby molecular motors that can perform useful work must do so in the presence of strong thermal fluctuations for the normal functioning of the cell. Operation of motors in such a noisy environment is governed by laws that are probabilistic in nature. This is manifest in single molecule experiments that observe motors stalling and sometimes reversing direction.

Energy conversion is crucial to any developmental or evolutionary process. The steam engine powered the industrial revolution. However, long before thinking beings with man-made machines founded the industrial revolution, power generation had already become a central part of life's nanotechnology. Indeed, the development of ATP-synthase is one of the cornerstones for the evolution of higher life-forms. An inevitable concomitant of evolution is the necessity for faster and more efficient operations. The industrial revolution led to the emergence of bigger and faster modes of transport; biological evolution led to the emergence of complex and intelligent organisms. Invariably, a machine or an organism is limited in its abilities by the speed at which it can convert one form of energy (usually chemical) to other forms of energy (usually mechanical). This is why a study of their "power plants" becomes important.

Power plants (or engines) are usually characterized by their force-velocity curves and compared using their power-to-weight (P/W) ratio. For example, the myosin motor has a P/W ratio of 2×10^4 W/kg, the bacterial flagellar motor stands at 100 W/kg, an internal combustion engine is at about 300 W/kg, and a turbojet engine stands at 3,000 W/kg [24.47]. These figures tell us that linear motors like myosin and kinesin are extremely powerful machines.

24.3 Modeling at the Nano-Bio Interface

We have already provided a number of different views of the biology-nanotechnology interface, all of which reveal the insights that can emerge from model building. Indeed, one of the key thrusts of this entire chapter is the view that as the type of data that emerges concerning biological systems becomes increasingly quantitative, it must be responded to with models that are also quantitative [24.30]. The plan of this section is to show how atomistic and continuum analyses each offer insights into problems of nanotechnological significance, but under some circumstances, both are found wanting and it is only through a synthesis of both types of models that certain problems will surrender. The plan of this section is to examine the advantages and difficulties associated with adopting both atomistic and continuum perspectives and then to hint at the benefits of seeking mixed representations.

24.3.1 Tension Between Universality and Specificity

One of the key insights concerning model building in nanomechanics, whether we are talking about the nanoscale tribological questions pertinent to magnetic recording or the operations of molecular motors, is that such questions live in the no-man's-land between traditional continuum analysis at one extreme and all-atom approaches such as molecular dynamics on the other. Indeed, there is much discussion about the breakdown of continuum mechanics in modeling the mechanics of systems at the nanoscale. This dichotomy between continuum theories, which treat matter as continuously distributed, and atomic-level models, which explicitly acknowledge the graininess of matter, can be restated in a different (and perhaps more enlightening) way. In particular, it is possible to see atomistic and continuum theories as offering complementary views of the same underlying physics. Continuum models are suitable for characterizing those features of a system that can be thought of as averages over the underlying microscopic fluctuations. By way of contrast, atomistic models reveal the details that a continuum model will never capture, and in particular, they shed light on the specificity of the problem at hand.

The perspective adopted here is that continuum models and atomistic models each reveal important features of a given problem. For example, in contemplating the competition between fracture and plasticity at crack tips, a continuum analysis provides critical insights into the nature of the elastic fields surrounding a defect such as a crack. These fields adopt a fundamental and universal form at large scales with all detailed material features buried in simple material parameters. By way of contrast, the precise details of the dissipative processes occurring at a crack tip (in particular, the competition between bond breaking with the creation of new free surface and dislocation nucleation) require detailed atomic-level descriptions of the energetics of bond stretching and breaking. In the biological setting, similar remarks can be made. In certain instances, the description of biological polymers as random coils suffices and yields insights into features such as the mean size of the polymer chain as a function of its length. On the other hand, if our objective is mechanistic understanding of processes such as how phosphorylation of a particular protein induces conformational change, this is an intrinsically atomic-level question. The language we invoke to describe this dichotomy is the use of the terms *universality* and *specificity*, where, as described above, insights of a universal character refer to those features of systems that are generic, while specificity refers to the features of systems that depend upon precise details such as whether or not a particular molecule is bound at a particular site. This fundamental tension between atomistic and continuum perspectives is elaborated in *Phillips* et al. [24.48].

24.3.2 Atomic-Level Analysis of Biological Systems

As already described in the introduction, one of the intriguing roles of nanotechnology in the biological setting is that it has brought the Instron technology of traditional solid mechanics to the nanoscale and has permitted the investigation of the force-extension characteristics of nanoscale systems (macromolecules and their assemblies, in particular). As noted earlier, mechanical force spectroscopy [24.20] is emerging as a profound tool for exploring the connection between structure, force, and chemistry, in much the same way that conventional stress-strain tests provided insights into the connection between structure and properties of conventional materials. Figure 24.3 gives one such example in the case of the muscle protein titin. Similar insights have been obtained through systematic examination of the force-extension properties of DNA [24.49].

The objective of this section is to call the reader's attention to the types of modeling that can be done from an all-atom perspective. What exactly is meant by a model in this setting? We begin by noting that for the purposes of the general discussion given here, the same basic ideas are present whether one is modeling tribological processes such as the sliding of adjacent surfaces, or attempting to examine the operation of a protein machine such as ATPsynthase. The set of degrees of freedom considered by the atomic-scale modeler is the full set of atomic positions ($\boldsymbol{R}_1, \boldsymbol{R}_2, \cdots \boldsymbol{R}_N$), which we also refer to as $\{\boldsymbol{R}_i\}$. For most purposes, one proceeds through reference to a *classical* potential energy function, $E_{\text{tot}}(\{\boldsymbol{R}_i\})$, which is a rule that assigns an energy for every configuration $\{\boldsymbol{R}_i\}$. While it would be most appealing to be able to perform a full quantum mechanical analysis, such calculations are computationally prohibitive. Given the potential energy, the forces on each and every atom can be computed where, for example, the force in the αth Cartesian direction on the ith atom is given by

$$F_{i,\alpha} = -\frac{\partial E_{\text{tot}}}{\partial R_{i,\alpha}} \,. \tag{24.8}$$

For those interested in finding the energy minimizers, such forces can be used in conjunction with methods such as the conjugate gradient method or the Newton–Raphson method. Alternatively, many questions are of a dynamic character, and in these cases, Newton's equations of motion are integrated, thus permitting an investigation of the temporal evolution of the system of interest. We note that we have neglected to discuss subtleties of how one maintains the system at constant temperature, and we leave such subtleties to the curious reader, who can learn more about them in *Frenkel* and *Smit* [24.50].

To give a flavor of where such calculations can lead we note that the same force-extension characteristics already shown in Fig. 24.3 have been computed in a molecular dynamics simulation [24.51]. One of the insights to emerge from these calculations was the particular dynamical pathway, namely, the breaking of a particular collection of hydrogen bonds during the rupture process of each of the immunoglobulin domains. We further note that in the case of titin there has been an especially pleasing synergy between the atomic-scale calculations and the corresponding force-extension measurements. In particular, in response to the suggestion that it was a particular set of hydrogen bonds that were impugned in the rupture process, mutated versions of the titin protein were created in which the number of such hydrogen bonds was changed with the result that the rupture force was changed according to expectation [24.52]. This can be seen as a primitive example of the ultimate goal of tailoring new materials (both biological and otherwise) through appropriate computer modeling.

24.3.3 Continuum Analysis of Biological Systems

We have already noted that there are many appealing features to strictly continuum analyses of material systems. In particular, models based upon continuum mechanics result in a mathematical formulation that permits us to uncork the traditional tools associated with partial differential equations and functional analysis. In keeping with our argument that it is the role of models to serve our intuition, the ability to write down continuum models raises the possibility of obtaining analytic solutions to problems of interest, an eventuality that is nearly impossible once the all-atom framework has been adopted.

Macromolecules as Elastic Rods

Whether we contemplate the information carrying nucleic acids, the workhorse proteins, or energy storing sugars, ultimately, the molecular business of the living world is dominated by long chain molecules. For the model builder, such molecules suggest two complementary perspectives, each of which contains a part of the whole truth. On the one hand, polymer physicists have gained huge insights [24.53] by thinking of long chain molecules as random walks. Stated simply, the key virtue of the random-walk description of long chain molecules is that it reflects the overwhelming importance of entropy in governing the geometric conformations that can be adopted by macromolecules. The other side of the same coin considers long chain molecules as elastic rods with a stiffness that governs their propensity for bending. We will take up this perspective in great detail in the final section of this chapter when we consider the energetics of DNA packaging in viruses.

For our present purposes, we examine one case study in treating macromolecules as elastic rods. The example of interest here is chosen in part because it reflects another fascinating aspect of biological nanotechnology, namely, regulation and control. It is well-known that genes are switched on and off as they are needed. These topics are described beautifully in the work of *Ptashne* [24.54]. The basic idea can be elucidated through the example of a particular set of genes in *E. coli*: the *lac* operon. There are a set of enzymes exploited by this bacterial cell when it needs to digest the sugar lactose. The gene that codes for these enzymes is only turned on when lactose is present and certain other sugars are absent. The nanotechnological solution to the problem of regulating this gene has been solved by nature through the presence of a molecule known as the *lac* repressor, which binds onto the DNA in the region of this *lac* gene and prevents the gene from being expressed. More specifically, the *lac* repressor binds onto two different regions of the DNA molecule simultaneously, forming a loop in the intervening region, and thus rendering that region inoperative for transcription.

We have belabored the difficulties that attend the all-atom simulation of most problems of nanotechnological interest – system sizes are too small and simulated times are too short. On the other hand, clearly it is of great interest to probe the atomic-level dynamics of the way that molecules such as *lac* repressor interact with DNA and thereby serve as gene regulators. A compromise position adopted by *Balaeff* et al. [24.55] was to use elasticity theory to model the structure and energetics of DNA, which then served effectively as a boundary condition for their all-atom calculation of the properties of the *lac* repressor/DNA complex. The simulation cell is shown in Fig. 24.6, which also shows the looped region of DNA that serves as a boundary condition for the atomic-level model of the complex.

Membranes as Elastic Media

One way to classify biological structures is along the lines of their dimensionality. In the previous discussion, we examined the sense in which many of the key macromolecules of the living world can be thought of as one-dimensional rods. The next level in this dimensional hierarchy is to consider the various membranes that compartmentalize the cell and which can be examined from the perspective of two-dimensional elasticity. Just as there are a huge number of modeling questions to be posed concerning the structure and function of long chain molecules such as nucleic acids and proteins, there is a similar list of questions that attend the presence of a host of different membranes throughout the cell. To name a few, we first remind the reader that such membranes are full of various proteins that serve in a variety of different capacities, some of which depend upon the mechanical state of the membrane itself. In a different vein, there has been great interest in examining the factors that give rise to the equilibrium shapes of cells [24.56, 57]. In both instances, the logic associated



Fig. 24.6 Illustration of the way that the properties of a particular DNA-protein binding interaction were modeled by virtue of an elastic treatment of the looped region of the DNA [24.48]

with building models of these phenomena centers on the construction of an elastic Hamiltonian that captures the energetics of deformations expressed in terms of surface area, curvature, and variations in thickness. Also, just as there has been great progress in measuring the properties of single proteins and nucleic acids, there has been considerable progress in examining the force response of membranes as well [24.58].

The prospect of bringing the tools of traditional continuum theory to bear on problems of biological significance is indeed a daunting one. As noted earlier, to our way of thinking one of the biggest challenges posed by biological problems is the dependence of these systems on detailed molecular structures and dynamics – what we have earlier characterized as "specificity", one of the hallmarks of biological action.

24.4 Nature's Nanotechnology Revealed: Viruses as a Case Study

Over the course of this chapter, we have presented different facets of the relationship between biology and nanotechnology and the modeling challenges they encompass. For example, we have noted that two key aspects of nature's nanotechnologies are the exploitation of self-assembly processes for the construction of molecular machines and the role of active processes mediated by molecular motors. We have also argued for the synergistic role of nanotechnology in producing new methods for the experimental analysis of biological systems with examples ranging from new molecular dyes to the use of optical tweezers. Finally, we have described some of the modeling challenges posed by contemplating the biology-nanotechnology interface and the sorts of coarse-grained models that have arisen to meet these challenges. In this final section, we present a discussion of viruses as a case study at the confluence of these different themes.

Though the importance of viruses from a health perspective are well-known even to the casual observer, they are similarly important both from the technological perspective (as will be explained below) and as a compelling and profound example of nature's nanotechnology par excellence. To appreciate the sense in which viruses serve as a compelling example of biological nanotechnology, we begin by reviewing the nature of the viral life cycle with special reference to the case of bacterial viruses (i. e., viruses that infect bacteria), known as bacteriophages. For concreteness, we consider the life cycle of a bacteriophage such as the famed lambda phage that infects *E. coli*. The life cycle of such viruses is shown schematically in Fig. 24.7. Upon an encounter with the *E. coli* host, the virus attaches to a receptor (protein) embedded in the bacterial membrane and ejects its DNA into the host cell, leaving an empty capsid as refuse from the process. As an aside, it is worth noting that experiments such as the famed Hershey–Chase experiment used tagged DNA and tagged proteins on viruses to settle the question of whether proteins or nucleic acids are the carriers of genetic information. The outcome of these experiments was the conclusion that DNA is the genetic material. For the purposes of the present discussion, the other interesting outcome of the Hershey–Chase experiment is that it provides insights into the mechanistic process associated with delivery of the viral genome.



Fig. 24.7 Schematic representation of the viral life cycle illustrating the various nanotechnological actions in this cycle. During the infection stage, the viral genome is delivered to the victimized bacterial cell. During the process labeled DNA replication and protein synthesis, the machinery of the host cell is enlisted to produce renegade DNA and proteins to be used in the assembly of new viral particles. The capsid assembly process involves the attachment of the various protein building blocks that make up the capsid. DNA packing refers to the active packaging of DNA into the newly formed capsids by a molecular motor. Finally, once the assembly process is complete, the infectious phage particles are released from the victimized cell to repeat their infectious act elsewhere

Once the viral genome has been delivered to the host cell (we now oversimplify), the replication machinery of *E. coli* is hijacked to do the virus' bidding. In particular, the genes coded for in the viral DNA are expressed, and the proteins needed to make copies of the phage particle (i. e., the ingredients for an eventual self-assembly process) are created. Interestingly, part of the gene products associated with this process are the components of the molecular motor, which is responsible for packaging the replicated viral DNA into the new protein capsids that will eventually become the next generation of viruses. Indeed, once assembled, this motor takes the replicated viral DNA and packs it into the viral capsid. Recall our insistence that another of the important themes presented by biological examples of nanotechnology is the huge role played by active processes that reflect mechanochemical coupling. Once the packaging process is completed, and the remaining parts of the self-assembly process have been effected (such as the attachment of the viral sheath and legs whereby the phage attaches to host cells), enzymes are released that breakdown the cell wall of the infected cell with the ultimate result that what started as a single bacteriophage has in less than an hour become on the order of 100 new phage particles ready to infect new cells.

As noted above, a second sense in which viruses are deserving of case study status in the current chapter is the role viruses such as lambda phage play in biotechnology itself. For example, from the standpoint of both cloning and the construction of genomic libraries, the use of viruses is commonplace. From a more speculative perspective, viruses are also drawing increasing attention from the standpoint of gene therapy (as a way of delivering DNA to specific locations) and, more generally, as small-scale containers. To substantiate these assertions, we briefly consider the construction of genomic libraries and the role played by viruses in these manipulations. We pose the following question: Given that the length of the human genome is on the order of 10^9 base pairs, how can one organize and store all of this genetic information for the purposes of experiments such as the sequencing of the human genome? One answer to this challenge is the use of bacteriophage to deliver phage DNA to *E. coli* cells, but with the subtlety that the delivered DNA fragments have ligated within them fragments of the human genome whose lengths are on the order of 10 kb (kb = kilo base-pairs). The particulars of this procedure involve first cutting the DNA into fragments of roughly 10 kb in length using a class of enzymes known as restriction enzymes. The result of this operation is that the original genome is now separated into a random collection of fragments. These fragments are then mixed with the original lambda phage DNA that has also been cut at a single site such that the genomic fragments and the lambda fragments are complementary. Using a second enzyme known as ligase, the genomic DNA is joined to the original lambda phage fragments so that the resulting DNA resembles the original lambda DNA, but now with a 10 kb fragment inserted in the middle. These cloned lambda DNA molecules are then packaged into the lambda phage using a packaging reaction (see the website www.stratagene.com for an example of these products). The resulting lambda phage, now fully packed with cloned DNA, are used to infect *E. coli* cells, and the cloned DNA, once in the bacterial cell, circularizes into a DNA fragment known as a plasmid. The plasmid is then passed from one generation of *E. coli* to the next. This is the so-called prophage pathway in which, unlike the lytic pathway shown in Fig. 24.7, the bacteriophage is latent and does not destroy the cell [24.1]. Note that different *E. coli* cells are infected with viruses containing different cloned fragments. As a result, the collection of all such *E. coli* cells constitute a library of the original genomic DNA.

We round out our introductory discussion on viruses with a discussion of the compelling recent experiments that have been performed to investigate the problem of viral packing and, similarly, how ideas like those described in this chapter can be used to model these processes. *Smith* et al. [24.29] used optical tweezers to measure the force applied by the packaging motor of the ϕ-29 bacteriophage during the DNA packaging process. In particular, they measured the force and rate of packaging as a function of the amount of DNA packed into the viral head with the result that as more DNA is packed, the resistive force due to the packed DNA increases, and the packing rate is reduced.

As noted above, the viral problem is interesting not only because it exemplifies many of the features of biological nanotechnology introduced throughout this chapter, but also illustrates the way in which model building has arisen in response to experimental insights. The various competing energies that are implicated in the DNA packing process have been described by *Riemer* and *Bloomfield* [24.59]. The energetics of viral packing is characterized by a number of different factors, including: i) the entropic-spring effect that causes the DNA in solution to adopt a more spread out configuration than that in the viral capsid, ii) the energetics of elastic bending, which results from inducing curvature in the DNA on a scale that is considerably smaller than the persistence length of $\xi_p \approx 50$ nm, and iii) those factors related to the presence of charge both on the DNA itself and in the surrounding solution. As shown by *Riemer* and *Bloomfield* [24.59], the entropic contribution is smaller by a factor of 10 or more relative to the bending energies and those mediated by the charges on the DNA and the surrounding solution, and hence we make no further reference to it. As a result, just like in earlier work [24.60, 61], we examine the interplay of elastic and interaction forces, though we neglect surface terms originating from DNA-capsid and DNA-solvent interactions.

We note that the viral packing process involves DNA segments with lengths on the order of 10 µm and takes place on the time scale of minutes. As a result, from a modeling perspective, it is clear that such problems are clearly out of reach of conventional molecular dynamics. As a result, we exploit a continuum description of the DNA packing process with the proviso that such models will ultimately need to be refined to account for the sequence dependence of the elasticity of DNA.

A mathematical description of the energetics of viral packing must account for two competing factors, namely, the energy cost to bend the DNA and place it in the capsid and the repulsive interaction between adjacent DNA segments that are too close together. The structural picture of the packaged DNA is inspired by experiments that indicate that the DNA is packed in concentric rings from large radii inwards [24.62–64]. The bending energy cost of accumulating hoops within the capsid is given by

$$E_{\mathrm{el}} = \pi \xi_{\mathrm{p}} k_{\mathrm{B}} T \sum_i \frac{N(R_i)}{R_i} \,, \tag{24.9}$$

where $N(R_i)$ is the number of hoops that are packed at the radius R_i [24.59]. The basic idea of this expression is that we are adding up the elastic energy on a hoop by hoop basis, with each hoop penalized by the usual energy cost to bend an elastic beam into a circular arc. The presence of $N(R_i)$ reflects the fact that because of the shape of the capsid, as the radius gets smaller the DNA can pack higher up into the capsid, thus increasing the number of allowed hoops. To make analytic progress with the expression for the stored elastic energy given above, we convert it into an integral of the form

$$E_{\mathrm{el}} = \frac{\pi \xi_{\mathrm{p}} k_{\mathrm{B}} T}{\sqrt{3} d_{\mathrm{s}}/2} \int_R^{R_{\mathrm{out}}} \frac{N(R')}{R'} \,\mathrm{d}R' \,. \tag{24.10}$$

The summation $\sum_i$ has been replaced by an integral $\int_R^{R_{\mathrm{out}}} \mathrm{d}R'/(\sqrt{3}d_{\mathrm{s}}/2)$, where the integration bounds are the inner and outer radii of the inner spool and $\sqrt{3}d_{\mathrm{s}}/2$ is the horizontal spacing between adjacent strands of the DNA. The geometrical factor $\sqrt{3}/2$ owes its presence to the hexagonal packing of the DNA strands. R is the radius of the innermost stack of hoops, R_{out} is the radius of the capsid, $N(R')$ is the number of hoops at radius R', d_{s} is the spacing between adjacent hoops, and ξ_{p} is the persistence length of DNA. We note that this expression is a manifestation of the first term in the energy functional in (24.3), used earlier in the context of the biofunctionalized cantilever and now specialized to the geometry of a partially filled capsid. Just as the energy functional in the cantilever context reflected a competition between different contributions to the total energy (in that case, elastic bending energy and surface terms), the DNA packing problem reflects a similar competition, this time between the elastic bending and the interactions between nearby DNA segments by virtue of the charge along the DNA. In particular, the interaction energy between the DNA hoops packed in the viral capsid scales with the length and is given by

$$E_{\mathrm{int}} = F_0 L (c^2 + c d_{\mathrm{s}}) \exp(-d_{\mathrm{s}}/c) \,, \tag{24.11}$$

where c and F_0 are constants for a given solvent and L is the length of the packed DNA. This form of the interaction energy was shown to be very robust for a variety of solvents containing monovalent and divalent cations in a series of experiments by *Rau* et al. [24.65, 66] and *Parsegian* et al. [24.67]. The forces arising from this kind of an energy are purely repulsive in character. Interestingly, in this setting, rather than using temperature as a control parameter, it is much more common to change the circumstances in such experiments by tuning concentrations of various chemical constituents. In particular, when trivalent or tetravalent cations are present in solution there is an effective attractive interaction between DNA segments. In that case, the forces are repulsive only when d_{s} is smaller than a certain critical separation d_0 (and attractive otherwise) and the form of the interaction energy changes to

$$E_{\mathrm{int}} = F_0 L (c^2 + c d_{\mathrm{s}}) \exp\left(\frac{d_0 - d_{\mathrm{s}}}{c}\right) . \tag{24.12}$$

Once both the elastic and interaction contributions to the energy have been reckoned, we are in a position to compute the total energy. If we recognize that the length L of the packed DNA is given by

$$L = \frac{2}{\sqrt{3} d_{\mathrm{s}}} \int_R^{R_{\mathrm{out}}} 2\pi R' N(R') \,\mathrm{d}R' \,, \tag{24.13}$$

then the total energy for the packed DNA, in terms of L and d_s, is given by

$$E(L, d_s) = \frac{\pi \xi_p k_B T}{\sqrt{3} d_s / 2} \int_R^{R_{out}} \frac{N(R')}{R'} \, dR' \qquad (24.14)$$

$$+F_0(c^2 + c d_s) \exp(-d_s/c) \frac{2}{\sqrt{3} d_s} \int_R^{R_{out}} 2\pi R' N(R') \, dR' \, .$$

The spacing at a given length L is determined by requiring that the packed DNA be in a minimum energy configuration, which is equivalent to asking that $\partial E/\partial d_s = 0$. Hence, for a given geometry and length packed, one obtains d_s and thereby calculates the energy. Thus the energy is known as a function of the length packed, and to compute the force as a function of length of DNA packed one need only differentiate this energy with respect to the length packed. The result of this procedure is an expression for the force of the form

$$F(L) = F_0(c^2 + c d_s) \exp\left(-\frac{d_s}{c}\right) + \frac{\xi_P k_B T}{2R^2} \, . \qquad (24.15)$$

This is a generic expression valid for a capsid of any shape. The effect of the geometry is captured in the variation of d_s as a function of the length packed, as well as through the inner packing radius R. The resulting force-packing curves are shown in Fig. 24.8. In particular, this figure shows the packing force as a function of a fraction of the genome packed for a number of different solutions, with the different curves revealing the large role played by positive counterions in dictating the overall energetics of these processes.

On the basis of calculations like those given above, *Kindt* et al. [24.61] estimate that the pressure inside the capsid of the phage is on the order of 35 atmospheres. A crude estimate by *Smith* et al. [24.29] gives a figure close to 60 atmospheres. These numbers are intriguing in their own right, but more importantly they demonstrate the promise that proteins and other biological materials hold as candidates for engineering materials. To further explore the structural integrity of viruses in their role as pressurized protein shells, we now turn to an examination of the rupture stress of viral capsids.

Throughout this chapter, one of our main arguments has been the idea that whether it is our ambition to model conventional materials or their biological counterparts, modeling at the nanoscale implies challenges that can not be met either by purely continuum ideas or by traditional all-atom thinking. Indeed, one set of powerful methods is built around the attempt to borrow those features of continuum and atomistic thinking that are most robust, while rejecting those that are inapplicable at the atomic scale. As an example of this type of thinking, we examine another question drawn from the viruses-as-nanotechnology setting. In particular, since viruses have been considered a means of transporting material other than the genetic material of the virus itself, it is of interest to consider the maximum internal pressure viral capsids can sustain without rupture, as this will determine how much material can be safely packaged. To that end, we use continuum mechanics to estimate the stresses within the capsid walls. These stresses are then mapped onto atomic-level forces by appealing to the details of the protein structure of the monomers making up the capsid and a knowledge of the forces that link them. By relating the continuum and atomistic calculations, we then determine the maximum sustainable internal pressure.

We imagine the capsid to be a hollow sphere loaded by a pressure p_i from inside and a pressure p_o from outside. The inner and outer radii are R_i and R_o, respectively. As a representative example, bacteriophage



Fig. 24.8 Force as a function of the percent packed for a cylindrical capsid under purely repulsive solvent conditions. The dimensions of the capsid and the length of genome packed were chosen to represent the ϕ29 phage: $R_{out} = 210$ Å, $z = 540$ Å, and $L = 6.6\,\mu$m. Curve (c) shows the experimental results of *Smith* et al. [24.29], while theoretical curves (a), (b), and (d) are given by (24.15), with $F_0 = 10 \times 55{,}000$, $40 \times 55{,}000$, and $100 \times 55{,}000\,\text{pN/nm}^2$, respectively

GA is characterized geometrically by $R_\mathrm{i} = 123\,\text{Å}$ and $R_\mathrm{o} = 145\,\text{Å}$. Evaluation of a number of different capsid types suggests that treating capsids as though they have a mean thickness of roughly 15 Å suffices for the level of modeling being considered here. For the purposes of computing the internal stresses within the capsid, we begin with a statement of equilibrium from continuum mechanics that requires that at every point in the capsid

$$\nabla \cdot \sigma = \mathbf{0}\,, \tag{24.16}$$

where σ is the stress tensor comprising three normal stresses and three shear stresses. For a problem with spherical symmetry, like that considered here, the stresses reduce to a radial stress σ_R and a circumferential stress σ_T. Solution of the equilibrium equations results in stresses of the form [24.32]

$$\sigma_R = \frac{C}{r^3} + D, \quad \sigma_T = -\frac{C}{2r^3} + D\,. \tag{24.17}$$

By using the boundary conditions $\sigma_R|_{r=R_\mathrm{i}} = -p_\mathrm{i}$ and $\sigma_R|_{r=R_\mathrm{o}} = -p_\mathrm{o}$, the constants C and D can be determined with the result

$$\sigma_R = \frac{p_\mathrm{o} R_\mathrm{o}^3 \left(r^3 - R_\mathrm{i}^3\right)}{r^3 \left(R_\mathrm{i}^3 - R_\mathrm{o}^3\right)} + \frac{p_\mathrm{i} R_\mathrm{i}^3 \left(R_\mathrm{o}^3 - r^3\right)}{r^3 \left(R_\mathrm{i}^3 - R_\mathrm{o}^3\right)}\,, \tag{24.18}$$

$$\sigma_T = \frac{p_\mathrm{o} R_\mathrm{o}^3 \left(2r^3 + R_\mathrm{i}^3\right)}{2r^3 \left(R_\mathrm{i}^3 - R_\mathrm{o}^3\right)} - \frac{p_\mathrm{i} R_\mathrm{i}^3 \left(2r^3 + R_\mathrm{o}^3\right)}{2r^3 \left(R_\mathrm{i}^3 - R_\mathrm{o}^3\right)}\,. \tag{24.19}$$

The stress σ_T is our primary concern, since it acts so as to tear the sphere apart. By looking at the expressions above, we can see that this stress is maximum at $r = R_\mathrm{i}$ and the maximum value is given by

$$\sigma_T^\mathrm{max} = \frac{3 p_\mathrm{o} R_\mathrm{o}^3 - p_\mathrm{i} \left(2R_\mathrm{i}^3 + R_\mathrm{o}^3\right)}{2\left(R_\mathrm{i}^3 - R_\mathrm{o}^3\right)}\,. \tag{24.20}$$

We note that elasticity theory in and of itself is unable to comment on σ_T^max, since this is effectively a material parameter that characterizes the contacts between the various protein monomers that make up the capsid. As a result, we first examine how the rupture strength depends upon capsid dimensions in abstract terms and then turn to a concrete estimate of σ_T^max itself from several complementary perspectives. If (24.20) is rewritten using $p_\mathrm{i} = p_\mathrm{o} + \Delta p$ and $R_\mathrm{o} = R_\mathrm{i} + \Delta R$, and, further, it is realized that for typical capsid dimensions $\Delta R / R_\mathrm{i} \ll 1$, it can be shown by rearranging (24.20) and by considering the case in which σ_T^max is much larger than p_o, the maximum sustainable internal pressure is given by

$$p_\mathrm{i}^\mathrm{max} = \frac{2\sigma_T^\mathrm{max} \Delta R}{R_\mathrm{i}}\,, \tag{24.21}$$

where $p_\mathrm{i}^\mathrm{max}$ is really the quantity of interest, namely, the maximum sustainable internal pressure.

To make concrete progress to the point where we can actually estimate the rupture stress in atm, we need to consider capsids for which the structure is known and for which, at least approximately, the bonds between the monomers making up the capsid are understood. We note that in the language of fracture mechanics, what we seek is a cohesive surface model that provides a measure of the energy of interaction between two surfaces as a function of their separation [24.68]. There are a number of different ways to go about estimating the effective interaction between the monomers making up the capsid, one of which is by appealing to atomic-level calculations like those made by *Reddy* et al. [24.69]. The Viper website has systematized such information for a number of capsids, and one of the avenues we take to estimate σ_T^max is to appeal directly to their calculations. To that end, we assume that the energy of interaction per unit area as a function of separation x between adjacent monomers making up the capsid can be written in the form

$$E(x) = V_0 \left[\frac{1}{4}\left(\frac{x^*}{x}\right)^{12} - \frac{1}{2}\left(\frac{x^*}{x}\right)^{6}\right]. \tag{24.22}$$

The motivation for this functional form is the idea that the energy of interaction between adjacent monomeric units making up the capsid is the result of van der Waals contacts, and hence our cohesive surface law has inherited the properties of the underlying atomic force fields. To proceed to an estimate of σ_T^max itself, we must determine the parameters in the cohesive model described above. To that end, we note that *Reddy* et al. [24.69] have computed the association energies of various inequivalent contacts throughout a number of different icosahedral capsids. Their calculations result in a roughly constant value of $\approx -45\,\mathrm{cal/mole}\,\text{Å}^2$ as the association energy, which in the language of our cohesive potential results in $V_0 \approx 12.5\,\mathrm{pN/Å}$. This may be seen by noting that the association energy is given by $E(x^*) = -V_0/4$.

Once we have fixed x^*, which amounts to choosing a particular value for the equilibrium separation between two monomers, the material parameter σ_T^max is obtained by evaluating $\partial E(x)/\partial x$ at a value of x corresponding to the point of inflection $(\partial^2 E(x)/\partial x^2 = 0)$ in the cohesive surface function. For the cohesive surface function used above, this results in a maximum stress of the form

$$\sigma_T^{\max} = \frac{7^{7/6}\times 18}{13^{13/6}}\,\frac{V_0}{x^*}\,. \tag{24.23}$$

With $\sigma_T^{\max}$ in hand, the maximum sustainable pressure is obtained from (24.21), and the results are shown in Fig. 24.9. These estimates suggest that the pressures within capsids as a result of packed DNA while large, are still smaller than our estimated rupture stresses. To more completely examine this question we have undertaken finite element elasticity calculations to examine the stresses in capsids exhibiting irregularities in both shape and thickness. In addition, further atomistic analysis of $\sigma_T^{\max}$ is needed with special reference to its dependence on distance between protein units. It would also be of interest to examine mutant versions of the monomeric units making up the capsid to see the implications of such mutations for $\sigma_T^{\max}$.



Fig. 24.9 Rupture pressure as a function of capsid radius for $x^* = 3$ Å (*upper curve*) and $x^* = 4$ Å (*lower curve*). The width of the capsid walls was set to $\Delta R = 1.5$ nm, while $V_0 = 180$ cal/molÅ^2

24.5 Concluding Remarks

One of the most compelling areas to be touched by nanotechnology is biological science. Indeed, we have argued that there is a fascinating interplay between these two subjects, with biology as a key beneficiary of advances in nanotechnology as a result of a new generation of single molecule experiments that complement traditional assays involving statistical assemblages of molecules. This interplay runs in both directions with nanotechnology continually receiving inspiration from biology itself. The goal of this chapter has been to highlight some representative examples of the interplay between biology and nanotechnology and to illustrate the role of nanomechanics in this field and how mechanical models have arisen in response to the emergence of this new field. Primary attention has been given to the particular example of the processes that attend the life cycle of bacterial viruses. Viruses feature many of the key lessons of biological nanotechnology, including self-assembly, as evidenced in the spontaneous formation of the protein shell (capsid) within which the viral genome is packaged and a motor-mediated biological process, namely, the packaging of DNA in this capsid by a molecular motor that pushes the DNA into the capsid. We argue that these processes in viruses are a compelling real-world example of nature's nanotechnology and reveal the nanomechanical challenges that will continue to be confronted at the nanotechnology-biology interface.

Though this chapter represents something of a departure from the rest of the chapters in this volume, it advances the view that biological nanotechnology serves as an inspiring vision of what nanotechnology can offer and reflects the authors' views that biologically inspired nanotechnology will play an ever increasing role as Feynman's view that "there is plenty of room at the bottom" continues to play out. Moreover, developing simple models of nature's nanotechnology can provide important insights into viable strategies for making machines at the nanoscale.

We have argued that the advance of single molecule technology presents both scientific and technological possibilities. Both classes of questions imply significant modeling demands, just as earlier advances in other settings, such as in materials for microelectronics applications, did. We claim that these modeling challenges are perhaps more acute as a result of the vicious chemical and structural nonhomogeneity of biological systems. As a result, we see an ever increasing role for modeling methods that aim to keep atomic-level specificity where needed, while rejecting such resolution elsewhere.

References

24.1 B. Alberts, D. Bray, A. Johnson, J. Lewis, M. Raff, K. Roberts, P. Walter: *Essential Cell Biology* (Garland, New York 1997) Chap. 12

24.2 B. Alberts: The cell as a collection of protein machines: Preparing the next generation of molecular biologists, Cell **92** (1998) 291

24.3 D. Bray: *Cell Movements From Molecules to Motility* (Garland, New York 2001)

24.4 S. J. Flint, L. W. Enquist, R. M. Krug, V. R. Racaniello, A. M. Skalka: *Principles of Virology* (ASM, Washington, DC 2000)

24.5 J. C. M. van Hest, D. A. Tirrell: Protein-based materials, toward a new level of structural control, Chem. Commun. **19** (2001) 1807–1904

24.6 H. Berg: Motile behavior of bacteria, Phys. Today **53** (2000) 24

24.7 J. E. Walker: ATP synthesis by rotary catalysis, Angew. Chem. Int. Edn. **37** (1998) 2308

24.8 P. D. Boyer: The ATP synthase – A splendid molecular machine, Annu. Rev. Biochem. **66** (1997) 717

24.9 M. Yoshida, E. Muneyuki, T. Hisabori: ATP synthase – A marvelous rotary engine of the cell, Nature Rev. Mol. Cell Bio. **2** (2001) 669

24.10 R. Yasuda, H. Noji, K. Kinosita, M. Yoshida: F_1-ATPase is a highly efficient molecular motor that rotates with discrete 120° steps, Cell **93** (1998) 1117

24.11 J. Howard: *Mechanics of Motor Proteins and the Cytoskeleton* (Sinauer, Sunderland 2001)

24.12 B. Hille: *Ion Channels of Excitable Membranes* (Sinauer, Sunderland 2001)

24.13 S. Sukharev, S. R. Durell, H. R. Guy: Structural Models of the MscL gating mechanism, Biophys. J. **81** (2001) 917

24.14 S. Sukharev, M. Betanzos, C.-S. Chiang, H. R. Guy: The gating mechanism of the large mechanosensitive channel MscL, Nature **409** (2001) 720

24.15 K. Kinosita, R. Yasuda, H. Noji: F_1-ATPase: A highly efficient rotary ATP machine, Essays Biochem. **35** (2000) 3

24.16 E. Racker, W. Stoeckenius: Reconstitution of purple membrane vesicles catalyzing light-driven proton uptake and adenosine triphosphate formation, J. Biol. Chem. **249** (1974) 662

24.17 G. Groth, J. E. Walker: ATP synthase from bovine heart mitochondria: reconstitution into unilamellar phospholipid vesicles of the pure enzyme in a functional state, Biochem. J. **318** (1996) 351

24.18 G. Wu, R. H. Datar, K. M. Hansen, T. Thundat, R. J. Cote, A. Majumdar: Bioassay of prostrate-specific antigen (PSA) using microcantilevers, Nature Biotech. **19** (2001) 856

24.19 R. P. Feynmann: There's plenty of room at the bottom, Eng. Sci. **23** (1960) 22–36, and www.zyvex.com/nanotech/feynman.html (1959)

24.20 E. Evans: Probing the relation between force-lifetime and chemistry in single molecular bonds, Annu. Rev. Biophys. Biomol. Struct. **30** (2001) 105

24.21 T. E. Fisher, P. E. Marszalek, J. M. Fernandez: Stretching single molecules into novel conformations using the atomic force microscope, Nature Struct. Bio. **7** (2000) 719

24.22 M. Rief, M. Gautel, F. Oesterhelt, J. M. Fernandez, H. Gaub: Reversible unfolding of individual titin immunoglobulin domains by AFM, Science **276** (1997) 1109

24.23 K. Svoboda, S. M. Block: Biological applications of optical forces, Annu. Rev. Biophys. Biomol. Struct. **23** (1994) 247

24.24 C. Bustamante, J. C. Macosko, G. J. L. Wuite: Grabbing the cat by the tail: Manipulating molecules one by one, Nature Rev. Mol. Cell Bio. **1** (2000) 130

24.25 K. Svoboda, S. M. Block: Force and velocity measured for single kinesin molecules, Cell **77** (1994) 773

24.26 M. J. Schnitzer, S. M. Block: Kinesin hydrolyses one ATP per 8-nm step, Nature **388** (1997) 386

24.27 B. Maier, T. R. Strick, V. Croquette, D. Bensimon: Study of DNA motors by single molecule micromanipulation, Single Mol. **1** (2000) 145

24.28 A. A. Simpson, Y. Tao, P. G. Leiman, M. O. Badasso, Y. He, P. J. Jardine, N. H. Olson, M. C. Morais, S. Grimes, D. L. Anderson, T. S. Baker, M. G. Rossmann: Structure of the bacteriophage ϕ-29 DNA packaging motor, Nature **408** (2000) 745

24.29 D. E. Smith, S. J. Tans, S. B. Smith, S. Grimes, D. L. Anderson, C. Bustamante: The bacteriophage ϕ-29 portal motor can package DNA against a large internal force, Nature **413** (2001) 748

24.30 D. Bray: Reasoning for results, Nature **412** (2001) 863

24.31 G. Wu, H. Ji, K. Hansen, T. Thundat, R. Datar, R. Cote, M. F. Hagan, A. K. Charkraborty, A. Majumdar: Origin of nanomechanical cantilever motion generated from biomolecular interactions, Proc. Nat. Acad. Sci. **98** (2001) 1560

24.32 L. D. Landau, E. M. Lifshitz: *Theory of Elasticity* (Pergamon, Oxford 1986)

24.33 D. H. Bamford, R. J. C. Gilbert, J. M. Grimes, D. I. Stuart: Macromolecular assemblies: greater than their parts, Curr. Op. Struc. Biology **11** (2001) 107

24.34 J. Frank: Single-particle imaging of macromolecules by cryo-electron microscopy, Annu. Rev. Biophys. Biomol. Struct. **31** (2002) 303

24.35 S. A. Darst: Bacterial RNA polymerase, Curr. Op. Struc. Biology **11** (2001) 155

24.36 N. Ban, P. Nissen, J. Hansen, P. B. Moore, T. A. Steitz: The complete atomic structure of the large ribosomal subunit at 2.4 Å resolution, Science **289** (2000) 905

24.37 T. S. Baker, N. H. Olson, S. D. Fuller: Adding the third dimension to virus life cycles: Three-dimensional reconstruction of icosahedral viruses from cryo-electron micrographs, Microbiol. Mol. Bio. Rev. **63** (1999) 862

24.38 H.-S. Chan, K. A. Dill: The protein folding problem, Phys. Today **46** (February 1993) 24

24.39 M. D. Wang, M. J. Schnitzer, H. Yin, R. Landick, J. Gelles, S. M. Block: Force and velocity measured for single molecules of RNA polymerase, Science **282** (1998) 902

24.40 M. L. Roukes: Nanoelectromechanical Systems, Technical Digest of the 2000 Solid-State Sensor and Actuator Workshop (2000)

24.41 K. Adachi, R. Yasuda, H. Noji, H. Itoh, Y. Harada, M. Yoshida, K. Kinosita: Stepping rotation of F_1-ATPase visualized through angle-resolved single-fluorophore imaging, Proc. Nat. Acad. Sci. **97** (2000) 7243

24.42 J. Wrigglesworth: *Energy and Life* (Taylor and Francis, London 1997)

24.43 V. Smil: *Energies* (MIT, Cambridge 1999)

24.44 J. T. Finer, R. M. Simmons, J. A. Spudich: Single myosin molecule mechanics: Piconewton forces and nanometre steps, Nature **368** (1994) 113

24.45 S. B. Smith, Y. Cui, C. Bustamante: Overstretching B-DNA: The elastic response of individual double-stranded and single-sranded DNA molecules, Science **271** (1996) 795

24.46 S. Munevar, Y. Wang, M. Dembo: Traction force microscopy of migrating normal and H-ras transformed 3T3 fibroblasts, Biophys. J. **80** (2001) 1744

24.47 L. Mahadevan, P. Matsudaira: Motility powered by supramolecular springs and ratchets, Science **288** (2000) 95

24.48 R. Phillips, M. Dittrich, K. Schulten: Quasicontinuum representations of atomic-scale mechanics: From proteins to dislocations, Ann. Rev. Mat. Sci. **32** (2002) 219

24.49 T. Strick, J.-F. Allemand, V. Croquette, D. Bensimon: Twisting and stretching single DNA molecules, Prog. Biophys. Mol. Bio. **74** (2000) 115

24.50 D. Frenkel, B. Smit: *Understanding Molecular Simulation* (Academic, San Diego 1996)

24.51 H. Lu, B. Isralewitz, A. Krammer, V. Vogel, K. Schulten: Unfolding of titin immunoglobulin domains by steered molecular dynamics simulation, Biophys. J. **75** (1998) 662

24.52 M. Carrion-Vazquez, A. F. Oberhauser, T. E. Fisher, P. E. Marszalek, H. Li, J. M. Fernandez: Mechanical design of proteins studies by single-molecule force spectroscopy and protein engineering, Prog. Biophys. Mol. Bio. **74** (2000) 63

24.53 A. Y. Grosberg, A. R. Khokhlov: *Giant Molecules* (Academic, San Diego 1997)

24.54 M. Ptashne, A. Gann: *Genes and Signals* (Cold Spring Harbor Laboratory Press, Cold Spring Harbor 2002)

24.55 A. Balaeff, L. Mahadevan, K. Schulten: Elastic rod model of a DNA loop in the Lac Operon, Phys. Rev. Lett. **83** (1999) 4900

24.56 U. Seifert: Configurations of fluid membranes and vesicles, Adv. Phys. **46** (1997) 13

24.57 D. Boal: *Mechanics of the Cell* (Cambridge Univ. Press, Cambridge 2002)

24.58 D. Leckband, J. Israelachvili: Intermolecular forces in biology, Q. Rev. Biophys. **34** (2001) 105

24.59 S. C. Riemer, V. A. Bloomfield: Packaging of DNA in bacteriophage heads: Some considerations on energetics, Biopolymers **17** (1978) 785

24.60 T. Odijk: Hexagonally packed DNA within bacteriophage T7 stabilized by curvature stress, Biophys. J. **75** (1998) 1223

24.61 J. Kindt, S. Tzlil, A. Ben-Shaul, W. Gelbart: DNA packaging and ejection forces in bacteriophage, Proc. Nat. Acad. Sci. **98** (2001) 13671

24.62 K. E. Richards, R. C. Williams, R. Calendar: Mode of DNA packing within bacteriophage heads, J. Mol. Bio. **78** (1973) 255

24.63 M. E. Cerritelli, N. Cheng, A. H. Rosenberg, C. E. McPherson, F. P. Booy, A. C. Steven: Encapsidated conformation of bacteriophage T7 DNA, Cell **91** (1997) 271

24.64 N. H. Olson, M. Gingery, F. A. Eiserling, T. S. Baker: The structure of isomeric capsids of bacteriophage T4, Virology **279** (2001) 385

24.65 D. C. Rau, B. Lee, V. A. Parsegian: Measurement of the repulsive force between polyelectrolyte molecules in ionic solution: Hydration forces between parallel DNA double helices, Proc. Natl. Acad. Sci. **81** (1984) 2621

24.66 D. C. Rau, V. A. Parsegian: Direct measurement of the intermolecular forces between counterion-condensed DNA double helices, Biophys. J. **61** (1992) 246

24.67 V. A. Parsegian, R. P. Rand, N. L. Fuller, D. C. Rau: Osmotic stress for the direct measurement of intermolecular forces, Meth. Enzymol. **127** (1986) 400

24.68 R. Phillips: *Crystals, Defects and Microstructures* (Cambridge Univ. Press, Cambridge 2001)

24.69 V. S. Reddy, H. A. Giesing, R. T. Morton, A. Kumar, C. B. Post, C. L. Brooks, J. E. Johnson: Energetics of quasiequivalence: Computational analysis of protein-protein interactions in icosahedral viruses, Biophys. J. **74** (1998) 546
The parameters can be found at http://www.scripps.edu/pub/olson-web/gmm/autodock/ad305/Using_AutoDock_305.a.html

25. Mechanical Properties of Nanostructures

Knowledge of the mechanical properties of nanostructures is necessary for designing realistic MEMS/NEMS devices. Microelectromechanical systems (MEMS) refer to microscopic devices that have a characteristic length of less than 1 mm but more than 1 μm and combine electrical and mechanical components. Nanoelectromechanical systems (NEMS) refer to nanoscopic devices that have a characteristic length of less than 1 μm and combine electrical and mechanical components.

Elastic and inelastic properties are needed to predict deformation from an applied load in the elastic and inelastic regimes, respectively. The strength property is needed to predict the allowable operating limit. Some of the properties of interest are hardness, elastic modulus, bending strength, fracture toughness, and fatigue strength.

Structural integrity is of paramount importance in all devices. Load applied during the use of devices can result in component failure. Cracks can develop and propagate under tensile stresses, leading to failure. Atomic force microscopy and nanoindenters can be used satisfactorily to evaluate the mechanical properties of micro/nanoscale structures for use in MEMS/NEMS.

The most commonly used materials are single-crystal silicon and silicon-based materials, e.g., SiO_2 and polysilicon films deposited by low-pressure chemical vapor deposition. An early study showed silicon to be a mechanically resilient material in addition to its favorable electronic properties. Single-crystal SiC deposited on large-area silicon substrates is used for high-temperature micro/nanosensors and actuators. Amorphous alloys can be formed on both metal and silicon substrates by sputtering and plating techniques, providing more flexibility in surface-integration. Electroless deposited Ni-P amorphous thin films have been used to construct microdevices, especially using the so-called LIGA techniques. Micro/nanodevices need conductors to provide power, as well as electrical/magnetic signals to make them functional. Electroplated gold films have found wide applications in electronic devices because of their ability to make thin films and process simply. Use of SiC, Ni-P, and Au films, together with silicon and silicon-based materials, opens up new design opportunities for MEMS/NEMS devices.

This chapter presents a review of mechanical property measurements on the nanoscale of various materials of interest and stress and deformation analyses of nanostructures.

25.1 **Experimental Techniques for Measurement of Mechanical Properties of Nanostructures** 765
25.1.1 Indentation and Scratch Tests Using Micro/Nanoindenters 765
25.1.2 Bending Tests of Nanostructures Using an AFM 765
25.1.3 Bending Tests Using a Nanoindenter.................. 769

25.2 **Experimental Results and Discussion** 770
25.2.1 Indentation and Scratch Tests of Various Materials Using Micro/Nanoindenters 770
25.2.2 Bending Tests of Nanobeams Using an AFM.............................. 773
25.2.3 Bending Tests of Microbeams Using a Nanoindenter.................. 777

25.3 **Finite Element Analysis of Nanostructures with Roughness and Scratches**.............. 778
25.3.1 Stress Distribution in a Smooth Nanobeam 779
25.3.2 Effect of Roughness in the Longitudinal Direction......... 781
25.3.3 Effect of Roughness in the Transverse Direction and Scratches 781
25.3.4 Effect on Stresses and Displacements for Materials That Are Elastic, Elastic-Plastic, or Elastic-Perfectly Plastic 784

25.4 **Closure** 785

References 786

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Microelectromechanical systems (MEMS) refer to microscopic devices that have a characteristic length of less than 1 mm but more than 1 µm and combine electrical and mechanical components. Nanoelectromechanical systems (NEMS) refer to nanoscopic devices that have a characteristic length of less than 1 µm and combine electrical and mechanical components. To put the dimensions in perspective, individual atoms are typically fraction of a nanometer in diameter, DNA molecules are about 2.5 nm wide, biological cells are in the range of thousands of nm in diameter, and human hair is about 75 µm in diameter. The mass of a micromachined silicon structure can be as low as 1 nN, and NEMS can be built with a mass as low as 10^{-20} N with cross sections of about 10 nm. In comparison, the mass of a drop of water is about 10 µN and the mass of an eyelash is about 100 nN. The acronym MEMS originated in the United States. The term commonly used in Europe and Japan is micro/nanodevices, which is used in a much broader sense. MEMS/NEMS terms are also now used in a broad sense. A micro/nanosystem, a term commonly used in Europe, is referred to as an intelligent miniaturized system comprising sensing, processing, and/or actuating functions.

A wide variety of MEMS, including Si-based devices, chemical and biological sensors and actuators, and miniature non-silicon structures (e.g., devices made from plastics or ceramics) have been fabricated with dimensions in the range of a couple to a few thousand microns (see e.g., [25.1–9]). A variety of NEMS have also been produced [25.10–15]. Two of the largest "killer" industrial applications of MEMS are accelerometers (about 85 million units in 2002) and digital micromirror devices (about $ 400 million in revenues in 2002). BIOMEMS and BIONEMS are increasingly used in commercial applications. The largest applications of BIOMEMS include silicon-based disposable blood pressure sensor chips for blood pressure monitoring (about 20 million units in 2002) and a variety of biosensors.

Structural integrity is of paramount importance in all devices. Load applied during the use of devices can result in component failure. Cracks can develop and propagate under tensile stresses, leading to failure [25.16, 17]. Friction/stiction and wear limit the lifetimes and compromise the performance and reliability of the devices involving relative motion [25.4, 18]. Most MEMS/NEMS applications demand extreme reliability. Stress and deformation analyses are carried out for an optimal design. MEMS/NEMS designers require mechanical properties on the nanoscale. Mechanical properties include elastic, inelastic (plastic, fracture, or viscoelastic), and strength. Elastic and inelastic properties are needed to predict deformation from an applied load in the elastic and inelastic regimes, respectively. The strength property is needed to predict the allowable operating limit. Some of the properties of interest are hardness, elastic modulus, bending strength (fracture stress), fracture toughness, and fatigue strength. Micro/nanostructures have some surface topography and local scratches dependent upon the manufacturing process. Surface roughness and local scratches may compromise the reliability of the devices and their effect needs to be studied.

Most mechanical properties are size-dependent [25.11, 16, 17]. Several researchers have measured mechanical properties of silicon and silicon-based milli- to microscale structures using tensile tests and bending tests [25.19–28], resonant structure tests for measurement of elastic properties [25.29], fracture toughness tests [25.20, 22, 30–34], and fatigue tests [25.32, 35, 36]. Most recently, a few researchers have measured mechanical properties of nanoscale structures using atomic force microscopy (AFM) [25.37, 38] and nanoindentation [25.39, 40]. For stress and deformation analyses of simple geometries and boundary condition, analytical models can be used. For analysis of complex geometries, numerical models are needed. The conventional finite element method (FEM) can be used down to a few tens of nanometers, although its applicability is questionable at the nanoscale. FEM has been used for simulation and prediction of residual stresses and strains induced in MEMS devices during fabrication [25.41], to perform fault analysis in order to study MEMS faulty behavior [25.42], to compute mechanical strain resulting from the doping of silicon [25.43], and to analyze micromechanical experimental data [25.22, 44, 45] and nanomechanical experimental data [25.38]. FEM analysis of nanostructures has been carried out to analyze the effect of types of surface roughness and scratches on stresses in nanostructures [25.46, 47].

The most commonly used materials for MEMS/NEMS are single-crystal silicon and silicon-based materials (e.g., SiO_2 and polysilicon films deposited by low pressure chemical vapor deposition (LPCVD) process) [25.11]. An early study showed silicon to be a mechanically resilient material in addition to its favorable electronic properties [25.48]. Single-crystal 3C-SiC (cubic or β-SiC) films deposited by atmospheric pressure chemical vapor deposition (APCVD) process on large-area silicon substrates are produced for high-temperature micro/nanosensor and actuator applications [25.49–51]. Amorphous alloys can be formed on both metal and silicon substrates by sputtering and plating techniques, providing more flexibility in surface-integration. Electroless deposited Ni-P amorphous thin films have been used to construct microdevices, especially using the so-called LIGA techniques [25.11, 40]. Micro/nanodevices need conductors to provide power, as well as electrical/magnetic signals to make them functional. Electroplated gold films have found wide applications in electronic devices, because of their ability to make thin films and process simplicity [25.40]. Use of SiC, Ni-P, and Au films together with silicon and silicon-based materials open up new design opportunities for MEMS/NEMS devices.

This chapter presents a review of mechanical property measurements on the nanoscale of various materials of interest, and stress and deformation analyses of nanostructures.

25.1 Experimental Techniques for Measurement of Mechanical Properties of Nanostructures

25.1.1 Indentation and Scratch Tests Using Micro/Nanoindenters

A nanoindenter is commonly used to measure hardness, elastic modulus, and fracture toughness and to perform micro/nanoscratch studies to get a measure of scratch/wear resistance of materials [25.11, 52].

Hardness and Elastic Modulus

The nanoindenter monitors and records the dynamic load and displacement of the three-sided pyramidal diamond (Berkovich) indenter during indentation with a force resolution of about 75 nN and displacement resolution of about 0.1 nm. Hardness and elastic modulus are calculated from the load-displacement data [25.11]. The peak indentation load depends on the mechanical properties of the specimen; a harder material requires higher load for a reasonable indentation depth.

Fracture Toughness

The indentation technique for fracture toughness measurement on the microscale is based on the measurement of the lengths of median-radial cracks produced by indentation. A Vickers indenter (a four-sided diamond pyramid) is used in a microhardness test. A load on the order of 0.5 N is typically used in making the Vickers indentations. The indentation impressions are examined using an optical microscope with Nomarski interference contrast to measure the length of median-radial cracks, c. The fracture toughness (K_{IC}) is calculated by the following relation [25.53]:

$$K_{\mathrm{IC}} = \alpha \left(\frac{E}{H}\right)^{1/2} \left(\frac{P}{c^{3/2}}\right) , \tag{25.1}$$

where α is an empirical constant depending on the geometry of the indenter, H and E are hardness and elastic moduli, and P is the peak indentation load. For Vickers indenters, α has been empirically found based on experimental data and is equal to 0.016 [25.11]. Both E and H values are obtained from the nanoindentation data. The crack length is measured from the center of the indent to the end of the crack using an optical microscope. For one indent, all crack lengths are measured. The crack length c is obtained from the average values of several indents.

Scratch Resistance

In micro/nanoscratch studies, a conical diamond indenter with a tip radius of about 1 μm and an included angle of 60° is drawn over the sample surface, and the load is ramped up until substantial damage occurs [25.11]. The coefficient of friction is monitored during scratching. In order to obtain scratch depths during scratching, the surface profile of the sample surface is first obtained by translating the sample at a low load of about 0.2 mN, which is insufficient to damage a hard sample surface. The 500-μm-long scratches are made by translating the sample while ramping the loads on the conical tip over different loads depending on the material hardness. The actual depth during scratching is obtained by subtracting the initial profile from the scratch depth measured during scratching. In order to measure the scratch depth after the scratch, the scratched surface is profiled at a low load of 0.2 mN and is subtracted from the actual surface profile before scratching.

25.1.2 Bending Tests of Nanostructures Using an AFM

Quasi-static bending tests of fixed nanobeam arrays are carried out using an AFM [25.37, 38, 54]. A three-sided pyramidal diamond tip (with a radius of about 200 nm)



Fig. 25.1 Schematic showing the details of a nanoscale bending test. The AFM tip is brought to the center of the nanobeam and the piezo is extended over a known distance. By measuring the tip displacement, a load-displacement curve of the nanobeam can be obtained [25.38]

mounted on a rectangular stainless steel cantilever is used for the bending tests. The beam stiffness is selected based on the desired load range. The stiffness of the cantilever beams for application of normal load up to 100 µN is about 150–200 N/m.

The wafer with nanobeam array is fixed onto a flat sample chuck using double-stick tape [25.38]. For the bending test, the tip is brought over the nanobeam array with the help of the sample stage of the AFM and a built-in high magnification optical microscope (Fig. 25.1). For the fine positioning of the tip over a chosen beam, the array is scanned in contact mode at a contact load of about 2–4 µN, which results in negligible damage to the sample. After scanning, the tip is located at one end of a chosen beam. To position the tip at the center of the beam span, the tip is moved to the other end of the beam by giving the X-piezo an offset voltage. The value of this offset is determined after several such attempts have been made in order to minimize effects of piezo drift. Half of this offset is then applied to the X-piezo after the tip is positioned at one end of the beam, which usually results in the tip being moved to the center of the span. Once the tip is positioned over the center of the beam span, the tip is held stationary without scanning, and the Z-piezo is extended by a known distance, typically about 2.5 µm, at a rate of 10 nm/s, as shown in Fig. 25.1. During this time, the vertical deflection signal ($\mathrm{d}V_{\mathrm{AFM}}$), which is proportional to the deflection of the cantilever (D_{tip}), is monitored. The displacement of the piezo is equal to the sum of the displacements of the cantilever and nanobeam. Hence, the displacement of the nanobeam (D_{beam}) under the point of load can be determined as

$$D_{\mathrm{beam}} = D_{\mathrm{piezo}} - D_{\mathrm{tip}} \,. \qquad (25.2)$$

The load (F_{beam}) on the nanobeam is the same as the load on the tip/cantilever (F_{tip}) and is given by

$$F_{\mathrm{beam}} = F_{\mathrm{tip}} = D_{\mathrm{tip}} \times k \,, \qquad (25.3)$$

where k is the stiffness of the tip/cantilever. In this manner, a load displacement curve for each nanobeam can be obtained.

The photodetector sensitivity of the cantilever needs to be calibrated to obtain D_{tip} in nm. For this calibration, the tip is pushed against a smooth diamond sample by moving the Z-piezo over a known distance. For the hard diamond material, the actual deflection of the tip can be assumed to be the same as the Z-piezo travel (D_{piezo}), and the photodetector sensitivity (S) for the cantilever setup is determined as

$$S = D_{\mathrm{piezo}} / \mathrm{d}V_{\mathrm{AFM}} \ \mathrm{nm/V} \,. \qquad (25.4)$$

In the measurements, D_{tip} is given as $\mathrm{d}V_{\mathrm{AFM}} \times S$.

Since a sharp tip would result in an undesirable large local indentation, *Sundararajan* and *Bhushan* [25.38] used a worn (blunt) diamond tip. Indentation experiments using this tip on a silicon substrate yielded a residual depth of less than 8 nm at a maximum load of 120 µN, which is negligible compared to displacements of the beams (several hundred nm). Hence, we can assume that negligible local indentation or damage is created during the bending process of the beams, and that the displacement calculated from (25.2) is entirely that of the beam structure.

Elastic Modulus and Bending Strength

Elastic modulus and bending strength (fracture stress) of the beams can be estimated by equations based on the assumption that the beams follow linear elastic theory of an isotropic material. This is probably valid since the beams have high length-to-width (ℓ/w) and length-to-thickness (ℓ/t) ratios and also since the length direction is along the principal stress direction during the test. For a fixed elastic beam loaded at the center of the span, the elastic modulus is expressed as

$$E=\frac{\ell^3}{192I}m\,, \tag{25.5}$$

where ℓ is the beam length, I is the area moment of inertia for the beam cross section, and m is the slope of the load-displacement curve during bending [25.55]. The area moment of inertia for a beam with a trapezoidal cross section is calculated from the following equation:

$$I=\frac{w_1^2+4w_1w_2+w_2^2}{36(w_1+w_2)}t^3\,, \tag{25.6}$$

where w_1 and w_2 are the upper and lower widths, respectively, and t is the thickness of the beam. According to linear elastic theory, for a centrally loaded beam, the moment diagram is shown in Fig. 25.2. The maximum moments are generated at the ends (negative moment) and under the loading point (positive moment), as shown in Fig. 25.2. The bending stresses generated in the beam are proportional to the moments and are compressive or tensile about the neutral axis (line of zero stress). The maximum tensile stress (σ_b, which is the bending strength or fracture stress) is produced on the top surface at both the ends and is given by [25.55]

$$\sigma_b=\frac{F_{\max}\ell e_1}{8I}\,, \tag{25.7}$$

where $F_{\max}$ is the applied load at failure and e_1 is the distance of the top surface from the neutral plane of the beam cross section and is given by [25.55]

$$e_1=\frac{t(w_1+2w_2)}{3(w_1+w_2)}\,. \tag{25.8}$$

Although the moment value at the center of the beam is the same as at the ends, the tensile stresses at the center (generated on the bottom surface) are less than those generated at the ends, as per (25.7), because the distance from the neutral axis to the bottom surface is less than e_1. This is because of the trapezoidal cross section of the beam, which results in the neutral axis being closer to the bottom surface than the top (Fig. 25.2).

In the preceding analysis, the beams were assumed to have fixed ends. However, in the nanobeams used by *Sundararajan* and *Bhushan* [25.38], the underside of the beams was pinned over some distance on either side of the span. Hence, a finite element model of the beams was created to see if the difference in the boundary conditions affected the stresses and displacements of the beams. It was found that the difference in the stresses was less than 1%. This indicates that the boundary conditions near the ends of the actual beams are not that different from that of the fixed ends. Therefore, the bending strength values can be calculated from (25.7).



Fig. 25.2 A schematic of the bending moments generated in the beam during a quasi-static bending experiment with the load at the center of the span. The maximum moments occur under the load and at the fixed ends. Due to the trapezoidal cross section, the maximum tensile bending stresses occur at the top surfaces at the fixed ends

Fracture Toughness

Fracture toughness is another important parameter for brittle materials such as silicon. In the case of the nanobeam arrays, these are not best suited for fracture toughness measurements, because they do not possess regions of uniform stress during bending. *Sundararajan* and *Bhushan* [25.38] developed a methodology, and its steps are outlined schematically in Fig. 25.3a. First, a crack of known geometry is introduced in the region of maximum tensile bending stress, i. e., on the top surface near the ends of the beam. This is achieved by generating a scratch at high normal load across the width (w_1) of the beam using a sharp diamond tip (radius < 100 nm). A typical scratch thus generated is shown in Fig. 25.3b. By bending the beam as shown, a stress concentration will be formed under the scratch. This will lead to failure of the beam under the scratch once a critical load (fracture load) is attained. The fracture load and relevant dimensions of the scratch are input into the FEM model, which is used to generate the fracture stress plots. Figure 25.3c shows an FEM simulation of one such experiment, which reveals that the maximum stress does occur under the scratch.

If we assume that the scratch tip acts as a crack tip, a bending stress will tend to open the crack in Mode I. In this case, the stress field around the crack tip can be described by the stress intensity parameter K_I (for Mode I) for linear elastic materials [25.56]. In particular, the stresses corresponding to the bending stresses are



Fig. 25.3 **(a)** Schematic of technique to generate a defect (crack) of known dimensions in order to estimate fracture toughness. A diamond tip is used to generate a scratch across the width of the beam. When the beam is loaded as shown, a stress concentration is formed at the bottom of the scratch. The fracture load is then used to evaluate the stresses using FEM. **(b)** AFM 3-D image and 2-D profile of a typical scratch. **(c)** Finite element model results verifying that the maximum bending stress occurs at the bottom of the scratch [25.38]

described by

$$\sigma = \frac{K_\mathrm{I}}{\sqrt{2\pi r}} \cos\left(\frac{\theta}{2}\right)\left[1+\sin\left(\frac{\theta}{2}\right)\sin\left(\frac{3\theta}{2}\right)\right] \tag{25.9}$$

for every point $p(r,\theta)$ around the crack tip, as shown in Fig. 25.4. If we substitute the fracture stress (σ_f) to the left hand side of (25.9), then the K_I value can be substituted with its critical value, which is the fracture toughness K_IC. Now, the fracture stress can be determined for the point ($r = 0$, $\theta = 0$), i. e., right under the crack tip as explained above. However, we cannot substitute $r = 0$ in (25.9). The alternative is to substitute a value for r, which is as close to zero as possible. For silicon, a reasonable number is the distance between neighboring atoms in the (111) plane, the plane along which silicon exhibits the lowest fracture energy. This value was calculated from silicon unit cell dimensions of 0.5431 nm [25.57] to be 0.4 nm (half of the face diagonal). This assumes that Si displays no plastic zone around the crack tip, which is reasonable since in tension, silicon is not known to display much plastic deformation at room temperature. *Sundararajan* and *Bhushan* [25.38] used values $r = 0.4–1.6$ nm (i. e., distances up to four times the distance between the nearest neighboring atoms) to estimate the fracture toughness for both Si and SiO_2 according to the following equation:

$$K_\mathrm{IC} = \sigma_\mathrm{f}\sqrt{2\pi r} \qquad r = 0.4–1.6\,\mathrm{nm}\,. \tag{25.10}$$



Fig. 25.4 Schematic of crack tip and coordinate systems used in (25.9) to describe a stress field around the crack tip in terms of the stress intensity parameter, K_I [25.38]

Fatigue Strength

In addition to the properties mentioned so far that can be evaluated from quasi-static bending tests, the fatigue properties of nanostructures are also of interest. This is especially true for MEMS/NEMS involving vibrating structures such as oscillators and comb drives [25.58] and hinges in digital micromirror devices [25.59]. To study the fatigue properties of the nanobeams, *Sundararajan* and *Bhushan* [25.38] applied monotonic cyclic stresses using an AFM, Fig. 25.5a. Similar to the bending test, the diamond tip is first positioned at the center of the beam span. In order to ensure that the tip is always in contact with the beam (as opposed to impacting it), the piezo is first extended by a distance D_1, which ensures a minimum stress on the beam. After this extension, a cyclic displacement of amplitude, D_2, is applied continuously until failure of the beam occurs.



Fig. 25.5 **(a)** Schematic showing the details of the technique to study fatigue behavior of the nanobeams. The diamond tip is located at the middle of the span, and a cyclic load at 4.2 Hz is applied to the beam by forcing the piezo to move in the pattern shown. An extension is made every 300 s to compensate for the piezo drift to ensure that the load on the beam is kept fairly constant. **(b)** Data from a fatigue experiment on a nanobeam until failure. The normal load is computed from the raw vertical deflection signal. The compensations for piezo drift keep the load fairly constant [25.38]

This results in the application of a cyclic load to the beam. The maximum frequency of the cyclic load that could be attained using the AFM by *Sundararajan* and *Bhushan* [25.38] was 4.2 Hz. The vertical deflection signal of the tip is monitored throughout the experiment. The signal follows the pattern of the piezo input up to failure, which is indicated by a sudden drop in the signal. During initial runs, piezo drift was observed that caused the piezo to gradually move away from the beam (i. e., to retract), resulting in a continuous decrease in the applied normal load. In order to compensate for this, the piezo is given a finite extension of 75 nm every 300 s, as shown in Fig. 25.5a. This results in keeping the applied loads fairly constant. The normal load variation (calculated from the vertical deflection signal) from a fatigue test is shown in Fig. 25.5b. The cyclic stress amplitudes (corresponding to D_2) and fatigue lives are recorded for every sample tested. Values for D_1 are set such that minimum stress levels are about 20% of the bending strengths.

25.1.3 Bending Tests Using a Nanoindenter

Quasi-static bending tests of micro/nanostructures are also carried out using a nanoindenter [25.39, 40]. The advantage of the nanoindenter is that loads up to about 500 mN, higher than that in AFM (up to about 100 µN), can be used for structures requiring high loads for experiments. To avoid the indenter tip pushing into the specimen, a blunt tip is used in the bending and fatigue tests. *Li* et al. [25.40] used a diamond conical indenter with a radius of 1 µm and an included angle of 60°. The load position used was at the center of the span for the bridge beams and 10 µm off from the free end of the cantilever beams. An optical microscope with a magnification of 1,500× or an in situ AFM is used to locate the loading position. Then the specimen is moved under the indenter location with a resolution of about 200 nm in the longitudinal direction and less than 100 nm in the lateral direction.

Using the analysis presented earlier, elastic modulus and bending strength of the beams can be obtained from the load-displacement curves [25.40]. For fatigue tests, an oscillating load is applied and contact stiffness is measured during the tests. A significant drop in the contact stiffness during the test is a measure of the number of cycles to failure [25.39].

25.2 Experimental Results and Discussion

25.2.1 Indentation and Scratch Tests of Various Materials Using Micro/Nanoindenters

Studies have been conducted on five different materials: undoped single-crystal Si(100), undoped polysilicon film, SiO_2 film, SiC film, electroless deposited Ni-11.5 wt% P amorphous film, and electroplated Au film [25.40, 50, 51]. A 3-μm thick polysilicon film was deposited by a low pressure chemical vapor deposition (LPCVD) process on a Si(100) substrate. The 1-μm thick SiO_2 film was deposited by a plasma enhanced chemical vapor deposition (PECVD) process on a Si(111) substrate. A 3-μm thick 3C-SiC film was epitaxially grown using an atmospheric pressure chemical vapor deposition (APCVD) process on a Si(100) substrate. A 12-μm thick Ni-P film was electroless plated on a 0.8-mm-thick Al-4.5 wt% Mg alloy substrate. A 3-μm-thick Au film was electroplated on a Si(100) substrate.

Hardness and Elastic Modulus

Hardness and elastic modulus measurements are made using a nanoindenter [25.40]. The hardness and elastic modulus values of various materials at a peak indentation depth of 50 nm are summarized in Fig. 25.6 and Table 25.1. The SiC film exhibits the highest hardness of about 25 GPa and an elastic modulus of about 395 GPa among the samples examined, followed by the undoped Si(100), undoped polysilicon film, SiO_2 film, Ni-P film, and Au film. The hardness and elastic modulus data of the undoped Si(100) and undoped polysilicon film are comparable. For the metal alloy films, the Ni-P film exhibits higher hardness and elastic modulus than the Au film.

Table 25.1 Hardness, elastic modulus, fracture toughness, and critical load results of the bulk single-crystal Si(100) and thin films of undoped polysilicon, SiO_2, SiC, Ni-P, and Au

Samples	Hardness (GPa)	Elastic modulus (GPa)	Fracture toughness $(\mathrm{MPa\,m^{1/2}})$	Critical load (mN)
Undoped Si(100)	12	165	0.75	11
Undoped polysilicon film	12	167	1.11	11
SiO_2 film	9.5	144	0.58 (Bulk)	9.5
SiC film	24.5	395	0.78	14
Ni-P film	6.5	130		0.4 (Plowing)
Au film	4	72		0.4 (Plowing)



Fig. 25.6 Bar chart summarizing the hardness, elastic modulus, fracture toughness, and critical load (from scratch tests) results of the bulk undoped single-crystal Si(100) and thin films of undoped polysilicon, SiO_2, SiC, Ni-P, and Au [25.40]

Fracture Toughness

The optical images of Vickers indentations made using a microindenter at a normal load of 0.5 N held for 15 s on the undoped Si(100), undoped polysilicon film, and SiC film are shown in Fig. 25.7 [25.51]. The SiC film exhibits the smallest indentation mark, followed by the undoped polysilicon film and undoped Si(100). These Vickers indentation depths are smaller than one-third of the film thickness. Thus, the influence of the substrate on the fracture toughness of the films can be ignored. In addition to the indentation marks, radial cracks are observed emanating from the indentation corners. The SiC film shows the longest radial crack length, followed by the undoped Si(100) and undoped polysilicon film. The radial cracks for the undoped Si(100) are straight, whereas those for the SiC and undoped polysilicon film are not straight but go in a zigzag manner. The fracture toughness (K_{IC}) is calculated using (25.1).

The fracture toughness values of all samples are summarized in Fig. 25.6 and Table 25.1. The SiO_2 film used in this study is about 1 µm thick, which is not thick enough for a fracture toughness measurement. The fracture toughness values of bulk silica are listed instead for a reference. The Ni-P and Au films exhibit very high fracture toughness values that cannot be measured by indentation methods. For other samples, the undoped polysilicon film has the highest value, followed by the undoped Si(100), SiC film, and SiO_2 film. For the undoped polysilicon film, the grain boundaries can stop the radial cracks and change the propagation directions of the radial cracks, making the propagation of these cracks more difficult. Values of fracture toughness for the undoped Si(100) and SiC film are comparable. Since the undoped Si(100) and SiC film are single crystal, no grain boundaries are present to stop the radial cracks and change the propagation directions of the radial cracks. This is why the SiC film shows a lower fracture toughness value than the bulk polycrystal SiC materials of 3.6 MPa $m^{1/2}$ [25.60].



Fig. 25.7 Optical images of Vickers indentations made at a normal load of 0.5 N held for 15 s on the undoped Si(100), undoped polysilicon film, and SiC film [25.51]

Scratch Resistance

The scratch resistance of various materials has been studied using a nanoindenter by *Li* et al. [25.40]. Figure 25.8 compares the coefficient of friction and scratch depth profiles as a function of increasing normal load and optical images of three regions over scratches: at the beginning of the scratch (indicated by A on the friction profile), at the point of initiation of damage at which the coefficient of friction increases to a high value or increases abruptly (indicated by B on the friction profile), and towards the end of the scratch (indicated by C on the friction profile) for all samples. Note that the ramp loads for the Ni-P and Au range are from 0.2 to 5 mN, whereas the ramp loads for other samples are from 0.2 to 20 mN. All samples exhibit a continuous increase in the coefficient of friction with increasing normal load from the beginning of the scratch. The continuous increase in the coefficient of friction during scratching is attributed to the increasing plowing of the sample by the tip with increasing normal load, as shown in the SEM images in Fig. 25.8. The abrupt increase in the coefficient of friction is associated with catastrophic failure, as well as significant plowing of the tip into the sample. Before the critical load, the coefficient of friction of the undoped polysilicon, SiC, and SiO_2 films increased at a slower rate and was smoother than that of the other samples. The undoped Si(100) exhibits some bursts in the friction profiles before the critical load. At the critical load, the SiC and undoped polysilicon films exhibit a small increase in the coefficient of friction, whereas the undoped Si(100) and undoped polysilicon film exhibit a sudden increase in the coefficient of friction. The Ni-P and Au films show a continuous increase in the coefficient of friction, indicating the behavior of a ductile metal. The bursts in the friction profile might result from the plastic deformation and material pile-up in front of the scratch tip. The Au film exhibits a higher coefficient of friction than the Ni-P film, because it has lower hardness and elastic modulus values than the Ni-P film.

The SEM images show that below the critical loads the undoped Si(100) and undoped polysilicon film were damaged by plowing, associated with the plastic flow of the material and formation of debris on the sides of the scratch. For the SiC and SiO_2 films, in region A, a plowing scratch track was found without any debris on the side of the scratch, which is probably responsible for the smoother curve and slower increase in the


Coefficient of friction
Scratch depth (nm)
Region A
Region B
Region C
Undoped Si(100)
Before scratch
After scratch
During scratch
Friction
A
B
C
Undoped polysilicon film
SiO2 film
SiC film
Ni-P film
Au film
1.2
0.8
0.4
0.0
500
0
– 500
– 1000
– 1500
1000
–3000
0
5
10
15
20
1
2
3
4
5
Normal load (mN)
2 µm

Fig. 25.8 Coefficient of friction and scratch depth profiles as a function of increasing normal load and optical images of three regions over scratches: at the beginning of the scratch (indicated by A on the friction profile), at the point of initiation of damage at which the coefficient of friction increases to a high value or increases abruptly (indicated by B on the friction profile), and towards the end of the scratch (indicated by C on the friction profile) for all samples [25.40]

coefficient of friction before the critical load. After the critical load, for the SiO_2 film, delamination of the film from the substrate occurred, followed by cracking along the scratch track. For the SiC film, only several small debris particles were found without any cracks on the side of the scratch, which is responsible for the small increase in the coefficient of friction at the critical load. For the undoped Si(100), cracks were found on the side of the scratch right from the critical load and up, which is probably responsible for the big bursts in the friction profile. For the undoped polysilicon film, no cracks were found on the side of the scratch at the critical load. This might result from grain boundaries, which can stop the propagation of cracks. At the end of the scratch, some of the surface material was torn away and cracks were found on the side of the scratch in the undoped Si(100). A couple of small cracks were found in the undoped polysilicon and SiO_2 films. No crack was found in the SiC film. Even at the end of the scratch, less debris was found in the SiC film. A curly chip was found at the end of the scratch in both Ni-P and Au films. This is a typical characteristic of ductile metal alloys. The Ni-P and Au films were damaged by plowing right from the beginning of the scratch with material pile-up at the side of the scratch.

The scratch depth profiles obtained during and after the scratch on all samples with respect to initial profile, after the cylindrical curvature is removed, are plotted in Fig. 25.8. Reduction in scratch depth is observed after scratching as opposed to during scratching. This reduction in scratch depth is attributed to an elastic recovery after removal of the normal load. The scratch depth after scratching indicates the final depth, which reflects the extent of permanent damage and plowing of the tip into the sample surface and is probably more relevant for visualizing the damage that can occur in real applications. For the undoped Si(100), undoped polysilicon film, and SiO_2 film, there is a large scatter in the scratch depth data after the critical loads, which is associated with the generation of cracks, material removal, and debris. The scratch depth profile is smooth for the SiC film. It is noted that the SiC film exhibits the lowest scratch depth among the samples examined. The scratch depths of the undoped Si(100), undoped polysilicon film, and SiO_2 film are comparable. The Ni-P and Au films exhibit much larger scratch depths than other samples. The scratch depth of the Ni-P film is smaller than that of the Au film.

The critical loads estimated from friction profiles for all samples are compared in Fig. 25.6 and Table 25.1. The SiC film exhibits the highest critical load of about 14 mN, as compared to other samples. The undoped Si(100) and undoped polysilicon film show comparable critical load of about 11 mN, whereas the SiO_2 film shows a low critical load of about 9.5 mN. The Ni-P and Au films were damaged by plowing right from the beginning of the scratch.

25.2.2 Bending Tests of Nanobeams Using an AFM

Bending tests have been performed on Si and SiO_2 nanobeam arrays [25.38, 54]. The single-crystal silicon bridge nanobeams were fabricated by bulk micromachining incorporating enhanced-field anodization using an AFM [25.37]. The Si nanobeams are oriented along the [110] direction in the (001) plane. Subsequent thermal oxidation of the beams results in the formation of SiO_2 beams. The cross section of the nanobeams is trapezoidal owing to the anisotropic wet etching process. SEM micrographs of Si and SiO_2 nanobeam arrays and a schematic of the shape of a typical nanobeam are shown in Fig. 25.9. The actual widths and thicknesses of nanobeams were measured using an AFM in tapping mode prior to tests using a standard Si tapping mode tip (tip radius < 10 nm). Surface roughness measurements of the nanobeam surfaces in tapping mode yielded a σ of 0.7 ± 0.2 nm and peak-to-valley (P–V) distance of 4 ± 1.2 nm for Si and a σ of 0.8 ± 0.3 nm and a P–V distance of 3.1 ± 0.8 nm for SiO_2. Prior to testing, the Si nanobeams were cleaned by immersing them in a "piranha etch" solution (3 : 1 solution by volume of 98% sulphuric acid and 30% hydrogen peroxide) for 600 s to remove any organic contaminants.

Bending Strength

Figure 25.10 shows typical load-displacement curves for Si and SiO_2 beams that were bent to failure [25.38, 54]. The upper width (w_1) of the beams is indicated in the figure. Also indicated are the elastic modulus values obtained from the slope of the load-displacement curve



Fig. 25.9 **(a)** SEM micrographs of nanobeam arrays, and **(b)** a schematic of the shape of a typical nanobeam. The trapezoidal cross section is due to the anisotropic wet etching during the fabrication [25.54]

(25.5). All the beams tested showed linear elastic behavior followed by abrupt failure, which is suggestive of brittle fracture. Figure 25.11 shows the scatter in the values of elastic modulus obtained for both Si and SiO$_2$ along with the average values (± standard deviation). The scatter in the values may be due to differences in the orientation of the beams with respect to the trench and the loading point being a little off center with respect to the beam span. The average values are a little higher than the bulk values (169 GPa for Si[110] and 73 GPa for SiO$_2$ in Table 25.2). However, the values of E obtained from (25.5) have an error of about 20% due to the uncertainties in beam dimensions and spring constant of the tip/cantilever (which affects the measured load). Hence the elastic modulus values on the nanoscale can be considered comparable to bulk values.



Fig. 25.10 Typical load-displacement curves of silicon and SiO$_2$ nanobeams. The curves are linear until sudden failure, indicative of brittle fracture of the beams. The elastic modulus (E) values calculated from the curves are shown. The dimensions of the Si beam were $w_1 = 295$ nm, $w_2 = 484$ nm, and $t = 255$ nm, while those of the SiO$_2$ beam were $w_1 = 250$ nm, $w_2 = 560$ nm, and $t = 425$ nm [25.54]



Fig. 25.11 Elastic modulus values measured for Si and SiO$_2$. The average values are shown. These are comparable to bulk values, which demonstrates that elastic modulus shows no specimen size dependence [25.38]

Most of the beams when loaded quasi-statically at the center of the span broke at the ends, as shown in Fig. 25.12a, which is consistent with the fact that maximum tensile stresses occur on the top surfaces near the ends. (See FEM stress distribution results in Fig. 25.12b.) Figure 25.13 shows the values of bending strength obtained for different beams. There appears to be no trend in bending strength with the upper width (w_1) of the beams. The large scatter is expected for the strength of brittle materials, since they are dependent on preexisting flaw population in the material and, hence, are statistical in nature. The Weibull distribution, a statistical analysis, can be used to describe the scatter in the bending strength values. The means of the Weibull distributions were found to be 17.9 GPa and 7.6 GPa for Si and SiO$_2$, respectively. Previously reported numbers of strengths range from 1 to 6 GPa for silicon [25.19, 20, 22–25, 27, 45, 61, 62] and about 1 GPa for SiO$_2$ [25.34] microscale specimens. This clearly indicates that bending strength shows a specimen size dependence. Strength of brittle materials is dependent on preexisting flaws in the material. Since for nanoscale specimens the volume is smaller than for micro- and macroscale specimens, the flaw population will be smaller as well, resulting in higher values of strength.

Table 25.2 Summary of measured parameters from quasi-static bending tests

Sample	Elastic modulus E (GPa)		Bending strength σ_b (GPa)		Fracture toughness K_{IC} (MPa $\sqrt{m}$)		
	Measured	Bulk value	Measured	Reported (microscale)	Estimated	Reported (microscale)	Bulk value
Si	182±11	169^1	18±3	$< 10^3$	1.67±0.4	$0.6-1.65^5$	0.9^6
SiO_2	85±13	73^2	7.6±2	$< 2^4$	0.60±0.2	$0.5-0.9^4$	–

[1] Si(110), [25.63] [2] [25.64] [3] [25.19, 20, 22–25, 45, 61, 62] [4] [25.34] [5] [25.30–33] [6] [25.57]



Fig. 25.12 **(a)** SEM micrographs of nanobeams that failed during quasi-static bending experiments. The beams failed at or near the ends, which is the location of maximum tensile bending stress [25.54], and **(b)** bending stress distribution for silicon nanobeam, indicating that the maximum tensile stresses occur on the top surfaces near the fixed ends



Fig. 25.13 Bending strength values obtained from bending experiments. Average values are indicated. These values are much higher than values reported for microscale specimens, indicating that bending strength shows a specimen size effect [25.38]



Fig. 25.14 Fracture toughness (K_{IC}) values for increasing values of r corresponding to distance between neighboring atoms in {111} planes of silicon (0.4 nm). Hence r values between 0.4 and 1.6 nm are chosen. The K_{IC} values thus estimated are comparable to values reported by others for both Si and SiO_2 [25.38]

Fracture Toughness

Estimates of fracture toughness calculated using (25.10) for Si and SiO_2 are shown in Fig. 25.14 [25.38]. The results show that the K_{IC} estimate for Si is about 1–2 MPa $\sqrt{m}$, whereas for SiO_2 the estimate is about 0.5–0.9 MPa $\sqrt{m}$. These values are comparable to values reported by others on larger specimens for Si [25.30–33] and SiO_2 [25.34]. The high values obtained for Si could be due to the fact that the scratches, despite being quite sharp, still have a finite radius of about 100 nm. The bulk value for silicon is about 0.9 MPa $\sqrt{m}$ (Table 25.2). Fracture toughness is considered a material property and is believed to be independent of specimen size. The values obtained in this study, given its limitations, appear to show that fracture toughness is comparable, if not a little higher on the nanoscale.

Fatigue Strength

Fatigue strength measurements of Si nanobeams have been carried out by *Sundararajan* and *Bhushan* [25.38] using an AFM and *Li* and *Bhushan* [25.39] using a nanoindenter. Various stress levels were applied to nanobeams by *Sundararajan* and *Bhushan* [25.38]. The minimum stress was 3.5 GPa for Si beams and 2.2 GPa for SiO_2 beams. The frequency of applied load was 4.2 Hz. In general, the fatigue life decreased with increasing mean stress as well as increasing stress amplitude. When the stress amplitude was less than 15% of the bending strength, the fatigue life was greater than 30,000 cycles for both Si and SiO_2. However, the mean stress had to be less than 30% of the bending strength for a life of greater than 30,000 for Si, whereas even at a mean stress of 43% of the bending strength, SiO_2 beams showed a life greater than 30,000. During fatigue, the beams broke under the loading point or at the ends when loaded at the center of the span. This was different from the quasi-static bending tests, where the beams broke at the ends almost every time. This could be due to the fact that the stress levels under the load and at the ends are not that different and fatigue crack propagation could occur at either location. Figure 25.15 shows a nanoscale *S-N* curve with bending stress (*S*) as a function of fatigue in cycles (*N*) with an apparent endurance life at lower stress. This study clearly demonstrates that fatigue properties of nanoscale specimens can be studied.



Fig. 25.15 Fatigue test data showing applied bending stress as a function of number of cycles. A single load-unload sequence is considered 1 cycle. The bending strength data points are, therefore, associated with $\frac{1}{2}$ cycle, since failure occurs upon loading [25.38]

SEM Observations of Fracture Surfaces

Figure 25.16 shows SEM images of the fracture surfaces of nanobeams broken during quasi-static bending, as well as fatigue [25.38]. In the quasi-static cases, the maximum tensile stresses occur on the top surface, so it is reasonable to assume that fracture initiated at or


a) Quasi-static bending
Si
Si
200 nm
200 nm
SiO_2
200 nm
b) Fatigue
Si
Si
200 nm
200 nm
Fatigue life = 2 k cycles
Mean stress = 8.0 GPa,
stress ampl. = 4.6 GPa
Fatigue life = 6 k cycles
Mean stress = 6.5 GPa
stress ampl. = 3.0 GPa
SiO_2
SiO_2
200 nm
200 nm
Fatigue life = 0.1 k cycles
Mean stress = 4.8 GPa
stress ampl. = 2.6 GPa
Fatigue life = 13.4 k cycles
Mean stress = 3.7 GPa
stress ampl. = 1.6 GPa

Fig. 25.16a,b SEM micrographs of fracture surfaces of silicon and SiO_2 beams subjected to **(a)** quasi-static bending and **(b)** fatigue [25.38] near the top surface and propagated downward. The fracture surfaces of the beams suggest a cleavage type of fracture. Silicon beam surfaces show various ledges or facets, which is typical for crystalline brittle materials. Silicon usually fractures along the (111) plane, due to this plane having the lowest surface energy to overcome by a propagating crack. However, failure has also been known to occur along the (110) planes in microscale specimens, despite the higher energy required compared to the (111) planes [25.45]. The plane normal to the beam direction in these samples is the (110) plane, while (111) planes will be oriented at 35° from the (110) plane. The presence of facets and irregularities on the silicon surface in Fig. 25.16a suggest that it is a combination of these two types of fractures that has occurred. Since the stress levels are very high for these specimens, it is reasonable to assume that crack propagating forces will be high enough to result in (110) type failures.

In contrast, the silicon fracture surfaces under fatigue, shown in Fig. 25.16b, appear very smooth without facets or irregularities. This is suggestive of low energy fracture, i. e., of (111) type fracture. We do not see evidence of fatigue crack propagation in the form of steps or striations on the fracture surface. We believe that for the stress levels applied in these fatigue experiments, failure in silicon occurred via cleavage associated with "static fatigue" type of failures.

SiO_2 shows very smooth fracture surfaces for both quasi-static bending and fatigue. This is in contrast to the hackled surface one might expect for the brittle failure of an amorphous material on the macroscale. However, in larger scale fracture surfaces for such materials, the region near the crack initiation usually appears smooth or mirror-like. Since the fracture surface here is so small and very near the crack initiation site, it is not unreasonable to see such a smooth surface for SiO_2 on this scale. There appears to be no difference between the fracture surfaces obtained by quasi-static bending and fatigue for SiO_2.

Summary of Mechanical Properties Measured Using Quasi-Static Bending Tests

Table 25.2 summarizes the various properties measured via quasi-static bending in this study [25.38]. Also shown are bulk values of the parameters, along with values reported on larger scale specimens by other researchers. Elastic modulus and fracture toughness values appear to be comparable to bulk values and show no dependence on specimen size. However, bending strength shows a clear specimen size dependence with nanoscale numbers being twice as large as numbers reported for larger-scale specimens.

25.2.3 Bending Tests of Microbeams Using a Nanoindenter

Bending tests have been performed on Ni-P and Au microbeams [25.40]. The Ni-P cantilever microbeams were fabricated by focused ion beam machining technique. The dimensions were $10 \times 12 \times 50\,\mu m^3$. Notches with a depth of $3\,\mu m$ and a tip radius of $0.25\,\mu m$ were introduced in the microbeams to facilitate failure at a lower


Ni-P cantilever microbeam

Load-displacement curve

Broken microbeam

FEM stress contour at 20 mN

Fig. 25.17 SEM micrographs of the new and broken beams, load-displacement curve, and FEM stress contour for the notched Ni-P cantilever microbeam [25.40]



Fig. 25.18 SEM micrographs of the new and deformed beams, load-displacement curve, and FEM stress contour for the Au bridge microbeam [25.40]

load in the bending tests. The Au bridge microbeams were fabricated by electroplating technique.

Figure 25.17 shows the SEM images, load displacement curve, and FEM stress contour for the notched Ni-P cantilever microbeam that was bent to failure [25.40]. The distance between the loading position and the fixed end is 40 µm. The 3-µm-deep notch is 10 µm from the fixed end. The notched beam showed linear behavior followed by abrupt failure. The FEM stress contour shows that there is higher stress concentration at the notch tip. The maximum tensile stress σ_m at the notch tip can be analyzed using Griffith fracture theory as follows [25.53]:

$$\sigma_\mathrm{m} \approx 2\sigma_\mathrm{o}\left(\frac{c}{\rho}\right)^{1/2} , \qquad (25.11)$$

where σ_o is the average applied tensile stress on the beam, c is the crack length, and ρ is the crack tip radius. Therefore, elastic-plastic deformation will first occur locally at the end of the notch tip, followed by abrupt fracture failure after the σ_m reaches the ultimate tensile strength of Ni-P, even though the rest of the beam is still in the elastic regime. The SEM image of the fracture surface shows that the fracture started right from the notch tip with plastic deformation characteristic. This indicates that although local plastic deformation occurred at the notch tip area, the whole beam failed catastrophically. The present study shows that FEM simulation can predict well the stress concentration and helps in understanding the failure mechanism of the notched beams.

Figure 25.18 shows the SEM images, load-displacement curve and FEM stress contour for the Au bridge microbeam that was deformed by the indenter [25.40]. The recession gap between the beam and substrate is about 7 µm, which is not large enough to break the beam at the load applied. From the load-displacement curve, we note that the beam experienced elastic-plastic deformation. The FEM stress contour shows that the maximum tensile stress is located at the fixed ends, whereas the minimum compressive stress is located around the center of the beam. The SEM image shows that the beam has been permanently deformed. No crack was found on the beam surface. The present study shows a possibility for mechanically forming the Au film into the shape as needed. This may help in designing/fabricating functionally complex smart micro/nanodevices that need conductors for power supply and input/output signals.

25.3 Finite Element Analysis of Nanostructures with Roughness and Scratches

Micro/nanostructures have some surface topography and local scratches dependent upon the manufacturing process. Surface roughness and local scratches may compromise the reliability of the devices and their effect needs to be studied. Finite element modeling is used to perform parametric analysis to study the effect of surface roughness and scratches in different well-defined forms on tensile stresses that are responsible for crack propagation [25.46, 47]. The analysis has been carried out on trapezoidal beams supported at the bottom whose data (on Si and SiO_2 nanobeams) have been presented earlier.

The finite element analysis has been carried out using the static analysis of ANSYS 5.7, which calculates the deflections and stresses produced by the applied loading. The type of element selected for the present study was the SOLID95, which allows the use of different shapes without much loss of accuracy. This element is 3-D with 20 nodes, each node having three degrees of freedom that imply translation in the x, y, and z directions. Each nanobeam cross section is divided into six elements along the width and the thickness and 40 elements along the length. SOLID95 has plasticity, creep, stress stiffening, large deflection, and large strain capabilities. The large displacement analysis is used for large loads. The mesh is kept finer near the asperities and the scratches in order to take into account variation in the bending stresses. The beam materials studied are made of single-crystal silicon (110) and SiO$_2$ films whose data have been presented earlier. Based on bending experiments presented earlier, the beam materials can be assumed to be linearly elastic isotropic materials. Young's modulus of elasticity (E) and Poisson's ratio (ν) for Si and SiO$_2$ are 169 GPa [25.63] and 0.28 [25.57], and 73 GPa [25.64] and 0.17 [25.64], respectively. A sample nanobeam of silicon was chosen for performing most of the analysis, as silicon is the most widely used MEMS/NEMS material. The cross section of the fabricated beams used in the experiment is trapezoidal and supported at the bottom, Fig. 25.9. The following dimensions are used: $w_1 = 200$ nm, $w_2 = 370$ nm, $t = 255$ nm, and $\ell = 6$ µm. In the boundary conditions, the displacements are constrained in all directions on the bottom surface for 1 µm from each end. A point load applied at the center of the beam is simulated with the load being applied at three closely located central nodes on the beam used. It has been observed from the experimental results that the Si nanobeam breaks at around 80 µN. Therefore, in this analysis, a nominal load of 70 µN is selected. At this load, deformations are large and a large displacement option is used.



Fig. 25.19 **(a)** Plots showing the geometries of modeled roughness – semicircular and grooved asperities along the nanobeam length with defined geometrical parameters. **(b)** (*See on next page.*) Schematic showing semicircular asperities and scratches in the transverse direction, followed by the illustration of the mesh created on the beam with fine mesh near the asperities and scratches. Also shown are the semicircular asperities and scratches at different pitch values

To study the effect of surface roughness and scratches on the maximum bending stresses the following cases were studied. First, the semicircular and grooved asperities in the longitudinal direction with defined geometrical parameters are analyzed, Fig. 25.19a. Next, semicircular asperities and scratches placed along the transverse direction at a distance c from the end and separated by pitch p from each other are analyzed, Fig. 25.19b. Lastly, the beam material is assumed to be either purely elastic, elastic-plastic, or elastic-perfectly plastic. In the following section, we begin with the stress distribution in smooth nanobeams followed by the effect of surface roughness in the longitudinal and transverse directions and scratches in the transverse direction.

25.3.1 Stress Distribution in a Smooth Nanobeam

Figure 25.20 shows the stress and vertical displacement contours for a nanobeam supported at the bottom and loaded at the center [25.46, 47]. As expected, the maximum tensile stress occurs at the ends, while the maximum compressive stress occurs under the load at


b)
Semicircular asperities
Scratches
Transverse direction
R
L
h
c
c
p
c
Single asperity
Single scratch
R = 25 nm, c = 0 nm
c = 50 nm, L = 100 nm, h = 20 nm
Throughout the nanobeam
p = 50 nm
4 Scratches
p = 100 nm
p = 100 nm
p = 200 nm

Fig. 25.19b



Fig. 25.20 Bending stress contours, vertical displacement contours, and bending stress contours after loading trapezoidal Si nanobeam ($w_1 = 200\,\text{nm}$, $w_2 = 370\,\text{nm}$, $t = 255\,\text{nm}$, $\ell = 6\,\mu\text{m}$, $E = 169\,\text{GPa}$, $\nu = 0.28$) at $70\,\mu\text{N}$ load [25.47]

the center. Stress contours obtained at a section of the beam from the front and side are also shown. In the beam cross section, the stresses remain constant at a given vertical distance from one side to another and change with a change in vertical location. This can be explained by the fact that the bending moment is constant at a particular cross section, so the stress is only dependent on the distance from the neutral axis. However, in cross section A-A the high tensile and compressive stresses are localized near the end of the beam at top and bottom, respectively, whereas the lower values are spread out away from the ends. High value of tensile stresses occurs near the ends because of high bending moment.

25.3.2 Effect of Roughness in the Longitudinal Direction

The roughness in the form of semicircular and grooved asperities in the longitudinal direction on the maximum bending stresses are analyzed [25.47]. The radius R and depth L are kept fixed at 25 nm, while the number of asperities is varied and their effect is observed on the maximum bending stresses. Figure 25.21 shows the variation of maximum bending stresses as a function of asperity shape and the number of asperities. The maximum bending stresses increase as the asperity number increases for both semicircular and grooved asperities. This can be attributed to the fact that as the asperity number increases, the moment of inertia decreases for that cross section. Also, the distance from the neutral axis increases because the neutral axis shifts downwards. Both these factors lead to the increase in the maximum bending stresses, and this effect is more pronounced in the case of semicircular asperity as it exhibits a higher value of maximum bending stress than that in grooved asperity. Figure 25.21 shows the stress contours obtained at a section of the beam from the front side for both cases when we have a single semicircular asperity and when four adjacent semicircular asperities are present. Trends are similar to those observed earlier for a smooth nanobeam (Fig. 25.20).

25.3.3 Effect of Roughness in the Transverse Direction and Scratches

We analyze semicircular asperities when placed along the transverse direction followed by the effect of scratches on the maximum bending stresses in varying numbers and pitch [25.47]. In the analysis of semicircular transverse asperities, three cases were considered, which included a single asperity and asperities throughout the nanobeam surface separated by pitch equal to 50 nm and 100 nm. In all of these cases, c value was kept equal to 0 nm. Figure 25.22 shows that the value of maximum tensile stress is 42 GPa, which is much larger than the maximum tensile stress value with no asperity of 16 GPa, or when the semicircular asperity is present in the longitudinal direction. It is also observed that the maximum tensile stress does not vary with the number of asperities or the pitch, while the maximum compres-



Fig. 25.21 Effect of longitudinal semicircular and grooved asperities in different numbers on maximum bending stresses after loading trapezoidal Si nanobeams ($w_1 = 200$ nm, $w_2 = 370$ nm, $t = 255$ nm, $\ell = 6$ µm, $E = 169$ GPa, $\nu = 0.28$, load = 70 µN). Bending stress contours obtained in the beam with semicircular single asperity and four adjacent asperities of $R = 25$ nm [25.47]



Fig. 25.22 Effect of transverse semicircular asperities located at different pitch values on the maximum bending stresses after loading trapezoidal Si nanobeams ($w_1 = 200$ nm, $w_2 = 370$ nm, $t = 255$ nm, $\ell = 6$ µm, $E = 169$ GPa, $\nu = 0.28$, load = 70 µN). Bending stress contours obtained in the beam with semicircular single asperity and semicircular asperities throughout the nanobeam surface at $p = 50$ nm [25.47]

sive stress does increase dramatically for the asperities present throughout the beam surface from its value when a single asperity is present. Maximum tensile stress occurs at the ends, and an increase in p does not add any asperities at the ends, whereas asperities are added in the central region where compressive stresses are maximum. The semicircular asperities present at the center cause the local perturbation in the stress distribution at the center of the asperity where load is being applied, leading to a high value of maximum compressive stress [25.65]. Figure 25.22 also shows the stress contours obtained at a section of the beam from the front and side for both cases when there is a single semicircular asperity and when asperities are present throughout the beam surface at a pitch equal to 50 nm. Trends are similar to those observed earlier for a smooth nanobeam (Fig. 25.20).

In the study pertaining to scratches, the number of scratches are varied along with the variation in the pitch. Furthermore, the load is applied at the center of the beam and at the center of the scratch near the end, as for all the cases. In all of these, c value was kept equal to 50 nm and L value was equal to 100 nm with h value being 20 nm. Figure 25.23 shows that the value of maximum tensile stress remains almost the same with the number of scratches for both types of loading – that is, when load is applied at the center of the beam and at the center of the scratch near the end. This is because the maximum tensile stress occurs at the beam ends no matter where the load gets applied. But the presence of scratch does increase the maximum tensile stress compared to its value for a smooth nanobeam, although the number of scratches no longer matter as the maximum tensile stress occurring at the nanobeam end is unaffected by the presence of more scratches beyond the first scratch in the direction toward the center. The value of the tensile stress is much lower when the load is applied at the center of scratch, and it can be explained as follows. The negative bending moment at the end near the applied load decreases with load offset after two-thirds of the length of the beam [25.66]. Since this negative bending moment is responsible for tensile stresses, their behavior with the load offset is the same as the negative bending moment. Also, the value of maximum compressive stress when load is applied at the center of the nanobeam remains almost the same as the center geometry is unchanged due to the number of scratches and, hence, the maximum compressive stress occurring below the load at the center is same. On the other hand, when the load is applied at the center of the scratch we observe that the maximum compressive stress in-



Fig. 25.23 Effect of number of scratches along with the variation in the pitch on the maximum bending stresses after loading trapezoidal Si nanobeams ($w_1 = 200$ nm, $w_2 = 370$ nm, $t = 255$ nm, $\ell = 6\,\mu$m, $E = 169$ GPa, $\nu = 0.28$, load = 70 μN). Also shown is the effect of load when applied at the center of the beam and at the center of the scratch near the end [25.47]

creases dramatically because the local perturbation in the stress distribution at the center of the scratch where load is being applied leads to a high value of maximum compressive stress [25.65]. It increases further with the number of scratches and then levels off. This can be attributed to the fact that when there is another scratch present close to the scratch near the end, the stress concentration is more, as the effect of local perturbation in the stress distribution is more significant. However, this effect is insignificant when more than two scratches are present.

Now we address the effect of pitch on the maximum compressive stress when the load is applied at the center of the scratch near the end. When the pitch is up to a value of 200 nm the maximum compressive stress increases with the number of scratches, as discussed earlier. On the other hand, when the pitch value goes beyond 225 nm this effect is reversed. This is because the presence of another scratch no longer affects the local perturbation in the stress distribution at the scratch near the end. Instead, more scratches at a fair distance distribute the maximum compressive stress at the scratch near the end and the stress starts going down. Such observations of maximum bending stresses can help in identifying the number of asperities and scratches allowed separated by an optimum distance from each other.



Fig. 25.24 Schematic representation of stress-strain curves and load-displacement curves for material when it is elastic, elastic-plastic, or elastic-perfectly plastic for a Si nanobeam ($w_1 = 200\,\mathrm{nm}$, $w_2 = 370\,\mathrm{nm}$, $t = 255\,\mathrm{nm}$, $\ell = 6\,\mu\mathrm{m}$, $E = 169\,\mathrm{GPa}$, tangent modulus in plastic range $= 0.5\,E$, $\nu = 0.28$) [25.47]

25.3.4 Effect on Stresses and Displacements for Materials That Are Elastic, Elastic-Plastic, or Elastic-Perfectly Plastic

This section deals with the beam modeled as elastic, elastic-plastic, and elastic-perfectly plastic to observe the variation in the stresses and displacements from an elastic model used so far [25.47]. Figure 25.24 shows the typical stress-strain curves for the three types of deformation regimes and their corresponding load-displacement curves obtained from the model of an Si nanobeam that are found to exhibit the same trends.

Table 25.3 shows the comparison of maximum von Mises stress and maximum displacements for

Table 25.3 Stresses and displacements for materials that are elastic, elastic-plastic, or elastic-perfectly plastic (load $= 70\,\mu\mathrm{N}$, $w_1 = 200\,\mathrm{nm}$, $w_2 = 370\,\mathrm{nm}$, $t = 255\,\mathrm{nm}$, $\ell = 6\,\mu\mathrm{m}$, $R = 25\,\mathrm{nm}$, $E = 169\,\mathrm{GPa}$, tangent modulus in plastic range $= 0.5E$, $\nu = 0.28$)

	Elastic		**Elastic-plastic**		**Elastic-perfectly plastic**	
	Smooth nanobeam	**Single semicircular longitudinal asperity**	**Smooth nanobeam**	**Single semicircular longitudinal asperity**	**Smooth nanobeam**	**Single semicircular longitudinal asperity**
Max. von Mises stress (GPa)	18.2	19.3	13.5	15.2	7.8	9.1
Max. displacement (µm)	1.34	1.40	3.35	3.65	11.5	12.3

both smooth nanobeam and nanobeam with a defined roughness, which is single semicircular longitudinal asperity of R value equal to 25 nm for the three different models. It is observed that the maximum value of stress is obtained at a given load for elastic material, whereas the displacement is maximum for elastic-perfectly plastic material. Also, the pattern that the maximum bending stress value increases for a rough nanobeam still holds true in the other models as well.

25.4 Closure

Mechanical properties of nanostructures are necessary in designing realistic MEMS/NEMS devices. Most mechanical properties are scale-dependent. Micro/nanomechanical properties, hardness, elastic modulus, and scratch resistance of bulk materials of undoped single-crystal silicon (Si) and thin films of undoped polysilicon, SiO_2, SiC, Ni-P, and Au are presented. It is found that the SiC film exhibits higher hardness, elastic modulus, and scratch resistance as compared to other materials.

Bending tests have been performed on the Si and SiO_2 nanobeams and Ni-P and Au microbeams using an AFM and a depth-sensing nanoindenter, respectively. The bending tests were used to evaluate elastic modulus, bending strength (fracture stress), fracture toughness (K_{IC}), and fatigue strength of the beam materials. The Si and SiO_2 nanobeams exhibited elastic linear response with sudden brittle fracture. The notched Ni-P beam showed linear deformation behavior followed by abrupt failure. The Au beam showed elastic-plastic deformation behavior. Elastic modulus values of 182±11 GPa for Si(110) and 85±3 GPa for SiO_2 were obtained, which are comparable to bulk values. Bending strength values of 18±3 GPa for Si and 7.6±2 GPa for SiO_2 were obtained, which are twice as large as values reported on larger scale specimens. This indicates that bending strength shows a specimen size dependence. Fracture toughness value estimates obtained were $1.67 \pm 0.4\,\text{MPa}\sqrt{\text{m}}$ for Si and $0.60 \pm 0.2\,\text{MPa}\sqrt{\text{m}}$ for SiO_2, which are also comparable to values obtained on larger specimens. At stress amplitudes less than 15% of their bending strength and at mean stresses of less than 30% of the bending strength, Si and SiO_2 displayed an apparent endurance life of greater than 30,000 cycles. SEM observations of the fracture surfaces revealed a cleavage type of fracture for both materials when subjected to bending, as well as fatigue. The AFM and nanoindenters used in this study can be satisfactorily used to evaluate the mechanical properties of micro/nanoscale structures for use in MEMS/NEMS.

FEM simulations are used to predict the stress and deformation in nanostructures. The FEM has been used to analyze the effect of the type of surface roughness and scratches on stresses and deformation of nanostructures. We find that roughness affects the maximum bending stresses. The maximum bending stresses increase as the asperity number increases for both semicircular and grooved asperities in the longitudinal direction. When the semicircular asperity is present in the transverse direction the maximum tensile stress is much larger than the maximum tensile stress value with no asperity or when the semicircular asperity is present in the longitudinal direction. This observation suggests that the asperity in the transverse direction is more detrimental. The presence of scratches increases the maximum tensile stress. The maximum tensile stress remains almost the same with the number of scratches for two types of loading, that is, when load is applied at the center of the beam or at the center of the scratch near the end, although the value of the tensile stress is much lower when the load is applied at the center of the scratch. This means that the load applied at the ends is less damaging. This analysis shows that FEM simulations can be useful to designers to develop the most suitable geometry for nanostructures.

References

25.1 R. S. Muller, R. T. Howe, S. D. Senturia, R. L. Smith, R. M. White: *Microsensors* (IEEE, New York 1990)

25.2 I. Fujimasa: *Micromachines: A New Era in Mechanical Engineering* (Oxford Univ. Press, Oxford 1996)

25.3 W. S. Trimmer (Ed.): *Micromachines and MEMS, Classic and Seminal Papers to 1990* (IEEE, New York 1997)

25.4 B. Bhushan: *Tribology Issues and Opportunities in MEMS* (Kluwer, Dordrecht 1998)

25.5 G. T. A. Kovacs: *Micromachined Transducers Sourcebook* (WCB McGraw-Hill, Boston 1998)

25.6 S. D. Senturia: *Microsystem Design* (Kluwer, Boston 2001)

25.7 M. Gad-el-Hak: *The MEMS Handbook* (CRC, Boca Raton 2002)

25.8 T. R. Hsu: *MEMS and Microsystems* (McGraw-Hill, Boston 2002)

25.9 M. Madou: *Fundamentals of Microfabrication: The Science of Miniaturization*, 2nd edn. (CRC, Boca Raton 2002)

25.10 K. E. Drexler: *Nanosystems: Molecular Machinery, Manufacturing and Computation* (Wiley, New York 1992)

25.11 B. Bhushan: *Handbook of Micro/Nanotribology*, 2nd edn. (CRC, Boca Raton 1999)

25.12 G. Timp (Ed.): *Nanotechnology* (Springer, New York 1999)

25.13 E. A. Rietman: *Molecular Engineering of Nanosystems* (Springer, New York 2001)

25.14 H. S. Nalwa (Ed.): *Nanostructures Materials and Nanotechnology* (Academic, San Diego 2002)

25.15 W. A. Goddard, D. W. Brenner, S. E. Lyshevski, G. J. Iafrate: *Handbook of Nanoscience, Engineering, and Technology* (CRC, Boca Raton 2003)

25.16 B. Bhushan: *Principles and Applications of Tribology* (Wiley, New York 1999)

25.17 B. Bhushan: *Introduction to Tribology* (Wiley, New York 2002)

25.18 B. Bhushan: Macro- and microtribology of MEMS materials. In: *Modern Tribology Handbook*, ed. by B. Bhushan (CRC, Boca Raton 2001) pp. 1515–1548

25.19 S. Johansson, J. A. Schweitz, L. Tenerz, J. Tiren: Fracture testing of silicon microelements in-situ in a scanning electron microscope, J. Appl. Phys. **63** (1988) 4799–4803

25.20 F. Ericson, J. A. Schweitz: Micromechanical fracture strength of silicon, J. Appl. Phys. **68** (1990) 5840–5844

25.21 E. Obermeier: Mechanical and thermophysical properties of thin film materials for MEMS: Techniques and devices, Micromechan. Struct. Mater. Res. Symp. Proc. **444** (1996) 39–57

25.22 C. J. Wilson, A. Ormeggi, M. Narbutovskih: Fracture testing of silicon microcantilever beams, J. Appl. Phys. **79** (1995) 2386–2393

25.23 W. N. Sharpe, Jr., B. Yuan, R. L. Edwards: A new technique for measuring the mechanical properties of thin films, J. Microelectromech. Syst. **6** (1997) 193–199

25.24 K. Sato, T. Yoshioka, T. Anso, M. Shikida, T. Kawabata: Tensile testing of silicon film having different crystallographic orientations carried out on a silicon chip, Sens. Actuators A **70** (1998) 148–152

25.25 S. Greek, F. Ericson, S. Johansson, M. Furtsch, A. Rump: Mechanical characterization of thick polysilicon films: Young's modulus and fracture strength evaluated with microstructures, J. Micromech. Microeng. **9** (1999) 245–251

25.26 D. A. LaVan, T. E. Buchheit: Strength of polysilicon for MEMS devices, Proc. SPIE **3880** (1999) 40–44

25.27 E. Mazza, J. Dual: Mechanical behavior of a μm-sized single crystal silicon structure with sharp notches, J. Mech. Phys. Solids **47** (1999) 1795–1821

25.28 T. Yi, C. J. Kim: Measurement of mechanical properties for MEMS materials, Meas. Sci. Technol. **10** (1999) 706–716

25.29 H. Kahn, M. A. Huff, A. H. Heuer: Heating effects on the Young's modulus of films sputtered onto micromachined resonators, Microelectromech. Struct. Mater. Res. Symp. Proc. **518** (1998) 33–38

25.30 S. Johansson, F. Ericson, J. A. Schweitz: Influence of surface-coatings on elasticity, residual-stresses, and fracture properties of silicon microelements, J. Appl. Phys. **65** (1989) 122–128

25.31 R. Ballarini, R. L. Mullen, Y. Yin, H. Kahn, S. Stemmer, A. H. Heuer: The fracture toughness of polysilicon microdevices: A first report, J. Mater. Res. **12** (1997) 915–922

25.32 H. Kahn, R. Ballarini, R. L. Mullen, A. H. Heuer: Electrostatically actuated failure of microfabricated polysilicon fracture mechanics specimens, Proc. R. Soc. London A **455** (1999) 3807–3823

25.33 A. M. Fitzgerald, R. H. Dauskardt, T. W. Kenny: Fracture toughness and crack growth phenomena of plasma-etched single crystal silicon, Sens. Actuators A **83** (2000) 194–199

25.34 T. Tsuchiya, A. Inoue, J. Sakata: Tensile testing of insulating thin films: Humidity effect on tensile strength of SiO_2 films, Sens. Actuators A **82** (2000) 286–290

25.35 J. A. Connally, S. B. Brown: Micromechanical fatigue testing, Exp. Mech. **33** (1993) 81–90

25.36 K. Komai, K. Minoshima, S. Inoue: Fracture and fatigue behavior of single-crystal silicon microelements and nanoscopic AFM damage evaluation, Microsyst. Technol. **5** (1998) 30–37

25.37 T. Namazu, Y. Isono, T. Tanaka: Evaluation of size effect on mechanical properties of single-

© Springer 2004

crystal silicon by nanoscale bending test using AFM, J. Microelectromech. Syst. **9** (2000) 450–459
25.38 S. Sundararajan, B. Bhushan: Development of AFM-based techniques to measure mechanical properties of nanoscale structures, Sens. Actuators A **101** (2002) 338–351
25.39 X. Li, B. Bhushan: Fatigue studies of nanoscale structures for MEMS/NEMS applications using nanoindentation techniques, Surf. Coat. Technol. **163-164** (2003) 521–526
25.40 X. Li, B. Bhushan, K. Takashima, C.W. Baek, Y.K. Kim: Mechanical characterization of micro/nanoscale structures for MEMS/NEMS applications using nanoindentation techniques, Ultramicroscopy **97** (2003) 481–494
25.41 T. Hsu, N. Sun: Residual stresses/strains analysis of MEMS, Proc. of the Int. Conf. on Modeling and Simulation of Microsystems, Semiconductors, Sensors and Actuators, ed. by M. Laudon, B. Romanowicz (Computational Publications, Cambridge 1998) 82–87
25.42 A. Kolpekwar, C. Kellen, R.D. (Shawn) Blanton: Fault model generation for MEMS, Proc. of the Int. Conf. on Modeling and Simulation of Microsystems, Semiconductors, Sensors and Actuators, ed. by M. Laudon, B. Romanowicz (Computational Publications, Cambridge 1998) 111–116
25.43 H.A. Rueda, M.E. Law: Modeling of strain in boron-doped silicon cantilevers, Proc. of the Int. Conf. on Modeling and Simulation of Microsystems, Semiconductors, Sensors and Actuators, ed. by M. Laudon, B. Romanowicz (Computational Publications, Cambridge 1998) 94–99
25.44 M. Heinzelmann, M. Petzold: FEM analysis of microbeam bending experiments using ultramicro indentation, Comput. Mater. Sci. **3** (1994) 169–176
25.45 C.J. Wilson, P.A. Beck: Fracture testing of bulk silicon microcantilever beams subjected to a side load, J. Microelectromech. Syst. **5** (1996) 142–150
25.46 B. Bhushan, G.B. Agrawal: Stress analysis of nanostructures using a finite element method, Nanotechnology **13** (2002) 515–523
25.47 B. Bhushan, G.B. Agrawal: Finite element analysis of nanostructures with roughness and scratches, Ultramicroscopy **97** (2003) 495–501
25.48 K.E. Petersen: Silicon as a mechanical material, Proc. IEEE **70** (1982) 420–457
25.49 B. Bhushan, S. Sundararajan, X. Li, C.A. Zorman, M. Mehregany: Micro/nanotribological studies of single-crystal silicon and polysilicon and SiC films for use in MEMS devices. In: *Tribology Issues and Opportunities in MEMS*, ed. by B. Bhushan (Kluwer, Dordrecht 1998) pp. 407–430
25.50 S. Sundararajan, B. Bhushan: Micro/nanotribological studies of polysilicon and SiC films for MEMS applications, Wear **217** (1998) 251–261
25.51 X. Li, B. Bhushan: Micro/nanomechanical characterization of ceramic films for microdevices, Thin Solid Films **340** (1999) 210–217
25.52 B. Bhushan, X. Li: Nanomechanical characterization of solid surfaces and thin films, Int. Mater. Rev. **48** (2003) 125–164
25.53 B.R. Lawn, A.G. Evans, D.B. Marshall: Elastic/plastic indentation damage in ceramics: The median/radial system, J. Am. Ceram. Soc. **63** (1980) 574
25.54 S. Sundararajan, B. Bhushan, T. Namazu, Y. Isono: Mechanical property measurements of nanoscale structures using an atomic force microscope, Ultramicroscopy **91** (2002) 111–118
25.55 R.J. Roark: *Formulas for Stress and Strain*, 6th edn. (McGraw-Hill, New York 1989)
25.56 R.W. Hertzberg: *Deformation and Fracture Mechanics of Engineering Materials*, 3rd edn. (Wiley, New York 1989) pp. 277–278
25.57 Anonymous: Properties of silicon, EMIS Datareviews Series No. 4 (1988)
25.58 C.T.C. Nguyen, R.T. Howe: An integrated CMOS micromechanical resonator high-Q oscillator, IEEE J. Solid State Circ. **34** (1999) 440–455
25.59 L.J. Hornbeck: A digital light processing^{TM} update – status and future applications, Proc. SPIE **3634** (1999) 158–170
25.60 M. Tanaka: Fracture toughness and crack morphology in indentation fracture of brittle materials, J. Mater. Sci. **31** (1996) 749
25.61 T. Tsuchiya, O. Tabata, J. Sakata, Y. Taga: Specimen size effect on tensile strength of surface-micromachined polycrystalline silicon thin films, J. Microelectromech. Syst. **7** (1998) 106–113
25.62 T. Yi, L. Li, C.J. Kim: Microscale material testing of single crystalline silicon: Process effects on surface morphology and tensile strength, Sens. Actuators A **83** (2000) 172–178
25.63 B. Bhushan, S. Venkatesan: Mechanical and tribological properties of silicon for micromechanical applications: A review, Adv. Info. Storage Syst. **5** (1993) 211–239
25.64 B. Bhushan, B.K. Gupta: *Handbook of Tribology: Materials, Coatings, and Surface Treatments* (McGraw-Hill, New York 1991)
25.65 S.P. Timoshenko, J.N. Goodier: *Theory of Elasticity*, 3rd edn. (McGraw-Hill, New York 1970)
25.66 J.E. Shigley, L.D. Mitchell: *Mechanical Engineering Design*, 4th edn. (McGraw-Hill, New York 1993)

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Part D

Molecular

Part D Molecularly Thick Films for Lubrication

26 **Nanotribology of Ultrathin and Hard Amorphous Carbon Films**
Bharat Bhushan, Columbus, USA

27 **Self-Assembled Monolayers for Controlling Adhesion, Friction and Wear**
Bharat Bhushan, Columbus, USA
Huiwen Liu, Columbus, USA

28 **Nanoscale Boundary Lubrication Studies**
Bharat Bhushan, Columbus, USA
Huiwen Liu, Columbus, USA

29 **Kinetics and Energetics in Nanolubrication**
Rene M. Overney, Seattle, USA
George W. Tyndall, San Jose, USA
Jane Frommer, San Jose, USA

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

26. Nanotribology of Ultrathin and Hard Amorphous Carbon Films

Diamond material and its smooth coatings are used for very low wear and relatively low friction. Major limitations of the true diamond coatings are that they need to be deposited at high temperatures, can only be deposited on selected substrates, and require surface finishing. Hard amorphous carbon, commonly known as diamond-like carbon or DLC coatings, exhibit mechanical, thermal, and optical properties close to that of diamond. These can be deposited with a large range of thicknesses by using a variety of deposition processes on a variety of substrates at or near room temperature. The coatings reproduce substrate topography, avoiding the need of post-finishing. Friction and wear properties of some DLC coatings can be very attractive for tribological applications. The largest industrial application of these coatings is in magnetic storage devices.

The prevailing atomic arrangement in the DLC coatings is amorphous or quasi-amorphous with small diamond, graphite, and other unidentifiable micro- or nanocrystallites. Most DLC coatings, except those produced by filtered cathodic arc, contain from a few to about 50 at% hydrogen. Sometimes hydrogen is deliberately incorporated in the sputtered and ion plated coatings to tailor their properties.

EELS and Raman spectroscopies can be successfully used for chemical characterization of amorphous carbon coatings. The prevailing atomic arrangement in the DLC coatings is amorphous or quasi-amorphous with small diamond (sp^3), graphite (sp^2) and other unidentifiable micro- or nanocrystallites. Most DLC coatings except those produced by filtered cathodic arc contain from a few to about 50 at% hydrogen. Sometimes hydrogen is deliberately incorporated in the sputtered and ion plated coatings to tailor their properties.

Amorphous carbon coatings deposited by various techniques exhibit different mechanical and tribological properties. The nanoindenter can be successfully used for measurement of hardness, elastic modulus, fracture toughness, and fatigue life. Microscratch and microwear experiments can be performed using either a nanoindenter or an AFM. Thin coatings deposited by filtered cathodic arc, ion beam, and ECR-CVD hold a promise for tribological applications. Coatings as thin as 5 nm or even thinner provide wear protection. Microscratch, microwear, and accelerated wear testing, if simulated properly, can be successfully used to screen coating candidates for industrial applications. In the examples shown in this chapter, trends observed in the microscratch, microwear, and accelerated macrofriction wear tests are similar to that found in functional tests.

In this chapter, the state-of-the-art of recent developments in the chemical, mechanical, and tribological characterization of ultrathin amorphous carbon coatings is presented.

26.1 Description of Commonly Used Deposition Techniques ... 795
26.1.1 Filtered Cathodic Arc Deposition Technique ... 798
26.1.2 Ion Beam Deposition Technique ... 798
26.1.3 Electron Cyclotron Resonance Chemical Vapor Deposition Technique ... 799
26.1.4 Sputtering Deposition Technique ... 799
26.1.5 Plasma-Enhanced Chemical Vapor Deposition Technique ... 799

26.2 Chemical Characterization and Effect of Deposition Conditions on Chemical Characteristics and Physical Properties ... 800
26.2.1 EELS and Raman Spectroscopy ... 800
26.2.2 Hydrogen Concentrations ... 804
26.2.3 Physical Properties ... 804
26.2.4 Summary ... 805

26.3 Micromechanical and Tribological Characterizations of Coatings Deposited by Various Techniques ... 805
26.3.1 Micromechanical Characterization ... 805
26.3.2 Microscratch and Microwear Studies ... 813
26.3.3 Macroscale Tribological Characterization ... 822
26.3.4 Coating Continuity Analysis ... 826

References ... 827

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Carbon exists in both crystalline and amorphous forms and exhibits both metallic and nonmetallic characteristics [26.1–3]. Crystalline carbon includes graphite, diamond, and a family of fullerenes, Fig. 26.1. The graphite and diamond are infinite periodic network solids with a planar structure, whereas the fullerenes are a molecular form of pure carbon with a finite network with a nonplanar structure. Graphite has a hexagonal, layered structure with weak interlayer bonding forces and exhibits excellent lubrication properties. The graphite crystal may be visualized as infinite parallel layers of hexagons stacked 0.34 nm apart with a 0.1415-nm interatomic distance between the carbon atoms in the basal plane. The atoms lying in the basal planes are trigonally coordinated and closely packed with strong σ (covalent) bonds to its three carbon neighbors using the hybrid sp^2 orbitals. The fourth electron lies in a p_z orbital lying normal to the σ bonding plane and forms a weak π bond by overlapping side to side with a p_z orbital of an adjacent atom to which carbon is attached by a σ bond. The layers (basal planes) themselves are relatively far apart and the forces that bond them are weak van der Waals forces. These layers can align themselves parallel to the direction of the relative motion and slide over one another with relative ease, thus providing low friction. Strong interatomic bonding and packing in each layer is thought to help reduce wear. The operating environment has a significant influence on lubrication, i. e., low friction and low wear, properties of graphite. It lubricates better in a humid environment than a dry one, resulting from adsorption of water vapor and other gases from the environment, which further weakens the interlayer bonding forces and results in easy shear and transfer of the crystallite platelets to the mating surface. Thus, transfer plays an important role in controlling friction and wear. Graphite oxidizes at high operating temperatures and can be used up to about 430 °C.



Fig. 26.1a–c The structure of three known forms of crystalline carbon **(a)** hexagonal structure of graphite, **(b)** modified face-centered cubic (fcc) structure, two interpenetrating fcc lattices displaced by one-quarter of the cube diagonal, of diamond (each atom is bonded to four others that form the corners of the pyramidal structure called tetrahedron), and **(c)** the structure of the two most common forms of fullerenes-soccer ball C_{60} and rugby ball C_{70} molecules

One of the fullerene molecules is C_{60}, commonly known as Buckyball. Since the C_{60} molecules are very stable and do not require additional atoms to satisfy chemical bonding requirements, they are expected to have low adhesion to the mating surface and low surface energy. Since C_{60} molecules with a perfect spherical symmetry are weakly bonded to other molecules, C_{60} clusters get detached readily, similar to other layered lattice structures, and either get transferred to the mating surface by mechanical compaction, or are present as loose wear particles that may roll like tiny ball bearings in a sliding contact, resulting in low friction and wear. The wear particles are expected to be harder than as-deposited C_{60} molecules, because of their phase transformation at high asperity contact pressures present in a sliding interface. The low surface energy, spherical shape of C_{60} molecules, weak intermolecular bonding, and high load bearing capacity offer potential for various mechanical and tribological applications. The sublimed C_{60} coatings and fullerene particles as an additive to mineral oils and greases have been reported to be good solid lubricants comparable to graphite and MoS_2 [26.4–6].

Diamond crystallizes in the modified face centered cubic (*fcc*) structure with an interactomic distance of 0.154 nm. The diamond cubic lattice consists of two interpenetrating fcc lattices displaced by one-quarter of the cube diagonal. Each carbon atom is tetrahedrally coordinated, making strong σ (covalent) bonds to its four carbon neighbors using the hybrid sp^3 atomic orbitals, which accounts for its highest hardness (80–104 GPa) and thermal conductivity (900–2,100 W/mK, on the order of five times that of copper) of any known solid, and a high electrical resistivity, optical transmission, and a large optical band gap. It is relatively chemically inert, and it exhibits poor adhesion with other solids with consequent low friction and wear. Its high thermal conductivity allows dissipation of frictional heat during sliding and protects the interface, and the dangling carbon bonds on the surface react with the environment to form hydrocarbons that act as good lubrication films. These are some of the reasons for low friction and wear of the diamond. Diamond and its coatings find many industrial applications: tribological applications (low friction and wear), optical applications (exceptional optical transmission, high abrasion resistance), and thermal management or heat sink applications (high thermal conductivity). The diamond can be used to high temperatures, and it starts to graphitize at about 1,000 °C in ambient air and at about 1,400 °C in vacuum. Diamond is an attractive material for cutting tools, as an abrasive for grinding wheels and lapping compounds, and other extreme wear applications.

The natural diamond, particularly in large sizes, is very expensive and its coatings, a low cost alternative, are attractive. The true diamond coatings are deposited by chemical vapor deposition (CVD) processes at high substrate temperatures (on the order of 800 °C). They adhere best on a silicon substrate and require an interlayer for other substrates. A major roadblock to the widespread use of true diamond films in tribological, optical, and thermal management applications is the surface roughness. Growth of the diamond phase on a non-diamond substrate is initiated by nucleation either at randomly seeded sites or at thermally favored sites, due to statistical thermal fluctuation at the substrate surface. Based on growth temperature and pressure conditions, favored crystal orientations dominate the competitive growth process. As a result, the grown films are polycrystalline in nature with relatively large grain size (> 1 µm) and terminate in very rough surfaces with RMS roughnesses ranging from a few tenths of a micron to tens of microns. Techniques for polishing these films have been developed. It has been reported that the laser polished films exhibit friction and wear properties almost comparable to that of bulk polished diamond [26.7, 8].

Amorphous carbon has no long-range order, and the short-range order of carbon atoms can have one or more of three bonding configurations: – sp^3 (diamond), sp^2 (graphite), or sp^1 (with two electrons forming strong


Magnetic rigid-disk drive
Thin-film disk
Liquid lubricant (1–2 nm)
Diamond-like carbon overcoat (3–5 nm)
Magnetic coating (25–50 nm)
Al-Mg/10 µm Ni-P, glass or glass-ceramic (0.78–1.3 nm)
ME tape
Liquid lubricant (1–2 nm)
Dual magnetic layers (0.1 µm each)
Liquid lubricant (8–10 nm)
DLC (8–10 nm)
Polymer film with particulates (10–25 nm)
PET base film (6 µm)
Polymer film with particulates (20–50 nm)
Back coat (0.5 µm)
MR type picoslider
Diamond-like carbon overcoat (3.5 nm thick)
Al_2O_3–TiC

Fig. 26.2 Schematic of a magnetic rigid-disk drive and MR type picoslider and cross-sectional schematics of a magnetic thin-film rigid disk and a metal evaporated (ME) tape


a)
Supporting springs
Suspended mass
Stationary plates
Suspended mass
Stationary plates
b)
Slider
Fixed
Spring
Suspended
Silicon substrate
Suspension
Electrostatic actuator (nickel)
c)
Mirror –10 deg
Mirror +10 deg
Hinge
Yoke
Landing site
Spring tip
CMOS substrate
Hinge
Yoke
Landing site
Tip

Fig. 26.3a–c Schematics of **(a)** a capacitive-type silicon accelerometer for automotive sensory applications, **(b)** digital micrometer devices for high-projection displays, and **(c)** polysilicon rotary microactuator for magnetic disk drives

σ bonds, and the remaining two electrons left in orthogonal p_y and p_z orbitals to form weak π bonds). Short-range order controls the properties of amorphous materials and coatings. Hard amorphous carbon (a-C) coatings, commonly known as diamond-like carbon or DLC (implying high hardness) coatings, are a class of coatings that are mostly metastable amorphous materials, but include a micro- or nanocrystalline phase. The coatings are random networks of covalently bonded carbon in hybridized tetragonal (sp^3) and trigonal (sp^2) local coordination with some of the bonds terminated by hydrogen. These coatings have been successfully deposited by a variety of vacuum deposition techniques on a variety of substrates at or near room temperature. These coatings generally reproduce substrate topography and do not require any post-finishing. However, these coatings mostly adhere best on silicon substrates. The best adhesion is obtained on substrates that form carbides, e.g., Si, Fe, and Ti. Based on depth profile analyses using Auger and XPS of DLC coatings deposited on silicon substrates, it has been reported that a substantial amount of silicon carbide (on the order of 5–10 nm in thickness) is present at the carbon-silicon interface for the coatings with good adhesion and high hardness (e.g., [26.9]). For good adhesion of DLC coatings to other substrates, in most cases, an interlayer of silicon is required except for cathodic arc deposited coatings.

There is significant interest in DLC coatings because of their unique combination of desirable properties. These properties include high hardness and wear resistance, chemical inertness to both acids and alkalis, lack of magnetic response, and an optical band gap ranging from zero to a few eV, depending upon the deposition conditions. These are used in a wide range of applications, including tribological, optical, electronic, and biomedical applications [26.1, 10, 11]. The high hardness, good friction and wear properties, versatility in deposition and substrates, and no requirements of post-finishing make them very attractive for tribological applications. Two primary examples include overcoats for magnetic media (thin-film disks and ME tapes) and MR type magnetic heads for magnetic storage devices, Fig. 26.2 [26.12–20] and the emerging field of microelectromechanical systems, Fig. 26.3 [26.21–24]. The largest industrial application of the family of amorphous carbon coatings, typically deposited by DC/RF magnetron sputtering, plasma-enhanced chemical vapor deposition, or ion beam deposition techniques, is in magnetic storage devices. These are employed to protect against wear and corrosion, magnetic coatings on thin-film rigid disks and metal evaporated tapes, and the thin-film head structure of a read/write disk head (Fig. 26.2). To maintain low physical spacing between the magnetic element of a read/write head and the magnetic layer of a media, thicknesses ranging from 3 to 10 nm are employed. Mechanical properties affect friction wear and therefore need to be optimized. In 1998, Gillette introduced Mach 3 razor blades with ultrathin DLC coatings, which has the potential of becoming a very large industrial application. DLC coatings are also used in other commercial applications such as glass windows of supermarket laser barcode scanners and sunglasses. These coatings are actively pursued in microelectromechanical systems (MEMS) components [26.23].

In this chapter, a state-of-the-art review of recent developments in the chemical, mechanical, and tribological characterization of ultrathin amorphous carbon coatings is presented. An overview of the most commonly used deposition techniques is presented, and followed by typical chemical and mechanical characterization data and typical tribological data both from coupon level testing and functional testing.

26.1 Description of Commonly Used Deposition Techniques

The first hard amorphous carbon coatings were deposited by a beam of carbon ions produced in an argon plasma on room-temperature substrates, as reported by *Aisenberg* and *Chabot* [26.25]. Subsequent confirmation by *Spencer* et al. [26.26] led to the explosive growth of this field. Following the first work, several alternative techniques have been developed. The amorphous carbon coatings have been prepared by a variety of deposition techniques and precursors, including evaporation, DC, RF or ion beam sputtering, RF or DC plasma-enhanced chemical vapor deposition (PECVD), electron cyclotron resonance chemical vapor deposition (ECR-CVD), direct ion beam deposition, pulsed laser vaporization and vacuum arc, from a variety of carbon-bearing solids or gaseous source materials [26.1, 27]. Coatings with both graphitic and diamond-like properties have been produced. Evaporation and ion plating techniques have been used to produce coatings with graphitic properties (low hardness, high electrical conductivity, very low friction, etc.), and all techniques have been used to produce coatings with diamond-like properties.

The structure and properties of a coating are dependent upon the deposition technique and parameters. High-energy surface bombardment has been used to produce harder and denser coatings. It is reported that sp^3/sp^2 fractions are in the decreasing order for cathodic arc deposition, pulsed laser vaporization, direct ion beam deposition, plasma-enhanced chemical vapor deposition, ion beam sputtering, and DC/RF sputtering [26.12,28,29]. A common feature to these techniques is that the deposition is energetic, i. e., carbon species arrive with an energy significantly greater than that represented by the substrate temperature. The resultant coatings are amorphous in structure, with hydrogen content up to 50%, and display a high degree of sp^3 character. From the results of previous investigations, it has been proposed that deposition of sp^3-bonded carbon requires that the depositing species have kinetic energies on the order of 100 eV or higher, well above

Table 26.1 Summary of the most commonly used deposition techniques and the kinetic energy of depositing species and deposition rates

Deposition technique	Process	Kinetic energy (eV)	Deposition rate (nm/s)
Filtered cathodic arc (FCA)	Energetic carbon ions produced by a vacuum arc discharge between a graphite cathode and grounded anode	100–2,500	0.1–1
Direct ion beam (IB)	Carbon ions produced from methane gas in an ion source and accelerated toward a substrate	50–500	0.1–1
Plasma-enhanced chemical vapor deposition (PECVD)	Hydrocarbon species, produced by plasma decomposition of hydrocarbon gases (e.g., acetylene), are accelerated toward a DC-biased substrate	1–30	1–10
Electron cyclotron resonance plasma chemical vapor deposition (ECR-CVD)	Hydrocarbon ions, produced by plasma decomposition of ethylene gas in the presence of a plasma in electron cyclotron resonance condition, are accelerated toward a RF-biased substrate	1–50	1–10
DC/RF sputtering	Sputtering of graphite target by argon ion plasma	1–10	1–10

those obtained in thermal processes like evaporation (0–0.1 eV). The species must then be quenched into the metastable configuration via rapid energy removal. Excess energy, such as that provided by substrate heating, is detrimental to the achievement of a high sp^3 fraction. In general, a high fraction of the sp^3-bonded carbon atoms in an amorphous network results in a higher hardness [26.29–36]. The mechanical and tribological properties of a carbon coating depend on the sp^3/sp^2-bonded carbon ratio, the amount of hydrogen in the coating, and adhesion of the coating to the substrate, which are influenced by the precursor material, kinetic energy of the carbon species prior to deposition, deposition rate, substrate temperature, substrate biasing, and the substrate itself [26.29, 33, 35, 37–46]. The kinetic energies and deposition rates involved in selected deposition processes used in the deposition of DLC coatings are compared in Table 26.1 [26.1, 28].

In the studies by *Gupta* and *Bhushan* [26.12, 47], *Li* and *Bhushan* [26.48, 49], and *Sundararajan* and *Bhushan* [26.50], DLC coatings ranging typically in thickness from 3.5 nm to 20 nm were deposited on single-crystal silicon, magnetic Ni-Zn ferrite, and Al_2O_3-TiC substrates (surface roughness ≈ 1–3 nm RMS) by filtered cathodic arc (FCA) deposition, (direct) ion beam deposition (IBD), electron cyclotron resonance chemical vapor deposition (ECR-CVD), plasma-enhanced chemical vapor deposition (PECVD), and DC/RF planar, magnetron sputtering (SP) deposition techniques [26.51]. In this chapter, we will limit the presentation of data of coatings deposited by FCA, IBD, ECR-CVD, and SP deposition techniques.


a)
Gated high power pulse generator
Substrate holder
Substrate
Pulse generator
Filtered plasma
Anode
+
−
Arc power supply
Macroparticle filter with magnetic oil
Plasma source
Cathode
b)
Magnet
Precursor gas (Ar+CH$_4$)
Ion source
Anode
Ring magnet
Cathode
Ring magnet
Screen grid
Accel. grid
Neutralizer (electron emitting filament)
Substrate
Water- or LN$_2$- cooled sample holder
Ion beam envelope
c)
Negative self-bias voltage monitor
Baratron vacuum gauge
Gas inlet
Matching unit
Reaction chamber
Magnet coils
Gas inlet
Substrate
Microwave 2.45 GHz
Plasma chamber
RF generator 13.56 MHz
To pump
d)
Magnet
Cooled cathode (target)
Cathode dark space
(−)
DC power supply
Ar+H$_2$ plasma
Anode
Anode sheath
Substrate
e)
RF power supply
Insulated feedthrough
Electrode
Substrate
Electrode
Precursor gas (C$_2$H$_2$+H$_2$)

Fig. 26.4a–e Schematic diagrams of deposition by **(a)** filtered cathodic arc deposition, **(b)** ion beam deposition, **(c)** electron cyclotron resonance chemical vapor deposition (ECR-CVD), **(d)** DC planar magnetron sputtering, and **(e)** plasma-enhanced chemical vapor deposition (PECVD)

26.1.1 Filtered Cathodic Arc Deposition Technique

In the filtered cathodic arc deposition of carbon coating [26.29, 52–59], a vacuum arc plasma source is used to form carbon film. In the FCA technique used by *Bhushan* et al. (e.g., [26.12]), energetic carbon ions are produced by a vacuum arc discharge between a planar graphite cathode and grounded anode, Fig. 26.4a. The cathode is a 6-mm-diameter high-density graphite disk mounted on a water-cooled copper block. The arc is driven at an arc current of 200 A, arc duration of 5 ms, and arc repetition rate of 1 Hz. The plasma beam is guided by a magnetic field that transports current between the electrodes to form tiny, rapidly moving spots on the cathode surface. The source is coupled to a 90° bent magnetic filter to remove the macroparticles produced concurrently with the plasma in the cathode spots. The ion current density at the substrate is in the range of 10–50 $\mathrm{mA/cm^2}$. The base pressure is less than 10^{-4} Pa. Compared with electron beam evaporation with auxiliary discharge, much higher plasma density is achieved with the aid of powerful arc discharge. In this process, the cathodic material suffers a complicated transition from the solid phase to an expanding, nonequilibrium plasma via liquid and dense, equilibrium non-ideal plasma phases [26.58]. The carbon ions in the vacuum arc plasma have a direct kinetic energy of 20–30 eV. The high voltage pulses are applied to the substrate mounted on a water-cooled sample holder, and ions are accelerated through the sheath and arrive at the substrate with an additional energy given by the potential difference between the plasma and the substrate. The substrate holder is pulse biased to a negative voltage up to −2 kV with a pulse duration of 1 μs. The negative biasing of −2 kV corresponds to 2 keV kinetic energy of the carbon ions. The use of a pulse bias instead of a DC bias has advantages of applying a much higher voltage and building a surface potential on a nonconducting film. The energy of the ions is varied during the deposition. For the first 10% of the deposition the substrates are pulsed biased to −2 keV with a pulse duty cycle of 25%, i. e., for 25% of the time the energy is 2 keV, for the remaining 75% it is 20 eV, which is the "natural" energy of carbon ions in a vacuum discharge. For the last 90% of the deposition the pulsed bias voltage is reduced to −200 eV with a pulse bias duty cycle of 25%, i. e., the energy is 200 eV for 25% and 20 eV for 75% of the deposition. The high energy at the beginning leads to a good intermixing and adhesion of the films, whereas the lower energy at the later stage leads to hard films. Under the conditions described, the deposition rate at the substrate is about 0.1 nm/s, which is slow. Compared with most gaseous plasma, the cathodic arc plasma is nearly fully ionized, and the ionized carbon atoms have high kinetic energy of carbon ions which help achieving a high fraction of sp^3-bonded carbon ions, which in turn result in a high hardness and higher interfacial adhesion. *Cuomo* et al. [26.42] have reported that based on electron energy loss spectroscopy (EELS) analysis, the sp^3-bonded carbon fraction of cathodic arc coating is 83% compared to 38% for the ion beam sputtered carbon. These coatings are reported to be *nonhydrogenated*.

This technique does not require an adhesion underlayer for non-silicon substrates. However, adhesion of the DLC coatings on the electrically insulating substrate is poor, as negative pulse biasing forms an electrical sheath that accelerates depositing ions to the substrate and enhances the adhesion of the coating to the substrate with associated ion implantation. It is difficult to build potential on an insulating substrate, and lack of biasing results in poor adhesion.

26.1.2 Ion Beam Deposition Technique

In the direct ion beam deposition of carbon coating [26.60–64], as used by *Bhushan* et al. (e.g., [26.12]), the carbon coating is deposited from an accelerated carbon ion beam. The sample is pre-cleaned by ion etching. For the case of non-silicon substrates, a 2–3-nm-thick amorphous silicon adhesion layer is deposited by ion beam sputtering using an ion beam of a mixture of methane and argon at 200 V. For the carbon deposition, the chamber is pumped to about 10^{-4} Pa, and methane gas is fed through the cylindrical ion source and is ionized by energetic electrons produced by a hot-wire filament, Fig. 26.4b. Ionized species then pass through a grid with a bias voltage of about 50 eV, where they gain a high acceleration energy and reach a hot-wire filament, emitting thermionic electrons that neutralize the incoming ions. The discharging of ions is important when insulating ceramics are used as substrates. The species are then deposited on a water-cooled substrate. Operating conditions are adjusted to give an ion beam with an acceleration energy of about 200 eV and a current density of about 1 $\mathrm{mA/cm^2}$. At this operating condition, the deposition rate is about 0.1 nm/s, which is slow. Incidentally, tough and soft coatings are deposited at a high acceleration energy of about 400 eV and at a deposition rate of about 1 nm/s. The ion beam deposited carbon coatings are reported to be hydrogenated (30–40 at% hydrogen).

26.1.3 Electron Cyclotron Resonance Chemical Vapor Deposition Technique

ECR plasma's lack of electrodes and ability to create high densities of charged and excited species at low pressures ($\leq 10^{-4}$ Torr) make it an attractive processing discharge in the coating depositions [26.65]. In the ECR-CVD deposition process of carbon coating described by *Suzuki* and *Okada* [26.66] and used by *Li* and *Bhushan* [26.48, 49] and *Sundararajan* and *Bhushan* [26.50], microwave power is generated by a magnetron operating in continuous mode at a frequency of 2.45 GHz, Fig. 26.4c. The plasma chamber functions as a microwave cavity resonator. The magnetic coils arranged around the plasma chamber generate a magnetic field of 875 G, necessary for electron cyclotron resonance condition. The substrate is placed on a stage that is connected capacitively to a 13.56 MHz RF generator. The process gas is introduced into the plasma chamber and the hydrocarbon ions generated are accelerated by a negative self-bias voltage, which is generated by applying RF power to the substrate. Both the substrate stage and plasma chamber are water-cooled. The process gas used is 100% ethylene and its flow rate is held constant at 100 sccm. The microwave power is 100–900 W. The RF power is 30–120 W. The pressure during deposition is kept close to the optimum value of 5.5×10^{-3} Torr. Before the deposition, the substrates are cleaned using Ar ions generated in the ECR plasma chamber.

26.1.4 Sputtering Deposition Technique

In DC planar magnetron sputtered carbon coating [26.13, 33, 37, 40, 67–71], the carbon coating is deposited by the sputtering of graphite target with Ar ion plasma. In the glow discharge, positive ions from the plasma strike the target with sufficient energy to dislodge the atoms by momentum transfer, which are intercepted by the substrate. First, an about 5-nm-thick amorphous silicon adhesion layer is deposited by sputtering if the deposition is to be carried out on a non-silicon surface. In the process used by *Bhushan* et al. (e.g., [26.12]), the coating is deposited by the sputtering of a graphite target with Ar ion plasma at 300 W power for a 200-mm-diameter target and pressure of about 0.5 Pa (6 mTorr), Fig. 26.4d. Plasma is generated by applying a DC potential between the substrate and a target. *Bhushan* et al. [26.35] reported that sputtered carbon coating contains about 35 at% hydrogen. Hydrogen comes from the hydrocarbon contaminants present in the deposition chamber. To produce hydrogenated carbon coating with a larger concentration of hydrogen, deposition is carried out in Ar and hydrogen plasma.

26.1.5 Plasma-Enhanced Chemical Vapor Deposition Technique

In the RF-PECVD deposition of carbon coating, as used by *Bhushan* et al. (e.g., [26.12]), carbon coating is deposited by adsorption of most free radicals of hydrocarbon to the substrate and chemical bonding to other atoms on the surface. The hydrocarbon species are produced by the RF plasma decomposition of hydrocarbon precusors such as acetylene (C_2H_2), Fig. 26.4e [26.27, 69, 72–75]. Instead of requiring thermal energy in thermal CVD, the energetic electrons in the plasma (at pressures ranging from 1 to 5×10^2 Pa, typically less than 10 Pa) can activate almost any reaction among the gases in the glow discharge at relatively low substrate temperatures ranging from 100 to 600 °C (typically less than 300 °C). To deposit the coating on non-silicon substrates, an about 4-nm-thick amorphous silicon adhesion layer, used to improve adhesion, is first deposited under similar conditions from a gas mixture of 1% silane in argon [26.76]. In the process used by Bhushan and coworkers [26.12], the plasma is sustained in a parallel-plate geometry by a capacitive discharge at 13.56 MHz, at a surface power density on the order of 100 mW/cm^2. The deposition is performed at a flow rate on the order of 6 sccm and a pressure on the order of 4 Pa (30 mTorr) on a cathode-mounted substrate maintained at a substrate temperature of 180 °C. The cathode bias is held fixed at about −120 V with an external DC power supply attached to the substrate (powered electrode). The carbon coatings deposited by PECVD usually contain hydrogen up to 50% [26.35, 77].

26.2 Chemical Characterization and Effect of Deposition Conditions on Chemical Characteristics and Physical Properties

The chemical structure and properties of amorphous carbon coatings are a function of deposition conditions. It is important to understand the relationship of the chemical structure of amorphous carbon coatings to the properties in order to define useful deposition parameters. Amorphous carbon films are metastable phases formed when carbon particles are condensed on a substrate. The prevailing atomic arrangement in the DLC coatings is amorphous or quasi-amorphous with small diamond (sp^3), graphite (sp^2), and other unidentifiable micro- or nanocrystallites. The coating is dependent upon the deposition process and its conditions contain varying amounts of sp^3/sp^2 ratio and hydrogen. The sp^3/sp^2 ratio of DLC coatings ranges typically from 50% to close to 100% with an increase in hardness with the sp^3/sp^2 ratio. Most DLC coatings, except those produced by filtered cathodic arc, contain from a few to about 50 at% hydrogen. Sometimes hydrogen and nitrogen are deliberately added to produce hydrogenated (a-C:H) and nitrogenated amorphous carbon (a-C:N) coatings, respectively. Hydrogen helps to stabilize sp^3 sites (most of the carbon atoms attached to hydrogen have a tetrahedral structure); therefore, the sp^3/sp^2 ratio for hydrogenated carbon is higher [26.30]. Optimum sp^3/sp^2 in a random covalent network composed of sp^3 and sp^2 carbon sites (N_{sp^2} and N_{sp^3}) and hydrogen is [26.30]:

$$\frac{N_{sp^3}}{N_{sp^2}} = \frac{6X_\mathrm{H} - 1}{8 - 13X_\mathrm{H}} , \qquad (26.1)$$

where X_H is the atom fraction of hydrogen. The hydrogenated carbon has a larger optical band gap, higher electrical resistivity (semiconductor), and a lower optical absorption or high optical transmission. The hydrogenated coatings have a lower density, probably because of the reduction of cross-linking due to hydrogen incorporation. However, hardness decreases with an increase of the hydrogen, even though the proportion of sp^3 sites increases (that is, as the local bonding environment becomes more diamond-like) [26.78, 79]. It is speculated that the high hydrogen content introduces frequent terminations in the otherwise strong 3-D network, and hydrogen increases the soft polymeric component of the structure more than it enhances the cross-linking sp^3 fraction.

A number of investigations have been performed to identify the microstructure of amorphous carbon films using a variety of techniques such as Raman spectroscopy, EELS, nuclear magnetic resonance, optical measurements, transmission electron microscopy, and X-ray photoelectron spectroscopy [26.33]. The structure of diamond-like amorphous carbon is amorphous or quasi-amorphous with small graphitic (sp^2) and tetrahedrally coordinated (sp^3) and other unidentifiable nanocrystallites (typically on the order of a couple nm, randomly oriented) [26.33, 80, 81]. These studies indicate that the chemical structure and physical properties of the coatings are quite variable, depending on the deposition techniques and film growth conditions. It is clear that both sp^2 and sp^3-bonded atomic sites are incorporated in diamond-like amorphous carbon coatings and that the physical and chemical properties of the coatings depend strongly on their chemical bonding and microstructure. Systematic studies have been conducted to carry out chemical characterization and investigate how the physical and chemical properties of amorphous carbon coatings vary as a function of deposition parameters (e.g., [26.33, 35, 40]). EELS and Raman spectroscopy are commonly used to characterize the chemical bonding and microstructure. Hydrogen concentration of the coatings is obtained by means of forward recoil spectrometry (FRS). A variety of physical properties of the coatings relevant to tribological performance are measured.

To present the typical data obtained for characterization of typical amorphous carbon coatings and their relationships to physical properties, we present data on several sputtered coatings, RF-PECVD amorphous carbon and microwave-PECVD (MPECVD) diamond coatings [26.33,35,40]. The sputtered coatings were DC magnetron sputtered at a chamber pressure of 10 mTorr under sputtering power densities of 0.1 and 2.1 W/cm^2 in a pure Ar plasma, labeled as W1 and W2, respectively. They were prepared at a power density of 2.1 W/cm^2 with various hydrogen fractions of 0.5, 1, 3, 5, 7 and 10% of Ar/H, the gas mixtures labeled as H1, H2, H3, H4, H5, and H6, respectively.

26.2.1 EELS and Raman Spectroscopy

EELS and Raman spectra of four sputtered (W1, W2, H1, and H3) and one PECVD carbon samples were obtained. Figure 26.5 shows the EELS spectra of these carbon coatings. EELS spectra for bulk diamond and polycrystalline graphite in an energy range up to 50 eV are also shown in Fig. 26.5. One prominent peak is seen at 35 eV in diamond, while two peaks are seen at 27 eV and 6.5 eV in graphite, which are called $(\pi+\sigma)$ and (π) peaks, respectively. These peaks are produced by the energy loss of transmitted electrons to the plasmon oscillation of the valence electrons. The $\pi+\sigma$ peak in each coating is positioned at a lower energy region than that of graphite. The π peaks in the W series and PECVD samples are also seen at a lower energy region than that of the graphite. However, the π peaks in the H-series are comparable to or higher than that of graphite (see Table 26.2). The plasmon oscillation frequency is proportional to the square root of the corresponding electron density to a first approximation. Therefore, the samples in the H-series most likely have a higher density of π electrons than the other samples.

Amorphous carbon coatings contain (mainly) a mixture of sp^2- and sp^3-bonds, even though there is some evidence for the presence of sp-bonds as well [26.82]. The PECVD coatings and the H-series coatings in this study have nearly the same mass density, as seen in Table 26.4, to be presented later, but the former have a lower concentration of hydrogen (18.1%) than the H-series (35–39%), as seen in Table 26.3, to be presented later. The relatively low energy position of π peaks of PECVD coatings, compared to those of the H-series, indicates that the PECVD coatings contain a higher fraction of sp^3-bonds than the sputtered hydrogenated carbon coatings (H-series).



Fig. 26.5 **(a)** Low energy, and **(b)** high energy EELS of DLC coatings produced by DC magnetron sputtering and RF-PECVD techniques. Data for bulk diamond and polycrystalline graphite are included for comparison [26.35]

Figure 26.5b shows the EELS spectra associated with the inner-shell (K-shell) ionization. Again, the spectra for diamond and polycrystalline graphite are included for comparison. Sharp peaks are observed at

Table 26.2 Experimental results from EELS and Raman spectroscopy [26.35]

Sample	EELS peak position		Raman peak position		Raman FWHM[a]		I_D/I_G^d
	π (eV)	$\pi+\sigma$ (eV)	G-band[b] (cm^{-1})	D-band[c] (cm^{-1})	G-band (cm^{-1})	D-band (cm^{-1})	
Sputtered *a*-C coating (W1)	5.0	24.6	1541	1368	105	254	2.0
Sputtered *a*-C coating (W2)	6.1	24.7	1560	1379	147	394	5.3
Sputtered *a*-C:H coating (H1)	6.3	23.3	1542	1334	95	187	1.6
Sputtered *a*-C:H coating (H3)	6.7	22.4	e	e	e	e	e
PECVD *a*-C:H coating	5.8	24.0	1533	1341	157	427	1.5
Diamond coating	...	...	1525[f]	1333[g]	...	8[g]	...
Graphite (for reference)	6.4	27.0	1580	1358	37	47	0.7
Diamond (for reference)	...	37.0	...	1332[g]	...	2[g]	...

[a] Full width at half maximum width

[b] Peak associated with sp^2 "graphite" carbon

[c] Peak associated with sp^2 "disordered" carbon (not sp^3-bonded carbon)

[d] Intensity ratio of the D-band to the G-band

[e] Fluorescence

[f] Includes D and G band, signal too weak to analyze

[g] Peak position and width for diamond phonon

Table 26.3 Experimental results of FRS analysis [26.35]

Sample	Ar/H ratio	C (at% ±0.5)	H (at% ±0.5)	Ar (at% ±0.5)	O (at% ±0.5)
Sputtered *a*-C coating (W2)	100/0	90.5	9.3	0.2	...
Sputtered *a*-C:H coating (H2)	99/1	63.9	35.5	0.6	...
Sputtered *a*-C:H coating (H3)	97/3	56.1	36.5	...	7.4
Sputtered *a*-C:H coating (H4)	95/5	53.4	39.4	...	7.2
Sputtered *a*-C:H coating (H5)	93/7	58.2	35.4	0.2	6.2
Sputtered *a*-C:H coating (H6)	90/10	57.3	35.5	...	7.2
PECVD *a*-C:H coating	99.5% CH_4	81.9	18.1	...	...
Diamond coating	H_2-1 mole % CH_4	94.0	6.0	...	...

Table 26.4 Experimental results of physical properties [26.35]

Sample	Mass density (g/cm^3)	Nano-hardness (GPa)	Elastic modulus (GPa)	Electrical resistivity (Ohm-cm)	Compressive residual stress (GPa)
Sputtered *a*-C coating (W1)	2.1	15	141	1300	0.55
Sputtered *a*-C:H coating (W2)	1.8	14	136	0.61	0.57
Sputtered *a*-C:H coating (H1)	...	14	96	...	> 2
Sputtered *a*-C:H coating (H3)	1.7	7	35	$> 10^6$	0.3
PECVD *a*-C:H coating	1.6–1.8	33–35	~ 200	$> 10^6$	1.5–3.0
Diamond coating	...	40–75	370–430	...	...
Graphite (for reference)	2.267	Soft	9–15	5×10^{-5a}, 4×10^{-3b}	0
Diamond (for reference)	3.515	70–102	900–1050	10^7–10^{20}	0

[a] Parallel to layer planes
[b] Perpendicular to layer planes

285.5 eV and 292.5 eV in graphite, while no peak is seen at 285.5 eV in diamond. The general features of the K-shell EELS spectra for the sputtered and PECVD carbon samples resemble those of graphite, but with the higher energy features smeared. The observation of the peak at 285.5 eV in the sputtered and PECVD coatings also indicates the presence of sp^2-bonded atomic sites in the coatings. All these spectra peak at 292.5 eV, similar to the spectra of graphite, but the peak in graphite is sharper.

Raman spectra from samples W1, W2, H1, and PECVD are shown in Fig. 26.6. Raman spectra could not be observed in specimens H2 and H3 due to high flourescence signals. The Raman spectra of single crystal diamond and polycrstalline graphite are also shown for comparison in Fig. 26.6. The results of the spectral fits are summarized in Table 26.2. We will focus on the G-band position, which has been shown to be related to the fraction of sp^3-bonded sites. Increasing the power density in the amorphous carbon coatings (W1 and W2) results in a higher G-band frequency, implying a smaller fraction of sp^3-bonding in W2 than in W1. This is consistent with higher density of W1. H1 and PEVCD have still lower G-band positions than W1, implying an even higher fraction of sp^3-bonding, which is presumably caused by the incorporation of H atoms into the lattice. The high hardness of H3 might be attributed to efficient sp^3 cross-linking of small, sp^2-ordered domains.

The Raman spectrum of a MPECVD diamond coating is shown in Fig. 26.6. The diamond Raman peak is at 1,333 cm^{-1} with a line width of 7.9 cm^{-1}. There is a small broad peak around 1,525 cm^{-1}, which is attributed to a small amount of a-C:H. This impurity peak is not intense enough to fit to separate G- and D-bands. The diamond peak frequency is very close to that of natural diamond (1,332.5 cm^{-1}, e.g. Fig. 26.6), indicating that the coating is not under stress [26.83]. The large line width compared to that of natural diamond (2 cm^{-1})



Fig. 26.6 Raman spectra of DLC coatings produced by DC magnetron sputtering and RF-PECVD techniques and a diamond film produced by MPECVD technique. Data for bulk diamond and microcrystalline graphite are included for comparison [26.35]

indicates that the microcrystallites likely have a high concentration of defects [26.84].

26.2.2 Hydrogen Concentrations

FRS analysis of six sputtered (W2, H2, H3, H4, H5, and H6) coatings, one PECVD coating, and one diamond coating was performed. Figure 26.7 shows an overlay of the spectra from the six sputtered samples. Similar spectra were obtained from the PECVD and the diamond films. Table 26.3 shows the H and C fractions, as well as the amount of impurities (Ar and O) in the films in atomic %. Most apparent is the large fraction of H in the sputtered films. Regardless of how much H_2 is in the Ar sputtering gas, the H content of the coatings is about the same, ~ 35 at%. Interestingly, there is still $\sim 10\%$ H present in the coating sputtered in pure Ar (W2). It is interesting to note that Ar is present only in coatings grown under low ($< 1\%$) H content in the Ar carrier gas. The presence of O in the coatings, combined with the fact that the coatings were prepared approximately nine months before the FRS analysis, caused suspicion that they had absorbed water vapor, and that this may be the cause for the H peak in specimen W2.

All samples were annealed for 24 h at 250 °C in a flowing He furnace and then reanalyzed. Surprisingly, the H content of all coatings measured increased slightly, even though the O content decreased, and W2 still had a substantial amount of H_2. This slight increase in H concentration is not understood. However, since H concentration did not decrease with the oxygen as a result of annealing, it suggests that high H concentration is not due to adsorbed water vapor. The PECVD film has more H ($\sim 18\%$) than the sputtered films initially, but after annealing it has the same fraction as specimen W2, the film sputtered in pure Ar. The diamond film has the smallest amounts of hydrogen, as seen in Table 26.3.



Fig. 26.7 FRS spectra of six DLC coatings produced by DC magnetron sputtering [26.35]

26.2.3 Physical Properties

Physical properties of the four sputtered (W1, W2, H1, and H3) coatings, one PECVD coating, one diamond coating, and bulk diamond and graphite are presented in Table 26.4. The hydrogenated carbon and the diamond coatings have very high resistivity compared to unhydrogenated carbon coatings. It appears that unhydrogenated carbon coatings have a higher density than the hydrogenated carbon coatings, although both groups are less dense than graphite. The density depends on the deposition technique and the deposition parameters. It appears that unhydrogenated sputtered coatings deposited at low power exhibit the highest density. Nanohardness of hydrogenated carbon is somewhat lower than that of the unhydrogenated carbon coatings. PECVD coatings are significantly harder than sputtered coatings. The nanohardness and modulus of elasticity of the diamond coatings are very high compared to that of DLC coatings, even though the hydrogen content is similar. The compressive residual stresses of the PECVD coatings are substantially higher than those of sputtered coatings, which is consistent with the hardness results.

Figure 26.8a shows the effect of hydrogen in the plasma on the residual stresses and the nanohardness for sputtered coatings W2 and H1 to H6. The coatings made with H_2 flow between 0.5 and 1.0% delaminate very quickly, even when only a few tens of nm thick. In pure Ar and at H_2 flows greater than 1%, the coatings appear to be more adhesive. The tendency of some coatings to delaminate can be caused by intrinsic stress in the coating, which is measured by substrate bending. All of the coatings in the figure are in compressive stress. The maximum stress occurs between 0 and 1% H_2 flow, but the stress cannot be quantified in this range because the coatings instantly delaminate upon exposure to air. At higher hydrogen concentrations the stress gradually diminishes. A generally decreasing trend is observed in the hardness of the coatings as hydrogen content increased. The hardness decreases slightly, going from 0% H_2 to 0.5% H_2, and then decreases sharply. These results are probably lower than the true values because of local delamination around the indentation point. This is especially likely for the 0.5% and 1.0% coatings where delamination is visually apparent, but may also be true to a lesser extent for the other coatings. Such an adjustment would bring the hardness profile into closer correlation with the stress profile. *Weissmantel* et al. [26.68] and *Scharff* et al. [26.85] observed a downturn in hardness for high bias and low pressure of hydrocarbon gas in ion plated carbon coating, and, therefore, presumably low hydrogen content in support of the above contention.

Figure 26.8b shows the effect of sputtering power (with no hydrogen added in the plasma) on the residual stresses and nanohardness for various sputtered coatings. As the power decreases, compressive stress does not seem to change while nanohardness slowly increases. The rate of change becomes more rapid at very low power levels.

The addition of H_2 during sputtering of carbon coatings increases H concentration in the coating. Hydrogen causes the character of the C-C bonds to shift from sp^2 to sp^3, and the rising number of C-H bonds, which ultimately relieves stress and produces a softer "polymer-like" material. Low power deposition, like the presence of hydrogen, appears to stabilize the formation of sp^3 C-C bonds, increasing hardness. These coatings have relieved stress and led to better adhesion. An increase in temperature during deposition at high power density results in graphitization of the coating material, responsible for a decrease in hardness with an increase in power density. Unfortunately, low power also means impractically low deposition rates.

26.2.4 Summary

Based on the EELS and Raman data, all DLC coatings have both sp^2 and sp^3 bondings. The sp^2/sp^3 bonding ratio depends on the deposition techniques and parameters. The DLC coatings deposited by sputtering and PECVD contain significant concentrations of hydrogen, while the diamond coating contains only small amounts of hydrogen impurity. Sputtered coatings with no deliberate addition of hydrogen in the plasma contain a significant amount of hydrogen. Regardless of how much hydrogen is in the Ar sputtering gas, the hydrogen content of the coatings increases initially with no further increase.

Hydrogen flow and sputtering power density affect the mechanical properties of these coatings. Maximum compressive residual stress and hardness occur between 0 and 1% hydrogen flow, resulting in rapid delamination. Low sputtering power moderately increases hardness while relieving residual stress.



Fig. 26.8a,b Residual compressive stresses and nanohardness **(a)** as a function of hydrogen flow rate; sputtering power is 100 W and target diameter is 75 mm (power density = 2.1 W/cm^2), and **(b)** as a function of sputtering power over a 75-mm-diameter target with no hydrogen added in the plasma [26.40]

26.3 Micromechanical and Tribological Characterizations of Coatings Deposited by Various Techniques

26.3.1 Micromechanical Characterization

Common mechanical characterizations include measurement of hardness and elastic modulus, fracture toughness, fatigue life, and scratch and wear testing. Nanoindentation and atomic force microscopy (AFM) are used for mechanical characterization of ultrathin films.

Hardness and elastic modulus are calculated from the load displacement data obtained by nanoindentation at loads ranging typically from 0.2 to 10 mN using a commercially available nanoindenter [26.23,86].

This instrument monitors and records the dynamic load and displacement of the three-sided pyramidal diamond (Berkovich) indenter during indentation. For the fracture toughness measurement of ultrathin films ranging from 100 nm to a few μm, a nanoindentation-based technique is used in which through-thickness cracking in the coating is detected from a discontinuity observed in the load-displacement curve and energy released during the cracking is obtained from the curve [26.87–89]. Based on the energy released, fracture mechanics analysis is then used to calculate fracture toughness. An indenter with a cube-corner tip geometry is preferred because the through-thickness cracking of hard films can be accomplished at lower loads. In fatigue measurement, a conical diamond indenter having a tip radius of about one micron is used and load cycles of a sinusoidal shape are applied [26.90, 91]. The fatigue behavior of coatings is studied by monitoring the change in contact stiffness, which is sensitive to damage formation.



Fig. 26.9 Load versus displacement plots for various 100-nm-thick amorphous carbon coatings on single-crystal silicon substrate and bare substrate

Hardness and Elastic Modulus

For materials that undergo plastic deformation, high hardness and elastic modulus are generally needed for low friction and wear, whereas for brittle materials, high fracture toughness is needed [26.2, 3, 21]. DLC coatings used for many applications are hard and brittle, and values of hardness and fracture toughness need to be optimized.

Representative load-displacement plots of indentations made at 0.2 mN peak indentation load on 100-nm-thick DLC coatings deposited by the four deposition techniques on single-crystal silicon substrate are compared in Fig. 26.9. The indentation depths at the peak load range from about 18 to 26 nm, smaller than that of the coating thickness. Many of the coatings exhibit a discontinuity or pop-in marks in the loading curve, which indicate a sudden penetration of the tip into the sample. A nonuniform penetration of the tip into a thin coating possibly results from formation of cracks in the coating, formation of cracks at the coating-substrate interface, or debonding or delamination of the coating from the substrate.

The hardness and elastic modulus values at a peak load of 0.2 mN on the various coatings and single-crystal silicon substrate are summarized in Table 26.5 and Fig. 26.10 [26.47, 49, 89, 90]. Typical values for the peak and residual indentation depths ranged from 18 to 26 nm and 6 to 12 nm, respectively. The FCA coatings exhibit the highest hardness of 24 GPa and elastic modulus of 280 GPa of various coatings, followed by the ECR-CVD, IB, and SP coatings. Hardness and elastic modulus have been known to vary over a wide range with sp^3-to-sp^2 bonding ratio, which depends on the kinetic energy of the carbon species and amount of hydrogen [26.6, 30, 47, 92, 93]. The high hardness and elastic modulus of the FCA coatings are attributed to the high kinetic energy of carbon species involved in the FCA deposition [26.12, 47]. *Anders* et al. [26.57] also reported a high hardness, measured by nanoindentation, of about 45 GPa for cathodic arc carbon coatings. They observed a change in hardness from 25 to 45 GPa with pulsed bias voltage and bias duty cycle. The high hardness of cathodic arc carbon was attributed to the high percentage (more than 50%) of sp^3 bonding. *Savvides* and *Bell* [26.94] reported an increase in hardness from 12 to 30 GPa and an elastic modulus from 62 to 213 GPa with an increase of sp^3-to-sp^2 bonding ratio, from 3 to 6, for a C:H coating deposited by low-energy ion-assisted unbalanced magnetron sputtering of a graphite target in an Ar-H_2 mixture.

Bhushan et al. [26.35] reported hardnesses of about 15 and 35 GPa and elastic moduli of about 140 and 200 GPa, measured by nanoindentation, for a-C:H coatings deposited by DC magnetron sputtering and RF-plasma-enhanced chemical vapor deposition techniques, respectively. The high hardness of RF-PECVD a-C:H coatings is attributed to a higher concentration of sp^3 bonding than in a sputtered hydrogenated a-C:H coating. Hydrogen is believed to play a crucial role in the bonding configuration of carbon atoms by helping to stabilize tetrahedra-coordination (sp^3 bonding) of carbon species. *Jansen* et al. [26.78] suggested that the incorporation of hydrogen efficiently passivates the dangling bonds and saturates the graphitic bonding to some extent. However, a large concentration of hydrogen in the plasma in sputter deposition is undesirable. *Cho* et al. [26.33] and *Rubin* et al. [26.40] observed that hardness decreased from 15 to 3 GPa with increased hydrogen content. *Bhushan* and *Doerner* [26.95] reported a hardness of about 10–20 GPa and an elastic modulus of about 170 GPa, measured by nanoindentation, for 100-nm-thick DC-magnetron sputtered a-C:H on the silicon substrate.

Residual stresses measured using a well-known curvature measurement technique are also presented in Table 26.5. The DLC coatings are under significant compressive internal stresses. Very high compressive stresses in FCA coatings are believed to be partly responsible for their high hardness. However, high stresses result in coating delamination and buckling. For this reason, the coatings that are thicker than about 1 µm have a tendency to delaminate from the substrates.

Fracture Toughness

Representative load-displacement curves of indentations on the 400-nm-thick cathodic arc carbon coating on silicon at various peak loads are shown in Fig. 26.11. Steps are found in all curves, as shown by arrows in Fig. 26.11a. In the 30 mN SEM micrograph, in addition to several radial cracks, ring-like through-thickness cracking is observed with small lips of material overhanging the edge of indentation. The step at about 23 mN in the loading curves of indentations made at 30 and 100 mN peak indentation loads results from the ring-like through-thickness cracking. The step at 175 mN in the loading curve of the indentation made at 200 mN peak indentation load is caused by spalling and second ring-like through-thickness cracking.



Fig. 26.10 Bar charts summarizing the data of various coatings and single-crystal silicon substrate. Hardness, elastic modulus, and fracture toughness were measured on 100-nm-thick coatings, and fatigue life and critical load during scratch were measured on 20-nm-thick coatings

Based on *Li* et al. [26.87], the fracture process progresses in three stages: (1) ring-like through-thickness cracks form around the indenter by high stresses in the contact area, (2) delamination and buckling occur around contact area at the coating/substrate interface by high lateral pressure, (3) second ring-like through-thickness cracks and spalling are generated by high bending stesses at the edges of the buckled coating, see Fig. 26.12a. In the first stage, if the coating under the indenter is separated from the bulk coating via the first ring-like through-thickness cracking, a corresponding step will be present in the loading curve. If discontinuous cracks form and the coating under the indenter is not separated from the remaining coating, no step appears in the loading curve, because the coating still supports the indenter and the indenter cannot suddenly advance into the material. In the second stage,



Fig. 26.11 **(a)** Load-displacement curves of indentations made at 30, 100, and 200 mN peak indentation loads using the cube corner indenter, and **(b)** the SEM micrographs of indentations on the 400-nm-thick cathodic arc carbon coating on silicon. *Arrows* indicate steps during loading portion of the load-displacement curve [26.87]

for the coating used in the present study, the advances of the indenter during the radial cracking, delamination, and buckling are not big enough to form steps in the loading curve, because the coating around the indenter still supports the indenter, but generate discontinuities that change the slope of the loading curve with increasing indentation loads. In the third stage, the stress concentration at the end of the interfacial crack cannot be relaxed by the propagation of the interfacial crack. With an increase in indentation depth, the height of the bulged coating increases. When the height reaches a critical value, the bending stresses caused by the bulged coating around the indenter will result in the second ring-like through-thickness crack formation and spalling at the edge of the buckled coating, as shown in Fig. 26.12a, which leads to a step in the loading curve. This is a single event and results in the separation of the part of the coating around the indenter from the bulk


a)
Stage 1
t
$2c_{R1}$
First ring-like through-thickness crack formation
Delamination and buckling
Stage 2
t
$2c_{DB}$
Partial spalling formation
Stage 3
t
$2c_{R2}$
Second ring-like through-thickness crack formation
Lateral cracking during unloading
b)
Load (mN)
D
B
A
C
F
E
0
Displacement (nm)

Fig. 26.12 **(a)** Schematic of various stages in nanoindentation fracture for the coatings/substrate system, and **(b)** schematic of a load-displacement curve showing a step during the loading cycle and associated energy release

Table 26.5 Hardness, elastic modulus, fracture toughness, fatigue life, critical load during scratch, coefficient of friction during accelerated wear testing and residual stresses of various DLC coatings on single-crystal silicon substrate

Coating	Hardness[a] [26.48] (GPa)	Elastic modulus[a] [26.48] (GPa)	Fracture toughness[a] [26.89] (MPa $m^{1/2}$)	Fatigue life[b], N_f[d] [26.90] $\times 10^4$	Critical load during scratch[b] [26.48] (mN)	Coefficient of friction during accelerated wear testing[b] [26.48]	Compressive residual stress[c] [26.47] (GPa)
Cathodic arc carbon coating (a-C)	24	280	11.8	2.0	3.8	0.18	12.5
Ion beam carbon coating (a-C:H)	19	140	4.3	0.8	2.3	0.18	1.5
ECR-CVD carbon coating (a-C:H)	22	180	6.4	1.2	5.3	0.22	0.6
DC sputtered carbon coating (a-C:H)	15	140	2.8	0.2	1.1	0.32	2.0
Bulk graphite (for comparison)	Very soft	9–15	–	–	–	–	–
Diamond (for comparison)	80–104	900–1050	–	–	–	–	–
Si(100) substrate	11	220	0.75	–	0.6	0.55	0.02

[a] Measured on 100-nm-thick coatings

[b] Measured on 20-nm-thick coatings

[c] Measured on 400-nm-thick coatings

[d] N_f was obtained at a mean load of 10 μN and a load amplitude of 8 μN

coating via cracking through coatings. The step in the loading curve results totally from the coating cracking and not from the interfacial cracking or the substrate cracking.

The area under the load-displacement curve is the work performed by the indenter during elastic-plastic deformation of the coating/substrate system. The strain energy release in the first/second ring-like cracking and spalling can be calculated from the corresponding steps in the loading curve. Fig. 26.12b shows a modeled load-displacement curve. OACD is the loading curve and DE is the unloading curve. The first ring-like through-thickness crack should be considered. It should be emphasized that the edge of the buckled coating is far from the indenter and, therefore, it does not matter if the indentation depth exceeds the coating thickness, or if deformation of the substrate occurs around the indenter when we measure fracture toughness of the coating from the released energy during the second ring-like through-thickness cracking (spalling). Suppose that the second ring-like through-thickness cracking occurs at AC. Now, let us consider the loading curve OAC. If the second ring-like through-thickness crack does not occur, it can be understood that OA will be extended to OB to reach the same displacement as OC. This means that the crack formation changes the loading curve OAB into OAC. For point B, the elastic-plastic energy stored in the coating/substrate system should be OBF. For point C, the elastic-plastic energy stored in the coating/substrate system should be OACF. Therefore, the energy difference before and after the crack generation is the area of ABC, i. e., this energy stored in ABC will be released as strain energy to create the ring-like through-thickness crack. According to the theoretical analysis by *Li* et al. [26.87], the fracture toughness of thin films can be written as

$$K_{\mathrm{Ic}} = \left[\left(\frac{E}{(1-\nu^2)\, 2\pi C_{\mathrm{R}}} \right) \left(\frac{U}{t} \right) \right]^{1/2} , \qquad (26.2)$$

where E is the elastic modulus, ν is the Poisson's ratio, $2\pi C_{\mathrm{R}}$ is the crack length in the coating plane, t is the coating thickness, and U is the strain energy difference before and after cracking.

Using (26.2), the fracture toughness of the coatings is calculated. The loading curve is extrapolated along the tangential direction of the loading curve from the starting point of the step up to reach the same displacement as the step. The area between the extrapolated line and the step is the estimated strain energy difference before and after cracking. C_{R} is measured from SEM micrographs or AFM images of indentations. The second ring-like crack is where the spalling occurs. For example, for the 400-nm-thick cathodic arc carbon coating data presented in Fig. 26.11, U of 7.1 nNm is assessed from the steps in Fig. 26.11a at the peak indentation loads of 200 mN. For C_{R} of 7.0 µm from Fig. 26.11b, $E = 300$ GPa measured using a nanoindenter and an assumed value of 0.25 for ν, fracture toughness values are calculated as 10.9 MPa$\sqrt{m}$ [26.87, 88]. The fracture toughness and related data for various 100-nm-thick DLC coatings are presented in Fig. 26.10 and Table 26.5.

Nanofatigue

Delayed fracture resulting from extended service is called fatigue [26.96]. Fatigue fracturing progresses through a material via changes within the material at the tip of a crack, where there is a high stress intensity. There are several situations: cyclic fatigue, stress corrosion, and static fatigue. Cyclic fatigue results from cyclic loading of machine components. In a low-flying slider in a magnetic head-disk interface, isolated asperity contacts occur during use and the fatigue failure occurs in the multilayered thin-film structure of the magnetic disk [26.13]. In many MEMS components, impact occurs and the failure mode is cyclic fatigue. Asperity contacts can be simulated using a sharp diamond tip in an oscillating contact with the component.



Fig. 26.13 Schematic of a fatigue test on a coating/substrate system using the continuous stiffness measurement technique

Figure 26.13 shows the schematic of a fatigue test on a coating/substrate system using a continuous stiffness measurement (CSM) technique. Load cycles are applied to the coating, resulting in a cyclic stress. P is the cyclic load, P_{mean} is the mean load, P_{o} is the oscillation load amplitude, and ω is the oscillation frequency. The following results can be obtained: (1) endurance limit, i. e., the maximum load below which there is no coating failure for a preset number of cycles; (2) number of cycles at which the coating failure occurs; and (3) changes in contact stiffness measured by using the unloading slope of each cycle, which can be used to monitor the propagation of the interfacial cracks during cyclic fatigue process.

Figure 26.14a shows the contact stiffness as a function of the number of cycles for 20-nm-thick FCA coatings cyclically deformed by various oscillation load amplitudes with a mean load of 10 µN at a frequency of 45 Hz. At 4 µN load amplitude, no change in contact stiffness was found for all coatings. This indicates that 4 µN load amplitude is not high enough to damage the coatings. At 6 µN load amplitude, an abrupt decrease in contact stiffness was found at a certain number of cycles for each coating, indicating that fatigue damage had occurred. With increasing load amplitude, the number of cycles to failure, $\mathrm{N_f}$, decreases for all coatings. Load amplitude versus $\mathrm{N_f}$, a so-called S-N curve, is plotted in Fig. 26.14b. The critical load amplitude, below which no fatigue damage occurs (an endurance limit), was identified for each coating. This critical load amplitude, together with mean load, are of critical importance to the design of head-disk interfaces or MEMS/NEMS device interfaces.

To compare the fatigue lives of different coatings studied, the contact stiffness as a function of the number of cycles for 20-nm-thick FCA, IB, ECR-CVD and SP coatings cyclically deformed by an oscillation load amplitude of 8 µN with a mean load of 10 µN at a frequency of 45 Hz is shown in Fig. 26.14c. FCA coating has the longest $\mathrm{N_f}$, followed by ECR-CVD, IB, and SP coatings. In addition, after the $\mathrm{N_f}$, the contact stiffness of the FCA coating shows a slower decrease than the other coatings. This indicates that after the $\mathrm{N_f}$, the FCA coating had less damage than the others. The fatigue behavior of FCA and ECR-CVD coatings of differ-



Fig. 26.14 **(a)** Contact stiffness as a function of the number of cycles for 20-nm-thick FCA coatings cyclically deformed by various oscillation load amplitudes with a mean load of 10 μN at a frequency of 45 Hz; **(b)** plot of load amplitude versus N_f; **(c)** contact stiffness as a function of the number of cycles for four different 20-nm-thick coatings with a mean load of 10 μN and load amplitude of 8 μN at a frequency of 45 Hz; and **(d)** contact stiffness as a function of the number of cycles for two coatings of different thicknesses at a mean load of 10 μN and load amplitude of 8 μN at a frequency of 45 Hz

ent thicknesses is compared in Fig. 26.14d. For both coatings, N_f decreases with decreasing coating thickness. At 10 nm, FCA and ECR-CVD have almost the same fatigue life. At 5 nm, ECR-CVD coating shows a slightly longer fatigue life than FCA coating. This indicates that even for nanometer-thick DLC coatings their microstructure and residual stresses are not uniform across the thickness direction. Thinner coatings are more influenced by interfacial stresses than thicker coating.

Figure 26.15a shows the high magnification SEM images of 20-nm-thick FCA coatings before, at, and after N_f. In the SEM images, the net-like structure is the gold film coated on the DLC coating, which should be ignored in analyzing the indentation fatigue damage. Before the N_f, no delamination or buckling was found except the residual indentation mark at magnifications up to 1,200,000× using SEM. This suggests that only plastic deformation occurred before the N_f. At the N_f, the coating around the indenter bulged upwards, indicating delamination and buckling. Therefore, it is believed that the decrease in contact stiffness at the N_f results from the delamination and buckling of the coating from the substrate. After the N_f, the buckled coating was broken down around the edge of the buckled area, forming a ring-like crack. The remaining coating overhung at the edge of the buckled area. It is noted that the indentation size increases with the increasing number of cycles. This indicates that deformation, delamination and buckling, and ring-like crack formation occurred over a period.



Fig. 26.15 **(a)** High magnification SEM images of a coating before, at, and after N_f, and **(b)** schematic of various stages in the indentation fatigue damage for a coating/substrate system [26.90]

The schematic in Fig. 26.15b shows various stages in the indentation fatigue damage for a coating/substrate system. Based on this study, three stages in the indentation fatigue damage appear to exist: (1) indentation-induced compression; (2) delamination and buckling; (3) ring-like crack formation at the edge of the buckled coating. The deposition process often induces residual stresses in coatings. The model shown in Fig. 26.15b considers a coating with the uniform biaxial residual compression σ_r. In the first stage, indentation induces elastic/plastic deformation, exerting an outward acting pressure on the coating around the indenter. Interfacial defects like voids and impurities act as original cracks. These cracks propagate and link up as the indentation compressive stress increases. At this stage, the coating, which is under the indenter and above the interfacial crack (with a crack length of $2a$), still maintains a solid contact with the substrate; the substrate still fully supports the coating. Therefore, this interfacial crack does not lead to an abrupt decrease in contact stiffness, but gives rise to a slight decrease in contact stiffness, as shown in Fig. 26.14. The coating above the interfacial crack is treated as a rigidly clamped disk. We assume that the crack radius, a, is large compared with the coating thickness t. Since the coating thickness ranges from 5 to 20 nm, this assumption is easily satisfied in this study (radius of the delaminated and buckled area, shown in Fig. 26.15a, is on the order of 100 nm). The compressive stress caused by indentation is given as [26.97]:

$$\sigma_i = \frac{E}{(1-\nu)}\varepsilon_i = \frac{EV_i}{2\pi t a^2(1-\nu)}\,, \tag{26.3}$$

where ν and E are the Poisson's ratio and elastic modulus of the coating, V_i is the indentation volume, t is the coating thickness, and a is the crack radius. With an increasing number of cycles, the indentation volume V_i increases. Therefore, the indentation compressive stress σ_i increases accordingly. In the second stage, buckling occurs during the unloading segment of the fatigue testing cycle when the sum of indentation compressive stress σ_i and the residual stress σ_r

exceed the critical buckling stress σ_b for the delaminated circular section as given by [26.98]

$$\sigma_b = \frac{\mu^2 E}{12\left(1-\nu^2\right)}\left(\frac{t}{a}\right)^2 , \tag{26.4}$$

where the constant μ equals 42.67 for a circular clamped plate with a constrained center point and 14.68 when the center is unconstrained. The buckled coating acts as a cantilever. In this case, the indenter indents a cantilever rather than a coating/substrate system. This ultrathin coating cantilever has much less contact stiffness than the coating/substrate system. Therefore, the contact stiffness shows an abrupt decrease at the N_f. In the third stage, with an increasing number of cycles, the delaminated and buckled size increases, resulting in a further decrease in contact stiffness since the cantilever beam length increases. On the other hand, a high bending stress acts at the edge of the buckled coating. The larger the buckled size, the higher the bending stress. The cyclically bending stress causes fatigue damage at the end of the buckled coating, forming a ring-like crack. The coating under the indenter is separated from the bulk coating (caused by the ring-like crack at the edge of the buckled coating) and the substrate (caused by the delamination and buckling in the second stage). Therefore, the coating under the indenter is not constrained, but is free to move with the indenter during fatigue testing. At this point, the sharp nature of the indenter is lost, because the coating under the indenter gets stuck on the indenter. The indentation fatigue experiment results in the contact of a relative huge blunt tip with the substrate. This results in a low contact stiffness value.

Compressive residual stresses result in delamination and buckling. A coating with a higher adhesion strength and a less compressive residual stress is required for a higher fatigue life. Interfacial defects should be avoided in the coating deposition process. We know that the ring-like crack formation occurs in the coating. Formation of fatigue cracks in the coating depends upon the hardness and fracture toughness. Cracks are more difficult to form and propagate in the coating with higher strength and fracture toughness.

It is now accepted that long fatigue life in a coating/substrate almost always involves "living with crack", that the threshold or limit condition is associated with the non-propagation of exiting cracks or defects, even though these cracks may be undetectable [26.96]. For all coatings studied, at 4 μN, contact stiffness does not change much. This indicates that delamination and buckling did not occur within the number of cycles tested in this study. This is probably because the indentation-induced compressive stress was not high enough to allow the cracks to propagate and link up under the indenter, or the sum of indentation compressive stress σ_i and the residual stress σ_r did not exceed the critical buckling stress σ_b.

Figure 26.10 and Table 26.5 summarize the hardness, elastic modulus, fracture toughness, and fatigue life of all coatings studied. A good correlation exists between fatigue life and other mechanical properties. Higher mechanical properties result in a longer fatigue life. The mechanical properties of DLC coatings are controlled by the sp^3-to-sp^2 ratio. The sp^3-bonded carbon exhibits the outstanding properties of diamond [26.51]. A higher deposition kinetic energy will result in a larger fraction of sp^3-bonded carbon in an amorphous network. Thus, the higher kinetic energy for the FCA could be responsible for its better carbon structure and higher mechanical properties [26.48–50, 99]. Higher adhesion strength between the FCA coating and substrate makes the FCA coating more difficult to delaminate from the substrate.

26.3.2 Microscratch and Microwear Studies

For microscratch studies, a conical diamond indenter (e.g., having a tip radius of about one micron and included angle of 60°) is drawn over the sample surface, and the load is ramped up (typically from 2 mN to 25 mN) until substantial damage occurs. The coefficient of friction is monitored during scratching. Scratch-induced damage of coating, specifically fracture or delamination, can be monitored by in situ friction force measurements and by optical and SEM imaging of the scratches after tests. A gradual increase in friction is associated with plowing, and an abrupt increase in friction is associated with fracture or catastrophic failure [26.100]. The load, corresponding to the abrupt increase in friction or an increase in friction above a certain value (typically 2× the initial value), provides a measure of scratch resistance or adhesive strength of a coating and is called "critical load". The depth of scratches with increasing scratch length or normal load is measured using an AFM, typically with an area of 10 × 10 μm [26.48, 49, 101].

The microscratch and microwear studies are also conducted using an AFM [26.23, 50, 99, 102, 103]. A square pyramidal diamond tip (tip radius ∼ 100 nm) or a three-sided pyramidal diamond (Berkovich) tip with an apex angle of 60° and a tip radius of about 100 nm mounted on a platinum-coated, rectangular stainless steel cantilever of stiffness of about 40 N/m is scanned



Fig. 26.16a,b

orthogonal to the long axis of the cantilever to generate scratch and wear marks. During the scratch test, the normal load is either kept constant or increased (typically from 0 to 100 µN) until damage occurs. Topography images of the scratch are obtained in situ with the AFM at a low load. By scanning the sample during scratching, wear experiments can be conducted. Wear at a constant load is monitored as a function of the number of cycles. Normal loads ranging from 10–80 µN are typically used.

Microscratch

Scratch tests conducted with a sharp diamond tip simulate a sharp asperity contact. In a scratch test, the cracking or delamination of a hard coating is signaled by a sudden increase in the coefficient of friction [26.23]. The load associated with this event is called the "critical load".

Wu [26.104], *Bhushan* et al. [26.70], *Gupta* and *Bhushan* [26.12,47], and *Li* and *Bhushan* [26.48,49,101] have used a nanoindenter to perform microscratch studies (mechanical durability) of various carbon coatings. The coefficient of friction profiles as a function of increasing normal load and AFM surface height maps of regions over scratches at the respective critical loads (indicated by the arrows in the friction profiles and AFM images) made on the various coatings of different thicknesses and single-crystal silicon substrate using a conical tip are compared in Figs. 26.16 and 26.17. *Bhushan* and *Koinkar* [26.102], *Koinkar* and



Fig. 26.16a–d Coefficient of friction profiles as a function of normal load and corresponding AFM surface height maps of regions over scratches at the respective critical loads (indicated by the arrows in the friction profiles and AFM images) for coatings of different thicknesses deposited by various deposition techniques: **(a)** FCA, **(b)** IB, **(c)** ECR-CVD, **(d)** SP

Bhushan [26.103], *Bhushan* [26.23], and *Sundararajan* and *Bhushan* [26.50, 99] have used an AFM to perform microscratch studies. Data for various coatings of different thicknesses and silicon substrate using a Berkovich tip are compared in Figs. 26.18 and 26.19. Critical loads for various coatings tested using a nanoindenter and AFM are summarized in Fig. 26.20. The selected data for 20-nm-thick coatings obtained using nanoindenter are also presented in Fig. 26.10 and Table 26.5.

It can be seen that a well-defined critical load exists for each coating. The AFM images clearly show that below the critical loads the coatings were plowed by the scratch tip, associated with the plastic flow of materials.



Fig. 26.17 Coefficient of friction profiles as a function of normal load and corresponding AFM surface height maps of regions over scratches at the respective critical loads (indicated by the arrows in the friction profiles and AFM images) for Si(100)


a)
FCA 3.5 nm
FCA 5 nm
FCA 10 nm
FCA 20 nm
b)
ECR–CVD 3.5 nm
ECR–CVD 5 nm
ECR–CVD 10 nm
ECR–CVD 20 nm
Coefficient of friction
0.0
0.1
0.2
0.3
0.4
0.5
0
25
50
75
100
125
Normal load (µN)
A
B
0 nm
20 nm
2 µm



Fig. 26.18a–c Coefficient of friction profiles during scratch as a function of normal load and corresponding AFM surface height maps for **(a)** FCA, **(b)** ECR-CVD, and **(c)** SP coatings [26.99]

At and after the critical loads, debris (chips) or buckling was observed on the sides of scratches. Delamination or buckling can be observed around or after the critical loads, which suggests that the damage starts from delamination and buckling. For the 3.5- and 5-nm-thick FCA coatings, before the critical loads small debris is observed on the sides of scratches. This suggests that the thinner FCA coatings are not so durable. It is obvious that for a given deposition method, the critical loads increase with increasing coating thickness. This indicates that the critical load is determined not only by the adhesion strength to the substrate, but also by the coating thickness. We note that the debris generated on the thicker coatings is larger than that generated on the thinner coatings. For a thicker coating, it is more difficult to be broken; the broken coating chips (debris) for a thicker coating are larger than those for the thinner coatings. The difference in the residual stresses of the coatings of different thicknesses could also affect the size of debris. The AFM image shows that the silicon substrate was damaged by plowing, associated with the plastic flow of materials. At and after the critical load, small and uniform debris is observed and the amount of debris increases with increasing normal load.



Fig. 26.19 Coefficient of friction profiles during scratch as a function of normal load and corresponding AFM surface height maps for Si(100) [26.99]



Fig. 26.20a,b Critical loads estimated from the coefficient of friction profiles from **(a)** nanoindenter and **(b)** AFM tests for various coatings of different thicknesses and Si(100) substrate



Fig. 26.21a,b Measured critical loads estimated from the coefficient of friction profiles from AFM tests as a function of **(a)** coating hardness and **(b)** fracture toughness. Coating hardness and fracture toughness values were obtained using a nanoindenter on 100-nm-thick coatings (Table 26.5)

Since at the critical load, the damage mechanism appears to be the onset of plowing, higher hardness and fracture toughness of a coating will therefore result in a higher load required for deformation and hence a higher critical load. Figure 26.21 shows critical loads of the various coatings, obtained with AFM tests, as a function of the coating hardness and fracture toughness (from Table 26.5). It can be seen that, in general, higher coating hardness and fracture toughness result in a higher critical load. The only exceptions are the FCA coatings at 5- and 3.5-nm coating thickness, which show the lowest critical loads despite their high hardness and fracture toughness. The brittleness of the thinner FCA coatings may be one reason for their low critical loads. The mechanical properties of coatings that are less than 10 nm thick are unknown. The FCA process may result in coatings with low hardness at such low thickness due to differences in coating stoichiometry and structure compared to the coatings of higher thickness. Also, at these thicknesses stresses at the coating-substrate interface may affect adhesion and load-carrying capacity of the coatings.

Based on the experimental results, a schematic of scratch damage mechanisms of the DLC coatings used in this study is shown in Fig. 26.22. Below the critical load, if a coating has a good combination of strength and fracture toughness, plowing associated with the plastic flow of materials is responsible for the damage of coating (Fig. 26.22a). Whereas if a coating has a lower fracture toughness, cracking could occur during plowing, asso-



Fig. 26.22a–d Schematic of scratch damage mechanisms of the DLC coatings: **(a)** plowing associated with the plastic flow of materials, **(b)** plowing associated with the formation of small debris, **(c)** delamination and buckling at the critical load, and **(d)** breakdown via through coating thickness cracking at and after the critical load [26.48]

ciated with the formation of small debris (Fig. 26.22b). When normal load increases up to the critical load, delamination or buckling will occur at the coating/substrate interface (Fig. 26.22c). A further increase in normal load will result in the breakdown of coating via through coating thickness cracking, as shown in Fig. 26.22d. Therefore, adhesion strength plays a crucial role in the determination of critical load. If a coating has stronger adhesive strength with the substrate, the coating is more difficult to delaminate, which will result in a higher critical load. The interfacial and residual stresses of a coating could greatly affect the delamination and buckling [26.1]. The coating with higher interfacial and residual stresses is more easily delaminated and buckled, which will result in a low critical load. It has been reported earlier that the FCA coatings have higher residual stresses than the other coatings [26.47]. Interfacial stresses play a more important role when a coating gets thinner. A large mismatch in elastic modulus between the FCA coatings and the silicon substrate may cause large interfacial stresses. This may be why the thinner FCA coatings show relatively low critical loads compared with the thicker FCA coatings, even though the FCA coatings have a higher hardness and elastic modulus. The brittleness of the thinner FCA coatings may be another reason for the lower critical loads. The strength and fracture toughness of a coating also affect the critical load. Higher strength and fracture toughness will make the coating more difficult to be broken after delamination and buckling. The high scratch resistance/adhesion of FCA coatings is attributed to an atomic intermixing at the coating-substrate interface because of high kinetic energy (2 keV) plasma formed during the cathodic arc deposition process [26.57]. The atomic intermixing at the interface provides a graded compositional transition between the coating and the substrate materials. In all other coatings used in this study, the kinetic energy of the plasma was insufficient for atomic intermixing.

Gupta and *Bhushan* [26.12, 47] and *Li* and *Bhushan* [26.48,49] measured scratch resistance of DLC coatings deposited on Al_2O_3-TiC, Ni-Zn ferrite, and single-crystal silicon substrates. For good adhesion of DLC coating to other substrates, in most cases, an interlayer of silicon is required except for cathodic arc deposited coatings. The best adhesion with cathodic arc carbon coating is obtained on electrically conducting substrates such as Al_2O_3-TiC and silicon, as compared to Ni-Zn ferrite.

Microwear

Microwear studies can be conducted using an AFM [26.23]. For microwear studies, a three-sided pyramidal single-crystal natural diamond tip with an apex angle of about 80° and a tip radius of about 100 nm is used at relatively high loads of 1–150 µN. The diamond tip is mounted on a stainless steel cantilever beam with a normal stiffness of about 30 N/m. The sample is generally scanned in a direction orthogonal to the long axis of the cantilever beam (typically at a rate of 0.5 Hz). The tip is mounted on the beam such that one of its edges is orthogonal to the beam axis. In wear studies, typically an area of 2 µm × 2 µm is scanned for a selected number of cycles.


a)
Si(100)
nm
100
50
0
W=20 μN
2 cycles
d=8 nm
0
1.00
2.00
3.00
4.00 μm
b)
10 nm
FCA
IB
ECR–CVD
SP
W=45 μN
1 cycle
d=0.8 nm
W=45 μN
3 cycles
d=2.5 nm
W=60 μN
5 cycles
d=2 nm
W=35μN
1 cycle
d=8 nm
13 cycles
d=2 nm
12 cycles
d=3 nm
30 cycles
d=2.5 nm
2 cycles
d=13 nm
16 cycles
d=22 nm
17 cycles
d=23 nm
48 cycles
d=18 nm

Fig. 26.23a,b AFM images of wear marks on **(a)** bare Si(100), and **(b)** all 10-nm-thick DLC coatings [26.50]

Microwear studies of various types of DLC coatings have been conducted [26.50, 102, 103]. Fig. 26.23a shows a wear mark on uncoated Si(100). Wear occurs uniformly and material is removed layer by layer via plowing from the first cycle, resulting in the constant friction force seen during the wear (Fig. 26.24a). Figure 26.23b shows AFM images of the wear marks on all 10 nm coatings. It is seen that coatings wear nonuniformly. Coating failure is sudden and accompanied by a sudden rise in the friction force (Fig. 26.24b). Figure 26.24 shows the wear depth of Si(100) substrate and various DLC coatings at two different loads. FCA and ECR-CVD, 20-nm-thick coatings show excellent wear resistance up to 80 μN, the load that is required for the IB 20 nm coating to fail. In these tests, "failure" of a coating results when the wear depth exceeds the quoted coating thickness. The SP 20 nm coating fails at the much lower load of 35 μN. At 60 μN, the coating hardly provides any protection. Moving on to the 10 nm coatings, ECR-CVD coating requires about 45 cycles at 60 μN to fail as compared to IB and FCA, which fail at 45 μN. The FCA coating exhibits slight roughening in the wear track after the first few cycles, which leads to an increase in the friction force. The SP coating continues to exhibit poor resistance, failing at 20 μN. For the 5 nm coatings, the load required to fail the coatings continues to decrease. But IB and ECR-CVD still provide adequate protection as compared to bare Si(100) in that order, failing at 35 μN compared to FCA at 25 μN and SP at 20 μN. Almost all the 20, 10, and 5 nm coatings provide better wear resistance than bare silicon. At 3.5 nm, FCA coating



Fig. 26.24a,b Wear data of **(a)** bare Si(100) and **(b)** all DLC coatings. Coating thickness is constant along each row in **(b)**. Both wear depth and coefficient of friction during wear for a given cycle are plotted [26.50]

provides no wear resistance, failing almost instantly at 20 µN. The IB and ECR-CVD coating show good wear resistance at 20 µN compared to bare Si(100). But IB lasts only about 10 cycles and ECR-CVD about 3 cycles at 25 µN.

The wear tests highlight the differences in the coatings more vividly than the scratch tests. At higher thicknesses (10 and 20 nm), the ECR-CVD and FCA coatings appear to show the best wear resistance. This is probably due to higher hardness of the coatings (see Table 26.5). At 5 nm, IB coating appears to be the best. FCA coatings show poorer wear resistance with decreasing coating thickness. This suggests that the trends in hardness seen in Table 26.5 no longer hold at low thicknesses. SP coatings showed consistently poor wear resistance at all thicknesses. The IB 3.5 nm coating does provide reasonable wear protection at low loads.

26.3.3 Macroscale Tribological Characterization

So far, data on mechanical characterization and microscratch and microwear studies using a nanoindenter and an AFM have been presented. Mechanical properties affect tribological performance of the coatings, and microwear studies simulate a single asperity contact, which helps in developing a fundamental understanding of the wear process. These studies are useful in screening various candidates, as well as understanding the relationships between deposition conditions and properties of various samples. As a next step, macroscale friction and wear tests need to be conducted to measure tribological performance of the coatings.

Macroscale accelerated friction and wear tests to screen a large number of candidates and functional tests on selected candidates have been conducted. An accelerated test is designed to accelerate the wear process such that it does not change the failure mechanism. The accelerated friction and wear tests are generally conducted using a ball-on-flat tribometer under reciprocating motion [26.70]. Typically, a diamond tip with a 20 µm tip radius or a sapphire ball with a 3 mm diameter and surface finish of about 2 nm RMS is slid against the coated substrates at selected loads. Coefficient of friction is monitored during the tests.

Functional tests are conducted using an actual machine under close-to-actual operating conditions for which coatings are developed. Generally, the tests are accelerated somewhat to fail the interface in a short time.

Accelerated Friction and Wear Tests

Li and *Bhushan* [26.48] conducted accelerated friction and wear tests on DLC coatings deposited by various deposition techniques using a ball-on-flat tribometer.



Fig. 26.25 Optical micrographs of wear tracks and debris formed on the various coatings of different thicknesses and silicon substrate when slid against a sapphire ball after sliding distance of 5 m. The end of the wear track is on the right-hand side of the image



Fig. 26.26 Wear damage index bar chart of the various coatings of different thicknesses and Si(100) substrate based on optical examination of the wear tracks and debris

Average values of coefficient of friction are presented in Table 26.5. The optical micrographs of wear tracks and debris formed on all samples when slid against a sapphire ball after a sliding distance of 5 m are presented in Fig. 26.25. The normal load used for the 20- and 10-nm-thick coatings is 200 mN, and the normal load used for the 5- and 3.5-nm-thick coatings and silicon substrate is 150 mN.

Among the 20-nm-thick coatings, the SP coating exhibits a higher coefficient of friction of about 0.3 than the other coatings, which have comparable values of coefficient of friction of about 0.2. The optical micrographs show that the SP coating has a larger wear track and more debris than the IB coatings. No wear track and debris were found on the 20-nm-thick FCA and ECR-CVD coatings. The optical micrographs of 10-nm-thick coatings show that the SP coating was severely damaged, showing a large wear track with scratches and lots of debris. The FCA and ECR-CVD coatings show smaller wear tracks and less debris than the IB coatings.

For the 5-nm-thick coatings, the wear tracks and debris of the IB and ECR-CVD coatings are comparable. The bad wear resistance of the 5-nm-thick FCA coating is in good agreement with the low scratch critical load, which may be due to the higher interfacial and residual stresses as well as brittleness of the coating.

At 3.5 nm, all coatings exhibit wear. The FCA coating provides no wear resistance, failing instantly like the silicon substrate. Large block-like debris is observed on the sides of the wear track of the FCA coating. This indicates that large region delamination and buckling occurred during sliding, resulting in large block-like debris. This block-like debris, in turn, scratched the coating, making the coating damage even more severe. The IB and ECR-CVD coatings are able to provide some protection against wear at 3.5 nm.

In order to better evaluate the wear resistance of various coatings, based on the optical examination of the wear tracks and debris after tests, the wear damage index bar chart of the various coatings of different thicknesses and an uncoated silicon substrate is presented in Fig. 26.26. Among the 20- and 10-nm-thick coatings, the SP coatings show the worst damage, followed by FCA/ECR-CVD. At 5 nm, the FCA and SP coatings show the worst damage, followed by IB and ECR-CVD coatings. All 3.5-nm-thick coatings show the same heavy damage as the uncoated silicon substrate.

The wear damage mechanisms of thick and thin DLC coatings studied are believed to be as illustrated in Fig. 26.27. At the early stages of sliding, deformation zone and Hertzian and wear fatigue cracks formed beneath the surface extend within the coating on subsequent sliding [26.1]. Formation of fatigue cracks depend on the hardness and subsequent cycles. These are controlled by the sp^3-to-sp^2 ratio. For thicker coating, the cracks generally do not penetrate the coating. For a thinner coating, the cracks easily propagate down to the interface with the aid of the interfacial stresses and get diverted along the interface just enough to cause local delamination of the coating. When this happens, the coating experiences excessive plowing. At this point, the coating fails catastrophically, resulting in a sudden rise



Fig. 26.27 Schematic of wear damage mechanisms of thick and thin DLC coatings [26.48]

in the coefficient of friction. All 3.5-nm-thick coatings failed much quicker than the thicker coatings. It appears that these thin coatings have very low load-carrying capacity and, therefore, the substrate undergoes deformation almost immediately. This generates stresses at the interface that weaken the coating adhesion and lead to delamination of the coating. Another reason may be that the thickness is insufficient to produce a coating comprised of the DLC structure. Instead, the bulk may be made up of a matrix characteristic of the interface region where atomic mixing occurs with the substrate and/or any interlayer used. This would also result in poor wear resistance and silicon-like behavior of the coating, especially in the case of FCA coatings, which show the worst performance at 3.5 nm. In contrast to the other coatings, all SP coatings show the worst wear performance at any thickness (Fig. 26.25). This may be due to their poor mechanical properties, such as lower hardness and scratch resistance, compared to the other coatings.



Fig. 26.28 Coefficient of friction as a function of relative humidity and water vapor partial pressure of RF-plasma deposited amorphous carbon coating and bulk graphitic carbon coating sliding against a steel ball

Comparison of Figs. 26.20 and 26.26 shows a very good correlation between the wear damage and scratch critical loads. Less wear damage corresponds to higher scratch critical load. Based on the data, thicker coatings do show better scratch and wear resistance than thinner coatings. This is probably due to better load-carrying capacity of the thick coatings compared to the thinner ones. For a given coating thickness, higher hardness and fracture toughness and better adhesion strength are believed to be responsible for the superior wear performance.

Effect of Environment

Friction and wear performance of amorphous carbon coatings are found to be strongly dependent on the water vapor content and partial gas pressure in the test environment. The friction data for an amorphous carbon film on the silicon substrate sliding against steel are presented as a function of the partial pressure of water vapor in Fig. 26.28 [26.1, 13, 69, 105, 106]. Friction increases dramatically above a relative humidity of about 40%. At high relative humidity, condensed water vapor forms meniscus bridges at the contacting asperities, and the meniscii result in an intrinsic attractive force that is responsible for an increase in friction. For completeness, the data for the coefficient of friction of bulk graphitic carbon are also presented in Fig. 26.28. Note that friction decreases with an increase in the relative humidity [26.107]. Graphitic carbon has a layered lattice crystal structure. Graphite absorbs po-



Fig. 26.29 Coefficient of friction as a function of sliding distance for a ceramic slider against a magnetic disk coated with 20-nm-thick DC magnetron sputtered DLC coating, measured at a speed of 0.06 m/s and 10 g load. The environment is alternated between oxygen and nitrogen gases [26.108]

lar gases (H_2O, O_2, CO_2, NH_3, etc.) at the edges of the crystallites, which weakens the interlayer bonding forces facilitating interlayer slip and results in lower friction [26.1].

To better study the effect of environment for carbon coated magnetic disks, a number of tests have been conducted in controlled environments. *Marchon* et al. [26.108] conducted tests in alternating environments of oxygen and nitrogen gases, Fig. 26.29. The coefficient of friction increases as soon as oxygen is added to the test environment, whereas in a nitrogen environment the coefficient of friction reduces slightly. Tribochemical oxidation of the DLC coating in the oxidizing environment is responsible for an increase in the coefficient of friction, implying wear. *Dugger* et al. [26.109], *Strom* et al. [26.110], *Bhushan* and *Ruan* [26.111], and *Bhushan* et al. [26.71] conducted tests with DLC coated magnetic disks (with about 2-nm-thick perfluoropolyether lubricant film) in contact with Al_2O_3-TiC sliders, in different gaseous environments including a high vacuum of 2×10^{-7} Torr, Fig. 26.30. The wear lives are shortest in high vacuum and longest in most atmospheres of nitrogen and argon with the following order (from best to worst): argon or nitrogen, $Ar+H_2O$, ambient, $Ar+O_2$, and $Ar+H_2O$, vacuum. From this sequence of wear performance, we can see that having oxygen and water in an operating environment worsens wear performance of the coatings, but having nothing in it (vacuum) is the worst of all. Indeed, failure mechanisms differ in various environments. In high vacuum, intimate contact between disk and slider surfaces results in significant wear. In ambient air, $Ar+O_2$, and $Ar+H_2O$, tribochemical oxidation of the carbon overcoat is responsible for interface failure. For experiments performed in pure argon and nitrogen, mechanical shearing of the asperities cause the formation of debris, which is responsible for the formation of scratch marks on the carbon surface as could be observed with an optical microscope [26.71].



Fig. 26.30 Durability measured by sliding a Al_2O_3-TiC magnetic slider against a magnetic disk coated with 20-nm-thick DC sputtered amorphous carbon coating and 2-nm-thick perfluoropolyether film, measured at a speed of 0.75 m/s and 10 g load. Vacuum refers to 2×10^{-7} Torr [26.71]

Functional Tests

Magnetic thin-film heads made with Al_2O_3-TiC substrate are used in magnetic storage applications [26.13]. A multilayered thin-film pole-tip structure present on the head surface wears more rapidly than the much harder Al_2O_3-TiC substrate. Pole-tip recession (PTR) is a serious concern in magnetic storage [26.15–19,112]. Two of the diamond-like carbon coatings superior in mechanical properties – ion beam and cathodic arc carbon – were deposited on the air bearing surfaces of Al_2O_3-TiC head sliders [26.15]. The functional tests were conducted by running a metal-particle (MP) tape in a computer tape drive. Average PTR as a function of sliding distance data are presented in Fig. 26.31. We note that PTR increases for the uncoated head, whereas for the coated heads there



Fig. 26.31a,b Pole tip recession as a function of sliding distance measured with an AFM for **(a)** uncoated and 20-nm-thick ion beam carbon coated, and **(b)** uncoated and 20-nm-thick cathodic arc carbon coated Al_2O_3-TiC heads run against MP tapes [26.15]



Fig. 26.32 Quantified XPS data for various DLC coatings on Si(100) substrate [26.50]. Atomic concentrations are shown



Fig. 26.33 (a) XPS spectra for FCA and SP coatings of 5 nm and 20 nm coating thicknesses on Si(100) substrate, and **(b)** AES spectra for FCA and SP coatings at 5 nm thickness on Si(100) substrate [26.50]

is a slight increase in PTR in early sliding followed by little change. Thus, coatings provide protection.

Micromechanical and accelerated and functional tribological data presented here clearly suggest that there is a good correlation between the scratch resistance and wear resistance measured using accelerated tests and functional tests. Thus, scratch tests can be successfully used to screen coatings for wear applications.

26.3.4 Coating Continuity Analysis

Ultrathin coatings less than 10 nm may not uniformly coat the sample surface. In other words, coating may be discontinuous and deposited in the form of islands on the microscale. A possible reason for poor wear protection and the nonuniform failure of the coatings may be due to poor coverage of the thin coatings on the substrate. Coating continuity can be studied by using surface analytical techniques such as Auger and/or XPS analyses. Any discontinuity with coating thickness less than the sampling depth of the instrument will detect locally the substrate species [26.49, 50, 102].

The results of XPS analysis on various coatings deposited on Si(100) substrates, over a 1.3 mm^2 region (single point measurement with spot diameter of 1,300 μm) are shown in Fig. 26.32. The sampling depth is about 2–3 nm. The poor SP coatings show much less carbon content ($<$ 75% atomic concentration) as does the poor 5 nm and 3.5 nm FCA coatings ($<$ 60%) compared to the IB and ECR-CVD coatings. Silicon is detected in all 5 nm coatings. From the data it is hard to say if the Si is from the substrate or from exposed regions due to coating discontinuity. Based on the sampling depth any Si detected in 3.5 nm coatings would likely be from the substrate. The other interesting observation is that all poor coatings (all SP and FCA 5 and 3.5 nm) show almost twice the oxygen content than that of the other coatings. Any oxygen present may be due to leaks in the deposition chamber and is present in the form of silicon oxides.

AES measurements averaged over a scan area of 900 μm^2 were conducted on FCA and SP 5 nm coatings at six different regions on each sample. Very little silicon was detected on this scale, and the detected peaks were characteristic of oxides. The oxygen levels were comparable to that seen for the good coatings by XPS. These contrast the XPS measurements at a larger scale, suggesting that the coating possesses discontinuities only at isolated areas and that the 5 nm coatings are generally continuous on the microscale. Figure 26.33 shows representative XPS and AES spectra of selected samples.

References

26.1 B. Bhushan, B. K. Gupta: *Handbook of Tribology: Materials, Coatings, and Surface Treatments*, reprint edn. (Krieger, Malabar 1997)
26.2 B. Bhushan: *Principles and Applications of Tribology* (Wiley, New York 1999)
26.3 B. Bhushan: *Introduction to Tribology* (Wiley, New York 2002)
26.4 B. Bhushan, B. K. Gupta, G. W. VanCleef, C. Capp, J. V. Coe: Fullerene (C_{60}) films for solid lubrication, Tribol. Trans. **36** (1993) 573–580
26.5 B. K. Gupta, B. Bhushan, C. Capp, J. V. Coe: Material characterization and effect of purity and ion implantation on the friction and wear of sublimed fullerene films, J. Mater. Res. **9** (1994) 2823–2838
26.6 B. K. Gupta, B. Bhushan: Fullerene particles as an additive to liquid lubricants and greases for low friction and wear, Lubr. Eng. **50** (1994) 524–528
26.7 B. Bhushan, V. V. Subramaniam, A. Malshe, B. K. Gupta, J. Ruan: Tribological properties of polished diamond films, J. Appl. Phys. **74** (1993) 4174–4180
26.8 B. Bhushan, B. K. Gupta, V. V. Subramaniam: Polishing of diamond films, Diam. Films Technol. **4** (1994) 71–97
26.9 P. Sander, U. Kaiser, M. Altebockwinkel, L. Wiedmann, A. Benninghoven, R. E. Sah, P. Koidl: Depth profile analysis of hydrogenated carbon layers on silicon by X-ray photoelectron spectroscopy, auger electron spectroscopy, electron energy-loss spectroscopy, and secondary ion mass spectrometry, J. Vac. Sci. Technol. A **5** (1987) 1470–1473
26.10 A. Matthews, S. S. Eskildsen: Engineering applications for diamond-like carbon, Diam. Relat. Mater. **3** (1994) 902–911
26.11 A. H. Lettington: Applications of diamond-like carbon thin films, Carbon **36** (1998) 555–560
26.12 B. K. Gupta, B. Bhushan: Mechanical and tribological properties of hard carbon coatings for magnetic recording heads, Wear **190** (1995) 110–122
26.13 B. Bhushan: *Tribology and Mechanics of Magnetic Storage Devices*, 2nd edn. (Springer, New York 1996)
26.14 B. Bhushan: *Mechanics and Reliability of Flexible Magnetic Media*, 2nd edn. (Springer, New York 2000)
26.15 B. Bhushan, S. T. Patton, R. Sundaram, S. Dey: Pole tip recession studies of hard carbon-coated thin-film tape heads, J. Appl. Phys. **79** (1996) 5916–5918
26.16 J. Xu, B. Bhushan: Pole tip recession studies of thin-film rigid disk head sliders II: Effects of air bearing surface and pole tip region designs and carbon coating, Wear **219** (1998) 30–41
26.17 W. W. Scott, B. Bhushan: Corrosion and wear studies of uncoated and ultra-thin DLC coated magnetic tape-write heads and magnetic tapes, Wear **243** (2000) 31–42
26.18 W. W. Scott, B. Bhushan: Loose debris and head stain generation and pole tip recession in modern tape drives, J. Info. Storage Proc. Syst. **2** (2000) 221–254
26.19 W. W. Scott, B. Bhushan, A. V. Lakshmikumaran: Ultrathin diamond-like carbon coatings used for reduction of pole tip recession in magnetic tape heads, J. Appl Phys **87** (2000) 6182–6184
26.20 B. Bhushan: Macro- and microtribology of magnetic storage devices. In: *Modern Tribology Handbook*, ed. by B. Bhushan (CRC, Boca Raton 2001) pp. 1413–1513
26.21 B. Bhushan: Nanotribology and nanomechanics of MEMS devices, Proc. Ninth Annual Workshop on Micro Electro Mechanical Systems 1996 (IEEE, New York 91–98
26.22 B. Bhushan (Ed.): *Tribology Issues and Opportunities in MEMS* (Kluwer, Dordrecht 1998)
26.23 B. Bhushan: *Handbook of Micro/Nanotribology*, 2nd edn. (CRC, Boca Raton 1999)
26.24 B. Bhushan: Macro- and microtribology of MEMS materials. In: *Modern Tribology Handbook*, ed. by B. Bhushan (CRC, Boca Raton 2001) pp. 1515–1548
26.25 S. Aisenberg, R. Chabot: Ion beam deposition of thin films of diamond like carbon, J. Appl. Phys. **49** (1971) 2953–2958
26.26 E. G. Spencer, P. H. Schmidt, D. C. Joy, F. J. Sansalone: Ion beam deposited polycrystalline diamond-like films, Appl. Phys. Lett. **29** (1976) 118–120
26.27 A. Grill, B. S. Meyerson: Development and status of diamondlike carbon. In: *Synthetic Diamond: Emerging CVD Science and Technology*, ed. by K. E. Spear, J. P. Dismukes (Wiley, New York 1994) pp. 91–141
26.28 Y. Catherine: Preparation techniques for diamond-like carbon. In: *Diamond and Diamond-like Films and Coatings*, ed. by R. E. Clausing, L. L. Horton, J. C. Angus, P. Koidl (Plenum, New York 1991) pp. 193–227
26.29 J. J. Cuomo, D. L. Pappas, J. Bruley, J. P. Doyle, K. L. Seagner: Vapor deposition processes for amorphous carbon films with sp^3 fractions approaching diamond, J. Appl. Phys. **70** (1991) 1706–1711
26.30 J. C. Angus, C. C. Hayman: Low pressure metastable growth of diamond and diamondlike phase, Science **241** (1988) 913–921
26.31 J. C. Angus, F. Jensen: Dense diamondlike hydrocarbons as random covalent networks, J. Vac. Sci. Technol. A **6** (1988) 1778–1782
26.32 D. C. Green, D. R. McKenzie, P. B. Lukins: The microstructure of carbon thin films, Mater. Sci. Forum **52–53** (1989) 103–124
26.33 N. H. Cho, K. M. Krishnan, D. K. Veirs, M. D. Rubin, C. B. Hopper, B. Bhushan, D. B. Bogy: Chemical structure and physical properties of diamond-like

amorphous carbon films prepared by magnetron sputtering, J. Mater. Res. **5** (1990) 2543–2554

26.34 J. C. Angus: Diamond and diamondlike films, Thin Solid Films **216** (1992) 126–133

26.35 B. Bhushan, A. J. Kellock, N. H. Cho, J. W. Ager III: Characterization of chemical bonding and physical characteristic of diamond-like amorphous carbon and diamond films, J. Mater. Res. **7** (1992) 404–410

26.36 J. Robertson: Properties of diamond-like carbon, Surf. Coat. Technol. **50** (1992) 185–203

26.37 N. Savvides, B. Window: Diamondlike amorphous carbon films prepared by magnetron sputtering of graphite, J. Vac. Sci. Technol. A **3** (1985) 2386–2390

26.38 J. C. Angus, P. Koidl, S. Domitz: Carbon thin films. In: *Plasma Deposited Thin Films*, ed. by J. Mort, F. Jensen (CRC, Boca Raton 1986) pp. 89–127

26.39 J. Robertson: Amorphous carbon, Adv. Phys. **35** (1986) 317–374

26.40 M. Rubin, C. B. Hooper, N. H. Cho, B. Bhushan: Optical and mechanical properties of DC sputtered carbon films, J. Mater. Res. **5** (1990) 2538–2542

26.41 G. J. Vandentop, M. Kawasaki, R. M. Nix, I. G. Brown, M. Salmeron, G. A. Somorjai: Formation of hydrogenated amorphous carbon films of controlled hardness from a methane plasma, Phys. Rev. B **41** (1990) 3200–3210

26.42 J. J. Cuomo, D. L. Pappas, R. Lossy, J. P. Doyle, J. Bruley, G. W. Di Bello, W. Krakow: Energetic carbon deposition at oblique angles, J. Vac. Sci. Technol. A **10** (1992) 3414–3418

26.43 D. L. Pappas, K. L. Saegner, J. Bruley, W. Krakow, J. J. Cuomo: Pulsed laser deposition of diamondlike carbon films, J. Appl. Phys. **71** (1992) 5675–5684

26.44 H. J. Scheibe, B. Schultrich: DLC film deposition by laser-arc and study of properties, Thin Solid Films **246** (1994) 92–102

26.45 C. Donnet, A. Grill: Friction control of diamond-like carbon coatings, Surf. Coat. Technol. **94-95** (1997) 456

26.46 A. Grill: Tribological properties of diamondlike carbon and related materials, Surf. Coat. Technol. **94-95** (1997) 507

26.47 B. K. Gupta, B. Bhushan: Micromechanical properties of amorphous carbon coatings deposited by different deposition techniques, Thin Solid Films **270** (1995) 391–398

26.48 X. Li, B. Bhushan: Micro/nanomechanical and tribological characterization of ultra-thin amorphous carbon coatings, J. Mater. Res. **14** (1999) 2328–2337

26.49 X. Li, B. Bhushan: Mechanical and tribological studies of ultra-thin hard carbon overcoats for magnetic recording heads, Z. Metallkd. **90** (1999) 820–830

26.50 S. Sundararajan, B. Bhushan: Micro/nanotribology of ultra-thin hard amorphous carbon coatings using atomic force/friction force microscopy, Wear **225-229** (1999) 678–689

26.51 B. Bhushan: Chemical, mechanical, and tribological characterization of ultra-thin and hard amorphous carbon coatings as thin as 3.5 nm: Recent developments, Diam. Relat. Mater. **8** (1999) 1985–2015

26.52 I. I. Aksenov, V. E. Strel'Nitskii: Wear resistance of diamond-like carbon coatings, Surf. Coat. Technol. **47** (1991) 252–256

26.53 D. R. McKenzie, D. Muller, B. A. Pailthorpe, Z. H. Wang, E. Kravtchinskaia, D. Segal, P. B. Lukins, P. J. Martin, G. Amaratunga, P. H. Gaskell, A. Saeed: Properties of tetrahedral amorphous carbon prepared by vacuum arc deposition, Diam. Relat. Mater. **1** (1991) 51–59

26.54 R. Lossy, D. L. Pappas, R. A. Roy, J. J. Cuomo: Filtered arc deposition of amorphous diamond, Appl. Phys. Lett. **61** (1992) 171–173

26.55 I. G. Brown, A. Anders, S. Anders, M. R. Dickinson, I. C. Ivanov, R. A. MacGill, X. Y. Yao, K. M. Yu: Plasma synthesis of metallic and composite thin films with atomically mixed substrate bonding, Nucl. Instrum. Meth. Phys. Res. B **80-81** (1993) 1281–1287

26.56 P. J. Fallon, V. S. Veerasamy, C. A. Davis, J. Robertson, G. A. J. Amaratunga, W. I. Milne, J. Koskinen: Properties of filtered-ion-beam-deposited diamond-like carbon as a function of ion energy, Phys. Rev. B **48** (1993) 4777–4782

26.57 S. Anders, A. Anders, I. G. Brown, B. Wei, K. Komvopoulos, J. W. Ager III, K. M. Yu: Effect of vacuum arc deposition parameters on the properties of amorphous carbon thin films, Surf. Coat. Technol. **68-69** (1994) 388–393

26.58 S. Anders, A. Anders, I. G. Brown, M. R. Dickinson, R. A. MacGill: Metal plasma immersion ion implantation and deposition using arc plasma sources, J. Vac. Sci. Technol. B **12** (1994) 815–820

26.59 S. Anders, A. Anders, I. G. Brown: Transport of vacuum arc plasma through magnetic macroparticle filters, Plasma Sources Sci. **4** (1995) 1–12

26.60 D. M. Swec, M. J. Mirtich, B. A. Banks: Ion beam and plasma methods of producing diamondlike carbon films, Report No. NASATM102301, Cleveland 1988

26.61 A. Erdemir, M. Switala, R. Wei, P. Wilbur: A tribological investigation of the graphite-to-diamond-like behavior of amorphous carbon films ion beam deposited on ceramic substrates, Surf. Coat. Technol. **50** (1991) 17–23

26.62 A. Erdemir, F. A. Nicols, X. Z. Pan, R. Wei, P. J. Wilbur: Friction and wear performance of ion-beam deposited diamond-like carbon films on steel substrates, Diam. Relat. Mater. **3** (1993) 119–125

26.63 R. Wei, P. J. Wilbur, M. J. Liston: Effects of diamond-like hydrocarbon films on rolling contact fatigue of bearing steels, Diam. Relat. Mater. **2** (1993) 898–903

26.64 A. Erdemir, C. Donnet: Tribology of diamond, diamond-like carbon, and related films. In: *Modern Tribology Handbook*, ed. by B. Bhushan (CRC, Boca Raton 2001) pp. 871–908

26.65 J. Asmussen: Electron cyclotron resonance microwave discharges for etching and thin-film deposition, J. Vac. Sci. Technol. A **7** (1989) 883–893

26.66 J. Suzuki, S. Okada: Deposition of diamondlike carbon films using electron cyclotron resonance plasma chemical vapor deposition from ethylene gas, Jpn. J. Appl. Phys. **34** (1995) L1218–L1220

26.67 B. A. Banks, S. K. Rutledge: Ion beam sputter deposited diamond like films, J. Vac. Sci. Technol. **21** (1982) 807–814

26.68 C. Weissmantel, K. Bewilogua, K. Breuer, D. Dietrich, U. Ebersbach, H. J. Erler, B. Rau, G. Reisse: Preparation and properties of hard i-C and i-BN coatings, Thin Solid Films **96** (1982) 31–44

26.69 H. Dimigen, H. Hubsch: Applying low-friction wear-resistant thin solid films by physical vapor deposition, Philips Tech. Rev. **41** (1983/84) 186–197

26.70 B. Bhushan, B. K. Gupta, M. H. Azarian: Nanoindentation, microscratch, friction and wear studies for contact recording applications, Wear **181-183** (1995) 743–758

26.71 B. Bhushan, L. Yang, C. Gao, S. Suri, R. A. Miller, B. Marchon: Friction and wear studies of magnetic thin-film rigid disks with glass-ceramic, glass and aluminum-magnesium substrates, Wear **190** (1995) 44–59

26.72 L. Holland, S. M. Ojha: Deposition of hard and insulating carbonaceous films of an RF target in butane plasma, Thin Solid Films **38** (1976) L17–L19

26.73 L. P. Andersson: A review of recent work on hard i-C films, Thin Solid Films **86** (1981) 193–200

26.74 A. Bubenzer, B. Dischler, B. Brandt, P. Koidl: R.F. plasma deposited amorphous hydrogenated hard carbon thin films, preparation, properties and applications, J. Appl. Phys. **54** (1983) 4590–4594

26.75 A. Grill, B. S. Meyerson, V. V. Patel: Diamond-like carbon films by RF plasma-assisted chemical vapor deposition from acetylene, IBM J. Res. Develop. **34** (1990) 849–857

26.76 A. Grill, B. S. Meyerson, V. V. Patel: Interface modification for improving the adhesion of a-C:H to metals, J. Mater. Res. **3** (1988) 214

26.77 A. Grill, V. V. Patel, B. S. Meyerson: Optical and tribological properties of heat-treated diamond-like carbon, J. Mater. Res. **5** (1990) 2531–2537

26.78 F. Jansen, M. Machonkin, S. Kaplan, S. Hark: The effect of hydrogenation on the properties of ion beam sputter deposited amorphous carbon, J. Vac. Sci. Technol. A **3** (1985) 605–609

26.79 S. Kaplan, F. Jansen, M. Machonkin: Characterization of amorphous carbon-hydrogen films by solid-state nuclear magnetic resonance, Appl. Phys. Lett. **47** (1985) 750–753

26.80 H. C. Tsai, D. B. Bogy, M. K. Kundmann, D. K. Veirs, M. R. Hilton, S. T. Mayer: Structure and properties of sputtered carbon overcoats on rigid magnetic media disks, J. Vac. Sci. Technol. A **6** (1988) 2307–2315

26.81 B. Marchon, M. Salmeron, W. Siekhaus: Observation of graphitic and amorphous structures on the surface of hard carbon films by scanning tunneling microscopy, Phys. Rev. B **39** (1989) 12907–12910

26.82 B. Dischler, A. Bubenzer, P. Koidl: Hard carbon coatings with low optical-absorption, Appl. Phys. Lett. **42** (1983) 636–638

26.83 D. S. Knight, W. B. White: Characterization of diamond films by Raman spectroscopy, J. Mater. Res. **4** (1989) 385–393

26.84 J. W. Ager, D. K. Veirs, C. M. Rosenblatt: Spatially resolved Raman studies of diamond films grown by chemical vapor deposition, Phys. Rev. B **43** (1991) 6491–6499

26.85 W. Scharff, K. Hammer, O. Stenzel, J. Ullman, M. Vogel, T. Frauenheim, B. Eibisch, S. Roth, S. Schulze, I. Muhling: Preparation of amorphous i-C films by ion-assisted methods, Thin Solid Films **171** (1989) 157–169

26.86 B. Bhushan, X. Li: Nanomechanical characterization of solid surfaces and thin films, Int. Mater. Rev. **48** (2003) 125–164

26.87 X. Li, D. Diao, B. Bhushan: Fracture mechanisms of thin amorphous carbon films in nanoindentation, Acta Mater. **45** (1997) 4453–4461

26.88 X. Li, B. Bhushan: Measurement of fracture toughness of ultra-thin amorphous carbon films, Thin Solid Films **315** (1998) 214–221

26.89 X. Li, B. Bhushan: Evaluation of fracture toughness of ultra-thin amorphous carbon coatings deposited by different deposition techniques, Thin Solid Films **355-356** (1999) 330–336

26.90 X. Li, B. Bhushan: Development of a nanoscale fatigue measurement technique and its application to ultrathin amorphous carbon coatings, Scripta Mater. **47** (2002) 473–479

26.91 X. Li, B. Bhushan: Nanofatigue studies of ultrathin hard carbon overcoats used in magnetic storage devices, J. Appl. Phys. **91** (2002) 8334–8336

26.92 J. Robertson: Deposition of diamond-like carbon, Philos. Trans. R. Soc. London A **342** (1993) 277–286

26.93 S. J. Bull: Tribology of carbon coatings: DLC, diamond and beyond, Diam. Relat. Mater. **4** (1995) 827–836

26.94 N. Savvides, T. J. Bell: Microhardness and Young's modulus of diamond and diamondlike carbon films, J. Appl. Phys. **72** (1992) 2791–2796

26.95 B. Bhushan, M. F. Doerner: Role of mechanical properties and surface texture in the real area of contact of magnetic rigid disks, ASME J. Tribol. **111** (1989) 452–458

26.96 S. Suresh: *Fatigue of Materials* (Cambridge Univ. Press, Cambridge 1991)

26.97 D. B. Marshall, A. G. Evans: Measurement of adherence of residual stresses in thin films by indentation. I. Mechanics of interface delamination, J. Appl. Phys. **15** (1984) 2632–2638

26.98 A. G. Evans, J. W. Hutchinson: On the mechanics of delamination and spalling in compressed films, Int. J. Solids Struct. **20** (1984) 455–466

26.99 S. Sundararajan, B. Bhushan: Development of a continuous microscratch technique in an atomic force microscope and its application to study scratch resistance of ultrathin hard amorphous carbon coatings, J. Mater. Res. **16** (2001) 437–445

26.100 B. Bhushan, B. K. Gupta: Micromechanical characterization of Ni-P coated aluminum-magnesium, glass and glass-ceramic substrates and finished magnetic thin-film rigid disks, Adv. Info. Storage Syst. **6** (1995) 193–208

26.101 X. Li, B. Bhushan: Micromechanical and tribological characterization of hard amorphous carbon coatings as thin as 5 nm for magnetic recording heads, Wear **220** (1998) 51–58

26.102 B. Bhushan, V. N. Koinkar: Microscale mechanical and tribological characterization of hard amorphous coatings as thin as 5 nm for magnetic disks, Surf. Coat. Technol. **76–77** (1995) 655–669

26.103 V. N. Koinkar, B. Bhushan: Microtribological properties of hard amorphous carbon protective coatings for thin-film magnetic disks and heads, Proc. Inst. Mech. Eng., Part J **211** (1997) 365–372

26.104 T. W. Wu: Microscratch and load relaxation tests for ultra-thin films, J. Mater. Res. **6** (1991) 407–426

26.105 R. Memming, H. J. Tolle, P. E. Wierenga: Properties of polymeric layers of hydrogenated amorphous carbon produced by plasma-activated chemical vapor deposition: tribological and mechanical properties, Thin Solid Films **143** (1986) 31–41

26.106 C. Donnet, T. Le Mogne, L. Ponsonnet, M. Belin, A. Grill, V. Patel: The respective role of oxygen and water vapor on the tribology of hydrogenated diamond-like carbon coatings, Tribol. Lett. **4** (1998) 259

26.107 F. P. Bowden, J. E. Young: Friction of diamond, graphite and carbon and the influence of surface films, Proc. R. Soc. Lond. **208** (1951) 444–455

26.108 B. Marchon, N. Heiman, M. R. Khan: Evidence for tribochemical wear on amorphous carbon thin films, IEEE Trans. Magn. **26** (1990) 168–170

26.109 M. T. Dugger, Y. W. Chung, B. Bhushan, W. Rothschild: Friction, wear, and interfacial chemistry in thin film magnetic rigid disk files, ASME J. Tribol. **112** (1990) 238–245

26.110 B. D. Strom, D. B. Bogy, C. S. Bhatia, B. Bhushan: Tribochemical effects of various gases and water vapor on thin film magnetic disks with carbon overcoats, ASME J. Tribol. **113** (1991) 689–693

26.111 B. Bhushan, J. Ruan: Tribological performance of thin film amorphous carbon overcoats for magnetic recording rigid disks in various environments, Surf. Coat. Technol. **68/69** (1994) 644–650

26.112 B. Bhushan, G. S. A. M. Theunissen, X. Li: Tribological studies of chromium oxide films for magnetic recording applications, Thin Solid Films **311** (1997) 67–80

27. Self-Assembled Monolayers for Controlling Adhesion, Friction and Wear

Reliability of micro- and nanodevices, as well as magnetic storage devices require the use of lubricant films for the protection of sliding surfaces. To minimize high adhesion, friction, and because of small clearances in the devices, these films should be molecularly thick. Liquid films of low surface tension or certain hydrophobic solid films can be used. Ordered molecular assemblies with high hydrophobicity can be engineered using chemical grafting of various polymer molecules with suitable functional head groups, spacer chains and nonpolar surface terminal groups.

The classical approach to lubrication uses multi-molecular layers of liquid lubricants. Boundary lubricant films are formed by either physisorption, chemisorption, or chemical reaction. The physiosorbed films can be either monomolecularly or polymolecularly thick. The chemisorbed films are monomolecular, but stoichiometric films formed by chemical reaction can be multilayered. A good boundary lubricant should have a high degree of interaction between its molecules and the sliding surface. As a general rule, liquids are good lubricants when they are polar and thus able to grip on solid surfaces (or be adsorbed).

In this chapter, we focus on self-assembled monolayers (SAMs) for high hydrophobicity and/or low adhesion, friction, and wear. SAMs are produced by various organic precursors. We first present a primer to organic chemistry followed by an overview on suitable substrates, head groups, spacer chains, and end groups in the molecular chains and an overview of tribological properties of SAMs. The adhesion, friction, and wear properties of SAMs, having alkyl and biphenyl spacer chains with different surface terminal and head groups, are surveyed. The friction data are explained using a molecular spring model in which the local stiffness and intermolecular force govern its frictional performance. Based on the nanotribological studies of SAM films by AFM, they exhibit attractive hydrophobic and tribological properties.

27.1 **A Primer to Organic Chemistry** 834
27.1.1 Electronegativity/Polarity 834
27.1.2 Classification and Structure of Organic Compounds 835
27.1.3 Polar and Nonpolar Groups 838

27.2 **Self-Assembled Monolayers: Substrates, Head Groups, Spacer Chains, and End Groups** 839

27.3 **Tribological Properties of SAMs** 841
27.3.1 Surface Roughness and Friction Images of SAMs Films 844
27.3.2 Adhesion, Friction, and Work of Adhesion 844
27.3.3 Stiffness, Molecular Spring Model, and Micropatterned SAMs 848
27.3.4 Influence of Humidity, Temperature, and Velocity on Adhesion and Friction 850
27.3.5 Wear and Scratch Resistance of SAMs 853

27.4 **Closure** 856

References 857

Reliability of micro/nanodevices, also commonly referred to as micro/nanoelectromechanical systems (MEMS/NEMS), as well as magnetic storage devices (which include magnetic rigid disk drives, flexible disk drives, and tape drives) require the use of molecularly thick films for protection of sliding surfaces [27.1–8]. A solid or liquid film is generally necessary for acceptable tribological properties of sliding interfaces. However, a small quantity of high surface tension liquid present between smooth surfaces can substantially increase the adhesion, friction, and wear as a result of formation of menisci or adhesive bridges [27.9, 10]. It

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

becomes a major concern in micro/nanoscale devices operating at ultralow loads, as the liquid mediated adhesive force may be on the same order as the external load.

The source of the liquid film can be either preexisting film of liquid and/or capillary condensates of water vapor from the environment. If the liquid wets the surface ($0 \leq \theta < 90°$, where θ is the contact angle between the liquid-vapor interface and the liquid-solid interface for a liquid droplet sitting on a solid surface, Fig. 27.1a), the liquid surface is thereby constrained to lie parallel to the surface [27.11], and the complete liquid surface must therefore be concave in shape, Fig. 27.1b. Surface tension results in a pressure difference across any meniscus surface, referred to as capillary pressure or Laplace pressure, and is negative for a concave meniscus [27.9, 10]. The negative Laplace pressure results in an intrinsic attractive (adhesive) force, which depends on the interface roughness (local geometry of interacting asperities and number of asperities), the surface tension, and the contact angle. During sliding, frictional effects need to be overcome, not only because of external load, but also because of intrinsic adhesive force.



Fig. 27.1 (a) Schematic of a sessile-drop on a solid surface and the definition of contact angle, and **(b)** formation of meniscus bridges as a result of liquid present at an interface. The direct measurement of contact angle is most widely made from sessile-drops. The angle is generally measured by aligning a tangent with the drop profile at the point of contact with the solid surface using a telescope equipped with a goniometer eyepiece

Measured value of high static friction force contributed largely by liquid mediated adhesion (meniscus contribution) is generally referred to as “stiction”. Basically, there are three ways to minimize the effect of liquid-mediated adhesion: increase in surface roughness, use of hydrophobic (water-fearing) rather than hydrophilic (water-loving) surfaces, and the use of a liquid with low surface tension [27.9, 10, 12, 13].

As an example, bulk silicon and polysilicon films used in the construction of micro/nanodevices can be dipped in hydrofluoric (HF) to make them hydrophobic (e.g., *Maboudian* [27.14]; *Scherge* and *Schaefer* [27.15]). In HF etching of silicon, hydrogen passivates the silicon surface by saturating the dangling bonds, and it results in a hydrogen-terminated silicon surface that is responsible for less adsorption of water. However, after exposure of the treated surface to the environment, it reoxidizes, which can adsorb water, and thus the surface again becomes hydrophilic.

The surfaces can also be treated or coated with a liquid with relatively low surface tension or a certain solid film to make them hydrophobic and/or to control adhesion, friction, and wear. The liquid lubricant film should be thin (about half of the composite roughness of the interface) to minimize liquid-mediated adhesion contribution [27.9, 10, 12, 13]. Thus, for ultra-smooth surfaces with RMS roughness on the order of a few nm, molecularly thick liquid films are required for liquid lubrication. The classical approach to lubrication uses freely supported multi-molecular layers of liquid lubricants [27.2, 4, 9, 10, 16–19]. Boundary lubricant films are formed by either physisorption, chemisorption, or chemical reaction. The physiosorbed films can be either monomolecularly or polymolecularly thick. The chemisorbed films are monomolecular, but stoichiometric films formed by chemical reaction can be multilayered. In general, stability and durability of surface films decrease in the following order: chemically reacted films, chemisorbed films, and physisorbed films. A good boundary lubricant should have a high degree of interaction between its molecules and the sliding surface. As a general rule, liquids are good lubricants when they are polar and thus able to grip on solid surfaces (or be adsorbed). Polar lubricants contain reactive functional end groups. Boundary lubrication properties are also dependent on the molecular conformation and lubricant spreading. It should be noted that the liquid films with a thickness on the order of a few nm, may be discontinuous and may deposit in an island form of nonuniform thickness with a lateral resolution on the nanometerscale.

Solid films are also commonly used for controlling hydrophobicity and/or adhesion, friction, and wear. Hydrophobic films have nonpolar surface terminal groups (to be described later) that repel water. These films have low surface energy (15–30 dyn/cm) and high contact angle ($\theta \geq 90°$), which minimize wetting (e.g., *Zisman* [27.20]; *Schrader* and *Loeb* [27.21]; *Neumann* and *Spelt* [27.22]). It should be noted that these films do not totally eliminate wetting. Multi-molecularly thick (few tenths of a nm) films of conventional solid-lubricants have been studied. *Hansma* et al. [27.23] reported the deposition of multi-molecularly thick, highly-oriented PTFE films from the melt or vapor phase or from solution by a mechanical deposition technique by dragging the polymer at controlled temperature, pressure, and speed against a smooth glass substrate. *Scandella* et al. [27.24] reported that the coefficient of nanoscale friction of MoS_2 platelets on mica, obtained by exfoliation of lithium intercalated MoS_2 in water, was a factor of 1.4 less than that of mica itself. However, MoS_2 is reactive to water and its friction and wear properties degrade with an increase in humidity [27.9, 10]. Amorphous diamond-like carbon (DLC) coatings can be produced with extremely high hardness and are commercially used as wear-resistant coatings [27.25, 26]. Their largest application is in magnetic storage devices [27.2]. Doping of the DLC matrix with elements like hydrogen, nitrogen, oxygen, silicon, and fluorine influences their hydrophobicity and tribological properties [27.25, 27, 28]. Nitrogen and oxygen reduce the contact angle (or increase the surface energy), due to the strong polarity that is formed when these elements are bonded to carbon. On the other hand, silicon and fluorine increase the contact angle ranging from 70–100 ° (or reduce the surface energy to 20–40 dyn/cm), making them hydrophobic [27.29, 30]. Nanocomposite coatings with a diamond-like carbon (a-C:H) network and a glass-like a-Si:O network are generally deposited using a plasma-enhanced chemical vapor deposition (PECVD) technique in which plasma is formed from a siloxane precursor using a hot filament. For a fluorinated DLC, CF_4 is added as the fluorocarbon source to an acetylene plasma. In addition, fluorination of DLC can be achieved by the post-deposition treatment of DLC coatings in a CF_4 plasma. Silicon- and fluorine-containing DLC coatings mainly reduce their polarity due to the loss of sp^2-bonded carbon (polarization potential of the involved π electrons) and dangling bonds of the DLC network. As silicon and fluorine are unable to form double bonds, they force carbon into a sp^3 bonding state [27.30]. Friction and wear properties of both silicon-containing and fluorinated DLC coatings have been reported to be superior to that of conventional DLC coatings [27.31,32]. However, DLC coatings require line of sight deposition process, which prevents deposition on complex geometries. Furthermore, it has been reported that some self-assembled monolayers (SAMs) are superior to DLC coatings in hydrophobicity and tribological performance [27.33].

Organized and dense molecular-scale layers of, preferably, long-chain organic molecules are known to be superior lubricants on both macro- and micro/nanoscales as compared with freely supported multi-molecular layers [27.4, 34–38]. Common techniques to produce molecular-scale organized layers are Langmuir–Blodgett (LB) deposition and chemical grafting of organic molecules to realize SAMs [27.39,40]. In the LB technique, organic molecules from suitable amphiphilic molecules are first organized at the air-water interface and then physisorbed on a solid surface to form mono- or multi-molecular layers [27.41]. In the case of SAMs, the functional groups of molecules chemisorb on a solid surface, which results in the spontaneous formation of robust, highly ordered, oriented, and dense monolayers [27.40]. In both cases, the organic molecules used have well distinguished amphiphilic properties (hydrophilic functional head and a hydrophobic aliphatic tail) so that an adsorption of such molecules on an active inorganic substrate leads to their firm attachment to the surface. Direct organization of SAMs on the solid surfaces allows coating in the tight areas such as the bearing and journal surfaces in an assembled bearing. The weak adhesion of classical LB films to the substrate surface restricts their lifetimes during sliding, whereas certain SAMs can be very durable [27.34]. As a result, SAMs are of great interest in tribological applications.

Much of the research in the application of SAMs has been carried out for the so-called soft lithographic technique [27.42, 43]. This is a non-photolithographic technique. Photolithography is based on a projection-printing system used for projection of an image from a mask to a thin-film photoresist and its resolution is limited by optical diffraction limits. In the soft lithography, an elastomeric stamp or mold is used to generate micropatterns of SAMs either by contact printing (known as microcontact printing or μCP [27.44]), by embossing (imprinting) [27.45], or by replica molding [27.46], which circumvents the diffraction limits of photolithography. The stamps are generally cast from photolithographically generated patterned masters, and the stamp material is generally polydimethylsiloxane (PDMS). In µCP, the ink is a SAM precursor to produce nm-thick resists with lines thinner than 100 nm. Although soft lithography requires little capital investment, it is doubtful that it would ever replace well established photolithography. However, µCP and embossing techniques may be used to produce microdevices that are a substantially cheaper and more flexible choice of material for construction than conventional photolithography (e.g., SAMs and non-SAM entities for µCP and elastomers for embossing).

Other applications for SAMs are in the areas of bio/chemical and optical sensors, for use as drug-delivery vehicles and in the construction of electronic components [27.39, 47]. Bio/chemical sensors require the use of highly sensitive organic layers with tailored biological properties that can be incorporated into electronic, optical, or electrochemical devices. Self-assembled microscopic vesicles are being developed to ferry potentially lifesaving drugs to cancer patients. By getting organic, metal, and phosphonate molecules (complexes of phosphorous and oxygen atoms) to assemble themselves into conductive materials, these can be produced as self-made sandwiches for use as electronic components. The application of interest here is an application requiring hydrophobicity and/or low friction and wear.

An overview of molecularly thick layers of liquid lubricants and conventional solid lubricant can be found in various references [27.2, 4, 9, 10, 18, 19, 25]. In this chapter, we focus on SAMs for high hydrophobicity and/or, low adhesion, friction, and wear. SAMs are produced by various organic precursors. We first present a primer to organic chemistry followed by an overview on suitable substrates, spacer chains, and end groups in the molecular chains, an overview of tribological properties of SAMs, and some concluding remarks.

27.1 A Primer to Organic Chemistry

All organic compounds contain the carbon (C) atom. Carbon, in combination with hydrogen, oxygen, nitrogen, and sulfur results in a large number of organic compounds. The atomic number of carbon is six, and its electron structure is $1s^2\,2s^2\,2p^2$. Two stable isotopes of carbon, ^{12}C and ^{13}C, exist. With four electrons in its outer shell, carbon forms four covalent bonds with each bond resulting from two atoms sharing a pair of electrons. The number of electron pairs that two atoms share determines whether or not the bond is single or multiple. In a single bond, only one pair of electrons is shared by the atoms. Carbon can also form multiple bonds by sharing two or three pairs of electrons between the atoms. For example, the double bond formed by sharing two electron pairs is stronger than a single bond, and it is shorter than a single bond. An organic compound is classified as saturated if it contains only the single bond and as unsaturated if the molecules possess one or more multiple carbon-carbon bonds.

27.1.1 Electronegativity/Polarity

When two different kinds of atoms share a pair of electrons a bond is formed in which electrons are shared unequally, one atom assumes a partial positive charge and the other a negative charge with respect to each other. This difference in charge occurs because the two atoms exert unequal attraction for the pair of shared electrons. The attractive force that an atom of an element has for shared electrons in a molecule or polyatomic ion is known as its electronegativity. Elements differ in their electronegativities. A scale of relative electronegatives, in which the most electronegative element, fluorine, is assigned a value of 4.0, was developed by Linus Pauling. The relative electronegativities of the elements in the periodic table can be found in most undergraduate chemistry textbooks (e.g., *Hein* et al. [27.48]). Relative electronegativity of the nonmetals is high compared to that of metals. Relative electronegativity of selected elements of interest with high values is presented in Table 27.1.

The polarity of a bond is determined by the difference in electronegativity values of the atoms forming the bond. If the electronegativities are the same, the bond is nonpolar and the electrons are shared equally. In this type of bond, there is no separation of positive and negative charge between atoms. If the atoms have greatly different electronegativities, the bond is very polar. A dipole is a molecule that is electrically asymmetrical, causing it to be oppositely charged at two points. As an example, both hydrogen and chlorine need one electron to form stable electron configurations. They share a pair of

Element	Relative electronegativity
F	4.0
O	3.5
N	3.0
Cl	3.0
C	2.5
S	2.5
P	2.1
H	2.1

Table 27.1 Relative electronegativity of selected elements

electrons in hydrogen chloride, HCl. Chlorine is more electronegative and, therefore, has a greater attraction for the shared electrons than hydrogen. As a result, the pair of electrons is displaced toward the chlorine atom, giving it a partial negative charge and leaving the hydrogen atom with a partial positive charge, Fig. 27.2. However, the entire molecule, HCl, is electrically neutral. The hydrogen atom with a partial positive charge (exposed proton on one end) can be easily attracted to the negative charge of other molecules, and this is responsible for the polarity of the molecule. A partial charge is usually indicated by δ, and the electronic structure of HClis given as:

$$\overset{\delta+}{\mathrm{H}}:\overset{\delta-}{\underset{\cdot\cdot}{\ddot{\mathrm{Cl}}}}: \;.$$

Similar to the HCl molecule, HF is polar, and both behave as a small dipole. On the other hand, methane (CH_4), carbon tetrachloride (CCl_4), and carbon dioxide (CO_2) are nonpolar. In CH_4 and CCl_4, the four C−H and C−Cl polar bonds are identical, and because these bonds emanate from the center to the corners of a tetrahedron in the molecule, the effect of their polarities cancels out one another. CO_2 (O=C=O) is nonpolar, because carbon-oxygen dipoles cancel each other by acting in opposite directions. Symmetric molecules are generally nonpolar. Water (H−O−H) is a polar molecule. If the atoms in water were linear as in CO_2, two O−H dipoles would cancel each other, and the molecule would be nonpolar. However, water has a bent structure with an angle of 105° between the two bonds, which is responsible for the water being a polar molecule.



Fig. 27.2 Schematic representation of the formation of a polar HCl molecule

27.1.2 Classification and Structure of Organic Compounds

Tables 27.2–27.6 present selected organic compounds grouped into classes.

Hydrocarbons

Hydrocarbons are compounds that are composed entirely of carbon and hydrogen atoms bonded to each other by covalent bonds. Saturated hydrocarbons (alkanes) contain single bonds. Unsaturated hydrocarbons that contain a carbon-carbon double bond are called alkenes, and ones with a triple bond are called alkynes. Unsaturated hydrocarbons that contain an aromatic ring, e.g., benzene ring, are called aromatic hydrocarbons.

Saturated Hydrocarbons: Alkanes. The alkanes, also known as paraffins, are saturated hydrocarbons, straight- or branched-chain hydrocarbons with only single covalent bonds between the carbon atoms. The general molecular formula for alkanes is C_nH_{2n+2}, where n is the number of carbon atoms in the molecule. Each carbon atom is connected to four other atoms by four single covalent bonds. These bonds are separated by angles of 109.5° (the angle by lines drawn from the center of a regular tetrahedron to its corners). Alkane molecules contain only carbon-carbon and carbon-hydrogen bonds, which are symmetrically directed toward the corners of a tetrahedron. Therefore, alkane molecules are essentially nonpolar.

Common alkyl groups have the general formula C_nH_{2n+1} (one hydrogen atom less than the corresponding alkane). The missing H atom may be detached from any carbon in the alkane. The

Table 27.2 Names and formulas of selected hydrocarbons

Name	Formula
Saturated hydrocarbons	
Straight-chain alkanes	C_nH_{2n+2}
e.g., methane,	CH_4
ethane	C_2H_6 or CH_3CH_3
Alkyl groups	C_nH_{2n+1}
e.g., methyl,	$-CH_3$
ethyl	$-CH_2CH_3$
Unsaturated hydrocarbons	
Alkenes	$(CH_2)_n$
e.g., ethene,	C_2H_4 or $CH_2{=}CH_2$
propene	C_3H_6 or $CH_3CH{=}CH_2$
Alkynes	
e.g., acetylene	$HC{\equiv}CH$
Aromatic hydrocarbons	
e.g., benzene	

Table 27.3 Names and formulas of selected alcohols, ethers, phenols, and thiols

Name	Formula
Alcohols	$R-OH$
e.g., methanol,	CH_3OH
ethanol	CH_3CH_2OH
Ethers	$R-O-R'$
e.g., dimethyl ether,	CH_3-O-CH_3
diethyl ether	$CH_3CH_2-O-CH_2CH_3$
Phenols	C_6H_5OH or 
Thiols	$-SH$
e.g., methanethiol	CH_3SH

The letters R- and R′- represent an alkyl group. The R- groups in ethers can be the same or different and can be alkyl or aromatic (Ar) groups.

name of the group is formed from the name of the corresponding alkane by replacing -ane with -yl ending. Some examples are shown in Table 27.2.

Unsaturated Hydrocarbons. Unsaturated hydrocarbons consist of three families of compounds that contain fewer hydrogen atoms than the alkane with the corresponding number of carbon atoms and contain multiple bonds between carbon atoms. These include alkenes (with carbon-carbon double bonds), alkynes (with carbon-carbon triple bonds), and aromatic compounds (with benzene rings that are arranged in a six-member ring with one hydrogen atom bonded to each carbon atom and three carbon-carbon double bonds). Some examples are shown in Table 27.2.

Alcohols, Ethers, Phenols, and Thiols

Organic molecules with certain functional groups are synthesized for desirable properties. Alcohols, ethers, and phenols are derived from the structure of water by replacing the hydrogen atoms of water with alkyl groups (R) or aromatic (Ar) rings. For example, phenol is a class of compounds that have a hydroxy group attached to an aromatic ring (benzene ring). Organic compounds that contain the $-SH$ group are analogs of alcohols and are known as thiols. Some examples are shown in Table 27.3.

Aldehydes and Ketones

Both aldehydes and ketones contain the carbonyl group, $>C{=}O$, a carbon-oxygen double bond. Aldehydes have at least one hydrogen atom bonded to the carbonyl group, whereas ketones have only an alkyl or aromatic group bonded to the carbonyl group. The general formula for the saturated homologous series of aldehydes and ketones is $C_nH_{2n}O$. Some examples are shown in Table 27.4.

Carboxyl Acids and Esters

The functional group of the carboxylic acids is known as a carboxyl group, represented as $-COOH$. Carboxylic acids can be either aliphatic (RCOOH) or aromatic (ArCOOH). The carboxylic acids with even numbers of carbon atoms, n, ranging from 4 to about 20 are called fatty acids (e.g., $n = 10$, 12, 14, 16 and 18 are called capric acid, lauric acid, myristic acid, palmitic acid, and stearic acid, respectively).

Esters are alcohol derivates of carboxylic acids. Their general formula is $RCOOR'$, where R may be a hydrogen, alkyl group, or aromatic group, and R' may be an alkyl group or aromatic group but not a hydrogen. Esters are found in fats and oils. Some examples are shown in Table 27.5.

Table 27.4 Names and formulas of selected aldehydes and ketones

Name	Formula
Aldehydes	RCHO or  $R-\overset{O}{\overset{\|}{C}}-H$
	ArCHO or  $Ar-\overset{O}{\overset{\|}{C}}-H$
e.g., methanal or	HCHO
formaldehyde ethanal or acetaldehyde	CH_3CHO
Ketones	RCOR′ or  $R-\overset{O}{\overset{\|}{C}}-R'$
	RCOAr or  $R-\overset{O}{\overset{\|}{C}}-Ar$
	ArCOAr or  $Ar-\overset{O}{\overset{\|}{C}}-Ar$
e.g., butanone or methyl-ethyl ketone	$CH_3COCH_2CH_3$

The letters R and R′ represent alkyl groups, and Ar represents an aromatic group.

Table 27.5 Names and formulas of selected carboxylic acids and esters

Name	**Formula**
Carboxylic acid*	RCOOH or  $R-\overset{O}{\overset{\|}{C}}-OH$
	ArCOOH or  $Ar-\overset{O}{\overset{\|}{C}}-OH$
e.g., methanoic acid (formic acid),	$HCOOH$
ethanoic acid (acetic acid),	CH_3COOH
octadecanoic acid (stearic acid)	$CH_3(CH_2)_{16}COOH$
Esters**	RCOOR′ or  $\underbrace{R-\overset{O}{\overset{\|}{C}}}_{\text{acid}}-\underbrace{O-R'}_{\text{alcohol}}$
e.g., methyl propanoate	$CH_3CH_2COOCH_3$

* The letter R represents an alkyl group and Ar represents an aromatic group.

** The letter R represents hydrogen, an alkyl group, or an aromatic group and R′ represents an alkyl group or aromatic group

Table 27.6 Names and formulas of selected organic nitrogen compounds (amides and amines)

Name	**Formula**
Amides	$RCONH_2$ or  $R-\overset{O}{\overset{\|}{C}}-NH_2$
e.g., methanamide (formamide),	$HCONH_2$
ethanamide (acetamide)	CH_3CONH_2
Amines	RNH_2 or 
	R_2NH
	R_3N
e.g., methylamine,	CH_3NH_2
ethylamine	$CH_3CH_2NH_2$

The letter R represents an alkyl group or aromatic group.

Amides and Amines

Amides and amines are organic compounds containing nitrogen. Amides are nitrogen derivatives of carboxylic acids. The carbon atom of a carbonyl group is bonded directly to a nitrogen atom of a $-NH_2$, $-NHR$, or $-NR_2$ group. The characteristic structure of amide is $RCONH_2$.

An amine is a substituted ammonia molecule that has a general structure of RNH_2, R_2NH, or R_3N, where R is an alkyl or aromatic group. Some examples are shown in Table 27.6.

27.1.3 Polar and Nonpolar Groups

Table 27.7 summarizes polar and nonpolar groups commonly used in the construction of hydrophobic and hydrophilic molecules. Table 27.8 lists the relative polarity of selected polar groups [27.49]. Thiol, silane, carboxylic acid, and alcohol (hydroxyl) groups are the most commonly used polar anchor groups for their attachment to surfaces. Methyl and trifluoromethyl are commonly used end groups for hydrophobic film surfaces.

27.2 Self-Assembled Monolayers: Substrates, Head Groups, Spacer Chains, and End Groups

SAMs are formed as a result of spontaneous, self-organization of functionalized organic molecules onto the surfaces of appropriate substrates into stable, well-defined structures, Fig. 27.3. The final structure is close to or at thermodynamic equilibrium, and as a result, it tends to form spontaneously and rejects defects. SAMs consist of three building groups: a head group that binds strongly to a substrate, a surface terminal (tail) group that constitutes the outer surface of the film, and a spacer chain (backbone chain) that connects the head and surface terminal groups. The SAMs are named based on the surface terminal group followed by spacer chain and the head group (or type of compound formed at the surface). For a SAM to control hydrophobicity, adhesion, friction, and wear, it should be strongly adherent to the substrate, and the surface terminal group of the organic molecu-

Table 27.7 Some examples of polar (hydrophilic) and non-polar (hydrophobic) groups

Name	Formula
Polar	
Alcohol (hydroxyl)	$-OH$
Carboxyl acid	$-COOH$
Aldehyde	$-COH$
Ketone	 $R-\overset{\overset{\displaystyle O}{\|}}{C}-R$
Ester	$-COO-$
Carbonyl	
Ether	$R-O-R$
Amine	$-NH_2$
Amide	 $-\overset{\overset{\displaystyle O}{\|}}{C}-NH_2$
Phenol	
Thiol	$-SH$
Trichlorosilane	$SiCl_3$
Nonpolar	
Methyl	$-CH_3$
Trifluoromethyl	$-CF_3$
Aryl (benzene ring)	

The letter R represents an alkyl group.

Table 27.8 Organic groups listed in the increasing order of polarity

Alkanes
Alkenes
Aromatic hydrocarbons
Ethers
Trichlorosilanes
Aldehydes, ketones, esters, carbonyls
Thiols
Amines
Alcohols, phenols
Amides
Carboxylic acids


Surface terminal group
Spacer chain
Interchain
van der Waals
and electrostatic
interactions
Chemical bond
at the surface
Surface-active
head group
Substrate
A single chain
α
Substrate
Self-assembly molecules

Fig. 27.3 Schematic of a self-assembled monolayer on a surface and the associated forces

lar chain should be nonpolar. For strong attachment of the organic molecules to the substrate, the head group of the molecular chain should contain a polar end group resulting in the exothermic process (energies on the order of tens of kcal/mol), i. e., it results in an apparent pinning of the head group to a specific site on the surface through a chemical bond. Furthermore, molecular structure and any crosslinking would have a significant effect on their friction and wear performance. The substrate surface should have a high surface energy (hydropolic), so that there will be a strong tendency for molecules to adsorb on the surface. The surface should be highly functional with polar groups and dangling bonds (generally unpaired electrons), so that they can react with organic molecules and provide a strong bond. Because of the exothermic head group–substrate interactions, molecules try to occupy every available binding site on the surface, and during this process they generally push together molecules that have already adsorbed. The process results in the formation of crystalline molecular assemblies. The interactions between molecular chains are van der Waals or electrostatic-type with energies on the order of a few (< 10) kcal/mol, exothermic. The molecular chains in SAMs are not perpendicular to the surface; the tilt angle depends on the anchor group, as well as on the substrate and the spacer group. For example, the tilt angle for alkanethiolate on Au is typically about 30–35 ° angle with respect to substrate normal.

SAMs are usually produced by immersing a substrate in a solution containing precursor (ligand) that is reactive to the substrate surface, or by exposing the substrate to a vapor of the reactive chemical species [27.39]. Table 27.9 lists selected systems that have been used for formation of SAMs [27.43]. The spacer chain of SAM is mostly an alkyl chain ($-C_nH_{2n+1}$), or made of a derivatized alkyl group. By attaching different terminal groups at the surface, the film surface can be made to attract or repel water. The commonly used surface terminal group of a hydrophobic film with low surface energy, in the case of a single alkyl chain, is a nonpolar methyl ($-CH_3$) or trifluoromethyl ($-CF_3$) group. For a hydrophilic film, the commonly used surface terminal groups are alcohol ($-OH$) or carboxylic acid ($-COOH$) groups. Surface active head groups most commonly used are thiol ($-SH$), silane (e.g., trichlorosilane or $-SiCl_3$), and carboxyl ($-COOH$) groups. The substrates most commonly used are gold, silver, platinum, copper, hydroxylated (activated) surfaces of SiO_2 on Si, Al_2O_3 on Al, glass, and hydrogen-terminated single-crystal silicon (H−Si). Hydroxylation of oxide surfaces is important to make them hydrophilic. Thermally grown silica can be activated through a sulfochromic treatment. The sample is dipped in a solution consisting of 100 mL of concentrated H_2SO_4, 5 mL of water, and 2 g of potassium



Fig. 27.4 Schematic showing the hydroxylation process occurring on a silica surface through a sulfochromic treatment

Table 27.9 Selected substrates and precursors that have commonly been used for formation of SAMs

Substrate	Precursor	Binding with substrate
Au	RSH (thiol)	RS−Au
Au	ArSH (thiol)	ArS−Au
Au	RSSR′ (disulfide)	RS−Au
Au	RSR′ (sulfide)	
Si/SiO_2, glass	$RSiCl_3$ (trichlorosilane)	Si−O−Si (Siloxane)
Si/Si−H	RCOOH (carboxyl)	R−Si
Metal oxides (e.g., Al_2O_3, SnO_2, TiO_2)	RCOOH (carboxyl)	RCOO− . . . MO_n

R represents alkane (C_nH_{2n+2}) and Ar represents aromatic hydrocarbon. It consists of various surface active head groups and mostly with methyl terminal group bichromate for 3–15 min [27.34]. The sample is then rinsed with flowing pure water. This results in a surface with silanol groups (−Si−OH) that is hydrophilic, Fig. 27.4. Bulk silicon, polysilicon film, or SiO_2 film surfaces can also be treated to produce activated hydrophilic silica surface by immersion in about three parts H_2SO_4 and one part H_2O_2 at temperatures ranging from ambient to 80 °C. For organic molecules to pack together and provide a better ordering, a substrate for given molecules should be selected such that the cross-sectional diameter of the spacer chains of the molecule is equal to or smaller than the distance between the anchor groups attached to the substrate. As an example, epitaxial Au film on glass, mica, or single-crystal silicon, produced by e-beam evaporation, is commonly used because it can be deposited on smooth surfaces as a film that is atomically flat and defect free. For the case of alkanethiolate film, the advantage of Au substrate over SiO_2 substrate is that it results in better ordering, because the cross-sectional diameter of the alkane molecule is slightly smaller than the distance between sulfur atoms attached to the Au substrate (∼ 0.53 nm). The thickness of the film can be controlled by varying the length of the hydrocarbon chain, and the surface properties of the film can be modified by the terminal group.



Fig. 27.5 Schematics of a methyl-terminated, n-alkylsiloxane monolayer on Si/SiO_2

Some of the SAMs have been widely reported. SAMs of long-chain fatty acids, $C_nH_{2n+1}COOH$ or $(CH_3)(CH_2)_nCOOH$ ($n = 10, 12, 14$ or 16), on glass or alumina have been used in films studies since the 1950s [27.16, 20]. Probably the most studied SAMs to date are n-alkanethiolate monolayers $CH_3(CH_2)_nS-$, prepared from adsorption of alkanethiol $-(CH_2)_nSH$ solution onto an Au film (n-alkyl and n-alkane are used interchangeably) [27.35–37, 43] and n-alkylsiloxane monolayers produced by adsorption of n-alkyltrichlorosilane $-(CH_2)_nSiCl_3$ solution onto hydroxylated Si/SiO_2 substrate [27.50] with siloxane (Si−O−Si) binding, Fig. 27.5. *Jung* et al. [27.51] have produced organosulfur monolayers – decanethiol $(CH_3)(CH_2)_9SH$, and didecyl $CH_3(CH_2)_9-S-(CH_2)_9CH_3$ on Au films. *Geyer* et al. [27.52], *Bhushan* and *Liu* [27.35], *Liu* et al. [27.36], and *Liu* and Bhushan [27.37] have produced monolayers of 1,1′-biphenyl-4-thiol (BPT) on Au surface, where the spacer chain of the film consists of two phenyl rings with a hydrogen end group. *Bhushan* and *Liu* [27.35] and *Liu* and *Bhushan* [27.37] have also reported monolayers of 4,4′-dihydroxybiphenyl on Si surface.

27.3 Tribological Properties of SAMs

The basis for molecular design and tailoring of SAMs must start from a complete knowledge of the interrelationships between the molecular structure and tribological properties of SAMs, as well as a deep understanding of the adhesion, friction, and wear mechanisms of SAMs at the molecular level. Friction and wear properties of SAMs have been studied on macro- and nanoscales. Macroscale tests are conducted using a so-called pin-on-disk tribotester apparatus in which a ball specimen slides against a lubricated flat specimen [27.9, 10]. Nanoscale tests are conducted using an atomic force/friction force microscope (AFM/FFM) [27.4, 9, 10]. In the AFM/FFM experiments, a sharp tip of radius ranging from about 5–50 nm slides against a SAM specimen. A Si_3N_4 tip is commonly used for friction studies and a natural diamond tip is commonly used for scratch, wear, and indentation studies.

In early studies, the effect of chain length of the carbon atoms of fatty acid monolayers on the coefficient of friction and wear on the macroscale was studied by *Bowden* and *Tabor* [27.16] and *Zisman* [27.20]. *Zisman* reported that for the monolayers deposited on a glass surface sliding against a stainless steel surface, there is a steady decrease in friction with increasing chain length. At a significantly long chain length, the coefficient of friction reaches a lower limit, Fig. 27.6. He further reported that monolayers having a chain length below 12 carbon atoms behave as liquids (poor durability), those with chain length of 12–15 carbon atoms behave like a plastic solid (medium durability), whereas those with chain lengths above 15 carbon atoms behave like a crystalline solid (high durability). Investigations by *Ruhe* et al. [27.53] indicated that the lifetime of the alkylsilane monolayer coating on a silicon surface increases greatly with an increase in the chain length of the alkyl substituent. *DePalma* and *Tillman* [27.54] showed that a monolayer of n-octadecyltrichlorosilane (n-$C_{18}H_{37}SiCl_3$, OTS) is an effective lubricant on silicon, followed by n-undecyltrichlorosilane (n-$C_{11}H_{23}SiCl_3$, UTS) and (tridecafluoro-1,1,2,2-tetrahydrooct-1-yl) trichlorosilane (n-$C_6F_{13}CH_2CH_2SiCl_3$, FTS). *Ando* et al. [27.55] suggested that γ-(N,N-dioctadecylsuccinylamino) propyltriethoxysilane monolayer is a candidate lubricant. The film exhibited a low coefficient of kinetic friction of 0.1, without stick-slip. However, tests in all these investigations were carried out using a pin-on-disk tribotester under relatively large normal loads up to 0.15 N. Thus, the relevance of these tests is questionable for micro/nanodevice application.

With the development of AFM techniques, researchers have successfully characterized the nanotribological properties of self-assembled monolayers [27.1, 4, 34–38]. Studies by *Bhushan* et al. [27.34] showed that C_{18} alkylsiloxane films exhibit the lowest coefficient of friction and can withstand a much higher normal load during sliding compared to LB films, soft Au films, and hard SiO_2 coatings.

McDermott et al. [27.56] studied the effect of length of alkyl chains on the frictional properties of methyl-terminated n-alkylthiolate $CH_3(CH_2)_nS-$ films chemisorbed on Au(111) using an AFM. They reported that the longer chain monolayers exhibit a markedly lower friction and a reduced propensity to wear than shorter chain monolayers, Fig. 27.7. These results are in good agreement with the macroscale results by *Zisman* [27.20]. They also conducted infrared reflection spectroscopy to measure the bandwidth of the methylene stretching mode (ν_a (CH_2)), which exhibits a qualitative correlation with the packing density of the chains. They found that the chain structures of monolayers prepared with longer chain lengths are more ordered and more densely packed in comparison to those of monolayers prepared with shorter chain lengths. They further reported that the ability of the longer chain monolayers to retain molecular-scale order during shear leads to a lower observed friction. Monolayers with a chain length of more than 12 carbon atoms, preferably 18 or more, are desirable for tribological applications. (Incidentally, the monolayer with 18 carbon atoms, octadecanethiol films, are commonly studied.)



Fig. 27.6 Effect of chain length (or molecular weight) on coefficient of macroscale friction of stainless steel sliding on glass lubricated with a monolayer of fatty acid and contact angle of methyl iodide on condensed monolayers of fatty acid on glass [27.20]



Fig. 27.7 Effect of chain length of methyl-terminated, n-alkanethiolate over Au film $AuS(CH_2)_nCH_3$ on the coefficient of microscale friction and peak bandwidth at half maximum ($\Delta\nu_{1/2}$) for the bandwidth of the methylene stretching mode [ν_a (CH_2)] [27.56]

Xiao et al. [27.57] and *Lio* et al. [27.58] also studied the effect of the length of the alkyl chains on the frictional properties of n-alkanethiolate films on gold and n-alkylsilane films on mica. Friction was found to be particularly high with short chains of less than eight carbon atoms. Thiols and silanes exhibit a similar friction force for the same n when $n > 11$; while for $n < 11$, silanes exhibit higher friction, larger than that for thiols by a factor of about 3 for $n = 6$. The increase in friction was attributed to the large number of dissipative modes in the less ordered chains that occurs when going from a thiol to a silane anchor or when decreasing n. Longer chains ($n > 11$), stabilized by van der Waals attraction, form more compact and rigid layers and act as better lubricants. *Schonherr* and *Vancso* [27.59] also correlated the magnitude of friction with the order of the alkane chains. The disorder of the short-chain hydrocarbon disulfides SAMs was found to result in a significant increase in the magnitude of friction.

Fluorinated carbon (fluorocarbon) molecules are commonly used for lubrication [27.2, 9, 10]. *Kim* et al. [27.60, 61] studied the influence of methyl-, isopropyl-, and trifluoromethyl-terminated alkanethiols on the friction properties of SAMs. They reported a factor of three increases in the friction in going from the methyl-terminated SAM to the trifluoromethyl-terminated SAM. They suggested that fluorinated monolayers exhibit higher frictional properties due to tighter packing at the interface, which arises from the larger van der Waals radii of the fluorine atoms. Subsequent steric and rotational factors between adjacent terminal groups give rise to long-range multi-molecular interactions in the plane of the $-CF_3$ groups. When these energetic barriers are overcome in the film structure, more energy is imparted to the film during sliding and results in higher friction for the fluorinated films.

Tsukruk et al. [27.62] and *Lee* et al. [27.63] studied the nanotribological properties of C_{60}-terminated alkyltrichlorosilanes and alkanedisulfides self-assembled monolayers. Both of their studies observed that the frictional forces of the C_{60}-terminated films are higher than those on normal methyl-terminated SAMs. However, *Tsukruk* et al. [27.62] reported that the C_{60}-terminated alkyltrichlorosilanes SAMs exhibit high wear resistance. *Tsukruk* and *Bliznyuk* [27.64] also studied the adhesion and friction between a Si sample and Si_3N_4 tip, in which both surfaces were modified by $-CH_3$, $-NH_2$, and $-SO_3H$ terminated silane-based SAMs. Various polymer molecules for the backbone were used. They reported that a very broad maximum adhesive force in the pH range of from 4 to 8 with a minimum adhesion at $pH > 9$ and $pH < 3$ were observed for all of the studied mating surfaces. This observation can be understood by considering a balance of electrostatic and van der Waals interaction between composite surfaces with multiple isoelectric points. The friction coefficient of NH_2/NH_2 and SO_3H/SO_3H mating SAMs is very high in aqueous solutions. Cappings of NH_2 modified surfaces (3-aminopropyltriethoxysilane) with rigid and soft polymer layers resulted in a significant reduction in adhesion to a level lower than that of untreated surfaces [27.65]. *Fujihira* et al. [27.66] studied the influence of surface terminal groups of SAMs and functional tip on adhesive force. It was found that the adhesive forces measured in air increase in the order of CH_3/CH_3, $CH_3/COOH$, and $COOH/COOH$.

Bhushan and *Liu* [27.35], *Liu* et al. [27.36], and *Liu* and *Bhushan* [27.37, 38] have studied the influence of spacer chains, surface terminal groups, and head groups on adhesion, friction, and wear properties of SAMs. They have explained the friction mechanisms using a molecular spring model in which local stiffness and the intermolecular forces govern the friction properties. They studied the influence of relative humidity, temperature, and velocity on adhesion and friction. They also investigated the wear mechanisms of SAMs by a continuous microscratch AFM technique.

To date, the nanotribological properties of alkyltrichlorosilanes, alkanethiols, and biphenyl thiol SAMs have been widely studied. In this chapter, we review, in some detail, the nanotribological properties of five kinds of SAMs, having alkyl and biphenyl spacer chains with different surface terminal groups ($-CH_3$, $-COOH$, and $-OH$), and head groups ($-SH$ and $-OH$), which have been investigated by AFM at various operating conditions, Fig. 27.8 [27.35–38]. Hexadecane thiol (HDT), 1,1′-biphenyl-4-thiol (BPT) and crosslinked BPT (BPTC), and 16-mercaptohexadecanoic acid thiol (MHA) were deposited on Au(111) substrates. A 4,4′-dihydroxybiphenyl (DHBp) film was deposited on a hydrogenated Si(111) substrate. Figure 27.8 shows that HDT and MHA have the same head groups and spacers, but different surface terminal groups; their surface terminals are $-CH_3$ and $-COOH$, respectively. BPT and DHBp have the same spacers, but the head and surface terminal groups of DHBp are $-OH$ instead of $-SH$ and $-CH$ in BPT. Crosslinked BPTC was produced by irradiation of BPT monolayers with low energy electrons.



Fig. 27.8 Schematics of the structures of HDT, BPT, MHA, DHBp, and BPTC SAMs [27.35]

27.3.1 Surface Roughness and Friction Images of SAMs Films

Surface height and friction force images of SAMs were recorded simultaneously on an area of 1 μm × 1 μm by an AFM, Fig. 27.9 [27.35]. The topography of Au(111) film and SAMs deposited on Au(111) substrates appear to be granular. A good correlation between the surface height and the corresponding friction force images was observed. It was noticed that the friction force changed with surface height in the same direction (upwards and downwards) in both trace and retrace friction profiles of the friction loop. Thus, the change in friction force corresponds to transitions in surface slope [27.4, 35, 36, 67]. Figure 27.9 also indicates that the topography and friction images of Si(111) and DHBp/Si(111) are very similar; they exhibit featureless surfaces and their friction force images do not show any abrupt changes.

For further analysis presented later in this chapter, the roughness, thickness, tilt angles, and spacer chain lengths of Si(111), Au(111), and various SAMs are listed in Table 27.10 [27.35]. The roughness values of BPT and MHA are very close to that of Au(111). But the roughness of BPTC is lower than that of Au(111) and BPT; this is caused by electron irradiation. Table 27.10 indicates that the roughness values of HDT and DHBp are much higher than their substrate roughness of Au(111) and Si(111), respectively. This is caused by local aggregation of organic compounds on the substrates during SAMs deposition. Table 27.10 also indicates that the thickness of biphenyl thiol SAMs is generally thinner than the alkylthiol, which is responsible for shorter spacer chain in biphenyl thiol.

27.3.2 Adhesion, Friction, and Work of Adhesion

The average values and standard deviation of the adhesive force and coefficients of friction measured by contact mode AFM are presented in Fig. 27.10 [27.35]. Based on the data, the adhesive force and coefficient of friction of SAMs are less than their corresponding substrates. Among various films, HDT exhibits the lowest values. The ranking of adhesive forces F_a is in the following order: $F_{\text{a-Au}} > F_{\text{a-Si}} > F_{\text{a-DHBp}} \approx F_{\text{a-MHA}} > F_{\text{a-BPT}} > F_{\text{a-BPTC}} > F_{\text{a-HDT}}$. And the ranking of the coefficients of friction μ is in the following order: $\mu_{\text{Si}} > \mu_{\text{Au}} > \mu_{\text{DHBp}} > \mu_{\text{BPTC}} > \mu_{\text{BPT}} \approx \mu_{\text{MHA}} > \mu_{\text{HDT}}$. The ranking of various SAMs for adhesive force and coefficient of friction is similar. It suggests that alkylthiol and biphenyl SAMs can be used as effective molecular lubricants for micro/nanodevices fabricated from silicon.

In micro/nano scale contact, liquid capillary condensation is one of the factors that influence adhesion and friction. In the case of a sphere in contact with a flat surface, the attractive Laplace force caused by water


Surface height (0–1 nm)
Friction force (0–0.1 V)
Surface height (0–1 nm)
Friction force (0–0.1 V)
0
1 µm
0
1 µm
Au(111)
0
1 µm
0
1 µm
HDT/Au(111)
0
1 µm
0
1 µm
BPT/Au(111)
0
1 µm
0
1 µm
BPT/Au(111)
0
1 µm
0
1 µm
MHA/Au(111)
0
1 µm
0
1 µm
Si(111)
0
1 µm
0
1 µm
DHBp/Si(111)

Fig. 27.9 AFM gray-scale surface height and friction force images of Au(111), Si(111), and various SAMs [27.35]

Table 27.10 The R_a roughness, thickness, tilt angles, and spacer chain lengths of SAMs

Samples	R_a roughness[1] (nm)	Thickness[2] (nm)	Tilt angle[2] (deg.)	Spacer length[3] (nm)
Si(111)	0.07			
Au(111)	0.37			
HDT	0.92	1.89	30	1.91
BPT	0.36	1.25	15	0.89
BPTC	0.14	1.14	25	0.89
MHA	0.37	2.01	30	1.91
DHBp	0.25	1.13	–	0.89

[1] Measured by an AFM with 1 µm × 1 µm scan size using a Si_3N_4 tip under 3.3 nN normal load.

[2] The thickness and tilt angles of BPT, BPTC, and DHBp are reported by *Geyer* et al. [27.52]. The thickness and tilt angles of HDT and MHA are reported by *Ulman* [27.40].

[3] The spacer chain lengths of alkylthiols were calculated by the method reported by *Miura* et al. [27.68]. The spacer chain lengths of biphenyl thiols were calculated by the data reported by *Ratajczak-Sitarz* et al. [27.69].



Fig. 27.10 Adhesive forces and coefficients of friction of Au(111), Si(111), and various SAMs [27.35]

capillary is:

$$F_L = 2\pi R\gamma_{la}(\cos\theta_1 + \cos\theta_2)\ , \tag{27.1}$$

where R is the radius of the sphere, γ_{la} is the surface tension of the liquid against air, θ_1 and θ_2 are the contact angles between liquid and flat and spherical surfaces, respectively [27.9, 10]. In an AFM adhesive study, the tip-flat sample contact is just like a sphere in contact with a flat surface and the liquid is water. Since a single tip was used in the adhesion measurements, $\cos\theta_2$ can be treated as a constant. Therefore,

$$\begin{aligned} F_L &= 2\pi R\gamma_{la}(1+\cos\theta_1) - 2\pi R\gamma_{la}(1-\cos\theta_2) \\ &= 2\pi R\gamma_{la}(1+\cos\theta_1) - C\ , \end{aligned} \tag{27.2}$$

where C is a constant.

Based on the following Young-Dupre equation, work of adhesion W_a (the work required to pull apart the unit area of the solid-liquid interface) can be written as [27.70]

$$W_a = \gamma_{la}(1+\cos\theta_1)\ . \tag{27.3}$$

It indicates that W_a is determined by the contact angle of SAMs, i. e., is influenced by the surface chemistry properties (polarization and hydrophobicity) of SAMs. By substituting (27.3) into (27.2), F_L can be expressed as

$$F_L = 2\pi R W_a - C\ . \tag{27.4}$$

When the influence on the adhesive force of other factors, such as van der Waals force, is very small, then adhesive force $F_a \approx F_L$. Thus the adhesive force F_a should be proportional to work of adhesion W_a.

Contact angle is a measure of the wettability of a solid by a liquid and determines the W_a value. The value of the contact angle changes with time. If the droplet expands, the contact angle is referred to as the advancing contact angle. The contact angles of distilled water on Si(111), Au(111), and SAMs were measured using a contact angle goniometer [27.35]. After dropping water on the sample surfaces, the dynamic advancing contact angle (DACA) was measured with a frequency of 60 s for spontaneous spreading for at least 420 s. The DACA as a function of time data is given in Fig. 27.11a. It indicates that there is a linear relationship between DACA and rest time. As stated by many authors, the static advancing contact angle (SACA) (at $t = 0$) should be used for surface characterization [27.71–73]. This SACA can be obtained by simple extrapolation of the data in Fig. 27.11a to $t = 0$. The SACA of Si(111), Au(111), and SAMs is summarized in Fig. 27.11b. For water, $\gamma_{\text{la}} = 72.6\,\text{mJ/m}^2$ at 22 °C, and by using (27.3), the W_a data are obtained and presented in Fig. 27.11c. The W_a can be ranked in the following order: $W_{\text{a-Si}}(117.0) > W_{\text{a-DHBp}}(98.8) \approx W_{\text{a-MHA}}(101.8) \approx W_{\text{a-Au}}(97.1) > W_{\text{a-BPT}}(86.8) > W_{\text{a-BPTC}}(82.1) > W_{\text{a-HDT}}(61.4)$. Excluding $W_{\text{a-Au}}$, this order exactly matches the order of adhesion force in Fig. 27.10. The relationship between F_a and W_a is summarized in Fig. 27.12 [27.35]. It indicates that the adhesive force F_a (nN) increases with work of adhesion W_a (mJ/m^2) by the following linear relationship:

$$F_\text{a} = 0.57 W_\text{a} - 22\,. \tag{27.5}$$

These experimental results agree well with the modeling prediction presented earlier in (27.4). It proves that on the nanoscale at ambient condition the adhesive force of SAMs is mainly influenced by the water capillary force. Comparing the results of Figure 27.12 with Figure 27.8, it is found that MHA and DHBp, which have polar surface terminal groups (−COOH and −OH), lead to larger W_a and eventually larger adhesive forces. Though both HDT and BPT do not have polar surface groups, the surface terminal of HDT has a symmetrical structure, which causes a smaller electrostatic attractive



Fig. 27.11 **(a)** Variation of dynamic advancing contact angle (DACA) with time, **(b)** the static advancing contact angle (SACA), and **(c)** work of adhesion of Au(111), Si(111), and various SAMs. All of the points in this figure represent the mean value of six measurements. The uncertainty associated with the average contact angle is within ±2°. The insert schematic in **(a)** shows the contact angle of the water droplet on the sample surface [27.35]



Fig. 27.12 Relationship between the adhesive forces and work of adhesion of different specimen [27.35]

force and yields smaller adhesive force than BPT. It is believed that the easy attachment of Au on the tip should be one of the reasons that cause the large adhesive force, which do not fit the linear relationship described by (27.5).

27.3.3 Stiffness, Molecular Spring Model, and Micropatterned SAMs

Next, the friction mechanisms of SAMs are examined. Monte Carlo simulation of the mechanical relaxation of $CH_3(CH_2)_{15}SH$ self-assembled monolayer performed by *Siepman* and *McDonald* [27.74] indicated that SAMs compress and respond nearly elastically to microindentation of an AFM tip under a critical normal load.



Fig. 27.13 **(a)** Slopes of cantilever deflection versus piezo displacement measured by force distance calibration mode AFM, and **(b)** normal load versus displacement curves of Au(111), Si(111), and various SAMs

Compression can lead to major changes in the mean molecular tilt (i. e., orientation), but the original structure is recovered as the normal load is removed.

To study the difference in the stiffness of various films, the stiffness properties were measured by an AFM in force-distance calibration mode, as well as in force modulation mode [27.4, 37]. Figure 27.13a shows the slope of cantilever deflection versus piezo movement obtained in the force-distance calibration mode. For an infinite hard material, since the surface can not be compressed, the cantilever deflection should equal the piezo movement distance, which means the slope of the cantilever deflection versus piezo movement equals 1. For a soft material, the surface can be compressed, causing a reduced cantilever deflection, and the slopes are smaller than 1. In this study the cantilever has been initially calibrated to slope $= 1$ against a clean, rigid Si(111) surface. Figure 27.13a indicates that the slopes of all of the SAMs are less than 1, which suggests that all of the SAMs can be compressed by a Si_3N_4 tip during the loading process. The slope value of SAMs can be ranked in the following order: $S_{\mathrm{DHBp}} > S_{\mathrm{BPT}} > S_{\mathrm{MHA}} \approx S_{\mathrm{HDT}}$. This order reflects the influence of molecular structure on the compression properties of SAMs. Since BPT and DHBp have rigid benzene structure, they are more difficult to compress than HDT and MHA. Figure 27.13b shows the variation of the displacement with normal load during indentation mode. It also clearly indicates that SAMs can be compressed. At a given normal load, long carbon chain structure SAMs such as HDT and MHA are easy to compress compared to rigid benzene-ring structure SAMs such as BPT and DHBp. *Garcia-Parajo* et al. [27.75] have also reported the compression and relaxation of octadecyltrichlorosilane (OTS) film in their loading and unloading tests.

In order to explain the frictional difference of SAMs, based on the friction and stiffness measurements by AFM and the Monte Carlo simulation, a molecular spring model is presented in Fig. 27.14. It is believed that the self-assembled molecules on a substrate are just like assembled molecular springs anchored to the substrates [27.35]. A Si_3N_4 tip sliding on the surface of SAMs is like a tip sliding on the top of "molecular springs or brush". The molecular spring assembly has compliant features and can experience compression and orientation under normal load. The orientation of the "molecular springs or brush" reduces the shearing force at the interface, which, in turn, reduces the friction force. The possibility of orientation is determined by the spring constant of a single molecule (local stiffness), as well as the interaction between the neighboring



Fig. 27.14 Molecular spring model of SAMs. In this figure, $\alpha_1 < \alpha_2$, which is caused by the orientation under the normal load applied by an AFM tip. The orientation of the molecular springs reduces the shearing force at the interface, which, in turn, reduces the friction force. The molecular spring constant, as well as the inter-molecular forces can determine the magnitude of the coefficients of friction of SAMs. In this figure, the size of the tip and molecular springs are not drawn exactly to scale [27.35]

molecules, which can be reflected by packing density or packing energy. It should be noted that the orientation can lead to conformational defects along the molecular chains, which lead to energy dissipation. In the study of BPT by AFM, it was found that after the first several scans, the friction force is significantly reduced, but the surface height does not show any apparent change. This suggests that the molecular orientation can be facilitated by initial sliding and is reversible [27.38].

Based on the stiffness measurement results presented in Fig. 27.13 and the view of molecular structures in Fig. 27.14, biphenyl is a more rigid structure due to the contribution of two rigid benzene rings. Therefore, the spring constant of BPT is larger than that of HDT. The hydrogen (H^+) in a biphenyl chain has an electrostatic attractive force with the π electrons in the neighboring benzene ring. Thus, the intermolecular force between biphenyl chains is stronger than that for alkyl chains. The larger spring constant of BPT and stronger intermolecular force require a larger external force to allow it to orient, thus causing higher coefficient of friction. For MHA and DHBp, their basic chain structures are very close to HDT and BPT, respectively. But their surface terminals are different. The polar −COOH and −OH external functional groups in MHA and DHBp increase the adhesive force, thus leading to higher friction force than HDT and BPT, respectively. The crosslinking of BPT leads to a larger packing energy for BPTC. Therefore, it requires a larger external force to allow BPTC orientation, i. e., the coefficient of BPTC is higher than BPT.



Fig. 27.15 **(a)** AFM gray-scale surface height and stiffness images, and **(b)** AFM gray-scale surface height and friction force images of micropatterned BDCS [27.37]

An elegant way to demonstrate the influence of molecular stiffness on friction is to investigate SAMs with different structures on the same wafer. For this purpose, a micropatterned SAM was prepared. First, the biphenyldimethylchlorosilane (BDCS) was deposited on silicon by the typical self-assembly method [27.37]. Then the film was partially crosslinked using mask technique by low energy electron irradiation. Finally, the micropatterned BDCS films were realized that had the as-deposited and crosslinked coatings on the same wafer. The local stiffness properties of these micropatterned samples were investigated by force modulation AFM technique [27.76]. The variation in the deflection amplitude provides a measure of the relative local stiffness of the surface. Surface height, stiffness, and friction images of the micropatterned biphenyldimethylchlorosilane (BDCS) specimen are obtained and presented in Fig. 27.15 [27.37]. The circular areas correspond to the as-deposited film, and the remaining area to the crosslinked film. Figure 27.15a indicates that crosslinking caused by the low energy electron irradiation leads to about a 0.5 nm decrease of the surface height of BDCS films. The corresponding stiffness images indicate that the crosslinked area has a higher stiffness than the as-deposited area. Figure 27.15b indicates that the as-deposited area (higher surface height area) has lower friction force. Obviously, the data of the micropatterned sample prove that the local stiffness of SAMs has an influence on their friction performance. Higher stiffness leads to larger friction force. These results provide a strong proof of the suggested molecular spring model.

In summary, it has been found that SAMs exhibit compliance and can experience compression and orientation under normal load. The orientation of SAMs reduces the shear stress at the interface; therefore SAMs can serve as good lubricants. The molecular spring constant (local stiffness), as well as the intermolecular forces can influence the magnitude of the coefficients of friction of SAMs.

27.3.4 Influence of Humidity, Temperature, and Velocity on Adhesion and Friction

The influence of relative humidity on adhesion and friction was studied in an environmentally controlled chamber at 22 °C [27.35]. The results are presented in Fig. 27.16. It shows that for Si(111), Au(111), DHBp and MHA, the adhesive and friction forces increase with relative humidity. For BPT and BPTC, the adhesive force only slightly increases with relative humidity when the relative humidity is higher than 40%, but it is very interesting that their friction decreases in the same range. For HDT, in the testing range, the adhesive and friction force are not sensitive to changes in relative humidity.

It has already been shown that the adhesive force is linearly related to the W_a value of the surfaces in Fig. 27.12. DHBp and MHA have polar surface terminals and larger W_a value. This must therefore lead to the larger adhesive forces in higher relative humidity, which, in turn, increase the friction force. In comparison, HDT has a nonpolar $-CH_3$ surface terminal and a very small W_a value. Thus, the adhesive force and friction force of HDT are not sensitive to the change of humidity. The W_a values of BPT and BPTC are between Si(111) and HDT (see Fig. 27.11c); therefore their adhesive forces show a slight increase when RH > 40%. The fact that BPT and BPTC show lower friction force when RH > 40% suggests that a thin adsorbed water layer can act as a lubricant [27.35, 37]. The reason why the adsorbed water layer acts as a lubricant may be related to the thickness of the absorbed layer.



Fig. 27.16a,b The influence of relative humidity on the **(a)** adhesive force and **(b)** friction forces at 200 nN of Si(111), Au(111), and various SAMs [27.35]

Results of the influence of temperature on adhesion and friction of Si(111) and two selected typical SAMs – HDT and BPT – are presented in Fig. 27.17 [27.37]. The friction data are presented at various normal loads. In all cases, the normal load does not change the general trends. The data show that for Si(111), once the temperature is higher than 75 °C, the adhesive force decreases with temperature. The friction force of silicon decreases slightly with temperature from room temperature to 100 °C; once the temperature is higher than 100 °C, the friction force shows an apparent decrease. It is believed that desorption of the adsorbed water layer on Si(111) and the reduction of surface tension of water at high temperature are responsible for the decrease in adhesion and friction [27.77]. For HDT, in the testing range (22 °C–125 °C) its adhesion and friction show very slight change with temperature. For BPT, its adhesive force initially increases with temperature from 22 °C–75 °C, but when the temperature is higher than



Fig. 27.17a,b The influence of temperature on **(a)** adhesive forces and **(b)** friction forces of Si(111), HDT, and BPT [27.37]

Compound type	Molecular formula	Melting points (°C) [27.77]
Linear carbon chain	$CH_3(CH_2)_{14}CH_2OH$	50
Benzene ring	$3\text{-HO}-C_6H_4C_6H_5$	78
	$2\text{-HO}-C_6H_4C_6H_5$	58–60

Table 27.11 Melting point of typical organic compounds similar to HDT and BPT SAMs



Fig. 27.18 The influence of velocity on friction forces of Si(111) and SAMs [27.37]

75 °C, the adhesive force remains steady within the experimental error. The variations in the friction force with temperature for BPT exhibit the maximum value, and the corresponding critical temperature is related to the normal load. The reason why BPT shows maximum friction force is believed to be caused by the melting of film at high temperature. When the temperature is below the melting point, an increase of temperature leads to the softening of SAM, which increases the real contact area and, consequently, the friction force. Once the temperature is higher than the melting point, the lubrication regime is changed from boundary lubrication in a solid

SAM to liquid lubrication in the melted SAM, and therefore the friction force is decreased. To date, the melting points of HDT and BPT SAMs are unknown. But from the literature [27.77], the melting points of typical linear carbon chain and benzene ring compounds are presented in Table 27.11. It is found that the reported melting of the benzene ring compounds is somewhat close to the frictional transition temperature of BPT measured by AFM. For HDT, their very compliant carbon chain can serve as an excellent lubricant even in solid state (i. e., at or near room temperature), so clear temperature effect is not observed as in the case of HDT.

Figure 27.18 shows the influence of velocity on the friction force of SAMs at different normal loads [27.37]. In all cases, normal load does not change the general trends. It is shown that for a silicon wafer, cleaned by Piranha solution just before the friction test, the friction force decreases linearly with increasing velocity. But for Si(111) without cleaning just before the AFM test, the friction force decreases only at high velocity. It is believed that this difference is caused by the adsorbed water and/or contamination on the surface during storage. Figure 27.18 also indicates that the velocity effects of SAMs depend on the molecular structures of SAMs. For SAMs that have compliant long carbon spacer chains, such as HDT and MHA, the friction force increases at high velocity, while for SAMs that have rigid biphenyl chains, such as BPT, BPTC, and DHBp, the friction force changes in the opposite way. The mechanisms responsible for the variation of the friction forces of SAMs with velocity are believed to be related to the viscoelastic properties of SAMs.



Fig. 27.19a,b Wear depth as a function of normal load after one scan cycle [27.35]. **(a)** on Au(111) and SAMs deposited on Au(111)/Si(111) **(b)** on Si(111) and DHPp deposited on Si(111)

27.3.5 Wear and Scratch Resistance of SAMs

Wear resistance was studied on an area of 1 µm × 1 µm using a diamond tip in an AFM. The variation of wear depth with normal loads is presented in Fig. 27.19 [27.35]. It clearly shows that in the whole testing range, DHBp on Si(111) exhibits much better wear resistance compared to Si(111), Au(111), and other SAMs that were deposited on the Au(111) substrate. For the SAMs deposited on Au(111), HDT exhibits the best wear resistance. For all of the tested SAMs, in the wear depth as a function of normal load curves, there appears a critical normal load, which is marked by arrows in Fig. 27.19. When the normal load is smaller than the critical normal load, the monolayer only shows slight height change in the scan areas. When the normal load is higher than the critical value, the height change of SAMs increase dramatically. Relocation and accumulation of BPT molecules have been observed during the initial several scans, which lead to the formation of a larger terrace. Wear studies of a single BPT terrace indicate that the wear life of BPT increases exponentially with terrace size [27.36, 37].

Scratch resistances of Si(111), Au(111), and SAMs were studied by a continuous AFM microscratch technique. Figure 27.20a shows coefficient of friction profiles as a function of increasing normal load and corresponding tapping mode AFM surface height images of the scratches captured on Si(111), Au(111), and SAMs [27.37]. Figure 27.20a indicates that there is an abrupt increase in the coefficients of friction for all of the tested samples. The normal load associated with this event is termed the critical load (indicated by the arrows labeled "A"). At the initial stages of the scratch, all the samples exhibit a low coefficient of friction, indicating that the friction force is dominated by the shear com-





Fig. 27.20 **(a)** Coefficient of friction profiles during scratch as a function of normal load and corresponding AFM surface height images, and **(b)** critical loads estimated from the coefficient of friction profile and AFM images for Au(111), HDT/Au(111), BPT/Au(111), Si(111), and DHBp/Si(111) [27.37]

ponent. This is in agreement with analysis of the AFM images, which shows negligible damage on the surfaces prior to the critical load. At the critical load, a clear groove is formed, accompanied by the formation of material pileup at the sides of the scratch. This suggests that the initial damage that occurs at the critical load is due to ploughing associated with plastic deformation, which causes a sharp rise in the coefficient of friction. Beyond the critical load, debris can be seen in addition to material pile-up at the sides of the scratch. Figure 27.20b summarizes the critical loads for the various samples obtained in this study. It clearly indicates that all SAMs can increase the critical load of the corresponding substrate. DHBp, which is deposited on Si(111), shows superior scratch resistance in all of the tested samples.

Mechanisms responsible for a sudden drop in the decrease in surface height with an increase in load during wear and scratch tests need to be understood. *Barrena* et al. [27.78] observed that the height of self-assembled alkylsilanes decrease in discrete amounts with normal load. This step-like behavior is due to the discrete molecular tilts, which are dictated by the geometrical requirements of the close packing of molecules. Only certain angles are allowed due to the zigzag arrangement of the carbon atoms. The relative height of the monolayer under pressure can be calculated by the following equation:

$$\left(\frac{h}{L}\right)=\left[1+\left(\frac{na}{d}\right)^{2}\right]^{-\frac{1}{2}}, \qquad (27.6)$$

Table 27.12 Calculated $\left[1+\left(\frac{na}{d}\right)^2\right]^{-1/2}$ and measured $\left(\frac{h}{L}\right)$ relative heights of HDT and MHA self-assembled monolayers [27.35]

Steps (n)	Calculated[1] $\left[1+\left(\frac{na}{d}\right)^2\right]^{-1/2}$	Measured[2] $\left(\frac{h}{L}\right)$	
		HDT	MHA
1	0.883		
2	0.685	0.674[3]	0.643[3]
3	0.531	0.532[3]	0.552[3]
4	0.425	0.416[3]	
5	0.352	0.354[3]	
6	0.299		

[1] Calculations are based on the assumption that the molecules tilt in discrete steps (n) upon compression with a diamond AFM tip [27.78].

[2] Measured values are the mean values of three tests.

[3] These measured values correspond to the normal loads of 0.50 µN, 1.57 µN, 2.53 µN, and 4.03 µN, respectively.

where L is the total length of the molecule, h is the height of the SAMs in the tilt configuration (monolayer thickness), a is the distance between alternate carbon atoms in the molecule, d is the separation of the molecules, and n is the step number. For HDT and MHA, only the head groups are different in their work and this study. The spacer carbon chains in alkanethiol and alkylsilane are exactly the same. So the same a (0.25 nm) and d (0.47 nm) values are used in the calculation for HDT and MHA. The calculated and measured relative heights of HDT and MHA are listed in Table 27.12. When the normal loads are smaller than the critical values in Fig. 27.19, the measured relative height values of HDT and MHA are very close to the calculated values. This means that HDT and MHA underwent step tilting below critical normal loads.

Table 27.13 Calculated L_0 and measured residual film thickness for SAMs under critical load

	L_0^1 (nm)	Residual thickness[2] (nm)
HDT	0.24	0.25
BPT	0.39	0.42
BPTC	0.33	0.38
MHA	0.36	0.29
DHBp	–	0.52

[1] Calculated by the equation of $h = b\cos(\alpha)n + L_0$ [27.68]

[2] Measured by AFM using diamond tip under critical normal load. All of the data are the mean values of three tests

The residual SAMs thickness after wear under critical normal load was measured by profiling the worn film using AFM. The results are listed in Table 27.13. For an alkanethiol monolayer, the relationship between the monolayer thickness h and intercept length L_0 can be expressed as (see Fig. 27.21):

$$h = b\cos(\alpha)n + L_0 \,, \tag{27.7}$$

where b is the length of the projection of the C–C bond onto the main chain axis ($b = 0.127$ nm for alkanethiol), n is the chain length defined by $CH_3(CH_2)_nSH$, and α is the tilt angle [27.68]. For BPT and BPTC, based on the same principle and using the bond lengths reported in reference [27.69], the L_0 values are also calculated, Table 27.13. It indicates that the measured residual thickness values of SAMs under critical load are very close to the calculated intercept length L_0 values. It means that under the critical normal load, the Si_3N_4 tip approaches the interface and SAMs wear severely away from the substrate. This is due to the interface chemical adsorption bond strength (HS–Au and Si–O) being generally smaller than the other chemical bond strengths in SAMs



Fig. 27.21 Illustration of the relationship between the components of the equation $h = b\cos(\alpha)n + L_0$ [27.35]

Table 27.14 Bond strengths of the chemical bonds in SAMs [27.35]

SAMs	Bond	Bond strength[1] (kJ/mol)
Thiol on Au	S−Au	184 [27.58]
Hydroxyl on Si	O−Si	242.7 [27.79]
HDT	$H-CH_2$	464.8
	H−CH	421.7
	CH_3-t-C_4H_9	425.9±8
	t-C_4H_9−SH	286.2 ± 6.3
MHA	O=CO	532.2 ± 0.4
	$H-OCOC_2H_5$	445.2±8
	$HO-OCH_2C(CH_3)$	193.7 ± 7.9
	$C_6H_5CH_2-COOH$	280
BPT	CH_3-CH_3	376.0 ± 2.1
	$H_2C=CH_2$	733±8
	C_6H_5-SH	361.9±8
DHBp	C_6H_5-OH	361.9±8

[1] Most of the data are cited from [27.77], except where indicated. For MHA and DHBp, the bonds that are common as in HDT and DHBp are not repeated

spacer chains (see Table 27.14). Based on this discussion, it is believed that the reason why DHBp has the best wear resistance is due to the rigid biphenyl ring structure (compared to linear carbon chain in alkylthiol), the hard Si(111) substrate (compared to Au(111) substrate), and the strong interface Si−O bond strength (compared to the weak S−Au bond strength in the other SAMs, see Table 27.14).



Fig. 27.22 Illustration of the wear mechanisms of SAMs with increasing normal load [27.37]

According to the wear and scratch results reported here and the above discussion, the transition of the wear mechanisms of SAMs with increasing normal load is illustrated in Fig. 27.22. Below the critical normal load, SAMs undergo step orientation, at the critical load SAMs wear away from the substrate due to the weak interface bond strengths, while above the critical normal load severe wear takes place on the substrate. In order to improve wear resistance, the interface bond must be enhanced; a rigid spacer chain and a hard substrate are also preferred.

27.4 Closure

Exposure of devices to humid environments results in condensates of water vapor from the environment. Condensed water, or a preexisting film of liquid, forms concave meniscus bridges between the mating surfaces. The negative Laplace pressure present in the meniscus results in an adhesive force that depends on the interface roughness, surface tension, and contact angle. The adhesive force can be significant in an interface with ultra-smooth surfaces, and it can be on the same order as the external load if the latter is small, such as in micro/nanodevices. Surfaces with high hydrophobicity can be produced by surface treatment. In many applications, hydrophobic films are expected to provide low adhesion, friction, and wear. To minimize high adhesion, friction, and/or because of small clearances in micro/nanodevices, these films should be molecularly thick. Liquid films of low surface tension or certain hydrophobic solid films can be used. Ordered molecular assemblies with high hydrophobicity can be engineered using chemical grafting of various polymer molecules with suitable functional head groups and nonpolar surface terminal groups.

The adhesion, friction, and wear properties of SAMs, having alkyl and biphenyl spacer chains with different surface terminal groups ($-CH_3$, −COOH, and −OH) and head groups (−SH and −OH), studied using an AFM, are reported in this chapter. It is found that the adhesive force varies linearly with the W_a value of SAMs, which indicates that capillary condensation of water plays an important role to the adhesion of SAMs on nanoscale at ambient conditions. It has been found that HDT exhibits the smallest adhesive force and friction force, because of low W_a of $-CH_3$ surface terminal groups, and high-compliance long carbon spacer chain. The friction data are explained using a molecular spring model, in which the local stiffness and intermolecular force governs its frictional performance. The results of the stiffness and friction characterization of the micropatterned sample with different structures support this model. The influence of relative humidity on adhesion and friction of SAMs is dominated by the thickness of the adsorbed water layer. At higher humidity, water can either increase friction through increased adhesion by meniscus effect in the contact zone or reduce friction through an enhanced water-lubricating effect. In the case of Si(111), the desorption of the adsorbed water layer and reduction of surface tension of water with increasing temperature reduce the adhesive force and friction force. The increase of temperature does not show an apparent influence on HDT, but strongly influences the adhesion and friction properties of BPT, which are believed to be related to its melting. The effect of velocity on friction properties of SAMs depends on their molecular structures. For alkylthiol SAMs, their friction is increased by increasing velocity, while for biphenyl SAMs it changes in the opposite way. The mechanism responsible for the variation of the friction forces of SAMs with velocity is believed to be related to their viscoelastic properties. Wear and continuous microscratch tests show that among the SAMs on Au(111), HDT exhibits the best wear resistance. DHBp on Si(111), due to its rigid biphenyl spacer chains, strong interface bonds, and a hard substrate, has the best wear resistance among all of the tested samples. For all of the SAMs, the wear depth as a function of normal load curves shows critical normal loads. Below the critical normal load SAMs undergo step orientation, at the critical load SAMs wear away from the substrate due to the weak interface bond strengths, while above the critical normal load severe wear take place on the substrate.

Based on the nanotribological studies of SAM films by AFM, they exhibit attractive hydrophobic and tribological properties. SAM films should find many tribological applications, including in micro/nanodevices.

References

27.1 B. Bhushan, J. N. Israelachvili, U. Landman: Nanotribology: Friction, wear and lubrication at the atomic scale, Nature **374** (1995) 607–616

27.2 B. Bhushan: *Tribology and Mechanics of Magnetic Storage Devices*, 2nd edn. (Springer, New York 1996)

27.3 B. Bhushan: *Tribology Issues and Opportunities in MEMS* (Kluwer, Dordrecht 1998)

27.4 B. Bhushan: *Handbook of Micro/Nanotribology*, 2nd edn. (CRC, Boca Raton 1999)

27.5 K. F. Man, B. H. Stark, R. Ramesham: *A Resource Handbook for MEMS Reliability* (California Institute of Technology, Pasadena 1998)

27.6 S. Kayali, R. Lawton, B. H. Stark: MEMS reliability assurance activities at JPL, EEE Links **5** (1999) 10–13

27.7 D. M. Tanner, N. F. Smith, L. W. Irwin et al.: *MEMS Reliability: Infrastructure, Test Structure, Experiments, and Failure Modes* (Sandia National Laboratories, Albuquerque 2000)

27.8 S. Arney: Designing for MEMS reliability, MRS Bull. **26** (2001) 296–299

27.9 B. Bhushan: *Principles and Applications of Tribology* (Wiley, New York 1999)

27.10 B. Bhushan: *Introduction to Tribology* (Wiley, New York 2002)

27.11 A. Ulman (Ed.): *Characterization of Organic Thin Films* (Butterworth-Heineman, Boston 1995)

27.12 B. Bhushan: Contact mechanics of rough surfaces in tribology: Multiple asperity contact, Tribol. Lett. **4** (1998) 1–35

27.13 B. Bhushan, W. Peng: Contact mechanics of multilayered rough surfaces, Appl. Mech. Rev. **55** (2002) 435–480

27.14 R. Maboudian: Surface processes in MEMS technology, Surf. Sci. Rep. **30** (1998) 209–269

27.15 M. Scherge, J. A. Schaefer: Surface modification and mechanical properties of bulk silicon. In: *Tribology Issues and Opportunities in MEMS*, ed. by B. Bhushan (Kluwer, Dordrecht 1998) pp. 529–537

27.16 F. P. Bowden, D. Tabor: *The Friction and Lubrication of Solids, Part I* (Clarendon, Oxford 1950)

27.17 V. N. Koinkar, B. Bhushan: Microtribological studies of unlubricated and lubricated surfaces using atomic force/friction force microscopy, J. Vac. Sci. Technol. A **14** (1996) 2378–2391

27.18 B. Bhushan, Z. Zhao: Macro- and microscale tribological studies of molecularly-thick boundary layers of perfluoropolyether lubricants for magnetic thin-film rigid disks, J. Info. Storage Proc. Syst. **1** (1999) 1–21

27.19 H. Liu, B. Bhushan: Nanotribological characterization of molecularly-thick lubricant films for applications to MEMS/NEMS by AFM, Ultramicroscopy **97** (2003) 321–340

27.20 W. A. Zisman: Friction, durability and wettability properties of monomolecular films on solids. In: *Friction and Wear*, ed. by R. Davies (Elsevier, Amsterdam 1959) pp. 110–148

27.21 M. E. Schrader, G. I. Loeb (Eds.): *Modern Approaches to Wettability* (Plenum, New York 1992)

27.22 A. W. Neumann, J. K. Spelt (Eds.): *Applied Surface Thermodynamics* (Dekker, New York 1996)

27.23 H. Hansma, F. Motamedi, P. Smith, P. Hansma, J. C. Wittman: Molecular resolution of thin, highly oriented poly(tetrafluoroethylene) films with the atomic force microscope, Polymer Commun. **33** (1992) 647–649

27.24 L. Scandella, A. Schumacher, N. Kruse, R. Prins, E. Meyer, R. Luethi, L. Howald, H. J. Guentherodt: Tribology of ultra-thin MoS_2 platelets on mica: Studies by scanning force microscopy, Thin Solid Films **240** (1994) 101–104

27.25 B. Bhushan: Chemical, mechanical and tribological characterization of ultra-thin and hard amorphous carbon coatings as thin as 3.5 nm: Recent developments, Diam. Relat. Mater. **8** (1999) 1985–2015

27.26 A. Erdemir, C. Donnet: Tribology of diamond, diamond-like carbon, and related films. In: *Modern Tribology Handbook Vol. 2: Materials, Coatings, and Industrial Applications*, ed. by B. Bhushan (CRC, Boca Raton 2001) pp. 871–908

27.27 V. F. Dorfman: Diamond-like nanocomposites (DLN), Thin Solid Films **212** (1992) 267–273

27.28 M. Grischke, K. Bewilogua, K. Trojan, H. Dimigan: Application-oriented modification of deposition process for diamond-like carbon based coatings, Surf. Coat. Technol. **74-75** (1995) 739–745

27.29 R. S. Butter, D. R. Waterman, A. H. Lettington, R. T. Ramos, E. J. Fordham: Production and wetting properties of fluorinated diamond-like carbon coatings, Thin Solid Films **311** (1997) 107–113

27.30 M. Grischke, A. Hieke, F. Morgenweck, H. Dimigan: Variation of the wettability of DLC coatings by network modification using silicon and oxygen, Diam. Relat. Mater. **7** (1998) 454–458

27.31 C. Donnet, J. Fontaine, A. Grill, V. Patel, C. Jahnes, M. Belin: Wear-resistant fluorinated diamondlike carbon films, Surf. Coat. Technol. **94-95** (1997) 531–536

27.32 D. J. Kester, C. L. Brodbeck, I. L. Singer, A. Kyriakopoulos: Sliding wear behavior of diamond-like nanocomposite coatings, Surf. Coat. Technol. **113** (1999) 268–273

27.33 H. Liu, B. Bhushan: Adhesion and friction studies of microelectromechanical systems/nanoelectromechanical systems materials using a novel microtriboapparatus, J. Vac. Sci. Technol. A **21** (2003) 1528–1538

27.34 B. Bhushan, A. V. Kulkarni, V. N. Koinkar, M. Boehm, L. Odoni, C. Martelet, M. Belin: Microtribological characterization of self-assembled and Langmuir–Blodgett monolayers by atomic and friction force microscopy, Langmuir **11** (1995) 3189–3198

27.35 B. Bhushan, H. Liu: Nanotribological properties and mechanisms of alkylthiol and biphenyl thiol self-assembled monolayers studied by atomic force microscopy, Phys. Rev. B **63** (2001) 245412-1–245412-11

27.36 H. Liu, B. Bhushan, W. Eck, V. Stadler: Investigation of the adhesion, friction, and wear properties of biphenyl thiol self-assembled monolayers by atomic force microscopy, J. Vac. Sci. Technol. A **19** (2001) 1234–1240

27.37 H. Liu, B. Bhushan: Investigation of nanotribological properties of alkylthiol and biphenyl thiol self-assembled monolayers, Ultramicroscopy **91** (2002) 185–202

27.38 H. Liu, B. Bhushan: Orientation and relocation of biphenyl thiol self-assembled monolayers, Ultramicroscopy **91** (2002) 177–183

27.39 A. Ulman: *An Introduction to Ultrathin Organic Films: From Langmuir–Blodgett to Self-Assembly* (Academic, San Diego 1991)

27.40 A. Ulman: Formation and structure of self-assembled monolayers, Chem. Rev. **96** (1996) 1533–1554

27.41 J. A. Zasadzinski, R. Viswanathan, L. Madsen, J. Garnaes, D. K. Schwartz: Langmuir–Blodgett films, Science **263** (1994) 1726–1733

27.42 J. Tian, Y. Xia, G. M. Whitesides: Microcontact printing of SAMs. In: *Thin Films – Self-Assembled Monolayers of Thiols*, Vol. 24, ed. by A. Ulman (Academic, San Diego 1998) pp. 227–254

27.43 Y. Xia, G. M. Whitesides: Soft lithography, Angew. Chem. Int. Edn. **37** (1998) 550–575

27.44 A. Kumar, G. M. Whitesides: Features of gold having micrometer to centimeter dimensions can be formed through a combination of stamping with an elastomeric stamp and an alkanethiol ink followed by chemical etching, Appl. Phys. Lett. **63** (1993) 2002–2004

27.45 S. Y. Chou, P. R. Krauss, P. J. Renstrom: Imprint lithography with 25-nanometer resolution, Science **272** (1996) 85–87

27.46 Y. Xia, E. Kim, X. M. Zhao, J. A. Rogers, M. Prentiss, G. M. Whitesides: Complex optical surfaces formed by replica molding against elastomeric masters, Science **273** (1996) 347–349

27.47 R. F. Service: Self-assembly comes together, Science **265** (1994) 316–318

27.48 M. Hein, L. R. Best, S. Pattison, S. Arena: *Introduction to General, Organic, and Biochemistry*, 6th edn. (Brooks/Cole, Pacific Grove 1997)

27.49 J. R. Mohrig, C. N. Hammond, T. C. Morrill, D. C. Neckers: *Experimental Organic Chemistry* (Freeman, New York 1998)

27.50 S. R. Wasserman, Y. T. Tao, G. M. Whitesides: Structure and reactivity of alkylsiloxane monolayers formed by reaction of alkylchlorosilanes on silicon substrates, Langmuir **5** (1989) 1074–1089

27.51 C. Jung, O. Dannenberger, Y. Xu, M. Buck, M. Grunze: Self-assembled monolayers from organosulfur compounds: A comparison between sulfides, disulfides, and thiols, Langmuir **14** (1998) 1103–1107

27.52 W. Geyer, V. Stadler, W. Eck, M. Zharnikov, A. Golzhauser, M. Grunze: Electron-induced cross-linking of aromatic self-assembled monolayers: Negative resists for nanolithography, Appl. Phys. Lett. **75** (1999) 2401–2403

27.53 J. Ruhe, V. J. Novotny, K. K. Kanazawa, T. Clarke, G. B. Street: Structure and tribological properties of ultrathin alkylsilane films chemisorbed to solid surfaces, Langmuir **9** (1993) 2383–2388

27.54 V. DePalma, N. Tillman: Friction and wear of self-assembled tricholosilane monolayer films on silicon, Langmuir **5** (1989) 868–872

27.55 E. Ando, Y. Goto, K. Morimoto, K. Ariga, Y. Okahata: Frictional properties of monolayers of silane compounds, Thin Solid Films **180** (1989) 287–291

27.56 M. T. McDermott, J. B. D. Green, M. D. Porter: Scanning force microscopic exploration of the lubrication capabilities of n-alkanethiolate monolayers chemisorbed at gold: Structural basis of microscopic friction and wear, Langmuir **13** (1997) 2504–2510

27.57 X. Xiao, J. Hu, D. H. Charych, M. Salmeron: Chain length dependence of the frictional properties of alkylsilane molecules self-assembled on mica studied by atomic force microscopy, Langmuir **12** (1996) 235–237

27.58 A. Lio, D. H. Charych, M. Salmeron: Comparative atomic force microscopy study of the chain length dependence of frictional properties of alkanethiol on gold and alkylsilanes on mica, J. Phys. Chem. B **101** (1997) 3800–3805

27.59 H. Schonherr, G. J. Vancso: Tribological properties of self-assembled monolayers of fluorocarbon and hydrocarbon thiols and disulfides on Au(111) studied by scanning force microscopy, Mater. Sci. Eng. C **8–9** (1999) 243–249

27.60 H. I. Kim, T. Koini, T. R. Lee, S. S. Perry: Systematic studies of the frictional properties of fluorinated monolayers with atomic force microscopy: Comparison of CF_3- and CH_3-terminated groups, Langmuir **13** (1997) 7192–7196

27.61 H. I. Kim, M. Graupe, O. Oloba, T. Koini, S. Imaduddin, T. R. Lee, S. S. Perry: Molecularly specific studies of the frictional properties of monolayer films: A systematic comparison of CF_3-, $(CH_3)_2CH$-, and CH_3-terminated films, Langmuir **15** (1999) 3179–3185

27.62 V. V. Tsukruk, M. P. Everson, L. M. Lander, W. J. Brittain: Nanotribological properties of composite molecular films: C_{60} anchored to a self-assembled monolayer, Langmuir **12** (1996) 3905–3911

27.63 S. Lee, Y. S. Shon, T. R. Lee, S. S. Perry: Structural characterization and frictional properties of C_{60}-terminated self-assembled monolayers on Au(111), Thin Solid Films **358** (2000) 152–158

27.64 V. V. Tsukruk, V. N. Bliznyuk: Adhesive and friction forces between chemically modified silicon and silicon nitride surfaces, Langmuir **14** (1998) 446–455

27.65 V. V. Tsukruk, T. Nguyen, M. Lemieux, J. Hazel, W. H. Weber, V. V. Shevchenko, N. Klimenko, E. Sheludko: Tribological properties of modified MEMS surfaces. In: *Tribology Issues and Opportunities in MEMS*, ed. by B. Bhushan (Kluwer, Dordrecht 1998) pp. 607–614

27.66 M. Fujihira, Y. Tani, M. Furugori, U. Akiba, Y. Okabe: Chemical force microscopy of self-assembled monolayers on sputtered gold films patterned by phase separation, Ultramicroscopy **86** (2001) 63–73

27.67 S. Sundararajan, B. Bhushan: Topography-induced contribution to friction forces measured using an atomic force/friction force microscopy, J. Appl. Phys. **88** (2000) 4825–4831

27.68 Y. F. Miura, M. Takenga, T. Koini, M. Graupe, N. Garg, R. L. Graham, T. R. Lee: Wettability of self-assembled monolayers generated from CF_3-terminated alkanethiols on gold, Langmuir **14** (1998) 5821–5825

27.69 M. Ratajczak-Sitarz, A. Katrusiak, Z. Kaluski, J. Garbarczyk: 4,4′-biphenyldithiol, Acta Crystallogr. C **43** (1987) 2389–2391

27.70 J. N. Israelachvili: *Intermolecular and Surface Forces*, 2nd edn. (Academic, London 1992)

27.71 R. J. Good, C. J. V. Oss: *Modern Approaches to Wettability – Theory and Applications* (Plenum, New York 1992)

27.72 Y. Unno, H. Kawamura, H. Kita, S. Sekiyama: Friction characteristics of sintered Si_3N_4 in oil-lubricated medium, Proc. Int. Symp. Canadian Institute of Mining, Metallurgy and Petroleum, Montreal 1995 (Canadian Institute of Mining, Metallurgy and Petroleum, Montreal 1995) 275–284

27.73 M. H. V. C. Adao, B. J. V. Saramago, A. C. Fernandes: Estimation of the surface properties of styrene-acrylonitrile random copolymers from contact angle measurements, J. Coll. Interface Sci. **217** (1999) 94–106

27.74 J. I. Siepman, I. R. McDonald: Monte Carlo simulation of the mechanical relaxation of a self-assembled monolayer, Phys. Rev. Lett. **70** (1993) 453–456

27.75 M. Garcia-Parajo, C. Longo, J. Servat, P. Gorostiza, F. Sanz: Nanotribological properties of octadecyltrichlorosilane self-assembled ultrathin films studied by atomic force microscopy: Contact and tapping modes, Langmuir **13** (1997) 2333–2339

27.76 D. DeVecchio, B. Bhushan: Localized surface elasticity measurements using an atomic force microscope, Rev. Sci. Instrum. **68** (1997) 4498–4505

27.77 D. R. Lide: *CRC Handbook of Chemistry and Physics*, 75th edn. (CRC, Boca Raton 1994)

27.78 E. Barrena, S. Kopta, D. F. Ogletree, D. H. Charych, M. Salmeron: Relationship between friction and molecular structure: Alkysilane lubricant films under pressure, Phys. Rev. Lett. **82** (1999) 2880–2883

27.79 T. Hoshino, C. Yayoi, K. Inage: Adsorption of atomic and molecular oxygen and desorption of silicon monoxide on Si(111) surface, Phys. Rev. B **59** (1999) 2332–2340

28. Nanoscale Boundary Lubrication Studies

Boundary films are formed by physisorption, chemisorption, and chemical reaction. With physisorption, no exchange of electrons takes place between the molecules of the adsorbate and those of the adsorbant. The physisorption process typically involves van der Waals forces, which are relatively weak. In chemisorption, there is an actual sharing of electrons or electron interchange between the chemisorbed species and the solid surface. The solid surfaces bond very strongly to the adsorption species through covalent bonds. Chemically reacted films are formed by the chemical reaction of a solid surface with the environment. The physisorbed film can be either monomolecularly or polymolecularly thick. The chemisorbed films are monomolecular, but stoichiometric films formed by chemical reaction can have a large film thickness. In general, the stability and durability of surface films decrease in the following order: chemically reacted films, chemisorbed films, and physisorbed films. A good boundary lubricant should have a high degree of interaction between its molecules and the sliding surface. As a general rule, liquids are good lubricants when they are polar and, thus, able to grip solid surfaces (or be adsorbed). In this chapter, we focus on PFPEs. We first introduce details of the commonly used PFPE lubricants; then present a summary of nanodeformation, molecular conformation, and lubricant spreading studies; followed by an overview of nanotribological properties of polar and nonpolar PFPEs studied by atomic force microscopy (AFM) and some concluding remarks.

28.1 **Lubricants Details** 862
28.2 **Nanodeformation, Molecular Conformation, and Lubricant Spreading** . 864
28.3 **Boundary Lubrication Studies** 866
    28.3.1 Friction and Adhesion................. 866
    28.3.2 Rest Time Effect.......................... 869
    28.3.3 Velocity Effect 871
    28.3.4 Relative Humidity and Temperature Effect............... 873
    28.3.5 Tip Radius Effect 876
    28.3.6 Wear Study................................ 879
28.4 **Closure** 880
References 881

Boundary films are formed by physisorption, chemisorption, and chemical reaction. With physisorption, no exchange of electrons takes place between the molecules of the adsorbate and those of the adsorbant. The physisorption process typically involves van der Waals forces, which are relatively weak. In chemisorption, there is an actual sharing of electrons or electron interchange between the chemisorbed species and the solid surface. The solid surfaces bond very strongly to the adsorption species through covalent bonds. Chemically reacted films are formed by the chemical reaction of a solid surface with the environment. The physisorbed film can be either monomolecularly or polymolecularly thick. The chemisorbed films are monomolecular, but stoichiometric films formed by chemical reaction can have a large film thickness. In general, the stability and durability of surface films decrease in the following order: chemically reacted films, chemisorbed films, and physisorbed films. A good boundary lubricant should have a high degree of interaction between its molecules and the sliding surface. As a general rule, liquids are good lubricants when they are polar and, thus, able to grip solid surfaces (or be adsorbed). Polar lubricants contain reactive functional groups with low ionization potential, or groups having high polarizability [28.1–3]. Boundary lubrication properties of lubricants are also dependent upon the molecular conformation and lubricant spreading [28.4–7].

Self-assembled monolayers (SAMs), Langmuir–Blodgett (LB) films, and perfluoropolyether (PFPE) films can be used as boundary lubricants [28.2, 3, 8–10].

PFPE films are commonly used for lubrication of magnetic rigid disks and metal evaporated magnetic tapes to reduce friction and wear of a head-medium interface [28.10]. PFPEs are well suited for this application because of the following properties: low surface tension and low contact angle, which allow easy spreading on surfaces and provide a hydrophobic property; chemical and thermal stability, which minimizes degradation under use; low vapor pressure,which provides low outgassing; high adhesion to substrate via organofunctional bonds; and good lubricity, which reduces the interfacial friction and wear [28.10–12]. While the structure of the lubricants employed at the head-medium interface has not changed substantially over the past decade, the thickness of the PFPE film used to lubricate the disk has steadily decreased from multilayer thicknesses to the sub-monolayer thickness regime [28.11, 13]. Molecularly thick PFPE films are also being considered for lubrication purposes of the evolving microelectromechanical systems (MEMS) industry [28.14]. It is well-known that the properties of molecularly thick liquid films confined to solid surfaces can be dramatically different from those of the corresponding bulk liquid. In order to efficiently develop lubrication systems that meet the requirements of the advanced rigid disk drive and MEMS industries, the impact of thinning the PFPE lubricants on the resulting of nanotribology should be fully understood [28.15, 16]. It is also important to understand lubricant-substrate interfacial interactions and the influence of the operating environment on the nanotribological performance of molecularly thick PFPEs.

An overview of nanotribological properties of SAMs and LB films can be found in many references such as [28.17]. In this chapter, we focus on PFPEs. We first introduce details of the commonly used PFPE lubricants; then present a summary of nanodeformation, molecular conformation, and lubricant spreading studies; followed by an overview of nanotribological properties of polar and nonpolar PFPEs studied by atomic force microscopy (AFM) and some concluding remarks.

28.1 Lubricants Details

Properties of two commonly used PFPE lubricants (Z-15 and Z-DOL) are reviewed here. Their molecular structures are shown schematically in Fig. 28.1. Z-15 has nonpolar $-CF_3$ end groups, whereas Z-DOL is a polar lubricant with hydroxyl ($-OH$) end groups. Their typical properties are summarized in Table 28.1. It shows that Z-15 and Z-DOL almost have the same density and surface tension. But Z-15 has larger molecular weight and higher viscosity. Both have low surface tension, low vapor pressure, low evaporation weight loss, and good oxidative stability [28.10, 12]. Generally, single-crystal Si(100) wafer with a native oxide layer was used as a substrate for deposition of molecularly thick lubricant films



Fig. 28.1 Schematics of the molecular structures of Z-15 and Z-DOL. In this figure the m/n value, shown in Table 28.1, equals 2/3



Fig. 28.2 Schematic of Z-DOL molecules that are chemically bonded on Si(100) substrate surface (which has native oxide) after thermal treatment at 150 °C for 30 min

Table 28.1 Typical properties of Z-15 and Z-DOL (data from Montefluous S.p.A., Milan, Italy)

	Z-15	**Z-DOL (2000)**
Formula	$CF_3{-}O{-}(CF_2{-}CF_2{-}O)_m{-}$ $(CF_2{-}O)_n{-}CF_3{}^*$	$HO{-}CH_2{-}CF_2{-}O{-}(CF_2{-}CF_2{-}O)_m{-}$ $(CF_2{-}O)_n{-}CF_2{-}CH_2{-}OH^*$
Molecular weight (Daltons)	9,100	2,000
Density *(ASTM D891)* 20 °C (g/cm^3)	1.84	1.81
Kinematic viscosity *(ASTM D445)* (cSt)		
20 °C	148	85
38 °C	90	34
99 °C	25	–
Viscosity index *(ASTM D2270)*	320	–
Surface tension *(ASTM D1331)* (dyn/cm) 20 °C	24	24
Vapor pressure (torr)		
20 °C	1.6×10^{-6}	2×10^{-5}
100 °C	1.7×10^{-5}	6×10^{-4}
Pour point *(ASTM D972)*		
°C	−80	–
Evaporation weight loss *(ASTM D972)*		
149 °C, 22 h (%)	0.7	–
Oxidative stability (°C)	–	320
Specific heat (cal/g °C)		
38 °C	0.21	–

* $m/n \sim 2/3$

for nanotribological characterization. Z-15 and Z-DOL films can be deposited directly on the Si(100) wafer by dip coating technique. The clean silicon wafer is vertically submerged into a dilute solution of lubricant in hydrocarbon solvent (HT-70) for a certain time. The silicon wafers are vertically pulled up from the solution with a motorized stage at a constant speed for deposition of desired thicknesses of Z-15 and Z-DOL lubricants. The lubricant film thickness obtained in dip coating is a function of the concentration and pulling-up speed, among other factors. The Z-DOL film is bonded to the silicon substrate by heating the as-deposited Z-DOL samples in an oven at 150 °C for about 30 s. The native oxide layer of Si(100) wafer reacts with the −OH groups of the lubricants during thermal treatment [28.18–21]. Subsequently, fluorocarbon solvent (FC-72) washing of the thermal treated specimen removes loosely absorbed species, leaving chemically bonded phase on the substrate. The chemical bonding between Z-DOL molecules and silicon substrate is illustrated in Fig. 28.2. The bonded and washed Z-DOL film is referred to as Z-DOL(BW) in this chapter. The as-deposited Z-15 and Z-DOL films are mobile phase lubricants (i. e., liquid-like lubricant), whereas the Z-DOL(BW) films are fully bonded soft solid phase (i. e., solid-like) lubricants. This will be further discussed in the next section.

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

28.2 Nanodeformation, Molecular Conformation, and Lubricant Spreading

Nanodeformation behavior of Z-DOL lubricants was studied using an AFM by *Blackman* et al. [28.22,23]. Before bringing a tungsten tip into contact with a molecular overlayer, it was brought into contact with a bare clean-silicon surface, Fig. 28.3. As the sample approaches the tip, the force initially is zero, but at point A the force suddenly becomes attractive (top curve), which increases until at point B, where the sample and tip come into intimate contact and the force becomes repulsive. As the sample is retracted, a pull-off force of 5×10^{-8} N (point D) is required to overcome adhesion between the tungsten tip and the silicon surface. When an AFM tip is brought into contact with an unbonded Z-DOL film, a sudden jump into adhesive contact is also observed. A much larger pull-off force is required to overcome the adhesion. The adhesion is initiated by the formation of a lubricant meniscus surrounding the tip. This suggests that the unbonded Z-DOL lubricant shows liquid-like behavior. However, when the tip was brought into contact with a lubricant film, which was firmly bonded to the surface, the liquid-like behavior disappears. The initial attractive force (point A) is no longer sudden, as with the liquid film, but, rather, gradually increases as the tip penetrates the film.

According to *Blackman* et al. [28.22, 23], if the substrate and tip were infinitely hard with no compliance and/or deformation in the tip and sample supports, the line for B to C would be vertical with an infinite slope. The tangent to the force-distance curve at a given point is referred to as the stiffness at that point and was determined by fitting a least-squares line through the nearby data points. For silicon, the deformation is reversible (elastic), since the retracting (outgoing) portion of the curve (C to D) follows the extending (ingoing) portion (B to C). For bonded lubricant film, at the point where slope of the force changes gradually from attractive to repulsive, the stiffness changes gradually, indicating compression of the molecular film. As the load is increased, the slope of the repulsive force eventually approaches that of the bare surface. The bonded film was found to respond elastically up to the highest loads of 5 µN that could be applied. Thus, bonded lubricant behaves as a soft polymer solid.

Figure 28.4 illustrates two extremes for the conformation on a surface of a linear liquid polymer without any reactive end groups and at submonolayer coverages [28.4, 6]. At one extreme, the molecules lie flat on the surface, reaching no more than their chain diameter δ above the surface. This would be the case if a strong attractive interaction exists between the molecules and the solid. On the other extreme, when a weak attraction exists between polymer segments and the solid, the molecules adopt conformation close to that of the molecules in the bulk, with the microscopic thickness equal to about the radius of gyration R_g. *Mate* and *Novotny* [28.6] used AFM to study conformation of 0.5–1.3 nm-thick Z-15 molecules on clean Si(100) surfaces. They found that the thickness measured by AFM is thicker than that measured by ellipsometry with the offset ranging from 3–5 nm. They found that the offset was the same for very thin submonolayer coverages. If the coverage is submonolayer and inadequate to make a liquid film, the relevant thickness is then the height (h_e) of the molecules extended above the solid surface. The offset should be equal to $2h_e$, assum-



Fig. 28.3 Wire deflection (normal load) as a function of tip-sample separation distance curves comparing the behavior of clean Si(100) surface to a surface lubricated with free and unbonded PFPE lubricant, and a surface where the PFPE lubricant film was thermally bonded to the surface [28.22]

ing that the molecules extend the same height above both the tip and silicon surfaces. They therefore concluded that the molecules do not extend more than 1.5–2.5 nm above a solid or liquid surface, much smaller than the radius of gyration of the lubricants ranging between 3.2 and 7.3 nm, and to the approximate cross-sectional diameter of 0.6–0.7 nm for the linear polymer chain. Consequently, the height that the molecules extend above the surface is considerably less than the diameter of gyration of the molecules and only a few molecular diameters in height, implying that the physisorbed molecules on a solid surface have an extended, flat conformation. They also determined the disjoining pressure of these liquid films from AFM measurements of the distance needed to break the liquid meniscus that forms between the solid surface and the AFM tip. (Also see [28.7].) For a monolayer thickness of about 0.7 nm, the disjoining pressure is about 5 MPa, indicating strong attractive interaction between the liquid molecules and the solid surface. The disjoining pressure decreases with increasing film thickness in a manner consistent with a strong attractive van der Waals interaction between the liquid molecules and the solid surface.



Fig. 28.4 Schematic representation of two extreme liquid conformations at the surface of the solid for low and high molecular weights at low surface coverage. δ is the cross-sectional diameter of the liquid chain, and R_g is the radius of gyration of the molecules in the bulk [28.6]

Rheological characterization shows that the flow activation energy of PFPE lubricants is weakly dependent on chain length and is strongly dependent on the functional end groups [28.25]. PFPE lubricant films that contain polar end groups have lower mobility than those with nonpolar end groups of similar chain length [28.26]. The mobility of PFPE also depends on the surface chemical properties of the substrate. The spreading of Z-DOL on amorphous carbon surface has been studied as a function of hydrogen or nitrogen content in the carbon film, using scanning microellipsometry [28.24]. The diffusion coefficient data presented in Fig. 28.5 is thickness-dependent. It shows that the surface mobility of Z-DOL increased as the hydrogen content increased, but decreased as nitrogen content increased. The enhancement of Z-DOL surface mobility by hydrogenation may be understood from the fact that the interactions between Z-DOL molecules and the carbon surface can be significantly weakened, due to a reduction of the number of high-energy binding sites on the carbon surface. The stronger interactions between the Z-DOL molecules and carbon surface, as nitrogen content in the carbon coating increases, leads to the lowering of Z-DOL surface mobility.



Fig. 28.5 Diffusion coefficient $D(h)$ as a function of lubricant film thickness for Z-DOL on different carbon films [28.24]

Molecularly thick films may be sheared at very high shear rates, on the order of 10^8–10^9 s^{-1} during sliding, such as during magnetic disk drive operation. During such shear, lubricant stability is critical to the protection of the interface. For proper lubricant selection, viscosity at high shear rates and associated shear thinning need to be understood. Viscosity measurements of eight different types of PFPE films show that all eight lubricants display Newtonian behavior and their viscosity remains constant at a shear rate up to 10^7 s^{-1} [28.27, 28].

28.3 Boundary Lubrication Studies

With the development of AFM techniques, studies have been carried out to investigate the nanotribological performance of PFPEs. *Mate* [28.29, 30], *O'Shea* et al. [28.31, 32], *Bhushan* et al. [28.15, 33], *Koinkar* and *Bhushan* [28.20, 34], *Bhushan* and *Sundararajan* [28.35], *Bhushan* and *Dandavate* [28.36], and *Liu* and *Bhushan* [28.21] used an AFM to provide insight into how PFPE lubricants function at the molecular level. *Mate* [28.29, 30] conducted friction experiments on bonded and unbonded Z-DOL and found that the coefficient of friction of the unbonded Z-DOL is about two times larger than the bonded Z-DOL (also see [28.31, 32]). *Koinkar* and *Bhushan* [28.20, 34] and *Liu* and *Bhushan* [28.21] studied the friction and wear performance of a Si(100) sample lubricated with Z-15, Z-DOL, and Z-DOL(BW) lubricants. They found that using Z-DOL(BW) could significantly improve the adhesion, friction, and wear performance of Si(100). They also discussed the lubrication mechanisms on the molecular level. *Bhushan* and *Sundararajan* [28.35] and *Bhushan* and *Dandavate* [28.36] studied the effect of tip radius and relative humidity on the adhesion and friction properties of Si(100) coated with Z-DOL(BW).

In this section, we review, in some detail, the adhesion, friction, and wear properties of two kinds of typical PFPE lubricants of Z-15 and Z-DOL at various operating conditions (rest time, velocity, relative humidity, temperature, and tip radius). The experiments were carried out using a commercial AFM system with pyramidal Si_3N_4 and diamond tips. An environmentally controlled chamber and a thermal stage were used to perform relative humidity and temperature effect studies.

28.3.1 Friction and Adhesion

To investigate the friction properties of Z-15 and Z-DOL(BW) films on Si(100), the friction force versus normal load curves were measured by making friction measurements at increasing normal loads [28.21]. The representative results of Si(100), Z-15, and Z-DOL(BW) are shown in Fig. 28.6. An approximately linear response of all three samples is observed in the load range of 5–130 nN. The friction force of solid-like Z-DOL(BW) is consistently smaller than that for Si(100), but the friction force of liquid-like Z-15 lubricant is higher than that of Si(100). *Sundararajan* and *Bhushan* [28.37] have studied the static friction force of silicon micromotors lubricated with Z-DOL by AFM. They also found that liquid-like lubricants of Z-DOL significantly increase the static friction force, whereas solid-like Z-DOL(BW) coating can dramatically reduce the static friction force. This is in good agreement with the results of *Liu* and *Bhushan* [28.21]. In Fig. 28.6, the nonzero value of the friction force signal at zero external load is due to the adhesive forces. It is well-known that the following relationship exists between the friction force F and external



Fig. 28.6 Friction force versus normal load curves for Si(100), 2.8-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) film at 2 μm/s, and in ambient air sliding against a Si_3N_4 tip. Based on these curves, coefficient of friction μ and adhesion force of W_a can be calculated [28.21]

normal load W [28.2, 3]

$$F = \mu(W + W_a)\,, \tag{28.1}$$

where μ is the coefficient of friction and W_a is the adhesive force. Based on this equation and the data in Fig. 28.6, we can calculate the μ and W_a values. The coefficients of friction of Si(100), Z-15, and Z-DOL are 0.07, 0.09, and 0.04, respectively. Based on (28.1), the adhesive force values are obtained from the horizontal intercepts of the friction force versus normal load curves at a zero value of friction force. Adhesive force values of Si(100), Z-15, and Z-DOL are 52 nN, 91 nN, and 34 nN, respectively.

The adhesive forces of these samples were also measured using a force calibration plot (FCP) technique. In this technique, the tip is brought into contact with the sample and the maximum force, needed to pull the tip and sample apart, is measured as the adhesive force. Figure 28.7 shows the typical FCP curves of Si(100), Z-15, and Z-DOL(BW) [28.21]. As the tip approaches the sample within a few nanometers (A), an attractive force exists between the tip and the sample surfaces. The tip is pulled toward the sample, and contact occurs at point B on the graph. The adsorption of water molecules and/or presence of liquid lubricant molecules on the sample surface can also accelerate this so-called "snap-in", due to the formation of meniscus of the water and/or liquid lubricant around the tip. From this point on, the tip is in contact with surface, and as the piezo extends further, the cantilever is further deflected. This is represented by the slope portion of the curve. As the piezo retracts, at point C the tip goes beyond the zero deflection (flat) line, because of the attractive forces, into the adhesive force regime. At point D, the tip snaps free of the adhesive forces and is again in free air. The adhesive force (pull-off force) is determined by multiplying the cantilever spring constant (0.58 N/m) by the horizontal distance between points C and D, which corresponds to the maximum cantilever deflection toward the samples before the tip is disengaged. Incidentally, the horizontal shift between the loading and unloading curves results from the hysteresis of the PZT tube.

The adhesive forces of Si(100), Z-15, and Z-DOL(BW) measured by FCP and friction force versus normal load plot are summarized in Fig. 28.8 [28.21]. The results measured by these two methods are in good agreement. Figure 28.8 shows that the presence of mobile Z-15 lubricant film increases the adhesive force as compared to that of Si(100). In contrast, the presence of solid phase Z-DOL(BW) film reduces the adhesive force as compared to that of Si(100). This result is in good agreement with the results of *Blackman* et al. [28.22] and *Bhushan* and *Ruan* [28.38]. Sources of adhesive forces between the tip and the sample surfaces are van der Waals attraction and long-range meniscus force [28.2, 3, 16]. Relative magnitudes of the forces from the two sources are dependent on various factors, including the distance between the tip and the sample surface, their surface roughness, their hydrophobicity, and relative humidity [28.39]. For most surfaces with some roughness, meniscus contribution dominates at moderate to high humidities.



Fig. 28.7 Typical force calibration plots of Si(100), 2.8-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) film in ambient air. The adhesive forces can be calculated from the horizontal distance between points C and D, and the cantilever spring constant of 0.58 N/m [28.21]



Fig. 28.8 Summary of the adhesive forces of Si(100), 2.8-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) film measured by force calibration plots and friction force versus normal load plots in ambient air. The schematic (*bottom*) shows the effect of meniscus formed between the AFM tip and the sample surface on the adhesive and friction forces [28.21]

The schematic (bottom) in Fig. 28.8 shows relative size and sources of meniscus. The native oxide layer (SiO_2) on the top of Si(100) wafer exhibits hydrophilic properties, and some water molecules can be adsorbed on this surface. The condensed water will form meniscus as the tip approaches the sample surface. In the case of a sphere (such as a single-asperity AFM tip) in contact with a flat surface, the attractive Laplace force (F_L) caused by capillary is:

$$F_L = 2\pi R\gamma_{la}(\cos\theta_1 + \cos\theta_2)\,, \tag{28.2}$$

where R is the radius of the sphere, γ_{la} is the surface tension of the liquid against air, θ_1 and θ_2 are the contact angles between liquid and flat and spherical surfaces, respectively [28.2, 3, 40]. As the surface tension value of Z-15 (24 dyn/cm) is smaller than that of water (72 dyn/cm), the larger adhesive force in Z-15 cannot only be caused by the Z-15 meniscus. The nonpolarized Z-15 liquid does not have complete coverage and strong bonding with Si(100). In the ambient environment, the condensed water molecules will permeate through the liquid Z-15 lubricant film and compete with the lubricant molecules present on the substrate. The interaction of the liquid lubricant with the substrate is weakened, and a boundary layer of the liquid lubricant forms puddles [28.20, 34]. This dewetting allows water molecules to be adsorbed on the Si(100) surface as aggregates along with Z-15 molecules. And both of them can form meniscus while the tip approaches the surface. In addition, as the Z-15 film is pretty soft compared to the solid Si(100) surface, penetration of the tip in the film occurs while pushing the tip down. This leads to a large area of the tip involved to form the meniscus at the tip-liquid (water aggregates along with Z-15) interface. These two factors of the liquid-like Z-15 film result in higher adhesive force. It should also be noted that Z-15 has a higher viscosity compared to that of water. Therefore, Z-15 film provides higher resistance to sliding motion and results in a larger coefficient of friction. In the case of Z-DOL(BW) film, both of the active groups of Z-DOL molecules are strongly bonded on Si(100) substrate through the thermal and washing treatment. Thus, the Z-DOL(BW) film has relatively low free surface energy and cannot be displaced readily by water molecules or readily adsorb water molecules. Thus, the use of Z-DOL(BW) can reduce the adhesive force. We further note that the bonded Z-DOL molecules can be orientated under stress (behaves as a soft polymer solid), which facilitates sliding and reduces coefficient of friction.



Fig. 28.9 Gray-scale plots of the surface topography and friction force obtained simultaneously for unbonded 2.3-nm-thick Demnum-type PFPE lubricant film on silicon [28.20]



Fig. 28.10 Gray-scale plots of the adhesive force distribution of a uniformly coated, 3.5-nm-thick unbonded Z-DOL film on silicon and 3- to 10-nm-thick unbonded Z-DOL film on silicon that was deliberately coated nonuniformly by vibrating the sample during the coating process [28.36]

These studies suggest that if the lubricant films exist as liquid-like, such as Z-15 films, they easily form meniscus (by themselves and the adsorbed water molecules), and thus have higher adhesive force and higher friction force. Whereas if the lubricant film exists in solid-like phase, such as Z-DOL(BW) films, they are hydrophobic with low adhesion and friction.

In order to study the uniformity of lubricant film and its influence on friction and adhesion, friction force mapping and adhesive force mapping of PFPE have been carried out by *Koinkar* and *Bhushan* [28.34] and *Bhushan* and *Dandavate* [28.36], respectively. Figure 28.9 shows gray-scale plots of surface topography and friction force images obtained simultaneously for unbonded Demnum-type PFPE lubricant film on silicon [28.34]. The friction force plot shows well distinguished low and high friction regions corresponding roughly to high and low surface height regions in the topography image (thick and thin lubricant regions). A uniformly lubricated sample does not show such a variation in friction. Figure 28.10 shows the gray-scale plots of the adhesive force distribution for silicon samples coated uniformly and nonuniformly with Z-DOL lubricant. It can be clearly seen that there exists a region that has an adhesive force distinctly different from the other region for the nonuniformly coated sample. This implies that the liquid film thickness is nonuniform, giving rise to a difference in the meniscus forces.

28.3.2 Rest Time Effect

It is well-known that in the computer rigid disk drive, the stiction force increases rapidly with an increase in rest time between the head and magnetic medium disk [28.10, 11]. Considering that the stiction and friction are



Fig. 28.11 **(a)** Rest time effect on friction force, adhesive force, and coefficient of friction of Si(100). **(b)** (*see next page*) Summary of the rest time effect on friction force, adhesive force, and coefficient of friction of Si(100), 2.8-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) film. All of the measurements were carried out at 70 nN, 2 µm/s, and in ambient air [28.21]



Fig. 28.11b



Fig. 28.12a



Fig. 28.12 **(a)** Schematic of a single asperity in contact with a smooth flat surface in the presence of a continuous liquid film when ϕ is large. **(b)** Results of the single asperity model. Effect of viscosity of the liquid, radius of the asperity, and film thickness is studied with respect to the time-dependent meniscus force [28.41]

two of the major issues that lead to the failure of computer rigid disk drives and MEMS, it is very important to find out if the rest time effect also exists on the nanoscale. First, the rest time effect on the friction force, adhesive force, and coefficient of Si(100) sliding against Si_3N_4 tip was studied, Fig. 28.11a [28.21]. It was found that the friction and adhesive forces logarithmically increase up to a certain equilibrium time after which they remain constant. Figure 28.11a also shows that the rest time does not affect the coefficient of friction. These results suggest that the rest time can result in growth of the meniscus, which causes a higher adhesive force, and in turn, a higher friction force. But in the whole testing range the friction mechanisms do not change with the rest time. Similar studies were also performed on Z-15 and Z-DOL(BW) films. The results are summarized in Fig. 28.11b [28.21]. It is seen that similar time effect has been observed on Z-15 film, but not on Z-DOL(BW) film.

AFM tip in contact with a flat sample surface is generally believed to represent a single asperity contact. Therefore, a Si_3N_4 tip in contact with Si(100) or Z-15/Si(100) can be modeled as a sphere in contact with a flat surface covered by a layer of liquid (adsorbed water and/or liquid lubricant), Fig. 28.12a. Meniscus forms around the contacting asperity and grows with time until equilibrium occurs [28.41]. The meniscus force, which is the product of meniscus pressure and meniscus area, depends on the flow of liquid phase toward the contact zone. The flow of the liquid toward the contact zone is governed by the capillary pressure P_c, which draws liquid into the meniscus, and the disjoining pressure Π, which tends to draw the liquid away from the meniscus. Based on the Young and Laplace equation, the capillary pressure, P_c, is:

$$P_c = 2K\gamma \, , \tag{28.3}$$

where $2K$ is the mean meniscus curvature ($= K_1 + K_2$, where K_1 and K_2 are the curvatures of the meniscus in the contact plane and perpendicular to the contact plane) and γ is the surface tension of the liquid. *Mate* and *Novotny* [28.6] have shown that the disjoining pressure decreases rapidly with increasing liquid film thickness in a manner consistent with a strong van der Waals attraction. The disjoining pressure, Π, for these liquid films can be expressed as:

$$\Pi = \frac{A}{6\pi h^3} \, , \tag{28.4}$$

where A is the Hamaker constant and h is the liquid film thickness. The driving forces that cause the lubricant flow that results in an increase in the meniscus force are the disjoining pressure gradient, due to a gradient in film thickness, and capillary pressure gradient, due to curved liquid-air interface. The driving pressure, P, can then be written as:

$$P = -2K\gamma - \Pi \, . \tag{28.5}$$

Based on these three basic relationships, the following differential equation has been derived by *Chilamakuri* and *Bhushan* [28.41], which can describe the meniscus at time t:

$$\begin{aligned} & 2\pi x_0 \left(D + \frac{x_0^2}{2R} - h_0 \right) \frac{\mathrm{d}x_0}{\mathrm{d}t} \\ & = \frac{2\pi h_0^3 \gamma}{3\eta} \frac{(1+\cos\theta)}{D + a - h_0} - \frac{A x_0}{3\eta h} \cot\alpha \, , \end{aligned} \tag{28.6}$$

where η is the viscosity of the liquid and a is given as

$$a = R(1-\cos\phi) \sim \frac{R\phi^2}{2} \sim \frac{x_0^2}{2R} \, . \tag{28.7}$$

The differential equation (28.4) was solved numerically using Newton's iteration method. The meniscus force at any time t less than the equilibrium time is proportional to the meniscus area and meniscus pressure ($2K\gamma$), and it is given by

$$f_m(t) = 2\pi R\gamma(1+\cos\theta) \left(\frac{x_0}{(x_0)_{eq}} \right)^2 \left(\frac{K}{K_{eq}} \right) \, , \tag{28.8}$$

where $(x_0)_{eq}$ is the value of x_0 at the equilibrium time

$$\left[(x_0)_{eq} \right]^2 = 2R \left[\frac{-6\pi h_0^3 \gamma (1+\cos\theta)}{A} + (h_0 - D) \right] . \tag{28.9}$$

This modeling work (at the microscale) showed that the meniscus force initially increases logarithmically with the rest time up to a certain equilibrium time after which it remains constant. Equilibrium time decreases with an increase in liquid film thickness, a decrease in viscosity, and a decrease in the tip radius, Fig. 28.12b. This early numerical modeling work and the data at the nanoscale in Fig. 28.11a are in good agreement.

28.3.3 Velocity Effect

To investigate the velocity effect on friction and adhesion, the friction force versus normal load relationships of Si(100), Z-15, and Z-DOL(BW) at different velocities were measured, Fig. 28.13 [28.21]. Based on these data,



Fig. 28.13 Friction forces versus normal load data of Si(100), 2.8-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) film at various velocities in ambient air [28.21]

the adhesive force and coefficient of friction values can be calculated by (28.1). The variation of friction force, adhesive force, and coefficient of friction of Si(100), Z-15, and Z-DOL(BW) as a function of velocity are summarized in Fig. 28.14. It indicates that for silicon wafer, the friction force decreases logarithmically with increasing velocity. For Z-15, the friction force decreases with increasing velocity up to 10 µm/s, after which it remains almost constant. The velocity has a much smaller effect on the friction force of Z-DOL(BW); it reduced slightly only at very high velocity. Figure 28.14 also indicates that the adhesive force of Si(100) is increased when the velocity is higher than 10 µm/s. The adhesive force of Z-15 is reduced dramatically with a velocity increase up to 20 µm/s, after which it is reduced slightly. And the adhesive force of Z-DOL(BW) also decreases at high velocity. In the testing range of velocity, only the coefficient of friction of Si(100) decreases with velocity, but the coefficients of friction of Z-15 and Z-DOL(BW) almost remain constant. This implies that the friction mechanisms of Z-15 and Z-DOL(BW) do not change with the variation of velocity.

The mechanisms of the effect of velocity on the adhesion and friction are explained based on the schematics shown in Fig. 28.14 (right). For Si(100), tribochemical reaction plays a major role. Although at high velocity the meniscus is broken and does not have enough time to rebuild, the contact stresses and high velocity lead to tribochemical reactions of Si(100) wafer and Si_3N_4 tip, which have native oxide (SiO_2) layers with water molecules. The following reactions occur:

$$SiO_2 + 2H_2O = Si(OH)_4 \quad (28.10)$$

$$Si_3N_4 + 16H_2O = 3Si(OH)_4 + 4NH_4OH\,. \quad (28.11)$$

The $Si(OH)_4$ is removed and continuously replenished during sliding. The $Si(OH)_4$ layer between the tip and Si(100) surface is known to be of low shear strength and causes a decrease in friction force and coefficient of friction in the lateral direction [28.42–46]. The chemical bonds of Si−OH between the tip and Si(100) surface induce large adhesive force in the normal direction. For Z-15 film, at high velocity the meniscus formed by condensed water and Z-15 molecules is broken and does not have enough time to rebuild. Therefore, the adhesive force and, consequently, friction force is reduced. For Z-DOL(BW) film, the surface can adsorb few water molecules in ambient condition, and at high velocity these molecules are displaced, which is responsible for a slight decrease in friction force and adhesive force. Even at high velocity range, the friction mechanisms for Z-15 and Z-DOL(BW) films still are shearing of the vis-



Fig. 28.14 The influence of velocity on the friction force, adhesive force, and coefficient of friction of Si(100), 2.8-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) film at 70 nN, in ambient air. The schematic (*right*) shows the change of surface composition (by tribochemical reaction) and change of meniscus with increasing velocity [28.21]

cous liquid and molecular orientation, respectively. Thus the coefficients of friction of Z-15 and Z-DOL(BW) do not change with velocity.

Koinkar and *Bhushan* [28.20, 34] have suggested that in the case of samples with mobile films, such as condensed water and Z-15 films, alignment of liquid molecules (shear thinning) is responsible for the drop in friction force with an increase in scanning velocity. This could be another reason for the decrease in friction force with velocity for Si(100) and Z-15 film in this study.

28.3.4 Relative Humidity and Temperature Effect

The influence of relative humidity on friction and adhesion was studied in an environmentally controlled chamber. The friction force was measured by making measurements at increasing relative humidity, the results are presented in Fig. 28.15 [28.21]. It shows that for Si(100) and Z-15 film, the friction force increases with a relative humidity increase up to RH 45%, and then it shows a slight decrease with a further increase in relative humidity. Z-DOL(BW) has a smaller friction force than Si(100) and Z-15 in the whole testing range. And its friction force shows a relatively apparent increase when the relative humidity is higher than RH 45%. For Si(100), Z-15, and Z-DOL(BW), adhesive



Fig. 28.15 The influence of relative humidity (RH) on the friction force, adhesive force, and coefficient of friction of Si(100), 2.8-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) film at 70 nN, 2 μm/s, and in 22 °C air. Schematic (*right*) shows the change of meniscus with increasing relative humidity. In this figure, the thermally treated Si(100) represents the Si(100) wafer that was baked at 150 °C for 1 hour in an oven (in order to remove the adsorbed water) just before it was placed in the 0% RH chamber [28.21]

forces increase with relative humidity. And their coefficients of friction increase with a relative humidity up to RH 45%, after which they decrease with a further increase of the relative humidity. It is also observed that the humidity effect on Si(100) really depends on the history of the Si(100) sample. As the surface of Si(100) wafer readily adsorbs water in air, without any pre-treatment the Si(100) used in our study almost reaches its saturate stage of adsorbing water and is responsible for less effect during increasing relative humidity. However, once the Si(100) wafer was thermally treated by baking at 150 °C for 1 hour, a bigger effect was observed.

The schematic (right) in Fig. 28.15 shows that because its high free surface energy Si(100) can adsorb more water molecules with increasing relative humidity. As discussed earlier, for Z-15 film in a humid environment, condensed water competes with the lubricant film present on the sample surface. Obviously, more water molecules can also be adsorbed on a Z-15 surface with increasing relative humidity. The more adsorbed water





Fig. 28.16 The influence of temperature on the friction force, adhesive force, and coefficient of friction of Si(100), 2.8-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) film at 70 nN, at 2 µm/s, and in RH 40–50 % air. The schematic (*right*) shows that at high temperature, desorption of water decreases the adhesive forces. And the reduced viscosity of Z-15 leads to the decrease of coefficient of friction. High temperature facilitates orientation of molecules in Z-DOL(BW) film, which results in lower coefficient of friction [28.21]

molecules in the case of Si(100), along with lubricant molecules in Z-15 film, form a bigger water meniscus, which leads to an increase of friction force, adhesive force, and coefficient of friction of Si(100) and Z-15 with humidity. But at very high humidity of RH 70%, large quantities of adsorbed water can form a continuous water layer that separates the tip and sample surface, and acts as a kind of lubricant, which causes a decrease in the friction force and coefficient of friction. For Z-DOL(BW) film, because of its hydrophobic surface properties, water molecules can only be adsorbed at high humidity ($\geq$ RH 45%), which causes an increase in the adhesive force and friction force.

The effect of temperature on friction and adhesion was studied using a thermal stage attached to the AFM. The friction force was measured at increasing temperature from 22–125 °C. The results are presented in Fig. 28.16 [28.21]. It shows that the increasing temperature causes a decrease of friction force, adhesive force, and coefficient of friction of Si(100), Z-15, and Z-DOL(BW). The schematic (right) in Fig. 28.16 indicates that at high temperature, desorption of water leads to the decrease of friction force, adhesive force, and coefficient of friction for all of the samples. Besides that, the reduction of surface tension of water also contributes to the decrease of friction and adhesion. For Z-15 film, the reduction of viscosity at high temperature has an additional contribution to the decrease of friction. In the case of Z-DOL(BW) film, molecules are more easily oriented at high temperature, which may also be responsible for the low friction.

Using a surface force apparatus, *Yoshizawa* and *Israelachvili* [28.47, 48] have shown that a change in the velocity or temperature induces phase transformation (from crystalline solid-like to amorphous, then to liquid-like) in surfactant monolayers, which are responsible for the observed changes in the friction force. Stick-slip is observed in a low velocity regime of a few µm/s, and adhesion and friction first increase followed by a decrease in the temperature range of 0–50 °C. Stick-slip at low velocity and adhesion and friction curves peaking at some particular temperature (observed in their study), have not been observed in the AFM study. It suggests that the phase transformation may not happen in this study, because PFPEs generally have very good thermal stability [28.10, 12].

As a brief summary, the influence of velocity, relative humidity, and temperature on the friction force of Z-15 film is presented in Fig. 28.17. The changing trends are also addressed in this figure.


Friction force (nN)
Molecularly thick Z-15 film
Lack of meniscus reformation decreases friction with increasing velocity
Reaches equilibrium
Log velocity
Friction force (nN)
Meniscus formation increases friction with increasing RH
Thick water film serves as a lubricant
Relative humidity
Friction force (nN)
Desorption of water and decrease of viscosity decrease friction with increase of temperature
Temperature

Fig. 28.17 Schematic shows the change of friction force of molecularly thick Z-15 films with log velocity, relative humidity, and temperature [28.21]

28.3.5 Tip Radius Effect

The tip radius and relative humidity affect adhesion and friction for dry and lubricated surfaces [28.35, 36]. Figure 28.18a shows the variation of single point adhesive force measurements as a function of tip radius on a Si(100) sample for several humidities. The adhesive force data are also plotted as a function of relative humidity for various tip radii. Figure 28.18a indicates that the tip radius has little effect on the adhesive forces at low humidities, but the adhesive force increases with tip radius at high humidity. Adhesive force also increases with an increase in humidity for all tips. The trend in adhesive forces as a function of tip radii and relative humidity, in Fig. 28.18a, can be explained by the presence of meniscus forces, which arise from capillary condensation of water vapor from the environment. If enough liquid is present to form a meniscus bridge, the meniscus force should increase with an increase in tip radius based on (28.2). This observation suggests that thickness of the liquid film at low humidities is insufficient to form continuous meniscus bridges and to affect adhesive forces in the case of all tips.

Figure 28.18a also shows the variation in coefficient of friction as a function of tip radius at a given humidity and as a function of relative humidity for a given tip radius on the Si(100) sample. It can be observed that for RH 0%, the coefficient of friction is about the same for the tip radii except for the largest tip, which shows



Fig. 28.18a,b Adhesive force and coefficient of friction as a function of tip radius at several humidities and as a function of relative humidity at several tip radii on **(a)** Si(100) and **(b)** 0.5-nm Z-DOL(BW) films [28.35]



Fig. 28.19 Friction force and coefficient of friction versus number of sliding cycles for Si(100), 2.8-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) film at 70 nN, 0.8 µm/s, and in ambient air. Schematic (*bottom*) shows that some liquid Z-15 molecules can be attached on the tip. The molecular interaction between the attached molecules on the tip with the Z-15 molecules in the film results in an increase of the friction force with multiple scanning [28.21]

a higher value. At all other humidities, the trend consistently shows that the coefficient of friction increases with tip radius. An increase in friction with tip radius at low to moderate humidities arises from increased contact area (i. e., higher van der Waals forces) and higher values of shear forces required for a larger contact area. At high humidities, similar to adhesive force data, an increase with tip radius occurs due to of both contact area and meniscus effects. It can be seen that for all tips, the coefficient of friction increases with humidity to about RH 45%, beyond which it starts to decrease. This is attributed to the fact that at higher humidities, the adsorbed water film on the surface acts as a lubricant between the two surfaces [28.21]. Thus the interface is changed at higher humidities, resulting in lower shear strength and, hence, lower friction force and coefficient of friction.

Figure 28.18b shows adhesive forces as a function of tip radius and relative humidity on Si(100) coated with 0.5-nm-thick Z-DOL(BW) film. Adhesive forces for all the tips with the Z-DOL(BW) lubricated sample are much lower than those experienced on unlubricated Si(100), shown in Fig. 28.18a. The data also show that even at a monolayer thickness of the lubricant there is very little variation in adhesive forces with tip radius at a given humidity. For a given tip radius, the variation in adhesive forces with relative humidity indicates that these forces slightly increase from RH 0% to RH 45%, but remain more or less the same with a further increase in humidity. This is seen even with the largest tip, which indicates that the lubricant is indeed hydrophobic; there is some meniscus formation at humidities higher than RH 0%, but the formation is very minimal and does not increase appreciably even up to RH 65%. Figure 28.18b also shows coefficient of friction for various tips at different humidities for the Z-DOL(BW) lubricated sample. Again, all the values obtained with the lubricated sample are much lower than the values obtained on unlubricated Si(100), shown in Fig. 28.18a. The coefficient of friction increases with tip radius for all humidities, as was seen on unlubricated Si(100), due to an increase in the contact area. Similar to the adhesive forces, there is an increase in friction from RH 0% to RH 45%, due to a contribution from an increased number of menisci bridges. But thereafter there is very little additional water film forming, due to the hydrophobicity of the Z-DOL(BW) layer, and, consequentially, the coefficient of friction does not change appreciably, even with the largest tip. These findings show that even a monolayer of Z-DOL(BW) offers good hydrophobic performance of the surface.

28.3.6 Wear Study

To study the durability of lubricant films at the nanoscale, the friction of Si(100), Z-15, and Z-DOL(BW) as a function of the number of scanning cycles was measured, Fig. 28.19 [28.21]. As observed earlier, friction force and coefficient of friction of Z-15 is higher than that of Si(100), and Z-DOL(BW) has the lowest values. During cycling, friction force and coefficient of friction of Si(100) show a slight variation during the initial few cycles then remain constant. This is related to the removal of the top adsorbed layer. In the case of Z-15 film, the friction force and coefficient of friction show an increase during the initial few cycles and then approach higher and stable values. This is believed to be caused by the attachment of the Z-15 molecules onto the tip. The molecular interaction between these attached molecules to the tip and molecules on the film surface is responsible for an increase in the friction. But after several scans, this molecular interaction reaches the equilibrium, and after that, friction force and coefficient of friction remain constant. In the case of Z-DOL(BW) film, the friction force and coefficient of friction start out low and remain low during the entire test for 100 cycles. It suggests that Z-DOL(BW) molecules do not get attached or displaced as readily as Z-15.



Fig. 28.20 Wear depth as a function of normal load using a diamond tip for Si(100), 2.9-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) after one cycle [28.20]



Fig. 28.21 Wear profiles for Si(100), 2.9-nm-thick Z-15 film, and 2.3-nm-thick Z-DOL(BW) film after wear studies using a diamond tip. Normal force used and wear depths are listed in the figure [28.20]

Koinkar and *Bhushan* [28.20, 34] conducted wear studies using a diamond tip at high loads. Figure 28.20 shows the plots of wear depth as a function of normal force, and Fig. 28.21 shows the wear profiles of the worn samples at 40 µN normal load. The 2.3-nm-thick Z-DOL(BW) lubricated sample exhibits better wear resistance than unlubricated and 2.9-nm-thick Z-15 lubricated silicon samples. Wear resistance of a Z-15 lubricated sample is little better than that of unlubricated sample. The Z-15 lubricated sample shows debris inside the wear track. Since the Z-15 is a liquid lubricant, debris generated is held by the lubricant and they become sticky. The debris moves inside the wear track



Fig. 28.22 Friction force as a function of number of cycles using a Si_3N_4 tip at a normal load of 300 nN for Z-DOL(BW) and Z-DOL(BUW) films with different film thicknesses [28.34]

and does damage, Fig. 28.20. These results suggest that using Z-DOL(BW) can improve the wear resistance of substrate.

To study the effect of the degree of chemical bonding, the durability tests were conducted on both fully bonded and partially bonded Z-DOL films. Durability results for Z-DOL(BW) and Z-DOL bonded and unwashed (Z-DOL(BUW), a partially bonded film that contains both bonded and mobile phase lubricants) with different film thicknesses are shown in Fig. 28.22 [28.34]. Thicker films, such as Z-DOL(BUW), with a thickness of 4.0 nm (bonded/mobile = 2.3 nm/1.7 nm) exhibit behavior similar to 2.3-nm-thick Z-DOL(BW) film. Figure 28.22 also indicates that Z-DOL(BW) and Z-DOL(BUW) films with a thinner film thickness exhibit a higher friction value. Comparing 1.0-nm-thick Z-DOL(BW) with 3.0-nm-thick Z-DOL(BUW) (bonded/mobile = 1.0 nm/2.0 nm), the Z-DOL(BUW) film exhibits a lower and stable friction value. This is because the mobile phase on a surface acts as a source of lubricant replenishment. A similar conclusion has also been reported by *Ruhe* et al. [28.19], *Bhushan* and *Zhao* [28.13], and *Eapen* et al. [28.49]. All of them indicate that using partially bonded Z-DOL films can dramatically reduce the friction and improve the wear life.

28.4 Closure

Nanodeformation study has shown that fully bonded Z-DOL lubricants behave as soft polymer solids, while the unbonded lubricants behave liquid-like. AFM studies have shown that the physisorbed nonpolar molecules on a solid surface have an extended, flat conformation. The spreading property of PFPE is strongly dependent on the molecular end groups and substrate chemistry.

Using solid-like Z-DOL(BW) film can reduce the friction and adhesion of Si(100), while using liquid-like lubricant of Z-15 shows a negative effect. Si(100) and Z-15 film show apparent time effect. The friction and adhesion forces increase as a result of growth of meniscus up to an equilibrium time, after which they remain constant. Using Z-DOL(BW) film can prevent time effects. High velocity leads to the rupture of meniscus and prevents its reformation, which leads to a decrease of friction and adhesive forces of Z-15 and Z-DOL(BW). The influence of relative humidity on the friction and adhesion is dominated by the amount of the adsorbed water molecules. Increasing humidity can either increase friction through increased adhesion by water meniscus, or reduce friction through an enhanced water-lubricating effect. Increasing temperature leads to desorption of water layer, decrease of water surface tension, decrease of viscosity, and easier orientation of the Z-DOL(BW) molecules. These changes cause a decrease of friction force and adhesion at high temperature. During cycling tests, the molecular interaction between the attached Z-15 molecules to the tip and the Z-15 molecules on the film surface causes the initial rise of friction. Wear tests show that Z-DOL(BW) can improve the wear resistance of silicon. Partially bonded PFPE film appears to be more durable than fully bonded films.

These results suggest that partially/fully bonded films are good lubricants for devices operating in different environments and under varying conditions.

References

28.1 B. Bhushan: Magnetic Recording Surfaces. In: *Characterization of Tribological Materials*, ed. by W. A. Glaeser (Butterworth-Heinemann, Boston 1993) pp. 116–133
28.2 B. Bhushan: *Principles and Applications of Tribology* (Wiley, New York 1999)
28.3 B. Bhushan: *Introduction to Tribology* (Wiley, New York 2002)
28.4 V. J. Novotny, I. Hussla, J. M. Turlet, M. R. Philpott: Liquid polymer conformation on solid surfaces, J. Chem. Phys. **90** (1989) 5861–5868
28.5 V. J. Novotny: Migration of liquid polymers on solid surfaces, J. Chem. Phys. **92** (1990) 3189–3196
28.6 C. M. Mate, V. J. Novotny: Molecular conformation and disjoining pressures of polymeric liquid films, J. Chem. Phys. **94** (1991) 8420–8427
28.7 C. M. Mate: Application of disjoining and capillary pressure to liquid lubricant films in magnetic recording, J. Appl. Phys. **72** (1992) 3084–3090
28.8 G. G. Roberts: *Langmuir–Blodgett Films* (Plenum, New York 1990)
28.9 A. Ulman: *An Introduction to Ultrathin Organic Films* (Academic, Boston 1991)
28.10 B. Bhushan: *Tribology and Mechanics of Magnetic Storage Devices*, 2nd edn. (Springer, New York 1996)
28.11 B. Bhushan: Macro- and microtribology of magnetic storage devices. In: *Modern Tribology Handbook Vol. 2: Materials, Coatings, and Industrial Applications*, ed. by B. Bhushan (CRC, Boca Raton 2001) pp. 1413–1513
28.12 Anonymous: Fomblin Z Perfluoropolyethers, Data sheet Montedism Group, Milan (2002)
28.13 B. Bhushan, Z. Zhao: Macroscale and microscale tribological studies of molecularly thick boundary layers of perfluoropolyether lubricants for magnetic thin-film rigid disks, J. Info. Storage Proc. Syst. **1** (1999) 1–21
28.14 B. Bhushan: *Tribology Issues and Opportunities in MEMS* (Kluwer, Dordrecht 1998)
28.15 B. Bhushan, J. N. Israelachvili, U. Landman: Nanotribology: Friction, wear and lubrication at the atomic scale, Nature **374** (1995) 607–616
28.16 B. Bhushan: *Handbook of Micro/Nanotribology*, 2nd edn. (CRC, Boca Raton 1999)
28.17 B. Bhushan: Self-assembled monolayers for controlling hydrophobicity and/or friction and wear. In: *Modern Tribology Handbook Vol. 2: Materials, Coatings, and Industrial Applications*, ed. by B. Bhushan (CRC, Boca Raton 2001) pp. 909–929
28.18 J. Ruhe, G. Blackman, V. J. Novotny, T. Clarke, G. B. Street, S. Kuan: Thermal attachment of perfluorinated polymers to solid surfaces, J. Appl. Polym. Sci. **53** (1994) 825–836
28.19 J. Ruhe, V. Novotny, T. Clarke, G. B. Street: Ultrathin perfluoropolyether films – influence of anchoring and mobility of polymers on the tribological properties, ASME J. Tribol. **118** (1996) 663–668
28.20 V. N. Koinkar, B. Bhushan: Microtribological studies of unlubricated and lubricated surfaces using atomic force/friction force microscopy, J. Vac. Sci. Technol. A **14** (1996) 2378–2391
28.21 H. Liu, B. Bhushan: Nanotribological characterization of molecularly-thick lubricant films for applications to MEMS/NEMS by AFM, Ultramicroscopy **97** (2003) 321–340
28.22 G. S. Blackman, C. M. Mate, M. R. Philpott: Interaction forces of a sharp tungsten tip with molecular films on silicon surface, Phys. Rev. Lett. **65** (1990) 2270–2273
28.23 G. S. Blackman, C. M. Mate, M. R. Philpott: Atomic force microscope studies of lubricant films on solid surfaces, Vacuum **41** (1990) 1283–1286
28.24 X. Ma, J. Gui, K. J. Grannen, L. A. Smoliar, B. Marchon, M. S. Jhon, C. L. Bauer: Spreading of PFPE lubricants on carbon surfaces: Effect of hydrogen and nitrogen content, Tribol. Lett. **6** (1999) 9–14
28.25 C. A. Kim, H. J. Choi, R. N. Kono, M. S. Jhon: Rheological characterization of perfluoropolyether lubricant, Polym. Prepr. **40** (1999) 647–649
28.26 M. Ruths, S. Granick: Rate-dependent adhesion between opposed perfluoropoly(alkylether) layers: Dependence on chain-end functionality and chain length, J. Phys. Chem. B **102** (1998) 6056–6063
28.27 U. Jonsson, B. Bhushan: Measurement of rheological properties of ultrathin lubricant films at very high shear rates and near-ambient pressure, J. Appl. Phys. **78** (1995) 3107–3109
28.28 C. Hahm, B. Bhushan: High shear rate viscosity measurement of perfluoropolyether lubricants for magnetic thin-film rigid disks, J. Appl. Phys. **81** (1997) 5384–5386
28.29 C. M. Mate: Atomic-force-microscope study of polymer lubricants on silicon surface, Phys. Rev. Lett. **68** (1992) 3323–3326
28.30 C. M. Mate: Nanotribology of lubricated and unlubricated carbon overcoats on magnetic disks studied by friction force microscopy, Surf. Coat. Technol. **62** (1993) 373–379
28.31 S. J. O'Shea, M. E. Welland, T. Rayment: Atomic force microscope study of boundary layer lubrication, Appl. Phys. Lett. **61** (1992) 2240–2242
28.32 S. J. O'Shea, M. E. Welland, J. B. Pethica: Atomic force microscopy of local compliance at solid–liquid interface, Chem. Phys. Lett. **223** (1994) 336–340

28.33 B. Bhushan, T. Miyamoto, V.N. Koinkar: Microscopic friction between a sharp diamond tip and thin-film magnetic rigid disks by friction force microscopy, Adv. Info. Storage Syst. **6** (1995) 151–161
28.34 V. N. Koinkar, B. Bhushan: Micro/nanoscale studies of boundary layers of liquid lubricants for magnetic disks, J. Appl. Phys. **79** (1996) 8071–8075
28.35 B. Bhushan, S. Sundararajan: Micro/nanoscale friction and wear mechanisms of thin films using atomic force and friction force microscopy, Acta Mater. **46** (1998) 3793–3804
28.36 B. Bhushan, C. Dandavate: Thin-film friction and adhesion studies using atomic force microscopy, J. Appl. Phys. **87** (2000) 1201–1210
28.37 S. Sundararajan, B. Bhushan: Static friction and surface roughness studies of surface micromachined electrostatic micromotors using an atomic force/friction force microscope, J. Vac. Sci. Technol. A **19** (2001) 1777–1785
28.38 B. Bhushan, J. Ruan: Atomic-scale friction measurements using friction force microscopy: Part II – application to magnetic media, ASME J. Tribol. **116** (1994) 389–396
28.39 T. Stifter, O. Marti, B. Bhushan: Theoretical investigation of the distance dependence of capillary and van der Waals forces in scanning probe microscopy, Phys. Rev. B **62** (2000) 13667–13673
28.40 J. N. Israelachvili: *Intermolecular and Surface Forces*, 2nd edn. (Academic, London 1992)
28.41 S. K. Chilamakuri, B. Bhushan: A comprehensive kinetic meniscus model for prediction of long-term static friction, J. Appl. Phys. **15** (1999) 4649–4656
28.42 H. Ishigaki, I. Kawaguchi, M. Iwasa, Y. Toibana: Friction and wear of hot pressed silicon nitride and other ceramics, ASME J. Tribol. **108** (1986) 514–521
28.43 T. E. Fischer: Tribochemistry, Annu. Rev. Mater. Sci. **18** (1988) 303–323
28.44 K. Mizuhara, S. M. Hsu: Tribochemical reaction of oxygen and water on silicon surfaces. In: *Wear Particles*, ed. by D. Dowson (Elsevier, New York 1992) pp. 323–328
28.45 S. Danyluk, M. McNallan, D. S. Park: Friction and wear of silicon nitride exposed to moisture at high temperatures. In: *Friction and Wear of Ceramics*, ed. by S. Jahanmir (Dekker, New York 1994) pp. 61–79
28.46 V. A. Muratov, T. E. Fischer: Tribochemical polishing, Annu. Rev. Mater. Sci. **30** (2000) 27–51
28.47 H. Yoshizawa, Y. L. Chen, J. N. Israelachvili: Fundamental mechanisms of interfacial friction I: Relationship between adhesion and friction, J. Phys. Chem. **97** (1993) 4128–4140
28.48 H. Yoshizawa, J. N. Israelachvili: Fundamental mechanisms of interfacial friction II: Stick slip friction of spherical and chain molecules, J. Phys. Chem. **97** (1993) 11300–11313
28.49 K. C. Eapen, S. T. Patton, J. S. Zabinski: Lubrication of microelectromechanical systems (MEMS) using bound and mobile phase of Fomblin Z-DOL, Tibol. Lett. **12** (2002) 35–41

29. Kinetics and Energetics in Nanolubrication

Lubrication, one of human kind's oldest engineering disciplines, in the 19th century gained from Reynolds' classical hydrodynamic description a theoretical base unmatched by most of the theories developed in tribology to date. In the 20th century, however, increasing demands on lubricants shifted the attention from bulk film to ultrathin film lubrication. Finite size limitations imposed constraints on the lubrication process that were not considered in bulk phenomenological treatments introduced by Reynolds. At this point, as is common in many engineering applications, empiricism took over. Functional relationships derived from the classical theories were tweaked to accommodate the new situation of reduced scales by introducing "effective" or "apparent" properties.

With the inception of nanorheological tools of complementary nature in the later decades of the 20th century (e.g., the surface forces apparatus and scanning force microscopy), tribology entered the realm of nanoscience. Through an increasing confidence in experimental findings on the nanoscale, kinetic and energetic theories incorporated interfacial and molecular constraints.

The very fundamentals have been challenged in recent years. Researchers have realized that bulk perceptions, such as "solid" and "liquid" are defied on the nanoscale. The reduction in dimensionality of the nanoscale imposes constraints that bring into question the use of classical statistical mechanics of decoupled events. The diffusive description of lubrication is failing in a system that is thermodynamically not well-equilibrated.

The challenge any nanotechnological endeavor encounters is the development of a theoretical framework based on an appropriate statistics. In tribology this is met with spectral descriptions of the dynamic sliding process. Statistical kernels are being developed for probability density functions to explain anomalous transport processes that involve long-range spatial or temporal correlations. With such theoretical developments founded in nanorheological experiments, a more realistic foundation will be laid to describe the behavior of lubricants in the confined geometries of the nanometer length scale.

29.1 **Background: From Bulk to Molecular Lubrication** 885
  29.1.1 Hydrodynamic Lubrication and Relaxation 885
  29.1.2 Boundary Lubrication 885
  29.1.3 Stick Slip and Collective Phenomena 885

29.2 **Thermal Activation Model of Lubricated Friction** 887

29.3 **Functional Behavior of Lubricated Friction** 888

29.4 **Thermodynamical Models Based on Small and Nonconforming Contacts** ... 890

29.5 **Limitation of the Gaussian Statistics – The Fractal Space** 891

29.6 **Fractal Mobility in Reactive Lubrication** .. 892

29.7 **Metastable Lubricant Systems in Large Conforming Contacts** 894

29.8 **Conclusion** 895

References 895

What is inaccessible today may become accessible tomorrow as has happened by the invention of the microscope. ... Coherent assumptions on what is still invisible may increase our understanding of the visible. ... Strong reasons have come to support a growing probability, and it can finally be said the certainty, in favor of the hypothesis of the atomists. (Jean Baptiste Perrin – Nobel Lecture, December 11, 1926)

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Since technology is driving lubricant films to molecular thickness, kinetic friction and its dependence on the sliding parameters – especially the sliding velocity – have become of great interest. The complexity of the frictional resistance in lubricated sliding is illustrated in Fig. 29.1 with a *Stribeck Curve*. Various regimes of lubrication can be identified in the Stribeck curve. They express to what degree the hydrodynamic pressure is involved in the lubrication process. In the ultra-low speed regime, called the *boundary lubrication regime*, no hydrodynamic pressure is built up in the lubricant. Consequently the load is carried by contact asperities coated with adsorbed lubricant molecules. If the speed is raised, a hydrodynamic pressure builds that leads to a *mixed lubrication*, in which the load is carried by both asperities and hydrodynamic pressure. At even higher speeds, elastic contributions of the solid surfaces have to be considered paired with hydrodynamic pressure effects (elastohydrodynamic lubrication), until only *hydrodynamic lubrication* matters. Hence, the Stribeck curve combines various aspects of lubrication. The curve cannot be discussed without considering the lubricant thickness and the different models of asperity contact sliding.

In one of the first comprehensive physical models of "dry" friction, Bowden and Tabor introduced a plastic asperity model, in which the material's yield stress and adhesive properties play an important role [29.1]. Considering this model, which depends on surface energies and mechanical yield properties paired with all the properties that come along with a surface adsorbent lubricant, one can hardly grasp the difficulty level involved in describing the frictional kinetics in lubrication.



Fig. 29.1 Stribeck Curve (schematic) relates the fluid lubricant thickness, δ, and the friction coefficient μ to the Gumbel Number $N_G = \eta\omega P^{-1}$; i.e., the product of the liquid bulk viscosity, η, the sliding speed (or more precisely the shaft frequency), ω, and the inverse of the normal pressure, P. BL: Boundary Lubrication, ML: Mixed Lubrication, EHL: Elastohydrodynamic Lubrication, HL: Hydrodynamic Lubrication

Past and current engineering challenges in lubrication have been met with great and complex empiricism. The theoretical modeling of lubrication junctions generally involved only bulk property considerations with inadequately known adsorption mechanisms. The complexity of today's lubricants, most of them, such as motor oil, a product of empirical design over many years, increased exponentially, making it very difficult to meet future challenges. The problem of empiricism is that conventional laws and perceptions are unchallenged. *Effective* quantities are invented (e.g., effective viscosity), exponential fitting parameters are introduced (e.g., Kohlrausch relaxation parameter), and terminologies such as *solid* and *liquid* are taken as granted. Progress based on empiricism is only incremental and rarely revolutionary.

One of the reasons for empiricism is a lack of access to a system with fewer and better controlled parameters. In lubrication sliding that challenge has been addressed over the last two decades with the inception of the surface forces apparatus (SFA) by *Tabor* et al. [29.2] and scanning force microscopy (SFM) by *Binnig* et al. [29.3]. These two instrumental methods allow lubrication studies where roughness effects can be neglected, surface energies controlled, and wear from wearless friction distinguished. Lubricant properties can be studied at nearly mathematically described boundaries, atomistic friction events can be recorded, and fundamental models that have been considered to be mere Gedanken Experiments, such as the *Tomlinson model of friction*, can be verified. In the wake of these nanoscopic tools, exciting new theoretical lubrication and friction models have appeared.

This chapter considers these recent experimental and theoretical developments with a particular focus on sliding speed and real or apparent changes in the lubricant material properties. We will discuss kinetics and energetics in the "simplified" world of nanolubrication, in which our conventional perception is challenged. After a brief review of some of the classical lubrication concepts (hydrodynamic lubrication and boundary lubrication), we will turn our attention to a thermal activation model of friction, functional behavior of lubricated friction with velocity, and models based on small non-conforming contacts. We will critically discuss the limitation of the underlying Gaussian statistics, introduce fractal dynamics in lubrication, and will end our discussion with metastable lubricant systems.

29.1 Background: From Bulk to Molecular Lubrication

29.1.1 Hydrodynamic Lubrication and Relaxation

In the classical theories of tribology by da Vinci, Amonton, and Coulomb, not much attention was given to the dependence of kinetic friction on the sliding velocity. This clearly changed in the 19th century during the first industrial revolution, at which time lubricants became increasingly important, for instance, in ball and journal bearings. It was *Petrov* [29.4], *Tower* [29.5], and *Reynolds* [29.6] who established that the liquid viscous shear properties determine the frictional kinetics. *Reynolds* [29.6] combined the pressure-gradient determined *Poisseuille flow* with the bearing surface induced *Couette flow* assuming, based on Petrov's law [29.4], a no-slip condition at the interface between lubricant and solid. This led to the widely used linear relationship between friction and velocity. Reynolds' hydrodynamic theory of lubrication can be applied to steady state sliding at constant relative velocity and to transient decay sliding (sliding is stopped from an initial velocity v and a corresponding shear stress τ_0), which leads to the classical Debye exponential relaxation behavior, i. e.:

$$\tau = \tau_0 \exp\left(\frac{-D}{A\eta}t\right) \; ; \quad \tau_0 \propto \frac{v\eta}{D} \, . \tag{29.1}$$

D is the lubricant thickness, A the area of the slider, and η the viscosity of the fluid. We will later see that this classical exponential relaxation behavior, obtained in a thermodynamically well-mixed three dimensional medium, is distorted when the liquid film thickness is reduced to molecular dimensions.

29.1.2 Boundary Lubrication

Reynolds hydrodynamic description of lubrication was found to work well for thick lubricant films but to break down for thinner films. One manifestation is that for films on the order of ten molecular diameters, the stress in the film does not allow the tension to return to zero. It was also found that the motion in the steady state sliding regime was disrupted, exhibiting a stick–slip-like slider motion [29.7]). Consequently, this non-Newtonian behavior was treated with a modified viscosity parameter (effective viscosity), which was composed of the pressure, temperature, and rate of shear.

The term *Boundary Lubrication* is used to describe a lubricant that is reduced in thickness to molecular dimension and effectively reduces friction between two opposing solid surfaces. *Hardy* et al. [29.8] recognized that molecular properties such as molecular weight and molecular arrangement, are governing the frictional force. This confined concept of lubrication, often visualized by two highly ordered opposing films with shear taking place somewhere in between the two layers, contains many of the rate dependent manifestations of frictional sliding; e.g., stick–slip, ultra-low friction, transitions from high to low friction, phase transitions, dissipation due to dislocations (e.g., gauche and cis-transformations), and memory effects.

Boundary lubrication was found to be in many respects unique [29.9]. In macroscopic experiments, which involved rough surfaces, friction–velocity plots resembled logarithmic functions at moderate speeds. No static stiction force peaks were observed in boundary lubricants close to zero speed. On the contrary, retractive slips could be observed upon halting, constituting a static friction coefficient exceeded by the dynamic friction coefficient [29.9]. These unique manifestations of boundary lubrication were discussed in terms of a lubricated asperity–junction mechanism, which associated "an increase in the coefficient of friction with a decrease in the adsorptive coverage of the rubbing surfaces by the lubricant substance" [29.9]. It was argued that in the course of the sliding process of a macroscopic slider, more adsorbed lubricant is expected to exist within the interfacial area than outside the contact zone. This would lead upon halting to a relaxation process of the elastic restraints on the slider, causing the slider to a retractively slip.

29.1.3 Stick Slip and Collective Phenomena

Based on numerous friction experiments at the initiation of sliding with rough macroscopic contact, it was argued that the distinction between static and kinetic friction is not categorical but rather a manifestation of the apparatus [29.9]. This was a widely held opinion prior to *Briscoe*'s et al. [29.10] molecularly smooth monolayer SFA experiments of aliphatic carboxylic acids and their soaps. Briscoe found that the character of sliding motion (continuous vs. discontinuous), depends not only on the apparatus but also on the properties (chemistry) of the monolayer. As in the rough boundary layer experiments discussed above, Briscoe's molecularly smooth monolayer experiments exhibited logarithmic-like friction–velocity behaviors.



Fig. 29.2 **(a)** SFM friction measurements at a speed 1 μm/s: Cooperative molecular response of polyethylene co-propylene to frictional shear forces as a function of the applied load. P_t (t corresponds to the thickness of the polymer film) represents the critical activation load at which collective sliding is energetically more favorable than local plastic yielding. Adapted from [29.11]. **(b)** Sketch of the degree of disentanglement in the vicinity to the solid substrate surface

It was *Israelachvili* et al. [29.7] who, based on SFA experiments and computer simulations, provided a molecular picture of the stick–slip behavior caused by the lubricant material. The major achievement of this work was to draw our attention to the molecular structure of the lubricant, which is often different from the bulk and unstable during the sliding motion. It was recognized that bulk rheology failed to describe the lubrication process. Finally addressed in the Israelachvili study were in-plane structuring of simple liquids caused by compression forces and "freezing–melting" transitions due to shear.

The simple concept of a freezing–melting transition is based on a common perception of the two distinctive parts of a stick–slip occurrence: the solid (Hookian)-like sticking part and the liquid (Newtonian)-like slipping part. But a deformation of a solid can be both, coordinated or uncoordinated, and thus can exhibit both solid-like and liquid-like behavior. For instance, most of the plastic yielding processes are uncoordinated. On the other hand, slipping within a solid, along a crystal plane in a thermally activated strain-release process for instance, is a highly coordinated molecular process [29.12].

Similar arguments can be made for a liquid. For example, stick–slip behaviors were observed in more complex fluidic systems by *Reiter* et al. [29.13], who compared a molecularly "wet" lubricant film with a "dry" self-assembled monolayer lubricant. They concluded that sliding in liquid films is the result of slippage along an interface. In other words, the degree of molecular cooperation determined the frictional resistance.

The concept of local-*versus*-cooperative yield to shear is briefly illustrated here with a frictional-load study of a molecularly entangled polymer melt obtained in a SFM study of *Buenviaje* et al. [29.11]. Each of the curves presented in Fig. 29.2a represents a polymer film of polyethylene co-propylene of distinctly different degree of entanglement. Films of thickness above 230 nm exhibit the strongest entanglement strength. Films of 20 nm thickness or thinner are fully disentangled. The reason for the film thickness-dependent entanglement strength is given by the substrate distance-dependent shear strength during the spin coating process of the thin films. For entangled films SFM friction studies exhibit a critical applied load (identified by P_t, and the thickness t) that separates two friction regimes: One identified by a high friction coefficient and the other by a low friction coefficient. At loads below P_t the friction coefficients are high, indicating plastic yielding during sliding. In these plastic regimes of sliding, molecular cooperation is low, leading to high local shear stresses compensated by local yielding of the material. Above the critical load, the friction coefficient drops, independent of the film thickness, to a low value of 3.0, corresponding to the value obtained from the fully disentangled film. Note that the polymer molecules in the 20-nm-thick film experience high substrate tangential stresses during the spin coating process. Hence the disentangled polymer molecules can be considered to be aligned preferentially along the substrate surface as sketched in Fig. 29.2b. This leads to a decrease of the structural entropy the closer the material is to the solid substrate surface. Considering the matching friction coefficient of 0.3 above P_t for thicker films, we can assume that any entangled film above a critical load exhibits a similar molecular collective response toward shear as the 20 nm film during spin coating. The critical load and its related pressure represent a barrier that has to be overcome before a collective phenomenon is activated.

29.2 Thermal Activation Model of Lubricated Friction

With the discussion of shear in entangled polymer systems we have introduced structural entropy as one of the key players that affect frictional resistance in lubricants. We found that the structural entropy was affected by the load of the slider, which introduces an activation barrier in the form of a critical pressure. The terminology used here resembles the one of the Eyring theory of molecular liquid transport [29.14].

Eyring discussed a pure liquid at rest in terms of a thermal activation model. The individual liquid molecules experience a "cage-like" barrier that hinders molecular free motion, because of the close packing in liquids. To escape from the cage an activation barrier needs to be surmounted. In Eyring's model, two processes are considered in order to overcome the potential barrier: (i) shear stresses and (ii) thermal fluctuations. The potential barrier in the thermal activation model is depicted in Fig. 29.3 indicating the barrier modification by the applied pressure force P, and shear stress τ. *Briscoe* et al. [29.10] picked up on this idea to interpret the frictional behavior observed on molecularly smooth monolayer systems. Starting from the overall barrier height $E = Q + P\Omega - \tau\phi$ that is repeatedly overcome during a discontinuous sliding motion, using a Boltzmann distribution to determine the average time for single molecular barrier-hopping, and assuming a regular series of barriers and a high stress limit ($\tau\Phi/kT > 1$), the following shear strength versus velocity v relationship was derived [29.10]:

$$\tau = \frac{k_B T}{\phi} \ln\left(\frac{v}{v_0}\right) + \frac{1}{\phi}(Q + P\Omega) . \tag{29.2}$$

The barrier height, E, is composed of the process activation energy Q, the compression energy $P\Omega$, where P is the pressure acting on the volume of the junction Ω, and the shear energy $\tau\phi$, where τ is the shear strength acting on the stress activation volume ϕ. T represents the absolute temperature. The stress activation volume ϕ can be conceived as a process coherence volume and interpreted as the size of the moving segment in the unit shear process, whether it is a part of a molecule or a dislocation line. The most critical parameter in (29.2), v_0, is a characteristic velocity related to the frequency of the process and to a jump distance (discussed further below).

From (29.2) the following iso-relationships can be directly deduced [29.10]:

$$\begin{aligned}
&\tau = \tau_0 + \alpha P ; \quad \tau_0 = \frac{1}{\phi}\left(k_B T \ln\left(\frac{v}{v_0}\right) + Q\right) ; \\
&\alpha = \frac{\Omega}{\phi} ; \text{ at constant } v, T , \qquad (29.3a)\\
&\tau = \tau_1 - \beta T ; \quad \tau_1 = \frac{1}{\phi}(Q + P\Omega) ; \\
&\beta = -\frac{k}{\phi} \ln\left(\frac{v}{v_0}\right) , \quad \text{at constant } P, v , \qquad (29.3b)\\
&\tau = \tau_2 + \theta \ln v ; \quad \tau_2 = \frac{1}{\phi}(Q + P\Omega - kT \ln v_0) ; \\
&\theta = \frac{kt}{\phi} , \quad \text{at constant } P, T . \qquad (29.3c)
\end{aligned}$$

Thus Eyring's model predicts a linear relationship of friction (the product of the shear strength and the active process area) in pressure and temperature and a logarithmic relationship in velocity.

Eyring's model has been verified in lubrication experiments of solid (soap-like) lubricants by Briscoe and liquid lubricants by *He* et al. [29.15] within



Fig. 29.3 Potential barrier in a lubricant based on Eyring's thermodynamic "cage-model." The normal pressure P and the shear stress τ are modifying the barrier height Q. Modified from [29.10]

Fig. 29.4 (a) Logarithmic $F_F(v)$-plots. $F_F(v) = F_0 + \alpha \ln(v[\mu\mathrm{m/s}])$: ● "dry" contact (18% relative humidity) with $F_0 = 16.4\,\mathrm{nN}$ and $\alpha = 0.91\,\mathrm{nN}$, △ OMCTS lubricated with $F_0 = 11.3\,\mathrm{nN}$ and $\alpha = 3.4\,\mathrm{nN}$, and ■ n-hexadecane (n-$C_{16}H_{34}$) lubricated with $F_0 = 7.1\,\mathrm{nN}$ and $\alpha = 2.5\,\mathrm{nN}$. The measurements were obtained with rectangular SFM cantilevers (0.4–0.8 N/m) at 100 nN load and 21 °C, both feedback-controlled. **(b)** Stress activation length, ϕ/A. (A area of contact) for OMCTS, n-hexadecane and dry contact. The *inset* provides a linear relationship between friction and temperature at a velocity of 1 µm/s and a normal load of 100 nN. Adapted from [29.15]



three logarithmic decades of velocities. While *Briscoe* et al. [29.10] employed a SFA that confines and pressurizes the film over several square microns, He et al. used a SFM system in which the contact is on the order of the lubricant molecular dimension.

He et al. determined the degree of interfacial structuring and its effect on lubrication of n-hexadecane and octamethylcyclotetrasiloxane (OMCTS). For spherically shaped OMCTS molecules, only an interfacial "monolayer" was found; in contrast, a 2-nm-thick entropically cooled layer was detected for n-hexadecane in the boundary regime to an ultra-smooth silicon wafer. SFM measurements of the two lubricants (with similar chemical affinity to silicon) identified the molecular shape of n-hexadecane responsible for augmented interfacial structuring. Consequently, interfacial liquid structuring was found to reduce lubricated friction, Fig. 29.4. Again as reasoned above, these results can be discussed in terms of a collective phenomenon, i. e., in terms of increased molecular coordination in n-hexadecane versus OMCTS.

29.3 Functional Behavior of Lubricated Friction

Friction-rate experiments are well suited to evaluate the rheological nature of interfacial liquids. In classical theories, such as the Reynolds' hydrodynamic theory discussed above, drag forces in lubricated sliding over thick liquid films were found to depend linearly on the rate of sliding and on the viscosity of the bulk fluid. In high-pressure lubrication, described by the elastohydrodynamic lubrication theory [29.16, 17], it was found that the linear relationship between friction and velocity can be retained by adjusting the (apparent) viscosity by introducing an *apparent viscosity term*. Qualitatively, the same linear relationship has been observed for highly confined simple liquids between ultrasmooth mica surfaces such as alkanes [29.18]. Note that the lubricated contact area in SFA experiments is on the micron-scale. It significantly exceeds the size of the confined molecules. For small and unbranched molecules, such as simple alkanes, it is possible that the confined material undergoes a pressure-induced phase reconstruction, which leads to material properties that deviate significantly from the bulk. Larger and more complex (branched) molecules are less likely to exhibit pressure-induced phase reconstruction due to internal constraints and poor mixing within the contact area. This was shown by *Drummond* et al. [29.19] in SFA shear experiments. They found that the linear friction–velocity dependence does not apply for branched hydrocarbon lubricants. Also Drummond discussed "molecular lubrication" in terms of a logarithmic friction–velocity relationship, which is in accordance with the above-discussed thermal activation model, the solid lubricant SFA study by *Briscoe* et al. [29.10], and the liquid lubricant SFM study by *He* et al. [29.15].

Common to the three studies by *Briscoe*, *He*, and *Drummond* is that they operate on a single material phase that is disrupted or relaxed over a very specific lateral length scale. In the Eyring model, the length scale is deduced by assuming a regular series of barriers, separated by a *virtual jump distance*. The distance is embedded in v_0, the characteristic velocity, which is the product of the jump distance and the frequency of the process. *Briscoe* et al. [29.10] used the lattice constant of the highly oriented monolayers as the virtual jump distance. It was assumed that the process frequency was related to the vibrational frequency of the molecules ($10^{11}\ \mathrm{s}^{-1}$), neglecting sliding velocity, temperature, and pressure effects. *He* et al. [29.15] assumed a jump distance of 0.2 nm and considered frequencies between a perfectly structured alkane layer (10^{11} Hz) and the bulk fluid (10^{13}–10^{15} Hz, estimated from infrared absorption data for typical covalent bonds). With these assumptions *He* determined total "jump-energies" of $4–8 \times 10^{-20}$ J. *Briscoe* and *He* pointed out that a friction–velocity study alone provides only a qualitative measure of the microscopic origin of friction. Additional measurements have to be conducted that quantitatively address jump distances and frequencies.

The issue of the jump distance has been addressed by *Overney* et al. [29.20] in a SFM study on a highly ordered lubricant model system. This study avoided two levels of difficulties *Briscoe* et al. [29.10] and *He* et al. [29.15] encountered: (a) large contact areas of SFA studies, and (b) complex rheology with unknown structure parameters as in liquid lubricant studies. It involved contact dimensions on the order of 1 nm^2, and the crystalline form a bilayer model-lipid-lubricant with in-plane lattice spacings of 0.6 and 1.1 nm. The study mainly focused on the effect of the depth of the corrugation potential (barrier height) on the static and dynamic friction force. This is illustrated in Fig. 29.5 in the form of stick–slip amplitude plotted as a function of the drag direction (i. e., sliding with respect to the anisotropic row-like film structure). Relevant to our discussion about jump distance in lubrication events is Overney's discussion about the sliding speed and its effect on the slip distance. They demonstrated that within sliding speeds of 36 nm/s to 100 nm/s, the jump distance corresponded to the lattice spacing. At higher velocities, however, they could observe jumps over multiples of lattice distances and found the jump length distribution to become increasingly stochastic. They proposed molecular (or atomistic) friction as a white-noise driven system, which obeys a Gaussian fluctuation–dissipation relation. Hence, based on this finding one should consider discussing kinetic friction in terms of a statistical fluctuation model and understand the jump distance as a statistical quantity.



Fig. 29.5 SFM molecular stick-slip measurements of a bilayer lipid system (5-(4'-N,N-dihexadecylamino)benzylidene barbituric acid). **(a)** High amplitude frictional stick-slip behavior is observed for scans perpendicular to molecular rows as imaged in **(c)**. F_{st}, static friction, is assigned to the maximum force occurrence. The average value corresponds to the dynamic friction value, F_{dyn}, determined on large-scale micrometer scans. **(b)** A 30° out of row direction scan leads to decreased frictional stick-slip behavior due to smaller molecular corrugations. **(c)** $12 \times 12\ \mathrm{nm}^2$ SFM lateral force image of a highly structured lipid bilayer. Two crystalline domains with a boundary are imaged. The anisotropic row-like structure is responsible for directional dependent friction forces. The molecular corrugation between the rows is larger than the molecular corrugation in between a single row. **(a)** and **(b)** are adapted from [29.20] and **(c)** from [29.21].

29.4 Thermodynamical Models Based on Small and Nonconforming Contacts

The SFM approach simulates a single asperity contact with a very high compliance, provided by a microfabricated and etched ultra-sharp tip and a typically soft cantilever spring. From a realistic, tribological perspective, the SFM approach is targeted toward the study of the intrinsic lubricant properties of a thin film in close vicinity to the solid substrate. The small contact area on the order of the lubricant's molecular dimension allows discussing SFM results in terms of a thermodynamic equilibrium. The area is insufficient in reorganizing the lubricant molecules coherently, to cause an apparent material phase-transition, or to generate a metastable situation as observed in SFA experiments (see below). SFM is therefore not appropriate to reflect on tribological issues involving large area confinement effects.

In our prior molecular discussion of friction above, we introduced for solid and liquid lubrication a thermal activation model, the *Eyring model*, which employed a regular series of potential barriers. Note that the concept applies for a solid lubricant of an inherent, highly ordered structure (e.g., [29.10]), but also for a liquid system in which the series of potentials is built up and overcome in the course of the shear process (e.g., [29.15]).

Gnecco et al. [29.22] showed in a ultrahigh vacuum study on sodium chloride that the concept of the Eyring model also applies for dry SFM friction studies. Thus a molecular theory of lubricated friction involving a molecular contact could be derived from a very simplistic model of an apparent sinusoidal-corrugated surface over which a cantilever tip is pulled. In a first attempt one could assume that the corresponding wave length of the shear process corresponds to the apparent lattice spacing of the corrugated surface. With such a simple attempt it is, however, assumed that there is no noise, such as thermal noise, existing in the system, and thus the driven tip leaves the total potential well when the barrier vanishes at the instability point. In the presence of noise, the transition to sliding can be expected to occur before the top of the barrier is reached. Such barrier-hopping fluctuations have been theoretically discussed by *Sang* et al. [29.23] and *Dudko* et al. [29.24].

The relationship between thermal fluctuations and velocity must be handled thoughtfully. *Sang* et al. [29.23] pointed out that in previous considerations of thermal fluctuations by *Heslot* et al. [29.25], the fluctuations were proportionally related to the velocity, which led to a friction force that is logarithmically dependent on the velocity. In Heslot's *linear creep model*, the barrier height is proportional to the frictional force. *Sang* argued that if one considered an absorbing boundary condition (i. e., an elastic deformation of the overall potential which is accomplished by shifting the x-axis) the barrier height becomes proportional to a $3/2$-power law in the friction force. *Sang*'s extended linear creep model resembles a *ramped creep model* and leads analytically to a logarithmic distorted dynamic friction-*versus*-velocity relationship; i. e.,

$$F = F_\mathrm{c} - \Delta F \left|\ln v^*\right|^{2/3} . \tag{29.4}$$

In (29.4) v^* represents a dimensionless velocity, $\Delta F \propto T^{2/3}$, and F_c is an experimentally determined constant (by plotting F versus $T^{2/3}$ for a fixed ratio $T/v = 1\,\mathrm{K}/(\mathrm{nm}/\mathrm{sec})$) that contains the critical position of the cantilever support. The same relationship of friction with velocity was also derived for the maximum spring force by *Dudko* et al. [29.24]. ΔF and v^* in (29.4) were derived as follows by *Sang*:

$$v^* = 2\left(\frac{v\beta\omega_0^2 U_0}{k_\mathrm{B} T\,\lambda}\right)\frac{\Omega_k^2}{\left(1-\Omega_k^4\right)^{1/2}} ;$$

$$\Omega_k = \frac{\omega_0}{2\pi\omega_k} ;$$

$$\omega_0 = \sqrt{\frac{M\lambda^2}{U_0}} ; \quad \omega_k = \sqrt{\frac{M}{k}} , \tag{29.5a}$$

$$\Delta F = \frac{\pi U_0}{\lambda}\left(\frac{3}{2}\frac{k_\mathrm{B} T}{U_0}\right)^{\frac{2}{3}}\left(\frac{\left(1-\Omega_k^4\right)^{\frac{1}{6}}}{1+\Omega_k^2}\right) . \tag{29.5b}$$

In (29.5a,b) v is the velocity of the cantilever stage, β is the microscopic friction coefficient or dissipation (damping) factor, ω_0 is the frequency of the small oscillations of the tip in the minima of the periodic potential, λ is the lattice constant, U_0 is the surface barrier potential height, M and k represent the mass and the spring constant of the cantilever, respectively, and $2\pi\Omega_k$ represents the ratio of ω_0 with the intrinsic cantilever resonance frequency ω_k.

Sang's and *Dudko*'s model was experimentally confirmed by *Sills* and *Overney* [29.26] on an unstructured amorphous surface of atactic polystyrene, Fig. 29.6. *Dudko* determined that the typically used weak spring constants in SFM measurements are responsible for



Fig. 29.6 Collapse of SFM friction data obtained on atactic polystyrene using the ramped creep scaling model. The regression parameters from the linear fit (*dashed line*) are $-2.158 \times 10^{-2}\,\text{N}^{3/2}\,\text{s/m}$ and $40.186 \times 10^{-2}\,\text{nN}^{-3/2}/\text{K}$ ($R^2 = 0.9124$). Lower *inset*: the constant F_c is determined from the intercept of the friction force F versus $T^{2/3}$ for a fixed ratio $T/v = 1\,\text{K/(nm/s)}$: $F_c = 44.5\,\text{nN}$. (Adapted from *Sills* and *Overney* [29.26])

the more pronounced logarithmic behavior of friction in velocity as found by *Gnecco* et al. [29.22] and *He* et al. [29.15]. The ramped creep model is also supported by numerical solutions of the Langevin equation.

The Langevin equation combines the equation of motion (including the sinusoidal potential and perfect cantilever oscillator in the total potential energy E) with the thermal noise in the form of the random force, $\xi(t)$, i. e.,

$$M\ddot{x} + M\beta\dot{x} + \frac{\partial E(x,t)}{\partial x} = \xi(t)\,, \tag{29.6}$$

$$\text{where } E(x,t) = \frac{k}{2}\,(R(t)-x)^2 - U_0\left(\frac{2\pi x}{\lambda}\right)\,.$$

Equation (29.6) was solved numerically by both *Sang* et al. [29.23] and *Dudko* et al. [29.24] independently, assuming a Gaussian fluctuation–dissipation relation, $\langle\xi(t)\xi(t')\rangle = 2M\beta k_b T\delta(t-t')$ to express the random force. *Sang* confirmed the *ramped creep model*, and *Dudko* showed that a force reconstruction approach from the density of states (accumulated from the corresponding Fokker–Planck equation) is equivalent to the Langevin equation. From the dynamic spectral analysis, it could be concluded that the locked states (states within the potential wells) contribute mostly to the potential component of the friction force that dominates at low driving velocities, and sliding states contribute to viscous friction dominating at high driving velocities [29.24].

It should be noted that all of the above results considered an overdamped SFM system with respect to the driven spring (i. e., $\beta^2 > 4\,\text{kM}$), and an underdamped system with respect to the periodic potential (i. e., $\beta^2 < 4(M\omega)^2$). This aspect will be further addressed below in our discussion of metastable lubricant systems in large conforming contacts.

29.5 Limitation of the Gaussian Statistics – The Fractal Space

The spectral description of dynamic processes involving probability density functions has recently been the focus of numerous theoretical papers that treat various statistical kernels [29.27–30]. *Dudko*'s et al. [29.24] Fokker–Planck discussion of kinetic friction and *Luedtke*'s et al. [29.27] Lévy flight model of slip diffusion of adsorbed nanoclusters are two examples in which statistical methods are applied to describe diffusive properties relevant to the kinetics in tribology.

Currently most models used to describe tribological processes assume Gaussian statistics (e.g., [29.23], and [29.24]). One of the limitations of a Gaussian statistics is that there are no correlations between statistical incidences. In other words, the Gaussian dynamic system is without memory. This is important to remember as the Eyring model discussed above, with its equally spaced potential barriers, used a Gaussian statistics. Simple "inert" lubricants, such as short chain alkanes embedded between silicon wavers, are described satisfactorily with such a statistics; however, confined complex liquids are not, including branched molecules, polymers, and generally chemically interactive and entropically confined systems (e.g., perfluropolyether lubricants as discussed below).

Confined complex liquids, for instance, easily exhibit strongly interacting glass-like behavior. The dynamic and stress relaxation behaviors in glasses, frequently discussed only as a low interacting system with

Arrhenius laws (Gaussian statistics), are often distorted from processes described by independently occurring microscopic processes. For instance, deviations from the Debye exponential relaxation as introduced in (29.1) are expressed in the form of an *extended exponential* Kohlrausch relaxation function over time t; i. e.,

$$F(t) \equiv \left[\frac{X(t) - X(\infty)}{X(0) - X(\infty)}\right] = \mathrm{e}^{-\left(\frac{t}{\tau}\right)^b}\,; \quad 0 < b < 1\,, \tag{29.7}$$

where X is the property that is relaxed. The exponent b, the Kohlrausch exponent, can theoretically be determined if one assumes that the process occurs in series, representing a well-determined microscopic origin that correlates the various degrees of freedom [29.31]. This approach is borrowed from magnetic spin models such as the *Ising spin model* [29.32]. The idea is that a given molecular motion is dependent on the availability of other degrees of freedom of mobile neighboring structural units. Finite relaxation times, $t_{\max}$, are gradually obtained with increasing spin levels (ergodic limit).

As mentioned above, the models by *Dudko* et al. [29.24] and *Sang* et al. [29.23] assumed Gaussian statistics. To illustrate how a diffusion process can deviate from Gaussian statistics, we introduce a simplified version of the Langevin equation, i. e.,

$$\ddot{x} = -\eta\dot{x} + \varsigma(t) \tag{29.8}$$

with the coordinate x, the dissipation (or dampening) parameter η, and the random acceleration $\zeta(t)$. Assuming Gaussian statistics, the mean squared displacement is

$$\left\langle x^2(t)\right\rangle = 2k_{\mathrm{B}}T\eta t = 2Dt\,, \tag{29.9}$$

where $D = \eta kT$ defines the diffusion constant [29.33]). It was already realized at the time of Smoluchovski at the beginning of the 20th century that a diffusive description of a dynamic process demands a thermodynamically well-equilibrated or mixed system. Especially in a confined tribological system that involves a third medium (e.g., a lubricant), it can be expected that the Markovian nature of the underlying stochastic process could be disturbed. Consequently, for a monolayer lubricant that is chemically interacting, a nonlinear relationship of the mean squared displacement in time can be expected. Manifestations of anomalous transport are long-range spatial or temporal correlations. Two extreme limits can be distinguished: (a) processes with strong temporal relations ("fractal time") [29.29], and (b) systems that exhibit long jumps ("Lévy flights") [29.30].

29.6 Fractal Mobility in Reactive Lubrication

The importance of the underlying kinetics is illustrated by ultra-thin wetting lubricants. The spreading of "completely wetting" polymer liquids on solid surfaces has revealed unexpected spatial and temporal features when examined at the molecular level. The spreading profile is typically characterized by the appearance of a precursor film of monomolecular thickness extending over macroscopic distances and, in many cases, a terracing (also on the order of molecular dimensions) of the fluid remaining in the reservoir [29.34]. These spatial features have been shown to be consistent with a Poiseuille-like flow in which the disjoining pressure gradients with film thickness drive the spreading process [29.35]. The temporal evolution of the spreading profile in this film thickness regime is, however, found to universally scale as $t^{1/2}$ even at short times [29.34]. That the spreading dynamics are reflective of a diffusive transport mechanism and not of a pressure driven "liquid" flow suggests that interfacial confinement substantially alters the mobility of molecularly thin polymer fluids [29.36].

The molecular mobility is of fundamental importance for monolayer lubrication purposes, such as in magnetic storage devices. It has, for instance, been shown that for low surface energy hydroxyl-terminated perfluoropolyether (PFPE-OH) films, the lubricant exhibits spatially terraced flow profiles indicative of film layering [29.35] and spreading dynamics that are diffusive in nature [29.37, 38]. In magnetic storage devices the hydroxylated chain ends of molecularly thin PFPE-OH films interact with the solid surface, an amorphous carbon surface, via the formation of hydrogen-bonds with the polar, carbon-oxygen functionalities located on the carbon surface. The bonding of the PFPE-OH polymer to carbon is predicated on the ability of the PFPE backbone to deliver spatially the hydroxyl end-group to within a sufficiently close distance to the surface active sites. Kinetic measurements probing the bonding of the PFPE-OH polymer to the carbon reveal two distinctive kinetic behaviors, as illustrated in Fig. 29.7 at two representative temperatures: 50 °C and 90 °C for the



Fig. 29.7 Representative kinetic data for the bonding of PFPE-OH (tradename: Fomblin ZDOL) to amorphous carbon at $T = 50\,°\mathrm{C}$ and $T = 90\,°\mathrm{C}$. *Solid lines* represent fits using a rate coefficient of the form, $k(t) = k_0 t^{-\alpha}$ with $\alpha = 0.5$ for $T = 50\,°\mathrm{C}$ and $\alpha = 1.0$ for $T = 90\,°\mathrm{C}$



Fig. 29.8a,b Shear-modulated SFM experiments performed on a 10.7 ± 0.5 Å Fomblin Zdol film: **(a)** phase shift response between disturbance and response, and **(b)** contact stiffness response vs. temperature

two temperature regimes below 56 °C and above 85 °C. Below 56 °C the kinetics are described with a time-dependent (fractal time dependent) rate coefficient of the form

$$k(t) = k_0 t^{-1/2} \tag{29.10}$$

and at temperatures above 85 °C with the form

$$k(t) = k_0 t^{-1.0}\,. \tag{29.11}$$

The initial bonding rate constants, k_0, increased abruptly as the temperature rose above 50 °C.

The bonding kinetics in the low-temperature regime is characteristic of a diffusion-limited reaction occurring from a glass-like state of the molecularly thin PFPE-OH film [29.39]. The mobility of the PFPE chain in the glass-like state is limited by the propagation of holes or packets of free volume, which facilitate configurational rearrangements of the chain. The onset of changes in the bonding kinetics at nominally $T > 56°$ signifies a fundamental change in the mobility of the molecularly thin PFPE-OH film. Specifically, the transition in the fractal time dependence suggests that delivery of the hydroxyl moiety to the surface is no longer limited by hole diffusion, and the increase in the initial rate constant indicates an enhancement in the backbone flexibility. These results are consistent with a transition in the film from a glass-like to a liquid-like state in which the enhanced PFPE-OH segmental mobility results from rotations about the ether oxygen linkages in the chain that become increasingly facile. The time dependence observed in the high-temperature rate coefficients, $k(t) = k_0 t^{-1.0}$ is characteristic of a process occurring from a confined liquid-like state in which the activation energy increases as the extent of the reaction increases.

The impact of this transition in the molecular mobility on tribology can be illustrated with sinusoidally modulated shear force experiments [29.40, 41]. In brief, a molecularly thin (10.7 ± 0.5 Å) PFPE-OH film is subjected to a local shear stress by means of a sinusoidal force applied *laterally* to a SFM probe (at constant load) where the modulation amplitude is initially set below that required to initiate sliding between the tip and the sample. The amplitude and phase-shift responses are measures of the contact stiffness and the effective viscous dampening, respectively. From Fig. 29.8 it can be inferred that the SFM-measured nanorheological properties of the PFPE-OH film exhibit the changes discussed above in the molecular mobility. Thus kinetic and rheological data suggest that the thermal transition observed is due to the formation of a two-dimensional (2-D) glass. The "glass transition" results from the preferential "freezing out" of the out-of-plane torsional motions of the energetically confined PFPE backbone. The confinement-induced solidification in the molecularly thin precursor film will significantly impact the lubrication properties and challenge thermodynamic, well-equilibrated models of lubrication as introduced above.

29.7 Metastable Lubricant Systems in Large Conforming Contacts

It is important to note that in an experiment of thermal activation, the critical time of the experiment t_{exp} decides the system response with its finite relaxation time $t_{\max}$. If $t_{\mathrm{exp}} > t_{\max}$, the system behaves in an ergodic manner, and thermodynamic laws apply for interpreting lubrication results. On the contrary, if $t_{\mathrm{exp}} < t_{\max}$ the thermal evolution cannot be described by classical statistical thermodynamics. A metastable configuration is generated. The experimental time depends strongly on the contact area, the parameter that most differs between SFA and SFM measurements. SFA experiments involve large micron-scale contacts while SFM measurements are conducted with contacts on the nanoscale

Because of the large contact area, SFA experiments are very susceptible to generating unequilibrated metastable lubricant configurations. The SFA study by *Yoshizawa* et al. [29.42], in which distinctively different *dynamic states of friction* were introduced, could be interpreted as such. To date there are three velocity regimes used to describe the dynamic state of friction for a system that is "underdamped" [29.43]. In an underdamped system, realized by a stiff spring compared to the friction constant, the characteristic slip time is comparable or smaller than the response time of the mechanical system. One distinguishes three velocity regimes, as depicted in Fig. 29.9. The three regimes distinguish themselves by a single discriminator, v_{c}, a material, pressure and temperature dependent critical velocity. The regimes are described as

1. highly regular with high amplitude stick–slip for $v \ll v_{\mathrm{c}}$,
2. intermittent stochastic stick–slip for $v < v_{\mathrm{c}}$, and
3. smooth low friction sliding for $v > v_{\mathrm{c}}$.



Fig. 29.9 Dynamic states of friction for an underdamped spring system

Various models have been suggested to describe the different dynamic states, including melting freezing transition [29.44], chain adsorption on substrates [29.45], and embedded particle [29.43]. Until the embedded particle model by Rozman was introduced, the SFA approach seemed to be the tool of choice to investigate metastable lubricant configurations. Rozman's single particle model alerts us, however, to drawing unambiguous conclusions on the dynamical structure of a molecular system embedded between two plates and driven by an underdamped system. In Rozman's simple theoretical model, sketched in Fig. 29.10, a single particle is embedded between two corrugated



Fig. 29.10 Model of single particle embedded in a two-wave potential driven at constant force, F, and velocity v

surfaces (*two-wave potential*). The top plate is pulled at constant velocity by a linear spring, and the plate motion is monitored. Interestingly, the plate exhibits exactly the same dynamic state of frictional motion as introduced above with the three regimes, which were attributed to a rate-dependent configurational change of the lubricant.

Finally it shall be noted that the slip relaxation pattern depends condition under which the stick–slip motion is being studied. In an *overdamped* system, i. e., a system in which the spring constant is weak compared to the friction constant, *Rozman* et al. [29.46] found that one can control the experimentally observed relaxation pattern of the slip by controlling the spring constant.

29.8 Conclusion

Starting from a classical tribological Master Curve, the Stribeck curve, with its complex description of lubrication for thin lubricants, we launched a discussion of molecular lubrication pulling together disparate approaches to studying friction. We found that phenomenological descriptions of lubrication, such as the Reynolds' theory, were kept alive for ultra-thin lubricants by "adjusting" material properties, such as the viscosity. This is a common engineering approach to introduce "effective" or "apparent" properties, if tested models fail to describe new situations.

In the case of molecular lubrication, significant progress has been made in the last ten years. Two instrumental techniques have in particular contributed to this progress: the SFA and the SFM. The contributions of these two techniques have been complementary. While the SFA has tested lubricants under pressure constraints with large contacts in respect to the size of the trapped molecules, the SFM has probed the degree of collective mobility with disturbances in the size of the molecules themselves.

One feature common to interpreting lubrication results, and which was discussed here in detail, is the problem of finding the appropriate underlying statistics to describe the lubrication process. Most of the current molecular models that have been used to describe molecular friction and lubrication assumed a Gaussian statistics. Only recently has it been recognized important to consider statistics that embrace long-range spatial or temporal correlations. In the near future, it can be expected that the next leap in an improved fundamental understanding of kinetics and energetics in nanolubrication will come from interpretations that are challenging the Markovian nature of the underlying stochastic process.

References

29.1 F. P. Bowden, D. Tabor: *The Friction and Lubrication of Solids* (Clarendon, Oxford 1951)

29.2 D. Tabor, R. H. S. Winterton: The direct measurement of normal and retarded van der Waals forces, Proc. R. Soc. Lond. A **312** (1969) 435–450

29.3 G. Binnig, C. F. Quate, C. Gerber: Atomic Force Microscope, Phys. Rev. Lett. **56** (1986) 930–933

29.4 N. P. Petrov: *Friction in Machines and the Effect of the Lubricant* (St. Petersburg 1883)

29.5 B. Tower: First report on friction experiments (friction of lubricated bearings), Proc. Inst. Mech. Eng. (November 1883) 632–659

29.6 O. Reynolds: On the theory of lubrication and its application to Mr. Beauchamp tower's experiments, including an experimental determination of the viscosity of olive oil, Philos. Trans. Roy. Soc. Lond. **177** (1886) 157–234

29.7 J. P. Israelachvili, G. M. McGuiggan, M. Gee, A. Homola, M. Robbins, P. Thompson: Liquid dynamics in molecularly thin films, J. Phys. **2** (1990) 89–98

29.8 W. B. Hardy, I. Doubleday: Boundary lubrication – The paraffin series, Proc. Roy. Soc. Lond. A **100** (1922) 550–574

29.9 A. Dorinson, K. C. Ludema: *Mechanics and Chemistry in Lubrication* (Elsevier, Amsterdam 1985)

29.10 B. J. Briscoe, D. C. B. Evans: The shear properties of Langmuir–Blodgett layers, Proc. Roy. Soc. Lond. A **380** (1982) 389–407

29.11 C. Buenviaje, S. Ge, M. Rafailovich, J. Sokolov, J. M. Drake, R. M. Overney: Confined flow in polymer films at interfaces, Langmuir **19** (1999) 6446–6450

29.12 S. Blunier, H. Zogg, A. N. Tiwari, R. M. Overney, H. Haefke, P. Buffat, G. Kostorz: Lattice and thermal misfit dislocations in epitaxial CaF_2/Si(111) and

$BaF_2/CaF_2/Si(111)$ structures, Phys. Rev. Lett. **68** (1992) 3599–3602

29.13 G. Reiter, A. L. Demirel, J. Peanasky, L. L. Cai, S. Granick: Stick to slip transition and adhesion of lubricated surfaces in moving contact, J. Chem. Phys. **101** (1994) 2606–2615

29.14 S. Glasstone, K. J. Laidler, H. Eyring: *Theory of Rate Processes* (McGraw-Hill, New York 1941)

29.15 M. He, A. Szuchmacher Blum, G. Overney, R. M. Overney: Effect of interfacial liquid structuring on the coherence length in nanolubrication, Phys. Rev. Lett. **88**(15) (2002) 154302/1–4

29.16 K. L. Johnson: *Contact Mechanics* (Cambridge Univ. Press, Cambridge 1987)

29.17 E. Meyer, R. M. Overney, K. Dransfeld, T. Gyalog: *Nanoscience: Friction and Rheology on the Nanometer Scale* (World Scientific, Singapore 1998)

29.18 H. K. Christenson, D. W. R. Gruen, R. G. Horn, J. N. Israelachvili: Structuring in liquid alkanes between solid-surfaces – Force measurements and mean-field theory, J. Chem. Phys. **87**(3) (1987) 1834–1841

29.19 C. Drummond, J. Israelachvili: Dynamic behavior of confined branched hydrocarbon lubricant fluids under shear, Macromolecules **33**(13) (2000) 4910–4920

29.20 R. M. Overney, H. Takano, M. Fujihira, W. Paulus, H. Ringsdorf: Anisotropy in friction and molecular stick–slip motion, Phys. Rev. Lett. **72** (1994) 3546–3549

29.21 R. M. Overney, H. Takano, M. Fujihira: Elastic compliances measured by atomic force microscopy, Europhys. Lett. **26**(6) (1994) 443–447

29.22 E. Gnecco, R. Bennewitz, T. Gyalog, C. Loppacher, M. Bammerlin, E. Meyer, H.-J. Güntherodt: Velocity dependence of atomic friction, Phys. Rev. Lett. **84**(6) (2000) 1172–1175

29.23 Y. Sang, M. Dube, M. Grant: Thermal effects on atomic friction, Phys. Rev. Lett. **87**(17) (2001) 174301/1–4

29.24 O. K. Dudko, A. E. Filippov, J. Klafter, M. Urbakh: Dynamic force spectroscopy: A Fokker–Planck approach, Chem. Phys. Lett. **352** (2002) 499–504

29.25 F. Heslot, T. Baumberger, B. Perrin, B. Caroli, C. Caroli: Creep, stick–slip, and dry-friction dynamics: Experiments and a heuristic model, Phys. Rev. E **49** (1994) 4973–4988

29.26 S. Sills, R. M. Overney: Creeping friction dynamics and molecular dissipation mechanisms in glassy polymers, Phys. Rev. Lett. **91** (2003) 095501(1–4)

29.27 W. D. Luedtke, U. Landman: Slip diffusion and Levy flights of an adsorbed gold nanocluster, Phys. Rev. Lett. **82** (1999) 3835–3838

29.28 I. M. Sokolov: Levy flights from a continuous-time process, Phys. Rev. E **63** (2000) 011104/1–10

29.29 R. Metzler, J. Klafter: The random walks guide to anomalous diffusion: A fractional dynamics approach, Phys. Rep. **339** (2000) 1–77

29.30 R. Metzler, J. Klafter: Levy meets Boltzmann: Strange initial conditions for brownian and fractional Fokker–Planck equations, Physica A **302** (2001) 290–296

29.31 R. G. Palmer, D. L. Stein, E. Abrahams: Models of hierarchically constrained dynamics for glass relaxation, Phys. Rev. Lett. **53** (1984) 958–961

29.32 N. W. Ashcroft, N. D. Mermin: *Solid State Physics* (CBS Asia, Philadelphia 1976)

29.33 R. Becker: *Theorie der Wärme* (Springer, Berlin 1985)

29.34 F. Heslot, N. Fraysse, A. M. Cazabat: Molecular layering in the spreading of wetting liquid drops, Nature **338** (1989) 640–642

29.35 T. E. Karis, G. W. Tyndall: Calculation of spreading profiles for molecularly-thin films from surface energy gradients, J. Non-Newtonian Fluid Mech. **82** (1999) 287–302

29.36 S. F. Burlatsky, G. Oshanin, A. M. Cazabat, M. Moreau: Microscopic model of upward creep of an ultrathin wetting film, Phys. Rev. Lett. **76** (1996) 86–89

29.37 T. M. O'Connor, Y. R. Back, M. S. Jhon, B. G. Min, D. Y. Yoon, T. E. Karis: Surface diffusion of thin perfluoropolyalkylether films, J. Appl. Phys. **79** (1996) 5788–5790

29.38 X. Ma, J. Gui, L. Smoliar, K. Grannen, B. Marchon, C. L. Bauer, M. S. Jhon: Complex terraced spreading of perfluoropolyalkylether films on carbon surfaces, Phys. Rev. E **59** (1999) 722–727

29.39 A. Plonka, J. Bednarek, K. Pietrucha: Reaction dynamics in glass transition region: propagating radicals in ultraviolet-irradiated poly(methyl methacrylate), J. Chem. Phys. **104** (1996) 5279–5283

29.40 R. M. Overney, C. Buenviaje, R. Luginbuehl, F. Dinelli: Glass and structural transitions measured at polymer surfaces on the nanoscale, J. Therm. Anal. Calorimetry **59** (2000) 205–225

29.41 S. Ge, Y. Pu, W. Zhang, M. Rafailovich, J. Sokolov, C. Buenviaje, R. Buckmaster, R. M. Overney: Shear modulation force microscopy study of near surface glass transition temperature, Phys. Rev. Lett. **85**(11) (2000) 2340–2343

29.42 H. Yoshizawa, P. McGuiggan, J. N. Israelachvili: Identification of a second dynamic state during stick–slip motion, Science **259** (1993) 1305–1308

29.43 M. G. Rozman, M. Urbakh, J. Klafter: Stick-slip motion and force fluctuations in a driven two-wave potential, Phys. Rev. Lett. **77** (1996) 683–686

29.44 J. M. Carlson, A. A. Batista: Constitutive relation for the friction between lubricated surfaces, Phys. Rev. E **53** (1996) 4153–4164

29.45 Y. Braiman, F. Family, H. G. E. Hentschel: Array-enhanced friction in the periodic stick–slip motion of nonlinear oscillators, Phys. Rev. E **53** (1996) R3005–R3008

29.46 M. G. Rozman, M. Urbakh, J. Klafter: Controlling chaotic frictional forces, Phys. Rev. E **57** (1998) 7340–7343

Part E Industrial

Part E Industrial Applications and Microdevice Reliability

30 Nanotechnology for Data Storage Applications
Dror Sarid, Tucson, USA
Brendan McCarthy, Tucson, USA
Ghassan E. Jabbour, Tucson, USA

31 The "Millipede" – A Nanotechnology-Based AFM Data-Storage System
Gerd K. Binnig, Rüschlikon, Switzerland
G. Cherubini, Rüschlikon, Switzerland
M. Despont, Rüschlikon, Switzerland
Urs T. Duerig, Rüschlikon, Switzerland
Evangelos Eleftheriou, Rüschlikon, Switzerland
H. Pozidis, Rüschlikon, Switzerland
Peter Vettiger, Rüschlikon, Switzerland

32 Microactuators for Dual-Stage Servo Systems in Magnetic Disk Files
Roberto Horowitz, Berkeley, USA
Tsung-Lin Chen, Shin Chu, Taiwan
Kenn Oldham, Berkeley, USA
Yunfeng Li, Berkeley, USA

33 Micro/Nanotribology of MEMS/NEMS Materials and Devices
Bharat Bhushan, Columbus, USA

34 Mechanical Properties of Micromachined Structures
Harold Kahn, Cleveland, USA

35 Thermo- and Electromechanics of Thin-Film Microstructures
Martin L. Dunn, Boulder, USA
Shawn J. Cunningham, Colorado Springs, USA

36 High Volume Manufacturing and Field Stability of MEMS Products
Jack Martin, Cambridge, USA

37 MEMS Packaging and Thermal Issues in Reliability
Yu-Ting Cheng, HsinChu, Taiwan
Liwei Lin, Berkeley, USA

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

30. Nanotechnology for Data Storage Applications

Nanotechnolo

This chapter considers atomic force microscopy (AFM) as an enabling technology for data storage applications, considering already existing technologies such as hard disk drives (HDD), optical disk drives (ODD) and Flash Memories that currently dominate the nonvolatile data storage market, together with future devices based on magnetoresistive and phase change effects. The issue at hand is the question of whether the novel AFM-based storage, dubbed "Probe Storage", can offer a competing approach to the currently available technologies by playing the role of a disruptive technology. Probe Storage will be contrasted to HDD and ODD who are purely mechanical, as they are based on a rotating disk that uses just a single probe to address billions of bits of data, and nonvolatile RAM that has no moving parts yet requires billions of interconnects. In particular, capacity, areal density, transfer rate, form factor and cost of various data storage devices will be discussed and the unique opportunity offered by Probe Storage in employing massive parallelism will be outlined. It will be shown that Probe Storage bridges the gap between HDD, ODD and other nonvolatile RAM, drawing from the strength of each one of these and adding a significant attribute neither of these has; namely, the possibility of addressing a very large number of nanoscale bits of data in parallel. This chapter differs from the other chapters in this book in that it addresses the important issue of whether a given scientific effort, namely, Probe Storage, is mature enough to evolve into a commercially viable technology. The answer seems to indicate that there indeed is a huge niche in the data storage arena that such a technology is uniquely qualified to fill, which is large enough to justify a major investment in research and development. Indeed, as other chapters indicate, such an effort is developing at a rapid pace, with hopes of having a viable product within a few years.

30.1 **Current Status of Commercial Data Storage Devices** 901
30.1.1 Non-Volatile Random Access Memory 904

30.2 **Opportunities Offered by Nanotechnology for Data Storage** 907
30.2.1 Motors 907
30.2.2 Sensors 909
30.2.3 Media and Experimental Results ... 913

30.3 **Conclusion** 918

References 919

This chapter will differ from the other chapters in this handbook in that it addresses the important issue of whether a given scientific effort is mature enough to evolve into a commercially viable technology. Specifically, we consider scanning probe microscopy (SPM), consisting of scanning tunneling microscopy (STM) [30.1–3] and atomic force microscopy (AFM) with all their variants, as a means for storing and retrieving nanoscale bits of data to and from a substrate. Indeed, many studies have already been published in which researchers demonstrated the feasibility of using SPM techniques that hold promise for realistic applications [30.4]. However, in approaching a topic from a practical point of view, that is, whether it has the ingredients that will spawn a commercial product, it is imperative to obtain a clear view of the status of competing technologies. The commercially available technologies that will concern us here entail two classes of devices, one consisting of hard disk drives (HDD) and optical disk drives (ODD), and the other consisting of Non-Volatile Random Access Memories (NVRAM) based on charge trapping (Flash Memory) that currently dominate the data storage market. The latter may soon be supplemented by magnetoresistive RAM (MRAM) and phase change RAM (PC-RAM). For brevity, we will refer to the first class as HDD and the one as NVRAM.

It is commonly thought that nanotechnology is a breakthrough technology that is a quantum leap beyond existing technologies in its capabilities. In reality, however, nanotechnology is in many cases just a limiting

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

case to the already commercially available technologies. The latter may progress at such a high rate that the distinction between what is considered "conventional" and "nano" becomes blurred. A case in point is data storage in which distances and times are already specified by nanometers and nanoseconds. For example, the head of an HDD in a PC's hard disk flies across the storage medium (platter) at a speed of 10 m/s ($\sim$ 22 miles per h) at a height of $\sim$ 10 nm, reading and writing bits of data on a nanosecond time scale. Also, both giant magnetoresistance (GMR) devices that read magnetic data in an HDD and transistors belonging to NVRAM devices use nanoscale structures, one employing spintronic effects and the other tunneling junctions between pairs of transistors, where quantum laws of physics have to be used to describe their operation.

The issue at hand is, therefore, whether novel nanotechnologies can offer a competing approach to currently available technologies by playing the role of a "disruptive technology". This term has been coined in the high-tech industry to describe a situation where, figuratively speaking, a discovery developed in a basement can lead to a development of a new device that has the potential of becoming a commercial alternative to a commonly used one. Such a disruption of the success of a commercially established technology by a product developed by a new start-up, for example, has been witnessed more and more frequently in recent years. One would even venture to assume that the support companies give to research groups at universities can be attributed to their concern about a possible disruption of their own technology.

The important issue here is the question of what nanotechnology can offer to an already mature field such as data storage. As will be discussed later, HDD and NVRAM are worlds apart in technology. HDD is purely mechanical, as it is based on a rotating disk that uses just a single probe (head) to address billions of bits of data. NVRAM, on the other hand, has no moving parts yet requires billions of probes, i. e., interconnects, positioned at the intersection of horizontal and vertical interconnects with one probe for every bit of data. Another distinction between HDD and NVRAM is the time it takes to access a random bit of data. For an HDD the random access time is 10 ms (75 ms for ODD), while for NVRAM it is less than one µs. Clearly, NVRAM beats HDD (and ODD) in the random access arena, if that is the criteria for performance. On the other hand, the rate at which an HDD can read data sequentially is rather impressive. The current performance of an HDD stands at 436 Mb/s and 22 Mb/s for ODD, comparable to what NVRAM can offer, being of the order of 10 MByte/s. Another playing field in the battle between HDD and NVRAM performance concerns capacity and areal density of bits of data. Here, capacity measures the total number of bytes of data, while areal density measures the number of bits per square inch. The first addresses the ever growing need for storing larger and larger amounts of data, say, for high-definition TV applications, while the latter is related to what is commonly called the form factor, namely, the physical size of a storage device. The form factor is intimately connected to portability, as more and more hand-held devices have restrictions on the physical size of each of its components. Note also that a major consideration in comparing HDD and NVRAM is cost, a topic that will be addressed later.

As discussed before, both HDD and ODD use just a single probe that addresses all the bits of data on a platter where data is stored. NVRAM, on the other hand, has to resort to a grid of interconnects that contacts each bit of information individually. Such a grid, in which each bit is interfaced with one "word line" and one "bit line", occupies expensive real estate across a storage device, and, even more importantly, it requires that the interconnects be on the order of the bits of data they address. As long as these bits have dimensions on the order of, say, 1 µm, one is able to use conventional lithography for the fabrication of the interconnects. However, when the bits of data shrink to, say, 25 nm in size, interconnects are no longer a viable option due to lithographic limitations. HDD and ODD, in contrast, require no interconnects, so this limitation on the size of bits is not a concern. However, there are many other problems that arise as one tries to push the size of the stored bits to nanoscale dimensions, as will be discussed later.

By now we have touched on the heart of the challenge that nanotechnology-based storage faces if it is to compete with HDD and NVRAM in both performance and cost. Practically, one should restate this issue and ask a more modest question, namely, what niche nanotechnology will fill in consumer data-storage applications. To address this question, one notes that nanotechnology is concerned with the ability to miniaturize and characterize nanometer-sized structures. For data storage, the question is how to address nanoscale data bits rapidly without having to resort to the use of too many interconnects.

A possible solution to this challenge emerged from a brilliant idea developed at IBM and Stanford laboratories, as part of their scanning probe microscopy research [30.5–9].

A conventional AFM employs a single cantilever with a sharp tip at its end to raster scan a sample and its minute deflections, due to protrusion on the surface, generate a map of the surface topography. Under ideal conditions one can even obtain atomically resolved images. The IBM-Stanford group demonstrated that it is possible to employ a large number of such cantilevers and operate them in parallel. Such an operation provides a faster means of obtaining images of different parts of a sample simultaneously. These cantilever arrays are often referred to as types of microelectromechanical systems (MEMS), or if they are small enough, nanoelectromechanical systems (NEMS).

One can view this breakthrough concept as an enabling technology for data storage applications in that it bridges the gap between HDD and NVRAM technologies, drawing from the strength of each. To appreciate this concept, consider a medium whose area is sectioned into a thousand squares, each containing one million bits of data. Each square is addressed by its own interconnect whose width can now be as wide as a thousand bits of data. Consider now a square structure consisting of one thousand cantilevers whose tips are aligned such that each one addresses its own square. Such an arrangement, known as probe storage, and dubbed "millipede" by IBM, has some attributes belonging to an HDD, some attributes belonging to NVRAM, and potentially one significant attribute neither of these has: the possibility of addressing nanoscale bits of data. While random access is faster than that of a HDD, it is slower than that of NVRAM.

In this chapter, we will address the issues mentioned in the introduction with an emphasis on a comparison between existing and future development of conventional technologies and nanotechnologies. We will not address more futuristic approaches such as DNA and molecular electronics for data storage applications – fascinating topics on their own merit, yet deemed too far in the future for our more "technological" approach.

30.1 Current Status of Commercial Data Storage Devices

Before describing the current status of commercial storage devices, it is worthwhile to reiterate definitions and cover some new key features associated with HDD [30.10]. A schematic of a hard disk drive, shown in Fig. 30.1, is configured into sectors, each having radial tracks; there are typically 58,000 tracks per in. for HDD and 34,000 tracks per in. for ODD, 562 kbits per in. for HDD, and 100 kbits per in. for ODD. In 1993, a HDD head was flying above the storage media at a typical height of 100 nm, which dropped to 10 nm in 2002, and is expected to drop to 4 nm in 2004.

Hard Disk Drives and Optical Disk Drives

The time it takes the read-write head to get to a random bit along a track is called latency, while the time it takes the head to get to a random sector is called seek time. The time to get to any random bit is called access time. From 1990 to 2002 this time decreased linearly from 20 ms to 8 ms, and is expected to decrease to 4 ms by 2004.

Transfer time is the time it takes to transfer a given number of bits from the hard drive to a given destination in a computer. The total number of bits per unit area, usually given in bpsi (bits per square inch), is called areal density. The total number of bytes in a storage device is called capacity.

The physical size of a storage device and its price are paramount factors in its commercial viability. Disk drives are usually divided into magnetic and optical, although a combination of both is currently advanced by several companies and research groups around the world. A magnetic hard drive (HDD) has a higher capacity, lower cost, and higher performance than an optical hard drive (ODD), but its disk is not removable. The ODD, on the other hand, has a removable disk that can be mass produced by parallel replication (stamping), making it cheaper for large-scale distribution. Also, an ODD is configured to operate in such a way that the head reads data sequentially, while HDD is optimized for random access operation. Note that units of bits are usually denoted by a lower case "b" and used for areal density and transfer rate, while units of bytes are usually denoted by an upper case "B" and used for capacity. A note in passing: Areas are, oddly enough, expressed in square inches, and the holy grail for areal density is denoted by 1 tbpsi (one terabit per square inch).

Now, a crucial question when assessing the viability of a promised technology concerns the demand for the commercial product in question. Figure 30.2 estimates that a grand total of 2.12 million terabytes of information were produced in 1999 [30.11]. The breakdown is 83 terabytes for optical, 240 terabytes for paper, 427,000 terabytes for film, and 1.6 million terabytes for magnetic data storage. PC disk drives take the first place in demand: 700,000 terabytes of data!



Fig. 30.1 A schematic diagram of a hard disk drive illustrating the concepts of cylinder, track, and sector



Fig. 30.3a,b Storage drive industry shipments in [30.10]. **(a)** Categorized by value and **(b)** units shipped



Fig. 30.4 Disk drive manufacturers and merchant component suppliers [30.12]. The number of disk drive manufacturers decreased from 62 in 1985 to a mere 7 by 2002



Fig. 30.2 World production of data in 1999 estimates

To appreciate the economic impact of the HDD storage drive industry (NVRAM will be discussed later), consider Fig. 30.3, which is current to 2002 [30.10]. Here, one observes that the industry shipped 528 million units with a value of $ 35.5 billion, 58% of the value consisting of HDD and 27% of ODD, while the numbers shipped are almost evenly divided between HDD, ODD, and floppies. Based on Fig. 30.3, one would think that such a huge market would involve a large number of companies competing with each other in price and performance.

However, as shown in Fig. 30.4, the cut-throat competition among various companies gave rise to the disappearance of many of them and mergers between the others [30.12]. Note that the number of disk drive manufacturers dropped from 62 in 1985 to only seven in 2002, while merchant components suppliers dropped from 28 to eight during that period! For example, Maxtor and Quantum merged, IBM sold its disk drive division to Hitachi, and Fujitsu exited desktop HDD altogether. In 2002, Seagate shipped 1,959,000 terabytes of storage, 10.2 million enterprise drives, 1.2 million 15,000 rpm drives, and 44.8 million personal storage devices. And they expect that there will be migration to smaller form factors and increased areal density in all segments of the industry and that mobility will be become increasingly important.

A projection of HDD areal density on a logarithmic scale is shown in Fig. 30.5 [30.13]. Whereas in 1990 the areal density was only 1 gigabit per sq. in., it reached 100 gigabits per square inch in 2002 and is projected to reach 1 Tbpsi in 2006. One wonders whether it will take nanotechnology to get to 50 Tbpsi in 2017, as the figure suggests. As quoted from a Seagate presentation, "in traditional applications, areal density has grown faster than consumption, moving to a single platter society in PC's that enables smaller form factors. In non-traditional markets, new applications drive capacity growth, especially with video content." [30.12].

Table 30.1 [30.10] presents several key parameters characterizing HDD and ODD that should serve as a reality check for the potential viability of any nanotechnology approach that aims to act as a disruptive technology. Thus any new concept should be judged against this current status of HDD and ODD and, as described later, NVRAM. Note that in contrast to these impressive parameters associated with HDD and ODD, seek time is limited to 10 ms and 75 ms, respectively.

A comparison of the perceived limits to HDD and ODD performance are presented in Table 30.2 [30.10]. For magnetic disk drives, the limit to areal density is the superparamagnetic effect in which too small a magnetic domain can be thermally excited into an opposite direction, losing the reliability of the stored data. Ways and means for approaching this limit and maintaining reliability will be discussed later. For optical data storage, the conventional limit is clearly the spot size of the focused laser beam. However, near-field methods are currently being developed to circumvent this limit. As far as speed goes, switching times for magnetic domains is around 1 ns, while for laser-induced thermal effects it is ten times slower.

The current and projected relationship between areal density and data rate for several technologies are



Fig. 30.5 Projected areal density for hard disk drives [30.13]

Table 30.1 A comparison of the parameters of HDD and ODD

Product comparison		
Parameter	HDD (80 Gb desktop)	ODD (4.7 Gb DVD-RAM)
Areal density	32.6 Gb/in.^{2}	3.3 Gb/in.^{2}
	Best = 50.0 Gb/in.^{2} (2.5″)	Best = 4.6 Gb/in.^{2} (50 mm)
TPI/BPI	58 K/562 K	34 K/100 K
Capacity/platter	40 Gb (2 side, 95 mm)	9.4 Gb (2 side, 120 mm)
Unit price (drive)	\$80–\$120	\$365
Price/Gb (drive)	\$1–\$1.5	\$39
Price/Gb (media)	–	∼ \$1.5–\$2
Seek time	10 ms	75 ms
Transfer rate (writing)	436 Mb/s	22 Mb/s
Research laboratory comparison		
Parameter	HDD (longitudinal)	ODD (blue near-field)
Areal density	130 Gb/in.^{2}	45 Gb/in.^{2}
TPI/BPI	213 K/610 K	141 K/319 K

Table 30.2 Perceived technical limits for hard disk drive technology [30.10]

	Magnetic	Optical
Areal density (Gb/in.^{2})	**Superparamagnetism** 1994: 35 (scaling) 1997: 100 (lower bit aspect ratio) 2002: 500 (perpendicular) 1,000 (patterned) > 1,000 (HAMR)	**Focused spot size** 1994: 0.7 ($\lambda = 780$ nm) 1997: 3.3 ($\lambda = 650$ nm) 2002: 19 (Blu-Ray) 2× (ML) 2–3× (NF) ? × (Volume)
Switching time (ns)	**Gyromagnetic ratio** ~ 1	**Media crystallization** ~ 10

shown in Fig. 30.6 [30.5]. These technologies consist of CD-ROM, magneto-optical, magnetic disks, magnetic tape, SIL, holography, and thermo-mechanical AFM. According to this projection, magnetic disks are in the forefront of technology and are expected to have the same areal density as that of the probe storage concept, yet have a much faster data rate. The latter technology, as predicted in this figure, will grow from a data rate of only 1 Mb/s to more than 10 Mb/s, accompanied by an increase in areal density from 10 gigabits per sq. in. to hundreds of gigabits per sq. in. More about the probe storage concept will be discussed later.



Fig. 30.6 Projected areal density vs. data rate for several technologies

30.1.1 Non-Volatile Random Access Memory

Demand for Flash Memory has been growing rapidly over the last few years, driven by the rapid expansion of several markets, including mobile communications and portable media devices (notably cameras and MP3 players). Flash Memory is by now the fastest growing segment of the memory market. Figure 30.7 [30.14] shows the total value of the Flash Memory market year by year. It can be seen that the market is increasing by nearly a factor of ten every five years and up to 100% every year. The market is projected to reach $ 23 billion by 2003, up from $ 2.5 billion in 1998. The reasons for this dramatic growth are depicted in Fig. 30.8 [30.14], which shows the demand by industry sector and the growth in these areas. By far the biggest driver of demand for Flash Memory is consumer electronics and, in particular, cellular phones, which account for nearly half the market and are growing at a compounded annual growth rate of 120%.

Flash Memory

Flash Memory, the most common non-volatile, programmable memory device, uses rows and columns of interconnects that address each data cell. At the intersection of these are two transistors, which comprise the Flash Memory cell, as shown in Fig. 30.9. Each cell is addressed by a network of interconnects, where the common connection to the transistor gates is called the word



Fig. 30.7 Total value of the flash memory market, 1998–2003. The market has been growing rapidly over the last few years, and is now the fastest growing sector of the memory market



Fig. 30.8 Market segments that are driving the demand for flash memory where cellular phones are leading the demand

line and the common connection to the drain is called the bit line. Every cell in the memory array can be accessed by activating a unique combination of these lines. Here, the floating gate is linked to a word line via a second gate that serves as a control gate. The floating gate potential is altered by Fowler–Nordheim tunneling of electrons, an effect that takes place when the applied bias needed for switching is larger than the work function of the relevant electrode. The electrons arrive from the column, or bit line, and enter the floating gate from which they drain to the ground. A cell sensor monitors the flow of electrons through the gate. A value of 1 is assigned when the current is greater than a given threshold value, and 0 if it is below that value. Approximately 30,000 electrons are stored in the gate to make a 1 and 5,000 for a 0. The memory of the device derives from the very long storage time (tens of years) of the tunneling electrons in the gate capacitor. For the data to have a lifetime of ten years, the electrons can leak at a rate of no more than five a day. Flash memory can only be rewritten a limited number of times (10^{5-6}), as electrons get permanently trapped in the gate over time, impairing device efficiency. Memory devices using this technology are SmartMedia, CompactFlash cards, and Memory Sticks, for example, that read and write memory in 256- or 512-byte increments, enhancing their speed of operation. A Flash Memory device, in contrast to a hard disk drive, is noiseless, has no moving parts, is lighter and smaller, and, above all, has access times orders of magnitude faster than HDD. SmartMedia cards, which serve as solid-state floppy disk cards, were originally developed by Toshiba. They are currently available in a capacity of 128 Mbytes and higher and measure roughly 45 mm × 37 mm × 1 mm. In comparison to a HDD, however, SmartMedia cards are much more expensive. Note that a single storage cell occupies roughly 0.1 μm^2, a size limited by the complexity of its physical structure and width of the addressing interconnects.



Fig. 30.9 Schematics diagram of a typical Flash Memory cell

Magnetoresistive Random-Access Memory

Figure 30.10 [30.15] is a schematic diagram of a magnetoresistive random-access memory (MRAM) that acts as a non-volatile storage device. As with Flash Memory, there are word lines and bit lines at the intersection of which is a cell with a switchable property. Whereas with Flash Memory the electric potential of a storage cell is modified by electron tunneling, here it is the magnetic domain orientation that is switched by the current flowing through the electrodes. Passage of electrons through the magnetic domain of the cell depends on the state of polarization of the spins of the injected electrodes, much the same as the operation of giant magnetoresistance elements used to read data in a hard disk drive. In contrast to HDD and Flash Memory, MRAM is still in a stage of development and, as such, is not yet commercially available. One of its main attributes is its high speed of programming, which is faster than that of Flash Memory. The main challenges confronting MRAM technology are: (i) the size of the cell is still too large, (ii) the power consumption required during the write mode is still too high, and (iii) there are manufacturing difficulties associated with high temperature steps that may damage the magnetic layers.



Fig. 30.10 A diagram of a MRAM cell

To exemplify the status of this technology, note that Motorola demonstrated a 1-Mbit MRAM test chip using a 0.6-µm process, yielding a cell size of 7.2 µm^2. Projections are that using a 0.18-µm process will shrink the cell size to about 0.7 µm^2, and thus be competitive with Flash Memory. Also, Sony demonstrated an MRAM test chip using a 0.35-µm process that yielded a cell size of 5.8 µm^2. Other companies like IBM, which is partnering with Infineon, are also active in MRAM research.

Phase-Change Random-Access Memory

Phase-change random-access memory is a technology that uses a chalcogenide as the data storage material in the memory cell. The medium is similar to the switchable material used in rewritable CDs. It is being pioneered by Ovonyx, in association with Intel. A schematic diagram of an Ovonyx Unified Memory (OUM) is shown in Fig. 30.11 [30.16]. The OUM is an example of a phase-change random-access memory that operates much as the Flash Memory and MRAM, as far as the electrodes are concerned, except that the memory bit cell consists of a chalcogenide material that undergoes a phase change. Upon passing current from the word line to the bit line, the chalcogenide, a GeTeSb alloy, changes its phase reversibly between amorphous and crystalline states, depending on the temperature it is heated to and the rate of cooling. This change in phase is accompanied by a several orders of magnitude change in conductivity, which makes it possible to obtain a high reading signal-to-noise ratio. Similar to Flash Memory and MRAM, the OUM requires a protective shield from the environment for reliable operation over a long period. We shall come back to this issue later.



Fig. 30.11 A cross section of an OUM cell

30.2 Opportunities Offered by Nanotechnology for Data Storage

We have by now summarized the two mainstream commercial data storage devices, HDD and NVRAM, and the two near-term candidates for future commercial success, the MRAM and PC-RAM devices. As stated before, the technology utilized by these devices should be used as a measure against which novel nanotechnology approaches are judged. Note that even if a promising novel nanotechnology-based device comes into being, it will take time to bring it into maturity, and during that period, the state-of-the-art of HDD, Flash Memory, MRAM, and PC-RAM will steadily improve. One could state that we have here a competition on the "run" that will be decided based on the following four criteria: (i) capacity, (i) cell size, which translates to areal density or form factor, (iii) access time, and (iv) price, where each technology is looking for its own business niche.

Nanotechnology offers two unique opportunities to solve the problem of how to miniaturize storage devices. The first opportunity entails the use of a variety of chemical and physical processes to fabricate memory media capable of supporting nanoscale features that have reversible properties, be it magnetic, electric, or phase change. Such media should satisfy the first and second criteria, namely, a large data storage capacity and a small form factor. The second opportunity derives from the ability of scanning probe microscopy, the champion of nanotechnology, to characterize and modify structures down to atomic dimensions. Here, the use of a large number of probes operating in parallel should satisfy the third criterion, namely, fast access times. Also, because the fabrication of multiple cantilevers lends itself rather readily to mass production using currently available photolithographic processes, it should satisfy the fourth criterion: low cost.

In the next section, we describe how probe storage can be realized as a data storage technology that may find a commercially viable niche. It will be useful to divide this section into three parts, each one describing different aspects of what is known as probe storage. The first part, titled "Motors", will deal with the question of how one can access a large number of nanoscale memory cells using parallel and sequential processes. The second part, denoted by "Heads", will describe methods for reading and writing each individual memory cell using different SPM techniques. The third part, called "Media and Experimental Results", will describe the properties of different media applicable to data storage that have or can be used for probe storage.

30.2.1 Motors

This section considers two possible geometric configurations of data storage devices that operate in parallel. One consists of a rotating cylinder and an array of cantilevers positioned in an axial direction, as shown in Fig. 30.12, and the other is a 2-D, all-MEMS configuration, as shown in Fig. 30.13 [30.17]. Very little work has been done in the first, "mixed" configuration, and we will, therefore, present only a short survey of this work. Most of the section will be dedicated to the all-MEMS configuration, on which massive work has been proposed, tested, and published.

Cylinder

A cylindrical ROM media for optical data storage is currently being explored as an alternative to DVD devices, using an adhesive tape film as the recordable medium [30.18]. The purpose of the study is to find out whether this geometry will result in a smaller form factor



Fig. 30.12 A schematic diagram of a comb storage device



Fig. 30.13 A schematic diagram of a MEMS storage device

and reduced vibrations relative to a commercial DVD. These authors find that this geometry offers a larger writing area than that of a disk. For example, consider a disk with inner and outer radii of r and R, respectively, and a cylinder with the same radius and a height of h. For equal areas, the height of the cylinder is given by $h = \left(R^2 - r^2\right)/2R$. Therefore, for $r = 2.5$ mm and $R = 15$ mm, one obtains $h = 7.3$ mm. As a result, a cylinder with $R = h = 15$ mm offers more than twice the area of a disk. Such a device presents an interesting opportunity that the authors are currently pursuing. Figure 30.12 is an artist's concept of a possible geometry where a linear array of 32 cantilevers with their tips is mounted along the axis of a rotating cylinder. This array, which resembles a comb, is mounted on a piezoelectric actuator that can move the minute array very fast across a distance that equals the gap between adjacent cantilever tips. Let the cylinder circumference be divided into 32 sectors, each containing data bits arranged as circular tracks within each sector. As the cylinder rotates, each of the 32 tips reads independently a single track. Using the piezoelectric actuator, one can now move all the tips such that they read the next 32 tracks. Consider the particular geometry presented in Fig. 30.12, where the diameter of the cylinder is 1 mm, its length 3 mm, the distance between tips 100 μm, and a cylinder rotation rate of 10,020 rpm.

A crude assessment of the possible performance of such a device indicates promising values for the capacity, latency, access time, and transfer rate [30.19].

Note that while the rotational rates of these devices are expected to be similar to those of a HDD, one can conceive of MEMS-derived motors increasing the rotation rate. For example, a micro-engine with a diameter of 64 μm driven electrostatically at 300,000 rpm has recently been investigated [30.20]. The purpose here was to study the out-of-plane displacement and tilts about the rotating hub. Optical methods have been developed to characterize the operation of this device, together with a model that takes into account the various parameters relating to its operation. One wonders whether a combination of this MEMS technology with a disk or cylindrical recordable medium is a viable option for reducing latency and decreasing access time for data storage applications.

Probe Storage

The next section provides a detailed description of a probe storage device, so here we will only outline briefly the main principles of its operation [30.8, 9, 21–26]. Consider a typical schematic of a MEMS-based storage presented in Fig. 30.13, [30.17] where the cantilevers are laid out on a "sled" in both the x and y directions. The sled is translated, typically by electrostatic actuators, over the medium surface. This means that, unlike in conventional hard disks, the sectors are laid out adjacent to each other.

There are two possible architectures to this arrangement, one in which the media is moved relative to the tips and one in which the media is fixed and the tips are moved. The moving-tips model is very space inefficient, allowing only about 1% of the media area to be used for data storage, and, therefore, making it unviable in comparison to other storage technologies. In this configuration, the media is suspended by springs over the tips with actuators that control their positioning. In contrast, however, a typical design for a moving media model could have 10,000 tips in a 1 cm^2 area with a bit size of 50 nm^2. This geometry allows 30–50% of the area of the media to be utilized. Allowing for overheads such as error correction, this gives a storage capacity of 4 Gb/cm^2.

The disadvantage of this scheme is the greater mass that needs to be moved, resulting in large seek times. There is a settling time associated with each movement of the system, as the springs cause the sled to oscillate around its final position before coming to rest.

As shown in Fig. 30.14, the media is divided into $M \times N$ rectangular regions, each of which is accessible only by a single tip. The major advantage of this is that the data can be "striped" across multiple regions, dramatically increasing read times, as one seek operation is sufficient to read many bits.

The notation to address each bit is of the form $\langle x, y, tip\rangle$, where x and y are the horizontal and vertical coordinates of the bit within a rectangular region accessible by *tip*. A tip track is the data for which $\langle x, tip\rangle$ is the same, i. e., a vertical column within a rectangular region. By analogy with hard disk architecture, all data with identical x form a cylinder, accessible without moving the sled in the x direction. Cylinders are divided into tracks, which are accessible by the currently active tips, as not all tips can be active simultaneously for power considerations.

As mentioned, a benefit of this architecture is that data tracks are striped across tip tracks. This is depicted in Fig. 30.14 [30.23], where each data sector is mapped across several tip tracks. Sectors 1 and 2 can be read in parallel by activating tips 1–4 and moving them vertically downwards.

Simulated device performance for a prototype sled with parameters given in Table 30.3 is shown in Ta-

Table 30.3 A table of probe storage operating parameters

Sled mobility in x and y	100 µm
Bit cell width (area)	50 nm (0.0025 µm^2)
Number of tips	6,400
Simultaneously active tips	1,280
Tip sector length	80 bits (8 bytes)
Servo overhead	10 bits per tip sector
Device capacity (per sled)	2.1 GByte
Sled acceleration	114.8 m/s^2
Per-tip data rate	400 kbit/s
Settling time constants	1
Sled resonant frequency	220 Hz
Spring factor	75%

ble 30.4. Note that an important breakthrough in MEMS technology has recently been reported in which over one million cantilevers per sq. cm have been fabricated by anisotropic etching of silicon [30.27]. The cantilevers, which had tips at their end, measured a few micrometers in length, had spring constants of a few N/m, resonance frequencies around 10 MHz, and Q factors of 5 in air. Significantly, the resonance frequencies within the same row deviated only by 0.01%. Cantilevers as short as 100 nm and as thin as 20 nm were also fabricated, demonstrating the latitude that this technology offers. Also reported was the fabrication of a large number of cantilevers operating at frequencies up to 1 GHz with Q factors up to 8,000 [30.28]. These results will no doubt play a pivotal role in MEMS-related data storage technology for which mass parallelism combined with superfast sensors offer an important advantage.

Table 30.4 Probe storage projected performance

Average service time	1.49 ms (0.25)
Maximum service time	4.51 ms
Average seek time	1.27 ms (0.25)
Maximum seek time	1.66 ms
Average x seek time	1.24 ms (0.21)
Maximum x seek time	1.66 ms
Average y seek time	0.90 ms (0.31)
Maximum y seek time	1.62 ms
Settling time	0.72 ms
Average per request turnaround time	0.20 ms (0.20)
Maximum per request turnaround time	1.34 ms



Fig. 30.14 A schematic diagram of a probe storage data organization

Table 30.4 [30.22] takes into account the physical performance of the device, including the acceleration of the actuators, settling time, etc. One observes that the results of the model compare favorably to current hard disk technology, having access times that are approximately six times faster. Note that recent results by the IBM group imply a potential bit areal densities of 400 Gbpsi [30.29].

30.2.2 Sensors

As stated before, the key problem associated with densely packed nanoscale data bits is how to address them, realizing that no interconnects of this small size exist. Clearly, the only known method is to utilize MEMS technology where sharp tips are used to read, write, and rewrite the data bits. Although such a technology is attractive, one has to realize that the number of physical phenomena available for effecting such an interaction is quite limited.

There are, in principle, three modes for interfacing, or sensing nanoscale data bits. In the first mode, denoted as contact mode, a sharp tip is constantly in contact with the medium on which the bits are written. Here, the apex of the tip has to be comparable in size to that of the bit. The second mode involves such a tip in close proximity to the bit without actually touching it. The third mode, dubbed the noncontact mode, is a combination of the other two modes. Here, the tip vibrates in close proximity to the media in such a way that on each cycle it touches or taps its surface for a short period. This mode is referred to as the tapping mode [30.30], which turns out to have several advantages relative to the other two modes. In either mode one can use an electric current within the tip to heat up a data bit, inject a current into it, or impose an electric field across it.

For the noncontact mode, one can use field emission from a sharp tip that is positioned several nanometers away from a sample, or use a tunneling current when the tip is within a fraction of a nanometer away from the sample. The current can then be used to heat a data bit and probe its conductivity as a means for data storage and retrieval. Yet both of these are accompanied with electronic noise when operating in ambient, thus requiring vacuum for a more steady operation. Note that a tunneling current is so sensitive to a tip-sample gap that a change of 0.1 nm in gap size will change the tunneling current by one order of magnitude. One can, therefore, rule out such a technique, as its restrictions on media flatness are too strenuous. In spite of some inherent difficulties, field emission maintained its position as a viable technology for data storage applications. A schematic diagram of the operation of a device based on this technology is shown in Fig. 30.15 [30.31].

Here, a multiplicity of stationary tips is positioned in close proximity to a conducting medium, such as a chalcogenide, and a controlled current emission for each tip is used to transform its phase reversibly from crystalline to amorphous. Either the tips or the media are raster scanned across each other such that, as with the probe storage device, one can address a large number of data bits. Both tips and media are placed under a mild vacuum that has to be maintained at all times. Although writing bits may be utilized efficiently, reading them back, namely, measuring their conductivity is a nontrivial task that requires further investigation. Along these lines, one may employ a MEMS-based approach and use conducting tips that are in direct contact with a conducting medium.

A different approach to locally heating a sample that does not require direct tip-sample contact, vacuum conditions, or conducting media, is to have a heating element embedded inside each tip. In spite of the fact that each tip has a complex structure, as shown in Fig. 30.16b, it was found possible to fabricate a 64 × 64 2-D array that raster scans a polymer medium. Heating a data bit and pressing a sharp tip into it generates a nanoscale pit that is estimated to persist for years. Sensing the pit for readout is accomplished by monitoring the heat



Fig. 30.15 A schematic diagram of field-emission tips



Fig. 30.16 **(a)** A schematic diagram of a cantilever with a heating and heat-sensing tip. Indentations are inscribed into a polymeric medium by means of a heated tip. The bits are read by sensing the increased heat loss in an indentation due to the greater surface area in contact. **(b)** Details of the tip structure

dissipation of the heated tip as a function of the media topography. When the tip is across a smooth surface, it is exposed mostly to air. When the tip is sunk into a pit, it is surrounded partially by the polymer material. Thus, the difference in heat conductivity between these two cases serves as a measure of the state of the polymer, whether it is smooth or dimpled. A key difficulty with this technology has been the erase mechanism, which is currently being addressed [30.29].

In the noncontact mode, the tip is vibrated at a distance such that the tip never touches the surface directly. However, the tip senses the surface of the sample indirectly through force gradients that modify the resonance frequency of the cantilever. This mode can be useful in magnetic recording if one attaches a small magnet to the tip and uses it to both modify and sense magnetic domains. This mode, however, is slow, as the tip has to vibrate many times during the sensing of a single data bit and, therefore, can be ruled out as a candidate for data storage.

We shall now consider the tapping mode that has three main advantages to the contact mode. First, the tip-sample contact time is reduced by almost two orders of magnitude, thus minimizing tip-media wear. The second advantage is that it touches the media in a much gentler way and, therefore, does not twist or bend. The third advantage is that the tip jumps between points of contacts, which constitute the data bits, so it is less prone to crash due to media roughness. If one uses the tapping mode with a conducting tip and taps on a conducting substrate, it is possible to follow the motion of the vibrating cantilever by monitoring the time the tip makes contact with the sample. This method makes it easy to control a feedback system that keeps the motion of the cantilever under control, provided the contact is good enough. The problem one encounters using this mode, however, is that such an operation is usually chaotic and, therefore, difficult to control. If one were to overcome this problem, this mode would be fast enough relative to the noncontact mode to be considered a viable method for data storage.

We will now consider the theory and experimental results of the tapping mode by first treating it as a grazing impact oscillator (GIO) for which one can obtain closed-form expressions connecting all of its parameters [30.32]. The GIO consists of a cantilever driven at a constant frequency and an amplitude by an external force. The vibrating cantilever is then brought into close proximity to the surface of a sample until its tip starts impacting the surface. At this point the amplitude of vibration of the GIO changes, together with the relative phase between the driver and the tip. Let the amplitude of vibration of the driver be denoted by a and the spring constant and quality factor of the cantilever be denoted by k_0 and Q, respectively. On impact, the GIO acquires amplitudes of vibration A and effective spring constant k_{eff}, establishing a new value for the input power and phase:

$$A = \frac{aQ}{\sqrt{Q^2\left(1-\frac{k}{k_0}\right)^2+\frac{k}{k_0}}}\,, \tag{30.1a}$$

$$\theta = \tan^{-1}\left(\frac{\sqrt{k/k_0}}{Q(1-k/k_0)}\right)\,, \tag{30.1b}$$

$$k = k_0\left[\sqrt{\left(\frac{a}{AA}\right)^2+\frac{1}{4}\left(\frac{1}{Q^4}-\frac{4}{Q^2}\right)} - \frac{1}{2Q^2}+1\right]. \tag{30.1c}$$

Equation (30.1) shows the relationship among the various parameters governing the operation of the GIO in a closed form, making it possible to model the effect that impacting has on the tapping cantilever. Figure 30.17a shows that on bringing the vibrating cantilever closer to the surface, its amplitude of vibration decreases and its effective spring constant increases. Figure 30.17b shows the phase of the vibrating cantilever as a function of the amplitude of vibration. Figure 30.17c and d depict the input power as a function of the amplitude of vibration of the cantilever and of its phase, respectively. The double-



Fig. 30.17 Calculated tapping behavior. Modeling of the relationships among the amplitude A, effective spring constant k_{eff}, input power P_{in}, and phase ϕ

valued functions express the fact that one can operate either below or above the original resonance frequency of the cantilever.

This simplified model of a tapping mode neglects many effects such as indentation of the surface on impact and adhesion and other interface tip-sample forces. For our purpose, however, we will neglect these effects and explore the feasibility of using the tapping mode for data storage applications. The idea here is to have the tip jump from one pixel, or bit of stored data on the surface of a sample to another pixel without touching the surface in between. And while briefly touching the surface, the tip, which is conducting, will inject a pulse of current into the pixel and modify its conductivity [30.33]. Upon returning to the same pixel, the tip could monitor the conductivity of that particular pixel.

Considering the fact that the tapping mode involves a driven, damped oscillator, it is apparent that the motion of the cantilever traces a chaotic trajectory, necessitating an averaging process. For most imaging or nanofabrication purposes, such an averaging, combined with an appropriate image processing procedure, can indeed yield images with nanometer resolution. For data storage applications, however, it is desirable to have non-chaotic, reproducible interactions for every single tap because one could not afford an averaging procedure.

There are two key issues regarding the requirement that each tap produce a controlled interaction. The first concerns the identification of conditions under which (i) chaotic motion of the cantilever is minimized and (ii) good tip-sample contact is established. The second issue concerns the means by which one can observe these individual interactions. The difficulty in measuring tip-sample interactions during an individual tap stems from the fact that most of the time the tip is far away from the sample, and only during a small fraction of a cycle does it actually sense the presence of the sample. Also, it is the nature of the tapping mode of operation that the tip approaches the sample at a relatively small velocity, which is the reason why it acts as a grazing impact oscillator in the first place. One can choose the electrical contact between tip and sample as the measuring tool for the reproducibility of the interaction for individual taps. This choice is clearly compatible with storage modalities in which current injection into storage media gives rise to writing and reading of phase-change data.

The use of all-metal cantilevers tapping on a gold substrate was recently demonstrated, whereby carefully chosen parameters enable the generation and observation of individual current pulses [30.34]. These pulses were generated by applying a short bias pulse during the tip-sample contact time. Each current pulse, lasting up to 20 µs, could produce a current of ~ 10 µA in a nm^2 region yielding a current density of 10^{13} A/m^2. This density is large enough to be applicable for phase-change. The cantilever was fabricated from a rectangular PtIr wire whose length, width, and thickness were 1,200 µm, 100 µm, and 50 µm, respectively. One side of the cantilever was attached to a driving bimorph, and the other side etched to produce a tip whose apex radius was estimated to be 70 nm. The spring constant, resonance frequency, amplitude of vibration, and quality factor of the cantilever were 300 N/m, 13 kHz, 100 nm, and 100, respectively. The all-metal cantilever ensured good conductivity and could withstand a large number of



Fig. 30.18 **(a)** A typical current pulse train (*solid line*) obtained with pulsed voltage bias in phase with the cantilever's lowest position and the associated cantilever motion (*dotted line*), **(b)** two current pulses (*solid line*), bias voltage pulses (*dashed line*), and cantilever motion (*dotted line*)

tapping impacts without degrading and had a shiny surface that acted as a good mirror for the optical deflection technique.

The experimental results yielded long trains of individually injected current pulses. Figure 30.18 (left-hand side) shows 14 non-averaged experimental current pulses (solid line) and their associated cantilever motion (dashed line) with a background of instrumental noise [30.34]. The current pulses demonstrate the reproducibility of the conductance established during each tap. Figure 30.18 [30.34] (right-hand side) shows two averaged current pulses (solid line) with their input bias pulses (dashed line) and the associated cantilever motion (dotted line). Note that the tip-sample contact time is revealed by the duration of the current pulse, which is shorter than the duration of the applied bias pulse. Here, the amplitude of the bias pulse was 10 mV, its duration was 40 μs, and the timing of its application relative to the motion of the cantilever was provided by the output of the atomic force microscope photodiode. The current pulses, with a magnitude of 0.5 mA, are much larger than the tunneling current occurring while the tip is within a fraction of a nanometer from the surface. Also, the displacement current, due to the motion of the cantilever and the time varying nature of the applied bias, is expected to be much smaller than the observed current pulses. The contact conductance is shown in Fig. 30.19, where a linear relation between voltage and current implies a good ohmic contact. These results demonstrate that it is possible to minimize the chaotic behavior of a tapping cantilever and obtain reproducible conductance on each individual tap. The next step is to use the tapping mode in conjunction with current injection to write and read data bits on conducting media.



Fig. 30.19 An I–V curve taken with an individual ramped input voltage pulse demonstrating an ohmic contact. *Insert:* The current pulse (*solid line*), ramped input bias voltage (*dashed line*), and cantilever motion (*dotted line*)

30.2.3 Media and Experimental Results

This section summarizes several typical experimental results using different data storage media, electric charging, electric domain orientation, magnetic domain orientation, chemical modification, and phase change in chalcogenides and organic films.

Electric Charging

Quate's group at Stanford has studied charge trapping in a silicon nitride/silicon dioxide/silicon system using a scanning capacitance microscope [30.6]. The charge trapping in this system has been used for many years for non-volatilesemiconductor memory. Using chemical vapor deposition, 500 Å of silicon nitride was deposited onto a silicon wafer with a 50 Å oxide coating. By selectively storing charge into the substrate, they were able to write bits as small as 0.02 μm^2. Using this method, they were able to write the founding document of the Swiss Confederation onto a 120 μm^2 area, corresponding to 256 kilobits of information that yields a data density of 10 Gbpsi.

Electric Domains

Hidaka et al. have demonstrated the possibility of ultra-high density charge storage in a ferroelectric film, $PbZr_{1-x}Ti_xO_3$ [30.35]. They show that a change in the topography of the film can be introduced by domain reorientation induced by the application of a 10 V pulse with a duration of 100 μs. This is due to the piezoelectric effect caused by domain structures. Data bits as small as 40 nm were written this way. This result implies a data density of approximately 300 Gbpsi, suggesting that this medium is a good candidate for high-density data storage.

Thin Oxide Films

IBM Research in Switzerland has demonstrated reproducible switching in thin oxide perovskite films [30.36]. By constructing metal-insulator-metal capacitor-like devices, with $SrZr0_3$ as the insulator, they were able to observe an order of magnitude increase in the leakage current of the device at a threshold voltage of −0.5 V. This process is perfectly reversible, and the leakage current can be restored to its initial state upon application of a positive voltage. The switching occurs very rapidly, taking less than 100 ns to change from one conductivity state to another. Interestingly, the magnitude of the transition depends on the voltage applied, suggesting the possibility of storing multiple bits in one pixel.

Magnetic Domains

Sun et al. have demonstrated a novel way to overcome the limitations of media currently used for magnetic data storage [30.37]. By reducing iron and platinum-containing compounds, they demonstrated the formation of large-scale self-ordered arrays of magnetic particles. Initial studies suggest that an assembly of magnetic particles as small as 4 nm can support stable magnetization transitions at room temperature. By using the particles in these arrays as bits, the possibility of terabit-per-square-inch magnetic data storage could be realized.

Figure 30.20 shows transmission electron microscopy of these arrays that indicate a remarkable uniformity of particle size and large-scale periodicity. The figure also shows assemblies of these particles deposited onto a silicon oxide substrate under varying experimental conditions.

Chemical Modification

We have discussed the fact that the tapping mode is considerably less damaging to the tip and sample, as the tip spends less time contacting the sample and does not drag across it while raster scanning. For this purpose, diamond-coated cantilevers have been found useful for experiments in which wear is a problem. For sample oxidation purposes, the tip is first oscillated away from the sample with peak-to-peak amplitude of 10–15 nm, and then a feedback system reduces the amplitude to 7–10 nm by pressing the tip further into the sample. A 50 ms-long pulse with a 10–12 V magnitude is then applied to oxidize a thin Ti film. It was found that this technique produces much finer structures. Figure 30.21 [30.38] is a tapping mode AFM image of four dots created in such a way. The dots in this image have a diameter of less than 10 nm and a height of 3.5 nm above the surrounding Ti surface with a center separation of 20 nm. Around the dots there is what appears to be a lower ring of material with a channel in between. This experiment demonstrates that one can use the tapping mode to write fine pixels, albeit not to erase them.



Fig. 30.20 **(a)** TEM micrograph of a 3-D assembly of 6-nm as-synthesized $Fe_{50}Pt_{50}$ particles deposited from a hexane/octane (v/v 1/1) dispersion onto a SiO-coated copper grid. **(b)** TEM micrograph of a 3-D assembly of a 6-nm $Fe_{50}Pt_{50}$ sample after replacing oleic acid/oleyl amine with hexanoic acid/hexylamine. **(c)** HRSEM image of a ∼180-nm-thick, 4-nm $F_{52}Pt_{48}$ nanocrystal assembly annealed at 560 °C for 30 min under 1 atm of N_2 gas. **(d)** High-resolution TEM image of 4-nm $Fe_{52}Pt_{48}$ nanocrystals annealed at 560 °C for 30 min on a SiO-coated copper grid reference



Fig. 30.21a,b Experimental results of local chemical modification using AFM tip: **(a)** 20-nm dots written on Ti film, **(b)** cross section of written bit

Phase Change in Chalcogenides

Chalcogenides, the active material in rewritable CDs, have the advantage of being a well-characterized and understood bistable phase change material that has already had successful commercial data storage applications, i. e., CDRWs. Currently, NVRAM using chalcogenides as the active material is being pursued by an alliance of Ovonyx and Intel. Chalcogenides are materials that have an easily reversible stable change between amorphous and crystalline phases. To switch from the crystalline to the amorphous phase, the material is heated sufficiently, so that the material subsequently cools rapidly into the amorphous phase. The reverse change is achieved by heating the material above the glass transition temperature, so that it recrystallizes upon cooling. For commercial CDRWs, writing is done by means of laser light heating and reading is done by measuring the difference in reflectivity of the laser light from each of these two phases.

Scanning probe microscopy can be used to switch the phase of a chalcogenide material by the application of a pulse of current that heats the material as it passes through it [30.39]. The state of the material can be read typically by measuring the resistance of the sample. Figure 30.22 shows the two different states, amorphous and crystalline of the chalcogenides. The reversibility of this transition is remarkable, and has been shown to be stable over 10^{12} repeated read-write cycles. *Gotoh* et al. demonstrated this effect using conducting AFM tips, where a transition from the high resistance amorphous state to the lower resistance crystalline state was observed both the in topography and the conductivity of the sample. The change from amorphous to crystalline phases was confirmed by X-ray diffraction. Figure 30.23a and a′ show a conductance AFM image and a profile of the surface after the application of varying voltage pulses. The topography of the substrate is shown in Fig. 30.23b. Figure 30.23c and c′ show the equivalent conductance AFM images after the substrate has been scanned at a negative voltage, erasing the lower power marks on the substrate.



Fig. 30.22a–c Experimental results of phase change using interconnects. **(a)** Crystalline area, **(b)** amorphous area, **(c)** stability of bits over 1,012 rewrites (Ovonyx)

These materials have been further characterized by *Gidon* et al. [30.26], who showed that the resistivity of the film in its amorphous phase was $100\,\Omega\,\text{cm}^{-1}$, while that of the crystalline state was $0.1\,\Omega\,\text{cm}^{-1}$. They also show that a data bit requires a 200 ns pulse with a power of 50 μW, which translates to a total energy of 10 pJ.

Phase Change in Organics

Organics have proved important in a variety of electronic and optoelectronic applications such as light-emitting diodes, thin-film displays, transistors, photovoltaics, and



Fig. 30.23 Experimental results of phase change using an AFM tip **(a)**, **(a′)**, conducting AFM images after applying 100 ns pulses to the substrate, **(b)** topography AFM image of the substrate, **(c)**, **(c′)** conducting AFM images showing erasure after scanning the substrate with an applied bias of −1 V, **(d)** *I*–*V* curves of untreated (*dotted*) and treated (*solid*) regions

lasers. There are several advantages to organics for economic and manufacturing reasons, and a large body of research already exists in this field. As such, there is significant interest and motivation in finding data storage applications based on organic technology.

There has been much research recently into organic materials and systems capable of reversible switching and thus capable of being exploited for data storage applications. There are two broad categories of organics data storage; one where the active material (which can be homogenous or heterogeneous) has inherent bistability, and one where the bistability is a property of the device structure.

There are many different materials that have been investigated for data storage. The fundamental property is that it should have two states (electronic, morphological, or some other easily measured physical characteristic) that the material can exist in, and it should be stable indefinitely in either state. Furthermore, the material should be able to be easily and reversibly switched between these states, and this should be reproducible over many millions of cycles for it to be useful as a data storage medium.

Several groups have been working on reversible transitions in organic complexes suitable for switching by scanning probe techniques. Many complexes have been demonstrated to exhibit reversible switching, e.g., 3-nitrobenzal malonitrile (NBMN) and 1,4-phenylenediamine (pDA) [30.40], tetrathiofulvane (TTF) and *m*-nitrobenzylidene propanedinitrile (*m*-NBP) [30.41], and many other variants.

Li et al. [30.41] have studied organic films consisting of tetrathiofulvane (TTF), an electron donor, and *m*-nitrobenzylidene propanedinitrile (*m*-NBP), an electron acceptor. This complex demonstrates electrical bistability, which can be written and read by scanning tunneling microscopy.

The nature of the measurement means that it is difficult to ascertain whether this is due to solely conductive changes in the sample, or whether topographic modifications might also contribute. By applying pulses of 1 ms duration, bits of 1.2 nm diameter could be written. This implies an areal density of $\sim 10^{18}$ bits/in^2. This change was characterized electrically, and the resistance was measured as changing from $10^8\ \Omega$ to $10^3\ \Omega$ with a threshold switching voltage of 3.1 V. The proposed switching mechanism is charge transfer between the two film constituents. This change was stable over time and is reversible. This change is reversible, but only by heating for prolonged periods, making it unsuitable for applications as of yet.

Gao et al. have demonstrated stable, local, reversible nanoscale switching [30.40] using a charge transfer complex of 3-nitrobenzal malonitrile (NBMN) and 1,4-phenylenediamine (pDA). A 200-nm-thick film of this complex was deposited onto highly ordered pyrolitic graphite. Macroscopic electrical measurements demonstrate the bistability and switching of the material. Figure 30.24a shows the current-voltage characteristics of the sample in these two conductivity states. Initially, the material is in a low conductivity state, but upon reaching a certain threshold voltage, in this case 3.2 V, the material abruptly changes to a conductive state. The transition time is very abrupt, 80 ns, as shown in Fig. 30.24b.

Of further interest for data storage applications is that, having demonstrated reversible switching in macroscopic films, Gao et al. also showed that it was possible to switch these materials on the nanoscale using an STM



Fig. 30.24a,b Experimental results of bulk conductivity changes of organic films. **(a)** I–V curves of a 200-nm-thick film showing the two conductivity states. Switching voltage is 3.2 V. **(b)** Change in conductivity against time, showing a transition time of 80 ns

to apply pulses, i. e., to write bits, and also to measure conductivity, i. e., to read bits.

Figure 30.25a shows the local nanoscale film morphology of the sample. Figure 30.25b and c show patterns written on a sample by application of voltage pulses from the STM tip. Figure 30.25d demonstrates the erasure of a single bit from the pattern by application of a reverse-biased voltage pulse. Similar to the work of *Li* et al., the entire substrate could be erased by prolonged heating. Of much greater interest is the demonstration of individual bit erasure, achieved by applying reverse voltage pulses. The erasure is incomplete unless the pulse is reverse-biased, indicating that it is the combined effect of heating and electric field that erases the bits.



Fig. 30.25a–f STM of the NBMN-pDA film on HOPG. **(a)** 6 nm^2 image showing the crystalline order of the film; **(b)** a 3×3 array of bits (4 V, 1 µs); **(c)** an "A" pattern (3.5 V, 2 µs); **(d)**, **(e)**, **(f)** STM images after erasing marks with reverse-biased pulses (−4.5 V, 50 µs). Distance between neighboring marks is 1.7 nm



Fig. 30.26a–c Experimental results of conductivity changes of organic device structures: **(a)** the structure of the bistable device, **(b)** *I*–*V* characteristics. Voltage was scanned in steps of 0.1 V from 0 to 5 V. Curves a and b represent the *I*–*V* characteristics of the first and second bias scan, respectively. Curve c is the *I*–*V* curve of the third bias scan after the application of a reverse voltage pulse (−3 V). **(c)** Typical current responses of the device being written, read, erased, read over time

Several proposed mechanisms were investigated as the possible origin of this switching, including conformational switching and charge transfer. These could be discounted for reasons, including the stability and time scale of the switching. A more plausible hypothesis is a local phase transition from crystalline insulating regions to amorphous conducting regions. TEM and diffraction studies of the samples agree with this hypothesis. It should be pointed out that an alternative interpretation has been suggested by *Zhao* et al. [30.42]. The conductivity change could be due mainly to a change in the topography of the sample, reducing the tip-sample distance and, therefore, the tunneling distance, manifested as an apparent change in conductivity.

Ma et al. have developed a simple device structure that exhibits electrical bistability [30.43]. This device has a fairly simple structure consisting of alternating layers of aluminum and an organic compound, 2-amino-4,5-imidazoledicarbonitrile (AIDCN), as depicted in Fig. 30.26a. Several alternative organics (Alq3 and MEH-PPV) and metals (copper, silver, and gold) have been tried with varying degrees of success.

Figure 30.26b shows the current-voltage bistability of a device with structure Al/AIDCN (50 nm)/Al (20 nm)/AIDCN (50 nm)/Al. A first run shows an initially low current, followed by an abrupt and dramatic increase in the current of four orders of magnitude at 2 V. Subsequent repeated voltage runs (b) show that this transition is stable, being orders of magnitude higher than the initial measurement. The devices proved to be stable in this state over periods ranging from days to weeks.

Of further interest is that the device proved to be erasable by purely electrical means, the application of a -0.5 V pulse bringing the device back to its original state. This is denoted by c in Fig. 30.26b. Furthermore, the devices showed excellent stability over time, with over one million read-write-erase cycles being performed on the devices with excellent repeatability, as depicted in Fig. 30.26c. The origin of this bistability is unclear. It is clear that the central electrode is critical to the observed effect, as the bistability is only observed when the central electrode thickness is above a threshold value, 10 nm. Organics with high dielectric constants and low conductivity are believed to be important for device performance. The exact mechanism, however, is as yet unclear. Preliminary results on novel materials [30.44] have suggested the possibility of an all-organic variation of this concept, with an AFM tip switching between bistable states of the system.

30.3 Conclusion

Nanotechnology is perceived as a branch of science that deals with structures whose dimensions are measured in nanometers. Clearly, new phenomena become apparent when the number of atoms at the interface of such a structure becomes comparable to the number of atoms in its volume. As a result, nanotechnology evolved into a new kind of science that deals with the physics of small things. However, the suffix -technology here implies a far more reaching aspect than just a scientific curiosity; this branch of science should also be of some use. This poses a dilemma for researchers whose main interest is in understanding new phenomena, rather than in finding a use for them. Consider scanning probe microcopy, which is celebrating its twentieth birthday now with uncountable contributions to the science of measurement of surfaces and near-surface phenomena. Despite all the contributions scanning probe microscopy has made, it has always served as a tool for investigations, rather than as a practical device that can become a commercial commodity. And yet this is exactly what this chapter deals with. The challenge of converting scanning probe microscopy from a research tool into a probe storage device is daunting indeed and will require new ideas to make it happen. The danger associated with this challenge is that novel ideas developed by research groups are sometimes too immature to be measured against any existing technology, in general, and against data storage, in particular. One has to keep pursuing research opportunities whose outcomes are unknown and whose applications are unexpected with the hope that they will bring about good science and hopefully useful applications.

However, based on the technical breakthroughs delineated in this and the following chapter and judging from the history of data storage evolution, it seems plausible that probe storage will serve as a disruptive technology that replaces data storage devices in a particular market niche. These new devices should be non-volatile, have terabyte capacity with microsecond access times with gigabyte transfer rates, all for a cost that is highly competitive with current commercially available data storage devices.

References

30.1 D. Sarid: *Scanning Force Microscopy, with Applications to Electric, Magnetic, and Atomic Forces* (Oxford Univ. Press, Oxford 1991)

30.2 D. Sarid: *Scanning Force Microscopy, with Applications to Electric, Magnetic, and Atomic Forces*, revised edn. (Oxford Univ. Press, Oxford 1994)

30.3 D. Sarid: *Exploring Scanning Probe Microscopy with Mathematica* (Wiley, New York 1997)

30.4 B. G. Levi: Do atomic force microscope arrays have the write stuff?, Phys. Today **55**(10) (2002) 14–17

30.5 H. J. Mamin, B. D. Terris, L. S. Fan, S. Hoen, R. C. Barrett, D. Rugar: High-density data storage using proximal probe techniques, IBM J. Res. Dev. **39**(6) (1995) 681–699

30.6 R. C. Barrett, C. F. Quate: Large-scale charge storage by scanning capacitance microscopy, Ultramicroscopy **42–44** (1992) 262–267

30.7 H. J. Mamin, R. P. Ried, B. D. Terris, D. Rugar: High-density data storage based on the atomic force microscope, Proc. IEEE **87**(6) (1999) 1014–1027

30.8 P. Vettiger, J. Brugger, M. Despont, U. Drechsler, U. Durig, W. Haberle, H. Lutwyche, H. Rothuizen, R. Stutz, R. Widmer, G. Binnig: Ultrahigh density, high-data-rate NEMS-based AFM data storage system, Microelectron. Eng. **46** (1999) 11–17

30.9 P. Vettiger, M. Despont, U. Drechsler, U. Durig, W. Haberle, M. I. Lutwyche, H. E. Rothuizen, R. Stutz, R. Widmer, G. K. Binnig: The millipede-more than one thousand tips for future AFM data storage, IBM J. Res. Dev. **44**(3) (2000) 323–340

30.10 B. Schechtman: The future of optical disk storage, NSIC Annual Meeting Symposium, Monterey 2002, 1–14

30.11 P. Lyman, H. L. Varian: How much information (2000) retrieved from http://:www.sims.berkeley.edu/how-much-info

30.12 W. Perdue: Private Communication (September, 2002)

30.13 P. Frank: private communication, (2002)

30.14 H. De J. Ruiz, S. D. Morgan: , Witter Semiconductor and Systems Conference, Laguna Michael 2001

30.15 J. Daughton, NVE Inc., private communication

30.16 M. Gill, T. Lowrey, J. Park: Ovonics unified memory – A high performance nonvolatile memory technology for stand alone memory and embedded applications, 2002 IEEE Int. Solid State Circuits Conf., San Francisco 2002 (IEEE, Piscataway 2002)

30.17 M. Despont, J. Brugger, U. Drechsler, U. Dürig, W. Häberle, M. Lutwyche, H. Rothuizen, R. Stutz, R. Widmer, G. Binnig, H. Rohrer, P. Vettiger: VLSI–NEMS chip for AFM data storage, Technical Digest 12th IEEE Int. Conf. on Micro Electro Mechanical Systems (MEMS'99) (IEEE, Piscataway 1999) 564–569

30.18 K. Schulte-Wieking, S. Noehte, C. Dietrich, M. Mayer: A new cylindrically shaped optical data storage medium based on adhesive tape-concept and first results, IEEE Proc. Technical Digest of ISOM/ODS 2002, Joint Int. Symp. on Optical Memory and Optical Data Storage 2002 (IEEE, Piscataway 2002) 117–120

30.19 D. Sarid: unpublished results, (2002)

30.20 L. A. Romero, F. M. Dickey: A method for achieving constant rotation rates in a microorthogonal linkage system, J. Microelectromech. Syst. **9**(2) (2000) 236–244

30.21 L. R. Carley, G. R. Ganger, D. F. Nagle: MEMS-based integrated-circuit mass-storage systems, Commun. ACM **43**(11) (2000) 71–80

30.22 J. L. Griffin, S. W. Schlosser, G. R. Ganger, D. F. Nagle: Modeling and performance of MEMS-based storage devices, Int. Conf. on Measurement and Modeling of Computer Systems, Proc. of ACM Sigmetrics, Santa Clara 2000, **28**(1) (2000) 56–65, published as Performance Evaluation Review

30.23 S. W. Schlosser, J. L. Griffin, D. F. Nagle, G. R. Ganger: Designing computer systems with MEMS-based storage, Proc. of the 9th International Conf. on Architectural Support for Programming Languages and Operating Systems, Boston 2000, 1–12

30.24 L. R. Carley, G. Ganger, D. F. Guillou, D. Nagle: System design considerations for MEMS-actuated magnetic-probe-based mass storage, IEEE Trans. Magn. **37**(2) (2001) 657–662

30.25 R. T. El-Sayed, L. R. Carley: Performance analysis of beyond 100 Gb/in^2 MFM-based MEMS-actuated mass storage devices, IEEE Trans. Magn. **38**(5) (2002) 1–3

30.26 O. Bichet, S. Gidon, Y. Samson: Scanning probe based storage on phase change media, OSA Trends in Optics and Photonics Vol. 88 Optical Data Storage (OSA, Washington D.C. 2003)

30.27 H. Kawakatsu, D. Saya, A. Kato, K. Fukushima, H. Toshiyoshi, H. Fujita: Millions of cantilevers for atomic force microscopy, Rev. Sci. Instrum. **73**(3) (2002) 1188–1192

30.28 H. Kawakatsu, S. Kawai, D. Saya, M. Nagashio, D. Kobayashi, H. Toshiyoshi, H. Fujita: Towards atomic force microscopy up to 100 MHz, Rev. Sci. Instrum. **73**(6) (2002) 2317–2320

30.29 P. Vettiger, G. Cross, M. Despont, U. Drechsler, U. Dürig, B. Gotsman, W. Häberle, M. A. Lantz, H. E. Rothuizen, R. Stutz, G. K. Binnig: The 'millipede' – Nanotechnology entering data storage, IEEE Trans. Nanotechnol. **1** (2002) 39–55

30.30 Q. Zhong, D. Inniss, K. Kjoller, V. B. Elings: Fractured polymer/silica fiber surface studied by tapping mode atomic force microscopy, Surf. Sci. **290**(1–2) (1993) L688–L692

30.31 A. M. Hayashi: Punch cards of the future, Sci. Am. (May 2000)

30.32 J. P. Hunt, D. Sarid: Kinetics of lossy grazing impact oscillators, Appl. Phys. Lett. **72**(23) (1998) 2969–2971

30.33 D. Sarid: Tapping-mode scanning force microscopy: Metallic tips and samples, Comp. Mater. Sci. **5** (1996) 291–297

30.34 A. Fein, Y. Zhao, C. A. Peterson, G. E. Jabbour, D. Sarid: Individually injected current pulses with conducting-tip, tapping-mode atomic force microscopy, Appl. Phys. Lett. **79**(24) (2001) 3935–3937

30.35 T. Hidaka, T. Maruyama, M. Saitoh, N. Mikoshiba, M. Shimizu, T. Shiosaki, L. A. Willis, R. Hiskes, S. A. Dicarolis, J. Amano: Formation and observation of 50 nm polarized domains in $\mathrm{PbZr_{1-x}Ti_xO_3}$ thin film using scanning probe microscope, Appl. Phys. Lett. **68**(17) (1996) 2358–2359

30.36 A. Beck, J. G. Bednorz, Ch. Gerber, C. Rossel, D. Widmer: Reproducible switching effect in thin oxide films for memory applications, Appl. Phys. Lett. **77**(1) (2000) 139–141

30.37 S. Sun, C. B. Murray, D. Weller, L. Folks, A. Moser: Monodisperse FePt nanoparticles and ferromagnetic FePt nanocrystal superlattices, Science **287** (2000) 1989–1992

30.38 C. Peterson: Characterization of semiconductor devices through scanned probe microscopy. Ph.D. Thesis (University of Arizona, Tucson 2002)

30.39 T. Gotoh, K. Sugawara, K. Tanaka: Nanoscale electrical phase-change in $\mathrm{GeSb_2Te_4}$ films with scanning probe microscopes, J. Non-Cryst. Solids **299–302** (2002) 968–972

30.40 H. J. Gao, K. Sohlberg, Z. Q. Xue, H. Y. Chen, S. M. Hou, L. P. Ma, X. W. Fang, S. J. Pang, S. J. Pennycook: Reversible, nanometer-scale conductance transitions in an organic complex, Phys. Rev. Lett. **84**(8) (2000) 1780–1783

30.41 J. C. Li, Z. Q. Xue, W. M. Liu, S. M. Hou, X. L. Li, X. Y. Zhao: Study on a new organic-complex thin film with electrical bistable properties using a scanning tunneling microscope, Phys. Lett. A **266** (2000) 441–445

30.42 Y. Zhao, A. Fein, C. A. Peterson, D. Sarid: Comment on reversible, nanometer-scale conductance transitions in an organic complex, Phys. Rev. Lett. **87**(17) (2001) 179706–1

30.43 L. P. Ma, J. Liu, Y. Yang: Organic electrical bistable devices and rewritable memory cells, Appl. Phys. Lett. **80**(16) (2002) 2997–2999

30.44 B. McCarthy, K. Yamnitskiy, G. E. Jabbour, D. Sarid: unpublished results, (2002)

31. The "Millipede" – A Nanotechnology-Based AFM Data-Storage System

The "millipede" concept presented here is a new approach for storing data at high speed and ultrahigh density. The interesting part is that millipede stores digital information in a completely different way from magnetic hard disks, optical disks, and transistor-based memory chips. The ultimate locality is provided by a tip, and high data rates are a result of massive parallel operation of such tips. As storage medium, polymer films are being considered, although the use of other media, in particular, magnetic materials, has not been ruled out. The current effort is focused on demonstrating the millipede concept with areal densities of up to $0.5-1\,\mathrm{Tb/in^2}$ and parallel operation of very large 2-D (up to 64×64) AFM cantilever arrays with integrated tips and write/read/erase functionality. The fabrication and integration of such a large number of mechanical devices (cantilever beams) will lead to what we envision as the VLSI age of micro- and nanomechanics.

In this chapter, the millipede concept for a MEMS-based storage device is described in detail. In particular, various aspects pertaining to AFM thermomechanical read/write/erase functions, 2-D array fabrication and characteristics, $x/y/z$ microscanner design, polymer media properties, read channel modeling, servo control and synchronization, as well as modulation coding techniques suitable for probe-based data-storage devices are discussed.

31.1 **The Millipede Concept** 923
31.2 **Thermomechanical AFM Data Storage** 924
31.3 **Array Design, Technology, and Fabrication** 926
31.4 **Array Characterization** 927
31.5 ***x/y/z* Medium Microscanner** 929
31.6 **First Write/Read Results with the 32×32 Array Chip** 931
31.7 **Polymer Medium** 932
  31.7.1 Writing Mechanism 932
  31.7.2 Erasing Mechanism 935
  31.7.3 Overwriting Mechanism 937
31.8 **Read Channel Model** 939
31.9 **System Aspects** 943
  31.9.1 PES Generation for the Servo Loop .. 943
  31.9.2 Timing Recovery 945
  31.9.3 Considerations on Capacity and Data Rate 946
31.10 **Conclusions** 948
References 948

In the twenty-first century, the nanometer will probably play a role similar to the one played by the micrometer in the twentieth century. The nanometer scale will presumably also pervade the field of data storage, although there is so far no obvious way in conventional magnetic, optical, or transistor-based storage to achieve the nanometer scale in all three dimensions. After decades of spectacular progress, those mature technologies have entered the homestretch; imposing physical limitations loom before them.

One promising method involves the use of patterned magnetic media for which the ideal write/read concept still needs to be demonstrated. The biggest challenge, however, is to pattern the magnetic disk in a cost-effective way. If such approaches are successful, the basis for large-capacity storage in the twenty-first century might still be magnetism.

Other proposals call for totally different media and techniques such as local probes, near-field optics, magnetic super-resolution or holographic methods. In general, when an existing technology is about to reach its limits in the course of its evolution and alternatives are emerging in parallel, two things usually happen: First, the existing and well-established technology is explored further and every effort is made to push its limits to the utmost in order to get the maximum return on the considerable investments made. Then, when all possibilities for improvement have been exhausted, the technology may still survive for certain niche applications, but the emerging technology will take over, opening new perspectives and new directions.

In many fields today we are witnessing the transition of structures from the micrometer to the nanometer scale, a dimension that nature has long been using to build the finest devices with a high degree of local functionality. Many of the techniques we use today are not suitable for the nanometer age; some will require minor or major modifications, others will be partially or entirely replaced. It is certainly difficult to predict which techniques will fall into which category. In key information technology areas, such as nano-electronics and data storage, it is not yet obvious which technologies and materials will be used in the future.

In any case, for an emerging technology to be seriously considered as a candidate to replace an existing technology that is approaching its inherent limits, it must provide a long-term perspective. For instance, the silicon microelectronics and storage industries are huge and have exacted correspondingly enormous investments, which makes them long-term oriented by nature. The consequence for storage is that any novel technology with higher areal storage density than today's magnetic recording [31.1, 2] should have long-term potential for further scaling, preferably down to the nanometer or even atomic scale.

The only available tool known today that is simple and yet provides this very long-term perspective is the nanometer-sharp tip. The simple tip is a very reliable tool that concentrates on one functionality: the ultimate local confinement of interaction. Techniques that use nanometer-sharp tips for imaging and investigating the structure of materials down to the atomic scale, such as the atomic force microscope (AFM) and the scanning tunneling microscope (STM) [31.3, 4], are suitable for the development of ultrahigh-density storage devices.

In the early 1990s, Mamin and Rugar at the IBM Almaden Research Center pioneered the capability of using an AFM tip for writing and readback of topographic features for data storage. In one of their schemes [31.5], writing and reading were demonstrated with a single AFM tip in contact with a rotating polycarbonate substrate. The writing was performed thermomechanically by heating the tip. In this way, storage densities of up to 30 $\mathrm{Gb/in^2}$ were achieved, constituting a significant advance over the densities of that time. Later refinements included increasing readback speeds to attain a data rate of 10 Mb/s [31.6] and the implementation of track servoing [31.7].

When using single tips in AFM or STM operation for storage, one has to deal with their fundamental data-rate limitations. At present, the mechanical resonant frequencies of the AFM cantilevers limit the data rates of a single cantilever to a few Mb/s for AFM data storage [31.8, 9]. The feedback speed and low tunneling currents limit STM-based storage approaches to even lower data rates.

Currently a single AFM operates at best on the microsecond time scale. Conventional magnetic storage, however, operates at best on the nanosecond time scale, making it clear that AFM data rates have to be improved by at least three orders of magnitude to be competitive with current and future magnetic recording. One solution for substantially increasing the data rates achievable by tip-based storage devices is to employ micro-electro-mechanical system (MEMS) arrays of cantilevers operating in parallel, with each cantilever performing write/read/erase operations in an individual storage field. It is our conviction that very large-scale integrated (VLSI) micro/nanomechanics will greatly complement future micro- and nanoelectronics (integrated or hybrid) and may generate hitherto inconceivable applications of VLSI-MEMS.

Various efforts are under way to develop MEMS-based storage devices. For example, a MEMS-actuated magnetic-probe-based storage device capable of storing 2 GB of data on 2 $\mathrm{cm^2}$ of die area and whose fabrication is compatible with a standard integrated circuit manufacturing process is described by *Carley* et al. [31.10]. In their device, a magnetic storage medium is positioned in the x/y plane, and writing is achieved magnetically by using an array of probe tips, each tip being actuated in the z-direction. Another concept is the atomic resolution storage described by *Gibson* et al. [31.11], who employ electron field emitters to change the state of a phase-change medium in a bit-wise fashion from polycrystalline to amorphous or vice versa. Reading is done with lower currents by detecting either back-scattered electrons or changes in the semiconductor properties in the media.

The "millipede" concept presented here is a new approach for storing data at high speed and ultrahigh density. The interesting part is that millipede stores digital information in a completely different way from magnetic hard disks, optical disks, and transistor-based memory chips. The ultimate locality is provided by a tip, and high data rates are a result of massive parallel operation of such tips. As storage medium, polymer films are being considered, although the use of other media, in particular, magnetic materials, has not been ruled out. Our current effort is focused on demonstrating the millipede concept with areal densities of up to $0.5-1\,\text{Tb/in}^2$ and parallel operation of very large 2-D (up to 64×64) AFM cantilever arrays with integrated tips and write/read/erase functionality. The fabrication and integration of such a large number of mechanical devices (cantilever beams) will lead to what we envision as the VLSI age of micro- and nanomechanics.

In this chapter, the millipede concept for a MEMS-based storage device is described in detail. In particular, various aspects pertaining to AFM thermomechanical read/write/erase functions, 2-D array fabrication and characteristics, $x/y/z$ microscanner design, polymer media properties, read channel modeling, servo control and synchronization, as well as modulation coding techniques suitable for probe-based data-storage devices are discussed.

31.1 The Millipede Concept

A 2-D AFM cantilever array storage technique [31.13–15], internally called the millipede, is illustrated in Fig. 31.1. Information is stored as sequences of indentations and no indentations written on nanometer-thick polymer films using the array of AFM cantilevers. The presence and absence of indentations will also be referred to as logical marks. Each cantilever performs write/read/erase operations over an individual storage field with an area on the order of $100\times100\,\mu\text{m}^2$. Write/read operations depend on a mechanical parallel x/y scanning of either the entire cantilever array chip or the storage medium. The tip-medium contact is maintained and controlled globally, i. e., not on an individual cantilever basis, by using a feedback control in the z-direction for the entire chip, which greatly simplifies the system. This basic concept of the entire chip approach/leveling has been tested and demonstrated for the first time by parallel imaging with a 5×5 array chip [31.16, 17]. These parallel imaging results have shown that all 25 cantilever tips have approached the substrate within less than $1\,\mu\text{m}$ of z-actuation, which indicates that overall chip tip-apex height control to within 500 nm is feasible. The stringent requirement for tip-apex uniformity over the entire chip is determined by the uniform force required to reduce tip and medium wear due to large force variations resulting from large tip-height nonuniformities [31.7]. Moreover, as the entire array is tracked without individual lateral cantilever positioning, thermal expansion of the array chip has to be small or well controlled. Thermal expansion considerations are a strong argument for a 2-D instead of a 1-D array arrangement.

Efficient parallel operations of large 2-D arrays can be achieved by a row/column time-multiplexed addressing scheme similar to that implemented in DRAMs. In the case of the millipede, the multiplexing scheme is used to address the array column by column with full parallel write/read operation within one column [31.18]. In particular, readback signal samples are obtained by applying an electrical read pulse to the cantilevers in a column of the array, low-pass filtering the cantilever response signals, and finally sampling the filter output signals. This process is repeated sequentially until all columns of the array have been addressed, and then restarted from the first column. The time between two pulses applied to the cantilevers of the same column corresponds to the time it takes for a cantilever to move from one logical mark position to the next. An alternative approach is to access all or a subset of the cantilevers simultaneously without resorting to the row/column multiplexing scheme. Clearly, the latter scheme yields higher data rates, whereas the former leads to lower implementation complexity of the channel electronics.


2-D cantilever array chip
Multiplex driver
MUX
MUX
x
y
Polymer storage medium on xyz scanner

Fig. 31.1 The millipede concept (after [31.12])

31.2 Thermomechanical AFM Data Storage

In recent years, AFM thermomechanical recording in polymer storage media has undergone extensive modifications mainly with respect to the integration of sensors and heaters designed to enhance simplicity and to increase data rate and storage density. Thermomechanical writing in polycarbonate films and optical readback was first investigated and demonstrated by Mamin and Rugar (1992). Using heater cantilevers, thermomechanical recording at 30 Gb/in^2 storage density and data rates of a few Mb/s for reading and 100 kb/s for writing have been demonstrated [31.5, 6, 19]. Although the storage density of 30 Gb/in^2 obtained originally was not overwhelming, the results were encouraging enough to consider using polymer films to achieve density improvements. The current millipede storage approach is based on a new thermomechanical write/read process in nanometer-thick polymer films.

Thermomechanical writing is achieved by applying a local force through the cantilever/tip to the polymer layer and simultaneously softening the polymer layer by local heating. Initially, the heat transfer from the tip to the polymer through the small contact area is very poor, but it improves as the contact area increases. This means that the tip must be heated to a relatively high temperature of about 400 °C to initiate softening. Once softening has been initiated, the tip is pressed into the polymer, and hence the indentation size is increased. Rough estimates [31.20, 21] indicate that at the beginning of the writing process only about 0.2% of the heating power is used in the very small contact zone (10–40 nm^2) to soften the polymer locally, whereas about 80% is lost through the cantilever legs to the chip body and about 20% is radiated from the heater platform through the air gap to the medium/substrate. After softening has started and the contact area has increased, the heating power available for generating the indentations increases at least ten times to reach 2% or more of the total heating power.

With this highly nonlinear heat-transfer mechanism it is very difficult to achieve small tip penetration and hence small bit sizes, as well as to control and reproduce the thermomechanical writing process. This situation can be improved if the thermal conductivity of the substrate is increased and if the depth of tip penetration is limited. We have explored the use of very thin polymer layers deposited on Si substrates to improve these characteristics [31.22, 23], as illustrated in Fig. 31.2. The hard Si substrate prevents the tip from penetrating farther than the film thickness, and it enables more rapid transport of heat away from the heated region, as Si is a much better conductor of heat than the polymer. Using coated Si substrates with a 50-nm film of polymethylmethacrylate (PMMA), we have achieved indentation sizes of between 10 and 50 nm. However, increased tip wear has occurred, probably caused by contact between the Si tip and the Si substrate during writing. Therefore, a 70-nm layer of crosslinked photoresist (SU-8) was introduced between the Si substrate and the PMMA film to act as a softer penetration stop that avoids tip wear, but remains thermally stable.



Fig. 31.2 New storage medium used for writing small bits. A thin, writable PMMA layer is deposited on a Si substrate separated by a cross-linked film of epoxy photoresist (after [31.15])



Fig. 31.3a–c Series of 40-nm indentations formed in a uniform array with **(a)** 120-nm pitch and **(b)** variable pitch ($\geq$ 40 nm), resulting in areal densities of up to 400 Gb/in^2. Images obtained with a thermal readback technique. **(c)** Ultra-high-density bit writing with areal densities approaching 1 Tb/in^2. The scale is the same for all three images (from [31.15] © 2002 IEEE)

Using this layered storage medium, indentations 40 nm in diameter have been written as shown in Fig. 31.3. These experiments were performed using a 1-µm-thick, 70-µm-long, two-legged Si cantilever [31.19]. The cantilever legs are made highly conducting by high-dose ion implantation, whereas the heater region remains low-doped. Electrical pulses 2 µs in duration were applied to the cantilever with a period of 50 µs. Figure 31.3a demonstrates that 40-nm bits can be written with 120-nm pitch or, as shown in Fig. 31.3b, very close to each other without merging, implying a potential areal density of 400 Gb/in^2. Figure 31.3c shows recent results from a single-lever experiment, where indentations are spaced as closely as 25 nm apart, resulting in areal densities of up to 1 Tb/in^2, although with a somewhat degraded write/read quality.

Imaging and reading are performed by a new thermomechanical sensing concept [31.24]. To read the written information, the heater cantilever originally used for writing is given the additional function of a thermal readback sensor by exploiting its temperature-dependent resistance. In general, the resistance increases nonlinearly with heating power/temperature from room temperature to a peak value at 500–700 °C. The peak temperature is determined by the doping concentration of the heater platform, which ranges from 1×10^{17} to 2×10^{18} at/cm^3. Above the peak temperature, the resistance drops as the number of intrinsic carriers increases due to thermal excitation [31.25]. For sensing, the resistor is operated at about 350 °C, a temperature that is not high enough to soften the polymer as in the case of writing. The principle of thermal sensing is based on the fact that the thermal conductance between the heater platform and the storage substrate changes according to the distance between them. The medium between the heater platform and the storage substrate, in our case air, transports heat from the cantilever to the substrate. When the distance between cantilever and storage substrate is reduced as the tip moves into an indentation, the heat transport through the air becomes more efficient. As a result, the evolution of the heater temperature differs in response to a pulse applied to the cantilever. In particular, the maximum value achieved by the heater temperature is higher in the absence of an indentation. As the value of the variable resistance depends on the temperature of the cantilever, the maximum value achieved by the resistance will be lower as the tip moves into an indentation. Therefore, during the read process, the cantilever resistance reaches different values depending on whether the tip moves into an indentation (logical bit "1") or over a region without an indentation (logical bit "0"). Figure 31.4 illustrates this concept.


Scan direction
Sensing current
Polymer double layer
Less cooling by substrate
More cooling by substrate
50-nm PMMA medium layer
70-nm cross-linked SU-8 underlayer
→ $T\searrow$ → $R\searrow$
$\Delta R^{\Theta}/R^{\Theta} \sim 10^{-5}$ per nm

Fig. 31.4 Principle of AFM thermal sensing. The tip of the heater cantilever is continuously heated by a dc power supply while the cantilever is being scanned and the heater resistivity measured (after [31.15])

Under typical operating conditions, the sensitivity of thermomechanical sensing is even greater than that of piezoresistive-strain sensing, which is not surprising because thermal effects in semiconductors are stronger than strain effects. The good sensitivity is demonstrated by the images of the 40-nm-sized indentations in Fig. 31.3, which were obtained using the described thermal-sensing technique.

The thermomechanical cantilever sensor, which transforms temperature into an electrical signal that carries information, is the electrical equivalent, to a first degree of approximation, of a variable resistance. A detection circuit must, therefore, sense a voltage that depends on the value of the cantilever resistance to decide whether a "1" or a "0" is written. The relative variation of thermal resistance is on the order of 10^{-5}/nm. Hence a written "1" typically produces a relative change of the cantilever thermal resistance $\Delta R^{\Theta}/R^{\Theta}$ of about 10^{-4} to 5×10^{-4}. Note that the relative change of the cantilever electrical resistance is of the same order of magnitude. Thus, one of the most critical issues in detecting the presence or absence of an indentation is the high resolution required to extract the signal that contains the information about the logical bit being "1" or "0". The signal carrying the information can be regarded as a small signal superimposed on a very large offset signal. The large offset problem can be mitigated by subtracting a suitable reference signal [31.12, 26, 27].

31.3 Array Design, Technology, and Fabrication

Encouraged by the results of the 5×5 cantilever array [31.16, 17], a 32×32 array chip was designed and fabricated [31.18]. With the findings from the fabrication and operation of the 5×5 array and the very dense thermomechanical writing/reading in thin polymers with single cantilevers, some important changes of the chip functionality and fabrication processes were made. The major differences are (1) surface micromachining to form cantilevers at the wafer surface, (2) all-silicon cantilevers, (3) thermal instead of piezoresistive sensing, and (4) first- and second-level wiring with an insulating layer for a multiplexed row/column-addressing scheme.


Nickel bridge
Metal 1
Gold
Highly doped silicon cantilever leg
Metal 2
Nickel
Low doped Schottky diode area
Stress-controlled nitride
Silicon cantilever
Heater platform

Fig. 31.5 Layout and cross section of one cantilever cell (after [31.28])



Fig. 31.6 Photograph of fabricated chip (14×7 mm^2). The 32×32 cantilever array is located at the center with bond pads distributed on either side (from [31.28] © 1999 IEEE)

As the heater platform functions as a read/write element and no individual cantilever actuation is required, the basic array cantilever cell becomes a simple two-terminal device addressed by a multiplexed x/y wiring, as shown in Fig. 31.5. The cell area and x/y cantilever pitch are 92×92 µm^2, which results in a total array size of less than 3×3 mm^2 for the 1,024 cantilevers. The cantilevers are fabricated entirely of silicon for good thermal and mechanical stability. They consist of a heater platform with the tip on top, legs acting as soft mechanical springs, and electrical connections to the heater. They are highly doped to minimize interconnect resistance and to replace the metal wiring on the cantilever in order to eliminate electromigration and parasitic z-actuation of the cantilever due to a bimorph effect. The resistive ratio between the heater and the silicon interconnect sections should be as high as possible; currently the resistance of the highly doped interconnections is ∼ 400 Ω and that of the heater platform is 5 kΩ (at 3 V reading bias).

The cantilever mass has to be minimized to obtain soft, high-resonant-frequency cantilevers. Soft cantilevers are required for a low loading force in order to eliminate or reduce tip and medium wear, whereas a high resonant frequency allows high-speed scanning. In addition, sufficiently wide cantilever legs are required for a small thermal time constant, which is partly determined by cooling via the cantilever legs [31.19]. These design considerations led to an array cantilever with 50-µm-long, 10-µm-wide and 0.5-µm-thick legs, and a 5-µm-wide, 10-µm-long and 0.5-µm-thick heater platform. Such a cantilever has a stiffness of ∼ 1 N/m and a resonant frequency of ∼ 200 kHz. The heater time constant is a few microseconds, which should allow a multiplexing rate of up to 100 kHz.

The tip height should be as small as possible because the heater platform sensitivity depends strongly on the platform-to-medium distance. This contradicts the requirement of a large gap between the chip surface and the storage medium to ensure that only the tips, and not the chip surface, make contact with the medium. Instead of making the tips longer, we purposely bent the cantilevers a few micrometers out of the chip plane by depositing a stress-controlled plasma-enhanced chemical vapor deposition (PECVD) silicon-nitride layer at the base of the cantilever (see Fig. 31.5). This bending as well as the tip height must be well controlled in order to maintain an equal loading force for all cantilevers of an array.

Cantilevers are released from the crystalline Si substrate by surface micromachining using either plasma or wet chemical etching to form a cavity underneath the cantilever. Compared to a bulk-micromachined through-wafer cantilever-release process, as was done for our 5 × 5 array [31.16, 17], the surface micromachining technique allows an even higher array density and yields better mechanical chip stability and heat sinking. As mentioned above, the entire array is tracked without individual lateral cantilever positioning, therefore thermal expansion of the array chip has to be small or well controlled. For a 3 × 3-mm^2 silicon array area and 10-nm tip-position accuracy, the temperature difference between array chip and medium substrate has to be controlled to about 1 °C. This is ensured by four temperature sensors in the corners of the array and heater elements on each side of the array.

The photograph in Fig. 31.6 shows a fabricated chip with the 32 × 32 array located in the center (3 × 3 mm^2) and the electrical wiring interconnecting the array with the bonding pads at the chip periphery. Figure 31.7 shows the 32 × 32 array section of the chip with the independent approach/heat sensors in the four corners and the heaters on each side of the array, as well as zoomed scanning electron micrographs (SEMs) of an array section, a single cantilever, and a tip apex. The tip height is 1.7 µm and the apex radius is smaller than 20 nm, which is achieved by oxidation sharpening [31.29]. The cantilevers are connected to the column and row address lines using integrated Schottky diodes in series with the cantilevers. The diode is operated in reverse bias (high resistance) if the cantilever is not addressed, thereby greatly reducing cross talk between cantilevers. More details about the array fabrication are given in [31.28, 30].



Fig. 31.7 SEM images of the cantilever array section with approaching and thermal sensors in the corners, array and single cantilever details, and tip apex (© 2000 International Business Machines Corporation; after [31.18])

31.4 Array Characterization

The array’s independent cantilevers, which are located in the four corners of the array and used for approaching and leveling the chip and storage medium, serve to initially characterize the interconnected array cantilevers. Additional cantilever test structures are distributed over the wafer; they are equivalent to but independent of the array cantilevers. Figure 31.8 shows an I/V curve of such a cantilever; note the nonlinearity of the resistance. In the low-power part of the curve, the resistance increases as a function of heating power, whereas in the high-power regime, it decreases.

In the low-power, low-temperature regime, silicon mobility is affected by phonon scattering, which depends on temperature, whereas at higher power, the intrinsic temperature of the semiconductor is reached, which results in a resistivity drop owing to the increasing number of carriers [31.25]. Depending on the heater-platform doping concentration of 1×10^{17} to 2×10^{18} at/cm^3, our calculations estimate a resistance maximum at a temperature of 500 to 700 °C, respectively.

The cantilevers within the array are electrically isolated from one another by integrated Schottky diodes. As every parasitic path in the array to the cantilever addressed contains a reverse-biased diode, the cross talk current is drastically reduced, as shown in Fig. 31.9. Thus, the current response of an addressed cantilever in an array is nearly independent of the size of the array, as demonstrated by the I/V curves in Fig. 31.9. Hence, the power applied to address a cantilever is not shunted by other cantilevers, and the reading sensitivity is not degraded – not even for very large arrays (32 × 32). The introduction of the electrical isolation using integrated



Fig. 31.8 *I*/*V* curve of one cantilever. The curve is nonlinear owing to the heating of the platform as the power and temperature are increased. For doping concentrations between 1×10^{17} and 2×10^{18} at/cm^3, the maximum temperature varies between 500 and 700 °C (after [31.30])



Fig. 31.9 Comparison of the *I*/*V* curve of an independent cantilever (*solid black line*) with the current response when addressing a cantilever in a 5×5 (*solid brown line*) or a 32×32 (*dashed line*) array with a Schottky diode serially connected to the cantilever. Little change is observed in the *I*/*V* curve between the different cases. Inset: sketch of the direct path (*bold line*) and a parasitic path (*thin line*) in a cantilever-diode array. In the parasitic path there is always one diode in reverse bias that reduces the parasitic current (after [31.30])

Schottky diodes turned out to be crucial for the successful operation of interconnected cantilever arrays with a simple time-multiplexed addressing scheme.

The tip-apex height uniformity within an array is very important because it determines the force of each cantilever while in contact with the medium and hence influences write/read performance, as well as medium and tip wear. Wear investigations suggest that a tip-apex height uniformity across the chip of less than 500 nm



Fig. 31.10 Tip-apex height uniformity across one cantilever row of the array with individual contributions from the tip height and cantilever bending. (© 2000 International Business Machines Corporation; after [31.18])

is required [31.7], with the exact number depending on the spring constant of the cantilever. In the case of the millipede, the tip-apex height is determined by the tip height and the cantilever bending. Figure 31.10 shows the tip-apex height uniformity of one row of the array (32 tips) due to tip height and cantilever bending. It demonstrates that our uniformity is on the order of 100 nm, thus meeting the requirements.

31.5 *x*/*y*/*z* Medium Microscanner

A key issue for the millipede concept is the need for a low-cost, miniaturized scanner with $x/y/z$ motion capabilities and a lateral scanning range on the order of 100 μm. Multiple-probe systems arranged as 1-D or 2-D arrays [31.18] must also be able to control, by means of tilt capabilities, the parallelism between the probe array and the sample [31.18, 32].

We have developed a microscanner with these properties based on electromagnetic actuation. It consists of a mobile platform supported by springs and containing integrated planar coils positioned over a set of miniature permanent magnets [31.33]. A suitable arrangement of the coils and magnets allows us, by electrically addressing the various coils, to apply magnetically induced forces to the platform and drive it in the x, y, z, and tilt directions. Our first silicon/copper-based version of this device has proved the validity of the concept [31.34], and variations of it have since been used elsewhere [31.35]. However, the undamped copper spring system gave rise to excessive cross talk and ringing when driven in an open loop, and its layout limited the compactness of the overall device.

We investigate a modified microscanner that uses flexible rubber posts as a spring system and a copper-epoxy-based mobile platform, Fig. 31.11. The platform is made of a thick, epoxy-based SU-8 resist [31.36], in which the copper coils are embedded. The posts are made of polydimethylsiloxane (PDMS, Sylgard 184 silicon elastomer, Dow Corning, Midland, MI) and are fastened at the corners of the platform and at the ground plate, providing an optimally compact device by sharing the space below the platform with the magnets. The shape of the posts allows their lateral and longitudinal stiffness to be adjusted, and the dissipative rubber-like properties of PDMS provide damping to avoid platform ringing and to suppress nonlinearities.

Figure 31.12 shows the layout of the platform, which is scaled laterally, so that the long segments of the "racetrack" coils used for in-plane actuation coincide with commercially available 24 mm^2 SmCo magnets. The thickness of the device is determined by that of the magnets (1 mm), the clearance between magnet and platform (500 μm), and the thickness of the platform itself, which is 250 μm and determined mainly by the aspect ratio achievable in SU-8 resist during the exposure of the coil plating mold. The resulting device volume is approximately $15 \times 15 \times 1.6\,\mathrm{mm}^3$.


Mobile platform with integrated coils
Lateral scanning
Z/Tilt motion
Flexible PDMS posts (combined spring & damping)
Permanent magnets

Fig. 31.11 Microscanner concept using a mobile platform and flexible posts (after [31.31])



Fig. 31.12 Arrangement of the coils, the interconnects, and the permanent magnets, as well as the various motions addressed by the corresponding coils (from [31.15] © 2002 IEEE)

The SmCo magnets produce a measured magnetic field intensity of ∼ 0.14 T at the mid-thickness of the coils. The effective coil length is 320 mm, yielding an expected force $F_{x,y}$ of 45 µN per mA of drive current.

The principal design issue of the spring system is the ratio of its stiffnesses for in-plane and out-of-plane motion. Whereas for many scanning probe applications the required z-axis range need not be much larger than a few microns, it is necessary to ensure that the z-axis retraction of the platform due to the shortening of the posts as they take on an S-shape at large in-plane deflections can be compensated for at acceptable z-coil current levels. Various PDMS post shapes have been investigated to optimize and trade off the various requirements. Satisfactory performance was found for simple O-shapes [31.31].

The fabrication of the scanner, Fig. 31.13, starts on a silicon wafer with a seed layer and a lithographically patterned 200-µm-thick SU-8 layer, in which copper is electroplated to form the coils (Fig. 31.13a). The coils typically have 20 turns, with a pitch of 100 µm and a spacing of 20 µm. Special care was taken in the resist processing and platform design to achieve the necessary aspect ratio and to overcome adhesion and stress problems of SU-8. A second SU-8 layer, which serves as an insulator, is patterned with via holes, and another seed layer is then deposited (Fig. 31.13b). Next, an interconnect level is formed using a Novolac-type resist mask and a second copper-electroplating step (Fig. 31.13c). After stripping the resist, the silicon wafer is dissolved by a sequence of wet and dry etching, and the exposed seed layers are sputtered away to prevent shorts (Fig. 31.13d).

The motion of the scanner was characterized using a microvision strobe technique [31.37]. The results presented below are based on O-type PDMS ports. Frequency response curves for in-plane motion (Fig. 31.14) show broad peaks (characteristic of a large degree of damping) at frequency values that are consistent with expectations based on the measured mass of the platform (0.253 mg). The amplitude response (Fig. 31.15) displays the excellent linearity of the spring system for displacement amplitudes up to 80 µm (160-µm displacement range). Based on these near-DC (10 Hz) responses (∼ 1.4 µm/mA) and a measured circuit resistance of 1.9 Ω, the power necessary for a 50-µm displacement amplitude is approximately equal to 2.5 mW.

Owing to limitations of the measurement technique, it was not possible to measure out-of-plane displacements greater than 0.5 µm. However, the small-



Fig. 31.13a–d Cross section of the platform fabrication process. **(a)** Coils are electroplated through an SU-8 resist mask, which is retained as the body of the platform; **(b)** an insulator layer is deposited; **(c)** interconnects are electroplated; **(d)** the platform is released from the silicon substrate (after [31.31])



Fig. 31.14 Frequency response for in-plane x- and y-axis motion. The mechanical quality factors measured are between 3.3 and 4.6 (after [31.15])



Fig. 31.15 In-plane displacement amplitude response for an ac drive current at 10 Hz (off resonance) (after [31.15])



Fig. 31.16 Out-of-plane amplitude response for an ac drive current at 3 Hz. The drive current is the total for all four corner coils, which are driven in phase (after [31.31])

amplitude response for z-motion when all four corner coils are driven in-phase also displays good linearity over the range that can be measured (Fig. 31.16).

The electromagnetic scanner performs reliably and as predicted in terms of the scan range, device volume, and power requirements, achieving overall displacement ranges of 100 µm with approximately 3 mW of power. The potential access time in the 100-µm storage field is on the order of a few milliseconds. By being potentially cheap to manufacture, the integrated scanner presents a good alternative actuation system for many scanning probe applications.

31.6 First Write/Read Results with the 32×32 Array Chip

We have built a prototype that includes all the basic building blocks of the millipede concept (see Fig. 31.1) [31.38]. A 3×3-mm^2 silicon substrate is spin-coated with the SU-8/PMMA polymer medium, as described in Sect. 31.3. This storage medium is attached to the $x/y/z$ microscanner and approaching device. The magnetic z-approaching actuators bring the medium into contact with the tips of the array chip. The z-distance between the medium and the millipede chip is controlled by the approaching sensors in the corners of the array. The signals from these cantilevers are used to determine the forces on the z-actuators and, hence, the forces of the cantilever while it is in contact with the medium. This sensing/actuation feedback loop continues to operate during x/y scanning of the medium. The PC-controlled write/read scheme addresses the 32 cantilevers of one row in parallel. Writing is performed by connecting the addressed row for 20 µs to a high negative voltage and simultaneously applying data inputs ("0" or "1") to the 32 column lines. The data input is a high positive voltage for a "1" and ground for a "0". This row-enabling and column-addressing scheme supplies a heater current to all cantilevers, but only those cantilevers with high positive voltage generate an indentation ("1"). Those grounded are not hot enough to form an indentation and thus write a "0". When the scan stage has moved to the next logical mark position, the process is repeated, and this is continued until the line scan is finished. In the read process, the selected row line is connected to a moderate negative voltage, and the column lines are grounded via a protection resistor of about 10 kΩ, which keeps the cantilevers warm. During scanning, the voltages across the resistors are measured. Depending on the topography of the recording surface, the degree of cooling of each cantilever varies, thus changing the resistance and voltage across the series resistor and allowing written data to be read back.

The results of writing and reading in this fashion can be seen in Fig. 31.17, which shows 1,024 images corresponding to the 1,024 storage fields and associ-



Fig. 31.17 **(a)** 1,024 images, each one obtained from a cantilever of the 2-D array. **(b)** Enlarged view of typical images from **(a)**. The numbers in the images indicate the row and column of each lever (from [31.38])

ated cantilevers. Of the 1,024 levers, 834 were able to write and read data back, i. e., a success rate of more than 80%. The sequence is as follows. First, a bit pattern is written simultaneously by each of the levers in row 1, then read back simultaneously, followed by row 2, etc. through row 32. The data sent to the levers is different, each lever writing its own row and column number in the array. The bit pattern consists of 64 × 64 bits, where odd-numbered bits are always set to 0. In this case, the area used is $6.5 \times 6.5\,\mu\text{m}^2$. The readback image is a grey-scale bit map of 128 × 128 pixels. The distance between levers is 92 µm, so the images in Fig. 31.17 are also 92 µm apart. The areal density of the written information shown in Fig. 31.17 corresponds to $15{-}30\,\text{Gb/in}^2$, depending on the coding scheme adopted. More recently, an areal density of $150{-}200\,\text{Gb/in}^2$, at an array yield of about 60%, has been demonstrated.

Those levers that did not read back failed for one of four reasons: (i) a defective chip connector rendered an entire column unusable, (ii) a point defect occurred, meaning that a single lever or tip was broken, (iii) there was a nonuniformity of the tip contact due to tip/lever variability or storage substrate bowing due to mounting, (iv) there were thermal drifts. The latter two reasons were the most likely and major failure sources. At present, there is clearly a tradeoff between the number of working levers and the density, which will most likely be resolved by a better substrate/chip mounting technique and lower thermal drifts.

The writing and readback rates achieved with this system are 1 kb/s per lever, thus, the total data rate is about 32 kb/s. This rate is limited by the rate at which data can be transferred over the PC ISA bus, not by a fundamental time limitation of the read/write process.

31.7 Polymer Medium

The polymer storage medium plays a crucial role in millipede-like thermomechanical storage systems. The thin-film multilayer structure with PMMA as active layer (see Fig. 31.2) is not the only possible choice, considering the almost unlimited range of polymer materials available. The ideal medium should be easily deformable for writing, yet indentations should be stable against tip wear and thermal degradation. Finally, one would also like to be able to erase and rewrite data repeatedly. In order to be able to address all important aspects properly, some understanding of the basic physical mechanism of thermomechanical writing and erasing is required.

31.7.1 Writing Mechanism

In a *gedanken* experiment we visualize writing of an indentation as the motion of a rigid body (the tip) in a viscous medium (the polymer melt). Let us initially assume that the polymer, i. e., PMMA, behaves like a simple liquid after it has been heated above the glass-transition temperature in a small volume around the tip. As viscous drag forces must not exceed the loading force applied to the tip during indentation, we can estimate an upper bound for the viscosity ζ of the polymer melt using Stokes's equation:

$$F = 6\pi\zeta\varrho v\ . \qquad (31.1)$$

In actual indentation formation, the tip loading force is on the order of $F = 50\,\text{nN}$ and the radius of curvature at the apex of the tip is typically $\varrho = 20\,\text{nm}$. Assuming a depth of the indentation of, say, $h = 50\,\text{nm}$ and a heat pulse of $\tau_h = 10\,\mu\text{s}$ duration, the mean velocity during indentation formation is on the order of $v = h/\tau_h = 5\,\text{mm/s}$. Note that thermal relaxation times are on the order of microseconds [31.20, 21] and, hence, the heating time can be equated to the time it takes to form an indentation. With these parameters we obtain $\zeta < 25\,\text{Pa s}$, whereas typical values for the shear viscosity of PMMA are at least seven orders of magnitude larger even at temperatures well above the glass-transition point [31.39].

This apparent contradiction can be resolved by considering that polymer properties are strongly dependent on the time scale of observation. At time scales on the order of 1 ms and below, entanglement motion is in effect frozen in and the PMMA molecules form a relatively static network. Deformation of the PMMA now proceeds by means of uncorrelated deformations of short molecular segments, rather than by a flow mechanism involving the coordinated motion of entire molecular chains. The price one has to pay is that elastic stress builds up in the molecular network as a result of the deformation (the polymer is in a so-called rubbery state). On the other hand, corresponding relaxation times are orders of magnitude smaller, giving rise to an effective viscosity at millipede time scales on the order of 10 Pa s [31.39], as required by our simple argument (see (31.1)). Note that, unlike normal viscosity, this high-frequency viscosity is basically independent of the detailed molecular structure of the PMMA, i. e., chain length, tacticity, polydispersity, etc. In fact, we can even expect that similar high-frequency viscous properties can be found in a large class of other polymer materials, which makes thermomechanical writing a rather robust process in terms of material selection.

We have argued above that elastic stress builds up in the polymer film during the formation of an indentation, creating a corresponding reaction force on the tip on the order of $F_r \sim 2\pi G\varrho^2$, where G denotes the elastic shear modulus of the polymer [31.40]. An important property for millipede operation is that the shear modulus drops by several orders of magnitude in the glass-transition regime, i. e., for PMMA from $\sim 1\,\text{GPa}$ below Θ_g to $\sim 0.5{-}1\,\text{MPa}$ above Θ_g, where Θ_g denotes the glass-transition temperature [31.39]. The bulk modulus, on the other hand, retains its low-temperature value of several GPa. Hence, in this elastic regime, formation of an indentation above Θ_g constitutes a volume-preserving deformation. For proper indentation formation, the tip load must be balanced between the extremes of the elastic reaction force F_r for temperatures below and above Θ_g, i. e., $F \ll 2.5\,\mu\text{N}$ for PMMA to prevent indentation of the polymer in the cold state and $F \gg 2.5\,\text{nN}$ to overcome the elastic reaction force in the hot state. Unlike the deformation of a simple liquid, the indentation represents a metastable state of the entire deformed volume, which is under elastic tension. Recovery of the unstressed initial state is prevented by rapid quenching of the indentation below the glass temperature with the tip in place. As a result, the deformation is frozen in, because below Θ_g motion of molecular-chain segments is, in effect, inhibited (see Fig. 31.18).

This mechanism also allows indentations to be erased locally – it suffices to heat the deformed volume locally above Θ_g, whereupon the indented volume reverts to its unstressed flat state driven by internal elastic stress. In addition, erasing is promoted by surface tension forces, which give rise to a restoring surface pressure on the order of $\gamma(\pi/\varrho)^2 h \approx 25\,\text{MPa}$, where $\gamma \sim 0.02\,\text{N/m}$ denotes the polymer-air surface tension.

One question immediately arises from these speculations: If the polymer behavior can be determined from the macroscopic characteristics of the shear modulus as a function of time, temperature, and pressure, can the time-temperature superposition principle also be applied in this case? The time-temperature superposition principle is a powerful concept of polymer physics [31.41]. It basically states that the time scale and the temperature are interdependent variables that determine the polymer behavior such as the shear modulus. A simple transformation can be used to translate time-dependent into temperature-dependent data and vice versa. It is not clear, however, whether this principle can be applied in our case, i. e., under such extreme conditions (high pressures, short time scales, and nanometer-sized volumes, which are clearly below the radius of gyration of individual polymer molecules).

To test this, we varied the heating time, the heating temperature, and the loading force in indentation-writing experiments on a standard PMMA sample. The results



Fig. 31.18a–c Viscoelastic model of indentation writing. **(a)** The hot tip heats a small volume of polymer material to more than Θ_g. The shear modulus of the polymer drops drastically from GPa to MPa, which in turn allows the tip to indent the polymer. In response, elastic stress (represented as compression springs) builds up in the polymer. In addition, viscous forces (represented as pistons) associated with the relaxation time for the local deformation of molecular segments limit the indentation speed. **(b)** At the end of the writing process, the temperature is quenched on a microsecond time scale to room temperature: The stressed configuration of the polymer is frozen-in (represented by the locked pistons). **(c)** The final indentation corresponds to a metastable configuration. The original unstressed flat state of the polymer can be recovered by heating the indentation volume to more than Θ_g, which unlocks the compressed springs (after [31.15])



Fig. 31.19 Indentation-writing threshold measurements. The load was controlled by pushing the cantilever/tip into the sample with a controlled displacement and a known spring constant of the cantilever. When a certain threshold is reached, the indentations become visible in subsequent imaging scans (see also Fig. 31.21). The *solid lines* are guides to the eye. Curves of similar shape would be expected from the time-temperature superposition principle (after [31.15])

are summarized in Fig. 31.19. The minimum heater temperature at which the formation of an indentation starts for a given heating-pulse length and loading force was determined. This so-called threshold temperature is plotted against the heating-pulse length. A careful calibration of the heater temperature has to be done to allow a comparison of the data. The heater temperature was determined by assuming proportionality between temperature and electrical power dissipated in the heater resistor at the end of the heating pulse when the tip has reached its maximum temperature. An absolute temperature scale is established using two well-defined reference points. One is room temperature, corresponding to zero electrical power. The other is provided by the point of turnover from positive to negative differential resistance (see Fig. 31.8), which corresponds to a heater temperature of approximately 550 °C. The general shape of the measured threshold temperature versus heating time curves indeed shows the characteristics of time-temperature superposition. In particular, the curves are identical up to a load-dependent shift with respect to the time axis. Moreover, we observe that the time it takes to form an indentation at constant heater temperature is inversely proportional to the tip load. This property is exactly what one would expect if internal friction (owing to the high-frequency viscosity) is the rate-limiting step in forming an indentation (see (31.1)).

The time it takes to heat the indentation volume of polymer material higher than the glass-transition temperature is another potentially rate-limiting step. Here, the spreading resistance of the heat flow in the polymer and the thermal contact resistance are the most critical parameters. Simulations suggest [31.20, 21] that equilibration of temperature in the polymer occurs within less than 1 µs. Very little is known, however, about the thermal coupling efficiency across the tip-polymer interface. We have several indications that the heat transfer between tip and sample plays a crucial role, one of them being the asymptotic heater temperature for long writing times, which according to the graph in Fig. 31.19 is approximately 200 °C. The exact temperature of the polymer is unknown. However, the polymer temperature should approach the glass-transition temperature (around 120 °C for PMMA) asymptotically. Hence, the temperature drop between heater and polymer medium is substantial. Part of the temperature difference is due to a temperature drop along the tip, which according to heat-flow simulations [31.20, 21] is expected to be on the order of 30 °C at most. Therefore, a significant temperature gradient must exist in the tip-polymer contact zone. Further experiments on the heat transfer from tip to surface are needed to clarify this point.

We also find that the heat transfer for a nonspherical tip is anisotropic. As shown in Fig. 31.20, in the case of a pyramid-shaped tip, the indentation not only exhibits sharp edges, but also the region around the indentation, where polymer material is piled up, is anisotropic. The pile-up characteristics will be discussed in detail below. At this point we take it as an indication of the relevance of the heat transfer to the measurements.

One of the most striking conclusions of our model of the indentation-writing process is that it should in principle work for most polymer materials. The general behavior of the mechanical properties as a function of temperature and frequency is similar for all polymers [31.41]. The glass-transition temperature Θ_g would then be one of the main parameters that determines the threshold writing temperature.



Fig. 31.20a,b Topographic image of individual indentations. **(a)** The region around the actual indentations clearly shows the threefold symmetry of the tip, here a three-sided pyramid. **(b)** The indentations themselves exhibit sharp edges, as can be seen from the inverted 3-D image. Image size is $2\times2\,\mu\mathrm{m}^2$ (from [31.15] © 2002 IEEE)

A verification of this was found experimentally by comparing various polymer films. The samples were prepared in the same way as the PMMA samples discussed above [31.18]: by spin-casting thin films (10–30 nm) onto a silicon wafer with a photo-resist buffer. Then, threshold measurements were done by applying heat pulses with increasing current (or temperature) to the tip while the load and the heating time were held constant (load about 10 nN and heating time 10 µs). Examples of such measurements are shown in Fig. 31.21, where the increasing size and depth of indentations can be seen for different heater temperatures. A threshold can be defined based on such data and compared with the glass-transition temperature of these materials. The results show a clear correlation between the threshold heater temperature and the glass-transition temperature (see Fig. 31.22).

With our simple viscoelastic model of writing we are able to formulate a set of requirements that potential candidate materials for millipede data storage have to fulfill. First, the material should ideally exhibit a well-defined glass-transition point with a large drop of the shear modulus at Θ_g. Second, a rather high value of Θ_g (on the order of 150 °C) is preferred to facilitate thermal read back of the data without destroying the information. We have investigated a number of materials to explore the Θ_g parameter space. The fact that all polymer types tested are suitable for forming small indentations leaves us free to choose which polymer type to optimize in terms of the technical requirements for a device such as lifetime of indentations, polymer endurance of the read and write process, power consumption, etc. These are subjects of ongoing research.



Fig. 31.21 Written indentations for different polymer materials. The heating pulse length was 10 µs, the load about 10 nN. The grey scale is the same for all images. The heater temperatures for the indentation on the left-hand side are 445, 400, 365, and 275 °C for the polymers Polysulfone, PMMA II (anionically polymerized PMMA, $M \approx 26\,\mathrm{k}$), PMMA I (Polymer Standard Service, Germany, $M \approx 500\,\mathrm{k}$), and Polystyrene, respectively. The temperature increase between events on the horizontal axis is 14, 22, 20, and 9 °C, respectively (from [31.15] © 2002 IEEE)



Fig. 31.22 The heater temperature threshold for writing indentations with the same parameters as in Fig. 31.21 is plotted against the glass-transition temperature for these polymers, including poly-α-methyl-styrene (after [31.15])

31.7.2 Erasing Mechanism

It is worthwhile to look at the detailed shapes of the written indentations. The polymer material around an indentation appears piled up as can be seen, for example, in Fig. 31.20. This is not only material that was pushed aside during indentation formation as a result of volume conservation. Rather, the flash heating by the tip and subsequent rapid cooling result in an increase of the specific volume of the polymer. This phenomenon, that the specific volume of a polymer can be increased by rapidly cooling a sample through the glass transition [31.41], is well-known. Our system allows a cooling time on the order of microseconds, which is much faster than the highest rates that can be achieved with standard polymer-analysis tools. However, a quantitative measurement of the specific volume change cannot be easily performed with our type of experiments. On the other hand, the pile-up effect serves as a convenient threshold thermometer. The outer perimeter of the pile-ups surrounding the indentations corresponds to the Θ_g isotherm, and the temperature in the enclosed area has certainly reached values greater than Θ_g during the indentation process. Based on our viscoelastic model, one would thus conclude that previously written indentations that overlap with the piled up region of a subsequently written indentation should be erased.

That this pile-up effect actually works against the formation of an indentation can clearly be seen in the line scans of a series of indentations written in Polysulfone (Fig. 31.23). Here, the heating of the tip was accompanied by a rather high normal force. The force was high enough to create a small indentation, even if the tip was too cold to modify the polymer (Fig. 31.23a).

Then, with increasing tip heating, the indentations initially fill up in the piled up region (Fig. 31.23b) before they finally become deeper (Fig. 31.23c).

The pile-up phenomenon turns out to be particularly beneficial for data-storage applications. The following example demonstrates the effect. If we look at the sequence of images in Fig. 31.24, taken on a standard PMMA sample, we find that the piled up regions can overlap each other without disturbing the indentations. However, if the piled up region of an individual writing event extends over the indented area of a previously written "1", the depth of the corresponding indentation decreases markedly (Fig. 31.24d). This can be used for erasing written data. On the other hand, if the pitch between two successive indentations is decreased even further, this erasing process will no longer work. Instead, a broader indentation is formed, as shown in Fig. 31.24e. Hence, to exclude mutual interference, the minimum pitch between successive indentations, which we denote by minimum-indentation pitch ($\mathrm{BP_{min}}$), must be larger than the radius of the piled up area around an indentation.

In the example shown in Fig. 31.24, the temperature chosen was so high that the ring around the indentations was very large, whereas the depth of the indentation was limited by the stop layer underneath the PMMA material. Clearly, the temperature was too high here to form small indentations, the minimum pitch of which is around 250 nm. However, by carefully optimizing all parameters it is possible to achieve areal densities of up to 1 Tb/in^2, as demonstrated in Fig. 31.3c.

The new erasing scheme based on this volume effect switches from writing to erasing merely by decreasing the pitch of writing indentations. This can be done in a very controlled fashion, as shown in Fig. 31.25, where individual lines or predefined subareas are erased. Hence, this new erasing scheme can be made to work in a way that is controlled on the scale of individual indentations. Compared with earlier global erasing schemes [31.23], this simplifies erasing significantly.

31.7.3 Overwriting Mechanism

Overwriting data on some part of the storage medium can be achieved by first erasing the entire area and then writing the desired data on the erased surface. Although this process works well, it is time-consuming and dissipates a significant amount of power. In a millipede-based storage device, where data rate and power consumption are at a premium, such a two-step overwriting mech-



Fig. 31.23 Section through a series of indentations similar to Fig. 31.21. Here, a load of about 200 nN was applied before a heating pulse of 10-µs length was fired. The temperature of the heater at the end of the pulse has been increased from 430 to 610 °C in steps of about 10.6 °C. (a) The load was sufficient to form a plastic indentation even if the polymer was not heated enough to come near the glass transition. (b) With increasing heater temperature, the polymer swells. This eliminates the indentation, thus erasing previously written "cold" marks. (c) As this process continues, the thermomechanical formation of indentations begins to dominate until, finally, normal thermomechanical indentation writing occurs (after [31.15])



Fig. 31.24a–e Indentations in a PMMA film at several distances. The depth of the indentations is ∼ 15 nm, roughly the same as the thickness of the PMMA layer. The indentations on the left-hand side were written first, then a second series of indentations was made with decreasing distance from the first series going from **(a)** to **(e)** (after [31.15])



Fig. 31.25a–c Demonstration of the new erasing scheme: **(a)** A bit pattern recorded with variable pitch in the vertical axis (fast scan axis) and constant pitch in the horizontal direction (slow scan axis) was prepared. **(b)** Then two of the lines were erased by decreasing the pitch in the vertical direction by a factor of three, showing that the erasing scheme works for individual lines. One can also erase entire fields of indentations without destroying indentations at the edges of the fields. This is demonstrated in **(c)**, where a field has been erased from an indentation field similar to the one shown in **(a)**. The distance between the lines is 70 nm (from [31.15] © 2002 IEEE)

anism may be impractical. Instead, a one-step, direct overwriting process similar to those applied in magnetic hard-disk drives and rewritable optical drives is desired.

As discussed above, switching from writing to erasing may be achieved by decreasing the pitch of writing. It has been found experimentally that erasing can be performed effectively by halving the pitch of writing successive indentations, which is denoted as BP, provided the condition $\mathrm{BP} \approx \mathrm{BP}_{\mathrm{min}}$ is satisfied. This suggests that the basic distance unit for combined write-erase operations should be BP/2. Written indentations are spaced n units apart, where $n \geq 2$. Let us recall that the presence of an indentation corresponds to a logical bit "1" and the absence of an indentation to a logical bit "0". Logical bits are then stored in the medium at the points of a regular lattice with minimum distance between points equal to BP/2 in the on-track direction, with successive "1"s separated by at least one "0". This condition is necessary in order to avoid mutual interference between successive "1"s. It is also the basis for an important category of codes known as (d, k) codes, which are described in Sect. 31.9.3. Coding can thus be used to enable direct data overwriting in an elegant way. Direct overwriting requires the simultaneous realization of two conditions: If previously written "1"s exist where "0"s are to be written, then these "1"s have to be *erased*. On the other hand, if "0"s exist where "1"s are to be written, then these "1"s have to be *written*. Writing an indentation is performed thermomechanically as described above. Erasing an existing indentation is done by writing another indentation next to it, at a distance of BP/2 units. However, as this operation creates a new indentation shifted by BP/2 with respect to the one erased, the erasing process must be performed repeatedly until the newly created indentation lies at a position corresponding to a "1" in the new data pattern. The basic principle of erasing is illustrated in Fig. 31.26a and b. The figures show how the four bit strings 001, 010, 100, and 101 are modified into the string 010. Figure 31.27 depicts the results of a rewriting experiment; the top track shows a prestored sequence, which is to be overwritten by another sequence, shown on the bottom track for comparison. The result of direct



Fig. 31.26a,b Bit strings **(a)** 001 and 010, and **(b)** 100 and 101, overwritten to 010

overwriting of the prestored sequence is shown on the middle track.

Comparison with the sequence on the bottom track, which is written on a clean surface, illustrates the effectiveness of the proposed procedure. Although the write/read quality of overwritten data is somewhat inferior to that of data written on a clean storage surface, detection of the newly written sequence is not affected. However, repeated overwriting may further degrade the quality of stored data. As the extent and rate of degradation are important characteristics of a storage system, this remains an area of ongoing investigation.



Fig. 31.27 Experimental result of overwriting a bit sequence

31.8 Read Channel Model

Let us now consider the readback channel for a single cantilever that is scanning a storage field where bits are written as indentations or absence of indentations in the storage medium. As discussed above, a cantilever is modeled as a variable resistor that depends on the temperature at the cantilever tip. The model of the read channel, used for the design and analysis of the detection system, is illustrated in Fig. 31.28 [31.12, 26, 27].

To evaluate the evolution of the temperature of a heated cantilever during the read process, we resort to a simple RC-equivalent thermal circuit, illustrated in Fig. 31.29, where $(1+\eta_x)R^{\Theta}$ and C^{Θ} denote the thermal resistance and capacitance, respectively. The parameter $\eta_x = \Delta R^{\Theta}(x)/R^{\Theta}$ indicates the relative variation of thermal resistance that results from the small change in air-gap width between the cantilever and the storage medium. The subscript x indicates the distance in the direction of scanning from the initial point. Therefore, the parameter η_x will assume the largest absolute value when the tip of the cantilever is located at the center of an indentation. The heating power that is dissipated in the cantilever heater region is expressed as

$$P^e[t, \Theta(t,x)] = \frac{V_C^2(t)}{R^e[\Theta(t,x)]}\,, \tag{31.2}$$

where $V_C(t)$ is the voltage across the cantilever, $\Theta(t,x)$ is the cantilever temperature, and $R^e[\Theta(t,x)]$ is the temperature-dependent cantilever resistance.



Fig. 31.29 RC-equivalent thermal model of the heat transfer process (after [31.12])



Fig. 31.28 Block diagram of the detection circuit

As the heat-transfer process depends on the value of thermal resistance and on the read pulse waveform, the cantilever temperature $\Theta(t, x)$ depends on time t and distance x. However, because the time it takes for the cantilever to move from the center of one logical mark to the next is greater than the duration of a read pulse, we assume that $\Theta(t, x)$ does not vary significantly as a function of x while a read pulse is being applied, and that it decays to the ambient temperature Θ_0 before the next pulse is applied. Therefore, the evolution of the cantilever temperature in response to a pulse applied at time $t_0 = x_0/v$ at a certain distance x_0 from the initial point of scanning and for a certain constant velocity v of the scanner obeys a differential equation expressed as

$$\Theta'(t, x_0) + \frac{1}{(1+\eta_{x_0})R^{\Theta}C^{\Theta}}\left[\Theta(t, x_0) - \Theta_0\right] = \frac{1}{C^{\Theta}}\frac{V_{\mathrm{C}}^2(t)}{R^e[\Theta(t, x_0)]}, \tag{31.3}$$

where $\Theta'(t, x_0)$ denotes the derivative of $\Theta(t, x_0)$ with respect to time.

With reference to the block diagram of the read channel illustrated in Fig. 31.28, the source generates the read pulse $V_{\mathrm{P}}(t)$ applied to the cantilever. Clearly, because of the virtual ground at the operational amplifier input, the voltage $V_{\mathrm{C}}(t)$ across the cantilever variable resistance is equal to $\mathrm{V_P}(t)$. Furthermore, the active low-pass RC detector filter, where R_{lpf} and C_{lpf} denote the resistance and capacitance of the low-pass filter, respectively, is realized using an ideal operational amplifier that exhibits infinite input impedance, zero output impedance, and infinite frequency-independent gain. Therefore, the readback signal $V_o(t, x_0)$ obtained at the low-pass filter output in response to the applied voltage $V_{\mathrm{P}}(t) = A\,\mathrm{rect}\,[(t - T_0)/\tau]$, where

$$\mathrm{rect}\left(\frac{t}{\tau}\right) = \begin{cases} 1 & \text{if } 0 \le t \le \tau \\ 0 & \text{otherwise} \end{cases}, \tag{31.4}$$

and A denotes the pulse amplitude, obeys the differential equation

$$V_o'(t, x_0) = \frac{1}{R_{\mathrm{lpf}}C_{\mathrm{lpf}}}\left[-V_o(t, x_0) + \frac{R_{\mathrm{lpf}}}{R^e\left[\Theta(t, x_0)\right]}V_P(t)\right]. \tag{31.5}$$

As the voltage at the output of the low-pass filter depends on the value of the variable resistance $R^e[\Theta(t, x_0)]$, the readback signal is determined by solving jointly the differential equations (31.3) and (31.5), with initial conditions $\Theta(t_0, x_0) = \Theta_0$ and $V_o(t_0, x_0) = 0$. For example, a comparison between experimental and synthetic readback signals is shown in Figs. 31.30 and 31.31 for a time constant of the low-pass filter $\tau_{\mathrm{lpf}} = 1.18\,\mu\mathrm{s}$ and two values of the duration of the applied rectangular pulse. For a given cantilever design the function $R^e(\Theta)$ is determined experimentally. Finally, the parameters R^{Θ} and C^{Θ} used in the simple readback channel model are obtained via simulated annealing, where the cost function is given by the mean-square error between experimental and synthetic signals at the low-pass filter output.

Assuming that ideal control of the scanner is performed such that the time of application of a read pulse corresponds either to the cantilever located at the center of an indentation for detecting a "1" bit, or away from an indentation for detecting a "0" bit, two possible responses are obtained at the output of the low-pass filter as solutions of (31.3) and (31.5), which we denote as $V_{o,1}(t, x_0)$ and $V_{o,0}(t, x_0)$, respectively. By sampling the readback signal at the instant $t_s = t_0 + \tau$, simple threshold detection may in principle be applied to detect a written bit, where the value of the threshold is given by

$$V_{\mathrm{Th}} = \frac{1}{2}\left[V_{o,1}(t_s, x_0) + V_{o,0}(t_s, x_0)\right]. \tag{31.6}$$

As mentioned in Sect. 31.2, one of the most critical issues in detecting the presence or absence of an indentation is the high resolution required to extract the small signal $V_{o,1}(t_s, x_0) - V_{o,0}(t_s, x_0)$ that contains the information about the bit being "1" or "0" superimposed on the offset signal $V_{o,0}(t, x_0)$. As illustrated in Fig. 31.28, this problem can be solved by subtracting a suitable reference signal $V_{o,\mathrm{ref}}(t, x_0)$ from the readback signal. The readback signal is thus given by

$$\tilde{V}_o(t, x_0) = V_o(t, x_0) - V_{o,\mathrm{ref}}(t, x_0), \tag{31.7}$$

and the threshold is set at $\tilde{V}_{\mathrm{Th}} = \frac{1}{2}\left[V_{o,1}(t_s, x_0) - V_{o,0}(t_s, x_0)\right]$. A VLSI implementation of the detection scheme analyzed here is presented in [31.42].

Now consider read pulses of duration τ that are periodically applied at instants $t_n = nT$, where $1/T$ denotes the symbol rate. Assuming that the response of the previous pulse has vanished as a new pulse is applied and that the temperature of the cantilever has approached the ambient temperature, i. e., $V_o(t_n, x_n) = 0$ and $\Theta(t_n, x_n) = \Theta_0$, then the analysis presented above still holds. In particular, the readback signal samples ob-



Fig. 31.30 **(a)** Experimental and **(b)** synthetic readback signal for $\tau = 10.25\,\mu s$ (after [31.12])



Fig. 31.31 **(a)** Experimental and **(b)** synthetic readback signal for $\tau = 15.25\,\mu s$ (after [31.12])

tained in response to N pulses applied to the cantilever for detecting a sequence of N binary written symbols are expressed as

$$s(t_{s,n}) = \tilde{V}_o(t_{s,n}, x_n), \quad t_{s,n} = nT + \tau, \\ n = 0, \dots, N-1 , \tag{31.8}$$

where $\tilde{V}_o(t, x_n)$ is given by (31.7) for pulses applied at time t_n and at distance $x_n = nT\upsilon$, $n = 0, \dots, N-1$ from the initial point of scanning. Note that the functions $V_o(t, x_n)$ and $V_{o,\text{ref}}(t, x_n)$ in (31.7) are ideally given by the solution of the differential equations (31.3) and (31.5) for $\eta_x = \Delta R^{\Theta}(x_n)/R^{\Theta}$ and $\eta_x = 0$, respectively.

The readback signal (31.7) at the output of the low-pass filter is observed in the presence of additive noise. Therefore, the readback signal for the detection of the n-th binary symbol is given by

$$r(t_{s,n}) = s(t_{s,n}) + w(t_{s,n}) , \tag{31.9}$$

where $w(t)$ denotes the noise signal. The components of the noise signal that must be taken into account are thermal noise (Johnson's noise) from the sensor, which reaches a temperature of about $\Theta_1 = 350\,°\text{C}$ during the read process, as well as from front-end analog circuitry. However, note that besides thermal noise, medium-related noise also affects the overall system performance.

Based on the above analysis, the response to a pulse applied to the cantilever at a distance x from some initial point can be calculated given the parameter $\eta_x = \Delta R^{\Theta}(x)/R^{\Theta}$. Recall that the value of η_x is proportional to the distance of the cantilever from the storage medium at the current location of the tip. Therefore, during tip displacement due to scanner motion, η_x is modulated from the topographical features of the storage surface such as written indentations, rings, and dust particles. This indicates that the modeling of the readback signal is a two-step process. First,

a) Experimental data



b) Synthetic model



Fig. 31.32a,b Comparison between **(a)** the readback signal obtained experimentally along a data track and **(b)** the readback signal obtained by the synthetic model (after [31.12])

a model for the storage surface topography is developed, which directlyand then the above procedure is used to calculate the readback signal samples in response to pulses applied at selected points in the particular storage area.

In the absence of any imperfections during the manufacturing and the writing process, the storage surface would consist of completely flat regions interrupted by uniformly shaped indentations, possibly surrounded by polymer rings. A 1-D cross section of an indentation along the scanning direction is modeled by a function with one main lobe and two side lobes, one on each side of the main lobe, the magnitude and the extent of which can be varied independently. The side lobes are of opposite sign than the main lobe and simulate the polymer rings around written indentations. By varying their magnitude and extent while keeping the total extent of the pulse fixed, one can simulate indentations/rings of varying width and asymmetric ring formation, phenomena that are caused by different recording conditions. In practice, however, no polymer surface is entirely flat and indentation shapes are far from uniform. The deviation of indentations from uniformity is simulated by scaling the amplitude of each pulse shape by a random number drawn from a Gaussian distribution with unit mean and adjustable variance. The surface roughness is in turn simulated by adding white Gaussian noise to the height of every point in the area of interest. Note that surface roughness is a medium-related effect and manifests itself in the readback signal as a noise process, which is, however, of a very different nature than thermal noise. The advantage of the adopted two-step model is that it naturally decouples these unrelated noise sources, as well as the write and the read processes.

Figure 31.32 illustrates the experimental and synthetic readback signals obtained along a data track. The waveforms shown in Fig. 31.32 have been obtained by applying pulses at the oversampling rate of q/T, where q denotes the oversampling factor. For a more detailed comparison between model and actual signals, Figs. 31.33 and 31.34 illustrate 3-D views of isolated indentations from experimental and synthetic readback



Fig. 31.33 Three-dimensional view of an isolated indentation obtained experimentally



Fig. 31.34 Three-dimensional view of an isolated indentation obtained by the synthetic model

signals, respectively. The dark regions in the center of both figures correspond to the indentation centers, whereas dark regions around them are due to rings. Note also the irregular height of the surrounding surface, which is attributed to the roughness of the storage medium.

31.9 System Aspects

In this section, we describe various aspects of a storage system based on our millipede concept. Each cantilever can write data to and read data from a dedicated area of the polymer surface, called a *storage field*. As mentioned above, in each storage field the presence (absence) of an indentation corresponds to a logical "1" ("0"). All indentations are nominally of equal depth and size. The logical marks are placed at a fixed horizontal distance from each other along a data track. We refer to this distance, measured from one logical mark center to the next, as the *bit pitch* (BP). The vertical (cross-track) distance between logical mark centers, the *track pitch* (TP), is also fixed. To read and write data the polymer medium is moved under the (stationary) cantilever array at a constant velocity.

A robust way to achieve synchronization and servo control in an x/y-actuated large 2-D array is by reserving a small number of storage fields exclusively for timing recovery and servo-control purposes, as illustrated in Fig. 31.35. Because of the large number of levers in the millipede, this solution is advantageous in terms of overhead compared with the alternative of timing and servo information being embedded in all data fields.



Fig. 31.35 Layout of data and servo/timing fields. *Dark boxes* represent dedicated servo/timing fields, *white boxes* represent data fields

31.9.1 PES Generation for the Servo Loop

With logical marks as densely spaced as in the millipede, accurate track following becomes a critical issue. Track following means controlling the position of each tip such that the tip is always positioned over the center of a desired track during reading. During writing, the tip position should be such that the written marks are aligned in a predefined way. In electromechanical systems, track following is performed in a servo loop, which is driven by an appropriate error signal called position-error signal (PES). Ideally, its magnitude is a direct estimate of the vertical (cross-track) distance of the tip from the closest track centerline, and its polarity indicates the direction of this offset.

Several approaches exist to generate a PES for AFM-based storage devices [31.9]. However, based on the results reported, none of these methods can achieve the track-following accuracy required for the millipede system. The quality of the PES directly affects the stability and robustness of the associated tracking servo loop [31.43].

We describe a method for generating a uniquely decodable PES for the millipede system [31.12, 27]. The method is based on the concept of *bursts* that are vertically displaced with respect to each other, arranged in such a way as to produce two signals in quadrature, which can be combined to provide a robust PES. This concept is borrowed from magnetic recording [31.43]. However, servo marks, as opposed to magnetic transitions, are placed in bursts labeled A and B for the in-phase signal and C and D for the quadrature signal. The centers of servo marks in burst B are vertically offset from mark centers in burst A by d' units of length. This amount of vertical spacing is related to the diameter of the written marks. The same principle applies to marks in the quadrature bursts C and D, with the additional condition that mark centers in burst C are offset by $d'/2$ units from mark centers in A in the cross-track direction. The latter condition is required in order to generate a quadrature signal. The configuration of servo bursts is illustrated in Fig. 31.36 for a case where $\text{TP} = 3d'/2$. Al-



Fig. 31.36 Servo burst configuration (after [31.12])

though each burst typically consists of many marks to enable averaging of the corresponding readout signals, only two marks per burst are shown here to simplify the presentation. The solid horizontal lines depict track centerlines, and circles represent written marks, which are modeled here as perfect conical indentations on the polymer storage surface.

To illustrate the principle of PES generation, let us assume that marks in all bursts are spaced BP units apart in the longitudinal direction, and that sampling occurs exactly at mark centers, so that timing is perfect. The assumption of perfect timing is made only for the purpose of illustration. In actual operation, sampling is performed with the aid of a timing recovery loop, as described in Sect. 31.9.2. Referring to Fig. 31.36, let us further assume that the cantilever/tip is located on the line labeled “0” and moves vertically toward line “3” in a line crossing the centers of the left-most marks in burst A (shown as a brown dashed line). The tip moves from the edge of the top mark toward its center, then toward its bottom edge, then to a blank space, again to a mark, and so on. The readout signal magnitude decreases linearly with the distance from the mark center and reaches a constant, background level value at a distance greater than the mark radius from the mark center, according to the adopted (conical mark) model. To synthesize the in-phase signal, the readout signal is also captured as the tip (conceptually) moves in a vertical line crossing the mark centers of burst B (brown dashed line in Fig. 31.36). The in-phase signal is then formed as the difference $\bar{A}-\bar{B}$, where $\bar{A}$ and $\bar{B}$ stand for the measured signal amplitudes in bursts A and B, respectively. This signal is represented by the line labeled “I” in Fig. 31.37. It has zero-crossings at integer multiples of d', which do not generally correspond to track centers because we set TP $= 3d'/2$ in this example. Therefore, the I-signal is not a valid PES in itself. This is why the quadrature (Q) signal becomes necessary in this case. The Q-signal is generated from the servo readback signals of bursts C and D as $\bar{C}-\bar{D}$ and is also shown in Fig. 31.37 (Q-curve). Note that it exhibits zero-crossings at points where the I-signal has local extrema.

A certain combination of the two signals (I and Q), shown as solid lines in Fig. 31.37, has zero-crossings at all track center locations and constant (absolute) slope, which qualifies it as a valid PES. However, this PES exhibits zero-crossings at all integer multiples of $d'/2$. For our example of TP $= 3d'/2$, three such zero-crossings exist in an area of width equal to TP around any track centerline. This fact, however, does not hamper unique position decoding. At even-numbered tracks, it is the zero of the *in-phase* signal that indicates the track center. The zeros of the quadrature signal, in turn, can be uniquely mapped into a position estimate by examining the polarity of the in-phase signal at the corresponding positions. This holds for any value of the combined PES within an area



Fig. 31.37 Ideal position-error signal (after [31.12])

of width equal to TP around each current track centerline. The signals exchange roles for odd-numbered tracks. The current track number, which is known a priori from the seek operation, is used to determine the mode of operation for the position demodulation procedure.

The principle of PES generation based on servo marks has been verified experimentally. For this purpose, A, B, C, and D bursts were written by an AFM cantilever/tip on an appropriate polymer medium consisting of a polymer coating on a silicon substrate. The bit pitch was set to 42 nm, and the track pitch was taken to be approximately equal to d', the cross-track distance between A (C) and B (D) bursts. An image created by reading the written pattern with the same cantilever is shown in Fig. 31.38. Shaded areas indicate indentations. The readout signal from the cantilever was also used for servo demodulation, as described above. The resulting in-phase and quadrature signals are shown in Fig. 31.39. The track centerlines are indicated by vertical dotted lines in the graph.

It can be observed that the zero-crossings of the in-phase signal are closely aligned with the track centerlines, as well as with the minima and maxima of the quadrature signal, as required for unique position decoding across all possible cross-track positions, at least in cases where $\mathrm{TP} \neq d'$. Moreover, the PES slope is nearly linear along a cross-track width of one track pitch around each track center, as $\mathrm{TP} \approx d'$ in this case, although deviations from the ideal signal shape exist. These deviations occur mainly because written indentations do not have perfect conical shapes, and also because of medium noise due to the roughness of the recording medium. Nevertheless, the experimentally generated error signals indicate that the proposed concept is valid and promising. Specifically, the results indicate that servo self-writing is feasible, that servo demodulation is almost identical to data readout and can be performed by any cantilever without special provisions, and that the PES generated closely approximates the desirable features described above.



Fig. 31.38 Experimental A, B, C, and D servo bursts (BP = 42 nm) (after [31.12] © 2003 IEEE)



Fig. 31.39 Demodulated in-phase (*solid line*) and quadrature (*dashed line*) PES based on the servo burst of Fig. 31.38 (after [31.12])

31.9.2 Timing Recovery

Similar to obtaining servo information based on using dedicated servo fields, we employ separate dedicated clock fields for recovery of timing information [31.12, 26, 27]. The concept is to have continuous access to a pilot signal for synchronization after initial phase acquisition and gain estimation. The recovered clock is then distributed to all remaining storage fields to allow reliable detection of random data. Initial phase acquisition is obtained by a robust correlation algorithm, gain estimation is based on averaging of the readback signal obtained from a predefined stored pattern, and tracking of the optimum sampling phase is achieved by a second-order digital loop.

At the beginning of the read process, several signal parameters have to be estimated prior to data detection. Besides the clock phase and frequency, it is necessary to estimate the gain of the overall read channel. To solve the problem of initial estimation of signal parameters prior to data detection, the sequence written in the clock field consists of a preamble, followed by a pattern of all "1"s for tracking the optimum sampling phase during the detection of random data. The transition between the preamble and the pattern of all "1"s must be detected reliably, as it indicates the start of data records to the remaining storage fields. Assuming that the initial frequency offset is within a small, predetermined range, usually 1,000 parts-per-million (PPM), we distinguish the tasks needed for timing recovery as follows: (i) acquisition of the optimum sampling phase; (ii) estimation of the overall channel gain needed for threshold detection; (iii) detection of the transition between the preamble and the pattern of all "1"s; and (iv) tracking of the optimum sampling phase.

At the beginning of the acquisition process, an estimate of the optimum sampling phase is obtained by resorting to a correlation method. We rely on the knowledge of the preamble and of an ideal reference-channel impulse response, which closely resembles the actual impulse response (see Sect. 31.9). The channel output samples obtained at the oversampling rate q/T are first processed by removing the dc-offset, then averaging is performed to reduce the noise level, and finally the resulting sequence is correlated with the reference impulse response to determine the phase estimate.

After determining the estimate of the optimum sampling phase, an estimate of the overall channel gain is obtained by averaging the amplitude of the channel output samples at the optimum sampling instants. The gain estimate is obtained from an initial segment of the preamble corresponding to an "all 1" binary pattern. As mentioned above, it is necessary that the end of the preamble is indicated by a "sync" pattern, which marks the transition between acquisition mode and tracking mode. Detection of the sync pattern is also based on a robust correlation method. After the sync pattern, an "all 1" pattern, as in the case of robust phase acquisition and gain estimation, is employed for tracking. The "all 1" pattern corresponds to regularly spaced indentations, which convey reliable timing information.

Tracking of the optimum sampling phase is achieved by the second-order loop configuration shown in Fig. 31.40. Assuming data detection is performed at instants that correspond to integer multiples of the oversampling factor q, the deviation of the sampling phase from the optimum sampling phase is estimated as

$$\Delta\tau_n = r(t_{s,nq+1}) - r(t_{s,nq-1}) \,. \tag{31.10}$$



Fig. 31.40 Second-order loop for tracking the optimum sampling phase (after [31.12])

This estimate of the phase deviation is input to a second-order loop filter, which provides an output given by

$$\Delta T_n = u_n + \alpha\,\Delta\tau_n \,, \tag{31.11}$$

where the discrete-time integrator is recursively updated as

$$u_{n+1} = u_n + \beta\,\Delta\tau_n \,. \tag{31.12}$$

The loop-filter output then determines the control signal for a voltage-controlled oscillator (VCO).

Note that a similar concept for timing recovery can also be applied if no separate clock field is available. In this case, the timing information is extracted from the random user data on each storage field.

31.9.3 Considerations on Capacity and Data Rate

The ultimate locality provided by nanometer-sharp tips represents the pathway to the high areal densities that will be needed in the foreseeable future. The intrinsic nonlinear interactions between closely spaced indentations, however, may limit the minimum distance between successive indentations and, hence, the areal density. The storage capacity of a millipede-based storage device can be further increased by applying modulation or constrained codes [31.12].

With modulation coding, a desired constraint is imposed on the data-input sequence, so that the encoded data stream satisfies certain properties in the time or frequency domain. These codes are very important in digital recording devices and have become ubiquitous in all data-storage applications. The particular class



Fig. 31.41 Areal density versus indentation spacing. Curve 1: $d = 0$; curve 2: $d = 1$; and curve 3: $d = 2$

of codes that imposes restrictions on the number of consecutive "1"s and "0"s in the encoded data sequence, generally known as run-length-limited (RLL) (d, k) codes [31.44], can be used to facilitate overwriting and also increase the effective areal density of a millipede-based storage device. The code parameters d and k are nonnegative integers with $k > d$, where d and k indicate the minimum and maximum number of "0"s between two successive "1"s, respectively. In the past, the precoded (RLL) (d, k) codes were mainly used for spreading the magnetic transitions further apart via the d-constraint, thereby minimizing intersymbol interference and nonlinear distortion, and for preventing loss of clock synchronization via the k-constraint. In optical recording, precoded RLL codes are primarily used for increasing the shortest pit length in order to improve the reliability of bit detection, as well as for limiting the number of identical symbols, so that useful timing information can be extracted from the readback signal.

For the millipede application, where dedicated clock fields are used, the k-constraint does not really play an important role and, therefore, can, in principle, be set to infinity, thereby facilitating the code design process. In a precoderless RLL code design, where the presence or absence of an indentation represents a "1" or "0", respectively, the d-constraint is instrumental in limiting the interference between successive indentations, as well as in increasing the effective areal density of the storage device. In particular, the quantity $(d+1)R$, where R denotes the rate of the (d, k) code, is a direct measure of the increase in linear recording density. Clearly, the packing density can be made larger by increasing d. On the other hand, large values of d lead to codes with very low rate, which implies high recording symbol rates, thus rendering these codes impractical for storage systems that are limited by the clock speed. The choice of $d = 1$ and $k \geq 6$ guarantees the existence of a code with rate $R = 2/3$. Use of $(d = 1, k \geq 6)$ modulation coding reduces the bit distance by half while maintaining the pitch between "1"s constant, thereby



Fig. 31.42 User data rate versus number of active cantilevers for the $(d = 1, k \geq 6)$ coding scheme. Curve 1: $T = 20\,\mu\text{s}$; curve 2: $T = 10\,\mu\text{s}$; curve 3: $T = 5\,\mu\text{s}$; curve 4: $T = 2\,\mu\text{s}$; and curve 5: $T = 1\,\mu\text{s}$ (after [31.12])

Table 31.1 Areal density and storage capacity (after [31.12] with permission © 2003 IEEE)

Coding	Linear density (kb/in)	Track density (kt/in)	Areal density (Gb/in^2)	Capacity (Gb)
Uncoded	847	847	717	1.21
$(d = 1, k \geq 6)$	1,129	847	956	1.61
$(d = 2, k > 6)$	1,269	847	1,075	1.81

increasing the linear density by a factor of 4/3. Similarly, the choice of $d = 2$ and $k > 6$ guarantees the existence of a code with rate $R = 1/2$. Use of ($d = 2$, $k > 6$) modulation coding reduces the bit distance to a third while maintaining the pitch between "1"s constant, thereby increasing the linear density by a factor of 3/2. Figure 31.41 shows the areal density as a function of the indentation spacing for an uncoded system, as well as for systems coded with ($d = 1$, $k \geq 6$) and ($d = 2$, $k > 6$), where coding is applied only in the on-track direction.

Table 31.1 shows the achievable areal densities and storage capacities for a 32×32 cantilever array with 1,024 storage fields, each having an area of $100 \times 100\,\mu\text{m}^2$, resulting in a total storage area of $3.2 \times 3.2\,\text{mm}^2$. The indentation pitch and the track pitch are set equal to 30 nm. Finally, for the computation of the storage capacity an overall efficiency of 85% has been assumed, taking into account the redundancy of the outer error-correction coding, as well as the presence of dedicated servo and clock fields.

Figure 31.42 shows the user data rate as a function of the total number of cantilevers accessed simultaneously, for various symbol rates and a ($d = 1$, $k \geq 6$) modulation coding scheme. For example, for a 32×32 cantilever array, a system designed to access a maximum of 256 cantilevers every $T = 5\,\mu\text{s}$ provides a user data rate of 34.1 Mb/s. Alternatively, by resorting to the row/column multiplexing scheme with $T = 80\,\mu\text{s}$ a data rate of 8.5 Mb/s is achieved.

31.10 Conclusions

A very large 2-D array of AFM probes has been operated for the first time in a multiplexed/parallel fashion, and write/read/erase operations in a thin polymer medium have been successfully demonstrated at densities of or significantly higher than those achieved with current magnetic storage systems.

The millipede has the potential to achieve ultrahigh storage areal densities on the order of $1\,\text{Tb/in}^2$ or higher. The high areal storage density, small form factor, and low power consumption render the millipede concept a very attractive candidate as a future storage technology for mobile applications, as it offers several Gigabytes of capacity at data rates of several Megabytes per second. Dedicated servo and timing fields allow reliable system operation with a very small overhead. The read channel model provides the methodology for analyzing system performance and assessing various aspects of the detection and servo/timing algorithms that are key to achieving the system reliability required by the applications envisaged.

Although the first high-density storage operations with the largest 2-D AFM array chip ever built have been demonstrated, there are a number of issues that need further investigation such as overall system reliability, including long-term stability of written indentations, tip and medium wear, limits of data rates, array and cantilever size, as well as trade-offs between data rate and power consumption.

References

31.1 E. Grochowski, R. F. Hoyt: Future trends in hard disk drives, IEEE Trans. Magn. **32** (1996) 1850–1854

31.2 D. A. Thompson, J. S. Best: The future of magnetic data storage technology, IBM J. Res. Dev. **44** (2000) 311–322

31.3 G. Binnig, H. Rohrer, C. Gerber, E. Weibel: 7×7 reconstruction on Si(111) resolved in real space, Phys. Rev. Lett. **50** (1983) 120–123

31.4 G. Binnig, C. F. Quate, C. Gerber: Atomic force microscope, Phys. Rev. Lett. **56** (1986) 930–933

31.5 H. J. Mamin, D. Rugar: Thermomechanical writing with an atomic force microscope tip, Appl. Phys. Lett. **61** (1992) 1003–1005

31.6 R. P. Ried, H. J. Mamin, B. D. Terris, L. S. Fan, D. Rugar: 6-MHz 2-N/m piezoresistive atomic-force-microscope cantilevers with incisive tips, J. Microelectromech. Syst. **6** (1997) 294–302

31.7 B. D. Terris, S. A. Rishton, H. J. Mamin, R. P. Ried, D. Rugar: Atomic force microscope-based data storage: Track servo and wear study, Appl. Phys. A **66** (1998) S809–S813

31.8 H. J. Mamin, B. D. Terris, L. S. Fan, S. Hoen, R. C. Barrett, D. Rugar: High-density data storage using proximal probe techniques, IBM J. Res. Dev. **39** (1995) 681–699

31.9 H. J. Mamin, R. P. Ried, B. D. Terris, D. Rugar: High-density data storage based on the atomic force microscope, Proc. IEEE **87** (1999) 1014–1027

31.10 L. R. Carley, J. A. Bain, G. K. Fedder, D. W. Greve, D. F. Guillou, M. S. C. Lu, T. Mukherjee, S. Santhanam, L. Abelmann, S. Min: Single-chip computers with microelectromechanical systems-based magnetic memory, J. Appl. Phys. **87** (2000) 6680–6685

31.11 G. Gibson, T. I. Kamins, M. S. Keshner, S. L. Neberhuis, C. M. Perlov, C. C. Yang: Ultra-high density storage device, (1996) US Patent 5,557,596

31.12 E. Eleftheriou, T. Antonakopoulos, G. K. Binnig, G. Cherubini, M. Despont, A. Dholakia, U. Dürig, M. A. Lantz, H. Pozidis, H. E. Rothuizen, P. Vettiger: millipede – A MEMS-based scanning-probe data-storage system, IEEE Trans. Magn. **39** (2003) 938–945

31.13 G. K. Binnig, H. Rohrer, P. Vettiger: Mass-storage applications of local probe arrays, (1998) US Patent 5,835,477

31.14 P. Vettiger, J. Brugger, M. Despont, U. Drechsler, U. Dürig, W. Häberle, M. Lutwyche, H. Rothuizen, R. Stutz, R. Widmer, G. Binnig: Ultrahigh density, high-data-rate NEMS-based AFM data storage system, J. Microelectron. Eng. **46** (1999) 11–17

31.15 P. Vettiger, G. Cross, M. Despont, U. Drechsler, U. Dürig, B. Gotsmann, W. Häberle, M. A. Lantz, H. E. Rothuizen, R. Stutz, G. K. Binnig: The "millipede" – Nanotechnology entering data storage, IEEE Trans. Nanotechnol. **1** (2002) 39–55

31.16 M. Lutwyche, C. Andreoli, G. Binnig, J. Brugger, U. Drechsler, W. Häberle, H. Rohrer, H. Rothuizen, P. Vettiger: Microfabrication and parallel operation of 5 × 5 2D AFM cantilever array for data storage and imaging, Proc. IEEE 11th Int. Workshop MEMS, Heidelberg 1998 (IEEE, Piscataway 1998) 8–11

31.17 M. Lutwyche, C. Andreoli, G. Binnig, J. Brugger, U. Drechsler, W. Häberle, H. Rohrer, H. Rothuizen, P. Vettiger, G. Yaralioglu, C. Quate: 5 × 5 2D AFM cantilever arrays: A first step towards a terabit storage device, Sens. Actuators A **73** (1999) 89–94

31.18 P. Vettiger, M. Despont, U. Drechsler, U. Dürig, W. Häberle, M. I. Lutwyche, H. E. Rothuizen, R. Stutz, R. Widmer, G. K. Binnig: The "millipede" – More than one thousand tips for future AFM data storage, IBM J. Res. Dev. **44** (2000) 323–340

31.19 B. W. Chui, H. J. Mamin, B. D. Terris, D. Rugar, K. E. Goodson, T. W. Kenny: Micromachined heaters with 1-μs thermal time constants for AFM thermomechanical data storage, Proc. IEEE Transducers, Chicago 1997 (IEEE, Piscataway 1997) 1085–1088

31.20 W. P. King, J. G. Santiago, T. W. Kenny, K. E. Goodson: Modelling and prediction of sub-micrometer heat transfer during thermomechanical data storage, 1999 Microelectromechanical Systems (MEMS). Proc. ASME Intl. Mechanical Engineering Congress and Exposition, ed. by A. P. Lee, L. Lin, F. K. Forster, Y. C. Young, K. Goodson, R. S. Keynton (ASME, New York 1999) 583–588

31.21 W. P. King, T. W. Kenny, K. E. Goodson, G. L. W. Cross, M. Despont, U. Dürig, H. Rothuizen, G. Binnig, P. Vettiger: Design of atomic force microscope cantilevers for combined thermomechanical writing and thermal reading in array operation, J. Microelectromech. Syst. **11** (2002) 765–774

31.22 G. K. Binnig, M. Despont, W. Häberle, P. Vettiger: Method of forming ultrasmall structures and apparatus therefore, (March 1999) US Patent Office, Application No. 147865

31.23 G. Binnig, M. Despont, U. Drechsler, W. Häberle, M. Lutwyche, P. Vettiger, H. J. Mamin, B. W. Chui, T. W. Kenny: Ultra high-density AFM data storage with erase capability, Appl. Phys. Lett. **74** (1999) 1329–1331

31.24 G. K. Binnig, J. Brugger, W. Häberle, P. Vettiger: Investigation and/or manipulation device, (March 1999) US Patent Office, Application No. 147867

31.25 S. M. Sze: *Physics of Semiconductors Devices* (Wiley, New York 1981)

31.26 G. Cherubini, T. Antonakopoulos, P. Bächtold, G. K. Binnig, M. Despont, U. Drechsler, A. Dholakia, U. Dürig, E. Eleftheriou, B. Gotsmann, W. Häberle, M. A. Lantz, T. Loeliger, H. Pozidis, H. E. Rothuizen, R. Stutz, P. Vettiger: The millipede, a very dense, highly parallel scanning-probe data-storage system, ESSCIRC – Proceedings 28th European Solid-State Circuits Conference, ed. by A. Baschirotto, P. Malcovati (Univ. Bologna, Bologna 2002) 121–125

31.27 E. Eleftheriou, T. Antonakopoulos, G. K. Binnig, G. Cherubini, M. Despont, A. Dholakia, U. Dürig, M. A. Lantz, H. Pozidis, H. E. Rothuizen, P. Vettiger: "millipede": A MEMS-based scanning-probe data-storage system, Digest of the Asia-Pacific Magnetic Recording Conference 2002, APMRC '02 (IEEE, Piscataway 2002) CE-2-1–CE2-2

31.28 M. Despont, J. Brugger, U. Drechsler, U. Dürig, W. Häberle, M. Lutwyche, H. Rothuizen, R. Stutz, R. Widmer, G. Binnig, H. Rohrer, P. Vettiger: VLSI-NEMS chip for AFM data storage, Technical Digest 12th IEEE Int. Micro Electro Mechanical Systems Conf. "MEMS '99" (IEEE, Piscataway 1999) 564–569

31.29 T. S. Ravi, R. B. Marcus: Oxidation sharpening of silicon tips, J. Vac. Sci. Technol. B **9** (1991) 2733–2737

31.30 M. Despont, J. Brugger, U. Drechsler, U. Dürig, W. Häberle, M. Lutwyche, H. Rothuizen, R. Stutz, R. Widmer, G. Binnig, H. Rohrer, P. Vettiger: VLSI-NEMS chip for parallel AFM data storage, Sens. Actuators A **80** (2000) 100–107

31.31 H. Rothuizen, M. Despont, U. Drechsler, G. Genolet, W. Häberle, M. Lutwyche, R. Stutz, P. Vettiger: Compact copper/epoxy-based micromachined electromagnetic scanner for scanning probe applications, Technical Digest, 15th IEEE Int. Conf. on Micro Electro Mechanical Systems "MEMS 2002" (IEEE, Piscataway 2002) 582–585

31.32 S. C. Minne, G. Yaralioglu, S. R. Manalis, J. D. Adams, A. Atalar, C. F. Quate: Automated parallel high-speed atomic force microscopy, Appl. Phys. Lett. **72** (1998) 2340–2342

31.33 M. Lutwyche, U. Drechsler, W. Häberle, R. Widmer, H. Rothuizen, P. Vettiger, J. Thaysen: Planar micromagnetic x/y/z scanner with five degrees of freedom. In: *Magnetic Materials, Processes, and Devices: Applications to Storage and Micromechanical Systems (MEMS)*, Vol. 98–20, ed. by L. Romankiw, S. Krongelb, C. H. Ahn (Electrochemical Society, Pennington 1999) pp. 423–433

31.34 H. Rothuizen, U. Drechsler, G. Genolet, W. Häberle, M. Lutwyche, R. Stutz, R. Widmer, P. Vettiger: Fabrication of a micromachined magnetic x/y/z scanner for parallel scanning probe applications, Microelectron. Eng. **53** (2000) 509–512

31.35 J.-J. Choi, H. Park, K. Y. Kim, J. U. Jeon: Electromagnetic micro x-y stage for probe-based data storage, J. Semicond. Technol. Sci. **1** (2001) 84–93

31.36 H. Lorenz, M. Despont, N. Fahrni, J. Brugger, P. Vettiger, P. Renaud: High-aspect-ratio, ultrathick, negative-tone near-UV photoresist and its applications for MEMS, Sens. Actuators A **64** (1998) 33–39

31.37 C. Q. Davis, D. Freeman: Using a light microscope to measure motions with nanometer accuracy, Opt. Eng. **37** (1998) 1299–1304

31.38 M. I. Lutwyche, M. Despont, U. Drechsler, U. Dürig, W. Häberle, H. Rothuizen, R. Stutz, R. Widmer, G. K. Binnig, P. Vettiger: Highly parallel data storage system based on scanning probe arrays, Appl. Phys. Lett. **77** (2000) 3299–3301

31.39 K. Fuchs, C. Friedrich, J. Weese: Viscoelastic properties of narrow-distribution poly(methyl metacrylates), Macromolecules **29** (1996) 5893–5901

31.40 U. Dürig, B. Gotsman: This estimate is based on a fluid dynamic deformation model of a thin film, private communication

31.41 J. D. Ferry: *Viscoelastic Properties of Polymers, 3rd edition* (Wiley, New York 1980)

31.42 T. Loeliger, P. Bächtold, G. K. Binnig, G. Cherubini, U. Dürig, E. Eleftheriou, P. Vettiger, M. Uster, H. Jäckel: CMOS sensor array with cell-level analog-to-digital conversion for local probe data storage, ESSCIRC – Proceedings 28th European Solid-State Circuits Conference, ed. by A. Baschirotto, P. Malcovati (Univ. Bologna, Bologna 2002) 623–626

31.43 A. H. Sacks: Position signal generation in magnetic disk drives. Ph.D. Thesis (Carnegie Mellon University, Pittsburgh 1995)

31.44 K. A. S. Immink: *Coding Techniques for Digital Recorders* (Prentice Hall, Hemel 1991)

32. Microactuators for Dual-Stage Servo Systems in Magnetic Disk Files

This chapter discusses the design and fabrication of electrostatic MEMS microactuators and the design of dual-stage servo systems in disk drives. It introduces fundamental requirements of disk drive servo systems, along with challenges posed by storage densities increases. It describes three potential dual-stage configurations and focuses on actuated slider assemblies using electrostatic MEMS microactuators. The authors discuss major electrostatic actuator design issues, such as linear versus rotary motion, electrostatic array configuration, and differential operation. Capacitive and piezoresistive elements may be used to sense relative slider position, while integrated gimbals and structural isolation may prove useful in improving performance. A detailed design example based on a translational, micromolded actuator illustrates several of these concepts and is accompanied by theoretical and experimental results.

The chapter continues to discuss MEMS microactuator fabrication. It describes several processes for obtaining appropriate electrostatic devices including micromolding, deep-reactive ion etching, and electroplating. The primary goal of these processes is to obtain very high-aspect ratio structures, which improve both actuation force and structural robustness. Other fabrication issues, such as electrical interconnect formation, material selection, and processing cost, are also considered. Actuated slider fabrication is compared to that of actuated suspension and actuated head assemblies; this includes instrumentation of a suspension with strain sensors to aid in vibration detection.

The section on controller design reviews dual-stage servo control design architectures and methodologies. The considerations for controller design of MEMS microactuator dual-stage servo systems are discussed. The details of control designs using a decoupled SISO design method and the robust multivariable design method of μ-synthesis are also presented. In the decoupled design, a self-tuning control algorithm has been developed to compensate for the variations in the microactuator's resonance mode. In the μ-synthesis design, robust controllers can be synthesized by using additive and parametric uncertainties to characterize the un-modeled dynamics of the VCM and the variations in the microactuator's resonance mode. Finally, the chapter also introduces a dual-stage short-span seek control scheme based on decoupled feed forward reference trajectories generations.

32.1 **Design of the Electrostatic Microactuator** 952
  32.1.1 Disk Drive Structural Requirements ... 952
  32.1.2 Dual-Stage Servo Configurations ... 953
  32.1.3 Electrostatic Microactuators: Comb-Drives vs. Parallel-Plates ... 954
  32.1.4 Position Sensing ... 956
  32.1.5 Electrostatic Microactuator Designs for Disk Drives ... 958

32.2 **Fabrication** ... 962
  32.2.1 Basic Requirements ... 962
  32.2.2 Electrostatic Microactuator Fabrication Example ... 962
  32.2.3 Electrostatic Microactuator Example Two ... 963
  32.2.4 Other Fabrication Processes ... 966
  32.2.5 Suspension-Level Fabrication Processes ... 967
  32.2.6 Actuated Head Fabrication ... 968

32.3 **Servo Control Design of MEMS Microactuator Dual-Stage Servo Systems** ... 968
  32.3.1 Introduction to Disk Drive Servo Control ... 969
  32.3.2 Overview of Dual-Stage Servo Control Design Methodologies ... 969
  32.3.3 Track-Following Controller Design for a MEMS Microactuator Dual-Stage Servo System ... 971
  32.3.4 Dual-Stage Seek Control Design ... 976

32.4 **Conclusions and Outlook** ... 978

References ... 979

This chapter discusses the design and fabrication of electrostatic MEMS microactuators, and the design of dual-stage servo systems, in disk drives. The focus of the chapter is an actuated slider assembly using an electrostatic MEMS microactuator. We discuss major design issues, including linear versus rotary actuation, electrostatic array configuration, and integrated sensing capability. We describe several fabrication processes for obtaining the necessary devices, such as micromolding, deep-reactive ion etching, and electroplating. Dual-stage servo control design architectures and methodologies are then reviewed . We present in detail track-following controller designs based on a sensitivity function decoupling single-input-single-output design methodology and the robust μ-synthesis design methodology. Finally, we introduce a 2-DOF short span seek control design using a dual-stage actuator.

Since the first hard disk drive (HDD) was invented in the 1950s by IBM, disk drives' storage density has been following Moore's law, doubling roughly every 18 months. The current storage density is 10 million times larger than that of the first HDD [32.1]. Historically, increases in storage density have been achieved by almost equal increases in track density, the number of tracks encircling the disk, and bit density, the number of bits in each track. However, because of superparamagnetism limitations, future areal storage density increases in HDDs are predicted to be achieved mainly through an increase in track density [32.2].

Research in the HDD industry is now targeting an areal density of one terabit per square inch. For a predicted bit aspect ratio of 4 : 1, this translates to a linear bit density of 2 M bits per inch (BPI) and a radial track density of 500 K tracks per inch (TPI), which in turn implies a track width of 50 nm. A simple rule of thumb for servo design in HDDs is that three times the statistical standard deviation of the position error between the head and the center of the data track should be less than 1/10 of the track width. Thus, to achieve such a storage density, nanometer-level precision of the servo system will be required.

A disk drive stores data as magnetic patterns, forming bits, on one or more disks. The polarity of each bit is detected (read) or set (written) by an electromagnetic device known as the read/write head. The job of a disk drive's servo system is to position the read/write head over the bits to be read or written as they spin by on the disk. In a conventional disk drive, this is done by sweeping over the disk or disks a long arm consisting of a voice coil motor (VCM), an E-block, suspensions, and sliders, as shown in Figs. 32.1 and 32.2. A read/write head is fabricated on the edge of each slider (one for each disk surface). Each slider is supported by a suspension and flys over the surface of a disk on an air-bearing. The VCM actuates the suspensions and sliders about a pivot in the center of the E-block. We describe this operation in more detail in the following section.

The key to increasing HDD servo precision is to increase servo control bandwidth. However, the bandwidth of a traditional single-stage servo system as shown in Fig. 32.2 is limited by the multiple mechanical resonance modes of the pivot, the E-block, and the suspension between the VCM and the head. Nonlinear friction of the pivot bearing also limits achievable servo precision. Dual-stage actuation, with a second stage actuator placed between the VCM and the head, has been proposed as a solution that would increase servo bandwidth and precision.

Several different secondary actuation forces and configurations have been proposed, each having strengths and weaknesses given the requirements of HDDs. The dual-stage configurations can be categorized into three groups: actuated suspension, actuated slider, and actuated head. Within these, actuation forces include piezoelectric, electrostatic, and electromagnetic. In this chapter, we discuss design, fabrication and control of an electrostatic MEMS microactuator (MA) for actuated slider dual-stage positioning.

32.1 Design of the Electrostatic Microactuator

The servo system of a hard disk drive is the mechatronic device that locates and reads data on the disk. In essence, it is a large arm that sweeps across the surface of the disk. At the end of the arm is the read-write head, containing the magnetic reading and writing elements that transfer information to and from the disk.

32.1.1 Disk Drive Structural Requirements

This read-write head is contained in a box-like structure known as a slider. The slider has a contoured lower surface that acts as an air bearing between the head and the disk. The high-velocity airflow generated by the spinning disk pushes up on the air-bearing surface, maintaining the slider and read-write head at a constant distance from the disk, despite unevenness of the disk, permitting reliable data reading and writing.

The arm over an HDD's disk has three primary stages: the voice-coil motor (VCM), the E-block, and the suspension. In a conventional disk drive, the VCM performs all positioning of the head, swinging it back and forth across the disk. The E-block lies between the VCM and the suspension and contains the pivot point. The suspension projects from the E-block over the disk as a thin flexible structure, generally narrowing to a point at the location of the slider.

For a disk drive servo to operate effectively, it must maintain the read-write head at a precise height above the disk surface and within a narrow range between the disk tracks arranged in concentric circles around the disk. It must also be able to seek from one track on the disk to another. Information about the track that the head is following is encoded in sectors radiating from center of the disk, allowing the head to identify its position and distance from the center of the track. To maintain a correct flying height, the suspension must be designed with an appropriate stiffness in the vertical direction to balance an air-bearing force corresponding to the slider design in use in the drive. Meanwhile, the suspension must be flexible to roll and pitch at the slider location to permit adaptation to unevenness of the disk surface. This is accomplished using a gimbal structure. The suspension as a whole, however, should not bend or twist during the operation, as this would misdirect the head away from the track it is following.

As data densities in HDDs increase and track widths diminish, single-stage, conventional servo systems become less able to position the head precisely. Because the VCM/E-block/suspension assembly is large and massive as a unit, the speed at which the head can be controlled is limited. Furthermore, the assembly tends to have a low natural frequency, which can accentuate vibration in the disk drive and cause off-track errors. At track densities in the future approaching one Terabit per square inch, the vibration induced in a disk drive by airflow alone is enough to force the head off-track.

A solution to these problems is to complement the VCM with a smaller, secondary actuator to form a dual-stage servo system. The VCM continues to provide rough positioning, while the second stage actuator does fine positioning and damps out vibration and other disturbances. The smaller second stage actuator can typically be designed to have a much higher natural frequency and less susceptibility to vibration than the VCM. Any actuator used in a dual-stage system should be inexpensive to build, require little power to operate, and preserve the stiffness properties described above necessary to preserve the flying height.



Fig. 32.1 A schematic diagram of an HDD



Fig. 32.2 VCM actuator in an HDD

32.1.2 Dual-Stage Servo Configurations

In the past six years, much research work has been dedicated to the exploration of suitable secondary actuators for constructing dual-stage servo systems for HDDs. These dual-stage configurations can be categorized into three groups: "actuated suspension," "actuated slider," and "actuated head."

Actuated Suspension

In this approach, the suspension is redesigned to accommodate an active component, typically a piezoelectric material. This piezoelectric material stretches or flexes the suspension to position the slider and magnetic head. Piezoelectric material is an active actuation element that produces a large actuation force but small actuation stroke. In the "actuated-suspension" configuration, therefore, the piezoelectric actuators are usually implemented in a leverage mechanism that can convert small actuation displacements into large head displacements. Typically this is done by placing the piezoelectric actuators away from the magnetic head (between the E-block and suspension) so that they can have a long leverage arm to gain mechanical amplification and produce a sufficient magnetic-head motion. The advantage of this approach is that the suspension can be fabricated by a conventional suspension-making process, and its dual-stage servo configuration is effective in attaining low frequency runout attenuation in the positioning servo loop. The major drawback of this approach is that the system is still susceptible to instabilities due to the excitation of suspension resonance modes. Thus, track-per-inch (TPI) servo performance can be increased but remains limited when compared to the alternative approaches. The actuated suspension approach, nonetheless is expected to be the first deployed in commercial HDDs [32.3, 4].

Actuated Slider

In this approach, a microactuator is placed between the slider and gimbal to position the slider/magnetic heads. The resulting servo bandwidth can be higher than the previous approach because the secondary actuation bypasses the mechanical resonances of the suspension. This approach uses existing sliders and microactuators that can be batch fabricated, and thus could be cost effective. However, the size and mass of the microactuator are significant relative to those of current sliders and may interfere with the slider flying stability. Current suspensions, therefore, need to be redesigned to adopt this secondary actuator. Suitable driving forces in this approach include electrostatic, electromagnetic, and piezoelectric [32.5–8]. To further reduce the assembly task of placing the microactuator in between gimbal structure and slider, some researchers have proposed microactuators that are either integrated with the gimbal structure [32.6] or the slider [32.9].

Actuated Head

In this approach, the slider is redesigned so that the microactuators can be placed inside the slider block and actuate the magnetic heads with respect to the rest of the slider body. As these microactuators are very small, they only slightly increase the slider weight and are thus capable of working with the current suspension assembly. Researchers have successfully demonstrated the integrated fabrication process for fabricating the electrostatic microactuators and magnetic heads within one piece of ceramic block (slider). The embedded electrostatic microactuator has its resonance close to 30 kHz and was able to position the magnetic heads relative to the rest of the slider body by 0.5 μm [32.10, 11]. Full-fledged integration of slider, actuator, and read/write head remains a challenge.

In this chapter, we focus on actuated slider configurations, as they involve a great deal of interesting microscale engineering. In particular, we will discuss electrostatic actuation, probably the most common method of implementing microactuation in microelectromechanical devices. Any such microactuator will exhibit certain features:

- a fixed base, which attaches to the suspension,
- a movable platform, upon which the slider rests,
- springs between the base and platform, flexible in the direction of desired motion, and stiff in all other directions, and
- an electrostatic actuation array that generates the force used to move the platform and slider.

Microactuators must also include a wiring scheme for transferring signals to and from the slider and often incorporate a structure for sensing the motion of the slider relative to the suspension. Electrostatic microactuators to be discussed in this chapter include HexSil and DRIE fabricated actuators from the University of California, Berkeley, and electroplating-formed actuators by IBM and the University of Tokyo.

Electromagnetic or piezoelectric force are alternatives to electrostatic actuation in the actuated-slider configuration. Electromagnetic microactuators use ferromagnetic films to produce force perpendicular to an applied electric field. This type of actuation has potentially low voltage requirements but requires special fabrication techniques to integrate the magnetic components into the assembly. A microactuator of this type for hard disk drives is under development at Seagate, with results as yet unpublished. Piezoelectric microactuators use a piezoelectric material, which expands or contracts in response to applied voltage, to move the slider. These actuators have simple fabrication, the patterning a piece of piezoelectric material to sit between the suspension and slider, but it is difficult to obtain an adequate range of motion. A short stroke from the piezoelectric piece must be leveraged into a much larger motion at the read/write head. A piezoelectric microactuator has been produced by TDK corporation with a 0.5 μm stroke length at 10 V, with a 10 V bias [32.12].

32.1.3 Electrostatic Microactuators: Comb-Drives vs. Parallel-Plates

Electrostatic microactuators have been studied as the secondary actuators in HDDs for their relative ease of fabrication, particularly in the configurations of "actuated slider" and "actuated head," since the structural material needs only to be conductive rather than ferromagnetic or piezoelectric. Electrostatic force is generated by applying a voltage difference between the moving shuttle and a fixed stator element. Depending on the designated motion for the shuttle, electrostatic actuators are often categorized into two groups: comb-drives and parallel-plates, as illustrated in Fig. 32.3.

The magnitude of the electrostatic force generated equals the rate of change of energy that is retained within the finger-like structure and varied by shuttle motion. Therefore, the electrostatic force for comb-drive actuators, in which the designated shuttle motion moves along the x-direction, as shown in Fig. 32.3, equals

$$F_{\text{comb}} = \frac{\partial E}{\partial x} = \frac{\epsilon h}{2d} V^2 , \tag{32.1}$$

where ϵ is the permittivity of air, x is the overlap between two adjacent plates, h is plate thickness, and d is the gap between two parallel plates. Similarly, the electrostatic force for parallel-plates actuators is

$$F_{\text{parallel}} = \frac{\partial E}{\partial y} = \frac{\epsilon x h}{2d^2} V^2 , \tag{32.2}$$

where x is the finger overlap.

As indicated in (32.1) and (32.2), the electrostatic force for comb-drives actuators does not depend on the displacement of the moving shuttle and thus allows a long stroke while maintaining a constant electrostatic force. The electrostatic force for parallel-plates actuators, in contrast, is a nonlinear function of its shuttle motion ($\propto 1/d^2$), and the maximum stroke is limited by the nominal gap between shuttle and stator. A longer stroke is achieved with a larger gap, at the expense of lower electrostatic force. For applications that require small stroke but large force output, parallel-plates actuators are preferred since the output force from parallel-plates can be x/d times larger than the force from comb-drives. The following equation (32.3) is easily derived from (32.1) and (32.2).

$$\frac{F_{\text{parallel}}}{F_{\text{comb}}} = \frac{x}{d} . \tag{32.3}$$

A simplified second-order differential equation is often utilized to describe the dynamic response of an electrostatic microactuator

$$m\ddot{x}(t) + b\dot{x}(t) + K_{\text{m}}x(t) = F\,[V, x(t)] \ , \tag{32.4}$$

where m is the mass of the moving shuttle, b is the damping coefficient of the microactuator, K_{m} is the spring constant of the mechanical spring that connects the moving shuttle to an anchor point, and F is the electrostatic force that can be obtained from (32.1) and (32.2).



Fig. 32.3 Electrostatic microactuators. Comb-drives versus parallel-plates

Differential Drives

Because electrostatic force is always attractive, electrostatic microactuators need other features to actively control the direction of shuttle motion in servo applications, as opposed to relying on the restoring force from a mechanical spring. For this reason, the differential-drives approach, as shown in Fig. 32.4, is frequently adopted in electrostatic microactuator designs. Based on the differential-drive configuration, the simplified second-order differential equation (32.4) is rewritten as

$$\begin{aligned} m\ddot{x}(t)+b\dot{x}(t)+K_{\text{m}}x(t) = F\,[&V_{\text{bias}}+V_{\text{dr}},\, x_o-x(t)] - \\ &F\,[V_{\text{bias}}-V_{\text{dr}},\, x_o+x(t)] \ , \end{aligned} \tag{32.5}$$

where x_0 is the nominal position of the moving shuttle. If the differential drive is operated at the bias voltage (V_{bias}) with a small perturbation voltage (V_{dr}), the nonlinear force input in (32.5) can be linearized with a first-order



Fig. 32.4 Differential parallel-plates actuators and electrical-isolation features

approximation.

$$\begin{aligned} &m\ddot{x}(t)+b\dot{x}(t)+(K_{\mathrm{m}}-K_{\mathrm{e}})x(t)=K_v V_{\mathrm{dr}}\;, \\ &K_{\mathrm{e}}=2\frac{\partial F}{\partial x}\,|_{V_{\mathrm{bias}}}\;, \\ &K_{\mathrm{v}}=2\frac{\partial F}{\partial V_{\mathrm{dr}}}\,|_{V_{\mathrm{bias}}}\;. \end{aligned} \tag{32.6}$$

Here K_{e} represents a softening electrostatic spring constant, and K_{v} represents the voltage-to-force gain. The electrostatic spring constant acts as a negative spring during the electrostatic microactuator operation, and its value varies with the bias voltage (V_{bias}). When the electrostatic spring constant K_{e} exceeds the spring constant K_{m} from the mechanical spring, the microactuator becomes unstable; this is often described as pull-in instability. As shown in (32.5) and (32.6), the differential configuration cancels the even order harmonics in voltage and thus linearizes the voltage–force relation to some extent. Furthermore, in parallel-plates actuators, the differential configuration reduces the nonlinearity in actuation voltage as well as in shuttle displacement.

Electrical Isolation

Because electrostatic actuation requires multiple voltage levels for actuation force and position sensing (as discussed in the following section), electrical isolation is another challenge for designing an electrostatic microactuator. Generally speaking, when multiple voltage levels are needed in MEMS devices, electrical isolation is achieved by breaking up the parts that need to be on different voltage level and anchoring them separately to a nonconductive substrate. This approach has many drawbacks, not only because it requires a substrate in a device but also because structures have to be mechanically separated to be electrically isolated. The electrical isolation problem is far more severe in parallel-plates microactuators than comb-drive microactuators since parallel-plates actuation generally requires different voltage levels for stator fingers pulling in opposite directions.

Figure 32.4 shows an example of how an electrical-isolation feature can be utilized to increase the actuation force output in a differential parallel-plates microactuator design. As shown in the figure, without the proper electrical isolation, drive-electrodes with different voltage potentials have to be placed in separate groups and result in the same voltage difference between drive-electrodes and shuttle on both sides of each shuttle finger [32.5, 6]. Since electrostatic forces are always attractive, gaps on two sides of the interlaced structure cannot be made equal, otherwise the forces on two sides of a shuttle finger will be equal and the shuttle's movement direction will be uncontrollable. With such electrical-isolation features as the "isolation plug," shown on the left in Fig. 32.4, gaps of the interlaced structure can be the same width, since different voltages can be applied on the two sides of the shuttle fingers. As shown in Fig. 32.4, the design with integrated electrical-isolation features is more compact than without isolation features. Consequently, more finger structures can fit in the same amount of space, and the actuation voltage can be reduced.

32.1.4 Position Sensing

Most proposed HDD dual-stage servo controllers utilize only the position of the magnetic head relative to the center of data track, known in the industry as the position error signal, or PES, for closed-loop track following control. These systems have a single-input-multi-output (SIMO) control architecture. In some instances, however, it is also possible to measure the relative position error signal (RPES) of the magnetic head relative to the VCM. In this case, the control architecture is multi-input-multi-output (MIMO). As shown in [32.13], RPES can be used in a MIMO controller to damp out the second stage actuator's resonance mode and enhance the overall robustness of the servo system.

Capacitive position sensing and piezoresistive position sensing are two popular sensing mechanisms among electrostatic microactuator designs. Each of these sensing mechanisms is discussed in more detail in the following sections.

Capacitive Position Sensing

Capacitive position sensing is based on shuttle movement causing a capacitance change between the moving shuttle and fixed stators. By measuring the change in capacitance, it is possible to determine the shuttle location relative to the fixed stator. The output voltage (V_{o}) for both differential drives in Fig. 32.5 equals $2\delta C/C_{\mathrm{i}}V_{\mathrm{s}}$. The capacitance change due to shuttle movement ($\mathrm{d}C/\mathrm{d}x$) can be derived and the output voltage (V_{o}) for the comb-drives and parallel-plates can be formulated as a function of shuttle displacement.

$$\begin{aligned} V_{\mathrm{comb}}&=2\frac{C_{\mathrm{s}}}{C_{\mathrm{i}}}\frac{\delta x}{x_0}V_{\mathrm{s}}\;, \\ V_{\mathrm{parallel}}&=2\frac{C_{\mathrm{s}}}{C_{\mathrm{i}}}\frac{y_0\delta y}{y_0^2-\delta y^2}V_{\mathrm{s}}\;, \\ &\approx 2\frac{C_{\mathrm{s}}}{C_{\mathrm{i}}}\frac{\delta y}{y_0}V_{\mathrm{s}}\;, \end{aligned} \tag{32.7}$$


Differential comb-drives
X
Vs
Shuttle
x0
Ci
Cs+δC
Cs−δC
Vo
−Vs
Stator
Differential parallel-plates
Y
Vs
y0
Ci
Shuttle
Cs+δC
Cs−δC
Vo
Stator
−Vs

Fig. 32.5 Capacitive position sensing. Comb-drives versus parallel-plates motion

where x_0 is the nominal overlap for interlaced fingers and y_0 is the nominal gap between overlapped fingers, as shown in Fig. 32.5.

As indicated by (32.7), the voltage output for the comb-drives sensing structure, V_{comb}, is linear with shuttle displacement. On the other hand, the sensing configuration that makes use of parallel-plates motion has better sensitivity for detecting shuttle motion since y_0 is usually smaller than x_0. Although the nonlinearity in parallel-plates sensing can be linearized by the differential drive configuration to some extent, in a design example of 4 μm gap with 1 μm stroke, the linear model shown in (32.7) still produces 6% deviation from the nonlinear model.

Among electrostatic microactuators that use capacitive position sensing, the capacitance variation due to shuttle motion ($\mathrm{d}C/\mathrm{d}x$) is typically at the level of 100 fF/μm. In order to obtain 10 nm position sensing resolution, the capacitance sensing circuit must be able to detect capacitance variation of 1 fF in the presence of parasitic capacitance and offset/mismatches from op-amps, which can easily result in an output voltage orders of magnitude larger than the output voltage from the designated capacitance variation. In most capacitive position sensing, the limiting factor for the sensing resolution is not the thermal noise but the sensing circuit's design.

Here we introduce two basic capacitance sensing circuits suitable for high-resolution position sensing [32.14]. The concept of the "synchronous scheme," as shown in Fig. 32.6 I, is to reduce the impedance of sense capacitors as well as the offset and 1/f noises from op-amps by applying modulation techniques on the sense voltage (V_s). The R_{dc} resistor on the feedback loop sets the DC voltage level at the input nodes of the "charge integrator." The effect of the presence of parasitic capacitance (C_p) is nullified by the virtual ground condition from the op-amps. The major drawback of the synchronous scheme is that the DC-setting resistor (R_{dc}) has to be large to ensure the proper gain for the capacitance sensing [32.14], which introduces excessive thermal noise into the sensing circuit. In addition, a large resistor usually consumes a large die space in implementation.

A switched-capacitance scheme, as shown in Fig. 32.6 II, is one alternative that avoids the use of DC-setting resistor. The capacitance sensing period is broken into two phases: reset phase and sense phase. During the reset phase, input/output nodes of capacitors


I. Synchronous scheme
+Vs
−Vs
Shuttle
CS
Rdc
Ci
Charge integrator
Pre-amplifier
Stator
−
+
Gain
LPF
VO
CS
Cp
+1
−1
Shuttle
+Vs
−Vs
II. Switched-capacitance scheme
−Vs
ΦRS
Shuttle
CS
Ci
Ch
Stator
−
+
Gain
VO
ΦRS
ΦSN
ΦRS
ΦSN
ΦRS
ΦSN
CS
Cp
Shuttle
ΦSN
+Vs
Reset Phase : ΦRS
Sense Phase : ΦSN
ΦRS
ΦSN
Sensing period (1/fs)

Fig. 32.6 Capacitive position sensing circuits. Synchronous scheme versus switched-capacitance scheme

and input voltage to op-amps are set to ground or reference level to ensure proper DC voltage for the charge integrator. During the sense phase, sense voltage $\pm V_\mathrm{s}$ is applied to the sense capacitors, and the amount of charge proportional to the mismatch in the sense capacitors is integrated on the capacitor C_i, thus producing an output voltage proportional to the capacitance mismatch from the sense capacitors. This approach replaces the large DC-setting resistor by capacitors and switches and results in a much smaller die compared to the synchronous scheme. Furthermore, the switching technique allows more design flexibility for system integration and performance improvement because of the ability to allocate separate phases for various operations. The major drawback of this design is that it draws noise into sensing circuits from switches and sampling capacitor C_h. However, these noises can be compensated by dividing the sense phase into $2 \sim 3$ sub-sense phases [32.14], at the expense of a complicated circuit design.

Piezoresistive Sensing

Piezoresistive films have been widely used as strain-sensitive components in a variety of MEMS devices, including pressure sensors and vibration sensors. Generally speaking, piezoresistive sensing techniques require less complicated sensing circuits and perform better in a severe environment than other sensing techniques. When a piezoresistive film is subjected to stress, the film resistivity and dimensions change. The fractional change of resistance is proportional to the deformation of the piezoresistive film. For a small change of resistance, this relation can be expressed as,

$$\frac{\Delta R}{R} = K \cdot \epsilon \,, \tag{32.8}$$

where R is resistance of the piezoresistive film, K is its gage factor and ϵ is strain. In microactuator designs, the piezoresistive film is usually applied to the spring structure that connects the moving shuttle to an anchor point. When the shuttle moves, it stretches the spring as well as the piezoresistive film, consequently, the piezoresistive film produces a deformation signal proportional to the shuttle displacements. As a result, piezoresistive sensing is easier to implement than capacitive position sensing, but the sensing resolution is usually less accurate due to higher thermal noises introduced by the resistance of the piezoresistive film.

Another application of piezoresistive sensing, aside from measuring relative slider position, is to detect vibration in the suspension itself. The idea is to sense airflow-induced vibration of the suspension and feed that information forward to an actuated slider to damp out motion at the head. Piezoresistors used for this purpose can be made from metal or semiconductor materials, arranged as a strip or series of strips oriented along the direction of vibration strain. It is important that these sensors observe all vibration modes that contribute to off-track error, so a number of optimization schemes for locating the sensors have been developed [32.15]. One method is to maximize the minimum eigenvalue of the observability matrix of the sensor or sensors. This ensures that all relevant modes are observed. Another method is to minimize a linear quadratic gaussian control problem over potential sensor locations [32.16]. This serves to determine an optimal placement from the perspective of a linear controller.

32.1.5 Electrostatic Microactuator Designs for Disk Drives

Various electrostatic microactuators have been designed for secondary actuation in HDDs. To incorporate an electrostatic microactuator into a HDD without altering much of current suspension configuration, many design constrains are imposed. In this section, we will first discuss some design issues and then present one specific design example.

Translational Microactuators versus Rotary Microactuators

Depending on the motion of the magnetic head actuated, microactuator designs are categorized into two groups: translational actuators and rotary actuators. Either type can be implemented by comb-drives [32.8, 17] or parallel-plates [32.5, 6, 18] actuation.

When employing a translational microactuator in a dual-stage HDD servo, previous research [32.13] has shown that a force coupling between the suspension and the translational microactuator exists, consisting of transmitted actuation force from the VCM and suspension vibration induced by windage. The force coupling from the VCM not only complicates the dual-stage servo controller but also imposes a design constraint on a translational microactuator design, in that the translational microactuator has to provide a large force output to counterbalance the coupling force. When the VCM makes a large movement, as in seeking a new data track, the microactuator may be overpowered. One solution is to pull the actuator to one side and lock it momentarily in place. Even then, the use of the two actuation-stages must be carefully coordinated to moderate the influence of the VCM on the microactuator. On the other hand, the linear springs in the translational microactuator can also aid in damping out motion of the suspension. The portion of suspension vibration induced by windage mostly consists of high frequency excitation, so the resulting magnetic head's position error can be passively attenuated by low resonant frequency translational microactuators.

Generally speaking, rotary actuators are more difficult to design/analyze than translational actuators because of their nonuniform gap between shuttle and stator. Still, their different operating properties have both strengths and weaknesses. Unlike a translational actuator, no obvious force coupling is transmitted from the suspension to a rotary actuator, as the microactuator is nearly always attached to the end of suspension at the microactuator's center of rotation, which acts as a pivot point. With no mechanical coupling, the dual-stage servo system using a rotary microactuator does not suffer from the force coupling between VCM and microactuator seen in translational designs. However, the rotary microactuator has to compensate for the magnetic head's position error induced by suspension vibration without any passive attenuation of the vibration. Overall, a rotary acuator is likely to behave better than a translational microactuator during track seeking and worse during track following.

Gimballed Microactuator Design

Proper flying height and orientation of a slider and read-write head over a hard disk is maintained by the interaction of the suspension, the air bearing of the slider, and a gimbal structure. The gimbal structure is located at the tip of the suspension and holds the slider/microactuator in its center coupon. The dynamic characteristic requirements of gimbal structures are that they be flexible in pitch and roll motion but stiff in in-plane and out-of-plane bending motion. To meet all these requirements using only one piece of metal is a highly challenging task. For this reason, most commercially available suspension/gimbal designs consist of two to four pieces of steel, each with different thickness.

The goal of a gimballed microactuator design is to seamlessly integrate an actuator and gimbal into a one-piece structure, as shown in Fig. 32.7, to simplify both suspension design and HDD assembly. A full integrated suspension that includes suspension, gimbal, and microactuators in one part has also been proposed [32.19]. The dimple structure, existing in most current gimbal structures, is excluded from the gimballed microactuator design and electrical interconnects are in situ fabricated on the gimballed microactuator, replacing the flexible cable in current HDD suspension assembly.



Fig. 32.7 Schematics of translational microactuator versus rotary microactuator. Courtesy from Lilac Muller

The dimple structure in current suspension assemblies provides out-of-plane stiffness while preserving the necessary torsional compliance in the gimbal structure. Without a dimple structure in the suspension assembly, the gimbal itself must provide high out-of-plane bending stiffness. Otherwise, it would unbalance the suspension pre-load, which is an overbend of the suspension that balances the upward air-bearing force on the suspension during operation. The electrical interconnects are implemented to transmit data between magnetic heads, located at the center coupon of the gimbal structure, and IC circuits located at the end of the suspension. The in situ fabricated electrical interconnects are inevitably passed through torsion bars of the gimbal and thus set a design constraint for the minimum width of torsional bars. Furthermore, both the gimbal structure and microactuator should be the same thickness to simplify the MEMS fabrication process.

To summarize the design constrains discussed above, the integrated gimbal structure has to meet performance requirements with a single, uniform piece of material that would previously have been achieved by two to four metal pieces with different thicknesses, while the minimum width of any torsion bars that may be used pre-determined. To solve this problem, *Muller* [32.6] proposed a T-shaped structure (a beam structure with overhang surface sheet) for the torsion bars, and *Chen* [32.19] proposed "double-flexured" torsion bars. Additionally, many suspension manufacturers have developed new gimbal structures for their suspensions designed specifically for use with MEMS microactuators, moving the gimbal location back to the suspension from the microactuator.



Fig. 32.8 Pico-slider mounted on a translational microactuator. Courtesy from Horsely 1998

An Electrostatic Microactuator Design Example

Figure 32.8 shows a translational microactuator design suitable for the HDD dual-stage actuation by *Horsley* in 1998 [32.5]. The translational electrostatic microactuator dimensions are 2.2 mm × 2.0 mm × 0.045 mm and weight 67 µg. The dimensions of the pico-slider on the top are 1.2 mm × 1.0 mm × 0.3 mm and weight 1.6 mg. This microactuator design does not include "electrical-isolation" features, and thus the electrical isolation and electrical-interconnects were fabricated on a separate substrate and subsequently bonded to the microactuator. This microactuator uses parallel-plates for actuation force but does not have dedicated position sensing structures due to fabrication process limitations. Table 32.1 summarizes key parameters of this microactuator design.

Based on these parameters, the characteristics of this electrostatic microactuator can be estimated by the linear differential equation shown in (32.6).

Figure 32.9 shows the schematics of a circuit design by *Wongkomet* in 1998 [32.14], in which actuation driving voltage and capacitive position sensing were implemented for the electrostatic microactuator designed by Horsley. As mentioned before, the electrostatic microactuator design doesn't have dedicated structure for a position sensing; as a consequence, the input nodes for actuation and output nodes for capacitive position sensing have to share the same electrodes. Capacitors C_c and C_{c0}, shown in Fig. 32.9, are carefully designed to shield the high voltage presented in actuation circuit from sensing circuit, which is mostly low voltage, and thus enable driving/sensing circuit integration.

The driving circuit, shown in the left in Fig. 32.9, demonstrates how to generate the bias voltage (V_{bias}, ±40 V) and drive voltage (V_{dr}, -40–$+40$ V) from 0–5 V CMOS compatible circuits. The switches at the output of the charge pumps were synchronized with the switching period ϕ_{RS}. During the sense phases ϕ_{SN1} and ϕ_{SN2}, therefore, the switches are left open and thus no voltage fluctuation is seen by the sensing circuits. This arrangement was utilized to reduce feedthrough from the driving circuit to position sensing circuit.

The design target for the capacitive position sensing circuit was to achieve position sensing resolution of 10 nm, and this goal was approached by two main techniques implemented in the circuit: differential sensing and Correlated-Double-Sampling (CDS). The main

Table 32.1 Parameters of the electrostatic microactuator design by *Horsley* 1998 [32.5]

Parameters	Source*	Value
Nominal gap	D	10 µm
Structure thickness	D	45 µm
Rotor mass, m	I	44 µg
$\mathrm{d}C/\mathrm{d}x$	C	68 fF/µm
Actuation voltage, bias voltage	D	40 V
Actuation voltage, maximum driving voltage	D	±40 V
Voltage-to-force gain K_v	I	50 nN/V
Mechanical spring constant K_m	I	29 N/m
Electrostatic spring constant K_e	I	9.6 N/m
Damping coefficient, b	I	1.03×10^{-4} N/(m/s)
Voltage-to-position DC gain	M	0.05 µm/V
Resonance frequency, w_r	M	550 Hz

*: D = Design value, C = Calculation, M = Measurement, I = Inferred from measurements


Driving circuit
Electrostatic microactuator
Position sensing circuit
V_{dd}^{+} +5 V
V
+2.5 ~ −2.5 V
V_{dd}^{-} 0 V
Charge pump
Actuation driving circuit
Charge pump
V_{bias}^{+} +40 V
V_{dr}
+40 ~ −40 V
V_{bias}^{-} −40 V
Φ_{RS}
Φ_{RS}
Φ_{RS}
C_p
C_s^{+}
Cp0
C_s^{-}
C_p
Cc
Cc0
Cc
V_{dd}^{+}
Φ_{RS}
Φ_{RS}
C_i
Φ_{SN2}, Φ_{RS}
Φ_{SN2}
Φ_{SN1}
V_S
Φ_{RS}
Φ_{SN2}
V_S
C_h
Gain
Buf-fer
C_h
Φ_{SN2}, Φ_{RS}
Φ_{SN2}
C_i
Φ_{RS}
Φ_{RS}
V_{dd}^{+}
Φ_{RS}
Φ_{SN1}
Φ_{SN2}

Fig. 32.9 A simplified schematic including driving and sensing circuits for the electrostatic microactuator. Courtesy from Wongkomet 1998

benefits of the differential sensing scheme are reduced noise coupling and feedthrough, elimination of even-order harmonics, and improvement of dynamic range by doubling the output swing. To adapt this differential sensing scheme in a differential parallel-plates electrostatic microactuator, a bias voltage (V_{bias}) was applied to the stator and the drive voltage (V_{dr}) was applied to the shuttle. The CDS technique, a modified capacitance sensing technique based on the switched-capacitance scheme, was implemented along with the differential sensing scheme to compensate for sensing noises including 1/f, KT/C, switch charge injection and offset from op-amps [32.14]. The concepts of CDS can be briefly described as follows: the sense period is broken into three phases: one reset phase, ϕ_{RS}, and two sense phases, ϕ_{SN1} and ϕ_{SN2}. During the ϕ_{RS} sense phase, the voltages for capacitors and input nodes to op-amps are set to the reference level of the DC-voltage setting for the charge integrator, same as for the switched-capacitance scheme discussed in Sect. 32.1.4. During the ϕ_{SN1} sense phase, a sensing voltage $-V_s$ is applied to the shuttle and results in a voltage difference, $\alpha(-V_s) + V_{error}$, across the sampling capacitor C_h, where α is the transfer function from sense voltage to the output voltage at the pre-amplifier, shown as *Gain* in the plot, and V_{error} is the voltage at the output node of pre-amplifier resulting from noise, leakage charge, and offset of op-amps. Lastly, during the ϕ_{SN2} sense phase, the sensing voltage is switched from $-V_s$ to V_s and the switch next to C_h is switched open. This results in a voltage output $\alpha(V_s) + V_{error}$ at the output node of the pre-amplifier and a voltage, $2\alpha(V_s)$, at the input node of the buffer. As a consequence, the voltage resulting from sensing error (V_{error}), which appears at the output node of pre-amplifier, disappears from the voltage-input node to the buffer. Switches utilized in



Fig. 32.10 Open-loop and closed-loop frequency response of the prototype microactuator with a pico-slider. The capacitive position measurement (*solid line*) is compared to the measurements from LDV (*dashed line*). Courtesy from Wongkomet

the circuit and their correspondent timing are shown in Fig. 32.9. Be aware that for presentation simplicity components in the pre-amplifier and buffer are not shown in detail in Fig. 32.9.

The frequency response, both open-loop and closed-loop with a PD controller, of the electrostatic microactuator measured by a capacitive position sensing circuit is shown in Fig. 32.10. The position measurements from an LDV are also shown in the same plot for comparison. The deviation between measurements from the different position sensing devices appears in the high frequency region of the plot and has been identified as the feedthrough from the capacitance sensing circuit. The effect from feedthrough was negligible at low frequency region but becomes significant and results in a deviation in magnitude for the transfer function of $-80\,\mathrm{dB} \sim -90\,\mathrm{dB}$ after 2 kHz. The feedthrough presented in the capacitance sensing circuits limited the position sensing resolution to the level of 10 nm.

32.2 Fabrication

While there are several approaches to building electrostatic microactuators suitable for hard disk drives, they all exhibit certain common features from a fabrication standpoint.

32.2.1 Basic Requirements

As we discussed earlier, nearly all electrostatic microactuators rely on a system of interlaced fingers or plates to provide actuation force. As a result, a method for producing arrays of these fingers or plates with narrow gaps between them is usually the central concern in developing a fabrication process. The resulting structure must then be strong enough to support both the slider on the microactuator and the microactuator on the suspension, particularly when loaded by the air-bearing that supports the slider above the hard drive's spinning disk. In addition, the design and fabrication process must include a way to perform electrical interconnection on the microactuator. This involves transferring signals to and from the actuator and slider and isolating the parts of the microactuator requiring different voltage levels.

Meanwhile, the microfabrication process is subject to certain basic constraints. The materials used in fabrication must either be thermally and chemically compatible with any processing steps that take place after their deposition or must somehow be protected during steps that would damage them. This often constrains the choice of materials, deposition techniques, and processing order for microdevices. Another concern is that the surface of the structure be planar within photoresist spinning capabilities and lithography depth-of-focus limits if patterning is to be performed. This can be a major challenge for disk drive microactuators, which are large in size and feature high-aspect ratio trenches compared to other MEMS devices.

32.2.2 Electrostatic Microactuator Fabrication Example

Section 32.1.5 described the design and operation of a translational electrostatic microactuator. This section examines the fabrication process by which that microactuator was built [32.5]. The process is a variation on a micro-molding process known as HexSil [32.20]. In a micro-molding process, a mold wafer defines the structure of the microactuator and may be reused many times like dies in macro-scale molding; in the HexSil version of the procedure, the mechanical parts of the microactuator are formed in the mold by polysilicon. A second wafer is used to create metallized, patterned target dies. Upon extraction from the mold, the HexSil structure is bonded to this target substrate, which is patterned to determine which sections of the HexSil structure are electrically connected.

Naturally, the mold wafer is the first item to be processed and is quite simple. It is a negative image of the desired structure, etched down into the wafer's surface, as shown in Fig. 32.11a. A deep but very straight etch is critical for successful fabrication and subsequent operation of the devices. If the trench is too badly bowed or is undercut, the finished devices will be stuck in the mold and difficult to release. On the other hand, a tall device will have a larger electrostatic array area, will generate more force, and be better able to support a slider while in a disk drive.

Fabrication of the HexSil structure forms the majority of the processing sequence Fig. 32.11b–g. HexSil fabrication begins by coating the surface of the mold wafer with a sacrificial silicon oxide. This layer, deposited by low-pressure chemical vapor deposition (LPCVD), must coat all surfaces of the mold, so that removal of the oxide at the end of the process will



Fig. 32.11 Fabrication example 1: HexSil

leave the device completely free of the mold. This microactuator uses a 3 to 4 µm thick oxide layer to ensure clearance between the polysilicon structure and the trench walls during release. The mold is then refilled completely with LPCVD polysilicon, which will form the desired mechanical structure. Polysilicon is chosen for its conductivity and good conformality in refilling trenches. This also leaves a planar surface ready for photolithography to cover bonding locations. After the lithography step, the polysilicon deposited on top of wafer is removed, except where the bonding points were defined.

The structure is then prepared for bonding by forming a soldering surface. First a chrome/copper seed layer is evaporated on the surface of the wafer. The chrome promotes copper adhesion to the silicon, while the copper forms the starting point for electroplating. The seed layer is covered with photoresist, which is cleared only in the locations where contacts are desired. There, electroplating will produce a metal film, forming soldering points for the device to the target substrate that will form its base. In this case, copper is used as the plating material, thanks to its high conductivity and solderability. The device is released from the mold by ion milling away the thin seed layer, then dissolving the oxide lining with a hydroflouric (HF) acid wet etch. The free standing portion of the microactuator is thus ready for bonding to the target. The mold, meanwhile, may be used again after a simple cleaning step.

The target substrate may be prepared in several ways. The target shown above consists simply of indium solder bumps and interconnects on a patterned seed layer; this is known as a "plating bus" arrangement. The seed layer is used for the same reasons as on the HexSil structure, but in this case the seed layer is patterned immediately, with the unwanted portions removed by sputter etching. This provides isolation where desired without having to etch the seed layer after the indium is in place. Photoresist is spun again and patterned to uncover the remaining seed layer. A layer of indium is then electroplated everywhere the seed layer is visible. Indium acts as the solder when the two parts of the microactuator are pressed together, forming a cold weld to the copper at 200–300 MPa as shown in Fig. 32.11h, that was found suitable for hard disk requirements.

32.2.3 Electrostatic Microactuator Example Two

The high-aspect ratio microactuator described in this section is in development at the University of California, Berkeley, and demonstrates another way to create the features required of an actuated slider. The microactuator is translational, with parallel-plates actuation, and includes two of the design options described previously: integrated isolation plugs, as described in Sect. 32.1.3, and a capacative sensing array, as described in Sect. 32.1.4. A picture of the basic design is shown in Fig. 32.12; a central shuttle holding the slider is supported by four folded-flexure springs and driven by parallel-plates arrays.

Basic Process: Silicon-on-Insulator

Successful processing of the design is centered around the ability to etch very straight, narrow trenches using deep reactive ion etching (DRIE). DRIE is a special plasma etching sequence that uses polymerization of the sidewalls of a trench to keep the walls straight even at extreme aspect ratios. Deep, narrow trenches


Spring
Sensing capacitor, C_s^+
Spring
Driving array
Shuttle
Driving array
Spring
Sensing capacitor, C_s^-
Spring

Fig. 32.12 Translational high-aspect ratio microactuator


a) DRIE of isolation trenches
b) Nitride & poly-Si refill
c) Etch back and nitride cap
d) Etch contact holes
e) Metallization
f) Pattern interconnect
g) DRIE with thick photoresist
h) HF release
Lightly doped silicon
Highly doped silicon
Undoped polysilicon
Silicon nitride
Aluminium
Thermal oxide
LPCVD oxide
Spin-on glass
Photoresist

Fig. 32.13 Basic silicon-on-insulator fabrication process

make possible a microactuator with both closely packed electrostatic arrays and good mechanical strength. Conventional surface micromaching is used to produce the majority of the electrical interconnects.

The basic fabrication process uses a silicon-on-insulator (SOI) wafer to control DRIE trench depth. SOI wafers are very useful in microfabrication as they provide a layer of single-crystal silicon (the device layer) separated from the bulk of the wafer (the handle layer) by a thin layer of buried silicon oxide. This gives a very well controlled thickness to finished device but is very expensive. The microactuators described here are fabricated from an SOI wafer with a 100 μm device layer. A variation on the processing sequence and layout eliminates the need for SOI wafers and will be discussed in the following section.

The first stage of fabrication is creation of deep isolation trenches (see Fig. 32.13a–c). This procedure has been adapted to MEMS from integrated circuit processing for isolating thick MEMS structures [32.21]. The isolation pattern is formed by photolithography and etched by DRIE down to the buried oxide. With trenches only 2 μm wide, this corresponds to an aspect ratio of 50 : 1. The wafer surface and trenches are then coated with LPCVD silicon nitride, which acts as the electrical insulator. The trench is then refilled in its entirety with LPCVD polysilicon, which is a more conformal material better fills the trench than silicon nitride would alone; polysilicon also has much lower residual stresses than silicon nitride. The refill leaves a layer of polysilicon on the surface of the substrate, which must be etched or polished back to the silicon nitride. After etch-back, a second layer of LPCVD nitride completes isolation between regions.

Next, electrical interconnects are formed, as shown in Fig. 32.13d–f. Contact holes to the substrate are defined by photolithography and etched by reactive ion etching of the silicon nitride. Metal lines may then be patterned directly by photolithography or formed by lift-off. In a lift-off process, photoresist is deposited and patterned before the metal. The metal is then deposited vertically, so that the sidewalls of the resist are uncovered. Dissolving the resist allows the metal on top to float away, leaving behind the interconnect pattern. In the figures shown here, the interconnects are formed by evaporated aluminum, eliminating the need for electroplating and a seed layer. The ability to isolate portions of the substrate is useful for simplifying the interconnect layout, as one interconnect can cross another by passing underneath it through an isolated portion of the substrate.

Finally, structural lithography is performed and a second etch by DRIE is done, as shown in Fig. 32.13g. These trenches will define the shape of the microactuator, and are larger, 4 μm wide, to allow sufficient rotor travel. After this etch step, the device layer on the SOI buried oxide consists of fully defined microactuators. When the buried oxide is removed by wet etching, the microactuator is released from the substrate Fig. 32.13h and, after removal of the photoresist that protected the device surface from HF during release, ready for operation. Thanks to the high-aspect ratios of DRIE and the efficient integrated isolation scheme, the microactuator can theoretically be operated with a DC bias voltage of 15 V on the rotor, and a dynamic stator voltages below 5 V. In practice, higher voltages are required due to the spreading of trench walls over the course of DRIE. A picture of the electrostatic structure, with the rotor fingers on the left and the stator fingers on the right, divided down the center by isolation trenches, is shown in Fig. 32.14.

Variation: Anisotropic Backside Release

An alternative fabrication approach is to build the microactuator from a regular silicon wafer (∼ 550 μm thick), but then, since the microactuator shouldn't be more than 100 μm thick to fit in a HDD, etch away the backside of the wafer to obtain devices of that size. The main reason for using a silicon-only wafer is to reduce the need for expensive SOI wafers, which cost approximately ten times as much as single-material wafers. Another benefit is the elimination of the need for etch holes to reach the buried oxide layer, which increase vulnerability of microactuators to particle or moisture contamination. However, the thickness of the devices cannot be controlled as accurately as with the SOI process, and the processing sequence is more complicated.



Fig. 32.14 Electrostatic driving array of microactuator from SOI

Control of backside etching is difficult, making it hard to obtain devices with uniform thickness across a wafer. A proposed solution is to use an anisotropic wet etchant during the backside etch step. Anisotropic etchants work very slowly on certain crystal planes of a single-crystal silicon wafer; a coating on trench sidewalls can protect fast-etching planes when the etchant reaches the trenches from the back, causing slow-etching crystal planes to begin coming together slowing the etch. The result is a nearly self-stopping etch with a V-shaped profile that prevents overetching even in the presence of nonuniformities in etch rate and trench depth across the wafer. The most common anisotropic etchants are potassium hydroxide (KOH) and tetramethyl ammonium hydroxide (TMAH). This release process is referred to here as an anisotropic backside release (ABR).

The key to a good release by this method is to achieve excellent protection of the top of the wafer and the deep trenches from the etchant, and this neccessitates changes in the process flow from that for an SOI wafer. Without a good protective film, the interconnects on the surface of the wafer could be destroyed, or the fast-etching planes might be attacked along the trench sidewalls. Of the etchants mentioned above, TMAH is preferred, due to high selectivity to both silicon oxide and nitride and, especially, thermally grown oxide, which can be used as protective films. However, growing thermal oxide and/or depositing high-quality nitride are high temperature processes not compatible with most metals, so the structural trenches must be etched and oxidized before forming the electrical interconnects. As shown in Fig. 32.15c–d, the isolation trenches are formed as before, but the structural trenches are patterned and etched in the very next step. A thermal oxide is then grown in the trenches to produce the protective oxide layer Fig. 32.15e.

To do lithography for the interconnects at this point, then, the surface of the wafer must be planarized. This is done by refilling the trenches with spin-on-glass. The spin-on-glass plugs the trenches nearly to the top and can be sacrificed along with the thermal oxide at the end of the process. Extra glass on the wafer surface can be removed by a quick HF dip or chemical mechanical polishing. The resulting surface is uneven, as shown in Fig. 32.15f, but a thick photoresist layer can be applied over the trenches evenly enough to accomplish contact and metal patterning lithographies. After metallization much the same as for the SOI wafer Fig. 32.15g, a final coating of etch resistant material is required to protect the metal during backside release, as shown in

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004


c) Isolation as before
g) Metallization
d) DRIE structural trenches
h) Deposit protective coating
e) Oxidize trench surface
i) Anisotropic backside etch
f) SOG refill, etchback
j) Strip protective films
Lightly doped silicon
Highly doped silicon
Undoped polysilikon
Silicon nitride
Aluminium
Thermal oxide
LPCVD oxide
Spin-on glass
Photoresist

Fig. 32.15 Deep trench fabrication process adapted for backside release



Fig. 32.16 Microactuator with integrated gimbal fabricated by ABR

Fig. 32.15h–j. After ABR, the backside of the device will be shaped by crystal planes, but the thickness of the device at the edge of DRIE features will be fixed. While a combination of silicon oxide and silicon nitride has been effective over a "metallization" of undoped polysilicon, an effective combination of true metal interconnects and protective films has yet to be found and is an ongoing area of research for improving the ABR process sequence.

A prototype microactuator with integrated gimbal fabricated using ABR is shown in Fig. 32.16. This prototype was operated with a 30 V DC bias and ±8 V AC driving voltage for ±1 μm displacement, while a larger version (shown in Fig. 32.12) was operated at 15 V bias and ±3 V driving. This layout and fabrication concept is currently being adjusted to fit a MEMS-ready suspension for more advanced testing.

32.2.4 Other Fabrication Processes

Where the DRIE-based process described above "digs" the microactuator out of a wafer, a procedure developed by IBM "grows" a microactuator with high-aspect ratio trenches on top of a wafer [32.22].

IBM Electroplated Microactuator

The microactuator is fabricated by a clever sequence of electroplating steps and sacrificial depositions. An oxide sacrificial film is first patterned then covered with a metal seed layer. When later removed, the sacrificial will have left a gap between the microactuator and substrate portions of the microactuator needed to move freely. A polymer, 40 μm thick, is spun onto the wafer and patterned with a reverse image of the main structural layer. Trenches are etched down to the sacrificial layer by plasma etching then refilled by electroplating, much like micro-molding. Another sacrificial polymer, photoresist this time, separates the top of the fixed portions of the structure from the platform upon which the slider will sit, while conveniently planarizing the surface for further lithography. The platform is created by two more electroplating steps on top of the parts of the structure that will move freely. Removal of the sacrificial layers (photoresist, polymer, and oxide) releases the microactuator for use.

This process has been used to produce both rotary and linear microactuators and is comparatively advanced from a commercial standpoint. The resulting devices are thinner than those described in the previous example, but a similar aspect ratio (20 : 1) can be achieved. This procedure also has the benefits of being a low temperature process, which helps decrease processing cost and is compatible with the thin film magnetic head manufacturing process. Moreover, it includes an upper structure that covers the fingers, which improves device reliability by shielding the fingers from particles.

Additional fabrication details and dynamic testing results for the IBM design may be found in references [32.22] and [32.23]. Certain control results are described in Sect. 32.3.2.

Electroplated Microactuators with Fine Gaps

Finally, fabrication processes developed at the University of Tokyo demonstrate additional techniques for obtaining very small gaps between electrostatic fingers [32.24]. Similar to the IBM process, electrostatic fingers are electroplated, in this case by nickel, within a polymer pattern. The gap between closely spaced fingers, however, is then formed by a sacrificial metal. Photoresist is used to cover the fingers except for the surfaces where a small gap is desired; these are electroplated with sacrificial copper, making narrow, well-defined gaps possible, in perhaps the most reliable of the processes described here. Continuing with a second nickel electroplating step creates the interlaced fingers, which will also support the slider; the wafer is polished down to level the structure. Finally the copper, photoresist, and seed layer are etched away, leaving the free standing structure.

In another version of process, photoresist alone separates the stator and rotor fingers. In this case, a thin layer of photoresist is left where small gaps are desired, instead of growing a layer of copper. This method is dependent on excellent alignment but can eliminate the need for polishing after the second electroplating step.

32.2.5 Suspension-Level Fabrication Processes

The long, highly integrated fabrication processes required by actuated slider microactuators contrast greatly with the fabrication of actuated suspension microactuators.

PZT Actuated Suspensions

In most cases, actuated suspensions use piezoelectric (PZT) drivers cut or etched as single, homogeneous pieces and attached to the steel suspension. Nevertheless, microfabrication techniques can still be useful in suspension processing. For example, some recent suspensions have used thin film PZT deposited on a substrate by sputtering or spinning-on of a sol-gel for incorporation in a suspension. This is intended to produce a higher quality PZT films and begins to introduce MEMS-style processing techniques even into suspension-scale manufacturing [32.25, 26].

Integrated Silicon Suspension

Another area where silicon processing has been suggested for use on a suspension is the gimbal region, or even the entire suspension, as described in [32.19]. An integrated silicon suspension would incorporate aspects of both actuated suspension and actuated slider fabrication. Force is provided by four piezes of bulk PZT cut down to size, as in other actuated suspensions, but the rest of the suspension is fabricated from single-crystal silicon by bulk micromachining.

The fabrication process for the integrated suspension is the precursor to the ABR process used to fabricate the microactuator in Sect. 32.2.3. Layers of LPCVD silicon nitride and polysilicon are deposited on a bare silicon wafers. The polysilicon is doped by ion implantation and covered with a second layer of nitride. The outline of the suspension and any spaces within it are then lithographically patterned. After a reactive-ion nitride etch to reach the substrate, trenches are etched by DRIE. The trenches are then plugged with spin-on-polymer for further lithography. First, the top layer of polysilicon is patterned into piezoresisistive strips for sensing vibration. Second, a layer of photoresist is patterned for copper lift-off, to create metal interconnects. Last, the planarizing polymer is removed, and the entire surface is coated with silicon nitride. This final coating protects the top surface during an anisotropic backside wet etch, in this case by potassium hydroxide.

Instrumented Suspensions

Finally, microfabrication techniques may be useful for installing sensors on conventional steel suspensions. The concept is to deposit a dielectric and a piezoresistive material on the stainless steel sheet that will be formed into the central piece of the suspension and then to pattern piezoresistive layer directly by photolithography and etching to form strain gages. A second lithography may be used to add metal lines back to the E-block. Vibration sensors on the suspension are very desirable for controlling slider position, and the use of thin-film deposition and photolithography permits the sensors to be located at the points most effective for detecting vibration. An example of a sensor formed by this method is shown in Fig. 32.17.

32.2.6 Actuated Head Fabrication

Several interesting fabrication processes have been proposed for another approach to creating a dual-stage disk drive servo: the actuated head. In an actuated head, the actuator is built into the slider and moves just the read/write head. This could potentially eliminate many of the mechanical limits of actuated suspensions or actuated sliders. Actuation techniques are typically similar to those of actuated sliders, with the key complication being the need to integrate an actuator fabrication process with a slider fabrication process. We discuss ways in which this might be done below.

One fabrication approach to actuating a read/write head is to enclose an electrostatic driving array inside a slider. The slider is built on a glass or silicon substrate, beginning with the air-bearing surface (ABS), followed by a microactuator, and then surrounded by the remainder of the slider. The ABS is formed by silicon oxide deposited over aluminum and tapered photoresist layers that give it a contoured shape. The majority of the ABS is then covered with photoresist, while a block in the center is plated with nickel and etched to form the electrostatic actuator. The electrostatic microactuator, in turn, is covered while the remainder of the slider body is electroplated. The slider may then be bonded to a suspension and the ABS surface released from the substrate by etching away the original aluminum and photoresist surface [32.9].

The sacrificial metal technique described in Sect. 32.2.4 is another possibility for building an electrostatic array onto a slider. It can be used to form small array with very narrow gaps, and the process is compatible with slider and head materials [32.27].



Fig. 32.17 Piezoresistive strain sensor on steel substrate

The third actuated-head process makes use of an SOI wafer and silicon based materials. For this structure, a 20 μm device layer is coated with silicon nitride. The nitride is patterned with contact holes for connections to the substrate and used as insulation over the rest of the device. A layer of molybdenum is sputter deposited to perform interconnections to both the head and the electrostatic array. This array is formed by DRIE to the buried oxide, using a lithographically patterned hard mask of tetraethylorthosilicate. The result is a simple, tiny, actuator that must be bonded to the edge of a slider after release from the SOI wafer [32.28].

32.3 Servo Control Design of MEMS Microactuator Dual-Stage Servo Systems

The objective of disk drive servo control is to move the read/write head to the desired track as quickly as possible, referred to as track seek control, and, once on-track, position the head on the center of the track as precisely as possible, referred to as track-following control, so that data can be read/written quickly and reliably. The implementation of the servo controller relies on the position error signal (PES), which is obtained by reading the position information encoded on the disk's data tracks.

32.3.1 Introduction to Disk Drive Servo Control

The position error is also called track mis-registration (TMR) in the disk drive industry. Major TMR sources in the track-following mode include spindle runout, disk fluttering, bias force, external vibration/shock disturbance, arm and suspension vibrations due to air turbulence, PES noise, written-in repeatable runout, and residual vibration due to seek/settling [32.29]. These sources can be categorized as runout, r, input disturbance, d, and measurement noise, n, by the locations they are injected into the control system, as shown in Fig. 32.18. In Fig. 32.18, $G_P(s)$ and $G_C(s)$ represent the disk drive actuator and the controller, respectively; r and x_p represent track runout and head position, respectively.

From Fig. 32.18, the PES can be written as

$$\mathrm{PES} = S(s)r + S(s)G_P(s)d - S(s)n\,, \tag{32.9}$$

where $S(s)$ is the closed loop sensitivity function defined by

$$S(s) = \frac{1}{1 + G_C(s)G_P(s)}\,. \tag{32.10}$$

The higher the bandwidth of the control system, the higher the attenuation of the sensitivity function $S(s)$ below the bandwidth. Thus, one of the most effective methods to reduce PES and increase servo precision is to increase the control system bandwidth.

Traditional disk drive servo systems utilize a single voice coil motor (VCM) to move the head. Multiple structural resonance modes of the E-block arm and the suspension located between the pivot and the head impose a major limitation on the achievable control bandwidth. A dual-stage servo system using a MEMS actuated-slider microactuator can achieve high bandwidth because the microactuator is located between the suspension and the slider, thus by-passing the pivot, E-block arm, and suspension resonance modes.



Fig. 32.18 Disk drive servo control

One basic task of dual-stage servo control design is to increase control bandwidth using the second stage actuator. Many design methodologies have been developed to accomplish this objective. In this section, we first review major dual-stage servo control design methodologies, and then we discuss design considerations for controller design of a MEMS microactuator dual-stage servo system. As design examples, the details of track-following control designs using a sensitivity function decoupling design method and the μ-synthesis design method are presented in Sect. 32.3.3. In Sect. 32.3.4, we introduce a short-span seek control scheme using a dual-stage actuator based on decoupled feed forward reference trajectories generations.

32.3.2 Overview of Dual-Stage Servo Control Design Methodologies

Various control design architectures and methodologies have been developed for dual-stage servo control design. They can be largely classified into two categories: those based on decoupled or sequential single-input-single-output (SISO) designs, and those based on modern optimal design methodologies, such as LQG, LQG/LTR, H_∞, and μ-synthesis, in which the dual-stage controllers are obtained simultaneously.

Two constraints must be considered in dual-stage servo control design. First, the contribution from each actuator must be properly allocated. Usually the first stage actuator, or the coarse actuator, has a large moving range but a low bandwidth while the second stage actuator, or the fine actuator, has a high bandwidth but small moving range. Second, the destructive effect, in which the two actuators fight each other by moving in opposite directions, must be avoided.

Classical SISO Design Methodologies

Several architectures and design methodologies have been proposed to transform the dual-stage control design problem into decoupled or sequential multiple SISO compensators design problems, for example, master–slave design, decoupled design [32.30], PQ method [32.31], and direct parallel design [32.32]. Figures 32.19 to 32.22 shows the block diagrams of dual-stage controller designs using these methods. In these figures, G_1 and G_2 represent the coarse actuator (VCM) and fine actuator (microactuator) respectively; x_1 is the position of the coarse actuator; x_r is the position of the fine actuator relative to the coarse actuator; x_p is the total position output; r is the reference input (runout), and PES is the position error, $e = r - x_\mathrm{p}$.



Fig. 32.19 Master–slave design structure



Fig. 32.20 Decoupled control design structure



Fig. 32.21 PQ control design structure



Fig. 32.22 Parallel control design structure

Master–slave Design. In a traditional master–slave structure, the absolute position error is fed to the fine actuator, and output of the fine actuator is fed to the coarse actuator, as shown in Fig. 32.19. The position error will be compensated by the high bandwidth fine actuator. The coarse actuator will follow the fine actuator to prevent its saturation.

Decoupled Design. Figure 32.20 shows the decoupled design structure [32.30], which is similar to the master–slave structure. A summation of the fine actuator output and the position of the coarse actuator, is fed the coarse actuator. A very nice feature of this structure is that the control system is decoupled into two independent control loops, and the total sensitivity function is the product of the sensitivity functions of each of the control loops [32.13]. Thus the two compensators C_1 and C_2 can be designed independently. Decoupled design is also referred to as decoupled master–slave design, or sensitivity function decoupling design. In Sect. 32.3.3, we will discuss details of a track-following controller for MEMS microactuator dual-stage servo system designed using this method.

Both the master–slave and the decoupled designs use the relative position of the fine actuator, x_r. If a relative position sensor is unavailable, x_r can be estimated using a model of the fine actuator.

PQ Design Method. The PQ method is another innovative design technique for control design of dual-input, single-output system [32.31]. A block diagram of a dual-stage control design using this method is shown in Fig. 32.21.

In PQ design, P is defined by

$$P = \frac{G_1}{G_2} , \qquad (32.11)$$

and a dual-stage controller can be designed in two steps. The first involves the design of an auxiliary compensator Q for plant P, which is defined by

$$Q = \frac{C_1}{C_2} . \qquad (32.12)$$

Q is designed to parameterize the relative contribution of the coarse and fine actuators. The 0 dB crossover frequency and phase margin of the open loop transfer function PQ are the design parameters in the design of Q. At frequencies below the 0 dB crossover frequency of PQ, the output is dominated by the coarse actuator, while at frequencies above the 0 dB crossover frequency, the output is dominated by the fine actuator. At the 0 dB crossover frequency, the contributions from the two actuators are equal. A large phase margin of PQ will ensure that the two actuators will not fight each other when their outputs are close in magnitude, thus avoiding any destructive effects.

The second step in the PQ design methodology is to design a compensator C_0 for SISO plant PQ such that the bandwidth (crossover frequency), gain margin, phase margin, and error rejection requirements of the overall control system are satisfied.

Direct Parallel Design. It is also possible to design the dual-stage controller directly using a parallel structure, as shown in Fig. 32.22, by imposing some design constraints and by sequential loop closing [32.32].

The two constraints for parallel design in terms of the PES open loop transfer functions are [32.32]:

$$C_1(s)G_1(s) + C_2(s)G_2(s) \to C_2(s)G_2(s) \,, \quad (32.13)$$

at high frequencies and

$$|C_1(s)G_1(s) + C_2(s)G_2(s)| \gg |C_2(s)G_2(s)| \,, \quad (32.14)$$

at low frequencies. The first constraint implies that open loop frequency response of the dual-stage control system at high frequencies approximately equals that of the fine actuator control loop. Thus the compensator $C_2(s)$ can be first designed independently as a SISO design problem to satisfy the bandwidth, gain margin, and phase margin requirements of the dual-stage control system. The second constraint ensures that the fine actuator will not be saturated. Compensator $C_1(s)$ can then be designed for the SISO plant model with the fine actuator control loop closed, such that the low frequency constraint and overall stability requirement are satisfied. This model is defined by:

$$G(s) = \frac{G_1(s)}{1 + C_2(s)G_2(s)} \,. \quad (32.15)$$

A dual-stage controller for a MEMS dual-stage actuator servo system has been designed using this method and implemented at IBM. An open loop gain crossover frequency of 2.39 kHz with gain margin 5.6 dB and phase margin 33° was obtained. In experimental testing, a 1-σ TMR of 0.024 µm has been achieved [32.32].

Modern MIMO Design Methodologies

Since the dual-stage actuator servo system is a MIMO system, it is natural to utilize modern MIMO optimal design methodologies, such as LQG, LQG/LTR, H_∞, and µ-synthesis, to design the dual-stage controller. Usually MIMO optimal designs are based on the parallel structure shown in Fig. 32.22, augmented with noise/disturbances models and other weighting functions to specify the control design performance objectives.

Linear quadratic Gaussian (LQG) control combines a Kalman filter and optimal state feedback control based on the separation principle. However, the Kalman filter weakens the desirable robustness properties of the optimal state feedback control. Linear quadratic Gaussian/loop-transfer recovery (LQG/LTR) control recovers robustness by a Kalman filter redesign process. Examples of dual-stage control designs using LQG and LQG/LTR have been reported in [32.33–35].

The LQG design methodology minimizes the H_2 norm of the control system, while the H_∞ design methodology minimizes the H_∞ norm of the control system. µ-synthesis design methodology is based on the H_∞ design and accounts for plant model uncertainties during the controller synthesis process with guaranteed robustness. Examples of dual-stage control designs based on the H_∞ and µ-synthesis design methodologies have been reported in [32.33, 36, 37]. A control design using µ-synthesis for the MEMS microactuator dual-stage servo system will be presented in Sect. 32.3.3

Other advanced control theories also have been applied to dual-stage servo control designs, such as sliding mode control [32.38] and neural networks [32.39].

32.3.3 Track-Following Controller Design for a MEMS Microactuator Dual-Stage Servo System

MEMS microactuators for dual-stage servo application are usually designed to have a single flexure resonance mode between 1–2 kHz [32.8,40]. This resonance mode is usually very lightly damped and can have a ±15% variations due to the differences in the fabrication processes. Since the uncertain resonance frequency is relatively low and close to the open loop gain crossover frequency of the control system, robustness to these variations must be considered in the controller design.

Controller Design Considerations for MEMS Microactuator Dual-stage Servo System

Capacitive sensing can be utilized in MEMS microactuators to measure the position of the microactuator relative to the VCM actuator [32.14, 40]. However, this requires additional sensing electronics and wires to and from the head gimbal assembly (HGA), which result in additional fabrication and assembly costs. Thus, whether or not a relative position sensor will be used in MEMS dual-stage servo systems is still an open question. If the microactuator's resonance mode is lightly damped, it is susceptible to airflow turbulence and external disturbances. The relative position signal can be utilized to damp the microactuator's resonance mode. Dual-stage control can be classified as MIMO or SIMO designs according to the availability of the relative position signal.

Given the fact that the inertia of the MEMS microactuator is very small compared to that of the VCM, the effect of the motion of the microactuator on the VCM can be neglected. By feeding the control input of the VCM to the input of the microactuator with a proper gain, we can cancel the coupling effect of the VCM on the microactuator [32.13]. Thus the dual-stage control model can be decoupled as the sum of the outputs of the VCM and the microactuator, as shown in Fig. 32.23, in which G_V, G_M are the VCM and microactuator models respectively, and x_p is the absolute position of the read/write head, which equals the absolute position of the VCM, x_v, and the position of the microactuator relative to the VCM, RPES.

Decoupled Track-Following Control Design and Self-Tuning Control

Figure 32.24 shows a block diagram used for decoupled control design of a MEMS microactuator dual-stage servo systems [32.13].

Sensitivity Function Decoupling Design Methodology. The part enclosed in the dashed box on the upper-right corner is the dual-stage plant model shown in Fig. 32.23. In the figure, G_V and G_M are the VCM and microactuator models, respectively; x_P is the absolute position of the read/write head; x_v is the absolute position of the VCM actuator; and RPES is the position of the microactuator relative to the VCM; r represents the track runout, and PES is the position error signal of the head relative to the data track.



Fig. 32.23 Dual-stage control plant



Fig. 32.24 Decoupled dual-stage control design block diagram



Fig. 32.25 The sensitivity block diagram

The decoupling control approach, originally introduced in [32.30], utilizes the PES and RPES signals to generate the position error of the VCM relative to the data track center, labeled as $VPES$,

$$VPES = \text{PES} + \text{RPES} = r - x_v \,, \tag{32.16}$$

and this signal is fed to the VCM loop compensator.

As shown in the block diagram, three compensators need to be designed: the VCM loop compensator K_V; the microactuator PES loop compensator K_M; and the microactuator RPES minor loop compensator $K_{MM} = K_{RR}/K_{RS}$ is used to damp the microactuator's flexure resonance mode and place the closed loop poles of the microactuator RPES loop at appropriate locations. The damped microactuator closed loop transfer function G_R, shown in the lower-middle dashed box, is defined by

$$G_R = \frac{G_M}{K_{RS} + G_M K_{RR}} \,. \tag{32.17}$$

The total dual-stage open loop transfer function from r to x_P, G_T, is

$$G_T = K_V G_V + K_M G_R + K_M G_R K_V G_V \,. \tag{32.18}$$

It can be shown that the block diagram in Fig. 32.24 is equivalent to the sensitivity block diagram shown in Fig. 32.25, and the total closed loop sensitivity function from r to PES equals the product of the VCM and microactuator loop sensitivities, S_V and S_M, respectively:

$$S_T = \frac{1}{1 + G_T} = S_V S_M \,, \tag{32.19}$$

where

$$S_V = \frac{1}{1 + K_V G_V} \,, \; S_M = \frac{1}{1 + K_M G_R} \,. \tag{32.20}$$

Thus the dual-stage servo control design can be decoupled into two independent designs: the VCM loop and the microactuator loop designs. The VCM loop sensitivity can be designed using traditional single-stage servo design methodologies. The microactuator loop sensitivity is designed to expand the bandwidth and increase the attenuation of low frequency runout and disturbances.



Fig. 32.26 Illustration of dual-stage sensitivity S_T design

Closed Loop Sensitivity Design by Pole Placement. For a typical sampled second order system with the discrete time transfer function

$$G\left(q^{-1}\right)=\frac{q^{-1}B_o\left(q^{-1}\right)}{A_o\left(q^{-1}\right)}\,, \tag{32.21}$$

where q^{-1} is one step delay operator; $B_o\left(q^{-1}\right)$ is the plant zero polynomial, and $A_o\left(q^{-1}\right)=1+a_1q^{-1}+a_2q^{-2}$ is the plant pole polynomial. The closed loop sensitivity function can be designed by pole placement, solving the following Diophantine equation [32.41]:

$$\begin{aligned}A_{\mathrm{c}}\left(q^{-1}\right)=A_o\left(q^{-1}\right)S\left(q^{-1}\right)\\+q^{-1}B_o\left(q^{-1}\right)R\left(q^{-1}\right)\,,\end{aligned} \tag{32.22}$$

where $A_{\mathrm{c}}\left(q^{-1}\right)$ is the desired closed loop characteristic polynomial. The closed loop sensitivity function, G_{S}, is

$$G_{\mathrm{S}}\left(q^{-1}\right)=\frac{A_o\left(q^{-1}\right)\,S\left(q^{-1}\right)}{A_{\mathrm{c}}\left(q^{-1}\right)}\,, \tag{32.23}$$

and the discrete time controller $C\left(q^{-1}\right)$ is

$$C\left(q^{-1}\right)=\frac{R\left(q^{-1}\right)}{S\left(q^{-1}\right)}\,. \tag{32.24}$$

$A_{\mathrm{c}}\left(q^{-1}\right)$ can be chosen such that the required bandwidth and system response are satisfied. Usually it is more intuitive to describe it with its continuous time equivalent parameters: the damping ratio, ζ, and the natural frequency, ω_n. The damping ratio is directly related to the phase margin of the open loop transfer function. For a typical design, it can be chosen to be equal to or greater than one, in order to ensure adequate phase margin. ω_n is related to the control system's bandwidth, which is limited by sampling frequency and time delay, or the high frequency structural dynamics of the system.

Dual-Stage Sensitivity Function Design. The compensators in the dual-stage servo system depicted in Fig. 32.24 can be designed by a two-step design process, as illustrated in Fig. 32.26.

First, the VCM loop compensator K_{V} is designed to attain a desired VCM closed loop sensitivity S_{V}, as shown in the top part of Fig. 32.26. Its bandwidth, ω_{VC} in Fig. 32.26, is generally limited by the E-block and suspension resonance modes. The design of this compensator can be accomplished using conventional SISO frequency shaping techniques.

The second step of the design process involves the design of the microactuator loop compensators to attain additional attenuation S_{M}, as shown in the middle part of Fig. 32.26. This step is itself accomplished in two steps. First, the minor RPES loop compensator, $K_{\mathrm{RR}}/K_{\mathrm{RS}}$, is determined in order to damp the microactuator resonance mode and place the poles of G_{R}, or equivalently ω_{MR} in Fig. 32.26, at desired locations. The compensator can be obtained by solving a Diophantine equation by pole placement as discussed in the previous subsection. The poles of G_{R} will become the zeros of the microactuator loop sensitivity function, S_{M}.

Finally, the PES loop compensator K_{M} is designed to place the poles, or equivalently. ω_{MC} in Fig. 32.26, of the microactuator loop closed loop sensitivity S_{M}. ω_{MC} is limited by the PES sampling frequency and computational time delay [32.42].

The total dual-stage sensitivity is shown in the bottom part of Fig. 32.26. For a given ω_{MC}, the additional attenuation A_S, provided by the microactuator loop, will be determined by ω_{MR}. In our proposed procedure, the initial value of ω_{MR} can be chosen to be the same as ω_{VC}. It is then adjusted so the desired attenuation and phase margin requirements of the overall dual-stage system are satisfied. Decreasing ω_{MR} increases the low frequency attenuation of the closed loop sensitivity function S_{T} but also generally reduces the phase margin of open loop transfer function G_{T}.

For SIMO design when the RPES is not available, the microactuator model can be used as an open loop observer to estimate the RPES. The combination of the open loop observer and the minor loop compensator is equivalent to a notch filter.

Self-Tuning Control to Compensate Variations in the Microactuator's Resonance Mode. An adaptive control scheme can be combined with the decoupled discrete time pole placement design methodology described above to compensate variations in the microactuator's resonance mode by tuning the microactuator RPES inner loop compensator.

A block diagram for the microactuator inner loop self-tuning control is shown in Fig. 32.27. The parameter adaptation algorithm (PAA) is a direct self-tuning algorithm, based on the microactuator inner loop pole placement design.

Consider the microactuator open loop transfer function in (32.21). Since the microactuator's resonance mode is lightly damped, the zero of the microactuator's discrete time transfer function is very close to 1 ($z_o \approx 1$). Thus it is possible to factor out the "known" term $(1+z_o q^{-1})$ from the Diophantine equation (32.22). The resulting RPES minor-loop closed loop dynamics is given by

$$A_{\mathrm{c}}\left(q^{-1}\right) y(k) = q^{-1} b_0 \left(1+z_o q^{-1}\right) \times\left[K_{\mathrm{RS}}\left(q^{-1}\right) u_{\mathrm{M}}(k) + K_{\mathrm{RR}}\left(q^{-1}\right) y(k)\right] ,$$

where u_{M} is the control input to the microactuator; y denotes the position of the microactuator relative to the VCM, i.e. $y = \mathrm{RPES}$. Defining:



Fig. 32.27 Self-tuning control of the microactuator

$$S\left(q^{-1}\right) = b_0 K_{\mathrm{RS}}\left(q^{-1}\right) = s_0 + s_1 q^{-1} , \tag{32.25}$$

$$R\left(q^{-1}\right) = b_0 K_{\mathrm{RR}}\left(q^{-1}\right) = r_0 + r_1 q^{-1} , \tag{32.26}$$

the regressor vector, $\phi(k)$ and filtered regressor vector, $\phi_{\mathrm{f}}(k)$,

$$\phi(k) = \left[u_{\mathrm{M}}(k)\ u_{\mathrm{M}}(k-1)\ y(k)\ y(k-1)\right] , \tag{32.27}$$

$$A_{\mathrm{c}}\left(q^{-1}\right) \phi_{\mathrm{f}}(k) = \left(1+z_o q^{-1}\right) \phi(k) , \tag{32.28}$$

and the controller parameter vector $\theta = [s_0\ s_1\ r_0\ r_1]^T$, the closed loop RPES dynamics (32.25) can be rewritten as

$$y(k) = \theta^T \phi_{\mathrm{f}}(k-1) . \tag{32.29}$$

From (32.29), the controller parameter vector estimate $\hat{\theta}(k) = [\hat{s}_0(k)\ \hat{s}_1(k)\ \hat{r}_0(k)\ \hat{r}_1(k)]^T$ can be updated using a standard recursive least square algorithm (RLS) [32.41]:

$$\hat{\theta}(k) = \hat{\theta}(k-1) + P(k)\phi_{\mathrm{f}}(k)e^o(k) , \tag{32.30}$$

$$e^o(k) = y(k) - \hat{\theta}^T(k-1)\phi_{\mathrm{f}}(k-1) , \tag{32.31}$$

$$P(k) = \left[P(k-1) - \frac{P(k-1)\phi_{\mathrm{f}}(k-1)\phi_{\mathrm{f}}^T(k-1)P(k-1)}{1+\phi_{\mathrm{f}}^T(k-1)P(k-1)\phi_{\mathrm{f}}(k-1)}\right] , \tag{32.32}$$

The control law is

$$\hat{S}\left(k, q^{-1}\right) u_{\mathrm{M}}(k) = \hat{S}_o(k) u_{\mathrm{M}}(k) - \hat{R}\left(k, q^{-1}\right) y(k) , \tag{32.33}$$

with

$$\hat{S}\left(k, q^{-1}\right) = \hat{s}_0(k) + \hat{s}_1(k) q^{-1} , \tag{32.34}$$

$$\hat{R}\left(k, q^{-1}\right) = \hat{r}_0(k) + \hat{r}_1(k) q^{-1} , \tag{32.35}$$

and $u_{\mathrm{M}}(k)$ being the output of the microactuator fixed outer loop compensator K_{M}, $u_{\mathrm{M}}(k)$ being the control input to the microactuator.

Dual-Stage Track-Following Control Design Using μ-Synthesis

The structured singular value, μ, is a measure of how big a perturbation to a system needs to be to make the system unstable. By incorporating a fictitious uncertainty block, robust performance in terms of the H_∞ norm of the closed loop transfer function can be related to the value of μ. μ-synthesis is a robust optimal controller design technique that attempts to minimize μ through an iterative process [32.43].

Design Methodology. For controller design using μ-synthesis, the model uncertainties are represented using linear fractional transformations (LFT). Disturbances and outputs are weighted to characterize the real plant environment and the performance requirements. A block diagram used for dual-stage μ-synthesis controller design is shown in Fig. 32.28.

In the block diagram, two model uncertainties, δ_1 and δ_2, are considered. δ_1 is an additive uncertainty used to describe the VCM unmodeled dynamics. δ_2 represents the parametric uncertainty in the stiffness of the microactuator.

Disturbance signals accounted for in the model include the track runout r, input disturbances to the VCM d_{VCM}, input disturbances to the microactuator d_{MA}, PES sensor noise n_{PES}, and the $RPES$ sensor noise n_{RPES}. These disturbance signals are generated by passing normalized signals $\overline{r}$, $\overline{d_{\mathrm{VCM}}}$, $\overline{d_{\mathrm{MA}}}$, $\overline{n_{PES}}$, and $\overline{n_{RPES}}$ through weighting functions W_r, $W_{d\mathrm{VCM}}$, $W_{d\mathrm{MA}}$, W_{nPES}, and W_{nRPES}, respectively, which can be either constants or frequency shaping filters. These weights are selected by the designer so that disturbances are modeled with sufficient fidelity.

The output signals in the synthesis model are head position error signal, PES, the microactuator relative position signal, $RPES$, the VCM control input u_{VCM}, and the microactuator control input u_{MA}. These signals are multiplied by scaling factors, W_{PES}, W_{RPES}, $W_{u\mathrm{VCM}}$, and $W_{u\mathrm{MA}}$, respectively, to produce the weighted performance signals $\overline{PES}$, $\overline{RPES}$, $\overline{u_{\mathrm{VCM}}}$, $\overline{u_{\mathrm{MA}}}$. The scaling factors are selected to characterize the performance requirements.

Given a set of input and output weights and plant uncertainties, if the synthesized controller achieves

$$\mu \le \beta\,, \tag{32.36}$$

the closed loop transfer function, $\overline{T}$, from the normalized disturbances

$$\overline{d} = \left[\overline{r}\ \overline{d_{\mathrm{VCM}}}\ \overline{d_{\mathrm{MA}}}\ \overline{n_{\mathrm{PES}}}\ \overline{n_{\mathrm{RPES}}}\right], \tag{32.37}$$

to the weighted performance signals

$$\overline{e} = \left[\overline{\mathrm{PES}}\ \overline{\mathrm{RPES}}\ \overline{u_{\mathrm{VCM}}}\ \overline{u_{\mathrm{MA}}}\right], \tag{32.38}$$

will have infinity norm

$$\|\overline{T}\|_\infty \le \beta\,, \tag{32.39}$$

for perturbations

$$\|\Delta\|_\infty = \left\| \begin{bmatrix} \delta_1 & 0 \\ 0 & \delta_2 \end{bmatrix} \right\|_\infty \le \frac{1}{\beta}\,. \tag{32.40}$$

The interpretation of H_∞ as the RMS gain of the sinusoidal signals to help understand the design is as follows. Assume that each element $\overline{d_i}$ of the disturbance



W_{UVCM}
$\overline{u_{\mathrm{VCM}}}$
$\overline{\mathrm{PES}}$
W_{PES}
$\overline{n_{\mathrm{PES}}}$
W_{NPES}
$\overline{d_{\mathrm{VCM}}}$
W_{DVCM}
W_{U1}
δ1
x_{V}
+
$\overline{r}$
W_{R}
r
−
PES
K
u_{VCM}
u_{MA}
+
VCM
MA
x_{p}
RPES
+
+
RPES
W_{NRPES}
$\overline{n_{\mathrm{RPES}}}$
W_{DMA}
δ1
$\overline{d_{\mathrm{MA}}}$
W_{RPES}
$\overline{\mathrm{RPES}}$
W_{UMA}
$\overline{u_{\mathrm{MA}}}$

Fig. 32.28 μ-synthesis design block diagram

input vector in (32.37) is a sinusoid of the form

$$\overline{d_i}(t) = D_i \sin(\omega_i t + \psi_i)\,, \tag{32.41}$$

such that

$$\sum_{i=1}^{5} D_i^2 \leq 1\,. \tag{32.42}$$

Then the steady state response of output in (32.38) will also be a sinusoid of the form

$$\overline{e_i}(t) = E_i \sin(\omega_i t + \phi_i)\,, \tag{32.43}$$

and

$$\sum_{i=1}^{4} E_i^2 \leq \beta\,, \tag{32.44}$$

under the perturbations defined in (32.40).

Weighting Functions for μ-Synthesis Design. Performance weights are chosen based on limits that the error signals should not exceed. The limit on the PES is based on a rule of thumb commonly used in the disk drive industry which states that the position error of the head should not exceed 1/10 of a track width during track following. RPES is limited by the stroke limit of the microactuator. Thus,

$$W_{\mathrm{PES}} = \frac{10}{\text{track width}}\,; \quad W_{\mathrm{RPES}} = \frac{1}{\text{stroke limit}}\,. \tag{32.45}$$

Weights on control inputs are based on the control input saturations.

$$W_{UVCM} = \frac{1}{(i_{\mathrm{V}})_{\max}}\,; \quad W_{U\mathrm{MA}} = \frac{1}{(v_{\mathrm{M}})_{\max}}\,, \tag{32.46}$$

where $(i_{\mathrm{V}})_{\max}$ and $(v_{\mathrm{M}})_{\max}$ are the maximum drive current of the VCM and the maximum drive voltage of the microactuator, respectively.

The weights for PES noise, n_{PES}, and the disturbance to the VCM, $w_{d\mathrm{VCM}}$, were determined by extrapolating the PES decomposition results presented in [32.29]. The weight of the RPES sensing noise, n_{RPES}, is assumed to be 8 nm [32.14]. The disturbance weight, $w_{d\mathrm{MA}}$, is assumed to be 0.1 V in the design.

The runout weighting function is a low pass filter that captures the combined effects of track runout, mechanical vibrations, and bias force disturbance to PES,

$$W_{\mathrm{r}} = \frac{2\times 10^{-8}(s + 2\pi\times 10)^2}{(s + 2\pi\times 1000)^2}\,. \tag{32.47}$$

The combination of W_{PES} and W_{r} determines the closed loop sensitivity function from r to PES, $S(s)$, of the dual-stage system. If the designed control system achieves a peak μ value of β, we have

$$\left\| W_{\mathrm{PES}} S(s) W_{\mathrm{r}} \right\|_{\infty} \leq \beta\,. \tag{32.48}$$

If $\beta = 1$, the magnitude of bode plot of $S(s)$ lies below that of $1/W_{\mathrm{PES}} W_{\mathrm{r}}$.

For SIMO design, the controller to be synthesized has only one input. In the synthesis model, RPES is not fed to the controller K, and RPES noise n_{rpes} and its weights W_{nRPES} are not used.

Design and Simulation Results

Figure 32.29 shows the Bode plots of the open loop transfer functions from r to $x_{\mathrm{p}}p$ and the closed loop sensitivity functions of the two designs, respectively. Sampling frequency was chosen to be 20 kHz in both designs.

For the decoupled MIMO design, the gain crossover frequency, gain margin, phase margin of the open loop system are 2,201 Hz, 9.1 dB, and 48.8°, respectively. For the decoupled SIMO design, they are 2,381 Hz, 8.7 dB, and 30.6°, respectively.

For μ-synthesis MIMO design, the gain crossover frequency, gain margin, phase margin of the open loop system are 2,050 Hz, 9.5 dB, 66.0°, respectively. For μ-synthesis SIMO design, they are 2,223 Hz, 2.9 dB, 32.0°, respectively.

The above controller designs have not been implemented on a MEMS microactuator dual-stage servo system. Controllers designed using both methods have been tested on a PZT actuated suspension dual-stage servo system, however, validating their effectiveness [32.44].

Figure 32.30 shows the simulation of control parameters adaptation for the self-tuning controller, when the real microactuator resonance frequency is 1.2 times its nominal value. The controller parameters converge to their desired values. Similar responses were obtained when the real resonance frequency is 0.8 times the nominal value.

32.3.4 Dual-Stage Seek Control Design

Because the inertia of a microactuator is much smaller than that of the VCM, it can produce a larger acceleration and move faster than the VCM. The motion range of a microactuator is usually limited to a few micrometers, however. Thus the performance improvement in seek control made possible by using



Fig. 32.29 **(a)** Open loop Bode plot of the decoupled design; **(b)** open loop Bode plot of the μ-synthesis design; **(c)** closed loop sensitivity Bode plot of the decoupled design; **(d)** closed loop sensitivity Bode plot of the μ-synthesis design

dual-stage actuation will mainly be in short distance seeks.

Two degree-of-freedom (DOF) position control has been a very popular control technique in short distance seeks. A 2-DOF control technique utilizing decoupled feed forward reference trajectories has been developed for short span seek control using a PZT actuated suspension dual-stage servo system [32.45]. The same technique can also be applied to seek control of MEMS microactuator dual-stage servo system.

Figure 32.31 shows a block diagram for dual-stage short span seek control design using this method. In the figure, x_{V}^{d} and x_{R}^{d} are the desired seek trajectories of the VCM and the microactuator respectively. K_{VF} and K_{RF} are Zero Phase Error Tracking Feed Forward Controllers (ZPETFFC) generated using with the VCM model G_{V} and the damped microactuator model G_{R} [32.46].

To minimize the residual vibration after seek operation, minimum jerk seek trajectories were applied to both the VCM and the microactuator. These can be generated



Fig. 32.30 Control parameters adaptation response

by [32.47]

$$x_{\mathrm{V}}^d(t) = 60\, d_s \left[\frac{1}{10}\left(\frac{t}{T_{\mathrm{V}}}\right)^5 - \frac{1}{4}\left(\frac{t}{T_{\mathrm{V}}}\right)^4 + \frac{1}{6}\left(\frac{t}{T_{\mathrm{V}}}\right)^3\right], \tag{32.49}$$

$$x_{\mathrm{R}}^d = \begin{cases} 60\,\left(d_s - x_{\mathrm{V}}^d(T)\right) & \\ \times\left[\frac{1}{10}\left(\frac{t}{T}\right)^5 - \frac{1}{4}\left(\frac{t}{T}\right)^4 + \frac{1}{6}\left(\frac{t}{T}\right)^3\right] & t \le T\,, \\ d_s - x_{\mathrm{V}}^d(t) & t > T \end{cases} \tag{32.50}$$

where d_s is the distance of the head from the target track; T is the time when the head reaches the target track if dual-stage actuator is used, while T_{V} is the time when the head reaches the target track if only VCM is used. T_{V} and T can be chosen based on the control force saturation and seek performance requirements.



Fig. 32.31 Dual-stage seek control design



Fig. 32.32 Dual-stage short span seek response

Figure 32.32 shows the 1 µm seek responses of the dual-stage actuator for the MIMO design. Overshoot was eliminated, and no obvious residual vibrations occured. The seek time using the dual-stage actuator is about 0.25 ms, compared to a seek time of about 0.7 ms if only the VCM is used.

32.4 Conclusions and Outlook

In order to increase hard disk drive storage density, high bandwidth dual-stage servo systems are necessary to suppress disturbances and increase servo precision. Various prototype MEMS microactuators have been designed and fabricated to provide a dual-stage actuation system. The most common approach for these prototypes is to use electrostatic driving arrays produced by MEMS fabrication methods.

MEMS microactuators provide a potentially high performance and low cost solution for achieving the servo requirements for extremely high HDD storage density. Simulations and experiments show that many

MEMS microactuator features, such as integrated silicon gimbals and capacitive relative position sensing arrays, can meet important requirements for operation of HDDs. The use of structural electrical-isolation in the microactuator design could considerably reduce microactuator driving voltages, while processes that avoid the use of silicon-on-insulator wafers or high-temperature processing steps could reduce manufacturing costs. High bandwidth dual-stage track-following controllers have been designed using both a decoupled SISO design method and robust μ-synthesis design method, among others. In addition, short-span seeking control using a 2-DOF control structure with decoupled feed forward trajectory generation can greatly reduce the short span seek time.

Research remains to be done in the areas of system integration, reliability, and performance enhancement for this technology to be utilized in commercial products. Cost and reliability are probably the most important obstacles to commercial implementation of actuated slider dual-stage servo systems at this time. Streamlining of microactuator fabrication processes or development of a process compatible with that of the slider and head fabrication could reduce manufacturing costs, which are not quite yet economical. Meanwhile, dynamic behavior and reliability of the microactuator under disturbances from airflow, head-disk interaction, and particle presence are being experimentally studied by industry.

Further in the future, to achieve nanometer servo precision, third-generation dual-stage servo systems will have to employ an actuated head approach. Research in this area has just started, with the key problem being how to combine microactuator fabrication with read/write head fabrication. Another area of research is the use of MEMS technology to incorporate additional sensors, such as accelerometers and strain gauge vibration sensors, to suppress the TMR due to airflow and external disturbances excited structural vibrations. New robust, adaptive MIMO control architectures and algorithms must be developed for such a multisensing and multiactuation servo system.

Besides the application of MEMS microactuators in dual-stage servo control of traditional rotating media magnetic HDDs, recent advances in MEMS and nanotechnology have made possible the development of a new class of miniaturized ultra-high density storage devices that use probe arrays for recording and reading data. This new architecture abandons the traditional rotating media and flying slider paradigm in favor of parallel x-y scanning of entire probe arrays over a storage medium. The probe arrays and/or the media are moved with electrostatic or electromagnetic microactuators that generate x-y in-plane relative motion, as well as z-axis out-of-plane relative motion. One example of this new generation of storage devices is IBM's "millipede," which utilizes atomic force microscopy (AFM) recording technology [32.48]. Data is recorded on a polymer media by tiny depressions melted by a thermomechanical process by the AFM tips. 400 Gb/in.^{2} bit patterns have been demonstrated using thermal probes.

By any of the paths above, MEMS and nanotechnology will become a basic enabling technology for the development of future data storage devices, offering the capabilities of small size, low power consumption, ultra-high densities, low cost, and high performance.

References

32.1 T. Yamaguchi: Modelling and control of a disk file head-positioning system, Proc. Inst. Mech. Eng. I (J. Syst. Cont. Eng.) **215** (2001) 549–567

32.2 T. Howell, R. Ehrlich, M. Lippman: TPI growth is key to delaying superparamagnetism's arrival, Data Stor. (1999) 21–30

32.3 R. B. Evans, J. S. Griesbach, W. C. Messner: Piezoelectric microactuator for dual-stage control, IEEE Trans. Magn. **35** (1999) 977–981

32.4 I. Naniwa, S. Nakamura, S. Saegusa, K. Sato: Low voltage driven piggy-back actuator of hard disk drives, IEEE International MEMS 99 Conference (IEEE, Piscataway 1999) 49–52

32.5 D. Horsley: Microfabricated electrostatic actuators for magnetic disk drives. Ph.D. Thesis (University of California, Berkeley 1998)

32.6 L. Muller: Gimballed electrostatic microactuators with embedded interconnects. Ph.D. Thesis (University of California, Berkeley 2000)

32.7 S. Koganezawa, K. Takaishi, Y. Mizoshita, Y. Uematsu, T. Yamada: Development of integrated piggyback milli-actuator for high density magnetic recording, International Conference on Micromechatronics for Information and Precision Equipment 1997 (IEEE, New York 1997) 20–23

32.8 L.-S. Fan, T. Hirano, J. Hong, P. R. Webb, W. H. Juan, W. Y. Lee, S. Chan, T. Semba, W. Imaino,

T. S. Pan, S. Pattanaik, F. C. Lee, I. McFadyen, S. Arya, R. Wood: Electrostatic microactuator and design considerations for hdd application, IEEE Trans. Magn. **35** (1999) 1000–1005

32.9 T. Imamura, M. Katayama, Y. Ikegawa, T. Ohwe, R. Koishi, T. Koshikawa: MEMS-based integrated head/actuator/slider for hard disk drives, IEEE/ASME Trans. Mechatron. **3** (1998) 166–174

32.10 T. Imamura, T. Koshikawa, M. Katayama: Transverse mode electrostatic microactuator for MEM-based HDD slider, Proc. IEEE MEMS Workshop, San Diego 1996 (IEEE, New York 1996) 216–221

32.11 S. Nakamura, K. Suzuki, M. Ataka, H. Fujita: An electrostatic micro actuator for a magnetic head tracking system of hard disk drives, Transducers '97 (IEEE, Piscataway 1997) 1081–1084

32.12 Y. Soeno, S. Ichikawa, T. Tsuna, Y. Sato, I. Sato: Piezoelectric piggy-back microactuator for hard disk drive, IEEE Trans. Magn. **35** (1999) 983–987

32.13 Y. Li, R. Horowitz: Mechatronics of electrostatic microactuator for computer disk drive dual-stage servo systems, IEEE/ASME Trans. Mechatron. **6** (2001) 111–121

32.14 N. Wongkomet: Position sensing for electrostatic micropositioners. Ph.D. Thesis (University of California, Berkeley 1998)

32.15 A. Hac, L. Liu: Sensor and actuator location in motion control of flexible structures, J. Sound Vib. **167** (1993) 239–261

32.16 K. Hiramoto, H. Doki, G. Obinata: Optimal sensor/actuator placement for active vibration control using explicit solution of algebraic Riccati equation, J. Sound Vib. **229** (2000) 1057–1075

32.17 P. Cheung, R. Horowitz, R. Howe: Design, fabrication and control of an electrostatically driven polysilicon microactuator, IEEE Trans. Magn. **32** (1996) 122–128

32.18 T. Chen, Y. Li, K. Oldham, R. Horowitz: MEMS application in computer disk drive drive dual-stage servo systems, J. Soc. Instrum. Control Eng. **41** (2002) 412–420

32.19 T.-L. Chen: Design and fabrication of PZT-actuated silicon suspensions for hard disk drives. Ph.D. Thesis (University of California, Berkeley 2001)

32.20 C. G. Keller, R. T. Howe: HexSil tweezers for teleoperated micro-assembly, 10th Int'l Workshop on Micro Electro Mechaninical Systems (MEMS'97), Nagoya 1997 (IEEE, New York 1997) 72–77

32.21 T. J. Brosnihan, J. M. Bustillo, A. P. Pisano, R. T. Howe: Embedded interconnect and electrical isolation for high-aspect-ratio, SOI inertial instruments, International Conference on Solid-State Sensors and Actuators, New York 1997 (IEEE, New York 1997) 637–640

32.22 T. Hirano, L.-S. Fan, T. Semba, W. Y. Lee, J. Hong, S. Pattanaik, P. Webb, W.-H. Juan, S. Chan: Microactuator for tera-storage, IEEE Int'l MEMS 1999 Conference, Orlando 1999 (IEEE, Piscataway 1999) 6441–6446

32.23 T. Hirano, L.-S. Fan, T. Semba, W. Lee, J. Hong, S. Pattanaik, P. Webb, W.-H. Juan, S. Chan: High-bandwidth HDD tracking servo by a moving-slider micro-actuator, IEEE Trans. Magn. **35** (1999) 3670–3672

32.24 T. Iizuka, T. Oba, H. Fugita: Electrostatic micro actuators with high-aspect-ratio driving gap for hard disk drive applications, Int'l Symposium on micromechatronics and human science (IEEE, Piscataway 2000) 229–236

32.25 H. Kuwajima, K. Matsuoka: Thin film piezoelectric dual-stage actuator for HDD, InterMag Europe, Session BS04 (IEEE, Piscaraway 2000) BS4

32.26 Y. Lou, P. Gao, B. Qin, G. Guo, E.-H. Ong, A. Takada, K. Okada: Dual-stage servo with on-slider PZT microactuator for hard disk drives, InterMag Europe, Session BS03, Amsterdam 2002 (IEEE, Piscataway 2002)

32.27 H. Fujita, K. Suzuki, M. Ataka, S. Nakamura: A microactuator for head positioning system of hard disk drives, IEEE Trans. Magn. **35** (1999) 1006–1010

32.28 B.-H. Kim, K. Chun: Fabrication of an electrostatic track-following micro actuator for hard disk drives using SOI wafer, J. Micromech. Microeng. **11** (2001) 1–6

32.29 R. Ehrlich, D. Curran: Major HDD TMR sources, and projected scaling with TPI, IEEE Trans. Magn. **35** (1999) 885–891

32.30 K. Mori, T. Munemoto, H. Otsuki, Y. Yamaguchi, K. Akagi: A dual-stage magnetic disk drive actuator using a piezoelectric device for a high track density, IEEE Trans. Magn. **27** (1991) 5298–5300

32.31 S. J. Schroeck, W. C. Messner, R. J. McNab: On compensator design for linear time-invariant dual-input single-output systems, IEEE/ASME Trans. Mechatron. **6** (2001) 50–57

32.32 T. Semba, T. Hirano, L.-S. Fan: Dual-stage servo controller for HDD using MEMS actuator, IEEE Trans. Magn. **35** (1999) 2271–2273

32.33 T. Suzuki, T. Usui, M. Sasaki, F. Fujisawa, T. Yoshida, H. Hirai: Comparison of robust track-following control systems for a dual stage hard disk drive, Proc. of International Conference on Micromechatronics for Information and Precision Equipment, ed. by B. Bhushan, K. Ohno (Word Scientific, Singapore 1997) 101–118

32.34 X. Hu, W. Guo, T. Huang, B. M. Chen: Discrete time LQG/LTR dual-stage controller design and implementation for high track density HDDs, Proc. of American Automatic Control Conference (IEEE, Piscataway 1999) 4111–4115

32.35 S.-M. Suh, C. C. Chung, S.-H. Lee: Design and analysis of dual-stage servo system for high track density HDDs, Microsyst. Technol. **8** (2002) 161–168

32.36 D. Hernandez, S.-S. Park, R. Horowitz, A. K. Packard: Dual-stage track-following servo design for hard disk drives, Proc. of American Automatic Control Conference (IEEE, Piscataway 1999) 4116–4121

32.37 M. Rotunno, R. A. de Callafon: Fixed order H_∞ control design for dual-stage hard disk drives, Proc. of the 39th IEEE Conference on Decision and Control (IEEE, Piscataway 2000) 3118–3119

32.38 S.-H. Lee, S.-E. Baek, Y.-H. Kim: Design of a dual-stage actuator control system with discrete-time sliding mode for hard disk drives, Proc. of the 39th IEEE Conference on Decision and Control (IEEE, Piscataway 2000) 3120–3125

32.39 M. Sasaki, T. Suzuki, E. Ida, F. Fujisawa, M. Kobayashi, H. Hirai: Track-following control of a dual-stage hard disk drive using a neuro-control system, Eng. Appl. Artif. Intell. **11** (1998) 707–716

32.40 D. Horsley, N. Wongkomet, R. Horowitz, A. Pisano: Precision positioning using a microfabricated electrostatic actuator, IEEE Trans. Magn. **35** (1999) 993–999

32.41 K. J. Åström, B. Wittenmark: *Adaptive Control*, 2nd edn. (Addison-Wesley, Reading 1995)

32.42 M. T. White, W.-M. Lu: Hard disk drive bandwidth limitations due to sampling frequency and computational delay, Proc. of the 1999 IEEE/ASME International Conference on Intelligent Mechatronics (IEEE, Piscataway 1999) 120–125

32.43 G. J. Balas, J. C. Doyle, K. Glover, A. Packard, R. Smith: *μ-Analysis and Synthesis ToolBox* (MUSYN Inc. and The MathWorks, Natick 1995)

32.44 Y. Li, R. Horowitz: Design and testing of track-following controllers for dual-stage servo systems with PZT actuated suspensions [in HDD], Microsyst. Technol. **8** (2002) 194–205

32.45 M. Kobayashi, R. Horowitz: Track seek control for hard disk dual-stage servo systems, IEEE Trans. Magn. **37** (2001) 949–954

32.46 M. Tomizuka: Zero phase error tracking algorithm for digital control, Trans. ASME J. Dynam. Syst. Meas. Control **109** (1987) 65–68

32.47 Y. Mizoshita, S. Hasegawa, K. Takaishi: Vibration minimized access control for disk drive, IEEE Trans. Magn. **32** (1996) 1793–1798

32.48 P. Vettiger, G. Cross, M. Despont, U. Drechsler, U. Durig, B. Gotsmann, W. Haberle, M. A. Lantz, H. W. Rothuizen, R. Stutz, G. K. Binnig: The "millipede" – nanotechnology entering data storage, IEEE Trans. Nanotechnol. **1** (2002) 39–55

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

33. Micro/Nanotribology of MEMS/NEMS Materials and Devices

The field of MEMS/NEMS has expanded considerably over the last decade. The length scale and large surface-to-volume ratio of the devices result in very high retarding forces such as adhesion and friction that seriously undermine the performance and reliability of the devices. These tribological phenomena need to be studied and understood at the micro- to nanoscales. In addition, materials for MEMS/NEMS must exhibit good microscale tribological properties. There is a need to develop lubricants and identify lubrication methods that are suitable for MEMS/NEMS. Using AFM-based techniques, researchers have conducted micro/nanotribological studies of materials and lubricants for use in MEMS/NEMS. In addition, component level testing has also been carried out to aid in better understanding the observed tribological phenomena in MEMS/NEMS.

Macroscale and microscale tribological studies of silicon and polysilicon films have been performed. The effects of doping and oxide films and environment on the tribological properties of these popular MEMS/NEMS materials have also been studied. SiC film is found to be a good tribological material for use in high-temperature MEMS/NEMS devices. Hexadecane thiol self-assembled monolayers and bonded perfluoropolyether lubricants appear to be well suited for lubrication of microdevices under a range of environmental conditions. DLC coatings can also be used for low friction and wear. Surface roughness measurements of micromachined polysilicon surfaces have been made using an AFM. The roughness distribution on surfaces is strongly dependent on the fabrication process. Roughness should be optimized for low adhesion, friction, and wear. Adhesion and friction of microstructures can be measured using novel apparatuses. Adhesion and friction measurements on silicon-on-silicon confirm AFM measurements that hexadecane thiol and bonded perfluoropolyether films exhibit superior adhesion and friction properties. Static friction force measurements of micromotors have been performed using an AFM. The forces are found to vary considerably with humidity. A bonded layer of perfluoropolyether lubricant is found to satisfactorily reduce the friction forces in the micromotor.

AFM/FFM-based techniques can be satisfactorily used to study and evaluate micro/nanoscale tribological phenomena related to MEMS/NEMS devices.

This chapter presents a review of macro- and micro/nanoscale tribological studies of materials and lubrication studies for MEMS/NEMS and component-level studies of stiction phenomena in MEMS/NEMS devices.

33.1 **Introduction to MEMS** 985

33.2 **Introduction to NEMS** 988

33.3 **Tribological Issues in MEMS/NEMS** 989
  33.3.1 MEMS 989
  33.3.2 NEMS 994
  33.3.3 Tribological Needs 995

33.4 **Tribological Studies of Silicon and Related Materials** 995
  33.4.1 Tribological Properties of Silicon and the Effect of Ion Implantation 996
  33.4.2 Effect of Oxide Films on Tribological Properties of Silicon 998
  33.4.3 Tribological Properties of Polysilicon Films and SiC Film 1000

33.5 **Lubrication Studies for MEMS/NEMS** 1003
  33.5.1 Perfluoropolyether Lubricants 1003
  33.5.2 Self-Assembled Monolayers (SAMs) 1004
  33.5.3 Hard Diamond-like Carbon (DLC) Coatings 1008

33.6 **Component-Level Studies** 1009
  33.6.1 Surface Roughness Studies of Micromotor Components 1009
  33.6.2 Adhesion Measurements 1011
  33.6.3 Static Friction Force (Stiction) Measurements in MEMS 1014
  33.6.4 Mechanisms Associated with Observed Stiction Phenomena in Micromotors 1016

References 1017

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Microelectromechanical systems (MEMS) refer to microscopic devices that have a characteristic length of less than 1 mm but more than 1 µm and combine electrical and mechanical components. Nanoelectromechanical systems (NEMS) refer to nanoscopic devices that have a characteristic length of less than 1 µm and combine electrical and mechanical components. In mesoscale devices, if the functional components are on the micro- or nanoscale, they may be referred to as MEMS or NEMS, respectively. To put the dimensions and masses in perspective, see Fig. 33.1 and Table 33.1. The acronym MEMS originated in the United States. The term commonly used in Europe and Japan is micro/nanodevices, which is used in a much broader sense. MEMS/NEMS terms are also now used in a broad sense. A micro/nanosystem, a term commonly used in Europe, is referred to as an intelligent miniaturized system comprising sensing, processing, and/or actuating functions.

Fabrication techniques include top-down methods, in which one builds down from the large to the small, and the bottom-up methods, in which one builds up from the small to the large. Top-down methods include micro/nanomachining methods and methods based on lithography, as well as nonlithographic miniaturization for MEMS and NEMS fabrication. In the bottom-up methods, also referred to as nanochemistry, the devices and systems are assembled from their elemental constituents for NEMS fabrication, much like the way nature uses proteins and other macromolecules to


MEMS – characteristic length
less than 1 mm,
larger than 1 µm
NEMS – less than 1000 nm
Human hair
50–100 µm
DMD
14 µm
Mirror
Hinge
Yoke
Landing site
Red blood cell
8 µm
500 nm
Source
Drain
Quantum-dot transistor
300 nm
DNA
2.5 nm
Molecular gear
10 nm–100 nm
C atom
0.16 nm
0.1
1
10
100
1,000
10,000
100,000
Size (nm)

Fig. 33.1 Dimensions of MEMS and NEMS in perspective. An example of molecular dynamic simulations of carbon-nanotube-based gear is obtained from [33.1], quantum-dot transistor is obtained from [33.2], and DMD is obtained from [33.3]

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

Table 33.1 Dimensions and masses in perspective

A Dimensions in Perspective	
NEMS characteristic length	$< 1,000$ nm
MEMS characteristic length	< 1 mm and > 1 µm
Individual atoms	typically fraction of a nm in diameter
DNA molecules	~ 2.5 nm wide
Molecular gear	~ 50 nm
Biological cells	in the range of thousands of nm in diameter
Human hair	$\sim 75,000$ nm in diameter
B Masses in Perspective	
NEMS built with cross sections of about 10 nm	as low as 10^{-20} N
Micromachine silicon structure	as low as 1 nN
Water droplet	~ 10 µN
Eyelash	~ 100 nN

construct complex biological systems. The bottom-up approach has the potential to go far beyond the limits of top-down technology by producing nanoscale features through synthesis and subsequent assembly. Furthermore, the bottom-up approach offers the potential to produce structures with enhanced and/or completely new functions. It allows the combination of materials with distinct chemical composition, structure, and morphology.

MEMS and emerging NEMS are expected to have a major impact on our lives, comparable to that of semiconductor technology, information technology, or cellular and molecular biology [33.4, 5]. MEMS/NEMS are used in mechanical, information/communication, chemical, and biological applications. The MEMS industry in 2000 was worth about $15 billion and, with a projected 10–20% annual growth rate, is expected to be more than $100 billion by the end of this decade [33.6]. Growth of Si MEMS may slow down and non-silicon MEMS may pick up during this decade. The NEMS industry is expected to expand in this decade, mostly in biomedical applications, as well as in nanoelectronics or molecular electronics. The NEMS industry was worth about $100 million in 2002 and integrated NEMS are expected to be more than $25 billion by the end of this decade. Due to the enabling nature of these systems, and because of the significant impact they can have on both commercial and defense applications, industry, as well as the federal government have taken a special interest in seeing growth nurtured in this field. Micro- and nanosystems are the next logical step in the "silicon revolution."

33.1 Introduction to MEMS

The advances in silicon photolithographic process technology beginning in the 1960s led to the development of MEMS in the early 1980s. More recently, lithographic processes have been developed to process nonsilicon materials. The lithographic processes are being complemented with non-lithographic processes for fabrication of components or devices made from plastics or ceramics. Using these fabrication processes, researchers have fabricated a wide variety of miniaturized devices, including Si-based devices, chemical and biological sensors and actuators, and miniature non-silicon structures (e.g., devices made from plastics or ceramics) with dimensions in the range of a couple to a few thousand microns (see e.g., [33.7–15]). MEMS for mechanical applications include acceleration, pressure, flow, gas sensors, linear and rotary actuators, and other microstructures or microcomponents such as electric motors, gear trains, gas turbine engines, nozzles, fluid pumps, fluid valves, switches, grippers, and tweezers. MEMS for chemical applications include chemical sensors and various analytical instruments. Microoptoelectromechanical systems, or MOEMS, include micromirror arrays and fiber optic connectors. BIOMEMS include biochips. Radio frequency MEMS or RF-MEMS include inductors, capacitors, and antennas. High-aspect-ratio MEMS (HARMEMS) have also been introduced.

The fabrication techniques for MEMS devices include lithographic and non-lithographic techniques. The lithographic techniques fall into three basic categories: bulk micromachining, surface micromachining, and LIGA (a German acronym for Lithographie Galvanoformung Abformung), a German term for lithography, electroforming, and plastic molding. The first two approaches, bulk and surface micromachining, use planar photolithographic fabrication processes developed for semiconductor devices in producing two-dimensional (2-D) structures [33.10, 15–17]. The various steps involved in these two fabrication processes are shown schematically in Fig. 33.2. Bulk micromachining employs anisotropic etching to remove sections through the thickness of a single-crystal silicon wafer, typically 250 to 500 μm thick. Bulk micromachining is a proven high-volume production process and is routinely used to fabricate microstructures such as accelerometers, pressure sensors, and flow sensors. In surface micromachining, structural and sacrificial films are alternatively deposited, patterned and etched to produce a freestanding structure. These films are typically made of low-pressure chemical vapor deposition (LPCVD) polysilicon film with 2 to 20 μm thickness. Surface micromachining is used to produce sensors, actuators, and complex microdevices such as micromirror arrays, motors, gears, and grippers.

The LIGA process is based on the combined use of X-ray lithography, electroforming, and molding processes. The steps involved in the LIGA process are shown schematically in Fig. 33.3. LIGA is used to produce high-aspect-ratio MEMS (HARMEMS) devices that are up to 1 mm in height and only a few microns in width or length [33.18]. The LIGA process yields very sturdy 3-D structures due to their increased thickness. One of the limitations of silicon microfabrication processes originally used for fabrication of MEMS devices is the lack of suitable materials that can be processed. With LIGA, a variety of non-silicon materials such as metals, ceramics, and polymers can be processed. Nonlithographic micromachining processes, primarily in Europe and Japan, are also being used for fabrication of millimeter-scale devices using direct material microcutting or micromechanical machining (such as microturning, micromilling, and microdrilling), or removal by energy beams (such as microspark erosion, focused ion beam, laser ablation, and laser polymerization) [33.19, 20]. Hybrid technologies, including LIGA and high-precision micromachining techniques, have been used to produce miniaturized motors, gears, actuators, and connectors [33.21–24]. These millimeter-scale devices may find more immediate applications.


Bulk micromachining
Deposition of silica layers on Si
Membrane
<111> face
Patterning with mask and etching of Si to produce cavity
Silicon
Silica
Surface micromachining
Deposition of sacrificial layer
Patterning with mask
Deposition of microstructure layer
Etching of sacrificial layer to produce freestanding structure
Silicon
Polysilicon
Sacrificial material

Fig. 33.2 Schematics of process steps involved in bulk micromachining and surface micromachining fabrication of MEMS



Fig. 33.3 Schematic of process steps involved in LIGA fabrication of MEMS

A microfabrication technique, so-called "soft lithography," is a nonlithographic technique [33.25, 26] in which an elastomeric stamp or mold is used to generate micropatterns by replica molding [33.27], embossing (imprinting) [33.28], or by contact printing (known as microcontact printing or μCP) [33.29]. Replica molding is commonly used for mass-produced, disposable plastic microcomponents, for example, microfluidic chips, generally made of poly(dimethylsiloxane) (PDMS) and polymethyl methacrylate (PMMA). The elastomeric stamps are generally cast from photolithographically generated micropatterned masters. This technique is substantially cheaper and more flexible in choice of materials for construction than conventional photolithography.

To assemble microsystems, microrobots are used. Microrobotics include building blocks such as steering links, microgrippers, conveyor system, and locomotive robots [33.13].

A variety of MEMS devices have been produced and some are commercially used [33.8, 10–12, 14, 15]. A variety of sensors are used in industrial, consumer, defense, and biomedical applications. Various microstructures or microcomponents are used in micro-instruments and other industrial applications such as micromirror arrays. Two of the largest "killer" industrial applications are accelerometers (about 85 million units in 2002) and digital micromirror devices (about $400 million in sales in 2001). Integrated capacitive-type, silicon accelerometers have been used in airbag deployment in automobiles since 1991 [33.30, 31]. Accelerometer technology was about a billion-dollar-a-year industry in 2001 dominated by Analog Devices, followed by Motorola and Bosch. Commercial digital light processing (DLP) equipments, using digital micromirror devices (DMD), were launched in 1996 by Texas Instruments for digital projection displays in portable and home theater projectors, as well as table top and projection TVs [33.32–34]. More than 1.5 million projectors were sold before 2002. Other major industrial applications include pressure sensors, inkjet printer heads and optical switches. Silicon-based piezoresistive pressure sensors for manifold absolute pressure sensing for engines were launched in 1991 by NovaSensor, and their annual sales were about 25 million units in 2002. Capacitive pressure sensors for tire pressure measurements were launched by Motorola. Annual sales of inkjet printer heads with microscale functional components were about 400 million units in 2002. Other applications of MEMS devices include chemical sensors, gas sensors, infrared detectors and focal plane arrays for earth observation, space science, and missile defense applications, pico-satellites for space applications, and many hydraulic, pneumatic, and other consumer products. MEMS devices are also being pursued in magnetic storage systems [33.35], where they are being developed for super-compact and ultrahigh-recording-density magnetic disk drives. Several integrated head/suspension microdevices have been fabricated for contact recording applications [33.36, 37]. High-bandwidth servo-controlled microactuators have been fabricated for ultrahigh-track-density applications that serve as the fine-position control element of a two-stage, coarse/fine servo system, coupled with a conventional actuator [33.38–40].

BIOMEMS are used increasingly in commercial and defense applications (e.g., [33.8, 41–44]). Applications of BIOMEMS include biofluidic chips (microfluidic chips or bioflips or simply biochips) for chemical and biochemical analyses (biosensors) in medical diagnostics (e.g., DNA, RNA, proteins, cells, blood pressure and assays, and toxin identification) and implantable pharmaceutical drug delivery. The biosensors, also referred to as lab-on-a-chip, integrate sample handling, separation, detection, and data analysis onto one platform. Biosensors are designed to either detect a single or class of (bio)chemicals or system-level analytical capabilities for a broad range of (bio)chemical species known as micro total analysis systems (µTAS). The chips rely on microfluidics and involve manipulation of tiny amounts of fluids in microchannels using microvalves. The chips consist of several basic components, including microfluidic channels and reservoirs, microvalves, micropumps, flow sensors, and biosensors. The test fluid is injected into the chip generally using an external pump or a syringe for analyses. Some chips have been designed with an integrated electrostatically actuated diaphragm-type micropump. Micropumps both with and without valves are used. The sample, which can have volume measured in nanoliters, flows through microfluidic channels via an electric potential and capillary action using microvalves (having various designs, including membrane type) for various analyses. The fluid is preprocessed and then analyzed using a biosensor. For a review on micropumps and microvalves, see [33.11, 45, 46]. Silicon-based disposable blood-pressure sensor chips were introduced in the early 1990s by NovaSensor for blood pressure monitoring (about 20 million units in 2002). A blood sugar monitor, referred to as GlucoWatch, was introduced in 2002. It automatically checks blood sugar every 10 min by detecting glucose through the skin, without having to draw blood. If glucose is out of the acceptable range, it sounds an alarm so the diabetic can address the problem quickly. A variety of biosensors, many using plastic substrates, are manufactured by various companies, including ACLARA, Agilent Technologies, Calipertech, and I-STAT.

After the tragedy of Sept. 11, 2001, concern over biological and chemical warfare has led to the development of handheld units with bio- and chemical sensors for detection of biological germs, chemical or nerve agents, and mustard agents, and chemical precursors to protect subways, airports, water supply, and population at large [33.47].

Other BIOMEMS applications include minimal invasive surgery, including endoscopic surgery, laser angioplasty, and microscopic surgery. Implantable artificial organs can also be produced.

Micro-instruments and micromanipulators are used to move, position, probe, pattern, and characterize nanoscale objects and nanoscale features. Miniaturized analytical equipment include gas chromatography and mass spectrometry. Other instruments include micro-STM, where STM stands for scanning tunneling microscope.

In some cases, MEMS devices are used primarily for their miniature size. While in others, as in the case of air bags, they are used because of their low-cost manufacturing techniques, since semiconductor-processing costs have reduced drastically over the last decade, allowing the use of MEMS in many fields.

33.2 Introduction to NEMS

NEMS are produced by nanomachining in a typical top-down approach (from large to small) and bottom-up approach (from small to large) largely relying on nanochemistry [33.48–53]. The top-down approach relies on fabrication methods, including advanced integrated-circuit (IC) lithographic methods – electron-beam lithography and STM writing by removing material atom by atom. The bottom-up approach includes chemical synthesis, the spontaneous "self-assembly" of molecular clusters (molecular self-assembly) from simple reagents in solution, or biological molecules (e.g., DNA) as building blocks to produce 3-D nanostructures, quantum dots (nanocrystals) of arbitrary diameter (about $10-10^5$ atoms), molecular beam epitaxy (MBE) and organometallic vapor phase epitaxy (OMVPE) to create specialized crystals one atomic or molecular layer at a time, and manipulation of individual atoms by an atomic force microscope or atom optics. The self-assembly must be encoded. That is, one must be able to precisely assemble one object next to another to form a designed pattern. A variety of nonequilibrium plasma chemistry techniques are also used to produce layered nanocomposites, nanotubes, and nanoparticles. The NEMS field, in addition to fabrication of nanosystems, has provided the impetus to develop experimental and computation tools.

Examples of NEMS include nanocomponents, nanodevices, nanosystems, and nanomaterials such as microcantilevers with integrated sharp nanotips for STM and atomic force microscopy (AFM), AFM array (millipede) for data storage, AFM tips for nanolithography, dip-pen nanolithography for printing molecules, biological (DNA) motors, molecular gears, molecularly thick films (e.g., in giant magnetoresistive or GMR heads, and magnetic media), nanoparticles (e.g., nanomagnetic particles in magnetic media), nanowires, carbon nanotubes, quantum wires (QWRs), quantum boxes (QBs), and quantum transistors. BIONEMS include nanobiosensors – a microarray of silicon nanowires, roughly a few nm in size, to selectively bind and detect even a single biological molecule such as DNA or protein by using nanoelectronics to detect the slight electrical charge caused by such binding, or a microarray of carbon nanotubes to electrically detect glucose, implantable drug-delivery devices – e.g., micro/nanoparticles with drug molecules encapsulated in functionized shells for a site-specific targeting applications and a silicon capsule with a nanoporous membrane filled with drugs for long-term delivery – , nanodevices for sequencing single molecules of DNA in the Human Genome Project, cellular growth using carbon nanotubes for spinal cord repair, nanotubes for nanostructured materials for various applications such as spinal fusion devices, organ growth, and growth of artificial tissues using nanofibers.

Nanoelectronics can be used to build computer memory using individual molecules or nanotubes to store bits of information, molecular switches, molecular or nanotube transistors, nanotube flat-panel displays, nanotube integrated circuits, fast logic gates, switches, nanoscopic lasers, and nanotubes as electrodes in fuel cells.

33.3 Tribological Issues in MEMS/NEMS

Tribological issues are important in MEMS/NEMS requiring intended and/or unintended relative motion. In MEMS/NEMS, various forces associated with the device scale down with size. When the length of the machine decreases from 1 mm to 1 µm, the area decreases by a factor of a million and the volume decreases by a factor of a billion. As a result, surface forces such as adhesion, friction, meniscus forces, viscous drag forces, and surface tension that are proportional to area become a thousand times larger than the forces proportional to the volume such as inertial and electromagnetic forces. In addition to the consequence of a large surface-to-volume ratio, since MEMS/NEMS are designed for small tolerances, physical contact becomes more likely, which makes them particularly vulnerable to adhesion between adjacent components. Since the start-up forces and torques involved in MEMS/NEMS operation available to overcome retarding forces are small, the increase in resistive forces such as adhesion and friction become a serious tribological concern that limits the life and reliability of MEMS/NEMS [33.10]. A large lateral force required to initiate relative motion between two surfaces, large static friction, is referred to as "stiction," which has been studied extensively in tribology of magnetic storage systems [33.35, 54, 55]. A large normal force required to separate two surfaces is also referred to as stiction. Adhesion, friction/stiction (static friction), wear, and surface contamination affect MEMS/NEMS performance and in some cases, can even prevent devices from working. Some examples of devices that experience tribological problems follow.

33.3.1 MEMS

Figure 33.4a shows examples of several microcomponents that can encounter the aforementioned tribological problems. The polysilicon electrostatic micromotor has 12 stators and a four-pole rotor and is produced by surface micromachining. The rotor diameter is 120 µm and the air gap between the rotor and stator is 2 µm [33.56]. It is capable of continuous rotation up to speeds of 100,000 RPM. The intermittent contact at the rotor-stator interface and physical contact at the rotor-hub flange interface result in wear issues, and high stiction between the contacting surfaces limits the repeatability of operation, or may even prevent the operation altogether. Next, a bulk micromachined silicon stator/rotor pair is shown with bladed rotor and nozzle guide vanes on the stator with dimensions less than a mm [33.57]. These are being developed for high-temperature micro-gas turbine generators with an operating speed up to 1 million RPM. Erosion of blades and vanes and wear of bearings used in the turbine generators are some of the concerns. Next, is an SEM micrograph of a surface micromachined polysilicon six-gear chain from Sandia National Lab. (For more examples of previous versions, see [33.58, 59].) As an example of non-silicon components, a milligear system produced using the LIGA process for a DC brushless permanent magnet millimotor (diameter = 1.9 mm, length = 5.5 mm) with an integrated milligear box [33.21–23] is also shown. The gears are made of metal (electroplated Ni-Fe), but can also be made from injected polymer materials (e.g.,



Electrostatic micromoter (*Tai* et al., [33.56])

Microturbine bladed rotor and nozzle guide vanes on the stator (*Spearing* and *Chen*, [33.57])

Six gear chain (www.sandia.gov)

Ni-Fe Wolfrom-type gear system by LIGA (*Lehr* et al., [33.21])

a) Low-pressure flow modulator with electrostatically actuated microvalves (*Robertson* and *Wise*, [33.60])



Multiple microgear speed reduction unit (*Tanner* et al., [33.62])

Fig. 33.4a,b Examples of MEMS devices and components that experience tribological problems: **(a)** several microcomponent and **(b)** a polysilicon, multiple microgear speed reduction unit

Polyoxy-methylene, or POM) using the LIGA process. Even though the torque transmitted at the gear teeth is small, on the order of a fraction of a nNm, because of small dimensions of gear teeth, the bending stresses are large where the teeth mesh. Tooth breakage and wear at the contact of gear teeth are concerns. Next, in a micromachined flow modulator, several micromachined flow channels are integrated in series with electrostatically actuated microvalves [33.60]. The flow channels lead to a central gas outlet hole drilled in the glass substrate. Gas enters the device through a bulk micromachined gas inlet hole in the silicon cap. After passing through an open microvalve, the gas flows parallel to the glass substrate through flow channels and exits the device through an outlet. The normally open valve structure consists of a freestanding double-end-clamped beam, which is positioned beneath the gas inlet orifice. When deflected electrostatically upwards, the beam seals against the inlet orifice, and the valve is closed. In these microvalves used for flow control, the mating valve surfaces should be smooth enough to seal while maintaining a minimum roughness to ensure low adhesion [33.54, 55, 61]. High adhesion (stiction) is a major issue.

Figure 33.4b shows a polysilicon, multiple microgear speed reduction unit and its components after laboratory wear tests conducted in air [33.62]. These units have been developed for an electrostatically driven microactuator (microengine) developed at Sandia National Lab for operation in the kHz frequency range. Wear of various components is clearly observed in the figure. Humidity was shown to be a strong factor in the wear of rubbing surfaces. In order to improve the wear characteristics of rubbing surfaces, 20-nm-thick tungsten (W) coating using chemical vapor deposition (CVD) technique was used [33.63]. Tungsten-coated microengines tested for reliability showed improved wear characteristics with longer lifetimes than polysilicon microengines.

Commercially available MEMS devices also exhibit tribological problems. Figure 33.5 shows an integrated capacitive-type silicon accelerometer fabricated using surface micromachining by Analog Devices, a couple of mm in dimension, which is used for the deployment of airbags in automotives and more recently for


Supporting springs
Suspended mass
Stationary plates
Suspended mass
Stationary plates
Slider
Fixed
Spring
Suspended
Silicon substrate
Suspension
Electrostatic actuator (nickel)

Capacitive-type silicon accelerometer for automotive sensory applications (*Sulouff*, [33.64])

Electroplated-nickel rotary microactuator for magnetic disk drives (*Hirano* et al., [33.40])


Mirror −10 deg
Mirror +10 deg
Hinge
Yoke
Landing site
Tip
Hinge
Yoke
Landing site
Spring tip
CMOS substrate

Digital micromirror device for displays (*Hornbeck*, [33.33])

Fig. 33.5 Examples of commercial use MEMS devices that experience tribological problems

the consumer electronics market [33.30, 64, 65]. These accelerometers are now being developed for many other applications such as vehicle stability, rollover control, and gyro sensor applications. The central suspended beam mass (about 0.7 µg) is supported on the four corners by spring structures. The central beam has interdigitated, cantilevered electrode fingers (about 125 µm long and 3 µm thick) on all four sides that alternate with those of the stationary electrode fingers, as shown, with about a 1.3 µm gap. Lateral motion of the central beam causes a change in the capacitance between these electrodes, which is used to measure the acceleration. Here stiction between the adjacent electrodes, as well as stiction of the beam structure with the underlying substrate are detrimental to the operation of the sensor [33.30, 64]. Wear during unintended contacts of these polysilicon fingers is also a problem. A molecularly thick diphenyl siloxane lubricant film with high resistance to temperature and oxidation, applied by a vapor deposition process is used on the electrodes to reduce stiction and wear.

Figure 33.5 also shows two digital micromirror device (DMD) pixels used in digital light processing (DLP) technology for digital projection displays in portable and home theater projectors, as well as table-top and projection TVs [33.32–34]. The entire array (chip set) consists of a large number of rotatable aluminum micromirrors (digital light switches) that are fabricated on top of a CMOS static random access memory integrated circuit. The surface micromachined array consists of half of a million to more than two million of these independently controlled, reflective micromirrors (mirror size on the order of 14 µm square and 15 µm pitch) that flip backward and forward at a frequency on the order of 5,000 times per s. For the binary operation, a micromirror/yoke structure mounted on torsional hinges is rotated ±10° (with respect to the horizontal plane) as a result of electrostatic attraction between the micromirror structure and the underlying memory cell and is limited by a mechanical stop. Contact between cantilevered spring tips at the end of the yoke (four present on each yoke) with the underlying stationary landing sites is required for true digital (binary) operation. Stiction and wear during a contact between aluminum alloy spring tips and landing sites, hinge memory (metal creep at high operating temperatures), hinge fatigue, shock and vibration failure, and sensitivity to particles in the chip package and operating environment are some of the important issues affecting the reliable operation of a micromirror device [33.66–68]. Perfluorodecanoic acid (PFDA) self-assembled monolayers are used on the tip and landing sites to reduce stiction and wear. The spring tip is employed in order to use the spring stored energy to pop up the tip during pull-off. A lifetime estimate of over 100,000 operating hours with no degradation in image quality is the norm.



Fig. 33.6a,b Schematics of **(a)** a MEMS-based biofluidic chip, commonly known as disposable lab-on-a-chip, and **(b)** (*see next page*) a NEMS-based submicroscopic drug-delivery device, and an intravascular micro/nanoparticles for search-and-destroy diseased blood cells

b) **BioNEMS, submicroscopic drug-delivery device**
(*Ferrari* and *Liu*, [33.73])



BioNEMS, intravascular micro/nanoparticles
(*Martin* and *Grove*, [33.74])


1. Binding (0–8 h after injection)
2. Plug rupture, drug release (12–48 h)
3. Pore formation–cell lysis and death (12–48 h)

Fig. 33.6b

A third MEMS device, shown in Fig. 33.5, is an electrostatically driven rotary microactuator for a magnetic disk drive surface-micromachined by a multilayer electroplating method [33.40]. This high-bandwidth servo-controlled microactuator, located between a slider and a suspension, is being developed for ultrahigh-track-density applications, which serves as the fine-position and high-bandwidth control element of a two-stage, coarse/fine servo system when coupled with a conventional actuator [33.38–40]. A slider is placed on top of the central block of a microactuator, which gives rotational motion to the slider. The bottom of the silicon substrate is attached to the suspension. The radial flexure beams in the central block give the rotational freedom of motion to the suspended mass (slider), and the electrostatic actuator drives the suspended mass. Actuation is accomplished via interdigitated, cantilevered electrode fingers, which are alternatingly attached to the central body of the moving part and to the stationary substrate to form pairs. A voltage applied across these electrodes results in an electrostatic force, which rotates the central block. The inter-electrode gap width is about 2 µm. Any unintended contacts between the moving and stationary electroplated-nickel electrodes may result in wear and stiction.

An example of disposable plastic lab-on-a-chip using microfluidics and BIOMEMS technologies is shown in Fig. 33.6a [33.69]. This biofluidic chip integrates multiple fluidic components on a microfluidic motherboard that can be worn like a wristwatch. It enables the unobstructive assessment of a human's medical condition through continuous blood sampling. It can be used for the analysis of a number of different compounds, including lactate, glucose, carbon dioxide, and oxygen levels in the blood and for the detection of infectious diseases. The test fluid is injected into the microchannels using a micropump, and the flow is regulated using microvalves. A magnetic bead approach is used for identification of target biomolecules based on sandwich immunoassay and electrochemical detection. Adhesion in micropumps and microvalves involving moving parts and adhesion of fluid in microchannels are some of the tribological issues. In both active and passive microvalves, the main wear mechanism appears to be erosion, corrosion, and fatigue. As the magnetic bead particulates are pumped through the microfluidic system, they could erode the valve material. Also, several different reagents are used to perform the necessary analyses. The interaction of these reagents with the valve material could cause corrosive wear. Finally, because the valves are continuously being activated, fatigue failure becomes a concern.

Stiction/friction and wear clearly limit the lifetimes and compromise the performance and reliability of microdevices. Figure 33.7 summarizes tribological problems encountered in some of the MEMS devices and components just discussed. In addition, tribological issues are present in the processes used for fabrication of MEMS/NEMS. For example, in surface micromachining, the suspended structures can sometimes collapse and permanently adhere to the underlying substrate due to meniscus effects during the final rinse and dry process, as shown in Fig. 33.7 [33.70]. Adhesion is caused by water molecules adsorbed on the adhering surfaces and/or because of formation of adhesive bonds by silica residues that remain on the surfaces after the water has evaporated. This so called release stiction is overcome


Tribological issues during device operation
Electrostatic micromotor
Wear
Rotor
Hub
Wear
Stator
Stiction
(meniscus effects)
Capacitive-type accelerometer
Suspended
mass
Impact/
wear
Stiction
(meniscus
effects)
Stationary
plates
Digital micromirror device
Stiction
and wear
Tip
Yoke
Hinge
Landing site
Tribological issues in
surface micromachining
Unreleased beam
Rinse liquid
Released beam before drying
Released beam collapsed to substrate
due to meniscus forces during drying
Silicon
Polysilicon
Sacrificial material

Fig. 33.7 Summary of tribological issues in MEMS device operation and fabrication via surface micromachining

by using dry release methods (e.g., CO_2 critical point drying or sublimation methods [33.71]).

33.3.2 NEMS

Figure 33.8 shows an AFM-based nanoscale data storage system for ultrahigh density magnetic recording that experiences tribological problems [33.72]. The system uses arrays of several thousand silicon microcantilevers ("millipede") for thermomechanical recording and playback on an about 40-nm-thick polymer (PMMA) medium with a harder Si substrate. The cantilevers are integrated with integrated tip heaters that have tips of nanoscale dimensions. Thermomechanical recording is a combination of applying a local force to the polymer layer, and softening it by local heating. The tip heated to about 400 °C is brought in contact with the polymer for recording. Imaging and reading are done using the heater cantilever, originally used for recording, as a thermal read-back sensor by exploiting its temperature-dependent resistance. The principle of thermal sensing is based on the fact that the thermal conductivity between the heater and the storage substrate changes according to the spacing between them. When the spacing between the heater and sample is reduced as the tip moves into a bit, the heater's temperature and hence its resistance will decrease. Thus, changes in temperature of the continuously heated resistor are monitored while the cantilever is scanned over data bits, providing a means of detecting the bits. Erasing for subsequent rewriting is carried out by thermal reflow of the storage field by heating the medium to 150 °C for a few seconds. The smoothness of the reflown medium allows multiple rewriting of the same storage field. Bit sizes ranging between 10 and 50 nm have been achieved by using a 32 × 32 (1024) array write/read chip (3 mm × 3 mm). It has been reported that tip wear occurs through the contact between tip and Si substrate during writing. Tip wear is considered a major factor in device reliability.

Figure 33.6b shows two examples of BIONEMS [33.73, 74]. The figure shows a conceptual model of a submicroscopic drug delivery device with the ability to localize in the areas of need. It is a silicon capsule with a nanoporous membrane filled with drugs for long-term delivery. It uses a nanomembrane with pores as small as 6 nm that are used as flux regulators for the long-term release of drugs. The nanomembrane also protects therapeutic substances from attack by the body's immune system. The figure also shows a conceptual model of an intravascular drug delivery device – micro/nanoparticle used for search-and-destroy disease cells. With the lateral dimensions of 1 µm or less, the particle is smaller than any blood cells. These particles can be injected into the blood stream and travel freely through the circulatory system. In order to direct these drug-delivery micro/nanoparticles to cancer sites, their external surfaces are chemically modified to carry molecules that have lock-and-key binding specificity with molecules that support a growing cancer mass. As soon as the particles dock on the cells, a compound is released that forms a pore on the membrane of the cells, which leads to cell death and ultimately to that of the cancer mass that was nourished by the blood vessel. Adhesion between micro/nanodevices and disease cells is required.

33.3.3 Tribological Needs

The MEMS/NEMS need to be designed to perform expected functions typically in the ms to ps range. Expected life of the devices for high speed contacts can vary from a few hundred thousand to many billions of cycles, e.g., over a hundred billion cycles for DMDs, which puts serious requirements on materials [33.10, 62, 75–78]. Most mechanical properties are known to be scale-dependent [33.79]. The properties of nanoscale structures need to be measured [33.80]. Tribology is an important factor affecting the performance and reliability of MEMS/NEMS [33.10, 49, 81]. There is a need for developing a fundamental understanding of adhesion, friction/stiction, wear, and the roles of surface contamination and environment [33.10]. MEMS/NEMS materials need to exhibit good mechanical and tribological properties on the micro/nanoscale. There is a need to develop lubricants and identify lubrication methods that are suitable for MEMS/NEMS. Component-level studies are required to provide a better understanding of the tribological phenomena occurring in MEMS/NEMS. The emergence of micro/nanotribology and atomic force microscopy-based techniques has provided researchers with a viable approach to address these problems [33.49, 82]. This chapter presents a review of macro- and micro/nanoscale tribological studies of materials and lubrication studies for MEMS/NEMS and component-level studies of stiction phenomena in MEMS/NEMS devices.



Fig. 33.8 Example of a NEMS device – AFM-based nanoscale data storage system with 32×32 tip array – that experiences tribological problems [33.72]

33.4 Tribological Studies of Silicon and Related Materials

Materials of most interest for planar fabrication processes using silicon as the structural material are undoped and boron-doped (p^+-type) single-crystal silicon for bulk micromachining and phosphorus (n^+-type) doped and undoped LPCVD polysilicon films for surface micromachining. Silicon-based devices lack high-temperature capabilities with respect to both mechanical and electrical properties. Researchers have been pursuing SiC as a material for high-temperature microsensor and microactuator applications, for some time [33.83, 84]. SiC is a likely candidate for such applications, since it has long been used in high temperature electronics, high frequency and high power devices. SiC can also be desirable for high-frequency micromechanical resonators, in the GHz range, because of its high modulus of elasticity and, consequently, high resonant frequency. Table 33.2 compares selected bulk properties of SiC and Si(100). Researchers have found low cost techniques of producing single-crystal 3C-SiC (cubic or β-SiC) films via epitaxial growth on large-area silicon substrates for bulk micromachining [33.85] and polycrystalline 3C-SiC films on polysilicon and silicon dioxide layers for surface micromachining of SiC [33.86].

Table 33.2 Selected bulk properties[a] of 3C (β- or cubic) SiC and Si(100)

Sample	Density (kg/m^3)	Hard-ness (GPa)	Elastic modulus (GPa)	Fracture toughness (MPa m$^{1/2}$)	Thermal conductivity[b] (W/m K)	Coeff. of thermal expansion[b] ($\times 10^{-6}$/°C)	Melting point (°C)	Band gap (eV)
β-SiC	3,210	23.5–26.5	440	4.6	85–260	4.5–6	2,830	2.3
Si(100)	2,330	9 –10	130	0.95	155	2 –4.5	1,410	1.1

[a] Unless stated otherwise, data shown were obtained from [33.87]

[b] Obtained from [33.88]

As will be shown, bare silicon exhibits inadequate tribological performance and needs to be coated with a solid and/or liquid overcoat or surface treated (e.g., oxidation and ion implantation, commonly used in semiconductor manufacturing), which exhibit lower friction and wear. SiC films exhibit good tribological performance. Both macroscale and microscale tribological properties of virgin and treated/coated silicon, polysilicon films, and SiC are presented next.

33.4.1 Tribological Properties of Silicon and the Effect of Ion Implantation

Friction and wear of single-crystalline and polycrystalline silicon samples, as well as the effect of ion implantation with various doses of C$^+$, B$^+$, N$_2^+$, and Ar$^+$ ion species at 200 keV energy to improve their friction and wear properties have been studied [33.89–91]. The coefficient of macroscale friction and wear factor of virgin single-crystal silicon and C$^+$-implanted silicon samples as a function of ion dose are presented in Fig. 33.9 [33.89]. The macroscale friction and wear tests were conducted using a ball-on-flat tribometer. Each data bar represents the average value of four to six measurements. The coefficient of friction and wear factor for bare silicon are very high and decrease drastically with ion dose. Silicon samples bombarded above the ion dose of 10^{17} C$^+$ cm^{-2} exhibit extremely low values of coefficients of friction (typically 0.03 to 0.06 in air) and wear factor (reduced by as much as four orders of magnitude). *Gupta* et al. [33.89] reported that a decrease in coefficient of friction and wear factor of silicon as a result of C$^+$ ion bombardment occurred because of formation of silicon carbide, rather than amorphization of silicon. *Gupta* et al. [33.90] also reported an improvement in friction and wear with B$^+$ ion implantation.



Fig. 33.9 Influence of ion doses on the coefficient of friction and wear factor on C$^+$ ion bombarded single-crystal and polycrystalline silicon slid against an alumina ball. V corresponds to virgin single-crystal silicon, while S and P denote tests that correspond to doped single- and polycrystalline silicon, respectively [33.89]

Table 33.3 Surface roughness and micro- and macroscale coefficients of friction of selected samples

Material	RMS roughness (nm)	Coefficient of microscale friction[a]	Coefficient of macroscale friction[b]
Si(111)	0.11	0.03	0.33
C^+-implanted Si(111)	0.33	0.02	0.18

[a] Versus Si_3N_4 tip, tip radius of 50 nm in the load range of 10–150 nN (2.5–6.1 GPa) at a scanning speed of 5 µm/s over a scan area of 1 µm × 1 µm in an AFM

[b] Versus Si_3N_4 ball, ball radius of 3 mm at a normal load of 0.1 N (0.3 GPa) at an average sliding speed of 0.8 mm/s using a tribometer

Microscale friction measurements were performed using an atomic force/friction force microscope (AFM/FFM) [33.49]. Table 33.3 shows values of surface roughness and coefficients of macroscale and microscale friction for virgin and doped silicon. There is a decrease in coefficients of microscale and macroscale friction values as a result of ion implantation. When measured for small contact areas and very low loads used in microscale studies, the indentation hardness and elastic modulus are higher than at the macroscale. This, added to the effect of the small apparent area of contact reducing the number of trapped particles on the interface, results in less plowing contribution and lower friction in the case of microscale friction measurements. Results of microscale wear resistance studies of ion-implanted silicon samples studied using a diamond tip in an AFM [33.92] are shown in Fig. 33.10a, b. For tests conducted at various loads on Si(111) and C^+-implanted Si(111), it is noted that wear resistance of an implanted sample is slightly poorer than that of virgin silicon up to about 80 µN. Above 80 µN, the wear resistance of implanted Si improves. As one continues to run tests at 40 µN for a larger number of cycles, the implanted sample exhibits higher wear resistance than the unimplanted sample. Damage from the implantation in the top layer results in poorer wear resistance. However, the implanted zone at the subsurface is more wear resistant than the virgin silicon.

Hardness values of virgin and C^+-implanted Si(111) at various indentation depths (normal loads) are presented in Fig. 33.10c [33.92]. The hardness at a small indentation depth of 2.5 nm is 16.6 GPa and drops



Fig. 33.10a–c Wear depth as a function of **(a)** load (after one cycle), and **(b)** cycles (normal load = 40 mN) for Si(111) and C^+-implanted Si(111). **(c)** Nanohardness and normal load as a function of indentation depth for virgin and C^+-implanted Si(111) [33.92]

to a value of 11.7 GPa at a depth of 7 nm and a normal load of 100 μN. Higher hardness values obtained in low-load indentation may arise from the observed pressure-induced phase transformation during the nanoindentation [33.93, 94]. An additional increase in the hardness at an even lower indentation depth of 2.5 nm reported here may arise from the contribution of complex chemical films (not from native oxide films) present on the silicon surface. At small volumes there is a lower probability of encountering material defects (dislocations, etc.). Furthermore, according to the strain gradient plasticity theory advanced by *Fleck* et al. [33.95], large strain gradients inherent in small indentations lead to the accumulation of geometrically necessary dislocations that cause enhanced hardening. These are some of the plausible explanations for an increase in hardness at smaller volumes. If the silicon material were to be used at very light loads such as in microsystems, the high hardness of surface films would protect the surface until it is worn.

From Fig. 33.10c, hardness values of C^+-implanted Si(111) at a normal load of 50 μN is 20.0 GPa with an indentation depth of about 2 nm, which is comparable to the hardness value of 19.5 GPa at 70 μN, whereas measured hardness value for virgin silicon at an indentation depth of about 7 nm (normal load of 100 μN) is only about 11.7 GPa. Thus, ion implantation with C^+ results in an increase in hardness in silicon. Note that the surface layer of the implanted zone is much harder compared to the subsurface and may be brittle, leading to higher wear on the surface. The subsurface of the implanted zone is harder than the virgin silicon, resulting in higher wear resistance, which is also observed in the results of the macroscale tests conducted at high loads.

33.4.2 Effect of Oxide Films on Tribological Properties of Silicon

Macroscale friction and wear experiments have been performed using a magnetic disk drive with bare, oxidized, and implanted pins sliding against amorphous-carbon coated magnetic disks lubricated with a thin layer of perfluoropolyether lubricant [33.96–99]. Representative profiles of the variation of the coefficient of friction with a number of sliding cycles for Al_2O_3-TiC slider and bare and dry-oxidized silicon pins are shown in Fig. 33.11. For bare Si(111), after an initial increase, the coefficient of friction drops to a steady state value of 0.1 following the increase, as seen in Fig. 33.11. The rise in the coefficient of friction for the Si(111) pin is associated with the transfer of amorphous carbon from the disk to the pin and the oxidation-enhanced fracture of pin material followed by tribochemical oxidation of the transfer film, while the drop is associated with the formation of a transfer coating on the pin, as shown in Fig. 33.12. Dry-oxidized Si(111) exhibits excellent characteristics, and no significant increase was observed over 50,000 cycles (Fig. 33.11). This behavior has been attributed to the chemical passivity of the oxide and lack of transfer of DLC from the disk to the pin. The behavior of PECVD-oxide (data are not presented here) was comparable to that of dry oxide, but for the wet oxide there was some variation in the coefficient of friction (0.26 to 0.4). The difference between dry and wet oxide was attributed to increased



Fig. 33.11 Coefficient of friction as a function of number of sliding revolutions in ambient air for Si(111) pin in ambient air and dry nitrogen and dry-oxidized silicon pin in ambient air [33.96]

Ambient air, 6,000 cycles



Dry nitrogen, 15,000 cycles



Fig. 33.12 Scanning electron micrographs of Si(111) after sliding against a magnetic disk in a rigid disk drive in ambient air for 6,000 cycles and in dry nitrogen after 15,000 cycles

porosity of the wet oxide [33.96]. Since tribochemical oxidation was determined to be a significant factor, experiments were conducted in dry nitrogen [33.97, 98]. The variation of the coefficient of friction for a silicon pin sliding against a thin-film disk in dry nitrogen is shown in Fig. 33.11. It is seen that in a dry nitrogen environment, the coefficient of friction of Si(111) sliding against a disk decreased from an initial value of about 0.2 to 0.05 with continued sliding. Based on SEM and chemical analysis, this behavior has been attributed to the formation of a smooth amorphous-carbon/lubricant transfer patch and suppression of oxidation in a dry nitrogen environment. Based on macroscale tests using disk drives, it was found that the friction and wear performance of bare silicon is not adequate. With dry-oxidized or PECVD SiO_2-coated silicon, no significant friction increase or interfacial degradation was observed in ambient air.

Table 33.4 and Fig. 33.13 show surface roughness, microscale friction and scratch data, and nanoindentation hardness for various silicon samples [33.92]. Scratch experiments were performed using a diamond tip in an AFM. Results on polysilicon samples are also shown for comparison. Coefficients of microscale friction values for all the samples are about the same. These samples could be scratched at 10 µN load. Scratch depth increased with normal load. Crystalline orientation of silicon has little influence on

Table 33.4 RMS, microfriction, microscratching/microwear, and nanoindentation hardness data for various virgin, coated, and treated silicon samples

Material	RMS roughness[a] (nm)	Coefficient of microscale friction[b]	Scratch depth[c] at 40 µN (nm)	Wear depth[c] at 40 µN (nm)	Nanohardness[c] at 100 µN (GPa)
Si(111)	0.11	0.03	20	27	11.7
Si(110)	0.09	0.04	20		
Si(100)	0.12	0.03	25		
Polysilicon	1.07	0.04	18		
Polysilicon (lapped)	0.16	0.05	18	25	12.5
PECVD-oxide coated Si(111)	1.50	0.01	8	5	18.0
Dry-oxidized Si(111)	0.11	0.04	16	14	17.0
Wet-oxidized Si(111)	0.25	0.04	17	18	14.4
C^+-implanted Si(111)	0.33	0.02	20	23	18.6

[a] Scan size of 500 nm × 500 nm using AFM.

[b] Versus Si_3N_4 tip in AFM/FFM, radius 50 nm; at 1 µm × 1 µm scan size.

[c] Measured using an AFM with a diamond tip of radius 100 nm.



Fig. 33.13 Scratch depth as a function of normal load after 10 cycles for various silicon samples: virgin, treated, and coated [33.92]

scratch resistance, because natural oxidation of silicon in ambient masks the expected effect of crystallographic orientation. PECVD-oxide samples showed the best scratch resistance, followed by dry-oxidized, wet-oxidized, and ion-implanted samples. Ion implantation with C^+ does not appear to improve scratch resistance.

Wear data on the silicon samples are also presented in Table 33.1 [33.92]. PECVD-oxide samples showed superior wear resistance followed by dry-oxidized, wet-oxidized, and ion-implanted samples. This agrees with the trends seen in scratch resistance. In PECVD, ion bombardment during deposition improves the coating properties such as suppression of columnar growth, freedom from pinhole, decrease in crystalline size, and increase in density, hardness, and substrate-coating adhesion. These effects may help in improving the mechanical integrity of the sample surface. Coatings and treatments improved nanohardness of silicon. Note that dry-oxidized and PECVD films are harder than wet-oxidized films, as these films may be porous. High hardness of oxidized films may be responsible for measured high scratch/wear resistance.

33.4.3 Tribological Properties of Polysilicon Films and SiC Film

Studies have also been conducted on undoped polysilicon film, heavily doped (n^+-type) polysilicon film, heavily doped (p^+-type) single-crystal Si(100), and 3C-SiC (cubic or β-SiC) film [33.10, 100, 101]. The polysilicon films studied here are different from the ones discussed previously.



Fig. 33.14 **(a)** Scratch depths for 10 cycles as a function of normal load and **(b)** wear depths as a function of normal load and as a function of number of cycles for various samples [33.10]

Table 33.5 presents a summary of the tribological studies conducted on polysilicon and SiC films. Values for single-crystal silicon are shown for comparison. Polishing of the as-deposited polysilicon and SiC films drastically affects the roughness, as the values reduce by two orders of magnitude. Si(100) appears to be

Table 33.5 Summary of micro/nanotribological properties of the sample materials

Sample	RMS roughness[a] (nm)	P–V distance[a] (nm)	Coefficient of friction		Scratch depth[d] (nm)	Wear depth[e] (nm)	Nano-hardness[f] (GPa)	Young's modulus[f] (GPa)	Fracture toughness[g], K_{IC} MPa m$^{1/2}$
			Micro[b]	Macro[c]					
Undoped Si(100)	0.09	0.9	0.06	0.33	89	84	12	168	0.75
Undoped polysilicon film (as deposited)	46	340	0.05						
Undoped polysilicon film (polished)	0.86	6	0.04	0.46	99	140	12	175	1.11
n^+-Type polysilicon film (as deposited)	12	91	0.07						
n^+-Type polysilicon film (polished)	1.0	7	0.02	0.23	61	51	9	95	0.89
SiC film (as deposited)	25	150	0.03						
SiC film (polished)	0.89	6	0.02	0.20	6	16	25	395	0.78

[a] Measured using AFM over a scan size of 10 µm × 10 µm

[b] Measured using AFM/FFM over a scan size of 10 µm × 10 µm

[c] Obtained using a 3-mm-diameter sapphire ball in a reciprocating mode at a normal load of 10 mN and average sliding speed of 1 mm/s after 4 m sliding distance

[d] Measured using AFM at a normal load of 40 µN for 10 cycles, scan length of 5 µm

[e] Measured using AFM at normal load of 40 µN for 1 cycle, wear area of 2 µm × 2 µm

[f] Measured using nanoindenter at a peak indentation depth of 20 nm

[g] Measured using microindenter with Vickers indenter at a normal load of 0.5 N

the smoothest followed by polished undoped polysilicon and SiC films, which have comparable roughness. The doped polysilicon film shows higher roughness than the undoped sample, which is attributed to the doping process. Polished SiC film shows the lowest friction followed by polished and undoped polysilicon film, which strongly supports the candidacy of SiC films for use in MEMS/NEMS devices. Macroscale friction measurements indicate that SiC film exhibits one of the lowest friction values as compared to the other samples. The doped polysilicon sample shows low friction on the macroscale as compared to the undoped polysilicon sample, possibly due to the doping effect.

Figure 33.14a shows a plot of scratch depth vs. normal load for various samples [33.10, 100]. Scratch depth increases with increasing normal load. Figure 33.15 shows AFM 3-D maps and averaged 2-D profiles of the scratch marks on the various samples. It is observed that scratch depth increases almost linearly with the normal load. Si(100) and the doped and undoped polysilicon films show similar scratch resistance. It is clear from the data that the SiC film is much more scratch resistant than the other samples. Figure 33.14b shows results from microscale wear tests on the various films. For all the materials, the wear depth increases almost linearly with increasing number of cycles. This suggests that the material is removed layer by layer in all the materials. Here also SiC film exhibits lower wear depths than the other samples. Doped polysilicon film wears less than the undoped film. Higher fracture toughness and hardness of SiC compared to Si(100) are responsible for its lower wear. Also the higher thermal conductivity of SiC (see Table 33.2) compared to the other materials leads to lower interface temperatures, which generally results in less degradation of the surface [33.35, 54, 55]. Doping of the polysilicon does not affect the scratch/wear resistance and hardness much. The measurements made on the doped sample are affected by the presence of grain boundaries. These studies indicate that SiC film exhibits desirable tribological properties for use in MEMS devices. Recently, researchers have fabricated SiC micromotors and have reported satisfactory operation at high temperatures [33.102].



Fig. 33.15 AFM 3-D maps and averaged 2-D profiles of scratch marks on various samples [33.10]

33.5 Lubrication Studies for MEMS/NEMS

Several studies of liquid perfluoropolyether (PFPE) lubricant films, self-assembled monolayers (SAMs), and hard diamond-like carbon (DLC) coatings have been carried out for the purpose of minimizing adhesion, friction, and wear [33.49, 66, 99, 103–108]. Many variations of these films are hydrophobic (low surface tension and high contact angle) and have low shear strength, which provide low adhesion, friction, and wear. Relevant details are presented here.

33.5.1 Perfluoropolyether Lubricants

The classical approach to lubrication uses freely supported multimolecular layers of liquid lubricants [33.49, 54, 55]. The liquid lubricants are sometimes chemically bonded to improve their wear resistance. Partially chemically bonded, molecularly thick perfluoropolyether (PFPE) lubricants are widely used for lubrication of magnetic storage media [33.35] and are suitable for MEMS/NEMS devices.



Fig. 33.16 Summary of the adhesive forces of Si(100) and Z-15 and Z-DOL (BW) films measured by force calibration plots and friction force versus normal load plots in ambient air. The schematic (*bottom*) showing the effect of meniscus, formed between the AFM tip and the surface sample, on the adhesive and friction forces [33.103]

Adhesion, friction, and durability experiments have been performed on virgin Si(100) surfaces and silicon surfaces lubricated with two commonly used PFPE lubricants – Z-15 (with -CF_3 nonpolar end groups) and Z-DOL (with -OH polar end groups) [33.49, 103, 105, 106]. Z-DOL film was thermally bonded at 150 °C for 30 min and an unbonded fraction was removed by a solvent (BW) [33.35]. The thicknesses of Z-15 and Z-DOL (BW) films were 2.8 nm and 2.3 nm, respectively. Nanoscale measurements were made using an AFM. The adhesive forces of Si(100), Z-15 and Z-DOL (BW) measured by force calibration plot and friction force versus normal load plot are summarized in Fig. 33.16. The results measured by these two methods are in good agreement. Figure 33.16 shows that the presence of mobile Z-15 lubricant film increases the adhesive force compared to that of Si(100) by meniscus formation [33.54, 55, 109]. The presence of solid phase Z-DOL (BW) film reduces the adhesive force compared to that of Si(100) due to the absence of mobile liquid. The schematic (bottom) in Fig. 33.16 shows the relative size and sources of meniscus. It is well-known that the native oxide layer (SiO_2) on the top of Si(100) wafer exhibits hydrophilic properties, and some water molecules can be adsorbed on this surface. The condensed water will form meniscus as the tip approaches the sample surface. The larger adhesive force in Z-15 is not only caused by the Z-15 meniscus. The nonpolarized Z-15 liquid does not have good wettability and strong bonding with Si(100). In the ambient environment, the condensed water molecules from the environment permeate through the liquid Z-15 lubricant film and compete with the lubricant molecules presented on the substrate. The interaction of the liquid lubricant with the substrate is weakened, and a boundary layer of the liquid lubricant forms puddles [33.105, 106]. This dewetting allows water molecules to be adsorbed on the Si(100) surface as aggregates, along with Z-15 molecules. And both of them can form meniscus while the tip approaches the surface. Thus, the dewetting of liquid Z-15 film results in higher adhesive force and poorer lubrication performance. In addition, as the Z-15 film is pretty soft compared to the solid Si(100) surface, penetration of the tip in the film occurs while pushing the tip downwards. This leads to the large area of the tip involved to form the meniscus at the tip-liquid (mixture of Z-15 and water) interface. It should also be noted that Z-15 has a higher viscosity compared to water, and therefore, Z-15 film provides higher resistance to motion and coefficient of friction. In the case of Z-DOL (BW) film, the active groups of Z-DOL molecules are mostly bonded on Si(100) substrate, thus the Z-DOL (BW) film has low free surface energy and cannot be displaced readily by water molecules, or readily adsorb water molecules. Thus, the use of Z-DOL (BW) can reduce the adhesive force.

To study the relative humidity effect on friction and adhesion, the variations of friction force, adhesive force, and coefficient of friction of Si(100), Z-15, and Z-DOL (BW) as a function of relative humidity are shown in Fig. 33.17. It shows that for Si(100) and Z-15 film, the friction force increases with a relative humidity increase of up to 45% and then slightly decreases with a further increase in relative humidity. Z-DOL (BW) has a smaller friction force than Si(100) and Z-15 in the whole testing range. And its friction force shows a relative apparent increase when the relative humidity is higher than 45%. For Si(100), Z-15, and Z-DOL (BW), the adhesive forces increase with relative humidity. And their coefficients of friction increase with a relative humidity up to 45%, after which they decrease with a further increase in relative humidity. It is also observed that the humidity effect on Si(100) really depends on the history of the Si(100) sample. As the surface of Si(100) wafer readily adsorbs water in air, without any pre-treatment the Si(100) used in our study almost reaches its saturated stage of adsorbed water and is responsible for less effect during increasing relative humidity. However, once the Si(100) wafer was thermally treated by baking at 150 °C for 1 h, a bigger effect was observed.

The schematic (right) in Fig. 33.17 shows that Si(100), because its high free-surface energy, can adsorb more water molecules with increasing relative humidity. As discussed earlier, for the Z-15 film in the humid environment, the condensed water from the humid environment competes with the lubricant film present on the sample surface, and interaction of the liquid lubricant film with the silicon substrate is weakened, and a boundary layer of the liquid lubricant forms puddles. This dewetting allows water molecules to be adsorbed on the Si(100) substrate mixed with Z-15 molecules [33.105, 106]. Obviously, more water molecules can be adsorbed on Z-15 surface while increasing relative humidity. The more adsorbed water molecules in the case of Si(100), along with lubricant molecules in Z-15 film case, form bigger water meniscus, which leads to an increase in friction force, adhesive force, and coefficient of friction of Si(100) and Z-15 with humidity. But at a very high humidity of 70%, large quantities of adsorbed water can form a continuous water layer that separates the tip and sample surface and acts as a kind of lubricant, which causes a decrease in the friction force and coefficient of friction. For Z-DOL (BW) film, because of its hydrophobic surface properties, water molecules can be adsorbed at a humidity higher than 45% and cause an increase in the adhesive and friction forces.

To study the durability of lubricant films at the nanoscale, the friction of Si(100), Z-15, and Z-DOL (BW) as a function of the number of scanning cycles are shown in Fig. 33.18. As observed earlier, friction force and coefficient of friction of Z-15 is higher than that of Si(100) with the lowest values for Z-DOL (BW). During cycling, friction force and coefficient of friction of Si(100) show a slight decrease during the initial few cycles, then remain constant. This is related to the removal of the top adsorbed layer. In the case of Z-15 film, the friction force and coefficient of friction show an increase during the initial few cycles and then approach higher and stable values. This is believed to be caused by the attachment of the Z-15 molecules onto the tip. The molecular interaction between these attached molecules and molecules on the film surface is responsible for an increase in friction. But after several scans, this molecular interaction reaches the equilibrium, and after that, friction force and coefficient of friction remain constant. In the case of Z-DOL (BW) film, the friction force and coefficient of friction start out low and remain low during the entire test for 100 cycles, suggesting that Z-DOL (BW) molecules do not get attached or displaced as readily as Z-15.

33.5.2 Self-Assembled Monolayers (SAMs)

A preferred method of lubrication of MEMS/NEMS is by the deposition of organized and dense molecular-scale layers of long-chain molecules, as they have been shown to be superior lubricants [33.54, 55, 104, 107, 108, 110, 111]. Two common methods of producing monolayers are the Langmuir–Blodgett (L-B) deposition and self-assembled monolayers (SAMs) by chemical grafting of molecules. L-B films are physically bonded to the substrate by weak van der Waals forces, while SAMs are bonded covalently to the substrate and provide high durability.

SAMs can be formed spontaneously by the immersion of an appropriate substrate into a solution of an




H2O
Si(100)
Z-15
Z-15
Z-15
−O−Si−O−
O
Z-DOL
Z-DOL (BW)
0 %
70 %
Increasing relative humidity

Fig. 33.17 The influence of relative humidity on the friction force, adhesive force, and coefficient of friction of Si(100), Z-15, and Z-DOL (BW) films at 70 nN, 2 µm/s, and in 22 °C air. Schematic (*right*) shows the change of meniscus with increasing relative humidity. In this figure, the thermally treated Si(100) represents the Si(100) wafer that was baked at 150 °C for 1 h in an oven (in order to remove the adsorbed water) just before it was placed in the 0% RH chamber [33.103]



Fig. 33.18 Friction force and coefficient of friction versus number of sliding cycles for Si(100) and Z-15 and Z-DOL (BW) films at 70 nN, 0.4 µm/s, and in ambient air. Schematic (*bottom*) shows that some liquid Z-15 molecules can be attached onto the tip. The molecular interaction between the attached molecules with the Z-15 molecules in the film results in an increase of the friction force with multi-scanning [33.103]

active surfactant in an organic solvent. SAMs offer the flexibility and advantage of molecular tailoring to obtain a variety of different tribological and mechanical properties. For example, researchers have shown that by changing the head groups, tail groups, chain lengths, or types of bonds within a chain, varying degrees of friction, adhesion and/or compliance can be obtained (e.g., [33.107, 108]). These studies indicate that the basis for molecular design and tailoring of SAMs must include a complete understanding of the interrelationships between the molecular structure and tribological properties of SAMs, as well as a deep understanding of the friction and wear mechanisms of SAMs at the molecular level.

Bhushan and *Liu* [33.107] and *Liu* and *Bhushan* [33.108] studied nanotribological properties of four different kinds of alkylthiol and biphenyl thiol monolayers with different surface terminals, spacer chains, and head groups using AFM/FFM techniques. These monolayers, along with a schematic of their structures and substrates, are listed in Fig. 33.19. Surface roughness, adhesion, and microscale friction studies were carried out using an AFM/FFM. The average values and standard deviation of the adhesive force and coefficient of microscale friction for the various SAMs are summarized in Fig. 33.20. It shows that SAMs can reduce the adhesive and friction forces. Alkylthiol and biphenyl thiol SAMs can be used as effective molecular lubricants for MEMS/NEMS fabricated from silicon. In order to explain the frictional differences in SAMs, a molecular spring model is presented in Fig. 33.21. It is suggested that the chemically adsorbed self-assembled molecules on a substrate are just like assembled molecular springs anchored to the substrate. An AFM tip sliding on the surface of a SAM is like a tip sliding on the top of "molecular springs or brush." The molecular assembly has compliant features and can experience orientation and compression under load. The orientation of the molecular springs under normal load reduces the shearing force at the interface, which, in turn, reduces the friction force. The possibility of orientation is determined by the spring constant of a single molecule (local stiffness), as well as the interaction between the neighboring molecules, which is reflected by the packing density or packing energy. It is noted that HDT exhibits the lowest adhesive and friction forces. Based on local stiffness measurements [33.108] and the view of molecular structures, biphenyl is a more rigid structure due to the contribution by two benzene rings. Therefore, the spring constant of BPT is larger than that of HDT. A more compliant film (HDT) exhibits lower friction force than a rigid film (BPT/BPTC).


Hexadecane thiol
(HDT)
CH3
CH3
Alkyl
–(CH2)n–
S
S
Au(111)
1,1'–biphenyl–4–thiol
(BPT)
Biphenyl
–(C6H6)2–
S
S
Au(111)
Cross-linked 1,1'–
biphenyl–4–thiol
(BPTC)
S
S
S
S
Au(111)
4,4'–dihydroxybiphenyl
(DHBp)
OH
OH
O
O
Si(111)

Fig. 33.19 Structure of SAMs studied using AFM/FFM techniques



Fig. 33.20 Adhesive force and coefficient of friction values for the various SAMs studied


α_1
α_2
Substrate

Fig. 33.21 Molecular spring model of SAMs. In this figure, $\alpha_1 < \alpha_2$, which is caused by the further orientation under the normal load applied by an asperity tip [33.107]

Crosslinking of chains in BPTC resulted in higher coefficient of friction. It should be noted that the orientation can lead to conformational defects along the molecular chains that lead to energy dissipation.

The influence of relative humidity on adhesion and friction was studied in an environmentally controlled chamber. The results are given in Fig. 33.22, which show that for Si(111), Au(111), and DHBp, the adhesive and frictional forces increase with relative humidity. For BPT and BPTC (cross-linked BPT), the adhesive forces slightly increase with relative humidity when the relative humidity is higher than 40%, but it is very interesting that their coefficients of friction decrease slightly in the same range. For HDT, over the testing range, the adhesive and friction force do not seem to be sensitive to the change in relative humidity. The influence of relative humidity on adhesive and frictional forces can be mainly understood by comparing their surface terminal polarization properties and work of adhesion. Meniscus forces are related linearly to the works of adhesion of a surface, which in



Fig. 33.22 The influence of relative humidity on the adhesive and friction forces at 200 nN of various SAMs studied [33.107]



Fig. 33.23 Wear depth as a function of normal load for various SAMs [33.107]

the case of SAMs, is dependent on the surface terminals. Polar surface terminals such as DHBp on Si(111) result in higher work of adhesion and hence higher adhesive forces. Larger adhesive forces result in higher friction forces. Nonpolar surface terminals (HDT) have very small work of adhesion and hence low adhesive and friction forces. In higher humidity, water capillary condensation can either increase friction through increased adhesion in the contact zone, or reduce friction through an enhanced water-lubricating effect.

Figure 33.23 shows results of microscale wear tests on SAMs using a diamond tip in an AFM. DHBp on Si(111) shows the best wear resistance. For the SAMs deposited on gold substrate, HDT exhibits the best wear resistance. Scratch tests corroborated the wear results. The wear resistance of SAMs is influenced by the interfacial bond strength, the molecular structure of the spacers, and the substrate hardness. Based on the wear data, the SAMs with high-compliance long carbon chains, in addition to low friction, exhibit the best wear resistance [33.107, 108]. In wear experiments, the wear depth as a function of normal load curves shows critical normal load (Fig. 33.23). Below the critical normal load, SAMs undergo orientation. At the critical load, SAMs wear away from the substrate due to weak interfacial bond strength, while above the critical normal load, severe wear takes place on the substrate, Fig. 33.24.

According to these results, it is suggested that a dual SAM with a compliant layer on a stiff layer, deposited on hydrogenated silicon, may have optimized tribological performance for MEMS/NEMS applications.

33.5.3 Hard Diamond-like Carbon (DLC) Coatings

Hard amorphous carbon (a-C), commonly known as DLC (implying high hardness), coatings are deposited by a variety of deposition techniques including



Fig. 33.24 Illustration of the wear mechanism of SAMs with increasing normal load [33.108]

filtered cathodic arc, ion beam, electron cyclotron resonance chemical vapor deposition (ECR-CVD), plasma-enhanced chemical vapor deposition (PECVD), and sputtering [33.83, 99]. These coatings are used in a wide range of applications, including tribological, optical, electronic, and biomedical applications. Ultrathin coatings (3.5 to 10 nm thick) are employed to protect against wear and corrosion in magnetic storage applications (thin-film rigid disks, metal evaporated tapes) and thin-film read/write head (Gillette Mach 3 razor blades, glass windows, and sunglasses). The coatings exhibit low friction, high hardness and wear resistance, chemical inertness to both acids and alkalis, lack of magnetic response, and optical band gap ranging from zero to a few eV, depending on the deposition technique and its conditions. Selected data on DLC coatings relevant for MEMS/NEMS applications are presented in a following section on adhesion measurements.

33.6 Component-Level Studies

33.6.1 Surface Roughness Studies of Micromotor Components

Most of the friction forces resisting motion in the micromotor are concentrated near the rotor-hub interface, where continuous physical contact occurs. Surface roughness of the surfaces usually has a strong influence on the friction characteristics on the micro/nanoscale. A catalog of roughness measurements on various components of a MEMS device does not exist in the literature. Using an AFM, measurements on various component surfaces was made for the first time by *Sundararajan* and *Bhushan* [33.112].

Table 33.6 shows various surface roughness parameters obtained from 5×5 μm scans of the various component surfaces of several unlubricated micromotors using the AFM in tapping mode. A surface with a Gaussian height distribution should have a skewness of zero and kurtosis of three. Although the rotor and stator top surfaces exhibit comparable roughness pa-

Table 33.6 Surface roughness parameters and microscale coefficient of friction for various micromotor component surfaces measured using an AFM. Mean and $\pm 1\sigma$ values are given

	RMS roughness[a] (nm)	Peak-to-valley distance[a] (nm)	Skewness[a], Sk	Kurtosis[a], K	Coefficient of microscale friction[b] μ
Rotor topside	21 ± 0.6	225 ± 23	1.4 ± 0.30	6.1 ± 1.7	0.07 ± 0.02
Rotor underside	14 ± 2.4	80 ± 11	−1.0 ± 0.22	3.5 ± 0.50	0.11 ± 0.03
Stator topside	19 ± 1	246 ± 21	1.4 ± 0.50	6.6 ± 1.5	0.08 ± 0.01

[a] Measured from a tapping mode AFM scan of size 5 μm × 5 μm using a standard Si tip scanning at 5 μm/s in a direction orthogonal to the long axis of the cantilever

[b] Measured using an AFM in contact mode at 5 μm × 5 μm scan size using a standard Si_3N_4 tip scanning at 10 μm/s in a direction parallel to the long axis of the cantilever

rameters, the underside of the rotors exhibits lower RMS roughness and peak-to-valley distance values. More importantly, the rotor underside shows negative skewness and lower kurtosis than the topsides both of which are conducive to high real area of contact and hence high friction [33.54, 55]. The rotor underside also exhibits higher coefficient of microscale friction than the rotor topside and stator, as shown in Table 33.6. Figure 33.25 shows representative surface height maps of the various surfaces of a micromotor measured using the AFM in tapping mode. The rotor underside exhibits varying topography from the outer edge to the middle and inner edge. At the outer edges, the topography shows smaller circular asperities, similar to the topside. The middle and inner regions show deep pits with fine edges that may have been created by the etchants used for etching the sacrificial layer. It is known that etching can affect the surface roughness of surfaces in surface micromachining. The residence time of the etchant near the inner region is high, responsible for larger pits. Figure 33.26 shows roughness of the surface directly beneath the rotors (the base polysilicon layer). There appears to be a difference in the roughness between the portion of this surface that was initially underneath the rotor (region B) during fabrication and the portion that was away from the rotor and hence always exposed (region A). The former region shows lower roughness than the latter region. This suggests that the surfaces at the rotor-hub interface that come into contact at the end of the fabrication process exhibit large real areas of contact that result in high friction.



Fig. 33.25 Representative AFM surface height images obtained in tapping mode (5 µm × 5 µm scan size) of various component surfaces of a micromotor. RMS roughness and peak-to-valley (P-V) values of the surfaces are given. The underside of the rotor exhibits drastically different topography from the topside [33.112]



Fig. 33.26 Surface height images of polysilicon regions directly below the rotor. Region A is away from the rotor, while region B was initially covered by the rotor prior to the release etch of the rotor. During this step, slight movement of the rotor caused region B to be exposed [33.112]

33.6.2 Adhesion Measurements

Surface force apparatus (SFA) and AFMs are used to measure adhesion between two surfaces on micro- to nanoscales. In the SFA, the adhesion of liquid films sandwiched between two curved and smooth surfaces is measured. In an AFM, as discussed earlier, adhesion between a sharp tip and the surface of interest is measured. To measure adhesion between two beams in the mesoscopic length scale, a cantilever beam array (CBA) technique is used [33.113, 115–117]. The technique utilizes an array of micromachined polysilicon beams (for Si MEMS applications) anchored to the substrate at one end and with different lengths parallel to the surface. It relies on the peeling and detachment of cantilever beams. Change in free energy, or reversible work done to separate unit areas of two surfaces from contact is called work of adhesion. To measure the work of adhesion, electrostatic actuation is used to bring all beams in contact with the substrate, Fig. 33.27 [33.113, 117]. Once the actuation force is removed, the beams begin to peel themselves off the substrate, which can be observed with an optical interference microscope. For beams shorter than a characteristic length, the so-called detachment length, their stiffness is sufficient to completely free them from the substrate underneath. Beams larger than the detachment length remain adhered. The beams at the transition region start to detach and remain attached to the substrate just at the tips. For this case, by equating the elastic energy stored within the beam and the beam-substrate interfacial energy, the work of adhesion, W_{ad}, can be calculated by the following equation [33.117]:

$$W_{\mathrm{ad}} = \frac{3Ed^2t^3}{8l_{\mathrm{d}}^4}\,, \tag{33.1}$$

where E is the Young's modulus of the beam, d is the spacing between the undeflected beam and the substrate, t is the beam thickness, and l_{d} is the detachment length. The technique has been used to screen methods for adhesion reduction in polysilicon microstructures.



Fig. 33.27 SEM micrograph of a micromachined array of polysilicon cantilever beams of increasing length. The micrograph shows the onset of pinning for beams longer than 34 µm [33.113]

To measure adhesion, friction, and wear between two microcomponents, a microtriboapparatus has been used. Figure 33.28 shows a schematic of a microtriboapparatus capable of adopting MEMS components [33.114]. In this apparatus, an upper specimen mounted on a soft cantilever beam comes in contact with a lower specimen mounted on a lower specimen holder. The apparatus consists of two piezos (x- and z-piezos), and four fiber optic sensors (x- and z-displacement sensors, and x- and z-force sensors). For adhesion and friction studies, z- and x-piezos are used to bring the upper and lower specimens in contact and to apply a relative motion in the lateral direction, respectively. The x- and z-displacement sensors are used to measure the lateral position of the



Fig. 33.28 Schematic of the microtriboapparatus, including specially designed cantilever (with two perpendicular mirrors attached on the end), lower specimen holder, two piezos (x- and z-piezos), and four fiber optic sensors (x- and z-displacement sensors and x- and z-force sensors) [33.114]

lower specimen and vertical position of the upper specimen, respectively. The x- and z-force sensors are used to measure friction force and normal load/adhesive force between these two specimens, respectively, by monitoring the deflection of the cantilever.

As most of the MEMS/NEMS devices are fabricated from silicon, the study of silicon-on-silicon contacts is important. This contact was simulated by a flat single-crystal Si(100) wafer (phosphorus doped) specimen sliding against a single crystal Si(100) ball (1 mm in diameter, 5×10^{17} atoms/cm^3 boron doped) mounted on a stainless steel cantilever [33.114, 118]. Both of them have a native oxide layer on their surfaces. The other materials studied were 10-nm-thick DLC deposited by filtered cathodic arc deposition on Si(100), 2.3-nm-thick chemically bonded PFPE (Z-DOL, BW) on Si(100), and hexadecane thiol (HDT) monolayer on evaporated Au(111) film to investigate their anti-adhesion performance.

It is well-known that in the computer rigid disk drives, the adhesive force increases rapidly with an increase in rest time between a magnetic head and a magnetic disk [33.35]. Considering that adhesion and friction are the major issues that lead to the failure of MEMS/NEMS devices, the rest time effect on microscale on Si(100), DLC, PFPE, and HDT was studied, and the results are summarized in Fig. 33.29a. It is found that the adhesive force of Si(100) increases logarithmically with the rest time to a certain equilibrium time ($t = 1{,}000$ s), after which it remains constant. Figure 33.29a also shows that the adhesive force of DLC, PFPE, and HDT does not change with rest time. Single-asperity contact modeling of the dependence of meniscus force on the rest time has been carried out by *Chilamakuri* and *Bhushan* [33.119], and the modeling results (Fig. 33.29b) verify experimental observations. Due to the presence of thin film adsorbed water on Si(100), meniscus forms around the contacting asperities and grows with time until equilibrium occurs, which causes the rest time effect on its adhesive force. The adhesive forces of DLC, PFPE, and HDT do not change with rest time, which suggests that either water meniscus is not present on their surfaces, or it does not increase with time.

The measured adhesive forces of Si(100), DLC, PFPE, and HDT at rest time of 1 s are summarized in Fig. 33.30. It shows that the presence of solid films of DLC, PFPE, and HDT greatly reduces the adhesive force of Si(100), whereas HDT film has the lowest adhesive force. It is well-known that the native oxide layer (SiO_2) on the top of Si(100) wafer exhibits hydrophilic properties, and water molecules produced by capillary condensation of water vapor from the environment can be adsorbed easily on this surface. The condensed water will form meniscus as the upper specimen approaches the lower specimen surface. The meniscus force is a major contributor to the adhesive force. In the case of DLC, PFPE, and HDT, the films are found to be hydrophobic based on contact angle measurements, and the amount of condensed water vapor is low compared to that on Si(100). It should be noted that the measured adhesive force is generally higher than that measured in AFM,



Fig. 33.29 **(a)** The influence of rest time on the adhesive force of Si(100), DLC, chemically bonded PFPE, and HDT, and **(b)** single asperity contact modeling results of the rest time effect on the meniscus force for an asperity of R in contact with a flat surface with a water-film thickness of h_0 and absolute viscosity of η_0 [33.119]



Fig. 33.30 Adhesive forces of Si(100), DLC, chemically bonded PFPE, and HDT at ambient conditions and a schematic showing the relative size of water meniscus on different specimens

because the larger radius of the Si(100) ball compared to that of an AFM tip induces larger meniscus and van der Waals forces.

To investigate the velocity effect on friction, the friction force as a function of velocity was measured and is summarized in Fig. 33.31a. It indicates that for Si(100) the friction force initially decreases with increasing velocity until equilibrium occurs. Figure 33.31a also indicates that the velocity almost has no effect on the friction properties of DLC, PFPE, and HDT. This implies that the friction mechanisms of DLC, PFPE, and HDT do not change with the variation in velocity. For Si(100), at high velocity, the meniscus is broken and does not have enough time to rebuild. In addition, it is believed that tribochemical reaction plays an important role. The high velocity leads to tribochemical reactions of Si(100), which has native oxide SiO_2, with water molecules to form a $Si(OH)_4$ film. This film is removed and continuously replenished during sliding. The $Si(OH)_4$ layer at the sliding surface is known to be of low shear strength. The breaking of the water meniscus and the formation of a $Si(OH)_4$ layer result in a decrease in friction force of Si(100). For DLC, PFPE, and HDT, surfaces exhibit hydrophobic properties and can only adsorb a few water molecules in ambient conditions. The above mentioned meniscus breaking and tribochemical reaction mechanisms do not exist for these films. Therefore, their friction force does not change with velocity.

The influence of relative humidity was studied in an environmentally controlled chamber. The adhesive and friction forces were measured at increasing relative humidity, and the results are summarized in Fig. 33.31b. The figure shows that for Si(100), the adhesive force increases with relative humidity, but the adhesive forces of DLC and PFPE only show slight increases when humidity is higher than 45%, while the adhesive force of HDT does not change with humidity. Figure 33.31b also shows that for Si(100), the friction force increases with a relative humidity increase up to 45%, and then it shows a slight decrease with a further increase in the relative humidity. For PFPE, there is an increase in the friction force when humidity is higher than 45%. In the whole testing range, relative humidity does not have any apparent influence on the friction properties of DLC and HDT. In the case of Si(100), the initial increase of relative humidity up to 45% causes more adsorbed water molecules and forms bigger water meniscus, which leads to an increase of friction force. But at a very high humidity of 65%, large quantities of adsorbed water can form a continuous water layer that separates the tip and sample surfaces and acts as a kind of lubricant, which causes a decrease in the friction force. For PFPE, dewetting of lubricant film at humidity larger than 45% results in an increase in the adhesive and friction forces. DLC and HDT surfaces show hydrophobic properties, and increasing relative humidity does not play much of a role in their friction forces.

The influence of temperature was studied using a heated stage. The adhesive force and friction force were measured at increasing temperatures from 22 °C to 125 °C. The results are presented in Fig. 33.31c. It shows that once the temperature is higher than 50 °C, increasing temperature causes a significant decrease in adhesive and friction forces of Si(100) and a slight decrease in the cases of DLC and PFPE. But the adhesion and friction forces of HDT do not show any apparent change with test temperature. At high temperature, desorption of water, and reduction of surface tension of water lead to the decrease of adhesive and friction forces of Si(100), DLC, and PFPE. However, in the case of HDT film, as only a few water molecules are adsorbed on the surface, the above mentioned mechanisms do not play a big role. Therefore, the adhesive and friction forces of HDT do not show any apparent change with temperature. Figure 33.31 shows that in the whole ve-



Fig. 33.31a–c The influence of **(a)** sliding velocity on the friction forces, **(b)** relative humidity on the adhesive and friction forces, and **(c)** temperature on the adhesive and friction forces of Si(100), DLC, chemically bonded PFPE, and HDT

locity, relative humidity, and temperature test range, the adhesive forces and friction forces of DLC, PFPE, and HDT are always smaller than that of Si(100), whereas HDT has the smallest value.

To summarize, several methods can be used to reduce adhesion in microstructures. MEMS surfaces can be coated with hydrophobic coatings such as PFPEs, SAMs, and passivated DLC coatings. It should be noted that other methods to reduce adhesion include the formation of dimples on the contact surfaces to reduce contact area [33.10, 54, 55, 116, 117]. Furthermore, an increase in hydrophobicity of the solid surfaces (high contact angle approaching 180°) can be achieved by using surfaces with suitable roughness, in addition to lowering their surface energy [33.120, 121]. The hydrophobicity of surfaces is dependent on a subtle interplay between surface chemistry and mesoscopic topography. The self-cleaning mechanism, or so-called "Lotus-effect", is closely related to the ultra-hydrophobic properties of these biological surfaces, which usually show micro-sculptures in specific dimensions.

33.6.3 Static Friction Force (Stiction) Measurements in MEMS

In MEMS devices involving parts in relative motion to each other, such as micromotors, large friction forces become the limiting factor to their successful operation and reliability. It is generally known that most micromotors cannot be rotated as manufactured and require some form of lubrication. It is therefore critical to determine the friction forces present in such MEMS devices. To measure in situ the static friction of a rotor-bearing interface in a micromotor, *Tai* and *Muller* [33.122] measured the starting torque (voltage) and pausing position for different starting positions under a constant-bias voltage. A friction-torque model was used to obtain the coefficient of static friction. To measure the in situ kinetic friction of the turbine and gear structures, *Gabriel* et al. [33.123] used a laser-based measurement system to monitor the steady-state spins and decelerations. *Lim* et al. [33.124] designed and fabricated a polysilicon microstructure to in situ measure the static friction of various films. The microstructure consisted of a shuttle suspended above the underlying electrode by a folded beam suspension. A known normal force was applied, and lateral force was measured to obtain the coefficient of static friction. *Beerschwinger* et al. developed a cantilever-deflection rig to measure friction of LIGA-processed micromotors [33.125, 126]. Table 33.7 presents static friction coefficients of various MEMS devices evaluated by various researchers. Most of these techniques employ indirect methods to determine the friction forces, or involve fabrication of complex structures.



Fig. 33.32 **(a)** Schematic of the technique used to measure the force, F_s, required to initiate rotor movement using an AFM/FFM. **(b)** As the tip is pushed against the rotor, the lateral deflection experienced by the rotor due to the twisting of the tip prior to rotor movement is a measure of static friction force, F_s, of the rotors. **(c)** Schematic of lateral deflection expected from the above mentioned experiment. The peak V_f is related to the state of the rotor [33.112]

A novel technique to measure the static friction force (stiction) encountered in surface micromachined polysilicon micromotors using an AFM has been developed by *Sundararajan* and *Bhushan* [33.112]. Continuous physical contact occurs during rotor movement (rotation) in the micromotors between the rotor and lower hub flange. In addition, contact occurs at other locations between the rotor and the hub surfaces and between the rotor and the stator. Friction forces will be present at these contact regions during motor operation. Although the actual distribution of these forces is not known, they can be expected to be concentrated near the hub, where there is continuous contact. If we, therefore, represent the static friction force of the micromotor as a single force F_s acting at point P_1 (as shown in Fig. 33.32a), then the magnitude of the frictional torque about the center of the motor (O) that must be overcome before rotor movement can be initiated is:

$$T_s = F_s l_1 \,, \tag{33.2}$$

where l_1 is the distance OP_1, which is assumed to be the average distance from the center at which the friction force F_s occurs. Now consider an AFM tip moving against a rotor arm in a direction perpendicular to the long axis of the cantilever beam (the rotor arm edge closest to the tip is parallel to the long axis of the cantilever beam), as shown in Fig. 33.32a. When the tip encounters the rotor at point P_2, the tip will twist, generating a lateral force between the tip and the rotor (event A in Fig. 33.32b). This reaction force will generate a torque about the center of the motor. Since the tip is trying to move farther in the direction shown, the tip will continue to twist to a maximum value at which the lateral force between the tip and the rotor becomes high enough such that the resultant torque T_f about the center of the motor equals the static friction torque T_s. At this point, the ro-

Table 33.7 Published data on coefficient of static friction measurements of MEMS devices and structures

Reference	Test method	Device/structure	Material pairs	Environment	Coefficient of static friction
[33.122]	Starting voltage	IC-processed micromotor	PolySi/Si_3N_4	Air	0.20–0.40
[33.124]	Electrostatic loading	Comb-drive microstructure	PolySi/PolySi PolySi/Si_3N_4	Air	4.9 ± 1.0 2.5 ± 0.5
[33.127]	Pull-off force	Silicon microbeams	SiO_2/SiO_2	Air	2.1 ± 0.8
[33.126]	Cantilever/fiber deflection rig	LIGA micromotors	Ni/Alumina	Air	0.6–1.2

Fig. 33.33 Static friction force values of unlubricated motors and motors lubricated using PFPE lubricants, normalized over the rotor weight, as a function of rest time and relative humidity. Rest time is defined as the time elapsed between a given experiment and the first experiment in which motor movement was recorded (time 0). The motors were allowed to sit at a particular humidity for 12 h prior to measurements [33.112]



tor will begin to rotate, and the twist of the cantilever decreases sharply (event B in Fig. 33.32b). The twist of the cantilever is measured in the AFM as a change in the lateral deflection signal (in volts), which is the underlying concept of friction force microscopy (FFM). The change in the lateral deflection signal corresponding to the above mentioned events as the tip approaches the rotor is shown schematically in Fig. 33.32b. The value of the peak V_f is a measure of the force exerted on the rotor by the tip just before the static friction torque is matched and the rotor begins to rotate.

Using this technique, the viability of PFPE lubricants for micromotors has been investigated and the effect of humidity on the friction forces of unlubricated and lubricated devices was studied as well. Figure 33.33 shows static friction forces normalized over the weight of the rotor of unlubricated and lubricated micromotors as a function of rest time and relative humidity. Rest time here is defined as the time elapsed between the first experiment conducted on a given motor (solid symbol at time zero) and subsequent experiments (open symbols). Each open symbol data point is an average of six measurements. It can be seen that for the unlubricated motor and the motor lubricated with a bonded layer of Z-DOL (BW), the static friction force is highest for the first experiment and then drops to an almost constant level. In the case of the motor with an as-is mobile layer of Z-DOL, the values remain very high up to 10 days after lubrication. In all cases, there is negligible difference in the static friction force at 0% and 45% RH. At 70% RH, the unlubricated motor exhibits a substantial increase in the static friction force, while the motor with bonded Z-DOL shows no increase in static friction force due to the hydrophobicity of the lubricant layer. The motor with an as-is mobile layer of the lubricant shows consistently high values of static friction force that vary little with humidity.

33.6.4 Mechanisms Associated with Observed Stiction Phenomena in Micromotors

Figure 33.34 summarizes static friction force data for two motors, M1 and M2, along with schematics of the meniscus effects for the unlubricated and lubricated surfaces. Capillary condensation of water vapor from the environment results in the formation of meniscus bridges between contacting and near-contacting asperities of two surfaces in close proximity to each other, as shown in Fig. 33.34. For unlubricated surfaces, more menisci are formed at higher humidity, resulting in a higher friction force between the surfaces. The formation of meniscus bridges is supported by the fact that the static friction force for unlubricated motors increases at high humidity (Fig. 33.34). Solid bridging may occur near the rotor-hub interface due to silica residues after the first etching process. In addition, the drying process after the final etch can result in liquid bridging formed by the drying liquid due to meniscus force at these areas [33.54,55,113,116]. The initial static friction force therefore will be quite high, as evidenced by the solid data points in Fig. 33.34. Once the first movement of the rotor permanently breaks these solid and liquid bridges, the static friction force of the motors will drop (as seen in Fig. 33.34) to a value dictated predominantly by the adhesive energies of rotor and hub surfaces, the real area of contact between these surfaces and meniscus forces due to water vapor in the air, at which point, the effect of lubricant films can be observed. Lubrication with a mobile layer, even a thin one, results in very high static friction forces



Fig. 33.34 Summary of effect of liquid and solid lubricants on static friction force of micromotors. Despite the hydrophobicity of the lubricant used (Z-DOL), a mobile liquid lubricant (Z-DOL as is) leads to very high static friction force due to increased meniscus forces, whereas a solid-like lubricant (bonded Z-DOL, BW) appears to provide some amount of reduction in static friction force

due to meniscus effects of the lubricant liquid itself at and near the contact regions. It should be noted that a motor submerged in a liquid lubricant would result in a fully flooded lubrication regime. In this case, there is no meniscus contribution and only the viscous contribution to the friction forces would be relevant. However, submerging the device in a lubricant may not be a practical method. A solid-like hydrophobic lubricant layer (such as bonded Z-DOL) results in favorable friction characteristics of the motor. The hydrophobic nature of the lubricant inhibits meniscus formation between the contact surfaces and maintains low friction even at high humidity (Fig. 33.34). This suggests that solid-like hydrophobic lubricants are ideal for lubrication of MEMS, while mobile lubricants result in increased values of static friction force.

References

33.1 NASA Ames Research Center, Mottett Field, CA, USA, http://www.ipt.arc.nasa.gov/gallery.html

33.2 W. G. van der Wiel, S. De Franceschi, J. M. Elzerman, T. Fujisawa, S. Tarucha, L. P. Kouwenhoven: Electron transport through double quantum dots, Rev. Mod. Phys. **75** (2003) 1–22

33.3 Texas Instruments DLP Products, Plano, TX, USA, http://www.dlp.com

33.4 Anonymous: *Microelectromechanical Systems: Advanced Materials and Fabrication Methods* (National Academy Press, Washington, D.C. 1997)

33.5 M. Roukes: Nanoelectromechanical systems face the future, Phys. World (February 2001) 25–31

33.6 M. A. Huff: A distributed MEMS processing environment, http://www.mems-exchange.org/ (2002)

33.7 R. S. Muller, R. T. Howe, S. D. Senturia, R. L. Smith, R. M. White: *Microsensors* (IEEE, New York 1990)

33.8 I. Fujimasa: *Micromachines: A New Era in Mechanical Engineering* (Oxford Univ. Press, Oxford 1996)

33.9 W. S. Trimmer (Ed.): *Micromachines and MEMS: Classic and Seminal Papers to 1990* (IEEE, New York 1997)

33.10 B. Bhushan (Ed.): *Tribology Issues and Opportunities in MEMS* (Kluwer, Dordrecht 1998)

33.11 G. T. A. Kovacs: *Micromachined Transducers Sourcebook* (WCB McGraw-Hill, Boston 1998)

33.12 S. D. Senturia: *Microsystem Design* (Kluwer, Boston 2001)

33.13 M. Gad-el-Hak: *The MEMS Handbook* (CRC, Boca Raton 2002)

33.14 T. R. Hsu: *MEMS and Microsystems* (McGraw-Hill, Boston 2002)

33.15 M. Madou: *Fundamentals of Microfabrication: The Science of Miniaturization*, 2nd edn. (CRC, Boca Raton 2002)

33.16 R. C. Jaeger: *Introduction to Microelectronic Fabrication*, 5th edn. (Addison-Wesley, Reading 1988)

33.17 J. W. Judy: Microelectromechanical systems (MEMS): Fabrication, design, and applications, Smart Mater. Struct. **10** (2001) 1115–1134

33.18 E. W. Becker, W. Ehrfeld, P. Hagmann, A. Maner, D. Munchmeyer: Fabrication of microstructures with high aspect ratios and great structural heights by synchrotron radiation lithography, galvanoforming, and plastic moulding (LIGA process), Microelectron. Eng. **4** (1986) 35–56

33.19 C. R. Friedrich, R. O. Warrington: Surface characterization of non-lithographic micromachining. In: *Tribology Issues and Opportunities in MEMS*, ed. by B. Bhushan (Kluwer, Dordrecht 1998) pp. 73–84

33.20 M. Madou: Facilitating choices of machining tools and materials for miniaturization science: A review. In: *Tribology Issues and Opportunities in MEMS*, ed. by B. Bhushan (Kluwer, Dordrecht 1998) pp. 31–51

33.21 H. Lehr, S. Abel, J. Doppler, W. Ehrfeld, B. Hagemann, K. P. Kamper, F. Michel, Ch. Schulz, Ch. Thurigen: Microactuators as driving units for microrobotic systems, SPIE Proc. Microrobotics: Components and Applications **2906** (1996) 202–210

33.22 H. Lehr, W. Ehrfeld, B. Hagemann, K. P. Kamper, F. Michel, Ch. Schulz, Ch. Thurigen: Development of micro-millimotors, Min. Invas. Ther. Allied Technol. **6** (1997) 191–194

33.23 F. Michel, W. Ehrfeld: Microfabrication technologies for high performance microactuators. In: *Tribology Issues and Opportunities in MEMS*, ed. by B. Bhushan (Kluwer, Dordrecht 1998) pp. 53–72

33.24 M. Tanaka: Development of desktop machining microfactory, Riken Rev. **34** (2001) 46–49

33.25 Y. Xia, G. M. Whitesides: Soft lithography, Angew. Chem. Int. Edn. **37** (1998) 550–575

33.26 H. Becker, C. Gaertner: Polymer microfabrication methods for microfluidic analytical applications, Electrophoresis **21** (2000) 12–26

33.27 Y. Xia, E. Kim, X. M. Zhao, J. A. Rogers, M. Prentiss, G. M. Whitesides: Complex optical surfaces formed by replica molding against elastomeric masters, Science **273** (1996) 347–349

33.28 S. Y. Chou, P. R. Krauss, P. J. Renstrom: Imprint lithography with 25-nanometer resolution, Science **272** (1996) 85–87

33.29 A. Kumar, G. M. Whitesides: Features of gold having micrometer to centimeter dimensions can be formed through a combination of stamping with an elastomeric stamp and an alkanethiol ink followed by chemical etching, Appl. Phys. Lett. **63** (1993) 2002–2004

33.30 T. A. Core, W. K. Tsang, S. J. Sherman: Fabrication technology for an integrated surface-micromachined sensor, Solid State Technol. **36** (1993) 39–47

33.31 J. Bryzek, K. Peterson, W. McCulley: Micromachines on the march, IEEE Spectrum (May 1994) 20–31

33.32 L. J. Hornbeck, W. E. Nelson: Bistable deformable mirror device. In: *OSA Technical Digest Series, Vol. 8, Spatial Light Modulators and Applications* (OSA, Washington 1988) pp. 107–110

33.33 L. J. Hornbeck: A digital light processing(tm) update – Status and future applications, Proc. SPIE **3634** (1999) 158–170

33.34 L. J. Hornbeck: The DMD^{TM} projection display chip: A MEMS-based technology, MRS Bull. **26** (2001) 325–328

33.35 B. Bhushan: *Tribology and Mechanics of Magnetic Storage Devices*, 2nd edn. (Springer, New York 1996)

33.36 H. Hamilton: Contact recording on perpendicular rigid media, J. Mag. Soc. Jpn. **15** (1991) (Suppl. S2) 483–481

33.37 T. Ohwe, Y. Mizoshita, S. Yonoeka: Development of integrated suspension system for a nanoslider with an MR head transducer, IEEE Trans. Magn. **29** (1993) 3924–3926

33.38 L. S. Fan, S. Woodman: Batch fabrication of mechanical platforms for high-density data storage, 8th Int. Conf. Solid State Sensors and Actuators (Transducers '95)/Eurosensors IX, Stockholm 1995, 434–437

33.39 D. A. Horsley, M. B. Cohn, A. Singh, R. Horowitz, A. P. Pisano: Design and fabrication of an angular microactuator for magnetic disk drives, J. Microelectromech. Syst. **7** (1998) 141–148

33.40 T. Hirano, L. S. Fan, D. Kercher, S. Pattanaik, T. S. Pan: HDD tracking microactuator and its integration issues, Proc. ASME **2** 2000, ed. by A. P. Lee, J. Simon, F. K. Foster, R. S. Keynton (ASME, New York 2000) 449–452

33.41 P. Gravesen, J. Branebjerg, O. S. Jensen: Microfluidics – A review, J. Micromech. Microeng. **3** (1993) 168–182

33.42 C. Lai Poh San, E. P. H. Yap (Eds.): *Frontiers in Human Genetics* (World Scientific, Singapore 2001)

33.43 C. H. Mastrangelo, H. Becker (Eds.): Microfluidics and BioMEMS, Proc. SPIE **4560** (2001)

33.44 H. Becker, L. E. Locascio: Polymer microfluidic devices, Talanta **56** (2002) 267–287

33.45 S. Shoji, M. Esashi: Microflow devices and systems, J. Micromech. Microeng. **4** (1994) 157–171

33.46 P. Woias: Micropumps – Summarizing the first two decades, *Proc. SPIE – Microfluidics and BioMEMS*, ed. by C. H. Mastrangelo, H. Becker, Proc. SPIE **4560** (2001) 39–52

33.47 M. Scott: MEMS and MOEMS for national security applications, *Reliability, Testing, and Characterization of MEMS/MOEMS II*, Proc. SPIE **4980** (2003) 37–44

33.48 K. E. Drexler: *Nanosystems: Molecular Machinery, Manufacturing and Computation* (Wiley, New York 1992)

33.49 B. Bhushan: *Handbook of Micro/Nanotribology*, 2nd edn. (CRC, Boca Raton 1999)

33.50 G. Timp (Ed.): *Nanotechnology* (Springer, New York 1999)

33.51 E. A. Rietman: *Molecular Engineering of Nanosystems* (Springer, New York 2001)

33.52 H. S. Nalwa (Ed.): *Nanostructured Materials and Nanotechnology* (Academic, San Diego 2002)

33.53 W. A. Goddard, D. W. Brenner, S. E. Lyshevski, G. J. Iafrate: *Handbook of Nanoscience, Engineering, and Technology* (CRC, Boca Raton 2003)

33.54 B. Bhushan: *Principles and Applications of Tribology* (Wiley, New York 1999)

33.55 B. Bhushan: *Introduction to Tribology* (Wiley, New York 2002)

33.56 Y. C. Tai, L. S. Fan, R. S. Muller: IC-processed micromotors: Design, technology and testing, Proc. IEEE Micro Electro Mechanical Systems 1989, 1–6

33.57 S. M. Spearing, K. S. Chen: Micro-gas turbine engine materials and structures, Ceramic Eng. Sci. Proc. **18** (2001) 11–18

33.58 M. Mehregany, K. J. Gabriel, W. S. N. Trimmer: Integrated fabrication of polysilicon mechanisms, IEEE Trans. Electron. Dev. **35** (1988) 719–723

33.59 E. J. Garcia, J. J. Sniegowski: Surface micromachined microengine, Sens. Actuators A **48** (1995) 203–214

33.60 J. K. Robertson, K. D. Wise: An electrostatically actuated integrated microflow controller, Sens. Actuators A **71** (1998) 98–106

33.61 B. Bhushan: Nanotribology and nanomechanics of MEMS devices, Proc. Ninth Annual Workshop on Micro Electro Mechanical Systems 1996 (IEEE, New York 1996) 91–98

33.62 D. M. Tanner, N. F. Smith, L. W. Irwin et al.: *MEMS Reliability: Infrastructure, Test Structures, Experiments, and Failure Modes* (Sandia National Laboratories, Albuquerque 2000) 2000–2091

33.63 S. S. Mani, J. G. Fleming, J. A. Walraven, J. J. Sniegowski et al.: Effect of W coating on microengine performance, Proc. 38th Annual Inter. Reliability Phys. Symp. 2000 (IEEE, New York 2000) 146–151

33.64 R. E. Sulouff: MEMS opportunities in accelerometers and gyros and the microtribology problems limiting commercialization. In: *Tribology Issues and Opportunities in MEMS*, ed. by B. Bhushan (Kluwer, Dordrecht 1998) pp. 109–120

33.65 Analog Devices Inc., Berkeley, CA, USA, http://www.analog.com

33.66 S. A. Henck: Lubrication of digital micromirror devices, Tribol. Lett. **3** (1997) 239–247

33.67 M. R. Douglass: Lifetime estimates and unique failure mechanisms of the digital micromirror devices (DMD), Proc. 36th Annual Inter. Reliability Phys. Symp. 1998 (IEEE, New York 1998) 9–16

33.68 M. R. Douglass: DMD reliability: A MEMS success story, Reliability, Testing, and Characterization of MEMS/MOEMS II, Proc. SPIE **4980** (2003) 1–11

33.69 W. C. Tang, A. P. Lee: Defense applications of MEMS, MRS Bull. **26** (2001) 318–319. Also see www.darpa.mil/mto/mems

33.70 H. Guckel, D. W. Burns: Fabrication of micromechanical devices from polysilicon films with smooth surfaces, Sens. Actuators **20** (1989) 117–122

33.71 G. T. Mulhern, D. S. Soane, R. T. Howe: Supercritical carbon dioxide drying of microstructures, Proc. Int. Conf. on Solid-State Sensors and Actuators 1993 (IEEE, New York 1993) 269–299

33.72 P. Vettiger, J. Brugger, M. Despont, U. Drechsler, U. Duerig, W. Haeberle: Ultrahigh density, high data-rate NEMS based AFM data storage system, Microelectron. Eng. **46** (1999) 11–27, also see http://www.ibm.com

33.73 M. Ferrari, J. Liu: The engineered course of treatment, Mech. Eng. (December 2001) 44–47

33.74 F. J. Martin, C. Grove: Microfabricated drug delivery systems: Concepts to improve clinical benefits, Biomed. Microdev. **3** (2001) 97–108

33.75 K. F. Man, B. H. Stark, R. Ramesham: *A Resource Handbook for MEMS Reliability*, Rev. A (California Institute of Technology, Pasadena 1998)

33.76 S. Kayali, R. Lawton, B. H. Stark: MEMS reliability assurance activities at JPL, EEE Links **5** (1999) 10–13

33.77 S. Arney: Designing for MEMS reliability, MRS Bull. **26** (2001) 296–299

33.78 K. F. Man: MEMS reliability for space applications by elimination of potential failure modes through testing and analysis (2001), http://www.rel.jpl.nasa.gov/Org/5053/atop/products/Prod-map.html

33.79 B. Bhushan, A. V. Kulkarni, W. Bonin, J. T. Wyrobek: Nano/picoindentation measurement using a capacitance transducer system in atomic force microscopy, Philos. Mag. **74** (1996) 1117–1128

33.80 S. Sundararajan, B. Bhushan: Development of AFM-based techniques to measure mechanical properties of nanoscale structures, Sens. Actuators A **101** (2002) 338–351

33.81 B. Bhushan (Ed.): *Modern Tribology Handbook* (CRC, Boca Raton 2001)

33.82 B. Bhushan, J. N. Israelachvili, U. Landman: Nanotribology: Friction, wear and lubrication at the atomic scale, Nature **374** (1995) 607–616

33.83 J. S. Shor, D. Goldstein, A. D. Kurtz: Characterization of n-type β-SiC as a piezoresistor, IEEE Trans. Electron. Dev. **40** (1993) 1093–1099

33.84 M. Mehregany, C. A. Zorman, N. Rajan, C. H. Wu: Silicon carbide MEMS for harsh environments, Proc. IEEE **86** (1998) 1594–1610

33.85 C. A. Zorman, A. J. Fleischmann, A. S. Dewa, M. Mehregany, C. Jacob, S. Nishino, P. Pirouz: Epitaxial growth of 3C-SiC films on 4 in. diam Si(100) silicon wafers by atmospheric pressure chemical vapor deposition, J. Appl. Phys. **78** (1995) 5136–5138

33.86 C. A. Zorman, S. Roy, C. H. Wu, A. J. Fleischman, M. Mehregany: Characterization of polycrystalline silicon carbide films grown by atmospheric pressure chemical vapor deposition on polycrystalline silicon, J. Mater. Res. **13** (1998) 406–412

33.87 B. Bhushan, B. K. Gupta: *Handbook of Tribology: Materials, Coatings and Surface Treatments* (Krieger, Malabar 1997) Reprint

33.88 J. F. Shackelford, W. Alexander, J. S. Park (Eds.): *CRC Material Science and Engineering Handbook*, 2nd edn. (CRC, Boca Raton 1994)
33.89 B. K. Gupta, J. Chevallier, B. Bhushan: Tribology of ion bombarded silicon for micromechanical applications, ASME J. Tribol. **115** (1993) 392–399
33.90 B. K. Gupta, B. Bhushan, J. Chevallier: Modification of tribological properties of silicon by boron ion implantation, Tribol. Trans. **37** (1994) 601–607
33.91 B. K. Gupta, B. Bhushan: Nanoindentation studies of ion implanted silicon, Surf. Coat. Technol. **68-69** (1994) 564–570
33.92 B. Bhushan, V. N. Koinkar: Tribological studies of silicon for magnetic recording applications, J. Appl. Phys. **75** (1994) 5741–5746
33.93 G. M. Pharr: The anomalous behavior of silicon during nanoindentation. In: *Thin Films: Stresses and Mechanical Properties III*, Vol. 239, ed. by W. D. Nix, J. C. Bravman, E. Arzt, L. B. Freund (Materials Research Soc., Pittsburgh 1991) pp. 301–312
33.94 D. L. Callahan, J. C. Morris: The extent of phase transformation in silicon hardness indentation, J. Mater. Res. **7** (1992) 1612–1617
33.95 N. A. Fleck, G. M. Muller, M. F. Ashby, J. W. Hutchinson: Strain gradient plasticity: Theory and experiment, Acta Metall. Mater. **42** (1994) 475–487
33.96 B. Bhushan, S. Venkatesan: Friction and wear studies of silicon in sliding contact with thin-film magnetic rigid disks, J. Mater. Res. **8** (1993) 1611–1628
33.97 S. Venkatesan, B. Bhushan: The role of environment in the friction and wear of single-crystal silicon in sliding contact with thin-film magnetic rigid disks, Adv. Info Storage Syst. **5** (1993) 241–257
33.98 S. Venkatesan, B. Bhushan: The sliding friction and wear behavior of single-crystal, polycrystalline and oxidized silicon, Wear **171** (1994) 25–32
33.99 B. Bhushan: Chemical, mechanical, and tribological characterization of ultra-thin and hard amorphous carbon coatings as thin as 3.5 nm: Recent developments, Diam. Relat. Mater. **8** (1999) 1985–2015
33.100 S. Sundararajan, B. Bhushan: Micro/nanotribological studies of polysilicon and SiC films for MEMS applications, Wear **217** (1998) 251–261
33.101 X. Li, B. Bhushan: Micro/nanomechanical characterization of ceramic films for microdevices, Thin Solid Films **340** (1999) 210–217
33.102 A. A. Yasseen, C. H. Wu, C. A. Zorman, M. Mehregany: Fabrication and testing of surface micromachined polycrystalline SiC micromotors, IEEE Electron. Dev. Lett. **21** (2000) 164–166
33.103 H. Liu, B. Bhushan: Nanotribological characterization of molecularly-thick lubricant films for applications to MEMS/NEMS by AFM, Ultramicroscopy **97** (2003) 321–340
33.104 B. Bhushan, A. V. Kulkarni, V. N. Koinkar, M. Boehm, L. Odoni, C. Martelet, M. Belin: Microtribological characterization of self-assembled and Langmuir–Blodgett monolayers by atomic force and friction force microscopy, Langmuir **11** (1995) 3189–3198
33.105 V. N. Koinkar, B. Bhushan: Micro/nanoscale studies of boundary layers of liquid lubricants for magnetic disks, J. Appl. Phys. **79** (1996) 8071–8075
33.106 V. N. Koinkar, B. Bhushan: Microtribological studies of unlubricated and lubricated surfaces using atomic force/friction force microscopy, J. Vac. Sci. Technol. A **14** (1996) 2378–2391
33.107 B. Bhushan, H. Liu: Nanotribological properties and mechanisms of alkylthiol and biphenyl thiol self-assembled monolayers studied by AFM, Phys. Rev. B **63** (2001) 245412:1–11
33.108 H. Liu, B. Bhushan: Investigation of nanotribological properties of self-assembled monolayers with alkyl and biphenyl spacer chains, Ultramicroscopy **91** (2002) 185–202
33.109 T. Stifter, O. Marti, B. Bhushan: Theoretical investigation of the distance dependence of capillary and van der Waals forces in scanning force microscopy, Phys. Rev. B **62** (2000) 13667–13673
33.110 B. Bhushan: Self-assembled monolayers for controlling hydrophobicity and/or friction and wear. In: *Modern Tribology Handbook*, ed. by B. Bhushan (CRC, Boca Raton 2001) pp. 909–929
33.111 H. Liu, B. Bhushan, W. Eck, V. Stadler: Investigation of the adhesion, friction, and wear properties of biphenyl thiol self-assembled monolayers by atomic force microscopy, J. Vac. Sci. Technol. A **19** (2001) 1234–1240
33.112 S. Sundararajan, B. Bhushan: Static friction and surface roughness studies of surface micromachined electrostatic micromotors using an atomic force/friction force microscope, J. Vac. Sci. Technol. A **19** (2001) 1777–1785
33.113 C. H. Mastrangelo, C. H. Hsu: Mechanical stability and adhesion of microstructures under capillary forces – Part II: Experiments, J. Microelectromech. Syst. **2** (1993) 44–55
33.114 H. Liu, B. Bhushan: Adhesion and friction studies of microelectromechanical systems/nanoelectromechanical systems materials using a novel microtriboapparatus, J. Vac. Sci. Technol. A **21** (2003) 1528–1538
33.115 M. P. De Boer, T. A. Michalske: Accurate method for determining adhesion of cantilever beams, J. Appl. Phys. **86** (1999) 817
33.116 R. Maboudian, R. T. Howe: Critical review: Adhesion in surface micromechanical structures, J. Vac. Sci. Technol. B **15** (1997) 1–20
33.117 C. H. Mastrangelo: Surface force induced failures in microelectromechanical systems. In: *Tribology Issues and Opportunities in MEMS*, ed. by B. Bhushan (Kluwer, Dordrecht 1998) pp. 367–395
33.118 B. Bhushan, H. Liu, S. M. Hsu: Adhesion and friction studies of silicon and hydrophobic and low fric-

tion films and investigation of scale effects, ASME J. Tribol. in press

33.119 S. K. Chilamakuri, B. Bhushan: A comprehensive kinetic meniscus model for prediction of long-term static friction, J. Appl. Phys. **15** (1999) 4649–4656

33.120 J. Kijlstra, K. Reihs, A. Klamt: Roughness and topology of ultra-hydrophobic surfaces, Colloids Surf. A **206** (2002) 521–529

33.121 D. Quere, P. Aussillous: Non-stick droplets, Chem. Eng. Technol. **25** (2002) 925–928

33.122 Y. C. Tai, R. S. Muller: Frictional study of IC processed micromotors, Sens. Actuators A **21–23** (1990) 180–183

33.123 K. J. Gabriel, F. Behi, R. Mahadevan, M. Mehregany: In situ friction and wear measurement in integrated polysilicon mechanisms, Sens. Actuators A **21–23** (1990) 184–188

33.124 M. G. Lim, J. C. Chang, D. P. Schultz, R. T. Howe, R. M. White: Polysilicon microstructures to characterize static friction, Proc. IEEE Micro Electro Mechanical Systems (IEEE, New York 1990) 82–88

33.125 U. Beerschwinger, S. J. Yang, R. L. Reuben, M. R. Taghizadeh, U. Wallrabe: Friction measurements on LIGA-processed microstructures, J. Micromech. Microeng. **4** (1994) 14–24

33.126 D. Matheison, U. Beerschwinger, S. J. Young, R. L. Rueben, M. Taghizadeh, S. Eckert, U. Wallrabe: Effect of progressive wear on the friction characteristics of nickel LIGA processed rotors, Wear **192** (1996) 199–207

33.127 R. Maboudian: Adhesion and friction issues associated with reliable operation of MEMS, MRS Bull. (June 1998) 47–51

34. Mechanical Properties of Micromachined Structures

To be able to accurately design structures and make reliability predictions, in any field it is necessary first to know the mechanical properties of the materials that make up the structural components. In the fields of microelectromechanical systems (MEMS) and nanoelectromechanical systems (NEMS), the devices are necessarily very small. The processing techniques and microstructures of the materials in these devices may differ significantly from bulk structures. Also, the surface-area-to-volume ratio in these structures is much higher than in bulk samples, and so the surface properties become much more important. In short, it cannot be assumed that mechanical properties measured using bulk specimens will apply to the same materials when used in MEMS and NEMS. This chapter will review the techniques that have been used to determine the mechanical properties of micromachined structures, especially residual stress, strength, and Young's modulus. The experimental measurements that have been performed will then be summarized, in particular the values obtained for polycrystalline silicon (polysilicon).

34.1 Measuring Mechanical Properties of Films on Substrates 1023
34.1.1 Residual Stress Measurements 1023
34.1.2 Mechanical Measurements Using Nanoindentation 1024

34.2 Micromachined Structures for Measuring Mechanical Properties 1024
34.2.1 Passive Structures 1025
34.2.2 Active Structures 1028

34.3 Measurements of Mechanical Properties . 1034
34.3.1 Mechanical Properties of Polysilicon 1034
34.3.2 Mechanical Properties of Other Materials 1036

References 1037

34.1 Measuring Mechanical Properties of Films on Substrates

In order to determine accurately the mechanical properties of very small structures, it is necessary to test specimens made from the same materials, processed in the same way, and of the same approximate size. Not surprisingly it is often difficult to handle specimens this small. One solution is to test the properties of films remaining on substrates. Micro- and nanomachined structures are typically fabricated from films that are initially deposited onto a substrate, are subsequently patterned and etched into the appropriate shapes, and then finally released from the substrate. If the testing is performed on the continuous film, before patterning and release, the substrate can be used as an effective "handle" for the specimen (in this case, the film). Of course since the films are adhered to the substrate, the types of tests possible are severely limited.

34.1.1 Residual Stress Measurements

One common measurement easily performed on films attached to substrates is residual film stress. The curvature of the substrate is measured before and after film deposition. Curvature can be measured in a number of ways. The most common technique is to scan a laser across the surface (or scan the substrate beneath the laser) and detect the angle of the reflected signal. Alternatively, profilometry, optical interferometry, or even atomic force microscopy can be used. As expected, tools that map a surface or perform multiple linear scans can give more accurate readings than tools that measure only a single scan.

Assuming that the film is thin compared to the substrate, the average residual stress in the film, σ_f, is given

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

by the Stoney equation,

$$\sigma_{\mathrm{f}} = \frac{1}{6}\frac{E_{\mathrm{s}}}{(1-\nu_{\mathrm{s}})}\frac{t_{\mathrm{s}}^{2}}{t_{\mathrm{f}}}\left(\frac{1}{R_1}-\frac{1}{R_2}\right) , \qquad (34.1)$$

where the subscripts f and s refer to the film and substrate, respectively; t is thickness, E is Young's modulus, ν is Poisson's ratio, and R is radius of curvature before (R_1) and after (R_2) film deposition [34.2]. For the typical (100)-oriented silicon substrate, $E/(1-\nu)$ (also known as the biaxial modulus) is equal to 180.5 GPa, independent of in-plane rotation [34.3]. This investigation can be performed on the as-deposited film or after any subsequent annealing step, provided no changes occur to the substrate.

This measurement will reveal the average residual stress of the film. Typically, however, the residual stresses of deposited films will vary through the film thickness. One way to detect this, using substrate curvature techniques, is to etch away a fraction of the film and repeat the curvature measurement. This can be iterated any number of times to obtain a residual stress profile for the film [34.4]. Alternatively, tools have been designed to measure the substrate curvature during the deposition process itself, to obtain information on how the stresses evolve [34.5].

An additional feature of some of these tools is the ability to heat the substrates while performing the stress measurement. An example of the results obtained in such an experiment is shown in Fig. 34.1 [34.1], for an aluminum film on a silicon substrate. The slope of the heating curve gives the difference in thermal expansion between the film and the substrate. When the heating curve changes slope and becomes nearly horizontal, the yield strength of the film has been reached.

34.1.2 Mechanical Measurements Using Nanoindentation

Aside from residual stress, it is difficult to measure mechanical properties of films adhered to substrates without the measurement being affected by the presence of the substrate. Recent developments in nanoindentation equipment have allowed this technique to be used in some cases. With specially designed tools, indentation can be performed using very low loads. If the films being investigated are thick and rigid enough, measurements can be made that are not influenced by the presence of the substrate. Of course, this can be verified by depositing the same film onto different substrates. By continuously monitoring the displacement as well as the load during indentation, a variety of properties can be measured, including hardness and Young's modulus [34.6]. This area is covered in more detail in a separate chapter.



Fig. 34.1 Typical results for residual stress as a function of temperature for an aluminum film on a silicon substrate [34.1]. The stresses were determined by measuring the curvature of the substrate before and after film deposition, using the reflected signal of a laser scanned across the substrate surface

For brittle materials, cracks can be generated by indentation, and strength information can be gathered. But the exact stress fields created during the indentation process are not exactly known, and, therefore, quantitative values for strength are difficult to determine. Anisotropic etching of single crystal silicon has been done to create 30-μm-tall structures that were then indented to examine fracture toughness [34.7], however this is not possible with most materials.

34.2 Micromachined Structures for Measuring Mechanical Properties

Certainly the most direct way to measure the mechanical properties of small structures is to fabricate structures that would be conducive to such tests. Fabrication techniques are sufficiently advanced that virtually any design can be realized, at least in two dimensions. Two basic types of devices are used for mechanical property testing: "passive" structures and "active" structures.

34.2.1 Passive Structures

As mentioned previously, the main difficulty in testing very small specimens is in handling. One way to circumvent this problem is by using passive structures. These structures are designed to act as soon as they are released from the substrate and to provide whatever information they are designed to supply without further manipulation. For all of these passive structures, the forces acting on them come from the structural materials' own internal residual stresses. For devices on the micron scale or smaller, gravitational forces can be neglected, and therefore internal stresses are the only source of actuation force.

Stress Measurements

Since the internal residual stresses act upon the passive devices when they are released, it is natural to design a device that can be used to measure residual stresses. One such device, a rotating microstrain gauge, is shown in Fig. 34.2. There are many different microstrain gauge designs, but all operate under the same principle. In Fig. 34.2a, the large pads, labeled A, will remain anchored to the substrate when the rest of the device is released. Upon release, the device will expand or contract in order to relieve its internal residual stresses. A structure under tension will contract, and a structure under compression will expand. For the structure in Fig. 34.2, a compressive stress will cause the legs to lengthen. Since the two opposing legs are not attached to the central beam at the same point but are offset, they will cause the central beam to rotate when they expand. The device in Fig. 34.2 contains two independent gauges that point to one another. At the ends of the two central beams are two parts of a Vernier scale. By observing this scale, one can measure the rotation of the beams.

If the connections between the legs and the central beams were simple pin connections, the strain, ε, of the legs (the fraction of expansion or contraction) could be determined simply by the measured rotation and the geometry of the device, namely

$$\varepsilon = \frac{d_{\text{beam}} d_{\text{offset}}}{2 L_{\text{central}} L_{\text{leg}}} , \qquad (34.2)$$

where d_{beam} is the lateral deflection of the end of one central beam, d_{offset} is the distance between the connections of the opposing legs, L_{central} is the length of the central beam (measured to the center point between the leg connections), and L_{leg} is the length of the leg. But since the entire device was fabricated from a single polysilicon film, this cannot be the case; there must be some bending occurring at the connections. As a result, to get an accurate determination of the strain relieved upon release, finite element analysis (FEA) of the struc-



Fig. 34.2 **(a)** Microstrain gauge fabricated from polysilicon. **(b)** shows a close-up of the Vernier scale before release, and **(c)** shows the same area after release

ture must be performed. This is a common situation for microdevices. FEA is a powerful tool in determining the displacements and stresses of nonideal geometries. One drawback is that Young's modulus of the material must be known in order to do the FEA as well as to convert the measured strain into a stress value. But Young's moduli for many micromachined materials are known or can be measured using other techniques.

Other devices, besides rotating strain gauges, are designed to measure residual stresses. One of the most simple is a doubly clamped beam, a long, narrow beam of constant width and thickness that is anchored to the substrate at both ends. If the beam contains a tensile stress, it will remain straight. But if the beam contains a compressive stress, it will buckle if its length exceeds a critical value, l_{cr}, according to the Euler buckling criterion [34.8],

$$\varepsilon_{\mathrm{r}} = -\frac{\pi^2}{3}\left(\frac{h}{l_{\mathrm{cr}}}\right)^2 , \tag{34.3}$$

where ε_{r} is the residual strain in the beam, and h is the width or thickness of the beam, whichever is less. To determine the residual strain, a series of doubly clamped beams are fabricated of varying lengths. In this way, the critical length, l_{cr}, for buckling can be deduced after release. One problem with this technique is that during the release process, any turbulence in the solution will lead to enhanced buckling of beams, and a low value for l_{cr} will be obtained.

For films with tensile stresses, a similar analysis can be done using ring-and-beam structures, also called Guckel rings after their inventor, Henry Guckel. A schematic of this design is shown in Fig. 34.3 [34.8]. A tensile stress in the outer ring will cause it to contract. This will lead to a compressive stress in the central beam, even though the material was originally tensile before release. The amount of compression in the central beam can be determined analytically from the geometry of the device and the residual strain of the material. Again, by changing the length of the central beam, the l_{cr} will be determined, and then the residual strain can be deduced.

Stress Gradient Measurements

For structures fabricated from thin deposited films, the stress gradient can be just as important as the stress itself. Figure 34.4 shows a portion of a silicon microactuator. The device is designed to be completely planar; however, stress gradients in the film cause the structures to bend. This figure illustrates the importance of characterizing and controlling stress gradients, and it also demonstrates that the easiest structure for measuring stress gradients is a simple cantilever beam. By measuring the end deflection δ, of a cantilever beam of length l, and thickness t, the stress gradient, $\mathrm{d}\sigma/\mathrm{d}t$ is determined by [34.9]

$$\frac{\mathrm{d}\sigma}{\mathrm{d}t} = \frac{2\delta}{l^2}\frac{E}{1-\nu} . \tag{34.4}$$

The magnitude of the end deflection can be measured by microscopy, optical interferometry, or any other technique.

Another useful structure for measuring stress gradients is a spiral. For this structure, the end of the spiral not anchored to the substrate will move out-of-plane. Also



Fig. 34.3a,b Schematic **(a)** top view and **(b)** side view of Guckel ring structures [34.8]. The *dashed lines* in **(a)** indicate the anchors



Fig. 34.4 Scanning electron micrograph (SEM) of a portion of a silicon microactuator. Residual stress gradients in the silicon cause the structure to bend

the diameter of the spiral will contract, and the free end of the spiral will rotate when released [34.10].

Strength and Fracture Toughness Measurements

As mentioned above, if a doubly clamped beam contains a tensile stress, it will remain taut when released because it cannot relieve any of its stress by contracting. This tensile stress can be thought of as a tensile load being applied at the ends of the beam. If this tensile load exceeds the tensile strength of the material, the beam will break. Since the tensile stress can be measured, as discussed in the Sect. 34.2.1, this technique can be used to gather information on the strength of materials. Figure 34.5 shows two different beam designs that have been used to measure strength. The device shown in Fig. 34.5a was fabricated from a tensile polysilicon film [34.11]. Different beams were designed with varying lengths of the wider regions (marked l_1 in the figure). In this manner, the load applied to the narrow center beam was varied, even though the entire film contained a uniform residual tensile stress. For l_1 greater than a critical value, the narrow center beam fractured, giving a measurement for the tensile strength of polysilicon.

The design shown in Fig. 34.5b was fabricated from a tensile Si_xN_y film [34.12]. As seen in the figure, a stress concentration was designed into the beam, to ensure the fracture strength would be exceeded. In this case, a notch was etched into one side of the beam. Since the stress concentration is not symmetric with regard to the beam axis, this results in a large bending moment at that position, and the test measures the bend strength of the material. Again, like the beams shown in Fig. 34.5a, the geometry of various beams fabricated from the same film were varied, to vary the maximum stress seen at the notch. By seeing which beams fracture at the stress concentration after release, the strength can be determined.

Through a similar technique but by using an atomically sharp pre-crack instead of a stress concentration, the fracture toughness of a material can be determined. Sharp pre-cracks can be introduced into micromachined structures before release by placing a Vickers indent on the substrate, near the device; the radial crack formed by the indent will propagate into the overlying structure [34.14]. Accordingly, the beam with a sharp pre-crack, shown in Fig. 34.6, was fabricated using polysilicon [34.13]. Due to the stochastic nature of indentation, the initial pre-crack length will vary from beam to beam. Because of this, even though the geometry of the beams remains identical, the stress intensity, K, at the pre-crack tip will vary. Upon release, only those pre-cracks whose K exceeds the fracture toughness of the material, K_{Ic}, will propagate, and in this way upper and lower bounds for K_{Ic} for the material can be determined.

For all of the beams discussed in this section, finite element analysis is required to determine the stress concentrations and stress intensities. Even though approximate analytical solutions may exist for these designs, the actual fabricated structure will not have idealized geometries. For example, corners will never be perfectly sharp, and cracks will never be perfectly straight. This



Fig. 34.5a,b Schematic designs of doubly clamped beams with stress concentrations for measuring strength. **(a)** was fabricated from polysilicon [34.11], and **(b)** was fabricated from Si_xN_y [34.12]



Fig. 34.6 **(a)** SEM of a 500 µm long polysilicon beam with a Vickers indent placed near its center; **(b)** higher magnification SEM of the area near the indent showing the pre-crack traveling from the substrate into the beam [34.13]

reinforces the idea that FEA is a powerful tool in determining mechanical properties of very small structures.

34.2.2 Active Structures

As discussed above, it is very convenient to design structures that act upon release to provide information on the mechanical properties of the structural materials. This is not always possible, however. For example, those passive devices just discussed rely on residual stresses to create the changes (rotation or fracture) that occur upon release, but many materials do not contain high residual stresses as deposited, or the processing scheme of the device precludes the generation of residual stresses. Also, some mechanical properties, such as fatigue resistance, require motion in order to be studied. Active devices are therefore used. These are acted upon by a force (the source of this force can be integrated into the device itself or can be external to the device) in order to create a change, and by the response to the force, the mechanical properties are studied.

Young's Modulus Measurements

Young's modulus, E, is a material property critical to any structural device design. It describes the elastic response of a material and relates stress, σ, and strain, ε, by

$$\sigma = E\varepsilon \,. \tag{34.5}$$

In bulk samples, E is often measured by loading a specimen in tension and measuring displacement as a function of stress for a given length. While this is considerably more difficult for small structures, such as those fabricated from thin deposited films, it can be achieved with careful experimental techniques. Figure 34.7 shows the schematic of one such measurement system [34.15]. The fringe detectors in the figure detect the reflected laser signal from two gold lines deposited onto the polysilicon specimen, which act as gage markers. In this manner, the strain in the specimen during loading can be monitored. Besides gold lines, Vickers indents placed in a nickel specimen can also serve as gage markers [34.16], or a speckle interferometry technique [34.17] can be used to determine strain in the specimen. Once the stress-versus-strain behavior is measured, the slope of the curve is equal to E.



Fig. 34.7 Schematic of a measurement system for tensile loading of micromachined specimens [34.15]

In addition to the tensile test, Young's modulus can be determined by other measures of stress-strain behavior. As seen in Fig. 34.8, a cantilever beam can be bent by pushing on the free end with a nanoindenter [34.18]. The nanoindenter can monitor the force applied and the displacement, and simple beam theory can convert the displacement into strain to obtain E. A similar technique, shown schematically in Fig. 34.9 [34.19], involves pulling downward on a cantilever beam by means of an electrostatic force. An electrode is fabricated into the substrate beneath the cantilever beam, and a voltage is applied between the beam and the bottom electrode. The force acting on the beam is equal to the electrostatic force corrected to include the effects of fringing fields acting on the sides of the beam, namely

$$F(x) = \frac{\varepsilon_0}{2}\left(\frac{V}{g+z(x)}\right)^2\left(1+\frac{0.65[g+z(x)]}{w}\right) , \tag{34.6}$$

where $F(x)$ is the electrostatic force at x, ε_0 is the dielectric constant of air, g is the gap between the beam and the bottom electrode, $z(x)$ is the out-of-plane deflection of the beam, w is the beam width, and V is the applied voltage [34.19]. In this work, the deflection of the beam as a function of position is measured using optical interferometry. These measurements combine to give stress-strain behavior for the cantilever beam. An extension of this technique uses doubly clamped beams instead of cantilever beams. In this case, the deflection of the beam at a given electrostatic force depends on the residual stress in the material as well as Young's modulus. This method can also be used, therefore, to measure residual stresses in doubly clamped beams.

Another device possible to fabricate from a thin film and also possible to use for investigating stress-strain behavior is a suspended membrane, seen in Fig. 34.10 [34.20]. As shown in the schematic figure, the membrane is exposed to an elevated pressure on one side, causing it to bulge in the opposite direction. The deflection of the membrane is measured by optical or other techniques and related to the strain in the mem-



Fig. 34.8 Schematic of a nanoindenter loading mechanism pushing on the end of a cantilever beam [34.18]



Fig. 34.9 Schematic of a cantilever beam bending test using an electrostatic voltage to pull the beam toward the substrate [34.19]



Fig. 34.10 Schematic cross section of a microfabricated membrane [34.20]

brane. These membranes can be fabricated in any shape, typically square or circular. Both analytical solutions and finite element analyses have been done to relate the deflection to the strain. Like the doubly clamped beams, both Young's modulus and residual stress play a role in the deflected shape. Both of these mechanical properties can therefore be determined by the pressure-versus-deflection performance of the membrane.

Another measurement besides stress-strain behavior that can reveal Young's modulus of a material is the determination of the natural resonance frequency. For a cantilever, the resonance frequency, f_r, for free undamped vibration is given by

$$f_\mathrm{r} = \frac{\lambda_i^2 t}{4\pi l^2} \left(\frac{E}{3\rho} \right)^{1/2} , \tag{34.7}$$

where ρ, l, and t are density, length, and thickness of the cantilever; λ_i is the eigenvalue, where i is an integer that describes the resonance mode number; for the first mode $\lambda_1 = 1.875$ [34.22]. By measuring f_r and knowing the geometry and density, therefore, E can be determined. The cantilever can be vibrated by a number of techniques, including a laser, loudspeaker, or piezoelectric shaker. The frequency that produces the highest amplitude of vibration is the resonance frequency.

A micromachined device that uses an electrostatic comb drive and an AC signal to generate the vibration of the structure is known as a lateral resonator [34.23]. One example is shown in Fig. 34.11 [34.21]. When a voltage is applied across either set of interdigitated comb fingers shown in Fig. 34.11, an electrostatic attraction will be generated due to the increase in capacitance as the overlap between the comb fingers increases. The force,



Fig. 34.11 SEM of a polysilicon lateral resonator [34.21]

F, generated by the comb drive is given by

$$F = \frac{1}{2}\frac{\partial C}{\partial x}V^2 = n\varepsilon\frac{h}{g}V^2 , \qquad (34.8)$$

where C is capacitance, x is distance traveled by one comb-drive toward the other, n is the number of pairs of comb fingers in one drive, ε is the permittivity of the fluid between the fingers, h is the height of the fingers, g is the gap spacing between the fingers, and V is the applied voltage [34.23]. When an AC voltage at the resonance frequency is applied across either of the two comb drives, the central portion of the device will vibrate. In fact, since force depends on the square of the voltage for electrostatic actuation, for a time, t, dependent drive voltage, $v_\mathrm{D}(t)$, of

$$v_\mathrm{D}(t) = V_\mathrm{P} + v_\mathrm{d}\sin(\omega t) , \qquad (34.9)$$

where V_P is the DC bias and v_d is the AC drive amplitude, the time dependent portion of the force will scale with

$$2\omega V_\mathrm{P} v_\mathrm{d}\cos(\omega t) + \omega v_\mathrm{d}^2\sin(2\omega t) \qquad (34.10)$$

[34.23]. Therefore, if an AC drive signal is used with no DC bias, at resonance, the frequency of the AC drive signal will be one half the resonance frequency. For this device, the resonance frequency, f_r, will be

$$f_\mathrm{r} = \frac{1}{2\pi}\left(\frac{k_\mathrm{sys}}{M}\right)^{1/2} , \qquad (34.11)$$

where k_sys is the spring constant of the support beams and M is the mass of the portion of the device that vibrates. The spring constant is given by

$$k_\mathrm{sys} = 24EI/L^3 , \qquad (34.12)$$

$$I = \frac{hw^3}{12} , \qquad (34.13)$$

where I is the moment of inertia of the beams, and L, h, and w are the length, thickness, and width of the beams. By combining these equations and measuring f_r, therefore, E can be determined.

One distinct advantage of the lateral resonator technique and the electrostatically pulled cantilever technique for measuring Young's modulus is that they require no external loading sources. Portions of the devices are electrically contacted, and a voltage is applied. For the pure tension tests, such as shown in Fig. 34.7, the specimen must be attached to a loading system, which for the very small specimens discussed here, can be extremely difficult, and any misalignment or eccentricity in the test could lead to unreliable results. But the advantage of the externally loaded technique is that there are no limitations on the type of materials that can be tested. Conductivity is not a requirement, nor is any compatibility with electrical actuation.

Strength and Fracture Toughness Measurements

As one might expect, any of the techniques discussed in the previous section that strain specimens in order to measure Young's modulus can also be used to measure fracture strength. Simply, the load is increased until the specimen breaks. As long as either the load or the strain is measured at fracture, and the geometry of the specimen is known, the maximum stress required for fracture, σ_crit, can be determined, either through analytical analysis or FEA. Depending on the geometry of the test, σ_crit will represent the tensile or bend strength of the material.

If the available force is limited, or if it is desired to have a localized fracture site, stress concentrations can be added to the specimens. These are typically notches micromachined into the edges of specimens.



Fig. 34.12 **(a)** SEM of a device for measuring bend strength of polysilicon beams; **(b)** image of a test in process; **(c)** higher magnification view of one beam shortly before breaking [34.24]

Focused ion beams have also been used to carve stress concentrations into fracture specimens.

All of the external loading schemes, such as those shown in Figs. 34.7 and 34.8, have been used to measure fracture strength. Also, the electrostatically loaded doubly clamped beams can be pulled until they fracture. In this case, there is one complication. The electrostatic force is inversely proportional to the distance between the electrodes, and at a certain voltage, called the "pull-in voltage," the attraction between the beam and the substrate will become so great that the beam will immediately be pulled into contact with the bottom electrode. As long as the fracture takes place before the pull-in voltage is reached, the experiment will give valid results.

Other loading techniques have been used to generate fracture of microspecimens. Figure 34.12 [34.24] shows one device designed to be pushed by the end of a micromanipulated needle. The long beams that extend from the sides of the central shuttle come into contact with anchored posts, and, at a critical degree of bending, the beams will break off. Since the applied force cannot be measured in this technique, the experiment is optically monitored continuously during the test, and the image of the beams just before fracture is analyzed to determine σ_{crit}.

Another loading scheme that has been demonstrated for micromachined specimens utilizes scratch drive actuators to load the specimens [34.25]. These types of actuators work like inchworms, traveling across a substrate in discrete advances as an electrostatic force is repeatedly applied between the actuator and the substrate. The stepping motion can be made in the nm scale, depending on the frequency of the applied voltage, and so it can be an acceptable approximation to continuous loading. One advantage of this scheme is that very large forces can be generated by relatively small devices. The exact forces generated cannot be measured, so like the technique that used micromanipulated pushing, the test is continuously observed to determine the strain at fracture. Another advantage of this technique is that, like the lateral resonator and the electrically pulled cantilever, the loading takes place on-chip, and, therefore, the difficulties associated with attaching and aligning an external loading source are eliminated.

Another on-chip actuator used to load microspecimens is shown in Fig. 34.13, along with three different microspecimens [34.14]. Devices have been fabricated with each of the three microspecimens integrated with the same electrostatic comb-drive actuator. In all three cases, when a DC voltage is applied to the actuator, it moves downward, as oriented in Fig. 34.13. This pulls down on the left end of each of the three microspecimens, which are anchored on the right. The actuator contains 1,486 pairs of comb fingers. The maximum voltage that can be applied is limited by the breakdown



Fig. 34.13 **(a)** SEM of a micromachined device for conducting strength tests; the device consists of a large comb drive electrostatic actuator integrated with a microspecimen; **(b)–(d)** SEMs of various microspecimens for testing bend strength, tensile strength, and fracture toughness, respectively [34.14]

voltage of the medium in which the test takes place. In air, that limits the voltage to less than 200 V. As a result, given a finger height of 4 µm and a gap of 2 µm, and using (34.8), the maximum force generated by this actuator is limited to about 1 mN. Standard optical photolithography has a minimum feature size of about 2 µm. As a result, the electrostatic actuator cannot generate sufficient force to perform a standard tensile test on MEMS structural materials such as polysilicon. The microspecimens shown in Fig. 34.13 are therefore designed such that the stress is amplified.

The specimen shown in Fig. 34.13b is designed to measure bend strength. It contains a micromachined notch with a root radius of 1 µm. When the actuator pulls downward on the left end of this specimen, the notch serve as a stress concentration, and when the stress at the notch root exceeds σ_{crit}, the specimen fractures. The specimen in Fig. 34.13c is designed to test tensile strength. When the left end of this specimen is pulled downward, a tensile stress is generated in the upper thin horizontal beam near the right end of the specimen. As the actuator continues to move downward, the tensile stress in this beam will exceed the tensile strength, causing fracture. Finally, the specimen in Fig. 34.13d is similar to that in Fig. 34.13b, except that the notch is replaced by a sharp pre-crack that was produced by the Vickers indent placed on the substrate near the specimen. When this specimen is loaded, a stress intensity, K, is generated at the crack tip. When the stress intensity exceeds a critical value, K_{Ic}, the crack propagates. K_{Ic} is also referred to as the fracture toughness.

The force generated by the electrostatic actuator can be calculated using (34.8). But (34.8) assumes a perfectly planar, two-dimensional device. In fact, when actuated, the electric fields extend out of the plane of the device, and so (34.8) is just an approximation. Instead, like many of the techniques discussed in this section, the test is continuously monitored, and the actuator displacement at the time of fracture is recorded. Then FEA is used to determine the magnitude of the stress or stress intensity seen by the specimen at the point of fracture.

Fatigue Measurements

A benefit of the electrostatic actuator shown in Fig. 34.13 is that, besides monotonic loading, it can generate cyclic loading. This allows the fatigue resistance of materials to be studied. Simply by using an AC signal instead of a DC voltage, the device can be driven at its resonant frequency. The amplitude of the resonance depends on the magnitude of the AC signal. This amplitude can be increased until the specimen breaks; this will investigate the low-cycle fatigue resistance. Otherwise the amplitude of resonance can be left constant at a level below that is required for fast fracture, and the device will resonate indefinitely until the specimen breaks; this will investigate high-cycle fatigue. It should be noted that the resonance frequency of such a device is about 10 kHz. Therefore, it is possible to stress a specimen over 10^9 cycles in less than a day. In addition to simple cyclic loading, if a DC bias is added to the AC signal, a mean stress can be superimposed on the cyclic load. In this way, nonsymmetric cyclic loading (either with a large tensile stress alternating with a small compressive stress, or vice versa) can be studied.

Another device that can be used to investigate fatigue resistance in MEMS materials is shown in Fig. 34.14 [34.26]. In this case, a large mass is attached to the end of a notched cantilever beam. The mass contains two comb drives on opposite ends. When an AC signal is applied to one comb drive, the device will res-



Fig. 34.14 SEM of a device for investigating fatigue; the image on the right is a higher magnification view of the notch near the base of the moving part of the structure [34.26] (a) mass, b) comb drive actuator, c) capacitive displacement sensor)

onate, cyclically loading the notch. The comb drive on the opposite side is used as a capacitive displacement sensor. This device contains many fewer comb fingers than the device shown in Fig. 34.13. As a result, it can apply cyclic loads by exploiting the resonance frequency of the device but cannot supply sufficient force to achieve monotonic loading.

Fatigue loading has also been studied using the same external loading techniques shown in Fig. 34.7. In this case, the frequency of the cyclic load is considerably lower, since the resonance frequency of the device is not being utilized. This leads to longer high-cycle testing times. Since the force is essentially unlimited, however, this technique allows a variety of frequencies to be studied to determine their effect on the fatigue behavior.



Fig. 34.16 Schematic cross section and top-view optical micrograph of a hinged-cantilever test structure for measuring friction in micromachined devices [34.28]

Friction Measurements

Friction is another property that has been studied in micromachined structures. To study friction, of course, two surfaces must be brought into contact with each other. This is usually avoided at all costs for these devices because of the risk of stiction. (Stiction is the term used when two surfaces that come into contact adhere so strongly that they cannot be separated.) Even so, a few devices have been designed to investigate friction. One of these is shown schematically in Fig. 34.15 [34.27]. It consists of a movable structure with a comb drive on one end and a cantilever beam on the other. Beneath the cantilever, on the substrate, is planar electrode. The device is moved to one side using the comb drive. Then a voltage is applied between the cantilever beam and the substrate electrode. The voltage on the comb drive is then released. The device would normally return to its original position, to relax the deflection in the truss suspensions, but the friction between the cantilever and the substrate electrode holds it in place. The voltage to the substrate electrode is slowly decreased until the device starts to slide. Knowing the electrostatic force generated by the



Fig. 34.15a,b Schematic drawings of a device used to study friction. **(a)** shows top and side views of the device in its original position, and **(b)** shows views of the device after it has been displaced using the comb drive and clamped using the substrate electrode [34.27]

substrate electrode and the stiffness of the truss suspensions, the static friction can be determined. For this device, bumps were fabricated on the bottoms of the cantilever beams. This limited the surface area that came into contact with the substrate and so lowered the risk of stiction.

Another device designed to study friction is shown in Fig. 34.16 [34.28]. This technique uses a hinged cantilever. The portion near the free end acts as the friction test structure, and the portion near the anchored end acts as the driver. The friction test structure is attracted to the substrate by means of electrostatic actuation, and when a second electrostatic actuator pulls down the driver, the friction test structure slips forward by a length proportional to the forces involved, including the frictional force. This distance, however, has a maximum of 30 nm, so all measurements must be exceedingly accurate in order to investigate a range of forces. This test structure can be used to determine the friction coefficients for surfaces with and without lubricating coatings.

34.3 Measurements of Mechanical Properties

All of the techniques discussed in Sects. 34.1 and 34.2 have been used to measure the mechanical properties of MEMS and NEMS materials. As a general rule, the results from the various techniques have agreed well with each other, and the argument becomes which of the measurement techniques is easiest and most reliable to perform. It is crucial to keep in mind, however, that certain properties, such as strength, are process dependent, and so the results taken at one laboratory will not necessarily match those taken from another. This will be discussed in more detail in Sect. 34.3.1.

34.3.1 Mechanical Properties of Polysilicon

In current MEMS technology, the most widely used structural material is polysilicon deposited by low-pressure chemical vapor deposition (LPCVD). One reason for the prevalence of polysilicon is the large body of processing knowledge for this material that has been developed by the integrated circuit community. Another reason, of course, is that polysilicon possesses a number of qualities beneficial for MEMS devices, particularly its high strength and Young's modulus. As a natural result, most of the mechanical properties investigations on MEMS materials have focused on polysilicon.

Residual Stresses in Polysilicon

The residual stresses of LPCVD polysilicon have been thoroughly characterized using both the wafer curvature technique, discussed in Sect. 34.1.1, and the microstrain gauges, discussed in Sect. 34.2.1. The results from both techniques give consistent values. Figure 34.17 summarizes the residual stress measurements as a function of deposition temperature taken from five different investigations at five different laboratories [34.29]. All five sets of data show the same trend. The stresses change from compressive at the lowest deposition temperatures to tensile at intermediate temperatures and back to compressive at the highest temperatures. The exact transition temperatures vary somewhat among the different investigations, probably due to differences in the deposition conditions: the silane or dichlorosilane pressure, the gas flow rate, the geometry of the deposition system, and the temperature uniformity. But in each data set the transitions are easily discernible. The origin of these residual stress changes lies with the microstructure of the LPCVD polysilicon films.

As with all deposited films, the microstructure of LPCVD polysilicon films is dependent on the deposition conditions. In general, the films are amorphous at



Fig. 34.17 Results for residual stress of LPCVD polysilicon films taken from five different investigations [34.29]. The data from each investigation are connected by a line

the lowest growth temperatures (lower than ∼ 570 °C), display fine (∼ 0.1 μm diameter) grains at intermediate temperatures (∼ 570 °C to ∼ 610 °C), and contain columnar (110)-textured grains with a thin fine-grained nucleation layer at the substrate interface at higher temperatures (∼ 610 °C to ∼ 700 °C) [34.29]. The fine-grained microstructure results from the homogeneous nucleation and growth of silicon grains within an as-deposited amorphous silicon film. In this regime, the deposition rate is just slightly faster than the crystallization rate. The as-deposited films will be crystalline near the substrate interface and amorphous at the free surface. (The amorphous fraction can be quickly crystallized by annealing above 610 °C.) The columnar microstructure seen at the higher growth temperatures results from the formation of crystalline silicon films as deposited, with growth being fastest in the ⟨110⟩ directions.

The origin of the tensile stress in the fine-grained polysilicon arises from the volume decrease that accompanies the crystallization of the as-deposited amorphous material. The origins of the compressive stresses in the amorphous and columnar films are less well understood. One proposed explanation for compressive stress generation during thin film growth postulates that an increase in the surface chemical potential is caused by the deposition of atoms from the vapor; the increase in surface chemical potential induces atoms to flow into newly formed grain boundaries, creating a compressive stress in the film [34.30].

Stress gradients are also typical of LPCVD polysilicon films. The partially amorphous films contain large stress gradients since they are essentially bilayers of compressive amorphous silicon on top of tensile fine-grained polysilicon. The fully crystalline films also exhibit stress gradients. The columnar compressive films are most highly stressed at the film-substrate interface, with the compressive stresses decreasing as the film thickness increases; the fine-grained films are less tensile at the film-substrate interface, with the tensile stresses increasing as the film thickness increases [34.29]. Both stress gradients are associated with microstructural variations. For the columnar films, the initial nucleation layer corresponds to a very high compressive stress, which decreases as the columnar morphology develops. For the fine-grained films, the region near the film-substrate interface has a slightly smaller average grain size, due to heterogeneous nucleation at the interface. This region displays a slightly lower tensile stress than the rest of the film, since the increased grain boundary area reduces the local density.

Young's Modulus of Polysilicon

The Young's modulus of polysilicon films has been measured using all the techniques discussed in Sect. 34.2.2. A good review of the experimental results taken from bulge testing, tensile testing, beam bending, and lateral resonators are contained in [34.31]. All of the reported results are in reasonable agreement, varying from 130 to 175 GPa, though many values are reported with a relatively high experimental scatter. The main origin of the error in these results is the uncertainties involving the geometries of the small specimens used to make the measurements. For example, from (34.13), the Young's modulus determined by the lateral resonators depends on the cube of the tether beam width, typically about 2 μm. In general, the beam width and other dimensions can be measured with scanning electron microscopy to within about 0.1 μm; however, the width of the beams is not perfectly constant along the entire length or even through the thickness. These uncertainties in geometry lead to uncertainties in modulus.

In addition, the various experimental measurements lie close to the Voigt and Reuss bounds for Young's modulus calculated using the elastic stiffnesses and compliances for single crystal silicon [34.31]. This strongly implies that Young's modulus of micro- and nanomachined polysilicon structures will be the same as for bulk samples made from polysilicon. This is not unexpected, since Young's modulus is a material property. It is related to the interatomic interactions and should have no dependence on the geometry of the sample. It should be noted that polysilicon can display a preferred crystallographic orientation depending on the deposition conditions, and that this could affect the Young's modulus of the material, since the Young's modulus of silicon is not isotropic. But the anisotropy is fairly small for the cubic silicon.

A more recent investigation that utilized electrostatically actuated cantilevers and interferometric deflection detection yielded a Young's modulus of 164 GPa [34.19]. They found the grains in their polysilicon films to be randomly oriented and calculated the Voigt and Reuss bounds to be 163.4–164.4 GPa. This appears to be a very reliable value for randomly oriented polysilicon.

Fracture Toughness and Strength of Polysilicon

Using the device shown in Fig. 34.13a and the specimen shown in Fig. 34.13d, the fracture toughness, K_{Ic}, of polysilicon has been shown to be $1.0 \pm 0.1\,\mathrm{MPa\,m^{1/2}}$ [34.32]. Several different polysilicon microstructures were tested, including fine-grained, columnar, and multilayered. Amorphous silicon was also investigated. All of the microstructures displayed the same K_{Ic}. This indicates that, like Young's modulus, fracture toughness is a material property, independent of the material microstructure or the geometry of the sample.

A tensile test, such as shown in Fig. 34.7 but using a sample with indentation-induced sharp pre-cracks, reveals a K_{Ic} of $0.86\,\mathrm{MPa\,m}^{1/2}$ [34.33]. The passive, residual stress loaded beams with sharp pre-cracks, shown in Fig. 34.6, gave a K_{Ic} of $0.81\,\mathrm{MPa\,m}^{1/2}$ [34.13].

Given that K_{Ic} is a material property for polysilicon, measured fracture strength, σ_{crit}, is related to K_{Ic} by

$$K_{\mathrm{Ic}} = c\sigma_{\mathrm{crit}}(\pi a)^{1/2}\,, \qquad (34.14)$$

where a is the crack-initiating flaw size, and c is a constant of order unity. The value for c will depend on the exact size, shape, and orientation of the flaw; for a semicircular flaw, c is equal to 0.71 [34.34]. Therefore, any differences in the reported fracture strength of polysilicon will be the result of changes in a.

A good review of the experimental results available in the literature for polysilicon strength is contained in [34.35]. The tensile strength data vary from about 0.5 to 5 GPa. Like many brittle materials, the measured strength of polysilicon is found to obey Weibull statistics. This implies that the polysilicon samples contain a random distribution of flaws of various sizes, and that the failure of any particular specimen will occur at the largest flaw that experiences the highest stress. One consequence of this behavior is that, since larger specimens have a greater probability of containing larger flaws, they will exhibit decreased strengths. More specifically, it was found that the most important geometrical parameter is the surface area of the sidewalls of a polysilicon specimen [34.35]. The sidewalls, as opposed to the top and bottom surfaces, are those surfaces created by etching the polysilicon film. This is not surprising since LPCVD polysilicon films contain essentially no flaws within the bulk, and the top and bottom surfaces are typically very smooth.

As a result, the etching techniques used to create the structures will have a strong impact on the fracture strength of the material. For single-crystal silicon specimens it was found that the choice of etchant could change the observed tensile strength by a factor of two [34.36]. In addition, the bend strength of amorphous silicon was measured to be twice that of polysilicon for specimens processed identically [34.32]. It was found that the reactive ion etching used to fabricate the specimens produced much rougher sidewalls on the polysilicon than on the amorphous silicon.

Fatigue of Polysilicon

Fatigue failure involves fracture after a number of load cycles, when each individual load is not sufficient by itself to generate catastrophic cracking in the material. For ductile materials, such as metals, fatigue occurs due to accumulated damage at the site of maximum stress and involves local plasticity. As a brittle material, polysilicon would not be expected to be susceptible to cyclic fatigue. But fatigue has been observed for polysilicon tensile samples [34.33], polysilicon bend specimens with notches [34.26, 37], and polysilicon bend specimens with sharp cracks [34.38]. The exact origins of the fatigue behavior are still subject to debate. But some aspects of the experimental data are that the fatigue lifetime does not depend on the loading frequency [34.33], the fatigue behavior is affected by the ambient [34.13, 38], and the fatigue depends on the ratio of compressive to tensile stresses seen in the load cycle [34.13].

Friction of Polysilicon

The friction of polysilicon structures has been measured using the techniques described in Sect. 34.2.2. The measured coefficient of friction was found to vary from 4.9 [34.27] to 7.8 [34.28].

34.3.2 Mechanical Properties of Other Materials

As discussed above, of all the materials used for MEMS and NEMS, polysilicon has generated the most interest as well as the most research in mechanical properties characterization. But measurements have been taken on other materials, and these are summarized in this section.

As discussed in Sect. 34.2.2, one advantage of the externally loaded tension test, as shown in Fig. 34.7, is that essentially any material can be tested using this technique. As such, tensile strengths have been measured to be 0.6 to 1.9 GPa for SiO_2 [34.39] and 0.7 to 1.1 GPa for titanium [34.40]. The yield strength for electrodeposited nickel was found to vary from 370 to 900 MPa, depending on annealing temperature [34.16]. In addition, the yield strength was strongly affected by the current density during the electrodeposition process. Both the annealing and current density effects were correlated to changes in the microstructure of the material. Young's moduli were determined to be 100 GPa for titanium [34.40] and 215 GPa for electrodeposited nickel [34.16].

The technique of bending cantilever beams, shown in Fig. 34.8, can also be performed on a variety of materials. The yield strength and Young's modulus of gold were found to be 260 MPa and 57 GPa, respectively, using this method [34.18]. Another technique that can be used with a number of materials is the membrane deflection method, shown in Fig. 34.10. A polyimide membrane gave a residual stress of 32 MPa, a Young's modulus of 3.0 GPa, and an ultimate strain of about four percent [34.20]. Membranes were also fabricated from polycrystalline SiC films with two different grain structures [34.41]. The film with (110)-texture columnar grains had a residual stress of 434 MPa and a Young's modulus of 349 GPa. The film with equiaxed (110)- and (111)-textured grains had a residual stress of 446 MPa and a Young's modulus of 456 GPa.

Other devices used for measuring mechanical properties require more complicated micromachining, namely patterning, etching, and release, in order to operate. These devices are more difficult to fabricate with materials not commonly used as MEMS structural materials. The following examples, however, demonstrate work in this area. The structure shown in Fig. 34.5b was fabricated from $\mathrm{Si}_x\mathrm{N}_y$ and revealed a nominal fracture toughness of 1.8 MPa m$^{1/2}$ [34.12]. Lateral resonators of the type shown in Fig. 34.11 were processed using polycrystalline SiC, and Young's modulus was determined to be 426 GPa [34.42]. The device shown in Fig. 34.12 was fabricated from polycrystalline germanium and used to measure a bend strength of 1.5 GPa for unannealed Ge and 2.2 GPa for annealed Ge [34.43].

References

34.1 W. Nix: Mechanical properties of thin films, Metall. Trans. A **20** (1989) 2217–2245

34.2 G. G. Stoney: The tension of metallic films deposited by electrolysis, Proc. R. Soc. Lond. A **82** (1909) 172–175

34.3 W. Brantley: Calculated elastic constants for stress problems associated with semiconductor devices, J. Appl. Phys. **44** (1973) 534–535

34.4 A. Ni, D. Sherman, R. Ballarini, H. Kahn, B. Mi, S. M. Phillips, A. H. Heuer: Optimal design of multilayered polysilicon films for prescribed curvature, J. Mater. Sci., in press

34.5 J. A. Floro, E. Chason, S. R. Lee, R. D. Twesten, R. Q. Hwang, L. B. Freund: Real-time stress evolution during $\mathrm{Si}_{1-x}\mathrm{Ge}_x$ heteroepitaxy: Dislocations, islanding, and segregation, J. Electron. Mater. **26** (1997) 969–979

34.6 X. Li, B. Bhusan: Micro/nanomechanical characterization of ceramic films for microdevices, Thin Solid Films **340** (1999) 210–217

34.7 M. P. de Boer, H. Huang, J. C. Nelson, Z. P. Jiang, W. W. Gerberich: Fracture toughness of silicon and thin film micro-structures by wedge indentation, Mater. Res. Soc. Symp. Proc. **308** (1993) 647–652

34.8 H. Guckel, D. Burns, C. Rutigliano, E. Lovell, B. Choi: Diagnostic microstructures for the measurement of intrinsic strain in thin films, J. Micromech. Microeng. **2** (1992) 86–95

34.9 F. Ericson, S. Greek, J. Soderkvist, J.-A. Schweitz: High sensitivity surface micromachined structures for internal stress and stress gradient evaluation, J. Micromech. Microeng. **7** (1997) 30–36

34.10 L. S. Fan, R. S. Muller, W. Yun, R. T. Howe, J. Huang: Spiral microstructures for the measurement of average strain gradients in thin films, Proc. IEEE Micro Electro Mechanical Systems Workshop, Napa Valley 1990 (IEEE, New York 1990) 177–182

34.11 M. Biebl, H. von Philipsborn: Fracture strength of doped and undoped polysilicon, Proc. Intl. Conf. Solid-State Sensors and Actuators, Stockholm 1995, ed. by S. Middelhoek, K. Cammann (Royal Swedish Academy of Engineering Sciences, Stockholm 1995) 72–75

34.12 L. S. Fan, R. T. Howe, R. S. Muller: Fracture toughness characterization of brittle films, Sens. Actuators A **21–23** (1990) 872–874

34.13 H. Kahn, R. Ballarini, J. J. Bellante, A. H. Heuer: Fatigue failure in polysilicon is not due to simple stress corrosion cracking, Science **298** (2002) 1215–1218

34.14 H. Kahn, N. Tayebi, R. Ballarini, R. L. Mullen, A. H. Heuer: Wafer-level strength and fracture toughness testing of surface-micromachined MEMS devices, Mater. Res. Soc. Symp. Proc. **605** (2000) 25–30

34.15 W. N. Sharpe Jr., B. Yuan, R. L. Edwards: A new technique for measuring the mechanical properties of thin films, J. Microelectromech. Syst. **6** (1997) 193–199

34.16 H. S. Cho, W. G. Babcock, H. Last, K. J. Hemker: Annealing effects on the microstructure and mechanical properties of LIGA nickel for MEMS, Mater. Res. Soc. Symp. Proc. **657** (2001) EE5.23.1–EE5.23.6

34.17 W. Suwito, M. L. Dunn, S. J. Cunningham, D. T. Read: Elastic moduli, strength, and fracture initiation at sharp notches in etched single crystal silicon microstructures, J. Appl. Phys. **85** (1999) 3519–3534

34.18 T. P. Weihs, S. Hong, J. C. Bravman, W. D. Nix: Mechanical deflection of cantilever microbeams: A new technique for testing the mechanical properties of thin films, J. Mater. Res. **3** (1988) 931–942

34.19 B. D. Jensen, M. P. de Boer, N. D. Masters, F. Bitsie, D. A. La Van: Interferometry of actuated microcantilevers to determine material properties and test structure nonidealities in MEMS, J. Microelectromech. Syst. **10** (2001) 336–346

34.20 M. G. Allen, M. Mehregany, R. T. Howe, S. D. Senturia: Microfabricated structures for the in situ measurement of residual stress, Young's modulus, and ultimate strain of thin films, Appl. Phys. Lett. **51** (1987) 241–243

34.21 H. Kahn, S. Stemmer, K. Nandakumar, A. H. Heuer, R. L. Mullen, R. Ballarini, M. A. Huff: Mechanical properties of thick, surface micromachined polysilicon films, Proc. IEEE Micro Electro Mechanical Systems Workshop, San Diego 1996, ed. by M. G. Allen, M. L. Redd (IEEE, New York 1996) 343–348

34.22 L. Kiesewetter, J.-M. Zhang, D. Houdeau, A. Steckenborn: Determination of Young's moduli of micromechanical thin films using the resonance method, Sens. Actuators A **35** (1992) 153–159

34.23 W. C. Tang, T.-C. H. Nguyen, R. T. Howe: Laterally driven polysilicon resonant microstructures, Sens. Actuators A **20** (1989) 25–32

34.24 P. T. Jones, G. C. Johnson, R. T. Howe: Fracture strength of polycrystalline silicon, Mater. Res. Soc. Symp. Proc. **518** (1998) 197–202

34.25 P. Minotti, R. Le Moal, E. Joseph, G. Bourbon: Toward standard method for microelectromechanical systems material measurement through on-chip electrostatic probing of micrometer size polysilicon tensile specimens, Jpn. J. Appl. Phys. **40** (2001) L120–L122

34.26 C. L. Muhlstein, E. A. Stach, R. O. Ritchie: A reaction-layer mechanism for the delayed failure of micron-scale polycrystalline silicon structural films subjected to high-cycle fatigue loading, Acta Mater. **50** (2002) 3579–3595

34.27 M. G. Lim, J. C. Chang, D. P. Schultz, R. T. Howe, R. M. White: Polysilicon microstructures to characterize static friction, Proc. IEEE Micro Electro Mechanical Systems Workshop, Napa Valley 1990 (IEEE, New York 1990) 82–88

34.28 B. T. Crozier, M. P. de Boer, J. M. Redmond, D. F. Bahr, T. A. Michalske: Friction measurement in MEMS using a new test structure, Mater. Res. Soc. Symp. Proc. **605** (2000) 129–134

34.29 J. Yang, H. Kahn, A. Q. He, S. M. Phillips, A. H. Heuer: A new technique for producing large-area as-deposited zero-stress LPCVD polysilicon films: The MultiPoly process, J. Microelectromech. Syst. **9** (2000) 485–494

34.30 E. Chason, B. W. Sheldon, L. B. Freund, J. A. Floro, S. J. Hearne: Origin of compressive residual stress in polycrystalline thin films, Phys. Rev. Lett. **88** (2002) 156103-1–156103-4

34.31 S. Jayaraman, R. L. Edwards, K. J. Hemker: Relating mechanical testing and microstructural features of polysilicon thin films, J. Mater. Res. **14** (1999) 688–697

34.32 R. Ballarini, H. Kahn, N. Tayebi, A. H. Heuer: Effects of microstructure on the strength and fracture toughness of polysilicon: A wafer level testing approach, ASTM STP **1413** (2001) 37–51

34.33 J. Bagdahn, J. Schischka, M. Petzold, W. N. Sharpe Jr.: Fracture toughness and fatigue investigations of polycrystalline silicon, Proc. SPIE **4558** (2001) 159–168

34.34 I. S. Raju, J. C. Newman Jr.: Stress intensity factors for a wide range of semi-elliptical surface cracks in finite-thickness plates, Eng. Fract. Mech. **11** (1979) 817–829

34.35 J. Bagdahn, W. N. Sharpe Jr., O. Jadaan: Fracture strength of polysilicon at stress concentrations, J. Microelectromech. Syst. (2003) 302–312

34.36 T. Yi, L. Li, C.-J. Kim: Microscale material testing of single crystalline silicon: Process effects on surface morphology an dtensile strength, Sens. Actuators A **83** (2000) 172–178

34.37 H. Kahn, R. Ballarini, R. L. Mullen, A. H. Heuer: Electrostatically actuated failure of microfabricated polysilicon fracture mechanics specimens, Proc. R. Soc. Lond. A **455** (1999) 3807–3923

34.38 W. W. Van Arsdell, S. B. Brown: Subcritical crack growth in silicon MEMS, J. Microelectromech. Syst. **8** (1999) 319–327

34.39 T. Tsuchiya, A. Inoue, J. Sakata: Tensile testing of insulating thin films; humidity effect on tensile strength of SiO_2 films, Sens. Actuators A **82** (2000) 286–290

34.40 H. Ogawa, K. Suzuki, S. Kaneko, Y. Nakano, Y. Ishikawa, T. Kitahara: Measurements of mechanical properties of microfabricated thin films, Proc. IEEE Micro Electro Mechanical Systems Workshop (IEEE, New York 1997) 430–435

34.41 S. Roy, C. A. Zorman, M. Mehregany: The mechanical properties of polycrystalline silicon carbide films determined using bulk micromachined diaphragms, Mater. Res. Soc. Symp. Proc. **657** (2001) EE9.5.1–EE9.5.6

34.42 A. J. Fleischman, X. Wei, C. A. Zorman, M. Mehregany: Surface micromachining of polycrystalline SiC deposited on SiO_2 by APCVD, Mater. Sci. Forum **264-268** (1998) 885–888

34.43 A. E. Franke, E. Bilic, D. T. Chang, P. T. Jones, T.-J. King, R. T. Howe, G. C. Johnson: Post-CMOS integration of germanium microstructures, Proc. Intl. Conf. Solid-State Sensors and Actuators (IEE Jpn., Tokyo 1999) 630–637

35. Thermo- and Electromechanics of Thin-Film Microstructures

Applications using thin-film micromechanical structures for actuation and sensing require the coupling of energy between various physical domains. This chapter focuses on two important couplings: thermomechanics and electromechanics. Thermomechanical phenomena is considered in Sect. 35.1 where we describe broad aspects of the deformation characteristics and stress states that arise when dealing with a large class of thin-film microstructures. These include the origin of stresses in multiplayer films and their qualitative evolution through processing and release from the substrate. A basic framework is described for the analysis of the thermo mechanics of multiplayer films, emphasizing linear response. Issues of geometric and material no linearity are then taken up, and equal emphasis is put on the generality of the analysis approach and specific applications. As much as possible, we show comparisons between theoretical predictions and companion experimental results.

A common use of electro mechanics in microsystems involves the application of an electric potential between two electrodes where one is fixed and the other is connected to a deformable elastic structure. The electric potential produces an electric field and an associated electrostatic force that deforms the structure, and in turn alters the electrostatic force, resulting in fully-coupled nonlinear behavior. At some point an instability can occur where the deformable structure snaps into contact with the fixed electrode. This phenomena, called pull-in is often used for switching applications. In Sect. 35.2 we describe the basic electromechanical phenomena using a parallel-plate electrostatic actuator as a reference. We discuss many important phenomena including pull-in, external forcing, stabilization, time response, the effects of dielectric charging, and breakdown of gases in small gaps. We address these phenomena for a wide range of micro mechanical structures including cantilevered beams and plates, torsion ally suspended plates, and zipper actuators with curved electrodes.

35.1 **Thermomechanics of Multilayer Thin-Film Microstructures** .. 1041
  35.1.1 Basic Phenomena 1041
  35.1.2 A General Framework for the Thermomechanics of Multilayer Films 1046
  35.1.3 Nonlinear Geometry 1054
  35.1.4 Nonlinear Material Behavior 1058
  35.1.5 Other Issues 1061

35.2 **Electromechanics of Thin-Film Microstructures** 1061
  35.2.1 Applications of Electromechanics . 1061
  35.2.2 Electromechanics Analysis 1063
  35.2.3 Electromechanics – Parallel-Plate Capacitor 1064
  35.2.4 Electromechanics of Beams and Plates 1066
  35.2.5 Electromechanics of Torsional Plates 1068
  35.2.6 Leveraged Bending 1069
  35.2.7 Electromechanics of Zipper Actuators 1070
  35.2.8 Electromechanics for Test Structures 1072
  35.2.9 Electromechanical Dynamics: Switching Time 1073
  35.2.10 Electromechanics Issues: Dielectric Charging 1074
  35.2.11 Electromechanics Issues: Gas Discharge 1075

35.3 **Summary and Mention of Topics not Covered** 1078

References 1078

Microsystems rely heavily on thin-film technology: the deposition, patterning, etching, and so on, of multiple film layers to yield micromechanical structures. We do not discuss fabrication techniques here but instead refer the interested reader to many excellent references that describe the fabrication of micromechanical structures by means of thin-film technology [35.1, 2] and, in particular, surface micromachining [35.3]. Regardless of the fabrication process flow, the end result is a thin-film microstructure that is connected to a substrate through one or more *sacrificial* film layers, which must be released to render it freestanding and thus useful. Figure 35.1a illustrates a simple, yet typical in terms of the microstructure and the materials involved, case: a cantilevered beam made of polycrystalline silicon (polysilicon) anchored to a silicon substrate and encased in an SiO_2 sacrificial layer. Also shown is a metal electrode used for electrostatic actuation of the cantilever after release. This is the state of affairs after the thin-film fabrication steps; we refer to it as the as-processed but unreleased condition. To render the beam freestanding, although anchored to the substrate at one end, the sacrificial material must be removed (Fig. 35.1b). For SiO_2, this is usually accomplished by etching in an HF solution, followed by drying. The latter step is important because during wet etching, strong (at the microscale) capillary forces can pull the beam into contact with the substrate. If the microstructure is too compliant, adhesive forces between the microstructure and the substrate can pin the beam to the substrate, rendering it useless. This phenomena is often referred to as stiction, and many recent references describe the phenomena, its impact regarding reliability, and practical ways to overcome it [35.4, 5]. For our purposes, we assume that the microstructure can be successfully released so that it is free from the substrate where desired and anchored where desired.

High stresses can develop in the film layers during processing, and these can vary significantly from layer to layer and even within a single layer. When the sacrificial layers are removed, the stresses redistribute, but at the expense of deformation. This can be detrimental in applications in which planarity is essential, or it can be used advantageously for actuation purposes. Indeed many applications are based on the use of thermally induced bending of bilayer beams and plates that arises due to the difference in thermal expansion coefficients between the film layers. An example is shown in Fig. 35.2 where a micromirror is suspended above the substrate by 2.0-μm-thick gold/polysilicon bilayer beams that position the mirror (or any desired device) and can then be electrostatically actuated to control the position of the micromirror. Upon release, microstructures are typically used for actuation and/or sensing functions. This requires the coupling of the mechanical behavior of the microstructure with various energy domains. These couplings include, among others, thermomechanics, electromechanics, electrothermomechanics, and magnetomechanics. The most common, and perhaps the most easily realizable, is electromechanics, specifically the coupling of electrostatics and mechanics. This coupling has been successfully demonstrated by many applications as both sensors and actuators.

This chapter focuses on the behavior of thin-film microstructures under the action of thermomechanical and electromechanical loadings. Section 35.1 is devoted to the development of stresses and deformation in multilayer thin-film microstructures when subjected to thermomechanical loading. It focuses heavily on linear thermoelastic behavior but describes important issues regarding geometric and material nonlinearity. Section 35.2 is devoted to the electromechanics of microstructures, emphasizing general approaches to modeling and then focusing on the behavior of typ-



Fig. 35.1a,b Schematic of thin-film microstructures **(a)** attached to a substrate layer, and **(b)** freestanding after release from the substrate by etching of the sacrificial film



Fig. 35.2 Scanning electron microscope image of a micromirror (300 μm square) supported above the substrate by gold/polysilicon bilayer beams that can be individually actuated electrostatically to control the position of the micromirror

ical classes of electromechanical microstructures. The treatment is certainly not exhaustive, but we hope it is detailed enough to provide the interested reader with an entry-level understanding of the basic phenomena and some guidance regarding where to turn to obtain more in-depth information.

35.1 Thermomechanics of Multilayer Thin-Film Microstructures

In this section we describe aspects of the deformation characteristics and stress states in multilayer thin-film microstructures. Deformation and stress states will be considered for microstructures that are both attached to a substrate and freestanding after release from the substrate. In the modeling formalism that we will describe, the substrate simply serves as another layer. We will refer to microstructures as beams and/or plates, depending on the relevant dimensions. At times we will use the terms loosely, but we will describe the difference of their deformation characteristics in detail. The remainder of this section will be organized as follows: Section 35.1.1 provides an overview of the basic phenomena including the origin of stresses in multilayer films and their qualitative evolution through processing and then release from the substrate. Section 35.1.2 outlines a general framework for the analysis of the thermomechanical behavior of multilayer thin films, emphasizing *linear* response. Issues of *geometric* and *material* nonlinearity are then briefly taken up in Sects. 35.1.3 and 35.1.4, respectively. Section 35.1.5 touches on a number of related and important issues that were not covered in the other sections.

The objectives of this section are to describe the thermomechanical phenomena that arise when dealing with a large class of thin-film microstructures. A basic framework is described for analysis, and equal emphasis is put on the generality of the approach and specific applications. When possible, we show comparisons between theoretical predictions and companion experimental results. To this end, a specific material and geometric system must be chosen, and we use a gold/polysilicon multilayer for most of these cases. We note, though, that the phenomena discussed are not restricted to the gold/polysilicon system but arise in many multilayer film systems.

35.1.1 Basic Phenomena

During the multiple thin-film deposition and etching processes, many complicated mechanisms occur that result in straining of the film layers, and these generally differ from layer to layer. The requirement that the film layers maintain coherency at the interfaces between them means that these strains cannot occur freely, and thus they are constrained. This constraint leads to stresses in the layers and curvature of the multilayer film system; both can have significant practical implications. The mechanisms that lead to internal stresses include chemical reactions, lattice mismatch, and grain growth, among others, and are often called *intrinsic* stresses (see, for example [35.6]). The details of intrinsic stress development in thin films have been the subject of extensive study for both scientific and technological reasons, but they are beyond the scope of our study. In addition, stresses may arise due to thermal expansion mismatch between layers when subjected to a temperature change. Such stresses are often called *extrinsic* stresses. Now, in the unreleased configuration of Fig. 35.1a, a complicated stress distribution exists as a result of the intrinsic stresses. The release process to yield the configuration of Fig. 35.1b obviously alters the stress distribution as well as the state of deformation. In order to gain physical insight, the remainder of this section discusses rather qualitatively the nature of the stress states in the unreleased and released configurations. In subsequent sections details are given regarding analysis of these thermomechanical phenomena.

Transformation Strains, Misfit Strains, and Thin-Film Stresses

The important concepts here are most easily described in terms of a bilayer film system in which both layers are isotropic. Furthermore, they are easier to grasp in the context of a specific example, of which many would suffice. Once this understanding is in place, the generalization of the concepts to multilayer film systems follows naturally. To begin, we define a couple of terms. A *transformation strain* ε^* is a strain that occurs in a solid, but with no accompanying stress. It is thus an inelastic strain. In the literature a number of other terms are used to describe this concept including *stress-free strain* and *eigenstrain*. It can result, for example, from thermal expansion, a crystallographic phase transformation, or a variety of sources. When thermal expansion is the source, ε^* can be specified as $\varepsilon^* = \alpha T$ where

α is the thermal expansion coefficient of the material and T is the temperature change from a reference (usually stress-free) configuration. In general ε^* and α are second-order tensors. Stresses and deformation develop in bilayer film/substrate systems when, due to external or internal sources, each layer wants to undergo a *different* transformation strain, but the requirement of bonding of the films at the interface constrains each film to some degree. The source of the stress and deformation is then the difference in the transformation strains between the layers, i. e., $\Delta\varepsilon = \varepsilon_1^* - \varepsilon_2^*$ where ε_1^* and ε_2^* are the transformation strains of the two layers. For example, if a bilayer is subjected to a uniform temperature change T, then $\Delta\varepsilon = (\alpha_1 - \alpha_2)\,T = \Delta\alpha T$ where α_1 and α_2 are the thermal expansion coefficients of the two layers. $\Delta\varepsilon = \varepsilon_1^* - \varepsilon_2^*$ is termed the *misfit strain*. Its role as the direct source of deformation is obvious and clear for two-layer systems. The concept of misfit strain is not as direct for multilayer systems, and so we simply characterize the behavior in terms of the individual transformation strains of each layer.

It is important to understand the character of the stress distribution and deformation. To make the ideas concrete, consider the bilayer film system with planar dimensions (normal to the film thickness direction) that far exceed the total thickness. The two layers, denoted by 1 and 2, are perfectly bonded along the interface and have different isotropic thermal expansion coefficients and elastic moduli. The bilayer is initially flat, and each layer is stress free. Now assume the bilayer is subjected to a uniform temperature change T, which would lead to equibiaxial ($\varepsilon^* = \varepsilon_{xx}^* = \varepsilon_{yy}^*$, $\gamma_{xy}^* = 0$) transformation strains $\varepsilon_1^* = \alpha_1 T$ and $\varepsilon_2^* = \alpha_2 T$ in the two layers if they were not bonded. Because they are bonded, though, this results in the development of equibiaxial stresses ($\sigma = \sigma_{xx} = \sigma_{yy}$, $\sigma_{xy} = 0$) in the layers, a change of length in the planar directions (in-plane straining) and bending of the bilayer (curvature). This can be understood by the following thought experiment, which is often used in the calculation of film stresses. We will only use it, though, to explain the basics of the resulting deformation and will leave the actual calculations to the next section.



Fig. 35.3 Illustration showing the development of stresses and deformation in a bilayer film/substrate system

Consider the bilayer system shown schematically in Fig. 35.3a. The film layers are stress free and perfectly bonded. Our discussion will be in the context of biaxial transformation strains and stresses, but the ideas can be immediately applied to situations of uniaxial stress/strain behavior or plane stress or strain situations. We are interested in obtaining the deformation and stress state when the bilayer is subject to a uniform temperature change T. Since the films are stress free in Fig. 35.3a, one can cut the bonds that connect the two layers and separate the films (Fig. 35.3b) without generating any stresses or deforming either layer. Now we (Fig. 35.3c) subject the layers to a uniform temperature change T; each layer will undergo its stress-free biaxial strain, $\varepsilon_1^* = \alpha_1 T$ and $\varepsilon_2^* = \alpha_2 T$ (for simplicity, Fig. 35.3c illustrates the deformation for the case where $\varepsilon_2^* = 0$, $T < 0$, and $\alpha_1 > 0$, but the ideas are the same for more general situations). Now the interfaces, which were originally in perfect registry, are no longer. To bring them into registry, a uniform stress must be applied to the film (Fig. 35.3d) by means of the application of forces along the film edge. At this stage the film is subjected to the uniform biaxial stress $\sigma_1 = M_1\varepsilon_1^*$, where M_1 is the biaxial modulus of the film (see Sect. 35.1.2), the substrate is still stress free, $\sigma_2 = 0$, and the layers are in perfect registry. They can then be reconnected (imagine reattaching the original bonds that were cut in Fig. 35.3b), without generating additional stresses or deforming the layers (Fig. 35.3e). The stress state in Fig. 35.3e is the same as that in Fig. 35.3d, the only difference is that the films are now bonded. Now, to recover the solution for the bilayer subjected to a uniform temperature change T, we only have to remove the edge forces. This can be accomplished by applying forces of equal magnitude but opposite sign to the edges (Fig. 35.3f). The solution is then obtained as the superposition of the problems in Fig. 35.3e, which is trivial, and Fig. 35.3f, which is difficult in general. Instead of now trying to solve the problem in Fig. 35.3f, we will simply describe the character of the resulting deformation and stress state. Two aspects are important: the behavior near the free edge where the stress in Fig. 35.3f is applied, and the behavior far away from the free edge. One can appeal to St. Venant's principle to simplify the latter, but more involved analysis is required for the former (see for example [35.7]).

At a distance of ten or so film thicknesses away from the edges, the solution to the problem in Fig. 35.3f can be decomposed, as shown in Fig. 35.4. The uniform force distribution on the edges of the film (Fig. 35.4a) can be replaced by a concentrated force acting at the middle z-coordinate of the film thickness (Fig. 35.4b). The solution to this problem can then be obtained by the superposition of the two problems in Fig. 35.4c and 35.4d, the loadings of which are statically equivalent to that in Fig. 35.4b. That in Fig. 35.4c is a concentrated force applied at the as-yet-unknown neutral surface of the bilayer; it will lead to a uniform in-plane (x-y plane) straining of the bilayer. That in Fig. 35.4d is a moment of magnitude Pd, where d is the distance between the z-coordinates of the middle of the film and the neutral surface of the bilayer; it will lead to bending of the bilayer. If there were also a film on the bottom of the substrate so that the layered film was symmetric in material properties and geometry (film thicknesses) in the z-direction, then no moment would result, and the layered system would not bend but would only strain in-plane.



Fig. 35.4 Decomposition of the edge-loading problem into the superposition of a force and moment applied to the multilayer. Away from the edge, the force gives rise to uniform straining, and the moment gives rise to bending

It is probably obvious that very near the edge, the stress state is quite complicated. In fact, in the context of linear elasticity, a stress singularity generally exists at the intersection of the free edge and the interface between the two layers. This singular stress state is similar to that which exists at a crack tip, but the strength of the singularity differs depending on the mismatch in elastic constants of the materials [35.8, 9]. The region within which this stress state exists depends on the film thickness, and for very thin films it is often so small that it is insignificant. It has recently been shown, however, that in some cases it can be appreciable and in fact can be the primary source of failure [35.10]. As described in detail by *Hui* et al. [35.7], aside from the singular stresses, the stress state near the edges contains highly localized shear and normal stress (perpendicular to the interface) components. By St. Venant's principle these stress components decay over a rather short distance from the edge, but they can play a significant role in the durability of the film/substrate system as they can lead to delamination of the interface or cracking into one of the layers. The character of these stress components at the interface is shown qualitatively in Fig. 35.5. Note that in order to satisfy equilibrium, the normal stress (often called the peel stress) changes sign from tensile to compressive. Furthermore, since these stress components are highly localized at the edge, in the interior of the system the interface is free of normal or shear stresses. In this chapter we will not further consider these localized stresses but instead will concern ourselves with the stresses away from the edges and the companion deformation.

Our discussion has been based on the assumption that transformation strains are constant throughout the cross section of each film. In microsystems applications, though, films will often have transformation strains that vary through the thickness. This will lead to bending of the film after it is released from the substrate. Transformation strains that vary through the thickness, i. e.,



Fig. 35.5 Character of the normal and shear stress distribution at the film/substrate interface near the free edge

$\varepsilon^*(z)$, can be easily accommodated in the description of Fig. 35.3. It is altered in that now in Fig. 35.3c an in-plane strain results, the magnitude of which is given by the through-thickness average of $\varepsilon^*(z)$, but in addition, the film bends with constant curvature. Then, both a force (uniform stress) and moment (linearly varying stress) must be applied in Fig. 35.3d to flatten the film and lengthen it so that it is again in perfect registry with the substrate and can then be rebonded [35.11].

This description provides the starting point for understanding the effects of transformation strains on stresses and deformation in a multilayer thin-film system. It is an accurate picture of the state of affairs before release of a film from the substrate to yield a freestanding microstructure. In the next sections we will discuss the changes in the deformation that occur upon release as the constraint of the substrate is removed.

Single-Layer Beams

To keep things simple, in this and the following section we focus on *beams*, which have one nonzero normal stress component, that along the beam axis. In subsequent sections we will discuss the limitations of approximating such structures as beams and proceed with a more appropriate development in terms of *plates*. Consider the beam shown in Fig. 35.1. For simplicity we assume that the sacrificial material is much thinner than the substrate, has the same elastic moduli as the substrate, and so before release is mechanically equivalent to the substrate. In this way we can describe the stress distribution before release as that of a two-layer beam. To make the discussion more tangible, consider a specific but realistic case of a polysilicon beam on a silicon substrate. The top layer of thickness 1.5 µm is the polysilicon film, and the bottom layer of thickness 500 µm is the silicon substrate (including the very thin sacrificial layer that will be removed). Assume that the polysilicon film has an intrinsic mean stress S and a linear stress gradient β (we can easily consider a nonlinear stress gradient, but the simple linear gradient suffices to demonstrate the concepts involved). This intrinsic stress is interpreted as the stress state in the film if it were free, i. e., a transformation stress. It could be expressed in terms of a transformation strain $\varepsilon^*(z)$, but since reference is often made to thin-film stresses we will carry out this and the following example using this transformation stress rather than a transformation strain. We consider three cases to isolate the effects of the mean stress and the stress gradient: (a) $S = -10\,\text{MPa}$, $\beta = 0$, (b) $S = 0$, $\beta = 0.8\,\text{MPa}/\mu\text{m}$, and (c) $S = -10\,\text{MPa}$, $\beta = 0.8\,\text{MPa}/\mu\text{m}$. In all cases, the intrinsic stress in the substrate is zero.

In Table 35.1 we give calculated results using a simple beam theory (to be discussed in the following sections) for the three scenarios. Case (a) $S = -10\,\text{MPa}$, $\beta = 0$ results in a slight contraction and a negative curvature (bent downward) of the film/substrate system prior to release. The compressive stress in the polysilicon beam is uniform but slightly lower than the value of S. The stress induced in the substrate is small and varies linearly through its thickness. It changes sign through the substrate, a necessary requirement to satisfy equilibrium. After release the stress is zero throughout the beam. To relax the stress, the beam extends (the midplane strain ε^0 is positive), but because $\beta = 0$ it does not bend. Case (b) $S = 0\,\text{MPa}$, $\beta = 0.8\,\text{MPa}/\mu\text{m}$ results in a slight positive curvature (bent upward) but no extension or contraction of the film/substrate system prior to release. The mean compressive stress in the polysilicon beam is zero, and the gradient of the stress distribution through the film is decreased from the value of β. The stress induced in the substrate is again small and varies linearly through its thickness, changing sign. After release the stress is again zero throughout the beam. The beam does not extend or contract since $S = 0$, but it bends, assuming a curvature $\kappa = \beta/E$ where E is Young's modulus of polysilicon (see Sect. 35.1.2 for details regarding this result). Careful examination of Table 35.1 shows that the strain, curvature, and stress for case (c) $S = -10\,\text{MPa}$, $\beta = 0.8\,\text{MPa}/\mu\text{m}$ can be obtained as the superposition of the results of cases (a) and (b). Specifically, after release the beam extends and bends.

Table 35.1 Stresses, curvature, and strains in a film/substrate system consisting of a 1.5-µm-thick polysilicon film and a 500-µm-thick silicon film. The elastic moduli of the film and the substrate are assumed equal, and the film has an intrinsic mean stress and stress gradient. The sign convention for curvature is that (−) indicates bending downward and (+) indicates bending upward

		(a) $S = -10\,\text{MPa}$ $\beta = 0\,\text{MPa}/\mu\text{m}$		**(b)** $S = 0\,\text{MPa}$ $\beta = 0.8\,\text{MPa}/\mu\text{m}$		**(c)** $S = -10\,\text{MPa}$ $\beta = 0.8\,\text{MPa}/\mu\text{m}$	
		Unreleased	**Released**	**Unreleased**	**Released**	**Unreleased**	**Released**
	ε^0 (µε)	0.0624	62.5	0	0	0.0624	62.5
	κ (m^{-1})	-7.5×10^{-4}	0	5.0×10^{-9}	5.0	-7.5×10^{-4}	5.0
σ (MPa)	Top	−9.96	0	0.2	0	−9.76	0
Polysilicon Film	Bottom	−9.96	0	−0.2	0	−10.16	0
σ (MPa)	Top	0.04	0	-2.0×10^{-7}	0	0.04	0
Silicon Substrate	Bottom	−0.02	0	2.0×10^{-7}	0	−0.02	0

These results illustrate the behavior of beams before and after release when they contain a mean stress and/or a linear stress gradient. The results also suggest natural means to attempt to measure the mean stress and the gradient. Test structures that are sensitive to length changes of beams after release can be used to characterize mean stress. For example, fracture of arrays of beams of varying width upon release can be used to estimate tensile stress, and fixed-fixed beams that buckle can be used to estimate compressive stress. The stress gradient in a beam can be determined by measuring its curvature after release. A survey of test structures suitable for these purposes can be found in [35.12].

Bilayer Beams

While stresses in single-layer microstructures are important for many applications, multilayer film microstructures abound in microsystems technology, and the development of stresses and deformation in them is also important. In order to convey the basic ideas, we consider an example of a two-layer beam fixed to a substrate in the same manner as that in the previous section. Specifically we consider the layered structure shown in the inset of Fig. 35.6: a polysilicon beam of thickness 1.5 µm attached to a silicon substrate of thickness 500 µm, covered with a gold film of thickness 0.5 µm. Photos of actual beams of this form are shown in Fig. 35.7 where the length of the longest beam shown is 600 µm, and the beams are 50 µm wide. Again we assume that the sacrificial material is very thin and has the same elastic moduli as the substrate, and so before release it is mechanically equivalent to the substrate. We assume that the polysilicon film has an intrinsic mean stress S and a linear stress gradient β as in the previous example, and that the gold film has an intrinsic mean stress but no stress gradient. We consider the reasonably typical stress states: $S = -10\,\text{MPa}$ and $\beta = 0.8\,\text{MPa}/\mu\text{m}$ in the polysilicon beam and $S = 50\,\text{MPa}$ in the gold film. The resulting curvature and stress distribution before and after release are shown in Fig. 35.6. They show that before release the stresses in the polysilicon and gold layer are nearly uniform, compared to the range of stresses throughout the layers. The multilayer experiences a positive curvature; recall that the system consisting of just the polysilicon



Fig. 35.6 Stress distribution through the thickness for a bilayer film consisting of a 0.5-µm-thick gold film on a 1.5-µm-thick polysilicon film subjected to an internal stresses and stress gradients. Stress distributions are shown before and after release from a 500-µm-thick silicon



Fig. 35.7 Scanning electron microscope image of gold/polysilicon bilayer cantilever beams as released from the substrate. All beams have a 0.5-µm-thick gold film, but the beams on the *left* have a 1.5-µm-thick polysilicon film, and those on the *right* a 3.5-µm-thick polysilicon layer

film and the substrate experienced a negative curvature of about the same magnitude. Thus the tensile stress in the gold is significant enough to drive the curvature from negative (bending down) to positive (bending up).

After release from the substrate, the gold/polysilicon beam contracts and bends substantially to a curvature of about 300 m^{-1}. This should be compared with 5 m^{-1} for the polysilicon beam with a stress gradient. For a beam 300 µm long cantilevered from one end as shown in Fig. 35.6, this amounts to a tip deflection of about 13 µm. The stress states in both the gold and polysilicon are significantly altered upon release. Perhaps most significantly, large stress gradients exist through the thickness of each layer. Starting at the top of the gold film, the tensile stress increases through the gold thickness. Due to the discontinuity in elastic modulus and the residual stress and stress gradients, there is a jump in the stress of about −77 MPa at the gold/polysilicon interface. The stress is compressive at the top of the polysilicon film layer and increases linearly through the thickness of the polysilicon film, taking on its maximum tensile value at the bottom of the two-layer beam. In summary, the release process results in a reduction of the stress in the gold, an increase of the stress in the polysilicon, stress gradients in both layers, a small contraction, and a large curvature change.

These examples are meant to convey the basic phenomena and give a feel for the magnitudes of the quantities involved. The actual numerical results are based on calculations performed using a relatively simple multilayer beam theory and are reasonable estimates. Details regarding the analysis will be given in the following section, including a discussion of the suitability of the simple beam theory.

35.1.2 A General Framework for the Thermomechanics of Multilayer Films

Numerous studies have elucidated the basic thermomechanical response of multilayer material systems when subjected to temperature changes or other sources of transformation strains between the layers. These have come in the context of many technological applications, the most common being structural composite materials [35.13, 14] and thin film/substrate systems for microelectronics [35.15–22], which are directly applicable to the analysis of multilayer films.

The General Multilayer Film

When a layered film is subjected to transformation strains, two aspects of deformation play a primary role: straining of the midplane and bending. When the transverse deflections due to bending are of prime importance, as is often the case, one way to broadly characterize the deformation response, especially for plates with relatively large in-plane dimensions as compared to their thickness, is in terms of the average curvature developed as a function of the transformation strains. Formally the curvature is a second-rank tensor, and for the type of layered film problems considered here it can be wholly described by the two principal curvature components, e.g., in the x- and y- directions, κ_x and κ_y. The curvature is a pointwise quantity, meaning it varies from point to point over the in-plane dimensions of the plate. In terms of the average curvature variation as a function of misfit strain, three deformation regimes have been identified [35.16–19, 22, 23]. The first regime is a linear relation between the average curvature and temperature change where $\kappa_x = \kappa_y$, i. e., the average curvature is spherically symmetric (when the materials are isotropic). This symmetric deformation would not exist if the material properties were anisotropic. This deformation regime is characterized by both small transverse displacements and rotations, and so conventional thin-plate theory adequately describes the deformation. It is the subject of the analysis in this section. The second and third regimes, which arise due to geometric nonlinearity, will be taken up in Section 35.1.3.



Fig. 35.8 Multilayer film system with a definition of the parameters involved in the analysis

Figure 35.8 shows a schematic of the geometry considered in this study; a multilayer film microstructure with lateral dimensions that far exceed the total thickness. As such we ignore the effects of the free edges and focus on a representative point in the layered film that lies at least a distance of a few film thicknesses from the edge. The layers are numbered $1, 2, \dots, N$ where 1 is the top layer and N is the bottom layer. Each layer has a thickness t_i $(i = 1 \rightarrow N)$, and the total thickness of the microstructure is t. Each of the film layers consists of an isotropic material with a Young's modulus E_i, Poisson's ratio, ν_i, and may undergo a transformation strain $\varepsilon_i^*(z)$, which may vary with position z through the film thickness. The source of $\varepsilon_i^*(z)$ may be arbitrary, and the effect of multiple sources can be considered as the sum of the individual ones. A common source, and one that we will focus on, is thermal expansion upon a uniform temperature change. In this case $\varepsilon_i^*(z) = \varepsilon_i^* = \alpha_i T$ where α_i is the thermal expansion coefficient and T is the temperature change from a reference state. In addition, each layer may contain an internal stress $\hat{\sigma}(z)$, which also may vary with position z through the thickness. For simplicity we focus our results on isotropic layers, but the framework is applicable to anisotropic behavior of each layer. As a result of the difference in stress-free strains and/or internal stresses between each layer, stresses are developed in the layers and the structure deforms; our intent is to compute these.

Analysis

The analysis presented here is somewhat standard in the treatment of laminated composite plates but has not been often used in the analysis of multilayer thin film problems for microelectronics and/or microelectromechanical systems. Detailed accounts of parts of the theory can be found in texts on composite materials (see for example [35.24,25]), and so only a brief account is presented here.


a
a'
x.u
y,v
z,w
z
a
a'
x
u^0
w^0
β
$z\beta$
β
$u = u^0 - z\frac{\partial w^0}{\partial x}$
$\beta = \frac{\partial w^0}{\partial x}$

Fig. 35.9 Kinematics of the deformation of the thin-film multilayer

The displacements u and v at any point z through the thickness of the laminate are assumed to be described by the classical Kirchoff hypothesis. As illustrated in Fig. 35.9, the Kirchoff hypothesis states that after loads are applied to the layered film, the line a–a' which is initially straight and normal to the geometric midplane remains straight, normal to the deformed geometric midplane, and its length is unchanged. In other words, the normal does not deform but only translates and rotates. As a consequence of this assumption, the displacements of any point in the layered film are given by:

$$\begin{aligned} u &= u^0 - z\frac{\partial w^0}{\partial x} \\ v &= v^0 - z\frac{\partial w^0}{\partial y} \\ w &= w^0 \,, \end{aligned} \tag{35.1}$$

where u^0, v^0, and w^0 are the displacements of the geometric midplane at $z = 0$. Note that in addition to this explicit dependence of the displacements on z, they are generally functions of x and y.

The nonzero normal and shear strains are then:

$$\begin{aligned} \varepsilon_x &= \frac{\partial u}{\partial x} = \frac{\partial u^0}{\partial x} - z\frac{\partial^2 w^0}{\partial x^2} = \varepsilon_x^0 + z\kappa_x \\ \varepsilon_y &= \frac{\partial v}{\partial y} = \frac{\partial v^0}{\partial x} - z\frac{\partial^2 w^0}{\partial x^2} = \varepsilon_y^0 + z\kappa_y \\ \gamma_{xy} &= \frac{\partial u}{\partial y} + \frac{\partial v}{\partial x} = \frac{\partial u^0}{\partial y} + \frac{\partial v^0}{\partial x} - 2z\frac{\partial^2 w^0}{\partial x \partial y} \\ &= \gamma_{xy}^0 + z\kappa_{xy} \end{aligned} \tag{35.2a}$$

or in matrix form:

$$\{\varepsilon\} = \left\{\varepsilon^0\right\} + z\,\{\kappa\} \,, \tag{35.2b}$$

where:

$$\{\varepsilon\} = \begin{Bmatrix} \varepsilon_x \\ \varepsilon_y \\ \gamma_{xy} \end{Bmatrix} \quad \left\{\varepsilon^0\right\} = \begin{Bmatrix} \varepsilon_x^0 \\ \varepsilon_y^0 \\ \gamma_{xy}^0 \end{Bmatrix} = \begin{Bmatrix} \dfrac{\partial u^0}{\partial x} \\ \dfrac{\partial v^0}{\partial y} \\ \dfrac{\partial u^0}{\partial y} + \dfrac{\partial v^0}{\partial x} \end{Bmatrix}$$

$$\{\kappa\} = \begin{Bmatrix} \kappa_x \\ \kappa_y \\ \kappa_{xy} \end{Bmatrix} = \begin{Bmatrix} -z\dfrac{\partial^2 w^0}{\partial x^2} \\ -z\dfrac{\partial^2 w^0}{\partial y^2} \\ -2z\dfrac{\partial^2 w^0}{\partial x \partial y} \end{Bmatrix} . \tag{35.3}$$

In (35.3), $\left\{\varepsilon^0\right\}$ is the midplane strain and $\{\kappa\}$ is the midplane curvature. As with the displacements, $\left\{\varepsilon^0\right\}$ and $\{\kappa\}$ are generally functions of x and y.

The stress-strain relations for each layer are:

$$\begin{Bmatrix} \sigma_x(z) \\ \sigma_y(z) \\ \sigma_{xy}(z) \end{Bmatrix}_k = \begin{bmatrix} Q_{11} & Q_{12} & Q_{16} \\ Q_{12} & Q_{22} & Q_{26} \\ Q_{16} & Q_{26} & Q_{66} \end{bmatrix}_k \times \left[\begin{Bmatrix} \varepsilon_x \\ \varepsilon_y \\ \gamma_{xy} \end{Bmatrix} - \begin{Bmatrix} \varepsilon_x^*(z) \\ \varepsilon_y^*(z) \\ \gamma_{xy}^*(z) \end{Bmatrix}_k \right] + \begin{Bmatrix} \hat\sigma_x(z) \\ \hat\sigma_y(z) \\ \hat\sigma_{xy}(z) \end{Bmatrix}_k \tag{35.4a}$$

or in compact form:

$$\{\sigma(z)\}_k = \left\{\overline{Q}\right\}_k \left[\{\varepsilon\} - \{\varepsilon(z)\}_k^*\right] + \left\{\hat\sigma(z)\right\}_k , \tag{35.4b}$$

where $k = 1 \rightarrow N$ denotes the layer number. Equation (35.4) is written in a global coordinate system for the layered structure, (x, y, z). As such, $\left[\overline{Q}\right]_k$ are the (generally anisotropic) elastic stiffness coefficients of the kth layer in the global coordinate system. They are obtained by transformation (see [35.24, 25], for example) of the stiffnesses, $[Q]_k$, from a natural coordinate system (x_1, x_2, x_3). For orthotropic materials the nonzero components of $[Q]$ for each layer are,

$$[Q] = \begin{bmatrix} \dfrac{E_1}{1-\nu_{12}\nu_{21}} & \dfrac{\nu_{12}E_2}{1-\nu_{12}\nu_{21}} & 0 \\ \dfrac{\nu_{21}E_1}{1-\nu_{12}\nu_{21}} & \dfrac{E_2}{1-\nu_{12}\nu_{21}} & 0 \\ 0 & 0 & G_{12} \end{bmatrix} , \tag{35.5a}$$

where E_i, ν_{ij}, and G_{ij} are the orthotropic Young's moduli, Poisson's ratios, and the shear modulus, respectively, of the layer, in the local coordinate system. Note that $Q_{12} = Q_{21}$, and so the equality of these expressions in (35.5a) shows the reciprocal relationship between E_i and ν_{ij}; only three of the four are independent. For isotropic materials $\left[\bar{Q}\right] = [Q]$, and the nonzero components for each layer are:

$$\left[\bar{Q}\right] = [Q] = \begin{bmatrix} \dfrac{E}{1-\nu^2} & \dfrac{\nu E}{1-\nu^2} & 0 \\ \dfrac{\nu E}{1-\nu^2} & \dfrac{E}{1-\nu^2} & 0 \\ 0 & 0 & G \end{bmatrix} \tag{35.5b}$$

In (35.4) $\left\{\hat\sigma(z)\right\}_k$ is the residual internal stress in the layer and may be an arbitrary function of z, i. e., a stress gradient may exist within each layer; $\{\varepsilon\}$ is the total strain, $\{\varepsilon^*\}_k$ is the inelastic transformation strain, and the term in rectangular brackets is the elastic strain. The stresses and strains are all defined in the (x, y, z) coordinate system. Substituting (35.2) into (35.4) yields the stress distribution through the thickness:

$$\{\sigma(z)\}_k = \left\{\overline{Q}\right\}_k \left[\left\{\varepsilon^0\right\} + z\{\kappa\} - \left\{\varepsilon^*(z)\right\}_k\right] + \left\{\hat\sigma(z)\right\}_k . \tag{35.6}$$

For the layered film system we define a resultant force $\{N\}$ and moment $\{M\}$ per unit length as:

$$\begin{Bmatrix} N_x \\ N_y \\ N_{xy} \end{Bmatrix} = \{N\} = \int_{-t/2}^{t/2} \{\sigma(z)\}_k \,\mathrm{d}z$$
$$\begin{Bmatrix} M_x \\ M_y \\ M_{xy} \end{Bmatrix} = \{M\} = \int_{-t/2}^{t/2} \{\sigma(z)\}_k \, z \,\mathrm{d}z . \tag{35.7}$$

For example, N_x is the force in the x-direction per unit length in the y-direction. $\{N\}$ and $\{M\}$ have units of $[F/L]$, $[F \cdot L/L]$, respectively.

Substituting (35.6) into (35.7) and breaking the integrals through the thickness into sums of integrals over each layer yields:

$$\begin{aligned} \{N\} &= [A]\left\{\varepsilon^0\right\} + [B]\{\kappa\} - \left\{N^\varepsilon\right\} + \left\{N^\sigma\right\} \\ \{M\} &= [B]\left\{\varepsilon^0\right\} + [D]\{\kappa\} - \left\{M^\varepsilon\right\} + \left\{M^\sigma\right\} , \end{aligned} \tag{35.8}$$

where:

$$
\begin{aligned}
[A] &= \int_{-t/2}^{t/2} \left\{\overline{Q}\right\}_k \, \mathrm{d}z = \sum_{k=1}^{N} \left\{\overline{Q}\right\}_k (z_k - z_{k-1})\\
[B] &= \int_{-t/2}^{t/2} \left\{\overline{Q}\right\}_k z \, \mathrm{d}z = \frac{1}{2} \sum_{k=1}^{N} \left\{\overline{Q}\right\}_k \left(z_k^2 - z_{k-1}^2\right)\\
[D] &= \int_{-t/2}^{t/2} \left\{\overline{Q}\right\}_k z^2 \, \mathrm{d}z = \frac{1}{3} \sum_{k=1}^{N} \left\{\overline{Q}\right\}_k \left(z_k^3 - z_{k-1}^3\right)\\
\left\{N^{\varepsilon}\right\} &= \int_{-t/2}^{t/2} \left\{\overline{Q}\right\}_k \left\{\varepsilon^*(z)\right\}_k \, \mathrm{d}z\\
\left\{N^{\sigma}\right\} &= \int_{-t/2}^{t/2} \left\{\hat{\sigma}(z)\right\}_k \, \mathrm{d}z\\
\left\{M^{\varepsilon}\right\} &= \int_{-t/2}^{t/2} \left\{\overline{Q}\right\}_k \left\{\varepsilon^*(z)\right\}_k z \, \mathrm{d}z\\
\left\{M^{\sigma}\right\} &= \int_{-t/2}^{t/2} \left\{\hat{\sigma}(z)\right\}_k z \, \mathrm{d}z\,. \qquad (35.9)
\end{aligned}
$$

In the terminology of laminated composite materials, $[A]$, $[B]$, and $[D]$ are the extensional, coupling, and bending constants and are functions of the elastic moduli of each layer and the arrangement of the layers through the thickness. $[A]$, $[B]$, and $[D]$ have units of $[F/L]$, $[F]$, and $[F \cdot L]$, respectively. Physically, $[A]$ describes the connection between in-plane forces and straining of the midplane, $[D]$ describes the connection between moments and curvature, and $[B]$ connects moments to midplane strain and forces to curvature. If both the geometry and material properties, including $\varepsilon^*(z)$ and $\hat{\sigma}(z)$, of the layered film system are symmetric about $z = 0$, then $[B] = [0]$ and there is no coupling between in-plane straining and bending. Note that $[A]$, $[B]$, and $[D]$ are 3×3 matrices, as are $\left[\bar{Q}\right]_k$, while all other terms a 3×1 column vectors of the form of (35.3) and (35.4).

Equation (35.8) can be written in compact form as:

$$
\left\{\begin{matrix}\{N\}\\ \{M\}\end{matrix}\right\} = \begin{bmatrix}[A] & [B]\\ [B] & [D]\end{bmatrix} \left\{\begin{matrix}\left\{\varepsilon^0\right\}\\ \{\kappa\}\end{matrix}\right\} - \left\{\begin{matrix}\{N^{\varepsilon}\}\\ \{M^{\varepsilon}\}\end{matrix}\right\} + \left\{\begin{matrix}\{N^{\sigma}\}\\ \{M^{\sigma}\}\end{matrix}\right\}. \qquad (35.10)
$$

Equation (35.10) is most easily implemented in matrix form as a 6×6 system of equations that hold at each (x, y) coordinate. These are the constitutive equations for the layered film, incorporating the Kirchoff hypothesis and the strain-displacement relations. In order to completely describe the response of a layered film due to external or internal loads, (35.10) must be supplemented with the stress equilibrium equations and appropriate boundary conditions. In general the solution of these equations for a specified multilayer film geometry and loading is a complex undertaking and recourse is often taken to numerical methods such as the finite element method (FEM). Alternatively, the equations can be formulated using an energy approach that will be advantageous when we consider geometric nonlinearity in Section 35.1.3.

Fortunately, using this formulation we can solve a number of important problems simply using (35.10). For example, if there are no externally applied loads then $\{N\} = \{M\} = \{0\}$ and (35.10) can be inverted to yield:

$$
\left\{\begin{matrix}\left\{\varepsilon^0\right\}\\ \{\kappa\}\end{matrix}\right\} = \begin{bmatrix}[A] & [B]\\ [B] & [D]\end{bmatrix}^{-1} \times \left\{\left\{\begin{matrix}\{N^{\varepsilon}\}\\ \{M^{\varepsilon}\}\end{matrix}\right\} - \left\{\begin{matrix}\{N^{\sigma}\}\\ \{M^{\sigma}\}\end{matrix}\right\}\right\}. \qquad (35.11)
$$

Recall that all terms on the right-hand side are functions of the elastic moduli, the known transformation strains and stresses, and the geometrical arrangement of the layers. Once the midplane strain and curvature are computed using (35.11), the stress distribution in each layer can be computed using (35.6).

Special Cases

Here we apply (35.11) to yield some simple, yet important, results. Before doing so, it is useful to explicitly express the form of the transformation stress distribution $\left\{\hat{\sigma}(z)\right\}_k$. To this end we restrict $\left\{\hat{\sigma}(z)\right\}_k$ to be a linearly varying function through each layer. This can be written as:

$$
\left\{\hat{\sigma}(z)\right\}_k = \{S\}_k - \{\beta\}_k \left(z - \frac{z_{k-1} + z_k}{2}\right), \qquad (35.12)
$$

where $\{S\}_k$ is the average stress in layer k and $\{\beta\}_k$ is the stress gradient as shown in Fig. 35.10. For this form of the stress, $\{N^{\sigma}\}$ and $\{M^{\sigma}\}$ can be expressed



Fig. 35.10 Schematic showing a linear stress distribution characterized by a mean stress S and linear through-thickness stress gradient β

as:

$$\{N^\sigma\} = \sum_{k=1}^{N} \{S\}_k \left(z_k - z_{k-1}\right)$$

$$\{M^\sigma\} = \frac{1}{2}\sum_{k=1}^{N} \{S\}_k \left(z_k^2 - z_{k-1}^2\right) - \frac{1}{12}\sum_{k=1}^{N} \{\beta\}_k \left(z_k^3 - z_{k-1}^3\right) . \qquad (35.13)$$

Furthermore, it is useful to specify the form of $\{\varepsilon^*(z)\}$ when its source is thermal expansion during a uniform temperature change T from a reference temperature. In this case:

$$\left\{\varepsilon^*(z)\right\}_k = \left\{\varepsilon^*\right\}_k = \{\alpha\}_k T . \qquad (35.14)$$

For this form of the stress-free strain, $\{N^\varepsilon\}$ and $\{M^\varepsilon\}$ can be expressed as:

$$N^\varepsilon = \int_{-t/2}^{t/2} \left\{\overline{Q}\right\}_k \{\alpha\}_k T \,\mathrm{d}z = \Delta T \sum_{k=1}^{N} \left\{\overline{Q}\right\}_k \{\alpha\}_k \left(z_k - z_{k-1}\right)$$

$$M^\varepsilon = \int_{-t/2}^{t/2} \left\{\overline{Q}\right\}_k \{\alpha\}_k Tz \,\mathrm{d}z = \frac{\Delta T}{2} \sum_{k=1}^{N} \left\{\overline{Q}\right\}_k \{\alpha\}_k \left(z_k^2 - z_{k-1}^2\right) . \qquad (35.15)$$

In all of the examples described in this section we will consider only cases in which all layers have elastic constants, thermal expansion properties, and misfit strains that are isotropic. As a result, $A_{16} = A_{26} = B_{16} = B_{26} = D_{16} = D_{26} = 0$. The ramifications of this are that the midplane shear strains $\gamma_{xy}^0 = 0$ and the twist curvatures $\kappa_{xy} = 0$. In addition, the midplane strains and curvatures are equibiaxial, i. e., $\varepsilon_x^0 = \varepsilon_y^0 = \varepsilon^0$ and $\kappa_x = \kappa_y = \kappa$. So in the remainder of this section this equibiaxial deformation state is understood, and we refer to it simply by ε^0 and κ. While this is the case in the examples presented in this section, it is not the case when material anisotropy exists, the film is patterned in lines instead of as a blanket, or large deflections occur which result in geometric nonlinearity. These issues will be discussed briefly in later sections.

Single-Layer Plate. Consider a single-layer film with an internal biaxial mean stress $S = S_{11} = S_{22}$ and stress gradient $\beta = \beta_{11} = \beta_{22}$ that is subjected to a uniform temperature change T. This scenario models the deformation of a film after release from a substrate when subjected to a temperature change where before release the film had an internal stress S, and stress gradient β. In this case, after significant manipulation (35.11), with (35.12) and (35.13), yields:

$$\kappa = \frac{\beta}{M} \qquad (35.16)$$

$$\varepsilon^0 = -\frac{S}{M} + \alpha T , \qquad (35.17)$$

where $M = \frac{E}{1-v}$ is the biaxial modulus. As previously discussed, after release there is straining due to S and $\varepsilon^* = \alpha T$, and the plate bends with a biaxial curvature κ. The result of (35.16), and especially the simplification that results for beams (simply obtained by setting $\nu = 0$ and interpreting κ and ε^0 as the uniaxial curvature and midplane strain in the direction of the beam length) is commonly used in conjunction with measurements of the curvature after release to determine the stress gradient in a film.

Bilayer Plate. Another simple yet practically important special case is that of two isotropic layers of thicknesses t_1 and t_2, subject only to a uniform temperature change T. In this case, (35.11), with (35.12) and (35.13), yields:

$$\kappa = \frac{6\Delta\alpha T}{t_2} hm \left(\frac{1+h}{1+2hm\left(2+3h+2h^2\right)+h^4m^2}\right) \qquad (35.18)$$

$$\varepsilon^0 = T \left(\frac{\alpha_1 mh\left(1+3h+3h^2+mh^3\right)}{1+2hm\left(2+3h+2h^2\right)+h^4m^2} + \frac{\alpha_2\left[1+mh\left(3+3h+h^2\right)\right]}{1+2hm\left(2+3h+2h^2\right)+h^4m^2}\right) , \qquad (35.19)$$

where $h = \frac{t_1}{t_2}$, $m = \frac{M_1}{M_2}$, and $M_k = \frac{E_k}{1-\upsilon_k}$ (here $k = 1, 2$ corresponds to layers 1 and 2) and $\Delta\alpha = \alpha_2 - \alpha_1$.

It is often convenient to define a nondimensional curvature $\hat{\kappa}$:

$$\hat{\kappa} = \frac{\kappa\, t_2}{6\Delta\alpha T} \tag{35.20}$$

Equation (35.18) can then be written as

$$\hat{\kappa} = \frac{hm\,(1+h)}{1 + 2hm\left(2 + 3h + 2h^2\right) + h^4 m^2}\ . \tag{35.21}$$

Two limiting values of (35.21) are of interest. The first is the case where there is no elastic mismatch between the layers, i. e., $m = 1$. In this case (35.21) simplifies to:

$$\hat{\kappa} = \frac{h}{(1+h)^3}\ . \tag{35.22}$$

The other is the *thin-film limit* where $t_1 \ll t_2$. Expanding (35.18) in powers of h and retaining only the lowest order term recovers *Stoney's* [35.26] well-known result:

$$\begin{aligned} \kappa &= \frac{6\Delta\alpha T}{t_2} hm \\ \hat{\kappa} &= hm\ . \end{aligned} \tag{35.23}$$

In the thin film limit, (35.19) reduces to $\varepsilon^0 = \alpha_2 T$.

Figure 35.11 shows the normalized curvature $\hat{\kappa}$ as a function of the layer thickness ratio h for various ratios of the biaxial moduli, m. The curves from top to bottom are for $m = 10$, 0.66, and 0.1. $m = 10$ and 0.1 represent a stiff film on a compliant substrate and a compliant film on a stiff substrate, respectively. $m = 0.65$ represents a gold film on a polysilicon substrate. The solid curves are the exact results from (35.21) and the dashed curves are the Stoney's result for the thin-film limit, (35.23). In the latter case, $\hat{\kappa}$ varies linearly with h, with slope m. The results in Fig. 35.10 show how the range of applicability of Stoney's result depends on both h and m; the range decreases for increasing h and decreasing m. For most microstructure applications where the layer thicknesses are comparable ($h > 0.1$), Stoney's result is not accurate unless the film is much more compliant than the substrate. Thus physically, Stoney's result is accurate when the substrate stiffness controls the deformation, either because it is much thicker or has much higher elastic moduli than the film. Over the years many papers have discussed *corrections* to Stoney's result to increase the region of validity in terms of layer thicknesses and modulus mismatch. We emphasize, though, that (35.18) is valid for arbitrary layer thicknesses and modulus mismatch and is quite simple to use itself. We refer the reader interested in more details to [35.7, 18, 22].



Fig. 35.11 Normalized curvature $\hat{\kappa}$ as a function of the film thickness ratio $h = t_1/t_2$ for three values of the biaxial modulus ratio, $m = M_1/M_2$. From *top* to *bottom*, the curves are for $m = 10$, 0.65 (gold/polysilicon), and 0.1. The *solid lines* are the exact solution, (35.21) and the *dashed lines* are Stoney's result in the thin-film limit, (35.23)

Equally important from a technological viewpoint is the equibiaxial stress distribution through the thickness $\sigma_x(z) = \sigma_y(z) = \sigma(z)$ obtained from (35.6):

$$\sigma(z)_k = M_k\left(\varepsilon^0 + z\kappa - \alpha_k T\right)\ , \tag{35.24}$$

where $k = 1, 2$ denotes the layer. In (35.24), κ and ε^0 are obtained from (35.18) and (35.19), respectively, and M_k and α_k are the values for the kth layer. In the thin-film limit the equibiaxial stress varies so little through the film thickness that it can be taken as constant, i. e., $\sigma_x = \sigma_y = \sigma$. This is the reason one often refers to the *stress* in a thin-film by a single number. In the thin film limit, the substrate (layer 2) thermal expansion dominates the deformation process, and so the film strains by an amount $\Delta\alpha T$, and the biaxial stress in the film is $\sigma_1 = M_1 \Delta\alpha T$, or in terms of the curvature:

$$\sigma_1 = \frac{M_2}{6}\frac{t_2^2}{t_1}\kappa\ . \tag{35.25}$$

Note that, as written, the thermoelastic properties of the film do not enter (35.25). We will discuss the practical ramifications of this shortly.

Figure 35.12 shows the stress distribution through the thickness of both layers for a negative unit temperature change, (35.24), as a function of $h = t_1/t_2$ for



Fig. 35.12 Biaxial stress per unit temperature change, (35.24), for a gold/polysilicon bilayer ($m = 0.67$) for a 0.5-µm-thick gold film as a function of the polysilicon thickness $h = t_1/t_2$. Biaxial stresses are shown at four locations: the interface on the gold and polysilicon sides (*dashed lines*), and the surfaces of the gold and polysilicon (*solid lines*)

$m = 0.67$, and $t_1 = 0.5\,\mu\text{m}$, representative of a gold film on a silicon substrate. Equation (35.24) shows, and we have previously discussed, that the biaxial stress varies linearly through each material. Thus we can completely specify the stress distribution by plotting it at four points: the top of material 1, the interface in material 1, the interface in material 2, and the bottom of material 2. Referring to Fig. 35.8, these positions are $z = z_0$, z_1, and z_2. Because of the perfect bonding between the two films, the total strain must be continuous across the interface. The elastic moduli are different for the two films, though, and so the stresses will be discontinuous at the interface. Hence we interpret $z = z_1$ as a position just above, or just below, the interface, and use M_k and α_k in (35.24) as appropriate. As $h \to 0$ the stresses at the top and at the interface in the film (layer 1) converge and take on a maximum value given by $\sigma = M_1 \Delta\alpha T$. The stress in the substrate vanishes in this limit. As the substrate thickness increases (increasing h) the stress in the film decreases with the maximum value occurring at the interface. The stress in the substrate increases at the interface but decreases on the bottom surface. In general this results in a stress distribution in the substrate that is compressive on the bottom surface and tensile at the interface. Depending on h, the stresses in the film are either tensile throughout or tensile on the interface and compressive on the surface. The difference in stress between the interface and the surface is a measure of the stress gradient in each layer; it increases with increasing h. For different values of m, the behavior with varying h is similar to that in Fig. 35.12, with the stress in the film increasing with increasing m.

Equation (35.25) is the theoretical basis of what is perhaps the most common technique to measure thin-film stresses – the wafer curvature method [35.6]. It involves measuring the curvature of a thick (compared to the film thickness) wafer with and without a film, and then using the curvature difference between the two in (35.25) to determine the film stress. It is particularly convenient because the film stress is obtained from the measured curvature regardless of the source of the stress and the thermoelastic moduli of the film. It is necessary, though, to know accurately the thickness of the film and substrate, as well as the elastic properties (biaxial modulus, $E/(1-\nu)$) of the substrate. An appealing feature of the method is that the elastic properties of the film, typically difficult to measure themselves, do not need to be known. This is because the much thicker substrate controls the deformation response.

Three-Layer Symmetric Plate. Considerable simplification also results for the technologically important case of a thin-film multilayer subject to a uniform temperature change T that consists of three layers, but the top and bottom layer are identical in terms of thickness ($t_3 = t_1$) and material properties ($M_3 = M_1, \alpha_3 = \alpha_1$). In this case, from (35.9) $[B] = [0]$, and thus the plate does not bend, i.e., $\kappa = 0$. Equation (35.11), with (35.12) and (35.13), then yields:

$$\varepsilon^0 = \frac{(2\alpha_1 mh + \alpha_2)\,T}{2mh+1}\,. \tag{35.26}$$

In the thin-film limit $h \to 0$, $\varepsilon^0 = \alpha_2 T$.

The equibiaxial stress distribution is such that it does not vary through the thickness within each layer, i.e., $\sigma(z)_3 = \sigma(z)_1 = \sigma_1$, and $\sigma(z)_2 = \sigma_2$. From (35.6) with $\kappa = 0$ and ε^0 from (35.26):

$$\begin{aligned}\sigma_1 &= \frac{M_1 \Delta\alpha T}{2mh+1}\\ \sigma_2 &= \frac{-2mhM_2\Delta\alpha T}{2mh+1}\,.\end{aligned} \tag{35.27}$$

In the thin-film limit, the stresses of (35.27) reduce to $\sigma_1 = M_1 \Delta\alpha T$ and $\sigma_2 = -2M_1 h \Delta\alpha T$.

Figure 35.13 shows the uniform biaxial stress in each material for a negative unit temperature change as a function of $h = t_1/t_2$ for $m = 0.65$, and $t_1 = 0.5\,\mu$m, again representative of a gold film on a silicon substrate. As $h \to 0$, the stresses in the films (layers 1 and 3) are given by $\sigma_1 = M_1 \Delta\alpha T$, and that in the substrate (layer 2) approaches zero. The stress in the films is tensile and decreases with increasing h while that in the substrate is compressive, increasing in magnitude with increasing h.

Beams. Our analysis thus far has focused on multilayer plates where both in-plane dimensions far exceed the thickness and where the transformation strains, and thus the stresses, are equibiaxial. When one in-plane dimension, say x, is much larger than the other, the structure is often referred to as a beam. In the classical treatment of the flexure of beams, it is assumed that only one nonzero normal stress component exists, σ_x. This greatly simplifies the analysis for homogeneous beams, but the situation is not as straightforward for multilayers with biaxial transformation strains. From the results in the previous section, one can obtain results for a beam theory by simply setting $\nu_1 = \nu_2 = 0$ in the formulae developed for biaxial stresses, but these results should be used with caution as the transverse component of the moment that results from the equibiaxial transformation strains cannot be neglected as shown by three-dimensional finite element calculations [35.27, 28]. *Swanson* [35.29] describes how to apply the results from a multilayer plate theory to beams and specifically focuses on the effect of the beam width, giving easily usable results for narrow and wide beams. The main results are an effective structural stiffness $(EI)_{\text{eff}}$ that can be used to replace EI (E is Young's modulus and I is the cross-sectional moment of inertia) in existing beam theory results, such as those that will be presented in Sect. 35.2 for electromechanics analysis. Insight into the behavior can be seen in the results in Table 35.2, which show measurements (using interferometry as described by *Dunn* et al. [35.30]) and predictions based on (35.18) for plates and the simplified version for beams obtained by setting $\nu_1 = \nu_2 = 0$. In all calculations both the gold and polysilicon are modeled as linear thermoelastic with isotropic material properties. Input parameters to the finite element calculations are $E_2 = 163$ GPa, $\nu_2 = 0.22$, $E_1 = 78$ GPa, $\nu_1 = 0.42$ [35.31]. The thermal expansion coefficients of the materials were assumed to vary linearly with temperature, and values at 100(24) °C used are $\alpha_2 = 3.1(2.6) \times 10^{-6}$ /°C, and $\alpha_1 = 14.6(14.2) \times 10^{-6}$ /°C [35.31]. Although some uncertainty exists in the values of these material properties for the gold and polysilicon films, we think they are sufficiently accurate for the purpose of modeling the observed phenomena. Young's modulus and Poisson's ratio of the polysilicon are in line with many measurements over many MUMPS runs [35.32] and agree adequately with bulk polycrystal averages of single-crystal elastic constants. Good agreement exists between the predictions using plate theory and the measurements, while predictions based on beam theory are significantly less accurate, demonstrating the need to use plate, rather than beam, theory.



Fig. 35.13 Biaxial stress per unit temperature change for a gold/polysilicon/gold ($m = M_1/M_2 = 0.65$) three-layer film system. The calculations, (35.27), are for a 0.5-µm-thick gold film as a function of the polysilicon thickness $h = t_1/t_2$. Biaxial stresses are shown in the gold (*top curve*) and polysilicon (*bottom curve*)

Patterned Films. In microsystems applications, additional design freedom can be obtained by using multilayer films with patterned, rather than blanketed,

Table 35.2 Predicted and measured curvature per unit negative temperature change for gold/polysilicon microstructures as a function of the polysilicon thickness. In all cases the gold thickness is 0.5 µm. The microstructures are 300 µm long and 50 µm wide and cantilevered from one end

Polysilicon	$d\kappa/dT$ (m^{-1}/°C)		
thickness (µm)	Measured	Predicted (plate)	Predicted (beam)
1.5	−5.36	−5.56	−4.86
3.5	−1.42	−1.44	−1.16

films. In general one can use the finite element method with multilayer plate elements to model the deformation and stresses in a multilayer with arbitrary patterned layers. A useful practical example is a beam of width w_2 that is covered with a film in the pattern of a stripe of width w_1 as shown in Fig. 35.14. A simple modification of (35.18) yields the curvature along the length of the patterned beam as a function of the nondimensional linewidth, $c = w_1/w_2$:

$$\kappa_{\text{patterned}} = \frac{6\Delta\alpha T}{t_2} hcm \times \left(\frac{1+h}{1+2hcm\left(2+3h+2h^2\right)+h^4c^2m^2} \right) . \tag{35.28}$$

Predictions from (35.28), normalized as $\eta = \kappa_{\text{patterned}}/T$, are shown in Fig. 35.14 for $m = 0.65$ (the gold/polysilicon bilayer) along with predictions from detailed finite element calculations and measurements over the entire range of $c = w_1/w_2$ [35.33]. Equation (35.28) accurately describes the effect of linewidth on curvature development and can be used to design bilayer beams.

Deflections. Thus far our discussion of deformation has been cast in terms of curvature. An important quantity for many applications where control of the deformation is important is the deflection of the multilayer. Formally this can be obtained by integrating the curvature-displacement relationship and applying the relevant boundary conditions. For example, assuming constant curvature, the tip deflection $w(x = L)$ for a cantilever beam of length L, is:

$$w(x = L) = \frac{\kappa L^2}{2} . \tag{35.29}$$



Fig. 35.14 Curvature per unit temperature change as a function of the ratio of gold to polysilicon film width w_1/w_2 for gold (0.5 µm thick)/polysilicon (1.5 µm thick) strip-patterned beams. *Grey circles* are finite element simulation results, the *solid line* is the analytical result of (35.28), and the *brown circles* are measurements

35.1.3 Nonlinear Geometry

In the previous section we noted that in general the deformation of a layered film microstructure subjected to transformation strains consists of three regimes but focused on the first, linear regime. Here we focus on the second and third regimes. To illustrate, consider the seemingly simple case of a plate with total thickness much less than the in-plane dimensions, composed of two isotropic layers with different material properties (elastic moduli and thermal expansion coefficients) subjected to a temperature change. Although we use a temperature change to demonstrate, the results hold for any type of transformation strains. In terms of the average curvature variation as a function of temperature change, three deformation regimes have been identified as illustrated in Fig. 35.15 [35.16–19, 22, 23]. The first regime, I, consists of a linear relation between the average curvature and temperature change where $\kappa_x = \kappa_y$, i. e., the average curvature is spherically symmetric. This deformation regime is characterized by both small transverse displacements and rotations, and so conventional thin-plate theory adequately describes the deformation. In Sect. 35.1.2 we outlined the analysis in this regime. The second regime, II, consists of a nonlinear relation between the average curvature and temperature, but again $\kappa_x = \kappa_y$. The behavior is due to *geometric nonlinearity* that results when the deflections become excessively large relative to the plate thickness, and they contribute significantly to the in-plane strains. It has been shown [35.15–19, 22, 23] that in these two regimes the symmetric deformation modes are stable. The second regime ends at the point when the deformation response bifurcates from a spherical to ellipsoidal deformation, i. e., $\kappa_x \neq \kappa_y$. At this point, the beginning of regime III, it becomes energetically favorable for the plate to assume the ellipsoidal shape because to retain the spherical deformation under an increasing temperature change requires increased mid-plane straining. After the bifurcation, the curvature in one direction increases while that perpendicular to it decreases; the plate tends toward a state of cylindrical curvature. This observation helps to explain the energetic argument, as unlimited cylindrical curvature can be obtained with no midplane straining, while spherical curvature cannot. This discussion has been cast in the context of linear material behavior. Additional deformation regimes result if material nonlinearity is present, for example, yielding [35.18].

Analysis

The understanding described above derives from a number of studies with different technological motivations, primarily structural laminated composites and thin films for microelectronics. Most of these studies are analytical [35.15–19, 22, 23, 34] and build upon the original work of Hyer [35.13, 14]. To illustrate the computational approach in a reasonably simple setting, here we consider a two-layer plate with layer thicknesses t_1 and t_2. Each layer is isotropic and characterized by the Young's modulus E_i, Poisson's ratio ν_i, and thermal expansion coefficient α_i $(i = 1, 2)$. We consider a square plate with side length L; a similar analysis can be carried out for circular [35.22] or other plate shapes. The plate is subject to a uniform temperature change, T. In other words, the stress-free strains $\{\varepsilon^*\}_k$ are due to thermal expansion as given by (35.14).

In order to compute the deformed shape when the plate is subject to a temperature change we use the approach of *Hyer* [35.14] as applied by *Masters* and *Salamon* [35.16]. The basic idea is to assume an admissible displacement field $w(x, y)$ in terms of unknown parameters (d_i) that are suitably chosen to be consistent with observed deformation modes. Values of the parameters d_i are then determined via a Ritz procedure so as to minimize the total potential energy of the system. Different choices of the assumed displacement field have been considered, and details of the procedures are given in the above references. Such analyses are sufficient to qualitatively, and in many cases quantitatively, explain the three regimes of deformation shown in Fig. 35.15. In fact, quite simple closed-form expressions result for special cases that provide illuminating descriptions of observed phenomena (see for example [35.22]). A disadvantage of the analytical approaches is that for simplicity a displacement field consistent with a spatially constant curvature deformation mode is usually chosen. Additionally, these formulations are useful for only simple plate shapes. While this may be adequate for the structures demonstrated here, it is not for more complex in-plane shapes, of either or both layers, that arise in microsystems applications. In this more general case the best approach is probably to use the finite element method for the approximate analysis.



Fig. 35.15 General characteristics of the average curvature-versus-temperature change of a two-layer plate microstructure showing the three deformation regimes. The interferograms in the *inset* show measured displacement contours for gold/polysilicon plates in Regimes II and III

To proceed, we assume the transverse midplane displacement is of the form:

$$w^0(x, y) = d_1 x^2 + d_2 y^2 \,. \tag{35.30}$$

d_1 and d_2 are immediately recognized as one-half the curvature in the x- and y-directions, and the deformation is seen to be a constant curvature mode. The midplane displacements u^0 and v^0 are assumed to be described by third order polynomials in x and y, also with unknown constant coefficients d_3–d_8 to be determined:

$$\begin{aligned} u^0(x, y) &= d_3 x + \frac{d_5}{3} x^3 + d_7 x y^2 - \frac{d_1^2}{6} x^3 \\ v^0(x, y) &= d_4 y + \frac{d_6}{3} y^3 + d_8 x^2 y - \frac{d_2^2}{6} y^3 \,. \end{aligned} \tag{35.31}$$

The midplane strains are then computed from the nonlinear strain-displacement relations of the von Karman plate theory:

$$\begin{aligned} \varepsilon_x^0 &= \frac{\partial u^0}{\partial x} + \frac{1}{2}\left(\frac{\partial w^0}{\partial x}\right)^2 \\ \varepsilon_y^0 &= \frac{\partial v^0}{\partial y} + \frac{1}{2}\left(\frac{\partial w^0}{\partial y}\right)^2 \\ \gamma_{xy}^0 &= \frac{\partial u^0}{\partial y} + \frac{\partial v^0}{\partial x} + \left(\frac{\partial w^0}{\partial x}\right)\left(\frac{\partial w^0}{\partial y}\right) \,. \end{aligned} \tag{35.32}$$

The strains at any point through the thickness are then computed using the standard kinematic relations for thin plates, (35.2), and the stresses are computed from the strains using the conventional linear thermoelastic constitutive relations for each layer, (35.6) with $\{\varepsilon^*\}_k = \{\alpha\}_k T$. The first term in (35.32) is recognized as the conventional small deformation, and the second term arises from the large transverse deflections w^0, which result in straining of the midplane. This is shown schematically in Fig. 35.16 for the strain component ε_x^0; similar results are obtained for ε_y^0 and γ_{xy}^0.

The potential energy density of each layer is computed from the stress and strain in each layer, and the total potential energy of the plate is then computed by integrating it over the volume of the plate. This yields an expression for the potential energy of the plate in terms of the unknown coefficients d_i:

$$U(d_i) = \int\limits_{-L/2}^{L/2}\int\limits_{-L/2}^{L/2}\int\limits_{-t/2}^{t/2} \{\varepsilon\}^T \{\sigma\}_k \;\mathrm{d}z\,\mathrm{d}x\,\mathrm{d}y\,, \tag{35.33}$$

where the superscript T denotes the transpose of the 3×1 column vector. The coefficients d_i are determined by application of the principle of minimum potential energy:

$$\frac{\partial U(d_i)}{\partial d_i} = 0\,. \tag{35.34}$$

This yields eight equations for the eight unknown d_i and thus solutions for the deformation response of Fig. 35.15. Complete details regarding this analysis can be found elsewhere [35.14, 16]; here we present only the pertinent results in what we hope is an accessible form. When the displacements are small, the solution of (35.34) and (35.35) recovers (35.18) and (35.19).


dx
x
w^0
$w^0 + \frac{\partial w^0}{\partial x}dx$
dx'
$dx' = dx\sqrt{1+\left(\frac{\partial w^0}{\partial x}\right)^2} = dx\left[1+\frac{1}{2}\left(\frac{\partial w^0}{\partial x}\right)^2+\ldots\right]$
$\varepsilon_x^0 = \frac{dx'-dx}{dx} = \frac{1}{2}\left(\frac{\partial w^0}{\partial x}\right)^2+\ldots$

Fig. 35.16 Illustration of the development of midplane strain due to bending when nonlinear geometry effects arise

In the nonlinear but symmetric deformation regime II, the relationship between both the curvature and midplane strain, and the thermal expansion mismatch is too complex to present here. This is also the case in the nonlinear regime III after bifurcation. An important difference between the linear and nonlinear response, though, is that the nonlinear response depends on the plate size. The critical curvature at which bifurcation occurs, though, can be obtained explicitly and is given by:

$$\kappa_{\mathrm{cr}} = \frac{12\sqrt{2}}{L^2}\sqrt{\frac{6+A_{12}/A_{11}}{1+A_{12}/A_{11}}}\,\frac{\sqrt{A_{66}D_{66}-B_{66}^2}}{A_{66}^2} \tag{35.35}$$

for a square plate of side length t, where A_{ij}, B_{ij}, and D_{ij} are the composite moduli of (35.8). In the simplified case where there is no elastic mismatch between the layers and the elastic, response can be expressed in terms of the Young's modulus E and Poisson's ratio ν, (35.35) reduces to:

$$\kappa_{\mathrm{cr}} = 2\sqrt{6}\sqrt{\frac{6+\nu}{1+\nu}}\,\frac{t}{L^2}\,, \tag{35.36}$$

where $t = t_1 + t_2$. These results have also been obtained by *Finot* and *Suresh* [35.18]; similar results exist for a circular plate [35.22, 30].

The analysis just discussed is made tractable by assuming a displacement field consistent with a constant curvature. In the nonlinear case, this assumption is questionable. While the assumed displacement field used in the Ritz procedure could be modified to incorporate the dependence of curvature on position, perhaps the simplest approach to tackle these more general problems is to use the finite element method to solve the geometrically nonlinear equations over an arbitrary spatial domain. This is also the most viable approach for more complicated in-plane geometries, including patterned films. Complete details regarding the use of the finite element method to carry out such calculations can be found in *Dunn* et al. [35.30]. Here we will simply show the result of some of these calculations. The input parameters used are the same as those given in Sect. 35.1.2.

Deformation Behavior

In order to illustrate the nature of the deformation phenomena in the nonlinear regimes, Fig. 35.17 shows contour plots of measured (using an interferometric microscope as described by *Dunn* et al. [35.30]) and predicted displacement fields $w(x, y)$ for square plates of four plate sizes that have been cooled from about 100 °C where they are flat to room temperature. Due to the thermal expansion mismatch between the polysilicon and gold, the $L = 150\,\mu\text{m}$ samples deform in a spherically symmetric manner; contours of constant transverse displacement $w(x, y)$ are nearly circles. This is also the case as the size increases to $L = 200$ and $250\,\mu\text{m}$, although the displacements increase as the plate size increases. At $L = 300\,\mu\text{m}$, though, the transverse displacement contours are not circular but elliptical, indicating that the deformation is no longer spherically symmetric. Thus when subjected to the same temperature change, both the magnitude and deformation mode depend on the plate size. As the in-plane dimension of the plate increases with the thickness held constant, the deformation mode changes from one of spherical symmetry to one more like cylindrical symmetry.

A complete picture of the deformation as a function of plate size and temperature change could be obtained by acquiring full-field displacements like those in Fig. 35.17 as a function of temperature. But a reasonable picture of the deformation behavior can be obtained in much simpler form by considering the *average* curvature in the x- and y-directions as a function of temperature. This is shown in Fig. 35.18, in which the average curvature in the x- and y-directions is plotted as a function of the magnitude of the temperature change during cooling. The temperature change is actually negative according to our convention, but its magnitude is plotted for convenience. The average curvatures are determined from the measured and computed $w(x, y)$ by averaging $\kappa_x = -\partial^2 w(x, 0)/\partial x^2$ and $\kappa_y = -\partial^2 w(0, y)/\partial y^2$ along the paths $y = 0$ and $x = 0$, respectively [35.30]. The x- and y-directions are taken to be aligned with the principal curvatures after bifurcation. The use of the average curvature as a measure of the plate deformation seems appropriate if the curvature is, or is close to, spatially uniform. This aspect will not be taken up in detail, but we refer the interested reader to [35.22,30] for details. It is apparent from both the measurements and predictions that in regime I, the curvature-temperature response is



Fig. 35.17a,b Contour plots of the **(a)** measured, and **(b)** predicted transverse displacements $w(x, y)$ at room temperature following cooling from 100 °C for the four gold/polysilicon square plates: $L = 150$, 200, 250, and $300\,\mu\text{m}$ from *left* to *right*. Each contour band represents a displacement of 0.23, 0.35, 0.45, and $0.6\,\mu\text{m}$ for the $L = 150$, 200, 250, and $300\,\mu\text{m}$ plates, respectively



Fig. 35.18 Average measured (*top*) and predicted (*bottom*) curvature as a function of temperature change upon cooling from 100 °C to room temperature. The curves from *top* to *bottom* are for the $L = 150$, 200, 250, and $300\,\mu\text{m}$ structures, respectively

independent of plate size and shape. In regime II, though, there is a strong dependence on plate size, and this is also the case in regime III. The major discrepancy between the measurements and predictions is the sharpness of the bifurcation for the $L = 300\,\mu\text{m}$ plate; it is quite sharp in the predictions but much more gradual in the measurements. To understand this we note that the source of the bifurcation is an *imperfection* of some sort that breaks the ideal symmetry, and in general it is difficult to accurately model the detailed imperfection.

Figure 35.19 demonstrates the connection between the thermomechanical loading (the temperature change), the geometry (plate size, L), and the boundaries between the three deformation regimes for gold/polysilicon plate microstructures. Specifically, it shows the temperature change necessary to initiate nonlinear effects (the transition between regions I and II), and bifurcation (the transition between regions II and III) as a function of polysilicon thickness when the gold film thickness is kept constant at $0.5\,\mu\text{m}$. Despite the fact that the constant curvature approximation becomes questionable for larger plate sizes, (35.35) is a good approximation as seen by the agreement with the finite element calculations, at least for the elastic mismatch and plate sizes considered here. In fact, although not shown, the simplified result of (35.36) for no elastic mismatch is in reasonable agreement with the finite element and the complete analytical results. The measurement for $L = 300\,\mu\text{m}$ is accurately described by both the analytical and finite element results.



Fig. 35.19 Temperature change required for the initiation of nonlinear geometry effects (*dotted lines*) and critical temperature change for bifurcation (*solid lines*) as a function of square plate size and the thickness of polysilicon for the gold/polysilicon microstructures. Lines in each set from *left* to *right* represent $1.5\,\mu\text{m}$, $3.5\,\mu\text{m}$, $5.5\,\mu\text{m}$, and $8.5\,\mu\text{m}$ thick polysilicon, respectively. *Grey circles* are finite element calculations, and the *brown circle* is a measurement

In the analytical treatments discussed previously, it is assumed that the curvature is spatially uniform. The power of finite element calculations is that this requirement is relaxed and the spatial variation of the curvature can be studied theoretically. Full-field interferometry measurements allow one to study this experimentally as well. Briefly we discuss the resulting behavior for gold/polysilicon plate microstructures but refer the interested reader to [35.22, 30] for more details. In the linear regime, measurements and predictions both show that curvature is essentially uniform across the plate. In the nonlinear regime, though, the curvature varies appreciably with position, increasing by about a factor of two from the center to the periphery of the plate. The spatial nonuniformity of the curvature increases as the plate size increases. The spatial variation of the curvature raises concern regarding the suitableness of an analysis based on constant curvature. As mentioned previously, such an analysis may be adequate to describe the general deformation behavior but not for finer details.

35.1.4 Nonlinear Material Behavior

So far we have discussed in some detail the linear thermoelastic response of multilayer films and to a lesser degree, the effects of geometric nonlinearity. An additional complication is material nonlinearity. It can arise in numerous forms including plasticity, creep, stress relaxation, and evolution of the material microstructure (densification, grain growth, defect annihilation, etc.) during thermomechanical loading. In this section we briefly discuss nonlinear material behavior of multilayer films, focusing on the phenomena most relevant for the realization of reliable devices. The discussion in this section is concerned primarily with multilayer films where one of the films is a metal.

Nonlinear Material Behavior During Initial Thermal Cycles

As deposited, the material microstructure of a metal film is generally not stable. As the film is heated, microstructural evolution leads to the development of internal stress, which then can lead to changes in the curvature of the multilayer film. The general behavior is common to films made of many different metals, such as aluminum, copper, nickel, and gold. It has been studied extensively in the context of microelectronics applications (see for example [35.6, 35, 36]) where the substrate



Fig. 35.20 Curvature versus temperature for gold (0.5-µm-thick)/polysilicon (1.5-µm-thick) 300 µm × 50 µm beam microstructures. The *solid lines* are tests with six cycles from room temperature to 200 °C with the maximum temperature in each successive cycle increasing by 20 °C. The *dashed lines* are tests with two cycles: the first from room temperature to 200 °C and then back to 30 °C, and the second to 275 °C and then back to 30 °C

is much thicker than the film and the thin-film limit results, which simplifies the interpretation of the results.

Figure 35.20 shows the general behavior of the curvature vs. temperature for a bilayer film consisting of a 0.5 µm gold film that was evaporated onto a 1.5 µm polysilicon film. During the initial heating the deformation is thermoelastic, characterized by a decrease in curvature with a constant $d\kappa/dT$, until the temperature reaches about 70 °C (the theoretical thermoelastic slope from (35.18) is shown on the figure). Between 70 °C and 100 °C, the curvature decreases at a much lower rate; in fact the curve flattens, i. e., $d\kappa/dT \approx 0$. Interestingly, between room temperature and 100 °C, the curvature changes from positive to negative, our convention being that a positive curvature means a beam with the gold on top is curved upward. The strong departure of the curvature from the thermoelastic behavior results because the microstructure of the evaporated film is not stable in the as-deposited condition. The temperature increase during the first cycle promotes microstructural changes in the film. These result in tensile straining of the film, which competes with the thermoelastic deformation (see for example [35.6, 36]). Upon cooling from 100 °C, the response is again thermoelastic, this time throughout the entire cooling process. Although it does not occur here, if the temperature change is large enough, yielding of the metal film can occur upon cooling. The curvature upon return to room temperature is greater than that initially at room temperature. It is important to understand this behavior because many post-fabrication and packaging processes expose a microstructure to elevated temperature excursions. During these, the film is susceptible to this nonlinear deformation. In the tests in Fig. 35.20, the material has not been taken to a temperature high enough to stabilize fully the gold microstructure in the first cycle. As a result, subsequent cycles going to successively higher temperatures appear to have the effect of continuing to stabilize the microstructure. The response during the second cycle is similar to the first with the exception that the temperature change required to initiate nonlinear behavior is increased. Indeed, over the range of temperature cycles studied, each subsequent cycle is similar, exhibiting thermoelastic response upon heating until a point where nonlinear κ-T behavior commences. The cooling process is again thermoelastic with the subsequent room temperature curvature increasing with each cycle. Also shown in Fig. 35.20 is a result for a second test on a nominally identical microstructure with only two cycles: the first from room temperature to 200 °C and back to 30 °C, and the second to 275 °C and back to 30 °C. The results of the first cycle to 200 °C neatly envelope the results of the set of tests with cycles up to 200 °C. This shows that although there is a path dependence of the deformation behavior, it is controlled by the maximum temperature reached during cycling, independent of how many increments are carried out to reach that temperature. The second cycle to 275 °C shows the same behavior observed in all cycles. The results in Fig. 35.20 have been obtained at a constant heating/cooling rate. In terms of the stabilization of the material microstructure that results in nonlinear material behavior, the rate, along with the time held at the elevated temperature, plays a significant role.

Figure 35.20 suggests that a simple description of the evolution of curvature with temperature can be obtained with parameters as shown in Fig. 35.21: the as-released curvature κ_r (and associated temperature, T_r), a critical temperature at which inelastic mechanisms are activated, T_{cr} (and the associated curvature, κ_{cr}), the slope of the inelastic κ-T behavior (assuming simple linear behavior) for $T > T_{cr}$, ξ, and the thermoelastic slope $\eta = d\kappa/dT$. The as-released curvature is determined primarily by the intrinsic stress development upon film deposition, cooling to room temperature, and release. These also influence T_{cr}. The parameter ξ is physically related to the curvature per unit temperature change due to inelastic mechanism(s) activated beyond T_{cr}. The situation in Fig. 35.20 is much simplified in that $\xi = 0$.



Fig. 35.21 Schematic diagram showing the parameters in the simple model that describes the curvature-versus-temperature behavior of the bilayer beam during thermal cycling after release

With knowledge of these parameters, one can compute the curvature following a defined thermal loading history. The qualitative behavior in Fig. 35.21 also results for a substrate with patterned lines (Sect. 35.1.2), and the same formalism can be used with κ_r, η, and ξ depending on linewidth [35.33]. For example, (35.28) gives the dependence of η on linewidth.

Plasticity

Plasticity in thin-film multilayers has been studied in depth for thin metal films on thick substrates (see, for example [35.6, 37, 38]), but little work has been directed toward freestanding multilayers. This is probably because, at least when subject to thermal loading, the stresses are typically smaller in freestanding multilayer films than in systems with thin films on thick substrates (see Fig. 35.12). Many interesting open issues exist with regard to the general issue of plasticity in microstructures including the understanding of size effects and strain gradient effects (see for example [35.39, 40]).

Creep and Stress Relaxation

For many microsystems applications, it is important to control accurately the deformation of thin-film microstructures over a significant period of time in order to meet performance and reliability requirements. This is especially important for microstructures subjected to thermal loading and/or operated at elevated temperatures. When one or more of the layers consists of a metal or polymer film, creep and stress relaxation in the film can significantly influence deformation and compromise device performance, and so their effects must be carefully considered. For example, *Miller* et al. [35.41] designed and fabricated microrelay switch arrays for RF communications applications using prestressed gold/polysilicon bimaterial beams as electrostatically actuatable switches. They observed a change in the switch shape and position over time and attributed it to stress relaxation in the gold. *Vickers-Kirby* et al. [35.42] report that creep in gold and nickel cantilever beams leads to voltage drops in micromachined tunneling accelerometers over time.

Creep and stress relaxation phenomena have been investigated in some detail for thin film on thick substrate systems, motivated primarily by microelectronics applications (see for example [35.11, 35, 43–46]). These studies have focused on measuring, understanding, and modeling the stress-versus-temperature behavior that occurs when a metal film-substrate system is heated from room temperature, then cooled back to room temperature, over one or a few cycles. The stress-temperature curves in the experimental works are typically obtained using the wafer curvature method that is now widely used to measure stress in thin films. During a typical test thermoelastic and inelastic mechanisms contribute to produce a complex nonlinear stress-temperature curve like that in Fig. 35.20. In most of these studies, the stress-temperature response is studied using wafer curvature measurements at a fixed heating or cooling rate so that rate dependent and independent phenomena are coupled in the response. Stress relaxation during an isothermal hold has been studied by [35.35, 43, 45, 47], among others. These studies all show that significant stress relaxation can occur over periods of only a few hours at modest temperatures of only about 100 °C for many metal thin-film systems. Due to the thin-film/thick-substrate system, the stress in the metal films is quite high, on the order of hundreds of MPa. Models incorporating power law creep of the metal film were successfully able to describe the observed response qualitatively and, to a large degree, quantitatively. The latter, however, sometimes required modification of the power-law exponent. *Shen* and *Suresh* [35.35] showed experimentally that a thin passivation layer on a metal film on thick silicon substrates can significantly reduce creep and stress relaxation. *Thouless* et al. [35.45] also studied the effect of a thin passivation layer on the stress relaxation of thin films with a focus on the deformation mechanisms. Their experimental results suggest that the presence of a passivation layer on the surface of a film can have a substantial effect on relaxation rates likely by suppressing mechanisms associated with diffusion and dislocation motion.

Thermomechanical Fatigue

It is also important to understand the development of damage and its effect on deformation during cyclic thermomechanical loading. To date, only very limited attention has been directed toward this issue. *Zhang* and *Dunn* [35.33] showed that if gold/polysilicon multilayers were cycled (Fig. 35.20) to an elevated temperature and then cooled to room temperature, they followed the thermoelastic path on subsequent cycling to a temperature below the maximum reached during the initial thermal cycle. Presumably over this range of temperature and time, the gold microstructure has been stabilized by the first cycle, and the polysilicon microstructure is not changing. This was confirmed for only a few, perhaps ten, cycles. *Gall* et al. [35.48] have shown that for thousands of cycles, though, a gradual shift of the thermoelastic curve downward is observed, possibly due to creep and stress relaxation in the gold, although the thermoelastic slope is maintained.

35.1.5 Other Issues

There are a number of additional issues regarding the thermomechanical behavior of thin-film microstructures that warrant discussion. Due to space limitations, however, we will only mention them and refer the reader to appropriate references.

In addition to the deformation itself, the stiffness characteristics of a microstructure, such as for example a beam or plate, can depend significantly on the stress in the beam. *Senturia* [35.49] describes the phenomena and discusses implications for microstructure design. This includes tensile stresses that tend to stiffen beams and plates as well as compressive stresses that can lead to buckling.

An important strategy has emerged to characterize the effects of processing on the residual stress state and thermomechanical behavior of films: the use of on-chip test structures to extract material properties including film stresses. Many test structures, both passive and active, have been developed to measure residual stresses (tensile and compressive), stress gradients, elastic moduli, strength, toughness, thermal expansion, and many others. Nice surveys of many test structures are given by Masters et al. [35.12] and *de Boer* et al. [35.50] where further references to more extensive details can be found.

35.2 Electromechanics of Thin-Film Microstructures

Electromechanics, the coupling of electrostatics and mechanics, is perhaps the most common of the energy couplings used in microsystems technology for sensing and actuation. In this section we summarize the contemporary application of electromechanics, the analysis of fundamental electromechanics problems, and the practical issues that arise in the design of an electromechanical microsystem.

35.2.1 Applications of Electromechanics

Our reference to electromechanics will be limited to the coupling of electrostatics and the mechanics of constrained elastic media such as a cantilever beam. In this case, the electrical energy is transformed into strain energy of the elastic media but with typically negligible energy dissipated due to material damping. An alternative application of electromechanics is the coupling of electrostatics with rigid body mechanics. In this case the mechanical structure is not constrained by a compliant support to the substrate but by a kinematic constraint, which is a pin joint between multiple structural layers or anchor between the substrate and a structural element. An example of these rigid body constraints is the anchor in the electrostatic micromotors. In this case, the electrostatic energy is dissipated by friction (Coulomb type friction between structural elements and pin joints, other structural elements, and/or the substrate) and is stored in the kinetic energy of the rigid body. In this case, the energy stored as strain energy in the structural element is by design negligible. In both electromechanics cases, the energy is dissipated by viscous forces under dynamic conditions. Finally the coupling of electrostatics and mechanics can more broadly; consider the coupling of electrostatics and fluids or electro-thermo-mechanics.

Microsystems have enabled many different commercial applications of electromechanics. These applications have included pressure sensors, accelerometers, gyros, resonators, micropumps, optical mirrors, optical shutters/VOAs, and DC and RF switches. In these examples, electrostatic forces are produced between a stationary electrode and a movable electrode, which is often the proof mass for an accelerometer or the diaphragm for a pump. The electrostatic forces are imparted by a voltage difference between the movable and stationary electrode. The electromechanics is typically implemented in two ways, with the first characterized by a stable, analog behavior, and the second characterized by an unstable, digital behavior. The stable behavior is implemented as a self-test capability for accelerometers such that a specific, stable displacement is produced with the application of the voltage. The unstable behavior is implemented with a switch so that when the instability point (snap-in or pull-in) is reached, the switch will instantaneously close.

Electrostatic actuation has been used for switches and microrelays [35.51–53], accelerometers [35.54,55], micropumps [35.56, 57], and micromirror [35.58–65]. The specific case of switches and relays involves multiple regions of electromechanical behavior and represents one of the richer electromechanics design problems. The general behavior is shown in Fig. 35.22. The first region is the stable actuation region. In this region, the switch is actuated to an instability point in the voltage displacement curve called the pull-in or snap-in voltage. Up to the instability, the displacement increases monotonically until the pull-in voltage is reached. At the pull-in voltage, the switch instantaneously closes the gap because of the instability and establishes contact with the substrate. In the case of the switch, this means the closure of a contact. The electromechanics problem continues with a new set of boundary conditions in the next region because the switch is now "simply" constrained at the contact and fixed at its anchors to the substrate. In Fig. 35.22, the switches tip displacement is shown, which is the reason the displacement is unchanged as the voltage increases. Region 2 is then characterized by a constant displacement for increasing voltage. The shape of the beam continues to change as the voltage is increased to the point that the electrodes could short if necessary precautions are not taken.



Fig. 35.22 Characteristic electromechanical hysteresis curve showing pull-in, contact, and release voltages

If the first consideration of the switch design is pull-in voltage, the second consideration of the switch design is the development of contact force, which is directly related to the contact resistance. The electromechanical analysis is continued beyond the pull-in voltage once contact is established to develop an increasing contact force. The electrostatic force is distributed between the anchor and the contacts, assuming other portions of the switch are not in contact. The electrostatic force increases as the square of the voltage difference, so the force acting on the contact will increase in proportion to this. Of course other physical limitations must be considered such as gas breakdown or a secondary pull-in that cause shorting between electrodes. The contact areas of the switch that are not the contacts should be minimized, so this does not detract from the contact force.

A third design consideration is the overdrive capability, defined as the maximum voltage the switch control electrodes can support before they touch and short. In some cases, the electrodes may be isolated from each other by a thin dielectric film, whose implications will be discussed in a later section. As suggested in the later section, the insulation material can be patterned to reduce the contacting area between the electrodes and the insulating material, in order to reduce charge accumulation. With the patterned isolation, the switch could be driven by such a large voltage to short the uninsulated regions. This failure mode could be evaluated by the same electromechanics analysis.

A fourth design issue would be the switch's release voltage, which is the voltage when the contact force reaches zero and the switch opens. This is shown as the beginning of region 3, where the deformation is reduced as the voltage is decreased. The release voltage is lower than the pull-in voltage because the electrostatic forces are much greater for the reduced gap than compared to the larger gap just before the pull-in instability. A fifth design consideration is the switch's self-actuation voltage, which is that which occurs across open contact and unintentionally causes the switch to close. By design, the switch's self-actuation voltage should be maximized in the electromechanical analysis. A final design issue is the determination of breakdown limits across the switch's control electrodes. This is not limited to the voltage supported across the equilibrium gap of the control electrodes and needs to be considered for different cases. The breakdown will be described by the Paschen curve or by vacuum breakdown proportional to the gap.

35.2.2 Electromechanics Analysis

An electromechanics analysis requires modeling of the structural domain, the electrostatic domain, and the coupling between the electrostatic fields and the structural elements. It has been approached at three levels of complexity. The simplest approach is the development of lumped parameter models, which have provided the basic understanding of instability, the impact of nonlinear springs, and the pull-in voltage-gap relationship. The lumped parameter model is comprised of the parallel plate capacitor and a spring (linear or nonlinear). One plate is constrained in space, by a substrate for example. The second plate is elastically constrained to one degree-of-freedom, typically, of motion, which is usually closing the "air" gap. The spring element represents the effective spring stiffness K of the structural element that could be a beam, a plate, a membrane. The parallel plate capacitor represents the electrostatic coupling between the fixed and moving elements.

Increasing in complexity, the second level of analysis considers continuum structural elements with a distributed electrostatic load. For example, the solution for an isotropic homogeneous beam would satisfy the Euler–Bernoulli beam equation:

$$EI\frac{\mathrm{d}^4 w}{\mathrm{d}x^4} = q(x) , \qquad (35.37)$$

where E is Young's modulus, I is the structure's moment of inertia, $w(x)$ is the transverse deflection of the beam, x is the coordinate along the length of the beam, and $q(x)$ represents the distributed electrostatic load. For a multilayer film, an effective EI can be used, as mentioned in Sect. 35.1.2. The third level of analysis is to model the fully coupled problem as continuum solids. The approach has used different implementations of finite difference (FD), finite element (FE), and boundary element (BE). A typical example would be to implement a finite element code to solve the continuum mechanics problem and a boundary element code to solve the electrostatics problem. Another implementation would use finite element methods to solve both the mechanics and the electrostatics problems. In each case, a similar algorithm is followed for developing a self-consistent solution to the coupled electromechanics analysis.

The coupled electromechanics problem can be described simply as a pair of conductors, where one conductor has a fixed constraint and the second conductor is attached to an elastic structure, such as a beam, a plate, a membrane, or an elastic substrate. The conductors support a voltage difference between them that causes charge to be induced on the surface of the conductors. This charge produces an electrostatic force that attracts the two conductors together. As the elastically supported conductor deforms toward the fixed conductor, the charge redistributes and modifies the field, thereby the force distribution. The process continues until a redistribution of charge is no longer necessary to maintain equilibrium. The typical algorithm begins by calculating the displacements of the undeformed geometry, which is updated before proceeding to the electrostatic analysis. In the electrostatic analysis, the surface charge density distribution is calculated and then used to calculate the electrostatic forces. The electrostatic force distribution is the important parameter because it is passed to the mechanical analysis as the loading condition on the conductors in the undeformed state to deform the structure until a state of equilibrium is reached.

Electromechanical Systems Energy Balance

A general analytical methodology can be applied to many different structures including parallel plate actuators with linear or nonlinear springs and plates supported by torsional suspensions [35.66]. They consider a single input system with charge control or voltage control. To begin, a generalized actuator is considered that consists of two conductors. One conductor is fixed. The second conductor is constrained by an elastic support.

In the charge controlled actuator, the total energy for the generalized actuator is written in terms of the mechanical energy as a function of the generalized coordinate χ and of the electrical energy stored in the capacitance of the actuator. The total energy is:

$$U_\mathrm{T}(\chi, Q) = U_\mathrm{M}(\chi) + \frac{Q^2}{2C(\chi)} , \qquad (35.38)$$

where U_T is the total energy, U_M is the mechanical energy, and the electrical energy is determined by the charge Q, and the capacitance $C(\chi)$. The first derivative of the total energy with respect to the generalized coordinate set equal to zero determines the equilibrium. The second derivative of the total energy with respect to the generalized coordinate set equal to zero determines the stability. The first and second derivatives are determined and then combined to determine what is referred to as the charge-controlled pull-in equation:

$$\frac{\partial U_{\mathrm{M}}(\chi_{\mathrm{PI}})}{\partial \chi}\frac{\partial^2}{\partial \chi^2}\left(\frac{1}{C(\chi_{\mathrm{PI}})}\right) - \frac{\partial^2 U_{\mathrm{M}}(\chi_{\mathrm{PI}})}{\partial \chi^2}\frac{\partial}{\partial \chi}\left(\frac{1}{C(\chi_{\mathrm{PI}})}\right) = 0 \tag{35.39}$$

and the pull-in charge Q_{PI}:

$$Q_{\mathrm{PI}} = \left(\frac{-2\dfrac{\partial U_{\mathrm{M}}(\chi_{\mathrm{PI}})}{\partial \chi}}{\dfrac{\partial C(\chi_{\mathrm{PI}})}{\partial \chi}}\right)^{1/2} . \tag{35.40}$$

In the voltage controlled case, the total co-energy for the generalized actuator is used because the capacitor is nonlinear, and the actuator is voltage controlled. The co-energy is written in terms of the capacitance between the generalized conductors, the voltage across the conductors, and the mechanical energy. The total co-energy is:

$$U_{\mathrm{T}}^{*}(\chi, Q) = \frac{1}{2}C(\chi)V^2 - U_{\mathrm{M}}(\chi) . \tag{35.41}$$

The relationship between energy and co-energy is shown in Fig. 35.23.

In a similar process to the charge-controlled system, the voltage-controlled pull-in equation is determined by the first derivative of the total co-energy with respect to the generalized coordinate and by the second derivative of the total co-energy with respect to the generalized coordinate. The equations for the first and second derivative are combined to determine the voltage-controlled pull-in equation

$$\frac{\partial U_{\mathrm{M}}(\chi_{\mathrm{PI}})}{\partial \chi}\frac{\partial^2 C(\chi_{\mathrm{PI}})}{\partial \chi^2} - \frac{\partial^2 U_{\mathrm{M}}(\chi_{\mathrm{PI}})}{\partial \chi^2}\frac{\partial C(\chi_{\mathrm{PI}})}{\partial \chi} = 0 \tag{35.42}$$



Fig. 35.23 Effort-Displacement curve showing the relationship between energy and co-energy

The pull-in voltage V_{PI} is:

$$V_{\mathrm{PI}} = \left(\frac{2\dfrac{\partial U_{\mathrm{M}}(\chi_{\mathrm{PI}})}{\partial \chi}}{\dfrac{\partial C(\chi_{\mathrm{PI}})}{\partial \chi}}\right)^{1/2} . \tag{35.43}$$

The application of this approach, to either the voltage-controlled or the charge-controlled case involves determining the mechanical energy and the capacitance. From the mechanical energy and the capacitance, the pull-in parameters and voltage are determined.

Lagrangian Approach to Electromechanics

Li and *Aluru* [35.67] and *Aluru* and *White* [35.68] have proposed a Lagrangian approach for both the electrostatic analysis and the mechanical analysis. Their algorithm begins by calculating the structural displacements for the undeformed geometry. They proceed to the electrostatic analysis to calculate the charge distribution on the conductors in the undeformed state. The charge distribution is used to calculate the electrostatic forces on the undeformed geometry until the system reaches equilibrium. The first advantage of their approach is that the algorithm does not require the structural geometry to be updated. A second advantage is the elimination of the integration error, wich occurs because flat panels are used in other approaches to approximate curved surfaces. The overall algorithm is shortened because the interpolation functions do not have to be updated as the structure shape changes.

35.2.3 Electromechanics – Parallel-Plate Capacitor

The classic element for understanding electromechanics is the simple parallel-plate capacitor model with one plate fixed and the second, moveable, plate, suspended by a spring. This basic electromechanics element is shown in Fig. 35.24. The capacitor is described by an area, A; an initial gap, g_0; and a dielectric constant of ε in the air gap (where ε is the product of the relative dielectric of the media filling the gap, ε_{r}, and the permittivity of free space, $\varepsilon_0 = 8.854 \times 10^{-12}\,\mathrm{F/m}$). The moveable plate is shown suspended by the spring, with spring constant K, and a single degree-of-freedom represented by the coordinate z. In this case, the equilibrium position is represented by having no charge on the plates (i. e. no electrostatic force) and no displacement of the spring (i. e. no spring force). It should be noted that as the spring length grows by increasing z, the gap decreases. The behavior of this simple model is described in detail in many sources including [35.49, 66].



Fig. 35.24 Lumped parameter parallel plate capacitor electromechanical model

The parallel plate capacitor can be analyzed with either a voltage source or a current source. With a voltage source, the charge on the capacitor plates is

$$Q = \frac{\varepsilon A}{g} V \,, \qquad (35.44)$$

where Q is the charge on the capacitor plates, ε is the dielectric constant in the gap, A is the capacitor plate area, g is the instantaneous gap between plates, and V is the voltage across the plates.

The electrostatic force on the capacitor plates is determined by the dielectric constant, the capacitor plate area, the instantaneous gap, and the voltage across the capacitor:

$$F = \frac{\varepsilon A V^2}{2g^2} \,. \qquad (35.45)$$

The electrostatic force scales as the voltage squared and inversely diminishes as the instantaneous gap squared. This is the force that acts on the movable plate; hence the spring stretches (or is relaxed if the voltage is lowered). The amount of stretch in the spring is:

$$z = \frac{F}{K} \,. \qquad (35.46)$$

The instantaneous gap is

$$g = g_0 - z = g_0 - \frac{\varepsilon A V^2}{2Kg^2} \,. \qquad (35.47)$$

Electromechanics – Parallel Plate Capacitor with External Forcing

Nemirovsky et al. [35.66] examined the case of constant applied force acting on the suspended capacitor plate of a parallel-plate electrostatic actuator. This situation represents a force-balanced system, in which the electrostatic force is used to balance a pressure load acting on a membrane or an inertial load (e.g. acceleration induced) on a suspended proof mass. With an applied mechanical force, the mechanical energy is:

$$U_\mathrm{M}(z) = \frac{1}{2} K z^2 - F_\mathrm{ext} z \,, \qquad (35.48)$$

where F_ext is the externally applied force. The solution to the pull-in equation is

$$\zeta_\mathrm{PI} = \frac{z}{z_\mathrm{max}} = \frac{1}{3}\left(1 + 2\frac{F_\mathrm{ext}/K}{z_\mathrm{max}}\right) \,, \qquad (35.49)$$

where ζ_PI is the ratio z/z_max. It can be seen when the applied force is zero. Equation (35.49) reduces to the familiar result of $z = z_\mathrm{max}/3$. The pull-in voltage is

$$V_\mathrm{PI} = \left(\frac{8K\left(z_\mathrm{max} - \frac{F_\mathrm{ext}}{K}\right)^3}{27\varepsilon_0 A}\right)^{1/2} \,. \qquad (35.50)$$

Electromechanics – Parallel Plate Stabilization

An important practical consideration is the stabilization of the parallel plate electrostatic actuator. *Seeger* et al. [35.69] and Nemirovsky et al. [35.66] showed that the addition of a series capacitance (feedback capacitance) stabilizes the actuator such that it does not pull-in to the substrate. The series capacitance and the variable actuator capacitance combine to form a voltage divider that provides passive control of the voltage across the actuator. In this case, Nemirovsky et al. [35.66] identified three regimes, defined in terms of δ, which is the ratio of the initial actuator capacitance to the series capacitance (Nemirovsky et al. [35.66] had defined the series capacitance in terms of a dielectric layer on one capacitor plate). The first regime is defined for $0 < \delta < 0.5$, when the series capacitance is less than half the nominal actuator capacitance. In this case, the actuator is stable so the pull-in effect is eliminated. The second regime is defined by $\delta > 0.5$ and the pull-in occurs between $1/3$ of the gap and the full distance of the gap. In the third regime $\delta \gg 1$, which means the series capacitance is much greater than the nominal capacitance. The pull-in parameter is given by:

$$\zeta_\mathrm{PI} = \frac{1}{3}\left(1 + \frac{1}{\delta}\right) \,, \qquad (35.51)$$

which reduces to $\zeta_{PI} = \zeta_{max}/3$ when the series capacitance is eliminated. The pull-in voltage is:

$$V_{PI} = \left[\frac{8Kz^3_{max}}{27\varepsilon_0 A}\left(1+\frac{1}{\delta}\right)^3\right]^{1/2} . \qquad (35.52)$$

Electromechanics – Extending the Range of Motion

Electromechanical systems have two obvious characteristics: nonlinearity and instability. If one desires digital operation or fast switching times, the inherent electromechanical instability is a significant benefit. On the other hand if analog control is desired, the control is faced with both the nonlinearity and the instability. In both cases, the range of motion of the electromechanical device is limited. The range of motion to the instability was extended by the addition of a series capacitor, but this did not address the linearity. *Toshiyoshi* et al. [35.59] addressed the linearity of electrostatically actuated mirrors in an optical scanner. Their's was a two degree-of-freedom scanner, so the increased linearity was necessary to improve the crosstalk between the two different scanner modes. The scanner in question is a square plate suspended by torsion beams within a frame that is itself suspended by another pair of torsion beams. The plate and frame are suspended above the substrate, which has four stationary electrodes defined in the four quadrants of the plate as shown in Fig. 35.25. To actuate the mirror with increased linearity, a bias voltage V_{bias} was applied between each electrode and the plate. Independent differential control voltages are superimposed on the bias voltage supplied between each electrode and the plate. The driving voltages are described by two independent differential voltages such that $V_{diff1} = (V_x + V_y)/2$, $V_{diff2} = (-V_x + V_y)/2$, $V_{diff3} = (-V_x + -V_y)/2$ and $V_{diff4} = (V_x + -V_y)/2$. A second approach taken to improve the linearity was to consider the shape of the mirror, because of the geometric relationship that determines the net electrostatic torque. They considered such simple geometries as square, diamond (square rotated by 45), and a circular plate, as shown in Fig. 35.26, but more complex shapes could be considered. The square plate is presumed to have worse linearity because as the plate rotates the corners deflect toward the control electrodes, which increases the applied torque and further distorts the shape of the mirror. This suggested the removal of the corners could contribute to increased linearity and reduced distortion of the mirror surface. They found the circular plates reduced the distortion by 50% over the rectangular and diamond shaped plates, which is significant for the optical performance. The authors defined distortion as the normalized angle deviation from the ideal value. It is normalized relative to the maximum scan angle. *Nadal-Guardia* et al. [35.70] have described extending the range of travel by using current drive methods instead of voltage drive.



Fig. 35.25 Two degree-of-freedom torsional electromechanical actuator with a rectangular plate and a stationary electrode divided into four sections

35.2.4 Electromechanics of Beams and Plates

The basic understanding of electromechanics and pull-in phenomena has been developed around the simple parallel plate capacitor model developed above. Many MEMS designers innately understand that the electrostatic force is proportional to the square of the voltage, is inversely proportional to the square of the gap, and



Fig. 35.26 Alternate two degree-of-freedom torsional, electromechanical actuators with diamond and circular plates

that the plate will pull in after displacing 1/3 of the gap. While this is good to first order, it is not adequate for the electromechanical design of other structures such as cantilevered beams/plates, beams/plates with multiple supports, plates with torsional supports, and other structures.

O'Brien et al. [35.71] and *Choi* and *Lovell* [35.72] have studied the electromechanics of cantilever beams by presenting two improved models for the cantilever beam electrostatic actuators. In both cases, the cantilever beam is a homogeneous material anchored to the substrate at one end and otherwise freely suspended along its length, which is supported above a stationary electrode. The new models are compared to the parallel plate capacitance model and a simple extension of the parallel plate model to a cantilever beam. The cantilever beam model uses a simple cantilever of width, W, length, L, thickness, T, and initial air gap of Z_0. The parallel plate capacitance model is based on a capacitance determined by the length and width of the beam. The beam deflection was represented by the displacement function of a beam with a force applied at the beam tip. The beam spring constant was determined by the ratio of the force at the beam tip to the displacement at the beam tip (maximum displacement). The capacitance was determined by integrating the parallel plate capacitance for a differential length element along the length of the beam, where the beam gap is defined by the initial gap in the mechanical displacement function. This showed the beam tip displaced 45% of the initial gap before pull-in occurred. In this case the pull-in voltage can be expressed as a function of the beam's Young's modulus E, cross-sectional moment of inertia I, length L, and width W, the initial gap Z_0, and the dielectric constant in the air gap as

$$V_1 = \sqrt{\frac{18EIZ_0^3}{5\varepsilon_0 L^4 W}} = 0.5477\sqrt{\frac{ET^3Z_0^3}{\varepsilon_0 L^4}} \quad \text{(Volts)}\,. \tag{35.53}$$

In the first improved model, the cantilever beam is defined by the same characteristics, but the electrostatic force acting along the length of the beam is replaced by an equivalent bending moment M applied at the beam tip. The beam displacement was determined for a uniform, homogeneous beam with a bending moment applied at its end. The beam's spring constant was determined by the ratio of the force at the beam tip and the displacement at the beam tip. The capacitance was determined by integrating the parallel plate capacitance for a differential length element along the length of the beam, where the beam gap is defined by the initial gap in the mechanical displacement function. This model showed the beam tip displacement was approximately 46% of the initial gap before pull-in occurred. In this case the pull-in voltage is

$$V_2 = \frac{43}{50}\sqrt{\frac{18EIZ_0^3}{5\varepsilon_0 L^4 W}} = 0.471\sqrt{\frac{ET^3Z_0^3}{\varepsilon_0 L^4}} \quad \text{(Volts)}\,. \tag{35.54}$$

In the second improved model, the cantilever beam was defined by a rigid beam, whose anchor was replaced by a simple hinge and continuum elasticity replaced by an equivalent spring at the beam's free end. Three new variables were introduced to describe the behavior in terms of radial coordinates centered at the hinge. The two radial coordinates describe the beginning of the electrode at r_0 and the end of the beam/electrode at r_1. The angle θ was introduced to describe the angular displacement of the beam. In this model, the tip of the beam displaced 44% of the initial gap before pulling into the substrate. The pull-in voltage is estimated by (35.55) or (35.56) where r_0 and r_1 have been replaced by 0 and L.

$$V_3 = \frac{11}{25r_1^2}\sqrt{\frac{77ET^3Z_0^3}{25\varepsilon_0\left[\frac{11(r_1-r_0)}{r_1-\frac{11}{25}r_0} - 14\ln\left(\frac{25r_1-11r_0}{14r_1}\right)\right]}}\,, \tag{35.55}$$

$$V_3 = \frac{11}{25L^2}\sqrt{\frac{77ET^3Z_0^3}{25\varepsilon_0}} = 0.4548\sqrt{\frac{ET^3Z_0^3}{\varepsilon_0 L^4}} \quad \text{(Volts)}\,. \tag{35.56}$$

As expected, the dependence on parameters, such as Young's modulus, beam thickness, beam length, initial air gap, and the air gap dielectric constant is the same for all cases presented. The difference in the three models is the coefficient of the pull-in voltage function and the tip deflection at pull-in. The coefficients of the pull-in voltage predictions are 0.5479, 0.471 and 0.4548, respectively. The beam tip deflected 45%, 44%, and 46% of the initial gap before pull-in occurred. This is in contrast to the parallel plate model that predicts the plate deflection will be 33% of the initial gap before pull-in. By comparison to experimental test results, the models presented in (35.54) and (35.56) were more accurate at predicting the pull-in voltage for cantilever beams. The parallel plate electromechanics model had greater error and under-predicted the pull-in voltage. The model represented by (35.53) over-predicted the pull-in voltage with greater error than either of (35.54) or (35.55). The beam models predicted more accurately for wider beams, which means they are better applied to beams with dimensions representative of a parallel plate model used as a basis of the capacitance estimate. In all three cases, the beam models presented in (35.53)–(35.55) predicted poorly the pull-in voltage for narrow beams, which are dominated by the effects of nonuniform fringing fields and not the uniform parallel plate fields. The typical application of the parallel plate capacitor model is to geometries with a width W and length L that are much greater than the capacitor gap Z_0 ($W \gg Z_0$, $L \gg Z_0$; where greater than a factor of 10 is a common rule of thumb). In Fig. 35.27, two capacitors are shown such that in one case the plate dimensions are much greater than the gap, and in the second case the plate dimensions are much smaller than the gap. When the plate dimensions are much larger than the gap, the uniform fields in the gap dominate the capacitive coupling. A small contribution to the capacitive coupling comes from the *fringing* fields at the edge of the plate (or the perimeter of the plate in three dimensions). As shown in Fig. 35.6, the fringing fields could depend on the thickness of the plate. When the plate dimensions are of the same order as the gap, the fringing fields may dominate or be of the same order as the contribution of the uniform field in the gap. This is the nature of the narrow cantilever beams that were not predicted well by a parallel plate capacitor model. A correction can be introduced to the parallel plate model to approximate the contribution of the fringing fields. This approximation is often referred to as the Love approximation.

Segmented Control of Electromechanical Membrane Deformation

Wang and *Hadaegh* [35.62] describe the electrostatic actuation of a deformable membrane mirror with segmented electrodes on the substrate. The membrane mirror, in this case silicon nitride with a conductive film, was suspended above the substrate containing the segmented electrode. The segmented electrodes are defined along angular and radial pattern. A specified voltage can be applied between the membrane and each electrode segment to develop a specific deformation for the mirror. This increases the complexity of the control system but also the flexibility of controlling the shape of the mirror surface. The optical properties could be optimized by individual characterization of membranes or by feedback from the optical output. This basic concept was also applied by *Zhang* and *Dunn* [35.73] who were able to linearize the voltage–deflection relationship by tailoring the shape of the electrodes and the beam structure used to support them.



Fig. 35.27 Cross-sections of wide and narrow electrodes showing uniform electric fields in the gap and fringing fields at the edges (perimeter)

35.2.5 Electromechanics of Torsional Plates

The plate suspended by a torsional suspension instead of bending is the final configuration to be considered in terms of electromechanics. The electrostatic torsional plate has many applications, such as optical mirrors [35.58,63] and accelerometers [35.55]. The plate will define the optical surface of the mirror, the moveable plate of a varactor, or the proof mass of an accelerometer. It will be conductive or have a conductive film so that it can couple electrostatically to a stationary plate on the substrate. The moveable plate will be suspended by a torsional suspension such that the bending modes are suppressed and the primary kinematic mode is rotation of the plate. The variable capacitive coupling is used in two ways. First, it is used for actuation by applying a voltage between the moveable plate and a stationary plate. Second, it is used for sensing or use of the variable capacitance. Both actuation function and the variable capacitance function can be present in a device. The key elements of interest are the voltage-displacement function and the pull-in voltage.

Small Angular Deflection Approximation

Degani et al. [35.74], *Xiao* et al. [35.75], and Nemirovsky et al. [35.66] have considered the torsional electrostatic actuator from an analytical perspective with comparison to experimental results and other modeling results. The effective torsional spring constant is determined from the torque-twist angle relationship, where the torque is the electrostatic torque. The electrostatic torque is developed for both small and large angle cases. The pull-in angle and pull-in voltage are determined from the pull-in equations for voltage control (35.42, 43) and charge control (35.39, 40). Their method is an improved approach for modeling torsional electrostatic actuators over approximations involving parallel plate models and effective spring constants as they have shown by comparison to experimental measurements. The torsional plate considered is suspended by a torsional suspension, whose axis of rotation defines a gap of d. It is assumed the plates extend into the page (z-axis) by a depth b and have a total length a. The torsional plate electrostatic actuator is shown in Fig. 35.28. The solution assumes the tilted plates are semi-infinite, ignoring the effects of fringing fields hence their corrections, and are tilted by angles that satisfy the small angle approximation ($\tan\alpha \approx \sin\alpha \approx \alpha$ and $\cos\alpha \approx 1$). The capacitance is:

$$C(\Theta) = \frac{\varepsilon_0 b}{\alpha_{\max}} \frac{1}{\Theta} \ln\left(\frac{1}{1-\Theta}\right) , \qquad (35.57)$$

where $\alpha_{\max} = d/a$ and $\Theta = \alpha/\alpha_{\max}$.

The capacitance function and the linear relationship for the elastic restoring force ($F_M = K\,a$) are used to develop the electrostatic and mechanical energy function to substitute in the pull-in equations. For voltage controlled actuation, the pull-in parameter is developed from (35.42) to yield:

$$4 + \frac{5\Theta_{PI} - 4}{(1-\Theta_{PI})^2} - 3\ln(1-\Theta_{PI}) = 0 . \qquad (35.58)$$

Equation (35.58) is solved numerically to show the voltage-controlled pull-in angle is $\Theta_{PI} \approx 0.44$. The pull-in angle is substituted in (35.43) to determine the voltage controlled pull-in voltage:

$$V_{PI} = \left(\frac{0.827 K \alpha_{\max}^3}{\varepsilon_0 b}\right)^{1/2} . \qquad (35.59)$$

The charge-controlled pull-in parameter relationship is determined by substituting the electrostatic energy and mechanical energy functions in the charge-controlled pull-in parameter (35.39). This provides the nonlinear relationship for the charge controlled pull-in angle:

$$\ln(1-\Theta_{PI}) - \frac{\Theta_{PI}}{(1-\Theta_{PI})^2} - \frac{2\Theta_{PI}^2}{(1-\Theta_{PI})^2 \ln(1-\Theta_{PI})} = 0 . \qquad (35.60)$$

The charge-controlled pull-in angle is given by $\Theta_{PI} \approx 0.71$. The pull-in angle is used in the charge-controlled pull-in equation (35.40) to determine the pull-in charge relationship:

$$Q_{PI} = (1.798 K \varepsilon_0 b \alpha_{\max})^{1/2} . \qquad (35.61)$$



Fig. 35.28 Cross-section of a torsional actuator with a uniform cross section into the page showing the angular degree-of-freedom, α; plate length, a; and initial gap, d

Large Angular Deflection and Plate Geometry

Nemirovsky and *Bochobza-Degani* [35.66] have extended the work to the case of large angle deflections, which included using the trigonometric relationship in the capacitance function and a nonlinear relationship for the mechanical spring constant. These nonlinear relationships were used in the voltage-controlled pull-in equation. In addition, their methodology was extended to planar plates with different shapes (Fig. 35.29). They specifically considered triangular plates (the apex of the triangle is near the axis of rotation), a reversed triangular plate (the triangle apex is at the distal end of the plate), a square plate (with the rotational axis on the edge of the plate), and a circular plate (with the axis of rotation passing through a point on the perimeter and the opposite point on the perimeter defining the most distal point of the plate). Only simple geometries were considered, and their methodology can be applied to other more general geometry. The rectangular plate torsional, electrostatic actuator will provide the lowest actuation voltage relative to a fixed plate length. The reversed triangular plate has proved beneficial with regard to pixel area in mirror application and has been able to provide a higher torque for a specific plate length.

35.2.6 Leveraged Bending

As discussed, when the actuation electrode spans the entire length of the actuator, the stable controllable travel distance of the actuator plate is severely limited due to the pull-in instability. One can get around the problem of



Fig. 35.29 Rectangular, triangular, reverse triangular, and circular plates are shown suspended by torsion beams for application to electromechanical mirrors or other actuators

pull-in by applying an electrostatic force to only part of the structure and using the rest of the structure as a lever to move the structure through a larger range of motion. This concept, referred to as leveraged bending [35.76], is shown schematically in Fig. 35.30 for a cantilever beam. The key idea is that the portions of the beam above the electrodes do not deflect far enough to violate the pull-in limit. The concept can be applied to other microstructure shapes and support conditions, but for fixed-fixed beams, the effect can be diminished by tensile residual stresses [35.76].

35.2.7 Electromechanics of Zipper Actuators

The design requirements for electromechanical actuators usually require minimizing the actuation voltage but maximizing the largest displacement. With the parallel plate actuator, be it a plate, beam, or torsional plate, the pull-in voltage is reduced by minimizing the air gap, but this limits the maximum displacement. Actuators with a zippering behavior have been implemented to achieve greater deflections for a lower actuation voltage. In one example (see [35.77, 78]), a plate is suspended by a torsional suspension. A long slender electrode extends from the plate and terminates with plate-like area. This electrode is supported above the fixed substrate electrode by a largely uniform gap. A voltage is applied between the substrate electrode and the extended electrode, such that the plate-like area is first pulled into the substrate. As the actuation voltage is increased, the long-slender electrode continues to collapse against the substrate electrode until a desired maximum deflection is achieved or until the drive voltage becomes impractical. This is the so-called zippering effect, which has been described for a motion perpendicular to the substrate. This uniform gap scenario is not the best suited for minimizing the pull-in voltage, so other configurations such as the curved electrode actuator have been proposed and applied to such devices as a switch and optical shutters as described by *Jin* et al. [35.79].



Fig. 35.30 Illustration of the concept of leveraged bending to increase the range of stable motion

Legtenberg et al. [35.80, 81] have described the basic operating features of the curved-electrode actuator. These actuators will provide large deflections in the plane of the substrate. The curved electrode actuator is composed of a stationary electrode and a compliant, moving electrode. The stationary electrode has a shape described by the function $s(x)$ shown in (35.62) and Fig. 35.31, which is written in terms of the maximum gap between electrodes $\delta_{\max}$, the length of the electrode L, the distance along the length of the electrode x, and the polynomial order of the curve n.

$$s(x) = \delta_{\max}\left(\frac{x}{L}\right)^n . \qquad (35.62)$$

A necessary feature of the curved electrode actuators and zipper actuators, in general, is the contact between the moving and stationary electrodes. Without due consideration, these electrodes will short upon contact and damage the actuator. Two isolation solutions are implemented to prevent the shorting scenario. First, a continuous insulation film can be added between the electrodes to prevent them from shorting. In this case, the simplest solution is to add the insulation layer to the fixed, curved electrode. The alternative solutions include adding the insulating film to only the moving electrode or to both the moving and stationary electrodes. If the insulation is added to the moving electrode, it will become part of the stiffness of the beam. A second solution would be to add discrete, isolated contact bumpers that are made from the same conducting material as the moving electrode. As it closes the gap, the moving electrode makes contact with the isolated bumpers but not the actuation electrode. These have their operational differences as described by *Legtenberg* et al. [35.81]. Three other issues that must be considered during the design of a curved electrode actuator or zipper actuators are dielectric charging, stiction, and dielectric breakdown.

Legtenberg et al. [35.81] found that as the polynomial order increased for the electrode curve, the pull-in voltage will decrease for about the same maximum displacement. This means larger displacements can be achieved for lower voltages when compared to the parallel plate actuator. Once the moving electrode is pulled in to the curved electrode, the moving electrode will collapse to the maximum displacement. It was shown for polynomial curves of order above $n = 2$ that the maximum tip deflection becomes stable because of the geometric constraints provided by the curved electrode. This means to achieve the maximum displacement with the lowest pull-in voltage, a polynomial curve of order $n = 2$ should be specified. For polynomial curves with $n > 2$, stable continuous deflection along the curved electrode can be implemented with the maximum deflection occurring at lower voltages for polynomial orders just above two. If an approximate linear range of operation is desired (i. e. the tip deflection versus voltage is approximately linear), the higher order curves ($n > 2$) are desired. *Legtenberg* et al. [35.81] analyzed the curved electrode problem by application of analytical energy methods, specifically the Rayleigh–Ritz method and of three-dimensional self-consistent electromechanical numerical simulations using CoSolve-EM in MEMCAD (now integrated into CoventorWare). From an energy perspective, the total potential energy U_T is determined in terms of the mechanical energy associated with the strain energy of bending and the electrostatic energy stored in the electric field. For the curved electrode of Fig. 35.31, the total potential energy is:

$$
\begin{aligned}
U_{\mathrm{T}} &= U_{\mathrm{M}} + U_{\mathrm{E}} \\
&= \frac{1}{2}\int_0^L EI\left(\frac{\mathrm{d}^2 w\,(x)}{\mathrm{d}x^2}\right)^2 \mathrm{d}x \\
&\quad - \frac{1}{2}\int_0^L \frac{\varepsilon_0 h V^2}{\frac{d}{\varepsilon_r} + s(x) - w(x)}\,\mathrm{d}x\,,
\end{aligned}
\tag{35.63}
$$

where L is the beam length, E is the beam's Young's modulus, I is the beam's cross-sectional moment of inertia, h is the thickness of the beam, V is the voltage applied between the beam and electrode, d is the initial gap at the start of the electrode, ε_0 is the permittivity of free space, and $w(x)$ is the beam's deflection curve. The next step in the solution of this problem is to determine an admissible trial function that satisfies the beam boundary conditions and can adequately approximate the solution. In this case the deflection curve for a uniformly loaded cantilever beam is chosen as the trial function:

$$
\omega(x) = cx^2\left(6L^2 - 4Lx + x^2\right) = c\,f(x)\,, \tag{35.64}
$$

where c is a constant to be determined for specific cases.

The approach of Nemirovsky et al. [35.66] can be taken by substituting the potential energy functions in the voltage-controlled pull-in equations. The simultaneous solution of the pull-in equations will result in the pull-in voltage and an implicit equation in terms of the constant c at pull-in. The pull-in voltage relationship is



Fig. 35.31 Curved electrode shape curve shown as a function of order of the curve n

$$
V_{\mathrm{PI}}^2 = \frac{EI}{\varepsilon_0 h}\,\frac{\int_0^L \left(\frac{\mathrm{d}^2 f(x)}{\mathrm{d}x^2}\right)^2 \mathrm{d}x}{\int_0^L \frac{f^2(x)}{\left[d/\varepsilon_r + s(x) - c_{\mathrm{PI}} f(x)\right]^3}\,\mathrm{d}x}\,. \tag{35.65}
$$

The implicit equation to determine the coefficient of the beam deformation function is

$$
\begin{aligned}
&\int_0^L \frac{c_{\mathrm{PI}} f^2(x)\,\mathrm{d}x}{\left[d/\varepsilon_{\mathrm{r}} + s(x) - c_{\mathrm{PI}} f(x)\right]^3} \\
&\quad = \int_0^L \frac{f(x)\,\mathrm{d}x}{\left[d/\varepsilon_{\mathrm{r}} + s(x) - c_{\mathrm{PI}} f(x)\right]^2}\,.
\end{aligned}
\tag{35.66}
$$

DeReus [35.82] designed the curved electrode actuator to convert the curvilinear motion into a translational motion at the tip of the moving electrode. The transformation is accomplished by a folded spring that connects the electrode to the body that will be translating. A solid model of this actuator design is shown in Fig. 35.32. A pull-in analysis was performed with the results before pull-in and after pull-in presented in Fig. 35.33. This shows that a 60 µm translation was accomplished



Fig. 35.32 Solid model of a curved electrode actuator with a folded suspension showing the curved electrode δ and the actuator beam length L



Fig. 35.33 Results of electromechanical pull-in analysis showing curved electrode actuator before and after pull-in has occurred



Fig. 35.34 Beam tip deformation as a function of electrode potential and δ for a suspension with a single fold

with this particular design, which has a twofold flexure and could have application as a optical shutter or VOA. In Fig. 35.34, electrode tip displacement is shown as a function of electrode voltage and electrode curve δ for a onefold flexure design. The displacement as a function of electrode potential and curve δ is shown for a twofold flexure in Fig. 35.35.



Fig. 35.35 Beam tip deformation as a function of electrode potential and δ for a suspension with a doubly folded suspension

35.2.8 Electromechanics for Test Structures

Electromechanics test structures are an important contributor to the development of microsystems products as they are used to extract information about material properties of thin films for specific process parameters. They are also used to monitor the material property variation during the fabrication process. In this case, they are distributed around the wafer on specific test die or they may be included in the dicing streets of more mature processes. These distributed test structures enable the manufacturer to track the variation in material properties with its associated within-wafer variation, wafer-to-wafer variation, and lot-to-lot variation. Another application of test structures is to characterize the impact of the first level packaging on the performance of the product. With all the critical information being extracted from the test structures, it is important for the information to be easy to interpret. Test structures have been developed that involve electrical, optical, and mechanical interrogation of the structure, but these are not easily instituted at all levels of characterization. The purely electrical test structures offer simple evaluation at the wafer, die, and package level so manufacturers often prefer them. The most common electrical test structures used for extracting information on mechanical properties involve electromechanics, of course. This section has provided a basis for interpreting and modeling the behavior of specific test structures, such as a homogeneous cantilever beam, and can be extended to other structures.

Osterberg and *Senturia* [35.83] describe in detail the application of electromechanics to the extraction of mechanical properties for microsystems design. They labeled their test structures as M-TEST for mechanical test structure. Their test structures comprised arrays of cantilever beams, fixed-fixed beams, and clamped, circular plates of various lengths, widths, or diameters. With these test structures, they demonstrated the extraction of important mechanical properties such as Young's modulus, plate modulus, and the residual film stress. Why choose an electromechanics test structure unless for the breadth and ease of application? An additional reason is the inherent instability that has been described as the pull-in of an electromechanical structure. The pull-in voltage is very distinct and can be measured in terms of a single parameter, the pull-in voltage. Given a control range of pull-in voltages for different structural layers in the manufacturing process, the pull-in parameter can be used as a simple control parameter.

Osterberg and *Senturia* [35.83] describe the methodology for extracting the mechanical properties. Their methodology includes the measurement of plan-view dimensions (i. e., width and length), out-of-plane curvature, pull-in voltage, film thickness, and air gap. With these measured parameters, the mechanical properties can be extracted. Their extraction methodology includes general closed form expressions for pull-in voltage that depend on the material properties and geometry of a homogeneous, isotropic material.

35.2.9 Electromechanical Dynamics: Switching Time

Switching time is an important factor in the design of such electromechanical devices as electrical or optical switches. The switching time analysis requires consideration of the dynamic equations representing the device and the electrical source. *Castaner* et al. [35.84–86] have considered the optimization of the speed-energy product. In this case, a parallel plate electrostatic actuator is described by an equivalent mechanical circuit that includes the mass m, the damping b, and the spring k, and a variable gap g. The variable gap depends on the initial gap g_0 and the displacement of the moving electrode x, such that $g = g_0 - x$. In the parallel plate, variable gap model the damping is described by squeeze film damping. (Other electrostatic actuators that move parallel to the substrate with variable gaps defined by groups of moving and stationary fingers.) In these cases, the damping model will need to include squeeze film damping and shear flow damping (Couette or Stokes Flow models). The electrical source is modeled as a voltage source and a source series resistance. A schematic of the model is shown in Fig. 35.36.

The equivalent electrical circuit of the parallel plate electrostatic actuator is modeled by (35.67), where V_s is the source voltage, V is the voltage across the variable capacitance, R is the series source resistance, and Q is the charge on the capacitor plates

$$\frac{V_\mathrm{s}}{R} = \frac{V}{R} + \frac{\mathrm{d}Q}{\mathrm{d}T} \,. \tag{35.67}$$

The equivalent mechanical circuit is described by:

$$m\frac{\mathrm{d}^2X}{\mathrm{d}T^2} + b\frac{\mathrm{d}X}{\mathrm{d}T} + kX = \frac{Q^2}{2C_0G_0} \,. \tag{35.68}$$

Equation (35.68) includes the sum of the inertial force, the damping force, the spring force, and the electrostatic force. Equation (35.68) is written in terms of the mass of the moving capacitor plate, m; the damping coefficient due to squeeze film damping, b; the elastic constant of the spring by which the capacitor plate is suspended, k; the charge on the capacitor plate, Q; the initial gap, G_0; and the initial capacitance, C_0. The initial capacitance is written in terms of the area of the capacitor A, the dielectric constant of the capacitor air gap ε, and the initial gap:

$$C_0 = \frac{\varepsilon A}{G_0} \,. \tag{35.69}$$

The dynamics of the parallel plate electrostatic actuation were divided into four events. The first occurrence is a short charging time for the capacitor. The second phase is the acceleration phase, which defines the rapidly increasing velocity of the mass, but the



Fig. 35.36 Lumped parameter model of the parallel plate electromechanical actuator including damping and series resistance for dynamic analysis

position is still close to the initial equilibrium position. The third phase is the damping phase, defined by the velocity reaching a maximum, then decreasing due to the increased damping, and then finally increasing due to the increasing electrostatic forces as the gap closes. The fourth and final phase is the pull-in phase, characterized by a rapidly increasing velocity. *Hung* and *Senturia* [35.76] have described generating efficient dynamical models from a minimal set of finite element simulations. *Pons-Nin* et al. [35.87] have described the behavior of pull-in voltage and pull-in time for electromechanical actuators with current drives.

35.2.10 Electromechanics Issues: Dielectric Charging

Electrostatic actuators are operated in three different regimes depending on the application. In the first regime, the electrostatic actuator is operated over the voltage range that does not include the pull-in voltage. In this case, the actuated element does not contact the opposing substrate. In the second regime, the electrostatic actuator is operated through a voltage range that does include the pull-in voltage ($V_{\mathrm{act}} \geq V_{\mathrm{PI}}$). In this case, the desired response is to establish contact with or without some overdrive to achieve greater contact force or other response parameter. In the third regime, the electrostatic actuator is operated through a voltage range beyond the pull-in voltage. This is characteristic of electrostatic zipper actuators. In this case, the operating voltage is programmed to quickly establish pull-in, thereby contact, then the actuator operates in a range above the pull-in voltage ($V_{\mathrm{PI}} < V_{\mathrm{act}}$). In all three regimes, dielectric isolation layers are considered to prevent shorting between actuation electrodes. For the first and second case, the use of the insulating material is a preventative measure to protect against electrode shorting during an unintentional overdrive of the actuator. It is preventative because the actuation electrodes are not intended to touch. In the third case, the gap separating the moving and stationary actuation electrodes is reduced to zero so that an insulating layer is required. The insulating layer may be patterned or unpatterned.

The third regime defines the touch mode electrostatic actuators. *Cabuz* et al. [35.88] have described many of the failure modes that can be observed with the touch mode electrostatic actuators and that should be addressed during the design of the actuator and process. The observations and failure modes included: 1) a significant difference between the experimental actuation voltage (DC) and the theoretical actuation voltage, 2) a closed state electrostatic pressure lower than predicted, 3) an actuation voltage that increases with each subsequent cycle until electrical breakdown occurs, 4) actuator vibration observed between an open and a closed state, 5) actual release voltage is higher than theoretical, but the electrostatic forces should be much higher in the closed state such that the release voltage is always lower than the pull-in voltage, 6) the actuator remains closed temporarily after shorting, 7) permanent stiction will occur when in the closed state for a long period of time, 8) permanent stiction occurs after many actuation cycles.

Wibbeler et al. [35.89] have analyzed this problem in terms of one of the contributing factors, the accumulation and storage of localized charge in dielectrics. The common dielectrics in microsystems devices are SiO_2 and Si_3N_4, which show low mobility for surface charges and provide trap sites for positive or negative charge within their volume and at interfaces. *Kubo* et al. [35.90] showed this charge can be produced by the fabrication process by contact electrification, and by gas discharge in the air gap (the case focused on that by *Wibbeler* et al. [35.89]), and static electrification during handling (ESD). The contact electrification created electrical charge through the mechanical contact of two materials with different work functions and the separation of the two materials.

To understand the impact of the accumulated charge, *Wibbler* et al. [35.89] considered the impact of stored surface charge on the electrostatic force acting on a simple parallel plate capacitor. In Fig. 35.37, a simple capacitor is considered with a dielectric (ε_{d}) filling part of the air gap (ε). The dielectric has a surface charge of $\sigma_{\mathrm{s}}(x, y)$. The capacitor plates carry charge shown as σ_1 and σ_2, which are provided by the battery, of voltage V, connected across the capacitor plates. The thicknesses of the dielectric and air gap are d_{d} and d, respectively. The force was estimated from the applied voltage and from the offset voltage due to the accumulated surface charge. The force acting on the capacitor plate as a function of the applied voltage, V; the offset



Fig. 35.37 Parallel plate capacitor with dielectric and parasitic charges

voltage, V_s; and the capacitance, C, is:

$$F = \frac{\mathrm{d}C}{\mathrm{d}z} \int_A \frac{[V - V_s(x, y)]^2}{2} \mathrm{d}A \, . \qquad (35.70)$$

The offset voltage is shown in (35.71) as a function of the surface charge; the thickness of the dielectric, d_d; the dielectric constant, ε_d; or the dielectric's contribution to the total capacitance, C_d. The capacitance of the dielectric layer, per unit area, being defined as $C_d = \varepsilon_d / d_d$.

$$V_s = -\sigma_s(x, y) \frac{d_d}{\varepsilon_d} = -\frac{\sigma_s(x, y)}{C_d} \, . \qquad (35.71)$$

Electromechanical Pull-In with Dielectric Charging

Nemirovsky et al. [35.66] and *Chan* et al. [35.91] studied the effect of residual charge at the interface of a dielectric and the air in the capacitor gap. With the dielectric in the capacitor gap and the residual charge, the total energy for the actuator is:

$$U_T = \frac{1}{2}Kz^2 + \frac{Q_{res}^2}{2(C(z) + C_d)} - \frac{C(z)C_d}{2(C(z) + C_d)} V^2 \, . \qquad (35.72)$$

In (35.72), Q_{res} is the residual charge, $C(z)$ is the air gap capacitance, and C_d is the dielectric capacitance. From the total energy, the pull-in parameter and pull-in equations (35.42) and (35.43) can be solved for the pull-in parameter ζ_{PI} and pull-in voltage V_{PI}:

$$\varsigma_{PI} = \frac{1}{3}\left(1 + \frac{1}{\delta}\right) , \qquad (35.73)$$

$$V_{PI} = \left[\frac{8Kz_{max}^3}{27\varepsilon_0 A}\left(1 + \frac{1}{\delta}\right)^3 - \frac{Q_{res}^2}{C_d^2}\right]^{1/2} . \qquad (35.74)$$

In (35.73), ζ_{PI} is the ratio z/z_{max} and δ is the ratio $\varepsilon_d z_{max}/z_d$. Equation (35.74) shows that the dielectric layer will increase the pull-in voltage and the residual charge will lower the pull-in voltage. It can be seen that the residual charge does not impact the normalized pull-in coordinate shown in (35.73).

Test structures were fabricated to verify the shift predicted by (35.70) that would result with a dielectric in the air gap. Test structures with a dielectric did show a shift in the voltage–deflection curve, whereas a shift was not observed when a dielectric was not present. A shift of −25 V was observed. Following electrostatic discharge events, the offset voltages of −210 V and 145 V were observed during different phases of a charge-discharge cycle. This demonstrates the significant bias the accumulated surface charge can create. As a result, *Wibbler* et al. [35.89] did not recommend trying the fix shorting by adding dielectric films over the electrodes. They did recommend estimating the influence of accumulated charge on the response of the device being designed. Instead of complete dielectric film coverage of an electrode, they recommended patterning the dielectric such that it was limited to the edges of the electrodes or patterned at locations that will touch first. By patterning small areas of insulation, the surface area available to store charge is smaller and the distance to the electrode is shorter for more timely dissipation of stored charge.

Cabuz et al. [35.88] identified the effects of humidity, DC or AC driving voltage, and SAM coatings on the performance of electromechanical actuators. With a DC operating voltage, the devices operated as expected below 35% RH except in dry air or dry N_2. In the dry environment the actuator would temporarily remain closed, would remain closed after high fields are applied, or would remain closed after a high number of cycles. When operated above 35% RH, the DC voltage was higher than expected, the closed state electrostatic pressure was lower, the actuator did not release when expected, the actuator vibrated, and the voltage increased with subsequent cycles. When an AC actuation voltage is used the actuators operated up to 55% RH. At higher RH, the actuation voltage increased. The dry condition operation was improved with AC driving compared to DC operation. AC voltage control is recommended for eliminating RC effects but cannot overcome the effects of humidity. To avoid the effects of humidity, two SAM coatings (octadecyltrichlorosilane (OTS) and perfluorodecyltrichlorosilane (PFTS)) were tried to influence the hydration of the surfaces. The OTS eliminated the effects observed for uncoated samples up to a 95% RH level for both DC and AC voltages. The PTFS improved operation up to 95% RH for AC voltages and 70% RH for DC control voltages. The residual in-use stiction was determined to be associated with accumulated and trapped charge on the surfaces or at interfaces.

35.2.11 Electromechanics Issues: Gas Discharge

As described in previous sections, the electromechanical actuation of a microstructure is performed by applying a voltage across two plates. The two plates can be defined by two conductors (e.g. Al to Al), by semiconductors (e.g. polysilicon), or by a combination of a conductor and a semiconductor (e.g. Al and polysilicon). When these two plates (or other similarly described structures) are fabricated in proximity with each other, they are usually fabricated with an "air" gap less than 10 µm. With the electrostatic actuators, a small gap is desirable to minimize the voltage required for actuation.

The presence of small gaps in microsystems devices has prompted the further investigation of electrical breakdown in air and other ambient conditions at small gaps (i. e. less than 50 µm). *Slade* and *Taylor* [35.92] have demonstrated that breakdown in small gaps is defined by three regimes: less than 4 µm, 4 to 6 µm, and greater than 6 µm. In the first case, the breakdown event follows the behavior for a vacuum breakdown process at a larger gap. In the last case, the breakdown follows the behavior of Paschen's law for breakdown in air. The middle case of gaps between 4 and 6 µm, the breakdown process is in a transition from following the vacuum breakdown process to following the Paschen curve. In this case, the breakdown voltage is lower than predicted in either case, which indicates significant contributions from factors in both cases. The deviation from Paschen's curve was observed by *Torres* and *Dhariwal* [35.93] for gaps less than 4 µm.

The goal of this section is to describe some basic breakdown principles that can be used to determine whether or not a particular design will break down during an actuation event. Different processes will be considered for different gap regimes so that breakdown estimates can be made.

The vacuum breakdown region is characterized by a breakdown voltage that is a function of the gap separating the two electrodes. This contrasts with the breakdown behavior that follows the Paschen curve, which shows electrode gap-pressure product dependence. The breakdown voltage in vacuum is

$$V_B = K_V t_g \,. \tag{35.75}$$

Equation (35.75) shows the breakdown voltage V_B is proportional to the gap t_g where the proportionality constant is $K_v = 97\,\mathrm{V/\mu m}$ for data from many sources as indicated by *Slade* and *Taylor* [35.92]. The breakdown data for vacuum was determined for electrode gaps between 35 and 200 µm. For electrode gaps between 0.2 and 40 µm in air, the proportionality constant was between 65 and 110 V/µm.

The electric field at the surface of the electrode is a critical parameter for determining breakdown in vacuum. This is estimated by the ratio of the voltage between the electrodes V and the gap between the electrodes t_g with a modification factors β_g. β_g is a geometrical enhancement factor that captures the field enhancement due to the macroscopic geometry:

$$E_g = \beta_g V / t_g \,. \tag{35.76}$$

The geometrical enhancement factor can be determined by performing finite element analysis to determine the macroscopic electric field as a function of the electrode gap for the electrode geometry under consideration. The geometric enhancement factor is determined from the ratio of the macroscopic electric field E_g, from finite element simulations, to the electric field estimated by V/t_g [35.92, 94]. The estimated electric field, V/t_g, can be used as a reasonable approximation when the electrode gap is much smaller than that radius of curvature of the cathode electrode. If this is not the case, the geometric enhancement factor needs to be estimated from numerical analysis such as finite element or boundary element methods. The geometric enhancement factor is shown, by *Slade* and *Taylor* [35.92], to be between 1.01 and 1.57 for gaps ranging from 0.2 to 40 µm, respectively, for the geometry of a needle cathode and a plate anode.

A second enhancement factor is attributed to the microscopic field enhancement due to the surface roughness of the electrodes. The electric field containing the effects of the geometric enhancement and the microscopic enhancement is:

$$E = \beta_m \beta_g V / t_g \,. \tag{35.77}$$

In (35.77) β_m is the microscopic enhancement factor. The total enhancement factor is $\beta_g \beta_m$, which can have a range of 100 to 250 for polished electrodes [35.95].

Following the estimate of the electric field at the surface of the electrodes, the current density for the field emission of electrons is calculated. This current density j_{FE} is described by the Fowler–Nordheim equation, which depends on the electric field E, the work function of the electrode material ϕ, and the dimensionless parameters of $t(y)$ and $\nu(y)$, where y is a parameter defined as $3.79 \times 10^{-5} \sqrt{E}/\phi$. Typically, $t(y)$ is one. $\nu(y)$ is given by $0.956 - 1.06y^2$. The Fowler–Nordheim equation is presented in (35.78) with j_{FE} in A/m², E in V/m, and ϕ in eV.

$$j_{FE} = \frac{1.54 \times 10^{-6} E^2}{\phi t(y)^2} \exp\left(\frac{-6.83 \times 10^9 \phi^{3/2} \nu(y)}{E}\right) . \tag{35.78}$$

Equation (35.78) can be rewritten with E substituted from (35.77) and the current density replaced by an emission current I_e and the area A_e of a microprojection where the emission occurs. Equation (35.78) is shown rewritten in (35.79), such that the slope from the Fowler–Nordheim plot will provide the field enhancement factor as shown in (35.80) where m is the slope. The Fowler–Nordheim plot is the plot of I_e/V^2 versus $1/V$, which is constructed by measuring the voltage across the electrode gap and measuring I_e.

$$\begin{aligned}\mathrm{Log}_{10}\left(\frac{I_e}{V^2}\right) &= \mathrm{Log}_{10}\left(\frac{1.54\times10^{-6}A_e\beta^2}{\phi\, t(y)^2 t_g^2}\right)\\ &\quad -\frac{1}{2.303}\left(\frac{6.83\times10^9\phi^{3/2}t_g\nu(y)}{\beta}\right)\frac{1}{V}\,, \end{aligned} \qquad (35.79)$$

$$\beta = -\frac{2.303m}{6.83\times10^9\phi^{3/2}t_g\nu(y)}\,. \qquad (35.80)$$

For gaps larger than 6 µm, the electrical breakdown as a function of gap does follow the Paschen curve for air and does not follow the vacuum breakdown curve for these larger gaps. The electrode gap is now larger than the mean free path of the air molecules so it is expected that emitted electrons will collide with the air molecules in the gap. For these larger electrode gaps, it is assumed the electrical breakdown will follow the Townsend electron avalanche theory. A similar process is followed to estimate the breakdown. First, the electric field at the surface of the cathode electrode is estimated including the enhancement factors for geometry and surface microstructure. An estimate of the total field enhancement factor is required for this. The electric field is substituted into the Fowler–Nordheim equation (35.78) to estimate the field emission current. In this case, the emitted electrons will interact with the background gas molecules causing an avalanche in the current. The current avalanche process is described by (35.79) and (35.80), where t_g is the electrode gap, α is the first Townsend coefficient, and γ is the second Townsend coefficient. The first Townsend coefficient represents the number of electrons produced per unit distance along the direction of the electric field. The second Townsend coefficient is the number of electrons generated by secondary processes per each primary avalanche. Breakdown will occur when the denominator of the expression for current approaches zero: $\gamma\exp(\alpha t_g)$ approaches unity.

In the transition region, the breakdown voltage can be lower than predicted by the Paschen curve or vacuum breakdown. It is suggested that in this regime, the partial electron avalanche process enhances the vacuum breakdown process to lead to a lower breakdown voltage [35.92].

The choice of materials is another consideration for the design of an electrostatic microactuator. As mentioned, the electrode pairs could comprise the following combinations: conductor-conductor, conductor-semiconductor, or semiconductor-semiconductor. In *Torres* and *Dhariwal* [35.93], the breakdown voltage was measured for electrode pairs comprised of nickel, brass, or aluminum. A significant difference was not observed between the breakdown voltages of the different conductors or for the size of the electrode. At larger gaps, the breakdown voltage was different for different electrode shapes (cylindrical versus spherical) but this can be explained by the relative difference in the geometric enhancement factor for the electric field for the different electrodes. *Ono* et al. [35.96] made a comparison between electrode combinations where both a semiconductor (silicon) and a silicon–metal combination were used. In the case of a silicon electrode with a metal electrode, the breakdown voltage deviated from the Paschen curve at approximately 6 µm. It was lower than the breakdown voltage predicted by the Paschen curve and trailed off with an approximate linear dependence on the electrode gap. With the silicon as one electrode, Au/Cr or Pt/Cr was used as the second electrode but little difference was found for the different metals. With the silicon-silicon electrode combination, the breakdown voltage followed the Paschen curve for air. For similar gaps, the breakdown voltage was significantly higher for the silicon-silicon electrodes than for the silicon-metal electrode. This was true for a thin silicon film over a Cr/Pt/Cr electrode.

Another option for reducing the electric breakdown in the air gap is to introduce an insulating material over the electrode. But *Wibbeler* et al. [35.89] have demonstrated this does not solve the problem of breakdown by itself and can lead to parasitic charging of the insulator. An electric breakdown will produce a large current, as described previously, that is destructive to the electrodes without insulation. The dielectric limits the current so that the electrical breakdown event is not so destructive. *Wibbeler* et al. [35.89] demonstrated through highly chaotic behavior in the voltage–displacement response of an electrostatic actuator. It is reasoned that the local field strength at the electrode reached a magnitude to cause an avalanche of free electrons and ions, as described here. These free charges travel the length of the air gap, but they are stopped and neutralized at the dielectric surface. This reduces the local electric field at the location of the surface charge so that the force on the cantilever is reduced and the process repeats itself. Throughout this process, a large amount of charge can be introduced onto the dielectric surface, which will typically have a very long dissipation time constant.

35.3 Summary and Mention of Topics not Covered

This chapter has focused on the thermomechanics and electromechanics of thin-film microstructures. Emphasis has been placed on the basic physical phenomena, approaches to analyze the phenomena, and the presentation of accessible results for special cases of practical importance in a variety of applications. We have not discussed many other energy domain couplings that play major roles in microsystems technology such as electrothermomechanics and magnetomechanics. We have also not discussed the role and behavior of materials such as piezoelectrics or shape memory alloys, which play important roles in electromechanics and thermomechanics, respectively. We refer the interested reader to *Senturia* [35.49] for an introduction and further references.

References

35.1 M. Madou: *Fundamentals of Microfabrication* (CRC, Boca Raton 1997)

35.2 M. Gad-el-Hak: *The MEMS Handbook* (CRC, Boca Raton 2001)

35.3 J.J. Sniegowski, M.P. de Boer: IC-compatible polysilicon surface micromachining, Annu. Rev. Mater. Sci. **30** (2000) 299–333

35.4 C. H. Mastrangelo: Adhesion-related failure mechanisms in microelectromechanical devices, Tribol. Lett. **3** (1997) 223–238

35.5 M. P. de Boer, T. M. Mayer: Tribology of MEMS, MRS Bull. **26** (2001) 302–304

35.6 W. D. Nix: Mechanical properties of thin films, Metall. Trans. A **20A** (1989) 2217–2245

35.7 C. Y. Hui, H. D. Conway, Y. Y. Lin: A reexamination of residual stresses in thin films and of the validity of Stoney's estimate, J. Electron. Packaging **122** (2000) 267–273

35.8 D. B. Bogy, K. C. Wang: Stress singularities at interface corners in bonded dissimilar materials, Int. J. Solids Struct. **7** (1971) 993–1005

35.9 V. L. Hein, F. Erdogan: Stress singularities in a two material wedge, Int. J. Fract. Mech. **7** (1971) 317–330

35.10 E. D. Reedy, T. R. Guess: Nucleation and propagation of an edge crack in a uniformly cooled epoxy/glass bimaterial, Int. J. Solids Struct. **39** (2002) 325–340

35.11 M. D. Thouless: Modeling the development and relaxation of stresses in films, Annu. Rev. Mater. Sci. **25** (1995) 69–96

35.12 N. D. Masters, M. P. de Boer, B. D. Jensen, M. S. Baker, D. Koester: Side-by-side comparison of passive MEMS residual strain test structures under residual compression. In: *Mechanical Properties of Structural Films*, ASTM STP **1413**, ed. by C. L. Muhlstein, S. B. Brown (2001) 168–200

35.13 M. W. Hyer: Calculation of the room-temperature shapes of unsymmetric laminates, J. Compos. Mater. **15** (1981) 296–310

35.14 M. W. Hyer: The room-temperature shape of four-layer unsymmetric cross-ply laminates, J. Compos. Mater. **16** (1982) 318–340

35.15 D. E. Fahnline, C. B. Masters, N. J. Salamon: Thin film stress from nonspherical substrate bending measurements, J. Vac. Sci. Technol. A **9** (1991) 2483–2487

35.16 C. B. Masters, N. J. Salamon: Geometrically nonlinear stress-deflection relations for thin film/substrate systems, Int. J. Eng. Sci. **31** (1993) 915–925

35.17 C. B. Masters, N. J. Salamon: Geometrically nonlinear stress-deflection relations for thin film/substrate systems with a finite element comparison, J. Appl. Mech. **61** (1994) 872–878

35.18 M. Finot, S. Suresh: Small and large deformation of thick and thin film multilayers: effects of layer geometry, plasticity and compositional gradients, J. Mech. Phys. Solids **44** (1996) 683–721

35.19 M. Finot, I. A. Blech, S. Suresh, H. Fujimoto: Large deformation and geometric instability of substrates with thin film deposits, J. Appl. Phys. **81** (1997) 3457–3464

35.20 L. B. Freund: The stress distribution and curvature of a general compositionally graded semiconductor layer, J. Cryst. Growth **132** (1993) 341–344

35.21 L. B. Freund: Some elementary connections between curvature and mismatch strain in compositionally graded thin films, J. Mech. Phys. Solids **44** (1996) 723–736

35.22 L. B. Freund: Substrate curvature due to thin film mismatch strain in the nonlinear deformation range, J. Mech. Phys. Solids **48** (2000) 1159–1174

35.23 N. J. Salamon, C. B. Masters: Bifurcation in isotropic thin film/substrate plates, Int. J. Solids Struct. **32** (1995) 473–481

35.24 R. M. Jones: *Mechanics of Composite Materials*, 2nd edn. (Taylor & Francis, London 1999)

35.25 M. W. Hyer: *Stress Analysis of Fiber-reinforced Composite Materials* (McGraw-Hill, Boston 1998)

35.26 G. G. Stoney: The tension of metallic films deposited by electrolysis, Proc. R. Soc. Lond. A **82** (1909) 172–175

35.27 C. D. Pionke, G. Wempner: The various approximations of the bimetallic thermostatic strip, J. Appl. Mech. **58** (1991) 1015–1020

35.28 P. Krulevitch, G. C. Johnson: Curvature of a cantilever beam subjected to an equibiaxial bending moment, Mater. Res. Symp. Proc. **518** (1998) 67–72

35.29 S. R. Swanson: *Introduction to Design and Analysis with Advanced Composite Materials* (Prentice-Hall, Upper Siddel River 1997)

35.30 M. L. Dunn, Y. Zhang, V. Bright: Deformation and structural stability of layered plate microstructures subjected to thermal loading, J. Microelectromech. Syst. **11** (2002) 372–383

35.31 J. A. King: *Materials Handbook for Hybrid Microelectronics* (Teledyne Microelectronics, Los Angeles 1988)

35.32 W. N. Sharpe: Mechanical properties of MEMS materials. In: *The CRC Handbook of MEMS*, ed. by M. Gad el Hak (CRC, Boca Raton 2001) Chap. 3

35.33 Y. Zhang, M. L. Dunn: Deformation of blanketed and patterned bilayer thin film microstructures during post-release thermal and cyclic thermal loading, J. Microelectromech. Syst. (2003) in press

35.34 B. D. Harper, C.-P. Wu: A geometrically nonlinear model for predicting the intrinsic film stress by the bending plate method, Int. J. Solids Struct. **26** (1990) 511–525

35.35 Y. L. Shen, S. Suresh: Thermal cycling and stress relaxation response of Si-Al and Si-Al-SiO$_2$ layered thin films, Acta. Metall. Mater. **43** (1995) 3915–3926

35.36 S. P. Baker, A. Kretschmann, E. Arzt: Thermomechanical behavior of different texture components in Cu thin films, Acta Mater. **49** (2001) 2145–2160

35.37 W. D. Nix: Elastic and plastic properties of thin films on substrates, Mater. Sci. Eng. A **234–236** (1997) 37–44

35.38 C. Thompson: The yield stress of polycrystalline thin films, J. Mater. Res. **8** (1993) 237–238

35.39 H. Gao, Y. Huang, W. D. Nix, J. W. Hutchinson: Mechanism-based strain gradient plasticity – I. Theory, J. Mech. Phys. Solids **47** (1999) 1239–1263

35.40 H. D. Espinosa, B. C. Prorok, M. Fischer: A novel method for measuring elasticity, plasticity, and fracture of thin films and MEMS materials, J. Mech. Phys. Solids **51** (2003) 47–67

35.41 D. C. Miller, M. L. Dunn, V. M. Bright: Thermally induced change in deformation of multimorph MEMS structures, Proc. SPIE **4558** (2001) 32–44

35.42 D. J. Vickers-Kirby, R. L. Kubena, F. P. Stratton, R. J. Joyce, D. T. Chang, J. Kim: Anelastic creep phenomena in thin film metal plated cantilevers for MEMS, Mater. Res. Soc. Symp. **657** (2001) EE2.5.1–EE2.5.6

35.43 R. M. Keller, S. P. Baker, E. Arzt: Stress-temperature behavior of unpassivated thin copper films, Acta Mater. **47** (1999) 415–426

35.44 M. D. Thouless, J. Cupta, J. M. E. Harper: Stress development and relaxation in copper films during thermal cycling, J. Mater. Res. **8** (1993) 1845–1852

35.45 M. D. Thouless, K. P. Rodbell, C. Cabral Jr.: Effect of a surface layer on the stress relaxation of thin films, J. Vac. Sci. Technol. **14** (1996) 2454–2461

35.46 R. P. Vinci, E. M. Zielinski, J. C. Bravman: Thermal stress and strain in copper thin films, Thin Solid Films **262** (1995) 142–153

35.47 J. Koike, S. Utsunomiya, Y. Shimoyama, K. Maruyama, H. Oikawa: Thermal cycling fatigue and deformation mechanism in aluminum alloy thin films on silicon, J. Mater. Res. **13** (1998) 3256–3264

35.48 K. Gall, M. L. Dunn, Y. Zhang, B. Corff: Thermal cycling response of layered gold/polysilicon MEMS structures, Mech. Mater. (2003) in press

35.49 S. D. Senturia: *Microsystems Design* (Kluwer, Dordrecht 2001)

35.50 M. P. de Boer, N. F. Smith, N. D. Masters, M. B. Sinclair, E. J. Pryputniewicz: Integrated platform for testing MEMS mechanical properties at the wafer scale by the IMaP methodology. In: *Mechanical Properties of Structural Films*, ASTM STP **1413** (2001) 85–95

35.51 Z. J. Yao, S. Chen, S. Eshelman, D. Denniston, C. Goldsmith: Micromachined low-loss microwave switches, J. Microelectromech. Syst. **8** (1999) 129–134

35.52 B. McCarthy, G. G. Adams, N. E. McGruer, D. Potter: A dynamic model, including contact bounce of an electrostatically actuated microswitch, J. Microelectromech. Syst. **11** (2002) 276–283

35.53 H.-S. Lee, C. H. Leung, J. Shih, S.-C. Chang, S. Lorincz, I. Nedelescu: Integrated microrelays: Concept and initial results, J. Microelectromech. Syst. **11** (2002) 147–153

35.54 S. J. Cunningham, S. Tatic-Lucic, J. Carper, J. Lindsey, L. Spangler: A high aspect ratio accelerometer fabricated using anodic bonding, dissolved wafer, and deep RIE processes, Proc. Transducers '99, the 10th Intl. Conf. Solid-State Sensors and Actuators, Sendai 1999, ed. by M. Esashi (IEE Jpn. 1999) 1522–1525

35.55 L. Spangler, C. Kemp: ISAAC: integrated silicon automotive acceleromter, Sens. Actuators A **54** (1996) 523–529

35.56 M. T. A. Saif, B. E. Alaca, H. Sehitoglu: Analytical modeling of electrostatic membrane actuator for micropumps, J. Microelectromech. Syst. **8** (1999) 335–345

35.57 C. Huang, C. Christophorou, K. Najafi, A. Naguib, H. M. Naguib: An electrostatic microactuator system for application in high-speed jets, J. Microelectromech. Syst. **11** (2002) 222–235

35.58 H. Toshiyoshi, H. Fujita: Electrostatic micro torsion mirrors for optical switch matrix, J. Microelectromech. Syst. **5** (1996) 231–237

35.59 H. Toshiyoshi, W. Piyawattanametha, C.-T. Chan, M. C. Wu: Linearization of electrostatically actuated surface micromachined 2-D optical scanner, J. Microelectromech. Syst. **10** (2001) 205–214

35.60 M. Fischer, M. Giousouf, J. Schaepperle, D. Eichner, M. Weinmann, W. von Münch, F. Assmus: Electrostatically deflectable polysilicon micromirrors-dynamic behaviour and comparison with the results from FEM modelling with Ansys, Sens. Actuators A **67** (1998) 89–95

35.61 P. K. C. Wang, R. C. Gutierrez, R. K. Bartman: A method for designing electrostatic-actuator electrode pattern in micromachined deformable mirrors, Sens. Actuators A **55** (1996) 211–217

35.62 P. K. C. Wang, F. Y. Hadaegh: Computation of static shapes and voltages for micromachined deformable mirrors with nonlinear electrostatic actuators, J. Microelectromech. Syst. **5** (1996) 205–220

35.63 J. Bühler, J. Funk, J. G. Korvink, F.-P. Steiner, P. M. Sarro, H. Baltes: Electrostatic aluminum micromirrors using double-pass metallization, J. Microelectromech. Syst. **6** (1997) 126–135

35.64 M. Fischer, H. Graef, W. von Münch: Electrostatically deflectable polysilicon torsional mirrors, Sens. Actuators A **44** (1994) 83–89

35.65 H. Schenk, P. Dürr, D. Kunze, H. Lakner, H. Kück: An electrostatically excited 2D-micro-scanning-mirror with an in-plane configuration of the driving electrodes, Proc. IEEE MEMS 2000, The 13th Ann. Intl. Conf. Micro Electro Mechanical Systems, Miyazaki 2000, ed. by I. Shimoyama, H. Kuwano (IEEE, Piscataway 2000)

35.66 Y. Nemirovsky, O. Bochobza-Degani: Methodology and model for the pull-in parameters of electrostatic actuators, J. Microelectromech. Syst. **10** (2001) 601–615

35.67 G. Li, N. R. Aluru: A Lagrangian approach for electrostatics analysis of deformable conductors, J. Microelectromech. Syst. **11** (2002) 245–254

35.68 N. R. Aluru, J. White: A multilevel Newton method for mixed-energy domain simulation of MEMS, J. Microelectromech. Syst. **8** (1999) 299–308

35.69 J. I. Seeger, S. B. Crary: Stabilization of electrostatically actuated mechanical devices, Proc. Transducers '97, 1997 Intl. Conf. Solid-State Sensors and Actuators, Chicago 1997, ed. by K. Wise (IEEE, Piscataway 1997) 1133–1136

35.70 R. Nadal-Guardia, A. Dehe, R. Aigner, L. M. Castaner: Current drive methods to extend the range of travel of electrostatic microactuators beyond the voltage pull-in point, J. Microelectromech. Syst. **11** (2002) 255–263

35.71 G. J. O'Brien, D. J. Monk, L. Lin: Electrostatic latch and release; a theoretical and empirical study, Proc. Micro-Electro-Mechanical Syst. (MEMS) 2000, MEMS-Vol. 2, The 2000 ASME Intl. Mech. Eng. Cong. and Expo., Orlando 2000, ed. by A. J. Malshe, Q. Tan, A.¶. Lee, F. R. Forster, R. S. Kenten (ASME, New York 2000) 19–26

35.72 B. Choi, E. G. Lovell: Improved analysis of microbeams under mechanical and electrostatic loads, J. Micromech. Microeng. **7** (1997) 24–29

35.73 Y. Zhang, M. L. Dunn: A vertical electrostatic actuator with extended digital range via tailored topology, Proc. SPIE **4700** (2002) 147–156

35.74 O. Degani, E. Socher, A. Lipson, T. Leitner, D. J. Setter, S. Kaldor, Y. Nemirovsky: Pull-in study of an electrostatic torsion microactuator, J. Microelectromech. Syst. **7** (1998) 373–379

35.75 Z. Xiao, X. Wu, W. Peng, K. R. Farmer: An angled-based design approach for rectangular electrostatic actuators, J. Microelectromech. Syst. **10** (2001) 561–568

35.76 E. S. Hung, S. D. Senturia: Generating efficient dynamical models for microelectromechanical systems from a few finite-element simulation runs, J. Microelectromech. Syst. **8** (1999) 280–289

35.77 J. R. Gilbert, R. Legtenberg, S. D. Senturia: 3D coupled electro-mechanics for MEMS: Application of CoSolve-EM, Proc. IEEE MEMS Conference, Amsterdam 1995, ed. by M. Elwenspoek, N. de Rooij (IEEE, Piscataway 1995) 122–127

35.78 J. R. Gilbert, G. K. Ananthasuresh: 3D modeling of contact problems and hysteresis in coupled electro-mechanics, Proc. IEEE MEMS 1996, The ninth Ann. Intl. Workshop on Micro Electro Mechanical Syst., San Diego 1996, ed. by M. G. Allen, M. L. Reed (IEEE, Piscataway 1996) 127–132

35.79 Y.-H. Jin, K.-S. Seo, Y.-H. Cho, S.-S. Lee, K.-C. Song, J.-U. Bu: An integrated SOI optical microswitch using electrostatic micromirror actuators with insulated touch-down beams and curved electrodes, Proc. Micro-Electro-Mechanical Syst. (MEMS) 2000, MEMS-Vol. 2. The 2000 ASME Intl. Mech. Eng. Cong. and Expo., Orlando 2000, ed. by A. J. Malshe, Q. Tan, A. P. Lee, F. R. Forster, R. S. Kenten (ASME, New York 2000) 177–181

35.80 R. Legtenberg, E. Berenschot, M. Elwenspoeke, J. Fluitman: Electrostatic curved electrode actuators, Proc. IEEE MEMS Conference, Amsterdam 1995 (IEEE, Piscataway 1995) 37–42

35.81 R. Legtenberg, J. Gilbert, S. D. Senturia, M. Elwenspoek: Electrostatic curved electrode actuators, J. Microelectromech. Syst. **6** (1997) 257–265

35.82 D. DeReus: Personal communications and internal reports (2002)

35.83 P. M. Osterberg, S. D. Senturia: M-TEST: A test chip for MEMS material property measurement using electrostatically actuated test structures, J. Microelectromech. Syst. **6** (1997) 107–118

35.84 L. M. Castaner, S. D. Senturia: Speed-energy optimization of electrostatic actuators based on pull-in, IEEE J. Microelectromech. Syst. **8** (1999) 290–298

35.85 L. Castaner, A. Rodriguez, J. Pons, S. D. Senturia: Measurement of power-speed product of electrostatic actuators, Proc. Transducers '99, the 10th Intl. Conf. Solid-State Sensors and Actuators, Sendai 1999, ed. by M. Esashi (IEE Jpn., Tokyo 1999) 1772–1775

35.86 L. Castaner, A. Rodriguez, J. Pons, S. D. Senturia: Pull-in time-energy product of electrostatic actuators: Comparison of experiments and simulation, Sens. Actuators **83** (2000) 263–269

35.87 J. Pons-Nin, A. Rodriguez, L. M. Castaner: Voltage and pull-in time in current drive of electrostatic actuators, J. Microelectromech. Syst. **11** (2002) 196–205

35.88 C. Cabuz, E. I. Cabuz, T. R. Ohnstein, J. Neus, R. Maboudian: Factors enhancing the reliability of touch-mode electrostatic actuators, Sens. Actuators **79** (2000) 245–250

35.89 J. Wibbeler, G. Pfeifer, M. Hietschold: Parasitic charging of dielectric surfaces in capacitive microelectromechanical systems (MEMS), Sens. Actuators A **71** (1998) 74–80

35.90 H. Kubo, T. Namura, K. Yoneda, H. Ohishi, Y. Todokoro: Evaluation of charge build-up in wafer processing by using MOS capacitors with charge collecting electrodes, ICMTS 1995 Proc. IEEE Intl. Conf. Microelectronic Test Structures, Vol. 8, Nara 1995, ed. by T. Sugano, K. Asada (IEEE, Piscataway 1995) 5–9

35.91 E. K. Chan, K. Garikipati, R. W. Dutton: Characterization of contact electromechanics through capacitance-voltage measurement and simulations, IEEE J. Microelectromech. Syst. **8** (1999) 208–217

35.92 P. G. Slade, E. D. Taylor: Electrical breakdown in atmospheric air between closely spaced (0.2 μm–40 μm) electrical contacts, Proc. 47th IEEE Holm Conf. Electrical Contacts, Montreal 2001, ed. by K. Leung (IEEE, Piscataway 2001) 245–250

35.93 J-M. Torres, R. S. Dhariwal: Electric field breakdown at micrometer separations, Nanotechnology **10** (1999) 102–107

35.94 R. Longwitz, H. van Lintel, R. Carr, C. Hollenstein, P. Renaud: Study of gas ionization schemes for microdevices, Proc. Transducers '01, Eurosensors XV, The 11th Intl. Conf. Solid-State Sensors and Actuators, Munich 2001, ed. by O. Obermeier (Springer, Berlin, Heidelberg 2001) 1258–1261

35.95 D. K. Davies, M. F. Biondi: Vacuum breakdown between plane-parallel copper plates, J. Appl. Phys. **37** (1966) 2969–2977

35.96 T. Ono, D. Y. Sim, M. Esashi: Micro-discharge and electric breakdown in a micro-gap, J. Micromech. Microeng. **10** (2000) 445–451

36. High Volume Manufacturing and Field Stability of MEMS Products

Low volume MEMS/NEMS production is practical when an attractive concept is implemented with business, manufacturing, packaging, and test support. Moving beyond this to high volume production adds requirements on design, process control, quality, product stability, market size, market maturity, capital investment, and business systems. In a broad sense, this chapter uses a case study approach: It describes and compares the silicon-based MEMS accelerometers, pressure sensors, image projection systems, and gyroscopes that are in high volume production. Although they serve several markets, these businesses have common characteristics. For example, the manufacturing lines use automated semiconductor equipment and standard material sets to make consistent products in large quantities. Standard, well controlled processes are sometimes modified for a MEMS product. However, novel processes that cannot run with standard equipment and material sets are avoided when possible. This reliance on semiconductor tools, as well as the organizational practices required to manufacture clean, particle-free products partially explains why the MEMS market leaders are integrated circuit manufacturers. There are other factors. MEMS and NEMS are enabling technologies, so it can take several years for high volume applications to develop. Indeed, market size is usually a strong function of price. This becomes a vicious circle, because low price requires low cost – a result that is normally achieved only after a product is in high volume production. During the early years, IC companies reduced cost and financial risk by using existing facilities for low volume MEMS production. As a result, product architectures are partially determined by capabilities developed for previous products. This chapter includes a discussion of MEMS product architecture with particular attention to the impact of electronic integration, packaging, and surfaces. Packaging and testing are critical, because they are significant factors in MEMS product cost. These devices have extremely high surface/volume ratios, so performance and stability may depend on the control of surface characteristics after packaging. Looking into the future, the competitive advantage of IC suppliers will decrease as small companies learn to integrate MEMS/NEMS devices on CMOS foundry wafers. Packaging challenges still remain, because most MEMS/NEMS products must interact with the environment without degrading stability or reliability. Generic packaging solutions are unlikely. However, packaging subcontractors recognize that MEMS/NEMS is a growth opportunity. They will spread the overhead burden of high-capital-cost-facilities by developing flexible processes in order to package several types of moderate volume integrated MEMS/NEMS products on the same equipment.

36.1 Manufacturing Strategy 1086
36.1.1 Volume 1086
36.1.2 Standardization 1086
36.1.3 Production Facilities 1086
36.1.4 Quality 1087
36.1.5 Environmental Shield 1087

36.2 Robust Manufacturing 1087
36.2.1 Design for Manufacturability 1087
36.2.2 Process Flow and Its Interaction with Product Architecture 1088
36.2.3 Microstructure Release 1095
36.2.4 Wafer Bonding 1095
36.2.5 Wafer Singulation 1097
36.2.6 Particles 1098
36.2.7 Electrostatic Discharge and Static Charges 1098
36.2.8 Package and Test 1099
36.2.9 Quality Systems 1101

36.3 Stable Field Performance 1102
36.3.1 Surface Passivation 1102
36.3.2 System Interface 1105

References 1106

Solid-state pressure sensors were first reported in the 1960s and commercialized by a number of start-up companies in the 1970s. By 1983, a *Scientific American* cover story [36.1] described pressure sensors, accelerometers, and ink-jet print heads and featured a gas chromatograph that combined an injection valve, a detector, and a chromatographic column on a silicon wafer. The future of the budding micromechanical device industry looked bright, but commercial reality has seriously lagged the rosy market projections. The reason was simple: Market forecasters failed to recognize the difference between lab prototypes and high volume production of stable products. Many companies have demonstrated that small quantities can be produced for niche markets. However, routine high volume production of reliable packaged devices is much more challenging. It requires the production prototype skills plus the manufacturing disciplines that are critical to long-term stable production.

Successful companies understand and apply these lessons. Indeed, over a hundred million MEMS pressure sensor, accelerometer, gyro, gas flow, and optical projection devices are shipped to customers annually. There is no universally accepted definition of MEMS. This chapter focuses on silicon-based products with movable micromechanical elements. It excludes disk drive heads, ink-jet print heads, hearing aids, microscale plastic, ceramic, quartz and metal components, and test strips for in vitro diagnostics that are sometimes included within the definition of MEMS. Many MEMS products do not integrate support electronics with the MEMS element on the chip even though they are produced with IC equipment, materials, and processes. However, integrated MEMS products are becoming ubiquitous. By 2002 Analog Devices had shipped over a hundred million surface micromachined MEMS accelerometers with integrated electronics to customers.


Bond pads
Piezoresistors
Etched cavity in silicon forms thin diaphragm
Diaphragm
Silicon
Glass or silicon substrate
Back side port for barometric or differential pressure

Fig. 36.1 Cross section of a piezoresistive silicon sensor after it is bonded to a silicon or glass substrate. When pressure is applied, the thin silicon diaphragm deforms. This causes changes in four implanted resistors that form a Wheatstone bridge. The resistors are located and oriented to cause resistance to increase in two resistors and decrease in the other two

The literature related to high volume production of MEMS products is quite uneven. Some suppliers have published detailed process and design descriptions, while others limit disclosures to market-focused publications. The two major suppliers of integrated MEMS products have discussed their designs and processes in detail. *Core* et al. [36.2], *Kuehnel* et al. [36.3], *Chau* et al. [36.4], and *Sulouff* [36.5] describe the Analog Devices *i*MEMS accelerometers and gyros. *Mignardi* et al. [36.6] give an in-depth review of the Texas Instruments DLP (Digital Light Processing) products.

MEMS devices are components in larger systems, so every MEMS product must define its system interface in a way that adds value from the perspective of the system designer. Some MEMS pressure sensor products are simply Wheatstone bridge elements in a circuit (Fig. 36.1). The image projection systems that use the Texas Instruments Digital Light Processing Technology$^{\text{TM}}$ could never be designed in this manner, because up to 1.3 million mirrors are driven on each chip (Fig. 36.2). Such a system would be impractical unless electronics are integrated with the MEMS mirrors on the chip. Air bag sensors also illustrate how integration adds value. Non-MEMS ball-and-spring air bag sensors were often used in the early 1990s. Upon impact, a ball would be released and detected as it passed through the sensor tube. Unfortunately, these binary sensors could not always distinguish a frontal collision from the jolt of a pothole or a side collision. Therefore, multiple ball-and-spring sensors were placed at different locations in a vehicle and wired together in order to reliably identify accidents that should result in air bag deployment. High cost limited the use of these distributed systems. Analog Devices changed the air bag market when it introduced the ADXL50 in 1993 (Fig. 36.3). The ADXL50 integrated electronics and an accelerometer on one chip to provide an analog output of deceleration versus time when an impact event occurred. This allowed automobile manufacturers to design air bag modules that compared the ADXL50 output to the known signature of a frontal collision. The result was greater reliability



Fig. 36.2 Digital Light Processing technology$^{\text{TM}}$ is based on Digital Micromirror Device (DMD) chips that address and drive a "sea of mirrors." The DMD is the key element in small computer-based projection systems. Each of the 14 or 17 µm mirrors represents one pixel. The diagram on the *left* represents light reflecting from a mirror to the system lens. The illustration on the *right* is an exploded view of a small region of mirrors in a packaged DMD. (Courtesy of Digital Light Processing$^{\text{TM}}$, Texas Instruments, Inc.)

and lower cost, which led to the installation of air bags in almost every new automobile.

This chapter will not recite detailed descriptions of particular commercial products. Instead, brief descriptions will be used to illustrate basic principles and concepts. Part of the chapter is organized according to MEMS-specific issues like wafer singulation. This is useful because some designs and unit processes are well suited for lab scale or low volume production, but impractical in a high volume manufacturing environment. Complete reliance on such an organization would be artificial, because partitioning omits the greatest challenge – combining these individual topics into a manufacturing flow that routinely produces products that meet cost, performance, and reliability expectations. The importance of process integration cannot be



Fig. 36.3a,b Three generations of integrated accelerometers designed for single-axis air bag applications. **(a)** Die size is reduced by a factor of two about every four years. **(b)** Package technology also evolved to meet size, cost, and automated handling requirements. The ADXL50 was packaged in TO-100 seam-sealed metal headers. ADXL76 cerpacs (*bottom left*) are being replaced by the ADXL78 in 5 mm × 5 mm LCC packages (*bottom right*). (Courtesy of Micromachined Products Division, Analog Devices, Inc.)

overemphasized, because changes in one step almost always affect other steps. Solutions may involve design modifications, so design-for-manufacturability is an important topic. Manufacturing and business skills are included to the extent that they apply to stable production of reliable MEMS products.

36.1 Manufacturing Strategy

MEMS manufacturing is based on existing IC technology. However, there are only a few examples of routine MEMS and IC production intermixed on the same equipment (or of MEMS devices with electronics integrated on the chip). Even when a MEMS process step is nominally the same as a standard IC process, the specific conditions or end point or some quality such as film stress will differ. Technologists from Analog Devices and Motorola have discussed these thin film issues in depth [36.7–10].

Manufacturers prefer to use dry etch processes when possible in order to achieve better control of features, minimize waste disposal, and utilize automated equipment developed for the IC industry. However, anisotropic wet etching provides unique value in the production of some MEMS products like pressure, mass flow, and yaw rate sensors [36.11].

Although MEMS production economics is closely tied to the semiconductor model, useful lessons can be drawn from many industries. Some of the key characteristics that affect success are as follows:

36.1.1 Volume

Semiconductor economics is rooted in the principle that expensive processes are cost-effective when many devices are made simultaneously. Obviously, a MEMS product that is sold in low quantities loses this critical advantage. MEMS components are "disruptive technologies" – they are the key element in higher-level products that were previously impractical. It can take several years to develop a higher-level product and build its customer base. Therefore, it is prudent to include an incubation phase in the business plan for a novel MEMS device. Low sales volume during this phase causes high unit costs – batch process cost benefits are achieved only after the market develops.

Start-up companies often do not understand the implications of design-for-volume. It is a major challenge to transfer products made on lab tools to manufacturing equipment. The challenge is sufficient to justify the use of manufacturing people and equipment for product development.

Realistic price-volume estimates are also essential to a good business plan. The highest volume MEMS products (accelerometers and pressure sensors) all represent a small part of the total system cost, even though the functions they provide are absolutely critical to system performance.

Market-pull business models that respond to the needs of a specific large application in a particular industry are usually more successful than technology-driven models that seek applications for new devices. Given this reality, it is prudent to thoroughly understand the target industry and its quirks. Biotech, wireless, image projection, optical communications, and consumer markets offer tremendous growth potential. However, the past and present growth in high volume MEMS products have been driven primarily by the automotive industry, with pressure sensors also benefiting from medical applications. *Sulouff* [36.12], *Weinberg* [36.13], *Marek* et al. [36.14], *Eddy* et al. [36.15], and *Verma* et al. [36.16] discuss automotive applications and the challenges a successful supplier must master.

36.1.2 Standardization

Mature industries develop standards in response to equipment vendors, material suppliers, and customer interface requirements. The MEMS industry is fragmented, so even after 30 years it is not mature. Deviations from semiconductor industry standards are inevitable because MEMS products impose unique requirements on wafer processing, packaging, handling, and testing. For example, KOH wet etching raises mobile ion concerns. Gold used in some optical products is incompatible with CMOS. Any deviation from standard process and material sets is serious, because the price-volume relationship is a steep curve in high volume applications.

36.1.3 Production Facilities

The semiconductor industry is divided into front-end (wafer fabrication) and back-end (product assembly and test) operations. IC design rules are based on pre-qualified fab, assembly, and test capabilities at specific sites. Consider how each of these functions matches the needs of MEMS production:

1. An IC product might be produced at an internal wafer fab, or designed to run on a standard foundry process. In contrast, production challenges and "know-how" have caused MEMS suppliers to retain wafer fab production within their internal facilities. High volume production in MEMS foundries was limited to pressure sensors. However, Motorola is now outsourcing accelerometer production. This suggests that the MEMS industry will follow the IC model, with foundry services becoming more substantial in the future.
2. IC suppliers have shifted assembly operations to subcontractor facilities located in Southeast Asia. Some MEMS suppliers have followed this model. It is common to assemble low volume products in North America, Europe, or Japan. However, semiconductor assembly and package technology are evolving rapidly and are driven by subcontractors based in Southeast Asia. MEMS companies that do not utilize these resources pay a significant cost penalty. Obviously, the break point at which offshore assembly is attractive differs from one product to the next. Products that have unique assembly requirements and support high market prices may never reach this point.
3. IC testing is often carried out at the assembly subcontractor site. MEMS package and testing comprise a substantial portion of the total product cost, so a high volume manufacturing strategy should consider Southeast Asia packaging and testing. This is complicated by the fact that MEMS testing requires unique stimuli that are not in the standard IC portfolio.

36.1.4 Quality

The goal in lab and low volume production environments is to make functioning devices. As quantities increase, other factors become more important: lot-to-lot repeatability, yield, device performance that meets well-defined specifications, process stability to ensure predictable on-time delivery, documentation and procedures that enable traceability and corrective actions when problems arise, etc. Methodologies that promote stable, high-quality manufacturing practices have been established in several industries. These standard procedures such as ISO9000, QS9000, and cGMP overlap to a large extent. QS9000 was developed to help automotive suppliers implement effective, well controlled processes to produce reliable products. It has several unique features, so it is used as the model in this chapter.

36.1.5 Environmental Shield

IC wafers are completely passivated before packaging in order to meet product stability and reliability requirements. Aside from ink-jet print heads, the active regions of all MEMS devices currently in high volume production replicate this hermetic barrier in some manner. This passivation requirement is noteworthy because it has been a primary limitation on the growth of the MEMS industry. For example, it limits electrochemical sensors to benign or "throw-away" applications.

36.2 Robust Manufacturing

Stable production requires a manufacturing flow that is well controlled when measured against the product performance specifications. This has several implications.

36.2.1 Design for Manufacturability

Low maintenance products and processes must be designed to run on standard equipment. The semiconductor industry has invested billions of dollars to develop equipment that is automated, maintainable, reliable, and capable of supporting well controlled processes. Processes that are implemented on custom-designed equipment put this experience base aside and invariably have a long learning curve.

Equipment

Microstructure release illustrates this issue and how it changes over time. Virtually all semiconductor processes operate in vacuum or at atmospheric pressure. In a brief, unpublished 1992 study related to ADXL50 development, the author demonstrated the use of supercritical CO_2 mixtures for microstructure release and particle cleaning. Unfortunately, supercritical processes were incompatible with the industry infrastructure, because they require pressures in excess of 7.38 MPa (72.8 atm; 1,070 psi). Implementation would have required process and equipment development, so a release process that ran on existing equipment was selected.

Supercritical equipment designed for MEMS release was introduced a few years later. However, maintenance and cycle time concerns, as well as single wafer capabilities limited its adoption to university and low volume manufacturing.

The intrinsic limitations of non-standard equipment have caused high volume MEMS suppliers to avoid supercritical processes. However supercritical equipment will continue to evolve and become competitive, particularly in applications where the design requirements make alternative processes unusable.

Materials

Process control can be no better than the materials used in the process. SAM (*s*elf-*a*ssembled *m*onolayer) coatings illustrate this limitation. These materials suppress stiction following aqueous release of microstructures by treating the wafers in a SAM solution before drying. Although straightforward in principle, high volume manufacturers have not (yet) adopted SAM processes (Sect. 36.2.3 reviews the processes that are used commercially). There are several reasons for this reticence. Classical SAM materials are chlorosilanes that have at least one organic substituent. Organosilanes have been used to treat the surface of inorganic materials for many years. Applications include coupling agents on the surface of fillers and reinforcing agents in polymers, as well as agglomeration control of particles. The chlorine sites hydrolyze when dissolved in solutions that contain a small amount of water. The resulting hydroxyl groups react with the microstructure surface oxide to produce a chemically bonded layer that reduces stiction due to the low surface energy and hydrophobic nature of the organic-rich surface. The concerns that cause manufacturers to use alternative stiction solutions include:

1. High variability due to the SAM chemical reactivity
2. Particles are common by-products of the reactivity
3. Many SAM process flows require organic baths. This raises health, safety, and waste disposal concerns
4. Possibility of chloride corrosion on aluminum interconnects

Maboudian et al. [36.17], *Srinivasan* et al. [36.18], *Kim* et al. [36.19], and *Pamidighantam* et al. [36.20] describe the use of SAM solutions to suppress stiction. There is also ongoing research focused on solving the manufacturing concerns [36.21–25].

Note that stiction also arises in packaged MEMS products. This yield and reliability problem is discussed in Sect. 36.3.1.

36.2.2 Process Flow and Its Interaction with Product Architecture

MEMS products have structures and functions that do not exist in standard IC devices, so it is unrealistic to expect that every fab, assembly, and test step will reapply a previously qualified IC process. The challenge is to maximize utilization of available IC technology within the constraints of the product function and cost requirements. This leads to fundamental choices in product architecture, product design, and process flow, as discussed below.

Integration of MEMS and Circuits

The integration of MEMS and electronics onto one chip has proven difficult. It adds little value in some MEMS products. However, as noted earlier, integration is essential to products based on the Texas Instruments (TI) DLP (Digital Light Processing^{TM}). The third (and largest) category consists of applications where integrated and non-integrated products compete for market share. Pressure sensors and accelerometers are examples of this group.

Image Projection. The first projectors based on the DLP technology were shipped in 1996. DLP chips are produced on CMOS wafers in a mature TI process. The circuitry addresses and drives aluminum mirror arrays that function as on-off pixels – 1.3 million mirrors in the latest SXGA products (Fig. 36.2). *Mignardi* et al. [36.6] describe the DMD (Digital Mirror Device) fabrication process and illustrate some of the factors that must be considered when manufacturing flows are changed. The manufacturing flow patterns three aluminum depositions over SRAM cells that are positioned with 14 or 17 μm center-to-center spacing (Figs. 36.4 and 36.5). The first of these metal films form electrostatic drive electrodes and landing pads. The yoke and hinge layer has spring tips that land on the first metal layer when mirrors are rotated (Fig. 36.6). Mirrors are mechanically connected to the yokes through center pedestals. Sacrificial organic films separate the metal layers. These organics, along with a protective organic cover film, remain on the device until after the wafer is sawn and the chips are mounted in a ceramic package. They are removed by dry etching.



Fig. 36.4 DMD pixel array with tilted and non-tilted mirrors. (Courtesy of Digital Light Processing^{TM}, Texas Instruments, Inc.)



Fig. 36.5 Ion milled section of DMD pixel showing one mirror on its center support and its relation to the underlying layers. Note the close mirror spacing. (Courtesy of Digital Light Processing^{TM}, Texas Instruments, Inc.)

Following surface passivation, inspection, and testing, an optical glass sub-assembly is hermetically sealed to the ceramic package (Fig. 36.7). At this point, the device is ready for burn-in and final test – a significant task because each mirror is actuated on chips with as many as 1.3 million mirrors.

In operation, a (nominal) 26 V electrode bias generates an electrostatic force that causes the mirror/yoke assembly to rotate either plus or minus 10 degrees around the hinge. Over one million DMD devices had been shipped by 2002 [36.26].



Fig. 36.6 DMD yoke and hinge layer. The spring tip touches landing pads when the drive electrode tilts the mirror. Elastic energy stored in the deformed spring is part of the restoring force that overcomes stiction when the drive electrode voltage is removed. (Courtesy of Digital Light Processing^{TM}, Texas Instruments, Inc.)

Unlike the pressure sensors and accelerometers discussed below, TI had no choice but to integrate. It would be difficult, if not impossible, to devise a cost-effective multi-chip solution to control and drive a matrix of over a million mirrors. Successful integration of circuits and mirrors was only one step in the commercialization process. To remain competitive against lower cost LCD products, TI continues to develop their package and test technologies, because package and test comprise a major part of the total product cost. This is discussed further in Sect. 36.2.8.

Pressure Sensors. Early (1970s-era) bulk micromachined piezoresistive pressure sensors from Honeywell, ICT (later Foxboro-ICT), and Kulite were not integrated. However, in the 1980s, Motorola commercialized the



Fig. 36.7 DMD products in hermetic packages. (Courtesy of Digital Light Processing^{TM}, Texas Instruments, Inc.)



Fig. 36.8 Pressure sensor surface mount packages. (Courtesy of Semiconductor Products Sector, Motorola, Inc.)

first of its MPX5100 series piezoresistive pressure sensor products. These products had bipolar signal conditioning electronics and temperature compensation on the sensor chip. Current MPX products are offered in various plastic packages (Figs. 36.8 and 36.9) with maximum pressure ranges between 10 and 300 kPa (1.45–44 psi). Medical and tire pressure products are also available.

Integrated Motorola piezoresistive pressure sensor products are cited here for illustrative purposes, but capacitive and piezoresistive silicon pressure sensors are available from many companies. Capacitive designs are less temperature sensitive and require less power than piezoresistive designs. However, die size tends to be larger. The fabrication process and interface electronics are also more involved. Piezoresistive products (sensor plus signal processing) are less expensive, smaller, easier to manufacture and suitable for most applications. They rely on the fact that the resistance of silicon changes in response to strain. This effect is very temperature sensitive. However, configuring four piezoresistors as a Wheatstone bridge, judicious selection of the doping level and junction depth and the use of a temperature compensating resistor network minimizes temperature error.



Fig. 36.9 Cross section of a typical gauge or differential pressure sensor. The silicon pressure sensor chip is bonded to a silicon substrate. This bonded unit is mounted in a pre-molded plastic package and protected from the ambient environment by silicone gel. (Courtesy of Semiconductor Products Sector, Motorola, Inc.)

Piezoresistive pressure sensors (Fig. 36.1) require double-sided polished wafers and front-to-back alignment. The piezoresistors are implanted into the front side of (100) wafers and precisely located with respect to the edges of thin diaphragms. The diaphragms are produced by anisotropically wet etching cavities into the back surface of the wafers. KOH etch solutions are usually used to avoid the safety, toxicity, and waste disposal concerns that arise when large quantities of organic etchants like EDP (Ethylenediamine-pyrocatechol-water) are used. Front-to-back side wafer alignment is critical in order to achieve precise resistor location with respect to the cavity edges. Alignment to the wafer crystal axis is also important, because the slow-etching (111) planes determine the cavity wall, and thus the location of the diaphragm edges. The piezoresistors are commonly placed near these edges to maximize the signal (the effect of pressure on diaphragm stress is greatest at the edges). An etch stop is sometimes used at additional cost because diaphragm thickness variations also have a large effect on sensitivity.

Control of mount stress is critical to achieving predictable performance. After wafer fab, some suppliers hermetically bond pressure-sensor wafers to a backup silicon wafer using glass frit. Others anodically bond them to a borosilicate glass wafer that has a thermal expansion coefficient close to silicon (Pyrex 7740 and Schott 8330 are two glasses used for this purpose). Absolute pressure sensors are produced when this bonding step is done in vacuum. As shown in Fig. 36.1 and Fig. 36.9, differential pressure and gauge pressure products incorporate through holes in the backup wafers. These ports allow fluid pressure to be applied through the cavities to the back side of the diaphragms.

After wafer singulation, the chips are mounted and sealed in cavity packages. Soft die attach materials, often silicone-based, are used to decouple the sensor from package and substrate stresses. In some products, the sensor chip is directly mounted to a substrate with a soft die attach without the intermediate backup wafer. Many package variations of MEMS pressure sensors are available, as summarized in Sect. 36.2.8.

The MEMS pressure sensor market is believed to exceed a hundred million pressure sensors annually [36.27]. Automotive applications like manifold absolute pressure (MAP) sensors and a wide range of gas and liquid pressure sensors form the largest market segment. Health care and medical uses such as disposable blood pressure transducers and sensors to measure pressure in angioplasty catheters, infusion pumps, and intrauterine products are the second largest market. Industrial products such as process control pressure and differential pressure transmitters, household appliance, and aeronautical products are also significant. *Maudie* et al. [36.28] review the performance and reliability issues related to appliance applications like household washing machines.

Accelerometers. Most MEMS accelerometer designs apply some variant of Newton's Law, $F = ma$, to sense the response of a proof mass. Many sensing principles, including piezoresistive, capacitive, piezoelectric, and resonant, have been examined [36.29]. Figure 36.10 has a conceptual view of the capacitive design used in Analog Devices ADXL accelerometers.



Fig. 36.10 Block diagram of the MEMS element in an ADXL78 single-axis accelerometer. The detailed design applies design-for-manufacturability principles to ensure close control of critical dimensions and residue-free removal of the sacrificial layer. (Courtesy of Micromachined Products Division, Analog Devices, Inc.)

SensorNor was an early pioneer in silicon accelerometer manufacturing. Their product had a mass bonded to the end of a silicon piezoresistive element in an oil-filled package. However, the first MEMS accelerometer product to achieve large-scale market acceptance was the integrated ADXL50 air bag sensor from Analog Devices. When it was fully qualified in 1993, the ADXL50 was the first integrated surface-micromachined MEMS device of any type in production. The MEMS element in the ADXL50 was part of a closed loop differential capacitance circuit, but was designed to allow routine self-testing after the air bag module was installed in vehicles. This self-test capability eased concerns related to the adoption of a new technology in a critical safety application. The analog output feature also allowed the industry to design single point sensors – a significant system cost savings. *Core* et al. [36.2] and *Sulouff* [36.5] describe the ADXL wafer fabrication process. In essence, circuits are fabricated with a well-established BiCMOS process. The sensor polysilicon is deposited after these high temperature steps, followed by the lower temperature metal and passivation processes. The in situ doped polysilicon is connected to the circuit through N+ doped runners. Following wafer fabrication, thin film resistors are laser trimmed in an automated trim system to meet the specific end user's requirements. After wafer singulation (Sect. 36.2.5), the chips are assembled in hermetic cavity packages and screened in an automated test system to ensure compliance to the performance specification (Sect. 36.2.8).

Front air bag sensors have an output of 2 V at a full scale acceleration that is specified by the user (typically 35–50 g). Satellite air bag sensors are located in door pillars and near the front of the automobile and typically have higher ranges (250 g). Regardless of range, all air bag sensors must meet stringent cross-axis specifications, i. e., a front air bag sensor must not react to a side collision or to potholes in the road. This cross-axis requirement also applies to products that are designed to sense in two axes (Fig. 36.11).

Progressive reductions in chip and package sizes (Fig. 36.3) led to cost reductions and penetration into new markets. One example is the ADXL202 (Fig. 36.11). This two-axis, low-g accelerometer has a full scale of 2 g in each axis. It is widely used in industrial, consumer, and automotive applications. Production of integrated MEMS accelerometers at Analog Devices has grown rapidly in recent years (several million devices per month by 2001). It is worth noting that these products are developed using an organizational philosophy that emphasizes design-for-manufacturability. For example, development is conducted on production equipment and directly involves production personnel. This may appear to be expensive and unwieldy, however, it ensures that product designs remain within the bounds of practical man-



Fig. 36.11 Three two-axis accelerometers. *Top left:* ADXL276 was the first two-axis air bag accelerometer. The ADXL278 family (*bottom right*) is replacing it. *Top right:* 2-g ADXL202. The ADXL202 and ADXL278 are packaged in the LCC shown in Fig. 36.3. (Courtesy of Micromachined Products Division, Analog Devices, Inc.)



Fig. 36.12 Two-chip accelerometer in 16 lead plastic SOIC package. (Courtesy of Semiconductor Products Sector, Motorola, Inc.)

ufacturing. It also minimizes the difficulties that are normally encountered when new products are transferred to production.

Prior to the introduction of the ADXL50, most of the MEMS air bag candidates were nonintegrated, bulk-micromachined piezoresistive sensors [36.3]. However, Motorola and Bosch soon followed with an integrate-in-the-package strategy. Denso, Delphi, and VTI Hamlin are also active in some market sectors. The Motorola and Bosch products are nonintegrated capacitive MEMS products that are hermetically sealed at the wafer level (Sect. 36.2.4). By interconnecting a separate circuit chip and a sealed accelerometer chip in one package, they are able to use low cost CMOS for signal processing and near-standard plastic packaging (Sect. 36.2.8).

In contrast to the ADXL sensors, Motorola's MMA air bag products measure acceleration normal to the plane of the chip (z-axis). These differential capacitance sensors are formed from three layers of polysilicon. The middle layer is a "proof mass" that is suspended with ligaments and is free to move in response to an accelerating force. Ranges and outputs are similar to the ADXL products. Recent Motorola expansions add x-axis air bag products and a new line of low-g z-axis products (Fig. 36.12).

The Bosch x-axis sensor has interdigitated fingers that are patterned in a thick (11 µm) polysilicon film that is deposited in an epi reactor. Tight control of stress and stress gradients in these films is essential in order to meet sensor performance requirements [36.30, 31]. After patterning, the polysilicon is dry etched using fluorine-based chemistry [36.32] to form the differential capacitance sensor. An HF vapor process is used to remove the sacrificial oxide and release the microstructures. These thick structures have working capacitances near 1 pF [36.33]. *Laermer* et al. [36.34] explain how Bosch applies deep silicon etch processing to several production and experimental inertial sensors. Better known as the "Bosch etch," this deep reactive ion etching technique has pioneered the field of high-aspect-ratio silicon-based MEMS.

The Future of Integration. The high growth rate of integrated MEMS products demonstrates the value of integration in MEMS applications. To date, integration has been limited to large semiconductor companies that have in-house signal processing expertise and the willingness to invest substantial resources over a number of years. Each company identified a large volume market that could support a profitable integrated product. This "large semiconductor company" barrier-to-entry for integrated MEMS products will diminish in the future due to new SOI wafer technology (Sect. 36.2.4), new flip-chip equipment, and the development of low temperature MEMS processes. With these capabilities, MEMS-only companies will be able to integrate microstructures on circuit wafers that are preprocessed in CMOS foundries. To be successful, they will also have to develop cost-effective manufacturing and quality expertise (Sect. 36.2.9).

Risk

High risk is normal in research programs. However, the tremendous financial investments required to manufacture new products make the risk of failure a key consideration. This section discusses how the perception of manufacturing risk changes with time and is influenced by available knowledge and expertise.

Every development program makes fundamental product architecture decisions. These decisions can lead competing companies down different paths. For example, Analog Devices pursued chip-level integration, while Bosch and Motorola chose package-level integration. Why did these companies choose different paths? The answer is related to available resources, cost, time-to-market, and technical maturity. Analog Devices chose to integrate because of its expertise in process innovation and signal processing. This path did have risks. When the ADXL50 was designed, the fatigue life of polysilicon MEMS devices was unknown. Therefore, a closed loop circuit architecture was chosen in order to keep the proof mass motion under 100 Å. Polysilicon actually has excellent fatigue life. Once this was established, Analog changed their ADXL products to an open loop architecture that can detect capacitance changes as low as 20 zF (10^{-21} F). Most companies do not have the expertise to work in this regime, but the decision to integrate on one chip allowed Analog to make full use of its signal processing knowledge.

The two-chip Motorola and Bosch designs allow the circuit chip to be fabricated on any IC process. This product concept also removed the concern that integrating MEMS and circuits onto one chip might reduce overall product yield. However, it does require higher output signals from the MEMS chip in order to overcome parasitics that arise in the bond wires between the circuit and sensor chips. This requirement led Motorola toward large-area z-axis designs, while Bosch utilized its deep-etch process capability. To minimize cost and ensure reliability, both companies seal the sensors with glass at the wafer level. Sensor and circuit chips are then molded together in one plastic package. Each company built on expertise that it already had in order to minimize risk and cost. Motorola had in-house manufacturing expertise in wafer-level glass frit sealing of pressure sensors that are subsequently molded in plastic packages. Bosch had deep-etch process capability and the world's largest hybrid manufacturing plant, so screen printing and glass sealing were well-established. These considerations plus the concern that MEMS yield loss would undermine product yield contributed to their two-chip decision.

Semiconductor companies continually drive down cost and serve evolving markets by shrinking product size. Analog Devices believes that this long-term roadmap requires an integrated product. They chose to deal with one-chip risks, rather than package uncertainties. ADXL50 chips had been capped and molded in plastic long before the first qualified products were shipped in 1993 [36.35]. However, production-worthy capping equipment did not exist at that time. The effects of plastic package stress on yield and long-term device parametrics were also uncertain. By introducing the initial product in TO-100 hermetic metal packages, the risks associated with custom equipment and package stress were removed.

Reusable Engineering and Facilities to Achieve Economies of Scale

The IC industry produces many products on each process flow. Foundries and packaging subcontractors routinely apply this "economy-of-scale" principle. Only basic items like mask sets and bond pad diagrams are changed. The MEMS industry has been less successful in this area, although techniques like wafer-level laser trim and blowing poly fuses allow accelerometer suppliers to offer "specialty" products without losing the advantages of high volume production.

If only a few devices are produced in a capital-intensive facility, unit costs are high. This issue is particularly critical during the first years of product life when sales volume is normally low. One solution is to build the market by manufacturing the new product in an existing facility. The two-axis low-g ADXL202 (Fig. 36.11) was built using a new mask set with an existing air bag sensor process. Many ADXL202 consumer, industrial, and automotive applications are too small to justify the capital investment risk required to develop and produce a two-axis accelerometer, but use of an existing design and manufacturing base removed this constraint.

Market Dynamics Drive New Product Opportunities

In the 1980s, low cost and high reliability allowed MEMS pressure sensors to penetrate automotive applications like the measurement of manifold vacuum (MAP sensors). Once a technology is accepted, new opportunities usually develop. For example, tire pressure monitors with RF communication capability are now available in some car models. In the future, this type of monitor will be a safety feature expected by all consumers. Indeed, wireless communication capabilities will also be a common MEMS product requirement.

This example illustrates the fact that MEMS products are merely system components. They must support seamless integration into the larger system. MEMS opportunities in automobile safety systems will be affected by both communication protocols and interconnect technology (copper, fiber optic, and wireless). The growth spurt of the 1990s started with front-air-bag crash sensors located in the center module of automobiles. It has evolved to include satellite crash sensors behind bumpers, side-impact sensors in the B pillar (the vertical post between doors), impact sensors inside doors, rollover sensors, and vehicle dynamic control sensors to improve ride and handling. Each of these applications has unique characteristics that can favor one technology over another. For example, side-impact sensing systems must activate the air bags faster than front-impact systems. This response time characteristic can favor the use of pressure sensors that monitor air pressure inside door cavities – a good solution as long as the cavity remains sealed. An alternative is to place an accelerometer in the B pillar. These thin structural members have very little space, so z-axis accelerometers are sometimes easier to implement. Delphi and Motorola products have this characteristic. Analog's small x-axis accelerometers also meet this space requirement.

Gyros – New Products Produced with Preexisting Manufacturing Capabilities

Gyroscopes are transducers for rotational motion. They have a wide range of uses in platform stabilization and robotics, as well as automotive applications (dead reckoning backup for GPS navigation systems when satellite communication links are lost, skid control systems, and rollover detection). Unfortunately, the non-MEMS and resonant quartz gyros used in military and aerospace applications are rather expensive for many high volume applications. BEI Systron Donner tailored their high performance quartz gyro to meet automotive needs and has shipped several million gyros. Other lower cost gyro and angular rate products, like the Murata vibrating ceramic bimorph products, are used in cameras. However, as a group, these low cost products do not meet the performance required for many applications.

Analog Devices and Bosch reapplied their accelerometer capabilities to develop and manufacture low cost gyroscopes. *Geen* et al. [36.36] describe the Analog Devices product. *Funk* et al. [36.37] and *Lutz* et al. [36.38] describe the Bosch product. These three publications reference previous work and discuss the challenges of producing gyros that meet performance, reliability, and cost targets.

The Analog Devices ADXRS150 gyro (Fig. 36.13) illustrates the technology. It has a resonant microstructure that is integrated with two electronic systems on one chip. One of the electronic systems drives the MEMS resonator. When the ADXRS150 is rotated, Coriolis ac-



Fig. 36.13 **(a)** ADXRS150 gyro with integrated electronics in 7 mm × 7 mm BGA package. **(b)** ADXRS150 chip. **(c)** MEMS portion of the ADXRS150 chip. (Courtesy of Micromachined Products Division, Analog Devices, Inc.)

celeration is generated in a direction that is perpendicular to the vibration axis of the resonator. This motion is detected by the second accelerometer system. Full scale is rated at 150 deg/s, although it can sustain overloads up to 10,000 deg/s. Integration of electronics on the chip, microstructure modeling, and predictable manufacturing were essential to success, because the full-scale Coriolis motion is only about 1 Å. The combination of differential capacitance detection, area averaging, and correlation techniques allow this motion to be resolved from thermal noise down to about 0.00016 Å [36.36].

Resonant gyros are not new. However, as noted above, their high cost restricts them to specialty applications. Many are non-MEMS, or utilize the piezoelectric properties of quartz, so chip-level integration is not an option. Most require expensive vacuum packaging to achieve high mechanical Q at resonance. Unfortunately, vacuum packaging also makes them susceptible to mechanical damage. Viscous damping in gas-filled devices like the ADXRS150 suppresses the destructive impact events that occur in vacuum-packaged MEMS products during shipping and handling and in-use conditions. Equally important are ADXRS150 design features that allow the measurement to reject mechanical shock, vibration, and other environmental noise sources. As a result, under-the-hood location is practical in automotive applications, an unmatched characteristic that significantly reduces system cost.

Analog Devices and Bosch both needed several years to develop their gyro products. Use of existing accelerometer infrastructure during the prototype and early production phases significantly reduced development costs and manufacturing risks. Early ADXRS150 gyros were sold as engineering grade products in socketable side braze packages. This allowed the development team and customers to understand the design and process parametrics that affect performance, reliability, and yield. Side braze packages are unacceptable in high volume applications, so the ADXRS150 is sold in a hermetic, ceramic, surface mount package.

36.2.3 Microstructure Release

Release stiction occurs when microstructures stick together after the sacrificial material is removed in a wet etch. It can cause considerable yield loss and must be considered in devices like capacitive pressure sensors and accelerometers that have closely spaced, mechanically compliant microstructures. Piezoresistive pressure sensors are not susceptible to release stiction, because these sensing diaphragms are not near other surfaces.

Release stiction is most frequently observed in silicon MEMS devices that use a sacrificial oxide. The oxide is removed by etching in wet HF, rinsed in deionized water, and then dried. Water promotes growth of a hydrophilic surface oxide. It also has a high surface tension. To minimize energy, the high surface tension in the shrinking water droplets causes the microstructures to be pulled together. When they touch, clean oxide surfaces stick, thus destroying device functionality. *Maboudian* et al. [36.17] review release stiction mechanisms, as well as the solutions that have been reported in the literature.

Some manufacturers do not publicly discuss their fab process. Those that do avoid release stiction by using gas phase processes to remove the sacrificial material. Texas Instruments uses photoresist, rather than silicon dioxide as the sacrificial material in their DMD manufacturing process. Two photoresist layers are under the aluminum mirrors. The wafer is also covered with a third organic layer to provide mechanical damage protection and allow for particle cleaning after the wafer is singulated into individual devices. By removing these organics in a dry etch process, the stiction problems that characterize wet etch processes are avoided.

Analog Devices avoids release stiction by dividing its accelerometer process flow into several steps, each of which is well controlled with standard manufacturing equipment. After the microstructure is formed, a few small channels are etched in the sacrificial oxide and filled with photoresist. These photoresist pedestals hold the microstructures in place when the remaining sacrificial oxide is etched, rinsed, and dried. The pedestals are then removed in a dry etch process. *Core* et al. [36.39] and *Sulouff* [36.5] describe this technique in more detail.

Bosch avoids release stiction by holding accelerometer wafers above an HF solution. HF vapors from the solution react with the sacrificial oxide, converting it to gaseous SiF_4 and water. The wafers are heated to prevent water from condensing. This process is noted in *Offenberg* et al. [36.40]. *Anguita* et al. [36.41] describe a similar process.

36.2.4 Wafer Bonding

To date, the growth of MEMS wafer bonding has been driven by three factors:

- Sealing microstructures by bonding wafers together addresses two sources of yield loss in MEMS manufacturing: wafer singulation and particles.

- Wafer-level mounting can be a cost-effective way to control stress in products that are sensitive to variations in mount stress.
- Fabrication of 3-D microstructures from elements that are formed on multiple wafers.

Piezoresistive pressure sensor wafers have been anodically bonded to borosilicate glass wafers for about 25 years. The earliest products were manufactured using little more than a hot plate and a high-voltage power supply. The era of custom built manual equipment has passed, because both Electronic Visions and Karl Suss now offer automated production-worthy tools for anodic, glass frit, organic, and silicon-silicon wafer bonding. *Schmidt* [36.42] reviews wafer-wafer bonding processes, while *Mirza* [36.43, 44] addresses MEMS wafer-level bonding applications and equipment.

Anodic Bonding

Anodic bonding is commonly used to seal glass wafers to the back side of bulk micromachined pressure sensor wafers. The process requires that a silicon wafer be placed in intimate contact with a glass wafer that contains a mobile ion at elevated temperature. An applied electric field causes mobile ions (usually sodium) in the glass to move away from the silicon interface toward the cathode at the other side of the glass. Bound negative charges remain in the glass near the silicon interface. These charges produce an electric field that pulls the wafers together and drives oxygen across the interface to anodically oxidize the silicon surface. Hermetic seals are routinely produced between flat wafers when particles are rigorously excluded. Process conditions depend on the glass composition and thickness, but 500–1,000 V at 400 °C with 10 min cycle times is typical. Borosilicate glasses with thermal expansion coefficients close to silicon are used to minimize stress. Anodic bonding promotes surface conformation so hermetic glass-silicon seals can be formed with surface grooves as deep as 50 nm [36.45]. This process has been demonstrated to work with many material combinations [36.46].

Glass Frit Bonding

Glass frit bonding reapplies techniques and materials developed for hybrid processes and cerdip sealing. It is often used to seal pressure sensor wafers to silicon substrate wafers. A second common application is to glass-frit seal bulk-micromachined silicon cap wafers over the microstructures in accelerometer wafers. In this process, fine glass powder is dispersed in an organic binder to form a paste. This paste is screen printed or stenciled in the desired pattern on a wafer. The wafer is then passed through a furnace (typically 430–500 °C). This causes the organics to burn off and the individual glass particles to coalesce into the desired pattern.

The wafer bonding process starts with a wafer prepared as described in the preceding paragraph. This wafer is aligned to a second wafer, where they are held in intimate contact and heated until the glass softens. Liquid glass readily wets the surface of the adjacent wafer when at least trace amounts of oxygen are present. The liquid-wetting mechanism produces hermetic seals even when the wafer surfaces are relatively rough. However, seal widths less than 100 μm are difficult to achieve. Fixtures that maintain wafer alignment through the bonding process are also required. Low-melting lead oxide and boron oxide glasses are commonly used in processes that typically run at 450 °C. Glass wet-out occurs quickly, but process cycle times are limited by the cooling rate (rapid cooling can cause stress gradients and cracking in the glass if proper design practices are not followed). Glass frit bonding to semiconductor wafers requires a good understanding of glass composition effects and process conditions [36.47].

Silicon–Silicon Wafer Bonding

Silicon-silicon bonding has been demonstrated in many IC and MEMS applications over the last 30 years. These processes bring highly polished wafers into intimate contact and are often promoted by a thin hydrophilic oxide that is left on the surfaces by the aqueous cleaning process. Clean, well polished wafers will bond at room temperature. However, heating (800–1,200 °C) increases bond strength by an order of magnitude. A fundamental difference between MEMS silicon–silicon bonding and either anodic or glass frit bonding is that it is used to produce complex microstructures that cannot be made in one wafer. In contrast, most anodic and glass frit bonding applications address assembly and packaging issues.

Recent silicon-silicon advances have solved technical factors like stress control that had limited MEMS applications. For example, Analog Devices balances the stresses at oxide interfaces and the handle wafer to produce flat, three- and four-layer SOI wafers [36.48, 49]. The thickness of each layer is precisely controlled using grinding and CMP (chemical-mechanical polishing). Intermediate layers can be patterned, electrically isolated, electrically interconnected and locally etched to produce single-crystal silicon microstructures that are hundreds of microns thick on CMOS compatible wafers. With this new capability, several organizations are fab-



Fig. 36.14 Array of steerable mirrors designed for fiber optic network switching applications. The gimbal-mounted mirrors in this experimental product are electrostatically driven. Closed loop control based on capacitive sense electrodes ensures that the proper angle is maintained. High and low voltage circuits are integrated with mirrors on one chip. (Courtesy of Micromachined Products Division, Analog Devices, Inc.)

ricating MEMS devices for biotech, automotive, and communications applications. One example is the array of gimbal-mounted mirrors shown in Figs. 36.14 and 36.15. These mirrors can be tilted in any axis to steer light between fibers in optical fiber bundles. The mirrors are driven by electrostatic force applied from electrodes that are patterned under the mirrors. Capacitance measurements based on a second set of electrodes are also part of a closed loop control system that maintains position control. Integration of high voltage drive electronics, low voltage control electronics, and MEMS mirrors would be impractical without this SOI capability and related MEMS processes.

36.2.5 Wafer Singulation

The cooling water and the particles generated in a standard IC diamond saw will destroy MEMS wafers unless some form of protection is used. Manufacturers solve this problem in several ways. Bosch and Motorola bulk micromachine cap wafers that are glass frit bonded to surface micromachined wafers. The caps protect the microstructures from water, particles, and mechanical damage so the wafers can be sawn with standard equipment.

The optical function of DMD chips required Texas Instruments to find a different solution for DMD wafers. Originally, they used a partial saw process on wafers that were protected with an organic film. This allowed wafer-level testing, but caused particle contamination and die loss when wafers were broken along the partial saw cuts. They now use a standard saw process, but do it before the mirrors are released. The wafers have the protective organic film over the mirrors, so normal cleaning processes are used. The singulated chips are



Fig. 36.15 View of the deep etched trenches, interlayer connections, and electrodes under a mirror of the SOI MEMS device illustrated in Fig. 36.14. (Courtesy of Micromachined Products Division, Analog Devices, Inc.)



Fig. 36.16a–c Analog Devices "upside-down" saw process flow. **(a)** Saw tape is mounted on a saw frame. Holes are punched in the tape to match the microstructures on the wafer. The wafer is mounted-upside down on the saw tape and aligned so that the microstructures are in the holes. **(b)** A second layer of tape is placed over the first layer to form watertight pockets. **(c)** Wafer is aligned and sawn using standard equipment (adapted from [36.50])

mounted in ceramic packages before the organic layers are dry etched. This flow eliminates a primary source of particle contamination and problems associated with handling partially sawn wafers [36.6].

Analog Devices singulates uncapped MEMS wafers using an upside-down saw process and standard equipment and fixtures that are slightly modified (Fig. 36.16) (*Roberts* et al. [36.50]). A major attraction is that it allows wafer-level test and trim, so only chips that meet the product specification are assembled. It also avoids the added cost and yield loss associated with wafer capping. Although originally developed for accelerometers, this technology was extended to gyro wafers and to wafers that contain optical mirror arrays (see Figs. 36.13 and 36.14).

36.2.6 Particles

Particles cause yield loss in every product that has closely spaced movable microstructures. They also cause large area defects in anodic and silicon-silicon wafer bonded processes. Commercial MEMS suppliers use several solutions:

1. Cap the MEMS wafers before they leave the wafer fab clean area. Bosch and Motorola use this approach to produce accelerometer products (Fig. 36.12). It solves the wafer saw dilemma faced by most MEMS suppliers and allows the use of plastic packaging. Disadvantages include yield loss due to cap misalignment and stress, as well as the cost of the added capping steps. Hermeticity testing is also difficult because capped devices require sensitivity levels beyond the capabilities of standard analytical test equipment.
   Capping protects MEMS from particle contamination during assembly, but does not prevent wafer fab contamination. A greater concern is that glass-frit seal processes and equipment do not usually meet fab cleanliness standards. Once capped, inspection is essentially impossible.
2. Analog Devices and Texas Instruments assemble their MEMS products in clean rooms. This option increases capital costs. TI invested in environmental and process control, rather than develop optical quality capping for the DMD. Analog Devices had solved the wafer saw dilemma, so environmental and process control was the low risk path for particle control.

Particle control is central to high yield and reliability. The first control level is to minimize particle contamination through proper handling procedures, equipment maintenance, environment controls, and process design. The DMD protective organic film illustrates how process design can be used to control particles. This film allows the wafer to be cleaned after wafer saw and die attach.

Even with the best of controls, some particle contamination occurs in every clean room. Electrical tests in the automated wafer- and package-level test programs are designed to detect particles in Analog Devices products. Texas Instruments also finds particles in DMD products by driving each mirror in an array to ensure proper operation. Such screens are good but imperfect. Attempts have been made to replace visual inspection with automated particle inspection based on pattern recognition software. To date, however, machine vision systems have not been able to match the human eye and mind aided by a high quality microscope.

36.2.7 Electrostatic Discharge and Static Charges

Susceptibility to electrostatic discharges (ESD) led semiconductor manufacturers to make ESD avoidance a central criterion in equipment and fixture design, as well as handling procedures. Control of ESD events on the manufacturing floor is only the first step. Analog Devices and Texas Instruments incorporate ESD protective circuitry into their MEMS products as a standard practice to avoid failures in their customer assembly lines, as well as in the final system.

Most MEMS products use electrostatic force to actuate or control suspended microstructures. This design characteristic introduces performance parasitics and failure mechanisms that are not encountered in normal IC devices. For example, charges that build up on a dielectric surface can deflect unshielded microstructures, even when they are several millimeters apart. Such effects are insidious, because closed loop control systems do not always correct for electrostatic-induced errors.

Section 36.3.1 discusses surface treatments designed to suppress stiction caused by surface forces. These treatments often produce a dielectric surface. If the dielectric properties of the treatment and the device design cause the surface to hold a charge, that anti-stiction coating may actually promote electrostatic stiction! Thus, any "solution" must be critically evaluated in order to identify and remove undesirable side effects.

36.2.8 Package and Test

IC packages are environmental (mechanical, chemical, electromagnetic, optical) barriers that protect the chips from surrounding media. Only power and electrical signals and inertial forces pass unimpeded, so most MEMS sensors and actuators require that this barrier be selectively penetrated. Package and test functions are unique to each company's design and MEMS product type. Standard semiconductor packaging equipment and processes are modified when possible. However, even the line of demarcation that separates wafer fab from packaging is unique to each product.

High volume MEMS testing is even more challenging than MEMS packaging. In essence, the task is to measure and trim the response of products mounted in non-standard packages to calibrated stimuli over a range of temperatures. Automated IC test equipment does not have the calibrated pressure, acceleration, or optical test functionality required for this task. *Maudie* et al. [36.51] detail the test system elements that are required to support volume production of MEMS products.

Pressure Sensors

Pressure sensors are extremely susceptible to stress, so die-attach stress variations broaden performance distributions. The uniformity produced by wafer-level bonding is a primary reason why these processes are used to make the first-level package in many pressure sensor products. Soft silicone and fluorosilicone rubber products are often used to attach the sensor chip to the package to maximize isolation from mechanical stresses transmitted through the mount.

Most semiconductor products are assembled in plastic packages. The automated plastic presses transfer viscous epoxy compounds into multi-cavity molds at 175 °C and pressures near 6,900 kPa (1,000 psi). The hot liquid plastic creates high shear stress as it flows around devices in the mold cavities. Further stresses develop as the plastic hardens and cools. Even if this technology were adapted to create pressure ports in packages, the mold stresses would substantially affect pressure sensor performance.

Pre-molded plastic packages avoid the stress problem and incorporate pressure ports (Figs. 36.8 and 36.9). Polyphenylene sulfide (a high temperature thermoplastic) and medical-grade polysulfone are commonly used to make pre-molded pressure sensor packages.

The liquid or gas that is being measured can cause corrosion of interconnects and chip metallurgy, as well as parasitic leakage paths in the sensor. For that reason, a barrier such as silicone or fluorosilicone gel is often applied over the sensor. The soft gel transmits pressure with high fidelity over a wide temperature range and passivates the chip against many types of chemical attack. Parylene is also used for this purpose. This vapor-deposited organic coating is much stiffer than the gels, so thickness is typically controlled near 1 μm.

Petrovic et al. [36.52] tested the ability of fluorosilicone gels and several Parylene C thicknesses to protect powered pressure sensors against automotive and white goods benchmark liquids. One purpose of their study was to propose and demonstrate a formal media compatibility test protocol for pressure sensors similar to the IC industry standard tests. They found that the lifetime of sensors coated with both gel and parylene was considerably longer than sensors coated with either gel or parylene alone. *Petrovic* [36.53] later summarized the advantages and limitations of gels, parylene, and other techniques.

Figure 36.8 has examples of commercial plastic packaged pressure sensors. Pressure calibration equipment and software must be custom designed and built for these products. However, most pressure products are dimensioned to match IC packages in order to maximize compatibility with standard IC test handlers.

The harsh environment of some under-the-hood applications has been used to justify the high cost of metal cavity packages. For example, Bosch introduced a piezoresistive MAP sensor with signal conditioning that was hermetically sealed in an evacuated T08 header [36.54]. In-package trim was based on planar thyristors that were zapped as needed to bring the sensor within spec. The design avoided chip metallurgy corrosion and surface electrical parasitics by using the back surface of the silicon diaphragm as the fluid interface.

Much more expensive packaging is used in the pressure and differential pressure transmitters that are designed for industrial process control. These products seal the sensor in silicone oil behind thin metal diaphragms. Such products can measure pressure differences of 20 kPa superimposed on a pressure of 20,000 kPa (3,000 psi) over wide temperature ranges with high accuracy and stability. Soft die attach materials decouple the sensor from thermal stresses that arise when they are mounted in metal housings. Note, however, that silicone die attach materials cannot be used if the transmitter is filled with silicone oil. Fluorosilicones are one alternative. Piezoresistive sensors have been used in pressure and differential pressure transmitters since the 1980s. *Fung* et al. [36.55] describe a relatively new version. This product uses a piezoresistive polysilicon sensor to measure both absolute and differential pressure on the same chip. See *Chau* et al. [36.56] for early work on a multirange version of this technology.

Image Projection

The Texas Instruments DMD poses unusual challenges because the package lid must be an optical quality glass with anti-reflection coatings to improve optical performance and reduce heat load. The glass lid has opaque borders around the image area to minimize stray light effects and create a sharp edge on the projected image. It is fused to Kovar frames to produce lid sub-assemblies. The package base is a multilayer alumina substrate with co-fired tungsten to provide the electrical interconnects. The package sidewalls are formed by brazing a Kovar seal ring to the substrate. Heat dissipation through this substrate is a significant consideration because the service life of DMD mirror hinges (Fig. 36.6) is largely determined by operating temperature [36.57]. Excessive high temperature creep results in "hinge memory" and would cause a gradual drift in mirror orientation.

The DMD chips are die attached in the package cavity before the mirrors are released. A dry etch process is used to remove the organic sacrificial layers. The die are then passivated and tested. Getter strips are attached on the inside surface of the glass at the sides to control vapor composition in the package cavity before the lid is aligned and seam sealed to the package seal ring. Image quality requirements place stringent requirements on handling, alignment, and spacing tolerances. Thermal stresses also arise when dissimilar materials are joined in high temperature processes to produce the final hermetic package. The DMD packages (Fig. 36.7) and the related processes are discussed further in *O'Connor* [36.58], *Mignardi* et al. [36.6], *Bang* et al. [36.59], and *Poradish* et al. [36.60].

DMD mirror release does not occur until after die attach. This has advantages with respect to wafer saw and particle suppression, but it sacrifices the economic attraction of wafer-level testing. There is no commercial test system capable of combining CMOS electrical testing with 100% testing of optical mirrors. Therefore, a custom electro-optic test system was built around an x-y-θ translation stage with a CCD camera, light source, control hardware and software, and test programs [36.6]. A characteristic of the papers published by the DMD group is their effective use of this test system to examine problems and statistically validate the solutions.

Assembly of the DMD on the projector electronics board requires alignment with the system optics, in addition to electrical connections. Initially, the DMD was held with a plastic clamp and electrically connected through elastomer pads that had alternating layers of conductive and nonconductive material. This allowed easy replacement if a DMD was damaged during assembly. However, the impedance of this connector system was too high for new, higher speed products. Electrical intermittents were also observed. Therefore, it was replaced [36.61] by a grid of c-shaped springs (cLGA$^{\text{TM}}$, Intercon Systems, Inc., Harrisburg, PA).

The DMD has about 40% of the business and entertainment image projection market [36.62]. Products based on liquid crystal technology serve the balance of the market. Market share is largely driven by price, so considerable effort has been placed on reducing the cost of DMD package and board-level assembly. *Migl* [36.61] reports on the assembly benefits achieved by replacing the epoxied heat sink with a mechanically attached heat sink. *Jacobs* et al. [36.62] describes the effort to replace the seam sealed window mount with a lower cost epoxy-bonded design. In theory, such a bond is not hermetic. However, the team realized that proper material selection, design, analysis, and use of moisture getters would produce a low humidity package through the product life. This change was not released to production. If it is implemented, success will require that adhesive bond integrity also be maintained, because the adhesive joint sustains thermal expansion and mechanical clamp stress cycling each time the projector is used.

Accelerometers and Gyros

The Bosch and Motorola capping processes are a first-level package that is applied at the end of wafer fab. After capping, the wafers can be sawn using standard equipment and do not require clean room assembly conditions. In principle, capped devices are compatible with standard plastic packaging. However, molding stresses can be a serious problem. To minimize stress, capped sensor chips are mounted on lead frames with a soft elastomer and often coated with a silicone gel to isolate the sensors from the package stress. Motorola products are calibrated by burning EPROMS after molding. Their early air bag accelerometers were molded in DIP and SIP packages for assembly on through-hole circuit boards. The shift to smaller surface mount SOIC packages reduces the quantity of plastic, so package stresses are reduced. To maintain compatibility with standard tooling in small thin plastic packages, either the cap or the MEMS wafers must be backlapped.

Analog Devices uses a near-standard saw process (Sect. 36.2.5 and Fig. 36.16), so capping is not required if hermetic cavity packages are used. Such packages are standard, but more expensive than molded plastic. A major attraction of cavity packages is that they eliminate plastic package stress (see page 1099), because the only mechanical connection between the chip and the package is through the die attach and bond wires. As a result, ADXL accelerometers and ADXRS gyro products are fully tested and trimmed on automated systems before the wafers are sawn. A lot-tracking system transfers this data to automated die attach systems. These systems are programmed to pick only chips that meet performance specifications from the wafer saw film frames. Thus, reject die are not assembled into packages. After packaging, devices are tested to ensure conformance to specification. However, package-level trim is not required, because the assembly process and cavity packages do not appreciably shift device parametrics.

The evolution of ADXL cavity packages is illustrated in Fig. 36.3. Initial products were packaged in TO-100 metal packages. This seam-sealed package is useful for development purposes. However, it is expensive and incompatible with the automated equipment used to assemble electronic circuit boards. Therefore, the early air bag sensors were soon switched to cerdips. Cerdips are made from low cost, molded, ceramic bases that have glass seal surfaces. The high process temperature requires use of a silver-glass die attach product. The full assembly flow includes two or three furnace passes near 450 °C to produce hermetic cavity packages.

IC products have been packaged in cerdips for decades, but through-hole circuit boards are seldom used today. A simple change in lead forming allows cerdips to be fully compatible with standard surface mount boards ("cerpacs"), so cerdips and cerpacs are assembled on the same equipment. Most of the ADXL products shipped in the late 1990s were packaged in cerpacs. However, small LCCs have become the package of choice for one- and two-axis accelerometers. The LCC (Leadless Chip Carrier) uses solder-sealed ceramic bases and metal lids. Organic die attach materials are practical, because the furnace gas is nitrogen, rather than air, and temperatures are about a hundred degrees lower than cerpac furnace temperatures. ADXRS gyros are assembled in a solder-sealed 7 mm × 7 mm ceramic ball grid array package (Fig. 36.13).

The fundamental message of this section is that IC package technology – both plastic and hermetic – is evolving very rapidly. Cost-competitive suppliers must remain cognizant of these trends in order to use them to best advantage. MEMS products that are packaged in a way that is not compatible with standard IC equipment and interfacing standards bear a significant cost premium. High package cost seriously limits market size because the price-volume curve is steep for most products. The package size trend is also critical to new market penetration. In summary, customer interface and new application requirements will continue to drive down both the cost and the size of most MEMS products.

The ADXL and ADXRS automated testers and handlers measure multiaxial linear and rotational acceleration. Analog Devices has a division that designs and manufactures automated test systems (many of the corporation's IC products have unique test requirements), so it avoided some of the problems associated with the procurement of custom-automated test equipment. MEMS suppliers have relied on custom-designed test equipment, but this situation is gradually changing. For example, Multitest GmbH now makes handlers with integrated shakers that are specifically designed for accelerometer testing.

36.2.9 Quality Systems

Quality systems are an intrinsic part of stable MEMS production. Management must drive a systemic approach to quality and set continuous improvement as a high priority goal.

Several quality systems define continuous improvement methodologies. In general, they formalize the process used to minimize defects and variations in products and in the processes used to manufacture them. Automotive supply companies must implement quality systems that meet QS-9000 [36.63] before product volume ramps up and continue them through the product life cycle. Four elements that are worthy of note:

1. *Failure Mode Effect Analysis* (*FMEA*). Early in the development phase, a team with representatives from several disciplines reviews the design (or process) in order to identify possible causes of failure. Each potential failure mode is given three numerical rankings. One ranking represents the likelihood of an occurrence, while the others rank the severity of that result and detectivity. These numerical scores are combined for each potential failure mode in order to identify the issues that merit the most attention before they become problems. FMEA spreadsheets are periodically updated as the product or process moves into production. More targeted versions are used in products or processes that are in stable production.

2. *Process Control*. Every significant process must have a "short loop" monitor to ensure stability. This measurement is tracked and statistically analyzed with respect to the control limits to identify changes before the process strays beyond the control limits.
3. *Review Boards*. Every change, unusual occurrence, and proposed solution is assessed by boards that meet on a regular basis to ensure that it does not put product quality at risk. Affected production material is put aside until the appropriate board approves its release. This may appear to be expensive and bureaucratic. However, the cost of a scraped wafer lot is insignificant when compared to the cost of a field replacement program.
4. *Procedures and Specifications*. Each step must be fully specified and identified in the process flow, along with the appropriate metrics for each lot. The compilation of this data in a retrievable form is an essential part of every continuous improvement program. By combining these product and process databases with lot tracking software, Pareto charts linking yield loss and test failures to process variations can be identified and eliminated. Experience has shown that unexpected second-order effects are present in every production line – but data-driven decisions on indirect effects cannot be made on small test populations.

Implementation of a continuous improvement program requires well-informed failure analysis teams, methodologies, and programs. Such analyses start with gathering facts and making relatively simple tests. Often this is sufficient. However, MEMS products are susceptible to uncommon failure modes, so *Walraven* et al. [36.64] gathered examples of more powerful analytical techniques and showed how they are applied to MEMS devices.

Each supplier uses the information and insights gathered from product performance, as well as control and yield data at different points in the process flow to refine their operations. *Douglass* [36.65], for example, outlined the yield loss and failure mechanisms observed in early Texas Instruments DMD products. Concerns like hinge memory, hinge fatigue, particles, stiction, and environmental robustness were each addressed and mitigated by focused teams. For example, *Mignardi* et al. [36.6] describe the partial wafer saw process used in the original DMD manufacturing flow process. Breaking these delicate wafers into individual product chips generated particles that caused yield loss and were potential sources of field failures. A new flow based on a standard full saw process eliminates this particle source. The result was an increase in both yield and reliability. Hinge fatigue characterization showed that bulk metal fatigue models do not properly describe thin film behavior. The hinge memory effort required an understanding of how thin film metal creep is affected by alloy composition and the environment [36.57]. Stiction control involves surface passivation, spring design, mirror dynamics, and moisture level [36.26, 65]. These publications give an insight into the quantities of data and the time required to bring robust products to market. They also illustrate how data-based evaluations can uncover unexpected effects like the acceleration of hinge creep by adsorbed moisture [36.26].

The second continuous improvement example applies to MEMS integration. High yield loss is perceived to be a serious risk when electronics and MEMS are integrated on one chip. Indeed, the initial yields on the Analog Devices integrated MEMS accelerometers were not impressive. However, it increased each year due to the work of many mission-oriented teams. Yield has reached defect density limited levels because the teams eliminated all significant failure mechanisms.

Coincident with the annual yield increases were reductions in customer failure rates. Failure rates in Analog's accelerometer products are in the low single digit ppm range. Quality does pay.

36.3 Stable Field Performance

Some topics discussed in Sect. 36.2 like particles and ESD are equally relevant to long-term stability. Most microstructure products have elements that are in close proximity, so stability is also affected by surface characteristics and mechanical shock.

36.3.1 Surface Passivation

Early, 1970s-era piezoresistive pressure sensors were not passivated. Like early ICs, these wafers only had oxide over the piezoresistors. Performance was inconsistent and drifted over time, because surface interactions with moisture and other atmospheric gases created a variety of shunts, parasitics, and charging issues.

Electrical Surface Passivation

The introduction of silicon nitride passivation and conductive field plates led to stable products that were hitherto unobtainable. The ability to achieve measurement stability was absolutely critical to growth of the MEMS pressure sensor industry.

Aside from pressure sensors, few MEMS products are passivated. Indeed, standard plasma nitride processes are usually impractical, because they produce dielectric coatings that support static charges. Such charges can cause electrical drift, or be the source of electrostatic forces that cause stiction.

There have been published reports attributing instability to the lack of passivation on microstructures. For example, Analog Devices implemented a special process in ADXL50 accelerometers before the product was released in order to suppress high temperature electrical drift [36.66]. This was not a moisture effect, because it occurred in dry nitrogen packages. Later ADXL designs eliminated the root cause.

Scientists at Lucent Technologies [36.67] observed anodic oxidation in polysilicon electrodes used to electrostatically drive mirrors in optical cross-connect products. If allowed to occur, this corrosion mechanism would cause the mirror position to drift and the product to eventually fail. The study concluded that, within the limits of the test, maintaining low moisture in these optical packages eliminates anodic oxidation.

The preceding paragraphs suggest that lack of MEMS passivation can affect long-term product stability. This issue is very design-related and can be driven by factors other than humidity. Even when low package humidity is determined to be adequate, design reviews should consider how normal manufacturing variations, outgassing and diffusion over the product life affect the moisture level in the gas adjacent to the microstructures.

Mechanical – Stiction and Wear

In-use stiction is difficult to predict and may not become an issue until manufacturing volumes increase, or when endusers handle the part in ways that are not anticipated [36.68]. The resulting product liability and field replacement programs carry substantial financial costs and have caused MEMS suppliers to withdraw from the market. End users have little tolerance for failure. Since in-use stiction is a failure mechanism in MEMS devices, a company that solves this problem creates an effective market barrier against competitors.

The scale of this problem varies between product areas. For example, the Texas Instruments DMD has moving mirrors that are designed to touch down on a substrate and later release. This product must address both stiction and wear. In contrast, the accelerometer products from Analog Devices, Bosch, and Motorola have proof masses that are suspended on compliant springs. By design, an automobile collision only displaces the proof mass by a few percent of the gap that separates it from adjacent surfaces. It is difficult to generate a shock wave in an air bag module that is sufficient to cause these proof masses to contact adjacent surfaces (acceleration levels of several thousand g are required). However, handling of the discrete packaged parts during test, shipment, and module assembly frequently cause shock events that bring MEMS surfaces into contact. For example, *Li* et al. [36.69] used both math modeling and tests to show that dropping a packaged MEMS accelerometer from the height of a table top generates several tens of thousands of g in the device when it lands on the floor. Thus, noncontacting MEMS products must be designed to withstand at least transient stiction.

Design. When shock, vibration, or functional operation causes MEMS elements to touch, the mounting springs are designed to pull them apart (Fig. 36.10). High stiffness springs are desirable to suppress stiction, but low stiffness springs increase measurement sensitivity and signal-to-noise ratio. Thus stiction is a fundamental MEMS design constraint that often limits product performance. Each manufacturer has proprietary design practices to address this performance versus reliability trade-off. In general, designers suppress stiction by minimizing the sources and applying supplementary techniques to ensure recovery when contact occurs:

1. Thorough analysis and testing to move harmful resonances beyond the range where they might be excited. Note that MEMS component-level analysis is insufficient – this is a system issue based on the packaged part as it is handled through manufacturing, system assembly, and end use.
2. Surface modification (discussed in the next section).
3. Minimizing contact area by integrating bumps and "stoppers" into the design [36.70].
4. Elimination of dielectric surfaces that may accumulate surface charges and result in electrostatic attraction.

5. Release of DMD mirrors from the touchdown position is assisted by pulsing the reset voltage to excite a mirror resonant frequency [36.65, 71].
6. Use of gas-filled packages to reduce contact velocity, as discussed later in this chapter.
7. ESD-protected designs that prevent voltage transients that may cause electrostatic attraction.

The only product in significant production that contains MEMS elements that are designed to touch is the Texas Instruments DMD. The proprietary aluminum alloy springs used in the mirror contact points touch and release millions of times during the product life. Considerable development was required to overcome metal creep that occurred in early designs.

Surface Modification. In addition to the touchdown springs, early DMD die were treated with perfluorodecanoic acid vapor before the glass lid was sealed onto the package. This treatment [36.72] created a low energy monolayer coating that suppressed initial stiction. However, improvements were required to achieve longer wear life, higher production rates, and lower contamination levels. A new process [36.73] places capsules inside DMD packages. After cleaning, the packages are immediately sealed. An oven bake releases anti-stiction vapor from the capsules to create a monolayer organic coating on surfaces inside these sealed packages. Excess anti-stiction material in the capsules maintains a low vapor pressure in the package cavities throughout the product life. Therefore, wear damage at the mirror contact springs is continuously repaired to prevent stiction failures before they occur.

Maintaining a low level of organic vapor inside the DMD reapplies a concept used with other organics to prevent corrosion of electronic metallurgy and contact fretting of separable connectors (see, for example, [36.74, 75]). These treatments have been shown to add years to the useful life of electronic systems that are in enclosures but also exposed to aggressive environments.

Stiction can be minimized by design and process spin-offs – stiff springs, control of contact area, etch residues, etc. Some suppliers design within these limits; others seek to modify the MEMS surfaces. The requirements of any surface modification technology are quite substantial. In addition to normal manufacturing requirements (stable, scalable process and materials), the process must be conformal and must uniformly treat all areas, including microstructure bottom and side surfaces. If a conductive material is used, it must somehow be patterned in order to avoid electrical shorting. If a dielectric surface is formed, it must be extremely thin because thick dielectrics support surface charges. Such charges cause performance shifts and induce electrostatic stiction.

Since devices with movable microstructures are particularly susceptible to stiction, most suppliers who develop production-worthy surface modification processes consider this information a trade secret. Analog Devices chose to patent portions of its technology. The following paragraphs give an overview of the published Analog Devices surface treatment technologies. *Martin* [36.66] describes the evolution of these technologies from 1992 to 1999. Further information is contained in *Martin* et al. [36.76] and *Martin* [36.77].

The earliest of the published Analog surface treatment technologies was implemented after stiction was observed during automated testing and module assembly of air bag sensors that were packaged in cerdips. Cerdip assembly typically includes at least two furnace processes in air at 440–500 °C, so they seldom contain organic materials. The high temperature furnace air thermo-oxidizes adsorbed materials and removes them from the MEMS surface. The resulting surfaces are extremely clean. Unfortunately, clean inorganics have high surface energies. Therefore, adjacent microstructures readily stick together if shock and vibration during handling cause them to touch. Cerdips (and the surface mount cerpacs) have very low moisture levels (Mil specs allow up to 5,000 ppm moisture, but < 100 ppm moisture is common in a well controlled manufacturing line). Deliberately raising the moisture level was found to be a potential solution because, within limits, moisture adsorption reduces surface energy. However, the solution adopted by Analog Devices in the mid-1990s was the anti-stiction agent (ASA) process. This process involved dispensing a controlled amount of a pure siloxane liquid (ASA) into each package immediately before sealing. ASA selection was based on thermo-oxidative stability, low volatility, purity, and the requirement that it be a liquid at the dispensing temperature. As packages heat in the furnace, adsorbed material on the microstructures is removed, leaving chemically active, high energy surfaces. Further heating volatilizes the ASA. Before escaping into the furnace, the ASA vapor surrounds the reactive MEMS surfaces and chemically bonds to them. The result is infusion of organic groups into the native oxide surface. Organic-rich surfaces are unreactive and have low surface energy. Thus the treatment is self-limiting after the first vapor molecules react. Obviously, ASA volatilization must be complete before the glass softens and seals the package cavity. Some

ASA degrades in this process. However, silicone thermo-oxidation simply adds a few angstroms of silicon oxide to the native oxide, so the ASA process, by design, is non-contaminating.

Although variations and refinements of the ASA process were developed, this technology required that each individual package be treated. Automated dispense equipment made ASA acceptable when product volumes were moderate. However, as production approached several million per month, it became evident that a wafer-level anti-stiction process was desirable.

Assessment of candidate processes and materials led to a vapor treatment based on a custom-synthesized solid polymeric siloxane. This polymer is volatilized in a standard CVD furnace that treats up to a hundred wafers at a time. Repeatability is extraordinary because thickness variation within a furnace run, or from run to run, is only about one angstrom.

Package Environment Effects. The viscosity and density of the gas that contacts MEMS resonators limit the device Q, so resonant devices are often designed to operate in vacuum. Unfortunately, this makes them susceptible to handling damage. Viscous fill gases reduce destructive excursions of high-Q microstructures when they are mechanically shocked. They also provide squeeze film damping to cushion the contact event as surfaces approach each other. None of the high volume MEMS products on the market are evacuated. Presumably, this is due to the high cost of vacuum packaging and the susceptibility to handling damage.

Many investigators believe that suppression of in-use stiction requires low humidity in the package. This view is not surprising because most MEMS research groups have observed stiction caused by aqueous surface tension during microstructure release. However, in-use stiction and wear test results published by several investigators lead to a different conclusion [36.76, 78–83]. In general, they find high stiction in both dry and moist environments. However, stiction is substantially suppressed at intermediate humidity levels (approximately 15–40 % relative humidity at room temperature). This is equivalent to a moisture level of 3,000–10,000 ppm. Note that the limits cited by different authors vary considerably due to the use of different materials and test conditions. Stiction at low humidity is probably caused by high surface energy on inorganic oxides that do not have adsorbed surface films. The low stiction and wear rates observed at intermediate humidity are attributed to the passivating and lubricating effects of adsorbed water. Capillary forces caused by the high surface tension of water become dominant at high humidity.

36.3.2 System Interface

MEMS products are mounted in systems that have much greater mass than the device itself. For this reason, it is difficult to transmit a mechanical shock wave to a MEMS sensor that is sufficient to cause failure after it is installed in a module. However, failures are possible when the devices are handled during module assembly. Improper functional response is also possible if the module mount system has a mechanical resonance that amplifies or reduces mechanical transmission under different conditions. This is a particular concern in automotive safety applications because every automobile platform has a different mechanical signature. Proper module mount design is required to ensure that the impact signal from an automobile crash is properly transmitted to air bag modules.

Suppliers of large IC die closely examine board-level stresses in order to minimize solder joint fatigue. Such stresses are more serious in MEMS products because the device, as well as the package are susceptible to mounting conditions. Furthermore, customer processes impose these stresses, so a supplier may have little information with respect to their origin or existence. One solution is to define and qualify a product-specific mount system, as Texas Instruments has done with the DMD. The ideal, however, is to devise products that are compatible with standard board footprint and assembly processes. This challenge became more difficult with the shift from through-hole to surface mount technology, because the mechanical isolation provided by the package pins is no longer present. Small package size, in-package, and within-chip isolation techniques, as well as thorough package-board stress analysis are used to address this concern.

References

36.1 J. B. Angell, S. C. Terry, P. W. Barth: Silicon micromechanical devices, Sci. Am. **248** (1983) 44–50

36.2 T. A. Core, W. K. Tsang, S. J. Sherman: Fabrication technology for an integrated surface-micromachined sensor, Solid State Technol. **36**(10) (1993) 39–47

36.3 W. Kuehnel, S. Sherman: A surface micromachined silicon accelerometer with on-chip detection circuitry, Sens. Actuators A **45** (1994) 7–16

36.4 K. H.-L. Chau, R. E. Sulouff Jr.: Technology for the high-volume manufacturing of integrated surface-micromachined accelerometer products, Microelectron. J. **29** (1998) 579–586

36.5 B. Sulouff: Integrated surface micromachined technology. In: *Sensors for Automotive Technology*, Sensors Applications, Vol. 4, ed. by J. Marek, H.-P. Trah, Y. Suzuki, I. Yokomori (Wiley-VCH, Weinheim 2003) Chap. 5.2

36.6 M. A. Mignardi, R. O. Gale, D. J. Dawson, J. C. Smith: The digital micromirror device – A micro-optical electromechanical device of display applications. In: *MEMS and MOEMS Technology and Applications*, ed. by P. Rai-Choudhury (SPIE, Bellingham 2000) Chap. 4

36.7 K. Nunan, G. Ready, J. Sledziewski: LPCVD & PECVD operations designed for iMEMS sensor devices, Vac. Technol. Coat. **2**(1) (2001) 26–37

36.8 M. Williams, J. Smith, J. Mark, G. Matamis, B. Gogoi: Development of low stress, silicon-rich nitride film for micromachined sensor applications, *Micromachining and Microfabrication Process Technology VI*, Proc. SPIE **4174**, ed. by J. Karam, J. Yasaitis, Proc. SPIE **4174** (2000) 436–442

36.9 Z. Zhang, K. Eskes: Elimination of wafer edge die yield loss for accelerometers, *Micromachining and Microfabrication Process Technology VI*, ed. by J. Karam, J. Yasaitis, Proc. SPIE **4174** (2000) 477–484

36.10 G. Bitko, A. C. McNeil, D. J. Monk: Effect of inorganic thin film material processing and properties on stress in silicon piezoresistive pressure sensors, Proc. Mat. Res. Soc. Symp. **444** (1997) 221–226

36.11 A. Hein, S. Finkbeiner, J. Marek, E. Obermeier: Material related effects on wet chemical micromachining of smart MEMS devices, *Micromachined Devices and Components V*, ed. by P. French, E. Peeters, Proc. SPIE **3876** (1999) 29–36

36.12 B. Sulouff: Commercialization of MEMS automotive accelerometers, 7th International Conference on the Commercialization of Micro and Nano Systems (COMS), Ypsilanti 2002 (MANCEF, Albuquerque 2002) 267–270

36.13 H. Weinberg: MEMS sensors are driving the automotive industry, Sensors **19**(2) (2002) 36–41

36.14 J. Marek, M. Illing: Microsystems for the automotive industry, Electron Devices Meeting, IEDM Technical Digest International, San Francisco 2000 (IEEE, New York 2000) 3–8

36.15 D. S. Eddy, D. R. Sparks: Application of MEMS technology in automotive sensors and actuators, Proc. IEEE **86**(8) (1998) 1747–1755

36.16 R. Verma, I. Baskett, B. Loggins: Micromachined electromechanical sensors for automotive applications, SAE Special Pub. **1312** (1998) 55–59

36.17 R. Maboudian, R. T. Howe: Critical review: Adhesion in surface micromechanical structures, J. Vac. Sci. Technol. B **15**(1) (1997) 1–20

36.18 U. Srinivasan, M. R. Houston, R. T. Howe, R. Maboudian: Alkyltrichlorosilane-based self-assembled monolayer films for stiction reduction in silicon micromachines, J. Microelectromech. Syst. **7**(2) (1998) 252–260

36.19 B. H. Kim, T. D. Chung, C. H. Oh, K. Chun: A new organic modifier for anti-stiction, J. Microelectromech. Syst. **10**(1) (2001) 33–40

36.20 S. Pamidighantam, W. Laureyn, A. Salah, A. Verbist, H. Tilmans: A novel process for fabricating slender and compliant suspended poly-Si micromechanical structures with sub-micron gap spacing, 15th IEEE 2002 Micro Electro Mechanical Systems (MEMS) Conf. (IEEE, New York 2002) 661–664

36.21 B. C. Bunker, R. W. Carpick, R. A. Assink, M. L. Thomas, M. G. Hankins, J. A. Voigt, D. Sipola, M. P. de Boer, G. L. Gulley: Impact of solution agglomeration on the deposition of self-assembled monolayers, Langmuir **16** (2000) 7742–7751

36.22 Y. Jun, V. Boiadjiev, R. Major, X.-Y. Zhu: Novel chemistry for surface engineering in MEMS, *Materials and Devices Characterization in Micromachining III*, ed. by Y. Vladimirsky, P. Coane, Proc. SPIE **4175** (2000) 113–120

36.23 R. Maboudian, W. R. Ashurst, C. Carraro: Self-assembled monolayers as anti-stiction coatings for MEMS: Characteristics and recent developments, Sens. Actuators A **82**(1) (2000) 219–223

36.24 W. R. Ashurst, C. Yau, C. Carraro, R. Maboudian, M. T. Dugger: Dichlorodimethylsilane as an anti-stiction monolayer for MEMS: A comparison to the octadecyltrichlorosilane self-assembled monolayer, J. Microelectromech. Syst. **10** (2001) 41–49

36.25 W. R. Ashurst, C. Yau, C. Carraro, C. Lee, G. J. Kluth, R. T. Howe, R. Maboudian: Alkene based monolayer films as anti-stiction coatings for polysilicon MEMS, Sens. Actuators A **91**(3) (2001) 239–248

36.26 S. J. Jacobs, S. A. Miller, J. J. Malone, W. C. McDonald, V. C. Lopes, L. K. Magel: Hermeticity and stiction in MEMS packaging, 40th Annual IEEE In-

ternational Reliability Physics Symp., Dallas 2002 (IEEE, New York 2002) 136–139
36.27 Nexus Task Force Report: *Market Analysis for Microsystems 1996-2002* (NEXUS, Grenoble 1998) www.nexus-mems.com
36.28 T. Maudie, J. Wertz: Pressure sensor performance and reliability, IEEE Industry Appl. Mag. **3**(3) (1997) 37–43
36.29 Lj. Ristic, R. Gutteridge, B. Dunn, D. Mietus, P. Bennett: Surface micromachined polysilicon accelerometer, IEEE 1992 Solid State Sensor and Actuator Workshop, IEEE 5th Technical Digest, Hilton Head 1992 (IEEE, New York 1992) 118–121
36.30 M. Furtsch, M. Offenberg, H. Munzel, J. R. Morante: Influence of anneals in oxygen ambient on stress of thick polysilicon layers, Sens. Actuators **76** (1999) 335–342
36.31 P. Lange, M. Kirsten, W. Riethmuller, B. Wenk, G. Zwicker, J. R. Morante, F. Ericson, J. A. Schweitz: Thick polycristalline silicon for surface micromechanical applications: Deposition, structuring and mechanical characterization, Proc. 8th International Conf. on Solid State Sensors and Actuators and Eurosensors IX, Transducers '95, Vol. 1 (IEEE, New York 1995) 202–205
36.32 F. Laermer, A. Schilp: Method of anisotropically etching silicon, (1996) U.S. Patent 5,501,893
36.33 M. Offenberg, H. Munzel, D. Schubert, O. Schatz, F. Laermer, E. Muller, B. Maihofer, J. Marek: Acceleration sensor in surface micromachining for airbag applications with high signal/noise ratio, SAE Special Pub. **1133** (1996) 35–41
36.34 F. Laermer, A. Schilp, K. Funk, M. Offenberg: Bosch deep silicon etching: Improving uniformity and etch rate for advanced MEMS applications, Proc 12th International Conf. on Micro Electro Mechanical Systems MEMS (IEEE, New York 1999) 211–216
36.35 J. R. Martin, C. M. Roberts Jr.: Package for sealing an integrated circuit die, (2001) U.S. Patent 6,323,550
36.36 J. A. Geen, S. J. Sherman, J. F. Chang, S. R. Lewis: Single chip surface micromachined integrated gyroscope with 50 deg/hour allan deviation, IEEE J. Solid-State Circuits **37**(12) (2002) 1860–1866
36.37 K. Funk, H. Emmerich, A. Schilp, M. Offenberg, R. Neul, F. Larmer: A surface micromachined silicon gyroscope using a thick polysilicon layer, Proc. 12th International Conf. on Micro Electro Mechanical Systems MEMS (IEEE, New York 1999) 57–60
36.38 M. Lutz, W. Golderer, J. Gerstenmeier, J. Marek, B. Maihofer, S. Mahler, H. Munzel, U. Bischof: A precision yaw rate sensor in silicon micromachining, 11th International Conf. on Solid State Sensors and Actuators, Transducers '97 (IEEE, New York 1997) 847–850
36.39 T. A. Core, R. T. Howe: Method for fabricating microstructures, (1994) U.S. Patent 5,314,572
36.40 M. Offenberg, F. Laermer, B. Elsner, H. Munzel, W. Reithmuller: Novel process for a monolithic integrated accelerometer, Proc. 8th International Conf. on Solid State Sensors and Actuators and Eurosensors IX, Transducers '95 (IEEE, New York 1995) 589–592
36.41 J. Anguita, F. Briones: HF/H_2O vapor etching of SiO_2 sacrificial layer for large-area surface-micromachined membranes, Sens. Actuators A **64** (1998) 247–251
36.42 M. A. Schmidt: Wafer-to-wafer bonding for microstructure formation, Proc. IEEE **86**(8) (1998) 1575–1585
36.43 A. R. Mirza: Wafer-level bonding technology for MEMS, Proc. 7th Intersociety Conf. on Thermal and Thermomechanical Phenomena in Electronic Systems, ITHERM 2000, Vol. 1 (IEEE, New York 2000) 113–119
36.44 A. R. Mirza: One micron precision, wafer-level aligned bonding for interconnect, MEMS and packaging applications, Proc. 50th Electronic Components & Technology Conf. (IEEE, New York 2000) 676–680
36.45 S. Mack, H. Baumann, U. Goesele: Gas tightness of cavities sealed by silicon wafer bonding, Proc. 10th Annual International Workshop on Micro Electro Mechanical Systems, MEMS; IEEE Micro Electro Mechanical Systems (MEMS) (IEEE, New York 1997) 488–493
36.46 G. Wallis: Field assisted glass sealing, SAE Automotive Engineering Congress, Detroit 1971 (Society of Automotive Engineers, New York 1971) Paper 71023
36.47 S. A. Audet, K. M. Edenfeld: Integrated sensor wafer-level packaging, Proc. International Conf. on Solid State Sensors and Actuators, Transducers '97, Vol. 1 (IEEE, New York 1997) 287–289
36.48 C. Gormley, A. Boyle, V. Srigengan, S. Blackstone: HARM processing techniques for MEMS and MOEMS devices using bonded SOI substrates and DRIE, *Micromachining and Microfabrication Process Technology VI*, ed. by J. Karam, J. Yasaitis, Proc. SPIE **4174** (2000) 98–110
36.49 K. Somasundram, D. Cole, C. McNamara, A. Boyle, P. McCann, C. Devine, A. Nevin: Fusion-bonded multilayered SOI for MEMS applications, Smart Sensors, Actuators and MEMS, Proc. SPIE **5116**, ed. by J.-C. Chiao, V. Varadan, C. Cané (2003) 12–19
36.50 C. M. Roberts Jr., L. H. Long, P. A. Ruggerio: Method for separating circuit dies from a wafer, (1994) U.S. Patent 5,362,681
36.51 T. Maudie, T. Miller, R. Nielsen, D. Wallace, T. Ruehs, D. Zehrbach: Challenges of MEMS device characterization in engineering development and final manufacturing, Proc. 1998 IEEE AUTOTESTCON (IEEE, New York 1998) 164–170

36.52 S. Petrovic, A. Ramirez, T. Maudie, D. Stanerson, J. Wertz, G. Bitko, J. Matkin, D. J. Monk: Reliability test methods for media-compatible pressure sensors, IEEE Trans. Industrial Electron. **45**(6) (1998) 877–885

36.53 S. Petrovic: Progress in media compatible pressure sensors, Proc. of InterPACK'01, the Pacific Rim/International Intersociety Electronic Packaging Technical/Business Conf. & Exhibition (ASME, New York 2001) IPACK2001-15517

36.54 H.-J. Kress, J. Marek, M. Mast, O. Schatz, J. Muchow: Integrated pressure sensors with electronic trimming, Automotive Eng. **103**(4) (1995) 65–68

36.55 C. Fung, R. Harris, T. Zhu: Multifunction polysilicon pressure sensors for process control, Sensors **16**(10) (1999) 75–79

36.56 K. H.-L. Chau, C. D. Fung, P. R. Harris, J. G. Panagou: High-stress and overrange behavior of sealed cavity polysilicon pressure sensors, IEEE 4th Technical Digest, Solid State Sensor and Actuator Workshop (IEEE, New York 1990) 181–183

36.57 A. B. Sontheimer: Digital micromirror device (DMD) hinge memory lifetime reliability modeling, Proc. 40th Annual IEEE International Reliability Physics Symp. (IEEE, New York 2002) 118–121

36.58 J. P. O'Connor: Packaging design considerations and guidelines for the digital micromirror device$^{\mathrm{TM}}$, Proc. of InterPACK'01, the Pacific Rim/International Intersociety Electronic Packaging Technical/Business Conf. & Exhibition (ASME, New York 2001) IPACK2001-15526

36.59 C. Bang, V. Bright, M. A. Mignardi, D. J. Monk: Assembly and test for MEMS and optical MEMS. In: *MEMS and MOEMS Technology and Applications*, ed. by P. Rai-Choudhury (SPIE, Bellingham 2000) Chap. 7

36.60 F. Poradish, J. T. McKinley: Package for a semiconductor device, (1994) U.S. Patent 5,293,511

36.61 T. W. Migl: Interfacing to the digital micromirror device for home entertainment applications, Proc. of InterPACK'01, the Pacific Rim/International Intersociety Electronic Packaging Technical/Business Conf. & Exhibition (ASME, New York 2001) IPACK2001-15712

36.62 S. J. Jacobs, J. J. Malone, S. A. Miller, A. Gonzalez, R. Robbins, V. C. Lopes, D. Doane: Challenges in DMD$^{\mathrm{TM}}$ assembly and test, Proc. Mater. Res. Soc. **657** (2001) EE6.1.1–EE6.1.12

36.63 Automotive Industry Action Group: *Quality Systems Requirements QS-9000*, 3rd edn. (Automotive Industry Action Group of the American Society for Quality, Milwaukee 1998)

36.64 J. A. Walraven, B. A. Waterson, I. De Wolf: Failure analysis of micromechanical systems (MEMS). In: *Microelectronic Failure Analysis*, 4th edn. (ASM, Materials Park 2002) 2002 Suppl.

36.65 M. R. Douglass: Lifetime estimates and unique failure mechanisms of the digital micromirror device (DMD), Proc. 1998 36th Annual IEEE International Reliability Physics Symp. (IEEE, New York 1998) 9–16

36.66 J. R. Martin: Surface characteristics of integrated MEMS in high volume production. In: *Nanotribology: Critical Assessment and Research Needs*, ed. by S. M. Hsu, Z. C. Ying (Kluwer, Dordrecht 2002) Chap. 14

36.67 H. R. Shea, A. Gasparyan, C. D. White, R. B. Comizzoli, D. Abusch-Magder, S. Arney: Anodic oxidation and reliability of MEMS poly-silicon electrodes at high relative humidity and high voltages, *MEMS Reliability for Critical Applications*; Proc. SPIE **4180** (2000) 117–122

36.68 J. Martin: Stiction suppression in high volume MEMS products, Proc. 2003 STLE/ASME Joint International Tribology Conf. (ASME, New York 2003) 2003TRIB-266

36.69 G. X. Li, F. A. Shemansky Jr.: Drop Test and analysis on micro-machined structures, Sens. Actuators **85** (2000) 280–286

36.70 R. T. Howe, H. J. Barber, M. Judy: Apparatus to minimize stiction in micromachined structures, (1996) U.S. patent 5,542,295

36.71 L. J. Hornbeck, W. E. Nelson: Spatial light modulator and method, (1992) U.S. Patent 5,096,279

36.72 L. J. Hornbeck: Low reset voltage process for DMD, (1994) U.S. Patent 5,331,454

36.73 E. C. Fisher, R. Jascott, R. O. Gale: Method of passivating a micromechanical device within a hermetic package, (1999) U.S. Patent 5,936,758

36.74 B. A. Miksic: Use of vapor phase inhibitors for corrosion protection of metal products, Proc. 1983 NACE Annual Conf., Corrosion 83 (National Assoc. Corrosion Engineers, Houston 1983) Paper 308

36.75 D. Vanderpool, S. Akin, P. Hassett: Corrosion inhibitors in the electronics industry: Organic copper corrosion inhibitors, Proc. 1986 NACE Annual Conf., Corrosion 86 (National Assoc. Corrosion Engineers, Houston 1986) Paper 1

36.76 J. R. Martin, Y. Zhao: Micromachined device packaged to reduce stiction, (1997) U.S. Patent 5,694,740

36.77 J. R. Martin: Process for wafer level treatment to reduce stiction and passivate micromachined surfaces and compounds used therefor, (2001) International Patent Application WO 01/57920 A1

36.78 S. T. Patton, J. S. Zabinski: Failure mechanisms of a MEMS actuator in very high vacuum, Tribol. Int. **35**(6) (2002) 373–379

36.79 S. T. Patton, K. C. Eapen, J. S. Zabinski: Effects of adsorbed water and sample aging in air on the μN level adhesion force between Si(100) and silicon nitride, Tribol. Int. **34**(7) (2001) 481–491

36.80 S. T. Patton, W. D. Cowan, K. C. Eapen, J. S. Zabinski: Effect of surface chemistry on the tribological performance of a MEMS electrostatic lateral output motor, Tribol. Lett. **9** (2000) 199–209

36.81 S. T. Patton, W. D. Cowan, J. S. Zabinski: Performance and reliability of a new MEMS electrostatic lateral output motor, Proc. 1999 37th Annual IEEE International Reliability Physics Symp. (IEEE, New York 1999) 179–188

36.82 D. M. Tanner, J. A. Walraven, L. W. Irwin, M. T. Dugger, N. F. Smith, W. P. Eaton, W. M. Miller, S. L. Miller: The effect of humidity on the reliability of a surface micromachined microengine, Proc. 1999 37th Annual IEEE International Reliability Physics Symp. (IEEE, New York 1999) 189–197

36.83 M. P. de Boer, P. J. Clews, B. K. Smith, T. A. Michalske: Adhesion of polysilicon microbeams in controlled humidity ambients, Proc. Mater. Res. Soc. Symp. **518** (1998) 131–136

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

37. MEMS Packaging and Thermal Issues in Reliability

MEMS Packag

The potential of MEMS/NEMS technologies has been viewed as a comparable or even bigger revolution than that of microelectronics. These scientific and engineering advancements in MEMS/NEMS could bring applications to reality previously unthinkable, from space systems, environmental instruments, to daily life appliances. As presented in previous chapters, the development of core MEMS/NEMS processes has already demonstrated a lot of commercial applications as well as future potentials with elaborated functionalities. However, a low cost and reliable package for the protection of these MEMS/NEMS products is still a very difficult task. Without addressing the packaging and reliability issues, no commercial products can be sold on the market. Packaging design and modeling, packaging material selection, packaging process integration, and packaging cost are main issues to be considered when developing a new MEMS packaging process. In this chapter, we will present the fundamentals of MEMS/NEMS packaging technology, including packaging processes, hermetic and vacuum encapsulations, thermal issues, packaging reliability, and future packaging trends. The future development of MEMS packaging will rely on the success of the implementation of several unique echniques, such as packaging design kits for system and circuit designer, low cost and high yield wafer level, chip-scale packaging techniques, effective testing techniques at the wafer-level to reduce overall testing costs; and reliable fabrication of an interposer [37.1] with vertical through-interconnects for device integrations.

37.1 **MEMS Packaging** 1111
  37.1.1 MEMS Packaging Fundamentals 1112
  37.1.2 Contemporary MEMS Packaging Approaches 1113

37.2 **Hermetic and Vacuum Packaging and Applications** 1116
  37.2.1 Integrated Micromachining Processes 1117
  37.2.2 Post-Packaging Processes 1118
  37.2.3 Localized Heating and Bonding 1119

37.3 **Thermal Issues and Packaging Reliability** 1122
  37.3.1 Thermal Issues in Packaging 1122
  37.3.2 Packaging Reliability 1124
  37.3.3 Long-Term and Accelerated MEMS Packaging Tests 1125

37.4 **Future Trends and Summary** 1128

References 1129

37.1 MEMS Packaging

MEMS are miniaturized systems in a size of micrometer to millimeter that may have mechanical, chemical, or biomedical features integrated with IC circuitry for sensor or actuator applications [37.2]. For example, pressure [37.3], temperature, flow [37.4], accelerometers [37.5], gyroscopes [37.6], and chemical sensors [37.7] can be fabricated by MEMS technologies for sensing applications. Fluidic valves [37.8], pumps [37.9], and inkjet printer heads are examples of actuation devices for medical, environmental, office, and industrial applications. Silicon is typically used as the primary substrate material for MEMS fabrication because it can provide unique electrical, thermal, and mechanical properties however also can be easily micromachined in a form of batch-processing and be incorporated with a microelectronic circuits by using most of the conventional semiconductor manufacturing processes and tools. As a result, smaller size, lighter weight, lesser power consumption and cheaper fabrication cost become the advantages of MEMS devices as compared with the existing macroscale systems with similar functionalities. With the advances of MEMS fabrication technology in the past decades, the MEMS market at the component-level is currently in excess of

$ 5 billion and is driving the end-product markets of large than $ 100 billion [37.10].

Nevertheless, the road to the commercialization of MEMS doesn't look as promising as expected. Many industrial companies took the advantages of MEMS technology of high production volumes and high added value created by product integrations. Therefore, cost-efficiency becomes the major factor driving MEMS toward commercialization. Several MEMS devices have been developed for and applied in automotive industry and information technology, and they dominate the MEMS market due to high production volumes. Most of custom-designed MEMS products are still very diverse, aiming for different applications, and their initial costs in small-to-medium-scale production are still much higher than market-acceptable levels. Consequently, high packaging and testing costs have slowed the commercialization of MEMS. Furthermore, based on the past experience of IC industry, the cost of packaging processes is about 30%, and sometimes can be more than 70%, of the total production expenses. MEMS packaging process is expected to be even more costly because of the challenging and stringent packaging issues with regard to the additional MEMS components, in addition to the microelectronic circuitry, in a typical MEMS product [37.11].

37.1.1 MEMS Packaging Fundamentals

The functions of conventional IC packaging are to protect, power, and cool the microelectronic chips or components and provide electrical and mechanical connection between the microelectronic part and the outside world. With the increase of the needs of high performance and multifunctional consumer electronic products, IC packaging processes have incorporated more complex designs and advanced fabrication technologies, such as Cu interconnects [37.12], flip-chip bonding [37.13], ball grid array [37.14], wafer-level chip scale packaging [37.15], and 3-D packaging [37.16], etc., in order to satisfy the need for high I/O density, large die area, and high clock frequency. In addition to the requirements of electrical interconnects, MEMS components may need to interface outside environment (for example, fluidic interconnectors [37.17]), some other components may need to be hermetically sealed in vacuum (for example, accelerometers [37.5]). Therefore, MEMS packaging processes have to provide more functionalities including better mechanical protection, thermal management, hermetic sealing, and complex electricity and signal distribution.

It has been suggested that MEMS packaging should be incorporated in the device fabrication stage as part of the micromachining process. Although this approach solves the need for some specific devices, it does not solve the packaging need for general microsystems. Many MEMS devices are now fabricated by various foundry services [37.18, 19], and there is a tremendous need for a uniform packaging process. Figure 37.1 shows a typical MEMS device being encapsulated by a packaging cap. The most fragile part of this device is the suspended mechanical sensor, which is a freestanding mechanical, mass-spring microstructure. This mechanical part must be protected during the packaging and handling process. Moreover, vacuum encapsulation may be required for these microstructures in applications such as resonant accelerometers [37.5] or gyroscopes [37.6, 20]. A "packaging cap" with properly designed micro cavity is to be fabricated to encapsulate and protect the fragile MEMS structure as the first-level MEMS post-packaging process. The wafer can be diced afterward, and the well-established packaging technology in IC industry can follow and finish the final packaging step. Unlike the packaging requirements for ICs, however, the common MEMS packaging requirement is hermetic seal and sometimes vacuum encapsulations. Hermetic seal is important to ensure that no moisture or contaminant can enter the package



Fig. 37.1 A typical MEMS packaging illustration in which a MEMS structure is encapsulated and protected by the packaging cap

and affect the functionality of microstructures. This increases the difficulty of common IC packaging processes tremendously. Although most single function MEMS chips can employ typical IC packaging techniques, such as die-attached processes, wiring interconnects, molded plastic, ceramic, and metal for packaging [37.21], with the increase of complexity MEMS devices, more advanced packaging techniques, especially wafer-level packaging, are required for the integration of multi-chips for multifunctional applications.

Before the state-of-the-art MEMS packaging processes are discussed, several primary micro-fabrication processes for packaging applications are described. These processes may include Flip-Chip (FC) technique, Ball Grid Arrays (BGA), through-wafer etching, and plating. Other silicon-based processes, such as thin-film deposition, wet and dry chemical etching, lithography, lift-off, and wiring bonding processes can be found in many textbooks [37.22].

Flip-Chip Technique (FC)

This technique is commonly used in the assembly process between a chip with microelectronics and a package substrate [37.13]. The microelectronic chip is "flipped joined" with the packaging substrate, and metal solder bumps are used as both the bonding agents and electrical paths between bond pads on the microelectronic chip and metal pads on the package substrate. Because the vertical bonding space can be very small as controlled by the heights of the solder bumps, and the lateral distributions of bond pads can be on the whole chip instead of being only on the edge, this technique can provide high density Input/Output (I/O) connections. In the FC technique, solder bumps are generally fabricated by means of electroplating. Before the bumping process, multiple metal layers, such as TiW-Cu, Cr-Cu, Cr-Ni, TaN/Ta/Ni, have to be deposited as a seed layer for electroplating and as a barrier to prevent the diffusion of solder into its underneath electrical interconnect.

Ball Grid Arrays (BGA)

This technology is very similar to the FC technique. An area array of solder balls on a single chip module or multi-chip module are used in the packaging process as electrical, thermal, and mechanical connects to join the module with the next level package, usually a printed circuit board [37.14]. The major difference between a typical BGA and FC is the size of solder bump. In BGA chip, the bumps are in the order of 750 μm in diameter which is ten times larger than those commonly used in FC.

Through-Wafer Etching

This is a chemical etching process to make through-wafer channels on a silicon substrate for the fabrication of vertical through-wafer interconnects. The chemical etching process can be either wet or dry. Anisotropic or isotropic etching solutions can be used in the wet etching process. The dry etch process is based on plasma and ion-assisted chemical reactions that can be either isotropic or anisotropic. In order to create high density and high aspect ratio through-wafer vias, Deep Reactive Ion Etching (DRIE) is typically used. Two popular DRIE approaches, Bosch and Cyro, are well described in literature [37.23].

Electroplating

Electroplating is another common micro-fabrication process. It can be conducted for the deposition of an adherent metallic layer onto a conductive or nonconductive substrate. The process on a conductive substrate is called electrolytic plating, which utilizes a seed layer as the anode to transfer metal ions onto the cathode surface when a DC current is passed through the plating solution. The plating process without applying electrical current is called electroless plating, which can happen in both conducive and nonconductive surfaces. Electroless plating process requires a layer of noble metal such as Pd, Pt, or Ru on the substrate as the catalysis to trigger the self-decomposition reaction in the plating solution. The electroplating processes are very important for electrical interconnect and solder bump fabrications for packaging applications because of low process temperature and cost.

These processes are generally developed for providing electrical and thermal paths for various IC/MEMS packaging approaches.

37.1.2 Contemporary MEMS Packaging Approaches

Several MEMS packaging issues and approaches before 1985 were discussed in [37.24], and researchers have been working on MEMS packaging approaches continuously. For example, *Senturia* and *Smith* [37.25] discussed the packaging and partitioning issues for microsystems. *Smith* and *Collins* [37.26] used epoxy to bond glass and silicon for chemical sensors. Several MCM methods have been proposed. *Butler* et al. [37.27] proposed adapting multi-chip module foundries using chip-on-flex (COF) process. *Schuenemann* et al. [37.28] introduced a 3-D stackable packaging concept for the Top-Bottom Ball Grid Array (TB-BGA) that includes electric, fluidic, optic, and communication interfaces. *Lee* et al. [37.29] and *Ok* et al. [37.10] presented a direct-chip-attach MEMS packaging using through-wafer electrical interconnects. *Laskar* and *Blythe* [37.30] developed a multi-chip modules (MCM) type packaging process by using epoxy. *Reichl* [37.31] discussed different materials for bonding and interconnection. *Grisel* et al. [37.32] designed a special process to package micro-chemical sensors. Special processes have also been developed for MEMS packaging, such as packaging for microelectrodes [37.33], packaging for biomedical systems [37.34], and packaging for space systems [37.35]. These specially designed, device-oriented packaging methods are meant for individual systems. There is no reliable method yet that would qualify as a versatile post-packaging process for MEMS with the rigorous process requirements of low temperature, hermetic sealing and long-term stability.

An integrated process by using surface-micromachined microshells has previously been developed [37.36]. This process applies the concepts of sacrificial layer and LPCVD sealing to achieve wafer-level post-packaging. Similar processes have been demonstrated. For example, *Guckel* et al. [37.37] and *Sniegowski* et al. [37.38] developed a reactive sealing method to seal vibratory micromachined beams. *Ikeda* et al. [37.39] adopted epitaxial silicon to seal microstructures. *Mastrangelo* et al. [37.40] used silicon nitride to seal mechanical beams as light sources. *Smith* et al. [37.41] accomplished a new fabrication technology by embedding microstructures and CMOS circuitry. All of these methods have integrated the MEMS process together with the post-packaging such that no extra bonding is required. These schemes are highly process dependent, however, and not suitable for prefabricated circuitry.

Recently several new efforts for MEMS post-packaging processes have been reported. *Butler* et al. [37.27] demonstrated an advanced MCM packaging scheme. It adopts the high density interconnect (HDI) process consisting of embedding bare die into premilled substrates. Because the MEMS structures have to be released after the packaging process, it is undesirable for general microsystems. *Van der Groen* et al. [37.42] reported a transfer technique for CMOS circuits based on epoxy bonding. This process overcomes the surface roughness problem, but epoxy is not a good material for hermetic sealing. In 1996, *Cohn* et al. [37.43] demonstrated a wafer-to-wafer to-wafer vacuum packaging process by using Silicon–Gold eutectic bonding with a 2-μm-thick polysilicon microcap. But experimental results show substantial leakage after a period of 50 days. *Cheng* et al. [37.44] developed a vacuum packaging technology using localized aluminum/silicon-to-glass bonding. In 2002, *Chiao* and *Lin* [37.45] demonstrated vacuum packaging of microresonators by rapid thermal processing. These recent and ongoing research efforts indicate the strong need for a versatile MEMS post-packaging process.

Bonding Processes for MEMS Packaging Applications

Previously, silicon-bonding technologies have been used in many MEMS fabrication and packaging applications, including epoxy bonding, eutectic bonding, anodic bonding, fusion bonding, and solder bonding. For example, such devices as pressure sensors, micro-pumps, biomedical sensors or chemical sensors require mechanical interconnectors to be bonded on the substrate (see for example [37.7, 17, 46]). Glass has been commonly used as the bonding material by anodic bonding at a temperature of about $300 \sim 450\,°\mathrm{C}$ (see for example [37.47, 48]). *Klaassen* et al. [37.49] and *Hsu* et al. [37.50] have demonstrated different types of silicon fusion bonding and Si–SiO_2 bonding processes at very high temperatures of over 1,000 °C. *Ko* et al. [37.24], *Tiensuu* et al. [37.51], *Lee* et al. [37.52] and *Cohn* et al. [37.43] have used eutectic bonding for different applications. All of these bonding techniques have different mechanisms that determine the individual bonding characteristics and process parameters. This section discusses the details of these processes.

Fusion Bonding for MEMS Packaging

Silicon fusion bonding is an important fabrication technique of the SOI (Silicon On Insulator). The bonding is based on Si−O, Si−N, or Si−Si strong covalent bond. But very high bonding temperature (higher than 1,000 °C) and flat bonding surfaces (less than 6 nm) are the two basic requirements for strong, uniform, and hermetic bonding. Although hydrophilic surface treatment can lower the bonding temperature, an annealing step higher than 800 °C is still needed to remove possible bubble formation at the bonding interface. *Bower* et al. [37.53] proposed that low temperature Si_3N_4 fusion bonding could be achieved at the temperature under 300 °C. *Takagi* et al. [37.54] proposed that silicon fusion bonding could be made at room temperature by using Ar^+ beam treatment on the wafer surface, and the bond strength is comparable to the conventional fusion bonding. In summary, fusion bonding has been a popular fabrication technique in MEMS fabrication and packaging.

Anodic Bonding for MEMS Packaging Applications

The invention of anodic bonding dates back to 1969 when *Wallis* and *Pomerantz* [37.55] found that glass and metal can be bonded together at about 200 ∼ 400 °C below the melting point of glass with the aid of a high electrical field. This technology has been widely used for protecting on-board electronics in biosensors (see for example [37.56–58]) and sealing cavities in pressure sensors (see for example [37.59]). Many reports have also discussed the possibility of lowering the bonding temperature by different mechanisms [37.60, 61]. Anodic bonding forms Si−O or Si−Si covalent bond and is one of the strongest chemical bonds available for silicon-based systems. The bonding process can be accomplished on a hot plate with a temperature between 180 °C and 500 °C in atmosphere or vacuum environment. When a static electrical field is built within the Pyrex glass (7740 from Dow Corning) and silicon, the electrostatic force can pull two surfaces close for a strong bond. In order to create high electrical field, a flat bonding surface with less than 50 nm roughness is required. In addition, the electrical field required for bonding is larger than 3×10^6 V/cm [37.24]. Such a high electrical field is generated by a power supply of 200 to 1,000 V, which may cause damages on integrated circuits. *Hanneborg* et al. [37.62] have successfully bonded silicon with other thin solid films, such as silicon dioxide, nitride, and polysilicon, together with an intermediate glass layer using anodic bonding technique. In practice, electrostatic bonding has become widely accepted in MEMS fabrications and packaging applications. Unfortunately, the possible contamination due to excessive alkali metal in the glass; possible damage to microelectronics due to the high electrical field; and the requirement of flat surface for bonding limit the application of anodic bonding to MEMS post-packaging applications [37.63].

Epoxy Bonding (Adhesive Bonding)

Four major components comprise epoxy : epoxy resin, filler – like silver slake, solvent or reactive epoxy diluent, and additives like hardener and catalyst [37.64, 65]. The bonding mechanism of epoxy is very complicated and depends on the type of epoxy. In general, the main source of bonding strength is the van der Waals force. Because epoxy is a soft polymer material and its curing temperature for bonding is only around 150 °C, low residual stress and process temperature are the major advantages of epoxy bonding. But the properties of epoxy can be easily changed with environmental humidity and temperature so the bonding strength decays over time. In addition, epoxy bonding has low moisture resistance and, due to its additives, is a dirty process. These disadvantages have made epoxy unfavorable for the special MEMS packaging need for hermetic or vacuum sealing.

Eutectic Bonding

In many binary systems, a eutectic point corresponds to the alloy composition with the lowest melting temperature. If the environmental temperature is kept higher than the eutectic point, two contacted surfaces containing two elements with the eutectic composition can form liquid phase alloy. The solidification of the eutectic alloy forms “eutectic bonding” at a temperature lower than the melting temperature of either element in the alloy. Eutectic bonding can be a strong bond. For example, in the case of Au/Si alloy system, eutectic temperature is only 363 °C when the composition is at the atomic ratio of 81.4% Au to 18.6% Si and bonding strength is higher than 5.5 GPa [37.66]. Because other alloy systems may have lower eutectic temperatures than Al/Si system, they present great potential for MEMS packaging applications. In addition to Au/Si, Al/Ge/Si, Au/SnSi, and Au/Ge/Si systems have been applied for MEMS packaging.

Solder Bonding

Solder bonding has been widely applied in microelectronic packaging [37.67]. Both low bonding temperature and high bonding strength are good characteristics for packaging. Furthermore, there are a variety of choices of solder material for specific applications. *Singh* et al. [37.68] have successfully applied solder bump bonding in the integration of electronic components and mechanical devices for MEMS fabrication [37.69]. In this case, indium metal was used for bonding two separated silicon surfaces together by applying 350 MPa pressure and the bonding strength was as strong as 10 MPa. Glass frits can also be treated as a solder material and have been extensively used for vacuum encapsulation in MEMS industry. Glass frits are ceramic materials that can provide strong bonding strength with silicon with good hermeticity. Its bonding temperature is lower than 400 °C and is suitable for electronic components. But a bonding area more than 200 µm wide is required to achieve good results, which may become a drawback because area is the measure of manufacturing cost in IC industry. Nevertheless, glass frit is the

Table 37.1 Summary of bonding mechanisms

Bonding methods	Temperature	Roughness	Hermeticity	Post-packaging	Reliability
Fusion bonding	very high	highly sensitive	yes	yes by LH	good
Anodic bonding	medium	highly sensitive	yes	difficult	good
Epoxy bonding	low	low	no	yes	???
Integrated process	high	medium	yes	no	good
Low Temp. bonding	low	highly sensitive	???	no	???
Eutectic bonding	medium	low	yes	yes by LH	???
Brazing	very high	low	yes	yes by LH	good
???: no conlusive data		LH: Localized Heating			

most popular bonding process used in the current MEMS products.

Localized Heating and Bonding

Low bonding temperature and short process time are desirable process parameters in MEMS packaging fabrication to provide less thermal budget and high throughput. Most chemical bonding reactions, however, require a minimum and sufficient thermal energy to overcome the reaction energy barrier, or activation energy, to start the reaction and to form a strong bond. As a result, high bonding temperature generally results in shorter processing time to reach the same bonding quality at a lower bonding temperature [37.70]. The common limitations for the above techniques are their individual bonding characteristics and temperature requirements. In general, MEMS packaging requires a good bonding for hermetic sealing while the processing temperature must be kept low at the wafer-level to have less thermal effects on the existing devices. For example, a MEMS device may have prefabricated circuitry, biomaterial, or other temperature-sensitive materials such as organic polymer, magnetic metal alloy, or pizeo-ceramic. Since the packaging step comes after the MEMS device fabrication processes, bonding temperature should be kept low to avoid high temperature effects on the system. Possible temperature effects include residual stress due to the mismatch of thermal expansion coefficient of bonding materials and substrates, electrical contact failure due to atom inter-diffusion at the interface, and contamination due to the outgas or evaporation of materials. In addition to the control of bonding temperature, Other factors to consider are the magnitude of applied force to create intimate contact for bonding and atmospherics environment control. Based on the heat transfer simulation study [37.71], it is possible to confine high temperature area in a small region by localized heating without heating the whole substrate. Assembly steps can therefore always be processed after device fabrication without having detrimental effects. As such, localized heating and bonding technique is introduced and implemented for the fabrication of MEMS packaging for post-processing approaches [37.70, 72].

Table 37.1 summarizes these MEMS packaging technologies and their limitations, including the localized heating and bonding approach. The localized heating approach introduces several new opportunities. First, better and faster temperature control can be achieved. Second, higher temperature can be applied to improve the bonding quality. Third, new bonding mechanisms that require high temperature such as brazing [37.73] may now be explored in MEMS applications. As such, it has potential applications for a widerange of MEMS devices and is expected to advance the field of MEMS packaging.

37.2 Hermetic and Vacuum Packaging and Applications

Hermetic packaging is desirable for MEMS packaging requirements in most cases because it provides a moisture free environment to avoid charge separation in capacitive devices, corrosion in metallization, or electrolytic conduction in order to prolong the lifetime of the electronic circuitry. In several device applications, vacuum encapsulation is necessary but can be costly. Many surface micromachined resonant devices need vacuum to improve the performance including comb-shape µ-resonators and ring-type µ-gyroscopes that have very large surface-to-volume ratios and vibrate in a very tight space [37.20,39]. Two major approaches of MEMS hermetic and vacuum packaging have been demonstrated: (1) the integrated encapsulation approach and (2) the post-process packaging approach. Both are discussed in this section. Vacuum encapsulation by means of localized heating and bonding is discussed separately as another example for issues related to hermetic and vacuum packaging.

37.2.1 Integrated Micromachining Processes

Several MEMS hermetic and vacuum packaging processes have been demonstrated before based on the integrated micromachining processes. An integrated vacuum sealing process by LPCVD is presented here as the illustration example. This integrated process can encapsulate comb-shape microresonators [37.74] in vacuum at the wafer level. Figure 37.2 illustrates the cross-sectional view of the manufacturing process. First, standard surface-micromachining process [37.75] is conducted by using four masks to define the first polysilicon layer, anchors to the substrate, dimples and, the second polysilicon layer as shown in Fig. 37.2a. The process so far is similar to the MCNC MUMPs process [37.19], and comb-shape microstructures are fabricated at the end of these steps. In the standard surface micromachining process, the sacrificial layer (oxide) is etched away to release the microstructures. In the MEMS post-packaging process, a thick PSG (phosphorus-doped glass) of 7 µm is deposited to cover the microstructure and patterned by using 5:1 BHF (buffered HF) to define the microshell area as shown in Fig. 37.2b. A thin PSG layer of 1 µm is then deposited and defined to form etch channels as illustrated in Fig. 37.2c. The microshell material, low-stress silicon nitride, is now deposited with a thickness of 1 µm. Etch holes are defined and opened on the silicon nitride layer by using a plasma etcher. Silicon dioxide inside the packaging shell is now etched away by concentrated HF, and the wafer is dried using the supercritical CO_2 drying process [37.76]. After these steps, Fig. 37.2d applies. A 2-µm-thick LPCVD low-stress nitride is now deposited at a deposition pressure of 300 mtorr to seal the shell in the vacuum condition. Finally, the contact pads are opened as shown in Fig. 37.2e. Figure 37.3 is the SEM (Scanning Electron Microscope) microphoto of a finished device with protected microshell on top. The total packaging area (microshell) is about 400×400 µm^2. A contact pad is shown with the covering nitride layer removed. The shape of the microresonator, with beams of 150-µm-long and 2-µm-wide is reflected on the surface of the microshell due to the integrated packaging process. The total height of the nitride shell is 12 µm, as seen standing above the substrate. Spectrum measurement of the comb resonator inside the packaging reveals that a vacuum level of about 200 mtorr has been accomplished [37.77].



Fig. 37.2 An integrated vacuum encapsulation process using LPCVD nitride sealing to package micro-mechanical resonators [37.71]

Although the above vacuum sealing process successfully achieves MEMS hermetic and vacuum packaging, it has several drawbacks. First, several high temperature steps were used after the standard surface-micromachining process. As such, no circuitry (such as those shown in Fig. 37.1) or temperature-sensitive materials



Fig. 37.3 SEM microphoto showing a vacuum packaged MEMS mechanical comb-shape resonator by an the integrated LPCVD sealing process as depicted in Fig. 37.2 [37.71]

will survive due to the global heating effect. Second, this post-packaging process is very specific and process dependent. MEMS companies or researchers have to adopt this post-packaging process with their own device manufacturing process. It can't be conducted in the multiuser MEMS process such as the MCNC MUMPs. Third, the thickness of the microshell is limited by the thin film deposition step that generally is in the range of a few micrometers. Wether the thin microshell can survive the high-pressure plastic molding process afterward in some device packaging design is a big concern. Finally, although integrated encapsulation can achieve low pressure by wafer-level fabrication and provide lower manufacturing cost, it does not provide the controllability of the cavity pressure.



Fig. 37.4 The schematic diagram of industrial post-packaging (DIPS) using a ceramic holder to be covered by a sealing lid

37.2.2 Post-Packaging Processes

The second approach is defined as post-packaging process. The packaging process starts when the device fabrication processes are completed, so this approach has high flexibility for various microsystems. For example, Fig. 37.4 shows a common industrial post-hermetic packaging called Dual-in-line packaging (DIP) [37.78, 79]. A die is placed inside a ceramic holder covered by a sealing lid. Solder or ceramic joining is generally used for assembling lid and holder under a pressure-controlled environment. High cost is the major drawback of this method because of expensive ceramic holder and low fabrication throughput. Another example of post-packaging method is based on wafer bonding techniques combined with a microshell encapsulation. Devices are sealed by stacking another micromachined silicon or glass substrate as illustrated in Fig. 37.1. Integrated microsystems and protection shells are fabricated on different wafers, either silicon or glass, at the same time. After the two substrates are assembled together using silicon fusion, anodic, or low temperature solder bonding to achieve the final encapsulation, these micro-shells will provide mechanical support, thermal path, or electrical contact for the MEMS devices. Low packaging cost can be expected due to wafer-level processing.

The related packaging issues are discussed by using a specific example of hermetic and vacuum post-packaging by rapid thermal processing (RTP) that provides the advantages of wafer-level processing and low thermal budget. Figure 37.5 shows the



Fig. 37.5 The schematic diagram of the RTP (Rapid Thermal Processing) aluminum-to-nitride bonding setup [37.45]

schematic illustration of the RTP MEMS vacuum packaging process. Comb-shape microresonators are chosen as the vacuum packaging examples in this chapter, and a standard surface-micromachining process is used to fabricate these microresonators [37.19]. One major addition to a regular microstructure is that an integrated sealing ring using silicon nitride as the topmost layer is incorporated in the manufacturing process for the purpose of aluminum-to-nitride bonding [37.45]. A glass cap wafer is deposited and patterned with 4-µm-thick aluminum sealing-rings with width ranging from 100 to 250 µm and bonding area ranging from 450 × 450 to 1,000 × 1,000 μm^2. Before the vacuum packaging process, both the device and cap wafers are baked in vacuum at 300 °C for over four hours to dry water and gas species adhere at the surface. Afterward, the device and cap wafers are flip-chip assembled immediately and loaded into a quartz chamber and put into a RTP chamber. The base vacuum estimated at 10 mtorr inside the quartz chamber is achieved by using a mechanical pump. After heating for 10 seconds at 750 °C, the aluminum-to-nitride bond is formed. Figure 37.6 shows the measured spectrum of a vacuum-packaged, double-folded beam comb-drive resonator by using a micro-stroboscope [37.80]. The central resonant frequency is about 18,625 Hz and the quality factor is extracted as 1,800 ± 200 corresponding to a pressure level about 200 mtorr inside the package [37.81].



Fig. 37.6 Spectrum measurement results of a vacuum encapsulated comb-shape resonator by using the RTP aluminum-to-nitride bonding method [37.45]

This type of post-packaging process at wafer level has become the favorite approach to fabricate a hermetic encapsulation because it can provide lower cost and more process flexibility. But the packaging process relies on "good" bonding techniques. A strong and reliable bonding between two substrates should be provided, and this procedure should be compatible with the other microsystem fabrication processes.

37.2.3 Localized Heating and Bonding

The approach of MEMS post-packaging by localized heating and bonding is proposed to address the problems of global heating effects. In this chapter, resistive micro-heaters are used as the examples to provide localized heating, although several other means of localized heating have been demonstrated recently, including laser welding [37.82], inductive heating [37.83], and ultrasonic bonding [37.84]. The principle of localized heating is to achieve high temperature for bonding while maintaining low temperature globally at the wafer level. Resistive heating by using micro-heaters on top of device substrate is applied to form strong bond with silicon or glass cap. According to the results of a 2-D heat conduction finite element analysis as shown in Fig. 37.7, the steady-state heating region of a 5-µm-wide polysilicon micro-heater capped with a Pyrex glass substrate



Fig. 37.7 The schematic diagram of 2-D heat transfer model, geometry and boundary conditions

can be confined locally as long as the bottom of the silicon substrate is constrained to the ambient temperature. The physics of localized heating behind this design can be understood by solving the governing heat conduction equations of the device structure without a cap [37.81]. As long as the width of micro-heater and the thickness of silicon substrate are much smaller than the die size and a good heat sink is placed underneath the silicon substrate, the heating can be confined locally. The temperature of silicon substrate can be kept low or close to room temperature. Several localized resistive heating and bonding techniques have been successfully developed for packaging applications including localized silicon-to-glass fusion bonding, gold-to-silicon eutectic bonding, and localized solder bonding. Several solder materials have been successfully tested, including PSG, indium, and aluminum alloy [37.85].

The vacuum packaging example presented in this chapter is based on localized aluminum/silicon-to-glass solder bonding technique. Built-in folded-beam comb drive μ-resonators are used to monitor the pressure of the package. Figure 37.8 shows the fabrication process of the package and resonators. Thermal oxide (2 μm) and LPCVD Si_3N_4 (3,000 Å) are first deposited on a silicon substrate for electrical insulation followed by the deposition of 3,000 Å LPCVD polysilicon. This polysilicon is used as both the ground plane and the electrical interconnect to the μ-resonators as shown in Fig. 37.8a. Figure 37.8b shows a 2 μm LPCVD SiO_2 layer that is deposited and patterned as a sacrificial layer for the fabrication of polysilicon μ-resonators using a standard surface micromachining process. A 2-μm-thick phosphorus doped polysilicon is used for both the structural layer of microresonators and the on-chip micro-heaters. This



Fig. 37.8a–h The schematic process flow of vacuum encapsulation using localized aluminum/silicon-to-glass bonding, **(a)** electrical ground plane and device interconnects fabrication **(b)** a 2 μm LPCVD SiO_2 sacrificial layer deposition for the fabrication of polysilicon μ-resonator **(c)** a 2 μm-thick phosphorus doped polysilicon deposition and patterning for both the structural layer of micro resonators and the on-chip microheaters **(d)** a LPCVD Si_3N_4 (750 Å)/SiO_2 (1,000 Å)/Si_3N_4 (750 Å) sandwich layer deposition and patterning on top of the microheater for the electrical isolation **(e)** an aluminum (2.5 μm) and polysilicon (5,000 Å) bonding materials are deposition and patterning. **(f)** a thick AZ 9245 photoresist deposition and patterning for the protection of aluminum/silicon-to-glass bonding layers **(g)** 20 minutes sacrificial release in concentrated HF **(h)** vacuum encapsulation with 0.2 MPa contact pressure and 3.4 W input power under a 25 mtorr vacuum environment

layer is formed over the sacrificial oxide in two steps to achieve a uniform doping profile. Lower input power and better process compatibility are two major advantages in using the on-chip micro-heater in the glass package. The resonators are separated from the heater by a short distance, 30 μm, to effectively prevent their exposure to the high heater temperature as shown in Fig. 37.8c. This concludes the fabrication of μ-resonators.

In order to prevent the current supplied to the micro-heater from leaking into the aluminum solder during bonding, a LPCVD Si_3N_4 (750 Å)/SiO_2 (1,000 Å)/Si_3N_4 (750 Å) sandwich layer is grown and patterned on top of the micro-heater as shown in Fig. 37.8d. Figure 37.8e and f show that aluminum (2.5 μm) and polysilicon (5,000 Å) bonding materials are deposited and patterned. The sacrificial release is the final step to form freestanding μ-resonators. Figure 37.8f shows a thick AZ 9245 photoresist is applied to cover aluminum/silicon-to-glass bonding system to ensure that the system withstands the attack from concentrated hydrofluoric acid. After 20 minutes sacrificial release in concentrated HF, the system as shown in Fig. 37.8g is ready for vacuum packaging. A Pyrex glass cap with a 10-μm deep recess is then placed on top with an applied pressure of ∼ 0.2 MPa under a 25 mtorr vacuum, and the heater is warmed using 3.4 watt input power (exact amount depends on the design of the micro-heaters) for 10 minutes to complete the vacuum packaging process as shown in Fig. 37.8h.

To evaluate the integrity of the resonators packaged using localized aluminum/silicon-to-glass solder bonding, the glass cap is forcefully broken and removed from the substrate. No damage is found on the μ-resonator and a part of the micro-heater is stripped away as shown in Fig. 37.9, demonstrating that a strong and uniform bond can be achieved without detrimental effects on the encapsulated device. Figure 37.10 shows a vacuum encapsulated unannealed μ-resonator (∼ 57 kHz) after



Fig. 37.9 The SEM microphoto of encapsulated micro-resonators after the glass cap is forcefully broken



Fig. 37.10 The transmission spectrum of a glass-encapsulated μ-resonator after 120 minute pump down time in vacuum environment ($Q = 9{,}600$)



Fig. 37.11 Measured Q factor vs. pressure of unpackaged μ-resonators

120 minutes of wait time. The measured Q-factor after packaging is 9,600. Based on the measurement of Q vs. pressure of a high Q unpackaged µ-resonator as shown in Fig. 37.11, it is demonstrated that the pressure inside the packaging is comparable to the vacuum level of packaging chamber.

The post-process packaging using localized heating and bonding technique includes four basic components: (1) an electrical and thermal insulation layer such as silicon dioxide or silicon nitride should be used for localized heating, (2) resistive micro-heaters will be fabricated to provide the heating source for localized bonding, (3) materials, including metal and polysilicon that can provide good bonding and hermeticity with silicon or glass substrates are considered as the bonding materials, and (4) a good heat sink under the device substrate for localized heating is provided during the bonding experiments. MEMS devices will be fabricated on the device chip and hermetically sealed in the cavity formed by the device chip, resistive micro-heaters, and protection cap. The process can be either die level or wafer level. The schematic design of wafer-level packaging process is shown in Fig. 37.12. The resistive micro-heaters are parallel to each other and connected in order to ensure that identical current density is applied for individual packages at the same time. These heaters can be fabricated either on the chip or protection cap and can be built in a larger wafer for current inputs. The interconnections for these packaging cavities can be built in the dicing area, so no extra space is required for the packaging process.



Fig. 37.12 Illustration of wafer-level vacuum packaging in the wafer level using localized heating and bonding technique

37.3 Thermal Issues and Packaging Reliability

37.3.1 Thermal Issues in Packaging

The two key thermal issues related to MEMS packaging are: 1) heat dissipation from actuators and integrated circuitry components and 2) thermal stress generated during the packaging process. These two topics are discussed separately.

Heat Dissipation Issues

In IC, heat dissipation is a serious problem when the size of transistor continues to shrink and the density of transistor on a chip continue to increase with the advance of IC fabrication technology. The trend of power packing into smaller packages has created increasing thermal management challenges [37.86]. Since the electrical characteristics of transistors change with working temperature, inefficient power dissipation could raise the working temperature and affect device performance. Present MEMS devices don't need high power, high performance microprocessors so power dissipation is not a problem. Nevertheless, some functional components in packaged MEMS are very sensitive to temperature variation, such as biomaterials or laser diodes. Several MEMS chemical sensors and other applications such as micro PCR chamber for DNA replication actually require elevated temperature for operation and micro-thermal platforms are built for these devices. Thermal management to maintain working temperature on these chips for stable operation is still an essential issue for packaging considerations. The geometrical complexity of MEMS resulting from packing various functional components in the tight space increases the difficulty of the thermal management. As the MEMS packaging integration process becomes more complex, the fabrication constraint in the packaging process will have great impact on the heterogeneous integration process in the front-end MEMS and IC processes. For example, low temperature requirement at the packaging process generally limits the possible choices of materials in the back-end process. In general, conventional IC packaging employs a heat sink attached to the chip to remove heat. The heat sink is generally made of a copper or stainless steel bar with an array of fin structures on one side for better natural or forced heat convection to dissipate heat into the environment. In addition to heat sinks, thermal vias, heat pipe cooling, immersion cooling, and thermoelectric cooling can also be used for effective heat removal. Because most MEMS packages still follow the typical IC packaging architecture, one promising thermal management method, heat pipe, is discussed for possible MEMS packaging applications.

A heat pipe is a sealed slender tube containing a wick structure and a working fluid, typically water in electronics cooling. It is composed of three sections, the evaporator section at one end, condenser section at the other end, and adiabatic section in the middle. In the evaporator section, heat is absorbed by the working fluid via phase transformation from liquid to vapor. In the section of condenser, heat dissipates into the outside environment. Thus the fluid goes back to liquid phase. Vapor phase is at a high pressure and temperature state that forces the vapor to flow into the condenser section at a lower temperature. Once the vapor condenses and gives up its latent heat, the condensed fluid is pumped back to the evaporator section by the capillary force developed in the wick structure. Therefore the middle adiabatic section contains two phases, the vapor phase in the core region and the liquid phase in the wick, flowing opposite to each other with no significant heat transfer between the fluid and the surrounding medium. Silicon has good thermal conductivity (1.41 W/cm/°C) and is easily micro-machined to fabricate the heat pipe. The implementation of the silicon micro heat pipe in IC and MEM packaging has therefore great potential and several approaches have been proposed on this topic [37.87–89].

Packaging Induced Thermal Stresses

Thermal based bonding processes have been used in MEMS packaging applications for many years, as introduced previously in this chapter. Thermal management is extremely important during the bonding process in order to avoid fracture in the substrate or MEMS device itself. Extremely high temperatures or rapid cooling conditions can cause damage and should be carefully evaluated both analytically and experimentally. There are many ways to provide heating energy including electrical resistive heating, oven heating or induction heating [37.83]. These bonding processes may be put into two categories. The first is localized bonding in which the heat is directly applied only to the adhesive material used to bond the package to the MEMS device. The second category is global heating where the entire system (MEMS device, adhesive, and packaging material) is heated to produce bonding of the materials. The latter is the common approach for all MEMS packaging processes. This section focuses therefore on the thermal stress effects during the heating and cooling procedures in MEMS packaging. The RTP aluminum-to-glass bonding process is used as the specific example for the discussion of thermal stresses [37.90]. The bonding process heats the packaging system to 750 °C for 10 seconds, and then cools it back to room temperature. To simulate this process, an ANSYS program [37.91] is established to examine the shear stress due to CTE (Coefficient of Thermal Expansion) variations in the bonding system as the result of temperature changes. The shear stress was recorded from the ANSYS analysis on the aluminum/Pyrex glass interface and the aluminum/silicon interface.

Two different models were analyzed. The first was the quartz-aluminum-silicon bonding system, and the second was the Pyrex glass-aluminum-silicon bonding system [37.92]. The results of the ANSYS analysis were then analyzed and compared with experimental observations. Figure 37.13 shows the ANSYS results for a Pyrex glass bonding system: the width of the aluminum solder is 100 μm and the maximum residual stress is be 60 MPa in glass, slightly lower than the fracture strength of Pyrex glass at 70 MPa. It was discovered that increasing the aluminum width leads to lower residual stresses. This likely occurred because the length of the Pyrex glass, quartz, and silicon remains constant. As a result, it will always want to contract the same amount with a constant temperature change independent of the aluminum width. When increasing the aluminum width, however, the stress is not in such a concentrated area and therefore decreases. For example, the maximum residual stress an-



Fig. 37.13 Residual Stress (GPa) for an aluminum solder width of 100 μm under the RTP silicon-aluminum-glass bonding system

alyzed from ANSYS in the Pyrex glass bonding systems is 74.5 Gpa, 58 Gpa, and 60 GPa for aluminum widths of 30, 50, and 100 µm, respectively [37.92]. Pyrex glass has a documented strength of around 69 GPa [37.93]. Fracture should always occur with an aluminum width of 30 µm or less, according to the ANSYS analysis. Fracture may occur sporadically at widths of 50 or 100 µm, depending on the amount and magnitude of the flaws in the Pyrex glass. Experiments were done on the Pyrex glass bonding systems with a width of 100 µm. The samples were heated to 750 °C and then cooled by taking them out of the oven. In all four experimental cases, small cracks were observed in Pyrex glass as shown in Fig. 37.14. These cracks may have occurred consistently for several reasons. First, it may be a result of handling of the Pyrex glass before bonding. The Pyrex glass samples were kept in containers with each other, which may have resulted in abrasive contact and possibly caused flaws in the materials. These flaws can cause a reduced strength from the 69 GPa and therefore the predictions from the ANSYS analysis could be correct. Second, the observation is made that the cracks are small, only occurring tens of microns away from the aluminum and not propagating completely through the Pyrex glass. These cracks could be caused by the high stress applied, but the crack has not reached a critical size and therefore has not propagated completely through the Pyrex glass. Therefore, the strength remains at the theoretical strength of 69 GPa, and the Pyrex glass is only partially cracked. Experimental analysis done by *Chaio* and *Lin* [37.90] shows that fracture was not observed when using aluminum widths greater than 150 µm. This is consistent with the results of the ANSYS analysis which show that as the width of the aluminum is increased, the residual stress decreases.

The quartz bonding system ANSYS stress predictions are conducted, and the maximum stress predicted in the analysis is 207 GPa, 117 GPa, and 100 GPa, for aluminum widths of 30 µm, 50 µm, and 100 µm, respectively. All three of these stresses are much larger than the theoretical strength of Quartz at 48 GPa, and therefore fracture should always occur. Quartz has a much larger coefficient of thermal expansion (CTE) than silicon, which is why this was predicted. Experimentally, a quartz substrate was tested for the silicon-aluminum-quartz bonding test and the result is shown in Fig. 37.15.Cracks happen all over the place and cause serious damages on the quartz wafer. These cracks could be the failure mechanism of the hermetic package. Pyrex glass is therefore identified as a better bonding substrate than quartz.



Fig. 37.14 Microphoto of the experimental result on Pyrex Glass-Aluminum-Silicon system. Small cracks can be observed



Fig. 37.15 Bonding result of Quartz-Aluminum-Silicon system, fracture can be observed

The thermal stresses generated in the packaging process in quartz are much larger than the stresses in Pyrex glass because of the difference between the CTE in the two systems. Quartz has a low CTE ($0.54 \times 10^{-6}\,\mathrm{K}^{-1}$) compared to the aluminum CTE ($23 \times 10^{-6}\,\mathrm{K}^{-1}$) and silicon CTE ($3.5 \times 10^{-6}\,\mathrm{K}^{-1}$). On the other hand Pyrex glass has a much closer CTE ($3.2 \times 10^{-6}\,\mathrm{K}^{-1}$) to silicon and aluminum, resulting in smaller stresses. The practical implications of the ANSYS results and the preceding information are that materials must be chosen carefully when carrying out bonding. Material should not be used with a much higher or lower CTE than silicon to ensure fracture will not occur. This finding is a valuable component of this particular packaging system and should benefit the other packaging processes involving bonding MEMS packaging because it supports the prediction that Pyrex glass is an excellent material to use when bonding with silicon in MEMS packaging, as long as sufficiently wide adhesive material is used.

37.3.2 Packaging Reliability

The thermal stress induced by the CTE mismatch is one of the main factors that affect the packaging reliability. As a matter of fact, the formation of the stress can happen not only during packaging process but also during the operation of devices. In particular, during device operation, the package will go through various temperature cycles because of environment change. Such temperature variation causes the expansion of packaging materials when they are constrained by the packaged assembly. As a result of such thermal mismatch, significant stresses are induced in the package and finally cause the device to fail. In addition to thermal mismatch, corrosion creep, fracture fatigue, crack initiation and propagation, and delamination of thin films are all possible factors to cause failure of packaged devices [37.94]. These failure mechanisms could be prevented or deferred under proper packaging designs. For instance, the thermally induced strain inside the packaging material is generally below the tolerance of the material and can't cause immediate catastrophic damage. But cyclic loading can generate and accumulate stresses, eventually causing failure. Several common designs in IC packaging have been used to prolong the lifetime of devices. For example, the strain in solder interconnects of BGA or flip-chip packaging can be effectively reduced by introducing a polymer underfill material between the chip and the substrate to distribute thermal stress induced by CTE mismatch [37.95]. The strain can further be reduced if excellent thermal paths are built around interconnects to diminish the thermal stress originated from the temperature gradient between ambient and operation temperatures. Delamination phenomenon is another source to cause reliability problems, and it happens in the interface of adjacent material layers. In MEMS, components made of dissimilar materials are commonly bonded together to provide specific functions. Delamination can result in electrical or mechanical failures of devices in the package such as mechanically cracking through the electrical via wall to make an electrical open because of the propagation of the delamination of metal line from the dielectric layer or over heating of the die because of the delamination of die from its underneath to make an opening on the heat dissipation path. Because the stress and thermal loading, the geometry, and the material properties are complex in MEMS, the development of the packaging designs to increase the reliability is very important and requires more extensive investigations.

Reliability testing is required before a new device can be delivered to the market. The test results can provide the information for the following improvement of packaging design and fabrication. How to analyze the failure data, called the "reliability metrology", is thus very important in the packaging industry. The analysis method is to use the mathematical tools of probability and statistical distributions to evaluate data to understand the patterns and identify the sources of failure. For example, a failure density function is defined as the time derivative of the cumulative failure function

$$f(t) = \frac{\mathrm{d}F(t)}{\mathrm{d}t}\,, \tag{37.1}$$

$$F(t) = \int_0^t f(s)\,\mathrm{d}s\,. \tag{37.2}$$

The cumulative failure function, $F(t)$, is the fraction of a group of original devices that has failed at time t. The Weibull distribution function is one of the analytic mathematic models commonly used in the packaging reliability evaluation to represent the failure density function [37.21].

$$f(t) = \frac{\beta}{\lambda}\left(\frac{t}{\lambda}\right)^{\beta-1} \exp\left[-\left(\frac{t}{\lambda}\right)^{\beta}\right], \tag{37.3}$$

where β and λ are the Weibull parameters. The parameters β, called a shape factor, measures how the failure frequency is distributed around the average lifetime. The parameter λ is called the lifetime parameter and indicates the time at which 63.2% of the devices faile. By integrating both sides of the equation (37.3). $F(t)$ becomes:

$$F(t) = 1 - \exp\left[-\left(\frac{t}{\lambda}\right)^{\beta}\right]. \tag{37.4}$$

Using the Weibull distribution function with the two parameters extrapolated by experimental data, one can estimate the number of failures at any time during the test. Moreover, by knowing the meaning and values of the parameters, one can compare two sets of test data. For example, the λ with greater number means this set of samples has longer lifetime. Because all of the mathematical models are statistical approximations based on the real experimental data, more testing samples can provide more accurate estimation.

37.3.3 Long-Term and Accelerated MEMS Packaging Tests

The reliability of MEMS packages is best characterized by means of long-term tests with statistical data analyses. But it is very difficult and time-consuming to obtain these experimental data so accelerated tests that put samples in extreme environment for accelerated failure are commonly used to predict the lifetime of the devices. Unfortunately, few research publications deal with these two issues. In this section, two MEMS packaging examples that aim to address these two tests we discuss.

Figure 37.16 shows long-term measurements of the Q factor of a vacuum packaged μ-resonators using localized aluminum/silicon-to-glass bonding [37.81] vacuum encapsulation process is described in details as shown in Fig. 37.8. It is found that the vacuum package by means of localized heating and bonding provides stable vacuum environments for the μ-resonator and a quality factor of 9,600 has been achieved with no degradation for at least one year. Since the performance of high Q μ-resonator is very sensitive to environmental pressure as shown in Fig. 37.11, any leakage can be easily detected. The fact that this high Q value can hold for one year indicates the packaging process is well performed and both aluminum and Pyrex glass are suitable materials for vacuum packaging applications. According to a previous study of hermeticity in different materials, metal has lower permeability to moisture than other materials such as glass, epoxy, and silicon. With a width of 1 μm, metal can effectively block moisture for more than ten years [37.21]. In this vacuum package system, the bonding width is 30 μm so it can sufficiently block the diffusion process of moisture. On the other hand, the diffusion effects of air molecules into these tiny cavities have not been studied extensively, and the design guidelines for vacuum encapsulations are not clearly defined. Further investigations will be needed in this area, and the example presented here serves as a good starting point.

On the other hand, accelerated testing puts a large amount of samples in harsh environments, such as elevated temperature, elevated pressure, and 100% humidity, to accelerate the corrosion process. The statistical failure data are gathered and analyzed to predict the lifetime of packages under normal usage environment. As a result, the long-term reliability of the package can be predicted without going through the true long-term tests. Unfortunately, accelerated tests have not been addressed in MEMS research papers. Although the MEMS industry must have done some extensive reliability tests, they do not publish their results, probably due to liability concerns. Among the very limited publications, this section uses as the illustration example a specific MEMS packaging system that has gone through accelerated tests [37.45].



Fig. 37.16 Long-term measurement of encapsulated μ-resonators. No degradation of Q factors is found after 56 weeks

The MEMS package is accomplished by means of RTP (Rapid Thermal Processing) bonding as described previously in this chapter. The goal of the accelerated test is to examine the failure rate at the bonding interface. The accelerated tests start by putting the packaged samples into the autoclave chamber filled with high temperature and pressurized steam at 130 °C, 2.7 atm, and 100% relative humidity for accelerated testing. The pressurized steam can penetrate small cracks if any defect exists at the bonding interface [37.96]. Elevated temperature and humid environment speed up the corrosion process. A package is considered a failure if water is condensed or diffused into the package. Statistical failure data are gathered every 24 h under optical examination for a period of 864 h, during which time new failure is seldom observed. Because of the robustness of the samples, it is difficult to conduct the tests to the point at which all the packages may fail. The cumulative failure function is recorded, and it is found that most failures occur in the first 96 h and such high early failure rate reflects the yielding issue of the bonding process. Weibull and Lognormal models are compared to predict the lifetime of the packages, and it is found that Lognormal model better describes the statistical data. Figure 37.17 shows the inverse standard normal distribution function vs. ln(time) and the Maximum Likelihood Estimator (MLE) is then used to predict the mean, standard deviation, and the MTTF (mean time to failure). Table 37.2 shows the MLE calculation results of MTTF. The wide interval of confidence level comes from the fact that only a small number of samples failed at the end of the test. It is also observed that packages with larger bonding width and smaller bonding areas have larger MTTF values. The lower bound of the MTTF provides the worst-case scenario. For example, only 4 our of 31 samples failed when tests stopped in the case of ring width of 200 μm and sealing area of $450\times450\,\mu\text{m}^2$. The MTTF predicts, in the worst-case scenario, that there



Fig. 37.17 Life data fitted by Lognormal distribution. R^2 is the coefficient of determination

Table 37.2 The Maximum Likelihood Estimation for Mean Time To Failure (MTTF)

MLE calculation resuls of MMTF[a]				
Bonding width, W (µm)	Area, A (µm²)	MTTF		Worst cases in jungle condition (years)
		UB (years)	LB (years)	
200	450× 450	1.8×10^7	0.57	1,700
100	450× 450	5.3	0.10	300
200	1,000×1,000	6.5×10^3	0.09	270
150	1,000×1,000	0.50	0.017	50

[a] UB is the upper bound, and LB is the lower bound of the 90% confidence interval, respectively. The MTTF LB times AF is the worst case MTTF used in jungle condition.

is 90% chance a package will fail in 0.57 years in the autoclave environment.

It is widely accepted that the acceleration factor (AF) for autoclave tests follows the Arrhenius equation [37.21] and can be modeled as:

$$\mathrm{AF} = \frac{(\mathrm{RH}^{-n}\,\mathrm{e}^{\Delta E_\mathrm{a}/kT})_{\mathrm{normal}}}{(\mathrm{RH}^{-n}\,\mathrm{e}^{\Delta E_\mathrm{a}/kT})_{\mathrm{accelerated}}}\,, \tag{37.5}$$

where RH is relative humidity (85%, RH = 85), k the Boltzmann constant and T the absolute temperature. The recommended value for n, an empirical constant, is 3.0 [37.97], and ΔE_a, the activation energy, is 0.9 eV for plastic dip package and 0.997 eV for anodically bonded glass-to-silicon package [37.58]. If $\Delta E_\mathrm{a} = 0.9$ is used to estimate the AF for the accelerated testing condition as compared with the jungle condition (35 °C, 1 atm and 95% RH), AF is about 3,000, and the worst-case lifetime values in jungle condition are also listed in Table 37.2. The high values of estimated MTTF in jungle condition could be a result of overestimation of AF because plastic dip package may have smaller AFs than those of glass packages. Nevertheless, these data and analyses provide important guidelines in the area of accelerated tests for MEMS packages.

37.4 Future Trends and Summary

In the past, the development of MEMS packaging is mainly originated from IC packaging advancement because existing packaging techniques can significantly reduce the development cost of MEMS. It is expected that the situation will be changed very soon, hoewever, in a way the MEMS packaging approaches will assist the IC packaging development. Recent advances in IC packaging aim to provide high I/O density and more chip integration capability for the needs of high speed and high data communication rate. In order to satisfy those requirements, several packaging concepts and techniques are developed, including 3-D packaging, wafer-level packaging, BGA, and flip-chip technique. Although all of the concepts and methods can provide a package with more I/O density, flexibility in chip integration, and lower manufacturing cost for IC fabrication, they are still insufficient for providing solutions for the future applications because of the increase of complexity and requirements of MEMS packaging. On the contrary, with the progress of MEMS fabrication technologies, several key processes such as DRIE (Deep Reactive Ion Etching), wafer bonding, and thick photoresist processes [37.98] have been utilized for IC packaging fabrication. Technologies developed in MEMS fabrication can therefore also assist the development of new IC packaging approaches.

In order to address the future needs of process integration, adaptive multi-chip module (MCM) [37.28] or 3-D packaging combined with vertical through substrate interconnects [37.10, 99] are promising approaches for the development of future MEMS packaging processes. Based on low temperature flip-chip solder bonding technique, these packaging methods can provide more flexibility in device fabrication and packaging. Devices can be fabricated before they are integrated to form microsystems to dramatically reduce the packaging cost. Vertical through substrate interconnects can have higher I/O density, smaller resistance, parasitic capacitance, and mutual inductance. Although this approach provides many possible advantages, technical challenges exist. For instance, metal is commonly used as the fill material inside the vertical vias as electrical interconnects, and it may introduce large thermal mismatch with respect to silicon substrate and generate huge thermal stress to cause packaging reliability problems. Moreover, it will be an interesting engineering challenge to fill the materials into those high aspect ratio vias.

The future development of MEMS packaging depends on the successful implementation of unique techniques as described in the following:

1. Development of mechanical, thermal, and electrical models for packaging designs and fabrication processes;
2. Wafer-level, chip-scale packaging with low packaging cost and high yield;
3. Effective testing techniques at the wafer level to reduce the testing costs;
4. Device integrations by vertical through-interconnects as an interposer [37.1] to avoid thermal mismatch problems.

In addition to these approaches and challenges, many other possibilities have not been listed but also require dedicated investigations. For example, several key nanotechnologies have been introduced in the previous chapters, but the packaging solutions for the NEMS devices have not been addressed. Because it is feasible to use MEMS as the platform for NEMS fabrication, all of the packaging issues discussed in the chapter can be directly applied to NEMS devices. On the other hand, nanotechnology may introduce new opportunities for MEMS/NEMS packaging applications by providing superior electrical, mechanical, and thermal properties [37.100–103]. For example, carbon nanotubes have very high thermal conductivity [37.102] and may be suitable to increase the thermal cooling effects for better IC/MEMS/NEMS packaging applications.

In summary, MEMS packaging issues have been introduced in the areas of fabrication, application, reliability, and future development. Packaging design and modeling, packaging material selection, packaging process integration, and packaging cost are the main issues to be considered when developing a new MEMS packaging process.

References

37.1 M. Matsuo, N. Hayasaka, K. Okumura, E. Hosomi, C. Takubo: Silicon interposer technology for high-density package, IEEE ECTC (2000) 1455–1459

37.2 K. E. Peterson: Silicon as a mechanical material, Proc. IEEE **70** (1982) 420–457

37.3 L. Lin, H.-C. Chu, Y.-W. Lu: A simulation program for the sensitivity and linearity of piezoresistive pressure sensors, IEEE/ASME J. Microelectromech. Syst. **8** (1999) 514–522

37.4 Y. C. Tai, R. S. Muller: Lightly-doped polysilicon bridge as a flow meter, Sens. Actuators **15** (1988) 63–75

37.5 D. Hicks, S.-C. Chang, M. W. Putty, D. S. Eddy: Piezoelectrically activated resonant bridge micro-accelerometer, 1994 Solid-State Sensors and Actuators Workshop (1994) 225–228

37.6 J. Berstein, S. Cho, A. King, A. Kourepenis, P. Maciel, M. Weinberg: A micromachined comb-drive tuning fork rate gyroscope, 6th IEEE Int. Conf. on MEMS (1993) 143–148

37.7 M. Madou: Compatibility and incompatibility of chemical sensors and analytical equipment with micromachining, Solid-State Sensor and Actuator Workshop, Hilton Head (1994) 164–171

37.8 M. J. Zdeblick, J. B. Angell: A microminiature electric-to-fluidic valve, Proceedings of Transducers'87, the 4th International Conference on Solid-State Transducers and Actuators (1987) 827–829

37.9 J. H. Tsai, L. Lin: A thermal bubble actuated micro nozzle-diffuser pump, IEEE/ASME J. Microelectromech. Syst. **11** (2002)

37.10 S. J. Ok, D. Baldwin: High density, aspect ratio through-wafer electrical interconnect vias for low cost, generic modular MEMS packaging, 8th IEEE Int. Symp. On Adv. Pack. Mater. (2002) 8–11

37.11 H. Reichl, V. Grosser: Overview and development trends in the field of MEMS packaging, 14th IEEE Int. Conf. on MEMS (2001) 1–5

37.12 P. Kapur, P. M. McVittie, K. Saraswat: Technology and reliability constrained future copper interconnects=Part II: Performance implication, Trans. Electron. Dev. **49** (2002) 598–604

37.13 J. Lau: *Flip Chip Technologies* (McGraw-Hill, New York 1996)

37.14 R. Prasad: *Surface Mount Technology: Principles and Practice*, 2nd edn. (Chapman, New York 1989)

37.15 M. Töpper, J. Auersperg, V. Glaw, K. Kaskoun, E. Prack, B. Keser, P. Coskina, D. Jäger, D. Petter, O. Ehrmann, K. Samulewicz, C. Meinherz, S. Fehlberg, C. Karduck, H. Reichl: Fab integrated packaging (FIP) a new concept for high reliability wafer-level chip size packaging, IEEE, ECTC (2000) 74–81

37.16 S. Savastiouk, O. Siniaguine, Ed. Korczynski: 3D wafer level packaging, IEEE, ECTC. (2000) 26–31

37.17 J. H. Tsai, L. Lin: Micro-to-macro fluidic interconnectors with an integrated polymer sealant, J. Micromech. Microeng. **11** (2001) 577–581

37.18 T. A. Core, W. K. Tsang, S. Sherman: Fabrication technology for an integrated surface-micromachined sensor, Solid State Technol. (October 1993) 39–47

37.19 K. Koester, R. Majedevan, A. Shishkoff, K. Marcus: *Multi-Sser MEMS Processes (MUMPS) Introduction and Design Rules* (MCNC MEMS Technology Applications Center, Research Triangle Park, NC 27709 1996)

37.20 R. Lengtenberg, H. A. C. Tilmans: Electrically driven vacuum-encapsulated polysilicon resonantor, Part I: Design and fabrication, Sens. Actuators A **45** (1994) 57–66

37.21 R. R. Tummala, E. J. Rymaszewski, A. G. Klopfenstein: *Microelectronics Packaging Handbook, Semiconductor Packaging* (Chapman, New York 1997)

37.22 S. Wolf: *Silicon Processing for the VLSI era, Vol. I: Process Technology* (Lattice Press, Sunset Beach 1995)

37.23 J. K. Bhardway, H. Ashraf: Advanced silicon etching using high density plasmas, SPIE Micromach. Fabr. Technol. **2639** (1995) 224–233

37.24 W. H. Ko, J. T. Suminto, G. J. Yeh: *Bonding Techniques for Microsensors, Micromachining and Micropackaging for Transducers* (Elsevier, Amsterdam 1985)

37.25 S. D. Senturia, R. L. Smith: Microsensor packaging and system partitioning, Sens. Actuators **15** (1988) 221–234

37.26 R. L. Smith, S. D. Collins: Micromachined packaging for chemical microsensors, IEEE Trans. Electron Dev. **35** (1988) 787–792

37.27 J. T. Butler, V. M. Bright, P. B. Chu, R. J. Saia: Adapting multichip module foundries for MEMS packaging, Int. Conf. on Multi. Mod. High Den. Pack. (1998) 106–111

37.28 M. Schuenemann, A. J. Kourosh, V. Grosser, R. Leutenbauer, G. Bauer, W. Schaefer, H. Reichl: MEM modular packaging and interfaces, IEEE ECTC (2000) 681–688

37.29 D. W. Lee, T. Ono, T. Abe, M. Esashi: Fabrication of microprobe array with sub-100nm nano-heater for nanometric thermal imaging and data storage, Proc. IEEE Micro Electro Mechanical Systems Conf., IEEE Int. Conf. on MEMS (January 2001) 204–207

37.30 A. S. Laskar, B. Blythe: Epoxy multichip modules, a solution to the problem of packaging and interconnection of sensors and signal-processing chips, Sens. Actuators A **36** (1993) 1–27

37.31 R. Reichl: Packaging and interconnection of sensors, Sens. Actuators A **25–27** (1991) 63–71
37.32 A. Grisel, C. Francis, E. Verney, G. Mondin: Packaging technologies for integrated electrochemical sensors, Sens. Actuators **17** (1989) 285–295
37.33 J. L. Lund, K. D. Wise: Chip-level encapsulation of implantable CMOS microelectrode arrays, 1994 Solid-State Sensor and Actuator Workshop, Hilton Head (1994) 29–32
37.34 T. Akin, B. Siaie, K. Najafi: Modular micromachined high-density connector for implantable biomedical systems, IEEE Micro Electro Mechanical Systems Workshop (1996) 497–502
37.35 L. Muller, M. H. Hecht, L. M. Miller et al.: Packaging qualification for MEMS-based space systems, IEEE Micro Electro Mechanical Systems Workshop 503–508
37.36 L. Lin, K. McNair, R. T. Howe, A. P. Pisano: Vacuum encapsulated lateral microresoantors, 7th Int. Conference on Solid State Sensors and Actuators (June 1993) 270–273
37.37 H. Guckel: Surface micromachined pressure transducers, Sens. Actuators A **28** (1991) 133–146
37.38 J. J. Sniegowski, H. Guckel, R. T. Christenson: Performance characteristics of second generation polysilicon resonating beam force transducers, IEEE Solid-State Sensor and Actuator Workshop, Hilton Head Island (1990) 9–12
37.39 K. Ikeda, H. Kuwayama, T. Kobayashi, T. Watanabe, T. Nishikawa, T. Oshida, K. Harada: Three dimensional micromachining of silicon pressure sensor integrating resonant strain gauge on diaphragm, Sens. Actuators A **21–23** (1990) 1001–1010
37.40 C. H. Mastrangelo, R. S. Muller: Vacuum-sealed silicon micromachined incandescent light source, IEEE IEDM (1989) 503–506
37.41 J. Smith, S. Montague, J. Sniegowski, R. Manginell, P. McWhorter, R. Huber: Characterization of the embedded micromechanical device approach to the monolithic integration of MEMS with CMOS, SPIE 2879
37.42 S. Van der Groen, M. Rosmeulen, P. Jansen, K. Baert, L. Deferm: CMOS compatible wafer scale adhesive bonding for circuit transfer, 1997 International Conference on Solid-State Sensors and Actuators, Transducers'97 (1997) 629–632
37.43 M. B. Cohn, Y. Liang, R. Howe, A. P. Pisano: Wafer to wafer transfer of microstructures for vacuum package, Solid State Sensor and Actuator Workshop, Hilton Head (1996) 32–35
37.44 Y. T. Cheng, Y. T. Hsu, L. Lin, C. T. Nguyen, K. Najafi: Vacuum packaging using localized aluminum/silicon-to-glass bonding, Int. Conf. on MEMS (2001) 18–21
37.45 M. Chiao, L. Lin: Vacuum packaging of microresonators by rapid thermal processing, Proc. of SPIE on Smart Electronics, MEMS, and Nanotechnology (2002) 17–21
37.46 M. Esashi, S. Shoji, A. Nakano: Normally closed microvalve and micropump fabricated on a silicon wafer, Sens. Actuators **20** (1989) 163–169
37.47 M. E. Poplawski, R. W. Hower, R. B. Brown: A simple packaging process for chemical sensors, Solid-State Sensor and Actuator Workshop, Hilton Head (1994) 25–28
37.48 S. F. Trautweiler, O. Paul, J. Stahl, H. Baltes: Anodically bonded silicon membranes for sealed and flush mounted microsensors, Micro Electro Mechanical Systems Workshop (1996) 61–66
37.49 E. H. Klaassen, K. Petersen, J. M. Noworolski, J. Logan, N. I. Malfu, J. Brown, C. Storment, W. McCulley, G. T. A. Kovac: Silicon fusion bonding and deep reactive ion etching: A new technology for microstructures, Sens. Actuators A **52** (1996) 132–139
37.50 C. H. Hsu, M. A. Schmidt: Micromachined structures fabricated using a wafer-bonded sealed cavity process, Solid State Sensor and Actuator Workshop, Hilton Head (1994) 151–155
37.51 A. L. Tiensuu, J. A. Schweitz, S. Johansson: In situ investigation of precise high strength micro assembly using Au-Si eutectic bonding, Int. Conf. Solid-State Sens. Actuators, Eurosens. IX (1995) 236–239
37.52 A. P. Lee, D. R. Ciarlo, P. A. Krulevitch, S. Lehew, J. Trevino, M. A. Northrup: Practical microgripper by fine alignment, eutectic bonding and SMA actuation, Int. Conf. Solid-State Sens. Actuators, Eurosens. IX (1995) 368–371
37.53 R. W. Bower, M. S. Ismail, B. E. Roberds: Low temperature Si_3N_4 direct bonding, Appl. Phys. Lett. **62** (1993) 3485–3487
37.54 H. Takagi, R. Maeda, T. R. Chung, T. Suga: Low temperature direct bonding of silicon and silicon dioxide by the surface activation method, Int. Conf. on Solid-State Sensors and Actuators, Transducer 97 (1997) 657–660
37.55 G. Wallis, D. Pomerantz: Filed assisted glass-metal sealing, J. Appl. Phys. **40** (1969) 3946–3949
37.56 L. Bowman, J. Meindl: The packaging of implantable integrated sensors, IEEE Trans. Biomed. Engin. **33** (1986) 248–255
37.57 M. Esashi: Encapsulated micro mechanical sensors, Microsyst. Technol. **1** (1994) 2–9
37.58 B. Ziaie, J. Von Arx, M. Dokmeci, K. Najafi: A hermetic glass-silicon micropackages with high-density on-Chip feedthroughs for sensors and actuators, J. Microelectromech. Syst. **5** (1996) 166–179
37.59 Y. Lee, K. Wise: A batch-fabricated silicon capacitive pressure transducer with low temperature sensitivity, IEEE Trans. Electron Dev. **29** (1982) 42–48
37.60 S. Shoji, H. Kicuchi, H. Torigoe: Anodic bonding below 180 degree C for packaging and assembling of MEMS using lithium aluminosilicate-beta-quartz glass-ceramic, Proc. 10th Annual Int. Workshop Micro Electro Mechanical Systems (1997) 482–487

37.61 M. Esashi, N. Akira, S. Shoji, H. Hebiguchi: Low-temperature silicon-to-silicon anodic bonding with intermediate low melting point glass, Sens. Actuators A **23** (1990) 931–934

37.62 A. Hanneborg, M. Nese, H. Jakobsen, R. Holm: Silicon-to-thin film anodic bonding, J. Micromech. Microeng. **2** (1992) 117–121

37.63 S.A. Audet, K.M. Edenfeld: Integrated sensor wafer-level packaging, International Conference on Solid-State Sensors and Actuators, Transducers'97 (1997) 287–289

37.64 R.C. Benson, N. deHaas, P. Goodwin, T.E. Phillips: Epoxy adhesives in microelectronic hybrid applications, Johns Hopkins APL Tech. Dig. **13** (1992) 400–406

37.65 M. Shimbo, J. Yoshikawa: New silicon bonding method, J. Electrochem. Soc. **143** (1996) 2371–2377

37.66 P.M. Zavracky, B. Vu: Patterned eutectic bonding with Al/Ge thin film for MEMS, SPIE **2639** (1995) 46–52

37.67 G. Humpston, D.M. Jacobson: Principles of soldering and brazing, ASM Int. (1993) 241–244

37.68 A. Singh, D. Horsely, M.B. Cohn, R. Howe: Batch transfer of microstructures using flip-chip solder bump bonding, International Conference on Solid State Sensors and Actuators, Transducer 97 (1997) 265–268

37.69 M.M. Maharbiz, M.B. Cohn, R.T. Howe, R. Horowitz, A.P. Pisano: Batch micropackaging by compression-bonded wafer-wafer transfer, 12th Int. Conf. MEMS (1999) 482–489

37.70 Y.T. Cheng, L. Lin, K. Najafi: Localized silicon fusion and eutectic bonding for MEMS fabrication and packaging, IEEE/ASME J. Microelectromech. Syst. **9** (2000) 3–8

37.71 L. Lin: Selective encapsulations of MEMS: micro channels, needles, resonators, and electromechanical filters. Ph.D. Thesis (University of California, Berkeley 1993)

37.72 Y.C. Su, L. Lin: Localized plastic bonding for micro assembly, packaging and liquid encapsulation, Proceedings of IEEE Micro Electro Mechanical Systems Conference, Interlaken (2001) 50–53

37.73 M. Schwartz: *Brazing* (Chapman, London 1995)

37.74 L. Lin, R.T. Howe, A.P. Pisano: Microelectromechanical Filters for Signal Processing, IEEE/ASME J. Microelectromech. Syst. **7** (1998) 286–294

37.75 W.C. Tang, C.T.-C. Nguyen, R.T. Howe: Laterally driven polysilicon resonant microstructures, Sens. Actuators A **20** (1989) 25–32

37.76 G.T. Mulhern, D.S. Soane, R.T. Howe: Supercritical carbon dioxide drying of microstructures, 7th International Conference on Solid State Sensors and Actuators, Yokohama (1993) 296–299

37.77 M. Judy: Micromechanisms using sidewall beams. Ph.D. Thesis (University of California, Berkeley 1994)

37.78 A.M. Leung, J. Jones, E. Czyzewska, J. Chen, B. Woods: Micromachined accelerometer based on convection heat transfer, International Conference on MEMS (1998) 627–630

37.79 D.R. Spark, L. Jordan, J.H. Frazee: Flexible vacuum-packaging method for resonating micromachines, Sens. Actuators A **55** (1996) 179–183

37.80 SensArray Corporation, 47451 Fremont Blvd. Fremont, CA 94538

37.81 Y.T. Cheng, W.T. Hsu, K. Najafi, C.T. Nguyen, L. Lin: Vacuum packaging technology using localized aluminum/silicon-to-glass bonding, IEEE/ASME J. Microelectromech. Syst. **11** (2002) 556–565

37.82 C. Luo, L. Lin: The application of nanosecond-pulsed laser welding technology in MEMS packaging with a shadow mask, Sens. Actuators A **97–98** (2002) 398–404

37.83 A. Cao, M. Chiao, Liwei. Lin: Selective and localized wafer bonding using induction heating, Technical Digest of Solid-State Sensors and Actuators Workshop (2002) 153–156

37.84 J.B. Kim, M. Chiao, L. Lin: Ultrasonic Bonding of In/Au and Al/Al for Hermetic Sealing of MEMS Packaging, Proceedings of IEEE Micro Electro Mechanical Systems Conference (2002) 415–418

37.85 Y.T. Cheng, L. Lin, K. Najafi: Localized bonding with PSG or indium solder as intermediate layer, 12th International Conference on MEMS (1999) 285–289

37.86 G. Thyrum, E. Cruse: Heat pipe simulation, a simplified technique for modeling heat pipe assisted heat sinks, Adv. Packaging (2001) 23–27

37.87 G.P. Peterson, A.B. Duncan, M.H. Weichold: Experimental investigation of micro heat pipes fabricated in silicon wafers, J. Heat Trans. (1993) 751–756

37.88 L. Jiang, M. Wong, Y. Zohar: Forced convection boiling in a microchannel heat sink, J. Microelectromech. Syst. **10** (2001) 80–87

37.89 F. Arias, S.R.J. Oliver, B. Xu, E. Holmlin, G.M. Whitesides: Fabrication of metallic exchangers using sacrificial polymer mandrils, IEEE/ASME J. Microelectromech. Syst. **10** (2001) 107–112

37.90 M. Chiao, L. Lin: Hermetic wafer bonding based on rapid thermal processing, Sens. Actuators A **91** (2001) 404–408

37.91 *ANSYS Modeling and Meshing Guide*, 3rd edn. (SAS IP, Inc., Canousburg 2002)

37.92 D. Bystrom, L. Lin: Residual stress analysis of silicon-aluminum-glass bonding processes, ASME International Mechanical Engineering Congress and Exposition, MEMS Symposium (November 2002)

37.93 H. Scholze: *Glass: Nature, Structure, and Properties*, 1st edn. (Springer, Berlin, Heidelberg 1991)

37.94 R.R. Tummala: *Fundamentals of Microsystems packaging* (McGraw-Hill, New York 2001)

37.95 S.J. Adamson: BGA, CSP, and flip chip, Adv. Packaging (2002) 21–24

37.96 D. Steoehle: On the penetration of water vapor into packages with cavities and on maximum allow-

able leak rate, 15th Annual Proceeding Reliability Physics Symposium (1977) 101–106
37.97 W. D. Brown: *Advanced Electronic Packaging* (IEEE Press, 1999)
37.98 F. Niklaus, P. Znoksson, E. Käluesten, G. Stemme: Void free full wafer adhesion bonding, Proceedings of IEEE Micro Electro Mechanical Systems Conf. 2000) 241–252
37.99 C. H. Cheng, A. S. Ergun, B. T. Khuri-Yakub: Electrical through-wafer interconnects with sub-picofarad parasitic capacitance, IEEE ECTC (2002) 18–21
37.100 D. Routkevitch, A. A. Tager, J. Haruyama, D. Almawlawi, M. Moskovits, J. M. Xu: Nonlithographic nano-array arrays: fabrication, physics, and device applications, IEEE Trans. Electron. Dev. **43** (1996) 1646–1658
37.101 J. Gou, M. Lundstrom, S. Datta: Performance projections for ballistic carbon nanotube fieldeffect transistors, Appl. Phys. Lett. **80** (2002) 3192–3194
37.102 S. U. S. Choi, Z. G. Zhang, W. Yu, F. E. Lockwood, E. A. Grulke: Anomalous thermal conductivity enhancement in nanotube suspensions, Appl. Phys. Lett. **79** (2001) 2252–2254
37.103 K. Velikov, A. Moroz, A. Blaaderen: Photonic crystals of core-shell colloidal particles, Appl. Phys. Lett. **80** (2002) 49–51

Part F Social and Ethical Implication

38 Social and Ethical Implications of Nanotechnology
William S. Bainbridge, Arlington, USA

Springer Handbook of Nanotechnology
B. Bhushan • © Springer 2004

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

38. Social and Ethical Implications of Nanotechnology

Social and Etl

Nanotechnology will have very broad applications across all fields of engineering, so it will be an amplifier of the social effects of other technologies. There is an especially great potential for it to combine with three other powerful trends – biotechnology, information technology, and cognitive science – based on the material unity of nature at the nanoscale and on technology integration from that scale. Technological convergence highlights such existing issues as the treatment of the disabled, communication breakdowns, economic stagnation, and threats to national security. Nanotechnology itself may possibly raise distinctive ethical and social issues in the future, but much of the public discussion to this point has been misdirected and misinformed, lacking a firm social scientific basis. Thus it will be important to integrate social and ethical studies into nanotechnology developments from their very beginning.

Social scientific and economic research can help manufacturers and governments make the right decisions when deploying a new technology, maximizing its benefit for human beings. In addition, technically competent research on the societal implications of nanotechnology will help give policymakers and the general public a realistic picture free of unreasonable hopes or fears. The costs of premature or excessive regulation would be extremely high, harming the very people it was intended to protect, and failure to develop beneficial nanotechnology applications would be unethical.

The significance of nanotechnology depends largely on how its development relates to wider trends going on in the world such as the impending population declines of most advanced industrial nations, the apparent diminishing returns to increased medical research and health care investment, and the threatened deceleration of progress in microelectronics. Well established social-scientific explanations for unethical behavior – such as learning, strain, control, and subculture theories – could help us understand possible future cases in nanotechnology industries. Ethics and social implications are largely matters of social perception, and the public conception of nanotechnology is still in the early stages of developing. Social science can now begin to examine its unfolding impacts in all sectors of the economy, in most spheres of life, and both short-term and long-term time scales.

38.1 **Applications and Societal Impacts** 1136
38.2 **Technological Convergence** 1139
38.3 **Major Socio-technical Trends** 1141
38.4 **Sources of Ethical Behavior** 1143
38.5 **Public Opinion** 1145
38.6 **A Research Agenda** 1148
References 1149

The views expressed in this essay do not necessarily represent the views of the National Science Foundation or the United States.

Science and engineering have only begun to explore the potential for discovery and creativity at the nanoscale, but already some intemperate voices call for government regulation or outright banning of nanotechnology [38.1–4]. Such action would be extremely premature, because we have just started on a very long road of research that we must traverse before we will know what is technically practical, what real-world applications nanotechnology might actually have, and what the appropriate societal responses would be to any hazards that might be directly or indirectly related to these applications. Some writers in the popular press seem to treat nanotechnology as

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

a new kind of Frankenstein's Monster, but it is worth remembering that biological science is still not able to create such a monster, nearly two centuries after Mary Shelly imagined one.

A good starting point for consideration of social and ethical issues is a formal definition of the topic, but unfortunately a somewhat different definition has lodged in the public mind from that employed by professionals working in the field. For example, *Merriam-Webster's Collegiate Dictionary* defines *nanotechnology* as: "the art of manipulating materials on an atomic or molecular scale especially to build microscopic devices (as robots)." Similarly, the online reference About.com defines it thus: "The development and use of devices that have a size of only a few nanometres." Later, we will examine public conceptions more closely, but it is worth noting here that these definitions focus on robot-like devices constructed at the nanoscale and ignore the topics of most chapters in this volume.

A more authoritative if long-winded definition of *nanotechnology* has been provided by the U.S. Government's National Nanotechnology Initiative: "Research and technology development at the atomic, molecular or macromolecular levels, in the length scale of approximately 1–100 nm range, to provide a fundamental understanding of phenomena and materials at the nanoscale and to create and use structures, devices and systems that have novel properties and functions because of their small and/or intermediate size. The novel and differentiating properties and functions are developed at a critical length scale of matter typically under 100 nm. Nanotechnology research and development includes manipulation under control of the nanoscale structures and their integration into larger material components, systems and architectures."

While this definition includes the word "devices," it also covers materials, structures, and systems. Significantly, it envisions that many nanotechnology advances will be integrated into "larger material components, systems and architectures," which means that we would need to understand the social and ethical implications of the larger-scale systems of which nanoscale structures are only components.

There is good reason to believe that engineering at the nanoscale will have very broad applications across all fields of technology and most fields of science [38.5–7]. Therefore, it will be an enabler or amplifier of the effects of other technologies. This means that it is foolish to ask, "Is nanotechnology harmful?" Nanotechnology is not one thing, either ethical or unethical. Rather, it is a myriad of different things – many nanotechnologies – each of which has a range of potential uses and misuses in conjunction with other technologies and applied to different goals.

This line of reasoning could lead some people to conclude that we did not need to worry at all about the social and ethical implications of nanotechnology, because they will be subsumed by the implications of larger systems. Others might conclude that it is far too early in the history of nanoscale engineering to consider societal implications, because we cannot study the impact of a technology that does not yet exist.

However, the very fact that some writers are urging regulation or banning of nanotechnology suggests that the debate about its value to humanity has begun, and we need to bring the best possible thinking and information to that debate [38.8–10]. In addition, a few relatively simple but significant applications have begun to appear, so in those cases at least an impact can be observed. Social scientists, natural scientists, philosophers, and engineers have indeed begun considering the future of nanotechnology, so we can draw upon the very first serious intellectual efforts in this important field.

38.1 Applications and Societal Impacts

In the year 2000, the National Science and Technology Council sponsored a major workshop at the National Science Foundation, which led to a published report, *Societal Implications of Nanoscience and Nanotechnology* [38.11]. Sixty-four representatives of academic science, government laboratories, and corporate research listed a large number of potential nanotechnology applications, a few of which had already entered production, but many of which could be expected only after decades of research. Following are diverse examples of possible applications suggested by workshop participants concerning a variety of sectors of the economy and spheres of life:

- More efficient components for the semiconductor industry such as integrated circuits containing transistors constructed from carbon nanotubes.

- Nanostructured catalysts for the chemical industry and for more effective converters to handle pollution from automobile exhausts and other combustion.
- Lighter and stronger nanomaterials in bulk quantities to enable safer and more efficient transportation vehicles, including automobiles, aircraft, and train systems.
- Improved pharmaceuticals with features such as programmed delivery to desired targets like tumors and the ability to employ substances that are not soluble in water as medications.
- Cost-effective and reliable filters for water decontamination, desalination, containment of industrial pollutants, and air purification.
- More efficient solar energy conversion, thereby reducing current reliance on oil and offering an alternative to nuclear power for future electricity needs.
- Efficient fuel cells and hydrogen storage systems, leading to nonpolluting automobiles, trucks, and buses.
- More durable composite materials, such as nanoparticle-reinforced polymers, designed for optimal performance in specific uses with reduced waste and greatly increased lifetime.
- Molecularly engineered biodegradable fertilizers and insecticides designed for precision agriculture with efficient delivery to where they are needed and prevention of unwanted side effects.
- Revolutionary launch vehicles with high mass-ratios, nonpolluting but powerful engines, and low electric power needs in order to finally realize the promise of space exploration.
- Nanoscale components in sensor systems that can quickly detect and identify pollutants and disease organisms, as well as chemical or biological warfare agents to allow quick and appropriate medical treatment or security responses.
- Coatings that would give ordinary materials extraordinary properties like self-cleaning window glass and heat-reflecting exterior architectural surfaces.

Knowledgeable scientists and engineers reported that these and many other similar applications were plausible benefits of nanotechnology research, but they recognized that progress has costs. For example, the creation of a new industry often results in the decline or complete destruction of an older industry, as in the proverbial case of buggy-whip manufacturers who were rendered obsolete by the automobile. The potential benefit from a new technology must be calculated in a sophisticated manner, taking into account the full life-cycle costs [38.12]. For example, an electric car may reduce some forms of pollution while increasing others such as the release of lead or other dangerous substances into the environment during the manufacture of the electric battery and the disposal of it when the car is eventually junked.

Many ethical issues of fairness will arise within nanotechnology industries themselves. For example, it will be important to invest in appropriate safeguards for workers engaged in hazardous production processes. In general, scientific discoveries cannot be patented, whereas new products and production methods can, so there will be serious issues of intellectual property protection in nanoscience, a nontraditional field where the legal line between discovery and invention has not yet been clearly drawn. Often, it will be necessary to bring together information and expertise from several different sources in order to create an economically profitable application, drawing upon government-funded university research projects, as well as several specialized industrial corporations, which will require improved models of collaboration across organizations.

As the *Societal Implications* report observed, the general public has a significant stake in the National Nanotechnology Initiative (NNI) that must be managed both directly through public participation and indirectly through the involvement of social scientists:

> It is important to include a wide range of interests, values, and perspectives in the overall decision process that charts the future development of nanotechnology. Involvement of members of the public or their representatives has the added benefit of respecting their interests and enlisting their support. ... The inclusion of social scientists and humanistic scholars, such as philosophers of ethics, in the social process of setting visions for nanotechnology is an important step for the NNI. As scientists or dedicated scholars in their own right, they can respect the professional integrity of nanoscientists and nanotechnologists, while contributing a fresh perspective. Given appropriate support, they could inform themselves deeply enough about a particular nanotechnology to have a well-grounded evaluation. At the same time, they are professionally trained representatives of the public interest and capable of functioning as communicators between nanotechnologists and the public or government officials. Their input may help maximize the societal benefits of the technology while reducing the possibility of debilitating public controversies [38.11].

Social scientific and economic research can help manufacturers and the government make the right decisions when deploying a new technology, maximizing its benefit for human beings. In addition, technically competent research on the societal implications of nanotechnology will help give policymakers and the general public a realistic picture free from unreasonable hopes or fears. As the report notes, the National Nanotechnology Initiative is just now commencing, so "there is a rare opportunity to integrate the societal studies and dialogues from the very beginning and to include societal studies as a core part of the NNI investment strategy" [38.11].

The workshop developed a number of recommendations for government, academia, and industry suggesting how the social and ethical implications of nanotechnology could best be addressed [38.11]. Here are some of the most important principles in education, social science, and ethics:

- Nanoscale concepts should be introduced into science and engineering education at all levels, thereby giving the widest possible range of students a fundamental understanding of the field while intellectually linking nanotechnology to many other fields.
- The training of nanotechnologists should include societal implications and ethical sensitivity, so their future work will be guided by principles that will maximize human benefit.
- A sufficient number and variety of social and economic scientists should receive effective multidisciplinary training, so they will be well prepared to work in the nanotechnology area.
- Formal measurement methods, such as social and economic indicators, should be developed and consistently employed to chart the actual widespread changes in industry, education, and public welfare as they occur.
- Government agencies, private foundations, and industry should support a wide range of high-quality, theory-based social and economic research studies on nanotechnology, examining both the decision processes that shape the emerging technology and itsspecific societal impacts once it is deployed.
- A knowledge base and institutional infrastructure must be created to evaluate the probable future intellectual and societal impacts of nanoscience and nanotechnology over the short, medium, and long term.
- Government and the private sector should establish effective channels for informing the public promptly about new concepts, projects, potential applications, and ethical issues as they emerge.
- There should be formal organizations and mechanisms to ensure participation by diverse societal institutions and the general public in setting priorities for research and development and in providing timely input to decision makers.
- Government and industry should develop management plans and policies that can effectively incorporate all relevant information and legitimate stakeholder interests to ensure that we can respond flexibly to social, ethical, legal, and economic implications as they appear.

It will take time and effort to implement these recommendations, but some progress has already been made. The National Science Foundation has recently funded Rosalyn Berne at the University of Virginia to study the developing ethics of nanotechnology through a narrative analysis of discourse from engineers and scientists in the field, and a team headed by Michael Gorman at the same institution was funded to explore the potential for multidisciplinary research on social and ethical dimensions of nanotechnology. The Environmental Protection Agency, which has supported several research projects on how nanotechnology might remedy conventional forms of pollution, has funded Darrell Velegol and Kristen Fichthorn at Pennsylvania State University to study "Green Engineering of Dispersed Nanoparticles," exploring how valuable nanoparticles might be produced without the use of polluting additives. In its review of the National Nanotechnology Initiative, the National Research Council has recommended the development of "a new funding strategy to ensure that the societal implications of nanoscale science and technology become an integral and vital component of the NNI" [38.13].

38.2 Technological Convergence

In the year following the *Societal Implications* workshop, NSF and the U.S. Department of Commerce staged an even larger meeting to examine the potential for *nanotechnology* to combine with three other powerful scientific and engineering trends: *biotechnology*, *information technology*, and *cognitive science* – four "NBIC" fields. The resulting report, *Converging Technologies for Improving Human Performance* [38.14], examined benefits of technological convergence that would specifically enhance the ability of humans to satisfy their needs and achieve their legitimate goals.

Convergence of diverse NBIC technologies will be based on the material unity of nature at the nanoscale and on technology integration from that scale. This is the scale at which much future biotechnology and the hardware for information technology will operate, and it is the scale from which fundamental research on the human nervous system will take place. Key transforming tools, including research instruments and production methods, will arise in the conjunction of previously separated fields of science. Drawing upon advances in mathematics and computation, it will be possible to model phenomena from the nanoscale to the cosmic scale as complex, coupled, hierarchical systems.

The *Converging Technologies* scientists, engineers, and policymakers sketched six general areas in which the human benefits and social issues are likely to result:

- Overall potential of converging technologies
- Expanding human cognition and communication
- Improving human health and physical capabilities
- Enhancing group and societal outcomes
- National security
- Unifying science and education

Numerous valuable applications were sketched in greater or lesser detail that could reasonably be expected to result from a decade or two of vigorous research and development, including the following ideas that depend on partnerships between nanotechnology and one or more of the other NBIC fields:

- Comfortable, wearable sensors and computers will enhance every person's awareness of his or her health condition, the environment, chemical pollutants, potential hazards, and information of interest about local businesses, natural resources, and the like.
- The human body will be more durable, healthier, more energetic, easier to repair, and more resistant to many kinds of stress, biological threats, and aging processes.
- Machines and structures of all kinds, from homes to aircraft, will be constructed of materials that have exactly the desired properties, including the ability to adapt to changing situations, high energy efficiency, and environmental friendliness.
- A combination of technologies and treatments will compensate for many physical and mental disabilities and will eradicate altogether some handicaps that have plagued the lives of millions of people.
- National security will be greatly strengthened by lightweight, information-rich war fighting systems, capable uninhabited combat vehicles, adaptable smart materials, invulnerable data networks, superior intelligence-gathering systems, and effective measures against biological, chemical, radiological, and nuclear attacks.
- The ability to control the genetics of humans, animals, and agricultural plants will greatly benefit human welfare; widespread consensus about ethical, legal, and moral issues will be built in the process.
- Agriculture and the food industry will greatly increase yields and reduce spoilage through networks of cheap, smart sensors that constantly monitor the condition and needs of plants, animals, and farm products.
- Transportation will be safe, cheap, and fast due to ubiquitous real-time information systems, extremely high-efficiency vehicle designs, and the use of synthetic materials and machines fabricated from the nanoscale for optimum performance.
- The work of scientists will be revolutionized by importing approaches pioneered in other sciences, for example, genetic research employing principles from natural language processing and cultural research employing principles from genetics.
- Formal education will be transformed by a unified but diverse curriculum based on a comprehensive, hierarchical intellectual paradigm for understanding the architecture of the physical world from the nanoscale through the cosmic scale.

Several of these application areas depend upon the development of nanoscale components for sensor, computation, and communication networks. Others involve a synergy between inorganic nanoscale engineering and organic chemistry or biology. Others extrapolate that it will be possible to build large-scale structures that are engineered at the nanoscale to enhance the qualities of architecture, transportation vehicles, or even the human body. Fundamental to all of the application areas is a conceptual revolution that unifies science and provides humanity with a comprehensive view of nature and technology.

Contributors to the report showed how nanoscale science and engineering were essential for progress in biology, information science, and cognitive science. The result of NBIC convergence will be the strengthening of science and the empowerment of humanity, as we will find solutions to many of humanity's problems in health, natural resources, environment, security, and even communication with fellow human beings. Often, the technologies based in the sister sciences will raise ethical issues. In such cases, nanotechnology may become implicated in controversies without being central to them. The correct policy response would then be to ignore the superficial nanotechnology aspects and focus directly on the core problem that lies in a different field. *Converging Technologies* contributors examined how technological convergence highlighted such existing issues as the treatment of the disabled, communication breakdowns, economic stagnation, and threats to national security.

For greater clarity, we can consider here the very specific example of the proliferation of nuclear weapons. Nuclear physics and atomic technology were specifically not included in the constellation of NBIC converging technologies considered by the workshop, so the following discussion supplements its findings. As scientists already understood in the early 1940s, there are fundamentally two ways that a rogue nation can build up its own supply of weapons-grade nuclear materials. One is breeding plutonium in a nuclear reactor fueled by uranium, transmuting the common uranium isotope of atomic weight 238. But this is hard to conceal from other nations, especially if reactors are open to international inspection. The other way is separation of the relatively rare uranium isotope ^{235}U, which, like plutonium, is suitable for use in weapons. The original separation method was gas diffusion, but then the centrifuge method was developed, and other approaches are possible such as laser or electromagnetic separation.

In the gas diffusion method, a chemical containing uranium (uranium hexaflouride) is passed through a porous barrier such as a ceramic wall that has tiny holes in it. Molecules containing ^{235}U travel through the barrier slightly faster than molecules containing ^{238}U. This is a very inefficient process, because the isotopes are very similar to each other, so many passes through a barrier are required to enrich the proportion of ^{235}U sufficiently for use in a nuclear weapon. The other approach uses centrifuges, rapidly spinning rotors containing the uranium hexaflouride to separate the two isotopes on the basis of their slight difference in mass. Both approaches are very difficult and costly, however. Conceivably, nanotechnology could slightly reduce the difficulty, by producing porous barriers with exactly the optimum sized holes and by providing lighter and stronger centrifuge rotors that could operate at higher speeds.

Therefore, without a more careful analysis someone might leap to the conclusion that nanotechnology is a danger because it facilitates proliferation of nuclear weapons. This ignores several crucial facts. First, the world already faces a very severe crisis of nuclear proliferation without nanotechnology. Second, the fundamental requirement for production of nuclear weapons is the availability of uranium, so the most logical preventive would be international monitoring and control over its mining and distribution. Third, there are many other technical requirements for production and delivery of nuclear weapons, and it is the whole collection of them that presents a threat, not any one alone. Fourth, nanotechnology is inherently nonnuclear, because nuclear reactions occur at a smaller scale than the nanoscale, so its connections to proliferation of nuclear weapons will always be highly indirect if they exist at all. Finally, the fundamental problem is not nuclear proliferation, but weapons of mass destruction in general, and nanotechnology has a major role to play in the defense against chemical and biological warfare agents in sensor systems that can detect them before they have caused harm.

Perhaps a very few nano products will need to be "controlled substances," analogous to narcotics, insecticides, asbestos, and antibiotics [38.15]. Conceivably, porous barriers with exactly the right pore size for uranium isotope separation would be controlled in some way. Some products could be produced and used under strict regulations, whereas a few others might be banned altogether. Most would not require restrictions of any kind.

Such decisions would need to be based on the careful analysis of facts related to the specific issue at hand. For example, it may be that no improvements in gas diffusion separation are possible through nanotechnology, or they are so slight as to be negligible. Perhaps technological developments in laser or electromagnetic separation, completely unrelated to nanotechnology, may render both the gas diffusion and centrifuge methods obsolete. Therefore, the mere fact that we can imagine a way in which nanotechnology might possibly encourage the proliferation of nuclear weapons is far too weak a justification for international regulation. We would need to go beyond vague fears to precise analysis based on rigorous scientific research to distinguish real dangers from imaginary ones and design appropriate safeguards in those rare cases when they are necessary.

The costs of excessive regulation would be extremely high, harming the very human beings it was intended to protect. Porous barriers precisely designed at the nanoscale are among the high benefit applications we can anticipate early in the history of nanotechnology. They would have a wide range of applications, from water purification and desalination to separation of valuable substances in biotechnology production processes. Similarly, new high-performance materials with great strength but low weight will have a myriad of applications throughout the civilian sectors of the economy. Among the products that would benefit millions of ordinary people are light but indestructible eyeglass frames, safety helmets, and hand tools.

Nanotechnology has the potential to increase the effectiveness of biotechnology, information technology, and technologies based on cognitive science through NBIC convergence. Therefore, it could become entangled in ethical issues that already involve those other technologies such as the conflict over genetically modified foods, the dispute over information privacy, and the debate over treatment of mental illness. These are not fundamentally nanotechnology issues, however, and it will be important to keep a proper perspective on their real nature.

38.3 Major Socio-technical Trends

The significance of nanotechnology depends not only on its own accomplishments and on convergence with other technologies, but also on how these purely technical developments relate to wider trends going on in the world [38.16, 17]. At present, many of these trends are confused and are the subject of great controversy in the social science and public policy arenas. It is always hazardous to extrapolate trends from any particular moment in history, but the present time appears so chaotic that the events of a single day might send humanity down a very different road.

A few years ago, there was a broad consensus that the rapid growth in the number of people on the planet, the so-called *population explosion*, was the dominant quantitative trend that needed to be factored into any projections [38.18]. But by the mid-1980s, it became obvious that population growth had been replaced by the threat of population decline in most advanced industrial nations, with the possible exception of the United States [38.19, 20]. Even before collapsing fertility begins to reduce the number of people in the affected nations, their average age and pension costs increase, social dynamism and creativity decrease, and governments become gridlocked trying to deal with ultimately insoluble problems of funding demanded services. This is one of the explicit reasons why the United States has begun to discount the influence of its European allies and Japan [38.21, 22].

Although nanotechnology has little obvious direct connection with fertility, there are two potentially counterbalancing, indirect connections. Rapid progress in nanotechnology could revitalize economic expansion and technical creativity, thereby to some extent offsetting the negative consequences of fertility collapse. However, the aversion to change that marks societies having a high proportion of elderly citizens may dampen the intellectual inquisitiveness and investment risk-taking required to develop nanotechnology and technological convergence.

A related trend is the constant improvement in health resulting from progress in medical science and the economic growth needed to fund increasingly costly health care. Continued progress in health is by no means assured, however. During the nineteenth century, American health may actually have declined significantly for a number of decades, despite economic growth [38.23]. We tend to attribute the undeniable improvement in health over the twentieth century to medical progress, but health education and public sanitation may have been more important [38.24]. The U.S. Centers for Disease Control argue that substantial improvements in health and longevity could be achieved by lifestyle changes, notably, exercising more, reducing the fats in our diet, and avoiding smoking [38.25, 26]. The introduction of antibiotics helped increase longevity, and modern cardiology saves the lives of many people who might otherwise die prematurely of heart attacks, but the progress against cancer, AIDS, and most aging-related illnesses has been agonizingly slow. On balance, economists find that the increasing investments in heath care are paying off, but not necessarily in all areas, or with very great benefit [38.27–29].

There are several reasons to be pessimistic about the future benefits of medicine, unless there are very major scientific breakthroughs. We have yet to find a cure for any chronic viral infections, of which AIDS is merely the most publicized example. Bacteria are rapidly evolving resistance to antibiotics, yet the rate of development of new prescription medicines is declining.

The average white American male born in 1900 could expect to live 48 years, but in 2000 this life expectancy had increased to 74 years. For white females, the average life expectancy increased from 51 to 80. Projecting these figures forward at the same rate of increase suggests that life expectancy in 2100 might be 114 for males and 125 for females. However, using more realistic assumptions, the U.S. Census Bureau has projected that life expectancy for Americans born in the year 2100 might be only around 88 for males and 92 for females [38.30]. This does represent progress, but at a steeply declining rate, and it depends upon continued economic growth.

Perhaps the most economically significant technical trend of recent years has been *Moore's Law*, Gordon Moore's observation that the density of transistors on the most advanced microchip doubles about every 18 months. The rapid improvement of computer and communications hardware has been fundamental to the implementation of new software applications, networking, and information technology in general. These, in turn, have been responsible for much economic growth. However, the semiconductor industry is approaching physical limits in the traditional methods of making integrated circuits, including computer chips, so Moore's Law will stall without breakthroughs in nanoscale technologies such as molecular logic gates and carbon nanotube transistors [38.31–33].

Arguably, several of the great thrusts of twentieth-century technology have already stalled. Except for the improved capacity of scientific instruments to collect and process astronomical data, the space program has hardly advanced since the mid-1970s. Civilian aviation and ground transportation have improved only in relatively minor design details since the 1950s. Despite great efforts, little progress has been made in controlling nuclear fusion for power generation. Nuclear fission power generation has largely been halted by public controversies, and no technological breakthroughs in safe operation of reactors or disposal of radioactive wastes have assuaged the public's concerns. The social sciences seem no better able to define good public policies than they were decades ago. Outside of nanotechnology itself, the two main areas where rapid progress obviously continues are information technology and genetic engineering. Convergence with nanotechnology is essential for further progress in both of these areas.

What would happen to the world economy if technological progress slowed or even halted? First, the advanced industrial nations would lose the advantage they currently hold over developing countries. For example, the American semiconductor industry would probably collapse if it lost its technological superiority, because nations with lower wage rates could produce the same things more cheaply. Technological products, from computer chips to pharmaceuticals, would become commodities, manufactured wherever it was cheapest to do so. With their heavy pension burdens and costly social services, governments of advanced nations would face fiscal crises of unprecedented magnitude. Indeed, the economies of these nations could fall rapidly down to the average of all nations, unleashing social discontent that could lead to unpredictable violence.

At the same time, some developing nations would advance economically, which would mean increased net world industrial production with concomitant increase in environmental pollution and resource depletion. Without technological progress to solve these problems, the average human welfare could decline, rather than remaining stable. In order to improve human welfare, technological progress must continue. Perhaps the best way to achieve that is through nanoscience and nanotechnology in convergence with the other NBIC fields, gaining understanding and control at the physical scale that is the basis for most science and technology.

It is impossible to predict how rapidly the conditions in the richest nations would deteriorate, or whether humanity could navigate through these crises to achieve a stable world. But clearly a halt in technological progress would be a shock to the world economy, global political institutions, and human welfare – which it would be wise to avoid.

38.4 Sources of Ethical Behavior

Ethical questions related to nanotechnology are not limited to the ways people might use it to harm others intentionally, but also include obligations to avoid potentially harmful unintended consequences [38.34]. An example of the former might be a weapon and of the latter, a kind of environmental pollution. In either case, the harm might be morally justified, as when a nation employs a weapon to defend against attack, or when limited pollution of the environment is offset by substantial benefits to humanity. Other ethical questions concern harm to the owners of nanotechnology, for example, if a competing company violates a nanotech patent, or if a government bans a nano-related product without careful examination of scientific evidence about its value. News reporters or popular writers who spread false information about nanotechnology may also be acting unethically, whether they are willfully lying or merely failing to be professionally diligent in checking their facts.

It is important to recognize that there are sins of omission as well as commission. To fail to develop a beneficial nanotechnology application could also be unethical. Imagine, for instance, that a laboratory had discovered how nanotechnology could enable a much more effective form of chemotherapy to cure cancer reliably and cheaply, but the company owning the patents prevented it from being developed, because its less effective traditional chemotherapy products were more profitable. This could be considered just as unethical as doing aggressive harm.

For over a century, social scientists have been studying the origins of ethical behavior – or its opposite, unethical behavior – in fields like the social psychology of groups, the sociology of deviance, and criminology. Although it is impossible to predict when a particular person will commit a specific ethical or unethical act, we can identify with good confidence the general factors that steer human behavior in one direction or another. An individual's behavior is determined by a complex of factors, few of which can be measured accurately, and chance seems to play a significant role in human affairs. Thus, the findings of social science tend to be statistical or conditional in nature. This does not render them useless, because one can develop rational laws, government policies, and investment strategies based on probabilities rather than certainties.

The theoretical and empirical scientific literature on the topic is vast, including literally thousands of publications dating back to the 1840s, expressing the views of countless schools of thought, often employing idiosyncratic terminology. For present purposes, we must distill that huge and incoherent intellectual heritage down to its most meaningful essentials. A good start is the following set of four themes, each of which can be expressed as a theory about why people might violate an ethical rule:

1. Learning – A person violates a rule because the person has learned it is rewarding to do so.
2. Strain – A person violates a rule because the person is frustrated in the attempt to fulfill one of the expectations of society.
3. Control – A person violates a rule because the person lacks stable social bonds that might prevent it.
4. Subculture – A person violates a rule because the person belongs to a group or network of other people who encourage violation.

When each of these ideas first appeared in the social-scientific literature, the theory's proponents tended to present it as the complete explanation for deviant behavior, but now we understand that each of these four has merit and the correct explanation is usually a mixture of two or more. We will illustrate each of the theories with hypothetical illustrations, because actual examples may not exist yet.

Learning Theory is sometimes interpreted in economic or "rational choice" terms, as meaning that a person will do whatever he or she perceives it is profitable to do. But human life is not spent entirely in a marketplace where one can compare prices and shop for a good deal. Rather, there are many quite different contexts in which people make decisions. Regardless of whether options can be quantified in dollars, people tend to rely upon their own past experiences in selecting between familiar courses of action [38.35–37].

If the managers of an industrial corporation have learned they can achieve higher profits by ignoring regulations against polluting the environment, and they have not suffered heavy fines from the government for doing so, they will be more likely to pollute in the future. Therefore, a corporation guilty of polluting with conventional technologies is apt to continue with this history of pollution when it adopts new nanotechnologies. This suggests that one way to reduce the likelihood that industrial companies will pollute when they adopt new nanotechnologies is to enact and enforce strong regulations against pollution in general, to make them learn to avoid polluting.

In Strain Theory, a person violates a norm because he or she is frustrated in the attempt to achieve one of the values endorsed by society [38.38, 39]. This idea has been used to explain why many members of poor communities or groups that have been subject to discrimination turn to crime to gain wealth and status, but it can also explain why a major corporation might begin to engage in dubious accounting practices when its growth in real business stalls. The central idea is that an individual or group becomes committed to a particular kind of success that society encourages – whether it is wealth, political power, widespread fame, or honor within a particular sector of society – then experiences frustration in attaining success, which motivates ethical violations.

Conceivably, a nanotechnology corporation could be affected by strain if it has committed itself to a new and untested line of products that turns out to be less effective, more harmful, or more costly than originally estimated. The corporation has committed not only its money and effort, but also its public prestige to success, but success may elude it. It may then unethically advertise its products as more effective than they really are, conceal knowledge of their danger to human health or the environment, and cook its financial records to deceive investors. Of course, many ordinary companies have done this in the past, and, ironically, they sometimes solve their problems before the public becomes aware of them, thereby becoming ethical and successful again (e.g., [38.40]).

When Merton proposed the most influential version of Strain Theory in 1938, he identified three modes of adaptation to three increasing levels of strain. If a person was unable to achieve society's values by following conventional norms, frustration might drive him or her to violate the norms in pursuit of the value, what Merton called *innovation*. If this did not work, he or she might substitute both new values and new norms for those of society, in what he called *rebellion*. But if this failed as well, the person might abandon values, as well as norms and fall into a demoralized state of inaction called *retreatism*. Retreatism is inconsequential, and successful rebellion tends to radicalize society, but innovation (in Merton's sense of the term) can promote scientific and technical progress. In other work, Merton [38.41, 42] was one of the founders of the sociology of science and technology, but he never followed through on the implications of Strain Theory for science, and his distinctive concept of innovation was chiefly used to explain criminal behavior by poor people who violated the law in order to the get the values (i. e., money) endorsed by capitalist society.

There are many examples in the history of science in which Strain Theory can be used to explain scientific and technological innovations that turned out to be beneficial, rather than unethical, and others where the result was a mixture of benefit and harm that presumably could have been managed to emphasize the benefit. In the seventeenth century, England led the world in scientific progress, perhaps in a nationalistic reaction to its inferiority in population and other resources relative to France and Spain [38.43]. In the late nineteenth and early twentieth centuries, Germany lacked access to as abundant a supply of natural resources as had the great colonial powers, Britain and France. This inferiority may have stimulated many advances in German chemistry such as Adolf Bayer's synthesis of indigo dye and the nitrogen fixation method developed by Fritz Haber and Karl Bosch, which allowed Germany to continue producing explosives for World War I after it had lost access to foreign sources of nitrates. When the Treaty of Versailles concluding World War I limited German long-range artillery, the Germans developed the V-2 rocket largely to get around this restriction, thereby ushering in the age of space flight [38.44, 45].

In Control Theory, a person violates norms because he or she lacks stable social bonds that might prevent it [38.46–48]. This is a very successful scientific explanation of many common crimes, such as ordinary theft, and many kinds of criminals tend to lack stable friendships or family relationships that might restrain their deviant behavior. Control Theory might seem irrelevant to nanotechnology ethics because no isolated individual is in a position to make major decisions about new applications. The theory perfectly fits the Hollywood image of Dr. Frankenstein living like a hermit in a remote castle, where he is free to conduct any ghastly experiment he wishes, but no real scientist lives like this.

However, a variant of Control Theory explains that a community or organization can suffer from a partial but pervasive form of isolation, called *social disorganization*, in which communication channels are poor and many people deviate to a moderate degree because they are somewhat detached from each other. In a socially disorganized research laboratory studying the properties of a new nanostructured material, the quality of the science could suffer, pieces of information could fail to get to scientists who need them, and management would get incorrect impressions about the material's properties. This could lead to a chain reaction of unethical behavior in which no one individual was primarily to blame. For instance, the result could be a corporate decision to put into production a new kind of aircraft component that was subject to unpredictable catastrophic failure, causing crashes and loss of life. In a case such as this, the unethical behavior is scattered in many small pieces, committed by many individuals, any time one of them presents a dubious observation as a scientific fact. The best way to reassert the truth-oriented professional norms of science would be to rebuild good channels of communication and cooperation, reattaching the researchers to each other and to the scientific community.

Subculture Theory is similar to Control Theory, but operates on the level of groups rather than individuals. A person violates a rule because he or she belongs to a subculture that rejects the rule and even encourages violation of it [38.49, 50]. A subculture is a group or network having a set of norms, roles, and values that differ from those of the surrounding culture. At the extreme, it can have a radical ideology or dogma, but practically every social group is a subculture to at least a very mild extent. Social psychologist *Janis* [38.51] has shown that even very powerful groups can become deviant subcultures, if they isolate themselves from the wider community, as the Nixon White House did during the Watergate episode.

Even if a research laboratory is functioning properly, the organization of which it is a part can make harmful decisions if the top management is a subculture practicing what Janis calls "groupthink," the refusal to accept information that conflicts with the group's beliefs and commitments. Sometimes this may result in harm to others, for instance, if a new nanotechnology-enabled treatment for cancer were put into production before safe methods for administering it to patients in hospital settings were worked out. Or the harm could fall on the organization itself, for example, if a semiconductor company decided to invest its future in molecular logic gates without fully assessing the potential of carbon nanotube transistors instead. In that case, we might say the company deserves what it gets, but there is the ethical issue of its responsibility to stockholders and employees, including to the scientists in the research laboratory who were ready to do the studies needed for a correct decision.

As the example of Strain Theory illustrates, sometimes strain has positive consequences, rather than negative ones. Similarly, Learning Theory explains why an individual or organization might develop habits of ethical innovation, and both Control Theory and Subculture Theory could show that a person or group may innovate best when somewhat detached from conventional thinking. Thus, the issue is not one of avoiding these four factors, but of finding the right levels of them to encourage healthy innovation without unleashing serious unethical behavior. This is the fundamental trade-off in any free society: How to liberate human creativity while restraining greed, immorality, and inhumanity.

Strain Theory has been used to explain the emergence of collective behavior and social movements [38.52], including reform movements such as the environmental movement or crusades to establish professional codes of ethics. Concern about the social and ethical implications of nanotechnology can, therefore, energize the development of appropriate institutions to manage it wisely. Learning Theory suggests that a rewarding market for beneficial nanotechnology products could teach scientists, engineers, and managers to invest their energy in projects that would serve the needs of humanity. Both Control Theory and Subculture Theory stress the importance of strong networks of communication in restraining unethical behavior. Convergence of nanotechnology with the other NBIC fields would support healthy communication by unifying science, providing a universal technical language for interaction across fields, and creating a network of collaborative relationships across sciences, institutions, and sectors of society.

38.5 Public Opinion

Ethics and social implications are largely matters of social perception, and the public conception of nanotechnology is still in the early stages of developing. Nanoscale science and engineering are evolving from conventional work in materials science, physics, chemistry, and related fields, as the gradual emergence of new methodologies permits many kinds of observation and experimentation with inorganic structures having at least one dimension less than about 100 nm. This progress in *real nanotechnology* is solidly based in existing scientific knowledge, even as it achieves new discoveries and inventions.

At the same time, something quite different has been emerging that also calls itself nanotechnology: a social movement based on metaphors, approximations, and hopes. *Tolles* [38.53] calls it an "irrational vision." In social science, popular enthusiasm for a loosely defined set of unreasonable hopes is often called a *mania* [38.54], so I will call this movement *nanomania*.

The key moment in the emergence of nanomania, but not of nanoscience and nanotechnology themselves, was the 1986 publication of *Engines of Creation* by Drexler. This is a popular book, inspirational rather than technical, filled with verbal metaphors about what might possibly be accomplished if nanoscale assemblers could be created, rather like industrial robot arms and assembly lines. The plausibility of Drexler's argument, such as it is, comes from his constant reminder that biological systems include "machines" that assemble themselves and manufacture or manipulate other nanoscale structures: proteins, RNA, and DNA.

In a rambling discourse that reminds us that Leonardo da Vinci could not have predicted the details of late twentieth century technology, Drexler asserts that some time in the future it will be possible to build nanoscale assemblers that are able to make *anything that can be designed*. At this point he has outstripped his biological analogy, because the "nanomachines" of biology cannot do this; they can make only those specific things that evolution has programmed them to make [38.55]. Drexler says that suitably programmed assemblers will be able to make copies of themselves, as living organisms do.

The specific image he offers is of tiny robot arms grabbing atoms from the surrounding raw material and putting them together in the correct configurations. These imaginary assemblers can make anything, he suggests, so they can quickly replace all the factories and construction companies on Earth, giving humankind perfect abundance of anything we might want. The book then scans quickly through other dreams of science fiction, including artificial intelligence, cheap space flight, near immortality, and the danger to human life of uncontrolled self-replicating intelligent machines.

In some ways the book is laudable, inspiring nontechnical readers with many conceivable applications of nanotechnology, some of which might actually turn out to be practical in the long run, discussing their social implications, and offering potential solutions to problems that might arise. The problem is that many people have come to the unfounded conclusion that Drexler's self-replicating universal assemblers are not only theoretically possible, but likely to be created in the near future. This is the fundamental error of nanomania, and it has called forth a reaction in the form of a *nanophobia* – the fear that all kinds of horrible evils will soon emerge from nanotechnology.

At the 2000 *Societal Implications* workshop, Drexler's assemblers were debunked by several participants, including Nobel prize-winner Smalley, discoverer of fullerenes and a pioneer of carbon nanotubes. *Smalley* observes that technical details of chemistry and a correct understanding of the properties of atoms and molecules are largely absent from nanomania [38.56]. In particular, the universal nanoscale assemblers envisioned by Drexler are physically impossible: "Because the fingers of a manipulator arm must themselves be made out of atoms, they have a certain irreducible size. There just isn't enough room in the nanometer-size reaction region to accommodate all the fingers of all the manipulators necessary to have complete control of the chemistry. . . . Manipulator fingers on the hypothetical self-replicating nanobot are not only too fat; they are also too sticky: the atoms of the manipulator hands will adhere to the atom that is being moved. So it will often be impossible to release this miniscule building block in precisely the right spot" [38.57].

The difficulty of developing reasonable public policies about nanotechnology when popular thinking is dominated by fanciful notions is illustrated by Chen's paper, "The Ethics of Nanotechnology", distributed online both by the Markkula Center for Applied Ethics at Santa Clara University and by BioScience Productions, Inc., which describes itself as "a non-partisan organization whose goal is the promotion of public literacy in the biosciences". Following Drexler's approach, *Chen* takes assumes that nanotechnology means the creation of molecular machines, "which could be used as molecular assemblers and disassemblers to build, repair, or tear down any physical or biological objects" [38.58]. Recognizing that such "nanites" may not be practical in the near future, Chen nonetheless suggests that we consider taking three possible actions soon:

1. Nanotechnology R&D should be banned
2. A nongovernmental regulatory or advisory commission should be set up
3. Adopt design guidelines
   - Nanomachines should only be specialized, not general purpose
   - Nanomachines should not be self-replicating

- Nanomachines should not be made to use an abundant natural compound as fuel
- Nanomachines should be tagged so they can be tracked

Chen notes that the first choice would undesirably prevent beneficial applications of molecular machines, but might not prevent "rogue researchers" from developing nanites anyway. However, readers of his article who are unfamiliar with real nanotechnology may not realize that most research in the field has nothing to do with these hypothetical nanites. It would take considerable wisdom to figure out how a regulatory commission might be set up, empowered, and managed effectively in such a way that it could ensure nanotechnology will be used for human benefit without stifling worthwhile innovations. The design guidelines flow from Chen's assumptions about what nanotechnology is, but any formal regulations embodying them could have serious negative unintended consequences, given that they start with a flawed definition of nanomachines.

Chen's rule that nanomachines be "specialized, not general purpose" may mean little, because a fully "general purpose" machine is as mythical as a "universal solvent" or "perpetual motion machine." However, a regulatory commission could do great harm by adopting poorly conceived definitions of *nanomachine* and *general purpose*. Suppose a very useful new abrasive were developed consisting of nanoparticles that changed shape, perhaps in response to temperature or force fluctuations, in some complex way that helped them do their intended job. *Webster's II New Riverside University Dictionary* defines *machine* thus: "a system, usually of rigid bodies, constructed and connected to change, transmit, and direct applied forces in a predetermined way to accomplish a particular objective, as performance." By this definition, the nanoscale abrasive particles would be machines. If they could be used to shape a wide range of industrial materials, they could be called general purpose. Yet this abrasive could be no more dangerous to humanity than ordinary sandpaper.

Strictly speaking, no entities on Earth are "self-replicating." Living organisms cannot replicate themselves without the help afforded them by the particular environment in which they dwell. All life is part of an ecology. Any regulation prohibiting self-replication would have to define very clearly what *self-replication* meant in the context of particular environments. Today, factory robots build parts of robots, but nobody worries about the ethical implications, perhaps because anybody can see that the manufacture process is entirely under the control of human beings. Because nanites are imaginary, and only vaguely defined, there are no facts to give nontechnical people comparable confidence.

Chen's rule against nanomachines that use "an abundant natural compound as fuel" presumably would prevent a nanite from rampaging uncontrolled in the natural environment. But this could outlaw the development of non-replicating nanoscale devices that can function only in very restricted laboratory or industrial systems, because most chemicals used in motors or batteries are abundant natural compounds.

Requiring that all nanoscale machines be "tagged so that they can be tracked" is reminiscent of the British Red Flag Act of 1865, which required that each horseless carriage be preceded by someone on foot waving a red flag. In the context of Chen's recommendations, *tracked* would seem to mean located, not merely identified once found. This could add an extremely heavy technical burden such as radioactive tagging, addition of a distinctive adulterating chemical, or even complex design features above the nanoscale to allow the nanomachine to be detected by microwave radio locators. If the machines are incapable of escaping into the natural environment, this burden would be not only ill-advised but ludicrous.

Has nanomania distorted the reception real nanotechnology is receiving? A survey done in 1999 found that the American business community was rather unaware of nanotechnology, only 2% saying they knew what it was and a further 2% reporting they had heard of it, but did not know what it was [38.59]. Two years later, a Web-based survey sponsored by the National Geographic Society found that science-attentive members of the general public are very enthusiastic about nanotechnology, and a rather large number of ideas about its benefits have already entered popular culture [38.60]. Statistical analysis of responses from 3,909 people revealed that they associate nanotechnology with other science-based technology, but do not connect it with pseudoscience. Significantly, when 598 people wrote paragraphs about nanotechnology, not a single respondent expressed concern about hypothetical dangers from self-reproducing nanites. Future surveys can examine the deepening popular awareness of nanotechnology, as the field itself progresses, and assess any public concerns that develop.

38.6 A Research Agenda

Sociologist *Etzkowitz* [38.61] has noted that the social sciences can play three different but mutually supportive roles in the development of nanotechnology:

1. Analyzing and contributing to the improvement of the processes of scientific discoveries that increasingly involve organizational issues where the social sciences have a long-term research and knowledge base.
2. Analyzing the effects of nanotechnology, whether positive or negative, expected or unintended, hypothetically and proactively and as they occur in real-time.
3. Evaluation of public and private programs to promote nanoscience and nanotechnology.

There are several ways social scientists can study the nanotechnology innovation process as it occurs [38.11, 62]. Cultural anthropologists and participant observation sociologists can enter nanoscience research teams, ethnographically documenting the behavior of the researchers over time as they frame their scientific problems, seek solutions, and labor collectively to understand the meaning of research results [38.63]. Fruitful sites for research on the innovation process include academe, industry, government laboratories, federal agencies, and professional societies.

Historical methods for collecting and analyzing written documents are also useful, even in cases where the documents are only days or weeks old, rather than the decades-old materials employed by most professional historians. Formal interviews, content analysis of communications such as e-mail messages, and questionnaires can provide more systematic kinds of data.

Application of a scientific idea to a technical problem, a technology transfer, and the introduction of products into the marketplace can be tracked through economic statistics on research and development investments, patent applications, and advertisements for new products and services. Some geographic areas, strata of society, and kinds of individuals and institutions experience technological change earlier than others, notably, the first adopters who try out an innovation before influencing other people to try it as well [38.64, 65]. Start-up companies are in a sense early adopters, even though they are also innovators, and thus they may be an especially fruitful if logistically difficult field for research.

There is a long tradition of systematic research on scientific publication, tracking the introduction of new concepts, charting the changing patterns of citation in scientific literature, and measuring the bulk of publications in different areas [38.66]. The progress of nanotechnology in modern culture could also be studied by tracking the introduction of new topics and courses in school and university curricula, mentions of nanoscale phenomena in the popular press, and the proliferation of both commercial and noncommercial Websites dedicated to nanotechnology. Professional societies and entrepreneurs are already creating series of new forums, symposia, journals, and job fairs oriented toward nanoscience and nanotechnology.

Nanotechnology may have significant impacts in all sectors of the economy, in most spheres of life, and on both short-term and long-term time scales. The intended consequences of any particular innovation can be determined simply by interviewing its investors or promoters and by inspecting their publications about it. Unintended consequences are much harder to study, because they require not only extensive research on the impacts on diverse areas of society, but also good scientific intuition about where to look for them. Consequences have consequences, in a continuing cascade, so the second-order consequences will also have to be studied [38.67]. Ultimately, this would require an extensive, vigorous interdisciplinary scientific community that is dedicated to research on social and technological change in general.

Technology is an elaborate system, embedded in the even more elaborate system that is global society. Through feedback among complex social subsystems, major phenomena can produce chaotic and unpredictable effects. Nanotechnology will have substantial impacts on many aspects of society in often different ways, so predictions of its influence will be difficult to make and evaluate scientifically. This means that researchers will have to invest considerable sophistication and effort in their work.

The social and ethical implications of nanotechnology are the results not merely of what the technology itself does, but also of how people react to it. Therefore, it will be important to understand the social acceptance, resistance, or rejection of nanotechnology at different times and in different places and human contexts. Interviews, focus groups, and questionnaire surveys can measure emotional, cognitive, and psychosocial parameters [38.68]. The combined methodologies of political science, sociology, and socio-legal studies will be required to chart the process of regulatory review and approval, court decisions that actively permit or prohibit the use of the technology, mobilization of political support and opposition, and the activities of relevant social movements.

Ultimately, the test of the various nanotechnologies will be their benefit for human beings, as measured by economic growth, improved health and longevity, environmental protection, strengthened security, social vitality, and enhanced human capabilities. Convergence with other NBIC technologies will complicate the challenge for researchers and policymakers who wish to understand the social and ethical implications of nanotechnology, but it will also magnify the potential benefits to humanity many times over. Success will be most complete and most probable if scientific research on these implications is an integral part of the effort from the very beginning.

References

38.1 B. Joy: Why the future doesn't need us, Wired **8**(4) (April 2000) 238–262

38.2 B.J. Feder: Opposition to nanotechnology, New York Times (August 19 2002) (http://www.nytimes.com/)

38.3 G. H. Reynolds: *Forward to the Future: Nanotechnology and Regulatory Policy* (Pacific Research Institute, San Francisco 2002)

38.4 J. S. Brown, P. Duguid: Don't count society out: A response to Bill Joy. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 37–45

38.5 R. W. Siegel, E. Hu, M. C. Roco (Eds.): *Nanostructure Science and Technology* (Kluwer, Dordrecht 1999)

38.6 M. C. Roco, R. S. Williams, P. Alivisatos (Eds.): *Nanotechnology Research Directions* (Kluwer, Dordrecht 2000)

38.7 M. Roco, R. Tomellini: *Nanotechnology: Revolutionary Opportunities and Societal Implications* (Office for Official Publications of the European Communities, Luxembourg 2002)

38.8 M. S. Meyer: Socio-economic research on nanoscale science and technology: A european overview and illustration. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 278–311

38.9 R. H. Smith: Social, ethical, and legal implications of nanotechnology. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 257–271

38.10 V. Weil: Ethical issues in nanotechnology. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 244–251

38.11 M. C. Roco, W. S. Bainbridge (Eds.): *Societal Implications of Nanoscience and Nanotechnology* (Kluwer, Dordrecht 2001)

38.12 L. B. Lave: Lifecycle/sustainability implications of nanotechnology. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 205–212

38.13 National Research Council: *Small Wonders, Endless Frontiers: A Review of the National Nanotechnology Initiative* (National Academy Press, Washington D.C. 2002)

38.14 M. C. Roco, W. S. Bainbridge (Eds.): *Converging Technologies to Improve Human Performance* (Kluwer, Dordrecht 2003)

38.15 M. C. Suchman: Envisioning life on the nanofrontier. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 271–276

38.16 N. Gingrich: The age of transition. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 29–35

38.17 G. Yonas, S. T. Picraux: National needs drivers for nanotechnology. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 46–55

38.18 P. R. Ehrlich: *The Population Bomb* (Ballantine, New York 1968)

38.19 K. Davis, M. S. Bernstam, R. Ricardo-Campbell (Eds.): *Below-Replacement Fertility in Industrial Societies: Causes, Consequences, Policies (A supplement to Population and Development Review)* 1986)

38.20 B. J. Wattenberg: *The Birth Dearth* (Ballantine, New York 1987)

38.21 Central Intelligence Agency: *Long-Term Global Demographic Trends: Reshaping the Geopolitical Landscape* (Central Intelligence Agency, Washington D.C. 2001)

38.22 Demography and the west, Economist **364**(8287) (August 2002) 20–22

38.23 D. L. Costa, R. H. Steckel: Long-term trends in health, welfare, and economic growth in the United States. In: *Health and Welfare During Industrialization*, ed. by R. H. Steckel, R. Floud (Univ. Chicago Press, Chicago 1997) pp. 47–89

38.24 S. H. Preston: *American Longevity: Past, Present, and Future* (Center for Policy Research, Syracuse University, Syracuse 1996)
38.25 HHS (U.S. Department of Health and Human Services): *Chronic Diseases and Their Risk Factors: The Nation's Leading Causes of Death* (Centers for Disease Control, Atlanta 1999)
38.26 HHS (U.S. Department of Health and Human Services): *Reducing Tobacco Use: A Report of the Surgeon General* (Centers for Disease Control, Atlanta 2000)
38.27 D. M. Cutler, M. McClellan, J. P. Newhouse, D. Remler: Are medical prices declining, Quarterly J. Economics **113** (1998) 991–1024
38.28 D. M. Cutler, E. Richardson: Your money and your life: The value of health care and what affects it. In: *Frontiers in Health Policy Research*, ed. by A. M. Garber (MIT, Cambridge 1999) pp. 99–132
38.29 V. R. Fuchs: The future of health economics, J. Health Economics **19** (2000) 141–157
38.30 F. W. Hollmann, T. J. Mulder, J. E. Kallan: *Methodology and Assumptions for the Population Projections of the United States: 1999 to 2100* (United States Census Bureau, Washington D.C. 2000)
38.31 R. Doering: Social implications of scaling to nanoelectronics. In: *Social Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 84–93
38.32 R. S. Williams, P. J. Kuekes: W've only just began. In: *Social Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 103–108
38.33 Central Intelligence Agency: *Experts See Risks to US IT Superiority Beyond Moore's Law*, report OTI IA 2002-151 (Central Intelligence Agency, Directorate of Intelligence, Washington D.C. 2002) pp. 2002–151
38.34 E. Tenner: Nanotechnology and unintended consequences. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 311–318
38.35 G. C. Homans: *Social Behavior: Its Elementary Forms* (Harcourt Brace Jovanovich, New York 1974)
38.36 R. L. Akers: *Deviant Behavior: A Social Learning Approach* (Wadsworth, Belmont 1985)
38.37 R. Stark, W. S. Bainbridge: *A Theory of Religion* (Rutgers University Press, New Brunswick 1987)
38.38 R. K. Merton: *Social structure and anomie* (Free Press, New York 1968) pp. 185–214, first published 1938
38.39 R. A. Cloward, L. E. Ohlin: *Delinquency and Opportunity* (Free Press, New York 1960)
38.40 A. P. Sloan: *My Years with General Motors* (Doubleday, Garden City 1964)
38.41 R. K. Merton: *Science, Technology and Society in Seventeenth Century England* (H. Fertig, New York 1970)
38.42 R. K. Merton: *The Sociology of Science: Theoretical and Empirical Investigations* (University of Chicago Press, Chicago 1973)
38.43 L. Greenfeld: *Nationalism: Five Roads to Modernity* (Harvard Univ. Press, Cambridge 1992)
38.44 W. S. Bainbridge: *The Spaceflight Revolution* (Wiley, New York 1976)
38.45 W. S. Bainbridge: *Goals in Space: American Values and the Future of Technology* (State Univ. New York Press, Albany 1991)
38.46 T. Hirschi: *Causes of Delinquency* (University of California Press, Berkeley 1969)
38.47 C. Shaw, H. D. McKay: *Delinquency Areas* (University of Chicago Press, Chicago 1929)
38.48 M. R. Gottfredson, T. Hirschi: *A General Theory of Crime* (Stanford Univ. Press, Stanford 1990)
38.49 E. H. Sutherland: *Principles of Criminology* (Lippincott, Philadelphia 1947)
38.50 G. Sykes, D. Matza: Techniques of neutralization: A theory of delinquency, Am. Sociol. Rev. **22** (1957) 664–670
38.51 I. L. Janis: *Groupthink: Psychological Studies of Policy Decisions and Fiascoes* (Houghton Mifflin, Boston 1982)
38.52 N. J. Smelser: *Theory of Collective Behavior* (Free Press, New York 1962)
38.53 W. M. Tolles: National security aspects of nanotechnology. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 218–237
38.54 W. S. Bainbridge: Collective behavior and social movements. In: *Sociology*, ed. by R. Stark (Wadsworth, Belmont 1985) pp. 493–523
38.55 V. Vogel: Societal impacts of nanotechnology in education and medicine. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 180–186
38.56 R. F. Service: Is nanotechnology dangerous?, Science **290** (2000) 1526–1527
38.57 R. E. Smalley: Of chemistry, love and nanobots, Sci. Am. **285** (2001) 76–77
38.58 A. Chen: *The Ethics of Nanotechnology* (BioScience Productions and Markkula Center for Applied Ethics, Santa Clara University, 2002) www.actionbioscience.org/newfrontiers/chen.html and www.scu.edu/ethics/publications/submitted/chen/nanotechnology.html
38.59 J. Canton: The strategic impact of nanotechnology on the future of business and economics. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 114–121
38.60 W. S. Bainbridge: Public attitudes toward nanotechnology, J. Nanopart. Res. **4** (2002) 561–570

38.61 H. Etzkowitz: Nano-science and society: Finding a social basis for science policy. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 121–128

38.62 J. S. Carroll: Social science research methods for assessing societal implications of nanotechnology. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 238–244

38.63 B. A. Nardi: A cultural ecology of nanotechnology. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 318–324

38.64 E. Katz, P. F. Lazarsfeld: *Personal Influence* (Free Press, Glencoe 1955)

38.65 E. M. Rogers: *Social Change in Rural Society* (Appleton-Century-Crofts, New York 1960)

38.66 D. Crane: *Invisible Colleges: Diffusion of Knowledge in Scientific Communities* (University of Chicago Press, Chicago 1972)

38.67 R. A. Bauer: *Second-Order Consequences: A Methodological Essay on the Impact of Technology* (MIT, Cambridge 1969)

38.68 P. B. Thompson: Social acceptance of nanotechnology. In: *Societal Implications of Nanoscience and Nanotechnology*, ed. by M. C. Roco, W. S. Bainbridge (Kluwer, Dordrecht 2001) pp. 251–256

Acknowledgements

4 Nanowires

by Mildred S. Dresselhaus, Yu-Ming Lin, Oded Rabin, Marcie R. Black, Gene Dresselhaus

The authors gratefully acknowledge the stimulating discussions with Professors Charles Lieber, Gang Chen, S. T. Lee, Arun Majumdar, Peidong Yang, and Jean-Paul Issi, Dr. Joseph Heremans, and Ted Harman. The authors are grateful for support for this work by the ONR Grant #000140-21-0865, the MURI program subcontract PO #0205-G-7A114-01 through UCLA, and DARPA contract #N66001-00-1-8603.

6 Stamping Techniques for Micro and Nanofabrication: Methods and Applications

by John A. Rogers

The author extends his deepest thanks to all of the collaborators who contributed the work described here.

8 MEMS/NEMS Devices and Applications

by Darrin J. Young, Christian A. Zorman, Mehran Mehregany

The authors wish to thank Wen H. Ko for the helpful discussions and suggestions and Michael Suster and Joseph Seeger for preparing the figures.

10 Therapeutic Nanodevices

by Stephen C. Lee, Mark Ruegsegger, Philip D. Barnes, Bryan R. Smith, Mauro Ferrari

The authors gratefully acknowledge many friends and colleagues whose input helped shape this article. Particularly, we acknowledge Beth S. Lee for many, many helpful discussions and for unflagging support. We also acknowledge Phil Streeter for many of the same services, performed in the office of friend rather than spouse. We acknowledge the support services of Anita Bratcher in manuscript preparation and the artistic stylings of Vladimir Marukhlenko for the figures incorporated in the manuscript. We also acknowledge Carol Bozarth for her kind and spontaneous support of the physical process of manuscript editing. This work is dedicated to the memories of Mildred A. Lee, Antonio Ferrari and Marialuisa Ferrari and the multitude of others whose lives have been tragically shortened by cancer, with the determination that therapeutic nanotechnology be used to help abolish the terrible power of the disease over human life.

13 Noncontact Atomic Force Microscopy and Its Related Topics

by Seizo Morita, Franz J. Giessibl, Yasuhiro Sugawara, Hirotaka Hosoi, Koichi Mukasa, Akira Sasahara, Hiroshi Onishi

Thanks to Tom Albrecht, Alexis Baratoff, Hartmut Bielefeldt, Gerd Binnig, Dominik Brändlin, Peter van Dongen, Urs Dürig, Christoph Gerber, Stefan Hembacher, Markus Herz, Lukas Howald, Christian Laschinger, Ulrich Mair, Jochen Mannhart, Thomas Ottenthal, Calvin Quate, Marco Tortonese, and the BMBF for funding under project no. 13N6918.

18 Surface Forces and Nanorheology of Molecularly Thin Films

by Marina Ruths, Alan D. Berman, Jacob N. Israelachvili

This work was supported by ONR grant N00014-00-1–0214. M. R. Luths thanks the Academy of Finland for financial support.

19 Scanning Probe Studies of Nano-scale Adhesion Between Solids in the Presence of Liquids and Monolayer Films

by Robert W. Carpick, James D. Batteas

We gratefully acknowledge the help of Ms. Erin Flater, who provided valuable assistance and insights into the literature on capillary formation. RWC acknowledges support of a career award from the National Science Foundation, grant #CMS-0134571.

24 Mechanics of Biological Nanotechnology

by Rob Phillips, Prashant K. Purohit, Jané Kondev

We happily acknowledge useful discussions with Kai Zinn, Jon Widom, Bill Gelbart, Andy Spakowitz, Zhen-Gang Wang, Ken Dill, Carlos Bustamante, Tom Powers, Larry Friedman, Jack Johnson, Pamela Bjorkman, Paul Wiggins, Steve Williams, Wayne Falk, Adrian Parsegian, Alasdair Steven and Steve Quake. RP and PP acknowledge support of the NSF through grant number 9971922, the NSF supported CIMMS center, and the support of the Keck Foundation. JK is supported by the NSF under grant number DMR-9984471 and is a Cottrell Scholar of Research Corporation.

30 Nanotechnology for Data Storage Applications

by Dror Sarid, Brendan McCarthy, Ghassan E. Jabbour

The authors would like to thank Digital Instruments (Veeco) for contributing their Multi-Mode Nanoscope III, the Department of Energy (DE-FG-3-02ER46013/A001) for a generous grant, EMC for their generous gift, and the Vice President for Research, University of Arizona, for equipment support.

31 The "Millipede" – A Nanotechnology-Based AFM Data-Storage System

by Gerd K. Binnig, G. Cherubini, M. Despont, Urs T. Duerig, Evangelos Eleftheriou, H. Pozidis, Peter Vettiger

It is our pleasure to acknowledge our colleagues T. Albrecht, T. Antonakopoulos, P. Bächtold, A. Dholakia, U. Drechsler, B. Gotsmann, W. Häberle, D. Jubin, M. A. Lantz, T. Loeliger, H. E. Rothuizen, R. Stutz, and D. Wiesmann for their invaluable contributions to the millipede project.

In addition, thanks and appreciation go to H. Rohrer for his contribution to the initial millipede vision and concept and to our former collaborators, J. Brugger, now at the Swiss Federal Institute of Technology, Lausanne (Switzerland), M. I. Lutwyche, now at Seagate, Pittsburg, IL, and W. P. King, now at Georgia Tech, Atlanta, GA, as well as to K. Goodson, T. W. Kenny, and C. F. Quate of Stanford University, CA.

We are also pleased to acknowledge stimulating discussions with and encouraging support from our colleagues W. Bux and P. F. Seidler of the IBM Zurich Research Laboratory, J. Mamin, D. Rugar, and B. D. Terris of the IBM Almaden Research Center, San Jose, CA, and G. Hefferon of IBM, East Fishkill, NY.

Special thanks go to J. Frommer, C. Hawker, J. Mamin, and R. Miller of the IBM Almaden Research Center for their enthusiastic support in identifying and synthesizing alternative polymer media materials, and to H. Dang, A. Sharma, and S. Sri-Jayantha of the IBM T. J. Watson Research Center, Yorktown Heights, NY, for their contributions to the work on servo control.

35 Thermo- and Electromechanics of Thin-Film Microstructures

by Martin L. Dunn, Shawn J. Cunningham

We are most grateful for the assistance of Ms. Yanhang Zhang, a Ph.D. student at the University of Colorado, for her help with the preparation of figures. Many of the calculations and measurements also draw from her work. MLD acknowledges support from DARPA, Sandia National Laboratories, and the AFOSR for support of aspects of his research that appear in this work.

About the Authors

Chong H. Ahn

University of Cincinnati
Department of Electrical
and Computer Engineering
and Computer Science
Cincinnati, OH, USA
chong.ahn@uc.edu
http://www.BioMEMS.uc.edu/

Dr. Chong Ahn is a Professor of Electrical and Computer Engineering at the University of Cincinnati. He obtained his Ph.D. degree in Electrical Engineering from the Georgia Institute of Technology in 1993 and then worked as a postdoctoral fellow at IBM T.J. Watson Research Center. His research interests include all aspects of design, fabrication, and characterization of magnetic MEMS devices, microfluidic devices, protein chips, lab-on-a-chips, nano biosensors, point-of-care testing and BioMEMS systems. He is an associate editor of the IEEE Sensors Journal.

Boris Anczykowski

nanoAnalytics GmbH
Münster, Germany
anczykowski@nanoanalytics.com
http://www.nanoanalytics.com

Dr. Boris Anczykowski is a physicist with an extensive research background in the field of dynamic Scanning Force Microscopy. He co-invented the Q-Control technique and received the Innovation Award Münsterland for Science and Economy in 2001 for this achievement. He is a managing director and co-founder of nanoAnalytics GmbH, a company specialized in the characterization of surfaces and interfaces on the micro- and nanometer scale.

Massood Z. Atashbar

Western Michigan University
Department of Electrical
and Computer Engineering
Kalamazoo, MI, USA
massood.atashbar@wmich.edu
http://homepages.wmich.edu/~zandim

Professor Atashbar's main area of research is nanotechnology and wireless sensors. He has been working in the field of micro/nanosensors for chemical and physical sensing specifically integrated smart wireless surface acoustic wave sensors and systems. He is a senior member of IEEE and an associate editor of the International Journal of Modelling and Simulation

Wolfgang Bacsa

Université Paul Sabatier
Laboratoire de Physique des Solides (LPST)
Toulouse, France
bacsa@lpst.ups-tlse.fr
http://www.lpst.ups-tlse.fr/users/
wolfgang/

Wolfgang Bacsa is an expert in the emerging field of Nano-Optics and Carbon Nanotubes. He has a Ph.D. from the Swiss Federal Institute of Technology (ETH) Zurich in Physics and has extensive experience in condensed matter physics, optics, microscopy, synthesis of ultra-thin films and nanostructured carbon. Professor Bacsa worked at the ETH Zürich, PennState Universiy and EPFL Lausanne.

William Sims Bainbridge

National Science Foundation
Division of Information
and Intelligent Systems
Arlington, VA, USA
wbainbri@nsf.gov
http://mysite.verizon.net/william.
bainbridge

William Sims Bainbridge earned his Ph.D. in Sociology from Harvard University in 1975 and is the author of 10 books, 4 textbook-software packages, and about 150 shorter publications in information science, social science of technology, and the sociology of culture. He has represented the social and behavioral sciences on five US government advanced technology initiatives: High Performance Computing and Communications, Knowledge and Distributed Intelligence, Digital Libraries, Information Technology Research, and Nanotechnology.

Antonio Baldi

Institut de Microelectronica
de Barcelona (IMB)
Centro National Microelectrónica
(CNM-CSIC)
Barcelona, Spain
Antoni.baldi@cnm.es

Antonio Baldi received his PhD from the Universitat Autonoma de Barcelona, Spain, in 2001. He is a postdoctoral fellow at the University of Minnesota. His current research is focused on the fabrication and testing of bioMEMS, on the development of new sensors and microfluidic devices incorporating stimuli-sensitive hydrogels and on the development of inductively coupled wireless MEMS.

Philip D. Barnes

Ohio State University
Biomedical Engineering Center
Columbus, OH, USA
d_skill@yahoo.com

Phillip D. Barnes is a graduate student at the Biomedical Engineering Center at the Ohio State University. His background is in electrical engineering and his current interests are in sensors and imaging devices.

James D. Batteas

National Institute
of Standards and Technology
Surface and Microanalysis Science
Division
Gaithersburg, MD, USA
james.batteas@nist.gov
http://www.cstl.nist.gov/div837/837.03/

Dr. James D. Batteas is a research chemist in the Surface and Interface Research Group of the National Institute of Standards and Technology. The group's current research involves developing and charcterizing the organization and properties of nanoscale materials and devices on surfaces, this includes nanoparticles for use in optoelectric and optomagnetic gating, molecular electronics, and sensors. His group is also investigating friction, adhesion and wear mechanisms on the nanoscale.

Roland Bennewitz

McGill University
Physics Department
Montreal, QC, Canada
roland@physics.mcgill.ca

Roland Bennewitz studied physics in Freiburg and Berlin where he received his PhD for work on defects at surfaces of insulators. He is now assistant at the University of Basel where his research activities focus on high-resolution force microscopy as a tool in nanotribology and surface science.

Alan D. Berman

Monitor Venture Enterprises
Los Angeles, CA, USA
alan.berman.2001@anderson.ucla.edu

Alan Berman received his Ph.D. from the Chemical Engineering Department at the University of California, Santa Barbara. He is involved in technology commercialisation, assisting large technology companies to maximize return on R&D investments by finding and developing applications for their intellectual property outside of their core business. Value is realized through technology licensing, joint ventures and venture capital funded new entities. Technical interests are in fields of tribology, MEMS, and nanotechnology.

Bharat Bhushan

The Ohio State University
Nanotribology Laboratory
for Information Storage
and MEMS/NEMS
Columbus, OH, USA
bhushan.2@osu.edu

Dr. Bharat Bhushan is an Ohio Eminent Scholar and The Howard D. Winbigler Professor in the Department of Mechanical Engineering, a Graduate Research Faculty Advisor in the Department of Materials Science & Engineering, and the Director of the Nanotribology Laboratory for Information Storage & MEMS/NEMS (NLIM) at the Ohio State University, Columbus, Ohio. He holds two M.S., a Ph.D. in mechanical engineering/mechanics, an MBA, and three semi-honorary and honorary doctorates. His research interests are in micro/nanotribology and its applications to magnetic storage devices and MEMS/NEMS (Nanotechnology). He has authored 5 technical books, 45 handbook chapters, more than 450 technical papers in referred journals, and more than 60 technical reports, edited more than 25 books, and holds 14 U.S. patents.

Gerd K. Binnig

IBM Zurich Research Laboratory
Micro-/Nanomechanics
Rüschlikon, Switzerland
gbi@zurich.ibm.com

Gerd Binnig obtained his Ph.D. from the Johann Wolfgang Goethe University, Frankfurt, Germany, and joined IBM Research in 1978. He was corecipient of the 1986 Nobel Prize in Physics for the invention of the scanning tunnelling microscope, and he also invented the atomic force microscope. His current research interests are micro- and nanosystem techniques and "Fractal Darwinism", a theory he developed to describe complex systems.

Marcie R. Black

Massachusetts Institute
of Technology
Department of Electrical Engineering and
Computer Science
Cambridge, MA, USA
marcie@alum.mit.edu
http://web.mit.edu/mrb/www/prof.html

Marcie Black recently received her Ph.D. from Prof. Dresselhaus's research group at MIT studying the optical properties of nanowires. In particular, she identified the dominant optical absorption mechanism in the IR of bismuth nanowires as an indirect interband transition that is enhanced over bulk bismuth. Currently she is studying organic opto-electronics with an emphasis on photovoltaics.

Jean-Marc Broto

University Toulouse III
Laboratoire National des Champs
Magnétiques Pulsés (LNCMP)
Toulouse, France
broto@insa-tlse.fr
http://www.insa-tlse.fr/

Jean-Marc Broto is Professor at the Universite Toulouse III, France. He is a specialist in electronic transport and magnetization properties under high magnetic fields and contributed to the discovery of the Giant Magnetoresistance in 1988.

Robert W. Carpick

University of Wisconsin-Madison
Department of Engineering Physics
Madison, WI, USA
carpick@engr.wisc.edu
http://www.engr.wisc.edu/ep/faculty/
carpick_robert.html

Robert Carpick has a Ph.D. in Physics (1997) from the University of California at Berkeley. He has been an Assistant Professor at the University of Wisconsin-Madison since 2000. He carries out research and publishes in the areas of nanotribology, nanomechanics, nanostructured materials, and scanning probe development. He serves on the editorial board of Review of Scientific Instruments. In 2002 he received a Faculty Early Career Development award from the U.S. National Science Foundation.

Tsung-Lin Chen

National Chiao Tung University
Department
of Mechanical Engineering
Shin Chu, Taiwan
tsunglin@mail.nctu.edu.tw

Tsung-Lin Chen received his B.S. and M.A. degrees in mechanical engineering from the National Tsing-Hua University, Taiwan in 1990 and 1992, respectively. He received Ph.D. degree in mechanical engineering from University of California at Berkeley, USA in 2001. He is currently an assistant professor in National Chiao Tung University in Taiwan. His research interests include MEMS devices design and MEMS fabrication process development.

Yu-Ting Cheng

National Chiao Tung University
Department
of Electronics Engineering
& Institute of Electronics
HsinChu, Taiwan
ytcheng@faculty.nctu.edu.tw

Yu-Ting Cheng received his Ph.D. degree in Electrical Engineering at the University of Michigan, Ann Arbor, in 2000. After his graduation, he worked for IBM Watson Research Center, Yorktown Heights, as a research staff member. He is a member of IEEE, IOP, and Phi Tau Phi. Currently he is Assistant Professor at the National Chiao Tung University, Taiwan. His research interests include the development of novel materials and fabrication technologies for MEMS/NEMS applications and microsystems integration.

Giovanni Cherubini

IBM Zurich Research Laboratory
Storage Technologies
Rüschlikon, Switzerland
cbi@zurich.ibm.com

Dr. Giovanni Cherubini received a Ph.D. degree in electrical engineering from the University of California, San Diego, in 1986, and joined IBM Research in 1987. His interests include high-speed data transmission and data storage systems. He is Editor for CDMA systems, for IEEE Transactions on Communications, and served as Guest Editor for the IEEE Journal on Selected Areas in Communications issues on access technologies (1995) and on multiuser detection techniques (2001–2002). He is co-author of the book Algorithms for Communications Systems and their Applications.

Jin-Woo Choi

Louisiana State University
Department of Electrical
and Computer Engineering
Baton Rouge, LA, USA
choi@ece.lsu.edu

Jin-Woo Choi received his B.S. and M.S. degree in Electrical Engineering from Seoul National University in Korea in 1994 and 1996, respectively. He received his Ph.D. degree in Electrical Engineering from the University of Cincinnati in 2000. Now he is an Assistant Professor at Louisiana State University, Baton Rouge, Louisiana. His current research activities include magnetic particle separators, microfluidic systems for biochemical detection, micro total analysis systems (μ-TAS), bioelectronics, and BioMEMS components and systems.

Shawn J. Cunningham

WiSpry, Inc.
Colorado Springs Design Center
Colorado Springs, CO, USA
shawn.cunningham@wispry.com

Shawn Cunningham is working on the development of RF MEMS switch and associated processes with wiSpry, Inc. His interests include materials characterization, reliability, and Design for MEMS Manufacturability. Prior to joining wiSpry, Shawn pursued MEMS research and product development at Coventor, Ford Microelectronics, and the University of Utah's Center for Engineering Design and in collaboration with the Univerisity of Colorado.

Michel Despont

IBM Zurich Research Laboratory
Micro-/Nanomechanics
Rüschlikon, Switzerland
dpt@zurich.ibm.com

Michel Despont received his Ph.D. in physics from the University of Neuchâtel, Switzerland, in 1996. After a postdoctoral fellowship at IBM's Zurich Research Laboratory, he was visiting scientist at the Seiko Instrument Research Laboratory in Japan in 1997. His current research at IBM focuses on the development of micro- and nanomechanical devices and of processes to fabricate so-called system-on-chip.

Gene Dresselhaus

Massachusetts Institute
of Technology
Francis Bitter Magnet Laboratory
Cambridge, MA, USA
gene@mgm.mit.edu
http://web.mit.edu/fbml/cmr/



Gene Dresselhaus received his Ph.D. in physics from the University of California in 1955. He was a faculty member at the University of Chicago, and assistant professor at Cornell before joining MIT Lincoln Laboratory in 1960 as a staff member. In 1976 he assumed his current position at the MIT Francis Bitter Magnet Laboratory. His area of interest is the electronic structure of nanomaterials and he has co-authored with M.S. Dresselhaus several books on fullerenes, nanowires, and nanotubes.

Mildred S. Dresselhaus

Massachusetts Institute
of Technology
Department
of Electrical Engineering
and Computer Science
and Department of Physics
Cambridge, MA, USA
millie@mgm.mit.edu
http://www.eecs.mit.edu/faculty/index.html

Mildred Dresselhaus received her Ph.D. in physics from the University of Chicago in 1958. She joined the MIT faculty in 1967. She has been active in research across broad areas of solid state physics, especially in carbon science. Her present research activities focus on carbon nanotubes, bismuth nanowires, low dimensional thermoelectricity, and novel forms of carbon. She is the recipient of the National Medal of Science and 17 honorary degrees.

Martin L. Dunn

University of Colorado at Boulder
Department of Mechanical Engineering
Boulder, CO, USA
martin.dunn@colorado.edu

Martin L. Dunn received the Ph.D. in Mechanical Engineering from the University of Washington and was a postdoctoral appointee at Sandia National Laboratories. His research focuses on the micromechanical behavior of materials and structures. He has published over 75 articles in archival journals, and his research has been sponsored by NSF, DOE, NIST, DARPA, AFOSR, and Sandia National Laboratories.

Urs T. Dürig

IBM Zurich Research Laboratory
Micro-/Nanomechanics
Rüschlikon, Switzerland
drg@zurich.ibm.com

Urs Dürig received a Ph.D. degree from the Swiss Federal Institute of Technology, Zurich, in 1984. He joined IBM as a post-doc working on near-field optical microscopy. He is Research Staff Member since 1986: He worked in the field of scanning tunnelling and dynamic force microscopy. In 1997, he joined the Micro/Nanomechanics group focusing on polymer material issues and thermal modelling.

Evangelos Eleftheriou

IBM Zurich Research Laboratory
Storage Technologies
Rüschlikon, Switzerland
ele@zurich.ibm.com

He received a Ph.D. in Electrical Engineering from Carleton University, Ottawa, Canada, in 1985, and joined IBM Research in 1986. His research focuses on signal processing and coding for recording and transmission systems. His current research interests include nanotechnology, in particular probe-storage techniques.
Dr. Eleftheriou was elected IEEE Fellow in 2002.

Mauro Ferrari

Ohio State University
Biomedical Engineering Center
Columbus, OH, USA
Ferrari.5@osu.edu
http://bmew.bme.ohio- state.edu/
bmeweb3/bme_faculty.htm

Mauro Ferrari is the Edgar Hendrickson Professor of Biomedical Engineering of the Ohio State University. A mechanical engineer by training, he also holds appointments in Internal Medicine, Mechanical Engineering and Materials Science. Professor Ferrari is a globally recognized figure in biomedical nanotechnology and micro and nanofabrication. His current interests are application of novel fabrication technologies to innovative drug delivery devices for treatment of cardiovascular disease, palliative care and oncology.

Emmanuel Flahaut

Université Paul Sabatier
CIRIMAT (Centre Interuniversitaire
de Recherche et d'Ingénierie
des Matériaux)
Toulouse, France
flahaut@chimie.ups-tlse.fr
http://eflahaut.nano.free.fr

Emmanuel Flahaut obtained his Ph.D in Materials Science in Toulouse working on CCVD synthesis of carbon nanotubes (CNTs) and dense ceramic-based composites including CNTs. He spent then more than one year as a post-doctoral researcher in Malcolm Green's Group in Oxford to work mainly on the filling of CNTs. He is now a permanent CNRS researcher at the University of Toulouse.

Lásló Forró

Swiss Federal Institute
of Technology (EPFL)
Institute of Physics
of Complex Matter
Lausanne, Switzerland
laszlo.forro@epfl.ch
http://nanotubes.epfl.ch

Professor László Forró is working on the synthesis, physical properties and manipulation of carbon nanostuctures and nanostuctured arrays, as well as, mechanical properties of carbon nanotubes, carbon onions, biological tubular systems. Transport and electron spin resonance studies of molecular materials, quasi-one-dimensional organic metals, organic superconductors, cuprates, manganates and fullerenes – up to high pressures. Tunneling spectroscopy in cuprate and fullerene superconductors. Optical properties of strongly correlated systems and biomaterials.

Jane Frommer

IBM Almaden Research Center
Department of Science
and Technology
San Jose, CA, USA
frommer@Almaden.ibm.com

Following a Ph.D. in Organometallic Chemistry from Caltech, Dr. Jane Frommer has been involved in a diverse set of research areas, including electronically conducting polymers and scanning probe microscopy. Her present AFM lab at IBM collaborates with a wide variety of laboratories involved in materials research, including lithography, chromatography, and storage. Common to all these studies is Frommer's interest in the properties and structure of molecules in confined geometries.

Harald Fuchs

Universität Münster
Physikalisches Institut
Münster, Germany
fuchsh@uni-muenster.de
http://www.uni-muenster.de/Physik/PI/Fuchs

1984 Ph.D. Universität des Saarlandes with Prof. H. Prof Gleiter (nano crystalline Systems), 1984–1985, Post doc with IBM Research Lab. Zurich in the group of G. Binnig and H. Rohrer, 1985–1993 Project manager 'Ultrathin Organic Films' with BASF AG, Ludwigshafen, Germany. Since 1993 he is full Professor and Director at the Physical Institute of the University of Münster, 2000: Cofounder and Scientific Director of the Center for Nanotechnology (CeNTech).

Franz J. Giessibl

Universität Augsburg
Lehrstuhl für Experimentalphysik VI
Augsburg, Germany
franz.giessibl@physik.uni-augsburg.de
http://www.physik.uni-augsburg.de/exp6/

Dr. Giessibl is working in atomic force microscopy and scanning tunnelling microscopy in ultrahigh vacuum at room temperature and low temperatures. He is a Steering Committee Member of the International Conference on Noncontact Atomic Force Microscopy. He received the R&D 100 Award Chicago 1994, the German Nanoscience Award 2000, and the Rudolf Kaiser Price in 2001.

Enrico Gnecco



University of Basel
Department of Physics
Basel, Switzerland
Enrico.Gnecco@unibas.ch
http://monet.physik.unibas.ch/~gnecco/

Enrico Gnecco studied physics in Genoa, where he received his PhD for work on the mechanism of growth of nanostructured carbon films. He is now assistant at the University of Basel, where his research activities focus on friction force microscopy and molecular machinery.

Gérard Gremaud

Swiss Federal Institute
of Technology (EPFL)
Institute of Physics
of Complex Matter
Lausanne, Switzerland
gremaud@epfl.ch

Dr. Gérard Gremaud is a physicist and senior lecturer at the Ecole Polytechnique Fédérale de Lausanne (EPFL). He is active in the research fields of dislocation dynamic, acoustic and atomic force microscopy and granular physics. He is also responsible for the teaching of metrology and practical works to the physics students.

Jason H. Hafner

Rice University
Department of Physics
& Astronomy
Houston, TX, USA
hafner@rice.edu
http://www.ruf.rice.edu/~hafner

Jason Hafner earned his Ph.D. in physics from Rice University in 1998. He then held an NIH postdoctoral fellowship at Harvard University working on nanotube probes for high resolution biological atomic force microscopy. In 2001 he returned to Rice as an assistant professor where his group is pursuing various biophysical applications of scanned probe microscopy and nanomaterials. Dr. Hafner received a Beckman Young Investigator award in 2002.

Stefan Hengsberger



University of Applied Science
of Fribourg
Fribourg, Switzerland
stefan.hengsberger@eif.ch
http://www.anwalt-homburg.de/Stefan-index.htm

Stefan Hengsberger received his diploma in physics from the University of Saarbrücken in 1997. He started as a research scientist at Fraunhofer/Miami (Florida) where he worked until mai 1998. In July 1998 he joined the swiss federal institute of Technology (EPFL) where he earned his PhD in biomechanics in spring 2002. He stayed for another year at EPFL as a postdoc in biomechanics and physics until summer 2003. Since October 2003 he is Professor of Physics at the University of Applied Science in Fribourg, Switzerland.

Peter Hinterdorfer

Johannes Kepler University of Linz
Institute for Biophysics
Linz, Austria
peter.hinterdorfer@jku.at
http://at22.bphys.uni-linz.ac.at/bioph/staf/hipe/hipe.htm

Peter Hinterdorfer earned a Dr. tech. from the University of Linz, Austria, Institute for Biophysics in 1992. He was a postdoctoral fellow at the University of Virginia, Department of Molecular Physiology and Biological Physics (1992/1993). Since then he is at the University of Linz, Institute for Biophysics, where he holds a position as Associate Professor. His current and ongoing research includes single molecule force spectroscopy and high resolution topography and recognition imaging of biological samples.

Roberto Horowitz

University of California at Berkeley
Department
of Mechanical Engineering
Berkeley, CA, USA
horowitz@me.berkeley.edu
http://www.me.berkeley.edu/~horowitz

Roberto Horowitz joined the Department of Mechanical Engineering at the University of California at Berkeley in 1982, where he is currently a Professor. Dr. Horowitz teaches and conducts research in the areas of adaptive, learning, nonlinear and optimal control, with applications to Micro-Electromechanical Systems (MEMS), computer disk file systems, robotics, mechatronics and intelligent vehicle and highway systems (IVHS).

Hirotaka Hosoi

Japan Science and Technology
Corporation
Sapporo, Japan
hosoi@sapporo.jst-plaza.jp

Hirotaka Hosoi received the D.E. degree in electronic enginnering from Hokkaido University in 1999. Since 2002 he is at Innovation Plaza Hokkaido, Japan Science and Technology Corporation (JST). His main research focus is in high-resolution magnetic imaging of magnetic materials surfaces using a scanning force microscope. His current research interests includes magnetism on metal-oxide surfaces.

Jacob N. Israelachvili

University of California
Department of Chemical Engineering and
Materials Department
Santa Barbara, CA, USA
Jacob@engineering.ucsb.edu
http://www.chemengr.ucsb.edu/people/faculty/israelachvili

Jacob Israelachvili earned his Ph.D. 1971 at the Cavendish Laboratory, University of Cambridge, UK. He held various positions at the Department of Applied Mathematics at the Australian National University (1974–1986), including those of Professional Fellow and Head of Department. In 1986 he joined the faculty at University of California, Santa Barbara as Professor in the Department of Chemical Engineering and Materials Department. In 1988 he was elected a Fellow of the Royal Society of London, and in 1991 he was awarded the Alpha Chi Sigma Award for Chemical Engineering Research by the AIChE. He was elected as a foreign associate of the US National Academy of Engineering in 1996.



Ghassan E. Jabbour

University of Arizona
Optical Sciences Center
Tucson, AZ, USA
gej@optics.arizona.edu

Ghassan E. Jabbour is the head of the research group Organic Optoelectronic Materials and Devices at the Optical Sciences Center working on organic and hybrid materials and their applications to light emitting dvices, solar cells, memory storage, solid state lighting, and other areas. Professor Jabbour is a SPIE Fellow, Track Chair of the Nanotechnology Program for SPIE, and Associate Editor of the Journal of the Society for Information Display (JSID). He has over 200 publications, invited talks, and conference proceedings.

Harold Kahn

Case Western Reserve University
Department of Materials Science
and Engineering
Cleveland, OH, USA
kahn@cwru.edu

Harold Kahn is Researcher Associate Professor of Materials Science and Engineering at Case Western Reserve University, Cleveland, Ohio. His research is focused on MEMS device processing and testing, particularly wafer-level mechanical testing and shape-memory actuated microfluidics. He received a B.S. in metallurgical engineering from Lafayette College and a Ph.D. in electronic materials from the Massachusetts Institute of Technology.

András Kis

Swiss Federal Institute
of Technology (EPFL)
Institute of Physics
of Complex Matter
Lausanne, Switzerland
andras@igahpse.epfl.ch
http://www.andras.kis.name

András Kis is a Ph.D. student of Prof. László Forró at the Swiss Federal Institute of Technology (EPFL) where he works together with Andrzej Kulik. His main subject is the measurement of the mechanical properties of nanoscale objects, including carbon nanotubes and microtubules with the aim of understanding the interplay between their nanoscale structure and mechanical properties.

Jané Kondev

Brandeis University
Physics Department
Waltham, MA, USA
kondev@brandeis.edu
http://mattter.cc.brandeis.edu

Professor Kondev graduated with a PhD from Cornell University and did postdoctoral work at Brown University and Princeton University before joining the faculty at Brandeis University. He is a recipient of the CAREER award from the National Science Foundation and is a Cotrell Scholar of the Research Corporation.

Andrzej J. Kulik

Swiss Federal Institute
of Technology (EPFL)
Institute of Physics
of Complex Matter
Lausanne, Switzerland
andrzej.kulik@epfl.ch

Andrzej Kulik is the Head of the Biostructures and Nanomechanics Laboratory of the Swiss Federal Institute of Technology (EPFL) in Lausanne, Switzerland. His research concentrates on quantitative nanoscale materials properties, nanotribology. scanning probe microscopy, contact mechanics, nanoindentation, near-field ultrasonics, optical tweezers, nanolithography, and nanomanipulation.

Christophe Laurent

Université Paul Sabatier
CIRIMAT (Centre Interuniversitaire
de Recherche et d'Ingénierie
des Matériaux)
Toulouse, France
laurent@chimie.ups-tlse.fr
http://ncn.f2g.net/

Dr. Ch. Laurent is Professor of Materials Chemistry at University Paul Sabatier and is the head of the Nanocomposites and Carbon Nanotubes group of CIRIMAT. His research include in the synthesis, characterization and mechanical properties of ceramic-matrix nanocomposites, and since 1994, carbon nanotubes (synthesis of single- and double-walled CNTs, formation mechanisms, characterization, localized growth, hydrogen storage, ceramic-matrix composites).

Stephen C. Lee

Ohio State University
Biomedical Engineering Center
Columbus, OH, USA
Lee@bme.ohio-state.edu
http://medicine.osu.edu/mcbiochem/

Stephen C. Lee is a pioneer in the field of semi-biological nanodevices (nanobiological devices), having published the first monograph devoted to the topic in 1998. His interests are in enabling technologies for the incorporation of functional proteins and nucleic acids into nanodevices, particularly for application in oncology and cardiovascular disease. He is currently Associate Professor of Cellular and Molecular Biochemistry, Chemical Engineering and Biomedical Engineering at the Ohio State University.

Yunfeng Li

University of California at Berkeley
Department
of Mechanical Engineering
Berkeley, CA, USA
yunfeng@me.Berkeley.edu

Yunfeng Li received the B.S. and M.S. degrees from Beijing University of Aeronautics and Astronautics, Beijing, China, in 1992 and 1995, respectively. He is currently working towards the Ph.D. degree in the Department of Mechanical Engineering, University of California, Berkeley, CA, USA. His research interests include motion control, vibration control, control of MEMS devices, and mechatronics.

Liwei Lin

University of California at Berkeley
Mechanical Engineering Department
Berkeley, CA, USA
lwlin@me.berkeley.edu
http:// me.berkeley.edu/faculty/lin/index.html

Liwei Lin received his Ph.D. from the University of California, Berkeley, in 1993. He was an Associate Professor in the Institute of Applied Mechanics, National Taiwan University, Taiwan (1994–1996) and an Assistant Professor in Mechanical Engineering Department, University of Michigan (1996–1999). He joined UC-Berkeley in 1999 and is now an Associate Professor at Mechanical Engineering Department and Co-Director at Berkeley Sensor and Actuator Center.

Yu-Ming Lin

Massachusetts Institute
of Technology
Department of Electrical Engineering and
Computer Science
Cambridge, MA, USA
yming@mgm.mit.edu

Lin Yu-Ming performed experimental and theoretical studies on Bi-based nanowires for next-generation thermoelectric materials. The electronic transport properties of these systems are studied to investigate quantum size effects. He received the Masterworks Award of the Department of EECS, MIT (2000) and the Gold Medal, MRS Graduate Student Award (2002)

Huiwen Liu

Ohio State University
Nanotribology Laboratory
for Information Storage
and MEMS/NEMS
Columbus, OH, USA
liu.403@osu.edu

Dr. Huiwen Liu is the associate director of the Nanotribology Laboratory for Information Storage and MEMS/NEMS at The Ohio State University. His research interests are study of mechanical, tribological, and physical properties of advanced materials and MEMS/NEMS devices on micro/nano scale. He obtained an Alexander von Humboldt fellowship and the Japanese Science and Technology Agency Fellowship in 1997 and 1998, respectively

Adrian B. Mann

Rutgers University
Department of Ceramics
and Materials Engineering
Piscataway, NJ, USA
abmann@rci.rutgers.edu

Dr. Mann's research focuses on the nanomechanics of materials and the fabrication of nanostructured materials. His research is predominantly on biomedical materials, but also includes ceramics, polymers and metals. He is currently an Assistant Professor at Rutgers University, New Jersey. Prior to this he was a lecturer at the University of Manchester, England and a Fulbright scholar at The Johns Hopkins University, Maryland.

Othmar Marti

University of Ulm
Department of Experimental Physics
Ulm, Germany
Othmar.Marti@physik.uni-ulm.de
http://servex.physik.uni-ulm.de/marti

Profesor Othmar Marti is Head of the Department of Experimental Physics at the University of Ulm. His main research topics are polymers, scanning force microscopy, friction, near-field optics, and the optics of nanoparticles. Studies: diploma from ETH Zürich, Dr. sc. nat. ETH Zürich, Habilitation University Konstanz. He worked at IBM Research Zurich, Switzerland, University of California, USA, ETH Zurich, Switzerland and University of Konstanz, Germany.

Jack Martin

Analog Devices, Inc.
Micromachined Products Division
Cambridge, MA, USA
jack.martin@analog.com

Jack Martin has been a technologist and manager in the design, development and manufacture of industrial MEMS products for 25 years. His accomplishments include development of wafer fab and packaging processes that are used by Analog Devices to produce iMEMS integrated accelerometers and gyroscopes. He has a Ph.D. in Materials Science, a BS and MS in Chemical Engineering, and is a Licensed Professional Engineer.

Brendan McCarthy

University of Arizona
Optical Sciences Center
Tucson, AZ, USA
bmccarthy@optics.arizona.edu

Brendan Mc Carthy is a postdoctoral researcher in the Optical Sciences Center, University of Arizona. He received his PhD in 2001, from Trinity College, University of Dublin, Ireland. His thesis topic was the characterisation of composite materials based on carbon nanotubes and conjugated polymers, using optical and vibrational spectroscopy, scanning tunnelling microscopy, and transmission electron microscopy.

Mehran Mehregany

Case Western Reserve University
Department of Electrical Engineering and Computer Science
Cleveland, OH, USA
mxm31@cwru.edu
http://mems.cwru.edu/

Mehran Mehregany is currently the Chairman of the Electrical Engineering and Computer Science Department at Case and the Goodrich Professor of Engineering Innovation. His research interests include: silicon and silicon carbide micro/nano systems technology (including MEMS/NEMS); micromachining and microfabrication technologies; materials and modeling issues related to MEMS/NEMS and (in some cases) integrated circuits technologies; and MEMS packaging.

Ernst Meyer

University of Basel
Institute of Physics
Basel, Switzerland
Ernst.Meyer@unibas.ch
http://monet.unibas.ch/cgi-bin/people/meyer/

Ernst Meyer is professor of physics at the University of Basel. He is interested in friction force and dynamic force microscopy with true atomic resolution. He is also active in the field of sensors based upon micromechanics and magnetic spin resonance detection with force microscopy. Awarded from the Swiss Physical Society, he is member of the Swiss and American Physical Society, of the Editorial Board of Tribology Letters, and co-editor of books on atomic force microscopy.

Marc Monthioux

UPR A-8011 CNRS
Centre d'Elaboration des Matériaux et d'Etudes Structurales (CEMES)
Toulouse, France
monthiou@cemes.fr



Marc Monthioux has been working on carbon materials for more than 20 years. He is involved in research on carbon nanotubes since 1998, discovered the ability of single-wall nanotubes in being filled by foreign molecules the same year, associated with B. Smith and Prof. D.E. Luzzi from University of Pennsylvania. He is currently Director of Research at the French National Center for Scientific Research and European Associate Editor of CARBON Journal.

Markus Morgenstern

University of Hamburg
Institute of Applied Physics
Hamburg, Germany
mmorgens@physnet.uni-hamburg.de
http://www.nanoscience.de/group_r/stm-sts/

Markus Morgenstern earned his Ph.D. from the Institute of Interface Research and Vacuum Physics of the Forschungszentrum Jülich, Germany in 1996. After one year of research at the University of Paris VII he joined the Group of Prof. Dr. R. Wiesendanger in 1997 as a Senior Scientist. In 2002 he completed his Habilitation at the University of Hamburg with the subject Scanning tunnelling spectroscopy on semiconductor systems and nanostructures

Seizo Morita

Osaka University
Department of Electronic Engineering
Suita-Citiy, Osaka, Japan
smorita@ele.eng.osaka-u.ac.jp
http://www-e2.ele.eng.osaka-u.ac.jp/

Prof. Seizo Morita works in the atomic force microscopy (AFM). He has discovered two-dimensional friction with a lattice periodicity, and two-dimensional solid phase of densely contact-electrified electrons on SiO_2 thin films under ambient conditions. He has achieved mapping, discrimination and control of atomic force and atom with atomic resolution, and also atom manipulation based on a mechanical method using the noncontact AFM apparatus.

Koichi Mukasa

Hokkaido University
Nanoelectronics Laboratory
Sapporo, Japan
mukasa@nano.eng.hokudai.ac.jp
http://www.nano.eng.hokudai.ac.jp/nano/

K. Mukasa is a Professor of electronics at Hokkaido University, Sapporo, Japan. In 1980 he joined Alps Electric Co.Ltd, where he worked on the magnetic thin film heads and materials. In 1987 he moved to the university. His research interests include spin-polarized STM, exchange force microscopy, magnetic force microscopy, Mott spin detectors, nanostructure concerning electron spin and molecular/biological materials and devices.

Martin H. Müser

University of Western Ontario
Department of Applied Mathematics
London, Ontario, Canada
mmuser@uwo.ca
http://publish.uwo.ca/~mmuser/

Prof. Martin Müser received his Ph.D. (1995) and habilitation (2002) from the University of Mainz, Germany. He was a post doctoral researcher at Columbia University (1996/97) as Feodor Lynen fellow and at Johns Hopkins University (1998). He joined the faculty of the University of Western Ontario (U.W.O.) in 2002. His research interests are statistical physics with emphasis on computational materials science, tribology, and quantum solids.

Kenn Oldham

University of California at Berkeley
Department
of Mechanical Engineering
Berkeley, CA, USA
oldham@newton.berkeley.edu

Kenn Oldham is a graduate student in Mechanical Engineering at the University of California at Berkeley, pursuing M.S. and Ph.D. through National Science Foundation Graduate Fellowship. He received his B.S. from Carnegie Mellon University, Pittsburgh, PA. He is currently researching microdevices for hard disk drives. Research interests include MEMS design for control and reliability, optimal and robust control, and materials for microdevices.

Hiroshi Onishi

Kanagawa Academy
of Science and Technology
Surface Chemistry Laboratory
Kanagawa, Japan
oni@net.ksp.or.jp
http://home.ksp.or.jp/onishipro/home.eng/

Dr. Onishi Hiroshi is an experimental chemist at the Kanagawa Academy of Science and Technology interested in molecule-scale reaction kinetics at interfaces. He likes to observe molecules moving and reacting over metal oxide surfaces by time-lapse imaging with scanning probe microscopes. Domestic societies encouraged him with awards to further develop his research towards nano-scale chemistry.

René M. Overney

University of Washington
Department of Chemical Engineering
Seattle, WA, USA
roverney@u.Washington.edu
http://depts.washington.edu/nanolab/

René Overney received his Ph.D. in Physics at the University of Basel in 1992. After his postdoctoral years in Japan and at Exxon, CR, Annandale (NJ) he joined the University of Washington in 1996. His research interests are in mesoscale sciences involving nanorheological interpretations of processes that are as diverse as lubrication, membrane transport, or quantum yield in optoelectronic devices.

Alain Peigney

Université Paul Sabatier
CIRIMAT (Centre Inter-universitaire de Recherches et d'Ingénierie
des Matériaux) – UMR CNRS 5085
Toulouse, France
peigney@chimie.ups-tlse.fr
http://ncn.f2g.net/

Ceramic Engineer and Doctor in Physical-Chemistry – Associate Professor of Materials Chemistry at the Paul Sabatier University – Researches in the synthesis, sintering and microstructural characterization of ceramics and ceramic matrix nanocomposites, and from 1994 on the synthesis on single- and double-walled carbon nanotubes and preparation of nanocomposites containing carbon nanotubes.

Oliver Pfeiffer

University of Basel
Institute of Physics
Basel, Switzerland
Oliver.Pfeiffer@stud.unibas.ch

Oliver Pfeiffer is PhD student at the University of Basel. The main topic of his work is the energy dissipation of oscillating cantilevers in non-contact AFM. Related to this research field is the examination of damping of torsional oscillations of cantilevers when approaching the sample.

Rob Phillips

California Institute of Technology
Mechanical Engineering
and Applied Physics
Pasadena, CA, USA
phillips@aero.caltech.edu
http://www.rpgroup.caltech.edu/people/phillips.html

Rob Phillips is Professor of Mechanical Engineering and Applied Physics at CALTECH, Pasadena. Phillips' work aims to examine nanomechanics of both crystalline solids and biological molecules and their assemblies. Recent efforts have been aimed at investigating mechanics of DNA packing in viruses, the tension-induced gating of ion channels and the mechanical response of bio-functionalized cantilevers.

Haralampos Pozidis

IBM Zurich Research Laboratory
Storage Technologies
Rüschlikon, Switzerland
hap@zurich.ibm.com

He received the Ph.D. in electrical engineering from Drexel University, Philadelphia, PA, in 1998. After working with Philips Research, Eindhoven, the Netherlands, on signal processing and coding for optical storage technologies, with focus on DVD and Blue-Ray-Disc, Dr. Pozidis joined IBM Research in 2001. His research focuses on receiver design for alternative storage technologies, particularly scanning probe microscopy-based techniques.

Prashant K. Purohit

California Institute of Technology
Mechanical Engineering
Pasadena, CA, USA
prashant@caltech.edu
http://www.rpgroup.caltech.edu/~prashant/

Purohit Prashant is currently a Postdoctoral Scholar in Applied Mechanics in the Mechanical Engineering department at Caltech. The overall theme of his research is to develop systematic methods to understand the physics operative at the nanometer scales. His research falls broadly into two categories. The first concerns the subject of coarse-graining methods for crystalline solids and the second mechanics problems in biology. His group hopes to extend the coarse-graining methods in solids to the arena of biological macromolecules.

Oded Rabin

Massachusetts Institute
of Technology
Department of Chemistry
Cambridge, MA, USA
oded@mgm.mit.edu



Oded Rabin is a Ph.D. candidate in Prof. Mildred S. Dresselhaus' group working on the thermoelectric properties of bismuth-antimony nanowire systems, and on electrochemistry-based nanowire synthesis methods. He earned a B.A. degree in Chemistry from the Technion – Israel Institute of Technology, Haifa, Israel and an M.A. degree in Chemistry from the Weizmann Institute of Science, Rehovot, Israel.

Françisco M. Raymo

University of Miami
Department of Chemistry
Coral Gables, FL, USA
fraymo@miami.edu
http://www.as.miami.edu/chemistry/FMRaymo.html

Françisco M. Raymo is Assistant Professor in the Department of Chemistry at the University of Miami. His research interests lie at the interface of chemistry and materials science. In particular, he is exploring innovative strategies to process optical signals with molecular switches, design fluorescent probes for chemical sensing and assemble nanostructured films from electroactive building blocks.

Manitra Razafinimanana

Université Paul Sabatier
Centre de Physique des Plasmas
et leurs Applications (CPPAT)
Toulouse, France
razafinimanana@cpat.ups-tlse.fr
http://cpat.ups-tlse.fr

Manitra Razafinimanana was born in Analalava, Madagascar, on June 28, 1951. He received the 3rd cycle degree, and Doctorat d'Etat ès Sciences Physiques degree from the Université Paul Sabatier, Toulouse, France, in 1982 and 1986 respectively. Since 2000, he was held the position of Professor. He has worked on plasma diagnostics, arc-electrode interaction, transport coefficients and thermodynamical properties calculation.

Mark O. Robbins

Johns Hopkins University
Department of Physics
and Astronomy
Baltimore, MD, USA
mr@jhu.edu
http://www.pha.jhu.edu/~mr

Mark Robbins is a Professor in the Department of Physics and Astronomy of the Johns Hopkins University. His research focuses on non-equilibrium processes like friction, adhesion, spreading, fluid invasion, and shear-induced phase transitions. A common goal is to understand the atomic origins of macroscopic behaviour. He is a fellow of the American Physical Society and was a Sloan Fellow and Presidential Young Investigator.

John A. Rogers

University of Illinois
Department of Materials Science and
Engineering
Urbana, IL, USA
jrogers@uiuc.edu
http://www.mse.uiuc.edu/faculty/
Rogers.html

John A. Rogers earned the Ph.D. degree in physical chemistry from M.I. T. in 1995. Until 2002, he was at Bell Labs serving first as a Member of Technical Staff and subsequently as research Director. John is currently Founder Professor of Engineering at University of Illinois at Urbana/ Champaign. His research interests include methods for micro/ nanofabrication, plastic and molecular electronics, photonics



Mark Ruegsegger

Ohio State University
Biomedical Engineering Center
Columbus, OH, USA
mark@bme.ohio-state.edu

Mark Ruegsegger received his PhD in biomedical engineering at Case Western Reserve Unviersity and is currently an Assistant Professor of Biomedical Engineering at The Ohio State University. His research focus is the development of superparamagnetic particles that can target specific cell or tissue types, in particular atherosclerotic plaque. Other projects include biomimetic surface coatings on biomaterials and characterization of biomolecular flow in nanochannels.

Marina Ruths

Åbo Akademi University
Department of Physical Chemistry
Åbo, Finland
mruths@abo.fi

Marina Ruths received her Ph.D. from the University of California, Santa Barbara in 1996 followed by postdoctoral research at the University of Illinois at Urbana-Champaign, at the Max-Planck-Institute for Polymer Research, an at Åbo Akademi University. Her current research includes adhesion, friction and nanorheology of surfactant, polymer, and liquid crystal systems. She received an ASLA-Fulbright grant in 1991 and an Alexander von Humboldt fellowship in 1998.

Dror Sarid

University of Arizona
Optical Sciences Center
Tucson, AZ, USA
sarid@optics.arizona.edu
http://www.optics.arizona.edu/spm

Dror Sarid is Professor of Optical Sciences and Director of the Optical Data Storage Center. He is conducting research in scanning tunneling microcopy, atomic force microscopy and related systems and in particular probe storage, nano-optics and nano-technology. He published three books and more than 150 papers, mostly on optics and nanotechnology related topics.

Akira Sasahara

Kanagawa Academy
of Science and Technology
Surface Chemistry Laboratory
Kanagawa, Japan
ryo@net.ksp.or.jp
http://home.ksp.or.jp/onishipro/home.
eng/

Dr. Sasahara Akira is interested in local structures formed on solid surfaces. His current research focuses on elucidation of chemical and physical properties of nano-scale structures on metal oxide surfaces and their effect on chemical reaction.

André Schirmeisen

University of Münster
Institute of Physics
Münster, Germany
schira@uni-muenster.de
http://www.andre-schirmeisen.de

Dr. André Schirmeisen is currently working with his research group on nanoscale mechanical phenomena at Münster University. First to combine field ion microscopy with force microscopy to investigate atomically defined nanocontacts. He spent several years in Canada at McGill University to earn his PhD degree in physics. Before he worked as a strategic business consultant and is always interested in connecting nanoscience research with business applications.

Alexander Schwarz

University of Hamburg
Institute of Applied Physics
Hamburg, Germany
aschwarz@physnet.uni-hamburg.de
http://www.nanoscience.de/group_r/

Dr. Alexander Schwarz belongs to the scientific staff of the Center of Microstructure Research at the Institute of Applied Physics at the University of Hamburg, Germany. The group has 10 years (since 1993) experience in scientific research in the field of force microscopy and spectroscopy at cryogenic temperatures in ultrahigh vacuum and high magnetic fields. He is a Senior Scientist and works on Magnetic Force Microscopy (MFM) at low temperatures

Udo D. Schwarz

Yale University
Department
of Mechanical Engineering
New Haven, CT, USA
udo.schwarz@yale.edu
http://www.eng.yale.edu/
nanomechanics/

Udo D. Schwarz received his Ph.D. from the University of Basel in 1993 already using scanning force microscopy. Subsequently he moved to the University of Hamburg where he specialised on low-temperature scanning force microscopy and nanotribology. After spending a year at the Lawrence Berkeley National Laboratory he accepted a position as Associate Professor of Mechanical Engineering at Yale University in 2002.

Philippe Serp

Ecole Nationale Supèrieure d'Ingénieurs
en Arts Chimiques
et Technologiques
Laboratoire de Catalyse,
Chimie Fine et Polymères
Toulouse, France
Philippe.Serp@ensiacet.fr
http://www.ensiacet.fr/



Philippe Serp is associate professor in the LCCFP at ENSIACET. After receiving is PhD from Paul Sabatier University, Toulouse, in 1994 where he worked on the preparation of supported catalyst, he moved to Universidade do Porto to carry out post-doctoral research on catalytic CVD to prepare carbon fibers. His current research interests include CVD preparation of nanostructured materials and catalysis.



Bryan R. Smith

Ohio State University
Biomedical Engineering Center
Columbus, OH, USA
bryan@bme.ohio-state.edu

Bryan Smith is a Ph.D. candidate in biomedical engineering at The Ohio State University, specializing in the microfabrication and bioconjugation of micro- and nanoparticles for proteomics as well as imaging and drug delivery in breast cancer and atherosclerosis.

Anisoara Socoliuc

University of Basel
Institute of Physics
Basel, Switzerland
A.Socoliuc@unibas.ch
http://monet.physik.unibas.ch/gue/
uhvafm/

Anisoara Socoliuc studied physics in Iasi, Romania. She is now PhD student at the University of Basel. The main topic of her work is the study of wear processes on the nanometer scale by friction force microscopy.

Yasuhiro Sugawara

Osaka University
Department of Applied Physics
Suita, Japan
sugawara@ap.eng.osaka-u.ac.jp

Yasuhiro Sugawara received his Ph.D. in 1988 from Tohoku University and is Professor in the Department of Applied Physics of the Graduate School of Engineering at Osaka University since 2002. His research focuses on the further development of scanning probe microscopes and their applications, especially the noncontact atomic force microscope for the observation of solid surfaces at the atomic and molecular level. His aim is also to develop new nanomaterials and nanodevices by manipulation of single atoms and molecules using the atomic force microscope.

George W. Tyndall

IBM Almaden Research Center
Science and Technology
San Jose, CA, USA
tyndallgw@netscape.net

Dr. George Tyndall's current research focuses on the friction and adhesion in boundary lubricants especially as it pertains to the tribology of the magnetic recording head-disk interface in hard-disk drive applications.

Peter Vettiger

IBM Zurich Research Laboratory
Manager Micro-/Nanomechanics
Rüschlikon, Switzerland
pv@zurich.ibm.com

In 1963 Peter Vettiger joined IBM Research (Rüschlikon). He established and headed micro/nanoscale fabrication activities for superconducting, electronic and opto-electronic devices. Together with G.K. Binnig, he initiated Millipede probe-storage activities in 1995. His research interests are micro/nanomechanical devices and systems for probe-storage and biological applications. He is an IEEE Fellow and received a Doctor honoris causa from the University of Basel, Switzerland.

Darrin J. Young

Case Western Reserve University
Electrical Engineering
and Computer Science
Cleveland, OH, USA
djy@po.cwru.edu
http://home.cwru.edu/~djy

Darrin J. Young received his BS, MS, and PhD degrees from the EECS Department at University of California at Berkeley in 1991, 1993, and 1999, respectively. He pioneered RF MEMS high-Q tunable passive devices for wireless communications. He joined the EECS Department at Case Western Reserve University as an assistant professor in 1999. His main research interests include MEMS device design and fabrication.

Babak Ziaie

University of Minnesota
Department of Electrical
and Computer Engineering
Minneapolis, MN, USA
ziaie@ece.umn.edu

Dr. Babak Ziaie is an assistant professor in the Electrical and Computer Engineering Department of the University of Minnesota. His research interests are located at the boundaries between engineering and biology. He collaborates with physicians and biologists of all kinds and his lab is actively involved in the design and fabrication of biomedical micro and nanoelectromechanical systems.

Christian A. Zorman

Case Western Reserve University
Department of Electrical Engineering
and Computer Science
Cleveland, OH, USA
caz@po.cwru.edu
http://mems.cwru.edu/

Christian A. Zorman received a B.S. cum laude in physics and a B.A. cum laude in economics from The Ohio State University in 1988. He received M.S. and Ph.D. degrees in physics from Case Western Reserve University (CWRU) in 1991 and 1994, respectively. Dr. Zorman served in several research capacities at CWRU between 1994 and 2002, before being appointed an Associate Professor in 2002. His research interests involve materials and processes for MEMS.

Philippe K. Zysset

Technische Universität Wien
Institut für Leichtbau
und Flugzeugbau (ILFB)
Wien, Austria
philippe.zysset@epfl.ch
http://ilfb.tuwien.ac.at/

Philippe Zysset graduated in physics in 1987 and obtained a Ph.D. in biomechanics in 1994 at Ecole Polytechnique Fédérale de Lausanne (EPFL) in Lausanne, Switzerland. He completed his postdoctoral training at the Orthopaedic Research Laboratories of the University of Michigan and returned to EPFL as an assistant professor in 1997. His current research interests are in bone biomechanics.

Detailed Contents

List of Tables XXIX
List of Abbreviations XXXIII

1 **Introduction to Nanotechnology** 1
  1.1 Background and Definition of Nanotechnology 1
  1.2 Why Nano? 2
  1.3 Lessons from Nature 2
  1.4 Applications in Different Fields 3
  1.5 Reliability Issues of MEMS/NEMS 4
  1.6 Organization of the Handbook 5
  References 5

Part A Nanostructures, Micro/Nanofabrication, and Micro/Nanodevices

2 **Nanomaterials Synthesis and Applications: Molecule-Based Devices** 9
  2.1 Chemical Approaches to Nanostructured Materials 10
    2.1.1 From Molecular Building Blocks to Nanostructures 10
    2.1.2 Nanoscaled Biomolecules: Nucleic Acids and Proteins 10
    2.1.3 Chemical Synthesis of Artificial Nanostructures 12
    2.1.4 From Structural Control to Designed Properties and Functions 12
  2.2 Molecular Switches and Logic Gates 14
    2.2.1 From Macroscopic to Molecular Switches 15
    2.2.2 Digital Processing and Molecular Logic Gates 15
    2.2.3 Molecular AND, NOT, and OR Gates 16
    2.2.4 Combinational Logic at the Molecular Level 17
    2.2.5 Intermolecular Communication 18
  2.3 Solid State Devices 22
    2.3.1 From Functional Solutions to Electroactive and Photoactive Solids 22
    2.3.2 Langmuir–Blodgett Films 23
    2.3.3 Self-Assembled Monolayers 27
    2.3.4 Nanogaps and Nanowires 31
  2.4 Conclusions and Outlook 35
  References 36

3 **Introduction to Carbon Nanotubes** 39
  3.1 Structure of Carbon Nanotubes 40
    3.1.1 Single-Wall Nanotubes 40
    3.1.2 Multiwall Nanotubes 43

Springer Handbook *of* Nanotechnology
B. Bhushan • © Springer 2004

3.2 Synthesis of Carbon Nanotubes 45
  3.2.1 Solid Carbon Source-Based Production Techniques for Carbon Nanotubes 45
  3.2.2 Gaseous Carbon Source-Based Production Techniques for Carbon Nanotubes 52
  3.2.3 Miscellaneous Techniques 57
  3.2.4 Synthesis of Aligned Carbon Nanotubes 58
3.3 Growth Mechanisms of Carbon Nanotubes 59
  3.3.1 Catalyst-Free Growth 59
  3.3.2 Catalytically Activated Growth 60
3.4 Properties of Carbon Nanotubes 63
  3.4.1 Variability of Carbon Nanotube Properties 63
  3.4.2 General Properties 63
  3.4.3 SWNT Adsorption Properties 63
  3.4.4 Transport Properties 65
  3.4.5 Mechanical Properties 67
  3.4.6 Reactivity 67
3.5 Carbon Nanotube-Based Nano-Objects 68
  3.5.1 Hetero-Nanotubes 68
  3.5.2 Hybrid Carbon Nanotubes 68
  3.5.3 Functionalized Nanotubes 71
3.6 Applications of Carbon Nanotubes 73
  3.6.1 Current Applications 73
  3.6.2 Expected Applications Related to Adsorption 76
References 86

4 **Nanowires** 99
4.1 Synthesis 100
  4.1.1 Template-Assisted Synthesis 100
  4.1.2 VLS Method for Nanowire Synthesis 105
  4.1.3 Other Synthesis Methods 107
  4.1.4 Hierarchical Arrangement and Superstructures of Nanowires 108
4.2 Characterization and Physical Properties of Nanowires 110
  4.2.1 Structural Characterization 110
  4.2.2 Transport Properties 115
  4.2.3 Optical Properties 126
4.3 Applications 131
  4.3.1 Electrical Applications 131
  4.3.2 Thermoelectric Applications 133
  4.3.3 Optical Applications 134
  4.3.4 Chemical and Biochemical Sensing Devices 137
  4.3.5 Magnetic Applications 137
4.4 Concluding Remarks 138
References 138

5 **Introduction to Micro/Nanofabrication** 147
5.1 Basic Microfabrication Techniques 148
5.1.1 Lithography 148
5.1.2 Thin Film Deposition and Doping 149
5.1.3 Etching and Substrate Removal 153
5.1.4 Substrate Bonding 157
5.2 MEMS Fabrication Techniques 159
5.2.1 Bulk Micromachining 159
5.2.2 Surface Micromachining 163
5.2.3 High-Aspect-Ratio Micromachining 166
5.3 Nanofabrication Techniques 170
5.3.1 E-Beam and Nano-Imprint Fabrication 171
5.3.2 Epitaxy and Strain Engineering 172
5.3.3 Scanned Probe Techniques 173
5.3.4 Self-Assembly and Template Manufacturing 176
References 180

6 **Stamping Techniques for Micro and Nanofabrication: Methods and Applications** 185
6.1 High Resolution Stamps 186
6.2 Microcontact Printing 187
6.3 Nanotransfer Printing 190
6.4 Applications 193
6.4.1 Unconventional Electronic Systems 193
6.4.2 Lasers and Waveguide Structures 198
6.5 Conclusions 200
References 200

7 **Materials Aspects of Micro- and Nanoelectromechanical Systems** . 203
7.1 Silicon 203
7.1.1 Single Crystal Silicon 204
7.1.2 Polysilicon 205
7.1.3 Porous Silicon 208
7.1.4 Silicon Dioxide 208
7.1.5 Silicon Nitride 209
7.2 Germanium-Based Materials 210
7.2.1 Polycrystalline Ge 210
7.2.2 Polycrystalline SiGe 210
7.3 Metals 211
7.4 Harsh Environment Semiconductors 212
7.4.1 Silicon Carbide 212
7.4.2 Diamond 215
7.5 GaAs, InP, and Related III-V Materials 217
7.6 Ferroelectric Materials 218
7.7 Polymer Materials 219
7.7.1 Polyimide 219
7.7.2 SU-8 220

7.7.3 Parylene 220
7.8 Future Trends 220
References 221

8 **MEMS/NEMS Devices and Applications** 225
8.1 MEMS Devices and Applications 227
8.1.1 Pressure Sensor 227
8.1.2 Inertial Sensor 229
8.1.3 Optical MEMS 233
8.1.4 RF MEMS 239
8.2 NEMS Devices and Applications 246
8.3 Current Challenges and Future Trends 249
References 250

9 **Microfluidics and Their Applications to Lab-on-a-Chip** 253
9.1 Materials for Microfluidic Devices and Micro/Nano Fabrication Techniques 254
9.1.1 Silicon 254
9.1.2 Glass 254
9.1.3 Polymer 255
9.2 Active Microfluidic Devices 257
9.2.1 Microvalves 258
9.2.2 Micropumps 260
9.3 Smart Passive Microfluidic Devices 262
9.3.1 Passive Microvalves 262
9.3.2 Passive Micromixers 265
9.3.3 Passive Microdispensers 266
9.3.4 Microfluidic Multiplexer Integrated with Passive Microdispenser 267
9.3.5 Passive Micropumps 269
9.3.6 Advantages and Disadvantages of the Passive Microfluidic Approach 269
9.4 Lab-on-a-Chip for Biochemical Analysis 270
9.4.1 Magnetic Micro/Nano Bead-Based Biochemical Detection System 270
9.4.2 Disposable Smart Lab-on-a-Chip for Blood Analysis 273
References 276

10 **Therapeutic Nanodevices** 279
10.1 Definitions and Scope of Discussion 280
10.1.1 Design Issues 281
10.1.2 Utility and Scope of Therapeutic Nanodevices 285
10.2 Synthetic Approaches: “top-down” versus “bottom-up” Approaches for Nanotherapeutic Device Components 285
10.2.1 Production of Nanoporous Membranes by Microfabrication Methods: A top-down Approach 285

10.2.2 Synthesis of Poly(amido) Amine (PAMAM) Dendrimers: A bottom-up Approach 286
10.2.3 The Limits of top-down and bottom-up Distinctions with Respect to Nanomaterials and Nanodevices 287
10.3 Technological and Biological Opportunities 288
10.3.1 Assembly Approaches 288
10.3.2 Targeting: Delimiting Nanotherapeutic Action in Three-Dimensional Space 296
10.3.3 Triggering: Delimiting Nanotherapeutic Action in Space and Time 298
10.3.4 Sensing Modalities 302
10.3.5 Imaging Using Nanotherapeutic Contrast Agents 304
10.4 Applications for Nanotherapeutic Devices 307
10.4.1 Nanotherapeutic Devices in Oncology 307
10.4.2 Cardiovascular Applications of Nanotherapeutics 310
10.4.3 Nanotherapeutics and Specific Host Immune Responses 311
10.5 Concluding Remarks: Barriers to Practice and Prospects 315
10.5.1 Complexity in Biology 315
10.5.2 Dissemination of Biological Information 315
10.5.3 Cultural Differences Between Technologists and Biologists 316
References 317

Part B Scanning Probe Microscopy

11 **Scanning Probe Microscopy – Principle of Operation, Instrumentation, and Probes** 325
11.1 Scanning Tunneling Microscope 327
11.1.1 Binnig et al.'s Design 327
11.1.2 Commercial STMs 328
11.1.3 STM Probe Construction 330
11.2 Atomic Force Microscope 331
11.2.1 Binnig et al.'s Design 333
11.2.2 Commercial AFM 333
11.2.3 AFM Probe Construction 338
11.2.4 Friction Measurement Methods 342
11.2.5 Normal Force and Friction Force Calibrations of Cantilever Beams 346
11.3 AFM Instrumentation and Analyses 347
11.3.1 The Mechanics of Cantilevers 347
11.3.2 Instrumentation and Analyses of Detection Systems for Cantilever Deflections 350
11.3.3 Combinations for 3-D-Force Measurements 358
11.3.4 Scanning and Control Systems 359
References 364

12 **Probes in Scanning Microscopies** 371
- 12.1 Atomic Force Microscopy 372
  - 12.1.1 Principles of Operation 372
  - 12.1.2 Standard Probe Tips 373
  - 12.1.3 Probe Tip Performance 374
  - 12.1.4 Oxide-Sharpened Tips 375
  - 12.1.5 FIB tips 376
  - 12.1.6 EBD tips 376
  - 12.1.7 Carbon Nanotube Tips 376
- 12.2 Scanning Tunneling Microscopy 382
  - 12.2.1 Mechanically Cut STM Tips 382
  - 12.2.2 Electrochemically Etched STM Tips 383
- **References** 383

13 **Noncontact Atomic Force Microscopy and Its Related Topics** 385
- 13.1 Principles of Noncontact Atomic Force Microscope (NC-AFM) 386
  - 13.1.1 Imaging Signal in AFM 386
  - 13.1.2 Experimental Measurement and Noise 387
  - 13.1.3 Static AFM Operating Mode 387
  - 13.1.4 Dynamic AFM Operating Mode 388
  - 13.1.5 The Four Additional Challenges Faced by AFM 388
  - 13.1.6 Frequency-Modulation AFM (FM-AFM) 389
  - 13.1.7 Relation Between Frequency Shift and Forces 390
  - 13.1.8 Noise in Frequency-Modulation AFM – Generic Calculation . 391
  - 13.1.9 Conclusion 391
- 13.2 Applications to Semiconductors 391
  - 13.2.1 Si(111)7×7 Surface 392
  - 13.2.2 Si(100)2×1 and Si(100)2×1:H Monohydride Surfaces 393
  - 13.2.3 Metal-Deposited Si Surface 395
- 13.3 Applications to Insulators 397
  - 13.3.1 Alkali Halides, Fluorides, and Metal Oxides 397
  - 13.3.2 Atomically Resolved Imaging of a NiO(001) Surface 402
  - 13.3.3 Atomically Resolved Imaging Using Noncoated and Fe-Coated Si Tips 402
- 13.4 Applications to Molecules 404
  - 13.4.1 Why Molecules and What Molecules? 404
  - 13.4.2 Mechanism of Molecular Imaging 404
  - 13.4.3 Perspectives 407
- **References** 407

14 **Low Temperature Scanning Probe Microscopy** 413
- 14.1 Microscope Operation at Low Temperatures 414
  - 14.1.1 Drift 414
  - 14.1.2 Noise 415
  - 14.1.3 Stability 415
  - 14.1.4 Piezo Relaxation and Hysteresis 415
- 14.2 Instrumentation 415

14.2.1 A Simple Design for a Variable Temperature STM 416
14.2.2 A Low Temperature SFM Based on a Bath Cryostat 417
14.3 Scanning Tunneling Microscopy and Spectroscopy 419
14.3.1 Atomic Manipulation 419
14.3.2 Imaging Atomic Motion 420
14.3.3 Detecting Light from Single Atoms and Molecules 421
14.3.4 High Resolution Spectroscopy 422
14.3.5 Imaging Electronic Wave Functions 427
14.3.6 Imaging Spin Polarization: Nanomagnetism 431
14.4 Scanning Force Microscopy and Spectroscopy 433
14.4.1 Atomic-Scale Imaging 434
14.4.2 Force Spectroscopy 436
14.4.3 Electrostatic Force Microscopy 438
14.4.4 Magnetic Force Microscopy 439
References 442

15 **Dynamic Force Microscopy** 449
15.1 Motivation: Measurement of a Single Atomic Bond 450
15.2 Harmonic Oscillator: A Model System for Dynamic AFM 454
15.3 Dynamic AFM Operational Modes 455
15.3.1 Amplitude-Modulation/ Tapping-Mode AFMs 456
15.3.2 Self-Excitation Modes 461
15.4 *Q*-Control 464
15.5 Dissipation Processes Measured with Dynamic AFM 468
15.6 Conclusion 471
References 471

16 **Molecular Recognition Force Microscopy** 475
16.1 Ligand Tip Chemistry 476
16.2 Fixation of Receptors to Probe Surfaces 478
16.3 Single-Molecule Recognition Force Detection 479
16.4 Principles of Molecular Recognition Force Spectroscopy 482
16.5 Recognition Force Spectroscopy: From Isolated Molecules to Biological Membranes 484
16.5.1 Forces, Energies, and Kinetic Rates 484
16.5.2 Complex Bonds and Energy Landscapes 486
16.5.3 Live Cells and Membranes 489
16.6 Recognition Imaging 489
16.7 Concluding Remarks 491
References 492

Part C Nanotribology and Nanomechanics

17 **Micro/Nanotribology and Materials Characterization Studies Using Scanning Probe Microscopy** 497
17.1 Description of AFM/FFM and Various Measurement Techniques 499

17.1.1 Surface Roughness and Friction Force Measurements 500
17.1.2 Adhesion Measurements 502
17.1.3 Scratching, Wear and Fabrication/Machining 503
17.1.4 Surface Potential Measurements 503
17.1.5 In Situ Characterization of Local Deformation Studies 504
17.1.6 Nanoindentation Measurements 504
17.1.7 Localized Surface Elasticity and Viscoelasticity Mapping 505
17.1.8 Boundary Lubrication Measurements 507
17.2 Friction and Adhesion 507
17.2.1 Atomic-Scale Friction 507
17.2.2 Microscale Friction 507
17.2.3 Directionality Effect on Microfriction 511
17.2.4 Velocity Dependence on Microfriction 513
17.2.5 Effect of Tip Radii and Humidity on Adhesion and Friction .. 515
17.2.6 Scale Dependence on Friction 518
17.3 Scratching, Wear, Local Deformation, and Fabrication/Machining ... 518
17.3.1 Nanoscale Wear 518
17.3.2 Microscale Scratching 519
17.3.3 Microscale Wear 520
17.3.4 In Situ Characterization of Local Deformation 524
17.3.5 Nanofabrication/Nanomachining 526
17.4 Indentation 526
17.4.1 Picoindentation 526
17.4.2 Nanoscale Indentation 527
17.4.3 Localized Surface Elasticity and Viscoelasticity Mapping 528
17.5 Boundary Lubrication 530
17.5.1 Perfluoropolyether Lubricants 530
17.5.2 Self-Assembled Monolayers 536
17.5.3 Liquid Film Thickness Measurements 537
17.6 Closure 538
References 539

18 **Surface Forces and Nanorheology of Molecularly Thin Films** 543
18.1 Introduction: Types of Surface Forces 544
18.2 Methods Used to Study Surface Forces 546
18.2.1 Force Laws 546
18.2.2 Adhesion Forces 547
18.2.3 The SFA and AFM 547
18.2.4 Some Other Force-Measuring Techniques 549
18.3 Normal Forces Between Dry (Unlubricated) Surfaces 550
18.3.1 Van der Waals Forces in Vacuum and Inert Vapors 550
18.3.2 Charge Exchange Interactions 552
18.3.3 Sintering and Cold Welding 553
18.4 Normal Forces Between Surfaces in Liquids 554
18.4.1 Van der Waals Forces in Liquids 554
18.4.2 Electrostatic and Ion Correlation Forces 554
18.4.3 Solvation and Structural Forces 557

18.4.4 Hydration and Hydrophobic Forces 559
18.4.5 Polymer-Mediated Forces 561
18.4.6 Thermal Fluctuation Forces 563
18.5 Adhesion and Capillary Forces 564
18.5.1 Capillary Forces 564
18.5.2 Adhesion Mechanics 566
18.5.3 Effects of Surface Structure, Roughness, and Lattice Mismatch 566
18.5.4 Nonequilibrium and Rate-Dependent Interactions: Adhesion Hysteresis 567
18.6 Introduction: Different Modes of Friction and the Limits of Continuum Models 569
18.7 Relationship Between Adhesion and Friction Between Dry (Unlubricated and Solid Boundary Lubricated) Surfaces 571
18.7.1 Amontons' Law and Deviations from It Due to Adhesion: The Cobblestone Model 571
18.7.2 Adhesion Force and Load Contribution to Interfacial Friction 572
18.7.3 Examples of Experimentally Observed Friction of Dry Surfaces 576
18.7.4 Transition from Interfacial to Normal Friction with Wear 579
18.8 Liquid Lubricated Surfaces 580
18.8.1 Viscous Forces and Friction of Thick Films: Continuum Regime 580
18.8.2 Friction of Intermediate Thickness Films 582
18.8.3 Boundary Lubrication of Molecularly Thin Films: Nanorheology 584
18.9 Role of Molecular Shape and Surface Structure in Friction 591
References 594

19 **Scanning Probe Studies of Nanoscale Adhesion Between Solids in the Presence of Liquids and Monolayer Films** 605
19.1 The Importance of Adhesion at the Nanoscale 605
19.2 Techniques for Measuring Adhesion 606
19.3 Calibration of Forces, Displacements, and Tips 610
19.3.1 Force Calibration 610
19.3.2 Probe Tip Characterization 611
19.3.3 Displacement Calibration 612
19.4 The Effect of Liquid Capillaries on Adhesion 612
19.4.1 Theoretical Background 612
19.4.2 Experimental and Theoretical Studies of Capillary Formation with Scanning Probes 614
19.4.3 Future Directions 618
19.5 Self-Assembled Monolayers 618
19.5.1 Adhesion at SAM Interfaces 618
19.5.2 Chemical Force Microscopy: General Methodology 619
19.5.3 Adhesion at SAM-Modified Surfaces in Liquids 620
19.5.4 Impact of Intra- and Inter-Chain Interactions on Adhesion 621

19.5.5 Adhesion at the Single-Bond Level 622
19.5.6 Future Directions 623
19.6 Concluding Remarks 624
References 624

20 **Friction and Wear on the Atomic Scale** 631
20.1 Friction Force Microscopy in Ultra-High Vacuum 632
20.1.1 Friction Force Microscopy 632
20.1.2 Force Calibration 632
20.1.3 The Ultra-high Vacuum Environment 635
20.1.4 A Typical Microscope in UHV 635
20.2 The Tomlinson Model 636
20.2.1 One-dimensional Tomlinson Model 636
20.2.2 Two-dimensional Tomlinson Model 637
20.2.3 Friction Between Atomically Flat Surfaces 637
20.3 Friction Experiments on Atomic Scale 638
20.3.1 Anisotropy of Friction 642
20.4 Thermal Effects on Atomic Friction 642
20.4.1 The Tomlinson Model at Finite Temperature 642
20.4.2 Velocity Dependence of Friction 644
20.4.3 Temperature Dependence of Friction 645
20.5 Geometry Effects in Nanocontacts 646
20.5.1 Continuum Mechanics of Single Asperities 646
20.5.2 Load Dependence of Friction 647
20.5.3 Estimation of the Contact Area 647
20.6 Wear on the Atomic Scale 649
20.6.1 Abrasive Wear on the Atomic Scale 649
20.6.2 Wear Contribution to Friction 650
20.7 Molecular Dynamics Simulations of Atomic Friction and Wear 651
20.7.1 Molecular Dynamics Simulation of Friction Processes 651
20.7.2 Molecular Dynamics Simulations of Abrasive Wear 652
20.8 Energy Dissipation in Noncontact Atomic Force Microscopy 654
20.9 Conclusion 656
References 657

21 **Nanoscale Mechanical Properties – Measuring Techniques and Applications** 661
21.1 Local Mechanical Spectroscopy by Contact AFM 662
21.1.1 The Variable-Temperature SLAM (T-SLAM) 663
21.1.2 Example One: Local Mechanical Spectroscopy of Polymers 664
21.1.3 Example Two: Local Mechanical Spectroscopy of NiTi 665
21.2 Static Methods – Mesoscopic Samples 667
21.2.1 Carbon Nanotubes – Introduction to Basic Morphologies and Production Methods 667
21.2.2 Measurements of the Mechanical Properties of Carbon Nanotubes by SPM 668
21.2.3 Microtubules and Their Elastic Properties 673

21.3 Scanning Nanoindentation: An Application to Bone Tissue 674
  21.3.1 Scanning Nanoindentation 674
  21.3.2 Application of Scanning Nanoindentation 674
  21.3.3 Example: Study of Mechanical Properties of Bone Lamellae Using SN 675
  21.3.4 Conclusion 681
21.4 Conclusions and Perspectives 682
References 682

22 **Nanomechanical Properties of Solid Surfaces and Thin Films** 687
22.1 Instrumentation 688
  22.1.1 AFM and Scanning Probe Microscopy 688
  22.1.2 Nanoindentation 689
  22.1.3 Adaptations of Nanoindentation 690
  22.1.4 Complimentary Techniques 691
  22.1.5 Bulge Tests 691
  22.1.6 Acoustic Methods 692
  22.1.7 Imaging Methods 693
22.2 Data Analysis 694
  22.2.1 Elastic Contacts 694
  22.2.2 Indentation of Ideal Plastic Materials 694
  22.2.3 Adhesive Contacts 695
  22.2.4 Indenter Geometry 696
  22.2.5 Analyzing Load/Displacement Curves 696
  22.2.6 Modifications to the Analysis 699
  22.2.7 Alternative Methods of Analysis 700
  22.2.8 Measuring Contact Stiffness 701
  22.2.9 Measuring Viscoelasticity 702
22.3 Modes of Deformation 702
  22.3.1 Defect Nucleation 702
  22.3.2 Variations with Depth 704
  22.3.3 Anisotropic Materials 704
  22.3.4 Fracture and Delamination 704
  22.3.5 Phase Transformations 705
22.4 Thin Films and Multilayers 707
  22.4.1 Thin Films 707
  22.4.2 Multilayers 709
22.5 Developing Areas 711
References 712

23 **Atomistic Computer Simulations of Nanotribology** 717
23.1 Molecular Dynamics 718
  23.1.1 Model Potentials 719
  23.1.2 Maintaining Constant Temperature 720
  23.1.3 Imposing Load and Shear 721
  23.1.4 The Time-Scale and Length-Scale Gaps 721
  23.1.5 A Summary of Possible Traps 722

23.2 Friction Mechanisms at the Atomic Scale 723
  23.2.1 Geometric Interlocking 723
  23.2.2 Elastic Instabilities 724
  23.2.3 Role of Dimensionality and Disorder 727
  23.2.4 Elastic Instabilities vs. Wear in Atomistic Models 727
  23.2.5 Hydrodynamic Lubrication and Its Confinement-Induced Breakdown 729
  23.2.6 Submonolayer Films 731
23.3 Stick-Slip Dynamics 732
23.4 Conclusions 734
References 735

24 **Mechanics of Biological Nanotechnology** 739
24.1 Science at the Biology–Nanotechnology Interface 740
  24.1.1 Biological Nanotechnology 740
  24.1.2 Self-Assembly as Biological Nanotechnology 740
  24.1.3 Molecular Motors as Biological Nanotechnology 740
  24.1.4 Molecular Channels and Pumps as Biological Nanotechnology 741
  24.1.5 Biologically Inspired Nanotechnology 742
  24.1.6 Nanotechnology and Single Molecule Assays in Biology 743
  24.1.7 The Challenge of Modeling the Bio-Nano Interface 744
24.2 Scales at the Bio-Nano Interface 746
  24.2.1 Spatial Scales and Structures 747
  24.2.2 Temporal Scales and Processes 749
  24.2.3 Force and Energy Scales: The Interplay of Deterministic and Thermal Forces 750
24.3 Modeling at the Nano-Bio Interface 752
  24.3.1 Tension Between Universality and Specificity 752
  24.3.2 Atomic-Level Analysis of Biological Systems 753
  24.3.3 Continuum Analysis of Biological Systems 753
24.4 Nature's Nanotechnology Revealed: Viruses as a Case Study 755
24.5 Concluding Remarks 760
References 761

25 **Mechanical Properties of Nanostructures** 763
25.1 Experimental Techniques for Measurement of Mechanical Properties of Nanostructures 765
  25.1.1 Indentation and Scratch Tests Using Micro/Nanoindenters .. 765
  25.1.2 Bending Tests of Nanostructures Using an AFM 765
  25.1.3 Bending Tests Using a Nanoindenter 769
25.2 Experimental Results and Discussion 770
  25.2.1 Indentation and Scratch Tests of Various Materials Using Micro/Nanoindenters 770
  25.2.2 Bending Tests of Nanobeams Using an AFM 773
  25.2.3 Bending Tests of Microbeams Using a Nanoindenter 777

25.3 Finite Element Analysis of Nanostructures with Roughness and Scratches 778
  25.3.1 Stress Distribution in a Smooth Nanobeam 779
  25.3.2 Effect of Roughness in the Longitudinal Direction 781
  25.3.3 Effect of Roughness in the Transverse Direction and Scratches 781
  25.3.4 Effect on Stresses and Displacements for Materials That Are Elastic, Elastic–Plastic, or Elastic–Perfectly Plastic .. 784
25.4 Closure 785
References 786

Part D Molecularly Thick Films for Lubrication

26 **Nanotribology of Ultrathin and Hard Amorphous Carbon Films** 791
26.1 Description of Commonly Used Deposition Techniques 795
  26.1.1 Filtered Cathodic Arc Deposition Technique 798
  26.1.2 Ion Beam Deposition Technique 798
  26.1.3 Electron Cyclotron Resonance Chemical Vapor Deposition Technique 799
  26.1.4 Sputtering Deposition Technique 799
  26.1.5 Plasma-Enhanced Chemical Vapor Deposition Technique ... 799
26.2 Chemical Characterization and Effect of Deposition Conditions on Chemical Characteristics and Physical Properties 800
  26.2.1 EELS and Raman Spectroscopy 800
  26.2.2 Hydrogen Concentrations 804
  26.2.3 Physical Properties 804
  26.2.4 Summary 805
26.3 Micromechanical and Tribological Characterizations of Coatings Deposited by Various Techniques 805
  26.3.1 Micromechanical Characterization 805
  26.3.2 Microscratch and Microwear Studies 813
  26.3.3 Macroscale Tribological Characterization 822
  26.3.4 Coating Continuity Analysis 826
References 827

27 **Self-Assembled Monolayers for Controlling Adhesion, Friction and Wear** 831
27.1 A Primer to Organic Chemistry 834
  27.1.1 Electronegativity/Polarity 834
  27.1.2 Classification and Structure of Organic Compounds 835
  27.1.3 Polar and Nonpolar Groups 838
27.2 Self-Assembled Monolayers: Substrates, Head Groups, Spacer Chains, and End Groups 839
27.3 Tribological Properties of SAMs 841
  27.3.1 Surface Roughness and Friction Images of SAMs Films 844
  27.3.2 Adhesion, Friction, and Work of Adhesion 844

27.3.3 Stiffness, Molecular Spring Model, and Micropatterned SAMs 848
27.3.4 Influence of Humidity, Temperature, and Velocity on Adhesion and Friction 850
27.3.5 Wear and Scratch Resistance of SAMs 853
27.4 Closure 856
References 857

28 **Nanoscale Boundary Lubrication Studies** 861
28.1 Lubricants Details 862
28.2 Nanodeformation, Molecular Conformation, and Lubricant Spreading 864
28.3 Boundary Lubrication Studies 866
28.3.1 Friction and Adhesion 866
28.3.2 Rest Time Effect 869
28.3.3 Velocity Effect 871
28.3.4 Relative Humidity and Temperature Effect 873
28.3.5 Tip Radius Effect 876
28.3.6 Wear Study 879
28.4 Closure 880
References 881

29 **Kinetics and Energetics in Nanolubrication** 883
29.1 Background: From Bulk to Molecular Lubrication 885
29.1.1 Hydrodynamic Lubrication and Relaxation 885
29.1.2 Boundary Lubrication 885
29.1.3 Stick Slip and Collective Phenomena 885
29.2 Thermal Activation Model of Lubricated Friction 887
29.3 Functional Behavior of Lubricated Friction 888
29.4 Thermodynamical Models Based on Small and Nonconforming Contacts 890
29.5 Limitation of the Gaussian Statistics – The Fractal Space 891
29.6 Fractal Mobility in Reactive Lubrication 892
29.7 Metastable Lubricant Systems in Large Conforming Contacts 894
29.8 Conclusion 895
References 895

Part E Industrial Applications and Microdevice Reliability

30 **Nanotechnology for Data Storage Applications** 899
30.1 Current Status of Commercial Data Storage Devices 901
30.1.1 Non-Volatile Random Access Memory 904
30.2 Opportunities Offered by Nanotechnology for Data Storage 907
30.2.1 Motors 907
30.2.2 Sensors 909
30.2.3 Media and Experimental Results 913
30.3 Conclusion 918

References 919

31 **The "Millipede" – A Nanotechnology-Based AFM Data-Storage System** 921
31.1 The Millipede Concept 923
31.2 Thermomechanical AFM Data Storage 924
31.3 Array Design, Technology, and Fabrication 926
31.4 Array Characterization 927
31.5 *x*/*y*/*z* Medium Microscanner 929
31.6 First Write/Read Results with the 32×32 Array Chip 931
31.7 Polymer Medium 932
  31.7.1 Writing Mechanism 932
  31.7.2 Erasing Mechanism 935
  31.7.3 Overwriting Mechanism 937
31.8 Read Channel Model 939
31.9 System Aspects 943
  31.9.1 [peserror]PES Generation for the Servo Loop 943
  31.9.2 Timing Recovery 945
  31.9.3 Considerations on Capacity and Data Rate 946
31.10 Conclusions 948
References 948

32 **Microactuators for Dual-Stage Servo Systems in Magnetic Disk Files** 951
32.1 Design of the Electrostatic Microactuator 952
  32.1.1 Disk Drive Structural Requirements 952
  32.1.2 Dual-Stage Servo Configurations 953
  32.1.3 Electrostatic Microactuators: Comb-Drives vs. Parallel-Plates 954
  32.1.4 Position Sensing 956
  32.1.5 Electrostatic Microactuator Designs for Disk Drives 958
32.2 Fabrication 962
  32.2.1 Basic Requirements 962
  32.2.2 Electrostatic Microactuator Fabrication Example 962
  32.2.3 Electrostatic Microactuator Example Two 963
  32.2.4 Other Fabrication Processes 966
  32.2.5 Suspension-Level Fabrication Processes 967
  32.2.6 Actuated Head Fabrication 968
32.3 Servo Control Design of MEMS Microactuator Dual-Stage Servo Systems 968
  32.3.1 Introduction to Disk Drive Servo Control 969
  32.3.2 Overview of Dual-Stage Servo Control Design Methodologies 969
  32.3.3 Track-Following Controller Design for a MEMS Microactuator Dual-Stage Servo System 971
  32.3.4 Dual-Stage Seek Control Design 976
32.4 Conclusions and Outlook 978
References 979

33 **Micro/Nanotribology of MEMS/NEMS Materials and Devices** 983
33.1 Introduction to MEMS 985
33.2 Introduction to NEMS 988
33.3 Tribological Issues in MEMS/NEMS 989
33.3.1 MEMS 989
33.3.2 NEMS 994
33.3.3 Tribological Needs 995
33.4 Tribological Studies of Silicon and Related Materials 995
33.4.1 Tribological Properties of Silicon and the Effect of Ion Implantation 996
33.4.2 Effect of Oxide Films on Tribological Properties of Silicon 998
33.4.3 Tribological Properties of Polysilicon Films and SiC Film 1000
33.5 Lubrication Studies for MEMS/NEMS 1003
33.5.1 Perfluoropolyether Lubricants 1003
33.5.2 Self-Assembled Monolayers (SAMs) 1004
33.5.3 Hard Diamond-like Carbon (DLC) Coatings 1008
33.6 Component-Level Studies 1009
33.6.1 Surface Roughness Studies of Micromotor Components 1009
33.6.2 Adhesion Measurements 1011
33.6.3 Static Friction Force (Stiction) Measurements in MEMS 1014
33.6.4 Mechanisms Associated with Observed Stiction Phenomena in Micromotors 1016
References 1017

34 **Mechanical Properties of Micromachined Structures** 1023
34.1 Measuring Mechanical Properties of Films on Substrates 1023
34.1.1 Residual Stress Measurements 1023
34.1.2 Mechanical Measurements Using Nanoindentation 1024
34.2 Micromachined Structures for Measuring Mechanical Properties 1024
34.2.1 Passive Structures 1025
34.2.2 Active Structures 1028
34.3 Measurements of Mechanical Properties 1034
34.3.1 Mechanical Properties of Polysilicon 1034
34.3.2 Mechanical Properties of Other Materials 1036
References 1037

35 **Thermo- and Electromechanics of Thin-Film Microstructures** 1039
35.1 Thermomechanics of Multilayer Thin-Film Microstructures 1041
35.1.1 Basic Phenomena 1041
35.1.2 A General Framework for the Thermomechanics of Multilayer Films 1046
35.1.3 Nonlinear Geometry 1054
35.1.4 Nonlinear Material Behavior 1058
35.1.5 Other Issues 1061
35.2 Electromechanics of Thin-Film Microstructures 1061
35.2.1 Applications of Electromechanics 1061
35.2.2 Electromechanics Analysis 1063

35.2.3 Electromechanics – Parallel-Plate Capacitor 1064
35.2.4 Electromechanics of Beams and Plates 1066
35.2.5 Electromechanics of Torsional Plates 1068
35.2.6 Leveraged Bending 1069
35.2.7 Electromechanics of Zipper Actuators 1070
35.2.8 Electromechanics for Test Structures 1072
35.2.9 Electromechanical Dynamics: Switching Time 1073
35.2.10 Electromechanics Issues: Dielectric Charging 1074
35.2.11 Electromechanics Issues: Gas Discharge 1075
35.3 Summary and Mention of Topics not Covered 1078
References 1078

36 **High Volume Manufacturing and Field Stability of MEMS Products** 1083
36.1 Manufacturing Strategy 1086
36.1.1 Volume 1086
36.1.2 Standardization 1086
36.1.3 Production Facilities 1086
36.1.4 Quality 1087
36.1.5 Environmental Shield 1087
36.2 Robust Manufacturing 1087
36.2.1 Design for Manufacturability 1087
36.2.2 Process Flow and Its Interaction with Product Architecture . 1088
36.2.3 Microstructure Release 1095
36.2.4 Wafer Bonding 1095
36.2.5 Wafer Singulation 1097
36.2.6 Particles 1098
36.2.7 Electrostatic Discharge and Static Charges 1098
36.2.8 Package and Test 1099
36.2.9 Quality Systems 1101
36.3 Stable Field Performance 1102
36.3.1 Surface Passivation 1102
36.3.2 System Interface 1105
References 1106

37 **MEMS Packaging and Thermal Issues in Reliability** 1111
37.1 MEMS Packaging 1111
37.1.1 MEMS Packaging Fundamentals 1112
37.1.2 Contemporary MEMS Packaging Approaches 1113
37.2 Hermetic and Vacuum Packaging and Applications 1116
37.2.1 Integrated Micromachining Processes 1117
37.2.2 Post-Packaging Processes 1118
37.2.3 Localized Heating and Bonding 1119
37.3 Thermal Issues and Packaging Reliability 1122
37.3.1 Thermal Issues in Packaging 1122
37.3.2 Packaging Reliability 1124
37.3.3 Long-Term and Accelerated MEMS Packaging Tests 1125

37.4 Future Trends and Summary 1128
References 1129

Part F Social and Ethical Implication

38 **Social and Ethical Implications of Nanotechnology** 1135
38.1 Applications and Societal Impacts 1136
38.2 Technological Convergence 1139
38.3 Major Socio-technical Trends 1141
38.4 Sources of Ethical Behavior 1143
38.5 Public Opinion 1145
38.6 A Research Agenda 1148
References 1149

Acknowledgements 1153
About the Authors 1155
Detailed Contents 1171
Subject Index 1189

Subject Index

1, 1′-biphenyl-4-thiol (BPT) 843
4, 4′-dihydroxybiphenyl (DHBp) 843
µCP (microcontact printing) 187, 197, 834
µTAS (micro-total analysis systems) 257
γ-modified geometry 700
1,4-phenylenediamine (pDA) 916
1/f noise 387, 957
16-mercaptohexadecanoic acid thiol (MHA) 843
1-D localization
– effects 120
– theory 120
1-D to 3-D transition in magnetic field 122
1-ethyl-3-(3-diamethylaminopropyl) carbodiimide (EDC) 80, 296
2-D FKT model 638
2-DEG
– two-dimensional electron gas 438
2-D-histogram technique 647
2-amino-4,5-imidazoledicarbonitrile (AIDCN) 918
2-mercaptoethylamine HCl 478
2-pyridyldithiopropionyl (PDP) 478
3,3′-dimethyl bipyridinium 14
3-D bulk state 428
3-D coil inductor 242
3-D switching architecture 238
3-D-force measurements 358
3-nitrobenzal malonitrile (NBMN) 916

A

abrasive wear 649, 652
Abrikosov lattice 440
ABS (air-bearing surface) 968
ac electrochemical deposition 104
ac electrodeposition 103
accelerated friction 822
acceleration energy 798
accelerometer 230
– lateral 231
– packaging 1100
– test 1101
– three-axis 233
– vertical 232
– wafer fabrication 1091
acetonitrile 14, 19
acetylene (C_2H_2) 799
acid-treated SWNT 64
acoustic emission 690
actin-myosin motor 751
activation energy barrier 482
active linearization 361
active matrix electronic paper 195
active microfluidic devices 257
active microvalves 258
active structures 1028
actuated head 954
– fabrication 968
actuated slider 954, 968
– configuration 954
actuated suspension 953
actuation
– pneumatic 258
actuator
– miniaturized 986
actuator failure modes 1074
adatoms 392
addressing nanoscale bits of data 901
adenine 10
adenosine triphosphate (ATP) 741
adhesion 325, 498, 507, 515, 605, 799, 844, 930, 983
– at SAM interfaces 618
– control 832
– energy 619
– force 452, 546, 547, 552, 564, 566, 567, 619, 621
– force, quantized 558, 584
– hysteresis 567, 568, 573
– hysteresis, relation to friction 573, 576–579, 585
– influence of humidity on 850
– measurement 1011
– measurement techniques 606
– mechanics 564–566
– performance 866
– primary minimum 544, 555, 559
– promoter 188
– quantization 623
– rate-dependent 567, 568
adhesion force
– total 616
adhesion-controlled friction 571, 572, 574
adhesive
– coating 479
– interaction 732
– material 610
– surfaces 731
– wear 728
adhesive force 335, 646, 662, 867, 1004
– increase 876
– intrinsic 832
– mapping 537, 869
– measurement 503
adhesive tape film 907
adiabatic limit 482
adsorbate 404, 695
adsorbed
– insulator substrate 400
– water 875
– water film 878
adsorption 64, 79, 476
– capacity 80
– sites in MWNT 65
AES (Auger electron spectroscopy) measurement 826
AFAM (atomic force acoustic microscopy) 326
affinity maturation 316
affinity selection 297
affinity-based targeting 301
AFM (atomic force microscope) 173–175, 743, 765
– adhesion measurement 620
– *Binnig* design 333
– calculated sensitivity 355
– cantilever 332, 350, 610
– cantilever array 923
– commercial 333
– construction 288
– contact mode 331
– control electronics 362
– design optimization 348
– designs 376
– feedback loop 362
– for UHV application 635
– image 392
– imaging signal 386
– instrumentation 347
– manufacturers 333
– microscratch technique 853
– probe construction 338
– probes 378
– pull-off force 619

– resolution 375
– set-up 450, 453
– spectroscopy 458
– surface height map 817
– test 818
– thermomechanical recording 924
– tip 288, 379, 386, 450, 452, 477, 480, 1013
– tip containing antibodies 489
– tip radius 518
– tip sensor design 476
– tip size 622
AFM image
– tapping mode 914
Ag 395, 397
– on Nb(110) 429
– trimer 395
air bag sensor 1084, 1091
air damping 470
air gap capacitance 1075
air induced oscillations 348
air/water interface 479
air-bearing surface (ABS) 968
Al_2O_3-TiC head 825
Al_2O_3 54, 462, 633
– grains 508
– ultrafiltration membrane 669
Al_2O_3-TiC composite 508
Al_2O_3-TiC slider 998
$Al_xGa_{1-x}As$ 248
AlAs 248
alcohol 837
aldehydes 837
aligned carbon nanotubes 58
alignment accuracy 195
alignment of nanowires 109
alkali halides 397
alkaline phosphatase (AP) 271
alkane 835, 888, 889
alkanethiolate 187
– film 841
– on gold 187
– on palladium 187
– on silver 187
alkanethiols 404
alkylsilane film 619
all-fiber interferometer 418
all-MEMS configuration 907
all-metal cantilever 912
all-optical logic gates 21
all-optical switching network 237
alloy 662
all-silicon cantilever 926
alumina template 127
aluminum
– gates 34
– mirror array 1088
aluminum oxide 54, 462, 633
aluminum-based surface micromachining 241
AM (amplitude modulation)
– AFM 388
– mode 455
amide 838
amine 838
Amontons law 454, 517, 571, 574, 577, 580, 646, 718
amorphous
– oxide layer 106
– surfaces 544
amorphous carbon 49, 793
– chemical structure 800
– coatings 800, 806
– phase 48
amperometric time-based detection method 272
amphiphilic molecular building blocks 23
amplitude feedback 465
amplitude modulation (AM) 388, 456
– mode 331
– SFM (scanning force microscope) 433
amplitude of vibration 911
anchor group 840
AND operator 15
angle of helicity 41
angle of twist formula 355
anion-terminated tip 399
anisotropy 704
– of friction 642
annealing effect 1036
anodic alumina (Al_2O_3) 100
– oxide films 102
– templates 103
anodic bonding 1096, 1115
anodization 100
ANSYS
– analysis 1123
– stress prediction 1124
anthracene 20
– channel 21
antibiotic-resistant pathogens 293
antibody 296
– directed enzyme-prodrug therapy (ADEPTS) 301
– production 312
antibody–antigen 475
– binding 283
– complex 484
– recognition 491
antibody-coated beads 271
antiferromagnetic spin ordering 403
antigen presenting cell (APC) 312
antigen recognition 282
antimicrobial chemotherapy 293
anti-stiction
– agent (ASA) 1104
– material 1104
AP (alkaline phosphatase) 271
APC (antigen presenting cell) 312
APCVD (atmospheric pressure chemical vapor deposition) 770
apparent viscosity 888
applications
– electrical 131
arc discharge 798
areal density 900, 901, 907, 925, 932, 947, 952
Arg-Gly-Asp (RGD) 489
armchair-type SWNT 42
array
– cantilever 927
– characterization 927
– chip 923
– of aligned nanowires 115
– of nanotubes 53
Arrhenius equation 1127
artifacts 415
artificial double helix 12
as-deposited film 1035
aspect ratio 127
asperity-asperity interaction 618
as-released curvature 1059
assembled nanotube probes 378
assembly approaches 288
assembly of nanostructures 294
association process 476
atmospheric pressure chemical vapor deposition (APCVD) 770
atomic
– interaction force 452
– manipulation 419
– motion imaging 420
atomic force acoustic microscopy (AFAM) 326
atomic force microscope (AFM) 114, 288, 289, 303, 325, 331, 371, 385, 404, 476, 498, 546, 547, 549, 585, 588, 688, 717, 743, 841, 861, 862, 899, 922
atomic resolution 330, 382, 388, 389, 427, 476, 480
– imaging 391, 394–397, 462
atomic-scale
– dissipation 655
– force measurement 347

– friction 507
– hysteresis 468
– image 327, 342, 434
– roughness 721
atomistic computer simulation 398, 724
ATP hydrolysis 742
ATP(adenosintriphosphate) synthase 741
attraction
– long-range 550, 562
attractive force–distance profile 480
attractive interaction 864
Au film 771
Au microbeam 777, 778, 785
Au tip 619
Au(111) 423, 848, 850
– surface 619
Aubry transition 728
Au-coated AFM tip 619
austenite 665
average
– distance 749
– lifetime 482
– stress 1049
axial strength 672
azopyridine 19

B

backbone chain 839
backflow 261
bacmid 283
bacteriophage 744, 755
bacteriorhodopsin 742
BaF$_2$ 398
ball and spring model 724
ball grid arrays (BGA) 1113
ballistic phonon transport 126
ballistic transport 115, 121
balloon angioplasty 189
bamboo texture 52, 61
band gap tunability 128
band structure
– electronic 128
barcode reading 233
barcode tags 136
barrier-hopping 887
– fluctuations 890
basic switching operations 15
batch fabrication 249
– techniques 373
batch nanotube tip fabrication 380
B-cell epitopes 311
bc-MWNT (bamboo-concentric) 44
BDCS (biphenyldimethylchlorosilane) 849
beam
– two-layer 1045
beam bending energy 745
beam deflection 455
beam failure 775
beam-deflection FFM 633
beam-steering mirror 239
behavior
– unethical 1143
Bell's formula 483
bending
– moment 767, 783
– stiffness 349
– strength 767, 774, 775, 785
– stress 767, 781
– test 765, 766, 769
Berkovich
– indenter 765
– indenter tip 677
– pyramid 696
– tip 815
BGA (ball grid arrays) 1113
bh-MWNT (bamboo-herringbone) 44
Bi$_2$Sr$_2$CaCu$_2$O$_{8+\delta}$ (BSCCO) 431
Bi$_{1-x}$Sb$_x$ nanowires 123
bias voltage 328
biaxial strain 1042
biaxial stress 1053
BiCMOS 229
bidirectional micropump 261
bifurcation 1056
bilayer
– beam 1054
– cantilever 1046
– film 1059
– model-lipid-lubricant 889
– plate 1050
– system 1042
bimetallic catalyst 51, 62
binary compound 397
bio force probe (BFP) 480
biochemical fluids 254
biochemical reaction 262, 270
biocompatibility 263, 311
bioconjugate chemistry 295, 296
bioconjugation method 288
biofilter 271
– surface-mounted 272
biofluidic chip 273, 987
biofunctionalized cantilever 742, 743, 745
biogenic amorphous silicon shells 314
biological
– activity 316
– affinity 297
– affinity reagents 303
– device 742
– device components 304
– evolution 751
– macromolecules 299
– nanotechnology 739, 760
– self-assembly 293
biomaterials 711
biomechanics 675
biomedical device 189
BioMEMS (Biological or Biomedical Microelectromechanical Systems) 253, 262, 764, 987
– actuation 269
biomimetic valves 262
biomolecules bound to carbon nanotubes 303
biomolecules in therapeutic nanodevices 293
bio–nano interface 744
BioNEMS (Biological or Biomedical Nanoelectromechanical Systems) 764, 989
bio-sampling
– magnetic bead-based 271
biosensors 80, 302
bio-surfaces 489
biotechnology 1139
– limits of 281
biotin 80, 476
biotin-avidin 622
– spectrum 487
biotin-directed IgG 476
biotinylated AFM tip 489
biphenyl 419
bipyridine
– building block 12, 31
– centered LUMOs 26
birefringent crystal 352
bismuth nanowire 118, 134
bistability 459, 916
bit pitch (BP) 943
bit strings 938
bits per inch (BPI) 952
blister test 691
Bloch states 428
Bloch wave 427
block co-polymer 291
block-like debris 823
blood cell analysis 310
blood flow measurement 304
blood-pool agents 306
BN nanotubes 68

Bode plot 976
Bohr radius of excitons 135
Boltzmann ansatz 482
Boltzmann distribution 887
bond
– angle 67
– breakage 483
– lifetime 482
– rupture 487
– scission 623
– strength 550
bonded lubricant film 864
bonded PFPE 1012
bonding
– energy 386
– kinetics 893
– techniques 1114
bone
– lamellae 675
– lamellation 679
– tissue 675
boron
– diffusion 227
– doped Si 205
– ion implantation 330
bottom-up
– approach 99, 107, 285
– chemical strategies 10
– materials 281
– scheme 133
boundary
– element (BE) 1063
– film formation 861
– lubricant 729, 861
– lubricant film 832
– lubrication 530, 569–571, 580, 583, 585, 852, 866, 885
– lubrication measurement 507
– lubrication regime 884
– scattering effects 125
bovine serum albumin (BSA) 476
bpsi (bits per square inch) 901
BPT (1, 1′-biphenyl-4-thiol) 854, 1007
BPTC (cross-linked BPT) 1007
branched hydrocarbon lubricants 889
breakdown
– electrical 1076
bridging of polymer chains 562, 563
broken beams 777
broken coating chip 817
brush *see* polymer brush
brush-like structures 109
buckling 808, 812, 1026
– force 377
– stress 813
bulge test 691
bulk
– addressing 22
– atoms 387
– conduction band 424
– diamond 793, 801, 803
– etched silicon wafer 263
– fluid transport 261
– graphitic carbon 824
– micromachining 229
– Si wafers 205
– state 428
– viscosity 731
– xenon 436

C

C_{70} 792
C_2 moieties 51
C_{60} 32, 41, 49, 404, 647, 792
– film 330
– fullerenes 289
– island 641, 642
– multilayered film 404
– SWNT (single wall nanotube) 70
C_{60}-terminated film 843
Ca ion 399
cadherin-mediated adhesion 488
CaF_2 398
CaF_2 tip 652
$CaF_2(111)$ 399
$CaF_2(111)$ surface 399, 652
calculated tapping behavior 911
calculus of variations 745
calibration 610, 698, 699
calorimetric experiments 482
cantilever 387, 390, 457, 481
– all-metal 912
– all-silicon 926
– array 926, 927
– axis 418
– base 469
– beam 1015, 1061
– beam array (CBA) 1011
– beam model 1067
– biofunctionalized 742, 743, 745
– biosensors 303
– cell 926
– deflection 332, 372, 387, 389, 418, 465, 480, 632, 745, 848
– deflection calculation 344
– diode array 928
– driven 455
– effective mass 633
– eigenfrequency 415
– elasticity 636
– fabrication 909
– flexible 332
– foil 373
– heater 925
– material 339, 387
– motion 331, 913
– mount 336
– oscillation 457, 469
– Q-factor 433
– resonance 451
– resonance behavior 350
– resonance frequency 481, 611, 890, 1029
– sensor 925
– spring 454
– spring constant 485
– stainless steel 813
– stiffness 338, 505, 610, 926
– temperature 940
– thickness 632, 633
– tip 303, 454
– triangular 339, 349, 354
– untwisted 335
cantilever-based probes 433
capacitance detection 356
capacitive
– accelerometers 230
– detection 361
– detector 331
– displacement sensor 1033
– forces 465
– position sensing 956
– sensor 227, 230
– transducer 245
capacitor-like device 913
capacity growth 903
capillarity-driven stop valve 265
capillary
– effect on adhesion 607
– electrophoresis (CE) 255
– force 544, 559, 564, 619, 662
– force curve 617
– formation 614
– pressure 265
– stiffness 614
capsid wall 760
carbon 792
– crystalline 792
– film 865
– magnetron sputtered 799
– shells 52
– source 57
– spacer chain 853
– superactivated 77

carbon coating
– unhydrogenated 804
carbon nanofiber
– vapor grown 56
carbon nanotube (CNT) 55, 105, 287, 425, 667
– adsorption properties 76
– application 73
– catalyst-free growth 59
– catalyst-supporting materials 75
– chemical reactivity 67
– diameters 63
– FETS 303
– field emission 74
– formation 46
– growth mechanisms 59
– heterogeneity 63
– in situ filling 69
– maximum current density 74
– mechanical properties 376
– molten state filling 69
– oxidation 72
– production 46
– properties 63
– quantum wires 66
– sublimation filling 70
– synthesis conditions 61
– tip 342, 375, 376, 501
– wet chemistry filling 69
carbon–carbon distance 436
carboxyl acid 837
carboxylates (RCOO$^-$) 404
cardiovascular
– sensors 310
– system 310
– tissue engineering 310
carrier
– density 118, 122
– gas 804
– mean free path 116, 118, 121
– mobility 118
Casimir force 545
casting 186
catalysis 397
catalysis-enhanced disproportionation 54
catalysis-enhanced thermal cracking 54
catalyst 49, 106, 668
– nanoparticles 58
– preparation 54
catalyst-based SWNT 61
catalyst-free 57
catalytic chemical vapor deposition (CCVD) 52, 55, 58, 60, 61
catalytic decomposition 54
catalytically grown MWNT 673
cathode deposit 49, 51
cathodic arc carbon 806
CCVD *see* catalytic chemical vapor deposition
CCVD method 61
CDS (correlated double sampling) technique 961
CdSe nanorods 136
cell adhesion 489
cellular immune responses 311
cellular phone 904
CeO$_2$(111) 400
ceramic
– matrix composites 81
– slider 824
– tip 74
cerpacs 1101
CFM (chemical force microscopy) 73, 489, 619
chain adsorption 894
chalcogenide 906, 910, 915
change of meniscus 1005
changing of surface conditions 117
channel etching process 255
channel-liquid pair 261
chaotic mixer 266
characteristic distance 588
characteristic slip time 894
characteristic velocity 889
charge density wave (CDW) 428
charge exchange interactions 545, 552, 553
charge fluctuation forces *see* ion correlation forces
charge separation 1116
charge transfer interactions *see* charge exchange interactions
charge trapping 913
charge-controlled pull-in equation 1064
check valve design 260
chelate metal cations 12
chemical
– bond 386
– bonding 388, 863
– bonding force 331
– characterization 800
– composition 115
– detection devices 137
– force 386
– force microscopy (CFM) 73, 489, 619
– heterogeneity 568
– input 16
– interaction force 452
– sensors 74
– signal 19, 20
– synthesis 12
– vapor deposition (CVD) 104, 793
– vapor infiltration 57
chemisorption 861
chemistry route 57
chemoselective conjugation 295, 296
chemotherapy 307
chip level integration 1093
chip-on-flex (COF) 1113
clamped-clamped mechanical beams 247
classical finite size 116
classical size effect 120
clock field 946
clogging 56
closed loop sensitivity 973
clustered acetate 406
CMOS electronics 230
CMOS static random access memory (SRAM) 235
CMOS sustaining electronics 245
c-MWNT (concentric multiwall nanotube) 43, 48, 60, 67
Co clusters 425
CO disproportionation 54
CO on Cu(110) 419
coated particles 306
coating
– continuity 826
– damage 823
– failure 820
– hardness 818
– hydrophobic 1014
– mass density 801
– microstructure 800
– thickness 810, 812
coating–substrate interface 819
coefficient
– effective 647
coefficient of friction 501, 510, 516, 535, 579, 634, 771, 773, 809, 813, 823, 824, 844, 868, 872, 996, 1005
– Si(100) 531
– Z-15 531
– Z-DOL (BW) 531
coefficient of friction *see* friction coefficient
coefficient of friction relationship 343
coefficient of thermal expansion (CTE) 1124
co-energy 1064
coercivity 137

COF (chip-on-flex) 1113
cognate receptors 298
cognitive ligands 476
cognitive science 1139
coherence length 423
cohesive
– potential 759
– surface model 759
coil inductor 242
cold welding 553, 579
collagen fibers 679
collective phenomenon 885, 888
colloidal
– forces 545
– probe 548
colossal magneto resistive effect 439
comb storage device 907
comb-drive 955, 1030
– actuator 955
– resonator 245
combined AFM nanoindenter device 676
commensurate Cu(111) 728
commensurate system 723
commercial data-storage device 907
commercial MEMS devices 991
communicating
– between compatible molecular components 19
– force 748
– molecular switches 19
compact bone
– lamellae 678
– mean hardness 680
complex
– bonds 486
– dielectric function 127
– fluidic systems 886
– logic functions with molecular switches 19
component
– failure 764
– supplier 902
– surface 1009
composite 662
composite material 81
compositionally modulated nanowires 106
compression energy 887
compressive stress 805, 812, 1035, 1044
computer simulation 718
– forces 553, 557, 561, 564, 565, 585
– friction 553, 573, 574, 579, 580, 583, 585, 586, 590, 591, 594
concentration
– critical 650
concentric
– graphenes 43
– texture 61
– type (c-MWNT) 43
conditional release of therapeutics 288
conductance 117
conductance quantization in metallic nanowires 115
conducting polymers 103, 304
conductive polymeric materials 304
conductivity 136
– electrical 133
confined
– complex liquids 891
– nanostructure 68
– simple liquids 888
confinement 544, 545, 570, 584, 593
conformation 864
conformational defect 849
conforming contacts 894
connector
– miniaturized 986
constant
– amplitude (CA) 464
– amplitude FM mode 468
– current mode 328
– excitation mode (CE) 464
– force mode 362
– height mode 328, 399
constrained elastic media 1061
consumer electronics 904
consumer nanotherapeutic device 288
contact
– AFM (atomic force microscope) 455
– AFM dynamic method 662
– angle 616, 833
– angle goniometer 847
– angle of SAM 846
– conductance 649, 913
– elastic 703
– mechanics *see* adhesion mechanics
– meniscus 619
– mode 373, 909
– mode photolithography 195
– printing 186, 200, 833
– radius 678
– resistance 690
– stiffness 677, 689, 698, 701, 810, 894
– stress 872
– value theorem 575
contact area 548, 650, 651, 677, 699, 709
– apparent macroscopic 571, 576, 580
– true molecular 547, 549, 566, 571, 574–576, 594
contamination 332
continuous micropump 269
continuous stiffness measurement (CSM) 810
continuum
– analysis 753
– model 638
– theory 554, 556, 558, 559, 569, 580
contour plot 1057
contour-mode disk resonator 246
contraction 1044
contrast 435
– agent design 306
– agents 304
– enhancing agents for medical imaging 304
– enhancing nanoparticle 306
– formation 397
control
– of nanotherapeutic action 302
– of position 109
– over nanowire diameter distribution 106
– system 359, 362
– theory 1144
controlled desorption 419
controlled evaporation 269
controlled geometry (CG) 330
controlled nanoscale architecture 294
controlled substances 1140
controlled triggering of therapeutic action 298
controller design 969
CoO 402
Co-O film on PET 524
Cooper pairs 429
coordinated molecular process 886
copper adhesion 963
copper hexadecafluorophthalocyanine 196
copper tip 652, 727
corannulene 61
cores of carbon nanotubes 105
core-sheath nanowire 114

core-shell structure 132
Coriolis acceleration 232, 1095
correlated-double-sampling (CDS) 960
corrosion 1116, 1125
cost of goods (COGs) 285, 307
co-transporter 489
Couette flow 569, 593, 885
Coulomb
– force 396
– interaction 66
– law of friction 644
coupled electromechanics 1063
covalent
– bonds 10
– scaffolds 12
Cr binding layer 619
Cr coating 432
Cr(001) 427
crack spacing 524
cracks 807
creativity at the nanoscale 1135
creep 415, 691, 1125
– effect 528
– relaxation 1060
creep model
– linear 890
critical
– concentration 650
– curvature 1056
– degree of bending 1031
– load 809
– magnetic field strength 122
– normal load 853
– position 636
– shear stress 570–572, 577, 585, 586
– temperature 423, 434, 1059
– time 894
– velocity 585, 587, 590, 591
crosshair alignment 195
crosslinked BPT (BPTC) 843
crosstalk 363, 927, 1066
cross-track distance 945
cryostat 415
crystal
– growth direction 103
– orientation 206
– structure 333
– surfaces 375
crystal growth orientation, preferred 104
crystalline
– carbon 792
– silicon 254
– surfaces 544
CSM (continuous stiffness measurement) 810
CTE (coefficient of thermal expansion) 1124
CTL (cytotoxic T-cell) responses 311
Cu(001) 397
Cu(100) 640
Cu(100) substrate 728
Cu(100) tip 728
Cu(111) 423, 639, 640, 655
Cu(111) surface states 427
Cu(111) tip 653
cube corner 696, 704
culture of engineering 315
cuprates 431
current density effect 1036
current rectification 116
current-voltage characteristics 116, 916
curvature 1044
– critical 1056
– effects 723
– measured 1053
– variation 1046
curved electrode
– actuator 1070
– shape 1071
custom-designed MEMS product 1112
cut-off distance 552, 573
CVD (chemical vapor deposition) 104, 793
cyclic
– fatigue 810, 1036
– olefin copolymers (COC) 257
– thermomechanical load 1061
– voltammograms 29
cytoplasmic surface 478
cytosine 10
cytoskeletal filament 747
cytotoxic therapeutics 307
cytotoxic T-lymphocytes (CTLs) 311
cytotoxin deposition 309

D

(d, k) codes 947
D_2O 425
damage 553, 569–588
damage mechanism 818
damped harmonic oscillator 454
damping 664
– effective 470
– effects 451
– pneumatic 418
data
– lifetime 905
– rate limitation 922
– rates 948
– storage 900
– storage application 912
– storage device 922
– storage system 994
dc electrochemical deposition 103, 104
de Broglie wavelength 116
Deborah number 583
debris 823
Debye exponential relaxation 885, 892
Debye length 555, 557
decoupled design 970
decoupled track-following control 972
deep reactive ion etching (DRIE) 156, 162, 254, 963
defect motion 415
defect nucleation 702
defect production 651
defects in channel 255
deflection 457, 1054
– curve 1071
– maximum 1071
– measurement 387
– noise 433
deformation 547, 549, 1041, 1047
– behavior 1058
– elastic 450, 566, 581, 647
– of microtubule 674
– plastic 553, 580
– regime 1046
deformed beam 778
degradability 311
degrees of freedom 753
delamination 704, 804, 808, 812, 1125
delivery of therapeutics 296
Demnum-type PFPE 537
– lubricant film 869
dendrimer-based therapeutic 284
dendritic
– cells (DCs) 312
– polymers 310
density
– functional theory (DFT) 78
– modulation 730
– of defects 193, 195
density of states (DOS) 66
– electronic 133
dental enamel 711

depletion
– attraction 545, 562
– interaction 562
– stabilization 545, 562
deployment of functional biomolecules 288
deposition
– conditions 206
– rate 798
– techniques 795, 796
Derjaguin approximation 546, 557, 559
Derjaguin–Landau–Verwey–Overbeek (DLVO) theory 555
Derjaguin–Muller–Toporov (DMT)
– model 647
– theory 566
design rule 348
designed molecules 12
design-for-manufacturability 1086
design-for-volume 1086
detection 939
– circuit 939
– systems 332, 350
device
– architectures 288
– components communication 304
– design 280
– electronic 133
– fluidic 253
– molecule-based 24, 28
– scaling 989
dewetting 868, 1003, 1013
DFM (dynamic force microscopy) 433, 471, 490, 501
DFS (dynamic force spectroscopy) 484
DHBp (4, 4′-dihydroxybiphenyl) 843, 854, 1007
diameter-dependent 116
diamond 67, 373, 379, 673, 698, 792
– coated cantilever 914
– coating 804, 833
– film 793
– like amorphous carbon coating 800
– like carbon (DLC) 524, 1003
– powder 51
– tip 504, 651, 662, 676, 814, 819, 841, 866, 999
diatoms 314
diblock copolymers 102, 103, 138
dicationic BIPY 17
dielectric
– breakdown 691
– capacitance 1075
– charging 1074
– function 127, 129
differential scanning calorimetry (DSC) 664
differential-drive configuration 955
diffuser micropumps 261
diffusion 1061
– based extractor 266
– coefficient 265, 865
– flame synthesis 58
– limited reaction 893
– parameters 420
– thermally activated 415
diffusive
– communication 750
– relaxation 482
– transport 115, 116
digital
– feedback 362
– light processing (DLP) 987
– micromirror device (DMD) 235, 987, 992
– signal processor (DSP) 328
– transmission between molecules 20
dilation 573, 584, 586, 593
dimension 387
dimensions of spatial structures 747
dimer structure 394
dimer-adatom-stacking (DAS) 392
Diophantine equation 973
DIP (dual in-line packaging) 1118
dip coating technique 863
diphtheria toxin (DT) 300
dipole molecule 834
dip-pen nanolithography (DPN) 175, 288
diprotic acid (11-thioundecyl-1-phosphonic acid) 621
direct overwriting 938
direct parallel design 970
direct write electron beam/focused ion beam lithography 186
directly growing nanotubes 379
discontinuous sliding motion 887
disjoining pressure 871
disk drive
– manufacturer 902
– servo control 968
dislocation
– line tension 704
– motion 570
– nucleation 696
dispersion
– force 406
– mixing 266
displacement 1047, 1057
– amplitude 930
– calibration 612
– controlled scanning probe 610
– field 1055
– maximum 1070
– resolution 681
– vertical 779
display
– paper-like 193
disposable biosensors 274
disposable plastic lab-on-a-chip 993
dissemination of biological information 315
dissipated power 939
dissipation 468
– force 461
– measurement 631
dissipative tip-sample interaction 468
dissociation 476
distortion 360
distributed
– Bragg reflector (DBR) 199
– feedback (DFB) 199
– laser resonators 199
dithio-bis(succinimidylundecanoate) 476
dithio-phospholipids 479
D-L amino acids (aas) 291
DLC 1012
– coating 524, 794, 796, 809, 819, 826, 1008
– coating microstructure 812
DLP technology 1088
DLVO interactions 549, 555–558
DMD (digital mirror device)
– fabrication 1088
– manufacturing 1095
– packaging 1100
DMT (Derjaguin–Muller–Toporov)
– model 695
– theory 724
DNA 404, 464, 467, 476, 747
– analysis 272
– analysis system 265
– nanostructure 294
– nanowire 33
– packing 756
domain
– pattern 439
– re-orientation 913
donor impurity concentration 127

doped
– anode 49
– polysilicon film 1001
– silicon 996
– silicon wafer 31
DOS structure 423
double barrier resonant tunneling 124
double-layer
– force 621
– interaction 545, 555–557
double-wall nanotubes (DWNTs) 51
doubly clamped beam 1028
doxorubicin 308
DRAM 923
Drexler 1146
DRIE (deep reactive ion etching) 156, 162, 166, 168–170, 254, 954, 963
dried tissue properties 676
drive amplitude 470
drive current
– maximum 976
driven cantilever 455
driving frequency 351
driving/sensing circuit integration 960
drug
– delivery 285
– resistant organism 293
– targeting 297
dry
– etching 205
– nitrogen environment 999
– (plasma) etching 254
– thermal oxidation 286
dry surfaces 571, 587
– forces 550, 552
– friction 571, 576, 588, 589
dual-axis gyroscope 233
dual-in-line packaging (DIP) 1118
dual-stage
– configuration 952
– sensitivity 973
– servo system 953
– short span seek 977
Dupré equation 569
DWNT (double-wall nanotubes) 51
dynamic
– interactions 544–546, 570, 581, 584
– mode 331
– operation mode 388
– oscillation force 456
– spectral analysis 891
– states of friction 894
– viscosity 264
dynamic AFM 387, 453–455, 461, 468, 469
dynamic force microscopy (DFM) 457, 471, 490, 501
dynamic force spectroscopy (DFS) 484
dynamic friction *see* kinetic friction

E

E. coli
– bacterium 748
– cells 756
early failure 1126
early tumor detection 310
EBD (electron beam deposited) tips 376
ECR (electron cyclotron resonance) CVD 795, 815, 1009
– coating 822
EDP (ethylene diamine pyrocatechol) 254
EELS (electron resonance loss spectroscopy) 800
EFC (electrostatic force constant) 678
effect of surface roughness 779, 781
effective
– coefficient of friction 647
– damping constant 470
– force gradient 463
– ligand concentration 485
– mass 433
– medium 127
– medium theory 127
– shear stress 648
– spring constant 637, 645, 721
– structural stiffness 1053
– tether length 485
– viscosity 583, 593, 885
effects of doping and annealing 120
EHD
– induction type 262
– injection type 262
eigenstrain 1041
elastic
– contact 703
– energy 732
– force 727, 757
– Frenkel–Kontorova chain 727
– Hamiltonian 755
– instabilities 727
– mismatch 1051, 1056
– modulus 664, 698, 767, 770, 774, 805, 806, 809
– properties 673
– properties of ssDNA 746
– stiffness coefficient 1048
elastic deformation 450, 647
– long-range 722
elasticity 433, 663
– of DNA 757
– two-dimensional 754
elastic-plastic deformation 785
elastohydrodynamic lubrication 569, 570, 581, 583
elastomer precursor 256
elastomeric stamp 190
electric charging 913
electric field gradient microscopy (EFM) 114
electric force gradient 338
electrical
– applications 131
– breakdown 1076
– conductivity 133
– isolation 956
– surface passivation 1103
electric-arc
– method 61
– reactor 48
electroactive
– fragments 14
– layer 24
– solids 22
electrochemical
– AFM 338
– cell 24
– degradation 304
– deposition 103, 675
– detection 270
– etch 383
– etching 373
– immunosensor 272
– STM 330
electrochemically etched tips 383
electrode
– arrays 26
– geometry 1076
– pair 1077
electrodeposition 103, 153, 180
electrodes with molecular layers 27
electrohydrodynamic (EHD) pumping 261
electroless deposition 188
electro-luminescence (EL) 132, 135
electrolytic
– conduction 1116

– method 57
electromagnetic
– actuators 259
– forces 550
– microvalves 259
electromechanical
– coupling 245
– load 1040
– mirror 1069
electromechanics
– analysis 1063
– application 1061
– test structure 1072
electromigration 419
electron
– beam deposition (EBD) 376
– cyclotron resonance chemical vapor deposition (ECR-CVD) 795, 799
– energy loss spectrometer (EELS) 113
– energy loss spectroscopy (EELS) 798
– Fermi wavelength 116
– field emission 133
– interactions 428
– mean free path 115
– scattering 120
– tunneling 327
electron-beam lithography 674
electronegativity 834
electron-electron interaction 423
electronic
– band structure 128
– density of states 133
– device 133
– ink 195
– newspaper 196
– noise 333
electron-phonon interaction 428
electro-optical modulation 136
electro-osmosis (EO) 261
electro-osmotic
– flow (EOF) 255
– pumping 260
electroplated microactuator 966
electroplating 153, 1113
electro-rheological fluid 260
electrostatic
– actuation 236, 244, 248
– binding 478
– coupling 1063
– discharge (ESD) 1098
– interaction 393, 402, 464
– microactuator 952
– micromotor 1061
– potential 398, 438
– short-range interaction 398
– spring constant 956
electrostatic force 386, 437, 544–558, 1062, 1103
– constant (EFC) 677
– interaction 393
– microscopy 438
electrostatically actuated devices 258
electrostatic-induced errors 1098
embedded atom method (EAM) 720
embedded system 721
embossing 833
– technique 191
end caps 47
end deflection 1026
end group 864
endofullerene 71
endothelial cell surfaces 488
energy
– barrier 482
– conservation 469
– dissipation 468, 567–569, 572–575, 578, 587, 654, 849
– elastic 732
– electrical 1063
– mechanical 1063
– resolution 422
– scales 750
– separation between subband 115
– total 1063
energy dispersive X-ray spectrometer (EDS) 113
engineered nanostructures 13
engineering materials 758
enhanced permeability and retention effect (EPR) 307
entangled states 570
entanglement 622, 886
– strength 886
entropic force 564
entropically
– confined systems 891
– cooled layer 888
entropy
– structural 886, 887
environmental shield 1087
enzymatic cleavage 287
enzymatic prodrug activator 301
enzymes 482
epitaxial silicon seal 1114
epitaxy 152, 170, 172
epitope mapping 491
epoxy bonding 1115
EPR tumor targeting 310
equibiaxial
– deformation state 1050
– stress distribution 1051
equilibrium
– equipartition 720
– interactions *see* static interactions
– true (full) or restricted 562
equivalent mechanical circuit 1073
erasing mechanism 936
ESD protective circuitry 1098
ester 837
etching 186, 1041
ethanolamine 477
ether 837
ethical rule violation 1143
ethics of nanotechnology 1138
ethylene diamine 287
ethylene diamine pyrocatechol (EDP) 254
Euler
– buckling criterion 1026
– equation 349
Euler–Bernoulli beam equation 1063
eutectic bonding 1115
evolution of curvature 1059
examples of NEMS 988
exchange
– force 402
– force interaction 402
– interaction energy 402
exchangeable carrier plate 636
excitation
– external 456
excitation amplitude 461
exciton 127, 136
– binding energy 135
– confinement 135
– laser action 135
extended exponential Kohlrausch relaxation function 892
external
– excitation 456
– excitation frequency 466
– noise 415
– normal load 867
– triggering 284
– vibrations 329
extraction of mechanical properties 1073
extravasation 297, 307
extrinsic stress 1041
Eyring
– model 644, 887, 890
– theory 887

F

Fab molecule 476
fabrication
– of membrane 314
– of microfluidic systems 254
– of mold masters 255
– techniques 254
– technology 225
face-centered cubic (fcc) 792
faceted 109, 111, 135
failure
– density function 1125
– mechanism 825, 1125
– mode 1101
– mode effect analysis (FMEA) 1101
– of MEMS/NEMS device 1012
– rate 1126
Fano resonance 425
fatigue 810
– behavior 769
– crack 776, 823, 1125
– damage 810
– failure 1036
– life 809
– measurement 1032
– properties 768, 776
– resistance 1028
– strength 776
– test 776, 813
fatty acid monolayer 841
FC (flip chip) technique 1113
FCA (filtered cathodic arc) 815
– coating 806, 811
$Fe(NO_3)_3$ 381
feasible simulation
– maximum 719
Fe-coated tip 403
feedback
– architecture 228
– circuit 333, 464, 465
– loop 363, 373, 450, 456, 461, 465, 485, 634, 957
– network 327
– signal 388
Fe-N/Ti-N multilayer 675
FeO 402
Feridex 306
Fermi
– energy 122
– level 33, 422
– points 428
ferrocene 59
– hydrophobic 24
ferroelectric film 913
ferromagnetic
– particles 305
– probe 439
– tip 441
FE-SEM image 136
FFM (friction force microscopy) 632
– dynamic mode 652
– on atomic scale 644
– tip 507, 636, 639
FIB (focused ion beam) tips 376
fiber
– optic telecommunication 233
– optical interferometer 352
– optics 299
FIB-milled probe 342
FID
– free induction decay 305
field
– emission 910
– emission tip 378, 910
– emission-based display 58
– emission-based screen 74
– ion microscope (FIM) 452
field-effect transistor (FET) 85, 116, 132, 137, 289, 290, 302
figure of merit 133
filled nanotube 69
filling efficiency 71
film/substrate system 1045
films on substrate 1023
film–substrate interface 1035
film–substrate system 1060
filtered cathodic arc (FCA) deposition 796–811
filtering 246
FIM (field ion microscope) 452
– technique 464
finite
– difference (FD) 1063
– element (FE) 1063
– element analysis 778
– element method (FEM) 764, 1049
– element modeling (FEM) 699
– size effect 131
first generation NEMS devices 247
first principle calculation 396
first principle simulation 434
FKT (Frenkel–Kontorova–Tomlinson)
– model 637
flagellar motor rotation rate 750
flap type valves 261
flash memory 899, 904–907
flat punch 697
flavin adenine dinucleotide (FAD) 303
flavoenyzme glucose oxidase (Gox) 303
flexible cantilever 332
flexible electronic devices 193
flip chip technique (FC) 1113
floating catalyst method 55
flocculation 555
Flory temperature 561
flow
– activation energy 865
– laminar 264
– rate 269
– resistance 266
fluid mosaic membranes 293
fluidic
– devices 253
– motion 270
– sampling 253
fluorescence
– quantum yield 17
– spectroscopy 127
fluoride 397, 398
fluoride (111) surface 400
fluorinated DLC 833
fluorinated silane monolayer 190
FM (frequency modulation)
– AFM 464
– AFM images 435
– mode 461
FMEA (failure mode effect analysis) 1101
focused ion beam (FIB) 330, 342, 376, 693, 709
foil cantilever 373
Fokker–Planck 891
folded protein structures 293
force
– advection 266
– and displacement calibration 618
– between macroscopic bodies 551, 556
– between surfaces in liquids 554
– calibration 610, 632
– calibration mode 526
– calibration plot (FCP) 867, 1003
– cantilever-based 433
– constant 618
– curve 382
– detection 348
– distribution 1043
– effective gradient 463
– elastic 727, 757
– extension curve 744
– induced unbinding 487

– long-range 389, 398, 437
– mapping 490
– measurement 387
– measuring techniques 546, 547, 549
– modulation mode (FMM) 663
– modulation technique 505
– packing curves 758
– repulsive 480
– resolution 433, 481
– scales 750
– sensing tip 358
– sensitivity 481
– sensor 332, 389, 635
– spectroscopy (FS) 362, 434, 436, 476
– titration 621
– undulation 545, 564
– velocity curve 752
force field spectroscopy
– three-dimensional 437
force-displacement
– curve 608, 677, 681
– plot 607
force-distance
– calibration 848
– curve 338, 451, 456, 621, 662, 668
– cycle 480
– diagram 469
form factor 900, 907
formate
– covered surface 405
– (HCOO$^-$) 404
formation of SAM 840
four helical bundle proteins 316
four-quadrants photodetectors 632
Fowler–Nordheim
– equation 1076
– plot 1077
– tunneling 905
fractal
– mobility 892
– space 891
– time 892
– time dependence 893
fracture 704, 1124, 1125
– strength 1036
– stress 767
– surfaces 777
– toughness 765, 767, 771, 775, 806, 807, 809, 810, 818
– toughness measurement 1027, 1030
Frank-Read source 703
free carrier density 127
free induction decay (FID) 305
free surface energy 874
freezing-melting transitions 588, 590, 886
Frenkel–Kontorova–Tomlinson (FKT) 637
– elastic chain 727
– model 725
frequency
– measurement precision 358
– modulation (FM) 388
– modulation (FM) mode 331
– modulation AFM (FM-AFM) 389
– modulation SFM (FM-SFM) 415
– shift calculation 390
– shift curve 463, 464
friction 325, 498, 507, 515, 606, 618, 631, 717, 793, 844, 983
– anisotropy 642
– characteristics 1009
– coefficient 569–572, 576, 577, 579, 580, 583, 590, 592, 593, 886
  load dependence 518
– control 832
– directionality effect 512
– effect of humidity on 515
– effect of tip on 515
– experiments on atomic scale 638
– global internal 667
– image 640
– kinetic 571–573, 583, 585–587, 589, 590, 593, 718, 728, 729, 884, 885
– lateral 453
– loop 637, 638, 649
– macroscale 842, 998
– macroscopic 732
– map 583, 640
– measurement 1033
– measurement methods 342
– measuring techniques 547, 548, 576, 583, 585
– mechanism 510, 723, 843, 848, 871, 1013
– molecular dynamics simulation 651
– performance 866
– rate experiments 888
– scale dependent 518
– torque 1015
– torque model 1014
– total 726
friction force 331, 335, 501, 516, 642, 813, 843, 850, 866, 1004, 1005
– calibration 335, 346
– curve 363
– decrease of 875
– image 845
– kinetic 722
– magnitude 345
– map 511, 648
– mapping 869
– microscope (FFM) 325, 498, 499, 841
– microscopy (FFM) 537, 631, 632
– Z-15 531
– Z-DOL (BW) 531
friction models
– cobblestone model 572, 574
– Coulomb model 572
– creep model 589
– distance-dependent model 589
– interlocking asperity model 572
– phase transitions model 587, 589, 590
– rate-and-state dependent 590
– rough surfaces model 588
– surface topology model 588
– velocity-dependent model 587, 589
fringe detector 1028
fringing field 1068
frustules 314
fullerene 41, 792
fullerene-like structure 49
fullerite 42
functionalized nanotube 71, 72
fundamental resonant frequency 350
fused silica 699, 700, 704
– hardness 678
fusion bonding 1114

G

GaAs 248
– stamp 191
– wafers 192
GaAs/AlGaAs
– heterostructures 438
– quantum well heterostructures 248
gage marker 1028
gain 465
gain control circuit 389
GaN nanowires 135
gap stability 327
GaP(110) 435
gas separation 79
gate potential
– floating 905

gauche defect 622
Gaussian
– fluctuation–dissipation relation 889, 891
– statistics 884, 891, 892
Gd on Nb(110) 429
Ge membranes 210
gear
– miniaturized 986
generalized actuator 1064
genetic engineering 1142
genomic libraries 756
genuine graphite 40
geometric
– interlocking 724
– nonlinearity 1054
– parameters 228
– restrictions 249
geometry effects in nanocontacts 646
germanium 705
g-factor 424
giant magnetoresistance (GMR) 900
gimballed microactuator design 959
gimbal-mounted mirror 1097
GIO (grazing impact oscillator) 911
glass 619
– bulk etching 255
– frit bonding 1096
– frit sealing 1093
– transition 894
– transition temperature 256, 570, 579, 665
glassiness 593
glass-like behavior 891
glass-to-glass direct bonding 271
glass-to-silicon package 1127
global internal friction 667
glucose oxidase (GOD) 274
GMR
– giant magnetoresistance 900
gold 330
– coated tip 476
– electrodes 27
– film on polysilicon substrate 1051
– nanowires 136
– to-silicon eutectic bonding 1120
Grahame equation 555
grain
– boundary 553, 1035
– boundary scattering 120, 121
– size 189, 793
graphene 40, 63, 667
– defect 70
graphite 415, 417, 507, 638, 651, 792
– cathode 798
– pellet 47
– surface 463
graphite(0001) 427
gratings 200
grazing impact oscillator (GIO) 911
Griffith fracture theory 778
grinding 382
growth
– by pressure injection 102
– of nanotubes 668
guanine 10
gyro
– packaging 1100
– test 1101
gyroscope 230, 232, 1094

H

H_2O 425
Hagen–Poiseuille equation 264
half-generation precursor 287
Hall resistance 438
Hall–Petch behavior 710
Hamaker constant 386, 464, 551–577, 621, 871
Hamilton–Jacobi method 390
hand-held biochip analyzer 274
handling damage 1105
haptenization 313
haptenized nanostructure 313
hard amorphous carbon coatings 795
hard disk drive (HDD) 899–907, 952
– head 901
– performance 903
hard disk drive technology
– limits for 904
hard-core or steric repulsion 545
hardness 504, 770, 800, 802, 805, 809, 1024
harmonic oscillator 454
harpooning interaction 545, 553
HARPSS 166, 169, 170
HDT (hexadecanethiol) 188, 843, 854, 1006, 1012
head
– displacement 953
– gimbal assembly (HGA) 971
– group 839
– position 969
health care 1141
heat
– curable prepolymer 186
– dissipation 1122
– pipe cooling 1123
– transfer model 1119
heater
– cantilever 925
– temperature 934
heavy ion bombardment 441
heavy metal toxicity 306
helicity 41
helper T-cell epitopes 311
hermetic
– packaging 1116
– seal 1112
herringbone
– MWNT 44, 60, 76
– texture 61
Hershey–Chase experiment 755
Hertz model 694
Hertzian contact model 695
Hertz-plus-offset relation 647
heterodyne interferometer 351
heterogeneous CCVD 53
hetero-nanotube 68
hexadecanethiol (HDT) 188, 843, 854, 1006, 1012
HexSil 166, 168, 169, 954
– micro-molding process 962
hierarchical arrangement 108
hierarchy
– of structures 747
– of temporal processes 749
high modulus elastomer 188
high quality manufacturing 1087
high reflectivity 136
high speed scanning 467
high temperature conditions 61
high temperature superconductivity (HTCS) 419, 431, 440
high volume production 1093
high-aspect-ratio
– MEMS (HARMEMS) 986
– tips 376, 377
high-definition television 235
higher orbital tip states 422
highest resolution images 382
highly ordered monolayers 187
highly oriented pyrolytic graphite (HOPG) 337, 507
high-performance material 1141
high-resolution
– electrodes 196
– FM-AFM 436
– image 305
– imaging 407

– MR images 305
– patterning 193
– printing 186
– spectroscopy 422
– stamps 186
– tips 379
high-temperature operation STM 417
Hill coefficient 488
hinged cantilever 1034
HiPCo process 56
HiPCo technique 48
h-MWNT (herringbone) 44, 60, 76
homodyne interferometer 351
honeycomb
– chained trimer (HCT) 395
– lattice 68
– pattern 399
Hooke's law 433, 450, 454, 469, 480
horizontal coupling 329
host immune responses 311
hot embossing 257
HtBDC (hexa-tert-butyl-decacyclene) on Cu(110) 420
HTCS (high temperature superconductivity) 419, 431, 440
Huber-Mises 695
human bone tissue 675
humanity 1136
humidity 645
– effect 1105
hybrid
– carbon nanotube 68
– manufacturing 1093
– nanotube tip fabrication 380
hybridization 41, 397
hydration forces 545–575
hydration regulation 560
hydrocarbon 53, 57, 835
– chains 731
– precusors 799
– unsaturated 836
hydrodynamic
– forces 545, 549
– lubrication 729, 884
– radius 561
hydrofluoric (HF) 832
hydrogen 394
– bonding 10, 561
– bonding force 622
– concentrations 804
– content 804
– end group 841
– flow rate 805
– in carbon nanotube 77
– sensor 137
– storage 77
– storage capacity 78
– termination 394
hydrogenated carbon 800
hydrogenated coating 800
hydrophilic
– control 262
– surfaces 544, 560
– tip 616
hydrophobic
– coating 1014
– control 262
– ferrocene 24
– force 559, 560
– surfaces 544, 560
– tip 616
hydroxyl polymethacrylamide (HPMA) 308
hydroxylated surfaces 29
hydroxylation 840
hydroxyl-terminated perfluoropolyether 892
Hysitron 676
hysteresis 360, 382, 388, 415, 439, 459, 469, 681
– loop 333, 363

I

IB (ion beam)
– coating 822
IBD (ion beam deposition) 796, 798, 815
IC (integrated circuit) 226, 988
– industry 1112
– package technology 1101
– packaging 1112
ideal nanobiological devices 282
IFM (interfacial force microscope) 610
IgG
– repetitive 484
image
– effects 710
– processing software 364
– topography 331, 406
image projection 1100
– system 1084
imaging
– bandwidth 339
– electronic wave functions 427
– signal noise 389, 391
– tools 111
immunoassay
– magnetic bead-based 271
immunogenic synthetic nanomaterials 313
immunoisolation 286, 313
immunosensor 271
immunosuppression 313
immunosurveillance 313
impregnation method 54
imprinted polymers 200
in situ
– environmental TEM chamber 112
– screening 137
– sharpening of the tips 328
in vivo properties 676
InAs 417
InAs(110) 423, 435
incipient wetness impregnation 76
incommensurate surface 725, 731
indentation 498, 526, 923, 932, 935, 936
– creep process 528
– depth 527, 678, 806, 809, 998
– fatigue damage 812
– hardness 325, 527
– induced compression 812
– modulus 679
– size 527, 924
– size effect (ISE) 704
– technique 765
independent molecular operators 19
indirect sensor-device coupling 304
indirect transition in bismuth 129
indium tin oxide (ITO) 193
induction type EHD 262
inductive heating 1119
inelastic tunneling 419
inertial sensor 229
infected cell 756
influence of humidity
– on adhesion 850
information technology 1139, 1142
initial contact 703
injection type EHD 262
ink
– electronic 195
ink jet printing 193
inorganic-organic solar cells 136
InP(110) 392
in-phase signal 944
in-plane
– actuation 929
– mechanical strain 188
instability position 461
instability, jump-to-position 388, 610

instrumented suspension 967
insulator 397
insuline pump 269
integrated
– circuit (IC) 226, 988
– MEMS 259, 1084, 1092
– MEMS accelerometer 1091
– micromachining process 1117
– silicon suspension 967
– suspension 967
– tip 341, 373
– vacuum sealing 1117
Intel 915
intellectual property protection 1137
interaction
– energy 757
– force 434, 757
– potential 718
interatomic
– attractive force 344
– bonding 393
– force 332
– force constants 387
– interaction 1035
– spring constant 332
interbulk interactions 728
intercalated MoS_2 833
intercellular adhesion molecule-1 (ICAM-1) 489
intercellular concentration 748
intercept length 855
interchain hydrogen bonding 621
interchain interactions 484
interconnect 900
interconnect technology 1094
interconnected operators 18
interdiffusion 568
interdigitation 568
interface sensor components 302
interfacial
– chemistry 607
– defects 813
– energy (tension) *see* surface energy (tension)
– force microscope (IFM) 610
– friction *see* also boundary lubrication, 571–574, 579, 580, 585, 862
– liquid structuring 888
– potential 726
– stress 819
– structuring 888
– wear 606
interferometeric detection sensitivity 353
interlocking macrocycles 26
intermediate or mixed lubrication 569, 570, 582, 583
intermittent contact mode 373, 460
intermolecular communication 18
intermolecular force 289, 481, 484, 606
internal friction 935
internal stress 1025, 1041
intersymbol interference 947
intertube distance 43
intraband transitions 423
intramolecular
– forces 484
– self-assembly 293
intrinsic
– adhesive force 832
– damping 469
– mean stress 1045
– stress 804
iodine 419
iodobenzene 419
ion
– correlation forces 554, 557
– displacement 398
– implantation 205, 528, 925, 996
– implanted silicon 997
– plating techniques 795
– source 798
ion beam
– deposition (IBD) 796, 798
– etching 248
– sputtered carbon 798
ion correlation forces 545
ionic bond 545
ionic strength 619
Ising spin model 892
isolated nanotubes 381
isotropic etching 189
isotropic layer 1050
itinerant nanotube levels 425
ITO (indium-tin-oxide) 195
I–V characterization 116, 124

J

JKR (Johnson–Kendall–Roberts)
– model 619, 621, 695
– relation 646
– theory 566
Joule
– dissipation 655
– heating 439
jump length distribution 889
jump-to-contact 388, 436, 452
junction area 132, 135

K

KBr 397
KBr(100) 640, 650
$KCl_{0.6}Br_{0.4}(001)$ surface 398
Kelvin
– equation 564, 612
– radius 613, 614
Kelvin probe force microscopy (KPFM) 407, 503
ketones 837
key scale at bio-nano interface 746
kidney exclusion limit 296
kinesin 741, 745
kinetic
– friction 571–573, 583, 585–587, 589, 590, 593, 718, 728, 729, 884, 885
– friction force 722
– friction ultralow 591
– measurements 892
– off-rate 487, 488
– processes 703
– rate constant 482, 486
kinetics 883
– of capillary formation 614
Kirchoff hypothesis 1047
knife-edge blocking 361
Koanda effect 266
KOH 330
Kohlrausch
– exponent 892
– relaxation 884
Kondo
– effect 414, 425
– temperature 425
K-shell EELS spectra 802

L

L amino acid 291
lab-on-a-chip 270, 988
– application 270
– concept 253
– disposable plastic 993
– systems 265
– technology 255
lac repressor 754
Lagrangian approach 1064
Lamb waves 693
laminar
– flow 264
– flow characteristics 266
laminated n-channel transistor 196
Landau
– levels 122, 415, 438

– quantization 424
Langevin equation 891, 892
Langmuir–Blodgett (LB) 861
– deposition 536, 833
– film (ethyl-2,3-dihydroxyoctadecanoate) 467
– methodology 35
Laplace
– force 844, 868
– pressure 544, 564, 613–618, 832
– pressure force 616
large angular deflection 1069
large array of nanowires 109
larger-scale systems 1136
large-scale stick-slip motion 733
Larmor frequency 305
laser
– ablation method 61
– beam deflection method 453
– deflection sensing 453
– deflection technique 333
– devices 46
– interference lithography 186
– vaporization method 61
– welding 1119
laser-to-fiber coupler 236
lateral
– accelerometer 231
– contact stiffness 631
– cracks 693
– deflection 671
– deflection signal 1016
– displacement 669
– force 632, 643, 669, 718, 1015
– force calculation 354
– force microscope (LFM) 325, 499, 632
– force microscopy (LFM) 187, 404, 548
– friction 453
– resolution 328, 331, 477, 500, 606, 663
– resonator 1037
– scanning range 929
– spring constant 338, 636
– stiffness 362, 376, 649
lattice
– constant 725
– imaging 332
– vibration 726
layer of resist 186
layered structure 1045
LCC (Leadless Chip Carrier) 1101
leakage 1126
– rate 263
learning theory 1143
length scale 722, 747
Lennard-Jones potential 436, 457, 719, 730
Lennard-Jonesium 727
leukocyte function-associated antigen-1 (LFA-1) 489
leveraged bending 1070
levers 932
lever-sample displacement 608
levitated copper inductor 242
Lévy flight model 891
LiF 397
LiF(100) surface 652
life-cycle costs 1137
lifetime broadening 419, 423
lifetime-force relation 485
Lifshitz theory 551, 552, 554
lift mode 338, 503
LIGA 166–168, 986
– fabrication of MEMS 987
– technique 765
ligand concentration
– effective 485
ligand-receptor affinity 288, 316
ligand-receptor interaction 476
light beam deflection galvanometer 353
light emission 135
light-emitting diode (LED) 132, 135
limits for hard disk drive technology 904
limits of biotechnology 281
linear
– creep model 890
– fractional transformations (LFT) 975
– friction–velocity dependence 889
– quadratic Gaussian (LQG) 971
– recording density 947
– stress gradient 1045
– variable differential transformers (LVDT) 361
lipid 747
lipid film 644
liposome 742
liquid
– capillaries 612
– capillary condensation 844
– film meniscus 612
– film thickness 537, 885
– helium 415
– helium operation STM 417
– lubricant 530, 832
– lubricated surfaces 572, 576, 578, 587
– mediated adhesion 832
– nitrogen (LN) 416
– perfluoropolyether (PFPE) 1003
– solid interface 832
– vapor interface 832
load
– critical 809
load contribution to friction 572–574
load dependence of friction 647
load-carrying capacity 824
load-controlled 610
load-controlled friction 571, 579
load-displacement 528
load-displacement curve 774, 778, 808, 809
loading curve 701
loading rate 483
local deformation 504, 518
local deformation of material 524
local density of states (LDOS) 422
local mechanical spectroscopy 664
local pinning 727
local shear stress 731
local stiffness 362, 1006
localization
– effect 122–125, 134
– theory 120
localized heat bonding 1116–1120
logarithmic-like friction–velocity behavior 885
logic
– devices 132
– gates 14, 15, 132
– protocols 15
Lognormal distribution 1127
London
– dispersion interaction 545, 550, 552
– penetration depth 431, 440
longitudinal
– magnetoresistance 120, 121
– piezo-resistive effect 356
– relaxation time (T_1) 305
long-range
– attraction 550, 562
– elastic deformation 722
– force 389, 398, 437
– tip-molecule force 406
long-term
– measurements 414
– memory 734
– reliability 1126
– stability 414, 948, 1102

– test 1125
loop-transfer recovery (LTR) 971
loss modulus 702
lot-to-lot variation 1072
low cost gyroscope 1094
low pressure chemical vapor deposition (LPCVD) 770
low temperature
– AFM/STM 332
– condition 60
– NC-AFM 402
– SFM (LTSFM) 417
low-cycle fatigue resistance 1032
lower lasing threshold 135
low-noise measurement 636
low-temperature microscope operation 414
low-temperature scanning tunneling spectroscopy (LTSTM) 419
low-temperature SPM (LTSPM) 414
LPCVD (low pressure chemical vapor deposition) 770, 962, 1034
– nitride sealing 1117
LTR
– loop-transfer recovery 971
LTSFM 417
LTSTM 419
lubricant 723
– atoms 732
– film 618
– meniscus 864
– spreading 864
– thickness 885
lubricated sliding 884
lubrication 717
– elastohydrodynamic 569, 581, 583
– intermediate or mixed 569, 570, 582, 583
– method 995
lumped
– parameter 1065
– parameter model 1063, 1073
Luttinger liquid 66
LVDT
– linear variable differential transformers 361

M

macrocyclic polyether 13, 25
macromolecular
– building block 747
– interaction 475
macromolecules as elastic rods 753
macroscale friction 842, 998
macroscopic
– building blocks 10
– friction 732
magnetic
– actuators 259
– applications 137
– dipole interaction 403
– disk 824
– disk drive 794
– information 138
– Ni 431
– ordering 129
– particles
self-ordered arrays 914
– quantum flux 440
– recording 911, 922
– storage device 795, 831
– tape 466, 513, 524, 862
– thin-film head 825
– tip 465
magnetic field
– critical strength 122
– length 122
– microscopy (MFM) 114
– triggering 299
magnetic force 386
– gradient 338
– microscope (MFM) 338
– microscopy (MFM) 326, 439
magnetic resonance
– force microscopy (MRFM) 441
– imaging (MRI) 304
magnetically coated tip 490
magnetohydrodynamic (MHD) pumping 261
magnetomotive transduction 248
magneto-optics 128
magnetoresistance 120
– longitudinal 120, 121
– transverse 121
magnetoresistive RAM (MRAM) 899, 906
magnetostatic interaction 439
magnetron sputtered carbon 799
major histocompatibility complex (MHC) 311
manganites 431
manifold absolute pressure (MAP) 1091
manipulation of individual atoms 325
manually assembled MWNT tips 378
manufacturability 1087
manufacturing “risk” change 1093
MAP sensor 1094
marginal dimension 727
martensite 665
mask, high resolution stamp 186
mass
– effective 433
mass of cantilever 331
master–slave design 970
material
– for microfluidic devices 254
– hardness 765
– molecule-based 35
– property variation 1072
– structural 1028
Matthiessen rule 120
maximum likelihood estimator (MLE) 1126
MBE (molecular beam epitaxy) 152, 172
MBI (multiple beam interferometry) 547
mean time to failure (MTTF) 1127
mean-field theory 556
measurement of hardness 505
mechanical
– coupling 588
– dissipation in nanoscopic device 631
– instability 452, 609
– micropumps 260
– protection 1112
– relaxation 457, 848
– resonance 591
– spectroscopy 664
– stability 927
– surface relaxations 468
– wear 263
mechanical properties 764, 1023
– characterization 1036
– of bone 675
– of carbon nanotubes 668, 672
– of DLC coating 813
mechanically cut tips 382
mechanics of cantilevers 347
mechatronic device 952
media flatness 910
mediator molecules 304
medium
– effective 127
medium theory
– effective 127
melting freezing transition 894
melting point of SAM 853
membrane
– deflection method 1037
– fabrication of 314

– proteins 375
membrane-embedded machine 741
membranes as elastic media 754
memory
– cells and switches 116
– distance 588
– long-term 734
MEMS 147–171, 225, 270, 376, 606, 617, 764, 795, 831, 862, 901, 983, 1023, 1084
– accelerometer manufacturing 1091
– accelerometers 230
– applications 985
– capacitive switch 244
– components 1011
– device 247, 987, 990
– device operation 994
– fabrication 1111
– fiber optic switching 238
– industry 1093
– integration 1102
– manufacturing 1086
– microactuator (MA) 952, 971
– mounting condition 1105
– packaging 1111, 1116, 1128
– packaging requirement 1112
– passivation 1103
– post-packaging 1114, 1117
– pressure sensor production 1090
– production economics 1086
– resonators 244
– sensor 229
– standardization 1086
– storage device 907
– structure 1112
– surface 1104
– switch, metal-to-metal 244
– technology 233, 237, 249, 1034
– testing 1099
– tribological problems 989
– tunable capacitors 241
– vacuum packaging 1117
– wafer bonding 1095
– wafer protection 1097
MEMS/NEMS 530
MEMS-based
– microfluidic system 270
– storage concept 904
– storage device 922
meniscus
– bridge 831, 876
– force 516, 871
– of liquid 564
mercaptopropyltrimethoxysilane (MPTMS) 191
merocyanine 18
mesoporous molecular sieves 102
mesoscale osmotic actuator 269
messenger RNA 750
metabolic facility 282
metal 103
– catalyst 379
– cavity packaging 1099
– cluster agents 306
– electroplating 255
– evaporated (ME) tape 793
– matrix composites 81
– nanowires 69
– oxide 397, 400
– particle catalyst 54
– porphyrin (Cu-TBPP) 404
– seed layer 966
metal/insulator/metal (MIM) 197
metal-catalyzed
– chemical vapor deposition (CVD) 379
– polymerization method 287
metal-deposited Si surface 395
metallic nanotube 34
metallic SWNT 66
metal-organic compound 56
metal-particle (MP) tape 825
metal-to-metal MEMS switch 244
metastable lubricant systems 894
methylene stretching mode 842
methyl-terminated SAM 843
Meyer's law 708
MFM sensitivity 338
MgO tip 398
MgO(001) surface 403
Mg-terminated tip 398
MHD (magnetohydrodynamic) pumping 261
mica 102, 337, 615, 619, 640, 888
– films 100
– muscovite 615, 650
– surface 641
micelles 291, 292
micro/nanofabrication 147–150, 154
microactuator 990
– design 960
– fabrication requirements 962
– loop 972
– shape 965
microbially-derived antibiotics 293
microcantilever 994
microchannel 260
microcomponent 989
microcontact printing (μCP) 187, 834
microcrystalline graphite 803
microdevice 1026
microdispenser 266
microelectromechanical
– motor 226
– resonators 244
– switch 244
microelectronics 397, 749
micro-electro-rheological valve 260
micro-engine 908
microfabricated
– cantilever 372, 453
– silicon cantilevers 387
microfabrication 187, 226, 249
– methods 285
– techniques 285, 372
microfluidic 253
– applications 255
– channel 254, 269
– channels on silicon substrates 254
– control 260
– line 258
– mixers 265
– motherboards 270
– multiplexer 268
– network 268
– passive 262
– pumping 260
– structures 256
microfluidic device 269
– disadvantages 270
– materials for 254
– passive 257, 269
microfluidic dispenser
– passive 273
microfriction 511
micro-hinge technology 236
microindentation 689
micro-injection molding 273
micromachined
– high-Q resonators 245
– inductors 242
– notch 1032
– silicon 310
micromachining 147, 150, 151, 154, 155, 159–163, 166–168, 170
micromanipulator 988
micromechanical
– cantilevers 303
– device 1084
– structures 204
micromirror 992, 1040
– array 237
micromixer category 265

micromotor 1016
micron-sized channels 265
micropatterned SAM 848
micropipette aspiration 549
micropump 260
– passive 269
micro-Raman spectroscopy 693
microrelay 1062
micro-resonators 244
microscale
– diffusion 265
– friction 1006, 1010
– material removal 521
– scratching 503
– silicon gate 34
– wear 503, 520
– wear test 1008
microscanner 929
microscope eigenfrequency 348
microscopic friction 723
microscopic origin of friction 889
microscratch 813
– test 675
microscratching measurement 519
microsensors 229
microstrain gauge 1025, 1034
microstructure 1040
microsystem 249
micro-total analysis systems (μTAS) 257
microtransformer 197
microtriboapparatus 1011
microtubule 740
– bending 673
– buckling 673
microvalve 258
– design 260
microwear 813, 819
midplane 1046
– curvature 1048
– strain 1048, 1049
milligear system 989
millipede 901, 994
– chip 931
– system concept 921, 923, 943
MIM capacitors 197
MIMO design 971
miniaturized
– actuator 986
– connector 986
– gear 986
– motor 986
minimal detectable depression 374
minimally invasive screening 285
minimum-indentation pitch 937
mirror/yoke assembly 1089
misfit
– angle 638
– strain 1042
mismatch
– elastic 1051, 1056
mismatch of crystalline surfaces 566, 567, 593
mitochondria 747
mixed C-N nanotube 56
mixed lubrication *see* intermediate or mixed lubrication, 884
mixing performance 265
MMA air bag sensor 1092
Mn on Nb(110) 429
Mn on W(110) 432
m-nitrobenzylidene propanedinitrile (*m*-NBP) 916
MOCVD (metallorganic chemical vapor deposition) 152, 172
mode coupling gratings 199
model potentials 719
modeling
– at the nanoscale 752
– mechanics of systems 752
– tribological process 753
modular multifunctionality 280
modulation codes 946
modulus
– elastic 664, 698, 767, 770, 774, 805, 806, 809
modulus of elasticity 325, 516
molarity 749
molding 186
molecular
– AND gate 17
– assembly 26
– beam epitaxy (MBE) 988
– building blocks 12, 35, 747
– chain 839
– conduction band 33
– conformation 864
– cooperation 886
– dynamics (MD) 476, 718, 749
– dynamics (MD) calculation 639
– dynamics simulation (MDS) 488, 622, 631, 651, 753
– engineering 281
– interaction 879
– interconverting state 15
– logic gates 15
– lubrication 885
– machines 13
– mobility 894
– motor 13, 673, 740
– NOT gate 16
– placement by force microscopy 285
– precursor 58
– pump 741, 748
– recognition force microscopy (MRFM) 476
– recognition force spectroscopy principles 482
– resolution 421
– reversible transformation 15
– scale layer 833
– shape 558, 559, 586, 591, 592
– shuttle 14
– spring 536
– spring model 843, 848
– stiffness 849
– switch 14, 35
– theory of lubricated friction 890
– wires 289
molecule-based
– device 24, 28
– materials 35
– switches 15
moment of inertia 1030
monodispersity 286
monolayer 885
– switches 28
– thickness 855
monolithic accelerometers 231
monolithic high-Q MEMS 245
Monte Carlo simulation 848
MoO$_3$ film 614
Moore's law 1142
Morse potential 464
MoS$_2$ friction 640, 641, 668
motion
– unperturbed 390
motor
– actin-myosin 751
– flagellar 750
– micro 1016
– microelectromechanical 226
– miniaturized 986
– molecular 13, 752
– myosin 741, 745
– oil 884
– voice coil 952, 969
movement-constrained macromolecules 305
moving media model 908
moving-tips model 908
MRAM (magnetoresistive RAM) 899–907
– cell 906
MRFM

– magnetic resonance force microscopy 441
MRI contrast agents 305
MTTF (mean time to failure) 1126
multicomponent nanodevice 288
multi-input-multi-output (MIMO) 956
multilayer 709
– devices 197
– Fe-N/Ti-N 675
– structures 104
– thin-film 825
multimode AFM 338
multiple beam interferometry (MBI) 547
multiple cantilever 907
multiple therapeutic nanodevice 294
multiple-asperity contact 517
multiplexed sensor arrays 304
multiplication of dislocations 703
multivalent targeting strategy 298
multiwall carbon nanotubes (MWCNT) 43–49, 289, 342, 376, 667, 727
muscle contraction 740
muscovite mica 615, 650
μ -synthesis 974
μ -synthesis controller design 975
MWCNT
– multiwall carbon nanotubes 43–49, 289, 342, 376, 667, 727
MWNT (multiwall nanotube) 64
– based catalyst-support 76
– bc (bamboo-concentric) 44
– bh (bamboo-herringbone) 44
– bunches 58
– catalytically grown 673
– composites
    MWNT-Al composite 81
– flexural modulus 67
– purified 378
– surface area 64
– tips
    manually assembled 378
– Young’s modulus 669
myosin motor 751

N

N acceptors 10
Na on Cu (111) 421
NaCl 397
– island on Cu(111) 655
– islands 468
– thin film on Cu(111) 398
NaCl(001) 397
NaCl(100) 641–643, 648
NaF 397, 640
NAND gate 15
nanites 1146
nanoasperity 515, 695
nanobeam 669
– array 766, 774
nanobiological
– applications 313
– design 312
– devices 281
– vaccine design 312
nanobiotechnological device 300
nanobiotechnological therapeutic device 313
nanochannel glass 100, 102
nanochemistry 984
nanocluster 400
nanocomposite
– coating 833
– materials 28
nanocrystallites 800
nanodeformation 864, 880
nanodevice 85, 281
– multiple therapeutic 294
nanoelectrodes 32
nanoelectromechanical systems (NEMS) 226, 246, 606, 764, 901, 984
nanoelectronic device 32, 34
nano-electronics 84
nanofabrication 147, 170, 175, 187, 326, 526
– techniques 253
nanofatigue 810
nanofiber 44, 53
nanofilament 44, 60
nanogaps 31
nanohardness 695, 804, 805, 1000
nanohelix 12
nanoimprint 171
nanoindentation 674, 688, 697, 805, 1024
– curve 677
– measurement 504
nanoindenter 765, 769, 818, 1028
nanolubrication 883
nanomachine 1147
nanomachining 325, 326
– techniques 205
nanomagnetism 431
nanomania 1146
nanomaterial 662
nanomechanical Si beams 247
nanometer resolution 186
nanometer servo precision 979
nano-objects 68
nanoparticle 49, 374
– contrast agents 305, 306
nanoparticulate carriers 310
nanophobia 1146
nanoporous membranes 285, 314
– microfabrication 286
nano-positioning 359
nanorheology 584
nanoscale
– antimicrobials 293
– architectural property 283
– assemblers 1146
– biomolecules 10, 12
– control of molecular events 310
– data bit 909
– drug delivery 291
– electrodes 23, 27
– FET 117
– film morphology 917
– interventions 285
– mechanical properties 661, 662
– molecular therapeutic device 308
– molecules 35
– Schottky barrier 34
– supramolecular assembly 407
– therapeutic device 281, 315
– therapeutic platforms 284
– wear 518
Nanoscope I 328
nanoscratch 522
– studies 765
nanostructures 147, 170, 171, 179
– containing proteins 307
– mechanical properties 764, 1023
nanoswitches 15
nanotechnological
– actions 755
– therapy 307
nanotechnology 280, 918, 1139
– definition 1136
– ethical issues 1136
– in the living world 740
– possible applications 1136
– recommendations 1138
– role of social sciences 1148
– social issues 1136
– unintended consequences 1143
nanotherapeutic 280, 288, 303
– contrast agents 304, 310
– delivery device 298
– design paradigms 282
– device application 307
– device components 285
– devices in oncology 307

– drug delivery 311
– triggering external stimuli 299
– vaccines 312
nanotransfer printing (nTP) 190
nanotransistor 32
nanotribology 717, 862
nanotube 12, 105, 133
– AFM tips 379
– buckling 377
– chemistry 67
– defects 47
– functionalization of wall 72
– functionalized 71, 72
– growth 45
– length 382
– morphology 49
– nucleation 45
– oxidation 72
– resistance 34
– strain 671
– surface energy 380
– tip fabrication 380
– tips, surface growth 380
– transistor 34
– volume fraction 83
– yield 49, 59
nanotube production 56
– efficiency 49
– electric-arc method 48
– laser ablation 46
– solar furnace 52
– techniques 57
nanotube-based
– emitter 74
– hybrid material 71
– sensor 75
– SPM tip 73
nanotube-Co-MgO 81
nanotube-containing
– composite 82
– electrical device 289
nanotube-Fe/Co-$MgAl_2O_4$ 81
nanotube-Fe-Al_2O_3 81
nanotube-polymer composite 83
nano-tweezer 85
nanowire 31
– applications 131, 138
– metal 69
– nucleation 110
– photodetectors 135
– semimetallic 118
– stress-induced crystalline 107
– superlattice 132
– Zn 120, 123
– ZnO 135
nanowire device
– two-terminal 132
naphthalene channel 21
National Nanotechnology Initiative (NNI) 1137
native oxide layer 868
Nb superconductor 423
NBIC convergence 1140
$NbSe_2$ 431, 649
NC-AFM (noncontact atomic force microscopy) 397, 433
near-field
– method 903
– scanning optical microscopy (NSOM) 128, 372
– technique 434
near-surface mechanical properties 665
necrotic domains 307
negative logic convention 26
negative magnetoresistance 121
neighbouring indents 678
NEMS 831, 983, 988, 1023
– devices 246
– nanoelectromechanical systems 226, 246, 606, 764, 901, 984
neocarzinostatin (NCS) 309
nested-arc structure 680
net electrostatic torque 1066
net fluid transport 261
newspaper
– electronic 196
Newton's first law 454
Newtonian flow 570, 580, 581, 583
Newton–Raphson method 753
n-hexadecane 888
N-hydroxysuccinimidyl (NHS) 478
Ni(001) tip on Cu(100) 653
Ni(111) tip on Cu(110) 653
Ni, Co catalyst 47
Ni/Y catalyst 49
Ni^{2+}-chelating 485
nickel-iron permalloy 259
Ni-Fe valve membrane 259
NIH3T3 fibroblast cell 489
NiO 402, 417
NiO(001) 397, 400, 402
NiO(001) surface 403
Ni-P
– beam 785
– cantilever 778
– film 770, 771
– microbeam 777, 785
NiTi 665
– transformation behavior 666
nitrogenated carbon 800
NMP (no moving part) valves 265
noble metal surfaces 424
n-octadecyltrichlorosilane ($n\text{-}C_{18}H_{37}SiCl_3$, OTS) 616, 842
n-octadecyltrimethoxysilane (OTE) 615
noise 387, 391, 453
– 1/f 387, 957
– electronic 333
– external 415
– performance 391
– signal 941
– source 355
– vertical 391
Nomarski-interferometer 352
nonconducting film 798
nonconductive
– materials 404
– sample 329
– surface 462
nonconforming contacts 890
noncontact
– dynamic force microscopy 654
– friction 438, 655
– imaging 331
– mode 373, 388, 909
noncontact atomic force microscopy (NC-AFM) 374, 385, 391, 393, 397, 404, 654
nondestructive contact-mode measurement 652
nondimensional curvature 1051
nonequilibrium interactions *see* dynamic interactions
nonequilibrium simulations 720
noninvasive device 283
nonlinear
– force 460
– geometry effect 1058
– *I*–*V* behavior 124
– material behavior 1058, 1059
– optical property 129
– spring 491
– strain-displacement relation 1055
nonliquidlike behavior 584
nonmagnetic Zn 431
non-Newtonian behavior 885
non-Newtonian flow 570, 581, 583
nonpolar group 838
nonspherical tip 647
nonsymmetrical passive valves 268
nontherapeutic nanobiological device 283
nonvolatile random access memories (NVRAM) 899–913
nonwetting 560
NOR gate 15

normal friction 569, 577, 579, 580
normal load 721, 866
– external 867
normalized frequency shift 463
no-slip boundary condition 729
NOT gate 15
N-succinnimidyl-3-(S-acethylthio)propionate (SATP) 478
NTA (nitrilotriacetate) - His$_6$ 478
nTP (nanotransfer printing) 197
nuclear weapon 1140
nucleation of nanowires 110
nucleic
– acid (NA) 294, 299
– acid hybridization 294, 300
nucleotides 747
n-undecyltrichlorosilane (n-$C_{11}H_{23}SiCl_3$, UTS) 842

O

O acceptors 10
$(OCN)^-$ 398
octamethylcyclotetrasiloxane 888
ODD performance 903
odd-even effect 621
off-track error 958
OH-terminated tip 398
on-chip
– actuator 1031
– electronic detection 231
– integration 210
– microvalves 260
– spiral inductors 242
oncological nanotherapeutics 291
one-dimensional quantum effect 115
one-dimensional system 100
open loop architecture 1093
operation 387
opsonized particle 296
optical
– absorption 129
– applications 134
– beam deflection 607
– cavity 135
– data switching 237
– deflection systems 372
– detector 331
– disk drives (ODD) 899, 900
– gap behavior 127
– head 336
– head mount 337
– integration 236
– MEMS 233
– output 16
– property 126, 127
– reflection 127
– switch 135
– transmission 127
– trap 480
– tweezers (OT) 480, 549, 744
optical lever 353
– angular sensitivity 355
– deflection method 362
– optimal sensitivity 355
optimal beam waist 355
optimum sampling phase 946
optoelectronic
– components 198
– module 236
– switch 136
OR
– operation 23
– operator 15
order
– in-plane 567, 584, 585, 593
– long-range 570
– out-of-plane 557–559, 567, 570, 584, 585, 591
– parameter 570, 586
ordering nanowires 108
organelles 281
organic
– compounds 835
– device structure 917
– film 916
– inverter circuit 196
– technology 916
– transistor 193, 196
organics 915
– data storage 916
organized molecular arrays 23
organometallic vapor phase epitaxy (OMVPE) 988
Orowan strengthening 710
orthogonal conjugation 295, 296
orthotropic Young's modulus 1048
oscillating tip 334, 469
oscillation
– amplitude 389, 453, 454, 457, 461
– loop 462
oscillatory force 544, 545, 557–561, 567
osmosis response time 269
osmotic
– interactions 545, 555, 562, 564
– pressure 555, 562, 575
– stress technique 549
OTE (octadecyltrimethoxysilane) 615
OTS (octadecyltrichlorsilane) 848, 1075
OUM cell 906
out-of-plane stiffness 959
overall barrier height 887
overdamped SFM system 891
overdrive capability 1062
overwriting mechanism 937
Ovonyx 915
Ovonyx Unified Memory (OUM) 906
oxide layer 703
– amorphous 106
oxide-enhanced nanowire growth mechanism 107
oxide-sharpened tips 375
oxidized nanotube 72
oxygen
– content 826
– sensor 274

P

package level integration 1093
packaging 248, 249
– cap 1112
– equipment 1099
– induced thermal stress 1123
– reliability 1125
– uniform 1112
packing density
– chains 842
palladium nanowires 137
PAMAM (polyamido amine) dendrimer 286, 287
p-aminophenyl phosphate (PAPP) 271
paper-like displays 193
paraboloid load displacement 697
paraffins 835
parallel-plate
– actuator 955
– capacitor model 1064
– sensing 957
paramagnetic particles 305
parasitic charging 1077
particle
– contamination 1098
– control 1098
– opsonized 296
– track-etched mica films 103
particle model
– embedded 894
Paschen curve 1076
passive
– check valves 262

– linearization 361
– microfluidic device 257, 269
– microfluidic dispenser 273
– microfluidics 262
– micromixers 265
– micropump 269
– microvalves 257, 262
– structure 1025
– valve geometry 264
patient-monitoring systems 274
pattern of ink 186
pattern transfer 191
patterned
– conductive substrate 110
– film 1053
– self-assembled monolayer (SAM) 188
– silicon chip 25
patterning 1075
Pb on Ge(111) 428
PbI$_2$ filled SWNT 70
PDP (2-pyridyldithiopropionyl) 478
peak indentation load 810
peapods 71, 289
PECVD (plasma enhanced chemical vapor deposition) 833, 926, 1009
– carbon sample 800
PEG (polyethylene glycol)
– crosslinkers 479
pegylated molecules 313
Peierls instability 428
per molecule adhesion force 620
perfluorodecanoic acid (PFDA) 992
perfluoropolyether (PFPE) 530, 861
perfluoropolyether Z-DOL 614
performance of electromechanical actuator 1075
performance parasitics 1098
periodic
– force 725
– potential 637, 891
permanent dipole moment 407
perpendicular scan 344
persistence length 488
perturbation approach 390
perylene 404
PES (photoemission spectroscopy) 956
– generation 944
– loop compensator 973
PFPE (perfluoropolyether) 864, 1012
– lubricant 862, 868, 1003, 1016
– OH 892
pH of water environment 619, 621
pH sensor 137
phage display 297, 298
pharmacoeconomics 285
phase
– angle image 530
– breaking length 120
– curve 458
– images 470
– lag spectrum 666
– measurement 471
– signal change 458
– transformation 690, 705
phase change
– material 915
– medium 922
– RAM (PC-RAM) 899, 906
phenol 837
phenoxy-centered HOMOs 26
phonon
– confinement effects 125, 127, 131
– excitation 468
– scattering 120
phosphorus-doped polysilicon 206
photoacid 19
photoactive
– fragments 14
– solids 22
– stopper 14
photo-conductance 128
photo-crosslinker 478
photodetector sensitivity 766
photoemission spectroscopy (PES) 423
photogenerated hole 30
photoinduced electron transfer 16, 17
photoinduced proton transfer 19
photolithography 285
– near-field conformal 187
– proximity mode 186
photolithography patterns 186
photo-luminescence (PL) 127, 135
– optical imaging 128
photoresist 188, 190, 1095, 1121
photothermal effect 465
physical properties of nanowires 110
physical vapor deposition 104
physisorbed protein layer 476
physisorption 861
pick-up
– SWNT tips 382
– tip method 381
pico-slider 960
piezo
– ceramic material 360
– effect 359
– element 461
– excitation 454
– hysteresis 415
– relaxation 415
– stacks 361
– tube 359
piezoelectric
– actuation 259
– actuator 908
– drive 327
– leg 636
– positioning elements 414
– scanner 372, 415, 676
piezoresistive
– cantilever 355
– coefficients 356
– detection 355, 387
– pressure sensor 1089
– sensing 958
– sensor 227
piezoscanner 363, 382
piezotranslator 363
piezotube calibration 329
pigment particles 195
pile-up, nanoindent 693, 699, 700, 709, 711
– characteristic 935
piling-up behavior 674
pilot signal 945
pinning 441
– forces 727
pin-on-disk tribotester 841
PL (photoluminescence) NSOM imaging 135
plane-to-plane separation 12
plasma
– etch 286
– frequency 127
– resonance 127
plasma enhanced chemical vapor deposition (PECVD) 197, 339, 770, 795, 799
plasminogen activator (PA) 302
plasmon mode 421
plastic
– asperity model 884
– circuit 193
– contact regime 517
– deformation 522, 728, 812, 854
– electronics 197
– fluidic chips 273
– large area circuit 194
– packaging 1099
plasticity 1060
platelet nanofiber 60

platform 929
– fabrication process 930
platinum-iridium 330
– tip 29
PMMA (poly(methyl methacrylate)) 247, 257, 671, 924, 933, 936, 994
p-n
– diodes 116
– junction diode 132
– junctions 132, 135
pneumatic
– actuation 258
– damping 418
p-nitrophenolate 19
point probes 688
Poisseuille flow 885
Poisson statistics 620
Poisson's ratio 698, 1047
polar
– group 838
– lubricant 832, 861
polarization dependence 129
polishing 793, 1000
poly(amido) amine (PAMAM) dendrimer 286
poly(ethylene glycol) (PEG) 477
poly(ethyleneterephthalate) (PET) 192
poly(methyl methacrylate) (PMMA) 247, 257, 671, 924, 933, 936, 994
polyaromatic shells 63
polycarbonate (PC) 257
polycrystalline
– films 210
– graphite 801
– Si 226
– SiGe 210
polydimethylsiloxane (PDMS) 187, 834
polyethylene (PE) 257
polyethylene co-propylene 886
polyethylene terephthalate (PET) 524
poly-Ge
– mechanical properties 210
polymer 255, 610, 664, 910
– blend 471, 662
– brush 563, 575, 581
– chemistry 286, 291
– conjugation (pegylation) 296
– fluids 892
– intermediates 287
– matrix composites 82
– medium 932
– melt 886
– membranes 103
– microfabrication techniques 255
– microstructures 257
– mushroom 562
– nanojunction 32
– properties 263
– therapeutics 307
– transparent microcapsules 195
polymeric
– liquids (melts) 561, 581, 583
– magnetic tape 526
polypeptides 10
polypropylene 404, 471
polysilicon 963, 967, 1010, 1040
– beam 1044
– fatigue 1036
– film 229, 995, 1027
– fracture strength 1036
– fracture toughness 1035
– friction 1036
– layer 263
– mechanical properties 1034
– MEMS 206
– microstructure 1035
– residual stress 1034
– resonators 245
– strip 245
– surface micromachining 210
– Young's modulus 1035
polystyrene (PS) 257, 936
polysulfone 936
polytetrafluoroethylene (PTFE) 639
polyurethane 471
poor mixing 889
pop-ins 690
pop-outs 690
population explosion 1141
porous
– silica or alumina 120
– vycor glass 102
position
– accuracy 363
– error 972
– error signal (PES) 943, 968
– sensing resolution 957
positioning 109
positive logic convention 18, 26
post-packaging process 1118
potential barrier 887
potential energy
– total 720
power dissipation 237, 470, 654
power to weight ratio 752
PQ design method 970
Prandtl–Tomlinson model 725–727
pre-crack length 1027
precursor 56, 69, 70
– gases 210
preferential flow direction 261
preparation improvements 54
pressure 871
– injection 104
pressure sensor 227
– fabrication process 1090
– packaging 1099
pressure-induced phase reconstruction 888
primary minimum adhesion 544, 555, 559
printed
– coil 197
– DFB resonator 200
probability density functions 891
probe
– FIB-milled 342
probe storage 901, 907, 908
– data organization 909
– operating parameters 909
probe tip 372
– characterization 611
– performance 374
probe-sample distance 457, 462
probe-surface distance 455
process
– control 1088
– flow 1088
– gas 799
process coherence volume 887
processing conditions 44
prodrugs 298
product architecture 1088
production efficiency 47
programmable microfluidic systems (sPROMs) 266
programmed assembler 1146
projection mode photolithography 186
propagation of cracks 524
properties of a coating 795
protection of sliding surface 831
protein 477
– bioactivity 294
– coupled to nanomaterials 294
– folding 293
– primary structure 293
– secondary structure 293
– synthetic chemistry 294
– tertiary structure 293
protofilament 673
prototyping of biological nanodevices 282
protrusion force 545, 564

P-selectin glycoprotein ligand-1 (PSGL-1) 488
PSG (phosphorus-doped glass) 1117
Pt alloy tip 330
PTCDA 404
PTFE (polytetrafluoroethylene)
– coated Si-tip 640
– film 833
Pt-Ir
– tip 330
– wire cantilever 912
pull-hold-release cycle 485
pull-in 1072
– angle 1068
– charge 1064
– instability 956
– voltage 1062, 1064, 1067, 1068, 1071, 1075
pull-off force *see* adhesion force, 608, 614, 615, 617, 635, 864
pulse-etching 379
pumping chamber 261
purified MWNT 378
pyramidal
– AFM tip 615
– etch 373
pyrazoline 16
pyrolysis of hydrocarbons 59
pyrolytic method 58
PZT (led zirconate titanate)
– actuated suspensions 967
– scanner 500
– tube scanner 328, 334

Q

Q-Control 464, 465
Q-factor 388, 436, 455, 1126
quad photodetector 334
quadrant detector 354
quadrature signal 943–945
quality factor Q 339, 348, 389, 454, 911
quality system 1101
quantization energy 117
quantum
– corrals 427
– dot 134, 172, 173
– effects 126, 134
– Hall regime 438
– limit for the thermal conductance 125
– subbands 116
– well 421
– wire superlattices 123
– yield 16
quantum confinement 99, 126, 127, 129
– effect 116, 135, 138
quantum size
– effect 118, 134
– regimes 116
quantum-confined structures 133
quartz-crystal microbalance (QCM) 717
quasi-optical experiment 421
quasi-static
– bending test 775, 777
– mode 388
– strain rate 677

R

radial cracking 808
radio-frequency (RF) MEMS 239
radiotherapy 307
radius of gyration 561
Raleigh's method 348
Raman
– spectra 131, 802
– spectroscopy 800
ramped creep model 890
random access memory (RAM) 28
random access time 900
random force 891
randomly oriented polysilicon 1035
rapid thermal processing (RTP) 1118
raster scan 901
Rayleigh wave 692
Rayleigh–Ritz method 1071
RbBr 397
RC-oscillators 358
reaction kinetics 483
reactive
– lubrication 892
– sealing 1114
– spreading 189
reactive ion etching (RIE) 205, 247, 254
read
– channel 939
– time 908
readback
– rates 932
– signal 940, 941
readout
– electronics 354
– signal 944
receptor binding 295
receptor-ligand
– bond 482
– interaction 484, 545
– unbinding 483
– unbinding force 476
receptor-mediated uptake of synthetic nanomaterial 296
recognition force microscopy (RFM) 476
recognition force spectroscopy (RFS) 484
recognition imaging 489
recombinant protein therapeutics 285
rectangular cantilever 339, 610, 656
rectifying properties 132
recursive least square algorithm (RLS) 974
reduced modulus 690
reflection interference contrast microscopy (RICM) 550
reflectivity 129
relative humidity (RH) 613
– effects of 533, 873, 1004
relative position error signal (RPES) 956
relaxation
– mechanical 457, 848
relaxation time 570–574, 583, 587, 588, 593, 894
relaxation time (T_1)
– longitudinal 305
relaxation time (T_2)
– transverse 305
release
– long-term of drugs 994
– stiction 1095
– voltage 1062
reliability 831
– long-term 1126
– of MEMS 995
– testing 1125
relief on a surface 186
remanence 137
remote detection system 354
removable disk 901
repetitive IgG 484
replica molding 833
repulsive force 480
residual
– film stress 1023
– stress 692, 699, 709, 804, 809, 812
– thickness 855
resistive micro-heater 1119
resolution 233, 374
– vertical 331

resonance
– curve detection 339
– frequency 454
– mechanical 591
resonant
– enhancement effects 131
– frequency 373
Resovist 306
response time 467
rest time 869
retardation effect 550, 552
reticuloendothelial system (RES) 296
retractive slips 885
Reynolds hydrodynamic theory of lubrication 885
RF magnetron sputtering 795
rheological
– characterization 865
– model 469, 664
rhombhedral R-8 706
rigid
– biphenyl chain 853
– disk drive 862, 869
– surface asperities 723
Ritz procedure 1055
RLL (run-length-limited) code 947
RMS roughness 1010
RNA polymerase 747
robust manufacturing 1087
rolling friction 552, 568
root mean square 433
ropes (SWNT) 66
rotary microactuator 958, 993
rotating cylinder 907
rotating strain gauge 1026
rotaxane 13
rough macroscopic contact 885
roughness 558, 559, 566–568, 594
RTP (rapid thermal processing) MEMS vacuum packaging 1119
Ru(II)-trisbipyridine 13
rule of mixtures 708, 709
run-length-limited (RLL) 947
rupture forces 488

S

sacrificial film layers 1040
sales volume 1093
SAM (self-assembled monolayer) 165, 176, 178, 622, 1088
– coating 1075
– melting point of 853
– modified surface 620
sample holder 416
sandwich immunoassays 270
sandwiched molecules 26
saturated calomel electrode 24
saturated hydrocarbons 835
scale-dependent surface tension 614
scaling factor 975
scan
– area 335
– direction 345
– frequency 335
– head 417
– range 359, 360
– rate 329
– size 337
– speed 360
scanner, piezo 436
scanning
– acoustic microscopy (SAM) 663, 692
– capacitance microscopy (SCM) 326
– chemical potential microscopy (SCPM) 326
– electrochemical microscopy (SEcM) 326
– electron microscope (SEM) 110, 373, 521
– electrostatic force microscopy (SEFM) 326
– head 328
– ion conductance microscopy (SICM) 326
– Kelvin probe microscopy (SKPM) 326
– lateral range 929
– local-acceleration microscopy (SLAM) 663
– magnetic microscopy (SMM) 326
– nanoindentation (SN) 674
– nanoindenter 662
– near field optical microscopy (SNOM) 326
– polarization force microscopy (SPFM) 615
– speed 335
– system 359
– thermal microscopy (SThM) 114, 326
– tunneling microscope (STM) 385, 396, 450, 498, 922
– tunneling microscopy (STM) 114, 325, 371, 382, 397, 899
– tunneling probe 114
– velocity 519
scanning force
– acoustic microscopy (SFAM) 326
– microscopy (SFM) 326, 433, 663, 884
– spectroscopy (SFS) 433
scanning probe
– lithography 186
– methods 606
– microscope (SPM) 326
– microscopy (SPM) 371, 385, 612, 663, 899
schematic diagram of T-SLAM 663
Schottky diode 132
scission 622
scope of therapeutic nanodevices 285
scratch
– critical load 824
– damage mechanism 818, 819
– depth 771, 773, 1000
– depth profile 773
– drive actuator 1031
– profile 519
– resistance 765, 771, 853, 1001
– test 520, 814
scratch-induced damage 813
scratching measurement 325
SCREAM 161
screen printing 193
sealing 1112
second anodization 100
secondary signaling drug delivery 301
Seebeck coefficient 123, 133
seek
– control 976
– time 901
selected area electron diffraction (SAED) 111
selective electrodeposition 108
self-actuation voltage 1062
self-aligning optical system 236
self-assembled
– growth 420
– microscopic vesicles 834
– monolayers (SAMs) 27, 165, 176, 187, 476, 536, 606, 618, 703, 833, 839, 861, 1003, 1004
– nanoparticles 312
– nanotube bunches 58
– structures 291, 310
self-assembled monolayer (SAM)
– patterned 188
self-assembly 131, 147, 170, 173, 176, 178, 179, 288
– in biological systems 740
– of nanostructures 289
– of organic layers 23

self-enhancing instability 458
self-excitation
– modes 461
– scheme 464
self-lubrication 652, 653
self-regulation of a therapeutic device 302
self-replicating nanobot 1146
self-tuning control 974, 976
semibiological nanodevices 281
semiconductor 103, 391
– economics 1086
– quantum dots 428
– surface 392
– SWNT 74, 85
semimetallic nanowire 118
semimetal–semiconductor transition 118, 123
sensing
– channel 303
– element 227
– modalities of therapeutic nanotechnology 302
sensing devices
– biological 137
– chemical 137
sensitivity 356, 357, 390, 467, 479, 633, 972
sensitizer 30
sensor 233
– and effector communication 283
– applications 117
– noise 975
– systems 302
– transducer interface 304
sequential logic circuits 20
sequential microfluidic manipulation 268
servo
– demodulation 945
– field 943
– loop 943
– self-writing 945
servo control design 968
sessile-drop 832
SFA (surface forces apparatus) 884, 894, 1011
– measurement 613
SFM (scanning force microscope) 884, 888, 890, 894
– shear force experiments 893
shallow indentation measurement 679
shape memory alloys (SMA) 260
sharpened metal wire tip 382
shear
– energy 887
– force *see* kinetic friction, static friction
– melting 570, 586
– modulus 633, 933
– rate 866
– strength 646
– stress 850, 887
– thinning 581, 583, 584, 589
shear flow
– damping 1073
– detachment (SFD) 479
shear stress
– critical 571, 572, 577, 585, 586
– effective 648
shearing force 848
shearing interface 721
shear-melting transitions 734
SH-group 476
short-cut carbon nanotubes 428
short-range
– chemical force 437, 464
– chemical interaction 402
– contribution 386
– electrostatic attraction 399
– electrostatic interaction 398
– energy dissipation 468
– interatomic force 455
– magnetic interaction 397, 402, 403
shot noise 355
Shubnikov–de Haas quantum oscillatory effect 122
shuttle
– displacement 957
– finger 956
Si 373, 375, 619
– adatom 393
– cantilever 373, 458, 465
– MEMS 247, 985
– nanobeam 773, 781, 785
– stamp 190
– tip 374, 392
– trimer 395
– wafer 373, 459, 619
Si(001)2×1 394
Si(001)2×1-H surface 394
Si(100) 515, 520, 614, 818, 820, 862, 867–869, 875, 877, 878, 995, 1012
– wafer 863
Si(100)2×1:H monohydride 393
Si(111) 519, 527, 848, 850, 999
Si(111) surface 404
Si(111)$\sqrt{3}\times\sqrt{3}$-Ag 395, 396
Si(111)(7×7) 434, 468, 640
Si(111)(7×7) surface 389, 397, 462, 639
Si(OH)$_4$ film 1013
Si$_3$N$_4$ 375, 501, 619
– based tip 619
– cantilever 373
– layer 373
– tip 341, 374, 531, 841, 848, 866, 871, 880
Si-Ag covalent bond 397
Si-based devices 764
SiC 995
– bulk properties 995
– film 770
signal
– distribution 1112
– transduction 20
silane (SiH$_4$) 206
silica
– thermally grown 840
silicon 332, 356, 388, 610, 693, 705, 1111
– AFM tip 478
– cantilever 387, 633
– chemistry 478
– crystalline 254
– dioxide (SiO$_2$) 254
– dioxide layer 31, 33
– FET 303
– fractures 777
– fusion 1118
– grain 1035
– membrane 263
– MEMS 1095
– micromachining 227
– micromotor 866
– oxide 106, 477
– surface 477
– tip 392, 434, 463, 635
– wafer 25, 27, 186, 189, 228, 286, 453, 614, 930
silicon nitride (Si$_3$N$_4$) 254, 332, 477, 610, 615, 913, 964, 968
– cantilever 372
– layer 1117
– tip 375, 635
silicon-based MEMS sensor 229
silicon-based mold masters 255
silicon-on-insulator (SOI) 205, 241, 964
– substrates 247
silicon-only wafer 965
silicon-on-silicon contact 1012
silicon-silicon bonding 1096
silicon-terminated tip 435

silicon-to-glass fusion bonding 1120
siloxane 833
simultaneous imaging 397
– of a TiO$_2$(110) surface 401
single asperity 646
– AFM tip 868
– contact 517, 1012
– size of 722
single bond 622
single crystal
– aluminum (100) 522
– nanowires 104
– Si(100) 770, 862
– silicon 504, 964, 995, 1024
– silicon cantilever 341, 611
– wafers 204
single crystalline iron 675
single domain magnetic 138
single magnetic flux quantum 122
single molecular motor 480
single molecule
– assays 743
– biology 743
– detection 477
– experiment 760
– studies 485
single particle model 894
single point sensor 1091
single protein therapeutics 281
single receptor-ligand pair 480
single stranded DNA (ssDNA) 746
single-input-multi-output (SIMO) 956
single-input-single-output (SISO) 969
single-layer
– beam 1044
– film 1050
single-particle wave function 422
single-stranded nucleic acid molecule (SSNA) 302
single-wall carbon nanotube (SWCNT) 34, 40, 289, 315, 342, 376, 668
single-wall nanocapsule 49
singularity in joint density of states 134
sink-in 693, 699, 700, 709, 711
– behavior 674
sintering 553
SiO$_2$ 54, 373, 375, 531, 615
– film 770
– nanobeam 773, 774, 785
– thin films 205
SiOH groups 478
Si-SiO$_2$ stress formation 375
SISO 973
– design 969
site-specific drug delivery 298
Si-wafer 460
SLAM 663
slider 952
sliding
– contact 651
– direction 585
– distance 587
– friction 734
– of tip 632
– speed 889
– velocity 574, 585, 644, 884
SLIGA 168
s-like tip states 422
slip distance 732, 889
slipping and sliding regimes 586
SMA (shape memory alloys) 260
– actuation schemes 260
– driven micropumps 261
small angular deflection 1068
small specimens handling 1025
SMANCS (S-Methacryl-neocarzinostatin) 309
– albumin complexes 309
smart media card 905
smart plastic biochip 273
smooth sliding 585
snap-in process 609
SnO$_2$(110) 400
soap-like lubricants 887
social
– perception 1145
– services 1142
societal impacts 1136
socio-technical trends 1141
soft
– cantilever 453
– coatings 708
– lithography 833
– polymer stamps 190
SOI wafer 1096
solar furnace
– devices 52
– method 61
solder bonding 1115, 1118
solid boundary lubricated surfaces 571, 572, 576–578, 587, 588
solid solution catalyst 55
solid xenon 436
SOLID95 779
solidification 578, 582
solid-like
– behavior 593
– Z-DOL(BW) 866
solution-phase synthesis 107
solvation
– effect 621, 623
– forces 545, 557, 558, 561, 567
sonolubrication 513
soot 46
SP 815
spacer chain 839–841
– length 844
spark plasma sintering (SPS) 81
spatial variation curvature 1058
specific accumulation of nanoparticles 311
specificity 752
spectroscopic resolution in STS 419
speed-energy product 1073
spin
– casting 192
– coating 887
– density waves 431
– quantization 423
spin-on-glass 965
spiropyran 18
SPM (scanning probe microscopy) 73, 372
– methods 672
– tip 452
spreading
– dynamics 892
– profile 892
spring
– sheet cantilever 341
– system 327, 929
spring constant 377, 387, 390, 393, 433, 450, 451, 469, 480, 483, 611, 633, 671, 911, 956, 1030, 1067
– calculation 347
– changes 415
– effective 637, 645, 721
– lateral 338, 636
– measurement 346
– torsional 1068
– vertical 338
sputtered coatings
– physical properties 804
sputtering
– deposition 799
– power 805
sp^3 bonding 806
sp^3-bonded carbon 813
squeeze film damping 248, 1073
SRAM
– cells 1088

– CMOS static random access memory 235
SrF_2 398, 399
$SrTiO_3$ 402
$SrTiO_3(100)$ 400, 401
stability
– mechanical 927
stabilization 1065
stable field performance 1102
stainless steel cantilever 813
stamp
– Au coated PDMS 192
– Au/Ti coated 191
– composite 188
– depth 190
– fabrication 186
– mechanical properties 187
– positioning 195
standardization 249
static
– advancing contact angle (SACA) 847
– AFM 388, 469
– charge 1103
– deflection AFM 450
– friction 571, 576, 579, 583, 585–587, 589, 590, 593, 718, 731, 1034
– friction force 722, 866, 1014
– interactions 544, 584
– mode 387, 433, 453
– mode AFM 354
statistical fluctuation model 889
statistical kernels 891
steady-state sliding *see* kinetic friction
steady-state velocity 733
step tilting 855
stepping motor 636
stereoelectronic properties 12
stick slip 592
sticking regime 586
stick–slip 571, 576, 579, 583–585, 587, 590, 876, 885, 886, 889, 894
– mechanism 636
– motion 732
stiction 579, 832, 885, 991, 1088, 1103
– phenomena in micromotors 1016
– suppression 1103
stiffness 390, 663, 819
– torsional 349
stiffness coefficient
– elastic 1048
stiffness measurement
– continuous (CSM) 810
STM (scanning tunneling microscope) 173–176, 325, 397
– cantilever 330
– cantilever material 339
– principle 327
– probe construction 330
– tip 325, 417
stoichiometry of compound nanowires 115
Stokes's equation 933
Stone–Wales defect 62, 68
Stoney equation 1024
storage
– capacity 946
– drive industry 902
– field 943
– modulus 702
– surface topography 942
strain
– energy 609
– energy difference 810
– engineering 147, 170
– theory 1144
– thermally induced 1125
– transformation 1041
strain–displacement relation 1049
stray capacitance 357
strength 1023
streptavidin 478
– mutants 484
stress 751, 930, 1023
– activation volume 887
– component 1043
– distribution 779, 1049
– field 1024
– gradient 1026
– maximum 1027
– measurement 1025
– relaxation 1060
– singularity 1043
– tensor 759
– transformation 1044
– uniaxial 1042
stresses within the capsid walls 758
stress–strain
– behavior 1028
– curve 671, 784
– relation 1048
stress–temperature response 1060
stretch modulus 751
Stribeck curve 569, 584, 884
strip domain 439
structural
– characterization 110
– entropy 886, 887
– forces 545, 557, 559, 566
– integrity 764
– material 1028
structurally programmable microfluidic system (sPROMs) 264
structure factor 730
structuring of simple liquids 886
SU-8 resist 929
sub-Angstrom deflections 372
subcontractor 1087
subculture theory 1145
sublimation 52
submicron
– electron-beam lithography 246
– ICs 247
– lithographic techniques 246
submonolayer
– coverage 864
– lubrication 731
subnanometer precision 10
sub-nanonewton precision 452
substrate 839, 840
substrate curvature technique 1024
substrate–slider interactions 727
subsurface water irrigation 676
super modulus 691
supercapacitor 85
superconducting
– gap 431
– magnetic levitation 327
– matrix 440
superconductivity 419
superconductors 103, 429
– type-I 431
– type-II 431
superficial nanotechnology aspects 1140
superlattice
– nanowire 103, 114
– structure 108
superlubricity 642
superparamagnetic materials 305
superparamagnetism 138
superstructures of nanowires 108
supramolecular
– assembly 17
– forces 35
surface
– adsorption 263
– amorphous 544
– asperity effect 513
– atom layer 388
– band 423
– barrier potential height 890
– charge 557, 621, 1074
– charge density 555–557

– chemistry 190, 296
– crystalline 544
– diffusion 190
– effects 129
– elasticity 529
– energy 619, 792, 1088
– energy (tension) 547, 552, 566, 567, 572, 574, 578
– forces 544
– forces apparatus (SFA) 479, 498, 546–548, 552, 576, 585, 588, 606, 717, 731, 884
– free energy 745, 746
– hydrophobic 544, 560
– micromachined accelerometers 231
– micromachining 163, 226, 229
– micromechanical properties 498
– microtribological properties 498
– mobility 865
– nanomechanical properties 498
– nanotribological properties 498
– passivation 1102
– potential 419, 555–557, 798
– potential measurement 503
– slope 844
– state lifetime 423
– stiffness 506
– structure 111, 400, 544, 558, 559, 566, 567, 570, 586, 591
– tension 265, 516, 618, 832, 846, 862
– terminal group 839
– topography 632, 778, 901
– transfer chemistry 190
– treatment 1104
surface roughness 383, 674, 678, 724, 773, 778, 844, 942, 997, 1009
– map 510
– measurement 500
surface-mounted biofilter 272
surfactant monolayers 547, 564, 568–570, 577, 580, 584, 585, 588
surfactants 103, 107
surgical resection 307
suspended membrane 1028
suspension 967
– vibration 959
suspension-level fabrication 967
sustainable internal pressure
– maximum 759
sustained drug delivery 269
switch
– two-state 19
switch design 1062
switches
– molecule-based 15
– monolayer 28
switching
– architecture 238
– devices 15
– energy 135
– speed 135
– time 1073
SWNT (single wall nanotube) 40, 52
– adsorption properties 63
– based FET 85
– based materials 64
– catalyst-based 61
– conductance 75
– electronic structure 66
– epoxy composite 82
– flexural modulus 67
– magneto-resistance 67
– matrix interaction 82
– production techniques 45
– rope 668, 670
– structure 41
– surface area 64
– tensile strength 67
– thermal conductivity 66
SWNT-PMMA composite 83
symmetric deformation mode 1054
sync pattern 946
synchronization 945
synthesis 100
– reactor 47
– yield 47
synthetic
– devices 281
– nanoporous membrane 313
– readback signal 941
system
– underdamped 894

T

tailoring of SAMs 841, 1006
tapping amplitude 529
tapping-mode 332, 373, 456, 501, 910
– AFM 456, 459
– etched silicon probe (TESP) 341
– resistance measurement 914
– tip assembly 507
targeting of nanomaterials 296
Taylor dispersion pattern 266
technical PVC 664
technological convergence 1139
Teflon layer 652
temperature
– annealing 227
– critical 423, 434, 1059
– dependence of friction 645
– domain 664
– effect 873
– regulation 720
– sensitive microcantilever 303
temperature-dependent resistance 118
template
– manufacturing 170, 176, 179
– synthesis 100
template-assisted synthesis 100
templates 103
templating technique 57
temporal scales 749
tensile
– load 1027
– maximum stress 783
– straining 1059
– stress 767, 1026, 1035, 1046
– test 1036
terabit 903
terabyte 901
test environment 824
tethering
– flexible 491
tetraarylmethane 13
tetracene 20
– channel 21
tetramethyl-aluminum hydroxide (TMAH) 204, 254
tetrapods 108
tetrathiofulvane (TTF) 916
T-filter 266
therapeutic
– bioactivity 312
– nanodevices 280
– nanomaterials 281
– nanotechnology 285
– photo-oxidation 299
thermal
– activation 894
– activation model of friction 884
– activation model of lubricated friction 887
– conductivity 125, 133
– drift 414, 417
– effect 642
– energy 481
– expansion coefficient 388, 1042
– expansion mismatch 1056
– fluctuation 633
– fluctuation forces 564
– fluctuations and velocity 890
– force 751

– frequency noise 415
– management 1112, 1122
– mismatch 1125
– noise 481, 891
– sensing 925
– vibration amplitude 377
thermocouples 123
thermodynamic forces 293
thermoelastic behavior 1040
thermoelectric
– applications 125, 133
– figure of merit 125, 133
– properties 122, 123
thermo-gravimetric analysis (TGA) 72
thermomechanical
– load 1040, 1058
– noise 433
– write/read 924
thermomechanics of multilayer film 1046
thermoplastics 257
thermopneumatic actuation 258
theta condition 561
thick film lubrication *see* elastohydrodynamic lubrication
thickness 1047
thickness of nanotubes 668
thin film 701, 707
thin oxide film 913
thin-film
– limit 1051
– lubrication 498
– microstructure 1040, 1041
thin-plate theory 1046, 1054
thiol 464, 837
three-axis accelerometer 233
three-digit input/output strings 20
three-dimensional force field spectroscopy 437
three-dimensional micromixers 265
three-input NOR gate 22
three-layer symmetric plate 1052
three-state molecular switch 18
three-terminal devices 31
three-way microvalve system 258
threshold potential 726
through wafer etching 1113
through-thickness
– average 1044
– cracking 807
thymine 10
Ti atom 405
TiAl alloy 675
TiC grains 508
tight-binding approximation 402
tilt angle of SAMs 855
time scales 721
timing field 943
timing recovery 945
TiO_2 400, 402, 425
– substrate 405
$TiO_2(100)$ 400
$TiO_2(110)$ 405
TiO_2-terminated layer 401
tip
– anion-terminated 399
– apex 435, 477, 655, 927
– artifact 392
– atom(s) 415
– atomic structure 383
– characterization 618
– deflection 503
– displacement 941
– Fe-coated 403
– ferromagnetic 441
– geometry 377
– hydrophilic 616
– load 933
– material 383
– mount 329
– oscillation 373
– oscillation amplitude 654
– performance 382
– preparation in UHV 635
– preparation method 330
– properties 382
– radius effect 339, 515, 813, 876, 878
– shape 611
– surface 477
– vibration 460
– vibration amplitude 664
tip-bound
– antigens 484
– biomolecule 303
tip-broadened image 374
tip–cantilever assembly 376
tip-induced atomic relaxation 435
tip-induced quantum dot 424
tip–liquid interface 531, 868
tip–molecule
– distance 419
– gap 406
– long-range force 406
tip–particle distance 29
tip–polymer interface 935
tip–sample 451
– contact 467
– dissipative interaction 468
– distance 388, 396, 399, 401, 435, 451, 459, 507
– electric field 656
– energy dissipation 389
– force 373, 388, 433, 436, 450, 453, 455, 460, 461
– force gradient 391
– gap 910
– interaction 391, 433, 441, 455, 456, 462, 654
– interaction force 608
– interaction potential 464
– interface 372
– junction 468
– potential 390
– separation 467, 608, 609
– system 664
tip–surface
– distance 406, 468
– interaction 490, 651
– potential 636
– separation 480
tip-terminated atom 400
tire pressure monitor 1094
tissue dendritic cells (DCs) 296
tissue engineering scaffolds 310
titin 485
TMR sources 969
Tomlinson model 631, 636
– finite temperature 642
– of friction 884
– one-dimensional 636
– two-dimensional 637
tooth enamel 675
top-down
– approach 10, 133
– materials 281
topographic
– AFM image 611
– images 331
topographical asymmetry 403
topography measurement 334
torsion mirror
– vertical 238
torsional plate 1068
torus model calculation 360
total internal reflection microscopy (TIRM) 550
touch mode architecture 228
Townsend electron avalanche theory 1077
toxicity monitoring 274
trabecular bone 679
track
– centerline 943, 945
– following 943
– mis-registration (TMR) 969
– pitch (TP) 943

track-etched
– polycarbonate membranes 102
– polymers 100
track-following controller 971
tracking servo loop 943
tracks per inch (TPI) 952
transducer component 302
transfer time 901
transformation
– strain 1041
– stress 1044
transistors 132
transition metal complexes 31
transition metal oxides 402
transitions between smooth and stick–slip sliding 585
translational microactuator 958
transmembrane channel 741
transmission 129
transmission electron microscopy (TEM) 111, 374, 521, 693
transplant rejection 311
transport properties of nanowires 115, 118
transversal piezo-resistive effect 356
transverse
– magnetoresistance 121
– midplane displacement 1055
– relaxation time (T_2) 305
traveling direction of the sample 346
Tresca criterion 695
triangular cantilever 339, 349, 354
triaryl 13
tribochemical
– oxidation 999
– reaction 531, 872
tribological
– characterization of coating 805
– computer simulations 721
tribological issues
– in MEMS 989
– in NEMS 989
tribological performance 996
– of coatings 822
tribological properties
– of SAM 841
– of silicon 996
tribometer 996
(tridecafluoro-1,1,2,2-tetrahydro-oct-1-yl) trichlorosilane (n-$C_6F_{13}CH_2CH_2SiCl_3$, FTS) 842
triethanolamine 14
triethoxysilane 644
trifluoromethyl-terminated SAM 843
triggering 288
– external 284
– strategy 298
trimer tip apex 452
true atomic resolution 389, 392, 434
true tip-sample interaction 608
truth table 17, 21
T-SLAM 663
tubulin monomer 740
tumor
– architecture 307
– associated antigens (TAAs) 307
– deposition 309
– properties 307
– targeting 307
– vasculature 307
tungsten 330
– sphere 633
– tip 330, 468, 614
tunneling
– current 327, 388, 389, 424
– detector 331
– junctions 25
– tip 431
turn-on voltage 117
two-body potentials 719
two-digit input strings 20
two-dimensional
– elasticity 754
– electron gas (2-DEG) 438
– electron system (2-DES) 428
two-layer beam 1045
two-state switch 19
two-terminal nanowire device 132

U

UHV environment 638
UHV-AVM 635
ultrahigh vacuum (UHV) 391, 418, 461, 607, 635
ultrasonic
– bonding 1119
– lubrication 513
– transducer 663
ultrasound triggering 299
ultrathin DLC coatings 795
umklapp processes 125
unbinding
– force 476, 481
– force distribution 485
– pathway 488
uncapped MEMS wafer 1097, 1098
uncoated monolithic cantilever 611
uncommon failure mode 1102
unconstrained binding 477
unidirectional electron transfer 28
unimolecular level 22
universality 752
unlubricated sample 879
unlubricated surfaces *see* dry surfaces
upward cantilever deflection 746
UV-LIGA lithography 267

V

vacuum encapsulation 1116, 1117, 1126
vacuum packaged MEMS 1118
vacuum packaging 231, 1116, 1121
van der Waals 607, 617, 621
– adhesion 616
– attraction 515
– contact 759
– force 372, 386, 398, 404, 406, 450, 544, 545, 550–554, 557, 558, 618
– interaction 58, 289, 402, 457, 843, 865
– surfaces 435
vanadium carbide 691
vapor deposition 104, 120
vapor grown
– carbon fiber 53
– carbon nanofiber 56
vapor-liquid-solid (VLS) mechanism 105
varactor diodes 241
variable capacitor 240
variable force mode 362
variable temperature STM
– setup 416
variable-temperature SLAM (T-SLAM) 663
vascular
– address system mapping 297, 298
– prosthesis 310
VCM loop compensator 972
vehicle stability 232
velocity
– critical 585, 587, 590, 591
velocity dependence of friction 644
velocity effect 871
Verlet algorithm 457
vertical coupling 329
vertical rms-noise 434
vertically aligned MWNT 59
Verwey transition temperature 439

very large-scale integration (VLSI) 922, 940
vibration 749
– external 329
vibratory rate gyroscope 232
vibromotor 236
Vickers
– hardness 674, 678, 695
– indentations 771
– indenter 765
vinylidene fluoride 404
viral life cycle 755
virgin single-crystal silicon 996
virtual jump distance 889
viruses 747
viscoelastic
– effect 468
– model 934
– properties 681
– relaxation time 731
– response 731
viscoelasticity 663, 702, 711
– mapping 505, 528
viscosity 730, 885
viscous
– damping 469
– force 569, 580, 584, 1061
VLS (Vapor-Liquid-Solid) 60
– growth method 116
– mechanism 60
– method 105, 108, 137
VLSI (very large scale integration) 922, 940
voice coil motor (VCM) 952
voltage bias 383
voltage-controlled oscillator (VCO) 239, 946
voltage-displacement function 1068
voltage-to-force gain 956
von Karman plate theory 1055
vortex in superconductor 440
V-shaped cantilever 341, 610, 634

W

W tip 330
wafer
– curvature technique 1034
– fabrication 1087
– saw dilemma 1097, 1098
wafer-level vacuum packaging 1122
wafer-to-wafer
– vacuum packaging 1114
– variation 1072
waste disposal concern 1090
water 613
– capillary force 847
– meniscus 461
water vapor 691, 695
– content 824
Watson-Crick base pairing 484
wear 498, *see* damage, 618, 793, 809
– contribution to friction 650
– control 832
– damage 824
– damage mechanism 823
– debris 521
– depths 1000
– measurement 325
– mechanical 263
– mechanism 522
– of tip 728
– performance 866
– process 822
– region 523
– resistance 822, 823, 853, 856, 879, 997, 1008
– study 879
– test 822
wearless
– friction 884
– static friction 726
Weibull
– distribution 774
– distribution function 1125
– statistics 1036
weight function 390
weighting functions for µ -synthesis 976
well-aligned nanowires 111
wet (chemical) etching 254
wet etching in HF 247
wettability 846
wetting 569
– lubricants 892
white-noise driven system 889
wire boundary scattering 121
wire cantilever 339
wireless communication 1094
work
– hardening 704, 709
– of adhesion 844, 847, 1011
– of indentation 701
write/read scheme 931
writing mechanism 932

X

xenon 417
XNOR 17
X-ray
– analysis 115
– diffraction (XRD) patterns 103
– lithographic techniques 286

Y

yield point 570, 571, 585
– load 703
yield stress 703
yielding 1055
Young’s modulus 81, 346, 362, 377, 415, 611, 646, 668, 677, 779, 1023, 1024, 1044, 1071
– measurement 1028
Young–Dupre equation 846
Young–Laplace equation 612

Z

Z-15 530, 862, 874–876, 878, 1006
– film 531, 879
– lubricant 1003
– lubricant film 867
– properties 863
z-axis accelerometer 230
z-axis gyroscope 233
Z-DOL 530, 614, 862, 869
– partially bonded film 880
– properties 863
Z-DOL(BW) 868, 874, 877–879, 1006
– film 530, 867, 1003
zeolites 54
zeta potential 261
zig-zag axis 42
zig-zag-type SWNT 42
zinc 704
zipper actuator 1070
Zn nanowire 120, 123
ZnO nanowire 135

Victor E. Borisenko
Stefano Ossicini

WILEY-VCH

What is what in the Nanoworld

A Handbook on Nanoscience and Nanotechnology

Second, Completely Revised and Enlarged Edition



Victor E. Borisenko and Stefano Ossicini

What is What in the Nanoworld

A Handbook on Nanoscience and Nanotechnology

Second, Completely Revised and Enlarged Edition

WILEY-VCH Verlag GmbH & Co. KGaA

Victor E. Borisenko
Stefano Ossicini
What is What in the Nanoworld

Related Titles

Vedmedenko, E.

Competing Interactions and Patterns in Nanoworld

2007
ISBN: 978-3-527-40484-1

Wolf, E. L.

Nanophysics and Nanotechnology

An Introduction to Modern Concepts in Nanoscience

2006
ISBN: 978-3-527-40651-7

Poole, C. P., Owens, F. J.

Introduction to Nanotechnology

2003
ISBN: 978-0-471-07935-4

Balzani, V., Credi, A., Venturi, M.

Molecular Devices and Machines

A Journey into the Nanoworld

2003
ISBN: 978-3-527-30506-3

Victor E. Borisenko and Stefano Ossicini

What is What in the Nanoworld

A Handbook on Nanoscience and Nanotechnology

Second, Completely Revised and Enlarged Edition

WILEY-VCH Verlag GmbH & Co. KGaA

The Authors

Victor E. Borisenko
University of Informatics
and Radioelectronics
Minsk, Belarus

Stefano Ossicini
University of Modena and Reggio Emilia
Faculty of Engineering
Reggio Emilia, Italy

Cover
Silver tip for scanning near-field optical microscopy, sharpened by focused ion beam milling. (SEM image).
Experiment: Gian Carlo Gazzadi, S3 Center (INFM-CNR), Modena and Pietro Gucciardi, CNR-IPCF, Messina.
Artwork: Lucia Covi. From ''Blow-up. Images from the nanoworld'' (www.s3.infm.it/blowup); Copyright S3, 2007.

All books published by Wiley-VCH are carefully produced. Nevertheless, authors, editors, and publisher do not warrant the information contained in these books, including this book, to be free of errors. Readers are advised to keep in mind that statements, data, illustrations, procedural details or other items may inadvertently be inaccurate.

Library of Congress Card No.: applied for
British Library Cataloguing-in-Publication Data
A catalogue record for this book is available from the British Library.

Bibliographic information published by the Deutsche Nationalbibliothek
The Deutsche Nationalbibliothek lists this publication in the Deutsche Nationalbibliografie; detailed bibliographic data are available in the Internet at <http://dnb.d-nb.de>.

© 2008 WILEY-VCH Verlag GmbH & Co. KGaA, Weinheim

All rights reserved (including those of translation into other languages). No part of this book may be reproduced in any form – by photoprinting, microfilm, or any other means – nor transmitted or translated into a machine language without written permission from the publishers. Registered names, trademarks, etc. used in this book, even when not specifically marked as such, are not to be considered unprotected by law.

Typesetting Laserwords Private Ltd, Chennai, India
Printing Strauss GmbH, Mörlenbach
Binding Litges & Dopf GmbH, Heppenheim

Printed in the Federal Republic of Germany
Printed on acid-free paper

ISBN: 978-3-527-40783-5

Contents

Preface to the Second Edition *VII*

Preface to the First Edition *IX*

Source of Information *XI*

A From Abbe's principle to Azbel'–Kaner cyclotron resonance *1*

B From B92 protocol to Burstein–Moss shift *27*

C From cage compound to cyclotron resonance *53*

D From D'Alembert equation to Dzyaloshinskii–Moriya interaction *81*

E From (e,2e) reaction to Eyring equation *109*

F From Fabry–Pérot resonator to FWHM (full width at half maximum) *133*

G From gain-guided lasers to gyromagnetic frequency *159*

H From habit plane to hyperelastic scattering *175*

I From ideality factor to isotropy (of matter) *199*

J From Jahn–Teller effect to Joule's law of electric heating *207*

K From Kane model to Kuhn–Thomas–Reiche sum rule *211*

L From lab-on-a-chip to Lyman series *225*

M From Mach–Zender interferometer to Murrell–Mottram potential *251*

N From NAA (neutron activation analysis) to Nyquist–Shannon sampling theorem *285*

O From octet rule to oxide *299*

P From PALM (photoactivable localization microscopy) to pyrrole *307*

Q From *Q*-control to qubit *341*

R From Rabi flopping to Rydberg gas *363*

S From Saha equation to synergetics *381*

T From Talbot's law to type II superconductors *443*

U From ultraviolet photoelectron spectroscopy (UPS) to Urbach rule *461*

V From vacancy to von Neumann machine *465*

W From Waidner–Burgess standard to Wyckoff notation *473*

X From XMCD (X-ray magnetic circular dichroism) to XRD (X-ray diffraction) *483*

Y From Yasukawa potential to Yukawa potential *487*

Z From Zeeman effect to Zundel ion *489*

A list and a presentation of Scientific Journals which contain the stem *Nano* in their title *493*

Abbreviations for the scientific journals which appear as sources in the text *507*

Appendix – main properties of intrinsic (or lightly doped) semiconductors *513*

Preface to the Second Edition

This is the second, enlarged and updated edition of our book. From more than 1400 entries in the first edition we have now reached about 2000 entries. Moreover a large number of the old entries have been extended. The gallery of illustrations is enriched by new figures, and new tables are added throughout the book.

The presented terms, phenomena, regulations, experimental and theoretical tools are very easy to consult since they are arranged in alphabetical order, with a chapter for each letter. The great majority of the terms have additional information in the form of notes such as *''First described in: . . .'', ''Recognition: . . .'', ''More details in: . . .''*, thus giving a historical retrospective of the subject with references to further sources of extended information, which can be articles, books, review articles, or web sites. In particular, in this second edition we have tried, for the overwhelming majority of the items, to find out who was the initiator and when and where the term was born, defined or first discussed. We think that all these additional notes are quite useful, since they give the possibility to all the readers to start independently their personal research.

Only four years separate this second edition from the first; nevertheless we have seen a true explosion of research in nanoscience and developments in nanotechnologies. One measure of the emergence of these fields is the growth of the literature dedicated to the new disciplines. Nanoscience and nanotechnology have, in the last years, witnessed not only an explosive growth in the number of relevant and important ''classical'' scientific journals, which have devoted, more and more, an increasing proportion of their published papers to ''nano''-related research, but also in the number of new journals which contain the stem ''nano'' in their title. A list of 62 ''nano'' journals has been added to the Appendix of the book. Only a few of them appeared before 2000 and most of them started their activity in the last four years.

In reviewing the first edition of this book Professor Vincenzo Balzani correctly pointed out that *''the actual Nanoworld is very large and comprises at least four regions that can be labelled Physics, Chemistry, Biology and Engineering. . .. The four component regions of the nanoscience and nanotechnology realm partly overlap but often ignore one another. Even worse, in the overlapping territories they do not speak the same language to such an extent that, in some cases, they seem even to obey different laws. Clearly,* *cooperation among physicists, chemists, biologists and engineers, which is of course essential for the progress of nanoscience and nanotechnology, is often hampered by such language barriers''*. Looking at the titles of the new journals listed in the Appendix, we see that the actual nanoworld is even larger. The concepts like nanoethics, nanoeducation, nanomedicine, nanotoxicology, and so on are new actors in the nanoarena. Moreover, fine art has now entered the nanoworld. The image on the front page of this edition is part of a book ''Blow-up. Images from the nanoworld'' born from the collaboration between Lucia Covi, an Italian photographer, and the CNR-INFM Research Center S^3*-nanoStructures and bioSystems at Surfaces* in Modena, Italy, where one of the authors of this book is active. Commenting on this picture (a silver tip for near-field scanning optical microscopy obtained by focused ion milling) in the foreword to the ''Blow-up'' book, Professor Roald Hoffmann, the Nobel Laureate in chemistry 1981, has labeled it *''a digital Tower of Babel''*. The Tower of Babel has to do with the myth of the birth of all the different languages; we hope this book can help in breaking these language barriers.

Minsk	*Victor E. Borisenko*
Modena/Reggio Emilia	*Stefano Ossicini*
January 2008	

Preface to the First Edition

There's Plenty of Room at the Bottom
Richard P. Feynman 1959
There's even more Room at the Top
Jean-Marie Lehn 1995

Nanotechnology and nanoscience are concerned with material science and its application at, or around, the nanometer scale (1 nm $= 10^{-9}$ m, 1 billionth of a meter). The nanoscale can be reached either from the top down, by machining to smaller and smaller dimension, or from the bottom up, by exploiting the ability of molecules and biological systems to self-assemble tiny structures. Individual inorganic and organic nanostructures involve clusters, nanoparticles, nanocrystals, quantum dots, nanowires, and nanotubes, while collections of nanostructures involve arrays, assemblies, and superlattices of individual nanostructures.

Rather than a new specific area of science, nanoscience is a new way of thinking. Its revolutionary potential lies in its intrinsic multidisciplinarity. Its development and successes strongly depend on efforts from, and fruitful interactions among, physics, chemistry, mathematics, life sciences, and engineering. This handbook intends to contribute to a broad comprehension of what are nanoscience and nanotechnology.

It is an introductory, reference handbook that first summarizes terms and definitions, most important phenomena, regulations, and experimental and theoretical tools discovered in physics, chemistry, technology and the application of nanostructures. We present a representative collection of fundamental terms and most important supporting definitions taken from general physics and quantum mechanics, material science and technology, mathematics and information theory, organic and inorganic chemistry, solid-state physics and biology. As a result, fast progressing nanoelectronics and optoelectronics, molecular electronics and spintronics, nano-fabrication and -manufacturing, bioengineering and quantum processing of information, an area of fundamental importance for the information society of the twenty-first century, are covered. More than 1300 entries, from a few sentences to a page in length, are given for readers ranging from beginners to professionals.

The book is organized as follows. Terms and definitions are arranged in alphabetic order. Those written in an article body with bold letters have extended details arranged alphabetically. Each entry in the book interprets the term or definition under consideration and briefly presents the main features of the phenomena behind it. The great majority of the terms are accompanied with additional information in the form of notes such as *"First described in: . . .", "Recognition: . . .", "More details in: . . ."*, thus giving a historical perspective of the subject with reference to further sources of extended information, which can be articles, books, review articles, or web sites. This makes it easier for the willing reader to reach a deeper insight. Bold characters in formulas symbolize vectors and matrices, while normal characters are scalar quantities. Symbols and constants of a general nature are handled consistently through the book (see **Fundamental Constants Used in Formulas**). They are used according to the IUPAP convention.

The book will help undergraduate and PhD students, teachers, researchers and scientific managers to understand properly the language used in modern nanoscience and nanotechnology. It will also appeal to readers from outside the nanoworld community, in particular to scientific journalists.

Comments and proposals related to the book will be appreciated and can be sent to borisenko@dsuir.unibel.by and/or to ossicini@unimore.it.

It is a pleasure for us to acknowledge our colleagues who have supported this work. Their contribution ranges from writing and correction of particular articles to critical comments and useful advice. In particular, we wish to thank (in alphabetical order) F. Arnaud d'Avitaya, L. J. Balk, C. M. Bertoni, V. P. Bondarenko, E. Degoli, J. Derrien, R. Di Felice, P. Facci, H. Fuchs, N. V. Gaponenko, S. V. Gaponenko, L. I. Ivanenko, G. F. Karpinchik, S. Y. Kilin, S. K. Lazarouk, E. Luppi, F. Manghi, R. Magri, M. Michailov, D. B. Migas, V. V. Nelaev, L. Pavesi, N. A. Poklonski, S. L. Prischepa, V. L. Shaposhnikov, G. Treglia, and A. Zaslavsky.

Minsk *Victor E. Borisenko*
Modena/Reggio Emilia *Stefano Ossicini*
April 2004

Sources of Information

Besides their personal knowledge and experience and the scientific journals and books cited in the text, the authors also used the following sources of information:

Encyclopedias and Dictionaries

1. *Encyclopedic Dictionary of Physics*, edited by J. Thewlis, R. G. Glass, D. J. Hughes, A. R. Meetham (Pergamon Press, Oxford 1961).
2. McGraw–Hill *Dictionary of Physics and Mathematics*, edited by D. N. Lapedes (McGraw–Hill Book Company, New York 1978).
3. Landolt-Bornstein. *Numerical Data and Functional Relationships in Science and Technology*, v. 17, edited by O. Madelung, M. Schultz, H. Weiss (Springer, Berlin 1982).
4. McGraw–Hill *Encyclopedia of Electronics and Computers*, edited by C. Hammer (McGraw–Hill Book Company, New York 1984).
5. *Encyclopedia of Semiconductor Technology*, edited by M. Grayson (John Wiley & Sons, New York 1984).
6. *Encyclopedia of Physics*, edited by R. G. Lerner, G. L. Trigg (VCH Publishers, New York 1991).
7. *Physics Encyclopedia*, edited by A. M. Prokhorov, vols. 1–5 (Bolshaya Rossijskaya Encyklopediya, Moscow 1998) – in Russian.
8. *Encyclopedia of Applied Physics*, Vols. 1–25, edited by G. L. Trigg (Wiley VCH, Weinheim 1992–2000).
9. *Encyclopedia of Physical Science and Technology*, Vols. 1–18, edited by R. A. Meyers (Academic Press, San Diego 2002).
10. *Handbook of Nanotechnology*, edited by B. Bhushan (Springer, Berlin 2004).

Sources of Information

Books

1. G. Alber, T. Beth, M. Horodecki, P. Horodecki, R. Horodecki, M. Rötteler, H. Weinfurter, R. Werner, A. Zeilinger, *Quantum Information* (Springer, Berlin, 2001).
2. G. B. Arfken, H. J. Weber, *Mathematical Methods for Physicists* (Academic Press, San Diego, 1995).
3. P. W. Atkins, J. De Paula, *Physical Chemistry* (Oxford University Press, Oxford, 2001).
4. V. Balzani, M. Venturi, A. Credi, *Molecular Devices and Machines: A Journey into the Nanoworld* (Wiley–VCH, Weinheim, 2003).
5. F. Bassani, G. Pastori Parravicini, *Electronic and Optical Properties of Solids* (Pergamon Press, London, 1975).
6. D. Bimberg, M. Grundman, N. N. Ledentsov, *Quantum Dot Heterostructures* (John Wiley & Sons, London, 1999).
7. W. Borchardt-Ott, *Crystallography*, Second edition (Springer, Berlin, 1995).
8. V. E. Borisenko, S. Ossicini, *What is What in the Nanoworld* (Wiley–VCH, Weinheim, 2004).
9. M. Born, E. Wolf, *Principles of Optics*, Seventh (expanded) edition (Cambridge University Press, Cambridge, 1999).
10. J. H. Davies, *The Physics of Low-Dimensional Semiconductors* (Cambridge University Press, Cambridge, 1995).
11. *DNA based Computers* edited by R. Lipton, E. Baum (Am. Math. Soc., Providence, 1995).
12. M. S. Dresselhaus, G. Dresselhaus, P. Eklund, *Science of Fullerenes and Carbon Nanotubes* (Academic Press, San Diego, 1996).
13. D. K. Ferry, S. M. Goodnick, *Transport in Nanostructures* (Cambridge University Press, Cambridge, 1997).
14. *Frontiers in Surface Nanophotonics*, edited by D. L. Andrews and Z. Gaburro (Springer, Berlin, 2007).
15. S. V. Gaponenko, *Optical Properties of Semiconductor Nanocrystals* (Cambridge University Press, Cambridge, 1998).
16. W. A. Harrison, *Electronic Structure and the Properties of Solids* (W. H. Freeman & Company, San Francisco, 1980).
17. H. Haug, S. W. Koch, *Quantum Theory of the Optical and Electronic Properties of Semiconductors* (World Scientific, Singapore, 1994).
18. S. Hüfner, *Photoelectron Spectroscopy* (Springer, Berlin, 1995).
19. Y. Imri, *Introduction to Mesoscopic Physics* (Oxford University Press, Oxford, 2002).

20. L. E. Ivchenko, G. Pikus, *Superlattices and Other Heterostructures: Symmetry and other Optical Phenomena* (Springer, Berlin, 1995).
21. C. Kittel, *Elementary Solid State Physics* (John Wiley & Sons, New York, 1962).
22. C. Kittel, *Quantum Theory of Solids* (John Wiley & Sons, New York, 1963).
23. C. Kittel, *Introduction to Solid State Physics*, seventh edition (John Wiley & Sons, New York, 1996).
24. L. Landau, E. Lifshitz, *Quantum Mechanics* (Addison–Wesley, London, 1958).
25. O. Madelung, *Semiconductors: Data Handbook* (Springer, Berlin, 2004).
26. G. Mahler, V. A. Weberrus, *Quantum Networks: Dynamics of Open Nanostructures* (Springer, New York, 1998).
27. L. Mandel, E. Wolf, *Optical Coherence and Quantum Optics* (Cambridge University Press, Cambridge, 1995).
28. *Molecular Electronics: Science and Technology* edited by A. Aviram, M. Ratner (Academy of Sciences, New York, 1998).
29. *Nanobiotechnology. Concepts, Applications and Perspectives*, edited by C. M. Niemeyer and C. A. Mirkin (Wiley–VCH, Weinheim, 2004).
30. *Nanoelectronics and Information Technology*, edited by R. Waser (Wiley–VCH, Weinheim, 2003).
31. *Nanostructured Materials and Nanotechnology*, edited by H. S. Nalwa (Academic Press, London, 2002).
32. R. C. O'Handley, *Modern Magnetic Materials: Principles and Applications* (Wiley & Sons, New York, 1999).
33. S. Ossicini, L. Pavesi, F. Priolo, *Light Emitting Silicon for Microphotonics*, Springer Tracts on Modern Physics **194** (Springer, Berlin, 2003).
34. J. Pankove, *Optical Processes in Semiconductors* (Dover, New York, 1971).
35. N. Peyghambarian, S. W. Koch, A. Mysyrowicz, *Introduction to Semiconductor Optics* (Prentice Hall, Englewood Cliffs, New Jersey, 1993).
36. C. P. Poole, F. J. Owens, *Introduction to Nanotechnology* (Wiley–VCH, Weinheim, 2003).
37. P. N. Prasad *Nanophotonics* (Wiley–VCH, Weinheim, 2004).
38. C. N. Rao, P. J. Thomas, G. U. Kulkarni, *Nanocrystals: Synthesis, Properties and Applications* (Springer, Berlin, 2007).
39. S. Reich, C. Thomsen, J. Maultzsch, *Carbon Nanotubes* (Wiley–VCH, Weinheim, 2004).
40. E. Rietman, *Molecular Engineering of Nanosystems* (Springer, New York, 2000).

41. *Roadmap of Scanning Probe Microscopy*, edited by S. Morita (Springer, Berlin, 2007).
42. K. Sakoda, *Optical Properties of Photonic Crystals* (Springer, Berlin, 2001).
43. *Silicon Photonics*, edited by L. Pavesi and D. J. Lockwood (Springer, Berlin, 2004).
44. S. Sugano, H. Koizumi, *Microcluster Physics* (Springer, Berlin, 1998).
45. *The Chemistry of Nanomaterials. Synthesis, Properties and Applications*, edited by C. N. Rao, A. Müller, A. K. Cheetham (Wiley–VCH, Weinheim, 2004).
46. L. Theodore, R. G. Kunz, *Nanotechnology. Environmental Implications and Solutions* (Wiley–VCH, Weinheim, 2005).
47. J. D. Watson, M. Gilman, J. Witkowski, M. Zoller, *Recombinant DNA* (Scientific American Books, New York, 1992).
48. E. L. Wolf, *Nanophysics and Nanotechnology – Second Edition* (Wiley–VCH, Weinheim, 2006).
49. S. N. Yanushkevich, V. P. Shmerko, S. E. Lyshevski, *Logic Design of NanoICs* (CRC Press, Boca Raton, 2004).
50. P. Y. Yu, M. Cardona, *Fundamentals of Semiconductors* (Springer, Berlin, 1996).

Sources of Information

Web sites

http://www.britannica.com	Encyclopedia Britannica
http://www.Google.com	Scientific Search Engine
http://www.wikipedia.com/	Encyclopedia
http://scienceworld.wolfram.com/	Science world. World of physics and mathematics. Eric Weisstein's World of Physics
http://www.photonics.com/dictionary/	PHOTONICS DIRECTORY
http://www.nobel.se/physics/laureates/index.html	The Nobel Prize Laureates
http://www-history.mcs.st-and.ac.uk/history/	MATHEMATICS ARCHIVE
http://www.chem.yorku.ca/NAMED/	Named Things in Chemistry and Physics
http://www.hyperdictionary.com/	HYPERDICTIONARY
http://www.wordreference.com/index.htm	WordReference.com. French, German, Italian and Spanish Dictionary with Collins Dictionaries
http://web.mit.edu/redingtn/www/netadv/	The Net Advance of Physics. Review Articles and Tutorials in an Encyclopedic Format

Sources of Information

Fundamental Constants Used in Formulas

$a_B = 5.29177 \times 10^{-11}$ m	Bohr radius
$c = 2.99792458 \times 10^{8}$ m/s	light speed in vacuum
$e = 1.602177 \times 10^{-19}$ C	charge of an electron
$h = 6.626076 \times 10^{-34}$ J·s	Planck constant
$h = h/2\pi = 1.054573 \times 10^{-34}$ J·s	reduced Planck constant
$\mathrm{i} = \sqrt{-1}$	imaginary unit
$k_B = 1.380658 \times 10^{23}$ J/K (8.617385×10^{5} eV/K)	Boltzmann constant
$m_0 = 9.10939 \times 10^{-31}$ kg	electron rest mass
$n_A = 6.0221367 \times 10^{23}\mathrm{mol}^{-1}$	Avogadro constant
$R_0 = 8.314510$ J/(K·mol)	universal gas constant
$r_e = 2.817938$ m	radius of an electron
$\alpha = \mu_0 c e^2/2h = 7.297353 \times 10^{-3}$	fine structure constant
$\varepsilon_0 = 8.854187817 \times 10^{-12}$ F/m	permittivity of vacuum
$\mu_0 = 4\pi \times 10^{7}$ H/m	permeability of vacuum
$\mu_B = 9.27402 \times 10^{24}$ A·m^2	Bohr magneton
$\pi = 3.14159$	
$\sigma = 5.6697 \times 10^{-5}$ erg/(cm^2·s·K)	Stefan–Boltzmann constant

A

From Abbe's principle to Azbel'–Kaner cyclotron resonance

Abbe's principle states that the smallest distance that can be resolved between two lines by optical instruments is proportional to the wavelength and inversely proportional to the angular distribution of the light observed ($d_{min} = \lambda / n \sin \alpha$). It establishes a prominent physical problem, known as the ''diffraction limit''. That is why it is also called **Abbe's resolution limit**. No matter how perfect an optical instrument is, its resolving capability will always have this diffraction limit. The limits of light microscopy are thus determined by the wavelength of visible light, which is 400–700 nm; the maximum resolving power of the light microscope is limited to about half the wavelength, typically about 300 nm. This value is close to the diameter of a small **bacterium**, and **virus**es, which cannot therefore be visualized. To attain sublight microscopic resolution, a new type of instrument would be needed; as we know today, accelerated electrons, which have a much smaller wavelength, are used in suitable instruments to scrutinize structures down to the 1 nm range.

The diffraction limit of light was first surpassed by the use of **scanning near-field optical microscopes**; by positioning a sharp optical probe only a few nanometers away from the object, the regime of far-field wave physics is circumvented, and the resolution is determined by the probe–sample distance and by the size of the probe which is scanned over the sample.

Also, fluorescence light microscopy based techniques have been developed in order to break the diffraction barrier, as in the case of **fluorescence nanoscopy**.

First described in: E. Abbe, *Beiträge zur Theorie des Mikroskops und der mikroskopischen Wahrnehmung*, Schultzes Archiv für mikroskopische Anatomie **9**, 413–668 (1873).

Abbe's resolution limit → **Abbe's principle**.

aberration – any image defect revealed as distortion or blurring in optics. This deviation from perfect image formation can be produced by optical lenses, mirrors and electron lens systems. Examples are astigmatism, chromatic or lateral aberration, coma, curvature of field, distortion, and spherical aberration.

In astronomy, it is an apparent angular displacement in the direction of motion of the observer of any celestial object due to the combination of the velocity of light and of the velocity of the observer.

***ab initio* (approach, theory, calculations)** – Latin meaning ‘‘from the beginning’’. It supposes that primary postulates, also called first principles, form the background of the referred theory, approach or calculations. The primary postulates are not so directly obvious from experiment, but owe their acceptance to the fact that conclusions drawn from them, often by long chains of reasoning, agree with experiment in all of the tests which have been made. For example, calculations based on the **Schrödinger** wave **equation**, as well as on the basis of **Newton equations** of motion or any other fundamental equations, are considered to be *ab initio* calculations.

Abney's law states that the shift in apparent hue of spectral color that is desaturated by addition of white light is toward the red end of the spectrum if the wavelength is below 570 nm and toward the blue if it is above.

First described in: W. Abney, E. R. Festing, *Colour photometry*, Phil. Trans. Roy. Soc. London **177**, 423–456 (1886).

More details in: W. Abney, *Researches in colour vision* (Longmans & Green, London, 1913).

Abrikosov vortex – a specific arrangement of lines of a magnetic field in a **type II superconductor**.

First described in: A. A. Abrikosov, *An influence of the size on the critical field for type II superconductors*, Doklady Akademii Nauk SSSR **86**(3), 489–492 (1952) – in Russian.

Recognition: in 2003 A. A. Abrikosov, V. L. Ginzburg, A. J. Leggett received the Nobel Prize in Physics for pioneering contributions to the theory of superconductors and superfluids.

See also www.nobel.se/physics/laureates/2003/index.html.

More details in: A. A. Abrikosov, Nobel Lecture: *Type-II superconductors and the vortex lattice*, Rev. Mod. Phys. **76**(3), 975–979 (2004).

absorption – a phenomenon arising when electromagnetic radiation or atomic particles enter matter. In general, two kinds of attenuation accompany the passage of radiation and particles through matter, which are absorption and scattering. Both obey the law $I = I_0\exp(-\alpha x)$, where I_0 is the intensity (flux density) of radiation entering the matter, and I is the intensity depth x. In the absence of scatter, α is the **absorption coefficient**, and in the absence of absorption, α is the scattering coefficient. If both forms of attenuation are present, α is termed the total absorption coefficient → **dielectric function**.

acceptor (atom) – an impurity atom, typically in semiconductors, which accepts electron(s). Acceptor atoms usually form electron energy levels slightly higher than the uppermost field energy band, which is the valence band in semiconductors and dielectrics. An electron from this band is readily excited into the acceptor level.

The consequent deficiency in the previously filled band contributes to the hole conduction.

achiral → **chirality**.

acoustic phonon – a quantum of excitation related to an acoustic mode of atomic vibrations in solids → **phonon**.

actinic – pertaining to electromagnetic radiation capable of initiating photochemical reactions, as in photography or the fading of pigments.

actinodielectric – a dielectric exhibiting an increase in electrical conductivity when electromagnetic radiation is incident upon it.

activation energy – an energy in excess over a ground state, which must be added to a system to allow a particular process to take place.

adatom – an atom adsorbed on a solid surface.

adduct – a chemical compound that forms from the addition of two or more substances. The term comes from Latin meaning ''drawn toward''. An adduct is a product of the direct addition of two or more distinct molecules, resulting in a single reaction product containing all atoms of all components, with formation of two chemical bonds and a net reduction in bond multiplicity in at least one of the reactants. The resultant is considered a distinct molecular species. In general, the term is often used specifically for products of addition reactions.

adiabatic approximation is used to solve the **Schrödinger equation** for electrons in solids. It assumes that a change in the coordinates of a nucleus passes no energy to electrons, that is the electrons respond adiabatically, which then allows the decoupling of the motion of the nuclei and electrons → **Born-Oppenheimer approximation**.

adhesion – the property of a solid to cling to another solid controlled by intermolecular forces at their interface.

adiabatic principle – perturbations produced in a system by altering slowly external conditions resulting, in general, in a change in the energy distribution in it, but leaving the phase integrals unchanged.

adiabatic process – a thermodynamic procedure which take place in a system without an exchange of heat with surroundings.

adjacent charge rule states that it is possible to write formal electronic structures for some molecules where adjacent atoms have formal charges of the same sign. In the Pauling formulation (1939), it states that such structures will not be important owing to instability resulting from the charge distribution.

adjoint operator – an operator **B** such that the inner products ($\mathbf{A}x,y$) and ($x,\mathbf{B}y$) are equal for a given operator **A** and for all elements x and y of the **Hilbert space**. It is also known as **associate operator** and **Hermitian conjugate operator**.

adjoint wave functions – functions in the Dirac electron theory which are formed by applying the **Dirac matrix** to the **adjoint operators** of the original wave functions.

admittance – a measure of how readily alternating current will flow in an electric circuit. It is the reciprocal of **impedance**. The term was introduced by Heaviside (1878).

adsorption – a type of **absorption**, in which only the surface of a matter acts as the absorbing medium. **Physisorption** and **chemisorption** are distinguished as adsorption mechanisms.

Term coined by: H. Kayser *Über die Verdichtung von Gasen an Oberflächen in ihrer Abhängigkeit von Druck und Temperatur*, Ann. Phys. **12**, 526–547 (1880).

AES – an acronym for **Auger electron spectroscopy**.

affinity → **electron affinity**.

AFM – an acronym for **atomic force microscopy**.

Aharonov–Bohm effect – the total amplitude of electron waves at a certain point oscillates periodically with respect to the magnetic flux enclosed by the two paths due to the interference effect. The design of the interferometer appropriate for experimental observation of this effect is shown in Figure A.1. Electron waves come from the waveguide to left terminal, split into two equal amplitudes going around the two halves of the ring, meet each other and interfere in the right part of the ring, and leave it through the right terminal. A small solenoid carrying magnetic flux Φ is positioned entirely inside the ring so that its magnetic field passes through the annulus of the ring. It is preferable to have the waveguide sufficiently small in order to restrict a number of possible coming electron modes to one or a few.

The overall current through the structure from the left port to the right one depends on the relation between the length of the ring arms and the inelastic mean free path of electrons in the ring material. If this relation meets the requirements for quasi-ballistic transport, the current is determined by the phase interference of the electron waves at the exit (right) terminal. The vector potential **A** of the magnetic field passing through the ring annulus is azimuthal. Hence electrons travelling in either arms of the ring move either parallel or antiparallel to the vector potential. As a result, there is a difference in the phases of the electron waves coming to the exit port from different arms. It is defined to be $\Delta\Phi = 2\pi(\Phi/\Phi_0)$, where $\Phi_0 = h/e$ is the quantum of flux. The interference of the electron waves appears to be periodic in the number of flux quanta passing through the ring. It is constructive when Φ is a multiple of Φ_0 and destructive halfway between. It produces a periodic modulation in the transverse conductance (resistance) of the ring by the magnetic field, which is known as the magnetic Aharonov–Bohm effect. It is worthwhile to note here that real devices hardly meet the requirements for observation of ‘‘pure’’ Aharonov–Bohm effect. The point is that the magnetic field penetrates the arms of the interferometer, not just the area enclosed by them. This leads to additional current variations at high magnetic fields, while the enclosed flux dominates at low magnetic fields.

First described in: Y. Aharonov, D. Bohm, *Significance of electromagnetic potentials in the quantum theory*, Phys. Rev. **115**(3), 485–491 (1959).



Figure A.1 Schematic layout of the interferometer for observation of the Aharonov–Bohm effect. Small solenoid inside the ring produces the magnetic field of the flux Φ enclosed between the two arms and characterized by the vector potential **A**.

Aharonov–Casher effect supposes that a beam of neutral particles with magnetic dipole moments passing around opposite sides of a line charge will undergo a relative quantum phase shift. The effect has a ‘‘duality’’ with the **Aharonov–Bohm effect**, where charged particles passing around a magnetic solenoid experience a phase shift despite, it is claimed, experiencing no classical force. It is pointed out that a magnetic dipole particle passing a line charge does indeed experience a classical electromagnetic force in the usual electric-current model for a magnetic dipole. This force will produce a relative lag between dipoles passing on opposite sides of the line charge, and the classical lag then leads to a quantum phase shift. Thus, the effect has a transparent explanation as a classical lag effect.

First described in: Y. Aharonov, A. Casher, *Topological quantum effects for neutral particles*, Phys. Rev. Lett. **53**(4), 319–321 (1984).

Airy equation – the second order differential equation $d^2y/dx^2 = xy$, also known as the **Stokes equation**. Here x represents the independent variable and y is the value of the function.

First described in: G. B. Airy, Trans. Camb. Phil. Soc. **6**, 379 (1838); G. B. Airy, *An Elementary Treatise on Partial Differential Equations* (1866).

Airy functions – solutions of the **Airy equation**. The equation has two linearly independent solutions, conventionally taken as the Airy integral functions Ai(x) and Bi(x). They are plotted in Figure A.2. There are no simple expressions for them in terms of elementary functions, while for large absolute values of x: $\mathrm{Ai}(x) \sim \pi^{-1/2}x^{-1/4}\exp[-(2/3)x^{3/2}]$, $\mathrm{Ai}(-x) \sim (1/2)\pi^{-1/2}x^{-1/4}\cos[-(2/3)x^{3/2} - \pi/4]$. Airy functions arise in solutions of the **Schrödinger equation** for some particular cases.

First described in: G. B. Airy, *An Elementary Treatise on Partial Differential Equations* (1866).



Figure A.2 Airy functions.

Airy spirals – spiral interference patterns formed by quartz cut perpendicularly to the axis in convergent circularly polarized light.

Recognition: in 1831 G. B. Airy received the Copley Medal of the Royal Society for their studies on optical subjects.

aldehydes – organic compounds that have at least one hydrogen atom bonded to the **carbonyl group** (>C=O). These may be RCHO or ArCHO compounds with R representing an **alkyl group** ($-C_nH_{2n+1}$) and Ar representing an **aromatic ring**.

algorithm – a set of well-defined rules for the solution of a problem in a finite number of steps.

aliphatic compound – an organic compound in which carbon atoms are joined together in straight or branched chains. The simplest aliphatic compound is methane

(CH_4). Most aliphatic compounds provide exothermic combustion reactions, thus allowing their use as a fuel.

alkanes → **hydrocarbons**.

alkenes → **hydrocarbons**.

alkyl groups → **hydrocarbons**.

allotropy – the property of a chemical element to exist in two or more different structural modifications in the solid state. The term **polymorphism** is used for compounds.

alternating current Josephson effect → **Josephson effects**.

Al'tshuler–Aronov–Spivak effect – occurs when the resistance of the conductor in the shape of a hollow cylinder oscillates as a function of the magnetic flux threading through the hollow with a period of $hc/2e$. This effect was predicted for the diffusive regime of the charge transport where the mean free path of the electrons is much smaller than the sample size. The conductance amplitude of the oscillations is of the order of e^2/h and depends on the phase coherence length over which an electron maintains its phase coherence. Coherent backscattering of an electron when there is interference in a pair of backscattered spatial waves with time-reversal symmetry causes the oscillations.

First described in: B. L. Al'tshuler, A. G. Aronov, B. Z. Spivak, *Aharonov–Bohm effect in non-ordered conductors,* Pis'ma Zh. Eksp. Teor. Fiz. **33**(2), 101–103 (1981) – in Russian.

amides – organic compounds that are nitrogen derivates of **carboxylic acids**. The carbon atom of a carbonyl group ($>C{=}O$) is bonded directly to a nitrogen atom of an $-NH_2$, $-NHR$ or $-NR_2$ group, where R represents an **alkyl group** ($-C_nH_{2n+1}$). The general formula of amides is $RCONH_2$.

amines – organic compounds that are ammonia molecules with hydrogen substituted by **alkyl groups** ($-C_nH_{2n+1}$) or **aromatic rings**. These can be RNH_2, R_2NH, or R_3N, where R is an alkyl or aromatic group.

amino acid – an organic compound containing an amino group (NH_2), a carboxylic acid group (COOH), and any of various side groups that are linked together by **peptide bonds**. The basic formula is $NH_2CHRCOOH$. Amino acids are building blocks of **proteins**.

There are twenty standard amino acids used in protein biosynthesis. These are presented in Figure A.3.


Amino acids with aliphatic R-groups
Glycine (Gly - G)
Alanine (Ala - A)
Valine(Val - V)
Leucine(Leu - L)
Isoleucine (Ile - I)
Non-aromatic amino acids with hydroxyl R-groups
Serine (Ser - S)
Threonine (Thr - T)
Amino acids with sulfur-containing R-groups
Cysteine (Cys - C)
Methionine (Met - M)
Acidic amino acids and their amides
Aspartic acid (Asp - D)
Asparagine (Asn - N)
Glutamic acid (Glu - E)
Glutamine (Gln - Q)
Basic amino acids
Arginine (Arg - R)
Lysine (Lys - K)
Histidine (His - H)
Amino acids with aromatic rings
Phenylalanine (Phe - F)
Tyrosine (Tyr - Y)
Tryptophan (Trp - W)
Imino acids
Proline (Pro - P)

Figure A.3 Amino acids found in proteins. Their symbols are shown in parentheses.

Just as the letters of the alphabet can be combined to form an almost endless variety of words, amino acids can be linked in varying sequences to form a huge variety of proteins.

More details in: //en.wikipedia.org/wiki/Amino_acid.

Amontons' law currently supposes the statement that the friction force between two bodies is directly proportional to the applied load (normal), with a constant of proportionality that is the friction coefficient. This force is constant and independent of the contact area, the surface roughness and the sliding velocity.

In fact, this statement is a combination of a few laws: the law of Euler and Amontons stating that friction is proportional to the loading force, the law of Coulomb → **Coulomb law (mechanics)** stating that friction is independent of the velocity, and the law of Leonardo da Vinci stating that friction is independent of the area of contact. In particular, Leonardo da Vinci arrived (1500) at the result that on an inclined plane a slider would move if the ratio between the tangential and normal components of the gravitational force exceeded one-fourth.

First described in: G. Amontons, *De la résistance causée dans les machines,* Mem. Acad. Roy. Sci. A, 206–222 (1699).

More information in: R. Schnurmann *Amontons' Law, "traces" of frictional contact, and experiments on adhesion,* J. Appl. Phys. **13**(4), 235 (1942).

amorphous solid – a solid with no long-range atomic order.

Ampère currents – molecular-ring currents postulated to explain the phenomenon of magnetism as well as the apparent nonexistence of isolated magnetic poles.

Ampère's law, as amended by Maxwell, states that magnetomotive force round any closed curve equals the electric current flowing through any closed surface bounded by the curve. The force appears clockwise to an observer looking in the direction of the current. It means that $\int \mathbf{H}\mathbf{dl} = I$, where $\mathbf{H}$ is the magnetic field strength, I is the current enclosed. The linear integral is taken round any closed path. If the current is flowing in a conducting medium, $I = \int \mathbf{J}\mathbf{ds}$, where $\mathbf{J}$ is the current density. Finally, it may be shown that $\nabla x \mathbf{H} = \mathbf{J}$, which is a statement of Ampère's law at a point in a conducting medium.

First described in: A. M. Ampère *Mémoire sur les effets du courant électrique*, Annales de chimie et de physique **15**, 59–118 (1820).

More details in: André-Marie Ampère, *Exposé méthodique des phénomènes électrodynamiques et des lois de ces phénomènes* (Plasson, Paris, 1822).

Ampère's rule states that the direction of the magnetic field surrounding a conductor will be clockwise when viewed from the conductor if the direction of current flow is away from the observer.

First described in: A. M. Ampère, *Mémoire sur les effets du courant électrique*, Annales de chimie et de physique **15**, 59–118 (1820).

More details in: André-Marie Ampère, *Exposé méthodique des phénomènes électrodynamiques et des lois de ces phénomènes* (Plasson, Paris, 1822).

Ampère's theorem states that an electric current flowing in a circuit produces a magnetic field at external points equivalent to that due to a magnetic shell whose bounding edge is the the conductor and whose strength is equal to the strength of the current.

First described in: A. M. Ampère, *Mémoire sur les effets du courant électrique*, Annales de chimie et de physique **15**, 59–118 (1820).

More details in: André-Marie Ampère, *Exposé méthodique des phénomènes électrodynamiques et des lois de ces phénomènes* (Plasson, Paris, 1822).

amphichiral → **chirality**.

AND operator → **logic operator**.

Andersen-Nose algorithm – a method used in **molecular dynamics simulation** for numerical integration of ordinary differential equation systems based on a quadratic presentation of time-dependent atom displacement.

First described in: S. Nose, F. Yonezawa, *Isothermal–isobaric computer simulations of melting and crystallization of a Lennard–Jones system*, J. Chem. Phys. **84**(3), 1803–1812 (1986).

Anderson localization means that electron wave function becomes spatially localized and the conductivity vanishes at zero temperature when the mean free path of electrons is short comparable to the Fermi wavelength ($\lambda_F = 2\pi/k_F$); multiple scattering becomes important. Metal-insulator transition takes place due to disorders. In the localized states, the wave function decays exponentially away from the localization center, that is $\psi(r) \sim \exp(-r/\xi)$, where ξ is called the localization length. Anderson localization depends strongly on dimensionality.

First described in: P. W. Anderson, *Absence of diffusion in certain random lattices,* Phys. Rev. **109**(5), 1492–1505 (1958).

Recognition: in 1977 P. W. Anderson, N. F. Mott and J. H. van Vleck received the Nobel Prize in Physics for their fundamental theoretical investigations of the electronic structure of magnetic and disordered systems.

See also www.nobel.se/physics/laureates/1977/index.html.

Anderson rule, which is also called the **electron affinity rule**, states that vacuum levels of two materials forming a **heterojunction** should be lined up. It is used for construction of energy band diagrams of **heterojunctions** and **quantum wells**.

The **electron affinity** χ of the materials is used for the lining up procedure. This material parameter is nearly independent of the position of the Fermi level, unlike the **work function**, which is measured from the Fermi level and therefore depends strongly on doping.

Figure A.4 shows the band alignment at the interface between small band gap material A with the electron affinity χ_A and large band gap material B with the electron affinity χ_B supposing $\chi_A > \chi_B$. According to the rule the offset of the conduction band $\Delta E_c = \Delta E_{cB} - \Delta E_{cA} = \chi_A - \chi_B$. Correspondingly, the offset of the valence band ΔE_v can be predicted from the above diagram accounting for both electron affinities and band gaps of the materials. At a temperature above absolute zero the misalignment of the Fermi levels, if there is any, is eliminated by redistribution of free charge carriers at the interface between the barrier and well regions.



Figure A.4 Alignment of the bands at a heterojunction according to Anderson's rule.

The validity of the rule was discussed by H. Kroemer in his paper *Problems in the theory heterojunction discontinuities* CRC Crit. Rev. Solid State Sci. **5**(4), 555–564 (1975). The hidden assumption about the relation between the properties of the interface between two semiconductors and those of the much more drastic vacuum-to-semiconductor interface is a weak point of the rule.

First described in: R. L. Anderson, *Germanium-gallium arsenide heterojunction*, IBM J. Res. Dev. **4**(3), 283–287 (1960).

Andreev process – reflection of a **quasiparticle** from the potential barrier formed by normal **conductor** and **superconductor** when the barrier height is less than the particle energy. It results in the temperature leap at the barrier if a heat flow takes place there. The conductor part of the structure can be made of a metal, **semimetal** or degenerate **semiconductor**.

The basic concept of the process is schematically illustrated in Figure A.5 for an electron crossing the interface between a conductor and superconductor.

There is a superconducting energy gap opened up for a single electron on the superconductor side. Thus, an electron approaching the barrier from the metal side with the energy above the **Fermi level**, but still within the gap, cannot be accommodated in the superconductor as a single particle. It can only form a **Cooper pair** there that needs an additional electron from the metal side with the energy below the Fermi level to come. This removed electron leaves behind a hole in the Fermi sea. If the incident electron had a momentum $\hbar k$, the generated hole has the momentum $-\hbar k$. It traces the same path as the electron, but in the opposite direction. Describing the phenomenon one says that the incident electron is reflected as a hole.

First described in: A. F. Andreev, *Thermal conductivity of the intermediate state of superconductors*, Zh. Exp. Teor. Fiz. **46**(5), 1823–1928 (1964) – in Russian.



Figure A.5 Andreev reflection process.

Ångstrom – a metric unit of length measurements that corresponds to 10^{-10} m. The atomic diameters are in the range of 1–2 Å. It is named in honor of the nineteenth-century physicist Anders Jonas Ångstrom, one of the founders of modern spectroscopy.

angular momentum – the energy of a rotating particle. It is quantized for quantum particles as $L^2 = l(l+1)\hbar^2$, where $l = 0, 1, 2, n-1$, where n is the principal quantum number. In an atom electrons with $l = 0$ are termed s states, $l = 1$ (p states), $l = 2$ (d states), $l = 3$ (f states), $l = 4$ (g states). The letters s, p, d were first used to describe characteristic features of spectroscopic lines and stand for ''sharp'', ''principal'', and ''diffuse''. After d the letters run alphabetically.

anisodesmic structure – a structure of an ionic crystal in which bound groups of ions tend to be formed → **mesodesmic** and **isodesmic structures**.

anisotropy (of matter) – different physical properties of a medium in different directions. The alternative is **isotropy**.

anisotropic magnetic resistance – the difference in **magnetoresistance** when the resistance of a **conductor** is measured by the current passing either parallel or perpendicular to the material → **giant magnetoresistance effect**.

First described in: W. Thomson (Lord Kelvin), *On the electro-dynamic qualities of metals: effects of magnetization on the electric conductivity of nickel and of iron,* Proc. R. Soc. London **8**, 546–550 (1856).

anodizing = anodic oxidation, is the formation of an adherent oxide film on the surface of a metal or semiconductor when it is anodically polarized in a suitable electrolyte or plasma of an electric discharge in a gas.

anomalous Hall effect – an additional voltage proportional to the magnetization arising in **Hall effect** measurements in **ferromagnetic** materials. Unlike the ordinary **Hall effect**, this contribution is strongly temperature dependent.

The related transverse resistivity ρ_{xy} in ferromagnetics contains the contribution due to the magnetization M in addition to the usual **Hall effect**: $\rho_{xy} = R_0 B + 4\pi R_a M$, where B is the magnetic field induction, R_0 is the usual Hall coefficient, and R_a is the anomalous Hall coefficient. This expression can be used as an experimental tool to measure the magnetization as a function of temperature.

More details in: *The Hall Effect in Metals and Alloys,* edited by C. Hurd (Plenum, New York, 1972).

See also www.lakeshore.com/pdf_files/systems/Hall_Data_Sheets/Anomalous_Hall1.pdf.

anomalous Zeeman effect → **Zeeman effect**.

antibody – an inducible immunoglobulin **protein** produced by B lymphocytes of the immune system, in humans and other higher animals, which recognizes and binds to a specific **antigen** molecule of a foreign substance introduced into the organism. When antibodies bind to corresponding antigens they set in motion a process to eliminate the antigens.

antibonding orbital – the orbital which, if occupied, raises the energy of a molecule relative to the separated atoms. The corresponding wave function is orthogonal to that of the bonding state → **bonding orbital**.

antiferroelectric – a dielectric of high permittivity, which undergoes a change in crystal structure at a certain transition temperature, usually called the antiferroelectric **Curie temperature**. The antiferroelectric state in contrast to a **ferroelectric** state possesses no net spontaneous polarization below the Curie temperature. No hysteresis effects are therefore exhibited by this type of materials. Examples: $BaTiO_3$, $PbZrO_3$, $NaNbO_3$.

antiferromagnetic → **magnetism**.

antigen – any foreign substance, such as virus, bacterium, or **protein**, which, after introduction into an organism (humans and higher animals), elicits an immune response by stimulating the production of specific **antibodies**. It also can be any large molecule, which binds specifically to an antibody.

anti-Stokes line → **Raman effect**.

anti-dot – a **quantum dot** made of wider band gap semiconductor in/on a smaller band gap semiconductor, for example Si dot in/on Ge substrate. It repels charge carriers rather than attracting them.

anti-wires – the **quantum wires** made of wider band gap semiconductor in/on a smaller band gap semiconductor. They repel charge carriers rather than attracting them.

APFIM – an acronym for **atom probe field ion microscopy**.

a priori – Latin meaning ‘‘before the day’’. It usually indicates some postulates or facts known logically prior to the referred proposition. It pertains to deductive reasoning from assumed axioms or self-evident principles.

approximate self-consistent molecular orbital method – the **Hartree-Fock theory** as it stands is too time consuming for use in large systems. However, it can be used in a parametrized form, and this is the basis of many of the semi-empirical codes used like **Complete Neglect of Differential Overlap (CNDO)** and **Intermediate Neglect of Differential Overlap (INDO)**.

In the **CNDO** method all integrals involving different atomic orbitals are ignored. Thus, the overlap matrix becomes the unit matrix. Moreover, all the two-center electron integrals between a pair of atoms are set equal and the resonance integrals are set proportional to the overlap matrix. A minimum basis set of valence orbital is chosen using **Slater type orbitals**. These approximations strongly simplify the Fock equation.

In the **INDO** method the constraint present in CNDO that the monocentric two-electron integrals are set equal is removed. Since INDO and CNDO execute on a computer at about the same speed and INDO contains some important integrals neglected in CNDO, INDO performs much better than CNDO especially in prediction of molecular spectral properties.

It is interesting to note that the first papers dealing with the CNDO method appear in a supplementary issue of the Journal of Chemical Physics that contains the proceedings of the International Symposium on Atomic and Molecular Quantum theory dedicated to R. S. Mulliken → **Hund–Mulliken theory**, held in USA on 18–23 January 1965.

First described in: J. A. Pople, D. P. Santry, G. A. Segal, *Approximate self-consistent molecular orbital theory. I. Invariant procedures*, J. Chem. Phys. **43**(10), S129–S135 (1965); J. A. Pople, D. P. Santry, G. A. Segal, *Approximate self-consistent molecular orbital theory. II. Calculations with complete neglect of differential overlap*, J. Chem. Phys. 43(10), S136–S151 (1965); J. A. Pople, D. P. Santry, G. A. Segal, *Approximate self consistent molecular orbital theory. III. CNDO results for* AB_2 *and* AB_3 *systems*, J. Chem. Phys. **44**(9), 3289–3296 (1965).

More details in: J. A. Pople, *Quantum chemical models*, Rev. Mod. Phys., **71** (5), 1267–1274 (1999).

Recognition: in 1998 J. A. Pople shared with W. Kohn the Nobel Prize in Chemistry for his development of computational methods in quantum chemistry.

See also www.nobel.se/chemistry/laureates/1998/index.html.

APW – an acronym for an **augmented plane wave**.

archaea – are single-celled organisms thriving in a variety of habitats. Most of the archaea prefer extreme environments. Archaea form together with bacteria and eucarya the three domains in life.

argon laser – a type of **ion laser** with ionized argon as the active medium. It generates light in the blue and green visible light spectrum, with two energy peaks: at 488 and 514 nm.

armchair structure → **carbon nanotube**.

aromatic compounds → **hydrocarbons**.

aromatic ring → **hydrocarbons**.

Arrhenius equation – the equation in the form $V = V_0\exp(-E_a/k_BT)$, which is often used to describe temperature dependence of a process or reaction rate V, where V_0 is the temperature independent pre-exponential factor, E_a is the activation energy of the process or reaction, and T is the absolute temperature. The plot representing $\log(V/V_0)$ as a function of $1/k_BT$ or $1/T$ is called the **Arrhenius plot**. It is used to extract the activation energy E_a as the slope of a linear part of the curve.

First described by J. H. van't Hoff in 1884; in 1889, S. Arrhenius provided a justification and interpretation for it. See S. A. Arrhenius, *Über die Reaktiongeschwindigkeit der Inversion vor Rohrzucker durch Säuren*, Z. Phys. Chem. **4**, 226 (1889).

Recognition: in 1901 J. H. van't Hoff received the Nobel Prize in Chemistry in recognition of the extraordinary services he has rendered by the discovery of the laws of chemical dynamics and osmotic pressure in solutions. In 1903 S. Arrhenius received the Nobel Prize in Chemistry in recognition of the extraordinary services he had rendered to the advancement of chemistry by his electrolytic theory of dissociation.

See also www.nobel.se/chemistry/laureates/1901/index.html.

See also www.nobel.se/chemistry/laureates/1903/index.html.

artificial atom(s) → **quantum confinement**.

associate operator → **adjoint operator**.

atomic engineering – a set of techniques used to built atomic-size structures. Atoms and molecules may be manipulated in a variety of ways by using the interaction present in the tunnel junction of **scanning tunneling microscope (STM)**. In a sense, there is a possibility to use the proximal probe in order to extend our touch to a realm where our hands are simply too big.

Two formal classes of atomic manipulation processes are distinguished: parallel processes and perpendicular processes. In the class of parallel processes an adsorbed atom or molecule is forced to move along the substrate surface. In the class of perpendicular processes the atom or molecular is transferred from the surface to the STM tip or vice versa. In both processes the goal is the purposeful rearrangement of matter on the atomic scale. One may view the act of rearrangement as a series of steps that results in the selective modification or breaking of chemical bonds between atoms and subsequent creation of new ones. It is equivalent to a procedure that causes a configuration of atoms to evolve along some time-dependent potential energy hyper-surface from an initial to a final configuration. Both points of view are useful in understanding physical mechanisms by which atoms may be manipulated with a proximal probe.

In the class of parallel processes, the bond between the manipulated atom and the underlying surface is never broken. This means that the adsorbate always lies within the absorption potential well. The relevant energy scale for these processes is the energy of the barrier to diffusion across the surface. This energy is typically in the range of 1/10 to 1/3 of the adsorption energy and thus varies from about 0.01 eV for weakly bound physisorbed atoms on a close-packed metal surface to 1 eV for strongly bound chemisorbed atoms. There are two parallel processes tested for atomic manipulation: field-assisted diffusion and sliding process.

The field-assisted diffusion is initiated by interaction of the spatially inhomogeneous electric field of an STM tip with the dipole moment of an adsorbed atom. The inhomogeneous electric field leads to a potential energy gradient at the surface resulting in a field-assisted directional diffusion motion of the adatom. In terms of the potential energy the process can be presented as follows.

An atom in an electric field $E(r)$ is polarized with a dipole moment $p = \mu + \overrightarrow{\alpha}\, E(r) + \cdots$, where μ is the static dipole moment, $\overrightarrow{\alpha}\, E(r)$ the induced dipole moment, and $\overrightarrow{\alpha}$ the polarizability tensor. The related spatially dependent energy of the atom is given by $U(r) = -\mu E(r) - 1/2\overrightarrow{\alpha}(r)E(r)E(r) + \cdots$. This potential energy is added to the periodic potential at the substrate surface. Weak periodic corrugation of the energy occurs. The resulting potential reliefs are shown in Figure A.6. A broad or sharp potential well is formed under the STM tip depending on the particular interaction between the tip, adatom and substrate atoms. The interaction of the electric field with the adsorbate dipole moment gives rise to a broad potential well. The potential energy gradient causes the adatom to diffuse toward the potential minimum under the tip. When there is a strong attraction of the adsorbate to the tip by chemical binding, it leads to a rather steep potential well located directly below the tip apex. The adsorbate remains trapped in the well as the tip is moved laterally.

Realization of field-assisted diffusion needs the substrate to be positively biased. At a negative substrate polarity the static and induced dipole terms being opposite in sign compensate each other. In this case no potential well and related stimulating energy gradient for diffusion are produced.

The sliding process supposes pulling of an adsorbate across the surface by the tip of a proximal probe. The tip always exerts a force on an adsorbate bound to the surface. One component of this force is due to the interatomic potential, that is, the chemical binding force, between the adsorbate and the outermost tip atoms.



Figure A.6 Schematic of the potential energy of an adsorbed atom as a function of its lateral position on a surface above which there is located the STM tip.



Figure A.7 Schematic of the sliding process: *a* and *e*–imaging, *b*–connecting, *c*–sliding, *d*–disconnecting.

By adjusting the position of the tip one may tune the magnitude and the direction of the force exerted on the adsorbate, thus forcing it to move across the surface.

The main steps of atomic manipulation via the sliding process are depicted in Figure A.7. The adsorbate to be moved is first located with the STM in its imaging mode and then the tip is placed near the adsorbate (position "*a*"). The tip–adsorbate interaction is subsequently increased by lowering the tip toward the adsorbate (position "*b*"). This is achieved by changing the required tunnel current to a higher value and letting the feedback loop move the tip to a height which yields the higher demanded current. The adsorbate–tip attractive force must be sufficient to keep the adsorbate located beneath the tip. The tip is then moved laterally across the surface under constant current conditions (path "*c*") to the desired destination (position "*d*"), pulling the adsorbate along with it. The process is terminated by reverting to the imaging mode (position "*e*"), which leaves the adsorbate bound to the surface at the desired location.

In order for the adsorbate to follow the lateral motion of the tip, the tip must exert enough force on the adsorbate to overcome the lateral forces between the adsorbate and the surface. Roughly speaking, the force necessary to move an adsorbate from site to site across the surface is given by the ratio of the corrugation energy to the separation between atoms of the underlying surface. However, the presence of the tip may also cause the adsorbate to be displayed normal to the surface relative to its unperturbed position. The displaced adsorbate would have an altered in-plane interaction with the underlying surface. If the tip pulls the adsorbate away from the surface causing a reduction of this in-plane interaction, then we would expect our estimate to be an upper bound for the force necessary to move the adsorbate across the surface.

The manipulation of an adsorbate with the sliding process may be characterized by a threshold tip height. Above this height the adsorbate-tip interaction is too weak to allow manipulation. At the threshold this interaction is just strong enough to allow the tip to pull the adatom along the surface. The absolute height of the STM tip above the surface is not directly measured. But resistance of the tunnel junction strongly correlated to the tip–surface separation is accurately controlled. An increasing resistance corresponds to greater tip–surface separation, and hence to their weaker interaction. The threshold resistance to slide an adsorbate depends on the particular arrangement of atoms at the apex of the tip. But for that reason it can vary by not more than a factor of 4. The resistance is more sensitive to the chemical nature of the adatom and surface atoms ranging from tens kΩ to a few MΩ. The ordering of the threshold resistances is consistent with the simple notion that the corrugation energy scales with the binding energy and thus greater force must be applied to move adatoms that are more strongly bound to the surface.

In perpendicular processes an atom, molecule or group of atoms is transferred from the tip to the surface or initially from the surface to the tip and then back to a new site on the surface. In order to illustrate the main regularities of these processes we discuss transferring an adsorbed atom from the surface to the tip. The relevant energy for such process is the height of the potential barrier that the adsorbate should come through to go from the tip to the surface. The height of this barrier depends on the separation of the tip from the surface. It approaches the adsorption energy in the limit of large tip–surface separation and goes to zero when the tip is located close enough to the adsorbate. By adjusting the height of the tip one may tune the magnitude of this barrier. Electrical biasing of the tip with respect to the substrate, as it is usually performed in STM, controls the transfer process. Three approaches distinguished by the physical mechanisms employed have been proposed for perpendicular manipulations of atoms. These are transfer on- or near-contact, field evaporation and electromigration.

The transfer on- or near-contact is conceptually the simplest among the atomic manipulation processes. It supposes the tip to be moved toward the adsorbate until the adsorption well on the tip and surface sides of the junction coalesce. That is, the energy barrier separating the two wells is gone and the adsorbate can be considered simultaneously bound to the tip and the surface. The tip is then withdrawn, carrying the adsorbate with it. For the process to be successful the adsorbate's bond to the surface must be broken when the tip is moved out. One might expect that the adsorbate would ‘‘choose’’ to remain bound to the side of the junction on which it has the greatest binding energy. However, the ‘‘moment of choice’’ comes when the adsorbate has strong interactions with both tip and surface, so the binding energy argument may be too simple. It does not account for the simultaneous interaction of the adsorbate with the tip and the surface.

At a slightly increased separation between the tip and sample surface, the adsorption well of the tip and surface atom are close enough to significantly reduce the intermediate barrier but have it still remain finite, such that thermal activation is sufficient for atom transfer. It is called transfer-near-contact. This process has a rate proportional to $\nu\exp(-E_a/k_BT)$, where ν is the frequency factor, and E_a the reduced energy barrier between the tip and the sample. The transfer rate exhibits an anisotropy if the depth of the adsorption well is not the same on each side of the barrier. It is important to distinguish this transfer-near-contact mechanism from field evaporation, which requires an intermediate ionic state.

In its simplest form, the transfer on- or near-contact process occurs in the complete absence of any electric field, potential difference, or flow of current between the tip and the sample. Nevertheless, in some circumstances it should be possible to set the direction of transfer by biasing the junction during contact.

The field evaporation uses the ability of ions to drift in the electric field produced by an STM probe. It is a thermally activated process in which atoms at the tip or at the sample surface are ionized by the electric field and thermally evaporated. Drifting in this field they come more easily through the potential Schottky-type barrier separating the tip and the surface because this barrier appears to be decreased by the electric field applied. Such favorable conditions are simply realized for positively charged ions by the use of a pulse voltage applied to the tip separated from a sample surface by about 0.4 nm or smaller. Field evaporation of negative ions meets difficulties associated with the competing effect of field electron emission, which would melt the tip or surface at the fields necessary for negative ion formation.

The electromigration in the gap separating an STM tip and sample has much in common with the electromigration process in solids. There are two components of the force driving electromigration. The first is determined by the electrostatic interaction of the charged adsorbates with the electric field driving the electron current through the gap. The second, which is called the ‘‘wind’’ force, is induced by direct scattering of electrons at the atomic particles. These forces are most strongly felt by the atoms in the immediate vicinity of the tunnel junction formed by the tip of a proximal probe and sample surface. The highest electric field and current density are here. Within the electromigration mechanism the manipulated atoms always move in the same direction as the tunneling electrons. Moreover, ‘‘heating’’ of adsorbates by tunnel current stimulates electromigration as soon as a ‘‘hot’’ particle may more easily jump to a neighboring site. Atomic electromigration is a reversible process.

Summarizing the above-presented physical mechanisms used for manipulation of individual atoms with proximal probes one should remember that there is no universal approach among them. Applicability of each particular mechanism is mainly determined by the physical and chemical nature of the atoms supposed to be manipulated, by the substrate and to some extent by the probe material. An appropriate choice of the adsorbate/substrate systems still remains a state-of-art point.

More details in: *Handbook of Nanotechnology*, edited by B. Bhushan (Springer Verlag, Berlin Heidelberg, 2004).

atomic force microscopy (AFM) originated from **scanning tunneling microscopy (STM).** Atomic and molecular forces, rather than a tunneling current, are monitored and used for the surface characterization at the atomic scale. The forces are detected by a probe tip mounted on a flexible cantilever, as shown in Figure A.8. Deflection of the cantilever, to a good approximation, is directly proportional to the acting force. It is optically or electronically monitored with high precision. The deflection signal is used to modulate the tip–sample separation in the way it is done in STM with the tunneling current. While scanning, one can obtain a profile of atomic and molecular forces over the sample surface. The sensitivity of AFM to the electronic structure of the sample surface, inherent in STM, is largely absent. Therefore it allows characterization of nonconducting materials.



Figure A.8 Tip–sample geometry and registered effect in atomic force microscopy.

There are three principle types of imaging modes of the sample surface in AFM: contact, tapping, and non-contact modes. In the contact mode, the probing tip is always in contact with the sample surface, and surface structure is obtained from the deflection of the cantilever. The force on the tip is repulsive with a mean value of about 10^{-9} N. This force is set by pushing the cantilever against the sample surface with a piezoelectric positioning element. In the tapping mode, the probe tip is periodically in contact with the sample surface, and surface structure is obtained from the change in the vibration amplitude or phase of the oscillating cantilever. In the non-contact mode, the probe tip is not in contact with the sample surface, and surface structure is obtained from the change in the the vibration amplitude or resonant frequency of the oscillating cantilever.

In the contact mode, there is a high possibility that the strong repulsive force acting between the sample surface and the probe tip will destroy the sample surface and/or the tip apex. So, the tapping and non contact modes are widely used because these modes are more gentle than the contact mode.

In the tapping mode, the cantilever is driven at a fixed frequency near resonance with large vibration amplitude. When the probe tip is far from the surface, the vibration amplitude of the oscillating cantilever is held constant. When the probe tip is close to the surface, the probe tip is periodically in contact with the sample surface, and the vibration amplitude of the oscillating cantilever decreases because of cyclic repulsive contact between tip and surface with loss of the energy stored in the oscillating cantilever. The surface structure is obtained by maintaining the vibration amplitude at a constant level using the feedback circuit. The loading force acting between the probe tip and the sample surface can be greatly reduced in the tapping mode.

The atomic force microscopy technique has also been developed to detect electrostatic and magnetic forces as well as friction forces at atomic scale → **electrostatic force microscopy, magnetic force microscopy, friction force microscopy**.

First described in: G. Binning, C. F. Quate, Ch. Gerber, *Atomic force microscope,* Phys. Rev. Lett. **56**(9), 930–933 (1986).

More details in: *Handbook of Nanotechnology*, edited by B. Bhushan (Springer Verlag, Berlin Heidelberg, 2007); *Roadmap of Scanning Probe Microscopy*, edited by S. Morita (Springer Verlag, Berlin Heidelberg, 2007).

atomic number – the number of protons in the atomic nucleus, and hence the nuclear charge.

atomic orbital – a wave function of a hydrogenic (hydrogen-like) atom. This term expresses something less definite than "orbit" of classical mechanics. When an electron is described by one of the wave functions, one says that it occupies that orbital. It defines the spatial behavior of an electron of a given energy level in a particular atom. An overlap of orbitals in solids produces bands.

In an atom all orbitals of a given value of principal quantum number n form a single shell. It is common to refer to successive shells by the letters: K$(n=1)$, L$(n=2)$, M$(n=3)$, N$(n=4)$. The number of orbitals in a shell of principal number n is n^2. In a hydrogenic atom each shell is n^2-fold **degenerate**.

The orbitals with the same value of n but different **angular momentum**, which corresponds to different values of l, form the subshell of a given shell. The subshells are referred to by the letters: s$(l=0)$, p$(l=1)$, d$(l=2)$, f$(l=3)$. Thus, the subshell with $l=1$ of the shell with $n=3$ is called the 3p subshell. Electrons occupying these orbitals are called 3p electrons. The number of orbitals for different n and l is listed in the Table A.1.

Table A.1 Number of orbitals as a function of the quantum numbers n and l.

$l \rightarrow$ $n \downarrow$	0 s	1 p	2 d	3 f	Total number of orbitals
1	1				1
2	1	3			4
3	1	3	5		9
4	1	3	5	7	16

s orbitals are independent of angle (the angular momentum is zero), so they are spherically symmetrical. The first s orbitals are schematically shown in Figure A.9.



Figure A.9 The form of hydrogenic atomic s orbitals.

p orbitals are formed by electrons with the angular momentum $L^2 = 2\hbar^2$. These orbitals have zero amplitude at $r = 0$. This can be understood in terms of the



Figure A.10 Three hydrogenic atomic p orbitals, each directed along a different axis.

centrifugal effect of the angular momentum, which flings the electron away from the nucleus. The same effect appears in all orbitals with $l > 0$.

The three 2p orbitals are distinguished by the three different values that m_l can take when $l = 1$, where m_l represents the angular momentum around an axis. They are presented in Figure A.10. Different values of m_l denote orbitals in which the electron has different angular momenta around an arbitrary axis, for instance the z-axis, but the same magnitude of momentum because l is the same for all three. In this case the orbital with $m_l = 0$ has zero angular momentum around the z-axis. It has the form $f(r)cos\theta$. The electron density, which is proportional to $cos^2\theta$, has its maximum on either side of the nucleus along the z-axis (for $\theta = 0^\circ$ and $\theta = 180^\circ$). For this reason, the orbital is also called a p_z orbital. The orbital amplitude is zero when $\theta = 90^\circ$, so the xy-plane is a nodal plane of the orbital. On this plane the probability of finding an electron occupying this orbital is zero.

The orbitals with $m_l = \pm 1$, which are the p_x and p_y orbitals, do have angular momentum about the z-axis. These two orbitals are different in the direction of the electron motion, which are opposite to each other. Nevertheless, they both have zero amplitude at $\theta = 0^\circ$ and $\theta = 90^\circ$ (along the z-axis) and maximum amplitude where $\theta = 90^\circ$, which is in the xy-plane. The p_x and p_y orbitals have the same shape as the p_z orbital, but are directed along x- and y-axis, respectively. Their combinations are standing waves with no net angular momentum around the z-axis, since they are composed of equal but opposite values of m_l.

d orbitals appear when $n = 3$. There are five orbitals in this case with $m_l = 0, \pm 1, \pm 2$, which correspond to five different angular momenta around the z-axis but with the same magnitude of the momentum. The orbitals with opposite values of m_l (and hence opposite senses of motion around the z-axis) may combine in pairs to produce standing waves. An important feature of d orbitals is that they are concentrated much more closely at the nucleus than s and p orbitals are. An example of the d orbital is depicted in Figure A.11.

d orbitals are more strongly concentrated near the nucleus and isolated from neighboring atoms than others. They are important in studying properties of **rare-earth** metals.

For the definitions of σ and π orbitals → **molecular orbital**.



Figure A.11 The d orbital of the xy/r^2 form.

atom probe field ion microscopy (APFIM) – the technique originated from field ion microscopy. The analyzed sample is prepared in the form of a sharp tip. A voltage pulse is applied to the tip causing atoms on the surface of the tip to be ejected. The atoms travel down a drift tube where their time of arrival can be measured. The time taken for the atom to arrive at the detector is a measure of the mass of that atom. Thus, compositional analysis of the sample can be carried out on a layer by layer basis.

The technique enables one to determine the chemical identity along with the position of surface atoms with atomic structural resolution. It has no elemental mass limitations, making it unique among analytical instruments.

First described in: E. W. Müller, J. A. Panitz, S. B. McLane, *The atom probe microscope*, Rev. Sci. Instrum. **39**(1), 83–86 (1968).

More details in: T. T. Tsong, *Atom-Probe Field Ion Microscopy: Field Ion Emission, and Surfaces and Interfaces at Atomic Resolution* (Cambridge University Press, Cambridge, 1990).

atto- – a decimal prefix representing 10^{-18}, abbreviated a.

aufbau principle – states that in any atom the lowest energy orbitals fill first. In conjunction with the **Pauli exclusion principle** and the **Hund rules**, it gives the correct electron configuration for an atom or ground state ion.

First described in: N. Bohr, *Der Bau der Atome und die physikalischen und chemischen Eigenschaften der Elemente*, Z. Phys. **9**, 1–67 (1922); E. C. Stoner, *The distribution of electrons among atomic levels*, Phil. Mag. **48**, 719–736 (1924).

Auger effect – formation of non-radiative re-arrangement of atomic electrons after the atom has been ionized in one of its inner shells.

Classically, if an atom is ionized in its S shell, the radiative mode of de-excitation is that in which a transition occurs involving an electron falling from a less tightly bound shell T to S with emission of a quantum of radiation with the energy $E_S - E_T$, which is the difference between the binding energies of the S and T shells, respectively. In the Auger transition, an electron, called the **Auger electron**, is emitted with kinetic energy $E = E_S - E_T - E_U$, with U being the same shell as

T or another one less tightly bound than S. For the transition to be energetically possible, of course $E_S - E_T - E_U = 0$. The process can be interpreted as the T electron falling into the S shell, the energy released being used to eject the U electron. The binding energy of the U electron is dashed because when it is ejected the atom is already ionized.

Most observable Auger transitions originate either by primary ionization in the K or L shells of an atom, because transitions due to ionization in the higher shells cause the emission of electrons with energies too low to be detected. The emitted electrons are called Auger electrons. Their energy spectrum is a fingerprint of the chemical nature of the atom. It is widely used for analysis of chemical compositions of matter by **Auger electron spectroscopy**.

First described in: P. Auger, *Sur les rayons* β *secondaires produits dans un gaz par des rayons*, C. R. **177**, 169–171 (1923).

Auger electron – an electron that is expelled from an atom in the **Auger effect**.

Auger electron spectroscopy (AES) – a technique of nondestructive elemental analysis of matter by examining energy distributions of secondary electrons emitted by the **Auger effect**. If a material is bombarded by electrons with an energy sufficient to ionize inner orbits of the atoms, the energy released when the ionized atom rearranges itself to fill the ionized level is characteristic of the atom. This energy may appear as an X-ray photon or may instead go to an outer orbit electron, ejecting it by the radiationless Auger process. Thus, the energy distribution of secondary Auger electrons contains peaks localized at energies which serve to identify the atoms producing them. The depth at which this information can be obtained is 0.5–2 nm for metals, 1.5–4 nm for oxides, and 4–10 nm for polymers.

More details in: M. De Crescenzi, M. N. Piancastelli *Electron Scattering and Related Spectroscopies* (World Scientific Publishing, Singapore, 1996).

Auger recombination – a transition of an electron from the conduction band to the valence band by transfer of the energy to another free electron or hole. No electromagnetic radiation is emitted during such process.

Auger scattering – one of the interacting charge carriers gives up its potential energy to another and hence relaxes down its energy level.

augmented plane wave (APW) – piecewise defined function consisting of the solution to the **Schrödinger equation** for an isolated atom within a sphere of given radius and a **plane wave** outside this region.

augmented-plane-wave method supposes solving the **Schrödinger equation** for electrons in an atom in terms of a set of fabricated functions that combine the oscillations inside the core with plane waves elsewhere. The potential is assumed to be spherically symmetrical within spheres centered at each atomic nucleus and constant in the interstitial region. Wave functions in the form of augmented plane waves are constructed by matching solutions of the **Schrödinger equation** within each sphere with plane-wave solutions in the interstitial region. Linear combinations of these wave functions are then determined by the **variational method**.

First described in: J. C. Slater, *Wave functions in a periodic potential,* Phys. Rev. **51**(10), 846–851 (1937).

autocorrelation function – the measure of the dependence of time series values at one time on the values at another time. The term autocorrelation means self-correlation. However, instead of correlation between two different variables, the correlation between two values of the same variable at times x_n and x_{n+k} is analyzed. For a time series $x(n), n = 1, 2, \ldots N$, the autocorrelation function is defined as: $R(k) = \frac{1}{(N-k)} \sum_{n=1}^{N-k} x(n)x(n+k)$, where k is the correlation distance and N is the length of the series. The argument of the autocorrelation function is the correlation distance k, and the function value at k expresses the average correlation between numbers separated by the distance k in the series.

The autocorrelation function is used to detect non-randomness in data and to identify an appropriate time series model if the data are not random. It is a powerful tool to find weak periodic signals in noisy data.

First described in: G. E. P. Box and G. Jenkins, *Time Series Analysis: Forecasting and Control* (Holden-Day, 1976).

autoelectronic emission – an emission of electrons from the surface of a conductor by application of an external electric field in the temperature range where conventional thermo-stimulated electron emission is rather small.

Aviram–Ratner model – a model for unimolecular electrical rectification employing a molecule with electrically isolated electron donor and acceptor groups.

The molecule is postulated to be initially in an electronically neutral state and placed between two metal electrodes. The current flow is proposed to be a three-step process, upon application of a bias. First, an electron passes from the cathode to the acceptor. The Fermi level of the anode is sufficiently lowered under the bias to allow the second step of the process, electron tunneling from the donor to the anode, to occur. Finally, the electron inelastically tunnels from the **acceptor** to the **donor**.

A demonstration **molecular rectifier** consists of a donor π system (tetrathiafulvalene) and an acceptor π system (tetracyanoquinodimethane), separated by a σ bonded (methylene) tunneling bridge.

First described in: A. Aviram, M. A. Ratner, *Molecular rectifiers,* Chem. Phys. Lett. **29**(2), 277–283 (1974).

Azbel'–Kaner cyclotron resonance – the method used to measure **cyclotron frequencies** in metals and thus useful in **Fermi surfaces** studies. In a large static magnetic field, a semiconductor permeated by a radiofrequency electromagnetic field produces sharp peaks in the radiofrequency energy absorption when the frequency coincides with the cyclotron resonance frequency ω_c. In metals this is impeded by the **skin-depth effect** that prevents the radiofrequency field penetration. In the Azbel'–Kaner method one accepts the limitation that the radiofrequency field can accelerate the electrons only within a very thin surface layer and arranges the geometry of the experiment such that the electrons return to this layer frequently. In order to obtain this the static magnetic field is oriented parallel to the surface of the sample. Thus, any electron at its general helical orbit around the magnetic field lines approaches the surface within the same distance on each cycle. If the radiofrequency coincides with the cyclotron frequency, the electron can resonantly absorb energy from the field. Here the condition for the resonance is $\omega = n\omega_c (n = 1, 2, 3, \ldots)$.

First described in: M. Ya. Azbel', E. A. Kaner, *Cyclotron resonance in metals,* J. Phys. Chem. Solids **6** (2–3), 113–135 (1958); M. Ya. Azbel', E. A. Kaner, Zh. Eksp. Teor. Fiz. **30**, 811 (1956) and **32**, 896 (1957) – in Russian.

More details in: L. M. Falicov, *Fermi surface studies,* in: *"Electrons in Crystalline Solids"* (IAEA, Vienna, 1973), pp. 207–280.

B

From B92 protocol to Burstein–Moss shift

B92 protocol – the protocol for quantum cryptographic key distribution developed by Charles **B**ennett in 1**992** (the acronym uses the bold characters). It works like the **BB84** protocol, but instead of using a system with four pairwise orthogonal states, only two non-orthogonal states are involved. This makes the protocol simpler.

First described in: C. H. Bennet, *Quantum cryptography using any two non-orthogonal states,* Phys. Rev. Lett. **68**(21), 3121–3124 (1992) – theory; A. Muller, J. Breguet, N. Gisin, *Experimental demonstration of quantum cryptography using polarized photons in optical fiber over more than 1 km,* Europhys. Lett. **23**(6), 383–388 (1993) – experiment.

Back–Goudsmit effect – breakdown of the coupling between the nuclear spin **angular momentum** and the total angular momentum of the electrons in an atom at relatively small magnetic field.

First described in: S. Goudsmit, E. Back, *Die Koppelung der Quantenvektoren bei Neon, Argon und einigen Spektren der Kohlenstoffgruppe,* Z. Phys. **40**(7), 530–538 (1927).

bacteriophage → **virus**.

bacterium – a single-celled organism. Bacteria form one of the three major branches of life. They lack the nucleus and **organelles** of the more complex cells which are **eukaryotes**. Nevertheless, they, like the cells of plants, mostly possess a carbohydrate-based cell wall.

Badger rule – a simple empirical relationship between the stretching force constant for a molecular bond and the bond length discovered by Badger in 1934, $k_e = A(R_e - B)^{-3}$, where k_e is the force constant and R_e is the equilibrium bond length.

First described in: R. M. Badger, *A relation between internuclear distances and bond force constants,* J. Chem. Phys. **2**(3), 128–131 (1934).

ballistic conductance – a characteristic of ideal **ballistic transport** of charge carriers in nanostructures. It is deduced from the fundamental constants, so it is material independent.



Figure B.1 Two reservoirs with electrons connected by a perfect conducting channel.

The simplest device appropriate for illustration this fact is a two-terminal conductor. It is schematically shown in Figure B.1, where constriction between two reservoirs of electrons acts as a conducting quantum wire. The size of the constriction must be close to the Fermi wavelength of electrons in order to observe the role of the wave-like nature of electrons in their transport behavior. No irregularities and related carrier scattering are expected along the conducting channel. Moreover, this perfect conducting tube is assumed to be tied to the reservoirs via tapered nonreflecting connectors. It means that carriers approaching a reservoir inevitably pass into it.

Take the zero temperature case and let the reservoirs be filled to with electrons up to the level characterized by electrochemical potentials μ_1 and μ_2, and $\mu_1 > \mu_2$. If electronic states in the range between μ_1 and μ_2 are fully occupied, there is a current between the reservoirs

$$I = (\mu_1 - \mu_2)ev(\mathrm{d}n/\mathrm{d}\mu),$$

where e is the electronic charge, v is the velocity component along the conducting channel at the Fermi surface, and $\mathrm{d}n/\mathrm{d}\mu$ is the density of states in the channel (allowing for spin degeneracy). In a quantum wire $\mathrm{d}n/\mathrm{d}\mu = 1/\pi hv$. Substituting $(\mu_1 - \mu_2) = e(V_1 - V_2)$, where V_1 and V_2 are the electrical potentials inducing the difference in the electrochemical potentials of the reservoirs, one can calculate the conductance of the quantum wire as

$$G = I/(V_1 - V_2) = e^2/(\pi h) = 2e^2/h.$$

This is the conductance of an ideal one-dimensional conductor operating in the ballistic transport regime. It is evident that it is determined only by fundamental constants. The quotient $e^2/h = 38.740\ \mu\mathrm{S}$ is referred to as the quantum unit of conductance. The corresponding resistance is $h/e^2 = 25812.807\ \Omega$.

ballistic magnetoresistance – the electrical resistance of a structure with the ballistic transport of charge carriers measured in the presence of a magnetic field. The size of the ballistic magnetoresistance is expressed as a percentage representing the change of the resistance of the ballistic conducting channel between two electrodes when the relative magnetic alignment of the electrodes changes from being parallel to antiparallel.

First described in: N. García, M. Muñoz, Y.-W. Zhao, *Magnetoresistance in excess of 200% in ballistic Ni nanocontacts at room temperature and 100 Oe,* Phys. Rev. Lett. **82**(14), 2923–2926 (1999).

ballistic transport (of charge carriers) – charge carriers pass through a structure without scattering.

Balmer series → **Rydberg formula**.

First described by: Johann Jacob Balmer on June 25, 1884, during a lecture to the *Naturforschende Gesellschaft* in Basel, Switzerland. J. J. Balmer *Notiz über die Spektrallinien des Wasserstoffs,* Ann. Phys. **25**, 80 (1885).

Banach space – the extended version of the **Hilbert space**, which is a vector space with a norm, but not necessarily given by an inner product. The space should be complete. Every **Cauchy sequence** converges to a point of the space.

First described in: S. Banach, *Sur le Problème de la Mesure,* Fund. Math. **4** (1), 7–33 (1923).

More details in: S. Banach, *Theorie des Operations Linéaires* (Warszawa, 1932).

band structure → **electronic band structure**.

Bardeen–Cooper–Schrieffer (BCS) theory explains theoretically the superconductivity phenomenon in metals, metallic compounds and alloys → **superconductivity**.

Recognition: in 1972 J. Bardeen, L. N. Cooper and J. R. Schrieffer received the Nobel Prize in Physics for their jointly developed theory of superconductivity, usually called the BCS-theory.

See also www.nobel.se/physics/laureates/1972/index.html.

Barkhausen effect – when a ferromagnetic material is subjected to a changing external magnetic field, part of the resultant change in its magnetization occurs via series of discontinous steps, even though the rate of the magnetic field change may be extremely slow. The discontinuities are produced by irreversible changes in the domain structure of the material.

First described in: H. G. Barkhausen, *Zwei mit Hilfe der neuen Verstärker entdeckte Erscheinungen,* Phys. Z. **20**, 401–403 (1919).

Barlow rule states that the volume occupied by the atoms in a given molecule is proportional to the valence of the atoms, using the lowest valency values.

Barnett effect – the magnetization of an initially unmagnetized specimen acquired when it is rotated in the absence of any external magnetic field.

First described in: S. J. Barnett, *An investigation of the electric intensities and electric displacement produced in insulators by their motion in a magnetic field,* Phys. Rev. **27**(5), 425–472 (1908).

Barnett–Loudon rule states that allowed modifications of the spontaneous emission rate for an electric dipole transition, caused by the atomic environment, are constrained by a sum rule

$$\int_0^\infty \mathrm{d}\omega_a \frac{\Gamma_m(\mathbf{r}, \omega_a) - \Gamma_0(\omega_a)}{\Gamma_0(\omega_a)} = 0,$$

where $\Gamma_0(\omega_a)$ is the **spontaneous emission** rate in free space and $\Gamma_m(\mathbf{r}, \omega_a)$ is the emission rate of an atom or molecule at position **r** as modified by the environment, whose effect is assumed to vary by a negligible amount across the extent of the emitting object. It follows that any reduction in spontaneous emission rate over some range of frequencies ω_a must necessarily be compensated by increases over some other range of transition frequencies. This rule is derived on the basis of **causality** requirements as expressed in the **Kramers–Kronig dispersion relation**.

It should be emphasized that the rule applies to the spontaneous emission by an atom or molecule in a completely arbitrary environment, which may include, for example, metallic mirrors, Bragg reflectors, photonic band gap materials and absorptive dielectrics or semiconductors. In all cases, the sum rule is used for model calculations of the modified spontaneous emission rates only if they use dielectric functions that conform to general causality and asymptotic requirements.

First described in: S. M. Barnett, R. Loudon, *Sum rule for modified spontaneous emission rates*, Phys. Rev. Lett. **77**(12), 2444–2446 (1996).

baryon – a particle belonging to the class of elementary particles that have a mass greater than or equal to that of the **proton**, participate in strong interactions, and have a spin of $\hbar/2$.

base pair – two complementary nitrogenous bases in a **DNA** molecule, such as the nucleotide coupling of adenine with thymine (A:T) and guanine with cytosine (G:C). It is also used as a unit of measurement for DNA sequences.

basis states – the states comprising the set in which the wave function is expanded.

BB84 protocol – the first protocol for quantum cryptographic key distribution developed by Charles **B**ennett and Gilles **B**rassard in 1984 (the acronym uses the bold characters). This scheme, which is a four state scheme, uses the transmission of non-orthogonal states of single-photon qubits, with security derived from the impossibility of an eavesdropper distinguishing the two states without being detected (on average). It works as follows.

Alice (conventional name of a sender) and Bob (conventional name of a receiver) are connected by two channels, one quantum and another public and classic. If photons are the vehicle carrying the key, the quantum channel is usually an optical fiber. The public channel can also be so, but with one difference: in the quantum channel there is in principle only one photon per bit to be transported, while in the public channel, in which eavesdropping by any non authorized person does not matter, the intensity is hundreds of times bigger.

Step 1. Alice prepares photons with linear polarizations randomly chosen among the angles 0°, 45°, 90°, 135°, which she sends "in a row" through the quantum channel, while keeping a record of the sequence of the prepared states and of the associated sequence of logic 0's and 1's obtained representing by 0 the choices of 0 and 45 degrees, and by 1 otherwise. This sequence of bits is clearly random.

Step 2. Bob has two analyzers, one "rectangular" (+type), the other "diagonal" (xtype). Upon receiving each of Alice's photons, he decides at random what analyzer to use, and writes down the aleatory sequence of analyzers used as well as the result of each measurement. He also produces a bit sequence associating 0 to the cases in which the measurement produces a 0° or 45° photon, and 1 in cases of 90° or 135°.

Step 3. Next they communicate with each other through the public channel the sequences of polarization basis and analyzers employed, as well as Bob's failures in detection, but never the specific states prepared by Alice in each basis nor the resulting states obtained by Bob upon measuring.

Step 4. They discard those cases in which Bob detects no photons, and also those cases in which the preparation basis used by Alice and the analyzer type used by Bob differ. After this distillation, both are left with the same random subsequence of bits 0, 1, which they will adopt as the shared secret key.

First described in: C. Bennett, G. Brassard, *Quantum cryptography: public key distribution and coin tossing*, Proc. IEEE Int. Conf. Comp. Syst. Signal Proc. **11**, 175–179 (1984) – theory; C. H. Bennett, G. Brassard, *The dawn of a new era for quantum cryptography: the experimental prototype is working!* SIGACT News **20**(4), 78–82 (1989) – experiment.

Becker–Kornetzki effect – a reduction in the internal friction of a ferromagnetic substance when it is subjected to a magnetic field that is large enough to produce magnetic saturation.

First described in R. Becker, M. Kornetzi, *Einige magneto-elastische Torsionsversuche*, Z. Phys. **88**(9–10), 634–646 (1934).

Beest–Kramer–Santen potential – the interatomic many force field Coulombic potential including a modified **Buckingham potential** for the repulsion and dispersion interactions, respectively, in the form

$$V(r_{ij}) = \sum_{i>j} \left[A_{ij} exp(-b_{ij} r_{ij}) - \frac{C_{ij}}{r_{ij}} \right] + \sum_{i>j} \frac{q_i q_j}{r_{ij}},$$

where r_{ij} is the distance between atoms i and j, the parameter A_{ij}, b_{ij}, and C_{ij} are fit to *ab initio* and empirical data, q_i and q_j are fixed partial charges of the atoms.

First described in: B. W. H. van Beest, G. J. Kramer, R. A. van Santen, *Force fields for silicas and aluminophosphates based on ab initio calculations*, Phys. Rev. Lett. **64**(16), 1955–1958 (1990).

Bell's inequality – the inequality for the outcomes of measurement of a bipartite system which must be satisfied if the system state were completely described by local **hidden variables**. For a pair of spins A and B, the inequality $P(1,2) + P(1,3) + P(2,3) \geq 1$ must hold, where $P(i,j)$ is the probability to get the same result when measuring the spin A along the direction i and the spin B along the direction j, the directions being defined in Cartesian coordinates as $\mathbf{n}_1 = (0,0,1), \mathbf{n}_2 = (\sqrt{3},0,-1)/2, \mathbf{n}_3 = (-\sqrt{3},0,-1)/2$. It shows that statistical predictions of quantum mechanics are incompatible with any local **hidden variables** theory apparently satisfying only the natural assumptions of locality. The inequality is violated if the joint state of two spins is a **Bell's state**.

First described in: J. S. Bell, *On the Einstein–Podolsky–Rosen paradox*, Physics **1**(3), 195–200 (1964); J. S. Bell, *On the problem of hidden variables in quantum mechanics*, Rev. Mod. Phys. **38**(3), 447–452 (1966).

More details in: J. S. Bell, *Speakable and Unspeakable in Quantum Mechanics* (Cambridge University Press, Cambridge, 1987).

Bell's state – the joint entangled state $|\psi\rangle = \frac{1}{\sqrt{2}}(|A-\uparrow\rangle|B-\downarrow\rangle - |A-\downarrow\rangle|B-\uparrow\rangle)$ of a pair of spins A and B. It is known as a spin singlet. This state violates the **Bell's inequality**.

Bell's theorem establishes that **hidden variables** theories can only reproduce the statistical predictions of quantum mechanics if the hidden variables in one region can be affected by measurements carried out in a space-like separated region. In other words it states that in the quantum theory there are states which violate **Bell's inequality**, showing the incompatibility of the quantum theory with the existence of local variables. Thus, some correlations predicted by quantum mechanics cannot be reproduced by any local theory.

First described in: J. S. Bell, *On the Einstein–Podolsky–Rosen paradox*, Physics **1**(3), 195–200 (1964); J. S. Bell, *On the problem of hidden variables in quantum mechanics*, Rev. Mod. Phys. **38**(3), 447–452 (1966).

More details in: J. S. Bell, *Speakable and Unspeakable in Quantum Mechanics* (Cambridge University Press, Cambridge, 1987).

Benedicks effect supposes that a voltage is induced between two points in a solid that are at the same temperature if the temperature profile between these points is asymmetric. It has been observed in semiconductors, while in metals it is expected to be negligibly small.

First described in: C. Benedicks, *Jetziger Stand der grundlegenden Kenntnisse der Thermoelektrizität*, Ergeb. Exakten Naturwiss. **8**, 26–67 (1929).

More details in: G. D. Mahan, *The Benedicks effect: nonlocal electron transport in metals*, Phys. Rev. B **43**(5), 3945–3951 (1991).

Berry phase arises in a system carried through a series of adiabatic changes, by varying a set of parameters, and then returned to its initial state when the parameters get their initial values. But the final state is multiplied by a phase factor that depends on the entire history of the parameters, and is thus nonlocal. This phase difference is called the Berry phase. Its occurrence typically indicates that the system's parameter dependence is undefined for some combination of parameters.

The Berry phase forms a crucial concept in many quantum mechanical effects, including for example the motion of vortices in superconductors, the electron transport in nanoelectronic devices, quantum computing.

First described in: M. V. Berry, *Quantal phase factors accompanying adiabatic changes*, Proc. R. Soc. A **392**, 45–57 (1984).

More details in: M. V. Berry, *Anticipations of the geometric phase,* Phys. Today **43**(12), 34–40 (1990).

Berthelot rule defines the relationship between energy attraction constants for a mixture of like ($\varepsilon_{ii}, \varepsilon_{jj}$) and unlike ($\varepsilon_{ij}$) species in the form $\varepsilon_{ij} = (\varepsilon_{ij} + \varepsilon_{ij})^{1/2}$.

Berthelot–Thomsen principle states that of all chemical reactions possible, the one developing the greatest amount of heat will take place, with certain obvious exceptions such as changes of state. This principle was formulated in two slightly different versions firstly by the Danish chemist Julius Thomsen in 1854 and then by the French chemist Marcellin Berthelot in 1873.

First described in: J. Thomsen, *Die Grundzüge eines thermochemischen Systems,* Ann. Phys. **47**, 34 (1854); M. Berthelot, *Sur la statique de dissolutions salines,* Bull. Soc. Chim. Paris **19**, 160 (1873).

Bessel function – the general part of the solution of the second order linear ordinary differential equation, known as **Bessel's equation**,

$$x^2 \frac{\mathrm{d}^2 y}{\mathrm{d}x^2} + x \frac{\mathrm{d}y}{\mathrm{d}x} + (x^2 - \nu^2) y = 0,$$

in which both x and the parameter ν can be complex. A complete solution of the equation depends upon the nature of the parameter ν. It can be found as a combination of the functions $B_\nu(x)$ with appropriate coefficients. The function

$$B_\nu(x) = \sum_{m=0}^{\infty} \frac{(-1)^m (0.5x)^{\nu+2m}}{m! \Gamma(\nu + m + 1)}$$

is a Bessel function of order ν and argument x of the first kind.

First described by: Friedrich Bessel in 1817.

More details in: I. N. Sneddon, *Special Functions of Mathematical Physics and Chemistry* (Oliver and Boyd, Edinburgh, 1956).

Bessel's equation → **Bessel function**.

Bethe–Salpeter equation – an integral equation for the relativistic bound state wave function of two interacting Fermi-Dirac particles. It is a direct application of the **S-matrix** formalism of Feynman. Starting from the Feynman two-body kernel one can prove that its usual power expansion can be re-expressed as an integral equation; this equation in the extreme non-relativistic approximation and to lowest order in the power expansion reduces to the appropriate **Schrödinger equation**. Consider two Fermi-Dirac particles of masses m_a and m_b, respectively, capable of interacting with each other through the virtual emission and absorption of quanta; let us denote the bound-state 4-momentum by P, while the Jacobi relative 4-momentum is denoted by

$$q = \frac{m_b p_a}{m_a + m_b} - \frac{m_a p_b}{m_a + m_b},$$

while the irreducible 2-body kernel is given by $G(q, q'; P)$. The Bethe–Salpeter equation takes the form:

$$\left(\frac{m_a \mathbf{P}}{m_a + m_b} + \mathbf{q} - m_a\right)\left(\frac{m_b \mathbf{P}}{m_a + m_b} - \mathbf{q} - m_b\right)\psi(q) = i\int d^4q'\, G(q, q'; P)\psi(q').$$

The Bethe–Salpeter equation was proven within the quantum field theory by Gell-Mann and Low. In recent years the Bethe–Salpeter equation has been widely used to go beyond the simple one-particle picture in the description of the electronic excitation processes in nanostructures (electron-hole interaction); these electronic excitations lie at the origin of most of the commonly measured spectra. Typical Feynman graphs representing the Bethe-Salpeter equation for the polarizability χ are shown in Figure B.2.



Figure B.2 Feynman diagrams representing the Bethe–Salpeter equation for χ. After G. Onida, L. Reining and A. Rubio, *Electronics excitations: density functional vs. many-body Green's-function approaches*, Rev. Mod. Phys. **74**(2), 601–659 (2002).

First described in: H. A. Bethe and E. E. Salpeter, *A Relativistic Equation for Bound State Problems,* Phys. Rev. **82**, 309–310 (1951), where the abstract of a paper presented at the 303-rd Meeting of the America Physical Society is reported. In the same year the equation was published in the paper with the same title: E. E. Salpeter and H. E. Bethe, *A Relativistic Equation for Bound State Problems*, Phys. Rev. **84**, 1232–1242 (1951); for the proof within quantum field theory see: M. Gell-Mann and F. Low, *Bound States in Quantum Field Theory*, Phys. Rev. **84**, 350–354 (1951).

More details in: G. Onida, L. Reining and A. Rubio, *Electronics excitations: density functional vs. many-body Green's-function approaches*, Rev. Mod. Phys. **74** (2), 601–659 (2002).

biexciton = excitonic molecule, which is a bound state of two electron-hole pairs (**exciton**s) similar to the hydrogen molecule.

binary decision diagram (BDD) – a directed acyclic graph with exactly one root, whose sinks are labeled by the constants 1 and 0, and whose internal nodes are labelled by a Boolean variable → **Boolean algebra**. The *nodes* have only two outgoing edges, a 0-edge and 1-edge. Such diagrams are suitable for representation of logic functions and computing.

First described in: C. Y. Lee, *Representation of switching circuits by binary-decision programs*, Bell Systems Technical Journal **38**, 985–999 (1959).

More details in: R. Drechsler, B. Becker, *Binary Decision Diagrams–Theory and Implementation* (Kluwer Academic Publishers, Boston, 1998).

biophysics – the physics of living organisms and vital processes. It studies biological phenomena in terms of physical principles.

bifurcation – a qualitative change in the properties of a system.

bioengineered materials – materials employed in biomedical technology designed to have specific, desirable biological interactions with the surroundings. Materials scientists are increasingly deriving new lessons from naturally occurring materials about useful composition–structure property relationships that might be mimicked with synthetic materials → **biomimetics**.

More details in: M. Tyrrell, E. Kokkoli, M. Biesalski, *The role of surface science in bioengineered materials*, Surface Sci. **500**, 61–83 (2002).

biological surface science – the broad interdisciplinary area where properties and processes at interfaces between synthetic materials and biological environments are investigated and biofunctional surfaces that are capable of directing and controlling a desired biological response are fabricated.

More details in: B. Kasemo *Biological surface science*, Surface. Sci. **500**, 656–677 (2002).

biomimetics – the concept of taking ideas from nature (imitating, copying and learning) and implementing them into another technology.

bioremediation – a use of biological agents to reclaim soils and waters polluted by substances hazardous to human health and/or environment. It is an extension of biological treatment processes that have been used traditionally to treat wastes in which micro-organisms typically are used to biodegrade environmental pollutants. In the case of nanomaterials the driver would be to design systems capable of fixing heavy metals, cyanides and other environmentally damaging materials.

Biot law states that an optically active substance rotates plane polarized light through an angle inversely proportional in its wavelength.

First described by J. B. Biot in 1815.

bipyridine – the organic compound $C_{10}H_8N_2$ shown in Figure B.3.

It consists of two **pyridine** molecules linked by a single bond.



Figure B.3 Bipyridine molecule.

Bir–Aronov–Pikus mechanism – the electron spin relaxation mechanism in semiconductors caused by exchange and annihilation interaction between electrons and holes.

This mechanism is important for p-doped semiconductors, in which the electron-hole exchange interaction gives rise to fluctuating local magnetic fields flipping electron spins. For electron-spin relaxation due to exchange with nondegenerate holes the relaxation time is

$$\frac{1}{\tau_s} = \frac{2}{\tau_0} N_a a_b^3 \frac{v_k}{v_B} \left[\frac{p}{N_a} |\psi(0)|^4 + \frac{5}{3} \frac{N_a - p}{N_a} \right],$$

where t_0 is the exchange splitting parameter, N_a is the concentration of acceptors, p is the concentration of free holes, a_B is the exciton Bohr radius, the velocity $v_B = \frac{\hbar}{m_c a_B}$ (with m_c denoting the conduction electron mass), $|\psi(0)|^2$ is the **Sommerfeld's factor** enhancing the free hole contribution.

The exchange splitting parameter is defined from $\frac{1}{\tau_0} = \frac{3\pi}{64} \frac{\Delta_{ex}^2}{\hbar E_B}$ with the Bohr exciton energy $E_B = \frac{\hbar^2}{2 m_c a_B^2}$ and Δ_{ex} to be the exchange splitting of the excitonic ground state.

If holes are degenerate and the velocity of electrons v_k is greater than the Fermi velocity of the holes, then

$$\frac{1}{\tau_s} = \frac{3}{\tau_0} p a_B^3 \frac{v_k}{v_B} \frac{k_B T}{E_{Fh}},$$

where k_B is the Boltzmann constant, T is the absolute temperature, and E_{Fh} is the hole Fermi energy.

For degenerate holes $|\psi(0)|^2$ is of order of 1. If electrons are thermalized, v_k has to be replaced by the thermal velocity $v_e = (\frac{3k_BT}{m_c})^{\frac{1}{2}}$.

The temperature dependence of the relaxation time τ_s is dominated by the temperature dependence of the Sommerfeld's factor as well as by the hole concentration p. The influence of the acceptor concentration N_a is evident from the above equations, and is essentially $\frac{1}{\tau_s} \sim N_a$ for nondegenerate/bound holes and $\frac{1}{\tau_s} \sim N_a^{\frac{1}{3}}$ for degenerate holes.

First described in: G. L. Bir, A. G. Aronov, G. E. Pikus, *Spin relaxation of electrons scattered by holes,* Zh. Eksp. Teor. Fiz. **69**(4), 1382–1397 (1975) – in Russian.

birefringence – splitting of light passing through a plate made of an optically anisotropic material into two refracted waves with two different directions and polarizations. It is illustrated in Figure B.4.

Because of the different **refractive indices** in different directions, the material of the plate supports two different modes of distinctly different phase velocities. Therefore, each incident wave splits into two orthogonal components.

Anisotropic crystal plates, e.g. quartz or rutile, are used as polarizing light splitters creating two laterally separated rays with orthogonal polarizations.



Figure B.4 Birefringence of light passing through optically anisotropic uniaxial plate.

Birge–Mecke rule states that the product of the equilibrium vibrational frequency and the square of the internuclear distance is a constant for various electronic states of a diatomic molecule.

First described in: R. Mecke, *Zur Systematik der Bandenspektra,* Z. Phys. **28**(1), 261–277 (1924); R. Mecke, Phys. Z. **26**, 217–225 (1925); R. T. Birge, *The structure of molecules,* Nature **117**, 300–302 (1926).

bit – an acronym for a **bi**nary digi**t**. It is a unit of information content equal to one binary decision or the designation of one of two possible and equally likely values or states of anything used to store or convey information.

Bitter pattern – a pattern produced when a drop of colloidal suspension of **ferromagnetic** particles is placed on the surface of a ferromagnetic crystal. The particles collect along domain boundaries at the surface.

First described in: F. Bitter *On inhomogeneities in the magnetization of ferromagnetic materials,* Phys. Rev. **38**(10), 1903–1905 (1931).

black-and-white groups = **Shubnikov groups**.

bleaching – a loss of **fluorescence**. It often occurs as a result of photochemical reactions.

Bloch equation provides a simple method for detecting change in the orientation of nuclear moments through the normal methods of radio reception. The signals to be detected would be due to the electromagnetic induction caused by nuclear reorientation and should appear as a voltage difference between the terminals of an external electric circuit.

Consider a great number of nuclei contained in a macroscopic sample of matter and acted upon by two external magnetic fields: a strong constant field in the z direction with strength H_0 and a comparatively weak radio-frequency field in the x direction of amplitude $2H_1$ and frequency ω, so that the total external field vector $\mathbf{H}$ has components $H_x = 2H_1 \cos(\omega t)$; $H_y = 0$; and $H_z = H_0$. If the thermal agitation does not essentially affect the nuclei (i.e. the time of establishment of thermal equilibrium or relaxation time is long compared to the considered time intervals), the angular momentum vector $\mathbf{A}$ satisfies the classical equation $\mathrm{d}\mathbf{A}/\mathrm{d}t = \mathbf{T}$, where $\mathbf{T}$ is the total torque acting upon the nuclei and is $\mathbf{T} = [\mathbf{MH}]$, where $\mathbf{M}$ represents the nuclear polarization, i.e. the magnetic moment per unit volume. The parallelity between the magnetic moment μ and the angular momentum a for each nucleus implies that $\mu = \gamma a$, where γ is the gyromagnetic ratio. Thus, we have $\mathbf{M} = \gamma\mathbf{A}$. Combining the previous equation gives the Bloch equation for the temporal variation of the nuclear polarization vector $\mathbf{M} : \mathrm{d}\mathbf{M}/\mathrm{d}t = \gamma[\mathbf{MH}]$.

Consequently a *radio-frequency* field at right angles to constant field causes a forced precession if the total polarization around the constant field, with a latitude that decreases as the frequency of the oscillating field, approaches the **Larmor** frequency. For frequencies near this magnetic resonance frequency one can expect an oscillating induced voltage in a pick-up coil with axis parallel to the y direction.

The relaxation of the condition about the influence of thermal agitation provides a way to the introduction of time constants or relaxation times t_1 and t_2. The system now performs a damped (relaxation acts like friction) precession in which the x and y components of M decay to zero with the time constant t_2 (called the transverse relaxation time) whereas M_z approaches its equilibrium value M_0 with the time constant t_1 (called the thermal or longitudinal relaxation time).

First described in: F. Bloch, *Nuclear induction,* Phys. Rev. **70**(7/8), 460–474 (1946), F. Bloch, W. W. Hansen, M. Packard, *The nuclear induction experiment,* Phys. Rev. **70**(7/8), 474–483 (1946).

Recognition: in 1952 F. Bloch and E. M. Purcell received the Nobel Prize in Physics for their development of new methods for nuclear magnetic precision measurements and discoveries in connection therewith.

See also www.nobel.se/physics/laureates/1952/index.html.

Bloch function – a solution of the **Schrödinger equation** for a periodic potential in the form $\psi_k = u_k exp(i\mathbf{kr})$, where u_k has the period of the crystal lattice $\mathbf{T}$, so that $u_k = u_k(\mathbf{r} + \mathbf{T})$. A one-electron wave function of the above form is called a **Bloch function** or a **Bloch wave**. In fact, it is a plane wave with amplitude modulation.

Bloch oscillation – a phenomenon of external electric field induced periodic motion of an electron within a band rather than uniform acceleration.

Bloch sphere represents the three-dimensional simulation and visualization through a vector (Bloch vector) of the dynamics of a two level system under near-resonant excitation. It is well known in nuclear magnetic resonance and quantum optics. A famous application is due to Feynman, Vernon and Hellwarth, who demonstrated that the behavior of any quantum mechanical two-level system can be modeled by classical torque equations, that is there is a one-to-one correspondence between the dynamics of a two level system and the dynamics of a spinning top. The Bloch sphere is also widely used in quantum computing. In the computational basis, the general one **qubit** state is represented as a linear combination of the basis states $|a\rangle$ and $|b\rangle$ and is denoted by $|\psi\rangle = a|0\rangle + b|1\rangle$, where $|a|^2 + |b|^2 = 1$. Thus, the qubit state can be written in the form $|\psi\rangle = exp(\mathrm{i}\gamma)[\cos(\theta/2)|0\rangle + exp(\mathrm{i}\phi)\sin(\theta/2)|1\rangle]$ and by ignoring the global phase factor, because it has no observable effects, one has $|\psi\rangle = \cos(\theta/2)|0\rangle + exp(\mathrm{i}\phi)\sin(\theta/2)|1\rangle$.

The angles ϕ and θ define a point (Bloch vector) on the unit three dimensional sphere, which is the Bloch sphere, as illustrated in Figure B.5.



Figure B.5 Bloch sphere representation of a qubit state. The yellow arrow represents a pure $|\psi\rangle$ qubit state. The Euler angles, θ and ϕ are indicated. The red arrow along the z axis represents the vector for $|0\rangle$.

First described in: F. Bloch, A. Siegert, *Magnetic resonance for nonrotating field*, Phys. Rev. **57**(6), 522–527 (1940).

More details in: R. P. Feynman, F. L. Vernon Jr., R. W. Hellwarth, *Geometrical representation of the Schrödinger equation for solving maser problems*, J. Appl. Phys. **28**(1), 49–52 (1957).

Bloch–Torrey–Kaplan equations describe magnetization dynamics accounting for spin precession, spin relaxation and spin dephasing of a spin ensemble. Electronic magnetization $\mathbf{M}$ in an applied magnetic field $\mathbf{B}(t) = B_0\mathbf{z} + \mathbf{B}_1(t)$, with a static longitudinal component B_0 (in the $\mathbf{z}$ direction) and a transverse oscillating part $\mathbf{B}_1$ (perpendicular to $\mathbf{z}$) varies as follows:

$$\begin{aligned}
\frac{\partial M_x}{\partial t} &= \gamma(\mathbf{M} \times \mathbf{B})_x - \frac{M_x}{T_1} + D\nabla^2 M_x, \\
\frac{\partial M_y}{\partial t} &= \gamma(\mathbf{M} \times \mathbf{B})_y - \frac{M_y}{T_1} + D\nabla^2 M_y, \\
\frac{\partial M_z}{\partial t} &= \gamma(\mathbf{M} \times \mathbf{B})_z - \frac{M_z - M_z^0}{T_2} + D\nabla^2 M_x,
\end{aligned}$$

where $\gamma = \frac{\mu_B g}{h}$ is the electron gyromagnetic ratio (with g denoting the electronic g factor), T_1 is the spin dephasing time, T_2 is the spin relaxation time, D is the diffusion coefficient, $M_z^0 = \chi B_0$ (with χ denoting the system's static susceptibility) is the thermal equilibrium magnetization.

The time T_1 is the time it takes for an ensemble of transverse electron spins, initially precessing in phase about the longitudinal field, to lose their phase due to spatial and temporal fluctuations of the precessing frequencies. The time T_2 is the time it takes for the longitudinal magnetization to reach equilibrium. Equivalently, it is the time of thermal equilibration of the spin population with the lattice. In T_2 processes the energy has to be taken from the spin system, usually by phonons, to the lattice. Note that spin decoherence and relaxation processes in many spin systems are generally too complex to be fully described by only two parameters T_1 and T_2. Nevertheless these parameters are extremely robust and convenient measures for quantifying such processes are in many cases of interest.

First described in: F. Bloch, *Nuclear induction*, Phys. Rev. **70**(7/8), 460–474 (1946); H. C. Torrey, *Bloch equations with diffusion terms*, Phys. Rev. **104**(3), 563–565 (1956); J. I. Kaplan, *Application of the diffusion-modified Bloch equation to electron spin resonance in ordinary and ferromagnetic metals*, Phys. Rev. **115**(3), 575–577 (1959).

Bloch wall – a transition layer or sheet which separates adjacent domains magnetized in different directions in **ferromagnetic** or **ferrimagnetic** materials. It is also known as a **domain wall**.

First described in: F. Bloch, *Theory of the exchange problem and residual ferromagnetism*, Z. Phys. **74**(5/6), 295–335 (1932).

Bloch wave = **Bloch function**.

blue shift – a systematic shift of an optical spectrum toward the blue end of the optical range.

body centered cubic (bcc) structure – a cubic lattice with one lattice point in the center of the **unit cell** in addition to the eight corner points. It is schematically shown in Figure B.6.



Figure B.6 Body-centered cubic structure.

Bohr correspondence principle states that quantum mechanics has a classical limit in which it is equivalent to classical mechanics. It should occur in the limit of vanishing **de Broglie wavelength**, or equivalently, at large quantum numbers.

First described in: N. Bohr, *Atomic structure,* Nature **108**, 208–209 (1921).

Recognition: in 1922 N. Bohr received the Nobel Prize in Physics for his services in the investigation of the structure of atoms and of the radiation emanating from them.

See also www.nobel.se/physics/laureates/1922/index.html.

Bohr frequency relation states that the frequency of radiation emitted or absorbed by a system when E_2 and E_1 are the energies of the states among which the transition takes place is $\nu = (E_2 + E_1)/h$.

First described in: N. Bohr *On the constitution of atoms and molecules,* Phil. Mag. **26**, 1–25 (1913).

Bohr magneton – the atomic unit of magnetic momentum, usually denoted by $\mu B = e\hbar/2m$, where m is the electron mass. It is the magnetic momentum of a single free electron spin.

Bohr magneton number – a magnetic momentum of an atom expressed in **Bohr magnetons**.

Bohr potential – the potential describing strong screened Coulomb collisions of two atoms in the form:

$$V(r) = \frac{Z_1 Z_2 e^2 a^{n-1}}{r^n} \left(\frac{n-1}{2.718}\right)^{n-1}.$$

For $n = 2$, it is

$$V(r) = \frac{Z_1 Z_2 e^2 a}{r^2} \left(\frac{1}{2.718}\right),$$

where r is the interatomic distance, and Z_1 and Z_2 are the atomic numbers of the interacting atoms,

$$a = \frac{a_B k}{(Z_1^{2/3} + Z_2^{2/3})^{1/2}}, \quad \text{where } k = 0.8\text{–}3.0$$

is the empirical coefficient used to fit experimental data.

First described in: N. Bohr, *The penetration of atomic particles through matter*, Kgl. Danske Videnskab. Selskab. Mat.-fys. Medd. **18**(8), 1–144 (1948).

Bohr radius – the radius of the lowest energy orbit in a hydrogen atom, denoted by $a_B = \hbar^2/me^2$, where m is the electron mass.

Boltzmann distribution (statistics) gives the number of noninteracting (or weakly interacting), distinguishable, classical particles with the energy E in equilibrium at a temperature T in the form $n(E) = A exp[-E/(k_B T)]$, where A is the normalization constant.

First described by: L. Boltzmann in 1868–1871. See L. Boltzmann, *Einige allgemeine Sätze über Wärmegleichgewicht*, Sitzungsber. Akad. Wiss. Wien **63**, 679–711 (1871).

Boltzmann transport equation is used in the classical theory of transport processes: $\partial f/\partial t + \mathbf{v} grad_v f + \alpha grad_v f = (\partial f/\partial t)_{coll}$, where $f(r, v)$ is the classical distribution function of particles in six-dimensional space of the Cartesian coordinates r and velocity v. It is defined as $f(r, v)\mathrm{d}r\mathrm{d}v =$ number of particles in $\mathrm{d}r\mathrm{d}v$. $\alpha = \mathrm{d}v/\mathrm{d}t$ is the acceleration. In many problems the collision term is treated by the introduction of a relaxation time $\tau : (\partial f/\partial t)_{coll} = -\frac{f-f_0}{\tau}$, where f_0 is the distribution function in thermal equilibrium. In the steady state $\partial f/\partial t = 0$ by definition.

bonding orbital – an atomic or molecular orbital which, if occupied by an electron, contributes to lowering of the energy of the molecule → **antibonding orbital**. Bonding is characterized by a bond order $b = 0.5(n - n^*)$, where n is the number of electrons in bonding orbitals and n^* the number in antibonding orbitals.

bond order → **bonding orbital**.

Boolean algebra (logic) – an algebraic system with two binary operations and one unitary operation important in representing a two-valued logic. Boolean calculus is useful for elucidating situations that can be *true* or *false*, making appropriate reasonings to draw conclusions correctly. They are therefore helpful in building practical computers and in programming.

First described in: G. Boole, *Mathematical Analysis of Logic* (1847) and *An Investigation of the Laws of Thought on which are founded the Mathematical Theories of Logic and Probabilities* (Walton and Maberly, London 1854).

Born approximation is based on an application of the perturbation theory to scattering problems in quantum mechanics. It consists of assuming that the scattering potential $V(r)$ can be regarded as small, so that the deviation of the wave function $\psi(r)$ from the incident plane wave is also small. So, one can write $V(r)\psi(r) \approx V(r)exp(\mathbf{ikr})$. This simplifies finding the solution of an appropriate **Schrödinger equation**. The approximation is most useful when the energy of colliding particles is large compared to the scattering potential.

First described in: M. Born, *Zur Quantenmechanik der Stossvorgänge*, Z. Phys. **37**(12), 863–867 (1926).

Recognition: in 1954 M. Born received the Nobel Prize in Physics for his fundamental research in quantum mechanics, especially for this statistical interpretation of the wavefunction.

See also www.nobel.se/physics/laureates/1954/index.html.

Born equation – an equation for determining the free energy of solvation of an ion. The equation identifies the variation in the **Gibbs free energy** for the process of solvation with the electrical work of transferring an ion from vacuum into the solvent as

$$\Delta G = -1/2\left(\frac{Z^2 e^2 n_A}{4\pi\varepsilon_0 R}\right)[1 - (1/\varepsilon_r)],$$

where Z is the ion's electric charge number, R is the ionic radius, and ε_r is the relative dielectric constant of the solvent.

First described in: M. Born, *Volumen und Hydratationswärme der Ionen*, Z. Phys. **1**(1), 45–48 (1920).

Born–Haber cycle – a sequence of chemical and physical processes by means of which the cohesive energy of an **ionic crystal** can be deduced from experimental qualities. It leads from an initial state in which a crystal is at zero pressure and 0 K to a final state, which is an infinitely dilute gas of its constituent ions in the same pressure and temperature conditions.

First described by: M. Born, Ver. Deut. Phys. Ges. **21**, 13 (1919), F. Haber, Ver. Deut. Phys. Ges. **21**, 750 (1919).

Born–Mayer potential – the interatomic pair potential in the form:

$$V(r) = A \exp\left(-\frac{r}{a}\right),$$

where r is the interatomic distance, and A and a are the empirical parameters depending on the charge of the nucleus. It is used for the simulation of closed electron ion shells repulsion.

First described in: M. Born, J. E. Mayer, *Zur Gittertheorie der Ionenkristalle*, Z. Phys. **75**(1/2), 1–18 (1932).

More details in: I. G. Kaplan, *Intermolecular Interactions: Physical Picture, Computational Methods and Model Potentials* (John Wiley & Sons, Chichester, 2006).

Born–Mayer–Bohr potential – the interatomic pair potential in the form of the **Born–Mayer potential** taking into account the Coulomb repulsion:

$$V(r) = A \exp\left(-\frac{r}{a}\right) + \frac{Z_1 Z_2 e^2}{r} \exp\left(-\frac{r}{a}\right),$$

where r is the interatomic distance, A and a are the empirical parameters depending on charge of the nucleus, and Z_1 and Z_2 are the atomic numbers of the interacting atoms.

Born–Mayer–Huggins potential – the interatomic pair potential in the form:

$$V(r) = A \exp\left(-\frac{r}{a}\right) + \frac{q_1 q_2}{4\pi\varepsilon_0} \operatorname{erfc}\left(\frac{r}{b}\right),$$

where the first term corresponds to repulsion and the second to a Coulomb interaction. Here r is the interatomic distance, A, a, and b are the empirical parameters, and q_1 and q_2 are formal charges of the atoms.

First described in: M. L. Huggins, J. E. Mayer, *Interatomic distances in crystals of the alkali halides*, J. Chem. Phys. **1**(9), 643–646 (1933); M. L. Huggins, *Molecular constants and potential energy curves for diatomic molecules*, J. Chem. Phys. **3**(8), 473–479 (1935).

Born–Oppenheimer approximation separates electronic and nuclear motions. It supposes that the nuclei, being so much heavier than the electron, move relatively slowly and may be treated as stationary as electrons move around them → **adiabatic approximation**.

First described in: M. Born, R. Oppenheimer, *Zur Quantum Theorie der Molekeln*, Ann. Phys. 84(4), 457–484 (1927).

Born–von Kármán boundary conditions – periodic boundary conditions used in quantum mechanical calculations. They suppose that the system under consideration can be constructed by repeating translations of a subsystem with the same wave function in each subsystem. It means that for a period of translation T the wave function $\psi(x)$ at $x = T$ must match smoothly to that at $x = 0$, which requires $\psi(0) = \psi(T)$ and $\frac{\partial\psi}{\partial x}|_{x=0} = \frac{\partial\psi}{\partial x}|_{x=L}$.

First described in: M. Born, T. von Karman, *Über die Verteilung der Eigenschwingungen von Punktgittern*, Phys. Z. **14**, 65–71 (1913).

Bose–Einstein condensate – an ensemble of particles, which are in the same quantum ground state, that is with zero momentum. To create such a state from atoms they must be cooled until their **de Broglie wavelength** becomes comparable with the interatomic spacing. This can be achieved at microkelvin temperatures. The process is similar to that when drops of liquid form from a gas; hence the term condensation is used to describe the process peculiarities. Bose–Einstein condensates are considered to be a new state of matter.

First described in: A. Einstein, *Quantentheorie des einatomigen idealen Gase. Zweite Abhandlung*, Sitzungber. Preuss. Akad. Wiss. Berlin **I**, 3–14 (1925) – theory; M. H. Anderson, J. R. Ensher, M. R. Matthews, C. E. Wieman, E. A. Cornell, *Observation of Bose–Einstein condensation in a dilute atomic vapor*, Science **269**, 198–201 (1995); C. C. Bradley, C. A. Sackett, J. J. Tollett, R. G. Hulet, *Evidence of Bose–Einstein condensation in an atomic gas with attractive interactions*, Phys. Rev. Lett. **75**(9), 1687–1690 (1995); K. B. Davis, M. O. Mewes, M. R. Andrews, N. J. van Druten, D. S. Durfee, D. M. Kurn, W. Ketterle, *Bose–Einstein Condensation in a gas of sodium atoms*, Phys. Rev. Lett. **75**(22), 3969–3973 (1995) – experiment.

Recognition: in 2001 E. A. Cornell, W. Ketterle and C. E. Wieman received the Nobel Prize in Physics for the achievement of Bose–Einstein condensation in dilute gases of alkali atoms, and for early fundamental studies of the properties of the condensates.

See also www.nobel.se/physics/laureates/2001/index.html.

More details in: W. Ketterle, *Dilute Bose–Einstein condensates – early predictions and recent experimental studies,*

www.physics.sunysb.edu/itp/symmetries-99/scans/talk06/talk06.html.

Bose–Einstein distribution (statistics) gives the number of photons with an energy E at a temperature T:

$$n(E) = \frac{1}{exp(E/k_B T) - 1}.$$

In general, it is relevant to particles which are indistinguishable and occupy definite quantum states, that is **bosons**.

First described in: S. N. Bose, *Plancks Gesetz und Lichtquantenhypothese,* Z. Phys. **26**(3), 178–181 (1924) and A. Einstein, *Quantentheorie des einatomigen idealen Gases. Erste Abhandlung,* Sitzungsber. Preuss. Akad. Wiss. Berlin **22**, 262–267 (1924).

bosons – quantum particles whose energy distribution obeys **Bose–Einstein statistics**. They have an integral or zero spin.

bottom-up approach – one of two ways to fabricate nanometer size elements of integrated electronic circuits. This is by building nanostructures from atoms and molecules by their precise positioning on a substrate. Hence a single device level is constructed upward.

Self-regulating processes, like **self-assembling** and **self-organization**, and **atomic engineering** are used for this. The alternative is a **top-down approach**. The bottom-up approach has the potential to go far beyond the limits of top-down technology by producing nanoscale features through synthesis and subsequent assembly.

Bouguer–Lambert law – a radiation power P of a parallel beam of monochromatic radiation entering an absorbing medium is described at a constant rate by each infinitesimally thin layer of thickness $\mathrm{d}x$. It is expressed mathematically as $\mathrm{d}P/P = -\alpha \mathrm{d}x$, where α is the parameter depending on the nature of the absorber, energy of radiation, and for some materials (indeed for semiconductors) on the temperature. An integration gives $P = P_0 exp(-\alpha x)$ for a uniform medium, where P_0 is the power of the incident beam. Here α is the absorption coefficient of the medium.

First described by P. Bouger in 1729 – experiment; J. H. Lambert in 1760 – theory.

bound state (of an electron in an atom) – a state in which the energy of the electron is lower than it is when infinitely far away and at rest (which corresponds to the zero of energy). Bound states always have negative energies → **unbound state**.

Bowden–Tabor law takes into account the problem of **real contact area** between bodies to explain the independence of **Amonton's law** on the apparent contact area. When two rough surfaces are in contact, the apparent contact area, that is the projected area of one body on the other, is much bigger (several orders of magnitude) than the real contact area between the surface asperities. The force friction thus becomes $F_f = \tau A_r$, where τ is the **shear modulus**, the friction force per unit area, and A_r is the real contact area. This equation is considered to be the fundamental equation for friction.

First described in: F. P. Bowden, D. Tabor, *The area of contact between stationary and moving surfaces*, Proc. R. Soc. Lond. A **169**, 391–413 (1939).

bra → **Dirac notation**.

Bragg equation defines conditions for an interference maximum, when X-rays with a single wavelength λ are diffracted by crystals as in Figure B.7.

It has the form $n\lambda = 2d \sin\theta$, where n is an integer representing the order of the interference, d is the spacing between the lattice planes reflecting the X-rays, θ is the angle between the falling X-rays and lattice planes. The reflection in conditions meeting the above requirement is called the **Bragg reflection**, and θ is the **Bragg reflection angle**. In fact, the Bragg reflection providing the interference of the reflected rays is not restricted to X-rays only, but is a general phenomenon for interaction of waves with periodic structures.

First described in: W. L. Bragg, *Diffraction of short electromagnetic waves by a crystal*, Proc. Camb. Phil. Soc. **17**(1), 43–57 (1913).

Recognition: in 1915 W. H. Bragg and W. L. Bragg received the Nobel Prize in Physics for their services in the analysis of crystal structures by means of X-rays.

See also www.nobel.se/physics/laureates/1915/index.html.



Figure B.7 Scheme of Bragg diffraction.

Bragg reflection → **Bragg equation**.

Bragg reflection angle → **Bragg equation**.

braking radiation → **Bremsstrahlung**.

Bravais lattice – a distinct type of lattice, which being translated completely fills the space. There are 5 Bravais lattices in two dimensions shown Figure B.8.



Figure B.8 Bravais lattices in two dimensions.

There are 14 lattices in three dimensions shown in Figure B.9. Only these fundamentally different lattices are possible.

First described by: A. Bravais, *Études cristallographiques,* Paris 1866.


Primitive
Base centered
Body centered
Face centered
Triclinic
Monoclinic
Orthorombic
Tetragonal
Trigonal
Hexagonal
Cubic
c
β
α
γ
b
a
120°

Figure B.9 Bravais lattice in three dimensions (angles are indicated where they are different from 90°).

Breit–Wigner formula → **Breit–Wigner resonance**.

Breit–Wigner resonance – a nuclear reaction induced by an incident particle with energy E corresponding to that required to form a discrete resonance level E_{res} of the component nucleus. The cross section is

$$\sigma(e) = \sigma_{res}\frac{\Gamma^2/4}{(E_{res}^2 - E^2) - \Gamma^2/4},$$

which is called the **Breit–Wigner formula**. Here Γ denotes the energy width over which the reaction occurs and σ_{res} is the resonant cross section.

First described in: G. Breit, E. Wigner, *Capture of slow neutrons*, Phys. Rev. **49**(7), 519–531 (1936).

Bremsstrahlung – German equivalent of the radiation also called **collision radiation** or **deceleration radiation** or **braking radiation**. This radiation arises when an electron is deflected by the Coulomb field of an atomic nucleus. In bremsstrahlung, a continuous spectrum with a characteristic profile and energy cutoff, that is wavelength minimum, is produced. In addition, lines can appear superimposed, corresponding to the ejection of K and L shell electrons knocked out of atoms in collisions with the high-energy electrons. This radiation is used for the analysis of solid, when it is known as the Bremsstrahlung isochromat spectroscopy technique.

First described theoretically in: H. Bethe, W. Heitler, *On the stopping of fast particles and on the creation of positive electrons*, Proc. Roy. Soc. A **146**, 83–112 (1934).

Bridgman effect – when an electric current passes through an anisotropic crystal, there is an absorption or liberation of heat that results from the nonuniform current distribution.

Bridgman relation – in a metal or semiconductor placed in a transverse magnetic field at a temperature T: $P = QT\sigma$, where P is the **Ettingshausen coefficient**, Q is the **Nernst coefficient**, and σ is the thermal conductivity of the material.

First described in: P. W. Bridgman, *Thermoelectric phenomena and electrical resistance in single metal crystals*, Proc. Am. Acad. Arts Sciences **63**, 351–99 (1929).

Brillouin function – a function of the form $f(x) = [(2n+1)/2n]\coth[(2n+1)x/2n] - (1/2n)\coth(x/2n)$, where n is the parameter. It appears in the quantum mechanical theories of paramagnetism and ferromagnetism.

Brillouin scattering – scattering of light in solids by acoustic waves.

First described in: L. Brillouin, *Diffusion of light and X-rays by a transparent homogeneous body. The influence of thermal agitation*, Ann. Phys. (France) **17**, 88–122 (1922) – in French, and independently L. I. Mandelstam, *On light scattering by an inhomogeneous medium*, Zh. Russkogo Fiz.-Khim. Obshch. **58**(2), 381–386 (1926) – in Russian.

Brillouin zone – a symmetrical unit cell constructed in **reciprocal lattic**e space. The construction procedure is the same as for a **Wigner-Seitz primitive cell** except that the points are now reciprocal lattice points. The Brillouin zones and their points of high symmetry for some often met crystal lattices are shown in Figure B.10.


z
b2
L
Λ
Q
U
S
Σ
Δ
Γ
x
K
W
Z
X
y
b1
b3
b3
z
Z
U
R
T
S
A
W
Λ
V
Δ
b2
Γ
X
y
Σ
Y
M
b1
x

Face-centered cubic

Tetragonal


b3
z
Z
B
A
T
R
Λ
D
H
b1
Σ
Γ
Δ
y
S
Y
F
b2
b2
x
b3
z
B
A
Z
E
T
U
P
R
Λ
H
G
Q
Y
b2
Σ
Γ
Δ
y
X
S
C
D
b1
x

Rhombic base-centered

Rhombic


b3
z
L
A
H
Γ
b1
y
b2
x
M
K

Hexagonal

Figure B.10 Brillouin zones and high-symmetry points of different crystal lattices.

The first Brillouin zone is the smallest polyhedron centered at the origin and enclosed by perpendicular bisectors of reciprocal lattice vectors. In one dimension it is a region of the k-space defined by $[-\pi/R, \pi/R]$, where R is the translation period used to construct the lattice.

First described in: L. Brillouin, *Die Quantenstatistik und ihre Anwendung auf die Elektronentheorie der Metalle* (Springer, Berlin, 1931).

Brownian motion – a random walk whose probability distribution is governed by the **diffusion** equation. The trajectory is **fractal** with the derivative (velocity) not well defined.

First described by: R. Brown, *Mikroskopische Beobachtungen über die im Pollen der Pflanzen enthaltenen Partikeln, und das allgemeine Vorkommen activer Molecüle in organischen und anorganischen Körpern,* Ann. Phys. **14**, 294 (1828) (although he was not the first to see this phenomenon).

Buckingham potential – the interatomic pair potential in the form $V(r_{ij}) = A_{ij} exp(-\frac{r_{ij}}{\sigma_{ij}}) - B_{ij}(\frac{\sigma_{ij}}{r_{ij}})^6$. Here r_{ij} is the interatomic distance and A_{ij}, B_{ij} and σ_{ij} are the parameters fitted to an experiment. The repulsive interaction is represented by the exponential term, and emanates from the repulsion of electron gas clouds around ions as they are brought together. The attractive part of the potential derives from the r_{ij}^{-6} term. It is a response to the dispersion forces sometimes called **van der Waals** attraction.

First described in: R. A. Buckingham, *The classical equation of state of gaseous helium, neon and argon,* Proc. R. Soc. Lond. A **168**, 264–283 (1938).

More details in: I. G. Kaplan, *Intermolecular Interactions: Physical Picture, Computational Methods and Model Potentials* (John Wiley & Sons, Chichester, 2006).

Buckingham's theorem states that if there are n physical quantities $x_1, x_2, \ldots, x_n$ which can be expressed in terms of m fundamental quantities and if there exists one and only one mathematical expression connecting them which remains formally true no matter how the units of the fundamental quantities are changed, namely $f(x_1, x_2, \ldots, x_n) = 0$, then the relation f can be expressed by a relation of the form $F(\pi_1, \pi_2, \pi_n - m) = 0$, where the πs are $n - m$ independent dimensionless products of $x_1, x_2, \ldots, x_n$. It is also known as the **pi or Π theorem**.

First described in: E. Buckingham *On physically similar systems; illustrations of the use of dimensional equations,* Phys. Rev. **4**(4), 345–376 (1914).

Buckminsterfullerene = **fullerene**. The name is related to the architect R. Buckminster Fuller (1895–1983) who pioneered the use of geodesic domes in architecture.

Bunsen–Roscoe law states that the amount of chemical change produced in a light-irradiated reacting system is proportional to the amount of light absorbed. Actually, the change is also dependent on the intensity of light, which is named the

reciprocity failure. Named after the German chemist R. W. E. Bunsen (1811–99) and the English chemist H. E. Roscoe (1833–1915).

Burger's vector shows the direction in which a region of a crystal is displaced relative to the neighboring region, thus forming a dislocation.

Burstein–Moss shift – a blue shift (the shift to the shorter wavelength range) of the absorption age in semiconductors due to band filling. It is observed in heavily doped materials with filled near band gap states.

First described in: E. Burstein, *Anomalous optical absorption limit in InSb*, Phys. Rev. **93**(3), 632–633 (1954); T. S. Moss, *The interpretation of the properties of indium antimonide*, Proc. R. Phys. Soc. Lond. B **67**(10), 775–782 (1954).

C

From cage compound to cyclotron resonance

cage compound = **clathrate compound**.

Caldeira–Leggett model deals with the problem of dissipation in a quantum system. The model consists of an independent oscillator bath linearly coupled to the system of interest through a coordinate-coordinate coupling. Originally it was used for the study of the quantum **Brownian motion** showing that in the classical limits the formalism reduces to the classical **Fokker–Planck equation**. The model has been widely used for study of the influence of damping on quantum interference with special attention to quantum tunneling and quantum coherence. Effective decoherence as a result of the interaction of a quantum system with an environment can provide a natural mechanism for the transition from quantum to classical behavior.

First described in: A. O. Caldeira, A. J. Leggett, *Path integral approach to quantum Brownian motion*, Physica A: Statistical and Theoretical Physics, **121**(3), 587–616 (1983).

calixarene → **electron-beam lithography**.

Callier effect – selective scattering of light as it passes through a diffusing medium.

First described in: A. Callier, Photogr. J. **49**, 200 (1909).

canonical – relating to the simplest or most significant form of a general function, equation, statement, rule or expression.

canonical equations of motion → **Hamiltonian equations of motion**.

capacitance – a ratio of the charge Q on one of the plates of a capacitor (there being an equal and opposite charge on the other plate) to the potential difference V between the plates: $C = Q/V$.

carbohydrate – an organic compound containing carbon, hydrogen and oxygen atoms in a 1 : 2 : 1 molecular ratio. Carbohydrates have the general formula $C_n(H_2O)_n$.

Carbohydrates are naturally produced by plants and animals. Glucose ($C_6H_{12}O_6$) is one of the most important among them, being used as an energy source in living bodies.

carbon dioxide laser – a type of **ion laser** with carbon dioxide gas as the active medium that produces infrared radiation at 10.6 μm.

carbon nanotube – naturally self-organized nanostructure in the form of a tube composed of carbon atoms with completed bonds. There are two general forms, which are single-wall and multiwall nanotubes. A single-wall carbon nanotube can be considered as a single sheet of graphite, which is called **graphene**, that has been rolled up into a tube. The resulting nanotube can have metallic or semiconducting properties depending on the direction in which the sheet was rolled up.

Graphene is a two-dimensional honeycomb net made up of sp^2 bonded carbon atoms as sketched in Figure C.1.

In a tube, some small contribution of sp^3 states are mixed in as a result of the tube curvature. For a seamless tube, the circumference or **chiral vector** $\mathbf{C}_h$ must be a linear combination of the unit vectors $\mathbf{a}_1$ and $\mathbf{a}_2$: $\mathbf{C}_h = n\mathbf{a}_1 + m\mathbf{a}_2$, where n and m are integers. These integers placed in brackets, for example (n, m), are used to identify a particular structure of a tube. The angle between $\mathbf{C}_h$ and $\mathbf{a}_1$ is called the **chiral angle**. The chiral vector also defines the propagation vector, which represents the periodicity of the tube structure in the direction parallel to its axis.

Typical structures of carbon nanotubes are shown in Figure C.2. If $n = m$, the chiral angle is 30° and the structure is called **armchair**. If either n or m is zero, the chiral angle is 0° and the structure is called **zig-zag**. All other nanotubes with nonzero $n \neq m$ have chiral angles between 0° and 30°. They are said to have a **chiral structure**. There is a mirror image of their structure upon an exchange of n and m. The average diameter of single-wall nanotubes is 1.2–1.4 nm.



Figure C.1 Arrangement of carbon atoms in graphene.



Figure C.2 Carbon nanotubes with different chiral vectors defined by n and m (by courtesy of Professor L. Kavan).

Electronic properties of single-wall nanotubes may be understood when those of graphene are analyzed. Graphene does not conduct electric current, except along certain directions where cones of electronic states at carbon atoms exist. This gives rise to the anisotropy of electronic properties of graphene in two principal directions, namely in the direction parallel to a C–C bond and in the direction perpendicular to a C–C bond. The electronic band structure of graphene is determined by electron scattering from the carbon atoms. Electrons moving along a C–C bond are backscattered by carbon atoms periodically appearing on their way. As a result, only electrons with certain energy can propagate in this direction. Thus, the material shows an energy gap like that in a semiconductor. Electrons traveling in the direction perpendicular to a C–C bond are scattered by different atoms. They interfere destructively, which suppresses backscattering and leads to metallic-like behavior. Thus, single-wall carbon nanotubes rolled up around an axis parallel to a C–C bond have semiconducting properties, while those rolled up around an axis perpendicular to the bonds are metallic in their electronic properties.

A particular electronic behavior of the nanotube is defined by its chiral vector $\mathbf{C}_h$ or equivalently by the relation of n and m. Armchair tubes always show metallic properties. This is also the case for zig-zag and chiral tubes, but when $n - m = 3i$, where i is an integer. In contrast, zig-zag and chiral tubes with $n - m \neq 3i$ demonstrate semiconducting behavior.

The fundamental band gap in semiconducting nanotubes ranges from 0.4 eV to 0.7 eV, being dependent on small variations in the diameter and bonding angle. In general, the band gap decreases with an increase of the tube diameter. There is quantum confinement in the radial direction of the tube provided by the monolayer thickness of its wall. In fact, single-wall nanotubes behave as one-dimensional structures. Electrons can travel along the tube for long distances without being backscattered. Moreover, metallic carbon nanotubes have been found to behave like quantum dots.

Multiwall nanotubes consist of several concentrically arranged single-wall nanotubes. They are typically 10–40 nm in diameter. Intertube coupling within a multiwall nanotube has a relatively small effect on its electronic band structure. As a consequence, semiconducting and metallic tubes retain their character if they are a part of a multiwall nanotube. By statistical probability, most of multiwall carbon nanotubes demonstrates overall metallic behavior because at least one metallic tube is sufficient to short circuit all semiconducting tubes. The phase coherence length in multiwall nanotubes (at 4.2 K) is about 250 nm, the elastic scattering length being about 60 nm.

Nanotubes have an impressive list of attributes. They can behave like metals or semiconductors, can conduct electric current better than copper, can transmit heat better than diamond, and rank among the strongest materials known-not bad for structures that are just a few nanometers across.

Carbon nanotubes are fabricated by vaporizing carbon electrodes using arc discharge, laser ablation, or chemical vapor deposition. The nanotubes grown by the arc discharge and laser ablation techniques produce tangled bunches. They are randomly arranged on electrodes or on a substrate, which makes them difficult to sort and manipulate for subsequent building of nanoscale electron devices. For studies and applications the tubes are extracted into suspension in dichloroethane by a short sonication and then dispersed and dried onto silicon or SiO_2 covered substrates. An **atomic force microscope (AFM)** operating in tapping mode is used to select appropriate nanotubes and locate them at a desired place on the substrate. In contrast, controlled growth of the tubes can be achieved by the use of the **chemical vapor deposition (CVD)** technique.

For the chemical vapor deposition of carbon materials, a hydrocarbon gas is passed over a heated catalyst. The action of the catalyst causes the hydrocarbon to decompose into hydrogen and carbon atoms, which provide the feedstock for the carbon tube growth. The key parameters controlling the growth are the type of hydrocarbons and catalysts used as well as the temperature at which the reaction is initiated. For fabrication of multiwall nanotubes one can use ethylene or acetylene gas as the carbon precursor, and iron, nickel or cobalt as the catalyst. The growth temperature is typically in the range of 500–700°C. At these temperatures carbon atoms dissolve in the metal, which eventually becomes saturated. The carbon then precipitates to form solid tubes, the diameters of which are determined by the size of the metal particles in the catalyst. The relatively low temperature of the process makes difficult the fabrication of tubes with a perfect crystalline structure. Thus, the use of methane and processing temperature as high as 900–1000°C is appropriate to produce virtually defect-free tubes, in particular single-wall ones. Methane is the most stable of all the hydrocarbon compounds with respect to the decomposition at high temperatures. It is a crucial property that prevents formation of amorphous carbon, which poisons the catalyst and coats the tubes.

Well-positioned and oriented tower-like bundles of nanotubes can be fabricated by CVD onto silicon substrates patterned with catalyst materials. Useful approaches are schematically shown in Figure C.3.



Figure C.3 Principles of controlled growth of carbon nanotubes: (a) the use of silicon pillars covered with a catalyst material, (b) the use of catalyst islands on SiO_2 film.

One of them includes fabrication of silicon pillars, tops of which are covered by the catalyst material (Figure C.3a). Individual nanotubes or bundles of them grow during methane decomposition on the tops of the pillars. They are suspended by the pillars and form networks that are oriented according to the pattern of the pillars. As the nanotubes grow, the flow of the gas keeps them floating and waving in the ''wind''. This prevents the nanotubes from touching the substrate and being caught by the bottom surface. The nearby pillars provide fixing points for the growing tubes. When the waving tubes touch the nearby pillars, the van der Waals interaction between the pillar and the tube are strong enough to catch the nanotubes and hold them aloft.

Controlled growth of nanotubes can be also performed at specific sites on an SiO_2-covered substrate patterned with catalyst islands (Figure C.3b). The mechanism of directional growth in this case has much in common with that previously discussed. A nanotube bridge forms when a tube growing from one catalyst island falls on and interacts with another island. When bundles of nanotubes are grown, an AFM tip is used to cut them mechanically or electrically until a single tube remains between the islands. The interactions tube/island and tube/substrate are strong enough to allow the nanotube to withstand mechanical forces in subsequent lithographic processing. Most methods produce nanotubes as long as 1–10 μm; however, lengths up to 200 μm can be reached.

Doping of the nanotube material, determining the type of charge carriers in semiconducting nanotubes, is achieved by substituting carbon atoms with boron (**acceptor** impurity) or nitrogen (**donor** impurity). Attaching alkali or halogen atoms to the outside of the tube can also be used for these purposes, but it is difficult to control.

Metal contacts connecting nanotubes with other electronic devices on the substrate can be fabricated in a number of different ways. One way is to make the electrodes and then drop the tubes onto them. Another is to deposit the tubes on to a substrate, locate them with a **scanning tunneling microscope (STM)** or AFM, and then attach leads using a lithography technique. More advanced approaches include the possibility of growing the tubes between electrodes made of a catalyst metal or of attaching the tubes to the surface in a controllable fashion using either electrostatic or chemical forces. Titanium has been found to give the lowest contact resistance compared with other metals, like gold and aluminum. The reason is that there is a strong chemical interaction between titanium and carbon atoms giving rise to carbide formation at their interface. This process leads to an intimate electrical coupling between the two materials. Gold and aluminum do not form stable carbides, and thus their contact resistance appears to be higher.

By combining different nanotubes, and supplementing them with gate electrodes, there is the potential to make a wide variety of nanoelectronic devices. The prototypes that have been fabricated include rectifying **diode**s using junctions of metallic and semiconducting tubes, single-electron transistors based on metallic nanotubes, and field-effect transistors employing semiconducting nanotubes.

As carbon atoms have very strong bonds in nanotubes, it is very difficult to displace them. Thus, carbon nanotubes appear to be much more resistant to electromigration than conventional copper and aluminum interconnections in integrated circuits. The electrical current that could be passed through a nanotube reaches 10^{13} A cm^{-2}. Small diameter carbon nanotubes and high current densities make them attractive in field electron emission applications. Mechanical deformations dramatically change the electronic properties of carbon nanotubes. It allows their use as building blocks of nanoscale electromechanical devices.

First described in: S. Iijima, *Helical microtubules of graphitic carbon*, Nature **354**, 56–58 (1991).

More details in: R. Saito, G. Dresselhaus, M. S. Dresselhaus, *Physical Properties of Carbon Nanotubes* (Imperial College Press, Singapore, 1998); P. J. F. Harris, *Carbon Nanotubes and Related Structures* (Cambridge University Press, 1999); R. E. Smalley, M. S. Dresselhaus, G. Dresselhaus, P. Avouris, *Carbon Nanotubes: Synthesis, Structure, Properties and Applications* (Springer, Berlin, 2001); S. Reich, C. Thomsen, J. Maultzsch, *Carbon Nanotubes* (Wiley-VCH, Weinheim, 2004).

See also www.pa.msu.edu/cmp/csc/nanotube.html;
http://shachi.cochem2.tutkie.tut.ac.jp/Fuller/Fuller.html.

carbonyl – a chemical compound containing the **carbonyl group** ($>C{=}O$).

carbonyl group – a carbon-oxygen double bonded group $>C{=}O$.

carboxylate – a salt or an anion of carboxylic acid (COOH). In general it is $RCOO^-$, where R is hydrogen or an **alkyl group**.

carboxyl group – the functional group of the **carboxylic acids** represented as –COOH.

carboxylic acids – organic acids containing the functional group –COOH. They can be either aliphatic (RCOOH) or aromatic (ArCOOH), where R represents an **alkyl group** ($–C_nH_{2n+1}$) and Ar stands for an aromatic ring. The carboxylic acids with even numbers of carbon atoms, n, ranging from 4 to about 20 are called fatty acids (e.g. $n = 10$, 12, 14, 16 and 18 are called capric acid, lauric acid, myristic acid, palmitic acid, and stearic acid, respectively).

Car–Parrinello algorithm – an efficient method to perform **molecular dynamics simulation** for covalent crystals by first-principles quantum mechanical calculations where the forces on the ions are calculated directly from the total energy of the ionic and electronic systems without needing a parameterized interatomic few-body potential. For the electronic contribution to the total energy, one actually solves the **Schrödinger equation** within the **local density approximation** with a **plane-wave** basis set.

The electron density in terms of occupied single-particle orbitals $\Psi_i(r)$ is $n(r) = \Sigma_i|\Psi_i(r)|^2$. The point of the potential energy surface is given by the minimum of the energy functional

$$E[\{\Psi_i\},\{R_I\}\{a_\nu\}] = \Sigma_i \int_\Omega \mathrm{d}^3 r \Psi_i^*(r)[-(\hbar/2m)\nabla^2]\Psi_i r) + U[n(r),\{R_I\}\{a_\nu\}].$$

Here R_I indicate the nuclear coordinates and a_ν are all possible external constraints imposed on the system like the volume Ω, the strain $\varepsilon_{\mu\nu}$, etc. The functional U contains the internuclear Coulomb repulsion and the effective electronic potential energy, including external nuclear, Hartree, exchange and correlation contributions.

Minimization of the energy functional $E[\Psi_i, R_I a_\nu]$ with respect to the orbitals $\Psi_i(r)$, subjected to the orthogonal constraint, leads to the self-consistent equations of the form:

$$\left[-\frac{\hbar^2}{2m}\nabla^2 + \frac{\delta U}{\delta n(r)}\right]\Psi_i(r) = \varepsilon_i \Psi_i(r).$$

Solution of the equations involves repeated matrix diagonalization with a computational effort rapidly growing with the size of the system.

First described in: R. Car, M. Parrinello, *Unified approach for molecular-dynamics and density-functional theory*, Phys. Rev. Lett. **55**(22), 2471–2474 (1985).

Cartesian axis – a set of mutually perpendicular lines which all pass through a single point. They are used to define a Cartesian coordinate system.

Casimir–du Pré theory describes spin lattice relaxation treating the lattice and spin system as distinct thermodynamic systems in thermal contact with one another.

First described in: H. B. G. Casimir, F. K. du Pré, *Note on the thermodynamic interpretation of paramagnetic relaxation phenomena*, Physica **5**(6), 507–511 (1938).

Casimir effect – attraction of two mirror plates facing each other in a vacuum due to fluctuations of surrounding electromagnetic fields exerting radiation pressure on the mirrors. The vacuum fluctuations were theoretically shown to result in the external pressure being, on average, greater than the internal pressure. as it is illustrated in Figure C.4.



Figure C.4 Vacuum fluctuations in the Casimir effect.

The mirror plates are mutually attracted to each other by what is termed the **Casimir force**. This force has been calculated to be $F_C = \frac{\pi^2 \hbar c}{240} S/d^4$, where S is the cross sectional area of the two mirrors and d is the distance between the mirrors. At separation of 10 nm, the Casimir effect produces the equivalent of about 1 atmosphere of pressure. The Casimir force attracting a sphere of radius r to a plane mirror surface is $F_C = \frac{\pi^3 \hbar c}{360} r/d^3$, where d is the separation between the sphere and the mirror.

The Casimir effect can influence the operation of microelectromechanical **(MEMS)** and nanoelectromechanical systems **(NEMS)**.

First described: H. B. G. Casimir, *On the attraction between two perfectly conducting plates,* Proc. K. Ned. Akad. Wet. **51**(7), 793–796 (1948) – theoretical prediction; M. J. Sparnaay, *Measurements of attraction forces between flat plates,* Physica **24**(9), 751–764 (1958) – experimental confirmation.

More details in: K. A. Milton, *The Casimir Effect* (World Scientific, Singapore, 2001).

Casimir force → **Casimir effect**.

Casimir operator plays a crucial role in the classification of group representations. The discussion of the commutators of infinitesimal operators that generate infinitesimal transformations led to **Lie algebra**, while the generation of finite transformations formed the global groups, the **Lie groups**. Casimir and van der Waerden proposed the subgroups and subalgebras of the Lie algebras and Lie groups, with Casimir returning to Lie's idea of invariance, thus developing the Casimir operator, which is an operator $\Gamma = \Sigma_{i=1}^{m} e_i^R u^{iR}$ on a representation R of a Lie algebra. This operator commutes with the action of any representation; in other words commutes with all generators of a group.

First described in: H. Casimir, *Über die Konstruktion einer zu den irreduzibelen Darstellungen halbeinfacher gruppengehörigen Differentialgleichung,* Proc. Roy. Acad.

Sci. (Amsterdam) **34**, 844–846 (1931); H. Casimir, B. L. van der Waerden, *Algebraischer Beweis der vollständigen Reduzibilität der Darstellungen halbeinfacher Liescher Gruppen*, Mathematische Annalen **111**(1), 1–12 (1934).

catalyst – a substance that increases the rate of a chemical reaction but which is left unchanged by the reaction. It works by providing an extended convenient surface for the reaction and by lowering the activation energy for the reaction. The reacting particles gather on the catalyst surface and collide more frequently with each other thus increasing the reaction yield.

catenane – a mechanically interlocked molecular architecture consisting of two or more interlocked molecular macrocycles. The families of catenanes are schematically shown in Figure C.5.

The interlocked rings cannot be separated without breaking the covalent bonds of the macrocycles. In the bridged catenanes called **pretzelanes**, the two macrocycles are linked with a spacer. In handcuff-shaped catenanes, two connected rings are threaded through the same ring.

See also en.wikipedia.org/wiki/Catenane.



Figure C.5 Families of catenanes.

cathodoluminescence – light emission excited by electron irradiation of matter.

First described by W. Crookes in the middle of the nineteenth century.

Cauchy principal value of the integral $\int_{-\infty}^{\infty} f(x)\mathrm{d}x$ is $lim_{\rightarrow\infty} \int_{-s}^{s} f(x)\mathrm{d}x$ provided the limit exists. If the function $f(x)$ is bounded on an interval (a, b) except in the neighborhood of a point c, the Cauchy principal value of $\int_{a}^{b} f(x)\mathrm{d}x$ is $lim_{\delta\rightarrow 0}[\int_{a}^{c-\delta} f(x)\mathrm{d}x + \int_{c+\delta}^{b} f(x)\mathrm{d}x]$ provided the limit exists. It is also known as the principal value.

Cauchy relations – a set of six relationships between the compliance constants of a solid which should be satisfied provided the force between atoms in the solid depends only on the distance between them and acts along the lines joining them, and provided that each atom is a center of symmetry in the lattice.

Cauchy sequence – a sequence with the property that the difference between any two terms is arbitrarily small provided they are both sufficiently far out in the sequence. More precisely it is stated: a sequence $\{a_n\}$ such that for every $\epsilon > 0$ there is an integer N with the property that if n and m are both greater than N, then $|a_n - a_m| < \epsilon$.

causality principle asserts that a response of a system follows its cause in time, or that the response at some time depends only on the driving force in the past.

cavitation – a tendency of liquids to form bubbles spontaneously when subjected locally to negative pressure, as they cannot withstand the tension involved.

CCD – an acronym for a **charged-coupled device**.

CCNOT (C^{2}NOT) gate → **quantum logic gate**.

central limit theorem states that the distribution of sample means taken from a large population approaches a **Gaussian distribution**.

Ĉerenkov angle → **Ĉerenkov radiation**.

Ĉerenkov condition → **Ĉerenkov radiation**.

Ĉerenkov radiation – light emitted when relativistic particles pass through non-scintillating matter: a charged particle travelling with a velocity v through a nonconducting medium having an index of refraction $n(f)$ emits electromagnetic radiation at all frequencies f for which the phase velocity c/n is less than v. In principle, a neutral particle having a magnetic moment (e.g. a neutron) will also emit such radiation, although it will be negligibly small because of the smallness of the magnetic moment. The radiation is emitted at one angle, the **Ĉerenkov angle** $\phi = \arccos(c/n\nu)$, with respect to the momentum vector of the particle. The light is 100% linearly polarized with the electric vector coplanar with the particle momentum vector. The emitted power is defined as

$$\frac{\mathrm{d}E}{\mathrm{d}z} = \frac{4\pi^2 e^2}{c^2} \int \left[1 - \left(\frac{c}{n\nu}\right)^2\right] f\,\mathrm{d}f,$$

where the integration is limited to those frequencies for which the **Ĉerenkov condition** $(c/n\nu) < 1$ is fulfilled.

The effect is used in high-energy particle physics, as only charged particles that fulfill the Ĉerenkov condition emit radiation, which then is detected. This is used either to select particles above a certain energy or to discriminate against the heavier particles in a beam of given momentum containing a mixture of particles.

First described in: P. A. Ĉerenkov, *Visible luminescence from pure liquids subjected to radiation*, Dokl. Akad. Nauk SSSR **2**(8), 451–457 (1934); S. I. Vavilov, *On possible origins of blue luminescence from liquids*, Dokl. Akad. Nauk SSSR **2**(8), 457–461 (1934)–experiment, both in Russian; I. E. Tamm, I. M. Frank, *Coherent* *radiation from a fast electron in a medium*, Dokl. Akad. Nauk SSSR **14**(3), 107–112 (1937)–theory, in Russian.

Recognition: in 1958 P. A. Ĉerenkov, I. M. Frank, I. E. Tamm received the Nobel Prize in Physics for the discovery and the interpretation of the Ĉerenkov effect.

See also www.nobel.se/physics/laureates/1958/index.html.

characteristic function – the **Fourier transform** of a probability function.

characteristic temperature T_0 – one of the experimental characteristics of a semiconductor laser indicating dependence of its threshold current density J_{th} on temperature. In a limited temperature range $J_{th} \sim exp(\frac{T}{T_0})$. The characteristic temperature usually takes values in the range of 100–150 K for AlGaAs lasers and 50–80 K for GaInPAs lasers. A higher characteristic temperature corresponds to a lower temperature sensitivity of the threshold current density. It is worthwhile to note that this sensitivity is considerably reduced in lasers based on low-dimensional structures.

Chargaff's rules → **DNA**.

First described in: E. Chargaff, *Chemical specificity of nucleic acids and mechanism of their enzymatic degradation*, Experientia **6**, 201–209 (1950).

charge coupled device (CCD) – an array of integrated metal-oxide-semiconductor capacitors which can accumulate and store charge because of their capacitance. Under the control of an external circuit, each capacitor can transfer its electric charge to one or other of its neighbors. CCDs are used in digital image processing, photometry, and optical spectrometry.

charge density wave – a static modulation of the charge density at atomic sites accommodated by a periodic lattice distortion.

chemical beam epitaxy → **molecular beam epitaxy**.

chemical potential – a thermodynamic variable bearing a relation to the flow of matter (or particles) similar to the relation which temperature bears to the flow of heat. Matter (particles) only flows between regions of different chemical potential and then in the direction of decreasing potential. The chemical potential of the i-th species is $\mu = (\frac{\partial G}{\partial n_i})_{T,p,n_i}\mu = \frac{\partial G}{\partial n_i}|_{T,p,n_i}$, where G is the Gibbs free energy, n_i is the number of modes of the i-th species, T is the absolute temperature, and p is the pressure.

chemical vapor deposition – a thin solid film growth of a material transported from the gas phase onto a suitable solid substrate. The gaseous medium actually contains vapors of the depositing material or a mixture of gaseous reactants capable of undergoing chemical conversion at the substrate surface to produce the film growth. The deposition is performed in open flow chambers, where a carrier gas containing the reactive species of the precursors is forced to flow past heated substrates. Chemical composition of the precursors, gas pressure in the reaction chamber and substrate temperature are the most important factors controlling the process to yield monocrystalline (epitaxial), polycrystalline or amorphous films.

chemiluminescence – light generation by electronically excited products of chemical reactions. Such reactions are relatively uncommon as most exothermic chemical processes release energy as heat. The initial step is termed chemiexcitation. Chemical energy is converted into electronic excitation energy. If the excited state species is fluorescent, the process is **direct chemiluminescence**. If the initial excited state species transfer energy to a molecule, which then emits light, the process is **indirect chemiluminescence**.

First described by: E. Wiedemann *Über Fluorescenz und Phosphorescenz*, Ann. Phys. **34**, 446 (1888).

chemisorption – an **adsorption** process characterized by strong chemical bond formation between adsorbed atoms and substrate atoms at the adsorbing surface.

Child–Langmuir law relates the density of the current which can be produced under space charge limited conditions between infinite parallel electrodes to the potential applied between the electrodes. The flow of charged particles is said to be space charge limited if the current density given off by an emitter is not limited by any property of the emitter but rather by the fact that the charge in the space near the emitter reduces the electric field at the emitter to zero. Finally, the current density is proportional to $V^{3/2}$, where V is the potential of the collector respect to the emitter.

First described in: C. D. Child, *Discharge from hot CaO*, Phys. Rev. (Series I) **32**(5), 492–511 (1911); I. Langmuir, *The effect of space charge and residual gases on thermionic currents in high vacuum*, Phys. Rev. **2**(6), 450–486 (1913).

chiral → **chirality**.

chirality – Greek meaning ‘‘handedness’’. It is an indication of a structure asymmetry. The word was first introduced by Lord Kelvin in a *Baltimore Lecture* in 1884 ‘‘I call any geometrical figure, or group of points, **chiral**, and say that it has **chirality** if its image in a plane mirror, ideally realized, cannot be brought to coincide with itself’’. Thus an object or a system is called chiral if it differs from its mirror image, and its mirror image cannot superimpose on the original object. A chiral object and its mirror image are called **enantiomorphs** (Greek ‘‘opposite forms’’) or, when referring to molecules, **enantiomers**. A non-chiral object is called **achiral** (sometimes also **amphichiral**). It can be superimposed on its mirror image. Recently a new definition of **chirality** has been proposed by L. D. Barron ‘‘True chirality is shown by systems existing in two enantiomeric states that are interconverted by space inversion but not by time reversal combined with any proper spatial rotation''. This definition includes motion; the system breaks parity P but not time reversal T.

First described in: L. Pasteur, *Recherches sur les relations qui peuvent exister entre la forme crystalline et la composition chimique, et le sens de la polarisation rotatoire*, Ann. Chim. Phys. **24**, 442–459 (1848).

More details in: L. D. Barron *Fundamental symmetry aspects of molecular chirality*, in *New Developments in Molecular Chirality*, ed. by P. G. Mezey (Elsevier, Dordrecht, 1991).

chromatin – the complex of **DNA** and **protein** making up **chromosomes**. The functions of chromatin are to package DNA into a smaller volume to fit in the cell, to strengthen the DNA to allow mitosis and meosis, and to serve as a tool to control expression.

First described by: W. Flemming, *Beiträge zur Kenntnis der Zelle und ihre Lebenserscheinungen*, Arch. Mikr. Anat., **18**, 151–259 (1880).

More details in: A. Wolffe, *Chromatin: Structure and Function* (Academic Press, London, 1998).

chromatography – a technique used to analyze material compositions including separation of the components in the mixture and quantitative measurement of the amount of each component. The mostly employed types of chromatography are:

- gas chromatography (to analyze gases or those liquids and solids, which can be heated to a volatile state without decomposition)
- liquid chromatography (to analyze liquids and solutions of solids when such materials cannot be analyzed by gas chromatography because of their thermal instability)
- ion chromatography (to analyze qualitatively and quantitatively ionic species in complex liquid and solid mixtures)
- gel permeation chromatography (to determine molecular weights and molecular weight distributions of polymer materials by separation of the molecules by size).

First described in: M. S. Tswett, *Adsorptionanalyse und chromatographische Methode–Anwendung auf die Chemie des Chlorophills*, Ber. Dtsch. Bot. Ges. **24**, 316–332 (1906); M. S. Tswett, *Physikalisch-chemische Studien über das Chlorophill. Die Adsorptionen*, Ber. Dtsch. Bot. Ges. **24**, 384–393 (1906).

More details in: V. G. Berezkin, Ed., *Chromatographic adsorption analysis: selected works of M. S. Twett* (Ellis Horwood, New York, 1990).

chromic wheel → **molecular nanomagnet**.

chromosome – a single **DNA** molecule that is the self-replicating genetic structure within the cell which carries the linear nucleotide sequence of genes. In humans (or **eukaryotes)**, the DNA is supercoiled, compacted, complexed with accessory proteins, and organized into a number of such structures. Normal human cells contain 46 chromosomes (except the germ cells, egg and sperm): 22 homologous pairs of autosomes and the sex-determining X and Y chromosomes (XX for females and XY for males). **Prokaryote**s carry their entire genome on one circular chromosome of DNA.

Term coined by: W. Waldeyer, *Zur Spermatogenese bei den Saugethieren*, Arch. Mikr. Anat. **32**, 1 (1888).

CIP geometry → **giant magnetoresistance effect**.

circularly polarized light → **polarization of light**.

cis–trans isomers → **isomers**.

cladding layers → **double heterostructure laser**.

Clark rule – a modification of the **Morse rule** relating the equilibrium internuclear distance in a diatomic molecule r and the equilibrium vibrational frequency ω in the form $\omega r^3(n)^{1/2} = k - k'$, where n is the group number assigned according to the number of shared electrons, k is a constant characteristic of the period, and k' is a correction for singly ionized molecules of that period (zero for neutral molecules).

First described in: C. H. D. Clark, *The relation between vibration frequency and nuclear separation for some simple non-hydride diatomic molecules*, Phil. Mag. **18**(119), 459–470 (1934); C. H. D. Clark, *The application of a modified Morse formula to simple hydride diatomic molecules*, Phil. Mag. **19**(126), 476–485 (1935).

clathrate = **clathrate compound**.

clathrate compound – a chemical substance consisting of a lattice of one type of molecule trapping and containing a second type of molecule. It is formed by inclusion of molecules in cavities existing in crystal lattices or present in large molecules. The constituents are bound in definite ratios, but these are not necessarily integral. The components are not held together by primary valence forces, but instead are the consequence of a tight fit which prevents the smaller partner, the guest, from escaping from the cavity of the host. Consequently, the geometry of the molecules is the decisive factor. A clathrate compound is a weak composite because the captured molecules occupy the space which are left by the other compound.

Inclusion compounds can be subdivided into (1) lattice inclusion compounds (inclusion within a lattice which, as such, is built up from smaller single molecules);

(2) molecular inclusion compounds (inclusion into larger ring molecules with holes); and (3) inclusion compounds of macromolecules.

First described in: P. Pfeiffer, *Organische Molekülverbindungen*, (Ferdinand Enke, Stuttgart, 1927).

Clausius–Mossotti equation connects total polarization of dielectric particles P with dielectric constant ϵ and molecular volume $\nu(= mol.wt./density)$ as $P = (\epsilon - 1)/(\epsilon + 2)\nu$. It supposes that particles of a dielectric under the inductive action of an electric field behave as a series of small insulated conductors and can be polarized as a whole.

First described by: O. F. Mossotti, *Memorie di Matematica e di Fisica della Societá Italiana delle Scienze Residente in Modena*, **24**(Part 2) 49–74 (1850); R. Clausius, *Die mechanische Behandlung der Electricität*, (Vieweg, Braunschweig 1858) p. 62.

clay–polymer nanocomposite – a **polymer** nanocomposite representing a new class of material alternative to conventional filled polymers. In this new class of material, nanosized inorganic fillers (at least one dimension) are dispersed in polymer matrix offering improvement in performance properties of the polymer. These hybrid compositions exhibit large increases in tensile strength, modulus, and heat distortion temperature as compared with the pristine polymer. The composites also have lower water sensitivity, reduced permeability to gases, and a similar thermal coefficient of expansion. All of these property improvements can be realized without a loss of clarity in the polymer. Typically smectite-type clays are used as fillers.

First described in: A. Usuki, M. Kawasumi, Y. Koyima, A. Okada, T. Karauchi, O. Kamigaito, *Swelling behavior of montmorillonite cation exchanged for* ω*-amino acids by* ϵ*-caprolactam*, J. Mater. Res. **8**(5), 1174–1178 (1993), *Synthesis of nylon 6-clay hybrid*, J. Mater. Res. **8**(5), 1179–1184 (1993).

More details in: Polymer-Clay Nanocomposites, edited by T. J. Pinnavaia, G. W. Beall (John Wiley & Sons, Chichester 2000).

Clebsch–Gordan coefficients – the elements of the unitary matrix $\langle m_1 m_2 | jm\rangle$, which are in fact the coefficients of the expansion of the eigenstates $|jm\rangle$ in terms of the eigenstates $|m_1 m_2\rangle$, in accordance with the formula $|jm\rangle = |m_1 m_2\rangle\langle m_1 m_2 | jm\rangle$. These coefficients are called Clebsch-Gordan coefficients. Sometime also termed Clebsch–Gordon, **Wigner**, vector addition or vector coupling **coefficients**. There are many symbols employed in the literature to denote the Clebsch–Gordan coefficients, for which it is possible to obtain explicit formula. The Clebsch–Gordan coefficients play a principal role in the general problem of the combination of angular momenta in quantum mechanics.

First described in: R. F. A. Clebsch, P. A. Gordan, *Theorie der Abelsche Funktionen* (Teubner, Leipzig, 1866).

More details in: A. Messiah, *Clebsch-Gordon Coefficients and 3j Symbols, Appendix C I.*, in: Quantum Mechanics (North Holland, Amsterdam, 1962); L. Cohen, *Tables of the Clebsch-Gordan Coefficients* (North American Rockwell Science Center, Thousand Oaks, California, 1974).

close packed crystal – a crystal with atoms arranged so that the volume of the interstitials between the spheres corresponding to the atoms is minimal.

clusters (atomic) – large ''molecules'' containing typically from 10 to 2000 atoms. They have specific properties (mainly due to their large surface-to-volume ratio), which are size dependent and different from both the atoms and the bulk material.

CMOS – an acronym for a **c**omplementary **m**etal **o**xide **s**emiconductor device. Such a device, typically being an **integrated circuit**, is a combination of p-channel metal oxide semiconductor transistors and n-channel metal oxide semiconductor transistors. It was initiated by technical investigations in the 1940s and started as an industry in the late 1960s. CMOS circuitry dominates the current semiconductor market because of the astonishing power of silicon electronic integration technology. CMOS technology has distinguished itself by the rapid improvements in its products, in a four-decade history, most of the figures of merit of the silicon industry have been marked by exponential growth → **Moore's law**, principally as a result of the ability to exponentially decrease the minimum feature sizes of integrated circuits.

More details in: http://www.sematech.org/public/roadmap/.

CNDO – an acronym for **c**omplete **n**eglect of **d**ifferential **o**verlap → **approximate self-consistent molecular orbital methods**.

CNOT gate → **quantum logic gate**.

coenzyme – a non**protein** portion of an **enzyme** that supports the catalytic process. Coenzymes are often vitamins or metal ions.

confocal fluorescence microscopy → **fluorescence nanoscopy**.

More details in: T. Wilson, C. J. R. Sheppard, *Theory and Practice of Scanning Optical Microscopy* (Academic Press, New York, 1984).

coherence – a quality that expresses the correlation between two stochastic processes or states.

coherent potential approximation is used for calculation of fundamental electronic properties of disordered alloys. It introduces the concept of coherent atom corresponding to an average of disorderly arranged atoms of various species constituting a given alloy. We solve the impurity problem, in which an atom of a given species substitutes a coherent atom in the lattice of the pure crystal of coherent atoms.

The potential of electrons related to the impurity atom can be determined self-consistently in the **local density approximation** if the potential of the coherent atom is known. The latter potential is called the coherent potential. It is determined self-consistently by making use of the potentials of component atoms, which in turn have been determined in terms of the coherent potential by solving the above-mentioned impurity problem.

First described in: P. Soven, *Coherent-potential model of substitutional disordered alloys*, Phys. Rev. **156**(3), 809–813 (1967).

cohesion – a property exhibited by condensed matter: work must be done in order to separate matter into its constituents (free atoms or molecules), which are normally held together by attractive forces. These forces are particularly strong in solids. The work required to dissociate one mole of the substance into its free constituents is called its **cohesive energy**.

collimated light – a beam of light whose rays are parallel and thus has a plane wavefront. A collimated light is usually generated by **laser**s. It has a low beam divergence, so that the beam radius does not undergo significant changes within moderate propagation distances.

collision radiation → **Bremsstrahlung**.

colloid – a substance consisting of a continuous medium and small (**colloidal**) particles dispersed therein.

First described in: M. Faraday, *The Bakerian lecture: experimental relations of gold (and other metals) to light*, Phil. Trans. R. Soc. **147**, 145–181 (1857).

colloidal crystal – a self organized periodic, like in a crystal, arrangement of **colloidal particles**.

More details in: P. Pieranski, *Colloidal crystals*, Contemp. Phys. **24**(1), 25–73 (1983).

colloidal particles – particles smaller than coarse, filterable particles but larger than atoms and small molecules. They may sometimes be large molecules composed of thousands of atoms. There are no generally accepted size limits for colloidal particles, but the upper limit is approximately 200–500 nm, while the smallest particles are measured to be 0.5–2 nm.

colored noise – a noise characterized by a second order correlation function, which is broader than a delta function.

commutator – a notation for operators $\mathbf{A}$ and $\mathbf{B}$, $[\mathbf{A},\mathbf{B}] = \mathbf{AB} - \mathbf{BA}$. The order of operators is important. They cannot be reordered like numbers. Two operators are said to commute if their commutator is zero. It is possible to measure two physical quantities simultaneously to arbitrary accuracy only if their operators commute.

complementarity – the term used by N. Bohr to describe the fact that in a given experimental arrangement one can measure either the particle aspects or the wave aspects of an electron, or other quantum particle, but not both simultaneously.

First described in: N. Bohr, *Can quantum-mechanical description of physical reality be considered complete?*, Phys. Rev. **48**(8), 696–702 (1935).

complete neglect of differential overlap (CNDO) → **approximate self-consistent molecular orbital methods**.

compliance constants → **elastic moduli of crystals**.

compliance matrix → **Hooke's law**.

Compton effect – electromagnetic radiation scattered by an electron in matter increasing its wavelength so that it becomes

$$\lambda_\theta = \lambda_0 \left[1 + \frac{2h}{mc\lambda_0} \sin^2(\theta/2) \right],$$

where λ_0 is the wavelength of the incident radiation, m is the mass of the electron, and θ is the scattering angle. It is indeed pronounced in the case of X-rays and gamma radiation. The radiation is scattered in some definite direction. The increase of the wavelength ($\Delta\lambda = \lambda_\theta - \lambda_0$) depends only on the angle of scattering θ. The term h/mc is called the **Compton wavelength**.

First described in: A. H. Compton, *A quantum theory of the scattering of X rays by light experiments*, Phys. Rev. **21**(5), 483–502 (1923).

Recognition: in 1927 A. H. Compton received the Nobel Prize in Physics for the discovery of the effect named after him.

See also www.nobel.se/physics/laureates/1927/index.html.

Compton scattering – elastic scattering of photons by electrons.

Compton wavelength → **Compton effect**.

conductance – the real part of the **admittance** of an electric circuit. When the circuit **impedance** contains no reactance, as in a direct current circuit, it is the reciprocal of **resistance**. Conductance is a measure of the ability of the circuit to conduct electricity.

conductivity – the ratio of the electric current density to the electric field in a material.

conduction band – a set of one-electron states most commonly available for conduction of electric current by electrons in solids.

conductor – a substance through which electric currents flow easily. It has resistivity in the range $10^{-6} - 10^{-4}$ Ω cm. A solid is a conductor if there is no energy gap between its **conduction band** and **valence band** and the conduction band is filled with electrons.

constitutive relations → **Hooke's law**.

confinement factor → **optical confinement factor**.

continuity equation – an equation which relates the rate of inflow of a quantity to the rate of increase of the amount of that quantity within a given system. It can be written in the most general form for a particle density N as $\frac{\mathrm{d}N}{\mathrm{d}t} = injection(and/or + production) - absorption - leakage$. Conservation of the particles in three dimensions gives $div\mathbf{J} + \frac{\partial N}{\partial t} = 0$, where J is the particle density vector. In the one dimensional case it transforms to $\frac{\partial J}{\partial x} + \frac{\partial N}{\partial t} = 0$.

controlled rotation gate (CROT gate) – a logical gate in which the state of one **bit** (the control bit) controls the state of another bit (the target bit). The target bit is rotated through π (that is from state 0 to 1 or vice versa) if and only if the control bit is 1. The transformation matrix of the simplest gate is:

$$\begin{pmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & -1 \\ 0 & 0 & 1 & 0 \end{pmatrix}.$$

The CROT gate is equivalent to the standard controlled NOT gate despite the difference in the minus sign placement in their matrix representation.

Cooley–Tukey algorithm – the efficient algorithm for calculations of the discrete Fourier transform → **fast Fourier transform**. It provides these calculations using only $n\log n$ arithmetic operations instead of n^2 operations.

Formally, the discrete **Fourier transform** is a linear transformation mapping any complex vector f of length n to its Fourier transform F. The k-th component of F is $F(k) = \sum_{j=0}^{n-1} f(j)\exp(2\pi ijk/n)$ and the inverse Fourier transform is $f(j) = \frac{1}{n}\sum_{k=0}^{n-1} F(k)\exp(2\pi ijk/n)$. Cooley and Tukey showed how the Fourier transform on the cyclic group $\mathbf{Z}/n\mathbf{Z}$, where $n = pq$ is composite, can be written in terms of Fourier transforms on the subgroup $q\mathbf{Z}/n\mathbf{Z}$ or $\mathbf{Z}/p\mathbf{Z}$. The trick is to change variables so that the one-dimensional formula giving the discrete Fourier tranform is turned into a two-dimensional formula which can be computed in two stages.

Cooley–Tukey algorithm

Define variables j_1, j_2, k_1, k_2 through the equations:

$$j = j(j_1, j_2) = j_{1q} + j_2$$

$$0 \leq j_1 < p, 0 \leq j_2 < q$$

$$k = k(k_1, k_2) = k_2 p + k_1$$

$$0 \leq k_1 < p, 0 \leq k_2 < q.$$

Then the Fourier transform can be rewritten as:

$$F(k_1, k_2) \sum_{j_2=0}^{q-1} \exp([2\pi i j_2 (k_2 p + k_1)]/n) \sum_{j_1=0}^{p-1} \exp[2\pi i j_1 (k_1/p)] f(j_1, j_2).$$

Now one can compute F at two stages:
1. For each k_1 and j_2 compute the inner form

$$F_F(k_1, j_2) = \sum_{j_1=0}^{p-1} \exp[2\pi i j_1 (k_1/p)] f(j_1, j_2).$$

This requires at most $p^2 q$ scalar operations.
2. For each k_1 and k_2 compute the outer sum

$$F(k_1, k_2) = \sum_{j_2=0}^{q-1} \exp([2\pi i j_2 (k_2 p + k_1)]/n) F_F(k_1, j_2).$$

This requires an additional $q^2 p$ operations. Thus, instead of $(pq)^2$ operations, the above algorithm uses $(pq)(p+q)$ operations. If n could be factored further, the same trick could be further applied obtaining the transform through only $n \log n$ operations.

The algorithm had a revolutionary effect on many digital and image processing methods and it is still the most widely used method for computing Fourier transforms. It is interesting to note that the idea started from the necessity to develop a method for detecting Soviet Union nuclear tests without visiting the nuclear facilities. One idea was to analyze a large number of seismological time series obtained from off-shore seismometers, which requires fast algorithms for computing discrete Fourier transforms. The algorithm was not patented, and the impressive rapid growth of its applications is testimony to the advantages of open developments.

First described in: J. W. Cooley and J. W. Tukey, *An algorithm for machine calculation of complex Fourier series,* Mathematics of Computations, **19**(2), 297–301 (1965).

Cooper pair – a pair formed by two electrons with differently oriented spins (up and down). As a result the pair has zero spin and energy distribution of such particles follows **Bose-Einstein statistics**. Cooper pairs are used in the explanation of superconductivity.

First described in: L. N. Cooper, *Bound electron pairs in a degenerate Fermi gas*, Phys. Rev. **104**(4), 1189–1190 (1956).

Recognition: in 1972 J. Bardeen, L. N. Cooper and J. R. Schrieffer received the Nobel Prize in Physics for their jointly developed theory of superconductivity, usually called the BCS theory.

See also www.nobel.se/physics/laureates/1972/index.html.

coordination number – the number of nearest neighbors of a certain atom. The polyhedron formed when the nearest neighbors are connected by lines is called its coordination polyhedron.

Corbino disc – a flat doughnut shaped sample (see Figure C.6) that has concentric contacts to the inner and outer cylindrical surfaces.

First described in: O. M. Corbino, *Elektromagnetische Effekte die von der Verzerrung herrühren*, Phys. Z. **12**, 842–845 (1911).



Figure C.6 Corbino disc.

Corbino effect – production of a circumferential electric current in a circular disk by the action of an external axial magnetic field upon a radial current in the disk.

First described in: O. M. Corbino, *Elektromagnetische Effekte die von der Verzerrung herrühren*, Phys. Z. **12**, 842–845 (1911).

Coriolis force – an inertial force arising when an object moves in a rotating coordinate system. As a result, the path of the object appears to deviate. In a moving coordinate system, this deviation makes it look as if a force is acting upon the object, but actually there is no real force acting on the object. The effect is due to rotation (associated with an acceleration) of the coordinate system itself. In a rotating frame of reference (such as the earth), the apparent force is $\mathbf{F} = 2m(\mathbf{v} \times \mathbf{\Omega})$, where m is the mass and $\mathbf{v}$ is the linear velocity of the object, $\mathbf{\Omega}$ is the angular velocity of the coordinate system.

First described in: G. Coriolis, *Mémoire sur l'influence du moment d'inertie du balancier d'une machine a vapeur et de sa vitesse moyenne sur la régularité du mouvement de rotation du va-et-vient du piston communiqué au volant*, J. Ecole Polytechn. **13**, 228–267 (1832).

correlation – the interdependence or association between two variables that are quantitative or qualitative in nature.

correspondence principle → **Bohr correspondence principle**.

Cottrell atmosphere – a cluster of impurity atoms surrounding a dislocation in a crystal.

First described in: A. H. Cottrell, B. A. Bilby, *Dislocation theory of yielding and strain ageing iron*, Proc. Phys. Soc. Lond. A **62**, 49 (1948).

co-tunneling – a tunneling process through an intermediate virtual state. It becomes relevant when sequential **single-electron tunneling** through quantum dots is suppressed by **Coulomb blockade**. The virtual states originate from quantum fluctuations of the number of electrons there. Co-tunneling is a process of high order tunneling in which only the energy from the initial to the final (after the tunneling events) state needs to be conserved. Elastic and inelastic co-tunneling are distinguished.

In **elastic co-tunneling** an electron tunnels into the dot and out of the dot through the same intermediate energy state of the dot. For a dot placed between two leads the corresponding current is

$$I = \frac{h\sigma_1\sigma_2\Delta}{8\pi^2 e^2}\left(\frac{1}{E_1} + \frac{1}{E_2}\right)V.$$

Here σ_1 and σ_2 are the barrier conductances in the absence of the tunneling processes, Δ is the energy gap between the states in the dot, and E_1 is the charging energy related to coming of one electron into the dot, and E_2 is the charging energy related to one electron leaving the dot. The current varies linearly with the applied voltage V. At low temperatures it is temperature independent.

In **inelastic co-tunneling**, an electron that tunnels from one lead into a state in the dot is followed by an electron that tunnels from a different state of the dot into another lead. In this case the current is

$$I = \frac{h\sigma_1\sigma_2}{6e^2}\left(\frac{1}{E_1} + \frac{1}{E_2}\right)^2 \left[(k_B T)^2 + \left(\frac{eV^2}{2\pi}\right)\right] V.$$

It is obvious that the current is temperature dependent and proportional to V^3. In a multidot system with N junctions $I \sim V^{2N-1}$.

The co-tunneling processes yield the current below the threshold voltage controlled by the Coulomb blockade. This limits the accuracy of the **single-electron turnstile** even under the most favorable conditions.

First described in: D. V. Averin, A. A. Odintsov, *Macroscopic quantum tunneling of the electric charge in small tunnel junctions*, Phys. Lett. A **140**, 251–257 (1989) – predicted; L. J. Geerligs, D. V. Averin, J. E. Mooij, *Observation of macroscopic quantum tunneling through the Coulomb energy barrier*, Phys. Rev. Lett. **65**(24), 3037–3040 (1990) – experimentally observed.

Coulomb blockade – an interdiction of an electron transfer into a region where it results in a change of the electrostatic energy greater than the thermal energy k_BT. Note that if the region is characterized by the capacitance C, its electrostatic energy is increased by $e^2/2C$ with an arrival of one electron. In macroscopic structures, this change in the energy is hardly noticeable, while in **nanostructures**, particularly in quantum dots, the condition $e^2/2C > k_BT$, is easily realized. The change in the electrostatic energy due to transfer of a single electron results in a gap of $e^2/2C$ in the energy spectrum at the **Fermi level** referred to as a **Coulomb gap**. Injection of an electron in a Coulomb blockade regime is inhibited until this energy gap is overcome through an applied bias. The phenomenon clearly manifests itself in **single-electron tunneling**.

First described in: C. J. Gorter, *A possible explanation of the increase of the electrical resistance of thin metal films at low temperatures and small field strengths*, Physica **17**(8), 777–780 (1951) – idea; I. Giaever, H. R. Zeller, *Superconductivity of small tin particles measured by tunneling*, Phys. Rev. Lett. **20**(26), 1504–1507 (1968) – experiment; I. O. Kulik, R. I. Shekhter, *Kinetic phenomena and charge discreteness effects in granulated media*, Zh. Exp. Teor. Fiz. **68**(2), 623–640 (1975) – in Russian, theory.

Recognition: in 1973 I. Giaever received the Nobel Prize in Physics for his experimental discoveries regarding tunneling phenomena in superconductors.

See also www.nobel.se/physics/laureates/1973/index.html.

Coulomb gap → **Coulomb blockade**.

Coulomb force → **Coulomb law (electricity)**.

Coulomb gauge – the gauge defined by the equation $\nabla \cdot \mathbf{A} = 0$, where $\mathbf{A}$ is the vector potential of the magnetic field.

Coulomb law (mechanics) states that frictional force between two bodies is independent of the velocity of their movement with respect each other → **Amontons' law**.

First described in: C. A. Coulomb, *Théorie des machines simples, en ayant égard au frottement de leurs parties, et la roideur des cordages*, Mem. Math. Phys., 161–342 Paris (1785).

Coulomb law (electricity) states that the electrostatic force of attraction or repulsion exerted by one particle with a charge q_1 on another with a charge q_2, also called the **Coulomb force**, is defined as $F = q_1q_2/r^2$, where r is the distance between the particles.

First observed by: H. Cavendish in 1773 but not published;

First described by: C. A. Coulomb, *Premier Mémoire sur l'électricité et le magnétisme*, Mem. Acad. Roy. Sci., 569–577 (1785).

Coulomb oscillations → **single-electron transistor**.

Coulomb potential – the potential describing the interaction of two charged particles in the form: $V(r) = \frac{q_1 q_2}{\varepsilon_0 \varepsilon r}$, where q_1 and q_2 are the charges of the interacting particles, ε is the relative permittivity, and r is the distance between the particles.

Coulomb scattering – scattering of charged particles by an atomic nucleus under the influence of the Coulomb forces exerted by the nucleus as a whole, that is the internal nuclear force field is neglected. This means that the charged particles which undergoes scattering does not approach the nucleus sufficiently closely for the nuclear forces acting between the protons and neutrons to have any external effect.

Coulomb staircase – a stair-like relation between electrical parameters of a system in which electronic transport is controlled by the **Coulomb blockade**. The charge accumulated in a **single-electron box** as a function of the gate–voltage and current–voltage characteristics of double barrier single-electron structures are typical examples.

covalent bond – an interatomic bond in which each atom of a bound pair contributes one electron to form a pair of electrons.

First described in: I. Langmuir, *Isomorphism, isosterism and covalence,* J. Am. Chem. Soc. **41**(10), 1543–1559 (1919).

Recognition: in 1932 I. Langmuir received the Nobel Prize in Chemistry for his discoveries and investigations in surface chemistry.

See also www.nobel.se/chemistry/laureates/1932/index.html.

CPHASE gate → **quantum logic gate**.

CPP geometry → **giant magnetoresistance effect**.

Cr-based molecular ring → **molecular nanomagnet**.

CROT gate → **controlled rotation gate**.

crown ethers – heterocyclic chemical compounds that, in their simplest form, are cyclic oligomers of ethylene oxide. Some examples are illustrated in Figure C.7.



Figure C.7 Crown ethers with 4, 5 and 6 repetitions of the ethyleneoxy groups.

The essential repeating unit of any simple crown ether is ethyleneoxy, i.e., $–CH_2CH_2O–$, which repeats twice in dioxane and six times in 18-crown-6. The nine-membered ring 1,4,7-trioxonane (9-crown-3) is often called a crown and can interact with cations. Macrocycles of the $(–CH_2CH_2O–)_n$ type in which $n \geq 4$ are generally referred to as crown ethers rather than by their systematic names. This is because the molecules formed when this special group of heterocycles binds to cations resemble a crown sitting on a head in structure.

The crown ethers are notable for their ability to strongly solvate cations. In other words, the equilibrium is strongly toward the complex. The oxygen atoms are ideally located to coordinate with a cation in the interior of the ring, whereas the exterior of the ring is **hydrophobic**. The result is that the complexed cation is soluble in nonpolar solvents. The size of the interior of the crown ether determines the size of the cation that it can solvate. Therefore, 18-crown-6 has a high affinity for potassium cation, 15-crown-5 for sodium cation and 12-crown-4 for lithium cation.

First described in: C. J. Pedersen, *Cyclic polyethers and their complexes with metal salts*, J. Am. Chem. Soc. **89**(26), 7017–7036 (1967).

Recognition: in 1987 C. J. Pedersen shared with D. J. Cram and J. M. Lehn the Nobel Prize in Chemistry for their development and use of molecules with structure-specific interactions of high selectivity.

See also www.nobel.se/chemistry/laureates/1987/index.html.

cryogenics – production and maintenance of very low temperatures, within a few degrees of absolute zero, and the study of phenomena at these temperatures.

crystal – a three-dimensional body consisting of periodic arrays of ions, atoms or molecules.

crystal point group → **point group**.

cubic lattice – a **Bravais lattice** whose unit cell is formed by perpendicular axes of equal length.

cucurbituril – a cyclic organic macrocyclic compound consisting typically of six units of glycoluril, while the molecules composed of 5, 7, 8, and 10 repeat units have been identified. Its cyclic unit is shown in Figure C.8.

This compound is of fundamental and applied interest because its molecule has roughly the shape of a hollow nanotube. The cavity of cucurbit [6] uril is characterized by the height of approximately 91 nm, the outer diameter is 58 nm and the inner diameter is 39 nm.

First described in: R. Behrend, E. Meyer, F. Rusche, *Über Condensationsprodukte aus Glycoluril und Formaldehyd*, Justus Liebigs Ann. Chem. **339**, 1–37 (1905).



Figure C.8 A cyclic unit of cucurbituril–glycoluril.

Curie law governs the variation of magnetic susceptibility with temperature of a paramagnetic material with negligible interaction between the magnetic carriers. It has the form $M = C/T$, where M is the molar susceptibility and C is the Curie constant.

First described in: P. Curie, *Propriétés magnétiques des corps à diverses températures*, Annales de Chimie et de Physique, 7 série, **1**(V), 289–331 (1985).

Curie point (temperature) – the temperature above which particular magnetic properties of the substance disappear. There are three of such points relating to different magnetic materials: i) the ferromagnetic, ii) the paramagnetic, iii) the antiferromagnetic Curie points. The latter is also called the **Néel point (temperature)**.

Curie–Weiss law – the **Curie law** modified to the case when internal interactions play a role. The temperature dependence of the molar susceptibility takes the form $M = C/(T - \Theta)$, where Θ is the **Curie point**.

First described in: P. Weiss, *L'hypothèse du champ moléculaire et la propriété ferromagnétique*, J. Phys. **6**(1), 661–690 (1907).

Curie–Wulff's condition → **Wulff's theorem**.

"current law" → **Kirchhoff laws (for electrical circuits)**.

cyclodextrins – cyclic **oligomer** compounds consisting of six to eight **glucose** units, forming ring-shaped molecules. They are respectively called α- (six-membered ring molecule), β- (seven-membered ring molecule) and γ-cyclodextrin (eight-membered ring molecule).

Topologically, cyclodextrins can be represented as toroids in which primary hydroxyl groups are located "inside" and secondary ones "outside". Because of this arrangement, the interior of the toroids is **hydrophobic** and thus able to host other hydrophobic molecules. They are known to form inclusion complexes with various low-molecular-weight compounds ranging from non-polar **aliphatic** molecules to polar **amines** and acids.

More information in: F. Cramer, *Einschlussverbindungen der Cyclodextrine*, Angew. Chem. **64**, 136 (1952).

cyclopentadienyl complex – a metal complex with one or more **cyclopentadienyl ring**s. One-cyclopentadienyl-ring complexes are shown in Figure C.9.

Based on the type of bonding between the metals and the cyclopentadienyl moieties, three categories of the complexes are distinguished: π-complexes, σ-complexes and ionic complexes. These complexes form **metallocene**s.



Figure C.9 Cyclopentadienyl complexes.

cyclopentadienyl ring – the organic complex of composition $(C_5H_5)^-$, in which C atoms are bound up with each other and arranged in the ring structure as in an aromatic ring. It is abbreviated as Cp^-.

cyclotron effect – any free electron of mass m moving in a plane normal to a magnetic field with induction B executes a circular trajectory in this plane with the characteristic frequency $\omega_c = eB/m$, known as the **cyclotron frequency**. The radius of the orbit, called the **cyclotron radius**, is $r_c = (2mE)^{1/2}/(eB)$, where E is the electron kinetic energy. Note that the period of the cyclotron motion is independent of the electron energy, while the radius of the orbit is dependent on the electron energy.

cyclotron frequency → **cyclotron effect**.

cyclotron radius → **cyclotron effect**.

cyclotron resonance – a resonance absorption of energy from an alternating current electric field by electrons in a uniform magnetic field when the frequency of the electric field equals the cyclotron frequency, or the cyclotron frequency corresponding to the electron's effective mass if the electrons are in a solid.

D

From D'Alembert equation to Dzyaloshinskii–Moriya interaction

d'Alembert equation – a system of simultaneous linear homogeneous differential equations with constant coefficients of the form $\mathrm{d}y_i/\mathrm{d}x = \sum a_{ik}y_k = 0$ ($i = 1, 2, \ldots n$), where $y_i(x)$ are the n functions to be determined and a_{ik} are constants.

First described by: J. d'Alembert in 1747.

d'Alembertian operator is $\partial^2/\partial x^2 + \partial^2/\partial y^2 + \partial^2/\partial z^2 - 1/v^2(\partial^2/\partial t^2)$. It is used in electromagnetic wave theory where the parameter v is the wave velocity in the medium under consideration.

damped wave – a wave whose amplitude drops exponentially with distance because of the energy losses, which are proportional to the square of the amplitude.

Darwin curve – the form of the angular distribution of intensity in the X-ray diffraction pattern from a perfect crystal, as originally calculated by C. G. Darwin.

First described in: C. G. Darwin, *The theory of X-ray diffraction*, Phil. Mag. **27**, 315–333 (1914); C. G. Darwin, *The theory of X-ray diffraction: Part II*, Phil. Mag. **27**, 675–690 (1914).

Davydov splitting – splitting in absorption spectra of molecular crystals due to the interaction between identical molecules having different orientations in the **unit cell** of the crystal.

First described in: A. S. Davydov, *Theory of absorption spectra of molecular systems*, Zh. Exp. Teor. Fiz. **18**(2), 210–218 (1948) – in Russian.

Davisson–Calbick formula gives the focal length for the simplest electrostatic lens composed of a single circular aperture in a conducting plate kept at the potential V and separating two regions of different potentials V_1 and V_2 in the form $f = 4V(V_2 - V_1)$.

First described in: C. J. Davisson, C. J. Calbick, *Electron lenses*, Phys. Rev. **42**(4), 580–580 (1932).

Davisson–Germer experiment – the first demonstration of electron diffraction in which a beam of electrons was directed at the surface of a nickel crystal. The distribution of scattered back electrons was measured with a Faraday cylinder.

First described in: C. J. Davisson, L. H. Germer, *Diffraction of electrons by a crystal of Nickel*, Phys. Rev. **30**, 705–740 (1927).

Recognition: in 1937 C. J Davisson shared with G. P. Thomson the Nobel Prize in Physics for their experimental discovery of diffraction of electrons by crystals.

See also www.nobel.se/physics/laureates/1937/index.html.

de Broglie wavelength appears from de Broglie's statement that any particle, not only photons, with a momentum p should have (in some sense) a wavelength given by the relation $\lambda = h/p$.

First described in: L. de Broglie, *Ondes et quanta*, C. R. Acad. Sci. (Paris) **177**, 507–510 (1923).

Recognition: in 1929 L. de Broglie received the Nobel Prize in Physics for his discovery of the wave nature of electrons.

See also www.nobel.se/physics/laureates/1929/index.html.

Debye effect – selective absorption of electromagnetic waves by a **dielectric** due to molecular dipoles.

First described by: P. Debye in 1933.

Recognition: in 1936 P. Debye received the Nobel Prize in Chemistry for his contributions to our knowledge of molecular structure through his investigations on the dipole moments and on diffraction of X-rays and electrons in gases.

See also www.nobel.se/chemistry/laureates/1936/index.html.

Debye frequency – the characteristic frequency of the lattice vibrations that couple the electrons in the superconducting state.

Debye-Hückel screening – phenomenon in a plasma, where the electric field of a charged particle is shielded by particles having charges of the opposite sign.

First described in: P. Debye, G. Hückel, *Zur Theorie der Elektrolyten. Part II. Law of the limit of electrolytic conduction*, Phys. Z. **24**(10), 305–325 (1923).

Debye–Hückel theory – the theory of the behavior of strong electrolytes according to which each ion is surrounded by an ionic atmosphere of charges of the opposite sign whose behavior retards the movement of ions when an electric current is passed through the medium.

The energy of interaction between the ions and their surrounding ionic atmospheres determine an electrostatic potential energy of the solution, which is assumed to account for the nonideal behavior. The following assumptions are made to calculate this potential energy: i) strong electrolytes are completely dissociated in the concentration range in which the theory is valid, ii) the only forces operative in interionic attraction are the **Coulomb force**s, iii) the dielectric constant of the solution is not essentially different from that of the solvent, iv) the ions can be regarded as point charges, v) the electrostatic potential energy is small compared with the thermal energy.

First described in: P. Debye, E. Hückel, *Zur Theorie der Elektrolyten,* Phys. Zeitschrift **24**(9), 185–206 (1923).

Debye–Hückel screening length – a penetration depth of an impurity charge screened by mobile carriers in semiconductors $L = (e^2 n/\epsilon_0 k_B T)^{-1/2}$, where n is the carrier concentration and T is the temperature. It is valid for lightly doped semiconductors at around room temperatures. The quantity $(L)^{-1}$ is denoted as the **Debye–Hückel screening wave number**.

Debye–Hückel screening wave number → **Debye–Hückel screening length**.

Debye–Jauncey scattering – incoherent background scattering of X-rays from a crystal in directions between those of **Bragg reflections**.

First described in: G. E. M. Jauncey, *Theory of diffuse scattering of X-rays by solids,* Phys. Rev. **37**(10), 1193–1202 (1931).

Debye relaxation – relaxation of a charge **polarization** characterized by a single relaxation time t. It is typical for the relaxation of orientation polarization in a material containing only one type of permanent dipoles. The relaxation current is exponentially decreased with time: $I \sim \exp(-t/\tau)$.

Debye screening length = **Debye–Hückel screening length**.

Debye temperature – the characteristic used to describe the slope of the temperature dependence of the heat capacity of matter generally presented as $c_v = f(T/T_\Theta)$. In fact, the Debye temperature T_Θ is dependent on temperature, so the above relation holds linearity in an appropriate power of T/T_Θ in a limited temperature range.

First described in: P. Debye, *Zur Theorie der spezifischen Wärmen,* Ann. Phys. **30**(4), 789–839 (1912).

Debye–Waller factor – a reduction in the intensity of X-rays diffracted at a crystal lattice due to the thermal motion of the atoms in the lattice. It is $D = \exp[-8\pi^2 u^2 \sin^2(\theta/2\lambda^2)]$, where u^2 is the average value of the square of the displacement of the atom perpendicular to the reflecting plane (a function of T), θ is the **Bragg reflection angle**, and λ is the wavelength of the X-rays.

First described in: I. Waller, *Zur Frage der Einwirkung der Wärmebewegung auf die Interferenz von Röntgenstralen,* Z. Phys. **17**(6), 398–408 (1923).

deca- – a decimal prefix representing 10, abbreviated da.

decoherence (quantum) – a transformation of a pure quantum state into a mixed state due to an interaction of the quantum system with surroundings.

deceleration radiation → **Bremsstrahlung**.

deci- – a decimal prefix representing 10^{-1}, abbreviated d.

deformation potential is introduced in order to describe how **phonons** compress and dilate alternating regions of a solid. A uniform compression or dilatation of the crystal causes the edge of each electronic energy band to move up or down proportionally to the strain. The constant of proportionality is called the deformation potential, Ξ.

The potential energy is $V(z) = \Xi e(z)$, where the longitudinal strain is $e(z) = \partial u/\partial z$, and $u(z)$ is the displacement of an atom at z.

degeneracy means the equality of quantities which are independent and thus in general distinct. In quantum mechanics, it is a number of **orbitals** (energy levels) with the same energy or, identically, the conditions when different wave functions correspond to the same energy.

degenerate states – the states of the same energy. In other words, different states with a common **eigenvalue** are said to be degenerate.

de Haas–van Alphen effect – oscillatory variation of magnetic susceptibility of metals as a function of $1/H$, where H is the strength of a static magnetic field. The effect is observed at sufficiently low temperatures, typically below 20 K. It is a consequence of the quantization of the motion of conduction electrons in a magnetic field. Recording field and temperature dependences of the effect, in particular as a function of the field orientation with respect to the crystal axes, provides finding the electron effective mass, electron relaxation time, and **Fermi level** in the material.

First described by: W. J. de Haas, P. M. van Alphen, *Relation of the susceptibility of diamagnetic metals to the field*, Proc. K. Akad. Amsterdam **33**(7), 680–682 (1930).

More details in: D. Schoenberg, *Magnetic Oscillations in Metals*, (Cambridge University Press, Cambridge, 1984).

Delbrück scattering – a scattering of light produced by a Coulomb field, i.e. by virtual electron–positron pairs.

First described in: L. Meitner, H. Kösters, M. Delbrück, *Über die Streuung kurzwelliger γ-Strahlen*, Z. Phys. **84**, 137–144 (1933).

delta-doped structure – a semiconductor structures with extremely inhomogeneous doping profile characterized by location of all impurities in a very thin inner



Figure D.1 Energy bands in a delta-doped semiconductor structure.

layer, ideally within one monolayer. The dopant profile resembles the Dirac **delta function**. Electronic bands in such a structure are shown in Figure D.1.

Carriers in the highly doped region are restricted to move far from the ionized impurity because of strong Coulomb interaction with them. The electric field of the ionized impurity atoms is screened by the free carriers they produce. A V-shaped potential well is formed. It can be approximated by

$$U(x) = \frac{me^4}{\epsilon^2\hbar^2}\left[\left(\frac{15\pi^3}{8\sqrt{2}}N_i^2 a_{B^*}^4\right)^{-1/10} + \sqrt{\frac{2\sqrt{2}}{15\pi}\frac{x}{a_{B^*}}}\right]^{-4},$$

where ϵ is the dielectric susceptibility of the material, N_i the sheet concentration of the impurity, and $a_{B^*} = \epsilon\hbar^2/me^2$ the effective Bohr radius.

Energy states in the well are quantized according to the quantum confinement regularities. They can accommodate a high density of electrons with a large number of occupied two-dimensional sub-bands.

One of the simplest delta-doped structures consists of a monolayer of silicon deposited onto the surface of monocrystalline GaAs and then buried with more epitaxial GaAs. Donor silicon atoms slightly diffuse away, but remain within some monolayers near the original doping plane. The electron-confining region extends to about 10 nm. The electron density in the 2DEG up to 10^{14} cm^{-2} can be reached, but at the cost of cutting their mobility.

A periodic alignment of *n*-type and *p*-type delta-doped layers separated by an intrinsic material is known as a *nipi* structure. When donor and acceptor concentrations in *n*-type and *p*-type layers, respectively, are equal the structure in equilibrium has no free carriers to move. Non-equilibrium carriers, generated for example by the light illumination of the structure, appear to be separated by the built-in electric field. Their charge modifies the energy band diagram in the same way as equilibrium carriers do. An identical effect can be also achieved by external electrical biasing of the *n*- and *p*-layers. Both approaches give an opportunity of effective tuning of the energy band diagram.

delta function – a distribution δ such that $\int_{-\infty}^{\infty} f(x)\delta(x-t)\mathrm{d}x = f(t)$, also known as a **Dirac delta function**. It is a functional generalization of the **Krönecker delta function**.

demagnetization curve – a functional relationship between the magnetic induction and the strength of the magnetic field when the strength of the field is decreased from the saturation state of the material to the point of zero flux.

Dember effect – an appearance of an electric field in a uniform semiconductor when it is nonuniformly irradiated with light. It is a result of different diffusion lengths of electrons and holes generated by the light.

First described in: H. Dember, *Über eine photoelektromotorische Kraft in Kupferoxid-Kristallen,* Phys. Z. **32**, 554–556 (1931) – experiment; J. I. Frenkel, *Possible explanation of superconductivity,* Phys. Rev. **43**(11), 907–912 (1933) – theory.

dendrimer – an artificially manufactured or synthesized branched molecule built up from **monomers**. Dendrimer = dendritic **polymer**, where Greek "dendra" means "tree". A schematic representation of a dendrimer is shown in Figure D.2.

First described in: E. Buhleier, W. Wehner, F. Vögtle, *"Cascade"- and "Nonskid-Chain-like" syntheses of molecular cavity topologies,* Synthesis **1978** 155–158 (1978).



Figure D.2 Schematic structure of a second-generation dendrimer.

dendrite – a tree-like crystal.

Derjaguin–Muller–Toporov force → **Derjaguin–Muller–Toporov model**.

Derjaguin–Muller–Toporov model approaches the problem of **adhesion** between a sphere and a flat surface considering a **Lennard-Jones potential** acting in the region around the contact area. The friction force becomes $F_f = \tau\pi(R/K)^{2/3}F_{DMT}^{2/3}$ where $F_{DMT} = N + 2\pi R\gamma$ is the so-called **Derjaguin–Muller–Toporov force**. In these formulae N is the applied load, R is the radius of the sphere, and $\gamma = \gamma_1 + \gamma_2 - \gamma_{1,2}$ is the interfacial energy (γ_1 is the surface energy of the sphere, γ_2 is the surface energy of the flat surface, and $\gamma_{1,2}$ is the energy of the interface). For the meaning of K → **friction force theory**. For zero applied load the friction force reduces to $F_{f0} = \tau\pi[(2\pi R^2\gamma)/K]^{2/3}$ and the contact radius is $a_0 = [(2\pi R^2\gamma)/K)]^{1/3}$. The model is more suitable for low adhesion and small (tip) radii.

First described in: B. V. Derjaguin, V. M. Muller, Y. P. Toporov, *Effect of contact deformations on the adhesion of particles,* J. Coll. Interface Sci. **67**(2), 314–326 (1975).

density functional theory states that the ground state energy corresponds to the minimum of a functional of the density of electrons, which is a function of position. Then electron distribution in the ground state is shown to be determined by solving the **Schrödinger equation** with an appropriate one-electron potential which takes into account the exchange correlation energy as well as the classical electron–electron and electron–nucleus Coulomb interactions. The exchange-correlation potential, which is a function of the electron density, in principle, can be determined only approximately. The approximation which is widely used is the **local density approximation**. By calculating the one-electron potential self-consistently, one can determine not only the electron structure for a given lattice configuration of nuclei but also the crystal structure itself and lattice spacing on the basis of the energy minimum principle by comparing the total energy of various configurations.

The density functional theory is based on two general theorems, the **Hohenberg–Kohn theorems**:

- any physical property of an interacting electron gas, in its fundamental state, can be written as a unique functional of the electron density $\rho(\mathbf{r})$ and, in particular, its total energy $E[\rho]$ (the total energy of an electron gas in the presence of a background potential may be written as a functional of the charge density)
- $E[\rho]$ reaches its minimum for the true density $\rho(\mathbf{r})$, that is, derived from the Schrödinger equation. The true charge density of the system is that which minimizes this functional subject to it having the correct normalization.

For electrons moving in a potential due to ions (in the CGS system)

$$E[\rho] = -e^2 \int \frac{\rho^-(\mathbf{r})\rho^+(\mathbf{r}')}{|\mathbf{r}-\mathbf{r}'|}\mathrm{d}^3\mathbf{r}\mathrm{d}^3\mathbf{r}' + \frac{e^2}{2} \int \frac{\rho^-(\mathbf{r})\rho^-(\mathbf{r}')}{|\mathbf{r}-\mathbf{r}'|}\mathrm{d}^3\mathbf{r}\mathrm{d}^3\mathbf{r}'$$

$$+\frac{e^2}{2}\int \frac{\rho^+(\mathbf{r})\rho^+(\mathbf{r}')}{|\mathbf{r}-\mathbf{r}'|}\mathrm{d}^3\mathbf{r}\mathrm{d}^3\mathbf{r}' + T[\rho(\mathbf{r})] + E_{xc}[\rho(\mathbf{r})],$$

where $\rho^+(\mathbf{r})$ is the number of elementary positive charges per unit volume. The first three terms are due to the classical Coulomb electron–ion, electron–electron and ion–ion interactions, respectively. The fourth term is the kinetic energy of a non-interacting electron system of density $\rho(\mathbf{r})$. The last term is the exchange and correlation energy.

The theory is applicable for simulation of fundamental electronic and related properties of matter.

First described in: P. Hohenberg, W. Kohn, *Inhomogeneous electron gas*, Phys. Rev. **136**(3B), B864–B871 (1964); W. Kohn, L. J. Sham, *Quantum density oscillations in an inhomogeneous electron gas*, Phys. Rev. **137**(6A), A1697–A1705 (1965); W. Kohn, L. J. Sham, *Self consistent equations including exchange and correlation effects*, Phys. Rev. **140**(4A), A1133–A1138 (1965).

More details in: E. K. Gross, F. J. Dobson, M. Petersilka, *Density Functional Theory* (Springer, Heidelberg, 1996).

Recognition: in 1998 W. Kohn received the Nobel Prize in Chemistry for his development of the density functional theory.

See also www.nobel.se/chemistry/laureates/1998/index.html.

density of states – a number of states per energy interval dE per spin orientation per unit volume of real space. Total density of states and projected density of states are distinguished. The **total density of states** is calculated as

$$n(E) = \frac{2}{V_{BZ}}\sum_n \int_{V_{BZ}} \delta(E - E_n(\mathbf{k}))\mathrm{d}\mathbf{k},$$

where V_{BZ} is the Brillouin zone volume. The integral is taken over the surface of constant energy E and n is the band index. The **projected density of states** of the atom type t is

$$n_l^t(E) = \frac{2}{V_{BZ}}\sum_n \int_{BZ} Q_l^t(\mathbf{k})\delta(E - E_n(\mathbf{k}))\mathrm{d}\mathbf{k},$$

where Q_l^t is the partial charge.

The total densities of states in three-dimensional (3D) and reduced-dimensionality systems are:

$$3D : n_{3D}(E) = \frac{m^*\sqrt{2m^*E}}{\pi^2\hbar^3},$$

$$2D : n_{2D}(E) = \frac{m^*}{\pi\hbar^2 l_x}\sum_i \Theta(E - E_i), i = 1, 2, \ldots,$$

$$1D : n_{1D}(E) = \frac{\sqrt{2m^*}}{\pi\hbar l_x l_y}\sum_{i,j}\sqrt{\frac{1}{(E - E_{i,j}}}, i,j = 1, 2, \ldots,$$

$$0D : n_{0D}(E) = \frac{2}{l_x l_y l_z} \sum_{i,j,k} \delta(E - E_{i,j,k}), i, j, k = 1, 2, \ldots,$$

where m^* is the effective electron mass, $\Theta(E - E_i)$ is the step function, $\delta(E - E_{i,j,k})$ is the δ function, and l_x, l_y, l_z are the sizes of low dimensionality.

deoxyribonucleic acid → **DNA**.

desorption – removal of a substance from a surface on which it has been adsorbed. The alternative process is **adsorption**.

Destriau effect – **electroluminescence** of zinc sulfide phosphors when excited by an electric field. This effect is the basis for the alternating-current phosphor panel technology. G. Destriau first coined the word ''electroluminescence'' to refer to the phenomenon he observed.

First described in: G. Destriau, *Recherches sur les scintillations des sulfures de zinc aux rayons*, J. Chem. Phys. **33**, 587–625 (1936).

Deutsch gate → **quantum logic gate**.

Deutsch-Jozsa algorithm – a quantum algorithm for solving the Deutsch-Jozsa problem: the task is to determine whether the Boolean function $f : \{0, 1\}^n \rightarrow \{0, 1\}$ is constant, always returning 0 or always 1 irrespective of the input, or balanced returning 0 for half of the inputs and 1 for the other half, for example, determining whether a coin is fair (heads on one side, tails on the other) or fake (heads or tails on both sides). Functions of this type are often referred to as oracle or black box. The algorithm gives the right answer using just an examination step. A classical algorithm requires in the best case two evaluations, in the worst case $(2^{n-1} + 1)$ evaluations. It is sufficient to require that f is linear and to note that a reversible implementation of f is possible by using at least one extra bit to represent the computation as a permutation of the states of the input bits.

First described in: D. Deutsch, R. Jozsa, *Rapid solutions of problems by quantum computation*, Proc. R. Soc. A **439**, 553–558 (1992).

More details in: A. Galindo, M. A. Martín Delgado, *Information and computation: classical and quantum aspects*, Rev. Mod. Phys. **74**(2), 347–423 (2002); S. Guide, M. Riebe, G. P. T. Lancaster, C. Becher, J. Eschner, H. Häffner, F. Schmidt-Kaler, I. L. Chuang, R. Blatt, *Implementation of the Deutsch-Josza algorithm on a ion-trap quantum computer*, Nature **421**(1) 48–50 (2003).

Recognition: in 2002 D. Deutsch received the International Award on Quantum Communication for his theoretical work on Quantum Computer Science.

diagonal sum rule – a sum of the diagonal elements (the trace) of the matrix of an observable is independent of representation and is just equal to the sum of the characteristic values of the observable weighted by their degeneracies.

diamagnetic – a substance which in an external magnetic field demonstrates magnetization opposite to the direction of the field, so that diamagnetics are repelled by magnets. The magnetization is proportional to the applied field. A substance in a superconducting state exhibits perfect diamagnetism → **magnetism**.

First described in: M. Faraday, *Experimental researches in electricity. - Twentieth Series*. Phil. Trans. **136**, 31–40 (1846); M. Faraday, *Experimental researches in electricity. - Twenty-first Series*. Phil. Trans. **136**, 41–62 (1846).

diamagnetic Faraday effect – the **Faraday effect** at frequencies near an absorption line, which is split due to the splitting of the upper level only.

diamond structure – specific crystalline structure which can be described as two interpenetrating **face-centered cubic (fcc)** lattices that are displaced relative to one another along the main diagonal (atomic arrangement in an fcc lattice can be seen in a **Bravais lattice**). The position of the origin of the second fcc lattice expressed in terms of the basis vector is (1/4,1/4,1/4). The structure takes its name from diamond where carbon atoms are arranged in such a fashion. It supposes three-dimensional covalent bonding in which every atom is surrounded by four nearest neighbors in a tetrahedral configuration. Other elements that crystallize with the same lattice are Si, Ge, and αSn.

diastereoisomers = **diastereomers**.

diastereomers – **stereoisomers** that are not **enantiomers** (mirror images of each other). They can have different physical properties and different chemical reactivity. In another definition diastereomers are pairs of **isomers** that have opposite configurations at one or more of the chiral centers but are not mirror images of each other → **isomers**.

Dicke effect – splitting of a **spontaneous emission** of photons by an ensemble of initially excited atoms. If the excited atoms are located in a region smaller than the wavelength of the emitted radiation, they no longer decay independently. Instead, the radiation has a higher intensity and takes place in a shorter time interval than for an ensemble of independent atoms due to the coupling of all atoms to the common radiation field.

In the case of emission from two excited atoms with dipole moments d_1 and d_2 at positions r_1 and r_2 the spontaneous emission rate of photons with wave vector **Q** following the **Fermi's golden rule** is $\Gamma_\pm(Q) \sim \sum_Q |g_Q|^2 |1 \pm \exp[i\mathbf{Q}(\mathbf{r}_2 - \mathbf{r}_1)]|^2 \delta(\omega_0 - \omega_q)$, where $Q = \omega_0/c$, ω_0 is the transition frequency between the upper and lower level, and g_Q is matrix element for the mode **Q**. The two signs "+" and "−" correspond to the two different relative orientations of the dipole moments of the two atoms. The interference of contributions of these atoms leads to splitting of the spontaneous emission of photons into a fast superradiant decay channel described by $\Gamma_+(Q)$ and a slow subradiant decay channel described by $\Gamma_-(Q)$.

From the four possible states in the **Hilbert space** of two two-level systems one can expect to observe their singlet and triplet states. The superradiant decay channel occurs via the triplet and the subradiant decay via the singlet states. In the extreme Dicke limit where the second phase factor is close to unity, $|\exp[\mathrm{i}\mathbf{Q}(\mathbf{r}_2 - \mathbf{r}_1)]| \approx 1$, it follows that $\Gamma_-(Q) = 0$ and $\Gamma_+(Q) = 2\Gamma(Q)$, where $\Gamma(Q)$ is the decay rate of one single atom. This limit is theoretically achieved if $|\mathbf{Q}(\mathbf{r}_2 - \mathbf{r}_1)| \ll 1$ for all wave vectors **Q**, so that the distance between the two atoms is much smaller than the wavelength of the light. In reality, the conditions for which the subradiant rate is zero and the superradiant rate is just twice the rate for an individual atom is never reached.

First described in: R. H. Dicke, *Coherence in spontaneous radiation processes*, Phys. Rev. **93**(1), 99–110 (1954).

Dicke superradiance – a collective decay of an ensemble of excited two-level systems due to spontaneous emission.

First described in: R. H. Dicke, *Coherence in spontaneous radiation processes*, Phys. Rev. **93**(1), 99–110 (1954).

More details in: M. G. Benedict, A. M. Ermolaev, V. A. Malyshev, I. V. Sokolov, E. D. Trifonov, *Super Radiance*, Optics and Optoelectronics Series (Institute of Physics, Bristol, 1996).

dielectric – a substance in which an external moderate electric field once established may be maintained without loss of energy. It is an insulator containing no free charges. Actual dielectrics may be slightly conducting and the line of demarcation between insulators or dielectrics and **semiconductors** or **conductors** is not sharp.

dielectric function – a function $\epsilon(\omega)$ relating the electromagnetic field **E** applied to matter and the displacement of charges **D** produced in it via $\mathbf{D} = \epsilon(\omega)\mathbf{E}$. It is a complex quantity, so $\epsilon(\omega) = \epsilon_1(\omega) + \mathrm{i}\epsilon_2(\omega)$ with the corresponding real $\epsilon_1(\omega)$ and imaginary $\epsilon_2(\omega)$ parts.

The imaginary part of the dielectric function is defined by the quantum-mechanical transition rate W_{ij} in the random phase approximation for transitions from the state i to j via $\epsilon_2 = (n^2/\omega)\sum W_{ij}(\omega)$. The summation runs over all occupied and unoccupied states. For transitions between one-electron Bloch states from the filled valence into empty conduction band states the transition rate within the first-order perturbation theory is $W_{ij}(\omega) = (2\pi/h)|V_{ij}(k)|^2\delta(E_{ij}(k) - \hbar\omega)$, where the interband **matrix element** $|V_{ij}|$ contains the Bloch factors of the valence and conduction band wave functions and the dipole operator of the incident light wave, which is considered as perturbation. The interband matrix element depends on the symmetry of the states participating in the optical transitions and the light polarization. The dipole operator has odd **parity**, therefore V_{ij} vanishes unless the Bloch factors have odd parity. Transitions are termed allowed if V_{ij} is non-zero, otherwise they are termed forbidden. Generally V_{ij} is dependent on the electron wave vector **k**; however, near critical points they are generally independent of **k**.

The real and imaginary parts of the dielectric function are connected by the **Kramers-Kronig dispersion relation**. They are used to calculate the macroscopic optical properties of solids represented by the **refractive index** n^*, **extinction coefficient** k^*, and **absorption coefficient** α:

$$n^* = \left\{(1/2)\left[\epsilon_1 + (\epsilon_1^2 + \epsilon_2^2)^{1/2}\right]\right\}^{1/2},$$

$$k^* = \left\{(1/2)\left[-\epsilon_1 + (\epsilon_1^2 + \epsilon_2^2)^{1/2}\right]\right\}^{1/2},$$

$$\alpha = \frac{4\pi k^*}{\lambda},$$

where λ is the wavelength of the light in a vacuum.

differential scanning calorimetry (DSC) – a technique of thermal analysis of matter which involves heating of a sample along with a thermally inert reference material and measuring the relative heat changes that occur in the sample during the heating process. The most common heat change normally observed is the melting transition of a crystalline material, which results in an absorption of heat or energy relative to the inert standard. It is observed as an endothermic peak in the thermogram. The reverse phenomenon, that is crystallization, occurring upon cooling a crystallizable material from the melt manifests itself as a release of heat. It is observed as an exothermic peak. Many other heat-sensitive phenomena can also be characterized by this technique, such as glass and multiple crystal phase transitions, loss of volatiles, melting of blends and alloys, and degradation processes.

diffraction – generation of a weaker wavefront at an opaque edge or around a hole when waves pass through them. These secondary wavefronts will interfere with the primary wavefront as well as with each other to form various diffraction patterns.

diffusion – a directed motion of matter driven by a gradient of the electrochemical potential in a system. It provides homogenization or approach to equilibrium through random atomic motion. Gradients of the electrochemical potential are often related to gradients of particle concentrations and temperature gradients in real systems.

When a gradient of particle concentration N is a driving force for diffusion, the flux of the diffusion particles per unit area is $J = -D\mathrm{grad}N$ (in the one-dimensional case $J = -D(\partial N/\partial x)$), where D is the coefficient of diffusion or particle's diffusivity. Time-dependent variation of the particle concentration is described by the equation $(\partial N/\partial t) = \text{grad}(D\text{grad}N)$ (in the one-dimensional case $(\partial N/\partial t) = (\partial/\partial x)(D\partial N/\partial x)$). The above equations are also referred to as **Fick's laws** of diffusion, the first law and the second law, respectively.

In solids, diffusion motion of atoms needs point lattice defects to be involved in the process. So far the mechanisms of atomic diffusion distinguished in solids are: i) vacancy mechanism (an atom in a substitutional position jumps into a nearest vacancy by exchanging with it), ii) interstitial mechanism (jumps between neighboring interstitial sites in the lattice), iii) place exchange or ring mechanism (the simultaneous movement of two (in place exchange) or more (in ring) neighboring atoms as a result of which they squeeze past each other and exchange sites in the lattice). In the last case, lattice defects are not so important. In practice, superposition of the above mechanisms can take place.

First described mathematically in: A. Fick, *Über Diffusion*, Ann. Phys. **94**, 59–86 (1855).

More details in: J. Crank, *Mathematics of Diffusion* (Clarendon Press, Oxford, 1956); B. I. Boltaks, *Diffusion in Semiconductors* (Academic Press, New York, 1963).

diffusion length – an average distance diffused by a particle, i.e. a charge carrier or an atom, from the point at which it is formed or liberated to the point where it is absorbed.

diluted magnetic semiconductors are typically $A^{II}B^{VI}$ and $A^{III}B^{V}$ semiconductors in which element A is partially substituted by magnetic ions - very often by manganese (Mn). In contrast to magnetic semiconductors, such as Eu chalcogenids or $ZnCr_2Se_4$, diluted magnetic semiconductors allow for tuning their magnetic properties by the variation of magnetic ion concentration. $Zn_{1-x}Mn_xSe$, $Zn_{1-x-y}Be_xMn_ySe$, and $Ga_{1-x}Mn_xAs$ are widely used examples of diluted magnetic semiconductors. Magnetic properties of these materials are determined by the manganese atoms. They are controlled by the strong exchange interaction between the hybridized $sp^2 - d$ **orbitals** of the magnetic ions and charge carriers. As a result, giant **Zeeman splitting** is observed in both conduction and valence bands when the material is placed in an external magnetic field. It is illustrated in Figure D.3.

The conduction band of the diluted semiconductors is two-fold spin degenerate, whereas the valence band has four spin degenerate states related to heavy and light holes. In the magnetic field the spin degeneracy is lifted providing vacant places for spin-up ($m_j = +1/2$) and spin-down ($m_j = -1/2$) electrons and both spin-oriented heavy ($m_j = +3/2$ and $m_j = -3/2$) and light holes ($m_j = +1/2$ and $m_j = -1/2$). Manganese incorporates into $A^{II}B^{VI}$ semiconductors isoelectrically, so manganese-containing materials may also be doped by either n- or p-type impurities. In $A^{III}B^{V}$ semiconductors manganese acts as a shallow acceptor precluding the fabrication of *n*-type material.

More details in: A. Twardowski, *Diluted Magnetic Semiconductors* (World Scientific, Singapore, 1996).



Figure D.3 Splitting of conduction and valence bands of a diluted semiconductor in an external magnetic field (B).

dimer – a molecule composed of two identical sub-units (**monomer**s) linked together.

diode – an electronic device permitting electric current to flow in one direction only.

diploid – a **eukaryotic** cell with two sets of **chromosomes**.

dipole – a pair of electric charges, equal in magnitude but opposite in size. The product of the magnitude of the charges and their distance of separation is the **dipole momentum**.

First described by: P. Debye, *Some Results of a Kinetic Theory of Insulators*, Phys. Z. **13**, 97–100 (1912).

Recognition: in 1936 P. Debye received the Nobel Prize in Chemistry for his contributions to our knowledge of molecular structure through his investigations on the dipole moments and on diffraction of X-rays and electrons in gases.

See also www.nobel.se/chemistry/laureates/1936/index.html.

dip-pen nanolithography – the technique providing fabrication of molecular layer patterns with nanometer features with the use of a scanning probe of an **atomic force microscope**. In this technique the water meniscus is formed between the tip of the probe and the substrate. The molecules to be deposited are dissolved in the water thus forming an ink. It acts both as a source of the molecules and as a medium for the molecular transport. The pattern formation is illustrated in Figure D.4.

First, the ink is deposited onto the tip from an ink-pot. Then, the tip is positioned at the substrate and scanned over it with a combination of contact and non-contact modes. The molecules are deposited only in the regions where the tip is in contact with the substrate and the meniscus is formed. The meniscus formation is dependent on the humidity of the ambient atmosphere and the water reaction of



Figure D.4 Pattern formation by dip-pen nanolithography.

the substrate surface (**hydrophilic** or **hydrophobic**). The scan speed determines the amount of ink that is carried out with the tip. At high scan rates the tip can carry less ink. As the molecular transport is essentially diffusion controlled, the number of deposited molecules is proportional to $t^{1/2}$, where t is the time of contact between the tip and the substrate.

The efficiency of the technique depends on the capability of depositing molecules to form self-assembled monolayers. Among already tested compounds, 16-mercapto hexadecanoic acid and 1-octadecane thiol have been shown to meet the requirements. The best results are obtained when the substrate is covered by a nanometer-thick gold film which is patterned first and then used as a mask for dipper profiling of the underlaying region. Surface structures with feature sizes down to 10 nm can be fabricated.

First described in: R. D. Piner, J. Zhu, F. Xu, *"Dip-pen" nanolithography*, Science **283**, 661–663 (1999).

Dirac delta function → **delta function**.

Dirac equation – a relativistic wave equation for a quantum particle in which the wave function has four components corresponding to four internal states specified by a two-valued spin coordinate and an energy, which can have a positive or negative value. It was obtained by employing the following linearized expression for energy of a quantum particle of mass m with momentum $\mathbf{p}$: $E = c\boldsymbol{\alpha}\cdot\mathbf{p} + \beta mc^2$ (instead of $E = (c^2\mathbf{p}^2 + m^2c^4)^{1/2}$ originating from the special theory of relativity). The four symbols $\alpha = (\alpha_1, \alpha_2, \alpha_3)$ and β are mutually anti-commuting operators satisfied by the matrices, i.e.:

$$\alpha_i = \begin{pmatrix} 0 & \sigma_i \\ \sigma_i & 0 \end{pmatrix}, \quad \beta = \begin{pmatrix} 1 & 0 \\ 0 & -1 \end{pmatrix},$$

where σ_i are **Pauli spin matrices**. Thus, $\alpha_i\alpha_j + \alpha_j\alpha_i = 2\delta_{ij}, \beta^2 = 1, \alpha_i\beta + \beta\alpha_i = 0$, where δ_{ij} is the **Krönecker delta function**.

Substituting the expression for energy into the **Schrödinger equation** leads to the Dirac equation:

$$i\hbar\frac{\partial\Psi(r,t)}{\partial t} = (c\boldsymbol{\alpha}\cdot\mathbf{p} + \beta mc^2)\Psi(r,t).$$

The wave function $\Psi(r, t)$ is now a four-component entity called a **spinor**. The time-independent Dirac equation for a single particle in the external potential $U(r)$ has the form

$$(c\boldsymbol{\alpha}\cdot\mathbf{p} + U(r) + \beta mc^2)\Psi(r) = (E + mc^2)\Psi(r),$$

where the binding energy E has the same meaning as that in nonrelativistic theory.

In fact, the Dirac equation is a Lorentz invariant relativistic generalization of the Schrödinger (nonrelativistic) equation.

First described in: P. A. M. Dirac, *The quantum theory of the electron* Proc. R. Soc. A **115**, 610–624 (1928).

Recognition: in 1933 P. A. M. Dirac and E. Schrödinger received the Nobel Prize in Physics for the discovery of new productive forms of atomic theory.

See also www.nobel.se/physics/laureates/1933/index.html.

Dirac matrix – any one of four 4 × 4 matrices designated $\gamma_k (k = 0, 1, 2, 3)$. They satisfy $\gamma_k\gamma_l + \gamma_l\gamma_k = 2\delta_{kl}\mathbf{E}, \gamma_k\gamma_0 + \gamma_0\gamma_k = 0, \gamma_k\gamma_l = \gamma_0^2 = \mathbf{E}$ for $k, l = 1, 2, 3$. Here δ_{kl} is the **Krönecker delta function**, and $\mathbf{E}$ is the single matrix. The matrices are used to operate on the four-component wave function in the **Dirac equation**.

First described in: P. A. M. Dirac, *The quantum theory of the electron*, R. Proc. Soc. A **115**, 610–624 (1928).

Dirac monopole – a quantum of magnetic charge equal to h/e. It is also known as the magnetic monopole.

First described in: P. A. M. Dirac, *The Principles of Quantum Mechanics* (Oxford University Press 1930).

Dirac notation (for quantum states) – any quantum state represented by a vector Ψ in a complex **Hilbert space** may be written as "**ket**"

$$|\Psi_a\rangle \to \begin{pmatrix} a_0 \\ a_1 \\ a_2 \end{pmatrix}$$

or "**bra**"

$$\langle\Psi_a| \to (a_0^* a_1^* a_2^*).$$

The state vector should be normalized, so $\sum_i |a_i|^2 = 1$.

Bras and kets are related by Hermitian conjugation: $|\Psi_a\rangle = (\langle\Psi_a|)^\dagger, \langle\Psi_a| = (|\Psi_a\rangle)^\dagger$. The inner product of a bra and a ket $\langle\Psi_a||\Psi_b\rangle$ denotes $\langle\Psi_a|\Psi_b\rangle$. It is a complex number: $\langle\Psi_a|\Psi_b\rangle = a_0^*b_0 + a_1^*b_1 + a_2^*b_2$. For normalized states $\langle\Psi|\Psi\rangle = 1$. The outer product of a bra and a ket is a linear operator (matrix):

$$|\Psi_a\rangle\langle\Psi_b| = \begin{pmatrix} a_0b_0^* & a_0b_1^* & a_0b_2^* \\ a_1b_0^* & a_1b_1^* & a_1b_2^* \\ a_2b_0^* & a_2b_1^* & a_2b_2^* \end{pmatrix}$$

It is often convenient to work with basis kets and bras representing a state:

$$|\Psi_a\rangle \rightarrow a_0|0\rangle + a_1|1\rangle + a_2|2\rangle$$

with

$$|0\rangle = \begin{pmatrix} 1 \\ 0 \\ 0 \end{pmatrix}, \quad |1\rangle = \begin{pmatrix} 0 \\ 1 \\ 0 \end{pmatrix}, \quad |2\rangle = \begin{pmatrix} 0 \\ 0 \\ 1 \end{pmatrix};$$

$$\langle\Psi_a| \rightarrow a_0^*\langle 0| + a_1^*\langle 1| + a_2^*\langle 2|$$

First described in: P. A. M. Dirac, *The Principles of Quantum Mechanics* (Oxford University Press, 1930).

Dirac wave function – a two-component function of the form

$$\psi = \begin{pmatrix} \phi_1 \\ \phi_2 \end{pmatrix}.$$

It is appropriate for describing spin 1/2 particles and antiparticles.

direct current Josephson effect → **Josephson effects**.

directed molecular evolution – a strategy within **protein engineering** where mutagenesis is applied to protein generating a greater diversity of mutation. If further diversity is desired a random factor is introduced to make more mutants and a selection regime is used to choose variants with the searched qualities.

More information in: J. A. Brannigan, A. J. Wilkinson, *Protein engineering 20 years on*, Nat. Rev. Molec. Cell Biol. **3**, 964–970 (2002).

dislocation – a region of distorted atom configuration formed between the displaced and normal areas in a crystal when part of the crystal is displaced tangentially.

dispersion curve – an electron energy versus momentum curve usually presented as $E(k)$, where k is the wave vector.

disruptive technologies are those that displace older technologies and enable radically new generations of existing products and processes to take over. The term has been coined by Clayton Christiansen in 1995. Nanotechnology is a disruptive technology.

dissociation – a process causing ingredients of a substance to split into simple groups, which in the case of compounds can be single atoms, groups of atoms or ions.

distributed Bragg reflector – a solid-state structure formed from multiple layers of alternating materials with varying **refractive index** or by periodic variation of some characteristic (such as height) of a dielectric waveguide, resulting in periodic variation in the effective refractive index in the guide. Each layer boundary causes a partial reflection of an optical wave. For waves whose wavelength is close to four times the optical thickness of the layers, the many reflections combine with constructive **interference**. The layers act as a high-quality reflector. The range of wavelengths that are reflected is called the **photonic stopband**. Within this range of wavelengths, light is ''forbidden'' to propagate in the structure.

Reflectivity of the reflector composed of N repeated pairs of materials with different (low/high) refractive indices n_1 and n_2 can be calculated as

$$R = \left[\frac{n_a(n_2)^{2N} - n_s(n_1)^{2N}}{n_a(n_2)^{2N} + n_s(n_1)^{2N}} \right]^2 ,$$

where n_a and n_s are the refractive indices of surrounding ambient and the substrate, respectively. The bandwidth of the photonic stopband is $\Delta\nu = (4\nu/\pi)\arcsin[(n_2 - n_1)/(n_2 + n_1)]$, where ν_0 is the central frequency of the band.

It is evident that an increase in the number of pairs in the reflector increases its mirror reflectivity. An increase in the refractive index contrast between the materials in the pairs brings increases in both the reflectivity and the bandwidth.

distributed-feedback laser – a **laser** with a resonator consisting of a periodic structure, which acts as a **distributed Bragg reflector** in the wavelength range of laser action and containing an optical gain medium. Typically, the periodic structure supposes a phase shift in its middle. This structure is thus basically the direct concatenation of two Bragg gratings with an internal optical gain. It has multiple axial optical modes, but there is typically one mode which is favored in terms of losses. Therefore, single-frequency operation is often easily achieved despite spatial **hole-burning** due to the standing-wave pattern in the gain medium. Most distributed-feedback lasers are either fiber lasers or semiconductor lasers.

DNA – an acronym for a **d**eoxyribo**n**ucleic **a**cid. A molecule of DNA contains six commonly occurring molecular components. They are: two purines–adenine (A) and guanine (G), two pyrimidines–cytosine (C) and thymine (T), sugar–deoxyribose, and phosphoric acid. Their formulae are presented in Figure D.5. The above purines and pyrimidines are called bases. Figure D.6 shows the chemical composition of a fragment of a DNA chain. Its backbone is built from repeating deoxyribose and phosphate groups. Each deoxyribose group is attached to one of four bases (adenine, guanine, cytosine or thymine). The sequence of bases constitutes the genetic code. In space, such chains form a double helix structure, similar to a twisted ladder, schematically shown in Figure D.7. It consists of two strands of DNA twisting around each other. Each strand is composed of a long chain of monomer nucleotides. The nucleotide of DNA consists of a deoxyribose



Figure D.5 Molecular components of DNA.

sugar molecule to which a phosphate group and one of the four bases are attached. The nucleotides are joined together by covalent bonds between the phosphate of one nucleotide and the sugar of the next, forming a phosphate sugar backbone from which the nitrogenous bases protrude. Hydrogen bonds between the bases couple the two strands together. The chemical bonding is such that adenine base in one chain forms hydrogen bonds with a thymine base in the other chain of the double helix, while guanine and cytosine bases are similarly hydrogen bonded across the axis of the double helix. The base pairs look like the rungs of a helical ladder. This is the **Watson–Crick double-helix model of DNA**. This A–T and G–C bonding, to give what are called **Watson–Crick base pairs**, satisfies **Chargaff's rules** that the molar ratios of A to T and of G to C are very close to unity in all DNA samples, whatever the sequence of bases.

The naturally occurring double helix structure has two preferential forms, A and B. The B form is the main one. It is shown in Figure D.7. Both A and B are right handed double helixes. The double helix is about 2 nm wide, and its repeat


Phosphate group
Deoxyribose
Adenine
Phosphate group
Deoxyribose
Guanine
Phosphate group
Deoxyribose
Cytosine
Phosphate group
Deoxyribose
Thymine

Figure D.6 Chemical composition of a part of a DNA chain.

consists of about 10.5 nucleotide pairs, each separated by about 0.34 nm. In the A structure, the bases are tilted and the hydrogen bonds are less nearly perpendicular to the axis of the helix. Which form occurs depends not on chemical composition but on the degree of hydration. An artificial left handed form, called Z form, can also exist. It got its name from the zigzag form of the phosphate sugar backbone. It has a repetition period of 4.46 nm containing 12 pairs of bases per one helix turn.



Figure D.7 Double helix structure of DNA (Figure 1a,b from C. Dekker, M. A. Ratner, *Electronic properties of DNA*, Physics World **14**(8), 29–33 (2001), by permission).

Two pairs of bases are repeated in the Z-DNA in contrast to one pair repetition in A- and B-DNA.

In a living cell, DNA is combined with protein to form chromosomes, which are replicated when a cell divides. DNA controls the functioning of the cell by determining which protein molecules are synthesized there, and the amino acid sequence in the proteins is in turn determined by the sequence of adenine, guanine, cytosine and thymine in the DNA chain. Thus, the sequence of bases in DNA constitutes a code for the amino acid sequence in a protein.

DNA is very important not only as a genetic biomolecule, but also as a molecular template for nanotechnology. Besides, it is a good medium for one-dimensional charge carrier transport predominantly via coherent tunneling and diffusive thermal hopping. That makes DNA molecules attractive for applications in nanoelectronics, molecular electronics and nanomechanics.

First described in: W. T. Astbury, F. O. Bell, *Some recent developments in the X-ray study of proteins and related structures,* Cold Spring Harbor Symposia in Quantum Biology **6**, 109–121 (1938) – DNA composition; J. D. Watson, F. H. C. Crick, *Molecular structure of nucleic acids,* Nature **171**, 737–738 (1953) – DNA double helix structure.

Recognition: in 1962 F. H. C. Crick, J. D. Watson and M. H. F. Wilkins (team leader) received the Nobel Prize in Physiology or Medicine for their discoveries concerning the molecular structure of nucleic acids and its significance for information transfer in living material.

DNA-based molecular electronics – **DNA** molecules seem particularly appealing for **molecular electronics** by virtue of their double-strand **recognition** and their special structuring that suggests their use in **self-assembly**. The idea that double-stranded DNA may function as a conduit for fast electron transport, along the axis of its base-pair stack, was first advanced in 1962. More and more evidence accumulating from the direct electrical transport measurements shows that it is possible to transport a charge carrier along short single DNA molecules, in bundles, and in a network, although the conductivity is rather poor.

First described in: D. D. Eley, D. I. Spivey, *Semiconductivity of organic substances: nucleic acid in dry state*, Trans. Faraday Soc. **12**, 245 (1962).

More details in: D. Porath, G. Cuniberti, R. Di Felice, *Charge transport in DNA-based devices* in *Long Range Charge Transport in DNA* ed. Gary Schuster, Topics in Current Chemistry (Springer Verlag, Berlin, 2004) pp. 183–227.

DNA probe – a single-stranded piece of **DNA** that binds specifically to a complementary DNA sequence. The probe is labeled, for example with a fluorescent or radioactive tag, in order to detect its incorporation through hybridization with DNA in a sample.

domain wall → **Bloch wall**.

dome – an open crystal form consisting of two faces astride a symmetry plane.

donor (atom) – an impurity atom, typically in semiconductors, which donates electron(s). Donor atoms usually form electron energy levels slightly below the bottom of the conduction band. An electron is readily excited into this band and may then contribute to the electrical conduction of the material.

Doppler effect – a difference between the frequency with which waves are produced by a source and the frequency with which they may be registered by an observer. This difference occurs, in general, when the source, the observer, or both are moving relative to the medium in which the waves are propagated.

First described in: C. Doppler, *Über das farbige Licht der Doppelsterne und einige andere Gestirne der Himmel*, Abhand. Köngl. Böhm. Ges. **2**(5), 465 (1842).

Doppler–Fizeau principle states that the displacement of spectral lines is determined by the distance between, and relative velocity of, the observer and the light source. When the distance decreases, the lines of the spectrum move toward the ultraviolet. When it increases, the lines move toward the red part of the spectrum.

First described by H. Fizeau in 1848.

d orbital → **atomic orbital**.

dot blot – a method for detecting **proteins** by specific binding of an **antibody** or binding molecule to a sample spot on nitrocellulose paper. The bound sample is visualized using an enzymatic or fluorimetric reporter conjugated to the probe.

double heterostructure laser – a semiconductor laser in which active layer of one semiconductor material is sandwiched between two *n*- and *p*-doped layers of another semiconductor that have wider band gaps. A heterostructure combining wider gap AlGaAs and smaller gap GaAs suits this demand well. Energy band diagram of such structure is shown in Figure D.8.

The *n*- and *p*-doped layers, called **cladding layers**, are used to inject carriers into the active region. Electrons and holes injected through the heterojunctions at forward bias appear to be confined to the active region by the potential barriers of the heterojunctions. Their radiative recombination there yields photons with the energy determined by the energy gap of the active layer semiconductor. The double heterostructure forms an efficient waveguide as well because the refractive index of the active layer is higher than that of the cladding layers. Thus, interaction between optical field and injected carriers is facilitated, which is needed for laser action. Polished mirror facets perpendicular to the heterojunction planes are used to form an optical resonator.


n-cladding layer
Active layer
p-cladding layer
E_c
E_v
E
x

Figure D.8 Energy bands in double heterojunction laser at forward bias.

Most promoted double heterostructure lasers adopt a stripe geometry in which current is injected only within a narrow region beneath a stripe contact in order to keep the threshold current low and to control the optical field distribution in the lateral directions. Their representative examples are schematically shown in Figure D.9. As compared with continuous layer lasers, the threshold current is reduced below 1000 A cm^{-2} roughly in proportion to the area of the contact. Lasing occurs in a limited region of the active layer where a high-density current flows.


W
Electrode
Insulator
p-cladding layer
n-burying layer
p-burying layer
Active layer
n-cladding layer
n-substrate
Electrode
Stripe-contact laser
Buried heterostructure laser

Figure D.9 Heterostructure laser in a stripe geometry.

In the simplest stripe contact geometry the optical intensity distribution in the lateral direction is determined by the gain profile related to the carrier density distribution. Lasers with such geometry are termed **gain-guided lasers**.

In the stripe-like buried geometry, refractive index variation in the lateral direction takes place. Such lasers are termed **index-guided lasers**. They have the active region surrounded by materials with lower refractive index in both vertical and lateral transverse directions. Thus, waveguiding can occur in both directions.

First described in: Zh. I. Alferov, R. F. Kazarinov, *Semiconductor laser with electric pumping,* Inventor's Certificate no.181737 (1963) – in Russian; H. Kroemer, *A proposed class of heterojunction injection lasers,* Proc. IEEE 51(12), 1782–1783 (1963).

Recognition: in 2000 Zh. I. Alferov and H. Kroemer received the Nobel Prize in Physics for developing semiconductor heterostructures used in high-speed and optoelectronics.

See also www.nobel.se/physics/laureates/2000/index.html.

Dresselhaus coupling – a **spin-orbit coupling** in solids resulting from breaking of the bulk inversion symmetry as takes place in **zinc blende structures**. The related spin-orbit contribution in the **Hamiltonian** is represented by the term $H_D = -\beta(k_x\sigma_x - k_y\sigma_y) + O(k^3)$, where β is the material-dependent parameter specifying the strength of the spin orbit interaction, k is the wave vector component, σ is the **Pauli spin matrix**, and $O(k^3)$ is the qubic component.

First described in: G. Dresselhaus, *Spin–orbit coupling effects in zinc blende structures,* Phys. Rev. **100**(2), 580–586 (1955).

Drude equation explains optical activity of matter containing **chiral** molecules through rotating the plane of polarization of polarized light. A molecule is chiral if it cannot be superimposed on its mirror image. Electrons in chiral molecules are considered to oscillate along a helix, giving the relationship between molecular polarizability α, wavelength of the probing light λ and the relative wavelengths λ_i in the form $\alpha = \sum_i (K_i/(\lambda^2 - \lambda_i^2))$, where K_i are constants proportional to the rotational strength of the transitions resulting in optical activity. Thus the rotation of the plane of polarization of plane-polarized light passing through the optically active media is inversely proportional to the difference between the square of the wavelength of the probing light and the square of the wavelengths relative to the transitions.

First described in: P. Drude, *Lehrbuch der Optik* (Hirzel, Leipzig, 1900).

More details in: S. F. Mason, *Molecular Optical Activity and the Chiral Discriminations* (Cambridge University Press, Cambridge, 1982).

Drude formula gives the frequency dependence of the conductivity of a solid in the form $\sigma(\omega) = \sigma_0(1 + i\omega t)/(1 + \omega^2\tau^2)$, where constant current conductivity $\sigma_0 = e^2 n\tau/m$, n is the density of free electrons, τ is the mean free time between electron scattering events, and m is the electron mass. It was obtained within a quasiclassical approach → **Drude theory** under the assumption that free electrons moving in the solid with friction define the conductivity. It is valid only when the

Fermi electron wavelength $\lambda_F = 2\pi/k_F$ is much smaller than the mean free path $l_F = v_F\tau$, that is $k_F l \gg 1$, $E_F\tau \gg 1$. Accounting for $\lambda_F \sim 0.5$ nm, it means that the quasiclassical theory becomes problematic for $\rho > 10^{-3}$ Ω cm.

First described in: P. Drude, *Zur Elektronentheorie. I,* Ann. Phys. **1**, 566–613 (1900); P. Drude, *Zur Elektronentheorie. II,* Ann. Phys. **3**, 369–402 (1900).

Drude theory was the first attempt to explain electronic properties of metals (later it was generalized for all solids) considering a gas of free electrons moving within a network of positively charged ionic cores. The assumptions applied are: (i) electrons collide and subsequently are scattered only by the ionic core; (ii) electrons do not interact with each other or with ions between the collisions; (iii) collisions are instantaneous and result in a change in the electron velocity; (iv) an electron suffers a collision with the probability per unit time proportional to τ^{-1}, where τ is the relaxation time, that is τ^{-1} is the scattering rate; (v) electrons reach thermal equilibrium with their surroundings only through collisions.

Within the framework of the theory, one may trivially express mobility of charge carriers μ and the conductivity σ of a homogeneous conductor through which the carriers are moving in terms of the electric charge e and the effective mass m of the mobile charge carriers as well as the carrier concentration n: $\mu = e\tau/m$, $\sigma = en\mu = e^2 n\tau/m$.

First described in: P. Drude, *Zur Elektronentheorie. I,* Ann. Phys. **1**, 566–613 (1900); *Zur Elektronentheorie. II,* Ann. Phys. **3**, 369–402 (1900).

DSC – an acronym for a **differential scanning calorimetry**.

DSG – an acronym for **dynamic shadowing growth**.

dual beam FIB–SEM system – a dual beam instrument composed of a **focused ion beam (FIB)** system and a **scanning electron microscope (SEM)** as schematically illustrated in Figure D.10. It is a shared experimental facility for sample preparation and fabrication at the nanoscale by ion-mill sculpting or beam-induced deposition



Figure D.10 A dual beam geometry for a combined FIB–SEM sample treatment (courtesy of P. Facci).

and offers high-resolution cross-section imaging. Thus the Dual Beam system combines in a single apparatus an ion column and an electron column working at coincidence. It enables high-resolution sample machining with the FIB and simultaneous high-resolution imaging with the non-destructive SEM probe.

Duane–Hunt law states that the frequency of X-rays resulting from electrons striking a target cannot exceed eV/h, where V is the voltage accelerating the electrons.

First described in: W. Duane, F. L. Hunt, *On X-ray wave-lengths*, Phys. Rev. **6**(2), 166 (1915).

D'yakonov–Perel mechanism – the electron spin relaxation mechanism in semiconductors in which spin splitting of the conduction band via spin–orbit coupling due to the lack of inversion symmetry (as III-V compounds) is the driving force. It is, for example, responsible for the fast spin dephasing in bulk GaAs at elevated temperatures. In bulk materials, the mechanism is usually less pronounced in semiconductors with a larger direct band gap because of the smaller influence of the **valence band** on the **conduction band**.

The related **spin relaxation time** τ can be been expressed in the semiphenomenological form as $1/\tau = A(\alpha^2/\hbar^2 E_g)\tau_p T^3$ for bulk semiconductors and $1/\tau = (\alpha^2 < p_z^2 >^2 /2\hbar^2 m^2 E_g)\tau_p T$ for **quantum well** structures. Here α describes conduction band spin splitting due to lack of inversion symmetry (for example $\alpha = 0.07$ for GaAs), E_g is the band gap, T is the absolute temperature, A is a numerical coefficient depending on the orbital scattering mechanism, $< p_z^2 >$ is the average square of the momentum in the quantum well growth direction, and τ_p is the average momentum relaxation time, being a phenomenological parameter.

Such spin relaxation increases both in (100) oriented quantum wells and in quantum wires because of the further decrease in the symmetry and increase in the momentum related to quantum confinement there. One requirement for room temperature spin transport in III-V semiconductors is therefore the suppression of the D'yakonov–Perel mechanism. This is possible since the electron interaction resulting in the spin relaxation depends on the semiconductor material and the direction of electron momentum and spin in the host crystal. This mechanism has been demonstrated to be suppressed by choosing a quantum well with special crystal axes. For instance, in an undoped (110) oriented GaAs quantum well a decrease of nearly one order of magnitude in the spin relaxation time with increasing temperature, reaching spin relaxation times as long as 2 ns at room temperature is observed. This is much longer than in (100) oriented quantum wells. An even stronger increase of nearly two orders of magnitude of the spin relaxation time with temperature is observed in ZnSe and ZnCdSe quantum wells. The slower spin dephasing at higher temperatures results from the reduced electron-hole exchange interaction, which is a very efficient source of spin relaxation due to thermal ionization of **exciton**s.

First described in: M. I. D'yakonov, V. I. Perel, *On spin orientation of electrons in interband absorption of light in semiconductors*, Zh. Eksp. Teor. Fiz. **60**(5), 1954–1965 (1971) – in Russian.

More details in: I. Žutić, J. Fabian, S. Das Sarma, *Spintronics: Fundamentals and applications*, Rev. Mod. Phys. **76**(2), 323–410 (2004).

dye – an organic molecule whose absorption bands are in the visible spectral region.

dye-sensitized solar cell – a device, also called a **Grätzel solar cell**, in which in contrast to the conventional silicon systems, where the semiconductor assumes both the task of light absorption and that of charge carrier transport, the two functions are separated. Light is absorbed by a sensitizer, which is anchored to the surface of a wide band gap **oxide** semiconductor. Charge separation takes place at the interface via photo-induced electron injection from the **dye** into the **conduction band** of the solid. Carriers are transported in the conduction band of the semiconductor to the charge collector. The use of sensitizers having a broad **absorption** band in conjunction with oxide films of nanocrystalline morphology permits one to harvest a large fraction of sunlight. Efficiencies of ∼11% have been reached. On similar principles are also based the so-called **McFarland and Tang solar cell**s.

First described in: B. O'Regan, M. Grätzel, *A low-cost, high-efficiency solar cell based on dye-sensitized colloidal TiO_2 films*, Nature **353**, 737–740 (1991); M. Grätzel, *Photoelectrochemical cells*, Nature **414**, 338–344 (2001).

More details in: M. Grätzel, *Conversion of sunlight to electric power by nanocrystalline dye-sensitized solar cells*, J. Photochem. Photobiol. A: Chem. **164**, 3–14 (2004); G. E. Tulloch, *Light and energy–Dye solar cells for the 21st century*, J. Photochem. Photobiol. A: Chem. **164**, 209–219 (2004).

dynamic force microscopy – an **atomic force microscopy** in a dynamic mode, that is when the tip is oscillating perpendicular to the sample surface. Two modes of operation are usually employed: the amplitude modulation mode (also called tapping mode) and the self-excitation mode. The first separates the purely attractive force interaction regime from the attractive-repulsive regime. It is primarily used for imaging in air and liquid. The second dominates for imaging in ultrahigh vacuum to get real atomic precision.

More details in: A. Schirmeisen, B. Anczykowski, H. Fuchs, *Dynamic force microscopy*, in: Handbook of Nanotechnology, edited by B. Bhushan (Springer, Berlin, 2004), pp. 449–473.

dynamic redox system – a compound that can be reversibly converted into the corresponding charged species upon electron transfer but accompanied by drastic structural changes and/or covalent bond making/breaking. Although transformation between the neutral and charged species proceeds quantitatively in most cases, their electrochemical processes are irreversible owing to the chemical reactions followed by the electron transfer. This situation endows the dynamic **redox** pairs with very high bistability, which is a prerequisite in order to construct the molecular response systems.

More details in: T. Suzuki, H. Higuchi, T. Tsuji. J. I. Nishida, Y. Yamashita, T. Miyashi, *Dynamic redox systems: Towards realization of the unimolecular memory,* in: *Chemistry of Nanomolecular Systems. Towards the realization of Nanomolecular Devices,* edited by T. Nakamura, T. Matsumoto, H. Tada, K. I. Sugiura (Springer, Berlin Heidelberg, 2003).

dynamic shadowing growth (DSG) – a technique that involves physical vapor deposition in which the angle of the vapor-beam direction can be controlled so that different shapes of material can be deposited on a substrate. It is used to fabricate catalytic nanomotors that mimic the way biological motors work.

First described in: Y. He, J. Wu, Y. Zhao, *Designing catalytic nanomotors by dynamic shadowing growth,* Nano Lett. **7**(5), 1369–1375 (2007).

dynamics – a study of the behavior of objects in motion. It can be distinguished in this way from statics, which deals with objects at rest or in a state of uniform motion, and also from **kinematics**, which studies the geometry of motion only without any reference to the forces causing it.

Dzyaloshinskii–Moriya interaction – a combination of superexchange and **spin–orbital interactions** in atomic systems. It originates from symmetry effects. The related antisymmetric spin coupling from purely symmetry grounds and the symmetric pseudodipolar magnetic interaction are estimated to be proportional to $(\Delta g/g)J$ and $(\Delta g/g)^2J$, respectively, where g is the gyromagnetic ratio and Δg is its deviation from the value for a free electron, J is the isotropic superexchange energy. For a particular spin system the allowed components of the interaction are determined by the symmetry of the spin complex. Corrections to the energy spectrum due to the interaction are usually small being proportional to D^2/Δ, where D is the magnitude of the interaction and Δ is the separation of the **singlet** and **triplet** energy levels.

This interaction is considered to be a consequence of the spin–orbital coupling in the presence of relativistic effects under peculiar structure symmetry in some crystals. Its effects can be explicitly exhibited only when an external magnetic field is applied.

First described in: I. E. Dzyaloshinskii, *A thermodynamic theory of "weak" ferromagnetism of antiferromagnetics,* J. Phys. Chem. Solids **4**(4), 241–255 (1958); T. Moriya, *Anisotropic superexchange interaction and weak ferromagnetism,* Phys. Rev. **120**(1), 91–98 (1960).

E

From (e,2e) reaction to Eyring equation

(e,2e) reaction → **(e,2e) spectroscopy**.

(e,2e) spectroscopy – very detailed analysis of electronic structures of atoms, molecules and solids, including ionization energy, electron momentum distribution and wavefunction mapping, can be obtained by means of the **(e,2e) reaction**. This is a scattering process in which a high-energy electron collides inelastically with an atomic, molecular or solid target. As a consequence, a bound target electron is ejected, and the outgoing electrons (one scattered and one knocked out) are detected. This process is very rich in information, since one can observe kinetic energies and momenta of three electrons (one primary and two secondary particles), and thus deduce some fundamental properties of the electronic structure of the target. The energies and momenta of the three electrons and of the target are interrelated by conservations laws.

More details in: M. De Crescenzi, M. N. Piancastelli, *Electron Scattering and Related Spectroscopies* (World Scientific Publishing, Singapore, 1996).

E91 protocol – the protocol for quantum cryptographic key distribution developed by A. K. **E**kert in 19**91** (the acronym uses the bold characters). Within this scheme the generalized **Bell's inequality** safeguards confidentiality in the transmission of pairs of spin-1/2 particles entangled like **Einstein–Podolsky–Rosen pairs**.

The idea consists of replacing the quantum channel carrying two **qubits** from Alice (conventional name of a sender) to Bob (conventional name of a receiver) by a channel carrying two qubits from a common source, one qubit to Alice and one to Bob. The source generates a random sequence of correlated particle pairs with one member of each pair (one qubit) being sent to each party. Spin-(1/2) particles or pairs of so-called Einstein–Podolsky–Rosen photons whose polarizations are able to be detected by the parties can be used for that.

Alice and Bob both measure their particle in two bases (two different orientations of the analyzer detecting spin orientation or photon polarization), again chosen independently and randomly. The source then announces the bases via an open channel. Alice and Bob divide results of their measurements into two separate groups: a first group for which they used different bases and a second group for which they used the same bases. Subsequently, they reveal publicly the results they obtained within the first group only. Comparing the results allows them to know whether there is an eavesdropper on their communication channel. The eavesdropper would have to detect a particle to read the signal, and retransmit it in order for his presence to remain unknown. However, the act of detection of one particle of a pair destroys its quantum correlation with the other, and the two parties can easily verify whether this has been done, without revealing the results of their own measurements, by communication over an open channel. After Alice and Bob become sure that the particles (qubits) they received are not disturbed by an eavesdropper, they can be converted into a secret string of bits representing the key. This secret key may be then used in a conventional cryptographic communication between them.

First described in: A. K. Ekert, *Quantum cryptography based on Bell's theorem*, Phys. Rev. Lett. **67**(6), 661–663 (1991).

ebit – an acronym for an **e**ntangled **bit**. It is defined as an amount of **quantum entanglement** in a two-**qubit** state maximally entangled, or any other pure bipartite state for which entropy of entanglement is 1. One ebit represents a computing resource made up of a shared **Einstein–Podolsky–Rosen pair**.

First described in: C. H. Bennett, D. P. Di Vincenzo, J. Smolin, W. K. Wootters, *Mixed-state entanglement and quantum error correction*, Phys. Rev. A **54**(5), 3824–3851 (1996).

edge states appear at a hard edge of a wire when an external magnetic field is applied perpendicular to the current flow in it. The classical behavior of electrons near the wire edge is shown in Figure E.1.

Electrons deep inside the wire execute circular **cyclotron orbits** with no net drift. Near the edge, the orbits are interrupted when the electrons hits the boundary. The result is a skipping orbit that bounces along the boundary. The electron thus acquires a net drift velocity, which is higher for orbits closer to the edge. The states on opposite edges travel in opposite directions. The states squeeze against the side of the wire with higher energy than those in the middle.



Figure E.1 Orbits of electrons in a wire placed in a magnetic field perpendicular to the electron flow in the wire.

eddy currents = **Foucault currents** – currents induced in a conducting medium subjected to a varying magnetic field. Such currents result in energy dissipation, termed eddy current loss, and a reduction of the apparent magnetic permeability of the conducting medium. In accordance with **Lenz's law**, the eddy currents circulate in such direction as to tend to prevent variation of the magnetic field.

First described by J. B. L. Foucault in 1855.

EDXS – an acronym for **energy dispersive X-ray spectroscopy**.

EELS – an acronym for **electron energy loss spectroscopy**.

effective mass (of charge carriers) is a characteristic of an extremum point at an electron energy band represented by the **dispersion curve** $E(k)$. A Taylor expansion of $E(k)$ around the extremum at $k = k_0$ and ignoring the high-order terms gives:

$$E(k) = E_0 + \frac{\hbar^2 (k - k_0)^2}{2m^*},$$

with

$$m^* = \hbar^2 \left(\frac{\mathrm{d}^2 E}{\mathrm{d}k^2} |_{k=k_0} \right)^{-1}$$

referred to as the effective mass of charge carriers occupying the band.

The effective mass is evidently inversely proportional to the curvature of $E(k)$ at $k = k_0$. Unlike the gravitational mass, the effective mass can be positive, negative, zero, or even infinite. An infinite effective mass corresponds to an electron localized at a lattice site. In this case, the electron bound to the nucleus assumes the total mass of the crystal. A negative m^* corresponds to a concave downward band and means that the electron moves in the opposite direction to the applied force. If the band structure of a solid is anisotropic, the effective mass becomes a tensor, characterizing by its m_x^*, m_y^*, m_z^* components. The average effective mass in this case can be calculated as $m^* = (m_x^* m_y^* m_z^*)^{1/3}$.

Four types of critical points, namely M_0, M_1, M_2, and M_3, are distinguished as a function of the sign of the effective mass components in a particular point of the **Brillouin zone** with a zero energy-gradient on k. In the M_0 critical point all three components are positive. In the M_1 and M_2 one and two components, respectively, are negative. In the M_3 point all three components are negative.

effective mass approximation supposes that the structure of energy bands $E(k)$ near extremum points, which are minima in conduction bands and maxima in valence bands, has a parabolic character well described within an assumption that they are formed by electrons or holes with an effective mass m^*, i.e. $E(k) = \hbar^2 k^2 / 2m^*$.

effective Rabi frequency → **Rabi frequency**.

effusion – a molecular flow of gases through an aperture when the molecules do not collide with each other as they escape through the aperture.

effusion (Knudsen) cell – the unit used in **molecular beam epitaxy** machines to create an atomic or molecular beam. It is schematically shown in Figure E.2.

An appropriate solid source material is loaded inside a cylindrical cell with a very small orifice and heated until it vaporizes. As the vapor escapes from the cell through the small nozzle, its atoms or molecules form a well-collimated beam, since the ultrahigh vacuum environment outside the cell allows them to travel without scattering.



Figure E.2 Effusion (Knudsen) cell.

Efimov quantum states – a universal set of bound **trimer** states appearing for three identical **bosons** with a resonant two-body interaction. These states should even exist in the absence of a corresponding two-body bound state.

First described in: V. Efimov, *Energy levels arising from resonant two-body forces in a three-body system,* Phys. Lett. B **33**(8), 563–564 (1970); V. Efimov, *Weakly bound states of three resonantly interacting particles,* Sov. J. Nucl. Phys. **12**, 589–595 (1971) – theoretical prediction.

EFM – an acronym for **electrostatic force microscopy**.

Ehrenfest adiabatic law states that if the **Hamiltonian** of a system undergoes an infinitely slow change and if the system is initially in an eigenstate of the Hamiltonian, then at the end of the change it will be in the eigenstate of the new Hamiltonian that derives from the original state by continuity, provided certain conditions are met.

First described in: P. Ehrenfest, *Adiabatische Invarianten und Quantentheorie,* Ann. Phys. **51**, 327–352 (1916).

Ehrenfest theorem states that the motion of a quantum mechanical **wave packet** will be identical to that of the classical particle it represents, provided that any potentials acting upon it do not change appreciably over the dimensions of the packet. In this interpretation, the position and momentum of the particle are replaced by their quantum mechanical expectation values.

First described in: P. Ehrenfest, *Bemerkung über die angenäherte Gültigkeit der klassischen Mechanik innerhalb der Quantenmechanik*, Z. Phys. **45**(7/8), 455–457 (1927).

Ehrlich–Schwoebel effect – an asymmetry in the adatom attachment and detachment to and from atomic steps on crystal surfaces. The steps capture atoms diffusing on the surface with certain probabilities and, in addition, the capture probability depends on the direction from which adsorbed atoms approach the step.

First described in: G. Ehrlich, F. G. Hudda, *Atomic view of surface self-diffusion: tungsten on tungsten*, J. Chem. Phys. **44**(3), 1039–1049 (1966); R. L. Schwoebel, E. J. Shipsey, *Step motion on crystal surfaces*, J. Appl. Phys. **37**(10), 3682–3686 (1966).

eigenfunction – was initially introduced in relation to the mathematics of function spaces or **Hilbert spaces**. The concept is a natural generalization of the notion of an eigenvector of a linear operator in a finite dimensionally linear vector space.

The eigenfunction, or characteristic function, is related to a linear operator defined on a given vector space of functions on some specified domain. If a function f, being not the null function of the functional space, is mapped by the operator **O** into a multiple of itself, that is $\mathbf{O}f = af$, where a is a scalar, f is said to be an eigenfunction of **O** belonging to the **eigenvalue** a.

Eigenfunctions find wide physical applications in classical field theories but they appear to be best known for their extensive use in Schrödinger's formulation of quantum mechanics.

eigenstate – a state of a quantum system for which the observables in some commuting, and hence simultaneously measurable, set have definite values, in the orthodox interpretation of the theory. It is a **wave function** in quantum mechanics.

eigenvalue = **energy (in quantum mechanics)**.

Einstein–Bohr equation defines the frequency of the radiation emitted or absorbed by a system when it undergoes a transition from one energy state to another as $\nu = \Delta E/h$, where ΔE is the energy difference between the states.

First described in: A. Einstein, *Über einen die Erzeugung und Verwandlung des Lichtes betreffenden heuristischen Gesichtspunkt*, Ann. Phys. **17**, 132–148 (1905); N. Bohr, *On the constitution of atoms and molecules*, Phil. Mag. **26**, 1–25 (1913).

Einstein–de Haas effect – axial rotation of a rod of a magnetic material, which occurs when the rod experiences a magnetic field applied parallel to its axis. Sometimes it also called the **Richardson effect** after Richardson who first predicted such behavior of magnetic materials.

First described in: A. Einstein, W. J. de Haas, *Experimenteller Nachweis der Ampereschen Molekularströme*, Dtsch. Phys. Ges., Verh. **17**(8), 152–170 (1915).

Einstein frequency – a single frequency with which each atom vibrates independently of the other atoms in the model of lattice vibrations. It is equal to the frequency observed in infrared absorption studies.

Einstein photochemical equivalence law → **Stark–Einstein law**.

Einstein photoelectric law states that the energy of an electron emitted from a system in the **photoelectric effect** is $(h\nu - W)$, where ν is the frequency of the incident radiation, W is the energy needed to remove the electron from the system. If $h\nu < W$, no electrons are emitted.

First described in: A. Einstein, *Über einen die Erzeugung und Verwandlung des Lichtes betreffenden heuristischen Gesichtspunkt*, Ann. Phys. **17**, 132–148 (1905).

Recognition: in 1921 A. Einstein received the Nobel Prize in Physics for his services to Theoretical Physics, and especially for his discovery of the law of the photoelectric effect.

See also www.nobel.se/physics/laureates/1921/index.html.

Einstein–Podolsky–Rosen pair – nonlocal pairwise entangled quantum particles → **quantum entanglement**. There is a strong correlation between characteristics of presently noninteracting members of a pair that have interacted in the past. Such nonlocal correlations occur only when the quantum state of the entire system is entangled.

First described in: A. Einstein, B. Podolsky, N. Rosen, *Can quantum mechanical description of physical reality be considered complete?* Phys. Rev. **47**(5), 777–780 (1935).

Einstein–Podolsky–Rosen paradox assumes as a necessary property for a physical theory to be complete that every element of the physical reality must have a counterpart in the physical theory. Originally it was formulated as ''If, without in any way disturbing a system, we can predict with certainty (that is with probability equal to unity) the value of a physical quantity, then there exists an element of physical reality corresponding to this physical quantity''. It is a sufficient condition for an element of physical reality. It means that if two quantum particles are in an entangled state, then a measurement of one can affect the state of the other instantaneously, even if they are separated.

First described in: A. Einstein, B. Podolsky, N. Rosen, *Can quantum mechanical description of physical reality be considered complete?* Phys. Rev. **47**(5), 777–780 (1935).

Einstein relationship = **Einstein–Smoluchowski equation**.

Einstein's coefficients A and B denote rates of **absorption** and **stimulated emission** per unit electromagnetic energy density (within the frequency interval between ν and $\nu + \Delta\nu$) due to the transition of an electron between the level i and another level j – the coefficient B_{ij}, and the rate for **spontaneous emission** of radiation due to transition from the level i to the level j – the coefficient A_{ij}. For two nondegenerate levels in a medium with a refractive index n the coefficients are related as: $B_{ij} = B_{ji}$, $A_{ij} = 8\pi h\nu^3 n^3 c^{-3} B_{ij}$. The total emission rate of radiation from the level i to the level j for a system in thermal equilibrium at a given temperature is $R_{ij} = A_{ij} + B_{ij}\rho_e(\nu) = A_{ij}(1 + N_p)$, where $\rho_e(\nu)$ is the photon energy density and N_p is the photon occupation number.

First described in: A. Einstein, *Strahlungs-Emission and -Absorption nach der Quantentheorie*, Verh. Deutsch. Phys. Ges. **18**, 318–323 (1916); A. Einstein, *Zur Quantentheorie der Strahlung*, Phys. Z. **18**, 121–128 (1917).

Einstein shift – a shift toward longer wavelengths of spectral lines emitted by atoms in strong gravitational fields.

Einstein–Smoluchowski equation states that the relation between diffusivity D of a particle and its mobility μ at the absolute temperature T is $D/\mu = k_B T/e$.

First described in: A. Einstein, *Über die von der molekularkinetischen Theorie der Wärme geforderte Bewegung von in ruhenden Flüssigkeiten suspendierten Teilchen*, Ann. Phys. **17**, 549–560 (1905); M. Smoluchowski, *Molekular-kinetische Theorie der Opaleszenz von Gasen im kritischen Zustande, sowie einiger verwandter Erscheinungen*, Ann. Phys. **25**, 205–226 (1908).

elastic moduli of crystals connect stresses and strains in a crystal. The coefficients of proportionality between the stresses and the strains, that is when the stresses are expressed in terms of the strains, are known as the crystal elastic **stiffness constants**. Another set of coefficients, which are crystalline **compliance constants**, is obtained when the strains are written in terms of the stresses.

elastic scattering – a scattering process in which the total energy and momentum of interacting (colliding) particles are conserved. The alternative is **inelastic scattering**.

electret – a dielectric body which retains an electric momentum after an externally applied electric field has been reduced to zero.

electrochromism – a color change of matter caused by an electric current.

electroluminescence – light emission from a solid excited by injection of electrons and holes via an external electric current. G. Destriau first coined the word ‘‘electroluminescence’’ to refer to the light emission he observed from zinc sulfide phosphors when excited by an electric field → **Destriau effect**.

First described in: H. J. Round, *A note on carborundum*, Electr. World **19** (February 9), 309 (1907).

electrolyte – a substance in which electric charges are transported by ions. Those ions bearing a negative charge called **anions**, while whose carrying a positive charge are called **cations**.

electromigration – net motion of atoms caused by the passage of an electric current through matter.

First described in: M. Gerardin, *De l'action de la pile sur lessels de potasse et de soude et sur les alliages soumis à la fusion ignée,* C. R. Acad. Sci. **53**, 727 (1861).

electron – a stable negatively charged elementary particle having a mass of 9.10939×10^{-31} kg, a charge of 1.602177×10^{-19} C, and a spin of 1/2.

Term coined by: G. J. Stoney, *Of the "Electron," or Atom of Electricity,* Phil. Mag. **38**, 418–420 (1894).

First described in: J. J. Thomson, *Cathode rays,* Phil. Mag. **44**(269), 293–316 (1897); J. J. Thomson, *On the mass of ions in gases at low pressures,* Phil. Mag. **48**(295), 547–567 (1899).

Recognition: in 1906 J. J. Thomson received the Nobel Prize in Physics in recognition of the great merits of his theoretical and experimental investigations on the conduction of electricity by gases.

See also www.nobel.se/physics/laureates/1906/index.html.

electron affinity – an energy distance between the bottom of the conduction band of a semiconductor or isolator and the energy level in a vacuum.

electron affinity rule → **Anderson's rule**.

electron-beam lithography – a technique for patterning integrated circuits and semiconductor devices by the use of an electron beam. A typical electron beam lithography machine includes a vacuum column with an electron source, accelerating electrodes, magnetic lenses, and a steering system. The electron beam formation system produces a flux of electrons accelerated to energies in the range 20–100 keV and focused into a spot of 0.5–1.5 nm in diameter. A conventional **scanning electron microscope** or scanning transmission electron microscope providing these facilities is often used for electron beam nanolithography. Moreover, conducting probes of a **scanning tunneling microscope** or **atomic force microscope** can be employed for low-energy electron exposure as well. The fundamental resolution limit is given by **Heisenberg's uncertainty principle**. Patterning below 10 nm is achievable.

The electron beam is scanned over the resist-covered surface exposing certain regions and avoiding others under the control of a computer pattern generator. The most frequently used organic positive resist is PMMA (poly(methylmethacrylate)), a long-chain polymer. Where the electron beam hits the resist the chain length is shortened and the polymer can then be easily dissolved away in an appropriate developer. The threshold of sensitivity to the electron exposure is around 5×10^{-4} C cm^{-2}.

Among organic negative resists, **calixarene** (MC6AOAc–hexaacetate *p*-methyl calixarene) and α-methylstyrene best meet the requirements of nanolithography, showing high durability against plasma etching. Calixarene has a cyclic structure in the form of a ring-shaped molecule about 1 nm in diameter. Its main component is a phenol derivative, which seems to have high durability and stability, originating from the strong chemical coupling of the benzene ring. Calixarene is almost 20 times less sensitive to electron exposure than PMMA. Meanwhile, Cl methylated calixarene, which is one of the calixarene derivatives where Cl atoms replace methyl groups of the calixarene, has practically the same sensitivity. The small size of the calixarene molecule and high molecule uniformity result in surface smoothness of the resist film and in ultrahigh resolution.

PMMA, calixarene and α-methylstyrene resist films with a typical thickness of 30–50 nm provide formation of nanopatterns with a resolution of 6–10 nm. Other polymer electron beam resists, such as positive resist ZEP, developed by Nippon Zeopn Company and negative resist SAL601 from Shipley Company have similar characteristics. The resolution limit of organic resists is set by low-energy secondary electrons (up to 50 eV), which are generated by a primary beam on impact with these materials. The secondary electrons expose the resist material around the beam to a distance of about 3–5 nm thus giving a writing resolution limit close to 10 nm.

Besides organic materials, inorganic compounds, such as SiO_2, AlF_3-doped LiF and NaCl, have shown good prospects as resist materials for electron beam nanopattern fabrication. They are promising to achieve sub-5-nm resolution level but their sensitivity, characterized by the threshold of sensitivity to the electron exposure above 0.1 C cm^{-2}, remains too small.

Direct nanopatterning of SiO_2 by an electron beam is indeed attractive for device fabrication. It can be realized with the use of oxide films less than 1 nm thick. Irradiation of such ultrathin films is performed by a focused electron beam at room temperature. The irradiated local regions are then decomposed and evaporated by annealing at 720–750°C in high vacuum. This method is attractive for *in situ* fabrication of nanostructures, because all processes of the SiO_2 mask formation, and subsequent deposition of other materials can be performed in an ultra high vacuum chamber without taking the sample out into air.

In conventional electron beam lithography, with electrons having energy in the range of 20–50 keV, the major resolution restrictions come from secondary electrons and electrons backscattered from the substrate. Furthermore, penetrating into the substrate, such energetic electrons generate radiation damages there. These effects can be significantly suppressed by using low-energy electron beams in the range of 2–10 keV. It is achieved at the expense of the decrease in the resist sensitivity and related increase of the exposed dose.

Once the resist mask is fabricated, two principle approaches can be used in order to transfer the resist pattern into features of metal, dielectric or semiconductor layers on the substrate. It can be done by etching to remove material in the windows of the resist mask or by material deposition onto developed resist mask.

The first approach is typical for conventional semiconductor technology. So far the etching rate of PMMA and calixarene is comparable to that of silicon and other electronic materials, and their durability is sufficient to fabricate dielectric and semiconductor nanostructures by plasma dry etching.



Figure E.3 Nanostructure fabrication by lift-off process with the use of positive electron resist (PMMA): (a) electron beam exposure of the resist film, (b) development of the resist, (c) metal deposition, (d) lift-off of the resist with the metal on its surface.

The second approach is also, known, as a **lift-off process**. It is mainly involved in fabrication of metal nanosize elements. The main steps of the process are shown in Figure E.3.

The resist film, usually spin-on deposited onto the substrate, is first exposed by a single pass of the electron beam. Then it is developed to form the windows in the film. Metal is evaporated onto the patterned surface in a direction normal to it in order to coat the resist and the substrate surface in the windows. After this the substrate is immersed in a powerful solvent, which dissolves the unexposed resist (for example, acetone for PMMA) with the metal deposited on top of it. The undesired metal is removed, leaving behind a copy of the elements that were initially patterned in the resist. The metal islands left can be used as an element of nanoelectronic devices or as a mask for etching semiconductor or dielectric films beneath it.

Electron beam lithography is being constantly developed. Nevertheless, its readiness for insertion into pilot production lines is less than satisfactory. The low speed of electron-beam wafer processing remains a major concern. Several advanced lithography schemes, based on the use of low-energy electrons are being developed. One of them proposes the application of arrays of microcolumn electron-beam guns. Many guns working in parallel significantly increase the throughput of the lithographic system. Further developments in applications of low-energy electrons for the fabrication of nanostructures are also expected using rapidly improving proximal probe techniques.

electronegativity – a qualitative measure of "power of an atom in a molecule to attract electrons to itself". A difference in electronegativity between atoms A and B is regarded as a measure of the degree of the electron transfer from atom A to atom B on forming the chemical bond between them. More electronegative atoms attract electrons more efficiently.

electron energy eigenstate = **energy level**.

electron energy loss spectroscopy (EELS) – energy-resolved registration of electrons passed through matter. When an electron beam is incident into a specimen, some electrons are inelastically scattered and lose a part of their energy. The energy loss is a fingerprint of a particular chemical element and particular atomic bonding. Thus, elemental composition and atomic bonding states in solids can be determined. It is usually realized with a spectroscope attached under the sample holder in an electron microscope.

More details in: M. De Crescenzi, M. N. Piancastelli, *Electron Scattering and Related Spectroscopies* (World Scientific Publishing, Singapore, 1996).

electronic band structure – a diagram presenting variation of the electron energy E in a solid as a function of the wave vector k. Since $E(k)$ is periodic in crystalline solids, the presentation is usually done within the first **Brillouin zone**.

electronic polarization → **polarization of matter**.

electron magnetic resonance (EMR) = **electron paramagnetic resonance**.

electron microscopy – an analytical imaging technique, whereby a beam of accelerated (up to 10–200 keV) electrons is directed onto a sample for analysis, and reflected or transmitted electrons are collected over a narrow solid angle and focused by electronic or magnetic lenses onto the image plane, thus providing an enlarged version of the sample structure. Scanning of the probing electron beam is employed in order to enlarge the analyzing area.

Among the variety of the techniques, **scanning electron microscopy (SEM)** and **transmission electron microscopy (TEM)** are distinguished in principle. SEM produces images by detecting scattered or secondary electrons which are emitted from the surface of a sample due to excitation by the primary electron beam. TEM forms images by detecting electrons that are transmitted through the sample. Generally, the space resolution of TEM (reaching atomic level) is about an order of magnitude better than that of SEM. TEM analysis usually needs sample thinning in order to make the sample transparent for probing electrons. SEM requiers no special sample preparation, except deposition of thin conductive film when the sample itself does not have appropriate conductivity for leaking the charge brought about by probing electrons.

First described in: M. Knoll, E. Ruska *Beitrag zur geometrischen Elektronenoptik I und II*, Ann. Phys. **12**, 607–640, 641–661 (1932).

Recognition: in 1986 E. Ruska received the Nobel Prize in physics (shared with G. Binning and H. Rohrer) for his fundamental work in electron optics, and for the design of the first electron microscope.

See also www.nobel.se/physics/laureates/1986/index.html.

electron-optical configuration for nanodiffraction – an **electron microscope** technique able to produce a **diffraction** pattern from an area of material just 10 nm in diameter with unprecedented precision. The configuration utilizes one of the round lenses in an objective prefield **aberration** corrector. The method allows one to tune carefully the size of the diffracting area to the features of interest in a particular material, excluding the surrounding material.

First described in: C. Dwyer, A. I. Kirkland, P. Hartel, H. Müller, M. Haider, *Electron nanodiffraction using sharply focused parallel probes*, Appl. Phys. Lett. **90**, 151104 (2007).

electron paramagnetic resonance (EPR) – a process of resonant absorption of microwave radiation by paramagnetic ions or molecules with at least one unpaired electron spin in the presence of a static magnetic field. It arises from the magnetic moment of unpaired electrons in a **paramagnetic** substance or in a paramagnetic center in a **diamagnetic** substance. Such resonance is used in a radiofrequency spectroscopy in which transitions among the energy levels of a system of weakly coupled electronic magnetic dipole moments in a magnetic field are detected.

It is also known as **electron spin resonance (ESR)** or **electron magnetic resonance (EMR)**.

First described in: E. K. Zavoisky, *The paramagnetic absorption of a solution in parallel fields*, Zh. Exp. Teor. Fiz. **15**(6), 253–257 (1945) – in Russian.

More details in: J. E. Wertz, J. R. Bolton, *Electron Spin Resonance: Elementary Theory and Practical Applications*, (Chapman and Hall, New York, 1986).

electron spectroscopy for chemical analysis (ESCA) = **X-ray photoelectron spectroscopy (XPS)**.

electron spin resonance (ESR) = **electron paramagnetic resonance**.

electrooptical Kerr effect → **Kerr effects**.

electrophoresis – the electrokinetic phenomenon consisting in motion of charged particles or agglomerates through a static liquid under the influence of an applied electric field.

More details in: A. T. Andrews, *Electrophoresis* (Clarendon Press, Oxford, 1986).

electrostatic force microscopy – detection of electrostatic forces with an **atomic force microscope**. In this technique tip and sample are regarded as two electrodes of a capacitor. If they are electrically connected and have different **work functions**, electrons will flow between tip and sample until their Fermi levels are equalized. As a result, an electric field and, consequently, an attractive electrostatic force exists between them at zero bias. This contact potential difference can be balanced by applying an appropriate bias voltage. It has been demonstrated that individual doping atoms in semiconducting materials can be detected by electrostatic interactions due to the local variation of the surface potential around them. Meanwhile, in practical applications, the technique is usually used to visualize the distribution of electric potential, charge, contact potential difference and their related characteristics of solid surfaces.

First described in: Y. Martin, D. V. Abraham, H. K. Wickramasinghe, *High-resolution capacitance measurement and potentiometry by force microscopy*, Appl. Phys. Lett. **52**(13), 1103–1105 (1988).

More details in: Roadmap of Scanning Probe Microscopy, edited by S. Morita (Springer Verlag, Berlin Heidelberg, 2007).

electrostriction – elastic deformation of a dielectric caused by the force produced, when the dielectric is placed in an inhomogeneous electric field.

Elliott–Yafet mechanism – the electron spin relaxation mechanism in solids, which results from spin–orbit scattering during collisions with phonons or impurities. The related spin relaxation time τ_s in semiconductors can be determined analytically using approximations of the band and phonon structures, as most important states are usually around high-symmetry points. The spin relaxation of conduction electrons with energy E_k in this case is described by

$$\frac{1}{\tau_s(E_k)} = A\left(\frac{\Delta_{so}}{E_g + \Delta_{so}}\right)^2 \left(\frac{E_k}{E_g}\right)^2 \frac{1}{\tau_p(E_k)},$$

where $\tau_p(E_k)$ is the momentum scattering time at energy E_k, E_g is the energy gap, and Δ_{so} is the spin–orbit splitting of the valence band. The numerical factor A, which is of order 1, depends on the dominant scattering mechanism (charge or neutral impurity, phonon, electron-hole).

The mechanism is important for small-gap semiconductors with large spin-orbit splitting. The temperature dependence of $1/\tau_s$ for metals and degenerate semiconductors follows the dependence of $1/\tau_p$. In metals this means a constant at low T and a linear increase at large T. For nondegenerate semiconductors,

$1/\tau_s(T) \sim T^2/\tau_p(T)$. In the important case of scattering by charged impurities ($\tau_p(T) \sim T^{3/2}$), $1/\tau_s(T) \sim T^{1/2}$.

First described in: R. J. Elliott, *Theory of the effect of spin–orbit coupling on magnetic resonance in some semiconductors*, Phys. Rev. **96**(2), 266–279 (1954); Y. Yafet, *g-factors and spin lattice relaxation of conduction electrons*, in: Solid State Physics, vol. **14**, edited by F. Seitz, D. Turnbull (Academic Press, New York, 1963), p. 1–98.

More details in: I. Žutić, J. Fabian, S. Das Sarma, *Spintronics: fundamentals and applications*, Rev. Mod. Phys. **76**(2), 323–410 (2004).

ellipsometry – a procedure for determining the nature of a specular surface from the change of the polarization state of the polarized light beam when it reflects from this surface.

First described in: P. Drude, *Zur Elektronentheorie der Metalle*, Ann. Phys. **36**, 566–613 (1889).

elliptical polarization of light → **polarization of light**.

embedded-atom method – the semiempirical technique for description of an atomic interaction in solids based on the **local density approximation**. The energy of each atom in a monoatomic solid is given by $E(r_0) = F(n_1 \rho^\alpha(r_0)) + 0.5 n_1 V(r_0)$ where r_0 is the first-neighbor distance, n_1 is the number of first neighbors, ρ^α is the spherically averaged atomic electron density at a distance r from the nucleus, V is the energy of atom-atom pair interaction and F is the embedding function. The method is used for molecular dynamics simulation of deformed crystals.

First described in: M. S. Daw, M. J. Baskes, *Applications of the embedded-atom method to covalent materials*, Phys. Rev. B **29**(11), 6443–6449 (1984).

embossing – one of the approaches used for a pattern fabrication by **imprinting**. The idea of the embossing process is that a reusable mold is stamped at high pressure into a polymer film on a heated substrate, and then removed. It is schematically illustrated in Figure E.4.

The mold is made so that it has desired topographic features raised from the surface. It is coated with a very thin film of mold release compound in order to protect its surface and prevent sticking during embossing. The substrate to be patterned is coated with a thin film of thermoplastic polymer. The substrate is heated above the glass transition temperature of the polymer to make it viscoelastic. The mold is then pressed into the polymer. The heating time and the pressure hold time last typically a few minutes each. After that the system is cooled back down below the glass transition temperature. The pattern freezes into the polymer film. After removal of the imprinter, the trenches formed are cleaned with either an oxygen plasma or solvents to remove any residual polymer from their bottom. The patterned polymer film is used as a mask for subsequent etching or lift-off process.

The most frequently used polymer is poly(methylmethacrelate) (PMMA), a well-known resist for electron beam lithography. Its good imprint properties



Figure E.4 Imprint process by embossing: (a) substrate with deposited resist film and master prior to imprinting, (b) imprinting, (c) patterned resist mask after imprinting with a residual polymer in the windows, (d) etching of the residual polymer.

are determined by an appropriate viscoelasticity of this material. PMMA has a glass transition temperature of about 105°C, thus providing good imprints in the temperature range of 190–200°C. Demounting and separation of the mold and substrate take place when both are at about 50°C. The ultimate resolution is of the order of 10 nm. It is limited by the radius of gyration of the polymer.

First described in: S. Y. Chou, P. R. Krauss, P. J. Renstrom, *Imprint of sub-25 nm vias and trenches in polymers,* Appl. Phys. Lett. **67**(21), 3114–3116 (1995).

EMR – an acronym for an **electron magnetic resonance** = **electron paramagnetic resonance**.

emulsion – a system containing two substantially immiscible liquids, one of which (the ‘‘internal’’ or ‘‘disperse’’ phase) is subdivided as fine droplets within the other (the ‘‘external’’ or ‘‘continuous’’ phase).

enantiomers → **chirality** and **isomers**.

enantiomorphs → **chirality**.

energy dispersive X-ray spectroscopy (EDXS) – registration of characteristic X-ray radiation excited by energetic electron bombardment of matter. The characteristic radiation arises when the incident electron transfers to an inner orbital electron the energy in excess of its binding energy, the orbital electron is ejected from the atom and the X-ray photon is generated when the vacancy is filled by an electron from the deeper inner orbital. As each chemical element has a unique electronic structure, the series of X-ray photons generated are characteristic of the particular element. The intensity of the X-rays is proportional to the number of atoms generating the rays. Thus, the energy dispersive analysis of the characteristic X-ray radiation is used for qualitative and quantitative study of matter.

engineering – an application of scientific principles to the exploitation of natural resources, to the design and production of commodities and to the provision and maintenance of utilities.

entanglement → **quantum entanglement**.

entanglement monotone – a minimum number of nonincreasing parameters characterizing quantum nonlocal resources of a **qubit** system.

First described in: G. Vidal, *Entanglement of pure states for a single copy*, Phys. Rev. Lett. **83**(5), 1046–1049 (1999).

entangled state – a state of a composite system whose parts can be spatially delocalized. Such states can have intrinsically nonlocal correlations. For more details → **quantum entanglement**.

enthalpy – a quantity conveniently expressing results of thermodynamic processes occurring under certain special conditions. It has the dimensions of energy and is also called heat content. A value of enthalpy for any system in a definite state depends only upon the state and not upon its prehistory, that is upon the way by which the system has evolved into this state.

entropy – a measure of the capacity of a system to undergo a spontaneous change. The term derives from the Greek expression for ‘‘transformation’’. Two consistent definitions of entropy are possible: thermodynamic and statistical. According to the thermodynamic definition, the entropy S defined by its change $\mathrm{d}S = \delta Q_{rev}/T$. That is, the entropy change in an infinitesimal process is equal to the heat absorbed divided by the absolute temperature at which the heat is absorbed. The heat absorbed must be that characteristic of a reversible process, if entropy is to be a state function, that is $\Delta S = S_2 - S_1$. From the statistical point of view $S = k_B \log \Omega + \text{constant}$, where Ω is the probability defined as the number of configuration states available to the system.

First described in: R. Clausius *Abhandlungen über die mechanische Wärmetheorie* (Friedrich Vieweg und Sohn, Braunschweig, 1864).

envelope function method is based on a plane wave expansion

$$\psi(\mathbf{r}) = \sum_{kG} \tilde{\psi}(\mathbf{k}+\mathbf{G}) \exp(\mathrm{i}(\mathbf{k}+\mathbf{G}) \cdot \mathbf{r}) = \sum_{kG} \tilde{\psi}(\mathbf{k}) \exp(\mathrm{i}(\mathbf{k}+\mathbf{G}) \cdot \mathbf{r}),$$

where the **G** are reciprocal lattice vectors of an underlying **Bravais lattice** and the **k** are wavevectors confined to a primitive cell of the reciprocal lattice usually taken as the first **Brillouin zone**. $\tilde{\psi}(\mathbf{k}+\mathbf{G})$ is the Fourier transform of ψ and $\tilde{\psi}(\mathbf{k})$ is an alternative notion that emphasizes the decomposition of the wavevector $\mathbf{k}+\mathbf{G}$ into a reciprocal lattice vector and a wavevector in the primitive cell. A complete set of functions, $U_n(\mathbf{r})$, periodic in the Bravais lattice, is introduced

$$U_n(\mathbf{r}) = \sum_G U_{nG} \exp(\mathrm{i}\mathbf{G} \cdot \mathbf{r})$$

usually chosen to be orthonormal so that expressing the plane waves in terms of them one has:

$$\exp(\mathrm{i}\mathbf{G} \cdot \mathbf{r}) = \sum_n U_{nG}^{*} U_n(\mathbf{r}).$$

Substitution for $\exp(\mathrm{i}\mathbf{G} \cdot \mathbf{r})$ finally gives

$$\psi(\mathbf{r}) = \sum_n F_n(\mathbf{r}) U_n(\mathbf{r}),$$

with the envelope functions, $F_n(\mathbf{r})$, given by

$$F_n(\mathbf{r}) = \sum_{kG} U_{nG}^{*} \tilde{\psi}(\mathbf{k}+\mathbf{G}) \exp(\mathrm{i}\mathbf{k} \cdot \mathbf{r}) = \sum_{kG} U_{nG}^{*} \tilde{\psi}_G(\mathbf{k}) \exp(\mathrm{i}\mathbf{k} \cdot \mathbf{r}),$$

which describes the slowly varying mesoscopic part of the locally highly oscillating microscopic wave functions. This expansion was introduced by Luttinger and Kohn to derive the **effective mass** equation for periodic structures in the presence of a slow perturbing potential. Thus it has sometimes been called the effective mass representation. Later Bastard introduced a prescriptive envelope function method in the case of **superlattices**, in which the real space equations satisfied by the envelope functions were equivalent to the $\mathbf{k} \cdot \mathbf{p}$ method, but the band edges were allowed to be functions of position, implicitly assuming that the equations would be valid at any atomically abrupt interfaces. Only the envelope of the nanostructure wavefunction is described, regardless of the atomic details. Despite the numerous assumptions involved, the envelope function approximation has had great success, mainly due to a fair compromise between the simplicity of the method and the reliability of the results. A method for deriving an exact envelope functions equation starting from the **Schrödinger** equation appropriate for the calculation of electronic states and photonic modes in nanostructures has been introduced by M. G. Burt.

First described in: J. M. Luttinger, W. Kohn, *Motion of Electrons and Holes in Perturbed Periodic Field,* Phys. Rev. **97**(4), 869–833 (1955) – introduction of the method of developing an ‘‘effective mass’’ equation for electrons moving in a perturbed periodic structure. G. Bastard, *Superlattice band structure in the envelope function approximation*, Phys. Rev. B **24**(10) 5693–5697 (1981) – application to superlattices. M. G. Burt, *An exact formulation of the envelope function method for the determination of electronic states in semiconductor microstructures*, Semicond. Sci. Techn. **3**(8), 739–753 (1998) – application to nanostructures.

More details in: M. G. Burt, *Fundamentals of envelope function theory for electronic states and photonic modes in nanostructures*, J. Phys: Condens. Matter **11**(9), R53–R83 (1999); A. Di Carlo, *Microscopic theory of nanostructured semiconductor devices: beyond the envelope-function approximation*, Semicond. Sci. Technol. **18**(1), R1–R31 (2003).

enzyme – a **protein** molecule partly associated with a nonprotein portion, the **coenzyme** or **prosthetic group**. It is a biocatalyst controlling all reactions within living organisms.

More details in: H. Bisswanger, *Proteins and enzymes*, in: *Encyclopedia of Applied Physics*, Vol. 15, edited by G. L. Trigg (Wiley-VCH, Weinheim, 1996).

epitaxy – a crystal growth onto a monocrystalline substrate. The term is derived from the Greek words *epi*, meaning ‘‘on’’, and *taxis*, meaning ‘‘orderly arrangement’’. For epitaxy techniques → **solid phase epitaxy, liquid phase epitaxy, chemical vapor deposition** and **metal-organic chemical vapor deposition, molecular beam epitaxy, chemical beam epitaxy**.

More details in: M. A. Herman, *Epitaxy* (Springer Verlag, Berlin, 2004).

EPR – an acronym for an **electron paramagnetic resonance**.

equation of state – a mathematical expression which defines the physical state of a homogeneous substance, that is gas, liquid or solid, by relating its volume to pressure and absolute temperature for a given mass of the material.

equivalent circuit – a representation of a real circuit or transmission system by a network of lumped elements.

ergodic hypothesis – the assumption that in the course of time a system will take up the totality of microstates compatible with the macroscopic conditions. It has been shown that this assumption cannot be justified mathematically and the original hypothesis has been replaced by a less strict formulation, the so called quasi ergodic hypothesis. This only requires that the phase curve of the system, that is the time succession of the system state represented in the phase space, should approximate as closely as may be desired to the energy surface in the phase space.

First described in: J. C. Maxwell *On the dynamical theory of gases*, Phil. Trans. R. Soc. Lond. **157**, 49 (1867); L. Boltzmann, *Studien über das Gleichgewicht der lebendigen Kraft zwischen bewegten materiellen Punkten*, Wiener Berichte **58**, 517 (1868).

ergodicity – property of a system that ensures equality of statistical ensemble averages and time averages, along the trajectory of the system through phase space.

Ericson fluctuations – reproducible fluctuations of nuclear reaction cross sections as a function of the nuclear reaction energy. They occur in the "continuum" regime when a large number of compound nuclear states overlap, owing to the short lifetime of the compound nucleus.

First described in: T. Ericson, *Fluctuations of nuclear cross sections in the "continuum" region*, Phys. Rev. Lett. **5**(9), 430–431 (1960).

error function $\mathrm{erf}(z) = 2/\sqrt{\pi}\int_0^z \exp(-y^2/2)\mathrm{d}y$, the complementary error function is $\mathrm{erfc}(z) = 1 - \mathrm{erf}(z)$.

ESCA – an acronym for **electron spectroscopy for chemical analysis**.

ESR – an acronym for **electron spin resonance** = **electron paramagnetic resonance**.

esters – organic compounds that are alcohol derivatives of carboxylic acids. Their general formula is RCOOR′, where R may be a hydrogen, alkyl group ($-C_nH_{2n+1}$), or aromatic ring, and R′ may be an alkyl group or aromatic ring but not a hydrogen.

Ettingshausen coefficient → **Ettingshausen effect**.

Ettingshausen effect – if a conductor carries a current density $\mathbf{J}$ in a transverse magnetic field $\mathbf{H}$, a temperature gradient appears in a direction normal to both. Assuming the heat current to be zero $\nabla_t T = P\mathbf{J}x\mathbf{H}$, where P is the **Ettingshausen coefficient**.

First described in: A. von Ettingshausen, W. Nernst, *Über das Auftreten electromotorischer Kräfte in Metallplatten, welche von einem Wärmestrome durchflossen werden und sich im magnetischen Felde befinden*, Ann. Phys. **265**(10), 343 (1886).

Ettingshausen–Nernst effect → **Nernst effect**.

eukaryote – an organism possessing a nucleus with a double layer of membrane and other membrane-bound organelles. It includes such unicellular or multicellular members as all members of the protist, fungi, plant, and animal kingdoms. The name came from the Greek root "karyon", meaning "nut", combined with the prefix "eu-" meaning "good" or "true".

Euler equations of motion describe motion of a mechanical system consisting of connected particles. Basically they are forms of the two vector equations $\mathrm{d}\mathbf{p}/\mathrm{d}t = \mathbf{R}$ and $\mathrm{d}\mathbf{h}/\mathrm{d}t = \mathbf{G}$, which are referred to as an inertial frame of reference with a stationary origin. The vectors $\mathbf{p}$ and $\mathbf{h}$ are the linear and angular momenta of the system referred to this frame, **R** is the vector sum of the forces applied to the system, the vector **G** is the sum of the vector moments of this applied forces about the origin. If the origin always coincides with the center of mass of the system, the second equation is unchanged, although $\mathrm{d}\mathbf{h}/\mathrm{d}t$ is now referred to a frame with moving origin. This means that one may use velocities relative to the center of mass instead of actual velocities. This is a principle of independence of translation and rotation.

When the mechanical system is a rigid body, the expression for **h** involves the moments and products of inertia and, in general, $\mathrm{d}\mathbf{h}/\mathrm{d}t$ will involve the rates of change of these coefficients of inertia owing to the motion of the body relative to the frame of reference. This difficulty is avoided by using axes which are fixed in the body.

More details in: L. Euler, *Opera omnia* (Teubner und Fussli, Leipzig, 1911).

Euler law states that the friction force between two bodies is proportional to the loading force → **Amontons' law**.

Euler–Maclaurin formula gives a connection between the integral and the sum for a smooth function $f(x)$ defined for all real numbers x between 0 and n, where n is the natural number, in the form $\int_0^n f(x)\mathrm{d}x = f(0)/2 + f(1) + \cdots + f(n-1) + f(n)/2$.

First described in: L. Euler, Comment. Acad. Sci. Imp. Petrop. **6**, 68 (1738).

Euler's formula (topology) gives a relation between the numbers of vertices V, of edges E, and faces F of a convex polyhedron, that is a polyhedron any two points of which can be joined by a straight line entirely contained in the polyhedron. It states that $V - E + F = 2$.

First described in: L. Euler, *Elementa doctrinae solidorum*, Novi. Comm. Acad. Sci. Imp. Petrop. **4**, 109 (1752).

even function – a function $f(x)$ with the property that $f(x) = f(-x)$.

Ewald sphere – a sphere superimposed on the reciprocal lattice of a crystal used to determine the directions in which an X-ray or other beam will be reflected by a crystal lattice.

First described in: P. P. Ewald, *Zur Theorie der Interferenzen der Röntgenstrahlen in Kristallen*, Phys. Z. **14**, 465–472 (1913).

More details in: J. B. Pendry, *Low Energy Electron Diffraction* (Academic Press, London, 1974).

EXAFS – an acronym for an **extended X-ray absorption fine structure**.

exchange interaction – a quantum mechanical effect which increases or decreases the energy of two or more electrons when their **wave functions** overlap. Arising from the **Pauli exclusion principle**, this energy change is the result of the identity of particles, exchange symmetry, and the electrostatic force. Exchange interaction is the mechanism by which the electron spins in many magnetic materials are lined up parallel or opposed.

First described in: W. Heisenberg, *Mehrkörperproblem und Resonanz in der Quantenmechanik,* Z. Phys. **38**(6–7), 411–426 (1926); P. A. M. Dirac, *On the theory of quantum mechanics,* Proc. R. Soc. Lond. A **112**(762), 661–677 (1926).

excimer – a combination of two atoms or molecules that survives only in an **excited state** and which dissociate as soon as the excitation energy has been discarded. The term is a contraction of ''excited dimer''. Excimers are used for light generation in lasers → **excimer laser**.

excimer laser – a rare-gas halide or rare-gas metal vapor laser emitting in the ultraviolet (from 126 to 558 nm) that operates on electronic transitions of molecules, up to that point diatomic, whose ground state is essentially repulsive. Excitation may be by done e-beam or electric discharge. Lasing gases include ArCl, ArF, KrCl, KrF, XeCl and XeF.

excited state – a high energy state of some entire system.

exciton – an electron–hole pair in a bound state in a hydrogen–atom–like fashion. Exciton formation processes in photon irradiated semiconductors are illustrated in Figure E.5. If the energy of the photon is larger than the band gap of the irradiated semiconductor (high energy excitation regime), then a free electron is created in the conduction band and an empty state, that is a hole, is left in the valence band. After relaxation they occupy the lowest energy states in the conduction and valence bands, respectively. The attractive force acting between the electron and hole leads to a reduction in their total energy, by an amount E_{X0}, and makes them bound. The exciton is formed. A photon with the energy just below the band gap can be resonantly absorbed, thus crating the exciton directly.



Figure E.5 Non-resonant and resonant exciton formation in semiconductors.

As the hole mass is generally much greater than the electron mass, the exciton can be considered like a two-body system resembling a hydrogen atom with the negatively charged electron orbiting the positive hole. Similarly to the hydrogen atom, the exciton is characterized by the **exciton Bohr radius** $a_B = \epsilon\hbar^2/\mu e^2 = \epsilon m_0/\mu(x0.053)$ nm where μ is the electron hole reduced mass $1/\mu = 1/m_e^* + 1/m_h^*$; $\epsilon = \epsilon_r\epsilon_0$ is the permittivity of the material. It is the natural physical separation in a crystal between an electron in the conduction band and the hole it leaves behind in the valence band. The size of this radius controls how large a crystal must be before its energy bands can be treated as continuous. Therefore, the exciton Bohr radius can rightly be said to define whether a crystal can be called a semiconductor quantum dot, or simply a bulk semiconductor.

The exciton binding energy is $E_{X0} = -\mu e^4/(32\pi^2\hbar^2\epsilon^2)$. The reduced electron–hole mass is smaller than the electron rest mass m_0, and the dielectric constant ϵ is several times bigger than that of vacuum. This is why the exciton Bohr radius is significantly larger and the exciton energy is significantly smaller than the relevant values for the hydrogen atom. Absolute values of a_B for most semiconductors range in the interval 1–10 nm, and the energy takes the values from 1 meV to 100 meV. The lifetime of excitons is of the order of hundreds of ps to ns.

The concentration of excitons n_{exc} and of the free electrons and holes $n = n_e = n_h$ are related via the ionization equilibrium equation known as the **Saha equation**:

$$n_{exc} = n^2 \left(\frac{2\pi\hbar^2}{k_B T} \frac{m_e^* + m_h^*}{m_e^* m_h^*} \right)^{3/2} e^{(E_{X0}/k_B T)}.$$

For $k_B T \gg E_{X0}$ most of the excitons are ionized and the properties of the electron subsystem of the crystal are determined by free electrons and holes. At $k_B T \leq E_{X0}$ a significant part of electron–hole pairs exists in the bound state.

Weakly bound excitons, typical for semiconductors, are also called **Mott-Wannier** excitons, while tightly bound excitons, usually found in solid inert gases, are called **Frenkel excitons**.

First described in: J. I. Frenkel, *Transformation of light into heat in solids,* Phys. Rev. **37**(1), 17–44 (1931).

exciton Bohr radius → **exciton**.

exclusion principle → **Pauli exclusion principle**.

exon – a segment of a **gene** present in mature m**RNA** transcripts that specify the amino acid sequence of a polypeptide during translation. Exons of a gene are linked together by mRNA splicing.

expectation value = **mean value**.

ex situ – Latin meaning ''away from''. The phrase ''ex situ analysis of experimental samples'' is used to show that the samples are analyzed at the place different from that where they have been fabricated. An alternative is ***in situ*** (Latin ''at the spot'') analysis supposing that the samples are analyzed in the same place where they have been fabricated.

extended Hückel method (theory) supposes molecular orbital treatment in which the interactions between electrons in different orbitals are ignored when the electronic bands in solids are simulated.

First described in: R. Hoffmann, *An extended Hückel theory*, J. Chem Phys. **39**(6), 1397–1412 (1963).

Recognition: in 1981 R. Hoffmann and K. Fukui received the Nobel Prize in Chemistry for their theories, developed independently, concerning the course of chemical reactions.

See also www.nobel.se/chemistry/laureates/1981/index.html.

extended state – a quantum mechanical state of a single electron in a random potential that extends throughout the whole sample.

extended X-ray absorption fine structure (EXAFS) spectroscopy – when an X-ray passes through a material, it attenuates progressively and undergoes some discontinuities for energies corresponding to electronic transitions of core electron towards unoccupied states above the **Fermi level**. In the case of a crystalline solid, the atom excited by the X-ray emits a photoelectron described by a spherical outgoing wave centered on the atomic target. The emitted photoelectron is retrodiffused by the electrons of the nearest neighbor atoms. This retrodiffusion is represented by spherical waves centered on the sites of neighboring atoms. A portion of these waves interferes with the first outgoing wave and gives rise to a modulation of the absorption coefficient. EXAFS spectroscopy reflects this local order, and the amplitude of the oscillations depends on the coordination number of neighbors N_j of type j located at a distance r_j from the absorbing central atoms. The absorption spectrum is composed by three regions:

1. an edge onset corresponding to the transition of a core electron to the Fermi level
2. a region close to the edge (**XANES – X-ray absorption near-edge structure**) where the emitted photoelectron carries little energy and because of the long mean free path the multiple scattering effects become important and reflect the geometry and the bond direction
3. a region showing oscillations of weak intensity, which is the EXAFS region, characterized basically by a single-scattering regime.

The absolute intensity of these fine structures is referred to the absorption coefficient of the isolated atom and in general is of the order of 10–20% of the total absorption.

More details in: B. K. Teo, D. C. Joy, *EXAFS Spectroscopy and Related Techniques* (Plenum Press, New York, 1981); M. De Crescenzi, M. N. Piancastelli, *Electron Scattering and Related Spectroscopies* (World Scientific Publishing, Singapore, 1996).

external quantum efficiency → **quantum efficiency**.

extinction – complete absorption of plane-polarized light by a polarizer whose axis is perpendicular to the plane of polarization.

extinction coefficient – a property of a material characterizing its ability to attenuate light → **dielectric function** and **refractive index**.

Eyring equation gives the specific reaction rate for a chemical reaction in the form $V = C^*(k_B T/h)p$, where C^* is the concentration of the activated complex formed by the collision of reactant molecules possessing the required energy, $k_B T/h$ is the classical vibration frequency of a bond which is broken when the complex dissociates, and p is the probability that this dissociation will lead to products.

First described in: H. Eyring, *The activated complex in chemical reactions*, J. Chem. Phys. **3**(2), 107–115 (1935).

F

From Fabry–Pérot resonator to FWHM (full width at half maximum)

Fabry–Pérot resonator consists of two parallel plates with their reflecting surfaces facing each other and spaced at a distance equal to $\lambda n/2$ ($n = 1, 2, \ldots$), where λ is the wavelength of the light desired to be in resonance conditions in it.

First described in: C. Fabry, A. Pérot, *Mesure de petites épaisseurs en valeur absolue,* Compt. Rend. Acad. Sci. **123**, 802 (1896).

face centered cubic (fcc) structure – a cubic lattice with lattice points on the faces of the unit cell in addition to the eight corner points. It is schematically shown in Figure F.1.



Figure F.1 Face centered cubic structure.

Falicov–Kimball model considers spinless electrons interacting with classical particles (ions) in a lattice. In fact, it is the **Hubbard model** including a few extra complications in order to investigate metal-insulator phase transitions in rare-earth materials and transition-metal compounds. These transitions are supposed to be regulated by the interactions between electrons in two electronic states: non-localized states (itinerant electrons) and states that are localized around the sites corresponding to the metallic ions of the crystal (static electrons).

The two species of particles are supposed to play a role in a crystal lattice within a **tight-binding approach**. The first species consists of spinless quantum fermions referred to as "electrons". The second species consists of localized holes or electrons considered as classical particles. Electrons hop between nearest-neighbor sites but classical particles do not. Both species obey **Fermi–Dirac statistics**. The **Pauli exclusion principle** prevents more than one particle of a given species to occupy the same site. Interactions are on-site and thus involve particles of different species. They can be repulsive or attractive.

The model can be viewed as the simplest model where quantum particles interact with classical fields.

First described in: L. M. Falicov, J. C. Kimball, *Simple model for semiconductor-metal transitions: SmB_6 and transition-metal oxides*, Phys. Rev. Lett. **22**(19), 997–999 (1969).

More details in: //arxiv.org/PS_cache/cond-mat/pdf/9811/9811299v1.pdf.

Fang–Howard wave function – $\psi(x) = x \exp[(1/2)bx]$. It vanishes at $x = 0$ and decays roughly like an exponent as $x \to 0$.

First described in: F. F. Fang, W. E. Howard, *Negative field-effect mobility on (100) Si surfaces*, Phys. Rev. Lett. **16**(18) 797–799 (1966).

Fano factor – the dimensionless characteristic of a short noise in an electronic device. It is defined as $\gamma = S_I/(2eI)$, with S_I being the spectral density of current fluctuations at low frequency, I the current flowing in the device, and e the elementary quantum of charge determining the current. In the absence of correlation between current pulses $j = 1$. This case corresponds to full shot noise. Deviations from this ideal situation are a signature of existing correlations between different pulses. A negative correlation corresponds to $\gamma < 1$ and a suppressed shot noise. In case of $\gamma > 1$ the correlation is positive and the shot noise is enhanced.

Fano interference → **Fano resonance**.

Fano resonance – arises from coupling (**Fano interference**) of a discrete energy state degenerate with a continuum. The mixing of a configuration belonging to a discrete spectrum with continuous spectrum configurations gives rise to the phenomenon of **autoionization**. Autoionized levels manifest themselves in continuous absorption spectra as asymmetric peaks because, in mixing of configurations to form a stationary state of energy E, the coefficients vary sharply when E passes through an autoionized level. It has been shown that the shapes of the absorption lines in the ionization continuum of atomic and molecular spectra are represented by the formula $\sigma(\epsilon) = \sigma_a[(q + \epsilon)^2/(1 + \epsilon^2)] + \sigma_b$, where $\epsilon = [(E - E_r)/(\Gamma/2)]$ indicates the deviation of the incident photon energy E from the idealized resonance energy E_r, which pertains to a discrete autoionizing level of the atom. This deviation is expressed in a scale whose units are the half-width $\Gamma/2$ of the line; $\sigma(\epsilon)$ is the absorption cross section for photons of energy E, and σ_a and σ_b are two portions of the cross section corresponding to transitions to states of the continuum that do and do not interact with the discrete auto-ionizing level, and q is a parameter (**Fano parameter**) which characterizes the line profile as shown in Figure F.2.

The Fano resonance is a universal phenomenon observed in **rare gas** spectra, impurity ions in semiconductors, electron-phonon coupling, photodissociation, bulk GaAs in a magnetic field, **superlattices** in electric field, and so on. It can be semiclassically understood in a coupled oscillator model. The discrete state drives the continuum oscillators, with eigenstates consisting of a mixture of the discrete state and the adjacent continuum. The continuum oscillators on either side of the discrete state move with opposite phase, according to whether the driving frequency is above or below their resonant frequency. Thus, on one side they interfere constructively with the discrete state and on the other destructively, leading to the characteristic asymmetric Fano resonance line shape.

First described in: U. Fano, *Sullo spettro di assorbimento dei gas nobili presso il limite dello spettro d'arco,* Nuovo Cimento **12**(2), 156 (1935); U. Fano, *Effects of configuration interaction on intensities and phase shifts*, Phys. Rev. **124**(6), 1866–1878 (1961).

More details in: U. Fano, J. W. Cooper, *Spectral distribution of atomic oscillator strengths,* Rev. Mod. Phys. **40**(3), 441–507 (1968).



Figure F.2 Natural line shapes for different values of q. (Reverse the scale of abscissas for negative values of q.)

Fano parameter → **Fano resonance**.

Faraday cell – a magneto optical device consisting of a fused silica or optical glass core inserted into a solenoid. When a linearly polarized light beam passes through the device, the direction of its polarization is rotated by an angle proportional to the magnetic flux density along the propagation direction.

Faraday configuration – the term used to indicate a particular orientation of a **quantum film** structure with respect to the magnetic field applied, that is when the field direction is perpendicular to the film plane. The alternative orientation is labeled as a **Voigt configuration**.

Faraday effect – a rotation of the plane of polarization of polarized light when it passes through a homogeneous medium along a magnetic field. The magnitude and direction of this magnetic rotation depend on the strength and direction of the field, but do not depend on the direction of the light propagation through the field. Mathematically it can be described by the relationship $\theta = VHL$, where θ is the amount of rotation, H is the strength of the magnetic field, and L is the path length of the light through the sample. The proportionality constant V is known as the **Verdet constant**. It is approximately proportional to the reciprocal of the square of the wavelength of the light. This constant can be either positive or negative. A positive value refers to a substance in which the direction of rotation is the same as the direction of the current producing the magnetic field. A negative one represents the opposite situation.

First described by: M. Faraday on September 13, 1845 and *published in* M. Faraday, *Experimental researches in electricity. – Nineteenth Series*. Phil. Trans. **136**, 1–20 (1846); M. E. Verdet, *Recherches sur les propriétés optiques développées dans les corps transparents par l'action du magnétisme*, Ann. Chim. **41**, 370–412 (1854).

Faraday law (of electrolysis) governs electrolysis within the following statements: i) the amount of chemical action produced by a current is proportional to the quantity of electricity passed, ii) the masses of different substances deposited or dissolved by the same quantity of electricity are in the same ratios as those of their chemical equivalents.

First described in: M. Faraday, *Experimental researches in electricity. – Seventh series*, Phil. Trans. **124**, 77–122 (1834).

Faraday law (of electromagnetic induction) states that any change of a magnetic flux Φ in an electric circuit induces the electromotive force E proportional to the rate of the flux change, so $E \propto (\mathrm{d}\Phi/\mathrm{d}t)$.

First described by: M. Faraday in 1831 and *published in* M. Faraday, *Experimental researches in electricity. – Third series*, Phil. Trans. **123**, 23–54 (1834).

fast Fourier transform (FFT) – a powerful tool used in many engineering and physical disciplines. It was developed to compute the discrete **Fourier transform** and its inverse (formally a discrete Fourier transform is a linear transformation mapping any complex vector of length N to its Fourier transform) of a sequence of N numbers in a faster and efficient manner. It is of great importance in several applications, from digital signal processing to solving partial differential equations to developing algorithms for quickly multiplying large integers. In particular, the **Cooley–Tukey algorithm**, being one of the fast Fourier transform algorithms, reduces the number of computations from $O(N^2)$ to $O(N \log N)$. It is interesting to note that an algorithm similar to the FFT has been recently attributed to Carl Friedrich Gauss.

More details in: M. T. Heidemann, D. H. Johnson, C. Sidney Burrus, *Gauss and the History of Fast Fourier Transform*, IEEE Acoustic, Speech, and Signal Processing Magazine, **1**(10), 14–21 (1984).

Fechner ratio – the differential luminance threshold divided by the luminance.

First described in: G. T. Fechner, *Vorschule der Ästhetik* (1876).

Feher effect – a dynamical nuclear polarization arising as a result of hyperfine coupling between the electron and nuclear spins together with different temperatures representing electron velocity and electron spin populations.

First described in: G. Feher, *Nuclear polarization via 'hot' conduction electrons,* Phys. Rev. Lett. **3**(3), 135–137 (1959).

Felgett advantage – the signal-to-noise ratio obtained with a **Fourier transform** spectrometer when detector noise prevails, which exceeds the signal-to-noise ratio of a scanning spectrometer in the same time by a factor proportional to the square root of the number of spectral elements studied. The increase is due to the ability of a Fourier transform spectrometer to observe all spectral elements simultaneously.

First described in: P. Felgett, *A propos de la théorie du spectrométric interférentiel multiplex,* J. Phys. Radium **19**, 187–222 (1954).

femto- – a decimal prefix representing 10^{-15}, abbreviated f.

Fermat's principle (in optics) states that the actual path between two points taken by a beam of light is the one which is traversed in the least time. In this original form however, the Fermat's principle is somewhat incomplete. An improved form is: a light ray, in going between two points, must traverse an optical path length which is stationary with respect to variations of the path. In such a formulation, the paths may be maxima, minima, or saddle points.

First described by P. Fermat in 1635. See in P. Fermat, *Oeuvres* (Gauthier-Villars, Paris, 1891).

Fermi–Dirac distribution (statistics) gives the probability that in an ideal electron gas in thermal equilibrium at a temperature T an electron state with an energy E will be occupied

$$f(E) = \frac{1}{\exp\left[(E - \mu)/k_B T\right] + 1},$$

where μ is the chemical potential. Differently from the **Bose–Einstein statistics** the Fermi–Dirac distribution also takes into account the **Pauli exclusion principle** – there can be no more than one particle in each quantum state. At absolute zero the chemical potential is equal to the **Fermi energy** E_F. The Fermi energy is often used instead of the chemical potential in the Fermi–Dirac distribution, but one must know that E_F is a temperature dependent quantity.

First described in: E. Fermi, *Zur Quantelung des idealen einatomigen Gases*, Z. Phys. **36**(11/12), 902–912 (1926); P. A. M. Dirac, *Theory of quantum mechanics*, Proc. R. Soc. Ser. A. **112**, 661–677 (1926).

Recognition: in 1933 P. A. M. Dirac and E. Schrödinger received the Nobel Prize in Physics for the discovery of new productive forms of atomic theory.

See also www.nobel.se/physics/laureates/1933/index.html.

Fermi energy – the energy of the topmost filled level in the ground state of an electron system at absolute zero (for more details → **Fermi–Dirac distribution**).

Fermi gas – a system of noninteracting **fermions**.

Fermi level = **Fermi energy**.

Fermi liquid – a system of interacting **fermions**. The low-energy excitations (or **quasiparticles**) of this system act almost like completely free electrons, moving entirely independently of one another.

fermions – quantum particles whose energy distribution obeys the **Pauli exclusion principle** and **Fermi–Dirac statistics**.

Fermi's golden rule – if an electron (or hole) in a state $|i\rangle$ of energy E_i experiences a time-dependent perturbation $\mathbf{H}$ which could scatter (transfer) it into any one of the final states $|f\rangle$ of energy E_f, then the lifetime of the carrier in the state $|i\rangle$ is given by

$$\frac{1}{\tau_i} = \frac{2\pi}{h} \sum_f |\langle f|\mathbf{H}|i\rangle|^2 \delta(E_f - E_i).$$

Thus, the rule describes the lifetime of a particle in a particular state with respect to scattering by a time varying potential.

The formula was firstly proposed by P. A. M. Dirac. More than 20 years later, Fermi, in his Chicago lectures, called the formula a golden rule.

First described in: P. A. M. Dirac, *The quantum theory of emission and absorption of radiation*, Proc. R. Soc. (London) A **114**, 243–265 (1927); E. Fermi, *Nuclear Physics* (University of Chicago Press, 1950).

Fermi sphere – the **Fermi surface** of an assembly of **fermions** in the approximation that they are free particles.

Fermi surface – a constant energy surface in the space containing the wave vectors of states, that is k space, defined by the **Fermi energy**.

Fermi–Thomas approximation supposes that if the total potential V of electrons in a solid does not vary greatly over the distance r corresponding to the electron wavelength, the local Fermi kinetic energy E_F must also vary in order to compensate the variation of the potential, so that $V + E_F = \text{constant}$.

Fermi wave vector – the momentum corresponding to the **Fermi energy**.

Fermi wavelength – $\lambda_F = 2\pi/k_F$, where k_F is the **Fermi wave vector**.

ferric wheel → **molecular nanomagnet**.

ferrimagnetic – a substance in which atomic magnetic momenta are arranged in such a way that a resulting momentum occurs as a consequence of the tendency for antiparallel orientation of the magnetic momenta of certain neighboring atoms → **magnetism**.

ferrite – a nonmetallic magnetic compound containing Fe_2O_3 as a major component. Examples: $MeFe_2O_4$ (Me = Mn, Fe, Co, Ni, Zn, Cd, Mg,) – spinel ferrites; $R_3Fe_5O_{12}$ (R- rare earth metal or yttrium) – garnets.

ferritin – a self-assembled multi-subunit protein involved in biological functions such as iron storage and heme production. It is about 12 nm in diameter. This protein is constructed from 24 nearly identical subunits forming a spherical shell that encloses an internal cage 8 nm in diameter. The cavity contains up to 4500 iron atoms in the form of a poorly crystalline Fe(III) oxy-hydroxide mineral, ferrihydrite. The size of the ferrihydrite core is constrained by the 8-nm inner cavity of the protein.

More details in: E. L. Mayers, S. Mann, *Mineralization in nanostructured biocompartments: biomimetic ferritins for high density data storage*, in: *Nanobiotechnology. Concepts, Applications and Perspectives*, edited by C. M. Niemeyer and C. A. Mirkin (Wiley-VCH, Weinheim, 2004).

ferrocene – the prototypical **metallocene** compound $Fe(C_5H_5)_2$ consisting of two **cyclopentadienyl** rings bound on opposite sides of a central iron atom and forming a sandwich structure schematically shown in Figure F.3.

It has two five-membered carbon rings which are parallel, with the iron ion sandwiched between them. The bonding is between π orbitals on the rings and d orbitals on the Fe^{2+} ion. That provides an electron configuration like that of an inert gas, making it chemically stable.

The compound demonstrates electrochemically reversible one-electron **redox** behavior. The ferrocenium ion, which is formed by oxidation of ferrocene is also stable in the air and easy to handle.

Ferrocene is used as a combustion control additive in fuels, an antiknock agent in gasoline, and for heat stabilization in greases and plastics. Its redox responsivity is of interest for the design of molecular devices.

First described in: T. J. Kealy, P. L. Pauson, *A new type of organo-iron compound*, Nature **168**, 1039–1040 (1951).



Figure F.3 Ferrocene molecule.

ferroelectric – a dielectric for which a nonlinear hysteretic relationship exists between **polarization** and applied electric field over certain temperature ranges. It can be considered as the electric analog of a **ferromagnetic**. All ferroelectrics are **piezoelectric** and **pyroelectric**, but they additionally possess a reversible, nonvolatile macroscopic spontaneous electric dipole moment in the absence of an external electric field. Ferroelectric crystals can be seen as an assembly of batteries with a particular orientation, which remains stable unless an external electric field is applied to change its direction. Their polar state is a consequence of the structural transition from a high-temperature, high-symmetry paraelectric phase to a low-temperature, low-symmetry ferroelectric phase. These materials also behave as high-dielectric-constant insulators useful for capacitors and energy storage materials.

First described in: J. Valasek, *Piezo-electric and allied phenomena in Rochelle salt*, Phys. Rev. **17**(4), 475–481 (1921).

ferromagnetic – a substance exhibiting: (i) high value of magnetization in weak magnetic fields, coming to saturation with an increase of the field strength, (ii) abnormally high permeability that depends on the field strength and prior magnetic history (hysteresis), (iii) residual magnetism and spontaneous magnetization. All these properties disappear above a certain temperature called the **Curie point** and the material behave like a **paramagnetic** → **magnetism**.

ferromagnetic resonance – a resonant absorption of energy in **ferromagnetics** from an external high frequency circularly polarized magnetic field when its frequency is equal to the internal frequency of precession. Note that if total magnetic momentum of a specimen is displaced from its equilibrium position, it precesses about the direction of the uni-directional magnetic field applied.

First described by V. K. Arkadiev in 1912 – prediction; J. H. E. Griffiths, *Anomalous high frequency resistance of ferromagnetic metals*, Nature **158**, 670–671 (1946) – experimental observation.

Feshbach resonance – a resonance of a many-body system, with more than one degree of freedom, which would turn into a bound state if coupling between some degrees of freedom and the degrees of freedom associated to the fragmentation were set to zero.

For instance, in a system containing two neutral atoms the electrostatic interaction between the electrons and nuclei creates a potential well that is attractive at large distances and repulsive at short distances. In Feshbach resonance a change of magnetic field mimics a change in the depth of the well. Crucially, a bound state of two atoms can exist when the depth of the well is large. Moreover, if the atoms occupying this bound state are **fermions**, the pair has integer spin and is therefore a **boson**. By cooling the system to the critical temperature where **Bose–Einstein condensation** takes place, the composite bosons can then undergo a phase transition to a superfluid state.

The phenomenon is important in the study of **Fermi gases**, as these resonances allow for the creation of Bose–Einstein condensates. In such systems the resonance occurs when the energy of a bound state of an interatomic potential is equal to the kinetic energy of a colliding pair of atoms, which have hyperfine structure coupled via Coulomb or **exchange interaction**s. This condition is rare, but can be satisfied in ultracold alkali atoms.

First described in: H. Feshbach, *Unified theory of nuclear reactions*, Ann. Phys. **5**(4), 357–390 (1958).

Feynman diagram – an intuitive picture of a term in perturbation expansion of a **scattering matrix** element or other physical quantity associated with interactions of particles: in the diagrams each line represents a particle, each vertex an interaction.

First described in: R. P. Feynman, *Space-time approach to quantum electricity*, Phys. Rev. **76**(6), 769–787 (1949).

Feynman–Hellman theorem states that the derivative of the energy E_n of a state n with respect to some parameter q is equal to the expectation value of the derivative of the **Hamiltonian H** in that state:

$$\frac{\partial E_n}{\partial q} = \left\langle \frac{\partial \mathbf{H}}{\partial q} \right\rangle_n = \left\langle n | \frac{\partial \mathbf{H}}{\partial q} | n \right\rangle .$$

First described in: H. Hellman, *Einführung in die Quanten Chemie* (Leipzig, 1937); R. P. Feynman, *Forces in molecules*, Phys. Rev. **56**(4), 340–343 (1939).

Feynman integral – a term in perturbation expansion of a **scattering matrix** element. It is an integral over the **Minkowski space** of various particles or over the corresponding momentum space of the product of propagators of these particles and quantities representing interactions between the particles.

First described in: R. P. Feynman, *Space-time approach to non-relativistic quantum mechanics*, Rev. Mod. Phys. **20**(2), 367–387 (1948).

Feynman propagator – a factor of the form $(p+m)/(p^2-m^2+i\epsilon)$ in a transition amplitude corresponding to a line that connects two vertices in a **Feynman diagram**, and that represents a virtual particle.

First described in: R. P. Feynman, *Space-time approach to non-relativistic quantum mechanics*, Rev. Mod. Phys. **20**(2), 367–387 (1948).

Fibonacci sequence – the sequence of integers produced by adding the two previous terms: 1, 2, 3, 5, 8, 13, 21,... One of the fascinating illustrations of the sequence in nature is that it predicts the number of rabbits there will be after a certain number of months starting from a single breeding couple. The ratio of successive terms tends to the golden ratio, which is about 1.618 – a number that appears throughout nature in different geometrical guises such as seashells, pine cones, and cauliflowers.

First described in: L. P. Fibonacci. *Liber Abbaci* (1202).

fibrous protein → **protein**.

Fick's laws → **diffusion**.

First described in: A. Fick, *Über Diffusion*, Ann. Phys. **94**, 59–86 (1855).

field emission – emission of electrons from a solid surface caused by an applied electric field.

field ion microscopy (FIM) – a projection-type microscopy in which individual atoms protruding on the surface of a needle-shaped specimen are imaged by preferential ionization of imaging gas, that is usually He or Ne, at the protruding site.

The sample to be analyzed is prepared in the form of a sharp tip. A positive potential is applied to the tip such that a very large electric field is present at the tip. The ambient gas surrounding the tip, that is the imaging gas, is usually He or Ne at a reduced pressure. The gas atoms are ionized in collisions with an atom protruding on the surface. Then they are accelerated away from the tip where they strike a fluorescent screen. The net effect of many gas atoms is to create a pattern on the fluorescent screen showing spots of light which correspond to individual atoms on the tip surface.

First described in: E. W. Müller, *Das Feldionenmikroskop*, Z. Phys. **131**(1), 136–142 (1951).

figure of merit – a performance rating that governs the choice of a device for a particular situation. For instance, the dimensionless thermoelectric characteristic (ZT) of a material is used as a figure of merit to evaluate the material's suitability for thermoelectric power generation. It is defined as $ZT = (S^2T)/(\kappa\rho)$, where S is the **Seebeck coefficient**, κ is the total thermal conductivity, and ρ is the electrical resistivity.

FIM – an acronym for a **field ion microscopy**.

fine structure constant – the dimensionless constant $\alpha = e^2/(hc)$ used in scattering theory.

In quantum electrodynamics it represents the strength of the interaction between **electrons** and **photons**. This value is $\alpha = 0.007297352533$, and for the often used inverse value $\alpha^{-1} = 137.03599977$.

Finnis–Sinclair potential – the interatomic short-range potential based on the second moment approximation within the **tight-binding approach**. It has the form

$$V = 0.5\sum_{ij} V(r_{ij}) - A\sum_{i}\sqrt{\rho_i},$$

where $V(r_{ij})$ is the pair potential, r_{ij} is the distance between atoms i and j, and A is the fitting parameter. The total electron density ρ_i at an atom position i is calculated as a linear superposition of electron-density contributions from neighboring atoms

$$\rho_i = \sum_{i\neq j}\phi(r_{ij}),$$

where the electron density contribution from an atom j to an atom i is $\phi(r_{ij}) = (r_{ij} - d)^2$ for $r_{ij} \leq d$ and $\phi(r_{ij}) = 0$ for $r_{ij} > d$ with d to be the fitted cutoff distance.

This potential is often used in the embedded atom method.

First described in: M. W. Finnis, J. E. Sinclair, *A simple empirical N-body potential for transition metals*, Phil. Mag. A **50**(1), 45–55 (1984).

More details in: G. A. Mansoori, *Principles of Nanotechnology: Molecular-based Study of Condensed Matter in Small Systems* (World Scientific, Singapore, 2005).

Firsov potential – the semiclassical interatomic pair potential in the form:

$$V(r) = \frac{Z_1 Z_2 e^2}{r} \chi \left[(Z_1^{1/2} + Z_2^{1/2})^{2/3} \frac{r_0}{a} \right],$$

where

$$\chi(x) = \chi \left[(Z_1^{1/2} + Z_2^{1/2})^{2/3} \frac{r_0}{a} \right]$$

is the screening function with the **Firsov scale factor** $V(r) = A/r^2$, with $A = (3.05 \times 10^{-16} Z_1 Z_2)/(Z_1^{1/2} + Z_2^{1/2})^{2/3}$. Here r is the interatomic distance, Z_1 and Z_2 are the atomic numbers of the interacting atoms, and r_0 and a are fitting parameters.

First described in: O. B. Firsov, *Calculation of the interaction potential of atoms*, Zh. Exp. Teor. Fiz. **33**(3), 696–699 (1957) – in Russian.

Firsov scale factor → **Firsov potential**.

FISH – an acronym for **fluorescence *in situ* hybridization**.

FLAPW method = **full potential augmented plane wave (FLAPW) method**.

Fleming tube – the first vacuum tube diode, consisting of a heated filament and cold metallic electrode placed in an evacuated glass tube.

First described by J. A. Fleming and patented on November 16, 1904.

flicker noise – the noise observed on the direct current (I) flowing through vacuum tubes and semiconductor devices. Its spectrum is $S(f) = KI^n/f^a$, where K is a constant dependent on the material, $n \approx 2$, and a varies between 0.5 and 2. This noise is also called **1/f noise** or **pink noise**. Its major cause in semiconductor devices is traced to surface properties of the material. The generation and recombination of charge carriers in surface energy states are the most influencing factors.

First described in: J. B. Johnson, *The Schottky effect in low-frequency circuits*, Phys. Rev. **26**(1), 71–85 (1925).

fluctuation–dissipation theorem states a general relationship between the response of a given system to an external disturbance and the internal fluctuation of the system in the absence of the disturbance. Such a response is characterized by a response function or equivalently by an admittance or an impedance. The internal fluctuation is described by a correlation function of relevant physical quantities of the system fluctuating in thermal equilibrium, or equivalently by their fluctuation spectra. The most striking feature of this theorem is that it relates, in a fundamental manner, the fluctuations of a physical quantity pertaining to the equilibrium state of the given systems to a dissipative process which, in practice, is realized only when the system is subjected to an external force that drives it away from equilibrium.

This means that the response of a given system to an external perturbation (nonequilibrium property) can be expressed in terms of fluctuation properties of the system in thermal equilibrium (equilibrium property).

Probably one of the first forms of the fluctuation–dissipation theorem was given by the **Einstein relationship** that relates the viscous friction of a Brownian particle to the diffusion constant of the particle in the form $D = k_B T/m\gamma$, where D is the diffusion constant and $m\gamma$ is the friction constant. The Einstein relation can be also written as: $\mu = 1/m\gamma = D/k_B T = (1/k_B T)\int_0^\infty < u(t_0)u(t_0 + t) > \mathrm{d}t$, which means that the mobility μ, the inverse of the friction constant, is related to the fluctuation of the velocity $u(t)$ of the **Brownian motion**; this is in fact the fluctuation–dissipation theorem.

The theorem can be used in two ways. From the known characteristics of the admittance or the impedance one can predict the characteristics of the fluctuation or the noise intrinsic to the system. Alternatively, from the analysis of thermal fluctuations of the system one can derive the admittance or the impedance. A general proof of the fluctuation–dissipation theorem has been given, in modern times, by the linear response theory.

First described: It is difficult to say definitely when the theorem was formulated for the first time. It appeared several times in different fields of applications. For two applications in the senses outlined above see H. Nyquist, *Thermal agitation of electrical charge in conductors*, Phys. Rev. **32**(1), 110–113 (1928), L. Onsager, *Reciprocal relations in irreversible processes. I*, Phys. Rev. **37**(4), 405–426 (1931), for a proof within the linear response theory see H. B. Callen, T. A. Welton, *Irreversibility and generalized noise*, Phys. Rev. **83**(1), 34–40 (1951).

More details in: R. Kubo, *The fluctuation–dissipation theorem*, Rep. Prog. Phys. **29**, 255–284 (1966).

Recognition: in 1968 L. Onsager received the Nobel Prize in Chemistry for the discovery of the reciprocal relations bearing his name, which are fundamentals for the thermodynamics of irreversible processes.

See also www.nobel.se/chemistry/laureates/1968/index.html.

fluorescence – classically the emission of radiation of a characteristic wavelength by a substance having been excited, which occurs no longer than 10^{-8} s after removal of the excitation. Longer light emission is called **phosphorescence**. In today words, it is the light emitted as a result of spin-allowed radiative deactivation of **excited states**.

First described in: G. Stokes, *On the change of refrangibility of light*, Proc. Roy. Soc. London **6**, 195–199 (1852).

fluorescence *in situ* hybridization (FISH) – an analytical technique employing fluorescent molecular tags to detect probes hybridized to **chromosomes** or chromatin. It is used for genetic mapping and detecting chromosomal abnormalities.

fluorescence microscopy – an optical imaging technique in which an analyzed specimen is irradiated at a wavelength exciting either natural or artificially introduced fluorescent molecules known as fluorophores. The image is then studied through a filter that transmits at the fluorescence wavelength, but absorbs light at the excitation wavelength.

fluorescence nanoscopy – a set of techniques employed to overcome the so-called **diffraction** or **Abbe's resolution limit**.

In **confocal fluorescence microscopy**, the excitation light wave formed by the lens to a spherical cap produces a three-dimensional diffraction spot, generating fluorescence in the focal region. A point-like detector registers fluorescence mostly from the main maximum, thus providing a slightly improved resolution (>200 nm in the focal plane and to >450 nm along the optical axis) with respect to conventional **fluorescence microscopy**.

In **structured illumination microscopy (SIM)** a diffraction grating is placed in the path of the excitation light generating a diffraction pattern on the sample. This fine pattern of light interacts with fine patterns in the sample and creates an interference pattern whose periodicity is much greater than that of the original pattern. Thus, fine patterns that were previously below the **Abbe's resolution limit** can now be visualized.

By combining the wavefront caps of two opposing lenses the emitted light can be harvested by a greater portion of the sphere surrounding the sample, this so called **FourPi (4Pi) microscopy** forms a narrower spot along the optical axis and hence an improved resolution along the optical axis (80 to 150 nm).

Stimulated emission depletion (STED) microscopy make use of a regularly focused excitation beam that is superimposed by a doughnut-shaped STED beam that instantly quenches excited molecules at the periphery of the excitation spot, thus confining fluorescence emission to the doughnut zero. Saturated quenching results in a fluorescent spot far below diffraction whose scanning across the sample yields a sub-diffraction-resolution image.

In **incoherent interference illumination (I^3M) microscopy** the light, coming from two objectives, interferes constructively at the focal plane allowing an stronger concentration of the effective excitation. If the emitted light through the two objectives is collected and constructively combined on a single detector one obtains a sharper pattern. This last technique is called **image interference (I^2M) microscopy**. These two last techniques can be combined creating **image interference (I^2M) + incoherent interference illumination (I^3M) microscopy (I^5M)**. The resolution reached is of the same order as that in **FourPi (4Pi) microscopy**.

Other techniques use bright and dark molecular states to break the diffraction limit.

Parallelized **STED**, **ground-state depletion** (**GSD**) and **saturated pattern excitation spectroscopy** (**SPEM**) (similar to **SSIM**) all use reversible saturable or photoswitchable transitions between two molecular states. In particular they use photophysical transitions. One limitation here is the finite number of cycles between the two states. These techniques are able to resolve ensembles of molecules.

Instead if one uses photochemical transitions in which atoms are relocated or bonds are formed or broken one has **photoactivable localization microscopy (PALM)** and **stochastic optical reconstruction microscopy (STORM)** that are able to resolve single molecules.

The acronym **RESOLFT** (i.e. **reversible saturable optically linear fluorescence transitions**) is now used for all these techniques.

More details in: W. A. Wells, *Man the nanoscopes*, J. Cell. Biol. **164**(3), 337–340 (2004); S. W. Hell, *Far-field optical nanoscopy*, Science **316**, 1153–1158 (2007).

fluxon – a quantum of magnetic flux $\Phi_0 = h/2e = 2.07 \times 10^{-15}$ Wb.

Foch space – the space in the quantum field theory where the number of particles is generally not fixed. It is sometimes convenient to represent the state of a system by an infinite set of wave functions, each of which refers to a fixed number of particles.

Fock exchange potential → **Hartree–Fock approximation**.

focused ion beam (FIB) system – a system for sample preparation and fabrication at the nanoscale by ion-mill sculpting or beam-induced deposition. Moreover, exposing sensitive surfaces to a focused ion beam makes it possible to fabricate and write dimensions into resist materials well below 20 nm, which in fact is a FIB lithography technique. A beam of singly charged ions (Ga^+) is usually used for this. Typical FIB instruments provide a focal spot size below 5 nm at a current of a few pA. Practical resolution is a few tens of nanometers. The proximity effect of FIB lithography is much weaker than that of **electron beam lithography** because of the shorter range of the exposing particles (ions), smaller lateral spread, weaker secondary electron generation, and lower energy of secondary electrons. A serial writing process employing scanning of the ion beam or a substrate is used to expose the whole substrate surface. This causes the throughput of the technique to be quite limited and not effective in mass production.

Fogden–White theory generalizes the **friction force theory (Hertz theory)** and **Johnson–Kendall–Roberts theory** for contact elasticity by introducing a condensable vapor atmosphere, in which capillary condensation is well known to significantly affect the force of **adhesion** between the solids.

First described in: A. Fogden, L. White, *Contact elasticity in the presence of capillary condensation: I. The nonadhesive Hertz problem*, J. Coll. Inter. Sci. **138**(2), 414–430 (1989).

Foiles potential describes the pair interaction between two different atoms approximated by the geometric mean of the pair interaction of the individual atoms. For atoms A and B separated by the distance r it has the form $V(r) = Z_A(r)Z_B(r)/r$, where $Z(r) = Z_0 \exp(-ar)$. The value of Z_0 is given by the number of outer electrons of the atom and a is the fitting parameter.

First described in: S. M. Foiles, *Calculation of the surface segregation of Ni-Cu alloys with the use of embedded-atom method,* Phys. Rev. B **32**(12), 7685–7689 (1985).

Fokker–Planck equation – an equation for the distribution function $f(r,p,t)$ of particles in a gas or a liquid, analogous to the **Boltzmann distribution** but applying where forces are long-range and collisions are not binary:

$$\frac{\partial f}{\partial t} + \frac{p}{M}\frac{\partial f}{\partial r} - \frac{\partial V}{\partial r}\frac{\partial f}{\partial p} = \frac{\partial}{\partial p}\xi\left(\frac{p}{M}f + k_B T\frac{\partial f}{\partial p}\right),$$

where r is the coordinate, p is the momentum, M is the mass of the gas particles; t is time and T is temperature; V is the potential from an external force acting on the particles and ξ is the friction coefficient. It describes the evolution of the distribution function in the presence of diffusion and driving force.

First described in: A. Einstein, *Über die von der molekularkinetischen Theorie der Wärme geforderte Bewegung von in ruhenden Flüssigkeiten suspendierten Teilchen,* Ann. Phys. **17**, 549–560 (1905), then by A. Fokker, *Die mittlere Energie rotierender elektrischer Dipole im Strahlungsfeld,* Ann. Phys. **43** 810–820 (1914) and by M. Smoluchowski, *Über Brownsche Molekularbewegung unter Einwirkung äusserer Kräfte und deren Zusammenhang mit der verallgemeinerten Diffusionsgleichung,* Ann. Phys. **48**, 1103–1112 (1915), and in the final form in: M. Planck, *Über einen Satz der statistischen Dynamik and seine Erweiterung in der Quantentheorie,* Sitzungsber. Preuss. Akad. Wiss. Berlin **24**, 324–341 (1917).

folded spectrum method supposes, instead of seeking solutions of the time-independent **Schrödinger equation**, that solutions are sought to the alternative expression: $(\mathbf{H} - E_{ref})^2\psi_{n,\mathbf{k}} = (E_{n,\,\mathbf{k}} - E_{ref})^2\psi_{n,\mathbf{k}}$, where the reference energy E_{ref} can be chosen to lie within the fundamental gap and hence the **valence** and **conduction band** edge states are transformed from being arbitrary high-energy states to being the lowest states. The technique serves to minimize the expectation value $\langle\psi|(\mathbf{H} - E_{ref})^2|\psi\rangle$, where the standard empirical pseudopotential operator can be employed.

First described in: L. W. Wang, A. Zunger, *Solving Schrödinger's equation around a desired energy: application to quantum dots,* J. Chem. Phys. **100**(3), 2394–2397 (1994).

f orbital → **atomic orbital**.

Ford–Kac–Mazur formalism was originally proposed to study Brownian motion in coupled oscillators. It was later extended to a general analysis of a quantum particle coupled to a quantum mechanical heat bath. Within this formalism the bath is considered as a collection of oscillators which are initially in equilibrium. Its degrees of freedom are then eliminated, leading to quantum Langevin equations for the remaining degrees of freedom of the whole system. Thus, such a bath can be viewed as a source of noise and dissipation in the system. The formalism is used for simulation of classical heat transport in disordered harmonic chains as well as for a detailed study of quantum transport in disordered electronic and phononic systems.

First described in: W. Ford, M. Kac, P. Mazur, *Statistical mechanics of assemblies of coupled oscillators*, J. Math. Phys. **6**(4), 504–515 (1965).

Förster energy transfer – a long-range Coulomb-induced transfer of optically excited **excitons**.

First described in: Th. Förster, *Transfer mechanisms of electronic excitation*, Disc. Faraday Soc. **27**, 7–17 (1959).

More details in: Th. Förster, *Delocalized excitation and excitation transfer*, in: Modern Quantum Chemistry, IIIB, edited by O. Sinanoglu (Academic Press, New York, 1965), pp. 93–137.

Foucault currents → **eddy currents**.

FourPi (4Pi) microscopy → **fluorescence nanoscopy**.

First described in: S. W. Hell, E. H. Stelzer, *Properties of a 4PI-confocal fluorescence microscope*, J. Opt. Soc. Am. A **93**, 277–282 (1992).

fountain effect occurs when two containers of superfluid helium are connected by a capillary tube and one of them is heated, so that helium flows through the tube in the direction of higher temperature.

Fourier analysis – a mathematical tool by which discontinuous and periodic functions may be represented in terms of continuous functions. If $f(x)$ is single valued in the range of $a < x < b$, and is sectionally continuous, that is it contains only a finite number of discontinuities in the range which are finite in magnitude, then it is possible to expand $f(x)$ in an infinite set of functions orthogonal in this range. By suitable scaling the range can be made $-\pi < x < \pi$, and it is then convenient to choose the circular functions for the expansion in the form $f(x) = A_0 + \sum_{k=1}^{\infty}(A_k \cos kx + B_k \sin kx)$, which is termed the **Fourier expansion** or **Fourier series**. The coefficients are $A_0 = 1/2\pi \int_{-\pi}^{\pi} f(x)\mathrm{d}x$, $A_k = 1/\pi \int_{-\pi}^{\pi} f(x)[\cos kx]\mathrm{d}x$, $B_k = 1/\pi \int_{-\pi}^{\pi} f(x)[\sin kx]\mathrm{d}x$. If $f(x)$ is an even function, the B_k are zero. If $f(x)$ is an odd function, the A_k are zero.

Instead of using sine and cosine functions for the expansion, one can employ the exponential function with the imaginary argument: $f(x) = \sum_{-\infty}^{\infty} C_k \exp(\mathrm{i}kx)$ with $C_k = 1/2\pi \int_{-\pi}^{\pi} f(x) \exp(-\mathrm{i}kx)\mathrm{d}x$. A Fourier series may be integrated term by term, but it cannot generally be differentiated.

First described in: J. Fourier, *La Thèorie Analytique de la Chaleur* (Didot, Paris, 1822).

Fourier equation – the differential equation giving the temperature T at any place and at any time when heat transport is by the conduction mechanism only. In the absence of internal heat sources and for a nonhomogeneous material it has the form $\rho C(\partial T/\partial t) = \nabla \cdot (K\nabla T)$, where ρ is the material density, C is the specific heat of the material, t is the time, and K is the thermal conductivity of the material.

Fourier law states that the rate of heat flow by conduction across an infinitesimally small area S is proportional to the temperature gradient normal to the area: $\mathrm{d}Q/\mathrm{d}T = -KS\mathrm{d}T/\mathrm{d}r$, where Q is the quantity of heat, t is the time, K is the thermal conductivity of the material at the place in question, r is the distance measured normal to S in the direction of decreasing temperature.

First described in: J. Fourier, *La Theorie Analytique de la Chaleur* (Didot, Paris, 1822).

Fourier series → **Fourier analysis**.

Fourier transform for a function $f(x)$ is given by

$$F(\xi) = 1/\sqrt{2\pi}\int_{-\infty}^{\infty} f(x)\exp(\mathrm{i}\xi x)\mathrm{d}x.$$

If the Fourier transform $F(\xi)$ of a function is known, the function itself can be found by means of the Fourier inversion theorem

$$f(x) = 1/\sqrt{2\pi}\int_{-\infty}^{\infty} F(\xi)\exp(-\mathrm{i}\xi x)\mathrm{d}x.$$

First described in: J. Fourier, *La Théorie Analytique de la Chaleur* (Didot, Paris, 1822).

Fowler–Nordheim tunneling describes charge carrier transport through insulators. The current density is $J = CE^2\exp(-E_0/E)$, where C and E_0 are constants in terms of effective mass and barrier height, and E is the electric field in the insulator (V/m).

First described in: R. H. Fowler, L. Nordheim, *Electron emission in intense electric fields*, Proc. R. Soc. A **119**, 173–181 (1928).

fractal – a rough or fragmented geometric shape that can be subdivided into parts, each of which is (at least approximately) a reduced-size copy of the whole. As a geometric object, a fractal is characterized by the following features: (i) it has a fine structure at arbitrarily small scales; (ii) it is too irregular to be easily described in traditional Euclidean geometric language; (iii) it is self similar, at least approximately; (iv) it has a Hausdorf dimension which is greater than its topological dimension, while this requirement is not met by space-filling curves such as the Hilbert curve; (v) it has a simple and recursive definition.

First described in: B. Mandelbrot, *Les objets fractals: forme, hasard et dimension*, (Flammarion, Paris, 1975).

More details in: K. Falconer, *Fractal Geometry: Mathematical Foundations and Applications* (John Wiley and Sons, Chichester, 2003).

fractional quantum Hall effect → **Hall effect**.

Franck–Condon excited state – an excitation of an electron in the potential adapted to the ground state.

Franck–Condon principle states that as nuclei, being heavy particles, are so much more massive than electrons, an electronic transition occurs faster than the nuclei can respond. It also states that for the transition probability not to be negligibly small it is necessary: (i) that there should be an overlap between the classically allowed regions of coordinates for the states participating in the transition, and (ii) that the classical velocities of the heavy particles within the region of the overlap should not be very different for these states. This principle explains the fact that in solids a luminescent center emits light at a longer wavelength than it absorbs, and that in order to impel an electron optically from an impurity level into the conduction band the necessary minimum energy is greater than the energy difference between the bottom of the conduction band and the impurity level.

First described in: J. Franck, *Elementary processes of photochemical reactions,* Trans. Faraday Soc. **21**(3), 536–542 (1925); E. Condon, *A theory of intensity distribution in band systems,* Phys. Rev. **28**(6), 1182–1201 (1926).

Franck–Hertz experiment first demonstrated that intrinsic energy of atoms could not be changed instantaneously. It was done by recording the kinetic energy lost by electrons in inelastic collisions with atoms.

First described in: J. Franck, G. Hertz, *Über Zusammenstösse zwischen Elektronen und den Molekülen des Quecksilberdampfes und die Ionisierungsspannung desselben,* Verh. Deutsche Phys. Ges. **15**(20), 929–934 (1914).

Recognition: in 1925 J. Franck and G. Hertz received the Nobel Prize in Physics for their discovery of the laws governing the impact of an electron upon an atom.

See also www.nobel.se/physics/laureates/1925/index.html.

Frank partial dislocation – a partial dislocation whose **Burger's vector** is not parallel to the fault plane, so that it can only diffuse and not glide, in contrast to a **Shockley partial dislocation**.

First described in: F. C. Frank, W. T. Read, *Multiplication processes for slow moving dislocations,* Phys. Rev. **79**(4), 722–723 (1950).

Frank–Read source – a self-regenerating configuration of dislocations from which, under the action of applied stress, successive concentric loops of dislocations can be thrown off in a glide plane. It provids a mechanism for continuing slip in a crystal and an increase in its dislocation content, without essential limit, through plastic deformation.

First described in: F. C. Frank, W. T. Read, *Multiplication processes for slow moving dislocations*, Phys. Rev. **79**(4), 722–723 (1950).

Frank–Van der Merwe growth mode (of thin films) – layer-by-layer growth of thin films during their deposition as illustrated in Figure F.4.

It arises when deposited atoms are more strongly attracted to the substrate than they are to themselves.

First described in: F. C. Frank, J. H. van der Merwe, *One-dimensional dislocation. II. Misfitting monolayers and oriented overgrowth*, Proc. R. Soc. A **198**, 216–225 (1949).



Figure F.4 Frank–Van der Merwe growth mode during thin film deposition.

Franz–Keldysh effect – an effect of an electric field on the optical absorption edge in semiconductors. It is illustrated in Figure F.5, where band structure of a semiconductor under external biasing is sketched. An optically induced transition of an electron from the valence into conduction band in an undisturbed semiconductor can occur only if two states have an energy separation $\Delta E \leq h\nu$, where ν is the light frequency. Moreover, the states have to overlap in space. Interband light absorption in a semiconductor is impossible if $h\nu$ is smaller than the band gap E_g because there are no available states for corresponding electron transitions.

Electric biasing of a semiconductor changes the states in both valence and conduction bands provided that the states are present at all energies. Their overlap in space depends on the difference in energies. It is strong if $\Delta E > E_g$, when the oscillating part of the wave functions overlap. Meanwhile, only the tails of the wave functions overlap if $\Delta E < E_g$, and this decays rapidly with an increase of $E_g - \Delta E$. Thus the absorption edge gains a tail tunneling into the previously forbidden gap, as well as due to changes in the wave function. Electron transitions in such conditions are considered as photo-assisted field-induced tunneling across



Figure F.5 Interband electron transitions determining light absorption in an electrically biased semiconductor

the band gap. They result in the shift of the absorption edge to a lower energy range. The related oscillations in imaginary part of the **dielectric function** above the band gap is known as **Franz–Keldysh oscillations**.

First described in: W. Franz, *Einfluss eines elektrischen Felds auf eine optische Absorptionskante,* Z. Naturforsch. A**13**(6), 484–489 (1958) – in German; and independently in: L. V. Keldysh, *Effect of a strong electric field on the optical properties of non conducting crystals,* Zh. Eksp. Teor. Fiz. **34**(5), 1138–1141 (1958) – in Russian.

Franz–Keldysh oscillations → **Franz–Keldysh effect**.

Fraunhofer diffraction – diffraction of radiation passed through an aperture and registered at a distance from it so large that waves from the virtual sources at the aperture arrive in phase at a point on the normal to the screen used for registration.

Fraunhofer lines – a set of dark lines appearing against the bright background of the continuous solar spectrum. The lines are mainly produced by absorption of light by the cooler gases in the Sun's outer atmosphere at frequencies corresponding to the atomic transition frequencies in particular chemical elements composing these gases. Some of the lines are the result of the absorption by oxygen in the Earth's atmosphere. Characteristics of the major Fraunhofer lines are presented in the Table F.1.

First described by W. H. Wollaston in 1802, then systematically studied by J. von Fraunhofer in 1814 and *published in*: J. Fraunhofer, Gilberts Ann. **56**, 264 (1817).

Table F.1 Major Fraunhofer lines.

Designation	Element	Wavelength (Wl) nm	Designation	Element	Wl nm
y	O_2	898.765	c	Fe	495.761
Z	O_2	822.696	F	H β	486.134
A	O_2	759.370	d	Fe	466.814
B	O_2	686.719	e	Fe	438.355
C	H α	656.281	G′	H γ	434.047
a	O_2	627.661	G	Fe	430.790
D_1	Na	589.592	G	Ca	430.774
D_2	Na	588.995	h	H δ	410.175
D_3 (or d)	He	587.5618	H	Ca^+	396.847
e	Hg	546.073	K	Ca^+	393.368
E_2	Fe	527.039	L	Fe	382.044
b_1	Mg	518.362	N	Fe	358.121
b_2	Mg	517.270	P	Ti^+	336.112
b_3	Fe	516.891	T	Fe	302.108
b_4	Fe	516.751	t	Ni	299.444
b_4	Mg	516.733			

Fredkin gate → **quantum logic gate**.

free electron laser – a **laser** producing **stimulated emission** by passing a beam of free electrons (not bound to an atom or molecule) through an undulator or ''wiggler.'' The undulator creates a magnetic field of alternating polarity (in another version it guides the electrons along a helical path), causing the electrons to ''wiggle" and thus release radiation. It covers a wide range of wavelengths – from the soft X-ray region to millimeters.

free energy – a state function of a system under consideration. There are two commonly used notations for it. The **Helmholtz free energy** is $F = U - TS$, where U is the internal energy, S is the **entropy**, T is the temperature. The **Gibbs free energy** is $G = H - TS = U + PV - TS = F + PV$, where H is the **enthalpy** of the system, P is the pressure, and V is the system volume. These functions serve immediately to give the maximum work available from the system in an isothermal process.

Frenkel defect – a crystal defect consisting of a lattice vacancy and a host interstitial atom. It is also known as a **Frenkel pair**.

First described in: J. Frenkel, *Über die Wärmebewegung in festen und flüssigen Körpern*, Z. Phys., **35**(8–9), 652–669 (1926).

Frenkel excitation – an excitation of electron-hole pairs with a distance between electron and hole, called the **exciton Bohr radius**, that is smaller than the length of the lattice **unit cell**. Such excited pairs are called **Frenkel excitons**. An alternative case is represented by **Wannier excitation** and **Wannier excitons**.

First described in: J. Frenkel, *On the transformation of light into heat in solids. I*, Phys. Rev. **37**(1), 17–44; J. Frenkel, *On the transformation of light into heat in solids. II*, Phys. Rev. **37**(10) 1276–1294 (1931).

Frenkel excitons → **Frenkel excitation**.

Frenkel pair → **Frenkel defect**.

Frenkel–Poole emission – an electric field assisted thermal excitation of trapped electrons into the conduction band in solids. It is also known as **Frenken–Poole law** or field-induced emission. Insulators and semiconductors display in high electric fields an increase in their electrical conductivity, which finally leads to a breakdown. The dependence of the conductivity on the electric field was represented by Poole in an exponential way (**Poole law)**. The Frenkel–Poole law differs from the Poole law by the substitution for the electric field of the square root of the electric field itself. Finally, the current related to the Frenkel–Poole emission is defined as

$$J = CE \exp\left[-\frac{e}{k_B T}\left(\phi_b - \sqrt{\frac{eE}{\pi\epsilon_i}}\right)\right],$$

where C is a constant in terms of the trapping density in the insulator (semiconductor), E is the strength of the electric field, ϕ_b the barrier height, and ϵ_i the dynamic permittivity.

First described in: H. H. Poole, *On the dielectric constant and electrical conductivity of mica in intense field*, Phil. Mag. **32**, 112–129 (1916); J. Frenkel, *On the theory of electrical breakdown of dielectrics and semiconductors*, Technical Physics USSR **5**, 685–687 (1938); J. Frenkel, *On pre-breakdown phenomena in insulators and electronic semi-conductors*, Phys. Rev. **54**(8), 647–648 (1938).

Frenkel–Poole law → **Frenkel–Poole emission**.

Fresnel diffraction – the diffracted field is studied at a distance from the aperture, which is large compared with the wavelength of the diffracting radiation and the aperture dimensions, but yet not so large that the phase difference between the waves from the aperture sources can be neglected, even along the normal to the screen used for registration. It contrasts with **Fraunhofer diffraction**.

Fresnel law states the conditions of interference of polarized light: (i) two rays of light emanating from a common polarized beam and polarized in the same plane interfere in the same manner as ordinary light, (ii) two rays of light emanating from a common polarized beam and polarized at right angles to each other will only interfere if they are brought into the same plane of polarization, (iii) two rays of light polarized at right angles and emanating from ordinary light will not interfere if brought into the same plane of polarization.

First described by A. J. Fresnel in 1823.

friction force theory (Hertz theory) describes the perfectly elastic, nonadhering case of the contact between two spheres of radii R_1, R_2, **Young's moduli** E_1 and E_2, Poisson ratio ν_1 and ν_2, and external applied load N. The friction force becomes $F_f = \tau\pi(R^*/K)^{2/3}N^{2/3}$, where τ is the **shear modulus**, $R^* = R_1R_2/(R_1 + R_2)$, $1/K = (3/4)(\frac{1-\nu_1^2}{E_1} + \frac{1-\nu_2^2}{E_2})$. Here the **real contact area** A_R and the applied load N are related through the formula $A_R = \pi(R^*/K)^{2/3}N^{2/3}$. When $R_2 = \infty$ the contact is between a sphere and a flat surface and $R^* = R_1$.

This theory does not take into account **adhesion** force at the interface.

First described in: H. Hertz, *Über die Berührung fester elastischer Körper*, J. Reine Angew. Math **92**, 156–171 (1881).

friction force microscopy – an **atomic force microscopy** measuring forces along the scanning direction. It is used for atomic scale and micro scale studies of friction and lubrication.

More details in: B. Bhushan, *Micro/nanotribology and materials characterization studies using scanning probe microscopy*, in: Handbook of Nanotechnology, edited by B. Bhushan (Springer, Berlin, 2004), pp. 497–541.

Friedel law states that X-ray or electron diffraction measurements cannot determine whether or not a crystal has a center of symmetry.

First described in: G. Friedel *Sur les symmétries cristallines que peut révéler la diffraction des rayons X*, C. R. **157**, 1533–1536 (1913).

Friedel oscillations – the oscillatory behavior of the screened potential of a point charge at large distances r as $\cos(2k_F r)/(k_F r)^3$, where k_F is the **Fermi wave vector**. The phenomenon originates from the singularity of the dielectric function at $q = 2k_F$. These oscillations, present in a variety of phenomena, depending on the context in which they are present, are also called **Ruderman–Kittel oscillations**.

First described in: J. Friedel, *The distribution of electrons around impurities in univalent metals*, Phil. Mag. **43**(2), 153 (1952); M. A. Ruderman, C. Kittel, *Indirect exchange coupling of nuclear magnetic moments by conduction*, Phys. Rev. **99**(1), 96–102 (1954).

Fröhlich interaction → **phonon**.

***f*-sum rule** → **Kuhn–Thomas–Reiche sum rule**.

Fulcher bands of hydrogen – a system of bands of molecular hydrogen, which are preferentially excited by a low-voltage discharge. They consist of a number of regularly spaced lines in the red and green spectral range.

First described in: G. S. Fulcher, *Spectra of low-potential discharges in air and hydrogen*, Astrophys. J. **37**, 60 (1913).

fullerene – a carbon nanostructure in which 60 or 70 carbon atoms are bound together in a closed hollow cage having the form of a ball. The designation fullerenes is taken from the name of an American architect, R. Buckminster-Fuller, who had designed a dome having the form of a football for the 1967 Montreal World Exhibition.

The prototype fullerene is C_{60}, a molecule formed out of 60 carbon atoms distributed on a sphere with a diameter of 0.7 nm. These carbon atoms are assembled in the form of a truncated dodecahedron with a carbon atom sitting at each corner of the polyhedron. It is shown in Figure F.6.

The carbon atoms outline 20 hexagons and 12 pentagons, the latter giving rise to the curvature and thus enabling the closed quasi spherical structure of the molecule. Valence electrons of the carbon atoms are predominantly sp^2 hybridized. There is also some, typical for a diamond admixture, sp^3 hybridization due to the finite curvature of the molecule.



Figure F.6 Structure of C_{60} fullerene.

First described in: E. Osawa, Kagaku (Kyoto) **25**, 854–863 (1970) – in Japanese, prediction of the truncated icosahedron isomer of C_{60}; D. A. Bochvar, E. G. Gal'perin, *About hypothetical systems: carbododekaedr, s-icosahedron and carbo-s-icosahedron*, Dokl. Akad. Nauk SSSR **209**, 610–612 (1973) – in Russian, Proc. Acad. Sci. USSR **209**, 239–241 (1973) – in English, first theoretical simulation of C_{60} cluster; H. W. Kroto, R. F. Curl, R. E. Smalley, J. R. Heath, *C-60 buckminsterfullerene*, Nature **318**(6042), 162–163 (1985) – fabrication and beginning of experimental study of C_{60} fullerenes.

Recognition: in 1996 H. W. Kroto, R. F. Curl and R. E. Smalley received the Nobel Prize in Chemistry for their discovery of fullerenes.

See also www.nobel.se/physics/laureates/1996/index.html.

fullerite – a solid-state compact manifestation of **fullerene**s and related carbon nanostructures in which these carbon nanounits form a crystal-type lattice.

Pure solid C_{60} fullerite has an **FCC** crystal structure with relatively small **van der Waals** cohesive energy. The fullerite does not appear to melt, but rather sublimes at low pressure. Below the structural phase transition point (~257 K) the fullerite structure transforms into a simple cubic one. In this structure, molecules with different orientations make up a larger unit cell than the FCC cell: the corner and face-centre molecules become inequivalent, that is there are four C_{60} molecules in the crystal basis.

Fullerites are harder than diamond. Ultrahard fullerites have a hardness value of 310 ± 40 GPa, while diamond is characterized by the maximum hardness of about 230 GPa.

Pure C_{60} fullerite is a semiconductor with a bandgap of 1.6 eV, a value reasonably close to the **HOMO–LUMO** gap of the free molecule.

full potential augmented-plane-wave (FLAPW) method – one of the most powerful schemes for electronic structure calculations of solids within the **density functional theory**. It is based on the **augmented plane wave method** extended by the assumption of no shape approximations for the charge density and the potential. Both the charge density and the effective one-electron potential are represented by the same analytical expansion, that is by a Fourier representation in the interstitial region, in spherical harmonics inside the spheres, and for surface and thin film calculations a two-dimensional Fourier series in the vacuum region. Thus, the charge density $\rho(\mathbf{r})$ is given (with a similar representation for the effective potential) by

$$\rho(\mathbf{r}) = \begin{cases} \sum_i \rho_j \exp i\mathbf{G_j} \cdot \mathbf{r} & \text{for } \mathbf{r} \text{ interstitial} \\ \sum_{lm} \rho_{lm}^{\alpha}(r_\alpha) Y_{lm}(r_\alpha) & \text{for } \mathbf{r} \text{ inside the sphere } \alpha \\ \sum_q \rho_q(z) \exp \mathrm{i}\mathbf{K}_\mathbf{q}^{\parallel} \cdot \mathbf{r} & \text{for } \mathbf{r} \text{ in vacuum} \end{cases}$$

where $\mathbf{G}_j$ denote reciprocal lattice vectors in the bulk, $\mathbf{K}_q$ reciprocal lattice vectors in vacuum and Y_{lm} are the spherical harmonics. The coefficients in the equations are used in each iteration to create the **Coulomb potential** via the solution of the **Poisson equation** and to construct the exchange-correlation potential. These coefficients for the input and output densities are also used to perform the self-consistency procedure mixing at each iteration for input and output density.

First described in: E. Wimmer, H. Krakauer, M. Weinert, A. J. Freeman, *Full-potential self-consisted linearized-augmented-plane-wave method for calculating the electronic structure of molecules and surfaces: O_2 molecule*, Phys. Rev. B **24**(2), 864–875 (1981).

More details in: E. Wimmer, A. J. Freeman, *Fundamentals of the electronic structure of surfaces*, in: Handbook of Surface Science, Vol. 2, edited by K. Horn, M. Scheffler, (Elsevier Science B.V., 2000), pp. 1–92.

functionalization (of surfaces) – design, tailoring and preparation of surfaces that are able to define, induce and control distinct architecture and outgrowth. In particular in the case of biofunctional surfaces one must be able to match the sophisticated (bio)**recognition** ability of biological systems on the nanoscale as well as on larger length scales.

FWHM – an acronym for a **f**ull **w**idth at **h**alf **m**aximum, which is a parameter used to characterize optical spectral lines.

G

From gain-guided laser to gyromagnetic frequency

gain-guided laser → **double heterostructure laser**.

galvanoluminescence – emission of light produced by the passage of an electrical current through an appropriate electrolyte in which an electrode, made of certain metals such as aluminum or tantalum, has been immersed.

gamma function $\Gamma(x) = \int_0^\infty y^{x-1} \exp(-y)\mathrm{d}y$, where x is a real number greater than zero. It can be also expressed as a contour integral: $\Gamma(x) = 1/(\exp(\mathrm{i}2\pi x) - 1) \int_C y^{x-1} \exp(-y)\mathrm{d}y$, where the contour C denotes a path which starts at $+\infty$ on the real axis, passes round the origin in the positive direction and ends at $+\infty$ on the real axis. The initial and final values of the argument are taken to be 0 and 2π respectively.

gas immersion laser doping (GILD) – an introduction of doping atoms contained in a gas ambient, for example BCl_3, into a semiconductor, for example silicon, by means of laser beam irradiation of the semiconductor making its surface amorphous. Doped layers of less than 20 nm thickness with a sharp doping impurity profiles are formed.

First described in: G. Kerrien, J. Boulmer, D. Débarre, D. Bouchier, A. Grouillet, D. Lenoble, *Ultra-shallow, super-doped and box-like junctions realized by laser-induced doping*, Appl. Surf. Sci. **186**(1–4), 45–51 (2002).

Gaussian distribution – the function describing how a certain property is distributed among members of a group, also called the frequency distribution, for the case when deviations of the members of the set from some assigned values are the algebraic sum of a very large number of small deviations. It is of the form $f(x) = 1/(\sqrt{2\pi}\sigma) \exp\{-1/2[(x - \overline{x})/\sigma]\}$, where $\overline{x} = 1/n \sum_{k=1}^{n} x_k$ is the mean value of x and $\sigma^2 = 1/n \sum_{k=1}^{n} (x_k - \overline{x})^2$ is the mean square deviation of x. This distribution is also called the **normal distribution**.

First described by K. F. Gauss in 1809.

Gauss theorem states that the total electric flux from a charge q is $\int_S D\mathrm{d}S = \int_V \nabla D\mathrm{d}v = 4\pi \int_V \rho\mathrm{d}v = 4\pi q$, where D is the flux of electric induction, ρ is the bulk density of the charge, and S is any surface surrounding the volume V, which contains this charge. In the magnetic case, since $\nabla B = 0$ one has $\int_S B\mathrm{d}S = 0$.

First described by K. F. Gauss in 1830.

gel → **sol–gel technology**.

gel point indicates the stage at which a liquid begins to exhibit increased viscosity and elastic properties.

gene – a constituent part or zone of a **chromosome**. It represents a **nucleotide** sequence of **DNA** that codes for a protein. It determines a trait in an organism.

gene mapping – a linear map determining the relative position of **genes** along a **chromosome** or plasmid. Distances are established by linkage analysis and measured in linkage units.

generalized gradient approximation (GGA) assumes that the exchange-correlation energy in solids is a function of the electron concentration n and its gradients ∇n, that is $E_{xc} = \int n(\mathbf{r})\epsilon_{xc}(n(\mathbf{r}), \nabla n(\mathbf{r}))\mathrm{d}\mathbf{r}$ where ϵ_{xc} is the exchange-correlation energy per electron for the electron gas at a given point in space $\mathbf{r}$. The combined exchange-correlation function is typically split up into two additive terms ϵ_x and ϵ_c for exchange and correlation ones, respectively.

First described in: D. C. Langreth, J. P. Perdew, *Theory of nonuniform electronic systems. I. Analysis of the gradient approximation and a generalization that works,* Phys. Rev. B **21** (12), 5469–5493 (1980).

More details in: J. P. Perdew, *Density functional approximation for the correlation energy of the inhomogeneous electron gas,* Phys. Rev. B **33** (12), 8822–8824 (1986); J. P. Perdew, Y. Wang, *Accurate and simple density functional for the electronic exchange energy: generalized gradient approximation,* Phys. Rev. B **33** (12), 8800–8802 (1986).

genetics – a field of science studying properties of single **genes** or groups of genes.

genome – a complete **DNA** sequence of one set of **chromosomes** in an organism. The chromosome set is species specific for the number genes and linkage groups carried in genomic DNA.

genomics – a field of science studying global properties of a **genome** (DNA sequence) of organisms.

g-factor – a ratio of the magnetic momentum of a particle to its mechanical momentum. It is defined by $g\mu_B \equiv -\gamma\hbar$, where γ is the gyromagnetic ratio (the ratio of the magnetic moment to the angular momentum). For an electron spin $g = 2.0023$.

GGA – an acronym for a **generalized gradient approximation**, which is an approach used for calculation of electronic band structure of solids.

GHZ theorem → **Greenberger–Horne–Zeilinger theorem**.

giant magnetoresistance effect – dramatic change in the resistance of layered magnetic thin-film structures composed of alternating layers of a nonmagnetic material between differently magnetized **ferromagnetic** materials when placed in a magnetic field. The effect is observed when the resistance of the structure is measured by the current passing either parallel to the layers (**C**urrent **I**n **P**lane – **CIP** geometry) or perpendicular to the layer plane (**C**urrent **P**erpendicular to **P**lane – **CPP** geometry).

A thin-film structure with a parallel geometry of the observation of the giant magnetoresistance effect is schematically shown in Figure G.1.



Figure G.1 Giant magnetoresistance effect measured with a current flowing in the plane of a layered magnetic material sandwich: antialigned magnetic moments – high resistance, aligned magnetic moments – low resistance.

The as-deposited ferromagnetic layers have opposite magnetizations that can be achieved by their deposition in the magnetic fields of opposite orientations. In the absence of the magnetic field the resistance measured by current flowing in the plane of the layers is the greatest when the magnetic moments in the alternating layers are oppositely aligned. The spin exclusion results in high interface scattering and forces the current to flow within narrowed pathways.

The resistance is the smallest when the magnetic moments become oriented all in one direction in the external magnetic field. The magnetic field required to achieve all magnetization states to be parallel (lowest resistance) is commonly termed the saturation field. The resistance decrease can reach a few hundreds % at low temperatures. The most pronounced effect is observed in Fe/Cr and Co/Cu multilayer structures. It increases with the number of layers and reaches its maximum for approximately 100 periods at layer thicknesses of a few nanometers.

Measurements of magnetoresistance in a perpendicular geometry yield a larger effect because of the elimination of the shunting current passing through intermediate nonmagnetic layers separating ferromagnetic layers. In this case all the carriers must undergo spin scattering at every interface when traversing the layered structure. However, the low resistance of all-metal structures requires the application of **nanolithography** techniques to fabricate vertical elements with very small cross-section in order to get detectable resistance variation. Figure G.2 presents schematically the main features of the vertical transport. When the magnetizations of the two ferromagnetics are antialigned, the spin polarized carriers coming into the nonmagnetic layer from one ferromagnetic layer cannot be accommodated in the other ferromagnetic layer. They are scattered at the interface giving rise to the high resistance. In contrast, aligned magnetizations of both ferromagnetics ensure identity in the spin polarization of injected electrons and electron states in the next ferromagnetic layer. Thus, the interface scattering is minimized, which correspond to the lowest vertical resistance of the structure.



Figure G.2 Spin-polarized transport across a layered ferromagnetic /nonmagnetic /ferromagnetic structure: antialigned magnetic moments – high resistance, aligned magnetic moments – low resistance.

The spin relaxation length has proved to be much longer than the typical thickness of the layers, that is around 10 nm. An electron can pass through many layers before its spin orientation is changed. Within this length, each magnetic interface can act as a spin filter. The more scattering interfaces an electron interacts with, the stronger the filtering effect. This explains the increase in the giant magnetoresistance effect with the number of layers.

The interfacial spin scattering itself ultimately derives from lattice matching of the contacting materials and from the degree to which their conduction bands at the **Fermi level** are matched at the interface. For example, the interfaces in the popular Fe/Cr structure are formed by two **bcc** lattice matched metals and the d conduction band of chromium (paramagnetic) closely matches the minority (spin down) d conduction band of iron. There is no close match to the conjugate majority (spin up) d conduction band of iron. This suggests severe discrimination between spin up and spin down electrons at the interface. As a result, the profound giant magnetoresistance effect is observed.

A thin-film structure consisting of two ferromagnetic layers with different magnetic properties is called a **spin valve**. The most commonly used method of attaining anti-parallel orientation of two magnetic films in a spin valve structure is to deposit two ferromagnetic materials that respond differently to magnetic fields, for instance cobalt and permalloy ($Ni_{80}Fe_{20}$). The coercivity of permalloy is smaller than that of cobalt. Thus, if both a permalloy film and a cobalt film are initially saturated in the same direction (low resistance state) and then a reversed magnetic field is applied having a value larger than the coercivity of the permalloy film but less than the coercivity of the cobalt film, the anti-parallel magnetic orientations (high resistance state) can be attained.

An improvement in making the two magnetic layers with different magnetic behavior is the use of an **antiferromagnetic** in contact with one of the ferromagnetic films to effectively ''pin'' the magnetization in the ferromagnetic layer. Under proper deposition and annealing conditions, the antiferromagnetic and the ferromagnetic layers couple at their interface. This coupling pins the ferromagnetic layer to fields of typically about 10^4 Am^{-1}, and even if much higher fields are applied, the original state of the pinned layer is restored upon relaxation of the field.

A further refinement of antiferromagnetic pinning involves the strong antiparallel coupling between two magnetic films with a thin interlayer of certain metals, such as ruthenium. The pair of ferromagnetic films can be coupled antiparallel with an equivalent field of about 10^5 Am^{-1}, well above the normal applied fields used in most devices. This structure is commonly called a synthetic antiferromagnetic. When one of the ferromagnetic layers in the synthetic antiferromagnetic is then pinned on an outside surface with an antiferromagnetic layer, the resulting structure is very stable to quite large fields and to temperatures approaching the **Néel temperature** of the antiferromagnetic. This allows for wide margins for magnetic fields where the structure can be in the high-resistance state.

There is another variant of the spin valve structure, that is the so-called **pseudo-spin valve**. It has two magnetic layers that have mismatched properties so that one tends to switch at lower fields than the other. No pinning layer is used and the two magnetic layers may be of the same composition, but different thickness, if the composite film layers are etched into small areas. In this case, the small lateral size of the structure contributes demagnetizing fields, which causes the thinner of the two film layers to switch at lower magnetic fields than the thicker film layer. Without switching the hard layer, the magnetization of the soft layer can be manipulated to be parallel or antiparallel to the hard layer. The resistance is the lowest at the fields where magnetizations of both layers are aligned with each other.

Spin valve and pseudo-spin valve structures usually have magnetoresistance values at room temperature of between 5% and 10% and saturation fields of between 800 and 8000 Am^{-1}.

First described in: M. N. Baibich, J. M. Broto, A. Fert, F. N. Van Dau, F. Petroff, *Giant magnetoresistance of (001)Fe/(001)Cr magnetic superlattices,* Phys. Rev. Lett. **61**(21), 2472–2475 (1988); G. Binasch, P. Grünberg, F. Saurenbach, and W. Zinn, *Enhanced magnetoresistance in layered magnetic structures with antiferromagnetic interlayer exchange*, Phys. Rev. B **39**(7), 4828–4830 (1989).

Recognition: in 2007 A. Fert and P. Grünberg received the Nobel Prize in Physics for the discovery of giant magnetoresistance.

See also www.nobel.se/physics/laureates/2007/index.html.

giant magnetoresistance nonvolatile memory – a thin-film memory device that employs the giant magnetoresistance effect. Giant magnetoresistance elements are fabricated in arrays in order to get a net of elements functioning as a memory. The principle is illustrated in Figure G.3.



Figure G.3 Fragment of random access memory constructed of giant magnetoresistance elements connected in series.

The elements are essentially spin valve structures that are arranged in series connected by conducting spacers to form a sense line. The sense line stores the information and has a resistance that is the sum of the resistances of its elements. Current is run through the sense line and amplifiers at the ends of the lines detect the changes in the total resistance. The magnetic fields needed to manipulate the magnetization of the elements are provided by additional lithographically defined wires passing above and below the elements. These wires cross the sense line in an *xy* grid pattern with intersection at each of the giant magnetoresistance information storage elements. The wire passing parallel to the sense line acts as a world writing line and the wire crossing the sense line perpendicularly acts as a bit writing line. All the lines are electrically isolated. When current pulses are run through world and bit lines, they generate magnetic fields controlling the resistance of giant magnetoresistance elements.

A typical addressing scheme uses pulses in the world and bit lines that are half-select. This means that the field associated with a world-line pulse is half that needed to reverse the magnetization of the giant magnetoresistance element. Where any two lines in the *xy* grid overlap, the two half-pulses can generate a combined field that is sufficient to selectively reverse a soft layer or, at higher current levels, sufficient to reverse a hard layer also. Typically one pulse rotates the layer 90°. Through this *xy* grid, any element of an array can be addressed either to store information or to interrogate the element.

The exact information storage and addressing schemes may be highly varied. One scheme may store information in the soft layer and use ‘‘destroy’’ and restore procedure for interrogation. Alternatively, another scheme could construct the individual giant magnetoresistance elements so that high-current pulses are used to store information in the hard layer. Low-current pulses can then be used to ''wiggle'' the soft layer to interrogate the element by sensing the change in resistance, without destroying and restoring the information. There are many additional variations on these schemes, and the exact scheme used is often proprietary and dependent on the specific requirements of the memory application.

giant magnetoresistance read head – a thin-film read head that employs the **giant magnetoresistance effect**. It is also called a **spin valve** read head. The head reads the magnetic bits that are stored on the surface of discs or tapes in the form of differently oriented magnetic domains as small as 10–100 nm. Where the heads of two of the oppositely magnetized domains meet, uncompensated positive poles generate a magnetic field directed out of the media perpendicular to the domain surface that is a positive domain wall. In the place where the tails of two domains meet, the walls contain uncompensated negative poles that generate a sink for magnetic lines of flux returning back into the media, that is a negative domain wall. The head senses the changes in the direction of the magnetic field at the domain walls.



Figure G.4 Schematic representation of a giant magnetoresistance read head that passes over recording media containing magnetized regions.

The principles of the read head and its operation are illustrated in Figure G.4. The sensing element of the head is a typical spin valve consisting of two layers: one with easily reversed magnetization and the other with a fixed (or difficult-to-reverse) magnetization.

Magnetic momentum in the magnetically soft layer is parallel to the plane of the media carrying magnetic domains in the absence of any applied fields. The magnetic momentum in the magnetically hard layer is perpendicular to the media plane. When the head passes over a positive domain wall, the magnetic field existing there pushes the magnetization of the easily reversed layer up. When the head passes over a negative domain wall, the magnetic momentum is pulled down. As soon as magnetization direction in the soft layer responds to the fields that emanate from the media by rotating either up or down, the measured change in the resistance is sensed by the current passing through the spin valve structure. Spin valve read heads enable very high aerial packing densities for hard drives, up to 25 Gbits per square inch.

More information in: Magnetic Multilayers and Giant Magnetoresistance: Fundamentals and Industrial Applications, edited by U. Hartmann, Springer Series in Surface Sciences, Vol. **37** (Springer, Berlin, 2000).

Gibbs distribution (statistics) asserts that the thermal equilibrium probability of finding an N particle system in an N particle stationary state of energy E at the temperature T is proportional to $\exp(-E/k_BT)$. It is generally valid for classical or quantum systems, whether or not they are weakly interacting. The **Maxwell–Boltzmann**, **Fermi–Dirac**, **Bose–Einstein distributions**, characterizing the occupation of single particle levels for weakly interacting particles or excitations, all follow from the Gibbs distribution in the appropriate special cases.

First described in: J. W. Gibbs, *On the equilibrium of heterogeneous substances*, Trans. Conn. Acad. **3**, 108–248 (1875); 227–229 (1876); 343–524 (1877).

Gibbs–Duhem equation connects the variations of the chemical potentials μ_i in a mixture containing n_i moles of species i, at given temperature and pressure in the form $\sum_i n_i \mathrm{d}\mu_i = \sum_i x_i \mathrm{d}\mu_i = 0$, where the mole fraction $x_i = n_i / \sum_i n_i$.

First described in: J. W. Gibbs, *On the equilibrium of heterogeneous substances*, Trans. Conn. Acad. **3**, 108–248 (1875), 227–229 (1876), and 343–524 (1877); P. Duhem, *Traité d'énergétique ou de thermodynamique générale*, (Gauthier-Villars, Paris, 1911).

Gibbs free energy → **free energy**.

First described in: J. W. Gibbs, *On the equilibrium of heterogeneous substances*, Trans. Conn. Acad. **3**, 108–248 (1875), 227–229 (1876), and 343–524 (1877).

Gibbs theorem states that the **entropy** change is zero for the process in which a perfect gas A occupying a volume ν and a perfect gas B occupying separately also volume ν are mixed isothermally so as to form a perfect gas mixture occupying a total volume ν.

First described in: J. W. Gibbs, *On the equilibrium of heterogeneous substances*, Trans. Conn. Acad. **3**, 108–248 (1875), 227–229 (1876), and 343–524 (1877).

giga- – a decimal prefix representing 10^9, abbreviated G.

GILD – an acronym for **gas immersion laser doping**.

Ginzburg–Landau equations – a pair of coupled differential equations relating a wave function Ψ representing superconducting electrons, a vector potential $\mathbf{A}$ at a point $\mathbf{r}$ representing a microscopic field in this point and the supercurrent $\mathbf{J}$:

$$\frac{1}{2m}\left(-\mathrm{i}\hbar\nabla - \frac{e}{c}\mathbf{A}\right)^2 \Psi + \frac{\partial F}{\partial \Psi^*} = 0,$$

$$\mathbf{J} = -\frac{ie\hbar}{mc}(\Psi^*\nabla\Psi - \Psi\nabla\Psi^*) - \frac{e^2}{mc}\Psi^*\Psi\mathbf{A},$$

where the free energy of the superconductor F can be represented by the series $F = F_0 + \alpha|\Psi|^2 + \beta/2|\Psi|^4$ with phenomenological parameters α and β.

Although the equations have some limitations, they are very useful for calculations of important characteristic length scales, for instance the penetration depth of a magnetic field, for different superconductors. In general, they provide the basis for most understanding of spatially varying superconducting states in solids.

First described in: V. L. Ginzburg, L. D. Landau, *To the theory of superconductivity*, Zh. Exp. Teor. Fiz. **20**(12), 1064–1082 (1950) – in Russian.

Recognition: in 2003 V. L. Ginzburg received the Nobel Prize in Physics for pioneering contributions to the theory of superconductors and superfluids.

See also www.nobel.se/physics/laureates/2003/index.html.

glass – a noncrystalline, inorganic mixture of various metallic oxides fused by heating with glassifiers such as silica, or boric or phosphoric oxides. Most glasses are transparent in the visible spectrum and up to about 2.5 μm in the infrared, but some are opaque such as natural obsidian. These are, nevertheless, useful as mirror blanks. Traces of some elements such as cobalt, copper and gold are capable of producing a strong coloration in glass. Laser glass contains a small amount of didymium oxide. Opal glass is opaque and white, with the property of diffusing light. Some opal glass has a thin layer of opal material flashed onto the surface of ordinary glass. Tempered glass has a high degree of internal strain, caused by rapid cooling, which gives it increased mechanical strength.

globular protein → **protein**.

glycolipids → **lipids**.

glycoluril → **cucurbituril**.

GNR – an acronym for a **graphene nanoribbon**.

Goldschmidt law states that crystal structure is determined by the ratios of the numbers of the constituents, the ratios of their size and their polarization properties.

First described in: V. M. Goldschmidt, T. Barth, G. Lunde, W. Zachariasen, *Geochemische Verteilungsgesetze: VII: Die Gesetze der Krystallochemie*, Skr. Norsk. Vid. Akademie, Oslo, Mat. Nat. Kl. **2** (1926), and *Geochemische Verteilungsgesetze: VIII: Untersuchungen über Bau und Eigenschaften von Krystallen*, Skr. Norsk. Vid. Akademie, Oslo, Mat. Nat. Kl. **8** (1926).

g permanence rule states that the sum of **g-factors** is the same for strong and weak magnetic fields for the same value of the magnetic quantum numbers.

First described in: W. Pauli, *Über die Gesetzmässigkeiten des anomalen Zeemaneffektes*, Z. Phys. **16**(3), 155–164 (1923).

Goodenough–Kanamori rules provide a description of the exchange interactions between magnetic atoms, and hence the magnetic ordering pattern, in terms of the relative orientation of valence orbitals on neighboring lattice sites. They state that if there is a large overlap between partly occupied orbitals at two magnetic ions, the superexchange interaction between them is strongly **antiferromagnetic** because of the **Pauli principle**, whereas overlap between partly occupied and unoccupied orbitals gives weakly **ferromagnetic** interaction due to **Hund rules**.

First described in: J. B. Goodenough, *Theory of the role of covalence in the perovskite-type manganites [La, M(II)]MnO*$_3$, Phys. Rev. **100**(2), 564–573 (1955); J. Kanamori, *Superexchange interaction and symmetry properties of electron orbitals*, J. Phys. Chem. Solids **10**(2–3), 87–98 (1959).

More details in: J. B. Goodenough, *Magnetism and the Chemical Bond* (Interscience, New York, 1963).

Grätzel solar cells = **dye-sensitized solar cells**.

graphene – the name given to a single layer of carbon atoms densely packed into a benzene-ring structure, thus being a two-dimensional honeycomb net made up of sp^2 bonded carbon atoms (for a picture of graphene → **carbon nanotube**). It is widely used to describe properties of many carbon-based materials, including graphite, large **fullerene**s, and carbon nanotubes. Graphene was isolated in 2004. Starting with a graphite crystal, layers of carbon atoms were peeled off one by one with adhesive tape until a single-layer flake was left. Graphene's conductivity never falls below a minimum value corresponding to the quantum unit of conductance, even when concentrations of charge carriers tend to zero. The **quantum Hall effect** in graphene occurs at half-integer filling factors. Electron transport is essentially governed by **Dirac**'s relativistic **equation**, and also **Berry phase** has been observed.

First described in: K. S. Novoselov, A. K. Geim, S. V. Morozov, D. Jiang, Y. Zhang, S. V. Dubonos, I. V. Grigorieva, A. A. Firsov, *Electric field effect in atomically thin carbon films*, Science **306**, 666–669 (2004); K. S. Novoselov, D. Jiang, F. Schedin, T. J. Booth, V. V. Khotkevich, S. V. Morozov, and A. K. Geim, *Two-dimensional atomic crystals*, PNAS, **102**(30), 10451–10453 (2005); K. S. Novoselov, A. K. Geim, S. V. Morozov, D. Jiang, M. I. Katsnelson, I. V. Grigorieva, S. V. Dubonos, A. A. Firsov, *Two-dimensional gas of massless Dirac fermions in graphene*, Nature **438**, 197–200 (2005); Y. Zhang, Y.-W. Tan, H. L. Stormer, P. Kim, *Experimental observation of the quantum Hall effect and Berry's phase in graphene*, Nature **438**, 201–205 (2005).

More details in: C. L. Kane, *Erasing electron mass*, Nature **438**, 168–169 (2005).

graphene nanoribbon (GNR) – the structure fabricated when **graphene** is etched or patterned along one specific direction, which in fact is a strip of graphene. It is a quasi-one-dimensional structure. The structure of graphene nanoribbons is closely related to that of **carbon nanotubes**, since they can be viewed as unrolled single-wall carbon nanotubes. Thus also in the case of graphene nanoribbons it is possible to describe the whole structure using only two indices. There are **armchair** and zigzag graphene nanoribbons. The main topological differences with respect to nanotube and graphene is related to the finite width, which implies two different atomic sites: bulk sites, with three neighboring carbon atoms, and edge sites, with only two C–C bonds. The GNRs with armchair-shaped edges are classified by the number of dimer lines across the ribbon width, and the ribbons with zigzag-shaped edges are classified by the number of zigzag chains across the ribbon width. These simple features of GNR have a great impact on both symmetry and electronic properties, for example the energy gap scales inversely with the ribbon width.

First described in: M. Fujita, K. Wakabayashi, K. Nakada, K. Kusakabe, *Peculiar localized state at zigzag graphite edge*, J. Phys. Soc. Jpn **65**(7), 1920–1923 (1996); M. Y. Han, B. Özyilmaz, Y. Zhang, P. Kim, *Energy band-gap engineering of graphene nanoribbons*, Phys. Rev. Lett. **98**(20), 206805 (2007).

Greenberg–Horne–Zeilinger states – multiparticle quantum states which have perfect correlations and such that these correlations are incompatible with a classical conception of locality: $|\Psi^{\pm}\rangle = 1/\sqrt{2}(|00\ldots0\rangle \pm |11\ldots1\rangle)$.

First described in: D. M. Greenberger, M. A. Horne, A. Shimony, A. Zeilinger, *Bell's theorem without inequalities*, Am. J. Phys. **58**(12), 1131–1143 (1990).

Greenberger–Horne–Zeilinger theorem, being an extension of **Bell's theorem** to three or more particles, shows that assumptions of the **Einstein–Podolsky–Rosen paradox** lead to predictions which are exactly opposite of those of quantum theory.

First described in: D. M. Greenberger, M. A. Horne, A. Zeilinger, *Going beyond Bell's theorem*, in: *Bell's Theorem, Quantum Theory, and Conceptions of the Universe*, edited by M. Kafatos (Kluver, Dordrecht, 1989), pp. 73–76.

Green's function arises in the solution w of the differential equation $\mathbf{L}w = f(\mathbf{x})$ satisfying certain boundary conditions. The operator $\mathbf{L}$ is a linear differential operator and $f(\mathbf{x})$ is a prescribed function of the n variables $(x_1, x_2, \ldots, x_n) = \mathbf{x}$ defined uniquely through a region Ω on whose boundary the prescribed boundary conditions are formulated. If one can find a function $G(\xi, \mathbf{x})$ such that this solution can be written in the form $w(\mathbf{x}) = \int_{\Omega} G(\xi, \mathbf{x}) f(\xi) d\xi$, the function $G(\xi, \mathbf{x})$ is called the Green's function corresponding to the operator $\mathbf{L}$ and the prescribed boundary conditions.

Introducing the n dimensional **Dirac delta function** as $\delta(\mathbf{x} - \xi) = \delta(x_1 - \xi_1) \ldots \delta(x_n - \xi_n)$ makes obvious that $G(\xi, \mathbf{x})$ is the appropriate solution of the differential equation $\mathbf{L}w = \delta(\mathbf{x} - \xi)$.

The name "Green's function" seems to have been applied to such a function for the first time by H. Burkhardt in 1894, because it is in some ways analogous to the function introduced in 1828 by George Green in his memoir on electricity and magnetism.

First described in: G. Green, *An essay on the application of mathematical analysis to the theories of electricity and magnetism* (1828). Reissued by Lord Kelvin in J. Reine Angew. Math. **39**, 73–89 (1850), **44**, 356–374 (1852), **47**, 161–221 (1854).

Green's theorem states that if $\mathbf{A} = (P, Q, R)$ is a vector each of whose components is a continuous function of x, y, z with continuous derivatives at each point of a simple volume V enclosed by a surface S then

$$\int_V\int\int \left(\partial P/\partial x + \partial Q/\partial y + \partial R/\partial z\right) \mathrm{d}x\mathrm{d}y\mathrm{d}z = \int_S\int (lP + mQ + nR)\mathrm{d}S,$$

where $(l, m, n) = \mathbf{n}$ are the direction cosine of the outward drawn normal to S.

First described in: G. Green, *An essay on the application of mathematical analysis to the theories of electricity and magnetism* (1828). Reissued by Lord Kelvin in J. Reine Angew. Math. **39**, 73–89 (1850), **44**, 356–374 (1852), **47**, 161–221 (1854).

Greenwood–Williamson theory reconciles **Amonton's law** and the **Bowden–Tabor law**. Taking two rough surfaces in contact through a large number of asperities (**multi-asperity contact model**) the **real contact area** depends linearly on the applied load.

This theory does not contemplate **adhesion** forces.

First described in: J. A. Greenwood, J. B. P. Williamson, *Contact of nominally flat surfaces*, Proc. R. Soc. London A, **295**, 300–319 (1966).

Grimm–Sommerfeld rule states that the absolute valency of an atom is numerically equal to the number of electrons engaged in attaching the other atoms.

First described in: H. G. Grimm, A. Sommerfeld, *Über den Zusammenhang des Abschlusses der Elektronengruppen im Atom mit den chemischen Valenzzahlen*, Z. Phys. **36**(1), 36–59 (1926).

ground state – the state of an entire system which is of minimum energy, in which, therefore, each electron is represented by an energy **eigenstate** corresponding to the lowest available energy level.

ground state depletion (GSD) microscopy → **fluorescence nanoscopy**.

First described in: S. W. Hell, M. Kroug, *Ground-state depletion fluorescence microscopy, a concept for breaking the diffraction resolution limit*, Appl. Phys. B **60**, 495–497 (1995).

group velocity → **wave packet**.

Grover algorithm – a quantum mechanical algorithm that would search an unsorted database of N elements in a time that scales roughly $N^{1/2}$ faster than any possible classical search algorithm. It supposes the following steps.

Step 1. Initialize the system to the superposition:

$$(1/N^{1/2}, 1/N^{1/2}, \dots, 1/N^{1/2});$$

that is, there is the same amplitude to be in each of the N states. This super position can be obtained in M (log N) steps.

Step 2. Repeat the following unitary operations $M(N^{1/2})$ times (the precise number of repetitions is important).

2 a. Let the system be in any state S: in case $C(S) = 1$, rotate the phase by π radians; in case $C(S) = 0$, leave the system unaltered.

2 b. Apply the diffusion transform D, which is defined by the matrix **D** as follows: $D_{ij} = 2/N$ if $i \neq j$ and otherwise $D_{ij} = -1 + 2/N$ (**D** can be implemented as a product of three elementary matrices).

Step 3. Measure the resulting state. This will be the state S_ν (that is the desired state that satisfies the condition $C(S_\nu) = 1$) with a probability of at least 0.5.

Note that the steps 1 and 2 are a sequence of unitary operations. The step 2 a is a phase rotation. In an implementation it would involve a portion of the quantum system sensing the state and then deciding whether or not to rotate the phase. It would do it in such a way so that no trace of the state of the system would be left after this operation, so as to ensure that paths leading to the same final state were indistinguishable and could interfere.

By having the input and output in quantum superpositions of states, one can find an object in $M(N^{1/2})$ quantum mechanical steps instead of $M(N)$ classical steps. This discovery started a flurry of theoretical activity searching for quantum computer applications.

First described in: L. K. Grover, *Quantum mechanics helps in searching for a needle in a haystack*, Phys. Rev. Lett. **78**(2), 325–328 (1997).

Grüneisen equation of state → **Grüneisen rules**.

Grüneisen rules are based on the **Grüneisen equation of state** for solids $PV + G(V) = \gamma E$, where P is the pressure, V is the molar volume, $G(V)$ depends on the interatomic potential energy, E is the energy of the atomic vibrations and γ is a dimensionless quantity. The **first rule** governs the change of the volume of a solid as $\triangle V = \gamma K_0 E$, where K_0 is the isothermal compressibility of the solid at absolute zero temperature. The **second rule** connects the volume coefficient of thermal expansion β and the molar specific heat of the solid C_ν in the form $\beta = \gamma K_0 C_\nu / V$.

First described in: E. Grüneisen, *Theorie des festen Zustandes einatomiger Elemente*, Ann. Phys. **39**, 257–306 (1912), and in *Handbuch der Physik*, **10** (Springer, Berlin, 1926).

GSD – an acronym for **ground state depletion (GSD) microscopy**.

Gudden–Pohl effect – a light flash that occurs when an electrical field is applied to a phosphor already excited by ultraviolet radiation.

First described in: B. Gudden; R. W. Pohl, *Über Ausleuchtung der Phosphoreszenz durch elektrische Felder*, Z. Phys. **2**(2), 192–196 (1920).

Gunn effect – generation of coherent microwaves when a constant electric field that exceed a critical threshold value of several thousand volts per centimeter is applied across a randomly oriented, short, n-type sample of GaAs or InP. The frequency of oscillations is approximately equal to the reciprocal of the carrier transit time across the length of the sample. The mechanism of observed oscillations is field-induced transfer of conduction band electrons from a low-energy, high-mobility valley to higher-energy, low-mobility satellite valleys.

First described in: J. B. Gunn, *Microwave oscillations of current in III-V semiconductors*, Solid State Commun. **1**(4), 88–91 (1963).

Gurevich effect – in electrical conductors with a pronounced phonon electron interaction, phonons carrying a thermal current in the presence of a temperature gradient tend to drag the electrons with them from hot to cold.

First described in: L. Gurevich, *Thermoelectric properties of conductors*, J. Phys. **9**, 477–488 (1945); ibid. **10**, 67–80 (1945).

GW approximation (GWA) is the approximation in which the self-energy of an electronic system of solids is calculated using **Green's function** G and screened Coulomb interaction W. The GWA may be regarded as a generalization of the **Hartree-Fock approximation** (HFA) but with a dynamically screened Coulomb interaction. The non-local exchange potential in the HFA is given by $\Sigma^x(\mathbf{r},\mathbf{r}') = \sum_{\mathbf{k}n}^{occ} \psi_{\mathbf{k}n}(\mathbf{r})\psi_{\mathbf{k}n}^*(\mathbf{r}')v(\mathbf{r}-\mathbf{r}')$. In the Green's function theory, the exchange potential is written as $\Sigma^x(\mathbf{r},\mathbf{r}',t-t') = \mathrm{i}G(\mathbf{r},\mathbf{r}',t-t')v(\mathbf{r}-\mathbf{r}')\delta(t-t')$, which when Fourier transformed yields the previous equation. The GWA corresponds to replacing the bare Coulomb interaction by a screened interaction $W : \Sigma(1,2) = \mathrm{i}G(1,2)W(1,2)$. This is physically well motivated especially in metals where the HFA leads to unphysical results such as zero density of states at the Fermi level, due to the lack of screening.

The GWA has been successful in predicting the quasiparticle systems such as free-electron like metals and semiconductors as well as Mott insulators and d- and f-band metals. It was also found that GWA gives a rather good description of the band gap of strongly correlated systems like NiO.

First described in: L. Hedin, *New method for calculating the one-particle Green's function with application to the electron-gas problem*, Phys. Rev. **139**(3A), A796–A823 (1965).

More details in: F. Aryasetiawan, O. Gunnarsson, *The GW method*, Rep. Prog. Phys. **61**(3), 237–312 (1998).

gyromagnetic effect – the rotation induced in a body by a change of its magnetization or magnetization resulting from a rotation.

gyromagnetic frequency – the term denoting the frequency of precession of a charged revolving particle of mass m placed in a magnetic field of strength H. This frequency is $qHp/(2mch)$, where q is the charge and p is the angular momentum of the particle.

H

From habit plane to hyperelastic scattering

habit plane – the crystallographic plane or system of planes along which certain phenomena such as twinning occur.

Hadamard gate → **Hadamard transformation** and **quantum logic gate**.

Hadamard operator produces self inverse operation forming superposition of states with equal coefficients → **Hadamard transformation**.

Hadamard product defines the product of two power series as the power series $P \times Q = \sum_{n=0}^{\infty} a_n b_n x^n$, where $P = \sum_{n=0}^{\infty} a_n x^n$ and $Q = \sum_{n=0}^{\infty} b_n x^n$.

Hadamard transformation – a unitary, orthogonal, real transformation. The basis functions could have only the value 1 and -1. In the matrix form we have

$$\mathbf{H} = \frac{1}{\sqrt{2}} \begin{pmatrix} 1 & 1 \\ 1 & -1 \end{pmatrix}.$$

Thus, one has, for example

$$\mathbf{H}|0\rangle = \frac{1}{\sqrt{2}}|0\rangle + \frac{1}{\sqrt{2}}|1\rangle$$

$$\mathbf{H}|1\rangle = \frac{1}{\sqrt{2}}|0\rangle - \frac{1}{\sqrt{2}}|1\rangle.$$

The Hadamard transformation matrix (called also **Hadamard gate**) is a special case of a generalized **qubit** rotation.

First described in: J. Hadamard, Bull. Sci. Math., **17**, 240–248 (1893).

Hagen–Rubens relation – an equation that links the reflectivity of a solid to the frequency of radiation and the conductivity of the solid: $R_{opt} = 1 - (f/\sigma)^{1/2}$, where f is the frequency of light, and σ is the electrical conductivity.

It applies at wavelengths long enough that the product of the frequency and the relaxation time is much less that unity.

First described in: E. Hagen, H. Rubens, *Über Beziehungen des Reflexions- und Emissionsvermögens der Metalle zu ihrem elektrischen Leitvermögen,* Ann. Phys. **11**(8b), 873–901 (1903).

half-metallic material – a material which can be considered in its electronic properties as a hybrid between a metal and a semiconductor or dielectric. Its main particular feature is that electrons at the Fermi level show complete one-direction spin polarization. For that reason half-metallic alloys and compounds have well pronounced **ferromagnetic** properties, making them prime targets for spintronic devices.

Typical examples of such materials are **diluted magnetic semiconductors** from $A^{II}B^{VI}$ and $A^{III}B^{V}$ groups, ternary compounds with the general formula AB_2O_4 (such as $Fe_3O_4 = FeFe_2O_4$), **Heusler alloys** with the general formula A_2MnB (such as Co_2MnSi), half Heusler alloys AMnB (such as NiMnSb), and the binary compound CrO_2. See Figure H.1.

First described in: R. A. de Groot, F. M. Mueller, P. G. van Engen, K. H. J. Buschow, *New class of materials: half-metallic ferromagnets*, Phys. Rev. Lett. **50**(25), 2024–2007 (1983) – coined the name of the half-metallicity phenomenon.

More details in: Half-metallic Alloys-Fundamentals and Applications, Lecture Notes in Physics, edited by P. H. Dederichs, I. Galanakis (Springer Verlag, Berlin, 2005).



Figure H.1 Normal metal, magnetic metal and half-metal.

halide – a chemical compound of an element wtith a halogen. .

Hall effect – in a conducting strip placed in magnetic field perpendicular to the direction of the current flow in the strip (see Figure H.2) the resistance across the current path linearly depends on the strength of the magnetic field. The electrons experience a **Lorentz force** that is perpendicular to both the magnetic field and their initial direction. They are pushed toward one side of the specimen (depending



Figure H.2 Sample geometry for measurements of the Hall effect.

on the direction of the magnetic field), giving rise to charge accumulation on that side as compared with the other. The voltage drop V measured along the current characterizes the material resistance $R = V/I$. The voltage V_H induced by the magnetic field across the current path is called **Hall voltage**. The related **Hall resistance** is defined as $R_H = V_H/I$.

In the classical Hall effect $R_H = B/(en)$, where B is the magnetic induction, e is the electron charge and n is the electron density per unit area in the strip. Most remarkably, the Hall resistance does not depend on the shape of the specimen. It increases linearly with the magnetic field, while longitudinal resistance R is predicted to be roughly independent of the magnetic field, as illustrated in Figure H.3 left. Because of its independence from the sample geometry, the classical Hall effect has become a standard technique for determination of the type, density and mobility of free carriers in metals and semiconductors.

When the Hall effect is measured at low temperatures in a sample containing two-dimensional electron gas (2DEG) in which electrons are confined to move only within the plane, the Hall resistance is found to deviate from classical behavior. At sufficiently high fields, a series of flat steps appear in the graph of the Hall voltage versus magnetic field (see Figure H.3 right), which is referred to as the **quantum Hall effect (QHE)**. At the plateaus of the Hall voltage the longitudinal voltage becomes zero. The Hall resistance at the position of the plateaus of the step is quantized to a few parts per billion to $R_H = h/(ie^2)$, where h is the Planck constant and i is an integer. Consequently this effect is called the **integer quantum Hall effect (IQHE)**. The effect is definitely material independent. The quantum of the resistance, h/e^2, as measured reproducibly with high precision via the integer quantum Hall effect, has become the resistance standard. The effect can be explained in terms of occupation of **Landau levels**.

Electrons moving in a perpendicular magnetic field are forced into circular orbits, following the **Lorentz force**. They perform a cyclotron motion with the angular frequency $\omega_c = eB/m$, called the **cyclotron frequency**, where m is the electron mass.



Figure H.3 Variation of the longitudinal voltage drop and the Hall voltage as a function of the magnetic field in classic and quantum Hall effect.

So far, available energy levels for electrons become quantized. These quantized energies are known as Landau levels. They are given by $E_i = (i + 1/2)\hbar\omega_c$ with $i = 1, 2, \ldots$. In an ideal perfect system containing a 2DEG these levels have a form of δ-function, as illustrated in Figure H.4. The gap between nearest levels is determined by the cyclotron energy $\hbar\omega_c$. The levels are broadened with temperature rise. Clearly one needs $k_B T \ll \hbar\omega_c$ to observe well-resolved Landau levels.

Electrons can only reside at the energies of Landau levels, but not in the gap between them. The existence of the gaps is crucial for the occurrence of the quantum Hall effect. Here 2DEG differs decisively from electrons in three dimensions. Motion in the third dimension, along the magnetic field, can add any amount of energy to the energy of the Landau levels, thus filling the gaps. Therefore, there are no energy gaps in three dimensions and the quantum Hall effect causes the background to disappear.

Two years after the discovery of the integer quantum Hall effect it was found that quantization i could take fractional values, like 1/3, 2/3, 2/5, 3/5 and so on. In general, $i = p/q$, where p and q are integers with q odd. The phenomenon got the name of **fractional quantum Hall effect (FQHE)**. As an explanation of the fractional quantum Hall effect it was supposed that electrons in a 2DEG placed in a strong magnetic field condense into an exotic new collective state, a quantum



Figure H.4 Occupation of Landau levels by electrons in 2DEG placed in a magnetic field at absolute zero temperature. $E_c = \hbar\omega_c$.

liquid, similar to the way in which collective states form in superfluid helium. A quantum of magnetic flux and an electron exist as a **quasiparticle** that carries a fractional charge. Such particles follow neither **Fermi–Dirac** nor **Bose–Einstein statistics**. Instead they obey special so-called fractional statistics.

First described in: E. H. Hall, *On a new action of the magnet on electric currents*, Am. J. Math. **2**, 287–292 (1879) – the classical effect; K. von Klitzing, G. Dorda, M. Pepper, *New method for high-accuracy determination of the fine-structure constant based on quantized Hall resistance*, Phys. Rev. Lett. **45**(6), 494–497 (1980) – the integer quantum Hall effect; D. C. Tsui, H. L. Störmer, A. C. Gossard, *Two-dimensional magnetotransport in the extreme quantum limit*, Phys. Rev. Lett. **48**(22), 1559–1562 (1982) and R. B. Laughlin, *Anomalous quantum Hall effect: an incompressible quantum fluid with fractionally charged excitations*, Phys. Rev. Lett. **50**(18), 1395–1398 (1983) – the fractional quantum Hall effect.

Recognition: in 1985 K. von Klitzing received the Nobel Prize in Physics for the discovery of the quantized Hall effect; in 1998 R. B. Laughlin, H. L. Störmer and D. C. Tsui received the Nobel Prize in Physics for their discovery of a new form of quantum fluid with fractionally charged excitations.

See also www.nobel.se/physics/laureates/1985/index.html.

See also www.nobel.se/physics/laureates/1998/index.html.

Hall resistance → **Hall effect**.

Hall voltage → **Hall effect**.

Hallwachs effect – the ability of ultraviolet radiation to discharge a negatively charged body in a vacuum.

First described in: W. Hallwachs, *Über den Einfluss des Lichtes auf electrostatisch geladene Körper,* Ann. Phys. **33**, 301–344 (1888).

halogens – F, Cl, Br, I, At.

Hamilton equations of motion form a set of first order symmetrical equations describing the motion of a classical dynamical system:

$$\dot{q} = \frac{\partial \mathbf{H}}{\partial p_i},$$

$$\dot{p} = -\frac{\partial \mathbf{H}}{\partial q_i},$$

with $i = 1, 2, \ldots,$ where q_i are generalized coordinates of the system, p_i is the momentum conjugate to q_i, and **H** is the **Hamiltonian**. They are also termed canonical equations of motion. The Hamiltonian determines the time evolution of the system.

First described in: W. R. Hamilton, *Second essay on a general method in dynamics,* Phil. Trans. R. Soc. **125**, 95–144 (1835).

Hamiltonian operator (or, shortly, Hamiltonian) – a differential **operator** typically used to represent energy relations governing behavior of quantum particles. It is denoted

$$\mathbf{H} = -\frac{\hbar^2}{2m}\nabla^2 + V(\mathbf{r})$$

and includes the kinetic energy term supposing that the particle has a mass m and the potential energy term $V(\mathbf{r})$. The operator takes the second derivative of a function (after multiplication by $-\hbar^2/2m$) and adds it to the result of multiplying this function by $V(\mathbf{r})$.

First described in: W. R. Hamilton, *Theory of systems of rays,* Trans. R. Irish Acad. **15**, 69–174 (1828); *Supplement to an essay on the theory of systems of rays,* Trans. R. Irish Acad. **16**, 1–61 (1830); *Second supplement to an essay on the theory of systems of rays,* Trans. R. Irish Acad. **16**, 93–125 (1831).

Hamilton–Jacobi equation –

$$\mathbf{H}\left(q_1, \ldots, q_n, \frac{\partial \phi}{\partial q_1}, \ldots, \frac{\partial \phi}{\partial q_n}, t\right) + \frac{\partial \phi}{\partial t} = 0,$$

where $q_1, \ldots, q_n$ are generalized coordinates, t is the time coordinate, **H** is the Hamiltonian, and ϕ is a function that generates a transformation by means of which the generalized coordinates and momenta may be expressed in terms of new generalized coordinates and momenta, which are constants of motion.

First described in: W. R. Hamilton, *On a General Method of Expressing the Paths of Light, and of the Planets, by the Coefficients of a Characteristic Function* (Dublin, 1833); C. G. Jacobi, *Opuscula mathematica* (Berlin, 1846–1857).

Hanle effect – magnetic field-induced depolarization of the **luminescence** in solids related to dephasing of electron spins as a result of their precessing along the magnetic field. Linear and nonlinear effects are distinguished.

The **linear Hanle effect** supposes a change in the degree of polarization of the resonant luminescence of an atomic or molecular sample in the presence of a magnetic field. The **nonlinear Hanle effect** is a change in the nonlinear absorption coefficient of an atomic or molecular sample as a function of the applied magnetic field. Since it is related to the removal of degeneracy of sublevels by the external field, it is also known as stimulated zero-field level crossing.

First described in: W. Hanle, *Über magnetische Beeinflussung der Polarisation der Resonanzfluoreszenz*, Z. Phys. **30**, 93–105 (1924).

More details in: G. Moruzzi, F. Strumia, *The Hanle Effect and Level-Crossing Spectroscopy* (Plenum Press, New York, 1991).

haploid – a cell or individual with a genetic complement containing one copy of each nuclear chromosome.

hard-sphere potential – the classical interatomic pair potential in the form:

$$V(r) = \begin{cases} 0 & \text{if } r > r_0 \\ \infty & \text{if } r \leq r_0 \end{cases}$$

where r_0 is the radius of the atom.

Hardy–Schulze rule states that the ion which is effective in causing precipitation in a sol is that whose charge is opposite to that on the colloidal particle, and its effect is greatly increased with increasing valence of the ion.

First described in: H. Schulze, *Schwefelarsen in wässriger Lösung*, Journal für Praktische Chemie **25**, 431–452 (1882); W. B. Hardy, *A preliminary investigation of the conditions which determine the stability of irreversible hydrosols*, Proc. R. Soc. Lond. **66**, 110–125 (1900) and J. Phys. Chem. **4**(4), 235–253 (1900).

harmonic function – a function which, both itself and its first derivative in a given domain, are continuous functions. It must also satisfy the **Laplace equation**. Special cases are spherical harmonic functions, which are homogeneous in variables x, y, z, for example **Legendre polynomials**.

harmonic oscillation – the simplest form of oscillation of a particle about a point arising when the force which tends to pull the particle back to this point is proportional to the displacement of the particle from the point. The displacement of the particle at any time t is $A\cos(\omega t + \phi)$, where A is the amplitude, ω is the frequency and ϕ is the phase of the motion.

Hartree approximation – the independent-particle approximation wherein the total wavefunction is approximated by a product of orthonormal molecular orbitals used to simplify finding a solution of the **Schrödinger equation** for many-electron systems. It is assumed that each electron moves independently within its own orbital and sees only the average field generated by all the other electrons. The Hartree wavefunction (for an N-electron system) is $\Psi = \psi_1(\mathbf{r}_1)\psi_2(\mathbf{r}_2)\ldots\psi_N(\mathbf{r}_N)$, where $\psi_N(\mathbf{r}_N)$ are orthonormal one-electron wave functions consisting of a spatial orbital and one of two spin functions representing spin up and spin down states.

First described in: D. R. Hartree, *Wave mechanics of an atom with a non Coulomb central field. Part I. Theory and methods,* Proc. Camb. Phil. Soc. **24**, 89–110 (1928); D. R. Hartree, *Wave mechanics of an atom with a non Coulomb central field. Part II. Some results and discussion,* Proc. Camb. Phil. Soc. **24**, 111–132 (1928).

Hartree–Fock approximation considers interaction of electrons in a many-electron system in terms of a potential. Interaction between particles is included by allowing each particle to be governed by an effective potential due to all other particles. The effective potential for one electron then has two additional terms, usually called the **Hartree potential** and the **Fock exchange potential**. The first, which is the electrostatic potential due to the charge distribution of the other electrons, is easily to understand. The second is a nonlocal potential due to the exchange interaction of the electron with the others.

Mathematically, the approximation consists in finding the best set of one-electron orbitals in the **Slater determinant** representing the ground state. According to the **variational principle**, the best set is the one which yields the lowest total energy for the interacting system. The resultant orbitals are given by a set of modified one-particle **Schrödinger equations**:

$$\left[-\frac{\hbar^2}{2m}\nabla^2 + V(\mathbf{r}) + \int \mathrm{d}r' \frac{e^2}{|\mathbf{r}-\mathbf{r}'|} n(\mathbf{r}')\right]\psi_i(\mathbf{r}) \\ - \int \mathrm{d}r' \frac{e^2}{|\mathbf{r}-\mathbf{r}'|} n(\mathbf{r},\mathbf{r}')\psi_i(\mathbf{r}') = E\psi_i(\mathbf{r})$$

referred to as the **Hartree–Fock equation**. It supposes that each electron moves under the combined influence of the external potential $V(\mathbf{r})$, the Hartree potential and the Fock exchange potential. The Hartree potential is expressed here as the electrostatic potential due to the electron density distribution $n(\mathbf{r})$ via the Coulomb interaction $e^2/|\mathbf{r}-\mathbf{r}'|$. The nonlocal Fock exchange potential is due to the one particle density matrix $n(\mathbf{r},\mathbf{r}')$ as a consequence of the **Pauli principle**. Both the density and density matrix are given by the N lowest energy orbitals of the above equation. The interaction of an orbital with itself in the Hartree and Fock terms cancels. The many-electron wave function Ψ is approximated as a product of single-particle functions ψ_i, *i.e.* $\Psi(\mathbf{r}_1, \mathbf{r}_2, \ldots) = \psi_1(\mathbf{r}_1) \cdot \psi_2(\mathbf{r}_2) \cdot \ldots \cdot \psi_N(\mathbf{r}_N)$. In addition to the ground state, the equation yields orbitals which can be used to construct excited states. The excitation energy over the ground state is simply the sum and difference of the single-particle energies of the orbitals added to or taken from the ground state. Note that the Hartree-Fock approximation misses so called correlation effects in many-electron systems.

First described in: D. R. Hartree, *Wave mechanics of an atom with a non Coulomb central field. Part I. Theory and methods*, Proc. Camb. Phil. Soc. **24**, 89–110 (1928); D. R. Hartree, *Wave mechanics of an atom with a non Coulomb central field. Part II. Some results and discussion*, Proc. Camb. Phil. Soc. **24**, 111–132 (1928); V. Fock, *Approximate method of solution of the problem of many bodies in quantum mechanics*, Z. Phys. **61**(1/2), 126–148 (1930).

Hartree–Fock equation → **Hartree–Fock approximation**.

Hartree method – an iterative variational method of finding an approximate wave function for a system of many electrons. Within the method one attempts to find a product of single-particle wave functions each one of which is a solution of the **Schrödinger equation** with the field deduced from the charge density distribution due to all the other electrons.

First described in: D. R. Hartree, *Wave mechanics of an atom with a non Coulomb central field. Part I. Theory and methods*, Proc. Camb. Phil. Soc. **24**, 89–110 (1928).

Hartree potential → **Hartree–Fock approximation**.

Hartree wave function → **Hartree approximation**.

Heaviside step function – zero for a negative argument and one for a positive argument.

First described by Oliver Heaviside in 1880.

hecto- – a decimal prefix representing 10^2, abbreviated h.

Heggie potential – a semiclassical interatomic many-body potential based on the proximity cell (the **Wigner–Seitz primitive cell**). It introduces three internal degrees of freedom per atom, representing the magnitude and direction of the p-orbital that is not involved in sp-hybridization. One of the variants of the potential has the form:

$$V(r_{ij}) = \left(\frac{1}{2}t^{-4} + \frac{1}{4}|\mathbf{p}_{ij}^{'}|^{-4} + \frac{1}{4}|\mathbf{p}_{ij}^{''}|\right)^{-1/4}$$

$$t = \left[1 - f(\triangle_{ij}, \triangle_l, \triangle_u)\right]\left[\mathbf{p}_i\mathbf{p}_j|\mathbf{p}_{ij}^{'}||\mathbf{p}_{ij}^{''}|(2 - |\mathbf{p}_{ij}^{'}|)(2 - |\mathbf{p}_{ij}^{''}|)\right]^4,$$

where $\mathbf{p}_i$ is the direction of the unhybridized p orbital on atom i being between 0 (sp^3 hybridization, for example diamond) and 1 (sp^2 hybridization, for example graphite), vectors $\mathbf{p}_{ij}^{'}$ and $\mathbf{p}_{ij}^{''}$ represent the projection of $\mathbf{p}_i$ onto the bond face and $\mathbf{p}_j$ onto the latter direction, respectively, as follows: $\mathbf{p}_{ij}^{'} = \mathbf{p}_i - (\mathbf{p}_i \cdot \hat{\mathbf{r}}_{ij})\hat{\mathbf{r}}_{ij}$, $\mathbf{p}_{ij}^{''} = (\mathbf{p}_i \cdot \hat{\mathbf{p}}_{ij}^{'})\hat{\mathbf{p}}_{ij}^{'}$; $\mathbf{r}_{ij} = \mathbf{r}_j - \mathbf{r}_i$ is the distance between atoms i and j.

First described in: M. I. Heggie, *Semiclassical interatomic potential for carbon and its application to the self-interstitial in graphite,* J. Phys.: Condens. Matter **3**(18), 3065–3078 (1991).

Heisenberg equation of motion gives the rate of change of an **operator** corresponding to a physical quantity within the **Heisenberg representation**.

First described in: W. Heisenberg, *Über quantentheoretische Umdeutung kinematischer und mechanischer Beziehungen,* Z. Phys. **33**(1), 879–893 (1925).

Heisenberg exchange interaction → **exchange interaction**.

First described in: W. Heisenberg, *Mehrkörperproblem und Resonanz in der Quantenmechanik,* Z. Phys. **38**(67), 411–426 (1926); P. A. M. Dirac, *On the theory of quantum mechanics,* Proc. R. Soc. Lond., Series A **112**, 661–677 (1926).

Heisenberg force – a force between two nucleons derivable from a potential with an **operator**, which exchanges both the positions and the **spins** of the particles.

First described in: W. Heisenberg, *Über den Bau der Atomkerne. I,* Z. Phys. **77**(1–2), 1–11 (1932); W. Heisenberg, *Über den Bau der Atomkerne. II,* Z. Phys. **78**(3–4), 156–164 (1932); W. Heisenberg, *Über den Bau der Atomkerne. III,* Z. Phys. **80**(9–10), 587–596 (1933).

Heisenberg representation – a mode of a description of a system in which stationary vectors represent dynamic states and **operators**, which evolve in the course of time, represent physical quantities.

First described in: W. Heisenberg, *Über quantentheoretische Umdeutung kinematischer und mechanischer Beziehungen,* Z. Phys. **33**(1), 879–893 (1925); M. Born, P. Jordan, *Zur Quantenmechanik,* Z. Phys. **34**(1), 858–888 (1925); M. Born, W. Heisenberg, P. Jordan, *Zur Quantenmechanik II,* Z. Phys. **35**(8–9), 557–615 (1925).

Heisenberg's uncertainty principle states that it is impossible to specify simultaneously, with arbitrary precision, both the momentum (p) and the position (r) of a quantum particle. The quantitative version of the position-momentum uncertainty relation is $\triangle p \triangle r \geq \hbar/2$ or equivalently for time (t) and energy (E) → $\triangle t \triangle E \geq \hbar/2$.

First described in: W. Heisenberg, *Über den anschaulichen Inhalt der quantentheoretischen Kinematik und Mechanik,* Z. Phys. **43**(3/4), 172–198 (1927).

Recognition: in 1932 W. Heisenberg received the Nobel Prize in Physics for the creation of quantum mechanics, the application of which has, among other things, led to the discovery of the allotropic forms of hydrogen.

See also www.nobel.se/physics/laureates/1932/index.html.

Heitler–London method – a way to describe molecules and molecular states supposing that each molecule is composed of atoms and their electronic structure is represented by atomic orbitals of the composing atoms, which later becomes the superposition of atomic orbitals. The method is an alternative to the molecular orbital method → **Hund–Mulliken theory**. Both are an approximation to the complete solution. Consider two atoms brought together starting from a large distance. One can consider and distinguish three regions. The first region is that located at long distances, where the atoms maintain their character but are polarized by each other. In the second, intermediate region, there is a ''real'' molecule and the atoms lose part of their identity. In the third region, at short distances, the atoms begin to behave like a single united atom. The molecular description in the Heitler–London method tries to describe the molecular states starting from the third region, while the Hund–Mulliken theory starts from the first region.

First described in: W. Heitler, F. London, *Wechselwirkung neutraler Atome and homopolare Bindung nach der Quantenmechanik*, Z. Phys. **44**, 455–472 (1927).

More details in: J. C. Slater, *Molecular orbital and Heitler–London Methods,* J. Chem. Phys. **43**(10), S11–S17 (1965); C. A. Coulson, *Valence* (Oxford University Press, Oxford, 1961).

helium I – the phase of liquid ^{4}He which is stable at temperatures above the **lambda point** (2.178 K) and has the properties of a normal liquid, except low density.

helium II – the phase of liquid ^{4}He which is stable at temperature between absolute zero and the **lambda point** (2.178 K) and demonstrates such exceptional properties as vanishing viscosity called **superfluidity** and extremely high heat conductivity. It also shows the **fountain effect**.

First described by P. L. Kapitza in 1937 – experiment; L. Landau in 1941 – theory.

Recognition: in 1962 L. D. Landau received the Nobel Prize in Physics for his pioneering theories for condensed matter, especially liquid helium.

See also www.nobel.se/physics/laureates/1932/index.html.

helium neon laser – a type of **ion laser** with a mixture of ionized helium and neon gases as the active medium. It generates light peaking at 633 nm (red light).

Hellman–Feynman theorem states that within the **Born–Oppenheimer approximation** the forces on nuclei in molecules or solids are those which would arise electrostatically if electron probability density were treated as a static distribution of negative electric charge.

First described in: H. Hellmann, *Zur Rolle der kinetischen Elektronenenergie für die zwischenatomaren Kräfte*, Z. Phys. **85**, 180 (1933); R. P. Feynman, *Forces in molecules*, Phys. Rev. **56**(4), 340–343 (1939).

Helmholtz double layer represents an electrical double layer of positive and negative charges one molecule thick which occurs at a surface where two different materials are in contact.

Helmholtz equation – an elliptical partial differential equation of the form $\nabla^2\phi + k^2\phi = 0$, where ϕ is a function, ∇^2 is the Laplace operator, k is a number. When $k = 0$, the equation reduces to the Laplace equation. With imaginary k, the equation becomes the space part of the diffusion equation.

First described in: H. Helmholtz, *Die Thermodynamik chemischer Vorgänge*, Sitzungsber. Berlin Akad. Wissen. **1**, 21, 825 (1882); H. Helmholtz, *Versuch an Chlorzinkelementen*, Sitzungsber. Berlin Akad. Wissen. **2**, 958, 1895 (1883); H. Helmholtz, *Folgerungen die galvanische Polarisation betreffend*, Sitzungsber. Berlin Akad. Wissen. **3**, 92 (1883).

Helmholtz free energy → **free energy**.

First described in: H. Helmholtz, *Über die Erhaltung der Kraft*, (Berlin 1847).

Hermann–Mauguin symbols (notations) – symbols representing the 32 symmetry classes of crystals. They consist of series numbers giving the multiplicity of symmetry axes in descending order with other symbols indicating inversion axes and mirror planes. They are widely used in crystallography. This type of symbol, first proposed by C. Hermann, was greatly simplified and owes its present form to the efforts of C. Mauguin.

First described in: C. Hermann, *Zur systematischen Strukturtheorie I. Eine neue Raumgruppensymbolik*, Z. Kristallogr. **68**, 257–287 (1928); C. Hermann, *Zur systematischen Strukturtheorie. II.*, Z. Kristallogr. **68**, 377–401 (1928); C. Hermann, *Zur systematischen Strukturtheorie. III. Ketten- und Netzgruppen*, Z. Kristallogr. **69**, 259–270 (1929); C. Hermann, *Zur systematischen Strukturtheorie. IV. Untergruppen*, Z. Kristallogr. **69** 533–555 (1929); C. Mauguin, *Sur le symbolisme des groupes de répétition ou de symmétrie des assemblages cristallins*, Z. Kristallogr. **76**, 542–558 (1931).

More details in: F. A. Cotton, *Chemical Applications of Group Theory*, 3rd edn. (Wiley, New York, 1990).

Hermite equation – a differential equation of the form $y'' - 2xy' + 2uy = 0$, where u is a constant, but not necessary an integer. Introducing the operator $\mathbf{D} = \mathrm{d}/\mathrm{d}x$ one can rewrite this as $(\mathbf{D}^2 - 2x\mathbf{D} + 2u)y = 0$.

Hermite polynomial has the form

$$H_n(x) = (2x)^n - n\frac{n-1}{1!}(2x)^{n-2} + \frac{(n-1)(n-2)(n-3)}{2!}(2x)^{n-4} \ldots,$$

where n is its degree. The first Hermite polynomials are: $H_0(x) = 1, H_1(x) = 2x, H_2(x) = 4x^2 - 2, H_3(x) = 8x^3 - 12x, H_4(x) = 16x^4 - 48x^2 + 12$. They are solutions of the **Hermite equation** for $n = u$.

First described in: C. Hermite, *Sur un nouveau développement en série des fonctions,* Compt. Rend. **58** 93–100 (1864).

Hermitian conjugate operator → **adjoint operator**.

Hermitian operator – a linear **operator A** acting on vectors in a **Hilbert space** such that if x and y are in the range of **A** then the inner products $(\mathbf{A}x, y)$ and $(x, \mathbf{A}y)$ are equal, or in the case of a function $\psi(r)$ one has $\int \psi^*(r)\mathbf{A}\psi(r) = \int (\mathbf{A}\psi(r))^*\psi(r)$.

Herring's γ plot → **Wulff's theorem**.

First described in: C. Herring, *Some theorems on the free energies of crystal surfaces,* Phys. Rev. **82**(1), 87–93 (1951).

Hertzian vector – a single vector describing an electromagnetic wave from which both the electrical and magnetic intensities can be obtained by derivation. The vector is represented by the equation $\mathbf{Z} = \int A\mathrm{d}t$, where A is the vector potential. Thus, the intensity of the electric field is

$$E = \nabla(\nabla\mathbf{Z}) - \frac{1}{c^2}\frac{\partial^2\mathbf{Z}}{\partial t^2}$$

and the intensity of the magnetic field is

$$H = \frac{1}{c}\nabla \times \frac{\partial\mathbf{Z}}{\partial t}.$$

Hess's law states that in a chemical reaction the evolved or absorbed heat is the same whether the reaction takes place one step or several steps.

First described in: G. H. Hess, *Recherches thermochimiques,* Bull. Sci. Acad. Imp. Sci. St Petersburg **8**, 257–272 (1840).

heterojunction – an interface between two dissimilar materials.

heterojunction solar cell makes use of **heterojunction**s formed from different $\mathrm{A^{III}B^{V}}$ compounds or their alloys to produce the rectifying junction. In these cells, the total current is a sum of the currents generated in the different materials but voltage is controlled by the lowest of the two band gaps. Also double- and triple-junction devices → **multijunction solar cell**s have been developed that allow the monolithic stacking of multiple cells on top of one another, so each efficiently converts a relatively narrow range of photon energies suited to its band gap.

First described in: Zh. I. Alferov, V. M. Andrew, M. B. Kagan, I. I. Protasov, V. G. Trosfim, Sov. Phys. Semicond. **4**, 2047 (1971).

Recognition: in 2000 Zh. I. Alferov received (shared with H. Kroemer and J. S. Kilby) the Nobel Prize in Physics for developing semiconductor heterostructures used in high-speed- and optoelectronics.

See also www.nobel.se/physics/laureates/2000/index.html.

heterostructure – structure comprising more than one kind of material. Heterostructures are formed from multiple **heterojunctions**.

heterostructure field effect transistor (HFET) → **high electron mobility transistor**.

Heusler alloy – an alloy made of metals that are only partially magnetically aligned in their pure state but have all their spins aligned at room temperature in the alloy form.

First described in: F. Heusler, Verh. Dtsch. Ges. **5**, 219 (1903).

hexagonal close-packed (hcp) structure is represented by a **unit cell** consisting of three layers of atoms as schematically shown in Figure H.5.

The top and bottom layers contain six atoms at the corners of a hexagon and one atom at the center of each hexagon. The middle layer contains three atoms nestled between the atoms of the top and bottom layers. This structure is adopted by many metals.



Figure H.5 HCP structure.

hexagonal lattice – a particular type of **Bravais lattice** whose unit cell is a right prism with a hexagonal base and whose lattice points are located at the vertices of the unit cell and at the center of the hexagon.

Heyd–Scuseria–Ernzerhof (HSE) functional – the hybrid functional employing screened short-range **Hartree–Fock** exchange instead of the full exact exchange. The exchange-correlation energy is written as

$$E_{xc}^{HSE} = aE_x^{HF,SR} + (1-a)E_x^{PBE,SR} + E_x^{PBE,LR} + E_c^{PBE},$$

where $E_x^{HF,SR}$ is the short-range Hartree–Fock exchange, $E_x^{PBE,SR}$ and $E_x^{PBE,LR}$ are the short-range and long-range components of the **Perdew–Burke–Ernzerhof** (PBE) exchange functional, respectively, and $a = 1/4$ is the Hartree–Fock exchange mixing parameter usually determined via perturbation theory. The form of the functional can be viewed as an adiabatic connection for the short-range portions of exchange, whereas long range exchange and correlation are treated with the PBE functional.

First described in: J. Heyd, G. E. Scuseria, M. Ernzerhof, *Hybrid functionals based on a screened Coulomb potential*, J. Chem. Phys. **118**(15), 8207–8215 (2003).

hidden variable – a hypothetical variable, in addition to the quantum state, that specifies a definite value for the observable of the quantum system.

high electron mobility transistor (HEMT) – a transistor exploiting the high in-plane mobility of electrons near a modulation-doped heterojunction. Synonyms are **heterostructure field effect transistor (HFET), modulation doped field effect transistor (MODFET), two-dimensional electron gas field effect transistor (TEGFET)**.

high-T_c superconductors → **superconductivity**.

Hilbert space – a many-dimensional normed linear vector space with an inner product that makes it complete. Points of real Hilbert space are sequences of numbers $x_1, x_2, \ldots$ such that the infinite sum $\sum x_i^2$ is finite. Elements of the basis are the interiors of balls in which the distance between $p = (x_1, x_2, \ldots)$ and $q = (y_1, y_2, \ldots)$ is the square root of $\sum(y_i - x_i^2)$. Hilbert space is an abstract mathematical tool for calculating the evolution in time of the energy levels of systems. This evolution occurs in ordinary space–time scale. It is widely used in quantum mechanics to define an observable value to be an operator on a Hilbert space.

More details in: D. Hilbert, *Grundlagen der Geometrie* (Teubner, Leipzig-Berlin, 1930).

Hilbert transform of a function $f(x)$ is $g(\xi) = 1/\pi \int_{-\infty}^{\infty} f(x)/(\xi - x)\mathrm{d}x$, where the integral is understood as a **Cauchy principle value**. If the transform of a function is known, then the inverse formula gives $f(x) = -1/\pi \int_{-\infty}^{\infty} g(\xi)/(\xi - x)\mathrm{d}\xi$.

Hohenberg–Kohn theorems relate to any system consisting of electrons moving under the influence of an external potential. Theorem 1: The external potential, and hence the total energy, is a unique functional of the electron density. Theorem 2: The ground-state energy can be obtained variationally: the density that minimizes the total energy is the exact ground-state density.

It is necessary to note that an electronic system with a given **Hamiltonian** has a ground-state energy as well as a ground-state **wave function**, which is completely determined by the minimization of the total energy as a functional of the wave function. Moreover, as the external potential together with the number of electrons completely determines the Hamiltonian, these two quantities determine all properties of the ground state.

The theorems provide the formal justification of the **Thomas-Fermi theory**, and the foundation of the **density functional theory**. They effectively reduce the $3N$-dimensional minimization problem of finding the wave function to a three-dimensional minimization problem of determining the density.

First described in: P. Hohenberg, W. Kohn, *Inhomogeneous electron gas,* Phys. Rev. **136**(3B), B864–B871 (1964).

Recognition: in 1998 W. Kohn received the Nobel Prize in Chemistry for his development of the density functional theory.

See also www.nobel.se/chemistry/laureates/1998/index.html.

Hofstadter butterfly – a diagram presenting energy levels in a two-dimensional crystal as a function of the magnetic field applied. In a sense it looks like a butterfly.

First described in: D. R. Hofstadter, *Energy levels and wave functions of Bloch electrons in rational and irrational magnetic fields,* Phys. Rev. B **14**(6), 2239–2249 (1976).

hole-burning → **spectral hole-burning**.

hologram – an interference pattern that is recorded on a high-resolution plate when two interfering beams formed by a coherent beam from a laser and light are scattered by an object. If after processing, the plate is viewed correctly by monochromatic light, a three-dimensional image of the object is seen. The name, coined by D. Gabor in 1947, derived from the greek word ‘‘holos’’ (the whole) because the interference pattern contains all the information.

First described in: D. Gabor, *A new microscopic principle,* Nature **161**, 777–778 (1948); D. Gabor, *Microscopy by reconstructed wavefronts,* Proc. R. Soc. (Lond.) A **197**, 454–487 (1949).

Recognition: in 1971 D. Gabor received the Nobel Prize in Physics for his invention and development of the holographic method.

See also www.nobel.se/physics/laureates/1971/index.html.

HOMO – an acronym for a **h**ighest **o**ccupied **m**olecular **o**rbital.

homopolar bond is formed between atoms, which share a pair of electrons with opposite spins.

Hooke's law originally stated that the power of any springy body is in proportion to the extension. In the modern corrected form it states that the extension Δl of an elastic spring and its tension F, but not power, are linearly related to each other: $F = k\Delta l$, where k is the spring constant. The law holds up to a limit, called the elastic limit, after which springs suffer plastic deformation up to the limit of plasticity, after which they break down. Later Cauchy generalized Hooke's law to three-dimensional elastic bodies and stated that the 6 components of stress are linearly related to the 6 components of strain. In the matrix form it is $\boldsymbol{\epsilon} = \mathbf{S} \times \mathbf{s}$ and $\mathbf{s} = \mathbf{C} \times \boldsymbol{\epsilon}$, where $\boldsymbol{\epsilon}$ is the 6 components stress vector, $\mathbf{s}$ is the 6 components strain vector, $\mathbf{S}$ is the compliance matrix (36 components), and $\mathbf{C}$ is the **stiffness matrix** (36 components). It is evident that $\mathbf{S} = \mathbf{C}^{-1}$. In general, the above stress-strain relationships are known as **constitutive relations**.

First described in: R. Hooke, *A description of helioscopes and some other instruments*, Phil. Trans. **10**, 440–442 (1675).

hopping conductivity – the charge transport mechanism where by conductivity is determined by electrons hopping via **localized states** without activation to the conduction band. If it is energetically favorable for localized electrons to hop beyond the nearest-neighbor impurity centers, so that the average hopping length exceeds the average distance between them, variable range hopping conductivity sets in the system. The average hopping length increases with the temperature decrease for disordered systems in which electronic states are localized close to the **Fermi level**. The temperature dependence of the hopping conductivity is described by the **Mott law**: $\ln \sigma \sim T^{-1/4}$, which in the general form looks like $\ln \sigma \sim T^{-1/n}$, where the parameter n depends on the dimensionality of the system $d(n = d + 1)$. The Mott law is derived assuming that the density of states near the Fermi level of the system is constant.

Accounting for the existence of a parabolic gap of width ΔE_C in the density of states near the Fermi level of the system, due to electron–electron Coulomb interaction, comes to the **Shklovskii-Efros law** of temperature dependence of hopping conductivity: $\ln \sigma \sim T^{-1/2}$. It is observed at low temperatures when $\Delta E_C > k_B T$. The power of temperature does not depend on the dimensionality of the system.

A crossover between the Mott and Shklovskii-Efros hopping regimes can be observed as a function of temperature.

First described in: N. F. Mott, *Conduction in non crystalline materials. III. Localized states in a pseudogap and near extremities of conduction and valence bands*, Phil. Mag. **19**(160), 835–852 (1969).

Recognition: in 1977 P. W. Anderson, N. F. Mott and J. H. van Vleck received the Nobel Prize in Physics for their fundamental theoretical investigations of the electronic structure of magnetic and disordered systems.

See also www.nobel.se/physics/laureates/1977/index.html.

hot carrier – a charge carrier, which may be an electron or a hole, that has relatively high energy with respect to the carriers normally found in the material.

hot-carrier solar cell – a **solar cell** designed to collect irradiation-induced electron–hole pairs in a semicondutor before they thermalize to respective band edges. This requires both an absorber with carrier cooling properties and a collection of carriers over a limited range of energies, such that cold carriers in the external contacts do not cool the hot carriers to be extracted.

More details in: R. T. Ross, A. J. Nozik, *Efficiency of hot-carrier solar energy converters,* J. Appl. Phys. **53**(5), 3813–3818 (1982).

HSE functional = **Heyd–Scuseria–Ernzerhof functional**.

Hubbard Hamiltonian – a common model phenomenological **Hamiltonian** used to describe properties of strong electron correlation in solids. In this model, which is in fact the **Hubbard model**, strongly correlated electrons move in a lattice. The related Hamiltonian has two terms: the first term describes a band of tight-binding electrons, the second term involves a repulsive electron–electron interaction. Thus this Hamiltonian studies the effects induced by the competition between localization and correlations.

The interaction between electrons only occurs if they are located on the same site. Only one orbital per site is considered. Thus the Hamiltonian is given by $\mathbf{H} = \sum_{i,j,\sigma} t_{ij} a^{+}_{i\sigma} a_{j\sigma} + U \sum_{j} n_{i\uparrow} n_{i\downarrow}$, where $n_{i\sigma} = a^{+}_{i\sigma} a_{i\sigma}$ is the occupation number operator, $a^{+}_{i\sigma}$ creates and $a_{i\sigma}$ annihilates an electron with spin σ on the i-th site of the lattice, U represents the effective on-site interactions, and t_{ij} is the tight binding hopping integral between the i-th and j-th sites. Strong correlations occur when the interaction U is large in comparison with the band width W of the system, that is for large U/t, called the interaction strength. The model successfully describes the itinerant magnetism and the metal–insulator transition → **Mott–Hubbard transition**. Despite the simplicity of the Hamiltonian, no exact solution has been found, except in the one-dimensional case. Nevertheless, it has been demonstrated that the Hubbard model has a non-trivial limit in higher dimensions.

First described in: J. Hubbard, *Electron correlations in narrow energy bands. I,* Proc. R. Soc. A **276**, 238–257 (1963); J. Hubbard, *Electron correlations in narrow energy bands. II,* Proc. R. Soc. A **277**, 237–259; J. Hubbard, *Electron correlations in narrow energy bands. III,* Proc. R. Soc. A **281**, 401–419 (1964); J. Hubbard, *Electron correlations in narrow energy bands. IV,* Proc. R. Soc. A **285**, 542–560 (1965).

Hubbard model → **Hubbard Hamiltonian**.

Hückel approximation is used to calculate molecular orbitals. The following assumptions are made:

1. If atoms i and j are not directly bonded, then H_{ij} (bond energy between atoms i and j) equals zero.
2. If all atoms and bond lengths are identical in a molecule, then all H_{ij} values for directly bonded atoms are identical.

3. If all atoms are identical, all H_{ii} integrals are equal and will be symbolized by α.
4. The atomic orbitals are normalized, therefore $\int \phi_i \phi_j d\tau = 1$.
5. The atomic orbitals are mutually orthogonal, therefore $\int \phi_i \phi_j d\tau = 0$.

The form of the Hückel secular equations is:

$$\begin{array}{ccc} c_{11}(\alpha - E)+ & \ldots + & c_{1n}\beta_{1n} = 0 \\ \vdots & & \vdots \\ c_{n1}\beta_{n1}+ & \ldots + & (\alpha - E) = 0 \end{array}$$

and the Hückel secular determinant is:

$$\begin{vmatrix} (\alpha - E) & \ldots & \beta_{1n} \\ \vdots & & \vdots \\ \beta_{n1} & \ldots & (\alpha - E) \end{vmatrix} = 0$$

It should be remembered that the first assumption states that non-directly bonded atoms have $H_{ij} = 0, (\beta = 0)$. The number of atomic orbitals equals the number of secular equations and the number of molecular orbitals.

First described in: E. Hückel, *Quantentheoretische Beiträge zum Benzolproblem*, Z. Phys. **70**, 204–286 (1931).

Hund-Mulliken theory supposes that in the case of an atom an atomic orbital is best taken to be an eigenfunction of the one-electron **Schrödinger equation** based on the nuclear attraction for the electron and on the average repulsion of all other electrons. The molecular orbital is defined in the same way. Now its one-electron Schrödinger equation is based on the attraction of two or more nuclei plus the averaged repulsion of all other electrons. It is also known as **molecular orbital theory**.

As in the theory of atoms, it is possible to use the **aufbau principle** (the building-up principle) in order to feed electrons into molecular orbitals. For example, in the case of a diatomic molecule the binding electrons occupy a quantum state specific to the extended chemical bond, thus Hund introduced the Greek symbols Σ, Π and Δ for designing the molecular electronic states, Mulliken used instead the symbols S, P and D. Differently from the valence-bond method or **Heitler–London method**, the molecular orbital method considers a molecule as a self-sufficient unit and not as a mere composite of atoms.

First described in: F. Hund, *Zur Deutung der Molekelspektren I*, Z. Phys. **36**, 657 (1926); F. Hund, *Zur Deutung der Molekelspektren II*, Z. Phys. **37**, 742 (1927); F. Hund, *Zur Deutung der Molekelspektren III*, Z. Phys. **42**, 93 (1927); F. Hund, *Zur Deutung der Molekelspektren IV*, Z. Phys. **43**, 805 (1927); R. S. Mulliken, *The assignment of quantum numbers for electrons in molecules. I*, Phys. Rev. **32**(2) 186–222 (1928); R. S. Mulliken, *The assignment of quantum numbers for electrons in molecules.*

II. Correlation of molecular and atomic electron states, Phys. Rev. **32**(5) 761–772 (1928); R. S. Mulliken, *The assignment of quantum numbers for electrons in molecules. III. Diatomic hydrides*, Phys. Rev. **33**(5) 730–747 (1929).

More details in: R. S. Mulliken, *Molecular scientists and molecular science: some reminiscences*, J. Chem. Phys. **43**(10), S2–S11 (1965); J. C. Slater, *Molecular orbital and Heitler–London methods*, J. Chem. Phys. 43(10), S11–S17 (1965).

Recognition: in 1966 R. S. Mulliken received the Nobel Prize in Chemistry for his fundamental work concerning chemical bonds and the electronic structure of molecules by the molecular orbital method.

See also www.nobel.se/chemistry/laureates/1966/index.html.

Hund rules give the order in the energy of atomic states formed by equivalent electrons: (i) among the terms given by equivalent electrons, the ones with greatest multiplicity have the least energy, and of these the one with greatest orbital angular momentum is lowest; (ii) the state with a multiplet with lowest energies is given by that state in which the total angular momentum is the least possible if the shell is less than half filled, and the greatest possible if the shell is more than half filled.

First described in: F. Hund, *Deutung von Spektra*, Z. Phys. **33**(5/6), 345–371 (1925).

Huntington potential – the interatomic pair potential in the form of **Born–Mayer potential**:

$$V(r) = A \exp\left(a\frac{r_0 - r}{r_0}\right),$$

where r is the interatomic distance, r_0 is the equilibrium distance between atoms in the perfect crystal, and A and a are fitted parameters defined from experimental data.

First described in: H. B. Huntington, *Mobility of interstitial atoms in a face-centered metal*, Phys. Rev. **91**(5), 1092–1098 (1953).

Huygens principle states that every point on a propagating wavefront serves as the source of spherical secondary wavelets, such that the wavefront at some later time is the envelope of these wavelets. If the propagating wave has a certain frequency and is transmitted through the medium at a certain speed, then the secondary wavelets will have the same frequency and speed.

First described in: C. Huygens, *Traité de la lumière* (Leyden, 1690).

hybridization – a process by which a number of constituent **orbitals** of an atom are linearly combined (hybridized) to form an equal number of equivalent and directed orbitals (hybrids).

hydride – a chemical compound of an element with hydrogen. Hydrides suitable for technological applications in fabrication of semiconductor electron devices are listed in Table H.1.

Table H.1 Hydrides for chemical vapor deposition of semiconductors.

Element	Compound		Melting point (°C)	Boiling point (°C)	Decomposition temperature (°C)
	Formula	Name			
Si	SiH_4	Silane	−185	−111.9	450
	Si_2H_6	Disilane	−132.5	−14.5	
	Si_3H_8	Trisilane	−117.4	52.9	
	Si_4H_{10}	Tetrasilane	−108	84.3	
Ge	GeH_4	Germane	−165	−88.5	350
	Ge_2H_6	Digermane	−109	29	215
	Ge_3H_8	Trigermane	−105.6	110.5	195
P	PH_3	Phosphine	−133	−87.8	
As	AsH_3	Arsine	−116	−62.5	
S	H_2S	Hydrogen sulfide	−85.5	−59.6	
Se	H_2Se	Hydrogen selenide	−65.7	−41.3	

hydrocarbons – compounds that are composed entirely of carbon and hydrogen atoms bonded to each other by covalent bonds. Saturated and unsaturated hydrocarbons exist.

Saturated hydrocarbons, called **alkanes**, contain single bonds. The alkanes, also known as parafins, have straight or branched-chain hydrocarbon compounds with only single covalent bonds between the carbon atoms. The general molecular formula for alkanes is C_nH_{2n+2}, where n is the number of carbon atoms in the molecule. Each carbon atom is connected to four other atoms by four single covalent bonds. These bonds are separated by angles of 109.5° (the angle between lines drawn from the center of a regular tetrahedron to its corners). Alkane molecules contain only carbon–carbon and carbon–hydrogen bonds, which are symmetrically directed toward the corners of a tetrahedron. Therefore, alkane molecules are essentially nonpolar.

Alkanes that have lost one hydrogen atom are called **alkyl groups**. These groups have the general formula $–C_nH_{2n+1}$. The missing hydrogen atom may be detached from any carbon in the alkane. The name of the group is formed from the name of the corresponding alkane by replacing *-ane* with the *-yl* ending, for example methane (CH_4) → methyl ($–CH_3$).

Unsaturated hydrocarbons consist of three families of compounds that contain fewer hydrogen atoms than the alkane with the corresponding number of carbon atoms and contain multiple bonds between carbon atoms. These include: **alkenes** with carbon–carbon double bonds; **alkynes** with carbon–carbon triple bonds; and **aromatic compounds** with benzene rings, also called **aromatic rings**, that are arranged in a six-membered ring with one hydrogen atom bonded to each carbon atom and three carbon–carbon double bonds, as illustrated in Figure H.6.



Figure H.6 Aromatic ring.

hydrogen bond – an association linkage between hydrogen atoms and the lone pairs of either nitrogen, oxygen or fluorine atoms, which are the most electronegative atoms in the periodic table, on a different molecule. This binding is mainly electrostatic, as the small radius of the positively charged hydrogen atom makes possible a very close approach to the electronegative atom. Hydrogen bonding is the strongest type of intermolecular force because the molecules that they exist between are very polar.

Hydrogen bonds can be formed within different parts of a single molecule (intramolecularly, as in proteins and nucleic acids) or between molecules (intermolecularly, as in water).

Figure H.7 shows some examples of hydrogen bonds.

More details in: Y. Maréchal, *The Hydrogen Bond and the Water Molecule: The Physics and Chemistry of Water, Aqueous and Bio-Media*, (Elsevier Science, Amsterdam, 2006).



Figure H.7 Hydrogen bonding (indicated by dashed lines) in different compounds.

hydrolysis – chemical reactions in which water as a reactant produces a bond rupture in compounds.

hydronium ion → **protonated water cluster**.

hydrophilic – literally, from the Greek, water loving. A hydrophilic compound is one that “loves” water and easily dissolves in it. Having lots of potential for **hydrogen bond**ing or having a charge will make a compound hydrophilic. Most inorganic salts and some organic molecules including ethanol and diethyl ether are hydrophilic. Opposite of **hydrophobic**.

hydrophobic – literally, from the Greek, water fearing. A compound is hydrophobic if it ''hates'' water and does not dissolve in it. Little **hydrogen bond**ing capacity and no charge makes a molecule hydrophobic. Most organic molecules are hydrophobic. Opposite of **hydrophilic**.

hydroxide – an inorganic chemical compound having one or more hydroxyl (–OH) groups.

hyperelastic scattering – a scattering process in which an excited heavy particle, like an atom, collides with a light particle, like a free electron, and the latter increases its kinetic energy by nearly the whole of the excitation energy leaving the heavy particle in its normal (unexcited) state.

I

From ideality factor to isotropy (of matter)

ideality factor – the parameter n in the semiconductor diode current–voltage relationship $j = j_0[exp(eV/nk_BT) - 1]$, where j_0 is the saturation current density and V is the applied voltage. It is equal to 1 for an ideal diode when carrier diffusion dominates the current flow, while it can approach 2 for real structures when recombination current dominates.

I^2M – an acronym for **image interference microscopy**.

I^3M – an acronym for a **incoherent interference illumination microscopy**.

I^5M – an acronym for a **image interference + incoherent interference illumination microscopy**.

image force – a force on a charge due to the charge or polarization that it induces on surrounding solids.

image interference microscopy (I^2M) → **fluorescence nanoscopy**.
First described in: M. G. L. Gustafsson, *Extended resolution fluorescence microscopy*, Curr. Opin. Struct. Biol. **9**, 627–634 (1999).

image interference (I^2M) + incoherent interference illumination (I^3M) microscopy (I^5M) → **fluorescence nanoscopy**.
First described in: M. G. L. Gustafsson, D. A. Agard, J. W. Sedat, *I^5M: 3D wide-field light microscopy with better than 100 nm axial resolution*, J. Microsc. **195**, 10–16 (1999).

imide – a chemical compound containing the >NH group attached to two **carbonyl** (or equivalent) groups.

impact – a collision between two bodies where relatively large contact forces exist during a very short interval of time.

impedance – the ratio of voltage to current amplitudes in a two-terminal electric network operating with alternating current. It is a complex characteristic including the real part called resistance and the imaginary part called **reactance**.

implicit function theorem states that if a function has nonzero slope at a point, then it can always be approximated by a linear function at this point.

imprinting – a lithography technique used for nanopattern fabrication. There are two approaches within it. The first is based on the transfer of a monolayer of self-assembled molecules from an elastomeric stamp to a substrate and is referred to as ink contact printing or simply **inking**. The second approach uses molding of a thin polymer film of the mask material by a stamp under controlled pressure at elevated temperature and is referred to as **embossing**. No kind of irradiation is involved in the pattern formation. Therefore, both techniques avoid shortcomings associated with wave diffraction and scattering.

The common feature of the imprint approaches is that they in fact are replication techniques. The patterns envisaged must be available as an original: the master or stamp. In analogy with conventional lithography, there is a possibility of positive and negative patterning. The originals must be fabricated following state of the art in **nanolithography** using, for example, electron beam lithography or scanning probes. For the imprint technology, where the stamp is the functional equivalent to the photo-mask in conventional projection lithography, a stepper can be used for the manufacturing process.

impurity photovoltaic effect solar cell – a **solar cell** based on the idea of exploiting two-step carrier generation via impurity states within the band gap to utilize sub-band gap **photon**s and therefore enhance solar cell performance. Three transitions available in that system, in principle, enable better matching to the solar spectrum. High efficiencies have been predicted for these solar cells. The challenge is to find a suitable host wide-band-gap semiconductor combined with a sufficiently radiatively efficient impurity.

First described in: M. A. Green, A. S. Brown, *Impurity photovoltaic effect: fundamental energy conversion efficiency limit*, J. Appl. Phys. **92**, 1329–1326 (2002); G. Beaucarne, A. S. Brown, M. J. Keevers, R. Corkish, M. A. Green, *The impurity photovoltaic (IPV) effect in wide-bandgap semiconductors: an opportunity for very-high-efficiency solar cells?*, Prog. Phot. Res. Appl. **10**, 345–353 (2002).

incoherent interference illumination microscopy (I^3M) → **fluorescence nanoscopy**.

First described in: M. G. L. Gustafsson, *Extended resolution fluorescence microscopy*, Curr. Opin. Struct. Biol. **9**, 627–634 (1999).

incoherent light – electromagnetic radiation in the optical range consisting of waves not all of the same phase and possibly wavelength.

incoherent scattering – scattering of particles or waves in which the scattering centers act independently of one another, so that there are no definite phase relationships among the different parts of the scattered beam.

independent electron approximation is used to solve the **Schrödinger equation** for electrons in solids. It removes the complications of the electron–electron interactions and replaces them with a time-averaged potential.

index guided lasers → **double heterostructure laser**.

inductance – the property of an electric circuit or of two neighboring circuits whereby, by electromagnetic induction, an electromagnetic force is generated in one circuit by a change of current in itself or in the other circuit.

inelastic collision – a collision process in which the total kinetic energy of the colliding particles is not the same as before. Part of the kinetic energy is converted into another type of energy, for example into heat, excitation, and so on.

inelastic electron tunneling spectroscopy consists of recording and analysis of tunnel currents and voltages across a metal–insulator–adsorbate–metal structure in order to extract vibrational and electronic spectroscopic information about the metals (**magnon**s and **phonon**s), the insulator, and the adsorbate.

The advantages of the method include: (i) ultra-high sensitivity–fewer than 10^{13} adsorbed molecules are required to provide a spectrum, (ii) overtone and combination bands are exceptionally weak thus making the identification of fundamentals in this method easier than in IR or **Raman** spectroscopy, (iii) optically forbidden transitions may be observed as strong bands, (iv) oxide bands are generally less intense than adsorbate bands, which makes it possible to obtain adsorbate spectra in the ''IR opaque'' regions of the oxide spectrum. Broad spectral range extending from 50 to 19 000 cm^{-1} with resolution better than 5 cm^{-1} is typically covered by the method. It is successfully used in studies of catalysis, biology, trace impurity detection, and electronic excitations.

More details in: K. W. Hipps, U. Mazur, *Inelastic electron tunneling spectroscopy*, in: *Handbook of Vibrational Spectroscopy*, edited by J. M. Chalmers, P. R. Griffiths (John Wiley and Sons, Chichester, 2002).

inelastic scattering – a scattering process in which the total momentum of interacting (colliding) particles is conserved but their total kinetic energy is not. Transformation of one type of energy into another type, for example kinetic energy of motion into heat or excitation energy, takes place. The alternative is **elastic scattering**.

inert gases – He, Ne, Ar, Kr, Xe, Rn, also called **rare gases**.

inhibitor – a substance whose addition to a reacting system results in a decrease in the rate of reaction.

injection laser → **semiconductor injection laser**.

inking – one of the approaches used for pattern fabrication by imprinting. The process is shown schematically in Figure I.1.

An elastomer stamp with a patterned surface is covered with ink and pressed onto the substrate. The ink composition is chosen to be able to form a **self-assembled** monolayer after coming into contact with the substrate. This monolayer then serves as a mask for further processing either by etching or surface reaction. The latter is particularly attractive since functionalization is intrinsic to the inking process.

The elastomeric stamp is normally made of polydi-methylsiloxane (PDMS). Thiols and alkanethiolates are suitable to be used as inks. Some of the technological challenges for the application of inking are, the alignment and diffusion of the self-assembled monolayer and the deformation of the stamp.

Mechanical stresses introduced into the PDMS stamp by handling, gravity or forces generated on the stamp/substrate interface during the propagation of the contact front negatively affect the alignment. Furthermore, because of large thermal expansion in the elastomer (for PDMS this is of the order of 10^4 K^{-1}), even small thermal fluctuations in the environment make it difficult to control the effective stamp dimension. A solution is to put a very thin pattern film (<10 μm thick PDMS) on a rigid carrier, like a silicon wafer, which reduces the distortion effects acting on the stamp.

Diffusion of the ink occurs during the printing stage, that is the period of actual contact between stamp and surface. Diffusion phenomena constitute a complex interplay between gas diffusion, movement of ink molecules and lateral movement of chemisorbed ink. Reduced diffusion leads to better resolution and hence to smaller printed feature sizes. The straightforward approach is printing with heavy inks. Long-chain thiols can be extended only to a certain limit, since further elongation leads to less ordered, and thus less etch-resistant monolayers. With thiols, the resolution is about 100 nm.



Figure I.1 Inking process steps: (a) stamp covered with monomer (top) and substrate (bottom) prior to imprinting, (b) self-assembled monolayer pattern left on the substrate after the stamp removal.

First described in: A. Kumar, G. M. Whitesides, *Features of gold having micrometer to centimetre dimensions can be formed through a combination of stamping with an elastomeric stamp and an alkanethiol 'ink' followed by chemical etching*, Appl. Phys. Lett. **63**(14), 2002–2004 (1993).

in situ – Latin meaning "at the spot", "within". The phrase "*in situ* analysis of experimental samples" is often used to show that the samples are analyzed at the place where they have been fabricated, for instance in the same vacuum chamber. An alternative is ***ex situ*** (Latin "away from") analysis indicating that the samples are analyzed in the place different from that where they have been fabricated.

insulator – a substance highly resistant to a flow of electric currents. It has a resistivity more than 10^{10} Ω cm and high dielectric strength. A solid is an insulator if there is an energy gap between its **conduction band** and **valence band** and the conduction band is not filled with electrons.

integrated circuit – an electronic solid state circuit composed of semiconductor transistors and diodes, resistors and capacitors, other electronic components and their interconnects fabricated in a single technological process into/onto a single substrate. Monocrystalline silicon is currently a widely used material for integrated circuits. The invention of the integrated circuit started the revolution in electronics and information technologies.

First described by J. S. Kilby in 1958.

More details in: J. S. Kilby, *Invention of the integrated circuits*, IEEE Trans. Electron. Dev. **23**(7), 648–654 (1976).

Recognition: in 2000 J. S. Kilby shared the Nobel Prize in Physics with Z. I. Alferov and H. Kroemer for his part in the invention of the integrated circuit.

See also www.nobel.se/physics/laureates/2000/index.html.

interface – a shared boundary between two materials.

interference – variation with distance or time of the amplitude of a wave, which results from the superposition (algebraic or vector addition) of two or more waves having the same or nearly the same frequencies.

intermediate band solar cell – a **solar cell** employing the fact that when this type of cell absorb sunlight, electrons are excited not only between the **valence** and **conduction band**s of the semiconductor material constituting the cell, but also between these bands and one or more additional bands that lie within the normally forbidden band gap of the material. Therefore, this device has the potential to reach high conversion efficiencies by increasing the photogenerated current, due to these multiple step excitations, without reducing the open-circuit voltage.

More details in: A. S. Brown, M. A. Green, *Intermediate band solar cell with many bands: Ideal performance,* J. Appl. Phys. **94**(9), 6150–6158 (2003) – theory; A. Luque, A. Marti, N. Lopez, E. Antolín, E. Canovas, C. Stanley, C. Farmer, L. J. Caballero, L. Cuadra, J. L. Balenzategui, *Experimental analysis of the quasi-Fermi level split in quantum dot intermediate-band solar cells,* Appl. Phys. Lett. **87**, 083505 (2005) – experiment.

internal photoelectric effect – excitation of electrons from the **valence band** of a semiconductor to its **conduction band** as a result of light absorption.

internal quantum efficiency → **quantum efficiency**.

interstitial – a position in a crystal lattice between regular lattice positions of atoms. The term is used for an atom occupying an interstitial position.

intrinsic semiconductor – if the concentration of charge carriers in a semiconductor is a characteristic of the material itself rather than dependent upon an impurity content or structural defects of the crystal, then the semiconductor is defined an intrinsic semiconductor.

intron – a **nucleotide** sequence intervening between **exons** (coding regions) that is excised from a gene transcript during **RNA** processing.

invariance – the property of a physical quantity or physical law of being unchanged by a certain transformations or operations such as reflection of spatial coordinates, time reversal, charge conjugation, rotations or **Lorentz transformations**.

inversion symmetry – the principle that laws of physics are unchanged by the operation of inversion.

ionic bond – a type of chemical bonding of atoms in which one or more electrons are transferred completely from one atom to another, thus converting the neutral atoms into electrically charged ions.

ionic crystal – a solid formed by **ionic bonds** between constituents.

ionization energy (of an atom) – the minimum energy required to ionize the atom starting from its ground state.

ion laser – a **laser** in which the transition involved in stimulated emission of radiation takes place between two energy levels in an ionized gas. One of the inert gases (argon, helium, neon, or krypton) is used as the active medium. The device is schematically shown in Figure I.2.

The gases are electrically excited in a container called a plasma tube, which typically consists of an alumina or ceramic envelope that is vacuum sealed at each end by either two Brewster windows or one Brewster window and one sealed cavity mirror. The optical cavity is defined by a 100% reflecting mirror and a partially transmissive output coupling mirror. It provides moderate to high continuous-wave output of typically 1 mW to 10 W. For single-frequency operation, the high reflector is replaced by a Brewster prism, and an etalon is inserted.



Figure I.2 Ion laser.

irradiance – an energy per unit time crossing a unit area oriented normal to the propagation direction. The term is usually applied to characterize light beams.

isodesmic structure – a crystal structure formed by ions in which there are no distinct groups formed within the structure, that is where no bond is stronger than any other → **anisodesmic** and **mesodesmic structures**.

isoelectronic atoms – atoms with the same number of valence electrons.

isoelectronic principle states that any two or more molecules which are isoelectronic will have similar molecular orbitals. Molecules possessing the same number of electrons distributed over a similar molecular framework are isoelectronic.

isomers – molecules with the same chemical formula but possessing different properties. There are two main forms of isomers: structural (constitutional) isomers and spatial isomers – **stereoisomers**. The tree of isomeric forms is presented in Figure I.3. In **structural isomers**, the atoms and functional groups are joined together in different ways, as in the example of propyl alcohol. This group includes **chain isomers** in which hydrocarbon chains have variable amounts of branching, **position isomers** which deal with the position of a functional group on a chain, and **functional group isomers** in which one functional group is split up into different smaller ones.

In **stereoisomers**, the bond structure is the same but the geometrical positioning of atoms and functional groups in space differs. This class includes **enantiomers** where different isomers are mirror-images of each other, and **diastereomers** when they are not. Diastereomers are again subdivided into **conformers** (conformal isomers) when isomers can interconvert by chemical bond rotations and **cis-trans isomers** when this is not possible. Note that although conformers can be referred to as having a diastereomeric relationship, the isomers over all are not diastereomers, since bonds in conformers can be rotated to make them mirror images. Such conformers are referred to as **rotamers**.

First described by J. J. Berzelius and F. Woehler in 1827.


Isomers
Structural isomers
Spatial isomers (stereoisomers)
Diastereomers
Enantiomers
Cis-trans isomers
Conformers
Rotamers

Figure I.3 Isomeric forms of molecules (from Wikipedia).

isomorphic solids – solids which crystallize with the same symmetry, with similar facial development, and have closely similar values of the interfacial angles. Such solids often form mixed compounds with one another.

isotope – one of two or more nuclides having the same atomic number, hence constituting the same element, but differing in mass number because of the difference in the content of neutrons in their nuclei.

isotropy (of matter) – the same physical properties of a medium found in all directions. The alternative is **anisotropy**.

J

From Jahn–Teller effect to Joule's law of electric heating

Jahn–Teller effect → **Jahn–Teller theorem.**

Jahn–Teller theorem states that if a particular symmetric configuration of a nonlinear molecule causes it to have an orbitally degenerate ground state, then this configuration is unstable with respect to one of lower symmetry which does not give rise to an orbitally degenerate ground state. Thus, a system having a degenerate ground state will spontaneously evolve to lower its symmetry unless the degeneracy is simply a spin degeneracy.

The tendency of molecular systems to distort when electronic degeneracy is present is referred to be the **Jahn–Teller effect**.

First described in: H. A. Jahn, E. Teller, *Stability of polyatomic molecules in degenerate electronic states. Part I. Orbital degeneracy*, Proc. R. Soc. A **161**, 220–235 (1937).

Jastrow correlation factor → **Slater–Jastrow wave function**.

Jaynes–Cummings model describes a system of a two-level atom interacting with a quantized mode of an optical cavity, with or without the presence of light. The **Hamiltonian** describing the interacting system is $\mathbf{H} = \mathbf{H}_{field} + \mathbf{H}_{atom} + \mathbf{H}_{JC}$, where $\mathbf{H}_{field}$ is the free field Hamiltonian, $\mathbf{H}_{atom}$ is the atomic excitation Hamiltonian and the Jaynes-Cummings interaction Hamiltonian assuming the zero field energy at zero is $\mathbf{H}_{JC} = g(\mathbf{A}_c\sigma_+ e^{i\delta t} + \mathbf{A}_a\sigma_- e^{-i\delta t})$ with $g = d(\omega/\hbar V\epsilon_0)^{1/2}$ and $\delta = |\omega - \nu|$, where d is the atomic transition moment, V is the mode volume of the cavity, ω is the atomic transition frequency, and ν is the radiation field angular frequency. Here $\mathbf{A}_c$ and $\mathbf{A}_a$ are the Bosonic creation and annihilation operators, respectively. The operators $\sigma_+ = \sigma_x + i\sigma_y$ and $\sigma_- = \sigma_x - i\sigma_y$ are the level raising and lowering operators or the atomic spin-flip operators in terms of **Pauli matrices**.

The model serves to find out how quantization of the radiation field affects the predictions for the evolution of the state of a two-level system in comparison with semi-classical theory of light–atom interaction.

First described in: E. T. Jaynes, F. W. Cummings, *Comparison of quantum and semiclassical radiation theories with application to the beam maser*, Proc. IEEE 51(1), 89–109 (1963).

More details in: C. C. Gerry, P. L. Knight, *Introductory Quantum Optics* (Cambridge University Press, Cambridge, 2005).

Johnsen–Rahbek effect is observed when a semiconductor is placed between two electrodes. The frictional force between the electrodes and the semiconductor is increased if an electric bias is applied to the electrodes. The effect is particularly strong in the case of suspensions of fine semiconductive powders of high dielectric constant in low-viscosity oils. It results in a marked increase in the viscosity of the liquid.

First described in: A. Johnsen, K. Rahbek, *A physical phenomenon and its applications to telegraphy, telephony, etc.*, J. Sci. Inst. Elect. Eng. **61**, 713–725 (1923).

Johnson and Lark–Horowitz formula defines the resistivity ρ of a metal or degenerate semiconductor as $\rho \sim N^{1/3}$, where N is the density of impurities.

First described in: V. A. Johnson, K. Lark–Horowitz, *Electronic mobility in germanium*, Phys. Rev. **79**(2), 409–410 (1950).

Johnson–Kendall–Roberts theory takes into account **adhesion** forces starting from the **friction force theory (Hertz theory)**. Considering the contact between a sphere and flat surfaces and taking into account the interfacial energies one obtains for the friction force $F_f = \tau\pi(R/K)^{2/3}F_{\mathrm{JKR}}^{2/3}$, where τ is the **shear modulus** and $F_{\mathrm{JKR}} = N + 3\pi R\gamma + \sqrt{6\pi R\gamma N + (3\pi R\gamma)^2}$ defines the **Johnson–Kendall–Roberts force**. In this force N is the applied load, R is the radius of the sphere, and $\gamma = \gamma_1 + \gamma_2 - \gamma_{1,2}$ is the interfacial energy (γ_1 is the surface energy of the sphere, γ_2 is the surface energy of the flat surface, and $\gamma_{1,2}$ is the energy of the interface). For the meaning of $K \rightarrow$ **friction force theory**. Practically, the effect of considering adhesion is to replace the external applied load N with a total load that includes the adhesive force. The contact area and the friction force can be different from zero even if the external applied load is zero, because of the presence of adhesion. For zero applied load, the friction force reduces to $F_{f0} = \tau\pi[(6\pi R^2\gamma)/K]^{2/3}$ and the contact radius becomes $a_0 = [(6\pi R^2\gamma)/K]^{1/3}$. The adhesion expressed in this theory can be measured by **atomic force microscopy (AFM)** withdrawing the probe until the contact is broken. The negative attractive force applied to the probe at this point is called the **pull-off force** $F_{JKR}^{PO} = -(3/2)\pi R\gamma$.

This theory is more useful for highly adhesive systems with low stiffness and large (tip) radii.

First described in: K. L. Johnson, K. Kendall, A. D. Roberts, *Surface energy and the contact of elastic solids*, Proc. R. Soc. Lond. A **324**, 301–313 (1971).

Johnson–Kendall–Roberts force → **Johnson–Kendall–Roberts theory**.

Johnson–Nyquist noise – equilibrium fluctuations of the electric potential inside a conductor occurring without any applied voltage. It is a result of the random thermal motion of the charge carriers. It is to be distinguished from **shot noise**, which describes the additional current fluctuations that occur when a voltage is applied and a macroscopic current starts to flow.

First described in: J. Johnson, *Thermal agitation of electricity in conductors,* Phys. Rev. **32**(1), 97–109 (1928) – experiment; H. Nyquist, *Thermal agitation of electric charge in conductors,* Phys. Rev. **32**(1), 110–114 (1928) – theory.

Josephson effects arise in tunneling of superconducting electron pairs from a superconductor through a layer of an insulator into another superconductor.

Direct current Josephson effect: a tunnel junction between superconductors shows a zero-voltage suppercurrent due to the tunneling of condensed pairs; a direct current flows across the junction in the absence of any electric or magnetic field.

Alternating current Josephson effect: if a voltage difference V was maintained across the junction, the current would be an alternating current of frequency $2eV/h$. A constant voltage applied across the junction causes high frequency current oscillations across the junction.

Macroscopic long-range quantum interference: a constant magnetic field applied through a superconducting circuit containing two junctions causes the maximum supercurrent to show interference effects as a function of magnetic field intensity. This effect is used in sensitive magnetometers.

First described in: B. D. Josephson, *Possible new effects in superconductive tunneling,* Phys. Lett. **1**(7), 251–253 (1962).

More details: A. Barone, G. Paterno, *Physics and Applications of Josephson Effects* (John Wiley, New York, 1982).

Recognition: in 1973 B. D. Josephson received the Nobel Prize in Physics for his theoretical predictions of the properties of a supercurrent through a tunnel barrier, in particular those phenomena which are generally known as the Josephson effects.

See also www.nobel.se/physics/laureates/1973/index.html.

Joule's law of electric heating – the heating effect of an electric current I passing through a resistance R for a time t is proportional to I^2Rt.

First described in: J. P. Joule, *On the heat evolved by metallic conductors of electricity,* Phil. Mag. **19**, 260–265 (1841).

K

From Kane model to Kuhn–Thomas–Reiche sum rule

Kane model is required if materials with narrow direct energy gaps at the first **Brillouin zone** center are considered. The energy of the Γ valley is assumed to be non-parabolic, spherical, and of the form $\hbar^2\mathbf{k}^2/2m^* = E(1+\alpha E)$, where $\mathbf{k}$ denotes the wavevector, E represents the energy, m^* is the effective mass, and $\alpha = (1 - m^*/m_0)^2/E_g$ is the non-parabolicity coefficient with E_g to be the energy gap.

First described in: E. O. Kane, *Band structure of indium antimonide,* J. Phys. Chem. Solids **1**, 249–261 (1957).

Keesom potential – the intermolecular potential accounting for a contribution from a dipole interaction in the **Lennard–Jones potential** in the form:

$$V(r_{ij}) = \epsilon[(r_0/r_{ij})^{12} - 2(r_0/r_{ij})^6] - \frac{\mu_i^2\mu_j^2}{3k_B T r_{ij}^2},$$

where r_{ij} is the distance between molecules i and j, μ_i and μ_j being the dipole moments of these molecules. Here the first term is the classical non-polar **Lennard–Jones potential** while the second one is responsible for the dipole interaction. The potential is useful for phase equilibria simulations, in particular in vapor-liquid systems.

First described in: W. H. Keesom, *Die van der Waalschen Kohäsionskräfte,* Phys. Z. **22**, 129–141 (1921).

More details in: J. Israelachvili, *Intermolecular and Surface Forces,* 2nd Edn. (Academic Press, London, 1991).

Keldish theory describes the process of multiphoton ionization in which an atom is ionized as a consequence of the rapid absorption of a sufficient number of photons. The ionization rate is predicted to be dependent primarily upon the ratio of the mean binding electric field to the peak strength of the incident electromagnetic field and upon the ratio of the binding energy to the energy of photons in the field.

First described in: L. V. Keldysh, *Ionization in the field of a strong electromagnetic wave,* Sov. Phys. JETP **20**(5), 1018–1027 (1965).

Kelvin equation gives the increase in vapor pressure of a substance at a temperature T, which accompanies an increase in the curvature of its surface: $p_s/p_f = (2\sigma v)/(rR_0T)$, where p_s and p_f are vapor pressures at spherical and flat surfaces respectively, σ is the surface tension, v is the molecular volume of the condensed phase, and r is the mean surface curvature. The equation predicts the greater rate of evaporation of a small liquid droplet than that of a larger one and the greater solubility of small solid particles than that of larger particles.

First described in: W. Thomson (Lord Kelvin), *On the equilibrium of vapor at a curved surface of liquid*, Phil. Mag. **42**, 448–452 (1871).

Kelvin problem is formulated as What shape would equal "volume bubbles need to take on in order to yield the minimum surface area for a foam?". Lord Kelvin thought (1887) that it was a body-centered cubic structure filled with distorted 14 sided cells, while later (1994) D. Weaire and R. Phelan showed that a lower surface area could be produced in a foam containing two kinds of bubbles: one with 14 sides and the other with 12 sides.

First described in: W. Thomson (Lord Kelvin), *On the division of space with minimum partitional area*, Phil. Mag. **24**(151), 503 (1887); D. Weaire, R. Phelan, *A counterexample to Kelvin's conjecture on minimal surfaces*, Phil. Mag. Lett. **69**, 107–110 (1994).

Kelvin relations – interrelations of the coefficients describing thermoelectric effects in a loop composed of two materials, say A and B, at absolute temperature $T : \alpha_{AB}T = \pi_{AB}$ and $T\mathrm{d}\alpha_{AB}/\mathrm{d}T = \tau_A - \tau_B$, where α_{AB} is the **Seebeck coefficient**, π_{AB} is the **Peltier coefficient**, τ_A and τ_B are the **Thomson coefficients**.

First described in: W. Thomson (Lord Kelvin), *On a mechanical theory of thermoelectric currents*, Proc. R. Soc. Edinburgh: 91–98 (1851).

Kennard packet indicates a wave packet for which the product of the root mean square deviations of position and momentum from their mean values is as small as possible, being equal to $h/4\pi$.

First described in: E. H. Kennard, *Wave mechanics of deflected electrons*, Phys. Rev. **36**(11), 1667–1668 (1930).

Kerr effects: **Electrooptical Kerr effect** – a transparent isotropic medium becomes doubly refracting when it is placed in an electric field. Its optical properties are similar to those of a birefringent crystal with its optical axis in the direction of the electric field. **Magnetooptical Kerr effect** – changes produced in the optical properties of a reflecting surface of a **ferromagnetic** when it is magnetized. This applies especially to the elliptical polarization of reflected light, when the ordinary rules of metallic reflection would give only plane polarized light.

First described in: J. Kerr, *A new relation between electricity and light: dielectrified media birefringent*, Phil. Mag. **50**, 337–348 and 446–458 (1875); J. Kerr, *On rotation of the plane of polarization by reflection from the pole of a magnet*, Phil. Mag. **3**(Ser. 5), 321–343 (1877); J. Kerr, *On reflection of polarized light from the equatorial surface* *of a magnet,* Phil. Mag. **5**(Ser. 5), 157–161 (1878); J. Kerr, *Measurements and law in electro-optics,* Phil. Mag. **9**(Ser. 5), 157 (1880).

ket → **Dirac notation**.

ketones – organic compounds that have an **alkyl group** ($–C_nH_{2n+1}$) or **aromatic ring** bonded to a **carbonyl group** ($>C=O$). These may be RCOR′ or ArCOR or ArCOAr compounds with R and R′ representing alkyl groups ($–C_nH_{2n+1}$) and Ar representing *aromatic ring*.

Kikoin–Noskov effect – appearance of an electric field in a light-irradiated semiconductor placed in a magnetic field. This electric field is perpendicular to the magnetic field and to the direction of diffusion of the light- generated carriers from the illuminated surface to the bulk.

First described in: I. K. Kikoin, M. M. Noskov, *Hall effect internal photoelectric effect in cuprous oxide,* Phys. Z. Sowjetunion **4**(3), 531–550 (1933).

kilo- – a decimal prefix representing 10^3, abbreviated k.

kinematics is the study of the motion of material particles without reference to the forces acting on them.

kinetics – from Greek meaning "motion". The term is used to describe how a process or chemical reaction develop in a time scale.

Kirchhoff equation – the rate of change with temperature of the heat ΔH of a process (such as a chemical reaction) carried out at a constant pressure is given by

$$\left(\frac{\partial \Delta H}{\partial T}\right)_P = \Delta \left(\frac{\partial H}{\partial T}\right)_P = \Delta C_P,$$

where ΔC_P is the change in the heat capacity at constant pressure for the same process. Similarly for a process carried out at a constant volume.

Kirchhoff law (for radiation) states that the ratio of the emissive power for thermal radiation of a given wavelength is the same for all bodies at the same temperature and is equal to the emissive power of a black body at that temperature.

First described in: G. R. Kirchhoff, *Über einen Satz der mechanischen Wärmetheorie und einige Anwendungen desselben,* Ann. Phys. **103**, 177–205 (1858).

Kirchhoff laws (for electrical circuits) refer to the voltage and electric currents in an electric network. The "**current law**" states that the sum of all currents flowing toward a node of the network must be zero $\sum_n I_n = 0$. The "**voltage law**" states that when traversing the network along a closed loop the sum of all voltages encountered must be zero $\sum_n V_n = 0$.

First described in: G. R. Kirchhoff, *Über den Durchgang eines elektrischen Stromes durch eine Ebene, insbesondere durch eine kreisförmige*, Ann. Phys. **64**, 497–514 (1845); G. R. Kirchhoff, *Über die Auflösung der Gleichungen, auf welche man bei Untersuchung der linearen Vertheilung galvanischer Ströme geführt wird*, Ann. Phys. **72**, 497–508 (1847).

Kirkendall effect – a movement of the interface between different phases due to high temperature interdiffusion of the constituents of these phases. It is observed in the migration of atomic markers that occurs when the markers are placed at the interface between an alloy and a metal. The markers usually move toward the alloy region because of an appropriate concentration gradient of the metal. The phenomenon supports the idea that atomic diffusion occurs mainly through a vacancy exchange mechanism.

The effect has important practical consequences. One of these is the prevention or suppression of voids formed at the boundary interface in various kinds of alloy-to-metal bonding. These voids are referred to as **Kirkendall voids**.

First described in: A. D. Smigelskas, E. O. Kirkendall, *Zinc diffusion in alpha brass*, Trans. AIME **171**, 130–142 (1947).

Kirkendall voids → **Kirkendall effect**.

KKR method → **Korringa–Kohn–Rostoker method**.

Klein–Gordon equation is $d^2\psi/dt^2 = -(\mathbf{c}^2\mathbf{p}^2 + m^2\mathbf{c}^4)\psi$, where $\mathbf{p}$ is the momentum operator of the particle with rest mass m. It accounts for the special theory of relativity. It is used in the theory of quantized fields of particles with spin 0 or 1. This equation was contemporarily formulated by many authors.

First described in: E. Schrödinger, *Quantisierung als Eigenwertproblem. (Vierte Mitteilung)*, Ann. Phys. **81**, 109–139 (1926); J. Kudar, *Zur vierdimensionalen Formulierung der undulatorischen Mechanik*, Ann. Phys. **81**, 632–636 (1926); O. Klein, *Quantentheorie und fünfdimensionale Relativitätstheorie*, Z. Phys. **37**(12), 895–906 (1926); V. Fock, *Zur Schrödingerschen Wellenmechanik*, Z. Phys. **38**(3), 242–250 (1926); V. Fock, *Über die invariante Form der Wellen- und der Bewegungsgleichungen für einen geladenen Massenpunkt*, Z. Phys. **39**(2–3), 226–232 (1926); W. Gordon, *Der Comptoneffekt nach der Schrödingerschen Theorie*, Z. Phys. **40**(1–2), 117–133 (1926).

More details in: H. Kragh, *Equation with the many fathers. The Klein–Gordon equation in 1926*, Am. J. Phys. **52**(11), 1024–1033 (1984).

Klein–Nishina formula gives the differential cross section $d\phi$ for **Compton scattering** into a small solid angle $d\Omega$ of an x- or gamma-photon by an unbound electron:

$$d\phi = \left(\frac{r_o \nu}{2\nu_0}\right)^2 \left(\frac{\nu_0}{\nu} + \frac{\nu}{\nu_0} - 2 + 4\cos^2\theta\right) d\Omega,$$

where ν and ν_0 are the frequencies of incident and scattered photons, θ is the angle between their polarization vectors, and $r_0 = e^2/mc^2$ the classical radius of an electron.

First described in: O. Klein, I. Nishina, *Scattering of radiation by free electrons on the new relativistic quantum dynamic of Dirac*, Z. Phys. **52**(11/12), 853–868 (1929).

Knight shift – a fractional increase in the frequency for **nuclear magnetic resonance** of a given nuclide in a metal subjected to an external magnetic field relative to that for the same nuclide in a nonmetallic compound in the same field, caused by the orientation of the conduction electrons in the metal.

First described in: C. H. Townes, C. Herring, C. Knight, *The effect of electronic paramagnetism on nuclear magnetic resonance frequencies in metals*, Phys. Rev. **77**(6), 852–853 (1950).

Knudsen cell → **effusion (Knudsen) cell**.

Knudsen cosine rule states that individual gaseous molecules impinging on an irregular solid surface are reflected in a direction totally independent of the direction of incidence. The probability ds that a molecule leaves the surface in the solid angle $d\omega$ forming an angle θ with the normal to the surface is defined as $\pi ds = d\omega \cos\theta$.

Kohlrausch laws – (i) the "**law of the independent migration of ions**" states that every ion at infinite dilution contributes a definite amount toward the equivalent conductance of an electrolyte, irrespective of the nature of the other ions with which it is associated; (ii) "**Kohlrausch's square root law**" states that the equivalent conductance of a strong electrolyte in a very dilute solution gives a straight line when plotted against the square root of concentration.

First described in: F. Kohlrausch, *Über das Leistungvermögen einiger Electrolyte in äusserst verdünnter wässriger Lösung*, Ann. Phys. **26**, 161–225 (1885).

Kohlrausch's square root law → **Kohlrausch laws.**

First described in: F. Kohlrausch, *Über die elastische Nachwirkung bei der Torsion*, Ann. Phys. **119**, 337–367 (1863).

Kohn–Sham equations promote practical applicability of the **density functional theory** (DFT) to map the many-particle problem to an independent particle problem in an affective potential. In DFT the total energy is described by:

$$E[n] = T_s[n] + E_H[n] + E_{ext}[n] + E_{xc}[n],$$

where $T_s[n]$ is the kinetic energy of noninteracting electrons, that is independent particles and can be given explicitly by the single-electron orbitals $\psi_i(\mathbf{r})$; $E_H[n]$ is the Hartree energy describing the Coulomb interaction of the electrons in their electrostatic potential; $E_{\text{ext}}[n]$ is the energy caused by the external potential; $E_{\text{xc}}[n]$ is the exchange-correlation energy functional. The final result of applying the **variation principle** leads to the Kohn–Sham equations:

$$\left(-\frac{\hbar^2}{2m}\nabla^2 + V_{\text{H}}(\mathbf{r}) + V_{\text{ext}}(\mathbf{r}) + V_{\text{xc}}(\mathbf{r})\right)\psi_i(\mathbf{r}) = \epsilon_i\psi_i(\mathbf{r}),$$

where ϵ_i are Lagrange parameters, which can be often interpreted as excitation energies.

This form of equations is equivalent to a one-particle **Schrödinger equation** in an effective potential consisting of the Hartree potential V_H:

$$V_H(\mathbf{r}) = e^2\int\frac{n(\mathbf{r}')}{|\mathbf{r}-\mathbf{r}'|\mathrm{d}^3r},$$

the external potential V_{ext} and the exchange-correlation potential V_{xc}:

$$V_{\text{xc}}(\mathbf{r}) = \frac{\delta E_{\text{xc}}[\mathbf{r}]}{\delta n(\mathbf{r})}.$$

First described in: W. Kohn, L. J. Sham, *Self-consistent equations including exchange and correlation effects,* Phys. Rev. A **140**(4), 1133–1137 (1965).

Kondo cloud → **Kondo effect**.

Kondo effect – an increase in the electrical resistance of a bulk sample when approaching absolute zero temperature related to nonzero total spin of all electrons in it. The effect is observed in bulk metals containing a small fraction of magnetic impurities (like Fe, Co, Ni) and in quantum dots; however, in this last case it is the conduction that shows an increase. The temperature T_K at which the resistance starts to increase again is called the **Kondo temperature**.

An explanation of the Kondo effect can be given within the model of a magnetic impurity proposed by P. W. Anderson (1961). It is illustrated by the energy diagrams presented in Figure K.1.

The magnetic impurity atom in a nonmagnetic metal is represented by a quantum well that has only one electron energy level E_0 below the Fermi energy of the host metal. This level is occupied by one electron with a particular spin, for instance the electron has its spin up as shown in the diagram. The impurity atom is surrounded by a sea of electrons from the host metal atoms in which all the states with energies below the Fermi level are occupied, while the high energy states are empty. An electric bias applied to the sample makes the occupied levels in the sea of electrons slightly different at the sides of the well.

Adding another electron to the well is prohibited by the Coulomb interaction characterized by the energy barrier U. Removal of the electron from the impurity atom would need at least E_0 to be added to the system. However, the **Heisenberg's**



Figure K.1 The Anderson's model of a magnetic impurity atom in a metallic electrically biased sample.

uncertainty principle allows the electron to leave the level in the well for a short time around h/E_0. The electron may tunnel out of the well to briefly occupy a classically forbidden virtual state outside the well, and then be replaced by an electron from the outside sea of electrons. The newcomer may have an oppositely directed spin, and it flips the spin of the impurity. As a result, a difference between the initial and final spin states of the impurity appears.

The spin exchange qualitatively modifies the energy dependence of the density of states in the system. Many such processes occurring together are known as **Kondo resonance**. It provides a new state, called the **Kondo state**, with exactly the same energy as the Fermi level. This state is always "on resonance" as it is attached to the Fermi energy. Since the Kondo state is created by the exchange process between the electron localized near the magnetic impurity atom and the free electrons of the host metal, the Kondo effect is a typical many-body phenomenon. The electrons that have previously interacted with the same magnetic impurity form so-called **Kondo clouds**. Since each of these electrons contains information about the same impurity, they inevitably carry information about each other. So, the electrons in the clouds are mutually correlated.

The increase in the resistance with a temperature drop in the low temperature range is the first hint of the existence of the Kondo state. This state increases scattering of electrons with energies close to the Fermi level. The hybridization of conduction electrons with the localized spin of a magnetic impurity atom in a metal leads to an enhancement of resistivity at low temperature. The total resistivity as a function of temperature has the form $\rho = AT^5 - B\ln T + C$, where A, B, C are the constants dependent on concentration of magnetic ions, exchange energy, and strength of the exchange scattering. The Kondo temperature is:

$$T_K = \frac{\sqrt{\Delta EU}}{2} \exp \frac{\pi E_0(E_0 + U)}{\Delta EU},$$

where ΔE is the width of the impurity energy level broadened by electron tunneling from it. The Kondo temperature varies as the one-fifth power of the concentration of the magnetic impurity. In bulk metallic systems it ranges from 1 to 100 K.

For a Kondo system, the ratio between its actual resistance R and its resistance at absolute zero R_0 depends only on temperature as $R/R_0 = f(T/T_K)$. All materials that contain spin 1/2 impurities can be described by the same temperature-dependent function $f(T/T_K)$. Thus, the system can be completely characterized by the Kondo temperature instead of the set containing U, E_0 and ΔE.

Quantum dots are another class of systems, whose transport properties can also be affected by the Kondo effect, but which offer a much higher degree of control over the system parameters with respect to magnetic impurities in bulk metals. A quantum dot confining a well-defined number of electrons can act as a magnetic impurity. The total spin is zero or an integer for an even number of electrons and an half integer for a odd number of electrons. The latter case is a canonical example to observe the Kondo effect. All electrons can be ignored, except for the one with the highest energy; that is, the case of a single, isolated spin, $s = 1/2$.

A dot supplied with gates can be switched from a Kondo system to a non-Kondo system as the number of electrons in the dot is changed from odd to even. Such a structure is shown in Figure K.2.



Figure K.2 An external bias-operated quantum dot and its conductance as a function of the gate voltage changing the number n of confined electrons at two different temperatures.

The dot is connected with two reservoirs of electrons by tunneling channels with transparencies controlled by the bias applied to the income and outcome gates. Coupling of the dot with the electron source and drain defines the energy broadening ΔE of the state in the dot. The number of electrons in the dot and their energy levels are tuned by the voltage applied to the central gate. The Kondo temperature can be varied by means of the gate voltage as a single particle energy state nears the **Fermi energy**.

One of the main distinctions between a quantum dot and a bulk metal with a magnetic impurity relates to the nature of the electron states there. In a metal, the electron states are plane waves. Their scattering at the impurity atoms results in mixing of the electron waves with different momenta. This change of the momentum increases the material resistance.

In a quantum dot, all electrons have to travel through the dot, as there is no electrical pass around it. In this case the Kondo resonance makes it easier for states belonging to the two opposite electrodes to mix. Such mixing increases the conductance–the resistance is decreased. So far the Kondo effect in quantum dots leads to the opposite behavior of the resistance to that in a bulk metal. Figure K.2 shows variation of the dot conductance as a function of the gate voltage tuning the number of electrons confined in the dot at two different low temperatures. When an even number of electrons is trapped, the conductance decreases as the temperature is lowered. Such behavior indicates that there is no Kondo effect in this case. The opposite temperature dependence is observed for an odd number of electrons when the Kondo effect takes place.

Like the resistance of a bulk sample in the Kondo regime, the conductance of a quantum dot depends only on the ratio T/T_K. At the lowest temperature the conductance approaches the quantum limit of conductance $2e^2/h$. The fact that the conductance reaches this value implies that electrons are transmitted through the dot perfectly. The Kondo effect allows a dot to become completely transparent.

The Kondo effect can also be observed in quantum dots with an even number of electrons, but the sample has to be placed in a magnetic field in order to get appropriate spin splitting and energy level occupation.

First described in: J. Kondo, *Resonance minimum in dilute magnetic alloys,* Prog. Theor. Phys. **32**(1), 37–49 (1964).

Kondo resonance → **Kondo effect**.

Kondo temperature → **Kondo effect**.

Koopmans theorem states that the ionization potentials for closed-shell molecules may be approximated by the negative of orbital energies obtained from a Hartree–Fock calculation. This provides a physical interpretation of the computed orbital energies. Thus, the lowest ionization potential of the neutral species can be estimated from the orbital energy of the highest occupied molecular orbital (**HOMO**). This is the so-called vertical ionization potential. ‘‘Vertical’’ because the underlying assumption is that no geometrical or electronic structural changes occur during the ionization process. Hence, in this model the wavefunction for the cation is identical to that of the neutral atom.

First described in: T. Koopmans, *Über die Zuordnung von Wellenfunktionen und Eigenwerten zu den einzelnen Electronen eines Atoms*, Physica **1**, 104–113 (1934).

Kopp law states that for solids, the molar heat capacity of a compound at room temperature and pressure approximately equals the sum of the heat capacities of the constituent elements.

First described in: H. Kopp, *Untersuchungen über die spezifische Wärme der starren und tropfbar-flüssigen Körper*, Ann. Chem. Pharm. Suppl. **3**, 289 (1864).

Korringa–Kohn–Rostoker (KKR) method – a method of band structure calculations of solids using standard **Green's functions** to transform the **Schrödinger equation** into the equivalent integral equation.

Within the method, the wave function $\psi(\mathbf{k},\mathbf{x})$ is calculated via the Green's function $G(\mathbf{k},\mathbf{x}\text{-}\mathbf{x}';\,E)$ satisfying the free-particle Schrödinger equation

$$\left(\frac{\hbar^2}{2m}\nabla^2+E\right)G(\mathbf{k},\mathbf{x}\text{-}\mathbf{x}';\,E)=\delta^3(\mathbf{x}\text{-}\mathbf{x}')$$

describing the response to a delta function $\delta^3(\mathbf{x}\text{-}\mathbf{x}')$. The final integral equation for the wave function takes the form

$$\psi(\mathbf{k},\mathbf{x})=\int d^3\mathbf{x}'\,G(\mathbf{k},\mathbf{x}\text{-}\mathbf{x}';\,E)\,V(\mathbf{x}')\,\psi(\mathbf{k},\mathbf{x}'),$$

where $V(\mathbf{x})$ is the crystal potential.

First described in: J. Korringa, *On the calculation of the energy of a Bloch wave in a metal*, Physica **13**, 392–400 (1947); W. Kohn, N. Rostoker, *Solution of the Schrödinger equation in periodic lattices with an application to metallic lithium*, Phys. Rev. **94**(5), 1111–1120 (1954).

Kossel crystal – a crystal in which repletion takes place in steps. Its widespread graphic representation in two dimensions is shown in Figure K.3.



Figure K.3 Two-dimensional Kossel crystal.

It typically has a simple cubic lattice and central symmetry of the additive interaction forces between its building elements.

First described in: W. Kossel, *Zur Theorie des Kristallwachstums*, Nachr. Akad. Wiss. Göttingen, math. phys. Kl. **27**, 135–143 (1927).

Kossel effect arises when characteristic X-rays generated by atoms in a single crystal produces series of cones of reflected X-rays.

Kossel–Stranski surface – a crystal surface built by step-by-step repetitions. It is typical for a **Kossel crystal**.

First described in: W. Kossel, *Molecular forces in crystal growth*, Phys. Z. **29**, 553–555 (1928); I. N. Stranski, *Zur Theorie des Kristallwachstums*, Z. Phys. Chem. **136**(3/4), 259–278 (1928).

Kramers theorem states that in the absence of an external magnetic field the stationary states of an atomic system are always degenerate when the system contains an odd number of electrons, the degree of degeneracy being an even number. If the number of electrons is even, the energy will not be influenced in the first approximation by a magnetic field.

First described in: H. A. Kramers, *General theory of paramagnetic rotation in crystals*, Proc. K. Akad. Amsterdam **33**(9), 959–972 (1930).

Kramers–Kronig dispersion relation connects real $\epsilon_1(\omega)$ and imaginary $\epsilon_2(\omega)$ parts of the **dielectric function** via

$$\epsilon_1(\omega) = 1 + (2/\pi)P \int \epsilon_2(\omega')\omega' d\omega'/(\omega'^2 - \omega^2),$$

where P means principal value of the following integral. The dispersion relation is based on the causality principle.

First described in: R. L. Kronig, *Theory of dispersion of X-rays*, J. Opt. Soc. Am. **12**(June), 547–557 (1926); H. A. Kramers, Estratto degli Atti del Congresso Internazionale dei Fisici, Como, vol. **2** (Bologna, 1927) p. 545.

Kronecker delta function denoted as $\delta_{m,n}$ has the value 1 when $m = n$ and 0 otherwise. It is also known as **Kronecker symbol**.

First described by L. Kronecker in 1866.

Kronecker product – a special tensor product of two matrices of arbitrary size. If **A** is an m-by-n matrix and **B** is a p-by-q matrix, then their Kronecker product is the *mp*-by-*nq* block matrix:

$$\mathbf{A}\otimes\mathbf{B}\begin{bmatrix} a_{11}b_{11} & \dots & a_{11}b_{1q} & \dots & a_{1n}b_{11} & \dots & a_{1n}b_{1q} \\ a_{11}b_{21} & \dots & a_{11}b_{2q} & \dots & a_{1n}b_{21} & \dots & a_{1n}b_{2q} \\ \dots & \dots & \dots & \dots & \dots & \dots & \dots \\ a_{11}b_{1p} & \dots & a_{11}b_{pq} & \dots & a_{1n}b_{p1} & \dots & a_{1n}b_{pq} \\ \dots & \dots & \dots & \dots & \dots & \dots & \dots \\ a_{m1}b_{11} & \dots & a_{m1}b_{1q} & \dots & a_{mn}b_{11} & \dots & a_{mn}b_{1q} \\ a_{m1}b_{21} & \dots & a_{m1}b_{2q} & \dots & a_{mn}b_{21} & \dots & a_{mn}b_{2q} \\ \dots & \dots & \dots & \dots & \dots & \dots & \dots \\ a_{m1}b_{p1} & \dots & a_{m1}b_{pq} & \dots & a_{mn}b_{p1} & \dots & a_{mn}b_{pq} \end{bmatrix},$$

Kronecker symbol → **Kronecker delta function**.

Kronig–Penney model – an idealized one- dimensional model for a crystal in which the potential energy of an electron is an infinite sequence of periodically spaced square wells. Such a rectangular in space potential is called the **Kronig–Penney potential**.

First described in: R. de L. Kronig, W. G. Penney, *Quantum mechanics of electrons in crystal lattices*, Proc. R. Soc. A **130**, 499–513 (1931).

Kronig–Penney potential → **Kronig–Penney model.**

Kubo formalism – the technique allowing formal calculations of many transport coefficients without the use of a kinetic equation. It supposes that a system is described by a Hamiltonian and that its equilibrium thermodynamic properties are determined by the equilibrium density matrix $\rho^{(0)}$. This system is now subject to an external influence described by $AF(t)$, where A is an arbitrary **operator** and F an arbitrary C-number function of time. The temporal behavior of the system is governed by the density matrix $\rho(t)$, which satisfies the **von Neumann equation** $i\hbar\partial\rho/\partial t = [H_t, \rho]$ with $H_t \equiv H + AF(t)$. So far everything is traditional and exact. The fundamental approximation made in calculating $\triangle\rho \equiv \rho(t) - \rho^{(0)}$ is to solve the von Neumann equation neglecting quadratic terms in either $\triangle\rho$ or A. This allows one to solve the equation for $\triangle\rho$ in that approximation. The average of a quantity B in this new time-dependent state $\rho_0 + \triangle\rho$ assumes a very elegant form

$$\langle B(t)\rangle = B_0 + Tr(B\triangle\rho) = B_0 + \int_0^\infty dt'\phi_{BA}(t-t')F(t'),$$

where B_0 is the equilibrium value of B and ϕ_{BA} is the response function

$$\phi_{BA}(\tau) = \frac{1}{i\hbar}Tr\rho^{(0)}\left[A, B(\tau)\right]$$

with

$$B(\tau) \equiv \exp\left(\frac{1}{i\hbar}H\tau\right)B\exp\left(-\frac{1}{i\hbar}B\tau\right).$$

This formalism is a characteristic of linear response. If an electric current caused by the electric field A and $F(t)$ varies like $\exp(\mathrm{i}\omega t)$, the above formulae yield, after considerable manipulation, the frequency-dependent conductivity tensor:

$$\sigma_{\mu\nu} = \frac{1}{k_B T} \int_0^\infty \mathrm{d}t \exp(\mathrm{i}\omega t) \left\langle j_\nu j_\mu(t) \right\rangle .$$

First described in: R. Kubo, *Statistical-mechanical theory of irreversible processes. I. General theory and simple applications to magnetic and conduction problems,* J. Phys. Soc. Japan **12**(6), 570–586 (1957).

Kubo oscillator – an oscillator with a random frequency.

Kuhn–Thomas–Reiche sum rule (or *f*-sum rule) states that for an atom whose electrons are undergoing all possible transitions from or to a given level (usually labeled level 2), if the f's are the corresponding oscillator strength, then $\sum_1 f_{21} + \sum_3 f_{23} = n$, where 1 indicates any level below 2, and 3 any level above 2, including the continuum, and n is the number of optical electrons. The absorption and emission oscillator strengths are related by $\omega_1 f_{12} = -\omega f_{21}$, where ω is the statistical weight.

First described in: W. Kuhn, *Über die Gesamtstärke der von einem Zustande ausgehenden Absorptionslinien,* Z. Phys. **33**(1), 408–410 (1925); W. Thomas, *Über die Zahl der Dispersionselektronen, die einem stationären Zustande zugeordnet sind (Vorläufige Mitteilung),* Naturwissen. **13**, 627 (1925); F. Reiche, W. Thomas, *Über die Zahl der Dispersionselektronen, die einem stationären Zustand zugeordnet sind,* Z. Phys. **34**(1), 510–525 (1925).

L

From lab-on-a-chip to Lyman series

lab-on-a-chip – a combination of fluidic elements, sensor(s), detection and signal processing units integrated on a chip in order to perform a complete sequence of chemical reactions or biomedical analysis. Sample preparation, appropriate reactions, separation of the products and their identification are usually realized by such a device.

Lagrange equation of motion has the form

$$\frac{\mathrm{d}}{\mathrm{d}t}\left(\frac{\partial \mathbf{L}}{\partial v_i}\right) - \frac{\partial \mathbf{L}}{\partial r_i} = 0, i = 1, 2, \ldots, n,$$

where **L** is the Lagrangian. Given a set of n independent generalized coordinates r_i and velocities v_i that describe the state of a conservative system (one in which all forces derive from some potential energy function U), so that $\mathbf{L} = \mathbf{L}(r_i, v_i, t)$.

First described in: J. Lagrange, *Mécanique Analytique* (1788).

Lagrangian function (or, shortly, Lagrangian) – the difference between the kinetic and potential energies of a particle or system. The function enables the equation of motion of classical mechanics and Hamilton's principle to be written in simple form. For systems involving relativistic velocities or in the preserve of a magnetic field the function may have a more complex form. See also **Lagrange equation of motion**.

lambda point – the temperature equal to 2.178 K at which the transformation between liquids **helium I** and **helium II** takes place.

Lambert law states that illumination of a surface by a light ray varies as the cosine of the angle of incidence between the normal to the surface and the incident ray.

First described in: J. H. Lambert, *Photometria* (Augsburg, 1760).

Lambert surface – an ideal perfectly diffusing surface for which the intensity of reflected radiation is independent of direction.

Lamb shift – a small shift in the energy levels of a hydrogen atom and of hydrogen-like ions from those predicted by the Dirac electron theory, in accord with principles of quantum electrodynamics.

First described in: W. E. Lamb Jr., R. C. Reserford, *Fine structure of the hydrogen atom by a microwave method*, Phys. Rev. **72**(3), 241–243 (1947).

Recognition: in 1955 W. E. Lamb received the Nobel Prize in Physics for his discoveries concerning the fine structure of the hydrogen spectrum.

See also www.nobel.se/physics/laureates/1955/index.html.

Landau damping – damping of an excitation in a system without collisions of the particles constituting this system when wave-particle interaction is involved.

First described in: L. D. Landau, *On the vibrations of the electronic plasma*, Zh. Eksp. Teor. Fiz., **16**, 574 (1946) – in Russian; J. Phys. USSR, **10**, 25 (1946).

Landauer–Büttiker formalism considers electron transport in low-dimensional structures in terms of transmitted and reflected electron waves. Within this point of view, the conductance is determined by the number of one-dimensional channels available for charge carriers injected from phase randomizing contacts and by the transmission properties of the structure for each channel. It can be illustrated by the schematic multi-terminal device shown in Figure L.1.

The device has i terminals, which connect it with reservoirs of electrons. Each of the reservoirs is characterized by some chemical potential μ_i. The net current in the i-th terminal is $I_i = (2e/h)[(1 - R_i)\mu_i - \sum_{i \neq j} T_{ij}\mu_j]$. It accounts for the fact that the current injected in the i-th terminal is reduced by the reflected back component, described by the reflection coefficient R_i, and by that transmitted from other reservoirs, described by the transmission coefficient T_{ij} representing the transmission probability from the j-th to the i-th reservoir. The factor 2 is included in order to represent electron spin degeneracy.

For a multi-mode regime of the i-th terminal, when there are N_i channels at the **Fermi energy**, the current has been obtained to be $I_i = (2e/h)[(N_i - R_i)\mu_i - \sum_{i \neq j} T_{ij}\mu_j]$. This is the **Landauer–Büttiker formula** for the conductance of a



Figure L.1 Multi-terminal low-dimensional structure illustrating the Landauer–Buttiker formalism.

device with many terminals. The reservoirs with electrons are assumed to feed all the channels equally up to the respective Fermi energy in the given terminal. Electrons reflected and transmitted in different m and n modes have to be accounted for by summation: $R_i = \sum_{mn}^{N_i} R_{i,mn}$, $T_{ij} = \sum_{mn}^{N_i} T_{ij,mn}$. Conservation of the current requires that this must be equal to the total current injected from terminal i that leaves the device through other terminals. This resulted in the sum rule for the reflection ant transmission coefficients: $R_i + \sum_{i \neq j} T_{ij,mn} = N_i$.

In many ways, the Landauer–Büttiker formula is the Ohm's law for low-dimensional structures. It is useful in explanation of a number of experimental observations in qualitative details. It works well in open structures where the picture of noninteracting electron waves is valid and interactions contribute only through finite dephasing times. In closed quantum dots, where charging energy is important, it usually does not hold except in special cases.

First described in: R. Landauer, *Spatial variation of currents and fields due to localized scatters in metallic conduction*, IBM J. Res. Dev. **1**(6), 223–231 (1957); M. Büttiker, *Four-terminal phase-coherent conductance*, Phys. Rev. Lett. **57**(14), 1761–1764 (1986).

More details in: S. Datta, *Electronic Transport in Mesoscopic Systems* (Cambridge University Press, Cambridge, 1995).

Landauer–Büttiker formula → **Landauer–Büttiker formalism**.

Landauer formula defines the resistance of single-mode one-dimensional conducting channel to be:

$$r = \left(\frac{h}{2e^2}\right) \frac{R}{1 - R},$$

where R is the reflection probability of electron waves.

First described in: R. Landauer, *Spatial variation of currents and fields due to localized scatters in metallic conduction*, IBM J. Res. Dev. **1**(6), 223–231 (1957).

Landau fluctuations – variations in the losses of energy of different particles in a thin detector resulting from random variations in the number of collisions and in the energies lost in each collision of the particle.

Landau levels – quantized orbits of free charge carriers in a crystal placed in a magnetic field.

Electrons moving in a perpendicular magnetic field B are forced onto circular orbits, following the **Lorentz force**. They perform a cyclotron motion with the angular frequency $\omega_c = eB/m$, called the **cyclotron frequency**, where m is the electron mass. So far, available energy levels for electrons become quantized. These quantized energies are Landau levels. They are given by $E_i = (i + 1/2)\hbar\omega_c$ with $i = 1, 2, \ldots$.

In an ideal perfect system containing a two-dimensional electron gas these levels have a form of a δ-function. The gap between nearest levels is determined by the cyclotron energy $\hbar\omega_c$. The levels are broadened by a temperature rise. Clearly one needs $k_B T \ll \hbar\omega_c$ to observe well-resolved Landau levels. Electrons can only reside at the energies of Landau levels, but not in the gap between them.

Landé equation gives the **g-factor** for free atoms in the form

$$g = 1 + \frac{J(J+1) + S(S+1) - L(L+1)}{2J(J+1)},$$

where J, S, L refer to the total, spin and orbital angular momentum quantum numbers, respectively.

First described in: A. Landé, *Über den anomalen Zeemaneffekt (Teil I)*, Z. Phys. **5**(4), 231–241 (1921); A. Landé, *Über den anomalen Zeemaneffekt (Teil II)*, Z. Phys. **7**(1), 398–405 (1921).

Landé *g*-factor determines the total magnetic moment M of an atom in spin–orbit coupling in the direction of the total mechanical moment via $M = -g_L(e/2mc)J$, where g_L is the Landé g-factor, m is the electron mass, and J is the resultant angular momentum. In fact, the Landé g-factor explicitly determines the splitting energy of each magnetic substance under a given magnetic field. See also **g-factor** and **Zeeman effect**.

First described in: A. Landé, *Über den anomalen Zeemaneffekt (Teil I)*, Z. Phys. **5**(4), 231–241 (1921); A. Landé, *Über den anomalen Zeemaneffekt (Teil II)*, Z. Phys. **7**(1), 398–405 (1921).

Landé interval rule states that when the spin-orbit interaction is weak enough to be treated as a perturbation, an energy level having definite spin angular momentum and orbital angular momentum is split into levels of differing total angular momentum, so that the interval between successive levels is proportional to the larger of their total angular momentum values.

First described in: A. Landé, *Termstruktur und Zeemaneffekt der Multipletts I*, Z. Phys. **15**(1), 189–205 (1923); A. Landé *Termstruktur und Zeemaneffekt der Multipletts II*, Z. Phys. **19**(1), 112–123 (1923).

Landé γ-permanence rule states that the sum of the energy shifts produced by the spin–orbit interaction, over the series of states having the same spin and orbital angular momentum quantum numbers (or the same total angular momentum quantum numbers for individual electrons) but different total angular momenta, and having the same total magnetic quantum number, is independent of the strength of an applied magnetic field.

Langevin–Debye formula gives the total polarizability of a substance per molecule in the form $\alpha = \alpha_0 + (p^2/3k_B T)$, where α_0 is the deformation polarizability being the sum of electronic and ionic contributions, and p is the dipole moment of the molecule. First described by P. Langevin in 1905 for magnetic susceptibility of a **paramagnetic** and in the final form by P. Debye in 1912.

First described in: P. Langevin, *Sur la theory du magnetism*, J. Phys. Radium, **4**, 678–693 (1905); P. Langevin, *Magnetism et theory des electrons*, Ann. Chim. Phys. **5**, 70 (1905); P. Debye, *Einige Resultate einer kinetischen Theorie der Isolatoren*, Phys. Z. **13**, 97 (1912).

Recognition: in 1936 P. Debye received the Nobel Prize in Chemistry for his contributions to our knowledge of molecular structure through his investigations on the dipole moments and on diffraction of X-rays and electrons in gases.

See also www.nobel.se/chemistry/laureates/1936/index.html.

Langevin function is $L(a) = \coth a - 1/a$. For $a \ll 1, L(a) = a/3$. It occurs in the expressions for the paramagnetic susceptibility of a classical collection of magnetic dipoles and for the polarizability of molecules having a permanent electric dipole moment.

Langmuir–Blodgett film – an organic film that is deposited onto a solid substrate when the substrate is dipped into a liquid, usually aqueous, that contains an organic film on the surface. The substrate adsorbs a layer of the film as it is lowered into the solution and a second layer as it is withdrawn. This technique of film deposition is called the **Langmuir–Blodgett method**. The organic molecules used for that contain two types of functional groups at their ends. One end has the hydrocarbon chain including an acid or alcohol group soluble in water. It makes this end **hydrophilic**, which means that it "likes" water. The other end contains insoluble hydrocarbon groups making it **hydrophobic**, which means that it is "afraid of" water. Such molecules, called amphiphilic, form a film on the water surface with the hydrophilic ends in the water side and the hydrophobic ends in the air side. This is a **Langmuir film**. A classical example of an amphiphile is stearic acid ($C_{17}H_{35}CO_2H$) where the long hydrocarbon tail ($C_{17}H_{35}$) is hydrophobic, and carboxyl acid head group ($-CO_2H$) is hydrophilic.

There can be three types of deposition of a Langmuir film onto a solid substrate, as illustrated in Figure L.2.



Figure L.2 Types of deposition of Langmuir–Blodgett films.

When a substrate is moved through the monolayer at the water/air interface, the monolayer can be transferred during immersion (dipping) or emersion (withdrawal). If the substrate surface is hydrophobic, a monolayer will be transferred in the immersion via interaction of the hydrophobic tails with the surface. On the other hand, if the substrate surface is hydrophilic, the monolayer will be transferred during withdrawal when hydrophilic head groups bond to the surface. Thus, a hydrophilic substrate appears to get a hydrophobic surface after the first immersion and withdrawal. The second monolayer will be transferred in the immersion. The immersion-withdrawal cycle can be repeated to add monolayers in a head to head, tail to tail configuration. This type of deposition is denoted as **Y-type**. This is the most usual mode of multilayer formation for amphiphilic molecules with a very hydrophilic head groups (like $-COOH$, $-PO_3H_2$) and where the tail is an alkyl chain. The deposited multilayer film is centrosymmetric.

When a hydrophobic surface, like clean silicon, is passed from air to water, the hydrophobic tails will stick to the surface. If now one moves the substrate to part of the bath where water is not covered by the foreign molecules and withdraws it there, a sequence of head to tail layers can be formed on the substrate. This is denoted as **X-type** deposition. The third possible deposition is **Z-type**, when the film composed of head to tail layers is formed only during withdrawal. Both X- and Z-types can be realized when the head group is not so hydrophilic (like $-COOMe$) or when the alkyl chain is terminated by a weak polar group (like $-NO_2$). In these cases, the interaction between adjacent monolayers is hydrophilic hydrophobic. Therefore the multilayers formed are less stable than those formed via Y-type deposition. X- and Z-deposited multilayer films are noncentrosymmetric.

A unique feature of Langmuir–Blodgett films is the ability to form a well-ordered structure on noncrystalline substrates.

First described in: K. B. Blodgett, *Films built by depositing successive monomolecular layers on a solid surface*, J. Am. Chem. Soc. **57**(6), 1007–1022 (1935); I. Langmuir, K. B. Blodgett, *Methods of investigation of monomolecular films*, Kolloid Z. **73**, 257–263 (1935).

More details in: A. Ulman, *An Introduction to Ultrathin Organic Films. From Langmuir–Blodgett to Self-Assembly* (Academic Press, Boston, 1991).

Langmuir–Blodgett method → **Langmuir–Blodgett film**.

Langmuir effect – ionization of atoms of low ionization potential that come into a contact with a hot metal with a high work function.

First described by I. Langmuir in 1924.

Recognition: in 1932 I. Langmuir received the Nobel Prize in Chemistry for his discoveries and investigations in surface chemistry.

See also www.nobel.se/chemistry/laureates/1932/index.html.

Langmuir film → **Langmuir–Blodgett film**.

lanthanides → **rare-earth elements**.

Laplace equation – the basic equation of potential theory:

$$\frac{\partial^2\phi}{\partial x^2}+\frac{\partial^2\phi}{\partial y^2}+\frac{\partial^2\phi}{\partial z^2}=0$$

or in terms of the **Laplace operator** ∇^2 it is $\nabla^2\phi = 0$. A function ϕ satisfying the Laplace equation is said to be harmonic.

First described in: P. S. Laplace, Mem. Acad. R. Sci. 249–267 (1787–1789).

Laplace operator (or, shortly, Laplacian) – the linear operator of the form

$$\nabla^2=\frac{\partial^2}{\partial x^2}+\frac{\partial^2}{\partial y^2}+\frac{\partial^2}{\partial z^2}=0.$$

Laplace transform for a function $f(x)$ defined for all real positive x is the function $L(f) = G$ defined by $L(f(s)) = G(s) = \int_0^\infty f(x)\exp(-\delta x)\mathrm{d}x$. If $f(x)$ is summable over every finite interval and there is a constant c such that $\int_0^\infty |f(x)|\exp(-\delta|x|)\mathrm{d}x$ exists, then the Laplace transform exists whenever δ is any complex number $s = s + \mathrm{i}t$, such that $s = c$. The Laplace transform is related to the Fourier transform by a simple change of variables: if $\delta = -\mathrm{i}\omega$, the Laplace transform $G(s) = (2\pi)/1/2F(\omega)$, where $F(\omega)$ is the Fourier transform of the function $f(x)$.

Laplacian = **Laplace operator.**

Laporte selection rule states that an electric dipole transition can occur only between states of opposite parity.

First described in: O. Laporte, G. Wentzel, *"Dashed" and displaced terms in spectra*, Z. Phys. **31**(1–4), 335–338 (1925); O. Laporte, W. F. Meggers, *Some rules of spectral structure*. J. Opt. Soc. Am. **11**(5), 459 (1925).

LAPW – an acronym for a **l**inearized **a**ugmented **p**lane **w**ave used in the **linearized augmented plane wave (LAPW)** method of calculation of electronic band structure of solids.

Larmor frequency → **Larmor theorem.**

Larmor theorem states that for an atom in a magnetic field H the motion of the electrons is, to the first order in H, the same as a possible motion in the absence of H except for the superposition of a common precession of angular frequency $\omega_L = -eH/(2mc)$, where m is the electron mass. This frequency of precession is called the **Larmor frequency**.

First described in: J. Larmor, *On the theory of the magnetic influence on spectra and on the radiation from moving ions*, Phil. Mag. **44**, 503–512 (1897).

laser – an acronym for a device producing **l**ight **a**mplification by **s**timulated **e**mission of **r**adiation. An operational principle of a laser, as well as of a **maser**, employs the **stimulated emission** of radiation in matter.

A laser consists of a gain medium inside an optical cavity, with a means to supply energy to the gain medium. The gain medium is a material (gas, liquid, solid or free electrons) with appropriate optical properties. An optical cavity in its simplest form consists of two mirrors arranged such that light bounces back and forth, each time passing through the gain medium. Typically, one of the two mirrors, the output coupler, is partially transparent in order to let the light go out of the device. The outgoing light is very intense and coherent (composed of one frequency). It can be easily focused.

laser ablation – instant evaporation of materials by an intense laser beam. As a technological tool it is used to evaporate complicated compounds from a target and deposit them onto a substrate. The composition of the target material is thus reproduced on the substrate.

latent heat – the amount of heat absorbed or evolved by 1 mole or a unit mass of a substance during a change of state, such as fusion, sublimation or vaporization, at constant pressure and temperature.

lateral force microscopy (LFM) – detection of the torsion of the scanning probe of **AFM** (lateral force) which is correlated to local frictional forces. It is an extension of a contact mode AFM, whereby an additional detected parameter is the torsion of the cantilever, which changes depending on the friction force. The LFM can provide material-sensitive contrast since different components of a composite material exert different friction forces on the scanning tip. The technique is also useful for obtaining edge-enhanced images.

Figure L.3 illustrates two sources of lateral deflections of the cantilever, these being changes in the surface friction and changes in the slope of surface structures. In the first case, the tip may experience greater friction as it traverses some areas, causing the cantilever to twist more strongly. In the second case, the cantilever may twist when it encounters a steep slope. To separate one effect from the other, LFM and AFM images should be collected simultaneously.



Figure L.3 Lateral deflection of the scanning cantilever as a result changes in surface friction and slope of the surface structures.

lattice (of a crystal) – a parallel net-like arrangement of points (atoms) with the special property that the environment about any particular point (atom) is in every way the same as that about any other point (atom) of the lattice.

Laue equations specify a set of conditions, which govern the diffraction of an X-ray beam by a crystal. They are also known as Laue conditions. These are illustrated in Figure L.4.

The point O is the origin of the unit cell in a crystal structure and A, B, C are equivalent points along the three axes OX, OY, OZ of the unit cell, so that $OA = a$, $OB = b$, $OC = c$, where a, b, c are the unit cell edges. Consider that a plane wave of monochromatic X-rays from a distant point P is falling on the assembly of points and let us deduce the conditions necessary to give a diffracted wave in the direction of Q. The direction cosines of OP are supposed to be $\alpha_1, \beta_1, \gamma_1$ and of $OQ - \alpha_2, \beta_2, \gamma_2$.



Figure L.4 Scheme of X-ray scattering by equivalent points of a crystal.

The rays with wavelength λ scattered from the points O and A, O and B, O and C will be in phase if $a(\alpha_1 - \alpha_2) = h\lambda$, $b(\beta_1 - \beta_2) = k\lambda$, $c(\gamma_1 - \gamma_2) = l\gamma$, where h, k, l are integers. These three equations are called the Laue equations and together constitute the conditions for a diffracted beam in the direction Q. In general, that is for any arbitrary set of incident direction cosines, all three will not be satisfied, since any direction of diffraction is completely specified by two of its direction cosines. This means that only for certain specified incident directions will any diffracted beam be formed when the incident X-rays are monochromatic.

The Laue conditions for reinforcement of the rays scattered from equivalent points of a crystal are identical with the **Bragg equation** governing X-ray diffraction by crystal planes.

First described in: W. Friedrich, P. Knipping, M. Laue, *Interferenzerscheinungen bei Röntgenstrahlen,* Sitzungsber. Bayer. Akad. Wiss. (Math. Phys. Klasse), **303** (1912).

Recognition: in 1914 M. von Laue received the Nobel Prize in Physics for his discovery of the diffraction of Röntgen rays by crystals.

See also www.nobel.se/physics/laureates/1914/index.html.

law of rational intercepts → **Miller law**.

law of the independent migration of ions → **Kohlrausch laws**.

First described in: F. Kohlrausch, *Über das Leistungvermögen einiger Electrolyte in äusserst verdünnter wässriger Lösung,* Ann. Phys. **26**, 161–225 (1885).

LCAO – an acronym for **linear combination of atomic orbitals**, which is a method of calculation of the electronic band structure of solids.

LDA – an acronym for a **local density approximation**, which is an approach used for calculation of the electronic band structure of solids.

LDA+U means **local density approximation** (LDA) with an orbital-dependent correction of the LDA potential. The main idea of the method is to separate electrons into two subsystems–localized d or f electrons for which the Coulomb d–d or f–f interactions should be taken into account in model **Hamiltonian** (through one-site Coulomb interaction U) and delocalized s and p electrons which could be described by using an orbital-independent one-electron potential (LDA). The orbital-dependent potential is written as $V_i(\mathbf{r}) = V_{LDA}(\mathbf{r}) + U(1/2 + n_i)$, where n_i indicates the occupation of the i-th orbital. The LDA + U may be regarded as a generalization of the **Hartree–Fock approximation** but with an orbital-dependent screened Coulomb interaction and, at least for localized states such as d–and f–orbitals of transition metal or rare-earth metal ions, the LDA + U theory may be regarded as an approximation to the **GWA**. This method is successfully used when describing the band gap of **Mott insulator**s such as transition metal and rare-earth compounds.

First described in: V. I. Anisimov, J. Zaanen, O. K. Andersen, *Band theory and Mott insulators: Hubbard U instead of Stoner I*, Phys. Rev. B **44**(3), 943–954 (1991).

LED – an acronym for a **light-emitting diode**.

LEED – an acronym for a **low-energy electron diffraction**.

Legendre polynomial has the form

$$L_n(x) = \frac{(2n)!}{n!^2 2^n}\left[x^n - \frac{n(n-1)}{2(2n-1)}x^{n-2} + \frac{n(n-1)(n-2)(n-3)}{2\cdot 4(2n-1)(2n-3)}x^{n-4}\ldots\right],$$

where n is its degree. The first Legendre polynomials are: $L_0(x) = 1$, $L_1(x) = x$, $L_2(x) = 1/2(3x^2 - 1)$, $L_3(x) = 1/2(5x^3 - 3x)$, $L_4(x) = 1/8(35x^4 - 30x^2 + 3)$.

First described in: A. M. Legendre, *Recherches sur la figure des planetes* (Paris 1784).

Lennard–Jones potential describes total potential energy of two atoms at separation r (originally proposed for liquid argon): $V(r) = \epsilon[(r_0/r)^{12} - 2(r_0/r)^6]$, where ϵ is the energy at the minimum of the potential energy well and r_0 is the intermolecular separation at this energy, which is in fact the equilibrium distance between atoms. The terms with $(1/r)^{12}$ and $(1/r)^6$ represent repulsive and attractive forces, respectively.

The parameter ϵ governs the strength of the interaction and r_0 defines a length scale. The interaction repels at close range, then attracts, and is eventually cut off at some critical separation. While the strongly repulsive core arising from the nonbonded overlap between the electron clouds has rather arbitrary form (and other powers and functional forms are sometimes used), the attractive tail actually represents the **van der Waals** interaction due to electron correlations. The interactions involve individual pairs of atoms. Each pair is treated independently. In practice, both ϵ and r_0 are considered as fitting parameters for a particular atomic system.

First described in: J. E. Lennard-Jones, *Cohesion*, Proc. Phys. Soc. 43, 461–482 (1931).

More details in: I. G. Kaplan, *Intermolecular Interactions: Physical Picture, Computational Methods and Model Potentials* (John Wiley & Sons, Chichester, 2006).

Lennard–Jones–Keesom potential = **Keesom potential**.

Lenz law states that when a flux of a magnetic field linking a closed electric circuit is changed, a current is induced in the circuit in such a direction as to produce a magnetic flux which opposes the changing magnetic field applied.

First described in: H. F. E. Lenz, Mem. Acad. Imp. Sci. (St. Petersbourg) **2**, 427 (1833); H. F. E. Lenz, *Über die Bestimmung der Richtung der durch elektrodynamische Vertheilung erregten Ströme*, Ann. Phys. **31**, 483–493 (1834).

Leonardo da Vinci law states that friction force between two bodies is independent of the area of their contact. See also **Amonton's law**.

LET – an acronym for a **light-emitting transistor**.

levitation – holding up an object with no visible support.

Lévy process – a random walk in space with infinite second moment of the jump size probability, or a random process with the first moment of the waiting time distribution between events being infinite.

First described in: P. Lévy, *Sur les integrales dont les elements sont des variables aléatoires indépendentes*, Ann. R. Scuola Norm. Super. Pisa, Sez. Fis. e Mat., Ser. **2**, 337–366 (1934), Ser. **4**, 217–218 (1935).

LFM – an acronym for a **lateral force microscopy**.

Lie algebra – the algebra of vector fields on a manifold with additive operation given by pointwise sum and multiplication by the **Lie brackets**.

First described by S. Lie in 1888. See also in S. Lie, F. Engel, *Theorie der Transformationsgruppen* (Teubner, Leipzig, 1888–1893).

More details in: B. Hall, *Lie Groups, Lie Algebras, and Representations* (Springer, Berlin, 2004).

Lie bracket – the vector field $\mathbf{Z} = \mathbf{XY} - \mathbf{YX}$ for given vectors **X** and **Y**.

Lie group – a topological group which is also a differentiable manifold in such a way that the group operations are themselves analytic functions.

lift-off process → **electron beam lithography**.

light-emitting diode (LED) – a semiconductor device that emits incoherent monochromatic light when electrically biased. Depending on the semiconductor used the color of the emitted light can be varied: yellow, orange, green, turquoise, blue-violet, and even white.

First described by: O. V. Losev for SiC in 1927 – principle possibility; N. Holonyak Jr, S. F. Bevaqua, *Coherent (visible) light emission from* $Ga(As_{1-x}P_x)$ *junctions*, Appl. Phys. Lett. **1**(1), 82–83 (1962) – device realization.

Recognition: Hailed as "the father of semiconductor light-emitter technology in the western world" Nick Holonyak Jr. received several awards; he is one of 13 Americans who have been awarded both the National Medal of Science (1990) and the National Medal of Technology (2002).

light-emitting silicon – Silicon, the most important elemental semiconductor, crystallizes in the **diamond structure** with a lattice constant of 0.5341 nm. Silicon has an indirect band gap of 1.12 eV in the infrared region, that is ideal for room temperature operation, and an oxide that allows the processing flexibility to place today more than 10^8 transistors on a single chip. The extreme integration levels reached by the silicon microelectronics industry have permitted high-speed performance and unprecedented interconnection levels. The present interconnection degree is sufficient to cause interconnect propagation delays, overheating and information latency between single devices. To overcome this bottleneck, **photonic integrated circuits** and photonic materials, in which light can be generated, guided, modulated, amplified and detected, need to be integrated with standard electronics circuits to combine the information processing capabilities of electronic data transfer and the speed of light. In particular, chip-to-chip or even intra-chip optical communications all require the development of efficient optical functions and their integration with state-of-art electronic functions. Silicon is the desired material, because silicon optoelectronics would open the door to faster data transfer and higher integration densities at very low cost. Silicon microphotonics has boomed these last years. Almost all the various photonic devices have been demonstrated, but the main limitation of silicon photonics remains the lack of any practical silicon-based light sources. Several attempts have been employed to engineer luminescing transitions in an otherwise indirect material. In particular, after the initial impulse given by the pioneering work on photoluminescence from **porous silicon** in 1990, nanostructured silicon has received extensive attention. This activity is mainly centered on the possibility of getting relevant optoelectronic properties from nanocrystalline Si. It is generally accepted that **quantum confinement** is essential for visible light emission in Si nanostructures. The optical gain observed in Si nanocrystals embedded in a SiO_2 matrix has given a further impulse to these studies.

More details in: S. Ossicini, L. Pavesi, F. Priolo, *Light Emitting Silicon for Microphotonics*, Springer Tracts on Modern Physics **194** (Springer-Verlag, Berlin, 2003); L. Pavesi, L. Dal Negro, C. Mazzoleni, G. Franzó, F. Priolo, Nature **408**, 440–446 (2000), L. Dal Negro, M. Cazzanelli, L. Pavesi, S. Ossicini, D. Pacifici, G. Franzó, F. Priolo, F. Iacona, *Dynamics of stimulated emission in silicon nanocrystals*, Appl. Phys. Lett. **82**, 4636–4638 (2003) – first observation of optical gain in silicon.

light-emitting transistor (LET) unlike conventional transistors, which include an electrical input port and an electrical output port, has also an infrared optical output port as illustrated in Figure L.5. This makes it possible to interconnect optical and electrical signals for display or communication purposes.

The LET can be made of indium gallium phosphide and gallium arsenide. Although it produces light essentially in the same way as a **light-emitting diode**, there is a possibility to modulate light at much higher speeds. While frequency modulation of about 1 MGz was demonstrated, higher speeds are theoretically possible.

First described in: M. Feng, N. Holonyak Jr., W. Hafez, *Light-emitting transistor: Light emission from InGaP/GaAs heterojunction bipolar transistors*, Appl. Phys. Lett. **84**(1), 151–153 (2004).



Figure L.5 Light-emitting transistor. The squiggly line in the figure represents an infrared photon emitted from the optical output port. After M. Feng, N. Holonyak Jr., W. Hafez, *Light-emitting transistor: Light emission from InGaP/GaAs heterojunction bipolar transistors*, Appl. Phys. Lett. **84**(1), 151–153 (2004).

Linde rule states that the increase in electrical resistivity of a monovalent metal produced by a substitutional impurity per atomic percent impurity is equal to

$a + b(v - 1)2$, where a and b are constants for a given solvent metal and a given row of the Periodic Table for the impurity and v is the valence of the impurity.

First described in: J. O. Linde, *Elektrische Eigenschaften verdünnter Mischkristalllegierungen. I. Goldlegierungen*, Ann. Phys. **10**, 52 (1931); J. O. Linde, *Elektrische Eigenschaften verdünnter Mischkristalllegierungen. III. Widerstand von Kupfer- und Goldlegierungen. Gesetzmässigkeiten der Widerstandserhöhungen*, Ann. Phys. **15**, 219–248 (1932).

Linear combination of atomic orbitals (LCAO) – a typical realization of the **tight-binding approach** for calculation of electronic band structures of solids. It is assumed that the atomic potential in the solid under consideration is so strong that electrons are essentially localized at their atoms and the wave functions for neighboring atomic sites have little overlap. Thus, the total wave function $\psi_k(\mathbf{r})$ and energy E for the solid are $\psi_k(\mathbf{r}) = \sum_n \exp(i\mathbf{k} \cdot \mathbf{r}_n)\phi(\mathbf{r} - \mathbf{r}_n)$ and $E = \int \psi_k^*(\mathbf{r})\mathbf{H}\psi_k(\mathbf{r})\mathrm{d}r / \int \psi_k^*(\mathbf{r})\psi_k(\mathbf{r})\mathrm{d}r$, where $\mathbf{r}_n$ is the radius vector to the n-th atom, is the single-electron wave function of the atom. The Hamiltonian for electrons of mass m: $\mathbf{H} = -\hbar^2/2m\nabla^2 + \sum_n V(\mathbf{r} - \mathbf{r}_n)$ includes the sum of single-atom potentials $V(\mathbf{r} - \mathbf{r}_n)$.

*More details in:*N. Peyghambarian, S. W. Koch, A. Mysyrowicz, *Introduction to Semiconductor Optics* (Prentice Hall, Englewood Cliffs, New Jersey, 1993), pp. 27–34.

linear Hanle effect → **Hanle effect**.

linearly polarized light → **polarization of light**.

linear muffin-tin orbital (LMTO) method – one of the most powerful methods for self-consistent electronic properties calculations of solids. Through the use of the **variational principle** for the **Schrödinger equation** with energy-independent basis functions, the secular equations become linear in energy, that is all eigenvalues and eigenvectors can be found simultaneously by diagonalization procedures. The trial basis functions are linear combinations of energy-independent **muffin-tin orbitals**.

The starting point is to approximate the full crystal potential with a muffin-tin potential that is spherically symmetric inside the radius r near the atomic sites and flat outside, in the interstitial region. In the atomic sphere approximation (LMTO-ASA) the radius r of the muffin-tin spheres equals the Wigner–Seitz radius. The spheres then overlap with each other and the interstitial region can be neglected. Moreover, in the ASA approximation the kinetic energy outside the spheres is chosen to be zero.

The LMTO method is particularly suited for close-packed structures. If the crystal is not close packed it is necessary to include the so-called empty spheres to reduce the overlap of muffin-tin spheres. The method combines desirable features of the **linear combination of atomic orbitals (LCAO)**, **Korringa–Kohn–Rostoker (KKR)** and cellular methods.

In the full-potential version of the LMTO (FP-LMTO) method the unit cell is divided into nonoverlapping muffin-tin spheres and the interstitial region. Inside the spheres the potential and electron densities are expanded in a way that no longer requires spherical symmetry. Differently from the **FLAPW** method, the FP-LMTO schemes use for the interstitial region localized functions derived from scattering theory (such as Hankel functions) instead of plane waves.

First described in: O. K. Andersen, *Linear methods in band theory*, Phys. Rev. B **12**(8), 3060–3083 (1975) – LMTO method; M. Methfessel, C. O. Rodriguez, O. K. Andersen, *Fast full-potential calculations with a converged basis of atom-centered linear muffin-tin orbitals: Structural and dynamic properties of silicon*, Phys. Rev. B **40**(3), 2009–2012 (1989) – FP-LMTO method.

More details in: H. L. Skriver, *The LMTO Method* (Springer-Verlag, Berlin, 1984).

linearized augmented plane wave (LAPW) method – one of the most accurate methods for calculations of electronic structure of solids. It is based on the **density functional theory** for the treatment of exchange and correlation effects.

The method is based on solving the **Kohn–Sham equations** for the ground state density, total energy, and eigenvalues of a many-electron system by introducing a basis set which is especially adapted to the problem. This adaptation is achieved by dividing the unit cell into 1. nonoverlapping atomic spheres (centered at the atomic sites) and 2. an interstitial region. In the two types of regions different basis sets are used:

1. Inside an atomic sphere a linear combination of radial functions times spherical harmonics $Y_{lm}(r)$ is used

$$\phi_{k_n} = \sum_{lm} \left[A_{lm} u_l(r, E_l) + B_{lm} \dot{u}_l(r, E_l) \right] Y_{lm}(\hat{r}),$$

   where $u_l(r, E_l)$ is the regular solution of the radial Schrödinger equation for energy E_l (chosen normally at the center of the corresponding band with l-like character) and the spherical part of the potential inside sphere t; $\dot{u}_l(r, E_l)$ is the energy derivative of u_l evaluated at the same energy E_l. A linear combination of these two functions constitutes the linearization of the radial function; the coefficients A_{lm} and B_{lm} are functions of k_n determined by requiring that this basis function matches each plane wave of the corresponding basis function of the interstitial region.
2. In the interstitial region a plane wave expansion is used $\phi_{k_n} = 1/\sqrt{\omega}\exp(\mathrm{i}k_n r)$, where $k_n = k + K_n$; K_n are the reciprocal lattice vectors and k is the wave vector inside the first Brillouin zone. Each plane wave is augmented by an atomic-like function in every atomic sphere. The solutions to the Kohn–Sham equations are expanded in this combined basis set of linearized augmented plane waves according to the linear variation method. In its general form the

LAPW method expands the potential in the following form:

$$V(\mathbf{r}) = \begin{cases} \sum_{lm} V_{lm}(\mathbf{r}) Y_{lm}(\hat{r}) & \text{inside the sphere} \\ \sum_{k} V_k \exp(\mathrm{i}\mathbf{Kr}) & \text{outside the sphere} \end{cases}$$

First described in: O. K. Andersen, *Linear methods in band theory*, Phys. Rev. B **12**(8), 3060–3083 (1975); D. D. Koelling, G. O. Arbman, *Use of energy derivative of the radial solution in an augmented plane wave method: application to copper*, J. Phys. F: Met. Phys. **5**(11), 2041–2054 (1975).

linewidth enhancement factor – the ratio between the carrier-induced variations of the real and imaginary parts of susceptibility:

$$\alpha = \frac{\partial\left[\mathrm{Re}\chi(n)\right]}{\partial n} \Big/ \frac{\partial\left[\mathrm{Im}\chi(n)\right]}{\partial n},$$

where the susceptibility $\chi(n)$ is a function of the carrier density n.

Liouville's equation → **Liouville's theorem in statistical mechanics**.

Liouville's theorem in statistical mechanics states that for a classical ensemble characterized by the distribution function $f(r_1, \ldots, r_n, p_1, \ldots, p_n)$ with generalized co-ordinates $r_1, \ldots, r_n$ and generalized momenta $p_1, \ldots, p_n$ in the defined phase space: $\mathrm{d}f/\mathrm{d}t = 0$. This is called **Liouville's equation**.

First described in: J. Liouville, *Mémoire sur la détermination des Intégrales dont la valeur est algébrique*, J. Ecole Polytechn. **14**(22), 124–193 (1833); J. Liouville, *Mèmoire sur les transcendantes elliptiques de première et de seconde espéce considérés comme fonctions de leur amplitude*, J. Ecole Polytechn. **14**(23), 37–83 (1834).

lipids – fatty acids and their derivatives. They constitute a class of relatively water-insoluble organic molecules, which are basic components of biological membranes.

Lipids consist of a polar or **hydrophilic** (attracted to water) head and one to three nonpolar or **hydrophobic** (repelled by water) tails. Since lipids have both functions, they are called amphiphilic. The hydrophobic tail consists of one or two (in triglycerides, three) fatty acids. These are unbranched chains of carbon atoms (with the correct number of H atoms), which are connected by single bonds alone (saturated fatty acids) or by both single and double bonds (unsaturated fatty acids). The chains are usually 14–24 carbon groups long.

Three groups of lipids are distinguished in biological membranes according to the composition of the hydrophilic head they have: (i) **glycolipids**, whose heads contain an oligosaccharide with 1–15 saccharide (sugar) residues; (ii) **phospholipids**, whose heads contain a positively charged group that is linked to the tail by a negatively charged phosphate group; (iii) **sterols**, whose heads contain a planar steroid ring, for example, cholesterol (only in animals).

In an aqueous environment, the heads of lipids are turned toward the environment and the tails are turned toward a hydrophobic region of another molecule. Driven by hydrophilic and hydrophobic forces, the nonpolar tails of lipids tend to cluster together, forming a lipid bilayer or a **micelle**, as schematically shown in Figure L.6. The polar heads face the aqueous environment. Micelles are spheres and can only reach a certain size, whereas bilayers have no limit to their extension. They can also form tubules.



Figure L.6 Self-organized lipid structures.

Lippmann effect – a change in surface tension that results from a potential difference across the interface between two immiscible conductors.

First described in: G. Lippmann, *Relations entre les phénomènes électriques et capillaires*, Ann. Chim. Phys. **5**, 494 (1875).

Lippmann–Schwinger equation describes scattering of nonrelativistic particles in the form $\mathbf{T} = \mathbf{V} + \mathbf{VGV}$, where $\mathbf{T}$ is the scattering operator, $\mathbf{V}$ is the scattering potential, and $\mathbf{G}$ is the full Green function of the system. It is appropriate to simulate scattering of one or two particles.

First described in: B. A. Lippmann, J. Schwinger, *Variational principles for scattering processes*, Phys. Rev. **79**(3), 469–480 (1950).

liquid crystal – a class of molecules that, under some conditions, inhabit a phase in which they exhibit isotropic, fluid they like behavior characterized by little long-range ordering. In other conditions they demonstrate one or more phases with significant anisotropic structure and long-range ordering, but still with an ability to flow. Liquid crystals find wide use in displays which rely on the change in the optical properties of certain liquid crystalline molecules in the presence or absence of an electric field. In the presence of an electric field, these molecules align with it, altering the polarization of the light in a certain way. The ordering of liquid-crystalline phases is extensive on the molecular scale, but does not extend to the macroscopic scale as might be found in classical crystalline solids. The ordering in a liquid crystal might extend along one dimension, but along another dimension might have significant disorder. Important types of liquid crystals include: the nematic phase (most nematics are uniaxial but biaxial ones are also known), the cholesteric phase, the smectic phase (smectic A, smectic C and hexatic), and columnar phases.

First described in F. Reinitzer, *Beiträge zur Kenntnis des Cholesterins,* Monatsh. Chem. **9**, 421 (1888).

Recognition: in 1991 P.-G. De Gennes received the Nobel Prize in Physics for discovering that methods developed for studying order phenomena in simple systems can be generalized to more complex forms of matter, in particular to liquid crystals and polymers.

See also www.nobel.se/physics/laureates/1991/index.html.

liquid-phase epitaxy – an epitaxial deposition of thin solid films of a material transported from the liquid phase, typically from the melt, onto a suitable solid substrate. The melt actually contains the deposited material in its original composition or in atomic components. The epitaxial deposition is performed in a heated pencil box like the arrangement schematically shown in Figure L.7.

Graphite is an appropriate material for such a pencil box. The upper sliding part of the box contains voids filled with different melted solutes. A solute is composed so as to have a melting point far below the melting point of the substrate material. For instance, for liquid-phase epitaxy of $A^{III}B^{V}$ semiconductors, a group III metal (usually Ga or In) is used as a solvent for group V elements and dopants. When a particular melt contacts the substrate, the dissolved material condenses at the substrate surface.

The advantage of liquid-phase epitaxy is that the required equipment is very cheap, and easy to set up and operate. Meanwhile, it is difficult to achieve the level of control over the epitaxial growth conditions and impurity pollution of the deposited film.



Figure L.7 A setup for liquid-phase epitaxy.

lithography – a process of pattern formation. For more details for electronics → **electron-beam lithography, optical lithography**.

LMTO method = **linear muffin-tin orbital (LMTO) method.**

local density approximation (LDA) expresses the potential at a given location of an electron as a function of the the electron density at the same site. The function is determined by use of the knowledge of the total energy of the jellium model in which the nuclear charges are smeared out and uniformly distributed in the whole space.

The approximation is used to describe the exchange potential. This treats the inhomogeneous electron case as uniform locally, and for the exchange-correlation energy it gives $E_{xc} = \int n(\mathbf{r}\epsilon_{xc}(n(\mathbf{r})))d\mathbf{r}$, where ϵ_{xc} is the exchange-correlation energy per electron for a uniform electron gas of density n.

First described in: W. Kohn, L. J. Sham, *Self-consistent equation including exchange and correlation effects*, Phys. Rev. **140**(4A), A1133–A1138 (1965).

localized state – a quantum mechanical state of a single electron in a strongly random potential that is localized in space so that the state amplitude is concentrated near a single point in the sample.

local spin–density approximation (LSDA) is used to describe the exchange potential accounting for the electron spin

$$E_{\text{xc}} = \int n(\mathbf{r})\epsilon_{\text{xc}}(n_{\uparrow}(\mathbf{r}), n_{\downarrow}(\mathbf{r})d\mathbf{r}),$$

where $\epsilon_{\text{xc}}(n_{\uparrow}(\mathbf{r}), n_{\downarrow}(\mathbf{r}))$ is the exchange and correlation energy per particle of a homogeneous spin-polarized electron gas with spin-up and spin-down densities.

logic gate – a device implementing a **logic operator** of **Boolean algebra**. Any logic gate realizing a particular logic operation has a specific form in drawings. Figure L.8 presents a convention for the basic logic gates. In the same way as the basic operators of the **Boolean algebra** make up more complicated expressions, the basic gates are combined to construct complex circuits. Note that additional gates that duplicate the input values on wires are frequently needed. These are called FANOUT or COPY gates. In classical computation, these are obvious gates, for they simply correspond to splitting the wire into two or more leads, which is an easy operation.

See also **quantum logic gate**.

More details in: A. Galindo, M. A. Martin-Delgado, *Information and computation: Classical and quantum aspects*, Rev. Mod. Phys. **74**(2), 347–423 (2002).



Figure L.8 Schematic presentations of logic gates.

Table L.1 Truth table for the unary logic operator **NOT**.

x	**NOT**x
0	1
1	0

Table L.2 Truth table for the binary logic operators **AND**, **OR**.

x	y	x**AND**y	x**OR**y
0	0	0	0
0	1	0	1
1	0	0	1
1	1	1	1

Table L.3 Truth table for the binary logic operators **NAND**, **NOR** and **XOR**.

x	y	x**NAND**y	x**NOR**y	x**XOR**y
0	0	1	1	1
0	1	1	0	1
1	0	1	0	1
1	1	0	0	0

logic operator (function) supposes an operation with logic variables. A logic operator or function f is an application $f : \{0,1\}^n \longmapsto \{0,1\}^m$ which maps an input of n-bit-valued operands into an m-bit-valued output. When the target space of f is $\{0,1\}$, one usually says that f is a **Boolean** operator or function.

An operator with one operand is called a unary operator, with two operands is a binary operator. There are three basic Boolean or logic operators: (1) The unary operator **NOT**: $\textbf{NOT}x = \overline{x} = 1 - x$, also denoted by overlining the argument; (2) the binary operator **AND**: $x\textbf{AND}y = x \wedge y = xy$, also denoted by the symbol $\wedge$; and (3) the binary operator **OR**: $x\textbf{OR}y = x \vee y = x + y - xy$, denoted also by the symbol $\vee$. The action of a logic operator is represented by a truth table. A **truth table** contains as many columns as input operands and output **bits**, and $2^{\sharp\text{operands}}$ rows. The inputs are shown on the left, and the outputs are shown on the right. The truth tables for the basic operators are shown above.

With the basic set comprising **NOT**, **AND**, **OR** operators one can build any logic function, so that it is considered as a universal set. Moreover, the application of the **NOT** operation to **AND** and **OR** ones gives another universal set including **NAND** and **NOR** operators.

London equations determine the relation between a supercurrent $\mathbf{I}_s$, which is the electrical current in a superconductor, and magnetic **H** and electrical **E** fields applied in the form:

$$\Lambda\nabla\times\mathbf{I}_s=-\frac{1}{c}\mathbf{H},\qquad \Lambda\frac{\partial}{\partial t}\mathbf{I}_s=\mathbf{E}.$$

Here Λ is a constant characteristic of the superconductor but temperature dependent. The equations were shown to have local validity as they relate to the supercurrent at a given point in the superconductor.

First described in: F. London, H. London, *The electromagnetic equations of the superconductor*, Proc. R. Soc. A **149**(866), 71–88 (1935).

longitudinal acoustic mode → **phonon**.

longitudinal optical mode → **phonon**.

Lorentz force – the force acting on an electron moving in a magnetic field perpendicular to the trajectory of the electron. It is $e(\mathbf{v}\times\mathbf{B})$, where e is the electron charge, **v** is the electron velocity, **B** is the induction of the magnetic field (note that **v** and **B** are vectors).

First described in: H. A. Lorentz, *Versuch einer Theorie der electrischen und optischen Erscheinungen in bewegten Körpern*, (Leiden, 1895), H. A. Lorentz, *Simplified theory of electrical and optical phenomena in moving systems*, Konik. Akad. Wetensch. Amsterdam, **1**, 427–442 (1899).

Lorentz frame – any of the family of inertial coordinate systems with three space coordinates and one time coordinate used in the special theory of relativity. Each frame is in uniform motion with respect to all the other Lorentz frames and the interval between any two events is the same in all frames.

Lorentz gauge – the condition determining the relation between the scalar potential ϕ and vector potential **A** of an electromagnetic field. It is

$$\nabla\mathbf{A}+\frac{1}{c}\frac{\partial\phi}{\partial t}=0.$$

Lorentzian – a frequency-dependent function presented in the form:

$$A(\Gamma/2)^2/[(\nu-\nu_0)+(\Gamma/2)^2],$$

where A is an overall strength, G is the full width at half maximum, ν is the frequency, and ν_0 is a center frequency.

Lorentz rule defines the relationship between interspecies distances in a mixture composed of like (l_{ii}, l_{jj}) and unlike (l_{ij}) species in the form $l_{ij}=(l_{ii}+l_{jj})/2$.

Lorentz invariance – the property possessed by the laws of physics and of certain physical quantities of being the same in any **Lorentz frame** and thus unchanged by a **Lorentz transformation**.

Lorentz transformation – a group operation that is used to transform the space and time coordinates of one inertial reference frame, say S, into those of another one, S', with S' travelling at a relative speed u to S. If an event has space-time coordinates of (x, y, z, t) in S and (x', y', z', t') in S', then these are related according to $x = \gamma(x - ut), y' = y, z' = z, t' = \gamma(t - ux/c^2)$, where $\gamma = (1 - u^2/c^2)^{-1/2}$. These equations only work if u is pointed along the x-axis of S. In other cases, it is generally easier to perform a rotation so that u does point along the x-axis. Moreover, the position of the origins must coincide at 0. What this means is that (0,0,0,0) in frame S must be the same as (0,0,0,0) in S'. The transformation forms the basis for the special theory of relativity. The speed of light is the same in all reference frames here.

First described in: H. A. Lorentz, *Electromagnetic phenomena in system moving with velocity less than that of light*, Konik. Akad. Wetensch. Amsterdam **12**, 986–1009 (1904).

Lorenz number → **Wiedemann–Franz–Lorenz law**.

Lorenz relation gives a relationship between the magnetic vector potential **A** and scalar potential ϕ in the form $\nabla \cdot A + \epsilon_0\mu_0\partial\phi/\partial t = 0$ (in MKS), $\nabla \cdot A + (1/c)\partial\phi/\partial t = 0$ (in cgs).

First described in: L. Lorenz, *On the identity of the vibrations of light with electrical currents*, Phil. Mag. **34**, 287–301 (1867).

low-energy electron diffraction (LEED) – the coherent reflection of electrons in the energy range 5–500 eV from the uppermost few atomic layers of crystalline solids. Diffraction occurs because the electron wavelength λ (in nanometers) is related to the accelerating voltage V (in Volts) via $\lambda = 1.22638/V^{1/2}$, providing that λ in the low energy range is of the order of interatomic distances in solids.

LEED measurements are schematically illustrated in Figure L.9.



Figure L.9 Principle of the arrangement for low-energy electron diffraction.

Electrons from an electron gun diffract off the sample and head back toward the electron gun and the grids surrounding it. The two middle grids are set at an energy slightly less than the electron beam to prevent any inelastically scattered electrons from reaching the screen. The screen is biased positive between 0 and 7 keV accelerating the electrons towards it. The screen is coated in phosphor which glows green when electrons hit it. The resulting pattern is viewed from the rear end of the apparatus. It is one of experimental techniques for determination of atomic geometries of crystalline surfaces and ordered overlays thereon.

First described in: C. J. Davisson, C. H. Kunsman, *The scattering of low-speed electrons by platinum and magnesium*, Phys. Rev. *22*(1), 242–258 (1923); G. P. Thomson, A. Reid, *Diffraction of a cathode ray by a thin film*, Nature **119**, 890 (1927).

Recognition: in 1937 C. J. Davisson and G. P. Thomson received the Nobel Prize in Physics for their experimental discovery of the diffraction of electrons by crystals.

See also www.nobel.se/physics/laureates/1937/index.html.

luminescence – a process where a system in an excited state emits photons in order to relax to a lower energy state. It consists of three separate steps: (i) *excitation* of the medium providing electrons and holes to be excited by an external source of energy, (ii) *thermalization* of the excited electrons and holes resulting in their energy relaxation towards quasi thermal equilibrium, (iii) *recombination* of electrons with holes via radiative mechanisms resulting in the light emission. According to the excitation mechanism the luminescence processes are distinguished as **photoluminescence** (excited by light), **electroluminescence** (excited by electrical injection of electrons and/or holes), **thermoluminescence** (excited by heating), **cathodoluminescence** (excited by electron irradiation), **sonoluminescence** (excited by sound waves), and **chemiluminescence** (excited by chemical reactions).

luminophor – a luminescent material that converts part of the primary absorbed energy into emitted luminescent radiation.

LUMO – an acronym for a **l**owest **u**noccupied **m**olecular **o**rbital.

Luttinger liquid – a universality class of liquids characterized by the following relation between spectral properties and correlation exponents of the **Luttinger model**: $v_j v_n / v_s^2 = 1$, where v_j, v_n and v_s are three distinct parameters, all with dimension of velocity. The parameter v_s is related to the variation of the total energy of the system with the total momentum ($v_s = \delta E / \delta P$). The parameter v_j is related to the variation of the energy with the shift of all the particles in the space of momentum. It is the renormalized Fermi velocity. Finally v_n relates to changes in chemical potential to those in the Fermi vector k_F: $\delta\mu = v_n \delta k_f$. Thus, the only parameter that determines the low-energy properties of the system is the ratio $\exp(-2\phi) = v_n / v_s = v_s / v_j$.

It is used for interacting quantum systems in one dimension that have many distinctive features not present in higher dimensions. In particular, gapless (metallic) one-dimensional systems of interacting fermions does not behave as a normal **Fermi liquid**. Luttinger liquids are low-energy collective excitations of the entire electron system in which electrons move in concert.

Lattice models identified as Luttinger liquids include the one-dimensional **Hubbard model** and variants such as the $t - J$ model or the extended Hubbard model. Moreover, one-dimensional electron-phonon systems, metals with impurities and edge states in the **quantum Hall effect** can be Luttinger liquids.

First described in: F. D. M. Haldane, *General relation of correlation exponents and spectral properties of one- dimensional Fermi systems: application to the anisotropic $S = 1/2$ Heisenberg chain*, Phys. Rev. Lett. **45**(16), 1358–1362 (1980).

More details in: J. Voit, One-dimensional Fermi liquids, Rep. Prog. Phys. **58**(9), 977–1116 (1995).

Luttinger model accounts for the fact that one-dimensional spin 0 **fermion** systems show the remarkable phenomenon of the anomaly of the ground state, that is a ground state with a density of states which does not have a discontinuity at the Fermi momentum, but its graph becomes vertical (Fermi surface anomaly). A scheme was introduced by Tomonaga to illustrate this theory, via an exactly soluble model for the low-energy properties of these quantum systems. The model contains fairly realistic interaction between pairs of fermions. The **Hamiltonian** is given by:

$$H = \int_{-L/2}^{L/2} \mathrm{d}x \sum_{\omega=\pm} \psi^{+}_{\omega,x} v_F (\mathrm{i}\omega\delta_x - p_F) \psi^{-}_{\omega,x}$$

$$+\lambda \int_{-L/2}^{L/2} \mathrm{d}x\mathrm{d}y \psi^{+}_{+,x} \psi^{-}_{+,x} \psi^{+}_{-,y} \psi^{-}_{-,y} v(x-y),$$

where λ is a coupling constant, $v(x-y)$ is a smooth short-range pair potential, and v_F is the velocity at the Fermi surface. $\psi^{a}_{\omega,x}$ are fields where $a = \pm$ specifies the creation and annihilation operators for fermions located at a point x in the interval $[-L/2, L/2]$ and distinguished by $\omega = +$ or $\omega = -$. The calculated momentum distribution in the ground state shows no discontinuity at the Fermi surface and possesses an infinite slope at the Fermi surface.

First described in: S. Tomonaga, *Remarks on Bloch's method of sound waves applied to many fermion problems,* Prog. Theor. Phys. **5**, 544–569 (1950); J. M. Luttinger, *An exactly soluble model of a many-fermion system,* J. Math. Phys. **4**(9), 1154–1162 (1963).

Historical note: The exact solution of Luttinger was not really correct because of an error in the canonical commutation relations which, in infinitely many degrees of freedom systems, do not have a unique representation. The exact solution was obtained in: D. Mattis, E. Lieb, *Exact solution of a many-fermion system and its associated boson field,* J. Math. Phys. **6**, 304–310 (1965). The real value of the anomaly and Luttinger's result agree to the second order in λ, but differ in higher orders.

More details in: G. Gallavotti, *The Luttinger model: in the RG-theory of the one-dimensional many-body Fermi system,* J. Statist. Phys. **103** (2), 459–483 (2001).

Luttinger theorem states that the **Fermi surface** in a momentum space, which separates unoccupied **quasiparticle** states from the occupied ones, must enclose the same volume as the Fermi surface of the independent electrons.

Lyddane–Sachs–Teller relation → **phonon**.

First described in: R. H. Lyddane, R. G. Sachs, E. Teller, *On the polar vibrations of alkali halides,* Phys. Rev. **59**(8), 673–676 (1941).

Lyman series → **Rydberg formula**.

First described in: Th. Lyman, *The spectrum of hydrogen in the region of extremely short wave lengths,* Astrophys. Jour. **23**, 181–210 (1904); Th. Lyman, *An extension of the spectrum in the extreme ultra-violet,* Nature **93**, 241 (1914).

M

From Mach–Zender interferometer to Murrell–Mottram potential

Mach–Zehnder interferometer – an optical device used to determine the phase shift caused by a small sample which is placed in the path of one of two collimated light beams from a coherent light source. It is schematically shown in Figure M.1 in the calibration mode when no sample is placed in the interferometer.

Adding up all the contributions for the two undisturbed paths, one can see that they are the same. Thus light entering detector 1 via the two paths is in phase. As a result there is a constructive interference for the light entering detector 1. Doing the same analysis for the light coming to detector 2 one sees that the light goes through one additional phase change of one-half a wavelength. Therefore, there will be complete destructive interference, and no light will reach detector 2. Thus, regardless of the wavelength of the light, it all goes to the detector 1 if no sample is placed in the way of the light. But if it is, the phase shift caused by the sample alters the phase relationships between the two beams. There is no longer complete destructive interference at detector 2. Measuring the relative amount of light entering detectors 1 and 2 allows a calculation of the phase shift produced by the sample.

First described in: L. Zehnder, *Ein neuer Interferenzrefraktor*, Z. Instrumentenkunde **11**, 275–285 (1891); L. Mach, *Über einen Interferenzrefraktor*, Z. Instrumentenkunde **12**, 89–93 (1892).



Figure M.1 A Mach–Zehnder interferometer.

macroscopic long-range quantum interference → **Josephson effect**.

Madelung constant arises when one expresses the energy per mole of a crystal, for two atom crystals, due to the Coulomb interaction in the form $E = \alpha N(q^{+} + q^{-})/d$, where α is the Madelung constant, N is the Avogadro number, q^{+} and q^{-} are the charges of positive and negative ions respectively, and d is the nearest-neighbor distance. The constant is dimensionless, of the order of 1, depends only upon the type of crystal structure and is independent of the lattice dimensions.

First described in: E. Madelung, *Molekulare Eigenschwingungen*, Gesell. Wiss. Göttingen, Nachr., Math.-Phys. Klasse **1**, 43–58 (1910); E. Madelung, *Das elektrische Feld in Systemen von regelmässig angeordneten Punktladungen*, Phys. Z. **19**, 524–532 (1918).

Madelung energy – electrostatic energy per ion pair

$$E = \frac{1}{2N_p} \sum_{i,j} \frac{(\pm)e^2}{r_{ij}},$$

for $i \neq j$, where N_p is the number of ion pairs.

First described in: E. Madelung, *Das elektrische Feld in Systemen von regelmässig angeordneten Punktladungen*, Phys. Z. **19**, 524–532 (1918).

Maggi–Righi–Leduc effect – a change in the thermal conductivity of a conductor when it is placed in a magnetic field.

First described in: G. A. Maggi, Arch. de Genève **14**, 132 (1859); A. Righi, Mem. Acc. Lincei **4**, 433 (1887); M. A. Leduc, J. Phys. 2e série **6**, 378 (1887).

magnetic force microscopy – a scanning probe technique for mapping magnetic field on a micro- and nanometer scale. The technique is an offspring of **atomic force microscopy (AFM)**. It is based on the use of a magnetized tip. The technique has been developed for micromagnetic stray field imaging by using a fine magnetic probe based on the magnetic balance and AFM. Its main features are (1) to detect a very small magnetic force (10^{-13} N) or its force gradient (around 10^{-4} N/m) by using the small magnetic probe, which acts strongly on the stray field from a sample surface (magnetic domain) in a near-field range, and (2) to obtain the distribution image of the stray field magnetic domain.

The images are obtained by measuring the interaction force between the magnetic tip and the magnetic sample. The field gradient is mapped as a variation of the force on the tip, as the tip is scanned in a raster pattern, at a constant height over the sample. Since magnetic interactions are long-range, they can be separated from the topography by scanning at a certain constant height (typically around 20 nm) above the surface, where the z component of the sample stray field is probed. Therefore, any magnetic force microscope is always operated in a noncontact mode. The signal from the cantilever is directly recorded while the z feedback is switched off. A static or dynamic mode can be employed. A lateral resolution below 50 nm can be routinely achieved.

First described in: Y. Martin, H. K. Wickramasinghe, *Magnetic imaging by "force microscopy" with 1000 Å resolution*, Appl. Phys. Lett. **50**(20), 1455–1457 (1987); J. J. Sáenz, N. García, P. Grütter, E. Mayer, H. Heinzelmann, R. Wiesendanger, L. Rosenthaler, H. R. Hidber, H. J. Güntherodt, *Observation of magnetic forces by the atomic force microscope*, J. Appl. Phys. **62**(10), 4293–4295 (1987).

More details in: D. Rugar, H. J. Mamin, P. Guenthner, S. E. Lambert, J. E. Stern, I. McFadyen, T. Yogi, *Magnetic force microscopy: General principles and application to longitudinal recording media*, J. Appl. Phys. **68**(3), 1169–1183 (1990); *Roadmap of Scanning Probe Microscopy*, edited by S. Morita (Springer Verlag, Berlin Heidelberg, 2007).

magnetic groups = **Shubnikov groups**.

magnetism – a set of phenomena representing a response of matter to an external magnetic field. Magnetic states of materials are primarily distinguished according to the sign, magnitude and temperature dependence of the magnetic susceptibility defined as $\chi = M/H$, where M is the induced magnetization and H is the applied magnetic field. The four basic magnetic states of matter are diamagnetism, paramagnetism, ferromagnetism, and antiferromagnetism. They are listed in the Table M.1 with their main characteristics.

The ferrimagnetic state, which is not represented in the Table M.1, is, except in detail, similar to the antiferromagnetic state. Below the **Curie point** or **Neél point**, the ferromagnetic, ferrimagnetic, and antiferromagnetic materials have an ordered arrangement of the magnetic moments associated with each atom, schematically shown in Figure M.2.

At temperatures above the Curie point or Neél point, these materials exhibit paramagnetic behavior.

Recognition: in 1970 L. Neél received the Nobel Prize in Physics for fundamental work and discoveries concerning antiferromagnetism and ferrimagnetism which have led to important applications in solid-state physics.

See also www.nobel.se/physics/laureates/1970/index.html.

Table M.1 Classification of materials according to their magnetic susceptibility.

χ → **State ↓**	**Sign**	**Magnitude**	**Temperature dependence**
diamagnetic	–	small	$\chi \neq f(T)$
paramagnetic	+	small to medium	$\chi \neq f(T)$
		large	$\chi = const/T$
ferromagnetic	+	large	for $T < T_C$* – complex
			for $T > T_C$ $\chi = const/(T - T_C)$
antiferromagnetic	+	small	for $T > T_C$ $\chi = const/(T + const)$

* T_C is the **Curie point** or **Neél point** for an antiferromagnetic.



Figure M.2 Arrangement of magnetic moments in different magnetic materials below the Curie temperature.

magnetooptical Kerr effect (MOKE) → **Kerr effects**.

magnetoresistance – the electrical resistance of a material or structure measured in the presence of a magnetic field. The size of the magnetoresistance effect is expressed as a percentage, $\Delta R/R_0$, where ΔR is the change in the resistance, and R_0 is usually the resistance at zero magnetic field. Positive magnetoresistance refers to an increase in resistance when the magnetic field is applied, while negative magnetoresistance is a decrease in resistance.

First described in: W. Thomson (Lord Kelvin), *On the electro-dynamic qualities of metals: effects of magnetization on the electric conductivity of nickel and of iron*, Proc. R. Soc. Lond. **8**, 546–550 (1856).

magnetostriction effect – a change in linear dimensions of a ferromagnetic appearing when an external magnetic field is applied in a specified direction.

First described in: J. P. Joule, Sturgeon's Ann. Electricity **8**, 219 (1842).

magnetotactic bacteria – a class of bacteria that exhibit the peculiar ability to orient themselves along the magnetic field lines of Earth's magnetic field. They contain linear arrays of **antiferromagnetic** nanocrystals of Fe_3O_4, known as magnetite, or Fe_3S_4, known as greigite. The arrays are oriented parallel to the long direction of bacteria. *Magnetospirillum magnetotacticum* is an example of magnetotactic bacterium.

First described in: S. Bellini, *Su di un particolare comportamento di batteri d'acqua dolce*, Instituto di Microbiologia dell'Universitá di Pavia (1963) – first obseravtion; R. Blakemore, *Magnetotactic bacteria*, Science **190**, 377–379 (1975)–rediscovering and birth of the term magnetotactic.

magnetotaxis – specific orientation of bacteria and their navigation along a magnetic field. The microorganisms with such properties are called **magnetotactic bacteria**.

First described in: R. P. Blakemore, *Magnetotactic bacteria*, Science **190**, 377–379 (1975).

magnon – the unit of energy of a spin wave.

Mahan effect (MND effect) – a dynamical response of the Fermi sea to the core hole in a band-to-band optical absorption by **degenerate semiconductors**. **Exciton** states, arising from the electron–hole Coulomb attraction, are considered to affect the optical absorption. The calculations show that exciton states cause a logarithmic **singularity** in the absorption at the Burstein edge. This singularity is present at a moderate density of electrons or holes in the degenerate band, but it gradually disappears in the high-density limit. Lifetime broadening could make the logarithmic singularity difficult to observe at higher densities.

First described in: J. D. Mahan, *Excitons in degenerate semiconductors*, Phys. Rev. **153**(3), 882–889 (1967); P. Noziéres, C. T. De Dominicis, *Singularities in the X-ray absorption and emission of metals. III. One-body theory exact solution*, Phys. Rev. **178**(3), 1097–1107 (1969) – more complete theory.

More details in: J. D. Mahan, *Many-Particle Physics*, 2nd edition (Plenum, New York, 1990).

majorization – the mathematical procedure involving two real m-dimensional vectors $\mathbf{x} = (x_1, \ldots, x_m)$ and $\mathbf{y} = (y_1, \ldots, y_m)$. The vector $\mathbf{x}$ is majorized by $\mathbf{y}$ (equivalently $\mathbf{y}$ majorizes $\mathbf{x}$), denoting $\mathbf{x} \prec \mathbf{y}$, if for each n in the range $1, \ldots, m$: $\sum_{j=1}^{n} x_j^{\uparrow} \leq \sum_{j=1}^{n} y_j^{\uparrow}$, with equality holding when $n = m$. The superscript "↑" indicates that elements are to be taken in descending order, so, for example, $x_1^{\uparrow}$ is the largest element in $(x_1, \ldots, x_m)$. The majorization relation is a partial order on real vectors, with $\mathbf{x} \prec \mathbf{y}$ and $\mathbf{y} \prec \mathbf{x}$ if and only if $x^{\uparrow} = y^{\uparrow}$.

More details in: R. Bhatia, *Matrix Analysis* (Springer-Verlag, New York, 1997).

Marangoni effect – the mass transfer on or in a liquid layer due to surface tension differences. Since a liquid with a high surface tension pulls more strongly on the surrounding liquid than one with a low surface tension, the presence of a gradient in surface tension will naturally cause the liquid to flow away from regions of low surface tension. The surface tension gradient can in turn be caused by a concentration gradient or by a temperature gradient.

First described in: J. Thomson, *On certain curious motions observable on the surfaces of wine and other alcoholic liquours*, Phil. Mag. **10**, 330 (1855); C. Marangoni, *Sull'espansione delle goccie di un liquido galleggiante sulla superficie di altro liquido*, (Fusi, Pavia, 1865); C. Marangoni, *Über die Ausbreitung der Tropfen einer Flüssigkeit auf der Oberfläche einer anderen*, Ann. Phys. **219**, 337–354 (1871).

Marcus formula presents the charge transfer rate in molecules between a donor and an acceptor, each with a discrete number of localized vibronic states in the form: $k_{da} = 2\pi/\hbar |V_{da}|^2 F$. Here V_{da} stands for the electronic coupling and the nuclear factor F contains the reorganization energy accounting for vibrionic effects.

First described in: R. A. Marcus, N. Sutin, *Electron transfer in chemistry and biology*, Biochim. Biophys. Acta 811(3), 265–322 (1985).

Recognition: in 1992 R. A. Marcus received the Nobel Prize in Chemistry for his contributions to the theory of electron transfer reactions in chemical systems.

See also www.nobel.se/chemistry/laureates/1992/index.html.

Markov process – a **stochastic process** which assumes that in a series of random events the probability of an occurrence of each event depends only on the immediately preceding outcome. It is characterized by a matrix of transition probabilities. It measures the probability of moving from one state to another.

First described in: A. A. Markov, *Rasprostranenie zakona bol'shih chisel na velichiny, zavisyaschie drug ot druga*, Izvestiya Fiziko-matematicheskogo obschestva pri Kazanskom universitete, 2-ya seriya, **15**, 135–156, (1906).

Marx effect – the energy of photoelectrons emitted from an illuminated surface is decreased when the surface is simultaneously illuminated by light of lower frequency than that causing the emission.

First described in: E. Marx, *On a new photoelectric effect in alkali cells*, Phys. Rev. **35**(9), 1059–1060 (1930).

maser – an acronym for a device producing **m**icrowave **a**mplification by **s**timulated **e**mission of **r**adiation.

First described in: N. G. Basov, A. M. Prokhorov, *The theory of a molecular oscillator and a molecular power amplifier*, Disc. Faraday Soc. **19**, 96–99 (1955); A. L. Schawlow, C. H. Townes, *Infrared and optical masers*, Phys. Rev, **112**(6), 1940–1949 (1958); A. M. Prokhorov, *A molecular amplifier and generator of submillimetre waves*, Zh. Eksper. Teor. Fiz. 34(6), 1658–1659 (1958)–in Russian; N. G. Basov, B. M. Vul, Y. M. Popov, *Quantum-mechanical semiconductor generators and amplifiers of electromagnetic oscillations*, Sov. Phys. JEPT **37**(2), 416 (1960).

Recognition: in 1964 C. H. Townes, N. G. Basov and A. M. Prokhorov received the Nobel Prize in Physics for fundamental work in the field of quantum electronics, which has led to the construction of oscillators and amplifiers based on the maser–laser principle.

See also www.nobel.se/physics/laureates/1964/index.html.

mass-detection NEMS – **nano-electromechanical systems** used for the detection of ultrasmall masses. The devices consist of an oscillating very tiny cantilever; when a small particle is absorbed onto the cantilever it alters the frequency at which the cantilever oscillates. The frequency variation can be measured using laser light reflected off the cantilever, and consequently the mass of the particle can be calculated. A sensitivity in the **atto**gram (10^{-18} grams) regime has been achieved. The **zepto**gram range (10^{-21} grams) is envisioned, thus allowing the detection of viruses.

master equation – a phenomenological first-order differential equation describing the time evolution of the probability of a system to occupy each one of a discrete set of states: $\mathrm{d}P_k/\mathrm{d}T = \sum_l \mathbf{T}_{kl} P_l$, where P_k is the probability for the system to be in the state k, while the matrix $\mathbf{T}_{kl}$ is filled with a grid of transition-rate constants.

Matthiessen rule empirically states that total resistivity of a solid is the sum of the resistivities related to different scattering mechanisms. It means that the scattering rate of electrons moving in solids is additive for different scattering mechanisms, that is $\tau^{-1} = \sum_i \tau_i^{-1}$ with τ representing the energy relaxation time. In terms of the electron mobility it has the form $\mu^{-1} = \sum_i \mu_i^{-1}$, where μ is the integral electron mobility accounting for partial electron mobilities μ_i corresponding to different scattering mechanisms. Note that it fails when the outcome of one scattering process influences the outcome of another and one or more scattering processes depend on the electron wave vector.

First described in: A. Matthiessen, C. Vogt, *Über den Einfluss der Temperatur auf die elektrische Leitungsfähigkeit der Legierungen*, Ann. Phys. **122**, 19–78 (1864).

matrix element – the notation $H_{mn} = \langle m|\mathbf{H}|n\rangle \equiv \int \psi_m^* \mathbf{H} \psi_n$, where **H** is the operator, and ψ_m and ψ_n are the wave functions corresponding to the states m and n. The notation is due to Dirac, where $|n\rangle$ is called a **ket** and denotes a state, and the **bra** $\langle m|$, is its complex conjugate. It bridges the gap between matrices and differential equations used in operators. In fact, it is a scalar product of a member of a complete orthogonal set of vectors representing states with a vector, which results from applying a specified operator to another member of this set.

Maxwell–Boltzmann distribution (statistics) gives the probability to find a particle of mass m and energy E in an ideal gas in thermal equilibrium at a temperature T

$$f(E) = \frac{1}{\sqrt{2\pi m k_B T}} \exp\left(-\frac{E}{k_B T}\right).$$

It can be derived from the more general **Gibbs distribution**. The Maxwell-Boltzmann statistics are valid only at temperatures and densities for which the probability of any given level being occupied is very small.

First described in: L. Boltzmann, *Einige allgemeine Sätze über das Wärmegleich gewicht*, Sitzungsber. Akad. Wiss. Wien: Math.-Naturwiss. Klas. **63**(II), 679 (1871).

Maxwell distribution (statistics) gives the probability to find a particle of mass m and velocity v in an ideal gas in thermal equilibrium at a temperature T. The Maxwellian distribution function is:

$$f(v_x, v_y, v_z) = \left(\frac{m}{2\pi k_B T}\right)^{3/2} \exp\left(-\frac{m(v_x^2 + v_y^2 + v_z^2)}{2k_B T}\right).$$

The Maxwellian velocity distribution is:

$$N(r, v)\mathrm{d}^3 r \mathrm{d}^3 v = \frac{N}{V}\left(\frac{m}{2\pi k_B T}\right)^{3/2} \exp\left(-\frac{mv^2}{2k_B T}\right) \mathrm{d}^3 r \mathrm{d}^3 v,$$

where N is the total number of particles, and V is the volume of the gas. The distribution of an individual velocity component is:

$$N(v_x)\mathrm{d}v_x = \frac{N}{V}\left(\frac{m}{2\pi k_B T}\right)^{1/2} \exp\left(-\frac{mv_x^2}{2k_B T}\right)\mathrm{d}v_x,$$

and the distribution of speeds is:

$$N(v)\mathrm{d}v = 4\pi\frac{N}{V}\left(\frac{m}{2\pi k_B T}\right)^{3/2} v^2 \exp\left(-\frac{mv^2}{2k_B T}\right)\mathrm{d}v.$$

First described in: J. C. Maxwell, *Illustrations of the dynamical theory of gases,* Phil. Mag. **19**, 19–32 (1860), and **20**, 21–37 (1860).

Maxwell equations connect electric charges and electric and magnetic fields in any medium. In the differential form they are:

$$\nabla\mathbf{D} = \rho, \qquad \nabla\mathbf{B} = 0$$

$$\nabla\times\mathbf{E} = -\frac{\partial\mathbf{B}}{\partial t}, \qquad \nabla\times\mathbf{H} = j + \frac{\partial\mathbf{D}}{\partial t}$$

$$\mathbf{D} = \epsilon_0\mathbf{E} + \mathbf{P}, \qquad \mathbf{B} = \mu_0\mathbf{H} + \mathbf{M},$$

where ∇ is the **Nabla-operator**, **D** is the electric displacement, **B** is the magnetic induction or magnetic flux density, **E** is the electric field strength, **H** is the magnetic field strength, **P** is the polarization density of the medium (that is the electric dipole moment per unit volume), **M** is the magnetization density of the medium (that is the magnetic dipole moment per unit volume), and j is the electrical current density.

The first pair of equations show that free electric charges ρ are the sources of the electric displacement and that the magnetic induction is source free. The second pair of equations demonstrate how temporally varying magnetic and electric fields generate each other. In addition, the magnetic field **H** can be created by a macroscopic current with density j. The third pair of equations are material equations in their general form. They show that electric displacement in the material is given by the sum of electric field and polarization, while the magnetic flux density is given by the sum of magnetic field and magnetization.

First described in: J. C. Maxwell, *A Treatise on Electricity and Magnetism,* vol. II (Clarendon Press, 1873).

Maxwell's demon – the name given by W. Thomson (Lord Kelvin) to the mysterious creature separating molecules according to their velocities in the thought experiment proposed by J. C. Maxwell. The demon opens and closes a trap door between two compartments of a chamber containing gas, and pursues the subversive policy of only opening the door when fast molecules approach it from the right, or slow ones from the left. In this way he establishes a temperature difference between the two compartments without doing any visible work, in violation of the second law of thermodynamics, and consequently permitting a host of contradictions.

In fact, the second law is not violated, as it was shown in the twentieth century. It becomes clear when one considers the tricks of the demon in terms of information processing. In order to select molecules, the demon stores the random results of his observations of the molecules. The information about the molecule's location must be present in the demon's memory. The demon's memory thus gets hotter. The irreversible step is not the acquisition of information, but the loss of information if the demon later clears his memory. The information erasure operation increases the entropy in the environment, as required by the second law. This is the thermodynamic cost of elementary information manipulations.

First described in: J. C. Maxwell, *Theory of Heat* (Longmans, Green and Co., London, 1871).

Maxwell triangle – a diagram used to represent the trichromatic variables of the components in a three-color combination.

First described in: J. C. Maxwell, *On the theory of compound colours, and the relations of the colours of the spectrum*, Phil. Trans. R. Soc. London **150**, 57–84 (1860).

Maxwell–Wagner polarization – a space charge polarization in a material consisting of electrically conducting grains and insulating grain boundaries.

First described in: K. W. Wagner, *Erklärung der dielectrischen Nachwirkungsvorgänge auf Grund Maxwellscher Vorstellung*, Arch. Electrotech. **2**, 371–387 (1914); J. C. Maxwell, *A Treatise on Electricity and Magnetism*, vol. I (Clarendon Press, 1873).

Maxwell–Wagner relaxation – relaxation of a charge **polarization** characterized by a set of different relaxation times. It is typical for the relaxation in inhomogeneous dielectrics with regions of different conductivity, as it takes place in ceramics containing conducting grains of different size with insulating grain boundaries. The total relaxation current in such systems is interpreted as the sum of exponential decays according to **Debye relaxation** (with a single relaxation time), thus yielding a nonexponential time dependence of the current.

First described in: K. W. Wagner, *Erklärung der dielectrischen Nachwirkungsvorgänge auf Grund Maxwellscher Vorstellung*, Arch. Electrotech. **2**, 371–387 (1914); J. C. Maxwell, *A Treatise on Electricity and Magnetism*, vol. I (Clarendon Press, 1873).

McFarland and Tang solar cell – a **solar cell** in which the creation of electron–hole pairs does not occur in the semiconductor. The model is based on a multilayer

photovoltaic device, where photons are absorbed in a photoreceptive layer, in one case consisting of semiconductor **quantum dot**s and in another case consisting of a photosensitive **dye** deposited on the surface of an ultrathin metal–semiconductor Schottky **diode**. The photoexcited electrons are transferred to the metal and travel ballistically to, and over, the **Schottky barrier**. The high ballistic mean free path for hot carriers in Au and the high dielectric constant of the TiO_2 semiconductor make the interface Au/TiO_2 a good candidate for the realization of such a photovoltaic device.

First described in: E. W. McFarland, J. Tang, *A photovoltaic device structure based on internal electron emission*, Nature **421**, 616–618 (2003).

mean free path – an average distance covered by a moving particle between two scattering events.

mechanic molecular machines are molecular assemblies that are chemically, photochemically, and/or electrochemically driven.

More detail in: V. Balzani, M. Venturi, A. Credi, *Molecular Devices and Machines: A Journey into the Nanoworld* (Wiley-VCH, Weinheim 2003).

mega- – a decimal prefix representing 10^6, abbreviated M.

Meissner–Ochsenfeld effect – when a superconducting specimen is placed in a not too large magnetic field and is then cooled through the transition temperature for superconductivity, the magnetic flux originally present is ejected from the specimen.

First described in: F. W. Meissner, R. Ochsenfeld, *Ein neuer Effekt bei Eintritt der Superaleitfähigkeit*, Naturwiss. **21**, 787–788 (1933).

MEMS – an acronym for a **m**icro-**e**lectro**m**echanical **s**ystem. It is a marriage of semiconductor processing to mechanical engineering at the micrometer scale. The principal components of MEMS are mechanical elements (for example a cantilever) and transducers. The transducers convert mechanical energy into electrical or optical signals and vice versa. Currently MEMS technology produces several objects, from digital projectors containing millions of electrically driven micromirrors to microscale motion sensors for use with airbags.

mesodesmic structure – a structure of an ionic crystal in which one of the cation-anion bonds is much stronger than the rest → **anisodesmic** and **isodesmic** structures.

mesoscopic – the term being used to indicate solid-state structures and devices that are large compared to the atomic scale but small compared to the macroscopic scale upon which normal **Boltzmann transport** theory has come to be applied.

Dimensions of such structures and devices are comparable to an elastic scattering length of electrons. In this regime, an electron can travel a great distance before suffering a scattering event that randomizes the phase of its wave function.

metal is distinguished from other substances by its large thermal and electrical conductivity, optical reflecting power, and opacity.

metallocene – an **organometallic compound** consisting of parallel cyclopentadienyl rings bound to a metal, forming **cyclopentadienyl complex**es. The ring molecule donates or accepts a pair of electrons to form a coordinate covalent bond with the central metal atom of coordination complexes and organometallic compounds.

There can be numerous organometallic coordination compounds distinguished by the number of cyclopentadienyl rings (with or without substituents) bonded to a central transition metal atom, the types of **transition metals** and the type of the bridge. Metallocenes possess transition metal atoms whose bonding involves an overlap of ns, (n−1) d, and np orbitals of the metal with molecular orbitals of appropriate symmetry of each aromatic ring. Metals known to form metallocene complexes are Ti, Zr, Hf, V, Cr, Mo, W, Mn, Fe, Ru, Os, Co, Rh and Ni.

Metallocenes having a catalytic site in a systematic molecular structure are used as polymerization catalysts to produce uniform polymers with unique structures and physical properties. Moreover, metallocenes are of practical interest in many electrochemical techniques, high-temperature chemistry, photolysis chemistry, structural chemistry, organic light-emitting devices, biochemistry and pharmaceutical manufacturing.

More details in: N. J. Long, *Metallocenes: An Introduction to Sandwich Complexes* (Blackwell Science, 1998).

metalloid – an element in which properties of both metallic and nonmetallic behavior can be discerned. Examples: Sb and Se. Chemical compounds of metalloids may also have intermediate properties.

metal–organic chemical vapor deposition (MOCVD) – a **chemical vapor deposition** techniques using **metal–organic compounds** as precursors for fabrication of high-quality semiconductor superlattices with abrupt interfaces and layer thicknesses down to the monolayer range. The term ''metal–organic'' denotes the broad group of compounds that contain metal–carbon bonds (known as organometallic compounds), those with metal–oxygen carbon bonds (the alkoxides) and the coordination compounds of metals and organic molecules. In practice, metal alkyls, preferentially with methyl (CH_3) and ethyl (C_2H_5) radical groups, are mainly used. Appropriate compounds are mentioned in the metal–organic compounds section. Most of them are liquid around room temperature. They are introduced into a reaction chamber by a carrier gas saturated with their vapor by passing through a bubbler. The deposition can be performed at atmospheric or lower pressure. The apparatus for MOCVD is sketched in Figure M.3. The classical



Figure M.3 Simplified schematic diagram of an MOCVD machine.

design appropriate for growth of GaAs and GaAlAs heterostructures is shown. Trimethyl gallium ($(CH_3)_3Ga$) and trimethyl aluminum ($(CH_3)_3Al$) are introduced into reactor chamber by bubbling supply metals for the compound formation. Group V components are often introduced in the form of hydrides, like AsH_3 in the example shown. Other widely used hydrides are discussed in the **hydride** section. Hydrogen is usually employed as a carrier gas in order to protect the pyrolysis of alkyl and hydride molecules by involving their common hydrogen ambient. The integrated scheme of the chemical reactions occurring at the heated surface of the substrate is as follows:

$$(CH_3)_3Ga + AsH_3 \xrightarrow{650\,^\circ C} GaAs \downarrow + 3CH_4$$

Acceptor impurities, such as Zn or Cd, can be introduced into the reaction chamber within alkyls, and donor impurities such as Si, S or Se can be introduced as hydrides. For deposition of group III nitrides (AlN, GaN, InN) ammonia (NH_3) is used as a source of nitrogen.

In order to form abrupt interfaces, for changes in either the solid composition or the doping level, the composition of the gas ambient is changed by closing the lines supplying certain gaseous reactants. The volumes of the mixing system and reactor must be reasonably minimized in order to change the composition of the gas, and the resulting material grows rapidly and gives sharp interfaces. The mixture of gases must be changed without affecting the total flow through the reaction chamber. Improved sharp interfaces are also formed when rapid thermal processing regimes are employed. Heating cycles as short as 30–60 s provide appropriate conditions for material deposition, but eliminate atomic interdiffusion mixing at interfaces.

MOCVD is capable of depositing highly stoichiometric materials of virtually all $A^{III}B^{V}$ semiconductors and the ternaries and quaternaries based on them. It is also successfully used for the growth of other semiconductors, like $A^{II}B^{VI}$, and oxides. Continuous epitaxial films, as well as **quantum wire** and **quantum dot** structures, are fabricated by this technique via mechanisms presented in **self-organization (during epitaxial growth)**. There is a possibility of growing on a large number of wafers simultaneously, which meets the requirements of commercial mass production. Restrictions associated with MOCVD include contamination by carbon and serious practical issue of safety related to handling of the highly toxic and explosive hydrides.

First described in: H. M. Manasevit, *Single-crystal gallium arsenide on insulating substrates,* Appl. Phys. Lett. **12**(4), 156–159 (1968).

metal–organic compounds (for chemical vapor deposition) – compounds consisting of metals attached to organic molecules, that is having at least one primary metal carbon bond. Those suitable for chemical vapor deposition are listed in the Table M.2.

First described by R. Bunsen in 1839.

metal–organic molecular beam epitaxy (MOMBE) → **molecular beam epitaxy**.

metamaterial – an artificially structured material with electromagnetic properties governed by elements that are patterned on a macroscopic scale and that take the place of atoms or molecules in naturally occurring materials. It can therefore be engineered so that it has a much wider range of electromagnetic responses, including a negative index of refraction → **negative-index material**. As an example of a metamaterial, copper rings and wires deposited on a circuit board substrate can be mentioned.

Metropolis algorithm aims to generate a trajectory in a phase space (let it be $\mathbf{R}$), which samples from a chosen statistical ensemble, when multidimensional integral are numerically evaluated. In order to do the evaluation, it is necessary to sample complicated probability distributions in many-dimensional spaces. The normalizations of these distributions are unknown and are so complicated that they cannot be sampled directly. The Metropolis rejection algorithm allows an arbitrarily complex distribution with a probability density $P(\mathbf{R})$ to be sampled in a straightforward way without knowledge of its normalization. It generates the sequence of sampling points $\mathbf{R}_m$ by moving a single walker according to the following steps:

Step 1. Start the walker at a random position $\mathbf{R}$.

Step 2. Make a trial move to a new position $\mathbf{R}'$ chosen from some probability density function $T(\mathbf{R}' \leftarrow \mathbf{R})$. After the trial move the probability that the walker initially at $\mathbf{R}$ is now in the volume element $d\mathbf{R}'$ is $d\mathbf{R}' \times T(\mathbf{R}' \leftarrow \mathbf{R})$.

Step 3. Accept the trial move to $\mathbf{R}'$ with probability

$$A(\mathbf{R}' \leftarrow \mathbf{R}) = \min\left(1, \frac{T(\mathbf{R}' \leftarrow \mathbf{R})P(\mathbf{R}')}{T(\mathbf{R}' \leftarrow \mathbf{R})P(\mathbf{R})}\right).$$

If the trial move is accepted, the point $\mathbf{R}'$ becomes the next point on the walk; if the trial move is rejected, the point $\mathbf{R}$ becomes the next point on the walk. If $P(\mathbf{R})$ is high, most trial moves away from $\mathbf{R}$ will be rejected and the point $\mathbf{R}$ may occur many times in the set of points making up the random walk.

Step 4. Return to step 2 and repeat the procedure.

Table M.2 Metal-organic compounds for chemical vapor deposition of semiconductors and metals.

Element	Compound		Melting point (°C)	Boiling point (°C)	Vapor pressure equation[a] $\log P = A - B/T$	
	formulae	name			A	B
Be	$(C_2H_5)_2Be$	diethylberyllium	solid at RT dissociate at 85°C		14.496	5102
Mg	$(C_2H_5)_2Mg$	diethylmagnesium	solid at RT dissociate at 175°C		9.121	2832
	$(C_5H_4CH_3)_2Mg$	ditolylmagnesium			$0.2T$ at 20°C $1.8T$ at 70°C	
Zn	$(CH_3)_2Zn$	dimethylzinc	−29.2	44.0	7.802	1560
	$(C_2H_5)_2Zn$	diethylzinc	−30.0	117.6	8.280	2109
Cd	$(CH_3)_2Cd$	dimethylcadmium	−4.5	105.5	7.764	1850
Al	$(CH_3)_3Al$	trimethylaluminum	15.4	126.1	8.224	2135
	$(C_2H_5)_3Al$	triethylaluminum	−52.5	185.6	8.999[b]	2361
	iso-$(C_4H_9)_3Al$	tri-isobutylaluminum	4.3		7.121[c]	1710
	$(CH_3)_2NH_2CH_2Al$	trimethylaminealuminum				
Ga	$(CH_3)_3Ga$	trimethylgallium	−15.8	55.7	8.07	1703
	$(C_2H_5)_3Ga$	triethylgallium	−83.2	142.8	8.224	2222
In	$(CH_3)_3In$	trimethylindium	88.4	135.8	10.52	3014
	$(C_2H_5)_3In$	triethylindium	−32	144	8.930	2815
	$(C_3H_7)_3In$	tripropylindium	−51	178		
Si	$(CH_3)_4Si$	tetramethylsilicon	−99.1	26.6		
	$(C_2H_5)_4Si$	tetraethylsilicon		153.7		

Ge	$(CH_3)_4Ge$	tetramethylgermanium	−88	43.6		
	$(C_2H_5)_4Ge$	tetraethylgermanium	−90	163.5		
Sn	$(CH_3)_2Sn$	dimethytin			7.445	1620
	$(C_2H_5)_2Sn$	diethytin	liquid at RT		6.445	1973
			dissociate at 150°C			
P	$(CH_3)_3P$	trimethylphosphine		37.8		
	$(C_2H_5)_3P$	triethylphosphine		127		
	$(t\text{-}C_4H_9)_3P$	tertiarybutylphosphine		215	7.586	1539
As	$(CH_3)_3As$	trimethylarsine		51.9	7.405	1480
	$(C_2H_5)_3As$	triethylarsine		140		
	$(CH_3)_4As_2$	tetramethyldiarsine		170		
	$(C_4H_9)_4As$	tetrabutylarsine			7.500	1562
Sb	$(CH_3)_3Sb$	trimethylantimony		80.6	7.707	1697
	$(C_2H_5)_3Sb$	triethylantimony		160		
Te	$(CH_3)_2Te$	dimethyltellurium	−10	82	7.970	1865
	$(C_2H_5)_2Te$	diethyltellurium		137.5		
Fe	$(C_5H_5)_2Fe$	ferrocene	solid at RT			
			sublimate at 179°C			

[a] P in Torr, T in K. [b] $\log P = A - B/(T - 73.82)$. [c] $\log P = A - B/(T - 73.82)$.

The initial points generated by this algorithm depend on the starting point and should be discarded. Eventually, however, the simulation settles down and sets of points snipped out of the random walk are distributed according to $P(\mathbf{R}')$.

First described in: N. Metropolis, A. W. Rosenbluth, M. N. Rosenbluth, A. H. Teller, E. Teller, *Equation of state calculations by fast computing machines,* J. Chem. Phys. **21**(6), 1087–1092 (1953).

More details in: D. Frenkel, B. Smit, *Understanding Molecular Simulation* (Academic Press, San Diego, 1996); W. M. C. Foulkes, L. Mitas, R. J. Needs, G. Rajagopal, *Quantum Monte Carlo simulations of solids,* Rev. Mod. Phys. **73**(1), 33–83 (2001).

micella = **micelle**.

micelle (micella) – an aggregate of **surfactant** molecules dispersed in a liquid **colloid**. A typical micelle in aqueous solution forms an aggregate with the **hydrophilic** ''head'' regions in contact with surrounding solvent, sequestering the **hydrophobic** tail regions in the micelle centre. This type of micelle is known as a normal phase micelle (oil-in-water micelle). Inverse micelles have the head groups at the centre with the tails extending out (water-in-oil micelle). Micelles are approximately spherical in shape. Other phases, including shapes such as ellipsoids, cylinders, and bilayers are also possible. The shape and size of a micelle is a function of the molecular geometry of its surfactant molecules and solution conditions such as surfactant concentration, temperature, pH, and ionic strength.

A **micelle** is formed when a variety of molecules including soaps and detergents are added to water. The molecule may be a fatty acid, a salt of a fatty acid (soap), a **phospholipid**, or other similar molecule. The process of forming micellae is known as **micellization**. It is part of the phase behavior of many **lipids** according to their polymorphism.

Micellar systems have the unique property of being able to solubilize both **hydrophobic** and **hydrophilic** compounds.

micellization → **micelle**.

Michelson interferometer produces interference fringes by splitting a beam of coherent light into two paths, bouncing the beams back and recombining them. It is schematically shown in Figure M.4.

The different paths may be of different lengths or be composed of different materials to create alternating interference fringes on a detector.

The interference is sensitive to differences in the phase of waves, which varies over distances less than one micrometer for visible light, corresponding to very short times (about 2 fs). Therefore it is a sensitive method used to detect and measure small deformations, displacements, etc.

See also www.phy.davidson.edu/StuHome/cabell_f/ diffractionfinal/pages/Michelson.html.



Figure M.4 A Michelson interferometer.

First described in: A. A. Michelson, *The relative motion of the earth and the luminiferous ether*, Am. J. Sci. (3)**22**, 120–29 (1881).

Recognition: in 1907 A. A. Michelson received the Nobel Prize in Physics for his optical precision instruments and the spectroscopic and metrological investigations carried out with their aid.

See also www.nobel.se/physics/laureates/1907/index.html.

micro- – a decimal prefix representing 10^{-6}, abbreviated μ.

microcavity (in a semiconductor light-emitting structure) – **quantum wells** sandwiched between two multilayer semiconductor mirrors that reflect light with an efficiency of over 99%. Any light entering the cavity containing the quantum wells is therefore trapped inside, provided that its wavelength is twice the thickness of the cavity. The light bounces back and forth between the mirrors, with a fraction less than 0.1% leaking through the mirrors at each bounce. The ability to trap photons and electrons in the cavity is used for engineering of **vertical-cavity surface-emitting lasers** and other optoelectronic devices.

micro-electromechanical system → **MEMS**.

Miller indices are used to define various planes and directions in a crystal. For a plane they are determined by first finding the intercepts $m\mathbf{a}$, $n\mathbf{b}$, $p\mathbf{c}$ of the plane with the three basis axes in terms of the lattice constant $(\mathbf{a}, \mathbf{b}, \mathbf{c})$ – see Figure M.5.

Then the reciprocals of these numbers are taken and the results are reduced to the smallest three integers h, k, l having the same ratio $(h : k : l = 1/m : 1/n : 1/p)$. The obtained integers are enclosed in parentheses (hkl) as the Miller indices for a single plane or set of parallel planes. If the plane intersects the axes at negative coordinates the minus sign is placed above the number to which it applies. The



Figure M.5 The intercepts on the axes of a lattice plane with the Miller indices.

designation {*hkl*} is used for planes of equivalent symmetry (for example {100} for (100), (010), $(\bar{1}00)$, $(0\bar{1}0)$ and $(00\bar{1})$ in cubic symmetry). The most important low-index planes in a cubic crystal are shown in Figure M.6.

The direction is indicated as [*hkl*], with $h : k : l = \cos\alpha : \cos\beta : \cos\gamma$, where α, β, γ are the angles between this direction and the related axes in the lattice. The designation $< hjl >$ is used for a full set of equivalent directions. In cubic crystals the [*hkl*] direction is normal to the (*hkl*) plane.

First described in: W. H. Miller, *A Treatise on Crystallography* (Deighton, Cambridge, 1839).



Figure M.6 Miller indices of the most important planes in a cubic crystal.

Miller law states that if the edges formed by the intersections of three faces of a crystal are taken as the three reference axes, then the three quantities formed by dividing the intercept of a fourth face with one of these axes by the intercept of a fifth face with the same axis are proportional to small whole numbers, rarely exceeding 6. It is also known as **law of rational intercepts**.

First described in: R.-J. Haüy, *Essai d'une Théorie sur la Structure des Cristaux*, (1784) and *Traité de Minéralogie* (1801), W. H. Miller, *A Treatise on Crystallography* (Deighton, Cambridge, 1839).

milli- – a decimal prefix representing 10^{-3}, abbreviated m.

Minkowski space – the four-dimensional space including time. In this space the unit of length may vary significantly with the direction in which the measurement occurs. It has the metric whose signature is $(+, -, -, -)$. It is equally often chosen to be $(-, +, +, +)$. If one denotes the coordinates of a point in Minkowski space as (t, x, y, z), then the distance l between this point and the origin is defined as $l^2 = t^2 - x^2 - y^2 - z^2$. The signs of the four terms correspond to the signature of the metric. Notice that the right side may be negative, making the distance imaginary.

It is used in the theory of special relativity.

First described in: H. Minkowski, *Die Grundgleichungen für die elektromagnetischen Vorgänge in bewegten Körpern*, Gött. Nachr. **2**, 53 (1908).

MND effect = **Mahan effect.**

mobility edge – a sharp boundary between states in which electrons are localized and can only move by thermally excited hopping to another localized state and the state that allows freedom of movement, albeit with a very short free path.

modality – distinct types of behavior that a system can exhibit under identical or nearly identical conditions.

modulation doped field effect transistor (MODFET) → **high electron mobility transistor (HEMT)**.

modulation-doped structure – a semiconductor heterojunction based structure, in which the region of a heavily doped semiconductor producing charge carriers and the region where their low scattering transport is needed are separated in space. A heterostructure formed by semiconductors with different band gaps is used for this. This approach is illustrated in Figure M.7.

In the modulation-doped structure, donor impurity is introduced into the semiconductor with the larger band gap. The structure is neutral everywhere as long as the electrons sit on their donor atoms. When being released they diffuse away, cross the junction and fall into the nearest region with a lower potential energy. There they lose energy and become trapped because they cannot climb the barrier presented by ΔE_c. Thus, the electrons appear to be space separated from the positively charged donors which have produced them. The fallen electrons set up an electrostatic potential that tends to drive them back. As a result, a roughly triangular potential well for electrons is formed at the heterojunction. This well is of the order of some nanometers wide. The energy levels in it for motion along the x direction are quantized in a similar way to those in a square well. Often only the lowest level is occupied. All electrons then occupy the same state for motion in x, but remain free to move in the other two directions. A **two-dimensional electron gas** is formed.

The heterostructure fabricated as a superlattice composed of n-AlGaAs (greater band gap material) and undoped GaAs represents a classical example of modulation-doped structures. It demonstrates some order of magnitude increase in the electron



Figure M.7 Conduction band profiles around a heterojunction formed by semiconducting small gap material A and semiconducting large gap material B.

mobility. The observed low-temperature mobility of electrons as high as 2×10^7 cm^2 V^{-1} s^{-1} seems to be a record for GaAs. Meanwhile, the electron density achieved in the two-dimensional electron gas is about 5×10^{11} cm^{-2}.

The modulation doping achieves two benefits. First, it separates electrons from their donor atoms, thus reducing scattering of electrons by ionized impurities. Second, it confines electrons in the near junction region in two dimensions.

First described in: R. Dingle, H. L. Störmer, A. C. Gossard, W. Weigmann, *Electron mobilities in modulation doped semiconductor heterojunction superlattices,* Appl. Phys. Lett. **33**(7), 665–667 (1978).

MOKE – an acronym for **magnetooptical Kerr effect.**

molecular antenna – an array of molecular components capable of absorbing light and delivering the resulting electronic energy to a predetermined component of the array.

molecular battery – a molecule able to accumulate charge.

molecular beam epitaxy (MBE) – a technique of material deposition in ultrahigh vacuum. In principle, it has appeared as an advanced variant of **chemical vapor deposition** providing better purity and crystalline perfection, as well as improved composition and thickness control of the epitaxial heterostructures formed. It is performed in a chamber evacuated to ultrahigh vacuum, typically of the order of 10^{-11} Torr or better. At such low pressure, atoms and molecules injected into the chamber travel in straight lines without collisions until they impinge on the substrate or the chamber walls. A sketch of the apparatus for MBE is shown in Figure M.8.



Figure M.8 Simplified schematic diagram of an MBE machine.

Molecular beams are usually created by **effusion cells** mounted in the machine. An MBE machine is typically equipped with several effusion cells containing the elements necessary for forming the semiconductor and for doping. Their orifices are directed to the heated substrate. Growth commences when the shutters shadowing the cells are opened. The composition of the film can be varied by controlling the flux of each component, which is operated by the temperature inside the cell. The temperature of the substrate is important for composition and quality of the deposited layers. Growth-related defects will have no time to be annealed at low temperatures, while if the temperature is too high incongruent component evaporation from the surface can modify its atomic composition and unwanted interdiffusion will blur the interfaces. The substrate may be rotated during deposition in order to have better composition and thickness uniformity over the deposited layers.

An important feature of MBE is that it is performed in ultrahigh vacuum, which allows many electron beam and ion beam diagnostic techniques to be used for monitoring of the film growth process and for *in situ* analysis of the grown films. Some of the often employed electron beam probing techniques are Auger electron spectrometry (**AES**), low-energy electron diffraction (**LEED**), reflection high-energy electron diffraction (**RHEED**), and X-ray and ultraviolet photoemission spectroscopy (**XPS** and **UPS**). The ion-based probe is usually secondary ion mass spectrometry (**SIMS**).

The one most commonly used for monitoring the growth process in MBE machines is RHEED. It is performed with the electron beam directed at nearly grazing incidence to the surface of the sample. The pattern of diffracting electrons is viewed on a fluorescent screen. As the surface changes in a periodic way as a new monolayer is grown, it can be observed in the intensity and pattern of the RHEED signal. The diffraction pattern reveals the structure of the surface.

A wide range of methods has been developed from the basic MBE. The examples are **chemical beam epitaxy (CBE)** and **metal–organic molecular beam epitaxy (MOMBE)**, where the solid sources of conventional MBE are replaced by similar precursors to those used in CVD and MOCVD processes. All are aimed at improving control of the thickness and composition of the layers to improve the performance of the resulting devices.

The MBE and related techniques are usually used for fabrication of high-quality **superlattices** for **quantum wells** on the basis of $A^{III}B^{V}$ and Si-Ge heterostructures. Their advantages include highly abrupt junctions between different materials and precise control of the particular layer thickness. Moreover, periodically arranged self-organized **quantum wires** and **quantum dots** of these materials can also be fabricated under the conditions presented in **self-organization (during epitaxial growth)**. The main drawback of the MBE techniques in commercial applications is their slow throughput and high cost.

First described in: B. A. Unvala, *Epitaxial growth of silicon by vacuum evaporation*, Nature **194**, 966 (1962) – first attempt to grow epitaxial silicon in a vacuum with a techniques similar to MBE; J. R. Arthur Jr., *Interaction of Ga and As*$_2$ *molecular beams with GaAs surfaces*, J. Appl. Phys. **39**(8), 4032–4034 (1968) – demonstration of the technique that is now called molecular beam epitaxy; in the late 1960s A. Cho and J. R. Arthur Jr. at Bell Laboratories developed the MBE technique to grow multilayer heterojunction structures with atomically abrupt interfaces and precisely controlled compositional and doping profiles over distances as short as few tens of angstroms.

molecular crystal – a solid formed by inactive atoms, such as the inert gases, and saturated with molecules, such as hydrogen, methane and benzene. They are usually bound together by weak electrostatic forces, have low melting and boiling points and generally evaporate in the form of stable molecules.

molecular device – an assembly of a discrete number of molecular components (a **supramolecule**) designed to perform a specific function.

More details in: V. Balzani, M. Venturi, A. Credi, *Molecular Devices and Machines: A Journey into the Nanoworld* (Wiley-VCH, Weinheim, 2003); A. Credi, *Artificial nanomachines based on interlocked molecules*, J. Phys. Condens. Matter **18**, S1779–S1795 (2006).

molecular dynamics (simulation) – a technique to compute the equilibrium and transport properties of a classical many-body system. "Classical" means that the motion of the constituent particles obeys the laws of classical mechanics.

Molecular dynamics simulation often realizes the search of the optimal atomic configuration by means of step-by-step motion of atoms to the sites providing zero balance of the static forces acting on each atom in the structure. This configuration has the lowest energy and thus it has to be stable. The motion of the *i*-th atom is described by Newton's equations:

$$\frac{d\mathbf{r}_i(t)}{dt} = \mathbf{v}_i(t),$$

$$\frac{d\mathbf{v}_i(t)}{dt} = \frac{1}{M}\mathbf{F}_i\left[\mathbf{r}_1(t), \ldots, \mathbf{r}_N(t); \mathbf{v}_i(t)\right],$$

where $\mathbf{r}_i(t)$ is the coordinate, $\mathbf{v}_i(t)$ the velocity, and M the mass of the *i*-th atom. The number of atoms in the structure is N. Given that the classical N-body problem lacks a general analytical solution, the only path open is numerical integration.

The force $\mathbf{F}_i$ acting on every atom is calculated using many-body potential for the atomic interaction in the system under consideration. If it is not known, pairwise additive interactions between the *i*-th atom and all other ones (*j*-ths) is assumed to represent the many-body case

$$\mathbf{F}_i = \sum_j \mathbf{F}_{ij}.$$

It depends on the positions of all atoms and the velocity of the *i*-th one. The force $\mathbf{F}_{ij}$, representing interaction between *i*-th and *j*-th atoms, as in the molecular dynamics approach, is determined by a many-body potential or more easily by the potential of pair atomic interaction ϕ_{ij}

$$\mathbf{F}_{ij} = \frac{dU_{ij}}{dr_{ij}}\frac{\mathbf{r}_{ij}}{r_{ij}},$$

where $\mathbf{r}_{ij} = \mathbf{r}_i - \mathbf{r}_j$. The pair potential U_{ij} can be given in the form of **Lennard–Jones, Born–Mayer, screened Coulomb potential**, or in another form adequate to the peculiarities of interaction between the atoms to be simulated.

As soon as all forces acting between the atoms have been described, Newton's equations of motion can be integrated. The solution is specified completely once the law of force between interacting particles is given. To start the simulation, we should assign initial positions and velocities to all particles in the system. The atom positions should be chosen compatible with the structure that we are aiming to simulate. A particularly simple choice is to start with the atoms at the sites of a regular undisturbed lattice. Random directions and a fixed magnitude based on temperature are assigned to the initial velocities. They are also adjusted to ensure the center of mass of the system to be at rest, so any overall flow is eliminated.

The choice of a particular algorithm for the numerical integration depends on the complexity of the structure to be simulated, available computer facilities and desired accuracy of the simulation. Meanwhile, the integration procedure supposes that after each time step new positions of atoms are computed and their coordinates are updated simultaneously. Newton's equations of motion are solved until the acting static forces no longer change with time, so one can conclude that the structure has equilibrated. Actual positions of atoms in the equilibrated structure are calculated.

More details in: D. C. Rapaport, *The Art of Molecular Dynamics Simulation* (Cambridge University Press, Cambridge, 1995).

molecular electronics – a field of research and development of information processing devices with single molecules. The basic idea of molecular electronics is to use individual molecules as wires, switches, rectifiers, and memories. Another conceptual idea that is advanced by molecular electronics is the switch from a **top-down approach**, where the devices are extracted from a single large-scale building block, to a **bottom-up approach** in which the whole system is composed of small basic building blocks with **recognition**, structuring, and **self-assembly**. The great advantage of molecular electronics is the intrinsic nanoscale size of the molecular building blocks that renders this technology potentially competitive with the conventional integrated circuit technology.

First described in: A. Aviram, M. A. Ratner, *Molecular rectifiers,* Chem. Phys. Lett. **29**(2), 277–283 (1974).

More details in: A. Aviram, M. A. Ratner (eds), *Molecular electronics science and technology*, Annals of the New York Academy of Sciences, vol. 852 (The New York Academy of Sciences, New York 1998), A. Aviram, M. A. Ratner, V. Mujica (eds), *Molecular electronics II*, Annals of the New York Academy of Sciences, vol. 960 (The New York Academy of Sciences, New York 2002); *Introducing Molecular Electronics,* edited by G. Cuniberti, G. Fagas, K. Richter (Springer Verlag, Berlin Heidelberg, 2005).

molecular engineering – control of the structure of matter at the molecular level or any means of manufacturing molecules.

molecular machine – a particular type of molecular device, where the relative positions of the component parts can change as a result of some external stimulus.

More details in: V. Balzani, M. Venturi, A. Credi, *Molecular Devices and Machines: A Journey into the Nanoworld* (Wiley-VCH, Weinheim, 2003); A. Credi, *Artificial nanomachines based on interlocked molecules,* J. Phys. Condens. Matter **18**, S1779–S1795 (2006).

molecular mechanics (simulation) – a technique to compute equilibrium atomic arrangements of solids. It supposes no permanent motion of atoms during searching for their equilibrium arrangement. A static relaxation procedure is used in this approach. Its methodology is based on the analysis of the total potential energy of the structure. This energy is calculated for different atomic arrangements. The atomic configuration characterized by the lowest energy is concluded to be the equilibrium configuration.

Initial positions of atoms and the potential of their pair interaction used for calculations are chosen using the same criteria as in molecular dynamics. Coordinates of atoms can be changed simultaneously or atom-by-atom. The accuracy of the prediction of the equilibrium atomic configuration depends to a great extent on the experience and intuition of the person performing the simulation and the number of arrangements calculated. Such an approach can be used not only within classical mechanics formalism but also when quantum mechanics calculations of total energy of the structure under consideration are performed. An application of the **Monte Carlo method** makes the results obtained statistically weighted.

molecular nanoelectronics → molecular electronics.

molecular nanomagnet – a molecular nano-object with tailored magnetic characteristics. The term **single molecule magnet** is also applicable to it if the magnet is formed by a single molecule. Synthetic chemistry has developed an extraordinary capability to produce new metal–organic compounds. A molecular nanomagnet is a **cluster**, typically with size $\sim$1 nm, where a finite number of magnetic centers (**transition-metal**, **rare-earth** ions, or even organic **radical**s) are strongly coupled by organic bridges that work as paths for the **exchange interaction**. In most cases, the intra-cluster magnetic interactions are stronger than those between clusters: the bearing of the molecule is therefore unrelated to the environment. This **bottom-up approach** allows us therefore to construct magnetic materials starting from the molecular level. The molecules are typically packed in ordered crystals of macroscopic size. One useful feature of single-molecule magnet behavior is that the properties observed in bulk crystals essentially reflect those of the single molecule. Measurement techniques on bulk sample thus have access to microscopic properties. Interest in these materials has increasingly grown owing to their possible use for high-density information storage, as well as the possibility that some member of this family of materials could provide the **qubit**s needed for **quantum computation**. Mn_{12}-acetate $[Mn_{12}O_{12}(CH_3COO)_{16}(H_2O_4)]$, **antiferromagnetic** spin clusters are the most studied systems because of high spin, $S = 10$, that arises by the interplay of **ferromagnetic** and antiferromagnetic interaction among the manganese atoms of the cluster, and its high anisotropy barrier. Another interesting class of magnetic molecules is constituted by antiferromagnetic rings: **ferric wheel**s, for example Fe_6, Fe_{10}, Fe_{12}, Fe_{18} (with Fe^{3+} ($s = 5/2$)), **Cr-based molecular ring**s (also called **chromic wheel**s) like Cr_8 and Cr_{10} (comprising Cr^{3+} ($s = 3/2$)) and **V-based molecular ring**s like V_8 and V_{10} (V^{3+} ($s = 1$)) were synthesized. $[Cr_8F_8(O_2CC(CH_3)_3)_{16}]0.25C_6H_{14}$, referred to as Cr_8, (see Figure M.9a) represents a paradigmatic case for this category in which **carboxylate** and fluoride bridges between the eight Cr^{3+} ions give rise to a planar and regular octahedron. The common feature of these systems is the small number n of **paramagnetic** ions and the nearest-neighbor **Heisenberg exchange interaction**. The coupling between spin centers leads to a characteristic ground state total spin $S = \sum_{i=1}^{n} s_i = 0$, due to the exact compensation between the spin centers within the ring (see Figure M.9b).



Figure M.9 (a) The structure of Cr_8 obtained by X-ray diffraction. The eight Cr^{3+} ions are bonded by two carboxylates and one fluoride bridges. H-atoms are omitted for clarity. (b) Schematic of the Heisenberg exchange interaction between the Cr^{3+} ions. Courtesy of A. Ghirri and M. Affronte.

More details in: O. Kahn, *Molecular Magnetism*, (Wiley VCH, New York 1993); D. Gatteschi, R. Sessoli, J. Villain, *Molecular Nanomagnets*, (Oxford University Press, 2006).

molecular orbital – an orbital formed by atomic orbitals when atoms are coupled in a molecule.

σ **orbital (**σ **state)** is a molecular orbital that has cylindrical symmetry around the internuclear axis. It resembles an s **atomic orbital** when viewed along the axis. The s orbital combinations have no angular momentum around the molecular axis.

π **orbital (**π **state)** is a molecular orbital which is perpendicular to the internuclear axis. The notation π is the analog of p for orbitals in atoms.

The atomic orbitals producing molecular orbitals may overlap constructively or destructively thus resulting in bonding or antibonding orbitals, respectively.

The molecular orbitals of homonuclear diatomic molecules can be labeled with a subscript g or u that specifies their **parity** indicating their behavior under inversion. The subscript *g* stands for gerade (German for ''even'') and *u* for ungerade (German for ''odd'') representing the fact that the wave function of the orbital can be even or odd when inverted through a point midway between the atoms. The bonding combination for σ orbitals is gerade. For π orbitals, the bonding combination is ungerade. A gerade π orbital is zero on the plane bisecting the bond. Examples of bonding combinations of atomic orbitals and resultant molecular bond designations are sketched in Figure M.10.

molecular orbital theory → **Hund-Mulliken theory.**



Figure M.10 Coupling of atomic orbitals in diatomic molecules.

molecular rectifier – a **diode** at molecular level→ **Aviram–Ratner model**.

First described in: A. Aviram, M. A. Ratner, *Molecular rectifiers,* Chem. Phys. Lett. **29**(2), 277–283 (1974).

More details in: A. Aviram, M. A. Ratner (eds), *Molecular electronics science and technology,* Annals of the New York Academy of Sciences, vol. 852 (The New York Academy of Sciences, New York 1998), A. Aviram, M. A. Ratner, V. Mujica (eds), *Molecular electronics II,* Annals of the New York Academy of Sciences, vol. 960 (The New York Academy of Sciences, New York 2002).

Möller scattering – scattering of electrons by electrons.

First described in: C. Möller, *Über den Stoss zweier Teilchen unter Berücksichtigung der Retardation der Kräfte,* Z. Phys. **70**(11–12), 786–795 (1931); C. Möller, *Zur Theorie des Durchgangs schneller Elektronen durch Materie,* Ann. Phys. **14**, 531 (1932).

momentum operator –

$$\mathbf{p} = \frac{\hbar}{\mathrm{i}}\nabla = \frac{\hbar}{\mathrm{i}}\left(\frac{\partial}{\partial x} + \frac{\partial}{\partial y} + \frac{\partial}{\partial z}\right).$$

monoclinic lattice – a **Bravais lattice** with a unit cell having a single two-fold symmetry axis or a single symmetry plane.

monochromatic – having a single color. The term is generally used to refer to electromagnetic radiation of a single wavelength.

monolayer (ML) – the thinnest layer containing a stoichiometrically complete set of atoms, that is one molecular thick.

monomer – one (mono) molecular unit.

Monte-Carlo method – a numerical simulation technique employing a random sample of the configurational state to obtain an approximate value of the average of a physical quantity. The **Metropolis algorithm** can be applied for sampling. The name ''Monte Carlo'' was chosen because of the extensive use of random numbers in the calculations.

The method is readily used for simulation of natural stochastic processes, like particle transport in matter, and for numerical calculations of many-dimensional integrals, sums, integral and matrix equations.

First described in: N. Metropolis, S. Ulam, *The Monte Carlo method,* J. Am. Stat. Ass. **44**(247), 335–341 (1949).

More details in: D. Frenkel, B. Smit, *Understanding Molecular Simulation* (Academic Press, San Diego, 1996).

Moore's law states that the maximum number of individual integrated circuit components which can be integrated within the most advanced single silicon chip is doubling every year (see Figure M.11).

First described in: G. E. Moore, *Cramming more components onto integrated circuits* Electronics **38**(8), 114-116 (1965).



Figure M.11 Evolution of the number of transistors in a single CPU (central processing unit) versus the year. The graph is based on the Intel CPU.

Morse potential – an interatomic pair potential of the form: $V(r) = A\exp(-ar) + B\exp(br)$, where r is the interatomic distance and A, a, B, b are fitted parameters.

First described in: P. M. Morse, *Diatomic molecules according to the wave mechanics. II. Vibrational levels,* Phys. Rev. **34**(1), 57–64 (1929).

More details in: I. G. Kaplan, *Intermolecular Interactions: Physical Picture, Computational Methods and Model Potentials* (John Wiley & Sons, Chichester, 2006).

Morse rule – an empirical relationship between an equilibrium interatomic distance r in a diatomic molecule and its equilibrium vibrational frequency ω in the form $\omega r^3 = 3000 \pm 120\ \text{cm}^{-1}$.

MOS – an acronym for a **m**etal/**o**xide/**s**emiconductor structure or electron device.

MOSFET – an acronym for a **m**etal/**o**xide/**s**emiconductor **f**ield **e**ffect **t**ransistor.

Mössbauer effect – recoil-free resonance absorption and emission of gamma-rays by nuclei. It is illustrated in Figure M.12.

A gamma-ray resulting from a nuclear excitation following the beta-decay of a radioactive isotope parent is removed from a collimated beam by resonantly re-exciting another or the same species. The emitted radiation is then absorbed or scattered by the target nuclei. The transmitted fraction is recorded with the use of a detector.

When a radioactive isotope is placed in a material, it may emit gamma-radiation of relatively low energy without creating or annihilating any phonons. The gamma-ray carries the total energy of the transition and may be absorbed by the nuclei in the reverse process in a recoil-free fashion. Thus, resonance occurs between two nuclei. Every phase containing **Mössbauer isotopes** exhibits an energy absorption spectrum with characteristic hyperfine interaction parameters, which are fingerprints of the phase. It is used for phase analysis of matter. The Mössbauer isotopes are ^{57}Fe, ^{119}Sn, ^{121}Sb, ^{125}Te, ^{129}I(radioactive), ^{151}Eu, ^{161}Dy, ^{170}Yb, ^{197}Au, and ^{237}Np(radioactive).

First described in: R. L. Mössbauer, *Kernresonanzabsorption von Gammastrahlung in Ir*^{191}, Naturwiss. **45**(22), 538–539 (1958); R. L. Mössbauer, *Kernresonanzfluoreszenz von Gammastrahlung in Ir*^{191}, Z. Phys. **151**(2), 124–143 (1958).

Recognition: in 1961 R. L. Mössbauer received the Nobel Prize in Physics for his researches concerning the resonance absorption of gamma radiation and his discovery in this connection of the effect which bears his name.

See also www.nobel.se/physics/laureates/1961/index.html.

Mössbauer isotopes → **Mössbauer effect**.



Figure M.12 The Mössbauer effect.

Mott–Hubbard transition – a transition from metallic to insulator properties in solids due to a sufficiently strong electron-electron interaction that produces a gap for current-currying charge excitations in systems with an integral average number of electrons for a lattice site. Consider a model consisting of hydrogen atoms forming a simple cubic lattice with adjustable lattice parameter a_0. The many-body wave function is described, within a tight-binding scheme, in terms of atomic 1s orbitals centered on the nuclei R_i. The effects on the total energy as a consequence of electrons hopping onto neighboring sites can be estimated. If the electrons have more room, increasing the lattice constant, their kinetic energy will reduce. On the other hand the Coulomb repulsion energy of the electrons will increase by an energy U for each double occupancy. If a_0 exceeds a critical value a_c, the system will become an insulator. This idea, due to Mott → **Mott metal–insulator transition**, can also be understood within the one-band Hubbard model → **Hubbard Hamiltonian.** When there is one electron per lattice site on average and the interaction U is large compared to the bandwidth W, a charge gap of the order of $\Delta = U - W$ will be produced in the system. This metal–insulator transition is hence called the Mott–Hubbard transition.

First described in: N. F. Mott, *The basis of the electron theory of metals, with special reference to the transition metals*, Proc. Phys. Soc. A **62**, 416–422 (1949); J. Hubbard, *Electron correlations in narrow energy bands. I*, Proc. R. Soc. A **276**, 238–257 (1963); J. Hubbard, *Electron correlations in narrow energy bands. II*, Proc. R. Soc. A **277**, 237–259; J. Hubbard, *Electron correlations in narrow energy bands. III*, Proc. R. Soc. A **281**, 401–419 (1964); J. Hubbard, *Electron correlations in narrow energy bands. IV*, Proc. R. Soc. A **285**, 542–560 (1965).

Mott insulator – a material that in the band description should behave like a **metal**, but nonetheless is an **insulator** because of localization of electrons on individual atoms by the Coulomb interaction.

Mott law → **hopping conductivity**.

Mott metal–insulator transition – a solid loses its metallic character when the concentration of electrons in it is so large that the average electron separation $n^{-1/3}$ becomes significantly larger than four Bohr radii $n^{-1/3} \gg 4a_B$. Above a certain critical electron density the screening length becomes so small that electrons can no longer remain in a bound state. This produces metallic behavior. Below this critical electron concentration the potential well of the screened field extends far enough for a bound state to be possible. There is a critical value of the lattice constant (lattice of hydrogen atoms at absolute zero) that separates the metallic state (smaller values) from the insulating state (larger values) $a_c = 4.5a_B$. The metallic state appears when a conduction electron starts seeing a screened Coulomb interaction from each proton.

First described in: N. F. Mott, *On the transition to metallic conduction in semiconductors*, Can. J. Phys. **34**(12A), 1356–1368 (1956).

Recognition: in 1977 P. W. Anderson, N. F. Mott and J. H. van Vleck received the Nobel Prize in Physics for their fundamental theoretical investigations of the electronic structure of magnetic and disordered systems.

See also www.nobel.se/physics/laureates/1977/index.html.

Mott scattering – scattering of identical particles due to a **Coulomb force**. It is typical for transition metals whose d band is only partially occupied and, therefore, the **Fermi level** in these metals intersects not only the conduction but also the d bands. Moreover, since the atomic wave functions of d levels are more localized than those of the outer levels, they overlap much less, which means that the d band is narrow and the corresponding density of states is high. This opens up a new very effective channel for scattering of conduction electrons into the d band. This scattering mechanism explains why all transition metals are poor conductors compared with noble metals.

First described in: N. F. Mott, *Electrons in transition metals*, Adv. Phys. **13**, 325–422 (1964).

Mott–Wannier exciton = **Wannier–Mott exciton.**

mRNA – messenger RNA→ **RNA**.

muffin-tin approach – an approximation of atomic potentials in solids by the spherically symmetrical function of the radius r_{mt}, which is the muffin-tin radius, and by a constant in the region between spheres. This potential function is called the **muffin-tin potential**. The potentials of two neighboring atoms do not overlap.

First described in: J. C. Slater, *Wave functions in a periodical potential*, Phys. Rev. **51**(10), 846-851 (1937).

muffin-tin orbital – a piecewise function consisting of the solution of the **Schrödinger equation** for an isolated atom within a sphere of given radius and a zero kinetic energy tail function outside this region.

muffin-tin potential → **muffin-tin approach**.

Mulliken transfer integral – an energy involved in moving an electron from one site in a crystal to a nearest-neighbor site.

First described in: R. S. Mulliken, *Overlap integrals and chemical binding*, J. Am. Chem. Soc. **72**(10), 4493–4503 (1950).

multi-asperity contact model → **Greenwood-Williamson theory**.

multiferroic material – a material having both **ferromagnetic** and **ferroelectric** properties in the same phase. It has spontaneous magnetization which can be switched by an applied magnetic field, spontaneous polarization which can be switched by an applied electric field, and often some coupling between the two.

In general, the transition metal d electrons, which are essential for magnetism, reduce the tendency for off-center ferroelectric distortion. Consequently, an additional electronic or structural driving force must be present for ferromagnetism and ferroelectricity to occur simultaneously.

The examples of multiferroic materials include $Ni_3B_7O_{13}I$, $Pb_2(CoW)O_6$, $Pb_2(FeTa)O_6$, $(1-x)Pb(Fe_{2/3}W_{1/3})O_3 - xPb(Mg_{1/2}W_{1/2})O_3$.

First described in: G. A. Smolensky, A. I. Agranovskaya, V. A. Isupov, *New complex ferroelectrics of the* $A_2^{2+}(B_I^{3}+B_{II}^{5+})O_6$ *type I*, Fiz. Tverdogo Tela 1(1) 170–171 (1959) (in Russian); Sov. Phys. Sol. Stat. 1(1), 149 (1959) (in English) – predicted; E. Ascher, H. Rieder, H. Schmid, H. Stössel, *Some properties of ferromagnetoelectric nickel-iodine boracite,* $Ni_3B_7O_{13}I$, J. Appl. Phys. 37(3), 1404–1405 (1966) – experimentally observed.

More details in: R. Ramesh, N. A. Spaldin, *Multiferroics: a magnetic twist for ferroelectricity*, Nature Materials 6, 13–20 (2007); R. Ramesh, N. A. Spaldin, *Multiferroics: progress and prospects in thin films*, Nature Materials 6, 21–29 (2007).

multijunction solar cell a device where multiple **solar cell**s are stacked on each other in decreasing energy band gap. The first material absorbs the high energy photons, but transmits photons with lower energies, which then get absorbed in the cells below. The total voltage is the sum of the voltages but the current is determined by the worst of the two sub-cells.

multimodal nanoparticle – a nanoparticle that can be simultaneously detected by magnetic resonance imaging (that is **nuclear magnetic resonance**) and optical imaging (that is **fluorescence microscopy**). These nanoparticles integrate the advantages of high sensitivity, due to the optical imaging, with the potential of three-dimensional imaging, due to the magnetic resonance detection. Thus they can play an important role in the understanding of biological processes at molecular level and in the progress of diagnostic tools. Examples are **dye**-doped silica nanoparticles, gold nanoparticles, and **quantum dots**.

More details in: P. Sarma, S. Brown, G. Walter, S. Santra, B. Moudgil, *Nanoparticles for bioimaging*, Adv. Coll. Int. Sci. **123–126**, 471–485 (2006).

multiplet – a collection of closely spaced energy levels which appear from of a single energy level as a result of its splitting due to a relatively weak interaction.

multiquantum well → **quantum well**

Murrell–Mottram potential – the many-body expansion of the potential energy function truncated at the three-body level. For *N* interacting atoms it has the form

$$V = \sum_{i}^{N-1} \sum_{j>i}^{N} V_{ij}^{(2)} + \sum_{i}^{N-2} \sum_{j>i}^{N-1} \sum_{k>j} V_{ijk}^{(3)},$$

where $V_{ij}^{(2)}$ and $V_{ij}^{(3)}$ are the two- and three-body terms, respectively.

The two-body term being a Rydberg energy function is $V_{ij}^{(2)} = -D(1 + a\rho_{ij})exp$ $(-a\rho_{ij})$ with $\rho_{ij} = (r_{ij} - r_e)/r_e$, where D is the energy scaling parameter which determines the well-depth, a is the parameter determining the range of the interaction, r_{ij} is the interatomic distance, and r_e is the equilibrium pair separation. The three-body term represents a repulsive interaction by a polynomial in terms of the separations between the three atoms: r_{ij}, r_{ik}, r_{jk}. This term must be symmetrical with respect to the interchange of like atoms and therefore the polynomial is not a simple function of the separations but is an expansion in terms of symmetry coordinates Q_i defined as:

$$\begin{pmatrix} Q_1 \\ Q_2 \\ Q_3 \end{pmatrix} = \begin{pmatrix} \sqrt{1/3} & \sqrt{1/3} & \sqrt{1/3} \\ 0 & \sqrt{1/2} & -\sqrt{1/2} \\ \sqrt{2/3} & -\sqrt{1/6} & -\sqrt{1/6} \end{pmatrix} \begin{pmatrix} \rho_{ij} \\ \rho_{jk} \\ \rho_{ki} \end{pmatrix},$$

The three-body term then becomes $V_{ijk}^{(3)} = DP(Q_1, Q_2, Q_3)F(b, Q_1)$. Here $P(Q_1, Q_2,$ $Q_3)$ is the polynomial in the symmetry coordinates and $F(b, Q_1$ is the damping function (with a damping parameter b) which constrains the three-body term to approach zero as Q_1 becomes large.

All totally symmetric polynomials can be written as sums of products of the following three functions: $Q_1 Q_2^2 + Q_3^2 Q_3 - 3Q_3 Q_2^2$.

The polynomial term in $V_{ijk}^{(3)}$ can be cubic or quartic. The cubic one is given by $P(Q_1, Q_2, Q_3) = c_0 + c_1 Q_1 + c_2 Q_1^2 + c_3(Q_2^2 + Q_3^2) + c_4 Q_1^3 + c_5 Q_1(Q_2^2 + Q_3^2) + c_6$ $(Q_3^3 - 3Q_3 Q_2^2)$ and the quartic polynomial has the additional terms $c_7 Q_1^4$ $+ c_8 Q_1^2(Q_2^2 + Q_3^2) + c_9(Q_2^2 + Q_3^2)^2 + c_1 0(Q_3^3 - 3Q_3 Q_2^2)$.

The damping function can be any of the following $F(b, Q_1) = \exp(-bQ_1)$, $F(b, Q_1) = \exp(-bQ_1^2)$, $F(b, Q_1) = 0.5 - 0.5\tanh(0.5bQ_1)$, or $F(b, Q_1) = \operatorname{sech}(bQ_1)$, which all decay exponentially at long range though they have different short range behavior.

As the potential is empirical the parameters are to be fitted to experimental data.

The potential is successfully applied to represent interactions in a wide range of atomic systems including metals from groups II and III of the Periodic Table, group IV semiconductors and transition metals.

First described in: J. N. Murrell, R. E. Mottram, *Potential energy functions for atomic solids*, Mol. Phys. **69**(3), 571–585 (1990).

More details in: G. A. Mansoori, *Principles of Nanotechnology: Molecular-based Study of Condensed Matter in Small Systems* (World Scientific, Singapore, 2005).

N

From NAA (neutron activation analysis) to Nyquist–Shannon sampling theorem

NAA – an acronym for **neutron activation analysis**.

Nabla-operator – the differential operator, which in Cartesian coordinates is $\nabla = (\partial/\partial x + \partial/\partial y + \partial/\partial z)$. Its applications to scalar $f(\mathbf{r})$ or vector $\mathbf{A}(\mathbf{r})$ fields are $\nabla f(\mathbf{r}) = \mathrm{grad} f$, $\nabla \cdot \mathbf{A}(\mathbf{r}) = \mathrm{div}\mathbf{A}$, $\nabla \times \mathbf{A}(\mathbf{r}) = \mathrm{curl}\mathbf{A}$.

NAND operator → **logic operator**.

nano- – a decimal prefix representing 10^{-9}, abbreviated n.

nanobiotechnology – a specialized field of **nanotechnology**, focusing on the improved and novel physical, chemical, and biological properties of biological objects at the nanoscale.

More details in: Nanobiotechnology: Concepts, Applications and Perspectives, edited by C. M. Niemeyer, C. A. Mirkin (Wiley-VCH, Weinheim, 2004).

nanocomposite – a material containing several compact components with their spatial organization at the nanoscale or molecular level.

nanocrystallite – a crystal of nanometer (1 nm = 10^{-9} m) dimensions.

nano-electromechanical system → **NEMS**.

nanoelectronics – the field of science and engineering dealing with fabrication, study and application of nanosize electronic devices for information technologies. Quantum effects generally determine operational principles of these devices.

More details in: R. Companó (ed.) *Technology Roadmap for Nanoelectronics*; Office for Official Publications of the European Communities: Luxembourg 2000.

nanoethics – the field related to the social, ethical and broader human implications of nanotechnology.

More details in: J. Moor, J. Weckert, *Nanoethics: assessing the nanoscale from an ethical point of view* in *Discovering the Nanoscale*, edited by D. Baird, A. Nordmann, J. Schummer (IOS Press, Amsterdam 2004).

nano-flash memory device – a flash memory device similar in structure to a MOS field effect transistor → **MOSFET** except that it is a three-terminal device with two gate electrodes, one on top of the other. The top electrode forms the control gate, below which a floating gate is capacitively coupled to the control gate. The memory cell operation involves putting charge on the floating gate or removing it, corresponding to two logic levels. Nanoflash devices utilize single or multiple nanoparticles as the charge storage element.

More details in: B. G. Streetman, S. Banerjee, *Solid State Electronic Devices* (Prentice Hall, New Jersey, 2000); R. Compañó (ed.) *Technology Roadmap for Nanoelectronics*; Office for Official Publications of the European Communities: Luxembourg 2000.

nanoimprinting → **imprinting**.

nanolithography – **lithography** at the nanometer scale.

nanomagnetism – a subfield of nanoscience dealing with magnetic structures having dimensions in the nanometer range. It is already central to data storage, sensor and device technologies but is increasingly being used in the life sciences and medicine.

More details in: D. L. Mills, J. A. C. Bland, *Nanomagnetism* (Elsevier, Amsterdam 2006); S. D. Bader, *Colloquium: Opportunities in nanomagnetism*, Rev. Mod. Phys. **78**(1), 1–15 (2006).

nanomedicine – includes the medical diagnosis, monitoring and treatment of the human body at the level of single molecules or molecular assemblies that provide structure, control, signaling, homeostasis, and motility at the nanoscale. More generally nanomedicine addresses the important challenges and advances in medical nanoscale-structured materials and devices, biotechnology devices and **molecular machine** systems and nanorobotics.

More details in: R. A. Freitas Jr, *What is nanomedicine?*, Nanomedicine: Nanotech. Biol. Med. **1**(1), 2–9 (2005).

nanoparticle-based solar cell – a **photovoltaic** device that relies on the properties of **nanostructure**s → **Grätzel solar cell**, **intermediate band solar cell**, **McFarland and Tang solar cell**, **plasmonic effects based solar cell**, **up- and down-conversion solar cell**.

nanopeapod – a nanostructure containing an interior space filled by foreign atom(s) or molecule(s). Typically these are **carbon nanotubes** and **fullerenes** with dopants inside.

First described in: P. M. Ajayan, S. Iijima, *Capillarity-induced filling of carbon nanotubes*, Nature **361**, 333–334 (1993).

nanophotonics – the field of science and engineering dealing with fabrication, study and application of optical phenomena at the nanoscale. It deals with structures and processes which are spatially localized in domains smaller than the wavelength of visible radiation. The field includes nanoscale confinement of radiation → **NSOM** and **photonic crystals**, nanoscale confinement of matter, nanoscale physical or photochemical transformations.

nanopiezotronics utilizes the coupled **piezoelectric** and semiconducting properties of nanowires and nanobelts for designing and fabricating electronic devices and components, such as field-effect **transistor**s and **diode**s.

More details in: Z. L. Wang, *Nanopiezotronics*, Adv. Matter. **19**, 889–892 (2007).

nanopolymers – a new class of materials that represents the nanoscale equivalent of **polymer**s. They were obtained by the introduction of defects onto two opposing areas on the surface of spherical-shaped metallic nanoparticles. These divalent nanoparticles were then chained together making freestanding films.

First described in: G. A. DeVries, M. Brunnbauer, Y. Hu, A. M. Jackson, B. Long, B. T. Neltner, O. Uzun, B. H. Wunsch, F. Stellacci, *Divalent metal nanoparticles*, Science **315**, 358–361 (2007).

nanostructure – an ensemble of bonded atoms that have at least one dimension in the range of one to some hundreds of nanometers ($1 \text{ nm} = 10 \text{ Å} = 10^{-9} \text{ m}$).

nanotechnology – a set of methods and techniques providing the fabrication of structures consisting of individual atoms, molecules or macromolecular blocks in the length scale of approximately 1–100 nm. It is applied to physical, chemical and biological systems in order to explore their novel and differentiating properties and functions arising at a critical length scale of matter typically under 100 nm.

nanotoxicology – the scientific field related to the potential for human and environmental exposure, hazard and risk associated with the use and development of nanostructured materials.

More details in: V. Stone, K. Donaldson, *Nanotoxicology: sign of stress*, Nature Nanotechnology **1**(1), 23–24 (2006).

nanotribology represents the study of friction, wear and lubrication at atomic length and time scales.

More details in: J. Krim, *Friction at the nanoscale*, Physics World **18**, 31–34 (2005).

nanotube radio – a fully functional, fully integrated radio receiver, orders-of-magnitude smaller than any previous radio, from a single **carbon nanotube**. The single nanotube serves, simultaneously, as all major components of a radio: antenna, tuner, amplifier, and demodulator. Moreover, the antenna and tuner are implemented in a radically different manner than traditional radios, receiving signals via high frequency mechanical vibrations of the nanotube rather than through traditional electrical means.

First described in: K. Jensen, J. Weldon, H. Garcia, A. Zettl, *Nanotube radio*, Nano Lett. **7**(11), 3508–3511 (2007).

nascent state – the condition of a chemical element at the instant of its liberation as a result of a chemical reaction. In some cases, the element will remain in the atomic state for an appreciable time before assuming its normal molecular condition. During this interval further chemical reactions are facilitated.

natural motors – play the role of a motor inside the cells. There are linear motors like dynein, kinesin and myosin, and rotory motors, like ATP syntase.

More details in: V. Balzani, M. Venturi, A. Credi, *Molecular Devices and Machines: A Journey into the Nanoworld* (Wiley-VCH, Weinheim, 2003); E. L. Wolf, *Nanophysics and Nanotechnology – Second Edition* (Wiley VCH, Weinheim, 2006).

near-field region – an area closest to an aperture or source of electromagnetic waves where the diffraction pattern differs substantially from that observed at an infinite distance.

near-field scanning optical microscopy (NSOM) – a type of scanning probe microscopy that maps the near-field electrical and optical properties of semiconductor structures on a nanometer scale. NSOM (also often termed **SNOM – scanning near-field microscopy**) is a technique in which a tapered optical fiber is held atop a sample within a fraction of wavelength and scanned across its surface, thus circumventing the far-field wave physics and its limitations → **Abbe's principle**. It is illustrated in Figure N.1.

At each point in the scan, the optical radiation emitted by the sample is collected from the near field through the small aperture created by the tip of the tapered fiber. It is an aperture-type NSOM. The spatial resolution of the scan is determined by the tip–sample distance and by the tip size. With the most widely used aperture probe, resolutions well below 100 nm have been demonstrated.

In addition, different apertureless techniques were also developed, some of which resulted in resolutions down to a few nanometers. Scattering type NSOM is one of them. It uses a sharpened homogeneous metal tip as a probe. When the tip is illuminated with the polarization parallel to the tip axis, the electric field at the



Figure N.1 Comparison of far-field and near-field imaging of a sample. (a) Far-field imaging. Light is diffracted so that the area illuminated is larger than the aperture. Sub-λ details of the image are lost. (b) Near-field imaging. The area illuminated corresponds well with the aperture of the optics. From http://www.thermomicro.com/products/aurora.html.

apex is induced and enhanced owing to the large surface charge accumulation at the apex. Spatial resolution defined by the apex diameter is expected. The field enhancement effect can also contribute to the detection of extremely weak signals, such as Raman scattering from single nanoobjects. However, because the illumination area is limited by diffraction generating unwanted background, elimination of signal from the strong background is critical for imaging with sufficient contrast.

Photon-emission **scanning tunneling microscopy (STM)** and light-illumination STM can be categorized into NSOM from the viewpoint of essential contributions of light to them. They allow the atomic resolution associated with from STM operation. In photon-emission STM, one detects photons created by inelastic scattering of electrons in the tunneling gap applying a bias voltage. Photon-emission spectra provide electronic state information of a nanoscale region, such as a local density of states. Light-illuminating STM measures the tunneling current of photoexcited carriers. Precise spectroscopy of local electronic states can be carried out by means of highly controlled light. By using polarized photons one can couple to a specific spin state. Ultrafast optical pulses enables one to observe electron dynamics with a high spatiotemporal resolution.

First described in: E. H. Singe, *A suggested method for extending microscopic resolution into the ultra microscopic region,* Phil. Mag. J. Sci. **6**, 356–362 (1928) – the suggestion; E. A. Ash, G. Nicholls, *Super-resolution aperture scanning microscope,* Nature **237**, 510–512 (1972) – demonstration for micro-wave radiation; D. W. Pohl, W. Fischer, M. Lanz, *Optical stethoscopy: image recording with resolution λ/20,* Appl. Phys. Lett. **44**(7), 651–653 (1984) and E. Betzig, A. Lewis, A. Q. Harootunian, M. Isaacson, E. Kratschmer, *Near-field scanning optical microscopy (NSOM)*, Biophys. J. **49**, 269–279 (1986) – practical development for the optical range.

More details in: R. C. Dunn, *Near-field scanning optical microscopy,* Chem. Rev. **99**(10), 2891–2927 (1999); *Roadmap of Scanning Probe Microscopy,* edited by S. Morita (Springer Verlag, Berlin Heidelberg, 2007).

Néel point (temperature) – the temperature above which particular **antiferromagnetic** properties of a substance disappear.

First described in: L. Néel, *Influence of the fluctuations of the molecular field on the magnetic properties of bodies,* Ann. Phys. (Paris) **18**, 1–105 (1932); *Propriétés magnétiques de l'état métallique et énergie d'interaction entre atomes magnétiques,* Ann. Phys. (Paris) **5**, 232–279 (1936).

Recognition: in 1970 L. Neél received the Nobel Prize in Physics for fundamental work and discoveries concerning antiferromagnetism and ferrimagnetism which have led to important applications in solid state physics.

See also www.nobel.se/physics/laureates/1970/index.html.

Néel wall – a boundary between two magnetic domains in a thin film in which the magnetization vector remains parallel to the faces of the film in passing through the wall.

First described in: L. Néel, *Energies des parois de Bloch dans les couches minces,* Compt. Rend. **241**, 533–536 (1955).

negative differential resistance – a property of some electric circuit components and networks which enables them to behave like a power source and supply energy to systems connected their terminals. It is typically a dynamic effect represented by current voltage characteristics shown in Figure N.2.



Figure N.2 Current voltage characteristics representing two types of negative differential resistance of an electronic component or circuit.

negative index material – a material with a negative index of **refraction**. It is also called left-handed material. Contrary to the usual ''positive'' refraction when a wave emerges on the opposite side of the line that runs perpendicular to the refracting interface (see Figure N.3), a wave coming to the interface with a negative index material emerges on the same side of the surface normal. The material composed of copper rings and wires deposited on a circuit board substrate can be an example of materials with a **negative refractive index**.

A slab of negative index material can be used to focus the rays coming from a nearby source. This is illustrated in Figure N.4.

If the source is placed on one side of a slab with a negative refractive index let it be ($n = -1$), the waves are refracted in such a way as to produce a focus inside the slab and then another just outside the slab. Focusing should be much



Figure N.3 Refraction of waves coming to the interface between a vacuum and a positive refractive index medium (a) and between a vacuum and a negative refractive index medium (b).



Figure N.4 Focusing of waves passing through a slab of a negative-index material.

better than positive index optics restricted by diffraction. It could lead to a perfect lens.

*First described in:*V. G. Veselago, *The electrodynamics of substances with simultaneously negative values of e and* μ, Uspekhi Fizicheskih Nauk **92**(3), 517–526 (1967) – in Russian, Sov. Phys. Uspekhi **10**(4), 509–514 (1968) – in English, theoretical prediction; R. A. Shelby, D. R. Smith, S. Schultz, *Experimental verification of a negative index of refraction*, Science **292**, 77–79 (2001) – experimental observation.

nematic phase – a form of **liquid crystal** with an appearance of moving, threadlike structures, particularly visible when observed in thick specimens with polarized light. During this phase, the molecules of the crystal are parallel and able to travel past each other following the direction of their longitudinal axes. This form has one optical axis that occupies the direction of an applied magnetic field. The transition from the isotropic liquid state to the nematic phase is a first-order phase transition.

NEMS – an acronym for a **n**ano-**e**lectro**m**echanical **s**ystem. Like **MEMS** (microelectromechanical system), it is a marriage of semiconductor processing to mechanical engineering, but at the nanometer scale. NEMS open the way to very-high-frequency mechanical devices, ultra-low power signal processing, and high sensitivity to applied forces.

More details in: K. L. Ekinci, M. L. Roukes, *Nanoelectromechanical systems,* Rev. Sci. Inst. **76**, 061–101 (2005).

Nernst effect – development of a transverse electric field in an electric conductor with zero current passing through it when there is a temperature gradient in the conductor and a transverse magnetic field is applied to it. This field is defined as $E = Q\nabla T \times \mathbf{H}$, where Q is the Nernst coefficient. It is also known as the **Ettingshausen–Nernst effect**.

First described in: A. von Ettingshausen, W. Nernst, *Über das Auftreten electromotorischer Kräfte in Metallplatten, welche von einem Wärmestrome durchflossen werden und sich im magnetischen Felde befinden*, Ann. Phys. **265**(10), 343 (1886).

Nernst–Thomson rule states that in a solvent having a high dielectric constant the attraction between anions and cations is small so that dissociation is favored, while the reverse is true in solvents with a low dielectric constant.

First described in: W. Nernst, *Dielektrizitätskonstante und chemisches Gleichgewicht*, Z. Phys. Chem. **13**, 531 (1894); J. J. Thomson, *On the effect of electrification and chemical action on a steam-jet and of water-vapor on the discharge of electricity through gases*, Phil. Mag. **36**, 320 (1893).

Neumann–Kopp's rule states that the heat capacity of 1 mole of a solid substance is approximately equal to the sum over the elements forming the substance of the heat capacity of a gram atom of the element times the number of atoms of the element in a molecule of the substance.

First described in: F. E. Neumann, *Untersuchung über die specifische Wärme der Mineralien*, Ann. Phys. **23**, 1–60 (1831); H. Kopp, *Geschichte der Chemie, Dritter Theil*, (1845) p. 138.

Neumann principle states that the symmetry elements of the point group of a crystal are included among the symmetry elements of any property of the crystal.

First described in: F. E. Neumann, *Vorlesungen über die Theorie der Elastizität der festen Körper und des Lichtäthers* (Teubner-Verlag, Leipzig, 1885).

neural network – a computing paradigm that attempts to process information in a manner similar to that of the brain. It differs from artificial intelligence in that it relies not on preprogramming but on the acquisition and evolution of interconnections between nodes.

neutron – a subatomic particle with no net electric charge, spin $\hbar/2$ and a mass of $1.6749543 \times 10^{-27}$ kg (slightly greater that of a **proton**). A neutron is classified as a **baryon** and consists of two down quarks and one up quark.

First described in: J. Chadwick, *Possible existence of a neutron,* Nature **129**, 312 (1932).

Recognition: in 1935 J. Chadwick received the Nobel Prize in Physics for his discovery of the neutron.

See also www.nobel.se/physics/laureates/1932/index.html.

neutron activation analysis (NAA) is based on bombarding a sample with neutrons, resulting in the production of a radioactive isotope of the element of interest. Thermal neutrons (energy about 0.025 eV) are usually used for this. Gamma-rays emitted by the radioactive isotope are then analyzed. The energy of the radiation is characteristic of the radioactive isotope. It is used for the identification of chemical elements, that is for qualitative analysis. The number of gamma rays emitted correlates to the number of particular atoms in the sample, which is appropriate for quantitative analysis.

Newton's laws of motion – (1) a particle not subjected to external forces remains at rest or moves with constant speed in a straight line; (2) the acceleration of a particle is directly proportional to the resultant external force acting on the particle and is inversely proportional to the mass of the particle; (3) if two particles interact, the force exerted by the first particle on the second particle (called the action force) is equal in magnitude and opposite in direction to the force exerted by the second particle on the first particle (called the reaction force). They form the basis of classical, or Newtonian, mechanics, and have proved valid for all mechanical problems not involving speeds comparable with the speed of light.

First described in: I. Newton, *Philosophiae Naturalis Principia Mathematica* (The Mathematical Principles of Natural Philosophy), 1687.

Newton–Raphson iteration – a technique to find out the solution satisfying the equation $f(E) = 0$. In this technique, if E_n is a first guess at the solution, then a better estimate is $E_{n+1} = E_n - f(E_n)/f'(E_n)$. The new estimate E_{n+2} is then used to generate a second approximation E_{n+3}, and so on, until the successive estimates converge to a required accuracy.

First described in: I. Newton, *Methodus fluxionum et serierum infinitarum* (1664–1671); J. Raphson, *Analysis aequationum universalis* (London, 1690).

Nielsen theorem states that a state $|\psi\rangle$ transforms to $|\phi\rangle$ using local operations and classical communication if and only if λ_ψ is majorized by λ_ϕ → **majorization**. More succinctly, $|\psi\rangle \rightarrow |\phi\rangle$ if $\lambda_\psi \prec \lambda_\phi$, where λ_ψ denotes the vector of eigenvalues of $\phi_\psi \equiv \mathrm{tr}(|\psi\rangle\langle\psi|)$.

First described in: M. F. Nielsen, *Conditions for a class of entanglement transformations,* Phys. Rev. Lett. **83**(2), 436–439 (1999).

nitrate – a salt of nitric acid (HNO_3). For inorganic salts the general formula of nitrates can be expressed as $Me(NO_3)_n$, where Me is a metal or NH_3^+ group and n represents the valency of the metal ($n = 1$ for $Me = NH_3^+$).

nitride – a compound formed by combination of an element with nitrogen.

nitrite – a salt of nitrous acid (HNO_2).

NMR – an acronym for **nuclear magnetic resonance**.

noble gases = **inert gases**.

noble metals – metals with resistance to attack by general chemical reagents: Hg, Ag, Au, Pt, Pd, Ru, Rh, Ir, Os.

Noether theorem states that every time a physical system is left invariant under a continuous transformation, a conserved quantity can be derived.

First described in: E. Noether, *Invariante Variationsprobleme,* Gött. Nachr., Math. Phys. Klasse, 235–252 (1918).

noiseless coding theorem → **Shannon's theorems.**

noisy channel coding theorem → **Shannon's theorems.**

noncloning theorem states that the linearity of quantum mechanics forbids exact replication of quantum states. This means that quantum information cannot be duplicated or cloned (accurately copied).

First described in: W. K. Wootters, W. H. Zurek, *A single quantum cannot be cloned,* Nature **299**, 802–803 (1982).

noncrossing rule states that potential energy curves of diatomic molecules which are of the same electronic species never cross.

First described in: J. von Neumann, E. Wigner, *Über merkwürdige diskrete Eigenwerte,* Phys. Z. **30**, 465–467 (1929).

nonlinear Hanle effect → **Hanle effect**.

NOR operator → **logic operator**.

Nordheim's rule states that the residual resistivity of a binary alloy containing mole fraction x of one element and $1-x$ of another is proportional to $x(1-x)$.

First described in: L. Nordheim, *Zur Elektronentheorie der Metalle. II,* Ann. Phys. **9**, 641–678 (1931).

normal distribution = **Gaussian distribution**.

NOT operator → **logic operator**.

Notre Dame architecture → **quantum cellular automata**.

NRA – an acronym for **nuclear reaction analysis**.

NSOM – an acronym for **near-field scanning optical microscopy**.

nuclear magnetic resonance (NMR) – some nuclei placed in a static magnetic field resonantly absorb energy from a radio frequency field at certain characteristic frequencies. The magnetic field forces magnetic moments, *i.e.* spins, of all the nuclei in the sample to line up and precess around the direction of the field. The spins all precess at the same frequency but with random phases. The radio frequency radiation directed at the sample disturbs the alignment of the spins and produces a state in which the phases are coherent. Thus, the frequency of the resonance coincides with the **Larmor frequency** of precession of the nuclei in the magnetic field and is proportional to the strength of the field.

Nuclear magnetic resonance spectroscopy is used to study molecular structures of matter.

First described in: E. M. Purcell, H. C. Torrey, R. V. Pound, *Resonance absorption by nuclear magnetic moments in a solid*, Phys. Rev. **69**(1), 37–38 (1946); F. Bloch, *Nuclear induction*, Phys. Rev. **70**(7/8), 460–474 (1946).

More details in: C. P. Slichter, *Principles of Magnetic Resonance* (Springer Verlag, Berlin, 1990).

Recognition: in 1952 F. Bloch and E. M. Purcell received the Nobel Prize in Physics for their development of new methods for nuclear magnetic precision measurements and discoveries in connection therewith; in 2003 P. C. Lauterbur and P. Mansfield received the Nobel Prize in Physiology or Medicine for their discoveries concerning magnetic resonance imaging.

See also www.nobel.se/physics/laureates/1952/index.html.

See also www.nobel.se/medicine/laureates/2003/index.html.

nuclear reaction analysis (NRA) involves probing a sample with light ions accelerated to approximately one tenth of the speed of light and measuring the energies and yields of resulting nuclear reaction products. It is often used instead of **Rutherford backscattering spectroscopy** when the matrix contains elements heavier than the isotope of interest. The list (see Table N.1) of usually used particle–particle nuclear reactions include:

For many elements, some being oxygen, nitrogen, carbon, aluminum, magnesium and sulfur, the use of a deuterium probing beam (rather than protons or helium) can give enhanced sensitivity and accuracy owing to larger nuclear reaction cross sections, better defined spectral features and less background interference.

As the technique is isotope specific, it is independent of chemical or matrix effects, providing depth profiling non-destructively.

Table N.1 Usually used particle–particle nuclear reactions.

With protons	With deuterons	With helium-3 ions
$^{6}\mathrm{Li}(p,{}^{4}\mathrm{He})^{3}\mathrm{He}$	$\mathrm{D}(d,p)\mathrm{T}$	$\mathrm{D}({}^{3}\mathrm{He},p)^{4}\mathrm{He}$
$^{7}\mathrm{Li}(p,{}^{4}\mathrm{He})^{4}\mathrm{He}$	$\mathrm{D}(d,n)^{3}\mathrm{He}$	$^{12}\mathrm{C}({}^{3}\mathrm{He},d)^{14}\mathrm{N}$
$^{11}\mathrm{B}(p,{}^{4}\mathrm{He})^{8}\mathrm{Be}$	$^{3}\mathrm{He}(d,p)^{4}\mathrm{He}$	$^{12}\mathrm{C}({}^{3}\mathrm{He},{}^{4}\mathrm{He})^{11}\mathrm{C}$
$^{15}\mathrm{N}(p,{}^{4}\mathrm{He})^{12}\mathrm{C}$	$^{6}\mathrm{Li}(d,{}^{4}\mathrm{He})^{4}\mathrm{He}$	$^{13}\mathrm{C}({}^{3}\mathrm{He},p)^{15}\mathrm{N}$
$^{18}\mathrm{O}(p,{}^{4}\mathrm{He})^{15}\mathrm{N}$	$^{11}\mathrm{B}(d,{}^{4}\mathrm{He})^{9}\mathrm{Be}$	$^{13}\mathrm{C}({}^{3}\mathrm{He},d)^{14}\mathrm{N}$
	$^{12}\mathrm{C}(d,p)^{13}\mathrm{C}$	$^{13}\mathrm{C}({}^{3}\mathrm{He},{}^{4}\mathrm{He})^{12}\mathrm{C}$
	$^{12}\mathrm{C}(d,{}^{4}\mathrm{He})^{10}\mathrm{B}$	$^{14}\mathrm{N}({}^{3}\mathrm{He},p)^{16}\mathrm{O}$
	$^{14}\mathrm{N}(d,p)^{15}\mathrm{N}$	$^{14}\mathrm{N}({}^{3}\mathrm{He},{}^{4}\mathrm{He})^{13}\mathrm{N}$
	$^{14}\mathrm{N}(d,{}^{4}\mathrm{He})^{12}\mathrm{C}$	$^{16}\mathrm{O}({}^{3}\mathrm{He},{}^{4}\mathrm{He})^{15}\mathrm{O}$
	$^{16}\mathrm{O}(d,p)^{17}\mathrm{O}$	$^{16}\mathrm{O}({}^{3}\mathrm{He},p)^{18}\mathrm{F}$
	$^{16}\mathrm{O}(d,{}^{4}\mathrm{He})^{14}\mathrm{N}$	
	$^{19}\mathrm{F}(d,{}^{4}\mathrm{He})^{17}\mathrm{O}$	
	$^{28}\mathrm{Si}(d,p)^{29}\mathrm{Si}$	
	$^{31}\mathrm{P}(d,p)^{32}\mathrm{P}$	
	$^{32}\mathrm{S}(d,p)^{33}\mathrm{S}$	

nucleon – a collective name for a **proton** or a **neutron**, which are main constituents of atomic nuclei.

nucleotide – a building unit of nucleic acids consisting of a heterocyclic base, a sugar (ribose or deoxyribose), and phosphoric acid → **DNA**.

nutation – nodding of the axis of a top about the cone of **precession** caused by impulses or rearrangement of the mass of the top.

Nyquist criterion – in image acquisition, it postulates that the pickup sampling frequency must be a minimum of twice the rate of brightness change of any detail to be resolved.

First described in: H. Nyquist, *Thermal agitation of electric charge in conductors,* Phys. Rev. **32**(1), 110–114 (1928).

Nyquist formula describes thermal generation of noise, also called **Johnson–Nyquist (or Nyquist) noise**, in an electrical resistor R related to the charge fluctuation in it at temperature T: $\overline{\Delta V^2} = 4k_B TR\Delta f$. The fluctuation is regarded as being produced by a zero impedance voltage generator ΔV in series with the resistor producing frequency components in a narrow bandwidth Δf.

First described in: H. Nyquist, *Thermal agitation of electric charge in conductors,* Phys. Rev. **32**(1), 110–114 (1928).

Nyquist frequency – a frequency equal to twice the frequency of the highest frequency significant spectral component of a signal → **Nyquist–Shannon sampling**

theorem. Signals sampled at rates higher than the Nyquist frequency can theoretically be accurately reconstructed from the sampled data.

Nyquist interval → **Nyquist–Shannon sampling theorem**.

Nyquist noise → **Johnson–Nyquist noise**.

Nyquist–Shannon interpolation formula states that if a function $s(x)$ has a Fourier transform $F[s(x)] = S(f) = 0$ for $|f| > W$, then $s(x)$ can be recovered from its samples s_n as

$$s(x) = \sum_{n=-\infty}^{\infty} s_n \frac{\sin[\pi(2Wx - n)]}{\pi(2Wx - n)}.$$

Nyquist–Shannon sampling theorem states that, when an analog signal is converted into the digital one (or otherwise sampling a signal at discrete intervals), the sampling frequency must be originated perfectly from the sampled version. If the sampling frequency is less than this limit, then frequencies in the original signal that are above half the sampling rate will be "aliased" and will appear in the resulting signal as lower frequencies. Therefore, an analog low pass filter (called an anti-aliased filter) is typically applied before sampling to ensure that no components with frequencies greater than half the sample frequency remain. The theorem also applies when reducing the sampling frequency of an existing digital signal.

If a function $s(x)$ has a **Fourier transform** $F[s(x)] = S(f) = 0$ for $|f| > W$, then it is completely determined by giving the value of the function at a series of points spaced $1/(2W)$ apart. The values $s_n = s(n/(2W))$ are called the samples of $s(x)$. The function $s(x)$ can be recovered from its samples by the **Nyquist–Shannon interpolation formula**.

The minimum sample frequency that allows reconstruction of the original signal, that is $2W$ samples per unit distance, is known as the **Nyquist frequency**, (or Nyquist rate). The time between samples is called the **Nyquist interval**.

It has to be noted that even if the concept of "twice the highest frequency" is the more commonly used idea, it is not absolute. In fact the theorem holds for "twice the bandwidth", which is totally different. Bandwidth is related to the range between the first frequency and the last frequency that represent the signal. Bandwidth and highest frequency are identical only in baseband signals, that is, those that go very nearly down to direct current. This concept leads to what is called **undersampling**, often used in software-defined radio systems, which are radio communication systems employing software for modulation and demodulation of radio signals.

The theorem is a fundamental tenet in the field of information theory.

First described in: H. Nyquist, *Certain topics in telegraph transmission theory*, Trans. AIEE **47**(4), 617–644 (1928) – first formulated; C. E. Shannon, *Communication in the presence of noise,* Proc. Inst. Radio Eng. **37**(1), 10–21 (1949) – formally proved.

O

From octet rule to oxide

octet rule states that atoms combine to form molecules in such a way as to give each atom an outer shell of eight electrons, that is an octet.

First described by I. Langmuir in 1919.

Recognition: in 1932 I. Langmuir received the Nobel Prize in Chemistry for his discoveries and investigations in surface chemistry.

See also www.nobel.se/chemistry/laureates/1932/index.html.

Ohm's law states that there is a linear relation between electric current density **J** in a matter and electric field **E** applied to it in the form $\mathbf{J} = \sigma\mathbf{E}$, where σ is the matter conductivity.

First described in: G. S. Ohm, J. Chem. Phys. (Schweigger's J.) **46**, 137 (1826); *Die galvanische Kette mathematisch gearbeitet* (Berlin, 1827).

OLED – an acronym for an **organic light emitting diode**.

oligomer – a molecule composed of a finite number of molecular subunits (**monomer**s) linked together, in contrast to a **polymer** consisting of an unbounded number of subunits. The actual figure is a matter of debate, but often a value between 10 and 100 is referred to.

oligonucleotide – a **polymer** formed by a few **nucleotide**s.

one-atom laser – a **laser** operating with a single atom. An atom (for example cesium) is cooled and trapped in an optical resonant cavity. Then a laser is used to excite the atom, which in its decay to an intermediate state emits a photon into the cavity. Another laser is used to excite the atom into another **excited state** from which the atom decays to the **ground state**, and the process starts again. In contrast to a, conventional laser there is no threshold for lasing. The output flux from the cavity mode exceeds that from atomic **fluorescence** by more than tenfold. The operation mode is sketched in Figure O.1.



Figure O.1 A simplified schematic of operation of a one-atom laser. (**a**) A cesium atom (black dot) is trapped inside a high finesse optical cavity formed by the curved, reflective surfaces of mirrors M_1 and M_2. Light generated by the atom's interaction with the resonant cavity mode propagates as a gaussian beam to single-photon detectors D_1 and D_2. (**b**) The relevant transitions involve the $6S_{1/2}$, $F = 3, 4$; $6P_{3/2}$, $F' = 3', 4'$ levels of the D_2 line at 852.4 nm in atomic cesium. Strong coupling at rate g is achieved for the lasing transition $F' = 3' \rightarrow F = 4$ near a cavity resonance. Pumping of the upper level $F' = 3'$ is provided by the field Ω_3, while recycling of the lower level $F = 4$ is achieved by way of the field Ω_4 and spontaneous decay back to $F = 3$. After J. McKeever, A. Boca, A. D. Boozer, J. R. Buck, H. J. Kimble, *Experimental realization of one-atom laser in the regime of strong coupling*, Nature **425**, 268–271 (2003).

First described in: J. McKeever, A. Boca, A. D. Boozer, J. R. Buck, H. J. Kimble, *Experimental realization of one-atom laser in the regime of strong coupling*, Nature **425**, 268–271 (2003).

opal glass – a glass which contains a disperse phase of small particles of different refractive index from that of the matrix has. They determine reflecting and scattering of light in the glass.

operator (mathematical) – a term used to mean something that operates on a function.

optical confinement factor – a fraction of the electromagnetic energy of the guided mode that exists within an active region of a semiconductor **laser**. It is calculated as a ratio of the emission profile within the active region to the emission profile within the cavity.



Figure O.2 Optical microcavity.

optical lithography – a process for creating chemical patterns on a surface. Actually optical lithography is the dominant lithography technique. Using projection optics, the resolution depends on the source wavelength; decreasing the wavelength decreases the critical dimensions of the patterning. Using optical proximity corrections and phase-shifting masks, structures smaller than the critical dimensions can be created. Actually optical lithography reaches the 100 nm region. Extreme ultraviolet lithography is a natural continuation of conventional optical lithography toward smaller wavelengths. Masks are used at wavelengths in the range 10 to 15 nm and reflection optics. Using wavelengths of the order of 1 nm, X-ray proximity lithography represents the last step in the decrease of the photon wavelength for **nanolithography** technology.

optical microcavity – a structure confining electromagnetic radiation of a particular wavelength from the optical range. It is used to select and amplify a particular wavelength in light-emitting devices. The basic principle is that an optically active material or light-emitting structure is placed in an optical cavity where only a single photon mode has a spectral overlap with the emission band. Radiative recombination in the material can only take place in that photon mode. The emitted light has the spectral characteristics of the photon mode, that is it can be extremely narrow as determined by the photon lifetime in the cavity. The fate of all electron–hole pairs not matching the energy and the momentum of the mode photon is to either recombine nonradiatively or to reach the photon-matched states by momentum and energy relaxation before a nonradiative recombination takes place.

Semiconductor microcavity structures have simple one-dimensional implementation: one uses planar **Fabry–Pérot resonator**s where the mirrors are multi quarter wave stacks distributed **Bragg reflector**s as shown in Figure O.2.

The usual multi-pass **interference** description of the **Fabry–Pérot resonator** shows that the resonant photon mode for which all reflected waves in the cavity are in phase has an intensity increased by a factor $4/(1-R)$, where R is the mirror reflectivity. Conversely, those nonresonant photon modes are suppressed by a factor of about $(1-R)$. The cavity acts as if it concentrates the electric field from a nonresonant mode into the resonant mode. The net effect is therefore that the spontaneous lifetime has hardly changed, as long as efficient relaxation toward the photon-coupled electron hole state prevents a too strong **hole-burning** phenomenon.

optical phonon – a quantum of excitation related to an optical mode of atomic vibrations in solids → **phonon**.

optical tweezers – an instrument using light pressure, within a highly focused laser beam, to trap tiny objects. It can be used to manipulate micrometer-sized dielectric particles and individual molecules with nanometer precision and measure sub-piconewton forces, making it possible to explore areas of research previously inaccessible to experimental investigation. Optical tweezing was also used by S. Chu for cooling and trapping atoms. Currently, optical tweezers are emerging as one of the most powerful tools to study physical properties of biomolecules.

First described in: A. Ashkin, *Acceleration and trapping of particles by radiation pressure*, Phys. Rev. Lett. **24**, 156–159 (1970).

More details in: A. Ashkin, *Optical trapping and manipulation of neutral particles using lasers*, PNAS **94**, 4853–4860 (1997).

Recognition: in 1997 S. Chu shared with C. Cohen-Tannoudij and W. D. Phillips the Nobel Prize in Physics for development of methods to cool and trap atoms with laser light.

See also www.nobel.se/physics/laureates/1997/index.html.

optics – the science of the behavior of light.

OPW – an acronym for an **orthogonalized plane wave**.

orbital → **atomic orbital**.

organelle – a discrete part of a biological cell having specialized functions.

organic light-emitting diode (OLED) – a solid-state light-emitting device in which an organic material is used to generate light by passing an electric current through it. It has much in common with a semiconductor **light-emitting diode**, but where the active semiconductor region is replaced by an organic thin film or a stacked layer of such films. The organic molecules emit light when they are electrically excited.

First described by C. W. Tang, US Patent 4356429 (1980).

organic radical battery – a new type of battery notable for its flexibility, rapid charging, and small size. Organic radical batteries are so named because, unlike traditional metal batteries, they use an organic radical **polymer** to produce energy. Developed by NEC Corporation in 2005.

organic solar cell = **polymer solar cell**.

organic spin valve – a **spin valve** that consists of a thin layer of an organic semiconductor sandwiched between two **ferromagnetic** electrodes. It has been demonstrated that the **spin relaxation time** in an organic **nanowire** spin valve is at least 1000 times longer than that reported in any other systems. These materials could be ideal for use in **spintronics**.

First described in: S. Pramanik, C.-G. Stefanita, S. Patibandla, S. Bandyopadhyay, K. Garre, N. Harth, M. Cahay, *Observation of extremely long spin relaxation times in organic nanowire spin valve,* Nature Nanotechnology **2**, 216–219 (2007).

organometallic compounds → **metal–organic compounds**.

orientation polarization → **polarization of matter.**

OR operator → **logic operator**.

orthogonal – perpendicular, or some concept analogous to it.

orthogonalized plane wave – a **plane wave** function made orthogonal to the atomic core functions.

orthogonalized-plane-wave method supposes solving the **Schrödinger equation** for electrons in an atom by building up the wave function out of only a few traveling plane waves, each constructed so as to be intrinsically orthogonal to the core functions. An expansion in terms of such orthogonalized plane waves does indeed exhibit vastly improved convergence properties over simple plane waves.

First described in: A. Sommerfeld, H. Bethe, *Handbuch der Physik*, Vol. 24 (Springer, Berlin, 1933) – the idea.

orthogonal transformation supposes that a linear transformation

$$y_1 = p_{11}x_1 + p_{12}x_2 + \ldots + p_{1n}x_n$$

$$y_2 = p_{21}x_1 + p_{22}x_2 + \ldots + p_{2n}x_n$$

$$\ldots$$

$$y_n = p_{n1}x_1 + p_{n2}x_2 + \ldots + p_{nn}x_n$$

for every choice of the argument x satisfies the relation

$$y_1^2 + y_2^2 + \ldots + y_n^2 = x_1^2 + x_2^2 + \ldots + x_n^2.$$

orthogonal wave functions (orbitals) – the **wave functions (orbitals)** for which the **overlap integral** is zero or more generally when

$$\int_a^b \psi_m(x)\psi_n(x)\mathrm{d}x = 0,$$

if $m \neq n$. Two different atomic orbitals on the same atom are always orthogonal.

orthohydrogen – the form of molecular hydrogen in which the nuclei of the atoms spin in the same direction. Its content in molecular hydrogen is about 75% at normal conditions. The rest is **parahydrogen**.

orthorombic lattice – a **Bravais lattice** in which the three axes of a unit cell are mutually perpendicular and two have not the same length. It is also known as a **rhombic lattice**.

oscillator strength – the dimensionless term introduced to characterize electron transitions from one energy state i to another energy state j. It is essentially the ‘‘number’’ of oscillators with frequency ω_{ji}:

$$f_{ij} = 2\frac{|P_{ij}|^2}{m\hbar\omega_{ji}} = 2h^2\frac{\left|\langle\psi_i|\partial/\partial x|\psi_j\rangle\right|^2}{m(E_i - E_j)}.$$

P_{ij} is the matrix element of the dipole, and m is the mass of the electron.

In fact, it is a dimensionless measure of the intensity of a spectral band: a classical concept (giving the effective number of electrons taking part in a certain transition) adapted to wave mechanics. It is defined as the ratio of the strength of atomic or molecular transition to the theoretical transition strength of a single electron using a harmonic-oscillator model.

oscillatory exchange coupling appears in a multilayer structure in which magnetic layers are separated by a nonmagnetic layer of a certain thickness. As a result, the orientation of the magnetic moments of the magnetic layers oscillates between parallel (**ferromagnetic**) and antiparallel (**antiferromagnetic**) as a function of the nonmagnetic layer thickness.

First described in: S. S. P. Parkin, N. More, K. P. Roche, *Oscillations in exchange coupling magnetoresistance in metallic surface structures: Co/Ru, Co/Cr and Fe/Cr,* Phys. Rev. Lett. **64**(19), 2304–2307 (1990).

osmosis – a spontaneous flow of a chemical species through a semi-permeable membrane from a region of high concentration to one of lower concentration. Semi-permeable membranes differ from ordinary membranes in that they are selective: they permit one or more types of molecular species to pass through but are impermeable to others.

Ostwald ripening – a growth of big islands in a thin film at the expense of the small ones.

First described in: W. Ostwald, *Lehrbuch der Allgemeinen Chemie,* vol. **2**, part 1 (Leipzig, 1896).

Overhauser effect – when a radio frequency field is applied to a substance in an external magnetic field, whose nuclei have spin 1/2 and which has unpaired electrons, at the electron spin resonance frequency, the resulting polarization of the nuclei is as great as if the nuclei had a much larger electron magnetic moment.

First described in: A. W. Overhauser, *Paramagnetic relaxation,* Phys. Rev. **89**(4), 689–700 (1953) – theoretical prediction; T. R. Carver, C. P. Slichter, *Polarization of nuclear spins in metals,* Phys. Rev. **92**(1), 212–213 (1953) – experimental confirmation.

overlap integral has the form $\int \psi(A)^* \psi(B) d\tau$. It is used as a measure of the extent to which two wave functions (orbitals) belonging to different atoms A and B overlap.

Ovshinsky effect – the characteristic of a particular thin-film solid-state switch that responds identically to both positive and negative polarities of the external voltage applied, so that the current can be made to flow in both directions equally.

First described in: S. R. Ovshinsky, *Reversible electrical switching phenomena in disordered structures,* Phys. Rev. Lett. **21**(20), 1450–1453 (1968).

oxide – a compound formed by an element with oxygen.

P

From PALM (photoactivable localization microscopy) to pyrrole

PALM – an acronym for **photoactivable localization microscopy**.

paraffins – saturated compounds of carbon and hydrogen of general formula C_nH_{2n+2}. The simplest examples are methane CH_4 and ethane C_2H_6.

parahydrogen – the form of molecular hydrogen in which the nuclei of the two atoms have spin in opposite directions. Its content in molecular hydrogen is about 25% at normal conditions. The rest is **orthohydrogen**.

First described in: K. F. Bonhoeffer, P. Harteteck, *Experimente über Para- und Orthowasserstoff*, Naturwiss. **17**, 182 (1929).

paramagnetic – a substance which in an external magnetic field demonstrates magnetization in the same direction as the field. The magnetization is proportional to the applied field → **magnetism**.

First described in: M. Faraday, *Experimental researches in electricity.–Twentieth Series*. Phil. Trans. **136**, 31–40 (1846), M. Faraday, *Experimental researches in electricity.–Twenty-first Series*. Phil. Trans. **136**, 41–62 (1846).

parity – a symmetry property of a wave function. The parity is 1 (or even) if the wave function is unchanged by an inversion (reflection with respect to the origin) of the coordinate system. It is −1 (or odd) if the wave function is only changed in sign. All degenerate states have a definite parity → **molecular orbital**.

parity conservation law states that if the wave function describing the initial state of a system has even (odd) parity, the wave function describing the final state has even (odd) parity. It is violated by the weak interactions.

PAS – an acronym for **positron annihilation spectroscopy**.

Paschen–Back effect – a change in the **Zeeman effect** arising as the strength of the external magnetic field reaches a certain critical value. A new complicated line pattern appears as soon as the magnetic separation reaches a value comparable with the natural separation of doublet or triplet lines. Under these conditions the coupling between orbital spin angular momentum of the electrons is reduced, the new lines being predominantly due to transitions between energy levels of electron orbits.

First described in: F. Paschen, E. Back, *Normale und anomale Zeemaneffekte,* Ann. Phys. **39**(5), 897–932 (1912).

Paschen series → **Rydberg formula**.

First described in: F. Paschen, *Zur Kenntnis ultraroter Linienspektra. I. (Normalwellenlängen bis 27000 Å.-E.),* Ann. Phys. **332**(13), 537–570 (1908).

Pauli exclusion principle states that there can never exist two or more equivalent electrons in the atom for which the values of all quantum numbers coincide.

First described in: W. Pauli, *Über den Zusammenhang des Abschlusses der Elektronengruppen im Atom mit der Komplexstruktur der Spektren,* Z. Phys. **31**(10), 765–783 (1925).

Recognition: in 1945 W. Pauli received the Nobel Prize in Physics for the discovery of the Exclusion Principle, also called the Pauli Principle.

See also www.nobel.se/physics/laureates/1945/index.html.

Pauling rule states that the number of ions of opposite charge in the neighborhood of a given ion in an **ionic crystal** is in accordance with the requirement of local electrical neutrality of the structure.

First described in: L. Pauling, *The principles determining the structure of complex ionic crystals,* J. Am. Chem. Soc. **51**(4), 1010–1026 (1929).

More details in: L. Pauling, *The Nature of the Chemical Bond and the Structure of Molecules and Crystals; An Introduction to Modern Structural Chemistry* (1960).

Recognition: in 1954 L. Pauling received the Nobel Prize in Chemistry for his research into the nature of the chemical bond and its application to the elucidation of the structure of complex substances.

See also www.nobel.se/chemistry/laureates/1954/index.html.

Pauli principle → **Pauli exclusion principle**.

Pauli spin matrices arise with the introduction of electron spin into nonrelativistic wave mechanics. The wave function ψ of a single-electron system is then a function not only of time t and position $\mathbf{r}$, but also of an additional variable σ. This spin variable is not permitted to vary continuously like the others, but is restricted to the two values, ± 1. The principal attitude of spin is of course angular momentum. It is necessary to have operators $\hbar s_x, \hbar s_y, \hbar s_z$ of spin angular momentum corresponding to the orbital angular momentum operators like

$$\hbar l_x = -\mathrm{i}\hbar \left(y\frac{\partial}{\partial z} - z\frac{\partial}{\partial y} \right).$$

It is found that the required operators can be defined by the equations:

$$\boldsymbol{\sigma}_\mathbf{x}\psi(\sigma, \mathbf{r}, t) = \psi(-\sigma, \mathbf{r}, t)$$
$$\boldsymbol{\sigma}_\mathbf{y}\psi(\sigma, \mathbf{r}, t) = -\mathrm{i}\sigma\psi(-\sigma, \mathbf{r}, t)$$
$$\boldsymbol{\sigma}_\mathbf{z}\psi(\sigma, \mathbf{r}, t) = \sigma\psi(\sigma, \mathbf{r}, t)$$

Now instead of regarding ψ as an ordinary function with an additional argument σ, one may equally regard it as a two-component function of the old variables:

$$\psi(\sigma, \mathbf{r}, t) \equiv \begin{pmatrix} \psi_1(\mathbf{r}, t) \\ \psi_2(\mathbf{r}, t) \end{pmatrix}, \quad \text{where} \quad \psi_1(+1, \mathbf{r}, t), \psi_2(-1, \mathbf{r}, t).$$

When arranged as in the last equation, the two components form a column vector, and also (in the present connection) a **2-spinor**. The column vector resulting when is operated on by σ_x, σ_y or σ_z, will have components, which are linear combinations of the originals, and may therefore be obtained by multiplying the original vector by a matrix. The matrix representations are:

$$\sigma_\mathbf{x} \equiv \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}, \quad \sigma_\mathbf{y} \equiv \begin{pmatrix} 0 & -\mathrm{i} \\ \mathrm{i} & 0 \end{pmatrix}, \quad \sigma_\mathbf{z} \equiv \begin{pmatrix} 1 & 0 \\ 0 & -1 \end{pmatrix}.$$

These are the Pauli matrices. Among their properties is that of forming, together with the unit matrix, a complete set as a linear combination of which any other 2 × 2 matrix can be expressed. They also, either as matrices or operators, satisfy the important algebraic relations:

$$\sigma_x\sigma_y = -\sigma_y\sigma_x = \mathrm{i}\sigma_z$$
$$\sigma_y\sigma_z = -\sigma_z\sigma_y = \mathrm{i}\sigma_x$$
$$\sigma_z\sigma_x = -\sigma_x\sigma_z = \mathrm{i}\sigma_y$$

First described in: W. Pauli, *Zur Quantenmechanik des magnetischen Elektrons,* Z. Phys. **43**(9/10), 601–623 (1927).

Paul trap – a device for the dynamic stabilization of free ions. It was originally named *Ionenkäfig*, German for ion trap. The trap allows observations of isolated ions, even a single one, over a long period of time, thus enabling measurements of their properties with extremely high accuracy. The potential configuration of the trap is generated by a structure consisting of two parts, as schematically shown in Figure P.1.

The first part is given by a hyperbolically shaped ring, whose symmetry is about the $x - y$ plane at $z = 0$. The inner surface of the ring electrode is a time-dependent electrical equipotential surface. Then one has two hyperbolic rotationally symmetric end caps. The distance form the origin to the ring focus of the hyperboloid is d, whereas the distance from the origin to the focuses of the two hyperbolic caps



Figure P.1 Schematic view of the Paul trap (a) and a cross section of the first Paul trap (1955) (b). After W. Paul, *Electromagnetic traps for charged and neutral particles*, Rev. Mod. Phys. **62**(3), 531–540 (1990).

is usually the square root of *d*. The two end cap surfaces are time-dependent equipotential surfaces with a sign opposite to that of the ring. The electrical field in the trap is thus a quadrupole field. Through the application of oscillatory potential, one can obtain the dynamic stabilization of a charged particle.

The dynamic stabilization of ions in the Paul trap can be easily understood through a mechanical analog, due to Paul himself. The equipotential lines in the trap form a saddle surface. A mechanical ball is put at the center of the surface. With no motion of the surface, the ball will fall off. However, rotating the saddle with an appropriate frequency about the axis normal to the surface renders the ball stable. The ball makes small oscillations and can be kept stable over a long time.

First described in: W. Paul, H. Steinwedel, Z. Naturforschung Teil A **8**, 448 (1953); W. Paul, H. Steinwedel. German Patent No. 944 900; US Patent 2939958 (1953).

More details in: W. Paul, *Electromagnetic traps for charged and neutral particles,* Rev. Mod. Phys. **62**(3), 531–540 (1990).

Recognition: in 1989 W. Paul shared the Nobel Prize in Physics with H. Dehmelt for the development of the ion trap technique.

See also www.nobel.se/physics/laureates/1989/index.html.

PCR – an acronym for a **polymerase chain reaction.**

peak-to-valley ratio → **resonant tunneling.**

Peierls gap → **Peierls transition**.

Peierls–Nabarro force – the force required to displace a dislocation along its slip plane.

First described in: R. Peierls, *The size of a dislocation*, Proc. R. Phys. Soc. **52**, 34–37 (1940); F. R. N. Nabarro, *Dislocations in a simple cubic lattice*, Proc. R. Phys. Soc. **59**, 256–272 (1947).

Peierls temperature → **Peierls transition**.

Peierls transition – a structural distortion or phase transition in solids driven by nonuniformities in the electron distribution resulting from electron–phonon interactions. It is characterized by the **Peierls temperature** T_P.

Below this temperature, either a dimerization into two sets of unequal interparticle distances d_1 and d_2, such that the result is $d = d_1 + d_2$, or some other structural distortions must take place. The electronic energy of the atomic chain is lowered by the formation of charge density waves. Their X-ray signature is diffuse reflection similar to thermal diffuse scattering streaks in a reciprocal lattice. This phase transition opens up an energy gap, called the **Peierls gap**, in the dispersion relation for the energy. Below T_P, the locked (static) charge density wave of the conduction electrons at $2k_F$ or $4k_F$, where k_F is the **Fermi wave vector**, couples with the other atomic or molecular electrons in the lattice. The resulting slight lattice distortions cause extra X-ray reflection peaks.

The Peierls distortion disrupts the periodicity in the lattice and can transform a metal (above T_P) into a semiconductor or insulator (below T_P).

First described in: R. Peierls, *On Ising's model of ferromagnetism*, Proc. Camb. Phil. Soc. **32**, 477–481 (1936).

More details in: R. E. Peierls, *Quantum Theory of Solids* (Clarendon, Oxford, 1955).

Pekar mechanism – the appearance of an effective A.C. electric field and related additional coupling of acoustic **phonon**s with **electron**s in crystalline solids in the presence of an external electric field. It is associated with the dependence of dielectric permittivity of the materials on the strain. This mechanism of the electron–phonon interaction is related directly to the **electrostriction** effect. The induced A.C. electric field has a piezo-like dependence on the phonon wavevector and can roughly be characterized by an effective piezo-constant $\beta_{eff} \sim \epsilon^2 Ep$, where ϵ is the dielectric permittivity of the unstrained crystal, E is the external electric field, and p is the photoelasticity constant.

The mechanism is essential only for materials having very large ϵ. In bulk semiconductors it appears only in a current-carrying state. In nanostructures, however, much stronger perpendicular electric fields are often encountered, which do not cause current and, on the other hand, make the Pekar interaction essential even in materials having ordinary dielectric parameters.

First described in: S. I. Pekar, *Electron–phonon interaction proportional to the external applied field and sound amplification in semiconductors,* Zh. Eksp. Teor. Fiz. **49**(2), 621–629 (1965) – in Russian, Sov. Phys. JETP **22**(2), 431–438 (1966); A. A. Demidenko, S. I. Pekar, V. N. Piskovoi, B. E. Tsekvava, *Voltage current curve of a semiconductor with electron–phonon coupling proportional to the applied field,* Zh. Eksp. Teor. Fiz. **50**(1), 124–130 (1966) – in Russian, Sov. Phys. JETP **23**(1), 84–89 (1966).

Peltier coefficient → **Peltier effect.**

Peltier effect – heat liberation or absorption when electric current flows across a junction composed of two different materials, as shown in Figure P.2.

When two different materials, such as conductors or semiconductors, are joined at two points to make a closed circuit and an electric current is passed round this circuit, heat is evolved at one of the junctions and absorbed at the other. The heat produced or absorbed per a unit area of the junction is given by the product of the current density and the **Peltier e.m.f.** (e.m.f. = electromotive force), also called the **Peltier coefficient**, which is a characteristic of the materials in question.

First described in: J. C. Peltier, *Nouvelles experiences sur la caloricité des courants electriques,* Ann. Chim. Phys. (2nd Ser.) **56**, 371–386 (1834).



Figure P.2 Schematic view of the Peltier effect.

Peltier e.m.f – Peltier electromotive force → **Peltier effect.**

Penn gap – an average energy gap used in calculations of the wave-number-dependent **dielectric function**. It arises in the isotropic version of the nearly free electron model in which both **Bragg reflections** and **Umklapp processes** were included. The dielectric function depends only on this parameter, which can be determined from optical data. Note that for small wave numbers Umklapp processes give the major contribution to the dielectric function, whereas for large wave numbers normal processes dominate.

First described in: D. R. Penn, *Wave number dependent dielectric function of semiconductors,* Phys. Rev. **128**(5), 2093–2097 (1962).

Penning ionization – the ionization of gas atoms or molecules in collisions with metastable atoms.

First described in: F. M. Penning, *Über Ionisation durch metastabile Atome*, Naturwiss. **15**, 818 (1927).

Penning trap – a quadrupole trap for charged particles schematically shown in Figure P.3. If one applies to the trap only a D.C. voltage such that ions perform stable oscillations in the z direction, the ions are unstable in the $x - y$ plane. Through the application of a magnetic field in the axial direction, the z motion remains unchanged but the ions perform a cyclotron motion in the $x - y$ plane because of the **Lorentz force** directed towards the center. This force is partially compensated by the radial electric force. As long as the magnetic force is much larger than the electric one, there is stability also in the $x - y$ plane.

The main difference between the Penning trap and the **Paul trap** is the use of static fields in order to confine charged particles. This helps in overcoming the problem called "*rf* heating" in the Paul traps, thus allowing laser cooling. In 1973, H. Dehmelt succeeded in observing for the first time a single electron in such a trap.

First described in: F. M. Penning, *Introduction of an axial magnetic field in the discharge between two coaxial cylinders*, Physica **3**, 873–894 (1936).

More details in: H. Dehmelt, *Experiments with an isolated subatomic particle at rest*, Rev. Mod. Phys. **62**(3), 525–530 (1990).

Recognition: in 1989 H. Dehmelt shared with W. Paul the Nobel Prize in Physics for the development of the ion trap technique.

See also www.nobel.se/physics/laureates/1989/index.html.


z, $\bar{B}_0$
Negative charge – Q/2 on upper cap
y
Positive charge + Q on ring
x
Electron orbit
Negative charge – Q/2 on lower cap

Figure P.3 Penning trap. The simplest motion of an electron in the trap is along its symmetry axis, along a magnetic field line. Each time it comes too close to one of the negatively charged caps it turns around, originating harmonic oscillations. After H. Dehmelt, *Experiments with an isolated subatomic particle at rest*, Rev. Mod. Phys. **62**(3), 525–530 (1990).

peptide – a natural or synthetic compound containing two or more **amino acids** linked by the **carboxyl** group of one amino acid to the amino group of another.

peptide bond – the C–N chemical bond formed between two molecules containing a **carboxyl** group and an **amino** group as shown in Figure P.4.

A molecule of water is released in the reaction. This is a dehydration synthesis reaction usually occurring between **amino acids**. The resulting molecule is called an **amide**.

The bond has a partial double bond character (with the nitrogen atom attaining a partial positive charge and the oxygen atom a partial negative charge) and the molecule can normally not rotate around this bond. The whole arrangement of the four C, O, N, H atoms as well as the two attached carbons in a peptide bond is planar.



Figure P.4 Formation of the peptide bond in the dehydration synthesis reaction.

peritectic – a crystalline structure of certain binary alloys in which a secondary crystal formed during cooling envelops the primary crystal and prevents its contact with the melt. As a result, the structure is not in equilibrium and does not obey the phase rule.

permanent spectral hole-burning → **spectral hole-burning.**

permanganate – a salt of the general formula $XMnO_4$, where X is monovalent.

permeability (absolute permeability of medium) – the ratio of the magnetic flux density B to the magnetizing force H applied to the medium: $\mu = B/H$.

permittivity (absolute permittivity of a medium) = dielectric constant of a medium – the ratio of the electric displacement D in the medium to the strength of the electric field E applied: $\epsilon = D/E$. It is a measure of the ability of the medium to be polarized → **polarization**.

perovskite structure – a structure of cubic symmetry possessed by crystals with chemical composition ABO_3. Typical examples are $CaTiO_3$ (perovskite) and $BaTiO_3$ (above 120 °C).

peroxide – a compound containing an oxygen–oxygen single bond per molecule thus forming O_2^{2-} anion. Among inorganic compounds hydrogen peroxide (H_2O_2) and sodium peroxide (Na_2O_2) are typical examples. In organic chemistry peroxides contain a specific functional group or a molecule with an oxygen–oxygen single bond (R–O–O–R′).

Peroxides are powerful oxidizers, and usually fairly unstable. Ionic peroxides react with water and diluted acids to form hydrogen peroxide. Organic compounds are oxidized to carbonates, even at normal temperatures.

persistent reversible hole-burning → **spectral hole-burning.**

Persson–Tosatti model studies the influence of surface roughness on the **adhesion** of elastic solids. Most real surfaces have roughness on many different length scales, and this fact is taken into account in the analysis. Considering in detail the case when the surface roughness can be described as a self-affine **fractal**, one can show that when the fractal dimension $D_f > 2.5$, the adhesion force may vanish, or be at least strongly reduced.

First described in: B. N. J. Persson and E. Tosatti, *The effect of surface roughness on the adhesion of elastic solids*, J. Chem. Phys. **115**(12), 5597–5610 (2001).

perturbation method – an approximate solution of equations for a complicated system by first solving the equations for another similar system, chosen so that its solution is relatively easy, and then considering the effect of small changes or perturbations on this solution.

Pettifor map – a heuristic scheme that assigns a numerical chemical scale value to each element allowing a binary alloy A_xB_y to be mapped on Cartesian axes of the chemical scales for element A and element B. Alloys with similar stable structure will cluster together in the map, so the unknown stable structure for a new alloy system can be predicted by examining the stable structures of its nearby neighbours.

First described in: D. G. Pettifor, *Structure maps for pseudobinaries and ternary phases*, Mater. Sci. Technol. **4**(8), 675–691 (1988).

More details in: http://www.tothcanada.com/PettiforMaps/.

phage → **virus**.

phase coherence length – a distance over which the electron maintains its phase memory.

phase velocity → **wave packet**.

phenols – a class of organic compounds that have a hydroxy group (–OH) attached to an **aromatic ring** (benzene ring).

Phillips model describes electron space distribution in covalent crystals with point charges localized at midpoints of covalent bonds. It is used for simulation of an interatomic interaction.

First described in: J. C. Phillips, *Covalent bond in crystals,* Phys. Rev. **166**(3), 832–838, 917–921 (1968).

phonon – a quantum of lattice vibrations. Phonons have a wave-like nature that allows them to be described in terms of wave mechanics. Four different modes of the vibrations are distinguished, as illustrated in Figure P.5.

Two modes characterized by the neighboring atoms to vibrate in phase are called acoustic, and consequently the phonons are acoustic phonons. In the **longitudinal acoustic mode**, abbreviated as LA, the atomic displacements are in the same direction as the direction of the energy transfer (**k**-vector direction). In the **transverse acoustic mode**, abbreviated as TA, the atomic displacements are perpendicular to this direction.

Two other modes with the displacements of neighboring atoms in opposite phase are called optical, with optical phonons representing them. They can be **longitudinal optical** (LO) and **transverse optical** (TO). In polar crystals a long-wavelength longitudinal optical phonon involves uniform displacement of the charged atoms within the primitive cell. Such relative displacement of oppositely charged atoms generates a macroscopic electric field. This electric field can then interact with electrons which is known as the **Fröhlich interaction**. The ratio of LO and TO phonon frequencies (ω_L and ω_T) is governed by the **Lyddane–Sachs–Teller** relation $\omega_L/\omega_T = (\epsilon_0/\epsilon_\infty)^{1/2}$, where ϵ_0 and ϵ_∞ are respectively low- and high-frequency dielectric constants of the material (high frequency supposes that it is much higher than the vibrational frequencies but below the frequency corresponding to electronic excitation energy). Optical lattice vibrations coinciding with an electric dipole moment are called **polar optical phonons**. As quantum



Figure P.5 Atomic displacements in solids.

particles, phonons belong to bosons, so their energy distribution follows the **Bose–Einstein statistics**.

First described in: J. Frenkel, *Wave Mechanics* (Clarendon, Oxford, 1932), p. 267.

phosphide – a compound of a metal with phosphorus in which phosphorous exerts a valency of three.

phosphite – a salt of dibasic phosphorous acid (H_3PO_3 or $HPO(OH)_2$).

phospholipids → **lipids**.

phosphor = **luminophor**.

phosphorescence – classically the continuous emission of a characteristic radiation by a substance after (usually after 10^{-8} s) an excitation. In today words, it is the light emission caused by a spin-forbidden radiative deactivation of **excited state**s.

photoactivable localization microscopy (PALM) → **fluorescence nanoscopy**.

First described in: E. Betzig, G. H. Patterson, R. Sougrat, O. W. Lindwasser, S. Olenych, J. S. Bonifacino, M. W. Davidson, J. Lippincott-Schwartz, H. F. Hess, *Imaging intracellular fluorescent proteins at nanometer resolution*, Science **313**, 1642–1645 (2006); S. T. Hess, T. P. K. Girirajan, M. D. Mason, *Ultra-high resolution imaging by fluorescence photoactivation localization microscopy*, Biophys. J. **91**(11), 4258–4272 (2006).

photochemistry – the study of chemical reactions induced by light.

photoconduction – electrical conduction produced in a solid by the influence of light (from ultraviolet to infrared).

photodissociation – dissociation of chemical compounds into simpler molecules or free atoms by the action of light (from ultraviolet to infrared).

photoelectric effect – a change of electronic properties of a substance subjected to irradiation with light. It can be external, when an ejection of electrons from a solid surface being irradiated takes place, or internal, when the substance being irradiated changes its internal electronic properties. The external photoelectric effect is also called photoemission.

First described in: H. Hertz, *Über einen Einfluss des ultravioletten Lichtes auf die electrische Entladung*, Ann. Phys. (Leipzig) **31**, 293 (1887). First described quantum mechanically in: A. Einstein, *Zur allgemeinen molekularen Theorie der Wärme*, Ann. Phys. **14**, 354–362 (1904), A. Einstein, *Über einen die Erzeugung und Verwandlung des Lichtes betreffenden heuristischen Gesichtspunkt*, Ann. Phys. **17**, 132–148 (1905).

Recognition: in 1921 A. Einstein received the Nobel Prize in Physics for his services to Theoretical Physics, and especially for his discovery of the law of the photoelectric effect.

See also www.nobel.se/physics/laureates/1921/index.html.

photoemission – a process in which a photon is absorbed by a solid and an electron is emitted. The photoemitted electron escapes the solid with a maximum energy $E = h\nu - E_I$, where ν is the frequency of the photon and E_I is the photothreshold (or ionization) energy.

photoluminescence – light emission from semiconductors and dielectrics excited by photons of energies higher than their band gaps. The emitted photons have energies lower than the excitation photons, which is the **Stokes law of photoluminescence**.

photon – a particle representing one quantum of light. It has the energy $E = h\nu$, where ν is the frequency of the radiated energy. The rest mass of a photon is zero.

First described in: A. Einstein, *Über einen die Erzeugung und Verwandlung des Lichtes betreffenden heuristischen Gesichtspunkt*, Ann. Phys. **17**, 132–148 (1905); A. Einstein, *Strahlungs-Emission and Absorption nach der Quantentheorie*, Verh. Dtsch. Phys. Ges. **18**, 318–323 (1916); A. Einstein, *Zur Quantentheorie der Strahlung*, Phys. Z. **18**, 121–128 (1917).

photonic crystal – a structure with a periodic space modulation of dielectric function with a period of the photon wavelength. Formation of allowed bands of particle states and appearance of the forbidden band gap in between, which is well known for conventional solids, is not due to the charge carried by an electron but is basically the common property of all waves in a periodic potential. In the case of optical waves, space modulation of the refractive index is an analog of electrostatic potential in the case of electrons. Simple examples of photonic crystals of different dimensionality are shown in Figure P.6.

The photon **density of states** is significantly modified when alternating layers, needles or balls are arranged in a one-, two-, or three-dimensional lattice, respectively. The terms ''one-, two- or three-dimensional'' refer to the fact that the structure has a periodic change in the refractive index in the indicated number of directions–one, two or three.



Figure P.6 Photonic crystals.

A one-dimensional photonic crystal is nothing else but a well-known dielectric mirror with alternating $\lambda/2$ layers. Because of the Bragg condition → **Bragg equation**, certain wave numbers are relevant to standing waves. These waves have to be reflected backward because they cannot propagate throughout the medium. A photonic band gap corresponding to the forbidden wavelength is formed, as illustrated in Figure P.7.

If the structure consists of alternating layers of two materials with different refraction indices n_1 and n_2 with the same thickness $a/2$, the band gap appears at wave numbers $k_m = m\pi/a$, where m is an integer. The larger ratio n_1/n_2 corresponds to a wider photonic band gap. Because of the periodicity of the structure, wave numbers differing by $2m\pi/a$ are equivalent. Thus, the photonic band structure can be presented in the reduced form, as in the right-hand plot, in the wave number interval from $-\pi/2$ to $+\pi/2$, which is the first Brillouin zone for photons. Photonic band gaps in two- and three-dimensional photonic crystals are formed under the same regularities.

A photonic crystal is an optical analogy of a periodic crystal potential for electrons, in which the role of the potential for light is played by the lattice of macroscopic dielectric media instead of atoms. If the dielectric constants of the materials forming the lattice are different enough, and the absorption of light by the material is minimal, then scattering at the interface can produce many of the same phenomena for photons as the atomic potential does for electrons.

First described in: E. Yablonovitch, *Inhibited spontaneous emission in solid-state physics and electronics*, Phys. Rev. Lett. **58**(20), 2059–2062 (1987); S. John, *Strong localization of photons in certain disordered dielectric superlattices*, Phys. Rev. Lett. **58**(23), 2486–2489 (1987).

More details in: J. D. Joannopoulos, R. D. Meade, J. N. Winn, *Photonic Crystals* (Princeton University Press, Princeton, 1995).



Figure P.7 Energy wave number relations demonstrating formation of the photonic band gap in a one-dimensional photonic crystal. S. V. Gaponenko, *Optical Properties of Semiconductor Nanocrystals* (Cambridge University Press, Cambridge, 1998).

photonic stopband → **distributed Bragg reflector**.

photorefractive effect – a change in the refractive index of medium as a function of the light intensity. Materials possessing such a property are called **photorefractive materials**.

First described in: S. J. Wawilov, W. L. Lewschin, *Die Beziehungen zwischen Fluoreszenz und Phosphoreszenz in festen und flüssigen Medien,* Z. Phys. **35**, 920–936 (1926).

photorefractive materials → **photorefractive effect**.

photovoltaic cell = **solar cell**.

photovoltaic effect – generation of electric current in materials or structures exposed to light.

First described in: E. Becquerel, *Mémoire sur les effets électriques produits sous les influences des rayons solaires,* C.R. **9**, 561–567 (1839).

phthalocyanine – a macrocyclic compound having an alternating nitrogen atom –carbon atom ring structure shown in Figure P.8.

The molecule is able to coordinate hydrogen and metal cations in its center by coordinate bonds with the four isoindole nitrogen atoms. The central atoms can carry additional ligands. Most of the elements have been found to be able to coordinate to the phthalocyanine macrocycle. Therefore, a variety of phthalocyanine complexes exist. Phthalocyanines are highly colored compounds which have found widespread commercial application.

More details in: A. L. Thomas, *Phthalocyanine Research and Applications* (CRC, 1990).



Figure P.8 A phthalocyanine molecule. M = Me (Ni, Co, Cu, Fe, Zn), 2H.

physisorption – an **adsorption** process characterized by weak **van der Waals forces** between adsorbed atoms and substrate atoms at the adsorbing surface.

pi or π theorem → **Buckingham's theorem**.

pico- – a decimal prefix representing 10^{-12}, abbreviated p.

piezoelectric – a material (usually dielectric) in which an electric charge is induced when it is subjected to pressure or tension in certain directions. A converse effect is also observed, that is if an external electric field is applied to a sample made of such material, the mechanical strain is induced in it leading to the change of its size.

First described in: J. Curie, P. Curie, *Sur l'électricité polaire dans les cristaux hémièdres à faces inclinées*, C. R. **91**, 294–295 (1880).

pink noise = flicker noise = $1/f$ noise.

pixel – contraction of "picture element." A small element of a scene, often the smallest resolvable area, in which an average brightness value is determined and used to represent that portion of the scene. Pixels are arranged in a rectangular array to form a complete image.

Planck law states that energy associated with electromagnetic radiation is emitted or absorbed in a discrete amount, which is proportional to the frequency of radiation.

First described in: M. Planck, *Zur Theorie des Gesetzes der Energieverteilung im Normalspektrum*, Verh. Dtsch. Phys. Ges. **2**, 237–245 (1900).

Recognition: in 1918 M. Planck received the Nobel Prize in Physics in recognition of the services he rendered to the advancement of Physics by his discovery of energy quanta.

See also www.nobel.se/physics/laureates/1918/index.html.

Planck length → **Planck scale**.

Planck mass → **Planck scale**.

Planck's radiation formula (for energy distribution) determines the energy density irradiated by a black body at the temperature T in the range from λ to $\lambda + d\lambda$ as:

$$dU = \frac{8\pi hc}{\lambda^5}\left[\exp\left(\frac{hc}{\lambda k_B T}\right) - 1\right]^{-1} d\lambda.$$

First described in: M. Planck, *Zur Theorie des Gesetzes der Energieverteilung im Normalspektrum*, Verh. Dtsch. Phys. Ges. **2**, 237–245 (1900).

Planck scale – the scale at which the gravitational interaction between individual particles becomes as strong as other interactions. At this scale, the description of sub-atomic particle interactions in terms of quantum field theory breaks down because of the nonrenormalizability of gravity.

The scale is represented by the energy scale of about 1.22×10^{19} GeV (corresponding to the **Planck mass** $m_P = (hc/2\pi G)^{1/2} = 2.2 \times 10^{-5}$ g), **Planck length** of 1.616×10^{-35} m calculated as $L_P = (hG/2\pi c^3)^{1/2}$ and **Planck time** of 5.4×10^{-44} s calculated as $t_P = (hG/2\pi c^5)^{1/2}$. Here G is the constant of gravitation.

At the Planck scale, the strength of gravity is expected to become comparable to the other forces, and it is theorized that all the fundamental forces are unified at that scale, but the exact mechanism of this unification remains unknown.

Planck time → **Planck scale**.

plane wave – a wave which is constant in any plane perpendicular to the direction of the wave propagation and periodic along the lines parallel to the direction of the wave propagation.

plasmon – a quantum of plasma oscillation arising as a result of collective excitation in a plasma-like system composed of positive ions and virtually free electrons.

plasmonic effects based solar cell – **solar cell**, in which metal nanoparticles are deposited onto its surface such that the surface **plasmon** can be excited in the nanoparticles layer. Such surface plasmon excitation results in large electromagnetic field enhancement near the metal surface where the absorption of photons increases. Nanoparticles can be varied in shape and size to enhance the absorption of a photon.

First described in: O. Stenzel, A. Stendal, K. Voigtsberger, C. von Borczyskowski, *Enhancement of the photovoltaic conversion efficiency of copper phthalocyanine thin film devices by incorporation of metal clusters,* Solar Energy Materials and Solar Cells **37**, 337–348 (1995).

Pockels effect – a change in the refractive properties of certain crystals in an applied electric field, which is proportional to the strength of the field.

First described in: F. Pockels, *Über den Einfluss des electro-statischen Feldes auf das optische Verhalten piezoelektrischer Kristalle,* Abh. Göttingen Ges. Wiss., Math. Physik. Kl. **39**, 1–204 (1893).

Poincaré sphere – the model construction used for the representation of light polarization. The Stokes coordinate system is used for this. The **Stokes parameters** S, Q, U, and V are real numbers, directly related to the intensity of light:

$$S = I_x + I_y = I$$
$$Q = I_x - I_y$$
$$U = I_{45^\circ} - I_{-45^\circ}$$
$$V = I_{LCP} - L_{RCP}.$$

Here S is the total intensity of light, Q is the difference in intensity between horizontal and vertical linearly polarized components, U is the difference in intensity between linearly polarized components oriented at $+45^\circ$ and -45°, and V is the difference between the intensity of left and right circularly polarized light.

The Stokes parameters are measurable quantities. For completely polarized light one has:

$$Q^2 + U^2 + V^2 = S^2.$$

For entirely unpolarized light:

$$Q^2 + U^2 + V^2 = 0.$$

Thus, it is possible to identify the parameters Q, U and V as the coordinates of a point of a sphere with radius corresponding to the intensity of the polarized part as illustrated in Figure P.9.

On the Poincaré sphere, each point represents a specific polarization state. Points on the equator define linearly polarized states, south and north poles represent left and right circularly polarized states. Points on the lower and upper hemisphere denote the degree of left and right elliptically polarized states. Any pair of antipodal points on the sphere defines states with orthogonal polarization.

First described in: G. G. Stokes, *On the composition and resolution of streams of polarized light from different sources*, Trans. Camb. Phil. Soc. **9**, 399–423 (1852) – Stokes parameters were introduced; H. Poincaré, *Theorie Mathématique de la Lumiére*, Georges Carrié Ed. Paris 1892, Vol. 2, Chap. 12, pp. 275–285 – the sphere was described.



Figure P.9 The Poincaré sphere and the Stokes coordinate system. The point *P* lies on the surface of the sphere and represents a given polarization state.

point group – a collection of symmetry operations which, when applied about a point in the crystal, will leave the crystal structure invariant. It does not contain any translation operations.

More details in: G. F. Koster, J. O. Dimmock, R. G. Wheeler, H. Statz, *Properties of the Thirty-two Point-Groups* (MIT Press, Cambridge, MA, 1963).

Poisson distribution – a probability distribution whose mean and variance have a common value k and whose frequency is $f(n) = k^n \exp(-k)/n!$ for $n = 0, 1, 2, \ldots$

First described in: S. D. Poisson, *Recherches sur la Probabilité des Jugements en Matière Criminelle et en Matière Civile*, Paris (1837).

Poisson equation $\nabla^2\phi = f(x, y, z)$. It occurs in electrostatics, where ϕ is the potential due to a charge distribution of volume density ρ and $f(x, y, z) = -4\pi\rho$. Poisson's equation reduces to the **Laplace equation** when $\rho = 0$.

First described in: S. D. Poisson, *Remarques sur une équation qui se présente dans la théorie des attractions des sphéroïdes*, Nouveau Bull. Soc. Philomathique de Paris **3**, 388–392 (1813).

polariton – a quantum **quasiparticle** formed by **exciton–photon coupling**. In fact, it is an oscillation of the elastically vibrating crystal lattice coupled to the electromagnetic field. Being part light, part matter, polaritons possess new properties that are not seen in either excitons or photons. An exciton combined with a photon can produce a high-energy polariton, also called the upper polariton, or a low-energy one called the lower polariton.

polarization of light is determined by the direction of the electric field vector, disregarding the magnetic field since it is almost always perpendicular to the electric field. The light can be linearly, circularly or elliptically polarized.

The light is said to be **linearly polarized** if the direction of oscillation of the electric field E is fixed. There are two possible linear polarization states, with their E fields orthogonal to one another. Any other angle of linear polarization can be constructed as a superposition of these two states. The direction of polarization is arbitrary with respect to the light itself. It is usual to label the two linear polarization states in accordance with some other external reference. For example, the terms horizontally and vertically polarized are generally used when light is propagating in free space. If the light is interacting with a surface, the terms s- and p-polarized are used in order to identify sagittal plane and tangential plane polarization, respectively.

The light is said to be **circularly polarized** if the direction of the electric field E is not fixed, but rotates as the light propagates. Two possible independent circular polarization states exist, termed left-hand or right-hand circularly polarized depending on whether the electric field is rotating in a counter-clockwise or clockwise sense, respectively, when looking in the direction of the light propagation.

Elliptical polarization is a combination of circular and linear polarization.

polarization of matter – a separation of positive and negative charge barycentres of bound charges forming electric dipoles. A macroscopic polarization of matter is defined by the vector sum of the individual dipole moments of atoms, molecules, ions and bigger charged atomic particles constituting the matter. An individual dipole moment is $\mathbf{p} = \alpha E_{loc}$, where α is the polarizability and E_{loc} is the local electric field at the site of the polarizing particle.

Four main mechanisms of polarization are distinguished in solids:

1. **Electronic polarization** is related to the displacement of the negatively charged electron shell of an atom against the positively charged nucleus. It is typical for dielectrics. The electronic polarizability is approximately proportional to the volume of the electron shell. It is practically temperature independent.
2. **Ionic polarization** takes place in materials with ionic bonds when positive and negative ion sublattices are displaced with respect each other by an electric field. The ionic polarizability is usually weakly positive because of the thermal expansion of the lattice.
3. **Orientation polarization** appears due to an alignment of permanent dipoles in matter when an electric field is applied. The average degree of orientation is a function of the applied field and temperature. The mean polarizability in this case is given by $< \alpha >= p^2/3k_bT$, where p is the value of the permanent dipole moment. The strong temperature dependence of this mechanism is its fingerprint.
4. **Space charge polarization** is a polarization effect in a dielectric material with spatial inhomogeneities of charge carrier densities. It also occurs in ceramics with electrically conducting grains and insulating grain boundaries, which is called **Maxwell–Wagner polarization**, and in composite materials in which metallic particles are isolated in polymer or glass matrices.

polarizer – an optical device that transmits the component of incident light having an electric field vector parallel to the transmission axis of the device.

polar molecule – a molecule composed of negatively charged electrons and positively charged nuclei in a state of vibration about certain fixed points in space.

polaron – an equilibrium assembly of an electron or a hole and the polarization field it induces in a solid.

First described in: L. D. Landau, *Über die Bewegung der Elektronen im Kristallgitter*, Phys. Z. Sowjetunion **3**, 664–666 (1933).

polar optical phonon → **phonon**.

polyelectrolyte – a **polymer** with repeating units bearing electrolyte groups. These groups dissociate in aqueous solutions, making the polymer charged. Polyelectrolyte properties are thus similar to both electrolytes and polymers. Because of this they are sometimes called polysalts. Like salts, their solutions are electrically conductive. Like polymers, their solutions are often viscous. Many biological molecules are polyelectrolytes.

polymer – a molecule composed of an unbounded number of molecular subunits (**monomer**s) linked together, in contrast to an **oligomer** consisting of a finite number of subunits.

polymer–clay nanocomposite → **clay–polymer nanocomposite**.

polymer nanocontainer – a hollow polymer particle. Such nanocontainers are useful for biomedical applications as confined reaction vessels, protective shells for **enzymes**, traps for the selective recovery of biotransformation or polymerase chain reaction products, or drug delivery carriers.

More details in: A. Graff, S. M. Benito, C. Verbert, W. Meier, *Polymer nanocontainer*, in: *Nanobiotechnology. Concepts, Applications and Perspectives*, edited by C. M. Niemeyer and C. A. Mirkin (Wiley-VCH, Weinheim, 2004).

polymer solar cell – a **solar cell** built from thin films of organic semiconductors such as polymers and small-molecule compounds.

More details in: J. J. M. Halls, R. H. Friend, *Organic photovoltaic devices* in: *Clean Electricity from Photovoltaics, Series on Photoconversion of Solar Energy*, Vol. **1**, edited by M. D. Archer, R. Hill, (Imperial College Press, 2001) pp. 377–432.

polymerase chain reaction (PCR) – the method for the generation of unlimited copies of any fragment of **DNA** or **RNA**. PCR exploits the natural function of the enzymes called polymerases. Polymerases are present in all living things and their action is to copy genetic material. The PCR works in three steps (see Figure P.10).

First, the target genetic material must be denatured, that is the strands of its helix must be unwound and separated by heating; second, two primers (short chains of the four different chemical components that construct any strand of genetic material) bind to their complementary bases on the single-stranded DNA by hybridization or annealing; finally, DNA synthesis is achieved by a polymerase which, starting from the primer, can read the template strand and match it with complementary nucleotides.

First described in: R. K. Saiki, S. J. Scharfs, F. A. Faloona, K. B. Mullis, G. T. Horn, H. A. Ehrlich, N. Arnheim, *Enzymatic amplification of* β *globin genomics sequences and restriction site analysis for diagnosis of sickle-cell anaemia*, Science **230**, 1350–1354 (1985); K. B. Mullis, F. A. Faloona, *Specific synthesis of DNA in vitro via a polymerase catalyzed chain reaction*, Meth. Enzymol. **155**, 335–350 (1987).

More details in: H. A. Erlich, *PCR Technology - Principles and Applications for DNA Amplification* (Oxford University Press, London, 1999).

Recognition: in 1993 K. B. Mullis shared the Nobel Prize in Chemistry with M. Smith for contributions to the developments of methods within DNA-based chemistry, in particular for his invention of the polymerase chain reaction (PCR) method.

See also www.nobel.se/chemistry/laureates/1993/index.html.


Cycle 0
Unamplified DNA
Targeted sequence
Cycle 1
Denature and anneal primers
Primer extension
(forms long product)
Cycle 2
Denature and anneal primers
Primer extension
(forms long and short product)
Cycle 3
Denature and anneal primers
Short product
Primer extension
Long product
Cycles 4 – 30 or more

Figure P.10 Polymerase chain reaction amplification cycles.

polymorphism – different crystal structures of the same chemical compound. For single element solids, the term **allotropy** is used.

polyrotaxane → **rotaxane**.

polysalt = **polyelectrolyte**.

p orbital → **atomic orbital**.

porosity – the ratio of the net volume of pores to the total volume of the sample containing these pores.

porous silicon – a porous material traditionally produced by anodic electrochemical etching of monocrystalline silicon in hydrofluoric acid (HF) solutions. It can be also fabricated by stain etching of silicon in HF–HNO_3 mixtures and by ion implantation of hydrogen or **noble gases**. This material has unique physical and chemical properties determined by a dense network of nanosize pores in the crystalline matrix and specific surface structure of the pore walls. Depending on the pore size, macroporous (>50 nm), mesoporous (2–50 nm) and nanoporous (≤2 nm) structures are distinguished. **Quantum confinement** and surface effects in nanostructures, that is **quantum dots** and **quantum wires**, formed in porous silicon, force this material to behave like a direct-gap semiconductor demonstrating rather effective photo- and electroluminescence. It is used in light-emitting devices integrated into monocrystalline silicon, for biological and medical applications, for **micro-electromechanicals** and **nano-electromechanical systems**, and in fuel cells.

The simplest cell for the anodization process consists of a chemically inert bath filled with an aqueous or ethanolic solution of HF, in which a silicon wafer and a platinum electrode are placed. In order to initiate electrochemical etching, the wafer is anodically polarized with respect to the platinum electrode. The process is usually performed with monitoring of the anodic current as it allows an appropriate control of both the porosity and thickness and good reproducibility from run to run. If the wafer is simply dipped into the solution the porous layer is formed on both wafer surfaces and the cleaved edges contacting with the solution. Since the electric current flows through the bulk of the wafer, there is a potential drop between the top and bottom parts of the wafer resulting in the decrease in the current density from the top to the bottom, which induces porosity and thickness gradients.

Better uniformity and formation of the porous layer on one side only are achieved in a cell with a planar electric contact to the silicon wafer being anodized. Such a cell, with a solid contact to the back of the wafer, is schematically shown in Figure P.11.

Only the front of the sample is exposed to the electrolyte. A metal or graphite external contact is gently pressed on to the back of the wafer. For low-resistivity silicon (typically lower than a few mΩcm), rather good uniformity is obtained without additional metal films or specially doped layers on the back surface, which indeed become important for providing a uniform current density through high-resistivity wafers. The porous layer homogeneity is also improved by agitating the electrolyte in order to remove bubbles and dissolved products of reactions. The reactions responsible for local electrochemical dissolution of silicon in HF solutions assume a hole(h^+) electron(e^-) exchange to be involved according to the



Figure P.11 Simplified schematic diagram of a conventional single-tank anodization cell.

following general scheme

$$\mathrm{Si} + 2\mathrm{HF} + lh^+ \rightarrow \mathrm{SiF_2} + 2\mathrm{H}^+ + (2 - l)e^-$$
$$\mathrm{SiF_2} + 2\mathrm{HF} \rightarrow \mathrm{SiF_4} + \mathrm{H_2} \uparrow$$
$$\mathrm{SiF_4} + 2\mathrm{HF} \rightarrow \mathrm{SiH_2F_6},$$

where l is the number of charges exchanged during the elementary step. The silicon dissolution requires HF and holes. Light illumination of the anodized surface is often performed in order to generate enough holes and electrons in silicon. It is in particular important for n-type and lightly doped (below $10^{18}\mathrm{cm}^{-3}$) p-type materials. Gaseous hydrogen and soluble H_2SiF_6 are main products of the reactions. When purely aqueous HF solutions are used, the hydrogen bubbles stick to the surface and induce lateral and in-depth inhomogeneity of the porous layer. One of the most efficient ways to eliminate the bubbles is to add a surfactant to the solution. Absolute ethanol at a concentration not less than 15% is good for this. Acetic acid is another efficient surfactant, which allows better control of the solution pH. Only a few percent of this acid is required for bubble removal.

All the properties of a porous layer, such as its thickness, porosity (fraction of voids within the layer), diameter of pores and their structure are strongly dependent on the silicon wafer characteristics and anodization conditions. The most influencing factors are the type of conductivity, resistivity and crystallographic orientation of silicon, as well as HF concentration, pH of the solution and its chemical composition, temperature, current density, duration of anodization, stirring conditions, and illumination during anodization. Optimal control of the fabrication process and its reproducibility are only possible by accounting for these factors.

There can be three principal types of structure of the porous layer, and these are illustrated in Figure P.12. They are: (i) cylinder-like structure with ordered nonconnected pore channels, (ii) tree-like structure with quasi-ordered branching pore channels, and (iii) sponge-like structure with a net of randomly running pores. The cylinder-like structure is usually formed in low-doped n- and p-type



Figure P.12 Typical morphology of porous silicon layers: cylinder-like (a), tree-like (b), sponge like (c) structures. The images reproduced by courtesy of Doctors V. V. Starkov and S. K. Lazarouk from their private collections.

monocrystalline silicon anodically etched in the dark (without illumination). It is characterized by a small branching density corresponding to porosity below 10%. The tree-like structure consisting of long voids of about 10 nm in diameter running perpendicular to the surface are formed on heavily doped silicon (resistivity lower than 0.05 Ω cm) either *n*- or *p*-type. Layers with porosity up to 60% can be produced. For lightly doped silicon, the situation is somewhat different. The porous layer fabricated on lightly doped *p*-type wafers and on *n*-type ones under illumination consists of apparently random arrays of very small holes of about 2–4 nm. Achievable porosity is higher.

The crystallographic orientation affects the morphology of the porous layer only in the case of *n*-type monocrystalline silicon determining directions of main pore channels. In all other cases, the porous material formed from amorphous, polycrystalline and monocrystalline silicon with identical type and concentration of major charge carriers have quite similar properties, while their behavior during anodization is different. Porosity is increased with an increase in the anodization current typically ranging from 10 to 200 mA cm^{-2}. An increase in the HF concentration in an electrolyte reduces porosity. Thickness of the porous layer is linearly increased with the anodization time. Porous layers as thick as tens of nanometers up to hundreds of micrometers can be formed. Patterned Si_3N_4 thin films or others resistant to HF masks are used for local formation of porous regions in silicon wafers and films.

Interpore regions in the monocrystalline silicon matrix preserve its crystalline structure. Thus, pores themselves and their branching produce a variety of nanocrystallites in the form of crystalline clusters and wires. They are randomly distributed within the porous layer with the density and size distribution determined by the matrix material and anodization conditions. Individual nanostructures are impossible to select within any porous layer. That is why practical applications of porous silicon are limited by optoelectronic devices based on statistical behavior of quantum size particle ensembles.

First described in: A. Ulhir, Jr., *Electrolytic shaping of germanium and silicon*, Bell Syst. Tech. J. **35**(2), 333–347 (1956) and D. R. Turner, *Electropolishing silicon in hydrofluoric acid solutions*, J. Electrochem. Soc. **105**(7), 402–408 (1958) – first formation of porous silicon; C. Pickering, M. I. J. Beale, D. J. Robbinson, P. J. Pearson,

R. Greef, *Optical studies of porous silicon films formed in p-type degenerate and non-degenerate silicon*, J. Phys. C **17**(35), 6535–6552 (1984) – first observation of visible photoluminescence from porous silicon at 4.2 K; L. T. Canham, *Silicon quantum wire array fabrication by electrochemical and chemical dissolution of wafers*, Appl. Phys. Lett. **57**(10), 1046–1048 (1990) – first observation of visible photoluminescence from porous silicon at room temperature; A. Richter, P. Steiner, F. Kozlowski, W. Lang, *Current-induced light emission from a porous silicon device*, IEEE Electron Device Lett. **12**(12), 691–692 (1991) and A. Halimaoui, C. Oules, G. Bomchil, A. Bsiesy, F. Gaspard, R. Herino, M. Ligeon, F. Muller, *Electroluminescence in the visible range during anodic oxidation of porous silicon films*, Appl. Phys. Lett. **59**(3), 304–306 (1991) – first light-emitting devices employed electroluminescence from porous silicon with solid and liquid contacts, respectively; S. Lazarouk, P. Jaguiro, V. Borisenko, *Integrated optoelectronic unit based on porous silicon*, Phys. Stat. Sol. (a) 165(1), 87–90 (1998) – first integrated in silicon optoelectronic unit including porous silicon light emitter and porous silicon light detector connected by alumina waveguide.

More details in: Properties of Porous Silicon, edited by L. Canham (INSPEC, The Institution of Electrical Engineers, London, 1997); O. Bisi, S. Ossicini, L. Pavesi, *Porous Silicon, a quantum sponge structure for silicon based optoelectronics*, Surf. Sci. Rep. **38**(1–3), 1–126 (2000).

porphyrin – a macrocyclic compound having an alternating nitrogen atom–carbon atom ring structure shown in Figure P.13. A porphyrin in which no metal is inserted in its cavity is called a free base.

Porphyrins exhibit strong light absorption, and thus play an important role in the light harvesting process of green plants, in the photoinduced charge separation at the photosynthetic reaction center as oxygen carriers, and as **redox** mediators. They can be used as a component molecule for molecular- based conductors, magnets, light emitting devices, and molecular memories.



Figure P.13 A porphyrin molecule. M=Me (Ni, Co, Cu, Fe, Zn,), 2H.

Pöschl–Teller potential describes potential relief for charge carriers of an effective mass m in barriers and hole-like wells produced by impurity diffusion

$$V(z) = -\frac{\hbar^2}{2m}\alpha^2\frac{\lambda(\lambda-1)}{\cosh^2\alpha z},$$

where α is the width parameter, and λ is the depth parameter. Values of $0 < \lambda < 1$ correspond to potential barriers, $\lambda = 1$ gives a flat band, and values of $\lambda > 1$ correspond to potential wells. The eigenvalues of the resulting **Schrödinger equation** for a well of width a are:

$$E_n = -\frac{\hbar^2\alpha^2}{2m}(\lambda - 1 - n)^2 a.$$

First described in: G. Pöschl, E. Teller, *Bemerkungen zur Quantenmechanik des anharmonischen Oszillators,* Z. Phys. **83**(3–4), 143–151 (1933).

More details in: I. G. Kaplan, *Intermolecular Interactions: Physical Picture, Computational Methods and Model Potentials* (John Wiley & Sons, Chichester, 2006).

positron – the anti-particle of the **electron** having mass and spin that are identical to those of an electron but a charge and magnetic moment that are opposite.

positron annihilation spectroscopy (PAS) is based on registration of gamma photons emitted during annihilation of **positrons** with **electrons** in condensed matter. These gamma photons carry information on the electronic environment at which the positron annihilates, in particular on defects in a crystal lattice. The most frequently used source of positrons is the radioisotope ^{22}Na, which has a 2.6 year half-life. It emits 0.545 MeV end-point energy positrons simultaneously with a 1.28 MeV gamma photons.

The penetration depth of the source emitted positrons is sufficient to probe the bulk of a solid sample. The positrons slow down and thermalize in the solid within a few picoseconds. After diffusing in the lattice, a thermalized positron annihilates with an electron creating two gamma quanta with energies of 511 keV, which is equivalent to the rest mass of the particles. These two quanta are emitted in approximately opposite directions. The deviation from 180° is caused by the momentum of the electron, since the momentum of the positron is negligible due to thermalization. In the case of core electrons, the momentum is large while for the valence electrons it is small.

The approaches employed to characterize defects from the positron annihilation include positron annihilation lifetime spectroscopy, two-dimensional angular correlation radiation (2D-ACAR) measurements and Doppler broadening measurements.

The lifetime experiments are capable of distinguishing different kinds of defects but provide no direct information on chemical variations. The number of exponential decay terms in the lifetime spectrum is the number of defect states plus one. The lifetimes deduced from the spectra are then checked against fingerprint values of known defects.

2D-ACAR data allow the characterization of defects through the analysis of the momentum distribution of conduction- and valence-band electrons in the perturbing fields of defects.

Doppler broadening of annihilation radiation provides a sensitive method of defect characterization by measuring the momentum distribution of the electrons.

Unlike 2D-ACAR, which is mainly sensitive to low-momentum electrons, it allows the examination of high-momentum core electrons. The core electrons of the atoms near a defect site retain the properties of the free atoms, including the momentum distribution. The principle of the method lies in the analysis of the positron annihilation line shape, which directly corresponds to the distribution of momentum of electron–positron pairs. The momentum itself is measured from the amount of the Doppler shift of the emitted photons.

More details in: A. Harrich, S. Jagsch, S. Riedler, W. Rosinger, *Positron annihilation coincidence Doppler broadening spectroscopy,* American Journal of Undergraduate Research **2**(3), 13–18 (2003).

power efficiency → **quantum efficiency**.

Poynting's vector – the vector **S** giving direction and magnitude of energy flow in an electromagnetic field:

$$\mathbf{S} = \frac{c}{4\pi}|\mathbf{E}| \times |\mathbf{H}|,$$

where **E** and **H** are the mutually orthogonal vectors of electric and magnetic field, respectively. If energy dissipation takes place during the propagation, this vector becomes complex with a real part equal to the average energy flow.

First described in: J. H. Poynting, *On the transfer of energy in the electromagnetic field*; Phil. Trans. **175**, 343 (1884).

precautionary principle – the statement that we should not go ahead with a new technology, or persist with an old one, unless we are convinced it is safe. It covers cases where scientific evidence is insufficient, inconclusive or uncertain. Emerging in European environmental policies in the late 1970s, the principle has becomes enshrined in numerous international treaties and declarations. The giant advances in communications technology have fostered public sensitivity to the emergence of new risks before scientific research has been able to fully illuminate the problems. The principle will play a more and more important role for future emerging technologies.

More details in: http://europa.eu.int/comm/off/com/healthconsumer.

precession – an effect shown by a rotating body when torque is applied to it in such a way as to tend to change the direction of its axis of rotation. If the speed of rotation and the magnitude of the applied torque are constant, the axis, in general, describes a cone, its motion at any instant being at right angles to the direction of the torque.

precipitation – formation of a new condensed phase in liquids and solids.

precision chemical engineering – a combination of **top-down** lithographic techniques with **bottom-up** assembly methodologies. Its principles are illustrated in Figure P.14.

In the beginning, a **self-assembled monolayer** (SAM) is fabricated on a substrate and then lithographically processed. Nanolithographic radiative techniques employing ultraviolet light, X rays or electron beams are used for this. Molecules in the SAM can undergo either removal (process A), crosslinking, damage, partial removal without exposing any new surface chemical functionality (process B) or modification of an internal and/or terminal functional group (process C) upon the irradiation. In a second stage, selective self assembling of nanocomponents onto the templated SAM can be achieved on the unirradiated (processes D, F and G) or irradiated (processes E and H) regions.

A suitable choice of the self-assembling material and lithographic technique provides fabrication of the structures with a lateral resolution down to 5 nm.

More details in: P. M. Mendes, J. A. Preece, *Precision chemical engineering: integrating top-down and bottom-up methodologies,* Cur. Opin. Colloid Interfacial. Sci. **9**, 236–248 (2004); N. P. Mahalik, *Micromanufacturing and Nanotechnology* (Springer, Berlin Heidelberg, 2005).


Photons, X-rays or electrons
SAM
Substrate
Top-down
Bottom-up
A
B
C
D
E
F
G
H
Non-selective chemical patterning
Selective chemical patterning

Figure P.14 Precision chemical engineering (From P. M. Mendes, J. A. Preece, Curr. Opin. Colloid Interfacial Sci. **9**, 236–248 (2004)).

pretzelane → **catenane**.

primer – a short segment of **DNA** or **RNA** that anneals to a single strand of DNA in order to initiate template-directed synthesis and extend a new DNA strand by the enzymatic action of DNA polymerase to produce a duplex-stranded molecule.

primitive cell – a minimum-volume parallelepiped defined by primitive axes, which being translated will reproduce a crystal structure.

primitive translations are used to construct theoretically a crystal lattice. A perfect crystal is characterized by a set of lattice translations **T** that, if applied to the crystal, take every ion (except those near the surface) to a position previously occupied by an equivalent ion. The three shortest such translations that are not coplanar are called primitive translations τ_1, τ_2, τ_3. The position of every ion in the crystal can be given by some lattice translation $T = n_1\tau_1 + n_2\tau_2 + n_3\tau_3$, where n_1, n_2 and n_3 are integers.

principal function – the stationary value of the integral $P = \int_{t_1}^{t_2} \mathbf{L}(r_i, v_i, t)\mathrm{d}t$, where $\mathbf{L}(r_i, v_i, t)$ is the Lagrangian and, r_i and v_i are generalized coordinates and velocities that describe the state of a conservative system. The stationary value of the principal function establishes the path traversed by the system between two fixed points $r_i(t1)$ and $r_i(t2)$.

projection operator – an **operator** that projects (maps) vectors in **Hilbert space** onto a subspace.

prokaryote – a single-celled organism without a nucleus, like bacteria and archaea. The name came from the Greek root *karyon*, meaning ‘‘nut’’, combined with the prefix *pro-*, meaning ‘‘before’’.

propagator – a function used in quantum field theory to characterize propagation of a relativistic field or a quantum of that field from one point to another.

prosthetic group – a non**protein** component covalently bound to a catalytic center of an **enzyme** and essentially involved in the catalytic mechanism.

protein – a high-molecular weight biological molecule composed of a **polymer** of **amino acids** linked via **peptide** bonds. The name originated from the Greek *proteios*, meaning ‘‘precedence’’, ‘‘holding the first place’’, which reflects their great importance in all living organisms. Proteins are formed by lineer polymerization of α-amino-acid $RCHNH_2CO_2H$, a molecule of water being eliminated between neighboring amino- (NH) and carboxyl- (CO) groups to form the peptide link: $–CHR_1ONHCHR_2–$.

The side chains R are of some twenty different kinds including aliphatic and aromatic polar and nonpolar types. All amino acids share the same backbone, differing in terms of their side chains. Seven amino acids have an aliphatic or aromatic side chain making them strongly **hydrophobic**: valine (V), isoleucine (I), leucine (L), phenylalanine (F), methionine (M), tyrosine (Y), and tryptophane (W). Six amino acids have a strongly **hydrophilic** side chain: aspartic acid (D), glumatic acid (E), asparagines (N), glutamine (Q), lysine (K), and arginine (R). The other seven have intermediate properties: alanine (A), cysteine (C), threonine (T), glycine (G), proline (P), serine (S), and histidine (H). Such a distribution of hydrophobicity/hydrophilicity offers an extremely useful range of blocks with which to build macromolecules exhibiting remarkable properties.

There are two cases when the side chain is bonded back to the main chain nitrogen atom to form an amino acid. The peptide link is generally planar, with N–H and C=O trans to the short C–N bond.

Under normal conditions, any fairly long polypeptide (from a few dozen to a few hundred amino acids) folds spontaneously in the presence of water into globular domains with a stable three-dimensional architecture. Some of them can also fold specifically, often in helical form, within lipid membranes. It is the dichotomy between hydrophobicity and hydrophilicity that acts as the driving force for these processes.

The succession of different types of amino acids along the polymer that is individual for each protein is called the primary structure or sequence. This information is sufficient for the polypeptide chain to adopt a stable and unique three-dimensional structure in a suitable medium, mainly water, with occasional exceptions.

Two classical groups of proteins are distinguished: **fibrous proteins**, which have the characteristic proteins of polymers, and **globular proteins**, which are molecular. The natural fibrous proteins have simpler analogs in synthetic polypeptide fibers containing only one kind of side chain. In a globular protein the chain is folded to make an approximately spherical shape. Larger molecules may be formed by association of a few such subunits, either similar or different.

First described by G. J. Mulder in an article published in the Bulletin des Sciences Physiques et Naturelles en Neerlande on July 30, 1838. Mulder appears to have taken the term from S. Berzelius, who, on July 10, sent Mulder a letter in which he suggested the name ‘‘protein’’.

More details in: T. Simonson, *Electrostatics and dynamics of proteins*, Rep. Prog. Phys. **66**(5) 737–787 (2003); H. Bisswanger, *Proteins and enzymes*, in: *Encyclopedia of Applied Physics*, Vol. 15, edited by G. L. Trigg (Wiley-VCH, Weinheim, 1996).

protein engineering – a highly visible expression of genetic engineering as well as a quintessential development of classical molecular biology. Its main applications are in medicine, namely in disease prevention and therapy, as well as in industry, notably in catalysis.

The field was pioneered by M. Smith in the late 1970s and early 1980s. The two main strategies currently underpinning the discipline are **structure-based engineering** (also called **rational design**) and **directed molecular evolution**.

More details in: J. A. Brannigan, A. J. Wilkinson, *Protein engineering 20 years on*, Nat. Rev. Molec. Cell Biol. **3**, 964–970 (2002).

Recognition: in 1993 M. Smith received the Nobel Prize in Chemistry for his fundamental contributions to the establishment of oligonucleotide-based, site-directed mutagenesis and its development for protein studies.

See also www.nobel.se/chemistry/laureates/1993/index.html.

protein folding – spontaneous rearrangements of **protein** chains related to their functional three-dimensional structure.

protein unfolding – stimulated rearrangements of **protein** chains related to their functional three-dimensional structure.

proteome – the term used to refer to the collection of **protein**s in certain biological systems. For example, all of the proteins in a **virus** can be called a viral proteome. A complete proteome for an organism can be conceptualized as the complete set of proteins from all of the various cellular proteomes.

A proteome is constantly changing through its biochemical interactions with the genome. One biological system will have radically different protein expression in its different parts and in different stages of its life cycle.

proteomics – the field of study of **protein**s, particularly their structure and functions.

proton – a subatomic particle with a single positive electric charge, spin 1/2 and a mass of $1.6726231 \times 10^{-27}$ kg. It is a **baryon**. The name originates from Greek *protos* first.

protonated water cluster – an association of a **proton** (H^+) with a finite number of water molecules described as $H_3O^+(H_2O)_n$. The basic component of the cluster is the **hydronium ion** H_3O^+, which is formed by a strong covalent bond between proton and oxygen. The ion has C_{3v} symmetry and an O–H bond dissociation energy of about 260 kcal mol^{-1}. Despite this relatively large bond strength, the hydronium ion is the key species in the transfer of protons between molecules in aqueous acid–base chemistry.

pseudomorphic superlattices → **superlattice**.

pseudopotential – a potential in the form $V_p = V(r) + V_R$, where $V(r)$ is the periodic crystal potential and V_R has the character of a repulsive potential, which cancels in part the large attractive **Coulomb potential**, such that in the region of the core the higher Fourier coefficients of the pseudopotential V_p are small enough to be neglected in the first-order approximation. In fact, the true potential is replaced by an effective potential producing the correct energies of the valence electrons and giving the right behavior of the corresponding wave functions except in the vicinity of the ion cores.

pseudopotential method supposes separation of the crystal **eigenfunctions** into core states and valence states and the solution of the **Schrödinger equation** with the resulting **Hamiltonian** for energies and wave functions within the valence subspace. It is used in the numerical simulation of electron energy band structure of solids.

pseudorotaxane → **rotaxane**.

pseudo-spin valve → **giant magnetoresistance effect**.

pull-off force → **Johnson–Kendall–Roberts theory**.

Purcell effect – a spontaneous emission of radiation from excited atoms enhanced or inhibited by placing the atoms in a specially designed cavity or between mirrors. It has the following explanation. A two-level system decays spontaneously by interaction with a vacuum continuum at a rate proportional to the spectral density of modes per volume evaluated at the transition frequency. Within a cavity, the density of modes is modified and huge variations in its amplitude can occur. In fact the maximal density of cavity modes occurs at quasi-mode resonant frequencies and is enhanced with respect to the corresponding free-space density. It was observed that a single mode occupies within a cavity of volume V a spectral linewidth ν/Q, where Q is the quality factor of the cavity. Normalizing a resulting cavity-enhanced mode density per unit volume to the mode density of the free space reveals that an atom whose transition falls within the mode linewidth will experience an enhancement of its spontaneous decay rate given by the factor $P = (3\lambda^3/4\pi^2)Q/V$, termed the **Purcell spontaneous emission enhancement factor**.

First described in: E. M. Purcell, *Spontaneous emission probabilities at radio frequencies*, Phys. Rev. **69**(1/2), 681 (1946); E. M. Purcell, H. C. Torrey, R. V. Pound, *Resonance absorption by nuclear magnetic moments in a solid*, Phys. Rev. **69**(1/2), 37–38 (1946).

Recognition: in 1952 E. M. Purcell shared with F. Bloch the Nobel Prize in Physics for their development of new methods for nuclear magnetic precision measurements and discoveries in connection therewith.

See also www.nobel.se/physics/laureates/1952/index.html.

Purcell spontaneous emission enhancement factor → **Purcell effect**.

pyridine – a simple heterocyclic aromatic organic compound C_5H_5N. Structurally it is a six-membered aromatic ring with one CH group replaced by a nitrogen atom as shown in Figure P.15.



Figure P.15 Pyridinium cation.

Pyridine has an equatorial lone pair of electrons at the nitrogen atom that does not participate in the aromatic π-system. That makes it a good solvent and a starting material for synthesis of other compounds.

pyroelectric – a material in which a spontaneous electric moment is developed when it is heated. The spontaneous polarization in such materials is temperature dependent. Therefore, any temperature change ΔT results in the change of the polarization $\Delta P = \alpha \Delta T$, where α denotes the pyroelectric coefficient.

First described by D. Brewster in 1824.

pyrolysis – decomposition of compounds by heat.

pyrrole – a heterocyclic organic compound of five-membered diunsaturated ring structure composed of four carbon atoms and one nitrogen atom (C_4H_5N). It is shown in Figure P.16.

The pyrrole ring system is involved in colored natural products (green pigment in chlorophyll, red in hemoglobin). Pyrrole and its derivatives are widely used as intermediates in the synthesis of pharmaceuticals, medicines, agrochemicals, **dye**s, photographic chemicals, perfumes and other organic compounds. They are also used as catalysts for polymerization processes, corrosion inhibitors, preservatives, and as solvents for resins and terpenes.



Figure P.16 Pyrrole molecule.

Q

From *Q*-control to qubit

***Q*-control** → *Q*-**factor.**

***Q*-factor** – the quality factor describing in **dynamic force microscopy** the number of cantilever oscillation cycles after which the damped oscillation amplitude decays to exp(−1) of the initial amplitude with no external excitation. It is $Q = m\omega_r/\alpha$, where m is the effective mass of the cantilever, ω_r is its resonant frequency, and α is the damping coefficient. The minimum detectable force gradient is inversely proportional to the square root of Q.

An additional feedback circuit in a dynamic force microscope allows the control of the quality factor that is referred to as ***Q*-control** feedback. It makes possible high-resolution, high-speed, or low-force scanning during atomic imaging of a sample surface.

More details in: A. Schirmeisen, B. Anczykowski, H. Fuchs, *Dynamic force microscopy*, in: *Handbook of Nanotechnology*, edited by B. Bhushan (Springer, Berlin, 2004), pp. 449–473.

***Q*-switching** – a modification of the resonance characteristics of the laser cavity. The name comes from the *Q*-factor used as a measure of the quality of a resonance cavity in microwave engineering.

quantum cascade laser is based on a fundamentally different principle to normal semiconductor **lasers**. It uses only one type of charge carrier, namely electrons, and is thus called a unipolar laser. It operates like an electronic waterfall that is initiated in a **multiquantum well** structure. Electrons cascade down a series of identical energy steps built into the wells, emitting a photon each step. The energy levels involved in the transitions are created by **quantum confinement** in the well, this being the active region of the laser.

So far, the quantum cascade laser has been demonstrated using two different approaches. The original design was based on a three-quantum well active region separated from the injection/relaxation region by a tunneling barrier. The second design has the active region consisting of a superlattice, which for the best performance can be chirped to compensate for the applied electric field (see Figure Q.1).



Figure Q.1 Schematic conduction-band diagram of a portion of the laser heterostructures at threshold bias. The thicknesses of the layers are indicated in nm, and the underlined numbers denote the four layers which are *n*-type doped. The wavy arrow indicates the transition 3→2 responsible for the laser action. The solid curves represent the moduli squared of the relevant wave functions. After C. Sirtori, P. Kruck, S. Barbieri, P. Collot, J. Nagle, *GaAs/Al$_x$Ga$_{1-x}$As quantum cascade lasers*, Appl. Phys. Lett. **73**, 3486–3488 (1998).

In both cases, the necessity to confine the upper state of the active region requires the laser to be separated into an active region followed by an injection/relaxation region. Quantum cascade lasers have been obtained using AlInAs/GaInAs/InP and AlGaAs/GaAs superlattices. They have demonstrated pulsed operation at room temperature in the midinfrared wavelength range (3–19 μm).

Quantum cascade structures are also employed in **quantum cascade distributed-feedback lasers** and microcavity **quantum disk lasers**.

First described in: R. F. Kazarinov, R. A. Suris, *Possibility of the amplification of eletromagnetic waves in a semiconductor with a superlattice,* Fiz. Tekh, Poluprovodn. **5**(4), 797–800 (1971) – idea (in Russian); J. Faist, F. Capasso, D.L. Sivco, C. Sirtori, A.L. Hutchinson, and A.Y. Cho, *Quantum Cascade Lasers,* Science **264**, 553–556 (1994) – realization.

More Details in: J. Faist, F. Capasso, C. Sirtori, A. Cho, in *Intersubband Transitions in Quantum Wells: Physics and Device Applications II,* edited by H. Liu and F. Capasso, (Academic, New York, 2000) vol. 66, pp. 1–83.

quantum cascade disk-lasers – a quantum cascade laser arranged as a freestanding-in-air disk cut off a thin quantum cascade structure → **quantum cascade laser**. The disk geometry allows small devices and low threshold currents. Moreover, laser lasing in this case occurs in the so-called "whispering gallery" modes that correspond to light travelling close to the perimeter of the disk impinging onto its edge at angles large than the critical angle of refraction. This results in a high-quality resonator, with only low losses due to tunneling of light, scattering from surface roughness and intrinsic waveguide loss.

First described in: J. Faist, C. Gmachl, M. Striccoli, C. Sirtori, F. Capasso, D. L. Sivco, C. Sirtori, and A. Y. Cho, *Quantum cascade disk lasers*, Appl. Phys. Lett. **69**(17), 2456–2458 (1996).

quantum cascade distributed-feedback laser is formed by incorporation of a grating in a **quantum cascade laser**. This allows tunable operation of the laser at and above room temperature with a linewidth consistent with the desired applications, such as remote chemical sensing and pollution monitoring.

First described in: J. Faist, C. Gmachl, M. Striccoli, F. Capasso, C. Sirtori, D. L. Sivco, J. N. Baillargeon, and A. Y. Cho, *Distributed feedback quantum cascade lasers*, Appl. Phys. Lett. **70**(20), 2670–2672 (1997).

quantum cellular automata – binary logical devices and computers designed as an array of **quantum-dot** cells that are connected locally by the Coulomb interaction of the electrons confined within the dots. It is also called the **Notre Dame architecture**. A basic cell consists of four (or five) quantum dots in a square array, as shown in Figure Q.2, coupled by tunnel barriers (in the case of five dots the fifth one is placed in the center of the square).

Electrons are able to tunnel between the dots, but cannot leave the cell. When two excess electrons are injected into the cell, Coulomb repulsion separates them and places them in dots on opposite corners. There are thus two energetically equivalent ground state polarizations, which can be labeled logic ‘‘0’’ and logic ‘‘1’’. If two cells are brought close together, the Coulomb interaction between the electrons forces the cells to get the same polarization. When the polarization of one of the cells is gradually changed from one state to another, the second cell exhibits a highly bistable switching of its polarization. It allows digital processing of information.

Some examples of logic elements based on these cells are shown in Figure Q.3. Since the cells are capacitively coupled to their neighbors, any change in the state of the input cell results in a change of the output. In a line of cells no metastable states, where only a few cells flip, are possible. Transmission of binary information, signal inversion, majority voting, splitting and other logic functions can be realized.

One meets two main problems when implementing quantum cellular automata devices: individual adjustment of each cell and the limit on the operating temperature. The individual adjustment is needed because of fabrication tolerance, the presence of stray changes, and the need for exactly $4N + 2$ excess electrons in each



Figure Q.2 Basic cell of quantum cellular automaton and its two ground polarization states.



Figure Q.3 Logic elements composed of quantum cellular automata cells.

cell. For a cell on the 100 nm scale, layout errors of less than a tenth of a nanometer would be sufficient to completely disrupt cell operation. The limitation on the operation temperature is determined by the weakness of the dipole interaction between the cells, which must be significantly larger than $k_B T$. Along quantum dot structures fabricated within a semiconductor-based nanotechnology, single bistable molecules have also prospects for implementation quantum cellular automata. In the latter case, the limitations related to fabrication tolerance are easily overcome, as molecules are intrinsically precise, and bound electrons are sufficiently localized to act as excess electrons without the need for external leads.

First described in: P. D. Tougaw, C. S. Lent, W. Porod, *Bistable saturation in coupled quantum dot cells*, J. Appl. Phys. **74**(5), 3558–3566 (1993).

quantum computations – a procedure of massively parallel computations exploiting the specific properties of quantum states, such as quantum superposition, **coherence** and **entanglement**. Quantum parallelism supposes a **quantum computer** to operate on quantum superposition states of all inputs simultaneously. The same mathematical operation on different input numbers is performed within a single quantum computational step. The result is a superposition of all the corresponding outputs. Extraction of information in a quantum computer is nontrivial, because simply measuring a quantum state with an exponential number of nonzero amplitudes will yield a highly random result. In certain algorithms, however, appropriate quantum logic gates cause the amplitudes to interfere so that only a few amplitudes survive in the end. Following a measurement (or a limited number of repeated measurements on identical runs), the result (or distribution of results) can depend on a global property of all inputs.

Parallel quantum information processing is evidently more efficient than any classical computational procedure.

First described in: Yu. I. Manin, *Computed and Non-computed* (Sovetskoe Radio, Moscow, 1980) – in Russian; R. P. Feynman, *Simulating physics with computers*, Int. J. Theor. Phys. **21**(6/7), 467–488 (1982).

More details in: M. A. Nielsen, I. L. Chang, *Quantum Computation and Quantum Information* (Cambridge University Press, Cambridge, 2000).

quantum computer – a machine realizing **quantum computation**.

quantum-confined Stark effect → **Stark effect**.

quantum confinement (effect) – the phenomenon of the nonzero lowest energy and quantization of the allowed energy levels in low-dimensional structures, arising from the confinement of electrons within a limited space. It is illustrated as follows.

A free electron moving in three dimensions has a kinetic energy corresponding to the space components of its impulse p_x, p_y, p_z:

$$E = \frac{1}{2m^*}(p_x^2 + p_y^2 + p_z^2) \quad \text{or in wave terms} \quad E = \frac{\hbar^2}{2m}(k_x^2 + k_y^2 + k_z^2),$$

where m^* is the effective mass of the electron, which in solids is usually appreciably less than m_0, the electron rest mass, and k_x, k_y, k_z are the space components of the wave vector. Free motion of electrons in a low-dimensional structure is restricted at least in one direction. In this direction, let it be the x direction, the forces which confine the electrons can conveniently be described by an infinitely deep potential well, as illustrated by Figure Q.4.

Noting that a is the width of the well in the x direction, the electrons have zero potential energy in the region $0 < x < a$. Infinitely high impenetrable potential barriers prevent them from straying beyond this region. Thus, the electron wave function drops to zero at $x = 0$ and a. Only a restricted set of **wave functions** meet these requirements. They can be only standing waves whose wavelength λ takes one of the discrete values given by $\lambda_n = 2a/n$ (where $n = 1, 2, \ldots$). The allowed wave vectors of the waves are $k_n = 2\pi\lambda_n = n\pi/a$. They result in the set of discrete energy states of electrons defined by:

$$E_n = \frac{\hbar^2 k_n^2}{2m} = \frac{\hbar^2 \pi^2 n^2}{2ma^2}.$$

The integer n is a **quantum number** that labels the state. It means that electrons confined to a region of space can occupy only discrete energy levels. The lowest



Figure Q.4 Potential well and wave functions of electrons confined in it.

state has the energy

$$E_1 = \frac{\hbar^2 \pi^2}{2ma^2},$$

which is always above zero. This contrasts with classical mechanics, where the lowest state of a particle sitting on the bottom of the well is equal to zero. Such behavior would violate the uncertainty principle in quantum mechanics. In order to satisfy the uncertainty relation $\Delta p \Delta x \geq \hbar/2$ (in our case $\Delta x = a$), the electron must have the uncertainty in its momentum $\Delta p \geq \hbar/2a$. The latter corresponds to a minimum amount of energy $\Delta E = (\Delta p)^2/2m = \hbar^2/8ma^2$, which resembles E_1 to an accuracy of $\pi^2/4$.

In addition to increasing the minimum energy of the electron, confinement also causes its excited state energies to become quantized proportionaly to n^2.

The number of directions remaining free of the confinement is used for classification of elementary low-dimensional structures within three groups. These are quantum films, quantum wires and quantum dots schematically shown in Figure Q.5.

Quantum films are two-dimensional (2D) structures in which quantum confinement acts only in one direction, which is the z direction in Figure Q.5 corresponding to the film thickness. Charge carriers are free to move in the xy plane of the film giving their total energy to be a sum of the quantum confinement induced and kinetic components:

$$E = \frac{\hbar^2 \pi^2 n^2}{2ma^2} + \frac{\hbar^2 k_x^2}{2m} + \frac{\hbar^2 k_x^2}{2m}.$$

In k-space it is represented by a set of parabolic bands called **sub-bands**. It can be seen that the sub-bands overlap in energy. The minimum energy that an electron can have in the n-th sub-band is $E_n = (\hbar^2 \pi^2 n^2)/(2ma^2)$ when there is no motion in the plane.

Density of states in a quantum film has a characteristic staircase shape, replacing the parabolic shape typical for free electrons in three-dimensional (3D) structures. Electrons in quantum films are usually considered as a **two-dimensional electron gas (2DEG)**.

Quantum wires are one-dimensional (1D) structures. As compared to quantum films, one more dimension of the structure appears to be so small as to provide quantum confinement. Charge carriers are free to move only along the wire. Thus, only one kinetic component along with the confined energy contributes to the total energy. As a consequence, the density of states has $E^{1/2}$ dependence for each of the discrete pairs of states in the confined directions.

Quantum dots are zero-dimensional (0D) structures in which carriers are confined in all three directions. Their energy states are quantized in all directions and the density of states is represented by series of discrete, sharp picks resembling that of an atom. This comparison is the origin of labeling of quantum dots as **artificial atoms**. Quantum dots are usually formed by a definite number of atoms. They are typically represented by atomic clusters or **nanocrystallites**. Considering coupling of quantum dots with external electric circuits, they can be classified as open dots and almost-isolated or closed quantum dots. In an open dot, the coupling is strong and the movement of electrons across dot-lead junctions is classically allowed. When point contacts, connecting a dot with an external circuit, are pinched off, effective barriers are formed and conductance occurs only by tunneling. These are almost-isolated or closed quantum dots.


Bulk
(3D)
z
y
x
E
k_y
k_x
E
N(E)
Quantum film
(2D)
E
n = 3
n = 2
n = 1
E_3
E_2
E_1
k_y
k_x
E
N(E)
Quantum wire
(1D)
E
n = 3
n = 2
n = 1
E_3
E_2
E_1
k_x
E
N(E)
Quantum dot
(0D)
E
n = 3
n = 2
n = 1
E_3
E_2
E_1
E
N(E)

Figure Q.5 Elementary low-dimensional structures, their electron energy diagrams $E(k)$ and electron density of states $N(E)$ in comparison with those in three dimensions.

quantum critical point → **quantum phase transition**.

quantum cryptography – the art of rendering a message unintelligible to any unauthorized party by the use of **Heisenberg's uncertainty principle**, **quantum entanglement** and the fact that it is not possible to take a measurement of a quantum system without perturbing the system. Hence, an eavesdropper cannot get any information about the communication without introducing perturbations that would reveal his presence.

In general, security of a cryptotext depends entirely on the secrecy of the key, which is a set of specific parameters defining encrypting/decrypting procedures. The key is supplied together with the plain text as an input to the encrypting algorithm, and together with the cryptogram as an input to the decrypting algorithm. The main quantum cryptosystems developed for the key distribution use: (i) encoding based on two non-commuting observables → **BB84 protocol**, (ii) encoding built upon **quantum entanglement** and **Bell's theorem** → **E91 protocol**, and (iii) encoding based on two nonorthogonal state vectors → **B92 protocol**.

Quantum cryptography provides means for two parties to exchange an enciphering key over a private channel with complete security of communication. While classical cryptography employs various mathematical techniques to restrict eavesdroppers from learning the contents of encrypted messages, in quantum cryptography, the information is protected by the laws of quantum physics.

First described in: S. Wiesner, *Conjugate coding*, SIGACT News **15**(1), 78–88 (1983). The original manuscript was written circa 1970, but rejected by the journal to which it was submitted.

More details in: N. Gisin, G. Ribordy, W. Tittel, H. Zbinden, *Quantum cryptography*, Rev. Mod. Phys. **74** (1) 145–195 (2002).

quantum decoherence → **decoherence (quantum)**.

quantum dot → **quantum confinement**.

quantum dot laser operates on the basis of the fact that population inversion necessary for lasing in semiconductors occurs more efficiently when the active layer material scales down from three-dimensional (bulk) to zero-dimensional (**quantum dot**) structures. The structure of the active layer of the laser is schematically shown in Figure Q.6 where the GaAs/InGaAs system is used as a prominent example.

In fact, a quantum dot laser combines the length scales defining the confinement of photons (100 nm) and the length scales defining the confinement of electrons and holes (10 nm). Moreover, quantum dot lasers exhibit reduced temperature



Figure Q.6 Composition of the active layer of a quantum dot laser.

sensitivity. For the fabrication, it is necessary to form high quality, uniform quantum dots in the active layer. This is provided by the self-assembly of nanoscale three-dimensional clusters through the **Stranski–Krastanov growth mode**. The number of layers with the vertically aligned dots can be 3–10 or even more.

First described in: Y. Arakawa, H. Sakaki, *Multidimensional quantum well laser and temperature dependence of its threshold current*, Appl. Phys. Lett. **40**(11), 939–441 (1982) – idea; N. Kirstaedter, N. N. Ledentsov, M. Grundmann, D. Bimberg, V. M. Ustinov, S. S. Ruvimov, M. V. Maximov, P. S. Kopev, Z. I. Alferov, U. Richter, P. Werner, U. Gosele, J. Heydenrieich, *Low threshold, large T_0 injection laser emission from (InGa)As quantum dots*, Electron. Lett. **30**(17), 1416–1417 (1994) – realization.

More details in: N. N. Ledentsov, V. M. Ustinov, V. A. Schukin, P. S. Kopev, Z. I. Alferov, D. Bimberg, *Heterostructures with quantum dots: fabrication, properties, lasers (Review)*, Semiconductors **32**(4), 343–365 (1998).

Recognition: in 2000 Z. I. Alferov received the Nobel Prize in Physics for basic work on information and communication technology: for developing semiconductor heterostuctures used in high-speed and optoelectronics.

See also www.nobel.se/physics/laureates/2000/index.html.

quantum dot solid – an ensemble of **quantum dots** spatially arranged with a period (the distance between the nearest dots) comparable or shorter than the electron **de Broglie wavelength**. The basic properties of such dense quantum dot ensembles are expected to reproduce features inherent in solids, namely formation of energy bands in a perfect lattice and coexistence of localized and delocalized electron states in disordered quantum dot structures. Electronic and optical properties of quantum dot solids are determined by electron confinement in each dot and collective effects arising from periodic special organization of the dots. The quantum dot solid can be considered as a particular form of **colloidal crystals**.

First described in: C. B. Murray, C. R. Kagan, M. G. Bawendi, *Self organization of CdTe nanocrystallites into three-dimensional quantum dot superlattices,* Science **270**, 1335–1338 (1995).

quantum efficiency – a capability of electrons and holes to generate photons by radiative recombination in a **light-emitting device (LED)**. Internal and external quantum efficiency are distinguished.

The **internal quantum efficiency** is defined as the ratio of the number of photons generated to the number of minority carriers injected into the region where recombination mostly occurs. In fact, it is the number of excited carriers that recombine radiatively expressed as a fraction of the total recombination rate $\nu_{\text{in}} = R_{\text{r}}/R = \tau_{\text{nr}}/(\tau_{\text{nr}} + \tau_{\text{r}})$, where R_{r} and R are the radiative and total recombination rates, and τ_{nr} and τ_{r} are the nonradiative and radiative relaxation times of carriers. It is used to characterize the internal generation of photons. It does not take into account (a) how many charge carriers injected into the LED do not excite the material to the photon emitting states, or (b) how many generated photons get lost before exiting the device (for example by reabsorption processes). In fact, for those photons that are generated, there can still be loss through absorption within the LED material, reflection loss when light passes from a semiconductor to air due to differences in refractive index and total internal reflection of light at angles greater than the critical angle defined by the **Snell's law**.

The **external quantum efficiency** is the ratio of the number of photons actually emitted by an LED and the number of electrical carriers entering the LED per unit time. By using the external quantum efficiency ν_{ext} one can derive the **power efficiency**, which is the ratio of the radiant flux (the power carried by the light beam) emitted by the LED to the input electrical power supplied to it: $\nu_{pow} = \nu_{ext} h\omega/2\pi eV$, where V is the applied voltage. The power efficiency of an LED should be at least 1% for display applications, whereas for optical interconnects it should be at least 10%, because of the requirement for a small thermal budget on the chip. Operating voltage can be high for display applications, while it should be low (1–5 V) for interconnects.

The power efficiency is sometimes reported in lumens per watt. It is also called **wall-in-plug efficiency** because it is intended that the power should be directly taken by the plug-in. It should be noticed that this general definition can be also used for nonelectrically pumped luminescence mechanisms.

quantum ensemble – a number of identically prepared particles.

quantum entanglement – the term introduced by E. Schrödinger for the description of nonseparable quantum states. It is an ability of quantum systems to exhibit correlations between states within a superposition. If there are two **qubit**s each in a superposition of 0 and 1 state, the qubits are said to be entangled if the measurement of one qubit is always correlated with the result of the measurement of the other qubit. It means that two spatially separated and noninteracting quantum systems that have interacted in the past may still have some locally inaccessible information in common–information which cannot be accessed in any experiment performed on either of them alone.

Entanglement is a feature of quantum systems that allows much stronger correlation between quantum particles than classical physics permits. A measurement on one particle in an entangled system instantly reveals the properties of the other particle even if the two particles are widely separated. The quantum entanglement is used for quantum processing of information.

First described in: E. Schrödinger, *Die gegenwärtige Situation in der Quantenmechanik,* Naturwiss. **23**(48), 807–812 (1935).

quantum film → quantum confinement.

quantum Fourier transform decomposes a quantum state of the form $|\phi\rangle = \sum_x a_x|x\rangle$ into

$$QFT|\phi\rangle = \sum_x a_x \sum_k \frac{1}{2^{N/2}} e^{i2\pi kx}|k\rangle = \sum_K \left(\sum_x \frac{1}{2^{N/2}} e^{i2\pi kx} a_x\right)|k\rangle$$

Here the term in the brackets is just the discrete Fourier transform of a_x, the representation $|k\rangle$ being the bit reversed of the representation of x. One could do a bit reversal operation to get $|k\rangle$ into the same bit order as $|x\rangle$.

More details in: M. A. Nielsen, I. L. Chuang, *Quantum Computation and Quantum Information* (Cambridge University Press, Cambridge, 2000).

See also en.wikipedia.org/wiki/Quantum_Fourier_transform.

quantum (quantized) Hall effect → **Hall effect**.

quantum leap – a leap-like transition of a quantum particle from one state to another under the influence of an interaction typical for this type of particle. It is often used to indicate an abrupt change, sudden increase, or dramatic advance.

First described in: N. Bohr, *On the constitution of atoms and molecules. I*, Phil. Mag. **26**, 1–25 (1913).

quantum logic gate – a device that performs as a quantum **unitary operator** acting on the states of a certain set of **qubit**s. If the number of such qubits is n, the evolution operator for this quantum gate is represented by a $2^n \times 2^n$ matrix in the same unitary group. It is thus a reversible gate: one can reverse the action, thereby recovering the initial quantum state from the final one. Generically a quantum logic gate can have any final number of input qubits. Schematically a quantum logic gate is usually represented by a box with a number of input and output lines. The performing operation is symbolically written inside the box.

Some representative gates in increasing order of complexity are shown below. One-qubit gates are the simplest possible gates because they take one input qubit and transform it into one output qubit. Their schematic representations are shown in Figure Q.7.

The quantum NOT gate is a one-qubit gate. Its unitary evolution operator is $\mathrm{U}_{\mathrm{NOT}} = \mathbf{PM} = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}$ where **PM** is the **Pauli spin matrice**. This quantum gate coincides with its classical counterpart → **logic gate**. However, there is a basic underlying difference: the quantum gate acts on qubits while the classical gate operates on bits.

This difference allows us to introduce a truly quantum one-qubit gate: the $\sqrt{\mathbf{NOT}}$ gate. Its matrix representation is

$$\mathrm{U}_{\sqrt{\mathbf{NOT}}} = \frac{e^{\mathrm{i}\pi/4}}{\sqrt{2}}(1 - \mathrm{i}\mathbf{PM}) = \begin{pmatrix} \frac{1+\mathrm{i}}{2} & \frac{1-\mathrm{i}}{2} \\ \frac{1-\mathrm{i}}{2} & \frac{1+\mathrm{i}}{2} \end{pmatrix}.$$



Figure Q.7 Quantum one-qubit logic gates.

This gate, when applied twice, gives $\mathbf{NOT} = U_{\sqrt{\mathbf{NOT}}} U_{\sqrt{\mathbf{NOT}}} = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix}$ $= U_{NOT}$. This gate has no counterpart in classical computers since it implements nontrivial superpositions of basis states.

Another one-qubit gate without analog in classical circuitry and heavily used in quantum computations is the so-called **Hadamard gate**. It is defined by the operator $U_H = \frac{1}{\sqrt{2}}(\mathbf{PM} + \mathbf{PM}) = \frac{1}{\sqrt{2}} \begin{pmatrix} 1 & 1 \\ 1 & -1 \end{pmatrix}$ where **PM** is the corresponding **Pauli spin matrice**.

Examples of quantum binary gates are presented in Figure Q.8.



Figure Q.8 Quantum binary logic gates.

The two qubits CNOT (controlled-NOT) gate is equivalent to the XOR (exclusive-OR) one. It is instructive to give the unitary action of this gate in several forms. Its action on the two-qubit basis states is $U_{\mathrm{CNOT}}|00\rangle = |00\rangle$, $U_{\mathrm{CNOT}}|01\rangle = |01\rangle$, $U_{\mathrm{CNOT}}|10\rangle = |11\rangle$, $U_{\mathrm{CNOT}}|11\rangle = |10\rangle$. From this definition one can see that the name of this gate is quite apparent, for it means that it executes a NOT operation on the second qubit conditioned to have the first qubit in the state. Its matrix representation is

$$U_{\mathrm{CNOT}} = U_{\mathrm{XOR}} = \begin{pmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & 1 \\ 0 & 0 & 1 & 0 \end{pmatrix}.$$

The CNOT gate plays a paramount role in both the theory and experimental realization of quantum computers. It allows the implementation of conditional logic at a quantum level.

Unlike the CNOT gate, there are two-qubit gates with no classical analog. One example is the controlled-phase gate or CPHASE:

$$U_{\mathrm{CPHASE}} = \begin{pmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ 0 & 0 & 0 & e^{i\phi} \end{pmatrix}.$$

It implements a conditional phase shift $e^{i\phi}$ on the second qubit. An important result is that it is possible to reproduce the CNOT gate with a controlled-phase gate of $\phi = \pi$ and two **Hadamard transformations** on the target qubits. This is a simple consequence of the relation $U_H \mathbf{PM} U_H = \mathrm{PM}$. Other interesting two-qubit gates are the **SWAP** gate, which interchanges the states of the two qubits, and the $\sqrt{\mathrm{SWAP}}$ gate, whose matrix representations are

$$\mathrm{U_{SWAP}} = \begin{pmatrix} 1 & 0 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & 1 \end{pmatrix}, \mathrm{U}_{\sqrt{\mathrm{SWAP}}} = \begin{pmatrix} 1 & 0 & 0 & 0 \\ 0 & \frac{1+i}{2} & \frac{1-i}{2} & 0 \\ 0 & \frac{1-i}{2} & \frac{1+i}{2} & 0 \\ 0 & 0 & 0 & 1 \end{pmatrix}.$$

Among three qubit gates the most representative are depicted in Figure Q.9.



Toffoli gate Deutsch gate Fredkin gate

Figure Q.9 Quantum three-qubit logic gates.

An immediate extension of the CNOT construction to three qubits yields the CCNOT gate (or C^2NOT), which is also called the **Toffoli gate**[1]. Its matrix representation is a one-qubit extension of the CNOT gate:

$$\mathrm{U_{CCNOT}} = \mathrm{U_T} = \begin{pmatrix} 1 & 0 & 0 & 0 & 0 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 & 0 & 0 & 0 & 0 \\ 0 & 0 & 1 & 0 & 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 1 & 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 & 1 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 & 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & 0 & 0 & 0 & 0 & 1 \\ 0 & 0 & 0 & 0 & 0 & 0 & 1 & 0 \end{pmatrix}.$$

The associated **truth table** is shown below.

Table Q.1 Truth table for the Toffoli gate.

x	*y*	*z*	*x′*	*y′*	*z′*
0	0	0	0	0	0
0	0	1	0	0	1
0	1	0	0	1	0
0	1	1	0	1	1
1	0	0	1	0	0
1	0	1	1	0	1
1	1	0	1	1	1
1	1	1	1	1	0

The first two input qubits x, y are copied to the first two output qubits x', y', while the third output qubit z' is the **XOR** of the third input z and the **AND** of the first two inputs x, y. The **Deutsch gate**[2] is also an important three-qubit gate. It realizes a controlled-controlled-S or $\mathbf{C}_2 S$ operation, where $\mathrm{U_S} = \mathrm{i}\cos(\theta/2) + \mathbf{PM}\sin(\theta/2)$ is a unitary operation that rotates a qubit about the x axis by an angle θ and then multiplies it by the factor i. The angle θ is required to be incommensurate to π, that is, not a rational multiple of π.

Another useful instance of a three-qubit gate is the **Fredkin gate**[3]. It performs a controlled **SWAP** operation represented by the matrix

$$\mathrm{U_F} = \begin{pmatrix} 1 & 0 & 0 & 0 & 0 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 & 0 & 0 & 0 & 0 \\ 0 & 0 & 1 & 0 & 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 1 & 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 & 1 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 & 0 & 0 & 1 & 0 \\ 0 & 0 & 0 & 0 & 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & 0 & 0 & 0 & 0 & 1 \end{pmatrix}.$$

The above unitary linear gates act not only on the individual basis states, but also on any linear combination of them. The simple gates can be assembled into a network-like arrangement that enables one to perform more complicated quantum operations than those initially carried out by those gates. This is the basic idea of a quantum circuit[4].

[1] *First described in:* T. Toffoli, *Bicontinuous extension of reversible combinatorial functions,* Math. Syst. Theory **14**(1), 13–23 (1981).

[2] D. Deutsch, *Quantum computational networks,* Proc. R. Soc. London A **425**, 73–90 (1989).

[3] E. Fredkin, T. Toffoli, *Conservative logic,* Int. J. Theor. Phys. **21**, 219–253 (1982).

[4] *More details in:* A. Galindo, M. A. Martín-Delgado, *Information and computation: Classical and quantum aspects,* Rev. Mod. Phys. **74**(2), 347–423 (2002); M. Nielsen, I. Chuang, *Quantum Computation and Quantum Information* (Cambridge University Press, Cambridge, 2000).

quantum mirage – a phenomenon of coherent projection of electronic structure in atomic scale arrangements. It is illustrated in Figure Q.10 for the case in which it was first observed.

A **scanning tunneling microscope** (STM) was used to position 36 cobalt atoms in an elliptical ring. Then another cobalt atom at one of the two focal points of the ring was placed. The **Kondo effect** was measured by the STM at both focal points. It can be seen to take place not only at the focal point with the lone cobalt atom, but also at the vacant focal point, where it is much weaker. It looks like a mirage, which gives gave the name to the phenomenon.

The phenomenon promises to make possible data transfer without conventional electrical wiring.

First described in: H. Manoharan, C. Lutz. D. Eigler, *Quantum mirages formed by coherent projection of electronic structure,* Nature **403**(5), 512–515 (2000).



Figure Q.10 Visualization of the quantum mirage.

quantum number – an integer (in the case of spin a half-integer) that labels the state of a quantum system.

quantum phase transition – a phase transition taking place at absolute zero temperature and driven solely by quantum fluctuations associated with **Heisenberg's uncertainty principle**. The fluctuations, being quantum mechanical in nature, exhibit scale invariance in both space and time. The location of the transition is indicated as a quantum critical point. At the critical point the critical fluctuations extend over the entire system. Unlike classical critical points, where the critical fluctuations are limited to a narrow region around the phase transition, the influence of a **quantum critical point** is felt over a wide range of temperatures above the quantum critical point, so the effect of quantum criticality is felt without ever reaching absolute zero.

Quantum phase transitions can lead to non-Fermi behavior of electrons and unusual states of matter.

More details in: S. Sachdev, *Quantum Phase Transitions* (Cambridge University Press, Cambridge, 2001).

quantum point contact – a narrow constriction of a two-dimensional conducting channel. An example of such a structure and its related conductance curve are illustrated in Figure Q.11. A short constriction in the burred **two-dimensional electron gas** is defined by the electrically connected surface gates shaped like opposed knives. The gates are negatively biased in order to deplete the two-dimensional electron gas under them and form a narrow conducting channel. For



Figure Q.11 Schematic layout and conductance of the quantum point contact induced in burred two-dimensional electron gas by surface gates. After B. J. van Wees, H. van Houten, C. W. J. Beenakker, J. G. Williamson, L. P. Kouwenhoven, D. Van der Marel, C. T. Foxon, *Quantized conductance of point contacts in a two-dimensional electron gas*, Phys. Rev. Lett. **60**(9), 848–850 (1988).

the channel with N transmitting modes its conductance is $G = N(2e^2/h)$ –it is quantized in units of $2e^2/h$.

The externally applied gate voltage V_g controls the channel width. By an increase of the negative bias, the width of the point contact can be gradually reduced, until it is fully pinched off. As the conducting channel is widened, the number of transverse eigenstates below the Fermi level increases. Conductance steps corresponding to increasing values of N appear. Note that if one is dealing with a nonideal channel in which scattering events reducing total current take place, it is important to account for the probability of transmission.

quantum teleportation – the "disembodied transport" of a quantum state (particle) from one place to another. It is an alternative to the hardly realized direct move of such states through space. Direct transmission would have to be along a channel that maintains quantum coherence, which requires the complete isolation of the transmitted quantum object. An approach based on the measurement of all observables of the quantum system, their subsequent transmission in the form of conventional digital codes and restoring the original quantum system by a receiver on the basis of measured observables, meets fundamental limitations. It cannot be applied to transmission of an unknown quantum system because any measurement made on a quantum system uncontrollably perturbs it, destroying the original. Accurate copying (cloning) of an unknown quantum state is also not possible (**non-cloning theorem**) because it would be equivalent to a simultaneous sharp measurement of all observables of the system, including non-commuting ones, which is forbidden by the uncertainty principle. Quantum teleportation avoids these restrictions.

A system for quantum teleportation should have a source of **Einstein–Podolsky –Rosen (EPR) pairs**, quantum decoder and quantum synthesizer connected with a sender (conventionally named Alice) and a receiver (conventionally named Bob) by communication channels, as schematically shown in Figure Q.12. In order to teleport an unknown quantum state Ψ represented by a quantum particle from Alice to Bob, they are each given one particle of the entangled EPR pair. Then Alice brings together her particle and the particle in an unknown state and performs jointly on those two particles a special measurement using the quantum decoder.

This measurement has four possible outcomes – it is, in fact, the same measurement that is performed at the end of the two-bit communication process. Alice then communicates the result of the measurement to Bob by any classical channel. According to these data, Bob, who has the other member of the EPR pair, performs one of four operations on his particle using the quantum synthesizer. As a result, Bob gets the particle in exactly the same state that Alice's particle was originally in. Thus, if Alice and Bob share an Einstein–Podolsky–Rosen pair Bob can reproduce Alice's unknown quantum state with the assistance of only two classical bits of information sent by Alice to Bob through a classical channel. Quantum teleportation supposes sending an unknown quantum state from one place, where it vanishes, to another place, where it shows up, without really traversing the intermediate space.

First described in: C. H. Bennett, G. Brassard, C. Crépeau, R. Jozsa, A. Peres, W. K. Wootters, *Teleporting an unknown quantum state via dual classical and Einstein–Podolsky–Rosen channels*, Phys. Rev. Lett. **70**(13), 1895–1899 (1993) – theory; D. Bouwmeester, J. W. Pan, K. Mattle, M. Eibl, H. Weinfurter, A. Zeilinger, *Experimental quantum teleportation*, Nature **390**, 575–579 (1997) – experiment.


Alice
Ψ
Quantum decoder
Classical communication channel
Bob
Quantum synthesizer
Ψ
Source of Einstein-Podilsky-Rosen pairs

Figure Q.12 Principle of quantum teleportation.

quantum well – a finite region of space restricted by potential barriers. In semiconductor electronics this is typically a structure composed of semiconductors with different band gaps or a semiconductor and a dielectric, in which the material with a small gap in a low-dimensional form is placed in between the regions of the large gap materials. It acts as a well for charge carriers. The material with the small gap creates a well, while the large gap material forms potential barriers for this well. Such an arrangement can be translated in space resulting in **multiquantum wells**.

Superlattices fabricated by deposition of semiconductors with dissimilar electronic properties are considered to be a classical example of solid-state quantum wells. Nevertheless, quantum wells are also formed when semiconductor low-dimensional structures are imbedded into a dielectric matrix even without lattice matching of the materials. Silicon nanoclusters imbedded into silicon dioxide can be an example of these.

According to the confinement energy schemes for electrons and holes, quantum wells are usually classified in two main groups, which are labeled **type I** and **type II**. Energy relationships in these groups are illustrated by Figure Q.13, where the material A is expected to have smaller band gap than the material B.

In the **type I** or straddling alignment, the bottom of the conduction band in the well (material A) lies lower in energy than in the barrier (material B), but for the top of the valence band it is quite the opposite: in the well it is higher than in the barrier. Electrons and holes are both localized and confined in the same region, which is the well. This type of the well can be called a ‘‘spatially direct gap semiconductor’’ having energy diagrams very similar to the band structure of direct gap semiconductors.



Figure Q.13 Arrangements of the confinement of electrons and holes in quantum wells formed by the small gap material A and large gap material B with the band gaps E_{gA} and E_{gB}, respectively.

In **type II**, both the bottom of the conduction band and the top of the valence band in the well are located lower in energy than those in the barrier. As a result, electrons appear to be localized and confined in the well, while holes come to the barrier. Meanwhile, the difference in energy between the bottom of the conduction band in the barrier and the top of the valence band in the well can be positive or negative in this case. If it is positive, the energy gap extends through the whole structure, as shown in the figure for type IIA (staggered alignment). Such a structure can be referred to as ''spatially indirect gap semiconductor''. If the energy difference is negative (or zero), as shown for type IIB (misaligned) structures, these can be considered as ''spatially gapless semiconductors''.

Quantum wells are one of the most important elements of many of nanoelectronic and optoelectronic devices.

quantum well laser – a semiconductor laser that has an active region composed of ultrathin layers (~20 nm or less) forming narrow potential wells for injected carriers. Quantization of electronic states in the wells, among other benefits, brings reduction of the threshold current as compared to semiconductor lasers with a uniform active region.

First described in: J. P. van der Ziel, R. Dingle, R. C. Miller, W. Wiegmann, W. A. Nordland, Jr, *Laser oscillations from quantum states in very thin GaAs-*$Al_{0.2}Ga_{0.8}As$ *multilayer structures*, Appl. Phys. Lett. **26**(8), 463–465 (1975) – first experimental demonstration.

quantum well solar cell – a multiple band gap **photovoltaic** device with intermediate properties between a **heterojunction solar cell** and a **tandem solar cell**.

First described in: K. W. J. Barnham, G. Duggan, *A new approach to high efficiency multi-band-gap solar cells,* J. Appl. Phys. **67**, 3490–3493 (1990).

quantum wire → **quantum confinement**.

quantum yield –the number of times that a defined radiation-induced event occurs per photon absorbed by the system. It is a measure of the efficiency with which the absorbed light produces some effect. In most processes quantum yield is less than 1 since not all photons are absorbed productively. Quantum yields greater than 1 are possible for radiation-induced avalanche reactions, in which a single photon may trigger a long chain of transformations.

quantum Zeno paradox – a continuously observed quantum system cannot make transitions. It is a consequence of the **Zeno paradox** that motion is impossible because before reaching a goal one has to get halfway there. Before that, one had to get halfway to the midpoint, and so on. The wave function of a quantum system evolves continuously according to the Schrödinger equation. When a measurement is made, there is a discontinuous reduction of the wave packet. Thus, if one could make a continuous set of measurements on a quantum system, this system would never evolve. Another name for the paradox is the **watched pot effect**, after the proverb "A watched pot never boils".

quasicrystal – a structure which cannot be indexed to any **Bravais lattice** and which has a symmetry intermediate between a crystal and a liquid. It has a well-defined, discrete point group symmetry, like a crystal, but one which is explicitly incompatible with periodic translational order (for example exhibiting five-, eight-, or twelve-fold symmetry axes). Instead, quasicrystals possess a particular kind of translational order known as quasiperiodicity.

First described in: D. Shechtman, I. Blech, D. Gratias, J. W. Cahn, *Metallic phase with long range orientational order and no translation symmetry*, Phys. Rev. Lett. **53**(20), 1951–1953 (1984).

First described in: R. McGrath, U. Grimm, R. D. Diehl, *The forbidden beauty of quasicrystals*, Physics World **17**(12), 23–27 (2004).

quasiparticle – a single particle excitation.

quasi-steady-state hole-burning → **spectral hole-burning**.

qubit – an acronym for a **qu**antum **b**it. It is a quantum system that, like an ordinary computer bit, has two accessible states. But unlike a classical system, a qubit can exist in a superposition of these two states at the same time. Qubits are just quantum two-level systems such as the spin of an electron, the nuclear spin or the polarization of a photon and can be prepared in a coherent superposition state corresponding to "0" or "1". Important times characterizing performance of different two-level quantum systems are tabulated below (Table Q.2).

The time t_{sw} is the minimum time required to execute one quantum gate. It is estimated as $h/\Delta E$, where ΔE is the typical energy splitting in the two-level system.

Table Q.2 Switching (t_{sw}) and phase coherence (t_{ph}) times of two-level quantum systems (D. P. DiVincenzo, *Quantum computation*, Science **270**, 255–261 (1995)).

Quantum system	t_{sw}(s)	t_{ph}(s)	t_{ph}/t_{sw}
Mössbauer nucleus	10^{-19}	10^{-10}	10^{9}
Electrons: GaAs	10^{-13}	10^{-10}	10^{3}
Electrons: Au	10^{-14}	10^{-8}	10^{6}
Trapped ions: In	10^{-14}	10^{-1}	10^{13}
Optical cavity	10^{-14}	10^{-5}	10^{9}
Electron spin	10^{-7}	10^{-3}	10^{4}
Electron quantum dot	10^{-6}	10^{-3}	10^{3}
Nuclear spin	10^{-3}	10^{4}	10^{7}

The duration of a π tipping pulse cannot be shorter than this uncertainty time for each system. The phase coherence time t_{ph} is the upper bound on the time scale over which a complete quantum computation can be executed accurately. The ratio of these two times gives the largest number of steps permitted in a quantum computation using these quantum bits.

First described in: B. Schumacher, *Quantum coding*, Phys. Rev. A **51**(4), 2738–2747 (1995).

R

From Rabi flopping to Rydberg gas

Rabi flopping – the sinusoidal population transfer in two-level systems → **Rabi frequency**.

Rabi frequency arises in an analysis of a system with two energy levels. The two-level system is a basic model approximating accurately many physical systems, in particular those with resonance phenomena. The basic two-level system is a spin 1/2 particle (spin-up and spin-down). Consider the motion of the spin 1/2 particle in the presence of a uniform but time-dependent magnetic field. Suppose the particle has a magnetic moment $\boldsymbol{\mu} = \gamma \mathbf{S}$, where γ is the gyromagnetic ratio and $\mathbf{S}$ is the spin operator. In a static magnetic field $\mathbf{B}_0$ lying along the z axis the motion of the magnetic moment can be described through

$$\mu_x = \mu \sin\theta \cos\omega_0 t; \quad \mu_y = \mu \sin\theta \sin\omega_0 t; \quad \mu_z = \mu \cos\theta.$$

Here θ is the angle between $\boldsymbol{\mu}$ and $\mathbf{B}_0$ and $\omega_0 = -\gamma B_0$ is the **Larmor frequency**. Now we introduce a magnetic field $\mathbf{B}_1$ and this field rotates in the $x - y$ plane at the Larmor frequency. The total magnetic field is $\mathbf{B} = (B_1 \cos\omega_0 t, -B_1 \sin\omega_0 t, B_0)$ (called the **Rabi pulse**) and we will find the motion of μ in this field. The solution is simple in a rotating coordinate system where one has that the moment μ precesses about the field at the rate:

$$\omega_R = \gamma B.$$

These frequency is called the **Rabi frequency**. If the moment initially lies along the z axis, then its tip traces a circle in the $y - z$ plane. At time t it has precessed through an angle $\phi = \omega_r t$ and the component z of the moment is given by $\mu_z(t) = \mu \cos\omega_R t$. At time $T = \pi/\omega_R$, the moment points along the negative z axis: it has turned over. This phenomenon is called **Rabi flopping**.

If the magnetic field rotates at a generic frequency different from the resonance frequency ω_0, it is straightforward to demonstrate that the moment precesses about the field at a rate (called the **effective Rabi frequency**)

$$\omega_R^{eff} = \sqrt{\omega_R^2 + (\omega_0 - \omega)^2}.$$

The z-component of the moment oscillates but, unless $\omega = \omega_0$, never completely inverts. The rate of oscillation (**Rabi oscillation**) depends on the magnitude of the rotating filed. Its amplitude depends on the frequency difference $\delta = \omega - \omega_0$ with respect to ω_R, called detuning. The moment in the field oscillates between two states at the effective Rabi frequency, where the contrast of the oscillation is determined by detuning.

The Rabi resonance method can be used to measure the energy splitting between two states. It plays an important role in quantum optics. It is fast becoming popular in the analysis and design of spin **qubit** systems.

First described in: I. I. Rabi, *On the process of space quantization*, Phys. Rev. **49**(4), 324–328 (1936); I. I. Rabi, *Space quantization in a gyrating magnetic field*, Phys. Rev. **51**(8), 652–654 (1937).

Recognition: in 1944 I. I. Rabi received the Nobel Prize in Physics for his resonance method for recording the magnetic properties of atomic nuclei.

See also www.nobel.se/physics/laureates/1944/index.html.

Rabi oscillations – oscillations in a two-level system → **Rabi frequency**.

Rabi pulse – if the oscillating field entering the determination of the **Rabi frequency** is resonant, that is it satisfies $\omega = \omega_0$, then it is called a Rabi pulse → **Rabi frequency**.

racemization – a process that converts an **enantiomer** into a racemic mixture of enantiomers.

Rademacher functions – the system of orthogonal functions defined as $f_n(x) = f_0(2^n x)$ with $n = 1, 2, 3\ldots$; $f_0(x) = 1$ for $0 \leq x < 1/2$; $f_0(x) = -1$ for $1/2 \leq x < 1$; $f_0(x+1) = f_0(x)$ for $-\infty < x < \infty$. This system is not a complete one. Its completion is achieved within the system of **Walsh functions**.

First described in: H. A. Rademacher, *Einige Sätze über Reihen von allgemeinen Orthogonalenfunktionen*, Math. Ann. **87**, 112–138 (1922).

radical (chemical) – a group of atoms, which occurs in different compounds and remains unchanged during chemical reactions.

Rafii–Tabar and Sutton potential – the potential energy of an atom i in a solid accounting for its long range interaction with neighbors and having the form: $V_i = \epsilon/2 \sum_j (a/r_{ij})^n - c\epsilon[\sum_j (a/r_{ij})^m]^2$, where a is chosen to be the lattice constant, and r_{ij} is the distance between the i-th and j-th atoms. The constant c is chosen so that the energy of an atom in the bulk has its minimum value when the r_{ij} assume the values they would have in a **face-centered cubic** lattice with a lattice constant of a. The parameters ϵ, n and m are obtained by fitting the cohesive energy and the bulk modulus, while n and m are required to be integers with m greater than or equal to 6. The potential is suitable for alloys.

First described in: H. Rafii-Tabar, A. P. Sutton, *Long-range Finnis-Sinclair potentials for fcc metallic alloys*, Phil. Mag. Lett. **63**, 217–224 (1991).

More details in: G. A. Mansoori, *Principles of Nanotechnology: Molecular-based Study of Condensed Matter in Small Systems* (World Scientific, Singapore, 2005).

Raman effect – the light scattered from solids contains components which are shifted in frequency with respect to the incident monochromatic light, as illustrated in Figure R.1.

The difference between the frequency of the incident **photon** and the frequency of the scattered photon is called **Raman frequency**. The shifts are caused by the gain or loss of characteristic amounts of energy when atoms or molecules change their rotational or vibrational motion. Light scattering involves two photons–one in (ω), one out (ω'). A photon is scattered inelastically by a crystal, with creation or annihilation of a **phonon** (Ω) or **magnon**. The photon at $\omega' = \omega - \Omega$ is called the **Stokes line** and the process of the phonon emission is a **Stokes process**. When a phonon is absorbed during scattering, such process is called an **anti-Stokes process** and corresponding photons with $\omega' = \omega + \Omega$ form the **anti-Stokes line**.

The process is called **Brillouin scattering** when an **acoustic phonon** is involved and **polariton** scattering when an optical phonon is involved. Similar processes occur with **magnons**.

The scattered radiation vanishes for certain choices of the light polarization and scattering geometries. These so-called **Raman selection rules** are a result of the symmetries of the medium and of the vibrational modes involved in the scattering.

First described in: C. V. Raman, *A new radiation*, Indian J. Phys. **2**, 387–398 (1928) and G. Landsberg, L. Mandelstam, *Über die Lichtzerstreuung in Kristallen*, Z. Phys. **50**(11/12), 769–780 (1928).

Recognition: in 1930 only C. V. Raman received the Nobel Prize in Physics for his work on the scattering of light and for the discovery of the effect named after him.

See also www.nobel.se/physics/laureates/1930/index.html.



Figure R.1 Raman scattering of a photon with emission or absorption of a phonon.

Raman frequency → **Raman effect**.

Raman selection rules → **Raman effect**.

Raman spectroscopy detects vibrational frequencies in molecules or molecule-like structures. The idea is that when an intense beam of light enters a sample its scattering due to the **Raman effect** occurs at frequencies higher and lower than the frequency of the incident light. The difference between the frequencies of the incident and scattered light is equal to the vibrational frequency of the molecular bond responsible for the Raman scattering. Thus, by analyzing the spectral dependence of Raman scattering, different molecular bonds and various functional groups in the molecule can be recognized.

rapid single flux quantum device – a two-terminal device formed by a Josephson junction → **Josephson effects** where a flux quantum is used as a **bit** of information. Logical 1 and 0 are represented by the existence or absence of a single flux quantum. Such devices have unusual dynamics due to the macroscopic quantum nature of **Cooper pairs** (that have an integer spin) employed as charge carriers. They exhibit a clock frequency beyond hundreds of gigahertz and extremely low power consumption. The main limit for a practical use of the devices is their low-temperature operation mode (4–5 K).

First described in: D. Zinoviev, K. Likharev, *Feasibility study of RSFQ-based selfrouting nonblocking digital switches,* IEEE Trans. Appl. Superconductivity **7**(2), 3155–3163 (1997).

rare earth elements – 17 metallic elements from Group IIIA of the Periodic Table ranging in atomic number from 21 (scandium) to 71 (lutetium). The elements from atomic number 57 (lanthanum) to 71 (lutetium) are also called **lanthanides**.

First described in: S. A. Arrhenius, Sitz. Ber. Wiener Akad., II Abteilung **96**, 831 (1887).

Rashba coupling = **Rashba effect**.

Rashba effect – spin splitting of electron energy levels in solids without external magnetic field as a result of enhanced spin-orbit coupling in the material. In bulk solids it is connected with a lack of inversion symmetry of the crystal potential. In low-dimensional structures, in particular in **quantum wells**, this effect can be superimposed by an inversion asymmetry of the confinement potential. Thus, two components, that is material-related spin–orbit coupling and quantum confinement, may contribute to the total spin splitting.

An asymmetric quantum well has an interface electric field, which is described along the normal of the well plane and lifts the spin degeneracy of the two-dimensional electron energy bands by coupling the electron spin and orbital motion. This spin–orbital coupling is described by a **Hamiltonian** $H_{so} = \alpha_s(\boldsymbol{\sigma} \times \mathbf{k}) \cdot \mathbf{z}$, where $\boldsymbol{\sigma}$ is the **Pauli spin matrix**, $\mathbf{z}$ is the unit vector along the surface field direction, and $\mathbf{k}$ is the electron wave vector along the plane. This Hamiltonian is usually referred to as a **Rashba term**. The spin–orbit coupling constant is implicitly proportional to the strength of the built-in surface electric field. The effective mass Hamiltonian with the spin–orbit term has the form:

$$H = \frac{\hbar^2 k^2}{2m} + \alpha_s(\boldsymbol{\sigma} \times \mathbf{k}) \cdot \mathbf{z}.$$

It yields the electron energy dispersion related to the motion along the plane:

$$E(k) = \frac{\hbar^2 k^2}{2m} \pm \alpha_s k.$$

The important characteristic of this dispersion relation is that the spins are degenerate at $k = 0$ and the spin splitting linearly increases with k, where α_s is the spin–orbit coupling constant, being a measure of the strength of this coupling.

First described in: E. I. Rashba, *Properties of semiconductors with a loop of extrema,* Fiz. Tverd. Tela (Lenigrad) **2**(6), 1224–1238 (1960) – in Russian – introduction of the spin–orbit term; Y. A. Bychkov, E. I. Rashba, *Oscillatory effects and the magnetic susceptibility of carriers in the inversion layers,* J. Phys. C **17**(33), 6039–6045 (1984) – first demonstration of the role of spin coupling in two-dimensional structures.

Rashba term → **Rashba effect**.

rational design → **structure-based engineering**.

Rayleigh–Jeans law expresses the energy density of black body radiation of wavelength λ corresponding to a temperature of the black body T as $P(\lambda) = 8\pi k_B T/\lambda^4$.

First described in: J. W. S. Rayleigh, *Remarks upon the law of complete radiation,* Phil. Mag. **49**, 539–540 (1900); J. H. Jeans, *On the partition of energy between matter and ether,* Phil. Mag. **10**, 91–98 (1905), and independently in: A. Einstein, *Über einen die Erzeugung und Verwandlung des Lichtes betreffenden heuristischen Gesichtspunkt,* Ann. Phys. **17**, 132–148 (1905).

Rayleigh law of scattering → **Rayleigh scattering (of light)**.

Rayleigh limit – the restriction of wavefront error to within a quarter of a wavelength of a true spherical surface to assure essentially perfect image quality.

Rayleigh line – the element of a spectrum line in scattered radiation having a frequency equal to that of the corresponding incident radiation, due to ordinary or **Rayleigh scattering**.

Rayleigh range – the axial distance from the point of minimum beam waist W to the point where the beam diameter has increased to $(2W)^{1/2}$ in the region of a Gaussian beam focus by a diffraction-limited lens.

First described in: Lord Rayleigh (J. W. Strutt), *Images formed without reflection or refraction,* Phil. Mag. **11**, 214–218 (1881).

Rayleigh scattering (of light) – the term employed to describe scattering of light waves by a particle much smaller than their wavelength. The scattered wave amplitude is directly proportional to the volume of the particle and inversely proportional to the square of the wavelength. The scattering intensity is thus proportional to the inverse fourth power of the wavelength, which is the **Rayleigh law of scattering**. It predicts that short-wavelength light will be scattered by a medium containing small particles more efficiently than long-wavelength radiation. This peculiarity of light scattering is responsible for the blue color of the sky on a sunny day and a red sunset. It results from air pollutants or more generally from entropy fluctuations. Blue light, having half of the wavelength of red, is scattered sixteen times as well. The red sunset is due to the fact that such selective scattering removes the blue rays from the direct beam much more effectively than the red. The great thickness of the atmosphere traversed is sufficient to produce the visible effect of giving the transmitted light its intense red color.

First described in: J. W. S. Rayleigh, *On the light from the sky, its polarization and colour*, Phil. Mag. **41** 107–120 and 274–279 (1871).

Rayleigh's equation (for group velocity of waves) expresses the group velocity as a function of the wave velocity v and wavelength λ in the form $v_{gr} = v - \lambda(\mathrm{d}v/\mathrm{d}\lambda)$.

First described in: J. W. S. Rayleigh, *On waves propagating along the plane surface of an elastic solid*, Proc. Lond. Math. Soc. **17**, 4–11 (1887).

RBS – an acronym for **Rutherford backscattering spectroscopy**.

reactance → **impedance**.

real contact area → **Bowden–Tabor law**.

reciprocal lattice – an invariant mathematical construction defined by the direct lattice of a crystal. If $\mathbf{a}_I (I = 1, 2, 3)$ are the primitive lattice vectors of the crystal in the direct lattice space, then its reciprocal lattice vectors $\mathbf{a}_j^* (j = 1, 2, 3)$ are given by the relation $\mathbf{a}_I \cdot \mathbf{a}_j^* = \delta_{ij}$, where $\delta_{ij} = 1$ if $i = j$, and $\delta_{ij} = 0$ if $i \neq j$. The two vectors, one in the direct lattice space (the $\mathbf{a}_I$) and the other in the reciprocal space (the $\mathbf{a}_j^*$) are orthogonal to each other. Thus, the vectors of a reciprocal lattice are $\mathbf{a}_1^* = (\mathbf{a}_2 \times \mathbf{a}_3)/V, \mathbf{a}_2^* = (\mathbf{a}_3 \times \mathbf{a}_1)/V, \mathbf{a}_3^* = (\mathbf{a}_1 \times \mathbf{a}_2)/V$, where $V = \mathbf{a}_1(\mathbf{a}_2 \times \mathbf{a}_3)$ is the volume of the unit cell in direct lattice space. Each set of lattice planes in a crystal is represented by a point in the reciprocal lattice. All symmetry properties possessed by the direct lattice are inherent in the reciprocal lattice.

reciprocity failure → **Bunsen–Roscoe law**.

recognition – molecular recognition describes the capability of a molecule to form selective bonds with other molecules or with substrates, based on the information stored in the structural features of the interacting partners. Molecular recognition processes may play a key role in molecular devices (in particular **molecular electronics**) by driving the fabrication of devices and integrated circuits from elementary building blocks, incorporating them into supramolecular arrays, allowing for selective operations on given species acting as dopants, and controlling the response to external perturbations represented by interacting partners or applied field.

reconstruction → **surface reconstruction**.

red shift – a systematic shift of an optical spectrum toward the red end of the optical range.

redox – the term originated from the two concepts of reduction and oxidation. These two terms go together, because in a chemical reaction, one cannot occur without the other. Electrons lost by one compound must be gained by another. Reduction can also be considered to be the reducing of an atom's positive charge, and oxidation its opposite (gaining positive charge). Reduction describes the uptake of an electron by a molecule, atom or ion. Oxidation describes a loss of an electron by the same species.

Reed–Muller algebra – operations within a universal basis including constant 1, **XOR**, **AND**, and **NOT** operations over Boolean → **Boolean algebra** variables. Expressions in this algebra are classified as fixed and mixed polarity expressions.

First described in: I. Reed, *A class of multiple-error-correcting codes and a decoding scheme*, IEEE Trans. Inform. Theory **4**, 38–49 (1954); D. Muller, *Applications of Boolean algebra to switching circuit design and to error correction*, IRE Trans. Elec. Comp. **3**, 6–12 (1954).

Reetz method provides electrochemical synthesis of metal nanocrystals via an electrorefining process. It consists of six elementary steps illustrated in Figure R.2.

These are: (1) oxidative dissolution of metal anode, (2) migration of metal ions to the cathode, (3) reduction of the ions to a zero-valent state, (4) formation of particles by nucleation and growth, (5) arrest of the growth by capping agents, (6) precipitaton of the particles. The capping agents are typically quaternary ammonium salts containing long-chain alkanes such as tetraoctyl-ammonium bromide.

The size of the nanocrystals can be tuned by altering the current density, the distance between the electrodes, the reaction time, the temperature, and the polarity of the solvent. Usually, low current densities yield larger particles, while high current densities yield smaller particles.

The method has been successfully employed to synthesize both Ni, Co, Fe, Ti, Ag, Au nanoparticles and bimetallic colloids like Pd-Ni, Fe-Co, Fe-Ni and others



Figure R.2 Schematic illustration of the electrochemical synthesis of metal nanocrystals by the Reetz method.

using two anodes consisting of either metals. Moreover, mono and bimetallic nanoparticles can be fabricated by reduction of their salts dissolved in the electrolyte.

First described in: M. T. Reetz, W. Helbig, *Size-selective synthesis of nanostructured transition metal clusters,* J. Am. Chem. Soc. **116**(16), 7401–7402 (1994).

reflection high-energy electron diffraction (RHEED) – diffraction of electrons reflected from a solid surface when the incident electron beam (5–100 keV) strikes the surface at a grazing angle. The diffraction pattern is used to distinguish monocrystalline, polycrystalline and amorphous structures of solid surfaces. It is widely employed in monitoring monoatomic layer growth from changes in surface atomic roughness. As the film thickness increases during the growth, the intensity of the specular and diffracted electron beams oscillates with a period equal to the atomic or molecular layer thickness. High scattered intensities are associated with flat surfaces, which occur when an atomic layer is complete. Low intensities correspond to atomically rough surfaces with a high density of monolayer thick islands. The technique is indeed useful for ***in situ*** monitoring of the growth of **superlattice** films.

More details in: P. K. Larsen and P. J. Dobson (eds) *Reflection High-Energy Electron Diffraction and Reflection Electron Imaging of Surfaces* (Plenum Press, New York, 1988).

reflectivity – the ratio of the intensity of the total reflected radiation to that of the total incident radiation.

refraction – a change in the direction of the wave propagation when a wave passes an interface between two media with different **refractive indexes**. At the interface the wave changes direction, its wavelength increases or decreases, but its frequency remains constant.

The phenomenon is schematically illustrated in Figure R.3 where a ruler is placed in water. The light waves travel more slowly in the water than in the air. As a result, the wavelength of the outcoming light decreases and the waves bend at the interface. This causes the end of the ruler to appear shallower than it really is.

Refraction is also responsible for rainbows and for splitting up of white light into a rainbow spectrum as it passes through a transparent prism. Different frequencies of light travel at different speeds, causing them to be refracted at different angles at the prism surface. The different frequencies correspond to different colors observed.

The amount that the light bends during refraction is calculated using **Snell's law**.



Figure R.3 Refraction of light waves coming out of water.

refractive index in the complex form provides a complete description of the linear optical response of the material. Its real part is the real index of refraction, namely the ratio of the speed of light in vacuum to the speed of light in the material. The imaginary part is the **extinction coefficient** → **dielectric function**.

relativistic particle – a particle moving at a speed comparable with the speed of light.

remanent magnetism – a magnetization left in a specimen after the removal of a magnetic field.

Renner–Teller effect – splitting in the vibrational levels of molecular entities due to even terms in the vibronic perturbation expansion. This is generally a minor effect for non-linear molecular entities compared to the **Jahn–Teller effect**, which is due to the odd terms. For linear molecular entities it is the only possible vibronic effect characteristic of degenerate electronic states.

First described in: R. Renner, *Zur Theorie der Wechselwirkung zwischen Elektronen- und Kernbewegung bei dreiatomigen, stabförmigen Molekülen*, Z. Phys. **92**, 172–193 (1934).

research misconduct – fabrication, falsification, or plagiarism in proposing, performing or reviewing research, or in reporting research results. A finding requires that: there be a significant departure from accepted practices of the relevant research community; and the misconduct be committed intentionally or knowingly, or recklessy; and the allegation be proven by a preponderance of evidence. This new definition of scientific misconduct arose in recent years after the discovery of several cases of misconduct also in nanoscience, as in the case of the nanophysicist Jan Hendrik Schön regarding the discovery of new nanodevices at Bell Laboratories in 1999–2002 and the south-Korean cloning researcher Woo Suk Wang regarding the creation of embryonic stem cells in 2005–2006.

resistance (electrical) – the property of an electric circuit element to obstruct current flow by causing electrical energy to be dissipated in the form of heat.

resistivity – the ratio of the electric field in a material to the density of the electric current passing through it. Phenomenologically, substances are broadly classified into three categories according to the value and temperature dependence of their resistivities: (i) **conductors** (10^{-6}–10^{-4} Ω cm, positive temperature coefficient of resistivity), (ii) **semiconductors** (10^{-4}–10^{9} Ω cm, negative temperature coefficient of resistivity), and (iii) **insulators** ($>10^{10}$ Ω cm, in general negative temperature coefficient of resistivity).

RESOLFT – an acronym for a **reversible saturable optically linear fluorescence transitions microscopy**.

resonance – a phenomenon exhibited by a system acted upon by an external periodic driving force in which the resulting amplitude of oscillation of the system becomes large when the frequency of the driving force approaches a certain value, which is usually a natural free oscillation frequency of the system.

resonant scattering – scattering of a photon by a quantum mechanical system (usually an atom or nucleus) in which the system first absorbs the photon by undergoing a transition from one of its energy state to one of higher energy and subsequently reemits the photon by the exact inverse transition.

resonant tunneling – a charge carrier tunneling process in which the electron transmission coefficient through a structure is sharply peaked about certain energies, analogous to the sharp transmission peaks, as a function of wavelength evident through optical filters such as a **Fabry–Pérot resonator**. It usually arises when charge carriers pass through a quantum well in which a quantized energy level is lined up with the energy level in the injected electrode when the external voltage is increased.

The simplest device demonstrating the phenomenon, which is a **resonant tunneling diode**, consists of a **quantum well** formed in a double tunnel barrier structure with emitter and collector contacts. Its energy band diagrams and current voltage characteristic are shown in Figure R.4.

The barriers are thin enough so that under certain circumstances electrons can tunnel from the emitter through the barrier into the well. At the same time the well is thin enough for the density of states to break up into a number of two-dimensional sub-bands. In the example considered here, only one sub-band is localized in the well at an energy $E_1 = \hbar^2\pi^2/(2m^*a^2)$ above the conduction band edge, where m^* is the electron effective mass and a is the well width. The important point is that at zero external bias E_1 is higher than the **Fermi energy** E_F in the contact regions on either side of barriers. Therefore, when a vanishingly small voltage is initially applied there are no states in the quantum well for the electrons to tunnel into. As a consequence, the only current flowing at low bias is that due to thermal emission over the barriers, which can be made negligibly small for high barriers. The applied voltage is dropped mostly across the resistive regions, namely the barriers. As the bias is increased the resulting electric field gives rise to appreciable band bending. The emitter region is warped upwards, and the collector region is warped downwards.



Figure R.4 Conduction band diagrams and current–voltage characteristics of a resonant tunneling diode.

Eventually at a certain voltage, the Fermi energy on the emitter contact is pulled through the resonant level E_1. As the Fermi level lines up with the resonant state in the well, a large current flows because of the increased transmission from emitter to collector. Electrons pass the well with energy and momentum conservation, which provides their highest transmission probability. At the same time, the back flow of electrons is suppressed as they meet a large potential barrier in the collector region. These conditions give an increase in the current up to the peak value.

When the applied voltage is further increased, the energy of the confined state drops below the Fermi energy in the emitter. At this point there are no electrons which can tunnel into the quantum well and still conserve energy and momentum, and the current through the device falls. The gradient of the current–voltage curve is now negative giving rise to a region of **negative differential resistance**, which makes the device useful as a high-frequency amplifier. At still higher bias the current begins to grow again because those electrons which are thermally activated over the barrier experience a large electric field and can contribute a significant current.

For an ideal double-barrier structure with identical barrier and contact parameters the current–voltage curve is symmetrical about the origin. The peak of the current corresponds to the voltage $2E_1/e$. Asymmetry is more typical for real structures arising from several technology-related sources, such as asymmetry in impurity and defect distribution through the structure or differences in roughness of interfaces.

For many applications, devices with a negative differential resistance should have a large peak current and a small valley current, where the latter is the minimum current following the peak current as the magnitude of the voltage increases. Therefore an important figure of merit for such devices is the **peak-to-valley ratio**. For resonant tunneling diodes it is in the range from 4 : 1 to 60 : 1 at room temperature depending on the geometry and well/barrier materials. It can be much higher at lower temperatures. Note that with a temperature increase the peak-to-valley ratio decreases until negative differential resistance completely vanishes. This reduction is simply related to the increase in off-resonant current over the barrier due to thermionic emission as well as the spreading of the distribution function around the resonant energy, which decreases the peak current. The valley current is also increased at higher temperatures as a result of phonon-assisted tunneling. Peak current density in excess of 10^5 A cm^{-2} may be obtained at room temperature. The highest peak current density and the peak-to-valley ratio are not achievable in the same structure because there is usually a trade-off between these two parameters in terms of device design.

First described in: D. Bohm, *Quantum Theory* (Prentice Hall, Englewood Cliffs, NJ, 1951), p. 283 – the phenomenon; L. V. Iogansen, *On the possibility of resonance passage of electrons in crystals through a system of barriers*, Zh. Eksp. Teor. Fiz. **45**(2), 207–213 (1963) – in Russian – theoretical description; L. Esaki, R. Tsu, *Superlattice and negative differential conductivity in semiconductors*, IBM J. Res. Dev. **14**(1), 61–65 (1970) – experimental resonant tunneling diodes.

Recognition: in 1973 L. Esaki received the Nobel Prize in Physics for his experimental discoveries regarding tunneling phenomena in semiconductors.

See also www.nobel.se/physics/laureates/1973/index.html.

rest mass – the mass of a particle in an inertial coordinate system with three space coordinates and one time coordinate (**Lorentz frame**) in which it is at rest.

Retger law states that properties of crystalline mixtures of isomorphous substances are continuous functions of the percentage composition.

First described by Retger in 1889.

reversible logic – logic devices organized in such a way as to permit arbitrary patterns of logically reversible information to be processed in 3D space. They entail no minimum entropy per operation. Reversible or information-lossless circuits are useful for digital signal processing, communication, computer graphics, cryptography, and quantum computation.

More details in: A. N. Al-Rabadi, *Reversible Logic Synthesis* (Springer, Berlin, 2003).

reversible saturable optically linear fluorescence transitions (RESOLFT) microscopy → **fluorescence nanoscopy**.

First described in: M. Hofmann, C. Eggeling, S. Jakobs, S. W. Hell, *Breaking the diffraction barrier in fluorescence microscopy at low light intensities by using reversibly photoswitchable proteins,* Proc. Natl. Acad. Sci. (PNAS) **102**(49), 17565–17659 (2005).

RHEED – an acronym for a **reflection high-energy electron diffraction**.

rhombic lattice → **orthorombic lattice**.

rhombohedral lattice → **trigonal lattice**.

ribosome – a cellular particle consisting of a **protein** and nucleic acid. It is responsible for the transition of the genetic information encoded in nucleic acids into the primary sequence of proteins.

Richardson constant → **Richardson equation**.

Richardson–Dushman equation → **Richardson equation**.

Richardson effect → **Einstein–de Haas effect**.

Richardson equation represents the saturation current density of electrons emitted from a hot metal at a temperature T in the form $j = AT^{1/2} \exp(-\phi/k_B T)$, where A is a constant and ϕ is the thermionic work function. It was later modified by Dushman using the quantum theory concept to give $j = BT^2 \exp(-\phi/k_B T)$, where B is the material-dependent parameter usually called the **Richardson constant**. It got the name **Richardson–Dushman equation**. Both equations have good agreement with experiment because the relationships are dominated by the exponential term. The plot $\log(j/T^2)$ versus $1/T$ is called a **Richardson plot** and helps to determine ϕ.

First described in: O. W. Richardson, *On the negative radiation from hot platinum,* Proc. Camb. Phil. Soc. **11**, 286–295 (1901); S. Dushman, *Electron emission from metals as a function of temperature,* Phys. Rev. **21**(6) 623–636 (1923).

More details in: S. Dushman, *Thermionic emission,* Rev. Mod. Phys. **2**(4), 381–476 (1930).

Recognition: in 1928 O. W. Richardson received the Nobel Prize in Physics for his work on the thermionic phenomenon and especially for the law named after him.

See also www.nobel.se/physics/laureates/1928/index.html.

Richardson plot → **Richardson equation**.

Righi–Leduc coefficient → **Righi–Leduc effect**.

Righi–Leduc effect – appearance of a transverse temperature gradient in an electronic conductor when it is placed in a magnetic field **H** and a temperature difference is maintained along it. It is described by the equation $\nabla_{tr} T = S\mathbf{H} \times \nabla_{long} T$, where S is the **Righi–Leduc coefficient**.

First described in: A. Righi, Mem. Acc. Lincei **4**, 433 (1887); M. A. Leduc, J. Phys. 2e série **6**, 378 (1887).

Ritz procedure → **variation principle**.

Rivest–Shamir–Adleman algorithm forms a base of an encryption and decryption. It has the property that publicly revealing an encryption key does not thereby reveal the corresponding decryption key. In the algorithm two large prime numbers are first generated, then multiplied, and through additional operations a set of two numbers that forms the encryption key and another set that constitutes the decryption key are obtained. Once the two keys have been established, the original prime numbers can be discarded. For encryption/decryption both keys are needed, but only the owner of the decryption key needs to know it. The security of the algorithm depends on the difficulty of factoring large integers.

First described in: R. L. Rivest, A. Shamir, L. Adleman, *A method for obtaining digital signatures and public-key cryptosystems*, Commun. Assoc. Comput. Mach. **21**(2), 120–126 (1978).

R-matrix theory → **random matrix theory**.

RNA – an acronym for **r**ibo**n**ucleic **a**cid, which is a complex compound of high molecular weight that functions in cellular **protein** synthesis and replaces **DNA** as a carrier of genetic codes in some viruses. It consists of ribose nucleotides in strands of varying lengths. The structure varies from helical to uncoiled strands. The nitrogenous bases in RNA are adenine, guanine, cytosine, and uracil.

There are three main types of RNA: messenger RNA (**mRNA**), transfer RNA (**tRNA**) and ribosomal RNA (**rRNA**). In protein formation, mRNA carries codes from the DNA in the nucleus to the sites of protein synthesis in the ribosomes. Ribosomes are composed of rRNA and protein; they can ‘‘read’’ the code carried by the mRNA. A sequence of three nitrogenous bases in mRNA specifies incorporation of an amino acid. The compound tRNA brings the amino acids to the ribosomes where they are linked into proteins. It is sometimes called soluble or activator, and contains fewer than 100 nucleotide units. Other types of RNA contain thousands of units.

First described in: R. W. Holley, J. Apgar, G. A. Everett, J. T. Madison, M. Marquisee, S. H. Merrill, J. R. Penswick, A. Zamir, *Structure of ribonucleic acid*, Science **147**, 1462–1465 (1965) – the structure of RNA.

Recognition: in 1968 R. W. Holley, H. G. Khorana, and M. W. Nirenberg received the Nobel Prize in Physiology or Medicine for their interpretation of the genetic code and its function in protein synthesis.

See also www.nobel.se/medicine/laureates/1968/index.html.

roadmap – an extended look at the future of a chosen field of research composed from the collective knowledge of the researchers involved in that field.

Roosbroek–Schockley relation links an emission rate R_{cv} for transitions from the conduction band to the valence band and the absorption rate P_{vc} for inverse transitions from the valence to conduction band in semiconductors and dielectrics at thermal equilibrium as $P_{vc}\rho(\nu) = R_{vc}(\nu)$, where $\rho(\nu)$ is the photon density (photon energy density divided by the photon energy).

First described in: W. van Roosbroek, W. Schockley, *Photon radiative recombination of electrons and holes in germanium*, Phys. Rev. **94**(6), 1558–1560 (1954).

rotamers → **isomers**.

rotaxane (rotor and axle) – a **supramolecular** assembly in which one or many cycle units are threaded onto a linear segment. Different types of rotaxanes are illustrated in Figure R.5.

Stopper groups preventing the macrocyclic rings from dethreading are their typical parts. Those having no stopper groups are referred to as **pseudorotaxanes**.



Figure R.5 The types of rotaxanes.

rRNA – ribosomal RNA → **RNA**.

Ruderman–Kittel oscillations = **Friedel oscillations**.

First described in: M. A. Ruderman, C. Kittel, *Indirect exchange coupling of nuclear magnetic moments by conduction*, Phys. Rev. **99**(1), 96–102 (1954).

Russell–Saunders coupling – a process for building many-electron single-particle eigenfunctions of orbital angular momentum and spin. The orbital functions are combined to make an eigenfunction of the total spin angular momentum and then the results are combined into eigenfunctions of the total angular momentum of the system.

First described in: H. N. Russell, F. A. Saunders, *New regularities in the spectra of the alkaline earths*, Astrophys. J. **61**, 38–69 (1925).

Rutherford backscattering spectroscopy (RBS) – a technique of nondestructive elemental analysis of condensed matter. Monoenergetic light ions, usually H^+, He^+, C^+, N^+, or O^+ with energies in the range 0.5–4.0 MeV, are used to probe a sample. When these ions strikes atoms in the target sample, the energy of backscattered ions appears to be characteristic of the scattering atoms and their depth location. The energy distribution and the intensity of the scattered ion beam recorded with a suitable detector is a function of atomic number, concentration and depth distribution of the atoms scattering the ions bombarding the sample. The thickness of thin films and depth profiles of foreign atoms can be measured within a few hundred nanometers of the surface when the foreign atoms are of greater atomic mass than the host material.

Rutherford scattering – elastic scattering of charged atomic particles by the Coulomb field of an atomic nucleus.

Rutherford scattering cross section gives effective cross section for scattering of two non-relativistic particles interacting via Coulomb forces within a solid angle $d\Omega$ in the form:

$$\frac{d\sigma}{d\Omega} = \left(\frac{q_1 q_2}{2mv^2}\right)^2 \sin^{-4}\left(\frac{\theta}{2}\right),$$

where q_1 and q_2 are charges of the particles, $m = m_1 m_2/(m_1 + m_2)$, m_1 and m_2 are masses of the particles, v is the velocity of one particle with respect to the other, and θ is the scattering angle.

First described in: E. Rutherford, *On the scattering of* α *and* β *particles by matter and the structure of the atom*, Phil. Mag. **21**, 669–688 (1911).

Rydberg atom – a cooled excited atom in which an outer electron has a radius larger than that in the ground state. An ensemble of such atoms is called a **Rydberg gas**. The more highly excited the atoms are, the more susceptible they are to environmental conditions, and the stronger their interactions with each other. Rydberg atoms do not move or collide because they are cooled, but the electron orbits of adjacent atoms can overlap. This gives rise to a distinction in properties between the Rydberg gas and a collection of the same atoms in the ground state.

Rydberg constant → **Rydberg formula**.

Rydberg formula determines the full spectrum of light emission from hydrogen as

$$\frac{1}{\lambda_{\text{vac}}} = R_H \left(\frac{1}{n_1^2} - \frac{1}{n_2^2} \right),$$

where λ_{vac} is the wavelength of the light emitted a in vacuum, R_H is the Rydberg constant for hydrogen ($2\pi^2 m_0 e^4/(ch^3) = 109737.31\ \text{cm}^{-1}$), and n_1 and n_2 are integers such that $n_1 < n_2$. By setting n_1 equal to 1 and letting n_2 run from 2 to infinity, the spectral lines known as the **Lyman series** converging to 91 nm are obtained. In the same manner the **Balmer series** ($n_1 = 2, n_2$ runs from 3 to infinity, converging to 365 nm) and the **Paschen series** ($n_1 = 2, n_2$ runs from 4 to infinity, converging to 821 nm) are obtained. The formula can be extended for use with any chemical element:

$$\frac{1}{\lambda_{\text{vac}}} = RZ^2 \left(\frac{1}{n_1^2} - \frac{1}{n_2^2} \right).$$

Here R is the Rydberg constant for this element, and Z is the atomic number that is the number of protons in the atomic nucleus of the element.

First described in: J. R. Rydberg, *On the structure of the line spectra of the chemical elements*, Phil. Mag. **29**, 331–337 (1890).

Rydberg gas → **Rydberg atom**.

S

From Saha equation to synergetics

Saha equation → **exciton**.

First described in: M. N. Saha, *On a physical theory of stellar spectra*, Proc. R. Soc. Lond., Series A, **99**(697), 135–153 (1921); M. N. Saha, *Versuch einer Theorie der physikalischen Erscheinungen bei hohen Temperaturen mit Anwendungen auf die Astrophysik*, Z. Phys. **6**(1) 40–55 (1921).

Sakata–Taketani equation – a relativistic wave equation for a particle with spin 1 whose form is similar to that of the nonrelativistic **Schrödinger equation**.

First described in: M. Taketani, S. Sakata, *On the wave equation of meson*, Proc. Phys. Math. Soc. Jap. **22**, 757–770 (1940), (Reprinted in Suppl. Progr. Theor. Phys. **22**, 84–97 (1955)).

SAM – an acronym for a **self-assembled monolayer**.

saturated hydrocarbons → **hydrocarbons**.

saturated pattern excitation microscopy (SPEM) → **fluorescence nanoscopy**.

First described in: R. Heintzmann, T. M. Jovin, C. Cremer, *Saturated patterned excitation microscopy – a concept for optical resolution improvement*, J. Opt. Soc. Am. A **19**, 1599 (2002); M. G. L. Gustafsson, *Nonlinear structured-illumination microscopy: Wide-field fluorescence imaging with theoretically unlimited resolution*, Proc. Natl. Acad. Sci. (PNAS) **102**(37), 13081–13086 (2005).

saturated structured illumination microscopy (SSIM) → **fluorescence nanoscopy**.

First described in: R. Heintzmann, T. M. Jovin, C. Cremer, *Saturated patterned excitation microscopy – a concept for optical resolution improvement*, J. Opt. Soc. Am. A **19**, 1599 (2002); M. G. L. Gustafsson, *Nonlinear structured-illumination microscopy: Wide-field fluorescence imaging with theoretically unlimited resolution*, Proc. Natl. Acad. Sci. (PNAS) **102**(37), 13081–13086 (2005).

SAXS – an acronym for a **small angle X-ray scattering**.

SCALPEL – an acronym for a **scattering with angular limitation projection electron-beam lithography**.

scanning capacitance microscopy (SCM) uses information obtained from the change in electrostatic capacitance between a surface of a sample and a probe scanning just above the surface. It is usually realized with an **atomic force microscope** (AFM) equipped with an ultrahigh frequency resonant capacitance sensor connected to a conducting probe as shown in Figure S.1. The technique is used to extract two-dimensional charge carrier profiles in semiconductor samples.

The fundamental principle of SCM is based on the metal-oxide-semiconductor concept. The tip of the conducting probe acts as the metal contacting the layer of insulating oxide grown on top of the semiconductor sample. The AFM employed is operated in the contact mode.

The tip–sample capacitance is probed by modulation of the carrier concentration in the semiconductor layer under the tip with a bias-containing alternating current (*ac*) and direct current (*dc*) components. As a practical matter, the capacitance variation $\mathrm{d}C/\mathrm{d}V$ is measured with high accuracy because the capacitance itself is too small to be measured reliably. The mapped in scanning area $\mathrm{d}C/\mathrm{d}V$ is a function of the lateral carrier concentration in the subsurface layer of the semiconductor sample.

More details in: Roadmap of Scanning Probe Microscopy, edited by S. Morita (Springer Verlag, Berlin Heidelberg, 2007).



Figure S.1 Schematic of scanning capacitance microscopy.

scanning electron microscopy (SEM) – a microscopy technique in which a beam of electrons, a few tens of nanometers in diameter or thinner, systematically sweeps over a specimen and the intensity of secondary electrons generated at the point of impact of the beam on the specimen is measured.

scanning Hall probe microscopy (SHPM) is a technique which incorporates the accurate sample approach and positioning of **STM** with a semiconductor Hall sensor. It exploits the high sensitivity of the Hall probe (down to 10^3 μ_B), which allows the pick-up of tiny magnetic signals in a wide range of temperature and magnetic fields. The main advantage of SHPM is to be directly sensitive to stray field **B** by means of the **Hall effect**, so the local field is measured by the sensor without interacting with the surface. In the first application, the corner of the SHPM sensor was gold coated and used as an STM tip for the positioning of the device on the surface, even allowing the simultaneous acquisition of SHPM and STM images. More recently other techniques have been developed for the approach to nonconducting surfaces. The lateral resolution of SHPM is related to the dimensions of the electrical channels of the Hall probe.

First described in: A. M. Chang, H. D. Hallen, L. Harriott, H. F. Hess, H. L. Kao, J. Kwo, R. E. Miller, R. Wolfe, J. van der Ziel, *Scanning Hall probe microscopy*, Appl. Phys. Lett. **61**(16), 1974–1976 (1992).

More details in: A. Oral, *Scanning Hall probe microscopy: quantitative & non-invasive imaging and magnetometry of magnetic materials at 50 nm scale*, in *Magnetic Nanostructures*, edited by B. Aktas, F. Mikailov, L. Tagirov, Springer Series in Materials Science **94** (Springer, Berlin 2007) pp. 7–14.

scanning probe lithography (SPL) – a lithographic technique employing a probe of a **scanning tunneling microscope** (STM) or **atomic force microscope** (STM) to fabricate surface structures with a size from hundreds of nanometers down to the atomic scale. The most practical approaches are based on the use of high electric field and current density between tip and substrate for **atomic engineering**, modification of **Langmuir-Blodgett films** and **self-assembled monolayers**, selective anodic oxidation of substrates and surface deposition of materials. Electrons injected from the tip apex are employed for **electron-beam lithography**. Mechanical modification of the material by the tip can be used for direct writing of grooves.

scanning SQUID microscopy (SSM) – a powerful tool for imaging magnetic fields above sample surfaces. It combines low-temperature positioning with a single-chip miniature **SQUID** magnetometer to make a sensitive and reliable magnetic field imaging instrument. There are various schemes for scanning the sample and for coupling the sample field into the SQUID sensor. One can distinguish two classes. In the first, both sample and SQUID are held at low temperatures either in a common vacuum space or in a cryogenic fluid. This allows for minimum spacing between SQUID and sample and therefore the best spatial resolution. In the second class, the SQUID is cold but the sample is warm and can be exposed to the atmosphere. In this case SQUID and sample are separated by some form of thermal insulation. This has the advantage of not requiring sample cooling, but entails some sacrifice in spatial resolution.

First described in: A. Mathai, D. Song, Y. Gim, F. C. Wellstood, *One-dimensional magnetic flux microscope based on the dc superconducting quantum interference device*, Appl. Phys. Lett. **61**(5), 598–600 (1992); J. R. Kirtley, M. B. Ketchen, K. G. Stawiasz, J. Z. Sun, W. J. Gallagher, S. H. Blanton, S. J. Wind, *High-resolution scanning SQUID microscope*, Appl. Phys. Lett. **66**(9), 1138–1140 (1995).

More details in: J. R. Kirtley, J. P. Wikswo Jr., *Scanning SQUID microscopy,* Ann. Rev. Mater. Sci. **29**, 117–148 (1999).

scanning tunneling microscopy (STM) – a technique based on the ability to position with extremely high precision an atomically sharp probe in close proximity to the sample surface. The physics behind the technique is schematically illustrated in Figure S.2.



Figure S.2 Tip–sample geometry in scanning tunneling microscopy.

A sharp metal probe tip, typically made of tungsten, is positioned over the surface of a conducting or semiconducting sample at a distance of about one nanometer or less. When a bias voltage V is applied between the sample and the tip, electrons tunnel through the potential barrier separating them. The magnitude of the tunneling current depends primarily on three factors: (i) the probability that an electron with energy will tunnel through the potential energy barrier between the sample and the tip, which varies exponentially with the tip–sample separation z; (ii) the electronic density of states at the sample surface; (iii) the electronic density of states at the tip. The last two factors are represented by the barrier potential U in the current dependence in the figure. The extreme sensitivity of the tunneling current to the separation between the tip and the sample surface is used in an electronic feedback loop that permanently adjusts the tip–sample separation, maintaining a constant current when the tip is scanned over the surface. Piezoelectric scanners are used for this. Thus, it yields a profile of the local electronic density of states resembling the arrangement of atoms at the surface and their chemical nature. STM has vertical resolution of 0.01–0.05 nm and lateral resolution less than 0.3 nm. It can image areas as large as several hundreds of micrometers.

First described in: G. Binning, H. Rohrer, *Scanning tunneling microscopy,* Helv. Phys. Acta **55**(6), 726–735 (1982); G. Binning, C. Gerber, H. Rohrer, E. Weibel, *Tunneling through controllable vacuum gap,* Appl. Phys. Lett. **40**(2), 178–180 (1982);

G. Binning, H. Rohrer, Ch. Gerber, E. Weibel, *Surface studies by scanning tunneling microscopy*, Phys. Rev. Lett. **49**(1), 57–61 (1982).

More details in: Handbook of Nanotechnology, edited by B. Bhushan (Springer, Berlin, 2004).

Recognition: in 1986 G. Binning and H. Rohrer received the Nobel Prize in Physics for their design of the scanning tunneling microscope.

See also www.nobel.se/physics/laureates/1986/index.html.

scattering – a change in the direction of a propagating particle or wave caused by inhomogeneity of the transmitting medium.

scattering matrix → ***S*-matrix**.

scattering with angular limitation projection electron-beam lithography (SCALPEL) – the approach combining high resolution and wide process latitude of **electron-beam lithography** with the throughput of a parallel projection system. It is schematically shown in Figure S.3. The mask consisting of a low atomic number membrane and a high number pattern layer is uniformly irradiated with high energy electrons. They are chosen to be essentially transparent to the electron beam, so very little of the beam energy is deposited on it. The portion of the beam which passes through the high atomic number pattern layer is scattered through angles of few milliradians. An aperture in the back focal plane of the electron projection imaging lenses stops the scattered electrons and produces a high-contrast image in the plane of the semiconductor wafer. One obtains lithography results down to less than 100 nm.

First described in: S. D. Berger, J. M. Gibson, *New approach to projection-electron lithography with demonstrated 0.1 μm linewidth*, Appl. Phys. Lett. **57**(2), 153–155 (1990).



Figure S.3 Basic principle of the SCALPEL technique. After L. R. Harriot, *Scattering with angular limitation projection electron beam lithography for sub optical lithography*, J. Vac. Sci. Technol. B **15**(6), 2130–2135 (1997).

More details in: L. R. Harriot, *Scattering with angular limitation projection electron beam lithography for sub optical lithography*, J. Vac. Sci. Technol. B **15**(6), 2130–2135 (1997).

Schoenflies symbols (notations) – symbols representing rotation axes, mirror rotation axes, order of rotations and other elements of symmetry operations used to describe symmetry of molecules. They are widely used in spectroscopy.

First described in: A. Schoenflies, *Krystallsysteme und Krystallstruktur* (Teubner, Leipzig 1891) (Reprinted by Springer, Berlin, 1984).

Schottky barrier – a barrier to a semiconductor, usually formed by metals, characterized by the formation of a charge carrier depleted layer in the semiconductor. Under an external voltage V applied, an electric current is passing through the barrier mainly due to the thermionic emission. Within this mechanism the current density is $j = B^* T^2 \exp(-\phi^*/k_B T)\exp(eV/nk_B T)[1 - \exp(eV/k_B T)]$, where B^* is the effective **Richardson constant** for the semiconductor, ϕ^* is the effective zero bias barrier height, and n is the **ideality factor**.

First described in: W. Schottky, *Halbleitertheorie der Sperrschicht*, Naturwiss. **26**, 843 (1938).

Schottky defect – **lattice vacancy**.

First described in: W. Schottky, C. Wagner, *Theorie der geordneten Mischphasen*, Z. Phys. Chem. B **11**, 163 (1930).

Schottky effect – image-force-induced lowering of the potential energy for charge carrier emission from a metallic surface when an electric field is applied.

First described in: W. Schottky, *Vereinfachte und erweiterte Theorie der Randschicht-gleichrichter*, Z. Phys. **118**(9–10), 539–592 (1942).

Schottky emission (of electrons) – electric field induced emission of electrons from solids.

First described in: W. Schottky, *Über kalte und warme Elektronenentladungen*, Z. Phys. **14**(1), 63–106 (1923).

Schrödinger equation – the fundamental wave equation of nonrelativistic quantum mechanics. For a single particle of mass m in a potential $V(\mathbf{r})$ its **time-dependent** form is:

$$i\hbar \frac{\partial \Psi(\mathbf{r},t)}{\partial t} = -\frac{\hbar^2}{2m}\nabla^2 \Psi(\mathbf{r},t) + V(\mathbf{r})\Psi(\mathbf{r},t), \quad \text{where} \quad \nabla^2 = \frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2} + \frac{\partial^2}{\partial z^2}.$$

$\Psi(\mathbf{r},t)$ is the wave function (each electron is represented by a wave function). It describes time evolution of electron waves. The equation is often written as $i\hbar(\partial \Psi(\mathbf{r},t)/\partial t) = \mathbf{H}\Psi(\mathbf{r},t)$, where $\mathbf{H} = -(\hbar^2/2m)\nabla^2 + V(\mathbf{r})$ is the **Hamiltonian**

operator. The equation has various extensions, which may be used to describe the whole of nonrelativistic dynamics, including systems that are free ($V(\mathbf{r}) = 0$) as well as bound.

The square of the absolute value of a given wave function $|\Psi(\mathbf{r}, t)|^2 d\tau$ is interpreted as a probability of finding a particle represented by the wave function $\Psi(\mathbf{r}, t)$ in the volume element $d\tau$ at a position r at time t.

Besides, the equation provides calculations of the energy of the stationary states of a quantum system. The **time-independent Schrödinger equation** in the form

$$-\frac{\hbar^2}{2m}\nabla^2\Psi_n(\mathbf{r}) + V(\mathbf{r})\Psi_n(\mathbf{r}) = E_n\Psi_n(\mathbf{r}),$$

or equivalently $\mathbf{H}\Psi_n(\mathbf{r}) = E_n\Psi_n(\mathbf{r})$, is used for this. Here $\Psi_n(\mathbf{r})$ is the wave function of the quantum particle in an energy eigenstate of energy E_n, and n is the integer called the quantum number. No arbitrary postulates concerning quantum numbers are required; instead, integers enter automatically in to the process of finding satisfactory solutions of the wave equation.

In the realm of quantum physics the **Schrödinger equation** plays a role of similar importance to that which Newton's equation of motion does for classical physics.

First described in: E. Schrödinger, *Quantisierung als Eigenwertproblem (erste Mitteilung)*, Ann. Phys. **79**(4), 361–376 (1926).

Recognition: in 1933 E. Schrödinger shared with P. A. M. Dirac the Nobel Prize in Physics for the discovery of new productive forms of atomic theory.

See also www.nobel.se/physics/laureates/1933/index.html.

Schrödinger's cat – the cat proposed by E. Schrödinger to be considered as an object in a thought experiment showing the absurdity of applying quantum mechanics to macroscopic objects. He invited one to imagine placing a cat in a box, along with a vial of poison that is connected to a radioactive atom. When the atom decays, it releases the poison, which kills the cat. If the box is closed, we do not know whether the atom has decayed or not. It means that the atom can be in a superposition of two states – decayed and nondecayed, at the same time. Therefore, the cat can be both dead and alive at the same time. Quantum mechanically his state can be described as $|\Psi\rangle_{\text{cat}} = |\text{alive}\rangle + |\text{dead}\rangle$, which is now known as the **Schrödinger cat state**. This clearly shows that describing a macroscopic object, such as a cat, in quantum terms is ridiculous. E. Schrödinger concluded that there was obviously a boundary between the microscopic world of atoms and quantum mechanics and the macroscopic world of cats and classical mechanics. The cat is a macroscopic object, the states of which (alive or dead) could be distinguished by a macroscopic observation as distinct from each other whether observed or not. He calls this "the principle of state distinction" for macroscopic objects, which is in fact the postulate that the directly measurable system (consisting of the cat) must be classical.

First described in: E. Schrödinger, *Die gegenwärtige Situation in der Quantenmechanik*, Naturwiss. **23**(48), 807–812 (1935).

Schrödinger's cat state → **Schrödinger's cat**.

Schwinger variational principle – the technique used to calculate an approximate value or a linear of a quadratic functional, such as scattering amplitude or reflection coefficient, when the function for which the functional is evaluated is the solution of an integral equation.

First described in: J. Schwinger, *On gauge invariance and vacuum polarization*, Phys. Rev. **82**(5), 664–679 (1951).

Schwoebel effect = **Ehrlich–Schwoebel effect**.

First described in: R. L. Schwoebel, E. J. Shipsey, *Step motion on crystal surfaces*, J. Appl. Phys. **37**(10), 3682–3686 (1966).

scintillation – a localized emission of light of short duration produced in a suitable solid or liquid medium by the absorption of a single ionized particle or photon. Most of the energy of such particles is lost in their interaction with electrons in the medium that leads to excitation and ionization of some molecules. The subsequent deexcitation and recombination result in the emission of light quanta with a characteristic spectral distribution.

SCM – an acronym for **scanning capacitance microscopy**.

screened Coulomb potential – the interatomic pair screening potential in the form

$$V(r) = \frac{Z_1 Z_2 e^2}{r} \exp\left(-\frac{r}{a}\right),$$

where r is the interatomic distance, Z_1 and Z_2 are the atomic numbers of the interacting atoms, $a = a_B k/(Z_1^{2/3} + Z_2^{2/3})^{1/2}$, $k = 0.8\text{–}3.0$ is the empirical coefficient used to fit experimental data.

More details in: I. G. Kaplan, *Intermolecular Interactions: Physical Picture, Computational Methods and Model Potentials* (John Wiley & Sons, Chichester, 2006).

screening wave number – inverse screening length defined as

$$k = \left(4\pi e^2 \frac{\partial n}{\partial \mu}\right)^{1/2},$$

where n is the density of electrons and μ is the chemical potential → **Debye–Hückel screening length** and **Thomas–Fermi screening length**.

secondary ion mass spectrometry (SIMS) – a technique of destructive elemental analysis of condensed matter. An analyzed sample is bombarded with energetic ions, such as He^+, Ar^+, Xe^+ or metal ions. They in turn cause ejection (by sputtering) of secondary ions from the sample surface. These secondary ions are then detected and analyzed by a quadrupole mass spectrometer. Thus, the technique provides information about elemental composition of the sample surface layer. The primary generated signal results from a region typically of about 1–3 nm. When it is combined with layer-by-layer etching of the surface, near surface concentration profiles of impurities can be recorded. The diameter of the ion probe varies from a few μm for **noble gas** ions to less than 50 nm for metal ions (Cs^+, Ga^+).

Seebeck coefficient → **Seebeck effect**.

Seebeck effect – a development of a voltage in a loop composed of two different materials, say A and B, (metals, semiconductors) when their junctions are held at different temperatures, as shown in Figure S.4. The developed open-circuit voltage V_{AB} is proportional to the temperature difference ΔT. The coefficient of the proportionality is the **Seebeck coefficient** defined as

$$\alpha_{AB} = \lim_{\Delta T \to 0} \frac{V_{AB}}{\Delta T}.$$

First described in: T. J. Seebeck, *Magnetische Polarisation der Metalle und Erze durch Temperatur-Differenz*, Abh. Kön. Akad. Wiss. Berlin, 265–373 (1822).



Figure S.4 Schematic of Seebeck effect.

Seebeck effect in an organic molecule was measured for the first time in 2007. Two gold electrodes were coated with molecules of benzenedithiol, dibenzenethiodol or tribenzenedithiol, and one side was then heated to create a difference in temperature. For each degree Celsius of difference, a voltage difference of ∼10 μV was measured. This could open the door to more cost-effective thermoelectric converters.

First described in: P. Reddy, S.-Y. Jang, R. Segalman, A. Majumdar, *Thermoelectricity in molecular junctions*, Science **315**, 1568–1571 (2007).

selection rule – the statement specifying which electron transitions in atoms and molecules are allowed when a photon is emitted or absorbed. It was derived from the conservation of **angular momentum** of the electron, characterized by quantum numbers l and m_l. So, a transition is possible when $\Delta l = \pm 1$ and $\Delta m_l = 0, \pm 1$. The principal quantum number n can change by any amount consistent with the Δl for the transition because it does not relate directly to the angular momentum.

self-assembled monolayer (SAM) – an ordered molecular assembly formed by **adsorption** of an active surfactant on a solid surface. It is produced within a **self-assembling process**.

First described in: W. C. Bigelow, D. L. Pickett, W. A. Zisman, *Oleophobic monolayers. I. Films adsorbed from solution in nonpolar liquids*, J. Colloid Interface Sci. **1**, 513–538 (1946).

self-assembly – a process of construction of a structure from components acting under forces/motives internal or local to the components themselves, and arising through their interaction with the environment. In nanotechnology it supposes the adsorption and particular arrangement of molecules on a solid surface. It can be considered as a coordinated action of independent entities under local control of driving forces used to produce larger, ordered structures or to achieve a desired group effect. It is usually driven by chemisorption, being pronounced for highly energetic reactions between adsorbate and substrate molecules. In contrast to strong interaction with the substrate surface, the adsorbed molecules weakly interact with each other. Many examples of self-assembly can be found in the organic and inorganic world. Self-assembled monolayer films have an extremely low defect density, and are quite environmentally stable and mechanically robust. They serve as imaging layers in lithographic processes. Imaging layers are used for recording a pattern, either by masking, as with photon-assisted processes, or by direct writing, as with conventional electron beam writers and scanning probes. Nanometer scale high-resolution lithography with imaging layers fabricated via self-assembly is usually performed with the use of a **scanning tunneling microscope (STM)** or **atomic force microscope (AFM)** probes.

A monolayer film appropriate for high-resolution patterning via self-assembly should consist of three main functional parts. These are a substrate surface binding part, a spacer part and a surface functional part. While these parts are not fully interchangeable from one molecule to the next, different considerations have to be made for the selection of each. Positioning of functional groups and their recognition properties are better developed for organic materials than for inorganic ones, whereas electronic properties of the latter are much better understood. It is, therefore, envisaged that especially the combination of the different materials will permanently lead to new and fruitful approaches.

For the substrate surface binding part, a silane $RSiX_3$ ($R = CH_3, C_2H_5, \ldots$) is usually used to bind to hydroxyl (OH) groups, which typically terminate silicon and other technologically important surfaces. Hydrogen substituents on the silane, namely the ‘‘X’’ component, are most commonly methoxy groups (CH_2O), Cl or a mixture of the two. The composition of the surface binding part strongly affects film ordering, the tendency of the film to grow multilayers and, to a lesser extent, the packing density. A thiol (RSH) forms highly ordered layers on surfaces of GaAs and gold.

The spacer part has an effect on the interaction of the film with the writing tool. By moving the functional part away from the surface and closer to the high field of the tip, long spacer groups (multiple CH_2 groups, for example) can lower the dose or voltage threshold for exposure. The conjugated bonds found in phenyl groups are also somewhat conductive, and hence more amenable to STM operation.

The surface functional part actually defines properties of the ''new'' surface. For example, **amine** (NH_2) groups can be used as ligation sites for certain molecules. While not particularly active themselves, **halide**s (Cl, I, etc.) have an extremely high cross section for electron capture and subsequent desorption of the halide fragment. Subsequent processing can be based on either replacing the halide atom with a more reactive functional group or acting upon the fragment remaining after halide desorption. Alkyl-terminated surfaces are extremely inert and **hydrophobic**, being chemically identical to paraffin. As such, they are implemented for pattern transfer as masks against wet etching and, to a limited extent, dry etching. They are also used to enhance STM-induced etching of gold.

Processing steps illustrating the use of a self-assembling monolayer film for nanopatterning on a silicon substrate are shown in Figure S.5.

Before the film deposition the silicon substrate is cleaned and hydrogen passivated in dilute HF. Then it is immersed briefly in a solution of an organosilane monomer, removed and dried in order to fabricate a self-assembling monolayer film on the substrate.



Figure S.5 Replication of a high-resolution pattern by the use of a STM-exposed self-assembling monolayer film: (a) deposition of the self-assembling monolayer film, (b) pattern generation with an STM tip, (c) ligation of Pd catalyst, (d) electroless deposition of Ni. After E. S. Snow, P. M. Campbell, F. K. Perkins, *Nanofabrication with proximal probes*, Proceedings of the IEEE, **85**(4), 601–611(1997).

The list of appropriate organosilanes includes: octadecyltrichlorosilane, phenethyltrimethoxysilane, chloromethylphenyltrimethoxysilane, chloromethyl-phenethyltrimethoxisilane, monochlorodimethoxysilane versions of phenethyl-trimethoxysilane and phenethyltrimethoxysilane.

The monolayer film with a typical thickness of about 1 nm is exposed to low-energy electrons from an STM or conducting AFM tip according to a desired pattern. Exposure threshold voltage is in the range of 2–10 V, depending on the film composition, mainly by the terminal group, and substrate surface passivation. After patterning, the sample is immersed in the colloidal palladium, which selectively attaches to the unexposed surface of the self-assembled film. The sample is then rinsed and again immersed in a nickel borate electroless plating bath, where nucleation of metallic nickel is catalyzed by the surface attached palladium islands. The subsequent growth of the depositing nickel occurs anisotropically, and rough edges reproducing boundaries of the islands become smoothed down. The patterned metallic film is used as a hard etch mask. The achievable resolution is in the range of 15–20 nm.

Most aspects of assembly and self-assembly, such as positioning of functional groups and their recognition properties, are better developed for organic materials than for inorganic ones, whereas the electronic properties of the latter are much better understood. It is, therefore, envisaged that especially the combination of the different material types will lead to fruitful new approaches. It may be the case that assembly will take place via recognition of organic parts followed by derivatization with inorganic materials, or that small inorganic units modified with organic anchoring points are assembled into circuits in a single process.

Within the self-assembling approach, the ultimate dimensions of nanoelectronic elements of integrated circuits are defined by the dimensions of atoms and molecules. At ambient temperature it is probably easier to confine a molecule through its functional groups than a single atom. The development of fast methods for performing chemistry on single molecules is therefore important. Various probe techniques, like STM and AFM, play a key role in this field.

self-organization (in bulk solids) supposes particular arranging of strongly interacting atoms in solid state structures. Spontaneous self-organization processes occurring in the bulk of solids and at their surfaces provide an effective way of nanostructure fabrication, namely of **quantum wires** and **quantum dots**. The major driving force of these processes is the tendency of the solid to attain a stable atomic configuration corresponding to the minimum free energy of the system. In solids it usually results in spontaneous crystallization. A phase transformation leading to nucleation and growth of a new crystalline phase occurs only in thermodynamically nonequilibrium conditions typically present in supersaturated or strained systems.

Formation of a crystalline nucleus lowers the energy of the system by $\triangle g = g_{\mathrm{am}} - g_{\mathrm{cr}}$, because the crystalline phase (characterized by the energy g_{cr}) is always more stable than an amorphous phase (characterized by the energy g_{am}). This energy decrease is opposed by the increase of the surface energy of the growing nucleus. With $\triangle g$ calculated per unit volume of the new phase, an appearance of a nucleus of radius r with a specific surface energy σ^* gives the total change of free energy in the system $\triangle G = 4\pi r^2\sigma^* - 4/3\pi r^3 \triangle g$.

The free energy change varies non-monotonically as a function of the nucleus radius. It is illustrated in Figure S.6. For the formation of the nucleus surface, work must be carried out on the system, while in the formation of the nucleus bulk work is gained from the system. The free energy change has its maximum value for an atomic cluster of critical radius r_{cr}. It corresponds to $r_{\mathrm{cr}} = 2\sigma^*/\triangle g$.

Formation of a cluster smaller than the critical nucleus needs a positive free energy change, and therefore the system is unstable. The population of such nuclei exists in equilibrium distribution. Bigger nuclei are energetically favored to be formed. The rate of nucleation ν_{n} is proportional to the concentration of critical nuclei and to the rate at which these nuclei originate. It can be described as $\nu_{\mathrm{n}} \sim \exp(-\triangle G_{\mathrm{cr}}/k_{\mathrm{B}}T)\exp(-E_{\mathrm{a}}/k_{\mathrm{B}}T)$, where G_{cr} is the free energy of the critical nuclei formation, T the absolute temperature. The term $\exp(-E_{\mathrm{a}}/k_{\mathrm{B}}T)$ represents atomic diffusion contributing to the nucleation and subsequent growth of the nuclei. It is characterized by the activation energy E_{a}. Since G_{cr} is inversely proportional to T^2, the rate of nucleation will vary as $\exp(-1/T^3)$. Thus, it is evident that nucleation of any particular phase takes place within narrow temperature limits, below which nothing occurs and above which the reaction is extremely fast.

The spontaneous crystallization is widely implemented for fabrication of quantum dot structures without sophisticated **nanolithography**. It is realized within nanocrystal growth initiated in inorganic and organic matrices.



Figure S.6 Variation of the free energy change of nuclei as a function of their radii.

self-organization (during epitaxial growth) becomes apparent in an epitaxial growth on **vicinal surfaces** and when **Stranski–Krastanov growth mode** of thin films is realized. These are illustrated as follows.

A particular growth mode of an epitaxial film for a given couple of materials depends on the lattice mismatch and on the relation between surface and interface energies. It is important to note here that all energetic considerations are valid for an equilibrium state of the system. The formation of thin epitaxial films, which is often an out-of-equilibrium process, is hardly described within the pure energetic approach. Kinetic effects controlled by the deposition rate and substrate temperature can dramatically modify the growth mode. Nevertheless, the energetic consideration presented below is very useful for many practical cases, at least for predicting behavior of a system in equilibrium or quasi-equilibrium conditions.

In a lattice-matched system, the growth mode is governed by the interface and surface energies only. If the sum of the surface energy of the epitaxial film and the interface energy is lower than the energy of the substrate surface (the deposited material wets the substrate), growth occurs in the **Frank–van der Merwe growth mode**. Uniform coherent pseudomorphic and strained superlattices are fabricated in this case. It is also appropriate for fabrication of self-organized quantum wires. Monocrystalline substrates with a surface oriented slightly off one of the low-index planes (usually (001) or (311)), a vicinal surface, are used for this. Figure S.7 shows the main stages of the fabrication procedure. An as-prepared vicinal surface consists of planar equal-width terraces with low **Miller indices**. The neighboring terraces are separated by equidistant monoatomic or monomolecular steps. Such step bunching is typically homogeneous throughout a vicinal surface. The deposition starts with the wire material.

The substrate temperature is chosen so as to allow the deposited atoms to be mobile enough for diffusion around the surface. It is energetically favorable for them to stick at the steps rather than the middle of the terraces. Only a portion of the wire material corresponding to its thickness of less than one monolayer is



Figure S.7 Fabrication of quantum wires by self-organization during epitaxial growth on the (001) vicinal surface: (a) as-prepared surface, (b) deposition of the wire material, (c) half-monolayer of the wire material has been deposited, (d) complementing half-monolayer of the substrate material has been deposited, (e) burred quantum wire produced be repetition of steps c and d.

deposited in order to leave space for the subsequently deposited substrate material, which restores the steps to their original position in the plane, but a monolayer higher. By repeating the deposition of wire and then substrate materials one can fabricate in-built quantum wires. One of the main problems in practical application of the above approach is nonlinearity of the terrace edges, which usually have a wave-like shape. This naturally results in the formation of wave-like quantum wires. In order to fabricate ordered arrays of linear-type quantum wires one should facet the surfaces with artificial grooves. In this case wires nucleate and grow in the grooves.

Strained homogenous epitaxial films can start to grow layer-by-layer even when there is a certain lattice mismatch between deposited and substrate materials. Accumulation of the strain energy with an increase of the film thickness inevitably pushes the system to lower its energy by island formation, which occurs in the **Stranski–Krastanov growth mode**. In this case the self-organized growth of nanocrystalline islands on a monocrystalline substrate occurs via strain-induced transition from a two- to a three-dimensional structure (2D→3D) when the growing material has a noticeably bigger lattice constant than the substrate. Reduction of the total energy of the strained substrate/epilayer system is a driving force of the monocrystalline island formation. In contrast to a pseudomorphic two-dimensional layer, which can relax only in the direction perpendicular to the surface, the formation of three-dimensional islands leads to strain relief within and around the islands, resulting in more efficient relaxation.

Consider qualitatively the changes in the total energy of a mismatched system versus deposition time at a sufficiently low deposition rate eliminating kinetic effects. Figure S.8 shows schematically the changes in the total energy of a mismatched system versus time. The material (under compression) is deposited at a constant deposition rate until time point X is reached. Three main periods, indicated A, B and C, are distinguished.



Figure S.8 Time variation of the total energy of the epitaxial structure being grown in Stranski–Krastanov mode. After W. Seifert, N. Carlsson, J. Johansson, M.-E. Pistol, L. Samuelson, *In situ growth of nano-structures by metal-organic vapour phase epitaxy*, J. Cryst. Growth **170**(1–4) 39–46 (1997).

In the initial period A the epitaxial two-dimensional structure is growing layer-by-layer. The substrate is perfectly wetted. The elastic strain energy increases linearly with the volume of the deposited material. At the time point t_{cw} the critical wetting layer thickness is reached and further layer-by-layer growth becomes metastable. A supercritically thick wetting layer builds up, which means that the still continuous epitaxial layer is potentially ready to be broken under Stranski–Krastanov transition to a three-dimensional island structure. The extent of the metastability range depends primarily on the height of the transition barrier E_A.

The period B, representing 2D→3D transition, starts when the stored elastic energy is sufficient to overcome the transition barrier at the time point X. It is presumed that once the transition starts it can continue without further material supply, simply by consuming the excess material accumulated in the supercritically thick wetting layer. There are two stages, namely island nucleation and its subsequent growth, within this period. One can assume that thickness or strain fluctuations lead to the formation of the critical nuclei on a uniform surface. The thickness of the wetting layer at which spontaneous nucleation of three-dimensional islands starts mainly depends on the lattice mismatch of the substrate, deposited material and surface anisotropy. For example, in epitaxy of germanium onto monocrystalline silicon it happens when the thickness of germanium film exceeds a few monolayers. For a controlled nucleation ‘‘geometrical’’ or ‘‘strain’’ pre-patterning of the surface is needed.

The nucleation stage defines the surface density of the islands. As soon as the first overcritical nuclei have been formed, the islands themselves act as catalysts to decompose the wetting layer. An expected strain energy density profile along the interface between the substrate and the island is shown in Figure S.9. The surface



Figure S.9 Change in the local strain energy density at the substrate/epilayer interface related to the island formation and schematic of deformation of lattice planes inside and around a coherent island. After W. Seifert, N. Carlsson, J. Johansson, M.-E. Pistol, L. Samuelson, *In situ growth of nano-structures by metal-organic vapour phase epitaxy*, J. Cryst. Growth **170**(1–4) 39–46 (1997).

of the island represents the minimum in this potential, whereas the maximum is at the edge of the island. It is induced by the strain propagation along the substrate, which increases the inherent misfit between the substrate and wetting layer material around the island. The minimum is caused by the partial strain relaxation in the island, and this is a driving force for the material to crystallize at its surface. As a result, three-dimensional coherently strained dislocation-free monocrystalline islands are formed.

The subsequent growth of islands is enhanced by high supersaturation at the beginning of this period. It is characterized by rates tens times higher than conventional growth rates. Intrinsically rough surfaces grow very fast and disappear, whereas facets of low indexed planes $\{11n\}$ ($n = 0, 1, \sim 3$) become rate limiting. As a result, the islands have a pyramidal shape typically with {113} or {110} facets or a shape of elongated truncated pyramids. Although the growing islands are usually coherent to the substrate, non-coherent islands and related misfit dislocations starting at the interface can also be produced in the case of too high a material supply rate.

Further growth of the islands proceeds within the period C, but via a ripening mechanism. The system has lost most of the excess energy accumulated by strains. A difference in the Gibbs free energy between small and large islands maintains slow growth of larger ones at the expense of small islands. The process is mediated by surface diffusion.

The epitaxial deposition in the Stranski–Krastanov mode is successfully employed for the formation of 2–40 nm quantum dots made of $A^{III}B^{V}$ and $A^{II}B^{VI}$ semiconductors, germanium, SiGe alloys with remarkably uniform size distribution and high surface density. It permits one to exceed the critical thickness limitation of pseudomorphic growth without introducing dislocations. Several methods were developed in order to provide nanoscale positioning and site selectivity of the quantum dot formation. It is achieved by selective epitaxial growth in the windows of a nanopatterned mask fabricated by conventional electron-beam or scanning probe lithography.

SEM – an acronym for a **scanning electron microscopy**.

semiconductor – a substance whose electrical resistivity (10^{-4}–10^{9} Ωcm, negative temperature coefficient of resistivity) is intermediate between that of **conductors** and **insulators**. Semiconductors have an energy gap between valence and conduction band not higher than 5 eV.

Pure semiconductor materials (say 99.999%) are called intrinsic semiconductors as their properties are intrinsic to the material itself. By adding some impurities to a semiconductor its electrical properties are changed. Doped semiconductors are called extrinsic semiconductors. Impurities that cause electron type of conductivity (*n*-type) are called **donor**s and those producing hole type of conductivity (*p*-type) are called **acceptor**s.

Donor impurities are elements with valence higher than that of the component they substitute, and acceptor impurities are elements with valence lower than that of the component they substitute. In $A^{III}B^{V}$ compound semiconductors, a tetravalent element, such as Si and Ge, can be both a donor impurity if it substitutes a trivalent component or an acceptor impurity if it substitutes a pentavalent component. Such impurities are called amphoteric.

The main properties of studied monoatomic and binary compound semiconductors are presented in Appendix.

semiconductor equation – in a semiconductor at thermal equilibrium $np = n_i^2$, where n and p are the concentrations of electrons and holes, respectively; n_i is the intrinsic carrier concentration in this material. It does not depend on doping or the position of the **Fermi level**.

semiconductor injection laser – a semiconductor device emitting coherent light. In general, it consists of a $p - n$ junction in a direct gap semiconductor placed in an optical resonator that is formed by the polished facets perpendicular to the junction plane. The light emission is produced under forward bias of the $p - n$ junction as a result of radiative recombination of electrons and holes injected into the depletion layer associated with the junction. The wavelength of the emitted radiation is basically determined by the relation $\lambda \sim hc/E_g$, where E_g is the energy band gap of the semiconductor. Optical feedback is provided by the polished facets. Lasing starts at a certain current density, called the threshold current density, that in case of a device made of a single semiconductor is usually above 10^4 A cm^{-2}.

First described in: N. G. Basov, O. N. Crokhin, Yu. M. Popov, *The possibility of use of indirect transitions to obtain negative temperature in semiconductors*, Z. Eksper. Teor. Fiz. **39**(5), 1486–1487 (1960) – idea (in Russian); R. N. Hall, G. E. Fenner, J. D. Kingsley, T. J. Soltys, R. O. Carlson, *Coherent light emission from GaAs junctions*, Phys. Rev. Lett. **9**(9), 366–368 (1962) and M. I. Nathan, W. P. Dumke, G. Burns, F. H. Dill, Jr., G. Lasher, Appl. Phys. Lett. **1**(1), 62–64 (1962) – experiment.

semimetal – a metal with a small overlap between partially filled **valence** and **conduction bands**.

Shannon's entropy → **Shannon's theorems**.

Shannon's theorems – two theorems forming the basis of classical information theory.

The **noiseless coding theorem** states that the optimal code compresses each symbol to $H(X)$ bits asymptotically. Here $H(X)$ is the **Shannon's entropy**, which is an entropy of an ensemble X consisting of strings of symbols defined as $H(X) = -\sum_i p(i) \log p(i)$, where $p(i)$ is the probability of the i-th symbol. Thus, information can be measured, and these measurements are of practical importance in choosing methods for transmission of messages.

Sent and received symbols may differ from one another because of a noise in the transmitting channel. The conditional probability to receive j-th symbol from ensemble Y while sending i-th symbol from ensemble X is denoted $p(j|i)$. The Shannon's entropy for the ensemble Y is $H(Y) = -\sum_{ij} p(i|j)p(i)\log[\sum_k p(j|k)p(k)]$ and the **joint Shannon's entropy for two ensembles** is defined as $H(X, Y) = -\sum_{ij} p(j|i)p(i)\log[p(j|i)p(i)|$.

The **noisy channel coding theorem** states that for the optimal coding one symbol transmits C bits of information at maximum and the probability of error goes to zero as the number of symbols in the message goes to infinity. The channel capacity C is defined as the maximal value of mutual information $H(X) + H(Y) - H(X, Y)$ over all possible probability distributions $p(i)$ for fixed $p(j|i)$. Information can be transmitted faithfully, even if errors are generated during the communication. The most famous example of this is given for the bandwidth-limited and power-constrained transmitting channel in the presence of Gaussian noise, usually expressed in the form $C = W\log_2(1 + R)$, where C is measured in bits/s, W is the bandwidth (in Hertz), and R is the signal-to-noise ratio.

First described in: C. E. Shannon, *A mathematical theory of communication,* Bell Syst. Tech. J. **27**(3), 379–423; C. E. Shannon, *A mathematical theory of communication,* Bell Syst. Tech. J. **27**(4), 623–656 (1948); C. E. Shannon, *Communication theory of secrecy systems,* Bell Syst. Tech. J. **28**(4), 656–715 (1949).

More details in: A. Galindo, M. A. Martín Delgado, *Information and computation: classical and quantum aspects,* Rev. Mod. Phys. **74**(2), 347–423 (2002).

Sharvin resistance – the resistance of a point electric contact in the classical ballistic regime. It is entirely due to elastic backscattering at the geometrical narrowing of the ballistic point contact. Dissipative processes, which bring the electron system into thermodynamic equilibrium, take place far away from the point contact. Therefore, the cause of the resistance in this system is spatially separated from its corresponding Joule heating. When the width of the contact is comparable to the Fermi wavelength one comes to the case of quantum point contact for which the resistance is $h/(2e^2N)$, where N is the number of the occupied electron subbands (transmitting modes).

First described in: Yu. V. Sharvin, *A possible method for studying Fermi surfaces,* Zh. Eksp. Teor. Fiz. **48**(3), 984–985 (1965) – in Russian, Sov. Phys. JETP **21**(3), 655–656 (1965) – in English.

shear modulus → **Bowden–Tabor law**.

Shenstone effect – an increase in photoelectric emission of certain metals following passage of an electric current.

First described in: A. G. Shenstone, *Effect of an electric current on the photoelectric effect,* Phil. Mag. **41**, 916 (1921).

Shklovskii–Efros law states that temperature dependence of hopping conductivity in a disordered system has the form $\ln\sigma \sim T^{-1/2}$ at low temperatures when $\triangle E_C > k_BT$, where E_C is the gap in the density of states near the **Fermi level** of the system due to electron-electron Coulomb interaction. See more details in **hopping conductivity**.

First described in: A. L. Efros, B. I. Shklovskii, *Coulomb gap and law temperature conductivity of disordered systems,* J. Phys. C: Solid State Phys. **8**(4), L49–L51 (1975).

Shockley partial dislocation – a partial dislocation whose **Burger's vector** lies in the fault plane, so that it is able to glide, in contrast to **Frank partial dislocation**.

First described in: W. Shockley, W. T. Read, *Quantitative predictions from dislocation models of crystal grain boundaries,* Phys. Rev. **75**(4), 692–692 (1949).

Shockley–Queisser limit – the maximum efficiency one can reach with the conventional **solar cell** structure, also called **single material limit**. Using a detailed balance approach and assuming that each photon above the band gap gives rise to just one electron-hole pair, while all photons with energy below the band gap is lost, one comes to a theoretical maximum energy conversion efficiency of 30%. In particular Shockley and Queisser derived this uppermost conversion efficiency for an optimum band gap of 1.26 eV by modeling the sunlight as unconcentrated black body radiation at a temperature of 6000 K. This efficiency is relatively low, mainly because of the thermalization and transmission losses, which account for about 56% loss of photon energy. These losses are the result of the fact that a single energy band gap is used to convert a wide range of solar energy photons. While two-band systems are bounded by the Shockley–Queisser efficiency limit, higher efficiencies are possible for systems with more than two different Fermi-distributions. Examples are **multijunction solar cell**s, **impurity photovoltaic effect solar cell**s, **intermediate band solar cell**s, **quantum well solar cell**s, **up- and down-conversion solar cell**s, or **hot-carrier solar cell**s.

First described in: W. Shockley, H. J. Queisser, *Detailed balance limit of efficiency of p-n junction solar cells,* J. Appl. Phys. **32**(3), 510–519 (1961).

More details in: C. S. Solanki, G. Beaucarne, *Advanced solar cell concepts,* Energy for Sustainable Development – The Journal of the International Energy Initiative **11**, 17–23 (2007).

shock wave – a fully developed compression wave of large amplitude across which density, pressure and velocity change drastically. Imagine you have a projectile that flies faster than the speed of sound; it will push on the sound waves in front of it. But sound waves cannot travel faster than the speed of sound. Thus, the waves pile up against each other as they are created. These piled up waves are shock waves.

Shock waves can be produced by hurling a projectile or shooting a high-intensity **laser** at a crystal. Recently computer simulations have shown that sending shock waves through a **photonic crystal** could lead to faster and cheaper telecommunication devices, more efficient **solar cell**s, and advances in **quantum computation**.

More details in: Ia. B. Zeldovich, I. P. Raizer, *Elements of Gas Dynamics and the Classical Theory of Shock Waves* (Academic Press, New York, 1968); M. Rasmussen, *Hypersonic Flow* (Wiley, New York, 1994).

Shor algorithm – the factoring algorithm, where a quantum computer would be able to factor N numbers exponentially faster than any known classical computer algorithm. It determines the period of the function $a^n \mathrm{mod} N$, where a is a randomly chosen small number with no factors in common with N, and n is an integer. The value of $a^n \mathrm{mod} N$ is the remainder that is left over when a^n is divided by N. Once the period of this function is known, N can be rapidly factored using classical number theory. Quantum factoring works by using quantum parallelism to try out all possible values of n simultaneously and then applying a quantum Fourier transform to find the period. In the special case of $N = 15$, the period is always either 2 or 4, making it particularly easy to implement the algorithm and determine the period.

Fast quantum number factoring has profound implications in cryptanalysis, of many popular encryption algorithms.

First described in: P. W. Shor, *Polynomial time algorithms for prime factorisation and discrete logarithms on quantum computer,* SIAM J. Comp. **26**(5), 1484–1509 (1997).

shot noise in electrical circuits is a consequence of the discrete nature of the electric charge passing through a conductor. It results from fluctuations in the number of charge carriers. The mean square fluctuation of electrical current I corresponding to individual current pulses due to arrival of individual electrons in a frequency interval $\triangle f$ is $\overline{\triangle I^2} = 2eI\triangle f$.

First described in: W. Schottky, *Über spontane Stromschwankungen in verschiedenen Elektrizitätsleitern,* Ann. Phys. **57**, 541–567 (1918).

SHPM – an acronym for a **scanning Hall probe microscopy**.

Shubnikov–de Haas effect – periodic variation of electric resistivity of **degenerate** solids (metals, semiconductors) with $1/H$, where H is the strength of a static magnetic field. The period of variation depends on the magnetic field orientation with respect to the crystal axes directions in the solid. It is $2\pi\hbar e/cS$, where S is the maximum cross-sectional area of the **Fermi surface** regarding projection of the electron momenta onto the magnetic field. The effect is observed when $\hbar e/m^*c > k_B T$ and $eH/m^*c > \tau$, where m^* is the effective mass of electrons and τ is the electron relaxation time.

The phenomenon is caused by the changing occupation of the **Landau levels** in the vicinity of the **Fermi energy** in the plane perpendicular to the direction of the magnetic field applied.

First described in: L. V. Shubnikov, W. J. de Haas, *Resistance changes of bismuth crystals in a magnetic field at the temperature of liquid hydrogen,* Proc. K. Akad. Amsterdam **33**(4), 363–378 (1930).

Shubnikov groups – points group and space groups of crystals if one adds another element of symmetry, for example two-color symmetry that switches black to white or vice versa. They are also called **black-and-white groups** or **magnetic groups**. Thus, Shubnikov groups are useful when properties such as spin are to be considered over the normal crystallographic symmetry. It is a powerful tool also for describing **quasicrystals**, crystals with imperfections and incommensurate modulated crystal phases.

First described in: A. V. Shubnikov, *On works of Pierre Curie in the field of symmetry*, Usp. Fiz. Nauk. **59**, 591–602 (1956) – in Russian, A. V. Shubnikov, *Time reversal as an operation of antisymmetry*, Kristallografiya (USSR) **5**(2), 328–333 (1960).

silicide – a compound formed by a metal with silicon. Elements of the Periodic Table form more than 100 such compounds. Most of them have electronic properties typical of metals and demonstrate electrical resistivity in the range of 15–100 $\mu\Omega$cm ($TiSi_2$, $CoSi_2$, $TaSi_2$, tetragonal $MoSi_2$, tetragonal WSi_2, PtSi, Pd_2Si) depending on the purity and structure of the materials. There are about a dozen silicides with semiconductor behavior. Their room temperature energy gaps range from 0.07 eV (hexagonal $MoSi_2$ and WSi_2) and 0.12 eV ($ReSi_{1.75}$) to 1.8 eV ($OsSi_2$) and 2.3 eV (Os_2Si_3).

More details in: Properties of Metal Silicides, edited by K. Maex, M. van Rossum (INSPEC, IEE, London, 1995); *Semiconducting Silicides*, edited by V. E. Borisenko (Springer, Berlin, 2000).

Silsbee's effect – the ability of an electric current to destroy a superconducting state by means of the magnetic field that it generates without raising the temperature.

First described in: F. B. Silsbee, Bull. Natl. Bur. Std. **14**, 301 (1918).

SIM – an acronym for a **structured illumination microscopy**.

SIMS – an acronym for a **secondary ion mass spectrometry**.

Sinai process – a random walk on a one-dimensional lattice with fixed probabilities to move to the right and left at each lattice site. Although these probabilities are fixed, their values are chosen from a probability distribution such that there is a strong bias at each site for the walker to go in a preferred direction. The walker makes many jumps going between two sites: a leftmost site that when approached from the right sends the walker back toward the right with high probability, and similarly a rightmost site that sends the walker back to the left. There can be many such pairs of sites, especially in a nested configuration. In the process, the mean value of $r^2(t)$ was shown to be proportional to $\ln^4(t)$.

First described in: Ya. G. Sinai, *The limiting behavior of one dimensional random walk in a random medium*, Theory Prob. Appl. **27**(2), 256–268 (1982).

sine-Gordon equation – the nonlinear differential equation with **soliton** solutions:

$$\frac{\partial^2\psi}{\partial t^2} - a^2\frac{\partial^2\psi}{\partial x^2} + \omega_p^2 \sin\psi = 0,$$

where ω_p and a are parameters. If ψ is so small that the sine term can be replaced by the argument, the solution is a harmonic wave with the frequency wave vector relation given by $\omega^2 = \alpha\omega_p^2 + a^2q^2$.

In the linear approximation, a superposition of the waves can make up a wave packet localized in space. However, the components are dispersive so that after a time the width of the packet grows and the wave packet begins to unravel. The nonlinear term in the equation acts to counter this tendency. A suitably localized wave packet can maintain its shape forever or for as long as damping, which has not been included in the equation, does not come into play. Such a soliton solution is $\psi = 4\arctan\{\exp[x - x_0 - vt]/\xi\}$. The solution changes from 0 to 2π in the neighborhood of $x_0 + vt$ within a width of the order

$$\xi = \frac{a}{\omega_p}\sqrt{1 - \frac{v^2}{a^2}}.$$

It is a rounded step propagating with speed $v < a$, not otherwise dependent on the equation. Although the equation is nonlinear, a characteristic of the solitons is that two solitons can pass through each other with no changes in shape.

single-electron box – a single-electron device which consists of just one small island separated from a larger electrode, serving as an electron source, by a tunnel barrier. It is schematically shown in Figure S.10. The island is made of a conducting or semiconducting material. It has a size typical of a **quantum dot**. An external electric field is applied to the island using a gate separated from the island by a thicker insulator which does not allow noticeable tunneling. Increasing gate voltage attracts more and more electrons to the island. In an electric circuit the tunnel barrier is represented by the barrier capacitance C_t and tunneling resistance R_t. The capacitance C_g belongs to the gate.

By applying a positive bias to the gate electrode one can attract an electron to the island. When the increasing gate bias exceeds the **Coulomb blockade** limit the electron enters the island. Further increase in the gate voltage makes it possible to add one more electron to the island and so on. The discreteness of the electron transfer through the tunnel barrier necessarily makes such an increase step-like, thus producing a **Coulomb staircase** in terms of the charge accumulated in the island as a function of the voltage applied to the gate. The conditions for an experimental observation of the staircase characteristic suppose the charging energy to exceed the thermal energy $e^2/2C >> k_BT$, where $C = C_t + C_g$, and $R_t >> h/e^2$. At finite temperatures the steps and sawtooth dependence are eliminated.

The single-electron box is a basic building unit for other single-electron devices.

More details in: K. K. Likharev, *Single-electron devices and their applications,* Proc. IEEE **87**, 606–632 (1999).



Figure S.10 Single-electron box; its representation in electric circuits (top) and (bottom) the average number of electron charges $\langle n \rangle$ in the box as a function of the gate charge ($Q_g = C_g V_g$).

single-electron device – an electron device that can control the motion of even a single electron for information storage and processing. It typically consists of one or-few **quantum dot**s electronically interconnected and connected to other elements by tunnel junctions. Such devices retain their scalability even on an atomic scale.

More details in: K. K. Likharev, *Single-electron devices and their applications*, Proc. IEEE **87**, 606–632 (1999).

single-electron pump – a **single-electron device** which consists of a series of small gated islands separated by tunnel barriers and placed between electrodes serving as an electron source and drain. It is schematically shown in Figure S.11.

Its operation has much in common with a **single-electron trap**. Alternating voltage waveforms applied to each gate electrode are phase shifted, forming a potential wave gliding along the island array. This wave picks up an electron from the source and carries it down to the drain – a process very similar to the action of charge-coupled devices. Notice that this device does not need a DC source drain voltage: the direction of the transferred electron is determined by that of the running wave of electric potential. The pump transfers exactly one electron from the source to the drain during one cycle of the alternating gate biases. Of all single-electron devices, it dissipates the lowest energy and has the highest transfer accuracy.

First described in: H. Pothier, P. Lafarge, P. F. Orfila, C. Urbina, D. Esteve, M. H. Devoret, *Single-electron pump fabricated with ultrasmall normal tunnel junctions*, **169**(1–4), 573–574 (1991).

More details in: K. K. Likharev, *Single-electron devices and their applications*, Proc. IEEE **87**, 606–632 (1999).



Figure S.11 Single-electron pump and its representation in electric circuits.

single-electron transistor – a **single-electron device** which consists of a small conducting island with a pair of tunnel junctions separating it from the electrodes serving as an electron source and drain. It is charge operated by the third electrode acting as a gate. The transistor is schematically shown in Figure S.12 with its direct current characteristics.

Note that the characteristics shown are typical for a symmetric structure supposing identity of the source and drain tunnel junctions. The conditions to maintain n uncompensated electrons in the island are:

$$\frac{1}{C_d}\left(ne - \frac{e}{2} - C_g V_g\right) \langle V_{sd} \langle \frac{1}{C_d}\left(ne + \frac{e}{2} - C_g V_g\right)$$

$$\frac{1}{C_s + C_g}\left(-ne + \frac{e}{2} + C_g V_g\right) \rangle V_{sd} \rangle \frac{1}{C_s + C_g}\left(-ne - \frac{e}{2} + C_g V_g\right),$$

where $V_{sd} = V_d - V_s$.

The grey areas shown in the $V_{sd} - V_g$ relationship corresponds to an effective **Coulomb blockade**. The number of electrons in the island takes a fixed value



Figure S.12 Single-electron transistor, its representation in electric circuits and static electric characteristics.

indicated in the dark areas. In the neighboring light areas the island can take two electron numbers, namely one of those indicated. In this case the bigger number corresponds to preferred tunneling through the source junction, while the smaller one supposes electron tunneling through the drain junction.

Initially there are no uncompensated electrons in the island. When a finite positive source-to-drain voltage V_{sd} (indicated by the dashed line) is applied and the gate voltage is $e/2C_g + ne/C_g$, electron transport through the island occurs. For the source tunneling junction, an increase in the electron number in the island is preferable, so that an electron tunnels from the source to the island. However, for the drain tunneling junction, a decrease in the electron number in the island is preferable, thus providing an electron to tunnel from the island to the drain. As a result, an electron passes from the source to the drain, and source-to-drain current is observable at these bias conditions. The oscillating $I_{sd} - V_g$ characteristics are often called **Coulomb oscillations**.

The current–voltage (I_{sd} versus V_{sd}) characteristics are dependent on both gate voltage and temperature. When $0 < V_g < e/2C_g$ there is no current at a small source–drain voltage. This suppression of the current is controlled by the **Coulomb blockade**. At a certain threshold voltage the Coulomb blockade is overcome, and at much higher voltages the current exhibits quasi-periodic increase similar to the

Coulomb staircase in the **single-electron box**. The threshold voltage, as well as the source–drain current in its vicinity, is a periodic function of the gate voltage.

Appropriate temperature conditions for a distinct operation of the transistor needs $e^2/2C >> k_B T$, where $C = C_g + C_s + C_d$.

First described in: D. V. Averin, K. K. Likharev, *Coulomb blockade of tunneling and coherent oscillations in small tunnel junctions*, J. Low. Temp. Phys. **62**(2), 345–372 (1986) – theory; T. A. Fulton, G. J. Dolan, *Observation of single-electron charging effects in small tunneling junctions*, Phys. Rev. Lett. **59**(1), 109–112 (1987) – experimental demonstration.

More details in: K. Uchida, *Single electron devices for logic applications*, in: *Nanoelectronics and Information Technology*, edited by R. Waser (Wiley-VCH, Weinheim, 2003).

single-electron trap – a **single-electron device** which consists of several islands between the source and **single-electron box** as schematically shown in Figure S.13

The main new feature of this system is its internal memory (bi- or multistability). Certain ranges of applied gate voltage cause the system to be in one of two (or more) charged states of its edge island. This is due to electric polarization effects: an electron located in one of the islands of the array extends its field to a certain distance outside.

By applying sufficiently high voltage $V^{\uparrow}$ to the gate one can force an electron to drive into the edge island. If the array is not too long, other electrons feel its repulsion and do not follow. When the gate voltage is subsequently decreased to the initial level, the electron is trapped in the edge island behind the energy barrier. In order to remove the electron from the trap, the voltage has to be reduced further, to $V^{\downarrow} < V^{\uparrow}$. As a result, the dependence of the number of electrons in the trap on the the gate voltage exhibits regions of bi- or multi-stability, in which the charge state of the trap depends on its prehistory.

The lifetime of a certain state within the multi-stability region is fundamentally limited by the thermal activation over the energy barrier (E_c) and **co-tunneling**. The first effect is exponentially low in $E_c/k_B T$, while the second effect falls exponentially with the number of the islands in the array. As a result, electron retention time may be very long.



Figure S.13 Single-electron trap and its representation in electric circuits.

First described in: T. A. Fulton, P. L. Gammel, L. N. Dunkleberger, *Determination of Coulomb-blockade resistances and observation of the tunneling of single electrons in small-tunnel-junction circuit*, Phys. Rev. Lett. **67**(22), 3148–3151 (1991).

More details in: K. K. Likharev, *Single-electron devices and their applications*, Proc. IEEE **87**, 606–632 (1999).

single-electron tunneling – electron-by-electron tunneling governed by the **Coulomb blockade** effect. It is illustrated in Figure S.14 for the system composed of two conducting electrodes separated by a tunnel junction formed by a very thin **dielectric**. Electronic processes in the structure are, in parallel, represented by the mechanical model showing formation of water droplets at a faucet on a pipe. Initially the charge at both surfaces of the dielectric is zero. When external constant bias is applied to the structure, the electric charge starts to accumulate at the surface of the dielectric. It is transferred by both continuous and discrete processes.

Electric current in solids is known to be a result of the motion of electrons through the lattice of atomic nuclei. While each electron carries the lowest fixed amount of the negative charge, denoted as $-e$, the smallest transferred charge can be lower than this value. This is due to the fact that the transferred charge is proportional to the sum of shifts of all electrons with respect to the lattice nuclei. As the shifts can be extremely small, their sum changes continuously. Thus, it can have practically any value, even a fraction of the charge of single electron.

The transferred charge flowing continuously through the conductor is accumulated on the surface of the electrode against the dielectric layer of the junction. The adjacent electrode will have equal but opposite surface charge. One can imagine this surface charge Q as a slight continuous shift of the electrons near the surface from their equilibrium positions. The charge collects in the junction just as water forms a droplet at the faucet. On the other hand, only tunneling can change this charge in a discrete way: when an electron tunnels through the dielectric barrier, the surface charge will be changed exactly by either $+e$ or $-e$, depending on the direction of tunneling.

A tunneling event becomes energetically favorable only when Q just exceeds $e/2$. At this condition the tunneling electron will change the charge abruptly from $+e/2$ to $-e/2$ and the energy of the junction remains the same. If Q is less than $+e/2$ or greater than $-e/2$, tunneling in any direction would increase the energy of the system. Thus, if the accumulated charge is within the range from $-e/2$ to $+e/2$, tunneling is forbidden by the Coulomb blockade.

When the charge reaches $e/2$, tunneling becomes possible. One electron crosses the junction, just like a water droplet falls as soon as it reaches a critical size. The accumulated charge drops to zero and the system appears at the Coulomb blockade range again. The repetition of the charge/discharge processes produces single-electron tunneling oscillations with a frequency equal to the current I divided by the charge of one electron, e.

First described in: I. O. Kulik, R. I. Shekhter, *Kinetic phenomena and charge discreteness effects in granulated media*, Zh. Eksp. Teor. Fiz. **68**(2), 623–640 (1975) – in Russian, Sov. Phys. JETP **41**(2), 308–314 (1975) – in English, theoretical prediction;


Conductor
Dielectric
Conductor
Tunneling
Electron

Figure S.14 Single-electron tunneling and its mechanical analogy with water falling from a pipe (from K. K. Likharev, T. Claeson, *Single electronics*, Scientific American (**6**), 50–55 (1992)).

E. Ben-Jacob, Y. Gefen, *New quantum oscillations in current driven small junctions,* Phys. Lett. **108**A(5/6), 289–292 (1985); K. K. Likharev, A. B. Zorin, *Theory of Bloch wave oscillations in small Josephson junctions,* J. Low Temp. Phys. **59**(3/4), 347–382 (1985); D. V. Averin, K. K. Likharev, *Coulomb blockade of tunneling and coherent oscillations in small tunnel junctions,* J. Low Temp. Phys. **62**(2), 345–372 (1986) – theory; T. A. Fulton, G. J. Dolan, *Observation of single-electron charging effects in small tunneling junctions,* Phys. Rev. Lett. **59**(1), 109–112 (1987) – experiment.

single-electron turnstile – a **single-electron device** which consists of an odd number of small islands separated by tunnel barriers and placed between electrodes serving as an electron source and drain. It is schematically shown in Figure S.15.

At $V = 0$, the device operates exactly like a **single-electron trap**: one electron is pulled into the central island (at random, from either source or drain) increasing the gate voltage U beyond a certain threshold. Then it may be pushed out by decreasing U. The application of a modest drain–source bias $V \neq 0$ breaks the source–drain symmetry. In this case an electron is always picked up from the source when the gate voltage goes up and delivered to the drain when it goes back down. If the gate voltage is cycled periodically, one electron is transferred from the source to the drain in each period.

First described in: L. J. Geerligs, V. G. Anderegg, P. A. M. Holweg, J. E. Mooij, H. Pothier, D. Esteve, C. Urbina, M. H. Devoret, *Frequency-locked turnstile device for single electrons,* Phys. Rev. Lett. **64**(22), 2691–2694 (1990).

More details in: K. K. Likharev, *Single-electron devices and their applications,* Proc. IEEE **87**, 606–632 (1999).



Figure S.15 Single-electron turnstile and its representation in electric circuits.

single material limit = **Shockley–Quesser limit**.

single molecule magnet → **molecular nanomagnet**.

singlet – a state of two electrons with paired (antiparallel) spins. It has zero net spin.

singularity or singular point of a function of one or more variables is a point about which it cannot be expanded in a **Taylor series**; in particular, one at which the function or any of its partial derivatives become infinite. For example, $x = a$ is a singular point of both the functions $(x - a)^{1/2}$ and $\log(x - a)$.

skin effect – a tendency for an alternating electric current in a conductor to concentrate in the outer part, or "skin", rather than be distributed uniformly over the body of the conductor. The effect arises from the increase of internal self-inductance of the conductor with the depth below the surface of the conductor. In consequence, the magnitude of the effect increases with the frequency of the current, the diameter of the conductor and the magnetic permeability of the conductor material. Defining the penetration depth d as the distance measured from the surface of the conductor at which the current has fallen to $1/l$ of its surface value, it can be given by $d = (\pi\mu\mu_0\nu\sigma)^{-1/2}$, where μ is the relative permeability of the material, ν is the frequency of the alternating current, and σ is the conductivity of the material.

skyrmion – a **quasiparticle** corresponding to topological twists or kinks in a **spin** space. It can also be interpreted as a **soliton** with spin and statistics different from those of the underlying fields in a nonlinear field theory. Skyrmions are a characteristic of nonlinear continuum models ranging from microscopic to cosmological scales.

First described in: T. H. Skyrme, *A non-linear field theory*, Proc. R. Soc., Ser. A **260**, 127–138 (1961).

Slater determinant – a quantum mechanical wave function for N electrons, or in general for N fermions, which is an $N \times N$ determinant whose entries are N different one particle wave functions $\psi_N(r_N)$ depending on the coordinates of each of the particles in the system:

$$\Psi = \frac{1}{(N!)^{1/2}} \begin{vmatrix} \psi_1(r_1) & \psi_2(r_1) & \dots & \psi_N(r_1) \\ \psi_1(r_2) & \psi_2(r_2) & \dots & \psi_N(r_2) \\ \dots & \dots & \dots & \dots \\ \psi_1(r_N) & \psi_2(r_N) & \dots & \psi_N(r_N) \end{vmatrix} .$$

First described in: J. C. Slater, *The theory of complex spectra*, Phys. Rev. **34**(10), 1293–1322 (1929).

Slater–Jastrow wave function – a product of **Slater determinant**s and the Jastrow correlation factor:

$$\psi_T(\{\mathbf{r}_i\}) = \det(A_{\mathrm{up}})\det(A_{down}) \exp\left(\sum_{i<j} U_{ij}\right) .$$

Here, the A_{up} and A_{down} are defined as the Slater matrices of the single particle up and down orbitals, respectively. That is

$$A = \begin{vmatrix} \phi_1(\mathbf{r}_1) & \phi_1(\mathbf{r}_2) & \phi_1(\mathbf{r}_3) & \cdots \\ \phi_2(\mathbf{r}_1) & \phi_2(\mathbf{r}_2) & \phi_2(\mathbf{r}_3) & \cdots \\ \phi_3(\mathbf{r}_1) & \phi_3(\mathbf{r}_2) & \phi_3(\mathbf{r}_3) & \cdots \\ \vdots & \vdots & \vdots & \ddots \end{vmatrix},$$

where ϕ_k are molecular orbitals centered at $\mathbf{c}_k$:

$$\phi_k(\mathbf{r}) = \exp\left(\frac{-(\mathbf{r}-\mathbf{c}_k)^2}{\omega_k^2 + \nu_k|\mathbf{r}-\mathbf{c}_k|}\right).$$

The **Jastrow correlation factor** U_{ij} terms are defined as

$$U_{ij} = \frac{a_{ij}r_{ij}}{1 + b_{ij}r_{ij}},$$

where $r_{ij} \equiv |r_i - r_j|$ and

$$a_{ij} = \begin{cases} e^2/8D & \text{if } ij \text{ are like spins} \\ e^2/4D & \text{if } ij \text{ are unlike spins} \\ e^2/2D & \text{if } ij \text{ are electron-nuclear pairs} \end{cases}$$

The Slater–Jastrow wave has a number of desirable properties for many-body quantum Monte Carlo calculations of electrons in the presence of ions.

First described in: J. C. Slater, *The self consistent field and the structure of atoms,* Phys. Rev. **32**(3), 339–348 (1928); R. Jastrow, *Many-body problem with strong forces,* Phys. Rev. **98**(5), 1479–1484 (1955).

Slater orbital – an approximate solution to the eigenvalue equation: $N\mathbf{r}^{n-1}\mathbf{e}^{\zeta\mathbf{r}}Y_l^m(\theta\phi)$, where N is the normalization constant, n is the principal quantum number of the orbital, $\zeta = (Z-s)/n$ is the orbital exponent, $Y_l^m(\theta\phi)$ is the angular part of the orbital, Z is the atomic number and s is a screening constant.

First described in: J. C. Slater, *Atomic shielding constants,* Phys. Rev. **36**(1), 57–64 (1930).

small angle X-ray scattering (SAXS) – **X-ray diffraction** technique with scattering angles less than 1°. The diffraction information about structures with large periods lies in the region. Therefore the technique is commonly used for probing large length scale structures, such as high-molecular-weight polymers, biological macromolecules (proteins, nucleic acids, and so on) and self-assembled superstructures (such as surfactant-templated mesoporous materials). The measurements are technically challenging because of the small angular separation of the direct beam and the scattered beam. Large specimen-to-detector distances (0.5–10 m) and high quality collimating optics are used to achieve a good signal-to-noise ratio.

***S*-matrix** = **scattering matrix**. It expresses what comes out of a system as a function what goes into it in a matrix form:

$$\begin{pmatrix} C \\ D \\ \dots \end{pmatrix} = \mathbf{S} \begin{pmatrix} A \\ B \\ \dots \end{pmatrix},$$

where $A, B, \dots$ represent the incoming influence on the system and $C, D, \dots$ represent the system reaction.

First described in: J. A. Wheeler, *On the mathematical description of light nuclei by the method of resonating group structure,* Phys. Rev. **52**(11), 1107–1122 (1937).

More details in: D. Iagolnitzer, *The S Matrix* (North Holland, Amsterdam, 1978).

Smith–Helmholtz law states that for a single refracting surface of sufficiently small aperture the product of the index of refraction, distance from the optical axis and the angle which a light ray makes with the optical axis at the object point is equal to the corresponding product at the image point. This formula is also associated with the names of Lagrange and Clausius. In a more restricted form it was also known to Huygens.

More details in: J. W. S. Rayleigh, *Notes, chiefly historical, on some fundamental propositions in optics,* Phil. Mag. **21**(5), 466 (1886); T. Smith, *The general form of the Smith-Helmholtz equation,* Trans. Opt. Soc. **31** 241–248 (1930); M. Born, E. Wolf, *Principles of Optics, Seventh Edition* (Cambridge University Press, Cambridge 1999).

Snell's law gives the relationship between the angle of incidence and the angle of refraction for a wave impinging on an interface between two media with different refractive indexes (Figure S.16): $n_1 \sin\theta_1 = n_2 \sin\theta_2$.

First described by: W. Snell in 1621 and published in: R. Descartes, *Dioptrique* (Leyden 1637).



Figure S.16 Refraction of light.

SNOM – an acronym for a **s**canning **n**ear-**f**ield **o**ptical **m**icroscopy. For more details → **near-field scanning optical microscopy**.

soft nanotechnology – the nanotechnology focused on soft materials.

Sohncke law states that the stress per unit area normal to a crystallographic plane needed to produce a fracture in a crystal is a constant characteristic of a crystalline substance.

First described in: L. Sohncke, *Entwicklung einer Theorie der Krystallstruktur* (Leipzig, 1879).

sol → **sol-gel technology**.

solar cell – a semiconductor device converting light energy into electrical energy. The **photovoltaic effect** is used for this. The first solar cell was fabricated by Fritts in 1883 using Se as the absorbing layer with a rectifying metal contact.

Usually three generations of solar cells are distinguished. The first generation consists of a large-area, single-crystal, single-layer $p-n$ junction **diode**, capable of generating electrical energy from light sources with the wavelengths of sunlight. The first semiconductor $p-n$ junction solar cells were described in 1941 by Ohl. Most photovoltaic solar cells produced to date have been based on silicon $p-n$ junctions, although now relying on junctions formed more controllably by diffusing one polarity dopant into a wafer substrate of opposite polarity. To reduce reflection losses crystallographic texturing on the top surface has been widely used. Silicon solar cells, made from single-crystalline and multi-crystalline silicon, contribute ~94% of the world market. The maximum efficiency one can reach with the conventional solar cell structure is given by the so-called **single material** or **Schockley-Queisser limit**. The second generation of solar cell relies on the use of thin epitaxial deposits of semiconductors on lattice-matched wafers. An example is the use of **heterojunction**s formed from different $A^{III}B^{V}$ compounds or their alloys to produce the rectifying junction in **heterojunction solar cell**s. In particular **multijunction solar cell**s are the most sophisticated solar cells to date. The dominance of the photovoltaic field by inorganic solid-state junction devices is now being challenged by the emergence of a third generation of cells, based, for example, on **polymer solar cell**s, **nanoparticle-based solar cell**s, and **dye-sensitized solar cell**s.

The main parameters characterizing a solar cell are open circuit voltage, short circuit current, energy conversion efficiency, fill factor, and quantum efficiency. All of them are referred to measurements under standard test conditions (STC). The most often used STC specifies a temperature of 25°C and an irradiance of 1000 W m^{-2} with an air mass 1.5 (AM1.5) spectrum. These correspond to the irradiance and spectrum of sunlight incident on a clear day upon a sun-facing 37°-tilted surface with the sun at an angle of 41.81° above the horizon.

First described in: C. E. Fritts, *New form of selenium cell, with some remarkable electrical discoveries made by its use,* Proc. Am. Assoc. Adv. Sci. **33**, 97 (1883); C. E. Fritts, *A new form of selenium cell,* Am. J. Sci. **26**, 465 (1883), R. S. Ohl, *Light-sensitive electric device,* US Patent No. 2 402 622, 27th May 1941; R. S. Ohl, *Light-sensitive device including silicon,* US Patent No. 2 443 542, 27th May, 1941.

More details in: M. A. Green, *Photovoltaic principles,* Physica E **14**, 11–17(2002); C. S. Solanki, G. Beaucarne, *Advanced solar cell concepts,* Energy for Sustainable Development–The Journal of the International Energy Initiative **11**, 17–23 (2007); P. Würfel, *Physics of Solar Cells: From Principles to New Concepts* (Wiley-VCH, Weinheim, 2005); T. Markvart, L. Castaner, *Solar Cells: Materials, Manufacture and Operation* (Elsevier, Amsterdam, 2005).

sol–gel technology – a method of material synthesis based on the sol–gel transition. A **sol** is a solution of colloidal particles, which are solid particles with a size of 1–100 nm, in a liquid. A **gel** represents a network of closely connected polymer chains derived from the colloidal particles of sol. Porous glasses and glasses with embedded nanocrystals of semiconductors can be formed in this way in the form of thin films and bulk samples.

An example is the sol–gel transition in water solutions of silicon-organic compounds with a composition $Si(OR)_4$, where R is one of the alkyl groups (CH_3, C_2H_5, C_3H_7, . . .). Substitution of the alkyls by OH-groups is the first step of the sol–gel transformation



$$\mathrm{RO{-}\overset{OR}{\underset{OR}{Si}}{-}OR + 4H_2O \rightarrow HO{-}\overset{OH}{\underset{OH}{Si}}{-}OH + 4ROH}$$

The produced molecules of silicon hydroxide ($Si(OH)_4$) then form chains and a threedimensional network by means of Si–O–Si bonds



$$\mathrm{HO{-}\overset{OH}{\underset{OH}{Si}}{-}OH + HO{-}\overset{OH}{\underset{OH}{Si}}{-}OH \rightarrow HO{-}\overset{OH}{\underset{OH}{Si}}{-}O{-}\overset{OH}{\underset{OH}{Si}}{-}OH + H_2O}$$

These transformations occur at relatively low temperatures – below 400°C. Porous glasses developed in this way contain nanometer-size voids. They can be easily impregnated with **dye** molecules or atomic clusters. Nanocrystals can be directly derived therefrom. As compared to conventional glasses, porous glasses can be saturated with semiconductor materials up to concentrations reaching 10%, which are high enough for the study and use of electron interactions between nanocrystals. Additionally, crystallites in these matrixes are expected to have a smaller amount of defects because of the lower precipitation temperature. $A^{II}B^{VI}$ and $A^{III}B^{V}$ semiconductor nanocrystals can be successfully produced by this technique. Their size distribution is rather wide.

More details in: J. D. Wright, N. A. J. M. Sommerdijk, *Sol-Gel Materials: Chemistry and Applications* (Taylor & Francis, New York, 2001).

solid phase epitaxy – solid state structural rearrangements in a thin amorphous or polycrystalline layer on a monocrystalline substrate resulting in the layer structure becoming epitaxial to the substrate. The epitaxial rearrangements starts at the interface and proceeds through the layer with a rate proportional to $\exp(-E_a/k_B T)$, where E_a is the activation energy of the solid-phase epitaxial growth. It is widely used to restore the crystalline structure in ion-implanted layers of semiconductors and to fabricate epitaxial **silicides** on monocrystalline silicon formed during their solid-phase synthesis.

solitary wave – a localized disturbance in a continuous medium that can propagate over a long distance without any change to its shape or amplitude.

soliton – a hump developed by waves in a shallow channel. It propagates as a coherent entity, continuing its course along the channel apparently without change of form. Solitons on canals can have various widths, but the smaller the width the larger the height must be and the faster the soliton travels. Thus, if a high, narrow soliton is formed behind a low, broad one, it will catch up with the low one. It turns out that, when the high soliton does so, it passes through the low one and emerges with its shape unchanged.

From the mathematical point of view, a soliton is a localized nonlinear wave that regains asymptotically (as $t \to \infty$) its original (as $t \to -\infty$) shape and velocity after interacting with any other localized disturbance. The only long-term effect on the soliton from the interaction is a phase shift. In other words, a soliton is a spatially localized object, that is a solitary wave, which is dynamically and structurally stable. Soliton waves can be obtained as solutions of the **sine-Gordon equation**.

First described by S. Russell in 1834.

More details in: S. E. Trullinger, V. E. Zakharov, V. L. Pokrovsky, *Solitons* (North Holland, Amsterdam, 1986).

Sommerfeld fine-structure constant – the nondimensional coefficient $\alpha = 2\pi e^2/(hc) = 7.297 \times 10^{-3}$. With the help of this constant, the grouping of closely spaced emission lines in the spectrum of one electron atoms can be related to the **precession** of elliptic electron orbitals.

First described in: A. Sommerfeld, *Zur Quantentheorie der Spektrallinie*, Ann. Phys. **51**, 1–94 (1916).

Sommerfeld's factor → **Bir–Aronov–Pikus mechanism**.

Sommerfeld wave – a surface wave guided by the plane interface between a dielectric and a good conductor, the energy decaying exponentially normal to the surface of the dielectric. The velocity of propagation depends on the dielectric constant of the medium in which the wave flows.

First described in: A. Sommerfeld, *Über die Fortpflanzung elektrodynamischer Wellen längs eines Drahtes*, Ann. Phys. **67**, 233–290 (1899).

sonoluminescence – light emission from a substance excited by high frequency sound waves or phonons.

First described in: W. T. Richards, A. L. Loomis, *The chemical effects of high frequency sound waves I. A preliminary survey*, J. Am. Chem. Soc. **49**(12), 3086–3100 (1927); F. O. Schmitt, C. H. Johnson, A. R. Olson, *Oxidations promoted by ultrasonic radiation*, J. Am. Chem. Soc. **51**(2) 370–375 (1929); H. Frenzel, H. Schultes, *Luminescenz im ultraschallbeschickten Wasser*, Z. Phys. Chem. Abt. B **27**, 421–424 (1934).

s orbital → **atomic orbital**.

space charge polarization → **polarization of matter**.

space group – a full symmetry group of a crystalline solid containing operations of a point group and lattice translation. In fact, space groups consist of rotations, reflections, screw rotations, glide reflections and translations, which transform the crystal as a whole into itself. There are 230 such groups. These are each described in the **Hermann–Mauguin notation**, which shows essential symmetry elements, for example $P6_3/mmc$. A space group symbol consists of two parts: a letter depicting the lattice type and some essential symmetry elements.

spectral hole-burning – the optical phenomenon observed in **quantum dot** ensembles, in particular for nanocrystals (dots) of semiconductors embedded in dielectric matrices. It is photo-induced modification of an emission spectrum just under irradiation, which is registered like a hole in the spectrum.

The phenomenon can have a transient, persistent or even irreversible character. In terms of the relaxation time of the burnt spectral hole the following groups are distinguished.

1. **Transient spectral hole-burning** due to selective population of the higher electron–hole states within the same crystallite with consequent relaxation to the lower levels. The typical relaxation times are in the subnanosecond range. In order to observe this effect the following condition should be satisfied $\tau_{imp} < \tau_{rel}$, where τ_{imp} is duration of the pump and probe pulses and τ_{rel} is the energy relaxation time of excitons from the upper to the lower states. In the specific case of large energy level separation when the “phonon bottleneck” effect is pronounced, a condition $\tau_{rec} < \tau_{rel}$, where τ_{rec} is the recombination lifetime, makes it possible to observe hole-burning of this type in a quasi-steady-state regime, that is independently of the pump pulse duration. The relevant effect in molecular spectroscopy is often considered in terms of the “hot luminescence”. In bulk semiconductors a similar phenomenon is possible on the femtosecond time scale when **Fermi–Dirac distribution** of electron–hole gas is not achieved. This effect is readily observable in nanocrystals of $A^{II}B^{VI}$ compounds in glass and in porous silicon.
2. **Quasi-steady-state hole-burning** due to absorption saturation of resonantly excited crystallites in an inhomogeneously broadened ensemble. The recovery process is controlled by electron–hole recombination with a characteristic time in the subnanosecond to microsecond range. This effect has been reported by a number of groups for $A^{II}B^{VI}$ and $A^{I}B^{VII}$ quantum dots in dielectric matrices. If the relaxation time is comparable to or longer than the recombination time, then a selective steady-state population of the higher states is possible similarly to case 1. Spectral hole-burning due to creation

of the first electron-hole pair in a crystallite is accompanied by an induced absorption due to the formation of a biexciton state when the pump and the probe quanta are absorbed by the same crystallite. In the case of larger dots exciton–exciton interactions results in more complicated deformation of the absorption spectrum.

3. **Persistent reversible hole-burning** due to photoionization of a crystallite and/or surface localization of the electron occurs under certain conditions. In this case optical absorption experiences modifications due to the local electric field effect (**quantum-confined Stark effect**) with a differential absorption spectrum typical of exciton absorption in the external electric field. In the case of small quantum dots, surface localization of one of the carriers leads to a problem of a biexciton and the differential absorption spectrum may be similar to case 2. The effect has a recovery time from microseconds to hours depending on the temperature and/or dot-matrix interface.
4. **Permanent spectral hole-burning** is possible due to an irreversible sequence of photochemical reactions in resonantly excited crystallites stimulated by a manifold photoionization. The phenomenon was observed in semiconductor-doped polymer and may be interpreted in terms of size-selective photolysis of nanocrystallites. At the early stage, photoionization results in the local electric field effect with a differential absorption spectrum similar to case 3.

Unlike case 1, cases 2–4 are possible only under conditions of inhomogeneous broadening. Therefore they have no analog among the intrinsic bulk semiconductors. The analogs can be found, however, in a number of systems possessing inhomogeneous broadening, such as doped semiconductors, atoms in gases, ions in dielectrics and molecules in a gas phase, in solution and in solid matrices.

In terms of the underlying microscopic mechanisms, spectral hole-burning in nanocrystals can be a result of population-induced effects (selective absorption saturation), local electric field induced effects (selective photoionization), or photochemical effects (selective photolysis). Some mechanisms of spectral hole-burning may coexist. Observation of the specific hole-burning effect does not eliminate a manifestation of the other possible hole-burning phenomena.

More details in: S. V. Gaponenko, *Optical Properties of Semiconductor Nanocrystals* (Cambridge University Press, Cambridge, 1998).

SPEM – an acronym for **saturated pattern excitation microscopy**.

spherical coordinates – a system of curvilinear coordinates in which the position of a point in space is designated by its distance *r* from the origin or pole, called the radius vector, the angle ϕ between the radius vector and a vertically directed polar axis, called the cone angle or colatitude, and the angle θ between the plane of ϕ and fixed meridian plane through the polar axis, called the polar angle or longitude.

spin – an intrinsic angular momentum of an elementary particle or nucleus. It exists even when the particle is at rest, as distinguished from orbital angular momentum.

First described in: A. H. Compton, *Magnetic electron*, J. Frankl. Inst. **192**, 145–155 (1921) – idea of a quantized spinning of the electron; G. Uhlenbeck, S. A. Goudsmit, *Ersetzung der Hypothese vom unmechanischen Zwang durch eine Forderung bezüglich des inneren Verhaltens jedes einzelnen Elektrons*, Naturwiss. **13**, 953–954 (1925) and G. Uhlenbeck, S. A. Goudsmit, *Spinning electrons and the structure of spectra*, Nature **117**, 264–265 (1926) – spin concept.

spin–Coulomb drag – a change in the electron transport due to Coulomb interaction between spin-up and spin-down electrons. This interaction can transfer momentum between spin-up and spin-down electrons thereby effectively introducing friction for the relative motion of the two spin components. If, for example, one of the two spin components is set in motion relative to the other, it will tend to drag the latter in the same direction. Or, if a finite spin current is set up through the application of an external field, then the Coulomb interaction will tend to equalize the net momenta of the two spin components. The most dramatic manifestation of the phenomenon is the appearance of a finite trans-resistivity defined as the ratio of the gradient of the spin-down electrochemical potential to the spin-up current density when the spin-down current is zero.

First described in: I. D'Amico, G. Vignale, *Theory of spin Coulomb drag in spin-polarized transport*, Phys. Rev. B **62**(8), 4853–4857 (2000).

spin drag = **spin–Coulomb drag**.

spinel – the mineral $MgAl_2O_4$.

spin glass – a magnetic alloy in which the concentration of magnetic atoms is such that below a certain temperature their magnetic moments are no longer able to fluctuate thermally in time but are still directed at random, in loose analogy to the atoms of ordinary glass. If such an alloy is cooled in an external magnetic field from above to below this transition temperature and the external field is then removed, the magnetization decays slowly to zero, typically in a matter of hours.

spin Hall effect – a deflection in opposite directions of electrons with different **spin**s perpendicular to the main current flow when they are scattered at impurities, defects or other imperfections in solids as illustrated in Figure S.17.

This spin current results in an accumulation of spin-up and spin-down electrons at different ages of the conducting channel, as takes place in the classical **Hall effect**, but without the influence of an external magnetic field. **Spin–orbit coupling** is considered to be the driving mechanism of the phenomenon. The process requiring electrons to scatter at impurities is referred to as the *extrinsic* spin Hall effect. In contrast, in the *intrinsic* spin Hall effect the effective magnetic field due to the spin–orbit interaction produces a torque on the electron spins that can also



Figure S.17 Origin of a perpendicular spin current when spin-up and spin-down electrons are scattered at a defect in a conductor.

induce a spin current. The important distinction between these two effects is that the intrinsic one arises as a result of the crystal structure of the material, even in the absence of impurities, while the extrinsic Hall effect only occurs in the impurity scattering.

First described in: M. I. D'yakonov, V. I. Perel', *Possibility of orienting electron spins with current,* JETP Lett. **13**, 467–469 (1971) – theoretical prediction; J. E. Hirsch, *Spin Hall effect,* Phys. Rev. Lett. **83**(9), 1834–1837 (1999) – the term "Spin Hall effect" was introduced; Y. K. Kato, R. C. Myers, A. C. Gossard, D. D. Awschalom, *Observation of the Spin Hall effect in semiconductors,* Science **306**, 1910–1913 (2004) – first experimental observation.

More details in: V. Sih, Y. Kato, D. Awschalom, *A Hall of spin,* Physics World **18**(11), 33–36 (2005).

spin–lattice relaxation – a magnetic relaxation in which the excess potential energy associated with electron spin in a magnetic field is transferred to the lattice.

spinor – a vector with two complex components which undergoes a **unitary** unimodular transformation when the three-dimensional coordinate system is rotated. It can represent the spin state of a particle of spin 1/2. More generally, a spinor of order (or rank) n is an object with 2^n components, which transform as products of components of n spinors of rank one.

spin–orbit coupling (interaction) arises in an atom as a result of the interaction of the electron spin magnetic moment with the magnetic moment related to the orbital motion of the electron. It is accompanied by a shift in energy levels (due to the potential energy of the spin magnetic moment of the electron in the magnetic field) that it feels as it moves through the electric field of the nucleus. In solids, the spin–orbit interaction consists of two distinct contributions: the **Dresselhaus coupling**, which is due to bulk inversion asymmetry of the lattice, and the **Rashba coupling**, which is due to structure inversion asymmetry along a particular crystallographic direction. Both of these terms result in the splitting of electron energy levels and in the mixing of the electron spin states.

spin polarization in a particular material is defined in terms of the number of carriers with spin-up ($n_\uparrow$) and spin-down ($n_\downarrow$) as

$$P = \frac{n_\uparrow - n_\downarrow}{n_\uparrow + n_\downarrow}.$$

The most pronounced spin effects are reasonably expected for the materials with the highest fractions of spin-polarized electrons. These are materials that have only one occupied spin band at the Fermi level. In practice, partially polarized materials are mainly used in device applications. Such materials, which are metals and their alloys, oxides, magnetic semiconductors, and related bulk electron spin polarizations, are listed in Table S.1.

Note that spin polarization is sensitive to sample fabrication conditions and impurities in the material; therefore the highest polarizations experimentally observed are summarized in Table S.1 .

An electron current in solid-state structures composed of differently spin-polarized materials is indeed dependent on the particular spin orientations in the regions through which electrons pass. Electrons originating from one spin state at the Fermi level of the injection electrode would be accommodated only by unfilled states of the same spin at the Fermi level of the accepting material. An electron spin polarized in the injection electrode undergoes many collisions, which modify its momentum until eventually its spin flips. For practical applications we need to know how long electrons remember their spin orientation, characterized by **spin relaxation length**.

Table S.1 Maximum conduction electron spin polarization observed in different materials.

Material	Co	Fe	Ni	$Ni_{80}Fe_{20}$*	CoFe	NiMnSb	$La_{0.7}Sr_{0.3}MnO_3$	CrO_2
Polarization, %	42	46	46	45	47	58	78	90

* The alloy $Ni_{80}Fe_{20}$ is called permalloy (Py).

Material	$Zn_{0.9}Be_{0.07}Mn_{0.03}Se$	$Zn_{0.94}Mn_{0.06}Se$
Polarization, %	90 (at ~5 K, 1.5 T)	70 (at 4.2 K, 4–5 T)

spin-polarized low energy electron microscopy (SPLEEM) – an imaging technique based on the use of an **electron microscope** and on the fact that the reflectivity of a magnetic surface for a spin-polarized low-energy electron beam depends on the relative orientation of the magnetization and the **spin polarization** of the incoming electron beam. Is is linked to the investigation of **ferromagnetic** structures and cannot provide magnetic contrast images from **antiferromagnetic** samples. Because of the very short penetration depth in materials of low-energy electrons, the technique is sensitive to the surface properties, but lacks chemical selectivity since the spin-resolved low-energy electron reflectivity of a solid surface is determined by the empty electron states just above the **Fermi level** in the **conduction band**. The spin polarization of the electron beam can be oriented in all spatial directions. A quantitative determination of unknown magnetic domain microstructures, magnetic configurations and structure–property relationships is possible.

First described in: E. Bauer, T. Duden, R. Zdyb, *Spin-polarized low energy electron microscopy of ferromagnetic thin films,* J. Phys. D: Appl. Phys. **35**(19) 2327–2331 (2002).

spin relaxation length – the mean distance traveled by an electron in solids before its spin flips. It depends on the spin independent mean free path, which reasonably should be the inelastic mean free path controlled by inelastic scattering, according to $l_s = (l_{in} v_F \tau_{\uparrow\downarrow})^{1/2}$, where v_F is the Fermi velocity and $\tau_{\uparrow\downarrow}$ is the **spin relaxation time**. The spin relaxation length is mainly defined by spin–orbit and exchange scattering. In materials of one chemical composition the spin relaxation length is shorter in the amorphous phase than the crystalline phase. Also note that holes have much shorter spin relaxation length than electrons because of their stronger spin–orbit coupling. A typical spin relaxation length of electrons in solids is estimated to be above 100 nm.

spin relaxation time → **spin relaxation length**.

spin–spin coupling – a reciprocal magnetic interaction between nuclei in a molecular system facilitated by the binding electrons of the molecule.

spin transfer torque – transfer of angular momentum from charge carriers in a spin-polarized current to a ferromagnet through which they are passing resulting in an alteration of the magnetization of the ferromagnet. The phenomenon can take place even in the absence of an applied magnetic field.

First described in: L. Berger, *Emission of spin waves by a magnetic multilayer transversed by a current,* Phys. Rev. B **54**(13), 9353–9358 (1996); J. C. Slonczewski, *Current-driven excitation of magnetic multilayers,* J. Magn. Mater. **159**(1), L1–L7 (1996).

spintronics – the field of science and engineering, which studies and aims to exploit the subtle and mind-bendingly esoteric spin properties of the electron to develop electronic devices that make use of the electron spin as well as the electron charge. The term was coined by S. A. Wolf in 1996 as a name for an initiative launched by the Defense Advanced Research Projects Agency of USA for the development of novel magnetic materials and devices.

spin valve – a thin film structure consisting of two ferromagnetic layers. It is constructed so that the magnetic moment of one of the ferromagnetic layers is hard to reverse by an externally applied magnetic field, whereas the moment of the other layer is very easy to reverse. This magnetically soft layer then acts as the valve control, being sensitive to manipulation with an external magnetic field. A typical change of the resistance is about 1% per Oersted. Spin valves fabricated within conventional microelectronic technology are used for the monitoring of magnetic fields, magnetic recording of information and for other magnetic device applications. For more details → **giant magnetoresistance effect**.

spin-valve transistor – a three-terminal device analogous to a metal base transistor. It is schematically shown in Figure S.18 with the related energy band diagram. The base region of the transistor contains a metallic **spin valve** sandwiched between two *n*-type silicon regions acting as a current emitter and collector. It employs hot electron transport across the spin valve.



Figure S.18 Schematic cross-section and energy diagram of the spin-valve transistor with the Si/Pt emitter and Si/Au collector Schottky barriers and the NiFe/Au/Co spin-valve base. After P. S. Anil Kumar, J. C. Lodder, *The spin-valve transistor*, J. Phys. D: Appl. Phys. **33**(22), 2911–2920 (2000). The graph shows the collector current in the transistor as a function of the external magnetic field applied.

The base is designed as an exchange decoupled soft spin-valve system, where two **ferromagnetic** materials, namely NiFe and Co, which have different coercivities, are separated by a nonmagnetic spacer layer (Au). The NiFe and Co layers have well-separated coercivity, such that clear parallel and antiparallel alignment is obtained over a wide temperature range. The ferromagnetic layers can be individually switched by the application of a suitable magnetic field. At the interfaces between the metal base and the semiconductors, **Schottky barrier**s are formed. In order to obtain the desired high-quality barrier with good rectifying behavior, thin layers of Pt and Au are incorporated at the emitter and collector side, respectively. These also separate the magnetic layers from direct contact with the silicon. Since the Si/Pt contact forms a high Schottky barrier, it is used as an emitter. The collector Schottky diode is defined in such a way that it has a lower barrier height than that of the emitter diode. The Si/Au contact, whose barrier height is nearly 0.1 eV less than the Si/Pt one suits this condition very well. A specially developed technique that comprises metal deposition onto two silicon wafers and their subsequent *in situ* bonding under ultrahigh vacuum conditions is used for the fabrication of such a spin-valve transistor.

The transistor operates as follows. A current is established between the emitter and the base (the emitter current I_e), such that electrons are injected into the base, perpendicular to the layers of the spin valve. Since the injected electrons have to go over the Si/Pt Schottky barrier, they enter the base as nonequilibrium hot electrons. The hot-electron energy is determined by the emitter Schottky barrier height, which is typically between 0.5 and 1 eV depending on the metal/semiconductor combination. As the hot electrons traverse the base they are subjected to inelastic and elastic scattering, which changes their energy as well as their momentum distribution. Electrons are only able to enter the collector if they have retained sufficient energy to overcome the energy barrier at the collector side, which is chosen to be somewhat lower than the emitter barrier. Equally important, the hot-electron momentum has to match with the available states in the collector semiconductor. The fraction of electrons that is collected, and thus the collector current I_c, depends sensitively on the scattering in the base, which is spin dependent when the base contains magnetic materials. It is tuned by switching the base valve from its aligned low-resistance state to its antialigned high-resistance state. The total scattering rate is controlled with an external applied magnetic field, which for example changes the relative magnetic alignment of the two ferromagnetic layers of a spin valve.

The magnetic response of the spin-valve transistor, called magnetocurrent (MC), is defined as the change in the collector current normalized to its minimum value, that is

$$\mathrm{MC} = \frac{I_\mathrm{c}^\mathrm{p} - I_\mathrm{c}^\mathrm{ap}}{I_\mathrm{c}^\mathrm{ap}},$$

where the superscripts p and ap refer to the parallel and antiparallel state of the spin valve, respectively.

The most important property of the spin-valve transistor is that its collector current depends sensitively on the magnetic state of the spin valve in the base. A typical dependence of the collector current on the magnetic field applied is shown in Figure S.18. At large magnetic fields, the two magnetic layers have their magnetization directions aligned parallel. This gives the largest collector current.

When the magnetic field is reversed, the different switching fields of Co (22 Oe) and NiFe (5 Oe) create a field region where the NiFe and Co magnetizations are antiparallel. In this state the collector current is drastically reduced. The relative magnetic response is indeed huge, providing the magneto current about 300% at room temperature and more than 500% at 77 K. Note that different scattering mechanisms of hot electrons may contribute to the decrease in the magnetic response. Scattering by thermal spin waves and thermally induced spin mixing look to be the most prominent.

The collector current and the magneto current are virtually independent of a reverse bias voltage applied across the collector Schottky barrier, when the leakage current of the collector is negligible. The reason for this behavior is that a voltage between base and collector does not change the maximum of the Schottky barrier when measured with respect to the Fermi energy in the metal. In other words, the energy barrier seen by hot electrons coming from the base is not changed. Similarly, a change in the emitter base voltage, or equivalently in the emitter current, does not affect the energy at which hot electrons are injected into the base. The result is that the collector current is simply linearly proportional to the emitter current, while the value of the collector current is a few orders of magnitude lower than the emitter current.

An important advantage of the spin-valve transistor is the huge relative magnetic effect, attained at room temperature, so that only small magnetic fields of a few Oersted are required. In spite of low current gain, it is a unique **spintronic** device with great prospects for magnetic memory and magnetic field sensor applications where current gain is not a critical issue.

First described in: D. J. Monsma, J. C. Lodder, T. J. A. Popma, B. Dieny, *Perpendicular hot electron spin-valve effect in a new magnetic field sensor: the spin-valve transistor,* Phys. Rev. Lett. **74**(26), 5260–5263 (1995).

SPLEEM – an acronym for a **spin-polarized low energy electron microscopy**.

split-gate structure – is used to ‘‘cut’’ electrostatically **quantum wires** and **quantum dots** from a **two-dimensional electron gas**. Its schematic design is presented in Figure S.19.

Metal gate electrodes are deposited on top of the semiconductor with a buried two-dimensional electron gas, which can be formed, for instance, in **modulation-doped** and **delta-doped** structures. When a reverse bias is applied to the gates the regions beneath are depleted of electrons by the **Schottky effect**, and current can only flow in the narrow ungated region. If the reverse bias is increased the fringing fields at the edges of the gates effectively squeeze the electron gas between them, and in this way the geometry can be varied within a single device. The particular configuration of the spin-gate electrodes defines the possibility to ‘‘cut’’ one-dimensional (**quantum wire**) or zero-dimensional (**quantum dot**) structures. Although the spin-gate approach is successful when applied to modulation-doped **heterojunction**s, it can hardly be used in the case of delta-doped structures. This



Figure S.19 Split gate arrangement for electrostatic cutting of one-dimensional and zero-dimensional elements from a two-dimensional electron gas.

is presumably because the gate isolation would begin to break down at the high electric fields required to deplete regions with an electron concentration close to or above 10^{13} cm^{-2}.

spontaneous emission – the radiation emitted when the internal energy of a quantum mechanical system drops from an excited upper state to a lower level without regard to the simultaneous presence of similar radiation. As a result, the population of the upper level is decreased and the population of the lower level increases. The excited system loses energy via the creation and emission of **photon**s.

sputtering – removal of surface atoms, atomic clusters or molecules by surface bombardment with energetic atomic particles, usually ions.

SQUID – an acronym for a **superconducting quantum interference device**.

SSIM – an acronym for a **saturated structured illumination microscopy**.

SSM – an acronym for a **scanning SQUID microscopy**.

stacking fault – a defect in a **face-centered cubic** or hexagonal crystal in which there is a change from a regular sequence of positions of atomic planes.

standing wave – a wave in which a ratio of an instantaneous value at one point to that at any other point does not vary with time.

Stark effect – modifications in emissions spectra which result from the application of a uniform external electric field to the source of light. In the atomic spectra from such a source many lines are appreciably displaced asymmetrically from their normal positions and commonly split into polarized components. Even more striking is the appearance of many new lines, which also have asymmetric displacements yet join with those of the normal spectrum to form groups with all-over patterns of marked symmetry. This effect is in many cases so great that in the green region the eye can readily detect the change in color. Modification of the electron orbits and related changes in their energy induced by the external electric field applied to atoms and molecules are responsible for the effect.

Suppression of the confined energy level by an electric field is also typical for low-dimensional structures, which has been named the **quantum confined Stark effect**. It is commonly observed in **heterostructures** and **quantum wells**. As the electric field F applied to the well has no impurity or defect dependence, then the change in the energy to second order $\triangle E^{(2)}$ is found to be proportional to F^2.

First described in: J. Stark, *Beobachtungen über den Effekt des elektrischen Feldes auf Spektrallinien*, Sitzungsber. Preuss. Akad. Wiss. (Berlin) 932–946 (1913) – the Stark effect; D. A. Miller, D. S. Chemla, T. C. Damen, A. C. Gossard, W. Wiegmann, T. H. Wood, C. A. Burrus, *Band edge electroabsorption in quantum well structures*, Phys. Rev. Lett. **53**(22), 2173–2176 (1984) – the quantum confined Stark effect.

Recognition: in 1919 J. Stark received the Nobel Prize in Physics for his discovery of the Doppler effect in canal rays and the splitting of spectral lines in electric fields.

See also www.nobel.se/physics/laureates/1919/index.html.

Stark–Einstein law states that one photon is absorbed by each molecule responsible for the primary photochemical process.

First described in: A. Einstein, *Thermodynamische Begründung des photochemischen Äquivalentgesetzes*, Ann. Phys. **37**, 832–838 (1912); J. Stark, *Über die Anwendung des Planckschen Elementargesetzes auf photochemische Prozesse. Bemerkung zu einer Mitteilung des Hrn. Einstein,* Ann. Phys. **38**, 467–469 (1912).

statics → **dynamics**.

STED – an acronym for **stimulated emission depletion microscopy**.

Stefan–Boltzmann constant → **Stefan–Boltzmann law**.

Stefan–Boltzmann law states that the total radiation emitted by a heated body increases rapidly with an increase in its temperature. For a perfect radiator, the radiating energy is proportional to the fourth power of the absolute temperature, so that for a body with surface area S it is $E = S\sigma T^4$, where σ is the **Stefan–Boltzmann constant**.

First described in: J. Stefan, *Über die Beziehung zwischen der Wärmestrahlung und der Temperatur,* Sitzungsber. Kaiser. Akad. Wiss. **79**, 391 (1879) – experiment, L. Boltzmann, *Ableitung des Stefanschen Gesetzes, betreffend die Abhängigkeit der Wärmestrahlung von der Temperatur aus der elektromagnetischen Lichttheorie,* Ann. Phys. **22**, 291–294 (1884) – theory.

step function – the function $\theta(a-b)$, which is equal to 1 for $a \geq b$ and zero for $a < b$.

Stern–Gerlach effect – splitting of an atomic beam passing through a strong inhomogeneous magnetic field into several beams. It is a demonstration of the quantization of angular momentum of electrons.

First described in: W. Gerlach, O. Stern, *Der experimentelle Nachweis der Richtungsquantelung im Magnetfeld,* Z. Phys. **9**(6), 349–352 (1922).

Recognition: in 1943 O. Stern received the Nobel Prize in Physics for his contribution to the development of the molecular ray method and his discovery of the magnetic moment of the proton.

See also www.nobel.se/physics/laureates/1943/index.html.

stereoisomers → **isomers**.

sterols → **lipids**.

stiffness constants → **elastic moduli of crystals**.

stiffness matrix → **Hooke's law**.

Stillinger–Weber potential – the interatomic many-body potential including empirical pair and triplet contributions:

$$V = \sum_{i} \sum_{j,i} V(r_{ij}) + \sum_{i} \sum_{j,i} \sum_{k,j} V(i,j,k),$$

with

$$V(r_{ij}) = A[B(r_{ij}/\sigma)^{-p} - r_{ij}/\sigma)^{-q}]exp(r_{ij}/\sigma - a)^{-1},$$

and

$$V(i,j,k) = h_{jik} + h_{ijk} + h_{ikj},$$

$$h_{jik} = \lambda exp[\gamma(r_{ij}/\sigma - a)^{-1} + \gamma(r_{ik}/\sigma - a)^{-1}][\cos\theta_{jik} + 1/3]^2.$$

Here r_{ij} is the distance between atoms i and j. It is implied that r_{ij} and r_{ik} are smaller than $a\sigma$. If not, the corresponding term $V(r_{ij})$ or h_{jik} vanishes. The angle θ_{jik} is the triplet angle subtended at atom i. The quantity σ sets the length scale and has a fixed value of 0.20951 nm. The values of the other parameters are fitted for a particular atomic system.

This potential gives a fairly realistic description of crystalline silicon. However, its built-in tetrahedral bias creates problems in other situations. Note that: it cannot predict the correct energies of the non-tetrahedral polytypes found under pressure; the coordination of the liquid is too low; surface structures are not correct.

First described in: F. H. Stillinger, T. A. Weber, *Computer simulation of local order in condensed phases of silicon,* Phys. Rev. B 31(8), 5262–5271 (1985).

stimulated emission – the radiation emitted when the internal energy of a quantum mechanical system drops from an excited upper state to a lower level when the process is induced by the presence of radiant energy at the same frequency. It is illustrated in Figure S.20 for the case of stimulated one-electron transition from an upper to a lower energy level. The process requires that the energy of stimulating photon given by the **Planck's law** be equal to the energy separation of the participating pair of quantum energy states. The emitted photon has the same energy as the original photon. The total radiation intensity is increased. When a sizable population of electrons resides in the upper level, it sets the stage for stimulated emission of multiple photons. The process can be thought of as an optical amplification. It forms a principle basis for **maser** and **laser operation** → **Einstein's coefficients A and B**.

First described in: A. Einstein, *Strahlungs-Emission and Absorption nach der Quantentheorie*, Verh. Deutsch. Phys. Ges. **18**, 318–323 (1916); A. Einstein, *Zur Quantentheorie der Strahlung*, Phys. Z. **18**, 121–128 (1917).



Figure S.20 Stimulated emission of photons.

stimulated emission depletion (STED) microscopy → **fluorescence nanoscopy**.

First described in: S. W. Hell, J. Wichmann, *Breaking the diffraction resolution limit by stimulated emission: stimulated-emission-depletion fluorescence microscopy*, Opt. Lett. **19**(11), 780–782 (1994); S. W. Hell, M. Kroug, *Ground-state depletion fluorescence microscopy, a concept for breaking the diffraction resolution limit*, Appl. Phys. B **60**, 495–497 (1995).

STM – an acronym for a **scanning tunneling microscopy**.

stochastic process – a process in which one or more variables take on values according to some, perhaps unknown, probability distribution.

stochastic optical reconstruction microscopy (STORM) → **fluorescence nanoscopy**.

First described in: M. J. Rust, M. Bates, X. Zhuang, *Sub-diffraction-limit imaging by stochastic reconstruction optical microscopy (STORM)*, Nature Methods **3**, 793–795 (2006).

Stokes equation → **Airy equation**.

Stokes law (of photoluminescence) states that the wavelength of the light-emitted by light-excited solids is always longer than the wavelength of the exciting radiation. This is because of the energy conservation, which means that the energy of an absorbed photon is greater than the energy of the emitted photon and the difference in the energy is dissipated as heat in exciting lattice vibrations. This energy difference is called the **Stokes shift**.

First described in: G. G. Stokes, Proc. R. Soc. **6**, 195 (1852).

Stokes line → **Raman effect**.

Stokes parameters → **Poincaré sphere**.

First described in: G. G. Stokes, *On the composition and resolution of streams of polarized light from different sources,* Camb. Phil. Soc. Trans. **9**, 399–423 (1852).

Stokes process → **Raman effect**.

First described in: G. G. Stokes, *On the dynamical theory of diffraction,* Camb. Phil. Soc. Trans. **9**, 1–62 (1856).

Stokes shift – a shift between the peak absorption and peak emission wavelengths.

Stone–Wales defect – the defect on the surface of a **carbon nanotube**, which consists of a local π/2 rotation of a C–C bond creating two pentagons and heptagons as illustrated in Figure S.21.



Figure S.21 Surface of (5,5) carbon nanotube with a Stone–Wales defect (indicated in light colour). From V. Gayathri, R. Geetha, J. Phys. Conf. Ser. *34*, 824–828 (2006).

It is also called the "5-7-7-5 defect". Once formed, the pentagon/heptagons could move along the structure, creating either dislocation centers in regions of positive (pentagons) or negative (heptagons) Gaussian curvature, which ultimately lead to the closing of the nanostructure. The defect causes little change to the diameter and chirality of the nanotube because the deformation effect is rather local. Meanwhile, the defect-related transformation effectively elongates the tube in the strain direction, releasing the excess strain energy.

Stone–Wales defects can also appear on boron nitride (BN) nanotubes, in which B–B and N–N bonds are formed.

First described in: A. J. Stone, D. J. Wales, *Theoretical studies of icosahedral C_{60} and some related species*, Chem. Phys. Lett. **128**(5–6), 501–503 (1986).

More details in: R. E. Smalley, M. S. Dresselhaus, G. Dresselhaus, P. Avouris, *Carbon Nanotubes: Synthesis, Structure, Properties and Applications* (Springer, Berlin, 2001).

Stone–Wales transformation – a $\pi/2$ rotation of two carbon atoms with respect to the midpoint of the C–C bond in a **graphene**-like structure. A sequence of such rearrangements supports coalescence processes of **fullerene**s or **carbon nanotube**s. Moreover, by this transformation, four hexagons are changed into two pentagons and two heptagons thus forming a **Stone–Wales defect**.

First described in: A. J. Stone, D. J. Wales, *Theoretical studies of icosahedral C_{60} and some related species*, Chem. Phys. Lett. **128**(5–6), 501–503 (1986).

Stoner–Wohlfarth model deals with the equilibrium state of the total magnetic moment of a single-domain **ferromagnetic** particle with uniaxial anisotropy. This particle is called a **Stoner–Wohlfarth particle**. The model assumes that all the magnetic moments in the particle are always parallel. The magnetization processes of the particle are effected through coherent rotation of all these moments. At any moment the directions of the magnetic moments within the particle are parallel. Any motion and pinning of domain walls are ignored in the model.

First described in: E. C. Stoner, E. P. Wohlfarth, *A mechanism of magnetic hysteresis in heterogeneous alloys*, Philos. Trans. R. Soc. Lond. A 240, 599–642 (1948).

Stoner–Wohlfarth particle → **Stoner-Wohlfarth model**.

STORM – an acronym for **stochastic optical reconstruction microscopy**.

strained superlattice → **superlattice**.

Stranski–Krastanov growth mode (of thin films) – a combined initial layer-by-layer thin film growth with subsequent droplet formation from the deposited material, as illustrated in Figure S.22. A continuous layer forms first, but then for one reason or another the system gets tired of this and switches to islands. For more details → **self–organization (during epitaxial growth)**.

First described in: I. N. Stranski, L. von Krastanow, *Zur Theorie der orientierten Ausscheidung von Ionenkristallen aufeinander*, Sitzungsber. Akad. Wiss. Wien, Math.-Naturwiss. Kl. IIb **146**, 797–810 (1938).



Figure S.22 Stranski–Krastanov growth mode during thin film deposition.

Strěda formula expresses the **Hall** conductivity as a sum of two contributions. Thus, components of the conductivity tensor σ are $\sigma_{ij} = \sigma^{I}_{ij} + \sigma^{II}_{ij}$. The first term depends on the structure of the solid and crystallographic orientation. Within the classical free-electron model with arbitrary energy-dependent self-energy $\sum(E)$ it is $\sigma^{I}_{xy} = -\omega\tau\sigma_{xx}$. Here ω is the **cyclotron frequency** and $\tau = \hbar/2(-\mathrm{Im}\sum(E_F))$ the lifetime, with E_F the **Fermy energy**.

The second term represents a quantum contribution. It is $\sigma^{II}_{xy} = -\sigma^{II}_{yx} = ec(\partial N(E)/\partial B)_{atE=E_F}$, where $N(E)$ is the number of states below the energy E and B is the induction of magnetic field. It has no classical analogy. In the classical limit the density of states is not a field-dependent quantity and σ^{II}_{xy} vanishes. Generally, this term depends on material constants only through the number of particles. It does not depend on the crystallographic orientation and the type of carrier scattering.

The formula shows that, if the **Fermi level** falls within the energy gap, the Hall conductivity can be given by the charge–density response to a magnetic field from orbital rather than Zeeman coupling. It can be used to calculate the conductivity of an electron gas in the presence of an additional periodic potential.

First described in: P. Středa, *Theory of quantised Hall conductivity in two dimensions*, J. Phys. C **15**, L717–L721 (1982).

Strehl ratio – the ratio of the illuminance at the peak of the diffraction pattern of an aberrated point image to that at the peak of an aberration-free image as formed by the same optical system.

First described in: K. Strehl, *Aplanatische und fehlerhafte Abbildung im Fernrohr*, Z. Instrumkde **15**, 362–370 (1895); K. Strehl, *Über Luftschlieren und Zonenfehler*, Z. Instrumkde, **22**, 213–217 (1902).

More details in: V. N. Mahajan, *Zernike annular polynomials for imaging systems with annular pupils*, J. Opt. Soc. Amer. **71**, 75–85 (1981).

structure-based engineering – the use of detailed knowledge of the structure and function of protein in order to produce desired changes and desired functions. Also called **rational design**.

More information in: J. A. Brannigan, A. J. Wilkinson, *Protein engineering 20 years on*, Nat. Rev. Molec. Cell Biol. **3**, 964–970 (2002).

structured illumination microscopy (SIM) → **fluorescence nanoscopy**.

First described in: M. G. L. Gustafsson, *Surpassing the lateral resolution limit by a factor of two using structured illumination microscopy*, J. Microsc. **198**, 82–87 (2000).

sub-band → **quantum confinement**.

superadditivity law states that the whole is more than the sum of its parts.
First described by Aristotle in his Metaphysics.

supercell method allows the use of the Bloch theorem also in the case of surfaces, clusters, molecules and defects calculations. An artificial periodicity is imposed on the calculation cell. The supercell is repeated over all space using periodic boundary conditions. Thus, in the case of a crystal surface the supercell will contain a crystal slab and a vacuum region repeated over all space. The vacuum region must be large enough so that the faces of the crystal slabs do not interact across the vacuum region and the crystal slab must be thick enough that the two surfaces of each slab do not interact through the crystal volume. For cluster or a molecule one assumes that the cluster or the molecule is enclosed in a sufficiently large box, in order to avoid interactions, and treated as a periodic system. For a defect, the supercell contains the defect surrounded by a sufficiently thick region of bulk crystal.
More details in: M. C. Payne, M. P. Teter, D. C. Allan, T. A. Arias, J. D. Joannopoulos, *Iterative minimization techniques for ab-initio total-energy calculations: molecular dynamics and conjugate gradients*, Rev. Mod. Phys. **64**(4) 1045–1097 (1992).

superconducting quantum interference device (SQUID) – the electronic device using the properties of electron-pair wave coherence and **Josephson effect**s to detect very small magnetic fields. The central element of a SQUID is a ring of superconducting material with one or more weak links. An example is shown in Figure S.23 with weak-links at points W and X (Josephson junctions). Critical current at these points is much less than the critical current of the main ring. This produces a very low current density making the momentum of the electron-pairs small. The wavelength



Figure S.23 Superconducting quantum interference device.

of the electron-pairs is thus very long leading to little difference in phase between any parts of the ring.

When a magnetic field B is applied perpendicular to the plane of the ring, a phase difference is produced in the electron-pair wave along the path XYW and WZX. A small current i is also induced to flow around the ring, producing a phase difference across the weak links. Normally the induced current would be of sufficient magnitude to cancel the flux in the hole of the ring but the critical current of the weak links prevents this.

The quantum condition that the phase change around the closed path must equal $2\pi n$ (n is an integer) can still be met by large phase differences across the weak links produced by even a small current. An applied magnetic field produces a phase change around the ring.

The phase difference due to the circulating current can either add to or subtract from that produced by the applied magnetic field but it is more energetically favorable to subtract. In this case a small anti-clockwise current i_- has the value $|i_-| = i_c \sin(\pi\Phi_a/\Phi_0)$, where i_c is the critical current, Φ_a is the flux produced in the ring by the applied magnetic field, and $\Phi_0 = h/2e$.

As the flux in the ring is increased from 0 to $0.5\Phi_0$ the magnitude of i_- increases to a maximum. As the flux is increased to $> 0.5\Phi_0$ it is now energetically favourable for a current, i_+, to flow in a clockwise direction, decreasing in magnitude to 0 as the flux reaches $0.5\Phi_0$. The circulating current has a periodic dependence on the magnitude of the applied field, with a period of variation of $0.5\Phi_0$, a very small amount of magnetic flux. Detecting this circulating current enables the use of a SQUID as a magnetometer. The device has a noise level as low as 3×10^{-15} $\mathrm{T{\cdot}Hz^{-1/2}}$ providing measurements of very small magnetic fields.

First described in: R. Jaklevic, J. Lambe, A. Silver, J. Mercereau, *Quantum interference from a static vector potential in a field-free region*, Phys. Rev. Lett. **12**(11), 274–275 (1964) – DC SQUID); J. E. Zimmerman in 1965 – RF SQUID.

More details in: J. Clarke, A. I. Braginski, *The SQUID Handbook: Fundamentals and Technology of SQUIDs and SQUID Systems* (Wiley-VCH, Weinheim, 2004); J. Clarke, A. I. Braginski, *The SQUID Handbook: Applications of SQUIDs and SQUID Systems* (Wiley-VCH, Weinheim, 2006).

superconductivity – disappearance of the electrical resistance of a material when it is cooled down. This phenomenon is characterized by a set of critical parameters, which includes critical temperature usually denoted T_c, critical magnetic field denoted H_c, and critical current denoted I_c. The critical temperature is the temperature at which electrical resistance of the material disappears. For most pure metals it is a few degrees above absolute zero.

The superconducting state in a material can be destroyed by an external applied magnetic field. It happens when the strength of the field reaches the critical value H_c, which is called the critical magnetic field. These fields are generally of the order of a few hundred Oersteds. It was also found experimentally that there exists for a current-carrying superconductor a critical current I_c above which the superconductivity is destroyed. The role of the current magnitude on the superconducting state of a material is recognized to be not a primary effect but rather due to the magnetic field produced by this current.

The number of known superconducting pure elements, compounds and alloys runs into thousands. Some 26 of the metallic elements are known to be superconductors in their normal forms, and another 10 become superconducting under pressure or when prepared in the form of highly disordered thin films. Semiconductors with very high densities of charge carriers are superconducting; others such as Si and Ge have high-pressure metallic phases, which are superconducting. Many elements, which are not themselves superconducting, form compounds which are. Classical superconductors are represented by pure metals, their binary compounds and alloys, which have critical temperatures not exceeding 40 K (the highest critical temperature 39 K is observed for MgB_2, 23 K for a specially prepared alloy of Nb, Al, Ge and 18.1 K for Nb_3Sn). Complex copper oxides (cuprates), discovered as superconductors by J. G. Bednorz and K. A. Müller in 1986, have much higher critical temperatures, for instance $YBa_2Cu_3O_7$, 92 K; $Tl_2Ca_2Ba_2Cu_3O_{10}$, 125 K. These materials are usually called **high-T_c superconductors**.

The different character of penetration of an external magnetic field into superconducting materials when they are heated up around critical the temperature is used to distinguish type I and type II superconductors. This is illustrated in Figure S.24. **Type I superconductors** in an external magnetic field below H_c at temperatures below T_c push out the magnetic field from their interior. In these conditions they behave like a perfect diamagnetic. If the applied field is increased above H_c, the entire superconductor reverts to the normal state and the flux of the magnetic field penetrates completely. The curve H_c versus temperature is thus a phase boundary in the magnetic field temperature plane separating a region where the superconducting state is thermodynamically stable from the region where the normal state is stable. This curve for type I superconductors is approximately parabolic: $H_c = H_0[1 - (T/T_c)^2]$, where H_0 is the value of H_c at absolute zero.

Type II superconductors are characterized by two critical magnetic fields: the lower critical field H_{c1} and the upper critical field H_{c2}. In applied fields less than H_{c1}, the superconductor completely excludes the fields, just as a type I superconductor does below H_c. At fields above H_{c1}, however, magnetic flux begins to penetrate the superconductor in microscopic filaments. Each wire consists of a normal core in which the magnetic field is large, surrounded by a superconducting region in which flows the vortex of the persistent supercurrent maintaining the field in the core. The diameter of the filament is typically of the order of 0.1 nm. In sufficiently pure and defect-free type II superconductors such wires tend to arrange themselves in a regular lattice. This vortex state of the superconductor is known as the mixed state. It exists for magnetic fields between H_{c1} and H_{c2}. At H_{c2} the superconductor becomes normal and the magnetic field penetrates completely.

Superconductivity was given a comprehensive explanation in the theory proposed by J. Bardeen, L. N. Cooper and J. R. Schrieffer, which bears their names (it is also abbreviated as the **BCS theory**). The basic idea behind the theory is that two electrons can attract each other and bind together to form a bound pair, called a **Cooper pair**, if they are in the presence of a high-density fluid of other electrons,



Figure S.24 Effect of temperature and external magnetic field on the superconducting state in type I and type II superconductors.

no matter how weak the interaction is. A Cooper pair is formed by electrons with opposite spins giving the total spin of the pair to be zero. Such pairs follow Bose–Einstein statistics so that all of them condense to the same ground state at low temperatures.

The pairing interaction is so weak that the two members of a pair are separated by a distance which turns out to be just the coherence length. The average distance between two paired electrons not involved in the same pair, however, is a hundred times smaller. When an electric field is applied, the electrons in a couple must move together. Consequently, electrons between the Cooper pairs have to follow them as far as they feel each other by the exciting interaction. A localized perturbation, which might deflect a single electron in a normal state and thus give rise to some resistance, cannot do so in the superconducting state without affecting all the electrons participating in the superconducting ground state at once. That is not impossible, but extremely unlikely, so that a collective drift of the coherent superconducting electrons, corresponding to an electric current, will be dissipationless.

The BCS theory gives three parameters essentially determining the critical temperature via $k_B T_c = 1.13\hbar\omega_D \exp[-1/VN(E_F)]$. These are the **Debye frequency**

ω_D, the strength of the coupling between the electrons and the phonons in the solid V, and the electron density of states at the Fermi level $N(E_F)$.

A number of previous theories of superconductivity proposed by F. London and H. London, V. L. Ginzburg and L. D. Landau and others have found logical explanation within the BCS theory. Nevertheless, this theory meets some difficulties in the interpretation of high-T_c superconductivity in cuprates.

First described in: H. Kamerlingh-Onnes, *Disappearance of the electrical resistance of mercury at helium temperature*, Communication no. 122b from the Phys. Lab. Leiden, Electrician **67**, 657–658 (1911) – experimental observation; V. L. Ginzburg, L. D. Landau, *Theory of superconductivity*, Zh. Exp. Teor. Fiz. **20**(12), 1064–1082 (1950) – theory of superconductivity (in Russian); A. A. Abrikosov, *An influence of the size on the critical field for type II superconductors*, Doklady Akademii Nauk SSSR **86**(3), 489–492 (1952) – theoretical prediction of type II semiconductors (in Russian); J. Bardeen, L. N. Cooper, J. R. Schrieffer, *Theory of superconductivity*, Phys. Rev. **108**(5), 1175–1204 (1957) – a comprehensive theory; J. G. Bednorz, K. A. Müller, *Possible high-T_c superconductivity in the Ba-La-Cu-O system*, Z. Phys. B **64**(2), 189–193 (1986) – experimental observation above liquid nitrogen temperature (77 K).

More details in: M. Cyrot, D. Pavuna, *Introduction to Superconductivity and High-T_c Materials* (World Scientific, Singapore, 1992);

http://www.suptech.com/knowctr.html.

Recognition: in 1913 H. Kamerlingh-Onnes received the Nobel Prize in Physics for his investigations on the properties of matter at low temperatures which led, inter alia, to the production of liquid helium; in 1972 J. Bardeen, L. N. Cooper and J. R. Schrieffer received the Nobel Prize in Physics for their jointly developed theory of superconductivity, usually called the BCS-theory; in 1987 J. G. Bednorz and K. A. Müller received the Nobel Prize in Physics for their important breakthrough in the discovery of superconductivity in ceramic materials; in 2003 A. A. Abrikosov, V. L. Ginzburg and A. J. Leggett received the Nobel Prize in Physics for pioneering contributions to the theory of superconductors and superfluids.

See also www.nobel.se/physics/laureates/1913/index.html.

See also www.nobel.se/physics/laureates/1972/index.html.

See also www.nobel.se/physics/laureates/1987/index.html.

See also www.nobel.se/physics/laureates/2003/index.html.

superelastic scattering – a scattering process in which a particle scattered in a solid absorbs energy from an excited atomic system and therefore possesses a greater kinetic energy after collision than before, while the previously excited atom returns to its ground state without giving out any net radiation.

superfluidity – the frictionless flow of liquid helium at a temperature below the lambda point (2.178 K).

First described in: P. L. Kapitza, *Viscosity of liquid helium below λ-point*, C. R. (Doklady) Acad. Sci. USSR **18**(1), 21–23 (1938) – experiment; L. Landau, *Theory of the superfluidity of helium II*, Phys. Rev. **60**(4), 356–358 (1941) – theory.

Recognition: in 1962 L. D. Landau received the Nobel Prize in Physics for his pioneering theories for condensed matter, especially liquid helium; in 1996 D. Lee, D. Osheroff and R. Richardson received the Nobel Prize in Physics for their discovery of superfluidity in helium-3; in 2003 A. A. Abrikosov, V. L. Ginzburg and A. J. Leggett received the Nobel Prize in Physics for pioneering contributions to the theory of superconductors and superfluids.

See also www.nobel.se/physics/laureates/1962/index.html.

See also www.nobel.se/physics/laureates/1996/index.html.

See also www.nobel.se/physics/laureates/2003/index.html.

superlattice – a monocrystalline film of one material reproducing the lattice constant of the monocrystalline substrate made of another material. When both materials have identical or very close lattice constants they produce so-called **pseudomorphic superlattices**. There are only a few such lattice-matched systems among semiconductors. Meanwhile, identical lattice constants are not a necessary condition for pseudomorphic growth of one semiconductor material on another.

Within a limited thickness of the film it is possible to force deposited atoms to occupy positions corresponding to the lattice constant of the substrate even though they may be different in the bulk. A **strained** but otherwise perfect superlattice is formed. It is schematically illustrated in Figure S.25.



Figure S.25 Formation of strained and relaxed epitaxial films.

As the strain energy increases with the film thickness, beyond some critical thickness the film can lower its total energy by relieving the strain via the creation of misfit dislocations. The deposited material takes up its natural lattice constant, yielding a relaxed film. The critical thickness obviously depends on the lattice mismatch and elastic parameters of the contacting materials at the deposition temperature. In principle, by keeping the deposited film thinner than the critical thickness, it is possible to grow a strained superlattice from any two semiconductors with the same type of crystalline structure without regard to their particular lattice constants.

In practice, the smallest possible lattice mismatch and difference in electronic properties are desired for perfect superlattices creating heterojunctions with an appropriate potential barrier. There is a choice of semiconductors for this. Figure S.26 presents the energy band gaps of a number of semiconductors with **diamond** and **zinc blende structures** versus their lattice constants.



Figure S.26 Low-temperature band gaps and lattice constants of semiconductors with diamond and zinc blende crystalline structures. Hexagonal nitrides are plotted for consistency in terms of their α lattice constants.

The shaded vertical regions show the groups of semiconductors with similar lattice constants. Materials within the same shaded region but having different band gaps can be combined to form **heterojunction**s with the potential barriers corresponding to their band offsets. The choice of band offsets can be extended by the use of binary (such as SiGe), ternary (such as AlGaN, AlGaAs) and quaternary (such as GaInAsP) compounds. The solid lines in the figure joining some of the semiconductors indicate that these materials form stable intermediate compounds over the entire composition range. Among the semiconductors shown, the nitrides have lattice constants smaller than other materials because of the small size of the nitrogen atom.

superposition principle states that if a physical system is acted upon by a number of independent influences, the resultant effect is the sum (vector or algebraic, whichever is appropriate) of the individual influences. This principle is applied only to linear systems, that is systems the behavior of which can be expressed as linear differential equations.

supramolecular chemistry – the chemistry beyond the molecule, bearing on organized entities of higher complexity that result from the association of two or more chemical species held together by intermolecular forces (after J.-M. Lehn). In more generalized form the chemistry of systems made of two or more molecular components.

More details in: J.-M. Lehn, *Supramolecular Chemistry : Concept and Perspectives* (VCH, Weinheim, 1995); V. Balzani, M. Venturi, A. Credi, *Molecular Devices and Machines: A Journey into the Nanoworld* (Wiley-VCH, Weinheim, 2003).

supramolecule – a system of two or more molecular entities held together and organized by means of intermolecular (noncovalent) binding interactions.

More details in: K. Ariga, T. Kunitake, *Supramolecular Chemistry – Fundamentals and Applications: Advanced Textbook* (Springer, Berlin, 2006).

Recognition: in 1987 D. J. Cram, J. M. Lehn and C. J. Pedersen received the Nobel Prize in Chemistry for their development and use of molecules with structure-specific interactions of high selectivity.

See also www.nobel.se/chemistry/laureates/1987/index.html.

surface reconstruction – lowering of the symmetry of real surfaces of crystals as a result of the surface atomic relaxation processes. In fact, solid surfaces are usually of lower symmetry than they would be if the crystals were simply terminated at a plane and all remaining atoms remained at their original positions.

A highly unstable or metastable state occurs when interatomic bonds are broken at a surface by cleavage. The surface (and subsurface) atoms use considerable elastic distortive energy in order to reach a structure that facilitates new bond formation. It initiates the reconstruction of the surface yielding geometrical structures that are much more complex than the ideal surface termination.

Special notations are used to indicate reconstructed surfaces. When translation vectors of the surface **unit cell** are $n\mathbf{a}$ and $m\mathbf{b}$, with $\mathbf{a}$ and $\mathbf{b}$ being the translation vectors of corresponding plane of the underlying undisturbed solid and n and m positive integers, the surface structure is labeled $\mathrm{p}(n \times m)$. The letter "p", meaning primitive, is often omitted. This simple notation is convenient when the surface unit cell is in registry with the substrate unit cell. The same scheme is used to describe square or rectangular lattices (with basis vectors $n\mathbf{a}$ and $m\mathbf{b}$) having two atoms per unit cell, the second atom occupying the center of the square or the rectangle. Such a structure is denoted $\mathrm{c}(n \times m)$, where "c" means centered. More complex notation, like $(x \times y)\mathrm{R}\theta$ is applied when the surface unit cell is rotated with respect to the substrate unit cell or when the ratio of the dimensions of these cells is not an integer. It means that the surface structure is obtained from the substrate unit cell by multiplying the length of the basis vectors by x and y and rotating the cell through the angle θ.

More details in: W. Mönch, *Semiconductor Surfaces and Interfaces* (Springer, Berlin, 1995); F. Bechstedt, *Principle of Surface Physics* (Springer, Berlin, 2003).

surfactant – a surface active agent easily absorbing onto surfaces and reducing the surface tension. Detergents or cleaning agents are prominent examples for solid surfaces. They reduce the surface tension of the water resulting in a better cleaning ability or wetting property.

Sutton–Chen potential – the interatomic potential adding long-range interactions to the **Finnis–Sinclair potential**. It has the form

$$V(r_{ij}) = \epsilon[\sum_{ij}(\frac{a}{r_{ij}})^n - C\sum_i \sqrt{\sum_{j\neq i}(\frac{a}{r_{ij}})^m}],$$

where ϵ is a parameter with dimensions of energy, C is a dimensionless fitting parameter, a is the lattice constant, r_{ij} is the distance between atoms i and j, and m and n are positive integers with $n > m$.

This potential has been developed for computer simulations of atomic structures in which **van der Waals** type interactions between well-separated atomic clusters are as important as the description of metallic bonding at short range. The potential always favors **face-centered cubic (fcc)** and **hexagonal close-packed (hcp)** structures over the **body-centered cubic (bcc)** structure. It displays convenient scaling properties for both length and energy, and a number of properties of the perfect crystal may be derived analytically.

The potential provides a reasonable description of various bulk properties, with an approximate many-body representation of the delocalized metallic bonding. However, it does not include any directional terms, which are likely to be important for transition metals with partially occupied d shells.

First described in: A. P. Sutton, J. Chen, *Long-range Finnis-Sinclair potentials*, Phil. Mag. Lett. 61, 139–146 (1990).

More details in: G. A. Mansoori, *Principles of Nanotechnology: Molecular-based Study of Condensed Matter in Small Systems* (World Scientific, Singapore, 2005).

SWAP gate → **quantum logic gate**.

swarm intelligence – the emergent, collective intelligence of social insect colonies. Individually, one insect may not be capable of much, but collectively social insects are capable of achieving great things. As an example, a colony of ants can collectively find out where the nearest and richest food source is located, without any individual ant knowing it. By discovering the shortest path to a food source, the ants solve collectively an optimization problem using emergent computation. Learning from this has helped, for example, in developing algorithms for solving routing problems in telecommunications networks. Swarm intelligence looks to be a mindset rather than a technology, initially inspired by how social insects operate. It is a **bottom-up approach** to controlling and optimizing distributed systems, using resilient, decentralized, self-organized techniques.

More details in: E. Bonabeau, M. Dorigo, G. Theralauz, *Swarm Intelligence: From Natural to Artificial Systems* (Oxford University Press, 1999).

symmetry that is exploited in solid state physics is defined in terms of symmetry operations. An operation is said to be a symmetry operation if the body looks exactly the same after the operation as it did before the operation was carried out. The operation could be, for example, rotations through certain angles or reflections in various mirror planes.

symmetry group – a collection of symmetry elements which satisfy the properties listed in the Table S.2.

More details in: S. J. Joshua, *Symmetry Principles and Magnetic Symmetry in Solid State Physics* (Adam Hilger, Bristol, 1991).

Table S.2 The basic type of symmetry elements in Schoenflies notation.

Symmetry element	Symbol	Symmetry operation(s)
Identity element	E	no operation; like multiplication by 1
Mirror plane	σ	reflection in a mirror
Center of inversion or inversion symmetry	I	inversion of all coordinates through the centre; it changes coordinates (x, y, z) to $(-x, -y, -z)$, which can be described as a reflection in a point
Proper rotation axis	C_n	n-fold rotation about an appropriate axis. An n-fold axis generates n operations, for example the symmetry element C_6 implies the operations $C_6^1, C_6^2, C_6^3, C_6^4, C_6^5, C_6^6 = E$
Improper rotation axis	S_n	n-fold rotation about an axis followed by a reflection in a plan perpendicular to the axis of rotation, that is the presence of S_n implies the independent existence of both C_n and σ elements

synergetics – an interdisciplinary science studying and explaining the formation and self-organization of patterns and structures in open systems far from thermodynamic equilibrium.

More details in: H. Haken, *Synergetics* (Springer, Berlin, 2004).

T

From Talbot's law to type II superconductors

Talbot's law states that the brightness of an object that is examined through a slotted disc, rotating over a critical frequency, is proportional to the angular aperture divided by the opaque sectors.

First described in: H. F. Talbot, *Experiments on light*, Phil. Mag. **5**, 321 (1834).

Tamm levels also called surface states, appear in solids at their surfaces as a result of the rupture of chemical bonds and distortion of the lattice there. In semiconductors, they usually locate in the forbidden energy gap.

First described in: I. E. Tamm, *Über eine mögliche Art der Elektronenbindung an Kristalloberflächen*, Z. Phys. **76**(11/12), 849–850 (1932).

tandem solar cell = **multijunction solar cell**.

Taylor criterion states that in interferometers in which the separation of the maxima is equal to the half-value width, a slight drop in intensity between fringes is distinguishable and the fringes can be considered resolved.

Taylor series corresponding to a function $f(x)$ at a point x_0 is the infinite series whose n-th term is $(1/n!)f^{(n)}(x_0)(x - x_0)^n$, where $f^{(n)}(x)$ denotes the n-th derivative of $f(x)$.

First described in: B. Taylor, *Methodus Incrementorum Directa et Inversa* (London, 1715).

TEEEM – an acronym for a **tip-enhanced electron emission microscopy**.

Teller–Redlich rule states that for two isotopic molecules the product of the frequency ratio values of all vibrations of a given symmetry type depends only on the geometrical structure of the molecule and the masses of the atoms and not on the potential constants.

First described in: O. Redlich, Z. Phys. Chem. B **28**, 371 (1935).

TEM – an acronym for a **transmission electron microscopy**.

template – a pattern or a structure which is used to guide or to frame a reaction or **adsorption** on solid surfaces. Its function principle has much in common with a lettering stencil.

tera- – a decimal prefix representing 10^{12}, abbreviated T.

Tersoff potential – the empirical interatomic many-body potential having the form of the **Morse potential**, but with the bond-strength parameters depending upon local environment including angle dependency upon bond-lengths: $V(r_{ij}) = f_c(r_{ij})[A\exp(-ar_{ij}) - B\exp(-br_{ij})]$, where r_{ij} is the distance between atoms i and j, A, a, B, b are positive constants, f_c is the cut-off function of the potential. The first term reproduces the repulse interaction, and the second term describes covalent bonding.

First described in: J. Tersoff, *New empirical model for the structural properties,* Phys. Rev. Lett. **56**(6), 632–635 (1986).

Tersoff–Hamann theory describes electronic interaction between the tip of a **scanning tunneling microscope (STM)** and a sample in terms of their **wave functions**. In this interacting system, schematically shown in Figure T.1, the tunneling current is supposed to depend on the overlap of the wave functions of the tip and the sample atoms, which decay exponentially. Thus, only the orbitals localized at the outermost tip atom are of importance for the tunneling process.

The main point of the theory is the choice of the wave function of the tip. It is modeled as a locally spherical potential with curvature R about the center r_0. For this case the tip wave function is chosen to have the form of an s wave:

$$\Psi_t(r) = kR\frac{\exp(-k|\gamma - \gamma_0|)}{k(r - r_0)}\exp(kR),$$

where $k = [2m\phi/\hbar^2]^{1/2}$ with m the effective mass of an electron and ϕ the **work function** of the surface. Finally, the current from the tip to the sample under the applied bias V has been found to be $I \sim VN_t(E_F)LDOS(r_0, E_F)$, where $N_t(E_F)$ is



Figure T.1 Tip-sample configuration and related parameters in the Tersoff-Hamann model.

density of states at the **Fermi level** in the tip, and $LDOS(r_0, E_F)$ is the local density of states of the sample at the Fermi level evaluated at the tip center.

Theory predicts that the basic quantity imaging with STM is the local density of states of the sample. It is used in the interpretation of experimental STM images.

First described in: J. Tersoff, D. R. Hamann, *Theory and application for the scanning tunneling microscope,* Phys. Rev. Lett. **50**(25), 1998–2001 (1983).

tetragonal lattice – a **Bravais lattice** in which the axes of a unit cell are perpendicular and two of them are equal in length to each other but not to the third axis.

thermal noise in electrical circuits is a consequence of thermally induced charge fluctuations in it. It is mathematically described by the **Nyquist formula**.

thermionic emission – the emission of electrons from a hot solid. It is usually described by the **Richardson equation**.

thermistor – a solid-state semiconducting structure that changes electrical resistance with temperature. Materially, some kind of ceramic composition is used. It has much higher electrical resistance than identical in function metallic bolometers and hence requires much higher voltages to become useful.

thermocouple – a device composed of dissimilar metals that, when welded together, develop a small voltage dependent upon the relative temperature between the hotter and colder junctions. Banks of thermocouples connected together in parallel/series make up a multiple thermocouple, or a thermopile. Either may be thought of as a weak battery that converts radiant energy to electrical energy.

thermodynamic density of states –

$$\frac{\partial n}{\partial \mu} = \int n(E) \frac{\partial f(E, \mu)}{\partial \mu} \mathrm{d}E = \int n(E) \left[\frac{\partial f(E, \mu)}{\partial E} \right] \mathrm{d}E,$$

where $n(E)$ is the ordinary density of states and $f(E, \mu)$ is the distribution function.

thermogravimetry – a technique to measure automatically the weight change as a material is heated either isothermally or in a programmed manner. It is used to study thermal stability of materials and volatile contents, as well as to perform residue or purity analysis.

thermoluminescence – production of light by heating a sample.

thermopower = **Seebeck coefficient** → **Seebeck effect** describes the voltage induced by a temperature difference between two contacts $\alpha(T) = V/(T_2 - T_1)$.

thiols – organic compounds that contain the −SH group. The simplest example is methanethiol CH_3SH.

Thomas–Fermi equation – a differential equation of the form

$$x^{1/2}(\mathrm{d}^2y/\mathrm{d}x^2) = y^{3/2}$$

that is used in calculations of the potential and density of electrons within the Thomas–Fermi atom model (**Thomas–Fermi theory**) in which electrons are treated as independent particles and electron–electron interaction energy is considered to arise solely from the electrostatic energy. The dimensionless variables are defined as

$$x = \left[\left(\frac{9\pi^2}{128Z}\right)^{1/3}\frac{\hbar^2}{me^2}\right]r \quad \text{and} \quad y = \frac{r|\phi|}{Ze},$$

where Z is the number of electrons in the atom, m is the electron mass, r is the distance, ϕ is the electrostatic potential. A physically meaningful solution has to satisfy the boundary conditions $y(0) = 1$ and $y(\infty) = 0$.

Thomas–Fermi screening length – a penetration depth of an impurity charge screened by mobile electrons in metals $L = [(e^2/\epsilon_0)/D(E_\mathrm{F})]^{-1/2} = (3e^2n/2\epsilon_0E_\mathrm{F})^{-1/2}$, where $D(E_\mathrm{F})$ is the density of states at the **Fermi level** E_F and n is the electron concentration. The quantity $(L)^{-1}$ is denoted as the **Thomas–Fermi screening wave number**.

Thomas–Fermi screening wave number → **Thomas–Fermi screening length**.

Thomas–Fermi theory – a simple many-body theory, sometimes called "statistical theory", proposed shortly after E. Schrödinger invented his quantum-mechanical wave equation. For a system with a large number of interacting electrons, the **Schrödinger equation**, which would give the exact electron density and ground state energy, cannot be easily handled. The basic idea of the Thomas–Fermi theory is to find the energy of electrons in a spatially uniform potential as a function of the density. Then one uses this function of the density locally, even when the electrons are in the presence of an external potential. The theory contains two basic ideas: the first electrostatic, the second quantum statistical. From the first we have that the electrostatic potential satisfies the **Poisson equation** that links potential and charge density. With quantum statistics we can connect the momentum of the electrons to the energy, the potential and the electron density. Thus, one obtains the Thomas–Fermi equations that provide a one-to-one implicit relation between the density and the external potential.

$$n(r) = \frac{1}{3\pi^2}(\frac{2m}{\hbar^2})^{3/2}[\mu - v_{eff}(r)]^{3/2}, \quad v_{eff} \equiv v(r) + \int(\frac{n(r')}{|r-r'|})dr',$$

where $n(r)$ is the electron density distribution, $v(r)$ is the applied external potential, μ is the r-independent chemical potential and the potential given by the integral is just the classically computed electrostatic potential times (-1), generated by the electron density distribution. The theory apply best for systems of slowly varying density and it was useful for describing qualitative trends like total energies of atoms.

The Thomas–Fermi theory was the first theory of electronic energy in terms of the electron density distribution. The idea of handling density functionals later became very successful in the treatment of many-body problems → **density functional theory.**

First described in: L. H. Thomas, *The calculation of atomic fields*, Proc. Camb. Phil. Soc. **23**, 542–548 (1927); E. Fermi, *Un metodo statistico per la determinazione di alcune proprietá dell'atomo*, Rend. Accad. Naz. Lincei **6**, 602–607 (1927).

More details in: E. H. Lieb, *Thomas–Fermi and related theories of atoms and molecules*, Rev. Mod. Phys. **53**(4), 603–641 (1981).

Thomas precession – the precession of a spinning object when it accelerates. It is a consequence of the special relativity consideration of the system. It gives a correction to the **spin–orbit interaction**, which takes into account the relativistic time dilatation between the electron and the nucleus in hydrogenic atoms.

First described in: L. H. Thomas, *The motion of the spinning electron*, Nature **117**, 514 (1926); L. H. Thomas, *The kinematics of an electron with an axis*, Phil. Mag. **3**(7), 1–22 (1927).

More details in: W. Rindler, *Relativity Special, General and Cosmological, Second edition* (Oxford University Press, Dallas, 2006).

See also www.mathpages.com/rr/s2-11/2-11.html.

Thomson effect – heat liberation or absorption when an electric current traverses a region where a temperature gradient $\triangle T$ exists along a single homogeneous conductor. The rate of the reversible heat generation or evolution is $Q = \tau I \triangle T$, where τ is the **Thomson coefficient** and I is the electric current.

Thomson relations → **Kelvin relations**.

Thomson scattering – scattering of electromagnetic radiation by free or very loosely bound charged particles. The energy is taken away from the primary radiation as the charged particles are accelerated by the transverse electric field of the radiation.

three-body-scattering (3BS) approach is based on the many-body **Hamiltonian**, containing on-site core–valence Coulomb interactions, being projected on a set of states obtained by adding a finite number of electron–hole pairs to the ground state of the single-particle band Hamiltonian. The expansion is truncated to include just one electron–hole pair, that is configurations with just three particles (two holes and one electron). The method can be seen as an extension to the solid state of the configuration–interaction scheme commonly used for finite systems. It fully includes the itinerant character of the valence states and treats the on-site many-body electron-electron interaction beyond a mean field. It is based on a non-perturbative solution of a multi-band **Hubbard Hamiltonian** and provides spin- and *k*-dependent self-energies, spectral functions, quasiparticle energies and lifetimes. It applies to all correlation regimes, from the low correlation regime up to the atomic limit, reproducing energy renormalization, band narrowing, quasiparticle quenching and, for sufficiently large Hubbard interaction, opening of a **Mott–Hubbard** gap. The method has been successfully applied in transition metals, transition-metal oxides, and cuprates.

First described in: J. Igarashi, *Three-body problem in transition metals: Application to nickel*, J. Phys. Soc. Jpn. **52**(8), 2827–2837 (1983); C. Calandra, F. Manghi, *Three-body scattering theory of correlated hole and electron states*, Phys. Rev. B **50**(4), 2061–2074 (1994); F. Manghi, C. Calandra, S. Ossicini, *Quasiparticle band structure of NiO: The Mott–Hubbard picture regained*, Phys. Rev. Lett. **73**(23), 3129–3132 (1994).

tight-binding approach assumes that valence electrons are completely delocalized when the solid is formed. In contrast, core electrons remain very localized and, thus, discrete core levels of the atoms are only very slightly broadened in the solid. The corresponding wave functions are not very different, in the vicinity of each atom, from the atomic wave functions.

time-dependent Schrödinger equation → **Schrödinger equation**.

time-independent Schrödinger equation → **Schrödinger equation**.

tip-enhanced electron emission microscopy (TEEEM) – like **scanning tunneling microscopy** this technique measures the effect of a sample surface on the electrical current flowing through a probe tip; here, however, the current is stimulated by a pulsed laser beam focused on the tip. Due to the fact that the **laser** field is affected by any kind of sample that is introduced near to the probe, the device acts in three dimensions. Moreover, the current flow scales highly nonlinearly with changes in the laser field, making the imaging extremely sensitive to whatever is out near the probe tip. Ultrafast time resolution is another advantage of this technique.

First described in: C. Ropers, D. R. Solli, C. P. Schulz, C. Lienau, T. Elsaesser, *Localized multiphoton emission of femtosecond electron pulses from metal nanotips,* Phys. Rev. Lett. **98**, 043907 (2007).

More details in: H. Batelaan, K. Uiterwaal, *Tip-top imaging,* Nature **46**, 500–501 (2007).

***T*-matrix** = transfer matrix. It describes a transfer process from one region of a nonhomogenous system to another usually accounting for incident and reflected fluxes. For instance, if a system contains a barrier separating it into right and left side regions, wave propagation through this barrier from left to right can be expressed by the matrix **T** satisfying

$$\begin{pmatrix} C \\ D \end{pmatrix} = \mathbf{T} \begin{pmatrix} A \\ B \end{pmatrix},$$

where A and B are the amplitudes of the incident and reflected waves, respectively, at the left side of the barrier and C and D are the amplitudes of the transmitted and scattered back to the barrier waves, respectively, at the right side.

Toffoli gate → **quantum logic gate**.

Tomonaga–Luttinger liquid = **Luttinger liquid**.

Tomonaga–Luttinger model = **Luttinger model**.

Tomonaga–Schwinger equation – an equation of motion of the state vector of a quantized field expressed in a covariant form. This is achieved by laying down a method for finding the field on a space-like surface provided this field is known on a similar surface initially close to that space-like surface. For an arbitrary space-like surface σ it is: $i\hbar c\partial\Psi(\sigma)/\partial\sigma(x) = \mathbf{H}(x)\Psi(x)$, where the interaction Hamiltonian is $\mathbf{H}(x) = -c^{-1}j(x)\mathbf{A}(x)$. Here $j(x)$ is the electric current density of the electrons, and $\mathbf{A}(x)$ is the electromagnetic vector potential.

First described in: S. Tomonaga, *On a relativistically invariant formulation of the quantum theory of wave fields*, Prog. Theor. Phys. **1**(2), 27–42 (1946); J. Schwinger, *Quantum electrodynamics. I. A covariant formulation*, Phys. Rev. **74**(10), 1439–1461 (1948).

Recognition: in 1968 S. Tomonaga and J. Schwinger shared with R. P. Feynman the Nobel Prize in Physics for their fundamental work in quantum electrodynamics, with ground-breaking consequences for the physics of elementary particles.

See also www.nobel.se/physics/laureates/1968/index.html.

top-down approach – one of two ways to fabricate micrometer and nanometer size elements of integrated electronic circuits. It pre-supposes that the manufacturing starts at the wafer level and employs a variety of sophisticated lithographic and etching techniques in order to pattern the substrate. The alternative is a **bottom-up approach**.

torsion – a twisting deformation in a solid about an axis in which lines that were initially parallel to the axis become helices.

Touschek effect – the effect whereby two electrons lose synchronism with the accelerating field and are lost during synchronous radiation. The effect is produced by the scattering of the electrons that are oscillating in the equilibrium orbit, which results in the transferral of transverse momentum into longitudinal momentum.

This effect is one of the limiting mechanism for present-day synchrotron radiation sources.

First described in: C. Bernardini, G. F. Corazza, G. Di Giugno, G. Ghigo, J. Haissinski, P. Marin, R. Querzoli, B. Touschek, *Lifetime and beam size in a storage ring*, Phys. Rev. Lett. **10**, 407–409 (1963).

trace operation denoted Tr. For a vector **A** it means $\mathrm{Tr}\mathbf{A} = \sum_k \langle k|\mathbf{A}|k\rangle$, where $\{|k\rangle\}$ is any orthonormal basis for the **Hilbert space**. The numerical result is independent of the basis choice.

transcription – the central dogma of molecular biology stating that the information required to build a living cell or organism is stored in **DNA**. This information must be transferred from the DNA to the **proteins**. These processes are called transcription and translation and are all executed by biomolecular components, mostly proteins and nucleic acids.

transient spectral hole-burning → **spectral hole-burning**.

transistor – a three-terminal semiconductor device for switching and amplification of electric signals.

First described in: J. Bardeen, W. H. Brattain, *Three-electrode circuit element utilizing semiconductive materials*, US Patent no. 2524035 (1948); J. Bardeen, W. H. Brattain, *The transistor, semiconductor triode*, Phys. Rev. **74** (1), 230–231 (1948); W. Shockley, *The theory of p-n junctions in semiconductors and p-n junction transistors*, Bell Syst. Tech. J. **28**(3), 435–489 (1949).

Recognition: in 1956 W. Shockley, J. Bardeen and W. H. Brattain received the Nobel Prize in Physics for their researches on semiconductors and their discovery of the transistor effect.

See also www.nobel.se/physics/laureates/1956/index.html.

transition metal – an element which has only partially filled d orbitals in its electronic structure. Transition metals and the number of electrons in the d orbitals are listed in the Table T.1.

Table T.1 Number of d electrons in a free atom of transition metals.

Groups ↓ Number of electrons →	**1**	**2**	**3**	**4**	**5**	**6**	**7**	**8**	**9**	**10**
3d elements	Sc	Ti	V		Cr,Mn	Fe	Co	Ni		
4d elements	Y	Zr		Nb	Mo,Tc		Ru	Rh		Pd
5d elements	La–Lu	Hf	Ta	W	Re	Os	Ir		Pt	
6d elements	Ac–Lr	Th, Ku								

transmission electron microscopy (TEM) → **electron microscopy**.

transverse acoustic mode → **phonon**.

transverse optical mode → **phonon**.

trefoil knot – the simple closed curve in three-dimensional space shown in Figure T.2. It can be a molecular architecture consisting of a single macrocycle.



Figure T.2 A trefoil knot.

tribo – a prefix meaning pertaining to or resulting from friction.

tribology – the science of interacting material surfaces in relative motion. It is specially focused on the friction and wear properties of the materials and the control of these processes through lubrication. The word tribology derives from the Greek ''tribo'' meaning ''rubbing''.

triboluminescence – luminescence that arises from friction and that usually occurs in crystalline materials.

triclinic lattice – a **Bravais lattice** with a unit cell in which axes are not at right angles and are not equal.

trigonal lattice – a **Bravais lattice** in which three axes of a unit cell are of equal length and the three angles between axes are the same and are not right angles. It is also know as **rhombohedral lattice**.

trimer – a molecule composed of three identical molecular subunits (**monomer**s) linked together.

triplet state – a system of atomic terms (energy levels) with maximum multiplicity 3. Triplet terms occur if the spin quantum number of electrons is unity. It can be formed by two electrons with parallel spins. Two spins add together giving a nonzero total spin.

tRNA – transfer RNA → **RNA**.

truth table → **logic operator**.

Tsuneyuki–Tsukada–Aoki–Matsui potential – the interatomic many-force-field-pair potential in the form $V(r_{ij}) = V_{ij}^{\mathrm{Coulomb}} + f_0(b_i + b_j)\exp[(a_i + a_j - r_{ij})/(b_i + b_j)] - c_i c_j / r_{ij}^6$ in which Coulomb interaction via $V_{ij}^{\mathrm{Coulomb}}$, as well as **Born–Mayer** type repulsion and dispersive interaction are included subsequently. Here r_{ij} is the interatomic distance, and a_i, a_j (effective radius), b_i, b_j (softness parameter), and c_i, c_j are the fitting parameters. The potential has been shown to be effective in **molecular dynamics** simulations for silica polymorphs (α-quartz, α-cristobalite, coesite, stishovite).

First described in: S. Tsuneyuki, M. Tsukada, H. Aoki, Y. Matsui, *First-principles interatomic potential of silica applied to molecular dynamics*, Phys. Rev. Lett. **61**(7), 869–872 (1988).

tunneling – the term referring to a particle transport into and through a classically forbidden region defined by a potential barrier with any energy larger than the total energy of the incident particle. This is illustrated in Figure T.3, where a particle of energy E approaches a rectangular barrier of height $U_0 > E$.

In classical mechanics, such particle has to be completely reflected from the barrier. This is not the case for quantum particles. Quantum mechanically, the motion of a particle around a step-like potential barrier is described by the **Schrödinger equation**, which for the one-dimension case is

$$-\frac{\hbar^2}{2m}\frac{\mathrm{d}^2\psi(x)}{\mathrm{d}x^2} + U(x) = E\psi(x).$$

Expecting the barrier to be rectangular with a finite height U_0 one has

$$U(x) = \begin{cases} 0 & \text{for} \quad x < x_0 \\ U_0 & \text{for} \quad x \geq x_0 \end{cases}$$

In case of $0 < E \leq U_0$ the solution of the Schrödinger equation is

$$\psi(x) = \begin{cases} A\exp(\mathrm{i}k_1 x) + B\exp(-\mathrm{i}k_1 x) & \text{for} \quad x < x_0 \\ U_0 \quad \text{for} \quad x \geq x_0 \end{cases}$$

with $k_1 = (1/\hbar)\sqrt{2mE}$ and $k_2 = (1/\hbar)\sqrt{2m(U_0 - E)}$. As the value and the slope of the wave function $\psi(x)$ must be continuous everywhere in the space, matching at the step $x = x_0$ gives the relations between amplitudes A, B, C, and D

$$A + B = C + D \quad \text{and} \quad k_1(A - B) = k_2(C - D).$$


Step-like potential barrier of height U_0
Step-like potential barrier of infinite height
Rectangular tunnel potential barrier of height U_0
Energy
U_0
E
a
x
Waves
$A\exp(ik_1x)$
$B\exp(-ik_1x)$
$C\exp(ik_2x)$
$D\exp(-ik_2x)$
Wave function $\Psi(x)$
Probability density $|\Psi(x)|^2$
x_0
x_1
x_2

Figure T.3 Interaction of quantum particle having total energy E with potential barriers of finite (U_0) and infinite heights.

Thus, if the amplitudes of the waves on the left, A and B, are known, the amplitudes on the right are

$$C = \frac{1}{2}\left(1 + \frac{k_1}{k_2}\right) A + \frac{1}{2}\left(1 - \frac{k_1}{k_2}\right) B,$$

$$D = \frac{1}{2}\left(1 - \frac{k_1}{k_2}\right) A + \frac{1}{2}\left(1 + \frac{k_1}{k_2}\right) B,$$

which give transmission T and reflection R coefficients in the form

$$T = \frac{4k_1k_2}{(k_1 + k_2)^2} \quad \text{and} \quad R = \left(\frac{k_1 - k_2}{k_1 + k_2}\right)^2 \quad \text{where} \quad R + T = 1.$$

As a result, one can see that the wave $A\exp(ik_1x)$, representing a quantum particle of mass m with energy E, coming to the step-like potential barrier of height U_0, is reflected as the wave $B\exp(-ik_1x)$. It also penetrates the barrier, decaying in the barrier region. The penetration, characterized by the transmission coefficient T, increases as E approaches U_0. The function $|\psi(x)|^2$ shown in Figure T.3 characterizes the probability to find the incident quantum particle. It is oscillating at the low energy side of the barrier and exponentially decreases inside the barrier. On the other hand, if the potential barrier is infinite in height, or at least $U_0/E \gg 1$, there is no penetration into the barrier region. The transmission coefficient becomes zero and the reflection coefficient reaches unity. Thus, perfect reflection takes place with the interference of incident and reflected waves at the left side of the barrier. The interference gives rise to the oscillations of the probability density at the barrier. Both, penetration of quantum particles into a classically forbidden region and oscillating behavior of the probability to find a quantum particle at a potential barrier are particular manifestations of quantum mechanics, which have no analogy in classical mechanics.

More mystery arises when a quantum particle passes over the step-like potential barrier, so $E > U_0$. From the point of view of classical mechanics, no particle reflection can be expected. But quantum mechanically, the reflection coefficient in this case is not absolute zero. As a result, the wavelength $\lambda_1 = h/(2mE)^{1/2}$ representing the quantum particle approaching the barrier is transformed into $\lambda_2 = h/[2m(E - U_0)]^{1/2}$ when the particle crosses the border at $x = x_0$ and moves over the barrier.

Although potential barriers in the form of steps are important to confine electrons within a particular region, barriers of a certain thickness allowing electrons to tunnel through them into another neighboring region are more often used in nanoelectronic devices. Consider electron transport through the rectangular tunnel potential barrier shown in Figure T.3, which has a height U_0 and thickness $a = x_2 - x_1$. A classical particle with total energy $E < U_0$ approaching such a barrier has no chance to pass through it. It will be reflected at the so-called classical turning point. The **turning point** is a point with a coordinate x at the boundary of a potential barrier where the total energy of the particle E equals the potential energy at the barrier $U(x)$. For the classical particle it means that its velocity becomes zero at this point and the particle starts moving in the opposite direction. For the rectangular tunnel barrier the turning points have coordinates (x_1 and x_2) coinciding with the boundary of the barrier.

For a quantum particle, there is a certain nonzero probability to find it, or the wave representing that particle, at the opposite side of the barrier. The probability function remains constant at the right side of the barrier, while at the left, incident, side it oscillates reaching values even lower than in the region after the barrier. The transparency of a symmetric rectangular tunnel barrier is characterized by the transmission coefficient

$$T = \left[1 + \frac{U_0^2}{4E(U_0 - E)} \sin \hbar^2 (ak_2)\right].$$

The reflection coefficient $R = 1 - T$. For many practical cases related to electron tunneling the product ak_2 is large enough to make the term with $\sinh^2(ak_2)$ dominating, thus providing a simplified representation of the transmission through the barrier as

$$T \approx \frac{U_0^2}{4E(U_0 - E)} \exp\left(-\frac{a}{\hbar}\sqrt{2m(U_0 - E)}\right).$$

There is also a useful representation of the rectangular barrier in the form of δ-function barrier. It appears when the height U_0 goes to infinity while the thickness a is reduced to zero, such that the product $S = aU_0$ remains constant. The transmission coefficient of this barrier is

$$T = \left(1 + \frac{2mS^2}{4\hbar^2 E}\right)^{-1}.$$

The tunnel transparency of potential barriers of an arbitrary shape $U(x)$ can be estimated with,

$$T \approx \exp\left(-\frac{2}{\hbar}\int_{x_1}^{x_2} \sqrt{2m(U(x) - E)}\mathrm{d}x\right)$$

where x_1 and x_2 are turning points defined by the condition $U(x_1) = U(x_2) = E$. Figure T.4 shows qualitatively variation of the transmission coefficient for tunnel barriers of different shapes as a function of the energy E of an incident electron weighted to the barrier height U_0.



Figure T.4 Transmission coefficient versus electron energy E reduced by the barrier height U_0 for differently shaped tunnel potential barriers.

Surprisingly, electron waves passing over a symmetric rectangular barrier, so that $E > U_0$, experience non-monotonous, in fact resonance, behavior. The maximum over-the-barrier transmission, corresponding to $T = 1$, occurs only for electrons with particular energies

$$E = U_0 + \frac{\pi^2\hbar^2}{8ma^2}n^2, \quad \text{with} \quad n = 1, 2, 3, \ldots.$$

Thus, a rectangular barrier has no influence on over-the-barrier passing electron waves if their wavelength is $\lambda = a/2, a, 2a, 4a, \ldots$. In other cases, incident electron waves are partially reflected. The over-the-barrier resonance is also seen in other systems, such as microwaves.

Electron tunneling is a rather general phenomenon for solid-state structures. However, there are two specific issues that distinguish tunneling in nanostructures from that in bulk systems. One is the granular nature of the electron charge, which evidences itself in the **single-electron tunneling** phenomenon. The second involves discrete energy levels induced in nanostructures by quantum confinement. Tunneling via energetically equivalent levels occurs with conservation of energy and momentum of electrons representing the **resonant tunneling** phenomenon. Moreover, additional effects arise when spin-polarized electrons participate in tunneling → **tunneling magnetoresistance**. All these phenomena are widely employed in **nanoelectronic** devices.

First described in: M. A. Leontovich and L. I. Mandelshtam, *On the theory of the Schrödinger equation*, Z. Phys. **47**, 131 (1928).

tunneling magnetoresistance effect – external magnetic field dependence of the tunnel current between two differently magnetized **ferromagnetic** layers separated by a thin insulator. Particular magnetization of the ferromagnetic layers is provided by their deposition in a magnetic field. The tunneling process is strongly mediated by spin orientations of the carriers in the electrodes controlled by the ferromagnetic material magnetization. As a general feature, the structure has high resistance when two ferromagnetic layers are magnetically antialigned and the resistance is significantly reduced when they become aligned in an external magnetic field. As in case of the **giant magnetoresistance effect**, the phenomenon is often described in terms of the tunneling junction magnetoresistance.

Typical junctions for spin-polarized tunneling are composed of ferromagnetic layers of Co, CoCr, CoFe, NiFe or other ferromagnetic alloys separated by Al_2O_3, MgO, Ta_2O_5 up to a few nanometers thick. Magnetoresistance of the junctions is a function of the bias, magnetic field and temperature. In the absence of the magnetic field, a tunnel junction, if it is perfect, has nearly constant conductance at low bias, that is in the mV range. At higher voltages, a close to parabolic dependence of the conductance on the applied voltage is observed.

The variation of the magnetoresistance with direction and strength of the magnetic field is illustrated in Figure T.5, where representative experimental data for $CoFe/Al_2O_3/Co$ junction, Co and CoFe films are depicted. Two curves shown for each structure correspond to two opposite starting directions of the magnetic field applied, namely black for starting from "+" and gray for starting from "−". At a starting high field, the junction magnetoresistance is low, because directions of magnetization of both ferromagnetic electrodes and consequently spin polarization there are aligned. It begins to increase as the strength of the magnetic field decreases toward zero. Upon reversing the field direction, the magnetoresistance rapidly rises, showing a peak. In the reversed magnetic field the magnetization of the electrode with a lower coercive force aligns itself in the new direction, while the second electrode with a higher coercive force remains magnetized in the starting field direction. The magnetization of the two electrodes appears to be antiparallel to each other. Note that the coercive force of a ferromagnetic film is easily controlled by the deposition conditions: the presence of a magnetic field, substrate temperature, a nucleating layer, thickness of the film, and so on.



Figure T.5 Magnetoresistance of two ferromagnetic thin films and their tunnel junction as a function of applied magnetic field at room temperature. The arrows indicate directions of magnetization in the films. After J. S. Moodera, L. R. Kinder, *Ferromagnetic-insulator-ferromagnetic tunneling: spin-dependent tunneling and large magnetoresistance in trilayer junctions*, J. Appl. Phys. **79**(8), 4724–4729 (1996).

With further increase in the field it becomes strong enough to align the magnetization of the second ferromagnetic electrode in the new field direction, resulting in parallel orientation. The magnetoresistance drops to its starting value. At high fields in either direction, the magnetizations of both electrodes are saturated and parallel to each other. When the magnetizations are parallel, the tunneling probability is the highest and tunneling current reaches its maximum, thereby yielding low junction resistance. In the antiparallel configuration, the tunneling probability and the current are lowest, resulting in higher resistance.

The model for spin-mediated tunneling between two differently magnetized ferromagnetic electrodes separated by a thin insulator assumes that spin is conserved in tunneling and tunnel current is dependent on the density of states of the two electrodes. Because of the uneven spin distribution of conduction electrons at the Fermi level in ferromagnetics, one can expect the tunneling probability to be dependent on the relative magnetization of the ferromagnetic films. The change in the tunnel resistance, which can be considered to be the highest tunneling junction magnetoresistance, is given by

$$\frac{\triangle R}{R} = \frac{R_a - R_P}{R_a} = \frac{2P_1P_2}{1 + P_1P_2}.$$

Here R_p and R_a are the resistances with magnetizations of the electrodes parallel and antiparallel, respectively, and P_1 and P_2 are the conduction electron spin polarizations in the ferromagnetic electrodes. The highest room temperature tunneling junction magnetoresistance at low bias, that is 20–23%, has been experimentally achieved for Al_2O_3 insulating layers.

First described in: P. M. Tedrow, R. Meservey, *Spin-dependent tunneling into ferromagnetic nickel,* Phys. Rev. Lett. **26**(4), 192–195 (1971).

tunneling magnetoresistance nonvolatile memory – a thin-film memory device employed the **tunneling magnetoresistance effect**. It is schematically shown in Figure T.6. The random access memory is formed by two arrays of parallel ferromagnetic lines separated in space by a thin insulating layer and orthogonal in the plane. Each intersection of the lines acts as a magnetic tunnel junction. When the two opposite ferromagnetic regions are magnetically aligned, the tunnel resistance is lower than when they are antialigned. A resistance change of at least about 30% is needed for the memory application.

The high resistance of tunnel junctions precludes the sense-line scheme used in a giant magnetoresistance-based random access memory. Instead, essentially a four-point probe arrangement (two that provide current and two that permit an independent voltage measurement) is attached to every device. Furthermore, the leads can provide a dual service, because pulse currents, which are directed to run above and below rather than through the tunnel junction, can provide the necessary magnetic fields to manipulate the magnetization directions in the ferromagnetic regions. This configuration is similar to the addressing scheme of the **giant magnetoresistance memory**. However, one problem is that such an array is multiply shorted through the elements; that is, the electrical path from an input lead to an output lead can proceed through many elements, not just the one at the intersection. The solution is to place a diode at every intersection so that the current can pass in only one direction, which eliminates alternative paths. It is a technological challenge to fabricate these diodes in an integrated manner with tunnel junction storage elements. Its solution permits the fabrication of an extremely high-density memory.



Figure T.6 Schematic of random access memory constructed of magnetic tunnel junctions.

turbulence – a chaotic motion of a fluid. It usually occurs when the flow rate exceeds a particular threshold limit value that is mainly determined by the viscosity of the fluid.

Turing machine – a mathematical idealization of a computing machine similar in some ways to real computing machines. It is used to define the concept of computability. The machine has a finite set of states S, a finite alphabet of symbols A, and a finite set of instructions I. In addition, it has an external infinitely long memory tape. This is called an S-state, A-symbol Turing machine.

The states s_i correspond to the functioning modes of the machine. The machine is exactly in one of these states at any given time. The symbols in the alphabet serve to encode the information processed by the machine: they are used to code input/output data and to store the intermediate operations. The instructions are associated with the states in S, and they tell the machine what action to perform if it is currently scanning a certain symbol, and what state to go into after performing this action. There is a single halt state s_{halt} (halt, for short) from which no instructions emerge, and this halt state is not counted in the total number of states.

The elements S, A, I are physically arranged in three main components:

1. The tape, which is a doubly infinite tape divided into distinct sections or cells. Each cell can hold only one symbol.
2. A read/write head or cursor, which can read or write a symbol in each tape cell. The read/write head is capable of only three actions: writing on the tape or erasing from the tape only the cell being scanned, changing the internal state, and moving the head one cell to the left or right.
3. A control unit, which is a device that controls the movements of the head according to the current state of the machine and the content of the cell currently scanned by the head.

The operation of a Turing machine is governed by the set of instructions I. These are rules that describe the transition from an initial pair of s_i and a_i to a final pair of s_f and a_f plus the movement of the read/write head.

First described in: A. Turing, *On computable numbers, with an application to the Entscheidungsproblem*, Proc. Lond. Math. Soc. **42**, 230–265 (1936); correction, ibid. **43**, 544–546 (1937).

turning point → **tunneling**.

twin (crystallographic) consists of two crystals of the same composition and structure, in intimate atomic contact with each other and possessing orientations that are related to each other in a special way. The orientations of the two crystals may be related by a reflection in a lattice plane (the twinning plane) common for both crystals, or they may be related by rotation, usually of 180°, about an axis (the twinning axis) common for both crystals. These types are termed reflection twins and rotation twins, respectively. When the crystal is of high symmetry, a twin may be of both types simultaneously. A given twinning plane or axis defines a twin law. There may be several twin laws for one substance.

two-dimensional electron gas (2DEG) – an ensemble of electrons in **quantum films**.

two-dimensional electron gas field effect transistor (TEGFET) → high electron mobility transistor (HEMT).

type I quantum wells → quantum well.

type II quantum wells → quantum well.

type I superconductors → superconductivity.

type II superconductors → superconductivity.

U

From ultraviolet photoelectron spectroscopy (UPS) to Urbach rule

ultraviolet photoelectron spectroscopy (UPS) – the technique for studying electronic states in valence and conduction bands in solids using energy analysis of photoelectrons emitted under illumination of the sample with ultraviolet radiation. The energy of the photons ranges from 10 eV to 50 eV.

Umklapp process – an interaction of three or more waves in a solid, such as lattice waves or electron waves, in which the sum of the wave vectors is not equal to zero but, rather, is equal to a vector in the reciprocal lattice.

unbound state (of an electron in an atom) – a state to which an electron is raised when it is ejected from the atom by a high-energy collision or phonon. The energies of an electron in an unbound state are always positive. They are not quantized and form continuum states of the atom. The alternative is a **bound state**.

uncertainty principle → **Heisenberg's uncertainty principle**.

unitary group – a group of **unitary transformations** on k-dimensional complex vector space.

unitary matrix – a matrix whose inverse is identical with its conjugate transpose.

unitary transform – a linear transform on a vector space, which preserves inner products and norms. Alternatively, it is a linear operator whose adjoint is equal to its inverse.

unit cell – the smallest three-dimensional cell which being translated into three directions reproduces the crystalline lattice of the solid (see Figure U.1).

It is described by six lattice parameters: length of lattice translation vectors $\mathbf{a} = a$, $\mathbf{b} = b$, $\mathbf{c} = c$ and interaxial lattice angles $\mathbf{b} \wedge \mathbf{c} = \alpha$, $\mathbf{a} \wedge \mathbf{c} = \beta$, $\mathbf{a} \wedge \mathbf{b} = \gamma$. The unit cell completely defines the entire lattice.



Figure U.1 Space lattice with the unit cell defined by the vectors **a**, **b** and **c**.

universal ballistic conductance → **ballistic conductance**.

universal conductance fluctuations – the root mean square fluctuations of the conductance in low-dimensional conductors are of the order e^2/h, independently of the size of the average conductance.

Variation of conductance is a result of the phase interference of electron waves in conventional low-dimensional conductors, which are normally long and thin. Impurities or other defects inside such conductors create potential hills around which electron waves must pass. This is schematically illustrated in Figure U.2 for one impurity atom (or other type point defect) disturbing the coherent propagation of electrons.

At low temperatures the material of a conductor is usually degenerate, and only the carriers with **Fermi energy** take part in transport processes. The Fermi energy can be varied either by some potential applied to the gate covering the conductor or by a magnetic field, both of which deplete the conduction band. As a result, the detailed Fermi surface upon which the carriers travel appears to be slightly shifted. It is thus possible for a carrier that moves on one side of the defect (path A) to modify the trajectory so that it travels on the other side of the defect (path B) after the shift of the Fermi energy. The change in the trajectory is equivalent to coupling an **Aharonov–Bohm** loop composed of the A and B arms. As a result, fluctuations of conductance occur in this process. It is quite static in time and depends on the particular configuration of scattering centers in the sample.

In order to observe quantum changes in conductance related to the phase interference of electron waves, the sample must be comparable in size to the



Figure U.2 Electron wave trajectories in the sample around impurity atoms.

phase coherence length, which is controlled by the density of scattering centers in the sample material. As the sample grows larger, the quantum fluctuation of conductance is smoothed out by ensemble averaging.

First described in: B. L. Altshuler, *Fluctuations of residual conductivity in non ordered semiconductors,* Pisma Zh. Exp. Teor. Fiz. **41**(12), 530–533 (1985); P. A. Lee, A. D. Stone, *Universal conductance fluctuations in metals,* Phys. Rev. Lett. **55**(15), 1622–1625 (1985).

unsaturated hydrocarbons → **hydrocarbons**.

up- and down-conversion solar cell – a **solar cell** in which the sun spectrum is converted into a smaller energy range by converting two or more low-energy **photon**s into a high-energy photon or converting one high-energy photon into two or more low energy-photons. Photon shifting can also be used where, by a **luminescence** process, a high-energy photon is converted into a single lower energy photon. Energetically, the latter process is not favorable, but there might still be some gain at solar cell level for industrial cells, which feature a rather poor response for short-wavelength light.

More details in: A. Shalav, B. S. Richards, T. Trupke, K. W. Krämer, H. U. Güdel, *Application of* $NaYF_4{:}Er_{3+}$ *up-converting phosphors for enhanced near-infrared silicon solar cell response,* Appl. Phys. Lett. **86**, 013505 (2005); V. Svrcek, A. Slaoui, J.-C. Muller, *Silicon nanocrystals as light converter for solar cells,* Thin Solid Films **451–452**, 384–388 (2004).

UPS – an acronym for **ultraviolet photoelectron spectroscopy**.

Urbach rule – the exciton absorption $\alpha(\omega)$ for frequencies below the exciton resonance at ω_0 decreases exponentially: $\alpha(\omega) = \alpha_0 \exp[-(\omega_0 - \omega)/\sigma]$.

First described in: F. Urbach, *The long-wavelength edge of photographic sensitivity and of the electronic absorption of solids,* Phys. Rev. **92**(5), 1324–1324 (1953).

V

From vacancy to von Neumann machine

vacancy – a point defect in the form of an unoccupied lattice position in a crystal.

valence band – an uppermost, filled electron energy band in solids. It is most commonly available for conduction of electric current by holes in solids.

van der Pauw configuration (sample) – the four-contact geometry shown in Figure V.1.

It is usually used for measurements of a conductivity of semiconductors.

First described in: L. van der Pauw, *A method of measuring specific resistivity and Hall effect of discs of arbitrary shape,* Philips Res. Rep. **13**(1), 1–9 (1958).



Figure V.1 van der Pauw sample.

van der Waals force – an attractive force between two atoms or nonpolar molecules arising as a result of a fluctuating dipole moment in one molecule that induces a dipole moment in the other whereupon the two dipole moments then interact.

First described in: J. D. van der Waals, *Over de Continuiteit van den Gas-en Vloeistoftoestand (on the continuity of the gas and liquid state)*, (Ph.D. thesis, Leiden, The Netherlands, 1873).

Recognition: in 1910 J. D. van der Waals received the Nobel Prize in Physics for his work on the equation of state for gases and liquids.

See also www.nobel.se/physics/laureates/1910/index.html.

Van Hove singularities – singularities in density of states of electron and phonon bands in solids at points where $|\nabla_k(E)|$ vanishes. These points are known as critical points.

Assuming that $k = 0$ is a critical point in the three-dimensional space, $E(k)$ can be expanded as a function of k about the critical point:

$$E(k) = E(0) + a_1 k_1^2 + a_2 k_2^2 + a_3 k_3^2 + \ldots.$$

The singularities are classified according to the number of negative coefficients a. In three dimensions there are four kinds of Van Hove singularities, labeled as M_0, M_1, M_2, and M_3 critical points. M_0 critical point has no negative as and therefore represents a minimum in the band separation. M_1 and M_2 are known as saddle points, since the plots of their energies versus wavevector resemble a saddle. M_3 critical point represents a maximum in the band separation.

First described in: L. Van Hove, *The occurrence of singularities in the elastic frequency distribution of a crystal*, Phys. Rev. **89**(6), 1189–1193 (1953).

Van Vleck equation shows the temperature dependence of susceptibility. It was obtained using the fact that atoms, ions or molecules are distributed in a magnetic field among various allowed energy levels according to the **Boltzmann distribution** in the form:

$$\chi = N \frac{\sum_i [(E_i')^2/k_B T - 2E_i''] \exp(-E_i/k_B T)}{\sum_i \exp(-E_i/k_B T)},$$

where N is the number of elementary dipoles, and E_i is the energy of a spin level developed into a **Taylor series** as a function of magnetic field as $E = E_i + E_i' H + E_i'' H$.

By the perturbation theory one has that $E_i' =< i|\mu_H|i >$, $E_i'' = \sum_i [| < i|\mu_H|j > |^2/h\nu_{ij}]\ (j \neq i)$, where $h\nu_{ij}$ is the energy interval $(E_i - E_j)$ spanned by the matrix element of the magnetic moment in the direction of the field H. Thus, the susceptibility behaves thus:

1) χ is proportional to $1/T$, if all $|h\nu_{ij}| \ll k_B T$
2) χ is independent of T, if all $|h\nu_{ij}| \gg k_B T$
3) $\chi = A + BT$, if all $|h\nu_{ij}|$ are either $\gg k_B T$ or $\ll k_B T$
4) no simple dependence of χ on T, if $|h\nu_{ij}|$ is comparable with $k_B T$.

The temperature-independent paramagnetic contribution is termed **Van Vleck paramagnetism**. Note that if the susceptibility follows the classical **Curie law** → also **Curie–Weiss law**) then it will display a linear dependence on the reciprocal of the temperature.

First described in: J. H. Van Vleck, *On dielectric constants and magnetic susceptibilities in the new quantum mechanics. Part I. A general proof of the Langevin–Debye formula*, Phys. Rev. **29**(5), 727–744 (1927); J. H. Van Vleck, *On dielectric constants and magnetic susceptibilities in the new quantum mechanics. Part III. Application to dia- and paramagnetism*, Phys. Rev. **31**(4), 587–613 (1928).

More details in: J. H. Van Vleck, *The Theory of Electric and Magnetic Susceptibilities* (Clarendon, Oxford, 1932).

Recognition: in 1977 P. W. Anderson, N. F. Mott and J. H. Van Vleck received the Nobel Prize in Physics for their fundamental theoretical investigations of the electronic structure of magnetic and disordered systems.

See also www.nobel.se/physics/laureates/1977/index.html.

Van Vleck paramagnetism → **Van Vleck equation**.

varactor – a semiconductor diode that exhibits change in capacitance with a change in applied voltage; used as a voltage-variable capacitor.

variance – the square of the standard deviation.

variational method – a method of calculating an upper bound on the lowest energy level of a quantum mechanical system and an approximation for the corresponding wave function. In the integral representing the expectation value of the **Hamiltonian operator**, one substitutes a trial function for the true wave function and varies parameters in the trial function to minimize the integral.

variational principle states that the lowest energy obtained is the closest approximation to the true state of the system. If an arbitrary wave function is used to calculate the energy, then the value calculated is never less than the true energy. The procedure based on this principle is also known in the literature as **Ritz procedure**.

Varshni law – the semiempirical expression describing the temperature dependence of the energy gap in semiconductors in the form $E(T) = E(0) - aT^2/(b + T)$, where a and b are the fitting parameters.

First described in: Y. P. Varshni, *Temperature dependence of the energy gap in semiconductors,* Physica (Amsterdam) **34**, 149–154 (1967).

V-based molecular ring → **molecular nanomagnet**.

VCSEL – an acronym for a **vertical cavity surface emitting laser**.

Vegard's law states that the lattice constant of an intermediate compound is given by linear interpolation between lattice constants of its constituents. It is valid for substitutional solid solutions of atoms with a similar electronic structure and close size. Thus, the lattice constant a of new compound can be calculated as $a(x) = xa_1 + (1 - x)a_2$, where x is the atomic fraction of the substituted atoms, and a_1 and a_2 are the lattice parameters of the virgin compounds between which the new one is formed.

First described in: L. Vegard, *Die Konstitution der Mischkristalle und die Raumfüllung der Atome,* Z. Phys. **5**(1), 17–26 (1921).

Verdet constant → **Faraday effect**.

*First described in:*M. E. Verdet, *Recherches sur les propriétés optiques développées dans les corps transparents par l'action du magnétisme,* Ann. Chim. **41**, 370–412 (1854).

vertical-cavity surface-emitting laser (VCSEL) – a semiconductor laser that has an optical resonator formed by two Bragg reflectors parallel to the surface of the wafer in which it has been fabricated. It is schematically shown in Figure V.2.

The reflectors sandwiching the active light-emitting region are composed of multilayers of semiconductors or dielectrics. Carrier injection is performed through a pair of electrodes in the upper and lower surfaces to excite cylindrical active region between them, which is typically about 10 μm in diameter and 1–3 μm thick. The generated light is emitted normal to the surface.

The simple difference in the cavity orientation results in many advantages of the VCSEL over the edge-emitting lasers in beam characteristic, scalability, optoelectronic design, fabrication and array configurability. In an edge-emitting laser the output beam is highly astigmatic whereas with the laser emission perpendicular to the wafer surface one has a symmetrical beam cross section, with small beam divergence. VCSEL can be fabricated into high-density two-dimensional arrays using low-cost batch processing techniques. Very short cavity lengths dictated by the vertical orientation lead to lasing in a single longitudinal mode. VCSEL mirrors are fabricated during epitaxial growth eliminating cleaving or dry etching processes. However, the reduction in the gain length must be compensated by a high-Q cavity. Materials used to manufacture VCSEL include GaAs, AlGaAs, InGaAsP, and InGaAsN.

VCSELs are indeed useful for monolithic integration to form and two-dimensional densely packed laser arrays. Other advantages over conventional edge-emitting lasers are the feasibility of stable single longitudinal mode operation because of the large mode spacing due to the short optical cavity length, and the attainability of a narrow circular output beam.



Figure V.2 Schematic sketch of vertical-cavity surface-emitting laser.

First described in: H. Soda, K. Iga, C. Kitahara, Y. Suematsu, *GaInAsP/ InP surface emitting injection lasers*, Jpn. J. Appl. Phys. **18**(12), 2329–2330 (1979).

More details in: W. W. Chow, K. D. Choquette, M. H. Crawford, K. L. Lear, G. R. Hadley, *Design, fabrication, and performance of infrared and visible vertical-cavity surface-emitting lasers*, IEEE J. Quantum Electron., **33**(10), 1810–1824 (1997).

Verwey transition – a metal–insulator transition accompanied by a structural phase transition. It takes place in mixed-valent systems. The driving force for the phenomenon is strong electron–electron and electron–lattice interactions in the system resulting in ordering of formal valence states.

The transition is also reflected by anomalies in many other physical properties, such as a jump in the magnetic susceptibility, a sharp peak in the specific heat and a change of the crystal symmetry above a certain temperature.

First described in: E. J. W. Verwey, *Electronic conduction of magnetite* (Fe_3O_4) *and its transition point at low temperatures*, Nature **144**, 327–328 (1939).

vibronic coupling – an interaction between electronic and nuclear vibrational motions in molecules. This type of coupling contradicts the **Born–Oppenheimer approximation** by considering the motion of electrons and nucleus in a molecule to be separable. Many effects, in particular at an intense excitation of molecules, are due to the coupling of electronic and nuclear degrees of freedom.

More details in: G. Fischer, *Vibronic Coupling–The Interaction between the Electronic and Nuclear Motions* (Academic Press, New York, 1984).

vicinal surface – a surface with periodic succession of terraces and steps of monoatomic height obtained by cutting a crystal along a plane making a small angle ($\leq 10^\circ$) with a low index plane. This surface is not an equilibrium shape of the crystal (**Wulff's theorem**).

Villari effect – a change in the magnetic induction within a ferromagnetic substance placed in a magnetic field when the substance is subjected to mechanical stress.

First described in: E. Villari, *Über die Änderungen des magnetischen Moments, welche der Zug und das Hindurchleiten eines galvanischen Stroms in einem Stabe von Stahl oder Eisen hervorbringen*, Ann. Phys. **126**, 87–122 (1865).

virus – a small biological particle which can infect other biological organisms. They are obligate intracellular parasites, meaning that they can only reproduce by invading and taking over other cells as they lack the cellular machinery for self-reproduction. The name virus usually refers to those particles which infect **eukaryote**s, these being multi-celled organisms and many single-celled organisms, whilst the term **bacteriophage** or **phage** is used to describe those infecting **prokaryote**s (bacteria and bacteria-like organisms). Typically these particles carry a small amount of nucleic acid (either **DNA** or **RNA**) surrounded by some form of protective coat consisting of **protein** or protein and **lipid**.

First described by: The term virus was introduced by M. J. Beijerinck in 1898. M. J. Beijerinck, *Über ein Contagium vivum fluidum als Ursache der Fleckenkrankheit der Tabakblätter*, Verh. Kon. Akad. Wetensch. **65**, 3–21 (1898).

Voigt configuration – the term used to indicate a particular orientation of a **quantum film** structure with respect to the magnetic field applied, that is when the field direction is parallel to the film plane. The alternative orientation is labeled as a **Faraday configuration**.

Voigt effect – double refraction of light passing through a substance placed in a magnetic field perpendicular to the light propagation.

First described in: W. Voigt, *Weiteres zur Theorie des Zeemaneffektes*, Gött. Nachr. (1898) and Ann. Phys. **67**, 352–364 (1899).

Volmer–Weber growth mode (of thin films) – droplet (island) formation during thin film deposition as illustrated in Figure V.3.

It appears when the deposited atoms are more strongly bound to each other than they are to the substrate.

First described in: M. Volmer, E. Weber, *Keimbildung in übersättigten Gebilden*, Z. Phys. Chem. **119**, 277–301 (1926).



Figure V.3 Volmer–Weber growth mode during thin film deposition.

von Neumann machine – a principle of computing automation based on the sequential execution of the programs registered in the memory of the computer. A computer realizing this principle has to be composed of two main components, the processor and the memory.

The processor is the active part of the computer in which the information contained in the programs is processed step by step. It is in turn divided into three main parts:

1. Control unit, which is the unit that controls all the parts of the computer in order to carry out all the operations requested by other parts, such as extracting data from the memory, executing and interpreting instructions, and so on.

2. Register, a very fast memory unit inside the processor, which contains that part of the data currently being processed.
3. Arithmetic and logic unit, which is the unit devoted to the actual computations such as sums, multiplications, logic operations, and so on, executed on the data supplied by the registers or memory upon demand by the control unit.

The memory is the part of the computer devoted to the storage of the data and instructions to be processed. It is divided into individual cells, which are accessible by means of a number called the address.

The functioning of the machine is cyclic. One of these cycles contains the following operations: the control unit reads one program instruction from the memory, which is executed after being decoded. Depending on the type of instruction, a piece of data can either be read from or written into the memory, or an instruction can be executed. In the next cycle to be performed, the control unit reads another program instruction, which is precisely next in the memory to the one processed in the previous cycle. The simplicity of this sequentially operating model is advantageous for many purposes because it facilitates the design of machines and programs.

First described in: J. von Neumann, *The principles of large scale computing machines* (1946); reprinted in: Ann. Hist. Comput. **3**(3), 263–273 (1981).

W

From Waidner–Burgess standard to Wyckoff notation

Waidner–Burgess standard – a standard of luminous intensity evaluated as the luminous intensity of 1 cm^2 of a black body at the melting point of platinum.

First described in: C. W. Waidner, G. K. Burgess, *Note on the primary standard of light*, Elec. World **52**, 625 (1908).

wall-in-plug efficiency → **quantum efficiency**.

Walsh functions – the complete system of orthogonal functions defined as: $f_0(x) = 1, f_n(x) = f_{n_1}(x) f_{n_2}(x) \ldots f_{n_q}(x)$ for $n = 2^{n^1} + 2^{n^2} + \ldots + 2^{n^q}$, where the non-negative integers n_i are uniquely defined by the condition $n_{i+1} < n_i$.

First described in: J. L. Walsh, *A closed set of normal orthogonal functions*, Am. J. Math. **55**(1), 5–24 (1923).

Wang–Chan–Ho potential – the interatomic pair potential for a given configuration of N atoms $\{r_1, r_2, \ldots, r_N\}$, expressing the total potential energy (per atom) of the system as $E_{tot}\{r_1, \ldots, r_N\} = E_{bs}\{r_1, \ldots, r_N\} + U\{r_1, \ldots, r_N\}$, where $E_{bs} = N^{-1} \sum_{j=1}^{N} E_j$ is the "band-structure" energy (per atom) consisting of the sum of the eigenvalues E_j for the occupied part of the electronic band structure; $U\{r_1, \ldots, r_N\} = (1/2N) \sum_{i,j=1, j \neq i}^{N} V(r_{ij})$ is a short-ranged two-body potential representing the sum of ion–ion repulsion and the correction to the double counting of the electron–electron interaction in the band-structure energy E_{bs}.

First described in: C. Z. Wang, C. T. Chan, K. M. Ho, *Empirical tight-binding force model for molecular-dynamics simulation of Si*, Phys. Rev. B **39**(12), 8586–8592 (1988).

Wannier equation describes the relative motion of an electron and a hole interacting via the attractive **Coulomb potential** $V(r)$:

$$-\left[\frac{\hbar^2 \nabla^2}{2m_r} + V(r)\right] \psi_\nu(\mathbf{r}) = E_\nu \psi_\nu(\mathbf{r}),$$

where one uses the inverse reduced mass $1/m_r = 1/m_e + 1/m_h$ with m_e and m_h to be masses of the electron in the conduction band and hole in the valence band, respectively. It has the form of a two-particle **Schrödinger equation**.

Wannier excitation – the excitation of electron–hole pairs with a distance between electron and hole, which is the exciton Bohr radius, larger than the length of the lattice **unit cell**. Such excited pairs are called **Wannier excitons**. These are typical for most $\mathrm{A^{II}B^{VI}}$, $\mathrm{A^{III}B^{V}}$ and group IV semiconductors. An alternative case is represented by **Frenkel excitation** and **Frenkel excitons**.

Wannier excitons → **Wannier excitation.**

Wannier functions – Fourier transforms of the **Bloch functions** $\psi_{nk}(\mathbf{r})$ in the form $W_n(\mathbf{r}, \mathbf{R}_i) = N^{-1/2} \sum_{\mathbf{k}} \exp(-i\mathbf{k} \cdot \mathbf{R})\psi_{nk}(\mathbf{r})$. For a crystal, N is the number of unit cells in the crystal, $\mathbf{R}_i$ is the lattice vector, and n is the band index. The wave vector $\mathbf{k}$ covers the first **Brillouin zone**. While Bloch functions are indexed by the wave vectors in reciprocal lattice space, Wannier functions are indexed by lattice vectors in real space. Bloch functions are convenient for representing extended states in solids and Wannier functions are more appropriate for localized states.

More details in: G. Wannier, *Elements of Solid State Theory* (Cambridge University Press, Cambridge, 1959).

Wannier–Mott exciton – an **exciton** with the excitation energy spread over a large number of lattice cells. It can be visualized as a correction to the transition energy between valence and conduction band due to the interaction potential between the extra electron in the conduction band and the hole in the valence band. The energy of the bound state will be lower that the transition energy by $E_{ex} = (e^2/\epsilon)/2a_0^*$, where ϵ is the dielectric constant of the crystal material and $a_0^* = \epsilon(m/m^*)a_B$ is the Bohr radius of the exciton, m and m^* being the electron and the reduced effective mass respectively and a_B the electron Bohr radius. This description is expected to be particularly convenient for crystals with a high dielectric constant and consequently weak electron–hole interaction.

In nanostructures a characteristic size effect is the confinement of the Mott–Wannier exciton, where there is an interesting interplay between the attractive electron–hole interaction and the boundary repulsion.

First described in: G. H. Wannier, *The structure of electronic excitation levels in insulating crystals*, Phys. Rev. **52**(3), 191–197 (1937); N. F. Mott, *Conduction in polar crystals: II. The conduction band and ultra-violet absorption of alkali-halide crystals*, Trans. Faraday Soc. **34**, 500–506 (1938).

More details in: D. L. Dexter, R. S. Knox, *Excitons* (Wiley, New York, 1965).

watched-pot effect → **Zeno paradox**.

Watson–Crick base pairs → **DNA.**

Watson–Crick double-helix model of DNA → **DNA.**

wave equation describes the wave ψ traveling with velocity v:

$$\nabla^2\psi = \frac{1}{v^2}\frac{\partial^2\psi}{\partial t^2}.$$

wave function has been introduced in order to describe the position of a quantum particle, which is distributed through space like a wave, in place of the trajectory.

waveguide – a device or structured material designed to confine and direct electromagnetic waves in a direction determined by its physical boundaries.

wavelet – a waveform-like function with a fast tail decay, oscillatory and localized. Such functions comprise the family of translations and dilatations of a single function. Wavelets are used to transform a signal into another representation that carries the information in a more useful form.

More details in: Y. Mayer, *Wavelets and Operators* (Cambridge University Press, Cambridge, 1992).

wavelet signal processing – the transform of signals using a single function $w(t)$ localized both in time and frequency: $F(m,n) = (1/\sqrt{a}) \int w^*[(t-n)/m] f(t)dt$, in contrast to traditional signal processing based on **Fourier transform** analysis, where the signal is decomposed into complex sinusoidal basis functions localized in time.

The function $w(t)$ can be thought of as a band-pass filter. From one side, the fine temporal analysis is performed using high-frequency contracted versions of the **wavelet**. On the other side, the fine frequency analysis is made using dilated versions of the wavelet. The localization in both time and frequency domains is one of the main advantages of wavelet applications, together with the existence of fast discrete wavelet transform algorithms that render the wavelet method particularly suitable for multiresolution signal decomposition. This approach is different from the traditional signal processing based on Fourier transform analysis, where the signal is decomposed into complex sinusoidal basis functions localized in time.

First described in: I. Daubechies, *Orthonormal bases of compactly supported wavelets*, Commun. Pure Appl. Math. **41**(7), 909–996 (1988); S. Mallat, *A theory for multiresolution signal decomposition: the wavelet representation*, IEEE Trans. On Pattern analysis and Machine Intelligence **11**, 674–693 (1989).

More details in: I. Daubechies, S. Mallat, A. S. Willshy (editors), *Special Issue on Wavelet Transforms*, IEEE Trans. Inform. Theory, **38**(2), part II (1992).

wavelet transform = **wavelet signal processing.**

wave number – the number of waves per unit length. It is the reciprocal of the wavelength: $k = 1/\lambda = \nu/c$, ν is the frequency and c is the velocity of the wave propagation.

wave packet – a wave restricted to a finite space by an envelope. It is illustrated in Figure W.1.

The **wavelets** inside the packet move along at the phase velocity $v_{ph} = \omega/k = \hbar k/2m = p/2m$, while the envelope moves at the **group velocity** $v_{gr} = d\omega/dk = \hbar k/m = p/m$, where ω is the circular frequency of the wave representing the particle, k is the wave number, m is the mass of the particle described as a wave, and p is the particle momentum.

If the packet represents a particle, for instance an electron, one is usually interested in the behavior of the **wave function** as a whole rather than its internal motion. The group velocity is often the appropriate one, and it is a relief that this agrees with the classical result.



Figure W.1 A wave packet.

wave plate – an optical element having two principal axes, slow and fast, that resolve an incident polarized beam into two mutually perpendicular polarized beams. The emerging beam recombines to form a particular single polarized beam. Wave plates produce full-, half- and quarter-wave retardations. Also known as a retardation plate.

wave train – a continuous group of waves that persists for a short time only.

weak localization – a set of electronic phenomena in solids characterized by weak (logarithmic) decrease of the conductivity to zero at low temperatures.

Weiss oscillations – the magnetoresistance oscillations in a two-dimensional electron gas with a lateral periodic modulation in one direction. The oscillations are periodic in B^{-1}. The effect results from an oscillatory dependence of the bandwidth of the modulation-broadened **Landau levels** of the two-dimensional electron system on the band index leading in high-mobility samples to a strongly anisotropic oscillating contribution to the conductivity tensor. The oscillations, periodic in B^{-1}, reflect the commensurability of cyclotron diameter at the **Fermi energy** and modulation period.

First described in: D. Weiss, K. v. Klitzing, K. Ploog, G. Weimann, *Magnetoresistance oscillations in a two dimensional electron gas induced by a submicrometer periodic* *potential,* Europhys. Lett. **8**(2), 179–184 (1989); R. R. Gerhards, D. Weiss, K. v. Klitzing, *Novel magnetoresistance oscillations in a periodically modulated two-dimensional electron gas,* Phys. Rev. Lett. **62**(10), 1173–1176 (1989).

Weiss zone law → **zone law of Weiss**.

Wentzel–Kramers–Brillouin (WKB) approximation supposes slow variation of coefficients α and β when one solves the differential equation

$$\frac{\mathrm{d}}{\mathrm{d}x}\left(\alpha\frac{\mathrm{d}\psi}{\mathrm{d}x}\right)+\alpha\beta^2\psi=0.$$

If α and β^2 are real functions of x, the two independent approximate solutions are

$$\psi=A(\alpha\beta)^{-1/2}\exp\left(\pm\mathrm{i}\int_0^x\beta(x')\mathrm{d}x'\right),$$

where A is a constant. These solutions are good when α and β vary by only a small fraction of themselves in the interval $|\beta^{-1}|$. They break down therefore at values of x for which α or β becomes zero. However, solutions valid at some distance on either side of such points can be correctly matched.

With $\alpha=\hbar^2/2m$ and $\beta=[(E-V)2m/\hbar^2]^{1/2}$ the above equation becomes the one-dimensional **Schrödinger equation** for the motion of a particle of mass m with energy E at the potential barrier of height V. If $(E-V)<0$ between the points x_1 and x_2 (**turning points**), the particle cannot pass through this region from the classical point of view. Meanwhile, wave mechanics allows it to tunnel through such potential barriers. The transition probability obtained within the WKB approximation is $(1+\exp 2K)^{-1}$ with $K=\int_{x_1}^{x_2}[(v-e)2m/\hbar^2]^{1/2}\mathrm{d}x$, which is the most frequently referred result of the approximation.

First described in: G. Wentzel, *Eine Schwierigkeit für die Theorie des Kreiselelektrons,* Z. Phys. **37**(12), 911–915 (1926); H. A. Kramers, *Wellenmechanik und halbzahlige Quantisierung,* Z. Phys. **39**(10/11), 828–840 (1926); L. N. Brillouin, *La mécanique ondulatoire de Schrödinger; une méthode générale de résolution par approximations successives,* C. R. **183**, 24–27; L. N. Brillouin, *Sur un type général de problèmes, permettant la sèparation des variables dans la mécanique ondulatoire de Schrödinger,* C. R. **183**, 270–271 (1926).

Whittaker–Shannon theorem states that, when the sampling period in a recorded sample hologram is matched to the object spectrum, the resulting image does not suffer any loss of information content.

Wiedemann additivity law states that the mass (or specific) magnetic susceptibility of a mixture or solution components is the sum of the proportionate (by weight fraction) susceptibilities of each component in the mixture.

Wiedemann–Franz law → **Wiedemann–Franz–Lorenz law.**

Wiedemann–Franz–Lorenz law states that the ratio of thermal (χ) to electrical (σ) conductivity at room temperature is the same for all metals, which is the **Wiedemann–Franz law**. Lorenz extended the law showing that this ratio is proportional to the absolute temperature, so that $\chi/(\sigma T)$ is a constant independent of temperature. This constant is called the **Lorenz number**. Within the **Drude theory** of a gas of free electrons it has been shown that $\chi/(\sigma T) = 3(k_B/e)^2$. Meanwhile, assuming that only the electrons at the top of the **Fermi distribution** (over the energy range where the distribution function falls to zero) contribute to the electrical and thermal properties this relation is modified to $\chi/(\sigma T) = \pi^2/3(k_B/e)^2$.

First described in: G. Wiedemann, R. Franz, *Über die Wärme–Leitungsfähigkeit der Metalle,* Ann. Phys. **89**, 497–531 (1853).

Wien's displacement law states that the spectral emittance of a heated body has its maximum at the wavelength $\lambda_{\max} = A/T$, where A is a constant, and T is the absolute temperature.

First described in: W. Wien, *Die obere Grenzen der Wellenlängen, welche in der Wärmestrahlung fester Körper vorkommen können; Folgerungen aus dem zweiten Hauptsatz der Wärmetheorie,* Ann. Phys. **49**, 633–637 (1893).

Wien's formula → **Wien's law states.**

Wien's law states that energy density per unit frequency interval for the light emitted by a heated body is defined as $w_\nu = A\nu^3 \exp(-B\nu/T)$, where A and B are constants, ν is the light frequency, and T is the absolute temperature. It is called **Wien's formula** and in fact appears to be the limiting case of Planck's radiation formula for high frequencies.

First described in: W. Wien, *Über die Energievertheilung im Emissionsspektrum eines schwarzen Körpers*, Ann. Phys. **58**, 662–669 (1896).

Recognition: in 1911 W. Wien received the Nobel Prize in Physics for his discoveries regarding the laws governing the radiation of heat.

See also www.nobel.se/physics/laureates/1911/index.html.

Wigner coefficients → **Clebsch-Gordan coefficients**.

Wigner crystal – a periodic spatial arrangement of electrons in matter appearing when a low-density electron liquid solidifies at low temperatures. The periodic structure is formed so that the energy due to mutual Coulomb repulsion is reduced. A two-dimensional Wigner crystal structure is experimentally observed above the surface of liquid helium, in a microchannel capillary filled with liquid helium, and at the interface of semiconductor heterostructures. When a small electric field is applied to a Wigner crystal, all electrons act in concert, driving the crystal with the electric field. Conductivity resonance and wave emission phenomena are typical for the system. The melting point of Wigner solids in liquid helium is around 0.5 K.

The Wigner crystals observed in semiconductors and on liquid helium have distinctive properties due to the difference in electron concentration in each system.

At the interface of a semiconductor heterostructure, there is typically a high concentration of about 10^{12} electrons cm^{-2}. To create a crystal, one needs to squeeze the in-plane wavefunction of each electron, for example by applying a strong magnetic field perpendicular to the interface. As an interface of a semiconductor heterostructure is not free of defects, at least one electron localized by a defect can bind the whole crystal. A small electric field applied to the heterostructure will only deform this pinned Wigner solid, rather than produce an electric current. Thus, Wigner crystallization forces the interface to behave like an insulator.

Peculiarities of Wigner crystallization and properties of the crystals formed are under investigation, keeping in mind their prospects for quantum computations and other applications for information processing.

First described in: E. Wigner, *On the interaction of electrons in metals*, Phys. Rev. **46**(11), 1002–1011 (1934).

Wigner–Eckart theorem states that the matrix element of a tensor operator can be factored into two quantities. The first one is a vector coupling coefficient. The second contains the information about the physical properties of the particular states and operator. It is completely independent of the magnetic quantum numbers.

First described in: E. P. Wigner, *Einige Folgerungen aus der Schrödingerschen Theorie für die Termstrukturen*, Z. Phys. **43**(5–6), 624–652 (1927); C. Eckart, *The application of group theory to the quantum dynamics of Monatomic Systems*, Rev. Mod. Phys. **2**, 305–380 (1930).

Wigner–Dyson distribution originated from the study of matrices with random entries used in nuclear physics. Later, the **random matrix theory** was found to have many other successful applications in different physical systems like molecules and solids, in particular in the field of quantum chaos.

In nuclear physics, the problem was to understand the energy level spectra of complex nuclei when model calculation failed to explain experimental data. E. P. Wigner made the assumption that the **Hamiltonian** of a heavy nucleus had, in the matrix representation, elements that could be assumed to be mutually independent random numbers. In fact, an infinite Hermitian matrix that possessed random matrix elements related to the level widths was involved in the problem. Finally, it was found that if level spacing distribution of a classical integrable system is Poissonian (the probability density of the nearest-neighbor spacing s is given by $P_P(s) = \exp(-s)$), the level statistics in a random system is given by the distribution $P_{WD}(s) = (\pi s/2)\exp(-\pi s^2/4)$.

The transition of the level spacing statistics from the **Poisson distribution** to the Wigner–Dyson distribution is one of the most direct indications of the emergence of quantum chaos.

First described in: E. P. Wigner, *On the statistical distribution of the width and spacings of nuclear resonance levels*, Proc. Camb. Phil. Soc. **47**(4), 790–798 (1951); F. J. Dyson, *Statistical theory of energy levels of complex systems I, II, and III*, J. Math. Phys. **3**(1), 140–175 (1962).

More details in: M. L. Metha, *Random Matrices* (Academic Press, Boston, 1991); A. Crisanti, G. Paladin, A. Vulpiani, *Products of Random Matrices in Statistical Physics* (Springer-Verlag, Berlin, 1993).

Recognition: in 1963 E. P. Wigner received the Nobel Prize in Physics for his contributions to the theory of the atomic nucleus and elementary particles, particularly through the discovery and application of fundamental symmetry principles.

See also www.nobel.se/physics/laureates/1963/index.html.

Wigner rule states that for all possible transfers of energy between two atoms, the one most likely to occur is that in which the total resultant spin remains constant.

Wigner–Seitz method approximates a band structure of a solid. **Wigner–Seitz primitive cells** surrounding atoms in the solid are approximated by spheres. Band solution of the **Schrödinger equation** for one electron are estimated by using the assumption that an electronic wave function is the product of a plane wave function and a function whose gradient has a vanishing radial component at the sphere's surface.

First described in: E. Wigner, F. Seitz, *On the constitution of metallic sodium*, Phys. Rev. **43**(10), 804–810 (1933); E. Wigner, F. Seitz, *On the constitution of metallic sodium. II*, Phys. Rev. **46**(6), 509–524 (1934).

Wigner–Seitz primitive cell displays the entire symmetry of the lattice. For a two-dimensional lattice constructed as illustrated in Figure W.2.

Draw lines to connect a given lattice point to all nearby lattice points and then at the midpoint and normal to these lines, draw new lines or planes. In three dimensions the cell is constructed by drawing perpendicular bisector planes in the reciprocal lattice from the chosen center to the nearest equivalent reciprocal lattice sites. In a crystal, all space may be filled by these cells.

First described in: E. Wigner, F. Seitz, *On the constitution of metallic sodium*, Phys. Rev. **43**(10), 804–810 (1933); E. Wigner, F. Seitz, *On the constitution of metallic sodium. II*, Phys. Rev. **46**(6), 509–524 (1934).



Figure W.2 Construction of the Wigner–Seitz cell for a two-dimensional oblique lattice.

Wigner–Seitz radius is equal to the ratio of the **Coulomb** energy per electron to the **Fermi** energy. It characterizes the strength of the Coulomb interaction between the charge carriers in solids.

First described in: E. Wigner, F. Seitz, *On the constitution of metallic sodium,* Phys. Rev. **43**(10), 804–810 (1933); E. Wigner, F. Seitz, *On the constitution of metallic sodium. II,* Phys. Rev. **46**(6), 509–524 (1934).

Wigner semicircle distribution – a probability function of the form $f(x) = (2/\pi R^2)\sqrt{R^2 - x^2}$, where R is the parameter and x is varied in the interval $[-R, R]$. If $x > R$ or $x < -R, f(x) = 0$. The graph of the function is a semicircle of radius R centered at $(0, 0)$. This distribution arises as the limiting distribution of eigenvalues of many random symmetric matrices as the size of the matrix approaches infinity.

Wilson–Sommerfeld quantization rule provides a method of quantizing action integrals of classical mechanics. A necessary condition is that each generalized coordinate q_k and its conjugate momentum p_k must be a periodic function of times. Then the action integral taken over one cycle of the motion is quantized: $\oint p_k \mathrm{d}q_k = n_k h$.

First described in: W. Wilson, *On the quantum-theory of radiation and line spectra,* Phil. Mag. **29**, 795–802 (1915); A. Sommerfeld, *Zur Quantentheorie der Spektrallinien,* Ann. Phys. (Leipzig) **51**, 1–94, 125–167 (1916).

Wootters–Zurek theorem → **noncloning theorem**.

work function – an energy distance between the **Fermi level** in a solid and the electron energy level in a vacuum.

Wulff's construction → **Wulff's theorem.**

Wulff's theorem formulates the criterion determining the shape of a small crystal: the equilibrium shape of a crystal is that providing a minimum for its surface free energy for a given volume. Total free surface energy of a crystal with i faces is $U = \sum_i \gamma_i S_i$, where γ_i is the surface tension and S_i is the area of the i-th face. Thus, the crystal gets an equilibrium shape if the condition $\mathrm{d}U = 0$ when $\mathrm{d}V = 0$, where V is the volume of the crystal, is satisfied. It is called the **Curie–Wulff condition**.

The theorem links linear dimensions, surface area and the volume of crystals having the equilibrium shape. A geometrical construction based on this theorem is referred to as **Wulff's construction**. It uses the so-called **Herring's** γ **plot**, which is a polar diagram representing surface tension versus angular space orientation. The two-dimensional plot and construction procedure for an anisotropic solid are illustrated in Figure W.3.

At each point of this polar plot (gray curve) construct a plane (represented by the line in two dimensions) perpendicular to the radius vector at that point. The volume, which can be reached from the origin without crossing any of the planes,



Figure W.3 Herring's γ plot and Wulff construction of the equilibrium shape of a crystal.

is geometrically similar to the ultimate equilibrium shape of the crystal, as it minimizes the total free surface energy of the crystal for a fixed volume.

While the proof of the theorem has been given only for the case in which the equilibrium shape is a polyhedron, it is easily generalized to apply to cases in which part or all of the equilibrium shape is bounded by smoothly curved surfaces. Also note that an equilibrium shape is of practical interest only for small crystals. For large crystals a significant alternation in shape can be achieved only by transporting a large number of atoms through a large distance, and the effort needed for this becomes very large in comparison with the minimization of the surface free energy.

First described in: G. Wulff, *Zur Frage der Geschwindigkeit des Wachstums und der Auflösung der Kristallflächen*, Z. Krist. Mineral. **34**, 449–530 (1901) and then extended in: C. Herring, *Some theorems on the free energies of crystal surfaces*, Phys. Rev. **82**(1), 87–93 (1951).

More details in: B. Mutaftschiev, *The Atomic Nature of Crystal Growth* (Springer, Berlin, 2001).

Wyckoff notation – a letter representing a set of symmetry-equivalent positions in a space group. A general point in a **unit cell** of a crystal belonging to any space group has coordinates x, y, z. However, if one or more of the coordinates has a specified value, the number of symmetry-equivalent positions is reduced. Most space groups have several sets of such points, and they are replaced by letters a, b, c, and so on, which are Wyckoff notation.

First described in: R. W. G. Wyckoff, *The Structure of Crystals* (New York, 1924) and *International Tables for X-ray Crystallography* (New York 1935).

X

From XMCD (X-ray magnetic circular dichroism) to XRD (X-ray diffraction)

XMCD – an acronym for **X-ray magnetic circular dichroism**.

XMLD – an acronym for **X-ray magnetic linear dichroism**.

XOR operator → **logic operator**.

XPS – an acronym for **X-ray photoelectron spectroscopy**.

X-ray – electromagnetic radiation with typical photon energies in the range 100 eV–100 keV.

First described in: W. C. Röntgen, *Eine neue Art von Strahlen*, read before the Würzburg Physical and Medical Society in 1895.

Recognition: in 1901 W. C. Röntgen received the first Nobel Prize in Physics in recognition of the extraordinary services he had rendered by the discovery of the remarkable rays subsequently named after him.

See also www.nobel.se/physics/laureates/1901/index.html.

X-ray absorption near-edge structure (XANES) → **extended X-ray absorption fine structure (EXAFS) spectroscopy**

X-ray diffraction (XRD) – a technique to characterize the crystalline nature of a condensed matter. When a beam of monochromatic X-rays is directed at a solid material, diffraction of the X-rays can occur. The relationship between the wavelength of the X-rays (λ), the angle of diffraction (θ), and the distance between each set of atomic planes of the crystal lattice (d) is given by the Bragg equation: $n\lambda = 2d \sin\theta$, where $n = 1, 2, \ldots$ represents the order of diffraction. The interplanar distance is easily derived from this relationship. It is also possible to reconstruct the total molecular structure of a solid by an analysis of the intensity of the X-ray scattering from various crystalline planes.

In the case of thin film analysis, XRD provides:

- estimation of lattice mismatch between the film and the substrate and related strain or stress in the thin film structure by precise lattice constant measurements derived from $2\theta - \theta$ scans
- study of the dislocation quality of the film by rocking curve measurements made by doing a θ scan at a fixed 2θ angle: the width of the rocking curve is inversely proportional to the dislocation density and is therefore used as a gauge of the quality of the film
- study of multilayered heteroepitaxial structures, which manifest themselves as satellite peaks surrounding the main diffraction peak: the heteroepitaxial film thickness and its quality can be deduced from the data
- determination of the thickness, roughness, and density of the film by glancing-incidence X-ray reflectivity measurements (the technique does not require a crystalline film and works even with amorphous materials).

First described in: W. Friedrich, P. Knipping, M. Laue, *Interferenz-Erscheinungen bei Röntgenstrahlen*, Sitzungsber. Bayer. Akad. Wiss. (Math. Phys. Klasse), 303–322 (1912).

Recognition: in 1914 M. Laue received the Nobel Prize in Physics for his discovery of the diffraction of Röntgen rays by crystals.

See also www.nobel.se/physics/laureates/1914/index.html.

X-ray fluorescence spectroscopy – a technique of nondestructive elemental analysis of condensed matter. When a material is bombarded by high-energy photons or electrons, some of the electrons in the atoms of the material are ejected. As the other electrons occupy the vacated levels, quanta of radiation, characteristic of the atom, are emitted. Such quanta in the form of X-rays can be detected by either a wavelength-dispersive or an energy-dispersive X-ray fluorescence spectrometer. Thus, particular atoms can be recognized. The technique makes it possible to detect and analyze all atoms down to boron with a lower limit of detection down to a few parts per million.

X-ray magnetic circular dichroism (XMCD) and X-ray magnetic linear dichroism (XMLD) consist in measuring the absorption cross section near a core level threshold as a function of the circular or linear **polarization** of the photons, respectively. The dependence of the absorption spectra on the direction of polarization is determined by the expectation values of odd-order (for magnetic circular dichroism) or even-order (for magnetic linear dichroism) local multipole magnetic moments of the ground state of the material under investigation. Even-order multipoles can have a non-zero value even in the absence of long-range magnetic order; thus magnetic circular dichroism can yield information about the magnetic structure even in **antiferromagnetic** systems, where no net magnetization is present. Both techniques can be employed with large externally applied magnetic fields and are characterized by the existence of sum rules allowing one to extract ground-state magnetic properties directly from the experimental spectra. The expectation value of the site and orbital projected orbital and spin magnetic moment can be obtained, in a large variety of cases, from the magnetic circular dichroism spectra, while the spin-orbit anisotropy can be estimated from the magnetic linear dichroism spectra. A drawback of magnetic linear dichroism is that dichroism effects in linearly polarized X-ray absorption spectroscopy may be determined not only by local exchange fields and magnetic moments, but also by the local crystal field symmetry, and it could be difficult to separate the magnetic from the non-magnetic contribution to the spectra. Moreover, in magnetic metallic systems the linear signal is much lower (about one order of magnitude) than the circular one.

First described in: B. T. Thole, G. van der Laan, M. Fabrizio, *Magnetic ground-state properties and spectral distributions. I. X-ray-absorption spectra*, Phys. Rev. B **50**(16), 11466–11473 (1994); B. T. Thole, G. van der Laan, *Magnetic ground-state properties and spectral distributions. II. Polarized photoemission*, Phys. Rev. B **50**(16), 11474–11483 (1994).

More details in: M. Finazzi, L. Duó, F. Ciccacci, *Magnetic properties of interfaces and multilayers based on thin antiferromagnetic oxide films*, Surface Sci. Rep. **62**(9), 337–371 (2007).

X-ray photoelectron spectroscopy (XPS) – the technique for studying composition and electronic states in solids using photo-ionization and energy dispersive analysis of photoelectrons emitted under X-ray illumination of the sample. It is based upon single photon in/electron out processes. The energy of the X-ray photons ranges from 100 eV to 10 eV.

In XPS the photon is absorbed by an atom in a molecule or solid, leading to ionization and the emission of a core (inner shell) electron. In contrast to **ultraviolet photoelectron spectroscopy** (UPS), the photon interacts with valence electrons leading to ionization by their removal from atoms or molecules. The kinetic energy distribution of the emitted photoelectrons can be measured using any appropriate electron-energy analyzer, and a photoelectron spectrum can thus be recorded.

Photoionization of an atom A can be considered as $A + h\nu \rightarrow A^+ + e^-$. Energy conservation requires $E(A) + h\nu = E(A^+) + E(e^-)$. Since the energy of the photoelectron (e^-) is present solely as kinetic energy (E_{kin}) this can be rearranged to give the following expression for it: $E_{\mathrm{kin}} = h\nu - (E(A^+) - E(A))$. The final term in brackets, representing the difference in energy between the ionized and neutral atoms, is generally called the binding energy (E_{bin}) of the electron. This then leads to the following commonly quoted equation: $E_{\mathrm{kin}} = h\nu - E_{\mathrm{bin}}$. Note that the binding energies in solids are conventionally measured with respect to the **Fermi level** rather than the vacuum level. This involves a small correction to the equation given above in order to account for the **work function** of the solid.

Each chemical element has a characteristic binding energy associated with each core atomic orbital, that is, each element will give rise to a characteristic set of peaks in the photoelectron spectrum at kinetic energies determined by the photon energy and the respective binding energies. The presence of peaks at particular energies therefore indicates the presence of a specific element in the sample. Furthermore, the intensity of the peaks is related to the concentration of the element within the sampled region. Thus, the technique is capable of yielding a quantitative analysis and is sometimes known by the alternative acronym, **ESCA** that is **electron spectroscopy for chemical analysis**. Its sensitivity is about 1 %, and the depth resolution ranges from 1 to 10 nm.

Recognition: in 1981 K. M. Siegbahn received the Nobel Prize in Physics for his contribution to the development of high-resolution electron spectroscopy.

See also www.nobel.se/physics/laureates/1981/index.html.

XRD – an acronym for a **X-ray diffraction** analysis.

Y

From Yasukawa potential to Yukawa potential

Yasukawa potential – a development of the **Tersoff potential** taking into account the effects of charge transfer in the materials containing ions of different species. For the interatomic distance r_{ij} between atoms i and j charged to q_i and q_j respectively, it is $V(r_{ij}) = \sum_i V_i = \sum_i [E_i^S + 0.5 \sum_{i \neq j} V_{ij}(r_{ij}, q_i, q_j)]$. Here V_i is the potential for the i-th atom. $E_i^S(q_i) = \chi_i q_i + 0.5 J_i q_i^2$ is the self-energy term for the i-th atom with χ_i being its electronegativity (a purely atomic, environment independent quantity), and J_i being the self-Coulomb repulsion (atomic hardness). The interaction potential energy V_{ij} consists of four components: the repulsive energy, the short-range attractive energy, the ionic bond energy, and the van der Waals energy.

The dynamic charge transfer intrinsic to the potential function allows the interface properties to be captured automatically,

First described in: A. Yasukawa, *Using an extended Tersoff interatomic potential to analyze the static-fatigue strength of SiO_2 under atmospheric influence*, JSME Int. J., Ser. A **39**(3), 313–320 (1996).

More details in: J. Yu, S. B. Sinnott, S. R. Phillpot, *Charge optimized many-body potential for the Si/SiO_2 system*, Phys. Rev. B **75**(8), 085311 (2007).

Young's modulus – the ratio of a simple tension stress applied to a material to the resulting strain parallel to the tension.

Yukawa potential describes the strong short-range interaction between **nucleons**: $V(r) = (A/r)\exp(-r/b)$, where r is the distance, and A and b are constants giving measures of the strength and range of the force, respectively.

First described in: H. Yukawa, *Interaction of elementary particles*, Proc. Phys. Math. Soc. Japan **17**, 48–57 (1935).

Recognition: in 1949 H. Yukawa received the Nobel Prize in Physics for his prediction of the existence of mesons on the basis of theoretical work on nuclear forces.

See also www.nobel.se/physics/laureates/1949/index.html.

Z

From Zeeman effect to Zundel ion

Zeeman effect – splitting of energy levels of electrons in an external magnetic field related to different spins of electrons. It is characterized by the so-called Zeeman term $g\mu_B B$ with the free-electron spin **g-factor** of about 2, where B is the induction of the external magnetic field applied.

The normal Zeeman effect is the observation of three lines in the emission spectrum where, in the absence of the field, there was only one. In the **anomalous Zeeman effect** the original line splits into more than three components. It relates to the anomalous magnetic moment of electron spin, and when spin is present the spin and orbital magnetic moments interact with the field in a more complicated way than in its absence.

First described in: P. Zeeman, Verslag. Koninkl. Akad. Wet. Amsterdam **5**, 181–242 (1897); P. Zeeman, *On the influence of magnetism on the nature of the light emitted by a substance*, Phil. Mag. **43**, 226 (1897); P. Zeeman, *The effect of magnetisation on the nature of light emitted by a substance*, Nature **55**, 347 (1897).

Recognition: in 1902 P. Zeeman received the Nobel Prize in Physics shared with H. A. Lorentz in recognition of the extraordinary service they rendered by their researches into the influence of magnetism upon radiation phenomena.

See also www.nobel.se/physics/laureates/1902/index.html.

Zener double exchange occurs when the two isolated magnetic atoms have a different number of electrons in the magnetic shell and hopping through the intermediate nonmagnetic atom involves magnetic-shell electrons. The double exchange couples magnetic moments ferromagnetically. Parallel spin alignment is favored because it increases the hopping probability and therefore decreases the kinetic energy of spin-polarized electrons. An example of double exchange is $A^{III}B^{V}$ semiconductors doped with Mn, in which Mn acceptor states form an impurity band with a mixed spd character. In these systems electrical conduction and Mn–Mn exchange coupling are both realized through hopping within an impurity band.

First described in: C. Zener, *Interaction between the d-shells in the transition metals. II. Ferromagnetic compounds of manganese with perovskite structure*, Phys. Rev. **82**(3), 403–405 (1951).

Zener effect – interband tunneling, in which electrons tunnel from one band to another through the forbidden energy gap of the solid. The presence of an external electric field in a periodic lattice potential causes transitions between the allowed energy bands in the crystal.

First described in: C. Zener, *A theory of the electrical breakdown of solid dielectrics,* Proc. R. Soc. A **145**, 523–529 (1934).

Zener exchange or indirect exchange interaction assumes that the interaction between the incomplete d shells of transition elements is insufficient to disrupt the coupling between the d electrons in the same shells, and that the exchange interaction between adjacent d shells always has the same sign irrespective of distance of separation. The direct interaction between adjacent d shells then invariably leads to a tendency for an **antiferromagnetic** alignment of d spins.

The spin coupling between the incomplete d shells and the conduction electrons leads to a tendency for a ferromagnetic alignment of d spins. The occurrence of ferromagnetism and antiferromagnetism in the body-centered cubic structure of the transition metals, as well as more complex lattices of certain alloys, is readily interpreted in a straightforward manner.

First described in: C. Zener, *Interaction between the d shells in the transition metals,* Phys. Rev. **81**(3), 440–444 (1951).

Zeno paradox – motion is impossible because before reaching a goal one has to get halfway there. Before that, one had to get halfway to the midpoint, and so on

zeolite – a crystalline Al–O–Si material with regularly arranged cages of about 1 nm size. It contains some very closely held water, which can be expelled by heat and reabsoarbed from a moist atmosphere without affecting the crystalline structure of the mineral.

zepto- – a decimal prefix representing 10^{-21}, abbreviated z.

zinc blende structure can be considered as the **diamond structure** in which two interpenetrating **face-centered cubic** lattices contain different atoms. The compound ZnS gives its name to this type of lattice. Other materials crystallizing with the same lattice are $A^{III}B^{V}$ compounds.

zitterbewegung – a theoretical helical or circular motion of elementary particles, in particular **electrons**, which is responsible for producing their **spin** and magnetic moment. It comes as a result of the analysis of the **wave packet** solutions of the **Dirac equation** for **relativistic** electrons in free space. An **interference** between positive and negative energy states produces what appears to be a fluctuation (at the speed of light) of the position of an electron around the median, with a circular frequency of $2mc^2/\hbar$, or approximately 1.6×10^{21} Hz. This peculiar oscillation happens because the velocity is not a constant of motion even in the absence of any potential and has a fluctuating component, while the momentum commutes with the Hamiltonian.

First described in: E. Schrödinger, *Über die kräftefreie Bewegung in der relativistischen Quantenmechanik*, Berliner Ber., pp. 418–428 (1930); *Zur Quantendynamik des Elektrons*, Berliner Ber., 63–72 (1931).

More details in: J. J. Sakurai, *Advanced Quantum Mechanics* (Addison Wesley, Reading, 1967).

zone law of Weiss states that the condition for a crystal face (hkl) to lie in the zone $[UVW]$ is $Uh + Vk + Wl = 0$.

First described in: C. S. Weiss, *De Indagando Formarum Crystallinarum Charactere Geometrico Principali* (Tauchnitz, Leipzig 1809).

Zundel ion – the smallest **protonated water cluster** $H_5O_2^+$.

First described in: G. Zundel, H. Metzger, *Energiebänder der tunnelnden Überschuss Protonen in flüssigen Säuren - eine IR-spektroskopische Untersuchung der Natur der Gruppierungen $H_5O_2^+$*, Z. Phys. Chem. **58**, 225–245 (1968).

A list and a presentation of Scientific Journals which contain the stem *N*ano in their title

One measure of the emergence of new fields of science and technology is the growth of the literature dedicated to the new disciplines. Nanoscience and nanotechnology have, in the last years, witnessed not only an impressive growth in the number of relevant classical scientific journals which have devoted, more and more, a consistent part of their published papers to ''nano''-related researches, but also in the number of entirely new journals, which contain the stem ''nano'' in their title. Here a list and a short presentation of these journals is presented. Inevitably, we will have omitted and forgotten some title, and new titles will appear in the coming years, confirming the broad and interdisciplinary nature of nanoscience and nanotechnology.

More details in: for the role of Journals in defining a new research field see C. G. Mainley, T. S. Welsh, *Publishing patterns and core journals of the ''Nano'' research front*, Proceedings of the SBA Conference 2005; L. Leydesdorff, P. Zhou, *Nanotechnology as a field of science: Its delineation in terms of journals and patents*, Scientometrics **70**, 693–713 (2007).

ACS Nano is an international forum for comprehensive articles on synthesis, assembly, characterization, theory, and simulation of nanostructures, nanobiotechnology, nanofabrication, methods and tools for nanoscience and nanotechnology, and self- and directed-assembly. The journal serves researchers at the interfaces of chemistry, biology, materials science, physics, and engineering.

Started in 2007, and published in 5 issues per year.

More details in: //pubs.acs.org.

Current Nanoscience publishes authoritative reviews and original research reports, written by experts in the field on all the most recent advances in nanoscience and nanotechnology. All aspects of the field are represented including nano- structures, synthesis, properties, assembly and devices. Applications of nanoscience in biotechnology, medicine, pharmaceuticals, physics, material science and electronics are also covered.

Started in 2005, and published in 4 issues per year.

More details in: www.bentham.org.

Fullerenes, Nanotubes, and Carbon Nanostructures – an international and interdisciplinary forum aimed at publishing peer-reviewed research of original work in all areas of fullerene research. Publishing high quality papers from all fields of scientific inquiry related to fullerenes, the journal intends to provide a means of communication between researchers who are interested in fundamental and applied fullerene science issues.

Started in 1993, and published in 6 issues per year.

More details in: www.tandf.co.uk.

IEEE Proceedings Nanobiotechnology covers all aspects of research and emerging technologies related to the convergence of nanotechnology with biotechnology, especially those aspects relating to the interactions between biomolecules and biomolecular assemblies with electronic structures or materials.

Started in 2003, and published in 6 issues per year.

More details in: //ieeexplore.ieee.org.

IEEE Transactions on NanoBioscience – this transaction reports on original, innovative and interdisciplinary work on all aspects of molecular systems, cellular systems, and tissues - including molecular electronics. The journal accepts basic and applied papers dealing both with engineering, physics, chemistry and computer science and with biology and medicine with respect to bio-molecules and cells.

Started in 2002, and published in 4 issues per year.

More details in: //ieeexplore.ieee.org.

IEEE Transactions on Nanotechnology – this transaction publishes novel and important results in engineering at the nanoscale. It focuses on nanoscale devices, systems, materials and applications, and on their underlying science. It is an interdisciplinary journal that covers all areas of nanotechnology.

Started in 2002, and published in 6 issues per year.

More details in: //ieeexplore.ieee.org.

IET Nanobiotechnology covers all aspects of research and emerging technologies related to the convergence of nanotechnology with biotechnology, especially those aspects relating to the interactions between biomolecules and biomolecular assemblies with electronic structures or materials.

Started in 2007, and published in 6 issues per year.

More details in: //ieeexplore.ieee.org.

International Journal of Nano and Biomaterials aims at promoting and coordinating developments in the field of nano and biomaterials. The international dimension is emphasized in order to meet the latest needs of accelerating theoretical knowledge and practical verification of new technologies and products.

Started in 2008, and published in 4 issues per year.

More details in: www.inderscience.com.

International Journal of Nanomanufacturing – the objectives of this journal are to establish an effective channel of communication on the latest developments in micro- and nanomanufacturing science, processes, technology and applications between engineers, scientists, industry, policy makers, academic and research institutions, and persons concerned with any aspect of nanomanufacturing. The interdisciplinary nature of nanomanufacturing will serve to break down cultural, international and academic barriers to meet the needs of accelerating technological developments in the international community for a global change.

Started in 2006, and published in 6 issues per year.

More details in: www.inderscience.com.

International Journal of Nanomedicine – an international, peer-reviewed journal focusing on the application of nanotechnology in diagnostics, therapeutics, and drug delivery systems throughout the biomedical field. Reflecting the growing activity in this emerging specialty, the aim of this journal is to highlight research and development leading to potential clinical applications in the prevention and treatment of disease.

Started in 2006, and published in 4 issues per year.

More details in: //dovepress.com.

International Journal of Nanoparticles focuses on the chemical, physical and biological phenomena and processes associated with nanoparticles and nanostructures ranging from molecular size to 100 nm which exhibit improved properties or have novel applications due to their size. It will include aspects of submicron nanoparticles in special cases.

Started in 2008, and published in 4 issues per year.

More details in: www.inderscience.com.

International Journal of Nanoscience – this inter-disciplinary, internationally reviewed research journal covers all aspects of nanometer scale science and technology. Articles in any contemporary topical areas are sought, from basic science of nanoscale physics and chemistry to applications in nanodevices, quantum engineering and quantum computing.

Started in 2002, and published in 6 issues per year.

More details in: www.worldscinet.com.

International Journal of Nanoscience and Nanotechnology is published by the Iranian Nanotechnology Society and is devoted to original scientific papers in the broad area of nanotechnology.

Started in 2007, and published in 4 issues per year.

More details in: www.nanosociety.ir.

International Journal of Nanotechnology offers a multidisciplinary source of information in all subjects and topics related to Nanotechnology, with fundamental, technological, as well as societal and educational perspectives.

Started in 2004, and published in 12 issues per year.

More details in: www.inderscience.com.

Internet Journal of Nanotechnology is devoted to the electronic publication of original high-quality medical articles on the Internet to distribute knowledge and research results.

Started in 2007, and published in 2 issues per year.

More details in: www.ispub.com.

Journal of Biomedical Nanotechnology – nanotechnology, dealing with functional structures and materials smaller than 100 nm, is emerging as a truly interdisciplinary research area spanning several traditional scientific disciplines. In keeping with the growing trend, there is a strong need for a platform to share original research related to applications of nanotechnology in biomedical fields. In order to fulfill this demand, this journal is being created as an international peer-reviewed periodical that covers applications of nanotechnology in all fields of life sciences.

Started in 2005, and published in 14 issues per year.

More details in: www.asppbs.com.

Journal of Bionanoscience – bionanoscience attempts to harness various functions of biological macromolecules and integrate them with engineering for technological applications. It is based on a bottom-up approach and encompasses structural biology, biomacromolecular engineering, material science, and engineering, extending the horizon of material science. The journal aims at publication of Letters, Reviews, Concepts, Rapid communications, Research papers, Book reviews, and Conference announcements in the interface between chemistry, physics, biology, material science, and technology.

Started in 2007.

More details in: www.asppbs.com.

Journal of Computational and Theoretical Nanoscience is an international peer-reviewed journal with a wide-ranging coverage, and consolidates research activities in all aspects of computational and theoretical nanoscience into a single reference source. This journal offers scientists and engineers peer-reviewed research papers in all aspects of computational and theoretical nanoscience and nanotechnology in chemistry, physics, materials science, engineering and biology.

Started in 2005, and published in 8 issues per year.

More details in: www.asppbs.com.

Journal of Experimental Nanoscience – international and multidisciplinary, this journal provides a showcase for advances in the experimental sciences underlying nanotechnology and nanomaterials. The journal exists to bring together the most significant papers making original contributions to nanoscience in a range of fields including biology and biochemistry, physics, chemistry, chemical, electrical and mechanical engineering, materials, pharmaceuticals and medicine. The aim is to provide a forum in which cross fertilization between application areas, methodologies, disciplines, as well as academic and industrial researchers can take place and new developments can be encouraged.

Started in 2006, and published in 4 issues per year.

More details in: www.tandf.co.uk.

Journal of Geoethical Nanotechnology explores economic, political, social and technological aspects of the developing technology of molecular nanotechnology. The journal invites submissions on controversial topics such as self-replication and governance.

Started in 2008, and published in 2 issues per year.

More details in: www.terasemjournal.org.

Journal of Laser Micro/Nanoengineering is an international online journal for the rapid publication of experimental and theoretical investigations in laser-based technology for micro- and nano-engineering. Access to the full article is provided free of charge.

Started in 2006, and published in 3 issues per year.

More details in: www.jlps.gr.jp.

Journal of Metastable and Nanocrystalline Materials is devoted to the rapid dissemination of recent high-quality research results concerning nanocrystalline, nanocomposite and metastable materials.

More details in: www.worldscinet.com.

Journal of Micro and Nano Mechatronics is devoted to the theory and applications of micro and nanotechnologies. The Journal promotes both theoretical and practical engineering research based on the analysis and synthesis from the micro level to the nano-level. The journal includes survey papers, technical papers, short papers and news items in the field of Micro and Nano Mechatronics.

Started in 2008, and published in 4 issues per year.

More details in: www.springerlink.com.

Journal of Micro/Nano Lithography, MEMS, and MOEMS – the Journal of Microlithography, Microfabrication, and Microsystems changed its title to the Journal of Micro/Nanolithography, MEMS, and MOEMS in January 2007.

Started in 2007, and published in 4 issues per year.

More details in: //spiedigitallibrary.aip.org.

Journal of Nano and Microsystem Technique – the task of the journal is to illuminate the modern status, perspectives and development trends of microsystem engineering, to consider the problems of development and embedding microsystems in

different areas of science, technology and production.
Started in 1999.
More details in: www.microsystems.ru.

Journal of Nanobiotechnology is devoted to the publication of research on all aspects of scientific and technological advances in the fields of medical, biological and nanoscale sciences.
Started in 2003, and published in 10 issues per year.
More details in: www.jnanobiotechnology.com.

Journal of Nano Education is a peer-reviewed international journal that aims to provide the most complete and reliable source of information on current developments in nanoscale science, technology, engineering, and medical education.
Started in 2008.
More details in: www.asppbs.com.

Journal of Nanoengineering and Nanosystems is dedicated to the particular aspects of nanoscale engineering, science, and technology that involve descriptions of nanoscale systems. This journal reflects the work on real devices and processes that arises from transitioning the scientific and engineering database.
Started in 2006, and published in 4 issues per year.
More details in: www.pepublishing.com.

Journal of Nanoelectronics and Optoelectronics is an international and cross-disciplinary peer-reviewed journal to consolidate emerging experimental and theoretical research activities in the areas of nanoscale electronic and optoelectronic materials and devices into a single and unique reference source. The aims are to facilitate the dissemination of interdisciplinary research results in the inter-related and converging fields of nanoelectronics and optoelectronics.
Started in 2006, and published in 3 issues per year.
More details in: www.asppbs.com.

Journal of Nanomaterials – the overall aim of this journal is to bring science and applications together on nanoscale and nanostructured materials with emphasis on synthesis, processing, characterization, and applications of materials containing true nanosize dimensions or nanostructures that enable novel/enhanced properties or functions. It is directed at both academic researchers and practicing engineers. Journal of Nanomaterials will highlight the continued growth and new challenges in nanomaterials science, engineering, and nanotechnology, both for application development and for basic research. All papers should emphasize original results relating to experimental, theoretical, computational, and/or applications of nanomaterials ranging from hard (inorganic) materials, through soft (polymeric and biological) materials, to hybrid materials or nanocomposites.
Started in 2006, and published in 1 issue per year.
More details in: www.hindawi.com.

Journal of Nanoneuroscience – advances in nanomaterials indicate that the central nervous system is susceptible to nanoparticle-induced alterations leading to functional or structural alterations. This knowledge is currently disseminated in vast array of journals dealing with broad subject areas related to pharmacology, toxicology, neuroscience or nanosciences.

Started 2008.

More details in: www.asppbs.com.

Journal of Nanoparticle Research – the objective of this journal is to disseminate knowledge of the physical, chemical and biological phenomena and processes in structures that have at least one lengthscale ranging from molecular to approximately 100 nm (or submicron in some situations), and exhibit improved and novel properties that are a direct result of their small size.

Started in 1999, and published in 6 issues per year.

More details in: www.springerlink.com.

Journal of Nanophotonics is an online-only journal and focuses on the fabrication and application of nanostructures that facilitate the generation, propagation, manipulation, and detection of light from the infrared to the ultraviolet regimes.

Started in 2007.

Journal of Nano Research is a multidisciplinary peer-reviewed journal, which publishes high quality work on all aspects of nanoscience and nanotechnology. This journal serves the global ''nano'' community in providing up-to-date information on all developments and progress being made in nanoscience and nanotechnology and the future predictions for this extraordinary technology.

Started in 2007.

More details in: www.scientific.net.

Journal of Nanoscience and Nanotechnology is an international and multidisciplinary peer-reviewed journal with a wide-ranging coverage, consolidating research activities in all areas of nanoscience and nanotechnology into a single and unique reference source. It is devoted to the publication of original full research articles, rapid communications of important new scientific and technological findings, timely state-of-the-art reviews with author's photo and short biography, and current research news encompassing the fundamental and applied research in all disciplines of science, engineering and medicine.

Started in 2001, and published in 10 issues per year.

More details in: www.asppbs.com.

Micro & Nano Letters is devoted to fundamental and applied research conducted at the forefront of micro- and nanoscale science and technology. The journal specializes in the express publication of short research papers concentrating on the latest advances in the science, engineering, technology and applications of miniature and ultraminiature structures and systems that have at least one dimension ranging from a few tens of micrometres to a few nanometres. This journal offers a rapid route for international dissemination of high quality research findings generated by researchers from both the micro and nano communities. Contributions addressing issues ranging from fundamental understanding to experimental demonstrations in the disciplines of engineering, physical, chemical, biological and material science should be submitted, with particular interest placed on manuscripts addressing cross-disciplinary activities and applications.

Started in 2006, and published in 4 issues per year.

More details in: www.ietdl.org.

Microfluidics and Nanofluidics is an international peer-reviewed journal that aims to publish papers in all aspects of microfluidics, nanofluidics and lab-on-a-chip science and technology. The journal broadly interprets microfluidics and nanofluidics as the studies of mass (including molecular and colloidal) and momentum transfer, heat transfer, and reactive processes coupled with transport in microscale and nanoscale systems.

Started in 2005, and published in 6 issues per year.

More details in: www.springerlink.com.

Microsystem Technologies. Micro- and Nanosystems Information Storage and Processing Systems was born on 1 January 2002, from the merging of Journal of Information Storage and Processing Systems and Microsystem Technologies. It is intended to provide rapid publication of important and timely results on electromechanical, materials science, design, and manufacturing issues of these systems and their components.

Started in 2002, and published in 6 issues per year.

More details in: www.springerlink.com.

Nano is an international peer-reviewed journal for nanoscience and nanotechnology that presents papers at the forefront of fundamental research and new emerging topics. It features timely scientific reports of new results and technical breakthroughs and also contains interesting review articles about recent hot issues.

Started in 2006, and published in 6 issues per year.

More details in: www.worldscinet.com.

NanoBiotechnology is an international peer-reviewed journal that publishes research papers covering all aspects of the emerging and rapidly growing research area at the intersection of nanotechnology, molecular biology and biomedical sciences. This journal serves as an authoritative forum presenting state-of-the-art, multidisciplinary research and technological advances in theory, instrumentation and methods as well as applications in a variety of areas of nanotechnology related to biology and medicine. The convergence of nanotechnology and biomedical sciences opens up a wide variety of biological research topics and medical uses at the molecular and cellular level.

Started in 2005, and published in 4 issues per year.
More details in: www.springerlink.com.

NanoBiotechnology Nanotechnology is a peer-reviewed scientific journal that provides a multidisciplinary forum for state-of-the-art nanobiotechnological methods, instrumentation, and research.
Started in 2005, and published in 4 issues per year.
More details in: www.humanapress.com.

Nanoethics – nanoscale technologies are currently surrounded by both hype and fear. Optimists suggest that these technologies are desperately needed to solve problems of terrorism, global warming, the shortage of clean water, land degradation and health. Pessimists fear the loss of privacy and loss of autonomy, ‘‘grey goo’’ and weapons of mass destruction, and serious environmental and health risks. There is also concern about the fair distribution of the costs and benefits of the technology. The field needs a forum for informed discussion of ethical and social issues related to nanotechnology to counterbalance popular discussions and fragmented representation of opinions and findings.
Started in 2007, and published in 3 issues per year.
More details in: www.springerlink.com.

Nano Letters – the leading forum for rapid communication of nanoscale research in a range of disciplines, from physical and materials chemistry to biotechnology and applied physics.
Started in 2001, and published in 12 issues per year.
More details in: www.acs.com.

Nanomedicine addresses the important challenges and advances in medical nanoscale-structured materials and devices, biotechnology devices and molecular machine systems and nanorobotics, delivering this essential information in concise, clear and attractive article formats, a valuable information source for all players in the field and across the scientific community.
Started in 2006, and published in 6 issues per year.
More details in: www.futuremedicine.com.

Nanomedicine: Nanotechnology, Biology, and Medicine is an international, peer-reviewed journal that delivers the latest advances in the innovative field of nano-scale medicine. The journal publishes articles on basic, diagnostic, experimental, clinical, engineering, pharmacologic and toxicologic nanomedicine. In addition, regular features address the commercialization of new technologies, ethics in the field, research funding, and other topics of interest to researchers and clinicians.
Started in 2005, and published in 4 issues per year.
More details in: www.sciencedirect.com.

Nanoscale and Microscale Thermophysical Engineering is a peer-reviewed journal covering the basic science and engineering of nanoscale and microscale energy conversion, transport, storage, mass transport, and reactions. In addition, the journal addresses their integration and uses in devices and systems in the fields of medicine, transportation, energy, environment, and information.

Started in 1997, and published in 4 issues per year.

More details in: www.tandf.co.uk.

Nanoscale Research Letters – as an open access journal, it is the first nanotechnology journal from a major commercial publisher to make all research results available to anyone with an internet connection. This Journal provides an interdisciplinary forum for open communication of scientific and technological advances in the creation and use of objects at the nanometer scale. The journal crosses all disciplines, and emphasizes research that seeks to uncover the underlying science and behavior of nanostructures. Nano Express are original research papers which publish approximately eight weeks following submission. Nano Reviews, Nano Ideas, and Nano Commentaries are also welcomed.

Started in 2006, and published in 12 issues per year.

More details in: www.springerlink.com.

Nano Science & Nano Technology is an Indian journal devoted to the rapid publication of fundamental research papers on all branches of the theory and practice of nanoscience and nanotechnology. It encompasses the understanding of the fundamental physics, chemistry, biology and technology of nanometer-scale objects.

Started in 2007, and published in 2 issues per year.

More details in: www.tsijournals.com.

Nanotechnology aims to publish papers at the forefront of nanoscale science and technology and especially those of an interdisciplinary nature. Here, nanotechnology is taken to include the ability to individually address, control, and modify structures, materials and devices with nanometer precision, and the synthesis of such structures into systems of micro- and macroscopic dimensions such as MEMS-based devices. It encompasses the understanding of the fundamental physics, chemistry, biology and technology of nanometer-scale objects and how such objects can be used in the areas of computation, sensors, nanostructured materials and nano-biotechnology.

Started in 1990, and published weekly.

More details in: www.iop.org.

Nanotechnology Law & Business is the source of information for professionals involved in micro- and nanotechnologies. This journal is devoted to the institutional investor seeking to understand how nanotechnology will impact on certain markets, to lawyers mapping the patent landscape surrounding a particular technology, or to companies navigating regulatory issues.

Started in 2004, and published in 4 issues per year.
More details in: www.nanolabweb.com.

Nanotechnology Perceptions is published to provide a stimulating forum for the exchange of ideas and information concerning nanotechnology (including bionanotechnology and nanomedicine) and ultraprecision engineering. Each issue contains essays on critical issues of the technologies themselves, as well as incisive appraisals of their impact on human life, society and its institutions. Articles are intended for a worldwide readership, and should be of especial interest to leaders in industry, commerce (including bankers and investors), the professions, politics and public administration, and all others who must make decisions based on a sober, impartial assessment of the potential and risks of nanotechnology in their areas of work.
Started in 2005, and published in 3 issues per year.
More details in: //pages.unibas.ch.

Nano Today is an international magazine for researchers with interests across the whole of nanoscience and technology. Through its unique mixture of peer-reviewed articles, the latest research news, and information on key developments, this journal provides comprehensive coverage of this exciting and dynamic new field.
Started in 2006, and published in 6 issues per year.
More details in: www.sciencedirect.com.

Nanotoxicology invites contributions addressing research relating to the potential for human and environmental exposure, hazard and risk associated with the use and development of nano-structured materials. In this context, the term nano-structured materials has a broad definition, including materials with at least one dimension in the nanometer size range. These nanomaterials range from nanoparticles and nanomedicines, to nano-surfaces of larger materials and composite materials. The range of nanomaterials in use and under development is extremely diverse, so this journal includes a range of materials generated for purposeful delivery into the body (food, medicines, diagnostics and prosthetics), to consumer products (for example, paints, cosmetics, electronics and clothing), and particles designed for environmental applications (such as remediation). It is the nano-size range of these materials which unifies them and defines the scope of of the journal. While the term ''toxicology'' indicates risk, the journal also aims to encompass studies that enhance safety during the production, use and disposal of nanomaterials. Well-controlled studies demonstrating a lack of exposure, hazard or risk associated with nanomaterials, or studies aiming to improve biocompatibility are welcomed and encouraged, as such studies will lead to an advancement of nanotechnology. Furthermore, many nanoparticles are developed with the intention to improve human health (for example, antimicrobial agents), and again, such articles are encouraged.
Started in 2007, and published in 4 issues per year.
More details in: www.tandf.com.

Nanotrends Journal is devoted to the publication of basic and applied papers dealing with latest trends in Nanotechnology and other scientific applications in the nanometer range.

Started in 2006, and published in 6 issues per year.

More details in: www.nstc.in.

Nature Nanotechnology is a research journal dedicated to all aspects of nanoscience and nanotechnology.

Started in 2006, and published in 12 issues per year.

More details in: www.nature.com.

Recent Patents on Nanotechnology publishes review articles by experts on recent patents on nanotechnology. A selection of important and recent patents on nanotechnology is also included in the journal. The journal is essential reading for all researchers involved in nanotechnology.

Started in 2007, and published in 3 issues per year.

More details in: www.bentham.org.

Open Nanoscience Journal is an Open Access online journal, which publishes research articles, reviews, and letters in the field of nanoscience and nanotechnology, encompassing biotechnology, medicine, pharmaceuticals, chemistry, physics, biology, materials science and electronics. This journal, a peer-reviewed journal, aims to provide the most complete and reliable source of information on current developments in the field. The emphasis will be on publishing quality papers rapidly and freely available to researchers worldwide.

Started in 2007.

More details in: www.bentham.org.

Photonics and Nanostructures: Fundamentals and Applications establishes a dedicated channel for physicists, material scientists, chemists, engineers and computer scientists who are interested in photonic crystals and photonic band gaps. The journal will help shed light on the latest developments in this growing field of science that will see the emergence of faster telecommunications and ultimately computers that use light instead of electrons to connect components. This journal features mainly original research work in experiment, theory and applications.

Started in 2003, and published in 6 issues per year.

More details in: www.sciencedirect.com.

Physica E (Low-dimensional systems and nanostructures) contains papers and review articles on the fundamental and applied aspects of physics in low-dimensional systems, including semiconductor heterostructures, mesoscopic systems, quantum wells and superlattices, two-dimensional electron systems, and quantum wires and dots. Both theoretical and experimental contributions are invited. Topics suitable for publication in this journal include optical and transport properties, many-body effects, integer and fractional quantum Hall effects, single-electron effects and devices, and novel phenomena.

Started in 1998, and published in 3 issues per year.

More details in: www.sciencedirect.com.

Precision Engineering–Journal of the International Societies for Precision Engineering and Nanotechnology is devoted to the multidisciplinary study and practice of high accuracy engineering, metrology, and manufacturing. The journal takes an integrated approach to all subjects related to research, design, manufacture, performance validation, and application of high precision machines, instruments, and components, including fundamental and applied research and development in manufacturing processes, fabrication technology, and advanced measurement science. The scope includes precision-engineered systems and supporting metrology over the full range of length scales, from atom-based nanotechnology and advanced lithographic technology to large-scale systems, including optical and radio telescopes and macrometrology. Precision Engineering was first published in January 1979; from January 2000, it assumes a new look, as the Journal of the International Societies for Precision Engineering and Nanotechnology.

Started in 2000, and published in 4 issues per year.

More details in: www.sciencedirect.com.

Synthesis and Reactivity in Inorganic, Metal-Organic, and Nano-Metal Chemistry is devoted to the rapid dissemination of original research papers of relevance to inorganic and metal-organic chemists and nano scientists engaged in synthesis. This journal publishes syntheses and reactivity of new compounds, new methods for preparation of known compounds, and new experimental techniques and procedures. The journal is a publication aimed at the rapid dissemination of original research papers of particular importance to inorganic and metal-organic chemists and nanotechnology professionals. This journal replaced in 2005 the journal Synthesis and Reactivity in Inorganic and Metal-Organic Chemistry. This new title reflects the rapidly growing fields of nanoscience and nanotechnology.

Started in 2005, and published in 10 issues per year.

More details in: www.tandf.com.

Virtual Journal of Nanoscale Science & Technology – this weekly virtual journal contains articles that have appeared in one of the participating source journals and that fall within a number of contemporary topical areas in the science and technology of nanometer-scale structures. The articles are primarily those that have been published in the previous week.

Started in 2000, and published weekly.

More details in: http://publish.aps.org.

Abbreviations for the scientific journals which appear as sources in the text

Abhand. Köngl. Böhm. Gesellsch. : Abhandlungen der Königlichen Böhmischen Gesellschaft der Wissenschaften.
Arch. Electrotech. : Archiv für Elektrotechnik.
Adv. Coll. Int. Sci. : Advances in Colloid and Interface Science.
Adv. Mater. : Advanced Materials.
Adv. Phys. : Advances in Physics.
Am. J. Math. : American Journal of Mathematics.
Am. J. Phys. : American Journal of Physics.
Am. J. Sci. : American Journal of Science.
Angew. Chem. : Angewandte Chemie.
Ann. Chim. Phys. : Annales de Chimie et de Physique.
Ann. Hist. Comput. : Annals of the History of Computing.
Ann. Phys. : Annalen der Physik.
Ann. Rev. Mater. Sci. : Annual Review on Materials Science.
Appl. Phys. : Applied Physics.
Appl. Phys. Lett. : Applied Physics Letters.
Appl. Surf. Sci. : Applied Surface Science.
Arch. Mikr. Anat. : Archiv für Mikroskopische Anatomie.
Astrophys. J. : Astrophysical Journal.
Bell Syst. Tech. J. : Bell Systems Technical Journal.
Ber. Dtsch. Bot. Ges. : Berichte der Deutschen Botanischen Gesellschaft.
Biochim. Biophys. Acta : Biochimica et Biophysica Acta.
Biophys. J. : Biophysical Journal.
Bull. Soc. Chim. Paris : Bulletin de la Société Chimique de Paris.
Bull. Natl. Bur. Std. : Bulletin of the National Bureau of Standards.
Can. J. Phys. : Canadian Journal of Physics.
Chem. Phys. Lett. : Chemical Physics Letters.
Chem. Rev. : Chemical Review.
Commun. Assoc. Comput. Mach. : Communications of the Association for Computing Machinery.
Commun. Pure Appl. Math. : Communications on Pure and Applied Mathematics.

Abbreviations for the scientific journals which appear as sources in the text

C. R. : Comptes Rendus.
Contemp. Phys. : Contemporary Physics.
Cur. Opin. Colloid Interf. Sci. : Current Opinion in Colloid & Interface Science.
Curr. Opin. Struct. Biol. : Current Opinion in Structural Biology.
Disc. Faraday Soc. : Discussion of the Faraday Society.
Dokl. Akad. Nauk. SSSR : Doklady Akademii Nauk SSSR.
Electron. Lett. : Electronic Letters.
Electr. World : Electrical World.
Europhys. Lett. : Europhysics Letters.
Fund. Math. : Fundamentals of Mathematics.
Fiz. Tekh. Poluprovodn. : Fizika i Tekhnika Poluprovodnikov.
Fiz. Teverd. Tela : Fizika Tverdogo Tela.
Gött. Nachr. Math. Phys. Klass. : Nachrichten von der Akademie der Wissenschaften zu Göttingen-Mathematisch-Physikalische Klasse.
Helv. Phys. Acta : Helvetica Physica Acta.
IBM J. Res. Dev. : IBM Journal of Research and Development.
IEEE: Institute of Electrical and Electronics Engineers.
IEEE Acoustic, Speech, Sign. Process. Mag. : IEEE Acoustic, Speech, and Signal Processing Magazine.
IEEE Int. Conf. Comp. Syst. Signal. Proc. : IEEE International Conference Composition System Signal Proceedings.
IEEE J. Quantum Electron. : IEEE Journal on Quantum Electronics.
IEEE Trans. Electron. Dev. : IEEE Transactions on Electronic Devices.
IEEE Trans. Inform. Theor. : IEEE Transactions on Information Theory.
IEEE Trans. Appl. Superconductivity : IEEE Transactions on Applied Superconductivity.
Ind. J. Phys. : Indian Journal of Physics.
Int. J. Theor. Phys. : International Journal of Theoretical Physics.
J. Am. Chem. Soc. : Journal of the American Chemical Society.
J. Am. Stat. Ass. : Journal of the American Statistical Association.
J. Appl. Phys. : Journal of Applied Physics.
J. Chem. Phys. : Journal of Chemical Physics.
J. Colloid Interface Sci. : Journal of Colloid & Interface Science.
J. Compt. : Journal of Computer.
J. Cryst. Growth : Journal of Crystal Growth.
J. Ecole Polytechn. : Journal de l'Ecole Polytechnique.
J. Electrochem. Soc. : Journal of the Electrochemical Society.
J. Frank. Inst. : Journal of the Franklin Institute.
J. Low Temp. Phys. : Journal of Low Temperature Physics.
J. Magn. Magn. Mat. : Journal of Magnetism and Magnetic Materials.
J. Mat. Res. : Journal of Material Research.
J. Math. Phys. : Journal of Mathematical Physics.
J. Microsc. : Journal of Microscopy.
J. Opt. Soc. Am. : Journal of the Optical Society of America.

Abbreviations for the scientific journals which appear as sources in the text

J. Photochem. Photobiol. : Journal of Photochemistry and Photobiology.
J. Phys. : Journal of Physics.
J. Phys. Chem. Sol. : Journal of Physics and Chemistry of Solids.
J. Phys. Condens. Matter : Journal of Physics; Condensed Matter.
J. Phys. Soc. Jpn. : Journal of the Physical Society of Japan.
J. Sci. Inst. Elect. Engrs. : Journal of Scientific Institute of Electrical Engineers.
JSME Int. J. : Japan Society Mechanical Engineering International Journal.
J. Stat. Phys. : Journal of Statistical Physics.
J. Vac. Sci. Tech. : Journal of Vacuum Science and Technology.
Jpn. J. Appl. Phys. : Japanese Journal of Applied Physics.
Kgl. Danske Videnskab. Selskab – Mat.-fys. Medd. : Kongelige Danske Videnskabernes Selskab – Matematisk-Fysiske Meddelelser.
Kolloid Z. : Kolloid-Zeitschrift.
Math. Syst. Theory : Mathematical Systems Theory.
Mat. Sci. Techn. : Materials Science and Technology.
Math. Annal. : Mathematische Annalen.
Methods Enzymol. : Methods in Enzymology.
Mol. Phys. : Molecular Physics.
Monatsh. Chem. : Monatshefte für Chemie.
Nano Lett. : Nano Letters.
Nanomedicine: Nanotech. Biol. Med. : Nanomedicine: Nanotechnology, Biology, and Medicine.
Naturwiss. : Naturwissenschaften.
Opt. Lett. : Optics Letters.
Phil. Mag. : Philosophical Magazine.
Phil. Trans. R. Soc. London : Philosophical Transactions of the Royal Society of London.
Philips Res. Rep. : Philips Research Reports.
Photogr. J. : Photographic Journal.
Phys. A : Physica A.
Phys. Lett. : Physics Letters.
Phys. Rev. : Physical Review.
Phys. Rev. A : Physical Review A.
Phys. Rev. B : Physical Review B.
Phys. Rev. Lett. : Physical Review Letters.
Phys. Today : Physics Today.
Phys. Z. : Physikalische Zeitschrift.
PNAS : Proceedings of the National Academy of Sciences.
Proc. Am. Acad. Arts Sci. : Proceedings of the American Academy of Arts and Sciences.
Proc. Inst. Radio Eng. : Proceedings of the Institute of Radio Engineers.
Proc. K. Ned. Akad. Wet. : Verhandelingen der Koninklijke Nederlandse Akademie van Vetenschappen.
Proc. Phys. Soc. : Proceedings of the Physical Society.

Abbreviations for the scientific journals which appear as sources in the text

Proc. R. Acad. Sci : Proceedings of the Royal Academy of Science.
Proc. R. Soc. Lond. : Proceedings of the Royal Society of London.
Proc. Camb. Phil. Soc. : Proceedings of the Cambridge Philosophical Society.
Prog. Phot. Res. Appl. : Progress in Photovoltaics: Research and Applications.
Proc. Phys. Math. Soc. Jpn. : Proceedings of the Physico-Mathematical Society of Japan.
Prog. Theor. Phys. : Progress on Theoretical Physics.
Pure Appl. Math. : Pure and Applied Mathematics.
Rend. Accad. Naz. Lincei : Rendiconti dell'Accademia Nazionale dei Lincei.
Rep. Prog. Phys. : Reports on Progress in Physics.
Rev. Mod. Phys. : Review of Modern Physics.
Rev. Sci. Instrum. : Review of Scientific Instruments.
Schultzes Arch. Mikr. Anat. : Schultzes Archiv für Mikroskopische Anatomie.
Semicond. Sci. Technol. : Semiconductor Science and Technology.
SIAM J. Comp. : Society for Industrial and Applied Mathematics Journal on Computing.
SIGACT News : Association for Computing Machinery – Special Interest Group on Algorithm and Computational Theory News.
Sitzungsber. Akad. Wiss. Wien, Math. Naturw. Kl. : Sitzungsberichte der Akademie der Wissenschaften in Wien, Mathematisch-Naturwissenschaftliche Klasse.
Sitzungsber. Bay. Akad. Wiss. : Sitzungsberichte der Bayerischen Akademie der Wissenschaften.
Sitzungsber. Preuss. Akad. Wiss. : Sitzungsberichte der Preussischen Akademie der Wissenschaften.
Skr. Norsk. Vid. Akademi, Oslo, Mat. Nat. Kl. : Tidskrifte Norske Videnskaps-Akademi i Olso, Matematisk-Naturvitenskapelige Klasse.
Solid State Commun. : Solid State Communications.
Sov. J. Nucl. Phys. : Soviet Journal of Nuclear Physics.
Sov. Phys. JETP : Soviet Physics – Journal of Experimental and Theoretical Physics.
Sov. Phys. Semicond. : Soviet Physics – Semiconductors.
Surf. Sci. : Surface Science.
Surf. Sci. Rep. : Surface Science Reports.
Symp. Quant. Biol. : Quantum Biology Symposium.
Theory Prob. Appl. : Theory of Probability and its Applications.
Trans. AIEE : Transactions of the American Institute of Electrical Engineers.
Trans. Conn. Acad. : Transactions of the Connecticut Academy of Arts and Sciences.
Trans. Faraday Soc. : Transactions of the Faraday Society.
Trans. Opt. Soc. : Transactions of the Optical Society.
Trans. R. Irish Acad. : Transactions of the Royal Irish Academy.
Usp. Fiz. Nauk. : Uspekhi Fiziceskih Nauk.
Verh. Deutsch. Phys. Ges. : Verhandlungen der Deutschen Physikalischen Gesellschaft.
Z. Instrumkde : Zeitschrift für Instrumentenkunde.
Z. Kristallogr. : Zeitschrift für Kristallographie.
Z. Krist. Miner. : Zeitschrift für Kristallographie und Mineralogie.

Abbreviations for the scientific journals which appear as sources in the text

Z. Naturforsch. : Zeitschrift für Naturforschung.
Z. Phys. : Zeitschrift für Physik.
Z. Phys. Chem. : Zeitschrift für Physikalische Chemie.
Zh. Exp. Theor. Fiz. : Zhurnal Experimentalnoy i Theoreticheskoy Fiziki.
Zh. Russkogo Fiz.-Khim. Obsch. : Zhurnal Russkogo Fiziko-Khimicheskogo Obschestva.

Appendix – main properties of intrinsic (or lightly doped) semiconductors

Table 1 Group IV semiconductors.

Material	**C**	**Si**	**Ge**	**α Sn**
Crystalline structure	cubic – diamond			
Lattice parameter at 300 K, nm	0.35668	0.54311	0.56579	0.64892
Nature of the E_{gap} (d – direct, i – indirect)	i	i	i	i
Fundamental E_{gap} at 0 K, eV	5.48	1.166	0.74	0.09
Fundamental E_{gap} at 300 K, eV	5.47	1.11	0.67	
Refractive index		3.44	4.00	
Rel. permittivity (static dielectric constant)	5.7	11.7	16.3	24
Mass of electrons, in m_0 units	0.2	0.980.19	1.580.08	0.023
Mass of holes, in m_0 units	0.25	0.52	0.3	0.20
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$	1800	1500	3900	1400
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	1200	450	1900	1200

Table 2 Semiconducting SiC.

Compound	**α–SiC**	**β–SiC**
Crystalline structure	6H (hexagonal)	3C (cubic)
Lattice parameters at 300 K (*a* or *a*,*c*), nm	0.30806 1.51173	0.43596
Nature of the E_{gap} (d – direct, i – indirect)	i	i
Fundamental E_{gap} at 0 K, eV		
Fundamental E_{gap} at 300 K, eV	2.86	2.2
Refractive index	2.65	2.66
Rel. permittivity (static dielectric constant)	$9.66_{\perp c}$, $10.03_{\parallel c}$	9.72
Mass of electrons, in m_0 units	$0.25_{\perp c}$, $1.5_{\parallel c}$	0.647 0.24
Mass of holes, in m_0 units	1.0	
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$	260	900
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	50	

Table 3 Semiconducting $A^{III}B^{V}$ nitrides.

Compound	**AlN**	**GaN**	**InN**
Crystalline structure	hexagonal – wurtzite		
Lattice parameters at 300 K (*a*,*c*), nm	0.3111 0.4978	0.3189 0.5185	0.3544 0.5718
Nature of the E_{gap} (d – direct, i – indirect)	d	d	d
Fundamental E_{gap} at 0 K, eV		3.50	
Fundamental E_{gap} at 300 K, eV	6.2	3.44	1.89
Refractive index	2.15	2.4	2.56
Rel. permittivity (static dielectric constant)	8.5	8.9	15.3
Mass of electrons, in m_0 units	0.48	0.2	0.11
Mass of holes, in m_0 units	0.471	0.259	
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$	135	1000	3200
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	14	30	

Table 4 Semiconducting $A^{III}B^{V}$ phosphides.

Compound	AlP	GaP	InP
Crystalline structure	cubic – zinc blende		
Lattice parameter at 300 K, nm	0.54635	0.5450	0.58687
Nature of the E_{gap} (d – direct, i – indirect)	i	i	d
Fundamental E_{gap} at 0 K, eV	2.51	2.4	1.42
Fundamental E_{gap} at 300 K, eV	2.45	2.25	1.35
Refractive index		3.37	3.37
Rel. permittivity (static dielectric constant)	9.8	11.1	12.1
Mass of electrons, in m_0 units	0.166	0.82	0.077
Mass of holes, in m_0 units	0.20	0.60	0.64
Mobility of electrons at 300 K, $cm^2/(V \cdot s)$	80	110	4600
Mobility of holes at 300 K, $cm^2/(V \cdot s)$		75	150

Table 5 Semiconducting $A^{III}B^{V}$ arsenides.

Compound	AlAs	GaAs	InAs
Crystalline structure	cubic – zinc blende		
Lattice parameter at 300 K, nm	0.5660	0.5653	0.6058
Nature of the E_{gap} (d – direct, i – indirect)	i	d	d
Fundamental E_{gap} at 0 K, eV	2.229	1.519	0.43
Fundamental E_{gap} at 300 K, eV	2.153	1.424	0.36
Refractive index		3.4	3.42
Rel. permittivity (static dielectric constant)	10.1	12.5	12.5
Mass of electrons, in m_0 units	0.1	0.07	0.028
Mass of holes, in m_0 units	0.15	0.5	0.33
Mobility of electrons at 300 K, $cm^2/(V \cdot s)$	294	8500	33000
Mobility of holes at 300 K, $cm^2/(V \cdot s)$		400	460

Table 6 Semiconducting $A^{III}B^{V}$ antimonides.

Compound	**AlSb**	**GaSb**	**InSb**
Crystalline structure	cubic – zinc blende		
Lattice parameter at 300 K, nm	0.61355	0.6095	0.64787
Nature of the E_{gap} (d – direct, i – indirect)	i	d	d
Fundamental E_{gap} at 0 K, eV	1.686	0.81	0.235
Fundamental E_{gap} at 300 K, eV	1.61	0.69	0.17
Refractive index		3.9	3.75
Rel. permittivity (static dielectric constant)	14.4	15	18
Mass of electrons, in m_0 units	0.12	0.045	0.0133
Mass of holes, in m_0 units	0.98	0.39	0.18
Mobility of electrons at 300 K, $cm^2/(V·s)$	200	5000	80 000
Mobility of holes at 300 K, $cm^2/(V·s)$	420	850	1250

Table 7 Semiconducting $A^{I}B^{VII}$ chlorides.

Compound	**γCuCl**	**AgCl**
Crystalline structure	cubic – zinc blende	cubic – NaCl
Lattice parameter at 300 K, nm	0.54057	0.55023
Nature of the E_{gap} (d – direct, i – indirect)	d	i
Fundamental E_{gap} at 0 K, eV	3.95	3.25
Fundamental E_{gap} at 300 K, eV		
Refractive index	2.1	2.1
Rel. permittivity (static dielectric constant)	7.9	11.1
Mass of electrons, in m_0 units	0.43	
Mass of holes, in m_0 units	4.2	
Mobility of electrons at 300 K, $cm^2/(V·s)$		
Mobility of holes at 300 K, $cm^2/(V·s)$		

Table 8 Semiconducting $A^{I}B^{VII}$ bromides.

Compound	**γ CuBr**	**AgBr**
Crystalline structure	cubic – zinc blende	cubic – NaCl
Lattice parameter at 300 K, nm	0.56905	0.57748
Nature of the E_{gap} (d – direct, i – indirect)	d	i
Fundamental E_{gap} at 0 K, eV	3.07	2.68
Fundamental E_{gap} at 300 K, eV		
Refractive index		
Rel. permittivity (static dielectric constant)	8.0	11.8
Mass of electrons, in m_0 units	0.21	0.22
Mass of holes, in m_0 units	23.2	0.52
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$		60
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$		2

Table 9 Semiconducting $A^{I}B^{VII}$ iodides.

Compound	**γCuI**	**β–AgI**
Crystalline structure	cubic – zinc blende	hexagonal-wurtzite
Lattice parameters at 300 K (*a* or *a*,*c*), nm	0.60427	0.4592 0.7512
Nature of the E_{gap} (d – direct, i – indirect)	d	d
Fundamental E_{gap} at 0 K, eV	3.12	3.02
Fundamental E_{gap} at 300 K, eV		
Refractive index		
Rel. permittivity (static dielectric constant)	6.5	7.0
Mass of electrons, in m_0 units	0.3	
Mass of holes, in m_0 units	1.4	
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$		
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$		

Table 10 Semiconducting $A^{II}B^{VI}$ sulfides.

Compound	**ZnS**	**CdS**	**HgS**
Crystalline structure	cubic – zinc blende		
Lattice parameter at 300 K, nm	0.541	0.582	0.58517
Nature of the E_{gap} (d – direct, i – indirect)	d	d	
Fundamental E_{gap} at 0 K, eV	3.84	2.58	−0.2
Fundamental E_{gap} at 300 K, eV	3.68	2.50	
Refractive index	2.37	2.5	
Rel. permittivity (static dielectric constant)	8.9		
Mass of electrons, in m_0 units	0.40	0.2	
Mass of holes, in m_0 units			
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$	165	340	
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	5	50	

Table 11 Semiconducting $A^{II}B^{VI}$ selenides.

Compound	**ZnSe**	**CdSe**	**HgSe**
Crystalline structure	cubic – zinc blende		
Lattice parameter at 300 K, nm	0.5667	0.608	0.6085
Nature of the E_{gap} (d – direct, i – indirect)	d	d	
Fundamental E_{gap} at 0 K, eV	2.80	1.85	−0.22
Fundamental E_{gap} at 300 K, eV	2.58	1.75	
Refractive index	2.89		
Rel. permittivity (static dielectric constant)	8.1	10.6	23
Mass of electrons, in m_0 units	0.21	0.13	0.05
Mass of holes, in m_0 units	0.6		0.02
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$	500	800	
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	30		

Appendix – main properties of intrinsic (or lightly doped) semiconductors

Table 12 Semiconducting $A^{II}B^{VI}$ tellurides.

Compound	**ZnTe**	**CdTe**	**HgTe**
Crystalline structure	cubic – zinc blende		
Lattice parameter at 300 K, nm	0.6101	0.6477	0.6453
Nature of the E_{gap} (d – direct, i – indirect)	d	d	
Fundamental E_{gap} at 0 K, eV	2.39	1.60	−0.28
Fundamental E_{gap} at 300 K, eV	2.2	1.50	−0.015, 0.14
Refractive index	3.56	2.75	3.7
Rel. permittivity (static dielectric constant)	9.7	10.9	20
Mass of electrons, in m_0 units	0.15	0.11	0.029
Mass of holes, in m_0 units	0.2	0.35	−0.3
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$	340	1050	
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	100	100	

Table 13 Semiconducting $A^{IV}B^{VI}$ tin compounds.

Compound	**SnS**	**SnSe**	**SnTe**
Crystalline structure	orthorhombic distorted – – distorted NaCl		
Lattice parameters at 300 K (a, b, c), nm	1.157	1.120	
	0.419	0.399	
	0.446	0.434	
Nature of the E_{gap} (d – direct, i – indirect)	d	i	
Fundamental E_{gap} at 0 K, eV			
Fundamental E_{gap} at 300 K, eV	1.09	0.9	0.36
Refractive index			
Rel. permittivity (static dielectric constant)	32	45	
Mass of electrons, in m_0 units			
Mass of holes, in m_0 units	0.2	0.15	0.07
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$			
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	90		840

Appendix – main properties of intrinsic (or lightly doped) semiconductors

Table 14 Semiconducting $A^{IV}B^{VI}$ lead compounds.

Compound	**PbS**	**PbSe**	**PbTe**
Crystalline structure	cubic – NaCl		
Lattice parameter at 300 K, nm	0.5936	0.6117	0.6462
Nature of the E_{gap} (d – direct, i – indirect)	d	d	d
Fundamental E_{gap} at 0 K, eV	0.29	0.15	0.19
Fundamental E_{gap} at 300 K, eV	0.41	0.28	0.31
Refractive index			
Rel. permittivity (static dielectric constant)	170	210	~1000
Mass of electrons, in m_0 units	0.25	0.04	0.17
Mass of holes, in m_0 units	0.25		0.20
Mobility of electrons at 300 K, $cm^2/(V \cdot s)$	600	1	6000
Mobility of holes at 300 K, $cm^2/(V \cdot s)$	700		4000

Table 15 Semiconducting Group II silicides.

Compound	**Mg_2Si**	**Ca_2Si**	**Ca_3Si_4**	**$BaSi_2$**
Crystalline structure	cubic – CaF_2	orthorhombic	hexagonal	orthorhombic – $BaSi_2$
Lattice parameters at 300 K (a, b, c), nm	0.63512	0.7691	0.8541	0.8942
		0.4816		0.6733
		0.9035	1.4906	1.1555
Nature of the E_{gap} (d – direct, i – indirect)	i	d	i	i
Fundamental E_{gap} at 0 K, eV	0.65	0.35, 1.0	0.35	0.83
Fundamental E_{gap} at 300 K, eV	0.78			1.10
				1.30
Refractive index				
Rel. permittivity (static dielectric constant)				
Mass of electrons (m_x,m_y,m_z), in m_0 units		0.64	>1	0.60
		0.10	0.7	0.37
		0.71	1.0	0.30
Mass of holes (m_x,m_y,m_z), in m_0 units		0.16	0.46	0.31
		2.21	>1	0.73
		2.30	0.83	0.67
Mobility of electrons at 300 K, $cm^2/(V \cdot s)$	406			
Mobility of holes at 300 K, $cm^2/(V \cdot s)$	56		~50	

Table 16 Semiconducting Group VI silicides.

Compound	**$CrSi_2$**	**$MoSi_2$**	**WSi_2**
Crystalline structure	hexagonal – $CrSi_2$		
Lattice parameters at 300 K (a, c), nm	0.44281	0.4596	0.4614
	0.63691	0.6550	0.6414
Nature of the E_{gap} (d – direct, i – indirect)	i	i	i
Fundamental E_{gap} at 0 K, eV	0.35	0.07	0.07
Fundamental E_{gap} at 300 K, eV			
Refractive index			
Rel. permittivity (static dielectric constant)			
Mass of electrons (m_x,m_y,m_z), in m_0 units	0.69	0.38	0.33
	0.66	0.33	0.30
	1.49	0.73	0.65
Mass of holes (m_x,m_y,m_z), in m_0 units	1.10	0.43	0.39
	1.20	0.55	0.57
	0.82	0.50	0.45
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$			
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	10	200	220

Table 17 Semiconducting Group VII silicides.

Compound	**$MnSi_{2-x}$**	**$ReSi_{1.75}$**
Crystalline structure	tetragonal	triclinic $\alpha = 89.90^\circ$
Lattice parameters at 300 K (a, b, c), nm	$a = 0.5530$	0.3138
	$c = 1.7517$	0.3120
	4.7763	0.7670
	6.5311	
	11.79	
Nature of the E_{gap} (d – direct, i – indirect)	i	i
Fundamental E_{gap} at 0 K, eV	0.7–0.8	
Fundamental E_{gap} at 300 K, eV	0.7–0.9	0.15
Refractive index		
Rel. permittivity (static dielectric constant)		
Mass of electrons (m_x,m_y,m_z), in m_0 units	8.17	0.35
	8.17	0.32
	3.40	0.37
Mass of holes (m_x,m_y,m_z), in m_0 units	1.64	0.27
	1.64	0.27
	5.72	11.82
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$		
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	230	370

Table 18 Semiconducting Group VIII disilicides.

Compound	**β-$FeSi_2$**	**$RuSi_2$**	**$OsSi_2$**
Crystalline structure	orthorhombic – β-$FeSi_2$		
Lattice parameters at 300 K (a, b, c), nm	0.98792 0.77991 0.78388	1.0053 0.8028 0.8124	1.0150 0.8117 0.8223
Nature of the E_{gap} (d – direct, i – indirect)	d/i	?	i
Fundamental E_{gap} at 0 K, eV			
Fundamental E_{gap} at 300 K, eV	0.78–0.87	0.35–0.52	1.4
Refractive index			
Rel. permittivity (static dielectric constant)			
Mass of electrons (m_x,m_y,m_z), in m_0 units	$>>1$		
Mass of holes (m_x,m_y,m_z), in m_0 units	0.21 0.27 0.27		
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$	900		
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	200		

Table 19 Semiconducting Group VIII silicides (except disilicides).

Compound	**Ru_2Si_3**	**Os_2Si_3**	**OsSi**	**Ir_3Si_5**
Crystalline structure	orthorhombic-Ru_2Si_3		cubic-FeSi	monoclinic $\alpha = 89.90^\circ$
Lattice parameters at 300 K (a, b, c), nm	1.1057 0.8934 0.5533	1.1124 0.8932 0.5570	0.4729	0.6406 1.4162 1.1553
Nature of the E_{gap} (d – direct, i – indirect)	d	d		i
Fundamental E_{gap} at 0 K, eV				
Fundamental E_{gap} at 300 K, eV	0.7–1.0	2.3	0.34	1.2
Refractive index				
Rel. permittivity (static dielectric constant)				
Mass of electrons (m_x,m_y,m_z), in m_0 units	3.28 2.85 0.61			
Mass of holes (m_x,m_y,m_z), in m_0 units	0.47 0.15 0.45			
Mobility of electrons at 300 K, $cm^2/(V{\cdot}s)$				
Mobility of holes at 300 K, $cm^2/(V{\cdot}s)$	2–3			2–3



5th EDITION

MOUNTAINEERING:
THE FREEDOM OF THE HILLS

The MOUNTAINEERS

MOUNTAINEERING
The Freedom of the Hills

Fifth Edition



Mountaineering
The Freedom of the Hills



Fifth Edition

Editor: Don Graydon

Revision Committee Chairpersons:
Paul Gauthier
Myrna Plum

THE
MOUNTAINEERS

© 1960, 1967, 1974, 1982, 1992 by The Mountaineers
All rights reserved

No part of this book may be reproduced in any form, or by any electronic, mechanical, or other means, without permission in writing from the publisher.

Published by The Mountaineers
1001 SW Klickitat Way, Seattle, Washington 98134

Published simultaneously in Canada by Douglas & McIntyre, Ltd., 1615 Venables Street, Vancouver, B.C. V5L 2H1

Published simultaneously in Great Britain by Swan Hill Press, 101 Longden Road, Shrewsbury SY3 9EB, England

Manufactured in the United States of America
Edited by Maureen O'Neal
Illustrations by Bob Cram, Nick Gregoric, Ross Prather, Ramona Hammerly
Cover design by Elizabeth Watson
Book layout by Barbara Bash

0 9 8 7 6
Pbk: 11 10 9 8
Cloth: 8 7 6 5

Cover photograph: Midnight on the summit of Mount McKinley, Alaska. Photo by Patrick Morrow
Frontispiece: Climbers on Vowell Pinnacle, Howser Spire in the distance, Bugaboos, Purcell Range, British Columbia. Photo by Baiba Morrow

The following trademarks appear in this book: Ball Nuts, Band-Aids, Camalots, Chevron Blazo, Clog, Coleman, Diamox, Friends, Gibbs, Gore-Tex, Hexentrics, Jumar, Kevlar, Masonite, Mylar, Polypro, Quickies, RURP, Rock 'n Rollers, RPs, Spectra, Stoddard, Stokes, Stones, Stopper, Styrofoam, Teflon, Therm-a-Rest, TCUs, Tri Cams, Velcro, and Vibram.

Library of Congress Cataloging in Publication Data

Mountaineering : the freedom of the hills / editor, Don Graydon. — 5th ed.
p. cm.
Includes bibliographical references (p.) and index.
ISBN 0-89886-201-9 — ISBN 0-89886-309-0 (pbk.)
1. Mountaineering. 2. Rock climbing. 3. Snow and ice climbing.
I. Graydon, Don. II. Mountaineers (Society)
GV200.M688 1991
796.5'22—dc20 91-26342
CIP

A NOTE ABOUT SAFETY

Safety is an important concern in all outdoor activities. No book can alert you to every hazard or anticipate the limitations of every reader. Therefore, the descriptions of equipment and techniques in this book are not representations that a particular tool or technique will be safe for you or your party. When you participate in the activities described in this book, you assume responsibility for your own safety. Keeping informed on current conditions and exercising common sense are the keys to a safe, enjoyable outing.

The Mountaineers

CONTENTS

Preface 6
Part One: Approaching the Peaks 11
1. First Steps 13
2. Clothing and Equipment 16
3. Camping and Food 36
4. Routefinding and Navigation 56
5. Wilderness Travel 79

Part Two: Climbing Fundamentals 89
6. Ropes, Knots, and Carabiners 90
7. Belaying 108
8. Rappelling 136

Part Three: Rock Climbing 155
9. Rock Climbing Technique 156
10. Leading and Placing Protection 188
11. Aid Climbing and Pitoncraft 232

Part Four: Snow and Ice Climbing 265
12. Snow Travel and Climbing 266
13. Glacier Travel and Crevasse Rescue 315
14. Ice Climbing 338
15. Winter and Expedition Climbing 372
16. Safety and Leadership 400
17. Alpine Rescue 407

Appendices 424
1. The Cycle of Snow 424
2. Rating Systems 430
3. Lightning 437
4. Supplementary Reading 439

Index 441

PREFACE

Mountaineering, the Freedom of the Hills is intended to present both introductory and advanced information on the sport of mountaineering. This fifth edition is an extensive revision of the fourth edition, the longtime, leading English-language text on mountaineering.

Each of the chapters from the fourth edition has been revised, rewritten, and, where necessary, expanded. These revisions reflect the rapid changes occurring in various areas of mountaineering and are due to increased popularity, the development of new techniques, and the introduction of new and improved equipment. Chapters considerably enhanced by these changes include: First Steps, Leading and Placing Protection, Rock Climbing Technique, Aid Climbing and Pitoncraft, and Belaying. This edition presents a completely new chapter on Winter and Expedition Climbing.

Many improvements make this edition more interesting to read, easier to use, and more accessible. A professional writer rewrote the material from all contributors, bringing the various parts and chapters together to form a comprehensive text. Additional headings clarify the topics and direct the reader to pertinent information. Completely new illustrations of techniques and equipment clearly and accurately illustrate the text. Line figure drawings were created from photographs of climbers demonstrating the precise technique.

SCOPE OF THE BOOK

As in previous editions, *Freedom* provides sound, clear, and current coverage of the concepts, techniques, and problems involved in the pursuit of mountain climbing. Individual topics, such as rock climbing technique or aid climbing, are detailed enough to be useful to readers with specific interests in those topics. The book provides a fundamental understanding of each topic. It is not intended, however, to be exhaustive or encyclopedic. In addition to presenting information for the novice, much of the material in this book can help experienced climbers review and improve their skills.

Mountaineering cannot be learned just by studying a book. *Freedom* was originally written as a textbook for students and instructors participating in organized climbing courses. The context of learning that is provided in a course of instruction, given either individually or in groups, and by competent instructors, is essential for beginning climbers.

Traditionally, climbing has been a thinking person's sport. The individual climber and climbing team bring their knowledge, skills, and experience to the problem at hand and apply their own solutions. In this fifth edition, *Freedom* presents widely used techniques and practices outlining both their advantages and limitations. It is presented not as dogma or the final word but as the basis for making sound judgments. This problem-solving approach is especially important in mountaineering because of the potential dangers that exist. Such dangers are inherently magnified by harsh conditions, insufficient skill, inexperience, and poor judgment.

Freedom characteristically describes not just simple climbing but wilderness mountaineering. Any person who becomes a wilderness mountaineer has a deep and abiding responsibility to help preserve the wilderness environment for present and future generations. Walking softly is a fair start. The mountain regions throughout the world constitute the domain of mountaineering. This dwindling and finite resource depends on the wilderness traveler for its future preservation.

ORIGINS OF THE BOOK

Freedom's direction and emphasis originated from the development of climbing in the Pacific Northwest. The wild and complex character of the mountains in this region, with their abundance of snow and glaciers throughout the year, furthered the mountaineering challenge. Access was inherently difficult. There were few roads, and the initial explorations were themselves expeditions, often with native guides.

When The Mountaineers was organized in 1906, one of its major purposes was to explore and study the mountains, forests, and watercourses of the Northwest. The journey to the mountain summit was a long and difficult one, and it required a variety of skills. With the knowledge of these skills, the competence that comes from their practice, and the experience gained through climbing mountains, more than a few had the exhilarating experience of the freedom of the hills.

As interest in mountaineering in the region grew, so did a tradition of tutelage. Increasingly, experienced climbers took novices under their wings to pass on their knowledge and skills. The Mountaineers formalized that exchange by developing a series of climbing courses. This book grew out of six decades' worth of teaching mountaineering and conducting numerous climbs in the Northwest and throughout the world.

LEGACY OF THE FIFTH EDITION

Issac Newton said, ''If I see farther than others, it is because I stood on the shoulder of giants.'' The various editions of *Freedom* represent a tradition of bringing together and sorting through the knowledge, techniques, opinions, and advice of a large number of practicing climbers. Students, both in training and on actual climbs, have been an especially pivotal source of information.

Prior to the publication of the first edition of *Freedom* in 1960, The Mountaineers climbing courses had used European works, particularly Young's classic *Mountaincraft,* as required reading. These works did not cover various subjects unique and important to American and Pacific Northwest mountaineering. To fill in the gaps, course lecturers prepared outlines, which they distributed to students. Eventually these outlines were fleshed out and gathered together as the *Climber's Notebook,* subsequently published, in 1948, as the *Mountaineers Handbook*. By 1955, tools and techniques had changed so drastically, and the courses had become so much more complex, that the new and more comprehensive textbook was needed.

Members of the first edition editorial committee were: Harvey Manning, chairman; John R. Hazle; Carl Henrikson; Nancy Bickford Miller; Thomas Miller; Franz Mohling; Rowland Tabor; and Lesley Stark Tabor. A substantial portion of the then relatively small Puget Sound climbing community participated—some seventy-five as writers of preliminary, revised, advanced, semifinal, and final chapter drafts, and another one or two hundred as reviewers, planners, illustrators, typists, proofreaders, financiers, promoters, retailers, warehousemen, and shipping clerks. At the time, there were few Mountaineer climbers who did not have a hand in making or selling the book.

Efforts leading to the publication of the second edition (in 1967) began in 1964. Members of the second edition editorial committee were: John M. Davis, chairman; Tom Hallstaff; Max Hollenbeck;

Jim Mitchell; Roger Neubauer; and Howard Stansbury. Even though much of the first edition was retained, the task force was, again, of impressive proportions, numbering several dozen writers, uncounted reviewers, and helpers. Survivors of the previous committee, notably John R. Hazle, Tom Miller, and Harvey Manning, provided continuity to the effort. As he had with the first edition, Harvey Manning once more edited the entire text and supervised production.

The third edition editorial committee was formed in 1971 and headed by Sam Fry. Initially, a planning committee analyzed the previous edition and set guidelines for its revision. A steering committee, consisting of Jim Sanford, Fred Hart, Sean Rice, Howard Stansbury, and Sam Fry, directed the revision and had overall responsibility for the text. A large number of climbers contributed to individual chapters; the reviewing, revising, editing, and collation of chapters and sections was a true community effort. Peggy Ferber edited the entire book, which was published in 1974.

The fourth edition of Freedom involved a major revision and included the complete rewrites of many chapters, most notably the entire Ice and Snow section. A cast of hundreds was guided by a team of technical editors: Ed Peters, chairman; Roger Andersen; Dave Enfield; Lee Helser; John Young; Dave Anthony; and Robert Swanson. A large number of climbers submitted comments to the committee. Small teams of "writers" prepared a series of drafts for review by the technical editors. In addition to the substantial contribution of such writers, many others provided valuable help through critiques of subsequent and final drafts not only for technical accuracy and consistency, but also for readability and comprehension.

THE FIFTH EDITION

In late 1987, climbing committee chairman Ken Small responded to concerns of The Mountaineers Books staff and initiated an effort to assess the need for a new edition. A *Freedom* Ad Hoc Study Committee was formed to make specific recommendations to the club's board of trustees. The committee reported the need for a revision of many technique sections, overall improvement in the writing quality, and an upgraded visual format. It also recommended that this revision be carried out in the tradition of a volunteer committee. Chaired by Paul Gauthier, the committee's members were Ben Arp, Steve Costie, Nancy Jackson, Tom Merritt, and Susan Price. In order to assess the current strengths and the specific needs for improvements to the fifth edition, the committee solicited the opinions of Mountaineer members and well-known climbers and writers from outside the Club. The committee is grateful for the well-thought-out responses received from Greg Child, Randall Green, Michael Loughman, Eric Perlman, Doug Robinson, and Gary Speer. Many of their suggestions were incorporated into this latest edition of the book.

The board of trustees selected Paul Gauthier to spearhead a substantial revision of the fourth edition. The committee was organized into a coordinators' group, which took on the responsibility for overall guidance, and into subcommittees for subject areas. The individual subcommittees used various methods to produce detailed narrative "outlines." These were reviewed and modified by the coordinators' group to incorporate a wide range of critique by the whole committee. Professional writer Don Graydon wrote "drafts" from these narratives, which were reviewed and revised by the committee. Graydon showed extraordinary skill in working both with a diverse committee and the Books staff and in enhancing the overall style.

The coordinator group consisted of Paul Gauthier, chairman; Ben Arp, editorial coordinator; Marty Lentz, Safety and Rescue section coordinator; Margaret Miller, Rock section coordinator; Judy Ramberg, Approaching the Peaks section coordinator; and Craig Rowley, Snow and Ice section coordinator. In 1990, Paul Gauthier moved to England, and the committee was subsequently chaired by Myrna Plum.

The Approaching the Peaks Subcommittee jointly developed five chapters with major contributors as follows: "First Steps," Bill Deter and Judi Maxwell; "Clothing and Equipment," Judy Ramberg; "Camping and Food," Judy Ramberg and Judi Maxwell; ''Routefinding and Navigation,'' Bob Burns with consultation on maps section by Stewart M. Wright; and ''Wilderness Travel,'' Judi Maxwell, Bill Deters, and Judy Ramberg.

The Fundamentals and Rock Climbing Subcommittee jointly reviewed the revisions developed by the following lead individuals: ''Ropes, Knots, and Carabiners,'' Jack E. Bennett and Larry Longley; ''Belaying,'' Allen Frees; ''Rappelling,'' Ken Small; ''Rock Climbing Technique,'' Susan Price; ''Leading and Placing Protection,'' Dan Bean; ''Aid Climbing and Pitoncraft,'' Jeff Johnson; and Rating Systems appendix, Jan Green. Cal Magnusson of REI consulted on the ''Belaying'' chapter.

The Snow and Ice Climbing Subcommittee jointly revised each of their chapters with the major contributors as follows: ''Snow Travel and Climbing,'' Kurt Hanson, Jim Cade, and Don Heck; ''Ice Climbing,'' Don Heck; ''Glacier Travel and Crevasse Rescue,'' Craig Rowley and Nancy Jackson; and ''Winter and Expedition Climbing,'' Kurt Hanson, Nancy Jackson, and Jim Cade.

The Safety and Rescue Subcommittee, with contributions by Paul Gauthier and Ben Arp, condensed and revised materials into ''Safety and Leadership,'' revision led by Marty Lentz, and the ''Alpine Rescue'' chapter, led by Pete A. Bustanoby.

As the text was reaching a final form, Books staff organized efforts to revise figures and illustrations and provide artwork and photography. The committee end of this large effort was coordinated by Marilyn O'Callaghan. Concurrently, the professional design and layout was directed by Books production and design manager Marge Mueller.

THE MOUNTAINEERS, founded in 1906, is a non-profit outdoor activity and conservation club, whose mission is ''to explore, study, preserve and enjoy the natural beauty of the outdoors....'' Based in Seattle, Washington, the club is now the third largest such organization in the United States, with 12,000 members and four branches throughout Washington State.

The Mountaineers sponsors both classes and year-round outdoor activities in the Pacific Northwest, which include hiking, mountain climbing, ski-touring, snowshoeing, bicycling, camping, kayaking and canoeing, nature study, sailing, and adventure travel. The club's conservation division supports environmental causes through educational activities, sponsoring legislation, and presenting informational programs. All club activities are led by skilled, experienced volunteers, who are dedicated to promoting safe and responsible enjoyment and preservation of the outdoors.

The Mountaineers Books, an active, non-profit publishing program of the club, produces guidebooks, instructional texts, historical works, natural history guides, and works on environmental conservation. All books produced by The Mountaineers are aimed at fulfilling the club's mission.

If you would like to participate in these organized outdoor activities or the club's programs, consider a membership in The Mountaineers. For information and an application, write or call The Mountaineers, Club Headquarters, 300 Third Avenue West, Seattle, Washington 98119; (206) 284-6310.





◆ PART ONE ◆

APPROACHING THE PEAKS

Stratocumulus front over the High Sierra, Mount Whitney region, California. Photo by Galen Rowell/Mountain Light

◆ 1 ◆

FIRST STEPS

Mountaineering is more than climbing, panoramic views, and wilderness experience. It is also challenge, risk, and hardship. And it is not for everyone. Those drawn to the mountains can find them exhilarating and irresistible, as well as frustrating and sometimes even deadly. There are qualities to mountaineering that inspire us and bring us to revel in a pursuit that is more than a pastime, more than a sport; a passion, certainly, and sometimes a compulsion.

''What was the force that impelled me?'' asks American mountaineer Fred Beckey. ''Something complex and undefinable, the attraction of uncertainty.'' British climber George Leigh Mallory, many years earlier, offered another version of mountaineering's attraction: ''What we get from this adventure,'' he said, ''is just sheer joy.''

Distant views of mountains may speak of adventure, but they seldom more than hint at the joys and hardships that await. If you want to climb mountains, be prepared for the totality of nature—storms as well as soft breezes, tangled brush as well as alpine flowers, biting insects as well as singing birds. Climbing mountains is a tough way to spend your spare time, and anyone who does it knows what Polish climber Voytek Kurtyka meant when he said that ''alpinism is the art of suffering.'' Mountaineering takes place in an environment indifferent to human needs, and not everyone is willing to pay the price in hardship for its rich physical and spiritual rewards.

FREEDOM OF THE HILLS

''Freedom of the hills'' is a concept that combines the simple joy of being in the mountains with the skill, gear, and strength to travel where we will without harm to ourselves, others, or the environment.

This book, with its roots in the mountains of the Pacific Northwest, champions this freedom by providing information for climbers of all levels, from novice to advanced. It represents the combined experiences of many climbers, who have traveled most of the major mountain ranges on earth. This does not make it gospel. Although learning from the experiences of others is valuable, time and again the student returns to instruct the teacher.

As you read, remember that new techniques and technical advances occur so frequently that any attempt to document the ''state of the art'' is quickly dated. With this caution in mind, this book can serve as your general passport to the freedom of the hills.

CARING FOR THE WILDERNESS

The beauty of wild places could be their undoing as they attract us to them—leaving them touched by human hands and eventually less than wild. We are consuming wilderness at an alarming rate, using it and changing it as we do so.

Though we sometimes act otherwise, the mountains don't exist for our amusement. They owe us nothing and they require nothing from us. Hudson Stuck wrote that he and the other members of the first party to climb Mount McKinley felt they had been granted "a privileged communion with the high places of the earth." As mountaineers traveling in the wilderness, our minimum charge for this privilege is to leave the hills as we found them, with no sign of our passing. We must study the places we visit and become sensitive to their vulnerability, then camp and climb in ways that minimize our impact.

The privileges we enjoy in the mountains bring responsibilities. Therefore, the facts of mountaineering life today include permit systems that limit access to the backcountry, road and trail closures, environmental restoration projects, legislative alerts, and the clash of competing interest groups. While we tread softly in the mountains, it's also time to speak loudly back in town for support of wilderness preservation and sensitive use of our wild lands. As mountaineers, we need to be activists as well as climbers if we want our children to be able to enjoy what we take for granted.

KNOWLEDGE AND SKILLS

As part of our passport to travel the mountains, we need the skills for safe, enjoyable passage. For our sake and the sake of everyone we climb with, we learn the tools and techniques of camping, navigation, belaying, rappelling, glacier travel, safety, rescue, and climbing on rock, snow, and ice. This book is a guide to this learning.

PHYSICAL PREPARATION

Mountaineering is a demanding activity, both physically and mentally. Rock climbing, in particular, has become increasingly athletic, especially at the higher levels of difficulty. Climbers today accomplish what was considered impossible only a few years ago. Many serious rock climbers work out at specialized gymnasiums, and the sport features international climbing competitions. In the world of alpine climbing, the highest peaks are commonly climbed without supplementary oxygen, in record times, and by more and more difficult routes. Most of us, however, appreciate such world-class performance from the sidelines. It's not necessary to devote your life to mountaineering in order to enjoy the activity at a level that provides personal satisfaction.

Levels of performance are rising even among recreational climbers and mountaineers. Good physical conditioning is one of the keys and can make the difference between enjoying an outing and merely enduring it. More important, the safety of the whole party may hinge on the strength—or weakness—of one member.

Most mountaineers train regularly. Aerobic activities such as running, cycling, swimming, cross-country skiing, snowshoeing, hiking uphill with a heavy pack, and climbing stairs are popular exercises. Many climbers lift weights to build strength and perform stretching exercises for flexibility. Specific exercises, those closest to climbing itself, are probably the best preparation. Physical fitness is the foundation for all the strenuous activities of mountaineering.

MENTAL PREPARATION

Just as important as physical conditioning, our mental attitude often determines success or failure. Once physical fitness is adequate, the "mind games" we play with ourselves are what really get us past a difficult move or help us decide to back off.

We need to be positive, realistic, and honest with ourselves. There is a personal balance required here. A "can do" attitude may turn into dangerous overconfidence if it isn't tempered with a realistic appraisal of ourselves and the situation.

Many a veteran mountaineer says the greatest challenges are mental. Perhaps this is one of mountaineering's greatest appeals: while seeking the freedom of the hills, we come face to face with ourselves.

JUDGMENT AND EXPERIENCE

This book outlines the basics of equipment and techniques and suggests how to learn from practice. But judgment, the most important of all mental qualities in climbing, develops from how we integrate our knowledge and experience.

Much of what we need are coping skills—the ability to deal with adverse weather, long hikes, thick brush, high exposure, and the like. As we endure these situations, we become better decision-makers, and the experiences we gain are useful for comparison the next time the going gets tough.

New situations, however, will still arise for which we have no trustworthy precedent. We won't be able to make an automatic, confident response, so we will have to exercise careful judgment. In this uncertainty lies much of the charm and challenge of mountaineering—as well as the potential for tragedy.

Many years ago, The Mountaineers club of Washington State devised a set of guidelines to help people conduct themselves safely in the mountains. Based on careful observation of the habits of skilled climbers and a thoughtful analysis of accidents, it has served well for not only climbers but, with slight adaptation, for all wilderness travelers. It is not inflexible doctrine, but it has proven to be a sound guide to practices that minimize risk.

A CLIMBING CODE

- A climbing party of three is the minimum, unless adequate prearranged support is available. On glaciers, a minimum of two rope teams is recommended.
- Rope up on all exposed places and for all glacier travel. Anchor all belays.
- Keep the party together, and obey the leader or majority rule.
- Never climb beyond your ability and knowledge.
- Never let judgment be overruled by desire when choosing the route or deciding whether to turn back.
- Carry the necessary clothing, food, and equipment at all times.
- Leave the trip schedule with a responsible person.
- Follow the precepts of sound mountaineering as set forth in textbooks of recognized merit.
- Behave at all times in a manner that reflects favorably upon mountaineering.

This code is by no means a step-by-step formula for reaching summits, but rather a guideline to safe and sane mountaineering. Climbers sometimes question the need for such standards for a sport in which much of the appeal lies in the absence of formal rules. But many serious accidents could have been avoided or their effects minimized if these simple principles had been followed. This climbing code is built on the premise that mountaineers want strong chances of safety and success, even in risk-filled or doubtful situations, and that they want safeguards in case they have misjudged those chances.

Experienced mountaineers often modify the code in practice, taking an independent course that combines an understanding of risk with the skill to help control it. The code is recommended especially for beginners, who have not yet developed the judgment that comes from years of experience.

If we learn to climb safely and skillfully, body and spirit in tune with the wilderness, we will be able to accept the lifetime invitation that John Muir extended to us so many years ago.

"Climb the mountains," he told us, "and get their good tidings. Nature's peace will flow into you as sunshine flows into trees. The winds will blow their own freshness into you and the storms their energy, while cares will drop off like autumn leaves."

• 2 •

CLOTHING AND EQUIPMENT

In packing for a wilderness trip, it's a simple matter of take it or leave it. The idea is to take what you need and to leave the rest at home. With thousands of choices widely available in outdoor clothing and equipment, it's no longer a question of how to find what you need, but rather of limiting your load to just the items that will keep you safe, dry, and comfortable.

To strike a balance between too much and too little, monitor what you take with you. After each trip determine what was used, what was really needed for a margin of safety, and what was not needed. As you buy equipment, go for lightweight alternatives if the weight reduction does not jeopardize the item's performance and durability. Whenever possible, look for versatile equipment you can use for several purposes.

If you're new to mountaineering, you don't have the experience yet to know what works best for you. So don't buy all your basic gear right away. Take it one trip at a time, one purchase at a time. Whether it's boots, packs, or sleeping bags, wait until you have enough experience to make intelligent decisions before spending your money. Rent, borrow, or improvise during your early outings until you learn what you need and what you don't need. Get advice by talking to seasoned hikers and climbers, by window-shopping at outdoors stores, and by reading mountaineering magazines.

This chapter is one useful source of information on basic wilderness gear, including guidelines on what constitutes good equipment. It won't tell you what brands to purchase, but it will help you find high-quality items among those thousands of choices.

FOOTGEAR

BOOTS

Not many years ago almost all boots were made of leather, but some modern materials have certain performance advantages. Plastic boots and lightweight hiking boots have now joined the classic leather boot as common footgear for wilderness travelers, although leather is still the first choice for general-purpose mountaineering.

Leather boots

A general mountaineering boot is a compromise between conflicting requirements. It should be tough enough to withstand the scraping of rocks, stiff and solid enough for kicking steps in hard snow, yet comfortable enough for the approach hike. In a single day of climbing, the boots may have to contend with streams, mud, logs, brush, scree, hard snow, and steep rock.

The classic leather mountaineering boot (fig. 2-1) has the following features: high uppers ($5^1/_2$ to $7^1/_2$ inches) to protect the ankles in rough terrain; Vibram-type soles for traction on slippery vegetation, mud, and snow; midsoles for insulation and shock absorption; and a semi-rigid shank.

The length and rigidity of a boot's shank (fig.



Fig. 2–1. A classic leather mountaineering boot

2-2) is a much-debated topic. The ideal length depends on how the boot will be used. For hiking, easy snow climbs, and rock routes, choose a boot with a half-length nylon or fiberglass shank, which keeps the sole reasonably flexible. Boots used primarily for technical ice climbing or difficult mountain routes benefit from being made of plastic or having a full-length shank. The rigid plastic or full-length shank impairs walking but greatly reduces leg fatigue when front-pointing with crampons or standing on small rock nubbins.



Fig. 2–2. The shank length determines the flexibility of the boot sole: a, full-length shank boot; b, half-length shank boot.

The sole of the boot should be attached to the uppers by means of a durable method of stitching, with the Norwegian welt (fig. 2-3) considered the longest lasting. The welt should be narrw (fig.


a
Upper
Welt
Insole
Filler/
midsoles
Rubber lug
b
Upper
Welt
Insole
Shank
Filler
Cemented midsole
Rubber lug
Stitching
c
Upper
Stitching
Insole
Rubber lug
Midsoles
d
Upper
Insole
Cemented layer
Rubber lug

Fig. 2–3. Four common methods of boot construction: a, Goodyear welt; b, Norwegian welt; c, Littleway; d, cemented.



Fig. 2–4. A narrow-welt boot works well on small footholds.

2-4) to prevent it from bending on small holds.

Other desirable boot features include the following:

- Tops that open wide so that even when the boots are frozen or wet, they can be put on easily.
- A minimum number of seams, to decrease the places water can leak through.
- A gusseted tongue, or a bellows tongue, to keep water from easily entering the boot.
- Double- or triple-layered leather or fabric at areas of high wear (toes and heels).
- Hard toe counters (stiffeners) built in to protect the feet, reduce compression caused by crampon straps, and facilitate kicking of steps in hard snow.
- Hard heel counters (stiffeners) built in to increase foot stability and facilitate plunge-stepping down steep snow slopes.

Lightweight hiking boots

Improvements in boot technology have led to evolution of the medium- and lightweight hiking boot (fig. 2-5). Made of leather and nylon, these boots weigh one-third to one-half as much as traditional boots, yet are sturdy enough for three-season trekking on moderate terrain. The uppers of these boots typically are glued to the sole, eliminating the need for a welt. Check that the boots are high enough for ankle protection, that a stiff counter wraps the heel and toe, and that abrasion areas are reinforced.

Advantages of lightweight boots include reduced cost, increased breathability, improved comfort, shorter break-in time, and faster drying. However, they are not as durable and cannot be made as waterproof as leather boots, and they lack the weight and stiffness for kicking steps in firm snow. On difficult off-trail terrain and on snow, leather boots are still preferred.



Fig. 2–5. Lightweight trail boots: a, leather; b, synthetic.

Plastic boots

Plastic boots (fig. 2-6), originally designed for technical ice climbing, have found a much wider market among general mountaineers interested in snow routes or winter climbing. The plastic shell of the boot is waterproof, so the inner insulating boot remains dry and keeps your feet warm. This inner boot can be removed, which helps in drying out perspiration.

Plastic boots need to fit well from the start because their rigid shape will not mold around your feet over time. The boot's relative rigidity and its



Fig. 2–6. Plastic boot: a, waterproof shell; b, insulating inner boot.

high degree of warmth makes it a poor choice for general trail use. When fitting plastic boots, make sure that they do not constrict the feet. Feet swell at high altitude, and plastic boots are frequently used for high-altitude expeditions.

The proper fit

Whether you're looking at leather, plastic, or lightweight boots, the fit is critical. Try on several makes and styles, with socks similar to the ones you will wear on a climb. Be sure to bring along any orthotic devices, insoles, or other inserts you plan to use. Wear the boots in the store for several minutes to give your socks time to compress around your feet. Then note whether the boots have any uncomfortable seams or creases and whether they pinch against your foot or Achilles' tendon. In properly fitting boots, your heels will feel firmly anchored in place while your toes will have plenty of room to wiggle and will not jam against the toe box when you press forward. Boots that are too tight constrict circulation, causing cold feet and increased susceptibility to frostbite. Loose boots, on the other hand, cause blisters.

Most people's feet swell during the course of the day, so consider buying boots in the evening for the best fit. Given the choice between boots that are a hair too big and ones that are a bit too small, go with the larger boots. You can fill the space with a thicker sock, and most boots can shrink as much as a half size over time (because the toe of a boot has a tendency to curl).

Boot care

With proper care, good boots can last several years. Keep mildew at bay by washing the boots frequently. After washing, stuff them with a boot tree or newspaper, and dry them in a warm (not hot), ventilated area. Heat can damage the welt and the adhesive used on boot soles. Avoid drying or storing boots at high temperatures: the boots dried over a campfire are likely to be the ones that fall apart on a future trip. Boot soles usually wear out long before the uppers. High-quality boots can be resoled, although this may change the original fit because new soles tighten the size somewhat.

During an outing, water can get into boots over the top and through the leather and seams. Wearing gaiters keeps water from running into boots from the top. Waterproofing agents applied to the leather and seams stop water from going through the boots.

With new boots, treat the welt first with one of the waterproofing products designed for this purpose. It's a process that needs to be repeated periodically. Boots must be clean and dry, with any wax removed. Apply the material directly to the threads and stitching holes, and let it dry before applying waterproofing to the rest of the boot. Some boot makers use waterproof rubber rands to seal the welt, a desirable feature that simplifies boot maintenance and keeps your feet drier.

Apply waterproofing to the boots a day or two before a trip to give the agents time to penetrate the leather. The makeup of the waterproofing used on leather uppers depends on how the leather was tanned, so follow the manufacturer's recommendations. The nylon in many lightweight boots is difficult to seal completely, but you can make it more water resistant by applying silicone-based sprays. Whatever you use on your boots, apply it frequently if you expect your feet to stay dry.

After using plastic boots, remove the inner boots and clean them with mild soap and water. Remove any debris from inside the plastic shells to prevent abrasion and excessive wear between the outer and inner boots.

Specialized footwear

Depending on the trip, a climber may wear one kind of boot for the approach hike, another type of footwear in camp, and yet another on the climb. If you can afford additional footgear and are willing to carry the extra weight, consider these options:

- Lightweight, flexible trail shoes for long trails, easy approaches, stream crossings, and for wearing in camp. They are less likely to cause blisters and are less fatiguing to wear. (The rule of thumb is that 1 pound of weight strapped to the foot is comparable to 5 on the back.) However, these lightweight shoes may not provide the support you need when carrying a heavy pack.

- Camp footwear (booties for comfort and warmer sleeping; running or tennis shoes, or sandals, for comfort and to give boots a chance to dry).
- Lightweight nylon-mesh socks for camp use and stream crossings. They are very light, have waffled soles for traction, and dry fast, but give no support.
- Special rock-climbing shoes for technical rock (see Chapter 9 for details).
- Full-shank boots that you can use with rigid crampons for ice climbing.

SOCKS

Socks cushion and insulate your feet, absorb perspiration, and reduce friction between the boot and the foot. Socks made of wool or synthetic materials can perform all these functions, while those made of cotton cannot. Cotton absorbs too much water, which destroys its insulating qualities and increases friction between the boot and the foot.

Most climbers wear two pairs of socks. Next to the skin, a smooth polyester or polypropylene sock transports perspiration from the foot to the outer sock. Over this goes a heavier, rougher sock made of wool or synthetics.

Of course there are many exceptions. A rock climber wants flexible rock shoes to fit like a glove, and so usually wears only one thin pair of socks. A hiker using trail shoes on a warm day keeps feet cooler by wearing just a single pair of socks, while a winter climber may wear three pairs of socks inside oversized boots. Always keep your toes free enough to wiggle. Three pairs of socks give less protection from the cold than two if the last pair constricts circulation.

Before donning socks, consider putting protective moleskin or tape on your feet at places prone to blisters, such as the back of the heel. Moleskin is especially valuable when breaking in new boots or early in the climbing season before your feet have toughened up. Another blister fighter is foot powder sprinkled on your socks and in your boots.

On expeditions or in cold weather, a vapor-barrier sock may be worn between the two main sock layers. Vapor-barrier liners keep moisture next to your foot and prevent perspiration from wetting your thick socks. They also keep your feet warmer by inhibiting the evaporation of sweat. In subfreezing temperatures, these socks reduce the danger of frostbite, but over time the moisture that is kept inside can result in trench foot—a serious problem. If you use vapor-barrier socks, dry your feet thoroughly at least once each day.

Insoles added to the inside of your boots provide extra insulation and cushioning. Synthetic insoles are non-absorbent, do not become matted when damp, and have a loose structure that helps ventilate your foot. Insoles made of felt, leather, and lambskin all absorb moisture and must be removed when drying boots. When trying on new boots, be sure to insert the insoles you intend to wear.

CLOTHING

Humans maintain body comfort by creating a microenvironment of warm air next to the skin. Combinations of cold temperatures, rain, and wind remove this warm air and can initiate a dangerous reduction in body temperature. If left unchecked, this condition, known as hypothermia, leads to uncontrolled shivering, loss of judgment, and eventually death.

Clothing protects you from the cold, wind, and wet and maintains a compatible environment next to your skin. Clothing also must help cool you when conditions become too hot. Over-exertion or excessive temperatures can cause the improperly clothed body to suffer heat exhaustion—an affliction that can be just as deadly as hypothermia.

LAYERING

Clothing maintains the body's microenvironment best when it is worn in multiple layers, letting you adapt easily to the fluctuating temperatures in the mountains. To keep pace with changing conditions, add or subtract layers of clothing one by one.

Three levels form the basis of this clothing system: a layer next to the skin, insulating layers, and an outer protective layer.

The layer next to the skin (long underwear) allows for ventilation so the body can cool itself. During the warmer parts of a day, many climbers wear just their long underwear and a pair of shorts. When it's cold, long underwear, covered by additional clothing, increases your insulation. This layer also transports perspiration away from your skin without absorbing the moisture. (Wet garments in contact with your skin draw away twenty-five times more heat than dry ones.)

The insulating layers (shirts, sweaters, pile coats) trap warm air next to the body. The thicker the layer of trapped or "dead" air, the warmer you'll be. However, several light, loosely fitting layers are usually warmer than one thick garment. They are also more versatile because the various pieces can be worn in different combinations depending on the temperature and your level of exertion.

The outer protective layer is essential for minimizing heat loss from wind and rain. Wind stirs up the warm air next to the body and blows it away, a process known as convection. The stronger the wind, the faster heat is blown away, producing a wind-chill effect that makes it feel much colder. When the air temperature is 10 degrees Fahrenheit, a 20-mile-per-hour wind produces a wind-chill effect (fig. 2-7) that is equivalent to –25 degrees. Rain dampens clothing and reduces its insulating

Fig. 2–7. Wind-chill chart

Wind Speed MPH	Temperature (°F)										
	50	40	30	20	10	0	-10	-20	-30	-40	-50
	Equivalent Chill Temperature										
Calm	50	40	30	20	10	0	-10	-20	-30	-40	-50
5	48	37	27	16	6	-5	-15	-26	-36	-47	-57
10	40	28	16	4	-9	-21	-33	-46	-58	-70	-83
15	36	22	9	-5	-18	-36	-45	-58	-72	-85	-99
20	32	18	4	-10	-25	-39	-53	-67	-82	-96	-110
25	30	16	0	-15	-29	-44	-59	-74	-88	-104	-118
30	28	13	-2	-18	-33	-48	-63	-79	-94	-109	-125
35	27	11	-4	-20	-35	-49	-67	-83	-98	-113	-129
40	26	10	-6	-21	-37	-53	-69	-85	-100	-116	-132
above 40	little additional effect										
Danger of Freezing Exposed Flesh if Dry and Properly Clothed:	Little Danger				Great			Extreme			

To use this table, which illustrates the intensely chilling effect of wind, find wind speed (in miles per hour) in left-hand column and temperature (in degrees F) in top row; the intersection of these is the equivalent temperature. For example, at a temperature of 0°F a breeze 15 mph has the cooling effect of a temperature of –36° on a calm day and precautions should be taken to protect exposed flesh from frostbite. The zones shown on the table indicate the danger of frostbite to any exposed flesh of an average person in good condition whose body is properly clothed for the conditions. When the effective temperature is –25°F or less, care should be taken to minimize exposure of bare skin to wind.

value, and wet clothing conducts heat from the body at an alarming rate. A waterproof shell over your insulating layers eliminates heat loss from conduction and convection. Wind cannot penetrate the shell, so warm air next to your body stays put. The shell also keeps the insulating layers drier so that body heat is not conducted away.

FABRICS

Clothing for the outdoors is made from a variety of fabrics, each with advantages and disadvantages.

Cotton is comfortable to wear when dry but absorbs many times its weight in water and loses its insulating qualities when wet. Because it absorbs so much water, it takes a long time to dry. In hot weather, however, cotton ventilates well and helps cool the body. Wet it down on a hot day, and the water evaporating from the cotton will cool you off.

Silk readily absorbs water, but not as much as cotton, so it dries faster. Silk is also useful in hot weather. Wetted down, it helps cool the body through evaporation.

Wool is far less absorbent than cotton, so it holds less water when wet. Consequently, it does not conduct away as much body heat and requires far less heat to dry. Wool is also warmer when wet because it does not collapse and therefore retains much of its dead-air space.

Synthetic pile does not absorb any water. Some moisture is held in suspension between the filaments of the fabric when it is wet, but most of the water can be wrung out. Garments made from synthetic pile are comparatively warm when wet, and they dry fast. Pile is also very light and fluffy so that, ounce for ounce, it traps more dead air than natural fibers like wool. All these features contribute to make pile a versatile and effective insulating material.

Polyester, acrylic, and polypropylene fabrics are used for a variety of long underwear and insulating garments. The synthetic filaments in these fabrics are also lightweight, non-absorbent, and quick drying. The filaments of some are also very good at transporting perspiration away from the body, making them well suited for use next to the skin. More and more fabrics are being designed to do this, and these fabrics have largely replaced wool, cotton, and silk for use in long underwear. When selecting items of clothing, consult the tags on individual garments or get help from a salesperson.

Down is still, ounce for ounce, the warmest insulation available. It is also the most compressible, so it packs away small yet quickly regains its loft—and therefore its warmth—when unpacked. These qualities make down an excellent insulator for cold-weather use. Unfortunately, down loses all its insulating value when wet and is almost impossible to dry in the mountains, making it a poor insulator in wet climates.

Spun synthetic filaments do not collapse when wet, as down does. Therefore they make excellent insulation for coats and sleeping bags used in moist climates. Although cheaper and more easily cleaned than down, they are not as warm, weigh more, and are less compressible. The useful life of synthetics is much shorter than down.

Nylon shells, which go over the insulating layers, give protection from the wind but are not waterproof unless the nylon is coated. Typically, polyurethane coatings are used to waterproof nylon. The thickness of the coating is measured by its weight per square yard, and a 1-ounce coating is the minimum weight you should consider. Polyurethane coatings are lightweight and effective when cared for but are not very resistant to abrasion or mildew, so some climbers prefer shells coated with synthetic rubber. These shells are more durable, but most rubber-coated raingear is too heavy for mountaineering.

Although most coatings keep rain out, they also seal sweat in. If you're working hard, the sweat generated can dampen your insulation from within. Microporous coatings were designed to attack this problem. These coatings have billions of microscopic holes per square inch. Moisture vapor from your skin has a much smaller molecular size than liquid water. The holes in the coating are large enough to let vapor escape but too small for liquid water to get in, so the coating breathes but is still waterproof. Gore-Tex, the first waterproof/breathable fabric on the market, works on the same theory but, rather than using a honeycombed coating, a Teflon film with microscopic holes is laminated to the inside of the nylon shell.

Many climbers see the waterproof/breathables as an improvement over the old-style coated nylons, but the new-generation materials are not perfect. If you work hard, you will exceed the garment's ability to blow off steam, and sweat will condense inside the shell. Once in liquid form, the sweat can no longer escape through the garment. Ventilating the garment helps keep you from overheating and building up perspiration. Most waterproof/breathables need maintenance. When water stops beading and rolling off the surface, the material should be washed, rinsed, dried, and treated with silicone or another waterproofing spray. Apply the spray generously three times over the course of three days.

HEADGEAR

When the rest of the body is covered in clothing, an unprotected head is like a radiator that accounts for more than half of the body's heat loss. The head is the first part of the body to uncover when you're overheated, and the first part to cover when you're cold. The old adage says "If your feet are cold, put on a hat." There's some truth to this because as the head and trunk get cold, the body reduces blood flow to the arms and legs in an attempt to warm vital areas. To increase blood flow back to the arms and legs, you need to warm the vital head and torso areas.

Climbers usually carry several different types of hats. Cotton glacier hats and baseball caps are popular for sun protection. A bandanna can be draped from a hat to help shade your neck, ears, and face, or it can be dipped in water and tied around your head to cool you on a hot day. A lightweight rain hat is useful for warm-weather trips because it keeps your head dry while allowing ventilation at the neck of your rain parka.

Warm insulating caps of wool, polypropylene, or pile are standard for cold weather. Consider carrying two hats, because an extra hat affords almost as much warmth as an extra sweater but weighs much less. Warm hats should also be part of your summer wardrobe in case of a forced bivouac. Balaclavas are versatile insulating hats. Rolled down, they protect the face and neck from the cold; rolled up, they warm the head but allow ventilation of the upper body through the neck area.

THE UPPER BODY

Long underwear

Protection of the torso begins with appropriate underwear. Synthetics like polypropylene and polyester are currently the best fabrics for this purpose. They are soft, stretchy, ventilate well, and wick moisture away from the skin. The underwear comes in a variety of weights, and you can choose which suits your climate and metabolism.

It's smart to buy light-colored long underwear. Light colors absorb *and* radiate heat more slowly. If it is warm enough to strip down to your underwear, you will appreciate having a white rather than black or dark blue shirt exposed to the sun.

Insulating layers

In hot weather a thin cotton shirt will keep you comfortable and serve as a first line of defense against sunburn. Stick to light colors. In cold weather you'll carry several insulating layers for your torso. Shirts and sweaters should be made of wool or synthetics, such as pile, so they still provide warmth if they get wet. Cotton sweatshirts are useless once wet, so don't bring them.

Shirts and sweaters should be long in the torso so they tuck into or pull over the waist of the pants. Gaps between the pants and upper body let valuable heat escape. Similarly, turtleneck sweaters can keep much of the torso's heat from escaping. Tests show that the addition of a turtleneck alone can increase a garment's comfort level by 5 to 10 degrees Fahrenheit.

Jackets insulated with down or synthetic fills are not usually needed on summer trips but are valuable in cold climates and for winter travel. These jackets, weighing between 2 and 3 pounds, are seldom worn while climbing but are needed for emergencies, bivouacs, and the cold hours in camp.

Rain and wind protection

On top of everything comes a shell of nylon or other synthetic material as an outer layer to provide protection from rain and wind. The ideal shell is uninsulated, windproof, waterproof, and breathable. Another option is to carry both a lightweight, unlined nylon windshirt and a coated rain parka. The breathable wind shirt (which won't be completely windproof) will reduce heat lost to the wind yet let sweat pass out of your clothing. The raincoat goes on when the dampness caused by precipitation exceeds the dampness caused by perspiration.

Many of the qualities you should look for in a good rain parka (fig. 2-8)are the same whether or not the fabric breathes.

- A size large enough to allow for additional layers of clothing underneath without compressing your insulation or restricting your movement.
- A hood with a brim, neck flap, and good drawstring to keep water from dribbling down your face and neck. The hood should be large enough to accommodate a hat (or climbing helmet) and should not impair vision when you glance to the side.
- Seams sealed at the factory with tape. Check that the tape has bonded well to the coat. All seams need to be sealed to prevent moisture from entering along the stitching, and it's preferable to have factory-sealed seams rather than trying to seal them later yourself.
- Zippers with large, durable teeth and good flaps that keep the zipper dry.
- Pockets that are easily accessible with gloved hands and with a pack on. Pockets also need good rain flaps that keep water out.
- A coat length that extends below the hips, and a drawstring at the waist that allows you to seal off the bottom of the coat.
- Sleeves that cover the wrists. Snaps, elastic, or Velcro should keep the sleeve in place at the wrist.
- Ventilation: controllable openings at the front, waist, underarms, sides, and cuffs that allow you to open up for ventilation or shut tight for trapping warm air next to your body.

Some climbers prefer anoraks, a pullover jacket with no front zipper, to standard rain parkas. The front zipper of a standard parka helps ventilation but can also leak, jam, or break. Cagoules (knee-length anoraks) are an option preferred by a few climbers. Ponchos, used by many hikers, are nearly useless in the wind and are not viable rain protection in the high mountains.



Fig. 2–8. Rain parkas: a, anorak (pullover parka); b, standard (zip-front parka).

THE LOWER BODY

Long underwear

Winter travel and cold alpine conditions call for long underwear, made of polypropylene, other synthetic material, or wool. Under these conditions, long underwear is not optional clothing, but an integral part of the layering system. The convenience and versatility of layering is compromised if a climber faced with a sudden storm has to strip to the skin to put on long underwear. Like your long underwear top, the bottoms should go on first and come off last. It is your heavier insulating pants that should be taken on or off as necessary. Down or synthetic pile underwear can also be carried and worn as outer wear during a bivouac. Synthetic briefs are an alternative to cotton.

Pants

Your insulating pants should be loose fitting for freedom of movement and made of a closely woven fabric with a hard finish so that it's resistant to wind and abrasion. Wool and wool/polyester blends work well. In cool, wet climates, synthetic pile is another good choice because it retains most of its insulating qualities when wet. Pile is not wind resistant, but a nylon shell, integral to the pants or separate, will remedy the problem.

To help layer your lower-body clothing, look for pants with full-length zippers that allow you to put the pants on while wearing boots. The life of your pants can be extended by reinforcing the seat and knees with patches of nylon or other durable fabrics.

Some climbers prefer knickers to long pants because knickers give better freedom of movement. By opening the leg straps and rolling down the socks, you can ventilate the knickers better than standard pants. Shorts are handy for hiking in the rain and for stream crossings, letting you keep your long pants dry inside the pack. Nylon shorts or gym pants worn over long underwear bottoms make a good summertime combination when shorts alone give inadequate protection against wind or cooler temperatures.

Wind and rain protection

Wind and rain pants should parallel your solution for protecting the upper half of your body. A pair of waterproof/breathable pants is one solution. Here again, full-length zippers are convenient. The zippers also help you ventilate the pants. An alternative to the waterproof/breathable fabrics is to carry both lightweight nylon wind pants and a pair of coated, non-breathable rain pants. Don the wind pants in blustery conditions, and the rain pants when it is raining hard.

Waterproof rain chaps are another outer covering for the legs, though they are now seen less and less frequently. Chaps protect the pant legs from rain, while the uncovered seat is protected by a long parka or cagoule. The system saves weight and improves ventilation but is more likely to fail in severe conditions, such as bushwhacking through wet brush or walking in blowing snow.

Some climbers use bibs made from waterproof/breathable fabrics and held up with suspenders. Bibs are best suited to winter snow and ice climbs, ski mountaineering, and cold-weather expeditions. They are considerably warmer than rain pants because they cover much of the torso and keep snow from melting around the waistline, but they are too warm for most summer uses.

Gaiters

The boundary between your trousers and boots is protected by gaiters (fig. 2-9). Climbers often carry gaiters both summer and winter to prevent wet brush, mud, or snow from saturating pant cuffs, socks, and boots. Gaiters are usually made from nylon packcloth and close with snaps, zippers, and/or Velcro. A cord running under the foot from one side of the gaiter to the other helps the gaiter hug your boot, while a drawstring at the top keeps the gaiter from sliding down. A tight fit around the boot is essential to prevent snow from entering underneath the gaiter. A tight fit also helps prevent catching your crampon points on the gaiters.

Short gaiters, those extending 5 or 6 inches over the top of the boot, are adequate for keeping corn



Fig. 2–9. Gaiters: a, short length; b, full length; c, supergaiter.

snow and gravel out of your boots in summer. The deep snows of winter, however, usually call for long gaiters that extend up over the calf.

The portion of the gaiter covering the boot should be made of coated nylon. The upper portion of long gaiters should be made of a waterproof/breathable fabric or an uncoated nylon so that the legs can breathe. Zippers are the usual failure point of a gaiter. Make sure yours are heavy-duty with large teeth. A flap that closes with snaps or Velcro protects the zipper from damage and can keep the gaiter closed and make it functional even if the zipper breaks.

The strap under the foot will wear out during the life of the gaiter. Neoprene straps work well in snow but wear quickly on rock, while heavy cord survives rock better but sometimes balls up with snow. Whatever you use, be sure the gaiter strap is designed for easy replacement.

Supergaiters completely cover the boot from the welt up but leave the lug soles exposed for good traction. Insulation built into these gaiters covers the boots and reduces the chance of frostbite during cold-weather climbs.

HANDS

Mittens are warmer than gloves because they allow your fingers to snuggle together and share warmth. A pair of synthetic pile or heavy wool mittens worn inside waterproof overmitts is fine for most non-technical climbs. Pile mitts can be wrung out when soaking wet and retain most of their insulating loft. Wool is not quite as effective once wet, so carry an extra pair of inner mitts (in a pinch, socks will work). Get inner mitts that cover the wrist.

Outer mitts can be made of a waterproof or waterproof/breathable nylon on the palm side. An increasing number of manufacturers use a non-slip coating on the palm to improve the climber's ability to grip ice tools. The backhand side of the overmitt should breathe, so choose a style that uses waterproof/breathable fabric. The overmitt should overlap the parka sleeve some 4 to 6 inches, and elastic or Velcro closures can cinch the overmitt around the forearm.

To prevent losing your mittens and overmitts, it's a good idea to sew on security cords (unless yours came so equipped). You'll find it's well worth the effort, especially when you need bare hands for snow or rock climbing, or if you take the mittens off in a high wind.

Many climbers wear polypropylene glove liners or a thin pair of fingerless gloves inside their mitts. Both give excellent dexterity for delicate chores. In very cold temperatures (around 0 degrees Fahrenheit, or −18 degrees Celsius), the polypropylene liners are better at keeping exposed flesh from freezing to metal. Fingerless gloves give slightly better dexterity and are preferred for cold-weather rock climbing when you don't want a layer of fabric between your fingers and the rock. You can buy fingerless gloves or make your own by cutting the fingers off a pair of army-surplus wool gloves.

Thin leather gloves are important for safety when rappelling or managing a hip belay because they prevent rope burns that could cause you to release the rope. These gloves are difficult to waterproof and they soak up water, so don't rely on them for warmth.

PACKS

Climbers usually own at least two packs: a rucksack to hold enough paraphernalia for a day climb and a large-capacity pack to carry the necessities for multiday trips. All packs should allow you to carry weight close to your body and center the load over your hips and legs.

INTERNAL AND EXTERNAL FRAMES

Soft packs with internal frames (fig. 2-10) that help maintain the pack's shape and transfer weight to the hips are by far the most popular packs among climbers and ski mountaineers. These packs allow the weight to be carried lower, and they do a better job of hugging the back. Internal frame packs are designed to move with you, while external frame packs tend to shift suddenly as you climb or ski. The sudden movement of 40 pounds or so can easily make you lose your balance.

The volume of most internal frame packs is easy to adjust. Most have compression straps so that the large-capacity pack used to approach a peak can be transformed into a compact, closely fitting summit pack. The clean, narrow profile of internal frame packs allows them to be hauled up rock pitches or taken through heavy brush with far fewer snags than external frame packs.

External frame packs (fig. 2-10) use a long rigid frame that is held away from the back by taut nylon



Fig. 2–10. Packs: a, small internal frame summit pack; b, large internal frame pack with padded hip band; c, external frame pack with padded hip band.

back bands. These packs provide excellent weight distribution by allowing the load to be carried high over the hips. This design lets the hips—not just the shoulders and back—share in the heavy work. Because the frame is held away from the back, these packs keep you cooler. External frame packs were designed for trail use and do a better job here than most internal frame packs. Some climbers use them for long, easy approaches and carry a small day pack for the summit day.

BUYING AN INTERNAL FRAME PACK

First and foremost, buy a pack that fits. The pack's adjustment range must be compatible with your back size, extending from the top of your sacrum to the top of your shoulders. Some packs adjust to a wide range of sizes, others don't.

Before buying a pack, loosen all the adjustments and load it up. Without a typical load, you can't tell how the pack rides or if the adjustments provide a good fit. Now put it on. The frame should follow the curve of your back. If it doesn't, can the stays or frame be bent so it does? The shoulder straps should attach to the pack about 2 or 3 inches below the crest of your shoulders and leave little or no gap behind your back. Check that the load-lifter straps work. These straps transfer weight between the shoulders and hips, allowing different muscle groups to share in the work.

Once the pack is adjusted to your liking, check the head clearance. Can you look up without hitting your head on the frame or top pocket? Can you look up if you're wearing a helmet? Next check for adequate padding wherever the pack touches your body. Pay particular attention to the thickness and quality of padding used in the shoulder straps and hip belt. Padding in the hip belt should extend beyond the hip bone. See that the hip belt goes around the top of the hip and not around the waist, because you want the bone structure of the hips to carry the weight of the pack.

Decide what capacity is right for your intended uses. A rucksack for day climbs and lightweight overnight trips usually has a capacity between 1,800 and 2,200 cubic inches. Longer trips and winter climbs require a pack with a capacity between 3,500 and 5,000 cubic inches.

Here are some additional questions to ask when shopping for a pack:

- Does it have a double bottom? This feature will greatly extend its life.
- Does the pack have haul loops and ice axe loops?
- Is there a means of increasing the pack's capacity for extended trips, such as an expandable snow skirt and an adjustable top pocket that will slide higher?
- Are there compression straps to reduce the pack's volume or to prevent the load from shifting while climbing or skiing?
- Does the pack offer a convenient way to carry crampons, skis, snowshoes, and other items?
- Are removable side pockets available? This feature can help convert a day pack into a weekender.
- Does the pack have a sternum strap, which will help keep the pack from shifting on difficult terrain?
- If you will be using the pack for technical climbs or in thick brush, does it have a smooth profile so it will not get hung up?
- Is the pack cloth durable enough for the activities you have in mind?
- How waterproof is the pack?
- Does the pack have load-restraining zippers? If the zippers fail, can you still use the pack?

TIPS ON PACKING

Packs constructed from waterproof materials are not necessarily waterproof. They can leak through seams, zippers, pockets, the top opening, and places where the coating has worn off. Individual plastic bags or good stuff sacks can protect the contents. You can use a large plastic bag as a liner, storing dry items inside the liner and wet clothing between the liner and the sides of the pack.

A climbing pack should allow you to carry the load closer to the pelvic area, the body's center of rotation. This prevents the pack's weight from shifting on the shoulders. On trails, however, the load should be carried high and close to the back.

ESSENTIAL EQUIPMENT

There is a selection of small but critical items that deserve a place in almost every pack. You won't use every one of these items on every trip, but they can be lifesavers in an emergency, insurance against the unexpected.

Exactly how much "insurance" you should carry is a matter of debate. Some respected minimalists argue that weighing down your pack with insurance items causes you to climb slower, making it more likely you'll get caught by a storm or nightfall and be forced to bivouac. "Don't carry bivy gear unless you plan to bivy," they argue.

The majority of climbers, however, take along carefully selected safety items to survive the unexpected. They sacrifice some speed but argue they will always be around tomorrow to attempt again what they failed to climb today.

The special items most climbers believe should always be with you have become known as the Ten Essentials. They are:

1. Map
2. Compass
3. Flashlight/headlamp, with spare bulbs and batteries
4. Extra food
5. Extra clothing
6. Sunglasses
7. First-aid supplies
8. Pocket knife
9. Matches, in waterproof container
10. Fire starter

Other critical items often join the list of essential equipment, depending on the trip. We will take a look at the Ten Essentials and at a number of these additional items in the sections that follow.

THE TEN ESSENTIALS

1. Map

Always carry a detailed map of the area you are visiting, in a protective case or plastic covering. (Chapter 4 gives details about maps, including how to interpret those all-important topographic maps.)

2. Compass

A compass is an essential tool of navigation and routefinding. (Chapter 4 explains the workings of a compass and describes how to use another navigation instrument, the altimeter.)

3. Flashlight/headlamp

Headlamps (fig. 2-11) and hand-held flashlights are important enough and temperamental enough to make it worthwhile to invest in only quality equipment. Waterproof flashlights are worth the added expense. They function reliably in all weather, and the contacts or batteries won't corrode even if stored in a moist garage for months.



Fig. 2–11. Examples of headlamps

Few headlamps are waterproof, but some are more water-resistant than others. If you decide that a truly waterproof headlamp is important, start by buying a small waterproof flashlight. Sew a wide length of elastic into a headband, then sew several small retaining loops of thinner elastic onto the headband to hold the flashlight in place. The flashlight will be held on the side of your head, much like a pencil resting on top of your ear.

All lights need durable switches that cannot turn on accidentally in the pack, a common and potentially serious problem. Switches tucked away in a recessed cavity are excellent. So are rotating switches in which the body of the flashlight must be twisted a half turn. If it looks like your light switch could be tripped accidentally, guard against this danger by taping the switch closed or removing the bulb or reversing the batteries.

Adjustable focus is an excellent feature available on some lights. The reflector rotates so that the lamp gives flood lighting for chores close at hand or spot lighting for viewing objects far away. Adjustable focus permits maximum use of your light, often letting you see farther and accomplish more than a brighter light lacking this feature.

Flashlight bulbs don't last long, so carry spare bulbs in addition to spare batteries. You don't have to stick with the bulb that comes with your light. If it's a vacuum bulb, you can get a brighter beam with a replacement bulb filled with a gas, such as halogen, krypton, or xenon. These gases allow filaments to burn hotter and brighter than in vacuum bulbs, though they also draw more current (amperage) and shorten battery life.

Most bulbs have their amperage requirement marked on the base. You can get a rough idea of battery life by dividing the bulb's amperage figure into the amp/hours assigned to the batteries. For example, batteries rated at 4 amp/hours will burn about 8 hours with a .5-amp bulb.

It's a good idea to carry bulbs drawing different amperages. Conserve batteries by using low-amperage bulbs for tasks around camp. Switch over to high-amperage bulbs when you need a brighter beam.

Alkaline batteries are the best general-purpose batteries commonly available at mass merchandisers. They pack more energy than cheaper lead-zinc batteries. The major problems with alkalines are that voltage (hence brightness) drops significantly as they discharge, they can't be recharged, and their life is drastically shortened by cold temperatures (they operate at only 10 to 20 percent efficiency at 0 degrees Fahrenheit).

Nickel-cadmium batteries (nicads) can be recharged up to a thousand times, maintain their voltage and brightness throughout most of their discharge, and function well in the cold (about 70 percent efficient at 0 degrees Fahrenheit). However, they don't store as much energy as alkalines. For climbing, look for high-capacity nicads, which pack two to three times the charge of standard nicads and are worth the added expense.

Lithium batteries have twice the voltage of regular batteries, so you'll need to rewire your light to run off half as many batteries. But one lithium cell packs more than twice the amp/hours of two alkalines. The voltage remains almost constant over the life of a lithium battery, and its efficiency at 0 degrees Fahrenheit is nearly the same as at room temperature. They are expensive.

4. Extra food

A one-day supply of extra food is a reasonable emergency stockpile in case you are delayed by foul weather, faulty navigation, injury, or other reasons. The food should require no cooking, be lightweight and easily digestible, and store well for long periods. A combination of jerky, nuts, candy, granola, and dried fruit works well. Some climbers also bring extra cocoa, dried soup, and tea if a heat source is available.

5. Extra clothing

How much extra insulation is necessary for an emergency? The garments used during the active portion of a climb and considered to be your basic climbing outfit are the inner and outer socks, boots, underwear, trousers, shirt, sweater or pile coat, hat, mitts or gloves, and raingear. These garments suffice over a wide range of temperatures and weather if the climber is active. Extra clothes for an unplanned bivouac are added to these basics according to the season. Ask yourself this question: what do I need to survive the worst conditions I could realistically encounter?

Extra underwear is a valuable addition that weighs little. During a strenuous climb, perspiration can soak the next-to-skin layer and conduct heat away from the core. It is important to get rid of wet garments in contact with the skin before donning thicker insulation, such as down or synthetic coats and an outer shell. Protection for the neck and head can be gained by using long underwear with a zippered turtleneck, and a balaclava. An additional thick hat will retain almost as much warmth as an additional sweater. For the feet, bring an extra pair of heavy socks; for the hands, an extra pair of polyester or pile mitts.

For winter and expedition climbing in severe conditions, you'll need more insulation for the torso as well as insulated overpants for the legs. In addition to your rain shell, carry some sort of extra shelter from the rain, such as a plastic tube tent, a Mylar "space blanket" taped into the shape of a bivy sack, or plastic trash-can liners. Carry an ensolite seat pad to reduce heat loss to the snow (some packs can double for this purpose).

Some climbers carry a bivouac sack, weighing about a pound, as part of their survival gear and go a little lighter on their insulating layers. It's a good strategy. (Chapter 3 has details on bivouacs and bivy sacks.) The sack protects your insulation from foul weather, minimizes the effects of convection by quieting the air surrounding you, and traps much of the heat escaping from your body so that the temperature of your cocoon rises.

6. Sunglasses

Eyes are particularly vulnerable to the brilliance of mountain skies, visible light reflecting off snow, and ultraviolet rays—which at 10,000 feet are 50 percent greater than at sea level. The retinas of unprotected eyes can be easily burned, causing the excruciatingly painful condition known as snowblindness.

Because damage occurs to the eyes before discomfort is felt, it is essential to wear sunglasses to reduce the visible light and invisible ultraviolet rays. Don't let cloudy conditions fool you into leaving your eyes unprotected. Ultraviolet rays penetrate clouds, and the glare of reflected light can cause headaches. Sunglasses should filter 95 to 100 percent of the ultraviolet light. They should also be tinted so that only a fraction of the ambient light is transmitted through the lens to your eyes. For glacier glasses you want a lens with a 5 to 10 percent transmission rate. For more general outdoor use, the lenses should have about a 20 percent transmission rate. Look in a mirror when trying on sunglasses: if you can easily see your eyes, the lenses are too light. Lens tints should be gray or green if you want the truest color, and yellow if you want visibility in overcast or foggy conditions.

There is little proof that infrared rays (heat-carrying rays) harm the eyes unless you look directly at the sun, but any product that filters out a high percentage of infrared, as most sunglasses do, is added eye insurance.

The frames of sunglasses should have side shields that reduce the light reaching your eyes, yet allow adequate ventilation to prevent fogging. Problems with fogging can be reduced by using one of the many anti-fog lens cleaning products that are available.

Groups should carry at least one pair of spare sunglasses in case a pair is lost or forgotten. You can also improvise eye protection by cutting small slits in an eye cover made of cardboard or cloth.

A climber who depends on corrective lenses should carry a spare pair of glasses. Normal glasses with clip-on sunglasses can function as one pair, and good prescription sunglasses with extra-dark coatings can be the second pair. Alternatively, this climber can carry two normal pairs of prescription glasses plus a well-ventilated pair of ski goggles outfitted with a very dark lens.

Many climbers who need corrective lenses prefer using contact lenses instead of glasses. Contacts improve visual acuity, don't slide down your nose, don't get water spots, and allow the use of non-prescription sunglasses. Contacts do have some problems, however. Sun and blowing dust and dirt can dry out or irritate your eyes, though good side shields reduce the ill effects. Backcountry conditions make it difficult to clean and maintain the lenses.

7. First-aid supplies

Don't let a first-aid kit give you a false sense of security. It cures very few ills. Doctors say that in the field there is often little they can do for a serious injury or affliction except initiate basic stabilizing procedures and evacuate the patient. The best course of action is to take the steps necessary to avoid injury or sickness in the first place. Still, you want to be prepared for the unexpected.

Your first-aid kit should be small, compact, and sturdy, with the contents wrapped in waterproof packaging. Commercial first-aid kits are widely available, though many are inadequate. (Two of the best sources of information on items to include in a first-aid kit are *Medicine for Mountaineering*, by James A. Wilkerson, M.D., and *Mountaineering First Aid*, by Marty Lentz, Steven C. MacDonald, and Jan D. Carline, both published by The Mountaineers.)

The contents of your kit will be items you carry on all trips: Band-Aids or other small adhesive bandages, moleskin, adhesive tape, cleansers, soap, butterfly bandages, scissors, triangular bandages, a carlisle bandage, roller gauze, and gauze pads in various sizes. Carry enough bandages and gauzes to absorb a significant quantity of blood. Severe bleeding wounds are a common backcountry injury, and sterile absorbent material cannot be readily improvised.

In addition to the basics, consider the length and nature of your trip. If you are traveling on a glacier, for example, tree branches won't be available for improvised splints, so a wire ladder splint would be extremely valuable in the event of a fracture. For a climbing expedition, you may need to consider appropriate prescription medicines.

8. Pocket knife

Knives are so essential for food preparation, fire building, first aid, and even rock climbing that every climber needs to carry one. The knife should have two folding blades, a can opener, a combination screwdriver and bottle opener, scissors, and an awl. The tools and the inside of the casing should be made of stainless steel. Although you may carry a few additional tools on certain trips, the knife is your basic tool kit. A cord attached to the knife and secured to your belt lets you keep the knife in your pocket for ready access without danger of losing it.

9. Matches

An emergency supply of matches, stored in a watertight container, should be carried on every trip in addition to the matches or butane lighter used routinely. Storing waterproof or wooden matches and a strip of sandpaper in a film canister makes a good emergency system.

10. Fire starter

Fire starters are indispensable for igniting wet wood or starting a fire quickly in an emergency. They can even be used to warm a cup of water or soup, if you have a metal cup to heat it in. Common fire starters are candles or solid chemical fuel (such as heat tabs or canned heat).

OTHER IMPORTANT ITEMS

Water and water bottles

High peaks are often bone dry or frozen solid, so you usually carry the water that is needed to prevent dehydration and maintain energy. A single 1-quart bottle usually suffices, but if it's hot and you sweat a lot, you may need to carry two. Wide-mouthed polyethylene bottles are the most popular because they can be easily refilled with snow or water, and they impart no flavor to the water, unlike aluminum. If you do use an aluminum bottle, be careful not to mix up the water bottle with the bottle that carries fuel for the stove.

Giardiasis, a waterborne bacterial infection, is a major health concern for alpine travelers. The cyst of the bacteria has tainted many water sources in the wilds, and it takes only one swallow of contaminated water to get sick. The illness takes six to twenty days to manifest itself, with symptoms that include nausea, flatulence, diarrhea, cramps, belching, fever, and dehydration.

Several methods of water purification make water safe to drink by killing or filtering out *Giardia lamblia* and other contaminants. Chemical treatment with tablets of iodine or halazone is effective, and tetraglycine hydroperidide (TGHP) tablets are better yet. Follow directions closely. The required amount of chemical and soaking time increases dramatically with colder water. If you fill your bottle from a glacial stream, you may need to place the bottle in the sun or inside your shirt to raise the water's temperature.

Bringing water to a rolling boil will kill *Giardia* cysts but may not kill other disease-causing bacteria and viruses unless the water boils for nearly 20 minutes. A combination of chemical treatment and a short boil makes water safe.

Water filters are another option. Filters with a pump can strain a quart of water in minutes and do not impart any unpleasant taste to the water. A good water-filtering device provides a method to clean and extend the life of the filter, which is replaceable. Buy only filters with pore sizes smaller than $^4/_{10}$ micron (.4 micron) to ensure you will filter out *Giardia* cysts, flukes, tapeworms, and protozoa.

Sunburn prevention

Sunlight at high altitudes has a burning capacity many times greater than at sea level, so much so that it is a threat to both comfort and health. Climbers cannot avoid long exposure to the sun so they must reduce the burning ultraviolet rays reaching their bodies by covering their skin with clothing or burn-preventing creams (sunscreens).

Individuals vary widely in natural pigmentation and the amount of protection their exposed skin needs. There is only one rule here: the penalty for underestimating the degree of protection needed is so severe, including the possibility of skin cancer, that you should always protect your skin.

Clothing is by far the best sun protection and is worth the discomfort it causes on a hot day. Skin not covered by clothing should be covered with sunscreen. Most sunscreens use *p*-amino benzoic acid (PABA), but if your skin is sensitive to PABA there are other chemicals that yield the same sun protection factor (SPF) as PABA creams.

For glacier travel or a snowy environment, get a sunscreen with an SPF of 15 or more. Cover all exposed skin, even if it's shaded, because reflected light can burn the underside of your chin and nose and the insides of your ears. Some sunscreens are advertised as waterproof and will protect you longer than regular products when you are sweating heavily. Regardless of the sunscreen used, reapply it occasionally if you are perspiring.

Actor's grease paint (clown white) or zinc-oxide pastes ensure complete protection, and the grease bases keep them from washing off. One application lasts the entire climb, except where fingers or equipment rub the skin bare. The disadvantages of these creams is that they are messy and so difficult to remove that you may need help from a cold-cream cleanser.

The area around the mouth is particularly susceptible to fever blisters caused by sun exposure. The lips should be covered with a total-blocking cream that resists washing, sweating, and licking. Zinc oxide and lip balms containing PABA are both good. Reapply lip protection frequently.

Insect repellent

The wilderness is an occasional home for people but the permanent habitat of insects. Some of them—mosquitoes, biting flies, "no-see-um" gnats, ticks, chiggers—want to feast on your body. You can protect your body and blood with heavy clothing, including gloves and head nets in really buggy areas.

In hot weather, covering your body with heavy clothing may be unbearable, and insect repellents become a good alternative. Repellents with *N,N*-diethyl-metatoluamide (DEET) claim to be effective against all these insects, but are really best for keeping mosquitoes at bay. One application of a repellent with a high concentration of DEET will keep mosquitoes from biting for several hours, though they will still hover about. Mosquito repellents are marketed under many names, have differing potencies, and come in liquid, cream, spray, and stick form. Be aware that DEET can discolor or dissolve plastics, paints, and synthetic fabrics.

Despite claims by manufacturers, DEET is not very effective at repelling biting flies. Products with ethyl-hexanediol and dimethyl phthalate are much more effective against black flies, deer flies, and gnats. Unfortunately fly repellents don't do much to ward off mosquitoes.

Ticks are a potential health hazard due to the diseases they can carry, such as Lyme disease and Rocky Mountain spotted fever. In tick country, check clothing and hair frequently during the day.

At night, give your clothes and body a thorough inspection to locate ticks before they embed themselves. If you find a tick on your body, cover it with heavy oil (mineral, salad, etc.) to close its breathing pores. The tick may disengage at once. If not, allow the oil to remain in place for half an hour, then carefully remove the tick with tweezers, taking care to remove all body parts. Once a tick is deeply embedded, you may need a physician to remove its buried head.

REPAIR KIT

It's helpful to carry an emergency repair kit for your equipment. It could include wire, tape, safety pins, thread, needles, yarn, string, patches, and small pliers. This kit will probably grow over time as you add items you wished were along on a previous trip.

ICE AXE

An ice axe is indispensable on snowfields and glaciers and on snow-covered alpine trails in spring and early summer. It also has great value when you are traveling in steep heather, scree, or brush, crossing streams, and digging sanitation holes. However, an axe is more dangerous than helpful in unpracticed hands. (Chapters 5 and 12 give the details on using an ice axe.)

EQUIPMENT CHECK LIST

Experienced climber or not, it's easy to forget an important item in the rush to get ready for the next trip. Seasoned climbers have learned that using a check list is the only sure way to avoid an oversight. The following list is a good foundation for formulating your own personal check list. Add to or subtract from this list as you see fit, then get in the habit of checking your own list before each trip.

Items in parentheses are optional, depending on your own preference and the nature of the trip.

Items marked with an asterisk can be shared by the group.

ALL TRIPS

The Ten Essentials

1. Map
2. Compass
3. Flashlight/headlamp, with spare bulbs and batteries
4. Extra food
5. Extra clothing
6. Sunglasses
7. First-aid supplies
8. Pocket knife
9. Matches, in waterproof container
10. Fire starter

Clothing

Boots
Socks: inner and outer
Long underwear
Pants: wool or pile
Sweater or shirt: wool or pile
Parka: wind and rain
Hats: wool, rain, sun
Mittens, gloves
Down or synthetic garments
Wind/rain pants
(Gaiters)
(Shorts)
(Hot-weather shirt)

Other

Rucksack
Ice axe
Emergency shelter or bivy sack
Water bottle/purification tablets
Lunch

Sunscreen and lip protection
Bandanna
Toilet paper
Whistle
(Cup)
(Insect repellent)
(Moleskin)
(Nylon cord)
(Altimeter)
(Watch)
(Camera and film)
(Binoculars)
(Insulated seat pad)

ADDITIONAL ITEMS FOR OVERNIGHT TRIPS

Internal- or external-frame pack
Sleeping bag and stuff sack
Sleeping pad
Spoon
*Shelter: tent or tarp
*Food
*Water container
*Repair kit
*Stove, fuel, and accessories
*Pots and cleaning pad
(Fork)
(Toiletries)
(Spare clothing)
(Camp footwear)
(Pack cover)

ADDITIONAL GEAR FOR GLACIER OR WINTER CLIMBS

Crampons
Carabiners
Slings: chest and prusik
Seat harness
Additional warm clothing: mittens, mitten shells, socks, balaclava, down or synthetic clothing, long underwear
Extra goggles
(Helmet)
(Supergaiters)
(Snowshoes or skis)
(Candles)
(Avalanche beacon)
*Climbing rope
*Rescue pulley
*Snow shovel
*Group first aid
*Alarm clock or alarm watch
*(Flukes, pickets, ice screws)
*(Wands)
*(Snow saw)

ADDITIONAL GEAR FOR ROCK CLIMBS

Helmet
Carabiners
Belay gloves
Runners
Seat harness
Prusik sling
*Climbing rope
*Rack: chocks, stoppers, etc.
*Chock pick
(Belay/rappel device)

---

* = equipment shared by the group
( ) = optional items

• 3 •

CAMPING AND FOOD

Camping, like mountaineering in general, is part ecstacy, part drudgery. You can make life easier on yourself by learning the art of camping and alpine cookery. Setting up a temporary home in the wilds ought to be quick work and provide cozy shelter, a warm bag, and good food.

Camping has another critical component: respect for the wilderness. In fact, that's number one. Let's face it: our comfort is secondary to preserving the mountain environment. The peaks aren't there for us, they're just there, and it's really not hard to do the things that show our respect for the places that bring us such happiness. That's why this chapter includes a lot of tips on camping clean in addition to camping easy.

LOW-IMPACT CAMPING

THE CAMPSITE

Mountain climbers don't always set up camp in the most comfortable places. They may walk right past an idyllic spot in the forest in favor of a windy mountain ledge because that puts them closer to the summit. What other reasons might there be for picking a particular campsite? Because it's comfortable? Scenic? Environmentally sound? Sometimes you can have it all, but at other times you need to give a little to help preserve the wilderness.

Let's look at camps from the standpoint of the wilderness to see which sites are least damaging to the environment. From best to worst, they are:

Snow: The snow will melt and show no sign of your tenancy.

Rock slab: Solid rock resists most damaging effects of a campsite.

Sandy, dirt, or gravelly flat: This is the next-best choice.

Open, plant-sparse area in deep forest: This is less ideal than the first three choices.

Grass-covered meadow above timberline: Meadows above timberline have a brief growing season and are the most fragile of mountain ecosystems. A tent left on a grass-covered meadow for a week can wipe out an entire growing season for the covered patch. Moving a long-term camp every few days reduces the harm to any one spot.

Plant-covered meadow above timberline: Alpine plants grow very slowly. Heathers, for example, have only a couple of months to bloom, seed, and add a fraction of an inch of growth. They could take years to recover from the damage of a brief encampment.

Waterfront: Waterside plant life is especially delicate and water pollution is a growing problem as more people head into the backcountry. A large proportion of long-established campsites in American mountains are on the banks of lakes and streams, but many areas now ban camping within 200 feet of the water.

In general, you want to honestly visualize the impact of any campsite. Camp away from water, meadows, trails, and other campers. Look for a resilient, naturally bare site. Try to find a spot that has just the right natural slope so you won't have to level it or dig channels for drainage. If there happens to be an established campsite far enough back from a water source, use it rather than setting up a new one.

From the standpoint of comfort, wind is a big consideration in choosing a campsite. You will find that alpine breezes are capricious. An up-slope afternoon breeze may reverse at night to an icy down-slope draft from snowfields. Cold air, heavier than warm air, flows downward during settled weather, following valleys and collecting in depressions. Thus there is often a chill breeze down a creek or dry wash and a pool of cold air in a basin. Night air is often several degrees cooler near a river or lake than on the knolls above.

Consider wind direction in pitching your tent. It can be a good idea to face an opening into the wind so that wind blowing in will distend the tent, equalizing interior and exterior pressure and minimizing tent flapping. But alpine winds are reversible without warning. One consolation of foul weather is that storm winds are fairly consistent.

CAMPFIRES

The old romantic days of cooking over an open fire and lounging around a big campfire are just about over. The price is too high in old scarce trees, especially at higher elevations. And no matter where, campfire scars are a blemish. Mountaineers now cook almost exclusively on lightweight stoves they carry with them, a big step toward low-impact, no-trace camping.

Some simple rules apply in case you do build a campfire. Keep it small, within an existing fire ring, and only where it's safe and legal. Stay there until the fire is dead and the ashes cold. For firewood, use only dead or downed wood from outside the camp area; never cut a standing tree or snag. You might consider using a stove, even if campfires are permitted, because the stove fire doesn't mar the landscape and because it's more dependable than counting on finding firewood.

WASHING

You can keep dishes reasonably clean without soap. By taking moderate care in cleaning pots with hot water after each meal, parties commonly remain healthy on week-long trips without so much as a pinch of soap or biodegradable detergent. Fill pots with water as soon as they are empty and clean them right away or leave them to soak. Be sure to get rid of the cleaning water a long way from water sources, and if you do use soap, use a biodegradable product and keep it off the plant life. On weekend trips it can be easiest to carry dishes and pots home dirty.

Woven plastic or metal scouring pads are handy and weigh next to nothing. Teflon-coated pots are easy to clean, but of course they can be easily damaged with metal or abrasive cleaners. Using sand, gravel, or grass to clean pots can leave unsightly bits of food to attract flies and rodents. Carry leftovers out with you, and try to do better meal planning next time. Also as part of the cooking routine, it helps to have a large water container along to save yourself and the terrain from a lot of trips to the water source.

If you need to wash yourself or your clothing, stay at least 200 feet from water. Go without soap, or use only biodegradable soap in very small quantities.

SANITATION

Plastic bags can be indispensable. Mountaineers use them to package food, as emergency mini-tents, and sometimes to keep the water away from their feet. Keep a heavy-duty plastic bag on hand to carry the garbage. The old rule about food containers is that if you can carry it into the wilderness full, you can carry it out empty. Mountaineers clean up every bit of their garbage (yes, even aluminum-foil flecks from a campfire) and often pack out anything they find in camp or on the trail, no matter who left it. Never bury garbage or dump it in latrines. The golden rule of camping: Leave the campsite cleaner than you found it.

Heavily used campsites usually have a pit toilet, set away from any source of water. Otherwise, go at least 200 feet from any open water (allowing for maximum level around lakes), dig a hole 8 to 10 inches in diameter and no deeper than 8 inches. Fill it after use with loose soil and tamp the sod back in place. Pack out used non-biodegradable items of personal hygiene, such as sanitary napkins, in airtight containers. In snow, find an unobtrusive toilet area, such as a clump of trees well away from camp, and wherever possible burn the used toilet paper. Pick up any trash before it gets covered with new-fallen snow, where it will lie hidden until the spring thaw.

ANIMALS AND FOOD

Bears and rodents will gnaw through plastic bags, packs, and even tents for food. A food sack or pack hung from a tree or suspended from a pole must be farther from the tree trunk and higher from the ground than a bear can reach. Watch out for mice that can walk a tight line and drop down to the food. Hanging food 4 feet from the tree trunk and 8 feet from the ground gives you a fighting chance against animals.

Some other tips: Keep the cooking area and food storage well away from where you sleep. Package food in containers with tight lids or in sealed plastic bags to conceal the smell. Don't encourage the wildlife by feeding them.

Hiding a food cache for your party in the wilderness is generally not acceptable. Animals can get into an improperly protected food cache and leave a big mess, which will only draw more animals.

SHELTER

When you settle in for a night in the mountains, your home away from home will be a tent, bivy sack, tarp, snow shelter, or hut. We will take a close look here at the kinds of shelters you can carry on your back or build from the snow. (Chapter 15 discusses tents, snow shelters, stoves, and sleeping bags as they are used in winter and expedition climbing.)

Tents are the most common shelter because of their many virtues. They are relatively quick and easy to put up, rainproof, private, usable almost anywhere, a refuge from wind or sun, and often roomy enough for you *and* your gear. They also are heavy and expensive. Tents are usually the best shelter above timberline and for glacier camps, winter camping, in strong winds, and in mosquito country. Alpine climbers in a hurry can get nighttime protection from a lightweight bivy sack, though the sack is not much help in heavy rain and has limited room inside for gear. A tarp in combination with a bivy sack increases protection from the elements. A snow shelter is a haven from wind and storm, but building it is hard work and time consuming.

Curiously enough, shelter is often more necessary on a clear night than on a cloudy one. When two opposing surfaces differ in temperature, the warmer radiates heat to the colder. Since the human body is usually warmer than the night sky, exposed portions of the body or sleeping bag radiate heat and grow cold. Any shelter at all serves as a baffle. Clouds often reflect heat back to earth, and thus have the effect of a huge tarp between sleeper and sky. The clear nights are the cold ones.

TENTS

The choice of a tent depends on what you like and what you plan to use it for. Will it be used only in the summer, or for three or four seasons of the year? Above or below timberline? For you alone, or for two people, or three, or four? Are you after luxurious space, or just the bare minimum? How much weight are you willing to carry? How much money are you able to spend? Manufacturers offer almost any combination of size, weight, and design. The choice is yours, after consulting catalogs, stores, your friends, and neighboring campers.

Water resistance

Tents are built with either single or double walls, of either waterproof or breathable materials. A completely enclosed unit must be well ventilated and preferably should ''breathe.'' If the tent is waterproof, the moisture you exhale condenses on the cold walls and runs down to collect in puddles on the floor. In a single night, you and your tentmate can expel enough water vapor to drench the sleeping bags. Watch out for the cheap tents built of a single layer of unbreathable waterproof material. They are only good for the mildest of conditions below timberline where the door and windows can be left open for ventilation; even then, you can expect some condensation. Some single-walled nylon tents have a design that uses gravity to spread and remove condensation, but to be effective, the tents must be well ventilated.

The dilemma of a waterproof yet breathable tent is solved by using double walls. The inner wall is breathable: it is not waterproof, so it allows your breath and perspiration to pass through to the outside. The outer layer is a waterproof rain fly, usually separate, that keeps the rain off the tent and also collects and disposes of the body moisture from inside the tent. The rain fly must not touch the inner walls, because where it touches, water will condense inside. The fly should come fairly close to the ground to cover the tent and entrance, discouraging wind-driven rain. Even in a double-walled tent, sleeping bags can get wet from condensation that forms on the waterproof side panels that extend a foot or so up from the floor in some models.

An important step in keeping a tent dry is to close up the needle holes from stitching by painting all seams with waterproof seam sealer. Do this before the tent is ever used. Some tents come with factory-sealed seams; on others, it's up to you, but it's got to be done. In camp, put a plastic or nylon ground cloth under the tent to stop ground moisture from entering the floor of the tent and to keep the bottom clean and protected from abrasion.

Strength

Many tents are rated by a ''relative strength factor,'' the speed of wind a tent can withstand before the frame deforms. If you expect to run into wind and snow, this is an important consideration. The tent should stand up to high winds and snow loads without structural failure.



Fig. 3–1. Two types of mountain tents: a, dome; b, tunnel (hoop).

Weight

It's usually a tradeoff: light weight, or more comfort and durability. Lightweight tents are available, but the question is whether they are big enough or tough enough for your particular uses. Simply look for the lightest tent that meets your requirements for number of occupants, head room, floor space, gear storage, strength, climate, and weather conditions. A two-person tent for summer camping might be light, while a three-person, four-season expedition tent could weigh twice as much, and be two to three times as expensive.

Shape

The trend in tent shapes has been to tunnels and domes (fig. 3-1). These designs make maximum use of space and minimize the number of stakes and guy lines. The free-standing dome needs no guy lines at all and can be picked up and moved as a unit, but it still must be staked down so it won't blow away. The two- or three-hoop tunnel tent, usually not free standing, offers efficient use of space and has wind-shedding characteristics. The traditional A-frame doesn't give as much usable space, but it's a simple, proven design.

Size

The two-person tent is probably the most popular size and offers the greatest flexibility in weight and choice of campsite. For versatility in a group, it's generally better to bring, for example, two two-person tents rather than one four-person tent. Many two-person tents handle three in a pinch, yet are light enough to be used by one person occasionally. Some three- and four-person tents are light enough to be carried by two people who crave luxurious living. Larger tents, especially those high enough to stand in, are big morale boosters during an expedition or long storm. For carrying, you can distribute the weight among a group by dividing the tent into parts.

Color

Warm tent colors such as yellow, orange, and red are cheerier if you're stuck inside, and they make it easier to spot camp on the way back. On the other hand, more subdued hues blend into the landscape. One's an eyesore; the other may be camouflaged only too well if you're having a little trouble finding camp.

Other features

Entrance designs offer zip doors, tunnels, alcoves, vestibules, and hoods. Compare designs to find the one that looks like it will keep out the most rain and snow as you're coming and going. Vestibules can be nice as a way to shelter the entrance and provide more room for gear, cooking, and dressing. There are a lot of options in the arrangement and type of ventilation holes and windows. Mosquito netting can help keep out rodents as well as flies and mosquitoes.

Cooking inside a tent

Avoid cooking inside a tent, especially with stoves that use white gas. Fumes, spilled fuel, and stove flare-ups are fire hazards. Asphyxiation is a danger in a closed tent, particularly from the combination of a watertight coated-nylon tent and cooking fumes. Cooking also adds greatly to inside condensation.

If you must cook inside the tent, do it in an alcove or vestibule. Well-placed ventilation holes can lessen the danger. Always start the stove outside the tent and use an insulating pad under the stove once it's inside.

Care and cleaning

Your tent will give more years of good service if you are careful to air-dry it thoroughly before storing it away after each trip.

To clean a tent, hose it off with water, or wash with mild soap and water. Scrub stains with a sponge or brush. Don't put the tent in a washer or dryer. High temperatures or prolonged exposure to sun are damaging to tent material.

TARPS

A tarp is light in weight and low in cost, and may offer adequate shelter (fig. 3-2) from all but extreme weather in lowland forests and among



Fig. 3–2. Improvising a shelter with the basic tarp

subalpine trees. It gives less protection than a tent from heat loss and wind, none at all from insects or rodents, and demands ingenuity on your part and some cooperation from the landscape to set up.

Plastic tarps don't hold up very well, but are cheap enough that you can replace them often. Coated-nylon tarps come with reinforced grommets on the sides and corners for easy rigging. If your tarp doesn't have grommets, sew on permanent loops of fabric, such as nylon or twill tape, before leaving home. Alternatively, you can just tie off each corner (fig. 3-3) around a small cone or pebble from the campsite. Take along some lightweight cord to string the tarp and perhaps a few light stakes.



Fig. 3–3. Securing a tarp without grommets

The most versatile tarp size is about 9 by 12 feet—luxurious space for two people and their gear, and adequate for three, or even four. An 11- by 14-foot size will handle four campers comfortably. Since the outer margins of tarp-covered ground are usually only barely protected, usable space quickly approaches the vanishing point if your tarp is smaller than 9 by 12 feet. Put down a waterproof ground sheet, but if rain results in a surprise flood, be ready to move camp. A tarp is not meant to be used as a blanket, because perspiration will condense inside the waterproof material and leave you damp.

BIVOUAC SACK

For super-lightweight alpine traveling, the bivy sack takes the place of a tent in providing shelter from wind and rain. The sack is a large envelope of tightly woven fabric with a zipper entrance at one end. The bottom, usually of waterproof coated nylon, goes against an insulating ground pad. The upper side, of a breathable, waterproof material such as Gore-Tex, allows moisture to escape into the atmosphere. The bivy sack is designed for one person, two in an emergency. It needs no poles or stakes, but usually has strong loops for anchoring and can be used by itself or to add extra warmth to a sleeping bag.

SNOW SHELTERS

Newcomers to snow camping are sometimes surprised at what a warm, comfortable, and beautiful experience it can be. To make it work, a good shelter and insulation are essential. At the very least, every snow traveler needs the skills and equipment to survive overnight in the snow.

Tents in the snow

The most convenient snow shelter is a tent installed on a stamped-out platform slightly larger than the tent floor. It's easy to put up and gets you quickly out of the elements. When conditions are serious, a tent can shelter double to triple the usual number of occupants.

There are a few tricks to anchoring a tent in snow, where metal or plastic stakes can melt out during the day. Stakes can be replaced by "deadman" anchors (fig. 3-4), such as a rock, a bag filled with rocks, or a nylon stuff sack filled with snow. Attach a cord or sling to the deadman, bury the deadman in the snow, stamp down the snow above it, and then connect a tent guy line to the cord or sling. Stakes themselves can be used as deadman anchors by burying them horizontally in a snow trench, perpendicular to the guy line. Even better, prepare the deadman in advance by drilling holes in a stake or metal plate and attaching a bridle, to which the guy line can be tied. Snowshoes and ice axes also make solid anchors, but of course you can't use them for anything else while they're holding down the tent.

Snow campers have to watch out that heavy, wet snow does not pile up on the tent or fly, because too much force can break rigging or tent poles and bring the whole structure down. A heavy snow load can even bury a tent and its occupants, asphyxiating them. Shake the walls and shovel out around the tent as often as necessary to keep a big load of snow off. A snow wall built around the tent helps give protection from blowing snow and heavy wind.

Snow caves

A snow cave (fig. 3-5) provides more protection, comfort, and insulation from a storm than a flapping, gale-swept tent, and it's an emergency shelter when you have no tent. Knowing how to build snow caves is an essential mountaineering skill. Be prepared for the fact that it's a time-consuming job.

You can dig an emergency cave with a cooking pot, a hard hat, or whatever gear might be handy, but a lightweight snow shovel is the best tool. (A



Fig. 3–4. Deadman anchors: a, metal plate; b, tent stake; c, nylon stuff sack.



Fig. 3–5. Cross-section of snow cave

grain scoop—a lightweight shovel with a very broad blade—can move a lot of snow, but it's difficult to use in tight quarters.) Holes can be drilled in the shovel base to make it lighter, without sacrificing its scooping power. Even with two shovels in the party, it can take 2 or 3 hours to dig a shelter for four people.

Here's how to go about building a snow cave:

Find a location. Look for obvious hazards. Are you on a potential avalanche slope? Could wind blow snow over the opening and seal you in? Look for fairly firm snow at least 6 feet deep. A short steep slope, such as along a riverbank or on the side of a snowdrift, makes for a better cave than trying to dig one on the flat.

Get to work. Keep your clothing dry. Work slowly to avoid excessive sweating.

Dig an entryway into the slope, far enough to start a tunnel. Continue to dig inward about 3 feet to form the entrance to the cave, then angle upward to excavate a living area. There should be at least 1 foot of snow on the slope above the cave ceiling to provide enough strength to keep it from collapsing.

Put the cave floor above the top of the entry tunnel, in order to trap warm air inside. Make the ceiling smooth, with no bumps or protrusions, so melting snow will run down the walls rather than drip on the climbers. Put down a ground sheet to keep things dry and prevent loss of equipment in the snow. A small tarp over the entrance will help keep the weather out.

Punch a ventilation hole through the ceiling. Enlarge the hole if it gets too warm inside.

There is even a way to build an emergency snow cave in shallow powder snow (fig. 3-6). You need at least 6 inches of snow, and it takes about 3 hours. Step by step, this is the way to do it. Drive a 6-foot stick vertically into the snow. Take another and draw a circle 12 feet in diameter around the stake. Lay the second stick on the snow, one end touching the vertical stick. (The second stick becomes a "guide" to point you toward the vertical stick after you've buried it within the cave.) Shovel snow into a big pile within the circle, packing it down until its center is about 1 foot above the top of the vertical stick. Let the pile sit for an hour or so, then tunnel into the pile following the guide stick. Excavate enough snow to make a small room, large enough for two or three people, with 2-foot-thick walls. Remove the vertical stake.



Fig. 3–6. Snow cave built in less than 6 inches of snow

Tree-pit shelter

With a little improvisation, natural shelters can be converted into snow hideaways in an emergency. Such shelters occur under logs, along riverbanks, or in the pits formed when snow melts and settles away from large trees. For a tree-pit shelter, enlarge the natural hole around the trunk and roof it with any available covering, such as ice blocks, tree limbs, or canvas. Boughs and bark can provide insulation (but don't cut live boughs unless it is a life-or-death emergency).

Snow trenches

When it is getting dark or the weather is especially bad, a snow-block shelter might be your answer. The trench igloo (fig. 3-7), built on either a slope or on the flat, is a quick emergency shelter for one or two people. Dig a narrow trench and then roof the trench, A-frame style, with snow blocks. (The blocks can be created as part of the process of removing snow for the trench, or they can be quarried nearby.) Then enlarge the interior and provide a vent hole. Smooth out any irregularities in the ceiling so that condensation will run down the blocks and not drip on the occupants. This shelter is not as easy to build as it looks, so practice first in good weather.

A more basic emergency snow shelter can be built by digging a trench some 4 to 6 feet deep and large enough for the party, then stretching a tarp over the top, perhaps gaining a slight angle by anchoring one side to a ridge of snow. This works well in wind or rain, but a heavy snowfall can collapse a roof that is so nearly flat. The smaller the trench, the easier it is to keep warm. Again, be sure to provide for ventilation.



Fig. 3–7. Trench igloo

Igloos

Igloos are equal in protection to snow caves, but the traditional dome-shaped igloo (fig. 3-8) built of snow blocks that spiral upward to the top requires


1
2
3
4
Blocks 1, 2, and 3 cut to angle shown after placement
2"
20"
Homemade aluminum snow saw
B
A
NECESSARY CONTACT POINTS
Block B will not stand unless leaning against A
Vent

Fig. 3–8. Construction of a traditional igloo

proper snow consistency or preparation, plus a builder with a good bit of expertise. Wet, packed snow provides blocks that stick together and stay in place, but makes them heavy and difficult to handle. Wind-packed snow is the easiest to work with. If the snow is soft, stomp it down and let it consolidate for a few minutes before starting to saw blocks with a snow saw or shovel. Each snow block should measure about 2 1/2 feet by 1 1/2 feet by 1/2 foot. Bevel the bottom of each block so the wall will tilt inward at the proper angle. Hold each block in place as it is installed while the cracks are chinked with snow. The igloo entrance should be below floor level so that warm air is trapped inside.

SLEEPING BAGS

Your sleeping bag should be lightweight, warm, comfortable, easily compressible, have a hood or other way to keep your head covered, and generally suit the climate where you do your camping.

WARMTH

The warmth of a sleeping bag is provided by insulating material that traps dead air. How warm a particular bag is depends on the type and amount of this insulating fill, the thickness (loft) of the fill, and the bags's size, style, and method of construction.

Sleeping bags are generally categorized as recommended for summer, three-season, or winter expedition use. (See Chapter 15 for tips on sleeping bags for winter climbs.) Manufacturers give their bags comfort ratings, meant to indicate the lowest temperature at which the bag will be comfortably warm. Methods of rating the bags vary from manufacturer to manufacturer, so they can give only a general idea of how the bag will perform. Bags are usually rated to a minimum temperature of somewhere between 40 degrees and –20 degrees Fahrenheit (between about 5 degrees and –30 degrees Celsius).

How closely a rating matches you personally depends on whether or not you are in a tent, the clothing you are wearing, the ground insulation, and your body size, metabolic rate, and caloric intake. Look for a rating that matches your use. If you're mainly a summer backpacker, a bag rated to –20 degrees Fahrenheit will be too warm.

The warmest, lightest sleeping-bag design is the mummy bag—tapered toward the feet, hooded to fit over the head, and with a small face opening secured with drawstrings. Whatever the design, your bag should have a form-fitting hood or a semicircular piece with drawstrings to keep your head warm and prevent heat loss. Some bags incorporate an insulated collar to provide extra warmth around the shoulders, and some include extra insulation at critical areas, such as chest or feet. You can buy a thin over-bag to put around the sleeping bag during colder weather to improve the bag's performance. Also available are vapor-barrier liners (for inside the sleeping bag) that can increase your bag's comfort range by 10 or 15 degrees Fahrenheit. However, figure that whatever clothing you have on in the bag is going to get damp from body vapor that has nowhere else to go. These liners are best used at below freezing temperatures.

There are some basic procedures for sleeping warmer, regardless of the bag you are in. Undress inside the bag. Wear a wool hat and dry socks to bed. Secure the bag closely around your face. Breathe through a sweater to reduce heat loss from exhalation. You can put your head inside the bag to help warm them both, though the water vapor from your breath will likely make it damper inside.

The comfort of the bag offers a chance to warm up not only you, but some of your things. Small items, like mittens and socks, can come into the bag to dry. Don't try to dry larger items of clothing by wearing them to bed, because they will just keep you cold and make the bag wet. In very cold weather, you may want to bring boots inside, wrapped in plastic. You may also need to make room for a water bottle, to keep it from freezing.

TYPES OF INSULATION

The warmth, weight, and cost of a sleeping bag depend chiefly on the kind and quantity of insulation, which is either goose down or a synthetic material.

Goose down is still the most efficient insulation per unit weight. Down bags are warm, very compressible, retain their loft well, and are long-lasting. Disadvantages? High cost and water absorbency. A wet down bag loses most of its loft and insulating value, making it almost worthless until it can be dried out. A down bag takes so long to dry—more than a day in good conditions—that it can't be dried during wet periods in the mountains. This characteristic makes down a questionable choice in a wet climate, unless you take extra care to keep it dry.

Synthetic insulation is resistant to moisture, retains most of its loft when wet, and dries relatively quickly. Bags with synthetic insulation are less expensive than down-filled designs. These bags are still slightly heavier than comparable down styles and do not compress quite as easily, thus making a weightier, bulkier load. Synthetic insulation does not last as long as down, and loses much of its loft with use.

CONSTRUCTION

Down bags are made with one of three basic construction methods (fig. 3-9) to keep the fill uniformly distributed: sewn-through, slant-tube, or overlapping tube. In sewn-through construction, the inner cover is stitched directly to the outer, a simple and inexpensive method but one with substantial heat loss at the seams. Most down bags are of slant-tube construction, which eliminates cold spots at the seams. The most efficient design, overlapping tubes, is used only in the most expensive bags. In addition, many designs incorporate channel blocks, baffles that prevent down from shifting.



Fig. 3–9. Down sleeping bag construction: a, sewn through; b, slant tubes; c, overlapping tubes.

Synthetic bags are built using a variety of methods. There are two basic types of synthetic fills. The first is a long, stable polyester fiber, manufactured in batts that stand up well to use and laundering. A widely used construction method is the shingle style, in which sections of batting are sewn in the bag, overlapping like roof shingles to cover cold spots. The second type of fill is a short, stable polyester fiber that is quilted or sewn into fine scrims to keep it from wadding up or moving around. To avoid cold spots, these must be shingled, or quilted in double or triple layers with quilted lines offset (fig. 3-10).



Fig. 3–10. Synthetic sleeping bag construction: a, triple-offset quilting; b, shingle.

Zippers are the almost universal means of closure even though they sometimes snag the fabric or go off the trolley. They are backed up with a tube of insulating material to reduce heat loss through the zipper. Long zippers make it easy to get in and out of the bag and are a big help in ventilating the lower portion. If you want to zip two bags together, be sure one zipper is right-sided and the other is left-sided.

EFFECTS OF WETNESS

Do yourself a big favor and keep your sleeping bag dry, especially if it is filled with down. Compared with down bags, polyester-filled bags retain much of their warmth when wet and are easier to dry, but a wet polyester bag is still a wet bag and colder than a dry one. You can buy a Gore-Tex sleeping-bag shell that lets body vapor escape while helping to protect the bag from condensation inside a tent or dripping water in a snow cave. Consider putting the sleeping bag inside a plastic sack before putting it on your pack, because most stuff sacks don't keep water out.

CARE AND CLEANING

Dirt decreases insulating efficiency. You should spot-clean soiled areas, especially around the head of the bag. A removable, washable liner or an outer cover of breathable material can provide protection from dirt and abrasion.

Both down and polyester bags can be hand-washed with any mild soap or with one of the excellent down soaps that are available. Rinse thoroughly to remove all soap. Squeeze water out gently by hand, or put the bag carefully through the spin cycle of a front-loading washing machine (with no agitator).

Down or polyester bags also can be washed in a front-loading washing machine on the gentle cycle because it doesn't have an agitator. The agitator will blow out the baffles in a down bag, which must be babied when wet to prevent damage to the inner structure.

Hang bags to air dry; do not dry either polyester or down bags in a dryer. Allow more drying time for a down bag (several days), and shake and turn the bag frequently to break up lumps of wet down. Both polyester and down bags can be put in a dryer after they have been line dried; use the fluff setting (air only—no heat), to fluff up the bag. A clean tennis shoe put in with the down bag may help break up any clumps of down.

A polyester or down bag can be dry-cleaned, but only by a professional who knows how to handle the material and only if it is thoroughly aired afterward to remove all traces of toxic fumes, which can cause illness or death. For best results, do what the manufacturer says.

GROUND INSULATION

The foundation for a comfortable night in the out-of-doors is a good piece of insulation under your sleeping bag. Summer or winter, in a tent or outside, that pad makes for a softer, warmer bed. On wet ground or snow, it's essential.

A thin pad of closed-cell foam, such as ensolite (more durable) or polyethylene (lighter weight), provides good insulation. Improved designs in closed-cell pads feature softer sleeping surfaces, lower weight, and an increased ability to trap air, resulting in greater thermal efficiency. Other pads use open-cell foam that offers 1½ inches of padding, but it makes for a bulky roll and must be protected from absorbing water.

An air mattress by itself is soft but provides no insulation. In fact, the air in the mattress carries heat away from the body. A pad, such as the Therm-a-Rest, that combines the insulation of open-cell foam with the softness of an air mattress is very popular and effective. Insulation pads come in a variety of lengths, but one that's only 4 feet long is usually adequate because you can use items of gear to support or insulate feet and legs. If you're stuck without a pad, use extra clothing, the pack, rope, or boots for padding and insulation.

BIVOUACS

A bivouac is a lightweight, no-frills overnight stay—sometimes planned, sometimes not. Climbers plan spartan bivouacs so they can travel fast and light and start high on the mountain. An unplanned bivouac comes as a not-so-pleasant surprise due to injury, bad weather, or getting off route.

Climbers at a planned bivouac camp make sure they have the essentials for a tolerable if not comfortable night, such as a bivy sack or cagoule, perhaps a tarp, some special food, and plenty of clothing.

Climbers at an emergency bivouac also carry everything necessary for survival—all the Ten Essentials and usually a good bit more. You can prepare for your own eventual unplanned bivouac by carrying an emergency shelter in your day pack, in the form of a very light bivy bag or plastic tube tent or even a couple of very large plastic trash bags. Another alternative for shelter from wind and rain is your pack. When it's time to settle down for a bivouac night, put your feet inside the empty pack, and pull the pack's load extension collar (the "bivouac sleeve") up over your legs and hips. Wear a waterproof parka or poncho to take care of the rest of your body.

A low-altitude bivouac might be a fairly comfortable affair, where you can get by comfortably by donning some extra clothing and sitting on a small insulating pad in front of a fire while you enjoy a hot drink. Most bivouacs aren't so pleasant. For a climbing bivouac, you may have to anchor yourselves and your gear to the mountain for safety during the night. Always conserve body heat by taking off wet boots, putting on dry socks and other dry clothes, keeping snow off your clothes, loosening belts and other items that can impede circulation, and putting on all the warm clothing you need or have. Huddle together with your bivouac-mates for as much warmth as possible.

How much clothing and gear should you carry to ensure that you survive a bivouac? The answer depends on a lot of other factors, including your experience, physical condition, and mental attitude. A mountaineer in top shape, who climbs 150,000 feet a year and has a positive outlook, might handle several planned bivouacs and perhaps a couple of emergency overnighters each year with no difficulty. Experience has shown this climber what we all can eventually figure out: how to distinguish that fine line between carrying too much and carrying too little.

FOOD

The art of camping includes the ability to set up a safe and comfortable camp and to provide food that's tasty and nutritious. Because mountaineering is such a strenuous and demanding activity, your body will need water and a variety of foods to provide sufficient carbohydrates, protein, and fats. With planning, it's not hard to choose foods that keep well, are lightweight, and meet your nutritional needs. But don't forget the other requirement of camping food: it must taste good, or you simply won't eat it. If fueling your body quickly and simply is the first aim of alpine cuisine, the enjoyment of doing so is a worthy secondary goal.

COMPOSITION OF FOODS

Each of the three major food components—carbohydrates, protein, and fats—provides energy, and each must be supplied in approximately the right amount to maintain a healthy mind and body. Food intake for mountaineers can go as high as 6,000 calories per day, possibly even more for larger folks. You will have to determine what is best for you depending on how demanding a trip you are planning and your own size, weight, metabolic rate, and level of conditioning.

Carbohydrates are easiest for the body to convert into energy, so they should constitute most of the total calories in your diet. Foods high in carbohydrates provide vitamins, minerals, protein, fiber, water, and essential fats. Good sources of carbohydrates include whole grains, rice, potatoes, cereals, pasta, bread, crackers, and granola bars. Eat small amounts but eat them often for sustained vigor and endurance.

Protein is important to include in your basic diet; the daily requirement is nearly constant regardless of activity. Your body cannot store protein, so once the requirement is met, the excess is either converted to energy or stored as fat. High-protein foods include cheese, peanut butter, nuts, beef jerky, canned meats and fish, powdered milk and eggs, and foil-packaged meals with meat or cheese.

Fats are also an important energy source, especially long-term. During moderate muscular exercise, energy is derived in approximately equal amounts from the body's stores of fats and carbohydrates. Fats occur naturally in small amounts in vegetables, grains, and beans, and when these are combined with fish, red meat, or poultry, your requirements for fat are easily met. High-fat foods include butter, margarine, peanut butter, nuts, canned bacon, salami, beef jerky, sardines, oils, meat, eggs, seeds, and cheese. Fats in the diet serve other functions in addition to providing energy. Stored body fats protect vital organs from shock and act as insulation to protect your body against the thermal stresses of a cold environment.

Eating for endurance

How efficient your body is in using its energy fuels is closely related to physical condition, rest, and nutrition. The better your condition, the greater the efficiency with which food and water will provide energy during heavy exercise. A well-rested, well-fed climber is less likely to experience difficulties from exertion, heat, cold, and illness.

WATER

Water is as vital to life as oxygen. You need it for energy metabolism, controlling your core and body temperature, and for eliminating metabolic wastes. During strenuous activity, particularly at high altitude, the amount of fluids lost through perspiration and evaporation of moisture from the lungs can be as much as 5 quarts or more per day.

If a substantial amount of fluid is lost and not replaced, the body's chemical equilibrium is upset and illness is more likely. The body can survive for a long time without food, but not without water. After hard exercise, replace fluids and carbohydrates as soon as possible. Then continue rehydration throughout the evening in preparation for the next day's activity.

Fluid intake for a 12-hour day of moderate activity in temperate climates should be at least 2 quarts (about 2 liters). For a longer climb or for more severe activity, you will need from 2 to 5 quarts.

The loss of salt through heavy sweating is normally not a problem, as most salts are replaced naturally in a well-balanced diet. If you're concerned about salt intake, you can use ''sports drinks'' that help replenish fluids and supply extra salt, sugar, calories, and minerals. Drinking additional water will also help.

Water sources

Water is sometimes at a premium in the wilderness. On a day trip, you can carry it from home. On longer trips, your sources will be lakes, streams, and snow.

You can often melt some snow for drinking by carrying it packed inside a water bottle. Start with a bit of water already in the bottle in order to hasten the melting time. When there is both sun and enough time, you can set out pots of snow to melt. Or, find a tongue of snow that is slowly melting into a trickle, dredge a depression below, let the water clear, and channel the resulting puddle into a container. You can also try catching the drips from melting overhanging eaves of snow. The most convenient and reliable way to get water on a snow-camping trip is to simply melt snow in a pot on the stove, though this obviously takes time and uses up cooking fuel.

Water purification

Clear, cold water looks pure, but may well be contaminated with harmful bacteria, *Giardia*, or other parasites that inhabit backcountry lakes and streams. For personal protection, it's best to purify all water. Common methods of purification are to put iodine in the water, to boil it (1 minute at sea level, or 5 minutes at 10,000 feet, will kill most bacterial or parasitic contaminants), or to use one of the filtration devices available at outdoors stores.

FOOD PLANNING

Put a reasonable amount of thought and effort into planning, and you should have no trouble ensuring the right combination of foods for optimum performance and enjoyment, whether your trip is for a day or for a week. As a rough general guideline, provide 2 pounds of food per person per day.

On very short trips, you can carry homemade sandwiches, fresh fruits and vegetables, and just about anything else you wish. For trips of two or three days—or longer if base camp is close to the road—any food from the grocery store is fair game. You can concoct a grocery-store stew from items selected almost at random, or by intuition. Canned or packaged items can be cooked together in one pot, then eaten with bread, a hot drink, and a dessert.

Cup-cooking works well for one-person meals. From one pot of hot water, eat each course in sequence from your cup, using instant foods such as soup, potatoes, rice, applesauce, or pudding.

For longer or more complicated trips, weight and packaging become more critical. Then freeze-dried foods are an easy, compact, lightweight option. Outdoors stores carry a large array of these prepackaged meals and snacks, and their variety and quality is constantly improving. They're expensive, but wonderfully convenient. Some require little or no cooking; you just add hot water, soak for a while, and eat from the package. Others are less easily hydrated, and require cooking in a pot. Freeze-dried meals include just about everything: main courses, potatoes, vegetables, soups, breakfasts, and desserts. Persons with access to a food dehydrator can make simple and nutritious foods from fruits, vegetables, and meat at a substantial savings.

Planning for a group

Because meals are social events, small groups often plan all food together. A common, carefully planned menu also reduces the overall weight carried by each person. Another typical arrangement is to leave breakfast and lunch to each individual, with only dinner, the most complicated meal of the day, as a group effort.

The number of people in a cooking group should rarely exceed four. Beyond that, group efficiency is outweighed by the complexities of large pots, small stoves, and longer cooking times. The ideal number is two to three people per stove. For longer trips, an extra stove is a good idea in case one breaks down.

Selecting the menu

A group can pack along just about whatever its members want on a short outing, but longer trips require precise food planning. It takes careful figuring to meet the conflicting goals of moderate-weight packs and plenty of good, nutritious food. You want to avoid unnecessary weight, but at the same time you need to ensure that right down to the last meal, there is enough food for all.

Meals can be planned by the group or by a chosen individual. In either case, the usual procedure is to write down a menu, discuss it with the group, compile an ingredients list, and then go shopping.

Packaging

The elaborate packages of commercial foods are too bulky and heavy for most trips, so repack the food in plastic bags. Place a label or cooking instructions inside each bag, or write on the outside with a felt pen. Smaller packages can be placed in larger ones that are labeled in broad categories, such as "breakfast," "dinner," or "drinks." For precise planning and packaging, a small kitchen scale comes in handy. Items such as jam, peanut butter, and honey pack best in squeeze tubes or in small plastic containers with airtight lids.

MENU SUGGESTIONS

Breakfast

When you're in a hurry to get under way, breakfast is merely the first installment of lunch. For a fast start, prepackage a standard meal before the trip, measuring a prepared cold cereal (such as granola), raisins or other fruit, and powdered milk into a breakfast bag. Stir in water—cold for a cold meal, hot for a hot one—and breakfast is ready.

A hot drink is a pleasant addition to a cold breakfast and a standard element of a hot one. Common choices are instant cocoa, coffee, malted milk, coffee-cocoa (mocha), tea, eggnog, and instant breakfast drinks. Fruit-flavored drinks include hot cider and flavored gelatin.

Other possibilities for breakfast are cooked grains such as oatmeal or rice, toaster pastries, bakery items, dried fruits, nuts, meat or fruit bars, and applesauce. If there's time, you can prepare a full-scale breakfast, with such items as potato slices, hash browns, omelets, scrambled eggs, bacon (canned or bars), and pancakes with syrup (made with brown sugar or syrup crystals).

Lunch and snacks

As soon as breakfast is over, lunch begins and is eaten throughout the day. Eat small amounts and eat often. You should have plenty of food, as half of your daily allotment is for lunch and snacks.

A good munching staple is gorp, a mixture of nuts, candy, raisins, and other dehydrated fruits. One handful makes a snack, several make a meal. Also good for munching is granola, with its mixture of grains, honey or sugar, and perhaps some bits of fruit and nuts. Gorp and granola are available premixed at many food stores or you can make your own. Other snack items are fruit leather and fruit pemmican.

Your basic lunch can include any of the following:

Protein: Canned meats and fish, beef jerky, precooked sausage, meat spreads, cheese, nuts, and seeds (sunflower and others).

Starches: Whole grain breads, bagels, granola and other cereals, crackers, brown-rice cakes, chips or pretzels, and granola bars.

Sugars: Cookies, chocolate, candy bars, hard candy, muffins, pastries, and honey.

Fruit: Fresh fruit, fruit bars, jam, and dried fruit such as raisins, peaches, and apples.

Vegetables: Fresh carrot or celery sticks, cucumbers, etc.

Dinner

The evening meal should have it all. It should be both nourishing and delicious, yet easily and quickly prepared. To supplement your liquid intake, include some items that take a lot of water, such as soup. A cup of soup makes a quick and satisfying first course while the main course is being prepared.

One-pot meals with a carbohydrate base of noodles, macaroni, rice, beans, potatoes, or grains are easy and nutritious. To ensure adequate protein, fat, and flavor, you can add other ingredients such as canned or dried chicken, beef or fish, sausage, freeze-dried vegetables or fruits, butter or margarine, and a dehydrated soup or sauce mix.

Meals from the grocery store are relatively easy to fix and many are quick cooking, such as spaghetti, macaroni, rice mixes, ramen noodles, and instant salads. There are also meals prepackaged in Styrofoam cups: just add boiling water, cover, and let sit for a few minutes, and your dinner is ready.

Freeze-dried meals offer a lot of dinner choices: almond chicken, chili, shrimp newberg, turkey, beef stroganoff, and many more.

A hearty soup can serve as the main course for dinner. Good choices include minestrone, multibean, beef barley, or chicken. Add instant potatoes, rice, crackers, cheese, or bread and the meal is complete. Bouillon is an old favorite that has minimal food value but weighs little and is helpful in replacing water and salt.

Side dishes of freeze-dried vegetables or beans add variety and substance. They can also be added to soup, along with instant rice or potatoes. Precooked beans or processed soy products (in powdered or textured forms) are excellent low-cost protein additions. For those more interested in nutrition and health foods, there are packaged supplements and organic items at stores that specialize in natural foods.

Staples and seasonings

Sugar is a matter of preference. Brown is one-third heavier than white because of moisture, but it's preferred by many for flavor. Instant powdered milk is a good protein supplement that can be added to many dishes. Margarine, which keeps better than butter on long trips, improves the flavor of many foods and is available in liquid or canned form. Dried butter substitutes are available, but they don't have the fat content of the original. For seasonings, try salt, pepper, herbs, garlic, chili powder, bacon bits, dehydrated onions, Parmesan cheese, or a dash of soy sauce.

Drinks and desserts

Cold drinks after a hot day on the mountain are necessary and can be especially satisfying. Lemonade, orange juice, grape juice, and sugar-free drinks are all available in powdered mixes. Just add water. Hot drinks such as cocoa, tea, or mocha taste good after the evening meal.

Occasional full-scale desserts are possible if you've planned the menus carefully. They can include cookies, candy, no-bake cheesecake, applesauce, cooked dried fruit, and that old standard, instant pudding. Freeze-dried desserts include pies, ice cream, and berry cobblers.

HIGH ALTITUDE

High-camp cooking is often difficult because cooking times are longer and conditions can be challenging, at best. Cooking that requires boiling becomes a problem. As you gain altitude and the atmospheric pressure decreases, water boils at lower and lower temperatures. Therefore, it takes longer to cook things. For every drop of about 10 degrees Fahrenheit (or 5 degrees Celsius) in boiling temperature, cooking time is approximately doubled (fig. 3-11). The most suitable foods are those that require only warming, such as canned chicken and instant rice. The weight of the fuel you have to pack is another argument for simple menus.

Fig. 3–11. Boiling point of water

Elevation ft	 m	Temperature °C	 °F	Cooking Time (sea level = 1)
sea level		100°	212°	1.0
5,000	1525	95°	203°	1.9
10,000	3050	90°	194°	3.8
15,000	4575	85°	185°	7.2
20,000	7000	80°	176°	13.0

The rigors of quick visits to higher altitudes require special attention to food. A typical quick gain to a relatively high elevation is the weekend ascent of Mount Rainier in Washington State, where climbers normally spend Friday night near sea level, Saturday night at 10,000 feet (about 3,000 meters), and perhaps only 20 hours after leaving tidewater, reach the 14,411-foot (4,392-meter) summit. Many climbers fall victim to symptoms of mountain sickness, ranging from a slight malaise to vomiting and severe headaches. The abrupt ascent doesn't allow time for acclimatization. Under these conditions it is more difficult to digest large meals because the stomach and lungs are competing for the same blood supply.

To repeat, eat light and eat often, stressing carbohydrates, which are easiest to digest. Bring foods that have proven themselves appealing at high altitude, because climbers often lose their appetite. Trial and error will teach you what foods your body can tolerate at altitude. You must continue to eat and drink, whatever the effort, for the loss of energy from a lack of food or water will only reinforce the debilitating effects of reduced oxygen.

UTENSILS FOR COOKING AND EATING

The simplest eating utensils are a spoon and a single large cup (or small pot). Some people like to add a bowl; bowls are available in plastic, stainless steel, metal, and lexan polycarbonate. Cook sets (fig. 3-12) should be durable and lightweight and nest for convenient carrying. You can get the cook sets in aluminum, stainless steel, and coated cookware for easy cleaning. The size of the set you pack along will vary depending on the needs of a particular trip, but generally you need at least two pots: one for food and one for water. You can even get it down to one if you use only freeze-dried dinners that are rehydrated in their own packaging. Be sure your pots have bails or handles for carrying and tight-fitting lids to conserve heat (and serve as makeshift fry pans).



Fig. 3–12. Cooking accessories: pots and lids; windscreen; utensils and cup.

STOVES

Stoves are now a necessity for backcountry travelers because many camping areas no longer have enough firewood, and others have banned natural-fuel fires. Stoves have a minimal impact on the wilderness and can be used in a variety of conditions.

In choosing a stove, consider a number of factors, including its weight, the altitude and temperature where it will be used, fuel availability, and its reputation for reliability. Whichever stove you select should be easy to start, operate, and maintain, even in cold, wet, or windy conditions.

Practice starting a new stove at home before a trip to be sure it's working and to be sure you know how to operate it. A stove kept in good working order will last for years. Check the stove frequently for dirt and carbon build-up. Stoves with pumps periodically need replacements for deteriorated pump leathers and gaskets. Mountaineering stoves typically weigh 1 to 1$^1/_2$ pounds and burn about an hour on approximately $^1/_2$ pint ($^1/_4$ liter or so) of fuel.

You'll be rewarded with a more productive stove if you make sure it has a wind shield to screen the flame and prevent heat from being blown away. If you don't have a shield for your stove, improvise a way to block the wind. Most mountaineering stoves will boil about 1 quart (approximately 1 liter) of water at sea level in 4 to 8 minutes. Wind can increase the time to as much as 25 minutes, or even prevent boiling.

Some preventive maintenance will help guard against dumping a pot of stew on the ground. Check the stability of the metal framework that supports the pot on the stove. Also see that the stove is solidly supported on the ground. In snow, a small square of Masonite or ensolite serves well as both a smooth base and insulation under the stove.

A direct flame under the pot is desirable for boiling water or melting snow. For heating food, you might consider some means to diffuse the direct heat of the flame, such as a large metal lid. Just place the lid on the burner, then sit the cooking pot on the lid. Some stoves have an adjustment valve that permits you to further control the stove's heat output and prevent scorched food and wasted fuel.

Mountaineers have a range of choices in stove designs (fig. 3-13) and in fuels (with white gas, kerosene, and butane being the most common). All stoves require a means of pressurization to force the fuel to flow to the burner. This is usually provided by a hand pump for white gas and kerosene stoves and by a pressurized cartridge for butane units. All stoves also need a way to vaporize the liquid fuel before it is burned. With white gas and kerosene stoves, a common method is to prime (preheat) the stove by burning a small amount of fuel in a priming cup to start the fuel vaporizing in the main supply line. With butane stoves, the fuel vaporizes inside the pressurized cartridge.

A pump on a stove lets you increase the pressure in the fuel tank; this causes the fuel to burn faster and hotter and brings water to a boil more quickly. Stoves that boil water fastest often do not simmer well, while those with a lower heat output give you more control at lower cooking temperatures.

Stove fuels

White gas is probably the most popular fuel in the United States for mountaineering stoves. It tends to burn hotter than butane and is excellent for melting large amounts of snow, boiling water, or heating food quickly. Unlike kerosene, white gas

Fig. 3–13. Types of outdoor stoves



Kerosene stove: high heat output; requires white gas, alchohol, or lighter fluid for priming.

White gas stove with enclosure: compact carrier for safe, convenient packing.

Butane/propane cartridge stove: uses 80 percent butane/20 percent propane for better cold-weather performance.

White gas stove: white gas only; burns hotter and boils water more quickly than other fuels.

Multi-fuel stove: burns most fuels--white gas, leaded or unleaded automobile gas, aviation gas, deodorized or regular kerosene, Stoddard Solvent No. 1, diesel fuel or No. 1 stove oil; easy to clean; ideal when clean fuel not available.

White gas/kerosene stove: burns either fuel; ideal stove for international use.

Isobutane stove: uses isobutane for best performance in cold weather.

can be used as its own priming agent. Use only refined or white gasoline prepared for pressurized stoves; don't use automotive gasoline, including unleaded gas. The correct fuel is less likely to clog jets, build up excess pressure, or emit toxic fumes. However, spilled white gas evaporates readily, with little odor, and is very flammable.

Kerosene is not as volatile as white gasoline and therefore is safer to transport and store. Kerosene stoves need to be pressurized in addition to being primed with either white gas, alcohol, or lighter fluid. (Liquid kerosene does not burn hot enough to preheat its own burner.) If the burner has not been heated sufficiently, the stove will burn with a sooty yellow flame, producing lots of smoke and carbon. But when it burns efficiently, a kerosene stove has a high heat output, equal to or greater than white gas.

Butane cartridge stoves are popular because of their convenience: easy to light, good flame control, immediate maximum heat output, and no chance of fuel spills. The pressure forces the fuel out as soon as the valve is opened, eliminating both pumping and priming. Most butane stoves are not recommended for temperatures below freezing unless the fuel is warmed. An exception is a stove that uses isobutane fuel, which has performed well at high altitude and in cold, wet conditions. With its windscreen/heat reflector, this stove has proven superior in the wind as well.

The disposable butane cartridges cannot be refilled. Therefore, you may end up leaving home with a cartridge that is only half full because it was already used on an earlier trip. The cartridges are bulky, and all too frequently the spent canisters are found discarded in the wilderness. Pack them out. Another drawback is that the maximum intensity of the flame declines as the fuel is used up (and the pressure in the cartridge drops correspondingly). This problem is partly compensated for at higher elevations, where lower atmospheric pressure means the interior cartridge pressure is relatively higher. Some cartridges cannot be changed until they are empty. Always change cartridges outside your tent because residual fuel in spent canisters can be a fire hazard.

Solid fuels such as candles and canned heat serve primarily as fire starters. They are lightweight and cheap, but provide only limited heat. Most are carried for emergency use only, along with a metal cup for heating small amounts of water.

Foreign travel

On foreign trips, fuel filters may be necessary because a high grade of fuel is often hard to find. Find out beforehand what fuels are available and take an appropriate stove. Kerosene is generally available worldwide, while white gas is not. Check airline restrictions about carrying fuel on planes. Most do not allow it.

Fuel storage

Carry extra fuel in a tightly closed metal container that has a screw top backed up by a rubber gasket. Plastic containers aren't good because fuel gradually diffuses out through the material. Plainly mark the fuel container and stow it in a place where it can't possibly contaminate any food. Some stoves have their fuel bottles directly attached to them, while others require a pouring spout or funnel to transfer the fuel from a storage container to a stove fuel tank.

How much fuel should you take along? It will depend on the conditions of the trip and the food you plan to cook. Will you have to melt snow for water? Will you cook your dinners on the stove or simply heat water for pouring into a food package? Practice and experience will eventually tell you how much fuel you need, but a good beginning would be to bring between $1^1/_2$ and 2 quarts for two people for one week.

Fuel safety

Tents have been blown up, equipment burned, and people injured by careless stove use. Apply rules of safety and common sense. Don't use a stove inside a tent unless it is absolutely necessary. If you must cook in a tent, provide plenty of ventilation to minimize the danger of fuel escaping and igniting. Always change pressurized fuel cartridges, and fill and start liquid-fueled stoves, outside the tent and away from other open flames.

◆ 4 ◆

ROUTEFINDING AND NAVIGATION

Where am I? How can I find my way from here to there? Are we almost there? These are three of the most popular questions in mountaineering, and this chapter shows how to find the answers by using routefinding, orientation, and navigation.

By the time you finish this chapter, you will have a good handle on the tools of navigation and the proven, painfully acquired techniques of top-notch routefinders. You will have the basic knowledge to eventually head into the wilds, work out the way to the mountain, and find the way home.

These tools and techniques are simple and straightforward, but exacting. Study them carefully to help make your mountain adventures successful and keep you safe within the ranks of surviving routefinders. Before you immerse yourself in this chapter, remember two things: Navigation is easy. Navigation is fun. A positive attitude will get you through the learning phase in a hurry and out into the field to use these indispensable skills of mountaineering.

First, a few definitions:

Orientation is the science of determining your exact position on the earth. It requires mastery of map and compass. People who spend a reasonable amount of time and effort usually gain this mastery, even when they have little background or interest in math or science.

Navigation is the science of determining the location of your objective and of keeping yourself pointed in the right direction all the way from your starting point to the destination. Like orientation, this takes map and compass and is a required skill for all wilderness travelers.

Routefinding is the art of locating and following a route that is appropriate to the abilities and equipment of the climbing party. It takes a lot to be a good routefinder: an integrated sense of terrain, distance, and direction; a combination of good judgment, experience, and instinct; and a solid grounding in the technical aspects of orientation and navigation. As with other arts, routefinding skills can be sharpened through practice, regardless of your basic aptitude.

A related activity is *orienteering*, a sport in which participants compete with each other and the clock in finding the way with map and compass to destinations along a structured course. Orienteering is not a part of mountaineering, but mountaineers can learn from those who compete. It is no accident that many of the best routefinders are people who have engaged in orienteering.

TRIP PREPARATION

Routefinding begins at home. Before heading out the door, you need to know not only the name of your wilderness destination, but a great deal about how to get there. The information is accessible to anyone who takes the trouble to seek it out, from guidebooks and maps and from people who have already been there.

Prepare for each trip as if you were going to lead it, even if you aren't. Each person in a climbing group needs to know wilderness navigation and must keep track of where the party has been, where it is, and where it's going. In case of emergency, each climber must be able to get back alone.

Guidebooks provide critical information such as a description of the route, the estimated time necessary to complete it, elevation gain, mileage, and so forth. Climbers who have made the trip will tell you about landmarks, hazards, and routefinding hassles. Useful details are packed into maps of all sorts: Forest Service maps, road maps, aerial maps, sketch maps, and topographic maps. For a trip into an area that's especially unfamiliar, more preparation is needed. This might include scouting into the area, observations from vantage points, or study of aerial photos.

If the route comes from a guidebook or from a description provided by another climber, plot it out on the topographic map you'll be carrying along, noting junctions and other important points. It can help to highlight the route with a yellow felt-tip marking pen, which doesn't obliterate map features. Other maps or route descriptions should be taken along, marked with notes on any more up-to-date information. In selecting the route, consider a host of factors, including the season, weather conditions, the abilities of the party members, and the equipment available.

Before you've even shouldered your pack, you should have a mental image of the route. From experience, and from all the sources of information about the climb, you'll know how to make the terrain work in your favor. To avoid brush, try not to follow watercourses or drainages; select ridges over hillsides and gullies. Clearcuts are often full of slash or brushy second-growth trees, so stick to old-growth forest if possible.

A rock-slide area can be a feasible route—providing you watch carefully for new rockfall. One problem in planning the route, however, is that a rock-slide area may look the same on a map as an avalanche gully, which can have avalanche hazard in winter and spring and be choked with brush in summer and fall. If your sources aren't helpful, only a firsthand look will clear up this question.

The most straightforward return route is often the same as the route going in. If you plan to come back a different way, that route also needs careful advance preparation.

Don't let outdated information ruin your trip. Check beforehand with the appropriate agencies about roads and trails, especially closures, and about climbing routes and regulations, permits, and camping requirements.

THE MAP

A map is a symbolic picture of a place. In convenient shorthand, it conveys a phenomenal amount of information in a form that is easy to understand and easy to carry. No mountaineer should travel without a map or the skill to translate its shorthand into details on the route. Note the publication date of the map because roads, trails, and other features may have changed since that time. Try to use the latest information. A number of different types of maps are available.

Relief maps are the maps that attempt to show terrain in three dimensions by the use of shadings of green, gray, and brown tones, terrain sketching, or raised surfaces. They help in visualizing the ups and downs of the landscape and have some value in trip planning.

Land management and recreation maps are updated frequently and thus are very useful for current details on roads, trails, ranger stations, and other marks of the human hand. They usually show only the horizontal relationship of natural features, without the contour lines that indicate the shape of the land. These maps, published by the U.S. Forest Service and other government agencies and by timber companies, are suitable for trip planning.

Climbers' sketch maps are generally crudely drawn but often make up in specialized route detail what they lack in draftsmanship. These rough and ready drawings can be effective supplements to other map and guidebook information.

Guidebook maps vary greatly in quality—some are merely sketches, while others are accurate modifications of topographic maps. They generally contain useful details on roads, trails, and climbing routes.

Topographic maps are the best of all for climbers. They depict topography, the shape of the earth's surface, by showing contour lines that represent constant elevations above sea level. These maps, essential to off-trail travel, are produced in many countries. As an example of this type of map, we will look in detail at the maps produced by the U.S. Geological Survey (USGS).

USGS TOPOGRAPHIC MAPS

It might be interesting to start this discussion of USGS maps with a refresher on how cartographers divide up the earth. The distance around our planet is divided into 360 units called degrees. A measurement east or west is called *longitude*; a measurement north or south is *latitude*. Longitude is measured 180 degrees, both east and west, starting at the Greenwich meridian in England. Latitude is measured 90 degrees, both north and south, from the equator.

By determining the intersection of longitude and latitude lines, any point on the earth's surface can be pinpointed. New York City, for instance, is situated at 74 degrees west longitude and 41 degrees north latitude. Each degree is divided into 60 units called minutes, and each minute is further subdivided into 60 seconds. On a map, a latitude of 47 degrees, 52 minutes, and 30 seconds north would probably be written like this: 47°52′30″N.

One type of USGS map used by mountaineers covers an area of 15 minutes (that is, $1/4$ degree) of longitude by 15 minutes of latitude. These maps are part of what is called the *15-minute series*. Another type covers an area of 7.5 minutes (that is, $1/8$ degree) of latitude by 7.5 minutes of longitude. These maps are part of the *7.5-minute series*.

The *scale* of a map is a ratio between measurements on the map and measurements in the real world. A common way to state the scale is to compare a map measurement with a ground measurement (as in 1 inch equals 1 mile), or to give a specific mathematical ratio (as in 1:24,000, where any one unit of measure on the map equals 24,000 units of the same measure on the earth). The scale is usually shown graphically at the bottom of a map.

In the USGS 7.5-minute series, the scale is 1:24,000, or roughly $2^1/_2$ inches to the mile, and each map covers an area of approximately 6 by 9 miles. It is the standard topographic map for all of the United States except Alaska.

In the 15-minute series, the scale is 1:62,500, or about 1 inch to the mile, and each map covers an area of four times that of the 7.5-minute series (about 12 by 18 miles). The 15-minute maps are no longer in production and are being replaced by the 7.5-minute series for all states except Alaska. (Most 15-minute maps will be permanently out of print by the mid-1990s.) For Alaska only, the 15-minute maps are still the standard, and the scale is somewhat different: 1:63,360, or exactly 1 inch to the mile. The east–west extent of each Alaska map is actually greater than 15 minutes because the lines of longitude are converging toward the North Pole.

The 15-minute and 7.5-minute maps are the ones that mountaineers use for cross-country routefinding and navigation. The USGS also produces maps that cover larger areas (with such scales as 1:100,000 and 1:250,000), and these are suitable for some trip planning and trail navigation. In some areas, private companies produce maps based on USGS topographic maps, but they are updated with more recent trail and road details and sometimes combine sections of USGS maps. These maps are often useful supplements to standard topographic maps.

How to read a topographic map

Consider this a language lesson, but in a language quite easy to learn and one that pays immediate rewards to any wilderness traveler. Some of this language is in words, but most of it is in the form of symbols drawn on a map. The best way to follow the lesson is to study it along with an actual USGS topographic map. Any one will do.

Each map is referred to as a quadrangle (or quad) and covers an area bounded on the north and south by latitude lines that differ by an amount equal to the map series (7.5 minutes or 15 minutes) and on the east and west by longitude lines that differ by the same amount. Each quadrangle is given the name of a prominent topographic or human feature of the area.

What the colors mean

Colors on a USGS topographic map have very specific meanings. This is what the different colors stand for:

Red: Major roads and survey information.

Blue: Rivers, lakes, springs, waterfalls, and other water-related features. The contour lines of glaciers and permanent snowfields are in solid blue, with their edges indicated by dashed blue lines.

Black: Roads, trails, railroads, buildings, and other features not part of the natural environment.

Green: Areas of substantial vegetation. Solid green marks a forested area while mottled green indicates scrub vegetation. The lack of green doesn't mean there's no vegetation in the area, simply that it is too small or scattered to show on the maps. Don't be surprised if a small, narrow gully with no green color on the map turns out to be choked with slide alder or vine maple.

Brown: Contour lines and elevations.

Purple: Partial revision of an existing map.

Translating contour lines

The heart of a topographic map is its overlay of contour lines, each line indicating a constant elevation as it follows the shape of the landscape. A map's *contour interval* is the difference in elevation between two adjacent contour lines (usually 40 feet on 7.5-minute maps and 80 feet on 15-minute maps). Every fifth contour line is printed darker than other lines and is labeled periodically with elevation.

One of the most important bits of information a topographic map reveals is whether you will be hiking uphill or downhill. If the route crosses lines of increasingly higher elevation, you will be going uphill. If it crosses lines of decreasing elevation, the route is downhill. Flat side-hill travel is indicated by a route that crosses no lines, remaining within a single contour interval.

This is only the start of the picture that contour lines paint of your actual wilderness route. They also show cliffs, passes, summits and other features (fig. 4-1). You will get better and better at interpreting these lines by comparing actual terrain with its representation on the map (fig. 4-2). The goal is to someday glance at a topographic map and realize you have a rather sharp mental image of just what the place will look like. The following listing shows the main features sketched by contour lines.

Flat areas: No contour lines at all.

Gentle slopes: Widely spaced contour lines.

Steep slopes: Closely spaced contour lines.

Cliffs: Contour lines extremely close together or touching.

Valleys, ravines, gullies, couloirs: Contour lines in a pattern of "U's" pointing in the direction of higher elevation, if the valley or gully is gentle and rounded; a pattern of "V's," if the valley or gully is sharp and narrow.

Ridge or spur: Contour lines in a pattern of "U's" pointing in the direction of lower elevation, if the ridge is gentle and rounded; a pattern of "V's," if the ridge is sharp.

Saddle, pass, col: A low point on a ridge, with higher contour lines on each side and often with a characteristic hourglass shape.

Cirques, bowls: Patterns of contour lines forming a semicircle (or as much as three-quarters of a circle), rising from a low spot in the center of the partial circle to form a natural amphitheater at the head of a valley.

Peak: A concentric pattern of contour lines with the summit being the innermost and highest ring. Peaks often are also indicated by X's, elevations, benchmarks (BM), or a triangle symbol.

The margin of a USGS map holds important information, such as date of publication and revision, names of maps of adjacent areas, contour


13
600
PACK
800
4915
4000
3200
5000
3800
3000
3800
2800
4600
3400
4000
2800
6200
5400
Elephant Butte
7380
6800
600
5400
5200
Howard Lake
4600
4600
4800
6352
6308

Nearly flat area
Gentle slope
Steep slope
Cliffs
Gully or couloir
Ridge
Summit
Cirque or bowl
Saddle, pass, or col

Fig. 4–1. Basic topographic features

interval, and map scale. The margin also provides a diagram showing the area's magnetic declination, which is the difference between true north and magnetic north.

Keep a couple of cautionary thoughts in mind as you study a topographic map, because they do have certain limitations. The map won't show all the terrain features you actually see on the climb because there's a limit to what can be jammed onto the map without reducing it to an unreadable clutter. If a feature is not at least as high as the contour interval, it may not be shown, so a 30-foot cliff may come as a surprise in an area mapped with a 40-foot contour interval. Check the date of the map


8
9
10
4
5
7
6
3
15
12
13
2
1
11
14

Fig. 4–2. Photograph of a mountainous area; keyed features are represented on topographic map.

KEY

1. Basin: moderate slope, camp spots
2. Snow or ice line: dashed line ends on cliffs, rock
3. Buttress: change in features of wall may provide approach to ridge
4. Twin summits: which is higher?
5. Gendarmes, aiguilles, or pinnacles
6. Gully or couloir
7. Saddle, pass, or col
8. Rock face
9. Summit: highest point on map
10. Ridge or arete
11. East slope: note shadows and ice accumulation
12. Cirque wall: glacier occupies this cirque
13. Moat
14. Crevasses: indicated by irregular contours, not smooth as near buttress, 3, above
15. Bergschrund: not seen on map but inferred possibility when rock and snow are steep


6600
4
5
7
9
15
14
10
Mount Torment
8100
8815
Forbidden Peak
12
13
7000
7800
11
7200
3
6
8
2
6600
6800
7800
6750
1
8056
740
Boston Basin
641
5'
642
(CASCADE PASS)
1780 I NE
SCALE 1:24 000
GN
MN
1°27'
26 MILS
22°
391 MILS
1
½
0
1000
0
1000
2000
3000
4000
5000
1
5
0
CONTOUR INTERVAL 40 FEET
DOTTED LINES REPRESENT 20-FOOT CONTOURS
DATUM IS MEAN SEA LEVEL

because topographic maps are not revised very often and information on forests and on roads and other manufactured features could be out of date. A forest may have been logged or a road either extended or closed since the last updating. Although topographic maps are essential to wilderness travel, they must be supplemented with information from visitors to the area, guidebooks, and other maps. As you learn about changes, note them on your map.

Sometimes a trip runs through portions of two or more maps. Adjoining maps can be folded at the edges and brought together, or you can create your own customized map by cutting out the pertinent areas and splicing them with tape. Include plenty of territory so that you have a good overview of the entire trip, including surrounding area. Photocopies, good for marking on, don't show colors and may distort, meaning they should be used only in addition to the real thing.

As the precious objects they are, maps deserve tender care in the wilds. A map can be kept in a plastic bag or map case. You can also laminate the map with plastic film or coat it with waterproofing, though these coatings are difficult to mark on. Some maps come already waterproofed. On the trip, carry the map in a jacket pocket or some other easily accessible place so you don't have to take off your pack to get at it.

ORIENTING A MAP

During a trip it sometimes helps to hold the map open so that north on the map is pointed in the actual direction of true north. This is known as orienting the map, a good way to gain a better feel of the relationship between the map and the countryside.

It's a simple process (fig. 4-3). Place your compass on the map, near its declination diagram. Turn the map and compass together until the north-seeking end of the compass needle is aligned with, or parallel to, the magnetic-north arrow on the diagram. The map is now oriented to the scene before you. (This orientation can give a general feel for the area but can't replace the precise methods of orientation and navigation that we will cover later in this chapter.)



Fig. 4–3. Using the compass to orient a map

ROUTEFINDING WITH THE MAP

Before the trip

Most wilderness orientation, navigation, and routefinding is done by simply looking at your surroundings and comparing them with the map.

One useful technique is to identify a navigational "handrail," a linear feature on the map that lies in the same direction you are traveling. The handrail should be within frequent sight of the route, so it can serve as an aid to navigation. Features that can be used from time to time as handrails during a trip include roads, trails, power lines, railroad tracks, fences, borders of fields and meadows, valleys, streams, ridges, lake shores, and the edges of marshes.

A handrail helps in staying on route. Another map technique can help in finding the way home if you've gone off track. This is the "base line," a long unmistakable line that always lies in the same direction from you, no matter where you are during the trip. Pick out the base line on the map during trip planning. It does not have to be something you can see during the trip. You just have to know that it is there, in a consistent direction from you. A base line (sometimes called a catch line) can be a road, the shore of a large lake, a river, trail, power line, or any other feature that's at least as long as your climbing area. If the shore of a distant lake always lies west of your climbing area, you can be sure that heading west at any time will get you to this identifiable landmark. It's not the fastest way to travel, but it saves you from being truly lost.

Also before the trip, anticipate specific route-finding problems. For example, if the route traverses a glacier, you may consider carrying route-marking wands, especially if the weather outlook is marginal. Make a note of any escape routes that can be used in case of sudden bad weather or other setbacks.

During the trip

Get off on the right foot by making sure that everyone understands the route. Gather the crew around a map and take time to discuss the route and make contingency plans in case the party gets separated. Point out on the map where you are and associate the surroundings with the piece of paper in front of you, orienting the map to true north if you wish. This is a good time for everyone to make a mental note of the main features the party will see during the trip, such as forest, streams, or trails.

Along the way, everyone needs to keep associating the terrain with the map. Ignorance of the territory is definitely not bliss for any daydreaming climber who gets separated from the party. Whenever a new landmark appears, connect it with the map. At every chance—at a pass, at a clearing, or through a break in the clouds—update your fix on the group's exact position. Keeping track of progress this way makes it easy to plan each succeeding leg of the trip. It also may turn you into an expert map interpreter because you'll know what a specific valley or ridge looks like compared with its representation on the map.

Look ahead to the return trip

The route always looks amazingly different on the way back. Avoid surprises and confusion by glancing back over your shoulder from time to time on the way in to see what the route should look like on the return. Fix in your mind this over-the-shoulder shape of the route. If you can't keep track of it all, jot down times, elevations, landmarks, and so on in a notebook. A cryptic few words—''7,600, hit ridge''—can save a lot of grief on the descent as a reminder that when the party has dropped to 7,600 feet, it's time to leave the ridge and start down the snow slope.

Think

Your brain is your most valuable navigational tool. As the party heads upward, keep asking yourself questions. How will we recognize this important spot on our return? What will we do if the climb leader is injured? Would we be able to find our way out in a white-out or if snow covered our tracks? Should we be using wands or other route-marking methods right now? Ask the questions as you go and act on the answers. It's a matter of think now or pay later.

Mark the route if necessary

There are times it may be best to mark the route going in so you can find it again going out. This situation can come up when the route is over snowfields or glaciers during changeable weather, in heavy forest, or when fog or nightfall threaten to hide landmarks. On snow, climbers use thin bamboo wands with tiny flags on top to mark the path. (Chapter 12 explains the construction and use of wands.) In the forest, the recommended marker is brightly colored crepe paper in thin rolls. Plastic surveyors' tape is also used.

One commandment here: REMOVE YOUR MARKERS. Markers are litter, and mountaineers never, ever litter. If there's any chance you will not come back the same way and will not be able to remove the markers, be especially sure to use the crepe paper, which will disintegrate over the winter. The plastic tape, on the other hand, might outlive the careless climbers who put it there.

Rock cairns appear here and there as markers, sometimes dotting an entire route and at other times signaling the point where a route changes direction. These heaps of rock are another imposition on the landscape, and they can create confusion for any traveler but the one who put them together—so don't build them. If there comes a time you decide you must, then tear them down on the way out. The rule is different for existing cairns. Let them be, on the assumption someone may be depending on them.

Keep track

As the trip goes on, it may be helpful to mark your progress on the map. Some climbers even note on the map the time that streams, ridges, and other landmarks are reached. Keep yourself oriented so that at any time you can point out your actual position to within $1/2$ mile on the map.

Part of navigation is having a sense of your speed. Given all the variables, will it take your party 1 hour to travel 2 miles or will it take 2 hours to travel 1 mile? The answer is rather important if it's noon and base camp is still 5 miles away. After enough trips into the wilds, you'll be good at estimating wilderness speeds. With a watch and a notebook (or good memory), you can monitor the rate of progress on any single outing. Here are some typical speeds for an average party, though there will be much variation:

- On a gentle trail, with a day pack: 2–3 miles per hour.
- Up a steep trail, with full overnight pack: 1–2 miles per hour.
- Traveling cross-country on gentle terrain, with a day pack: 1,000 feet of elevation gain per hour.
- Traveling cross-country up a moderate slope, with full overnight pack: 500 feet of elevation gain per hour.

In heavy brush, the rate of travel can drop to a third or even a quarter of what it would be on a good trail.

On technical portions of the climb

When the going gets tough, the tough forget about navigation and start worrying about the next handhold. But keep your map and other route information handy for the occasional rests. On rock climbs, don't let the mechanics of technical climbing overwhelm the need to stay on a particular route.

On the summit

Here is your golden opportunity to rest, relax, and enjoy—and to learn more about the area and about map reading by comparing the actual view with the way it looks on the map.

On the summit is the place to lay final plans for the descent, a journey often responsible for many more routefinding errors than the ascent. Repeat the trailhead get-together by discussing the route and emergency strategies with everyone. Stress the importance of keeping the party together on the descent, when some climbers will always want to race ahead while others lag behind.

During the descent

The descent is a time for extra caution as you fight to keep fatigue and inattention at bay. As on the ascent, everyone needs to maintain a good sense of the route and how it relates to the map. Stay together, don't rush, and be even more careful if you're taking a different descent route.

Now imagine your team is almost back to the car after a tough 12-hour climb. You follow a compass bearing right back to the logging road—but is the car to the left or the right? It's a bad ending to a good day if the car is a half-mile to the right and the climbers go left. It will be even worse if the car is parked at the end of the road and a routefinding error takes the party beyond that point and on and on through the woods (fig. 4-4a). The intentional offset (also called ''aiming off'') was invented for this situation (fig. 4-4b). Just travel in a direction that is intentionally offset some amount to the right or the left of where you really want to be. When you hit the road (or the river or the ridge), there will be no doubt about which way to turn.

After the climb

Back home, write a description of the route and of any problems, mistakes, or unusual features, and do it while the details are fresh in your mind. Imagine what you would like to know if you were



Fig. 4–4. Navigating to a specific point on a line: a, inevitable minor errors can sometimes have disastrous consequences; b, to avoid such problems, follow a course with an intentional offset.

about to make the climb for the first time, so you'll be ready with the right answers when another climber asks about it. If the guidebook was confusing or wrong, take time to write to the publisher.

THE COMPASS

The compass is a very simple device that can do a wondrous thing. It can reveal at any time and any place exactly what direction you are heading. On a simple climb in good weather, the compass may never leave your pocket. But as the route becomes more complex or the weather worsens, it comes into its own as a critical tool of mountaineering.

A compass is nothing more than a magnetized needle that responds to the earth's magnetic field. Compass-makers have added a few things to this basic unit in order to make it easy to read accurately. But stripped to the core, there's just that needle, aligned with the earth's magnetism, and from that we can figure out any direction.

These are the basic features (fig. 4-5a) of a mountaineering compass:

- A freely rotating magnetic needle. One end is a different color from the other so you can remember which end is pointing north.
- A circular rotating housing for the needle. This is filled with a fluid that dampens (reduces) the vibrations of the needle, making readings more accurate.
- A dial around the circumference of the housing. The dial is graduated clockwise in degrees from 0 to 360.
- An orienting arrow and a set of parallel meridian lines. These are located beneath the needle.
- An index line. Read bearings here.
- A transparent, rectangular base plate for the entire unit. This includes a direction-of-travel line (sometimes with an arrow at one end) to point toward your objective. The longer the base plate, the easier it is to get an accurate reading.

The following are optional features (fig. 4-5b) available on some mountaineering compasses:

- Adjustable declination arrow. It's well worth the added cost because it's such an easy, dependable way to correct for magnetic declination.
- Sighting mirror. This provides another way to improve accuracy.
- Ruler. This is calibrated in inches or millimeters.



Fig. 4–5. Features of mountaineering compasses: a, essential features; b, useful optional features.

Use it for measuring distances on a map.

- Clinometer. Use it to measure the angle of a slope. It can help resolve arguments over the steepness of slopes, and it can determine if you are on the higher of two summits. If there is an upward angle between you and the top of another mountain, then the other summit is higher.
- Magnifying glass. Use it to help read closely spaced contour lines.

The small, round, cheap compasses without base plates are not precise enough for mountaineering, nor can they be used for precise work with a map. For routefinding, the compass must be accurate to within 1 or 2 degrees. A larger margin of error, say 5 degrees, would land a mountaineering party 1/2 mile off target at the end of a 6-mile hike.

BEARINGS

A bearing is the direction from one place to another, measured in degrees of angle with respect to an accepted reference line. This reference is the line to true north.

The round dial of a compass is divided just as cartographers divide the earth, into 360 degrees. The direction in degrees to each of the cardinal directions, going clockwise around the dial starting from the top, is: north, 0 degrees (the same as 360 degrees); east, 90 degrees; south, 180 degrees; and west, 270 degrees.

The compass is used for two basic tasks regarding bearings:

1. The compass is used to *take* bearings. (You can also say that the compass is used to *measure* bearings.) To take a bearing means to measure the direction from one point to another, either on a map or on the ground.
2. The compass is used to *plot* bearings. (You can also say that the compass is used to *follow* a bearing.) To plot a bearing means to set a specified bearing on the compass and then to plot out, or to follow, where that bearing points, either on a map or on the ground.

Bearings on the map

The compass is used as a protractor to both measure and plot bearings on a map. Magnetic north and magnetic declination have nothing to do with these calculations. Therefore, ignore the magnetic needle. Never make any use of the magnetic needle when taking or plotting bearings on a map. (The only time the magnetic needle is used on the map is whenever you choose to orient the map to true north, which was explained earlier in this chapter. But there's no need to orient the map simply in order to measure or plot bearings.)

To take (measure) a bearing on the map: Place the compass on the map with one long edge of the base plate running directly between two points of interest. As you measure the bearing from

Point A to Point B, see that the direction-of-travel line is pointing in the same direction as from A to B. Then turn the rotating housing until its set of meridian lines is parallel to the north–south lines on the map. (Be sure the orienting arrow that turns with the meridian lines is pointing to the top of the map, to north. If you point it toward the bottom, your reading will be 180 degrees off.)

Now read the number that is at the index line. This is the bearing from Point A to Point B.

In the example shown in figure 4-6, the bearing from Point A, Panic Peak, to Point B, Deception Dome, is 40 degrees.

If your map doesn't happen to have north–south lines, just draw some in, parallel to the edge of the map and at intervals of an inch or two.



Fig. 4–6. Measuring a bearing on a map with the compass as a protractor

To plot (follow) a bearing on the map: In this case you are starting with a known bearing. And where does that bearing come from? From an actual landscape compass reading. Let's take a hypothetical example (fig. 4-7): A friend returns from a trip, disgusted at himself for leaving his camera somewhere along the trail. During a rest stop, he had taken some pictures of Mount Magnificent. At the same time, he had taken a bearing on Mount Magnificent and found it to be 135 degrees. That's all you need to know. You're heading into that same area next week, so get out the Magnificent quadrangle, and here is what you do:



Fig. 4–7. Plotting a bearing on a map with the compass as a protractor

First set the bearing of 135 degrees at the compass index line. Place the compass on the map, one long edge of the base plate touching the summit of Mount Magnificent, with the direction-of-travel line pointing toward Mount Magnificent. Rotate the entire compass (not just the housing) until the meridian lines are parallel with the map's north–south lines, and make sure the edge of the base plate is still touching the summit. Again, be sure the orienting arrow points to the top of the map, toward north. Follow the line made by the edge of the base plate, heading in the opposite direction from the direction-of-travel line because the original bearing was measured toward the mountain. Where the line crosses the trail is exactly where your friend's camera is (or was).

Bearings in the field

Now the magnetic needle gets to do its job. All bearings in the field are based on where the needle points. For the sake of simplicity in these first two examples, we will ignore the effects of magnetic declination, a subject that will be taken up in the next section. Let's imagine we are taking the bearings in Ohio, which happens to be along the line of zero declination.



Fig. 4–8. Taking a compass bearing in the field in an area with zero declination

To take (measure) a bearing in the field: Hold the compass in front of you and point the direction-of-travel line at the object whose bearing you want to find. Rotate the compass housing until the pointed end of the orienting arrow is aligned with the north-seeking end of the needle. Read the bearing at the index line (fig. 4-8). And that's all there is to it.

If the compass has no sighting mirror, hold it at or near arm's length and at or near waist level. With a sighting mirror, hold the compass at eye level with the sight pointing at the object. Observe the magnetic needle and the orienting arrow in the mirror as you rotate the housing to align the needle and the arrow. In either case, hold the compass level. Keep it away from ferrous metal objects, which can easily deflect the magnetic needle.

To plot (follow) a bearing in the field: Simply reverse the process used to take a bearing. Start by rotating the compass housing until you have set a desired bearing at the index line, say 270 degrees (due west). Hold the compass level in front of you and then turn your entire body until the north-seeking end of the magnetic needle is aligned with the pointed end of the orienting arrow. The direction-of-travel line is now pointing due west. And that's all there is to that.

MAGNETIC DECLINATION

A compass needle is attracted to *magnetic* north, while most maps are oriented to a different point on the earth, the *geographic* north pole (''true north''). This difference between the direction to true north and the direction to magnetic north, measured in degrees, is called *magnetic declination*. A simple compass adjustment or modification is necessary to correct for magnetic declination.

In areas west of the line of zero declination, the magnetic needle points somewhere to the east (to the right) of true north (fig. 4-9), so these areas are said to have *east declination*. It works just the opposite on the other side of the line of zero declination. Here, the magnetic needle points somewhere to the west (left) of true north, so these areas have *west declination*.

Consider a mountain traveler in Colorado, where the declination is 14 degrees east. The true bearing is a measurement of the angle between the line to true north and the direction-of-travel line. The magnetic needle, however, is pulled toward magnetic north, not true north. So instead it measures the angle between the line to magnetic north and the direction-of-travel line. This ''magnetic bearing'' is 14 degrees less than the true bearing. To get the true bearing, you must add 14 degrees to the magnetic bearing.

Like those in Colorado, climbers in all areas west of zero declination must add the declination to the magnetic bearing. In central California, for example, about 18 degrees must be added. In Washington State, it is about 20 degrees.

East of the zero-declination line, the declination is subtracted from the magnetic bearing. In Maine, for example, the magnetic bearing is 20 degrees greater than the true bearing. Subtracting the declination of 20 degrees gives a wilderness traveler in Maine the true bearing.

This is all very simple in theory but can be confusing in practice, and the wilderness is no place to practice mental arithmetic that can have life-and-death consequences. A more practical way to handle the minor complication of declination is to pay somewhat more for your compass and get one with an adjustable declination arrow instead of a fixed orienting arrow. The declination arrow can be easily set for any declination. Then the bearing you read at the index line will automatically be the true bearing, and concern about a declination error is one worry you can leave at home.

On compasses without adjustable declination ar-


To True North
To Magnetic North
Zero declination line
To Magnetic North
20°
To True North
Magnetic Bearing
14°
Magnetic Bearing
True Bearing
20° East
True Bearing
20° West
18° East
10° West
4° West
14° East
Zero
10° East
4° East

Fig. 4–9. Relationship between true and magnetic north in the United States

rows, you can get the same effect by sticking a thin strip of tape to the top or bottom of the rotating housing to serve as a customized declination arrow. Trim the tape to a point, with the point aimed directly at the specific declination for the area where you will be climbing.

In Colorado, your taped declination arrow must point at 14 degrees east (clockwise) from the 0 point (marked N for north) on the rotating compass dial (fig. 4-10a). In Maine, the declination arrow must point at 20 degrees west (counterclockwise) from the 0 point on the dial (fig. 4-10b). In Wash-


a
COLORADO
270
W
180
S
N
0
20
14°
E
90
DECLINATION ARROW
DECLINATION ARROW
b
270
W
340
20°
180
S
N
0
20
E
90
MAINE

Fig. 4–10. Compass declination corrections: a, for the area west of the zero-declination line; b, for the area east of the zero-declination line.

ington State, the declination arrow must point at 20 degrees east (clockwise) from the 0 point.

To take or to follow a bearing in the field, follow exactly the same procedure used in the earlier examples from Ohio, where the declination is zero. The only difference is that from now on, you will align the magnetic needle with the declination arrow instead of with the orienting arrow.

From here on in this chapter, it is assumed you are using a compass with a declination arrow—either an adjustable arrow or a taped arrow that you have added. For all bearings in the field, you will align the needle with this declination arrow. Unless otherwise stated, all bearings referred to are true bearings, not magnetic.

PRACTICING WITH THE COMPASS

Before you count on your compass skills in the wilderness, test them in the city. The best place to practice is a place where you already know all the answers, like a street intersection where the roads run north–south and east–west.

Take a bearing in a direction you know to be east. When you have lined up the declination arrow with the magnetic needle, the number at the index line should be 90 degrees, or within a few degrees of 90. Repeat for the other cardinal directions, south, west, and north. Then do the reverse. Pretend you don't know which way is west. Set 270 degrees (west) at the index line and hold the compass in front of you as you turn your entire body until the needle is again aligned with the declination arrow. The direction-of-travel line should now point west. Does it? Repeat for the other cardinal directions. This set of exercises will help develop precision and self-confidence at compass reading and also is a way to check the accuracy of the compass. And if you make a mistake or two, well, no harm done.

Look for chances to practice in the mountains. A good place is any known location—such as a summit or a lake shore—from which you can see identifiable landmarks. Take bearings as time permits, plot them on the map, and see how close the result is to your actual location.

CAUTIONS ABOUT COMPASS USE

As you've gathered by now, there's a big difference between using a compass for working with a map and using a compass for field work. When measuring and plotting bearings on a map, the compass needle is ignored. Just align the meridian lines on the compass housing with the north–south lines on the map. In the field, you *must* use the magnetic needle.

You may have heard that metal can mess up a compass reading. It's true. Ferrous objects—iron, steel, and other materials with magnetic properties—will deflect the magnetic needle and produce false readings, as will a battery-powered watch that is within 6 inches of a compass. Keep the compass away from belt buckles, ice axes, and other metal objects. If a compass reading doesn't seem to make sense, see if it's being sabotaged by nearby metal.

Keep your wits about you when pointing the declination arrow and the direction-of-travel line. If either is pointed backward—an easy thing to do—the reading will be 180 degrees off. If the bearing is north, the compass will say it's south. Remember that the north-seeking end of the magnetic needle must be aligned with the pointed end of the declination arrow. And that the direction-of-travel line must point from you to the objective, not the reverse.

There's yet another way to introduce a 180-degree error in a compass reading. The way to do it is to align the compass meridian lines with the north–south lines on a map, but have the declination arrow pointing backward. The way to avoid this is to check that your declination arrow is pointing more or less to north (rather than more or less to south). This check has nothing to do with declination. It just happens that the arrow is placed in a convenient spot to serve as a reminder of which way to direct the meridian lines.

If in doubt, trust your compass. The compass, correctly used, is almost always right, while your contrary judgment may be clouded by fatigue, confusion, or hurry. If you get a nonsensical reading, check to see you aren't making one of those 180-

degree errors. If not, and if there is no metal in sight, verify the reading with other members of the party. If they get the same answer, trust the compass over hunches, blind guesses, and intuition.

THE MAP AND COMPASS: A CHECK LIST

Do you have the hang of it? Let's run through the whole procedure. Check off each step as you do it.

To take (measure) a bearing on a map:

1. Place compass on map, with edge of base plate joining two points of interest.
2. Rotate housing to align compass meridian lines with north–south lines on map.
3. Read bearing at index line.

To plot (follow) a bearing on a map:

1. Set desired bearing at index line.
2. Place compass on map, with edge of base plate on feature from which you wish to plot bearing.
3. Turn entire compass to align meridian lines with map's north–south lines. The edge of the base plate is the bearing line.

To take (measure) a bearing in the field:

1. Hold compass level, in front of you, and point direction-of-travel line at desired object.
2. Rotate housing to align declination arrow with magnetic needle.
3. Read bearing at index line.

To plot (follow) a bearing in the field:

1. Set desired bearing at index line.
2. Hold compass level, in front of you, and turn your entire body until magnetic needle is aligned with declination arrow.
3. Travel in direction shown by the direction-of-travel line.

And for the last time:

- Never use the magnetic needle or the declination arrow when measuring or plotting bearings on the map (except to check that the declination arrow is pointing more or less north on the map, not south, as a check that the compass meridian lines are not upside-down).
- When taking or following a bearing in the field, always align the pointed end of the declination arrow with the north-seeking end of the magnetic needle.

THE ALTIMETER

An altimeter (fig. 4-11), like a compass, provides one simple piece of information that forms the basis for a tremendous amount of vital detail. The compass merely points the direction to magnetic north. The altimeter merely gives the elevation. But by monitoring the elevation and checking it against the topographic map, mountaineers keep track of their progress, pinpoint their location, and find the way to critical junctions in the route. Every climbing party should have an altimeter.

An altimeter is basically a modified barometer. A barometer measures air pressure (the weight of air) and displays it on a scale calibrated in inches or millimeters of mercury, or in millibars. Because air pressure decreases at a uniform rate with increasing altitude, a barometer can measure elevation if it is fitted with a scale calibrated in feet or meters instead of units of pressure.

To read a mountaineering altimeter, begin by holding it level in the palm of one hand. Look directly down on the needle, your eyes at least a foot above it, to reduce errors due to viewing



Fig. 4–11. Typical altimeters

angle. Tap it lightly several times to overcome slight friction in the mechanism, and then take an average of several readings. The elevations determined by an altimeter are only approximate because the instrument is strongly affected by variations in temperature and weather. Check the reading whenever you reach a point of known elevation so you can reset it if necessary.

HOW ALTIMETERS AID MOUNTAINEERS

The altimeter helps in deciding whether to continue a climb or to turn back, by letting you calculate your rate of ascent. Let's say you have been keeping an hourly check on time and elevation during a climb. It has taken the party 4 hours to climb 3,000 feet, an average of 750 feet per hour. But you know that the actual rate of ascent has been declining with each hour. In fact, the party gained only 500 feet in the past hour, compared with 1,000 feet the first hour. You know that the summit is at an elevation of 8,400 feet, and an altimeter reading shows you're now at 6,400. So you can predict that it will take roughly 4 more hours to reach the summit. Take that information, courtesy of the altimeter, combine it with a look at the weather, the time of day, and the condition of the climbers, and you have the data on which to base a sound decision.

An altimeter also can help determine exactly where you are. If you are climbing a ridge shown on the map, but don't know exactly where you are along the ridge, check the altimeter for the elevation. Where the ridge reaches that contour line on the map is your likely location.

Another way to ask the altimeter where you are is to start with a compass bearing to a summit or some other known feature. Find that peak on the map, and plot the bearing line from the mountain back toward the climbing party. You now know you must be somewhere along that line. But where? Take an altimeter reading and find out the elevation. Where the compass bearing line crosses a contour line at that elevation is your likely location. This could lead to an ambiguous answer, of course, because the line might cross that contour at several points. That's when you turn to further observations, common sense, and intuition.

Navigation gets easier with the aid of an altimeter. If you top a convenient couloir at 9,400 feet and gain the summit ridge, make a note of that elevation. On the way back, descend the ridge to that elevation and you will easily find the couloir again.

Guidebook descriptions sometimes specify a change in direction at a particular elevation. If it's on an open snowfield or a forested hillside, good luck in making the turn at the right place without an altimeter. The route you have worked out on a topographic map also may depend on course changes at certain elevations, and again the altimeter will keep the party on target. An altimeter obviously helps in mapping, providing elevations of key points along routes included on the map.

Last but not least, an altimeter will reveal if you're on the real summit when the visibility is too poor to be able to tell by looking around.

HOW TO GET THE MOST FROM YOUR ALTIMETER

Knowing all the facts about an altimeter—the pluses and minuses—will make it as valuable as possible in the wilderness. First of all, keep in mind that temperature and weather are always working their will on an altimeter's accuracy. A high-pressure weather area will tend to cause a lower elevation reading than a low-pressure area. Warmer, lighter air will tend to result in a higher elevation reading than colder, heavier air.

There's no need to be surprised if an elevation reading of 5,200 as you go to sleep turns into 5,300 when you wake up the next morning, even though the tent appears to be in the same spot. The elevation hasn't changed, but the weather has, and with it, the air pressure that is the basis for an altimeter's determination of elevation. That's just the way altimeters are, and as with any good friend, you've got to accept them despite their bad habits. The best way to keep them relatively honest is to check the reading at every known elevation point and reset the altimeter accordingly. Topographic maps give the correct elevations of many of the features you encounter on a trip, such as trailheads, lakes, and summits.

Try to keep the temperature of the altimeter relatively constant, perhaps by carrying it in your pocket. The altimeter expands and contracts due to variations in its temperature, causing changes in the indicated elevation. A bimetallic element in temperature-compensated altimeters adjusts for this effect of temperature when there is no actual change in elevation. The element counterbalances the effect on other parts of the instrument. When you are gaining or losing elevation, however, this adjustment sometimes is not enough, resulting in errors even in altimeters that are temperature-compensated.

The altimeter can help in predicting weather. The altimeter and barometer scales operate in opposition to each other. When one goes up, the other goes down. An altimeter reading showing an increase in elevation when no actual elevation change has taken place (such as at camp overnight) means a falling barometer, which generally indicates deteriorating weather. A decreasing altimeter reading, on the other hand, means increasing barometric pressure, generally associated with improving weather. This is an oversimplification, of course, as weather forecasting is complicated by the wind, local weather peculiarities, and the rate of barometric pressure change. Stay observant on climbing trips if you want to figure out the relationship between weather and altimeter readings in your area.

Because even the most accurate and costly altimeters bow to the weather, don't be misled into trusting them to accuracies greater than are possible. A typical high-quality altimeter may have a scale of resolution (smallest marked division) of 20 feet and a stated accuracy of plus-or-minus 30 feet. This doesn't mean the altimeter will always be that close to the truth. Get to know your own altimeter, use it often, check it at every opportunity, and note differences of opinion between it and the map. You'll soon know just what accuracy to expect, and it will then be a dependable aid to roving the wilds.

ORIENTATION BY INSTRUMENT

Figuring out exactly where you are is usually a relatively simple affair, just looking around and comparing what you see with what is on the map. Sometimes this is not accurate enough, or there is just nothing much nearby to identify on the map. The usual solution then is to get out the compass and try for bearings to some faraway landscape features. This is orientation by instrument.

The goal of orientation is to determine that precise point on the earth where you now stand. Your position can then be represented by a mere dot on the map which is known as your *point position*. There are two lower levels of orientation. One is called *line position*: the travelers know they are along a certain line on a map—such as a river, a trail, or a bearing line—but they do not know where they are along the line. The lowest level is *area position*: they know the general area they are in, but that's about it. The primary objective of orientation is to find out your exact point position.

POINT POSITION

With point position known, there is no question about where you are, and you can use that knowledge in identifying on the map any major feature visible on the landscape. You can also identify on the landscape any visible feature shown on the map.

For example, climbers on the summit of Forbidden Peak know their point position. It's at the top of Forbidden Peak. (You can refer back to the Forbidden topographic map, fig. 4-2.) They see an unknown mountain and want to know what it is. They take a bearing and get 275 degrees. They plot 275 degrees from Forbidden Peak on their topographic map, and it passes through Mount Torment. They conclude that the unknown peak is Mount Torment.

However, if you start by wanting to find Mount Torment, do the map work first. The climbers measure the bearing on the map from where they are, Forbidden, to Mount Torment, and come up with 275 degrees. Keeping 275 at the index line on the compass, one climber holds the compass out and turns until the magnetic needle is aligned with the declination arrow. The direction-of-travel line then points to Mount Torment.

LINE POSITION

With line position known, the goal is to determine point position. Knowing they are on a trail, ridge, or some other identifiable line, the climbers need only one more piece of information. For example, they are on Unsavory Ridge (fig. 4-12)—but exactly where? Off in the distance is Mount Majestic. A bearing on Majestic indicates 220 degrees. Plot 220 degrees from Mount Majestic on the map. Run this line back toward Unsavory Ridge, and where it intersects the ridge is exactly where the climbers are.



Fig. 4–12. Orientation with line position known

AREA POSITION

The climbers know their area position: they are in the general area of Fantastic Crags (fig. 4-13). They want to determine line position and then, from that, point position. To move from knowing area position to knowing point position, two trustworthy pieces of information are needed.

The climbers may be able to use bearings on two visible features. They take a bearing on Mount Majestic and get a reading of 40 degrees. They plot a line on the map, through Mount Majestic, at 40 degrees. They know they must be somewhere on that bearing line, so they now have line position. They can also see Unsavory Spire. A bearing on the spire shows 130 degrees. They plot a line on the map, through Unsavory Spire, at 130 degrees. The two bearing lines intersect, and that's where they are.



Fig. 4–13. Orientation with area position known

When you know the area position and there is just one visible feature to take a bearing on, the compass can't provide anything more than line position. That can be a big help, though. Climbers in the general vicinity of Fantastic River then know they are near where the bearing line plotted from the one feature intersects the river. Perhaps from a study of the map they can then figure out just where they are. They can also read the altimeter and see on the map where the bearing line intersects the contour line for that elevation. The closer an angle of intersection is to 90 degrees, the more accurate the point position will be.

Use every scrap of information at your disposal, but be sure your conclusions agree with common sense. If the climbers who took bearings on Mount Majestic and Unsavory Spire find that the two lines on the map intersect in the river, but the climbers are on a high point of land, something is wrong. Try again. Try to take a bearing on another landmark, and plot it. If lines intersect at a map location with no similarity to the terrain, there might be some magnetic anomaly in the rocks, or you may have an inaccurate map. And who knows? Maybe those peaks weren't really Majestic and Unsavory in the first place.

NAVIGATION BY INSTRUMENT

Getting from here to there is usually just a matter of keeping an eye on the landscape and watching were you're going, helped by an occasional glance at the map. However, if the current objective is out of sight, you can take compass in hand, set a bearing, and follow the direction-of-travel line as it guides you to the goal. This is navigation by instrument. Sometimes this is the only practical method for finding the pass or base camp or whatever. It also serves as a supplement to other methods and a way of verifying that you're on the right track. Again, use common sense and challenge a compass bearing that defies reason. (Is your declination arrow pointing the wrong way, sending you 180 degrees off course?)

MAP AND COMPASS

The most common situation requiring instrument navigation comes when the route is unclear because the topography is featureless or because landmarks are obscured by forest or fog. You do know exactly where you are and where you want to go, and can identify both the current position and the destination on the map. Simply measure the bearing from your position to your objective on the map, then follow that bearing. Let's say you get a bearing of 285 degrees (fig. 4-14a). Read this bearing at the index line and leave it set there as is (fig. 4-14b). Hold the compass out in front of you as you rotate your body until the north-seeking end of the magnetic needle is aligned with the pointed end of the declination arrow. The direction-of-travel line now points to the objective (fig. 4-14c). Start walking.

COMPASS ALONE

Navigators of air and ocean often travel by instrument alone; so can climbers. For example, if



Fig. 4–14. Navigation using the map and compass: a, measuring the bearing from point A to point B on the map; b, bearing at index line; c, following the bearing.

you are scrambling toward a pass and clouds begin to obscure it, take a quick compass bearing. Then follow the bearing, compass in hand if you wish. You don't even have to note the numerical bearing; just align the magnetic needle with the declination arrow and keep it aligned. Likewise, if you are heading into a valley where fog or forest will hide the mountain that is your goal, take the bearing to the peak before you drop into the valley (fig. 4-15). Then navigate by compass through the valley. This method becomes more reliable if several people travel together with compass in hand, checking each other's work.

USING INTERMEDIATE OBJECTIVES

A handy technique is available for those frustrating times you try to stay exactly on a compass bearing, but keep getting diverted by obstructions such as cliffs, dense brush, or crevasses. Try the technique of intermediate objectives. Sight past the obstruction to a tree or rock or other object that is exactly on the bearing line to the principal objective (fig. 4-16a). Then you're free to scramble over to the tree or rock by whatever route is easiest. When you get there, you can be confident that you


Take bearing on your objective while you can see it
DESTINATION
Ridgetop, from which you can see your destination
ROUTE
ROUTE
Valley, where view of objective is hidden by forest or fog
ROUTE
ROUTE

Fig. 4–15. Following a compass bearing when the view of the objective is obscured by forest or fog


a
ORIGIN
ACTUAL ROUTE
Hole
Big rock with split top
Rock
Funny-looking tree
with right side missing
near ground
PLANNED
ROUTE
Brush
Dead silver snag
Fallen tree
DESTINATION
b
DESIRED
DIRECTION
OF
TRAVEL
ORIGIN
Crevasse
Party
member
Crevasse
ACTUAL PATH
OF TRAVEL
DESTINATION

Fig. 4–16. Use of intermediate objectives: a, in a forest; b, on a glacier.

are still on the correct route. The technique is useful even when there is no obstruction. Moving from intermediate objective to intermediate objective means you can put the compass away for those short stretches rather having to check it every few steps.

Sometimes on snow or in fog, there *are* no natural intermediate objectives, just a white, undifferentiated landscape. Then another member of the party can serve as the target (fig. 4-16b). Send that person out to near the limit of visibility. Wave this new intermediate objective left or right, directly onto the bearing line. That person can then improve the accuracy of the route by taking a "back bearing" to you. (For a back bearing, keep the same bearing set at the index line, but for this purpose, align the *south-seeking* end of the magnetic needle with the pointed end of the declination arrow.) The combination of a bearing and a back bearing tends to counteract any compass error.

LOST

Why do people get lost? Lots of reasons. Some travel without a map because the route seems obvious. Others fail to check on recent changes in roads and trails. Some folks trust their own instincts over the compass. Others do not bother with the map homework that can start them off with a good mental picture of the area. Some don't pay enough attention to the route on the way in to be able to find it on the way out. Some rely on the skill of their climbing partner, who is just now in the process of getting them lost.

Why *do* people get lost? They don't take the time to think about where they are going, because they are in a hurry. They miss junctions or wander off on game trails. They charge mindlessly ahead despite deteriorating weather and visibility, fatigue, or flagging spirits.

Good navigators are never truly lost—but having learned humility through years of experience, they always carry enough food, clothing, and bivouac gear to get them through hours or even days of temporary confusion.

WHAT IF YOUR PARTY IS LOST?

The first rule is to STOP. Avoid the temptation to plunge hopefully on. Try to determine where you are. If that doesn't work, figure out the last time the group *did* know its exact location. If that spot is fairly close, within an hour or so, retrace your steps and get back on route. But if that spot is hours back and you can at least make an intelligent guess about the current position, continue forward, but cautiously and with a sharp eye out for landmarks. If the party tires or darkness falls before you find the route, bivouac for the night.

Groups of two or more rarely become dangerously lost, even if they have no wilderness experience. The real danger comes to an individual who is separated from the rest of the party. For this reason, always try to keep everyone together, and assign a rear guard to keep track of the stragglers.

WHAT IF YOU ARE LOST ALONE?

Again, the first rule is to STOP. Look around for other members of the party, shout, and listen for answering shouts. If the only answer is silence, sit down, try to regain your calm, and combat terror with reason.

Once you've calmed down, start doing the right things. Look at your map in an attempt to determine your location, and plan a route home in case you don't connect with the other climbers. Mark your location with a cairn or other objects, and then scout in all directions, each time returning to the marked position. Well before dark, prepare for the night by finding water, firewood, and shelter. Staying busy will raise your spirits. Keep a fire going to give searchers something to see, and try singing so you will have something to do and they will have something to hear.

The odds are that you will be reunited with your group by morning. If not, fight panic. After a night alone, you may decide to hike out to a base-line feature you picked out before the trip—a ridge or stream or highway. If the terrain is too difficult to travel alone, it might be better to concentrate on letting yourself be found. It's easier for rescuers to find a lost climber who stays in one place in the open, builds a fire, and shouts periodically, than one who thrashes on in hysterical hope, one step ahead of the rescue party.

FREEDOM OF THE HILLS

The wilderness awaits those who have learned the skills of routefinding and navigation. In large part, routefinding is the subject of this entire book because it is so essential to all off-trail adventure.

In medieval times the greatest honor a visitor could receive was the rights of a citizen and the freedom of the city, sometimes even today symbolized by presenting a guest with the ''keys to the city.'' For the modern alpine traveler, routefinding is the key to wandering at will through valleys and meadows, up cliffs and over glaciers, earning the rights of a citizen in a magical land, a mountaineer with the freedom of the hills.

◆ 5 ◆

WILDERNESS TRAVEL

Climbing the mountain is one thing. Getting from the car to the mountain is another. Wilderness travel is the art of getting there—across streams, around brush, along trails, and over snow.

When climbers leave the trailhead deep in a valley of Washington State's Cascade range or head inland from the beach of a British Columbia fiord, tough wilderness travel may lie ahead. The techniques of muddling through brush are not as glamorous as fifth-class rock climbing, but many a peak has been lost in thickets of slide alder. The biggest barriers on the way to a mountaintop often appear below snow line. Learn the skills of wilderness travel and you open the gateway to the summit.

WILDERNESS ROUTEFINDING

Routefinding is the art of working out an efficient route that is within the abilities of the climbing party. Navigation, on the other hand, is the science of using map and compass, and often an altimeter, to determine the location of the objective and to keep moving in the right direction toward it. Navigation points the way from where you are to where you want to be, but it takes skill in routefinding to surmount the hazards and hurdles between here and there. Intuition and luck play a role in routefinding, but there also are principles that can be learned. And there is no substitute for firsthand experience. Climb with experienced mountaineers, watch their techniques, and ask questions. Routefinding is one of the most satisfying of mountain crafts to master.

Each mountain range has its own peculiarities of geology and climate that affect routefinding. Mountaineers familiar with the Canadian Rockies, accustomed to broad valleys and open forests, will need to learn new rules to contend with the heavily vegetated, narrow canyons of British Columbia's Coast Range. The Pacific Northwest mountaineer used to deep snow at 4,000 feet in June will discover drastically different June conditions in the Sierra. Prolonged mountaineering in a single range teaches the lore of routefinding in that area, but a climber entering a new range has to be ready to learn again.

Some of the most detailed advice on routes will come out of conversations with local experts. Talk to geologists, rangers, and fellow mountaineers. Ask about climbers' trails that don't show on the map and about the best place to ford a stream. Stop at the ranger station on the way to the mountains and get word on current weather and route conditions. Spend a few minutes chatting with the other climbers who have stopped at the ranger station on the way to their own mountain adventure. Doing your homework makes for easier trips with fewer routefinding frustrations.

APPROACH OBSERVATIONS

Keep an eye on the mountain during the approach hike, studying it for climbing routes. The distant view reveals gross patterns of ridges, cliffs, snowfields, and glaciers, as well as the average angle of inclination.

As you get closer, details of fault lines, bands of cliffs, and crevasse fields show up. Gross patterns seen from far away usually are repeated in finer detail when viewed closer. Ledges revealed by snow or shrubs from a distance often turn out to be "sidewalks" with smaller ledges between. The major fault lines, or weaknesses, visible at a distance are usually accompanied by finer, less obvious repetitions.

If the approach skirts the base of the mountain, it can be viewed from various perspectives. A system of ledges indistinguishable against background cliffs may show clearly from another angle with the sky behind. The change of light as the sun traverses the sky often creates revealing shadows. A study of these lengthening or shortening shadows may disclose that apparently sheer cliffs are only moderately angled slopes.

The presence of snow often promises a modest angle and easy climbing, because it doesn't last long on slopes greater than 50 degrees. But beware of nature's illusions. Rime ice adhering to vertical or overhanging cliffs can at first appear to be snow. Deep high-angle couloirs (gullies) often retain snow or ice year-round, especially when shaded. And what look like brilliantly shining snowfields high on the mountain may actually be ice.

As you near the peak, look for climbing clues: ridges with lower average inclination than the faces they divide; cracks, ledges, and chimneys leading up or across the faces; snowfields or glaciers offering easier or predictable pitches.

Spot climbing hazards. Study snowfields and icefalls for avalanche danger, and cliffs for signs of possible rockfall. Snowfields reveal recent rockfall by the appearance of dirty snow or the presence of rock-filled "shell-craters." If the route goes through avalanche and rockfall territory, travel in the cold hours of night, or very early morning before the sun melts the ice mortar bonding precariously perched boulders and ice towers.

Throughout the approach, follow the old mountaineering dictum to "climb with your eyes." Keep evaluating hazards and looking for continuous routes. When the route information gets too complex to remember, begin making quick sketches during rest stops. These memory aids can prove invaluable during a climb when a critical exit gully, for example, becomes lost from view.

While you're at it, keep an eye out for emergency campsites, water supplies, firewood, and anything else that might make your return trip easier and safer.

WALKING

The basic skill for mountaineering is a simple act we all do every day: walking. But just as the ability to write doesn't mean you're a writer, the ability to walk doesn't mean you're a wilderness-ready walker. To walk efficiently in the mountains, you've got to take into account the varied terrain, the weight of your pack, and your physical condition.

PACE

Beginners often make one of two mistakes: they walk faster than they should, or they walk slower than they could.

The most common mistake is walking too fast, perhaps out of concern for the long miles ahead or from a desire to perform well in front of companions. But why wear yourself out on the first mile of a 10-mile hike if the whole day happens to be available for the walk? Take your time and enjoy it.

A simple test will reveal if your pace is too fast. If you cannot sustain it hour after hour, you're going too fast.

The other mistake is hiking too slowly. Your body complains long before it is hurt. Your muscles may ache but still have 10 miles left in them; your lungs may gasp but be able to go on gasping another 3 hours. A degree of suffering is inevitable on the way to becoming a good walker.

The most desirable hiking speed varies during a day. Get ready for a hike by stretching your legs, hips, back, and shoulders. Walk slowly at the start, letting the body become aware of the demands to come. Then start striding out, using will power to get through this period of increasing work until the body experiences its "second wind."

Physiologically, this means the heart has stepped up its beat, the blood is circulating more rapidly, the muscles have loosened. Psychologically, the hiker feels happy and strong.

Vary your pace depending on the trail. Plod slowly and methodically up steep hills; as the grade lessens, pick up the tempo. Your pace will slow late in the day as fatigue sets in. Adrenaline may fuel short bursts of exertion, but there is no "third wind."

THE REST STEP

The most valuable technique in wilderness hiking is setting the right pace. A very important way of controlling your pace is the rest step (fig. 5-1), used whenever legs or lungs need a little time to recuperate between steps on steep slopes. Once you learn it, you'll use it often.

The pace is slow, because for every step there is a pause. The rest takes place after one foot is swung forward for the next step. Support the entire weight of your body on the rear leg while relaxing the muscles of the forward leg. Important: keep your rear leg straight and locked at the knee so that bone, not muscle, supports the weight.

Synchronize breathing with the sequence. In a typical sequence, you may take a new breath with each step—but the number of breaths per step will be less or more depending on how hard the work is. With one breath per step, inhale as you bring your back foot up to the front; exhale as your front leg rests and your rear leg supports the body's weight. Keep repeating this sequence. Where the air is thin, the lungs need an extra pause—sometimes three or four breaths per step. Make a conscious effort to breathe deeply.



Fig. 5–1. The rest step

Mental composure is important with the rest step. The monotony of the pace, especially on glaciers and snowfields, can undermine morale. You must trust the technique to slowly but steadily chew up the miles, even when the summit seems to be getting no closer.

RESTS

Even the strongest and most experienced hikers need occasional full rests.

During the first half-hour of a hike, stop for a shakedown rest. This lets hikers loosen or tighten boot laces, adjust pack straps, add or take off layers of clothing.

In groups that include both men and women, remember to declare regular party separations (toilet stops), especially out of courtesy to the hiker who may be too shy to express the need. With large groups, the day's first party separation should come before the hike begins, at a service station or outhouse near the trailhead.

During the early part of the day, while your body is fresh, take short, infrequent breathers. Rest in a standing or semi-reclining position, leaning against a tree or hillside to remove pack weight from the shoulders, take deep breaths, and have a bite to eat.

Later, with the body demanding more complete relaxation, the party can take a sackout rest every hour or two. When it's about time for a stop, look for a place with special advantages, such as water, view, flowers, and convenient slopes for unslinging packs. Don't prolong such lovely rests. It's agonizing to resume a march once muscles become cold and stiff. But do remember to eat small amounts of food and drink water during rest stops.

A climbing party sprawled along the trail is not getting any closer to its objective. Take rests when necessary. Otherwise keep moving, unless there's so much extra time in the day that you can afford a luxury rest.

DOWNHILL AND SIDE-HILL

Walking downhill is less tiring than walking uphill, but it's a mixed blessing. Going down a trail, body weight drops roughly and abruptly on legs and feet. Toes are jammed forward. Jolts travel up the spine to jar the entire body. The result can be blisters and knee cartilage damage, sore toes and blackened nails, headaches, and back pain.

Hikers use a few tricks to ease their way downhill. Tighten laces to reduce movement inside the boot (and keep your toenails trimmed). Maintain a measured pace that is slower than the one urged by gravity. Bend your knees to cushion the shock with each step, and place your feet lightly, as if they were already sore. This restraint will tire your upper leg muscles, and you'll learn that rests going down a trail are just as essential as on the way up.

The ups and downs of hiking are far preferable to the torments of side-hilling (traversing). Walking across a side hill twists the ankles, contorts the hips, and destroys balance. If you can abandon a side hill in order to drop down into a brush-free valley or go up onto a rounded ridge, do it. It's worth going the extra distance. If you're stuck with side-hilling, switchback now and then to shift the strain. Work into your route any flat spots of relief provided by rocks, animal trails, and clumps of grass or heather.

ETIQUETTE

Walking with others requires certain courtesies that are nothing more than common-sense thoughtfulness.

- Avoid following too close. Instead of shadowing your companion, give the hiker ahead of you some space by staying perhaps seven or eight paces back.
- Avoid following too far back, so you don't lose contact with the other hikers or make them continually wait for you.
- Take a look back before you release the branches you've pushed aside along the route. If the hiker behind you has violated the first rule, that person is in danger of getting swatted.
- Step aside when you stop to tie a shoe lace, adjust your pack, or admire the view. (Step above those passing by, if possible.)
- Ask permission to pass, instead of elbowing your way forward.
- Step aside on the way downhill to let a party of uphill hikers continue forward without breaking their pace.
- Set a pace that everyone in the party can maintain. If someone can't keep up, slow the party's pace. Give the last person time to catch up with the party at rest stops—and time to rest after getting there.

TRAILS

The simplest way into the wilderness will always be a trail. They come in many shapes and sizes. One trail will be wide and well marked, while another will have a quality of magic about it: now you see it, now you don't. One big job of the wilderness traveler is to find trails and use them.

TRAIL FINDING

Very few trails were created for the use of climbers. Miners built trails to ore, fishermen to the high lakes, trappers along valleys, pioneers over passes, and animals to food and shelter. But the mine or the lake or the pass might make a good base camp, and any track is worth following as long as it heads the right way.

Even in popular areas with heavy foot traffic and lots of signs, keep alert to find the trail and stay on it. It's easy to stagnate mentally on a long, monotonous walk and miss a turnoff where a sign is missing or where logging has obliterated part of the trail.

Old blazes cut in tree trunks or ribbon tied to branches often mark the trail through a forest, and rock cairns may show the way above timberline. But these pointers don't last forever, and they aren't always reliable. A tiny cairn or a wisp of ribbon may reflect nothing more than the passage of a climber who was lost or was laying out a route to another destination.

As a trail-seeker, you become a detective who combines the clues (a bit of beaten path here, a tree blaze there) with the use of map, compass, and altimeter and with tips from guidebooks and the experts. You'll soon delight in rediscovering the trail just as your companions pronounce it lost forever. And you'll shock the lowland Sunday-afternoon hiker with your definition of the word "trail": any visible route, no matter how ragged, that efficiently gets you where you want to go without battling through brush.

The trick is to stay on the trail until the inevitable moment it disappears or until it becomes necessary to head off-trail in order to keep going in the right direction. Then create your own trail, choosing a course that a trail would follow if there were one. Trail builders look for the easiest way to go. Do as they do.

SOUND TRAIL PRACTICES

Finding the trail is only one half of trailcraft. Using it in a sensitive, caring way is the other. Here are some guidelines:

- Walk in single file to protect trail-side vegetation.
- Stay on the trail even if it's muddy, snow-covered, or rutted.
- Help save vegetation and prevent erosion by not cutting switchbacks.
- Select resilient areas instead of fragile vegetation for rest breaks.
- Look and photograph instead of picking or collecting.
- Guard against damage to stream banks.
- Do light trail maintenance and remove litter.
- Leave trailless areas free of cairns and flagging unless they're already there. Let others have the same adventure of routefinding that you experienced. If you need to mark your route, remove the markers on your way down.
- Choose talus instead of fragile meadows for cross-country travel.

BRUSH

Brush can be a backcountry horror, but there are ways to avoid it.

Wherever there is running water or sliding snow, brush thrives. The classic example is a low-altitude gully swept by avalanches in winter and a torrent in summer. Conditions are perfect for shrubs that flourish during the short summer season, bend undamaged under the snow, and quickly sprout again.

Along riverbanks, brush keeps a window on the sun and builds a narrow, dense thicket. A river that frequently changes course prevents large trees from growing but permits a wide belt of entangling brush. At subalpine elevations, avalanche snow that lasts late into summer prevents the growth of forests and leaves the valley floor crowded with brush.

Mountaineers prefer mature forests. The forests help by blocking sunlight, stifling growth of the deciduous brush that makes for rough going. Young forests, however, only add to the brush problem. The second-growth timber that springs up densely after a fire or windstorm or logging is at its worst when about 20 feet high. The branches fill the space between trees, and deciduous brush continues to thrive.

Blowdowns, avalanche fans, and logging trash are even tougher to get through. The chaotic jumble can slow progress to a crawl and justify a major change of route. Tough and twisted scrub cedar that clings to cliffs and bands of rock presents another hurdle.

When a skirmish with brush is inevitable, there are ways to minimize the hassle. Choose the shortest route across the brushy area. Use fallen trees with long straight trunks as elevated walkways. Push and pull the bushes apart—sometimes by stepping on lower limbs and lifting higher ones to make a passageway. On steep terrain, use hardy shrubs as handholds.

Brush can be dangerous: down-slanting vine maple or alder is slippery; brush obscures the peril of cliffs, boulders, and ravines; and brush snares ropes.

The best policy is to avoid brush. Here are some tips:

- Use trails as much as possible. Five miles of trail may be less work than 1 mile through brush.
- Consider traveling when snow covers brush. Some valleys are easy going in May when you can walk on snow but almost impossible in July when you must burrow through brush.
- Avoid avalanche tracks. The best route up a long valley may be on southern or western slopes, where avalanches hit less frequently than on northern and eastern slopes. When climbing a valley wall, stay in the trees between avalanche tracks.
- Aim for the heaviest timber. Brush is thinnest under the big trees.
- Travel on talus or scree and remnants of snow, rather than in adjacent thickets.
- Consider traveling on ridges and ridge spurs. They may be dry and brushless, while creek bottoms and valley floors are choked with vegetation.
- Consider climbing directly to timberline to take a high route above the brush. This may be worthwhile if the valley bottom seems impassable, and the valley sides are scarred by avalanche tracks.
- Consider going right into the stream channel. The stream bed could be a tunnel through the brush, though you may have to do some wading. Dry stream beds are sometimes ideal. In deep canyons, however, streams usually are choked with fallen trees or interrupted by waterfalls.
- Look for game trails. Animals generally follow the path of least resistance.

TALUS

Talus slopes can either help or hinder the climber. Most offer handy brush-free pathways to the mountains, but some are loose and dangerous.

The peaks constantly crumble, dropping fragments that pile up below as talus and scree. Most of the rubble pours from gullies and spreads out in fan-shaped cones that often merge into one another, forming a broad band of talus between valley greenery and the peaks. Talus fans also often alternate with forest.

Talus slopes build gradually over the ages. On the oldest slopes, soil fills the gap between rocks, making smooth pathways. But talus can be dangerous on volcanos and younger mountains, where rocks are only loosely consolidated because vegetation hasn't filled in the spaces. Move nimbly here, ready to leap away if a rock shifts underfoot. Disturbing one key stone on a glacial moraine or a talus slope can even set off a serious rock avalanche.

Climbers on talus slopes need to keep alert because almost everyone will knock loose a rock or two. Try to travel outside the fall line of climbers above and below. If you're in a narrow gully and this isn't possible, tread gently and be ready to shout "Rock!" if a stone is dislodged. Keep close together so a rock set off by one climber can't gain dangerous momentum by the time it reaches other team members. Or permit only one climber to move at a time, while the rest stay in a protected spot.

Slopes with the smallest fragments, called scree, are sometimes as loose as sand. This makes the uphill going a slow-motion torment, but on the way down it might permit some careful "screeing." This involves shuffling your feet to start a minor slide of pebbles and riding it down, in a standing glissade. If there is any vegetation on the slope, skip the screeing out of regard for the plants.

SNOW

Snow can be a blessing in wilderness travel. Many peaks are best climbed early in the season because talus, brush, and logging slash are covered by consolidated snow, and snow bridges provide an easy way over streams.

There are hazards, however. Streams will melt the underside of a snow bridge until it can no longer support your weight. You may break through, the result being wet feet or, much worse, being carried under the snow by a swift stream. To guard against a dunking, watch for depressions in the snow and variations in color or texture, and listen for sounds of running water. Water emerging at the foot of a snowfield gives a clue to the existence and perhaps the size of a cavity beneath the snow. Probe thin spots with your ice axe.

The snow next to logs and boulders often covers holes and soft spots, caused when the snow melts partially away from the wood and the rock. Probe or avoid likely trouble spots, and step wide off logs and rocks. As spring merges into summer, the best route along a valley floor may be somewhat erratic, taking advantage of each remaining snow patch for the few steps of easy walking it provides.

The techniques of snow travel are the same whether the snow lies high in the mountains or deep in the woods. On steep slopes, you may need safeguards such as an ice axe, a rope, or crampons. With experience, you'll recognize both the dangers and the advantages of snow and learn to use the medium to make wilderness travel easier and more enjoyable.

STREAMS

In a wilderness without trails or bridges, streams can become a major impediment. In Alaska or the Canadian Coast Range, climbers may spend more time and energy crossing a perilous river than on their ultimate objective, the mountain.

FINDING THE CROSSING

When the peak lies on the far side of a sizable river, the crossing is a major factor in route selection. Try to get a distant overall view of the river, perhaps from a ridge before dropping into the valley. This view can be more useful than a hundred close looks from the riverbank. When a distant view isn't possible or isn't helpful, you're stuck with either thrashing through the river-bottom brush looking for a way across or sticking to the slopes high above the river in hopes of spotting a sure crossing.

In deep forest there's a good chance of finding easy passage on a log jam over even the widest river. Higher in the mountains, foot logs are harder to come by, especially if the river changes course periodically and prevents growth of large trees near its channel.

A particular river may be impassable. If it's fed by snow, early morning is the time of minimum flow, and a party may camp overnight to wait for lower water. Sometimes it's necessary to hike for hours or days seeking a crossing. For the widest and deepest rivers, rafts are the only alternative short of hiking to the headwaters.

MAKING THE CROSSING

Unfasten the waist and chest straps of your pack before trying any stream crossing that would require swimming if you fell. You must be able to shed the pack in a hurry.

A foot log is a great way across, with an ice axe, stick, or tightly stretched handline to help with balance and support if the log is thin, slippery, or steeply inclined. Sit down and scoot across if that helps.

Boulders offer another way. Move from boulder to boulder—but only after mentally rehearsing the entire sequence of leaps. Safety lies in smooth and steady progress over stones that may be too slippery and unsteady for you to stop for more than an instant. Use an ice axe or pole for added balance.

If you must wade across, use the widest part of the river. The narrows may be appealing as the shortest way, but they're also the deepest, swiftest, and most dangerous.

If the water is placid and the stones rounded, put your boots in the pack and keep them dry as you wade across. In tougher conditions, wear your boots, but put socks and insoles in the pack. You can drain the boots on the far side, replace the insoles, and put the dry socks back on. You may decide to remove your pants or other clothing in deeper crossings. Loose clothing increases the drag from the water, but it also reduces chilling and may permit a longer crossing before your legs go numb.

The force of moving water is easy to underestimate. A swift stream flowing only shin-deep boils up against the knees. Knee-deep water may boil above the waist and give a disconcerting sensation of buoyancy. Whenever water boils above the knee, it is dangerous, and one false step could have you bouncing in white water from boulder to boulder. Frothy water, containing a great deal of air, is wet enough to drown in but may not be dense enough to float the human body. Streams fed by glaciers present an added difficulty because the bottom is hidden by milky water from glacier-milled rock flour.

If the stream is deep but not swift, you can cross by angling downstream at about the same speed as the current. But it's usually best to face upstream, lean into the current, and stab an ice axe or stout pole upstream for a third point of support. The leading foot probes for solid placement on the shifting bottom, the following foot advances, and the axe or pole is thrust into a new position.

Two travelers can cross together, taking turns securing the other as that person moves to a solid new stance. Team-crossing with a pole is another method. Team members enter the water, each grasping the pole, which is held parallel to the flow of the stream. The upstream member breaks the force of the current. Anyone who slips hangs on to the pole while the others keep the pole steady.

Using ropes for stream crossings is hazardous and not generally recommended. A taut handline can be helpful, but belaying someone across a river holds the danger that the person could be held by the belay and trapped under water.

THE ICE AXE

The tool is called an ice axe, but it's really an invaluable all-purpose item that often goes to work long before snow or ice is reached.

The axe has a lot of unsuspected uses. It provides a "third leg" during stream fording. It gives a brief touch-and-go balance point while you hop across talus. It also helps with balance on steep trails, serving as a heavy-duty cane going uphill and a brake going down. The axe held diagonally across the body, spike touching the slope, will help you hold a stable, vertical stance on steep hillsides. The ice-axe self-arrest is taught as a technique for snow, but many climbers have been happy to use their "dirt axe" to stop themselves in steep meadows, forest, and heather.

On open trails many climbers strap the axe on the pack. It comes off the pack and into the hands as the route gets rougher (and as the axe on the pack begins snagging on brush and tree limbs). The ice axe is truly the mountaineer's friend, but it's also probably the most dangerous implement of mountaineering. Its pick (the pointed end of the head), adze (broad end of the head), and spike are always ready to poke, gouge, and impale a climber or nearby companions. Leather or rubber guards are available to cover sharp points and edges when the axe is not needed. Be aware that these guards often get knocked off by brush. Remove the guards when on steep, slippery terrain, whether it's mud, needles, grass, or snow.

Carrying an axe without the skill to use it provides a false sense of security. All too often, climbers slip on hard snow and discover they don't know enough about self-arrest to stop their fall. This indispensable skill comes from practicing on slopes with safe run-outs. (See Chapter 12 for details on this technique and much more information on ice axes.)



Fig. 5–2. Carrying an ice axe: a, in your hand on easy terrain; b, as a cane.

The safe way to carry an axe while walking along a trail (fig. 5-2a) is to grasp the shaft at the balance point (shaft parallel to the ground), with the spike forward, and the head to the rear with the pick down. This way, the hiker behind is safeguarded against running into the spike and the pick is less likely to jab you in case you stumble. To use the axe as a cane while hiking (fig. 5-2b), grasp the head, with the spike toward the ground. It's usually easiest to have the pick pointing forward, permitting the palm of your hand to rest comfortably on top of the adze.

READY FOR THE WILDERNESS

Wilderness travel can be a complicated business because of all the variables of terrain, weather, snow, water, and vegetation. By putting the information in this chapter into practice, you can learn to travel safely and efficiently through some of the most awe-inspiring landscapes on earth. Combine this information with the advice in earlier chapters on navigation, camping, food, clothing, and equipment, and you should be ready for the wilderness.



◆ PART TWO ◆

CLIMBING FUNDAMENTALS

Climbing at dawn on the Park Glacier, Mount Baker, Washington. Photo by Alan Kearney

• 6 •

ROPES, KNOTS, AND CARABINERS

The rope, more than any other piece of equipment, symbolizes climbing and the climber's dependence on another person. Most climbers remember that very first tie-in—and their sudden dependence on the rope and on their partner or partners who joined them on that length of lifesaving line.

The rope is a "safety net" to catch you when the difficulty of a pitch exceeds your abilities or when the unexpected happens—a foothold crumbles, a snow bridge collapses, or a falling rock knocks you off an exposed stance. It is also fundamental to climbing because, when anchored, it can be climbed or descended.

The rope does not work alone in protecting you, but is one link in your chain of safety. Other links in that chain include the knots that allow you to use the rope for specialized tasks, the seat harness the rope is tied to, the loops of webbing known as runners that help connect the rope to rock or snow, and the carabiners that join parts of the climbing system. These links are the topics of this chapter.

ROPES

During climbing's infancy, ropes made of natural fibers (manila and sisal) were used to protect climbers, but these ropes were not reliable for holding severe falls. The development of nylon ropes during World War II forever changed the sport. Suddenly, climbers were offered lightweight lines capable of bearing more than 2 tons. The nylon ropes also had the remarkable quality of elasticity. Rather than bringing a falling climber to an abrupt, jolting stop, the nylon ropes stretched to dissipate much of the force of a fall.

The first nylon ropes were of "laid" or "twisted" construction. Like braided hair, these ropes were composed of many thin nylon filaments bunched into three or four major strands which were then woven together to form the rope.

The early nylon ropes were light-years ahead of natural fiber ropes, but they were stiff to handle and created substantial friction when run through the points of protection used by climbers. Also, they were so elastic that direct-aid climbing with them was inconvenient; they stretched too much when climbers ascended the rope.

Gradually, twisted nylon ropes were replaced by kernmantle ropes, synthetic ropes designed specifically for climbing. Today's kernmantle ropes (fig. 6-1) are composed of a core of braided or parallel nylon filaments encased in a smooth, woven sheath of nylon. Kernmantle rope maintains the advantages of nylon but improves upon the problems associated with twisted ropes—stiffness, friction, and excessive elasticity. Kernmantle



Fig. 6–1. Construction of a kernmantle rope

ropes are now the only climbing ropes approved by the Union Internationale des Associations d'Alpinisme (UIAA), the internationally recognized authority in setting standards for climbing equipment.

PERFORMANCE TESTS

The UIAA tests equipment to determine which gear meets its standards. In a sport where equipment failure can be fatal, it's wise to purchase equipment that has earned UIAA approval.

A principal UIAA test checks the strength of single ropes, the basic ropes used in most climbing. These ropes generally measure between 9.8 and 12 millimeters in diameter. For the test, the UIAA attaches an 80-kilogram (176-pound) weight to one end of a 2.8-meter (9-foot) length of rope. The other end is attached to a fixed point after passing through a carabiner-type ring about 1 foot above the point of attachment. The weight is raised as high as it can go, which puts it 2.5 meters above the ring, and dropped for a free fall of 5 meters (fig. 6-2).



Fig. 6–2. UIAA drop test

The test mimics a severe real-life climbing fall. To receive UIAA approval, a rope must survive at least five of these falls. The test also measures the impact force of the rope, which determines the stress of the fall on the climber's body and on the pieces of protection. UIAA standards require that the impact force not exceed 1,200 kilograms (about 2,700 pounds) on the first fall.

The UIAA also tests double ropes, those used in climbing techniques that utilize two ropes at a time. (Double-rope technique and twin-rope technique are explained in Chapter 10.) These ropes generally measure between 8 and 9 millimeters in diameter. The test for any individual rope used with two-rope technique is identical to the test for single ropes, except that a weight of only 55 kilograms (121 pounds) is used. Each rope must survive at least five falls, and the maximum permitted impact force on the first fall is 800 kilograms (about 1,800 pounds).

The UIAA also applies static tension tests to the ropes it approves, to keep rope stretch below a certain maximum. A load of 80 kilograms is applied to a 1-meter section of rope. A larger rope (between 9.8 and 12 millimeters in diameter) cannot elongate by more than 8 percent. A lighter rope used in two-rope climbing cannot elongate by more than 10 percent.

WATER-REPELLENT ROPES

Wet ropes are more than unpleasant to handle and heavy to carry. They can freeze and become difficult to manage. Equally important, studies show that ropes hold fewer falls and have about 30 percent less strength when they are wet.

Rope manufacturers treat some of their ropes to make them more water repellent and therefore stronger in wet conditions. The sheaths and cores of these ''dry'' ropes are treated with either a silicone-based or Teflon-based coating. The treatment improves the abrasion resistance of some ropes and also reduces friction of the rope as it runs through carabiners. The dry ropes cost about 15 percent more than untreated ropes.

ROPE CARE

When you consider what a climbing rope protects—your life—it's easy to understand why it deserves pampering. A new rope is extremely strong, but abusive treatment can soon destroy it.

Stepping on a rope is a common form of abuse that grinds sharp particles into and through the sheath. Over time, the particles act like tiny knives that slice the rope's nylon filaments. Stepping on the rope creates even more damage if it happens to be trapped between a sharp edge and your boot. Be doubly careful about keeping off the rope when you're wearing crampons. The havoc these metallic points can wreak is obvious, though not always visible. Crampons can damage the core of a rope without leaving any visible gash on the sheath.

Nonetheless, the sheath gives the best picture of the rope's overall condition. If a crampon wound, excessive abrasion, rockfall, or a sharp edge leaves the sheath looking tattered, the rope's integrity should be seriously questioned. Often the damaged portion of the sheath is near an end and cutting off a small segment of the rope solves the problem. But if the damaged section is closer to the center, retire the rope.

If no obvious blemishes scar the sheath, it's harder to decide when to retire the rope. Its actual condition depends on many factors including frequency of use, the care it has received, the number of falls it has endured, and how old it is. Following are some general guidelines to help you decide when to retire your rope:

- A rope used daily should be retired within a year.
- A rope used during most weekends should give about two years of service.
- An occasionally used rope should be retired after four years (nylon deteriorates over time).
- After one very severe fall, it may be wise to replace your rope. A *new* rope may be certified to take five falls, but if your rope is not new, consider all the other factors affecting its condition.

These guidelines assume proper cleaning and storage. A rope should be washed frequently with tepid water and a gentle detergent. Wash it by hand or in a side-loading machine (ropes can get caught under the agitator in top-loading machines). Rinse the rope several times in fresh water, and then hang it to dry in a shady area.

Before storing any rope, be sure it is completely dry. Remove all knots, coil the rope loosely, and store it in a cool, dry area away from sunlight, battery acid, and other strong chemicals.

Get in the habit of inspecting your rope frequently. Is the sheath clean? If not, wash the rope. Are the ends of the rope fraying or unraveling? If so, fuse them with a small flame. Are the ends and middle of the rope well-marked for easy detection? If not, mark them according to the manufacturer's guidelines.

COILING THE ROPE

For carrying or storing, the rope is normally coiled, most commonly in the mountaineeer's coil (fig. 6-3) or the butterfly coil (fig. 6-4). Most climbers prefer one or the other, but knowing both is useful. The mountaineer's coil is advantageous when the rope is carried over a pack. But the butterfly coil is faster, doesn't kink the rope, and ties snugly to your body if you are not wearing a pack.

Whatever your method, uncoil the rope carefully before use. Untie the cinch knot and then uncoil the rope, one loop at a time, into a pile. If you just drop the coils and start pulling on one end,



Fig. 6–3. Mountaineer's coil

you'll probably create a tangled mess.

Rope throw bags offer an alternative to coiling. These bags protect the rope, keep it cleaner and drier, and reduce chances of tangling. Throw bags have a loop of webbing sewn into the bottom of the inside. One end of the rope is tied into the loop before the rest of the rope is threaded and stuffed into the bag uncoiled. Do not connect the rope with a carabiner, because the carabiner could be damaged if the bag is thrown. Before tossing the bag—in preparation for a rappel, for example—don't forget to anchor the free end of the rope.



Fig. 6–4. Butterfly coil

KNOTS

Knots allow you to use the rope for many special purposes. They let you tie into the rope, anchor yourself to the mountain, tie two ropes together for long rappels, use slings to climb the rope itself, and much more.

Climbers rely most heavily on a dozen or so different knots (figs. 6-6 through 6-26). Practice these knots until tying them is second nature. If you really want a test, try tying them in a cold, dark shower to give you an idea of the conditions you may someday encounter on a climb.

In some cases, more than one knot can perform a particular task, and the knot chosen is a matter of personal preference. Some knots may be preferred because they have a higher breaking strength (fig. 6-5). Others may be chosen because they are easier to tie or are less likely to come apart in use.

Regardless of the knot, tie it neatly, keeping the separate strands of the knot parallel and free of twists. Cinch every knot tight, and tie off loose ends with the insurance of overhand knots.

	%		%
Without knot	100	Double fisherman's	65-70
Bowline	70-75	Water knot (ring bend)	60-70
Figure 8	75-80	Clove hitch	60-65
Fisherman's	60-65	Overhand	60-65

Fig. 6–5. Relative strengths of knots for single kernmantle rope (courtesy the American Alpine Journal*)*

Overhand knot

The overhand knot (fig. 6-6a) is most often used to secure loose rope ends after another knot has been tied. For instance, it can be used to secure rope ends after tying a square knot (fig. 6-6b) or a rewoven figure-8 (fig. 6-6c).

Overhand loop

The overhand loop (fig. 6-7) is often used for leg loops in prusik slings or to make a loop in a doubled rope or a length of webbing.



Fig. 6–7. Overhand loop

Water knot

The water knot (fig. 6-8), also known as the ring bend or tape knot, is used most often to tie a length of tubular webbing into a runner. This knot can work loose over time, so be sure the knot is



Fig. 6–6. Overhand knot: a and b, tying an overhand knot; c, overhand knot with a rewoven figure-8.



Fig. 6–8. Water knot

cinched very tight, and the tails of the knot are at least 2 inches long. Check the knot often in runners and retie any that have short tails.

Square knot

The general-purpose square knot (fig. 6-9) has many applications around camp. It is often used to finish off a coiled rope.



Fig. 6–9. Square knot



Fig. 6–10. Fisherman's knot

Fisherman's knot

The fisherman's knot (fig. 6-10) can be used to join two ropes together. It has been replaced to a large degree by the double fisherman's knot and is shown here primarily to provide a clearer understanding of the double fisherman's knot.



Fig. 6–11. Double fisherman's knot

Double fisherman's knot

The double fisherman's knot (fig. 6-11), also known as the grapevine knot, is the most secure and preferred knot for tying the ends of two ropes together for a rappel.



Fig. 6–12. Figure-8 loop

Figure-8 loop

The figure-8 loop (fig. 6-12) is a strong knot that can be readily untied after being under a load.

Rewoven figure-8

The rewoven figure-8 (fig. 6-13) is an excellent knot for tying into a seat harness at the end of the rope. Finish it off by tying one or two overhand knots in the loose end. This knot also can be used to connect a rope to an anchor.



Fig. 6–13. Rewoven figure-8



Fig. 6–14. Double rewoven figure-8

Double rewoven figure-8

The double rewoven figure-8 (fig. 6-14) is used by the middle person in a three-person rope team to tie the rope to the seat harness. Secure the resulting end loop with an overhand knot or a carabiner.

Single bowline

The single bowline (fig. 6-15) makes a loop at the end of the climbing rope that will not slip, and



Fig. 6–15. Single bowline

it can secure the rope around a tree or other anchor. Tie off the loose end with an overhand knot. The free end of the rope should come out on the inside of the loop, because the knot is much weaker if this end finishes on the outside.

Rewoven bowline

The rewoven bowline (fig. 6-16) is another excellent knot for tying into a seat harness at the end of the rope. It can be used in place of the rewoven figure-8. If the rewoven portion of the bowline comes untied, you are still tied in with a single bowline.



Fig. 6–16. Rewoven bowline



Fig. 6–17. Double bowline

Double bowline

The middle person on a three-person rope can tie the double bowline (fig. 6-17) to a seat harness. The resulting end loop should be secured with an overhand knot or a carabiner.



Fig. 6–18. Clove hitch

Clove hitch

The clove hitch (figs. 6-18 and 6-22) is a quick knot for clipping into a carabiner attached to an anchor. With the clove hitch, it is easy to adjust the length of the rope between the belayer and the anchor without unclipping.



Fig. 6–19. Double sheet bend

Double sheet bend

The double sheet bend (fig. 6-19) is sometimes used instead of a water knot as the tie-off knot on homemade seat harnesses because it is easier to adjust. This knot has a tendency to work loose. Tie off the loose ends with backup overhand knots.

Girth hitch, overhand slip knot, and clove hitch

The girth hitch (fig. 6-20), the overhand slip knot (fig. 6-21), and the clove hitch (fig. 6-22) are simple knots that can be used to tie off partially driven pitons or ice screws.



Fig. 6–20. Girth hitch



Fig. 6–21. Overhand slip knot



Fig. 6–22. Clove hitch

FRICTION KNOTS

Friction knots provide a quick and simple way to set up a system for ascending or descending a climbing rope. The knots grip the climbing rope when weight is on them, but are free to move when the weight is released. The best known friction knot is the prusik, but others such as the Bachmann and the Klemheist are also useful.

Prusik knot

The prusik (fig. 6-23) requires a few wraps of a light accessory cord around the climbing rope, and it's ready to go to work. The cord is usually a loop (sling) of 5-millimeter to 7-millimeter perlon, wrapped two or three times around the rope. Icy ropes or heavy loads require more wraps than dry ropes or light loads. The accessory cord must be smaller in diameter than the climbing rope, and the greater the difference in diameter, the better it grips. Webbing isn't used for prusik knots because it may not hold.

By attaching two slings to a climbing rope with prusik knots, you can "walk" up the rope. To do this, stand in one sling and take all your weight off the other; now you can slide that knot 1 foot or so up the rope. Then transfer your weight to the second sling, and slide the first sling another foot up the rope. Keep repeating the process and you'll slowly but steadily ascend the rope. (Chapter 13



Fig. 6–23. Prusik knot: a–c, tying sequence for the prusik knot; d, a two-wrap prusik knot; e, a three-wrap prusik knot.

describes this process in detail as it is used in getting out of a crevasse.) The knot is also used to help in raising and lowering people and equipment during rescues.

Bachmann knot

The Bachmann knot is used for the same purposes as a prusik knot. The Bachmann (fig. 6-24) is tied around a carabiner, making it much easier to loosen and slide than a prusik. It has the virtue of sometimes being "self-tending" when it's being used to help hoist an injured climber.

Klemheist knot

The Klemheist (fig. 6-25) is another alternative to the prusik, with the advantage that it allows you to use a sling made from either accessory cord or webbing. This can be a big help to a climber caught with an ample supply of webbing but little cord.

The cord or webbing is wound around the main rope in a spiral and then threaded through the loop of the top wrap. The Klemheist tied off with a sheet bend is an improved version that is less likely to jam and easier to loosen and slide. The knot also can be tied around a carabiner, providing a good handhold.



Fig. 6–24. Bachmann knot

The Münter hitch

The Münter is a simple hitch in the rope that is clipped into a carabiner to put friction on the line. It provides an excellent method of belaying a leader or lowering a climber because the hitch is



Fig. 6–25. Klemheist knot: a–b, winding and threading Klemheist knot; c, Klemheist tied off with a sheet bend; d, Klemheist tied around a carabiner.



Fig. 6–26. The Münter hitch

reversible (you can feed rope out of the carabiner or pull rope back in) and because the hitch slides (yet is easy to stop if you hold the braking end of the rope). It can also provide the necessary rope friction for rappelling, though it puts more twist in the rope than other rappel methods.

The Münter hitch (fig. 6-26) is very easy to set up and use, and the only equipment needed is a large pear-shaped locking carabiner. Even if you prefer to use a specialized belay device, this hitch is worth knowing as a backup for the time you lose or forget the gear.

HARNESSES

In the old days, climbers looped the climbing rope around the waist several times and tied in with a bowline-on-a-coil (fig. 6-27). That practice is no longer encouraged because long falls onto waist loops can injure your back and ribs. Falls that leave you hanging, such as a fall into a crevasse or over the lip of an overhang, will constrict your diaphragm and suffocate you.

Nowadays, climbers who value their health tie the rope into a harness designed to distribute the force of a fall over a larger percentage of the body. (The bowline-on-a-coil is an option for emergency use if no harness or harness material is available.) The rope is tied into the harness with knots such as the rewoven figure-8 or rewoven bowline (for climbers at the ends of the rope) or with the double rewoven figure-8 or double bowline (for middle climbers).

COMMERCIAL SEAT HARNESSES

With properly fitted leg loops, a seat harness rides comfortably on the hips, yet transfers the force of a fall over the entire pelvis. It also provides a comfortable seat while rappelling.

Several features are particularly desirable in a mountaineering seat harness (fig. 6-28a). Adjustable leg loops allow you to maintain a snug fit no matter how few or how many layers of clothing you wear. The loops also can be unbuckled to permit toilet calls without having to remove the harness, or even untie from the rope. Having the waist buckle located toward one side helps avoid conflict with the locking carabiner clipped to the front of the harness, and lets you move the carabiner left or right of center. Hardware loops are desirable for carrying carabiners and other pieces of climbing


Loop must be rotated in the direction shown to be tied properly
a
b
c
d
e
f
g
h

Fig. 6–27. Bowline-on-a-coil: a–f, for climber at the end of a rope; g–h, for middleman. It is not recommended that this knot be used around the body except in emergencies.



Fig. 6–28. Commercial seat harnesses showing principal features mentioned in text

gear, while padded waist and leg loops give added comfort.

Follow the manufacturer's instructions for buckling into these harnesses. For most harnesses, you will need to pass the waist strap back over and through the main buckle a second time for safety. Be sure that at least 2 inches of the strap extends beyond the buckle after reweaving it.

HOMEMADE SEAT HARNESSES

Homemade seat harnesses are an option for linking yourself to the rope, and you can make a simple one from 22 feet of 1-inch tubular webbing. Starting about 4½ feet from one end of the webbing, tie two leg loops in the webbing using overhand loops. Make the loops just large enough to fit



Fig. 6–29. Homemade seat harness

over your clothing, and leave about a 6-inch bridge between the loops. Once tied, leave the loops in place. That completes construction of the harness. To wear it, step into the leg loops and wrap the webbing as shown in the accompanying illustration (fig. 6-29). Use a square knot, water knot, or double sheet bend to tie off the harness, then secure the ends with overhand knots.

SWAMI BELTS

Swami belts (fig. 6-30), another method of tying into the rope, are usually commercially made and are secured to the waist with a buckle or a water knot. The climbing rope is tied through the belt with a rewoven figure-8 or a rewoven bowline.

The belts are wide enough to provide support around the middle of the waist and lower back and to help distribute the force of a fall. Still, if you are left hanging, the belt can creep up and restrict your breathing. Adding leg loops keeps a swami belt from creeping up and distributes the force of a fall to an even larger area, much like a seat harness. In fact, with leg loops attached, the swami belt becomes a seat harness.



Fig. 6–30. Swami belt

BODY HARNESSES

The only commercial harnesses approved by the UIAA are full body harnesses (fig. 6-31). Body harnesses, which incorporate both a chest and a seat harness, have a higher tie-in point. This greatly reduces the chance of flipping over backward during a fall, especially if a pack makes you top heavy. Because a body harness distributes the force of a fall throughout the trunk of your body, there is less danger of lower-back injury.

Although they are unquestionably safer, body harnesses are resisted by many climbers. They are more expensive and restrictive, and make it hard to add or remove clothing. Instead, many climbers prefer a seat harness for most climbs, and improvise a chest harness when one is warranted, such as when climbing with a heavy pack, crossing glaciers, or aid-climbing under large overhangs.

CHEST HARNESSES

A chest harness can be readily improvised with a long loop of webbing (a long runner). One popular design depends on a carabiner to bring the ends of the harness together at your chest. Another uses a knot instead to attach the ends.

The carabiner chest harness: Start with a double-length runner. Give the runner a half twist to create two temporary loops, and push one arm all the way through each loop. Lift the runner over your head and let it drop against your back, then pull the two sides together and clip with a carabiner at your chest. Connect the chest and seat harnesses with a short piece of webbing or cord to keep the chest harness from riding up around your neck in a fall (fig. 6-32).

The final step is to link the chest harness to the climbing rope to prevent you from being flipped upside down during a fall. There are two ways to do this. You can simply run the climbing rope from your seat harness up through the chest carabiner. Or, you can tie a short prusik sling onto the rope in front of you and clip this into the chest harness. If you use the prusik, be sure it is carefully adjusted to help keep you upright, but still permit your weight to be borne by the seat harness (not by the prusik).



Fig. 6–31. Full body harness

The baudrier chest harness: The harness known as the baudrier also is made from a runner, though it will take a somewhat longer runner than the carabiner harness. Put your arm through the runner and hang it over one shoulder. Pull the other end around your back, under the opposite arm, and across your torso. Wind it around a short loop from the other side of the runner, push it through the loop, and cinch the knot tight. Clip the tail of this chest harness directly into the locking carabiner on your seat harness (fig. 6-33).

This harness is linked to the climbing rope in the same way as the carabiner chest harness: either by running the climbing rope up through a carabiner clipped to the chest harness or by attaching a short prusik sling from the rope to the chest harness.

Regardless of the system used, remember that harnesses also deteriorate with use, abuse, and disuse. Replace them about as often as your climbing rope.



Fig. 6–32. The carabiner chest harness



Fig. 6–33. The baudrier chest harness

RUNNERS

Loops of tubular webbing or cord, called runners, are among the simplest pieces of climbing equipment and among the most useful. You'll use them in endless ways as a critical link in climbing systems that involve you, your rope, safety anchors and carabiners.



Fig. 6–34. Runners made of webbing: a, tied runner; b, sewn runner.

Runners are most commonly made by tying a loop with 9/16-inch to 1-inch webbing or with 8-millimeter to 9-millimeter perlon accessory cord. With webbing, a water knot is typically used to make the loop; with cord, a double fisherman's knot does the job. Melt the ends of your runners with a match or candle to keep the nylon from unraveling.

Most standard runners are made from about 5½ feet of webbing. You will also need several double-length runners, which take 9½ feet of material. To help you quickly identify the different lengths, make standard runners from one color of webbing and double-length runners from another color. You should also write your initials and the "manufacturing" date on the tails of all your runners so that you know which are yours and when to retire them.

Tied runners (fig. 6-34a) have several advantages over commercially made sewn runners. They are inexpensive to make, can be untied and threaded around trees and natural chockstones, or can be untied and tied to another length of webbing to create extra-long runners. However, sewn runners (fig. 6-34b) also have some advantages. Sewn runners, always made of webbing, are stronger, lighter, and less bulky than knotted runners. They also eliminate the possibility of the knot untying, a continual concern with homemade runners.

Sewn runners come in four normal lengths: 2-inch and 4-inch "quick draws," 12-inch "half-lengths," and 24-inch "full-lengths." They also come in a variety of widths, with 9/16-inch, 11/16-inch, and 1-inch being most common. Runners made from Spectra—a high-performance fiber that is stronger, more durable, and less susceptible to ultraviolet deterioration—are usually made from 9/16-inch webbing.

CARABINERS

Carabiners are another versatile and indispensable tool of climbing. These ingenious metal snap-links are used for belaying, rappelling, prusiking, clipping into safety anchors, securing the rope to points of protection, and a hundred and one other jobs.

Carabiners for climbing are made of aluminum alloy and require a UIAA minimum breaking strength of 2,000 kilograms (about 4,400 pounds) along the long axis and 400 kilograms (about 900 pounds) along the minor axis. The UIAA minimum breaking strength with the gate open is 600 kilograms (about 1,300 pounds) along the long axis.

Carabiners come in many sizes and shapes (fig. 6-35). Ovals (fig. 6-35a) are very popular because their symmetry makes them a good all-purpose shape. "D" carabiners (fig. 6-35b) also offer a good general-purpose shape and are stronger than ovals because more of the load is transferred to the long axis and away from the gate, the typical point of failure. Offset Ds (fig. 6-35c) have the strength advantage of standard Ds, but the gate on an offset D opens wider, making them easier to clip in awkward situations. Bent-gate carabiners (fig. 6-35d) are a specialty design most commonly used



Fig. 6–35. Carabiners: a, oval carabiner, with inset showing safe (notched) and unsafe (unnotched) carabiner gates; b, standard D carabiner; c, offset D carabiner; d, bent-gate carabiner; e, standard locking carabiner; f, locking pear-shaped carabiner.

on difficult routes where it's important to quickly clip and unclip the carabiners from the feel of the gates alone. These carabiners should always be used with a runner so that they are free to rotate.

Locking carabiners (fig. 6-35e), with a sleeve that screws over one end of the gate to prevent accidental opening, give a wider margin of safety for rappelling, belaying, or clipping into anchors. Some locking carabiners even have a spring that automatically positions the sleeve whenever the gate is closed. You can't forget to lock these carabiners, but you must always unlock them as well, which can be a nuisance. Pear-shaped locking carabiners (fig. 6-35f) are much larger at the gate-opening end than at the hinge end and are ideal for belaying with the Münter hitch.

A few basics apply to the use and care of all carabiners. First, always make sure the force on a carabiner falls on the long axis, and be especially careful that the gate does not receive the load. Check the carabiner gates occasionally. A gate should open easily, even when the carabiner is loaded, and the gate should have good side-to-side rigidity when open. A dirty gate can be cleaned by applying a solvent or lubricant to the hinge (oil, kerosene, white gas), working the hinge until it operates smoothly again, and then dipping the carabiner in boiling water for about 20 seconds to remove the cleaning agent. Finally, remember that a carabiner that has fallen off a cliff onto a hard surface has probably suffered hairline fractures and should be retired. Resist using such a "treasure" found at the base of a cliff.

In fact, you should resist using any equipment discussed in this chapter if you don't know its history. Ropes, harnesses, runners, and carabiners are all vital links in your chain of protection. Secondhand equipment, whether found or passed along without an account of its use, increases the possibility of a weak link in the chain you depend upon for safe climbing.

• 7 •

BELAYING

Belaying is a bedrock technique of climbing safety, a system of setting up the rope to hold a climber in the event of a fall. Belaying works like magic, but like any good magic trick, it takes a lot of practice to do well and requires a basic understanding of underlying principles.

In its simplest form, a belay consists of nothing more than a rope that runs from a climber to another person, the belayer, who is ready to put immediate friction on the rope to stop a fall. Three things make the magic work: a skilled belayer to apply friction to the rope, a stance or anchor to take the forward pull of the fall, and a method of amplifying the friction of the belayer's hand. There are many ways to amplify this friction, a variety of stances, and any number of methods for tying into the anchor. This chapter introduces the principal techniques and major options of belaying, so you can choose the methods that work best in your own climbing. The last section introduces the physics of belaying; you can skip this until you are thoroughly familiar with the procedures.

HOW BELAYS ARE USED IN CLIMBING

Before we move into the details of belay setups and procedures, it might be helpful to get a general feel of how belays are used on a climb (fig. 7-1). For the moment, picture just the essentials of a belay. There are two climbers, each tied into an end of a 150-foot rope. As one climbs, the other belays. The belay is connected to an anchor, a point of secure attachment to the rock or snow. The belayer pays out or takes in rope as the climber ascends, ready to use one of the methods of applying friction in case the climber falls.

Belay setups are usually established on the ground or on a ledge that is reasonably comfortable. One climber takes the lead, belayed from below, and moves up the route to the next desirable spot and sets up a new belay. The climber at the bottom then takes apart the belay and climbs up, belayed from above. The distance between belays is known as a pitch, or a lead. The climbers typically leapfrog their way up so that the one who goes first leads all of the odd-numbered pitches, and follows second on all of the even-numbered pitches. Each climber belays at the top of every pitch he leads, which allows a rest before following the next pitch.

The climber belayed from above—known as the follower, or the second—can climb aggressively, confident that any fall will be held easily by the belayer and will be very short, typically involving only a slight stretching of the rope.

It's a different matter for the leader of a pitch, who is belayed from below and will drop some distance before the rope begins to stop the fall. To reduce the distance of a potential fall, the leader attaches pieces of climbers' hardware—called protection—to the rock on the way up. The leader


Leader
Protection placed by leader while climbing
Belayer for second pitch
Belayer for first pitch
Protection removed by follower while climbing
Follower with upper belay

Fig. 7–1. The belay system for two pitches of a climb

attaches a carabiner to each piece of protection and clips the rope inside the carabiner so the rope is free to be pulled through as the ascent continues. Now, a fall can be no more than double whatever the distance the leader is above the highest piece of protection (plus some rope stretch and sometimes belayer movement or a bit of rope slippage at the belay).

The length of each pitch is usually determined by the location of a comfortable, convenient spot to establish the next belay. Being the belayer can be tough work—long, awkward and boring, but requiring nearly constant vigilance—making it essential to find a secure belay spot that is as comfortable as possible. Longer leads are more efficient, so if there are several nice belay ledges within reach of the rope, go for the highest one. The conditions of the moment can change this general rule. You may decide to set up the next belay somewhat early because the drag of the rope through pieces of protection and over rock is becoming too annoying. Or if a huge, enticing ledge is only 1½ rope lengths away, there is no advantage to pushing the first lead as far as possible, and you can just pick the most convenient intermediate belay spot.

The minimum belay location should have two attributes: good placement for anchors and reasonable comfort. Belayers also try to find a position where they can see the partner they are belaying. And they keep an eye out for rockfall if the climber is above. If there is significant rockfall danger, you might belay from the shelter of an overhang or bulge, or perhaps have your pack ready to hold above you, and wear a hard hat.

BASIC TECHNIQUES

A climber who is just learning to belay should select and stick to one method, perfecting it to the point that setup is largely automatic. At that stage, some climbers become very opinionated about the choice they've made. But the most experienced climbers often learn other methods and use them whenever they offer an advantage.

As you learn belaying, you will discover your own favorite tools and techniques. However you belay, the methods all boil down to a means of stopping a fall by applying friction to the rope and by resisting the forward pull of the fall.

PREPARING FOR THE PULL OF A FALL

There are two general approaches to belaying, depending upon whether the forward pull of the fall goes first to your body, or directly to the anchor.

Belaying from the anchor: Belaying directly from the anchor (fig. 7-2a) requires, at a minimum, complete confidence that the anchor is bombproof; in short, it will not fail under any conceivable force. If you are using one of the many available belay devices for applying friction to the rope, you must be able to assume a specific brak-



Fig. 7–2. Belaying: a, directly from an anchor; b, from the harness, with support from the anchor.

ing position for a fall. You need to be near the anchor, and of course you should be comfortable for the entire time or your attention will be divided and a poor belay will result. (In belaying from the anchor, there are unique advantages to the Münter hitch as a way to apply friction. The Münter hitch will be covered later in this chapter.)

Belaying from your body: In the other approach, the pull of the fall goes directly to your body (fig. 7-2b). You assume a belay stance by bracing against solid features of the mountain, and back this up with a snug attachment from you to the anchor. Friction on the rope comes from a belay device or Münter hitch attached to the front of the seat harness, or from a wrap of the rope around your hips. Your body, supported by the stance, takes the initial pull of the fall and keeps the anchor—the ultimate line of defense—from being fully tested. The inevitable movement of the belayer a few inches under the force of the fall also helps reduce the forces. If the consequences of a fall have been correctly visualized ahead of time, the impact on the belayer is small. You may be surprised to discover how readily a small belayer can catch a big climber. Belaying from a stance, with the climbing rope running directly to your body, helps prevent "sleeping at the wheel" during the sometimes dreary duty of belaying.

Which method is most popular depends in part on both local tradition and geology. In some mountain ranges or on certain routes, you will find belay spots where every available anchor is suspect; here a stance is essential. In other situations there will be a bombproof anchor but poor stances. The belayer may still set up a stance to simplify rope handling, knowing full well that the pull of the fall goes directly to the anchor. The stance can be used almost anytime, even when the stance itself plays a minor role in controlling forces. Belaying directly from the anchor, however, is done *only* when the anchor is believed to be bombproof.

Parts of the setup, and the constant task of rope handling, are the same for every belay, whether it's from your body in a stance or directly from an anchor. All belays depend on applying friction to the rope, and all belays (with occasional exceptions) require an anchor, either to take the pull directly or as backup for a stance.

The belay anchor

As the ultimate security for any belay, the anchor should be able to hold the longest possible fall and the full weight of both climbers. Anchors are essential on rock, snow, and ice for belaying and rappelling. You'll get a few tips here on selecting good anchors for belays, but for full details on finding and using natural features, and on using artificial protection on rock, snow, and ice, study Chapters 10, 12, and 14. This chapter will concentrate on ways to tie in to one or more anchors for belaying.

A large natural feature, such as a tree or pillar of sound rock, is an ideal anchor. However, it's easy to overestimate the stability of large boulders, which may be more lethal than stable. More important than size is the shape of the boulder's bottom, the shape of the socket it is sitting in or the angle of the slope it is on, and the ratio of height to width. Imagine the hidden undersurface and the block's center of gravity: will it pull over under a big load? Test it, but don't send it over the edge.

The beginner should not necessarily accept the first anchors that look good enough, but search widely for simple and obviously solid placements. When placing hardware, bend down, feel deep in cracks, and include everything within arm's length above or to the sides of your ledge. To save time, don't immediately pull out earlier hardware placements that seem less than optimal, as you may find nothing better. If a single bombproof anchor can't be set up, try to establish two or three that in combination will be capable of holding a pull. If you find an old bolt or piton already in place at the belay site, back it up with a second anchor because of the danger that the old placement is weak.

When the belay depends upon a single carabiner, use one locking carabiner or two regular carabiners with the two gates forming an X when held open and the carabiners are aligned (fig. 7-3). In free climbing, avoid chaining carabiners in suc-



Fig. 7–3. How to use two ordinary carabiners instead of a locking carabiner

cession, as a twisting motion relative to each other weakens them and can open a gate.

Tying into the anchor

The belayer ties in to the anchor with the climbing rope itself, using the first few feet of rope as it comes from its tie-in at the belayer's harness. The rest of the rope is available for use by the climber. The belayer faces quite an array of choices when it comes to knots and methods for tying in to the anchor. Let's take a look at them to identify some of the more useful.

One method of dealing with a large natural anchor is the simple technique of looping rope around it and clipping the loop back on itself with a carabiner (in a quasi–girth hitch). Tie an overhand knot in the end of the loop and clip the carabiner through that (fig. 7-4).

When a knot is needed to tie to an anchor carabiner, the figure-8 knot or the clove hitch is usually preferred. The figure-8 is strong, stable, and easy to untie. The clove hitch has the advantage of being adjustable after it is tied, and is the easiest way to back up a stance with a taut line from you to the anchor.

An anchor is often backed up with one or two other anchors. Because of its adjustability, a clove hitch on the carabiner at each anchor is the most convenient way to minimize slack between the anchors (fig. 7-5a). (Make sure the clove hitch is tight, or normal rope play will make it expand and possibly open the carabiner's gate. Beware of any pull on a clove hitch that makes it slide away from the end of the carabiner, which could also make it expand and open the gate.)



Fig. 7–4. Anchoring to a large object with a quasi–girth hitch

There is quite a disadvantage, however, in tying separate knots in a series of anchor carabiners, as in the series of clove hitches. If the anchor takes the force of a fall, all the impact first goes to a single anchor. The other anchors come into play only if the first one fails.

There are a couple of ways to overcome this disadvantage and spread the load so that more than one anchor takes the initial impact.

One way is to tie a clove hitch to each anchor carabiner, as before—but to run the rope back to a



Fig. 7–5. Tying into several anchors: a, with a series of knots—only one anchor holds weight at any given time; b, so that they all hold weight simultaneously.

locking carabiner at the harness and tie in (with a clove hitch) after every other clove hitch at an anchor (fig. 7-5b). This results in a section of rope tied between your seat harness and each anchor carabiner. You can then adjust the clove hitches to snug up the strand to each carabiner. Then if the anchor takes the force of a fall, the impact will be shared by the multiple placements, and if one fails, no drop results before the others come into play.

Another way to spread the load is the technique of self-equalization, which automatically distributes any force among all the anchors.

Two-point equalizing, using two anchors, is the simplest method of self-equalization (fig. 7-6a). Put a half twist in a high-strength runner (such as one made of Spectra), which divides the runner into two parts, and clip each end into an anchor with a carabiner. Then clip a locking carabiner over the X formed in the middle, from one half of the runner to the other, and tie into that carabiner.

Multipoint equalizing, using any number of anchors, is another technique in setting up a secure belay (fig. 7-6b). Take one high-strength runner, and clip it into the carabiners on each of the three anchors. Grasp the runner between each anchor, twist it 180 degrees, and clip each resulting loop into the main carabiner. Such twists guarantee that the main carabiner is clipped into, and not around, the runner, so that it will stay attached to the runner even if two of the three anchors fail. The smaller the runner, the smaller the drop if one anchor fails. Therefore, if the anchors are widely



Fig. 7–6. Equalization: a, two-point; b, multi-point.

separated, bring them together with other slings before equalizing.

How well an equalization setup reduces the pull on each individual anchor depends on the angle at the bottom where the parts of the runner come together. The smaller the angle, the less force each anchor will have to absorb. As the angle increases, each anchor is subject to an increasing force. Be sure that the angle is always less than 120 degrees. Above that, each anchor will actually be subject to a greater force than if equalization wasn't even used. This is true whether it's two-point or multi-point equalization.

Climbers also use the "triangle" method, instead of equalization, to spread the weight between two separate anchors. In a triangle, the runner simply goes through each carabiner in turn, without returning to the main carabiner between each anchor. Just as in equalization, the angle at the bottom where the two sides of the runner come together is critical. But with triangles, a significantly greater force hits each anchor for any given angle, compared with equalization (fig. 7-7). With triangles, the maximum angle can only be 60 degrees; beyond that, each anchor faces a greater force than if the method wasn't used at all. And for any given length of runner, the triangle puts more force on the anchors than equalization.



ANGLE	V	TRIANGLE
0°	50%	70%
60°	60%	100%
90°	70%	130%
120°	100%	190%
140°	150%	290%
150°	190%	380%
160°	290%	570%
170°	580%	1100%

Fig. 7–7. The force on two anchors depends upon the method of sharing the force and the angle at the bottom of the sling.

The triangle performs better when it comes to another aspect of hooking into two anchors. If one of the anchors fails in either the equalization or triangle methods, the belay will drop as far as needed to throw the weight onto the remaining anchor. This drop, though usually quite short, hits the remaining anchor with additional force. The drop will be less in a triangle setup, for any given length of runner used, than with equalization. This difference in the length of the drop increases with the length of the sling and with the distance between the two anchors.

Sometimes the length of the tie-in from you to the anchor is critical to the stability of your stance. Until now we have mainly discussed the situation in which the knots are located at the anchor. But if the anchor is out of reach, you can't adjust the knots while in your stance, so precise adjustment is tedious or impossible. The solution is to tie in with a knot only on your harness. Take the rope—after it has run from the harness and simply been clipped through the anchor carabiner—and tie it again at the seat harness. Make the new tie-in with a clove hitch, so you can easily adjust the tension on the rope between you and the anchor. In this option, the rope runs freely around a natural anchor or through a main anchor carabiner (fig. 7-8).



Fig. 7–8. A second tie-in on the climber's harness to allow convenient adjustment of tension on the anchor rope

The belay stance

If you belay from your harness or body rather than directly from the anchor, you usually will brace against the forward pull of a fall with a solid stance. The stance can help keep the anchor from being fully tested. You will usually support the stance with a short, tight rope to a strong anchor to greatly increase your stability. But for the moment we will consider the strength of the stance alone, based in part upon studies by the Sierra Club. Although the club's experiments used the hip wrap, the results apply to stances with modern belay devices (though perhaps a little on the conservative side). They give a good picture of the comparative value of different stances (fig. 7-9).

Located behind a solid object: In unusually fortunate situations, you can assume the strongest stance of all, directly behind an immovable object, such as a rock protrusion. Don't count on this luck often.

Sitting stances: The most common and versatile is the sitting stance, in which your feet and seat make three solid contacts with the mountain. It is most stable if the rope passes between your feet or legs, for it then resembles a tripod. The tripod's apex is the attachment of the belay to the front of your harness; one leg is your pelvic bones and seat, the other two your own legs. In that configuration, the average person can hold 350 pounds of tension on the rope for several seconds, or an impact about twice as great. Knees are strongest when the angle at the joint is nearly straight (180 to 140 degrees). The stance is only about half as strong if the knees are bent at an angle below 100 degrees, or if the rope runs over the foot support (directed slightly outside the tripod). The stance is suitable for rock, snow, or brush.

Standing stances: In the standing position there are only two points of contact with the rock. With one foot well forward, the average belayer can hold 200 pounds from below, but less than half as much with a pull to the side or with the feet together. Belaying a leader from a standing position (''slingshot'' belay) is extremely weak if the pull is forward. It should be done only with a short tight



Behind solid object: very strong

Standing: weak

"Sling shot:" very weak

Three-point, sitting: strong

Three-point, leaning: strong

Fig. 7–9. The strength of various types of stance, before adding support from the anchor

rope to the anchor, which will take most of the force, or when standing just below the first protection, so that you cannot be pulled over.

Even if your stance fails and you are pulled out of position, you *must* keep control of the rope. If you don't, it means loss of the belay and a disastrous plunge for the climber. Before tying in, visualize the consequences if you are pulled out of what you thought was a solid stance. Ask yourself if you will be able to keep charge of the rope and maintain the belay. The force on you will come from a new direction, pulling you into the straight line between the anchor and where the rope goes over the edge, or between the anchor and the first protection. The momentum of your body will carry you even farther; look to see whether you would strike something.

Imagine the results of being pulled in various directions, sideways or up or down, particularly if you are standing. There is less chance you will be jerked about, and you will be moved less, if you have a short tie-in from you to the anchor. This short tie-in is necessary if the direction of pull will change as the climber ascends. The longer the anchor tie-in, the more powerful and dangerous the pull. You must not be dragged, lifted into the air, or strike anything. It's OK to risk some movement in order to take advantage of a strong rock feature for a stance. But think it through. Visualize the possible consequences if you are pulled from the stance. If a loss of control of the rope is possible, find another solution.

Preparing to belay the follower

Because there are so many things to remember and balance, setting up the belay is one of the slower tasks for beginners. The more aggressively you search for anchors and stances, the more likely you will discover a simple solution. Don't rush the visualization stage. Here are factors to consider as you complete leading a pitch and have just reached a spot to set up a belay for the follower:

Establish an anchor for yourself and clip into it, and then call out "off belay" so the follower can stop belaying and start preparing to climb. Then attend to yourself. Take off your pack and the rack of climbing hardware. Put on extra clothes, if necessary, for the long period of staying stationary while you belay.

Search out available options for belay anchors and for a stance.

Visualize the consequences if your stance collapses.

Consider other factors. Assess the rockfall danger. Make the belay comfortable enough so you can belay without distraction. Try to be in position to watch the climber and route as you belay. An experienced climber can establish a belay that is also useful for belaying the next pitch, when the follower moves past and up into the lead.

Pick the best combination of anchor and stance, after weighing all the choices.

Check to be sure that knots are complete, that coils of rope won't snarl or catch on projections, and that your pack is conveniently nearby. For your very first belay, verify with your partner that you know the correct braking position—and that you are belaying the end of the rope that goes to the climber, not the end to the coils. (Partners should check each other's harness buckle and rope tie-in whenever roping up.)

Prepare to belay the next lead as soon as you have belayed the follower up to your position.

Preparing to belay the leader

Belaying the leader is a big change from belaying the follower because the pull is from a new direction, usually above. A new stance is often necessary.

The anchor for belaying the leader must hold a pull toward the first piece of protection, possibly straight up, so your existing anchor may have to be revised or augmented. Fortunately the follower has brought up all the hardware from the pitch below, so you should have plenty of gear to work with. Before setting up your belay, pull in all the slack rope, and pile it neatly to avoid snarls later.

The difference between a strong and weak stance is the direction of the expected pull in comparison with how your legs are placed. By putting in a piece of protection near you that the climber's rope will travel through, you can aim this pull to provide a stronger stance.

Aiming the pull is particularly useful with standing stances. If you are facing the anchor, a simple method is to add another carabiner to the anchor and clip the climbing rope through that. Later, after the climber has put in other protection higher up, this link becomes unnecessary, and you can remove it to reduce rope friction and increase your "feel" of the climber.

The belayer needs to be extra alert when the climbing is difficult right off a ledge because the leader may not be able to get in enough protection to prevent hitting the ledge in case of a fall. In fact, broken ankles are among the most common rock-climbing injuries. Of course, the climber should land with knees bent. Head injuries can be reduced by the belayer "spotting" the climber, preferably while tied in and otherwise ready to belay. Spotting does not mean cushioning the climber's weight with your body, but simply helping the falling climber land upright or preventing his head from hitting the ground.

The "zipper effect" is a concern for both belayer and climber. Whenever possible, the climber should position the lowest piece of protection to prevent this phenomenon, in which the bottom protection pulls out under the forces of a fall, and succeeding pieces up the route are yanked out one by one like the opening of a zippered jacket. To avoid it, the lowest protection should be multidirectional; that is, able to hold a pull from any direction, including outward or upward. If a zipper starts opening, you can only hope that a multidirectional piece of protection has been placed higher up that can put a stop to it. (Chapter 10 includes an illustration of the zipper effect.)

ROPE HANDLING AND COMMUNICATING

Ideally, when you are belaying the leader, the rope is never taut, which would impede the climber's next move. An alert belayer keeps just a hint of slack and responds immediately to the leader's advance by paying out more rope. When the climbing is easy, more slack is permissible.

As the leader climbs, it is inevitable that some friction will develop along the rope. This rope drag can greatly increase the difficulty of the climb or make the leader stop, creating time-consuming extra belays, often in uncomfortable spots. The problem can be caused by the terrain the climber passed, such as blocks of rock or rope-sized notches, or by poorly placed protection that forces the rope over convexities or into acute angles. Any friction applied by the belayer is multiplied by these, so if the leader tells you that rope drag is a problem, keep a few feet of slack in the rope and do everything possible to eliminate any pull. If the climber falls when there is a lot of friction in the system, the belayer may actually be unsure whether a fall took place. If it is impossible to communicate with the climber, you can find out by letting out a few inches of rope. If the same tension remains, then you are probably holding the climber's weight.

Ideally, when you are belaying a follower, there is no slack in the rope. At the same time, the rope should not be taut, which would hamper the climber's movement and balance.

When belaying a follower up to you, pile the rope where it won't be disturbed later. Don't let loops hang down if there are projections that could snag a loop. If the entire pile must be moved, picking it up is tempting but will produce snarls later. It is best to re-pile the entire rope twice, so the leader's end is on top. If the follower is climbing rapidly, you can take in more rope with each pull by leaning forward or bending over.

Your braking hand must never leave the rope. This is easier when belaying the leader because the leader is pulling up the slack. But when belaying a follower, you pull the slack in against gravity, and when you reset your braking hand, the natural tendency is to lift it off the rope. The correct procedure must be consciously learned (fig. 7-10).

To minimize falling distance, leaders preparing to make difficult moves often place protection well above their harness tie-in and clip in before moving up. This means the direction of rope movement will reverse twice. As you are belaying the leader and letting out rope, you will suddenly find yourself taking in slack as the climber moves up to the



Fig. 7–10. How to take slack in from a follower so the braking hand is always on the rope: a, pull in the rope with both hands; b, extend whichever hand is near your body, and grab both ropes with it, so that; c, the braking hand can slide back toward your body while remaining closed and ready to brake. Although a through c is commonly used with belay devices, another method offers extra security, as when the climber is at a crux. Keep the ropes in steps b and c apart and grab only the braking rope, as shown in the lower row of illustrations (d, e, and f).

protection, then letting it out again as the climber moves past the protection and puts renewed pull on the rope. These switches call for extra attention, especially as this tends to happen at the most difficult spots.

As climber and belayer get farther apart and hearing begins to be difficult, stick exclusively to the set of short commands that have been developed to express essential climbing communications. Prefacing them with explanations or justifications makes them harder to recognize and defeats their purpose. Use the commands alone. They have been chosen so that the sounds and number of syllables produce a distinctive pattern. Toward the end of the rope, shout as loudly as possible and space out each syllable, using very big spaces if there are echoes. In a crowded area, preface commands with your partner's name. Don't expect an audible response; just do your best the first time.

Three problems are common at the end of each pitch, when hearing is most difficult. First, when calling out to your leader the length of rope remaining in the coils, the first syllable is often lost, and if normal word order is used, the leader hears only "—ty feet." Instead, invert the word order and pronounce each digit separately: "Feet: . . . three . . . zero," for 30 feet. The climber will pause upon the first word and have a better chance of understanding the remainder. Second, when the leader completes a pitch and calls "Off belay," do not respond with "Belay off" to indicate you heard him, as is the natural reaction of a beginner. "Belay off" means you have taken apart your belay and the rope coils are ready to be pulled up, and you won't be ready to shout that command truthfully for a while yet. Third, avoid the impatient question "On belay?" unless a truly inordinate amount of time has passed. Usually the leader, at work on setting up anchors, is out of earshot anyway.

Commands are sometimes transmitted by rope pulls, but there is no universal system. Because of rope stretch at the end of long leads, it's necessary to greatly exaggerate the pulls. A simple tug will seldom be felt at the other end. Take in all slack and for each signal, yank 1 foot or more, holding it tight for awhile before releasing the tension. If there is much friction, pulls may not be distinguishable from normal rope movements. The most common commands correspond to the number of syllables in these verbal equivalents: one pull means "Slack," two means "Up rope," and three means "Belay on."

In reality the follower often decides when the belay is ready, based upon a partner's known rope-handling habits. Regular partners familiar with each other's habits can dispense with all normal commands, which is more aesthetic.

APPLYING FRICTION TO THE ROPE

In any belay method, the rope from the climber goes to a belay device or Münter hitch or around the belayer's hips, and then to the belayer's braking hand. This braking hand produces the belay, the controllable friction that is multiplied by a factor of as high as fourteen by the belay method and stops a falling climber.

Belay devices

Belay devices amplify the friction of the braking hand by passing the rope through an opening and wrapping it around a post. The opening guarantees a minimum of wrap, or bend, in the rope to produce enough friction on the post. The post is a locking carabiner or part of the device itself. The opening must be large enough to allow the device to touch the carabiner.

To stop a fall, the belayer pulls back on the free end of the rope to create a separation of at least 90 degrees between the rope entering the device and the rope leaving it. Nothing must be in the way of your braking hand or elbow carrying out this critical task, and it must not require an unnatural body twist or motion. The simplest way to learn to do this conveniently in all situations is to clip the device into a locking carabiner on your harness (currently the most popular belay method in the United States) rather than directly to the anchor. In this section on belay devices, we will stick to a description of their use when attached to the climber's harness.

Basic voice commands used by climbers:

Follower:	''That's me''	You have pulled up all the slack in the rope and are now tugging on my body; don't pull any more.
Belayer:	''Belay on''	I am belaying you.
Climber:	''Climbing''	I am, or will resume, moving up.
Belayer:	''Climb''	Response to ''Climbing.''
Climber:	''Slack''	Give me some slack in the rope and leave it out until I call ''Climbing.'' (If you want to indicate how much slack you need, the command would be ''Slack X feet,'' with X being the amount of slack.)
Climber:	''Up rope''	(Usually to upper belayer.) There is slack in the rope; pull it in.
Climber:	''Tension''	(Usually to upper belayer.) Take up all slack and hold my weight. (Should be used sparingly by beginners, to avoid overdependence on rope. Say ''Watch me'' instead.)
Climber:	''Falling!''	Assume your braking position and brace for a pull on the rope.
Belayer:	''Halfway''	About half of the rope remains.
Leader:	''How much rope?''	What length of rope remains?
Belayer:	''Feet ... four ... zero''	Forty feet of rope remains; find a belay soon (best used when 50 to 20 feet remain).
Leader:	''Off belay''	I am secure and no longer need your belay. Take it apart and prepare to follow the pitch.
Anyone:	''OK''	I heard you.
Follower:	''Belay off''	(After taking apart the belay.) You may pull in all the slack and remaining coils when you are ready.
Anyone:	''Rock!'' ''Ice!''	(Very loudly, immediately, and repeatedly until falling object stops; mandatory.) Falling objects. Look up or take cover.
Anyone:	''Rope''	A rappel rope is about to be thrown down by another party. Look up or take cover.

Climbers also use some discretionary voice commands, depending on local custom or prior agreement with a climbing partner. These are examples, and many idiosyncratic variations are also used.

Leader:	''Pro in''	I have just clipped into the first protection. Or I have clipped into protection located above my harness tie-in, so the direction of rope movement will reverse twice as I move up through a difficult spot.
Climber:	''Protection'' or ''Cleaning''	I am placing or cleaning protection and will not move up for awhile.
Climber:	''Good belay'' or ''Watch me''	I anticipate a fall or difficult move.
Climber:	''On top''	I have passed the difficulty.

Contrary to a popular misconception, there is no automatic clamping effect with a properly designed belay device. Your hand is the ultimate source of friction, and without your braking hand on the rope, there is no belay. The total friction is determined by the strength of your grip, the total number of degrees in the bends or turns the rope makes, and the rope's internal resistance to bending and deforming against the sides of the device and carabiner.

There are a number of popular belay devices (fig. 7-11). One general type may be referred to as an aperture device: It simply provides an aperture through which a bight (loop) of rope is pushed and then clipped to the locking carabiner on your harness or at the anchor. In one widely used version of this type, the aperture consists of a slot, or slots, in a metal plate. (The original and best known of these is the Sticht plate [fig. 7-11a].) In another version, the aperture is a cone-shaped tube (fig. 7-11b).

The figure-8 device (not to be confused with the figure-8 knot) was originally designed only for rappelling, not belaying. Some figure-8s now serve double-duty, for both rappelling and belaying. Figure-8s are seen in three different configurations as belay devices. One is the standard rappel configuration (fig. 7-11f). Another is set up like the Bachli (fig. 7-11e), described below. If the hole in the small end of the figure-8 is the size of a typical aperture device hole, it can also be used similarly to a slot or tube (fig. 7-11c). Make certain that your figure-8 was intended for belaying use by the manufacturer; most are not.

The Bachli device (fig. 7-11d) is, in appearance, a sort of streamlined figure-8. The bight of rope goes up through the large hole and is then clipped into a locking carabiner attached both to your harness and to the small hole in the device.

Your tie-in to the anchor should be on the braking-hand side when using a belay device. This way, your body rotation under the force of a fall will assist, rather than hinder, you in separating the ropes.

In belaying a lead climber, try to prepare for the possibility that before placing the first piece of pro-



Fig. 7–11. Major categories of belay device: a, slot; b, tube; c, figure-8 in aperture configuration; d, Bachli; e, figure-8 in Bachli configuration; f, figure-8 in rappel configuration.

tection, the leader could fall, plunging below your position. The braking hand should be on the opposite side of this possible fall, or you won't be able to separate the ropes entering and leaving the device.

Belayers rarely wear gloves when using a belay device, in part because the device itself provides a greater proportion of the total friction. However, rope burns are a possibility, although they seem to be rare.

When taking in or letting out slack with an aperture device (slot or tube), keep the ropes strictly parallel. Otherwise, the rope will pull the device up against the carabiner, and braking begins. Eventually the practice becomes automatic.

Among devices, slots and tubes produce the least friction in routine rope handling, which allows you to take in rope faster when the climber is on easy ground, and a slightly improved feel for small movements of the climber and elimination of slack. The Bachli configuration, however, generates less friction than slots and tubes when it holds a fall. This characteristic lends the Bachli to use on ice and snow, where stances and anchors are usually weaker and would benefit from a lower force, and where the consequences of a longer fall are often less important.



A belayer is called upon not just to stop falls, but to hold the climber stationary under tension, or lower him to a ledge. Devices vary significantly in how easily they perform these tasks. Slot devices require the least force to hold the climber's weight, but are the least smooth in lowering the climber.

Slots and tubes can be attached to a tether to keep them from sliding out of reach. Some of these devices include a hole for attaching the tether. A tether to your harness must be long enough so it doesn't interfere with belaying in any direction.

Like any piece of critical equipment made of metal, a belay device that is dropped a significant distance should be retired because internal stresses could cause it to break when holding a big fall.

Hard-anodized devices tend to glaze the outermost surface of the rope when stopping a fall, but this effect is purely cosmetic and not harmful. (The metallurgic process of hard-anodizing produces a thin layer of aluminum oxide whose surface is hard and microscopically pitted, and appears dull gray, black, or brown.)

Belay devices are also used for rappelling. Slot devices produce a jerky ride that puts unnecessarily high loads on the anchor. However, the slot design that has a spring may be OK, and tube devices may be acceptably smooth. The Bachli device and figure-8s are the smoothest for rappelling. However, figure-8s put one twist in the rope for every 10 feet of descent, producing snarls in the coils later.

The Münter hitch

The Münter hitch is a very effective method of using only the rope and a carabiner to provide the friction necessary to stop a fall. This method requires a large pear-shaped locking carabiner in order to allow the knot to pass through the interior. It amplifies the effect of your braking hand with the friction both of rope on rope and of rope on carabiner. When attached to the front of your harness it works much like a belay device. Although no belay method is foolproof, the Münter hitch requires the least skill and attention.

The Münter hitch is the only traditional belay method that provides sufficient friction regardless of the angle between the ropes entering and leaving it (fig. 7-12). This offers a number of advantages:

- No special braking position is required. Consider the situation of a belayer who cannot see the climber and is distracted at the moment of a fall. The belayer, caught by surprise, might merely squeeze the rope at the start, rather than immediately yanking it into the angle required by all other methods. This situation is unusual, but could occur at any time. The Münter hitch would hold. The other methods may not.
- If all of the slack rope is hanging down a wall, you may be unable to raise your braking hand high enough, as required by a standard belay device, to arrest a follower fall. The problem is caused by the weight of the rope, the extra force exerted by the falling climber, and the difficult arm position. But with a Münter hitch, it doesn't matter (fig. 7-13).

The friction of the Münter hitch is also unique in being less with the ropes 180 degrees apart than when 0 degrees apart. This usually means its friction is relatively less for leader falls than follower falls. But in absolute terms it often provides more friction than any other belay method, regardless of the angle between the ropes. This high friction means a quicker stop to a fall.



Fig. 7–12. The friction provided by the Münter hitch does not depend greatly upon the angle between the ropes.



Fig. 7–13. The Münter hitch works when the ropes must be hanging down a wall.

The Münter hitch has some drawbacks. Its friction, often higher than other methods, means more impact on a leader's protection and more danger that poor placements will pull out. It kinks the rope more than any other method, producing snarls in the last few feet of rope after several pitches, especially if the same person always leads. To unsnarl the rope, shake it out while it is hanging free. After a big fall, the outermost layer of the sheath is glazed (which, like the effect of hard-anodized devices, is probably only cosmetic). The Münter hitch isn't good for rappelling because it twists the rope once for every 5 feet of descent, and makes ropes very fuzzy if used regularly.

Every time the direction of pull on the hitch reverses, the entire knot first flip-flops through the carabiner oval. This can get a bit awkward when the leader clips into protection above, moves up toward it, and then passes it, because it requires the belayer to pay out, take in, and pay out rope in rapid succession, reversing the direction of pull on the Münter hitch each time. For a fall of a follower, or of a leader below a piece of protection, the Münter hitch produces an additional drop of 6 inches, as the knot pulls through the carabiner, before braking begins.

You may run across the Münter hitch under a variety of names, such as the friction hitch, Italian hitch, half ring bend, carabiner hitch, running R, half-mast belay, and UIAA method. It was introduced in Europe in 1973 as the *halbmastwurf sicherung* (half clove-hitch belay), now abbreviated as HMS. (Chapter 6 gives details on tying the Münter hitch.)

The hip wrap

The hip wrap (fig. 7-14) amplifies friction by passing the rope around your back—just below the top of your hips—and around your sides. Its main advantage is the speed with which you can belay a follower who is moving rapidly over easy ground. It can be set up quickly and requires no hardware.

The use of the hip wrap in climbing on upper fifth-class rock is rapidly declining. Because your back and sides provide most of the friction on the rope, you must wear a lot of clothes, preferably several thick layers—highly undesirable in hot climates. Even a short leader fall can cut through a polypropylene jacket. Although the belayer will feel the pain from the burn as it is produced, the fall will be completely arrested before he or she has time to react to the pain.

Because your hands provide a greater proportion of friction than in other methods, gloves are essential. Contrary to the usual expectation, burns are reduced with a tighter grip and less rope slippage (because slower rope velocity and less rope slippage generates less heat), another reason for wearing gloves. However, gloves can make your hands damp and soft, the opposite of what is necessary for difficult rock climbing.

There are additional problems with the hip wrap: if the climbing rope runs over the anchor attachment, it may be burned. In a big fall, the outermost layer of the rope sheath may be glazed and covered with melted fabric from your clothes. Because more time is required to attain the braking position and because it has the least braking friction of any method, the hip wrap more often results in rope slippage, and the climber usually falls



Fig. 7–14. The hip wrap is often used for the impromptu belaying of a fast-moving follower.

farther. If your stance fails, you will probably also lose control of the rope, which is less likely with other methods.

To catch a fall with the hip wrap, your elbow must be straight before you begin to grip hard (fig. 7-15), so that bone and not muscle resists the pull of the rope. (Your natural reaction will be to grip the rope first, but this may pull your arm into a helpless position, requiring you to let go and grasp the rope again.) Then bring your braking arm across in front of your body, to increase the amount of wrap for maximum friction. An optimal braking position can only be learned with practice, for which schools and climbing clubs have constructed belay towers.

Several precautions must be observed to prevent the hip wrap from unwrapping in a fall. With frequent practice, they should become automatic.

1. Run your anchor attachment from the side opposite the braking hand (fig. 7-16). If you put the line to the anchor on the same side as the braking hand, the rotation of your body under the impact of a climber's fall can unwrap the hip wrap, decreasing friction and stability.

2. If you are facing toward the rock, belaying the leader, have the braking hand on the same side as any fall that could happen before the leader puts in the first piece of protection. If the fall is on the opposite side and the leader drops below you, the rope could be unwrapped from your hip.

3. Clip a control carabiner on your harness anytime the climbing rope goes straight up or down from your hips (fig. 7-17). The carabiner goes well forward of the hip bone, on the same side as the rope coming from the climber. Clipping the rope into this carabiner keeps the rope where you want it, at your hip, and also counteracts body rotation.



Fig. 7–15. The correct braking arm position for the hip wrap must be achieved before braking begins, left; *or the arm will be pulled into a helpless position,* right.



Fig. 7–16. The anchor attachment on the side opposite the braking hand, left, *keeps the hip belay from unwrapping.*

4. If you don't use a control carabiner, take advantage of your anchor attachment to keep the climbing rope from being pulled over your head or under your seat. If the pull will come from below, put the rope above the anchor attachment. If the pull will come from above, put the rope below the anchor line.

Of all braking methods, the hip wrap exerts the smallest force for a given grip of the braking hand. In a fall, this lower force might preserve questionable protection when any other method would pull it out. This would be extremely important if both your stance and anchor were weak. On the other hand, the climber will fall farther, increasing the danger of hitting something.



Fig. 7–17. A control carabiner on the harness keeps the hip belay from unwrapping.



Fig. 7–18. A variant of the hip wrap, in which the forward pull of a fall goes directly to the anchor

As with belay devices, it is possible to arrange the hip wrap so that the forward pull of the fall goes directly to the anchor (fig. 7-18). This provides the same advantages as belaying directly from the anchor with a device. The friction of rope running against your back is replaced by the climbing rope's wrap of at least 90 degrees around the carabiner, a few inches to 1 foot or more behind your back. (If you are far from the anchor, a big fall could pull you toward it, especially on snow or wet rock.)

Fig. 7–19. Major belay options

METHOD	**REQUIRES**	**FEATURES, ADVANTAGES**	**DISADVANTAGES**
		Resisting the pull of the fall	
Belay attached to harness	Ledge permitting a stance	Force is absorbed before reaching anchor	Relationship between stance and anchor must be carefully visualized
Belay attached directly to anchor	Bombproof anchor	Simple set-up (except hip wrap); easy to tie off	Anchor not always available, or conveniently placed for rope-handling
		Applying friction to the rope	
Belay device	Device, locking carabiner	Some devices useful for rappelling	Figure-8s kink rope to some extent
Münter hitch	Large pear-shaped locking carabiner	Braking possible with ropes parallel	Slightly slower passing knot through carabiner; kinks rope; follower fall of at least 6 inches
Hip wrap	Protective clothes, gloves	Least braking friction; fast taking in rope	Burns possible unless much clothing worn; complex precautions required; greater chance of loss of control of rope if stance collapses

Fig. 7–20. Common beginner problems

PROBLEM	CORRECTION
Removes braking hand from braking rope (especially with hip belay)	Use the rope-handling procedure shown in fig.10,forcing yourself to be conscious of your braking hand at all times, until the technique becomes automatic.
Produces rope tension on leader	Watch leader or free-hanging sections of rope (if any) near your belay; keep hand on rope to feel movements; react quickly.
When belaying follower, unable to pull in rope fast enough	Bend over and extend your full reach for each cycle.
Great difficulty communicating when separated by a rope length	Stick to standard or agreed-upon commands; omit explanations; space out words more

OTHER TECHNIQUES

DECIDING WHEN TO ROPE UP

Climbers don't rope up and belay for every exposed place. There are occasions when it may be safer not to, even though you might wish you could. Rubble-strewn slopes are much more hazardous when dragging a rope. Some terrain has no suitable points for anchors. If you must pass through an area subject to rockfall or avalanche, roping is usually secondary to speed. Very experienced climbers may climb on solid rock well below their limit, ''third-classing'' what may nominally be a fifth-class route.

Anyone in the party may ask for a belay at any time, and must receive it immediately and without complaint from other members of the party. The primary exception is when roping up would significantly decrease the safety of the entire party. As difficulty and exposure increase on an alpine climb, natural differences in ability tend to spread the party out. It is just then, as the anticipated limit of the weakest member is approached, that the party must concentrate on keeping together, to enable roping up easily.

TYING OFF THE BELAY

There's at least one aspect of belaying you hope you'll never have to use: tying off the belay in order to help an injured partner. If your climbing partner is seriously injured and other climbers are nearby, it is usually best to let them help while you continue to belay. By staying there you could also help in raising or lowering the victim, if necessary. But if the two of you are alone, it is rare but conceivable that you may want to tie off the climbing rope to remove yourself from the belay system, so you can investigate, help your partner, or go for help.

If you are using a belay device or Münter hitch attached directly to the anchor, you need only to prevent rope from sliding through the belay. Simply form a knot such as the clove hitch in the braking rope and clip it to another carabiner on the anchor. You can now take your hand off the braking rope and it will be held by the knot.

If you are using a stance, with a belay device or Münter hitch attached to your harness, it is possible to tie off using one hand. However, it is easier and safer to put a clove hitch in the braking rope and clip it temporarily to your harness. Then while the clove hitch is doing the job of holding the belay rope, attach a normal sling to the climbing rope with a friction knot (prusik or Klemheist). Clip the sling into the anchor, chaining slings if necessary to make the connection long enough. If you can't reach the anchor, attach another sling with a friction knot to the rope that is holding you to the anchor, and join the slings with a carabiner. Transfer tension from the belay to the anchor by letting rope slip through the belay. But first tell the climber to expect being lowered a few inches, and not to worry.

With the hip wrap it may be impossible to tie off with one hand while in the braking position, so the first step may be to free yourself from holding the weight. Wrap the rope coming from your braking hand around the foot opposite the braking hand, keeping your knee locked (fig. 7-22). You can then proceed with both hands, attaching a sling to the climbing rope with a friction knot and clipping the sling to the anchor.

In any case, you should eventually back up the arrangement by tying the climbing rope itself directly to the anchor, with a figure-8 knot on a separate carabiner (fig. 7-21).

SELF-BELAYED SOLO CLIMBING

Self-belay devices, which allow roped solo climbing, have begun to appear. It is worn by the climber, and works like a ratchet, sliding up the rope during the climb, but not down it in a fall. To lead a pitch, the rope is first anchored at the bottom, and the climber protects as he ascends. Then the rope is anchored at the top, and the climber rappels. Finally, the climber removes the bottom anchor and climbs the pitch a second time, retrieving the protection as he goes.

This is not just another belaying alternative to be chosen on occasion. It is a different form of climbing, requiring a commitment to relearn many fundamentals. Shortcomings compared to a belay by a live partner are almost inevitable. Read the manufacturer's literature critically, and practice in a safe situation. Is the belay static? Does it work if you fall in a horizontal or head-down position? When climbing, does the rope feed automatically, without producing extra slack or drag, especially at the top of a pitch, or on a traverse? Can you clip into protection above your waist without trouble? To fully evaluate the device, you should understand the basic physics of belaying, as described in the next section.



Fig. 7–22. Freeing the hands before tying off the climber when using the hip wrap



Fig. 7–21. Tying off a fallen climber

THE PHYSICS OF BELAYING: WHAT HAPPENS WHEN THE CLIMBER FALLS

Many years ago, the leader's main fear in a fall was the very real possibility that the rope would break. Ropes were made of the natural fiber hemp, and if a belayer held on too strongly, the rope would snap, even in a fall that by today's standard is not long. To prevent this, early editions of this book said that beginners had to study the theory of something called dynamic belay technique and practice it every year by holding simulated falls with heavy weights. Today, this is no longer necessary. Everyone takes for granted that a belay, correctly set up and executed, will eventually hold any fall. Modern ropes seldom, if ever, break (although they can be cut by a sharp edge of rock).

Today, the leader's main fear in a fall is the failure of his *protection*. Protection is explained fully in Chapter 10, but its general purpose is shown in figure 7-23. The topmost piece of protection stops a leader fall. If it is pulled out of the mountain, then the climber falls much farther, until the next protection gets a chance to hold the fall. Unfortunately, the protection is the weakest link in the belay system. This is partly because the force on the protection is greater than anywhere else, 50 percent greater than in the rope between the top protection and the climber. But the major factor is the uncertainty of the protection itself. Usually the limiting factor is not the breaking strength of the hardware, but the firmness of its fit in the rock and the quality of the rock (or ice) itself. Climbing lore is replete with true horror stories of supposedly "bombproof" protection that pulled out of the mountain in a fall, or even after a firm test tug. Therefore, the older belay techniques for reducing forces, described below, are still relevant. They are not necessary to save the rope and the climber's life, but many experienced climbers know them and occasionally use them to protect the protection. Be forewarned: there are few simple rules. Many decisions involve some trade-off between benefit and risk. The best choice is seldom clear. However, if you understand how a belay works,



Fig. 7–23. If the topmost protection fails, the climber will fall an additional distance, which is twice the distance to the next protection down.

you can, at least, decide what would be a bad choice in certain situations.

We will progress from simple concepts of belay physics to complex ones. A little history can illustrate the principles.

WHAT DETERMINES THE FORCES IN A FALL

Static belay

The simplest belay is the one the word originally meant. The sailor wraps rope around a cleat so that it cannot be pulled; the earliest climbers wrapped rope around or over a boulder or rock horn or the like, hoping for the same result. The only difference between this and tying the rope directly to an anchor was that the rope could be fed out or taken in without untying and retying a knot. Today, a firm grip on the rope, coupled with a sufficiently small protected fall, produces the same functional result—no rope is pulled through the belay. By definition, this is a *static* belay. In fact, most falls today are held by static belays.

In a static belay we encounter the strangest truth in all of belay theory. The forces are determined only by the distance of the fall, divided by the length of the rope between climber and belayer (see fig 7-24). This number is so important it has a name: the *fall factor*. It is a pure number, independent of the scale, such as feet, used to calculate it. Thus, for example, a 20-foot fall on 100 feet of rope has the same fall factor as a 2-foot fall on 10 feet of rope: 0.2. Both falls produce the same force in a static belay, if the climber's weight and the rope's characteristics are identical. If a climber falls before placing any protection, the fall factor is 2, the maximum possible. No matter whether the climber was just above the belayer, or if he was at the top of a 150-foot pitch on an ice face, the resultant forces are the same (neglecting friction on the rock and in the system, air resistance, etc.). The energy of the longer fall is absorbed by the proportionally longer rope.

The rope's characteristics are crucial, because in a static belay, the rope absorbs nearly all of the energy of the fall. The more the rope stretches, the lower the forces become. The effect is dramatic. An old hemp rope stretches little, producing forces so high that it will break if the fall factor is greater than about 0.25 and the belay is static! A modern climbing rope stretches so much that no fall should exceed its strength if the rope is new and undamaged. Therefore, manufacturers no longer specify rope strength by the force required to break it, but by the number of standard static falls it will hold


1800 LBS.
1200 LBS.
600 LBS.
A
B

Fig. 7–24. Fall factor is defined as the fall length A, divided by the length of rope between the climber and belayer. (Slack rope contributes to A. B is due to rope stretch and/or slippage at the belay.)

before breaking. The standard is administered by the Union Internationale des Associations d'Alpinisme (UIAA). In order to pass this test, a rope must hold at least five such falls, spaced five minutes apart. The maximum force on the protection must not exceed 2,700 pounds (1,800 pounds for a half rope) on the first fall. However, this is still basically a rope-strength test. Because it uses a static belay and the extremely high fall factor of 1.7, it does not show the forces produced by real belays of typical falls. The only fall length tested is 16 feet long.

If all belays were static, fall factor alone would determine the forces of a fall, and forces could be controlled quite simply. The rule would be: it is more important to place protection at the beginning of a pitch, than at the end. This is because a given fall produces the highest force early in the pitch, the lowest force at the top. Although it is still good to keep that rule in mind, the forces in a real fall are reduced by two other factors. They constitute the difference between the static belay of the sailor and the actual belay given by the climber. These are: movement of the belayer, and friction on the rope at the belay. We will introduce them in their historical context.

The early climber's equivalent of a "cleat," a rock feature around which to belay a rope, was not always conveniently located near a place to stand or sit. The belayer, therefore, often substituted his own body for the cleat. It was quickly realized that if the belayer moved under the force of the fall, the force was significantly reduced. Sometimes called the *resilient belay*, this had one problem: the greater the movement, the greater the chance of collapse and total failure. Some authorities encouraged belayer movement, others warned against it. It is not surprising that up to the middle of the twentieth century, the situation was summed up in the golden rule of climbing, "the leader must not fall."

But world-famous climbers did in fact survive leader falls, which the theory of the day said should have broken their ropes. Some suspected that rope slip in the hands of their belayer played a role in saving their lives. But this was considered to be a partial loss of control of the rope, embarrassingly close to total failure of the belay. Its implications were seldom even discussed.

Dynamic belay

The first real breakthrough in belaying was the full realization of the value of substituting a frictional grip on the rope for a static belay. When the rope was pulled through a belayer's gloved hand, the climber decelerated slowly. The energy of the fall, instead of being absorbed in a small fraction of a second, was spread out and thereby reduced. The Sierra Club, in the 1930s and 1940s, demonstrated the value of the new *dynamic belay* theoretically, experimentally, and by putting it into actual practice. It was so successful that it allowed modern rock climbing to begin in Yosemite. The new golden rule became, "the rope must run."

There is a fundamental trade-off in a dynamic belay. It decreases the forces on the top protection at the expense of a longer fall and a greater risk of hitting something before being stopped by the belay. However, the benefit can be surprisingly great, as you can see from figure 7-25, which shows the effect with modern ropes. For example, if the climber is 8 feet directly above the protection



Fig. 7–25. The trade-off in a dynamic belay

and 32 feet from the belayer, the fall factor is 0.5. If rope slippage at the belay increases the fall 33 percent (5 feet), the force on the protection will be reduced by almost half. The benefit is greatest at high fall factors, which is also when rope slippage is most likely to occur. (This graph is based upon the current standard theory of belaying developed forty years ago by Wexler, which includes several simplifying assumptions, including simplifying the rope's characteristics and neglecting friction in the system and between the climber and the rock).

Modern kernmantle ropes stretch so well that they removed the necessity for the beginner to learn dynamic belay theory and technique. The golden rule ''the rope must run'' passed into history. Indeed, kernmantle ropes are frequently called ''dynamic ropes.'' But that does not mean a dynamic belay—rope slippage—never occurs; it means only that it is now very uncommon. Rope slippage is still possible if the fall factor is high, or the belay friction is low. In either case, the pull on the rope exceeds the friction in the belay, so the rope slides.

We have just considered separately the three factors that determine the forces of a fall: fall factor, belayer movement, and belay friction. To see how they work together, we will use the graph in figure 7-26. A given fall held by a given belay method produces a certain tension in the rope between the climber and the protection, which can be calculated using the current standard theory. The result is a point in this graph. A series of falls at different fall factors produces a line in the graph. In other words, each line shows the force produced by a given type of belay, at different fall factors. The solid lines represent static belays wherein all of the energy is absorbed only by rope stretch. There are two lines, showing the great difference between modern kernmantle and early hemp ropes. The dashed lines show the effect of 1 foot of belayer movement, holding an 8-foot fall, with each rope. The two horizontal lines show the effect of dynamic belays with two different levels of friction. These levels are the highest and lowest friction that have been suggested by various authorities in the past twenty years.



Fig. 7–26. Comparison of the major belay types

To illustrate, consider the previous example, whose fall factor was 0.5. If the belay is static, the peak tension is 1,200 pounds. If the belayer moves one foot during the fall, the tension is reduced by only 75 pounds. The ''strong dynamic belay'' in the graph reduces the force to 900 pounds, and the ''weak'' one reduces the force to 400 pounds. (The fall would be 2 and 12 feet longer, respectively). The same dynamic belays would, be definition, result in the same tensions in a hemp rope, regardless of fall factor. Of course, a static belay would break the hemp rope.

In summary, the friction applied to the rope at the belay places the real practical upper limit on the forces that a fall can produce. In other words, rope slippage at the belay dissipates excessive force, just like a safety valve on a boiler dissipates excessive pressure. How the belay is chosen and applied determines the force at which the rope slips, just as how the valve is designed determines the pressure at which it opens. Let's look more closely at how the belayer's ''safety valve'' works.

WHAT THE BELAYER CAN CONTROL

Three factors, which are at least theoretically under your control, determine the amount of friction that your belay will produce. The strength of your hand grip is one factor. Since the belay ampli-



Fig. 7–27. Comparison of some dynamic belay methods

fies this grip, your choice of belay method is a second factor. Both of these factors are shown in figure 7-27. For example, virtually anyone can grip a rope hard enough to hold a 50-pound pull. A standard slot device or the Münter hitch will amplify this grip so that your belay can hold a 350-pound steady pull before the rope begins to slide. (But as you grip harder, the Münter hitch grips harder than slot devices do, as shown by the diverging lines.) Figure-8 devices come in a wide variety of sizes and surface finishes, so their belay varies from 250 to 430 pounds, with a 50-pound grip. A standard slot device with two carabiners holds 700 pounds. (Different ropes can produce somewhat different numbers. For example, using a half rope, forces are reduced by an average of 20 percent.)

The third factor determining belay friction is the angle between the ropes entering and leaving the belay device or the Münter hitch, or the total number of degrees in all the wraps of the rope in the hip belay. Varying this factor produces a continuous change in the total grip, with no angle at which a sudden change occurs, for any belay method.

The belay method is the most important of the three factors, because it operates for every fall. Hand strength and rope angle can usually be varied only when a fall is expected by the belayer. Taken by surprise, a belayer will react as he has trained himself to do, with full braking efforts.

Although you can predetermine the level of friction to some extent, it would be an overstatement to say that you can precisely control it. Probably the most you can do is to seek to avoid the extremes. High friction is justified whenever protection is known to be bombproof. Low friction might be called for when protection and anchors are poor, or rope drag (acting just like the belay itself) is very high, or for a very long fall on uncertain protection, provided the extra fall length is not itself a hazard.

Most belays are chosen and executed by a given belayer in that belayer's customary way, to allow concentration on other aspects of climbing, as it should be. But armed with a knowledge of how belays work, informed climbers can recognize extreme conditions and may decide to vary their belay accordingly.

• 8 •

RAPPELLING

Rappelling can be so easy and exhilarating that you forget what a serious undertaking it really is. It's an indispensable activity in climbing, but it's also one of the more dangerous. If you learn it carefully from the start, you should have no trouble using this technique for sliding down a rope, controlling your speed with friction on the line. You will be able to descend almost any climbing pitch on rappel and, in fact, rappelling will be the only way to get down some faces of rock or ice.

You can get a sense of the danger by considering that as you rappel down a high cliff, full body weight on the rope, your life depends all the way on the anchor to hold the rope and on you to use the correct technique. If you fail or the anchor fails, you fall. Unlike belaying, where a large force comes on the system only if you fall, the force on the rappel system is always there. Despite the danger, it's easy to become cocky and careless after you learn how simple rappelling can be, and the exhilaration can encourage hazardous technique.

Coming down from a climb, there's often a choice between rappelling and downclimbing. Sometimes rappelling is the fastest and safest way to descend a particular pitch, but many times it is not. Think it through, considering the terrain, the weather, how much time is available, and the strength and experience of the party. If you decide to rappel, do it safely and efficiently. One of the hidden dangers of rappelling is that it can waste an awful lot of time in the hands of inexperienced rappellers.

RAPPEL SYSTEMS

A rappel system has four basic requirements: a rope, an anchor, someone to rappel, and a means of applying friction to the rope. The midpoint of the rope is looped through the anchor (a point of attachment to the rock or snow), with the two ends hanging down the descent route. The rappeller slides down this doubled rope and retrieves it from below by pulling on one end.

In mechanical rappel systems, the doubled rope passes through a friction device attached to your seat harness. In non-mechanical systems, friction is provided by wrapping the rope around your body. In either case, your braking hand grasps the rope to control the amount of friction. Gloves are usually worn to prevent rope burns.

Short rappels can be handled with just one rope, but longer rappels need the extra length of two ropes tied together, usually with a double fisherman's knot. The ropes are joined next to the anchor, with the two loose ends hanging down the cliff. With a two-rope rappel, you can even join ropes of different diameters, mating, for example, an 11-millimeter line with a 9-millimeter.

On rare occasions, climbers use a single-strand rappel, in which the rope is simply tied at one end to the anchor.

MECHANICAL SYSTEMS

Most climbers use a mechanical system (fig. 8-1) as their principal rappelling method, and all operate essentially the same. The two strands of rope are run through a rappel device attached to your harness. As you begin the rappel and gravity pulls you downward, the rope slides through the device. Your braking hand controls this natural pull by adjusting the amount of friction on the rope as it runs through the device. It does this through a combination of variations in grip and hand position. With some setups, you get additional friction by wrapping the rope partly around your back. You control the speed of descent, and you can come to a stop anytime you wish.

It takes less effort to produce friction at the top of a rappel than at the bottom, because the weight of the rope hanging below you puts added friction on the rappel device. This is especially so on very steep or overhanging rappels where most of the rope hangs free. But no matter how little grip strength may be required to control your descent, your braking hand must never leave the rope. Your other hand—the guiding, or uphill, hand—slides freely along the rope to help maintain balance.

To rappel with a mechanical system, you need to wear a seat harness, or an improvised diaper sling or figure-8 rappel seat. Never rappel with a simple loop of webbing tied around your waist, because it can constrict your diaphragm enough to make you lose consciousness.



Fig. 8–1. Mechanical rappel system



Fig. 8–2. Diaper sling

The diaper sling (fig. 8-2) takes about 10 feet of webbing tied into a large loop. With the loop behind your back, pull an end around to your stomach from each side. Bring a piece of the webbing from behind your back, between your legs, and up to your stomach to meet the other two parts. Clip them together in front with doubled carabiners or a locking carabiner. The diaper may also be clipped to a waist loop.

The figure-8 seat (fig. 8-3) is improvised from a standard-length runner. It must be clipped to a waist loop for stability.

Carabiner brake method

A very widely used mechanical system, the carabiner brake is somewhat complex to set up, but has the virtue of not requiring any special equipment—just carabiners. All climbers should know how to use the carabiner brake method, even if they normally use a specialized rappel device. It's a great backup if the device is lost or forgotten, and it's the safest method of rappelling without a special device.

To create the carabiner brake setup, start by attaching one locking or two regular carabiners to your seat harness. Any time a regular carabiner could be subjected to a twisting or side load, two carabiners or a locking carabiner are needed, and this is one of those cases. If you use two regular carabiners, position the gates to keep them from being forced open and accidentally unclipping (fig. 8-4). The correct position is with the gates on opposing sides, forming an X when they are opened at the same time.



Fig. 8–3. Figure-8 sling



Fig. 8–4. Proper and improper positioning of gates on double carabiners

After attaching the harness carabiners (or locking carabiner), clip another pair of carabiners to that, in the same correct position. Then face the anchor, if you can. Lift a loop of the rappel ropes through the outer carabiner pair. Take yet another carabiner and clip it across the outer carabiner pair, beneath the rope loop. The rope then runs across an outer edge of this final carabiner, known as the braking carabiner.

One braking carabiner (fig. 8-5a) provides enough friction for most rappels on ropes that are 10 or 11 millimeters in diameter. You might need a second or even a third braking carabiner (fig. 8-5b) for thinner ropes, heavy climbers or heavy packs, or steep or overhanging rappels. The ropes must always run over the solid side of the braking carabiners, never across the gate.

There are a couple of things to watch for as you're setting up the carabiner brake system. First, it's sometimes not possible to face the anchor as you pull the loop of rappel rope into the carabiner brake, and this can get confusing. A common beginner's mistake is to pull the rope into the system backward, as if preparing to rappel uphill toward the anchor.

Second, the weight of the rope hanging down the cliff may make it very difficult to pull the loop of rope up through the outer pair of carabiners and hold it while you clip in the braking carabiner. It helps to get that weight off the system. You can do that before pulling the loop of rope through by yanking up some slack rope and throwing a couple of wraps around a leg to take the weight. Or you can do it by pulling the loop through first, but making it extra large so you can lay it over your shoulder while you clip in the braking carabiner. Then drop the downhill strands back through the system so the brake remains close to the anchor.



Fig. 8–5. Carabiner brake system: a, with one carabiner clipped across the outer carabiner pair; b, with two carabiners clipped across the outer carabiner pair in order to give greater friction.

If you are near the edge while setting up the carabiner brake or any other rappel method, you should be attached to an anchor for safety.

Figure-8 rappel device

The figure-8 is probably the most popular special device for rappelling (fig. 8-6). It is simpler to set up and requires less force to control than the carabiner brake method.

Keep in mind the disadvantages. It means carrying an extra piece of equipment, and most figure-8s are relatively heavy. If you lose or forget it, you must be prepared to use another rappel method. Most figure-8s require use of a locking carabiner and don't give you the option of using doubled carabiners. And the figure-8 puts some twists in the rope. The figure-8 was designed for rappelling, though some climbers use the device in one of several possible configurations for belaying.

Other rappel devices

Many other devices are used for rappelling. Most are primarily belay devices that can also be used for rappelling, such as belay plates (slots) and tubes. Some have disadvantages, such as being difficult to feed rope through or heating up easily. Before buying any new device, check climbing literature for evaluation and test data, and read the manufacturer's instructions closely.

Other mechanical systems

Several mechanical rappel systems require no special device, just a locking carabiner. It can be worthwhile insurance to learn at least one of them.

To set up the carabiner wrap system (fig. 8-7), clip a locking carabiner into the locking carabiner or doubled carabiners that are clipped to your seat harness. Run the rappel rope through the outer end of the outside carabiner, and wrap it around the carabiner's solid back, giving it more turns if you want more friction. Two turns are usually just about right. Position the outer carabiner so that the locked gate opening is at the far end. A hazard of the carabiner wrap system is that the carabiner could flip around, and the movement of the wrapped rope might then unlock it.

The Münter hitch used for belaying can also be used for rappelling (see Chapter 7 for details on



Fig. 8–6. Attaching a figure-8 device for use in rappelling: a, figure-8 rappel device; b, attaching rope to the figure-8 device; c, figure-8 rappel device in use.



Fig. 8–7. The carabiner wrap system

using the Münter hitch while belaying). It's very easy to set up, but is the worst method for twisting the rope.

A method common in Europe merely runs the rappel rope through a locking carabiner at the harness, up over the climber's shoulder, and then down across the back to the opposite hand for braking. A danger is that, like non-mechanical systems, it is easy to fall out of.

NON-MECHANICAL SYSTEMS

Two traditional rappel methods use no hardware whatsoever to create friction on the rope. It's just the rope and your body.

The arm rappel (fig. 8-8) isn't used much, but it's occasionally helpful for quick descent of a low-angle slope. Lay the rappel rope behind your back, under your armpits, then wrap it once around each arm. Control your rate of descent by hand grip. For an arm rappel with a pack, be sure the rope goes behind the pack rather than on top or underneath.



Fig. 8–8. The arm rappel

The dulfersitz (fig. 8-9) is a simple all-purpose method that should be mastered by every climber for emergency use if you have no carabiners or seat harness. Face the anchor and step into the dulfersitz by straddling the rope. Bring it from behind around one hip, up across your chest, over the opposite shoulder, then down your back to be held by the braking hand on the same side as the wrapped hip. The other hand is your guiding hand to hold the rope above you to help stay upright.

The dulfersitz has a number of drawbacks compared with mechanical rappel systems. It can unwrap from your leg, especially on high-angle rappels, though it helps to keep the wrapped leg slightly lower than the other. Stay under careful control and try to pad your body, because rope friction around your hip and across the shoulder will be painful, especially on steep rappels. Turn your collar up to protect your neck. If you're wearing a pack, the dulfersitz is even more awkward. The dulfersitz is used in modern climbing only when there is no reasonable alternative or for short, easy rappels to save the trouble of putting a seat harness back on.

RAPPEL ANCHORS

You will often be hanging your full weight on the rappel anchor, which is simply some point of attachment to the rock, snow, or ice. Set up the anchor as close as possible to the edge of the rappel route (providing you can get a solid anchor). This provides the longest possible rappel. It also makes it easier to pull the rope down from below after the rappel, and often reduces the danger of rockfall as



Fig. 8–9. The dulfersitz

you do so.

Think about possible effects on the rope as you are looking for an anchor. Locate the anchor so as to minimize chances of the rope being pulled into a constricting slot or otherwise hanging up when you try to pull it down from below. Check the position of the rope over the edge of the rappel route as the person before you finishes rappelling. If the rope moves near or into a slot in the surface that could restrict its movement, consider relocating the anchor.

You can use natural anchors or artificial (manufactured) anchors, just as you do for belaying or for placing points of protection during a climb.

NATURAL ANCHORS

The best natural anchor is a living good-sized, well-rooted tree. The rappel rope usually goes through a runner that is attached to the anchor. If you can attach this runner to a tree branch rather than low on the trunk, it helps limit the rope's contact with the ground, making it easier to retrieve the rope and reducing rope abrasion and the risk of rockfall. But note that connecting to a branch rather than the trunk puts more leverage on the tree, increasing the danger that it could be pulled out. Be cautious in using bushes as an anchor, and if you do use one you'll probably want an additional anchor or two for safety. Also be careful using trees and bushes in very cold weather, when they can become brittle. Rock features—horns, columns, chockstones, large boulders—are commonly used as anchors. On snow or ice, you can make bollards (see Chapter 12 for illustrations of snow bollards).



Fig. 8–10. Runner looped around a rock horn: a, a dangerous rappel anchor; b, runner rides up and off rock horn.



Test a natural anchor if there's any question about whether it can support the weight of the heaviest climber, plus a large safety margin in case a rappeller puts extra force on the anchor by stopping quickly. You can test rock horns and smaller trees by pushing against them with your foot. Test the anchor before rappel gear is attached, and never after the rope or the rappeller is hooked in.

If you run the rappel rope through a runner looped around a rock horn (fig. 8-10a), be rigorous in determining the angle of force on the horn. You must eliminate the deadly possibility the runner could ride up and off the horn during a rappel (fig. 8-10b). Most climbers use only a single anchor if it's a solid, dependable natural anchor—but add another anchor or two if there are any doubts.

ARTIFICIAL ANCHORS

As a rule of thumb, if you are using artificial (manufactured) anchors, use at least two and try to equalize the load between them.

In unknown alpine terrain, some climbers carry pitons and a hammer to set anchors. The most common artificial rappel anchors are bolts or pitons that have been left in place by previous climbers, and which must be evaluated for safety just as if you were using them for belaying or for protection while climbing.

The climbers' hardware known as chocks—nuts, hexes, and so forth—are usually used only if no good alternative is available, but better a couple of good chocks than a shaky rock horn. It's not a good idea to trust chocks that you find already in place, left behind by climbers who weren't able to work them loose from their crack in the rock. However, sometimes you can take advantage of an abandoned chock by using it like a natural chockstone—looping a runner directly around it and making no use whatsoever of the sling attached to the old chock.

SETTING UP THE ROPE

To get the rope ready for rappelling, you attach it to an anchor. In the simplest case, you would untie a runner and retie it around a tree as a rappel sling. Then the midpoint of the rope is suspended from the sling (fig. 8-11a).

If you're using just one rope, put one end of the rope through the sling and pull it until you reach the midpoint. Or you can put the sling around the midpoint before you retie it around the tree. If you're joining two ropes together for the rappel, put one end of a rope through the sling and tie it to the other rope with a double fisherman's knot, backed up with overhand knots.



Fig. 8–11. Rappel rope attached to tree: a, rappel rope through a sling around a tree; b, poor—rappel rope directly around tree.

You could put the rope directly around the tree (fig. 8-11b), without use of a rappel sling—but this causes rope abrasion, makes it harder to retrieve the rope and, if done enough times, can kill the tree.

If your anchor is a rock feature or bolts or pitons, always attach a sling to the anchor, then run the rappel rope through the sling. Never put the rope directly around the rock or through the eye of the bolt hanger or piton, because the friction may make it impossible to pull the rope back down from below. Some climbers prefer to use two slings instead of one for added security. If you normally carry only sewn runners (which cannot be untied), you may want to bring along some $^{9}/_{16}$-inch webbing to cut and tie as needed for rappel slings.

On popular climbs, you will find established rappel anchors encircled with the slings that must be left behind when a rappel rope is retrieved. Some of the older slings will feel dry and less supple. It's a good idea to cut out a couple of the oldest slings and add a new one before running your rappel rope around them. If you are using



Fig. 8–12. The most common method of attaching the rappel rope to multiple anchors, with a separate sling attached to each of two anchors and meeting at the rappel rope: a, a narrow angle between slings is best; b, the angle between slings is too wide.

more than one sling, try to use the same length to help distribute the load.

When using two anchors to support the rappel, the most common method is to run a separate sling from each anchor, with the slings meeting at the rappel rope. Generally try to adjust the slings so the force is the same on each anchor. For the strongest setup, keep a narrow angle between the two slings (fig. 8-12). (You can also use just a single sling run through the two anchors, employing either self-equalization or the triangle method. Both are described in Chapter 7.)

You can help to avoid binding and abrasion of the rappel rope by making sure the point of connection between the rappel sling and the rope is away from the rock (fig. 8-13).

You can use a tiny piece of rappel hardware known as a descending ring to help reduce rope wear and make retrieval easier. It's simply a metal ring, 1$^1/_2$ inches or so in diameter. Thread the rappel sling through the ring before tying the sling.



Fig. 8–13. The point of connection between the rappel sling and the rappel rope: a, poor—rope binds and abrades against rock; b, better; c, best.

Then thread the rappel rope through the ring until you reach the rope's midpoint (fig. 8-14). When you pull the rope down later, it slides more easily through the descending ring than it would directly over the sling, which also can be weakened by rope friction.

The descending ring, however, does add another possible point of failure. Newer rings are continuous non-welded designs, much better than the welded type, which cannot be trusted. Some

Fig. 8–14. Rappel rope through descending ring

climbers insist on two rings, even if both are non-welded. An alternative is a single ring, backed up by a non-weight-bearing sling from the anchor through the rope, ready to hold the rope in case the ring fails.

Throwing down the rope

After the rappel rope is looped at its midpoint through an anchor, it's time to get the rope ready to toss down the rappel route.

Beginning from the rappel sling, coil each half of the rope separately into two butterfly coils. You'll end up with four butterfly coils, two on each side of the anchor. Throw the coils out and down the route, one at a time. Start on one side of the anchor by tossing the coil nearest the anchor, then the rope-end coil. Repeat for the other half of the rope (fig. 8-15). This sequence reduces rope snags and tangling. Before tossing, have another climber hold onto the rope near the anchor to make sure your tosses won't cause the rope to pull through the anchor. (Commercial rope bags are available which make it easier to carry ropes and to keep them clean and tangle-free, and rope-tossing is usually easier if you are using a rope bag.)

You won't always end up with a perfect toss, with the rope hanging straight down the rappel route. If you end up with tangles, hangups, or bunching, it's usually best to pull it back up, re-coil, and toss again. But sometimes it's just as well to work with what you've got. For instance, in a high wind, you're not likely to get a perfect toss. So just rappel down to the first problem, recoil the strands below that point, toss again, and continue the rappel.

Shout "Rope!" before you throw the rope down a rappel route. Some climbers shout the word two times, to give anyone below a little time to respond or to watch out for the rope. Others shout just once, but wait for a moment for any response. Be sure you're attached to an anchor as you stand at the edge of the route to toss the rope.



Fig. 8–15. Throwing down the rope

RAPPEL TECHNIQUE

In preparing to rappel, you will go through a sequence of establishing the anchor, attaching the rope to the anchor, throwing the rope down, and hooking yourself into the rappel system. At this point, you are facing the anchor, your back to the descent route, ready to head down the rope. Here's how to do it.

Start with a final check of the entire system: seat harness, rappel hardware, attachment to the rope, and anchor. Then, unless you're the last to rappel, wait while a partner checks your entire system. Pay special attention to the brake system: it's not set up backward, is it, as if you were rappelling uphill? Are the gates of carabiner pairs opposed correctly? Are locking carabiners securely closed? If another climber rappels before you, don't let the rappel begin until you've thoroughly checked out the setup.

GETTING STARTED

Now comes the most nerve-wracking part of most rappels. To gain stability, your legs must be nearly perpendicular to the slope. Therefore, at the very brink of a precipice, you're required to lean outward (fig. 8-16). In some cases you may be able to ease the transition by climbing down several feet before leaning out and putting your full weight on the rope to start the rappel (fig. 8-17).

With the carabiner brake or other mechanical systems, you may be able to sit on the edge of the



Fig. 8–16. Starting rappel from a high anchor



Fig. 8–17. Climbing below a low anchor before starting rappel



rappel ledge and wiggle gently off, simultaneously turning inward to face the slope. This technique is particularly useful when starting the rappel above an overhang (fig. 8-18).

POSITION, SPEED, AND MOVEMENT

As you move downward, your position should be something like this: feet apart, knees flexed, body at a comfortable angle to the slope, and facing a little toward the braking hand for a view of the route. The most common beginners' mistakes are keeping the feet together and failing to lean back far enough. (Some go to the other extreme and lean too far back, bringing the chance of tipping over.)

Move slowly and steadily, with no bounces or leaps. Higher speeds put more heat and stress on the rappel system, and it's especially important to



Fig. 8–18. Sitting down on ledge and squirming off to get started

go slowly on any questionable anchor. If you have to stop quickly while moving fast down the rope, the anchor comes under a great deal of additional force. Use extreme caution rappelling a face with loose or rotten rock. The danger here is that rock can be knocked loose and hit you or chop the rope.

Overhangs on the route can be a problem. It's easy to end up swinging into the face below the overhang and banging your hands and feet. There also is the danger of getting the brake system jammed on the lip of the overhang. One way to help get past that difficult transition from moving down against the rock wall to hanging below the overhang is to bend your knees sharply while your feet are at the edge of the overhang, then quickly drop three or four feet. This stresses the rappel system, of course, but it helps reduce both the chance of swinging into the face below and of jamming the brake on the lip.



Below an overhang, you will be dangling free on the rope. Assume a sitting position, hold yourself upright with the guiding hand on the rope above and continue steadily downward. Don't be surprised if you spin as twists in the rope unwind.

Sometimes, in order to reach the next rappel spot, you'll have to move at an angle to the fall line, walking yourself to one side instead of moving straight down. Be careful you don't lose your footing here. If you do, you will swing on the rappel rope back toward the fall line in what could be a nasty pendulum fall. And it could leave you in a position you can't recover from without climbing back up the rope with prusik slings or ascender devices.

POTENTIAL PROBLEMS

Shirttails, hair, chinstraps from a hard hat, and just about anything else have the potential to get pulled into the braking system. Keep a knife handy in case you have to cut foreign material out of the system.

If you run across a tangled or jammed rope on the way down, fix it while you're still above the problem. Stop at the last convenient ledge above the area, or stop with a leg wrap (explained in the next section). Pull the rope up, correct the problem, then throw it down again. Sometimes there's a simple solution. For instance, rappelling down blank slabs, you can often just shake out tangles as they are encountered.

STOPPING IN MID-RAPPEL

If it's ever necessary to stop partway down a rappel, wrap the rope two or three times around one leg (fig. 8-19a). The friction around your leg, increased by the weight of the hanging rope, is usually enough to hold you and to free your hands. Keep a braking hand on the rope until the wraps are completed and tested with your weight. Make the wraps tight, or you could end up a foot or two



Fig. 8–19. Stopping in mid-rappel: a, with rope wrapped around leg; b, with a carabiner brake or other mechanical rappel system.

lower than you intended as you put weight on the wraps and they tighten.

With the carabiner brake or other mechanical rappel system, an alternative method is to pass the rope around your waist, and tie two or three half-hitches around the rappel rope above the brake system (fig. 8-19b). This can be released easily when you're ready to continue the rappel.

MULTIPLE RAPPELS

A descent route often involves a series of rappels. These multiple rappels, especially in alpine terrain, present special problems and require maximum efficiency to keep the party on the move.

The trickiest is a rappel into the unknown, down a route you're not familiar with. Avoid this kind of multiple rappel. If you cannot, take the time to check out the possible rappel lines as carefully as time and the terrain permit. Sometimes you can find a photo of the route before you leave on the climb and bring it with you. Keep in mind that the first couple of rappels down an unfamiliar route may commit you to it all the way, for better or for worse.

If you can't see to the bottom of an unfamiliar rappel pitch, the first person down has got to be prepared to climb back up in case the rappel leads nowhere. This rappeller should carry prusik slings or mechanical ascenders for going up the rope. As additional preparation, the rappeller can tie both strands of the rappel rope to the anchor with figure-8 knots before starting the rappel. This secures the strands so the rappeller can climb up either strand if necessary. The next rappeller unties the knots before heading down.

Rappelling down unfamiliar terrain brings an increased risk of getting the ropes hung up. You can minimize the problem by downclimbing as much of the route as possible, instead of rappelling. You might also consider doing rappels using just one rope, even if two ropes are available, because one rope is easier to retrieve and less likely to hang up than two.

Even though it's nice to gain the maximum distance from each rappel, don't bypass a good rappel spot even 40 feet or so from the end of the rope if there are doubts about finding a good place farther down.

As a party moves through a series of rappels, the first person down each pitch usually carries gear to use in setting up the next rappel (after tying into an anchor at the bottom and trying to find shelter from rockfall). Climbers can take turns being first and last, though it's best for beginners to be somewhere in the middle.

SAFETY BACKUPS

Climbers have several options to increase the safety of a rappel. The options are occasionally useful in specific situations or for helping a beginner gain confidence in rappelling.

Knots in the end of the rope: It's possible to rappel off the end of the rope if you're not paying attention. Some climbers put a knot in the end of each rope, or tie the ends together, to eliminate this danger. If you add knots, don't rely blindly on them to tell when you've reached the end of the rope. The knots might come untied, of course, and in any case you want to keep an eye on the end of the rope so you can plan where to stop. The knots themselves can cause a problem by jamming in the rock if you ever find it necessary to pull the rope back up to work on it.

Pulling on the rappel ropes: A person standing below a rappeller can easily control the rappeller's movement, or stop it altogether, by pulling down on the rappel ropes, putting friction on the brake system. To safeguard the rappeller with this method, the person at the bottom simply holds the rope strands loosely, ready to pull them tight the instant the rappeller has difficulty (fig. 8-20).

Top belay: The rappeller can also be protected by a belay from above with a separate rope. If the belayer uses a separate anchor, the rappeller is safe



Fig. 8–20. Rappel halted by climber below, who is pulling down on the ends of the rope.

from even a total failure of the rappel anchor. A top belay is recommended for all beginners, for climbers with minor injuries, and for the first person down on a suspect anchor. The belays are too time-consuming for routine use because they drastically increase a party's descent time.

Prusik backup: Some climbers like the security of a prusik or Bachmann knot while rappelling, sliding the knot along the rappel ropes as they descend. The knot is in place above the brake system, and the prusik loop is clipped to a carabiner linked to your seat harness. If the brake system fails and you start to drop, the pull causes the prusik knot to automatically grip the ropes and stop the fall (fig. 8-21).



Fig. 8–21. Prusik backup for a carabiner brake rappel system

Backing up your rappel with a prusik knot has its dangers. Be careful it doesn't lock up unexpectedly—once it's under tension it can be tough to get loose—and keep the loop short so you can reach it if it locks. There's also the opposite danger: that the prusik knot will fail to lock when it should, particularly if you forget to release your hold on the knot. The prusik also has the unfortunate potential to burn through during a sudden stop from a high-speed rappel. Remember that controlling the prusik requires the full-time use of your guiding hand, which then isn't available for balance or protection.

RETRIEVING THE RAPPEL ROPE

Successful rope retrieval after a rappel depends on some important steps even before the last rappeller starts down the rope. It takes just one frightening experience with a stuck rappel rope to guarantee that you'll always take these precautions.

If you're using two ropes for the rappel, they will be tied together near the anchor. It's critical that you know which rope to pull on from below. Pull the wrong one, and you'll be attempting the impossible task of pulling the knot through the rappel sling. In some parties, the last two rappellers say out loud which rope is to be pulled, as an aid to remembering which is which.

The last rappeller should take a good final look at the rope and the rappel sling to see that everything is in order and that the rope isn't about to catch on the rock or the sling. Before the last person starts down, a climber at the bottom can test the rope by pulling to check that it can be moved and to see that the connecting knot in a two-rope rappel can be pulled free of the edge.

With such a two-rope rappel, the last person who starts down may want to stop at the first convenient ledge and pull enough of the rope down so that the connecting knot is clear of the edge. This helps take some of the uncertainty out of the difficult business of recovering a long rappel rope. However, it also shortens one rope end, so be sure the rappeller still has enough rope to reach the bottom.

The last rappeller has the main responsibility for spotting any retrieval problems. This last person can get twists out of the rope by keeping one finger of the braking hand between the ropes throughout the descent. (The same purpose is served by splitting the two ropes through a carabiner on your harness, just uphill of the braking hand.)

With the last rappeller down, it's time to retrieve the rope. First take out any visible twists. Then give the rope a slow, steady pull. Other climbers should take shelter to stay out of the way of falling rope or rockfall. If you've taken all the right steps and luck is on your side, the rope will pull free.

A jammed rappel rope is among a climber's worst nightmares. If it hangs up, either before or after the end clears the anchor, try flipping the rope with whipping motions before trying to get it down with extreme pulling. If you can, move both left and right and try more flipping or pulling. If all else fails, it may be necessary to climb up and free the rope. Belay the climber if enough rope is available. As a final resort if the party can't proceed without the rope, a climber might decide to attempt the desperate and very dangerous tactic of ascending the stuck rope with prusik slings or mechanical ascenders.

After you've studied rappelling and tried it a few times, it will be easy to see why climbers approach the technique with a fair degree of caution. But it's one of the activities central to climbing, and if you know what you're doing, it works well.



◆ PART THREE ◆

ROCK CLIMBING

Sherpa climber rappelling on a crag with Ama Dablam in the background, Khumbu region, Nepal. Photo by Gordon Wiltsie

• 9 •

ROCK CLIMBING TECHNIQUE

Climbing is a joyous, instinctive activity. As children, we scurry up trees, garden walls, building facades, and anything else steep and enticing. Then we grow up. For some of us, however, the adult urge to climb finds a beautiful outlet in rock climbing.

It's an exciting activity you can go at in many different styles and many different settings. For many, the ultimate pleasure is scaling steep solid granite in an isolated alpine setting far from the city. For them, the crags close to home are only a practice ground to hone skills in preparation for an escape to the mountains. For others, the primary pleasure is the kinesthetic joy of moving on rock, executing the most difficult and gymnastic moves. Mastering the challenge of the rock may be more important than the setting, and a long alpine approach a nuisance rather than a pleasure. And there are those who treasure the whole range of rock-climbing experiences, from working out a single move in a difficult bouldering problem or training on an artificial climbing wall, to completing sustained challenging pitches on a towering rock wall or climbing short sections of rock during an alpine climb on a glaciated peak.

The joys of rock climbing are found in all these ways, and despite their differences, the skills and techniques are essentially the same.

PREPARATION

PHYSICAL CONDITIONING

Climbing is physically demanding, and if you don't have the needed strength, some climbs will be too difficult. However, many climbs are possible without an abundance of strength. To some extent, technique can compensate for a lack of strength, while extra strength can sometimes compensate for a deficiency of technique. Some climbs, especially at the higher end of the rating scale, demand a high degree of both strength and technique.

ATTITUDE

To climb rock well, you must have the desire. Rock climbing calls for a commitment of both mind and body, and making the necessary moves requires total concentration and complete confidence. This confidence can come by practicing with a top rope (belayed from above), which minimizes possible injury in case of a fall and allows you to safely attempt harder and harder moves, eventually finding the limits of your ability.

Confidence goes hand in hand with physical conditioning. If hand, arm, or leg strength is not sufficient, it doesn't matter that the mind is willing. Conversely, physical ability alone won't move you if your mind says no.

An equally important component of attitude is an awareness of safety. This includes knowing your limits, and knowing when and how to back off when you don't have the strength or technique for a given route on a given day.

GEAR

Footwear

Mountaineering boots are commonly used on alpine climbs of modest technical difficulty or where weather or conditions (such as presence of snow or ice) favor their use. Boots generally hold on larger edges quite well, but are less useful on tiny edges or for "smearing" on holds.

For more difficult rock climbs, there are shoes made specifically for rock climbing (fig. 9-1). For many routes, rock shoes are essential. They are generally superior for smearing, and often will edge quite well also.

Most rock shoes consist of a flexible upper, often made of soft leather or cordura and leather, and a smooth flexible rubber sole. In recent years, new rubber compounds have been developed to create "stickier" soles that provide greater friction between rock and sole, and have aided in success on increasingly difficult routes. Rock shoes should fit very snugly to allow maximum control and feel of the rock. Specialized rock shoes are now available that are especially well suited for certain types of climbing, such as edges, pockets, and friction.



Fig. 9–1. Rock shoes: a, all-around shoe; b, more specialized edging shoe; c, slipper.

Clothing

Clothing for rock climbing should be chosen for appropriateness to weather conditions and for freedom of movement. Some climbers prefer loosely fitting pants; others prefer body-hugging tights made of stretchy material such as Lycra. Some climbers find that knickers provide a desirable combination of freedom of movement and utility in an alpine environment. Remove jewelry and watches that can get caught in equipment or abraded on holds or in cracks.

Tape

Athletic tape can protect hands from abrasion against rock, especially when climbing difficult jam cracks. There are a number of different taping methods, but no matter what the method, the tape must stay securely in place and not begin to peel off part way up a pitch. The tape also must protect vulnerable areas, especially knuckles and the back of the hand, while allowing maximum freedom of hand movement (fig. 9-2). A common mistake is to wrap the tape too tightly.

Some taping methods leave most of the palm untaped to increase sensitivity to the rock. Tape can also be used to provide support and/or protection for finger joints that are easily overstressed by difficult rock climbing or vigorous training.



Fig. 9–2. Hand taped for climbing: back of hand and knuckles are protected; palm is mostly left open.

Chalk

Many climbers use gymnastic chalk to improve their grip, especially in hot sweaty weather. The chalk is usually carried in a chalk bag worn on the back of the harness or attached to a separate runner tied around the waist, so you can dip a hand in the chalk whenever you need it.

Some climbers feel that chalk detracts from the rock by leaving white smudges. They also argue that the chalk identifies the holds, robbing other climbers of the experience of finding the holds and figuring out the climbing sequence for themselves. A compromise solution used by some is colored chalk that blends in with the rock. Several colors are commercially available.

On frequently climbed pitches, sweat and chalk can leave holds slimy and difficult to use. Some climbers carry a small brush, such as a toothbrush, to clean the holds.

Other gear

Additional gear is covered in other chapters. This includes equipment that is less specific to rock climbing, such as ropes and harnesses, and the varieties of hardware specific to the skills of leading and placing protection.

BASIC CLIMBING TECHNIQUES

PRINCIPLES OF MOVEMENT

Climbing with the feet

Pay attention to footwork and balance and you'll reduce the need to rely on arm and hand strength.

Stand erect over your feet and fight the tendency to lean in and hug the rock. On very steep rock, however, pressing the hips close to the rock can help push body weight directly down onto small footholds.

When possible, keep arms outstretched to avoid hanging on bent arms, which is very tiring. As you raise your feet to the next foothold, try to keep your arms straight, avoiding the tendency to use them to haul yourself from one hold to the next. Legs are much stronger than arms. Let the legs lift the body.

Three-point suspension

In this elementary approach, you move one hand or foot at a time while the other three limbs remain stationary (fig. 9-3). Be sure you're in balance over your feet before releasing a handhold to reach for the next one. This is an especially useful approach when the rock may be unsound, because it allows you to balance securely on three



Fig. 9–3. Three-point suspension: hands and right foot provide secure stance; left foot is moved to a higher hold.

holds while testing the next one.

Know where your center of gravity is. The optimal position will vary, but it's often useful to keep a low center of gravity, with weight directly over the feet. Move your center of gravity over a new foothold before committing weight to it. Only when your body is in balance over the new hold should you transfer weight onto it.

As you try more difficult climbs, you'll learn moves that don't adhere to the principle of three-point suspension. There may be only one or two sound holds and body position will be used to maintain a delicate balance over those holds. For example, a hand or foot may be positioned over a non-existent hold, or hips may be thrust in one direction, to counterbalance other parts of the body.



Fig. 9–4. "Resting" on an outstretched arm

CONSERVING ENERGY

Plan a move before trying to execute it. Move smoothly and deliberately, without wasted motion. Strive for fluidity, as if dancing a ballet with the rock, to conserve both time and energy.

Once you begin to step up on a foothold, transfer all your weight and complete the move. Avoid hanging with bent arms and bent knees in an awkward and tiring position while deciding what to do next.

Look for natural resting places such as ledges or secure footholds. If a no-hands rest isn't possible, try for a stance that uses as natural a body position as possible, and that requires the least amount of upper body strength.

If you must hang on handholds, the least tiring way is to hang on straight arms rather than bent arms (fig. 9-4). Do this either by lowering your center of gravity (bend knees, even squat) or by leaning out, away from the rock. Always maximize the proportion of weight being supported by the feet rather than the arms. It also helps to hang your arms down and shake them out, allowing a brief rest and return of circulation to stressed muscles.

USE OF HOLDS

Selection

In general, select holds based on solidness, convenience, and size. A visual inspection will often tell all you need to know. But if you doubt the soundness of a hold, test it with a kick, or with a blow from the heel of the hand. You can also push or pull on it. Keep alert to the consequences if the hold fails during testing: be sure it won't fall on people below, and be sure your stance is secure so you yourself won't fall. Remember that the hold must be useful in the context of the route. A large firm hold is useless if it leads away from the planned route and puts you into a position where you can't move to the next hold. A smaller but more conveniently placed hold may be a better choice.

Footholds should be comfortably spaced whenever possible. High steps are strenuous and make balance awkward, while steps close together waste energy without providing much upward progress.

Handholds at about head height provide a good stance and often are not as fatiguing as handholds above the head. They also let you lean away from the rock to view other potential hand- and footholds. Often, however, you won't have much choice in the matter, because the nature and difficulty of the rock may dictate where the holds are.

Footholds

Climbers use most footholds by employing one of two techniques, edging or smearing. On many holds, either technique will work, and the one to use depends on your own preference and type of footwear. We'll take up a third technique, called the foot jam, in a later section.

In edging, the edge of the boot or rock shoe is placed over the hold (fig. 9-5a). You can use either the inside or outside edge, but the inside is usually preferred for greater ease and security. The ideal point of contact may vary, but generally it's between the ball of the foot and the end of the big toe. Keeping the heel higher than the toes provides greater precision, but lowering the heel is a more restful position. Using the actual toe of the boot or rock shoe ("toeing in") may be very tiring. With practice, you will become proficient using progressively smaller footholds.

In smearing, the foot points more uphill, with the sole "smeared" over the hold (fig. 9-5b). The technique of smearing works best with rock shoes or flexible boots. On lower-angle rock, you may not need an actual hold, but will only have to achieve enough friction between sole and rock. On steeper terrain, smear the front of the foot over a hold, and see how even tiny irregularities in the rock can provide significant friction and security.

Fatigue, often aggravated by anxiety, can lead to troublesome vibrations in the muscles of the leg, known as "sewing-machine leg." The best way to stop it is to try to relax your mind and to change leg position, either by moving on, lowering the heel, or straightening the leg.



Fig. 9–5. Footholds: a, edging; b, smearing.

In using footholds, optimize the direction of force on the hold. Flexing the ankle may increase the surface area of contact between sole and rock, giving maximum friction. Leaning away from the rock can create inward as well as downward force on the hold, increasing security.

Decide the best way to use a hold before you put your foot on it. Then maintain your position on the hold. Although it's sometimes necessary to reposition the foot into a better relationship to the hold, avoid thrashing and repeated repositioning to try to find something better. This wastes time and energy and may cause you to slip off altogether. On marginal footholds it may be mandatory to maintain the position exactly, as any movement or rotation could cause the foot to slip off. Keeping your foot in position can take a lot of concentration and skill as you move up on the hold and step above with the other foot.

With the large footholds called buckets, place only as much of your foot as necessary on the hold (fig. 9-6). Putting your foot too far into the bucket can sometimes force the lower leg outward, making for an out-of-balance stance.

Generally avoid using your knees, which are susceptible to injury and offer little stability. Nevertheless, even experienced climbers occasionally use a knee to avoid an especially high or awkward step. The main considerations are to avoid injury from pebbles and sharp crystals, and to avoid becoming trapped on your knees, unable to rise to your feet. This can be a big problem if you find yourself beneath an overhanging bulge with insufficient space to easily stand up.



Fig. 9–6. Bucket hold: a, correct; b, incorrect.

Handholds

You can use handholds for balance, to help raise yourself by pulling up on the hold, or to provide various forms of counterpressure.

Handholds (fig. 9-7) offer maximum security when all fingers are used. Ways to use fingers aren't always obvious on small holds. For example, with fingers holding onto a tiny ledge, you may be able to use the thumb in opposition on a minor rugosity (fig. 9-7a). On a very narrow hold or a small pocket in the rock, you can stack fingers on top of each other to increase pressure on the hold (fig. 9-7b).

The most common handhold is the cling hold (fig. 9-7c). Large cling holds allow the entire hand to be cupped over the hold, while smaller variations (fig. 9-7e) may allow room for only the fingertips. Keeping fingers close together provides a stronger grip on the hold. If the hold is not large enough for all fingers to be placed on it, at least curl the other ones, which permits the fingers in use to get the most force from the muscle/tendon system (fig. 9-7f). When using cling holds, be aware that certain hand configurations put extreme stress on the fingers and may lead to injury (fig. 9-7e). (Other types of handholds will be discussed later in this chapter.)

DOWNPRESSURE

For this technique, place the finger tips, palm, side or heel of your hand on the hold and press down (fig. 9-8a). Pressing down with a thumb can



Fig. 9–7. Handholds: a, thumb used in opposition to other fingers; b, stacking fingers to apply greater pressure on a small hold; c, large cling hold; d, open grip. Keeping distal finger joints flexed puts less stress on joints and tendons. e, Cling grip on small hold. Extension of distal finger joints is more stressful and is more likely to cause injury than the open grip. f, Pocket grip: useful for small pockets only large enough to admit a single digit. Keeping other fingers curled helps get the most force out of the muscle-tendon system, but stresses the finger and may cause injury.

be useful on very small holds.

Holds are often used as cling holds from below, then as downpressure holds as you move above them. Downpressure holds may be used by themselves or in combination with other holds (fig. 9-8b), such as in counterforce with a lieback hold, or as part of a stemming move. With your arm extended and elbow locked, you can balance one-handed on a downpressure hold as you move the other hand to the next hold.



Fig. 9–8. Downpressure: a, using heel and palm of hand; b, used in combination with other holds.

MANTEL

The mantel is a very specific use of the downpressure technique. It lets you use hand downpressure to permit your feet to get up onto the same hold as your hands when no useful handholds are available higher.

For the classic mantel (fig. 9-9), place both hands flat on a ledge at about chest height, palms down, with the fingers of each hand pointing toward the other hand. Then raise your body up onto stiffened arms. This will be easier if you can first walk your feet a ways up the rock, or if you can spring up from a foothold. Then lift one foot up onto the ledge and stand up.

This basic mantel, however, isn't always



Fig. 9–9. Mantel: the climber turns his hand with the fingers pointed down to make use of the natural shape of the ledge, then reaches up to use a face hold.

possible, because a ledge will often be higher or smaller or steeper than you might wish. If the ledge is narrow, you may be able to use the heel of your hand, with the fingers pointed down. If the ledge is over your head, you'll use it first as a cling hold, and then convert to a downpressure hold as you move upward. If the ledge isn't big enough for both hands, you'll mantel on just one arm while the other hand makes use of any available hold, or perhaps just balances against the rock (fig. 9-10). Don't forget to leave room for your foot.

Avoid using knees on a mantel because it may be difficult to get off your knees and back on your feet, especially if the rock above is steep or overhanging. Sometimes in mid-mantel you'll be able to reach up to a handhold to help as you begin standing up.



Fig. 9–10. Manteling with one hand while using a face hold with the other



COUNTERFORCE

Counterforce is the use of pressure in opposing directions to help keep you in place. For instance, with both hands in a vertical crack, you can create outward pressure by pulling in opposite directions on the sides of the crack—a pulling-apart action (fig. 9-11a). Or you can create inward pressure by pulling in on widely spaced holds—a pulling-together action—or by pressing in on both sides of a sharp ridge. You can also use the hands in counterforce to the feet (fig. 9-11b). Counterforce plays a part in many of the climbing maneuvers described in this chapter.



Fig. 9–11. Counterforce: a, outward pressure; b, hands in counterforce to feet.



Fig. 9–12. Undercling: converting from a pinch grip (a) to an undercling (b).

UNDERCLING

In the undercling, the hands (palms up) push up beneath a lip of rock while the body leans out and the feet push against rock (fig. 9-12). The arms pull while the feet push, creating a counterforce. Try to keep your arms extended. Both hands can undercling at the same time, or one hand can undercling while the other uses a different type of hold.

An undercling hold may have multiple uses. For example, you can hold the bottom edge of a rock flake in a pinch grip from below, then convert to an undercling as you move up to the flake.





STEMMING

Stemming is a valuable counterforce technique that lets you support yourself between two spots on the rock that might be of little or no use alone. It often provides a method of climbing steep rock where no hold is apparent, simply by pressing in opposing directions with the feet or with a hand and a foot.

The classic use of stemming (also called bridging) is in climbing a rock chimney. It also comes into play in climbing dihedrals, where two walls meet in approximately a right-angled inside corner. One foot presses against one wall of the chimney or dihedral, while the other foot or an opposing hand pushes against the other wall (fig. 9-13a).

Stemming may also open an avenue of ascent on a steep face, where you can press one foot against a slight protrusion, while the other foot or a hand gives opposing pressure against another wrinkle in the rock (fig. 9-13b). When stemming between widely spaced holds on a steep face, be careful that your body doesn't rotate away from the



Fig. 9–13. Stemming: a, across a chimney; b, on a steep face.



Fig. 9–14. The barn door effect: a, the climber is balanced over two footholds with the left hand on a hold up and to the side. When the right hand is removed from the hold, the climber can no longer hold herself into the rock, creating the "barn door" effect, b, with the climber swinging away from the rock.



Two methods of avoiding the barn door effect: c, the climber moves the right foot to the hold where the left was to keep her weight more centered under the secure left handhold; d, the climber flags the left foot behind the right. Both techniques allow the climber to release the right hand to reach up to a new hold.

rock the second you release a hand to reach for a new hold (fig. 9-14b). Several methods can be used to avoid the barn-door effect. Sometimes a strong stem against the foot below the hand being moved is effective. Other times centering your weight over the foot below the stationary hand is more helpful (fig. 9-14c). One method is to try rearranging the body position using a counterbalance technique such as flagging one leg behind the other (fig. 9-14d).

LIEBACK

The classic lieback technique, another form of counterforce, uses hands pulling and feet pushing in opposition as the climber moves upward in shuffling movements (fig. 9-15a). It's used to climb a crack in a corner, or a crack with one edge offset beyond the other, or along the edge of a flake. Grasp one edge of the crack with both hands and lean back and to the side on straightened arms. Push your feet against the opposite wall of the crack. Then get a move on. It's a strenuous technique, and it's best to move as quickly and efficiently as possible.

Keep arms extended to minimize stress on tensed muscles. The right relationship of hands and feet will vary, but it becomes easier to determine with practice. In general, keep your feet high enough to maintain friction on the rock, unless a foothold is available. But the higher you bring your feet, the more strenuous the lieback becomes.

The lieback has variations. You can lieback on a single handhold in combination with other holds, or use one hand and foot in a lieback while utilizing face holds for the opposite hand and foot (fig. 9-15b).



Fig. 9–15. Lieback: a, a classic lieback; b, combining a lieback (right hand and foot) with face holds (left hand and foot).

JAMMING

The technique of jamming consists of wedging parts of the body, such as hands or feet, securely enough into a crack to bear weight. Jamming isn't as instinctive or natural-feeling as many other climbing techniques, but it works. It's the principal technique for working your way up the cracks that constitute a big part of rock climbing.

The basic procedure is to insert part of a hand or foot, usually just above a narrower part of the crack. Jams are usually locked by twisting (torquing) so the hand or foot is wedged against both sides of the crack.

Jamming can be used by itself, with both feet and hands utilizing jams, or in combination with other types of holds. As you move up on a jam handhold, you can maintain the jammed position but use it almost like a downpressure hold.

Cracks vary a great deal in size and configuration. The descriptions of jams that follow are just some basic techniques, with a lot of room remaining for creativity and ingenuity.

Finger jams

Finger jams make it possible to climb some of the narrowest cracks, where you may only be able to insert one or more fingers, or perhaps just the finger tips. Finger jams are commonly done with the thumbs down. Slip fingers into the crack and twist the hand to lock the fingers in place (fig. 9-16a). You get added strength by stacking fingers and also by pressing the thumb against the index finger in a ring jam (fig. 9-16b).

In slightly wider cracks, you can try a thumb lock. Place the up-pointing thumb in the crack, the



Fig. 9–16. Finger jams: a, thumb-down jam; b, ring jam; c, thumb lock; d, pinkie jam; e, jamming heel of hand as well as finger; f, using counterpressure with thumb.

pad against one side of the crack and the knuckle against the other. Slide the tip of the index finger tightly down over the first joint of the thumb to create the lock (fig. 9-16c).

Here are two other variations on the finger jam, done with the thumbs up (fig. 9-16d,e). You can put the little finger in a crack and stack the other fingers on top (finger tips down, nails up) for a "pinkie jam." In slightly larger cracks, you may be able to wedge the heel of the hand and the smaller fingers into a crack that isn't quite wide enough for a full hand jam. The weight here is borne by the heel of the hand.

For another variation, you can use counterpressure of thumb pushing against one side of the crack, fingers pushing against the other (fig. 9-16f).

Hand jams

With a wider crack, you'll gain the luxury of inserting your entire hand, cupping it as needed to provide adequate expansion against the walls of the crack (fig. 9-17a). To increase pressure against the walls, you'll sometimes tuck your thumb across the palm, especially in wider cracks (fig. 9-17b). You can often improve the hold by bending your wrist so the hand points into the crack rather than straight up and down.

The hand jam is done either thumbs up or thumbs down. Thumbs up often is easiest and most comfortable for a vertical crack, and it works especially well when the hand is relatively low. The thumbs-up configuration is most secure when the body leans to the same side as the hand that is jammed.

The thumbs-down technique may allow a more secure reach to a jam high above your head, because the hand can be twisted for better adhesion, and you can lean in any direction off this jam (fig. 9-17c). Climbers use a combination of thumbs up and thumbs down, especially in diagonal cracks where it's often useful to jam the upper hand thumb down and the lower hand thumb up (fig. 9-17d).

With both finger and hand jams, keep alert to the effect of your elbow and body position on the security of the hold. As you move up, you may have to rotate your shoulder or trunk to keep sufficient torque and downward pressure to maintain the jam. Direction of force should be pulling



Fig. 9–17. Hand jams: a, thumb-up jam; b, with thumb tucked across palm; c, thumb-down jam; d, combining thumb-down and thumb-up jams in a diagonal crack.

down, and not out of the crack.

In dealing with hand jams, you'll run across variants at both ends of the size scale: thinner cracks that won't admit the entire hand but are larger than finger cracks, and wider cracks that aren't quite large enough for a fist jam but require extra hand-twisting to create enough expansion for a secure jam. The size of your hand is a major factor in determining the appropriate technique and the degree of difficulty for any particular crack.

Fist jams

In a crack that's too wide for a hand jam, you can insert your fist (fig. 9-18). The thumb may be inside or outside the fist, depending on which provides the best fit. Your palm may face the back of the crack, the front, or either side. Flexing the muscles in the fist can expand the fist slightly to help fit the crack. Fist jams are often painful, but can be very useful. For the most secure hold, try to find a constriction in the crack that you can jam your fist above.



Fig. 9–18. Fist jam: three different positions



Fig. 9–19. Toe jams: a, jamming in a crack; b, smearing in a corner.

Toe jams

You can wedge your toe into a crack by turning your foot sideways—usually with the inside ankle up—and inserting the toe in the crack, then twisting the foot to jam it (fig. 9-19a). You can also wedge the toe into a steep inside corner with a smearing technique, keeping the heel lower than the toe and putting pressure down and in to keep the toe in place (fig. 9-19b).

Foot jams

If the crack is wide enough, jam more of the toe or even the entire foot into the crack. As with the toe jam, insert the foot sideways with the sole facing the side of the crack, then twist to jam (fig. 9-20a). Avoid twisting the foot so securely that it gets stuck, leaving you open to serious injury in case of a fall.

In even wider cracks, you can jam the foot diagonally or heel-to-toe (fig. 9-20b).



Fig. 9–20. Foot jams: a, foot jam in a crack; b, heel and toe jam.

Body jams

Climbers have figured out ways to jam arms, shoulders, hips, knees, and just about anything else into cracks that are too large for fist jams but too small to accommodate the entire body. These are the awkward off-width cracks, so called because they aren't the right width for any of the more standard jamming techniques. Details of off-width climbing are outlined later in this chapter.

COUNTERBALANCE

Counterbalance is not a specific type of move, but rather a principle that can be used in all kinds of climbing. It's the principle of distributing your body weight in a way that maintains your balance.

This means selecting holds that do the best job of keeping your body in balance. But it also sometimes means putting a hand or foot in a particular location, even if no hold is available, in order to provide counterbalance to the rest of the body. The hips and shoulders also come into play as you move them to provide counterbalance (fig. 9-21).



Fig. 9–21. Two examples of counterbalance: a, the left foot is extended to the side to provide counterbalance; b, the left foot is flagged behind the right for counterbalance.

LONG REACHES

What do you do when the next available handhold is a long reach away—or even out of reach?

The climber has several techniques available.

First, make the most of available holds, by using one or more of these tips: stand up on your toes; pull your body into the rock to achieve maximum extension of the body; use a foot for counterbalance to help in standing up completely on the other foot; move your foot higher on a sloped hold; move your foot more to the side that the next handhold is on. Additional tips: move your foot to the edge of a foothold for a traversing move; lean your body and hips out or to the side to allow a longer sideways reach; use a handhold for downpressure to allow maximum upward reach with the opposite hand. Sometimes a longer reach is possible by standing on the outside edge of your boot, which tends to turn your body somewhat sideways to the rock. And remember that the longest reach is possible with the hand that is opposite of the foot you're standing on.

Another option is to consider quick intermediate moves, using holds that are marginal but will be used just long enough to scamper up to the next good hold.

The last resort may be a dynamic move that could involve a lunge or simply a quick move before you lose your balance or grip. The time to grab the next higher handhold while making a dynamic move is at the "dead point"—at the apex of your arc of movement when the body is weightless for a fraction of a second before it begins to fall. Movement is most efficient at that point.

There's a built-in danger if a dynamic move fails: you're no longer in complete control and a fall is likely. Make a dynamic move only after calculating and accepting the consequences of failure. You should know beforehand that the protection is secure and that a fall onto the protection won't result in hitting a ledge or the ground or otherwise risking injury. Keep in mind that dynamic moves are for accomplished climbers, not for desperate novices.

EXCHANGING PLACEMENTS ON A SMALL HOLD

Sometimes you need to move one foot onto a small hold already occupied by the other foot, or one hand onto a hold being used by the other hand. Either move can be made several different ways.

To exchange a foot placement, you can make an intermediate move, using a poorer, even marginal hold to get the one foot off the good hold long enough for the other one to take it over. And there's the hop, in which you hop off the hold as you replace one foot with the other.

You can also try sharing the hold by matching feet, moving one foot to the very edge of the hold to make enough room for the other. Another technique is the crossover, in which you cross one foot in back of the other to occupy the far side of the hold (fig. 9-22).



Fig. 9–22. Foot crossing to change feet on a small hold

To trade hands, you can make an intermediate move, much as you might in exchanging feet. You have the option to match hands, placing both hands on the same hold. If space is limited, you can also try picking up the fingers of one hand, one finger at a time, and replacing them with the fingers of the other hand. The crossover technique also is occasionally useful.

PUTTING IT ALL TOGETHER

Once you've learned the basic climbing techniques, you are ready to begin combining them in ways that make different types of climbs possible.

You'll soon discover the value of planning before you start up a new pitch. Always plan several moves ahead to help you conserve energy and stay on route. Identify and examine difficult sections before you get to them, make a plan, then move through them quickly. Look ahead for good rest spots.

Many climbs require a variety of techniques, rather than pure jamming, or pure stemming, or pure anything. You'll often use one technique with one hand, or one side of the body, and another technique with the other. You can be jamming with one side of the body as you use face holds with the other. A single pitch may require different techniques in sequence: a jam followed by a lieback, then face climbing followed by a mantel onto what had been a cling hold.

Basic techniques are combined in various ways for climbing faces, slabs, cracks, dihedrals, chimneys, and overhangs.



Fig. 9–23. Face climbing

FACE CLIMBING

In some ways, face climbing is the most natural type of climbing (fig. 9-23). You move up a series of handholds and footholds, somewhat like climbing a ladder.

Remember that a single hold may be used in a variety of ways, by feet and hands. What initially appears to be a good cling hold may allow a lieback, a mantel, or a stemming move. Be creative.

SLAB CLIMBING

Also referred to as friction climbing, slab climbing (fig. 9-24) requires liberal use of smearing moves. Balance and footwork are the keys to success, and smearing with the feet is the primary technique.

Remember to flex the ankle (lowering the heel) and keep weight directly over the ball of the foot for maximum friction between rock and sole. Avoid leaning into the slope with your body, which pushes your feet away from the rock. Instead, keep weight over the feet, bending at the waist to allow your hands to touch the rock, and pushing hips and buttocks away.



Fig. 9–24. Slab climbing

Take short steps to maintain balance with weight over the feet. Look for the small edges, rough spots, or changes in angle that provide the best foot placements. On the toughest slabs, footholds may be so subtle you'll have to feel with your hand or foot to find the roughest surface.

Don't forget that other techniques can be useful on slabs. Face holds may be intermittently available, as well as cracks. You can use downpressure on small edges or irregularities, with the finger tips, thumb, or heel of your hand. A lieback with one hand might be possible using tiny edges. Look for an opportunity for stemming, which could mean a chance to rest.

CLIMBING CRACKS AND DIHEDRALS

Cracks may be climbed with a pure jamming technique or by a combination of techniques. A very potent combination is to jam with one side of the body and use face holds with the other (fig. 9-25).

Cracks also may be climbed with a pure lieback technique or by liebacking with one arm in combination with face holds for the other hand (fig. 9-26). This may result in a kind of stemming action.

Dihedrals (inside corners) may be climbed by pure stemming. You can also use various combinations, such as hands jammed in a crack splitting the dihedral combined with feet stemming on opposite sides of the dihedral (fig. 9-27). You may even use



Fig. 9–25. Combining jamming with face climbing

classic chimney technique, described later in this chapter.

Useful edges or other holds may be found hidden within cracks—on the sides or even at the back of wide cracks. Remember that horizontal cracks can also be used as cling holds.

Off-width cracks

Cracks that are too wide for standard jamming, but too narrow to admit the entire body for chimneying, call for specialized off-width technique. You stand sideways to the crack, and one full side of your body goes into the off-width.

When confronted by an off-width, first decide which side of your body to put inside the crack. This depends on several things, such as holds in the crack or on the face, and the lean, flare, and offset of the crack.



Fig. 9–26. Liebacking combined with face holds



Fig. 9–27. Climbing a dihedral using stemming and jamming

After you've settled on which side to use, the inside leg goes inside the crack and forms a leg bar, usually with counterpressure between foot and knee or foot and hip. This foot is often placed in a heel-toe jam.

The outside foot also is inside the crack in a heel-toe jam. Try to keep the heel above the toe (for better friction) and turned into the crack (to allow the knee to turn out).



Fig. 9–28. Off-width technique: a, arm bar; b, arm lock.

As for the arms, a primary body-jam technique is the arm bar (fig. 9-28a). With the body sideways to the crack, insert the arm fully into the crack, with the elbow and the back of the upper arm on one side of the crack giving counterpressure to the heel of the hand on the other side. Get the shoulder in as far as possible, and have the arm lock extend diagonally down from the shoulder.

In a variation, the arm lock, fold the arm back at the elbow and press the palm against the opposite side in counterforce to the shoulder (fig. 9-28b).

The outside arm is used to give downpressure to help hold you in the crack, or is brought across the front of the chest and pushed against the opposite side of the crack, elbow out.

You're now wedged securely in the crack. To climb, move the outside leg upward to establish a higher heel-toe jam. When this jam is set, stand up on it. Then re-establish the inside leg bar and arm bar (or arm lock), and reposition the outside arm. This again wedges the body in the crack. You're now ready to move the outside leg upward again to establish a yet higher heel-toe jam. Continue repeating this procedure (fig. 9-29).

You may use your outside foot occasionally on face holds, but watch out for the tendency for these outside footholds to pull you out of the crack.

CHIMNEY TECHNIQUE

A chimney is any crack big enough to climb inside, ranging in size from those that will barely admit the body (squeeze chimneys) to those the climber's body can barely span.

The basic principle is to span the chimney somehow with the body, using counterforce to keep from falling. Depending on the width of the crack, you will either face one side of the chimney, or face directly into or out of the chimney. The best body position and technique to use depends on the situation and on the size of the climber. Which direction you face may depend on what holds are available outide the chimney and on how you plan to climb out of it.



Fig. 9–29. Climbing an off-width crack

In squeeze chimneys, wedge your body in whatever way works best and squirm upward. Look for handholds on the outside edge or inside the chimney. Arm bars and arm locks may be useful. It's helpful, sometimes, to press the left foot and knee, for example, against opposite sides of the chimney. You might try stacking your feet in a T configuration, with one foot placed parallel to one side of the rock, while the other is placed perpendicular to it, jammed between the first foot and the opposite wall. Squeeze chimneys can be very strenuous, and the best approach here may be to look for an alternative way to climb that section.

In a crack that's somewhat wider than a squeeze chimney, you begin to have some room to maneuver (fig. 9-30a). You can then press your back and feet against one side of the chimney as your knees and hands push against the other side. You can move upward by squirming your way. Or try a sequence of wedging the upper body while raising the feet and knees, then wedging them and raising the upper body.

A wide chimney calls for stemming technique, with the climber facing directly into or out of the chimney (fig. 9-30b). Counterforce is between the right hand and foot on one side and the left hand and foot on the other. Press down as well as against the sides, especially if there are holds on the sides of the chimney. Ascend by alternately moving arms and legs, or by moving each leg, then each arm.

In a standard moderate-width chimney, perhaps 3 feet wide, you'll again face one wall of the chimney, your back to the other. For the upper body, your hands may push against one wall in counterforce to your back pressed against the other. Or the



Fig. 9–30. Chimney techniques: a, in a narrow chimney; b, in a wide chimney.

counterforce may be between hands on opposing walls. For the lower body, your feet may push against one wall in counterforce to your buttocks against the other. Or the counterforce may be between your two feet.

To climb this moderate-width chimney, use the following sequence (fig. 9-31): Start with your back toward one wall. Press one foot against each wall and one hand against each wall. Move upward by straightening your legs and then re-establishing hand positions. Immediately bring your back leg across to the same side as the forward leg. Then swing the forward leg across to the back position. You're now again in position to move upward by straightening your legs.

Beware of getting too far inside a chimney. Although psychologically it may feel more secure, you can get lodged deep inside and find it difficult to move back out. You have a better chance of finding useful hand- and footholds if you stay near the outside of the chimney.

Climbing deep inside the chimney also can make it harder to exit at the top. The transition from the top of the chimney to other types of climbing is often challenging and may require extra thought and creativity.

Chimney technique may be useful in places that don't look like classic chimneys. It can be used to climb dihedrals (fig. 9-32), or short wide sections of otherwise narrower cracks.

NEGOTIATING OVERHANGS AND ROOFS

Depending on the situation, overhangs and roofs require a variety of techniques such as manteling, face climbing, or crack climbing.

There are two important points to remember: maintain balance and conserve strength.



Fig. 9–31. Chimney techniques in a moderate-width chimney

To maintain balance, look for good footholds and make the most of them. This often means keeping feet high and hips low to help press weight against footholds (fig. 9-33). In some situations, it means pressing your hips into the rock, with back arched, to keep weight over the feet while poised under an overhang. While balanced over your feet beneath the overhang, locate the handholds you will use to move up and over the bulge. A cling hold, a jam, a lieback, or a combination of these may be the key.



To conserve strength, weight your feet as much as possible. Keep arms straight while raising the feet. When the feet are as high as possible, lift the body with your legs rather than pulling up on your arms. Avoid hanging on bent arms, as this will quickly exhaust arm strength. Move quickly through crux sections of the pitch to minimize the time spent in strenuous positions (fig. 9-34).

Occasionally you may need to raise up on your feet while making a dynamic reach (a lunge) to a handhold. Another trick is to throw one foot up



Fig. 9–32. Chimney techniques in a dihedral



Fig. 9–33. Climbing an overhanging route



Fig. 9–34. Climbing over a roof: a, the climber is poised under the roof with hips close to the rock; b, she leans out on an outstretched arm to locate a hold above the roof; c, she has both hands above the roof and feet are high, pushing against the rock; d, finally, she brings one foot up and begins to pull over the roof.

onto a ledge, perhaps hooking the heel on it while pushing with your other foot and pulling with your arms to swing up onto the top foot.

TRAVERSING

Traversing—going sideways across a section of rock instead of up or down—again calls for a catalog of climbing techniques (fig. 9-35). The main ones are side clings, liebacks, and stemming. And counterbalance is important when making a long sideways reach.

The climber usually faces into the rock, toes pointed away from each other. Hands and feet are commonly shuffled sideways, although exchanging one hand for the other, or one foot for the other, on a single hold can be very useful. You may occasionally cross one foot behind the other to reach the next hold, or cross one hand over the other.

On a steep pitch it's very tiring to hold yourself into the rock on bent arms. When possible, lean out from the rock on straight arms. This conserves arm strength, and it gives a better view of where you're going.

A specialized type of traverse is the hand traverse, used when footholds are marginal or nonexistent (fig. 9-36). The hands grip a series of holds or shuffle along an edge, while the feet provide a counterforce by pushing against the rock, as in a lieback or undercling. Keep the feet high and the center of gravity low so the feet are pushed into the rock. And once again, keep the arms straight to





Fig. 9–36. Hand traverse



Fig. 9–35. Traversing a steep face: a, lieback with one hand, leaning out to reach another hold with the other hand; b, climber twists body to take long sideways reach—an advanced technique.

conserve arm strength and to let the legs do as much of the work as possible.

EXITING ONTO LEDGES

As you approach a ledge, avoid the temptation to reach forward and pull yourself onto it. This may throw you off balance and also make it impossible to keep an eye on your footholds (fig. 9-37a).

Instead, continue to walk your feet up the rock, and then use downpressure with the hands near the edge of the ledge. You might do a classic mantel. Be careful not to exit onto the ledge on your knees and then find yourself beneath an overhang, unable to stand (fig. 9-37b).

DOWNCLIMBING

While you're learning lots of ways to climb upward, also allow some time to learn the valuable technique of downclimbing (fig. 9-38). Downclimbing at times is faster, safer, or easier than rappelling, such as when rappel anchors aren't readily available. Downclimbing provides a way to retreat when you find yourself off route or on a pitch where the rock above is more difficult than you care to attempt.

Downclimbing has its special difficulties, however, which helps explain why some climbers resist learning the skill. Holds are harder to see than when you're climbing upward—and holds on the steepest, most difficult sections are the most difficult to see, especially if the rock is undercut below a bulge or small roof. It's hard to test holds without committing to them, an unpleasant fact if you doubt the soundness of the rock. And unless you climbed up the same way, the terrain below is unknown, and you may not be able to anticipate the consequences of a fall.

For downclimbing on low-angle rock, face outward for the best visibility. Keep hands low and use downpressure holds whenever possible. Going down friction slabs, keep weight over your feet to maximize friction. It may help to keep your center



Fig. 9–37. Exiting onto a ledge: a, incorrect; b, correct.



Fig. 9–38. Downclimbing: a, facing out; b, facing sideways; c, facing in.

of gravity low, with knees well bent.

As the rock steepens, turn sideways, leaning away from the rock for better visibility. If the cliff gets even steeper, face into the rock. Keep hands low, and lean away from the rock to look for holds below.

SPECIAL DEMANDS OF ALPINE ROCK CLIMBING

GENERAL CONSIDERATIONS

When you take the rock-climbing skills you've learned during pleasant days on small nearby crags out into the mountains proper, some of the conditions of the game change. There are new things to keep in mind when it comes to alpine climbing which involves a mix of hiking, scrambling, routefinding, snow and ice climbing, and rock climbing.

First of all, you'll probably be climbing with a pack, a significant impediment to speed and performance. With a pack, it can be a challenge to climb rock several levels easier than what you lead comfortably on the crags. For a real test, try climbing a chimney or an off-width crack. Sometimes it's necessary to haul the pack up separately with a rope, and this again slows the climb.

Decisions about how much gear to take become extremely important as each extra pound cuts into speed and performance and, ironically, adds to the possibility that the extra gear may be needed to survive an unplanned bivouac or accident.

On the crags, you use light, flexible shoes specially designed for rock climbing. But on alpine climbs, heavy mountaineering boots are the usual footwear for approaches, for snow travel, and often for much or all of the climbing. As with carrying a pack, climbing in mountaineering boots adds to the challenge of otherwise moderate rock. If you decide to change to rock shoes for the more technical portions of a climb, you're stuck with packing the mountaineering boots. If you're wearing boots and crampons for hard snow or ice and encounter a short section of rock, you may have to ascend the rock in crampons, adding yet another dimension to the climb.

Use special care in testing holds on alpine climbs, where loose rocks may not have been discovered and discarded by previous climbers the way they are at popular crags. Unsound rock is common on alpine climbs because of the many different types and the constant weathering it receives. You may want to place protection even on rock that appears easy to climb. However, occasionally on low-angle loose rock, using the rope may be more hazardous than climbing unroped, because the rope can dislodge rocks onto climbers below.

Unpredictable weather, arduous approaches, high altitude, and routefinding problems all add to the commitment and challenge of alpine rock climbing.

SPEED AND SAFETY

A speedy ascent is sometimes an important part of safety on an alpine climb. On long routes, speed minimizes the risk of being caught by darkness. It provides extra time to deal with equipment breakdown, routefinding problems, injury, or illness. It lessens the length of exposure to rockfall, storms, or lightning.

Speed doesn't mean careless rushing. It means developing efficiency in such activities as testing holds, belaying, exchanging gear, and rope management. It means looking ahead at the route, formulating a plan, and moving smoothly ahead without thrashing over routefinding dilemmas.

As a team, climbing efficiently requires planning and practice, as well as development of a systematic approach to all basic activities. Moving efficiently over the rock saves a lot of time, promotes safety, and conserves energy for each member of a climbing team.

A light pack helps in completing a route quickly. Safety lies in having enough gear to do the climb and survive unexpected situations—not in carrying every piece of gear and shelter that might possibly come in handy.

The size of the climbing party and of the rope teams has an important bearing on speed. The more rope teams there are, the slower the party generally will move. However, rope teams of two are considerably more efficient than teams of three on an alpine route. Other things being equal, two rope teams of two can move much more quickly than a single team of three.

TRAINING FOR ROCK CLIMBING

Rock climbers need a fitness program tailored to their needs. Overall fitness is helpful, but general conditioning programs don't usually promote the forearm and finger strength needed by climbers.

TRAINING GOALS AND REGIMENS

A training program should be designed to develop and maintain strength, endurance, balance, and flexibility. Added benefits will be greater confidence and fluidity on the rock.

The energy required for muscular contraction is derived from three energy-producing systems (each of which produces adenosine triphosphate [ATP], the final common source of chemical energy for muscle).

The primary source of energy for sustained or repeated muscular contraction requires oxygen and is referred to as the aerobic system.

The other two systems do not utilize oxygen and are referred to as anaerobic. They are important when the demand for energy temporarily exceeds the capacity of the aerobic system, or during sudden muscular contractions demanding energy before the aerobic system can supply it.

Training should include use of all three of these energy-producing systems.

Be careful you don't hurt yourself while you train. Common causes of injury are overtraining, trying to increase strength too quickly, and failing to pay attention to early signs of overuse or acute injury, especially to tendons of the elbows and of the fingers.

Strength

Strength refers to the maximum force that can be exerted against a resistance. A practical example might be the heaviest weight you could lift a single time.

Developing strength is useful for individual moves or short sequences when maximum strength is required for a brief time. Maximum muscular effort requires use of the anaerobic energy systems. These can be trained using routines that alternate periods of intense muscular work, from seconds to less than 2 minutes, with periods of rest.

The best approach is progressive muscular overload exercises. This includes weight training with heavy loads and few repetitions, or other short-duration, near-maximal efforts, such as hanging from small holds for brief periods. A description of training regimens is beyond the scope of this chapter, but climbers can consult books and magazine articles devoted to strength training.

Endurance

Endurance is the ability to sustain muscular effort over time. Although crux sections of a pitch may require considerable absolute strength, climbing a full pitch, or more particularly a multipitch route, requires muscular endurance.

The primary energy system involved is aerobic, and the best training approach is lower-resistance, higher-repetition exercises than the ones used for strength training. You can adapt this approach to weight training, finger-board routines, or sustained bouldering.

Aerobic activities—such as jogging, bicycling, swimming, or rowing—help develop cardiovascular fitness, which aids in any sustained rock climbing effort. This is particularly true for alpine climbs, where the approach may be strenuous and where rapid progress up a long route can be essential.

Balance

Perhaps the best way to improve your balance is simply to climb. Try climbing exercises, such as moving up a slab without the use of hands, or working on difficult boulder problems that require balance. You can also devise other exercises, such as walking across a tightly stretched rope suspended above the ground. Many dancers take readily to climbing; dance lessons might improve both balance and flexibility.

Flexibility

Flexibility is essential for all rock climbing beyond an elementary level. Many books are available that describe stretching exercises to improve flexibility. They should be done regularly, like any training exercise. Take care to avoid injury.

Weight loss

You can increase your relative strength and endurance by losing excess weight, thereby decreasing the number of extra pounds you have to lift with your arms and legs. A lower body weight may enhance balance and flexibility as well.

USING AVAILABLE RESOURCES

Climbers can take advantage of natural resources to train specifically for the strength, endurance, and technique required in climbing.

Look for opportunities to climb on boulders at local crags or at developed climbing areas. Bouldering lets you practice close to the ground without needing a belay. Work on low-level traverses and on short but difficult problems.

Buildering is the same idea as bouldering, but using the sides of buildings instead of the sides of rocks. Beware of conflicts with authority.

Top-roped climbing is another training tool. In top roping, you are belayed so that any fall will result in only a short drop—just the distance the rope stretches when it takes your weight. Because you're safe, you can practice techniques and push the limits of your ability, increasing strength and confidence. You can try moves you wouldn't be willing to go for if you were leading a climb, belayed only from below and risking a leader fall.

SPECIALIZED EQUIPMENT

Climbers now have access to a growing catalog of manufactured climbing aids. They let you train whenever you want and tailor a fitness program to your own needs.

Artificial climbing walls are appearing both indoors and out, where you can boulder in the absence of readily available natural areas. The walls help develop both strength and technique, and they allow creation of specific problems to work on. These problems can even simulate a difficult sequence on an established natural route. Of course, indoor walls are especially welcome during bad weather.

Manufactured finger boards (fig. 9-39) have a selection of hand and finger holds to hang from or pull up on. Using a finger board improves upper body strength and also lets you concentrate on developing the finger strength needed to take advantage of small holds.



Fig. 9–39: Finger board

Other training tools have been developed and more are on the way. There are rope ladders and peg boards for improving upper body strength. There also are artificial cracks designed to improve strength and endurance with hands in specific configurations.

STYLE AND ETHICS

Climbing generates endless debate over which styles are fair and which are less than sporting, over which practices are harmful, and which are "none of your damn business." The terms "style" and "ethics" are sometimes used interchangably by climbers, but style usually refers to a person's mode of climbing, which is principally a personal decision. Ethics usually refers to issues where preservation of the rock itself, and thus the experience of other climbers, is at stake.

Climbers soon discover that getting to the end of the pitch or the top of the peak isn't the only goal—that it's also getting there in a way that feels right, that respects the rock, and that tests a person's skill and resolve as a climber. These are questions of style and ethics.

DIVERSITY OF STYLES

Styles change and attitudes evolve, but the core of the debate on climbing styles is about how to maintain the challenge of climber against rock and how to play the game in a way that fairly tests the climber.

Climbers adhering to traditional style prefer to climb each route strictly from the ground up, with no help from such aids as top ropes or preplaced protection. New routes are explored and protected only on the lead. After a fall, the climber returns to the start of the climb or at least to a no-hands resting place.

Climbers following the European-influenced sport-climbing style are more likely to find other techniques acceptable as well. This can include inspecting the route on rappel before trying to lead it from below. It can also mean cleaning the route and perhaps placing protection on rappel. Routes may be climbed with multiple falls, by resting on the rope while checking out the next move ("hangdogging"), or by rehearsing moves with the help of a top rope.

These sport-climbing techniques have made it possible to climb harder and harder routes. A particular climbing area may lend itself more to one style than another because of the type of rock, the difficulty of the routes, or the conventional style of the local climbers. In the world of climbing, there's room for a diversity of styles, and most climbers will experience a variety of them.

No matter what the style, a climber will work to eventually climb the route by putting no weight on the rope or on any piece of protection. The goal is to "redpoint" the route; that is, to eventually lead a complete no-falls ascent. Better yet is to "flash" the route, leading it all the way with no falls on the very first try. Best of all is to flash it "on sight"; that is, without prior inspection or knowledge.

ETHICS AND THE ROCK

The subject of ethics has to do with respecting the rock and every person's chance to use it. Unlike climbing style, ethics involves personal decisions that do affect the experience and the enjoyment of others. This includes the sticky question of the manner in which bolts are placed on a route. Are bolts placed on rappel different—less "ethical"—than bolts placed on the lead? Traditional climbers may argue that bolts placed while on rappel rob others of the chance to try the route from the ground up. But other climbers may say that placing the bolts gives a chance at a route that otherwise would be unclimbable.

Each area has its own tradition of what styles and ethics are acceptable, and visiting climbers should observe the local standards. It's not hard to find out what they are. The guidebook will say, the locals can tell you, and you can always just look around at what the other climbers are doing.

This book won't try to resolve issues of style and ethics. But there is general agreement on a couple of principles.

First of all, preservation of the rock is paramount. Chipping the rock to create new holds is almost universally condemned. And while bolt-protected routes are common in many areas, bolting should not be indiscriminate. In the mountains or other wilderness areas, away from concentrated centers of rock climbing, it's particularly important to preserve the environment for those who follow. If possible, stick to clean climbing, using only removable chocks for protection.

Secondly, it's almost never justified to add a bolt to an existing route. If you feel you can't safely climb the route as it is, don't try it. Exceptions may occur when a consensus of local climbers, usually including the person who first climbed the route, agree that another bolt should be placed to promote safety and enjoyment. There's rarely any objection if you replace an old bolt with a newer, stronger one or add a bolt at an established belay or rappel point.

COURTESY

Keep other climbers in mind when you're out climbing. If your party is moving up a multipitch route much slower than the people behind you, let them pass at a safe spot, such as a belay ledge.

Beware of tackling climbs that are beyond your abilities. You may prevent more capable climbers from enjoying the route. And if your inexperience gets you in trouble, you may end up dragging the other climbers into your rescue.

CLIMBING ACCESS

Access to many climbing areas is threatened and two issues are usually at stake. The people who own or manage the land are worried about liability for accidents and are concerned that climbers are defiling the environment.

As climbers, we can help by taking responsibility for our own actions. It's up to us to put in dependable anchors and otherwise promote safety—and to provide rescue services when they're needed, rather than expecting others to do it for us.

It's also up to us to leave areas in as natural a state as possible. Chalk, rappel runners, fixed protection, and litter can be eyesores. We can help by establishing rappel anchors that don't require leaving slings, using colored chalk that blends in with the rock, keeping bolt placements to a minimum, and removing all litter. These efforts can promote public acceptance of the sport and help maintain access to climbing areas.

◆ 10 ◆

LEADING AND PLACING PROTECTION

Climbers who have learned the basic techniques of rock climbing and who know how to belay and rappel are ready to take up the study of leading and of placing protection.

Leading is the skill of climbing first up a pitch, utilizing a belayer, rope, and intermediate protection for added safety. To many climbers, leading is one of the most satisfying activities in all of climbing. As leader, you're not just following; you've taken on the challenge and responsibility of determining the direction of the climb.

Placing protection is the skill of establishing points of protection along the route by using natural features such as trees and rock horns or by lodging safety devices in the rock. It's the technique that makes safe leading possible. The leader clips the rope through each piece of protection, while the belayer at the bottom of the pitch waits in position to hold the leader with the rope after any fall.

The skills of belaying, leading, and placing protection are combined in a two-person team for safe rock climbing. One climber, belayed by the second, leads up a pitch, placing protection along the way, and establishes a belay station at the top. The leader belays the second climber up. The leader then starts the next pitch, or alternates the lead (swings leads) with the second. The process is repeated until the end of the climb.

It's easy to picture how placing protection can save your life by limiting the severity of a fall. Unless there's an obstruction to stop the fall, you as the lead climber will fall just a bit more than twice the distance between you and your belayer. If you are climbing 20 feet above your belayer and have placed no protection, you could fall 40 feet: 20 feet back down to the level of the belayer, and another 20 feet to straighten the rope out again—plus a bit more due to rope stretch (fig. 10-1b). But add an intermediate point of protection, and the length of the fall is dramatically reduced. The fall now will be shortened to just twice the length of the rope between you and the last point of protection (fig. 10-1a).

The leader accepts more risk than the second, who has the luxury of a belay from above. The second doesn't have to place protection, and doesn't have to worry about dropping more than a short distance before the belayer stops a fall. The leader, on the other hand, has to place protection at intervals along the route and has to face the possibility of a longer fall.

Unless the leader falls, a piece of protection usually gets no use whatsoever. This is free climbing, in which the leader climbs free of the protection, never holding onto a piece of protection and never putting weight on the rope. In another type of climbing—aid climbing—the climber purposely hangs from the protection. (Aid climbing is covered in Chapter 11.)

Climbers distinguish between two main types of protection: natural protection and artificial protec-


a
CORRECT
b
INCORRECT

Fig. 10–1. Leader fall: a, with protection in place; b, no protection in place.

tion. With natural protection, you're relying on nature to provide something to connect the rope to. When natural protection is not available, you rely on metal wedges and cams (known as artificial chockstones, or chocks), and bolts and pitons, to establish artificial protection.

NATURAL PROTECTION

Some of the very best protection is already in place, just waiting for you. It's natural protection: trees and bushes, horns and flakes, chockstones, boulders, and other natural features. The leader can save the fancy hardware for later in the climb. Only the simplest tools—runners and carabiners—are needed to take advantage of these gifts from Mother Nature.

The basic technique for using all natural protection is identical: position a runner around the natural feature, clip a carabiner to the runner, clip the rope into the carabiner. And that's it.

Some things to pay attention to in using natural protection:

- **Test** every potential piece of natural protection before you trust your life to it. Take a close look at every tree and every rock. Does the tree look healthy? Does the rock appear unfractured, without cracks or other weaknesses? Carefully push them and pull them, tap and prod, kick and shake. Is everything solid?
- **Remember** the climbers down below as you're kicking and prodding. Be careful not to dislodge anything.
- **Try** to identify the type and composition of a rock feature as clues to its strength.
- **Check** to see if the protection will hold a pull in only one direction, or if it can take a tug from multiple directions. That is, is the protection one-directional or multidirectional? Multidirectional protection, such as a tree, is best because it can withstand an outward and upward pull.
- **Choose** an appropriate method of attaching the runner (fig. 10-2). You'll usually start by looping the runner around or over the natural feature. A runner that is looped around is secured by using a



Fig. 10–2. Methods of attaching a runner to natural protection: a, secured around a tree using a girth hitch; b, looped around a tree with the ends clipped together with a carabiner; c, retied around a tree trunk; d, attached to a rock horn using a clove hitch; e, looped over a flake.

girth hitch (fig. 10-2a) or by connecting the two ends with a carabiner (fig. 10-2b). If you clip the ends together with a carabiner, be sure the runner is long enough to permit the carabiner to extend out from the natural feature; this reduces the chance that the weight of a fall will be taken directly on the carabiner gate. Another method of attachment is to untie a runner and then retie it around the protection (fig. 10-2c). With rock horns, you also have the option of attaching the runner with a clove hitch (fig. 10-2d).

- **Position** carabiners with the gates down and facing out to lessen the chance that the rock will force the gate open during a fall. If there's danger of a carabiner being forced open, use a locking carabiner or two carabiners with opposing gates.
- **Pad** all sharp edges that the runner may touch.

TREES AND BUSHES

Trees and large bushes offer the most common and obvious natural protection. To judge their trustworthiness, look for vigorous growth and a well-developed root system. Avoid trees or bushes rooted in shallow soil, gravel, talus, or cracks. If you can identify the tree or bush, you may then know if it's one that tends to be shallow-rooted or especially brittle. Shake it. If the dirt or roots move, avoid it.

Select the largest tree or clump of bushes possible. Be wary of bushes, in general, and back them up with another point of protection if there's any doubt.

To reduce the leverage on a tree or clump of bushes—leverage that could bend or break them—it's best to position the runner as low as possible. However, sometimes it's desirable on a large tree to place the attachment point higher on the trunk, or even on a large branch, to avoid putting a sharp bend in the rope. If the runner is placed on a branch, keep it close to the trunk to reduce the leverage.

HORNS AND FLAKES

Horns are the most common type of natural rock protection. They also are called spikes, knobs, bosses, chicken heads, and rock bollards. They're small protrusions in the rock, and they come in handy.

Flakes are narrow pieces of rock partially detached from the main rock, and they also provide natural protection (fig. 10-2e).

Be aware that a horn or flake that was solid when you climbed the same pitch a year ago might have been weakened by frost action over the winter. Test the rock by pushing or pulling, gently at first, then with more force. Finally, hit it with your hand or foot and listen for a hollow sound. If it moves or creates a hollow sound, avoid it. If you use a girth hitch to secure the runner to a horn or flake, be sure it's placed so it can cinch up tight (fig. 10-3).

Horns and flakes frequently offer protection in only one direction. The runner may stay in place if there is a downward tug, but come loose if the pull is upward or sideways.

There are several ways to help overcome this problem. Attach some extra climbing gear to the runner in order to weight it and help keep it in place. Use a longer runner (or extend a short run-



Fig. 10–3. Runner attached to a horn: a, correct, attached by a correctly placed girth hitch. Girth hitch will cinch properly; b, incorrect, attached by an incorrectly placed girth hitch. Girth hitch will not cinch.

ner), a trick that will minimize the chance that rope movement will pull the runner off the rock. Place opposing protection that can take an upward pull. (We'll get into the theory and practice of opposing protection later in this chapter.)

CHOCKSTONES

A chockstone is a rock wedged in a crack. It can make a great protection point—if it passes a few tests. Does it have substantial contact with the sides of the crack? Is the chockstone, and the walls of the crack, of a non-friable type of rock (that won't tend to crumble and let the chockstone fall)? Does the crack narrow below the chockstone, causing it to be well-wedged? Will it jam even tighter if it must withstand the force of a fall?

Arrange a runner around the chockstone so the runner can't be pinched or jammed in case the chockstone comes under such a load. Be sure it can't be pulled sideways through a point of contact between the chockstone and rock. If you choose to simply clip the ends of the runner together with a carabiner, twist one end before clipping in. This ensures that if the runner does pull through one side of the chockstone, the carabiner won't drop off (fig. 10-4a). You also can attach the runner by a girth hitch around the point of contact between chockstone and rock, which can help hold the chockstone in place (fig. 10-4b).

You may be able to use an artificial chock to help thread the runner behind the chockstone.

Sometimes you can move a chockstone to a spot in the crack where it's more secure. Be careful you don't knock it loose and send it hurtling down the climbing route.

BOULDERS

A boulder, or a block detached from the main body of rock, can be used as a protection point if it's well-embedded or too heavy to move. Steer clear of boulders that look chancy—ones that lean, are perched precariously, or rest (temporarily) on a slope.

A runner is usually looped around the boulder to create the protection placement. Keep the runner low to reduce leverage and to keep it from being pulled off the top of the boulder. Use extreme care in using a boulder as a protection point because of the danger it poses to others if it comes loose.



Fig. 10–4. Attaching a runner to a chockstone: a, looped around a chockstone; b, using a girth hitch on one side of a chockstone.

THREADED PLACEMENTS

Threaded protection can be created from natural tunnels (fig. 10-5), arches, or the contact point between two blocks of rocks. If the rock feature is strong, the protection is usually a good choice because it is multidirectional; it can take a pull in any direction.

If you decide to use the contact point between two rocks, be sure the rocks can't move under the force of a fall. However, it's often difficult to test threaded protection, and you will usually have to rely on visual inspection and good judgment.



Fig. 10–5. Creating a threaded placement using a rock tunnel

ARTIFICIAL PROTECTION

In the absence of natural protection, climbers use artificial protection devices. These devices include chocks (artificial chockstones), bolts, and pitons. In most cases, the leader will use a chock or bolt, although pitons still have their uses. On a climb, the leader secures the piece of protection in the rock, providing a point of attachment for a runner, which is then connected to the climbing rope using carabiners.

CHOCKS

Chockcraft—the art of placing and removing chocks—is the preferred technique for protecting climbs. This supports the ethic of clean climbing, which is climbing that does not permanently alter the environment. Chocks are relatively easy to place and to remove and, unlike bolts and pitons, leave no scars on the rock.

Chocks are either wedges or cams (fig. 10-6). Wedges hold a fall by wedging against a constriction in a crack or against another wedge. Cams hold a fall by rotating slightly within a crack, creating a camming action that jams the chock against the rock.

Wedges and cams are either passive or spring-loaded. Passive wedges and cams are single pieces of metal, without moving parts, that are simply placed firmly in an appropriate location in the rock. Spring-loaded wedges and cams are chocks with moving parts that are retracted in order to fit them into a spot, then allowed to open fully again to hold them in that place.

To become proficient at chockcraft, a climber learns the strengths and weaknesses of different types of chocks and learns to place them correctly.

The lead climber should know the breaking strength of each chock, information published by manufacturers or independent testers. Larger chocks are usually heavier and stronger than smaller chocks, and therefore have a higher breaking strength. Some smaller chocks aren't even meant to hold a fall, but are strong enough to support a climber's weight in aid climbing.

All chocks are designed to use in a rock feature—usually a crack, sometimes a pocket. Before placing a chock, the climber inspects the rock, both to judge its soundness and to decide what chock to use.



Fig. 10–6. Examples of artificial protection: a, passive wedge; b, passive cam; c, spring-loaded wedge; d, spring-loaded cam.

The type of rock and its condition help indicate whether the chock will hold a fall. Specifically, chocks tend to hold well in solid rock. Crumbling or deteriorating rock is unreliable, and should be avoided.

If you're thinking of putting a piece of protection behind a rock flake, remember the hollow-sound test. Hit it with the palm of one hand, and if you hear a hollow sound, don't use the flake. Under load, it takes only a slight movement of the rock for the chock to lose its grip and fail.

The size, shape, and orientation of the crack or pocket determines what chock to use. Does the crack or pocket flare outward, flare inward, or have parallel sides? Is it shallow or deep? Is it vertical or horizontal? Some types of chocks work well in one situation, not so well in another.

Some other general considerations in placing chocks:

- **Learn** to estimate the right chock size for a particular placement. The better the estimate, the faster the placement—and the less chance the climber will tire and fall.
- **Choose** the best chock, not necessarily the largest one possible. A larger chock usually will hold a harder fall, but first decide if it actually provides the soundest protection or if a smaller piece would be more secure.
- **Decide** whether a particular chock is likely to be adequate, based on the characteristics of the rock and the magnitude of a possible fall. If not, reinforce it with another chock or find a better placement.
- **Check** out every chock after it's in place. Look to see that it's placed correctly. Tug on it to help determine the strength and security of the placement, especially in the likely direction of pull.
- **Guard** against the chock being dislodged by rope movement. A runner is usually attached, with carabiners, between the chock and the rope. This helps reduce the effect of rope movement. Wired chocks are more affected by rope movement and have a greater tendency to rotate out of place.
- **Guard** against the chock being dislodged by an outward or upward pull. Many chock placements are one-directional; they will take a load in only one direction. If a one-directional placement could come under a load from multiple directions, make it multidirectional by placing opposing chocks. (This procedure gets a full explanation later in this chapter.)
- **Remember** the climber who will be following behind you and removing the protection. Make your placements secure, but also try to make them reasonably easy to remove.

Chock slings

A climber's high-priced pieces of protection won't do any good until they're connected to the rope. So every chock must include some type of sling as a part of the attachment system from the chock to the rope. The sling is usually made from accessory cord, tubular webbing, or wire cable.

Smaller chocks usually come with a wire cable sling, which is much stronger than cord or webbing of the same size. The ends of the cable are swaged together. Larger chocks come pre-drilled with holes for accessory cord, which is usually added by the climber. Some chocks come pre-slung with tubular webbing.

There is a bonus advantage to using wire cable with passive wedges, such as Black Diamond (formerly Chouinard) Stopper nuts or Wild Country Stones. The wire's relative stiffness makes the wedges easier to handle and to place.

However, with passive camming chocks, such as Black Diamond Hexentric nuts, it's better to have accessory cord, providing it's strong enough. The cord permits the chock to rotate and cam freely as it's meant to do. Most modern hexes are drilled to accept 5.5-millimeter accessory cord.

For many years, climbers used 6- to 9-millimeter nylon cord and 1-inch nylon webbing to make chock slings. Nylon is durable and inexpensive but requires relatively larger diameters for strength, creating bulky and heavy chock slings.

An alternative fiber called Kevlar came into use for accessory cord. Kevlar cord at 5.5 millimeters in diameter is smaller, lighter, and stronger than nylon. However, Kevlar cord is weakened by repeated bending. Consequently, the manufacturer recommends it only for tying chock slings, because these slings are knotted just once and are not subjected to repeated bending.

A new fiber, Spectra, is even lighter, stronger, and more abrasion resistant than Kevlar. For use as chock slings, the Spectra fiber is used in 5.5-millimeter cord or 9/16-inch webbing.

Here are some things to keep in mind when attaching accessory cord as a sling to a chock:

- **Inspect** the holes that are drilled in the chock for the cord. They should have rounded edges to reduce the chance the sling could be cut under stress.
- **Tie** the ends of the cord together with a double fisherman's knot. Check it frequently in use to be sure it stays tight.
- **Determine** the right length for the sling. A sling is usually between 8 and 14 inches long, and some manufacturers provide information on how much sling material is needed for chocks of different sizes. One caution: If you make a chock sling too long, it could hang down far enough to interfere with footwork during climbing.

Passive wedging chocks

Out on a climb, no one will mention anything called a "passive wedging chock." Out there, passive wedging chocks go by a lot of catchier names: brands such as Stoppers, Stones, and RPs, and terms such as nuts, steel nuts, micronuts, tapers, and just plain chocks.

Wedging chocks are tapered down from top to bottom so they will fit into a constriction in a crack. They have a wide side and a narrow side, and are strongest when the wide surface area is touching the rock (fig. 10-7). The object is to get the greatest possible contact between chock and rock. Many wedging chocks, especially the smaller sizes, are not designed to be placed with the narrow side in contact with the rock.



Fig. 10–7. Wide-side and narrow-side placement of passive wedging chocks: a, wide sides are in contact with the rock, a stronger placement; b, narrow sides are in contact with the rock, a weaker placement.

A passive wedging chock has no moving parts to hold it in place. It sits passively in a constricting crack until it takes a load—such as a leader fall. Then the chock wedges into the crack, generating expansion forces and increased friction. It holds tight.

Though they all taper, there are variations in the shapes of wedging chocks (fig. 10-8). Manufacturers try subtle changes in design to improve performance, and new designs continue to appear.

Some wedging chocks are straight-sided, some



Fig. 10–8. Design variations in passive wedging chocks: a, wide side, straight sides; b, narrow side, straight sides; c, wide side, curved sides; d, narrow side, curved sides; e, top view, rectangular; f, top view, trapezoidal.

have slightly curved sides. They can also have a combination of straight and curved sides. Smaller wedging chocks are usually straight-sided, while larger chocks may have pronounced curvature. Viewed from the top, wedging chocks can be rectangular or trapezoidal.

The goal in using any wedging chock, regardless of shape, is to create a stable and secure point of protection—something you can stake your life on. A straight-sided chock may not place well in a crack with an uneven surface, whereas a curved chock may fit nicely. In another spot, the straight-sided chock could be just the thing.

A curved-sided chock creates three points of contact, which adds to stability (fig. 10-9). However, it may seat so securely that it can be tough to remove. If the edges on a wedging chock are slightly rounded, it tends to be easier to remove.



Fig. 10–9. Curved-sided chock, with three points of contact with the rock

The Hexentric passive camming chock can also be used as a passive wedge. Even though it doesn't look like a wedge, the ends of the Hexentric are tapered, allowing it to wedge in a constricting crack (fig. 10-10).

In an emergency, the knot of a runner can be jammed into a constricting crack and serve as a wedging chock.

Vertical cracks

Here's where wedging chocks work the best. Put the chock above a constriction in a vertical crack. A downward pull wedges the chock more tightly into the crack.

If the sides of the crack are generally smooth, a straight-sided chock works well. If the sides are rougher or slightly curved, a curved-sided chock works better.



Fig. 10–10. Hexentric used sideways in a crack as a passive wedging chock

For the most secure placement, slot the wedge completely into the crack (fig. 10-11).

Passive wedging chocks usually are able to hold a load only in one direction. However, if the chock is slotted deeply into a crack and seated correctly, it can handle pulls from multiple directions.



Fig. 10–11. Passive wedge slotted in a vertical crack: a, secure, slotted completely into a vertical crack; b, insecure, slotted partially into a vertical crack.

Passive wedging chocks do not work in parallel-sided vertical cracks (fig. 10-12). If the sides of the crack are straight and parallel, the chock has very little contact with the rock, and a severe downward pull can cause the contact points on the chock to shear.



Fig. 10–12. Incorrect, a passive wedge placed in a parallel-sided vertical crack with little contact to the rock

There's a way around this problem: use two wedges in a method called stacking. Stacked chocks can be created from two independent chocks or from a specially made chock stack.

The theory is the same in either case. The chocks are placed in opposition in a parallel crack. A downward pull on the larger chock causes it to wedge between one side of the crack and one side of the opposing chock. All stacked chocks should be seated with a firm tug before use.

If two independent chocks are used (fig. 10-13a), they should be connected with a carabiner so that if the placement fails, a chock will not be lost.

A chock stack (fig. 10-13b) is constructed by putting two passive wedging chocks on the same sling. The chocks are different sizes, with the smaller chock at the end so that either can be used in a non-stacking chock placement.

Stacked wedges aren't used so much any more because climbers now have the option of spring-loaded wedges or spring-loaded cams, which work better and are easier to place.

Horizontal cracks

Although wedging chocks work best in vertical or near-vertical cracks, horizontal cracks sometimes can be used. The horizontal crack should constrict at the lip of the crack. The chock can be slotted in a wider section and then slid behind the constriction (fig. 10-14). A well-placed wedging chock in a horizontal crack can be very secure because it tends to be multidirectional.

The chock should be well recessed, and the sling should not be able to contact a sharp upper or lower lip on the crack. A chock set at the lip of a crack is more likely to fail. The edge of the chock can cause the sling to shear, and the chock itself will create a camming action at the lip of the crack that could cause it to crumble (fig. 10-15).



Fig. 10–13. Stacking chocks: a, two independent chocks stacked together; b, chock stack.



Fig. 10–14. Passive wedge slotted behind a constriction in a horizontal crack



Fig. 10–15. Passive wedge placed in a horizontal crack, side view: a, correct, slotted deep within the crack; b, incorrect, slotted at the lip of the crack.

Flaring cracks

A wedge that's trapezoidal in shape from a top view may work well in a crack that flares outward. Used with the narrow sides of the chock against the rock, this shape can provide a stronger and more stable placement in this particular situation because it increases surface contact with the rock (fig. 10-16a).

A crack that flares inward can cause a seemingly strong placement to be insecure (fig. 10-16b). If you keep alert you should be able to see this situation before making a bad placement.



Fig. 10–16. Using passive wedges in flaring cracks: a, a secure placement in an outwardly flaring crack; b, an insecure placement in an inwardly flaring crack.

Pockets and threaded placements

Passive wedging chocks don't work well in pockets.

For a threaded placement, where a crack constricts to form a tunnel, a wedging chock can sometimes be threaded through to form a protection point (fig. 10-17). The chock can be threaded upward or downward. A wired chock will thread more easily than a chock that has accessory cord for a sling.

Be sure the crack does not widen too much behind the constriction, possibly permitting the chock to pull through. Good threaded placements, however, can be very secure because they are often multidirectional.



Fig. 10–17. A passive wedge threaded through a tunnel in a crack

Passive camming chocks

Climbers also have a batch of popular names and brand names to use in referring to passive camming chocks: hexes, hex nuts, Hexentrics, Tri Cams.

A passive camming chock is placed in a crack in such a way that when it takes a load—from, for example, a 160-pound climber at the end of a 30-foot leader fall—it tries to rotate. The rotation causes the chock to cam and lock in place.

The shapes of camming chocks vary. One manufacturer will use a design completely different from that of another, and designs continue to evolve.

Traditional camming chocks had a balanced hexagonal shape. Both pairs of opposing sides used for camming were the same distance apart. These hex nuts could cam and lock in place, but had limited versatility because each nut could fit only a small range of crack sizes.

Chouinard Equipment (now Black Diamond Equipment) modified the basic hex nut in creating its Hexentric nut, in which each pair of opposing sides is a different distance apart. The Hexentric can be used in a greater range of crack sizes because it can be placed for narrow camming or wide camming and provides different camming angles (fig. 10-18). It can also be used endwise as a passive wedge.



Fig. 10–18. Camming modes of a Hexentric chock: a, narrow camming; b, wide camming.

The Lowe Tri Cam is another design, using a completely different shape to generate the camming action. Because of its shape, the Tri Cam can be used in a range of crack sizes (fig. 10-19).



Fig. 10–19. Camming modes of a Lowe Tri Cam chock: a, major cam mode; b, minor cam and wedging mode.

Any single camming chock works only within a specific range of crack sizes. If a crack is too wide, the chock can fall out. An excessively tight fit, on the other hand, can prevent the camming action from occurring. Then the camming chock would simply act like a passive wedging chock.

After you've placed a passive camming chock, give a sharp tug on the sling. This will initiate some camming action and seat the chock in place.

Vertical cracks

Passive camming chocks work well in vertical cracks that are parallel or that do not expand too much. Place a chock that is tight enough to have maximum contact with the rock, but that has enough room for proper camming action to take place under load.

If the chock is too small, only its edges may be in contact with the rock and, under load, these edges can shear off. A loose chock also can be dislodged by rope movement. The fit should be snug, which will help hold the chock in place when it's not under load (fig. 10-20).

One trick that can create a stable placement is to build a combination stack using a passive wedging chock with a passive camming chock—a Stopper with a Hexentric (fig. 10-21).



Fig. 10–20. Placement of a Hexentric in a vertical crack: a, correct, Hexentric in proper camming mode with sides fully contacting the rock; b, incorrect, Hexentric is too small for the vertical crack. No camming will occur.



Fig. 10–21. A combination stack using a passive wedge and a passive camming chock

Horizontal cracks

Passive camming chocks also like parallel cracks that are horizontal. Place the chock so the sling leaves the crack closer to the roof than to the floor of the crack (fig. 10-22a). Otherwise, it won't cam (fig. 10-22b). Be careful that the chock isn't rotated out of position by sideways forces.

The crack shouldn't widen inward too much or proper camming action won't take place (fig. 10-22c).



Fig. 10–22. Placement of a Hexentric in a horizontal crack: a, correct, chock sling exits near roof of crack, proper camming will occur; b, incorrect, chock sling exits near bottom of crack, little or no camming will occur; c, caution, if the Hexentric moves back in the inwardly flaring crack, proper camming will not occur.

Flaring cracks

Passive camming chocks don't work well in flaring cracks, where they tend to be unstable and don't make maximum surface contact. Tri Cams work in some flaring cracks. However, all points must still be able to contact the rock and that may not be possible.

Pockets and threaded placements

If the pocket is deep enough, a Tri Cam will work, but it must be recessed completely into a pocket for maximum surface contact and stability (fig. 10-23). Rope movement can easily dislodge this placement.



Fig. 10–23. Tri Cam placed in a pocket

Like passive wedging chocks, some passive camming chocks can be threaded through a small rock tunnel to create a protection point. In this case, the chock is relying on wedging and not camming action to hold a load.

Spring-loaded wedging devices

This is another of those technical terms you won't usually hear while moving up a rock face: spring-loaded wedging devices (fig. 10-24). That's what they're called here, because it's a good technical description. In action, you'll hear them referred to under such names as Quickies, Rock 'n Rollers, and Ball Nuts.



Fig. 10–24. Examples of spring-loaded wedging devices: a, D. Best Quickie, contracted and expanded; b, Go-Pro Rock 'n Roller, contracted and expanded; c, Lowe Ball Nut, contracted and expanded.

These gadgets use variations on the chock stacking theme to create protection in tiny finger cracks. A spring-loaded wedging device features two sliding pieces in opposition. A trigger mechanism held by a spring controls the position of the smaller sliding piece.

Pull the trigger, and the smaller piece slides lower against the larger piece—narrowing the profile of the device so it can fit into the thin crack. Release the trigger, and the smaller piece springs back higher against the larger piece—expanding the profile and wedging the pieces against each other and against the walls of the crack. The force of a fall wedges the pieces even tighter.

You can place a spring-loaded wedge in a vertical crack using only one hand, a big improvement in efficiency over passive chock stacks. After placing a spring-loaded wedge, give it a tug to seat it securely.

Spring-loaded wedges also can be used in horizontal cracks. Try to place them so the stem of the device won't be bent sharply around a rock edge in case of a fall. The stems are flexible, but may not be designed to hold a fall if they are bent too much.

Some spring-loaded wedges are designed to be separated and used as individual wedges if you wish. This makes the device more versatile, but be sure that's what the manufacturer had in mind before you try it.

The orientation of the smaller piece on some spring-loaded wedges, such as the Quickie, is fixed in relation to the larger piece, limiting these devices to parallel-sided cracks. But the smaller piece on designs such as the Rock 'n Roller and the Ball Nut rotates relative to the larger piece. This allows the smaller piece to conform better to uneven or flaring cracks and reduces the possibility it will be dislodged by rope movement.

Spring-loaded wedges don't work in pockets and threaded placements.

Spring-loaded camming devices

First came Friends. The original spring-loaded camming device was developed in the mid-1970s and dramatically expanded the limits of free climbing by providing protection that could be placed with one hand and that could adapt to a variety of cracks. Climbers now could take on tough routes that would be very difficult to protect with conventional chocks.

Since the development of Friends, variations on the basic design have been created. Newer designs tend to use cable stems, more flexible than the solid stems of the original Friends. Some include three cams instead of the four used in each Friend. Among today's most popular spring-loaded camming devices (fig. 10-25) are Friends and Flexible Friends (manufactured by Wild Country), Camalots (made by Black Diamond Equipment), and TCUs (Three-Cam Units, by Metolius).

The three or four cams in a spring-loaded camming device are connected to a trigger mechanism.



Fig. 10–25. Examples of spring-loaded camming devices: a, Wild Country Friend, expanded and b, contracted; c, Wild Country Flexible Friend; d, Black Diamond Camalot; e, Metolius TCU (tri-cam unit).

Pull the trigger and the cams retract—narrowing the profile of the device so it can fit into a particular crack. Release the trigger and the cams again rotate outward—expanding the profile until the cams grip the sides of the crack (fig. 10-25a). In a fall, the cams try to rotate and expand again, gripping the crack even more securely.

The three or four cams rotate independently of each other, permitting each to expand to the maximum, wherever it may sit in a particular crack.

All is well if you've placed a spring-loaded camming device and all the cams, expanded to their midpoint, are in contact with the rock and the stem of the device is pointing in the likely direction of pull (fig. 10-26a).

But beware of these potential problems:

1. All the cams don't touch the rock. The placement will be unstable. Find a better spot.
2. The cams are over-retracted in the crack (fig. 10-26b). The device may be jammed in so tightly that it can't cam, and it may be very hard to get the thing out. Use a smaller spring-loaded cam.
3. The cams are over-expanded, with only the tips of the cams touching the rock (fig. 10-26c). No camming action can take place, and the device will serve only as a passive wedging chock. Under load, most devices will structurally fail. Use a larger spring-loaded camming device. (An exception is the Camalot, which is strong enough in the ''umbrella'' position to be used as a passive chock.)
4. The stem does not point in the likely direction of pull (fig. 10-26d). A fall can force the device to rotate, perhaps causing the cams to lose their grip.

In an uneven crack, the independent cams can expand to different widths. This is good. It means the device will adjust to variations in the crack. But if the cams are too unbalanced, proper camming action won't occur and the placement could fail. This is bad. So always try to make sure that each pair of cams is symmetrically oriented and that all cams contact the rock.

The spring-loaded camming devices that use



Fig. 10–26. Correct and incorrect placement of spring-loaded camming devices: a, correct, cams expanded to midpoint, stem in likely direction of pull; b, incorrect, cams are over-retracted, proper camming may not occur; c, incorrect, cams are over-expanded, no camming will occur; d, incorrect, stem is not pointed in likely direction of pull.

only three cams, instead of four, are smaller and narrower. They're designed for shallower placements, though they can also be used more conventionally. The four-cam devices have a bad habit of "walking" into cracks as a result of rope movement, making them sometimes difficult to retrieve. The three-cam units will rotate more and are less likely to walk.

Vertical cracks

Spring-loaded camming devices really come into their own in parallel-sided vertical cracks. They're easier, faster, and safer than stacked wedges or passive cams. When correctly placed, the stem of the device will point in the anticipated direction of pull, allowing the load to be transmitted along the axis of the stem and maximizing strength of the placement.

Horizontal cracks

You can also use spring-loaded cams in horizontal and diagonal cracks, but watch out for stem breakage.

The original Friends design uses a solid stem. This is fine as long as the direction of pull is along the axis of the stem, which is usually the case in a vertical crack. The picture changes with horizontal cracks.

Newer designs from the makers of Friends and from other manufacturers use flexible cable stems, which can bend and adjust if the direction of pull is not along the axis (fig. 10-27a). However, the original Friends are still being made and are in wide use, so it's important to know how to minimize the danger of having a solid stem break in a horizontal placement.

If the solid stem doesn't extend beyond the edge of the horizontal crack, the stem won't come under any dangerous forces. However, if the crack is shallow and the stem extends beyond the edge of the crack, the stem would be forced against an edge during a fall and could shear at the lip of the crack.

You can reduce the danger of breakage by adding a tie-off loop, of accessory cord or webbing, to the largest hole in the stem. Make it slightly shorter than the regular chock sling. Clip into the tie-off loop so the force of any load will be taken closer to the cams (and farther from the end of the stem). As a backup, also clip in the regular sling in case the tie-off loop fails (fig. 10-27b).



Fig. 10–27. Spring-loaded camming device placement in a horizontal crack: a, flexible cable stem can bend and adjust to the direction of pull; b, a tie-off loop can reduce the danger of solid-stem breakage.

Flaring cracks

Because each cam works independently, they can individually expand to fit a flaring crack. Problems occur if the crack flares too much. Some of the cams could over-expand, making for an unstable placement. The device may then be more susceptible to rotation or rope movement and less able to cam properly under load.

Pockets and threaded placements

Spring-loaded camming devices don't work for threaded placements.

They are usable in some pockets, but only if the pocket is deep enough to allow all cams to touch the rock.

Spring-loaded tube chocks

It's difficult to place protection in wide cracks because most chocks aren't big enough.

Sometimes the answer is a large spring-loaded camming device, but these can get awfully heavy. An alternative spring-loaded device for protecting wide cracks is the telescoping tube chock.

The tube chock has a spring-loaded inner sleeve. Release the spring and the sleeve pops out far enough for the tube to bridge the crack (fig. 10-28a). A locking collar keeps the tube extended. After setting the chock, the climber clips in to a sling attached to one end. With a load on that end resulting in an upward force on the other end, the device acts like a passive camming chock (fig. 10-28b).



Fig. 10–28. Spring-loaded tube chock: a, Mountain Hardwear Big Bro, contracted and expanded; b, Big Bro correctly placed in a vertical crack.

The wedging factor

Under load, a chock creates expansion forces. The relative amount of expansion force created by a chock—whether it's a wedge or a cam—is known as the wedging factor.

Splitting firewood with a wedge is an illustration of wedging action. A chock is a wedge in the rock. Put a load on the chock, and it tries to expand the rock—just as hitting a wedge with a hammer causes it to split firewood.

The relative amount of expansion force depends on the angle of a chock face (fig. 10-29a). If the taper angle is smaller, the wedging factor will be higher and it will put more force on the rock (fig. 10-29b). Conversely, if the taper angle is larger, the wedging factor will be lower (fig. 10-29c).

Friction between the rock and the chock affects the wedging factor. Rougher rock increases friction, which decreases the wedging factor. Dirt or vegetation can lubricate the chock, reducing friction and increasing the wedging factor.

The applied load and the wedging factor combine to determine the actual amount of expansion force generated. A high applied load, such as a falling climber, taken on a chock with a high wedging factor results in a very large expansion force.

A couple of examples can give an idea of how the wedging factor affects expansion forces. A chock with a taper angle of 14.4 degrees will cause it to push against the walls of a crack with a force equal to four times the load. Therefore, a 170-pound climber who puts full weight on this chock would generate 680 pounds of expansion force (and a little hop could easily double the force). Now take a smaller chock, with a taper angle of 4.5 degrees. The wedging factor goes much higher, now equal to 12 times the load. The 170-



Fig. 10–29. The wedging factor: a, illustration of taper angle and expansion forces; b, narrow chocks have small taper angles and generate greater expansion force under load; c, wide chocks have large taper angles and generate less expansion force under load.

pound climber who puts full weight on the chock now generates 2,040 pounds of expansion force.

The wedging factor becomes particularly important when placing a chock behind a flake. Expansion force could push the flake outward, loosening the protection. It could even knock the flake off, destroying the protection point. Chocks with higher wedging factors are more likely to generate this magnitude of expansion force.

A flake best resists expansion force near its point of attachment. Consequently, it may be better to use a smaller chock (with greater wedging factor) near the attachment point, than a larger chock (with lower wedging factor) higher up. The tradeoff in using a smaller chock is that it is a weaker piece of protection.

The camming action of a spring-loaded camming device generates very concentrated expansion force. Be cautious in using them behind flakes.

BOLTS AND PITONS

Bolts and pitons are protection devices that are drilled into the rock or pounded into cracks. They sometimes provide protection where there's no place to lodge a chock.

A bolt is a permanent piece of protection driven into a hole drilled in the rock (fig. 10-30a). A bolt hanger provides attachment for a carabiner, and a threaded nut is sometimes needed to attach the hanger to the bolt.

A piton is a metal spike that is pounded into a crack to provide a point of protection (fig. 10-30b). The blade of the piton is the part driven into the rock; the eye is the point of attachment for the carabiner.

Placing pitons is called pitoncraft, a skill that will be studied in Chapter 11. Pitons and bolts are being introduced here because it's necessary to know how to deal with ones you will encounter on climbs, put in place by previous climbers. You need to know how to check these placements to determine if they can be trusted as protection for your climb.



Fig. 10–30. Bolts and pitons: a, bolt with a bolt hanger; b, piton driven into a vertical crack.

Pitons are seldom used in modern free climbing. They still get some use on climbs in remote areas or on routes requiring mixed free and aid climbing.

Bolts are now widely used to protect some of today's severe free rock climbs. The bolts create artificial protection where there are no rock features to accept either chocks or pitons. However, climbing ethics encourage the use of clean-climbing techniques when possible, to prevent the permanent scarring caused by pitons and bolts.

Bolts

Look at fixed bolts with a skeptical eye.

How safe a particular bolt may be is going to depend on the quality of the hardware, the type of rock, the skill of the climber who placed the bolt, and so forth. It's to your advantage, to say the least, to carefully check out every bolt you encounter before clipping into it.

Check to see that the bolt is placed in rock that is solid, not crumbling or deteriorating. Be sure the hanger is flush to the rock. Look for corrosion or cracks on the bolt or hanger. Beware of aluminum hangers because they can become brittle with use. Steel hangers tend to be stronger.

Do not tap on a bolt to test its strength or security as repeated hammering only loosens the bolt. The bolt can be partially tested by hand or by clipping a runner onto it and tugging. If it moves, or if for any reason the placement doesn't seem solid, forget it except possibly for backup protection.

If you like the bolt, use a carabiner to clip a runner to the bolt hanger. In some climbing areas, bolt hangers are customarily removed by climbers after use, so it may be necessary to carry along a few hangers and nuts in $^1/_4$-inch and $^3/_8$-inch sizes.

If a hanger is not available, a hangerless bolt can be used by sliding a wired chock down its cable sling so the resulting wire loop can be placed over the bolt. Slide the chock back up the sling to create a snug noose, then clip into the sling (fig. 10-31). Rope movement easily dislodges this type of placement, so don't use it for protection unless it's an emergency. Nevertheless, it can be used in aid climbing or in constructing opposing chock placements.



Fig. 10–31. Placing a wired chock on a hangerless bolt: a, create a loop by sliding the chock down the chock sling; b, slide the chock up the sling to form a noose around the hangerless bolt.

Pitons

Can you trust an old piton? Well, it depends ...

A fixed piton that you run across during a climb may be a quick and easy way to get some good protection. It may also be old and in bad condition. Over the years, pitons rust, weaken, and become loose.

Take a close look at the piton. Is the eye broken or badly rusted? Is the piton rusting in the crack or perhaps even loose enough to pull out by hand? Is the piton bent?

Ideally, the fixed piton is perpendicular to the likely direction of pull, and it's driven in all the way, with the eye up close to the rock. Examine the condition of the rock, looking for deterioration. Test the piton first by hand. Then tap on it with a piton hammer or a large chock. If it moves, it's unreliable. Beware of older pitons that use iron rings as an attachment point because the rings tend to be very weak. If there is any doubt about a piton's strength or security, try to find other protection.

If the piton seems to be strong, secure, and in good condition, use it. Attach a runner with a carabiner clipped to the piton eye. Be sure the carabiner will not bind against the rock under load, which could cause carabiner failure.

If a piton is only partially driven, tie it off next to the rock with a runner, using a girth hitch or clove hitch (fig. 10-32). The tie-off reduces the leverage on the piton under the impact of a fall. It's also possible to get a marginal attachment by using a cabled chock in the same manner as in connecting to a hangerless bolt. (Slide a wired chock down its cable sling, place the resulting wire loop over the piton, and slide the chock back up the sling to make a snug noose.)



Fig. 10–32. Partially driven piton, with a tie-off next to the rock to reduce leverage

If a piton eye is bent so much that the carabiner won't fit through, it may be possible to thread a cabled chock through the eye. Don't count on it to hold a hard fall, however, and avoid this placement if you have an alternative.

The best judge of fixed pitons is the climber who knows how to place them correctly in the first place. (See Chapter 11 for information on placing pitons.)

DOUBLE PLACEMENTS

Two pieces of protection are sometimes linked in order to do a better job than a one-piece placement. This technique is commonly used in two different ways: to set up opposing chocks so the placement gives multidirectional protection, or to equalize the load over two pieces of protection.

Multidirectional protection

Most chock placements will hold only a downward pull. They are one-directional, providing protection for a load from only a single direction.

No problem, you might say. If I fall, I'll only fall downward. True. But there are times a chock must be able to hold an upward or sideways pull. When the route changes direction at or above a placement, the resulting bend in the rope may simply pull a passive chock up and out of the crack. In some cases a fall taken on a higher chock will put upward and outward forces on lower chocks.

What's needed in these situations is multidirectional protection—placements that will hold fast whether the pull is down, up, or out. The most obvious multidirectional protection is provided by trees, natural tunnels, pitons, and bolts. Otherwise, the standard method of providing multidirectional protection is to place a pair of opposed chocks—chocks that are linked so that they pull toward each other. This method also is used to hold passive wedging chocks in horizontal cracks that won't take a simple placement.

Vertical opposition

An "iffy" chock in a vertical crack needs help from an opposed "keeper" chock.

The basic procedure is simple. Place one chock in the crack so it can take a downward pull. Below that, place a chock that can take an upward pull. Clip a carabiner to each chock sling. Using a clove hitch or half hitches, tie the two carabiners together with a runner so there is tension between the two chocks, which helps hold them in place (especially the bottom chock—the keeper—which otherwise might drop out). Then clip the rope into this arrangement. Three methods are shown here in figure 10-33.

Another setup, recommended in some climbing



Fig. 10–33. Three methods for creating vertical opposition: a, using one runner, chocks are held by tension on one side of the runner using clove hitches; b, using one long runner, a clove hitch or two half hitches holds the tension between the chocks; c, using two short runners, one runner creates the tension between the chocks using a clove hitch or two half hitches, the other runner clips to the rope.

texts, should be avoided (fig. 10-34). This setup has two principal disadvantages compared with the preferred methods.

First of all, it places a dangerous multiplication of forces on the upper chock. Because the runner is not tied off to the upper chock, the runner moves freely through the carabiner, which acts like a pulley. This will double the usual force on the upper chock, perhaps causing it to fail.

Secondly, the bottom chock has nothing to hold it in place. This chock may stay put if it's set securely or if there is some tension on the rope. Otherwise, it could simply drop out.

The preferred methods (illustrated in figure 10-33) avoid the dangers of load multiplication. Each preferred method creates tension between the chocks to hold them in place and includes a tie-off at the upper chock to prevent the carabiner from acting like a pulley and multiplying the load.



Fig. 10–34. Incorrect method of creating vertical opposition



Fig. 10–35. Creating horizontal opposition in a crack: a, correct, chocks are slotted back into the crack and angled to resist rotation and outward pull under load; b, incorrect, chocks are slotted at the lip of the crack and face directly at each other; c, incorrectly placed chocks in vertical opposition can be rotated out of the crack under load.

Horizontal opposition

If a horizontal crack doesn't have a nice constriction to slot a passive wedging chock behind, you can try to set up opposing chocks. Under load, the opposition pulls the chocks toward each other, creating tension that keeps them in the crack.

Here's the basic procedure: slot two chocks back in the crack. They should face in the general direction of each other, yet be set at enough of an angle to withstand some outward and downward loading. If at least one chock cannot withstand some downward loading, the horizontal opposition is likely to fail.

There are a couple of ways to link the chocks to each other and to the rope. In one method, a runner clipped to the carabiner at one chock sling simply runs through the carabiner at the other sling and then is clipped to the rope (fig. 10-35a). Be *sure* the chocks are slotted back into the crack and are partially angled outward. If not, the chocks could rotate out of the crack and fail under load (fig. 10-35b and c). Also, be aware that the usual force felt by the right-hand chock in figure 10-35a will be increased because its carabiner will act like a pulley. Choose a strong chock for this placement.



Fig. 10–36. Clipping two chocks together to create horizontal opposition: a, correct, chocks are slotted back into the crack and angled to resist rotation and outward pull under load; b, incorrect, chocks are slotted at the lip of the crack and face directly at each other. The chocks are susceptible to rotation and outward pull under load.

Another method is to clip the two chocks together with a carabiner (fig. 10-36). The carabiner can either be clipped into both chock slings or into runners that extend from the slings.

In either case, there are two important things to remember:

First, slot the chocks back in the crack, facing in the general direction of each other but angled partially outward. At least one must be able to withstand outward and downward loading.

Second, keep the angle between the chock slings as small as possible. When two chocks are connected and subjected to a load, the angle between the slings determines how much force they will experience. The larger the angle, the greater the force on the chocks (fig. 10-37). Too large an



If the load on the carabiner is 100 lbs., then each anchor will be subjected to X pounds of force depending on the angle:

ANGLE BETWEEN PROTECTION (DEGREES)	LOAD ON PROTECTION (LBS.)
179	5727
175	1147
150	200
120	100
90	71
45	54
5	51

Fig. 10–37. How the angle between protection affects the force exerted on the protection under load

angle and the protection could fail. The angle should be kept below 90 degrees, and ideally around 45. Using runners to extend out from the slings will reduce the angle, helping minimize the force felt by the chocks during a fall.

Equalizing protection

Faced with a hard move and questionable protection, a leader may decide to place two pieces of protection close together. If the upper chock fails, the lower chock is there as a backup (fig. 10-38).



Fig. 10–38. Placing a backup chock to help protect a questionable placement

Another option is to equalize the load over two protection points, subjecting each to only a portion of the total force. (A more complicated version of equalizing protection, with three or more protection points, can be used at belay points to establish an anchor. See Chapter 7.)



Fig. 10–39. Constructing the two-point equalizing protection: a, correct, the carabiner is clipped from one loop of the twisted runner to the other; b, incorrect, the carabiner is clipped across the twisted runner.

Two-point equalizing protection can be placed with one hand and requires the use of only one runner. Twist the runner into two halves, then clip each end into a protection point. Clip a carabiner between the two halves, providing an attachment point for the rope (fig. 10-39a). A load on the rope causes this carabiner to slide between the questionable protection points, adjusting the runner to equalize the force exerted on each point.

Important: clip the carabiner from one loop of the twisted runner to the other loop, not crosswise (fig. 10-39b). You'll find out why if you fall and one of the protection points fails. If you've done it right, the carabiner will stay connected to the runner, which stays connected to the remaining protection. Do it wrong, and the carabiner, with you attached, will plummet.

TECHNIQUES OF PROTECTION: LEADING A PITCH

A SAFE LEADING STRATEGY

After you get to know the tools for protection and how to place them, it's time for the next move—literally.

It's one thing to recognize a Stopper and a hex and a Friend and to be able to use them in individual placements. You can learn all this at home or while standing safely at the base of a cliff.

It's another thing to get up on the cliff and take the lead. You now need to learn the protection techniques that let you use these tools safely in mapping strategy for an entire pitch.

You'll learn to think of the entire pitch as you make each placement. How will this placement affect the total climbing system—and vice versa? Learn these techniques and you shouldn't have any nasty surprises in a fall. That beautifully placed chock won't pop out, because you used the right tricks to make it do its job in the context of protection for the entire pitch.

Leading is a complex business. Beginners usually need an apprenticeship, moving behind seasoned climbers, before they can safely take the sharp end of the rope. Don't ever take a lead if you don't feel ready, and don't pressure others into leading. Keep the art of leading what it ought to be: exciting, challenging, satisfying, and safe.

DECIDING FREQUENCY OF PROTECTION

The universal fear of falling leads many climbers to place protection before almost every move. They deplete their hardware and waste valuable time. They also miss one of the great attractions of rock climbing, the exhilaration of moving smoothly and continuously up the rock.

Other climbers under-protect, sometimes to show off their strength and daring. They get a psychological lift that doesn't do a thing to counteract the law of gravity.

But the sensible climbers—you and I—base our decisions about protection on a careful assessment of our personal abilities, the character of the rock, and the time and equipment available.

The closest thing to a general rule is to place protection where you feel uncomfortable without it. Of course, comfort level isn't always determined by a rational assessment of danger. A climber who feels comfortable making a difficult move a mere 6 feet above the last piece of protection may risk a nasty fall onto a sharp rock horn, while a climber on a low-angle friction slab with no projections to hit if he falls may be terrified at running out 20 feet beyond the protection.

In coming to your own decision on when to place another piece of protection, keep in mind the quality of the placements on a pitch. If they're tending to be poor or questionable, you'll probably put in more to increase the likelihood that at least one will hold. Knowing the fall factor, discussed next, also helps in deciding the next placement.

DETERMINING THE FALL FACTOR

The relative forces generated by a leader fall are measured by the fall factor, determined by dividing the length of a fall by the length of rope run out from the belay. The higher the fall factor, the greater the force.

The fall factor is lower when the length of rope run out from the belay is relatively great, because a long length of rope stretches more and absorbs more energy than a short length. The practical effect of this fact is that when the length of rope between belayer and climber is great, a fall will usually result in a smaller force than the same fall on a short length. Therefore, it's possible to place protection less frequently toward the end of a pitch without increasing the fall factor.

The fall factor is an important concept for the lead climber to understand because it provides an estimate of the relative forces that will be generated in a fall. The lead climber—not the belayer—determines the fall factor by deciding when to place protection. Therefore, the leader should keep the fall factor in mind and take steps to minimize it. Place protection as soon as possible after leaving the belay stance, in order to eliminate chances of a fall with the maximum fall factor of two. Then place intermediate protection as the opportunity arises while you climb. You can roughly estimate the potential fall factor at different points during the lead, to help in deciding when to place more protection. Just remember that a fall near the start of a pitch puts relatively more force on you and the protection, so it generally promotes safety to place more protection near the beginning.

Your belayer has the capability to adjust the belay technique to help accommodate the fall factor and minimize the effects of the fall on you and the climbing system. However, if you allow too much friction to develop in the climbing system or lead out the full length of the rope, the belayer will not be able to dynamically feed out rope to reduce the fall forces. This can create a static belay and cause the actual fall forces experienced by the leader to be higher.

SELECTING A PLACEMENT

As you lead a pitch, moving up from the belay station or from the last piece of protection, you'll reach a point where you would like to put in another piece—either because you want the extra protection at that point, or because a good opportunity for a placement presents itself. Find a stance for yourself that is secure and comfortable as possible. It can take some time to put in a good placement, so you need a stance where you won't slip off or become dangerously tired.

If there's no good stance, you're stuck with some unpleasant options: downclimb and ask the belayer to lead the pitch; hang on desperately and hope to get in a placement before arms or legs give out; or charge on to the next available placement point. This unhappy situation usually can be avoided by planning ahead and placing protection before it's urgently needed. When such a situation does develop, however, don't panic. Make a decision and stick with it. Surprisingly often, the correct decision is to continue without protection to the next possible placement.

When you find a good stance, however, go ahead with the protection placement. Sometimes you'll be faced with a choice between two or more usable cracks for placing chocks. It's tempting to always place the largest possible chock, but which one you use should depend on considering several factors. Which placement would be the strongest? What size chocks should be conserved for use higher on the pitch? Which placement will be easiest for the second climber to remove? Choose your placement after thinking through all the consequences of your choice.

ATTACHING THE ROPE TO THE PROTECTION

The normal method of attaching the rope to any piece of artificial protection is very simple and very important. A runner clipped by a carabiner to the artificial protection is also clipped by another carabiner to the rope. The finished chain of protection is this: a piece of protection, a carabiner, a runner, another carabiner, the rope (fig. 10-40a).



Fig. 10–40. Attaching the rope to the protection: a, attaching the rope to a piece of artificial protection (artificial protection, carabiner, runner, carabiner, rope); b, attaching the rope to natural protection (natural protection, runner, carabiner, rope).

With natural protection, the usual method of attaching the rope is to clip it to a carabiner that is clipped to a runner around the point of natural protection—whether it's a tree, flake, rock horn, or whatever. The finished chain of protection is: the point of natural protection, a runner, a carabiner, the rope (fig. 10-40b).

These standard methods of extending the protection point with a runner have two critical virtues: they reduce the effect of rope movement on the protection, and they reduce the drag on the rope as it moves through the climbing system.

Carabiners

The carabiner is a basic tool for connecting parts of the climbing system. A carabiner's reliability in the event of a climber's fall is largely determined by how it is placed and used.

Clip each carabiner so the solid side is against the rock and the gate is down and facing out. This helps ensure that contact with the rock won't force the gate open—resulting in a much weaker carabiner—and makes it easier to clip a runner or rope into the carabiner.

The carabiner should allow the rope to run smoothly without twists or kinks. Avoid chaining carabiners, which can become unclipped if severely twisted. Use locking carabiners, or two carabiners with gates opposed, if there's danger of a carabiner being forced open as the result of a fall.

It's always best to use a carabiner to attach the runner to a chock sling, rather than tying the runner directly to the sling (fig. 10-41a). This is particularly important with wired chocks because the wire cable under load could cut the runner. In an emergency, you can loop a runner through a wire sling (fig. 10-41c). But never attach the runner to a wire sling with a girth hitch (fig. 10-41b).

When a carabiner is clipped directly into protection (usually a bolt or piton), see that the carabiner



Fig. 10–41. Attaching a chock to a runner: a, correct, a carabiner is used to connect the chock to the runner; b, emergency only, the runner is looped through the chock sling; c, incorrect, the runner is girth-hitched to the chock. A cable chock sling could cut the runner under load.

will not bind against the rock. A fall could subject the carabiner to loads from several directions and cause carabiner failure.

Runners

Single runners and the shorter runners known as quick draws are usually used with artificial protection. Double runners are often used to loop around natural protection such as trees and boulders.

You can create a large runner by connecting one runner to another with a girth hitch. Two single runners connected together like this will be about the length of a double runner.

For single runners or quick draws, there's a choice of using sewn or tied runners. Each has certain advantages and disadvantages. Sewn runners are stronger, lighter, less bulky, and have no knot that needs rechecking or retying. However, they cannot be untied and retied around a protection placement. Tied runners are cheaper and have a knot for use as a passive wedging chock in emergencies. They also can be untied and then retied around a tree or other point of protection. But tied runners are bulkier, and the knot (the weakest part of a tied runner) must be checked regularly for looseness.

Energy-absorbing runners can be used to reduce the load on marginal protection. This type of runner has a series of bar tacks designed to rip out as they absorb some of the load in a fall (fig. 10-42).

A safety consideration in using energy-absorbing runners: as each bar tack breaks, it can cause vibration that opens the gate of the attached carabiner. If all the bar tacks break, the final load could be on an open carabiner. (A locking carabiner would be insurance against this problem.) With these special runners, it's important to study the manufacturer's instructions.

KEEPING THE ROPE IN A STRAIGHT LINE

Keeping the rope in roughly a straight line from the belayer to the climber is the best way to reduce rope drag and to guard against unanticipated fall forces. Rope drag is at best an annoyance and at worst can cause a leader fall. Fall forces, if they're not anticipated and planned for, can yank your protection right out of the rock.



Fig. 10–42. Energy-absorbing runner: a, Yates Screamer energy-absorbing runner in use; b, during a fall, the bar tacks will break to absorb energy and help reduce the load on marginal protection.

Reducing rope drag

Rope drag causes all sorts of problems. It can hold a climber back. It can throw a climber off balance. It makes it hard for the leader to pull up enough rope to clip into the next protection. It adds friction to the climbing system, which can increase the force on the top piece of protection in a fall. Also, rope drag can affect how well a belayer responds to a fall, by reducing the ability to provide a dynamic belay.

If the protection placements do not follow a straight line up the pitch and if the rope is clipped directly in to these placements, it will zig-zag up the cliff, causing severe rope drag (fig. 10-43b). That's one main reason to extend runners from protection to rope, allowing the rope to hang straighter and run more freely through the protection system (fig. 10-43a).



Fig. 10–43. Reducing rope drag: a, correct, the protection placements are extended using runners to straighten the rope and reduce rope drag; b, incorrect, the rope was allowed to excessively zig-zag, causing severe rope drag.

There's another problem that can occur here: the increased fall distance when using an extra-long runner. The extension may help keep the rope in a straight line. But it may also add dangerous extra feet to the length of a fall. In such a case, it's sometimes better to accept some rope drag in order to get better security in case of a fall.

If the protection placements happen to be in a straight line, the rope will, of course, be straight and experience less rope drag, even if it's clipped directly to the protection. And by clipping the rope directly to the protection, the distance of any fall is minimized. However, be aware that rope movement might jiggle a chock out of position in this situation. When a rope is clipped directly to bolts or pitons, a short runner (known as a quick draw) or two linked carabiners are normally used to separate the rope from the protection.

Judging the direction of fall forces

The mechanics of placing protection is only one skill a leader must acquire. The leader must also anticipate the direction of forces that will be created by a fall and how they affect the protection placements.

Climbers can be so wrapped up in placing the next piece of protection that they fail to analyze the effect it will have on the entire climbing system. This can create a false sense of security. A protection point may seem solid and secure—but it may not withstand a fall that generates forces in directions not anticipated. It's the responsibility of the lead climber to anticipate and protect against these fall forces.

The dangers of a zig-zagging rope again command our attention. The zig-zag not only puts a dangerous amount of drag on the rope, but also can bring unanticipated forces to bear on the protection. The pieces of protection may have been placed only with the thought of holding a downward pull. Now they are in danger of taking sharp pulls from a number of directions during a fall.

Consider this: when a climber falls, the rope becomes taut in an attempt to form a straight line from the belayer up to the highest protection and then back down to the falling climber. The zig-zag rope tries to go straight—tugging sideways or up or outward on every piece of protection as it does so (fig. 10-44). If the placements are designed to take a pull in only one direction, they may come loose. If the highest piece of protection fails, the whole system could collapse.

During a fall, the top piece of protection is



Fig. 10–44. Judging the direction of fall forces: a, a zig-zagging rope can bring unanticipated fall forces to bear on the protection; b, as the rope tries to straighten, it can pull up or outward on the protection, causing it to fail, especially if it was placed only for a downward pull.



Fig. 10–45. The combined force on the top protection placement during a fall

loaded with the sum of two forces: the impact of the falling climber and the force exerted by the belay in arresting the fall (fig. 10-45). If a fall is taken by a weak piece of protection, it could fail. In this situation, it would be nice to know the protection below could be counted on to stay in place. But with the rope zig-zagging all over the hill, this might not be the case.

As in the problem of rope drag, keeping the rope in a straight line will prevent most of the problems caused by fall forces. Try to make all the protection placements form a straight line back to the belayer, or extend the protection with runners to permit the rope to run straight.

Work for placements that will take some upward or outward pull. Try to ensure that all awkward placements are multidirectional by using natural protection, such as a tree or a tunnel, or by setting up opposing chocks.

Consider ending the pitch early, before the normal belay point, to avoid awkward placements. Two smaller pitches may be better than one long meandering pitch.

GUARDING AGAINST THE ZIPPER EFFECT

The full-scale zipper effect is a dramatic demonstration of the importance of anticipating force directions. It happens most readily where the belay is established away from the base of the climb. The rope runs at a low angle from the belayer to the first piece of protection on the cliff. There, the rope changes direction and goes abruptly upward. In a leader fall, the rope goes taut and tries to run in a straight line from the belayer to the top piece of protection—putting great outward pressure on that bottom chock. If it pulls out, the line of chocks could be yanked out one by one from the bottom up—the zipper effect in action (fig. 10-46).



Fig. 10–46. The zipper effect in action: force on the bottom chock is up and out.

The zipper effect can also occur at placements higher on the pitch. Danger points are found on overhanging and traversing routes.

The zipper effect can be prevented by making the suspect placement multidirectional, using natural protection or opposing vertical chocks. At the bottom of the pitch, another method of prevention is to move the belay to the base of the climb. (This may not be possible, however, because of the danger of falling rock.)

PROTECTING SPECIAL SITUATIONS

Overhangs

That overhang looks intimidating, doesn't it? But for purposes of placing protection, simply pay close attention to the consequences of every placement, just as you've been doing on the rest of the pitch. Keep the rope running as free of the overhang as possible. Extend the rope with runners in order to reduce rope drag, prevent dangerous fall forces (the zipper effect), and keep the rope from being cut by the edge of the overhang (fig. 10-47). On small overhangs, it may be possible to lean out and place protection above it.

Traverses

A lead climber often places protection both before and after a hard move, which guards not only the leader but the climber who follows (fig. 10-48). This is particularly important on traverses, where the second climber could otherwise face a long pendulum fall. In addition to the danger of injury, that kind of fall could leave the second in a tough spot, off route and with no easy way back.

As you lead a diagonal or traversing section, keep in mind the effect each placement could have on a second. Put yourself in the second's shoes and ask, Would I like some extra protection here? If so, place it.

It's possible to belay the second with an extra rope, which may help protect against a pendulum fall and provide better protection than the leader's rope. If you happen to be using the double-rope technique (described later in this chapter), do not clip in both ropes during the traverse so that the follower can receive a belay from above on the free rope.



Fig. 10–47. Placements under overhangs: a, correct, rope runs free of the overhang; b, incorrect, bends cause rope drag and rope could be cut by rock edge during a fall.

PLANNING A FULL CLIMB

WHAT GEAR TO BRING

You're planning a climb. And the question before you is: what should we carry along for protection?

If you're in an established climbing area, no problem. A guidebook will often tell what you need to know before deciding what to carry: type of rock, width of cracks, amount of fixed or natural protection, length and direction of each pitch, difficulty rating—even the precise sizes of chocks needed.

It's a different matter on first ascents or in remote climbing areas. The leader then has much



Fig. 10–48. Protecting a traverse: a, correct, placing protection after a hard move on a traverse can reduce the potential pendulum fall for the second climber; b, incorrect, if the second climber falls on a traverse with inadequate protection, he faces a long pendulum fall.

less information to use in estimating what to take along. Take too much, and the extra weight and equipment make the climbing awkward and harder than necessary. Take too little, and you may be forced to "run it out"—to climb higher above the protection than is safe.

For protection, a leader always packs a selection of chocks, carabiners, and runners. But how many and what kind? These questions can't be answered without knowing some specifics of the climb at hand. However, there are some general considerations in choosing what to bring.

First of all, there's an endless variety of protection available—in the climbing shops. Because of the cost, most climbers own only a moderate number of protection devices. So the two climbers in a typical rock climbing team can really choose only from the protection they own (or borrow). The climbers usually combine their equipment to increase the choices of protection.

Chocks: It's very difficult to know just what size you'll need. Pick sizes and types that fit a wide range and offer more options.

Carabiners: In most cases, each protection placement requires at least two carabiners. Nonlocking carabiners are the norm, though locking carabiners can be used in cases where the gate might be forced open during a fall. Many climbers carry extra carabiners (free carabiners) for contingencies.

Runners: These will be in three lengths: short (quick draws), medium (single runners), and long (double runners). Each point of protection commonly requires one runner. The proper runner at any point is the one that helps the rope stay in as straight a line as possible. Additional runners are needed for belay anchors and unanticipated protection placements.

Chock picks: Sometimes chocks are harder to get out than to put in. That's why each climbing team needs a chock pick—a thin metal tool that helps the second climber remove pieces of protection from a pitch (fig. 10-49). The second climber uses the tool to pry and poke and tap and tug at chocks that are too tightly lodged to come out by hand. Even with the pick, it often takes persistence to remove a chock. Give up if it refuses to budge. Wasting time trying to remove a badly stuck chock only tires you out and delays the climb.



Fig. 10–49. Chock picks, left to right: shelf bracket, piton type, Leeper, skewer type or tent stake, Friend of a Friend.

In addition to chocks, carabiners, runners, and a chock pick, a rock climber often carries a belay device, a chalk bag, and tie-off loops (for such uses as emergency prusiking and for tying off a climber after a fall).

HOW TO CARRY THE GEAR

Once you've decided what gear to take, it must be organized for carrying. The technique of organizing the gear is called racking. The collection of gear is the rack.

Typically, pieces of protection are carried on a gear sling which is slung over the head and under one arm. (Climbing shops sell gear slings, or you can make your own by sewing 2-inch flat webbing into a loop and then rolling and sewing about half of it into a rope-like shape.) Single runners are grouped together and slung over the head—on top of the gear sling and under the opposite arm (fig. 10-50a).

Double runners are too long to handle without a little extra work. A double runner can just be doubled before it goes over your head. An alternative method, which makes it easier to get it when you need it, is to drape the double runner over one shoulder and then clip the two ends together under the opposite arm with a carabiner. Make one twist in the runner before attaching the carabiner, which will eliminate the possibility of the carabiner falling off when the runner is removed. When you need the runner, simply unclip the carabiner from one end and yank; the double runner will pull free.

Typical ways to rack gear

The ideal racking method would permit the leader to place protection efficiently and to climb without awkwardness despite carrying the gear. No such ideal method exists, but a variety of compromises are in use.

One carabiner per chock

In one common method, each chock and each runner gets its own carabiner (fig. 10-50b). In this setup, the gate of each carabiner that carries a chock should be up and toward your body, making it easier to unclip the carabiner from the gear sling.

This method can be very efficient for placing protection. The leader simply places the chock in the rock, clips the chock's carabiner to a runner, and clips the runner's carabiner to the rope. Easy.

Disadvantages of this method are bulkiness and poor weight distribution. The rack tends to be wider and more cumbersome, and there are fewer free carabiners. With a carabiner on each runner, the runners are more weighted and tend to shift, making climbing awkward.

Several chocks on one carabiner

In a second method, pieces of protection are grouped together, each group held by a single carabiner (fig. 10-50c). In this setup, the gate of each carabiner that carries a set of chocks is down and facing away from your body. In this method, single runners don't have carabiners, and extra



Fig. 10–50. Example racking methods: a, a climber carrying runners and a typical rack; b, a racking method where most pieces of protection get their own carabiner; c, a racking method where most pieces of protection are grouped together, each group held by a single carabiner.

carabiners are clipped to the gear sling in chains of two or three.

This second method can make climbing easier because it results in a less bulky rack with better weight distribution. But it also can make it more difficult to place protection. First of all, you have to decide whether to remove a single piece from the group of chocks on a carabiner, or to unclip the carabiner and hold the whole batch of chocks up to the placement.

If you've got a good eye and know what you'll want, you can remove a single chock and place it. But a wrong guess means you've got to put the chock back and try again.

On the other hand, if you unclip the carabiner with its batch of chocks, you can easily try out each chock and place the one that fits. You can then clip the carabiner to the rope for safekeeping while you finish constructing the placement. Finally, unclip the carabiner from the chock and return the carabiner and the unused chocks to the gear sling.

This method of racking gear with several chocks per carabiner usually means slower placements and more equipment handling. Even after placing a chock, the leader must handle two free carabiners and a runner to create the extension to the rope. All this increases the danger that the leader will drop gear or become exhausted. But some climbers feel the increased ease of climbing is worth the extra work.

Other methods

There are other ways to rack gear. Some climbers clip a separate carabiner to each larger chock, but group the smaller chocks so that several will be attached to one carabiner.

Some climbers carry part of the equipment on the gear loops of their harnesses. This helps distribute the weight of the rack, but be sure the gear doesn't hang down far enough to interfere with footwork.

Whatever the method, rack the protection in a systematic order that never varies, so you can find a particular piece in a hurry. The usual order is to start at the front with the smallest wired wedges and to work back with larger-size chocks.

A final point on runners

It's a good idea to carry a couple of runners readily accessible on the harness gear loops in case you can't get to the ones slung under one arm. (If that arm is being used in a jam crack, you won't be able to remove the runners.) You can carry quick draws on the gear loops. To shorten a longer runner so it won't trip you up, you can double it or "chain" (fig. 10-51) the runner and attach it to the



Fig. 10–51. "Chaining" a long runner: a, form a slip knot; b, pull runner through the loop formed by the slip knot; c, repeat this process until the runner is "chained"; d, the final loop can be attached to a carabiner for carrying and to ensure it does not unravel.

harness. When needed, just shake out the chained runner to remove the knots.

PLANNING THE ROUTE

The question of finding your way to the top depends on where you're climbing. If you're sport climbing in a popular spot, just follow the line of fixed pins and bolts, or look up the climb in the guidebook.

There's more involved in finding the route in alpine rock climbing. Even with a guidebook, the description may be sketchy: "Ascend NE Buttress for several hundred feet of moderate climbing." Figure on some planning and routefinding.

Start working out the route as soon as you can see the buttress, face, ridge, or whatever you plan to climb. Look for major features that the line of ascent might follow: crack systems, dihedrals, chimneys, areas of broken rock. Note areas of small trees or bushes that could indicate belay ledges.

Keep an eye out for deceptively tempting lines that lead to broad roofs or blank walls. These may not be visible from near the start of the ascent and if the climbers don't pay attention on the approach, they could climb four or five pitches only to hit a dead end.

Develop a flexible plan for the line of ascent, keeping in mind likely alternatives. Continue planning and routefinding as the actual climb begins, looking for more local features. The general principles are the same: look for natural lines to follow, such as cracks, chimneys and ledges; form a tentative plan for the pitch, perhaps including a place for the first piece of protection and a spot for the next belay station; and note alternative moves in case the planned line leads to a blank wall. Be prepared to look around the corner for easier alternatives not visible from below.

Faced with a choice between pitches of differing difficulty, look at the next pitch before deciding. It's better to climb two moderate pitches than to go for an easy pitch and then be faced with one that exceeds the party's ability.

On the way up, keep track of retreat possibilities in case the climb is aborted, as well as good descent routes from the summit if you don't know of any established route.

PLANNING THE BELAY

It's simple enough: if it's a one-pitch climb, the second belay setup only needs to be directed against a downward pull from the second climber. If it's a multipitch climb, the belay station will also be used to belay the next lead. The climber who sets up this dual-purpose station should try to arrange anchors that will handle the downward pull from the second climber and then, with minimal change, the upward pull of the leader. An efficient belay setup is faster, safer, and leaves more time for climbing.

CLEANING A PITCH

The climber who follows and cleans a pitch should be neat and efficient. A second who is slow and sloppy can drop chocks, allow dangling protection to dangerously interfere with the next move, and hold up the climb while the hardware is untangled at the belay station.

Here are some suggestions for the second:

Start preparing to climb as soon as the leader is off belay. Get out of the belay setup and break down the anchor system (staying clipped into one anchor until you are on belay).

Put on the pack before anything else, except perhaps a hardware sling. Rack all chocks and carabiners on a hardware sling or runner worn over one shoulder and under the opposite arm; then put your runners over the other shoulder and under the other arm. Give the area a last look to make sure nothing is left. Then, once you are on a belay, start climbing.

Remove a chock in reverse order of the way it was placed. If it was slotted down and behind a constriction, remove it by pushing back and up.

Be persistent. Although vigorous pulling or tugging may only set the chock more solidly, it may be necessary to tap or wiggle the chock to free it. Sometimes it takes a lot of work.

Carry a chock pick. You'll need it to tug and push on stubborn placements. Some chock picks also can be used to pull the retraction trigger on a spring-loaded camming device that has ''walked'' back into a crack. Wired chocks can also sometimes be used for that purpose.

Consider leaving the chock behind if it won't budge. Sure, they're expensive. But you can waste too much time and energy on a chock that won't come out.

The second can minimize the risk of dropping gear by using a careful cleaning procedure, which may depend on how you prefer to rack the hardware. In general, cleaning from the rock to the rope is best.

Consider a typical placement consisting of chock-carabiner-runner-carabiner-rope. If your rack features one carabiner on each chock and on each runner, the following cleaning procedure is very efficient. First, remove the chock from the crack. Hold the carabiner that is clipped to the chock, unclip it from the runner, and clip the carabiner-chock combination directly to your gear sling. Then loop the runner over your head, unclip the carabiner from the rope, slip the carabiner-runner combination under one arm and continue climbing.

If your rack features several chocks per carabiner, the following cleaning procedure works well with that method. First, remove the chock from the crack, unclip it, and rack it. Then remove the carabiner from the runner and rack it, then the runner, and finally the carabiner on the rope.

TRANSFERRING EQUIPMENT AT THE TOP OF A PITCH

If the second was neat and efficient in cleaning the pitch, organizing gear as it was removed, the transfer at the belay station will probably go quickly and the fun can resume.

First reconstruct the original leader's rack. The second clips the removed pieces to the leader's rack or hands them to the leader, who can rack them. Caution: don't drop any gear. The second then passes over the removed runners. If the original leader plans to lead the next pitch, the climbers then carefully switch places in the belay setup. This is one way to do it, but if the second is also a competent leader, it's a lot more efficient to swing leads, with the second now taking the lead.

To swing leads, the second usually takes over the leader's rack and runners. The original leader hands the runners to the second (an arm makes a good ''post'' to place the runners on). The rack is next, passed to the second, who places it over the head and under one arm. The runners then go over the head and under the other arm. The new leader checks and adjusts the rack to ensure that everything is ready for the new lead. During this whole procedure, the new leader stays clipped into a separate anchor and, as a backup, can remain on belay.

RUNNING BELAYS

The running belay is an old technique that is still occasionally used for the time it saves. Both climbers tie in and move simultaneously. There is no belayer. The leader places occasional protection and clips the rope through it. The leader also can weave between blocks and spires to take advantage of natural protection. The climbers can reduce rope friction and also stay closer together for communication by carrying some of the rope coiled. In any case, the follower usually carries a few coils in hand to avoid unpleasant jerks when the leader moves fast.

In a fall, the rope—running through the protection—will be held at some point by the weight of the other climber, because the rope is tied to both climbers' harnesses and neither is anchored. The friction of rope running over rock or snow also helps slow the fall. This technique probably only makes the difference between serious injury and total disaster. If either climber falls, both may fall—and a big fall is arrested only by dragging one's partner.

A running belay is not to be confused with moving in coils, which is simply carrying the rope over truly easy ground without using intermediate protection and when any type of belay is unnecessary.

HAULING PACKS

You may decide to shed your pack sometime because you can't fit inside a chimney with it or because the weight would make a pitch too difficult. Then you'll have to haul the pack up after you.

One way to handle this chore is to trail a rope behind you as you climb, tied to the pack down below. This can be either the unneeded end of the climbing rope, if the pitch is short enough, or a separate rope. At the end of the pitch, put in an anchor, haul the pack up hand-over-hand, untie it, and throw the end of the rope down to haul up your partner's pack. If you lack extra rope, have your partner untie from the climbing rope so you can pull it up through the protection and toss the end down for pack hauling.

Ice axes are often hauled separately so there is less danger the pack will snag as it is being pulled up. Tie the ice axe, and any other gear, securely to the rope.

Be sure you have a compelling reason for shedding your pack. If you're doing it only because climbing without it is more fun, think twice. Hauling packs takes valuable time, especially when they get stuck, and they do. It's also hard work that can rob you of precious arm strength. And remember, packs launch rocks.

CLIMBING WITH A PARTY OF THREE

Most rock climbing is done in teams of two, but occasionally a party will end up with three climbers. This works, though it's usually more awkward than climbing with just two.

A three-person team climbing on one rope is limited to pitches of only 70 to 80 feet, just half the rope length. Because many climbs have pitches much longer than this, a three-person team may need to carry two ropes.

With three climbers, the leader climbs while the second belays and the third remains anchored at the belay station. At the top of the pitch, the leader sets up a belay and brings up the second (who can also be belayed from below by the third).

If the pitch follows a straight line up, the second can clean the pitch. But if the line includes some traversing, the protection should stay in for the third climber, to help prevent a pendulum fall. In this situation, the second climber unclips each piece of protection from the first rope and clips it to the second rope. At the top of the pitch, the belay is reset to bring up the third climber. The climbers then may decide to swing leads, with the third climber leading the next pitch. The second generally doesn't do any leading in a party of three.

With all the anchors, ropes, and climbers involved, it can get messy and confusing at the belay station. A lot of time can be taken up setting and resetting belays. Throughout the commotion, it's critical that each of the three climbers be securely anchored. (The belay stations on some tough climbs are so small they couldn't accommodate a three-person team in the first place.)

There are occasional advantages to a three-person team, such as the added help in hauling packs and the availability of an extra rope if a full-length rappel is required. But the disadvantages usually outweigh the advantages.

SPECIAL ROPE TECHNIQUES

Much of this book describes climbing situations in which only a single rope, with a diameter between 10 and 11 millimeters, is used. However, climbers can opt for a system that uses two separate ropes (double-rope technique) instead of a single rope, or another in which two smaller-diameter ropes are used as one to replace the single rope (twin-rope technique).

Double-rope technique

Double-rope technique uses two ropes that serve as independent belay lines. The leader clips each rope into its own protection points on the way up, and a single belayer manages the ropes separately.

Yes, it's complicated, but the system offers some important rewards, such as reduced rope drag and safer traverses. The technique is widely used by British climbers and by an increasing number of climbers everywhere to protect highly technical routes. Double-rope technique usually employs color-coded 9-millimeter ropes.

The leader clips one rope into one series of protection placements and the other rope into another series, the goal being to keep each rope in as straight a line as possible so rope drag is at a minimum (fig. 10-52). The drag is usually less than what it would be on a single rope on the same pitch because the single rope would have to follow a more meandering route. The double ropes typically run in roughly parallel routes, and do not cross. However, if both ropes must be attached to one protection placement, each rope should be attached using a separate carabiner.

The system also helps reduce the worries of the leader who is straining to clip in to the next piece of protection. In single-rope climbing, the rope is slack as the climber pulls up a big hunk of it to clip the next placement. But on a double rope, only the one rope is slack if the belayer is holding the other snug. If the climber falls at this point, the fall will be taken on the nearest placement used by the snug rope, usually making for a shorter fall.

The system has the advantage that both ropes are unlikely to be cut by sharp rock edges or



Fig. 10–52. Double-rope technique: a, correct, the two ropes do not cross but run straight to reduce rope drag; b, incorrect, the two ropes cross and run in a zig-zag, increasing rope drag.



Fig. 10–53. Advantages of double-rope technique: a, using a single rope, the second climber will be exposed to a longer pendulum fall after traversing beyond the first protection; b, using double-rope technique, one rope can utilize the first protection and then be left free to safeguard the second on the traverse; c, off-line protection can be utilized to minimize or eliminate the pendulum risk.

rockfall, or to otherwise fail, at the same time. And it provides two ropes for rappels.

The double ropes can also be used to protect a traverse, particularly one at the start or the middle of a pitch which then goes straight up. In the event of a fall, without a second rope the second climber risks a long pendulum (see Fig. 10-53a). With double ropes, the pendulum can be minimized or avoided. The leader can use one of the ropes for protection on the traverse and leave the other free to protect the second from above (see Fig. 10-53b, 10-53c).

Disadvantages of the double-rope technique? The two ropes weigh more and cost more than the single rope (though often each climber will contribute one rope). The principal problem is that the



belayer's job is more complex as he must handle the movements of two ropes, often letting out slack on one rope while taking it in on the other. For this type of climbing a double slot Sticht belay plate is particularly useful, though other belay techniques can be used. Moreover, the rope has to be constantly monitored to avoid tangling or kinking. With practice these difficulties are soon mastered, and on long and complex rock pitches the advantages vastly outweigh the disadvantages.

Twin-rope technique

Twin-rope technique—with two ropes used as one—features ropes that are 8 to 8.8 millimeters in diameter. Both ropes are clipped into each piece of protection, just as in single rope technique (fig. 10-54).

The twin ropes absorb more energy and thus can withstand more falls than a single rope. Two ropes also are safer running over an edge, as it's unlikely that both ropes would be cut through at the same time. The smaller-diameter ropes are individually easier for the lead climber to handle than a standard single rope.

However, the technique means the belayer has to handle and belay with two ropes, so rope management is tricky. As with the double-rope method, both belayer and leader need a good bit of practice before taking this technique out on the cliffs. And again, twin ropes cost more than a standard single rope.



Fig. 10–54. Twin-rope technique: two small-diameter ropes are used as one, with both attached to each protection placement.

PERSONAL RESPONSIBILITY

ETHICS AND STYLE OF PLACING PROTECTION

Local climbers at each area have usually settled on some basic rules to play by, including standards for placing protection. Some climbing areas are more traditional, encouraging leading and placing protection "from the ground up." Other areas have embraced newer techniques, such as inspecting a route on rappel before climbing it, or placing bolts on rappel. You'll have your own opinions regarding protection, of course, but be sensitive to the climbing ethics and styles developed and demonstrated by local climbers.

ENVIRONMENTAL IMPACT

Everything about mountaineering, including rock climbing, is linked to affection and respect for the environment and consideration for the travelers who come after you. The general rule is the same whether you're hiking, backpacking, alpine mountaineering, or rock climbing: leave the world the way you found it. Specifically on a rock pitch, this means avoiding permanent scarring of trees, rock, and vegetation. If possible, stick to clean climbing, using only chocks for protection.

SAFETY

You know by now that climbing is a balancing act in more ways than one. There's not always one "correct" technique for doing something, and you often need to balance different factors in deciding on a course of action.

Likewise there's no simple set of commandments to memorize and mechanically follow to ensure safety. You may be called on to make life-and-death decisions despite incomplete knowledge, with no clear rule to follow, and without the luxury of being able to consult your favorite expert, even if that expert is on the other end of the rope.

Controlling the risks of climbing is a matter of understanding the reasons that underlie the techniques you've learned, being aware of everything that affects a safe choice, and being able to gauge all the consequences of your actions. And then making a decision as thoughtfully as time allows.

The important thing is that you'll be acting on knowledge, not ignorance; on deep understanding, not superficial rules. A climber who uses techniques without understanding them or who mechanically follows a set of safety rules is not thinking and is a danger to himself and fellow climbers. But learn the principles, make them yours, and you'll be free to do what we all want to do: climb hard, climb high, climb safe.

• 11 •

AID CLIMBING AND PITONCRAFT

Aid climbing is the technique of using gear to support your weight as you climb. It can be as simple as using a bolt as a single handhold, or as complex as climbing an entire route with your full weight on pieces of specialized gear you have placed.

Aid climbing is clearly a sharp departure from free climbing, where weighting the rope or the protective hardware is poor style. Free ascents are one of the goals of the sport of climbing, while aid climbing is a valuable skill for ascending currently ''unfreeable'' routes and for use in emergencies.

As standards of difficulty continue to rise, top climbers are freeing many of the routes originally climbed with aid. But despite the rise in free-climbing standards, there will always be tempting routes that are more difficult still—and so devoid of natural features that a climber will need some artificial assistance.

Skills in aid climbing and pitoncraft can also help overcome unexpected difficulties during normal free climbing. They can provide a way to move safely up or down when weather or accident puts your party in jeopardy. Knowing how to use pitons for aid also helps you in evaluating the soundness of fixed pitons you encounter while free climbing. In winter mountaineering, pitons may be the only protection that will hold in ice-filled cracks.

Any advice to use pitons always comes with a stern caveat: pitons permanently damage the rock. Don't use them unless you must. And don't use them at all on established free routes.

Aid climbing and pitoncraft require skill, judgment, and a lot of practice. To learn both the basics and the many ''tricks'' of the techniques, try to work with an experienced partner, and climb often.

CLEAN AID CLIMBING

Aid climbing takes a lot of gear, but it needn't be damaging to the rock. With all the chocks and camming devices on the market, you now have a better chance to climb routes clean, without putting in a single piton or bolt. The chocks and other devices can be removed without defacing the rock, and the next climber won't even be able to tell you were there.

Aid climbing may still require bolts and pitons, but keep them to a minimum. Pitons (also called pins) chip the rock, especially when you remove them. On popular routes, tiny cracks sometimes evolve into finger or hand cracks after generations of climbers force them to accept pitons.

When climbers make the first ascent of a major wall, they often carry bolts and pins to make it go. Once placed, the best approach is to leave them so future parties can use them without marring the rock further. In general, make clean climbing your goal.

TYPES OF AID CLIMBING

We can roughly categorize aid climbing based on the extent of its use on a particular climb.

Mountaineering alpine aid climbing uses a minimal amount of aid techniques and equipment to overcome short, blank (or extremely difficult) sections of a route that otherwise goes free. This type of climbing requires little or no specialized aid equipment. Usually you'll just use the free-climbing gear you have along.

General aid climbing often uses aid for extended distances, although artificial and free-climbing techniques may be interspersed. Long one-day climbs may involve ''fixing'' the initial pitches—putting up ropes and leaving them in place so they can be climbed quickly with mechanical ascenders the following morning to reach the previous high point.

Big-wall aid climbing involves ascents that take longer than one day to complete, even if the initial pitches are fixed. These climbs include either a hanging bivouac or ledge bivouac and require sack-hauling techniques.

Take a look at Appendix 2, Rating Systems, for a discussion of the various grades of difficulty in aid climbing.

AID CLIMBING EQUIPMENT

Probably more so than in any other type of climbing, you're now in for the true ''nuts and bolts'' of the sport. This section details the range of equipment used in aid climbing, and builds on all the gear and techniques described in Chapter 10. If you're not interested in aid climbing, this section may hold all the drama of a hardware catalog. But if you've become intrigued with the subject, you'll find this material both thorough and fascinating.

BASIC EQUIPMENT FOR CLEAN AID CLIMBING

Clean aid relies heavily on standard free-climbing equipment. You'll simply need more of it.

Chocks and camming devices: Because you'll be setting placements every several feet, a long pitch can require more than 50 assorted chocks and camming devices. The sling attached to each piece should be as short as possible to help you get the maximum elevation gain out of each placement.

Carabiners: While a minimum of 40 free carabiners are needed on an aid rack, it's not unusual to use 80 on a long pitch and more than 100 on a particularly difficult pitch. Many aid climbers prefer oval carabiners rather than D carabiners because ovals minimize the unnerving shifting that occurs when a D takes your weight. Regardless of the shape, you should be able to open the carabiner gate whenever you wish, even while it is holding your weight.

Small nuts: Aid racks include specialty small nuts, beyond those on free-climbing racks. These tapered nuts are often used instead of thin pitons, but they are not as strong. They are designed to support body weight, and may fail if fallen upon.

Two general styles of nuts are available. The first is a smaller version of a normal tapered Stopper. The second style has both horizontal and vertical taper and is more secure in flaring cracks and old pin scars (piton scars).

The heads of small nuts are made from aluminum, brass, or stainless steel. Aluminum and brass bite into the rock and hold better in marginal placements, but steel nuts are less likely to deform and fail if you take a fall on one of them.

Ropes: The tough duty of aid climbing usually requires 11-millimeter or 12-millimeter kernmantle ropes, 165 feet long. The haul line is typically an 11-millimeter or 9-millimeter line which doubles as a backup rope and a second rope for long rappels. If your route entails pendulums or other unusual problems, you may need a third rope.

Hero loops: Very short slings are useful for aid climbing. These tie-off (hero) loops—4 to 6 inches long—are threaded through fixed protection in place of a carabiner. Climbers usually tie their own out of 1/2-inch webbing. You'll use many of them if the route has a lot of fixed bolts or pitons. They are also used to prevent the loss of stacked pieces (described later), and to tie off partially driven pins. Also carry at least six regular-length slings for establishing anchors, extending placements to reduce rope drag, and other normal rock-climbing uses.

Chock picks: Picks used for aid climbing should be sturdy, because you'll often hammer on the pick to tap out lodged nuts.

Gloves: Over and above their value for belaying and rappelling, gloves protect your hands while "jugging" (ascending the climbing rope with mechanical ascenders) and removing protection placements.

Rock shoes: If the route involves only a small amount of aid, normal free-climbing rock shoes perform best. If sustained aid is anticipated, boots with greater sole rigidity provide a better working platform and more comfort. Some new boots on the market provide a rigid arch support and good torsional rigidity for aid climbing, yet have a flexible toe and a sole of soft friction rubber for good free-climbing capabilities.

Energy-absorbing slings: These slings increase security when climbing above placements of questionable strength. In a fall, the slings limit the shock delivered to the protection. Their use, however, limits the amount of elevation gained from the placements to which they are attached.

UNIVERSAL AID-CLIMBING EQUIPMENT

In addition to equipment normally used in free climbing, you will need a selection of gear that is used for both clean aid climbing and for aid that involves placing pins.

Etriers: These ladder-like slings (fig. 11-1) allow climbers to step up from one placement to the next when they are clipped to a chock, piton, or other aid piece. Consider the intended use when



Fig. 11–1. Types of etriers: a, sewn; b, tied; c, the frost knot. Tied etriers require twice their finished length plus 10 inches for each step (overhand knot) and the frost knot. A 60-inch etrier with five steps (four overhand knots) takes 170 inches of runner.



Fig. 11–2. Tied daisy chain

making or buying etriers. For alpine climbs, minimize weight by using a single pair of etriers made of 9/16-inch or 11/16-inch webbing. For most aid climbing, four- or five-step etriers made of 1-inch webbing are standard. Etriers should be long enough to let you step smoothly from the top step of one to the bottom step of another that has been clipped into a piece at arm's reach above.

Tying your own etriers lets you tailor their size to your own. However, commercially made or home-sewn etriers are preferred for routes with extensive aid because they remain open for foot placement when weighted. Metal-rung etriers have the same advantage and are less prone to blow in the wind, but they can cause more pain if they do hit you or your partner.

Some climbers use two pairs of etriers while aid climbing; others use a single pair—it depends on the nature of the route and on personal preference. Likewise, some climbers prefer to attach a short grab sling to the carabiner loop of their etriers.

Daisy chains are tied or sewn slings with a loop—formed by a knot or stitching—every 3 to 6 inches (fig. 11-2). The proper length for you is a daisy chain that, when attached to your harness, reaches as far as your raised hand. Attach a carabiner to every loop (or every other loop) in the chain so you can quickly clip into an aid placement and rest on your harness.

Carry a second daisy chain, without carabiners in each loop, for other purposes, such as attaching yourself to your ascenders while jugging or for preventing loss of etriers if a hook placement fails.

Fifi hooks function somewhat like daisy chains but are attached to your harness with a sling only 2 to 6 inches long (fig. 11-3). You can quickly clip the hook into an aid piece, allowing you to rest on your harness. Be careful. If you release the tension or change the angle, it could come unhooked. Aid climbers usually carry one fifi hook for use on bolt ladders and fixed pitches.



Fig. 11–3. Fifi hook with sling

A double rack, with equipment slings on both sides of the body, distributes the weight of the hardware (fig. 11-4). It improves your balance and



Fig. 11–4. Double rack

comfort and reduces the neck strain caused by a single rack. If it's built right, a double rack can also serve as a chest harness as you jug up a rope with mechanical ascenders. Some climbers carry a single rack in addition, for their free carabiners or as a supplemental free-climbing rack.



Fig. 11–5. Two-point belay seat; note the anchored climbing rope.

A belay seat with two- or three-point attachment is a great creature-comfort during hanging belays (fig. 11-5). One urgent warning: never let the belay seat be your sole means of attaching to an anchor. Clip in from your harness to the anchor with the climbing rope as usual—and then set up the belay seat for comfort.

Mechanical ascenders (fig. 11-6) serve the same function as prusik knots but are stronger, safer, faster, and less tiring. The devices are a requirement for sack hauling on big walls.

All ascenders employ a cam, allowing the ascender to slide freely in one direction on a rope but to grip tight when pulled in the opposite direction. They also have a trigger or locking mechanism to keep them from accidentally coming off the rope. Some triggers are difficult to release, decreasing the chance of accidental removal but making it harder to get them off when you want to. If your ascenders are made of cast aluminum, back up their frames with webbing to reduce the danger created should they break.

If you plan to use ascenders for cold-weather climbing, look for a pair with openings large enough to accommodate heavily gloved hands. Carabiner holes at the top and the bottom of the ascender come in handy for a number of purposes, such as sack hauling. If the ascender doesn't have



Fig. 11–6. Mechanical ascender with backup sling; ascender is attached in preparation for diagonal ascent.

these holes, you'll have to attach slings for clip-in points.

Piton hammers have a flat striking surface for cleaning and driving pitons, and a blunt pick for prying out protection, cleaning dirty cracks, and placing malleable pieces (fig. 11-7). Hammer shafts should be long enough to forcefully drive pins, and short enough to fit comfortably in a belt holster. The shafts should also be sturdy and taped for protection. A carabiner hole in the head is useful for cleaning pins and malleable pieces.

Attach a sling to your hammer that allows full arm extension when the hammer is in use (fig. 11-8). If you happen to drop the hammer, it will just hang below your feet on the sling. Be sure to check the sling regularly for wear.

Hooks come in many shapes and forms, and are most commonly used to grip ledges or small holes (fig. 11-9). With etriers attached to the hook, you have a rather delicate placement for moving upward. Hooks should be made of chrome-moly steel (for strength), and the non-hook end should be wider and curved (for stability). Attach slings to the bottom of your hooks with a girth hitch, positioned so that when the sling is weighted, the "legs" (lower end) of the hook are pulled into the



Fig. 11–7. Piton hammer styles: a, Mjollnir; b, Chouinard; c, less adequate.



Fig. 11–8. Hammer sling properly used



Fig. 11–9. Hook types: a, sky hook; b, Logan hook; c, bat hook.



Fig. 11–10. Hangers: a, wire; b, wire hanger on a bolt; c, keyhole; d, regular hanger on a bolt.

rock. To accomplish this, the sling should hang from the rock side of the hook.

Sky hooks look almost like giant fish hooks and are useful for small flakes and ledges. Greater stability is achieved on some routes if the tip of the hook is filed to a point, which can be set into small holes drilled at the back of tiny ledges. Fish hooks, or ring claws, are like large sky hooks and are used to grip larger flakes and ledges. Logan hooks are L-shaped: the wide style is stable on tiny ledges and flakes, and the narrow style can be used in shallow pockets. Bat hooks are basically a narrow-style Logan hook with a pointed blade, allowing their use in shallow 1/4-inch holes drilled for their use.

Wire hangers (fig. 11-10a and b) are loops of wire 1/8 inch or 3/32 inch in diameter, with a slider to cinch the wire tight over bolt studs and rivets (basically, bolts with a wide head). Small tapered chocks (Stoppers) with wire slings can also be used for this purpose, with the chock itself acting as the slider to tighten the wire against the bolt stud. However, because the chocks have a longer wire loop than the wire hangers, you won't get as much elevation gain from them.

Regular hangers and keyhole hangers serve a similar function to the wire hangers, but are shaped pieces of metal rather than wire loops (fig. 11-10c and d). They are useful, especially at belay anchors and for fixed bolts that have no hangers. Keyhole hangers have the metal between the bolt hole and carabiner hole filed out to allow placement over rivets and buttonhead bolts.

IRONMONGERY FOR FULL AID CLIMBING

To master the full range of aid-climbing techniques, climbers must have a knowledge of pitons and bolts.

Pitons

Modern pitons—or pins—are made of chromemoly (hard) steel. Rather than molding to cracks like the malleable pitons of old, they mold the crack to their form. Because of the damage that pitons cause and because of improvements in clean-climbing hardware, piton use has declined greatly. They are still important, however, on overhanging rock and very thin cracks. For winter mountaineering, when cracks are filled with ice, they may offer the only viable means of protection. To fit the diverse cracks encountered on rock walls, pitons vary tremendously in size and shape (fig. 11-11).

The Realized Ultimate Reality Piton (RURP) is the smallest piton, a postage-stamp-sized, hatchet-shaped pin used in incipient cracks. It will usually support only body weight and derives what little strength it has by minimizing the leverage between the piton and carabiner supporting your etriers. Some styles come with offset sides for use in corners.

Birdbeaks are similar to RURPs but have a longer arm for attaching a carabiner or sling. Generally they are easier to place and remove.

Knifeblades are long thin pitons that have two eyes—one at the end of the blade and a second in the offset portion of the pin. They come in different lengths and in thicknesses between 1/8 inch and 3/16 inch, and they are commonly used to fit many cracks that are too thin for tiny nuts.

Lost arrows are similar to knifeblades but have a single eye which is centered and set perpendicular to the end of the blade. These too are commonly used pitons that come in several lengths and thicknesses (5/32 to 3/8 inch). They are very good in horizontal cracks.

Angles are pitons formed into a "V." The V varies in height from 1/4 inch to 1 1/2 inches (smaller ones are most popular). Their strength is derived from the metal's resistance to bending and spreading. Angles and other large pitons have largely been replaced by modern free-climbing hardware.

Leeper Z pitons obtain their thickness through their Z profile as opposed to the V profile of an angle. These pitons are very solid and work well for stacking because of their short length, useful in bottoming cracks.

Bongs are large angle pitons that vary from 2 to 6 inches in width. In addition to their use as pitons, they can double as large chocks. Camming devices like Friends have largely replaced bongs.

Sawed-off pins are handy on routes that have been heavily climbed using pitons, leaving shallow pin scars. Several 3/4-inch and 1-inch angles with a few inches cut off the end are useful for shallow placements.

Malleable hardware (bashies)

Malleable hardware (fig. 11-12) is designed to hold weight by melding the soft head of the placement to the irregularities of the rock. The security



Fig. 11–11. Piton (pin) types: a, lost arrow; b, knifeblade; c, shallow angle; d, Leeper Z; e, angle; f, large angle; g, bong; h, birdbeak; i, RURP.



Fig. 11–12. Malleable head types: a, copperhead; b, aluma-head; c, circlehead.

of these bashies varies greatly, and it is difficult to gauge their strength, making them last-resort equipment.

Copperheads (fig. 11-12a) have a swage of copper attached to one end of a short cable that has a loop at the other end. They are placed by pounding the copper head into an irregularity in the rock. They tend to form well and are more durable than similar pieces with aluminum heads (aluma-heads).

Aluma-heads (fig. 11-12b) are not as tough as copperheads but are more malleable, so they tend to be used for the larger sizes, while the smaller heads are usually copper.

Circleheads (fig. 11-12c) consist of a wire loop with an extra copper swage on the loop, which is pounded into the rock like a copperhead. They are used in horizontal cracks.

Bolts

Chapter 10 includes a section on the use of existing bolts found on climbing routes. Bolts permanently scar the rock and alter the style of a climb, and very serious consideration should be given before placing one. Proper bolt placement is a special skill, beyond the scope of this book. Bolt placement is best left to the skill and judgment of very experienced climbers.

BIG-WALL EQUIPMENT

Climbers undertaking a big wall have other specialized equipment to consider.

Pulleys will be required to ease the chore of sack hauling. They receive much abuse, so they must be durable. Pulleys with bearings and larger wheels operate more smoothly.

Haul bags carry your clothing, water, food, sleeping bag, and other non-climbing paraphernalia. A good haul bag should have adequate cargo capacity, a solid haul suspension, durable fabric, an absence of snag points, and a removable backpacking harness system. Duffels can be converted into haul sacks by reinforcing the wear areas. A top cap to the haul bag is a good idea to protect the knot connecting the sack to the haul line and help reduce snagging problems while hauling.

Cheater sticks allow you to clip a carabiner into a piece of hardware beyond your reach. Although rarely needed, they are often used to avoid "top stepping" in etriers. Cheater sticks should have a means of holding a carabiner solidly while you clip in with your arm fully extended.

Knee pads protect your knees, which are regularly in contact with the rock during aid climbing. Pads should be comfortable and allow good circulation.

Portaledges or hammocks: Portaledges, which are lightweight cots, offer greater comfort from a single point of suspension than hammocks. Unfortunately, they are much heavier and bulkier. As with belay seats, climbers must *always* be anchored to the rock when using this equipment.

If you take on a big wall, safeguard important equipment with tie-in loops to attach anything you might drop. Bring gear that will get you through the worst possible weather, because there's not likely to be any easy way to retreat. Be sure your equipment is durable and beef up any item that could fail, such as water containers. Select only the sturdiest, and reinforce them with duct tape.

AID PLACEMENTS

The main rule for aid climbing is to place each aid piece as high as possible. If you make placements at 5-foot rather than 4-foot intervals, over the course of a 160-foot pitch you'll save eight placements, many more carabiners, and much time.

Most of the techniques for placing free-climbing protection apply to aid climbing. For aid climbing, if possible, you'll shorten the slings to your pieces and often use hero loops on fixed protection rather than clipping in directly with a carabiner.

Placing small nuts during an aid climb is similar to placing larger ones on a free climb. But because aid nuts take the weight of the lead climber and because they may be smaller than the chock pick, they can be difficult to remove. If you place small nuts near the outside of the crack, they will be easier to remove and there will be less danger of damaging them in the process. Test small nuts gently before committing your weight to them.

Fixed pins, bolts, or rivets must be evaluated before use (see Chapter 10). If you decide to use a fixed piece, thread a hero loop through its eye and clip a single carabiner into the two ends of the loop. This saves a carabiner. Note: use a direct carabiner clip-in every three or four pieces as a backup. The hero-looped pieces are not as safe for stopping a fall because of the danger the loop could be cut by the edge of the metal eye. It's also wise to carry a few bolt hangers and nuts (in both 1/4-inch and 3/8-inch sizes) for bolts with missing or damaged hangers.

PITON PLACEMENT

Here are some basic guidelines for the sound placement of pitons (pins) (fig. 11-13):

- Horizontal placement of pins is generally more secure than vertical placement because rotation is reduced or eliminated.
- Ideally, the eye should point downward.



Fig. 11–13. Piton placements and problems

- As with chocks, place pins in locally wider portions of a crack. If the crack is thinner below and above the pin, the pin will be supported when it has to take a climber's weight.
- A properly sized pin can be placed one-half to two-thirds of the way by hand. The remainder of the pin is hammered in place. Select the correct pin to fit the crack. Don't try to make the crack fit the pin; this practice causes needless destruction of the rock.
- A sound piton rings with a higher-pitched "ping" with each strike of the hammer. After the pin is driven, tap it to test for rotation. Rotation indicates the pin is not biting the rock. Replace such pins with a larger size.
- Knowing just how much to hammer a piton is a matter of touch and experience. Excessive hammering wastes energy, makes it harder for the second to remove the piton, and needlessly damages the rock. Under-driving a piton, however, increases the risk of it pulling out. If several pins are under-driven, the failure of one could result in a long fall as the series of pins zippers out.
- When possible, avoid placing a pin in a three-way corner. Such placements are often impossible to clean because the pin cannot be tapped back and forth for removal. Just leave it as a fixed pin.
- If the position of the piton causes the connecting carabiner to extend over an edge, add a hero loop to the piece (fig. 11-14). This prevents loading the carabiner across its sides.
- On overhangs, place pins with some horizontal orientation when possible (fig. 11-15). This reduces the odds of total failure should the pin shift when weighted.
- Place knifeblades in vertical cracks with the offset eye down.
- When placing angles, keep the three points of the V in contact with the rock (fig. 11-16). The back (point of the V) *always* must contact one wall, while the edges (two tips of the V) contact the opposing wall. In a horizontal crack, put the back of the angle up and the edges down.
- Bongs (fig. 11-17), being made of aluminum, are quite fragile, so pound them as little as possible. Bongs are often placed as chockstones, and you can add a sling to a bong before using it that way.



Fig. 11–14. Safely extending a piton; right figure eliminates side loading the carabiner.

- Expanding cracks present problems for pins because as subsequent pins are placed, lower ones loosen. When possible, use chocks in such situations, because they minimize flake expansion. If pins must be used, try to work with long minimum-taper pins placed lightly in natural slots, to minimize expansion of the rock flake.
- In shallow cracks and flutings, a piton may be driven over a chock. The chock creates a second "wall" against which the pin wedges. Because the chock would fall and be lost if the pin failed, attach a "keeper" sling to the chock and clip it into the



Fig. 11–15. Overhang piton placement



Fig. 11–16. Proper placements for angle pitons



Fig. 11–18. Sawed-off piton driven over a Stopper; note the non–load-bearing keeper sling on the Stopper.

sling or carabiner of the load-bearing pin. The keeper sling must not bear any weight (fig. 11-18).

- When a pin ''bottoms out'' in a crack (that is, cannot be driven in all the way), stop hammering, to avoid loosening it. The piton must be tied off around the shaft at the point where it emerges from the rock. A hero loop tied to the piton with a girth hitch or clove hitch supports your weight and re-



Fig. 11–17. Bong placements: a, driven and tied off through lightening holes; b and c, girth-hitched for use as a large chock.

duces the levering action on the pin (fig. 11-19). Bongs can be tied off through their lightening holes. Loop a longer keeper sling (or a second carabiner) through the eye of the pin and clip it into the hero loop or hero-loop carabiner. The keeper sling doesn't bear weight, but will catch your pin if it pops.



Fig. 11–19. Tied-off piton; note the use of a keeper sling through the piton eye.

STACKING AND NESTING

When no single pin or chock fits the crack at hand, aid climbing gets very creative. Whether you've run out of the proper-sized pieces or are facing a shallow flaring crack, it's time to improvise by stacking or nesting your hardware in whatever combination works (fig. 11-20).



Fig. 11–20. Examples of pitons stacked and nested (some keeper slings omitted for clarity); inset, angles stacked over each other.

Blades are nested back to back and are usually driven together. If a third blade is necessary, the first two are inserted by hand, and then the third is driven in between.

Some disagreement exists about the best way to stack angles. Most climbers stack them by keeping the backs of both angles against the rock, but any combination will work. Try to avoid stacking angles by simply placing one over the other, as these may be very hard to separate once removed. Leeper Z pitons are especially useful in stacking.

It may be possible to use a camming combination of a pin and a chock—or a pin and a wire hanger—in very difficult situations (fig. 11-21). The concept relies on the camming force exerted by the chock or wire on the back of the pin. The chock or wire loop is partially inserted into the crack. Then, the pin is inserted to anchor the chock or wire and to create an artificial wall against which the chock or wire can cam. You can often achieve a solid aid placement this way with minimal use of the hammer. Note, however, that wires used this way wear quickly.

These special combinations present another situation that requires non-load-bearing keeper slings to catch any pitons should the placement fail.

HOOK PLACEMENT AND USE

Before placing a hook, clip an etrier to it. Also make sure to connect a sling (or daisy chain) between the etrier's carabiner and your harness. The



Fig. 11–21. Camming combinations: a, piton and chock; b, piton and wire hanger (keeper sling omitted for clarity).

sling will prevent the loss of your gear if the hook pops off its purchase.

Now set the hook on the ledge, flake, or hole where it will be used. Test it gently before applying full body weight (or gently ''ooze'' onto the hook). Avoid standing with your face directly in front of the hook because it could pop out with a good deal of force.

If the hook is used in a shallow bolt hole, a very slight tap to set the point is sometimes useful. However, this practice increases the possibility the hook will pop out. It also erodes the existing hole, and eventually a bolt will need to be placed.

MALLEABLE PLACEMENTS

Because you often can't tell how secure they are, do not use malleable heads unless you're dealing with a pocket or flare where other protection just won't work.

Copperheads, aluma-heads, and circleheads take more practice to place than other types of aid and require some specialized tools. The hammer pick works for setting large heads, but small heads require a striking tool like a blunt chisel or, in a pinch, a lost arrow.

Figure 11-22 illustrates the following procedure for placing a head:

1. Place it. Insert a head as you would a chock—in a narrowing portion of a flare or seam.
2. ''X'' it. Pound it in using angled strokes that form an X pattern on the head.
3. Paste it. Now pound the right and left sides to ''pin'' the head.
4. Rotate it. Hit the bottom and top to see if the head rotates. If so, X it and paste it again.
5. Sniff it. If the head emits a metallic odor, it is under-driven or over-driven; do not use it. The smell arises from the cutting or cracking of the head rather than its molding to the rock.
6. Use it. Heads are used like any other aid piece—but remember their inescapable weakness. Inspection cannot guarantee the molding of the head to the rock. Some heads may hold a short fall, others will just support body weight, and others might fail. All malleable-head placements are suspect, and an acceptance of this fact is inherent in their use.



Fig. 11–22. Placing a malleable piece: a, place it; b, ''X'' it; c, paste it; d, rotate test it.

BASIC AID TECHNIQUES

Before starting up any aid pitch, study the terrain and make a plan. Determine the best rest spots, figure how to minimize rope drag, plan what gear you'll need and what you can leave for the second to carry, spot any obstructions that might plague sack hauling, and decide whether to save certain sizes of aid pieces for the end of the pitch.

Then gear up for the pitch. Place pitons (between three and six to a carabiner) on one side with the larger pieces to the rear. Place chocks and other gear for clean aid climbing on the other side, again with the larger pieces to the rear. Balance the



Fig. 11–23. The basic sequence (some equipment omitted for clarity): a, climb high; b, place piece; c, clip etrier to carabiner on higher piece; d, test, move onto new placement, remove lower etriers; e, clip rope into lower carabiner on new piece and clip in daisy chain if desired.

weight with free carabiners racked in groups of four (two pairs). Short slings are best racked (several to a carabiner) and clipped to an easily accessible part of your harness. Finally, check that the hammer is accessible, with its sling untangled.

THE BASIC SEQUENCE

The basic aid sequence (fig. 11-23) is the same whether you are starting from the ground, a comfortable free stance, or the top step of your etriers:

1. Look and feel the terrain above and select an aid piece to place at the highest spot within reach (fig. 11-23a).
2. Place the piece (fig. 11-23b).
3. Clip in a free carabiner. Some climbers prefer to clip in a two-carabiner chain (fig. 11-23c);



the second carabiner will later take the climbing rope. Other climbers feel two carabiners get in the way at this point. If you are moving onto a pin, first attach a hero loop to the pin, and then clip a carabiner to the loop.

4. If the aid piece you are currently weighting is questionable, you may want to clip the rope to the second carabiner of the higher piece if you are positive the higher placement is solid. Otherwise, the rope is not clipped into the higher piece yet.
5. Clip your free etrier(s) to the carabiner on the higher piece (the higher of the two carabiners if you used two) (fig. 11-23c). If moving onto a pin, clip the etrier(s) directly into the hero loop.
6. Test the new piece with a gentle, one-footed hop (the other foot is kept in an etrier on the lower piece). If the new piece is questionable, you may decide to avoid the test and simply "ooze" onto the new placement, applying your weight as gradually and smoothly as possible. Warn your belayer when you are about to test or move onto a dubious placement.
7. Move onto the higher etrier(s) (fig.11-23d). Clip the daisy chain into the new piece while in the lower step, if you wish.
8. Remove the lower etrier(s) (fig. 11-23d). For extended aid climbing, you will normally carry two pairs of etriers, so now you will remove the lower pair and clip it to your harness. (If you are climbing with just a single pair of etriers, remove the lower etrier and clip it to the highest aid piece.) Climb up the etriers until the daisy chain (or fifi hook) can be clipped in close to the new piece, if you wish.
9. Add a second carabiner (in chain fashion) to the new piece and clip in the rope. If you initially clipped two carabiners to the piece, clip the rope into the lower carabiner (fig. 11-23d).
10. Study the area immediately above to determine likely spots for the next placement. Then climb as high as possible, reclip the daisy if desired, and begin the process anew. Note: how high you climb in your etriers depends on the terrain, but ideally you want to place the new piece from the top step.

Top stepping

Moving onto the top step of your etriers can be unnerving, but the ability to do so greatly improves the efficiency of aid climbing. The process is simple on low-angle rock where the top steps are used like any other foothold, and the hands provide balance.

Vertical and overhanging rock makes top stepping difficult because your center of gravity moves away from the rock *and* above the point where the etriers are clipped to the aid placement. If the rock offers any features, your hands may provide the balance. If the rock is blank, keep your weight on your feet while leaning back and applying tension to the daisy chain between your harness and your aid placement. That tension provides the means of balancing yourself (fig. 11-24).

Special considerations

Problems encountered while aid climbing may cause you to add variations to the basic sequence. As in free climbing, rope drag can become a problem. Use long slings to keep the rope running straight. Add the slings after you have moved to the next higher piece so that you obtain the maximum gain out of each placement.

You may also realize you're short of certain-sized pieces and that you will need to reuse these sizes. As you move onto a higher placement, you may opt to pull the piece you were just using and save it for future use. As a general rule, however, leave at least every other piece as your protection against a fall.

RESTING

Don't wear yourself out. Climb in a relaxed fashion and take rests as often as necessary to conserve your strength or plot the next series of moves.

Here's a quick and easy rest: with each foot in separate etriers and one foot one step below the other, bend the knee of the higher leg and bring



Fig. 11–24. Top stepping; note the use of daisy-chain tension.

that foot under you. Most of your weight rests over the bent leg. The outstretched leg takes minimal weight but maintains balance (fig. 11-25).

You can also clip your daisy chain or fifi hook into the piece supporting you and rest in your harness.

Once the climbing rope is clipped into the supporting piece, you can also ask the belayer for tension and rest on the climbing rope. This is not an efficient method, however, due to stretch in the



Fig. 11–25. Resting on a foot

rope. It also places unnecessary strain on the belay system.

Finally, you can often find relaxing stances in your etriers. Generally, the greatest stability is obtained with the heels together and the toes spread apart against the rock.

SWITCHING BETWEEN AID AND FREE CLIMBING

Timing is the key problem in switching between the techniques of aid and free climbing.

From free to aid: Free climbers must remember that the switch to aid requires some preparation. Begin the aid sequence before stretching yourself to the limit of your ability. This is easy if you know you will be changing to aid, but problems arise if you are not expecting to use aid but suddenly need it. Finding yourself in this bind, you can improvise etriers by interconnecting several slings and aid your way over the blank area. Such creativity is particularly important when climbing in a remote alpine environment. The climb's style may be damaged, but your body will be spared.

From aid to free: To free-climb a few moves during an aid pitch, simply clip the etriers to the back of your harness, and then make the moves. It is best to continue climbing on aid until you can comfortably switch to free techniques. If the change is made too early, you may have trouble retrieving your etriers from the last aid placement.

When beginning a longer section of free climbing, clip etriers, daisies, and so forth to your harness and be sure they will not hinder your movement. This may entail removing most of your aid implements and hanging them behind you.

TENSION TRAVERSES AND PENDULUMS

These techniques allow you to move horizontally across blank sections of a wall that would normally require placement of bolts.

Tension traverses are the simpler technique, useful for short traverses. The leader takes tension from the belayer, then leans to the side and uses friction on small holds to work sideways.

Pendulums let you cross wider blank sections without bolts but often require more ropes and pose special problems for the second climber. Start by placing a bombproof anchor at the top of the planned pendulum. The equipment used for this anchor cannot be retrieved unless it is possible to come back to it from above.

Next, you'll be lowered by the belayer (or rappel while on belay) until you have enough rope to run back and forth across the rock and swing into a new crack system. If a rappel is used for the pendulum, an extra rope will be required. When being lowered by the belayer, it is best to be lowered too little than too much, because if you're too low it may be very difficult to correct the error.

Once in the new crack system, climb as high as safety allows before clipping your belayed climbing rope into aid pieces for protection. The higher you get, the easier and safer it will be for your belayer, who will second the pendulum.

See the section later in this chapter on seconding pendulums for more details and an illustration of pendulum technique.

OVERHANGS

Before leading an overhang, check that you have enough equipment for the job. It may be impossible to obtain more gear later from the second climber. Keep your ascenders handy, because if a piece pulls and you end up hanging, you'll need ascenders to climb back up to your last secure piece. Also, check that your belayer is securely anchored, or you could both end up hanging free in the event of a fall.

Balance will be difficult as you scale an overhang because you can't effectively place your feet against the rock. Use of a daisy chain or fifi hook, however, allows you to hang from the harness and achieve a stable position. As an overhang approaches the horizontal, you can achieve greater balance still by clipping a sling from a chest harness to the supporting aid piece (fig. 11-26).

Despite the difference in balance, the basic sequence for aiding over a roof is the same as described earlier, but you may find it more comfortable to sit with your legs through the middle



Fig. 11–26. Aiding under a roof; note the use of a chest harness for support, and the availability of ascenders.

step of the etriers rather than standing in the bottom steps. Expect to experience some swinging. Finally, because your belayer will probably aid over the overhang rather than use ascenders, consider the length of your partner's reach when making your placements.

Rope drag is a common side effect of overhangs, but liberal use of longer slings will help. You may also want to pull along a second belay rope and start climbing on it after clearing the lip of the overhang.

Finally, try to relax when working out over a big roof. Have confidence in your pieces. Clutching at them won't keep them in place but will drain your strength.

HANGING BELAYS

Upon reaching the end of the pitch, the leader establishes an anchor as a new belay station (fig. 11-27). Place this anchor, when possible, to the side of the route (especially if you are sack hauling) so that your second can easily climb through. Also try to place at least one aid piece at the start of the next pitch to give the second a stance while changing leads.

When establishing your anchor, make sure *all* anchor points (including the haul anchor) are connected to *all* other anchor points. If an existing anchor system is in place do not simply place a sling over the system. This is an easy mistake to make and experienced climbers have paid for this error with their lives. Clip in, instead, in such a way that should any portion of the anchor fail, your attachment won't slide off the failed end.

Similarly, complete anchor systems have failed when a separate haul anchor, which was not interconnected with the main anchor, failed. In these cases the force generated by the falling haul sack overloaded the main anchor.

Once you are clipped in, anchor the climbing

Fig. 11–27. Hanging-belay sequence: a, leader establishes anchor; b, with climbing rope anchored and the haul system set, the second frees the haul sack (note that the first piece of the next pitch is set); c, while the second "jugs," the leader hauls the sack; d, the haul sack is anchored, and the second moves onto the first piece of the next pitch; e, after re-racking, the new leader begins to lead.





d



e

rope so that the second can ascend it as a fixed line. Now prepare the hauling system, if you are hauling. Remove the aid rack and use it as the counterweight for the hauling system. Inform the second to free the haul sack so that you can hoist it while the second ascends the fixed climbing rope.

After the hauling is completed (or after the climbing rope was fixed if you are not hauling), establish your belay seat, get comfortable, and prepare for the exchange of leads. Sort the rack, organize the ropes, prepare your belay system, and so forth.

TYROLEAN TRAVERSES

Tyrolean traverses are most often used to return to a main wall after ascending a detached pillar. Ropes are strung between the main wall and the top of the pillar, allowing you to traverse through the air, attached to the rope.

You can establish a Tyrolean traverse like this:

1. After setting up a bombproof anchor on the main wall—one that can take both a horizontal and vertical pull—rappel on two ropes to the saddle between the main wall and the pinnacle. (You can use just one rope for the rappel if the traverse will be short enough.) Do not pull down the rappel ropes. If it takes more than one rappel to reach the saddle, you'll have to tie a light line to the two ends of the main rappel rope to give you a way to retrieve the ends once you're on top of the pinnacle.
2. Climb the pinnacle using an additional climbing rope. The second climber brings up the free ends of the rappel ropes.
3. Once atop the pinnacle, the free ends of the rappel ropes (now the traverse ropes) are stretched tight and anchored to the pinnacle. After the traverse, you will not be able to recover the equipment used for the pinnacle anchor.
4. While belayed, one climbers now "jugs" across the open area on *one* of the ropes, using the Texas prusik (which is explained in Chapter 13, in the section on crevasse rescue). The forward ascender is attached to the harness with a daisy chain. To the rear ascender is attached an etrier, and a second daisy chain attached to the climber's harness. Finally, the climber connects an additional safety sling between the traverse rope and the harness. This sling rides on a carabiner between the two ascenders. What would normally be the lower ends of the ascenders must be clipped to the rope with a safety carabiner (as shown in figure 11-6, earlier in this chapter).
5. After the first climber has jugged across, the second climber unties the ropes at the pinnacle anchor, threads the end of one rope through the anchor, and ties the ropes together as if preparing a rappel. This climber notes which rope will be pulled when it comes time to retrieve the ropes. (If it's a short traverse and you are using just a single rope, the climbers on each side of the traverse need to pull the rope around so that its center moves to the pinnacle anchor and the two ends are back on the main wall. Otherwise you will have problems retrieving the rope later.)
6. The first climber then tightens and anchors the rope ends on the main wall and belays the second, who will traverse in the same manner as the first.
7. Once both climbers are reunited, the ropes are untied at the main wall and retrieved by pulling on the appropriate rope.

SECONDING

As the second climber on short sections of aid, you will usually follow the same sequence as the leader, while belayed from above. You will, however, unclip the rope from a placement before clipping on the etriers, and clean the placement below you after stepping up higher. If you cannot reach a lower piece after moving up, lengthen your etriers with another sling, and then step down to clean the piece.

When climbing long sections of aid, a different strategy is called for. You will use mechanical ascenders to jug the fixed climbing rope and clean the route as you go. Before heading up, free the haul bag so the leader can start hauling it up the route. If it hangs up along the way, you will be the one to free it.

USING ASCENDERS

Although you could ascend fixed climbing ropes on slings attached with prusik knots, mechanical ascenders are both safer and more efficient (fig. 11-28). Attach an etrier and a daisy chain to each ascender. The etriers give you a platform to stand on, and the daisy chains positively connect the ascenders to your harness. Use a carabiner—not a fifi hook—to clip each daisy chain to an ascender. To expedite the process of preparing your ascenders, mark the loops in both the daisies and etriers where the gear is properly adjusted for length while jugging.

You do *not* untie from the end of the climbing rope while ascending. Remaining tied in serves as a backup in case both ascenders fail. To further decrease the likelihood of a long fall, you should periodically "tie in short."

Tying in short is an easy precaution that has saved lives. As the second ascends, an ever-lengthening loop of climbing rope forms below him, making for a long fall if the ascenders fail. To avoid this danger, stop periodically and, using the climbing rope just below the ascenders, tie a figure-8 loop and clip the loop into your harness with a locking carabiner. This guarantees a much shorter fall. Repeat this procedure about every 20 feet. Each time, unclip and untie the last figure-8 loop *after* the new figure-8 loop is clipped into your harness. Even when tying in short, *do not untie from the end of the rope.*

Often while jugging, it is necessary to remove the upper ascender from the rope and place it above a piece from which the rope cannot be unclipped while weighted from below. This same situation arises when the rope runs over an edge. Before removing the ascender, tie in short; this is a convenient time to do so.

After reattaching the upper ascender above the



Fig. 11–28. Use of ascenders; note daisy chains from each ascender to harness, and climber tied in short.

piece, check that the cam trigger is fully locked or the ascender could pop off the rope. This is especially true if you are jugging on a diagonal rope because the ascender has a tendency to twist to a vertical position once weighted. This twisting can be minimized by clipping a carabiner between the ascender and the rope as well (fig. 11-6). Once the upper ascender is reattached and your weight is on it, you will be able to unclip the rope from the problem piece of aid.

Other precautions should also be taken while ascending. First, carry a spare prusik sling just in case an ascender fails. And, as in all climbing, beware of sharp edges. Jugging places the rope under tension and sharp edges can damage it. Ascend as smoothly as possible to minimize the sawing motion of the rope running over an edge.

CLEANING

Efficiency in aid climbing is very much related to organization. While ascending and cleaning a pitch, rack the equipment as it will be placed on the lead rack. This greatly facilitates the lead changes.

Clean protection and aid placements that are lightly set often pop out if you jug right through them. Lift up on the placement as you slide your ascender up the rope. If clean aid has been used, you can often ascend from one tying-off-short spot to the next without stopping. After tying in short again, rack the pieces that have accumulated on the rope above your ascender.

This general system works even if a placement does not pop out as you move the ascenders upward. Keep the piece clipped into the climbing rope and use a chock pick and hammer to dislodge it. Once it pops free, continue ascending without reracking until you tie in short again. If, however, you must remove the upper ascender frequently, you should rack the pieces as they are removed.

Fixed pins found on the route should be left in place unless they are obviously unsafe or interfere with a chock placement. Take care not to break the eyes off these old pins, leaving a useless pin.

When cleaning one of your own pins, pound it back and forth along the axis of the crack, as far as it will go in each direction. Once the pin is loose enough to move easily back and forth, you can remove it by any of several means (fig. 11-29):



Fig. 11–29. Piton removal: a, use of "cleaner biner"; b, hammer used to pry; c, hammer swing.

1. Attach a "cleaner biner"—a carabiner no longer used for climbing—and a sling to the pin. Pull out on the sling while tapping the pin back and forth until it pops out (fig. 11-29a).
2. Pry out on the loose pin with the pick of the hammer, taking care not to break the hammer (fig. 11-29b).
3. Attach a "cleaner biner" and sling to the loose pin, then attach the sling to the hammer with another carabiner. Starting with slack in the sling, swing the hammer in the direction the pin should come out (fig. 11-29c).

Because the heads of malleable placements can only be reused a limited number of times, it is often best to leave them fixed. This is especially true if you think the wire will pull off the head as you remove the piece. If you decide to remove a malleable piece, attach a cleaner biner and sling between the head and your hammer. Then, as with pins, give the hammer a quick swing outward. It may take several swings before the head pops out. Inspect the head closely before reusing it because they deteriorate quickly. But if your attempt to remove the head merely strips the wire away, take the time to clean the head out of the rock. It is easier for you to do so on a fixed rope than for another climber on lead.

SECONDING TRAVERSES AND OVERHANGS

When traversing a long distance, it is generally more efficient if you aid across the traverse as if leading. Aiding in this fashion, you can receive a belay from above or self-belay by attaching ascenders to your harness with slings and sliding the ascenders along the climbing rope as you aid. When using the latter method, tie in short from time to time.

Short traverses, and those that are more diagonal than horizontal, can be crossed using normal jugging (mechanical ascender) techniques. The nearer the traverse is to horizontal, the less efficient this technique becomes, for at each piece you are faced with a small pendulum.

When jugging, remove the upper ascender at each placement and move it as far as possible above the currently weighted piece. This practice minimizes the pendulum that will result when you transfer your weight onto the upper ascender. Before doing this, however, allow some distance between the lower ascender and the placement so that the lower ascender does not jam into the piece as you transfer your weight to the upper ascender. Also, be sure to still tie in short at regular intervals.

The same basic methods just described for traverses also apply to seconding overhangs.

SECONDING PENDULUMS

The best method to second a pendulum depends on the length of the pendulum and the ropes available. The placements, slinging, and carabiner for the pendulum anchor usually will all need to be left behind, unless they can be reached from above after completing the pendulum.

Seconding long pendulums

All long pendulums require at least one rope in addition to the climbing and haul ropes. There are a number of ways to second a long pendulum, but the method shown in figure 11-30 will handle all such cases.

Figure 11-30a: All pendulums begin with a leader, of course, who rappels off a bombproof pendulum point using either one rope or two ropes tied together, depending on the width of the pendulum. The rappel rope should be clipped into the anchor so there's no danger of losing it. While on the pendulum, the leader is belayed on the climbing rope, which is not clipped into the pendulum anchor. At the bottom of the rappel, the leader runs back and forth across the rock to gain enough momentum to swing into the new crack system. On a very long pendulum, the leader may haul along an extra belay rope. The belayer keeps one end of this rope as the leader drags the other end.

Figure 11-30b: The leader ascends the new crack system and sets up an anchor. The leader attaches the climbing rope and the extra belay rope to the new anchor, the latter to serve as a belay



Fig. 11–30. Long pendulum sequence: a, leader rappels on two ropes while belayed on two; b, leader begins climbing, clipping in one of the belay ropes; c, with anchor set, leader belays with rope not clipped to aid pieces (the second rappels across the pendulum—note that the end of one rappel rope is attached to the second climber to prevent its loss); d, the second pulls the rappel ropes, ties in short, and "jugs" anchored climbing rope.

rope for the second climber. With the first climber now set to belay, the second climber frees or lowers the haul bag. The follower also unclips the rappel rope tie-in from the pendulum anchor so the rope can be retrieved later. (The follower can clip one end of the rappel rope to an out-of-the-way place on the seat harness to again ensure the rope can't be dropped.)

Figure 11-30c: The follower rappels the pendulum, with the first climber belaying and helping to pull the follower toward the new crack system at the end of the pendulum. (There's an alternative if the leader didn't drag an extra pendulum rope across. The second can pull across the pendulum on the lead climbing rope by hand, or with the help of mechanical ascenders.)

Figure 11-30d: Safely across, the second attaches ascenders to the climbing rope, ties off short, retrieves the rappel rope, and is ready to climb up the new crack system.

Seconding short pendulums

Climbers also have a variety of ways to handle the challenge of seconding a short pendulum. One clever and useful method is shown in figure 11-31. For this method to work, the slack rope from the pendulum anchor to the follower's harness must be at least double the arc of the pendulum. The follower stays tied in to the climbing rope during the sequence.

As shown in figure 11-31, here's how you as the follower could second a short pendulum:

Figure 11-31a: Connect the upper ascender with its attached etrier to the climbing rope beyond the pendulum anchor, facing across the pendulum. Clip a daisy chain from your harness to the ascender. Connect the lower ascender and etrier to the section of rope between the pendulum anchor and yourself. Clip it in with another daisy chain. Place your weight on the upper ascender. Next, attach a rappel device to the rope, below the lower ascender, and grasp the rope where it exits the device. Then, while keeping the safety trigger locked, release the cam of the lower ascender by pulling on the rope below it (this will take some effort). You're now ready to move.

Figure 11-31b: With one hand grasping the climbing rope as it leaves the rappel device and the other hand sliding the lower ascender, lower yourself across the pendulum. To put the brakes on at any time, simply let go of the lower ascender and the cam will again lock. (In fact, if a rappel device is not used, this ascender will often lock onto the rope by itself, requiring you to repeat the previous tactic of pulling hard on the rope below it.)

Figure 11-31c: Once across the pendulum, tie in short and move the lower ascender above that point. Now untie yourself from the end of the rope so you can pull it through the pendulum anchor. Once you've re-tied into the end of the climbing rope, you're set to ascend the climbing rope again.

The rappel device makes it easier to hold the rope while lowering yourself across the pendulum. However, you can also second a short pendulum this way without the device.

CHANGING LEADS

Unorganized belay stations can become a rat's nest of tangled ropes, twisted slings, and assorted hardware. Basic organization keeps the belay station manageable and the team functioning efficiently. Following are several methods to improve organization:

- All ropes should be different colors.
- After hauling the sack, the leader stacks the haul line and organizes the other ropes and hardware at the anchor.
- Once the second arrives at the anchor and begins consolidating the lead rack, the old leader (now the belayer) makes butterfly coils in the climbing rope and stacks these coils at the anchor with a sling. This prevents the climbing rope from getting snagged below and from tangling, and helps it pay out smoothly.
- If the second was carrying a rucksack, it can be packed with gear that won't be utilized on the next pitch and clipped into the anchor.
- Finally, the second (now the new leader) clips the free end of the haul rope to his or her harness, is placed on belay, and starts climbing.



Fig. 11–31. Seconding a short pendulum: a, after climbing to the pendulum anchor, the second prepares ascenders; b, the second lowers himself across the pendulum with a rappel device and lower ascender held open; c, the second ties in short, unties from the end of the rope, and pulls the rope through the anchor (and reties the end of the rope).

BIG-WALL MULTIDAY TECHNIQUES

"Big walls," the saying goes, "are 90 percent work and 10 percent fun." Not everyone agrees with those percentages, but few climbers will say big walls are easy. There's no question that proper conditioning is essential for the hauling of heavy loads and the scaling of multiple aid pitches.

Big walls also call for a high degree of mental composure. Inexperienced wall climbers easily find themselves the victim of heightened fears brought on by prolonged and severe exposure. If you're new to the game, perhaps you can soothe your fears by realizing that techniques for dealing with major walls are much the same as those needed for smaller climbs. Concentrate on the problem at hand and work away at the objective one move at a time.

In preparing for a big wall, guidebooks and other climbers are often helpful sources of information. Beware, however, of overdependence on climbers' topographic maps and equipment lists. Routes do change over time, especially if pins are used regularly.

Solid, efficient aid technique is a prerequisite if a major wall is to be completed within the time constraints dictated by reasonable food and water supplies. For success on the big walls, you must develop competency in hoisting heavy sacks up the route, and you should be able to live comfortably in a vertical world for days at a time.

HAULING

After anchoring yourself and fixing the climbing rope for the second, it's your job as the leader to begin hauling (fig. 11-32):

1. Attach a pulley, through which the haul line passes, to the anchor.
2. Attach an upside-down ascender to the haul line on the haul-sack side of the pulley. The end of the ascender closest to the pulley (normally the bottom) is clipped into the anchor, while the end pointing toward the haul sack is counterweighted with the remains of the rack (or another weight).
3. Attach a second ascender, in the normal direction, to the haul line on the opposite side of the pulley (between yourself and the pulley). Use a daisy chain to connect this ascender to your harness.
4. Push back from the wall using your legs and palms; your body weight will raise the haul sack. When you stop pushing, the upside-



Fig. 11–32. Sack-hauling system; hauler is preparing to move ascender up haul line and ascend etriers for next power haul.

down ascender acts as a brake to prevent backward slippage of the haul bag. You'll need a little slack in the climbing rope between yourself and the anchor to allow your hauling movement.

You can also haul by allowing slack of 6 to 8 feet between you and the anchor. Then, with the daisy chain connected between your harness and the haul line ascender, walk down the wall 6 to 8 feet until the anchor rope tightens. Climb back to your original position by stepping upward in etriers attached to the anchor, pulling the ascender with you. Repeat the process.

This method is also used if two people are needed to lift a very heavy bag. Both of you clip to the ascender on the haul rope, give yourself 6 to 8 feet of slack, and walk down the wall together. Regardless of the method used, *always* connect yourself to the anchor with the climbing rope.

FIXING PITCHES

On multiday climbs, you will often fix two or three pitches beyond the bivouac site and leave gear not needed for the bivouac at the high point. The lower end of each fixed rope is attached to the anchor of the previous pitch.

The next morning the pitches are jugged—one climber on a rope at a time. This gives a head start on the day and lets you warm up before new climbing begins.

RETREATING

Before a major climb, plan retreat lines in case of bad weather, accident, or other emergency. Locate other routes that are easy to reach to speed the ascent or that have fixed retreat lines.

If no retreat route exists, consider carrying a bolt kit for emergencies, allowing you to place rappel anchors. Also, as you climb each pitch, consider how you would descend it. On major walls rescues may be slow and difficult, if possible at all. It may be up to you to get back down in an emergency.

LIVING IN THE VERTICAL WORLD

Living for days on a vertical wall of rock brings some intriguing problems.

Dropped gear, for instance. Once dropped, it's gone. All vital items must have clip-in loops. Learn your gear so you can work it confidently. Get acquainted with unfamiliar items, such as Portaledges or hammocks, beforehand.

It's usually necessary to carry all your water with you. Each climber generally needs 2 quarts per day. For hot weather, especially if the route gets a lot of sun, you will need to carry even more.

Waste disposal poses another challenge. Tossing garbage down the wall is not acceptable, so you'll have to haul it up and off the climb. On popular routes, use paper bags for your excrement and toss these off the wall—warning climbers below when you are about to launch a bag. On seldom-climbed routes (or when no portion of a popular route is in your fall line), you can let your excrement fall out into space because this waste will decay far more quickly when not bagged. Keep all bivouac sites clean and sanitary, with no sign of your passing.

After completing a major wall, you need to get your gear back down. In the past, common practice was to toss the haul bag loaded with gear off the wall. Today, sack tossing is illegal at popular climbing areas like Yosemite; it endangers climbers below. Furthermore, many climbers have had their gear stolen by the time they got down to it. Carry down what you hauled up.

THE FUTURE OF AID CLIMBING

Free-climbers may feel that aid climbing isolates the climber from the rock. But anyone who has struggled to place a piece of aid while standing above a series of marginal placements understands that aid is not only climbing but a test of technical abilities and nerves.

To ensure that these routes will continue to be a test of skill and nerves, aid climbers are asked to respect certain ethics. If you are climbing an established route, adhere to the ethics of the first-ascent climbers. If they did not need a piton or bolt, *don't place one*. Use creativity and boldness to overcome the difficulty. A party following you on a route should find it in the condition you found it.

If you're putting up a new route, you are establishing the style for those who follow. Remember that routes once considered difficult using pitons are now free-climbed and that old bolt ladders are often viewed with disdain. Make it your goal to climb cleanly and in a style that climbers can respect. As time goes on, more of today's aid routes will be free-climbed, while aid climbers will push their limits on ever thinner and more remote climbs.





◆ PART FOUR ◆

SNOW AND ICE CLIMBING

Ice climbing on Habegger Falls, Bishop Creek in California's Sierra Nevada. Photo by Gordon Wiltsie

• 12 •

SNOW TRAVEL AND CLIMBING

Climbing in snow is a fundamental part of mountaineering. Snow adds beauty and challenge—but even if you wanted to avoid snow, it wouldn't be easy. Climbers work in a world in which their medium, the mountains, is sculpted by the action of snow, ice, and water. To avoid snow would mean climbing in only a select few mountain ranges or for only a few months each year.

Climbers like snow for at least a couple of reasons. First of all, it makes many climbs a lot easier by providing a pathway over brush and other obstacles on the approach hike and reducing the danger of loose rock on the ascent. It also brings new beauty to the mountains at the same time that it conceals the impact of people.

Snow is a complex medium that shows up in many forms that continually change, making snow travel trickier than trail hiking or rock climbing. Snow falls in a form that varies from tiny crystals to coarse pellets, depending on temperature and wind. Once fallen, snow begins to change as it is acted upon by sun, wind, temperature variations, and precipitation.

A rock face stays basically the same, while snow goes through many changes. It may start as a dusting of snow over a brush slope, progress to an unconsolidated powder bowl waiting to avalanche, then to a solid surface offering rapid ascent to a ridge top, and finally back to a brush slope with only scattered snow patches. Even in the course of a day, the snow can change from rock hard in the morning to thigh-sucking slush in the afternoon.

The changeable nature of snow means mountaineers have to be flexible in their mode of travel, ready to use snowshoes, skis, or crampons instead of boots alone. Snow conditions also affect decisions on route and climbing technique. Should you hike up the comfortable, snow-covered valley bottom or on the ridge top away from avalanche hazard? Should you go for the easy step-kicking of the sunny slope or the firmer, more stable snow of the shaded hill? Do the conditions mean it is safer to travel roped or unroped?

In this chapter we'll take a look at the equipment you need to travel in snow and techniques for traveling quickly and safely—with special emphasis on avalanche recognition and rescue.

EQUIPMENT

At the top of the list of basic snow-climbing equipment are ice axes and crampons. Snowshoes, skis, and ski poles are other important snow-travel aids. Climbers also use equipment for snow anchors, which will be taken up later in this chapter in the section on roped climbing.

ICE AXE

The ice axe (fig. 12-1) is one of the most versatile and important pieces of mountaineering equipment a climber owns. Without it, safe alpine travel is restricted to easy scrambles. With an axe,



Fig. 12–1. Parts of the ice axe

and the skill to use it, you can can venture onto all forms of snow and ice, enjoying a greater variety of mountain landscapes during more seasons of the year.

The modern ice axe is an inherently simple tool with many uses. Below the snow line, it's used for balance, as a walking cane, and to help brake going downhill. But its main role is in snow and ice travel, where it provides balance or a point of security to prevent a fall and serves to stop any fall that takes place.

The design of an ice axe often is a trade-off between features that make the tool better for particular uses. A longer axe may be OK for cross-country travel and scrambling, where it's used as a cane and to provide security in low-angle climbing. You'll probably want a shorter axe for the steeper slopes in alpine climbing. For ice climbing, the axes get shorter still and other design aspects become more specialized, such as the droop of the pick, placement of the teeth, and shape of the adze. These specialized axes are covered in Chapter 14.

Parts of the ice axe

The head of an ice axe—which includes the pick and the adze—is usually made of steel, a material strong enough for snow and ice climbing. Although the hole in the head of the axe is commonly called a carabiner hole, most climbers attach their wrist leash through it.

The pick on most ice axes (fig. 12-2) is curved or drooped, a design that provides better hooking action in snow or ice, causing the axe to dig in faster when you're trying to stop yourself (self-arrest) after a fall. A moderate hooking angle of 65 to 70 degrees from the shaft is right for general mountaineering uses. A sharper angle of 55 to 60 degrees is better for technical ice climbing as it coincides with the arc followed by the axe head when it is planted in steep ice. Teeth on the pick provide grip for ice and hard snow.



Fig. 12–2. Ice-axe picks: shapes and teeth patterns

The pick's hold for self-arrest is affected to some degree by its clearance (fig. 12-3). If the end edge of the pick is parallel to the shaft, the pick has neutral clearance. If the angle of the pick end tends toward the shaft, it has negative clearance. If the angle tends away from the shaft, it has positive clearance. Picks with neutral or negative clearance can skate or drag on an icy surface and not penetrate reliably during self-arrest. Picks with positive clearance tend to pull into the surface when pressure is applied—so much so that they can bite into hard snow with such suddenness that the axe may be yanked out of the climber's hands. To beat this



Fig. 12–3. Ice-axe clearance

problem, some climbers prefer a negative clearance to help with a more gradual stop in hard snow. But in most cases, the clearance probably makes little difference because self-arrest on ice is almost impossible regardless of the clearance, and in softer snow the pick will dig in whether the clearance is positive or negative.

The adze of the axe is used mainly for step-chopping on hard snow or ice. The flat top of the adze is also a firm, comfortable platform for the palm of your hand while holding the axe in the self-belay grasp during snow climbing. Adzes for general mountaineering may be flat or curved, straight-edged or scalloped, straight-out or drooped. A flat, straight-edged, non-drooped adze with sharp corners is probably the best all-around tool for step-chopping.

The shaft of your axe will most likely be made of metal (aluminum or titanium) or a composite (fiberglass, Kevlar, or carbon filament), or a combination of both. The wooden shafts of yesterday—often dense, straight-grained hickory—have been replaced by these stronger materials. Even the historical advantages of wood in dampening vibrations and offering a warmer grip have been minimized by the new composites.

Some shafts are covered at least partly by a rubber-type material for a better grip. The material helps give surer command of the axe during self-arrest and also dampens vibrations and increases control in placing the pick in ice. You can improve your hold on a shaft that doesn't have a rubber grip by adding athletic grip tape or using gloves with rubberized palms. However, the gripping material on the shaft can keep the axe from slipping as easily into the snow when you're using it for a boot-axe belay, probing, or self-belay. For this reason, it is recommended that ice axes for basic mountaineering not have this grip.

The spike, the metal tip of the axe, must be kept sharp so that it pokes readily into snow and ice. The axe does come in handy on rocky trails and talus slopes by helping with balance, but beware of dulling the spike.

Ice-axe length

Ice axes range in length from 40 centimeters (about 16 inches) to 90 centimeters (about 3 feet)—still much shorter than the 5-foot alpenstocks of the alpine pioneers. The shortest axes are for technical ice climbing; the longest ones are for tall mountaineers using the axe as a cane on easy terrain.

The optimal length for an ice axe may depend more on what you plan to do with it than on how tall you are. Axes less than 60 centimeters long are ice-climbing tools, excellent for placements on steep slopes but not so good for self-arrest. An axe of 70 centimeters is the longest that is generally useful for ice climbing. A length of 60 to 70 centimeters works well in most alpine situations, where you are climbing moderately steep snow slopes and using the axe for self-belay and self-arrest. Longer axes are better for cross-country travel and scrambling, and also are good as snow anchors and for probing for cornices and crevasses.

Ice-axe leash

The leash provides a way to attach the ice axe to your wrist or your harness when you want to ensure it won't be dropped. The leash also has other uses that we'll get to. Although the length of a leash can vary, it usually consists of a piece of accessory cord or webbing attached through the hole in the head of the ice axe (fig. 12-4).

The leash is valuable insurance on crevassed glaciers or long steep slopes where losing an axe would leave you without a principal tool for safety and put climbers below in danger from the runaway axe. The leash also lets the ice axe hang freely



Fig. 12–4. Ice-axe leashes (wrist loops), attached through carabiner hole in head of axe

while you make a move or two on occasional rock during a snow climb.

Short wrist leashes are favored by those who find them adequate for basic snow and glacier travel—easy to use and an aid to quicker control of the ice axe during a fall. During an uncontrolled fall in which you lose your grip on the axe, the short leash prevents the axe from flailing around as dangerously as it would on a longer leash. Ice axes sometimes come with a short wrist loop attached by the manufacturer.

A longer leash is now preferred, however, for all but the most basic of snow travel. With a long leash, you no longer have to switch the leash from wrist to wrist as you move the axe to the other hand for a change in direction up a snow slope. The long leash also makes the axe more versatile for climbing steep snow or ice.

A long wrist leash is usually about as long as the axe itself, and if it's just the right length, it can help reduce arm fatigue during step-chopping and ice climbing. It should be long enough to let you grasp the shaft near the spike through the wrist loop as you hold the leash taut from the head of the axe. This way, the wrist can share the work of the arm, and the head of the axe will be more stable. You can shorten the leash when you don't need it by wrapping it around the shaft.

With the long leash attached to your seat harness, the axe can serve as a personal anchor.

If you buy an ice axe without a leash, one can easily be made from a length of 5- or 6-millimeter accessory cord or $^1/_2$-inch to 1-inch flat webbing, tied into a sling, and then girth-hitched through the hole in the axe head. Tie a slip knot at the end of the sling to form the wrist loop. Ready-made leashes are also available at climbing stores.

Ice-axe maintenance

Modern metal-shaft ice axes require very little special care. Inspect the shaft before each use for deep dents that might weaken it to the point of failure under load (but don't worry about minor nicks and scratches). Clean mud and dirt off the axe after each climb and remove any rust.

Check the pick, adze, and spike regularly. To sharpen, use a small hand file instead of a grinding wheel, which could change the temper and strength of the metal.

CRAMPONS

Mountaineering is unthinkable without crampons, but when the first 10-point crampons came on the scene in Europe in the early 1900s, many alpinists thought the gadgets took unsporting advantage of the peaks. However, crampons proved to be the one aid that could relieve climbers of the tremendous burden of step-cutting and open up a vast array of new snow and ice faces. They have since evolved into the 12-point crampons of today, with 10 bottom points and 2 front points.

As with ice axes, the different crampon designs involve a trade-off between what's good for general alpine use and what's good for technical ice climbing. Most crampons are made from chrome-molybdenum steel, an extremely strong, lightweight alloy.

Climbers face a number of questions in shopping for crampons. What type of crampons should I buy? How will I know when the crampons fit my boots? Which attachment system should I use? This section provides information to help answer these questions and offers tips on crampon maintenance.

Crampon points

The early 10-point crampon has long-since been eclipsed by the addition of two forward-slanting points in the 1930s to create the 12-point crampon. The 12-point models eliminated even more step-chopping and permitted "front-pointing" up steep snow and ice. Because 10-point crampons usually don't have front points, they're no good for very steep ice and are no longer available except as used equipment.

The angles of the first two rows of points determine the best use for a set of crampons. When the first row (front points) is drooped and the second row is angled toward the toe of the boot (fig. 12-5), the crampons are better suited for front-pointing than for general mountaineering. This configuration allows the boot heel to be lower without additional calf strain. Straight points are better for flat-footing and general use.



Fig. 12–5. Angle of first two rows of points, best suited for front-pointing

Tiny instep crampons with four or six points are sold for use by backpackers who need to cross an occasional short snowfield. Because there are no points at the heel or toe, they're unsuitable for mountaineering and can be dangerous on steep snow or ice.

Hinged vs. rigid crampons

Mountaineers have a choice of either hinged or rigid crampons (fig. 12-6). Rigid crampons are for technical ice climbing. For most mountaineering, hinged crampons are preferable.

A hinged crampon flexes at the instep and is



Fig. 12–6. Types of crampons: a, rigid; b, hinged.

meant to bend with the natural rocking action of walking. It can be attached to any mountaineering boot, full shank or not, and to plastic boots. Attached to a full-shank or plastic boot, hinged crampons perform nearly as well for ice climbing as rigid crampons, because the boot provides the stable climbing platform that's required. If you buy only one set of crampons, buy hinged. If your goal is steep technical ice, then you can consider a rigid crampon. Some hinged crampons can be made rigid simply by adding a screw to each side of the crampon.

A rigid crampon is inflexible and not meant to bend at the instep. In most cases, it must be used with full-shank or plastic boots because it could break from the natural flex of another boot. Rigid crampons don't perform well in mixed terrain, where some flexibility is desired, and they can be heavier than hinged crampons. Rigid crampons come into their own when you're front-pointing up technical ice. They vibrate less than hinged crampons when you swing them into the ice, and their stiffness makes for less tiring front-pointing by allowing you to keep your heel lower.

Crampon attachment

Anyone who has had a crampon come loose in the middle of a steep slope of hard snow on a dark, cold morning knows the urgency of keeping crampons attached until you really want them off. To keep the crampons on the boots, climbers can choose from a variety of traditional strapping methods or the newer step-in/clamp-on bindings. The various systems are available on either hinged or rigid crampons.

Straps

Buckled straps do a good job of attaching crampons to boots. Neoprene-coated nylon is the best strap material because it is strong, doesn't absorb water, won't stretch, and can be easily transferred from one pair of crampons to another. Leather straps are less expensive but stretch when wet and will eventually rot or break. Nylon or fabric webbing is least desirable, since it readily accumulates snow and may freeze to the buckle.

Three strap-on designs are in general use:

Four independent straps per crampon are used in one design: two short straps, with buckles, attached to one side of the crampon and two longer straps attached to the other side. One long strap then connects the front four attachment posts over the instep of the boot, while the other wraps around the ankle and connects the two rear posts (fig. 12-7a).

Two independent straps per crampon are used



Fig. 12–7. Systems for attaching crampons to boots: a, four-strap; b, two-strap; c, Scottish; d, step-in/clamp on.

in an alternative strapping system: one connecting the front four attachment posts over the instep and the other wrapping around the ankle from the two rear posts (fig. 12-7b).

The Scottish system is a third strap-on method that is quicker than the other two and is gaining widespread use. A strap with a ring in the middle is permanently connected to the two front posts. A strap then runs from one side post through this ring to the other side post. The rear strap is the same as in the two-strap system (fig. 12-7c).

When strapping on crampons, position the buckles on the outward side of the boots to minimize the chance of catching a buckle with your foot as you walk. To reduce the danger of the front straps loosening on the two-strap and four-strap systems, thread the strap through the hole at each front attachment post *from the outside in*, and then give the strap an extra twist.

A word to beginning mountaineers: whatever you do, don't head out on a climb until you practice strapping on your crampons in the comfort of home. You'll have plenty of chances later to put the crampons on in the dark by feel, or by flashlight, with cold, numbed fingers. Lay the crampons on the floor with all straps started through the hole at an attachment post, put on your boots, place each boot in turn on its crampon, and attach the straps. Do the crampons fit? Do the straps have holes punched in them at the right places for attaching to the buckles? Do the straps need to be longer to accommodate insulated gaiters or overboots? Are they tight enough to keep the crampons on through thick and thin, but not so tight that they restrict blood flow? As best you can, work out all the wrinkles before you get out on that steep slope of hard snow in the cold, dark morning.

Step-in/clamp-on bindings

The old agony of fumbling with crampon straps and buckles is largely eliminated by the newer step-in/clamp-on bindings (fig. 12-7d). The crampons attach to the boot with a wire toe bale and a snap-up bale on the rear. They're fast and easy to put on, and each crampon has a safety strap so you won't lose it if it ever comes off. However, there are a couple of considerations in addition to higher cost to keep in mind before you decide to use step-in/clamp-on bindings.

The fit to the boot is more critical than with crampons that are strapped on. The boot must have a pronounced welt at both the heel and toe and, therefore, the step-in/clamp-ons fit especially well on plastic boots. Crampons with straps often work better on leather boots, particularly those without a decided heel welt. And some climbers, nervous about the possibility of the clamp-ons releasing, continue to use straps for technical ice.

Crampon fit

To ensure that crampons stay attached and perform well, it's essential they fit just right. Here are some tips to help in fitting crampons, either the kind that attach with straps or the step-in/clamp-on type.

- When buying crampons, try them on with the boots you'll be wearing. If you plan to use them on more than one pair of boots, check the fit on all pairs.
- If you'll be wearing gaiters with a rubber band that fits around the welt and instep of the boot, be sure to wear the gaiters when you fit the crampons.
- The front crampon points should protrude about $^3/_4$ inch to 1 inch beyond the toe of the boot.
- Many crampons are adjustable to one degree or another. This can include adjustments for length and for the width of instep, heel, and toe. Being able to adjust the heel and toe widths can be especially important if you're using telemark boots (for a climbing/skiing trip) or overboots.
- The attachment posts at the sides and rear of strap-on crampons should hug the boot snugly without significant bending to fit. Test the fit by lifting the boot upside down by the crampon. The posts should hold to the boot without the use of straps.
- The heel wire found on some strap-on crampons helps keep the boot heel in place by preventing it from slipping through the rear post, especially when using plastic boots.
- The welt on a boot is especially important with

step-in/clamp-on bindings, which grip the welt at toe and heel. Most desirable are Norwegian-style double-stitched welts on heavy leather boots and the indented toe and heel on plastic boots.

- Some climbers place a flat piece of foam, shaped like the bottom of the boot, between the boot and crampon to help insulate the foot from the snow. If you want to do this, take it into account when you fit your crampons.

Crampon maintenance and safety

Regular simple maintenance is required for safe, dependable crampons. Keep the points sharp, clean the crampons after every climb, and inspect them before the next outing.

Snow and ice routes often include short sections of rock that you'll climb with crampons on. The crampons should be able to take the punishment, but too much of this will dull the points. As with ice axes, sharpen crampon points with a hand file, not a grinding wheel (fig. 12-8).

After you return home from each climb, wipe dirt and water from crampons to prevent rust. Check the points before each climb. They should be clean and reasonably sharp, though very sharp points are needed only for technical ice climbing. Also check alignment of the points, because splayed points make the crampons less efficient at gripping the snow and more effective as a weapon that can slash pants and legs. It's probably best to retire a pair of crampons with badly misaligned points. Check the tightness of nuts and bolts on adjustable crampons. And while you're looking over the crampons, don't forget to inspect the straps if you have the strap-on type. Look for rotting, abrasion, cracks, or cuts.

In the mountains, following a few easy rules can protect you, your gear, and your companions from sharp crampon points. Walk carefully to avoid snagging your pants, gashing your leg, or stepping on the rope. When you're carrying the crampons, use a set of rubber protectors to cover the points, or keep the crampons in a special pouch. Both the 12-point protectors and the crampon pouch are available commercially.

One little trick makes crampons safer and more effective in soft, sticky snow. Just wrap the bottom of the crampon with duct tape to minimize the amount of snow that balls up under the crampon. This balling of snow can be dangerous, particularly where slushy snow overlays an icy base. Or you might be able to just take the crampons off.

WANDS

To find their way back over snow and glacier routes, mountaineers often mark the path with tiny flags atop thin bamboo wands. Climbers usually make their own, using the green-stained bamboo sticks sold at garden supply stores for plant supports. Convert them to wands by attaching a piece of bright, durable, water-repellent material to one end; plastic route-marking tape or coated nylon is best (fig. 12-9). A common method is to slit the first couple of inches at one end of a wand, slip the flag in the slit, tie it, then tape the slit closed. Be sure the flag is secure enough to withstand the high winds of open snow slopes and glaciers.

Wands usually vary in length from 30 inches to 4 feet. Less than 30 inches and the flag may not be high enough to be easily seen; longer than 4 feet and the wands are awkward to carry. Use your longest wands in winter when they have to be



Fig. 12–8. How to sharpen crampons



Fig. 12–9. Wand construction

pushed in farther because of soft snow and when new snowfall can bury them even deeper.

SKI POLES

Ski poles aren't only for use with skis. They beat an ice axe for balance when you're trudging with a heavy pack over level or low-angle snow, slippery ground or scree, or when you're trying to cross a stream or boulder field. They also can take some of the weight off your lower body. And the basket at the bottom keeps the poles from slipping deep into soft snow, a favorite trick of ice axes unless they're fitted with a special snow collar.

A variety of ski poles have features helpful to the trekker or mountaineer. Some poles telescope for adjustability on slopes and ease of strapping on a pack. With removable baskets, they can serve as a probe for crevasses or avalanche victims. Some poles fasten together to form an extra-long probe (fig. 12-10). Some poles both telescope out and fasten together. You can also buy a special self-arrest grip that has a pick protruding forward from the top, but this definitely is not a substitute for an ice axe on technical terrain. Most of these poles can be used whether you're traveling by foot, snowshoes, or skis.

SKIS

Mountaineering has become a popular four-season pursuit with the widespread use of Nordic and mountaineering skis fitted with climbing skins.

The Nordic ski, light and skinny, is worn with a special boot held in a toe binding that leaves the heel free (fig. 12-11a). Depending on the design and purpose of the ski, it may be referred to as a cross-country, touring, or telemark ski. Because the heel is not attached, Nordic skiers need the special skill of telemark turning for going downhill.



Fig. 12–10. Adjustable-length ski poles that can be fastened together to create an avalanche probe

Ski mountaineering employs a wider, heavier ski (sometimes called a randonée ski) that is closer to a traditional alpine (downhill) ski (fig. 12-11b). It has a binding that leaves the heel free for uphill travel but can secure the heel for standard downhill technique. Special boots are sold for use with mountaineering skis, though plastic mountaineering boots are often adequate.

Both kinds of skis will get you into the backcountry in winter for touring or mountain approaches. To provide uphill traction, both are used with removable climbing skins, in a textured material known as nylon plush, that adhere to the bottom of the skis (fig. 12-11c).

If you're accustomed to using only boots or snowshoes for backcountry snow travel, you may find certain disadvantages to skis. During the times you have to pack them, there's extra weight. It's difficult to self-arrest on steep slopes, though self-arrest grips on your ski poles can help. The skis are awkward on rocky or forested snow slopes; skiing can be difficult if you have a heavy pack; and



Fig. 12–11. Ski equipment for mountaineering: a, Nordic skis; b, mountaineering skis, boots, and bindings; c, climbing skins for skis.

you'll need a well-matched party in terms of skiing ability in order to keep a steady pace, especially for roped glacier travel.

But after all is said and done, skis are undeniably easier and faster for basic snow travel. They are giving more and more mountaineers a way to get to areas they couldn't readily reach before and to travel at more times of the year. Skis also can offer a safety bonus for crevasse crossings because with your weight distributed over a wider area, there is less danger of breaking through. They can also come in handy for rescue work, converting into a makeshift stretcher or sled.

Backcountry ski travel is a complex activity, with special techniques and equipment. For detailed information, take a look at articles or books devoted to the subject.

SNOWSHOES

Snowshoes (fig. 12-12) are a traditional aid to snow travel that have been updated into the small lightweight designs of today. Bindings hold your boots on the snowshoes, and metal claws or crampon-like devices improve traction on hard snow and ice.

Snowshoes are better than boots alone for traveling across fields of soft snow, where snowshoers float over the surface while hikers laboriously post-hole. But snowshoes are cumbersome for step-kicking uphill, even though modern snowshoes have an opening that lets you get the toe of your boot into the snow. Of course, when you're not wearing the snowshoes, they add extra weight to your pack.



Fig. 12–12. Snowshoes

Although snowshoes are a lot slower than skis, they can be used on mixed terrain where skis would be awkward, and they're often more practical than skis if you have a heavy pack. If your climbing party includes some people who aren't very good on skis, it's probably more efficient for everyone to travel on snowshoes, which are easy to learn. You wear normal mountaineering boots with snowshoes, unlike Nordic skis and some mountaineering skis that call for special footwear.

SHOVEL

A broad-bladed shovel is a utility and safety tool for snow travel (fig. 12-13). It's the only practical tool for uncovering an avalanche victim. Shovels are also used for digging snow shelters and leveling off tent platforms and have even been used as a climbing tool to shovel a pathway up a particularly snowy route.

A good snow shovel has a blade large enough to move snow efficiently and a handle long enough for good leverage but short enough for use in a confined area. It should strap easily to the pack for quick access in an emergency. Some shovels come with a detachable handle or with a blade that locks perpendicular to the handle so it can be used as a trenching tool. For projects such as building snow caves, mountaineers sometimes carry a grain scoop, a broad-bladed shovel that can move a lot of snow.



Fig. 12–13. Snow shovel

SNOW-CLIMBING TECHNIQUES

USING THE ICE AXE

How to carry an ice axe

The first rule is to carry your ice axe carefully. Keep in mind what its sharp points and edges could do to you or your partners. Whenever the axe is not in your hands, be sure it's secure against slipping down a snow slope or cliff.

When you're on the move and don't need the axe, the best bet is to slip it through the ice-axe loop on your pack and strap it down (fig. 12-14a). It's a good idea to keep rubber or leather guards on the pick, adze, and spike, particularly on an axe that's sharp as an axe should be. If you're simply carrying the axe in one hand, grasp the shaft at the balance point (shaft parallel to the ground), the spike forward and the pick down (fig. 12-14b).

During travel on snow that alternates with rocks or steep brush where you need both hands free, you can get the axe out of the way by sliding it diagonally between your back and the pack (fig. 12-14c). The spike is down and the pick, between the two shoulder straps, is well seated, clear of your neck, and pointing in the same general direction as the angle of the shaft. The axe can be stowed and retrieved quickly, and this works fine for short stretches. To avoid chances of a runaway axe, retrieve it before taking off the pack.

How to grasp an ice axe

How you hold the head of the axe when climbing in snow depends on your preference and on the climbing situation.

There are two principal ways to grasp the axe:

Self-arrest grasp: The thumb goes under the adze and the palm and fingers go over the pick, near the shaft (fig. 12-15a). As you climb, the adze points forward.

Self-belay grasp: The palm sits on top of the adze and the thumb and index finger drop under the pick (fig. 12-15b). As you climb, the pick points forward.

The self-arrest grasp puts you in perfect position to use the axe instantly to brake a fall down a steep



Fig. 12–14. Carrying an ice axe: a, attached to a pack by an ice-axe loop, with guards on the pick, adze, and spike; b, in the hand while walking; c, temporarily between back and pack.

slope. However, you're not going to fall very often, and in the meantime all the pressure of planting the axe as you climb is concentrated where the narrow top edge of the pick meets your palm. That hurts after awhile, and therefore you may not plant the axe as securely as you might otherwise. This compromises the safety of your critical self-belays (which are explained in the next section).

The self-belay grasp is much more comfortable because the pressure of placing the axe is spread over the wide, flat top of the adze, where your palm now rests. If you fall, you'll have to immediately flip to a self-arrest grip to put the brakes on. (This is something to practice during self-arrest drills.)

How to self-belay

The technique of planting the ice-axe shaft to help guard yourself against falls while snow climbing is called self-belay. We'll learn later in this chapter about what to do in the event you or a ropemate start sliding down a steep snow slope. Then self-arrest and other techniques come into their own. But knowing how to avoid the slide in the first place with a self-belay is as important as knowing what to do if it occurs.

Self-belay (fig. 12-16) is a way to lessen the likelihood that a simple slip or misstep on a snow slope will turn into a long fall. It is used repeatedly to help safeguard the way up or down a steep snow



Fig. 12–15. Grasping an ice axe: a, self-arrest grip; b, self-belay grip.



Fig. 12–16. The self-belay: a, climbing; b, falling; c, recovering.

slope when the potential for a fall is the highest: when you are moving or when you are in an out-of-balance position. You can create the belay with either a self-belay grasp or a self-arrest grasp on the axe, though you'll probably find more power and ease in the self-belay grasp.

Here's how to do the self-belay: be sure both feet are secure (in the position of balance described in the next section). Then jam the spike and shaft of the axe into the snow and continue to grip the head of the axe with one hand as you move a step forward with each foot. When both feet are again secure, pull the axe out and replant it farther along (fig. 12-16a). Continue this procedure until you feel it's safe to proceed without it.

Used like this, the ice axe is ready as a safety post as you are moving your feet. To be reliable, the shaft must be placed deep enough, in snow that's firm enough, to hold your full weight. If you slip, keep one hand on the head of the axe as you grab hold of the shaft at the surface of the snow and trust your weight to it (fig. 12-16b). The key to a successful self-belay recovery is the grabbing of the shaft right where it emerges from the snow, so that your pull is against the buried shaft while the hand on the head of the axe minimizes the risk of it levering out.

Practice this technique on a slope of hard snow with a safe runout to develop the confidence to know when a self-belay will hold while you replant your feet after a slip. If you're on a climb and begin to doubt your self-belays, it's time to make a critical decision: whether to back off, to rope up, or to climb on, recognizing the risk you're taking.

ASCENDING SNOW

Climbing up—and down—snow slopes takes a set of special skills. Different techniques come into play depending on how hard or steep the slope is. (The related skills of cramponing and step-cutting are covered in Chapter 14.)

Climbing in balance

As with rock climbing, staying in balance while moving on snow is less tiring, more efficient, and safer than struggling to keep from falling only by clinging to something—in this case, the ice axe or the snow. Snow climbers move from one balanced position to another, avoiding any prolonged stance in an unbalanced position.

On a diagonal uphill route, the most balanced position is with the inside (uphill) foot in front of and above the trailing outside (downhill) leg, which is fully extended to make use of the skeleton and minimize muscular effort. In that position, let the trailing leg bear most of your weight. Always grip the ice axe with your uphill hand.

The diagonal ascent is a two-step sequence: from a position of balance through an out-of-balance position and back to a position of balance (fig. 12-17). From the in-balance position, place the axe above and ahead into the snow. Move up two steps before repositioning the ice axe. The first step brings the outside (downhill) foot in front of the inside (uphill foot), putting the climber out of balance. The second step brings the inside foot up from behind and places it beyond the outside foot, putting the climber back in the balance position. Keep your weight over your feet and avoid leaning into the slope.

If you're heading straight up the fall line instead of moving diagonally, there's no longer an uphill or downhill leg, or an uphill or downhill hand. So carry the axe in the hand that feels most comfortable and climb in a steady, controlled manner. Regardless of the direction of travel, placing the axe firmly before each move will provide self-belay protection.



Fig. 12–17. Ascending a snow slope, diagonally, in balance

The rest step

Climbing a long featureless snow slope can give you the frustrating sensation that you're getting nowhere. Few landmarks help measure your progress, so distances are deceiving. Novice climbers try a dash-and-gasp pace in an attempt to rush the objective. But the only way to the top of the slope is to find a pace you can maintain, and then maintain it.

The solution is the rest step, a technique that conserves energy as it moves you methodically forward. (The rest step is illustrated in Chapter 5.) Use the rest step whenever legs or lungs need a bit of recuperation between steps. At lower elevations it's usually the leg muscles that require a break. At higher elevations, the lungs need the pause.

Here's a review of the rest step: the rest takes place after one foot is swung forward for the next step. Support all body weight on the rear leg while the unweighted forward leg muscles relax. During each mini-rest, the weighted rear leg must be kept straight and locked at the knee so that bone, not muscle, carries the load. The climbing pace is slow, because for every step there is a pause. Synchronize breathing with the sequence. At higher elevations you'll need to make a conscious effort to breath deeply and often.

Step-kicking

The technique of step-kicking is basic to snow climbing. It's a way to create a path of upward steps that provide the best possible footing with the least expenditure of energy. It is all that's needed for footing when the snow is yielding enough to permit security without the help of crampons or chopped steps.

The most efficient kick to create snow steps is a swing of the leg that lets its own weight and momentum provide the needed impact, with little muscular effort. This works fine in soft snow. On harder snow, you'll end up putting in more effort, and the steps will usually be smaller and less secure.

The definition of a secure step varies with the climber's skill and strength and with the effects of such factors as wind, altitude, and the weight of the pack. An average climber probably needs steps deep enough to take the ball of the foot when going straight up and at least half of the boot on a diagonal ascent. Steps that are kicked level or tilted slightly into the slope are more secure. The less space there is on a step, the more important it is that the step slope inward.

When you're kicking steps, keep the other climbers in mind. They can follow up your staircase in good balance if your steps are spaced evenly and somewhat close together. Make allowance for climbers whose legs aren't as long as yours.

Followers use the same leg swing as the leader, improving the steps as they climb. The follower must kick into the step, because simply walking onto the existing platform will not set the boot securely in position. In compact snow the kick should be somewhat low, the toe driving in and deepening the step. However, in very soft snow it is usually easier to bring the boot down from above, shearing off an edge of snow, which helps build a stronger step.

A basic principle of snow travel is that parties move in single file when ascending. If you're in the lead, you will be doing by far the hardest work. You also have to think harder in order to avoid potential hazards to the group and to choose the best route. Take turns leading so that no climber is worked to exhaustion.

Direction of ascent

You can either go directly up a snow slope or ascend it diagonally. If you're in a hurry, a direct ascent is usually the way to go. Speed is a primary consideration on a long snow climb, and a fast, direct ascent is the order of the day if you face bad weather, avalanche or rockfall danger, poor bivouac conditions, or a difficult descent.

When time permits, most climbers prefer a diagonal ascent, switchbacking up moderately angled slopes. They reason that the lower angle of ascent requires less energy for each step while it ends up gaining the same elevation as the fewer—but steeper—steps of a direct ascent. The strength of this argument probably depends on snow conditions. In good step-kicking snow, the energy you save at each step on a diagonal ascent can be used to kick the additional steps required by that angle. But in marginal step-kicking conditions, many climbers figure that a diagonal route is more difficult because of the work of kicking edged, traversing steps in hard snow.

Ice-axe technique: direct ascent

In a straight shot up a snowfield, step-kicking is the basic technique for your feet. Ice-axe technique, however, will vary depending on snow conditions and steepness.

Cane position: On a slope that is at a low or moderate angle (roughly up to 30 or 35 degrees), climb with the axe in the cane position, holding it in one hand by the head and using it for balance (fig. 12-18). You can continue in the cane position as the snow gets even steeper, as long as you feel secure with it. Setting the axe firmly before each move will provide a self-belay.



Fig. 12–18. Direct ascent, ice axe in cane position



Fig. 12–19. Direct ascent, ice axe in stake position

Stake position: At some point as the snow steepens, a climber may choose to switch to the two-handed stake position, a more secure stance often used for angles over 45 degrees (fig. 12-19). Before moving upward, plant the axe, with both hands, as far as it will go into the snow. Then continue to grasp it with both hands on the head, or with one hand on the head and one on the shaft. This position is particularly useful on steeper soft snow.

Horizontal position: This is a technique effective on steeper, harder snow that is covered with a soft layer. Hold the axe with both hands, one in the self-arrest grasp on the head and the other near the end of the shaft. Jab the axe horizontally into the



Fig. 12–20. Direct ascent, ice axe in horizontal position



Fig. 12–21. Diagonal ascent, ice axe in cross-body position

snow above you, the pick down and the shaft at right angles to your body (fig. 12-20). This jabs the pick into the harder base while the shaft gets some purchase in the softer surface snow. (Don't forget to take advantage of the rest step as you head up the hill, regardless of the ice-axe technique being used.)

Ice-axe technique: diagonal ascent

On a diagonal route, remember to climb in balance as you kick steps up the slope. (Figure 12-17 shows the sequence of moves in a diagonal ascent.) For slopes angled less than about 40 or 45 degrees, the axe usually works fine in the cane position. As the slope steepens, the cane position becomes awkward and it's time to switch to the cross-body position.

Cross-body position: For this position, hold the axe perpendicular to the angle of the slope, one hand grasping the head and the other holding the shaft, which is jabbed into the snow (fig. 12-21). The axe will cross diagonally in front of you. (Be sure the pick does not point toward your body.) Most of the weight placed on the axe should bear on the shaft, while the hand on the head merely stabilizes the axe. Move your feet upward in the same manner as with the cane position.

Diagonal ascents often mean switchbacks, which mean changes in direction. There's a specific sequence of steps for a safe change in direction on a diagonal route, whether you have the axe in the cane position or the cross-body position (fig. 12-22).

Start from a position of balance, the inside (uphill) foot in front of and above the outside (downhill) foot. Jab the axe shaft straight down into the snow at a spot as directly above your location as possible. Grasp the head of the axe with both hands as you move your outside foot forward, bringing you into the out-of-balance position. Continue holding onto the head with both hands as you move into a stance facing uphill, moving your inside foot toward the new direction of travel, and ending with splayed feet. Finally, a turn in the new direction of travel returns you to a position of balance, with the new uphill foot now in front and above. With the cane position, the new uphill hand now grasps the axe head. With the cross-body position, the hands holding the head and the shaft are now reversed. If splayed feet feel unstable as you change direction at a steep angle, kick the steps more directly into the slope.

Traversing

Long horizontal traverses, which neither gain nor lose elevation, are rarely any fun. This ''sidehill gouging'' works OK on soft snow at low and moderate angles, though it's still not as comfortable or efficient as a diagonal route. On horizontal traverses over harder or steeper snow, you can face into the slope and kick straight forward for more secure steps. But try to avoid horizontal traverses in the first place.

DESCENDING SNOW

One mark of a skillful snow climber is the ability to go downhill efficiently and confidently. Many otherwise competent and aggressive climbers blanch at the prospect of going forward down a steep snow gully. Why? Because there's a superb view—perhaps too superb—of the exposure. And because on steep snow the axe must be placed very low to move down, leaving the climber without the comforting stance and handhold that was there on the way up. You can minimize those downhill jitters by mastering a few descent techniques.



Fig. 12–22. Changing direction on a diagonal ascent: a, jab axe shaft straight down; b, face uphill with feet splayed; c, turn in new direction of travel.

Plunge-stepping

In going down, just like going up, technique is determined mainly by the hardness and angle of the snow. In soft snow on a moderate slope, simply face outward and walk down. With harder snow or a steeper angle, use the plunge step (fig. 12-23).

The plunge step is a confident, aggressive move. Face outward, step assertively away from the slope and land solidly on your heel with your leg vertical, transferring weight solidly to the new position. No timid steps allowed. Avoid leaning back into the slope, which could result in a glancing blow, less secure steps, and perhaps an unplanned glissade. Plunge-stepping can be secure with steps that hold only the heel of the boot, but most climbers do not trust steps more shallow than that.

When plunge-stepping, keep the knees bent a bit, not locked, to maintain control of balance. The degree of bending depends on the angle of the slope (the steeper the slope, the greater the bend) and the firmness of the surface (the harder the snow, the greater the bend). With bent knees, a forward lean is also needed to help with balance. An aggressive stride creates a deep step, so be careful in very soft snow that a plunging leg isn't injured by being buried so deep it can't be yanked back out as you take the next step.



Fig. 12–23. Plunge-stepping, moderate slope

The plunge-stepping climber holds the ice axe in one hand in either the self-arrest or self-belay grasp, with the spike close to the surface, well forward and ready to plant in the snow. You can spread and move the other arm for balance. Some climbers hold the axe in both hands in the full self-arrest position—one hand on the head, the other near the end of the shaft—but this allows less movement of the arms to maintain balance.

At some point, on harder or steeper snow, this style of plunge-stepping will not feel secure. Then it's necessary to plant the axe as low as possible in a self-belay before each move and advance the feet in a sort of crouched, modified plunge step (fig. 12-24).

Glissading

Glissading is one of the joyous bonuses of mountain climbing, offering the fastest, easiest, and most exhilarating way down many snow slopes for a climber on foot. It's an alternative to walking or plunge-stepping, for use on slopes where you can keep your speed under control. There are three principal methods of glissading. Which one you use will depend on how hard and steep the slope is, how safe the runout is at the bottom of the hill, and how good you are at glissading.

The sitting glissade (fig. 12-25a) is the easiest to learn and works on soft snow where you would bog down if you tried a standing glissade. You'll get the slickest and driest ride by wearing coated-nylon rain pants. For the sitting glissade, simply sit in the snow and let 'er rip, holding the axe in self-arrest position as you slide downhill. The standard posture is to sit fairly erect, knees bent and boot soles planing along the surface. However, to get started and maintain momentum in snow that



Fig. 12–24. Plunge-stepping with self-belay

is quite soft, it helps to stretch out your legs, spreading body weight over a greater area.

Run the spike of the axe, like a rudder, along the snow on one side of you. Putting pressure on the spike helps reduce speed and thwarts any tendency of your body to pivot head-downward. The standard posture, with knees bent and feet flat, also reduces speed. This posture is the most helpful in uncomfortable conditions: when the snow is crusted or firmly consolidated, pitted with icy ruts or small suncups, or dotted with rocks or shrubs. It provides more stability and control than with your legs straight out in front, and it helps minimize wear and tear on your bottom.

To stop, use the spike to slow down, then dig in your heels—but not at high speed or a somersault may be the result. For an emergency stop, simply self-arrest by rolling into position toward the side opposite the spike. (The indispensable technique of self-arrest will be explained in the next section of this chapter).

Turns are almost impossible in a sitting glissade. The spike, dragged as a rudder and assisted by body contortions, can exert a change in direction of a few degrees at most. The best way to get around an obstruction is to stop, walk sideways to a point that is not directly above the obstacle, and take off again.

The standing glissade (fig. 12-25b) is the best one, if you know how to do it and conditions are right. This position offers the earliest look at hazards of the route, is the most maneuverable, and saves your clothes from wetness and abrasion. The standing glissade is most effective on a firm base with a softer layer on top. The softer the snow, the steeper the slope needed to maintain speed. You can do a standing glissade down slopes of harder snow, but these will usually be at lower angles and with a safe runout. Slopes at very low angles can be skated, if the snow is firm.

Correct standing glissade technique is very similar to downhill skiing. The position is a semi-crouch over the feet with bent knees and outspread arms. The feet can be together or spread, as needed for stability, with one foot advanced slightly to further improve stability and prevent nose dives. Increase speed by bringing the feet closer together and leaning farther forward over the feet. Slow down and stop any number of ways: stand up and dig in the heels; turn the feet sideways and edge; crouch and drag the ice-axe spike as in the crouching glissade (described next); or perform a turn similar to skiing in which you rotate the shoulders, upper body, and knees in the direction of the turn and roll the knees and ankles in the same direction to rock the feet onto boot edges.

Transition areas, where the snow texture changes, are tricky. If you hit softer, slower snow, your head and torso will suddenly be outpacing your legs, so move one boot forward for stability. If you hit harder, faster snow or ice below the surface, lean well forward to prevent a slip. Keep speed under control by regular braking and traversing.

The crouching glissade (fig. 12-25c) is done



Fig. 12–25. Glissades: a, sitting; b, standing; c, crouching.

much like the standing glissade, except the climber holds the axe in the self-arrest position to one side of the body, sits back, and drags the spike in the snow. It's slower than a standing glissade and easier to learn. With three points of contact, it is also more stable. However, turning is more difficult, as is controlling speed with edging.

As in much of mountaineering, efficiency in glissading takes a smooth blend of several techniques. In particular, climbers who lack finesse in the standing glissade often use a combination: breaking into a plunge step to control speed, stepping off in a new direction rather than making a ski-style turn, and skating to maintain momentum as the slope angle lessens.

Glissading can be hazardous. Glissade only when there is a safe runout, close enough that if you slide out of control, you won't be injured before reaching it. Unless there is a view of the entire run, the first person down must use extreme caution and stop frequently to look ahead. The biggest risk is losing control at such high speed that self-arrest is not possible. This is most likely to happen on the best glissading slope, one with firm snow. Maintain control of speed.

Adjust equipment before beginning the descent, and stow crampons and other hardware in the pack. Don't try a sitting glissade while wearing crampons, because it's too easy to catch a point in the snow. Wear mittens, even on a warm day; snow is so cold and abrasive it can chill and flay the hands until they lose control of the axe.

Sometimes in soft snow, a glissader accidentally sets off a mass of surface snow, which slides down the slope with the glissader aboard. These are really small avalanches, known as avalanche cushions. The trick is to decide if it's a cushion safe to ride or if it is about to become a serious avalanche. If the moving snow is more than a few inches deep, self-arrest won't work because the ice-axe pick can't penetrate to the layer below. Sometimes the spike can be driven deep enough to slow, though probably not stop, the glissader. Unless you're sure the cushion is safe and your speed is under control, get off. Just roll sideways a few feet out of the path of the moving snow, then self-arrest.

Downclimbing

On steep snow where you may not feel secure glissading or plunge-stepping, you can face into the slope and downclimb backward by kicking steps straight into the slope. Use the axe in the stake position as a self-belay.

SELF-ARREST

Self-arrest is the lifesaving technique of using the ice axe to stop your own uncontrolled slide down a snow slope. It's used when you slip on the snow without a self-belay or when your self-belay fails. If you are unroped, it offers your only chance to stop the slide. It's the single most important snow-climbing skill, one you should continue to practice as long as you climb so that it remains an automatic response to a fall.

The technique also serves to brace you solidly in the snow if you have to hold the fall of a rope-mate. Therefore a climber's own life and those of fellow climbers could hinge on self-arrest skills. Every climber must be proficient and reliable at self-arrest, learned through practice on increasingly steep and hard snow with a safe runout. Strength obviously helps in self-arrest, but knowing the correct methods is more important than simple muscle power.

The first rule of self-arrest is: act fast. Good self-arrest form may be aesthetically satisfying, but fast is better than pretty when instantaneous action is critical. From the self-arrest position, get the ice-axe pick in as hard and as quickly as possible, before you've accelerated to an unstoppable speed.

Here's what you should look like as you complete a successful self-arrest, lying face down in the snow, head uphill, with the ice axe beneath you (fig. 12-26, last panel):

The hands hold the axe in a solid grip, one hand in the self-arrest grasp with thumb under the adze and fingers over the pick, the other hand on the shaft just above the spike.

The pick is pressed into the snow just above your shoulder so that the adze is near the angle formed by neck and shoulder.

The shaft crosses your chest diagonally and is held close to the opposite hip. Gripping the shaft near the end prevents that hand from acting as a pivot around which the spike can swing to jab the thigh. (A short axe is held the same way, although the spike will not reach the opposite hip.)

The chest and shoulder are pressed strongly down on the ice-axe shaft.

The spine is arched slightly away from the snow. This arch is critical; it places the bulk of your weight on the axe head and on your toes or knees, the points that dig into the snow to force a stop. Pull up on the end of the shaft, which starts the arch and rolls weight toward the shoulder by the axe head. (Note: the arch can be carried to excess by those unwilling to get their chest and face down into the snow.)

The knees are against the surface, helping slow the fall in soft snow. On harder surfaces, where they have little stopping power, they help stabilize your body position.

The legs are stiff and spread apart, toes digging in. But if you have crampons on, keep them above the snow until you've nearly come to a halt. A crampon point could catch on hard snow or ice and flip you over backward.



Fig. 12–26. Correct self-arrest technique, head uphill, on your back

Self-arrest from different positions

The position you find yourself thrown into when you fall determines how you self-arrest. You'll likely be sliding in one of four positions: head uphill or head downhill and, in either case, face down or on your back. The immediate goal is to get your body into the only usable self-arrest position: with your head uphill and your face down. And the first move toward that goal is to grasp the axe in both hands, one hand on the axe head in the self-arrest grasp and the other at the base of the shaft. From that point, here is how to handle each of the four situations:

Head uphill, face down: You're already in the desired self-arrest position. All you have to do is get your body over the axe shaft, as described above.

Head uphill, on your back: This isn't much more difficult than the first version. Roll toward the head of the axe and jab the pick into the snow at your side as you roll over onto your stomach (fig. 12-26). If the axe head is on the right, roll to the right. If it's on the left, roll to the left. Beware of rolling the other way, toward the spike, which could jam the spike in the snow before the pick and wrench the axe from your hands (fig. 12-27).

Head downhill, face down: self-arrest from head-first falls is more difficult because the feet have to first be swung downhill. In this face-down predicament, reach downhill and off to the axe-head side and get the pick into the snow to serve as a pivot to swing the body around. Work to help swing the legs around so they are pointing downhill (fig. 12-28). Never jab the spike into the snow and pivot on that end of the axe. That would bring the pick and adze of the axe across your slide path and on a collision course with your chest and face.

Head downhill, on your back: Hold the axe across your torso and slide the pick into the snow, then twist and roll toward it (fig. 12-29). Once again, the pick placed to the side serves as a pivot point. But merely planting the pick won't bring you around to the final self-arrest position. You must work at rolling your chest toward the axe head at the same time as you help your legs to swing around and point downhill. A sitting-up motion helps the roll.

Variations: In the loose snow of winter and early spring, the pick may not be able to reach compact snow, making the usual self-arrest useless. The best brakes in this case are feet and knees and elbows, widely spaced and deeply pressed into the snow. In this case the greatest drag potential of



Fig. 12–27. Incorrect self-arrest technique; do not roll toward spike

the axe lies not in the pick but in the shaft, thrust vertically into the slope or dragged in the self-arrest position. Pivoting is usually unnecessary on a headfirst fall because you stop before you can get turned around.

A final reminder: Act fast! How fast you get into the arrest position is the key to success. On hard snow, a quick stab at the slope with the pick or spike, or even boot heels, may stop a fall before it gets started. Arrest on extremely hard snow is very difficult if not impossible, but always give it an intense try, even if you're belayed on a rope. Occasionally, in the first instant of a fall, the pick lodges in a crevice or behind a hump and stops the action even on a very steep slope.

The limits of self-arrest

Self-arrest stops a fall by friction of axe and body against snow. When the slope is too steep or slippery—"too fast"—even the most skillful technique won't stop the slide. Acceleration can be so rapid on hard snow that the first instant of fall is the whole story. The climber rockets into the air and crashes back to the unyielding surface with stunning impact, completely losing uphill–downhill orientation.



Fig. 12–28. Self-arrest technique, head downhill, face down



Fig. 12–29. Self-arrest technique, head downhill on your back

Even successful arrests require at least a little time, during which the climber slides some distance. Therefore the effectiveness of the self-arrest is limited by the climber's speed of reaction and the steepness and length of the slope.

If all initial efforts at self-arrest are unsuccessful, don't give up. Keep fighting. Self-arrest might work in softer snow or at a lower angle farther down the slope. Even if you don't stop, the attempt may slow you down and help prevent rolling, tumbling, and bouncing. It may also help keep you sliding feet first, the best position if you end up hitting rocks or trees. And if you are roped to other climbers, anything you can do to slow your fall increases the chance that their self-arrests or belays will hold.

Keep alert at all times to the limits of self-arrest. If a slope seems too fast or too short, or members of a climbing party doubt their strength or skill, use one of the techniques of roped protection outlined later in this chapter.

The uses of self-belay and self-arrest

Self-belay is preventive; self-arrest is a recovery measure. Some climbers who learned self-arrest as the primary security technique on snow fear too much emphasis on self-belay. But the purposes of the two techniques are different and you need them both. Where the axe can be planted securely, self-belay is usually all that is needed, so any fall is prevented in the first place. If self-belay fails, you can then self-arrest.

While self-belaying on a climb, keep alert to changes in snow conditions that make the belays insecure. If the snow on a steep slope is so hard that axe placement might not hold a slip, it may be best to change to the self-arrest grasp, ready to instantly self-arrest. Of course, under these conditions, a self-arrest will also be very difficult. Even with the self-arrest grasp, you can continue to make self-belay placements, though they will be a little more difficult because your palm will no longer be on the flat, comfortable top of the adze.

One important skill comes into play if you are using the self-belay grasp and slip into a fall. You must be able to instantly flip the ice axe from the self-belay grasp to a self-arrest grasp. Grab the shaft of the axe just above the spike, then change the hand to the self-arrest grasp—and arrest. This takes practice. If you don't have the skill or confidence to do it, then it will be safer to do your self-belays holding the axe head in the self-arrest grasp.

ROPED CLIMBING TECHNIQUES

When is it time to rope up on a snow climb? In general, when the overall risks to the climbing party of continuing unroped are higher than those of roping up. It's often an issue of trade-offs, weighing the pros and cons of both choices.

On a glacier, the risks to unroped climbers of falling into a crevasse clearly exceed the risks to the team of roping up. So teams rope up.

As slopes steepen and snow hardens, the easy decisions disappear. It becomes a matter of deciding whether the risks to unroped climbers of being unable to stop their own individual falls exceed the risks to the team of roping up. These team risks are not trivial. They include the possibility of one person's fall pulling the entire rope team off the mountain and the danger that roped climbing will slow the climb, adding to avalanche and rockfall exposure and the likelihood of an unplanned bivouac. It becomes a delicate decision involving an evaluation of each climber's skills and the variety of alternatives for roped team protection.

OPTIONS FOR ROPED TEAM PROTECTION

If your party decides it would be safer overall to rope up, there are several different ways to match the type of rope protection to the conditions of the climb and the strengths of the climbers.

Team arrest (roped but unbelayed)

Team arrest depends on each climber to stop a personal fall and on the rest of the rope team to provide backup in case the attempt fails. Everyone involved uses self-belay or self-arrest.

Relying on team arrest as the ultimate team security makes sense only in selected situations, such as on a low- or moderate-angle glacier or on a moderate snow slope where a less skilled climber could be saved from a dangerous slide by the more proficient members of the rope team. On steeper, harder slopes you face that appraisal of risks, trying to decide which is safer: continuing to rely on team arrest, unroping and letting each climber go it alone, or switching to a more secure mode of roped travel.

You may be able to increase the odds that team arrest will work on a snow slope by trying the following procedures:

- Carry a few feet of rope coiled in your hand if there are any climbers below you. If a climber falls, drop the loose rope and it will give you an extra instant to get the axe into self-belay position and to brace yourself. (Note: do not carry coils on a glacier, because the extra rope simply increases the distance the victim will fall into the crevasse.)
- Put the weakest climber on the downhill end of the rope. As a rule, the least skilled climber should be last on the rope while ascending and the first on the rope while descending. This puts the climber most likely to fall in position where a fall will be of the least serious kind: below the other climbers and coming quickly onto the rope. Unfortunately, it also means the weakest climber will be the team's last hope if the climbers above fall.
- Climb on a shortened rope. This is most applicable to a two-person rope team. If a climbing pair uses only a portion of the rope—say 60 to 75 feet instead of the full length—they will reduce the sliding distance and the tug from the fall if one partner falls while above the other.
- Climb in separate parallel tracks. This is also most applicable to a two-person rope team. The climbers will be abreast of each other, separated by the rope. A falling climber will pendulum down, putting force on the rope to the side of and below the partner. The tug on the rope will be less than if

the climber fell from high above. Also, the friction of the rope as it pendulums across the snow will absorb some of the force. Traveling in separate tracks may be impractical on ascents where kicking two sets of steps would be a waste of time and energy. However, it might be used on ascents of harder snow and should be considered for any descent.

Running belays

The use of running belays (fig. 12-30) offers a middle level of protection, somewhere between team arrest and fixed belays. It can help in situations where a successful team arrest is improbable but where fixed belays aren't practical because they would take too much time. For example, running protection may do the job on long snow faces and couloirs.

To place running belays, the leader puts in pieces of snow protection as needed and uses a carabiner to clip the rope into each one. (Types of snow protection are discussed in the next section of this chapter, on snow anchors.) The climbers continue to make good progress because all members of the rope team climb at the same time, just as in unbelayed travel. Except that now there's protection in the snow that, if it is securely placed, will put an end to any fall. Traveling this way, the last



Fig. 12–30. A running belay setup

climber on the rope removes each piece. Of course the use of running protection means the team must pack the extra weight of the gear and must take the time to place it.

Fixed belays

The ultimate in safety comes from having climbers belay each other up snow pitches, in the same manner as in rock climbing. The catch is that this procedure may be so time-consuming it becomes impractical on the snow faces of major alpine routes. However, there is a wide variety of snow belays, varying in security and in the amount of time they take to set up. They are described later in this chapter.

Combination protection techniques

The reality of most serious snow climbs is that success calls for a combination of protection techniques. It's not likely a party will take on an entire climb unroped. It's just as unlikely that the party will use fixed belays all the way.

In deciding when to rope up, a climbing team is actually asking itself a series of questions. The team always ropes up on glaciers. But on snow or mixed terrain, the team asks:

1. Is each member of the party able to use self-belay or self-arrest to save himself or herself in case of a fall? If the answer is yes, the party can continue unroped. If the answer is no, the team asks:
2. Can we stop all falls by roping up and depending on team arrest? If so, rope up and continue climbing, unbelayed. If not, then ask:
3. Is it feasible to use some form of belay (a running belay or a fixed belay) and will this belay provide adequate protection? If so, begin belaying. If it's not feasible, because of poor terrain or lack of time, then the party must ask itself:
4. Shall we turn around, or shall we proceed unroped and assume the risks?

In practice, long snow routes are climbed roped and mostly unbelayed, with belays of some kind on steeper, harder snow or when climbers are tired or hurt. Most of the reliance is on team arrest or running protection, though some sections may lend themselves to unroped travel.

The option of turning around is always worth considering. If things aren't going well, select a new route, another destination, or just head home.

SNOW ANCHORS

Anchors are needed in snow for the same reasons they are needed on rock. The equipment is different but the purposes are the same: to anchor belays and rappels. But rock anchors are usually easy to inspect and predictable in performance. Snow anchors are not. They vary widely in strength depending on snow conditions and placement, and their strength changes during the day with changes in the snow. This uncertainty makes it even more imperative than on rock to check and recheck any belay or rappel anchor. Snow anchors can also require a lot of time to put in place. They include deadman anchors (such as snow flukes), pickets, and bollards.

A deadman anchor is any object you bury in the snow as a point of attachment for the rope. The most common is the snow fluke, a specially shaped aluminum plate with a metal cable attached (fig. 12-31a). Snow flukes are available in various sizes, their holding ability generally increasing with size. For maximum strength and reliability, a buried fluke should be angled back about 45 degrees from the direction of pull (fig. 12-31b). Dig a slot in the snow to permit the cable to be pulled in as direct a line as possible.

In theory, the fluke serves as a dynamic anchor, burrowing deeper into the snow when it takes a load, such as the weight of a climber on rappel. In practice, it may behave in more complicated ways, even coming out if it is tipped too far forward or back, or if the load is to the side rather than straight out. If the plate or the cable travels down into the snow and hits a harder layer, the fluke could be deflected and pull out. Flukes are available with bent faces, flanged sides, or fixed cables—features intended to make them maintain the correct orientation and to make them self-correct if deflected.

Flukes are most reliable—but also more diffi-



Fig. 12–31. Placing snow flukes: a, typical snow fluke; b, correct angle for fluke placement; c, incorrect, not angled back sufficiently; d, incorrect, no slot for cable.

cult to place—in the hard homogeneous snow of summer. They are generally used in a softer but dense pack, snow that is moist and heavy. They are least reliable under typical winter conditions, with snow layers of varying density where they may deflect off harder layers. Neither do they do well in dry, unconsolidated snow.

Ice axes, ice tools, and snow pickets can serve as deadman anchors (fig. 12-32). Bury the implement horizontally in the snow, with a runner attached at the midpoint. Cut a slot in the snow to let the runner lie in the direction of pull, and then clip into the runner.

A picket is a stake driven into the snow as an anchor (fig. 12-33). Aluminum pickets are available in lengths from 18 to 36 inches and are found in different styles, including round or oval tubes and angled or T-section stakes.

Pickets work well in snow too firm for flukes but too soft for ice screws. As with flukes, angle



Fig. 12–32. Ice axe buried as deadman anchor



Fig. 12–33. Picket placement

them back about 45 degrees from the direction of pull. Attach a carabiner or runner to the picket at the snowline—not higher on the picket, or a pull may lever it out. You can drive a picket into the snow with a rock or the side of an ice axe, but a North Wall hammer or other ice hammer works best and reduces the chance of equipment damage. An ice axe or ice tool can serve as a makeshift picket.

A bollard is a mound of snow that serves as an anchor when rope or webbing is positioned around it (fig. 12-34). Snow bollards provide highly reliable anchors for belaying or rappelling in soft snow and are possibly the most reliable in all snow conditions. There's a significant trade-off here, however. It takes a long time to build one.

Create the mound by making a trench around an oval area of snow. In hard snow, chop out the trench; in soft snow, just stamp it out. The bollard should end up as an oval-shaped island of snow. The softer the snow, the broader and deeper the bollard must be: up to 10 feet wide and $1^{1}/_{2}$ feet deep.

Try to use webbing around the bollard instead of rope because it's less likely to saw into the mound. For the same reason, avoid pulling on the rope or webbing after placing it. For more security, pad the rope or webbing with packs and clothing and whatever, especially in soft snow. For safety, inspect the bollard after each use to see it hasn't been damaged. You can also back up the bollard with a picket or fluke (which the last person on a rappel removes before rappelling).



Fig. 12–34. Snow bollard

Multiple anchors are the best insurance because of the inherent weakness and unpredictability of snow anchors. As with questionable anchors in rock, multiple anchors are safest. Two anchors can be chained sequentially so that the first takes the hit, but has a backup to absorb any remaining force. Or they can be connected in a way that will permit them to share any load (fig. 12-35). (More details and illustrations on joining multiple anchors are in Chapters 7, 8, and 10.) In general, place multiple snow anchors one behind the other to reduce the angle of pull and the potential load on the surviving anchor if the other one fails. Keep the anchors several feet apart so they don't end up sharing any localized weakness in the snow.

BELAYING ON SNOW

Snow climbers choose from a catalog of techniques that provide belay protection to their ropemates. They sometimes give belays using established snow anchors, and sometimes they give quicker and less formal belays using the ice axe. The changeable nature of snow and the difficulty of inspecting snow protection usually result in anchors that can't be considered bombproof like a good anchor in rock. But they are still effective because most mishaps on snow do not generate the high loads of rock-climbing falls. Snow falls are usually slides on relatively moderate (30- to 60-degree) slopes, with help from the friction of rope against snow and with no direct vertical pull.

No matter what the belaying technique, every snow belay should be as dynamic as possible to help limit the force on the anchor. The dynamic, shock-absorbing quality of climbing rope helps minimize chances of an abrupt, static stop to a fall. As a belayer, plan your stance so the force is taken on your body and dissipated as much as possible by the belay and the dynamic quality of the rope. The standard hip belay provides a more gradual, dynamic belay than mechanical belay devices. Think of the consequences if a heavy hit on a question-



Fig. 12–35. Two methods of connecting snow anchors: a, two pickets linked serially, top anchor supports lower anchor; b, two independent anchors with equalized connecting runner.



Fig. 12–36. Boot-axe belay

able snow belay yanks you and any anchor off your perch.

Set up a belay close to the climbing difficulties. If you're belaying the lead climber, get out of the line of fire by setting up the belay stance to one side of the fall line—not within it. If the leader is heading up on a diagonal, get outside any point where the climber's route could cross directly above you. On a ridge crest, it is not always possible to predict a fall line and plan a belay in advance. If a ropemate slips off one side of the ridge, the best reaction may actually be to jump off the opposite side, with the rope running over the ridge saving you both.

Quick belays

Snow climbers have a couple of quick belays for times the consequences of a fall would not be great, as in a sliding pendulum across a snow face. They are useful for belaying a climber who is probing a cornice or crevasse edge, or for providing a top belay to a weaker climber.

The boot-axe belay is a fast and easy way to provide protection as a rope team moves up together (fig. 12-36). Despite some naysayers, it has proven to be useful, provided its principal limitation is understood: it can't be expected to hold a high fall force. With thorough practice, you should be able to set up this belay in a couple of seconds with a jab of the ice axe and a quick sweep of the rope.

Step by step, here is how to do it (and after trying it a few times, you'll realize it is not as complicated as it sounds):

1. Stamp a firm platform in the snow, big enough for the axe and uphill boot.
2. Jam the ice-axe shaft as deeply as possible into the snow at the rear of the platform, the shaft tilted slightly uphill against a possible fall. Have the pick perpendicular to the fall line, thus applying the broadest side of the shaft against the force of a fall.
3. Stand below the axe, at approximately a right angle to the fall line and facing the side on which the climber's route lies.
4. Plant your uphill boot into the snow against the downhill side of the shaft, bracing it against a downward pull.
5. Plant the downhill boot in a firmly compacted step far enough below the other boot so that the downhill leg is straight, providing a stiff brace.
6. Flip the rope around the axe. The final configuration will have the rope running from the direction of potential load, across the toe of the uphill boot, around the uphill side of the axe, then back across the boot above the instep.
7. Hold the rope with the downhill (braking) hand, applying extra friction by bringing the rope uphill behind the heel, forming an S-

bend. The braking hand must never leave the rope.

8. Use the uphill hand for two jobs: to grasp the head of the axe to further brace the shaft and then, as the belayed climber moves upward, to take in rope.

Climbers must be equally adept at setting up the boot-axe belay with either foot uphill, because it is essential that the belayer face the climber's fall line. If a lead climber falls behind the belay, the rope unwraps from the axe and there is no belay.

The carabiner/ice-axe belay provides the same level of security as a boot-axe belay, with easier rope handling (fig. 12-37). To set it up, plant the axe as deeply as possible, the pick perpendicular to the fall line. Attach a very short sling with a girth hitch to the axe shaft at snowline and clip on a carabiner. Stand at right angles to the fall line, facing the same side as the climber's route. Brace the axe with your uphill boot, standing atop the sling but leaving the carabiner exposed. (Keep crampons off the sling.) The rope runs from the potential direction of pull up through the carabiner, then around the back of your waist and into your uphill (braking) hand. One nice thing about the carabiner/ice-axe belay: the force of a fall pulls the belayer more firmly into the stance.



Fig. 12–37. Carabiner/ice-axe belay



Fig. 12–38. Sitting hip belay

Anchored belays

Other snow belays usually are used with formal anchors, such as flukes, pickets, or bollards.

The sitting hip belay, with an anchor, is inherently dynamic and very secure on hard snow or deep, heavy, wet snow (fig. 12-38). The sitting belayer may face the prospect of a cold, wet assignment, and the belay can be difficult to work if the rope is frozen.

To set up the belay, stamp or chop a seat in the snow plus a platform to brace each boot against. Put down a pack, ensolite pad, or other material as insulation from the snow, then settle into a standard hip belay, with outstretched, stiffened legs.

The standing hip belay is easier to set up than a sitting hip belay, as it needs only deep, secure slots for each boot. However, it is far less secure because the belayer tends to be toppled under the force of a fall. Standing hip belays must be backed up with an anchor.

These belays can be arranged so the climber faces into the slope, out from the slope, or sideways. Facing into the slope is the poorest choice because the belayer will be completely wrapped by the rope if the climber falls below the belay stance. And it is difficult to pay out rope for a smooth belay. Facing out is an improvement because it gives a less complete wrap around the belayer and also permits a view of a fall below, important in timing a dynamic belay. But it shares a major weakness with the face-in stance: no way to brace the legs against toppling downhill. In both stances, the belayer should lean into the slope, against a downhill pull.

For the most reliable standing hip belay, stand sideways, facing the same side as the climber's route (fig. 12-39). The downhill leg is straight, locked at the knee, and braced in a snow slot. The uphill leg is on a line with the downhill leg and the direction of a potential fall. The downhill hand should be the braking hand to allow best control for a gradual dynamic belay.

Mechanical belay devices can be used in snow belaying. They are easy to set up and operate even with wet or icy ropes. With a device, you can belay directly from the anchor rather than from your seat harness, permitting you to get into a drier, more comfortable position. Be aware that belay devices provide a less dynamic belay than a hip belay, increasing the peak force of a fall on questionable snow anchors.



Fig. 12–39. Standing hip belay

ROUTEFINDING ON SNOW

Snow gives us passage over some frustrating obstacles, such as tundra, talus, brush, streams, and logging debris. At its best, it provides a smooth, uniform surface and a straight shot up the mountain. But because its very nature means it constantly changes, we always have to study typical seasonal weather patterns as well as current reports for an idea of what conditions to expect on any climb.

Snow can be too soft to support our weight, or it can be hard and slick. It covers obstacles in our path, but it also obscures trails, cairns, and other guideposts to the route, especially above tree line. Dangers often lie beneath the surface: crevasses, moats, or creeks hidden by a thin snow cover. Unstable slopes avalanche.

You can minimize the frustrations and dangers of snow by studying the medium. (The appendix in this book on ''The Cycle of Snow'' provides information on snow formation, types of snow, and the creation of glaciers.) Mountaineers let the snow work for them. They read the snow surface and terrain features to determine a safe, efficient route.

SURFACE CONSIDERATIONS

Evaluating the snow surface begins before you even leave home, by considering the effects of both the current weather and of conditions over the last several months.

If you are climbing during a cold, snowy spring following a prolonged late-winter thaw, the thaw's thick crust could hold a heavy load of spring snow ready to avalanche. If spring is cold but sunny, and follows a winter with little snow, a gully that usually offers good step-kicking in May could be filled with rock-hard consolidated snow. However, much of the change in the snow surface takes place rather quickly, so the weather just before and during a climb is the most important.

The best snow, from a mountaineer's point of view, is snow that is safe from avalanche and that will comfortably support a climber's weight for easy step-kicking. Such snow exists, but you have to seek it out. Location of the best snow varies from day to day, even from hour to hour. If the snow is slushy in one spot, or too hard or too crusty or too something, look around: there may be better snow a few feet away.

Here are some tips for making best use of the snow surface:

- Find patches of firmer snow on a slushy slope by walking in shade or using suncups as stairs.
- Try to find patches of softer snow on a slope that is too firm for good step-kicking.
- When the going is difficult, detour toward any surface with a different appearance and possibly more comfortable support.
- Use a different descent route if necessary to find the best snow.
- If you want a firmer surface, look for dirty snow, which absorbs more heat and therefore consolidates more quickly than clean snow.
- Remember that south and west slopes in the Northern Hemisphere, bearing the heat of afternoon sun, consolidate earlier in the season and quicker after storms. They offer hard surfaces when east and north slopes are still soft and unstable.
- Get an early start after a clear, cold night that follows a hot day, in order to take advantage of strong crusts on open slopes before they melt.
- Beware of the hidden holes next to logs, trees, and rocks, where the snow has melted away from these warmer surfaces.
- If you don't like the snow conditions on one side of a ridge, gully, clump of trees, or large boulder, try the other side. The difference may be just what you need.

TERRAIN CONSIDERATIONS

Major terrain features present both obstacles and opportunities (fig. 12-40). Some you use, some you avoid, but they all have to be reckoned with.

Couloirs

A main avenue for all mountain climbing is provided by angled gullies (couloirs). They can hold the key to upward progress because their overall angle is often less than that of the cliffs they breach, offering less technical climbing.

Deeply shaded couloirs are more often lined with ice than snow, especially in late season. Even in spring, however, when open slopes are deep in slush, the couloirs are likely to hold hard snow or ice caused by freezing or avalanche scouring.

Safe passage through a couloir usually depends on the time of day. They can be safe in early morning when the snow is solid and rocks and ice are frozen in place. It's often a different story later in the day, when they can turn deadly. Gullies are the garbage chutes of mountains and with the arrival of the sun they begin to carry down such rubbish as avalanching snow, rocks loosened by frost-wedging, and ice blocks weakened by melting. Most of the debris comes down the center. But even if you keep to the sides, listen for suspicious sounds from above and keep an eye out for quiet slides and silent falling rock.

Avalanches erode deep ruts in many steep couloirs. Climbers usually avoid these ruts or cross them rapidly. However, early in the year the floors of the ruts offer the soundest snow available, and in cold weather they may be quite safe, particularly for a fast descent. Try to be out of a couloir before the sun hits. This means an early start for a round trip, or else a bivouac or an alternative descent route.

Couloirs can become increasingly nasty the higher they are ascended, presenting extreme steepness, verglas, moats, rubble strewn loosely over smooth rock slabs, and cornices. Many lead to difficulties, as when the gentle angle at the bot-


1
2
4
20
3
18
5
19
17
21
10
6
9
7
33
9
10
11
12
13
8
14
15
16



Fig. 12–40. Alpine terrain features

1. Horn or aiguille
2. Ridge
3. Rock arete
4. Cornice
5. Glacier basin
6. Seracs
7. Fallen seracs
8. Erratic blocks
9. Icefall
10. Glacier
11. Crevasses
12. Lateral moraine
13. Snout
14. Moraine lake
15. Terminal moraine
16. Glacial runoff
17. Rock band
18. Shoulder
19. Col
20. Coulior or gully
21. Bergschrund
22. Hanging glacier
23. Buttress
24. Cirque or bowl
25. Headwall
26. Flutings
27. Ice wall
28. Summit
29. Ice arete
30. Towers or gendarmes
31. Avalanche chute
32. Avalanche debris
33. Snowfield

tom is more than balanced by a frosty vertical chimney at the top. However, when the couloir ends at a col (small, high pass), it can offer a lower average angle than the face.

If the bed of the couloir is too steep, try the moat along the sides, formed when the snow melts and settles away from the rock. Moats can be rather deep and will vary in width. Portions of a moat can require bridging between the snow and the rock wall, while other parts present either a tight squeeze or a gap too wide to bridge. You might crampon or step-cut up the couloir, and then drop into the moat on the way down to avoid a nerve-wracking descent on steep ice and exposure to rockfall.

Despite the problems, many snow and ice routes follow couloirs. The techniques are usually simple cramponing and step-kicking, but the frequent presence of moats, crevasses, suncups, and blocks of fallen rock and ice make rock-climbing techniques useful. Some of these irregularities are welcome as a good place to set up a belay.

Ridges

Routes along a ridge crest are free of rockfall and avalanche hazard, so they can be the best choice for a long ascent in a region of moderate to heavy snowfall. Routefinding on a ridge top is generally easier than other places on the mountain, and you can usually find a safe way to retreat. Ridge routes take the full brunt of wind and bad weather, but the most significant hazard of ridge routes is presented by cornices.

Cornices

The shape of a ridge crest helps determine the extent of cornice-building (fig. 12-41). A ridge that slopes on one side and breaks into an abrupt cliff on the other is a good candidate for a gigantic cornice. A knife-edge ridge or one gentle on both sides will have only a tiny cornice, if any at all.

When the physical features are right for building cornices, wind direction decides their exact location. Because storm winds have definite patterns in each mountain range, most cornices in the same area face the same way. In the Pacific Northwest region of the United States, for example, most storms blow from the southwest so the wind-drifted snow of the cornices mostly overhangs on the north and east. These same northern and eastern exposures were steepened by past glaciation, making the ridges ideally shaped for cornice formation.



Fig. 12–41. Cornice building

Temporary or local wind deflection can contradict the general pattern. In rare instances cornices are even built one atop the other, facing in opposite directions, the lower one partially destroyed and hidden by later formations.

Approaching from windward: A cornice gives little sign of its presence as you approach from windward. It simply appears to be a smooth snow slope that runs out to meet the sky. Look at nearby ridges for an idea of the frequency, size, and location of cornices in the area.

Not every snowy ridge conceals a cornice—but be sure to find out whether the ridge you are on does. Try to view the lee side of the ridge from a safe vantage point, such as a rock or tree jutting through the crest. If you can't, have a belayed climber approach the ridge at right angles while probing with an ice axe or reversed ski pole to see if the snow is solid. Look for a crack or indentation in the snow, which could indicate a cornice that has partially collapsed.

It's hard to judge the extent of a cornice overhang and the danger it presents. Don't be misled by appearances. For a mature cornice, the probable line of fracture could be 30 feet or more back from the lip—no doubt farther back than an examination would lead you to expect. And although rocks and trees projecting from the snow suggest safety, they could be on the tops of buttresses with a connecting ridge that curves far back into bays supporting wide cornices. Lots of climbers have had the enlightening experience of looking back along a ridge and discovering their tracks on snow poised above a chasm. The safe course along a corniced crest is well behind the probable fracture line.

Approaching from leeward: You can't miss a cornice from the leeward side. Resembling a wave frozen in the act of breaking, a large cornice close above you is an awesome sight. If you doubt the stability of the cornice, stay among trees or on spur crests as you travel below it. At times, it's quite safe to climb under a cornice. The colder the weather, the more secure the cornice. A late-season cornice, almost completely broken down, is not a problem.

Climbers sometimes even push directly through a cornice to force their way to a ridge crest or pass. It's easiest to penetrate an overhang at a rock spur or where the cornice already has partially collapsed. The leader cuts straight uphill at the point of least overhang, undermining as little of the mass as possible. Generally though, the safest bet with cornices is to avoid traveling on them, under them, or through them.

Bergschrunds

A bergschrund is the giant crevasse found at the upper limit of glacier movement, formed where the moving glacier breaks away from the ice cap. The downhill lip of the bergschrund can be considerably lower than the uphill edge, which may be overhanging. Sometimes the bergschrund is the final problem of the ascent.

Moats

The gap that separates a snowfield from its rock borders is a moat, formed when the snow melts and settles away from the warmer rock. Crossing a moat at the top of a snowfield can be as tough as getting past a bergschrund, with the main difference being that the far wall of a moat is rock instead of snow.

Rockfall hazard

Snowfields and glaciers are prime targets for rockfall from bordering walls and ridges—especially on volcanic peaks, where the rock is often rotten and unstable. Climbers can reduce rockfall danger by wearing hard hats in hazardous areas and by timing climbs for less dangerous periods.

Early-season outings usually face less rockfall than summer climbs because snow still helps cement loose rock in place. Whatever the season, the general rule for glacier climbs is "early on and early off." Nighttime cold often freezes rock in place and prevents most rockfall, but direct sun melts the bonds. The greatest hazard comes in the morning when sun melts the ice, and in evening when meltwater expands as it refreezes, breaking rocks loose.

In the Northern Hemisphere, southern and eastern slopes get the sun first, and therefore should be climbed very early. The shadier northern exposures usually offer less rockfall danger.

ROUTEFINDING AIDS

Crossing a snowfield or glacier, especially at night or in a white-out, can feel like being at sea, without landmarks. However, mountaineers have a couple of navigational opportunities denied to mariners. Mountaineers have a solid surface for planting their own landmarks (wands), and they experience changes in elevation that can be measured by an altimeter as a way to show progress.

The thin bamboo wands topped with tiny flags are left to mark the return route. Try to place wands so that on the return, the next one is visible when the last member of the party is at the previous wand. Coordinate communication so the last person doesn't leave that wand until the next one is sighted. The wands can also be used to mark points of danger (such as moats and crevasses), changes in direction, the boundaries of safe areas for unroped walking in camp, and the location of buried supplies (caches).

An altimeter helps determine your progress and location when you use it along with a topographic map and compass, especially above timberline on a large snowfield with few natural features. You may know that an established camp is located at 11,000 feet, 5 miles due east of the trailhead. By determining the elevation periodically with an altimeter and then finding that elevation on the map along the route, you can find just where you are and how far you have to go. Also relate the altimeter's findings to natural features whenever possible. If you know you are supposed to cross a ridge at an elevation of 9,500 feet in order to keep on the right track to the camp, check the altimeter when you hit the crest. You'll get a good indication of whether you have topped the ridge at the right spot.

A good routefinder uses a variety of tools to stay on route or reach a destination, including compass, map, altimeter, wands, cairns, sun, and visual landmarks. The creative use of several methods becomes especially important when visibility is poor.

AVALANCHES

Avalanches are the number-one hazard facing snow travelers. Avalanche hazard and the conditions that create it are fairly easy to recognize, though there's no way to predict an individual avalanche. Whenever the strength and cohesion of snow on a slope are no longer enough to support the accumulated weight of the snow, an avalanche is due.

Evaluating the stability of a specific snow pack is highly technical work, beyond the scope of this book. A little knowledge about digging snow pits or studying snow crystals sometimes does nothing but give climbers a false sense of security as they rely on an evaluation that may be little more than guesswork. However, climbers do need to learn to recognize generally hazardous terrain and weather.

Four out of five avalanches strike during and just after a storm. Danger increases rapidly with snowfall of an inch or more per hour, or accumulations of a foot or more. Storms starting with low temperature and dry snow, followed by rising temperatures, are even more likely to set up avalanche conditions. The dry snow forms a poor bond, without strength to support the heavier snow that falls later in the storm. Rainstorms, or spring weather with warm winds and cloudy nights, can result in water percolating into the snow and causing wet-snow avalanches. Rapid changes in temperature and wind increase avalanche danger.

Be prepared for two types of avalanches.



Fig. 12–42. Slab avalanche

A slab avalanche has an obvious fracture line at the top (fig. 12-42). The avalanche is a large area of snow that begins to move suddenly at the same time, sliding on a weak layer within the snowpack or on the ground. The snow in a slab avalanche can be from soft to hard, from wet to dry.

A loose-snow avalanche, on the other hand, starts at one point and grows in size as it slips



Fig. 12–43. Loose-snow avalanche

Hazard Evaluation Summary

Note: **Bold type** indicates the most critical factors in the evalution.

1. COULD THE SLOPE PRODUCE AVALANCHES?

Is the slope steep enough to slide?

- ☐ **Slopes greater than 25°**
- ☐ Variations in incline — cliff bands

What's the orientation of the slope to wind?

- ☐ **Lee slopes**

What's the orientation of the slope to sun?

- ☐ **S and SW slopes exposed to strong radiation.**
- ☐ First major thaw of spring

What's the nature of the slope?

- ☐ **Open slopes**
- ☐ Thin forest
- ☐ Confined slide path — gully or bowl
- ☐ Weak areas that might initiate failure

2. IS THE SNOW STABLE? COULD IT FAIL?

How deep is the snowpack?

Are there any signs of avalanche activity?

What layers are there in the snowpack?

- ☐ **Very hard or soft layers**
- ☐ Weak bond between layers
- ☐ 30 cm or more of snow above a weak layer
- ☐ Loose, cold snow
- ☐ Wet snow

How much snow has fallen?

- ☐ **Snowfall greater than 2 cm (3/4 in.) per hour**
- ☐ New snow depth greater than 30 cm (12 in.)
- ☐ Slow settlement of new snow
- ☐ Very light or very heavy snow
- ☐ Heavily rimed crystals, graupel
- ☐ Heavy stiff layer above a light weak layer
- ☐ Heavy rain
- ☐ Very easy or easy shovel test on new snow layer

Wind

- ☐ **Moderate or strong wind**
- ☐ Cracking and settling of snow

Air temperature

- ☐ **Rapid rise in temperature**
- ☐ Above freezing temperatures
- ☐ Sun on slope under consideration
- ☐ Sun with hazy sky
- ☐ Temperature inversions

Humidity

- ☐ **High relative humidity during snowfall or during periods of moderate and strong wind.**

3. WHAT WILL HAPPEN TO ME IF THE SLOPE AVALANCHES?

Depth of avalanche

- ☐ **Deep weak layers in snowpack**
- ☐ Foot penetration greater than 60 cm

Type of avalanche

- ☐ **Stiff slab above weak layers**
- ☐ Slope has not yet avalanched recently

Terrain

- ☐ **Long open slope above**
- ☐ Restricted deposition zone
- ☐ Drop-off below
- ☐ Trees to wrap around

4. WILL CONDITIONS GET WORSE?

- ☐ **Continuing snowfall**
- ☐ Increasing temperature
- ☐ Strong wind

Fig. 12–44. Hazard evaluation summary (reproduced by permission of the author from Avalanche Safety for Skiers & Climbers *by Tony Daffern, Rocky Mountain Books, 1983)*

downhill (fig. 12-43). The snow has little internal cohesion. There is no obvious fracture line and no clear layer where the sliding snow separates from snow beneath. A loose-snow avalanche can be wet and loose or soft and dry.

RECOGNIZING HAZARDOUS TERRAIN

It's easy to spot large slopes and wide swaths of avalanche activity. You'll get a lot of additional information on hazardous terrain by taking into account the time of year, previous weather, prevailing winds, snow characteristics, and the lay of the land (fig. 12-44). The classic law of avalanches says mountaineers face the least danger on ridges, more on the valley floor, and most on the slopes. Let's look first at the biggest danger zone.

The slopes

On slopes, danger comes in many shapes, angles, and sizes.

Slope angles between 30 and 45 degrees are the main originators of avalanches, although slides can start on inclines from 25 to 55 degrees (fig. 12-45). Angles above 55 degrees are generally too steep to collect a lot of snow, which tends to sluff off immediately after falling. Angles lower than 25 degrees are usually safe except for danger from very wet, and usually slow, avalanches. Climbers commonly overestimate the angle of a slope. Get a clinometer, built into a compass or as a separate instrument, if you want to end the guesswork.



Fig. 12–45. The frequency of avalanches on slopes of various angles

Slope shapes also affect the hazard (fig. 12-46). Snow on a slope that is straight, open, and moderately steep presents the most obvious danger. Snow on a convex slope, under tension as it stretches tightly over the curve of the hill, is more prone to avalanche than snow on a concave slope. Coming down a convex slope, you may not know how steep it will get until you're past the curve obstructing your view and are down on the face. Regardless of the shape of the slope, look at them all, large and small, for avalanche hazard. They all can slide.



Fig. 12–46. Convex and concave slopes

Bowls and cirques have a shape that invites wind-deposited snow. Once an avalanche starts, it often spreads to an entire face and dumps a great depth of snow into the constricted area below.

Couloirs are enticing, because they offer a direct route up a mountainside, and intimidating, because they are natural avalanche chutes. Always weigh the merits of these gullies against the dangers, and trust them only at certain times under certain conditions. Take into acccount the snow conditions and the amount of snow both in the couloir and adjoining slopes. A slide on a slope within the drainage system of a couloir can sweep the main channel. This slide, by undercutting every tributary on its descent, may pick up bigger loads or leave the tributaries poised and ready to dump their loads at the slightest provocation. Beware of lower-angled couloirs and canyons that are obvious collection areas for avalanche debris.

Forested slopes offer some protection but don't put too much trust in trees. Slides aren't likely to originate in a dense forest, but they can smash through from above. Look around as you climb. Do you spot shattered trees in avalanche fans, and wide swaths cut through old timber? This is evidence of large avalanches penetrating even thick forest. Does a slope grow only brush and small trees, all downslanting? This is probably a slope that avalanches so often that timber has no chance to grow. Are tree limbs missing from the uphill side in open timber? It might be the result of avalanches. There's little or no avalanche protection in open timber, such as you can easily ski through. Another type of vegetation—grass—can increase avalanche danger by providing a slick surface for a slide.

Valleys and flat terrain

In a valley, the question to ask is whether an avalanche on the slopes above could reach you. The danger is obvious in a narrow-floored canyon, but large avalanches have swept for more than a mile across a valley, even climbing the opposite wall. As you trek through a valley, keep an eye out for damaged trees and other signs of avalanching. Remember to pitch tents outside the potential reach of an avalanche.

A route beneath a cliff is a gamble unless you're convinced that conditions are in your favor. Cliffs above flat terrain may harbor cornices, icicles, or ledges piled high with snow—temporarily. All this stuff is ready to drop, and if it doesn't get your party, it could start an avalanche that will.

Ridges

Safe at last! Well, perhaps not quite. A ridge, especially a forested ridge, is usually the safest route when the avalanche hazard is high. However, a ridge presents its own problems of cornices and of crests that can be too jagged to serve as a practical route.

The elements

Climbers pay attention to how sun and wind hit a slope for invaluable clues to avalanche danger.

The sun

The direction a slope faces determines how much sun it gets—and this tells a great deal about its avalanche potential. Here's how it works in the Northern Hemisphere, and of course it's just the opposite on mountains south of the equator.

South-facing slopes receive more sun, and therefore snow settles and stabilizes faster than on northern slopes. In general (with plenty of local exceptions), this makes south-facing slopes safer in winter. They also release avalanches sooner after a storm, so if they are avalanching it's an indication that slopes facing in other directions may soon follow their lead. As warmer spring and summer days arrive, south slopes become prone to wet-snow avalanches and north-facing slopes may be safer.

North-facing slopes receive little or no sun in the winter, so consolidation of the snowpack takes longer. Colder temperatures cause depth hoar within the snowpack, creating weak layers. Therefore, in general (again with local exceptions), north slopes are more likely to slide in midwinter. In spring and summer, as south slopes become dangerously soft, look to the north side for firmer, safer snow.

The wind

Windward slopes—those that face into the wind—tend to be safer. They retain less snow because the wind blows some of it away, and what snow remains is compacted by the blast of the wind.

Lee slopes—those that face the same way the wind is blowing—collect snow rapidly during storms and on windy days as snow blows over from the windward slopes. The result is cornices on the lee side of ridges, snow that is deeper and less consolidated, and formation of wind slabs ready to avalanche.

The snow is full of clues to the prevailing wind direction. Cornices face the same way the wind is blowing. Deposits of rime, on the other hand, face into the wind: the larger the deposits, the stronger the wind. The steep faces of sastrugi and the rounded ends of snow drifts around trees and rocks also head into the wind (fig. 12-47).

Snow characteristics

Take a close at the nearby snow for more information on avalanche hazard. Are there new avalanches in the area? Do you see cracks close by, indicating you are on an unstable slab? Does an area of snow settle as you walk across it, again warning of a slab that could slide? Does the snow settle with a loud thump, indicating a hard slab ready to release?

The stability of the snow can be tested by probing with an ice axe or ski pole to feel for layers of varying solidity or by digging a pit to examine the layers for weakness. Specialized publications give details of these tests, which are mainly used during winter travel.

MINIMIZING THE RISK

Climbers have many ways to minimize the risk of avalanches and increase their chances of survival if one hits. These efforts begin before they leave home and continue throughout the climb. It's obvious advice, but check the weather report before starting the trip. Heed the detailed avalanche hazard reports prepared by agencies in many mountain areas. Talk to people with local knowledge.

Plan the route before getting under way, but be ready to adjust it depending on conditions. Lots of factors influence avalanche safety, and a problem with any one of them should be grounds to rethink your well-laid plans. During periods of general danger, are you willing to travel only in the morning and evening, when avalanche danger is lowest? Do you have a retreat route in mind? Are you prepared for an emergency bivouac? And don't let summit lust outweigh safety. The safest course might be to go home, or not to leave in the first place.

How to cross a questionable slope

Nobody likes it, but sometimes there's no way to avoid questionable avalanche terrain. The problem then is to make the passage with the least danger of disturbing the slope, and to minimize the consequences if the climbers set off an avalanche or one sweeps down from above.

Before heading out onto a questionable slope, check that your electronic avalanche rescue beacon is switched to the transmit position. Everyone in



Fig. 12–47. Wind-blown snow: a, sastrugi; b, rime-coated trees

the party should carry one of the small battery-powered devices. If one climber is carried away by an avalanche, the others switch their devices to receive and then use the signal from the buried beacon to find the victim.

After you've checked your avalanche beacon, put on mittens and warm clothing. Get set to jettison your gear so it can't drag you down in the event of an avalanche. Loosen the shoulder straps and undo the waist and chest bands on your pack.

When the route lies up a slope, head straight up the fall line instead of switchbacking, which undercuts the snow. Only one person moves at a time, and everyone else watches from safe places, ready to shout if a slide starts. If the climber is on belay, don't tie the rope directly to the belayer, who would risk being pulled in if it proved impossible to stop a climber hit by a wet, heavy avalanche.

On a traverse, it's usually best to take it as high up the slope as possible, above most of the dangerous snow. Again, only one person moves at a time. Cross gingerly, with long, smooth strides, being careful not to cut a trench across the slope. Each climber follows in turn, stepping in the leader's footprints. Everyone listens and watches for an avalanche.

How to survive an avalanche

If you're caught, don't give up. Yell to your partners. Throw off equipment, pack, skis, anything and everything you can get rid of. At the start, grab a rock or tree, or stab your axe or ski pole into the underlying snow, and hold on. Try to stop before you're swept away. If that doesn't work, swim. Stay on the surface by using swimming motions, flailing arms and legs, or by rolling.

Close your mouth if your head goes below the surface. As the snow slows, try to stand up if your feet are below you. If you are buried, try to make a breathing space by putting your elbow or hand in front of your face. Inhale deeply before the snow stops, in order to expand your ribs. As the snow closes around you, it will become impossible to move. Don't shout or struggle. Conserve oxygen and energy. Your partners know what to do, and they have begun rescue efforts.

RESCUE

The rescue effort starts even before the avalanche has stopped. The first step in a successful rescue is a tough one in the shock of the moment: someone must pay attention to where a victim is first caught, where the person disappears beneath the snow, and where the point of disappearance on the moving surface of the avalanche finally stops—and be able to relate these three points to fixed objects, such as trees or rocks. With this information, the search area is immediately reduced in size.

Then mark these three points and search. Do NOT go for help. This is a critical principle of avalanche rescue. Do not go for help. The chance of a person surviving depends almost certainly on everyone staying put, searching efficiently, and digging the victim from the snow. You can go for help after the victim is unburied or all search efforts turn out to be futile.

Select a search leader so the operation will be thorough and methodical. Approach the scene carefully, posting an avalanche lookout in case of another slide. Start with a quick scuff search of the snow surface, looking for someone partially buried, any castoff equipment, or any logical spot the victim might have come to a stop against a tree or rock. The missing climber could turn up in this quick and immediate search. If not, the next step is a thorough search with avalanche beacons, if the climbers are carrying them, or with snow probes if they are not.

Probing

A probe is anything you can use to poke into the snow in hopes of feeling the victim's body, such as wands, ski poles, ice axes, or commercial snow probe poles. Probing is a slow and uncertain mechanical process, but it's all there is in lieu of avalanche beacons. Probe first at likely areas—near pieces of the victim's equipment, at the marked points of disappearance, and around trees and rocks. Then set up a probe line.

The probe line must be highly organized and methodical. Searchers stand elbow to elbow in a line and insert their probes once between their feet. They take one step forward, uphill along the most likely search route, and probe again. Another step, another probe, each movement in unison at the spoken command of the leader. If a searcher hits something, they dig in that spot. After one run up the slope, the probe line moves to one side of the original course and probes some more, again starting at the bottom and probing uphill.

Searching with avalanche rescue beacons

The small electronic device known as an avalanche rescue beacon is the principal tool for finding buried victims.

A rescue beacon can be switched to either transmit or receive signals at a set radio frequency. Rescue depends on each member of a climbing party carrying a beacon, which during the climb is left switched on to the transmit mode. Searchers switch their beacons to the receive mode to zero in on the automatic transmission from a victim. A rescuer who has taken the time to practice with the battery-powered beacon, also called an avalanche transceiver, should locate a victim in short order.

Climbers will encounter beacons that use a frequency of 2275 hertz (most common in North America) or 457 kilohertz. The United States is switching to the world-standard 457 kilohertz frequency, with the change to be completed at the end of 1995. In the meantime, to avoid incompatibility, the American Association of Avalanche Professionals recommends the use of only 2275 hertz or dual frequency beacons through the end of 1995, and 457 kilohertz or dual frequency beacons only after 1995. Some models transmit both frequencies at the same time.

The main thing is that all the beacons in a climbing party transmit and receive a frequency in common. The workings are packaged in a crush-proof case inside a pouch that a climber typically straps around the neck and carries under the shirt. The device comes out for rescue work, and the searcher listens for transmissions through a tiny earphone carried with the beacon.

Initial beacon search

If the original quick scuff search for an avalanche victim turns up nothing, start an organized beacon search. The leader checks every beacon to be sure they are switched from transmit to receive. A line of searchers spaced no more than 60 feet apart across the slope starts where the victim was last seen and works its way downhill.

Put the volume control all the way up on every beacon. Move in unison, stay in a straight line, and keep talk to a minimum. Searchers stop every 10 paces and slowly rotate their beacons left and right, then front and back, listening closely for a signal. When a signal is picked up, one or two persons start to track down the sound with a final beacon search. (If there is more than one victim, the rest of the line continues its work. As each victim is found, turn off his or her beacon so searchers won't continue to pick up those signals.)

Final beacon search

Using a single rescue beacon, the final searchers follow a very critical series of steps to zero in on the signal from the buried victim (fig. 12-48). This is what they do:

First of all, orient the beacon for maximum signal strength, moving the unit back and forth, front and back, to find the best position. Then reduce volume as low as possible while still hearing the signal. Keep the beacon in the same orientation as you walk in any straight line. As soon as the signal reaches a peak and begins to drop, again reorient the beacon for maximum signal, and then reduce the volume as low as possible. Holding this orientation, continue on the same path. When the signal fades out, mark the spot.

Without changing orientation of the beacon, turn yourself around and retrace the same pathway. When the signal fades out again, mark that spot. You now have a straight line bracketed at the end by points where the signal disappears. Run to the center of this bracketed line and make a 90-degree turn. Repeat the process. Reorient the beacon for maximum signal, reduce volume to the minimum, and walk in a straight line until the signal fades out. Mark the spot, turn around without disturbing


Point of second
signal decline
Point of first
signal decline
a
First
bracket
Point of second
signal decline
Point of first
signal decline
b
Signal
detected
c

Fig. 12–48. Beacon search bracketing: a, first bracket; b, second bracket; c, summary of beacon search bracketing. (Illustrations by Ray Smutek, reprinted by permission, from "Avalanche Beacons." Summit *[March–April] 1984.)*

orientation of the beacon, and retrace your steps until the signal again disappears. You now have another straight line bracketed by two fade-out points. Run to the center of this new line and again make a 90-degree turn.

Work fast and efficiently, without worrying too much about precision. Continue this process of making bracketed lines until the distance between fade-out points on a line is less than 6 feet. You are now very close to the victim.

Finally, on hands and knees pinpoint your missing partner by moving the beacon from side to side and front to back in a small criss-cross. A loud signal when the volume control is down means you are close. Then dig. Use the beacon to recheck the victim's location with each 2 feet that you dig down. You have successfully found your stricken partner as quickly as possible.

• 13 •

GLACIER TRAVEL AND CREVASSE RESCUE

Traveling on a glacier is just like crossing any other field of snow, except for the crevasses. They say there's nothing worse than fear of the unknown, and perhaps that's what makes crevasses special. Many of them are hidden, they are deep and cold and scary, and they will kill you if you don't know what you're doing. The purpose of this chapter is to show you how to spot crevasses and stay clear of them, and how to get out if you fall in.

HOW CREVASSES FORM

Think of a glacier as a frozen river flowing slowly down the mountain (figs. 13-1 and 13-2). When the slope steepens, the glacier flows faster. Just as rivers form rapids, glaciers form crescentic crevasses when ice on steeper pitches flows faster and breaks away from slower moving ice above.


ACCUMULATION ZONE
ABLATION ZONE
MOAT
SNOWFIELD
BERGSCHRUND
FIRN LINE
SNOW AND NÉVÉ
SNOW BRIDGE
ICE
ICE FALL
CREVASSES
NUNATAK
MORAINE
ROCK
EH

Fig. 13–1. Cross-section of a glacier showing principal features



Ice features

1. Moat
2. Bergschrund
3. Crescentic crevasses
4. Firn line
5. Nunatak
6. Marginal crevasses
7. En echelon crevasses
8. Terminus or snout
9. Braided outwash stream

Moraine features

10. Outwash plain (and ground moraine)
11. Erratic
12. Old lateral moraine
13. Moraine lake
14. Terminal moraine
15. Old terminal moraine
16. Medial moraine
17. Lateral moraine

Fig. 13–2. Aerial view of a glacier showing principal features

The crevasses form at a right angle to the direction of flow.

In a river, a steep drop brings a waterfall; the glacial counterpart is an icefall. Crevasses shoot out in all directions from the base of an icefall, and large ice towers (seracs) hang above. Gradually, gravity combined with the forward movement of the glacier will bring these seracs crashing down.

Below steep sections, the glacier slows again, and there may be no crevasses at this point. But if the decrease in slope is too sudden, the glacier may buckle, creating broken, uplifted waves (pressure ridges) as fast-moving ice rams slower ice.

The glacier moves faster in the center than along the sides, where friction along the walls of its route slows it down. This difference in speed often creates lateral (marginal) crevasses, which trend up-valley, near the sides of the glacier. Both lateral and crescentic crevasses tend to angle upstream toward the glacier center, a good clue in guessing the hidden extension of a crevasse from a single hole on the surface. (Any series of crevasses that are parallel to each other are known as *en echelon* crevasses.)

Unfortunately, minor irregularities underneath a glacier can produce random fractures with no pattern. For example, protuberances of rock under the ice, called nunataks, usually form a halo of crevasses. If the rock doesn't actually reach the surface so you can see it, you may be at a loss to explain the odd crevassing. Because of bottom irregularities like this, the only absolute rule about crevasses is that they can form just about anywhere, anytime.

Crevasses are most dangerous in the accumulation zone, that portion of a glacier high enough to receive more snow every year than it loses to melting. Here, crevasses are frequently covered with snow, either filling the hole or forming bridges over the void. Some of the bridges are too weak to support a climber. Others are strong enough for the moment, but will weaken as the bridge melts or the crevasse widens.

Below the accumulation zone is the area of the glacier called the ablation zone, where annual melting matches or exceeds the yearly snowfall. Between the two zones is the firn line (also known as the névé line), named for the words that designate old snow.

Often a giant crevasse known as a bergschrund forms at the glacier's upper limit, where it pulls away from a stationary ice cap. Sometimes a bergschrund presents the final problem in a climb, with the summit a short stroll beyond. Other times, a snowfield above a bergschrund is separated from a higher rock face by a moat, formed by melting and the downhill creep of the snow. A moat can be every bit as hard to cross as a bergschrund.

EQUIPMENT FOR GLACIER TRAVEL

Take a look at your gear with glaciers and crevasses in mind. Here are some considerations in getting ready for glacier travel.

THE ROPE

The rope you need depends on the glacier. If steep technical climbing is expected, with the possibility of severe leader falls, use a standard 10- to 11-millimeter climbing rope or two 9-millimeter ropes. But for "easy" glaciers, a single 9-millimeter rope will handle crevasse falls. For the snow, use one of the "dry" ropes treated by the manufacturer to reduce moisture absorption. This keeps the rope lighter, drier, stronger, and easier to handle. Some parties carry an additional 100-foot rope, 8 or 9 millimeters in diameter, as an emergency rescue line.

HARNESS

For glacier travel, tie your climbing rope into a seat harness combined with a separate chest harness, or into a full body harness. You don't want to simply tie into a rope around your waist because it would dangerously constrict breathing if you fell into a crevasse and dangled from the rope. The chest harness keeps you from being flipped backward by the weight of your pack during a fall. (Chapter 6 gives details on this equipment.)

ICE AXE AND CRAMPONS

An ice axe and crampons are as important for safe glacier travel as a rope and harness. Crampons help you keep your footing if the snow is icy or the glacier slope gets steep. The ice axe does its usual job of aiding with balance and providing a tool for self-belay and self-arrest. It's also what you use to stop a ropemate's tumble into a crevasse, by falling into self-arrest position with the axe.

In order to keep the axe with you in case *you're* the one who falls in, attach a leash of accessory cord or webbing through the hole in the head of the axe. You can attach the other end of the leash around your wrist with a snug loop or to your waist harness with a locking carabiner. A short wrist leash can be somewhat inconvenient because you need to shift it from one wrist to the other when you change hands on the axe, while a long leash attached to one wrist or to your harness lets you switch hands freely. With the leash clipped to your harness, the axe can provide a quick personal anchor. (Chapter 12 includes a more complete discussion of ice-axe leashes.)

PRUSIK SLINGS AND ASCENDERS

Among the most important gear to help a climber out of a crevasse are slings, tied with prusik knots or other friction knots, and mechanical ascenders.

A prusik sling can be as simple as a mere loop of 5- to 7-millimeter accessory cord. One of these slings tied to a climbing rope with a prusik knot will slide up or down the rope when loosened but grip the rope firmly when tightened. The Bachmann knot does the same thing, but is tied around both a carabiner and the climbing rope. The Klemheist knot works best if the sling is made of webbing instead of cord. (Check back to Chapter 6 for refreshers on any of these knots.)

The simplest prusik slings are used as the link between a snow anchor and the rope that holds a fallen climber. More complicated prusik slings, with foot and safety loops, will be described later in this chapter in the section on crevasse self-rescue.

Mechanical ascenders (such as Jumars and Clogs) attached to slings can be used to replace friction knots such as the prusik for self-rescue and for anchoring an accident rope. Ascenders attach to the rope more easily than the knots. They work better on icy ropes and they can be operated more readily with gloved hands.

On the debit side, ascenders are heavy and expensive. As mechanical devices, they are more prone to failure than knots are and have popped off the rope under unusual circumstances.

On an expedition that fixes some of its ropes in place, most climbers will carry one or two ascenders for self-belay on the fixed lines. These climbers usually use the ascenders for glacier travel as well.

Other rescue gear: At a *minimum,* every glacier climber should carry a single-length runner and a double-length runner of 1-inch tubular webbing to attach to buried anchors; enough carabiners for rappelling (or two carabiners plus a belay device); and one rescue pulley (a carabiner will work in a pinch, but it adds considerable friction). Each rope team should carry at least one snow picket or ice screw (depending on snow conditions) for setting up a solid anchor. Anchors that use two placements are preferred for security, so a rope team may want to pack more anchoring hardware along, or they may have to borrow some from another team in an emergency.

CLOTHING

Dress for the crevasse, not for the glacier. It's frigid in the crevasses even when it's sunny and windless topside, and you want to be ready in case of a fall.

Even on a hot day, wear long trousers and a long-sleeve shirt (they can be wool or synthetic). Try to wear garments that can be ventilated, such as pants with side zippers or a parka with underarm zippers. You can zip these closed if you end up in a crevasse.

As further insurance against hypothermia, keep a jacket on the outside of your pack, where you can reach it easily. Stash a cap and gloves in your pockets. And wear light-colored garments that reflect the heat of the sun while you are on the glacier but will still provide insulation inside a crevasse.

SKIS AND SNOWSHOES

Skis or snowshoes are usually essential for winter or arctic mountaineering because they keep you from sinking too deeply into the snow by distributing your weight over a larger area. This same feature makes them helpful on some glacier climbs by reducing your danger of breaking through the snow bridging a hidden crevasse.

WANDS

Bamboo wands are valuable aids in marking the location of crevasses, identifying turns, and showing the climbing route for the return. Even on climbs where you intend to descend a different route, consider marking the ascent with these flag-topped sticks in case you're forced to retreat. (Chapter 12 explains how to make your own wands.)

If the visibility is poor, the safest spacing for the wands is a distance equal to the total length of your party (when roped and moving in single file). On the way down, the party can ''feel'' its way if necessary. The last person in the line stops at each wand and doesn't continue until it is confirmed that the next wand has been found. If visibility is fairly good, space the wands farther apart.

A few other tips on wands: if you tilt each wand as you place it so that it points toward the one below, the search will be narrowed on the way down. Remember that you'll be looking from above for the wands on the return trip, so avoid placing them in hollows or on the down side of ridges where they'll be hard to see. Mark critical spots with some kind of code, such as two wands pointing in the new direction for a turn, or two wands crossing each other for a snow bridge or hidden crevasse.

FUNDAMENTALS OF GLACIER TRAVEL

On a cold, clear morning in late spring, 2 hours before dawn, the glacier is a place of peace and beauty. Above this great silent sweep of ice and snow, the mountain stands silhouetted against a star-filled sky. Climbers fiddling with their headlamps or adjusting their gaiters or squirming into their seat harnesses are too busy and too sleepy to think much about the adventure that lies ahead. But from training and experience, they know just what to do to get ready for a long day on a big glacier. It's one of those days when all the training and preparation for staying out of trouble around crevasses will pay off.

USING THE ROPE

The first rule of glacier travel is very simple: rope up. This holds whether or not you're familiar with the glacier and whether or not you can see any crevasses.

It's tempting to walk unroped onto a glacier that looks like a benign snowfield, especially if you've gone up similar routes time after time without mishap. Avoid the temptation. The extra time and trouble of dealing with the rope, like wearing a seat belt in a car, greatly increases your chances of surviving the most likely accident on a glacier, falling into a crevasse.

Rope teams

Rope teams of three climbers each are a good size for moderate glaciers because they provide two people, not just one, to arrest a ropemate's fall into a crevasse. Glacier rope teams usually keep 40 or 50 feet between climbers, putting three people on a 120-foot rope and three or four on a 150-foot or 165-foot rope. Putting the climbers much closer together increases the danger that more than one will be dragged into a crevasse before a fall can be arrested.

On severely crevassed or very steep glaciers where frequent belaying is required, rope teams of only two climbers (as in rock climbing) are the most practical.

A minimum of two rope teams is recommended for glacier travel so that a rope team involved in an accident will have backup help. While the team with the fallen climber concentrates on holding the rope fast, the second team can set up a snow anchor and then help with the rescue, including providing a second rope.

Tying in

Every climber ties into a seat harness. For glacier travel, each person also needs to wear a chest harness. (Review the details in Chapter 6 about making and tying in to chest harnesses). Here are some general glacier tie-in procedures, depending on the size of the rope team:

Three-person rope: This is the standard size for a rope team on a moderate glacier. The middle climber ties into the very center of the rope, most commonly with a double bowline through the tie-in loops of the seat harness. The small loop that remains at the end of the double bowline should be clipped with a locking carabiner to the harness to ensure the knot can't come loose. The two other climbers tie in at the very ends of the rope, usually with a rewoven figure-8.

Four-person rope: Divide the rope into thirds. Two climbers tie in at the ends, the other two tie in at the one-third points.

Two-person rope: Although a three-person rope is preferred for moderate glacier travel, ropes will sometimes have only two climbers. The most convenient procedure is to use only a part of the rope so you don't have to drag the whole thing through the snow. Each climber ties in anywhere from 25 to 50 feet from an end of the rope; then each carries a loose end on top of the pack or around the shoulders. This keeps the loose rope out of your way while you climb, but ready for use in a crevasse rescue.

Rope management

Keep the rope extended, without slack. This is the most important rule of rope management on a glacier. A rope that is fully extended between climbers is your insurance against taking a long plunge into a crevasse. A slack rope means you drop farther, increasing chances of hitting the sides or bottom or becoming wedged where the crevasse narrows. For the climbers on top, it can mean a much greater hit on the rope from the fallen climber and the danger of being pulled into the hole.

To help keep slack out of the rope, a rope leader needs to set a pace the others can follow for a long time. For their part, the second and third climbers must try to closely match the pace of the leader so the rope stays extended—but not taut. A taut rope is annoying because it pulls back on the climber ahead. You'll need to pay extra attention at turns, where the rope will start to go slack as the climber in front of you heads in a new direction, then tightens as you near the turn yourself. Throughout the turn, adjust speed as necessary, and avoid following the leader's footsteps; select an independent route that will keep the rope taut.

Don't forget safety when you reach a rest stop or campsite. The rope must stay extended and slack-free until the area has been thoroughly probed for crevasses. At a campsite, mark boundaries of the safe area with wands. Always belay climbers into and out of all rest and camp areas.

Another rope-management technique is to keep the rope running at right angles to crevasses. This makes it less likely that two climbers on the same rope will be walking dangerously near the edge of a particular crevasse at the same time. A rope team traveling in single file parallel to a crevasse runs the risk of one climber taking a long fall or of more than one climber tumbling in. Therefore, the second and third climbers on a rope should again avoid the footsteps of a leader who is walking parallel to a crevasse (perhaps looking for a snow bridge or for the end of the cavity). Instead, the followers should stay downhill of the leader and walk on their own separate courses, trying to keep the rope at a right angle to the crevasse.

The same technique is a good safety idea for traveling sideways across a glacier even if no crevasse is in sight. A sideways (traversing) route puts climbers parallel with the most likely direction of any hidden crevasse. Once again, the second and third climbers can blaze their own trail, staying downhill of the leader so the rope is at right angles to the most likely danger.

DETECTING CREVASSES

The first step in staying out of crevasses is to know where they are. Sometimes you can even get a head start before the trip by studying photos of the glacier, because crevasse patterns remain fairly constant from year to year.

On the approach hike, try for a good up-valley or cross-valley look at the glacier before reaching it. You may see an obvious route that would be impossible to discover once you're there. Consider making notes or sketches to help in remembering major crevasses, landmarks, and routes.

These distant views are useful, but prepare to be surprised. What appeared to be small cracks may be gaping chasms, and major crevasses may have been hidden from the angle of your view. Plan alternative routes if you can.

Once you're on the glacier, it's a continuous game of Find the Crevasse. Just because you can't see them doesn't mean they aren't there. Here are some important tips for detecting crevasses:

- Keep an eye out for sagging trenches in the snow that mark where gravity has pulled down on snow that covers a crevasse. The sags will be visible by their slight difference in sheen, texture, or color.
- Take advantage of the low-angle light of early morning and late afternoon to spot the characteristic shadows of sagging snow trenches. They may be impossible to detect in the flat light of a fog and difficult to see in the midafternoon sun.
- Be wary after storms in fall or late spring, when new snow can mask the thin sagging roof of a crevasse.
- Be especially alert in areas where you know crevasses form, such as around nunataks, at the sides of the glacier, and where slopes steepen.
- Check regularly to the sides of your route to determine whether open cracks to your left or right could possibly extend, beneath the snow, under your path.
- Remember that where there is one crevasse there are often many.

Snow probing is the technique to use if you have found a suspicious-looking area and want to search it for crevasses. If your probe locates a crevasse, continue probing to find its true lip.

Probe with your ice axe, thrusting the shaft into the snow a couple of feet ahead of the snow you are standing on. Keep the axe perpendicular to the slope and thrust it in with a smooth motion. You need an axe with a uniform taper from the spike to the shaft, because a blunt spike or jutting ferrule makes it hard to feel the snow.

If resistance to the thrust is uniform, you have established that the snow is consistent to at least the depth of your axe. If resistance lessens abruptly, you've probably found a hole. If your route must continue in the direction of this hole, use further axe thrusts to establish its extent. The leader should open up the hole and mark it with wands.

The value of probing depends on your skill and experience at interpreting the changes felt in the snow layers. An inexperienced prober may think the shaft broke through into a hole when all it really did was hit a softer layer of snow.

The length of the ice axe becomes a limiting factor in probing. The lead climber can also carry an avalanche probe ski pole, which is lighter, longer, and thinner than the axe for easier, deeper probes.

CROSSING CREVASSES

Climbers have a number of ways to get past a crevasse that lies across their route.

The end run

When a crevasse pinches to a close at one end, the safest and most dependable technique is the end run (fig. 13-3). A quarter-mile walk may gain you only 20 or 30 feet of forward progress, but it often beats a direct confrontation with the crevasse.

In late summer when the winter snow has melted down to the ice, you may be able to see the true end of the crevasse. But if fresh snow still blankets the glacier, the visible end of the crack is usually not its true end. Make a wide swing around the corner and probe carefully.

Snow bridges

If an end run is impractical, look for a bridge (fig. 13-4). Remnant snowcover sagging over the void forms one type of bridge. Other, sturdier bridges are really thin isthmuses between two crevasses, with foundations that extend deep into the body of the glacier.

Study a bridge carefully—try for a side view—before putting any faith in it. If you're in doubt, belay the leader in for probing and a close-up look. After the leader gets across, you can follow exactly in the original tracks, belayed from both sides of



Fig. 13–3. End run around a crevasse, keeping the rope taut by not following in the leader's footsteps



Fig. 13–4. Crossing a bridged crevasse under belay

the crevasse if you're the middle person on a three-person rope. Then belay the third climber across.

The strength of a snow bridge varies tremendously with temperature. An arch that might support a truck in the cold of winter or early morning may collapse under its own weight during an afternoon thaw. Cross every bridge with caution every time. Don't assume that because it held in the morning during the ascent that it's safe as you head down in the afternoon.

Jumping

Jumping is the final common tactic for crossing a crevasse (fig. 13-5). Most jumps across crevasses are short, simple leaps. If you're planning a desperate lunge, be sure you've ruled out all the alternatives and see that you are well belayed.

Before any significant jump, remove your pack. While belayed, probe to find the true edge of the crevasse. If you need a running start, tramp down the snow for better footing. As final preparation, put on parka, mittens, and hat, check prusiks and harness, and spool out the amount of rope slack needed from the belayer. Then jump—with your ice axe in the self-arrest position, ready to help you claw over the edge if you're shy of a clean landing.

With the rope now linked to the landing side, the other climbers have a less dangerous job ahead. The belay rope can help pull up on any jumper who falls just short of the target.

Use caution and common sense if the leap is from the high lip of a crevasse over to a lower side. (Bergschrunds, for example, often have a high overhanging wall on the uphill side.) You can be injured in a long, hard leap. If you go for it, keep your feet slightly apart for balance, knees bent to absorb shock, and ice axe held ready for a quick self-arrest.



Fig. 13–5. Jumping a crevasse (belay not shown)

CREVASSE RESCUE

The depths of a great crevasse exhibit an awful beauty, both enticing and repellent. On a fine day, the walls are a sheen of soft blue ice in the filtered light from high above, and the cavern is cool and still as a church, or a tomb. It's a place every climber should visit once in a lifetime—for crevasse rescue practice. But if there's a second time, we hope it will be in the company of climbers who know the rescue techniques spelled out in the rest of this chapter.

RESCUE RESPONSE

You're the middle person on a three-person rope team traveling up a moderately angled glacier. The climber walking 50 feet in front of you suddenly disappears beneath the snow. What do you do?

Do not stop and think. Your immediate reflex must be to drop into self-arrest in the snow (facing away from the direction of pull) and hold the fall.

The climber at the end of the rope will be doing the same thing. (Chapter 12 details all the steps in self-arrest with the ice axe.)

After that, you and your ropemate topside, along with any other climbers in the neighborhood, get started on the rescue operation, working together with your fallen friend. The principal steps you will take (fig. 13-6), starting right from the instant of the fall, are:

1. Arrest the fall.
2. Set up an anchor.
3. Attach the rope to the anchor.
4. Check the fallen climber.
5. Devise a rescue plan.

Set up an anchor

Once the fall is stopped (fig. 13-6a), the middle climber on the three-person rope stays in self-arrest to support the weight of the fallen climber. The end climber slowly gets out of self-arrest, making sure the middle climber can hold the weight alone, then sets to work establishing an anchor (fig. 13-6b). However, if another rope team is on hand, both climbers can stay in self-arrest while the other team sets up the anchor.

The anchor goes between the middle climber and the lip of the crevasse. (If it's placed instead on the other side of the climber, eventual tension on the rope could make it impossible for that person to untie.) It takes a bombproof anchor because at least one life will be riding on it. Whoever establishes the anchor must work quickly, but without taking shortcuts.

Solid anchors can be made from the following types of protection: pickets pounded into firm snow; ice screws placed in ice; or snow flukes, ice axes, or skis buried as deadmen in soft snow. Ideally, put in two independent anchor placements (or more), with slings to equalize the load. A solitary ice axe driven vertically into the snow is not a good candidate as an anchor to carry the loads of a rescue.

Attach the rope to the anchor

The climber who set up the anchor now attaches a short sling to the climbing rope with a prusik knot, Bachmann knot, or mechanical ascender, and clips the sling to the anchor (fig. 13-6b). The knot or ascender is then slid down the rope, toward the crevasse, until the sling is tight. Now anyone who is still in self-arrest can ease the load off the ice axe and onto the anchor. Do it slowly to confirm that the anchor is solid and that the ascender or friction knot is gripping the climbing rope tightly. (Keep in mind that if you choose to use a prusik knot, one rescuer will have to tend the knot later to keep it open any time the fallen climber is being pulled up. The Bachmann knot and ascenders, on the other hand, usually require less tending.)

Check the fallen climber

Belay one rescuer to the edge of the crevasse to check out the climber's situation closely (fig. 13-6c). The rescuer can be belayed from the anchor by a teammate. Or the rescuer can operate with a self-belay—attaching a prusik loop to the rope that runs from the anchor to the fallen climber, then sliding this prusik along the rope as the rescuer moves toward the crevasse edge. On the way, the rescuer can probe the area and check for any other hazards that might endanger the rescue.

The rescuer will try to talk with the fallen climber. If there is no response, one person can rappel or be lowered on belay into the crevasse to help the fallen climber. But if there is a response, the rescuer can ask if the climber needs clothing, is injured, is able to get into prusik slings, and so forth. The person who fell in should be able to say whether self-rescue is a good possibility—by ice-climbing out or prusiking out—or whether a hoist from above will be needed.

Devise a rescue plan

With all the groundwork out of the way, it's time to get the climber out of the crevasse. There are a lot of methods to choose from, as you will see later in this chapter. Just use the one that looks the best for this particular case, depending on the condition of the climber, the number of rescuers, the equipment available, and any other variables.



Fig. 13–6. Rescue response: a, arresting the fall; b, setting up the anchor and attaching the rope to the anchor; c, checking on the fallen climber (anchor of the climber giving a boot-axe belay not shown for clarity).

Look for the best method that combines simplicity, speed, and safety.

First of all, a climber who falls into a crevasse doesn't necessarily have to come back up at the same spot. Sometimes there's another way out. Check the possibility of lowering or swinging the fallen climber to a ledge. It might be a good spot to rest and perhaps a gateway to a different part of the crevasse where rescue will be easier. Consider whether the bottom of the crevasse looks solid. This could offer another resting spot and a possible path to a climbing route or a snow ramp to the surface.

Whatever the rescue method, be sure the rope is padded to keep it from digging into the lip of the crevasse. A buried rope will sabotage either the rescuers' efforts to hoist the climber up over the lip or the climber's own attempts to prusik out. For padding, slide an ice-axe shaft, a ski, an ensolite pad, or even a pack under the rescue rope at the edge of the crevasse. (Anchor the padding so it can't fall into the crevasse.)

Throughout the rescue, everyone on top must be tied to the anchor or clipped into a prusik sling tied to an anchored rope or on belay at all times. If your party is large enough, assign one climber to brace and guard the anchor. Establish additional anchors if necessary.

Always remember who you're trying to help. Avoid knocking snow or ice down on the person in the crevasse. Keep talking to the fallen climber. Give reassurance and information about what's going on and enlist ideas for making the rescue go more smoothly.

INSIDE THE CREVASSE

While rescuers are busy topside, the person down below has work to do. Here's how you can prepare for rescue if you are the fallen climber:

Set up your prusik slings on the climbing rope so you can alternate between standing and sitting as you dangle. You will be a lot more comfortable, and will be ready to climb up the rope using the slings if that seems the best way out. (The next section in this chapter outlines self-rescue using prusik slings.)

Clip the climbing rope through a carabiner at your chest harness, if you didn't do so earlier. It will help you maintain an upright position.

Get your pack and ice axe out of the way. You may be able to send them up on a rope from the rescuers. You can also clip the axe to your seat harness, letting it hang so it doesn't interfere with your movement. For the pack, you have the option of attaching a sling to its haul loop and clipping the sling onto the climbing rope with a carabiner, just above your seat harness (but below the prusik attachments). Then the pack will just hang below you. Later, if you climb up the rope using a friction knot or ascenders, the hanging pack will slide freely along the bottom of the loop of climbing rope and weight the rope, making it easier to climb.

Keep warm. Close your parka, put on the hat and gloves you had stuffed in your pockets, and try to put on additional layers of clothing.

SELF-RESCUE

Self-rescue is often the easiest and fastest form of crevasse rescue. This is especially true for small parties that lack the muscle power to hoist you out or that may be pinned down holding the rope. It may be the only practical rescue method for a two-person party. Self-rescue has the added advantage of keeping the fallen climber active and warm.

In some cases, you may be able to climb the crevasse wall to safety, while on belay. Or you can climb back up the rope that held your fall. Two good self-rescue methods of ascending the rope are the stair-step prusik and the Texas prusik. They both use slings of accessory cord attached to the climbing rope with a prusik knot. However, they also work well if they are attached with the Bachmann knot, which incorporates a carabiner that makes a good handhold for loosening and sliding the slings. Mechanical ascenders also can be used instead of the friction knots.

If you ever use slings made of tubular webbing rather than accessory cord, the Klemheist knot is a better friction knot to use than the prusik or Bachmann.

Don't start up the rope until you get an OK from topside. Your movement could interfere with the work of rescuers who may be struggling to hold the fall and set up an anchor.

The stair-step prusik

This system of climbing the rope uses a separate sling for each leg. You can make a set of slings for yourself, and 25 feet (about 8 meters) of 6-millimeter accessory cord is plenty of material for both of them. Getting the size right requires some experimentation. When all the work is done, you should end up with two slings—one as long as the distance from your foot to your ears, the shorter one as long as from foot to elbow.

Each sling consists basically of a single strand of cord, tied with equal-sized loops (1 foot long or so) at each end. One will be the prusik loop, used in attaching the sling to the climbing rope with a prusik or Bachmann knot. The other is a foot loop, large enough to fit over any footwear, including crampons and overboots. Add a slip knot to this loop to prevent tightening down on the boot and cutting off circulation (fig. 13-7a-c).

You need to incorporate one little difference in the longer sling. Leave a 5-foot tail after you tie the loop that will be used for creating the prusik. Tie a small overhand loop at the end of this tail. When you use the slings, clip this small loop to your seat harness as a safety strap to catch you in case both feet slip out of the slings.

Before you head out onto a glacier, attach the prusik loops to the climbing rope so the slings are ready for immediate use in an emergency (fig. 13-7d,e). Attach them at a point beyond where the climbing rope leaves the carabiner at your chest harness, the longer sling attached beyond the shorter. (Pass the long sling through the chest carabiner as well.) Shove the other end of the long sling under the belt of your seat harness. Put the


Stopper knot can be moved up or down on the foot loop to change the size of the loop as needed to fit boots with crampons
a
b

Fig. 13–7. The stair-step prusik: a, tying the foot loop with one half of a double fisherman's knot; b, climber prepared to walk out onto a glacier with prusik slings attached to climbing rope

ends of both slings into your pockets, ready to be pulled out and slipped onto your feet when needed.

(If you are using mechanical ascenders instead of prusik loops to hold the sling to the rope, carry the ascenders on your seat harness and the slings in your pockets. After a crevasse fall, attach the ascenders to the rope.)

This is the sequence to follow if you need to climb the rope (fig. 13-8):

1. Take the foot loops from your pockets and slip them over your boots, cinching up on the slip knots.
2. Stand up in the short prusik sling, putting all your weight onto it.
3. Lift the leg attached to the long prusik sling, then loosen the knot attached to that sling and slide it up the rope some 18 inches.
4. Stand up in the long sling, shifting all your weight to it.
5. Lift the leg attached to the short sling, then loosen the knot attached to that sling and slide it about 18 inches up the rope.
6. Stand up again in the short sling.
7. Keep repeating the process and you'll walk up the rope, somewhat as if it were a flight of stairs.



Fig. 13–8. Ascending a rope using the stair-step prusik

The Texas prusik

This alternative method of ascending the rope also uses two slings, but this time only one goes to the feet while the other attaches directly to the seat harness (fig. 13-9). The foot sling has a separate loop for each foot (though an option is to provide just a single loop used by only one foot.)

As with the stair-step method, attach the slings to the climbing rope before you start walking on the glacier. The seat sling should extend to head level when you slide the prusik knot upward. The prusik for the foot loops should be tied below the seat prusik, with the knot at waist level when you are standing on the sling. (Attach a safety loop from the top of the leg sling to the locking carabiner at your seat harness.) Experiment to find the sling lengths that are best for you.



Fig. 13–9. Texas prusik dimensions

This is how to use the Texas prusik after a fall into a crevasse (fig. 13-10):

1. Remove the foot loops from your pocket and slip one over each boot, cinching up on the slip knots. (If you have a sling with just a single foot loop, slip it over one boot.)
2. Stand up in the foot slings.
3. Loosen the prusik knot attached to the seat sling and slide it up the rope until it is taut.
4. Sit down in the waist harness, putting all your weight on the seat sling.
5. Loosen the prusik knot attached to the foot slings and slide it up the rope (18 to 24 inches, if the sling is adjusted properly).
6. Once again, stand up in the foot slings.
7. Keep repeating the process.



Fig. 13–10. Ascending a rope using the Texas prusik: a, leg-raise position; b, stand-up position; c, rest position.

The Texas prusik is a simple system that permits more progress per cycle and more comfortable rests than with the stair-step prusik. A climber with an injured leg can still ascend the rope because only one leg is required if you choose to make use of only one foot loop. This method is harder to perform than the stair-step in very narrow crevasses.

With either the stair-step or the Texas prusik, some climbers attach etriers rather than conventional slings. The steps in these ladder-like slings can help you climb up and over a crevasse lip if the rope is entrenched in the snow.

TEAM RESCUES

All rescues are team rescues to some degree, because the fallen climber needs some help even for a self-rescue. However, a full team rescue usually involves hauling the climber to safety. Following are the principal team-rescue methods.

Brute force

Here's a technique we can all understand. Just grab the rope and pull. This is an excellent method for large groups because it's fast, uncomplicated, uses minimal equipment, and requires little or no help from the fallen climber. It works best when perhaps half a dozen strong rescuers can haul on the rope and when the working platform for the pullers is flat or downhill.

After the rescuers have established an anchor, checked the fallen climber, and padded the rope at the lip of the crevasse, they line up along the accident rope and grasp it. They haul by pulling on the rope hand over hand or by moving step by step away from the crevasse.

One rescuer tends the anchor and its tie-in point to the accident rope (where it is attached with a prusik knot, Bachmann knot, or a mechanical ascender). As the rope is pulled up, this rescuer sees that it moves smoothly through the tie-in point. The knot or ascender is then in position to grip and hold the rope if the rope is dropped or the pullers need a rest.

Rescuers should pull the rope at a slow, steady pace, especially when the fallen climber reaches the crevasse lip. If the rope has cut into the lip, the climber could be hurt by being pulled into the wall. At this point, rescuers may ask the climber to scramble over the lip while they hoist.

The single pulley (C-pulley)

Smaller groups without enough muscle to pull the climber out by brute force need a more sophisticated system. The single pulley gives rescuers a 2-to-1 mechanical advantage, doubling the amount of weight that each puller can raise (although friction somewhat lowers this ratio).

Several considerations enter into a decision to use the single-pulley (also known as the C-pulley). The fallen climber must be conscious in order to help by clipping into the rescue pulley. A separate length of rope is needed, either an unused end of the accident rope or another rope entirely. This method is, in fact, a good alternative to consider if the accident rope itself is embedded in the edge of the crevasse and won't move.

To carry out a single-pulley rescue (fig. 13-11), follow these steps:

1. Find a rescue rope. It must be at least twice as long as the distance from the anchor to the fallen climber.
2. Attach one end of the rescue rope to the existing anchor or to a new rescue anchor. (If the unused end of the accident rope is long enough to be used, tie a figure-8 loop in it a few feet beyond the rope's attachment to the anchor. Clip this loop into the anchor.)
3. Double the rescue rope into a big loop and attach a pulley with a locking carabiner.
4. Lower the loop with the pulley and carabiner down to the fallen climber. Tell the climber to clip the carabiner into the seat harness. Confirm that this has been done. Then tell the climber to take the strand of rescue rope that you will be pulling on and to run it through the carabiner at the chest harness, to help stay upright. Tell the climber *precisely* what to do.
5. Be sure the rescue rope runs over an ice axe or



Fig. 13–11. Setting up and raising a climber with the single pulley (rescuer's personal anchors omitted for clarity)

other padding at the crevasse edge to keep it from digging in.

6. Haul on the unanchored end of the lowered loop. As you haul, the climber can grab the anchored half of the loop and pull up. This relieves weight on the rope and makes hauling much easier.
7. A rescuer must attend to the original accident rope at the anchor and pull slack through the friction knot or ascender as the climber is raised. This keeps the accident rope ready at any time to accept the climber's weight again, in case of emergency or if the pullers need a rest.

The Z-pulley

The Z-pulley (fig. 13-12) magnifies the muscle power of small climbing parties by offering a 3-to-1 theoretical mechanical advantage through the use of two pulleys. It can be set up and operated with no help from the fallen climber, making it valuable in rescuing an unconscious person.



Fig. 13–12. Raising a climber with the Z-pulley

The Z-pulley system, which uses the accident rope, requires more equipment and is somewhat more complicated than the C-pulley.

You can get to work on the Z-pulley as soon as you have set up the anchor that is established after any crevasse fall. As usual, the accident rope will be secured to this anchor via a sling tied to the rope with a friction knot (prusik or Bachmann) or an ascender.

Take the loose end of the accident rope and lay out a long loop on the snow, in front of the anchor, so that the loop and the taut line leading to the fallen climber form a giant flat Z.

At the first bend in the Z (by the anchor), place a rescue pulley. Clip a locking carabiner through the pulley and attach the carabiner to the anchor with a short sling. (Some climbers prefer to establish a second anchor to secure this pulley.) The pulley will be located on the climbing rope, between the friction knot and the anchor.

At the second bend in the Z (closer to the crevasse lip), place a second pulley on the rope. Clip this "floating" pulley into a short sling that also is attached with a friction knot to the taut rope going to the fallen climber. You may have to see it to believe it, but you now have a Z-pulley setup, ready for use.

To work the system:

1. Pull hand over hand on the free end of the rope, hauling the climber upward.
2. Be sure the rope slides freely through the friction knot or ascender that is linked to the climbing rope near the anchor. This will be the friction brake that holds the accident rope whenever you reset the pulley. If it's a prusik knot, one rescuer needs to help keep it in the open, sliding position. If it's a Bachmann knot or mechanical ascender, it should be able to tend itself.
3. As the floating pulley is hauled in close to the other pulley, slowly relax your pull on the rope in order to let the friction brake take the weight of the climber. Don't let the two pulleys touch because that will undo the Z configuration and convert your system to a direct pull—the old brute-force method.
4. Reset the Z-pulley by loosening the friction knot that is attached to the floating pulley and sliding it way out toward the crevasse lip once again.
5. Haul again on the free end of the rope.
6. Keep repeating the process.

Remember that in any rescue system calling for pulleys, you can substitute carabiners if necessary. However, they create far more friction and the rope will be much harder to pull.

Piggyback systems

To get even more mechanical advantage out of a rescue hauling setup, you can piggyback two systems. For example, establish a separate single-pulley setup to haul on the rope coming from a Z-pulley system. This now gives you a 6-to-1 theoretical mechanical advantage. Or set up a single pulley to haul on another single-pulley system for a 4-to-1 advantage.

To piggyback two systems, set up your initial hoist to the fallen climber, either a single pulley or a Z-pulley. Now establish a second anchor some distance behind the main one, to anchor the second system. Attach the second hoist, again either a single pulley or a Z-pulley, to the accident rope at the point where the rescuers would normally pull.

As you might guess, piggyback systems require an ample supply of slings, pulleys, carabiners, anchor material, and rope.

The Bilgeri rescue

The Bilgeri (fig. 13-13) is a sort of "team self-rescue." It involves the rope-climbing techniques used in the stair-step prusik and the Texas prusik—except that the friction knots or ascenders are operated by a rescuer topside, not by the fallen climber.

Here's how to do it:

1. Secure the accident rope to an anchor with a friction knot or ascender—the standard procedure after any crevasse fall.



Climber is facing outward to show rope detail. In actual rescue situations the climber would be faced inward *toward* the crevasse wall.

Fig. 13–13. Climber ascending using the Bilgeri

2. Tie a foot loop in the end of a length of rope (either a spare rope or the loose end of the accident rope).
3. Lower this loop to the climber.
4. Attach the upper end of this rope to the anchor with a friction knot or ascender.
5. Tell the climber to put one foot in the foot loop you lowered and the other foot in a prusik sling attached to the accident rope. The climber should now be standing in two foot loops—each on a separate strand of rope that is secured topside by separate friction-knot slings clipped to the anchor.

   (To complete the picture, the fallen climber should take all the precautions associated with self-rescue: thread the foot loops through the seat harness and then down to the feet; run the ascent ropes through the chest carabiner to help maintain an upright position; clip a safety loop from the prusik sling to the seat harness.)

   Everything is now ready for the ascent:
6. Shout "Right," and the climber lifts (unweights) the right foot. You pull in 12 to 18 inches of slack through the friction knot anchoring that rope.
7. Next, shout "Left." The climber lifts (unweights) the left foot while transferring all weight to the opposite rope. You pull in 12 to 18 inches of slack through the friction knot anchoring that rope.
8. Repeat the sequence until the climber is up and out.

This version of the Bilgeri is similar to the stair-step prusik. There's also a "Texas prusik" variation, useful for a person with an injured leg. The climber puts a boot into the foot loop that is lowered from above. The other foot is left free. To ascend, the climber alternates standing in the foot loop on one rope with sitting in the seat harness attached to the accident rope.

The Bilgeri can be a good idea if the fallen climber is in pretty good shape and can communicate readily with rescuers, but isn't particularly adept at working prusik slings. The Bilgeri rescue has an advantage over prusiking methods when the crevasse lip is reached. Because the knots are being handled up top, the fallen climber does not have to force prusik knots up a rope burrowed in the snow. If either of the Bilgeri ropes digs into the crevasse lip, you can free it from up top while the climber's weight is on the opposite line.

SPECIAL SITUATIONS

The realities of a rescue are bound to bring a few snags and surprises on the way to a successful conclusion. You may need to improvise on the basic techniques of rescue. The following are some special situations you could encounter and ideas on how to deal with them.

The middle person

It's an awkward situation when the middle person on a three-person rope team falls in a crevasse, and there are no other teams around to help. The fallen climber is temporarily left hanging while the only two people who can help are separated by the crevasse, each in self-arrest.

To get out of this fix, the climbers start by deciding which side of the crevasse is the rescue side; that is, which side should the fallen climber come out on? Usually, one of the two rescuers in self-arrest is holding more weight than the other. The one holding the least weight usually has the best chance to get up and establish an anchor while the rescuer on the other side stays in self-arrest to hold the fall.

With the anchor set up, the rescuer in self-arrest is ready to get free. This rescuer can ease back until the fallen climber's weight is on the anchor (keeping alert to the danger of also being pulled into the crevasse). Or this rescuer can try to set up a temporary anchor that will take the weight being held by the self-arrest.

Next step: the climber at the anchor tries to belay the climber on the wrong side over to the rescue side, if that person is needed to help in the operation. The loose end of the rope on the rescue side can be used for belaying, if it happens to be long enough. Or if they thought to bring along a lightweight 100-foot accessory line (a good precaution for a rope team traveling alone), this can provide the belay.

However, the climber on the wrong side could be stuck there if no belay or safe route is available. This climber should then set up an anchor and stay put.

On the rescue side, the ideal option now is for the fallen climber to ascend the rope on prusik slings. The rescuer can also use the Bilgeri technique, providing there's enough rope. If a hoist is necessary, the single rescuer can try a Z-pulley or a piggyback system. (For the friction brake at the anchor, be sure to use a Bachmann knot or an ascender, which require less tending than a prusik knot.)

In case one of the two middle members of a four-person rope team falls into a crevasse, conduct the rescue from the side that has two climbers topside.

Two-person rope team

Glacier climbers on a two-person rope team traveling alone really need to know their stuff when it comes to crevasse rescue. Each climber must carry enough equipment for an anchor and a hauling system. The topside climber not only stops the fall but must set up the anchor while staying in self-arrest.

As the sole rescuer, first secure your arrest position by digging in your feet and pressing the ice axe firmly into the snow.

Try to free one hand by rotating the upper half of your body—but keep leaning on the axe. Use your free hand to place a fluke, picket, or ice screw. At this point, you'll see the value of keeping the anchors easily accessible.

Then attach the rope to the anchor with a prusik sling. Ease the weight onto the anchor, keeping ready to resume self-arrest if the anchor doesn't hold. Once you're safely out of self-arrest, back up the anchor.

Now the fallen climber can ascend on prusik slings. Another option for the fallen climber is to work with the rescuer on a Bilgeri ascent—provided the rescuer is carrying enough spare rope (either extra line, or the coiled and unused rope end carried by climbers in a two-person team). If neither of these methods works in this particular situation, the rescuer will set up a hoist, either a Z-pulley or a piggyback system, using the extra rope resulting from tying in 25 to 50 feet from the rope end. The climbing rope must have a self-tending attachment to the anchor (either a Bachmann knot or an ascender). The rescuer can lighten the hoisting job by first pulling up the fallen climber's pack.

If the rescuer isn't able to set up an anchor in the first place, the fallen climber has no choice but to ascend on prusik slings while the rescuer remains in self-arrest.

Special rescues

New considerations come into the picture when you have to deal with an unconscious victim or with more than one fallen climber at a time.

To help an unconscious climber, first send someone down by rappelling or being lowered on belay. The helper can administer first aid and also get a fallen climber right-side up if necessary. The unconscious climber can be pulled up by brute force or with the Z-pulley. To help get the unconscious climber over the lip of the crevasse, a rescuer may have to work right at the edge or from inside the crevasse.

To rescue more than one fallen climber, assess each person's condition and the best method for getting each one out, and then decide the order of rescue. Be sure each fallen climber is given warm clothing, if needed, and keep them informed of rescue plans as they develop.

Working space

Rescue procedures can be modified to help give you the working space needed to carry out a successful operation.

Temporary anchor

This is a solution to a situation where there is very little working space between the edge of the crevasse and the person who is in self-arrest position to hold the fall. Normally, the anchor and then the Z-pulley would be set up in this space. But now there's not enough room.

The answer is simply to set up the main anchor *behind* the climber in self-arrest (instead of between the climber and the crevasse). Attach the climbing rope to the main anchor with a friction knot or ascender—but at this point, leave a couple of feet of slack between the main anchor and the climber in self-arrest, so that this climber isn't trapped in the system by tension on the rope.

This is where a temporary anchor comes in. Between the climber and the crevasse, set up a temporary anchor and use a prusik sling to secure the rope to it. This permits the climber to ease off from the self-arrest position, let the temporary anchor take over the weight, and untie from the climbing rope.

Now the rescuers can set up a normal Z-pulley in front of the main anchor. They now have plenty of working space. Once hauling begins, the prusik attached to the temporary anchor can be untied.

Difficult areas

Rescuers trying to work in a very narrow area between two crevasses can consider moving the operation. The rescue might proceed better if it is run from the opposite side of either crevasse.

Another option in a tight spot is to change the direction of pull on a Z-pulley system. Hook another pulley to the anchor and run the hauling end of the rope through it. Now the rescuers can pull in a direction more parallel to the crevasses.

Rescues from the uphill side of a crevasse are harder than those from the downhill side. If possible, move the operation to the lower side, where it will be easier for rescuers to haul and for the fallen climber to get over the lip of the crevasse.

Entrenched ropes

The upward progress of a person climbing out or being pulled out of a crevasse can be stopped cold by a rope that has dug itself into the lip.

The situation calls for some improvisation. For instance, a rescuer can attach prusik slings or etriers above the entrenched portion of the rope and drop them down for the climber to step into.

Another option is to switch to a new rescue rope. A rescuer can lower a new rope to the climber. Or the fallen climber can, in effect, provide a new rope by tossing the loose end of the climbing rope up to the rescuers. This is done by prusiking up to the lip, untying from the end of the climbing rope (after first tying in higher up), and throwing the loose end up to the rescuers.

A new rescue rope, carefully padded at the lip of the crevasse so it doesn't also get entrenched, opens up several rescue possibilities. The climber can switch prusik slings from the original climbing rope to the new free rope. Or the rescuers can haul the climber up and out on the new rope. Or the climber can merely transfer all weight to the new rope to give rescuers a much better chance of freeing the entrenched line.

Roofed crevasses

Wide roofed crevasses present special problems. The fallen climber may be hanging free, without a stabilizing wall for support, and the accident rope typically entrenches itself deeply into the snow of the crevasse roof. The climber may be bombarded by snow and ice dislodged by the rescuers above, who will be working in an area of proven instability.

Sometimes it's necessary for a well-belayed rescuer to take a shovel or axe and enlarge the hole the climber fell through. Do your best to keep snow and ice from hitting the climber.

Knowledge and preparation will minimize the hazards of roofed crevasses and the other problems of traveling near crevasses. Glacier travelers who learn about crevasses and regard them with a healthy respect may never fall in. If they do, they will know the techniques that give them the best chance to get back out.

• 14 •

ICE CLIMBING

The world of the ice climber embraces all the forms in which ice exists. In the high mountains, snow and other frozen precipitation endures pressure and heat over time to become the *alpine* ice of glaciers, icefields, and couloirs. This alpine ice is sometimes seen as *blue ice*, a hue born of its exposure to very low temperatures during formation. Blue ice is good for climbing and placing protection. *Black ice* is another alpine variation—old, hard ice, mixed with dirt, pebbles or other debris, often found in gullies and couloirs, and very difficult to climb.

When water freezes, the result is *water ice*. It can be as dramatic as a frozen waterfall or as common as *verglas*, the thin, clear coating that forms when rainfall or melting snow from upper cliffs freezes on rock. Verglas is difficult to climb because crampons have little to penetrate. Water ice is usually harder, steeper, and more brittle than alpine ice, but at high altitudes and low temperatures, the two may be indistinguishable.

Rock also comes in various forms, but is very stable when compared with ice. Yesterday's crack and slab problem will likely be there next year, but this morning's ice route may be only wet rock by afternoon. The ice climber learns to anticipate the ever-changing character of the climbing medium.

Ice-climbing techniques vary depending on steepness of the slope. You can walk without crampons on flat ice fairly easily, especially if rocks are embedded in the surface. On short slopes, you can use an ice axe to chop steps, but longer sections call for crampons. French technique—''flat-footing''—works well on steepening ice, up to a limit. But the steepest routes require the German technique of front-pointing.

This chapter will use some descriptive terms in referring to the approximate steepness of ice slopes. Here's roughly what they mean, in degrees of angle:

- Gentle: Up to 30 degrees
- Moderate: 30 to 45 degrees
- Steep: 45 to 60 degrees
- Extremely steep: 60 degrees and over
- Vertical: 80 to 90 degrees
- Overhanging: Over 90 degrees

EQUIPMENT

Ice climbers refine and expand their techniques and use them on greater climbing challenges with the help of modern equipment. Manufacturers offer a steady stream of specialized clothing, boots, crampons, ice tools, and ice anchors. Review Chapter 12 for a good general rundown on gear such as crampons and ice axes. Building on Chapter 12, this chapter will outline equipment features that are especially important for ice climbing.

CLOTHING

Clothes for ice climbing should offer a combination of comfort and function. In choosing a jacket or anorak, check to see that you can reach high and not have the anorak or jacket bottom rise above your waist. You don't want your waist exposed to the elements as you're reaching up to make a high ice placement. Reinforce the knees and ankles of rain pants or bibs.

Some climbers wear bibs or a body suit as an alternative to the conventional outfit of jacket (or anorak) and pants. A one-piece body suit of synthetic material retains warmth and rebuffs debris. For ventilation, it needs zippers that open from elbow to ankle, and another that opens the suit from stomach to back via the crotch. The body suit should not be confused with the expedition suit, essentially an insulated body suit.

For the hands, mittens with rubberized palms can help in gripping the bare-metal shaft of an ice tool—a tough job with a snow-coated nylon mitten. One option for covering your hands is high-density wool mittens (such as Dachsteins), which are not only warm but offer an unusual secondary feature. If you hit a difficult section of climbing and have only one ice tool, you can temporarily freeze a mittened hand to the ice for help through a move. For safekeeping, always attach wrist loops to your mittens and gloves.

BOOTS

Ice climbers use plastic (synthetic) boots more commonly than leather footwear. The plastic boots are warmer than leather and provide a rigid platform for crampons, which is especially important for front-pointing. Many plastic boots have indented toes and heels that help keep step-in/clamp-on crampon bindings securely attached.

Three-quarter-shank leather boots usually are adequate for general alpine ice climbing. However, leather boots used for extensive front-pointing should have a full shank.

Because ankle rotation is so important in French technique (flat-footing), you need a boot that permits good rotation. Leather boots often are better in this regard. And like any boots, you want ice-climbing footwear to fit well: snug in the heel and instep, and with room for toes to wiggle.

Make sure your gaiters fit your boots. You'll need full-length gaiters that extend from your foot to just beneath the knee. Insulated gaiters are available for added warmth.

CRAMPONS

Properly fitted hinged crampons are adequate for most alpine ice climbing. They work well with most types of climbing boots and are less expensive than rigid-frame designs. They should have medium-length points and require front points for ice climbing.

Climbers who do a lot of front-pointing (especially waterfall climbing) prefer rigid-frame crampons, which vibrate less than hinged crampons when kicked into water ice. Most rigid crampons should be worn with full-shank or plastic (synthetic) boots to prevent over-stressing the frame, although some newer models are strong enough to be worn with boots having less than full shanks. (For a fuller discussion of crampons, see Chapter 12.)

Crampon points must be sharp, and the harder the ice, the sharper the points need to be. Check the points before each climb and sharpen them if they need it.

The angle of the front points and of the first row of downward points is critical in determining the best penetration. For regular ice, the front points are shaped straight but bent slightly downward, and the first row is angled slightly forward (fig. 14-1a).

For waterfall ice, the front points are curved downward, and the ends of the first row are angled more forward than those used for regular ice (fig. 14-1b).

Some waterfall climbers prefer crampons with



Fig. 14–1. Angle of front points: a, for regular ice; b, for waterfall ice.

just a single front point, which makes for easy placement (fig. 14-2). However, the single front point has more tendency to rotate than the normal double front points.

ICE TOOLS

Part of the fun of ice climbing is experimenting with the large variety of ice-climbing hand tools and learning how to use them. You can borrow, rent, or buy ice tools in order to discover which ones work best in your own climbing.

Most ice tools have shorter shafts than the standard axes used in snow climbing. The short shaft, commonly 50 to 60 centimeters, helps in accurate placement of the pick and reduces the shaft vibration that can fatigue arm muscles. Ice tools that feature a hammer in place of the adze (fig. 14-3) often have a shaft length even shorter than other tools (as short as 35 centimeters).

Many alpine ice climbers use a full-length ice axe partnered with a shorter hand tool. On more technical ice routes, many climbers choose to use two shorter hand tools. A versatile combination is to use one tool that has an adze and one that has a



Fig. 14–2. Rigid crampon with interchangeable single front point



Fig. 14–3. Typical ice hammers

hammer. The adze chops and scrapes ice for steps, belay positions, or ice bollards; the hammer pounds in pieces of protection. Some climbers prefer to hold the ice hammer in their dominant hand, which makes it easier to use in starting ice screws or placing ice and rock pitons.

For a long and demanding ascent, some climbers bring along a third tool. It can be used as an anchor at belay points, as a protection placement, or to replace a lost or broken tool. If your hand tools feature replaceable picks, you can carry a lightweight spare as insurance against a broken pick.

To help in gripping the ice tools, you can wear gloves with rubberized palms or use tools with a covering on the shaft that improves the grip. Inspect your tools before each outing to see that adzes, picks, and spikes are as sharp as possible. Keep these sharp edges covered with guards when they're not in use.

There is great variety in the styles of ice tools. Following are the principal design variations, categorized by the parts of the tool: pick, adze, shaft, and spike.

Picks

The job of the pick is to penetrate the ice, hold against a pull along the shaft, and release easily when its grip is no longer needed. The holding and releasing characteristics of a pick are determined by its weight and shape and by its teeth.

A tool with a relatively heavy head cuts and penetrates most readily, but may be difficult to extract because of its greater penetration. Removable weights can be added to the head to help balance your swing and give better ice penetration.

The steeper the droop of a pick and the sharper, deeper, and more frequent the teeth, the better the pick will hold; but the smoother the pick, the easier it is to remove. The teeth should be shaped to bite into the ice as you pull on the end of the shaft. Although thin, sharp edges penetrate and hold best, they are especially vulnerable to damage when they hit rock. A thin pick may place well, but is more prone to break from the twisting that often occurs when a climber tries to extract the tool. A thick-bladed pick, on the other hand, requires more force to place and is more likely to chip out plates



Fig. 14–4. Ice tools with various pick designs

of ice, but is less prone to break as you work to remove it.

With the conflicting demands on an ice tool, it's no wonder there is wide variation in pick design (fig. 14-4). Many tools are available with interchangeable picks, so you can choose the right one for a particular climb and replace a broken pick instead of discarding the tool. Talk to experienced ice climbers for help in choosing pick designs suitable for you. Here are the principal pick designs you will encounter.

Technically curved: The pick on a standard ice axe used in snow climbing curves slightly downward. But many of the shorter axes used in ice climbing feature a pick that curves down more sharply and holds better in ice. This technically curved pick is most often used on alpine and glacial ice. A good choice is an ice tool with a pick whose curvature matches your natural swing. The angle at the very end of the pick (which determines whether it has negative or positive clearance) is not a major consideration. The main thing is to keep the pick sharp.

Reverse curved: The ease of removal of a drooped pick that has some reverse curve (an upward curve) makes it a frequent choice for waterfall and other steep ice routes.

Straight drooped: An ice tool with a straight but sharply down-angled pick penetrates well in soft to hard ice.

Tubular: Tubular-nosed picks—thin and sharp—are popular for hard water ice because the tube shatters the ice less than a conventional pick.

Adzes

With the adze of an ice tool, you can chop steps, clear ice to make a good surface for screw placement, and cut footholds at belays. As with picks, adzes come in an array of shapes and sizes (fig. 14-5). Many ice tools accept interchangable adzes, letting you replace a broken adze or change adzes depending on ice conditions. You can even



Fig. 14–5. Side and end views of three adze designs

replace an adze with a hammer head.

The most common adze is straight, extending perpendicular to the shaft or drooping somewhat downward. The straight adze is excellent for cutting steps with sharp corners. Some adzes curve downward like the technically curved pick. The very end—the working edge—of some adzes curves slightly inward, although this impedes step-cutting because the full force of a swing is diffused. Tubular adzes are available, mainly for use on waterfall ice.

Shafts

The shafts of most ice tools are straight, but a few designs feature curved shafts (fig. 14-6). Be sure the curve of the shaft complements your natural swing. Curved shafts are designed to keep your knuckles from banging against the ice, aiding in a better placement.

Spikes

To penetrate ice, the spike on an ice tool must be sharp, and the joint between spike and shaft must be smooth. Spikes are solid or tubular. Solid spikes consist of a flat plate or a cone-shaped tip, and cone-shaped spikes point either straight down



Fig. 14–6. Curved-shaft ice tool



Fig. 14–7. Various ice-tool spike designs

or somewhat forward. Most spikes have carabiner holes, which you can clip to as a temporary anchor when setting up a belay anchor (fig. 14-7).

Attachment

A wrist leash from you to each ice tool serves several purposes. The leash secures a dropped tool, helps in the work of swinging the tool, and lets you rest your grip by hanging your weight from it.

A wrist leash is an energy-saving necessity on extremely steep or vertical ice. The leash attached through the carabiner hole at the head of the tool should be just long enough to let you grasp the shaft near the spike. The leash needs an end loop to slip your hand through. You may tie or tape the loop to the shaft at the desired hand position, to help hold your hand in the right spot at all times and direct the downward pull straight along the shaft (fig. 14-8). Used like this, the leash shares in the work of holding and swinging the axe.

The wrist leash also makes it possible to hang from an ice tool without maintaining a forearm-killing grip. To do this, let your arm hang straight, with hand and arm relaxed and body weight on your skeleton.

You can also rest by hanging from a tether that runs from the carabiner hole in the spike to your harness or gear sling. Make the tether long enough that it won't hinder your swing but short enough



Fig. 14–8. Wrist leash for ice tools

that it doesn't get in the way (perhaps catching on a crampon). Put an ice tool in a holster or tool loop when it's not needed.

ICE SCREWS

Ice screws evolved from ice pitons, which were extra-long, blade-type rock pitons with holes, notches, or bulges to increase their grip in ice. After World War II, climbers experimented with new designs that featured a greater shaft area to decrease the load per square inch on the ice and more holes to help the shaft freeze into the slope.

When ice screws first appeared in the early 1960s, enthusiasts claimed they would revolutionize ice climbing, bringing security to the slopes. Critics scoffed that the screws weren't much better than the older ice pitons. This proved particularly true of the lightweight, relatively weak "coat-hanger" ice screw, rarely used today. But ice screws continued to improve and now are considered reliable leader protection (fig. 14-9).

The modern tubular ice screw is the strongest and most reliable design. Commonly 7 to 9 inches long (18 to 23 centimeters), this screw works well in temperatures of both winter and summer. It is relatively easy to screw in and to screw out, with some models including a built-in ratchet for faster placement and removal. The hollow design minimizes fracturing of the ice by allowing the displaced ice to work itself out through the core of the screw.

After the screw is removed, ice inside the core must be cleaned out immediately or it may freeze to the interior, making the screw temporarily useless. The interior of some ice screws is slightly conical, permitting easier ice removal. If ice freezes to the inside, push it out with a length of stiff wire.

The shape and size of an ice screw have a great bearing on its strength. A large-diameter screw supports more weight than a smaller-diameter screw of the same length. A tubular screw holds a greater load than a solid one.

Another type of ice screw is hammered into place, but screwed back out. This type—developed in an attempt to make an easy-to-place and easy-to-remove screw—is available in both solid and tubular versions.

The solid versions can offer good protection in water ice at temperatures below freezing, but are less effective in other forms of ice and at higher temperatures. Melt-out is sometimes rapid because of limited thread displacement and, under load, they tend to shear through the ice. They can break



Fig. 14–9. Types of ice screws

if they aren't hammered in all the way, and they are sometimes tough to remove.

Hollow-core versions of pound-in, screw-out designs have the advantage of allowing the displaced ice to come out through the core instead of being forced aside by a solid screw. This design, with its small threads, can be placed with a series of light blows and removed relatively easily by unscrewing or by levering out with an axe pick. It works best in hard ice, but can be unreliable in temperatures above freezing.

OTHER GEAR

Holsters

You can add two holsters or a double-size holster to your seat harness for carrying ice tools. Try out the tools in the holster before you use it. The tools may be hard to remove if the holster was designed for small rock-climbing implements.

Ropes

Standard 10- to 11-millimeter climbing ropes are the most commonly used for ice climbing, though this depends on the type of climb and the preference of the climbers. Some ice climbers use a rope longer than the standard 50 meters (165 feet) to permit longer pitches. Some use double-rope or twin-rope techniques (outlined in Chapter 10).

Water-repellent ropes may be worth the extra cost because they won't freeze like regular ropes (though they can still become ice-coated). However, experience indicates the water repellency may not last the lifetime of the rope.

Head and eye protection

Your head and eyes need protection from the chunks of ice that start flying when climbers begin swinging their tools into ice. Helmets and goggles are both strongly recommended. The helmet, which also protects from rockfall, must adjust enough to make room for a stocking cap or balaclava. The goggles must fit when your helmet is on, provide protection from ultraviolet rays, and have adequate ventilation to minimize fogging. Sunglasses with side shields are an acceptable substitute.

TECHNIQUES OF ICE CLIMBING

A rock climber taking up ice climbing may find some striking similarities in the two pursuits. In both, climbers progress by moving their weight from one point of balance to another, support themselves as much as possible on their legs, and plan several moves in advance, climbing "with their eyes." On ice, as on rock, climbers use surface features, seeking out buckets and protrusions for handholds, footholds, and ice-tool placements. Of course, the differences are at least as striking. Ice climbers must rely on hand tools and on crampons. They learn to make do with anchors that can be uncertain, and they work in a medium that changes throughout the day and throughout the season.

TECHNIQUE OVERVIEW

Ice climbers usually employ features of two basic techniques, depending on steepness of the slope, conditions of the ice, and their ability and confidence level. They are known as the French and German techniques. The techniques are not mutually exclusive, and most climbers use aspects of both in working out the best way to handle a climb.

French technique (flat-footing)

French technique is the easiest and most efficient method of climbing gentle to steep ice and hard snow—once you learn how to do it. Good French technique demands balance, rhythm, and the confident use of crampons and axe.

French climbers developed the flat-footing technique, thus their terminology is commonly used. Terms using the French word *pied* refer to the feet; terms using *piolet* refer to the ice axe. *Pied à plat*, for example, is French for flat-footing. The name describes the technique: you must keep your feet as flat against the ice as possible at all times to keep all crampon points on the ice. It can be a difficult style to master because it requires severe rotation of the ankle on steep slopes.

The various French placements will be detailed later in this chapter. For now, here is an abbreviated directory of French ice-climbing terms, along with the approximate steepness of slope for each type:

For the feet:

• *Pied marche* (marching)	Gentle, 0 to 15 degrees
• *Pied en canard* (duck walk)	Gentle, 15 to 30 degrees
• *Pied à plat* (flat-footing)	Moderate to steep, 30 to 65 degrees and higher

For the ice axe:

• *Piolet canne* (cane)	Gentle to moderate, 0 to 40 degrees
• *Piolet ramasse* (cross-body)	Moderate, 35 to 50 degrees
• *Piolet ancre* (anchor)	Steep, 45 to 65 degrees and higher

German technique (front-pointing)

Developed by the Germans and Austrians for climbing the harder snow and ice of the eastern Alps, front-pointing can take an experienced ice climber up the steepest and most difficult ice slopes. With this technique, even average climbers can quickly overcome sections that would be difficult or impossible with French technique.

Front-pointing, in contrast to the choreography of flat-footing, is straightforward and uncomplicated. The technique is much like step-kicking straight up a snow slope, but instead of kicking your boot into the snow, you kick your front crampon points into the ice and step directly up on them.

Just as in French technique, however, good front-pointing is rhythmic and balanced, with the weight of your body over the crampons. Efficiency of movement is essential, whether it's planting your front points, placing your hand tools, or moving on the ice.

Although the Germans and Austrians developed it, German technique is frequently described with the general vocabulary of the French technique. Here is a brief directory of German technique, with approximate slope angles for each type. As you can see, aspects of French and German technique overlap in the steepness of slopes for which they are recommended. The proper technique to use depends on ice conditions and the preference of the climber.

For the feet:

• Front-pointing	For all angles from 45 degrees through vertical and overhanging

For the ice tools:

• *Piolet panne* (low dagger)	Steep, 45 to 55 degrees
• *Piolet poignard* (high dagger)	Steep, 50 to 60 degrees
• *Piolet ancre* (anchor)	Steep, 45 to 60 degrees
• *Piolet traction* (traction)	Extremely steep, 60 degrees through vertical and overhanging

CLIMBING WITHOUT CRAMPONS

Climbing gentle ice slopes without crampons is balance climbing, moving up from one position of balance to the next. At each point of balance, your inside (uphill) foot is in front of and above the trailing outside (downhill) leg, which is fully extended so you can put most of your weight on the bone of that leg, minimizing muscular effort. The axe, in your uphill hand, moves only after your body and feet are in balance, and your feet move only after the axe has been moved forward. As you climb, look for irregularities in the surface of the ice to use as footholds.

Step-cutting

The earliest method of ascending steep ice was simply to cut steps. The invention of crampons reduced the need for step-cutting, but never eliminated it. Climbers still encounter sections of ice when they are not carrying crampons or face short ice problems that may not merit taking the time to put on crampons. A broken crampon, or an injured or inexperienced climber, may be reason enough to cut steps. Even if you're wearing crampons, you might welcome a slight step chipped out by the axe for added security or to serve as a small platform to rest on.

A stairway chopped up an ice slope will consist of steps cut diagonally up the hill or of "pigeonhole" steps cut straight up the slope. In either case, the steps are cut from a position of balance. The usual sequence is to cut two steps from a position of balance, place the axe for security, move up to a new position of balance, cut two more steps, and so on.

A single line of diagonal steps is usually cut up gentle slopes, while a double parallel line of diagonal steps is put in on moderate slopes where balance is more of a problem. Pigeonhole steps are used on steeper slopes.

To make diagonal steps in relatively soft ice, such as summer serac ice, stand in a position of balance with the axe in your outside (downhill) hand (fig. 14-10). Swing the axe from your shoulder, cutting with the adze and letting the weight of the axe do most of the work. On harder ice, this takes extra muscle, and two hands may be necessary. With successive swings, slice ice out of the step. The swings cut away from your body, starting at the heel-end of the new step and working toward the toe. Scoop out chunks of ice with the adze and use the adze and pick to finish the step. (On steeper sections, you can cut small fingerholds to use while you are cutting steps.)

On hard ice that fractures easily, swing the pick horizontally into the ice to define the bottom of the step so that vertical chopping doesn't destroy the foothold. If you jerk outward on the axe just as the pick penetrates the ice, the pick should chip out the ice successfully rather than sticking in it. Make the step slope slightly inward to help keep your boot from slipping out. On gentle slopes, it may be OK if it holds only a small part of the boot, but steps on steeper slopes should be roomy enough for the entire boot. Space the steps so they are convenient for all members of your party.



Fig. 14–10. Cutting diagonal steps

When you're ready to change the direction of a series of diagonal steps, chop a hold large enough for both feet as a secure position for turning and for switching hands on the axe. For all step-cutting, you must attach the ice axe to your wrist with a leash to help support your hard-working hand and to prevent loss of the axe if you drop it.

Pigeonhole steps for the direct ascent of steep ice are placed about shoulder-width apart and within easy stepping distance of each other (fig. 14-11). Each step functions as both a handhold and foothold, so each should be large enough to hold the front half of a boot and should have a small lip to serve as a handhold. Cut the step, then create the lip with small chops of the adze.

If you decide to chop steps down an ice slope, the easiest method is to cut ladder steps that descend straight down the hill (fig. 14-12). To cut two steps in sequence, start in a position of balance, facing down the slope. Chop two steps directly below the ones you are standing in. When they are ready, step down with the outside (downhill) foot, and then the inside (uphill) foot. To cut just one step at a time, again start in a position of balance. Cut the step for the outside (downhill) foot and move that foot down into the step. Then cut the step for the inside (uphill) foot and move that foot down into it.

The step-cutter works at a tiring, difficult job on a slippery surface, often in an exposed location, and therefore usually needs to be belayed. The only way to be ready for that emergency when the skill of step-cutting can be a life-saver is to take the time once in a while to practice using your axe to chop steps.



Fig. 14–11. Cutting pigeonhole steps



Fig. 14–12. Cutting steps on descent

CLIMBING WITH CRAMPONS

Modern crampon technique, evolving from the French and German styles, moves an ice climber efficiently upward with minimum fatigue. Flat-footing is generally used on lower-angle slopes and where point penetration is easy; front-pointing is most common on slopes steeper than 45 degrees and on very hard ice. In practice, most climbers blend them into a combination technique. In any technique, the most important element is confident use of the crampons. Practice on gentle and moderate slopes helps develop skill, confidence, and the aggressive approach needed at steeper angles.

A skilled ice climber, whether flat-footing or front-pointing, displays the same deliberate movement as a skilled rock climber on a difficult slab. The crampon points must be carefully and deliberately placed on the ice, the weight transferred from one foot to the other smoothly and decisively.

Boldness is essential to skillful cramponing. Exposure must be disregarded and concentration focused solely on the climbing. But boldness is not blind bravado. It is confidence and skill born of time and enthusiasm, nurtured in many practice sessions on glacial seracs and on ice bulges in frozen gullies, and matured by ascents of increasing length and difficulty. (See Appendix 2 for an explanation of rating systems that are used in assessing the difficulty of ice climbs.)



Fig. 14–13. French technique: duck walk combined with ice axe in cane position (pied en canard/piolet canne).

Gentle to moderate slopes

French technique (flat-footing)

Many climbers find flat-footing awkward and needlessly complicated when they first try it. Once mastered, however, it provides great security because it keeps you in balance over your feet, with maximum penetration of all vertical crampon points.

Ankle strain can be eased by pointing your boots downhill more and more as the slope steepens, so the flex needed to keep your feet flat comes from the more normal forward flex of the ankle and from the knees, which are bent away from the slope and spread well apart. Boots that are flexible at the ankle help. In addition, unlacing the upper part of the boot may permit more ankle flex.

Walking on gentle slopes with crampons requires little more technique than walking anywhere else. Keep your feet slightly farther apart than normal to avoid snagging a crampon point on clothing or on a crampon strap on your other foot. Press all bottom points of each crampon firmly into the ice and walk straight forward (in the manner known as *pied marche*, or marching). Use the ice axe in the cane position (*piolet canne*), holding the axe in the self-belay grasp, with the pick forward and your palm on top of the adze.

As the slope steepens slightly, it will begin to get awkward to keep your toes pointing directly uphill. So splay them outward, duck fashion (*pied en canard*). Continue to use the axe as a cane, in *piolet canne* (fig. 14-13).

As the slope gets steeper still, heading straight upward in pied en canard causes severe ankle strain. Then it's time to turn sideways to the slope and ascend diagonally for a more relaxed, comfortable step. Keep the feet flat (*pied à plat*), with all bottom crampon points stamped into the ice (fig. 14-14). Don't try to edge with crampons. Start with your feet pointed in the direction of travel. As the slope steepens, you'll have to rotate your feet more and more downward in order to keep them flat on the ice. On the steepest slopes they may be pointing downhill.

As the slope angle changes from gentle to mod-



Fig. 14–14. French technique, on a diagonal ascent: flat-footing combined with ice axe in cane position (pied à plat/piolet canne).

erate, using the axe in the cane position becomes awkward. You can now get greater security by holding the axe in the cross-body position (*piolet ramasse*), as shown in figure 14-15. Grip the shaft just above the spike with the inside hand and hold the head of the axe in the self-belay grasp, pick pointing forward, with the outside hand. Drive the spike into the ice, the shaft perpendicular to the slope and roughly horizontal across your waist.

In the cross-body position, most of the force on the axe should be at the hand on the shaft. The hand on the head stabilizes the axe and is a reminder not to lean into the slope. You need a full-length ice axe, rather than a shorter ice tool, to keep your body from leaning into the ice. Even experienced ice climbers have difficulty maintaining proper French technique with a short axe.

Move diagonally upward in a two-step sequence, much the same as ascending a snow slope without crampons. Remember to keep your feet flat at all times (fig. 14-15). Start from a position of balance, your inside (uphill) foot in front of



Fig. 14–15. French technique, on a diagonal ascent: flat-footing combined with ice axe in cross-body position (pied à plat/piolet ramasse).

and above the trailing outside (downhill) leg. From this in-balance position, bring the outside foot in front of and above the inside foot, into the out-of-balance position. The outside leg crosses over the knee of the inside leg, because if the cross is made at the ankle, stability is compromised and the next step will be difficult to make. To return to a position of balance, bring the inside foot up from behind and place it again in front of the outside foot. Keep the weight of your body over the crampons. Avoid leaning into the slope and creating the danger of crampon points twisting out of the ice. Step on lower-angled spots and natural irregularities in the ice to ease ankle strain and conserve energy.

During this diagonal ascent, plant the axe about an arm's length ahead of you each time before moving another two steps. Whether you're using the axe in the cane or the cross-body position, plant it far enough forward so that it will be near your hip after you move up to the next in-balance position.

To change direction (switchback) on a diagonal ascent of an ice slope, use the same technique as on a snow slope where you aren't wearing crampons, but keep your feet flat (fig. 14-16). From a position of balance, place the axe directly above your location. Move your outside (downhill) foot forward, into the out-of-balance position, to about the same elevation as the other foot and pointing slightly uphill. Grasping the axe with both hands, turn into the slope, moving your inside (uphill) foot to point in the new direction and slightly uphill. You are now facing into the slope, standing with feet splayed outward. (If the splayed-foot position feels unstable, you can front-point.) Return to the in-balance position by turning your attention to the foot that is still pointing in the old direction. Move this foot above and in front of the other foot. Reposition your grasp on the ice axe, depending on whether you are using the cane or cross-body method. You're now back in balance and facing the new direction of travel.



Fig. 14–16. French technique, changing direction on a diagonal ascent: flat-footing combined with ice axe in cross-body position (pied à plat/piolet ramasse).



Fig. 14–17. French technique, on a diagonal ascent: flat-footing combined with ice axe in anchor position (pied à plat/piolet ancre).

Moderate to steep slopes

With steeper ice, other variations of the French technique are called for. At some point, the German technique of front-pointing comes into play.

French technique (flat-footing)

On moderate to steep slopes, you can switch the axe from the cross-body position (*piolet ramasse*) to what is known as the anchor position (*piolet ancre*) for more security. Your feet remain flat, with all bottom crampon points stamped into the ice at each step.

To place the axe in *piolet ancre*, begin in a position of balance. Grip the ice-axe shaft just above the spike with your outside (downhill) hand. Swing the axe so that the pick sticks into the ice in front of and above your head, with the shaft parallel to the slope (fig. 14-17a). With your other hand, take hold of the axe head in a self-arrest grasp. Now pull on the axe as you move two steps forward to a new position of balance (fig. 14-17c). A gentle and constant outward pull sets the teeth and keeps the axe locked into the ice. When you're ready to release it, push the shaft toward the ice as you lift the pick up and out.

In order to keep your feet flat at these angles, your body must lean farther away from the slope, knees and ankles flexed, and the toes of your boots will increasingly point downhill. Try to continue advancing upward in the standard sequence, moving two steps at a time. At the steepest angles, however, your feet will be pointing downhill, and you will have to begin shuffling your feet instead, moving backward up the slope. But continue to plant and remove the pick from a position of balance. The foot that is on the same side as your direction of travel should be at least slightly higher than the other foot, allowing the upper body to rotate for a smooth, strong swing of the axe.

You can change diagonal direction when the axe is in the anchor position by using the same sequence as with the cane or cross-body positions. However, on the steepest slopes, where you are shuffling backward, you can change direction simply by switching hands on the axe and planting it on your other side. There won't be much diagonal movement at this point, because you'll mainly be moving backward straight up the slope.

The French also devised a position—called *pied assis*—that gives leg muscles a rest and provides more security for replanting the axe (fig. 14-18). From a position of balance, bring your outside (downhill) foot up and beneath your buttocks, with the boot (flat as always) pointing straight downhill. Then sit down on that foot. You'll discover a balanced position, a relatively comfortable one.

The invaluable technique of flat-footing, used with the ice axe in the cane or cross-body positions, will serve an experienced climber for many alpine routes. For short stretches of steeper ice, flat-footing combined with the ice axe in anchor position will often work, but this marks the upper limit of French technique.

German technique (front-pointing)

On moderate to steep ice slopes, use of the French and German techniques begins to overlap. They both have a place on these slopes.

The French technique (flat-footing) takes a lot of practice to perfect, but most people pick up front-pointing quickly because it feels natural and secure. Unfortunately, this encourages climbers to use it excessively on moderate slopes where flat-footing would be more efficient and just as secure. In flat-footing, most of the stress is on the thigh muscles, where people usually have more strength than in the calf muscles strained by front-pointing. Even climbers who strongly prefer front-pointing would benefit from alternating the techniques to give calf muscles a rest.

Front-pointing uses not only the two forward points of each crampon, but also the two vertical points immediately behind them. These four points, properly placed, provide a platform to stand on.

Synthetic (plastic) boots provide a firm base for crampons and make front-pointing easiest. Full-shank stiff-soled leather boots also are good. Three-quarter-shank boots can be used in some cases, but require more muscular effort, while soft-soled boots are not suitable at all (fig. 14-19).

The best placement of the boot is straight into the ice, avoiding the splayed feet that tend to rotate the outside front points out of the ice. Boot heels need to be level in order to push the first set of vertical points into the ice and complete the four-point platform for standing (fig. 14-20).



Fig. 14–18. French technique: pied assis. The ice climber is using this position for rest and balance.



Fig. 14–19. Problems of trying to front-point with soft-soled boots

Resist the temptation to raise your heels higher. This pulls the stabilizing vertical points from the ice, endangering placement of the front points and fatiguing calf muscles. Your heels will normally feel lower than they really are, so if you think your heels are too low, the odds are that they are in the correct horizontal position. This is especially important coming over the top of steep ice onto a gentler slope, where the natural tendency is to raise your heels, relax your level of concentration, and hurry. This is a formula for trouble because it could cause the crampon points to shear from the ice.



Fig. 14–20. Correct boot position in front-pointing

Except in extremely hard ice, a firm, deliberate kick is usually enough to make sharp points bite. Kicking too hard or too often wastes energy and may shatter the ice. After placing the points, avoid foot movement because it can make them rotate out of the ice.

Front-pointing encompasses a selection of ice-axe positions.

Low-dagger ***(piolet panne)***: This position is helpful in tackling a short, relatively steep section that requires only a few quick front-pointing moves. For *piolet panne*, hold the axe by the adze in the self-belay grasp and push the pick into the ice near your waist, to aid balance (fig. 14-21). This position tends to hold you away from the



Fig. 14–21. Front-pointing, with axe in low-dagger position (piolet panne)

slope and out over your feet, the correct stance for front-pointing.

High-dagger ***(piolet poignard):*** If the slope is a bit too steep to insert the pick effectively into the ice at waist level, in low-dagger, move it into the high-dagger position (fig. 14-22). For this method, hold your hand on the axe head the same as if you were in self-arrest and jab the pick into the ice above your shoulder. Use the high-dagger in hard snow or relatively soft ice that the pick can penetrate easily.

Anchor position ***(piolet ancre):*** For harder ice or a steeper slope, you can abandon the high-dagger position for the anchor position that is also used in flat-footing. As you stand on front points, hold the axe shaft near the end and swing the pick in as high as possible (fig. 14-23). Front-point upward, holding on higher and higher on the shaft as you progress, adding a self-arrest grasp on the adze with the other hand when you get high enough. Finally, switch hands on the adze, converting to the low-dagger position. When the adze is at waist level, it's time to remove it from the ice and replant it higher.

Piolet traction: The steepest and hardest ice calls for piolet traction (fig. 14-24). The axe is held near the spike and planted high; the ice is then climbed by pulling down on the axe as you front-point up.

It becomes necessary to use a second ice tool on very hard or extremely steep ice when it gets too difficult to balance on your front points while replanting the axe. It's possible to use two tools at the same time because, except for the anchor position, all ice-axe techniques associated with front-pointing require only one hand.

Using two tools provides three points of support—two crampons and one ice tool—as you replant the other tool. The placements must be secure enough that if one point of support fails, the other two will hold you until the third point is replaced. The legs carry most of the weight, but the arms help with both weight and balance.

In double-tool technique, you can use the same ice-axe method for both hands or a different method for each. For instance, you can climb with



Fig. 14–22. Front-pointing, with axe in high-dagger position (piolet poignard)



Fig. 14–23. Front-pointing, using axe in anchor position (piolet ancre)



Fig. 14–24. Front-pointing with axe in piolet traction

both tools in low-dagger (*piolet panne*), as shown in figure 14-25. Or you can place one tool in high-dagger (*piolet poignard*) and the other in *piolet traction*, as shown in figure 14-26. The upcoming section on vertical ice spells out details of double-tool technique using traction with both tools.

Combination techniques

One fast and powerful technique combines flat-footing and front-pointing. It's called the three-o'clock position because as one foot is front-pointing, the other is flat and points to the side (to three o'clock if it's your right foot, or nine o'clock if it's your left). The French term for the position is *pied troisiéme* (fig. 14-27), literally "third foot."

Pied troisiéme is a potent resource for a direct line of ascent, much less tiring than front-pointing alone. The position lets you distribute the work over more muscle groups by alternating techniques with each leg. As you climb, seek out irregular flatter spots and any nooks or crannies for flat-footing, allowing you to rest calf muscles. With the ice axe, use whatever position is appropriate to the situation.



Fig. 14–25. Front-pointing, using low-dagger position (piolet panne) with two tools



Fig. 14–26. Front-pointing, using piolet traction with the tool in the left hand and high-dagger (piolet poignard) with the tool in the right hand

Climbers alternate crampon techniques depending on ice conditions. Flat-footing is usually more secure on frozen snow, ice crust over snow, and soft or rotten ice, because more crampon points dig into the surface. For soft snow over ice or hard snow, front-pointing or the three-o'clock position lets you blast through the surface to get points into the firmer layer beneath. Front-pointing is often the most secure technique for the average climber to use with very hard ice on all but gentle slopes. If you are having serious problems on a climb with flat-footing—perhaps due to fatigue, winds, high altitude, or fear—switch to front-pointing or the three-o'clock position.



Fig. 14–27. Three-o'clock position (pied troisiéme)

Vertical ice

The basic method of climbing vertical ice is front-pointing combined with use of two ice tools in piolet traction, in which you pull down on both tools as you ascend (fig. 14-28).

The standard position for the feet is about shoulder width apart and level with each other, a stable and relatively comfortable stance. Reach up and plant the pick of one ice tool as high as possible—but off to the side a bit so you're not hit by dislodged ice or by a tool that comes loose. Then plant the other tool, in the same manner.

From the back, your body at this point resembles an "X" against the ice wall. Your feet are level with each other, heels slightly down, and your arms are straight. As you pull down on the tools, also pull slightly outward to keep their teeth set in the ice and apply inward pressure on the crampon points. You can liken this to a mild lieback on rock. To conserve energy, you can now hang your weight from the wrist loops rather than gripping the tools tightly.



Fig. 14–28. Front-pointing on vertical ice, piolet traction with two tools

To ascend, grasp the tools and pull yourself higher as you step upward on the front points to a new level position. You're now ready to replant the ice tools higher, one at a time, returning you to the X body position. Repeat this sequence. Concentrate on efficient, methodical placement of crampon points and hand tools. Rhythm is as important as balance.

To overcome ice bulges and small overhangs, you can try the monkey hang (fig. 14-29). Starting from the X body position, walk your front points up the ice without raising your body. Loosen—but do not remove—one of the hand tools. Rise to a standing or nearly standing position by pushing with your feet and pulling on the tools, and in one smooth, continuous motion, remove and replant the loosened tool. Quickly rest that arm by relaxing the hand and letting the arm hang from the tool's wrist loop. Loosen and replant the other tool. You're now back in the X body position, ready to repeat the sequence.



Fig. 14–29. The monkey hang

Traversing steep to vertical ice

The principles for traversing are much the same as for front-pointing up steep ice. However, because you're moving to the side instead of straight up, it's more difficult to keep one foot perpendicular to the ice as you replace the front points of the other foot. If the heel rotates, the front points will also rotate and come out of the ice. Hand tools also tend to rotate out in sideways travel.

Start from a secure position—feet on the same level, with front points and hand tools in place (fig. 14-30). Replant the leading tool in the ice at about a 45-degree angle from your body. This puts it lower than if you were ascending, but not so far to the side that it causes your body to rotate out from the wall as soon as you remove the trailing tool. With the leading tool in place, you can shuffle sideways on front points. You also have the option of making a two-step move, crossing the trailing foot over the leading foot, and then bringing the other foot back into the lead. Most climbers prefer the shuffle, which is less awkward and feels more secure. After moving your feet, replant the trailing tool closer to your body. In good ice, the trailing tool can often be securely planted in a hole left by the leading tool—especially if the first tool leaves a small hole that can serve as a starter for a larger-nosed second tool.

Descending

Flat-footing

To descend gently sloping ice, simply face directly downhill, bend the knees slightly, and walk firmly downward (*pied marche*). Plant all bottom crampon points into the ice with each step. Hold the axe in the cane position (*piolet canne*).

As the descent angle steepens, bend your knees more and spread them apart, with body weight over your feet so all crampon points bite securely (fig. 14-31). Thigh muscles do the bulk of the work. For greater security, plant the axe perpendicular to the slope in the cross-body position (*piolet ramasse*), as shown in figure 14-32.



Fig. 14–30. Traversing vertical ice



Fig. 14–31. Flat-footing on descent, with ice axe in cane position (piolet canne)



Fig. 14–32. Flat-footing on descent, with ice axe in the cross-body position (piolet ramasse)

For the next level of security, use the axe in the support position (*piolet appui*), as shown in figure 14-33. Here's how to do it: grasp the axe near the middle of the shaft and hold it beside you as you descend. The axe head points uphill, with the pick down and the spike downhill.

As the slope steepens, switch the axe to the bannister position (*piolet rampe*), as shown in figure 14-34. To do this, grasp the axe near the end of the shaft. Swing the axe to plant the pick as far below as possible. Walk downward, sliding your hand along the shaft toward the head of the axe. It's important to maintain a slight outward pull on the shaft to keep the pick locked in the ice. Keep moving down until you are below the axe head. Then push the shaft against the ice to help release the pick, and replant the axe farther down.

On a slope too steep to safely descend facing outward, turn sideways and descend diagonally. Your footwork changes to the same flat-foot technique used to ascend diagonally. Use the axe in the anchor position (*piolet ancre*), as shown in figure



Fig. 14–33. Flat-footing on descent, with ice axe in the support position (piolet appui)



Fig. 14–34. Flat-footing on descent, with ice axe in the bannister position (piolet rampe)

14-35. With your outside arm, swing the axe out in front and plant the pick in the ice, take hold of the head with the other hand in the self-arrest grasp, and then flat-foot diagonally down below the axe. The shaft rotates as you pass below it.

Front-pointing

It's often tiring and ineffective to try front-pointing down a gentle to moderate slope. A climber tends to be bent over, facing the moderate slope, and to vacillate between flat-foot and front-point technique.

On steep slopes, front-point and hand-tool techniques are generally the same for going down as for going up. But just as on rock, downclimbing is more difficult. There is a tendency to step too low, which keeps the heel too high, so front points may



Fig. 14–35. Flat-footing on descent, with ice axe in the anchor position (piolet ancre)





shear out or fail to penetrate in the first place. It's awkward to plant the ice tools because they must be placed closer to your body, so you lose the power of a good full swing. You don't get a good view of the route on a descent (although descending on a slight diagonal will help).

Climbers don't often front-point a descent, but it's still a valuable skill for occasions such as retreating from a route. Downclimbing ability also builds confidence in ascending.

Rappelling

Ice climbers often descend on rappel, sliding down a doubled rope attached through an anchor, just as in rock climbing. They use natural anchors whenever possible, of course, because snow flukes or other manufactured anchors used for rappelling usually must be left behind, a costly way to go.

PLACING ICE TOOLS

With any ice tool, the goal is accuracy and a solid placement—the first time. One or two swings saved at the bottom of a pitch mean that much more energy at the top. It takes a lot of practice to learn pinpoint placement. But with a combination of proper technique and equipment, you should be able to place a tool easily and precisely, keep it secure for as long as it's needed, and extract it with less effort than you took to place it (fig. 14-36).

Study the ice for a good placement. A slight depression above and slightly to the side is likely to be good. Ice is more compact and holds the pick better in depressions than in bulges, which shatter or break off under the impact of an ice tool. Try to make placements in opaque ice, less brittle than clear ice because it has more air trapped inside. Minimize the number of placements by planting the axe as high as possible and by moving upward as far as you can with each placement.

Different climbers will have different experiences, though they may be using identical tools on the same climb, because of differences in ability and climbing background. The more experienced climber, for instance, may climb confidently with only a small bite of the pick into the ice, while another climber might not feel comfortable without slamming the tool deep. On most tools, only the first few teeth provide any useful bite in the ice, and the upward angle of the pick in the ice provides most of the holding power. (On an ice tool, small teeth often perform better than large teeth.) Keep your tools sharp.



Fig. 14–36. How to remove an ice tool

Placement and removal techniques will vary somewhat, depending on the type of pick that is on the ice tool:

Technically curved: These picks result in an ice tool that is most like a standard ice axe. However, the picks are curved more than on a regular axe to hold better in ice, and the shaft is shorter to permit an easier swing on steep surfaces. A tool with a technically curved pick requires a natural swing, from the shoulder. The first swing should result in a satisfying, solid "thunk"—the sound and feel of a well-placed ice tool. This tool is used in conditions ranging from soft serac ice to hard water ice, though you may need to weight a lighter tool (perhaps with lead sheet taped to the head) for good penetration on hard ice. The pick is usually removed from the ice by lifting straight up on the shaft.

Reverse curved: While technically curved picks take a natural swing, the sharp angles of the reverse-curved and straight-drooped picks require a shorter, choppy swing. A reverse-curved pick, featuring a drooped pick with a slight upward curve, penetrates waterfall ice with a straight, downward hooking motion. It is usually easy to remove.

Straight drooped: This sharply angled pick requires a decisive downward flick at the end of a short swing, making it penetrate well in ice from soft to hard. It is fairly easy to remove by using an up-and-down levering motion. Avoid sideways twisting.

Tubular: A tubular-nosed tool works best with a short-arc swing and often grips securely on the first try. A tubular pick is moderately easy to remove by twisting sideways while holding the head (up-and-down levering can fracture the nose). The nose dents easily and is particularly vulnerable if the climb involves ice with sand or rocks close to the surface.

ROPED CLIMBING TECHNIQUES

Climbers usually rope up on ice. The principal exception comes when they decide that overall team safety is served best by climbing unroped. Late on a stormy day, for example, or while ascending a couloir threatened by rockfall, the greater speed of unroped travel might offer relatively more safety than continuing on the rope. It is also sensible to unrope through a section so difficult to protect that a fall by one roped climber would sweep them both away.

Ice climbers can get a measure of protection that is somewhere between climbing on belay and climbing unroped by setting up a running belay. It's another way for a team to move faster when storms or avalanches threaten and, more than ever, speed is safety. It can also be useful on gentle to moderate terrain where danger of falling is minimal and actual belays would be too time-consuming.

A running belay on ice is created very much the same as a running belay on rock (described in Chapter 10) or snow (described and illustrated in Chapter 12). Team members move simultaneously. The leader places protection as they climb and clips the rope through it; the follower removes the protection. The idea is to keep at least two points of protection between them at all times to hold the rope in case of a fall. Because this technique sacrifices much of the safety of true belaying, the decision to use it takes fine judgment, based on extensive experience.

Full belaying on ice requires a belayer, belay anchor, and intermediate points of protection, just as it does on snow or rock. A belay anchor is set up and the leader climbs the pitch on belay, sets up another anchor, and then belays the follower up the route. The climbers can either swing leads or have a single climber continue as the leader.

PROTECTION ON ICE

Modern ice screws offer dependable security on ice climbs. However, there is some sacrifice of safety in the time and energy it takes to put them in place. Leaders, therefore, commonly place fewer points of protection in a rope length on ice than they would in a rock pitch of the same length. Ice climbers also make some use of natural protection.

Natural protection

Ready-made natural protection is hard to come by on an alpine ice route, although climbers make use of the medium to fashion ice bollards. Good natural protection may be available not on the ice itself, but in rock bordering the route or protruding through the ice.

Natural protection is often found on frozen waterfalls, where runners can be placed around ice columns. Climbers also devise some slightly unconventional protection points. On frozen waterfalls or high alpine routes, where large ice columns may form only an inch or two apart, an ice screw tied off with webbing can be inserted behind the columns and turned sideways as a deadman. You may find a sheet of ice separated from the underlying rock by an inch or two, leaving a slit that can be enlarged enough to insert a screw tied off with webbing; again, turn the screw sideways to function as a deadman. You can also punch two holes in the sheet of ice, thread a runner through them, and clip the rope into it. On mixed rock and ice climbs, rock-climbing chocks may be wedged into ice holes.

Ice bollards

A bollard can be among an ice climber's most useful anchors. It can be used for rappelling or belaying. By linking together two bollards, one cut for an upward pull and the other for a downward pull, you have a multidirectional anchor. The strength of a bollard is proportional to its size and the hardness of the ice. Made of hard, solid ice, it can be stronger than the rope.

A completed ice bollard is teardrop-shaped when viewed from above, and horn-shaped when viewed from the side (fig. 14-37). All you need for a bollard is an ice axe and good ice, uniform and without cracks or holes. Cut the outline of the bollard with the axe pick. In hard ice, give it a diameter of 12 to 18 inches (30 to 45 centimeters) across the wide end of the teardrop. Cut a trench around the bollard at least 6 inches (15 centimeters) deep, working outward from the outline with both the pick and the adze.

Undercut the sides and top half of the bollard to form a horn that prevents the rope from popping off over the top. This is the most sensitive part of the construction because you can easily fracture or break the bollard if you're careless with the axe.

Ice screws

A favorable location for an ice-screw placement is the same as for an ice tool. A good choice is a natural depression, where fracture lines caused by the screw are not as likely to reach the surface (fig. 14-38a).

A screw placed into a bulge in the ice, on the other hand, can cause serious fracturing that weakens the placement or makes it useless. If this happens, move the screw a foot or two and try again. Generally keep screw placements at least 2 feet apart—more in rotten ice—to reduce chances that fracture lines from one placement could reach the other, weakening both.

The procedures for placing a screw vary somewhat with ice conditions, but the basic routine is



Fig. 14–37. Ice bollard: a, diagram; b, with backup ice-tool anchor.

much the same in any case: punch out a small starting hole with the pick or spike of a hand tool, to give a good grip for the starting threads or teeth of the screw. Make the hole gently, with light taps, to avoid fracturing the ice. Start the screw in the hole, angled uphill 45 to 60 degrees against the anticipated direction of pull. (On hard ice, it may take a few light taps to make the threads catch.)

On ice topped with a layer of soft snow or rotten ice, scrape down with the adze to get to a hard, trustworthy surface before making the starting hole (fig. 14-38b). In extremely rotten ice, make a large horizontal step with a hand tool and place the screw vertically at the back of the step, in a starting hole (fig. 14-38c). Press the screw firmly and twist it into the ice at the same time.

When glacier ice fractures and shatters at the surface, you may still be able to get a secure placement by continuing to install the screw and gently chopping out the shattered ice with sideways strokes of the pick.



Fig. 14–38. Ice-screw placements: a, in solid surface; b, with soft or rotten surface layer; c, in extremely rotten ice.



Fig. 14–39. Screwing in an ice screw with an ice tool

A screw with sharp cutting teeth can sometimes be screwed in all the way by hand. If not, do it with the help of a lever through the screw eye; another ice screw or the pick of a hand tool works well (fig. 14-39). Some screws provide a kind of built-in ratcheting capability, simplifying the work of screwing them in.

Twist the screw all the way until the eye is against the ice, tight and solid. Clip a carabiner into the eye, with the carabiner gate down and out. To slow melt-out in soft summer ice or direct sun, pack ice around the screw head. If the screw doesn't go in all the way, reduce leverage on it by tying it off at the surface of the snow with a runner, and then clipping into the runner.

Climbing extremely steep ice is fatiguing, physically and mentally. To conserve energy and keep moving upward efficiently, climbers work to minimize the number of screw placements. If the ice is hard and solid, or the slope not extremely steep, only one or two protection points may be placed on an entire pitch. Unless the ice is rotten, only one screw is placed at each protection point.

It usually takes two hands to place an ice screw, ticklish business on extremely steep, exposed ice. For extra support, you can slip one arm through the



Fig. 14–40. Support from hand tools while placing an ice screw: a, through wrist leashes; b, from runners between tools and seat harness.

wrist loop of a solidly planted hand tool (fig. 14-40a). Or clip a runner from your seat harness to one or two securely placed hand tools (fig. 14-40b).

On a moderate to steep slope, it may help to chop a step for standing in as you place the screw. On extremely steep ice, however, it's too difficult a job, so save your energy. When it's time to place an ice screw, do it from your front points, and then continue climbing.

BELAYING ON ICE

Near the end of a pitch that you are leading, keep an eye out for a good belay spot, perhaps at a slight depression or where the ice is not so steep. Place a hand tool off to one side and clip in for temporary protection while you chop a step large enough to permit you to stand facing the ice with both feet flat and splayed.

Belay anchors

A standard anchor set-up for an ice belay takes two ice screws. Place the first screw in the ice in front of you, a bit to one side, at about waist to chest level. Clip in a carabiner and tie into it with the climbing rope as it comes from your seat harness. Use a clove hitch or figure-8 knot.

Unclip from the hand tool that was placed as a temporary anchor and replant that tool above and to the outside of the ice screw. Clip the tool to the screw (via the wrist leash or a runner) as a backup to the anchor. Then tell your belayer down below that you are off belay.

Now you can place the second ice screw. Put it



Fig. 14–41. Anchor set-up for an ice belay

above you and about 2 or 3 feet higher than the first one. Extend the climbing rope from the first screw to the second screw and tie in with a clove hitch. There should be little or no slack between the two screws. This completes the anchor set-up (fig. 14-41).

The next step in establishing your belay is to clip another carabiner into the second ice screw and clip the belay rope through the carabiner. This directs the pull from the climber through this screw. And after the follower ascends to the belay station and starts upward to take the lead, that screw becomes the first piece of protection on the new pitch.

Belay methods

You have the choice of using a mechanical belay device, a Münter hitch, or a hip belay. The anchor set-up is the same in any case. Your choice will probably depend on what you're accustomed to and on your degree of confidence in the anchor. The hip belay tends to be somewhat dynamic, with a bit of movement at the belay—resulting in a slower stop to a fall but less force on the anchor and intermediate protection points. Belay devices and the Münter hitch, on the other tend, tend to be less dynamic, stopping a fall faster but putting more force on the anchor and intermediate protection points. (See Chapter 7 for details on the various belay methods.)

Mechanical devices

A Münter hitch, or a belay device such as a slot, tube, or Bachli, is easy to set up and efficient in use. Many ice climbers use such a method as standard procedure. The mechanism is usually situated at your seat harness (fig. 14-42), though you also have the option of belaying directly from the anchor.



Fig. 14–42. Ice belay set-up for a mechanical belay device or Münter hitch at the climber's seat harness



Fig. 14–43. Ice belay set-up for a hip belay



Fig. 14–44. Boot/ice-screw belay

Hip belay

You can establish a hip belay as you stand facing the ice by running the belay rope through a control carabiner at your waist, around your back, through an extra carabiner on the first screw, and then into your braking hand (fig. 14-43). This arrangement is especially favored when the rope is stiff and frozen and could jam in belay devices.

Boot/ice-screw belay

For flat or gentle ice slopes, the boot/ice-screw belay is very useful (fig. 14-44). Here's how to do it: start by twisting an ice screw into place, then clip in a carabiner and run the belay rope through the carabiner. Plant your uphill boot over the screw, perpendicular to the direction of pull. Place the boot so that the inside point of your mid-boot row of crampons goes through the carabiner. Don't jab the rope. Bring the belay end of the rope over your instep, around the back of your boot ankle, and into your uphill hand.

You control friction on the rope by the amount of wrap on the ankle, much as in a boot-axe belay. You can also adjust the space between the edge of the boot and the outside edge of the carabiner. If the climber falls, slowly tighten the rope low against the ankle with your uphill hand.

Helpful variations of the boot/ice-screw belay include two that utilize the Münter hitch. Use a large pear-shaped carabiner, which has the correct diameter for the Münter, instead of a standard carabiner. In one method, simply use a Münter hitch at the carabiner instead of running the belay rope around your ankle (fig. 14-45). Another method permits you to operate the belay while standing (fig. 14-46).



Fig. 14–45. Boot/ice-screw belay using Münter hitch



Fig. 14–46. Boot/ice-screw belay using Münter hitch while standing

THE ICE CLIMBER

To climb steep ice, you'll use a lot of what you learned in rock and snow climbing and add in the special tools and techniques for ice. As an ice climber, you will especially share the joys of snow climbing, along with its perils: avalanches, hazardous couloirs, and unstable cornices, ice blocks, and icefalls. (Chapter 12 provides a full catalog of snow-climbing dangers and how to avoid them.) You can find climbing opportunities year-around, from the winter challenge of waterfall ice on short dark days in cold weather to the summer experience of alpine ice on days that are long and warm.

Skill and confidence in ice climbing comes from long practice. If you can link up with a steady partner, so much the better. Practice together often. Work on pinpoint ice-tool and crampon placement, which conserves energy so you can meet the rigors of serious routes. Also work to increase the speed and efficiency of your climbing, gearing it to the conditions of the ice and the current strength of your body. Learn to determine when you and your partner should rope up for protection—and when it's safer not to. An experienced ice climber learns these skills and applies them with confidence and good judgment.

◆ 15 ◆

WINTER AND EXPEDITION CLIMBING

Climbers enter a new world of effort and commitment when they take on winter or expedition climbing. There are big differences between the weekend alpine climbing practiced by most climbers and the winter and expeditionary mountaineering of the serious amateur climber or the professional alpine mountaineer. Winter climbing brings severe conditions that require specialized equipment, a high level of skill, and a tremendous will to succeed. Expedition climbing demands the skills of winter climbing in addition to the logistics of an extended trip, often in a foreign country.

The weather takes on a new importance during winter and on expeditions. On a typical weekend summer climb, weather is seldom a big issue. If the weather is poor, you can cancel the climb and try again when it gets better. If the weather turns poor on the climb, a bit of unpleasantry usually gets climbers down from the route and a wet walk brings them back to the trailhead. In the winter, however, good weather is harder to come by and frustrated climbers may give it a try despite a marginal forecast. If the weather does turn poor, descending the route and returning to the cars may become a mini-epic, with routefinding difficulties and increased danger from cornices and avalanches. On expeditions, the climbing team rarely has the luxury to pick and choose the weather. Once the team leaves town, the trip schedule grinds on inexorably and weather becomes a condition that must be dealt with like any other obstacle on the trip.

Extremes of hot and cold are common. You expect low temperatures during the winter, but it can get hot, too. On windless, cloudless days the temperature soars as sunlight reflects from the snow. Then, as quickly as a cloud can sail across the sky, the temperature plummets. At night, radiative cooling into a cloudless sky can create temperatures that test the mettle of the finest sleeping bag.

The shorter length of day is another obvious challenge of winter climbing. At the winter solstice, in the higher latitudes, the hours of daylight may be only half the hours available in summer. This means fewer hours for climbing and more hours of sack time in camp waiting for daylight. The winter camp must be made more comfortable for the long hours of waiting, and goals must be scaled back from summer expectations. You may decide to put off the most challenging climbs until late winter, when the day is longer. On expeditions, especially at higher latitudes during the summer, the shortness of day isn't usually a problem. However, climbers often adjust their own internal clocks, traveling in the cooler hours of early morning, late day, or even at night to reduce the problems of soft snow, rockfall, or avalanche.

If your goal is one of the high mountains of the world, acclimatization to the altitude is essential.

Schedules must match not only your ability to climb the route but the ability of your body to meet the rigors of living at high altitudes. More than one climber on the "dog" route of a high peak has turned back not because of weather or technical difficulties but because of too rapid an ascent.

To pull off a successful winter climb or expedition, it often takes a lot of extra gear. For a one-day summer rock climb, you may need little more than a rope, rack, lunch, water bottle, and windbreaker. But the pack for even the simplest winter climb is heavier, with more equipment and clothing. The pack for an overnight trip must accommodate a warm sleeping bag for the low temperatures, a comfortable four-season tent for the long nights and more severe weather, and an ample stove and cook kit. An expedition multiplies the amount of food and fuel by the length of the trip. The expedition also may require extra climbing equipment for "fixing" parts of the route, leaving ropes in place for the safety of climbers and porters.

Looking at all the special demands of winter and expedition climbing, it's no surprise you need exceptional endurance. This is different than the intense short-term effort made by weekend climbers, who are accustomed to the early Saturday morning drive to the trailhead and the bleary-eyed drive back home Sunday night or early Monday morning. It's the marathon run compared with the 100-yard dash. On an expedition, bursts of intense effort cannot be sustained, as the body does not heal or recover quickly at high altitudes. Team members need to find levels of physical and mental effort they can sustain for the entire trip. Save the climbing "burnout" of the weekend climb for the final summit push, and don't waste it on hauling a load between base camp and Camp 1.

Winter travelers often find the season's solitude a virtue of their adventures. Likewise, the expedition climber may cite the distance from civilization as a benefit. With this remoteness comes the need for self-sufficiency. The climbing team must rely on its own resources to get out of a jam because self-rescue is the only option when the nearest help is days or weeks away.

Winter mountaineering and expedition climbing have much in common. Most expeditions are to places where the climbing is decidedly wintery, such as Mount McKinley or the Himalaya. The best way to learn winter climbing is through multiday trips in your own part of the world. These climbs are obviously cheaper and easier to schedule than trips to Alaska or Nepal, but they get you fit and skilled for expedition climbing.

WINTER MOUNTAINEERING

Climbing in winter is a natural extension of climbing at other times of the year, with a lot of similar techniques and equipment and many of the same goals and rewards. It's just more complicated. This chapter goes into a number of topics that were taken up in earlier chapters, such as clothing, tents, and routefinding—but covers them in the specific detail needed to help you stay safe and comfortable in winter.

CLOTHING

Climb often enough in the mountains, and even in the summer you will encounter winterlike conditions. Likewise, many of the best winter climbs are done when the weather resembles spring. Your clothing and equipment must be prepared to accommodate both extremes.

For winter, summer clothing serves as the starting point. Begin with a wicking layer of underwear, followed by whatever layers of insulating clothing the weather dictates, topped off by a windbreaking layer. How much extra clothing you bring, and what kind, depends on the type of winter you can expect at your destination. Additional layers of synthetics work best in the cold damp of maritime climates. Where winter is drier and colder, you can take advantage of the lightness and compactness of down, which must be kept dry.

The dangerous chilling effect of wind means you must always pack a complete layer of windproof clothing during the winter. The wind layer needs to fit over all the insulating layers you are likely to wear at one time, and should overlay or tuck together for a solid shield against the wind. If you've left any chinks in the armor, the wind will find them. Fabrics vary in their windproofness so get recommendations from other climbers and from the people at outdoors stores. Laminated materials such as Gore-Tex are among the most windproof. (Chapter 2 has more information on clothes for mountaineering.)

Keeping dry

On a hot summer day, a sweaty shirt dries quickly in the sun and heat after you've stopped working. But in winter, there is little warmth from the sun to dry out wet clothing. The only other source of heat to dry a shirt is your own body, and tremendous amounts of energy are necessary to evaporate water. Wearing damp clothing is the quickest way to chill yourself.

Avoid dampness by regulating your pace and not allowing yourself to overheat. If clothes get damp, either from perspiration or precipitation, change as soon as camp is reached. If several layers of clothing are damp, at least change the layer closest to your skin.

CARE OF THE FEET

Because of their distance from the body core, extremities have the poorest circulation. To make matters worse for your feet in winter, they are always close to snow or ice. The same factors that keep your body warm—adequate insulation and staying dry—will also warm your feet.

The advent of plastic double boots made it much easier than before to keep your feet warm and dry. The plastic shell is an absolute barrier to snow and water, while the inner boot provides the insulation.

In some circumstances, bunny (or mouse) boots are an option. Developed originally for the military for arctic conditions, bunny boots rely on felt insulation sandwiched between airtight and watertight rubber inner and outer boots. The boot is not rigid and is best suited for non-technical routes. Because the rubber serves as a vapor barrier, keeping perspiration inside, it's necessary to dry your feet and change damp socks daily.

Gaiters are needed for keeping snow from entering the boot from the top. Standard gaiters cover the boot top and lower leg, while supergaiters add an additional layer over the entire boot. Overboots go one step further by including a layer, which quickly sheds snow, below the boot as well. Various brands of supergaiters and overboots offer insulation as well as a snow barrier.

Inside the boot, a vapor barrier sock will keep your foot warmer by preventing perspiration from evaporating. The energy required by evaporation robs warmth from your feet. The vapor barrier also keeps outer socks and boots drier. The sock is worn over a light pair of liner socks and beneath a heavier pair of insulating socks. The major disadvantage to vapor barrier socks is the necessity to change the liner socks and dry your feet each night. Apply foot powder and a strong anti-perspirant (not merely a deodorant) to help keep feet dry and comfortable—and watch out for blisters on the soft, moist skin.

The right socks are important in keeping your feet warm, but too many socks can do just the reverse. They can make the boot tight, restricting circulation and causing cold feet.

HEALTH

Surprisingly, dehydration is a winter hazard. Sweat may not pour from your brow the way it does in summer, but depending on your level of exertion and the dryness of the air, significant moisture loss occurs. Also, fluid intake normally drops because people don't crave cold drinks during the winter. Make a conscious effort to drink enough fluids to keep your urine output copious and clear. This need for fluids highlights the importance of a stove that can dependably melt plenty of snow for drinks.

Hypothermia and frostbite are more traditional winter health hazards. Both can be prevented by awareness of the hazards and by adequate clothing, food, and water. Avoid chills by staying as dry as possible and eating and drinking adequately. If you become chilled, do something about it. Put on more clothes or change damp clothes. If your feet are numb, wiggle your toes vigorously in the boot. If these actions don't work, it may be necessary to take a break to warm the numb body parts. When camp is established, inspect feet and fingers for frostbite and treat as necessary. (There is some general information on frostbite later in this chapter, but be sure to consult a first-aid text for details.)

As a member of a climbing party, you're responsible for taking good care of your own health and guarding against problems that could jeopardize the climb or endanger fellow climbers. At the same time, keep alert to any health problems of other team members.

WINTER CAMPING

Winter camping, more so than summer camping, demands well-developed rituals and habits. Efficiency and safety get a boost if everyone is familiar with their assignments. A tent goes up quickly and easily if two or three members of the party know exactly who does what: who holds the tent to keep it from blowing away, who threads poles through the sleeves, and who pushes the poles. Here's a look at the principal techniques and equipment that go into successful winter camping.

Snow shovels

The snow shovel (fig. 15-1) is a fundamental piece of equipment for the winter mountaineer, used to excavate climbers from avalanche debris, dig emergency shelters, prepare tent platforms, and—in some conditions—clear a climbing route. In choosing a shovel, a climber is torn between the heavy, bulky grain scoop, ideal for moving large amounts of snow quickly, and the compact folding or collapsing shovel, convenient to carry and therefore less likely to be left at home. A large party has the strength to carry both types. A small party will want to examine the route and expected uses before deciding which type or how many to take. If you expect to cut any sort of snow blocks for snow constructions, you will also need a snow saw.

Shelters

For overnight winter trips, you can stay in a tent or in a snow shelter. Tents are much easier to set up, but a good snow shelter is much sturdier. Both



Fig. 15–1. Snow construction tools

have their virtues depending on the situation, and you should know how to set up either one.

Snow shelters

A well-made snow shelter is far more secure than a tent. In a storm, as the snow piles up, the snow shelter becomes even more secure while the tent must be continually cleared of snow. Sometimes a snow shelter is the only possibility, such as on a narrow, windy ridge with no space for a tent. A snow shelter requires no special equipment other than a shovel and, sometimes, a snow saw.

Even if you use tents for sleeping, a snow shelter is a useful addition for an extended stay in one spot. The snow shelter can be the communal hall where cooking and socializing take place without fear of spilling soup on a sleeping bag or tearing a hole in a tent wall. The extra shelter also serves as a warehouse for equipment and a place of refuge if a tent fails in extreme conditions.

On the negative side, snow shelters take time to build; 2 to 3 hours is common. If you'll only be there one night, it may not be worth the effort. Building a snow shelter is hard work and may leave the building crew wet from perspiration and from the snow. In some circumstances a snow shelter is warmer than a tent. But if it's midday and the sun is out, the inside of a tent can be 40 or 50 degrees warmer than the outside air, and makes a great place for drying sleeping bags and clothing.

There are pluses and minuses to a number of snow-shelter designs. Check back to Chapter 3 for a look at how to build some of them.

Snow caves require both adequate snow depth and the right topography. Look for a fairly steep slope to dig into; it's much easier than trying to dig a cave into a shallow slope. The snow must be deep enough so you won't hit ground before you can excavate a cave that's large enough.

With igloos, the depth of the snow is not as critical because they are constructed of snow blocks. Therefore it's usually easier to build an igloo with lots of space and headroom than a roomy snow cave. In addition to a shovel, igloo construction requires a snow saw, experience in the art of igloo building, and good block-cutting snow. If the snow isn't just right, and the snow blocks fall apart as you move them, forget about building an igloo.

You can also create hybrid snow shelters, combining igloo and snow-cave techniques. To make a typical hybrid shelter, dig into a snow slope through a relatively large opening; this makes it easy to excavate snow. When the cave is big enough, close the opening over with snow blocks. Then dig a smaller entrance for access to the shelter. Various types of trenches also provide shelter in the snow. (Chapter 3 also has details on snow trenches.)

Snow-shelter construction is a useful skill and it can be fun, but for short winter trips these shelters are not usually practical to build. It is on longer trips, where the investment in the snow shelter can be amortized over several nights or where conditions are too extreme for a tent, that snow shelters are most valuable.

Tents

Tents are the first choice in shelters for the typical weekend winter outing. A quality winter tent must be sturdy enough to withstand high winds and snow dumped during the night. Steep side walls aid in clearing snow off the tent, and an aerodynamic shape helps outwit the wind. Free-standing dome-type tents work well, and so do the tunnel-style (hoop) tents, which require a few stakes (fig. 15-2). Every winter tent, free-standing or not, needs multiple lashing points for tying into anchors to keep it from taking off like a box kite in a strong gust. The considerations that go into selecting and using a good winter tent apply likewise to tents used for expeditions.

Size: For extreme routes, where flat real estate is rare and weight is a supreme consideration, consider the compact and lightweight "wedge" tent, a free-standing design with two poles that go from corner to corner and cross in the middle. On most winter trips, however, you will want a tent that is roomy, though heavy. The extra room is used to store packs and personal gear as well as reduce feelings of claustrophobia during 15-hour nights in the tent.



Fig. 15–2. Winter-quality tents: a, hoop style; b, dome.

Construction: Although single-walled tents of rainproof, breathable fabric are lighter, double-walled tents (with an integral or separate rain fly) are somewhat warmer and less subject to icing on the inside wall. Aluminum tent poles are usually stronger than fiberglass poles. High-tech poles of such materials as Kevlar or carbon fiber may someday supplant aluminum.

Features: Certain conveniences simplify wintertime tent living. These include multiple entrances (in case one entrance bears the brunt of the weather), a vestibule for cooking or storage, gear pockets inside the tent for organizing small items, and inside loops for hanging clothes or a lantern.

You can't pitch a tent without giving some thought first to selecting and preparing a site. Some tips:

Use the terrain to your advantage. Select a spot that is as near to flat as possible to make site preparation easier. Watch out for hazards such as crevasses, avalanche paths, and cornices. Observe the local wind patterns: a rock-hard or sculpted snow surface indicates frequent wind, while a loose powdery area indicates a zone where wind-transported snow is deposited. Keep in mind that although the powdery area may be protected from the direct wind, the tent may have to be cleared of snow frequently.

Compact a large-enough area for the tent and for movement around the tent to check tie lines or clear snow. Flatten and smooth the tent platform thoroughly to keep you from sliding toward one wall or the other during the night and to get rid of any uncomfortable lumps. This is especially important if you're staying for several nights, because the entire tent platform becomes rock hard with all features cast in ice after the first night. A ski does a great job of smoothing the tent platform.

Dig an entrance pit 1 foot or so deep once the tent is erected. The pit in front of the main tent door makes entering and leaving easier, as you can sit comfortably in the doorway and place your feet in the pit.

Build snow walls around the tent if the site is exposed to winds. The walls can be anywhere from about 3 to 6 feet high and will deflect some of the wind away from the tent (fig. 15-3). Keep the walls as far away from the tent as they are high (a 3-foot wall, for example, should be 3 feet away from the tent), because wind will deposit snow on the leeward side of the walls and fill this area quickly. Blocks cut by a snow saw make the easiest, quickest walls, though you can also just shovel snow into a pile to serve as a wall.

A number of special items are useful in winter camping. Each tent should have a snow brush—a small broom with synthetic bristles to sweep snow from boots, packs, clothing, and the tent. Each tent also needs a sponge for cleaning up cooking or drinking-cup spills and removing condensation from the inside tent walls. A cheery addition to a tent, especially during the long nights near the winter solstice, is a candle lantern. You might even consider a gas lantern, which can repay its price in weight and bother by bringing tremendous brightening and warming to a tent.

For anchoring a tent, you can use wide-profile stakes, mini snow flukes, or regular snow anchors.



Fig. 15–2. Winter-quality tents: a, hoop style; b, dome.

Construction: Although single-walled tents of rainproof, breathable fabric are lighter, double-walled tents (with an integral or separate rain fly) are somewhat warmer and less subject to icing on the inside wall. Aluminum tent poles are usually stronger than fiberglass poles. High-tech poles of such materials as Kevlar or carbon fiber may someday supplant aluminum.

Features: Certain conveniences simplify wintertime tent living. These include multiple entrances (in case one entrance bears the brunt of the weather), a vestibule for cooking or storage, gear pockets inside the tent for organizing small items, and inside loops for hanging clothes or a lantern.

You can't pitch a tent without giving some thought first to selecting and preparing a site. Some tips:

Use the terrain to your advantage. Select a spot that is as near to flat as possible to make site preparation easier. Watch out for hazards such as crevasses, avalanche paths, and cornices. Observe the local wind patterns: a rock-hard or sculpted snow surface indicates frequent wind, while a loose powdery area indicates a zone where wind-transported snow is deposited. Keep in mind that although the powdery area may be protected from the direct wind, the tent may have to be cleared of snow frequently.

Compact a large-enough area for the tent and for movement around the tent to check tie lines or clear snow. Flatten and smooth the tent platform thoroughly to keep you from sliding toward one wall or the other during the night and to get rid of any uncomfortable lumps. This is especially important if you're staying for several nights, because the entire tent platform becomes rock hard with all features cast in ice after the first night. A ski does a great job of smoothing the tent platform.

Dig an entrance pit 1 foot or so deep once the tent is erected. The pit in front of the main tent door makes entering and leaving easier, as you can sit comfortably in the doorway and place your feet in the pit.

Build snow walls around the tent if the site is exposed to winds. The walls can be anywhere from about 3 to 6 feet high and will deflect some of the wind away from the tent (fig. 15-3). Keep the walls as far away from the tent as they are high (a 3-foot wall, for example, should be 3 feet away from the tent), because wind will deposit snow on the leeward side of the walls and fill this area quickly. Blocks cut by a snow saw make the easiest, quickest walls, though you can also just shovel snow into a pile to serve as a wall.

A number of special items are useful in winter camping. Each tent should have a snow brush—a small broom with synthetic bristles to sweep snow from boots, packs, clothing, and the tent. Each tent also needs a sponge for cleaning up cooking or drinking-cup spills and removing condensation from the inside tent walls. A cheery addition to a tent, especially during the long nights near the winter solstice, is a candle lantern. You might even consider a gas lantern, which can repay its price in weight and bother by bringing tremendous brightening and warming to a tent.

For anchoring a tent, you can use wide-profile stakes, mini snow flukes, or regular snow anchors.



Fig. 15–3. Typical winter camp: kitchen area, snow walls, and well-placed tent.

Skis, ski poles, ice axes, and such also work well. Of course, whatever you use to hold down the tent won't be available for other uses. Tie the tent to a tree if there is one nearby.

To help make your winter tent-bound hours more pleasant, you need some house rules. They will depend on the weather, the size of the tent, and the experience of the occupants. For example, a small tent may mean that packs stay outside. If the tent is large enough and packs are brought inside, they should be thoroughly brushed of snow first. House rules may dictate that boots be taken off outside, brushed of snow, and placed in a waterproof boot bag inside the tent. Boots can bring in snow, and they also can cut or tear holes in the tent floor. Use stuff sacks or a large personal tent sack to help you organize and protect personal gear and keep it out of the way of your tentmates. It often helps to have one person enter the tent first to lay sleeping pads and organize gear before others enter.

During a storm, you'll face the necessary chore of keeping snow cleared away from the tent. In most storms, it isn't the snow falling from the sky that creates the problem, but rather the snow carried by the wind. Nature desires a smooth snow surface with minimal obstructions to impede the wind. When the wind encounters an obstruction, such as your tent or snow wall, wind-transported snow will be deposited in a way that minimizes its impact on the wind. Snow is deposited on the leeward side of tents and snow walls, and the tent begins to be buried. Even a partially buried tent poses the risk of asphyxiation, especially if you are cooking in the tent. Clear the snow regularly from around the tent. (Avoid cutting the tent with the shovel. Nylon cuts easily when it is tensioned by a snow load.)

In a severe or prolonged storm, your tent may begin to disappear into the hole created by neighboring snowdrifts. You may need to move the tent up on top of the new snow surface.

Stoves

As with winter tents, a stove suitable for winter must be tougher and more capable than a stove relegated to summer use. In addition to heating food, it is used to melt pots full of snow, providing your only reliable source of water. The stove must have a high heat output in order to melt snow quickly, stability so that it supports a full pot of snow, and relative ease of repairing when this becomes necessary. It also must operate well at low temperatures (which pretty much rules out self-pressurizing white gas stoves, which do not have a pump).

The most popular stove fuels are white gas, kerosene, or pressurized butane cartridges (see Chapter 3 for more details on stoves and fuels). White gas or its close equivalents, such as Coleman fuel or Chevron Blazo, are readily available in the United States, while kerosene is usually more common in other countries. Both fuels are inexpensive and efficient. Kerosene's lower volatility is both a virtue and a drawback. It necessitates priming your stove with something more volatile, such as alcohol or stove preheating paste. On the other hand, it lessens the chance of stove flare-up, a serious hazard if you're cooking in the tent.

A multifuel stove is useful for foreign travel, letting you burn such fuels as Stoddard solvent, stove oil, and alcohol when white gas or kerosene aren't available. Follow the manufacturer's instructions for using the selected fuel, as it may require changing fuel jets or burner heads.

Stoves that use pressurized gas cartridges are easy to use—just turn the valve and light—and there is less chance of a fuel flare-up. But these cartridges react to the lower temperatures of winter by putting out less heat, because the butane then does not vaporize as well. You can help out by prewarming the cartridge next to your body. Newer models burn a mixture of butane and propane, or isomers of butane, and do somewhat better at low temperatures. The problem is not as bad at greater altitudes, where lower atmospheric pressures mean higher relative pressure inside the cartridge to help vaporize the fuel. The disposable gas cartridges are expensive and heavy, and spent cartridges must be packed out. Another disadvantage of some cartridge stoves is poor stability because of a high stance and relatively narrow base. A cook set that suspends the stove and pot combination from the tent ceiling can solve this problem.

The snow that you melt for drinking water should come from a "drinking snow" pit, well away from the designated toilet and cleaning areas. Be sure everyone understands where it is and what it is for. Collect the snow as small pot-size chunks rather than as loose snow in order to make stoking the melting pot simpler and neater. If you are cooking in the tent, the process also is easier and cleaner if you collect the snow in a sack and then just bring the sack into the tent.

Cooking in the tent

Cooking in the tent is risky; it's also a convenience and at times a necessity. The risks go from the relatively minor ones of spilling pots onto sleeping bags or increasing condensation inside the tent, to the deadly dangers of tent fires or carbon monoxide poisoning. Nevertheless, cooking inside may be required if it's so windy the stove will not operate outside, or if it's so cold the cook risks frostbite. A tent vestibule is a big advantage because it provides the protection of cooking inside, with fewer risks.

Inside or out, your stove must be set on a stable platform to insulate the tent floor or snow from the heat of the stove, and to keep it from tipping over. A fallen stove is more than a nuisance, as it may spill fuel over gear or even set a tent on fire. Also, some stoves work significantly better if the fuel is insulated from the snow. A piece of $1/4$-inch plywood is a good stove pad. A snow shovel or snow fluke also may be pressed into service as a platform.

Here are some additional tips on inside cooking:

- Light the stove outside (or near an opening so it can be tossed outside if it flares) and bring it inside only after it is running smoothly.
- Cook near the tent door or in the tent vestibule. This puts the stove near the best ventilation and lets you throw the stove outside quickly in an emergency.
- Provide plenty of ventilation. This is critical. Carbon monoxide is colorless and odorless, so you

can't detect it. It is better to err on the conservative side by cooling off the tent with too large a ventilation hole rather than risk carbon monoxide poisoning with too small an opening.

Sleeping bags

A comfortable sleeping system is critical for winter trips, when the climber may spend the greater part of each day in the sack. It's colder than summer, so you need more insulation. This can come from a heavier sleeping bag or an overbag with additional insulation. An overbag must be large enough that it does not restrict the loft of the insulation in the inner bag. A non-insulating overbag, such as a bivouac sack, provides some extra warmth and protects the main bag from spills, condensation, and snow. If you don't use any kind of overbag, it may be helpful to have a sleeping bag with a cover made of material such as Gore-Tex to help keep the bag dry and windproof.

The type of insulation you want in your sleeping bag can depend on how wet the climate is. In the mild damp cold of coastal areas, synthetic bags work well as they absorb little or no moisture. As the temperature drops, there is less moisture in the air and the high loft of down clearly excels.

A vapor-barrier liner inside the sleeping bag adds to the sleeping system's warmth, especially in cold, dry environments. As with vapor-barrier clothing, the liner adds warmth by halting evaporative heat loss from your body. Less evaporation means less water vapor condensing on the sleeping bag and, therefore, a drier bag. The liner reduces your perspiration during the night and the subsequent necessary drinking the next morning to replace the lost fluid. The liner may feel clammy next to your skin so wear a single layer of synthetic underwear, which retains very little moisture and dries quickly in the morning. As an alternative to the liner, you can wear a vapor-barrier suit (shirt and bottom). The suit provides advantages similar to the liner, but it can also be worn when you're not in the sleeping bag.

An insulated pad is a critical component of the sleeping system, as the snow is virtually an infinite heat sink held at a constant 32 degrees. Inflatable foam pads such as the Therm-a-Rest are an excellent choice. You can add a closed-cell foam pad beneath the inflatable pad for added comfort, warmth, and reliability. Two foam pads or an extra-thick foam pad are good but somewhat bulky. (Take a look at Chapter 3 for additional general information on sleeping systems.)

WINTER CLIMBING

Winter makes just about every route harder to climb than in the summer. The first winter outing is usually a humbling experience in comparison to summer expectations. The days are shorter, travel is slower, and routine tasks take more time. Allow for the short days: scale down your goals, get under way at first light, and carry a good head lamp.

You will need skis or snowshoes for support, except during the low snow of early season or the firm snow of late season. Whether you choose skis or snowshoes depends on your ability and the route. Are you a diehard skier who loves skis even if conditions are poor? Are you good enough to ski virtually any slope? Will you be moving along a broad ridge or logging road, which is good terrain for skis, or will you be traveling through forest and brush? Is the approach long but easy, where the speed of skis is a benefit? Will you encounter technical climbing, where skis would be more cumbersome to carry than compact snowshoes? Consult specialized texts on skiing or snowshoeing for details on equipment and techniques.

For additional information applicable to mountaineering in snow, see Chapters 4, 12, and 14.

Routefinding

Winter routefinding gets challenging when bad weather hides the destination or landmarks along the way. Study the map ahead of time and become familiar with the terrain you will cross. Note broad features such as ridges, ravines, streams, and changes in steepness of the slope so that when you encounter them, you'll have an idea where you are. An altimeter is a vital companion to a compass for routefinding. If you cross an obvious ravine, for example, an altimeter should be able to pinpoint your position in the ravine by giving you an elevation to check on the map.

When the visibility is good, route features often stand out more clearly than in the summer. Ledges and couloirs hold snow and show up sharply against dark surrounding rock features. Ridges or arêtes blown free of snow stand out against the white of a snow face.

Avalanche hazard often dictates changes in the usual summer route, which may lead through an active avalanche path. Heavy snowfall, warm temperatures, or wind can increase the hazard of slab and loose-snow avalanches. Ridges are safer from avalanche than gullies and broad open slopes; windward slopes are safer than leeward. Never underestimate the danger of avalanche.

Wands are a big help in finding the return route during winter's poor weather and limited visibility, and when wind-driven snow covers your tracks. (For more details on routefinding on snow, see Chapter 12.)

Climbing mixed terrain

If your winter goal is normally a summer rock climb, be prepared to climb in crampons. Although considerable rock may be showing, the surface could be slick with a thin veneer of snow or ice. Even more than in the summer, climb deliberately. Search for small holds or level spots on which the crampon points can rest. This mixed climbing rapidly dulls crampon points, but they should be able to withstand the abuse. Consider carrying a small file to sharpen points if difficult ice climbing is required after the mixed terrain.

An ice tool (axe or hammer) is useful even on a rock route. The tool can be placed in occasional ice or snow pockets and can even be hooked over the edge of rock holds. When it is not needed, holster the tool on your harness (be sure the tool is secured, perhaps by its own leash) or sling it between your back and the pack.

Protection for mixed terrain

Previous chapters have detailed the types of protection used on rock, snow, and ice. Mix them all together, however, for winter climbing and there are some additional considerations.

Given a choice between a rock anchor and a snow anchor, the rock anchor is usually the one to use. It's relatively easy to check the soundness of rock anchors; not so with most snow or ice anchors. Even a good anchor in snow or ice has less strength than one well-placed in rock.

You may have to do a good bit of digging and grooming to clear away snow and ice in order to place a piece of protection in the rock. Your hands can knock off powdery snow, but it will probably take an ice axe to clear hard snow or ice. If a crack is filled with ice, a piton may be the only possible method of protection. But keep in mind that a piton scar made in winter is just as damaging as one made in summer. Always use the least damaging yet secure anchor.

Ice screws and pickets used for protection in mixed terrain sometimes go in only partway because the snow or ice is shallow. In this situation, tie off to the protection at the surface of the snow or ice to minimize the danger that the protection will be levered out (fig. 15-4). Don't try to force an ice screw farther in than it can go, because this useless effort could shatter the ice.



Fig. 15–4. Ice screw placement in thin ice over rock

Deep snow

The conventional wisdom is that loose snow will not stay long on a steep surface. But occasionally you encounter circumstances that seem to defy the rules, such as a short slope with snow well-anchored by boulders or by a wind-sculpted snow trough. Normal step-kicking won't work because the snow is too loose, nor is delicate footwork the answer. You must use your whole body to flail your way up the slope. An ice axe placed horizontally may be the only handhold, and you move upward on your knees rather than your feet. Rarely is the effort graceful.

At times, it takes a snow shovel to literally dig a path through the snow. Alternatively, teammates may pool their energies and toss the smallest member ahead in order to consolidate the path.

EXPEDITION CLIMBING

Expedition climbing does not represent a different type or standard of climbing as much as an expansion of the time scale for a climb. A weekend trip may involve several hours or a day for the approach to the peak, while an expedition can require two or three days of air travel followed by a day or two of land travel, followed by a ten-day hike into base camp. A rest break is not a 10- or 15-minute sit down, but may be an entire day spent lounging. The actual climbing is much the same as discussed in earlier chapters and in the winter climbing section of this chapter. The main differences between expedition climbing and other mountaineering come in the logistics of tackling a remote peak, the more severe weather likely to be encountered, and the challenge of climbing at high altitude.

The scope of this chapter is expeditions of three to four weeks, on relatively accessible 20,000- to 23,000-foot peaks, such as Alaska's Mount McKinley or Peru's Huascaran. Many of the techniques and considerations are similar to those of longer expeditions to higher peaks. However, there also are major differences in permits, hiring of porters, medical requirements, extremes of altitude and cold, use of oxygen, and so forth, that are beyond the scope of this chapter.

PLANNING AND PREPARATION

In deciding what peak to try and which route to climb, you will take a lot of factors into account:

Difficulty of the route: It's generally best to choose a route well within your climbing ability because the challenges of remoteness, changeable weather, and routefinding will add to the difficulties. Until you have gone on a few expeditions, think of the trip as an opportunity to apply well-practiced climbing skills in a new environment, rather than to push the limits of your ability.

Duration of the climb: Again, be realistic. Don't try to cram a twenty-five-day route into two weeks of annual leave.

Time of year: Study information on seasonal temperatures, winds, storms, rains, and amount of daylight. Your trip will be planned far in advance, so in choosing your dates you'll have to deal with probabilities and likelihoods, and hope that the realities will measure up when the time comes.

Costs: Major costs are equipment for the climb, transportation, and other expenses on the way to the peak, and hiring porters and pack animals to haul gear to base camp. In many cases, expenses within a country are minor compared with the cost of getting there. Estimate your costs based on research about the peak and/or area.

Location: Where to go? Alaska, Mexico, the Andes of South America, Europe, Nepal, Pakistan, India, the Soviet Union, and areas of Africa all boast difficult, remote peaks. The experience of traveling in a remote or foreign land is often one of the most enjoyable and rewarding aspects of an expedition.

After choosing your peak, research the mountain and its routes. Talk to climbers who have been there, look for write-ups in the journals of the American Alpine Club and of climbing organizations in Canada and Europe, and seek out guidebooks and stories in climbing magazines. Get all possible details on logistics, potential problems, where to buy fuel, what foods are available, objective hazards on the mountain, and so forth.

Have a backup route in mind in case the main objective is scratched because of avalanche hazard, bad weather, inability of some party members to continue, or any other reason. If you've chosen a highly technical route up your mountain, consider acclimating by climbing the standard route first, then taking on the tougher challenge.

Find out what permits and approvals are necessary. It helps to have typewritten itineraries, climbing resumes of party members, equipment lists, and medical information in hand ahead of time and while traveling to the peak. The appearance of good organization impresses bureaucrats the world around.

Choosing the team

Choosing a compatible team is the first step toward an enjoyable experience. Expedition climbing is full of stress, and climbers can be taxed to their physical and mental limits. Climbing literature abounds with "climb and tell" accounts of expeditions in which, it seems, team members despised their fellow climbers; you don't want your expedition to end up being another.

The skill of your team must, of course, be equal to the demands of the climb. Climbing with people of similar technical ability may improve compatibility. Team members need personalities that are compatible with each other, and must be able to live harmoniously with others in close quarters under stressful conditions. The climbers should agree on the philosophy of the trip in terms of climbing style, environmental impact, and degree of acceptable risk.

It's important to agree on leadership before the trip gets under way. If all climbers are of roughly equal experience, democratic decision-making usually works well. If one climber is clearly more experienced, that person can be given the leadership role. Even with a single leader, functional areas such as finance, food, medicine, and equipment should be delegated to others to lessen the leader's load and to keep everyone involved and informed. This also helps build expedition leaders for the future. (You might consider taking a guided climb if this is your first expedition or if you lack capable partners.)

The number of climbers in the expedition depends partly on what route you've chosen. A party of two or four climbers may be best on technically difficult routes because of the efficiency of two-person rope teams and the limited space at bivouac sites. However, climbing with a very small team means that if one person becomes ill or cannot continue, the entire team may have to abandon the climb.

When the route itself does not determine the optimum party size, logistics becomes the deciding factor. As the number of climbers increases, issues of transportation, food, lodging, and equipment become more complicated. The advantage is that parties of six or eight have strength and reserve capacity. If one climber doesn't continue, the rest of the party has a better chance to go on with the expedition. And larger parties usually are better able to carry out self-rescue than smaller teams. However, the logistics of an expedition with more than eight members can become more burdensome than many climbers are willing to accept.

Establishing a climbing style

Do you plan to climb "expedition style" or "alpine style" or somewhere in between? There's a big difference, and it's a question you need to resolve early, based on the route, the size and strength of your party, and the preference of the climbers.

Traditional expedition climbing style involves multiple carries between camps, during which food, fuel, and supplies are ferried to higher camps. Technically difficult sections of the route are often protected with fixed lines—ropes anchored in place to minimize danger during repeated trips up and down. It's a slow and measured campaign for the summit.

Alpine climbing style usually means moving camps up the mountain in a continuous push, so that the route is climbed only once. All equipment and supplies are carried with the team at all times.

It's a light, quick bid for the top.

Expedition-style ascents take longer because more time is spent hauling loads between camps. They are heavier because more food, fuel, and perhaps fixed line must be carried, and more costly because of the greater time, equipment, and food. Alpine-style trips tend to be riskier as there is less margin of safety in case of bad weather or injury.

The climbing itinerary

Once you've researched your mountain, you can set up an itinerary that makes a good estimate of the number of days to allow for the approach to the peak, for carrying loads up the mountain, for climbing, for sitting out storms and for resting. An average elevation gain of 1,000 feet per day is good for acclimatization, and this figure should be correlated where possible with good campsites. Rest days built into the schedule provide time for mental and physical recuperation, equipment sorting, and such. They can also serve as a time buffer for unplanned delays caused by storms, illness, or other problems. If a storm hits, try to reschedule a rest period for the same time, making the best of a bad day.

For moving camps expedition-style up the mountain, double carries are generally adequate on a three-week climb. The first carry hauls food, supplies and equipment to the site of the next camp. The second carry involves tearing down the current camp and resetting it at the next site. On bigger mountains, camps may need to be stocked pyramid style, with many carries between camps early in the trip and few if any carries between later camps.

When repeated carries are necessary, each load is usually cached at the next camp while the climbers go back down for more. Plan to set up a protected cache to avoid damage from the elements and from animals. Dig a hole, cover it with something an animal can't get through, such as a sled or snowshoes, and pile snow on top. Mark the cache with long wands. But beware. Ravens on popular peaks have learned to identify caches, so place the wands a little distance away and smooth the surface above the cache.

Food and equipment

On expeditions to the remote mountains of the world, you either take it with you or you do without it. Having the necessary equipment, in working order, is much more critical than on a weekend climb where home is a short drive away. Your expedition needs a complete equipment list, both group and personal, worked out in discussions with all team members. (See the sample equipment list at the end of this chapter.)

Supplies for the group

- Food

Food constitutes the heaviest single category of weight carried by an expedition. But who's complaining? Food provides the necessary fuel for your body to carry loads and climb the route, and it also can serve as one of the great pleasures of the trip.

Every climber has preferences in food, so conduct a team survey of strong food likes and dislikes before planning menus. Combat the danger of carrying unpopular foods by providing lots of variety. If some team members don't like one item, there should be several others they will find tasty, or at least palatable. A condiment and seasoning kit with the likes of Tabasco sauce, spices, soy sauce, margarine, and mustard will add interest to bland packaged foods and perhaps salvage the unpopular foods.

Although fats have the highest caloric density (9 calories per gram), carbohydrates (4.1 calories per gram) are easiest to digest and provide the quickest energy. Proteins have about the same caloric density as carbohydrates, but are not as easy to digest and are usually accompanied by substantially more fat. A reasonable expeditionary diet has about 50 percent of its calories from carbohydrates, 30 percent from fat, and 20 percent from protein.

Plan to provide about 35 ounces (roughly 2$^1/_4$ pounds) of food per person per day. With no waste, 35 ounces would provide more than 5,000 calories. In reality—because of packaging, nonnutritive fiber, and the food's irreducible water—the food will provide only about 3,900 calories per day. Experience will tell whether this is just right, too much, or not enough. Too much food means extra-heavy loads between camps and possibly a slower trip. Too little means you will begin losing weight. On a trip of three or four weeks, weight loss shouldn't cause a problem. But on longer expeditions, too much weight loss may effect the team's strength and endurance.

Food is your major controllable weight factor. As you sit at home planning menus and calculating energy expenditures, you'll be tempted to throw into the menu an extra cracker at breakfast, an extra candy bar during the day, or an extra cocoa at dinner. Resist this temptation at all cost. Unless the extra food never gets past base camp, it will eventually find its way onto the climbers' backs or into their sleds, slowing their pace while fatiguing them faster. If you are planning a twenty-day trip, take food for twenty days, not twenty-one. On unplanned storm days, you will simply have to stretch your rations. Food can always be stretched on an expedition, and it's easier than suffering the consequences of overloaded packs.

You can plan foods for early in the trip that are different from those for later as you get up on the mountain. Candidates for lower elevations and warmer climes are foods that are time-consuming to prepare, such as pancakes; items that suffer from freezing, such as cheese and peanut butter; and canned foods. Foods carried to higher altitudes should be very light and require a minimum of preparation, such as freeze-dried items, instant noodles, instant rice, and potatoes. Try to eat local food on approach marches and at base camp so you don't tire too early of expedition food.

Packaging and organizing food is an important element of planning. Take the food you've bought for the expedition and get rid of as much of the commercial packaging as possible. Repackage the food to minimize this packaging, reducing the weight you have to carry in and the garbage to be carried out. Keep the preparation instructions from the packaging material. You should prepackage rations into person-days (put in one bag the food for one person for one day), or into group-days (put in one bag the food for the entire group for one day), or into tent-days (put in one bag the food for one tent for one day). However you do it, measure the food into the correct portions and label it. Clear plastic sacks help organize the food while keeping the contents visible.

Adequate hydration is the first line of defense against altitude sickness. Bring lots of soups, hot drinks, and cold-drink mixes to help motivate you into drinking the necessary fluids. Contaminated water plagues nearly every part of the world. The expedition kitchen must be able to furnish adequate water for everyone through chemical decontamination, filtering, or boiling.

• Fuel

Fuel cannot be carried on airlines so it must be available at your destination. Multifuel stoves may be good insurance in foreign countries where white gas is not readily available. Even with a multifuel stove, check the fuel's compatibility with the stove before heading into the mountains. If you're using kerosene or a similar low-volatility fuel, be sure to buy alcohol or gas for priming the stove. The cleanliness of fuel in foreign countries is always questionable. Bring a filter and filter all fuel before using, and clean the stove often. Plan on using between $^1/_4$ pint and $^1/_2$ pint of fuel per person per day, depending on how much water must be boiled for purification or melted from snow.

Fuel containers are usually supplied in Alaska or Canada, but you must provide your own elsewhere. Aluminum containers as small as 1 liter are fine if you don't need to carry much fuel. For larger quantities, bring 1-gallon gas cans or sturdy approved plastic fuel containers. They should be new, as airlines object to containers with residual fuel vapors. Plastic bottles sold in foreign countries have a reputation for leaking.

• Community equipment

For communal cooking, take pots large enough for the group meal courses and for melting large amounts of snow. Filling water bottles is a common activity, so pots must be easy to pour from (a 2-quart coffee pot works well). Bring at least one cook pot per stove. Bring a metal gripper to use on pots that lack handles or bails, or use wool gloves as potholders. (Be careful using synthetic gloves, which will melt if they get too hot.)

To save a bit of weight, the party can carry an altimeter and a compass as pieces of group equipment rather than having each climber carry separate ones. Also among group equipment are wands, used for marking routes, camp perimeters, gear caches, and snow shelters. Carry long wands if there's a chance of significant snowfall. Tents are also community equipment. See the section on winter camping earlier in this chapter for guidelines on tents.

The party may carry radios to get weather information, call for emergency help, or communicate between climbers at different locations. The main choices are citizens' band, marine band, or FM. You'll have to do some investigating to determine both the technical feasibility and the legality of their use.

- **Community climbing gear**

The route determines the climbing gear you need. A route that involves only glacier travel may require just the basics: rope, crampons, and ice axe. Technical routes can take the whole gamut of equipment, from ice screws, snow flukes, and pickets to nuts and pitons.

Depending on the style and organization of the trip, climbing gear can be personal or community. On a technical route where climbers operate in self-sufficient pairs, climbing gear should be personal or left to each rope team to work out. In other cases, virtually all climbing gear—carabiners, runners, screws, and so forth—can be treated as group equipment. The choice is up to the team. Certain pieces of climbing gear, such as crampons and ice axes, are indispensable, and a large party may want to carry spares as insurance against equipment failure or loss.

The decision on what ropes to take also depends on the route and its difficulty. For technical pitches, you'll use use either a single rope (10.5 or 11 millimeters in diameter) or double or twin ropes (each 8 or 9 millimeters). On a glacier route, a single 9-millimeter rope may be adequate. Keep in mind, however, that an expedition puts extraordinary wear and tear on the rope because of its daily use in bright sunlight. The team also needs to decide how much rope to bring for fixed line along the route. Fixed line is usually a polypropylene braided rope or a nylon kernmantle rope. Polypro is lightest and cheapest, but kernmantle is better for areas of high use.

- **Repair kit**

Equipment failure is common under the prolonged and rugged demands of an expedition, so count on needing to repair or substitute for failed gear. Put together a comprehensive repair kit, keeping in mind the relative importance of each piece of equipment to the progress of the group.

Among the repair-kit items should be:

- Tape. Gray duct tape seems to be the universal repair favorite, but other tapes, such as ripstop fabric tape or filament tape, are useful.
- Sewing kit for permanent repairs or those beyond the capability of tape.
- Extra stove parts and the tools to disassemble the stove.
- Tent-pole splices or extra tent poles. While the tent body or fly can be patched with tape, broken tent poles must be repaired or replaced.
- Extra crampon parts, such as screws, nuts, and connecting bars, and the necessary tools.
- Patch kit for inflatable foam pads that spring leaks.
- Also: crampon file, pliers, wire, accessory cord, pack buckle.

- **First-aid kit**

An expedition usually carries a comprehensive first-aid kit, which is assembled after everyone in the party has had input into the selections. Keep in mind the isolation of the peak, the specific medical conditions of team members, and their medical knowledge. Discuss your group's medical needs with a doctor who is familiar with mountaineering.

The first-aid kit may include such specialized or prescription items as a strong painkiller, antibiotics, a dental repair kit, and a suture kit. Be sure to carry a first-aid manual.

Personal gear

Expedition climbers need clothing and sleeping bags that can stand up to prolonged use under severe conditions. The clothing and equipment suitable for winter climbing, outlined earlier in this chapter, works well for expeditions. The desired comfort rating for your sleeping system varies with the climate and season, but a good general rating for expeditions is about –30 degrees Fahrenheit (about –35 degrees Celsius).

Every person on an expedition team needs a big pack, with a capacity between 5,500 and 7,000 cubic inches, because there are times you will be called on to carry ''impossible'' loads. The pack also must be comfortable while you are wearing a climbing harness.

You may want mechanical ascenders, rather than prusik slings, both for crevasse rescue and for protection while climbing with a fixed line. The ascenders permit one-way movement by gripping or squeezing the line when your weight is on them but letting you move move them when they are unweighted. The ascenders, under such brand names as Jumar, Clog, and Gibbs, are necessary to handle the large, heavy expedition loads involved in any crevasse rescue. On fixed line, the prusik knots are unsafe because of the time required to unfasten and reattach them past each anchor you encounter on the way up or down.

Although two ascenders are the norm, one plus a prusik sling can work if you need to cut down on weight. Regardless of the choice, make sure the system can be operated while you're wearing bulky gloves or mittens.

Other items of personal gear to consider:

- Prescription glasses. Carry an extra set of prescription sunglasses.
- Journal. An expedition can make you introspective. A journal made of waterproof paper (look under surveyor supplies at a book store or stationery supply store) and some pencils can help pass the time.
- Books. You can catch up on reading while waiting for flights, or during rest days and storm days in the field. Coordinate your selection of books with other team members to avoid repetition and provide variety.
- Personal hygiene. On cold-weather trips where water is at a premium, chemical wash/wipes can provide a refreshing sponge bath.
- Pee bottle. During storms and cold nights, the pee bottle eliminates those unpleasant traipses to the latrine. Be sure the bottle has a secure top.

Physical and mental conditioning

Training for an expedition involves both physical and mental preparation. For the body, emphasize cardiovascular training and strength training equally. Cardiovascular conditioning is important for physical activity at high altitudes. Powerful leg muscles are needed to walk heavy loads up the mountain, and upper-body strength is needed to hoist and carry the large expeditionary packs.

Climbing itself is the best training. Climb often and in all weather conditions, carrying a heavy pack. If you can go on a typical two- to three-day climb packing gear for camping and climbing, gaining 3,000 to 5,000 feet per day, and feel you still have plenty of physical reserves, you're probably sufficiently fit for an expedition. An expedition climber needs the endurance to carry packs of 40 to 60 pounds (sometimes in addition to pulling a sled) for an elevation gain of 2,000 to 3,000 feet every day, day after day.

Your mind and spirit also need to get into shape for the rigors of an expedition. Learn about the special challenges of expedition travel and prepare yourself to accept them. Otherwise, you can be overwhelmed by the size and remoteness of the climbing area or lose your good spirits during a long storm or a bout with the flu.

Success on an expedition often goes to the person who has a greater desire or will to succeed, even though he or she may be physically weaker than another climber. It takes more than physical strength to deal with extreme cold, sickness, cramped quarters, poor food, conflict with teammates, the stress of technical climbing, and the lethargy brought on by high altitude.

You can work on both your physical and mental conditioning by seeking out experiences that come as close as possible to what you expect on the expedition. Prepare for the expedition by going on winter climbs and on longer trips. You may not be able to alter such objective conditions as cold or illness, but you can learn to exercise a great deal of mental control over your response and attitude toward them.

Before you leave home

Food and gear must be packed and frequently repacked to accommodate the various transportation modes used to get to the mountain. Become familiar with the requirements that face your expedition, such as airline regulations on bag sizes and weights, or muleteer requirements on load balancing. Keep lists of what went into each bag so any item can be retrieved readily. Before leaving home, plan travel arrangements for each leg of the journey and make reservations where possible. Try to work with a travel agent who has booked trips to the region before.

Be as healthy as possible when you leave town because, in all likelihood, you won't get better while traveling. For foreign travel, find out well in advance what inoculations are needed. Have a dental exam and leave no dental care pending. To stay healthy once you get to your destination, plan on purifying all water and be cautious about eating unpeeled fresh vegetables or fruit, dairy products, and uncooked food. And through all the complicated hurry and scurry of getting ready for a big expedition, try to remember that your goal is to get away from it all and climb a mountain.

EXPEDITIONARY CLIMBING TECHNIQUES

Expedition mountaineering calls for the rock, snow, ice, and winter climbing techniques that have been covered throughout this book. An expedition can add a couple of new techniques to your climbing repertoire: hauling sleds and using fixed lines.

Haul sleds

Expedition members often pull sleds or haul bags behind them on long glacier approaches as a way to move the loads of gear and supplies (fig. 15-5). A climber can transport a normal load in a backpack in addition to pulling a sled with another pack's worth of gear. Commercial haul sleds are available, with zippered covers to hold the load, a waist harness for you to wear, and rigid aluminum poles connecting the sled to the harness. These



Fig. 15–5. Sled and climber rigged for glacier travel

poles help control the sled when traversing or going downhill.

A cheaper but usable alternative is a plastic children's sled, with holes punched in the sides as rope attachment points. Load your gear into a duffel bag and tie it to the sled. Perlon (5 to 7 millimeters) is used to pull the sled, and most climbers prefer to attach the perlon to their pack, not their climbing harness. A final alternative is to drag a haul bag, constructed of durable, slick material to help it slide over the snow. A swivel connecter attaching the haul line to the haul bag will keep the rolling of the bag from putting twists in the line.

As the route steepens, the amount of weight you can pull in a sled decreases, and it can't be used at all on steep technical climbing terrain. Haul bags may then be what you need. (See Chapter 11 for techniques for using haul bags on technical routes.)

No special trick is involved in towing a sled behind you. It simply takes steadfast pulling. Where it can get complicated is during roped travel on glaciers, where any fall into a crevasse is made more treacherous by having the sled plunge down behind you. Even if you aren't injured by the plummeting sled, rescue is more difficult with the need to deal with you, your pack (perhaps weighing 60 pounds) and the sled (carrying another 50 pounds or so).

You can minimize the danger of getting hit by the sled during a crevasse fall with a simple preventive technique. Just take your climbing rope where it runs past the sled and tie it snugly with a clove hitch to a carabiner at the rear of the sled. In a crevasse fall, you will drop in, followed by the sled. But the sled will be stopped above you by the tie-in to the climbing rope. If you are using a hauling tether to the sled (instead of rigid aluminum poles), be sure the tether is long enough so you are well beyond the reach of the sled as it hangs from the climbing rope. This technique depends on having a team member behind you on the rope to arrest the fall of both you and the sled, so it won't work for the last climber on a rope. The last person either assumes the extra risk, or the team can decide to haul only two sleds for each three climbers.

Crevasse rescue

It takes some special procedures for crevasse rescue if you are hauling a sled (fig. 15-6), beyond those methods spelled out in Chapter 13. Imagine you have just fallen into a crevasse. The sled, attached to the climbing rope, dangles above you. Here is how you can help yourself get out.

First of all, get your weight onto the climbing rope. As you dangle in the crevasse, your weight may be on the sled haul line (or towing poles, if you are using a commercial sled). Transfer your weight to the climbing rope by standing in slings attached to your ascending system (mechanical ascenders, prusik slings, or a combination).

Then disconnect the attachment from you to the sled. If you are using a haul line attached to your pack, simply take off the pack and let it hang from the line.

Once free of the sled, you can try to rescue yourself or wait for your climbing mates to get you out. If you start up the climbing rope on your own, the sled probably will cause some complication. You may need to ascend around the climbing-rope knot that holds the sled. In this case, remove and reattach your ascenders above the knot, one at a time.

You may also need to untie from the climbing rope in order to move past the sled and reach the lip of the crevasse. To make it easier to disconnect from the climbing rope, many sled-pullers travel with the rope clipped to a locking carabiner on their harness, rather than tying directly to the harness itself. If you must unclip from the climbing rope, use extreme caution to ensure that the ascenders are secure.

Your fall into the crevasse can also mean extra effort for your teammates if they must pull you out. If you can't disconnect yourself from the sled or if there is no extra rescue rope available, they must haul both you and the sled at the same time. They will have to use a Z-pulley system to get the most mechanical advantage in pulling on the climbing rope. Far preferable is to use a spare rope to pull you out, and to then pull the sled out on the climbing rope it is already attached to.



Fig. 15–6. Crevasse self-rescue with sled

Fixed lines

A fixed line is simply a rope that is anchored to the route and left in place. It allows safe, quick travel up and down a difficult stretch. Climbers protect themselves by tying into a mechanical ascender on the fixed line, eliminating the need for time-consuming belays. If you fall while climbing next to the fixed line, the ascender cam locks onto the line and holds the fall.

It's also possible in some cases to climb a fixed line directly by hanging from slings attached to two ascenders and moving them methodically upward. However, fixed lines are not generally used for direct aid in the situations discussed in this chapter.

The fixed line simplifies the movement of people and equipment, especially when numerous trips are required, and permits less-experienced climbers to follow a route. Fixed lines have been common on large expeditions to major peaks to provide protection on long stretches of exposed climbing or to protect porters while they make carries from camp to camp in the face of such obstacles as icefalls, glaciers, and steep rock or ice. The lines make it possible for climbers and porters to carry heavier loads than they could safely carry without them.

Fixed lines are sometimes used as a siege tactic on difficult rock and ice faces, with climbers retreating down the lines each night to a base camp, then reascending the next day to push the route a little farther. They also come into play on continuous multiday aid climbs of big walls, where the second climber follows on the line, removing protection and hauling up equipment. The climbers do not retreat down this line, but move it upward as they go. Thus it becomes a "moving" fixed line, only one rope length long.

Some climbers argue that fixing ropes is an outmoded technique, no longer required to climb any mountain or route. This is not the majority view, but the technique should not be abused. Fixed lines should not be used to supplement the climbing ability of an expedition team. If many of the climbers don't have the ability to climb a route without help from a fixed line, find an alternate route. Fixed lines should not be added on popular routes or in regions where they are not normally used.

In the past, climbers often abandoned fixed lines when a climb was done. It was not uncommon to find several lines, one on top of the next, frozen into a route. This is no longer acceptable in a time of increasing environmental awareness, and each party needs to make a commitment to remove its fixed lines.

Equipment for fixed lines

To set up and use fixed lines, you need rope, anchors, and ascenders. Climbing ropes don't make good fixed lines because they are designed to stretch under a load, an undesirable characteristic in a fixed line. What you want is a more static rope, one with low elongation under load. Nylon is the most common material for fixed lines, though polypropylene and Dacron also are used. Kernmantle construction is best, though braided ropes can be used.

The diameter of fixed lines usually varies between 7 and 10 millimeters, with the size depending on the terrain and the amount of use the line is expected to get. Try to carry your fixed line in long lengths. The ropes are usually manufactured in lengths of somewhere between 300 and 1,000 feet, depending on rope diameter.

To anchor the fixed line to the mountain, employ any attachment points that are normally used in belaying and climbing on rock or ice: pitons, chocks, natural outcrops, ice screws, pickets, and snow flukes or other deadman anchors.

A mechanical ascender attached from your harness to the fixed line is the most efficient means of protecting you from a fall as you climb next to the line. Prusik knots can be dangerous because it is so time-consuming to untie and retie them as you move past an anchor, especially while wearing mittens. Prusiks are OK in an emergency or on very short sections of rope.

Anchors for fixed lines

Every fixed line needs an anchor at the bottom to hold the rope in place while climbers ascend, and a bombproof anchor at the top. Mark the location of the anchors with wands so you can find them after a snow storm.

Place a series of intermediate anchors between the bottom and top of the fixed line. The fixed line is tied off at each anchor so that every section of line is independent of the others. This permits more than one climber at a time on the line. In deciding where to place the intermediate anchors, take several considerations into account. Place an anchor at points where you would like to change direction of the line or prevent pendulum falls. An anchor at the top of difficult sections of the route is helpful. If possible, place the intermediate anchors at natural resting spots, making it easier to stand and move the ascenders past the anchor.

Always bury or cover snow and ice anchors and inspect them regularly for possible failure from creep or melting. Also keep a close eye on any rock anchors capable of creeping or loosening. Place anchors at locations that help keep the line from rubbing on rough or sharp surfaces, or pad the line at points of abrasion. Even small amounts of wear can multiply into dangerous weak spots on fixed lines, which usually use lightweight rope. Falls will also damage the line. After any fall on the line, inspect it for damage and check the anchors for any indications of possible failure.

How to set up fixed lines

There are many variations in how to set fixed line, each appropriate for certain conditions, climber preferences, types of line and so forth. The key is to think through a system prior to starting out and if possible test and refine it before you actually need it. Here are three possible methods:

1. The most common way is for two or three climbers to ascend the route—using a standard climbing rope to belay one another or to establish a running belay—and setting the fixed line as they climb. They can carry the whole spool of line with them and let it out as they ascend, tying it off at each intermediate anchor along the way. Or they can just pull the end of the line up with them as they ascend, clipping the line into each anchor with carabiners. Then after anchoring the top, they can go back down, tying off the line at each anchor as they go. In either case, it can be a big job. Carrying the spool of line is difficult, but so is pulling up on the end of the line and trying to overcome the tremendous friction that develops as it travels through carabiners and over the route.
2. The entire fixed line also can be set on descent. The material for the fixed line must first be carried to the top of the route, of course. Tie the line into a bombproof anchor at the top. Then rappel or downclimb to tie the line off at intermediate anchors. These anchors can be the ones that were placed on the earlier ascent of the route, although new ones can be added just for the fixed line.
3. You can also use the fixed line as your climbing rope at the same time you are setting it in place. Use the line just as you would a normal climbing rope, clipping it into anchors as you climb, belayed from below. At the top, tie the fixed line into a bombproof anchor, and then it is ready to be tied off at each intermediate anchor. The problem with this method is that fixed line is usually thinner and has less stretch than climbing ropes. If you fall, there's a bigger chance the line could break. Even if it holds, the limited stretch in the line would make for a hard fall. An additional drawback is that the friction on the line as you pull it up through more and more carabiners will probably limit the maximum length of the run. This method is best saved for short sections of fixed line or for instances where a standard climbing rope is being used as a fixed line.

Attaching fixed line to anchors

For the final tie-off of the fixed line at each intermediate anchor, use a clove hitch or figure-8 knot in the line. Tie a sling directly to the anchor and clip a figure-8 loop or clove hitch into a carabiner attached to that sling (fig. 15-7a). Or better yet, minimize use of carabiners and have one less link in the system by retying the sling directly through the figure-8 loop (fig. 15-7b).

Ascending

Ascending with a fixed line simply involves



Fig. 15–7. Intermediate, fixed anchors: a, anchor with carabiners in system; b, anchor without carabiners.

climbing as usual, except that your harness is attached by a sling to the mechanical ascender on the line in case you fall (fig. 15-8).

Start by tying a sling from the ascender to your seat harness where you normally tie in with the climbing rope. (A less desirable way is to clip the sling into a locking carabiner attached to the harness.) Make the sling short so the ascender won't be out of reach if you fall. If you're climbing a near-vertical section or have a heavy pack, you may want to pass the sling through your chest harness as well to prevent tipping upside down in a fall.

Then attach the ascender to the fixed line, following the specific directions for your brand of ascender. The ascender should be oriented so that a fall will cause it to clamp the rope. It should slide easily up the line, but lock tight when pulled down. Test it before starting upward and also check the fittings on your seat harness.

You should attach a carabiner from the ascender sling or a separate sling to the fixed line to serve as a safety link as you move upward. If you fall and the ascender fails, the safety carabiner will slide down the rope but stop at the next anchor below and arrest your fall.

At each intermediate anchor, you have to remove the ascender from the fixed line and reattach it beyond the knot. This is the most dangerous moment in fixed-line travel, particularly if conditions are severe and you are exhausted. Be sure the safety carabiner stays on the line while the ascender is detached. Some ascenders can be configured so the safety carabiner can be moved and reattached above the anchor first, followed by the ascender. This order offers more security than moving the ascender first. Another safety option is to briefly clip yourself into the anchor as you relocate the ascender.

Whatever your procedure, it's urgent that you think it through in advance and practice it on a good day so you can perform it reliably under the worst possible conditions.

More than one climber can use a fixed line at the same time as long as there is at least one anchor between each climber. Also be sure that a fall by



Fig. 15–8. Mechanical ascender attachment to fixed line: a, set up for normal movement; b, passing an anchor, move ascender separately from safety carabiner.

any climber would not cause rope movement, rockfall, or other activity that could endanger anyone else.

Descending

Climbing down with a fixed line is similar to climbing up. Again attach the ascender sling to your harness, then attach the ascender to the fixed line exactly the same as for ascending. Double-check that the ascender locks onto the rope when you pull down on it, and that it will be within reach if you end up hanging from it after a fall. Attach the safety carabiner.

Begin your descent. As you climb downward, you will be moving the ascender down the rope to stay with you. Use a light grip on the ascender release so that you can let go of it instantly to permit the ascender to grab the rope if you fall. It's natural to try to hang onto something if you lose your balance, but the last thing you want to grab hold of at that moment is the ascender release.

Take extreme care as you climb past anchors, removing and reattaching the ascender. As in climbing up, never detach the ascender and the safety carabiner at the same time. Again, you can temporarily clip into the anchor while you relocate the ascender. On steep sections of fixed line, rappelling the fixed line may be a good alternative to downclimbing.

Removing fixed lines

Exhausted mountaineers at the end of a grueling climb often find it easier to abandon gear, garbage, and fixed line to the mercies of the mountain. This kind of behavior has become less and less acceptable, and expeditions now are learning to approach their climbs with a commitment to removing all signs of their passage.

Removing fixed lines will be easier if you keep it in mind as you plan where to put them up in the first place. In some cases you may be able to use a "moving" fixed line, removing it and moving it higher as you ascend the mountain, then descending via a safer route. If you are leaving the mountain and going down a fixed route for the last time, plan a downclimbing or rappelling procedure, or a combination of the two, that will permit the party to remove the fixed line.

What applies to fixed line also applies to all the other odds and ends of the expedition. Everything that goes in has got to come back out. Crevasses can't be used as garbage dumps because between wind and hungry ravens, the contents can end up strewn up and down the glacier. You can set fire to burnable garbage, but haul the ashes out. For human waste, set up a group latrine at each camp. In an exception to the use of crevasses, you can line the latrine with plastic garbage bags and then dispose of the waste in a deep crevasse.

EXPEDITION WEATHER

You need to become something of an amateur weather forecaster on an expedition because your safety and success are so closely bound to nature's moods. When you get to the climbing area, add to your knowledge of local weather patterns by talking to other climbers and to people who live there. Find out the direction of the prevailing winds. Ask about rain and storms. On the mountain, become a student of weather patterns. Your altimeter can serve as a barometer to signal weather changes.

Take clues from the clouds. Cirrus clouds (mare's tails) warn of a front bringing precipitation within the next 24 hours. Lenticular clouds (cloud caps) mean high winds. A rapidly descending cloud cap signals that bad weather is coming. And if you climb into a cloud cap, expect high winds and poor visibility. Be prepared for the fact that big mountains typically have storms and winds to match. Wait storms out if you can because of the risk inherent in descending under bad conditions. If it looks like you'll be stuck for some time, start rationing food.

Fair weather poses problems too. If it's hot and solar radiation is intensified by protected glaciers, the result can be collapsing snow bridges, crevasse movement, and increased icefall. Then it's best to climb at night, when temperatures are lowest and snow and ice are most stable.

MEDICAL CONDITIONS RELATED TO HIGH ALTITUDE

Expedition climbing and a great deal of other mountaineering takes you to altitudes where your body no longer feels at home. Every climber is affected to one degree or other by the reduced oxygen of higher elevations. It often causes acute mountain sickness, and it can lead to the life-threatening conditions of high altitude pulmonary edema and high altitude cerebral edema. Frostbite is another danger, though it's not limited to high altitudes. It's important to learn how to prevent these conditions, and how to recognize and treat them when they occur. This chapter offers some general guidelines on these maladies, but consult your first-aid book, specialized texts, or physicians familiar with mountaineering for detailed information.

Altitude sickness (acute mountain sickness)

When you ascend rapidly to an altitude you're not accustomed to, your system works to adjust to the new conditions. Breathing becomes more rapid to extract enough oxygen from the thinner air, and the blood increases its proportion of oxygen-carrying red corpuscles. Climbing slowly and steadily upward, climbers routinely suffer uncomfortable symptoms from moving into this new environment. First comes a general malaise and loss of appetite, then headache, followed by increasing weakness and lessening of interest in the climb. If you continue on at that point, there's often increased apathy, nausea, dizziness, and sleepiness. A retreat to lower elevations usually brings about rapid improvement.

Symptoms of altitude sickness (mountain sickness) can occur at relatively low altitudes. Some people feel dizzy or tired or experience palpitations when riding in a car at 8,000 feet or so. Climbers generally have more time to acclimatize and, except for shortness of breath, usually feel only minor effects until after they reach 12,000 feet or more. In regions such as the Pacific Northwest, where climbers live at sea level yet ascend to over 14,000 feet for a weekend climb of Mount Rainier, altitude sickness of greater or lesser severity is the rule rather than the exception.

You can help moderate the more severe symptoms of altitude sickness by some relatively simple techniques. In ascending, use the rest step to give your leg muscles mini-rests all the way up the mountain and help you maintain measured, methodical breathing. Take occasional full rest stops with forced deep breathing. Drink lots of water and keep nourishment up by snacking often. Follow a program of careful acclimatization (outlined later in this chapter).

Medical experts and specialized texts can provide information on the current use of drugs in combatting altitude sickness. Two prescription drugs—Diamox and dexamethasone—are commonly used to aid in prevention and treatment of altitude sickness. They are not a substitute for proper acclimatization, or for immeditate descent if you get sick.

High-altitude pulmonary edema and cerebral edema

High-altitude pulmonary edema is the leakage of blood into the lungs, which restricts the air sacs (alveoli) in exchanging oxygen and carbon dioxide in the blood. Pulmonary edema rarely occurs in healthy people below 9,000 feet. The average elevation at which it strikes in the United States is 12,000 feet, and the level of onset varies for mountain ranges in other parts of the world.

Early symptoms of pulmonary edema are similar to those of pneumonia, although it is not precipitated by an infection and there is no fever. Within 12 to 36 hours after reaching high altitude, the victim of pulmonary edema experiences extreme weakness, shortness of breath, nausea, vomiting, very rapid pulse (120 to 160), cyanosis (bluish color) of the fingernails, face and lips, noisy breathing which progresses to moist crackling breath sounds, and irritative coughing which produces a frothy white or pink sputum and later blood.

If untreated, the victim rapidly moves into the final phase characterized by unconsciousness and bubbles in the mouth or nose, and death will follow. The early symptoms may be mistaken for mountain sickness or fatigue, or may pass unnoticed during the night, with the morning finding the victim unconscious and in the final phase.

High-altitude cerebral edema is the accumulation of fluid in the brain. Symptoms begin with a severe, relentless headache resulting from pressure due to the swelling of brain tissue. They advance to difficulties with physical coordination, slurred speech, irrational behavior, collapse, and eventually death.

For both pulmonary and cerebral edema, you need to be alert to symptoms in yourself and others. The most effective first aid is rapid evacuation to lower altitude or constant administration of oxygen. Descending is the only way to recover, with a rapid descent of 3,000 feet usually bringing marked improvement. If the victim exhibits only minor symptoms, it may be OK to spend a few days at lower elevations and then go back up. But a climber who demonstrates advanced signs should not return to high altitude, as it takes weeks to recover from edemas.

Frostbite

Frostbite is a concern at high altitudes because of the cold environment and because reduced oxygen means your body is less efficient at generating internal warmth, making hands and feet more susceptible to freezing.

Frostbite is freezing of the tissues, and most commonly affects toes, fingers, and face. It occurs when an extremity loses heat faster than it can be replaced by the circulating blood, or it may result from direct exposure to extreme cold or high wind. Damp feet can freeze when moisture conducts heat away from the skin and destroys the insulating value of socks and boots. With continued cold or inactivity, circulation to the extremities is steadily reduced, accelerating the freezing process. If you're using good mountaineering clothing and equipment, frostbite is not likely to occur.

An area of superficial frostbite looks white or gray. Surface skin feels hard, but the underlying tissue will be soft. As the frostbite intensifies, the affected area becomes hard, cold, and insensitive.

You can warm superficially frostbitten areas by placing them against warm skin. Put your feet against a companion's abdomen or armpits. Warm your fingers in your own armpits. During rewarming, large blisters may appear on the surface, as well as in the underlying tissue. Two important cautions. You must not raise the temperature of the frostbitten area much above body temperature, such as by warming near a fire. And never rub the injured part, especially not with snow. The additional cooling and the abrasive action further damage devitalized tissues. Misguided efforts to give speedy relief invariably increase the injury.

You can thaw extensive or deep frostbite, in which the affected area is white, has no feeling, and appears deeply frozen. Immerse the damaged area in water that is at a temperature between 99 and 104 degrees Fahrenheit until it is thawed. But do not start the thawing unless you are sure you can thaw the part completely and without interruption. It's better to wait for medical help than risk incomplete thawing or refreezing. Sometimes it's better to make no attempt to thaw frozen feet until after you retreat from the mountains and can get transportation and medical aid. If you leave your feet frozen, it's still possible to walk on them and suffer little or no additional tissue damage. But once your feet are thawed, you won't be able to walk and you will probably experience severe pain.

ACCLIMATIZATION

The body needs time to acclimate to higher altitude. However, the time it takes to adapt varies from person to person.

Ascend at a moderate rate, averaging 1,000 feet a day in net elevation gain. If you are doing double carries, this may mean establishing camps at 2,000-foot intervals so that you carry one day and move camp the next, for a net gain of 2,000 feet every two days. If the suitable campsites are 3,000 feet apart, you can carry one day, move camp the next, and rest the third day, for a net gain of 3,000 feet every three days. Try not to overdo your efforts until you've become well acclimated, and schedule rest days after big pushes.

Hydration is critical in avoiding altitude sickness. Rather than relying on a figure for daily liquid consumption, such as 4 quarts per person, monitor your urine output and color. A good rule of thumb is that urine should be copious and clear, while dark urine indicates you're not drinking enough water.

Above 18,000 feet, most people begin to deteriorate physically regardless of acclimatization. Minimize the stays at high altitudes and periodically return to lower altitudes to recover. The old advice is good: Climb high, sleep low. The body acclimates much faster during exertion than during rest, and recovers more quickly at a lower altitude. Expedition-style climbing takes advantage of these concepts in carrying loads to a high camp, returning to lower altitude to recover, then ascending again.

AN EXPEDITION PHILOSOPHY

Members of an expedition need a common code to live by during the weeks they struggle together. A good one is summed up in three promises you and your teammates can make: To respect the land, to take care of yourselves, and to come home again.

Every day, your expedition will have the chance to put the health and beauty of the land ahead of your immediate comfort. The easy way out might be to burn wood fires or set up camp in a virgin meadow or abandon heavy gear. But if you've promised to respect the land, you'll be able to do the right thing.

If you and your partners have promised to take care of yourselves, you've made a commitment to group self-reliance. You may have no choice in the matter, anyway, as you will likely be a long way from rescuers, helicopters, hospitals, or even other climbers. You can prepare by thinking through the emergencies the expedition could face and laying plans for saving the day. You'll be happy the plans are ready if you have to use them, and grateful if you don't.

The third promise might be the hardest to keep because it can conflict with that burning desire for the summit. It's really a promise to climb safely and to sacrifice dreams of the summit before laying your life on the line. But expedition climbing is, after all, about pushing limits and testing yourself in a very tough arena. Each person and each team must decide what level of risk they wish to accept. Out of that flows daily decisions on how fast to ascend, what gear to carry, when to change routes, when to back off. Most climbers would rather return home safely than push for the summit under unsafe conditions. But how do you define "unsafe"? You'll keep the third promise by being sure you find the definition that is just right for your expedition.

A SAMPLE EXPEDITION EQUIPMENT LIST

GROUP GEAR

Shelter

☐ Expedition-quality tent
☐ Snow stakes and/or tent flukes
☐ Sponge and whisk broom
☐ Snow shelter construction tools: large snow shovel (for moving lots of snow); small snow shovel (for delicate trimming); snow saw (for cutting blocks)

Group climbing gear

☐ Ropes
☐ Hardware: snow and ice gear (pickets, flukes, ice screws); rock gear (pitons, spring-loaded camming devices, chocks); carabiners; runners; fixed line; extra climbing equipment (spare ice axe or tool, spare crampons)

Kitchen

☐ Stove gear: stove; wind screen and stove pad; fuel containers and fuel filter; matches and/or butane lighters
☐ Cook gear: pots; pot gripper, sponge/scrubber; dip cup and cooking spoon; snow sack

Repair kit

☐ Tent repair kit (pole splices, spare pole)
☐ Stove repair kit
☐ Crampon repair kit (extra screw, connecting bars, straps)
☐ Tape (duct, filament, ripstop fabric repair tape)
☐ Tools (standard, Phillips, and Allen screwdrivers, small pliers, small wire cutter/shear)
☐ Sewing kit: assorted needles and thread; assorted buttons, snaps, buckles, and "D" rings; Velcro (hook and rug); fabric (cordura, ripstop); flat webbing
☐ Miscellaneous: extra ski pole basket; wire and cord

First-aid kit

- ☐ Most expeditions will have a comprehensive group first-aid kit. In addition to the normal first-aid items, the kit should include the following drugs, plus others recommended by a physician.
- ☐ Prescription drugs. This will vary with the destination but should include antibiotics, strong analgesics, anti-diarrhetic, laxatives, and altitude medication (Diamox, dexamethasone).
- ☐ Non-prescription drugs. This will vary with the destination but should include a cough suppressant, decongestant, and mild analgesic (aspirin, ibuprofen).

Miscellaneous group gear

- ☐ Altimeter and compass
- ☐ Radio transceiver
- ☐ Latrine equipment (plastic sacks, rubber gloves)

PERSONAL GEAR

Clothing

- ☐ Synthetic fabric underwear
- ☐ Insulating layers
- ☐ Down clothing
- ☐ Wind protection garments (top and bottom)
- ☐ Extremities: hands (liner gloves, insulating gloves, and mittens); feet (liner socks, insulating socks, vapor-barrier socks); head (balaclavas, sun hats, face masks)
- ☐ Miscellaneous: bandannas; sun shirt; plastic double boots; supergaiters and/or overboots

Sleeping

- ☐ Sleeping bag
- ☐ Bivouac sack
- ☐ Vapor-barrier liner
- ☐ Inflatable foam pad
- ☐ Closed-cell foam pad

Climbing

- ☐ Ice axe
- ☐ Second ice tool
- ☐ Ski pole
- ☐ Seat harness with ice tool holsters
- ☐ Chest harness
- ☐ Crampons
- ☐ Personal carabiners
- ☐ Personal runners
- ☐ Ascenders and/or prusiks
- ☐ Helmet
- ☐ Large-volume pack
- ☐ Snowshoes or skis
- ☐ Sled with associated hardware (haul lines, carabiners, prusiks)

Miscellaneous gear

- ☐ Avalanche beacon
- ☐ Sunglasses and goggles
- ☐ Spare prescription glasses
- ☐ Personal hygiene: toilet paper; pee bottle; toothbrush; comb; chemical wash/wipes; sunscreen; lip balm; foot powder; ear plugs
- ☐ Personal recreation: camera and film; books; journal (waterproof paper); personal stereo

• 16 •

SAFETY AND LEADERSHIP

Mountaineering is a sport of controlled risk. Climbers deal with the hazards of nature and their own shortcomings by cultivating knowledge, skill, and good judgment. A list of dangers in the wilderness reads like a catalog of disaster unless you've studied the hazards and know how to avoid them in order to establish control over your own safety. Climbers also need to develop leadership ability to help promote their group's safety, comfort, and success.

ACCIDENTS

One way to prevent accidents is to study incidents that have happened and try to learn from them. The American Alpine Club does just that in its annual publication "Accidents in North American Mountaineering." The publication includes only actual climbing accidents, as distinguished from other mishaps that occur in mountainous regions. It describes only those accidents that are voluntarily reported, so it doesn't include numerous unpublicized incidents. The accidents represent only a fraction of those in mountaineering areas throughout the world.

More than 1,100 climbers have been killed in North American mountaineering accidents since 1947, when the American Alpine Club began its annual reports. Despite advances in equipment, skills, and techniques, a number of climbers are killed or injured each year. Every accident is a little different from every other, but there are many common causes and most involve human error. For example, modern gear rarely breaks by itself. Equipment failure is usually related to improper use or to poor placement of protection. Climbers also cause accidents when they try to exceed their climbing abilities by relying on incompletely learned techniques.

There are some limitations to the American Alpine Club statistics because the types of causes change as climbing practices evolve, and the classification of accidents is a difficult judgment call, especially in deciding the relationship of immediate and contributing causes. But in spite of these limitations, the annual reports roughly indicate the elements of danger in climbing by showing recurring patterns.

The most common immediate causes of accidents reported were (1) fall or slip on rock, (2) slip on snow and ice, and (3) falling rock or other object. The most common contributing causes were (1) climbing unroped, (2) attempting a climb that exceeded abilities (inexperience), and (3) being inadequately equipped for the conditions or climbing situation.

An accident victim may feel that a mishap occurred "like a bolt out of the blue." But it's clear, in retrospect, that many accidents moved step by step toward an almost predictable incident. The climber who takes off on an ascent without an ice axe because it was forgotten in the rush of leaving home may do fine all day in soft snow. If this climber slips during the descent on the firmer snow of evening and is injured, it's an accident—but it's no "bolt out of the blue." An alert leader tries to spot potential accidents, and takes such precautions as turning back a minimally equipped party in the face of worsening weather.

CLIMBING HAZARDS

Mountaineers face hazards of two sorts: the objective dangers of the mountain environment, and the subjective factors that are dependent on the climber. The objective, physical hazards of the mountains—the storms, the cold, the high altitude—are easy to recognize. No less important, but far harder to evaluate, are the subjective factors involving the climber's knowledge, skill, and judgment.

OBJECTIVE HAZARDS: THE MOUNTAIN ENVIRONMENT

Objective hazards are the natural processes that exist whether humans are involved or not. Darkness, storms, lightning, cold, precipitation, high altitude, avalanches, and rockfall are powerful, impersonal environmental conditions that can easily overwhelm humans. These objective hazards of the mountains are eternally persistent and changeable. We cannot control these forces, but we can learn to recognize them and act to minimize their dangers.

You will find detailed information throughout this entire book on dealing with objective hazards, especially in the chapters on wilderness travel and on the various types of climbing—rock, snow, ice, winter, and aid. They spell out ways to confront objective hazards ranging from fearsome exposure and rotten rock to avalanches and steep snow slopes with poor runout. They give advice on avoiding rockfall, icefall, cornices, crevasses, and other environmental dangers.

Many of the hazards of the terrain are relatively easy to spot, such as rotten rock or a steep cliff. The hazards of weather can be somewhat more difficult to identify because they change so quickly. When they do, it often adds significant risk to the climb. Rain or snow turns warm, dry rock into wet or icy surfaces difficult to climb. Wind blows ropes around and also makes communication more difficult. Fog or whiteout obscures the route, forcing you to rely on compass and altimeter for navigation and increasing the danger of falling into a crevasse or off of a cornice.

Cold weather, especially if it is abetted by wind and rain, can bring deadly hypothermia. Hot weather, on the other hand, poses the dangers of dehydration and hyperthermia. (Specialized courses and publications on mountaineering first aid provide information for diagnosis and treatment of these conditions.) Lightning, although not one of the principal hazards of mountaineering, has caused a number of serious accidents. The peaks and ridges that climbers seek generate the vertical updrafts and rain-cloud conditions that generate lightning.

Reducing the risk

To reduce risk, you need to recognize objective hazards and learn how to avoid them. If you recognize the possibility of rockfall, for instance, you will wear a hard hat and take extra care to prevent knocking rock loose with the rope or with your body. If you recognize an avalanche-prone slope, you will follow the correct procedures to avoid it and will know what to do in the event you or someone in your party is caught in a slide. If you see a white-out or other extremes of weather developing, you will have the training and equipment to deal with it.

It's simple to recognize the objective hazard of high exposure—that is, being in a steep and exposed place. There are exposed places where you can sit or stand without serious danger, but loose footing or a moment of inattention can bring tragedy. The safest response to exposure is to rope up so you are on belay or tied into the mountain. If you are the belayer, estimate the direction and magnitude of any force you may have to absorb if your partner falls and set up an anchored belay station where you can handle such a fall.

It's not so easy to recognize the hazard of a crevasse that is hidden beneath a layer of snow. But if you have studied glacier travel and learned the external signs of hidden crevasses, you will know when to rope up and how to choose routes that minimize the danger of falling into one. You and your companions also will have the training and equipment to carry out a safe, efficient crevasse rescue if that becomes necessary.

Help fortify yourself against objective hazards by always carrying the proper clothing, food, and equipment, because any trip can bring unexpected danger or an emergency bivouac. Protective gear, whether it's for technical climbing or bivouac survival, doesn't do any good if it is left at home, and it cannot often be replaced merely by nerve or skill.

You can use this book as a basic guide to proven gear and techniques, by studying the chapters on the various types of climbing and wilderness travel in addition to the specialized chapters on clothing, equipment, camping, navigation, knots, belaying, and rappelling. Then work to develop the experience and judgment to make the right decisions at the right time in order to avoid what are generally called accidents.

SUBJECTIVE FACTORS: THE CLIMBER

Subjective human factors share the blame for many accidents along with the objective physical hazards of the mountain. The climber without a bivy sack or extra clothes wouldn't have become hypothermic if it were not for that unexpected snowstorm. Conversely, the snowstorm wouldn't have caused any grief if it had not crossed paths with the climber.

The natural forces constantly at work on a mountain are usually harmless unless a human being is in their way at a critical instant. Then a small mistake—the subjective human factor—can cost dearly. A slope may be ripening to an avalanche tomorrow, but a climber ignorant of snow structure can trigger it today. A rock weakened by natural processes may be preparing to fall next week, but the weight of a climber can pull it loose today. This subjective factor, which brings a particular climber to a given danger point at just the perilous moment, is nearly always at the root of a climbing accident.

Although we can't alter the objective hazards, we have considerable control over the subjective factors that can reduce their risk. These subjective elements affect every phase of a climb, including choice of route, skill of the climbers, equipment quality, physical conditioning, leadership, and climbing techniques. In the final analysis, everything goes back to a climber's knowledge, skill, and judgment. Any shortcomings will eventually show up in the reality of a climb.

Knowledge

A beginner ignorant of mountaineering gains knowledge from books, courses, mountain climbers—and from climbing. At the start, beginners won't even know they don't know: a novice might look at an avalanche-prone slope warming in the sun and not even be aware the party needs to ask itself whether there is a risk. But as they study and as they climb, beginners can add to their knowledge by keeping alert and asking questions.

A climber won't learn much by simply tagging along without paying attention to the climb, relying on others to make all the decisions and ending the day with not much more mountaineering knowledge than at the start. A climber with inadequate knowledge can mean danger to a climbing party, which may need to count on every member in an emergency—a poor time to have to unmask a climber's failings.

Skill

A great many climbers are skilled, but some are more skilled than others. The point is that it's important to match a climber's skill level with the particular climb. A good match and you have a safe, satisfying climb. A poor match and you could have disaster. An excellent climber trying to raise a personal level of skill faces increased risk; so does a novice moving up to an intermediate-level climb. A climber who does well on warm, dry rock may be in trouble if the rock is wet.

It takes practice and more practice to raise your level of skill. Practice under forgiving conditions. Try making those harder moves first at a practice area with a top rope, rather than on a long run-out at the end of a strenuous pitch. Keep working at it. A great part of climbing safety lies in competence that embraces a commitment to better methods, an eagerness to study and to learn, and a determination to practice and perfect the skills of mountaineering.

Judgment

Good judgment can be a climber's most valuable ally. Good judgment is the quality of using knowledge gained from study and experience to make sound decisions. Your mountaineering judgment should get better and better as you read and as you climb. Watch experienced climbers at work and try to determine what decision they will reach in a particular situation, and why. Learn to think, question, and reach informed decisions.

Experienced climbers won't always agree on what constitutes good judgment in a particular case. Some climbers demand a conservative high level of safety and would consider a decision that results in moderate risk to be evidence of poor judgment. Others would find the decision correct based on all the conditions of the climb and the abilities of the climbers. Each person has an individual definition of an acceptable level of risk, so climbers need to discuss this question with their teammates before a climb. The start of good judgment is to decide on an acceptable level of risk for yourself and to match your known skills with the difficulties of the climb.

A common form of poor judgment is underestimating the skills needed for an objective, whether it's a single move or a major mountain ascent. It's poor judgment to climb beyond your present ability and knowledge during a demanding climb. Try new moves and techniques in a practice situation. But if they come during a climb, be sure you have extra protection—good enough to prevent injury in case you fall and to permit you to get back on route afterward.

It's also poor judgment to let desire for the objective overwhelm an accurate assessment of the risk. Desire is a very useful element in climbing; it helps you forget weariness and calls forth your best efforts. But if it's not restrained, it can end in disaster. It can delude you into thinking that a faraway summit is close, that a questionable placement will hold, that a weakened team is strong enough. This is wishful thinking. Be rigorous in making a rational evaluation of weather, party strength, and other factors in deciding whether or not to turn back.

Good judgment in mountaineering also means acknowledging when you or your team are having a bad day. All experienced mountaineers remember days when their climbing lacked the usual feel; when easy pitches felt hard. Take any bodily limitations into account, such as fatigue, cramps, blisters, altitude sickness, or poor conditioning. If you're honest with yourself, you'll recognize that occasional bad day and scale back your plans accordingly.

LEADERSHIP

The safety, success, and fun of a climb depend in large part on leadership and organization. These formal concepts may sound a bit stuffy for the out-of-doors, but they exist in any successful climbing party. A small group of longtime climbing companions probably incorporates all the elements of leadership and organization with no conscious thought or effort because they have become habit over the years. It's a different matter with a party that includes beginners and whose members have never climbed together.

Leadership starts with each individual. Individual leadership means being aware of the group and its progress, whether or not you are the formal climb leader. Assume responsibility for your own knowledge and skill, and make personal judgments based on how they can support the group's objective. Be willing to speak up when you feel the risks of the climb may exceed the abilities of the party. Don't be deterred by fears that others know more than you and may consider you weak. By asserting personal leadership, you can contribute to group decision-making within the framework of the established organization.

The complexities of leadership grow as party size and trip length increase. On a weekend climb by two close friends, it's possible for one of them to take on all the organization and leadership chores: planning the menu, selecting the route, supplying the gear, and so forth. In a group of several friends, leadership may be by consensus. As the trip becomes more complex, one person may be designated the formal leader, charged with coordinating the group's activities.

The leader of a climb cannot do everything, nor is that desirable. A leader delegates duties and responsibilities in order to maintain an overview of the trip and ensure that all tasks are carried out. This also helps build morale as party members become more involved in the climb by taking on specific jobs such as planning meals, arranging transportation, or coordinating equipment. In a group that is large or in which the members are not well acquainted, the leader should appoint an assistant who can assume the role of leader if that becomes necessary.

A leader is also a teacher. Beginning mountaineers need help with climbing techniques, and experienced mountaineers may appreciate help in learning leadership. The best leaders exhibit the patience, empathy, and generosity that it takes to give members of their party experience in all phases of leadership.

Leaders prepare carefully to meet any major disaster that could befall their party. But the most common, and the most vexing, problems of leadership are the less dramatic, exasperating little mishaps that arise at the most inopportune moments—a lagging, footsore climber who is breaking in new boots, or another too ill or fatigued to continue the climb. There is no set answer for these trying situations. The leader is called on to use good judgment in evaluating the predicament, and then make a decision firmly and unequivocally. An effective leader recognizes the potential for serious consequences in such seemingly trivial problems.

Mountaineering trips bring a rich spectrum of choices and make continual demands on a climber's will. Without leadership, even a strong party may wander aimlessly or sit paralyzed with indecision. But with good leadership, even a relatively weak party may achieve its goals.

THE STRENGTH OF THE CLIMBING PARTY

Whether a party is up to the challenges of a particular climb depends on its overall strength, which in turn involves the proficiency of the climbers, the size and speed of the group, and other important factors. Good leadership is central to maintaining a party's morale and making the most of its attributes.

Mountaineering proficiency

The strongest party consists of several climbers with a high degree of mountaineering proficiency—experienced, well-equipped, in good physical condition, with every skill for the climb at hand. What constitutes a weak party is not so easy to define. In some cases, a party is strong enough if it has only two strong climbers in addition to many weak members. In other situations, a group of ten strong climbers and one ineffective climber is too weak a party. A group with no experienced members is a weak party in any case.

The leader should be familiar with the climbers' abilities in order to know how to assign them. The leader may need a patient, reliable climber to encourage slow members at the rear of the group, or a pair of sharp routefinders to scout out the way ahead. If the leader is traveling near one end of a large party, an assistant should be assigned to help near the other end.

The leader also uses knowledge of the climbers' skills in setting up rope teams. In small parties, rope teams are usually formed by tacit agreement among members of the group. But in larger parties or in groups where the people are relative strangers, the leader may set up teams based on the climbers' experience, speed, and personality. Each team of experienced climbers should have enough strength to rotate the lead, sharing the work and giving less proficient climbers a chance to expand their experience.

Size of the climbing party

The minimum size for a mountaineering party is considered to be the number of people who can handle an accident situation adequately. Traditionally, a minimum party of three has been standard. Thus, if one climber is hurt, the second can stay with the victim while the third goes for help.

Variations from the basic unit of three depend on the situation. On difficult terrain or in adverse weather, when it would be dangerous for one person to go alone for help, four may be the safe minimum. On the other hand, the complexity of the route may make more then a single rope team of two a liability.

A glacier climb calls for four to six people, divided into two rope teams, in order to carry out an efficient crevasse rescue. A climb in a remote area where there may be no help within 100 miles must be planned for complete self-sufficiency and, therefore, may become an expedition of relatively large numbers. A small party in a remote area must consciously accept an increased level of risk.

It's a mistake, however, to believe that a larger party is always a safer party. A larger party can start bigger avalanches and kick down more loose rock. It will generally be slower and more unwieldy, both in camping and climbing. A party of ten to twelve is considered the largest that can impose itself on the wilderness without serious damage to the ecosystem—and even this is too large a group for some areas.

Backup support

A party gains in strength if it has a support team nearby or if there are other climbers in the area. To be useful, a support team must be willing and able to come to your aid, and ready to initiate rescue automatically at a prearranged time. Then, if your party doesn't report in by a certain time, a rescue effort will get under way.

At the very least, be sure to leave a written description of your plans with a responsible person who will dispatch help if you don't return on time. Leave enough information so rescuers have a fair idea where to look, but there's no need to make it so detailed that you limit your own choices when you get to the area. If you do deviate from the schedule you left behind, keep in mind that you may be complicating any rescue effort. Give an estimated time of return, but build in enough leeway so that a few hours' delay from a routefinding error or other minor problem won't result in having the rescuers called out. Don't forget to check in when you return.

Keeping the party together

A critical responsibility of leadership is keeping the party together in order to concentrate strength and maintain communication. It's easy to divide up in the course of the trip, drifting into weak splinter groups. Some parties are large enough to divide into self-sufficient subgroups, but each subgroup must have adequate strength and leadership to meet its goals.

In small parties of equally proficient climbers, it's fairly simple to keep people together; if one lags, the others usually recognize the problem and slow their pace. In larger parties, the leader and assistants must work together to keep their group from splitting into independent fragments. This situation arises most often within organized club outings and climbing courses. Leaders of these groups may need to exert considerable control to keep the lead rope team from charging ahead, losing contact with climbers on the last rope.

It's even harder to keep a party together on the descent than it is on the way up. The leader, normally the last person off the mountain, must lay out crystal-clear instructions for where and when the party will meet in case of a separation. Glissading often results in breaking up parties. The fast, experienced glissaders are off the bottom of the run and on their way long before the last members of the group can overtake them. The leader should require a rendezvous of the entire party reasonably near the end of any major glissade. If the leader can hold the group to a pace everyone can maintain, there's little danger the party will be weakened by fragmentation or by having to search for a missing climber.

Time management

Speed is often equated with safety, and this can be true in crossing an area of rockfall hazard or trying to reach camp before dark. Speed also has its dangers. A quick, hard push can get climbers to a place where retreat is difficult in the face of deteriorating conditions, whereas a more measured, cautious approach would have left them with an easier withdrawal. Speed for its own sake can be a hazard if it comes at the expense of proper technique or safety precautions. The important thing is not how fast you go, but how wisely and well you use your time.

A climbing party's use of time should be planned out in advance, at least roughly. You can figure out the best time to get under way in the morning by mentally working through the various sections of the climb and estimating how long each will take. It's a good idea to set a time for turning back even if the summit hasn't been reached. The turn-around time will help prevent the party from pushing onward after it's too late to reach the summit and still get back to the camp or trailhead in daylight.

BECOMING A LEADER

Becoming a leader is a do-it-yourself project, requiring desire and initiative. The best way to become a good leader is to lead and to watch others lead, to organize informal private trips with friends on short, familiar climbs, and to gradually work up to more ambitious projects. Climb with experienced leaders and observe how they plan and how they work with their teams. Ask for assistant-leader positions on these climbs and become involved in the planning and decision-making.

Self-appraisal is a big part of becoming a good leader. Effective leaders take the time to assess their own performance, asking themselves: Did I do as well as I could? What went right? Why? What went wrong? Why? How could things have been improved?

Leadership brings pleasures as well as burdens. As awesome as the duty may appear, the exercise of competent leadership can become surprisingly easy if you prepare for it, fully accept the responsibility, and use common sense and good judgment to deal with rapidly changing situations.

• 17 •

ALPINE RESCUE

Mountaineer training emphasizes techniques for staying safe and healthy. But when injury or illness strikes, it's likely to be a long way from professional medical aid or rescue. Climbers are usually rescued by other climbers, often at great risk and sacrifice. So high a degree of mutual responsibility requires that every mountaineer be able to help in a rescue. This chapter focuses on efforts that can be mounted by a small climbing party without specialized equipment.

SEARCH

Searching for a missing person is one of the most common rescue activities. Start a search only if you can answer "yes" to this question: "Does the missing person need help?" If the person is healthy, well-equipped, traveling where injury is unlikely, and experienced in climbing and route-finding, there's a good chance he or she will find the way back to the party within a few hours. You may decide to defer a search until the next morning to give the missing person time to return.

Start the search immediately if the missing person might have wandered onto steep rock or a crevassed glacier, or is fatigued, inexperienced, or poorly equipped. Also get the search started right away if a physical problem, such as diabetes, is a factor, or if the missing person is a child. Search immediately if an entire rope team is missing after a severe storm, or in avalanche conditions, or on difficult terrain.

The thoroughness of a search will depend partly on how many searchers are available. A small party may be able to mount no more than a narrow search along a limited track. With a half dozen people, there probably can be a perimeter search. A large group can thoroughly comb a considerable area.

Regardless of the method, each person must know the full plan before the search begins. If the party decides to split up, each group must know where the others are. Arrange signals ahead of time: sounds such as yodels, yells or whistles, or visible signs with mirrors or lights. Establish a time and place for everyone to meet, whether or not they have found anything.

For safety, searchers should travel in pairs or remain within earshot of one another. Of course, this means that a search party of only two or three people can cover no more than a narrow strip of ground at a time. The best chance in this situation is to outguess the missing person. Put yourself in that person's place and visualize errors that might logically have been made. Check likely places such as the exits of off-route gullies and ridges.

If that doesn't work, retrace your party's original trail, searching all the way for tracks that indicate where the missing person wandered off. When such a point is found, proceed along the most likely path, watching for more footprints in snow, mud, sand, or on foot logs. In the absence of frequent footprints, searchers must fan out at broad intervals, calling to each other regularly and pausing frequently to listen for calls from the missing person. If no clues turn up after several hours of searching, it's probably time to go for outside help.

WHEN AN ACCIDENT HAPPENS

Leadership and discipline are key elements of success in alpine rescue. If your party has no recognized leader, select one to take charge in an emergency. The leader should consider suggestions from other members of the party, but the leader's decisions must be accepted without argument.

Go to the aid of an injured climber quickly—but move carefully to avoid any further accidents. On difficult terrain, dispatch only one or two rescuers, who are on belay and packing all the needed aid and rescue gear. As you climb or rappel down to an injured climber, keep to one side to avoid the danger of knocking rocks onto the victim. Stay calm; frenzied activity only complicates the rescue.

Urgent first aid should be rendered as soon as possible: bleeding stopped, breathing restarted, shock relieved, fractures immobilized. If it becomes necessary to move the victim to another spot because the accident site is too hazardous, use methods that will not compound the injuries.

It's important to keep close watch over the injured climber. A victim who is left unguarded, even for a few moments, must be tied to the mountain to prevent the danger of falling or wandering off, perhaps due to confusion or irrationality. Design the tie-in so that the climber cannot unfasten it.

In dealing with an emergency, swift action may be less effective than correct action. A hasty splitting up of the climbing party or any other spontaneous but shortsighted effort has less chance of ultimate success than one more deliberately considered. Therefore, after the initial demands of safety and first aid are satisfied, the leader and party sit down to plan. Everything must be thought through to the very end, everything prearranged, including what each person is to do under all circumstances throughout the rescue operation.

Every aspect of the situation needs cool analysis. How serious are the injuries? What measures are necessary to sustain the victim during evacuation? What is the terrain like and how far is it to the road? What are the strengths and resources of the party? Only after careful analysis of such questions should your party select a course of action.

EVACUATION BY THE CLIMBING PARTY

A climbing party can sometimes evacuate an ill or injured party member with no outside help. If the injured person can walk and the injuries are relatively minor, a lightened pack and moral support may be all that is needed. The party also may be able to evacuate a climber who has minor but disabling injuries such as a sprained ankle or injured knee.

An injured person generally benefits from a period of rest following an accident. Because the further trauma of immediate evacuation is seldom justified, postpone the move until the victim's condition has stabilized. The injured person can probably offer the best indications of when to begin the evacuation. Consult the victim and monitor the injuries closely, before and during the evacuation, and always keep the person's comfort in mind.

Some medical conditions require immediate evacuation: pulmonary edema, cerebral edema, unconsciousness for unknown cause, diabetic coma, and progressively deteriorating conditions such as appendicitis. Immediate evacuation also is necessary if circumstances of weather or terrain are life-threatening. Certain other conditions require that evacuation be delayed until trained medical help arrives (unless it will be more than 24 hours): head injuries, neck and spinal fractures, heart attack, apoplexy (stroke), and internal injuries. Evacuation is required but not urgent for all other serious injuries and illnesses.

OUTSIDE HELP

There are times a party can't cope with its own emergency. Outside help probably will be needed if a climber's injuries are severe, if the evacuation requires long stretches of lifting or lowering, or when circumstances—party size, condition of party, terrain, and distance to the trailhead—combine to make transport difficult. Thirty or more rescuers may be needed to carry a disabled victim for more than 2 or 3 miles on even the best of trails.

After your party decides that outside aid is needed, send for help as soon as the victim is stabilized and the persons going for aid are no longer needed at the accident site. In many areas, help by helicopter is usually no more than 3 hours away once word gets to the proper authorities, though this will depend on weather, terrain, and local politics. Ground rescuers often can be at the scene in 8 to 16 hours. If the climbing party is in a sheltered area accessible by helicopter and the weather is good, don't move the victim unless the injuries require doing so.

If your party needs help, don't hesitate in asking it from climbers on nearby peaks, from people living or working in the region, or from local authorities. A climbing party should know in advance where to turn for help if its own efforts fail and how to cooperate with rescuers and authorities.

It is sometimes not possible to send anyone from your group for help. Your only alternative then is to try to signal rescuers with noise or visual signals. Such a situation dramatizes the need to leave information about your intended route and estimated time of return with a responsible person, who will notify authorities if you don't show up.

GOING FOR HELP

If possible, send two climbers out together for help—partly for safety and partly because two people can do a better job of obtaining aid. Be sure they have a clear understanding of the party's situation and requirements so they will know exactly what aid to seek. They should take with them a list of the names and phone numbers of everyone in the party, a completed accident report form, and a map that pinpoints the accident site. Fill out an accident report form (fig. 17-1) for each injured person, with one copy going out with the messengers and the other being kept by the party leader.

Messengers need to carry enough gear to handle their own emergencies but not so much that they cannot move swiftly. However, the certainty, not the swiftness, of getting the message out is the most important consideration. The messengers must travel in a safe manner. The victim and other members of the party are relying solely on them, assuming authorities will get the word and that help will soon be on its way. The messengers should mark the route to help in finding the way back.

The messengers have several vital responsibilities once they get out of the wilderness. First of all, they contact the appropriate local authorities, such as the county sheriff or park personnel. They ask them to help in a rescue, or to relay the need for help to the local Mountain Rescue organization. If evacuation will take place over technical terrain, the authorities must know this so they will dispatch rescuers with the proper training.

The messengers' job is not ended at this point. They must make certain that messages are sent at once, accurately, and that they reach their destination. Often the organization of a rescue depends upon a chain of communication, messages relayed from person to person via telephone and radio, until finally a rescue leader is reached. Along the way, vital information may be ignored by non-mountaineers who do not understand the words they are asked to convey. The messengers should talk directly with a trusted fellow climber so that the line of communication is not broken. If the messengers can't speak personally to the rescue leader, they must be insistent with intermediaries—perhaps to the point of being obnoxious—to assure that a garbled message does not result in a tragic rescue failure.

The messengers then wait by the telephone at a meeting point, where they will get together with the rescue party. The messengers turn the accident report, map, and list of names over to the rescue leader and assist in devising a rescue plan. Unless

Fig. 17–1. Accident report form



© The Mountaineers

FIRST AID REPORT FORM

START HERE — **FINDINGS** — **FIRST AID GIVEN**

AIRWAY, BREATHING, CIRCULATION

INITIAL RAPID CHECK
(Chest Wounds, Severe Bleeding)

ASK WHAT HAPPENED:

ASK WHERE IT HURTS:

TAKE PULSE & RESPIRATIONS	PULSE	RESPIRATIONS

HEAD-TO-TOE EXAMINATION

- HEAD: Scalp—Wounds
  - Ears, Nose—Fluid
  - Eyes—Pupils
  - Jaw—Stability
  - Mouth—Wounds
- NECK: Wounds, Deformity
- CHEST: Movement, Symmetry
- ABDOMEN: Wounds, Rigidity
- PELVIS: Stability
- EXTREMITIES: Wounds, Deformity
  - Sensation & Movement
  - Pulses Below Injury
- BACK: Wounds, Deformity
- SKIN: Color
  - Temperature
  - Moistness

STATE OF CONSCIOUSNESS

PAIN (Location)

LOOK FOR MEDICAL ID TAG

ALLERGIES

VICTIM'S NAME	AGE
COMPLETED BY	DATE TIME

TEAR HERE–KEEP THIS SECTION WITH VICTIM

DETACH HERE–SEND OUT WITH REQUEST FOR AID

RESCUE REQUEST

Fill Out One Form Per Victim

TIME OF INCIDENT AM PM	DATE

NATURE OF INCIDENT
FALL ON: ☐ ROCK ☐ SNOW ☐ FALLING ROCK
☐ CREVASSE ☐ AVALANCHE
☐ ILLNESS EXCESSIVE ☐ HEAT ☐ COLD

BRIEF DESCRIPTION OF INCIDENT

INJURIES (List Most Severe First)	FIRST AID GIVEN
SKIN TEMP/COLOR:	
STATE OF CONSCIOUSNESS:	
PAIN (Location):	

RECORD:	INITIAL				WHEN LEAVE SCENE
Time					
Pulse					
Respiration					

VICTIM'S NAME	AGE
ADDRESS	
NOTIFY (Name)	
RELATIONSHIP	PHONE

SIDE 2 RESCUE REQUEST

EXACT LOCATION (Include Marked Map If Possible)
QUADRANGLE: SECTION:
AREA DESCRIPTION:

TERRAIN: ☐ GLACIER ☐ SNOW ☐ ROCK
☐ BRUSH ☐ TIMBER ☐ TRAIL
☐ FLAT ☐ MODERATE ☐ STEEP

ON SITE PLANS:
☐ Will Stay Put
☐ Will Evacuate To ____________
Can Stay Overnight Safely ☐ Yes ☐ No
On Site Equipment: ☐ Tent ☐ Stove ☐ Food
☐ Ground Insulation ☐ Flare ☐ CB Radio

LOCAL WEATHER

EVACUATION: ☐ Carry-Out ☐ Helicopter
☐ Lowering ☐ Raising

EQUIPMENT: ☐ Rigid Litter
☐ Food ☐ Water ☐ Other

PARTY MEMBERS REMAINING:
_____ Beginners _____ Intermediate _____ Experienced

NAME NOTIFY (Name) PHONE

NOTIFY:
IN NATIONAL PARK: Ranger
OUTSIDE NATIONAL PARK: Sheriff/County Police, RCMP (Canada)

TEAR HERE—KEEP THIS SECTION WITH THE VICTIM
DETACH HERE—SEND OUT WITH REQUEST FOR AID

VITAL SIGN RECORD

Record TIME	BREATHS		PULSE		PULSES BELOW INJURY	PUPILS	SKIN	STATE OF CONSCIOUS-NESS	OTHER
	Rate	Character	Rate	Character					
		Deep, Shallow, Noisy, Labored		Strong, Weak, Regular, Irregular	Strong Weak Absent	Equal Size, React To Light, Round	Color Tempera-ture Moistness	Alert, Confused, Unresponsive	Pain, Anxiety, Thirst, Etc.

they are injured or extremely fatigued, they lead the rescuers back to the climbing party.

The messengers also have the job of seeing that information gets to relatives of people in the climbing party. Because of the urgency of seeking aid and the need to keep phone lines available, this job may have to await arrival of the rescue leader, who probably has had considerable experience in working with concerned relatives and with the news media.

TRANSPORT ON TECHNICAL TERRAIN

On steep terrain that demands technical climbing, even a minor illness or injury can make a person unable to travel without help. A large, well-equipped rescue party has a lot of options for safe and efficient evacuation of the victim. A small climbing party, however, will find it difficult to take any route that involves much raising or traversing. The small party usually will take an evacuation route straight down the fall line, which uses the least energy and equipment. Rescue on class 4 and 5 terrain usually requires more equipment than on the easier class 2 or 3 ground, where people rather than gear can provide most of the help.

Raising or lowering an injured person on technical terrain is a serious undertaking, with any number of things that can go wrong. A small climbing party should be prepared with prior training in rescue techniques and their complications, in order to avoid errors that make matters worse. A rescue is inherently more dangerous than a normal climb over the same ground because attention is focused on the victim instead of on the climbing. Often, the climbers must descend by a route unknown to them.

The prime object—moving the victim without further injury—is naturally uppermost in everyone's mind, yet the safety of each individual must never be forgotten. Solidly anchored belays may be required both for the victim and for the rescuers, even if they wouldn't be set up under ordinary climbing conditions. If ropes are in short supply, rescuers can be safeguarded by a fixed line to which they attach themselves with prusik slings.

A small party uses its available climbing hardware for rescue work and must think through the limitations of this equipment. Be sure the equipment can safely do what you plan to ask of it. The party's standard 11-millimeter climbing rope is usually adequate for rescue raising and lowering of single-person loads, although keep in mind that it will stretch. If the rope was involved in the accident, check it carefully for damage before using it in the rescue. Climbers in small parties often carry emergency items to help in a rescue. Depending on the climb, such items might include extra slings and carabiners, a pulley, folding saw, snow shovel, whistle, plastic tarp, and emergency smoke.

THE RESCUE BELAY

The belay is an important component of the system of raising and lowering persons who are ill or injured. Whenever possible, the person being moved should be on a belay that is independent of the mechanism that is being used for raising or lowering (fig. 17-2). With this independent belay, the victim is safeguarded in case of any disaster to the raising/lowering system, such as failure of the main anchor, rockfall damage to the rope, loss of the lowering brake or of the raising pulley, or injury to anyone operating the system. The belay anchor, independent of the main system anchor, should be constructed of multiple self-equalizing placements.

For belaying one person who is being raised or lowered, the belayer can use any standard belay device, maintaining it in a position that ensures maximum friction. Do not use a hip belay. For belaying two people at once, only the Münter hitch provides a safe enough degree of friction. (For a review of the Münter hitch, see Chapter 6.) The belayer should have the ability to continue lowering the victim if the original descent system fails. The belayer also should be able to safely carry out a knot bypass of the belay device (described later



Fig. 17–2. Typical lower with belay

in this chapter) if two or more ropes must be tied together for lowering.

LOWERING THE VICTIM

Before deciding to lower a victim, be sure that's exactly what you want to do. Once started, it's very hard to reverse. It can be especially tricky with a small party, in which there are not enough people to provide an independent belay or help out if complications arise. If you go ahead with lowering, watch that the rope doesn't dislodge dirt or rocks.

There are several possibilities for getting the affected person down the mountain, depending on the extent of illness or injuries:

Downclimbing: A person with slight injuries can climb down under tension from a tight belay, assisted by a companion who helps with placement of hands and feet. On snow or ice, large platform steps can be prepared.

Rappelling: If the victim has no head injury or symptoms of shock and is not seriously hurt, a rappel is possible. You can belay the rappel from above with a separate rope. Alternatively, you can offer a belay from below by holding onto the rope strands from the victim's rappel device. (However, don't pull down on the strands unless the injured person loses control of the rappel. Otherwise, you could interfere with the rappel, especially if the person is using a hip wrap for additional friction.)

Lowering in the seat harness: You may be able to lower the injured climber by the seat harness if neither downclimbing nor rappelling is possible. The victim must have no serious leg or upper-body injuries. Use a rope with a lowering device (described in the next section) to lower the victim, who uses hands and feet against the terrain to help guide the way down. The person will stay upright more easily by wearing a chest harness with the rescue rope going up through a carabiner at the harness. The injured person should be on an independent belay.

Back carry: This is a good technique if the victim has a minor but disabling lower body injury or is uneasy about rappelling or being lowered. Keep in mind that the rescuer must be strong enough to take the weight of the other person and still be able to maneuver. This will be especially difficult on low-angle rock. Connected like this to the victim, the rescuer will find it almost impossible to give first aid if medical problems arise. Do not use the back carry in cases that involve back or neck injuries, suspected internal injuries, serious head injuries, or other conditions requiring constant monitoring. For these, a rigid stretcher must be used.

Two common methods of back carry are the coil carry and the nylon-webbing carry. If possible, have the rescuer and victim on an independent belay, regardless of the method.

In the coil carry, the rescuer slips half the loops of a coiled rope over one shoulder and half over the other, with the coils looping down the back to form a seat for the injured climber (fig. 17-3). Tie a short piece of webbing around both loops over the rescuer's sternum to keep the coils from slipping off the shoulders. Run a prusik loop from the lowering rope to the injured person's chest harness to take some weight off the rescuer's shoulders and help keep the victim upright.

Another method of back carry employs nylon webbing to support and distribute the victim's weight (fig. 17-4). The webbing should be extremely well padded, especially under the victim's thighs, to prevent concentrated pressure that will cause a loss of circulation.



Fig. 17–3. Rope coil carry



Fig. 17–4. Nylon webbing carry


a
LOAD
b
Disassemble carabiners to pass knot through, then reassemble
LOAD
c
LOAD
d
LOAD

Fig. 17–5. Passing the knot in a two-rope lower through a doubled carabiner brake system

The lowering device

The best lowering device for use by a small party without specialized rescue gear is the standard carabiner brake system, as used in rappelling—but doubled (fig. 17-5). Simply construct two carabiner brakes, and join them with a locking carabiner. (Chapter 8 gives details on putting together a carabiner brake.) Each brake should include two braking carabiners (the crosswise carabiners).

The rescue rope runs through both brakes, providing increased friction for holding weight during lowering. The use of a standard belay device for technical lowering is not recommended because these devices were designed for single-person loads and may not provide sufficient friction for all the conditions of lowering. A doubled carabiner brake, on the other hand, provides enough friction for lowering two people at once.

Please note that the doubled brake system calls for a locking carabiner—not a pair of opposed regular carabiners—to join the two carabiner brakes. The single locking carabiner eliminates the possibility the rope could be pinched between a pair of carabiners. For the brakes themselves, standard symmetric oval carabiners work best.

Passing the knot

On a long pitch, you may want to tie two or more ropes together to permit a long uninterrupted descent for the injured person. As the knot approaches the lowering device (the doubled carabiner brake), it's necessary to stop lowering and perform a careful procedure to pass the knot safely through the device (fig. 17-5). Otherwise, the knot would jam.

It usually takes two people to carry out this procedure. Stop the descent when the knot gets to within 2 or 3 feet of the braking device. One person holds the lowering rope while the other attaches a prusik sling to the rope just below the brake, and then wraps this sling several times around one side of a carabiner that is anchored above the brake. (You can also connect to this carabiner with a Münter hitch if you wish.) The second person holds tight to the loose end of the sling while the first person gently eases the load onto the prusik by slacking off the lowering rope. The first person then passes the knot through the braking system one brake at a time: the upper brake is disassembled, the knot brought through, and the brake reassembled; then the same procedure follows with the bottom brake.

Once the knot has been passed through the entire system and the brakes are reset, the second person loosens the hold on the sling that is wrapped around the carabiner (or connected with a Münter hitch). This allows the load to slowly transfer back to the lowering rope, so the descent can continue. (The prusik sling must be long enough to allow for the slack introduced into the system when passing the knot.)

RAISING THE VICTIM

Lowering a person puts the force of gravity on the side of the rescuers, and therefore it's the preferred way to go, but sometimes there's no alternative to raising a victim up a steep face. Rescuers then have a choice of two general methods: the prusik system, which depends upon the victim's own efforts, and the pulley system, in which rescuers do the lifting.

These systems work on steep rock, snow, or ice, but they are usually associated with crevasse rescue. (Several versions of these systems are described in full in Chapter 13.) The same safety precautions that apply to lowering injured climbers apply to raising them. Whenever possible, safeguard the injured person with the use of backup anchors, safety prusiks, independent belays, and with padding or other measures to prevent ropes from being cut on sharp edges.

In the prusik system, the climber carries out a self-rescue by ascending in slings that are tied to the rope with prusik knots or other friction knots or that are attached with mechanical ascenders. This is an exhausting technique and has limited use in evacuating a seriously ill or injured person.

For a pulley system, rescuers usually use the Z-pulley, the most mechanically efficient of the basic pulley methods. There are some precautions to observe in using the Z-pulley: establish a main anchor that is bombproof. Keep extra prusik slings handy for replacements if a prusik in the system jams—and have a knife ready to cut away the jammed sling. (Caution: ropes and slings under tension cut very easily, so always cut away from other ropes.) Keep in continuous communication with the person you are raising.

Also be careful that the haulers don't pull too zealously on the rope. The Z-pulley is a powerful multiplier of forces, and it's possible to yank out an anchor, break a rope, or further injure the climber by pulling too hard against excessive friction or an unexpected obstruction.

Many rescuers prefer prusik knots to mechanical ascenders in a Z-pulley, because of the possibility the ascender could fail or could damage the rope. Give the prusik at least three wraps around the rescue rope. Each time you reset the Z-pulley, check that the prusik is holding securely.

TRAVERSING

If the descent deviates much from a route that is straight down the fall line, moving an injured person becomes very difficult. Try to avoid highly technical, exposed traverses, using them only as a last resort.

A pendulum technique is useful on terrain where rescuers can traverse overhead. For this method, suspend the injured person from an anchored rope. With a second rope, also anchored above, pull the victim sideways. Gradually release tension on the first rope as the victim pendulums to a position beneath the anchor of the second rope. Repeat the procedure if you need to traverse farther. As you pull on the pendulum rope, remember that ropes stretched horizontally have a tendency to snag and to knock rocks loose, and that they develop high stress under load. Victim and rescuers alike should be wearing helmets.

HAZARDS

Rescuers face the same hazards as climbers in general—hazards from objective environmental conditions such as storms, rockfall, cold, and high altitude, or from subjective human factors such as inadequate training and poor judgment. Dealing with any of these hazards greatly complicates a high-angle rescue.

Rescuers and climbers can minimize the impact of a storm or other objective hazard with proper equipment and contingency training. Ask the big "What if" questions before you leave on a trip, to be sure you have thought through the possible consequences of cold weather or high altitude or other hazards and are ready for them.

Take every possible precaution to guard against hazards as you raise or lower a person. If there is any doubt, confusion, or major disagreement on what is to be done, stop and reconsider the entire situation. Be especially wary of rockfall during raising and lowering operations. Wear helmets.

Subjective hazards exist when a person's skill, conditioning, or other qualities fall short of what is needed for safety on a particular climb. You can exercise a good deal of control over subjective hazards through planning and training before a climb, and by keeping alert during a climb to such hazards in yourself or others in the party. Dealing with the subjective hazards at the start of a rescue can minimize problems from objective hazards.

TRANSPORT ON NON-TECHNICAL TERRAIN

In many rescues the hardest job begins when the steep terrain is past and the ropes are put away. No longer aided by gravity, the party must carry its burden, very fatiguing work on rough ground. Under some conditions, however, a few simple techniques extend the capacity of the small party so that it need not call for help.

SHORT-DISTANCE CARRIES

Four-hand seat: This technique, useful for very short distances, requires two carriers who are the same height. The carriers grasp their own right wrist with their left hand, palms down. With the right hand, they grasp their partner's left wrist, forming a seat for the incapacitated person (fig. 17-6).

Ice-axe carry: This method permits longer carries than the four-hand seat. Carriers wearing rucksacks stand side by side, with the bundled shafts of two long-shaft ice axes supported between them in their pack straps. The person being carried sits on the padded shafts, arms over the carriers' shoulders (fig. 17-7).

Back carries: A strong climber can carry a person on his back for a considerable distance if the weight is distributed properly. The two back carries described earlier in this chapter—using webbing or a coiled rope—work well. The rucksack carry is another useful type of back carry. In this method, a large backpack is slit on the sides near the bottom so the carried person can step into it like a pair of shorts.



Fig. 17–6. Four-hand seat carry



Fig. 17–7. Ice-axe carry

LONG-DISTANCE CARRIES

A stretcher improvised from rope can make it possible to carry a person long distances over nontechnical ground. But before doing this, carefully consider the fact that evacuation on an improvised stretcher is usually very rough on the victim. If there is a chance that further injury will result, wait until trained rescuers with proper equipment get there.

Here is how to make a stretcher from a climbing rope, as shown in figure 17-8: Place the rope (150 feet is best) on the ground. From its exact center, make sixteen 180-degree bends, eight extending on each side of the center. The distance between bends should be about as wide as the person who will be carried, with the full sixteen bends approximately as long as that person.

Bring one rope end around each side of the stretcher, next to the bends. Tie a clove hitch in the rope section adjacent to each bend; insert the bend through the loops of the clove hitch. Continue tying clove hitches and inserting bends until all the bends are bound within clove hitches. Leave a small loop between the apex of each bend and the knot; insert the remaining rope through these loops until the entire remainder is strung around the stretcher. Snug up the knots, tie off the rope ends, and pad the area that will support the person from neck to hips.

Have one of the rescuers try out any improvised stretcher to decide if it needs more padding or support, keeping the victim's comfort in mind.

EVACUATION ON SNOW

On snow, it's particularly urgent to protect an injured person from heat loss while you give first aid and plan the evacuation. Wrap the person in



Fig. 17–8. Climbing rope stretcher

extra clothing. Use pads, packs, or ropes as insulation from the snow. If the victim cannot be moved quickly, build a trench or low wall as a temporary wind shield. Of course, if you must stay overnight, the party will put up a tent or dig a snow cave.

If possible, move the victim to a sheltered location, preferably below timberline. Do this as soon as you have given first aid and prepared the person for travel.

An ill or injured climber may be able to get down a snow slope by using some form of assisted sitting glissade. Sometimes the climber can be lowered in a sitting glissade position. Or a rescuer can sit in front of the victim, smoothing the track, the two tied together and on belay. A victim in relatively good condition can be roped in with two or three companions who then glissade slowly as a team, constantly under control.

Rescuers can set up anchors for belays and for braking devices by using pickets, bollards, or deadman anchors such as snow flukes or buried ice axes. (Chapter 12 gives the details on setting up these anchors.) The boot-axe belay usually is not strong enough for use in rescues. Moats often provide superb anchor positions for lowering.

Snow evacuations often involve climbers rescued from an avalanche or a crevasse. (Techniques of avalanche rescue are covered in Chapter 12, and crevasse rescue is explained in Chapter 13.)

ORGANIZED RESCUE OPERATIONS

Mountain rescues are often mounted by professional rescue agencies or by highly trained volunteers. This chapter has emphasized rescue efforts that can be undertaken by climbing parties themselves. Organized rescue groups bring the benefits of wide experience and training, plus specialized equipment and techniques, including air rescue.

RESCUE ORGANIZATIONS

In the Alps, with its large corps of professional guides, organized rescue is all part of the business. In North America, mountain rescues are commonly carried out by volunteer organizations. The volunteers use their rescue training and knowledge of the local mountains to analyze a situation, decide a course of action and carry it through. They round up the needed equipment and rescuers from among local climbers who are on call for emergencies. In the state of Washington, for example, Mountain Rescue units are headquartered in the major cities. Rescue evacuations usually require a leader and from eighteen to twenty-four stretcher bearers, unless a helicopter does the job.

In most areas, official responsibility for rescue rests with an agency such as the county sheriff's department or the National Park Service, and volunteer rescue units work closely with these authorities.

SPECIALIZED EQUIPMENT

Rescue organizations use equipment specially designed to make their task easier. Although these items are not standard climbing gear, every climber should know what they are and what can be done with them.

Most important is a rigid stretcher of fiberglass or metal. A well-known design is the Stokes litter, which has a framework of metal tubing and a wire-mesh basket that closely fits the outlines of a person's body. The Stokes, although heavy, works well on technical evacuations and general carryouts. Fiberglass stretchers with a metal framework are lighter and can be broken down into sections for ease of carrying, especially valuable attributes for technical rescues. They are widely used on snow because they slide easily. Many stretchers permit attachment of a wheel for trail or snow carryouts.

For raising and lowering, rescuers sometimes employ hand-operated or engine-powered portable winches with wire cables or non-stretch ropes that are several hundred feet long. The ropes are lighter than wire cable and require no specialized equipment to use other than standard climbing gear.

Two-way radio communication greatly facilitates mountain rescue, if the gear is lightweight and efficient. However, it can be difficult to get reliable transmission and reception through heavy timber, intervening ridges, long distances, and bad weather.

HELICOPTER RESCUE

Climbers can communicate with air rescuers by constructing international ground symbols, which are familiar to most pilots (fig. 17-9). The symbols, signaling such information as the need for a doctor, should be 8 to 12 feet high with lines 1 foot wide. It's a good idea to keep a copy of the symbols in your first-aid kit.



Fig. 17–9. Ground-to-air signals

The helicopter revolutionized mountain rescue. It can pluck climbers from cliffs and glaciers and get them to hospitals in hours rather than the days sometimes required by ground transport, often meaning the difference between life and death. A helicopter takes on a load by landing, or by hovering and lowering a sling or a stretcher on a cable attached to a power winch. Climbers need to know some of the requirements and limitations of helicopter operation.

The most important factors governing a helicopter's ability to evacuate are visibility, wind velocity and turbulence, and air density. In mountain flight, continual visual contact with the ground is essential, so a helicopter can't operate in poor weather. It can maneuver safely in winds up to about 35 miles per hour, with a wind of about 10 miles per hour being better than still air. A dangerous turbulence usually accompanies high wind. The altitude to which a helicopter can fly depends on air density, which decreases as either altitude or temperature increases. Thinner air reduces the lifting force of the rotor blades.

The people on the ground should try to prepare a helicopter landing zone that has a 360-degree choice of landing and takeoff direction, so the pilot can land or take off into the prevailing wind. Clear an area at least 100 feet in diameter around the touchdown pad, removing obstacles such as brush and loose objects. Make the area as level as possible, with a slope of not more than 8 percent. Try to establish a landing zone where the helicopter can drop downward as it takes off rather than having to fly upward.

Mark the landing area with colored tape or brightly colored objects, and use streamers, plastic ribbon, or smoke to indicate wind direction. Put the wind indicators at the edge or downwind of the landing area so they don't obstruct the pilot's vision. It is urgent that all loose items near the landing zone be well secured, especially those used to mark the boundaries. If the helicopter lowers equipment, allow it to touch ground first to dissipate static electricity.

A couple of arm signals can be important. If there is a last-minute danger to the helicopter, signal "do not land" by holding your arms straight out horizontally from your sides and moving them to over your head several times. If your party has been unable to mark wind direction or landing site, members of the group should stand with arms extended toward the landing area and the wind at their backs. This signals to the pilot: "Land where we are pointing; our backs are into the wind."

Several safety precautions will minimize hazards from a helicopter. Stay away from cliff edges or anywhere else where you might be injured if you are knocked over by the helicopter rotor's powerful down-wash winds. Watch out for flying debris, use eye protection, and have all gear safely secured. Approach the helicopter only after signalled to do so by the pilot or a crew member, and then duck down and approach or leave from near the front so the pilot can always see you. Don't approach or leave the helicopter from any side where the ground is higher than where the helicopter is standing, and beware of the rear rotor, which is nearly invisible when spinning. If you're not needed near the helicopter, stay at least 75 feet away from the landing area.

Keep the victim's safety in mind as you prepare for the helicopter evacuation. Secure the person and any gear so there are no loose straps, ropes, or clothing; shield the person's face and eyes from flying debris and assure proper respiration. It takes time to secure an ill or injured climber to a stretcher. Remember that the person's safety is at stake and don't be rushed into this critical job just because the helicopter is waiting. Rescuers who put their training to use in a caring and efficient manner can often bring a happy ending to what may have been a long and difficult rescue effort.

◆ Appendix 1 ◆

THE CYCLE OF SNOW

Snow crystals form in the atmosphere when water vapor is precipitated at temperatures below freezing. They form around centers of foreign matter, such as microscopic dust particles, and grow as more ice formed from atmospheric water vapor is deposited on them. Tiny water droplets may also contribute to snow crystal growth. The crystals generally are hexagonal, but variations in size and shape are almost limitless and include plates, columns, and needles. The particular shape depends on the air temperature and the amount of water vapor available.

When a snow crystal falls through air masses with different temperature and water-vapor conditions, more complex or combined types may develop. Crystals in air that has a temperature near freezing stick together to become snowflakes, aggregates of individual crystals. When snow crystals fall through air that contains water droplets, the droplets freeze to the crystals, forming the rounded snow particles called graupel (soft hail).

The density of new-fallen snow depends on weather conditions. The lowest-density snow (lightest, driest) falls under moderately cold and very calm conditions. At extremely low temperatures, the new snow is fine and granular, with somewhat higher densities. The general rule is that the higher the temperature, the more dense (heavier, wetter) the snow, though density varies widely in the range of 20 to 32 degrees Fahrenheit (–7 to 0 degrees Celsius). The very highest densities are associated with graupel or needle crystals falling at temperatures near freezing. The percentage of water in new-fallen snow ranges from 1 to 30 percent, sometimes even higher, with the average for mountain snowfall being 7 to 10 percent. Wind affects snow density, for high winds break up falling crystals into fragments that pack together to form dense, fine-grained snow. The stronger the wind, the denser the snow.

Two types of snow form right at ground level.

Rime is the dull white, dense deposit formed from the freezing of droplets of water on trees, rocks, and other objects exposed to the wind. Rime deposits build up toward the wind. Rime may form large feathery flakes or a solid incrustation, but



Fig. App. 1–1. Snow crystal forms: a, plates; b, stellar crystals; c, columns; d, needles; e, spatial dendrites (combinations of feathery crystals); f, capped columns; g, irregular particles (compounds of microscopic crystals); h, graupel (soft hail); i, sleet (icy shell, inside wet); j, hail (solid ice).

lacks regular crystalline patterns.

Hoarfrost, on the other hand, displays distinct crystalline shapes: blades, cups, and scrolls. Hoarfrost forms on solid objects by the process of sublimation—the direct conversion of atmospheric water vapor to a solid. Deposited on top of snow, it is known as surface hoar and is generally produced during a cold, clear night. The crystals appear fragile and feathery, and sparkle brilliantly in sunlight. A heavy deposit of surface hoar makes for fast, excellent skiing.

AGING OF THE SNOWCOVER

Snow that remains on the ground changes with time. The crystals undergo a process of change—metamorphism—that results in smaller, simpler forms and a snowpack that shrinks and settles. Because the snowpack generally becomes more stable over time, mountaineers find it useful to know the recent history of weather and snow conditions in an area.

Metamorphism begins the moment that snow falls and lasts until it melts. The equilibrium growth process gradually converts the varied original forms of the crystals into homogeneous rounded grains of ice (old snow). Both temperature and pressure affect the rate of change. When temperature within the snow is near the freezing point (32 degrees Fahrenheit; 0 degrees Celsius), change is rapid. The colder it gets, the slower the change, and it virtually stops below –40 degrees Fahrenheit (–40 degrees Celsius). Pressure from the weight of new snowfall over an older layer speeds changes within the layer. Snow that has reached old age—surviving at least one year and with all original crystals now converted into grains of ice—is called firn (or névé). Any further changes to firn snow lead to formation of glacier ice.

Another type of metamorphism takes place when water vapor is transferred from one part of the snowpack to another by vertical diffusion and is deposited in the form of ice crystals with different characteristics than those of the original snow. This kinetic growth process produces faceted crystals. When the process is carried to completion, the crystals often have a scroll or cup shape, appear to be layered, and may grow to considerable size. They form a fragile structure that loses all strength when crushed, and becomes very soft when wet. This weak and unstable snow form is known as depth hoar, popularly referred to as sugar snow. The necessary conditions for its formation are a large difference in temperature at different depths in the snow and sufficient air space so that water vapor can diffuse freely. The conditions are most common early in winter when the snowpack is shallow and unconsolidated.

As the snowpack on a slope moves very slowly downhill under the influence of gravity, the upper layers travel faster than those next to the ground. This internal deformation, called creep, proceeds most rapidly at the freezing point and diminishes with decreasing snow temperature. The entire snowpack also glides on the ground when



Fig. App. 1–2. Destructive metamorphism of a snow crystal the interface between snow and earth is at the melting point. If the ground is smooth (covered with grass, for instance), gliding is the dominant form of snow motion. The slow combined motions of creep and glide are so unhurried that they can't be noticed by the casual observer, but they cause the snowcover to exert enormous forces on obstacles in its path. The stresses produced by uneven snow creep are an important factor in avalanche formation.

Variations in the strength of snow are among the widest found in nature, with strength continually changing due to metamorphism, temperature differences, and wind. The hardness of wind-packed old snow may be fifty thousand times that of fluffy new snow. An increase in hardness is always associated with wind-drifted snow, or snow mechanically disturbed in any fashion, which undergoes a process known as age-hardening for several hours after it is disturbed.

SURFACE FORMS OF SNOWCOVER

Snow and ice undergo endless surface changes as they are worked on by wind, temperature, sun, freeze-and-thaw cycles, and rain. Following is a rundown on most of the surface permutations mountaineers typically encounter.

Powder snow: This is a popular term for light, fluffy new-fallen snow. However, powder snow is more specifically defined as new snow that has lost some of its cohesion due to the recrystallizing effects of steep temperature differences in the surface layers. These changes occur only during periods of persistent low temperatures. The changed snow is loose and powdery, commonly affords good skiing, and may form dry loose-snow avalanches.

Corn snow: After the advent of melting in early spring, a period of fair weather may be followed by formation of coarse, rounded crystals on the snow surface, often called corn snow. The crystals are formed from the daily melting and refreezing of the snow. Only when the same surface layer continues to melt and refreeze does true corn snow develop. When corn snow thaws each morning after the nighttime freeze, it's great for skiing and step-kicking.

Rotten snow: Rotten snow is a spring condition characterized by soft, wet layers that offer little support to the firmer layers above. In its worst forms, it will not support even the weight of a skier. Snow that promises good spring skiing in the morning, while there's some strength in the crust, may deteriorate to rotten snow later in the day. Rotten snow forms when lower layers of depth hoar become wet and lose what little strength they have. It's a condition that often leads to wet loose-snow or slab avalanches running clear to the ground. Continental climates, such as those of the American Rockies, often produce rotten snow, which is much less likely to occur in the more stable maritime snowcovers of the Pacific coastal ranges of the United States and Canada.

Meltwater crust: This is a snow crust formed when water melted at the surface is refrozen and bonds snow crystals into a cohesive layer. A common variety is sun crust, so called because the source of heat for melting is solar radiation. Heat to permit meltwater crusts also comes from warm air or condensation at the snow surface. In winter and early spring the thickness of a sun crust is usually determined by the thickness of the surface layer where meltwater is formed in otherwise dry snow. In later spring and summer when free water is found throughout the snowcover, the thickness depends on how cold it gets at night.

Wind crust: In contrast to meltwater crust is the crust caused by action of the wind. After the surface snow layers are disturbed by the wind, age-hardening takes place. Fragments of snow crystals broken by the wind are compacted together when they come to rest, adding to the process. The hardening is compounded when the wind provides heat, particularly through water vapor condensation. Even when there is not enough heat to cause melting, the warming of the disturbed surface layer, followed by cooling when the wind dies, provides additional metamorphic hardening.

Firnspiegel: The thin layer of clear ice some-



Fig. App. 1–3. Surface features on snow: left, suncups; center, sastrugi; right, nieve penitentes.

times seen on snow surfaces in spring or summer is called firnspiegel. In the right conditions of sunlight and slope angle, its reflection produces the brilliant sheen of "glacier fire." Firnspiegel forms when solar radiation penetrates the snow and causes melting just below the surface at the same time that freezing conditions prevail at the surface. Once formed, it acts like a greenhouse, bringing melting of the snow beneath while the transparent ice layer remains frozen at the surface.

Verglas: This is a layer of thin, clear ice formed from water freezing on rock. It is most commonly encountered at higher elevations in the spring or summer when a freeze follows a thaw. The water comes from rainfall or melting snow. Verglas may also be formed directly by supercooled raindrops freezing as they fall onto exposed objects ("freezing rain," also sometimes inaccurately called "silver thaw").

Drainage patterns: After melting has begun in spring, drainage patterns formed by the runoff of water appear on snowfields. However, the actual flow takes place within the snowpack, not on the surface. As snow melts at the surface, the water formed percolates downward until it encounters impervious layers, which deflect its course, or highly permeable layers, which it can easily follow. Much of the water also reaches the earth beneath. The water that flows along within the snow often causes a branching pattern of channels on the surface. This happens because the flowing water accelerates the snow settlement around its channels, which are soon outlined by depressions at the surface. The dirt that collects in these depressions absorbs solar radiation and accentuates them further by differential melting.

Suncups: Suncups are depressions in the surface of summer snowfields, and they can vary in depth from 1 inch to 2 feet or more. They always occur as an irregular pattern covering an entire snowfield and form whenever weather conditions combine to accentuate surface irregularities. There must be motion of air to cause greater heat and mass transfer at high points of the snow than at the hollows. The air must be dry enough to favor evaporation, and there must be an additional source of external heat, usually the sun.

Under these circumstances, more heat reaches the points than the hollows but a larger proportion causes evaporation rather than melting. Because evaporation of snow demands more than seven times as much heat as melting, less snow is lost from the high points in the form of vapor than is lost from the hollows in the form of meltwater. The hollows melt faster than the points evaporate, and suncups form. They are enhanced by differential melting when dirt in the hollows absorbs solar radiation. The suncups also melt faster on the south (sunny) side in the Northern Hemisphere, so the whole suncup pattern gradually migrates northward across its snowfield.

Warm, moist winds tend to destroy suncups by causing faster melt at the high points and edges. A prolonged summer storm accompanied by fog, wind, and rain will often erase a suncup pattern completely, but they start to form again as soon as dry, fair weather returns.

Nieve penitentes: When suncups grow up, they become nieve penitentes (Spanish for "penitent snow"). They are the pillars produced when suncups intersect to leave columns of snow standing between the hollows. They are peculiar to snowfields at high altitudes, where radiation and atmospheric conditions conducive to suncups are intense. Nieve penitentes reach their most striking development among the higher peaks of the Andes and the Himalaya, where they may get several feet high and make mountain travel very difficult. The columns often slant toward the midday sun.

Wind and erosional features: The surface of dry snow develops a variety of erosional forms from the scouring of wind, such as the small ripples and irregularities on winter snowcover. On high ridges and treeless arctic territory, under the full sweep of the wind, these features attain considerable size. Most characteristic are the wavelike forms, with sharp prows directed toward the prevailing wind, known as sastrugi. A field of sastrugi—hard, unyielding, and as much as several feet high—can make for tough going. High winds over featureless snow plains also produce dunes similar to those found in desert sand, with the crescent-shaped dune, or barchan, being most common.

Cornices: Cornices are deposits of wind-drifted snow on the lee edge of ridges or other features. They offer a particular hazard as they overhang, forming an unstable mass that may break off



Fig. App. 1–4. Formation of cornices

from human disturbance or natural causes. Falling cornices are dangerous in themselves and also can set off avalanches.

During storms the precipitated snow furnishes material for cornice formation. Cornices also are formed or enlarged by material blown in from snowfields that lie to windward. As a general rule, cornices formed during snow storms are softer than those produced by wind drift alone.

THE FORMATION OF GLACIERS

Glaciers form for a rather simple reason. Snow that does not melt or evaporate during the year is carried over to the next winter. If snow continues to accumulate year after year, eventually consolidating and beginning a slow downhill movement, a glacier is formed.

Within the old snow (the firn, or névé), the metamorphic conversion of snow crystals into grains of ice has been completed. Now the grains of ice are changed into glacier ice in a process called firnification. Firn turns into glacier ice when the air spaces between the grains become sealed off from each other so that the mass becomes airtight.

Part of the glacier ice is formed by refreezing of percolating meltwater each spring when the lower snow layers are still at temperatures below freezing. This refrozen meltwater forms ice layers within the firn. Therefore, by the time compaction and metamorphism have prepared an entire area of firn for conversion to glacier ice, it may already contain irregular bodies of ice.

Once glacier ice has formed, metamorphism does not cease. Through crystallographic changes, some of the ice grains packed in the glacier continue to grow at the expense of their neighbors, and the average size of the ice crystals increases with age. Large glaciers, in which the ice takes centuries to reach the terminus, may produce crystals more than 1 foot in diameter, gigantic specimens grown from minute snow particles.

In our imagination, we can follow the birth of a simple valley-type alpine glacier. Picture a mountain in the Northern Hemisphere that has no glaciers. Now suppose climatic changes that cause snow to persist from year to year in a sheltered spot on a northern exposure.

From the first, snow starts to flow toward the valley in the very slow motion called creep. New layers are added each year, the patch of firn snow grows deeper and bigger, and the amount of snow in motion increases. The creeping snow dislodges soil and rock, while the melting, refreezing, and flow of water around and under the snow patch add to impact on the surroundings. This small-scale process of erosion eventually leads to formation of a hollow where the winter snows are deposited in deeper drifts. The snow gets to be 100 feet deep or so. The lower layers have nearly turned to glacier ice, while the increasing pressure of the many upper layers of firn causes the flow to accelerate. A glacier is born.

With continued nourishment from heavy winter snows, the glacier flows toward the valley as a stream of ice. At some point in its descent, the glacier reaches an elevation low enough and warm enough that no more new snow accumulates. The glacier ice begins to melt. Eventually the glacier reaches the point, even lower and warmer, at which all ice carried down from above melts each year. This is the lower limit of the glacier.

Glaciers vary from stagnant masses with little motion to vigorously flowing rivers of ice that transport large masses each year from higher to lower elevations. Glaciers in relatively temperate climates flow both by internal deformation and by sliding on their beds. Differences in speed within the glacier are somewhat like that in a river, fastest at the center and surface and slower at the sides and bottom where bedrock creates a drag. Small polar glaciers present a striking difference in appearance from their temperate cousins, for they are frozen to their beds and can flow only by internal deformation. The polar glaciers look much like flowing molasses, while temperate glaciers are rivers of broken ice.

◆ Appendix 2 ◆
RATING SYSTEMS

The development of rating systems began in the late-nineteenth and early-twentieth centuries in Britain and Germany. In the 1920s, Willo Welzenbach defined a rating system, using Roman numerals and the British adjectival system to compare and describe the routes in the Alps, which today forms the basis of the UIAA rating system. Today there are more than seven major rock, four alpine, four ice, and two aid-climbing rating systems used worldwide. This appendix will briefly describe some of these.

A rating system is a tool that helps a climber choose a climb that is within his or her abilities or presents a desirable level of challenge. The rating of a climb also reflects the type of equipment needed for the climb.

Rating climbs is a subjective task, which makes consistency between climbing areas elusive. The rating of climbs assumes good weather and the best equipment available. Variables that affect the rating of climbs include: how the local climbers who put up the routes interpret the rating system, how they want the area to be recognized, the type of rock or ice, and the type of climbing (e.g. face, crack, or friction rock climbing; front pointing or French technique ice climbing). The physical size and strength of the climber also affects how he or she thinks a climb should be rated. Ideally, a route is rated by consensus. A guidebook author typically has not climbed every route described and therefore has to rely on the opinions of others. In some cases, a route may have been done only once. When climbing in an area for the first time it is best to start at a lower level than normal in order to become familiar with the rock or ice, the type of climbing, and how the rating system reflects the qualities of the climbing.

NORTH AMERICAN RATING SYSTEMS

Rock climbing

Free climbing

In 1937, a modified Welzenbach rating system was introduced in America as the Sierra Club System. In the 1950s this system was modified to more accurately describe the technical climbing that was being done at Tahquitz Rock in California by adding a decimal figure to class 5 climbing. This has become known as the Yosemite Decimal System (YDS). This system categorizes terrain according to the techniques and equipment required to travel that terrain.

Class 1: A hiking scramble to a rocky gradient; generally hands are not needed.

Class 2: Involves some scrambling and likely use of hands; all but the most inexperienced and clumsy will not want a rope.

Class 3: Moderate exposure may be present; simple climbing or scrambling with frequent use of hands. A rope should be available.

Class 4: Intermediate climbing is involved and most climbers want a rope because of *exposure*. A fall could be serious or fatal. Another definition is that it begins when all beginners and most average climbers will want and should have a *belay*. Usually natural protection is easily found.

Class 5: Climbing involves use of a rope and natural or artificial protection by the leader to protect against a serious fall.

The extension of fifth-class climbing originally was meant to be a closed-ended scale of 5.0–5.9. The rising standards in the 1970s, however, led to a need for an open-ended scale. Strict decimal protocol was abandoned and 5.10 (pronounced "five ten") was adopted as the next highest class. Classes 5.10–5.14 (as of 1991) have been subdivided into four parts, a–d. (See Table 1.) A (+) or (–) is sometimes used as a rougher means to refine a classification. For example, 5.12(+) equates to 5.12c or 5.12d. It also can be used to indicate a sustained pitch (+) or a pitch of one or two moves of a given rating (–) (e.g. 5.8(–)).

The extension of fifth-class climbing cannot be defined accurately, either quantitatively or qualitatively. The following general guidelines to the extension of fifth-class climbing will aid the climber who is unfamiliar with the YDS descriptions.

5.0–5.4: A physically fit climber can usually climb at this level with little or no rock climbing skills, using only natural ability.

5.4–5.7: Requires use of rock-climbing techniques such as hand jamming and/or strength.

5.7–5.9: Rock-climbing shoes, good skills, *and* some strength are usually necessary at this level.

5.10 and above: Beyond rock shoes, excellent skills, and strength, this level requires training for climbing techniques and commitment of time to maintain that level.

The YDS rates only the hardest move on a pitch. The YDS gives no indication of overall difficulty, protection opportunity, exposure, runout, or strenuousness. Some guidebooks, however, will rate a pitch harder than the hardest move if it is very sustained at a lower level. A guidebook's introduction should explain any variation of the YDS used. Some guidebooks give routes two ratings, one for the hardest move and one for the overall difficulty of the pitch.

Because the standard use of the YDS defines only the hardest move, a *seriousness rating* was introduced by James Erickson in 1980 to indicate relative danger of a climb:

PG-13: Protection is considered adequate, and if properly placed, a fall would not likely be long or of consequence.

R: Protection is commonly considered inadequate. The possibility exists of a long fall onto good protection or a shorter fall onto poor protection, which may pull. A falling leader will probably suffer injuries.

X: Protection is commonly considered extremely poor. There exists the possibility of long falls, pulling several pieces of protection and causing serious injury or death.

Quality ratings are common in many guidebooks. The number of stars indicates the aesthetics of a particular climb. No standard has been set, so each area and guidebook have their own definitions. These star ratings are useful in guiding a climber who is new to the area to the quality routes.

The National Climbing Classification System (NCCS) for rating free climbing proposed in 1963, and using F1–F10, is largely out of use. Many old guidebooks used this system (see Table 1).

Aid climbing

Rating aid moves or climbs is different than rating free climbing in that it is not an open-ended system, nor do the ratings change with improved technology. The aid-climbing rating system indicates quality of protection and the difficulty of placing that protection. The scale is A0 or C0–A5 or C5, with A referring to the use of pitons and/or chocks, and C referring to clean aid climbing (chocks only), although the use of C has not been universally accepted. This system is used throughout the world except in Australia, which uses M0 (mechanical) to M8, with similar definitions as A0–A5.

A0 or C0: Aid points are fixed.

A1 or C1: Aid placements are solid and easily placed.

A2 or C2: Placements are awkward to place and

Fig. App. 2–1. Comparison of rock classification systems

UIAA	French	YDS	Australian	E. German	Brazilian	NCCS	British	
I	1	5.2		I		F4	3a	VD
II	2	5.3	11	II		F5	3b	
III	3	5.4	12	III	II		3c	HVD
IV	4	5.5		IV	IIsup	F6	4a	MS S
V-	5	5.6	13	V	III		4b	HS
V		5.7	14	VI	IIIsup	F7		VS
V+			15				4c	
VI-		5.8	16	VIIa	IV	F8		HVS
VI	6a	5.9	17 18	VIIb	IVsup	F9	5a	
VI+	6a+	5.10a	19	VIIc	V	F10		E1
VII-	6b	5.10b 5.10c	20	VIIIa	Vsup VI		5b	E2
VII	6b+	5.10d	21 22	VIIIb	VIsup	F11	5c	
V11+	6c 6c+	5.11a	23	VIIIc IXa	VII	F12		E3
VIII-	7a	5.11b 5.11c	24	IXb	VIIsup		6a	E4
VIII	7a+	5.11d	25	IXc	VIII	F13		
VIII+	7b	5.12a 5.12b	26	Xa	VIIIsup	F14	6b	E5
IX-	7b+ 7c	5.12c	27	Xb		F15	6c	E6
IX	7c+	5.12d 5.13a	28	Xc		F16	7a	
IX+	8a	5.13b	29					E7
X-	8a+	5.13c	30 31					
X	8b 8b+	5.13d	32					
X+	8c	5.14a	33					

holds less.

A3 or C3: Aid placements will hold a short fall.
A4 or C4: Aid placements hold only body weight.
A5 or C5: Entails enough A4 placements to risk a very substantial fall.

Bouldering

Bouldering has its own rating system. It is a floating scale that moves upward as the standards rise. B1 is always the hardest YDS classification in existence, and B3 is always a climb that has never been repeated. In 1991, the bouldering ratings could be compared to the YDS as follows:

B1: 5.14
B2: above 5.14
B3: the climb is unrepeated

Alpine climbing

The National Climbing Classification System (NCCS) describes the overall difficulty of a multi-pitch alpine climb in terms of time and technical rock difficulty. It takes the following factors into account: length of climb, number of hard pitches, average pitch difficulty, difficulty of hardest pitch, commitment, routefinding problems, ascent time, rockfall, icefall, and weather problems. The approach and remoteness of an area also influence the grade of a climb, which will be regional and, thus, guidebook-dependent. It should be emphasized that with increasing grade an increasing level of psychological preparation and commitment is necessary. This system assumes a competent party for the level of climbing expected.

Grade I: Normally requires only several hours to do the technical portion; can be of any technical difficulty.
Grade II: Normally requires a half day for the technical portion; can be of any technical difficulty.
Grade III: Normally requires a full day for the technical portion; can be of any technical difficulty.
Grade IV: Expected to take one long hard day of technical climbing (longer on the first ascent); the hardest pitch is usually no less than 5.7.
Grade V: Expected to take an average one-and-a-half days; the hardest pitch is rarely less than 5.8.
Grade VI: Usually takes two or more days; generally includes considerably difficult free climbing and/or aid climbing.

The times given do not especially apply to glacier/snow/ice climbs. The type of climb affects which factors are emphasized. It is important to study a route description to understand which factors make it the grade that it is.

Ice climbing

The variable conditions of snow and ice climbing make rating climbs difficult. The only two factors that do not vary greatly from year to year are length and steepness of the ice. Snow depth, thickness of ice, and temperature affect the condition of the route; these factors plus the nature of the ice and whether or not it offers good protection affect its difficulty.

Three rating systems have been introduced in North America: the New England Ice Rating System, first described in the early 1970s by Rick Wilcox, another in 1979 by Jeff Lowe, and the third in 1988 by Albi Sole. All use a modified version of the Scottish system (composed of Grades 1–6), which consists of two elements referred to as the *seriousness grade* (or *overall grade* [Lowe] or *commitment rating* [NEI]) and the *technical grade*.

Depending on the terrain being rated, water or alpine ice may be denoted as WI or AI, respectively. *Water ice* may be a seasonal frozen waterfall or nonporous ice found in the alpine environment. *Alpine ice* is permanent ice of a porous nature generally in the form of consolidated snow such as that usually found in glaciers.

The *technical grade*, as defined by Sole, rates the single most difficult pitch, taking into account the sustained nature of the climbing, ice thickness, and natural ice features, such as chandeliers, mushrooms, or overhanging bulges.

Grade 1: Walking up ice with only the use of crampons.
Grade 2: A pitch of 60–70 degree ice, reasonably

consistent, with few short, steep steps. Good protection and belays.

Grade 3: Sustained 70–80 degree ice, usually thick and solid. May contain short, steep section, but will have good resting places and offer good protection and belays.

Grade 4: Sustained 75–85 degree ice, separated by good belays or a less steep pitch with significant vertical sections. Generally good-quality ice, offering satisfactory protection.

Grade 5: A noticeably more strenuous pitch of good but steep (85–90 degree) ice. May be considered the equivalent of 5.9 rock in terms of relative technical ability required.

Grade 6: A very steep, strenuous pitch with few resting places and often a hanging belay. The ice may not be of top quality and protection may be dubious.

Grade 7: A pitch of near vertical ice, which may be thin, of poor quality, and doubtful adhesion to the rock. Protection difficult or nonexistent.

The *Seriousness grade*, as defined by Sole, takes into account the length, continuity, remoteness, hazards, and difficulty of descent; it is not, however, totally unaffected by technical difficulty.

Grade I: A short climb close to the road with bombproof belays and an easy descent.

Grade II: A 1- or 2-pitch climb within easy reach of a vehicle, little objective danger, and easy descent by rappel or downclimbing.

Grade III: A multipitch route at low elevation, which may take several hours, or a route with a long approach on foot or ski, demanding good winter travel skills, or a route subject to occasional winter hazards. Descent usually by rappelling.

Grade IV: A multipitch route at higher elevations or in a remote region requiring mountaineering and winter travel skills. May be subject to objective hazards such as avalanches or rockfall. Descent may present difficulties and usually involves rappelling from bolts.

Grade V: A long climb on a high mountain face requiring a high level of competence and commitment. Subject to hazards of bad weather and avalanches. May have long approach or difficult descent.

Grade VI: A long multipitch route on a high alpine face, which only the best climbers will complete in a day. May include the logistical problems of winter alpine climbing.

Grade VII: The biggest and hardest Himalayan alpine-style climbs (Lowe definition).

The *New England Ice Rating System* is used extensively in New England and was developed for the water-ice climbing found there. This system applies to a normal winter ascent of the route in moderate weather conditions.

NEI 1: Low-angle water ice of 40–50 degrees, or long, moderate snow climbs requiring a basic level of technical expertise for safety.

NEI 2: Low-angle water-ice routes with short bulges up to 60 degrees.

NEI 3: Steeper water ice of 50–60 degrees with 70–90 degree bulges.

NEI 4: Short, vertical columns, interspersed with rests, on 50–60 degree ice; fairly sustained climbing.

NEI 5: Generally multipitch ice climbs with sustained difficulties and/or strenuous vertical columns, with little rest possible.

NEI 5+: Multipitch routes with a heightened degree of seriousness, long vertical sections, and extremely sustained difficulties—the hardest ice climbs in New England to date.

The *commitment rating* shows the time and logistical requirements of the climb.

I: Up to several hours.

II: About half a day.

III: A full day, up to 7 or 8 hours.

IV: A substantial undertaking; a very long day, possibly including a bivouac.

V: A big-wall climb of one and a half to two days. Could be done in a single day by a very fit team.

VI: Multiday big-wall climbs requiring more than two days.

VII: Big-wall ascents in remote alpine situations.

Ice climbing is relatively new in America so standards vary from area to area and guidebook to guidebook. Some guidebooks define their own rating system: *Bob's Route* IV, 5 (indicating seriousness and technical grade), *Bob's Route* (5) (indicating technical grade), and *Bob's Route* IV, WI5 (indicating overall grade, technical grade, and water ice). Most guidebooks do give the length of the technical ice climbing.

OTHER MAJOR RATING SYSTEMS

Many of the rating systems used throughout the world are very similar to one another, especially in Europe. Table 2 indicates which rating systems are used in which country.

Rock climbing

Australian

The Australian system uses open-ended numerics 1–33. See Table 1.

Brazilian

The rating of climbs in Brazil is composed of two parts. The first number gives the general level of difficulty of the route ranging from first to eighth grade (or degree), which is written as grade 5°. There is no comparison to the YDS for this part of the system. The second part gives the difficulty of the hardest free move (or sequence of moves without a natural rest) in roman numerals with sup (superior) added for greater accuracy. See Table 1 for comparison to the YDS. Ratings of climbs are written as 5° VI.

Fig. App. 2–2. Rating systems used throughout the world

COUNTRY	RATING SYSTEM
Australia	Australian
Brazil	Brazilian
Britain	British, IFAS
Canada	YDS, NCCS
East Germany	E. German, IFAS
France	French, IFAS
West Germany	W. German = "UIAA," IFAS
Italy	French, IFAS
Japan	UIAA, "NCCS"
Spain	"French," IFAS
United States	YDS, NCCS

Quotation marks denote that only slight modifications have been made to the system indicated.

British

The British classification system is comprised of two elements, the adjectival grade and the technical grade, and is expressed as, for instance, HVS 5a.

The *adjectival grade* describes the overall difficulty of a route, including factors such as exposure, how sustained the route is, seriousness, strenuousness, protection opportunities, and runout. Acronyms are used up to Extremely Severe. The need for an open-ended, less cumbersome system led to an alphanumeric adaptation, hence E1, E2, E3, etc.

Easy	E
Moderate	M
Difficult	Diff
Very Difficult	V. Diff
Hard Very Difficult	HVD
Mild Severe	MS
Severe	S
Hard Severe	HS
Very Severe	VS
Hard Very Severe	HVS
Extremely Severe	ES
subdivided as:	E1, E2, E3, etc.

The *technical grade* is defined as the hardest move on a particular route. This numeric component of the British system is also open-ended and is subdivided into a, b, and c (see Table 1).

The two grades are linked to each other. For example, the standard adjectival grade for a well-protected 6a, which is not particularly sustained, is E3. If the route is a bit run out then it would be E4; if it is really run out then it would be E5.

French

The French open-ended rating system currently extends from 1–8c. Starting at level 6, the ratings are subdivided a, a(+), b, b(+), c, and c(+). See Table 1.

Soviet Union

Currently, there is no rock-climbing classification system used in the Soviet Union. First ascents are often done by climbers from other countries who rate the climb according the rating system used in his or her own country.

UIAA

The UIAA rating system currently extends from I–X(+) with levels V–X subdivided into (–), (nought), and (+). It does not express length, time, seriousness, and dangers of the climb. See Table 1.

West German

The same as UIAA except uses arabic numbers (see Table 1).

Alpine climbing/ice climbing

Europe

The International French Adjectival System (IFAS) is an overall rating of alpine and ice climbs used primarily in the Alps. It expresses the seriousness of the route, including factors such as length, objective danger, how sustained it is, commitment, altitude, runouts, descent, and technical difficulty in terms of *terrain*. It has six categories that are symbolized by the first one or two letters of the French adjective used. It is further subdivided with the use of (+) or (–) or sup (superior) or inf (inferior).

F: *Facile* = easy. Steep walking routes, rock scrambling, and easy snow slopes. Crevasses possible on glaciers. Rope not always necessary.
PD: *Peu difficile* = moderate. Rock climbing with some technical difficulty, snow and ice slopes, difficult glaciers, and narrow ridges.
AD: *Assez difficile* = fairly hard. Fairly difficult and serious climbs, steep rock climbing, long snow/ice slopes above 50 degrees.
D: *Difficile* = hard. Sustained hard rock and snow/ice climbing.
TD: *Trés difficile* = very hard. Very difficult technical climbing on all kinds of terrain.
ED: *Extrêmement difficile* = extremely difficult. Extremely serious climbs with long sustained difficulties of the highest order.
ABO: *Abominable*

Soviet Union

The Soviet Union has an alpine rating system somewhat comparable to the NCCS system used in the United States. The scale is 1–6, with a and b subdivisions.

◆ Appendix 3 ◆

LIGHTNING

Though not one of the principal perils of mountaineering, lightning has caused a number of serious—and mostly avoidable—accidents. The very nature of their sport places climbers on or near the most frequent targets: peaks and ridges produce the vertical updrafts and raincloud conditions that generate lightning; the prominences serve to trigger the strokes. Climbers therefore should understand the basic mechanisms involved and fix in their minds the fundamentals of evasive action.

For all practical purposes the hazards are three: (1) a direct strike, (2) ground currents, and (3) induced currents in the immediate vicinity of a strike.

Electrical potential builds up in a cloud in somewhat the same manner one's body picks up an electrical charge on a dry day. Air is normally a very poor conductor (good insulator) of electricity; trees, rock, or earth are better conductors, more so when wet; the human body is still better; and most metals are best of all. Lightning seeks the path of least total resistance between the cloud and earth—the shortest possible line through the air. Ordinarily the closest ground point is directly below the cloud, but a summit off to one side can be closer and become the bull's-eye.

Air ceases to be a good insulator when subjected to a sufficiently high electrical pressure; it *ionizes* and thereupon loses its insulating quality and becomes a conductor. The ionizing breakdown around a conducting projection often gives off a crackling noise (notorious in the Alps as the "buzzing of bees") caused by small sparks. The distinctive odor of ozone is usually noted. A bluish glow or *corona* (St. Elmo's fire) may be seen. If a person's head is the projection, the hair (if any) crackles and stands on end. Corona discharges have often been observed when the nearest cloud seemed too far away to be at all relevant. The sound or sight of corona does not necessarily indicate danger, but lacking more precise indication should be regarded as a warning, especially when thunderclouds are nearby. Additonally, any atmospheric activity symptomatic of commotion should stir suspicion. A sudden rush of cold air perhaps announces a strong cold front with possible lightning. A cloudburst of enormous raindrops or monster snowflakes or huge hailstones almost certainly means a cumulonimbus is overhead.

Lightning is, of course, electricity, which is a stream of electrons. When the more than 100 billion billion electrons in an average bolt strike a peak or a tree they do not just lie there in a puddle, but immediately spread out in all directions. In the process considerable damage can result. Two factors determine the extent of human injury: the quantity of current, and the part of the body affected.

The worst threat is the passage of electricity *through* the body in a way which impairs some vital function such as heart, brain, or breathing action. A current from one hand to the other through the heart and lungs, or from head to foot through virtually all organs, is most dangerous, even if relatively small; one can survive a larger current from one foot to the other through the legs.

Climbers face other potential hazards: large currents can cause deep burns at points of entry and exit; a mild shock may momentarily startle them or set off muscular spasms, or they may move about in semiconsciousness, and in either case may fall off a cliff.

First thought should be given to avoiding areas which might be hit. The governing rule is to seek a location with nearby projections or masses that are somewhat closer than one's own head to any clouds which may drift by. In a forest the safest shelter is amid the shorter trees. The middle of a ridge is preferable to the ends; avoid shoulders.

An electrical discharge at a strike point instantly radiates outward and downward, with the intensity of the flow, and consequently the danger to climbers, decreasing rapidly as the distance from the strike increases. On firm rock, especially when wet, the major path in most cases is along the surface. Lichen patches, cracks, or soil may hold moisture and thus provide easy paths. High-voltage currents tend to jump across short gaps, as in a spark plug, rather than take a longer path around.

Current flows because of a voltage difference between two points along its path. A person bridging two such points with some part of his or her body presents a second and probably better path for the current, some portion of which is therefore diverted through his or her body. The wider the span, the greater the voltage difference and the greater the flow through the body.

With this background, several precepts can be listed:

1. Avoid moist areas, including crevices and gullies.
2. Span as small a distance (occupy as little area) as possible. Keep the feet close together; keep the hands off the ground.
3. Sit, crouch, or stand on insulating objects if possible—a coiled rope or a sleeping bag, preferably dry.
4. Stay out of small depressions; choose instead a narrow slight rise. A small detached rock on a scree slope is excellent.
5. Stay away from overhangs and out of small caves. Large caves are very good if one keeps clear of the walls and entrance. However, a cave might well be the lower terminus of a drainage crevice, and in such case should be avoided.
6. When on a ledge, crouch at the outer edge, at least 4 feet from the rock wall if possible. If there is danger of falling off in event of a shock, tie in *crosswise* to the prospective flow of current. Make the tie short and avoid placing the rope under the armpits.
7. Rappelling when lightning is imminent should be avoided, but may be a valid calculated risk if it is the quickest way to escape a danger zone. Dry synthetic rope presents the minimum hazard.
8. Contrary to popular belief, metal objects do not attract lightning as such. However, in the immediate vicinity of a strike, metals in contact with one's person may augment the hazard from *induced currents*. Induced currents usually are quite small, but when added to ground currents may mean the difference between life and death. Thus it is best to set aside all metals, but to keep them close by (don't worry about an article buried in the pack). A metal pack frame might well be positioned to provide a more attractive path for ground currents beside and past one's body. At distances greater than 100 feet from a possible strike there is no need to divest oneself of metal objects.

Appendix 4

SUPPLEMENTARY READING

Chapter 3: Camping and food

American Heart Association. *Nutrition, Health and Athletic Performance*. Seattle: AHM, 1986.

Axcell, Claudia, Diana Cooke, and Vikki Kinmont. *Simple Foods For The Pack*. San Francisco: Sierra Club Books, 1986.

Berglund, Berndt and Clare Bolsby. *Wilderness Cooking*. New York: Charles Scribner's Sons, 1973.

Bergstrom, J., E. Hultman, L. Hermansen, and B. Saltin. "Diet, Muscle Glycogen and Physical Performance." Acta Physiol. Scand. 71:140, 1967.

Dairy Council. *Nutrition and Athletic Performance*. 46(2), March/April, 1975.

Fleming, June. *The Well-Fed Backpacker*. Portland, Oregon: Victoria House, 1978.

Food and Nutrition Board. *Recommended Dietary Allowances*, 19th ed. Washington, D.C.: 1980.

Gunn, Carolyn. *The Expedition Cookbook*. Denver: Chockstone Press, 1988.

McHugh, Gretchen. *The Hungry Hiker's Book of Good Cooking*. New York: Alfred A. Knopf, 1982.

Peterson, M. S. and C. M. Martinsen. *The Athlete's Cookbook*. Seattle: Smuggler's Cove Press, 1980.

Peterson, M. S. and K. Peterson. *Eat to Compete*. Chicago: Year Book Medical Publishers, Inc., 1988.

Prater, Yvonne and Ruth Dyar Mendenhall. *Gorp, Glop & Glue Stew: Favorite Foods from 165 Outdoor Experts*. Seattle: The Mountaineers, 1981.

SCAN. *Sports Nutrition*. Chicago: American Dietary Association, 1986.

Wallace, Aubrey. *Natural Foods for the Trail*. Yosemite, California: Vogelsang Press, 1977.

Chapter 4: Routefinding and navigation

Carrington, David and Richard Stephenson. *Map Collections in the United States and Canada—A Directory*, 4th ed. New York: Special Libraries Association, 1985.

Cobb, David. *Guide to U.S. Map Resources*. Chicago: American Library Association, 1986.

Dodd, K. *Guide to Obtaining USGS Information*, U.S. Geological Survey Circular 900. Washington, DC: U.S. Geological Survey, 1986.

Fleming, June. *Staying Found*. New York: Vintage Books, 1982.

Kals, W. *Land Navigation Handbook*. San Francisco: Sierra Club Books, 1983.

Makower, Joel, ed. *The Map Catalog*. New York: Vintage Books, 1986.

Miller, Victor C. and Mary E. Westerback. *Interpretation of Topographic Maps*. Columbus, OH: Merrill Publishing Company, 1989.

Moore Moffat, Riley. *Map Index to Topographic Quadrangles of the United States 1882–1940*.

Nicholson, N and L. Sebert. *The Maps of Canada*. Hamden, CT: Archon Press, 1981.

Parry, R. and C. Perkins. *World Mapping Today*. London: Butterworths, 1987.

Thompson, M. *Maps for America*, 3d ed. Washington, DC: U.S. Geological Survey, 1987.

Chapter 7: Belaying

Leeper, Ed. "Belaying: The European Connection." *Summit*, 25, no. 4 (August–September 1979): pp. 11–29.

——. "Belaying: Forces and Stopping Distances." *Summit*, 25, no. 6 (December–January 1980): pp. 6–13.

——. "Belaying: The Occupational Hazards." *Summit*, 26, no. 3: pp. 20–27.

Loughman, Michael. "Ropes, Anchors and Belayers." In *Learning to Climb*, pp. 64–104. San Francisco: Sierra Club Books, 1981.

Steele, George. "Equipment Notes: Some Thoughts on Belaying." *Mountain*, 32 (February 1974): pp. 35–37.

Chapter 8: Rappelling

Martin, Tom. *Rappelling*, 2d ed. Sterling, Kentucky: Search, 1988.

Chapters 9 and 10: Rock climbing and Leading and placing protection

Long, John. *How to Rock Climb*. Evergreen, Colorado: Chockstone Press, 1989.

Loughman, Michael. *Learning to Rock Climb*. San Francisco: Sierra Club Books, 1981.

March, Bill. *Modern Rope Techniques in Mountaineering*. Manchester/Milnthorpe, England: Cicerone Press, 1985.

Ontario Rock Climbing Association. *Rock Climbing Safety Manual*. Toronto: Ontario Rock Climbing Association, 1985.

Robbins, Royal. *Basic Rockcraft*. Glendale, California: La Siesta Press, 1971.

Chapters 12, 13, 14, and 15: Snow travel and climbing, Glacier travel and crevasse rescue, Ice climbing, and Winter and expedition climbing

Barry, John. *Alpine Climbing*. Seattle: Cloudcap Press, 1988.

——. *Snow and Ice Climbing*. Seattle: Cloudcap Press, 1987.

Chouinard, Yvon. *Climbing Ice*. San Francisco: Sierra Club Books, 1978.

Cliff, Peter. *Ski Mountaineering*. Seattle: Pacific Search Press, 1987.

Collister, Rob. *Lightweight Expeditions*. Seattle: Cloudcap Press, 1989.

Daffern, Tony. *Avalanche Safety for Skiers and Climbers*. Seattle: Rocky Mountain Books, 1983.

Everett, Boyd. *Organization of an Alaskan Expedition*. Pasadena, California: Gorak Press, 1984.

Fawcett, Ron, Jeff Lowe, Paul Nunn, and Alan Rouse. *The Climber's Handbook*. San Francisco: Sierra Club Books, 1987.

Houston, Charles. *Going Higher: The Story of Man and Altitude*. Burlington, Vermont: self-published, 1983.

LaChapelle, Edward. *ABC of Avalanche Safety*, 2d ed. Seattle: The Mountaineers, 1985.

Lowe, Jeff. *The Ice Experience*. Chicago: Contemporary Books, 1979.

March, Bill. *Modern Snow and Ice Techniques*. Manchester, England: Cicerone Press, 1973.

Prater, Gene. *Snowshoeing*, 3d ed. Seattle: The Mountaineers, 1988.

Selters, Andy. *Glacier Travel and Crevasse Rescue*. Seattle: The Mountaineers, 1990.

Chapter 17: Alpine Rescue

May, W. G. *Mountain Search and Rescue Techniques*. Boulder, Colorado: Rocky Mountain Rescue Group, 1973.

Padgett, Allen and Bruce Smith. *On Rope*. Huntsville, Alabama: National Speleological Society, 1987.

Setnica, Tim. *Wilderness Search and Rescue*. Boston: Appalachian Mountain Club, 1980.

Appendix 2: Rating systems

Fawcett, R., J. Lowe, P. Nunn, and A. Rouse. *Climbing*. London: Bell and Hyman Limited, 1986.

Lowe, Jeff. "Rate Your Turn, A System for Grading Ice Climbs." *Climbing*, no. 51 (November–December 1978): pp. 14–17.

Roberts, Eric. *Welzenbach's Climbs*. Seattle: The Mountaineers, 1980, pp. 38–41.

Smith, Craig. "Twigging the Grades." *Climbing*, 109 (August 1988): pp. 38–41.

Wiessner, Fritz. "UIAA Grading." *AAJ*, 16, no. 2 (1969).

Index

Boldface numbers indicate pages where illustrations occur.

Ablation zone. *See* Glacier
Accident report form, 409, **410–11**
Acclimatization, 397. *See also* Altitude sickness
Accumulation zone. *See* Glacier
Aid climbing. *See* Direct aid climbing
Air mattresses, 47
Altimeter, 71–73, 305–6
Altitude sickness, 395–96. *See also* Edema, high-altitude
Aluma-heads, 240, **240**
Anchor position. *See* Front-pointing, axe technique
Anchors, 111–15; belay, 111–12, 368–69; multiple, 113–15; position and placing of, 115–17, **116;** rappel, 142–44, **143–44;** in rescue, 324; on snow and ice, 294–97, **295–97;** tying into, 112–15. *See also:* Bollards; Bolts; Deadman anchors; Pickets; Pitons
Animals, 38. *See also* Insects.
Anorak, 24, **24**
Arrest: position for belayer, 318; self- (*see* Self-arrest); team, 292–93
Ascender, mechanical, 236–37, **236;** using, 255–56, **255,** 318
Avalanche: conditions, 306, 310–11; minimizing hazards of, 306, 311–12, 381; rescue from, 312–14, **314;** terrain, 309–10; types of, 306–9, **306–307.** *See also* Beacon, avalanche

Bachli device, 122, **122**
Back carry. *See* Rescue, carries
Back injuries. *See* Spine and neck injuries
Backpack, 27–28; carry for rescue, 418; hauling, 227
Bags, hauling. *See* Haul bags
Balaclava, 23, 30
Balance. *See* Position of balance
Bannister position. *See* Front-pointing, axe technique
Bashies. *See* Malleable hardware
Batteries, 30
Baudrier chest harness. *See* Harnesses, chest
Beacon, avalanche, 313–14, **314**
Bearings. *See* Navigation; Routefinding
Belay, 108–35, **109–10;** aiming a, 118; boot-axe (*see* Boot-axe belay); boot/ice-screw (*see* Boot/ice-screw belay); carabiner-ice-axe (*see* Carabiner-ice-axe belay); dynamic and static, 132–35; fixed, 294; hanging, 251–54, **252–53;** mechanical devices for, 120, 122–25, 369; physics of, 131–35; in rappelling, 151–52; relative security of, **128–29;** in rescue, 412–13; running, 226, 293–94, **293;** seat, 236, **236;** self- (*see* Self-belay); signals, 120, 121; on snow and ice, 297–300, **298–300,** 365, 368–70, **369–70;** for water crossing, 86. *See also* Anchors, belay; Hip belay; Leader, belaying the; Rope, management of; Stance, belay
Bergschrund, 305, **302–3, 316,** 317
Big-wall climbing. *See* Direct aid climbing, big-wall
Bilgeri rescue technique, 333–35, **334**
Bivouac, 29, 30–31, 47–48, 233, 262; sack, 41–42,
Birdbeaks, 239, **239**
Body jams. *See* Jamming
Bollards, 143, 191, 296, **296,** 366, **366**
Bolts, 206–7, **206–7,** 240; hangers, 206, 238
Bongs, 239, **239**
Boot-axe belay, 268, 298–99, **298**
Boot/ice-screw belay, 370, **370**
Boots, 16–19, 157; for front-pointing, 339; lightweight, 18; specialized, 18–20. *See also* Crampons; Rock shoes
Boulders, as protection, 192
Bowline. *See* Knots, bowline
Bridges, snow, 322–23
Bridging. *See* Counterforce climbing
Brush, 57, 64, 83–84

Butane, liquid. *See* Stoves

C-pulley rescue systems. *See* Pulley rescue systems, C-pulley
Cagoule, 24, 25, 47
Camps: on glacier, 320; location of, 36–37; low-impact, 36–38; in snow, 36. *See also* Bivouac
Cams. *See* Chocks, kinds of
Carabiner, 93, 106–7, **107,** 112, **112,** 233; brake method, 138–40, **139;** control, 126–27, **127;** in protection placement, 190–91, **190,** 192, 194, 197, 207, 208; racking chocks on, 223–24; on snow and ice climbs, 293, 296, 299, 318; wrap system, 140, **141**
Carabiner brake systems. *See* Carabiner, brake method
Carabiner-ice axe belay, 299, **299**
Carbohydrates, 48
Carries. *See* Rescue, carries
Chalk, 158
Cheater stick, 240
Chicken heads, 191
Chimneys, 165, 176–78, **176–79**
Chocks: kinds of, 193; loop in, 204, **204,** 207, **207;** minimum needed, 222, 233; and pitons, 193; placement of, 193; removal of, 193, 234; spring-loaded, 201–5, **201–5;** stacking, 197, **197;** wedging factor, 205–6, **206;** wired, 194, 198, **207.** *See also* Chockstones
Chockstones: artificial, 193–206, **193, 195–206;** natural, 192, **192**
Circleheads, 240, **240**
Cleaning. *See* Protection, cleaning
Cliffhangers. *See* Sky hook
Climate. *See* Weather
Climbing code, 15
Climbing party: emergency response of, 407–9; size of, 15, 184, 227, 383, 404, 405; strength and efficiency of, 14, 404. *See also* Evacuation; Leader; Rescue; Roping up; Team
Clothing, 20–27; for avalanche terrain, 312; extra, for emergency, 29, 30, 47, 48, 117; fabrics, 22–23; for ice climbing, 318–19; for rock climbing, 157; waterproof, 22, 23, 24, 25, 26. *See also individual articles of clothing*
Clouds: forecasting by, 395, 438; types of, 395
Clove hitch. *See* Knots, clove hitch
Coil carry. *See* Rescue, carries
Col, 59, 304
Communication: in belaying, 120, 121; importance of, 405; in rescue, 335, 409–12, 422
Compass, 62, **62,** 65–71, **66–69,** 73–77, **74–76.** *See also* Bearings; Magnetic declination; Navigation; Orientation
Conditioning, physical, 156, 387–88, 404
Conduction, 22
Convection, 21, 22, 31
Cooking, 37–38, 50, 51; at high altitudes, 52; in tents, 40, 379–80; units on semi-expeditions, 50. *See also* Food
Copperheads, 240, **240**
Corn snow, 427
Cornices, 304–5, **302–3,** 429–30, **429**
Cotton, 20, 22, 23
Couloirs, 301–4, **302–3**
Counterforce climbing, 164–67, **164–67,** 174–80, **174–79,** 175
Counterbalance, 171, **171**
Crack climbing. *See* Chimneys; Counterforce climbing; Jamming
Cracks, 175–76, 197–98. *See also* Chimneys
Crampons, 269–73, **270–71, 273,** 318, 339–40, **340;** attachment, 271–72; climbing with, 349–64, **350–63;** hinged versus rigid, 270–71, **270;** maintenance and safety, 273. *See also* Flat-footing; Front-pointing
Creep, snow, 317, 426–27
Crevasses: crossing, 321–23, **322–23;** detecting, 321; development of, 315–17; features of, **315–16;** kinds of, **316,** 317; rescue from, 323–37, **325, 327, 328–29, 331–32, 334,** 389. *See also* Bilgeri rescue technique; Pulley rescue systems

Dagger position. *See* Front-pointing, axe technique
Daisy chain: in aid climbing, 235, **235;** rest using, 249
Deadman anchors, 42, **42,** 294–95, **295,** 324
Declination. *See* Magnetic declination
Dehydration, 32, 374, 401
Depth hoar. *See* Snow, cover
Descent. *See* Downclimbing
Dihedrals. *See* Chimneys; Counterforce climbing
Direct aid climbing, 232–63; basic sequence, **246–47,** 247–48; big-wall, 260–62; clean, 232, 256–57, **256;** future of, 262–63; rating systems, 432–34; seconding, 254–59; techniques, 246–59, **246–47, 249, 251, 252–53, 255, 258, 260;** top stepping, 248; types of, 233. *See also* Bolts; Chocks; Pitons
Double figure-8. *See* Knots, figure-8
Double fisherman's knot. *See* Knots, fisherman's
Down, 22
Downclimbing: ice, 360–64, **361–64;** rock, 182–83, **183;** snow, 283–87; versus climbing up, 182; versus rappelling, 182
Downpressure, 161–63
Drinks, 49, 52
Dulfersitz rappel method, 142, **142–43**

Ecosystems, 36–37, 405. *See also* Environment

Edema, high-altitude: cerebral, 396, 408; pulmonary, 396, 408. *See also* Acclimatization; Altitude sickness

Emergency equipment, 29–32; check list, 19–20. *See also* Evacuation; Rescue

End run, 321–22

Energy, expenditure and requirements. *See* Food, requirements

Environment, 230–31. *See also* Ecosystems

Equipment, 16–35; for aid climbing, 233–40; big-wall, 240; deciding amount of, 16; essentials, 29–32, 34; for expeditions, 384–87, 388–89, 391, 398–99; investing in, 16; rescue, 412, 422; for rock, 35, 157–58; for snow and ice, 35, 266–76, **267–71, 273–76,** 317–19. *See also* Clothing; Direct aid climbing; Emergency equipment

Erosion, of snow, 301, 429, 430

Etriers, 234–35, **234, 246–47,** 247–48; top stepping, 248

Evacuation, 408–21; over non-technical terrain, 418–21; by outside help, 409; on snow and ice, 420–21; by stretcher, 420; over technical terrain, 412–18, **413–16.** *See also* Rescue

Evaporation, 20, 22, 49, 374, 380; of snow, 429

Exercise. *See* Conditioning

Expeditions: climbing style, 383; planning, 382–88

Exposure: to falling, 261, 284, 350, 401; to weather, 20

Eyes, protection of, 31, 346, 423

Face climbing. *See* Rock climbing, technique

Fall: action to check, 108, 110–11, 277–78; factor, 213–14. *See also* Crevasses, rescue from; Leader, falls; Protection

Fifi hook, 235, **235**

Figure-8: knot (*see* Knots, figure-8); rappel device, 140, **140**

Finger boards, 186, **186**

Finger jams. *See* Jamming

Fire starters, 32

Firn, 426; line, 317

Firnification, 430

Firnspiegel, 427–28

Fist jams. *See* Jamming

Fixed lines, 391–95

Flakes, 191, 206

Flashlights, 29–30

Flat-footing, 339, 350–54, **350–54;** anchor technique, 353, **353;** cane technique, 350, **350, 351;** cross-body technique, 351–52, **351–52;** descent, 360–63, **361–63;** and front-pointing, 358

Food: amounts, 49–50; efficiency, 50; for expeditions, 384–85; at high altitudes, 52; for long hauls, 50; protection of, from animals, 38; requirements, 29; for short hauls, 50

Foot care. *See* Blisters; Boots; Socks

Foot jams. *See* Jamming

Footgear. *See* Boots

Footholds, 160, **160–61;** on ice, 348, **348;** in slab climbing, 173–74

Forecasting. *See* Clouds, forecasting by; Weather, forecasting

Frame pack. *See* Backpacks

Free climbing. *See* Rock climbing. *See also* Direct aid climbing; Pitons

French technique. *See* Flat-footing; Ice climbing, techniques

French terminology, 346, 347

Friction, in rappelling, 136

Friction braking devices. *See* Brake systems, rappel

Friction climbing. *See* Rock climbing

Friction knots. *See* Knots

Friend. *See* Chocks, spring-loaded

Front-pointing, 354–60, **354–60,** 363–64; axe technique, 355–58; boots for, 339; and flat-footing, 354, 358; for traversing, 360, **361**

Fuel. *See* Stoves

Gaiters, 25–26, 339

Garbage. *See* Cooking

Gas and gasoline. *See* Stoves

Gear. *See* Clothing; Equipment

German technique. *See* Front-pointing; Ice climbing, techniques

Girth hitch. *See* Knots, girth hitch

Glacier, 315–17, **316,** 430. *See also* Camps, on glaciers; Erosion, snow and glacier

Glacier travel. *See* Crevasses; Glacier; Ice climbing

Glasses. *See* Eyes, protection of; Goggles

Glissade, 284–87, **286**

Gloves, 26–27, 234

Goggles, 346

Gore-Tex, 23

Gorp, 51

Grade. *See* Rating systems, alpine climbing

Graupel. *See* Snow, flakes

Ground cloth, 39, 41, 43

Ground insulation, 47

Hammer, piton, 237, **237**

Hammocks, 240

Hand jams. *See* Jamming

Hand tools, 340–41, 360, 367, **367,** 368, **368.** *See also* Ice axe

Handholds, 161, **161;** cling, 161, **161;** combinations of,

162, 168; in downclimbing, 183; downpressure, 161–63; on ice, 346, 348–49. *See also* Counterforce climbing
Hangers. *See* Bolts
Hard hat. *See* Helmets or hard hats
Hardware, racking. *See* Rack
Harnesses, 101–4, **104–5,** 317; body, 104, **104;** chest, 104, **105;** seat, 101–3, 137
Haul bags, 240
Hauling, 260–61, **260**
Hazards: at high altitudes, 33, 41, 372–73, 387, 395–97; objective, 305, 401–2; in rescues, 418, 423; of roping and belaying, 129, 140–41, 184; in snow, 43, 304, 306–11, **306–9;** of stoves and lanterns, 40, 55; subjective, 136, 402, 406. *See also* Cornices; Crevasses; Exposure; Lightning; Rockfall; Safety
Headgear, 23. *See also* Balaclava; Helmets or hard hats
Headlamps, 29–30, **29**
Helicopter rescue, 422–23; signals for, **422**
Helmets or hard hats, 35; climbing, 346; in rescue, 418
Hero loops, 234
Hip belay, 125–28, **125.** *See also* Anchors, belay; Belay; Rope, management of
Hip wrap. *See* Hip belay
Hoarfrost, 426
Hooks, 237–38, **237**
Horn. *See* Rock horn

Ice, 338; alpine, 338; vertical or overhanging, 338, 360; water, 338. *See also* Ice climbing; Icefalls
Ice axe, 34, 86–87, 266–69, 274, 276–83, 266–69, **267–69,** 318; arrest technique, 287–92; ascent technique, 281–83, **281–83;** belay technique, 277–78, 291–92, 294, 298–99; carrying, 276, **277;** in glissades, 285–86; on ice, 267; maintenance, 269; parts of, 267–69, **267;** rescue carry, 418; safety with, 276; in snow, 276–92. *See also* Hand tools; Ice climbing, tools for; Wrist leash
Ice climbing: equipment, 338–46, rating, 434–36; rope teams for, 365; speed in, 365; techniques of, 338, 346–68; tools for, 34–45, **341–44,** 364–65, **364;** on vertical or overhanging ice, 359–60, **359–60.** *See also* Clothing, for ice climbing; Crevasses; Equipment, for snow and ice; Position of balance; Protection, on ice; Routefinding, on snow
Ice screws and pitons, 345–46, **345,** 366–68, **367**
Icefalls, 317
Insects, 33–34
Insoles, 19, 20, 86
Insulation. *See* Clothing; Ground insulation; Sleeping bags

Jamming, 168–71, **168–71,** 173, **174–75**
Jugging. *See* Ascender, mechanical
Jumars. *See* Ascender, mechanical

Kerosene. *See* Stoves
Knee pads, 240
Knife, 32
Knot, passing the, 417
Knots, 94–101; Bachmann, 100, **100;** bowline, 96–98, **97–98;** clove hitch, 98, **99;** double sheet bend, 98, **98;** figure-8, 96, **96;** fisherman's, 95, **95;** girth hitch, 98, **98;** Kleimheist, 100, **100;** Münter hitch, 100–101, **101,** 369, **371;** overhand, 94, **94;** prusik, 99–100, **99;** slip, 98, **98, 224;** square, 95, **95;** water, 94–95, **95**

Layering system, clothing, 20–22, 23–24
Leader: belaying the, 117–18; falls, 124, 131, 133, **189,** 213, 219, 317; responsibilities and requirements of, 188, 213–14, 403–4; in roping, 216–19; training to be, 403–4. *See also* Direct aid climbing; Rescue, leader
Leading, skill of, 188; changing leads, 259
Leash. *See* Wrist leash
Leeper Z pitons, 239, **239**
Leeward slope, 305, 381. *See also* Cornices
Lieback. *See* Counterforce climbing
Lightning, 438–39
Liquefied gas. *See* Stoves
Lost, what to do when, 77–78
Lost arrows, 239, **239**

Magnetic declination, 60, 66, 68–70. *See also* Bearing; Compass
Malleable hardware, 239–40, **240**
Mantel, 162–63, **162–63**
Maps, 57–65, 66, 75
Matches, waterproof, 29, 32
Meals. *See* Cooking; Food
Mechanical systems, rappel, 137–41, **137–41**
Metamorphism, of snow and ice, 425–30, **425–26**
Mittens, 26
Moats, 305, **302–3**
Monkey hang, 360, **360**
Mosquitoes. *See* Insects
Mountain sickness. *See* Altitude sickness; Edema, high-altitude
Münter hitch. *See* Knots; Belay, mechanical devices for

Navigation: procedures for, 56–78; tools for, 57–62, 65–66, 71–73, 75–77
Nesting. *See* Pitons, stacking and nesting
Névé. *See* Firn

Nieve penitentes, **428,** 429
Nunataks, 317
Nuts. *See* Chocks

Objective hazards. *See* Hazards, objective
Orientation, 56, 62, **62, 73–75.** *See also* Bearings; Navigation
Overhand slip knot. *See* Knots, slip
Overhangs and roofs, 178–80, **179,** 250–51, **251**

Pace: adjusting, 81, 82; and rest, 81; on snow, 81; in walking, 80, 81
Packs, 27–28; hauling, 227
Pad, insulating, 47, 380
Pants, 25
Parka, 24, **24,** 34
Party climbing. *See* Climbing party
Pendulums. *See* Traverses, pendulum
Physical fitness. *See* Conditioning
Pickets, 295–96, **296, 297**
Pied à plat. See Flat-footing
Pigeonhole steps. *See* Stepcutting
Piggyback rescue systems. *See* Pulley rescue systems, piggyback
Pins, fixed. *See* Pitons
Piolet. *See* Flat-footing; Front-pointing, axe technique
Pitch, 108; cleaning the, 225, 254, 256–57, **256;** pendulum (*see* Traverses, pendulum)
Pitons, 206–8, **206, 208,** 232, 238–40; checking, for soundness, 206; fixed, 108, 144, 207–8, 256; kinds of, 238–39, **239;** placement of, 206, 208–11, 241–44, **241–45;** in protection, 206; in rappel, 144; removal of, 256–57, **256;** stacking and nesting, 244, **244–45;** versus bolts, 206; versus chocks, 193. *See also* Bongs; Hammer, piton; Ice screws and pitons; RURP; Tying off, pitons
Placements: aid, 241–54; double, 208–12, **209–12;** hook, 244–45; malleable, 245, **245;** piton, 241–44, **241–45;** threaded, 192, **192,** 198, **198.** *See also* Protection, placing
Planning: a climb, 220, 222, 225; for routefinding, 57–58, 62–63
Plunge step, 284, **284–85**
Ponchos, 24
Portaledge. *See* Hammocks
Position of balance, 279, **279,** 347
Powder snow, 427
Preparation: mental, 156, 402, 403; physical, 156, 402–3. *See also* Conditioning
Probing. *See* Crevasses, detecting
Protection: attaching rope to, 214–17; of belayer, 109, 112; cleaning, 256–57, **256;** equalizing, 212, **212;** on ice, 365–68, **366–68;** placing, 188–94, **190–92, 195–212,** 213, 214, 220; points of, 188; removal of, 225–6. *See also* Placements; Rack
Prusik, 99–100; knots (*see* Knots, prusik); sling, 35, 99–100; stair-step, 327–28, **327–28;** Texas, 328–30, **329**
Pulley rescue systems, 330–33; C-pulley, 330–31, **331;** piggyback, 333; Z-pulley, 331–33, **332**
Pulleys, hauling, 240
Pulmonary. *See* Edema, high altitude pulmonary

Rack, 222–25; double, 235–36, **235**
Radiation, in body heat loss, 23, 38, 372
Radio communication. *See* Communication, in rescue
Raingear, 25. *See also* Clothing, waterproof; Shelter
Rappel, 136–53, **136,** 250, 364; arm, 141, **141;** free, 137, 149; on ice, 364; multiple, 150–51; safety backups, 151–52, **151–52;** technique, 147–50, **147–50;** of victim, 413. *See also* Anchors, rappel; Mechanical systems, rappel; Dulfersitz rappel system; Friction, in rappelling; Pendulums; Rope, in rappel
Rating systems, 431–37, **433, 436;** alpine climbing, 434; foreign, 436–37, **436**
Rescue: by air, 422–23; carries, 414, **414–15,** 418–19, **419;** going for help for, 409–11; group organization for, 408, 421; leader, 408; lowering the victim, 413–17, **413, 416;** raising the victim, 417–18. *See also* Avalanche, rescue from; Crevasses, rescue from; Equipment, rescue; Evacuation; Self-rescue
Rest step: hiking, 81; in snow, 280
Rest stop: in aid climbing, 248–50, **249;** in glacier travel, 320; in ice climbing, 344; shakedown, 81–82
Ridges, 304
Rime, 425–26
River. *See* Streams and rivers, crossing
Rock, features of, 191
Rock climbing: alpine, 183–84; basic principles of, 156, 158–59; ethics, 186–87, 230; practice for, 184–86, **186;** rating systems, 431–32; styles, 186–87; technique, 158–84, **158–83.** *See also* Equipment, for rock
Rock horn, 143–44, **143,** 190, **190,** 191, **191**
Rock shoes, 20, 157, 234
Rockfall, 57, 80, 109, 117, 129, 142, 184, 305, 346, 401
Roofs. *See* Overhangs and roofs
Rope, 90–93; in aid climbing, 233; in belay, 108; coiling, 92–93, **93;** double-rope technique, 227–30, **228–29;** drag, 216–17, **217;** on glacier and ice, 317; management of, 320–21; in rappel, 144–46, **144–46,** 152–53; in rescue, 412, 413, **414,** 416, **416,** 417–18; safety with, 90, 92; twin-rope technique, 230, **230;** types of, 90, 92. *See also* Friction, in rappelling;

Knots; Stretchers, rope; Team; Tying off, rope
Roping up, 292, 319–20; on glaciers, 292, 319–20; order of, 292; responsibilities of members, 292, 294
Route: through couloirs, 301–4; among crevasses, 76, 315; evacuation, 412; rating of, 431–37; along ridges, 304; on rocks, 57, 84–85
Route marking, 63–64; for rescue party, 409, 422; on snow and glaciers, 63, 305, 319
Routefinding, 56–78, 79; through brush, 76, 83–84; on glaciers, 63, **77;** on ridges, 72, 74, 84; on snow, 63, 72, 77, 80, 85, 300–6, 380–81; over stream or river, 85–86. *See also* Bearings; Planning; Navigation
Rucksack. *See* Backpack
Rucksack carry. *See* Rescue, carries
Runners, 90, 106, **106,** 113–15, 143–44, **143,** 190–92, **190–92,** 196, **209,** 212, **212,** 214, **214,** 215, **215,** 216; energy-absorbing, **216,** 217, 222–23, **223,** 224–25, **224.** *See also* Slings
RURP (Realized Ultimate Reality Piton), 238–39, **239**

Safety: attitude for, 14, 156, 403; in climbing, 400; on ice, 365; loop, 328, 335; during rescue, 407, 408, 409, 412, 423; with stoves and lanterns, 55. *See also* Climbing code; Communication; Hazards; Leader; Protection; Rescue
Sag. *See* Crevasses, detecting
St. Elmo's fire (corona). *See* Lightning
Salt, 49
Sanitation, 37–38
Sastrugi, **428,** 429
Scree, 85
Search, 407–8. *See also* Beacon, avalanche
Seconding. *See* Direct aid climbing, seconding
Self-arrest, 287–91, **288–91;** limits of, 290–92
Self-belay, 130–31, 277–78, **277–78,** 291–92
Self-rescue, 326–30, **327–29**
Seracs, 317
Shakedown rest. *See* Rest stop, shakedown
Shelter, 38–45, 375–87; emergency, 34, 35, 48. *See also* Snow, shelters; Tarps; Tents; Trees, as cave shelter
Shirts, 21, 23
Shovel, snow, 276, **276,** 375, **375**
Signals. *See* Communication
Silicone, 92
Single pulley rescue system. *See* Pulley rescue systems
Skis, 274–75; equipment for mountaineering, 274, **275;** poles, 274, **274,** 319
Sky hook, 238
Slab climbing. *See* Rock climbing, technique
Sleeping bags, 45–47, 380. *See also* Ground insulation
Slings: chock, 194–95; energy-absorbing, 234; hammer, 237, **237;** hardware (*see* Hardware, racking); "keeper," 242, **243,** 244, **244;** prusik, 318; rappel, 144–45, **145**
Snow, 425–30; consolidation of, 301, 310; cover, 426–30, **426;** dangers in, 300; flakes, 425, **425–26;** shelters, 42–44, 376; slides, 310, 309, 310. *See also* Avalanche; Bridges, snow; Camps, in snow; Metamorphism
Snow climbing, 266–92. *See also* Anchors, on snow and ice; Belay, on snow and ice; Equipment, for snow and ice; Routefinding, on snow; Self-arrest; Self-belay
Snow flukes. *See* Deadman anchors
Snow travel. *See* Snow climbing.
Snowshoes, 275–76, **275,** 319
Socks, 20, 26
Soft pack. *See* Backpack
Speed: and navigation, 64; and safety, 129, 148–49, 184, 280, 284, 285, 286, 365, 371, 406
Spring-loaded devices. *See* Chocks, spring-loaded
Stacking. *See* Pitons, stacking and nesting
Stakes, 40, 41, 42
Stance, belay, 115–17; **116**
Stemming. *See* Counterforce climbing
Stepcutting, 348–49, **348–49**
Stepkicking, 280. *See also* Front-pointing
Sticht Belay Plate, 122, **122**
Stirrups. *See* Etriers
Storm formation, 395
Stoves, 53–55, 374, 378–79, 385, 398
Streams and rivers, crossing, 85–86
Stretcher: from helicopter, 422; rigid, 421; rope, 420
Suncups, 428–29, **428**
Sunglasses, 31
Swami belts, 103, **103**
Swing leads, 226–27
Synthetic fabrics: as insulators, 20, 22, 23; for rope, 90

Talus, 84–85
Tape, use of in rock climbing, 157, **157**
Tarps, 40–41, **41**
Team: expedition, 383; rope, in glacier travel, 319–20. *See also* Arrest, team; Climbing party
Ten Essentials, 29–32, 34
Tents, 38–40, **39,** 42, 376–78, **377–78;** cooking in, 40, 379–80
Terrain, alpine, 301–5, **302–3**
Texas prusik. *See* Prusik, Texas
Three-o'clock position, 358
Ticks. *See* Insects
Timing, in planning a climb, 305
Toe jams. *See* Jamming
Tools. *See* Hand tools

Top stepping. *See* Direct aid climbing, top stepping
Trails, etiquette, 82, 83; role of, in routefinding, 83
Traverses: hand, 180; on ice, 360; pendulum, 250, 257–59, **258;** on rock, 180–82, **180–81;** shuffling and stepping through, 180; in snow, 283; tension, 250; Tyrolean, 254
Trees: as anchors, 143–44, **144,** 191; as cave shelter, 43
Tying in: to anchor point, 112–14, **112–15;** to harness, 112–13, 115, 117; to rope team, 320
Tying off: pitons, 234, 244, **244;** rope, 129–30, **130**
Tyrolean traverse. *See* Traverses, Tyrolean

Undercling hold. *See* Counterforce climbing
Underclothing, 23, 25

Ventilation, clothing, 21, 22, 23, 24, 25; snow caves, 43; tents, 39
Verglas, 338

Wands, 273–74, **274,** 305, 319
Water, 32–33, 49
Waterproof clothing. *See* Clothing, waterproof
Waterproofing: backpacks, 28; boots, 18, 19. *See also* Clothing, waterproof
Weather: and helicopter rescue, 422; expedition, 372, 395; forecasting, 73, 395
Wedges. *See* Chocks, kinds of
Wedging factor. *See* Chocks, wedging factor
Wilderness travel, 79–87. *See also* Ice climbing; Rock climbing; Snow climbing
Wind, 21, 37, 39, 53, 73, 304, 310–11, 377, 378; protection from, 24, 25
Wind-chill effect, 21–22, **21,** 373
Windward slope, 304, 310, 381
Winter mountaineering, 372–82; camping, 375–80; clothing, 373–74; foot care, 374
Wool, 22
Wrist leash, 268–69, **269,** 344, **344**
Wrist loop, *See* Wrist leash

Z-pulley rescue system. *See* Pulley rescue systems, Z-pulley
Zig-zag diagonal steps. *See* Stepcutting
Zipper effect, 118, 219–21
Zippers, 24, 26, 28, 46

"When asked by either prospective mountaineers or hardened Himalayan veterans which book is essential for their library, I answer directly, *Mountaineering: The Freedom of the Hills*. The 5th edition continues to reflect a commitment to safety, changing techniques, and environmental concerns by The Mountaineers."

— John Roskelley, American mountaineer and author
Nanda Devi: The Tragic Expedition

"There are good manuals on rock climbing and good manuals on ice climbing, but only this book covers the whole realm of mountaineering—and does it well."

— Galen Rowell, author
My Tibet and *High and Wild*

"*The Freedom of the Hills* covers more ground than an alpine traverse. This book leads you step-by-step through the mountains, pausing along the way to teach the skills a climber needs. It's the next best thing to hiring a world-class mountain guide."

— Greg Child, K2 summiter and author
Thin Air: Encounters in the Himalaya

"The completeness, clarity, and modern point of view that characterize *Freedom*'s 5th edition now make it the single most useful mountaineering book published in the world . . ."

— Dunham Gooding, President
American Alpine Institute



For over thirty years and through four editions, *Mountaineering: The Freedom of the Hills* has been the "bible" of the climbing world. An essential teaching tool and resource for novice to advanced mountaineers, *Freedom* is the standard text for climbing courses throughout the United States and abroad, and even has been used as a training manual by the U.S. military.

Completely updated and revised, the 5th edition redefines the basics with expanded chapters on the latest developments in equipment, technique, snow and glacier travel, safety, and leadership. New sections on rock climbing, an entirely new chapter on winter and expedition climbing, plus 350 all-new illustrations, make *Freedom* the most comprehensive and contemporary source available on mountaineering.

Written and coordinated by The Mountaineers, a Seattle-based outdoor organization founded in 1906, *Mountaineering: The Freedom of the Hills* is a consensus on accepted, safe principles and methods of mountaineering. This book gathers the wisdom, instruction, and experience of some of the world's best climbers into one indispensable volume.

The MOUNTAINEERS
1001 SW Klickitat Way
Seattle, WA 98134 USA

ISBN 0-89886-309-0
U.S. $22.95

52295
9 780898 863093

Issued	**July 2008**
Superseding	**BR 45(1)**
Dated	**March 1987**

BR 45(1)(1)

ADMIRALTY MANUAL OF NAVIGATION

VOLUME 1 (PART 1)

THE PRINCIPLES OF NAVIGATION

By Command of the Defence Council

COMMANDER IN CHIEF FLEET

SPONSOR

This publication is sponsored by the Commander in Chief Fleet. All correspondence concerning this publication is to be forwarded to the Operational Publications Authority, with copies to the Sponsor Desk Officer, the relevant Subject Matter Specialist and, only if appropriate, to the MoD Intellectual Property Authority, as follows:

Operational Publication Authority:

OIC FPGO
Fleet Publications and Graphics Organisation
Pepys Building
HMS COLLINGWOOD
Fareham
Hampshire PO14 1AS

Sponsor Desk Officer:

FLEET-CAP SC NAVSEA SO1
Navy Command HQ
Leach Building (MP 2-4)
Whale Island
Portsmouth
Hampshire PO2 8DY

MoD Directorate of Intellectual Property Rights:

DIPR (PL)
Ministry of Defence
Abbey Wood
Bristol
Avon BS34 8JH

© British Crown Copyright 2008

RECORD OF CONFIGURATION CONTROL -1

	Authored by	**Checked by**	**Approved by**
Edition/Change: 2008 ORIGINAL	**Name:** PEACOCK	**Name:** RODGERS	**Name:** HOLT
	Tally: SO2 N7 (FSA-GT4)	**Tally:** SO1 N7 (FSA-GT)	**Tally:** FLEET CAP SC NAVSEA SO1
Date of edition/change: July 2008 ORIGINAL	**Signature:** Signed on master copy	**Signature:** Signed on master copy	**Signature:** Signed on master copy
	Date:	**Date:**	**Date:**
Edition/Change:	**Name:**	**Name:**	**Name:**
	Tally:	**Tally:**	**Tally:**
Date of edition/change:	**Signature:**	**Signature:**	**Signature:**
	Date:	**Date:**	**Date:**
Edition/Change:	**Name:**	**Name:**	**Name:**
	Tally:	**Tally:**	**Tally:**
Date of edition/change:	**Signature:**	**Signature:**	**Signature:**
	Date:	**Date:**	**Date:**
Edition/Change:	**Name:**	**Name:**	**Name:**
	Tally:	**Tally:**	**Tally:**
Date of edition/change:	**Signature:**	**Signature:**	**Signature:**
	Date:	**Date:**	**Date:**
Edition/Change:	**Name:**	**Name:**	**Name:**
	Tally:	**Tally:**	**Tally:**
Date of edition/change:	**Signature:**	**Signature:**	**Signature:**
	Date:	**Date:**	**Date:**

RECORD OF CONFIGURATION CONTROL -2

	Authored by	Checked by	Approved by
Edition/Change:	**Name:**	**Name:**	**Name:**
	Tally:	**Tally:**	**Tally:**
Date of edition/change:	**Signature:**	**Signature:**	**Signature:**
	Date:	**Date:**	**Date:**
Edition/Change:	**Name:**	**Name:**	**Name:**
	Tally:	**Tally:**	**Tally:**
Date of edition/change:	**Signature:**	**Signature:**	**Signature:**
	Date:	**Date:**	**Date:**
Edition/Change:	**Name:**	**Name:**	**Name:**
	Tally:	**Tally:**	**Tally:**
Date of edition/change:	**Signature:**	**Signature:**	**Signature:**
	Date:	**Date:**	**Date:**
Edition/Change:	**Name:**	**Name:**	**Name:**
	Tally:	**Tally:**	**Tally:**
Date of edition/change:	**Signature:**	**Signature:**	**Signature:**
	Date:	**Date:**	**Date:**
Edition/Change:	**Name:**	**Name:**	**Name:**
	Tally:	**Tally:**	**Tally:**
Date of edition/change:	**Signature:**	**Signature:**	**Signature:**
	Date:	**Date:**	**Date:**

PREFACE - 1

SCOPE OF ADMIRALTY MANUAL OF NAVIGATION (BR 45) VOLUME 1

Content of BR 45 Volume 1 'The Principles of Navigation'

This book (BR 45 Volume 1) deals with the essential principles of *Marine Navigation*: position and direction on the Earth's surface, map *Projections*, charts and publications, chartwork, fixing, aids to navigation, *Tides / Tidal Streams*, *Ocean Navigation, Coastal Navigation, Pilotage / Blind Pilotage,* anchoring, navigational errors, *Relative Velocity*, hydrographic surveys and Bridge organisation. Summaries of plane and spherical trigonometry, proofs of formulae etc, may be found in the Appendices at the back of the book.

Unchanging Principles of Navigation

Despite the advent of new technology, the underlying principles of *Navigation* (particularly that of cross-checking all available sources of information) remain unchanged by new techniques and equipment; therefore the treatment of the subject in this manual has been designed to re-state the principles while reflecting the latest methods.

Use of Terms - 'Marine Navigation'.

Navigation in its widest sense is the process of planning and executing the movement of people and/or vehicles from one place to another – at sea, in the air, on land or in space. The navigation of ships, submarines and all other waterborne craft is known as *Marine Navigation* to distinguish it from *Navigation* in other surroundings.

Use of Terms - Abbreviated Term 'Navigation'.

For the sake of brevity, from this point onwards, the term *Marine Navigation* is abbreviated to '*Navigation*' in this book and in its companion volumes in the BR 45 'Admiralty Manuals of Navigation' series.

Mathematical Concepts, Calculations and Formula Numbering

The concepts in Chapters 1-5 and Appendices 1-5 are presented in detail to provide the reader with a detailed mathematical explanation of the shape of the Earth and its associated calculations. This provides the mariner with a thorough knowledge of the fundamental 'tools of the trade' and their capabilities / limitations, and thus a firm foundation on which practical use of automated systems (eg *WECDIS / ECDIS* etc) may be carried out with confidence. For continuity, formulae numbering follows closely to that used in the 1987 edition (see page xiv).

Worked Examples - Method

MS Excel has been used with 'full-precision' values for calculations in all worked examples. Answers are usually rounded to the nearest 0.1 *n.mile* and 0.1˚.

Italicised Terms Included in Index-Glossary

Terms shown in '*italics*' (except as indicated below) are included in the Index-Glossary at the end of the book. **The Index-Glossary shows the primary paragraph reference(s) in bold font**, and 'passing' references to the term in ordinary font. On occasion, when a definition not covered within the main text of this book is deemed necessary for completeness, it is included in the Index-Glossary.

Italicised Entries NOT Included in Index-Glossary

Equations, 'Notes' and letters in the text referring to lettering in geometric-type diagrams are also italicised but are NOT included in the Index-Glossary.

PREFACE - 2

The Admiralty Manual of Navigation (BR 45) consists of nine volumes:

Volume 1 is an A4 book in two Parts covering 'The Principles of Navigation' **(see content list overleaf.** Volume 1 is also published by the Nautical Institute and is available to the public.

Volume 2 is an A4 book covering Astro Navigation (including Time). Chapters 1 to 3 cover the syllabus for officers studying for the Royal Navy 'Navigational Watch Certificate' (NWC) and for Royal Navy Fleet Navigator's Courses. The NWC is equivalent to the certificate awarded by the Maritime & Coastguard Agency (MCA) to OOWs in the Merchant Service under the international Standardisation of Training, Certification and Watchkeeping (STCW) agreements.) The remainder of the book covers the detailed theory of astro-navigation for officers studying for the Royal Navy "Specialist 'N' Course", but may also be of interest to others who wish to research the subject in greater detail. Volume 2 is also published by the Nautical Institute and is available to the public.

Volume 3 is a Protectively Marked A4 book, covering navigation equipment and systems (Radio Aids, Satellite Navigation, Direction Finding, Navigational Instruments, Logs and Echo Sounders, Gyros and Magnetic Compasses, Inertial Navigation Systems, Magnetic Compasses and De-Gausing, Automated Navigation and Radar Plotting Systems, AIS, and Navigational Equipment Fit Summary).

Volume 4 is a Protectively Marked A4 book covering the conduct of navigation in warships, submarines and Royal Fleet Auxiliaries at sea.

Volume 5 is an A4 book containing exercises in navigational calculations (Tides and Tidal Streams, Astro-Navigation, Great Circles, Rhumb Lines, Time Zones and Relative Velocity). It also provides extracts from most of the tables necessary to undertake the exercise calculations. Volume 5 (Supplement) provides worked answers.

Volume 6 is supplied in three, A4 binders: the non-Protectively Marked Binder 1 covering generic principles of shiphandling (Propulsion of RN ships, Handling Ships in Narrow Waters, Manoeuvring and Handling Ships in Company, Replenishment, Towing, Shiphandling in Heavy Weather and Ice), and the Protectively Marked Binders 2 and 3 covering all aspects of class-specific Shiphandling Characteristics of RN Ships / Submarines and RFAs). **Turning data quoted in Volume 6 is approximate and intended only for overview purposes; turning data for manoeuvring and *Pilotage* should be taken from ships' Navigational Data Books.**

Volume 7 is an A4 book covering the management of a chart outfit (Upkeep, Navigational Warnings, Chronometers and Watches, Portable / Fixed Navigational Equipment and Guidance for the Commanding Officer / Navigating Officer).

Volume 8 is supplied in three Protectively Marked A4 binders, covering the operation of *WECDIS*, *ECDIS* and *ECS* in the Fleet.

Volume 9 is a Protectively Marked A4 book covering operational navigation techniques that are of particular concern to the RN.

Note. *Terms in italics in newer books are contained in the Index-Glossary of each book.*

PROPOSALS FOR CHANGES

Protective Marking ....

Ship/Establishment .... Originating Dept .... Date ....

Title of Publication	
Current Issue Status	

DETAILS OF COMMENTS

Page	Para Number	Comment
		Continue on a separate sheet if required

Originator: (Name in Block Letters)	
Signature	
Rank/Rate	

Protective Marking ....

Forward copies of the above form to the addressees listed on Page ii.

RECORD OF CHANGES: VOLUME 1

Notes:

1. *The incorporation of Changes should be recorded below.*

2. *The incorporation of Temporary Amendments such as signals, AILs etc should be recorded on page ix opposite.*

CHANGE NO.	DATE INSERTED	SIGNATURE	NAME	REMARKS
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				

RECORD OF TEMPORARY AMENDMENTS: VOLUME 1

Note. *The incorporation of Signals and AILs or other temporary amendments should be recorded below.*

REFERENCE NO.	DATE INSERTED	SIGNATURE	NAME	REMARKS

CONTENTS: VOLUME 1 - PART 1

Chapter 1 **Position and Direction on the Earth's Surface**
Section 1 Position on the Earth's Surface
Section 2 Direction on the Earth's Surface

Chapter 2 **The Sailings (1) - Basic Calculations**

Chapter 3 **An Introduction to Geodesy**
Section 1 Spheroids
Section 2 Datums
Section 3 Earth Models for Navigation Systems

Chapter 4 **Projections and Grids**
Section 1 Projection Concepts and Principles
Section 2 Mercator Projection for Charts
Section 3 Transverse Mercator Projection for Charts
Section 4 Gnomonic Projection for Charts
Section 5 Grids

Chapter 5 **The Sailings (2) - More Complex Calculations**
Section 1 Spherical Mercator Sailing
Section 2 Spherical Great Circle Composite Track / Vertex
Section 3 Spheroidal Rhumb Line Sailing
Section 4 Spheroidal Geodesic (Great Circle) Sailing
Section 5 Comparison and Choice of Methods

Chapter 6 **Charts and Publications - Overview**
Section 1 Charting Concepts and Policy
Section 2 Navigational Charts
Section 3 Digital Navigation Systems and Electronic Charts
Section 4 UKHO Navigational and Digital Publications

Chapter 7 **Chartwork**
Section 1 Paper Chartwork Procedures
Section 2 Digital Chartwork Procedures

Chapter 8 **Visual Fixing**

Chapter 9 **Aids to Navigation**
Section 1 Satellite Navigation, LORAN and E-Nav / Digital Nav
Section 2 Compasses, Inertial Nav Systems, Echo Sounders & Logs
Section 3 Lights and Fog Signals
Section 4 Buoys, Other Floating Structures and Beacons
Section 5 Automatic Identification Systems (AIS) and VHF Radio

CONTENTS: VOLUME 1 - PART 1 (continued)

Chapter 10 Tides and Tidal Streams

Section 1 Tidal Theory
Section 2 The Tides in Practice
Section 3 Tidal Harmonics and SHM for Windows
Section 4 Tidal Streams and Currents
Section 5 Admiralty Tide Tables and Admiralty TotalTide
Section 6 Levels and Datums

Appendices

Appendix 1 Plane Trigonometry
Appendix 2 Spherical Trigonometry
Appendix 3 The Spherical Earth
Appendix 4 Projections
Appendix 5 The Spheroidal Earth
Appendix 6 Vertical and Horizontal Sextant Angles
Appendix 7 Doubling the Angle on the Bow
Appendix 8 Spare
Appendix 9 Spare
Appendix 10 *See Part 2*

Index-Glossary of Terms

(Part 2 - see overleaf)

CONTENTS: VOLUME 1 - PART 2

Chapter 11 Ocean Navigation
- **Section 1** Planning and Execution of Ocean Navigation
- **Section 2** Ocean Currents

Chapter 12 Coastal Navigation
- **Section 1** Planning Coastal Navigation
- **Section 2** Execution of Coastal Navigation
- **Section 3** Traffic Reporting and Monitoring Systems

Chapter 13 Pilotage and Blind Pilotage
- **Section 1** Planning Pilotage and Blind Pilotage
- **Section 2** Execution of Pilotage and Blind Pilotage
- **Section 3** Navigation in Canals and Narrow Channels

Chapter 14 Anchoring
- **Section 1** Anchoring a Single Ship
- **Section 2** Berthing Stern-To and Alongside with Anchors

Chapter 15 Radar Theory and Application
- **Section 1** Radar Wave Theory
- **Section 2** Radar for Navigation
- **Section 3** Limitations of Radar

Chapter 16 Navigational Errors
- **Section 1** Navigational Accuracies and Types of Error
- **Section 2** Practical Application of Navigational Errors
- **Annex A** One-Dimensional Random Errors
- **Annex B** Two-Dimensional Random Errors

Chapter 17 Relative Velocity
- **Section 1** Principles of Relative Velocity
- **Section 2** Plotting Relative Velocity on Radar Displays
- **Section 3** Some Relative Velocity Worked Examples

Chapter 18 Hydrographic Surveying for Non-Surveyors
- **Section 1** Guidance for ‘Short Period’ Surveying Tasks
- **Section 2** Guidance for a Complete Minor Survey

Chapter 19 Bridge Organisation and Management
- **Section 1** Navigational Conduct of the Ship
- **Section 2** WECDIS / ECDIS Bridge Organisations
- **Section 3** Paper Chart Bridge Organisations (Pre-WECDIS / ECDIS)

CONTENTS: VOLUME 1 - PART 2 (continued)

Appendices

Appendix 1 *See Part 1*
Appendix 2 *See Part 1*
Appendix 3 *See Part 1*
Appendix 4 *See Part 1*
Appendix 5 *See Part 1*
Appendix 6 *See Part 1*
Appendix 7 *See Part 1*
Appendix 8 *See Part 1*
Appendix 9 *See Part 1*
Appendix 10 Errors in Terrestrial Position Lines

Index-Glossary

WHEREABOUTS OF TOPICS FROM 1987 EDITION

To assist the many readers who are familiar with the 1987 edition of this book and who may have teaching notes based upon it, this fully updated 2008 edition has, as far as possible, retained a similar sequence and layout of information. The overall whereabouts of topics from the 1987 edition is as follows in the 2008 edition:

1987 Edition	**2008 Edition**
Chapter 1-3	Chapter 1-3
Chapter 4 (except parts of pages 81-83)	Chapter 4
Chapter 4 (parts of pages 81-83)	Transferred to BR 45 Vol 9
Chapter 5 (except parts of pages 94-95)	Chapter 5
Chapter 5 (parts of pages 94-95)	Appendix 5
Chapter 6 (except part of pages105-106)	Chapter 6
Chapter 6 (part of pages 105-106)	Chapter 9
Chapter 7 (except pages 164,166-168-172)	Chapter 6 and from BR 45 Vol 8
Chapter 7 (parts of pages 164,166-172)	Transferred to BR 45 Vol 4
Chapter 7 (part of page172 [Trials])	Covered in BR 45 Vol6(1)
Chapter 8	Chapter 7 and from BR 45 Vol 8
Chapter 9	Chapter 8 and from BR 45 Vol 4
Chapter 10	Chapter 9 and from BR 45 Vol 4
Chapter 11	Chapter 10 and from BR 45 Vol 4
-------------	New Chapter 11 from BR 45 Vol 4 and new data
Chapter 12	Chapters 12 / 15 and from BR 45 Vols 4 & 6(1)
Chapter 13	Chapters 12 / 15 and from BR 45 Vols 4 & 6(1)
Chapter 14	Chapter 14 and from BR 45 Vol 6(1)
Chapter 15	Chapter 15 and from BR 45 Vols 3 & 6(1)
Chapters 16-18	Chapters 16-18
Chapter 19	Chapter 19 and from BR 45 Vols 4 and 8(1)
Appendices 1-6	Appendices 1-6
Appendix 7	Appendices 7 and 10 (Appendices 8 / 9 are spare)

FORMULA NUMBERING: 1987 AND 2008 EDITIONS

Existing formula numbers from the 1987 edition have been retained, although their order of presentation may now be out of numerical sequence. Where formulae have been transferred to an Appendix or were in chapters whose numbers have altered (ie new Chapters 8 & 10 and new Appendices 5, 7 & 10) the new Chapter / Appendix number prefix is used but the 1987 number is shown as well (eg "**. . . 8.1 (1987 Ed . . . 9.1)**"). No formulae have been re-allocated to a different previously-used number; where additional formulae have been introduced into a sequence, they have been inserted with an alphabetical suffix (eg "**. . . 5.24a**").

BIBLIOGRAPHY

The following references have been consulted in the production of this book:

Admiralty Manual of Navigation (BR 45) - Volume 1 [1987 Edition].
Admiralty Manual of Navigation (BR 45) - Volumes 3, 4, 6 and 8.
Norrie's Nautical Tables (Imray Laurie Norie and Wilson Ltd, 1977).
UKHO Publications and Charts.
Bowditch, N (American Practical Navigator Vol I ,1977) Defence Hydrographic Mapping Centre.

ACKNOWLEDGEMENTS AND COPYRIGHT

MOD and Royal Navy Staffs

The contribution of the navigation, hydrographic, meteorological and oceanographic staffs of MoD DE & S (Sea Systems Directorate), Fleet HQ, Flag Officer Sea Training, the Royal Navy's Maritime Warfare School (Navigation & Seamanship Training Unit and HM Training Group) is acknowledged with thanks, particularly for the extensive validation of the material within this book.

UK Hydrographic Office (UKHO)

Thanks are due to the *UK Hydrographic Office* (*UKHO*) for their permission and assistance in reproducing data contained in this volume. This data has been derived from material published by the *UKHO* and further reproduction is not permitted without the prior written permission of the British Ministry of Defence DIPR and *UKHO*. Applications for permission should be made to MoD DIPR at the address shown on page ii and also to the Licensing Manager at UKHO, Admiralty Way, Taunton, Somerset TA1 2DN.

Offshore Systems Limited (OSL) - OSI Geospatial Group

Thanks are due to Offshore Systems Limited (OSL) for the use of screenshots and other information from 'ECPINS®' chart software fitted in Royal Navy '*Warship ECDIS'* (*WECDIS*) equipments.

Associated British Ports, Southampton

Thanks are due to Associated British Ports, Southampton for their permission to reproduce the AIS / radar image at Fig 9-11. Further reproduction of this image is not permitted without the prior written permission of MoD DIPR and Associated British Ports, Southampton. Applications for permission should be made to MoD DIPR at the address shown on page ii and also to the Harbour Master, ABP Southampton, VTS Centre, 37 Berth, Eastern Docks, Southampton, SO14 3GG.

Miss Catherine Hohenkerk, BSc (Hons), FRAS, MBCS

Special thanks are due to Miss Catherine Hohenkerk of HM Nautical Almanac Office (*UKHO*), for her contributions to this book, and in particular for checking and advising on the mathematical elements of Chapters 1-5 and Appendices 1-6.

Mr Christopher Peacock, MA (Cantab), C Eng, M I Mech E

Special thanks are due to Mr Christopher Peacock for his meticulous validation of this entire book, and especially for checking and advising on its mathematical elements.

Lieutenant Commander A S Peacock, MSc, FNI, AFRIN, RN

Thanks are due to Lieutenant Commander A S Peacock RN for his permission to reproduce the photograph at Fig 15-26. Further reproduction of this photograph is not permitted without the prior written permission of Lieutenant Commander Peacock. Applications for permission should be made to MoD DIPR at the address shown on Page ii; any such applications will be forwarded to Lieutenant Commander Peacock.

General

BR 45 Volume 1 is British Crown copyright and further reproduction is not permitted without the prior written permission of MoD DIPR at the address shown on Page ii.



Fig 0-1. T23 Frigate Entering Portsmouth Harbour (UK)

CHAPTER 1

POSITION AND DIRECTION ON THE EARTH'S SURFACE

CONTENTS

Para

0101. Scope of Chapter
0102. Choice of Units for Measuring Angles

SECTION 1 - POSITION ON THE EARTH'S SURFACE

0110. The Shape of the Earth
0111. Latitude and Longitude
0112. Difference of Latitude and Difference of Longitude
0113. Linear Measurement of Distance and Speed
0114. Linear Measurement of Latitude and Longitude
0115. The Earth as a Sphere
0116. Astronomical Positions Used with a Spheroidal Earth

SECTION 2 - DIRECTION ON THE EARTH'S SURFACE

0120. Direction
0121. The Gyro Compass
0122. The Magnetic Compass
0123. Magnetic Courses / Bearings and Compass Courses / Bearings
0124. Practical Application of Magnetic Compass Errors
0125. Checking Magnetic Deviation
0126. Relative Bearings
0127. The Radian Rule

INTENTIONALLY BLANK

CHAPTER 1

POSITION AND DIRECTION ON THE EARTH'S SURFACE

0101. Scope of Chapter

Chapter 1 introduces the basic terms dealing with position and direction on the Earth's surface. More detailed geodetic information about the Earth's shape and definition of position on the Earth's surface in relation to *Spheroids* and *Datums* is at Chapter 3.

0102. Choice of Units for Measuring Angles

From ancient Greek times, 'degrees' (˚) have been used to measure angles, with 360˚ in one complete revolution. Conveniently, 360 is exactly divisible by all single-digit prime numbers except 7 (ie 2, 3 & 5) and by their multiples (ie 4, 6, 8 & 9). See also Appendix 1.

0103-0109. Spare

SECTION 1 - POSITION ON THE EARTH'S SURFACE

0110. The Shape of the Earth

a. **The Earth's Dimensions.** The Earth is not a perfect *Sphere*; it is slightly flattened at the top and bottom, the smaller diameter being about 23.1 *n.miles* less than the larger. The Earth's 'flattened' shape is known as an *Oblate Spheroid* (see Fig 1-1 below) with an *Equatorial* radius '*a*' of approximately 3443.9 *n.miles* and a *Polar* radius '*b*' of 3432.4 *n.miles* (*International Nautical Miles* of 1852 m based on *WGS 84 Datum*).



Fig 1-1. The Shape of the Earth - an Oblate Spheroid

b. **The Earth's Rotation.** The Earth turns about its shortest diameter (*PP*' in Fig 1-1 above). An *Oblate Spheroid* is a figure traced out by the revolution of a semi-ellipse such as *PWP*', about its minor axis *PP*'. The Earth revolves about its *Axis PP'* in the direction shown; this direction of revolution is East, the opposite direction is West. The North *Pole* is on the left and the South *Pole* on the right of an observer facing East.

(0110) c. **Terminology.** The following definitions have been established to describe key aspects and measurements of the Earth's shape (see Fig 1-1 previous page).

- **Axis (of the Earth).** The Earth's *Axis* is its shortest diameter (*PP*'), about which it rotates in space.
- **Poles (of the Earth).** The *Poles* are the extremities of the *Axis* of the Earth.
- **Great Circle.** A *Great Circle* is the intersection of a *Spherical* surface and a plane which passes through the centre of the *Sphere*. It is the shortest distance between two points on the surface of a *Sphere*. See *Geodesic* and Note 1-1.
- **Geodesic.** See Note 1-1 (below) and full definition at Para 0540a.
- **Small Circle.** A *Small Circle* is the intersection of a *Spherical* surface and a plane which does NOT pass through the centre of the *Sphere* (see also Para 0115 / Fig 1-9). See Note 1-1 below.
- **Meridian.** A *Meridian* is a semi-*Great Circle* on the Earth's surface whose ends lie at opposite *Poles*. *Meridians* are shown by the successive positions of *PWP*' in Fig 1-1. **See Para 0202a for explanation of *Rhumb Line*.**
- **Prime Meridian.** The *Prime Meridian* (also known as the *Greenwich Meridian)* passes through the Greenwich Observatory (London, UK). The *Prime Meridian* is the starting point (0°) for the measurement of *Longitude*, East and West from this *Meridian*.
- **Equator.** The *Equator* is the line traced out on the Earth's surface by the mid points of the *Meridians*. The *Equator* is shown by the successive positions of *W* in Fig 1-1 and its plane is perpendicular to the Earth's *Axis*.

Note 1-1. *The Geodesic is the equivalent of a Great Circle on a Spheroid. In everyday use, the terms 'Great Circle' (in lieu of 'Geodesic') and 'Small Circle' are applied to the Earth's Oblate Spheroidal shape. See details at Paras 0115 and 0540.*

0111. Latitude and Longitude

a. **Latitude.** A position on the Earth's surface may be expressed by reference to the planes of the *Equator* and the *Prime Meridian* (see Note 1-2). Fig 1-2 (opposite) shows a *Meridional* section of the *Spheroid*; the *Latitude* of point *M* is the angle *MLE* (ϕ), where *L* is the point of intersection of the perpendicular to the Earth's surface at *M* and the plane of the *Equator* OE. It should be noted that in a *Spheroid*, point *L* may not coincide with point *O* (centre of the Earth). Two definitions arise from this:

- **Definition of Latitude.** The *Latitude* of a place on the Earth's surface (also called the *Geodetic, Geographical* or *True Latitude*) is the angle that the perpendicular at that place makes with the plane of the *Equator* and is measured from 0° to 90° North or South of the *Equator*.
- **Parallels of Latitude.** Planes parallel to the plane of the *Equator* are known as *Parallels of Latitude*. Except for the *Equator* itself, which is a *Great Circle*, they also comprise *Small Circles* (see Para 0115 / Fig 1-9).

Note 1-2. *A technical definition of 'Absolute Position' for use in Naval Command Systems is at BR 45 Volume 9.*

(0111a continued)



Fig 1-2. The *Latitude of Point M on the Earth's Surface
(also called Geodetic Latitude, Geographical Latitude or True Latitude*)**

(0111) b. **Longitude.** The *Longitude* of a place on the Earth's surface is the angle between the *Prime* (*Greenwich*) *Meridian* and the *Meridian* of that place, measured from 0˚ to 180˚ East or West of Greenwich (see Fig 1-3 below). In Fig 1-3, the *Longitude* of *F* is the arc *AB* = angle *AOB* (East of Greenwich).



Fig 1-3. The Longitude of Point F on the Earth's Surface

c. **Notation.** From the chart, Semaphore Tower in Portsmouth Naval Base, is in *Latitude* 50 degrees 47 minutes 59 seconds North of the *Equator* and in *Longitude* 1 degree 6 minutes 37 seconds west of Greenwich (*WGS 84*). This may be expressed as:

50˚ 47' 59"N	1˚ 06' 37"W	(for traditional use)
50˚ 47'.98N	1˚ 06'.62W	(*UKHO* accepted notation for Admiralty charts)
50˚ 47.98'N	1˚ 06.62'W	(alternative notation - common usage)
+ 50˚.79972	- 1˚.11028	(for calculator use, +ve for N and E)

The alternative notation (eg 50˚ 47.98'N 1˚ 06.62'W) is used in this book.

0112. Difference of Latitude and Difference of Longitude

a. **Difference of Latitude (d.lat).** The *Difference of Latitude* (*d.lat*) between two places is the arc of the *Meridian* between the two *Parallels of Latitude*. When proceeding from one place to another, *d.lat* is named North or South according to whether the *Latitude* of the destination is North or South of the *Latitude* of the place of departure. In Fig 1-4 (below) the *d.lat* between *F* and *T* is the same as the *d.lat* between *G* and *T*, where *GF* is the *Parallel of Latitude* through *F*.



Explanation: d.lat from F to T = angle GCT (south) = Lat F - Lat T

Note: 'C' is the centre of a circle and arc 'GT' is part of its circumference. Thus on a Spheroid (Ellipsoid), the position of 'C' will move relative to 'O' as arc 'GT' moves over the surface of the Spheroid.

Fig 1-4. Explanation of the "d.lat" Calculation

b. **Difference of Longitude (d.long).** The *Difference of Longitude* (*d.long*) between two places is the smaller arc of the *Equator* between their *Meridians*. When proceeding from one place to another, *d.long* is named East or West according to whether the *Meridian* of the destination is East or West of the *Meridian* of the place of departure. In Fig 1-5 (below), the *d.long* between *F* and *T* is the same as the *d.long* between *B* and *A*, where *FB* is the *Meridian* through *F*.



Explanation: d.long from F to T = arc BA = angle BOA (West) = angle FPT.
Angle FPT is the angle at the Pole between the Meridians of F and T.

Fig 1-5. Explanation of the "d.long" Calculation

(0112) c. **Calculation of "d.lat" and "d.long".** The rule for finding the *d.lat* and the d.*long* is as follows:

Same Names: SUBTRACT Opposite Names: ADD

If, when using this rule, the sum of the *Longitudes* exceeds 180°, this sum is subtracted from 360° to find the smaller angle and the name is reversed.

Examples 1-1 to 1-3.

Find the d.lat and d.long between:

1-1. Portsmouth (F): (50°48'N, 1°07'W) and New York (T): (40°40'N, 74°00'W).
1-2. Malta (F): (35°53'N, 14°31'E) and Gibraltar (T): (36°07'N, 5°21'W).
1-3. Sydney (F): (33°52'S, 151°13'E) and Honolulu (T): (21°18'N, 157°52'W).

Example 1-1.	Lat F 50°48'N	Long F	1°07'W
	Lat T 40°40'N	Long T	74°00'W
	d.lat 10°08'S	d.long	72°53'W
Example 1-2.	Lat F 35°53'N	Long F	14°31'E
	Lat T 36°07'N	Long T	5°21'W
	d.lat 0°14'N	d.long	19°52'W
Example 1-3.	Lat F 33°52'S	Long F	151°13'E
	Lat T 21°18'N	Long T	157°52'W
	d.lat 55°10'N	d.long	309°05'W
		subtract from	360°
		d.long	50°55'E

0113. Linear Measurement of Distance and Speed

a. **The Statute Mile**. The *Statute Mile* (also known as the *Land Mile*) is a standard fixed length of 1760 yards or 5280 feet (1609.36 m).

b. **The Geographical Mile.** A *Geographical Mile* is the length of 1' of arc measured along the *Equator* (ie 1' of *Longitude*); its value is 1855.3 m (*WGS 84*). As the *Equator* is a circle (*Great Circle*), the *Geographical Mile* is the same length at all parts of the *Equator* and is equal to "*a* sin 1' of arc", where "*a*" is the radius of the *Equator*.

c. **The International Nautical Mile.** The *International Nautical Mile* is a standard fixed length of 1852 m. Its abbreviation is the term "*n mile*" (or "*n.mile*" or "*nm*").

d. **The Knot.** In navigation, it is convenient to have a fixed or standard unit for measuring speed. This unit is called a *Knot*, and is one *International Nautical Mile* (1852 m) per hour. Its abbreviation is the term "*kn*" (NOT "kt"). The name '*Knot*' originates from running out a log line with distances marked by knots tied in the line. In normal practice, the errors arising from using *Sea Miles* (see Paras 0113e/f overleaf) instead of *International Nautical Miles* (*n.miles*) are very small (less than 0.5%); see details at Para 0113g (overleaf).

(0113) e. **The Sea Mile.** The *Sea Mile* is the length of one minute of arc (1') measured along the *Meridian* in the *Latitude* of the position (see explanation at Fig 1-6 below). On Admiralty charts on the *Mercator Projection* (see Chapter 4), the *Latitude* graduations form a *Scale* of *Sea Mile* (see Note 1-3 below). Except on charts (where the symbol 'M' is used) the *Sea Mile* is denoted by ', which is also the symbol for a minute of arc. Thus, 10'.8 (or 10.8') means 10.8 *Sea Mile*s. Traditionally, the symbol was always placed before the decimal point, but increasingly, this convention has altered and placing the symbol at the end of the expression (eg 10.8') is now considered equally acceptable.

Note 1-3. *It is a common but mistaken practice for mariners to refer to a 'Sea Mile' as a 'Nautical Mile'. The British Standard Nautical Mile was discarded in 1970.*

f. **Length of the Sea Mile.** The *Radius of Curvature* in the *Meridian* (see Fig 1-6 below) increases as *M* moves from the *Equator* to the *Pole*; thus, the distance subtended by 1' of arc also increases. The length of the *Sea Mile* is shortest at the *Equator* (1842.9 m) and longest at the *Poles* (1861.6 m), with a mean value of 1852.2 m at 45˚ *Latitude* (all *WGS 84*).

g. **Practical Differences: International Nautical Miles and Sea Miles.** In normal practice, the errors arising from using *Sea Miles* instead of *International Nautical Mile* are very small (effectively zero error at 45˚ *Latitude,* 0.5% [short] at the *Equator* and 0.5% [long] at the *Poles*). However, it is sometimes necessary to determine the error and the procedure for this is at Para 0314. Formulae (3.8 to 3.10) [see Para 0314] give the length of 1' of arc of *Latitude*; their derivation is at Appendix 5.

h. **Length of a Cable.** One-tenth of a *Sea Mile* is known as a *Cable*, which varies between 184.3 m (201.55 yds) and 186.2 m (203.63 yds) according to *Latitude*. A *Cable* thus approximates to 200 yards, and this nominal distance is a convenient measure normally used at sea for short-range navigational purposes.



***Note**: Position 'C' is the centre of a circle and arc 'AB' is part of its circumference. Thus on the Spheroid (Ellipsoid), the position of 'C' will move relative to 'O' as arc 'AB' moves over the surface of the Spheroid.*

Explanation: If M is the place on the Earth's surface, C the centre of circular curvature at M, and AMB is an arc of the *Meridian* subtending an angle of 1', then AMB is the length of the *Sea Mile* at M.

Fig 1-6. The Sea Mile

0114. Linear Measurement of Latitude and Longitude

a. **Linear Measurement of Latitude.** The *Linear Latitude* of a place is the length of the arc of the *Meridian* between the *Equator* and that place. It is measured in *Sea Miles* North or South of the *Equator* (see explanation at Fig 1-7 below).



Explanation: If M is in *Latitude* 60°N, then angle MLW = 60° = 60 x 60 minutes of arc = 3600'.
If place M_1 is 1800' south of the *Equator*, its *Latitude* is 1800 / 60 = 30°S.

Fig 1-7. Linear Measurement of Latitude

b. **Linear Measurement of Longitude.** The *Linear Longitude* of a place is the smaller arc of the *Equator* between the *Prime Meridian* and the *Meridian* of the place. Along the *Equator*, it is measured in *Geographical Miles*, (see Para 0113b) East or West of the *Prime Meridian* (see explanation at Fig 1-8 below).



Explanation: If point B is 40°E of the *Prime Meridian* PAP', the angle AOB is 40°, the arc AB of the *Equator* is 40° = 40 x 60 = 2400 minutes of arc along the *Equator* = 2400 *Geographical Miles*

Fig 1-8. Linear Measurement of Longitude

(0114) c. **Variation in Linear Distance of Longitude with Change in Latitude.** *Meridians* converge to meet at a point at the *Poles*, and thus the distance on the Earth's surface between any two *Meridians* is greatest at the *Equator* and diminishes until it is zero at the *Poles* (see Fig 1-8, previous page). The linear distance of a degree of *Longitude* on the surface of a *Spherical* Earth varies with the cosine of the *Latitude* [see formula (1.1) below], but in practice with the *Spheroidal* Earth's shape this is only an approximation.

With a *Spherical Earth* at *Latitude* ϕ :

$$1^\circ \text{Longitude} = \text{Linear distance at Equator} \times \text{cosine Latitude}\ \phi \qquad \ldots \mathbf{1.1}$$

d. **Linear Distance of Longitude - Errors.** In practice (*WGS 84 Spheroid*), the percentage errors in assuming formula (1.1) increase towards the *Poles*, but as linear distance between *Meridians* decreases towards the *Poles,* these two variables work against each other [see formula (3.12)]. Formulae (1.1) and (3.12) produce a maximum linear error at about *Latitude* 60 °, as follows:

- At the *Equator*: 0.0% error (0.0 metres)
- At *Latitude* 10°: 0.01% error (0.6 metres)
- At *Latitude* 30°: 0.08% error (81 metres)
- At *Latitude* 45°: 0.17% error (132 metres)
- At *Latitude* 60°: 0.25% error (140 metres)
- At *Latitude* 80°: 0.33% error (63 metres)
- At *Latitude* 89°: 0.34% error (0.6 metres)

In all cases the approximate distance is greater than the precise calculation. Formulae (3.8 to 3.12) [see Para 0314] give the precise *Spheroidal* distances.

0115. The Earth as a Sphere

a. **Properties of a Sphere.** A *Sphere* is the figure formed by rotating a semi-circle about its diameter. The following definitions are repeated from Para 0110c for the convenience of readers (see *Great* & *Small Circles* at Para 0115c / Fig 1-9 opposite).

(Extracts from Para 0110c):

- **Great Circles.** Any plane through the centre of the *Sphere* cuts the surface in a *Great Circle.*
- **Small Circles.** Any plane which cuts the surface of the *Sphere*, but does not pass through the centre, is called a *Small Circle.*

b. **Effect of Assuming the Earth as a Sphere.** Although the shape of the Earth is that of an *Oblate Spheroid*, for most purposes of navigation it may be assumed to be a *Sphere*, with radius equal to the mean of the greatest and least radii and measuring approximately 3438 *n.miles* (*International Nautical Miles* with *WGS 84* - see Note 1-4 below). Thus, when the Earth is regarded as a *Sphere*, *Meridians* of *Longitude* become *Great Circle*s which cut the *Equator* at right angles and join the *Poles*. The *Equator* is a *Great Circle* but all other *Parallels of Latitude* are *Small Circles*.

Note 1-4. *Where 'a' is the Equatorial radius and 'b' the Polar radius, the Earth's arithmetical mean radius is:*

$$\frac{a+b}{2} = 6{,}367{,}444.657 \text{ metres} = 3438.14506 \text{ n miles} \quad (WGS\ 84)$$

(0115) c. **Practical Use of the Great Circle.** The *Great Circle* gives the shortest distance between two points on the surface of a *Sphere*; for practical purposes, this term may also be applied to the surface of the Earth's *Oblate Spheroid* shape (ie as a *Geodesic* - see Para 0540a) without appreciable error. A *Great Circle* may thus be regarded as the shortest distance between two points on the Earth's surface and is also the path taken by an electro-magnetic radiation near the Earth's surface (radio, radar, light, etc).



Fig 1-9. The Earth as a Sphere

d. **Approximation of Distances - Assuming the Earth as a Sphere.** Using the mean radius for the *Sphere* derived from *WGS 84* (see Para 0115b opposite), the length of 1' of *Latitude* on the *Meridian* (or 1' of *Longitude* on the *Equator*) equals 1852.2 m. This distance approximates very closely to the length of the *International Nautical Mile* of 1852 m. Thus without appreciable error (see Note 1-5 below), the Earth may be treated as a *Sphere* where:

- 1' of *Latitude* equates to 1 *n.mile* (*International Nautical Mile*) anywhere.
- On the *Equator*, 1' of arc of *Longitude* equates to one *n.mile*.
- *Linear Latitude* and *Longitude* may be measured in the same units (*n.miles*).

Note 1-5. *The errors introduced by assuming a Spherical Earth based on the International Nautical Mile are not more than 0.5% for Latitude, 0.2% for Longitude.*

0116. Astronomical Positions Used with a Spheroidal Earth

Astronomical observations measure angles from the horizon, which is itself referenced to the local vertical (*Zenith*). If the Earth was *Spherical*, the *Zenith* line produced would pass through the centre of the Earth (which is also the centre of the *Celestial Sphere*) and positions from astronomical observations could be plotted without error. With a *Spheroidal Earth*, the *Zenith* line produced does NOT pass through the centre of the Earth except at the *Equator* and *Poles*; elsewhere, a small error occurs which is maximum at *Latitude* 45°. This error is NOT significant for distant celestial bodies (ie the sun, planets and stars), but can reach 0.2' of sextant altitude for the Moon; a correction for this is applied automatically in HM Nautical Almanac Office's *NAVPAC* software (available from *UKHO* as DP330 - see details at Para 0210a).

0117-0119. Spare.

SECTION 2 - DIRECTION ON THE EARTH'S SURFACE

0120. Direction

a. **True Direction.** The true direction between two points on the Earth's surface is given by the *Great Circle* between them; it is expressed as the angle between the *Meridian* and *Great Circle* (angle *PFT* in Figs 1-10a/b below). A technical definition of '*Direction*' for use in Naval Command Systems is at BR 45 Volume 9.


P
30°
T
030°
F
P'
True Bearing (small angle) - measured clockwise from *Meridian* to *Great Circle*

Fig 1-10a. True Bearing (Small Angle)


TRUE NORTH
P
030°
T
30°
F
True Bearing (small angle) - *Great Circle* treated as straight line over short distances

Fig 1-10b. True Bearing (Small Angle)

b. **True North.** *True North* is the northerly direction of the *Meridian* and is the reference from which true bearings and courses are measured.

c. **The Navigational Compass.** The navigational compass provides the reference direction from which courses and bearings may be measured. There are two principal types of compass: the *Gyro Compass* and the *Magnetic Compass*, both of which are described in detail in BR 45 Volume 3. The general principles of the two principal types of compass are described at Paras 0121 and 0122 respectively, with an explanation as to how true courses and true bearings may be obtained from them.

d. **True Bearing.** The true bearing of an object is the angle between the *Meridian* and the direction of the object.

- The true bearing of *T* from *F* is given by the angle *PFT* in Fig 1-10a (above) and Fig 1-11a (opposite), where *PF* is the *Meridian* through F and *FT* is the *Great Circle* joining *F* to *T.*
- Angle *PFT* is measured clockwise from 000˚ to 360˚. In Fig 1-10a (above), *T* bears 030˚ from F; in Fig 1-11a (opposite), T bears 330˚ from F.
- Over short distances the *Great Circle* may be drawn as a straight line without appreciable error, as in Fig 1-10b (above) and Fig 1-11b (opposite). The error varies with the *Latitude* and the bearing.

(0120d continued)



True Bearing (large angle) - measured clockwise from *Meridian* to *Great Circle*

Fig 1-11a. True Bearing (Large Angle)



True Bearing (large angle) - *Great Circle* treated as straight line over short distances

Fig 1-11b. True Bearing (Large Angle)

(0120) e. **Position by Bearing and Distance - Notation.** Rather than specify a position by *Latitude* and *Longitude*, it is often convenient to indicate either a position of an object from an observer by bearing and distance, or a position by bearing and distance from a known object. There are two notations for this: bearings centred on the observer and bearings centred on the object. It is essential to establish clearly the difference between these notations as otherwise an error of 180˚ may occur:

- **Position of an Object From an Observer.** When the position of an object is indicated from an observer by bearing and distance (as when taking a *Fix*), the convention is the state the object first, then the bearing and distance (eg Start Point Light 270˚ 4.0 *n.miles*). This indicates that the object is to the West of the observer.

- **Position from an Object.** When a position from a known object is indicated by bearing and distance (as in specifying a rendezvous position), the convention is to state the bearing first, then the object and then distance (eg 090˚ Start Point Light 4.0 *n.miles*). This indicates that the position is to the East of the object.

f. **True Course.** True course is the direction along the Earth's surface in which the vessel is being steered (or is intended to be steered). It is measured by the angle between the *Meridian* through the vessel's position and the fore-and-aft line, clockwise from 000˚ to 360˚. A technical definition of '*Course*' for use in Naval Command Systems is at BR 45 Volume 9.

g. **True Heading.** True course is not to be confused with *Heading* (or *Ship's Head*), which is the instantaneous direction of the ship and is thus a constantly changing value if the ship *Yaws* across the course due to the effect of wind, sea and steering errors. A technical definitions of '*Yaw*' and '*Heading*' for use in Naval Command Systems is at BR 45 Volume 9.

0121. The Gyro Compass

The *Gyro Compass* first made its appearance in the early part of the 20th century; in its simplest form it comprised a rapidly rotating wheel (*Gyroscope*), the *Spin Axis* of which was made to point along the *Meridian* to *True North*. By the late 20th / early 21st centuries, *Gyro Compasses* became extremely accurate, reliable instruments; some now use *Fibre Optic Gyro* (*FOG*) technology with few, if any, moving parts. See Para 0920 for *Gyro Compass* theory.

a. **Gyro Compass Output.** Provided there is no *Gyro* error, the *Gyro Compass* provides true courses and bearings, measured clockwise from 000˚ to 360˚.

b. **Gyro Compass Errors.** For a number of reasons the *Gyro Compass* may not always point exactly towards *True North*. Any *Gyro* error must be established before the *Gyro Compass* may be used as an accurate reference (see details at Para 0811).

c. **Gyro Repeater Error.** The alignment of the *Lubbers Line* of *Gyro* repeaters to *Ship’s Head* (see Fig 8-1 at Para 0802) should be checked frequently and adjusted if necessary. On offset repeaters (eg Bridge Wings) an incorrect alignment may not be easily noticed but will cause significant errors (see procedure at Para 1230f).

d. **Gyro Error Magnitudes.** The maximum error in Royal Navy *Gyro Compasses* in adverse conditions is normally better than ¼˚ at the *Equator* and ½˚ at *Latitude* 60˚, and much better in good conditions (see details at BR 45 Volume 3). However, in some commercial *Gyro Compasses* the error may exceed this by one or two degrees.

e. **Calculating the Gyro Error.** If the true bearing of an object is known to be 075˚ and the *Gyro* bearing is 077˚, then the *Gyro* is reading 2˚ high (see Fig 1-12a below); similarly, if the *Gyro* bearing is 073˚, the *Gyro* is reading 2˚ low (see Fig 1-12b below).

f. **Correcting the Gyro Error.** In order to calculate the true bearing:

- **Gyro Error High.** If the *Gyro* error is **high**, it must be **subtracted** from the *Gyro* bearing **observed** (or added to bearings from the chart).
- **Gyro Error Low.** If the *Gyro* error is **low**, it must be **added** to the *Gyro* bearing **observed** (or subtracted from bearings from the chart).
- **Suffixes ‘G’ and ‘T’.** The suffixes ‘G’ or ‘T’ should be used where appropriate to denote *Gyro* or ‘True’ courses / bearings respectively.



Fig 1-12a. Gyro Error High



Fig 1-12b. Gyro Error Low

0122. The Magnetic Compass

The *Magnetic Compass* is a bar magnet freely suspended in the horizontal plane and acted upon by both the Earth's magnetic field and the magnetic properties of the ship.

a. **The Earth's Magnetic Field.** The Earth may be considered as a gigantic magnet. Magnetic lines of force emanate from the South *Magnetic Pole* (located in Antarctica). These lines of force follow approximate semi-*Great Circle* paths to the North *Magnetic Pole* (located in the Canadian Arctic). These *Magnetic Pole*s are not stationary but are continually moving over a largely unknown path in a cycle of some hundreds of years.

b. **The Magnetic Meridian.** A freely suspended *Magnetic Compass* needle acted on only by the Earth's magnetic field will lie in the vertical plane along the Earth's magnetic field line of force. This vertical plane is known as the *Magnetic Meridian* (*Magnetic North*). However, as the Earth's magnetic field is irregular, *Magnetic Meridian*s do not always point towards the *Magnetic Pole*s. In addition, the *Magnetic Pole*s are not 180˚ apart; thus, it is rare for the magnetic needle to point towards the *Magnetic Pole*.

c. **Magnetic North.** *Magnetic North* is the name given to the direction in which the 'North' end of a magnetic needle, suspended so as to remain horizontal, would point when subject only to the influence of the Earth's magnetism. It is the northerly direction of the *Magnetic Meridian*.

d. **Magnetic Variation.** *Magnetic Variation* (normally abbreviated to '*Variation*') is the angle between the geographic (true) *Meridian* and the *Magnetic Meridian*. It is measured East or West from *True North*; in Fig 1-13 (below) the *Variation* at point *F* is shown as 20˚ West. *Variation* has different values at different places and is gradually changing. Its value at any place may be found from navigational charts which give the *Variation* for a certain year, together with a note of its annual value of secular change for which allowance must be made. *Variation* may also be taken from special *Isogonic* charts on which all places of equal *Variation* are joined by *Isogonic* lines known as *Isogonals* (not to be confused with *Magnetic Meridian*s, which are lines of force).



Fig 1-13. Magnetic Variation (Example)

(0122) e. **Magnetic Deviation and Compass North.** If a *Magnetic Compass* is put in a ship, the presence of iron, steel or electrical equipment will cause the *Magnetic Compass* to deviate from the *Magnetic Meridian*. The angle between the *Magnetic Meridian* (*Magnetic North*) and the direction in which the needle points (*Compass North*) is called *Magnetic Deviation* (normally abbreviated to '*Deviation*'). It is measured East or West from *Magnetic North*.

f **Reducing Deviation.** As a ship alters course in a particular *Magnetic Latitude*, the magnetic field of the ship changes, both in direction and magnitude. Consequently, *Deviation* is different for different compass courses. In practice, the *Deviation* of a ship's *Magnetic Compass* is reduced to a minimum (usually less than 3°) by the fitting and adjustment of permanent magnets and soft-iron *Spheres* at the compass binnacle.

g. **'Swinging the Ship' to Establish Residual Deviation.** After adjustment of the permanent magnets and soft-iron *Sphere*s at the compass binnacle, the ship's residual *Deviation* is found by slowly 'swinging the ship' through 360° and noting the *Deviation* for the various compass *Headings* (see Note 1-6 below); this may easily be done at sea as a 'Comparison Swing' against the *Gyro Compass* (see Para 0125c). The residual *Deviation* may be tabulated (see Table 1-1 below) or drawn as a graph (see Fig 1-14 opposite); intermediate values may be obtained by interpolation. If there is any significant change of *Magnetic Latitude*, the swinging (and sometimes adjustment) procedures should be repeated. Detailed procedures are at BR 45 Volume 3.

Table 1-1. Table of (Example) Residual Deviations

COMPASS HEADING	BEARING OF DISTANT OBJECT		DEVIATION
	MAGNETIC (FROM CHART)	COMPASS (OBSERVED)	
N (000°)	236° M	237½ °C	1½ °W
NNE (022½°)	236° M	237¾ °C	1¾ °W
NE (045°)	236° M	237¾ °C	1¾ °W
ENE (067½°)	236° M	237½ °C	1½ °W
E (090°)	236° M	237 °C	1 °W
ESE (112½°)	236° M	236½ °C	½ °W
SE (135°)	236° M	235½ °C	½ °E
SSE (157½°)	236° M	235 °C	1 °E
S (180°)	236° M	234½ °C	1½ °E
SSW (202½°)	236° M	234 °C	2 °E
SW (225°)	236° M	234 °C	2 °E
WSW (247½°)	236° M	234¼ °C	1¾ °E
W (270°)	236° M	234¾ °C	1¼ °E
WNW (292½°)	236° M	235¼ °C	¾ °E
NW (315°)	236° M	236 °C	NIL
NNW (337½°)	236° M	237 °C	1 °W

EXAMPLE

Note 1-6. *In the Royal Navy, Forms RNS 374A (Record of Observations for Deviation) and RNS 387 (Table of Deviations) are used to record Deviations. They are tabulated every 22½° to facilitate the calculation of the various compass coefficients (see BR 45 Volume 3).*

(0122g continued)



Fig 1-14. Graph of (Example) Residual Deviations

0123. Magnetic Courses / Bearings and Compass Courses / Bearings

a. **Magnetic Courses and Bearings.** Magnetic courses and bearings are measured clockwise from 000˚ to 360˚ from *Magnetic North* (the *Magnetic Meridian*) and are given the suffix 'M', eg 075˚M. They differ from true courses and bearings by the *Variation* (see Fig 1-15). See also Para 0123c opposite.


P (North Geographical Pole)
Magnetic Meridian
True Meridian
20°
Westerly Variation
T
F
P'
TRUE NORTH
P
M
20°
065°
T
Westerly Variation
085° M
F

Explanation: The magnetic bearing (or course) of T from F (angle MFT) is 085°M, while the true bearing of T from F (angle PFT) is 065°. The difference is the *Variation*, 20°W.

Fig 1-15. Magnetic Courses and Bearings

b. **Compass Courses and Bearings.** Compass courses and bearings are measured clockwise from 000˚ to 360˚ from *Compass North*, and are given the suffix 'C', eg 195˚C. They differ from true courses and bearings by the *Variation* for the geographical location and the *Deviation* for the compass *Headings* (see Fig 1-16). See also Para 0123c opposite.


C
P
M
Easterly Deviation
Westerly Variation
T
F
P'
TRUE NORTH
P
M
C
T
Variation (20°W)
Deviation (10°E)
45°
F

Explanation: The compass bearing (or course) of T from F (angle CFT) is 055°C, whereas the magnetic bearing (angle MFT) is 065°M and true bearing (angle PFT) is 045°. Angle MFC is the *Deviation* (10°E), and angle PFM is the *Variation* (20°W).

Fig 1-16. Magnetic Courses / Bearings and Compass Courses and Bearings

(0123) c. **'Traditional' Graduation of Older Magnetic Compass Cards.** Some older (mostly historical) *Magnetic Compass* cards may still be found which do not use 000˚ to 360˚ graduations, but instead, are graduated with 'traditional' markings:

- **Older Compass Cards.** Older *Magnetic Compass* cards were divided into four quadrants of 90˚, the angles being measured from North and South to East and West. For example, the bearing 137˚M would be shown as S43˚E.

- **Even Older Compass Cards.** Even older *Magnetic Compass* cards were divided into four quadrants by the cardinal points, North, East, South, West. Each quadrant is divided into eight equal parts, the division marks being called *Points*; each point has a distinctive name - North, North by East, North North East and so on. There were 32 *Points* in the whole card.

0124. Practical Application of Magnetic Compass Errors

a. **Compass Rose Magnetic Information.** All Admiralty (*UKHO*) charts have *Compass Roses* printed on them, containing the following information.

- **True and Magnetic Roses.** When there are two concentric *Roses*, the outer *Rose* represents the true compass and the inner the *Magnetic Compass* (see Fig 1-17 below). Some small-*Scale* charts have only the true *Compass Rose*.

- **Variation, Variation Change (and Deviation).** The *Variation,* the year for which it is correct and its annual rate of secular change are normally shown in the *Compass Rose* on its *Magnetic Meridian* (see Fig 1-17 below). Before using the magnetic *Rose* to lay off compass bearings or the compass courses, correction for the change in *Variation* (and *Deviation*) must be applied.



Fig 1-17. Compass Rose of the Type Printed on Admiralty Charts

(0124) b. **Difference Between 'Magnetic' and 'Compass'.** As defined at Para 0122, *Variation* is the difference between True and Magnetic, while *Deviation* is the difference between Magnetic and Compass, ie:

Magnetic = True ± *Variation*
Compass = Magnetic ± *Deviation* = True ± *Variation* ± *Deviation*

c. **Conversion of Magnetic and Compass Courses and Bearings to True.** The following rules should be applied for the conversion of magnetic or compass courses and bearings to true:

- Easterly *Variation* and *Deviation* are added or applied clockwise.
- Westerly *Variation* and *Deviation* are subtracted or applied anti-clockwise.
- The order of conversions (Compass-to-Magnetic-to-True) is:
  "Compass ± *Deviation* = Magnetic. Magnetic ± *Variation* = True"
  For True-to-Magnetic-to-Compass conversions, see Para 0124f overleaf.

d. **Mnemonics.** The conversion rules (Para 0124c above) may be easily memorised by the use of either of the two mnemonics shown below:

- '**CADET**'. When converting from compass to true, add East (ie **'C**ompass to True, **Ad**d **E**as**T'** ie ***"CADET"***). It follows that West *Variation* and *Deviation* are subtracted (see Para 0124f overleaf).
- **Alternative Rhyme.** An alternative (rhyming) mnemonic which may be used is: **"Error West, Compass Best; Error East, Compass Least.**"
- **'CDMVT'**. The 'Compass: *Deviation*: Magnetic: *Variation*: True' sequence may be summarised as '*CDMVT*' (ie ***"Cadbury's Dairy Milk Very Tasty"***).

e. **Methods for Laying off the Compass Course or Compass Bearing.** There are two methods available for laying off the compass course or bearing:

- **Method 1.** *Deviation* (for the compass course steered) and *Variation* (corrected to date) are applied in one step to the compass course or bearing in accordance with the above rule to obtain the true course or bearing. The parallel ruler is then placed at the true reading on the true *Compass Rose*.

Note 1-7. *The application of compass error in one step in Method 1 avoids a very common mistake, that of taking out the Deviation for the compass bearing of the object instead of the compass course of the ship.*

- **Method 2.** The parallel ruler is placed on the given compass bearing or course on the *Magnetic Compass Rose*. It is then slewed through a small angle (sometimes known as the *'Rose Correction'*) which is the algebraic sum of the *Deviation* and the change in *Variation* (taking +ve for East, -ve for West in accordance with mnemonics), to allow for:
  - The change in *Variation* to bring it up to date.
  - The *Deviation* for the compass course being steered.

Methods 1 and 2 are demonstrated overleaf at Examples 1-4 and 1-5 respectively.

(0124e) **Example 1-4 (Demonstrating Method 1 from Para 0124e opposite)**

A ship is steering 260˚C. *Variation* from the chart was 12˚W in 2007, decreasing 10' annually. The compass bearing of an object is 043˚C. Using the *Deviation* from Fig 1-14, what is the true course and how would the bearing be plotted using the above two methods? The year is 2010.

- **Calculation of the Deviation value that applies for Heading 260˚C**

Variation in 2007	12	˚W
Change in *Variation* 2007 to 2010: 3 x 10'E	½	˚E
Variation in 2010	11½	˚W
Thus *Deviation* applicable for 260˚C *Headings* =	1½	˚E

- **Application of CADET / CDMVT**

Compass *Headings*	260	˚C
Deviation	+ 1½	˚E
Magnetic *Headings*	261½	˚M
Variation	-11½	˚W
True course	250	˚T

Solution by Method 1 - Plotting the True Bearing

Compass bearing	043	˚C
Deviation	+ 1½	˚E
Magnetic bearing	044½	˚M
Variation	-11½	˚W
True bearing to be plotted	033	˚T

Note 1-8. *The compass error may be applied in one step (see Pare 0124e) to avoid the common mistake of taking out the Deviation for the compass bearing of the object instead of the compass course of the ship. In this case, the total error correction = +1½˚E - 11½˚W = -10˚W. Thus to convert to true while on compass Headings 260˚C, all compass bearings should be reduced by 10˚.*

(0124e) **Example 1-5 (Demonstrating Method 2 from Para 0124e opposite)**

Take the scenario from Example 1-4 (above). Place the parallel rule on the *Magnetic Compass Rose* in the direction 043˚M. Slew through a total *Rose Correction* of +2˚ clockwise (½˚ clockwise to allow for the easterly change of *Variation* and 1½˚ clockwise to allow for the easterly *Deviation*). Plot the bearing on the *Magnetic Compass Rose*, 045˚M. As *Magnetic North* on the *Magnetic Compass Rose* is already offset 12˚ to the West (see Fig 1-17), it will be immediately apparent that 045˚M is the same as 033˚T, the true bearing.

(0124) f. **Conversion of True Course to Compass Course.** To find the compass course from the true course, the mnemonic '*CADET*' (see Para 0124d) is used in the reverse direction, although it no longer forms a mnemonic:

True to Compass, add West (subtract East)

There is, however, a small complication. Before the Compass course may be found, the *Deviation* must be known, but that cannot be established until the Compass course in known. An iterative process follows, where the *Deviation* table is entered with the Magnetic course in lieu of Compass course. If the *Deviation* is large, a second calculation is required to establish the exact *Deviation* for the Compass course. This process is shown at Example 1-6 below.

Example 1-6. First and Second Approximations of Deviation for Compass Course

Using the *Deviations* at Fig 1-14 and a true *Headings* of 260˚ with 10˚W *Variation*, the following calculations are made:

1st Approximation

True course	260	˚T
Variation	+10	˚W
Magnetic course	270	˚M
Deviation (for 270˚M)	- 1¼	˚E
Approximate Compass course	268¾	˚C

The graph at Fig 1-14 indicates with this approximate course of 268¾˚C, the correct *Deviation* to use is nearer 1½˚E than 1 ¼˚E, thus giving the following 2nd approximation:

2nd Approximation

True course	260	˚T
Variation	+10	˚W
Magnetic course	270	˚M
Deviation (for 268¾˚M)	- 1½	˚E
Refined Compass course	268½	˚C

Note 1-9. *For practical purposes, providing that the Deviation is small, a second approximation is rarely necessary.*

0125. Checking Magnetic Deviation

a. **Principles.** If an accurate and reliable *Gyro Heading* is known, or a compass bearing is taken of a terrestrial or astronomical object whose true bearing is known, then provided the *Variation* is also known, the *Deviation* may be calculated and used to establish a new *Deviation* table. Various detailed procedures to establish *Deviation* exist; either by 'Comparison Swing' at Para 0125c (below) or by other methods at Para 0811, but the calculation required for all of them is at Example 1-7 (below).

Example 1-7. Calculating Deviation

By calculation, the sun's true bearing is 230˚T, the compass bearing is 235˚C and *Variation* 12˚W. What is the *Deviation*? (The same calculation is used if a Gyro 'Comparison Swing' is made, with Gyro *Heading* 230˚T and compass *Heading* 235˚C)

True bearing / *Headings*	230	˚T
Variation	+12	˚W
Magnetic bearing / *Headings*	242	˚M
Deviation (by subtraction 242˚-235˚ = 7˚)	**-7**	
Compass bearing / *Headings*	235	˚C

As 7˚ has to be subtracted from 242˚M to reach 235˚C, and since when calculating from 'True to Compass', East is subtracted (reverse of *CADET*), the *Deviation* is 7˚**E.**

b. **Acceptable Deviation Limits.** In practice, it should be possible to adjust a well placed *Magnetic Compass* to limit the residual *Deviation*s to less than 3˚. However, if a large change in *Magnetic Latitude* has taken place, any structural alterations have taken place near the compass, ferrous cargo loading / unloading has occurred etc, or if more than one year has elapsed since the previous compass swing (see full list of factors at BR 45 Volume 3), then a check 'Comparison Swing' (see Para 0125c below) should be carried out to establish a new *Deviation* table, as the residual *Deviations* may have changed substantially. Adjustment of the compass (ie moving magnets / *Spheres*) should only be carried out by a suitably qualified 'Compass Swinging Officer'.

c. **Establishing Magnetic Deviation by Gyro Compass 'Comparison Swing'.** As stated at Para 0122g, the ship's residual *Deviation* is found by slowly 'swinging the ship' through 360˚ and noting the *Deviation* for the various compass *Headings*, as compared to *Gyro Headings* (after making allowance for the correct *Variation* - see Para 0125a above); this may easily be done at sea as a 'Comparison Swing' without the need for a qualified 'Compass Swinging Officer'(as no compass adjustments are carried out).

- **Rate of Turn.** It is essential that the swing is carried out slowly, with a rate of turn no greater than 8˚ per minute (ie 360˚ in not less than 45 minutes); if necessary the ship may be steadied on each *Heading* for a period. Failure to observe this very slow rate of turn will not allow the ship's magnetism to adjust to each new *Heading*, and will result in a flawed set of readings.

0126. Relative Bearings

a. **"Red" or " Green".** *Relative Bearings* are normally stated relative to the ship's fore-and-aft line looking forward (ie from *Ship's Head*) and are measured from the bow from 0˚ to 180˚ on each side. Starboard bearings are prefixed "Green" and port bearings prefixed "Red". See Fig 1-18 below.

b. **"... Relative".** Occasionally, *Relative Bearings* are measured clockwise from 000˚ to 360˚ from *Ship's Head* and, if so, are given the suffix "Relative" (eg "135˚ Relative"). See Fig 1-18 below.

c. **"On the Bow" etc.** The expressions "On the bow", "On the beam" and "On the quarter" may be used with or without any specified number of degrees (or *Points* if 'traditional' language is used). When used without any specified number of degrees (or *Points* if 'traditional' language is used), they mean respectively 45˚ (4 *Points*), 90˚ (*8 Points*), and 135˚ (*12 Points*) from *Ship's Head*. When used with a specified angle, the meaning is as stated (see Fig 1-18 below).



Explanation: The bearing of X is "Green 30" (or 030° Relative) and that of Y is "Red 140" (or 220° Relative). Alternatively, X could be said to be "30° on the starboard bow" and Y to be "40° on the port quarter". If the ship is steering 045°, the true bearings of X and Y are 075° and 265° respectively.

Fig 1-18. Relative Bearings

0127. The Radian Rule

The 'Radian' is defined as the angle subtended at the centre of a circle by a length of arc equal to the radius. 'π' is defined as the ratio of the circumference of a circle to its diameter; this ratio is constant in all cases and π is approximately equal to 3.1415927. It can thus be shown (see Appendix 1 Para 2b) that 360˚ equates to 2π radians. From these definitions, it follows that:

$$1^\circ = \frac{2\pi}{360} \text{ radians}$$

and, at 1 *n.mile* (1852 metres):

$$1^\circ \text{ subtends: } \frac{2\pi}{360} \times 1852 \text{ metres} = 32.32 \text{ metres} = 35.35 \text{ yards} = 106.05 \text{ feet}$$

With small angles at reasonably short ranges, 1˚ may be taken to subtend 35 yards (approximately 100 feet) at 1 *n.mile* without serious error; this is known colloquially as the "*Radian Rule*".

CHAPTER 2

THE SAILINGS (1) - BASIC CALCULATIONS

CONTENTS

Para

0201. Scope of Chapter
0202 Rhumb Lines and Departure
0203. Parallel Sailing
0204. Plane Sailing
0205. Mean and Corrected Mean Latitude Sailing
0206. Traverse Sailing
0207. Mercator Sailing Overview
0208. Spherical Sailing - Great Circle Tracks
0209 Spherical Sailing - The Vertex and Composite Tracks
0210. Summary of Methods for Spherical Great Circle Calculations
0211. Spherical Great Circle Calculations - Cosine Method

INTENTIONALLY BLANK

CHAPTER 2

THE SAILINGS (1) - BASIC CALCULATIONS

0201. Scope of Chapter

a. **'Sailings'.** '*Sailings*' are terms used to describe the various mathematical methods of finding course and *Distance* from one place on the Earth's surface to another. Chapter 2 covers the following *Sailings*:

- *Parallel Sailing*.
- *Plane Sailing*.
- *Mean Latitude Sailing* and *Corrected Mean Latitude Sailing*.
- *Traverse Sailing*.
- *Mercator Sailing* (brief overview only).
- *Spherical Sailing* - *Great Circle* tracks (introduction only).
- *Spherical Sailing* - *Composite Tracks* (introduction only).

b. **Further Details.** *Mercator Sailing* is only introduced very briefly in Chapter 2, and further details are as follows:

- **Chapter 4.** *Mercator Projections* are covered in detail at Chapter 4.
- **Chapter 5.** The calculations involved in both *Spherical* and *Spheroidal Mercator Sailing* are set out Chapter 5, together with *Vertex* and the *Composite Track* calculations.

0202. Rhumb Lines and Departure

a. **Rhumb Lines.** A *Rhumb Line* is a curve drawn on the Earth's surface which cuts all *Meridians* at the same angle (see Fig 2-1 below).

- **Special Cases - Equator, Parallels of Latitude and Meridians.** As special cases, the *Equator* and *Parallels of Latitude* are *Rhumb Lines* of either 090˚ or 270˚, while *Meridians* are *Rhumb Lines* of either 000˚ or 180˚.
- **Other Rhumb Lines - Loxodromes.** Other *Rhumb Lines* (cutting *Meridians* at the same angle) spiral towards the *Pole* and are also called *Loxodromes*.
- **Use.** *Rhumb Lines* appear as straight lines on *Mercator Projection* charts and thus represent a ship's steady course.



Explanation: *Rhumb Line* curve *FT* cuts *Meridians* F, A, B, C and T at the same angle(θ) .

Fig 2-1. The Rhumb Line

b. **Departure.** *'Departure'* is the *Distance* made good in an East-West direction in sailing from one place to another along a *Rhumb Line*. The units of *Distance* used in *Departure* are the same as in *d.lat* (ie *Sea Miles*).

0203. Parallel Sailing

Parallel Sailing is a method of converting *Departure* along a *Parallel of Latitude* into *Longitude,* and assumes the Earth is a *Sphere*.

a. **The Arc of a Parallel of Latitude.** In Fig 2-2a (below), for a ship travelling along the *Equator* from *A* to *B*, the *Departure* and the *d.long* (*Difference of Longitude*) are equal. However, if the ship is travelling from *F* to *T* along any other *Parallel of Latitude* ϕ, the *d.long* λ is still *AB*, but the *Departure FT* (ie *Distance*) is numerically less than the *d.long*. The nearer the *Parallel of Latitude* is to the *Pole* (ie the higher the *Latitude*) the shorter *Departure FT* becomes, but the *d.long AB* does not alter.



Fig 2-2a. The Arc of a Parallel of Latitude



Fig 2-2b. Alteration of the Arc with a Change of Latitude

b. **Alteration of the Arc with a Change of Latitude.** The relationship between *Departure* and d.*long* may be found as follows (see Figs 2-2a/b above):

- The radius *r* of the circle of *Latitude* ϕ is $R \cos\phi$, where *R* is the radius of the *Sphere* (see Fig 2-2b above).
- The *Departure* (ie *Distance*) *FT* along the *Parallel of Latitude* is:

$= \lambda r$, where λ is in radians (see Fig 2-2a above)
$= \lambda R \cos\phi$ (see Fig 2-2b above)
$\therefore = AB \cos\phi$ (see Fig 2-2a above)
$\therefore = \lambda \cos\phi$ (where λ is in minutes, see Fig 2-2a above)
Departure = *d.long* (in minutes) cos *Latitude* . . . **2.1**

Thus for a *Sphere*, the *Departure* (*Distance*) along a *Parallel of Latitude* (in minutes of *Latitude*) equals *d.long* (in minutes of arc), times the cosine of the *Latitude*.

Examples 2-1 and 2-2.

2-1. At *Latitude* 40˚N with *Longitudes* of F (15˚E) and T (60˚E), the *d.long* is 45˚, or 2700' minutes of arc along the *Equator* (ie FT = 2700' cos 40˚ = 2068'.3).

2-2. Had the *Latitude* been 60˚N instead of 40˚N, the *Distance* along this new *Parallel of Latitude* would have been 2700' cos 60˚, ie 1350'.

0204. Plane Sailing

Plane Sailing is a method of solving the relationship between *d.lat* (*Difference of Latitude*)*, Departure* (see Para 0202b)*, Distance* and *Course*, when NOT *Parallel Sailing*; in this case, *Departure* does NOT equal *Distance*. *Plane Sailing* assumes the Earth is a *Sphere.* It does not involve *d.long* (*Difference of Longitude*) except indirectly (see Para 0205).



Fig 2-3. Departure, d.lat and Distance when Plane Sailing.

a. **Plane Sailing Formulae.** When a ship travels along any *Rhumb Line* other than a *Parallel of Latitude* or a *Meridian of Longitude* (ie not *Parallel Sailing*), its *d.lat*, *Departure*, *Distance* and *Course* may be considered as forming a plane right-angled triangle (see Fig 2-3 above). From this triangle it may be shown (and proved opposite at Para 0204b) that:

$$\text{Departure} = \text{Distance} \sin \text{Course} \qquad \ldots \mathbf{2.2}$$

$$d.lat = \text{Distance} \cos \text{Course} \text{ (but see Note 2-1)} \qquad \ldots \mathbf{2.3}$$

Dividing (2.2) by (2.3):

$$\tan \text{course} = \frac{\text{Departure}}{d.lat} \qquad \ldots \mathbf{2.4}$$

Note 2-1. *If using formula (2.3) to find the Distance, it has a fundamental weakness as the Course approaches 90°, because small errors in the Course introduce large errors in the Distance. Formula (2.2) should be used instead to find Distance in such cases.*

(0204) b. **Proof of the Plane Sailing Formulae.** The *Plane Sailing* formulae may be proved as follows. Consider the *Rhumb Line FT* in Fig 2-4 (below):



Fig 2-4. Division of the Rhumb Line (to Prove the Plane Sailing Formulae)

- **Division of the Rhumb Line**. In Fig 2-4 (above), let the *Rhumb Line FT* be divided into a large number '*n'* of equidistant *Parallels of Latitude* cutting the *Rhumb Line* at *F*, *A*, *B*, *C*, etc. Let the *Meridians* through the points cut the *Parallels of Latitude* at *X*, *Y*, *Z*, etc.
- **Small Triangles.** In the small triangles *FAX*, *ABY*, *BCZ* etc, the angles *FXA*, *AYB*, *BZC* are right angles. The angles *FAX*, *ABY*, *BCZ* are all equal, being equal to the *Course*. The sides *AX*, *BY*, *CZ* are all equal.
- **Consider as Plane Right-Angled Triangles.** These triangles are therefore equal in all respects and, as they are very small, may be considered as plane right-angled triangles. Thus, in the triangle *FAX* (et al):

$$AX = FA \cos Course$$
$$nAX = nFA \cos Course$$
$$d.lat = Distance \cos Course \qquad \text{. . . (formula 2.3)}$$
$$FX = FA \sin Course$$
$$nFX = nFA \sin Course$$
$$Departure = Distance \sin Course \qquad \text{. . . (formula 2.2)}$$

Dividing (2.2) by (2.3):

$$\tan Course = \frac{Departure}{d.lat} \qquad \text{. . . (formula 2.4)}$$

0205. Mean and Corrected Mean Latitude Sailing

There are two calculation methods by which a ship may determine its *Latitude* and *Longitude* after travelling along a *Rhumb Line* other than in a North-South or East-West direction. One of these methods uses the *Mean Latitude* or *Corrected Mean Latitude*, the other uses *Mercator Sailing* (introduced at Para 0207 and described at Chapter 5).

a. **Mean Latitude Sailing.** Consider the *Rhumb Line FT* in Fig 2-5 (below).

- **Relative Sizes of Departures.** The *Departure* of *FT* is greater than that of *HT* (ie *Departure* along the *Parallel of Latitude* through *T*), but less than that of *FG* (ie *Departure* along the *Parallel of Latitude* through *F)*. Therefore, the *Departure* from *F* to *T* must equal the *Departure* along a *Parallel of Latitude* lying somewhere between *FG* and *HT*. Let this *Parallel of Latitude* be *UV*.



Fig 2-5. Mean and Corrected Mean Latitudes

- **Mean Latitude.** Provided that the *d.lat* between *F* and *T* is fairly small and the *Latitudes* of *F* and *T* are not too high, this *Departure* is approximately equal to the arc of the *Parallel of Latitude MN*, which has as its *Latitude* the mathematical mean between *F* and *T*. This *Latitude* is referred to as the *'Mean Latitude'* (or *'Mean Lat'*). In these particular circumstances *MN* and *UV* are almost identical.

- **Mean Latitude Formula.** If *QR* is the *d.long* between *F* and *T*:

$$MN = QR \cos QM \qquad \text{. . . (formula 2.1)}$$

$$\textit{Departure} = \textit{d.long} \cos \textit{Mean Latitude} \text{ (for the } \textit{Sphere}\text{)} \qquad \text{. . . } \mathbf{2.5}$$

- **Errors.** However, formula (2.5) is not mathematically accurate except when *F* and *T* are on the same *Parallel of Latitude*.
  - **Distance.** In practice, the accuracy of this formula depends on how close *T* is to *F*, and it should NOT be used for *Distance*s exceeding 600'.
  - **Proximity to Equator.** If the *Latitudes* of *F* and *T* are on each side of the *Equator* and also within 10° of *Latitude* of the *Equator*, the *Departure* may be taken as the d.*long* without appreciable error (the maximum error in *Departure* cannot exceed 0.4%.)

(0205) b. **Corrected Mean Latitude Sailing - Formula.** The true or '*Corrected Mean Latitude*' between *F* and *T* is given by *UV* (see Fig 2-5 opposite). For the *Sphere* (see Note 2-2 below for the *Spheroid*), it may be shown (see Appendix 3) that the *Latitude* *L* of *UV* may be found from the following formulae:

Either:

$$\sec L = \frac{7915.7045}{d.lat(mins\ of\ arc)}\left[\log_{10}\tan\left(45°+\frac{T°}{2}\right) - \log_{10}\tan\left(45°+\frac{F°}{2}\right)\right] \qquad \ldots \mathbf{2.6}$$

Or (see Para 0422):

$$\sec L = \frac{DMP}{d.lat\ (mins\ of\ arc)} \qquad \ldots \mathbf{2.7}$$

c. **Corrected Mean Latitude Sailing - Terminology.** '*Corrected Mean Latitude*' is frequently referred to in nautical tables and other navigational publications as the '*Middle Latitude*', but in the BR 45 series the term '*Corrected Mean Latitude*' is used.

Note 2-2. *Rhumb Line position calculations for the Spheroid are at Paras 0530-0531.*

Example 2-3: Low Latitudes

A ship transits from position F (30°N, 40°W) to a point T (34°N, 36°W). Find the Departure, Course and *Distance* by both *Mean Latitude* and *Corrected Mean Latitude* methods.

- **Mean Latitude Sailing:**

$$d.lat = 4°N = 240'N$$
$$d.long = 4°E = 240'E$$
$$Mean\ Lat\ Sailing = \tfrac{1}{2}(30° + 34°)N = 32°N$$
$$Departure = 240' \cos 32°E = 203'.53E \qquad \ldots \text{(formula 2.5)}$$
$$\tan Course = \frac{Departure}{d.lat} \qquad \ldots \text{(formula 2.4)}$$
$$Course = 040.3°$$
$$\mathbf{Distance} = d.lat \sec Course = 240' \sec 040.3° = \mathbf{314'.68} \qquad \ldots \text{(formula 2.3)}$$

- **Corrected Mean Latitude Sailing:**

$$\sec L = \frac{7915.7045}{240'}\left(\log_{10}\tan\left(45° + \frac{34°}{2}\right) - \log_{10}\tan\left(45° + \frac{30°}{2}\right)\right) \qquad \ldots \text{(formula 2.6)}$$

$$L = 32°.033158\ (32°02')$$
$$Departure = 203.46'$$
$$Course = 040.3°$$
$$\mathbf{Distance} = \mathbf{314.64'}$$

- **Difference between Mean Latitude / Corrected Mean Latitude Sailing Results:** The difference in *Distances* (0.013%) between 314.68' for *Mean Latitude Sailing* and 314.64' for *Corrected Mean Latitude* is small, so *Mean Latitude Sailing* may be used here without appreciable error.

Example 2-4: High Latitudes

A ship in a high *Latitude* position F (70°N 20°W), steers a *Course* of 020° for a *Distance* of 600 miles. What is its *Latitude* and *Longitude* at the end of the run, by both *Mean Latitude* and *Corrected Mean Latitude Sailing* methods?

- **Mean Latitude Sailing:**

$$\begin{aligned}
d.lat &= 600' \cos 20^\circ N && \text{. . . (formula 2.3)}\\
&= 563.81557' N\\
&= 9.3969262^\circ \quad = \quad 9^\circ 23.8' N\\
\textbf{Latitude T} &= \mathbf{79^\circ 23'.8N}
\end{aligned}$$

$$\begin{aligned}
Departure &= 600' \sin 20^\circ E \quad = \quad 205.21209' E && \text{. . . (formula 2.2)}\\
Mean\ Lat &= 74.6984631^\circ N \quad = \quad 74^\circ 41.9' N
\end{aligned}$$

$$\begin{aligned}
d.long &= 205.21209' \sec 74.6984631^\circ E && \text{. . . (formula 2.5)}\\
&= 777.61623' E \quad = \quad 12^\circ 57.6' E\\
\textbf{Longitude T} &= \mathbf{7^\circ 02.4' W}
\end{aligned}$$

- **Corrected Mean Latitude Sailing:**

$$\sec L = \frac{7915.7045}{563.81557'}\left(\log_{10} \tan 84.698463^\circ - \log_{10} \tan 80^\circ\right) \qquad \text{. . . (formula 2.6)}$$

$$L = 75.197922^\circ \quad (75^\circ 11.9' N)$$

$$\begin{aligned}
d.long &= 205.21209' \sec 75.197922^\circ && \text{. . . (formula 2.5)}\\
&= 803.23871' E\\
&= 13.387312^\circ E \quad = \quad 13^\circ 23.2' E\\
\textbf{Longitude T} &= \mathbf{6^\circ 36.8' W}
\end{aligned}$$

- **Difference between Mean Latitude / Corrected Mean Latitude Sailing Results:** The difference in *Longitude* between *Mean Latitude* and *Corrected Mean Latitude Sailing* results is 25.6'E. From formula (1.1) [at *Latitude* 79° 23.8'N] this equates to 4.7 *n. miles*; over 600 *n. miles* this is 0.8% of the *Distance*. The discrepancy in position at the end of the run illustrates the danger of using the *Mean Latitude* method in high *Latitudes*, even though the *Distance* is only 600 *n. miles*.

0206. Traverse Sailing

Traverse Sailing is the term given to *Traverse* solutions for single or multiple *Plane Sailing*s (see Para 0204). The various leg(s) of the ship's track are the hypotenuses of a series of *Plane Sailing* triangles (see Fig 2-4 at Para 0204b). The individual *d.lats* and *Departures* may be found using formulae (2.2 to 2.4) and *d.long* using formula (2.5).

a. **Traverse Table.** The 'Traverse Table' in Norie's Nautical Tables solves the *d.lat* / *Departure* / *Distance* / *Course* plane triangles for any *Distance* up to 600'. Instructions for the use of these tables are given in the explanation within Norie's. The tables may also be used to find *d.long* by formula (2.5) by treating the *Course* as *Mean Latitude*, *d.lat* as *Departure* and *Distance* as *d.long*.

b. **Calculator or Spreadsheet.** A calculator or spreadsheet with trigonometric functions is quicker and more accurate to use than the Traverse Table. If a calculator or spreadsheet with co-ordinate conversion is available, it should be possible to read off *d.lat* and *Departure* directly using *Cartesian Coordinates* (x, y) (see Note 2-3 below). Using a calculator or spreadsheet avoids the need to interpolate between sets of figures in the Traverse Table.

c. **Polar and Cartesian Coordinates.** The position of point T (see Fig 2-6 below) may be defined in *Polar Coordinates* (r, θ) or *Cartesian Coordinates* (x, y) where:

r = *Distance*
θ = *Course*
x = *Departure*
y = *d.lat* (see Note 2-3 below)



Fig 2-6. Polar and Cartesian Coordinates of a Position

Note 2-3. *If converting between Polar and Cartesian Coordinates using a calculator, d.lat appears as 'x' and Departure as 'y' because of the difference between mathematical and navigational conventions on the initial line from which angles are measured. In navigational notation, Course is measured clockwise from the north-south line, while in mathematical notation, it is measured anti-clockwise from the east-west line.*

Example 2-5: Traverse Sailing by Traverse Table and Calculator Methods

A ship in position 45°25'N, 15°05'W at 0900 steers the following *Course*s and speeds. What is its position at 1315?

TIME	COURSE	SPEED	
0900-0946	045°	15	knots
0946-1015	312°	16½	knots
1015-1122	217°	14¾	knots
1122-1247	103°	17	knots
1247-1315	190°	15	knots

The ships track and the overall *d.lat / d.long* is shown at Fig 2-7 (below). Details for each leg by Traverse Table and calculator methods are at Table 2-1 (below):



Fig 2-7. Ship's Track and Overall d.lat / d.long from Example 2-5

Table 2-1. Details for each leg (Example 2-5) by Traverse Table and Calculator Methods

Time	Course θ	Speed	Distance *r*	Traverse Table Method			Calculator Method	
				Course	*Departure*	*d.lat*	*Dep* (*x*)	*d.lat* (*y*)
0900-0946	045°	15 kn	11.5'	N45°E	08.13'E	08.13'N	+08.132'	+08.132'
0946-1015	312°	16½ kn	7.975	N48°W	05.97'W	05.33'N	-05.927'	+05.336'
1015-1122	217°	14¾ kn	16.471'	S37°W	09.91'W	13.16'S	-09.912'	-13.154'
1122-1247	103°	17 kn	24.083'	S77°E	23.46'E	05.42'S	+23.466'	-05.417'
1247-1315	190°	15 kn	7.0'	S10°W	01.22'W	06.89'S	-01.216'	-06.894'
TOTALS (0900-1315)					**14.5'E**	**12.01'S**	**+14.543(E)**	**-11.997'(S)**

Mean Latitude (0900-1315):	45° 19.0'N
Departure:	00° 14.5'E (both methods - see Table 2-1 above)
d.long (from formula 2-5):	00° 20.7'E
d.lat:	00° 12.0' S (both methods - see Table 2-1 above)
Position at 1315:	**45° 13.0'N 14° 44.3'W**

0207. Mercator Sailing Overview

a. **Concept.** *Mercator Sailing* provides a method of determining position after travelling along a *Rhumb Line*, other than in a North-South or East-West direction. As stated at Para 0205, *Mercator Sailing* is an alternative to *Mean Latitude* / *Corrected Mean Latitude Sailing*. It uses *Difference of Meridional Parts* (*DMP*) instead of *d.lat*, and *d.long* instead of *Departure*.

b. **Meridional Parts.** *Meridional Parts* are a feature of the *Mercator* projection on which the great majority of small-*Scale* Admiralty (*UKHO*) navigational charts are based. *Meridional Parts* are discussed at length in Chapter 4.

c. **Further Details.** *Mercator Projection* charts are covered in detail at Chapter 4. The calculations involved in both *Spherical* and *Spheroidal Mercator Sailing* are set out Chapter 5, together with *Vertex* and the *Composite Track* calculations.

0208. Spherical Sailing - Great Circle Tracks

The definition of *Great Circle* is repeated for the convenience of readers, as follows:

> **(Extract from Para 0110c): Great Circle.** A *Great Circle* is the intersection of a *Spherical* surface and a plane which passes through the centre of the *Sphere*. It is the shortest distance between two points on the surface of a *Sphere*.

a. **The Great Circle - Explanation.** A straight line is the shortest distance between two points. However, when two points lie on the surface of a *Sphere*, the arc of the *Great Circle* joining them is the curve that most nearly approaches the straight line, because it has the greatest radius and therefore the least curvature.

- The smaller arc of the *Great Circle* joining two places on the Earth's surface (eg arc *FT* at Fig 2-8 below) is the shortest route between *F* and *T* (or *T* ').
- PF and *PT* are arcs of the *Meridians* passing through *F* and *T* (or *T* ') and are also arcs of *Great Circles*.
- The triangle *PFT* (or *PF T*') is therefore a *Spherical* triangle, and the *Distance FT* (or *F T* ') is the length of the side opposite the *Pole* in this triangle.



Fig 2-8. The Great Circle (shown in Northen Hemisphere)

(0208) b. **True Bearings on a Great Circle.** The true bearing of *T* from *F* (see Fig 2-9a/b below) is the angle between the *Meridian* through *F* and the *Great Circle* joining *F* and *T*, measured clockwise from the *Meridian* (ie the angle *PFT)*. This angle is the initial *Course* to be steered by a ship sailing on a *Great Circle* from *F* to *T*. Radio waves also travel along *Great Circles* near the Earth's surface (see Note 2-4 below) and the angle *PFT* is thus the bearing of *T* from *F* as given by a radio-direction finder.

Note 2-4. *The 'Geodesic' is the equivalent of a Great Circle on a Spheroid. However, in everyday use, the terms 'Great Circle' (in lieu of 'Geodesic') and 'Small Circle' are applied to the Earth's Oblate Spheroidal shape (see Note 1-1 at Para 0110c).*

c. **True Bearings at Intermediate Points on a Great Circle.** At any intermediate point *G* between *F* and *T* on a *Great Circle* (see Fig 2-9a below), the true bearing of *T* is the angle *PGT*, and this is not equal to the angle *PFT* (see Fig 2-9b below). To an observer moving along the *Great Circle* from *F* to *T*, the true bearing of *T* changes continuously. Only when *T* is close to *F* may this change be neglected (as the area of the Earth's surface traversed by *FT* is then sufficiently small to be considered as a plane or flat surface, on which *Great Circles* appear as straight lines).



Fig 2-9a. Great Circle True Bearings



Fig 2-9b. Initial and Intermediate Bearings

d. **Great Circle Distance and Bearing.** In *Spherical* triangle *FPT* (see Fig 2-8, previous page), the length of the side *FT* and its true bearing (angle *PFT*) may be calculated (see calculation at Para 0211), as the angle *FPT* and sides *PF* and *PT* (or PT_1) are known:

- **Angle *FPT*.** The angle *FPT* is the *d.long* between *F* and *T*.
- **Sides PF and PT - 'SAME' Names.** When the *Latitudes* of the sides *PF* and *PT* are in the same hemisphere (ie have *'SAME'* names, as in Fig 2-8 where *F* and *T* are both North), *PF* = (90˚ - *Latitude F*) and *PT* = (90˚ - *Latitude T*). The distance (90˚ - *Latitude*) is known as the *Co-Latitude*.
- **Sides PF and PT_1 - 'CONTRARY' Names.** When the *Latitudes* of the sides *PF* and *PT* are in different hemispheres (ie have *'CONTRARY'* names, as in Fig 2-8 where *F* is North and T_1 is South), PT_1 = (90˚ + *Latitude* T_1).

(0208d continued)

- **For Pole P (Northern Hemisphere).** From Fig 2-8, it can be seen that:

  For *Latitudes* of '*SAME*' name:

  $PF = 90^\circ - Latitude\ F = Co\text{-}Latitude\ F$

  $PT = 90^\circ - Latitude\ T = Co\text{-}Latitude\ T$

  angle $FPT = d.long$

  For *Latitudes* of '*CONTRARY*' names:

  $PF = 90^\circ - Latitude\ F = Co\text{-}Latitude\ F$

  $PT_1 = 90^\circ + Latitude\ T_1$

  angle $FPT_1 = d.long$

- **For Pole P'(Southern Hemisphere).** When *F* is also in southern *Latitudes* (see Fig 2-10), *P'* may substituted for *P* in the above expressions.



Fig 2-10. The Spherical Triangle (Southern Hemisphere)

- **Summary For Either Hemisphere.** So, for either hemisphere:

  $PF = 90^\circ \pm Latitude\ F$

  $PT = 90^\circ \pm Latitude\ T$

  The sign of the expression is determined by the NAME of the *Pole* and NAME of the *Latitude* of the places, summarised as:

SAME Names:	SUBTRACT
CONTRARY Names:	ADD

e. **Great Circle Sailing.** To follow a *Great Circle* track exactly would involve continuous *Course* changes. In practice, the *Great Circle* track is divided into a series of *Rhumb Lines*, approximating the *Great Circle* (see Fig 2-11 below, and Para 0441a).



Fig 2-11. Rhumb Line tracks approximating the Great Circle

0209. Spherical Sailing - The Vertex and Composite Tracks

a. **The Vertex**. The point at which a *Great Circle* most nearly approaches the *Pole* is called its *Vertex* - shown as '*V*' at Fig 2-12 (below). At the *Vertex*, the *Great Circle* ceases to approach the *Pole* and begins to curve away. Therefore, at the *Vertex*, the *Great Circle* must cut the *Meridian* at right angles. The method of finding this position involves the use of right-angled *Spherical* triangles, and is described in Chapter 5.

b. **The Composite Track.** A *Great Circle* track between any two points passes nearer to the *Pole* than does the *Rhumb Line* track (unless both points are on the *Equator*); the *Great Circle* track can easily reach high *Latitudes* (eg route from USA / Canada to UK). If ice is likely to be encountered, the *Great Circle* track should be modified to clear any ice danger by avoiding high *Latitudes*, while remaining the shortest possible safe track. This modified track is known as the *Composite Track*, and is formed by two *Great Circle* arcs joined at their *Vertices* by the '*Safe Parallel*' *of Latitude*. In Fig 2-12 below:

- **Great Circle FLVMT.** Track *FLVMT* is the *Great Circle* joining *F* and *T*.

- **'Safe Parallel' LM.** *Latitudes* higher than the *Safe Parallel LM* are assumed to be dangerous and *Great Circle* arc *LVM* cannot be used.

- **Shortest Track.** The track *FLMT* is not the shortest safe route. The shortest safe route is *FABT*, where *FA* and *BT* are *Great Circle* arcs tangential at *A* and *B* to the *Safe Parallel*. *FABT* is thus the *Composite Track* in this example.

- **Proof of FABT as the Shortest Track.** By inspection:
  - If *L* and *M* are taken as any points on the *Safe Parallel LM* outside the arc *AB*, (*FL* + *LA*) is greater than *FA* itself
  - Similarly, (*BM* + *MT*) is greater than *BT*.
  - By addition, *FL* + *LA* + *AB* + *BM* + *MT* is greater than *FA* + *AB* + *BT*.


P
DANGER AREA
(ABOVE SAFE PARALLEL)
90°
Great Circle Track
V
(Vertex)
M
90°
L
90°
B
A
T
Safe Parallel
Composite Track:
Safe Parallel Arc AB
Composite Track:
Great Circle Arc BT,
with its Vertex touching
the 'Safe Parallel' at B
Composite Track:
Great Circle Arc FA,
with its Vertex touching
the 'Safe Parallel' at A
F

Fig 2-12. The Great Circle, Vertex and Composite Track

c. **Calculation.** The calculation of the *Composite Track* is at Para 0522.

0210. Summary of Methods for Spherical Great Circle Calculations

Table 2-2 (below) lists 7 methods for solving *Spherical Great Circle* calculations, with their applicability to finding the *Distance* and *Course* / bearing. The calculation of *Great Circle* (*Geodesic*) *Course*s and *Distance*s taking into account the *Spheroidal* shape of the Earth are at Paras 0541-0542.

Table 2-2. Methods for Spherical Great Circle Calculations

Method	Distance	Course / Bearing
Software - 'NAVPAC 'program (UKHO: DP 330)	YES	YES
WECDIS and ECDIS equipments	YES	YES
Cosine	YES	YES
Sine	NO	YES
Haversine	YES	NO
Sight Reduction Tables (NP 401)	YES	YES
Half Log Haversine	NO	YES
ABC Tables (NP 320 - Norie's Nautical Tables)	NO	YES

a. **'NAVPAC' Program (UKHO - DP 330).** The *NAVPAC* software program is produced by HM Nautical Almanac Office (available to the public from *UKHO,* Taunton as DP 330); *NAVPAC* provides astronomical data and is a fast, reliable, authoritative method of solving *Spherical Great Circle*, *Spheroidal Rhumb Line* and astro-navigation calculations (see *NAVPAC* details at Para 0551). Its operation is fully described in BR 45 Volume 2 (available to the public and published by the Nautical Institute, London). ***NAVPAC* is in Royal Navy service and is the Royal Navy's preferred method for obtaining astronomical data and solving the above calculations.**

b. **WECDIS / ECDIS.** *WECDIS* also provides a fast, reliable and authoritative method of solving *Spherical Great Circle* and *Spheroidal Rhumb Line* calculations. *ECDIS* equipments are also capable of these calculations.

c. **Cosine and Sine Methods.** The '*Cosine Method*' is very suitable for use with a pocket calculator and is explained at Para 0211. The *'Sine Method'* may be used to cross-check the *Cosine* solution and may also be used to determine the *Course* or bearing. Both the *Cosine* and the *Sine Formulae* are set out in Appendix 2. Although the *Sine Formula* is ambiguous, this ambiguity is easily resolved in most cases, and the calculation is simpler than the *Cosine Method.* An example is given at Para 0211.

d. **Haversine and Half Log Haversine Methods.** The '*Haversine Method*' and *'Half Log Haversine Method*' are set out in Appendix 2.

e. **Sight Reduction and ABC Table Methods.** A full explanation of the *'Sight Reduction Method*' and '*ABC Table Method*' are set out in BR 45 Volume 2 (see details of Volume 2's availability to the public at Para 0210a above).

0211. Spherical Great Circle Calculations - Cosine Method

Although *Spherical* *Great Circle Distance* and *Course* / bearing calculations are most easily solved by using *NAVPAC* (see Para 0210a), they may also be solved effectively by the '*Cosine Method*', which is very suitable for use with a pocket calculator (see Fig 2-13 below).



Fig 2-13. Spherical Great Circle Calculations

a. **Great Circle Distance.** The equations for *Great Circle Distance* are:

$$\cos FT = \cos FP \cos PT + \sin FP \sin PT \cos FPT$$

$$\cos \text{Distance} = \cos(90^\circ \pm \text{Lat } F)\cos(90^\circ \pm \text{Lat } T) + \sin(90^\circ \pm \text{Lat } F)\sin(90^\circ \pm \text{Lat } T)\cos d.\,long \quad \ldots \mathbf{2.8}$$

- **Signs in Formula (2.8).** Signs are determined in formula (2.8) by the name of the elevated *Pole* and the *Latitude* of the place, as follows:

SAME Names:	SUBTRACT
CONTRARY Names:	ADD

In Fig 2-13 (above), *F* and *T* are on opposite sides of the *Equator*; thus in formula (2-8), the *Latitude* of *F* would be added and that of *T* subtracted.

- **Same and Opposite Hemispheres - Formula (2.9).** Formula (2.8) may be resolved into formula (2.9) below. In formula (2.9), when *F* and *T* are on the same side of the *Equator*, *F* and *T* are both positive; when *F* and *T* are different sides of the *Equator*, the *Latitude* of the point opposite the elevated *Pole* is negative (eg At point *F* in Fig 2-13, sin *Lat* (-*F*) and cos *Lat* (-*F*) would be used). Example 5-6 at Para 0541 provides an illustration of this concept.

$$\cos \text{Distance} = \sin \text{Lat } F \sin \text{Lat } T + \cos \text{Lat } F \cos \text{Lat } T \cos d.long \quad \ldots \mathbf{2.9}$$

- **Modified Formula (2.10).** Formula (2.9) may also be modified as follows:

$$\cos \text{Distance} = (\tan \text{Lat } F \tan \text{Lat } T + \cos d.long) \cos \text{Lat } F \cos \text{Lat } T \quad \ldots \mathbf{2.10}$$

(0211) b. **Great Circle Course / Bearing**. The equations for *Great Circle Course* / bearing are:

$$\cos PT = \cos FP \cos FT + \sin FP \sin FT \cos PFT$$

$$\cos PFT = \frac{\cos PT - \cos FP \cos FT}{\sin FP \sin FT}$$

$$\cos PFT = \frac{\cos (90° \pm lat\ T) - \cos (90° \pm lat\ F) \cos FT}{\sin (90° \pm lat\ F) \sin FT} \qquad \text{. . . } \mathbf{2.11}$$

- **Opposite Hemispheres.** In Fig 2-13, *F* and *T* are on opposite sides of the *Equator*; thus the *Latitude* of *T* would be subtracted and that of *F* added.

- **Same Hemispheres.** When *F* and *T* are both on the same side of the *Equator*, formula (2.11) resolves into:

$$\cos \text{initial course} = \frac{\sin lat\ T - \sin lat\ F \cos \text{distance}}{\cos lat\ F \sin \text{distance}} \qquad \text{. . . } \mathbf{2.12}$$

$$\sin \text{initial course} = \frac{\sin (90° \pm Lat\ T) \sin d.long}{\sin \text{distance}} \qquad \text{. . . } \mathbf{2.13}$$

- **Initial Courses.** In the Northern hemisphere, the initial *Course* is defined from North (and as either East or West). In the Southern hemisphere, it is defined from South unless Southern *Latitudes* are entered as negative values.

Example 2-6: Great Circle Calculations by the Cosine and Sine Methods

A ship transits from position F (45˚N, 140˚E) to T (65˚N, 110˚W). Find the *Great Circle Distance* and the initial *Course* by the *Cosine Method*, and the initial *Course* by the *Sine Method*.



Fig 2-14. Ship's Great Circle Track from Example 2-6

- **Great Circle Distance - Cosine Method:**

$$\cos \text{Distance} = \sin Lat\ F \sin Lat\ T + \cos Lat\ F \cos lat\ T \cos d.long$$

. . . (formula 2.9)

$$= \sin Lat\ 45° \sin Lat\ 65° + \cos Lat\ 45° \cos Lat\ 65° \cos 110°$$

$$= 0.53864837$$

$$\text{Great Circle Distance} = 57.408325° = 3444.5'$$

(0211b Example 2-6 continued)

- **Great Circle Initial Course - Cosine Method:**

$$cos\ initial\ course = \frac{sin\ lat\ T\ -\ sin\ lat\ F\ cos\ distance}{cos\ lat\ F\ sin\ distance} \quad \text{. . . (formula 2.12)}$$

$$= \frac{sin\ lat\ 65^\circ - sin\ lat\ 45^\circ\ cos\ 57.408325^\circ}{cos\ lat\ 45^\circ\ sin\ 57.408325^\circ}$$

$$= \frac{0.52542587}{0.59575915} = 0.88194343$$

$$Initial\ Course = N28.122305^\circ E = 028.1^\circ$$

- **Sine Rule Check**:

$$\frac{sin\ FT}{sin\ FPT} = \frac{sin\ PT}{sin\ PFT} \quad \text{. . . (Appendix 2, formula A2.5)}$$

$$\frac{sin\ 57.408325^\circ}{sin\ 110^\circ} = 0.8966024 = \frac{sin\ 25^\circ}{sin\ 28.122305^\circ}$$

- **Great Circle Initial Course - Sine Method:**

$$\frac{sin\ FT}{sin\ FPT} = \frac{sin\ PT}{sin\ PFT} \quad \text{. . . (Appendix 2, formula A2.5)}$$

$$sin\ PFT = \frac{sin\ PT\ sin\ FPT}{sin\ FT}$$

$$sin\ initial\ course = \frac{sin\ (90^\circ \pm Lat\ T)\ sin\ d.long}{sin\ distance} \quad \text{. . . (formula 2.13)}$$

$$= \frac{cos\ lat\ T\ sin\ d.long}{sin\ distance}$$

$$= \frac{cos\ 65^\circ\ sin\ 110^\circ}{sin\ 57.408325^\circ} = 0.47135526$$

$$PFT = N28.122305^\circ E\ or\ N151.87769^\circ E$$

In this case the ambiguity is easily resolvable, as the *Great Circle Course* from F to T must lie to the North of East. Thus:

$$Initial\ Course = 028.1^\circ$$

CHAPTER 3

AN INTRODUCTION TO GEODESY

CONTENTS

Para

0301. Scope of Chapter

SECTION 1 - SPHEROIDS

0310. The Shape of the Earth - Oblate Spheroid
0311. The Surfaces of the Earth (Physical Surface, Geoid and Spheroid)
0312. Spheroid - Geodetic and Geocentric Latitudes
0313. Spheroid - Parametric Latitude
0314. Spheroid - Length of 1' in Latitude and Longitude
0315. Spheroid - Geodesic

SECTION 2 - DATUMS

0320. Vertical and Horizontal Datums
0321. Geodetic Datums
0322. Multiplicity of Geodetic Datums
0323. Geodetic Datum Shifts
0324. Geodetic Datum Transformation Methods

SECTION 3 - EARTH MODELS FOR NAVIGATION SYSTEMS

0330. Earth Models - Spheroidal, Spherical and Flat Earth
0331. Spheroidal Earth Models
0332. Spherical Earth Models
0333. Flat Earth Models

INTENTIONALLY BLANK

CHAPTER 3

AN INTRODUCTION TO GEODESY

0301. Scope of Chapter

Geodesy is the branch of mathematics concerned with large areas of the Earth's surface in which allowance must be made for Earth's shape and the curvature of its surface. Chapter 3 introduces the basic concepts of this subject.

0302-0309. Spare

SECTION 1 - SPHEROIDS

0310. The Shape of the Earth - Oblate Spheroid

As stated at Para 0110a / Fig 1-1, and repeated below for the convenience of readers:

> **(Extract from Para 0110a):** The Earth is not a perfect *Sphere*; it is slightly flattened at the top and bottom, the smaller diameter being about 23.1 *n.miles* less than the larger. The Earth's 'flattened' shape is known as an *Oblate Spheroid* (see Fig 3-1 below) with an *Equatorial* radius '*a*' of approximately 3443.9 *n. miles* and a *Polar* radius '*b*' of 3432.4 *n. miles* (*International Nautical Miles* of 1852 m based on *WGS 84 Datum*).



Fig 3-1. The Shape of the Earth - an Oblate Spheroid (*Copy of Fig 1-1*)

0311. The Surfaces of the Earth (Physical Surface, Geoid and Spheroid)

Within the overall concept of the Earth being an *Oblate Spheroid*, the Earth has 3 distinct surfaces (see Fig 3-2 below): the *Physical Surface*, the *Geoid*, and the *Spheroid* (also called the *Ellipsoid* - see Note 3-1 below).


GEOID UNDULATION
SPHEROID (ELLIPSOID)
MEAN SEA LEVEL
OCEAN
GEOID
MOUNTAIN
EARTH'S
GEOID
SURFACE
SPHEROID (ELLIPSOID)
OCEAN
NORMAL TO SPHEROID
NORMAL TO GEOID
(This is the 'local vertical', as indicated by a plumbline to an observer on the Earth's surface)
DEFLECTION OF THE VERTICAL

Fig 3-2. The Surfaces of the Earth (Physical Surface, Geoid and Spheroid)

Note 3-1. *The term 'Ellipsoid' is also widely used for 'Spheroid'. For the purposes of simplicity, the term 'Spheroid' is used in BR 45 Volume 1.*

a. **Defining the Surfaces of the Earth.** The 3 surfaces of the Earth may be defined as follows:

- **Physical Surface.** The Earth's *Physical Surface* does not have a perfectly *Spherical* shape, but is slightly flattened in the *Polar* regions (see Para 0310a / Para 0110a previous page). In addition, although the Earth's shape approximates to an *Oblate Spheroid*, it is highly irregular with local departures of several kilometres from a 'pure' *Spheroida*l shape. Thus, it is NOT a suitable surface on which to base calculations.

- **The Geoid.** The *Geoid* is a more regular shape and is defined as:

  > *"An 'Equipotential Surface' (see Note 3-2 below) which is equivalent to Mean Sea Level"* .

  However, due to topography and variations in the earth's density, the *Geoid* is NOT a sufficiently regular surface on which to base calculations.

Note 3-2. *An 'Equipotential Surface' is one on which the gravity potential is always uniform and to which the direction of gravity is always perpendicular.*

- **The Spheroid (Ellipsoid).** The *Spheroid (Ellipsoid)* may be considered as an ellipse which has been rotated about its semi-minor axis. Calculations based on the semi-major and semi-minor axes provide a figure for the *Spheroid 's 'Flattening'* and *'Eccentricity'* (see Figs 3-3 and 3-4 opposite). The *Spheroid* forms a convenient surface on which to base positions and positional calculations. A large number of *Spheroids* have been developed for a number of *Local*, *Regional* or worldwide *Geodetic Datums* (see details at Para 0321).

(0311) b. **Flattening.** The *'Flattening'* (or ellipticity) of the *Spheroid* is an important factor in *Geodetic Datum* conversion calculations. The reciprocal of *Flattening* (ie '1/*f*') and the Earth's semi-major *Equatorial* axis '*a*' are defined values; others values are derived from these. The relationship between '*f*,' '*a*' and '*b*' (semi-major *Polar* axis) is:

$$f = \frac{a - b}{a} \qquad \text{. . . 3.1}$$


b
a
a = Semi-major (Equatorial) Axis
b = Semi-minor (Polar) Axis
f = Flattening (ellipticity)
$f = \frac{a - b}{a}$

Fig 3-3. The Spheroid - Flattening 'f' (*ellipse exaggerated for clarity*)

c. **Eccentricity.** The '*Eccentricity'* of the *Spheroid* is another important factor in *Geodetic Datum* conversion calculations. If point *'M'* moves so that its distance from a fixed point *'S'* (the focus of the ellipse) is always in a constant ratio *'e'* (less than unity) to its perpendicular distance from a fixed straight line *AB* (the directrix), then the locus of a point '*M'* is called an ellipse of *Eccentricity* '*e*'(see Fig 3-4 below). *Eccentricity* '*e*' may be calculated from the Earth's semi-major (*Equatorial*) axis '*a*' and semi-minor (*Polar*) axis '*b*' (see Fig 3-3 above), as follows:

$$e = \left(\frac{a^2 - b^2}{a^2}\right)^{1/2} \quad \text{and} \quad e^2 = \frac{a^2 - b^2}{a^2} \qquad \text{. . . 3.2}$$

and from . . . 3.1

$$e = \left(2f - f^2\right)^{1/2} \qquad \text{. . . 3.3}$$


A
C
D
B
Y
M
b
a
S
O
X
a = Semi-major (Equatorial) Axis
b = Semi-minor (Polar) Axis
e = Eccentricity
$e = \left(\frac{a^2 - b^2}{a^2}\right)^{1/2}$
$e^2 = \frac{a^2 - b^2}{a^2}$

Fig 3-4. The Spheroid - Eccentricity 'e' (*ellipse exaggerated for clarity*)

0312. Spheroid - Geodetic and Geocentric Latitudes

Fig 3-5 (below) shows a *Meridional* section of the *Spheroid*. *'M'* is a point on the *Meridian PAP'*, and *MK* is the tangent to the *Meridian* at *M*.

a. **Geodetic Latitude.** If the normal *LM* to the tangent *MK* cuts *OA* at *L*, the angle *MLA* is called the *Geodetic Latitude* of *M*, and denoted by the symbol ϕ . *ML* does NOT pass through the centre *O* of the *Spheroid,* except when *M* is on the *Equator* or at the *Poles*.

b. **Geocentric Latitude.** The angle *MOA* (which by definition, does pass through the centre *O* of the *Spheroid*) is called the *Geocentric Latitude* of *M* and is denoted by the symbol θ .

c. **Connection between Geodetic Latitude and Geocentric Latitude.** The *Geodetic Latitude* ϕ and *Geocentric Latitude* θ are connected by the following formula (see Appendix 5):

$$\tan\theta = \frac{b^2}{a^2}\tan\phi \qquad \ldots\mathbf{3.4}$$

$$= (1-f)^2 \tan\phi \qquad \ldots\mathbf{3.5}$$

$$= (1-e^2)\tan\phi \qquad \ldots\mathbf{3.6}$$

d. **Difference between Geodetic Latitude and Geocentric Latitude.** The difference between *Geodetic Latitude* and *Geocentric Latitude* is zero at the *Equator* and the *Poles*, and has a greatest value when $\phi = 45^\circ$. For *WGS 84 Datum,* the greatest value is 11.54 minutes of arc.



Fig 3-5. Geodetic Latitude and Geocentric Latitude

0313. Spheroid - Parametric Latitude

Fig 3-6 shows a *Meridional* section of a *Spheroid WPE* and *Sphere WBE*:

- The *Polar* axis of *Spheroid WPE* is *OP* and its shape and size are defined by the radii $OE = a$, and $OP = b$.
- *WBE* is the *Meridional* section of a *Sphere* with centre *O*, *Polar* axis *OB* and radii $OE = OB = a$.
- *M* is a point on the *Spheroid* with *Geodetic Latitude* ϕ .
- *HM* is parallel to *OP* and produced to cut the circle *WBE* at U. The radius *OU* makes an angle β with the X axis.

a. **Parametric Latitude.** Angle β is the *Parametric Latitude* (or *Reduced Latitude*) of point *M*. The *Parametric Latitude* is often used for *Geodesic* calculations on the *Spheroid* (see Paras 0541-0542).

b. **Connection between Geodetic Latitude and Parametric Latitude.** The *Geodetic Latitude* ϕ and *Parametric Latitude* β are connected by the following formula (see Appendix 5):

$$\tan \beta = \frac{b}{a} \tan \phi \qquad \ldots \mathbf{3.7}$$

The difference between the *Geodetic Latitude* and *Parametric Latitude* is zero at the *Equator* and at the *Poles* and has a greatest value when $\phi = 45^\circ$. For the *WGS 84 Spheroid*, where $f = 1/298.257223563$, the greatest value is approximately 5.85 minutes of arc.



Fig 3-6. Geodetic Latitude and Parametric Latitude (*ellipse exaggerated for clarity*)

0314. Spheroid - Length of 1' in Latitude and Longitude

As explained at Para 0113, the length of the *Sea Mile* varies between the *Equator* and the *Poles* because of the Earth's changing *Radius of Curvature*.

a. **Latitude Formula.** The length of 1 minute of *Latitude* may be found from the formula $\rho\delta\phi$, where ρ is the circular *Radius of Curvature* in the *Meridian* and $\delta\phi$ is a small increase (measured in radians) in the *Geodetic Latitude* ϕ (see Fig 3-7 below). It may be shown (Appendix 5) that:

$$\rho = \frac{a\left(1-e^2\right)}{\left(1-e^2\sin^2\phi\right)^{3/2}} \qquad \ldots \mathbf{3.8}$$

When $\delta\phi$ = 1 minute of arc:

$$1' \text{ of Latitude } = \frac{a\left(1-e^2\right)}{\left(1-e^2\sin^2\phi\right)^{3/2}} \sin 1' \qquad \ldots \mathbf{3.9}$$

When ϕ = zero

$$1' \text{ of Latitude at the Equator } = a\left(1-e^2\right)\sin 1' \qquad \ldots \mathbf{3.10}$$



***Note**: Position 'C' is the centre of a circle and arc 'ρdø' is part of its circumference. Thus on the Spheroid (Ellipsoid), the position of 'C' will move relative to 'O' as arc 'ρdø' moves over the surface of the Spheroid.*

Fig 3-7. Length of One Minute of Latitude

b. **Longitude Formulae**

$$1' \text{ of Longitude at the Equator } = a \sin 1' \quad \text{(minutes of arc)} \qquad \ldots \mathbf{3.11}$$

At *Latitude* ϕ,

$$1' \text{ Longitude } = \frac{a\cos\phi}{\left(1-e^2\sin^2\phi\right)^{1/2}} \sin 1' \qquad \ldots \mathbf{3.12}$$

0315. Spheroid - Geodesic

Just as a *Great Circle* gives the shortest distance between two points on a *Sphere*, a *Geodesic* is the shortest line between two points on the *Spheroidal* Earth. See Para 0540a.

0316-0319. Spare.

SECTION 2 - DATUMS

0320. Vertical and Horizontal Datums

Chart data is referenced to a *Vertical Datum* and a horizontal *Geodetic Datum*. Charted depths and heights are referenced to a *Vertical Datum*; this subject is covered in detail at Chapter 10. The horizontal *Geodetic Datum* defines the *Spheroidal* shape of the Earth used to establish the positional framework (ie *Latitude / Longitude*, *Grids* etc).

0321. Geodetic Datums

A position given solely in terms of *Latitude* and *Longitude* will NOT define a unique point on the Earth's surface (see Fig 3-8 below). To define a point unambiguously, it is also necessary to quote the *Geodetic Datum* (and the particular *Spheroid* utilised) to which the position is referred. Fig 3-8 illustrates the difference on the Earth's surface between the same *Latitude* and *Longitude*, but referenced to two different *Geodetic Datums*.



When referenced to OSGB 36, position 'A' (50° 21.5'N 004° 10.0'W) is 101 metres from position 'B' (also 50° 21.5'N 004° 10.0'W, when referenced to WGS 84 Datum)

Fig 3-8. Example of the Difference for the Same Position Referred to Different Datums

a. **Choosing a Geodetic Datum.** Classically, a *Geodetic Datum* can be considered as the surface to which positions are referred. A (horizontal) *Geodetic Datum* utilises a specific *Spheroid* which best fits the *Geoid* over the area of interest. This is because the *Geodetic* measurements, (angles obtained by theodolite, and heights obtained by spirit levelling), are obtained with respect to the local gravity surface - the *Geoid*. However, since calculations are performed on the *Spheroid*, it is necessary that the *Spheroid* and *Geoid* be in close agreement to minimise errors in calculation.

b. **Local Geodetic Datums.** Thus, in the simple case of a *Local Geodetic Datum*, an accurate position may be defined by precise astronomic observations, with a *Spheroid* chosen to fit the *Geoid* exactly at this point (see 'rugby ball / orange peel' analogy at Note 3-3 overleaf). *Local Geodetic Datums* thus deal only with discrete parts of the Earth's surface and are only loosely related to the Earth's centre of mass.

(0321) c. **Classical Regional Geodetic Datums.** For 'classical' *Regional Geodetic* networks, the differences between observed astronomic position and *Geodetic* position computed through the triangulation network at several points may be minimised, thus ensuring an overall minimal separation between the *Geoid* and the *Spheroid.* Like *Local Geodetic Datums,* 'classical' *Regional Geodetic Datums* deal only with discrete parts of the Earth's surface, are only loosely related to the Earth's centre of mass and suffer from the 'rugby ball / orange peel' analogy at Note 3-3 below. See also Para 0321e - 'Modern Regional Datums Tied to WGS 84' (below) and Table 3-1 (opposite).

Note 3-3. *A crude analogy for a Local or Regional Geodetic Datum is to consider the chosen Spheroid as a rugby ball and the Local Geodetic Datum as a piece of orange peel placed over it where the position and orientation fitted best. The precise observed position would then be a pin stuck into the orange peel at the appropriate location.*

d. **World Geodetic System (WGS).** The *World Geodetic System (WGS)* is a combined *Spheroid* and *Datum.* It is global in coverage and directly related to the Earth's centre of mass.

- **Concept.** A satellite-derived *World Geodetic Datum / Spheroid* is defined by the system in which the satellite orbit parameters are given. These in turn are dependent upon the precise coordinates of the satellite tracking stations, the geopotential model for the Earth's gravity field and a set of constants including GM (the Earth's mass 'M' times the gravitational constant 'G').
- **WGS 84.** From this satellite reference system data, a universal (worldwide) *Spheroid* and *Datum* was established. *WGS 1984* ('*WGS 84*') is the current system and is NATO's preferred *Spheroid / Datum*; it has replaced *WGS 72.*
- **GNSS: GPS and Equivalents.** The adoption of *WGS 84* has made it possible to define absolute position anywhere in the world by common *Geodetic Latitude* and *Longitude* for use with *Global Navigation Satellite Systems* (*GNSS*) [eg *Global Positioning System* (*GPS*) or equivalents].

e. **'Modern' Regional Datums Tied to WGS 84.** Due to satellite technology, centimetric distance measurement is now possible over many thousands of *nautical miles* and the motion of tectonic plates becomes *Geodetically* significant. Thus *Regional Geodetic Datums* tied to *WGS 84 Datum* have been established at a specific time epoch and then held fixed in relation to the tectonic plate for the region. For most practical navigational purposes, these 'modern'*Regional Geodetic Datums* may be considered equivalent to *WGS 84*; the differences are only significant for the most precise uses.

- **Movement of European Tectonic Plate - ETRS 89 Regional Datum.** The European tectonic plate is moving at approximately 2.5cm / year in relation to *WGS 84*. A 'modern' *European Regional Geodetic Datum* (*ETRS 89*) was established in 1989 where *WGS 84* coordinates of the fundamental points were observed and held fixed. Since 1989, *WGS 84* and *ETRS 89* have drifted apart by 2.5cm / year and are now (2008) 0.47metres apart (increasing).
- **Other Modern Regional Datums.** Other examples of modern *Regional Geodetic Datum*s are *NAD 83* (N. America) and *SIRGAS* (S. America). Other similar *Regional Geodetic Datums* are now (2008) being established.

0322. Multiplicity of Geodetic Datums

a. **Common Geodetic Datums.** Numerous *Geodetic Datums* have been defined throughout the world from past centuries to the present time. Some of the more common *Geodetic Datums*, the *Spheroids* associated with them and their areas of application are at Table 3-1 (below). The *International (1924) Spheroid* is used for the calculation of distances in (*UKHO*) 'Admiralty Distance Tables' (NP 350) and 'Ocean Passages for the World' (NP 136). All calculations in this book are based on *WGS 84.*

b. **Geodetic Datums Worldwide.**

- **NATO Data.** NATO lists those *Geodetic Datums* and *Spheroids* which may be applicable for mapping and charting products within the area of NATO interest (and hence is also of interest for naval operations in support of land based activities, eg *Naval Gunfire Support [NGS]* or amphibious warfare). While the stated aim is to adopt the *WGS84 Datum* and *Spheroid* for all such products, it may be some time before this objective is fully achieved.
- **UKHO Data.** The *Admiralty List of Radio Signals* (*ALRS*) Volume 2 provides further detail on this subject, including the number of *UK Hydrographic Office (UKHO*) charts currently based on each *Datum*.

Table 3-1. Common Datums and Associated Spheroids with Areas of Application

Datum & (Type)	**Spheroid**	**(*a*) Equatorial Radius (*b*) Polar Radius**	**Flattening (*f*) & Reciprocal (*1 / f*)** $f = (a-b) / a$	**Eccentricity (*e*) & Squared (e^2)** $e^2 = (a^2-b^2) / a^2$	**Remarks**
OSGB 36 (Regional)	Airy 1830	**(*a*) 6,377,563.396m** (*b*) 6,356,256.909m	(*f*) 0.003340851 **(*1/f*) 299.324964**	(*e*) 0.081673374 (e^2) 0.006670540	Some remaining UK charts.
OSSN 80 (Regional)	Airy 1830	**(*a*) 6,377,563.396m** (*b*) 6,356,256.909m	(*f*) 0.003340851 **(*1/f*) 299.3249645**	(*e*) 0.081673374 (e^2) 0.006670540	Not for charts. OSGB 36 related.
ED 50 (Regional)	International 1924	**(*a*) 6,378,388m** (*b*) 6,356,911.946m	(*f*) 0.003367003 **(*1/f*) 297**	(*e*) 0.081991890 (e^2) 0.006722670	Some remaining European charts.
NAD 27 (Regional)	Clarke 1866	**(*a*) 6,378,206.4m** (*b*) 6,356,583.8m	(*f*) 0.003390075 **(*1/f*) 294.978698**	(*e*) 0.082271854 (e^2) 0.006768658	Some remaining USA charts.
Arc (Regional)	Clarke 1880	**(*a*) 6,378,249m** (*b*) 6,356,515m	(*f*) 0.003407561 **(*1/f*) 293.465**	(*e*) 0.0824834 (e^2) 0.006803511	Some remaining S. African charts.
WGS 72 (W'ldwide)	WGS 72 (1972)	**(*a*) 6,378,135m** (*b*) 6,356,750.520m	(*f*) 0.003352779 **(*1/f*) 298.26**	(*e*) 0.081818811 (e^2) 0.006694318	Being replaced by WGS 84.
NAD 83 (Regional)	GRS 80 (1980)	**(*a*) 6,378,137m** (*b*) 6,356,752.3141m	(*f*) 0.00335281068 **(*1/f*) 298.25722210**	(*e*) 0.0818191910 (e^2) 0.0066943800	Regional WGS 84 for N. America
ETRS 83 (Regional)	GRS 80 (1980)	**(*a*) 6,378,137m** (*b*) 6,356,752.3141m	(*f*) 0.00335281068 **(*1/f*) 298.25722210**	(*e*) 0.0818191910 (e^2) 0.0066943800	Regional WGS 84 for Europe
WGS 84 (W'ldwide)	WGS 84 (1984)	**(*a*) 6,378,137m** (*b*) 6,356,752.3142m	(*f*) 0.00335281066 **(*1/f*) 298.257223563**	(*e*) 0.0818191908 (e^2) 0.0066943800	WGS 84 is NATO preferred Datum.
Note: The defined parameters are 'a' and '1/f'; all others are derived values.					

0323. Geodetic Datum Shifts

a. **Datum Shifts.** Where two adjacent *Geodetic Datums* overlap, the same point on the Earth's surface will have two distinct sets of *Geodetic Coordinates*, one set in relation to each *Geodetic Datum* (see Fig 3-8). The difference between these two sets of coordinates is called a *'Datum Shift'*. These differences are primarily a result of the two different reference systems. The *Datum Shift* may not be consistent in magnitude and direction (ie it is likely to vary with geographic location).

b. **Datum Shift Information.** *Datum Shift* information is shown on navigational charts in the form of a 'Satellite-Derived Positions Note' and 'Overlapping Charts Note'. However, some charts exist for which the (horizontal) *Datum* or the relationship to *WGS 84* is unknown (some 1762 *UKHO* chart panels in 2008). These areas will have to be re-surveyed to modern standards before accurate *WGS 84* coordinates may be obtained for use with *GNSS* (ie *GPS* or equivalent).

Table 3-2. Examples of Common 'Datum Shifts'

From Datum	To Datum	Devonport Lat(")	 Long(")	Rosyth Lat(")	 Long(")
WGS84	WGS72	-0.10N	-0.55E	-0.09N	-0.55E
WGS84	ED50	+3.40N	+5.16E	+2.75N	+5.82E
WGS84	OSGB36	-2.22N	+4.22E	+0.24N	+5.06E
OSGB36	ED50	+5.62N	+0.94E	+2.51N	+0.76E
OSGB80	ED50	+5.47N	+0.88E	+2.89N	+0.67E

EXAMPLE

Note 3-4. *See also Admiralty List of Radio Signals (ALRS) Volume 2, which provides further detail on this subject, including the number of UK Hydrographic Office (UKHO) charts currently based on each Datum.*

0324. Geodetic Datum Transformation Methods

Several techniques are available to transform positional information from a variety of *Geodetic Datums* onto a common reference *Geodetic Datum* (normally *WGS 84*).

a. **Non-Homogeneous Geodetic Datums - Inconsistencies.** Some of the earlier *Local* or *Regional Geodetic Datums* (eg *OSGB 36*) contain internal inconsistencies in *Scale* and *Azimuth*, and are thus known as *'Non-Homogeneous Geodetic Datums'*. These inconsistencies may be significant (eg for *Precise Navigation*) if calculating position transformations to other *Geodetic Datums,* particularly if using automatic systems.

b. **Published Geographical Shifts.** When the *Datum Shift* has been determined by comparison of positions common to both *Datum*s, a simple block shift in geographical coordinate values may be applied. As a result, many nautical charts referred to *Geodetic Datums* other than *WGS 84*, now show the *Datum Shift* between *WGS 84* and the horizontal *Datum* in which the chart is published. These *Datum Shifts* are quoted to an accuracy commensurate with the chart *Scale*, and should not produce an error capable of being plotted on the chart at that *Scale*.

c. **WGS 84 and WGS 72.** To plot *WGS 84* positions on *WGS 72* charts, the *WGS 84* positions must be moved by:

- **Longitude:** 0.554 seconds Westward.
- **Latitude:** 0.1455 cos *Latitude* + 0.0064 $\sin^2$*Latitude* seconds Southward. The distance varies between 17.1 metres at the *Equator* and zero at the *Poles.*

d. **Datum Conversions.** Further details may be found in NATO STANAG 2211 (available in the public domain). To transform positions between different *Geodetic Datums,* the *Geodetic Datum* coordinates of *Latitude* and *Longitude* are first converted into 3-dimensional *Cartesian Coordinates*. Using the 'Molodensky Equations', translations along the X, Y and Z axes, rotations around these axes and a *Scal*e factor are applied to the *Cartesian Coordinates*. The modified *Cartesian Coordinates* are then re-converted into the second *Geodetic Datum* coordinates of *Latitude* and *Longitude.*

- **Homogeneous Geodetic Datums.** For *Homogeneous Geodetic Datums,* an average set of values for X, Y and Z axis rotation will provide sufficient accuracy in *Datum* transformation. This process may be easily automated.

- **Non-Homogeneous Geodetic Datums.** For *Non-Homogeneous Geodetic Datums,* average values may not always be adequate. Two methods are commonly available to overcome this:
  - **Localised Values.** One method is to use localised values for X, Y and Z axis rotations. This method suffers from the disadvantage that no single value can be used in automated systems and that it must interrogate a digital record of the contours; these values should never be extrapolated.
  - **Multiple Regression Equations (MRE).** Another method is to use *Multiple Regression Equations (MRE)*. This method is appropriate for determining *Datum Shifts* for land based applications, but is NOT valid for maritime applications since the *MREs* become rapidly unstable outside the area for which they were defined.

0325-0329. Spare.

INTENTIONALLY BLANK

SECTION 3 - EARTH MODELS FOR NAVIGATION SYSTEMS

0330. Earth Models - Spheroidal, Spherical and Flat Earth

a. **Types of Earth Models.** A variety of Earth models may be used in navigation systems. These fall into three categories:

- A *'Spheroidal* Earth'
- A *'Spherical* Earth'
- A *'Flat Earth'* or *'Tangential Plane'*

b. **Choice of Earth Models in Navigation Systems.** The *Spheroidal* Earth model is the closest approximation to the 'true' Earth shape, and is the most suitable surface on which to base precise long-range calculations in navigation systems. The other Earth models are less accurate approximations of the ideal model and will give less accurate results, particularly when dealing with long-range contacts beyond horizon-distance. The size of these errors should be compared with those of the *Spheroidal* Earth model.

0331. Spheroidal Earth Models

Numerous *Spheroids* are in existence and standardisation is therefore necessary.

a. **Adoption of WGS 84 Spheroid.** The *Global Positioning System* (*GPS*) uses *WGS 84,* which combines functions of both *Datum* and *Spheroid.* The preferred NATO *Geodetic Datum* and *Spheroid* for mapping and charting products in the NATO maritime operational areas is *WGS 84*. *WGS 84* was adopted for all relevant Royal Navy applications from 1991. *WGS 84* has been adopted by the *IMO* for *WECDIS / ECDIS / ECS* equipments and for *Electronic Navigation Charts* (*ENCs*) / *Raster Navigation Charts* (*RNCs*) used with them. The *Automatic Identification System* (*AIS*) also uses *WGS 84.*

b. **Differences Between Spheroids.** The correct *Spheroid* associated with the *Geodetic Datum* to which *Geodetic Coordinates* are referred must always be used in all calculations, otherwise some quite large and unexpected errors can be introduced. In *Naval Gunfire Support* (*NGS*), *Geodetic Latitude* and *Longitude* coordinates may require to be converted to *Grid* coordinates to be compatible with adjacent land mapping. See Example 3-1 (below) for an indication of possible errors if incorrect *Datum / Spheroid* information is applied to *Geodetic / Grid* conversions.

Example 3-1. In a gunnery exercise, a target position on the North East corner of Garvie Island at 58° 37.09' N, 004° 52.20' W (*WGS 84*) translates into a *British National Grid* position of 233418E 973594N when using (correctly) the *Airy Spheroid (1830) / OSGB36 Datum* (see Fleet Chart F6681WGS). If no special (Fleet) chart overprinted with various *Grids* is available for a particular area, the transformation calculation has to be carried out mathematically; some transformation facilities are contained within *WECDIS* and may be included in *ECDIS* equipments. However, if the wrong *Spheroid / Datum* combination is selected for the transformation, a significant error can occur (eg in the above example, the incorrect use of, say, the *International Spheroid (1924)* instead of *Airy Spheroid (1830)* will result in a *British National Grid* position 19 metres East and 288 metres North of the correct position).

0332. Spherical Earth Models

Spherical Earth models, as their name suggests, assume a perfectly *Spherica*l Earth. Position calculations are therefore based on *Spherical* trigonometry. The errors introduced by this assumption and method of calculation are principally, but not exclusively, dependent upon the adopted value of *Spherical* Earth radius, the *Latitude* of own ship, and the distance and direction to the observed (or reported) contact. Table 3-3 below indicates the likely maximum size of error induced by assumption of a *Spherical* Earth, by comparison with the *WGS 84 Spheroid,* when dealing with contacts at long range.

Table 3-3. Errors from a Spherical Earth Calculation versus WGS 84 Spheroid

Range of Contact (n. miles)	**Positional error (n. miles) at Latitude 0˚**	**Positional error (n. miles) at Latitude 75˚**
50	0.1	0.3
100	0.1	0.7
250	0.3	1.7
500	0.5	3.4
1000	1.1	6.5
2000	1.9	11.3

Note 3-6. *In the above calculations and tabulated results no account has been taken of the height above (or below) the reference surface (Spheroid, Sphere, Tangential Plane) of own platform or the target. This in itself will lead to further range errors, in addition to those directly due to the use of approximate Earth models.*

0333. Flat Earth Models

a. **Flat Earth Assumptions.** *Flat Earth* models assume a plane Earth and their *Cartesian Coordinate* reference systems adopt a 2-dimensional concept. These 2-dimensional *Cartesian Coordinate* systems have axes arranged to lie along True (or Magnetic) North and due East from an arbitrarily chosen *Grid Origin*, which may not always coincide with own ship's position.

b. **Errors Associated with Flat Earth Assumption.** The errors introduced by the *Flat Earth* assumption are dependent on the specific algorithms implemented within individual navigation systems. However, in general, the size of error will be a function of both the distance from the *Grid Origin* and the *Latitude* of the *Grid Origin*. Thus errors in bearing and distance increase with distance from the *Grid Origin* and with increase in the *Latitude* of the *Grid Origin*.

CHAPTER 4

PROJECTIONS AND GRIDS

CONTENTS

Para

0401. Scope of Chapter

SECTION 1 - PROJECTION CONCEPTS AND PRINCIPLES

0410. Transposing Three Dimensions to Two Dimensions
0411. Distortion in Projections
0412. Projection Graticules and Grids
0413. Spherical Projections
0414. Spheroidal Projections

SECTION 2 - MERCATOR PROJECTION FOR CHARTS

0420. Principles of the Mercator Projection
0421. Mathematical Analysis of the Mercator Projection
0422. Meridional Parts of a Mercator Chart
0423. Constructing a (Small Scale) Mercator Chart of the World
0424. Constructing a (Larger Scale) Mercator Chart of Part of the World
0425. Great Circle Tracks on a Mercator Chart

SECTION 3 - TRANSVERSE MERCATOR PROJECTION FOR CHARTS

0430. Transverse Mercator Projection - Concept
0431. Transverse Mercator Projection - Principles

SECTION 4 - GNOMONIC PROJECTION FOR CHARTS

0440. Gnomonic Projection - Concept
0441. Transfer of a Great Circle Track from a Gnonomic to a Mercator Projection Chart
0442. Composite Tracks

SECTION 5 - GRIDS

0450. Grid Reference Systems - Concept
0451. Universal Transverse Mercator (UTM) Grid
0452. British (Ordnance Survey) National Grid
0453. Other National Grids
0454. Grivation

INTENTIONALLY BLANK

CHAPTER 4

PROJECTIONS AND GRIDS

0401. Scope of Chapter

Chapter 4 introduces *Projections* and *Grids* and their application in navigation. Detailed information on *Projections,* including their mathematical derivation, is at Appendix 4.

0402-0409. Spare

SECTION 1 - PROJECTION CONCEPTS AND PRINCIPLES

0410. Transposing Three Dimensions to Two Dimensions

a. **Requirement for Projections.** The Earth is a 3-dimensional *Spheroidal* object and a chart is a 2-dimensional plane. A *Projection* is a method of representing a *Spheroidal* surface on a plane. It is usually expressed as a mathematical formula for converting *Spheroidal* geographical co-ordinates to plane co-ordinates on charts or maps. Provided it is suitable, a *Projection* may be used to represent any portion of the Earth's surface.

b. **Distortion.** A *Spheroidal* surface CANNOT be fitted exactly on to a plane and, except over very small *Area*s, all *Projections* will contain some distortion. When the outline of three identical circular *Area*s from different parts of the Earth's surface are each *Projected* from a point of origin at the centre of the Earth on to a plane chart, they are represented by a quite different sizes and shapes (see example at Fig 4-1 below).



Fig 4-1. Example of Distortion of Areas of the Earth's Surface on a Chart

0411. Distortion in Projections

a. **Properties of Projections.** The distortion of a *Projection* must involve some or all of the following four interrelated properties:

- **Shape.**
- **Bearing.**
- **Scale.**
- **Area.**

b. **Choice of Projection Properties.** *Projections* can be devised which will eliminate or reduce to negligible proportions some of these distortions, while keeping the others within reasonable (and thus usable) limits. The choice of *Projection* for a chart of map is thus governed by the specific purpose for which the chart is intended.

c. **Mariners' Chart Projection Property Requirements.** Presentation of the correct *Area* of land on a chart is not usually a priority for the mariner, although it may be important for other users. Ideally, the mariner requires a chart which will provide the correct *Shape* of land, and correct *Bearings* and distances (*Scale*). Unfortunately these 3 requirements CANNOT be met in one single *Projection*, and a compromise must be made by accepting a very close approximation to all three (*Shape*, *Bearing*, *Scale*), or satisfaction of two (usually *Shape* and *Bearing*) at the expense of the third (*Scale*).

d. **Orthomorphism.** An *Orthomorphic* (or *Conformal*) *Projection* is one in which, with certain compromises (see Para 0411e below), *Shape*, *Scale* and *Bearings* are correctly represented. These properties are the ones needed by mariners, because, if distortion of *Shape* occurs, then distortion of the *Compass Rose* (ie *Bearing*) must also occur. A compass rose on a chart which is NOT *Orthomorphic* will NOT be circular, nor will its graduation be uniform, and so it would be impossible to lay off courses and bearings correctly. *Mercator*, *Transverse Mercator, Inverse (Oblique) Mercator, Lamberts Conical Orthomorphic, Skew Orthomorphic* and *Stereographic* charts (see Fig 4-3b) are *Orthomorphic*. In *Orthomorphic* chart *Projection*s, the following apply:

- **Shape.** The *Shape* of the land correctly represents that of the Earth's surface, at least over small *Area*s.
- **Scale.** At any specific point on that chart or map the *Scale* is the same in all directions. However, the same *Scale* may NOT apply to the whole chart.
- **Bearing.** The *Parallel of Latitude* and *Meridian* of *Longitude* at any point are at right angles to each other. Angles around any point on that chart or map, and hence *Bearings*, are correctly represented.

e. **Orthomorphism Compromises.** No *Projection* can meet the mariner's ideal requirement for perfect *Shape*, *Bearing* and *Scale* over large *Areas*. On a *Mercator* chart of the world, (see Fig 4-2 opposite), the *Area* around Cape Farewell (Greenland) is just as correctly shown for *Shape* as is the Amazon Estuary (South America), but Greenland as a whole 'appears' to have about the same *Area* as South America, whereas it is actually about one-tenth. This is because the *Scale* in the (near-*Polar*) Greenland *Area* is quite different from the *Scale* being used for *(Equatorial)* South America on the same chart, and this affects *Area* properties. The change of *Scale* can also be seen (at Fig 4-2) in the expanding intervals towards the *Poles* between *Parallels of Latitude*.

(0411e continued)


60° W
Meridian of 0° (Greenwich)
60° E
120° E
180° E / W
120° W
60° W
80°
70°
60°
50°
40°
30°
20°
10°
0°
10°
20°
30°
40°
50°
60°
70°
75°
GREENLAND
CAPE FAREWELL
EUROPE
ASIA
NORTH AMERICA
AFRICA
INDIA
AMAZON ESTUARY
SOUTH AMERICA
AUSTRALIA
ANTARCTICA

Fig 4-2. Mercator Chart of the World (*showing Scale Error increasing with Latitude*)

(0411) f. **The 'Flat Earth' Concept.** Over a limited *Area* (12 miles radius from a point) the Earth may be assumed to be flat for all practical purposes, as the errors introduced by this assumption are less than those resulting from the measurement of angles and distances. A simple sketch survey plan over a small *Area* may be constructed on *Flat Earth* principle by transferring observed ranges and bearings directly to a sheet of squared paper (see Chapter 18). However, at a distance of 50 miles from a point, the errors introduced by assuming a *Flat Earth* become navigationally and operationally significant; they increase rapidly with distance (see Para 0333).

0412. Projection Graticules and Grids

a. **Graticules.** A *Graticule* is the network of lines representing the *Parallels of Latitude* and *Meridians of Longitude* in a *Projection*.

b. **Grids.** A *Grid* is a reference system of rectangular *Cartesian Coordinates* obtained when a *Projection* is applied either to the whole world or a part of it. *Grids* are described in detail at Paras 0450-0453.

0413. Spherical Projections

If the Earth were considered to be *Spherical*, *Projections* could be created by wrapping a plane surface around an imaginary *Sphere*, switching a light on at its centre (or other position) and projecting features from the Earth's surface onto the plane. Although the Earth is *Spheroidal* and different methods are used in practice (see Para 0414 overleaf), the above analogy is adequate to explain the concepts and basic properties of the *Projections* in the examples below.

a. **Tangent and Secant Projections.** Using the above analogy, Fig 4-3a (opposite) shows six common examples of fitting plane surfaces around an imaginary *Sphere*.

- **Tangent Projections.** In the left column of Fig 4-3a (Examples 1, 3 and 5) the surfaces touch the *Sphere* along a circle or at a point. This type are known as '*Tangent Projections'*.
- **Secant Projections.** In the right column of Fig 4-3a (Examples 2, 4 and 6) the plane surfaces have been sunk into the *Sphere*; in Examples 2 and 4 they cut the *Sphere* twice and in Example 6 once. This type are known as '*Secant Projections*.

b. **Areas of Accuracy and Distortion.** If the detail on the *Spheres* at Fig 4-3a (opposite) are now projected on to a plane surface from a point on the axis of the cone, cylinder or plane circle, there will be no distortion of *Scale* along the lines where contact is made with the *Sphere* (shown by bold, grey-filled dashed lines). Elsewhere there is distortion of some sort or another, which will persist when the planes are unwrapped and laid flat.

c. **Points of Projection.** In Examples 1, 2, 3 and 4 of Fig 4-3a, the point from which the *Projection* takes place is usually the centre of the *Sphere*. With Examples 5 and 6 it may take place from anywhere on an axis at right angles to the plane, but usually from either the centre *B* of the *Sphere*, or from the opposite *Pole A*. The *Projections* at Fig 4-3a are usually referred to as follows:

- **Example 1:** '*Conical* with one *Standard Parallel*'.
- **Example 2:** '*Conical* with two *Standard Parallels*.
- **Example 3:** *'Cylindrical* with one *Standard Parallel* at the *Equator*'.
- **Example 4:** *'Cylindrical* with two *Standard Parallels*.
- **Example 5:** *'Zenithal'* projected from *A* – '*Stereographic*'.
- **Example 6:** *'Zenithal*' projected from *B* – '*Gnomonic*'.

d. **Orientation of Cones, Cylinders and Plane Circles.** Although for simplicity the examples in Fig 4-3a are oriented 'North-Up', the cones, cylinders and plane circles could equally well be inclined at any angle to the Earth's axis, and in practice, this does occur.

(0413 continued)



Example 1 (Tangent)
Conical with One Standard Parallel

Example 2 (Secant)
Conical with Two Standard Parallels



Example 3 (Tangent)
Cylindrical with One Standard Parallel at the Equator

Example 4 (Secant)
Cylindrical with Two Standard Parallels



Example 5 (Tangent)
Zenithal - Projected from A: Stereographic
Zenithal - Projected from B: Gnonomic

Example 6 (Secant)
Zenithal - Projected from A: Stereographic
Zenithal - Projected from B: Gnonomic

Fig 4-3a. Examples of Commonly Used Spherical Projections

0414. Spheroidal Projections

None of the ‘perspective’ *Projections* at Fig 4-3a (previous page) are *Orthomorphic* for the *Sphere* (except Examples 5 and 6 when *Projected* from *A*), and none at all are *Orthomorphic* for the Earth’s *Spheroidal* shape. To overcome this, completely ‘mathematical’ *Projections* have been devised, analogous to the perspective ones at Fig 4-3a, but with their formulae adjusted to ensure that some have *Orthomorphic* and others ‘*Equal Area*’ properties, as required for their intended task. The main types of *Spheroidal Projection* for charts and *Grids* are explained in outline at Paras 0414a-g (opposite and overleaf) and summarised at Fig 4-3b (below). Details of mathematical constructions are at Sections 2-5 of this Chapter (Paras 0420-0450).

	PROJECTION	TYPE	ORTHOMORPHIC	GRIDS	USED FOR SURVEYS	USED FOR CHARTS	REMARKS
A	**Lamberts Conical Orthomorphic**		Yes	Very many, with one or two Standard Parallels	Yes	Yes, but not many	Used for aeronautical charts. Unsuitable at high Latitudes, where Modified Lambert Conformal is used instead. Superseded by UTM for land mapping.
B	**Mercator**		Yes	Not often used, Grids can be made from Meriodinal navigation tables.	Yes, on small scales	Yes	Used for most small scale Admiralty charts.
C	**Transverse Mercator**		Yes	—	Yes	Yes	Used for large-scale charts.
				National Grid of Great Britain	Yes	No	Based on Airy’s Spheroid.
				UTM (Universal Transverse Mercator)	Yes	No	Worldwide between 84°N and 80°S
				Many Others	Yes	No	
D	**Skew Orthomorphic**		Yes	Malaysia, Borneo and Madagascar	Yes	No	Used mainly for land surveys and designed to keep scale errors small over the area covered by the grids
E	**Inverse (Oblique) Mercator**	 or 	Yes	Not often used	No	Yes	Excellent for air charts of Polar areas. A very close relation of the Transverse and Skew Orthomorphic.
F	**Stereographic**		Yes	Universal Polar Stereographic.	Yes	Yes (Polar Charts)	Good for surveys between the Pole and 80°. Not so good for small scale charts.
G	**Gnomonic**		No	Not used	No	Yes	Used for small scale Great Circle charts
H	**Polyconic**		No	Polyconic Projection Tables.	Yes	Yes	The so-called ‘Gnomonic’ of old large scale UKHO plans. Largely superseded by Transverse Mercator.

Fig 4-3b. Commonly Used Projections and Grids

(0414) a. **Lambert's Conical Orthomorphic Projection.** *'Lambert's Conical Orthomorphic Projection*' (see Fig 4-3b, Line A) is a modification of the *Conical Projection* with one or two *Standard Parallels* (see Fig 4-3a, Examples 1 and 2).

- **Orthomorphism.** The *Parallels* (of *Latitude*) other than the *Standard Parallels* appear as circular arcs, concentric with the *Standard Parallels*, but distances between them are chosen so that the *Projection* is *Orthomorphic*.
- **Scale Manipulation.** To achieve *Orthomorphic* properties, the *Scale* along the *Meridian* at any place must be equal to the *Scale* along the *Parallel* at that place. The *Scale* along the *Meridian* cannot now be uniform but must be adjusted to the *Scale* along the *Parallels*. The *Scale* is correct only along the *Standard Parallels*; if there are two of these, the *Scale* is smaller between them and it becomes increasingly large outside. The *Latitude* covered by the *Projection* is limited so that the *Scale* error does not become unacceptable.
- **Great Circles.** *Great Circles* are very nearly straight lines on this *Projection*.
- **Uses.** This *Projection* is widely used for aeronautical charts. It cannot be used in high *Latitudes* where *Modified Lambert's Conformal* is used instead. It can also be used for mapping countries with a large extent in *Longitude* but not much in *Latitude*, but has largely been superseded for this purpose by the *Universal Transverse Mercator Projection* (see Fig 4-3b / Para 0414c).
- **Derivatives.** The *Mercator Projection* is a derivative of *Lambert's Conical Orthomorphic Projection.*

b. **Mercator Projection.** The *Mercator Projection* (see Fig 4-3b, Line B) is described in detail at Paras 0420-0425, but a brief summary is as follows.

- **Scale Expansion.** *Scale* units are minutes of *Longitude* measured along the *Equator*. The *Scale* expands as *Latitude* increases (see Fig 4-2).
- **Meridional Parts.** The *(Cartesian Coordinate) Grid* is not normally shown, although accurate calculations are generally carried out in terms of *Meridional Parts* which form the unit of the *Grid.*
- **Properties.** The *Mercator Projection* is *Orthomorphic* and is a special case of *Lambert's Conical Orthomorphic Projection* in which the *Equator* is used as the *Standard Parallel*. Its properties are:
    - ‣ *Rhumb Lines* on the Earth appear as straight lines on the chart.
    - ‣ Angles between *Rhumb Lines* are the same on the Earth's surface / chart.
    - ‣ The *Equator* (a *Rhumb Line* & *Great Circle*) appears as a straight line.
    - ‣ *Parallels of Latitude* appear as straight lines parallel to the *Equator*.
    - ‣ *Meridians* appear as straight lines perpendicular to the *Equator*; use of a *Meridional Grid* to plot Eastings / Northings is unnecessary.
    - ‣ A straight line on the chart joining two points does NOT represent the shortest distance between them, unless it is also *Great Circle*. A *Great Circle* which is not a *Meridian* or the *Equator* will appear as a curve.
    - ‣ Increased spacing of adjacent *Parallels* away from the *Equator* leads to *Scale* magnification which increases with *Latitude* (see Fig 4-7).
    - ‣ The *Shape* of charted features is correctly drawn for small *Areas* but those of large features are distorted as *Latitude* increases.

(0414b continued)

- **Uses.** The *Mercator Projection* is extensively used for standard *UKHO* nautical charts at *Scales* smaller than 1:50,000, up to *Latitudes* 80°N / 80°S. However, for large *Scale* nautical charts (1:50,000 and greater), the *Transverse Mercator Projection* is generally used instead (see Paras 0430-0431).

- **Shape on a Mercator Chart - Scale Error Increasing with Latitude.** On the Earth, *Meridians* converge (see Fig 4-4 - left diagram), so land masses on a *Mercator Projection* chart will be increasingly distorted in an east-west direction proportional to their distance from the *Equator*, until at the *Poles* their sizes would be infinite. In order to preserve the correct *Shape*, the *Parallels of Latitude*, which are equally spaced on the Earth's surface (see Fig 4-4 - right diagram) must be increasingly spaced towards the *Poles* on the *Mercator Projection* chart until at the *Poles* the *Latitude Scale* is infinite. This distortion is governed by the secant of the *Latitude*. Thus, on a *Mercator Projection* chart of the world (see Fig 4-2 at Para 0411), Greenland appears as broad as Africa at the *Equator*, although the latter is three times wider; this fact becomes apparent once the distance is measured at the *Latitude Scale* in the vicinity of the two *Areas*.



Convergence of Meridians

Spacing of Parallels of Latitude

Fig 4-4. Earth's Surface - Convergence of Meridians and Spacing of Parallels

- **Practical Measurement of Distance on Mercator Projection Charts.** For the reasons stated above, distances should ALWAYS be measured using the *Latitude Scale* at the *Latitude* of the position concerned. The *Longitude Scale* must NEVER be used for measuring distances on a *Mercator Projection* chart.

- **Use of the Rhumb Line as Course.** If two places on the Earth's surface are joined by a *Rhumb Line* and a ship steers along that line, the direction of the ship's head will remain the same throughout the passage (see Para 0202a). This direction is measured by the angle from the *Meridian* to the *Rhumb Line*, measured clockwise from 0° to 360°, and is the *Course*. The *Rhumb Line* itself is often called the *Course*. On the Earth's surface, a continuous *Rhumb Line* (except 090°/270°) will spiral towards the *Pole*. The *Mercator Projection* chart shows the ship's track as a straight line between the starting-point and destination; the measurement of this straight line gives the steady *Course*.

(0414b continued)

- **Plotting of Great Circle Tracks.** A *Great Circle* which is not a *Meridian* or the *Equator* will appear as a curve on a *Mercator Projection* chart (see Fig 4-5 below). Thus *Great Circle* tracks are normally plotted on a *Gnonomic* chart and the *Waypoints* transferred to a *Mercator Projection* chart.



Fig 4-5. Mercator Projection of North Atlantic - Rhumb Line / Great Circle Tracks

(0414) c. **Transverse Mercator Projection.** The *Transverse Mercator Projection* (see Fig 4-3b, Line C) is described in detail at Paras 0430-0431, but a brief summary is as follows.

- **Construction.** The *Transverse Mercator Projection* may be considered as a standard *Mercator Projection* (see Fig 4-3a, Example 3) with the 'cylinder' turned through 90˚. The *Central Meridian* and the *Equator* plot as straight lines; all other *Meridians* and *Parallels* plot as curves.

- **Properties.** The *Transverse Mercator Projection* is *Orthomorphic*.
  - **Scale Expansion and Direction.** The *Scale* between *Meridians* expands as *Longitude* increases away from the *Central Meridian.* However, due to the large *Scale* used, these *Meridians* will appear as straight lines to the user, and for all practical purposes, straight lines can be used to plot all *Bearings* and direction lines on the chart.
  - **Central Meridians.** To minimise the effects of *Scale* expansion, coverage of a *Transverse Mercator Projection* chart is restricted to ±3˚ of *Longitude* from the *Central Meridian.*
  - **High Latitudes.** The *Transverse Mercator Projection* does not suffer from the high *Latitude* difficulties of standard *Mercator Projection*s.

- **Uses.** The *Transverse Mercator Projection* is used for:
  - Most *UKHO* large *Scale* charts of 1:50,000 or larger (ie covering a small *Area*) as well as for land maps.
  - Most land maps (including UK Ordnance Survey maps and NATO military maps).
  - *Polar* charts and maps, although the *Polar Stereographic Projection* (see Para 0414d overleaf) is more commonly used for this purpose.

(0414) d. **Stereographic Projection (Universal Polar Stereographic Projection).** The point of origin of a *Stereographic Projection* (see Fig 4-3b, Line F) may be anywhere; however, as this projection is normally only used in *Polar* regions, only the *Universal Polar Stereographic Projection* is considered here.

- **Construction.** For the *Universal Polar Stereographic Projection,* the *Meridians* and *Parallels of Latitude* are *Projected* on to a plane tangential to the *Pole*, the centre of *Projection* being the opposite *Pole* (see Fig 4-3a, Example 5). *Meridians* appear as straight lines originating from the *Pole*, *Parallels of Latitude* appear as concentric circles radiating outwards from and centred on the *Pole*.
- **Orthomorphic Properties.** The *Universal Polar Stereographic Projection* is *Orthomorphic*.
- **Great Circles.** *Great Circles* (except *Meridians*) are not projected as straight lines, although in practice, little accuracy is lost by plotting them as such.
- **Uses.** The *Universal Polar Stereographic Projection* is used for Polar charts and *Orthomorphic* maps of *Polar* regions.

e. **Gnomonic Projection.** The *Gnomonic Projection* (see Fig 4-3b, Line G) is described in detail at Paras 0440-0442, but a brief summary is as follows.

- **Construction.** The *Gnomonic Projection* projects the Earth's surface from the Earth's centre onto a tangent plane. The *Gnomonic Projection* is only applied to a *Sphere* which represents the Earth.
- **Properties.** The *Gnomonic Projection* is NOT *Orthomorphic* and has the following properties:
  - **Great Circles.** *Great Circles* are represented by straight lines on this *Projection*.
  - **Parallels of Latitude.** *Parallels of Latitude* are curves.
  - **Meridians.** The *Meridians* will not be parallel unless the tangent point is on the Equator.
  - **Rhumb Lines.** *Rhumb Lines* will be shown curves, not as straight lines.
  - **Tangent Point and Distortion.** Angles are also distorted, except at the tangent point. The farther a point on the chart is away from the tangent point, the greater will be the distortion. It is therefore impossible to take courses and distances from a *Gnomonic Projection* chart.
  - **Equal Areas.** The *Gnomonic Projection* does NOT have *Equal Area* properties.
- **Uses.** The distortion of the *Gnomonic Projection Graticule*, which gives neither *Orthomorphic* nor *Equal Area* properties, makes it quite unsuitable for general *Navigation* purposes. Its usage is limited entirely to plotting *Great Circles* as straight lines, usually in order to obtain *Great Circle Waypoints*. It was also used historically to plot long range radio beacon *Bearings*, although this usage has almost completely disappeared.

f. **Skew Orthomorphic Projection.** Instead of a *Central Meridian*, a central *Great Circle* passing through the axis of the country is used as the line of contact for the *Skew Orthomorphic Projection* (see Fig 4-3b, Line D). It is used mainly for land surveys.

(0414) g. **Polyconic Projection.** The *Polyconic Projection* (see Fig 4-3b, Line H) is a modification of the simple *Conical Projection*.

- **Construction.** The *Central Meridian* of the *Area* to be displayed is divided correctly for intervals of *Latitude*, but each *Parallel* is constructed as if it were the *Standard Parallel* of a simple *Conical Projection* (see Fig 4-6 below). The *Parallels* are arcs of circles, the radii of which steadily increase as the *Latitude* decreases. The *Central Meridian* is a straight line, although the other *Meridians* are curved.
- **Orthomorphic and Equal Area Properties.** The *Polyconic Projection* is neither *Orthomorphic* nor *Equal Area*, so it is unsuitable for large *Areas*.
- **Advantages.** The main advantage *Polyconic Projection* is that if small *Areas* are shown on this *Projection*, with each small *Area* covering the same amount of *Longitude*, the sheets on which the geographical *Graticules* are drawn fit exactly along their northern and southern edges. For ordinary purposes, the sheets also fit along their eastern and western edges, although the join here is a 'rolling fit' as the *Meridians* are curved (see Fig 4-6 below).
- **Modified Form.** In slightly modified form, the *Meridians* can be made to project as straight lines, and this modified form was used in practice.
- **Uses.** The modified *Polyconic Projection* is suitable for topographical maps which, individually covering a small *Area*, combine to cover a large one. However, it has been superseded by the *Transverse Mercator Projection*. A few old *UKHO* harbour plan charts may still exist with the legend '*Gnomonic Projection*', but they almost certainly used the modified *Polyconic Projection*.



Fig 4-6. Polyconic Projection

Paras 0415-0419. Spare

SECTION 2 - MERCATOR PROJECTION FOR CHARTS

0420. Principles of the Mercator Projection

An introduction to the *Mercator Projection* is at Para 0414b. It is a '*Cylindrical Orthomorphic Projection*' and in practice, it is a 'mathematical' rather than a 'perspective' projection.

a. **Mercator Projection - 'Perspective' Concept and 'Mathematical' Reality.** The 'perspective' concept of the *Mercator Projection* is to imagine a cylinder of paper wrapped around the Earth, with the cylinder's and Earth's axes coincident, and their surfaces in contact only at the *Equator*; the Earth's surface is then projected from the Earth's centre onto the cylinder (see Fig 4-5a below). When unrolled flat, the image on the paper cylinder will represent a *Mercator Projection.* In reality, the 'perspective' method is not used; instead the *Mercator Projection* is produced by 'mathematical' formulae which are adjusted to ensure that the resulting charts are *Orthomorphic*. Different formulae apply for the *Sphere* (see Para 0422) and *Spheroid* (see Para 0531a).


The complete *Polar* regions (N or S) cannot be shown on *Mercator Projection,* as expansion between *Parallels of Latitude* increases to infinity at *Latitude* 90°

Fig 4-7. Simplified Diagram of Mercator Projection

b. **Properties of Mercator Projection.** The properties of the (*Orthomorphic*) *Mercator Projection* are listed at Para 0414b:

c. **Uses.** The uses of *Mercator Projection* are listed at Para 0414b.

d. **History of the Mercator Projection.** The idea of the *Mercator Projection* belongs to Gerhard Kremer, a Fleming who adopted the name Mercator. Kremer used the *Graticule* derived from the *Projection* in the world map which he published in 1569. However, the *Graticule* was inaccurately drawn above the *Parallels* of 40˚, and there was no mathematical explanation of the *Projection.* In 1599, a mathematical explanation was established by Wright who correctly calculated the positions of the *Parallels* and published the results. The *Mercator Projection* chart came into general use among navigators in about 1630, but the first complete mathematical description of it was not available until 1645, when Bond published the logarithmic formula for it.

0421. Mathematical Analysis of the Mercator Projection

a. **Mercator Projection - Concept.** The *Mercator Projection* is introduced at Para 0414b and is "a special case of the *Lambert Conical Orthomorphic Projection* in which the *Equator* is used as the *Standard Parallel* ". Para 0420 and Fig 4-7 opposite) provide an outline of the principles of the *Mercator Projection*.

b. **Mercator Projection - Governing Criteria.** The requirements for the *Mercator Projection* are governed by two criteria:

- In a cylindrical *Projection* based on the *Lambert Conical Orthomorphic Projection,* the *Constant of the Cone* must be zero (see Para 0421d).
- The *Projection* must retain *Orthomorphic* properties (see Para 0421e).

c. **Mercator Projection - Detailed Mathematical Analysis.** Amplifying Para 0420 and Fig 4-7 (opposite) in more detail, Fig 4-8 (overleaf) takes the *Equator* as the *Latitude* of the origin ϕ_0 .

- *RO* is a *Central Meridian* and is equal in length to $V_o \cot \phi$, where V_o is the *Radius of Curvature* at right angles to the *Meridian* at *O* for the *Spheroid* of the Earth in use, and ϕ is the *Latitude* of *O*.
- As the cotangent of 0° is infinity, *R* recedes northwards (or southwards) to infinity (see Fig 4-8 overleaf); this can also be seen from Fig 4-7 (opposite) if *Latitude* is extrapolated to 90°. Thus the complete *Polar* regions can never be shown on *Mercator Projection* charts as expansion between *Parallels of Latitude* expands to infinity at *Latitude* 90°.
- The angle between *True North* and *Grid North* becomes zero for this *Projection*, thus there is no convergence.
- OP_o coincides with *Grid* East, all *Parallels* become straight lines parallel to OP_o and, since *Convergence* is zero, all the *Meridians* are parallel *Grid North*.
- One minute of *Longitude* measured along the *Equator* (or *Standard Parallel*) as the unit of the *Grid* makes this *Projection* suitable for navigation use.

d. **Constant of the Cone.** The quantity $Sin\ \phi_0$ is the *Constant of the Cone* (where ϕ is the *Latitude* of O) and it is a constant for any given *Latitude* of the point of origin. When the *Equator* is the point of origin:

$$\sin \phi_0 = \sin 0^\circ = 0$$

e. **Orthomorphism and Rhumb Lines.** The *Scale* along a *Meridian* in the neighbourhood of a point in *Latitude* ϕ is stretched by the same amount ($\sec \phi$) as the *Scale* along the *Parallel* through that point.

- **Orthomorphism.** In view of this, and that the *Meridians* and *Parallels* on the *Mercator Projection* are at right angles, the *Projection* must be *Orthomorphic*.
- **Rhumb Lines.** The *Parallels* are spaced at increasing intervals as they approach the *Poles* (see Fig 4-7 opposite), while the *Meridian*s are spaced equally. Thus any straight lines (including diagonals) make a constant angle with the *Meridian*s with no distortion; they are thus *Rhumb Lines*.

(0421c continued)



Fig 4-8. Detailed Analysis of Mercator Projection

(0421) f. **Use of Longitude Scale When Constructing a Mercator Chart.** As *Meridians* of the *Mercator Graticule* are straight lines at right angles to the *Equator*, the *Longitude Scale* is the same everywhere and provides a means of measurement in the *Graticule*.

- Let the *Scale* of any *Mercator Projection* chart be *x* millimetres to 1' of *d.long*.
- *Departure* ≃ *d.long* cos *Lat* (see Note 4-1 below), thus *Departure* on the chart represented by '*x* millimetres' approximates to *1'* cos *Lat* (ie one *Sea Mile* in that particular *Latitude* is represented by *x* sec *Lat* millimetres on the chart).
- **Therefore, the *Scale* of *Latitude* and distance at any part of a *Mercator Projection* chart is proportional to the secant of the *Latitude* of that part; thus the amount of distortion in any *Latitud*e is also governed by the secant of that *Latitude* (see Example 4-1 below)**.
- The *Latitude Scale* cannot be used to draw the *Parallel* in its correct position on the *Graticule* because it is continually being stretched as the *Latitude* increases. **Thus for this purpose, the spacing of any *Parallel* from the *Equator* must be calculated in units of the *Longitude Scale*.**

Example 4-1. On a *Mercator Projection* chart (see Fig 4-2), Greenland (70˚N) appears to have the same width as Africa (0˚), although Africa is in reality three times as wide as Greenland. This is not unexpected, as: *sec 70˚ ≃ 3.*

Note 4-1. *This formula is correct for the Sphere but only approximates for the Spheroid. The precise length of one minute of Longitude is given by formula (3.12) at Para 0314.*

(0421) g. **Measurement on the Chart.** *Mercator Projection* charts are graduated along the sides for *Latitude* and along the top and bottom for *Longitude*.

- **Latitude Scale and Distance.** The length of the *Rhumb Line FABCT* is the distance between them (see Fig 4-9); FF_1, AA_1, BB_1 etc are *Parallels* of *Latitude.* The distance between any two points must be measured on the *Latitude Scale* between their *Parallels* of *Latitude* (ie *FA* between F_1 and A_1, *AB* between A_1 and B_1 etc). If *FT* is less than 100', no appreciable error is made by measuring it on the *Scale* roughly either side of its middle point.
- **Longitude Scale.** The *Longitude Scale* is used only for laying down or taking off the *Longitude* of a place, never for measuring distance.


P
T
T1
Measure distance CT against Latitude C_1T_1
Parallel of Latitude
Rhumb Line 'FABCT'
C
C_1
Measure distance BC against Latitude B_1C_1
Parallel of Latitude
B
B_1
Measure distance AB against Latitude A_1B_1
Parallel of Latitude
A
A_1
Measure distance FA against Latitude F_1A_1
F
F_1

Fig 4-9. Measurement of Distance on a Mercator Chart

0422. Meridional Parts of a Mercator Chart

a. **Latitude and Distance Scale Distortion.** Para 0414b / Fig 4-4 and Para 0420a / Fig 4-7 established that the *Latitude* (distance) *Scale* of a *Mercator Projection* chart continually increases as it recedes from the *Equator*, until at the *Pole* it becomes infinite; thus the complete *Polar* regions cannot be shown on a *Mercator Projection* chart. Para 0421f (opposite) established that the *Latitude* (distance) *Scale* at any part of a *Mercator* chart is proportional to the secant of the *Latitude* of that part.

b. **Meridional Parts.** The *Latitude Scale* of a *Mercator Projection* chart affords no ready comparison with the fixed *Longitude Scale*. In Fig 4-9 (above), the tangent of the course-angle *PFT* cannot be *PT* (measured on the fixed *Longitude Scale*) divided by *FP* (measured on the *Latitude Scale*), because the units of *Latitude* measurement are continually changing. For the ratio *PT / FP* to be valid, *PT* and *FP* must be measured in the same fixed units. The length of 1 minute of arc of the fixed *Longitude Scale* provides this unit of measurement and is called a '*Meridional Part*'. Thus:

> ***The Meridional Parts of any Latitude are the number of 'Longitude Units' in the length of a Meridian between the Parallel of that Latitude and the Equator. A 'Longitude Unit' is the length on the chart representing one minute of arc in Longitude.***

Meridional Parts are lengths measured on the *Mercator Projection* chart (usually called '*Chart Lengths*') and should NOT be confused with distance on the Earth's surface, which is expressed in *Sea Miles* or *Nautical Miles* (see Para 0422c / Example 4-2).

(0422) c. **Number of Meridional Parts for Any Latitude.** The number of *Meridional Parts* for any *Latitude* may be found from formula (4.1) for the *Sphere* (see Para 0422e below) and formulae (5.21a/b) for the *Spheroid* (see Para 0531a). They are also tabulated in Norie's Nautical Tables (NP 320) which uses the Clarke 1880 *Spheroid* ('compression' of 1/293.465 [ie based on '*1/Flattening'* = 293.465 at Para 0322 Table 3-1]). Example 4-2 shows their use in calculating the length of the *Meridian* on a *Mercator Projection* chart (ie the *Chart Length*) between a *Parallel of Latitude* and the *Equator.*

Example 4-2. If the *Longitude Scale* on the *Mercator Projection* chart is 1 degree (ie 60 *Meridional Parts*) to 10 mm, what is the length of the *Meridian* between the *Parallel* of 45° 00' N and the *Equator*, when measured on the chart in millimetres?

From NP 320, for 45° 00' there are 3013.38 *Meridional Parts*. Thus the distance on the chart (ie the Chart Length) for the *Meridian* is 10 x 3013.38 / 60 = 502.23mm.

A simplistic and incorrect calculation of 45 x 10 = 450mm is entirely wrong.

d. **Difference of Meridional Parts (DMP).** Where the two positions are both remote from the *Equator* (eg *A* and *K* in Fig 4-10a, and *a* and *k* in Fig 4-10b opposite), their relative position may be determined by the difference between the individual *Meridional Parts* for *K* and the individual *Meridional Parts* for *A*, which gives the number of *Longitude Units* in the length of a *Meridian* between the two *Parallels of Latitude* through *A* and *K*. **This length *mk* (see Fig 4-10b opposite) is usually referred to as the '*Difference of Meridional Parts'* and written as '*DMP*'.** See also Para 0510-0511.

e. **To Find the Meridional Parts of any Latitude on a Sphere.** Fig 4-10a (opposite) represents a part of the Earth's *Spherical* surface (see Note 4-2 overleaf for *Spheroidal* data). Position *F* is a point on the *Equator* and *FT* is the *Rhumb Line* joining it to position *T.* Fig 4-10b (opposite) shows this same *Rhumb Line* as the straight line *ft* on a *Mercator Projection* chart.

- If TQ is now divided into n small lengths α, so that $(n\alpha)$ is equal to the *Latitude* of *T*, the arcs of *Parallels of Latitude* drawn through the points of division are equally spaced and, with the *Meridians*, form a series of small triangles *FAX*, *ABY*, ... If α is so small that these triangles may be considered plane, they are equal in **all** respects, since:

$$\begin{aligned} FX &= AY = \dots = \alpha \\ FXA &= AYB = \dots = \text{one right angle} \\ XFA &= YAB = \dots = \text{the course} \\ \therefore AX &= BY = \dots \end{aligned}$$

- Since these small arcs recede in size in succession from the *Equator*, the *Meridians* which bound them are spaced successively farther apart. Hence:

$$FQ_1 < Q_1Q_2 < \dots$$

- A comparison of Figs 4-10a and 4-10b shows that the small triangles on the Earth are all 'equal'(ie equal angles and linear dimensions), but when drawn on the chart, they are only 'similar'(ie equal angles only).
- The triangles in Fig 4-10b progressively increase in size as they recede from the *Equator*, and this is emphasised by progressively darker shading. This increase in size can be found by considering two similar and corresponding triangles.

(0422e continued)


P
Z
T
K
Fig 4-10a.
Representation
of a Rhumb Line on
the Earth's Surface
Rhumb Line
Meridional Parts
Y
α
B
X
M
α
A
W
E
F
Q1
Q2
Equator
Q3
Q


t
z
Fig 4-10b.
Representation
of Fig 4-10a (above)
on a Mercator
Projection Chart
k
Rhumb Line
Meridional Parts
y
b
x
a
m
w
e
f
q1
q2
Equator
q3
q

Fig 4-10a (top figure). Representation of a Rhumb Line / Mer Parts on the Earth's Surface

Fig 4-10b (bottom figure). Representation of Fig 4-10a on a Mercator Projection Chart

(0422e cont) Thus:

$$\frac{fx}{FX} = \frac{ax}{AX} = \frac{FQ_1}{AX} = sec\ \ Lat\ A$$

$$fx = FX\, sec\ Lat\ A$$

$$= \alpha\, sec\ \alpha$$

- Similarly, by considering the triangles *ABY* and *aby*:

$$ay = \alpha\, sec\ 2\ \alpha$$

- But *qt*, the length of the *Meridian* between the *Parallel of Latitude* through *t* and the *Equator,* is the sum of all the elements *fx*, *ay* . . . *kz*. That is:

$$qt = \alpha\,(\sec\alpha + \sec 2\alpha + \sec 3\alpha + \ldots + \sec n\alpha)$$

$$qt = 7915.7045\, log_{10} tan\left(45° + \frac{T°}{2}\right) \qquad \ldots \mathbf{4.1}$$

Note 4-2. *Formula (4.1) gives the number of Meridional Parts in the Latitude of T for a* *Sphere* *(see also Appendix 3). It is a simplified version of the equivalent* *Spheroidal* *formulae (5.21a/b) at Para 0531a, but with the corrections for Spheroidal Eccentricity 'e' ignored; the proof of formulae (5.21a/b) are at Appendix 5. As stated at Para 0422c, Norie's Nautical Tables (NP 320) gives the Meridional Parts for the* *Clarke 1880 Spheroid* *('compression' of 1 / 293.465).*

0423. Constructing a (Small Scale) Mercator Chart of the World

a. **Calculating the Longitude Scale.** As there is no *Latitude* or distance distortion at the *Equator* on a *Mercator Projection* chart, the base on which the chart is constructed must be the line representing the *Equator*, and convenience governs the length of this line. Suppose it is 720 mm (about 28 in). Then the *Longitude Scale* must be:

$$\frac{Length\ of\ Equator\ in\ degrees}{Length\ of\ base\ in\ millimetres} = \frac{360}{720} = \tfrac{1}{2}°\ Longitude\ per\ millimetre$$

½˚ of *Longitude* at the *Equator* equates to 30 *Meridional Parts*; more conveniently this can be expressed as 5˚ of *Longitude* or 300 *Meridional Parts* to 10 mm. Vertically the *Scale* will be the same, 300 *Meridional Parts* to 10 mm.

b. **Placing of Meridians.** If it is required (for example) to draw *Meridians* every 20˚ of *Longitude*, the *Equatorial* line must be divided into eighteen (20˚ x 18 = 360˚) equal parts, each of 40 mm (or 1200 *Meridional Parts*) in width. The perpendiculars drawn through the points of division will be the *Meridians*. For simplicity (see Note 4-3 below), the *Prime Meridian* (*Greenwich Meridian,* 0˚ *Longitude*) has been placed in the centre of Fig 4-11 (opposite); thus with a total coverage of 360˚ of *Longitude*, the extreme left-hand *Meridian* will be 180˚W and the extreme right-hand *Meridian* will be180˚E.

Note 4-3. *In practice, the Prime Meridian (0˚ Longitude) is normally placed off-centre to the left with some overlap (usually 40˚) of Longitude overall (ie 400˚ coverage), in order to show the Atlantic Ocean, Indian Ocean and Pacific Ocean in an unbroken view, with North America shown in full at one side of the chart and South America at the other (see example at Fig 4-2).*



Fig 4-11. Graticule for a Mercator Chart of the World (Centred on the Prime Meridian)

(0423) c. **Placing of Parallels of Latitude.** *Meridional Parts* for deciding the positions of the *Parallels of Latitude* may be extracted from Norie's Nautical Tables (NP 320), although it uses the Clarke 1880 *Spheroid* (see Para 0422c).

- **Parallels of Latitude for 20˚.** From NP 320, there are 1217.14 *Meridional Parts* between the *Parallels of Latitude* for 20˚ and the *Equator*. At a *Scale* of 300 *Meridional Parts* to 10 mm, the *Parallels of Latitude* for 20˚ must be drawn on the chart 1217.14 ÷30 = 40.57mm either side of the *Equator*.
- **Parallels of Latitude for 40˚.** Similarly, there are 2607.64 *Meridional Parts* between the *Parallels of Latitude* for 20˚ and the *Equator* and so the *Parallels of Latitude* for 40˚ are drawn 2607.64 ÷ 30 = 86.92mm from the *Equator*.
- **Other Parallels of Latitude.** In the same way the other *Parallels of Latitude* are drawn. On the *Graticule* formed (see Fig 4-11 above), it is possible to insert the position of any place, if the *Latitude* and *Longitude* are known.

d. **Choice of Spheroids when Constructing a Mercator Projection Chart.**

- **Errors Induced by Using Norie's Tables - Clarke 1880 Spheroid.** The table of *Meridional Parts* in Norie's Nautical Tables (NP 320) uses the (Clarke 1880 *Spheroid*). This will produce a chart based on the Clarke 1880 *Spheroid* and induce an error when plotting positions referred to *WGS 84* (ie *GPS*) on the chart. However, on a very small *Scale* world-map such as this, for practical purposes of plotting, the induced error will be negligible.
- **Use of Spheroid Meridional Parts Formulae for WGS 84.** To construct a *Mercator Projection* chart based on *WGS 84*, the appropriate *Meridional Parts* for this *Spheroid* need to be calculated using general formula (5.21a) at Para 0531a, which is customised for *WGS 84* at formula (5.21b) at Para 0531a.

0424. Constructing a (Larger Scale) Mercator Chart of Part of the World

To show small portions of the Earth in detail, a larger *Scale* is needed with only the relevant portion of the chart being constructed.

a. **Equator Not Included on Chart.** If the *Equator* is not included on the chart, the *Chart Lengths* between successive *Parallels of Latitude* on the chart (in millimetres, appropriate to the *Scale* chosen) are found from the *Difference of Meridional Parts* (*DMP*) for the corresponding *Parallels of Latitude* (see Para 0422d).

b. **Construction.** To construct a *Mercator Projection Graticule* (see Fig 4-12 opposite) from 142˚E - 146˚E and 45˚N - 49˚N at a *Scale* of 1˚ of *Longitude* to 30mm:

- At this *Scale*, 1' *Longitude* equates to 30÷60 = 0.5mm.
- The difference between 142˚E - 146˚E is 4˚, and at a *Scale* of 1˚ of *Longitude* to 30mm, the base-line at the bottom of the chart representing the *Parallel of Latitude* 45˚N is thus 30 x 4 = 120 mm in width.
- The limiting *Meridians* of 142˚E and 146˚E will be perpendiculars erected on this line at its two ends. The *Meridians* of 143˚E, 144˚E, 145˚E will be spaced equally between the limiting *Meridians* (see Fig 4-12 opposite).
- The length in millimetres between the *Parallels of Latitude* of 45˚N to 49˚N can be established from the *DMPs* at Table 4-1 (below).

Table 4-1. 'Chart Lengths' (mm) between Parallels of Latitude of 45˚N to 49˚N

Latitude	Meriodinal Parts (*from Norie's Tables - See Note 4-4 opposite*)	DMP	'Chart Lengths' between Parallels (DMP x 0.5)
49˚N	3364.41	---	
48˚N	3274.13	90.28	45.14 mm
47˚N	3185.59	88.54	44.27 mm
46˚N	3098.70	86.89	43.45 mm
45˚N	3013.38	85.32	42.66 mm

c. **Intermediate Divisions.** To create intermediate divisions on the *Graticule*, for both *Longitude* and *Latitude Scales*, the *Chart Lengths* between *Meridians*, and those between *Parallels of Latitude* may be calculated for smaller units (eg 10' of *Longitude* between *Meridians*, and 10' of *Latitude* between *Parallels*). This division is easily effected on the *Longitude Scale*, because it is fixed. On the *Latitude Scale*, a new table of *Meridional Parts* for every 10' of *Latitude* between 45˚ and 49˚is needed (not shown).

d. **Completed Graticule.** Fig 4-12 (opposite) shows the complete *Graticule* for this example. Each rectangle, whatever its dimensions in millimetres, represents a part of the Earth's surface bounded by *Meridians* 1˚ apart in *Longitude,* and *Parallels* 1˚ apart in *Latitude*. Although the *Chart Lengths* between these *Parallels of Latitude* vary from 42.66mm to 45.14mm as shown, each *Chart Length* represents a distance of 60 *Sea Miles* on the Earth's surface. The actual distance in *Sea Miles* between the *Meridians* depends on the *Latitude* in which it is measured on the chart (41.82 *Sea Miles* at 46˚N and 40.27 *Sea Miles* at 48˚N), and may be obtained by measurement against the *Latitude Scale*, or from formulae (3.12) and (3.9).

(0424d continued)


60 Miles
45.14mm
49°N
40.27 Miles
48°N
44.27mm
F
10 Miles
47°N
129° 135 Miles
43.45 mm
41.82 Miles
46°N
T
42.66mm
45°N
142°E
143°E
144°E
145°E
146°E

Fig 4-12. Construction of a (Larger Scale) Mercator Chart of Part of the World

(0424) e. **Measuring Distances on the Chart.** The distance between any two points must be measured on the *Latitude Scale* between their *Parallels* of *Latitude* (see Para 0421g / Fig 4-9). Using this method, the distances between points *F* and *T* on Fig 4-12 (above), measured on the *Latitude Scale* between 46˚ and 48˚, is found to be 135 miles.

Note 4-4. *The Meriodinal Parts at Table 4-1 (opposite) were taken from Norie's Nautical Tables (NP 320), so that the reader can easily duplicate them. Although NP 320 uses the Clarke 1880 Spheroid (not WGS 84), as it is the DMP which is actually used for construction, in practice little difference in the Graticule Shape is caused. To establish Meridional Parts for WGS 84, use the Spheroidal formulae at Para 0531a.*

0425. Great Circle Tracks on a Mercator Chart

Rhumb Lines appear as straight lines on a *Mercator Projection* chart. In general, *Great Circles* will appear as curves; the exceptions to this are the *Equator* and *Meridians,* which appear as straight lines perpendicular to each other. See also Paras 0414b / Fig 4-5 and Para 0441.

a. **Appearance of Great Circles.** On a *Mercator Projection* chart, the limiting *Great Circles* are the *Equator* which appears as a horizontal line, and any 'double' *Meridians*, which appear as two separate vertical lines 180˚ apart. Any other *Great Circles* passing through their points of intersection must appear as two curves with vertices towards the *Poles* (see Fig 4-13 below).

b. **Great Circles in One Hemisphere.** In Fig 4-13 (below), the *Great Circle* joining points *F* and *T* will always lie on the *Polar* side of the *Rhumb Line* joining them.

- **Small Latitude Difference and Large Longitude Difference.** When the difference of *Latitude* between *F* and *T* is small and the difference of *Longitude* large (ie a broadly East - West course), the difference between the two tracks is considerable.
- **Large Latitude Difference and Small Longitude Difference.** When the difference of *Latitude* between *F* and *T* is large and the difference of *Longitude* small (ie a broadly North - South course), the difference between the two tracks is small and is usually insignificant.

c. **Great Circles in Two Hemispheres.** In Fig 4-13 (below), as points *A* and *B* lie on opposite sides of the *Equator,* the *Rhumb Line* almost coincides with the *Great Circle*. The difference between the two tracks is small and is usually insignificant.


Meridian 180° W
Prime Meridian 0° (Greenwich)
Meridian 180° E
60° N
Rhumb Line
T
F
Greenwich
B
Equator
Rhumb Line
A
60° S
Any Great Circles through Prime Meridian (0°) and Equator (0°)
Meridian 180° W
Prime Meridian 0° (Greenwich)
Meridian 180° E

Fig 4-13. Great Circle Tracks on a Mercator Projection Chart

0426-0429. Spare.

SECTION 3 - TRANSVERSE MERCATOR PROJECTION FOR CHARTS

0430. Transverse Mercator Projection - Concept

The *Transverse Mercator Projection* (sometimes known as the *Gauss Conformal Projection*) is essentially a *Mercator Projection* with the 'cylinder' turned through 90˚; it is *Orthomorphic*. However, the resulting appearance of the *Graticule* is markedly different (see Fig 4-14 below and compare with Fig 4-2 / Fig 4-11). A list of *Transverse Mercator Projection*'s construction and uses is at Para 0414c, together with a list of its properties; an explanation of the mathematics for geographical / *Grid* conversions is at Appendix 4.


Increasingly curved Parallels and Meridians
Central Meridian (straight line)
Equator (straight line)

Fig 4-14. Global Application of the Transverse Mercator Projection

0431. Transverse Mercator Projection - Principles

a. **Central Meridian.** In the *Transverse Mercator Projection,* the line of contact with the cylindrical *Projection* surface is known as the *Central Meridian* and plots as a straight line; the *Equator* also plots as a straight line (see Fig 4-14 above and Fig 4-15 overleaf). All other *Meridians* and *Parallels of Latitude* plot as curves.

b. **Scale Expansion.** Adjacent *Meridians* (of *Longitude*) plot further apart as *Longitude* increases from the *Central Meridian*. This is analogous to the *Scale* expansion between *Parallels* with increasing *Latitude* in the *Mercator Projection.*

(0431) c. **Central Meridians and Zones of Longitude.** To minimise the effects of *Scale* expansion, a *Transverse Mercator Projection* chart is normally restricted to ±3˚ of *Longitude* from the *Central Meridian* (see Fig 4-15 below). Beyond these limits, a new chart must be constructed with a *Central Meridian* in a new *Zone* of *Longitude*.


Central Meridian (line of contact)
Increasingly curved Parallels and Meridians
Central Meridian (straight line)
Equator (straight line)
N
W
E
S
Cylindrical Projection Surface
N
W
E
S
Resulting Chart Graticule

Fig 4-15. Transverse Mercator Projection - Limited Longitude Coverage

d. **High Latitudes.** By restricting its use to a narrow band of *Longitude*, the accuracy constraints imposed by high *Latitude* working on *Mercator Projections* are overcome. Although it is possible to depict the *Polar* regions on the *Transverse Mercator Projection*, in practice, better *Projections* exist for coverage of these *Areas*.

e. **Properties and Uses.** The properties and uses of *Transverse Mercator Projection* charts are listed at Para 0414c.

f. **Universal Transverse Mercator (UTM) Grid.** Due to the *Meridians* (except the *Central Meridian*) and *Parallels of Latitude* (except the *Equator*) plotting as curves, a *Grid* with Eastings and Northings is needed for the rapid identification of positions. To exploit the properties of the *Transverse Mercator Projection* globally, the *Universal Transverse Mercator* (*UTM*) *Grid* has been devised with globally standardised *Central Meridians*. These standardised *Central Meridians* are spaced at 6˚ intervals based on initial *Central Meridians* of 3˚W and 3˚E (ie on either side of the *Prime* (*Greenwich*) *Meridian*). *Projections* for charts using the *UTM Grid* are constructed for the appropriate *Central Meridian*. See details at Para 0451.

g. **UK Transverse Mercator (UKTM) Grid.** Charts and maps (including Ordnance Survey maps) using the *British National Grid* are constructed on the *UK Transverse Mercator* (*UKTM*) *Projection* with a (non-standard) *Central Meridian* of 2˚W and *Grid Origin* 49˚N 2˚W. The *Grid* is then offset to give a *False Origin* located to the South and West of UK (see details at Para 0452).

0432-0439. Spare.

SECTION 4 - GNOMONIC PROJECTION FOR CHARTS

0440. Gnomonic Projection - Concept

An introduction to *Gnomonic Projection* is at Para 0414e / Fig 4-3b and an explanation of its application is at Para 0622. To establish the *Waypoints* for a *Great Circle* track, it is very helpful to show the *Great Circle* on a chart as a straight line. This also allows radio direction-finder *Bearings* to be plotted as straight lines, although this usage has almost completely disappeared.

a. **Gnomonic Projection - Construction.** The *Gnomonic Projection* achieves the representation of *Great Circles* as straight lines by projecting the Earth's surface from the Earth's centre onto the tangent plane (see Note 4-5 below). To minimise distortion, the tangent point is chosen to be at the centre of the *Area* to be shown on the chart.

b. **Gnomonic Projection - Example.** An example of a *Gnomonic Projection Graticule* is at Fig 4-16 (below). The tangent point has been placed on the *Equator* and at *Longitude* 0˚; the *Graticule* is symmetrical about the *Meridian* through this tangent point, which is independent of the *Longitude*. The *Longitude Scale* can thus be adjusted as required (eg *UKHO* Chart 5029).



Fig 4-16. Example Gnomonic Projection Graticule (*Similar to UKHO Chart 5029*)

Note 4-5. Gnomonic Projection - Type. *The Gnomonic Projection is a Zenithal Projection (from position 'B' at Para 0413, Fig 4-3a Example 5), and is based on a Sphere which represents the Earth. It is NOT a Spheroidal Projection.*

(0440) c. **Representation of Great Circles as Straight Lines.** A *Great Circle* is defined at Para 0110c as: "... the intersection of a *Spherical* surface and a plane which passes through the centre of the *Sphere*". As one plane will always cut another in a straight line, all *Great Circles* will appear on the chart as straight lines.

d. **Properties and Uses.** The properties and uses of *Gnomonic Projection* charts are listed at Para 0414e.

e. **Theory.** The mathematical theory of the *Gnomonic Projection* is at Appendix 4.

0441. Transfer of a Great Circle Track from a Gnonomic to a Mercator Projection Chart

a. **Transfer Procedure.** To transfer of a *Great Circle* track (eg *FT* in Fig 4-17), from a *Gnomonic* to a *Mercator* chart, note the *Latitude* / *Longitude* of convenient *Waypoints A, B, C* ...etc on the line *FT* and mark them on the *Mercator Projection* chart. This will produce a series of *Rhumb Lines*, closely approximating a curve. See also Para 0208e.


150°W
140°W
130°W
120°W
110°W
100°W
90°W
30°S
35°S
40°S
45°S
50°S
T
E
D
C
B
A
F
Great Circle Track
160°W
SOUTHERN HEMISPHERE GNONOMIC CHART
80°W
150°W
140°W
130°W
120°W
110°W
100°W
90°W
30°S
35°S
40°S
45°S
T
E
D
C
B
A
F
Direct Rhumb Line Track
Great Circle Track
SOUTHERN HEMISPHERE MERCATOR CHART

Fig 4-17. Great Circle Track on Gnomonic and Mercator Projection Charts (Southern Hemisphere Example)

(0441) b. **Adjusting Courses.** The *Rhumb Line* courses between transferred *Waypoints* may not be multiples of full (integer) degrees (see Fig 4-17 opposite). The *Waypoints* should thus be adjusted to approximate the *Great Circle* track, while achieving convenient whole-degree courses. If manual steering is intended (as opposed to auto-pilot) the track should ideally be adjusted to multiples of 5˚ (ie 295˚, 300˚ etc).

c. **Same and Opposite Sides of the Equator.** When *F* and *T* lie on the same side of the *Equator* (solid line at Fig 4-18 below), the procedure is as at Para 0441a opposite. When *F* and *T* lie on opposite sides of the *Equator* (eg *F* being North and *T* South in Fig 4-18 below), if the tangent point is on the *Equator* (eg *UKHO* Chart 5029), the same chart can be used (a *Gnomonic Projection* chart of both hemispheres is symmetrical about the *Equator)*. In practice, this is rarely necessary as in these case*s,* the *Rhumb Line* almost coincides with the *Great Circle*; the difference between the two tracks is small and is usually insignificant (see Para 0425c). However, if required to do so (see dashed lines at Fig 4-18 below), the following geometrical construction suffices:

- Mark the position of *T* as if it were in the Northern hemisphere.
- Join *F* to *K*, the point on the *Equator* which has *T*'s *Longitude*.
- Join *T* to *H*, the point on the *Equator* which has *F*'s *Longitude*.
- Drop a perpendicular *RQ* on the *Equator* from *R*, the point where *FK* cuts *TH*.
- Draw *FQ* and *QT*.
- Then *FQ* is the *Great Circle* track in the Northern hemisphere, and *QT* is the reflection of its continuation South of the *Equator*. Points on *QT* may therefore be treated as if they were in the Southern hemisphere.



Fig 4-18. Great Circle Track on One / Both Sides of Equator - Gnomonic Projection Chart

0442. Composite Tracks

A *Composite Track* may easily be constructed using a *Gnomonic Projection* chart (see Para 0441, previous pages). Fig 4-19 below shows three tracks - a *Rhumb Line*, a *Great Circle* track and a *Composite Track* - all on a *Mercator Projection* chart.

a. **Composite Track on a Gnomonic Projection Chart.** A *Composite Track* is formed by two *Great Circle* arcs joined at their *Vertices* by the '*Safe Parallel*' *of Latitude* (see Para 0209b / Fig 2-12). On a *Gnomonic Projection* chart, the two *Great Circle* tracks are shown as straight lines and the '*Safe Parallel*' *of Latitude* is shown as a curve (see single *Great Circle* track example at Fig 4-17 facing previous page) .

b. **Composite Track on a Mercator Projection Chart.** On a *Mercator Projection* chart, the appearance of *Composite Track* is the reverse of the *Gnomonic Projection* chart presentation. The two *Great Circle* tracks are shown as curves, and the '*Safe Parallel*' *of Latitude* is shown as a straight line (see Fig 4-19 below).

c. **Transferring Composite Track Waypoints.** *Waypoints* for the two separate *Great Circle* elements of the *Composite Track* may be transferred from a *Gnomonic Projection* chart to a *Mercator Projection* chart (as shown at Para 0441 / Fig 4-17 and Para 0208e / Fig 2-11).

d. **Calculation.** The calculation of the *Composite Track* is at Para 0522.


140° E
160° E
180°
160° W
140° W
120° W
100° W
80° W
60° W
40° S
50° S
60° S
70° S
80° S
F
T
A
B
Great Circle Arc (FA)
Safe Parallel (AB)
Great Circle Arc (BT)
RHUMB LINE TRACK
COMPOSITE TRACK
Vertex of Great Circle Arc (FA)
Vertex of Great Circle Arc (BT)
Safe Parallel
GREAT CIRCLE TRACK

Fig 4-19. Rhumb Line, Great Circle and Composite Track on a Mercator Chart

0443-0449. Spare.

SECTION 5 - GRIDS

0450. Grid Reference Systems - Concept

a. **Grids - Definition and Properties.** A *Grid* is a reference system of rectangular *Cartesian Coordinates* obtained when a *Projection* is applied to a part or all of the world. The *Grid* will have all the properties of the *Spheroid* and *Projection* used and may have some special ones peculiar to itself. Several *Grids*, all different, may be based on the same *Spheroid* and *Projection*.

b. **Grids and Geographical Graticules.** An example of a *Transverse Mercator Projection Grid* with a (geographical) *Graticule* superimposed is at Fig 4-20 below. A *Grid* equates to a large piece of graph paper, graduated in suitable *Grid* units North (Northings) and East (Eastings) from the *Grid Origin*. Distances West and South of the *Grid Origin* are given negative values of Eastings and Northings respectively, but this can be avoided by using a *False Origin*.



Fig 4-20. Generic Grid with Geographical Graticule Superimposed

c. **Plotting the Graticule on the Grid.** The intersections of *Meridians* (of *Longitude*) and *Parallels of Latitude* are converted into *Grid Eastings* and *Grid Northings*; these are then plotted as individual points on the *Grid* and joined by smooth curves to form the geographical *Graticule*. To simplify this conversion, a set of tables or a computer program may be created, based on the *Spheroid* and *Projection* used.

(0450) d. **Scale Factors.** At the *Grid Origin* (position *Grid* 0000 0000, or 50˚N 20˚W at Fig 4-20 previous page), the distortion in distance and direction is at a minimum. This distortion increases with distance from *Grid Origin* and can be represented by a *'Scale Factor'*, defined as:

Scale Factor = Grid Length ÷ Spheroidal Arc

The *Scale Factor* is applied to both Eastings and Northings. *Grid Length* and *Spheroidal Arc* are illustrated at at Fig 4-21 (below). *Scale Factors* for the *Universal Transverse Mercator Projection* (*UTM*) are at Fig 4-22 (below).


Central Meridian
(line of contact)
Grid Length
Spheroidal Arc
N
Grid Origin
W
E
S
Cylindrical Projection Surface
Equator
(straight line)
Scale Factor = Grid Length ÷ Spheroidal Arc

Fig 4-21. Grid Length, Spheroidal Arc & Scale Factor (Transverse Mercator Projection)



Fig 4-22. Scale Factors for Universal Transverse Mercator (UTM) Projection

(0450) e. **Grid Convergence and Grid Orientation.** On a *Transverse Mercator Projection* map / chart, the *Grid* does not always point North (see Fig 4-23 below); this also applies in principle to other *Grids* using other *Projections*. At any point on the *Grid*, the angle between the true *Meridian* (ie true North) and the *Grid North* line **(measured from True North),** is known as the *Grid Convergence* (*C*) in navigation and as *Grid Orientation* in gunnery. It varies as follows:

- **Transverse Mercator Projection.** On *Transverse Mercator Projection*, *Grid Convergence* increases with distance from the *Central Meridian*.
- **Polar Stereographic and Other Projections.** *Grid Convergence* varies with the *Projection* in use and can be as much as 180˚(eg *Polar Stereographic*).
- **Mercator Projection.** On *Mercator Projection* charts, *Grid Convergence* / *Grid Orientation* is zero everywhere (ie *Grid North always coincides with Meridians*). If a *Transverse Mercator Grid* is superimposed on a *Mercator Projection* chart, *Grid* distortions will occur away from the chart borders.

Part of the *Transverse Mercator Projection Grid* at Fig 4-20 containing the points *A* and *B*, is shown enlarged at Fig 4-23 below. AP_1 and BP are the *Meridians* through *A* and *B* respectively and they are both very slightly curved (see Fig 4-14). AX_1 and BX both define the direction of *Grid North* at positions *A* and *B* respectively.

C°, the *Grid Convergence* at *B* = angle PBX
C_1°, the *Grid Convergence* at *A* = angle P_1AX_1



Note. The Meridians BP and AP₁ are actually curved (see Fig 4-10), but on the Scale of this diagram, the curvature is imperceptible.

Fig 4-23. Transverse Mercator Projection Grid Convergence at ‘A’ and ‘B’ from Fig 4-20

f. **Calculating Grid Convergence and Grid Orientation.** On Military and Ordnance Survey (OS) maps, the difference between *True North* and *Grid North* is printed for specified positions - in the centre on Military Maps and in the corners on OS Maps. At any intermediate position, interpolation is required. Care must be taken when using Ordnance Survey Maps, as these show the difference of *True North* **from** *Grid North* (ie the opposite of the definition at Para 0450e above).

Example 4-3. If *Grid North* is 2˚ west of *True North* then *Grid Convergence* is 2˚ West.
Example 4-4. If *True North* is 2˚ east of *Grid North*, *Grid Convergence* is 2˚ West.

0451. Universal Transverse Mercator (UTM) Grid

The *Transverse Mercator Projection* was introduced at Paras 0430-0431 and was used to provide examples for the concept of *Grids* at Para 0450. The *Universal Transverse Mercator* (*UTM*) *Grid* is used extensively worldwide for military and civil maps. Detailed *UTM Grid* arrangements are contained in NATO 'STANAG 2211'(available in the public domain); the following sub-paragraphs contain a summary of this information.

a. **Scope of the UTM Grid - Zones of Longitude.** The *UTM Grid* is split into *UTM Zones* (or strips) of *Longitude* 6° wide (although there are a small number of NATO anomalies to this - see Para 0451d opposite). The *UTM Zones of Longitude* are numbered from 1 to 60, with *Zone 1* covering from 180° to 174° W (ie starting at the *International Date Line*), counting eastwards to *Zone 60* (174° E to 180°) Although 6° of *Longitude* wide, the geographical width of each *UTM Zone* varies with *Latitude* (ie at the *Equator* each *Zone* is 360 miles wide, reducing to 62 miles wide at 80° *Latitude).* A *UTM Zone* includes the West boundary but NOT the East boundary.

b. **Standardised Central Meridians.** Each *UTM Zone* is bisected by a *Central Meridian* (see Table 4-2 below). *UTM Grid Central Meridians* are spaced at 6° of *Longitude* intervals (except for some NATO anomalies - see Para 0451d opposite), with first / last *Central Meridians* at 177°W and177°E (ie on either side of the *International Date Line*); two of them will lie at 3°W and 3°E of the *Prime* (*Greenwich*) *Meridian*).

Table 4-2. Longitude, UTM Zones and Central Meridians

Longitude	180°	174°W	168°W	162°W	156°W	150°W	144°W	138°W	132°W	126°W	120°W	114°W	108°W	102°W	96°W	90°W	84°W
UTM Zone		**1**	**2**	**3**	**4**	**5**	**6**	**7**	**8**	**9**	**10**	**11**	**12**	**13**	**14**	**15**	**16**
Central Meridian		177° W	171° W	165° W	159° W	153° W	147° W	141° W	135° W	129° W	123° W	117° W	111° W	105° W	99° W	93° W	87° W
Longitude	84°W	78°W	72°W	66°W	60°W	54°W	48°W	42°W	36°W	30°W	24°W	18°W	12°W	6°W	0°	6°E	12°E
UTM Zone		**17**	**18**	**19**	**20**	**21**	**22**	**23**	**24**	**25**	**26**	**27**	**28**	**29**	**30**	**31**	**32**
Central Meridian		81° W	75° W	69° W	63° W	57° W	51° W	45° W	39° W	33° W	27° W	21° W	15° W	9° W	3° W	3° E	9° E
Longitude	12°E	18°E	24°E	30°E	36°E	42°E	48°E	54°E	60°E	66°E	72°E	78°E	84°E	90°E	96°E	102°E	108°E
UTM Zone		**33**	**34**	**35**	**36**	**37**	**38**	**39**	**40**	**41**	**42**	**43**	**44**	**45**	**46**	**47**	**48**
Central Meridian		15° E	21° E	27° E	33° E	39° E	45° E	51° E	57° E	63° E	69° E	75° E	81° E	87° E	93° E	99° E	105° E
Longitude	108°E	114°E	120°E	126°E	132°E	138°E	144°E	150°E	156°E	162°E	168°E	174°E	180°				
UTM Zone		**49**	**50**	**51**	**52**	**53**	**54**	**55**	**56**	**57**	**58**	**59**	**60**				
Central Meridian		111° E	117° E	123° E	129° E	135° E	141° E	147° E	153° E	159° E	165° E	171° E	177° E				

(0451) c. **Scope of the UTM Grid - Latitude Bands.** The *UTM Grid* covers *Latitude* 80°S to 84°N, and splits this *Area* into *Bands* of *Latitude* 8° high, except for the most Northerly *Band* (72°-84°N) which is 12° high. Each *(Latitude) Band* is given a letter, starting at 'C' in the Southern hemisphere through to 'X' in the Northern hemisphere, but omitting the letters 'I' and 'O' (see Table 4-3 below).

Table 4-3. Latitude and UTM Zones (*shown from South to North*)

Southern Hemisphere			**Northern Hemisphere**	
Letter	**Latitude Band**		**Letter**	**Latitude Band**
C	80°S-72°S		N	0°-8°N
D	72°S-64°S		P	8°N-16°N
E	64°S-56°S		Q	16°N-24°N
F	56°S-48°S		R	24°N-32°N
G	48°S-40°S		S	32°N-40°N
H	40°S-32°S		T	40°N-48°N
J	32°S-24°S		U	48°N-56°N
K	24°S-16°S		V	56°N-64°N
L	16°S-8°S		W	64°N-72N
M	8°S-0°		**X**	**72°N-84°N**

d. **NATO UTM Grid - Zone Anomalies.** NATO *UTM Grid* charting and mapping anomalies in the Northern hemisphere *Bands* 'V' and 'X' that do NOT comply with the normal convention for *UTM Zones* are at Tables 4-4a/b (below). These anomalies affect SW Norway, Denmark and the Svalbard Island between 56°N and 64°N (*Band* 'V'), and Norway between 72°N and 84°N (*Band* 'V', just south of the permanent pack ice line). NATO mapping in these *Area*s is based upon the following modified *UTM Zones*.

Table 4-4a. NATO UTM Grid - Band 'V'(56°N-64°N) - Zone Anomalies

UTM Zone	**Band Affected**	**Zone Limits (Longitude)**	**Central Meridian**
31	V (56°N - 64°N)	0° - 3°E	3°E
32	V (56°N - 64°N)	3°E - 12°E	9°E

Table 4-4b. NATO UTM Grid - Band 'X' (72°N-84°N) - Zone Anomalies

UTM Zone	**Band Affected**	**Zone Limits (Longitude)**	**Central Meridian**
32, 34, 36	X (72°N - 84°N)	Zones 32, 34, 36 not used	Not applicable
31	X (72°N - 84°N)	0° - 9°E	3°E
33	X (72°N - 84°N)	9°E - 21°E	15°E
35	X (72°N - 84°N)	21°E - 33°E	27°E
37	X (72°N - 84°N)	33°E - 42°E	39°E

e. **100,000 Metre Square Identifiers.** Two-letter identifiers are also provided to identify the 100,000 metre squares within a 6° *Zone* / 8° *Band.* These are not normally needed when using computerised *Grid* conversions (see Paras 0451g/i).

(0451) f. **UTM 'True' Grid Origin and 'False Origin.** The *UTM Grid Zone* number (see Para 0451a) and *Band* letter (see Para 0451c) may be combined to provide a single unique identifier for a *UTM Grid* 'block' (normally a 6˚ wide *Zone* of *Longitude* and 8˚ high *Band* of *Latitude*). The *Zone* number always precedes the *Band* letter (eg '30U').

- **'True' Grid Origin.** Each *Zone / Band* 'block' (eg '30U') has a 'True' *Grid Origin* at the intersection of its *Central Meridian* (*Longitude*) and the *Equator*. If a *Grid* value of zero was assigned to the 'Eastings' and 'Northings' of the 'True' *Grid Origin*, then *Grid* 'Eastings' for positions West of the *Central Meridian* would always have negative values, and in the Southern hemisphere, all *Grid* 'Northings' would have negative values.

- **Grid 'False Origin'.** To overcome negative values, each *Zone / Band* 'block' (eg '30U') is assigned a *Grid* '*False Origin*'. To achieve this, a '*False Easting*' and '*False Northing*' are assigned, but the '*False Northing*' is different in the Northern and Southern hemispheres (see Para 0451g below).

g. **Calculating Global UTM Grid References.** The method of calculating *UTM Grid* references from the *False Origin* (see Fig 4-24 below) is as follows:

- **Both Hemispheres - Eastings.** In both hemispheres, a *False Origin* is placed 500,000m West of the *Central Meridian* (which thus has a '*False Easting*' of 500,000m East). *UTM Grid Easting*s are counted eastwards across *Zone*, although they do not start at zero due to *Zone* width. At *Zone* boundaries, Eastings are re-set for the *Central Meridian* / *False Origin* of the new *Zone*.

- **Northern Hemisphere - Northings.** In the Northern hemisphere, the '*False Origin*' is on the *Equator* (ie *'False Northings'* are zero). *UTM Grid Northings* are counted northwards (irrespective of *Band* boundaries) from the *False Origin* at the *Equator; UTM Grid* *Northings* increase as *Latitude* increases **away** from the *Equator* and *False Origin* (eg 16˚N 3˚E has a Northing of 1,768,935m; 80˚N 3˚E has a Northing of 8,881,585m).

- **Southern Hemisphere - Northings.** In the Southern hemisphere, the '*False Origin*' is placed 10,000,000m South of the *Equator*, close to the *South Pole* (ie the *Equator* has a *'False Northing'* of 10,000,000m North). *UTM Grid Northings* are counted northwards (irrespective of *Band* boundaries) from the *False Origin*. *UTM Grid* *Northings* decrease as *Latitude* (South) increases **away** from the *Equator* but **towards** the *False Origin* (eg 16˚S 3˚E has a *Grid Northing* of 8,231,064m; 80˚S 3˚E has a *Grid Northing* of 1,118,416m).



Fig 4-24. UTMG True and False Grid Origins (N & S Hemispheres)

(0451) h. **Local UTM Grid References (4, 6 and 8 Figures).** Although the *Grid Easting* and *Northing* coordinates are measured in metres from the *False Origin*, when using maps, the user normally requires only the 'local' 6-Figure or 8-Figure *Grid* reference. On most maps and charts the smallest *Grid* division shown is the 1 kilometre (1000 metres) square (see Fig 4-25 below); however, so that there can be no doubt, the legend of the map or chart will normally specify the graduations shown.

- **Grid Coordinates.** To specify *Grid* coordinates of a point, the *Eastings* (measured from the western edge of the graduations) are stated first, followed by the *Northings* (measured from the southern edge of the graduations).
- **4-Figure Grid References.** Using the 1 kilometre square graduations, a 4-figure grid reference (eg '0588' at Fig 4-25 below) will specify a position to an accuracy of 1000 metres; it is in fact an 'area' rather than a 'point'.
- **6-Figure Grid References.** By estimating tenths in the 1 kilometre square graduations, a 6-figure grid reference (eg 'White Head Light' at *Grid* '040874' in Fig 4-25) will specify a position to an accuracy of 100 metres.
- **8-Figure Grid References.** By estimating hundredths in the 1 kilometre square graduations, an 8-figure grid reference (eg 'White Head Light' at *Grid* '03988743' in Fig 4-25 below) will specify a position to an accuracy of 10 metres. This level of accuracy is difficult to measure without a large *Scale* map or chart, but can be obtained by observation on the ground with a hand-held *DGPS* receiver, or by computer transformation of accurate *Latitude* and *Longitude* positions (see Para 0451i overleaf).


'White Head Light'
6 and 8 Figure Grid References
'040874' (100m accuracy)
'03988743' (10m accuracy)
'Area'
4-Figure Grid Reference
'0588' (1000m accuracy)
Sparrow Rock
(just dries)
An t-Aigeach
Eilean Cluimhrig(15)
Freisgill Head
Freisgill
Rispond
Loch na Ra fin
262
Cnoc a' Bhaid-bheithe
A' Creachan
Sgeir a Bhuic
Rubh' a' Mhuin
184
Cnoc nan Gobhar
Rubha Ruadh
White Head
Fl.WR.3s20m13/12M
Ben Heilam
178
R. Hope
Fàir Dhubh
03
04
05
06
07
08
09
10
91
90
89
88
87
41'
40'
39'
38'
37'
36'
35'
34'
33'
32'

Fig 4-25. UTM - 4, 6 and 8 Figure Grid References

Note 4-6. *The UTM Grid in Fig 4-25 is clearly not aligned exactly North-South, but is offset by the Grid Convergence / Grid Orientation due to this chart showing an Area some distance from the Central Meridian (see details at Para 0450e).*

(0451) i. **UTM Grid Conversions - 'Silent' Figures.** When converting from *Latitude / Longitude* to *UTM Grid* using computerised navigation systems (eg *ECDIS* or *WECDIS*) or even navaids (eg *DGPS / GPS* receivers), the full *Grid* coordinates to the nearest hundredth of a metre are normally given. The two-letter identifiers used to identify the 100,000 metre squares are normally replaced by figures (see Paras 0451e/g). This generates potentially confusing additional figures in addition to the 6 or 8 figure *Grid* references at Para 0451h (previous page). When converting from *UTM Grid* to *Latitude / Longitude*, to avoid ambiguity, care must be taken use the full *UTM Grid* reference and to specify the *Central Meridian* and hemisphere.

- **White Head Light Example.** In the case of the example of White Head Light (58° 31.01'N 004° 38.90'W [*WGS 84*]) at Para 0451h / Fig 4-25 (previous page), the full *UTM Grid* coordinates to the nearest hundredth of a metre (as provided by *WECDIS*) are: 403982.17 (Eastings), 6487431.13 (Northings).

- **'Silent' Figures - 'The Key'.** The key to decoding these coordinates is that the figures to the left of the decimal point (in order to the left) are: metres / tens of metres / hundreds of metres / thousands of metres etc.

- **6-Figure Grid References.** Thus, if a 6-figure *Grid* reference (ie accurate to 100 metres) is needed, ignore the first two figures to the left of the decimal point (ie metres / tens of metres), take the next three figures (rounded to the nearest significant figure) and ignore the figures further left to obtain *Grid* reference '040874' (see Table 4-5a below - significant figures underlined):

Table 4-5a. Decode of Full Grid Reference to 6-Figure Grid Reference

	Full Grid Reference (1/100th metre accuracy)	6-Figure Grid Reference (100 metre accuracy)
Eastings	403982.17	040 (rounded up)
Northings	6487431.13	874 (rounded down)

- **8-Figure Grid References.** Thus, if an 8-figure *Grid* reference (ie accurate to 10 metres) is needed, ignore the first figure to the left of the decimal point (ie metres), take the next four figures (rounded to the nearest significant figure) and ignore the figures further left to obtain *Grid* reference '03988743'(see Table 4-5b below - significant figures underlined):

Table 4-5b. Decode of Full Grid Reference to 8-Figure Grid Reference

	Full Grid Reference (1/100th metre accuracy)	8-Figure Grid Reference (10 metre accuracy)
Eastings	403982.17	0398 (rounded down)
Northings	6487431.13	8743 (rounded down)

- **'Silent' Figures on the Map / Chart.** The map or chart will normally show the 'silent' figures in small print at the edge of the map / chart where major *Grid* intersections occur. Some reference to these 'silent' figures may also be mentioned in the map / chart legend.

0452. British (Ordnance Survey) National Grid

The *British National Grid* is used for Ordnance Survey mapping of UK; it differs from *UTM* only in that it has a non-standard *Central Meridian* / *Grid Origin*, a non-standard *False Origin* and the *UK Transverse Mercator* (*UKTM*) *Projection* used is referenced to the Airy *Spheroid* / OSGB 36 *Datum*, rather than to the *WGS 84 Spheroid / Datum*.

a. **UTM Grid Covering UK.** The *UTM Grid* covering UK has an inconvenient change of *Zone* on either side of the *Prime* (*Greenwich*) *Meridian*, which straddles UK. To the West, *Zone* '30U' has a *Central Meridian* of 3˚W and covers from 6˚W-0˚, while to the East, *Zone* '31U' has a *Central Meridian* of 3˚E and covers from 0˚-6˚E (see Fig 4-26 below). Thus to use *UTM Grid* in UK would mean using coordinate systems from several different *Zones*.

b. **British National Grid.** To overcome this difficulty, the *British National Grid* uses a *Grid Origin* of 49˚N 002˚ W with a non-standard *Central Meridian* of 2˚W. Non-standard *False Eastings* of 400,000 metres and *False Northings* of 100,000 metres are applied to give a *False Origin* located to the South and West of UK (see Fig 4-27 overleaf). This choice allows all of UK (except Northern Ireland) to be covered by a single (non-standard) *Zone* with positive *Grid* coordinates. Unlike *UTMG Zones* which are normally limited to a width of 6˚(*Longitude)*, the *British National Grid* is approximately 12½˚ wide at 61˚N and 10¾˚wide at 52˚N, thus leading to substantial *Grid Convergence* at the extremities. Due to national boundaries, the overall shape of the *British National Grid* is not entirely regular (see Fig 4-27 overleaf).

c. **Spheroid and Projection.** For historical reasons, the *British National Grid* is based on the *UK Transverse Mercator* (*UKTM*) *Projection* referenced to the Airy *Spheroid* / OSGB 36 *Datum*. Particular care must be taken when transferring *British National Grid* coordinates to *Latitude / Longitude* if a different *Spheroid* (eg *WGS 84*) is involved.


0°
UTM Grid Zones 30U / 31U Boundary (0°)
9½°W
3°E
Width of British National Grid at Widest Point (North)
Width of British National Grid at Widest Point (South)
PART OF UTMG ZONE 30U
PART OF UTMG ZONE 31U
Note: UTMG Convergences are exaggerated for clarity, thus outer (E/W) UTMG Zone boundaries are not shown.
7¾°W
3°E
0°

Fig 4-26. UTM Grid Zones Covering UK and British National Grid Widths

(0452) d. **Simplified Diagram of British National Grid.** A simplified diagram of the *British National Grid* (source STANAG 2211) is at Fig 4-27 below.


Kilometres
Eastings
0
100
200
300
400
500
600
700
800
1300
1200
1100
1000
900
800
700
600
500
400
300
200
100
0
Excluded
Excluded
False Origin of
British National Grid
True Origin of
British National Grid
49°N 2°W
Co-ordinates of True Origin
+400,000 metres E
–100,000 metres N

Fig 4-27. Simplified Diagram of British National Grid (*source STANAG 2211)*

0453. Other National Grids

For the same reasons that the *British National Grid* differs from *UTM Grid*, certain other nations have dedicated *Grids* with non-standard *Central Meridians*, *False Origins and Spheroids*; these include the *Irish Grid*, the *Nord Maroc Grid*, the *Sud Maroc Grid*, the *Nord Algerie Grid*, the *Sud Algerie Grid*, the *Nord Tunisie Grid* and the *Sud Tunisie Grid*. Details of the above *Grids* are contained in NATO STANAG 2211 (available in the public domain).

0454. Grivation

The term '*Grivation*' is occasionally used for the combination of (*Grid*) *Convergence* and *Magnetic Variation*, and is the angular difference between *Magnetic North* and *Grid North*.

CHAPTER 5

THE SAILINGS (2) - MORE COMPLEX CALCULATIONS

CONTENTS

Para

0501. Scope of Chapter

SECTION 1 - SPHERICAL MERCATOR SAILING

0510. Mercator Sailing and Meridional Parts Overviews
0511. Spherical Rhumb Line Course and Distance From Meridional Parts

SECTION 2 - SPHERICAL GREAT CIRCLE COMPOSITE TRACK / VERTEX

0520. Finding the Position of the Vertex of a Great Circle
0521. Calculating Great Circle Waypoints for a Mercator Chart
0522. Calculating the Composite Track

SECTION 3 - SPHEROIDAL RHUMB LINE SAILING

0530. Rhumb Line Methods and Accuracies
0531. Calculating the Spheroidal Rhumb Line Course and Distance

SECTION 4 - SPHEROIDAL GEODESIC (GREAT CIRCLE) SAILING

0540. Spheroidal Geodesic (Great Circle) Terminology, Methods and Accuracies
0541. Spheroidal Geodesic - Parametric Latitude (Andoyer-Lambert) Method

SECTION 5 - COMPARISON AND CHOICE OF METHODS

0550. Summary of Methods of Calculation Available
0551. Choice of Methods

INTENTIONALLY BLANK

CHAPTER 5

THE SAILINGS (2) - MORE COMPLEX CALCULATIONS

0501. Scope of Chapter

a. **Sailings (1).** Chapter 2 introduced *'Sailings* (1)' (ie *Parallel Sailing, Plane Sailing, Mean Latitude Sailing / Corrected Mean Latitude Sailing, Traverse Sailing* and brief overviews of *Mercator Sailing* and *Spherical / Spheroidal Great Circle Sailing*).

b. **Sailings (2).** Chapter 5 deals with the more complex calculations of '*Sailings* (2)', consisting of:

- *Spherical Mercator Sailing*.
- *Spherical Great Circle Composite Track* and *Vertex.*
- *Spheroidal Rhumb Line Sailing*.
- *Spheroidal Great Circle Sailing*.

0502-0509. Spare

SECTION 1 - SPHERICAL MERCATOR SAILING

0510. Mercator Sailing and Meridional Parts Overviews

A very brief overview of *Mercator Sailing* is given at Para 0207; a detailed explanation of *Meridional Parts* is at Para 0422.

a. **Meridional Parts.** The number of *Meridional Parts* on a *Meridian* of the *Sphere* for any *Latitude* ϕ is established at Para 0422e, as follows:

$$Meridional\ Parts = 7915.7045 \log_{10} \tan\left(45° + \frac{\phi°}{2}\right) \qquad \text{. . . (formula 4.1)}$$

b. **Difference of Meridional Parts (DMP).** The term '*Difference of Meridional Parts* (*DMP*)' is explained at Para 0422d; an extract is repeated below for the convenience of readers:

> **(Extract fromPara 0422d):** Where the two positions are both remote from the *Equator*, their relative position may be determined by the difference between their individual *Meridional Parts*, which gives the number of *Longitude Units* in the length of a *Meridian* between the two *Parallels of Latitude*. **This length is usually referred to as the '*Difference of Meridional Parts'* and written as '*DMP*'.**

0511. Spherical Rhumb Line Course and Distance From Meridional Parts

Spherical Mercator Sailing (*Rhumb Line) Course* and *Distance* may be found by *Spherical Meridional Parts* calculations, although in different circumstances the appropriate or inappropriate choice of a particular formula can affect the accuracy of the calculation.

a. **Difference of Meridional Parts.** From the explanation at Para 0422d (repeated at Para 0510b previous page), the number of *Meridional Parts* in the length *MT* of a *Meridian* on a *Mercator Projection* chart between the *Parallels of Latitude* through two points *F* and *T* (see Figs 5-1a/b below) is the '*Difference of Meridional Parts* (*DMP*)'.

b. **Course by Meridional Parts.** From Para 0511a (above), it follows that:

- **Same Hemisphere.** If *F* and *T* are on the same side of the *Equator* (see Fig 5-1a below), then:

$$\text{Meridional Parts } TF = \text{ Meridional Parts } T \ \underline{\text{minus}} \ \text{Meridional Parts } F \qquad \ldots \mathbf{5.1}$$

- **Opposite Hemispheres.** If *F* and *T* are on opposite sides of the *Equator* (see Fig 5-1b below), then:

$$\text{Meridional Parts } TF = \text{Meridional Parts } T \ \underline{\text{plus}} \ \text{Meridional Parts } F \qquad \ldots \mathbf{5.2}$$

- **Course.** From the triangle *FTM* (see Fig 5-1a/b below), it follows:

$$\tan Course = \frac{FM}{MT} = \frac{d.long \ \ (E / W)}{DMP \ \ (N / S)} \qquad \ldots \mathbf{5.3}$$


T
Distance
DMP
Meridional Part T
F
d.long
M
Meriodinal Part F
EQUATOR
Fig 5-1a (Same Hemisphere)
F
d.long
M
Meriodinal Part F
EQUATOR
Distance
Meriodinal Part T
DMP
T
Fig 5-1b (Opposite Hemispheres)

Figs 5-1a/b. Difference of Meridional Parts - Same and Opposite Hemispheres

(0511) c. **Course by Departure.** An alternative method for finding the *Course* is by the *Departure* method (see Para 0204a):

$$\tan Course = \frac{Departure}{d.lat} \qquad \text{. . . (formula 2.4)}$$

d. **Comparison of Methods for Finding Course.** The relation between the two methods of finding the *Course* is shown at Fig 5-2 (below). The use of the *Departure* formula (2.4) involves finding a *Corrected Mean Latitude* (see Paras 0205b/c), if an error in the *Course* is to be avoided. For this reason, the *DMP* formula is preferred.

- **Course by Meridional Parts.** In the *Meridional Parts* method, *d.lat* (FM_1) is stretched into *DMP* (*FM*) and *d.long* (*MT*) remains unchanged, ie:

$$\tan Course = \frac{d.long}{DMP} \qquad \text{. . . (formula 5.3)}$$

- **Course by Departure.** In the *Departure* method, *d.lat* (FM_1) remains unchanged and *d.long* (*MT*) is compressed into *Departure* (MT_1), ie:

$$\tan Course = \frac{Departure}{d.lat} \qquad \text{. . . (formula 2.4)}$$



Fig 5-2. Comparison of Methods for Finding Course

e. **Finding Rhumb Line Distance - Method 1.** The *Course* angle obtained by formula (5.3) is exact, irrespective of the length of *Distance* (*FT*). The *Rhumb Line Distance*, as in *Plane Sailing*, is obtained from formula (2.3) re-arranged as follows:

$$Distance = d.lat \sec Course \qquad \text{. . . } \mathbf{5.4}$$

Formula (5.4) is quite satisfactory in use for *Course* angles approaching 90. There is, however, a fundamental weakness in this formula at *Course* angles between 60˚ and 90˚ because (see Note 2-1 at Para 0204a), small errors in the *Course* introduce increasingly large errors in the *Distance*. When using tables in these circumstances it is preferable to use the formula in Method 2 (see Para 0511f overleaf). See also Note 5-1 overleaf.

(0511) f. **Finding Rhumb Line Distance - Method 2.** Instead of Method 1 (Para 0511e previous page), the *Rhumb Line Distance* may also be obtained by formulae (5.5) or (5.6), particularly when the *Course* angle is between 60˚ and 90˚.

either: $$\text{Distance} = \text{d.lat}\ \frac{\text{d.long}}{\text{DMP}}\ \text{cosec Course} \qquad \ldots \mathbf{5.5}$$

or: $$\text{Distance} = \text{Departure Cosec Course} \qquad \ldots \mathbf{5.6}$$

Note 5-1. *The Rhumb Line Distance may also be found from formula (2.7) using a Corrected Mean Latitude, but as formula (2.7) can be manipulated into the Meridional Parts formula (5.3) by use of formulae (2.5) and (2.4), this will always give the same results for Course (and thence Distance) as formula (5.3).*

Example 5-1: Rhumb Line Course and Distance (Spherical Mercator Sailing)

What is the *Rhumb Line Course* and *Distance* by *Mercator Sailing* from F (45˚N, 140˚E) to T (65˚N, 110˚W) (the same positions as in the *Great Circle* Example 2-6 at Para 0211)?

$$\text{d.long (FT)} = 110^\circ\text{E} = 6600'\text{E}$$
$$\text{d.lat (FT)} = 20^\circ\text{N} = 1200'\text{N}$$

- **DMP (FT):**

$$\text{Meriodinal Parts T} = 7915.7045 \log_{10} \tan\left(45^\circ + \frac{65^\circ}{2}\right) = 5178.81 \qquad \ldots \text{(formula 4.1)}$$
$$\text{Meriodinal Parts F} = 7915.7045 \log_{10} \tan\left(45^\circ + \frac{45^\circ}{2}\right) = 3029.94$$
$$\text{DMP (FT)} = 2148.87\text{N}$$

- **Course:**

$$\tan \text{Course} = \frac{\text{d.long(E)}}{\text{DMP(N)}} \qquad \ldots \text{(formula 5.3)}$$
$$= \frac{6600}{2148.87}$$
$$= 3.0713817$$
$$\text{Course} = \text{N}71.965457^\circ = 072^\circ$$

- **Distance:**

Either:

$$\text{Distance} = \text{d.lat sec Course} \qquad \ldots \text{(formula 5.4)}$$
$$= 1200' \sec 71.965457^\circ = 3876'.09$$

Or:

$$\text{Distance} = \text{d.lat}\ \frac{\text{d.long}}{\text{DMP}}\ \text{cosec Course} \qquad \ldots \text{(formula 5.5)}$$
$$= 1200' \times 3.0713817\ \text{Cosec}\ 71.965457^\circ = 3876.09'$$

0512-0519. Spare

SECTION 2 - SPHERICAL GREAT CIRCLE COMPOSITE TRACK / VERTEX

0520. Finding the Position of the Vertex of a Great Circle

The concepts of the *Vertex* and the *Composite Track* were introduced at Para 0209. The calculations of the *Vertex* and the *Composite Track* are given below.

a. **The Vertex.** The point at which a *Great Circle* most nearly approaches the *Pole* is called its *Vertex* - shown as '*V*' at Fig 5-3 (below). If a series of *Parallels of Latitude* are drawn, one *Parallel of Latitude* will touch the *Great Circle FT* at *V*. As the *Great Circle* and the *Parallel of Latitude* touch at *V* and the *Meridian PV* cuts the *Parallel of Latitude* at right angles, it also cuts the *Great Circle* at right angles; thus the *Spherical Triangles PFV* and *PTV* are both right-angled at V (ie angles *PVF* and *PVT* = 90˚) and can be easily solved mathematically.



Fig 5-3. The Vertex (V) of a Great Circle (FT)

b. **Location of the Vertex.** The *Vertex* may NOT be located between *F* and *T*. Only one plane cuts the *Sphere* to create a *Great Circle* joining *F* and *T*. Depending on the positions of *F* and *T*, the *Vertex* (ie point at which it most nearly approaches the *Pole)* may be beyond *F* or *T* (eg if the final *Course* angle is < 90˚, the *Vertex* lies beyond *T*).

c. **Longitude of the Vertex.** The *Vertex Longitude* can be found from the formula:

$$\tan d.long\ VT = \tan Lat\ F \cot Lat\ T \operatorname{cosec} d.long\ FT - \cot d.long\ FT \qquad \ldots \mathbf{5.8}$$

d. **Latitude of the Vertex.** The *Vertex Latitude* may be found from the formula:

$$\cot Lat\ V = \cot Lat\ F \cos d.long\ FV \qquad \ldots \mathbf{5.9}$$

e. **Napier's Rules.** Alternatively, if the initial *Course* has been found, the position of *Vertex V* can be obtained from *Napier's Rules* (see Appendix 2 Para 10). Thus:

$$\cos Lat\ V = \cos Lat\ F \sin initial\ Course \qquad \ldots \mathbf{5.10}$$

$$\tan d.long\ FV = \operatorname{cosec} Lat\ F \cot initial\ Course \qquad \ldots \mathbf{5.11}$$

f. **Example.** An illustration of a *Vertex* calculation is at Example 5-2 (overleaf).

(0520f continued)

Example 5-2: Calculating the Position of the Vertex (Spherical Great Circle Sailing)

On the *Spherical Great Circle* F (45°N, 140°E) to T (65°N, 110°W) in Example 2-6, find the *Vertex* position.

From Napier's Rules:

- **Latitude of Vertex:**

$$\cos \text{Lat Vertex} = \cos \text{Lat F} \sin \text{initial Course} \qquad \ldots \text{(formula 5.10)}$$

$$= \cos \text{Lat } 45^\circ \sin 28.122305^\circ$$

$$\text{Lat Vertex} = 70.530896^\circ\text{N} = 70^\circ 31'.85\text{N}$$

- **Longitude of Vertex:**

$$\tan \text{d.long FV} = \text{cosec Lat F} \cot \text{initial Course} \qquad \ldots \text{(formula 5.11)}$$

$$= \text{cosec } 45^\circ \cot 28.122305^\circ$$

$$\text{d.long FV} = 69.297735^\circ\text{E} = 69^\circ 17'.86\text{E}$$

$$\text{Long Vertex} = 150^\circ.70227\text{W} = 150^\circ 42'.14\text{W}$$

0521. Calculating Great Circle Waypoints for a Mercator Chart

The simplest method of calculating *Great Circle Waypoints* for a *Mercator Projection* chart is to select and transfer them from a *Gnomonic Projection* chart (see Para 0441). However, if a *Gnomonic Projection* chart is not available, the *Waypoints* can be calculated with reference to the *Vertex* or to an intermediate *Meridian*. The latter method is used by HM Nautical Almanac Office's *NAVPAC* program (available from *UKHO* as DP330; see details at Paras 0210a / 0551a).

a. **Vertex Method.** There is no simple formula for finding where a *Great Circle* track cuts *Parallels of Latitude* without knowing the position of the *Vertex*. The '*Vertex* Method' is as follows

- **Vertex.** Find the position of the *Vertex V* [formulae (5.10), (5.11)].
- **Waypoints.** *Waypoints* are calculated from the following formula, where *G* is any position on the *Great Circle* joining *F* and *T* (see Fig 5-4 opposite). The results may be tabulated (see Example 5-3 opposite).

Either: $$\cos \text{d.long VG} = \cot \text{Lat V} \tan \text{Lat G} \qquad \ldots \mathbf{5.12}$$

Or: $$\tan \text{Lat G} = \tan \text{Lat V} \cos \text{d.long VG} \qquad \ldots \mathbf{5.13}$$

b. **Meridian Method.** The '*Meridian* Method' may be used to find the *Latitude* where a *Great Circle* track cuts an intermediate *Meridian*, without the need to find the position of the *Vertex*. However, if a number of intersections are required, it is simpler to use the *Vertex* method at Para 0521a (above).

$$\tan \text{Lat G} = \frac{\tan \text{Lat F} \sin \text{d.long GT} + \tan \text{Lat T} \sin \text{d.long FG}}{\sin \text{d.long FT}} \qquad \ldots \mathbf{5.14}$$

c. **Plotting.** Once calculated, the *Waypoints* may be plotted on the *Mercator Projection* chart and joined by means of a series of *Rhumb Lines* (see Para 0441b).

(0521 continued)



Fig 5-4. Calculating Great Circle Waypoints (‘G’, etc) for a Mercator Chart

Example 5-3: Calculating Spherical Great Circle Waypoints for a Mercator Chart

Find the *Latitude*s where the *Spherical Great Circle* track F (45˚N, 140˚E) to T (65˚N, 110˚W) used in Example 5-2 (opposite), cuts the *Meridian*s of 150˚E, 160˚E, 170˚E, 180˚, 170˚W, 160˚W, 150˚W, 140˚W, 130˚W, 120˚W. (F (45˚N, 140˚E), T (65˚N, 110˚W).)

- **Calculation and Tabulation.** Using formula (5.13) for a series of *Latitudes*, a Table / Tables (similar to Tables 5-1a/b, below) may be prepared.

Table 5-1a. Table of Calculated Great Circle Waypoints for a Mercator Chart

Longitude	150˚E	160˚E	170˚E	180˚	170˚W
VG (d.long)	59˚.298	49˚.298	39˚.298	29˚.298	19˚.298
Latitude *D*	55˚18'.1	61˚32'.3	65˚26'.9	67˚56'.1	69˚28'.0

Table 5-1b. Table of Calculated Great Circle Waypoints for a Mercator Chart

Longitude	160˚W	150˚W	140˚W	130˚W	120˚W
VG (d.long)	9˚.298	0˚.702	10˚.702	20˚.702	30˚.702
Latitude *D*	70˚17'.5	70˚31'.8	70˚12'.8	69˚17'.9	67˚39'.0

0522. Calculating the Composite Track

The concepts and definitions for the *Composite Track* were explained at Para 0209, to which reference should be made before proceeding further. In summary, the *Composite Track* is formed by two *Great Circle* arcs joined at their *Vertices* by the '*Safe Parallel*' *of Latitude*. It is normally used to avoid high *Latitude*s due to the danger of ice.

a. **High Latitude Situation.** Fig 5-5 (below) illustrates a high *Latitude* situation, showing:

- The *Safe Parallel [of Latitude]* (*LABM*).
- The *Great Circle* (*FLVMT*) joining *F* and *T*.
- The *Composite Track* (*FABT*) in which *FA* and *BT* are *Great Circle* arcs touching the *Safe Parallel* at *A* and *B*.
- *AB* is part of the *Safe Parallel* and comprises part of the *Composite Track*.


P
DANGER AREA
(ABOVE SAFE PARALLEL)
90°
V
(Vertex)
Great Circle Track
M
L
90°
90°
A
B
T
Safe Parallel
Composite Track:
Great Circle Arc FA,
with its Vertex touching
the 'Safe Parallel' at A
Composite Track:
Safe Parallel Arc AB
Composite Track:
Great Circle Arc BT,
with its Vertex touching
the 'Safe Parallel' at B
F

Fig 5-5. High Latitude Situation - The Composite Track (*Copy of Fig 2-12*)

b. **Calculation.** The positions of *A* and *B* are quickly found because the *Course* angles at *A* and *B* are right angles (*Meridians* and *Parallels of Latitude* intersect at 90˚). Also, along the *Parallel of Latitude AB,* the ship is steering a *Course* of 090˚/270˚.

- If the *Latitude* of the *Safe Parallel* (*LABM*) is ϕ :

$$\mathrm{AB} = d.long \cos \phi \qquad ..\ \mathbf{5.15a}$$

- Using the formulae for a *Spherical* right-angled triangle:

$$\cos PF = \cos PA \cos FA$$

$$\cos FA = \frac{\cos PF}{\cos PA} \qquad ...\ \mathbf{5.15}$$

$$\sin FPA = \frac{\sin FA}{\sin PF} \qquad ...\ \mathbf{5.16}$$

- Formula (5.15) gives the length of the *Great Circle* arc *FA*. Formula (5.16) gives the *d.long* between *F* and *A* by which the position of *A* may be found. *BT* may also be found in a similar manner.

(0522 continued)

Example 5-4: Calculating Spherical Composite Track

Find the *Spherical Composite Track Distance* F (45˚N, 140˚E) to T (65˚N, 110˚W), when a *Safe Parallel* of *Latitude* 67˚N is applied (see Fig 5-6 below). F and T are the same coordinates as in Examples 5-2 and 5-3.

- **Total Distance.** The total *Composite Track Distance* = FA + AB + BT
- **Distance FA:**

$$\cos FA = \frac{\cos PF}{\cos PA} = \frac{\cos 45°}{\cos 23°} \quad \text{. . . (formula 5.15)}$$

$$FA = 39.809911° = 39°48'.6 = 2388.6 \text{ miles}$$

- **Distance BT:**

$$\cos BT = \frac{\cos PT}{\cos PB} \quad \text{. . . (formula 5.15)}$$

$$BT = 10.075896° = 10°04'.6 = 604.6 \text{ miles}$$

- **Longitude A:**

$$\sin FPA = \frac{\sin FA}{\sin PF} = \frac{\sin 39.809911°}{\sin 45°} \quad \text{. . . (formula 5.16)}$$

$$FPA = 64.882575° = 64°53'E$$

Longitude of A is thus: 180 + 40 - 64°53' = 155°07'W.

- **Longitude B:**

$$\sin TPB = \frac{\sin TB}{\sin PT} = \frac{\sin 10°.075896}{\sin 25°} \quad \text{. . . (formula 5.16)}$$

$$TPB = 24.454656° = 24°27'.3\ W$$

Longitude of B is thus: 110 + 24°27'.3 = 134°27'.3 W.

- **Distance AB:**

$$FPT = 40° + 70° = 110°$$

Latitude of A and B is 67˚N (*Safe Parallel of Latitude*)

$$\begin{aligned} AB &= APB \cos 67° \quad \text{. . .(formula 5.15a)} \\ &= [FPT - (FPA + TPB)] \cos 67° \\ &= 20.662769° \cos 67° \\ &= 8.0735870° = 484.4 \text{ miles} \end{aligned}$$

- **Composite Track Distance FABT:**

$$FABT = 2388.6 + 604.6 + 484.4 \text{ miles} = 3477.6 \text{ miles}$$

- **Courses from F to A and B to T:** Course from F to A and B to T may be found by any of the methods listed at Para 0210.

0523-0529. Spare.

SECTION 3 - SPHEROIDAL RHUMB LINE SAILING

0530. Rhumb Line Methods and Accuracies

Provided that the *Meridional Parts* and the length of the *Meridional Arc* (eg *Arc 'EM'* in Fig 5-6 below), between the *Latitude*s of the two places are computed for the *Spheroid*, an accurate *Rhumb Line Course* and *Distance* may be calculated for any *Spheroid*. If *Spherical* formulae (ie Paras 0204-0205 and 0511) are used without correction for the *Spheroid*, the *Rhumb Line* solution will be inaccurate (up to 0.5% error), depending on *Course*, *Distance* and *Latitude*.

0531. Calculating the Spheroidal Rhumb Line Course and Distance

a. **Meridional Parts for the Spheroid.** *Meridional Parts* for the *Clarke Spheroid (1880)* are tabulated in Norie's Nautical Tables (NP 320). It is shown at Appendix 5 that the *Meridional Parts 'm'* may be evaluated for any *Spheroid*, from the formula:

$$m = \frac{10800}{\pi}\left[\log_e \tan\left(45° + \frac{L°}{2}\right) - e^2 \sin L - \frac{1}{3}e^4 \sin^3 L - \frac{1}{5}e^6 \sin^5 L - \ldots\right] \quad \ldots \mathbf{5.21a}$$

From (5.21a), a simplified numerical formula (ignoring e^6 and higher powers) for the *WGS 84 Spheroid*, giving the *Meridional Parts* '*m*' correct to four decimal places is:

$$m = 7915.7045 \log_{10} \tan\left(45° + \frac{L°}{2}\right) - 23.01358 \sin L - 0.05135 \sin^3 L \quad \ldots \mathbf{5.21b}$$

b. **Calculation of the Rhumb Line Course.** The *Rhumb Line Course* may now be calculated from formula (5.22), where m_1 and m_2 are the *Meridional Parts* evaluated from formula (5.21b) for the start and end points of the *Rhumb Line*:

$$\tan Course = \frac{d.long}{m_1 \pm m_2} = \frac{d.long}{DMP} \quad \ldots \mathbf{5.22}$$

c. **Length of the Meridional Arc.** It is shown at Appendix 5 that the length 'ℓ' of the *Meridional Arc 'EM'* (see Fig 5-6 below) may be found from the formula:

$$\ell = a\left(\phi - \frac{e^2\phi}{4} - \frac{3e^2}{8}\sin 2\phi - \frac{3e^4}{64}\phi - \frac{3e^4}{32}\sin 2\phi + \frac{15e^4}{256}\sin 4\phi\right) \quad [\phi \text{ in radians}] \ldots \mathbf{5.24}$$



Fig 5-6. Length of the Spheroidal Meridional Arc

(0531) d. **Length of the Meridional Arc in WGS 84.** For the *WGS 84 Spheroid*, where values of a and e^2 from Table 3-1 (see Para 0322) are applied (taking care to select the correct units), formula 5.24 may be simplified with negligible loss of accuracy, as:

$$\ell = 60.007\phi - 8.660\sin 2\phi + 0.009\sin 4\phi \qquad [\phi \text{ in degrees}] \quad \ldots \mathbf{5.24a}$$

e. **Calculation of the Rhumb Line Distance.** The *Rhumb Line Distance* may now be calculated, using the *Course* calculated from formula (5.22) and the *Meridional Arcs* 'ℓ' calculated from formula (5.24) for the start and end points of the *Rhumb Line.*

$$Distance = (\ell_1 \pm \ell_2)\ sec\ Course \quad \ldots \mathbf{5.23}$$

Example 5-5: Calculating Spheroidal Rhumb Line Course and Distance

Find *Rhumb Line Course* and *Distance* from F (40˚43'N, 74˚00'W) to T (55˚45'S, 37˚37'E) on the *WGS 84 Spheroid.*

- **Meridional Parts for the Spheroid:**

$$m = 7915.7045\log_{10}\tan\left(45° + \frac{L°}{2}\right) - 23.01358\ \sin\ L - 0.05135\ \sin^3 L \quad \ldots \text{(formula 5.21b)}$$

$$\begin{aligned} \text{Thus: } m_1\,(F) &= 2664.094 \\ m_2\,(T) &= \underline{-4028.114} \\ DMP &= -6692.208 \text{ (ie } 6692.208\ S) \end{aligned}$$

- **Calculation of the Rhumb Line Course:**

$$\tan Course = \frac{d.long}{m_1 \pm m_2} = \frac{d.long}{DMP} \quad \ldots \text{(formula 5.22)}$$

$$d.long = 111°37'\text{E} = 6697'\text{E}$$

$$\begin{aligned} \text{Thus: } \tan Course &= 6697 \div -6692.208 \\ Course &= -45°.021 = S45.021°E = 134.98° \quad \ldots \text{(formula 5.22)} \end{aligned}$$

- **Calculation of the Length of the Meridional Arcs:**

$$\ell = a\left(\phi - \frac{e^2\phi}{4} - \frac{3e^2}{8}\sin 2\phi - \frac{3e^4}{64}\phi - \frac{3e^4}{32}\sin 2\phi + \frac{15e^4}{256}\sin 4\phi\right) \quad \ldots \text{(formula 5.24)}$$

$$\begin{aligned} a &= 3443.918467 \text{ n. miles} \\ Lat\ F\ (\phi) &= 40.716° = 0.71063989 \text{ radians} \\ Lat\ T\ (\phi) &= 55.750° = 0.97302106 \text{ radians} \end{aligned}$$

Thus: $\ell_1 = 2434.724$ n. miles $\qquad \ell_2 = 3337.326$ n. miles

- **Calculation of the Rhumb Line Distance:**

$$Distance = (\ell_1 \pm \ell_2)\sec Course \quad \ldots \text{(formula 5.23)}$$

$$= 8165.83 \text{ n. miles} \quad \ldots \text{(formula 5.23)}$$

Note 5.2. *Lengths of the Meridional Arcs for WGS 84 by the simplified formula (5.24a) are:*
$\ell_1 = 2434.724$ *n. miles,* $\ell_2 = 3337.327$ *n. miles*

Note 5.3. *Full accuracy figures were used in the above calculations, but all intermediate and final answers shown (above) have been simplified to a lower numbers of decimal places.*

0532-0539. Spare.

SECTION 4 - SPHEROIDAL GEODESIC (GREAT CIRCLE) SAILING

0540. Spheroidal Geodesic (Great Circle) Terminology, Methods and Accuracies

a. **Geodesic - Definition and Properties.** The definition of a *Great Circle* was stated and the concept of a *Geodesic* was introduced at Para 0111c. A full explanation of a *Geodesic* is as follows.

- **Geodesic - Definition.** A *Geodesic* is the intersection of a *Spheroidal* surface and a plane which passes through the centre of the *Spheroid.*
- **Geodesic - Properties.** A *Geodesic* is the shortest distance between two points on the surface of a *Spheroid.*
- **Geodesic - Equivalence to Great Circle Properties.** The *Geodesic* (on a *Spheroid*) is the equivalent of a *Great Circle* on a *Sphere*; it properties and use are similar to those of a *Great Circle* (see details at Para 0115).

b. **Geodesic - Common Usage and Precise Terminology.** In everyday colloquial use, the terms *Great Circle* (in lieu of *Geodesic*) and *Small Circle* are usually applied to the Earth's *Oblate Spheroidal* shape. However, within this Section (Paras 0540-0541) and in Appendix 5, to avoid any possible mathematical confusion, the precise terminology is used. Elsewhere in this book, the colloquial usage of *Great Circle* is normally adopted to include the meaning of *Geodesic.*

c. **Methods for Calculating Geodesics.** There are a variety of solutions for computing the *Geodesic*; some of these use the *Geodetic Latitude* (see Para 0312) and some the *Parametric Latitude* (see Para 0313). Some of the formulae required are too complex for general use, but one of the most suitable formulae is the Andoyer-Lambert method using *Parametric Latitude,* which is fully explained at Para 0541 (opposite).

d. **Summary of the Andoyer-Lambert (Parametric Latitude) Method.** In this method, *Distance* and *Course* are pre-computed on a *Sphere* of radius equal to the semi-major axis of the *Spheroid* on which the positions are located. Corrections are then made to obtain the corresponding *Spheroidal* values.

e. **Accuracy of the Andoyer-Lambert (Parametric Latitude) Method.** The Andoyer-Lambert (*Parametric Latitude*) method is extremely accurate and has been adopted by the Royal Navy and the US Naval Oceanographic Office for navigational use. The magnitude of errors are as follows:

- **Distance Error.** This method has a maximum *Distance* error of 1 metre at 500 *n.miles* (0.00011 %) and 7 metres at 6000 *n.miles* (0.000063 %).
- **Course Error.** *Course* is correct to within 1 second of arc with this method.

0541. Spheroidal Geodesic - Parametric Latitude (Andoyer-Lambert) Method

a. **Sign Convention.** In this calculation, *Latitude* N, *Longitude* E, and *d.long* E are given a positive (+) value, while *Latitude* S, *Longitude* W, and *d.long* W are given a negative (-) value.

b. **Conversion of Geodetic to Parametric Latitudes.** *Geodetic Latitudes* (ϕ) are reduced to *Parametric Latitudes*(β) using '*a'* and *'b'* as the *Equatorial* and *Polar* radii respectively (see Para 0313) in formula (3.7):

$$\tan \beta = \frac{b}{a} \tan \phi \qquad \text{. . . (formula 3.7)}$$

c. **Initial Geodesic Course.** The *Geodesic Azimuth* (and thence initial *Course*) from *F* (*Parametric Latitude* β_1) to *T* (*Parametric Latitude* β_2) is found from formula (5.25):

$$tan\ Azimuth = \frac{sin\ d.long}{cos\ \beta_1\ tan\ \beta_2 - sin\ \beta_1 cos\ d.long} \qquad \text{. . . \textbf{5.25}}$$

d. **Spherical Distance.** The *Spherical Distance* (σ) is calculated in degrees from formula (2.9) and then converted into radians for use with the *Spheroidal Corrections* at Para 0541e (below):

$$cos\ \sigma = sin\ \beta_1\ sin\ \beta_2 + cos\ \beta_1\ cos\ \beta_2\ cos\ d.long \qquad \text{. . . (formula 2.9)}$$

e. **Spheroidal Corrections.** The *Spheroidal Correction* s *M, N, U, V* are now calculated as follows:

$$M = (sin\ \beta_1 + sin\ \beta_2)^2 \qquad \text{. . . \textbf{5.25a}}$$

$$N = (sin\ \beta_1 - sin\ \beta_2)^2 \qquad \text{. . . \textbf{5.25b}}$$

$$U = \frac{\sigma - sin\ \sigma}{1 + cos\ \sigma} \quad [\sigma\ in\ radians] \qquad \text{. . . \textbf{5.25c}}$$

$$V = \frac{\sigma + sin\ \sigma}{1 - cos\ \sigma} \quad [\sigma\ in\ radians] \qquad \text{. . . \textbf{5.25d}}$$

f. **Further Small Spheroidal Corrections.** A further small *Spheroidal Correction* (in seconds) may be applied for extreme accuracy, but for practical purposes this may usually be ignored, and is not covered here.

g. **Geodesic Distance.** Finally, the *Geodesic Distance* is calculated from formula (5.26), where '*a*' is the *Equatorial* radius measured in *International Nautical Miles* and *'f'* is the *Flattening* coefficient for the *Spheroid* in use (see Table 3-1 at Para 0322):

$$Geodesic\ Distance\ [in\ radians] = \sigma - \frac{f}{4}(MU + NV) \qquad \text{. . . \textbf{5.26a}}$$

$$Geodesic\ Distance\ [in\ nautical\ miles] = a\left[\sigma - \frac{f}{4}(MU + NV)\right] \qquad \text{. . . \textbf{5.26}}\ [\sigma\ in\ radians]$$

h. **Example.** An illustration of this calculation is at Example 5-6 overleaf.

(0541 continued)

Example 5-6. Calculating Spheroidal Geodesic Initial Course and Distance

What is the *Geodesic* initial *Course* and *Distance* from point F (40˚43'N, 74˚00'W) to point T (55˚45'S, 37˚37'E) on the *WGS 84 Spheroid?* See Fig 5-7 (below).



Fig 5-7. Spheroidal Geodesic Initial Course and Distance

- **Conversion of Geodetic to Parametric Latitudes:**

$a = 6{,}378{,}137m \div 1852 = 3443.918467$ *n. miles* (*see Table 3-1 at Para 0322*)

$b = 6{,}356{,}752.314m \div 1852 = 3432.37166$ *n. miles* (*see Table 3-1 at Para 0322*)

$$d.long = +111.61667^{\circ}$$

$$\phi_1 = +40.71667^{\circ} \qquad \phi_2 = -55.75^{\circ}$$

$$\tan\beta = \frac{b}{a}\tan\phi \qquad \text{. . . (formula 3.7)}$$

Thus: $\beta_1 = +40.62155172^{\circ}$ $\qquad$ $\beta_2 = -55^{\circ}.66042739^{\circ}$

- **Initial Geodesic Course:**

$$tan\ Azimuth = \frac{sin\ d.long}{cos\ \beta_1\ tan\ \beta_2 - sin\ \beta_1 cos\ d.long} \qquad \text{. . . (formula 5.25)}$$

$$Azimuth = 133.140^{\circ} \text{ or } 313.140^{\circ}$$

By Inspection: $Course = 133.1^{\circ}$

- **Spherical Distance (σ)*:***

$$cos\ \sigma = sin\ \beta_1\ sin\ \beta_2 + cos\ \beta_1\ cos\ \beta_2\ cos\ d.long \qquad \text{. . . (formula 2.9)}$$

$$\sigma = 134.0526724^{\circ} = 2.3396605\ radians$$

(0541 Example 5-6 continued)

- **Spheroidal Corrections:**

$$M = (\sin\beta_1 + \sin\beta_2)^2 \qquad \text{. . . (formula 5.25a)}$$

$$= 0.030502$$

$$N = (\sin\beta_1 - \sin\beta_2)^2 \qquad \text{. . . (formula 5.25b)}$$

$$= 2.180845$$

$$U = \frac{\sigma - \sin\sigma}{1 + \cos\sigma} \quad [\sigma \text{ in radians}] \qquad \text{. . . (formula 5.25c)}$$

$$= 5.320193$$

$$V = \frac{\sigma + \sin\sigma}{1 - \cos\sigma} \quad [\sigma \text{ in radians}] \qquad \text{. . . (formula 5.25d)}$$

$$= 1.804003$$

- **Geodesic Distance:**

$$f = 0.0033528107 \quad (\text{see Table 3-1 at Para 0322})$$

$$\text{Geodesic Distance } \underset{[\sigma \text{ in radians}]}{[\text{in nautical miles}]} = a\left[\sigma - \frac{f}{4}(MU + NV)\right] \qquad \text{. . . (formula 5.26)}$$

$$\text{Geodesic Distance} = 8045.775 \text{ n. miles}$$

Note 5.4. *Full accuracy figures were used in the above calculations, but all intermediate and final answers shown (above) have been simplified to a lower numbers of decimal places.*

0542-0549. Spare.

SECTION 5 - COMPARISON AND CHOICE OF METHODS

0550. Summary of Methods of Calculation Available (New)

a. **Mathematical Concepts and Calculations.** Chapters 1-5, supported by Appendices 1-5, have presented the reader with a detailed mathematical explanation of the shape of the Earth and the calculations necessary to create charts and plan *Sailings*. This provides the mariner with a thorough understanding of the fundamental 'tools of the trade', together with a working knowledge of their capabilities and limitations. It thus provides a firm foundation on which practical use of automated systems (eg *ECDIS / WECDIS* etc) may be carried out with confidence.

b. **Practical Solutions to Calculations.** In the current age of computerised navigation systems (eg *ECDIS / WECDIS*) and very capable stand-alone software (eg HM Nautical Almanac Office *NAVPAC* program [*UKHO* - DP 330]), in practice, it is unlikely that mariners will need to resort to lengthy hand-calculations, even with the assistance of programmable calculators or computer spreadsheets. However, care must be taken with computerised navigation systems (eg *ECDIS / WECDIS*) and stand-alone software that the user fully understands the parameters (ie *Spheroidal* / *Spherical* / *Flat Earth*) of the automatic calculation being performed. In the case of *Spheroidal* calculations, the user must also know which *Spheroid* / *Geodetic Datum* is being employed.

0551. Choice of Methods

a. **NAVPAC.** In the Royal Navy, the use of HM Nautical Almanac Offices's *NAVPAC* program (available from *UKHO* as DP 330) is regarded as the prime authoritative source for *Rhumb Line* and *Great Circle* calculations, as well as for astro navigation and other calculations. *NAVPAC* calculates *Rhumb Lines* on the *WGS 84 Spheriod / Geodetic Datum; Great Circle*s are calculated on a *Spherical* basis (ie not *Geodesics*), but a series of *Rhumb Lines* (with user-defined parameters) are also provided automatically for each *Great Circle* so that convenient *Rhumb Line* approximations may be selected and plotted for practical navigation (see Para 0208e and Para 0441b).

b. **ECDIS / WECDIS.** Most modern *ECDIS / WECDIS* provide a method of calculating *Rhumb Line* distance / courses and *Great Circle* distances on a variety of *Spheroids Datums* as well as on the *Sphere*. However, the facility provided in *NAVPAC* for automatic user-defined *Rhumb Line* approximations of *Great Circles* is not normally available; if it is not provided, this action will have to be carried out manually on the chart-display.

c. **Paper Chart Method.** The intended track may be plotted on a paper chart *(Mercator Projection* and/or *Gnonomic Projection* as appropriate) and the distance / course(s) measured.

d. **Manual Calculations by Hand.** In the event that none of the above methods are available, the necessary calculations (see Chapters 1 to 5 and Appendices 1 to 5) may have to be carried out by hand. In view of the mathematical complexity of some of the equations involved, the use of a computer spreadsheet is strongly recommended.

CHAPTER 6

CHARTS AND PUBLICATIONS - OVERVIEW

CONTENTS

Para

0601. Scope of Chapter

SECTION 1 - CHARTING CONCEPTS AND POLICY

0610. UK Charting Policy
0611. Types of Charts
0612. Organisation of Charts
0613. Legacy Chart Data
0614. Digital Chart Production Methods
0615. Correction and Upkeep of Paper Charts
0616. Reporting Hydrographic Information - Hydrographic Notes

SECTION 2 - NAVIGATIONAL CHARTS

0620. Mercator Projection Charts
0621. Transverse Mercator Projection Charts
0622. Gnomonic Projection Charts
0623. Large Scale Harbour Plans
0624. Information Shown on Paper Charts
0625. Information Shown on ENCs
0626. Selection and Use of Charts

SECTION 3 - DIGITAL NAVIGATION SYSTEMS AND ELECTRONIC CHARTS

0630. Digital Navigation Systems - International Standards
0631. Digital Navigation Systems - ECS, ECDIS and WECDIS Equipments
0632. Digital Navigation Systems - Electronic Chart Data
0633. RNC Raster and ENC Vector Charts - Advantages & Disadvantages

SECTION 4 - NAVIGATIONAL AND DIGITAL PUBLICATIONS

0640. UKHO Navigational and Digital Publications (NPs / DP)
0641. Navigational & Meteorological Stores, ‘RNS’ Forms and Other Stationary Products

INTENTIONALLY BLANK

CHAPTER 6

CHARTS AND PUBLICATIONS - OVERVIEW

0601. Scope of Chapter

Chapter 6 provides a brief summary of British Admiralty charts and publications. Further details of these products may be found at BR 45 Volume 7, and in *United Kingdom Hydrographic Office (UKHO*) publications 'The Mariners Handbook' (NP 100) and 'Catalogue of Admiralty Charts and Publications' (NP 131). This chapter replaces both Chapters 6 and 7 of the 1987 Edition of this book

0602-0609. Spare

SECTION 1 - CHARTING CONCEPTS AND POLICY

0610. UK Charting Policy

The policy followed by the *UKHO* is to chart all waters, ports and harbours in UK waters, UK Overseas Territories and certain Commonwealth and other areas on a *Scale* sufficient for the safe navigation of all vessels. Elsewhere overseas, Admiralty charts are schemed to enable ships to cross the oceans and proceed along the coasts of the world to reach the approaches to ports using the most appropriate *Scales*. In general, foreign ports are charted by *UKHO* at a *Scale* adequate for ships under *Pilotage* (but see Para 0611e). Major ports are charted on larger *Scales* commensurate with their importance or intricacy. Further details are at the *UKHO* publication 'The Mariners Handbook' (NP 100).

0611. Types of Charts

The following information is a brief overview only; for further details see BR 45 Volume 7 Chapter 1, 'The Mariners Handbook' (NP 100) Chapter 1 and 'Catalogue of Admiralty Charts and Publications' (NP 131).

a. **Standard Navigational Charts.** Standard navigational charts, which are usually *Mercator Projection* or *Transverse Mercator Projection* and available commercially from the *UKHO*, make up the vast bulk of a vessel's chart outfit. They are listed primarily in the 'Catalogue of Admiralty Charts and Publications' (NP 131) and (for RN / RFA vessels) in the 'Chart Correction Log and Folio Index' (NP 133B).

b. **'Fleet' and Other Protectively Marked Charts.** Certain charts and diagrams are available to authorised users only; they are not listed in NP 131 or made available for sale commercially. Some of these charts and diagrams are known as 'Fleet' charts and many are standard navigational charts overprinted with additional information; if so, they retain their normal chart number, prefixed by a letter. Their 'Protective Marking' status varies but, in some cases, where the additional data relates only to information (eg exercise area limits) now in the public domain, they have been downgraded to 'Unclassified' while still retaining their 'Fleet' status.

c. **Thematic Charts.** A variety of 'Thematic' charts are available from the *UKHO* including: Routeing Charts, Routeing Guides, *Gnomonic* Charts, Instructional Charts, Hydrographic Practice & Symbol Charts, UK Practice & Exercise (PEXA) Charts, Miscellaneous (UK & World Series Thematic) Charts, Astronomical Charts, Climatic Charts, Magnetic Variation Charts, Meteorological and Upper Air Charts, Territorial Sea Baseline Charts, Tidal Charts, *Bathymetric Charts,* and 'Plotting Diagrams and Sheets'. Details are listed in the 'Catalogue of Admiralty Charts & Publications' (NP 131).

(0611) d. **X Charts.** If a new regulation (eg new *Traffic Separation Scheme* [*TSS*]) affecting a chart is due to come into force on a particular date, *UKHO* will publish a *New Edition (NE)* of the chart well in advance showing the new information. At that time, the existing chart will be authorised to be prefixed 'X' and retained until the *NE* comes into force. In the interim, both charts should be corrected for *Notices to Mariners (NMs*).

e. **Foreign Charts.** *Foreign Charts* may be supplied by *UKHO* to RN / RFA vessels on request, if they are of a better *Scale* or more appropriate than the *UKHO* versions.

0612. Organisation of Charts

a. **Chart Folios.** Although charts may be supplied individually, they are also grouped together in 'folios' by geographical area. Chart outfits are normally supplied to RN / RFA vessels in folios, together with the associated *Navigational Publications (NPs)*.

- Folios 1-100 each provide all the available 'standard navigation charts' (see Para 0611a) for a particular geographical area.
- Folios in the '700 series' contain 'Fleet' charts (see Para 0611b).
- Folios in the '300 series' contain special diagrams, plotting sheets and 'Routeing' charts etc (see Para 0611c).

Chart folios are supplied with buckram covers of an appropriate colour and charts are arranged in numerical order within each folio. A list of unclassified chart folios is contained in 'Chart / Publication Outfits For HM Ships, RFAs and RMAS' (NP 104). A list of protectively marked folios, together with their contents, is listed in the 'Catalogue of Classified and Other Charts and Hydrographic Publications' (NP 111).

b. **Geographical Folio Coverage.** Approximate geographical limits of Folios 1-100 are in the 'Catalogue of Admiralty Charts & other Hydrographic Publications' (NP 131).

Note 6-1. *When deciding on the outfit, care must be taken to ensure sufficient folios are held, particularly if operating near the boundary of folios (eg the boundaries of folios 1, 7, 8, 9 and 16 are adjacent, in the southern North Sea / Thames Estuary / Dover Straits area).*

c. **Folio Labels.** When chart folios are supplied, a 'folio label' (H119 for standard folios / H82 for Fleet folios) is pasted on the cover showing the folio number, dates of issue, the correction state, and the name of ship / submarine to which it has been issued.

d. **Folio Lists.** When chart folios are supplied, in addition to the folio label (see Para 0612c above), a 'folio list' showing the numbers and titles of the charts contained in the folio, the *NP* numbers and titles of the appropriate volumes of *Admiralty Sailing Directions (Pilots)* and of the *Admiralty List of Lights and Fog Signals (ALLFS)*, and if appropriate, any other necessary *NP*. Duplicate folio lists are also supplied and kept in the 'Chart Correction Log and Folio Index' (NP 133B).

e. **Local Folios.** The number of 'spare' charts needed (eg for *Pilotage, Blind Pilotage*, exercises etc) may exceed the capacity of the folio cover (eg Folio 1, which includes naval base ports and exercise areas). It is thus appropriate to transfer some charts from the main folio to a 'local folio' for ease of storage and use; a note must be made in the 'Chart Correction Log and Folio Index' (NP 133B) and that the appropriate chart corrections must be properly logged and applied (see BR 45 Volume 7 Chapter 4).

f. **RN Backup Folios.** *UKHO* provides ten regional 'Backup' folios of paper charts for RN / RFA vessels corresponding to the ten regional *ARCS* areas.

0613. Legacy Chart Data

The compilation and production processes for British Admiralty charts has evolved from the days of the quill pen (see below) to [*Warship*] *Electronic Chart Display and Information Systems* (*WECDIS / ECDIS)* (see Para 0614). British Admiralty charts are produced by *UKHO,* which is an Agency of the British Ministry of Defence. This department was formed in 1795 because, it was said, more RN warships were being lost on uncharted or badly charted shoals than were being sunk by enemy action.

a. **Sounding Methods.**

- **Lead and Line Soundings: 1795-1935 / 1950.** Lead and line was the only method of sounding until *Echo Sounders* came into use in about 1935; the hand lead continued for inshore work into the 1950s. A sounding with lead and line covered only the few centimetres actually struck by the lead and objects less than a metre away from each cast remained undetected.
- **Vertical Echo Soundings: from 1935.** Vertical *Echo Sounders* only examine a narrow strip immediately under the hull of the ship, and even on a large-*Scale* harbour chart these strips can be as much as 60 metres apart.
- **Sidescan Sonar: from 1973.** Sidescan sonar was introduced in about 1973, allowing the detection of shoals and wrecks lying between sounding lines.
- **Examination of Dangers.** Until the early 1960s, *UKHO* did not examine in detail any object likely to be deeper than 66 feet (20 metres).

b. **Charted Soundings.** Although sidescan sonar has been employed extensively by *UKHO* since 1973, the large majority of charts in use are still based on older surveying methods. Ships can still find that in every part of the world there are areas which were surveyed using the hand lead only.

c. **Uncharted Dangers.** For the above reasons, it is still quite possible to find uncharted rocks, shoals and wrecks anywhere in the world. Rocky pinnacles rising to within 10 metres of the surface have been found in well-used waters (eg approaches to Holyhead [Wales] and Auckland [New Zealand]. The 18 metre ‘Walter Shoals’, surrounded by great oceanic depths on the route between Cape of Good Hope and Sunda Strait, were not discovered until 1962. It is estimated that there are some 20,000 wrecks or underwater obstructions in British coastal waters alone, but the exact position or the depth of water over many of them is unknown. For historical reasons, dangers to deep-draught ships still exist on continental shelves, even in well recognised shipping lanes (see CAUTION below). **Thus no chart is infallible.** Every chart is liable to be incomplete, either through imperfections in the surveys on which it is based, or through subsequent alterations to the topography and sea-bed.

CAUTION

UNCHARTED DANGERS. Deep-draught ships need to exercise care within the 200 metre depth contour, even in well recognised shipping lanes, because of the historic limit of 20 metres for the examination of dangers.

0614. Digital Chart Production Methods

UKHO methods for modern chart production are as follows. (See Para 0632 for details of *Vector* and *Raster* digital chart types [ie *Electronic Navigation Charts (ENCs), Raster Navigation Charts (RNC)* and 'non-*IHO*-compliant' *Vector* charts] and their legal status.)

a. **Digitisation of Paper Chart Data.** Over some years, navigational data previously stored on paper charts has been scanned digitally. The latest version of each *RNC* and paper navigational chart is now held digitally in *Raster* format in a *Raster* database.

b. **Input of New Data for Charts.** New data for charts is forwarded to the *UKHO* from a very wide range of sources in both analogue and digital formats; however, it can only be applied to *ENCs* which have been produced by *UKHO*. All new data (eg new foreign government charts, textual *NMs*, new surveys etc) is first assessed by the appropriate 'Nautical Chart Branch' or 'Specialist Branch' for safety-criticality before appropriate chart action is taken (*NM* textual correction / block correction for paper charts etc). Large *NM* updates and blocks for paper charts will be issued as *NEs* for *ENCs*. New data is transformed into the *UKHO* digital format for charts, as follows:

- **New Data in Digital Format.** On receipt of new digital data in the *UKHO*, it is validated and verified to ensure it is fit for purpose. Using the digital source as a backdrop to the *Raster* image of the existing chart, changes are captured in *Vector* format. Once the new information has been captured, it is then converted into *Raster* format and combined with the existing file.
- **New Data NOT in Digital Format.** Hard copy data is *Raster* scanned and used as a *Raster* backdrop to the existing chart, in order to view the existing chart and the new data together. The same editing process is then followed.

c. **Raster Database.** Once a chart has been revised, the digital *Raster* files are returned to the *Raster* database. The *Raster* database therefore holds the latest data for all *UKHO* charts. Several products are generated from the *Raster* database; these include paper charts, the (*RNC*) *Admiralty Raster Chart Service* (*ARCS*) version of the chart and inputs to the *ENC* database for the creation of updates and *NEs* of *ENCs.*

d. **Paper Chart Production.** The *Raster* database is used to export digital files to the computer-to-plate technology, which produces thin aluminium printing plates. These plates are used once, for a single multi-colour print run of the full sized paper chart using high quality paper and precision printing machines to ensure perfect colour registration.

e. **Notices to Mariners.** *Notices to Mariners (NM),* including their associated tracings and colour blocks for pasting onto charts, are produced similarly to paper charts.

0615. Correction and Upkeep of Paper Charts

To be safe and effective, navigational charts (whether in paper or electronic format) must be corrected up to date for safety-critical navigational information. The methods of promulgating this information are described in detail in 'The Mariners Handbook' (NP 100) Chapter 1; the detailed procedures for updating charts are at BR 45 Volume 7 Chapters 5 and 7 (paper charts) and at BR 45 Volume 8(1) Chapter 8 (charts in electronic format). The following information is a brief overview of the methods of promulgating safety-critical navigational information.

a. **Promulgation.** Safety-critical information is promulgated as follows:

- **Permanent Notices to Mariners (NMs).** Permanent *Notices to Mariners* (*NMs*) are issued weekly in hard and soft copy by *UKHO*. They are usually in text but may include a coloured 'block' to be pasted over part of the chart.
- **Temporary and Preliminary Notices to Mariners (T& Ps).** *Temporary and Preliminary Notices to Mariners* (*T&Ps*) are issued weekly in hard and soft copy by *UKHO*, together with ordinary *NMs*. They are normally plotted on paper charts in pencil and erased when no longer in force.
    - ‣ **Temporary Notices to Mariners.** *Temporary Notices to Mariners* are used when the information is only valid for a limited period.
    - ‣ **Preliminary Notices to Mariners.** *Preliminary Notices to Mariners* are used when early notification of changes needs to be promulgated (eg harbour development work about to take place, or notification that a *New Chart (NC) / New Edition (NE)* is about to be published).
- **Local Notices to Mariners.** Local *NMs* are issued by local authorities.
- **New Editions (NEs) / New Charts (NCs).** When substantial chart changes have accumulated *UKHO* will issue a *New Edition* (*NE*), or if the boundaries / number have changed will issue a *New Chart (NC)*. A *Preliminary Notice to Mariners* will normally precede the issue of a *NC / NE*.
- **Urgent New Edition (UNE).** An *NE* may be issued as an *Urgent New Edition* (*UNE*) but if so, may NOT include all available safety-critical data.
- **Radio Navigational Warnings.** Three types of *Radio Navigational Warning* are issued for urgent safety-critical navigational information: *NAVAREA Warnings, Coastal Warnings* and *Local Warning*s. *Radio Navigational Warnings* are normally plotted on the appropriate paper charts in pencil and erased when no longer in force.
    - ‣ **NAVAREA Warnings.** *NAVAREA Warnings* contain safety information for ocean-going mariners, divided into 16 areas (see Fig 6-1 overleaf). They are broadcast by 'SafetyNET' and appropriate *NAVTEX* stations.
    - ‣ **Coastal Warnings.** *Coastal Warnings* are promulgated by the appropriate National Coordinator for areas out to about 250 *n. miles* from the coastline. They are normally broadcast by the appropriate *NAVTEX* station but may also be broadcast on 'SafetyNET' or other means.
    - ‣ **Local Warnings.** *Local Warning*s supplement *Coastal Warnings* for detailed inshore or port information for ships visiting a particular harbour. They are usually issued by port, pilotage or coastguard authorities, often by VHF voice messages, which may be in English or the local language.

(0615a continued)


NAVAREA LIMITS OF THE
WORLD-WIDE NAVIGATIONAL WARNING SERVICE
Geographical Areas for co-ordinating and promulgating Radio Navigational Warnings
Key:
• Coast radio station
Limits of NAVAREAS
60°
0°
60°
120°
180°
120°
60°
Meridian of 0° Greenwich
I United Kingdom
II France
III Spain
Baltic Sea sub-area
IV USA
V Brazil
VI Argentina
VII South Africa
VIII India
IX
X Australia
XI Japan
XII USA
XIII Russia
XIV New Zealand
XV Chile
XVI Peru
Boston
Belém
Olinda
Rio de Janeiro
Junção
Buenos Aires
Cape Town
Durban
Karachi
India/Pakistan border
Bombay
Burma (Myanmar)/Thailand border
Russia/Korea, N border
Vladivostok
Guam
Honolulu
Sydney
Taupo
Valparaíso Playa Ancha
67°
50°

Fig 6-1. NAVAREA Limits of the World-wide Navigational Warning Service

(0615) b. **Digital Promulgation.** *NMs, T&Ps, NEs* and *NCs* are promulgated by cumulative weekly CD for digital charts (ie *RNCs* and *ENCs* etc). *Radio Navigation Warnings* (see Para 0615a) for digital charts are manually input to *RNCs / ENCs,* using digital methods.

0616. Reporting Hydrographic Information - Hydrographic Notes

a. **Requirement.** Subject to the provisions of international law concerning innocent passage through territorial seas or national laws where appropriate, mariners should endeavour to note where charts and navigational publications disagree with fact, and report any differences to the *UKHO*. In addition, statements confirming the accuracy of charted and published information which may be old is also of considerable value.

b. **Method.** Reports should be made to the "UKHO, Admiralty Way, Taunton, Somerset TA1 2DN, United Kingdom", either in manuscript, or by e-mail, or as a *Hydrographic Note* on Forms H.102 / H.102a. Current web, e-mail, FAX and phone contact details for *UKHO* are shown at the front of *Weekly NMs*. Copies of Forms H.102 / H.102a are included on *RNC / ENC* weekly CDs, in every *Weekly NM*, and in The Mariners Handbook (NP 100); they may also be obtained gratis from any Admiralty Chart Agent. Digital *Hydrographic Notes*, including instructions for completion are available in (NP 145) 'HMOG Forms', under 'H102, H102A and H102B'. These can also be downloaded from *UKHO* and e-mailed to *UKHO* when complete.

c. **Further Information.** For further information on all aspects of *Hydrographic Note*s, see 'The Mariners Handbook' (NP 100) Chapter 8.

0617-0619 Spare.

SECTION 2 - NAVIGATIONAL CHARTS

0620. Mercator Projection Charts

A list of *Mercator Projection* properties and uses is at Para 0414b and a full description of its construction is at Paras 0420-0425; an explanation of the mathematical basis for *Meridional Parts* and *Position Circles* is at Appendix 4. For the convenience of readers, an extract from Para 0414b (Uses of *Mercator Projection* charts) is repeated below:

> **(Extract from Para 0414b):**
>
> - **Uses.** The *Mercator Projection* is extensively used for small *Scale* nautical charts of 1:75,000 and smaller. However, for large *Scale* nautical charts (1:50,000 and greater), the *Transverse Mercator Projection* is generally used instead.

0621. Transverse Mercator Projection Charts

A list of *Transverse Mercator Projection* properties and uses is at Para 0414c and a full description of its construction is at Paras 0430-0431; an explanation of the mathematics for geographical / *Grid* conversions is at Appendix 4. For the convenience of readers, an extract from Para 0414c (Uses of *Transverse Mercator Projection* charts) is repeated below:

> **(Extract from Para 0414c):**
>
> - **Uses.** The *Transverse Mercator Projection* is used for:
>   - Most *UKHO* large *Scale* charts of 1:50,000 or larger (ie covering a small area) as well as for land maps.
>   - Most land maps (including UK Ordnance Survey maps / NATO military maps).
>   - *Polar* charts and maps, although the *Polar Stereographic Projection* is more commonly used for this purpose.

0622. Gnomonic Projection Charts

A list of *Gnomonic Projection* properties and uses is at Para 0414e, a full description of its construction is at Paras 0440-0442 and an explanation of its mathematical basis is at Appendix 4. For the convenience of readers, an extract from Para 0414e (Uses of *Gnomonic Projection* charts) is repeated below:

> **(Extract from Para 0414e):**
>
> - **Uses.** The distortion of the *Gnomonic Projection Graticule*, which gives neither *Orthomorphic* nor *Equal Area* properties, makes it quite unsuitable for general *Navigation* purposes. Its usage is limited entirely to plotting *Great Circles* as straight lines, usually in order to obtain *Great Circle Waypoints*.

a. **Gnomonic Projection - Available Charts.** A series of small-*Scale Gnomonic Projection* charts covering the major oceanic areas is available for plotting *Great Circles* as straight lines. They are particularly useful for *Composite Tracks* (combinations of *Great Circles* and a *Safe Parallel*). They should NOT be used for *Navigation*.

b. **Gnomonic Projection Chart - Incorrect Use of Title for Large Scale Plans.** In a few older Admiralty charts and plans of *Scale* 1:50,000 and larger, '*Gnomonic Projection*' was printed under the chart title, when in fact, a modified form of *Polyconic Projection* (see Para 0414g) was actually used. Although it was strictly incorrect to call these charts '*Gnomonic*', on such large *Scale* plans, lines of sight and other *Great Circles* are correctly represented by straight lines; for all practical purposes straight lines can be used on them to plot all bearing and direction lines. Modern charts of this *Scale* are constructed on the *Transverse Mercator Projection* (see Para 0623 overleaf).

0623. Large Scale Harbour Plans

a. **Modern Harbour Plans.** Most modern large-*Scale* harbour plans are constructed on *Transverse Mercator Projection* and are graduated for *Latitude* / *Longitude*. Linear *Scales* of feet, metres and cables (1 cable = 0.1 *Sea Mile*, see Para 0113) are given on all plans, with heights and depths in metres. A modern harbour plan is at Fig 6-2 below.


BRIXHAM
HARBOUR
SCALE 1:7500
Breakwater
Town Dock and Lifeboat Fairway
Main Fairway
Outer Harbour
Trawler and Small Craft Moorings
Small Craft Moorings
Prince William Marina
Wave Screen
Fishcombe Cove
Battery Pt.
Oxen Cove
Pontoon (Apr-Sep)
Brixham YC
Fish Quay
MFV Basin
Southern Quay
Eastern Pier
New Pier
Eastern Quay
King's Quay
Inner Harbour
Brixham CG
Marina Control
The Hard
Breakwater Beach
Swimming Pool
Holiday Centre
BRIXHAM
All Saints Ch
Feet 1000 500 0 1000 Feet
Metres 100 0 500 1000 Metres
Cable 1 0 5 Cables or 0·5 Sea Miles

Fig 6-2. **Modern Harbour Plan - Linear Scales (ft/m/c) with Depths / Heights (m)**

b. **Older Harbour Plans - Constructing a Longitude Scale.** On older harbour plans, the *Longitude Scale* may not be given. This may be found from the following construction.

- From the zero on the *Latitude Scale*, draw a line making an angle with it equal to the *Latitude* of the plan (see example of 45˚at Fig 6-3 below).
- From each division on the *Latitude Scale*, draw a perpendicular to this line. Intersections of the perpendiculars with the line mark the *Longitude Scale*.


Longitude Scale
1
2
3
4
5
Lat
= 45°
0
1
2
3
4
5
Sea Miles on Latitude Scale

Fig 6-3. **Older Harbour Plans - Constructing a Longitude Scale (eg 45˚ Latitude)**

0624. Information Shown on Paper Charts

Information contained on Admiralty charts is summarised as follows:

a. **Chart Number and Thumb Label.** The chart number is shown outside the bottom right-hand and top left-hand corners of the chart. If the chart is also in the International Series, this number is also shown, prefixed 'INT'. A small label, known as the 'thumb label', is printed on the reverse of each chart; it shows the number, title, printing date and printing batch number of the chart, and provides space for notation of the folio number.

b. **Chart Title.** The chart title is shown in the most convenient place so that no essential navigational information is obscured by it. The chart title is also shown in the thumb-label on the reverse of the chart.

c. **Source Data Diagram.** A *Source Data* diagram (see Fig 6-4 below) is normally shown on each chart. These diagrams indicate the source, date and *Scale* of the survey in each part of the chart.



Fig 6-4. Source Data Diagram

d. **Source Data Legends.** On some (usually older) charts, in lieu of the *Source Data*diagram, the source may be shown under the chart title.

e. **Satellite Derived Positions.** The *Datum Shift* (see Para 0323) is included on older charts adjacent to the chart title, indicating the amount by which a position obtained from a satellite navigation system should be moved to agree with the chart. Charts published in *WGS 84 Datum* indicate this in magenta, outside the bottom right and top left-hand corners, in lieu of the 'Depths in Metres' marking.

f. **New Charts (NCs) - Publication Date.** When a *New Chart* (*NC*) is published, the date of publication is shown outside its bottom margin, in the middle eg: "Published at Taunton, 30th March 2006" (Chart 2692).

g. **New Editions (NEs) / Urgent New Editions (UNEs) - Publication Date.** When a chart is revised, a *New Edition* (*NE*) or *Urgent New Edition* (*UNE*) is published. The edition number and date of publication is shown at the bottom of the chart eg:

"Edition Number 6 Edition Date 6th Mar 2003" (Chart 2675)

Older charts (pre-2000) state: "New Editions 27th July 1990, 1st July 1999" (Chart 3154)

(0624) h. **Notices to Mariners (Small Corrections).** *Notices to Mariners* (*NMs*) which have been applied to the chart are listed, by year and *NM* number, at the bottom left-hand corner of the chart eg:

"**Notices to Mariners 2005** - 6183- **2006** - 2652 - 4546" (eg Chart 34)

Charts issued as *NEs* prior to May 2000 may show the legend '*Small Corrections*' in lieu of '*Notices to Mariners'*. Admiralty charts corrected for Australian or New Zealand *NMs* list the applicable British Admiralty (BA) and AUS or NZ *Small Corrections* separately, prefixed accordingly.

i. **Large Corrections and Bracketed Corrections (Obsolete).** Until 1972, *Large Corrections* were sometimes issued instead of *New Editions (NEs)*. Until 1986, *Bracketed Corrections* were used to give information which was useful to mariners but not essential. These notations may still be found on some older charts.

j. **Date of Printing.** The date of printing is shown in the format YY / MM / DD in the thumb-label on the reverse of the chart eg: "01 / 05 /20" (Chart 30).

k. **Chart Dimensions.** Chart dimensions in millemetres (eg 630.0 x 980.0 mm) are shown in parentheses outside the lower right-hand border of the chart; some fathoms charts use inches. The dimensions are for the inner border of the chart (neat lines) and exclude chart borders. In the case of charts on the *Gnomonic Projection*, dimensions are quoted for the north and south borders, and on the *Transverse Mercator Projection* for all four borders. These dimensions may be used to check for chart distortion.

m. **Corner Co-ordinates.** Co-ordinates expressing the *Latitude* and *Longitude* of the limits of Admiralty charts published after 1972 as *New Charts* (*NCs*) or *NEs* are shown at the upper right and lower left corners of the chart.

n. **Scale of the Chart.** The natural *Scale* is shown beneath the title; on *Mercator Projection* charts this is for a stated *Latitude*. A *Scale* of metres is shown in the side margins of some charts of *Scale* larger than 1:100,000 to facilitate the plotting of ranges from radar displays graduated in this way. Large *Scale* plans have an additional *Scale*, normally showing feet, metres and cables.

o. **Colours Used on Metric Charts.** Shallow water on metric charts is distinguished by a light blue tint and a darker blue tint between the coastline and appropriate depth contours; these tints includes all isolated patches within the depth range and the darker blue tint indicates shallower water. Drying (intertidal) areas are shown in a green tint. Dry land is shown in a yellow tint. Magenta is used for the emphasis of certain details, notably lights and radio aids and to distinguish numerous other features superimposed on the basic hydrography. Example of modern metric charts are at Fig 6-2 (facing previous page) and Figs 12-1 & 12-2a/b/c (all at Para 1214).

p. **Depth Soundings - Position.** On all charts, the position of a depth sounding is the centre of the space occupied by the sounding figure(s).

q. **Depth Soundings - Units.** The unit in use for depths is stated in bold lettering below the title of the chart. It is also shown on older charts, in magenta, outside the bottom right and top left-hand corners of metric charts. Charts published in *WGS 84 Datum* indicate this in magenta, outside the bottom right and top left-hand corners, in lieu of the 'Depths in Metres' marking (see Para 0624e).

(0624) r. **Depth Soundings - Chart Datum.** Depths on charts are given below *Chart Datum* (see definition at Para 1062c).

- **UKHO as Charting Authority.** On metric charts for which the *UKHO* is the charting authority, *Chart Datum* is the approximate level of *Lowest Astronomical Tide* (*LAT*) - see definition at Para 1062e.
- **Charts Based on Foreign Charts.** For charts based on *Foreign Charts* in tidal waters, *Chart Datums* are LW levels which range from *Mean Low Water* (*MLW*) to the lowest possible LW; in non-tidal waters (eg the Baltic) *Chart Datum* is usually *Mean Sea Level (MSL)* - see definition at Para 1062e.
- **Chart Datum Information Legend / Panel.** A brief description of the level of *Chart Datum* is given under the title of all metric charts. Large and medium *Scale* charts contain a panel giving the heights above *Chart Datum* of either *Mean High Water Springs* (*MHWS*) and *Mean Low Water Neaps (MLWN)*, or *Mean Higher High Water* (*MHHW*) and *Mean Lower Low Water* (*MLLW*), whichever is appropriate (see definitions at Para 1062e).

s. **Depth Soundings - Metric Charts.** On metric charts, soundings are generally shown in metres and decimetres in depths of less than 21 metres; elsewhere in whole metres only. Where navigation of deep-draught vessels is a factor and where the survey data are sufficiently precise, soundings between 21 and 31 metres may be expressed in metres and half-metres.

t. **Depth Soundings - Fathom Charts.** On fathom charts, soundings are generally shown in fathoms and feet in depths of less than 11 fathoms, and in fathoms elsewhere. In areas used by deep-draught vessels where the depth data are sufficiently precise, charts show depths between 11 and 15 fathoms in fathoms and feet. Some older charts show fractional parts of fathoms in shallow areas and a few older charts express all soundings in feet.

u. **Depth Contours.** On charts, all soundings less than and equal to certain depths are enclosed by appropriate metre or fathom contour lines.

v. **Heights / Elevations.** Heights and *Elevations*, except *Vertical Clearance* and (drying) heights (see Paras 0624w/x), are given in metres or feet above a *Vertical Datum*, usually *Mean High Water Springs* (*MHWS*), or *Mean Higher High Water* (*MHHW*) or, where tidal *Range* is negligible, *Mean Sea Level* (*MSL*). In most instances the position of the height is that of the dot alongside the figure (eg **.135)**. Heights which are displaced from the feature to which they refer (eg a small islet), or which qualify the description of a feature (eg a chimney) are placed in parentheses.

w. **Vertical Clearance Heights.** Since 2004, *Vertical Clearance* of bridges and overhead power cables have been quoted above *Highest Astronomical Tide* (*HAT*) where there is an appreciable tidal *Range* (instead of *MHWS*), and above *MSL* where the *Range* is negligible. The *Vertical Datum* used for clearance heights is stated on the chart.

x. **Drying Heights.** Underlined figures on rocks and banks which uncover give the drying heights above *Chart Datum* in metres and decimetres, or in feet, as appropriate.

y. **Compass Roses.** *Compass Roses* are printed at intervals on paper charts and show true bearings from 0˚-360˚ (and usually local *Magnetic Variation* and its annual change).

(0624) z. **Tidal Stream Information.** *Tidal Stream* information may be shown either in a table, or (when insufficient data for constructing tables is available) by *Tidal Stream* arrows and notes giving the times of slack water and the rate of the *Tidal Stream*s. All information about *Tidal Stream*s is given in a convenient place on the chart and referred to by a diamond symbol (ie ◊) at the position for which the information is given.

aa. **Reference to Adjoining Chart or Large Scale Plan.** References to adjoining charts are shown in magenta on many charts. Larger *Scale* charts or plans are indicated on many charts by a magenta outline with the chart number shown in magenta.

ab. **Cautionary Notes.** Any 'Cautionary Notes' are printed prominently, usually under the chart title. 'Cautionary Notes' should ALWAYS be read before using the chart.

ac. **Abbreviations and Symbols.** Standard abbreviations and symbols used on Admiralty charts are shown in 'Chart Booklet' 5011, 'Thematic Charts' D6067 (Use of Symbols and Abbreviations) and D6695 (Borders, Grids, Graduations and Scales).

ad. **Crown Copyright.** All Admiralty charts are 'UK Crown Copyright' and this is indicated adjacent to the date of publication (see Para 0624f).

0625. Information Shown on ENCs

Much of the information on paper charts (see Para 0624) is presented on *ENCs* but often in a different form (see Para 0632). In particular, *ENCs* do not have *Source Data* diagrams but instead have *Category of Zone of Confidence* (*CATZOC*) data fields with 5 assessed categories (A1, A2, B, C, and D) and 1 category (U) which is not assessed. Details of *CATZOC* parameters are at 'The Mariners Handbook' (NP 100) Chapter 2.

0626. Selection and Use of Charts

a. **Using Charts.** Each Admiralty chart, or series of charts, is designed for a particular purpose. Large *Scale* charts are intended for entering harbours or anchorages or for navigating close to potential hazards. Medium *Scale* charts are intended for coastal navigation, while small *Scale* charts are intended for offshore navigation. Always use the largest *Scale* chart appropriate to the purpose.

- **Coastal Passage.** For passage along a coast, use the continuous series of medium *Scale* charts provided for that purpose.
- **Use of Larger Scale Charts on Coastal Passage.** Only transfer to the larger *Scale* chart where it depicts potential hazards close to the intended route more clearly. There is usually no need to transfer for short distances to a larger *Scale* chart intended for entering an adjacent port or anchorage. Although the larger *Scale* chart depicts information in more detail, the next smaller *Scale* shows all the dangers, traffic separation scheme, navigational aids etc that are appropriate to the purpose for which the smaller *Scale* chart is designed.
- **Sea-Bed.** The sea-bed is likely to correspond to the adjacent land features, even when the chart gives no hint of bottom irregularities. Off an area where sharp hillocks and rocky, off-lying islands abound, the sea-bed is likely to be equally uneven and old surveys must be even more suspect than off a coast where the visible land is flat and regular. There may be uncharted dangers on or near the rim of a saucer-like plateau surrounding a coral group.

(0626) b. **Distinguishing a Well-Surveyed Chart.** As stated at Para 0613c, no chart is infallible; every chart is liable to be incomplete in some way. The date of survey and sounding methods used (see Paras 0613, 0624c/d and 0625) will give a good indication of the chart's reliability. It should be carefully inspected to check the following:

- The survey should be reasonably modern (check *Source Data / CATZOC*).
- The survey authority should be reliable (check *Source Data / CATZOC*).
- The survey *Scale* should be adequate and will usually be larger *Scale* than that of the chart itself (check *Source Data/ CATZOC*).
- The character and completeness of the original survey material and of subsequent updates should be reliable (check *Source Data / CATZOC*).
- Soundings should be close together, regularly spaced with no blank spaces.
- Lead-line surveys should be treated with **particular caution**, particularly if the chart is to be used for pilotage (check *Source Data / CATZOC*). Vertical *Echo Sounder* surveys should also be treated with caution.
- Depth and height contour lines should be continuous, not broken.
- Topographical detail should be good.
- All the coastline should be completed, with no pecked portions indicating lack of information.
- Any suspicious inconsistencies of any sort (eg errors in *Latitude* and *Longitude* for geographical position) should be carefully assessed.

c. **Distortion of Paper Charts.** Paper charts are liable to slight distortion at various stages in the process of reproduction but the effect is seldom sufficient to affect navigation. Any distortion may be observed by checking the dimensions (see Para 0624k). If there is distortion, bearings of objects, however accurate, may not plot correctly, particularly if those objects are at a distance as displayed on the chart. The larger the *Scale* of the chart, the effects of distortion lessen proportionately.

d. **To Identify a Particular Copy of a Chart.** When ordering a chart from *UKHO* or elsewhere it is normally only necessary to state the chart number. However, to identify a particular copy of a chart, the following parameters are needed:

- Chart number.
- Chart title.
- Date of publication (as a *NC*)
- Date of the last *NE*
- Number (or date) of the last *NM* (or pre-2000: *Small Correction*).

0627-0629. Spare

SECTION 3 - DIGITAL NAVIGATION SYSTEMS AND ELECTRONIC CHARTS

0630. Digital Navigation Systems - International Standards

A wide variety of electronic navigation systems for use with charts in electronic format are available commercially. However, not all such systems are '*IMO*-compliant' and not all such charts conform to *International Hydrographic Organisation* (*IHO*) specifications for safe *Navigation*. Thus a wide variation in quality may be experienced between different electronic navigation systems and data, with obvious implications for safe *Navigation*. Detailed guidance on this subject is at BR 45 Volume 8, but this Section provides a brief summary.

0631. Digital Navigation Systems - ECS, ECDIS and WECDIS Equipments

a. **Electronic Chart System (ECS).** An *Electronic Chart System (ECS)* is a generic term for equipment that displays charts in electronic format, which do NOT satisfy *IMO SOLAS* requirements, and may NOT be used as a substitute for up-to-date official charts. However, an *ECS* may legally be used alongside paper charts and can improve navigational safety and situational awareness provided care is exercised in its use.

b. **Electronic Chart Display and Information System (ECDIS).** An *Electronic Chart Display and Information System (ECDIS)* is a navigational information system which complies with the *IMO* performance standards and which, with adequate back-up arrangements, can be accepted as complying with carriage requirements of Chapter V Regulation19 of the 2002 *IMO SOLAS* Convention. The presence of a second *ECDIS* system, robust *Uninterruptible Power Supply (UPS)* and/or the immediate availability of adequate, corrected paper charts covering the present area (although not necessarily the best *Scale* available) are deemed 'adequate back-up' by the *IMO* and RN.

c. **Warship Electronic Chart Display and Information System (WECDIS).** A *Warship Electronic Chart Display and Information System (WECDIS)* is an *ECDIS* with extra functionality to make it more effective for warfare purposes (see Fig 6-5 below).



Fig 6-5. A WECDIS Terminal fitted in an RN Warship (operating ECPINS software)

(0631) d. **Management of ECDIS and WECDIS - BR 45 Volume 8.** The effective management of an *ECDIS / WECDIS* being used for *Navigation* is a major task. All *RNCs / ENCs* held also need to be systematically updated and the updates recorded, particularly when duplicate / triplicate *ECDIS / WECDIS* are fitted. In the RN, *Standard Operating Procedures* (*SOPs*) have been devised for these purposes. Detailed *ECDIS / WECDIS* operating guidance and *SOPs* are at BR 45 Volume 8.

0632. Digital Navigation Systems - Electronic Chart Data

Wide variations exist in the quality and reliability of charts in electronic format available commercially. The existing types of chart in electronic format and their legal status are:

a. **Legal Status of ENCs and RNCs.** *SOLAS* Chapter V (2002) Regulations 2 and 19 state that paper charts and *ENCs* are legally classified as *'Nautical Charts'*, but *RNCs* are not because they are neither a 'map' nor a 'database', but are only a digital facsimile of the original paper chart. However, *ECDIS / WECDIS* using *RNCs* fulfills the carriage requirement when no *ENC* is available, provided it is used with an up-to-date outfit of paper charts.

b. **Official Chart Data.** Official chart data is issued from National Hydrographic Offices or equivalent, and should conform to *IHO* specifications. Official chart data includes: 'S-57' format *ENCs*, 'Official Paper Charts', *ARCS* and *Australian Hydrographic Office* (*AHO*) '*Seafarer*' *RNCs*. See Para 0615b for updating of official chart data.

c. **Raster Navigation Charts (RNC).** *RNCs*, known colloquially as '*Raster'* charts, are produced by scanning a paper chart. Official *RNCs* conform to *IHO* specifications, but as they are only a digital facsimile of the original paper chart, the image has no 'intelligence' and cannot be 'interrogated' other than by visual means.

d. **Raster Navigation Chart (RNC) Formats.** There are two *Raster* chart formats: *HCRF* and *BSB*. The *UKHO* produces *ARCS* charts in their proprietary *Hydrographic Chart Raster Format (HCRF)*. The *AHO* also uses *HCRF* to produce *AHO 'Seafarer' Raster* charts. The *US National Geospatial & Chart Agency (NGA)* produce *Raster* charts in *BSB* format, which is not compatible with *HCRF*.

e. **Vector Charts - General.** *Vector* charts comprise a digital database of chart data which can be input to an *ECDIS / WECDIS*. Certain *Vector* charts may, or may not, meet *IHO* standards and users should take particular care to establish the origin and reliability of any *Vector* charts used with an *ECDIS / WECDIS*.

f. **Electronic Navigation Charts (ENC).** *Electronic Navigation Charts (ENC)* are *Vector* charts which conform to the following legal (*IHO* specification) conditions:

- *ENC*s are compliant with *IHO* 'S-57 Edition 3.1' (see Note 6-2 below), for content, structure and format.
- *ENC*s are issued for use with *ECDIS / WECDIS* on the authority of government authorised Hydrographic Offices.

Note 6-2. *The IHO (Standard) "S-57 Edition 3.1" database format ensures that ENCs contain all the information necessary for safe Navigation, and may contain supplementary information in addition to that contained on the paper chart (eg Sailing Directions, tidal information, etc) which may assist safe Navigation.*

(0632) g. **Non-Compliant Vector Charts.** *Vector* charts which are NOT compliant with the *IHO* "*S-57* Edition 3.1" standard (eg *US NGA 'DNCs'*) have been produced by a number of organisations. **These charts are NOT legally considered to be *ENCs*.**

h. **ENC Chart Symbols.** The S-57 chart symbol specification complies with the *IHO*'s S.52 Presentation Library, and allow a user-choice of *Traditional Symbols* and *Simplified Symbols* to be displayed on *ENCs*. *Traditional Symbols* are closely matched to paper chart symbols, although variations do occur. *Simplified Symbols* are usually in a more generic style and one *Simplified Symbol* may represent two features (eg 2 buoys) which have different functions. *Simplified Symbols* may vary from manufacturer to manufacturer (see manufacturers' system-specific guidance for details).

i. **Capabilities of ENCs.** *ENCs* are 'intelligent charts' and have information that can be 'interrogated' electronically by the user (eg depths - which can be used to generate automatic alarms based on crossing danger depths). The information displayed can also be adjusted by the user, by removing certain parts of the chart file from the display. The 'look and feel' of *ENCs* is quite different to paper charts / *RNC*s and users may need some time to familiarise themselves with this (see Fig 6-6 below).

j. **Additional Military Layers (AML).** *Additional Military Layers (AMLs)* are layers of extra information for military use which may be displayed over the navigational chart information provided by *ENCs* or *RNCs*. *AMLs* will NOT function correctly in a commercial *ECDIS* and should ONLY be used on *WECDIS* or other systems specifically designed to exploit them. ***AMLs* are NOT to be used as a primary aid to *Navigation*.**



ECPINS-W Sub (RN) 2005 Apr 25 13:55:46 Zulu

13:47:53 Zulu auto-loaded GB: 2793 [p02] - * Cowes Harbour

[UNDERSCALE] GB40242B - The Solent and Southampton Water

Features(S)... + 6 nm 1:127000 - FP NUP E

Hdg: (HDG1) N/A
CMG: N/A
SMG: N/A

Lat: N/A
Lon: N/A
(POS1)

EBL:
Brg: N/A
Rng: N/A
Lat: N/A
Lon: N/A

XTD: N/A
TTG: N/A

Route: N/A

WP Brg: N/A
Crs/CTM: N/A
DTG: N/A
Dest ETA: N/A
Next Crs: N/A

Cursor: N/A
Brg: N/A
Rng: N/A
Lat: N/A
Lon: N/A
TTG: N/A

Sensor: N/A
HDOP: N/A
Sats: N/A
Beac Freq: N/A
Beac Str: N/A
Beac SNR (dB): N/A
Anti-Gr: N/A

Chart-Window Title Bar
Message Line
Chart-Window Menu
Date & Time
ECPINS version
Chart-Window, with 'Auto Loaded' mix of Vector and Raster charts displayed
Vector Chart
Text Boxes
Scale Bar
Depth Unit Indication
Raster Chart
GB40242B
2036P00
2021P02
I S L E O F W I G H T
NEWPORT

Fig 6-6. A WECDIS display fitted in an RN Warship, operating ECPINS software, showing mix of Vector and Raster charts, plus other data at the left and top of the screen.

0633. RNC Raster and ENC Vector Charts - Advantages & Disadvantages

Table 6-1 (below) summarises the main advantages / disadvantages of *RNC (Raster) / ENC (Vector)* chart formats.

Table 6-1. Summary of RNC Raster / ENC Vector Chart Advantages & Disadvantages

RNC (RASTER) CHARTS		ENC (VECTOR) CHARTS	
ADVANTAGES	**DISADVANTAGES**	**ADVANTAGES**	**DISADVANTAGES**
Direct copy of existing paper chart. Contents are as comprehensive, accurate and reliable as paper charts.	Chart displays CANNOT be customised, although other information may be overlaid.	Chart information is stored in layers in a database. Users CAN customise chart displays.	Creation of ENC Vector chart database is a very complex process.
Much easier to ensure the quality and integrity of Raster data during production. Raster charts are relatively cheap to produce.	Raster file sizes are generally large and have large memory / processing requirements.	ENC Vector file sizes are generally smaller than those for Raster charts and are easier to process for display.	More difficult to ensure the quality and integrity of ENC Vector data during production. ENC Vector charts are very expensive to produce.
Same familiar colours and symbols as paper charts.	Colour palette used is limited to that for paper charts.	Larger colour palette may be used for ENC Vector charts than is used for paper / Raster charts	Symbols and colours are often different to those on paper / Raster charts
Users will not require additional training to be able to interpret the charts			Users will require additional training to ensure that ENC Vector charts are used safely
Inadvertent omission of significant navigational info from the chart display information IS NOT possible	Chart features CANNOT be interrogated or alarmed. Chart boundaries are visible.	Chart features CAN be interrogated and some features CAN be alarmed. Chart boundaries are seamless.	Inadvertent omission of significant navigational info from the chart display information IS possible.
System display parameters are relatively simple to set.	May become cluttered when zoomed or overlaid with other information.	Zooming automatically filters features shown to avoid confusion on display	Careful management of system parameters needed to ensure correct feature filtering is set
Information from other nautical publications may be displayed in the same Raster format.		Information from other nautical publications may be displayed in Raster format.	
'Official' Raster charts are available virtually worldwide			Worldwide coverage in ENC Vector charts will not be available for many years
	Charts can ONLY be displayed North-up	Charts can be displayed OTHER than North-up (eg Head-up)	
It is possible to use SOME of the ECDIS / WECDIS functionality with Raster charts.		COMPLETE ECDIS / WECDIS functionality available with ENC Vector charts.	

0634-0639. Spare

SECTION 4 - NAVIGATIONAL AND DIGITAL PUBLICATIONS

0640. UKHO Navigational and Digital Publications (NPs / DP)

The following is a list of useful *UKHO* 'Unclassified' *Navigational Publications* (*NPs*) and *Admiralty Digital Publications* (*ADP*s). BR 45 Volume 7 contains amplifying information on each *NP / ADP* **and covers 'Protectively Marked' (Classified) publications**.

NP 1-72	Admiralty Sailing Directions (Pilots)
NP 1(S)-72(S)	Supplements to Sailing Directions
NP 74 - 84	Admiralty List of Light and Fog Signals (ALLFS):Volumes A - L
NP 100	Mariner's Handbook
NP 109	NW Europe Catalogue
NP 129	Wallet With Hydrographic Forms
NP 131	Catalogue of Admiralty Charts and Publications
NP 133B	Chart Correction Log and Folio Index
NP 136	Ocean Passages for the World
NP 139	Echo Sounding Correction Tables
NP 145	Hydrographic & Meteorology Operational Guidance (HMOG)
NP 164	Dover: Times of High Water
NP 167	Tidal Streams in the Approaches to HM Naval Bases
NP 201-204	Admiralty Tide Tables
NPs 209-266, 337 & 628-636	Admiralty Tidal Stream Atlases
NP 234A / NP 234B	Cumulative List of Admiralty Notices to Mariners
NP 281	Admiralty List of Radio Signals (ALRS) Vol 1 (Parts 1 & 2) - Coast Radio Stations
NP 282	ALRS Vol 2: Radio Aids to Navigation, Satellite Navigation Systems, Legal Time Radio Time Signals and Electronic Position Fixing Systems
NP 283	ALRS Vol 3 (Parts 1 & 2):Maritime Safety and Information Services
NP 284	ALRS Vol 4: Meteorological Observation Stations.
NP 285	ALRS Vol 5: Global Maritime Distress and Safety System
NP 286	ALRS Vol 6 (Parts 1 to 5) - Pilot Services, VTS and Port Operations
NP 303	Sight Reduction Tables For Air Navigation
NP 314	Nautical Almanac
NP 320	Nories Nautical Tables
NP 323	Star Identifier
NP 350	Admiralty Distance Tables
NP 400	Sight Forms
NP 401	Sight Reduction Tables for Marine Navigation (6 Volumes)
NP 441	Guide to Completing Bridge Weather Log
NPs 713 / 715	Folio Covers
NP 718	Polythene Chart Cover
NP 720	Conversation Table - Metres to Feet / Fathoms
NP 727	Wallet Containing Ships' Boats' Charts
NP 735	IALA Buoyage System
ADP Licence	Admiralty TotalTide / Digital List of Lights / Digital List of Radio Signals

0641. Navigational & Meteorological Stores, 'RNS' Forms and Other Stationary Products

Details of current RN / RFA Navigational & Meteorological Stores, 'RNS' Forms and other stationary products are contained in BR 45 Volume 7, Appendix 2.

CHAPTER 7

CHARTWORK

CONTENTS

Para

0701. Scope of Chapter

SECTION 1 - PAPER CHARTWORK PROCEDURES

0710. Positions and Position Lines
0711. Defining Position and Plotting Bearings
0712. Calculating Positions
0713. Plotting the Track
0714. Allowance for Turning Circles in Chartwork
0715. Chartwork Planning Symbols
0716. Execution of Chartwork on Passage

SECTION 2 - DIGITAL CHARTWORK PROCEDURES

0720. WECDIS / ECDIS Chartwork
0721. WECDIS / ECDIS Check-Fixing Intervals

INTENTIONALLY BLANK

CHAPTER 7

CHARTWORK

0701. Scope of Chapter

Chartwork procedures, whether 'traditional' with a paper chart or 'electronic' with a digital system, must be clear to all who use them. Thus standard symbols should be used for all forms of chartwork, including the planning and execution of all types of *Navigation*. This chapter replaces Chapter 8 of the 1987 Edition of this book

- **Section 1.** Section 1 covers 'traditional' chartwork, using a 2B pencil on a paper chart. It also provides the foundation principles for digital chartwork.
- **Section 2.** Section 2 provides an overview of the differences to be applied to 'traditional' paper-chartwork procedures, when carrying out similar functions with *WECDIS / ECDIS / ECS* equipments and software.

0702-0709. Spare

SECTION 1 - PAPER CHARTWORK PROCEDURES

0710. Positions and Position Lines

Fig 7-1 (below) sets out the standard symbols used in the Royal Navy to display positions and *Position Lines* on paper charts. Amplifying comments are at Para 0710a-b (overleaf).


Position Line
Visual Bearing
Astronomical Observation
0705
(Arrowhead away from object)
0715
Transferred Position Line
Visual Bearing
Astronomical Observation
0803
(Arrowheads away from object)
0815
Position Line
Radar Range or Vertical Sextant Angle
1506
Fix
(Arrowheads away from objects)
0926
(Bearings)
(Arrowheads at both ends)
0957
(Ranges)
DR
0942
48
54
1000
02½
06
EP
1100
15
Position Probability Area (PPA)
Major Axis
Minor Axis
Radio Aid Fixes
0845
Appropriate suffixes to identify the navaid should be inserted where ambiguity exists [eg (L) for Loran etc]
Fixes transferred from plotting sheets or other charts
(R) 1235
(GPS) 0430
(DGPS) 0615
(L) 0615
Obs 0615
HSA 0920
Appropriate suffixes to identify the navaid should be inserted [eg (L) for Loran, (R) for Radar etc]

Fig 7-1. Positions & Position Lines (Paper Charts) - Symbols in Use in the Royal Navy

(0710) a. **Arrowheads on Position Lines.** See illustrations at Fig 7-1 (previous page).

- **Terrestrial Bearing Line.** A *Position Line* obtained from a bearing of a terrestrial object is shown with a single open arrow at the outer end.
- **Terrestrial Transferred Position Line.** A terrestrial *Transferred Position Line* is shown with a double open arrow at the outer end.
- **Astronomical Position Line or Terrestrial Range.** A *Position Line* obtained from an astronomical observation or from the range of a terrestrial object is shown with a single open arrow at both ends.
- **Astronomical Transferred Position Line.** An astronomical *Transferred Position Line* is shown with a double open arrow at both ends.

b. **Positions.** See illustrations at Fig 7-1 (previous page).

- **Fix.** A *Fix* is shown on the chart as a dot surrounded by a circle with the time alongside, with its *Position Lines* (if appropriate) passing through the position of the *Fix*. An appropriate suffix may be added to the *Fix* to indicate the navaid used if other than by visual bearings.
- **Dead Reckoning (DR).** A *Dead Reckoning* (*DR*) position is shown on the chart as a small line drawn across the course being steered, with the time alongside. A small cross may be used to originate the *DR* if a *Fix* or *Estimated Position* (*EP*) is not available.
- **Estimated Position (EP).** An *Estimated Position* (*EP*) is shown on the chart as a dot surrounded by a small triangle, with the time alongside. The estimated *Ground Track* of the ship should pass through the dot.
- **Position Probability Area (PPA).** A *Position Probability Area* (*PPA*) may be shown on the chart as an ellipse with a major and a minor axis.

0711. Defining Position and Plotting Bearings

a. **Defining a Position.** A position may be defined by its *Latitude* and *Longitude* (provided the *Spheroid* and *Datum* used are also known or specified - see Chapter 3), or as a range and bearing from a specific object. It may be plotted on the chart using a parallel rule and dividers, and with the chart's *Latitude* and *Longitude Scale*s.

b. **Method of Transferring a Position.** More serious mistakes are made when transferring a position between two charts than any other single error. When transferring a position from one chart to another, it is essential to use two methods as a cross-check on each. Normally, *Latitude* / *Longitude* is used as one method, and bearing / distance from a distinguishing feature common to both charts (eg point of land or lighthouse etc) as another. A *Fix* should be taken as soon as possible thereafter.

c. **Position Line.** A *Position Line* represents a line on the Earth's surface on which the observer is believed to lie; it may be based on observation or detection of some terrestrial or astronomical information. In its simplest form, it may be the visual bearing of a conspicuous landmark. In the context of Astro-Navigation, the term *'Position Line'* is frequently used as an abbreviation for *'Astronomical Position Line'*.

(0711) d. **Plotting a Terrestrial Position Line.** In Fig 7-2 (below) a lighthouse *L* bears 065° at 1030. A line drawn in the direction 065° passing through *L* is the *Position Line*. It is only necessary to draw the *Position Line* in the vicinity of the ship's position ('Q'), the arrowhead being placed at the outer end to indicate the direction in which the observer must lie from the observed object. Always use the nearest *Compass Rose* (Para 0624y).



Fig 7-2. Plotting a Terrestrial Position Line

e. **The Fix**. If two or more *Position Lines* can be obtained at the same time, the position of the ship is at their point of intersection and this position is known as a '*Fix*'. *Position Lines* obtained from different sources may be combined in a *Fix*.

f. **The Observed Position.** If a *Fix* is obtained by astronomical observations, it is known as an *Observed Position* and is marked with the suffix 'Obs' (see Fig 7-1).

0712. Calculating Positions

a. **DR (Dead Reckoning).** *DR* (*Dead Reckoning*) is the expression used to describe the position obtained from the true course steered and the ship's speed through the water, and from no other factors. This is normally plotted either manually or automatically (via *WECDIS / ECDIS* or plotting tables), using compass and (speed) log inputs. In the absence of a speed log input, ship's speed may be calculated from engine rpm, making due allowance for the state of the ship's bottom, weather effects etc.

b. **EP (Estimated Position).** *EP* (*Estimated Position*) is the most accurate position that can be obtained by calculation and estimation alone. It is derived from the *DR* position (course and speed steered) adjusted for the effects of *Leeway, Tidal Stream, Currents* and *Surface Drift*. An *EP* symbol may also be used to update a *DR / EP* if only one *Position Line* is available (ie one *Position Line* does NOT comprise a *Fix*).

c. **Position Probability Area (PPA).** The *Position Probability Area* (*PPA*) is derived from a combination of appropriate *Position Lines* obtained from available navigational aids (including *Speed Log* and *Gyro*), after applying the relevant statistical error correction to each *Position Line* in turn (see Paras 1622-1623). It may be shown on the chart in the form of an ellipse with a major and a minor axis (see Fig 7-1).

d. **Most Probable Position (MPP).** Within the *PPA*, the *Most Probable Position* (*MPP*) may be determined (see detailed procedures at Para 1623), which, dependent on the quality of the inputs, may be considered as a *Fix*, an *EP* or a *DR*.

(0712) e. **Leeway.** *Leeway* is the effect of wind in moving a vessel bodily to leeward at right angles to the course steered (effects of the wind in altering ship's speed through the water are subsumed within the *DR*). *Leeway* is complex and depends on:

- **Own Ship's Speed.** The higher own ship's speed, the less is the *Leeway*.
- **Wind Speed and Own Ship's Course.** The greater the component of wind speed at right angles to the course, the greater is the *Leeway*.
- **Windage and Draught.** The greater the ratio of the area above the waterline to that below (ie the draught), the greater is the *Leeway*.
- **Depth of Water.** The shallower the depth of water in relation to the draught, the less *Leeway* is made.

f. **Estimation of Leeway.** *Leeway* may exceed 2 knots in storms, particularly if the ship is at slow speed; it can only be judged by experience, assisted by any records of previous experience. Throughout history many ships have gone aground through losing more ground to *Leeward* than expected; **it is wise to allow a liberal margin for safety when passing dangers to *Leeward*, even with modern ships.**

- **Apparent Mitigation of Leeway.** When steering manually in heavy weather, an inexperienced helmsman may steer a course 2° or 3° to windward of that ordered, as most ships tend to 'fly' into wind, especially when running with a quartering wind and sea. This may compensate for the effect of *Leeway*, and may be gauged by comparing the course ordered with that recorded on automatic plotters over a period, or by close observation.
- **Leeway Vector and Leeway Angle.** As RN warships frequently proceed at different speeds, it is usual to quantify *Leeway* in terms of a *Leeway Vector* (eg 120° ½ knot). In merchant ships, which normally proceed at a set service speed, *Leeway* is normally quantified in terms of *Leeway Angle* - the angular difference between the ship's course and its track through the water.

g. **Terminology of Wind and Current / Tidal Stream Directions.**

- **Wind Direction.** Wind direction is stated as the direction from which the wind blows.
- **Current / Tidal Stream Direction.** The direction of a *Current* or *Tidal Stream* is the direction toward which the water is moving.

h. **Tidal Streams.** *'Tidal Streams'* are the **periodic horizontal** movements of the water accompanying the vertical rising and falling of *Tides* (see Para 1040). *Tidal Stream* data is provided by *UKHO* on Admiralty charts, in *ENC* databases, *Admiralty Sailing Directions* ('*Pilots*') , Admiralty Tide Tables, *Tidal Stream Atlases* and in the comprehensive '*TotalTide*®' software (see Paras 1040-1042 and 1051).

i. **Differences in Predicted / Actual Tidal Streams.** *Tidal Stream* data must always be used with caution, particularly at *Springs* and around the calculated time of change-over from ebb to flood and vice-versa. **It will often be found that the actual *Tidal Stream* experienced is different from that predicted.**

(0712) j. **Currents.** An ocean *Current* is a non-tidal movement of water, which may flow at all depths in the oceans and may have both horizontal and vertical components; a *Surface Current* can only have a horizontal component (see Para 1120). *Current* data is provided at Chapter 11 (Paras 1120-1125) of this book, and by *UKHO* on Admiralty charts, in *Admiralty Sailing Directions* (‘*Pilots*’), on Routeing charts, in Ocean Passages for the World and in The Mariner’s Handbook (see Para 0640).

k. **Estimating Surface Drift.** When wind blows over the sea surface the frictional effect tends to cause the surface water to move with the wind; this is known as *Surface Drift* (or *Surface Drift Current*). Sometimes there may be no reliable data on ocean *Currents* in a particular area, or the wind itself may be in a different to that normally prevailing and thus affecting the usual ocean *Current.* It may therefore be necessary to to make an estimate for *Surface Drift* (or *Surface Drift Current*), which may or may not be in addition to that made for *Currents*. In practice it is often difficult to distinguish between the effects of *Surface Drift* and *Leeway*. *Surface Drift* can only be estimated from experience and with a knowledge of the meteorological conditions in the area through which the ship is passing; however, the following outline parameters may be helpful.

- **Maximum Drift Speeds.** The speeds of *Surface Drifts* are variable although it has been postulated that at a maximum they can amount to 1/40th of the wind strength. This figure should be treated with caution, as it also depends on the length of time and the *Fetch* involved (the extent of open water over which the over which the wind has been blowing).
- **Build up of Surface Drift.** The build-up of *Surface Drift* in response to wind is slow and a steady state takes some time to become established. With light winds the slight *Current* resulting may take only about 6 hours to develop, but with strong winds about 48 hours is needed for the *Current* to reach its full speed. Hurricane force winds may give rise to a *Surface Drift* in excess of 2 knots, but it is rare for such winds to persist for more than a few hours without a change in direction. The piling up of water caused by a storm near a coastline may lead to particularly strong *Surface Drift* parallel to that coast.
- **Surface Drift Direction.** The effect of the rotation of the Earth (Coriolis force) is to deflect water movement to the right in the Northern Hemisphere and to the left in the Southern Hemisphere. This produces a direction of the *Surface Drift* inclined at some 20˚ to 45˚ to the right of the wind direction in the Northern Hemisphere and to the left in the Southern Hemisphere.
- **Example.** If, for example, the wind has been blowing steadily from the north-east (045˚) at 20 knots for several days, the rate and direction of the *Surface Drift* in the Northern Hemisphere may be expected to be of the order of ½ knot in a direction between 225˚+20˚= 245˚ and 225˚+45˚= 270˚.

m. **Set and Drift - Definitions.** See Para 0713c (overleaf).

0713. Plotting the Track

a. **Plotting the Estimated Position (EP).** Plotting the *EP* from an initial *Fix* is carried out in two steps (see Fig 7-3).

- **Step 1.** Plot the *DR* position (course steered / speed through the water).
- **Step 2.** Plot the EP from the *DR* position by plotting the effect of:
  - *Leeway*
  - *Tidal Stream*
  - *Current*
  - *Surface Drift*


N
DR
Leeway Vector
Tidal Stream
Current
Surface Drift
Sea Position
Drift
EP
Water Track
Course Steered
Ground Track
Leeway Angle
Initial Fix
Drift Angle
Note. Effects of Leeway, Tidal Stream, Current and Surface Drift have been exaggerated for clarity.

Fig 7-3. Plotting the Estimated Position (EP) - (*Diagram exaggerated for clarity*)

b. **Terms and Definitions.** Fig 7-3 also displays the terms and symbols used in the calculation of the *EP*. Those not already defined are at Table 7-1 (below).

Table 7-1. Terms, Symbols and Definitions used for Construction of an EP

Term or Symbol	Definition and/or Use
Single Arrowhead	Course steered, Water Track (Track through the water), Leeway Vector.
Double Arrowhead	Ship's Ground Track (Track over the Ground / Course made good).
Treble Arrowhead	Tidal Stream, Current, Surface Drift and Drift
Track	The path followed or to be followed, between one position and another. It may be the Ground Track, Water Track, Relative Track or a True Track.
Track Angle	The direction of a Track.
Track Made Good	The mean Ground Track actually achieved over a given period.
Set	The resultant direction towards which Current, Tidal Stream and Surface Drift flow.
Drift	The distance covered in a given time due solely to the movement of Current, Tidal Stream and Surface Drift.
Drift Angle	The angular difference between the Ground Track and Water Track.
Sea Position	The point at the termination of the Water Track.

(0713) c. **Set and Drift - Definitions.** *Set* and *Drift* result from the combined effects of *Tidal Stream, Current* and any *Surface Drift*. *Set* and *Drift* are defined as direction and distance respectively (eg 103˚ 3.5'). *Drift* may also be expressed as *Drift Rate* in knots (eg if the time over which the drift of 3.5' has been determined is 2 hours, the *Drift Rate* would be 1.75 knots [ie *Drift* 3'.5 or *Drift Rate* 1.75 knots]).

d. **Practical Examples of Calculations.** Four practical examples of *Tidal Stream* calculations follow; the same method of solution applies to problems associated with *Leeway, Current* or *Surface Drift*. The fifth (final) example involves all four factors.

Example 7-1. Find the course to steer, allowing for Tidal Stream.
Find the course to steer at 12 knots, to make good 090˚ if the *Tidal Stream* is 040˚ at 3 knots?

- Lay off the *Ground Track* (course to make good - *AB* in Fig 7-4 below). From *A* lay off the direction of the *Tidal Stream* AC. Choosing a suitable *Scale*, mark along *AC* the distance *AD* that the *Tidal Stream* runs in any convenient interval. In Fig 7-4 an interval of 1 hour has been allowed: thus, *AD* will be 3 miles.
- With centre *D* and radius equal to the distance the ship runs in the same interval (ie 12 miles), and on the same *Scale*, cut *AB* at *E*. Then *DE* (101˚) is the course to steer. *AE* (13.7 miles) is the *Ground Track* distance in an 090˚ direction in 1 hour.



Fig 7-4. Find the Course to Steer, Allowing for Tidal Stream (*Not to Scale*)

Example 7-2. Find the course to steer and speed required, to make an ETA.
Find the course to steer and speed required, to proceed from *A* to position *B* (15 *n.miles*) in 1½ hours, allowing for a *Tidal Stream* setting 150˚ at 3 knots?

- Join *AB*, as shown in Fig 7-5 (below). Measure the *Ground Track* and distance required in 1½ hours (eg 090˚ 15'); thus, the *Ground Speed* required is 10 knots. Mark a position *D* along *AB* using a convenient time interval depending on the *Scale* of the chart (eg1 hour; in this case *AD* will be 10 miles).
- From A lay off the *Tidal Stream AC* for the same interval (ie 150˚ 3'). Join *CD*. *CD* will give the course (073˚) to steer and the speed (8.9 knots) required.



Fig 7-5. Find the Course to Steer and Speed Required, to make an ETA (*Not to Scale*)

(0713d continued)

Example 7-3. Find the time to pass an object at a given distance, allowing for Tidal Stream. A ship at *A* (see Fig 7-6 below) steers to clear a lighthouse '*L*' by 2 miles, allowing for a *Tidal Stream* setting 345˚. Show the method to calculate the time when the lighthouse *L* be abeam.

- From *L* draw the arc of a circle, radius 2'. From the ship's present position draw a tangent to the arc. This is the *Ground Track* required, *AD*.
- Find the course to steer *BC* by the method at Example 7-1. The light is abeam when 90˚ from the course steered (ie when the ship is at *E*, not at *D* which is the *Closest Point of Approach* [CPA] - 2 miles). The time will be that taken to cover the distance *AE* at a speed represented by *AC*, which is the *Ground Speed*.



Fig 7-6. To find the time to pass an object at a given distance, allowing for Tidal Stream
(*Not to Scale - Diagram exaggerated for clarity*)

Example 7-4. Find the direction and rate of the Tidal Stream between two Fixes. A ship is at *A* at 0100 (see Fig 7-7 below), and steers 110˚ at 10 knots. At 0300 it is *Fixed* at *B*. What is the direction and rate of the *Tidal Stream* from 0100 to 0300?

- Plot the ship's course 110˚ for a distance of 20' from *A*.
- The difference between the *DR* position *C* and the *Fix B* at 0300 gives the direction of the *Tidal Stream CB* (025˚) and the distance it has displaced the ship in 2 hours (7.6 miles). From this data the *Tidal Stream* may is as 025˚ at 3.8 knots.



Fig 7-7. To find the direction and rate of the Tidal Stream between two Fixes
(*Not to Scale - Diagram exaggerated for clarity*)

(0713d continued)

Example 7-5. Find the EP allowing for Leeway, Tidal Stream, Current and Surface Drift.

The ship is *Fixed* at 0700, on an ordered course of 090˚, speed 15 knots. At the end of 1 hour, course steered recorded by automatic plotting is 090½˚, speed through the water from the log is 14.7 knots (allowing for calibration errors). Estimated *Tidal Stream* (from tables) is 295˚ 1.5 knots. Estimated *Current* (from routeing charts) is 060˚ 0.75 knots.

The wind has been blowing steadily in the area from the south at about 20 knots over the past 2-3 days. *Leeway* as deduced from the data in the Navigational Data Book is ¾ knot. Plot the *EP* after 1 hour, and calculate the estimated *Ground Track* / *Ground Speed* (course / speed made good), and the *Set / Drift* from the combined effects of *Tidal Stream, Current* and *Surface Drift*. The ship is in the Northern Hemisphere. From a study of the area and the data available it is estimated that *Surface Drift* will be in addition to the predicted *Current*.

- The *Leeway Vector* will be perpendicular to the course steered; thus, in this case it will be 000½˚ ¾ knot. (The *Leeway Angle* is 3˚.) Estimated *Surface Drift* will be 020˚ to 045˚ ½ knot; allow for 030˚.
- Plot the *DR* position *B* at 0800 from the course steered 090½˚ at the speed through the water 14.7 knots (*AB* in Fig 7-8 below). (Hint: to achieve 090½˚, lay the parallel rule through 091˚ and 270˚ on the compass rose).
- Plot the *Leeway BC*, 000½˚ 0.75 knot (Hint: lay parallel rule through 000˚and 181˚ on the compass rose).
- Plot the *Tidal Stream CD*, 295˚ 1.5 knots.
- Plot the *Current DE*, 060˚ 0.75 knot.
- Plot the *Surface Drift EF*, 030˚ 0.5 knot.
- *F* is the *EP* at 0800, *AF* is the estimated *Ground Track* / *Ground Speed* (course and speed made good over the ground) and *CF* is the estimated *Set* and *Drift*.
- The estimated *Ground Track* / *Ground Speed* is 082˚ 14.4 knots; the *Set* and *Drift* are estimated to be 343˚ 1.5 miles, rate 1.5 knots.



Fig 7-8. To find the direction and rate of the Tidal Stream between two Fixes
(*Not to Scale - Diagram exaggerated for clarity*)

0714. Allowance for Turning Circles in Chartwork

During chartwork for *Pilotage* and some *Coastal Navigation*, it is necessary to plot the '*Wheel-Over*' position as well as the *Waypoint* where tracks meet. To do this, knowledge of the ship's *Turning Circle* is necessary. Use of *Turning Circle*s and the *Manoeuvring Data* trials necessary to establish it are covered in detail in BR 45 Volume 6 (Shiphandling) Chapter 1, but a brief summary is repeated here. *Manoeuvring Data* trials are conducted for all classes of RN warships and the results are contained in the Navigation Data Book for each ship.

a. **Calculation, Monitoring and Control of Turns.** The path followed by the Bridge of most RN warships turning with headway closely approximates that taken by the *Pivot Point*, and this makes the Bridge an ideal position from which to plan, monitor and control turns. As the *Manoeuvring Data* supplied is intended for use from the Bridge position of RN warships, this allows turns to be planned and executed with precision.

b. **Transfer**. The *Transfer* for a specific alteration of course is **the lateral distance moved in a direction at right angles to the original course.** In Fig 7-9 (opposite), distance *QC* is the *Transfer* for an alteration of 60°. When calculating the *Wheel-Over* position for a specific alteration of course, ***Transfer* is the first measurement that should be plotted** (as shown by the line *QC* in the 60° turn example at Fig 7-9).

c. **Advance.** The *Advance* for a specific alteration of course is **the distance moved in the direction of the original course** from the *Wheel-Over* position to the point where the ship steadies on her new course. In Fig 7-9 (opposite), the distance *AQ* is the *Advance* for an alteration of 60°; in this example, should be measured back from position Q (obtained from plotting the *Transfer*) to obtain the *Wheel-Over* position at *A*.

d. **Distance to New Course (DNC).** *DNC* is the distance along the original course from the *Wheel-Over* position to the point of intersection between the new and old courses. In Fig 7-9 (opposite), distance *AL* is the *DNC* for an turn of 60°. *DNC* is of little use for *Pilotage* and is misleading for turns over 120°; it is thus little used.

e. **Intermediate Course and Intermediate Distance**. The *Intermediate Course* and *Intermediate Distance* are the direction and distance respectively between the *Wheel-Over* position on the original course and the point where the ship steadies on the new course. *Intermediate Course* and *Intermediate Distance* for a 120° alteration are shown Fig 7-9 by the angle RAE and the distance AE. Plotting the *Intermediate Course* and *Distance* does NOT give the position at which the ship steadies on the new course.

f. **Times of Turning.** The times taken for alterations of course under different speeds and rudder angles are also given in the *Manoeuvring Data* for RN warships. They are normally provided in minutes and seconds and are useful for certain manoeuvres.

g. **Tactical Diameter.** The *Tactical Diameter* (shown by distance PF in Fig 7-9) is the distance moved at 90° to the original course after turning through 180°. *Tactical Diameter* does increase slightly with speed, but only by a relatively small amount.

h. **Final Diameter (Steady Turning Diameter).** The *Final Diameter* (also known as the *Steady Turning Diameter*) is the diameter of the *Turning Circle* when the ship is turning at a steady rate. It is shown by distance TU in Fig 7-9 (opposite).

(0714 continued)


Transfer (QC)
(60° turn)
R
Q
L
60°
C
D
E
(120° turn)
U
Intermediate Distance for 120° turn
Final Diameter (Steady Turning Diameter)
Tactical Diameter
P
F
H
Advance (AC) - (60° turn)
DNC (AL) - (60° turn)
A
Wheel-over (A)
T
G
Intermediate Course for 120° turn

Fig 7-9. A Turning Circle showing, Transfer, Advance, Distance to New Course, Intermediate Course, Intermediate Distance, Tactical Diameter and Final Diameter

(0714) i. **Allowance for Loss of Speed in Turns.** Ships inevitably lose speed in turns, and it is sometimes necessary to adjust the *DR* time for this. Automated systems (eg *WECDIS / ECDIS / ECS* etc) have log speed and/or *GPS* inputs, and thus will normally allow for this automatically. *Manoeuvring Data* for RN warships includes an '*Acceleration Distance*' in yards per knot (also known as '*Speed Factor*'). To make the adjustment to a manual chart *DR*, multiply the *Acceleration Distance* by the speed in knots lost in the turn; convert this distance into time at the original speed and add this 'time correction' to the *DR* time at which the ship is calculated (from *Advance / Transfer* and '*Duration of Turn*' figures) to steady on the new course. A table of such 'time corrections' may easily be constructed for turns at various speed and rudder angles. This technique may also be applied to speed changes on the same course. In practice, application of this manual 'time correction' is rarely necessary, but the calculation is available if such precision is needed.

Example 7-6. A ship with an *Acceleration Distance* of 60 yards/knot alters course at 15 knots and loses 3 knots in the turn. On steadying, the ship's manual *DR* at 15 knots will be in error by a time equivalent to a distance at 15 knots of 3 x 60 = 180 yards. At 15 knots this distance equates to approximately 21½ seconds, which should be added to the manual *DR* time.

(0714) j. **Warships Manoeuvring in Groups.** When warships are manoeuvring together in groups, it can be difficult to apply *Manoeuvring Data* manually to the many bold alterations of course and speed occurring in quick succession, in order to maintain an accurate *DR*. Possible solutions to achieve an accurate *DR* are:

- Use automatic plotting facilities (eg *WECDIS / ECDIS* etc) to maintain the *DR* position and to provide frequent / continuous *Fixing*.
- Establish the Guide's position on the chart, *DR* it on (at what will normally be a track with fewer alterations of course and speed than warship consorts), and plot own ship at intervals from the Guide. *Fix* frequently to update the *DR*.

k. **Manoeuvring Data in Merchant Ships.** *Manoeuvring Data* in merchant ships is usually sparse, and often confined to the *IMO* minimum requirement (currently one hard turn port and one hard turn starboard at full rudder and one crash stop, all at maximum manoeuvring speed). In addition, due to different upper deck configurations and cargo loadings, the *Pivot Point* may be far displaced from the Bridge, thus making it difficult to plan and execute turns with the precision normally expected of an RN warship.

0715. Chartwork Planning Symbols

At the planning stage, the following symbols should be used for chartwork on paper charts (see Fig 7-10 opposite). *Blind Pilotage* symbols are at Para 1316. Symbols used with *WECDIS / ECDIS* equipments, although based on the paper chart equivalent, may vary widely depending on the system facilities available. See details at Para 0720.

a. **Planned Track.** Draw the planned track boldly, writing the course along the track with the course to steer in brackets alongside and the speed in a box, north orientated, underneath. The figures for course and speed should be sufficiently far away from the track to permit the necessary chartwork. See Fig 7-10a (opposite).

b. **Tidal Stream.** Indicate the expected *Tidal Stream*, showing the direction by a triple arrowhead, the rate in a box, and the time at which it is effective. See Fig 7-10b.

c. **Currents.** Indicate the expected *Current* (or *Surface Drift*), showing the direction by a single arrowhead on a 'wavy' line and the rate in a box. See Fig 7-10c (opposite).

d. **Wind.** Show the expected wind with direction and speed in a black arrow-headed box (do not confuse with a magenta 'Direction of Buoyage' symbol). See Fig 7-10d.

e. **Dangers.** Emphasise dangers near the track by outlining them boldly in pencil (or coloured ink for often-used charts). The *Limiting Danger Line* (*LDL*) depth ('*No Go Line*') should ALWAYS be drawn to show the navigable channel; this will vary with the *Height of Tide* (*HOT*) and should NOT be inked-in. See Fig 7-10e (opposite).

f. **Clearing Bearings.** Draw *Clearing Bearings* boldly, using solid arrowheads pointing to the object. 'NLT ...' (Not Less Than ...) or 'NMT ...' (Not More Than ...) should be written alongside. *Clearing Bearings* should be drawn sufficiently clear of the danger so that the ship is still safe even if the Bridge is on the *Clearing Bearing* line but turning away from danger. Allow for the Bridge being on the line with the stem or stern on the dangerous side of it, whichever is the greater distance. See Fig 7-10f (opposite).

g. **Distance to Run.** Indicate the distance to run to the destination, rendezvous, etc. Numbers should be upright. See Fig 7-10g(opposite).

(0715 continued)


065° (063°)
15
a. Planned Track
1020
¾
b. Tidal Stream
¾
c. Current / Surface Drift
18
d. Wind
1 4
R
064° (067°)
e. Dangers
NMT 088°
f. Clearing Bearings
80M
60M
g. Distance to Run (Sea Miles)
20/1200
h. Planned Position and Time
0557 Sunrise
1809 Sunset
100°
15
i. Sunrise and Sunset
085°
Ushant Lt Fl(2) W 10s
j. Visual Limits of Lights
090°
WO(25)
085
1207
070°
10
10
k. Position and Time of 'Wheel Over'
Chart 1402
1900
090°
2000
10
Chart 1127
120°
10
m. Change of Charts

Fig 7-10. Chartwork Planning Symbols

(0715) h. **Planned Position and Time.** Indicate the time it is intended to be at particular positions at regular intervals, using 'bubbles' close to but clear of the track (ie '*Bubble Times*'). Ocean passages are normally marked every 12 hours and coastal passages more frequently, every 2 or 4 hours. See Fig 7-10h (above).

i. **SunRise and SunSet.** Indicate the times of *SunRise* (*SR*) and *SunSet* (*SS*)at the expected positions of the ship at those times. See Fig 7-10i (above).

j. **Visual Limits of Lights.** Indicate the arcs of the visual limits of lights that may be raised or dipped – the rising/dipping range. See Fig 7-10j (above).

k. **Position and Time of 'Wheel-Over'.** Show position and *DR / EP* time of '*Wheel-Over*' for alterations of course as a 4-figure time. The amount of wheel can be stipulated if this differs from standard. See Fig 7-10k (above).

m. **Change of Chart.** The positions of changes of chart should be indicated by double parallel lines, either vertical or horizontal. See Fig 7-10m (above).

0716. Execution of Chartwork on Passage

*Extracts of Paras 0716b/c are repeated at Paras 1231f/h and 1313a.

a. **Fixing.** Methods of *Fixing* the ship are at Chapter 8. With a sound plan, regular visual / radar *Fixing* has traditionally been the foundation of all *Coastal Navigation*, but this is now being supplanted by continuous *GPS / DGPS Fixing* with automatic *WECDIS / ECDIS* position displays. Although *WECDIS / ECDIS* give the Officer of the Watch (OOW) more time for other tasks (such as lookout), it is essential to make independent position checks at frequent intervals (see Para 0721).

b*. **Fixing and Comparison with DRs / EPs.** A *DR* (or *WECDIS / ECDIS* equivalent) from the last *Fix* should always be maintained ahead of the ship and an *EP* should be derived from all available information (ie *Leeway, Tidal Stream, Current*). Use of a *DR* alone may be acceptable when these factors are insignificant, **otherwise, an *EP* should ALWAYS be generated.** As soon as a new *Fix* is obtained, it should be compared with the *DR / EP* to ensure that there has been no mistake, to estimate the strength and direction of any *Tidal Stream* or *Current* since the last *Fix*, and to assess any actions needed. Generate a new *DR / EP* after an alteration of course.

c*. **Paper Charts - Frequency of Fixing.** The frequency of *Fixing* on paper charts should, in principle, depend on the distance from navigational hazards and the time the ship would take to run into danger before the next *Fix*; it is thus at least partly speed-dependent. The decision on the frequency of *Fixing* is ultimately for the CO and is usually specified in Captain's Standing Orders, although may be delegated to the NO or OOW. Useful 'Rules of Thumb' for *Fixing* on paper charts are:

- **Ocean Navigation - Fixing.** The frequency of *Fixes* will depend on the availability of position data (ie *GPS, LORAN-C / eLORAN*, astronomical observations, long range radar *Fixes* etc) and the distance from danger.

- ***Coastal Navigation - Fixing.** A useful *Coastal Navigation Fixing* 'Rule of Thumb' at 12-15 knots is as follows, although the actual *Fixing* interval chosen MUST be selected according to the circumstances prevailing:
    - *Fix* every 5 miles (approx) when navigating well offshore on a 1:150,000 coastal chart.
    - *Fix* every 2½ miles (approx) when coasting closer inshore on a 1:75,000 chart.
    - *Fix* every 1 mile (approx) when approaching a port using a 1:20,000 chart.
    - 6 minute intervals between *Fixes* are convenient for converting distance to *Ground Speed*, as 6 minutes is one-tenth of an hour (ie 1.35 miles in 6 minutes equals13.5 knots *Ground Speed* [speed made good]).

- **Fix Timing.** Every *Fix* should be timed to coincide with the *DR / EP* time, in order to check for unexpected position differences (see Para 0716b above).

- ***Pilotage.** In *Pilotage*, check *Fixes* should be plotted at least once per leg, and at intervals of not more than 6 minutes on long legs.

d. **WECDIS / ECDIS - Frequency of Check Fixing.** See Para 0721.

(0716) e. **Speed Calculations.** *Ground Speed* (speed made good) may be calculated from the distance run between *Fixes*, or estimated from predicted *Leeway, Tidal Stream, Current* and *Surface Drift*. Actual or estimated *Ground Speed* should always be used when projecting the *EP* ahead. *Ground Speed* is liable to fluctuate when any sea is running, also when the strength or direction of the *Tidal Stream* is changing.

f. **Chart Precautions.** Keep only one chart on the chart table, to avoid the error of measuring distances off the *Scale* of a chart underneath the one in use.

g. **Time Taken to Fix Manually.** The time taken to note the bearings and the time, plot the *Fix* on the chart, check the *DR* and lay off further *DR / EP*, verify time to '*Wheel-Over*' (if applicable), and return to lookout should not be more than 2 minutes at the most. A practised OOW should be able to complete the task within 60 seconds. If it is essential to reduce the *Fixing* time further, an assistant or a team should be used. Using an assistant, the time can be reduced to less than 30 seconds.

h. **Navigational Records.** Full details of the navigational records required in the RN / RFA are at BR 45 Volume 4. A summary is repeated here and amplified at Para 1238.

- **Navigational Record Book.** When any *Navigation* is being 'Executed', *Fixes* and alterations of course and speed, together with other information (see details at Para 1238) are entered in the *Navigational Record Book* (RNS 3034). The officer 'Executing' the *Navigation* keeps this record, but the NO has overall responsibility for supervising the OOWs to enter accurate and complete information. Care should always be taken to record times accurately as this is usually the single most difficult element when reconstructing the ship's track. The book's format is designed for entries to be made easily (see Fig 7-11) and the following symbols may be employed:

∅	Transit
⇤	Left-hand edge (of land, etc)
⇥	Right-hand edge (of land, etc)
⊥ Port (5c)	Abeam to port (5 cables)
⊥ Stbd (1'.2)	Abeam to starboard (1.2 miles)



DATE	*15th June*		WATCH *Forenoon*	OOW *AGD*
TIME	CO	SP	REMARKS	
0900	*090*	*15*	*Fidra ∅ Bass Lt. 089½°*	
			Elie Ness Lt. 047°	
			⇤ E WEMYSS 344°	
0915	*090*		*North Carr Lt. 335°*	
			Balcombe Tr. 279°	
			Fidra 243°	

Fig 7-11. The Navigational Record Book

- **The Ship's Log.** The NO has charge of the *Ship's Log* (RNS 0322) and is responsible for seeing that it is properly compiled in accordance with the instructions given inside the front cover. In particular, it should contain an extract of positional information from the *Navigation Record Book*.

0717-0719 Spare.

SECTION 2 - DIGITAL CHARTWORK PROCEDURES

0720. WECDIS / ECDIS Chartwork

Standard symbols to be used for chartwork on paper charts were specified at Paras 0710 and 0715, with *Blind Pilotage* paper chart symbols at Para 1316. Symbols used with *WECDIS / ECDIS* equipments, although based on the paper chart equivalents, may vary widely, depending on the system facilities available. One significant difference with most *WECDIS / ECDIS* equipments is that text labels are written horizontally and cannot normally be rotated parallel with a bearing line (eg *Clearing Lines* [ie *Clearing Range / Clearing Bearing*] or a 'Route' [Track] line). Paras 0720a-e with Figs 7-12 to 7-15 provide **some illustrative examples** of RN *WECDIS* chartwork, to provide an indication of current RN *WECDIS* symbology. A summary of *WECDIS / ECDIS / ECS* and *Electronic Chart* capabilities and limitations is at Paras 0630-0633. Full details are at BR 45 Volume 8.

a. **RN and RFA WECDIS / ECDIS Equipments.** In the RN / RFA, 'ECPINS' software (created by OSL Ltd) is installed on *WECDIS* terminals. This software provides comprehensive facilities to display automatic and manual chartwork symbols which are reasonably close to those specified for paper charts. A few older *ECDIS* systems are also fitted to some RFAs, and these have significantly less functionality and capability in symbology than *WECDIS* equipments.

b. **WECDIS - Safety Depth Contour and Interpolated Depth Contours.** On (*Vector*) *ENCs*, *WECDIS* is capable of higlighting a selected 'Safety Depth Contour' and drawing mathematically created intermediate interpolated depth contours, to assist with manual creation of the *Limiting Danger Line* (*LDL*). In addition *WECDIS* can display prominent 'Shallow Danger Marks' to highlight isolated dangers inside 'Safety Depth Contour'. See Fig 7-12 (below)


Lat: N/A
Lon: N/A
(POS1)
EBL:
Brg:
Rng: N/A
Lat:
Lon:
XTD: N/A
TTG:
Route:
WP Brg: N/A
Crs/CTM: N/A
DTG:
Dest ETA:
Next Crs:
Cursor: N/A
Brg: N/A
Rng:
Lat:
Lon:
TTG:
Sensor:
HDOP:
Sats: N/A
Beac Freq: N/A
Beac Str: N/A
Beac SNR (dB): N/A
by Irvine Bay-D
by Irvine Bay-C
Fl(1)Y 10
Fl(1)Y 5
by Irvine Bay-B
1866P02
by 1B-A1
R 2s3M

'Shallow Danger Marks' (ON), indicate isolated dangers inside Safety Depth Contour (20m)

'Interpolated Depth Contours' providing realistic indications

'Interpolated Depth Contours' providing doubtful indications

Safety Depth Contour (20m) (Safety Depth set at 12m)

'Shallow Danger Marks' (ON), indicate isolated danger (wreck) in otherwise deep water, inside Safety Depth Contour (20m)

Fig 7-12. Example WECDIS Symbology - 'Safety Depth Contour', 'Interpolated Depth Contours' and 'Highlight Shallow Dangers'

(0720) c. **WECDIS - Route Display Options.** *WECDIS* can display the 'Active Route' (Track) and 'Track Labels'(with predicted *Set* and *Drift* plus 'Course to Steer'), the 'Active Leg' within that 'Route', *Wheel-Overs* and a *Wheel-Over* line, a 'Cross Track Distance' (XTD) 'Alarm Corridor' (which alarms if 'Own Ship' strays outside it), '*Waypoints*' and '*Waypoint* Labels', as well as 'Own Ship' itself and an 'Anti-Grounding Cone'(AGC). All items are user-selectable for display. See Fig 7-13 (below).


CMG: 286.8°T
SMG: 15.5 kt
Lat: 55° 19.655' N
Lon: 005° 03.532' W
(DR) 50.0-100.0 m
SLog: (SPD1) N/A
Depth: (DEP1) N/A
Wind: (1) N/A
Drift: 1.0 kt
Set: (ORD) 230.0°T
RoT: N/A
EBL:
Brg: N/A
Rng: N/A
Lat: N/A
Lon: N/A
Route: test1
WP Brg:
XTD:
Crs/CTM: 2
DTG:
TTG: 00:45:42
Dest ETA: Feb 03 11:36
Next Crs: 355.3°T
Cursor: 50.0-100.0 m
Next Leg (Inactive)
Active Leg
XTD Alarm Corridor
Wheel-over Line
Track Label (Planned Speed)
Anti-Grounding Cone
Own Ship
Waypoint Label (PIM DTG, HOT and Predicted Set & Drift)
Track Label (Planned Course)
Track Label (Course to Steer)
Track Label (Predicted Set & Drift)
005 / 360 °T [S&D: 1.0 kt@230.0°T]
PIM: Jun 23 11:50:06
HoT: +3.0 m
S&D: 1.0 kt@230.0°T
293 / 298 °T [S&D: 1.0 kt@230.0°T]
10.0
10.0
10.0
10.0
wp 1
wp 3
wp 4
148 / 1
209 /

Fig 7-13. Example WECDIS Symbology - 'Route Display Options'

d. **WECDIS - Anti-Grounding Cone.** *WECDIS* provides an 'Anti-Grounding Cone' with user-selectable parameters, and which alarms against nominated dangers and certain features (see Fig 7-14a below). The 'Anti-Grounding Cone' (AGC) bends around *Waypoints* provided 'Own Ship' is inside the 'XTD Warning Corridor' (see Fig 7-14b below).


Own Ship
XTD Alarm Corridor (Port)
Active Leg of Active Route
AGC
Dangerous Wreck
XTD Alarm Corridor (Stbd)
wp 1
0736
8.0
180°T
45
wp 2
133°T
8.0
wp 3

Fig 7-14a. Anti-Grounding Cone (AGC) and XTD Alarm Corridor


Anti-Grounding Cone, bending at Waypoint *(provided Own Ship inside XTD Warning Corridor)*
XTD Alarm Corridors (Stbd)
XTD Alarm Corridors (Port)
Anti-Grounding Cone will alarm when it reaches Dangerous Wreck
wp 1
0736
8.0
180°T
45
wp 2
132°T
8.0
wp 3

Fig 7-14b. AGC bending at Waypoint if Own Ship is inside XTD Warning Corridor *(Warning Corridor not shown in diagram)*

(0720) e. **WECDIS - Radar Image Overlay and 'Ghost Ship'.** A '*Radar Image Overlay*' (*RIO*) can be superimposed over the *WECDIS* chart display for checking that the radar coastline and other features (shown in **GREEN** at Fig 7-15 below) are in alignment with the chart (ie *GPS* has not slipped). *WECDIS* can also display a 'Ghost Ship' positioned at a user-selectable distance ahead of 'Own Ship'. *Para 0720e is repeated at Para 1528.*


ECPINS-W Sub (RN) 2005 Apr 19 11:38:44 Zulu
GB: 30 [p00] - * Plymouth Sound and Approaches
RIO coastine echo (green)
RIO buoy echos (very feint green)
Clearing Bearing
Limiting Danger Line
RIO radar clutter (green) around Own Ship
Own Ship
'Ghost Ship'
NMT 4.0°
NMT 75.0°
NLT 276.3°
170°T
Better Positioning Source Available

```
Hdg: (HDG2) 229.8°T
CMG:        230.0°T
SMG:        15.0 kt
Lat:     50° 18.364' N
Lon:    004° 11.147' W
(POS4)       RCDS Mode
EBL:
Brg:               N/A
Rng:               N/A
Lat:               N/A
Lon:               N/A
XTD:S   0.548 nm
TTG:    00:19:34
Route:    Plymouth Out
        wp 10 to wp 11
WP Brg:        157.5°T
Crs/CTM: 170.0/161.5°T
DTG:           2.46 nm
Dest ETA: Apr 19 11:58
Next Crs:          N/A
Cursor:   Raster Chart
Brg:           191.2°T
Rng:          0.217 nm
Lat:     50° 18.155' N
Lon:    004° 11.201' W
TTG:          00:00:52
Sensor:        3D DGPS
HDOP:             1.40
Sats:          7 of 11
Beac Freq (kHz):   N/A
Beac Str:          N/A
Beac SNR (dB):     N/A
Anti-Gr:            OK
```

Fig 7-15. Example WECDIS Symbology - Radar Image Overlay (RIO) & 'Ghost Ship' (*RIO shown as a Green Image*)

0721. WECDIS / ECDIS Check-Fixing Intervals (**Extracts repeated at Paras 1231g/1313a*)

*For the purposes of check-*Fixing* in *WECDIS / ECDIS*, in the RN, *'Coastal Navigation'* is deemed (depending on circumstances and the size of vessel involved) to be *Navigation* at distances between about 2 *n. miles* and 15 *n. miles* from the *Limiting Danger Line* (*LDL*); *'Ocean Navigation'* is deemed to be *Navigation* at distances greater than 15 miles from the *LDL*. RN *WECDIS / ECDIS* check-*Fixing* intervals are as follows. See BR 45 Volume 8(1) for details.

a **Ocean Navigation.** In *Ocean Navigation*, the interval between manual check *Fixes* should not be greater than 30 minutes.

b*. **Coastal Navigation.** In *Coastal Navigation*, the interval between manual check *Fixes* should not be greater than 30 minutes, but a *RIO* coastline alignment check should be carried out (subject to emission policy) at not more than 15 minute intervals between *Fixes*.

c*. **Pilotage.** In *Pilotage*, check *Fixes* should be plotted at least once per leg and at intervals of not more than 6 minutes on long legs.

CHAPTER 8

VISUAL FIXING

CONTENTS

Para

0801. Scope of Chapter
0802. Azimuth Circles for Visual Bearings
0803. Methods of Obtaining a Position Line
0804. Transferred Position Lines
0805. Fixing Techniques - Summary of Methods
0806. Running Fixes
0807. Selection and Use of Visual Fixing Marks
0808. Horizontal Sextant Angle (HSA) Fixes
0809. Bearing Lattice Fixes
0810. HSA Fixing Procedures
0811. Adjustment of Fixes for Compass Errors
0812. Action on Obtaining a Cocked Hat

INTENTIONALLY BLANK

CHAPTER 8

VISUAL FIXING

0801. Scope of Chapter

This chapter builds on the principles established at Chapter 7 (Chartwork) and covers all aspects of *Fixing* a vessel's position by visual means. It replaces Chapter 9 of the 1987 Edition of this book. Radar *Fixing* is at Chapters 12, 13 and 15, as appropriate to the context.

0802. Azimuth Circles for Visual Bearings

A variety of bearing taking equipments (of greater or lesser ease of use) are found at sea, but most rely on some sort of prismatic *Azimuth Circle* fitted on a compass repeater.

a. **Admiralty Pattern Azimuth Circle.** The 'standard' Admiralty Pattern *Azimuth Circle* (see Fig 8-1 below) is easy to use and is accurate in all conditions. It uses a curved prism; thus if the object is seen through the ' V 'sight, the correct bearing is read, even if the *Azimuth Circle* itself is not aligned to the object (see Fig 8-2 below). A line is engraved on the face of the prism to assist reading of the bearing. Reflections of high altitude objects on the black mirror are sighted through the ' V 'sight; for this, the bubble level is used to keep the *Azimuth Circle* horizontal. The alignment of the *Lubbers Line* to ship's head should be checked frequently and adjusted if necessary (see Para 1230f).


Black Reflecting Mirror
Sighting 'V'
Curved Prism
Shade Glasses
Lubbers Point / Line
Azimuth Circle
Support Bracket (includes a Bubble Level)
Verge Ring
Compass Card
Binnacle (or 'Pelorus' if at Primary Conning Position)

Fig 8-1. The 'Standard' Admiralty Pattern Azimuth Circle


350°
000
350°
000

Fig 8-2. The Admiralty Azimuth Circle (does not need to be aligned to the object)

b. **Other Azimuth Circles.** Other designs of *Azimuth Circle* are often awkward to use and do not produce sufficiently accurate results, particularly in difficult conditions.

0803. Methods of Obtaining a Position Line

Although *Fixing* by *DGPS / GPS* is the norm, it may be necessary on occasion to use other means. A single *Position Line* (as opposed to a *Fix*) may be obtained from:

- **Compass Bearing (also radar bearings).** See details at Para 0803a.
- **Relative Bearing.** See details at Para 0803b.
- **Transit of Two Fixed Objects.** See details at Para 0803c.
- **Horizontal Angle (by compass or HSA).** See details at Para 0803d.
- **Radar Range.** See details at Para 0803e.
- **Range by Distance Meter (height of object known).** See Para 0803f.
- **Range by Rangefinder.** See details at Para 0803g.
- **Range by VSA / HSA (height of object known).** See Paras 0803h-i.
- **Soundings.** See details at Para 0803j.
- **Astronomical Observation.** See details at Para 0803k.
- **Sonar Range.** See details at Para 0803m.
- **Rising or Dipping Range (height of object known).** See Para 0803n.
- **Horizon Method of Rangefinding.** See Para 0803p.

a. **Compass Bearing (also Radar Bearings).** Bearings should be taken visually; radar bearings are significantly less accurate (see Para 1522) and should NOT normally be used as *Position Lines* unless no practical alternative exists. When a visual bearing of the edge of an object is taken, it is best to use a vertical edge if possible; the *Height of Tide* (*HOT*) must be taken into account if the bearing of a sloping edge of land is used, as the charted edge is the *MHWS / MHHW* line (or *Mean Sea Level* in areas where there are no tides). Symbols used for recording bearings of edges are at Para 0716h.

b. **Relative Bearing.** A *Position Line* may be calculated from a *Relative Bearing* (see Para 0126) when added-to / subtracted-from the True bearing of ship's head; if ship's head is not recorded at the instant of taking the *Relative Bearing,* inaccuracies may occur. At Fig 8-3 (below), an object is observed at Green 60; ship's head is 030˚, thus the True bearing of the object is 090˚.



Fig 8-3. Position Line by Relative Bearing and Ship's Head

c. **Transit of Two Fixed Objects.** If two fixed objects are seen in transit (in line), then the observer must be on an extension of line joining them (see Fig 8-4 opposite). For good 'sensitivity' of relative movement between the objects, ideally, the distance between the observer and the nearer object should be not more than 3 times the distance between the objects. However, less sensitive transits may still be used with care. Transits are used in *Fixes*, for checking compass errors (see Para 0811), and for assessing ship movement when *Turning at Rest* even if the objects are not charted. The symbol ∅ is used for a transit, but the symbol ≠ is used by the *UKHO* to identify transits on Admiralty charts (see *UKHO* Chart 5011 [Symbols & Abbreviations]).

(0803c continued)


Ideally, for good 'sensitivity', distance between ship and nearer object should be no more than 3 times distance between objects.

Fig 8-4. Position Line by a Transit of Fixed (Charted) Objects

(0803) d. **Horizontal Angle (Compass or HSA).** All angles subtended by a chord in the same segment of a circle are equal; it follows that if a horizontal angle between two objects is measured by sextant or by compass, the observer must lie on the arc of a circle containing the angle observed and both objects. In Fig 8-5 (below), the *Horizontal Sextant Angle* (*HSA*) between objects *A* and *C* is 80˚. The observer is thus on a *Position Line* which is the arc of the circle *ABC* along which the angle between *A* and *C* is always 80˚. An *HSA* may be used as a '*Danger Angle*' to clear a danger (see Fig 8-5 [below] and Para 1233 / Example 12-3). Detailed procedures for *HSAs* are at Para 0808.



The observer is on a Position Line which is the arc of the circle ABC, along which the angle between A and C is always 80°. HSAs may be used as 'Danger Angles'.

Fig 8-5. Position Line by Horizontal Sextant Angle (*also showing 'Danger Angle' use*)

e. **Radar Range.** Radar may be used to obtain a *Position Line* as a circular arc of a circle at both short and long ranges off the land. See details at Paras 1232 and 0710.

f. **Range by Distance Meter (Height of Object Known).** '*Distance Meters*' operate on the principle of the *Vertical Sextant Angle* (*VSA* - see Para 0803h overleaf) with the height of the object set onto the instrument and the ranges obtained read directly from it. *Distance Meters* of this type are normally for short range use. The operation of *Distance Meters* in RN service is covered in BR 45 Volume 3.

g. **Range by Rangefinder.** '*Optical Rangefinders*' use parallax principles to establish the distance of an object whose height is not known; none are currently in RN service. '*Laser Rangefinders*' operate by generating a narrow and intense beam of coherant infra-red radiation. Concerns over eye-safety, attenuation when used in wet weather and from enclosed Bridges have prevented their introduction into RN service.

(0803) h. **Range by VSA / HSA - Base of the Object Visible to the Observer.** A *Position Line* may be obtained from a *Vertical Sextant Angle* (*VSA*) of an object whose base is visible to the observer, by multiplying the height of the object by the *Cot* of the observed angle *BAC* (see formula (8.1) / Fig 8-6). The width may be used with formula (8.1a).

$$Distance\ = Visible\ Height\ of\ Object \text{ x } Cot\ (Observed\ Angle)$$

. . . 8.1 (1987 Ed . . . 9.1)

$$Distance\ = \frac{Width\ of\ Object \text{ x } 360}{2\pi \text{ x } Observed\ Angle\ (in\ degrees)}$$

. . . 8.1a

- **Position Line.** The *Position Line* will be the circumference of a circle, centred on the object (B), which has this distance as its radius.

- **Danger Angle.** A *VSA* may be used as a *Horizontal* or *Vertical Danger Angle* to clear a danger (see Fig 8-6 [below] and Para 1233d / Example 12-2).

- **Charted Height / Elevation and HOT Correction.** The charted height or *Elevation* of an object is usually above *MHWS* or *MHHW* (see Para 0624v) so it must be corrected for *HOT*. If this correction is not made, the calculated distance will be less than the actual distance (thus erring on side of safety).

- **Charted Elevation and Height of Structure.** The charted *Elevation* of a lighthouse is taken from *MHWS* or *MHHW* to the centre of the lens and NOT to the top of the structure. Heights of light structures (base to top) are also tabulated in the *Admiralty List of Lights and Fog Signals* (*ALLFS*).

- **Norie's Nautical Tables.** Norie's Nautical Tables solve the triangle for ranges between 1 cable and 7 miles and heights between 7 metres (23 feet) and 600 metres (1969 feet).

- **Shoreline Errors.** Angle (α) in Fig 8-6 is *BDE* but, provided that shoreline-distance (*DC*) is greater than *Elevation H* (*BE*) and *Elevation H* is greater than shoreline-object distance (*CE*), no appreciable error is introduced if angle *BAC* (α ') is used instead of *BDE* (α) (see Notes 8-1 / 8-2 below).



Fig 8-6. Vertical Sextant Angle (VSA) - Base of the Object Visible to the Observer

Notes:
8-1. Shoreline Errors - Object at Shoreline. *If the object observed (B) is vertically over the shore edge (C), and object-distance (DE) is greater than Elevation H (BE), the error in position will be less than the observer's height of eye (AD).*
8-2. Shoreline Errors - Object set back from Shoreline. *If the object is NOT vertically over the shore edge (C) (as in Fig 8-6), provided the shoreline-distance (DC) is greater than Elevation H, and Elevation H is greater than the shoreline-object distance (CE), the error in position is less than 3 times the observer's height of eye AD.*

(0803h continued)

Example 8-1. Vertical Sextant Angle (VSA) Calculation

A *VSA* of a lighthouse, charted *Elevation* 40 metres above *MHWS*, is 0°46'.2. *HOT* is 2.12m below *MHWS*. The *Index Error* of the sextant is + 1'.2. What is the range of the light?

Observed VSA = *0°46'.2*
Index Error = *+1'.2*
Corrected VSA = *0°47'.4* *(0.79°)*

Charted Elevation = *40.00m*
+ 2.12
Corrected Elevation = *42.12m (0'.02274 n. miles)* . . . (formula 8.1)

Range = *Corrected Elevation* x *cot Corrected angle*
= *0.02274 cot 0.79°*
= *1.65 n. miles (Norie's Nautical Tables also give 1.65 n. miles).*

(0803) i. **Range by VSA - Base of the Object Beyond the Observer's Horizon.** A *Position Line* may also be obtained from the observation of the *Vertical Sextant Angle* (*VSA*) of an object (eg distant mountain peak) where the base is out of sight beyond the observer's horizon, but the calculation is more complex, and some approximations are necessary. See Appendix 6 Para 2b for details.

j. **Soundings.** Soundings are frequently of value in establishing a *Position Line*. In areas where a particular depth contour on the chart is sharply defined and reasonably straight, or in approaches to the land where there is a steady decrease in depth, a *Position Line* may be obtained. Good examples of this are in the south-western approaches to the British Isles, where the depth decreases rapidly from 2000 to 200 metres in a distance of some 10 to 20 miles, or in the southern approaches to Beachy Head, where the depth shoals from 50 to 30 metres in about 1½ miles. In the latter case, it will be necessary to allow for the *HOT* and to ensure that the *Echo Sounder* is reading accurately. The procedures for calibrating the *Echo Sounder* are at BR 45 Volume 3 and are summarised at Paras 1807 and 1827n.

k. **Astronomical Observation.** An *Astronomical Position Line* is a small element of the circumference of a *Small Circle* centred on the *Geographic Position* of a heavenly body with a radius equivalent to '*90° - Altitude*'(corrected for errors), converted into *n.miles.* Although an *Astronomical Position Line* is circular, for practical purposes it may be treated as a straight line, except in the case of very high altitudes. An *Astronomical Position Line* may be obtained from the observation of one of the heavenly bodies - the sun, moon, stars or planets. The term *'Astronomical Position Line'* is often abbreviated to '*Position Line*'. Full details of astronomical observation procedures and methods of making the necessary calculations are at BR 45 Volume 2.

m. **Sonar Range.** Provided sonar equipment is fitted, it is possible to obtain the range of an underwater object (eg sonar conspicuous rock or *Coral* outcrop) which can be used for navigational purposes as a *Position Line* in the form of a circular arc. However, it is often impossible to determine precisely from which part of the sea-bed the sonar range is being obtained, **and so particular care should be taken with this technique.**

(0803) n. **Rising or Dipping Range.** The 'Rising or Dipping Range' is the range at which an object is observed to rise above / fall below the horizon. It is approximate, is substantially affected by *Atmospheric Refraction* and **should be treated with caution**.

- **Distance of the Sea Horizon - Formulae.** The theoretical geometric distance of the sea horizon for a height of *h* metres is a range between $1.92\sqrt{h}$ to $1.93\sqrt{h}$ *Sea Miles,* or $1.93\sqrt{h}$ to $1.92\sqrt{h}$ *n. miles* (depending on *Latitude*), thus in practice these units are interchangeable in the calculation and are identical at approximately 45° *Latitude*. However, the effect of 'standard' *Atmospheric Refraction* (see Para 1515) is to increase the geometric distance by about 8%. Formulae for the approximate distance of the sea horizon are:

$Distance = 2.08\sqrt{h}\ (metres)$ [approx] **. . . 8.2 (1987 Ed . . . 9.2)**
or: $Distance = 1.15\sqrt{h}\ (feet)$ [approx] **. . . 8.3 (1987 Ed . . . 9.3)**

- **Distance of Sea Horizon - Nories Nautical Tables and ALLFS.** These distances may also be found in Norie's Nautical Tables or the *Geographical Range* table in the *ALLFS* - [see Para 0932]. As these tables make different allowances for *Atmospheric Refraction* the distances obtained will be different (see Note 8-3 below) .

- **Distance of Sea Horizon + Distance of the Object Beyond the Horizon.** The distance of sea horizon and the distance of the object beyond the horizon added together give the distance of the ship from the object (see Fig 8-7)



Fig 8-7. Position Line from a Dipping Range

Note 8-3. *Norie's Tables uses the formula: distance of the sea horizon* $d = 2.095\sqrt{h}$ *where h is the Elevation in metres. ALLFS uses the formula:* $d = 2.03\sqrt{h}$, *where h is the Elevation in metres, or* $d = 1.12\sqrt{h}$, *where h is the Elevation in feet.*

Example 8-2. Rising or Dipping Range Calculation

A shore light, *Elevation* 40 metres, is observed from the Bridge to dip below the horizon. Height of eye is 12 metres. What is the range of the light?

From . . . formula (8.2), the following ranges are obtained:

Range of sea horizon for height of eye of 12 metres	7.21	Sea Miles
Range of sea horizon for *Elevation* of 40 metres	13.16	Sea Miles
Range of light	**20.37**	**Sea Miles.**

From Norie's Nautical Tables the following ranges are obtained:

Range of sea horizon for height of eye of 12 metres	7.3	Sea Miles
Range of sea horizon for *Elevation* of 40 metres	13.3	Sea Miles
Range of light	**20.6**	**Sea Miles.**

The range given in the *Geographical Range* table in *ALLFS* is **19.9 Sea Miles.**

(0803) p. **Horizon Method of Rangefinding.** When the height of the object is unknown or negligible, the range may be found if one's own height of eye is known. The (theoretically negative) *VSA* between the waterline of the object and the sea horizon is measured (see Fig 8-7a below). This angle, corrected for *Index Error* and *Dip* ('Dip of the Sea Horizon' - see the Nautical Almanac or Norie's Nautical Tables) is angle θ. It can be shown that angle θ, *h* (height of eye) and *d* (distance in n miles) are connected by the formulae:

$$\theta = 0.5658\frac{h}{d} + 0.42\,d \qquad \text{(h in feet, d in n.miles)} \qquad \textbf{. . . 8.3a}$$

$$\theta = 1.8563\frac{h}{d} + 0.42\,d \qquad \text{(h in metres, d in n.miles)} \qquad \textbf{. . . 8.3b}$$

These formulae may be solved for *d*, or *d* may be found from the 'Dip of the Shore Horizon' table in Norie's Nautical Tables. This method should give the range to within about 3% at short ranges. The greater the height of eye, the greater should be the accuracy, since the base line is the vertical line from the sea to the observer. However, any values obtained are approximate, especially if *Abnormal Refraction* is suspected.



Fig 8-7a. Horizon Method of Rangefinding.

Example 8-3. The angle between the base of an object and the horizon is observed to be 0˚ 12.1´ *Index Error* is + 1´.2. Height of eye is 49 feet. What is the range of the object?

Observed angle	0˚ 12´.1
Index Error	+ 1´.2
Corrected angle	0˚ 13´.3
(-) *Dip* of sea horizon	6´.8
θ	0˚ 20´.1

$$20.1' = \frac{27.7242}{d} + 0.42\,d$$ . . . (formula 8.3a)

d = 1.42 n. miles (or 1.43 from Nories)

0804. Transferred Position Lines

A *Position Line* may be '*Run-on*' along the ship's track as a '*Transferred Position Line*', allowing for wind and the estimated *Tidal Stream / Current* if known. This procedure has many uses, predominately in a *Running Fix*, but may also assist in clearing some danger or making a *Wheel-Over* into an ill-defined anchorage or port. It is a standard procedure in astro navigation when plotting *Astronomical Position Lines* (see BR 45 Volume 2 Chapter 3). The technique is illustrated at Examples 8-4 to 8-6 (below and opposite).

Example 8-4. A ship on course 090˚ speed 8 knots observes a lighthouse bearing 035˚ at 1600. There is no *Tidal Stream* or wind. Plot the *Transferred Position Line* for 1630. See Fig 8-8.

- **Position Line.** Draw a line in a 215˚ direction from the light. This is the *Position Line* at 1600. The ship's actual position *A* at 1600 is unknown, although it must be somewhere on the *Position Line* from the light through *A*.
- **Transferred Position Line.** Assume that the ship may be at *A* (somewhere on *Position Line* from the light) and project *AB* in a direction equivalent to a 30 minute run, in this case 090˚ 4 miles. Construct a *Transferred Position Line*, with a double arrowhead at the outer end, parallel to *Position Line* through *A* and passing through *B*. The ship should be on the *Transferred Position Line* at 1630.



Fig 8-8. Plotting a Transferred Position Line (No wind or Tidal Stream / Current)

Example 8-5. *Plot the Transferred Position Line* from position A for 1630 as in Example 8-4 (above), but with a *Tidal Stream* of 132˚ 1.7 knots. See Fig 8-9.

- **Transferred Position Line.** Proceed as in Example 8-4, but add a *Tidal Stream* vector (*BK*) of 132˚ 0.85' before plotting the *Transferred Position Line*.



Fig 8-9. Plotting a Transferred Position Line (With Tidal Stream)

Example 8-6. A ship on course 180˚ requires to turn onto an anchorage approach 080˚ in an ill-defined bay without a suitable *Wheel-Over* mark. Using lighthouse '*L*', plot the transferred *Wheel-Over* bearing and *Transferred Position Line* '*CK*' for the approach to anchorage '*K*'. Assume that there is no wind or *Tidal Stream*. See Fig 8-10 (below).

- **Position Line.** Observe lighthouse *L* when it bears 080˚ (parallel to the anchorage approach course '*CK*') and note the time.
- **Transferred Position Line.** Plot *Wheel-Over* position *B* using ship' turning data. Transfer the 080˚ *Position Line AL* through *B*, calculating the time the ship will reach the transferred *Wheel-Over* line.
- **Tidal Stream.** In this example (for simplicity), wind and *Tidal Stream* was assumed to be zero. In practice, this will rarely be the case and the time of the transferred *Wheel-Over* will need to take wind and *Tidal Stream* into account, using the procedures at Example 8-5 (previous page).



Fig 8-10. Plotting a Transferred Wheel-Over Line (No wind or Tidal Stream / Current)

0805. Fixing Techniques - Summary of Methods

A *Fix* is the position obtained by the intersection of two or more *Position Lines*. Unless the *Position Lines* are obtained at the same time, one or more of them must be transferred (see Paras 0804 and 0806). Methods of obtaining a *Fix* are:

- *DGPS / GPS* (or equivalent).
- *LORAN-C* and *eLORAN.*
- Cross Bearings - Theory and Practice.
- Bearing and Range.
- Transit and *HSA.*
- Bearing and *HSA*.
- Multiple *HSAs*.
- *Running Fix*.
- *Range Lattices* - Radar / Visual
- Astronomical Observations.
- Bearing / Range and Depth Contour Sounding.
- Bottom Contour Soundings.

a. **DGPS / GPS.** *DGPS / GPS* receivers are fitted in almost every vessel and *WECDIS / ECDIS* fits with automatic *DGPS / GPS* inputs are increasingly common (see Chapter 9 for *DGPS / GPS* theory). However, 'Traditional' *Fixing* methods are still important as a back-up method and to check automated systems.

- **DGPS / GPS Denial or Degradation.** *DGPS / GPS* signals are extremely weak; they may easily be jammed or seduced ('*GPS Denial*'). Graceful degradation of positional accuracy can occur which may be difficult to spot unless regular independent checks are made (see Note 8-4 opposite).

- **Check Fix Requirement and DR/EP Comparison.** It is essential to carry out independent regular check *Fixes* to check *DGPS / GPS* inputs, using another navaid; if this is not possible (ie outside radar range of land / no *LORAN* coverage / no 2nd *GPS* receiver / without astronomical observations), then comparison of the *DGPS / GPS* position against *DR/EP* is required.

- **Fix and Check Fix Intervals.** Intervals for *Fix*es and check-*Fixes* are at Paras 0716 / 0721 (with extracts repeated at Paras 1231f/g/h).

- **GPS Lattice.** Ships not fitted with *WECDIS / ECDIS* may need to construct a chart expansion with a *GPS Lattice* superimposed (*Latitude / Longitude Grid*) to allow rapid, accurate plotting of *GPS* positions and course alterations (eg for minefield swept channel transits etc). If the original chart is not based on *WGS 84*, a (*Geodetic*) *Datum Shift* must be applied.

- **Construction of GPS Lattice.** The quickest way of constructing a *GPS Lattice* chart expansion is by photocopying the navigational chart with a particular expansion factor set, taking care to include a suitable *Grid* and distance *Scale* on the area being photocopied. This *Grid* and distance *Scale* may then be subdivided into smaller divisions on the photocopy to assist rapid, accurate plotting of *Fixes*. **Care must be taken to ensure a uniform *Grid* and distance *Scale* expansion.** Alternatively, a *Mercator* chart expansion may be constructed using *UKHO* chart (Diagram) 5004, or from first principles by using *Meridional Parts* (see Para 0424).

Note 8-4. GPS Denial / Degradation. *'GPS Assisted' accidents, where over-reliance has been made on erroneous GPS inputs, are becoming increasingly common (see also Para 0916).*

- *In one notable case, a modern cruise liner with 1,509 persons on board, fitted with GPS and an automatic navigation system, grounded 17 n. miles from its presumed position. The GPS aerial lead had failed and GPS had automatically switched to DR mode for 34 hours until the grounding; aural and visual alarms were missed. With wind and a ½ kn Current taking effect, no independent position checks nor EP comparison with the GPS position were made in the entire 34 hour period.*
- *In another case, a large modern vessel equipped with 2 GPS receivers and ECDIS, grounded 15 n. miles from its presumed position. The GPS input to ECDIS had lost its signal some 30 hours earlier and had switched to DR mode; the alarm had been cancelled but no action taken. The 2nd GPS was operating correctly but was not used for comparison. No effective check Fixes were taken on the coastline, which had been in range for most of the preceding 30 hours prior to grounding.*

b. **LORAN-C / eLORAN.** *LORAN-C* is not as accurate as *GPS* but is valuable as a position source and for cross-checking *GPS* data. *eLORAN* is under development (2008) and has achieved accuracies similar to *GPS* during trials (see Para 0918).

c. **Cross Bearings in Theory.** When accurate bearings are obtained from two different known objects at the same time, the ship's position must be at the point of intersection of the two lines of bearing. To identify any possible errors, a third (check) bearing should always be taken at the same time and should pass through the point of intersection of the other two bearings. See Fig 8-11 (below).



Fig 8-11. Fixing by Cross Bearings

d. **Cross Bearings In Practice - The Cocked Hat.** When 3 bearings are taken, the resulting *Position Lines* may NOT meet at a point but as a triangle known as a *Cocked Hat* (see Fig 8-12 overleaf). The cause of a *Cocked Hat* may be any of the following:

(1) Excessive time interval between observations.

(2) Error in identifying the object(s).

(3) Error in plotting the lines of bearing.

(4) Inaccuracy of observation due to compass / repeater / human error.

(5) Inaccuracy of the survey or the chart.

(6) Compass error unknown or incorrectly applied.

(0805d continued)

A detailed treatment of bearing errors is at Chapter 16 and Appendix 8, but in summary:

- **Errors (1), (2) and (3).** If the *Cocked Hat* is large, removal of errors (1), (2) and (3) may usually be attempted, or the *Fix* re-taken avoiding them. Error (1) may be removed by applying a '*Run-on*' / '*Run-back*'(see Example 8-7).
- **Error 4.** Error (4) should never be greater than ¼°-½° with modern compass repeaters and may generally be disregarded.
- **Error 5.** Error (5) may be assessed by checking the chart *Source Diagram* (Paras 0624c/d) or *Category of Zone of Confidence* (*CATZOC*) (Para 0625).
- **Error 6.** Methods of eliminating error (6) are at Para 0811.

Example 8-7. A ship is on course 180 at 24 knots (see Fig 8-12 below). Bearings for a *Fix* were taken at 1059½, 1059¾ and 1100. On plotting the '1100 *Fix*', no allowance was initially made for the 15 second intervals (each equivalent to 1 cable's run) between each bearing, which caused a large *Cocked Hat*. On re-plotting with an appropriate '*Run-on*' for the earlier bearings, the 1100 *Position Lines* and *Transferred Position Lines* create a good *Fix*.



Fig 8-12. Example 8-7: The Cocked Hat and Resolution of 'Run' Errors

(0805) e. **Bearing and Range.** A visual bearing may be combined with a range to obtain two *Position Lines* and thus a *Fix*. To identify any possible errors, a third (check) bearing or range should always be taken at the same time (as for cross bearings). See Para 1232.

f. **Transit and HSA.** A transit may be combined with a range from an *HSA* between the nearer object of the transit and a third object. The position is the intersection of the transit and the arc of the circle obtained from the *HSA* (see Para 0803d / Fig 8-5). No compass is required for this method of *Fixing*.

(0805) g. **Bearing and HSA.** If passing a small island (or similar feature) where the compass bearings of the two edges give too small an angle of cut and a ranging aid (eg radar) is not available, a bearing of one edge may be combined with a range from the *HSA* between the edges. From the *Radian Rule* (see Para 0127), if the width of the island is measured on the chart, the range of the ship may be calculated (see Example 8-8).

Example 8-8. The *HSA* between the edges of an island 0.7 *n. miles* wide was 6˚ 00.0'. At the same time, the left-hand edge of the island bore 085˚. What was the range (R) of the island?

$$1° = \frac{2\pi}{360} \textit{ radians} \qquad \text{thus:} \qquad 6° = \frac{6 \times 2\pi}{360} \textit{ radians}$$

$$\textit{Range (R)} = \frac{360 \times 0.7}{6 \times 2\pi} \textit{ n.miles} = 6.68 \textit{ n.miles}$$



Fig 8-13. Example 8-8: Fixing by a Bearing and an HSA

h. **Multiple HSAs.** Multiple *HSAs* may be used to *Fix*. Details are at Para 0808.

i. **Running Fix.** A *Running Fix* involves transferring one *Position Line* to cross another (see Para 0804). Details of *Running Fix* techniques are at Para 0806.

j. **Range Lattices - Radar / Visual.** The intersection of range arcs (radar, *VSA* etc) provides a *Fix*. Radar / *VSA Range Lattices* of arcs cutting each other at angles of between 30˚ and 90˚ from two radar conspicuous objects may be constructed on the chart. The radar should be calibrated in *n. miles* and radar *Index Error* known to ensure accurate *Fixing*. Other radar *Fixing* techniques are at Para 1232.

k. **Astronomical Observations.** Calculation of an *Observed Position* (*Fix*) from astronomical observations is described in detail in BR 45 Volume 2.

m. **Bearing / Range and Depth Contour Sounding.** On transiting shoaling water, a *Position Line* may be obtained by an *Echo Sounder* reading when crossing (as nearly as possible at right angles) significant, substantially changing, clearly defined, reliable depth contours (see Fig 8-14 overleaf). The *Echo Sounder* reading may be combined with any other *Position Line* (eg visual bearing or radar / *VSA* range) taken simultaneously with the sounding. Before plotting the depth contour sounding *Position Line*, an allowance must be made for:

- The *HOT*.
- The draught of the *Echo Sounder* (usually ship’s draught) if it is NOT set to read depths below the waterline.

(0805m continued)

In Fig 8-14 (below), at 1000, St Anthony's Head bore 342½˚ at the same time as depth 47m (below the keel) was recorded on the *Echo Sounder*. Draught was 6.1m, *HOT* 3.1m. The sounding *Position Line* was drawn along the 50 metre depth contour (47 + 6.1 - 3.1 = 50m) and where it intersected the bearing of 342½˚, was the position at 1000.


Black Rk Beacon
Pendennis Pt
Qk Fl(3)
St Anthony Hd Occ.WR.15 sec 22m 22.20M Horn 30sec
OLD CG STN (conspic)
Zone Pt
St.Sh.ca Wd
R.Wd
White
bkSh
Wk
Red
Old Wall
White
Obscured
Eastern extreme of St Mawes Castle bearing 004°
050°
325°
12
06
1002
1000
Variation 8°30' W (1979)
MAGNETIC
f S.bk Sh
Wk PA
Fl.R.2·5sec 2D
RY

Fig 8-14. Fixing by Bearing and Sounding of Depth Contour

(0805) n. **Bottom Contour Soundings.** *Fixing* by the use of multiple bottom contour depth soundings alone is a specialized technique, normally only used by dived submarines. Details are at BR 45 Volume 9.

0806. Running Fixes

The concept of a *Transferred Position Line* was established at Para 0804. **The accuracy of the *Running Fix* is fundamentally dependent on the accurate assessment of the ship's course and speed (the *Water Track*) and the *Drift / Set* (effect of wind, *Tidal Stream / Current*) experienced over the period.** The biggest single source of error is likely to be an inaccurate assessment of the *Drift / Set*.

a. **'Standard' Running Fix.** A 'Standard' *Running Fix* is the point of intersection of a *Transferred Position Line* and a second *Position Line* on the same single object.

Example 8-9. 'Standard' Running Fix. A ship on course 090° speed 8 knots observes a lighthouse bearing 035° at 1600. At 1630 the same lighthouse bore 295°. The *Tidal Stream* is estimated as 132° at 1.7 knots. Find the ship's position at 1630. See Fig 8-15 (below).

- Plot the *Transferred Position Line* for 1630 allowing for *Tidal Stream*, as in Examples 8-4 / 8-5 (Para 0804).
- Plot the 1630 *Position Line* (295°). The 1630 *Running Fix* position is at the intersection of the *Transferred Position Line* and the 2nd *Position Line*.


090°
4′
A
B
Tidal Stream
K
035°
Running Fix at 1630
1630 (Second Position Line - 295°)
1600
(Initial Position Line)
1630
(Transferred Position Line - With Tidal Stream)

Fig 8-15. Example 8-9: A 'Standard' Running Fix

b. **'Special Case' Running Fix - Doubling the Angle on the Bow.** The range of an observed object is the distance run between observations when the 'angle on the bow' is doubled, provided there is no *Drift / Set*' (see Fig 8-16 below). Provided there is no *Drift / Set*, the distance run (AB) equals the range of the object (BL). If there is any *Drift / Set*, the observations should normally be plotted as a conventional *Running Fix* (see Example 8-9 at Para 0806a / Fig 8-15 above). The detailed theory of '*Doubling the Angle on the Bow*', both in still water and with a *Drift / Set*, is at Appendix 7.


L
α°
Provided there is no Set,
AB (Distance Run) = BL (Range of Object)
A
α°
B
2α°
Course Steered
1st Bearing
2nd Bearing

Fig 8-16. 'Special Case' Running Fix - Doubling the Angle on the Bow

(0806) c. **'Special Case' Running Fix - Establishing a Tidal Stream.** If starting from a known *Fix* position, the *Drift / Set* experienced may be estimated by *Running Fix*, provided it is certain that the strength and direction of the *Drift / Set* remain constant (see Example 8-10 / Fig 8-17 below).

Example 8-10. Running Fix from Fix Position with Unknown Tidal Stream. At 1700 a ship on course 180° was *Fixed* at *A*. At 1800 object *R* bore 090° and at 1836 it bore 053°. Assuming it is constant, establish the *Tidal Stream* from 1700 to 1836. See Fig 8-17 (below).

- Plot the ship's *Water Track AE* (180°) from the 1700 *Fix* at *A*.
- Plot the 1st (1800) *Position Line*, intersecting *AE* at *B*.
- Plot the *Transferred Position Line* at the *EP* position at 1836 using speed *AB*.
- Plot the 2nd *Position Line* (1836). The 1836 *Running Fix* position is at the intersection of the *Transferred Position Line* and the 2nd *Position Line*.
- The *Tidal Stream* from 1700-1836 is represented by *DP*, where *D* is the *DR* position at 1836, plotted from *A*.


A
1700 Fix Position
Ground Track
1800 1st Position Line
1830
B
R
180°
Transferred Position Line
(EP at speed AB) 1836
C
P - 1836 Running Fix Position
Tidal Stream
D
(DR) 1836
1836 2nd Position Line
E

Fig 8-17. Example 8-10: 'Special Case' Running Fix - Establishing a Tidal Stream

(0806) d. **'Special Case' Running Fix - Estimating Distance Abeam.** When '*Doubling the Angle on the Bow*', if the initial angle on the bow is 45° the second angle will be 90°, thus giving the distance abeam provided there is no *Drift / Set*; this is known as the '*Four-Point Bearing*' (ie one *Point* = 11¼° and thus four *Points* = 45° [see Para 0123c]). The *Four-Point Bearing* suffers the disadvantage that the distance abeam is not known until the object is abeam. However, provided the difference between the cotangents of the two measured angles is 1 [see formula (8.5) below], the distance run between the two angles equals the distance at which the object will pass abeam (see Fig 8-18 below); thus the distance abeam can be estimated before the object is abeam. A number of pairs of angles satisfy this criteria (see Table 8-1 below).


L
x
A
Ø
B
θ
C
1st Bearing
x
y
Course Steered
2nd Bearing
Provided there is no *Set*,
AB (Distance Run '*x*') = CL (Range Abeam of Object '*x*')

Fig 8-18. 'Special Case' Running Fix - Estimating Distance Abeam

In Fig 8-18: $cot\theta = \frac{y}{x}$ and $cot\phi = \frac{x+y}{x}$

$$cot\phi - cot\theta = \frac{x+y}{x} - \frac{y}{x}$$

$$cot\phi - cot\theta = 1$$

. . . 8.5 (1987 Ed. . . 9.5)

Table 8-1. Pairs of Angles for use in Estimating Passing Distance Abeam

ϕ	θ	**Remarks**
26½°	45°	Distance Run (AB) = Distance Abeam (CL) Distance Run (AB) = Distance to Abeam Position (BC)
30°	53¾°	
35°	67°	
40°	79°	

e. **Estimating Distance Abeam - Subtended Angle.** From the *Radian Rule*, 1° subtends approximately 1 *n.mile* at a distance of 60 *n.miles*. (or 2 cables at 12 *n.miles*). Thus the angle on the bow and range of an object may be used to calculate the distance it will pass abeam (*eg An object is 10° on the bow at 12 n.miles. Assuming no Tidal Stream or Leeway, it will pass at 10* x *2 cables = 2 n.miles*). Course may be altered to adjust the distance off, but allowance must be made for any *Tidal Stream* or *Leeway*.

0807. Selection and Use of Visual Fixing Marks

a. **Choosing Marks.** Marks selected for *Fixing* should be charted and identifiable. If possible, marks should be ahead of the ship and visible from the same repeater.

- **Bearing Separation.** Chosen marks should be well separated in bearing, normally with a minimum cut of 30˚. Fig 8-19 (below) illustrates the difference in position caused by an error of 5˚ with two cuts of 90˚ (*AB*) and 20˚ (*CD*). Ideally, when three objects are observed they should be 60˚ apart in bearing, and with two objects 90˚ apart.
- **Effect of Range.** The closer the object, the less will be the difference in position resulting from any error in the bearing.
- **Same Circle.** The marks and ship should NOT be on the circumference of the same circle, because any unknown compass error will NOT be revealed when the bearings are plotted (see details at Paras 0808f-h / Fig 8-27).
- **Channels.** When navigating in channels on older charts, marks should be selected from one side only to avoid any possible discrepancy arising from any different geographical *Datums* in use on opposite sides of the channel.



Fig 8-19. Effect of a 5˚ Error at 90˚ and 20˚ Angles of Cut

b. **Fixing Procedures.** The normal (single operator) procedure for *Fixing* is as follows, **and should NOT take more than 1 minute.** An assistant may be used to record and plot *Fixes*. *Fixing* procedure when anchoring are at Para 1415b.

- Select 3 or 4 marks from the chart and any additional marks to be 'shot-up'.
- Check the bearings of selected marks from the present *DR / EP* position.
- Positively identify the marks with binoculars. If in any doubt, identify them, either by transit bearing or from a previous *Fix* (see Para 0807d opposite).
- Write the names of selected marks in the *Navigational Record Book*.
- Observe the bearings as quickly as possible. Except when anchoring, the time of the *Fix* will be the last bearing, so take marks with slow bearing movement first (ie ahead / astern) and marks with rapid bearing last (ie beam). The time of *Fix* should ideally coincide with the *DR / EP* time on the chart.
- Note the bearings and time in the *Navigational Record Book* (see Fig 7-11). If using a magnetic compass, apply *Magnetic Deviation* and *Variation*.
- Plot the *Fix* and compare to the *DR / EP*. Lay off a further *DR / EP*.
- Verify time of *Wheel-Over* (if applicable). Plan marks for next *Fix*.
- Return to lookout.

(0807) c. **Shortcuts to Fixing.** Experienced OOWs may use shortcuts to *Fixing* procedures. Examples of these are as follows, but it should be emphasised that these are not recommended for beginners.

- The fastest changing bearing will be observed at the exact intended time for the *Fix*; the other bearings will be observed just before or just after this time.
- Only the last two digits of each bearing are memorised while taking the *Fix*; these are recorded in the *Navigational Record Book* after all bearings have been taken and the third (hundreds) figure of each added by inspection. This procedure allows 3 (or 4) bearings to be taken very rapidly, but does require mental agility and a practised memory for figures to achieve reliable results.

d. **Identifying Marks - Procedures.** The OOW / NO must plan ahead and positively identify any marks which are to be used for *Fixing* or as marks in *Pilotage*. **Chimneys, flagstaffs and radio masts are notorious for having been demolished and/or sometimes re-built in slightly different positions without the charting authority having been informed; such marks should be treated with particular caution.** Several methods are available to identify marks, as follows:

- **From the DR / EP.** Well-known, ‘Conspicuous’ marks (often marked ‘Conspic’ on the chart) may often be identified from the *DR / EP*, by looking down the expected bearing with binoculars. Such marks may be identified by this method alone, but less obvious marks will need further proving before being used.
- **By Transits.** A quick and most useful method of positively identifying an unknown mark is to select a bearing when it will be in transit with a known object and to observe the bearing of both at that moment. This can often be the ‘opening bearing’ when the object comes into transit with an edge of land. Compass error must be allowed for, as reliance is made of a single bearing. If doubt remains, another transit bearing will provide a ‘cut’, or it may be necessary to prove the mark by *Fix* (see Bullet below).
- **By Fix.** When taking a *Fix,* an additional bearing of an ‘unknown’ mark may be taken. Once the *Fix* is plotted, the extra bearing is plotted from the *Fix* to the mark to check whether it coincides with the mark’s charted position. If doubt remains, this process may need to be repeated to provide a ‘cut’ with another check bearing, either using another *Fix* or a or a suitable transit (see Bullet above).

e. **Poor Fixes.** If the *Fix* does not fit, **it must NOT be ‘fudged’**; this is both dishonest and dangerous. The *Fix* either needs to be re-worked to eliminate known errors (see Para 0805d / Fig 8-12), or to be retaken. **If there is any doubt about the ship’s position in relation to immediate dangers, the ship should be turned into safe water or stopped using astern power (as appropriate) and the navigation situation resolved before proceeding further.** This may dent the OOW / NO’s pride, but it may well prevent the ship itself from being severely ‘dented’ in a grounding.

(0807) f. **Identification of Uncharted Objects.** It sometimes happens that a shore object or buoy is visible from the ship but is not shown on the chart. Its position may be plotted on the chart by a series of bearings, using the *Fix* and / or transit methods at Para 0807d (previous page). Figs 8-20 and 8-21(below) illustrate these techniques in establishing the position of an uncharted buoy, by bearings and transits respectively. **In practice, these two methods may be mixed.** Once a fixed object has been positively identified and plotted on the chart, it may be used for *Fixing* the ship, subject to any accuracy limitations arising out of the processes used to chart the object.



Note. Ship Fixed from known charted objects, with 'Shoot-up' bearings taken at each Fix and plotted from the Fix to the buoy, to establish its position.

Fig 8-20. Establishing the Position of an Uncharted Buoy by Fixing Method



Note. Buoy's position established by transits of charted objects. Fixes (except at 1000) omitted from diagram for clarity.

Fig 8-21. Establishing the Position of an Uncharted Buoy by Transit Method

0808. Horizontal Sextant Angle (HSA) Fixes

Despite the advent of *DGPS / GPS* and *WECDIS / ECDIS* equipments, in the event of *'GPS Denial'* or other circumstances (eg defects, hostilities, action damage etc), it may still be necessary to navigate to a higher degree of accuracy than that obtainable from normal *Fixing*, while at the same time plotting the *Fix* quickly and maintaining an accurate record of the ship's movements. Examples of the occasions when this may be necessary are mine countermeasure operations, *Pilotage* and the anchoring of ships in company. Two visual methods are available for this type of *Fixing*: *Horizontal Sextant Angles* (*HSAs*) and *Bearing Lattices*.

a. **Fixing by HSAs.** Observing and plotting *HSAs* subtended by three or more objects *Fixes* the ship's position by the intersection of two or more *Position Lines*. It is extremely useful for *Fixing* the ship accurately when moored or at anchor, and for *Fixing* the ship accurately at sea when two trained observers are available. The theory of *HSA Fixes* is at Appendix 6 and errors in *HSA Fixes* at Chapter 16 / Appendix 10.

- **Advantages.** The advantages of the *HSA Fix* are:
  - *HSA Fixes* are more accurate than a compass *Fix*, because a sextant can be read more accurately than a compass.
  - *HSA Fixes* are independent of compass errors.
  - *HSAs* can be taken from any part of the ship.
  - *HSA Fixes* are easy to take, particularly with trained observers.
- **Disadvantages.** The disadvantages of the *HSA Fix* are:
  - Plotting *HSA Fixes* can take longer than plotting compass bearings.
  - Three suitable objects are essential (see Para 0808e).
  - If the objects are incorrectly charted or incorrectly identified the *Fix* will be false and the error may not be apparent. For this reason *HSA Fixes* should not normally be used with a poorly surveyed chart.
  - The *HSA* marks and ship should NOT be on the circumference of the same circle, because the *Fix* can be plotted anywhere on the circle (see details at Para 0808f / Fig 8-27).

b. **HSA Fixes - Concept.** Fig 8-22 (below) shows a ship *'L'* and marks (*A, B, C, D*), all in roughly the same horizontal plane. The angles *ALB* and *BLC* are measured by *HSA*. *L* and *B* lie at the intersection of the circles *ALB* and *BLC*, which contain the observed angles *ALB* and *BLC* respectively. The ship must be at *L*, and not at *B*.



Fig 8-22. Fixing by Two HSAs

(0808) c. **HSA Fixes - Plotting.** To plot the *Fix* at Fig 8-22 (previous page), the angles *ALB* and *BLC* are set on a *Station Pointer* which is placed over the chart so that *LA*, *LB* and *LC* pass through the charted positions of *A*, *B*, and *C*. *L* is the ship's position.

- **Plotting Check Angles.** To guard against incorrect identification, a check angle may be taken between the centre and fourth objects (*B* & *D* in Fig 8-22). When a *Station Pointer* is used, the fourth angle may be plotted after the *Fix* has been obtained, by holding the *Station Pointer* steady and moving the appropriate leg to the check angle. This leg should then pass through *D*.

- **Recording Angles.** The *Fix* shown in Fig 8-22 (previous page) would be recorded in the *Navigation Record Book* as:

  HSA A 34˚15' B 51˚46' C
  HSA B 73˚49' D

- **No Station Pointer.** If no *Station Pointer* is available, a *Douglas Protractor* (see Para 0811g) or tracing paper may be used instead. The observed angles are drawn from the centre of the *Douglas Protractor* or from any point on the sheet of tracing paper. The *Douglas Protractor* or tracing paper are placed on the chart and rotated until all the lines are in contact with the charted objects. The ship's position may then be pricked through onto the chart.

d. **Strength of an HSA Fix.** The mathematical strength or weakness of an *HSA Fix* is assessed by the angle of cut between the *Position Circles*; the closer the cut is to 90˚ the stronger the *Fix*. A major disadvantage of plotting by *Station Pointer*, *Douglas Protractor* or tracing paper (as at Para 0808c) is that none of these methods shows the *Position Circles*. The *Position Circles* may be drawn on the chart using a simple geometrical construction, allowing the angle of cut to be assessed (see Fig 8-23 below).



Fig 8-23. Plotting the Position Circles of an HSA Fix

- **Construction.** Perpendicular bisectors to *AB* & *BC* are *HDF* & *KEG* . The centres O_1 and O_2 of the two relevant *Position Circles* through *AB* and *BC* may be found from the calculations opposite, based on formula (A6.2):

(0808d) From example at Paras 0808c/d and Figs 8-22 / 8-23:

$$DO_1 = X_1 = \frac{\tfrac{1}{2}d}{tan34^\circ.25} = 37.45\ mm \qquad \text{. . . formula (A6.2)}$$

$$EO_2 = X_2 = \frac{\tfrac{1}{2}e}{tan51^\circ.2667} = 30.48\ mm \qquad \text{. . . formula (A6.2)}$$

- **Plotting the Position Circles.** The distance between *A* and *B* is represented by *d* the distance between *B* and *C* by *e*. The two *Position Circles*, radii AO_1 and BO_2, may now be plotted and the *Fix* at *L* established.
- **Angle of Cut.** The angle of cut between the two *Position Circles* is immediately apparent and the closer this is to 90˚, the stronger the *Fix*. Ideally, the angle of cut should never be less than 30˚. In Fig 8-23 (opposite), the angle of cut at *L* is about 70˚.
- **Third Position Circle.** If the two angles are small (eg 20˚ or 30˚) the weakness of the *Fix* may be overcome to some extent by plotting a third *Position Circle* through the two outer marks A and C (this would be circle *ALC* in Fig 8-23).

e. **Choosing Marks for an HSA Fix.** The sum of the two *HSAs* should be more than 50˚; better results will be obtained if neither *HSA* is less than 30˚. Marks for an *HSA Fix* should be chosen so that at least one of the following conditions applies:

(1) Marks are either all on or near the same straight line, and the centre mark is nearest the observer (see Fig 8-24 below).

(2) The centre mark is nearer the ship than the line joining the other two (see Fig 8-25 overleaf).

(3) The ship is inside the triangle formed by the marks or on the outer edge of the triangle formed by the marks (see Figs 8-26a/b overleaf).

(4) At least one of the *HSAs* should change rapidly as the ship alters position.



Fig 8-24. HSA Condition (1) - Marks are either all On or Near the Same Straight Line. Centre Mark is Nearest the Observer



Fig 8-25. HSA Condition (2) - The Centre Mark is Nearer the Ship than the Line Joining the other Two



Fig 8-26a. HSA Condition (3a) - Ship is Inside the Triangle Formed by the Marks



Fig 8-26b. HSA Condition (3b) - Ship is on Outer Edge of Triangle Formed by Marks

(0808) f. **When Not to Fix Using HSAs.** If the ship and the marks observed are all on the arc of the same circle (see Fig 8-27 below), the two *Position Circles* become one, and the two *HSAs* will cut at any point on the arc. **An *HSA Fix* is impossible in these circumstances.** In Fig 8-27, the beacon should have been chosen for the middle mark, and NOT the chimney.

g. **When Not to Fix Using Compass Bearings.** If the ship and the marks observed using compass bearings (instead of *HSAs*) are all on the arc of the same circle (as in Fig 8-27 below), and there is an unknown error in the compass**, this error will not be revealed by plotting.** The angles between the objects will be correct but the plotted bearings will always meet at some point on the arc of the circle. The plotted position will differ from the actual position dependent on the amount of the unknown error.

h. **Summary of When Not to Fix.** Never *Fix* the ship by *HSAs* or bearings when the ship and the objects observed are all on the arc of the same circle.


θ°
ø°
θ°
ø°
θ°
ø°
Some Possible Positions (etc), all on the arc of the same circle
Beacon
Chy

Fig 8-27. When Not to Fix Using HSAs or Bearings

i. **Rapid Plotting Without Instruments.** To enable *HSA Fixes* obtained to be plotted rapidly without instruments, an *HSA Lattice* of curves (see Fig 8-28 overleaf) may be constructed on the chart. Sets of curves are plotted from each of two pairs of marks and, if the angle between each pair is observed simultaneously, the *Fix* may be plotted immediately at the intersection of the two curves. The method for construction of the *HSA Lattice* is at Appendix 6.


A
B
C
50°
40°
30°
25°
20°
50°
40°
30°
25°
20°

Fig 8-28. HSA Lattice of Curves

0809. Bearing Lattice Fixes

To produce a *Bearing Lattice* for use with rapid plotting of visual *Fixes*, a lattice of bearing lines from two visually conspicuous objects is drawn on the chart (see Fig 8-29 below).

a. **Marks.** Marks should be suitably placed to give an acute angle of cut, ideally between 60˚ to 90˚ (a minimum angle of cut of 30˚ is acceptable). In Fig 8-29 (below), the acute angle of cut varies between 55˚ and 90˚. Depending on the distance of the objects and the *Scale* of the chart, lines may be drawn 1˚ to 5˚ apart. In Fig 8-29, the lines are drawn at 5˚ intervals, while two 'boxes' are illustrated at 1˚ intervals.

b. **Procedure.** A team of 3 is required: a 'plotter' to coordinate, record and plot the bearings, and two 'bearing takers'. The 'plotter' controls the rate of *Fixing* which should be about one *Fix* every 30 to 60 seconds. Noise level is reduced if headphone communication is available.


Fort (disused)
Sandway Pt.
Queen's Grounds
Fl(2)R.10s
Queens Ground
WESTERN CHANNEL
Dredged to
11·0m
Fl.W
New Rock
S.bkSh
S.Sh.P.G
fS.bkSh
Obstn
Wk
Fl.WR.10s19m12/9M
& Iso.4s12m10M
Horn(1)15s
4°10′W
50°20′N
CAWSAND BAY
Panther
Knap
Fl.G.5s
Knap
095°
090°
085°
080°
075°
070°
065°
060°
055°
015°
010°
005°
000°
355°
350°
345°
340°
335°
1c
2c
3c
4c
5c
330°

Fig 8-29. Bearing Lattice

0810. HSA Fixing Procedures

Successful rapid *Fixing* using *HSAs* and an *HSA Lattice* can only be achieved if there is a high standard of training and techniques. Special teams should be formed, as follows:

- Plotting/Course Control Officer
- Recorder
- Red Angle Taker
- Green Angle Taker

a. **Organisation.** When continuous *Fixing* is required, the angle takers should do a 20 minute trick. They should be positioned close together where they can best see the marks with good communications to the plotter; each *Fix* is recorded and plotted as the angle takers report their readings. *Fixes* should be plotted every 30-60 seconds. The *Index Error* of sextants must always be checked before use. The *Fixing* marks should be 'shot-up' beforehand to ensure they agree with the charted objects selected. Unless the *HSA Lattice* is drawn to a very large *Scale*, it will not usually be possible to plot to an accuracy of more than ± ½°, so angles need only be reported to the nearest ½°. But, if a *Station Pointer* is being used to plot the *Fixes* rather than an *HSA Lattice*, angles should be reported to the nearest 5' of arc. Either of the following *HSA Fixing* methods may be used, but it is easier to generate *DRs / EPs* with the 'Time Interval' method:

b. **Fixing by Time Intervals.** This method is more difficult to plot than Para 0810c.

- 5 - 10 seconds before the *Fix* is due, the recorder, using a stopwatch, gives the warning 'Standby' to the angle-takers.
- The angle-takers raise their sextants and align the marks. The lead angle-taker (whose angles are changing more quickly) and second are nominated.
- The second angle-taker reports 'On' when coincidence is obtained and then keeps the marks lined up.
- At the appropriate moment the recorder calls 'Time', and the lead angle-taker obtains coincidence and reports '*Fix*'. Both angle-takers record angles.
- The recorder notes the time of the *Fix* and the reported angles eg:
  'On the right, 60° 30′ (or Green 60° 30′)'.
  'On the left, 40° (or Red 40°)'.
- The *Fix* is plotted.

c. **By Angle Intervals.** This method is easier to plot than Para 0810b.

- The lead angle is usually chosen to coincide with one of the *HSA* curves drawn on the chart.
- The lead angle-taker pre-sets the sextant.
- As the marks near coincidence, the lead angle-taker calls 'Standby' and the second angle-taker aligns the marks.
- The lead angle-taker calls '*Fix*' as the marks come into coincidence
- The time of the *Fix* is recorded.
- The angle-takers report their angles and the *Fix* is plotted.

0811. Adjustment of Fixes for Compass Errors

a. **Compass Error Checks.** If it is suspected that a *Cocked Hat* has been caused by a compass error, first check that any known corrections have been applied correctly.

- **Gyro Errors.** *Gyro* error corrections should be applied as in Para 0121 (ie if gyro is HIGH, subtract error from observed bearing; if LOW, add error).
- **Magnetic Variation and Deviation.** *Magnetic Variation* and *Deviation* should be applied as in Para 0124 (ie subtract westerly *Variation* and *Deviation* from the *Magnetic Compass* bearing and add it when easterly; the mnemonics *'CADET* 'and *'CDMVT'* are useful for the conversion rules).

b. **Methods of Checking Gyro Error and Magnetic Deviation.** The *Gyro* error and / or *Magnetic Deviation* may be checked by any of the following methods:

- **Transit.** The compass bearing of two charted objects may be observed when they are in line (see Para 0803c) and the true or magnetic bearing taken from the chart. The difference between the observed and charted bearings will be the *Gyro* error (see Paras 0121e/f) or the *Magnetic Deviation* (see Para 0125 and Example 1-7).
- **Bearing of a Distant Object.** The ship (ideally at anchor) may be *Fixed* by *HSA*s, or may be alongside a jetty in a known geographic location. An observed bearing of a distant object may then be compared with the bearing taken from the chart and the error calculated. From the *Radian Rule* (see Para 0127), ½° subtends approximately 100 yards at 6 *n.miles*; so, if the ship's position is known to an accuracy of 100 yards, the compass error can be established to an accuracy of ½° using an object 6 *n.miles* away.
- **True Bearing of a Heavenly Body.** The true bearing of a heavenly body may be most easily and accurately calculated with *NAVPAC* software (DP 330; see Para 0210a), using the procedures at BR 45 Volume 2 Chapter 3. With data from the Nautical Almanac (NP 314), other methods include the *Cosine* formula, Weir's Azimuth Diagrams (Charts 5000 and 5001), Marine Sight Reduction Tables (NP 401), Air Navigation Sight Reduction Tables (NP 303), Concise Nautical Almanac Reduction Tables (NP 314), and the ABC Azimuth Tables / Amplitudes and Corrections Table in Norie's Nautical Tables (NP 320). Calculation details are at BR 45 Volume 2 Chapter 5.
- **Reduction of the Cocked Hat.** If it seems certain that the *Cocked Hat* is due to compass error alone, and none of the above three methods is available to resolve it, then the *Cocked Hat* may be reduced and the error found, as at Paras 0811d-e (opposite).
- **Magnetic Deviation - Gyro 'Comparison Swing'.** See Paras 0122g / 0125c.

c. **Reciprocal Compass Checks (RAS Operations).** Reciprocal compass checks may be carried out with other ships prior to conducting *Replenishment at Sea* (*RAS*) or similar close stationing operations. The procedure for carrying out reciprocal compass checks is at BR 45 Volume 6, Chapter 5. This method is NOT relevant for terrestrial *Fixing*.

(0811) d. **Reduction of the Cocked Hat - Station Pointer.** Assume that on taking a *Fix*, a *Cocked Hat* results (see Fig 8-30 below) and that the same compass error exists (see Note 8-5) on all three bearings (*A, B* and *C*). To reduce the *Cocked Hat*, subtract the three observed bearings from each other to establish the two angles between them (in Fig 8-30, 345½˚-051˚= 65½˚ and 097˚-051˚= 46˚). These angles are then set on a *Station Pointer* and the ship's position found by rotating the instrument until each arm of the *Station Pointer* goes through the charted position of the relevant mark. In the absence of a *Station Pointer*, the angles can be drawn on a *Douglas Protractor* (see Para 0811g overleaf) or piece of tracing paper and the same procedure adopted. The charted bearing of the furthest object may then be compared with the observed bearing; the difference is the compass error (*Gyro* error 3˚ Low in Fig 8-30).

e. **Reduction of the Cocked Hat - Iteration.** An alternative (iterative) method for establishing a (fixed) compass error is to add (or subtract) 1˚ to each bearing and re-plot the *Fix*. Provided that the same compass error exists (ie not *Random Errors* - see Note 8-5) on all three bearings, the compass error may be established by an iterative process of gradually refining its size and direction. In Fig 8-30, an *Gyro* error of 3˚ Low is found. A similar process may be adopted with *WECDIS / ECDIS.*

Note 8-5. *Random Errors are explained at Paras 1611-1612; Cocked Hats resulting from different Random Errors on each bearing are covered at Appendix 10 Para 3e.*



Fig 8-30. The Cocked Hat Resulting from Gyro Error (*Same Error on all Bearings*)

f. **Fix Position - Inside or Outside the Cocked Hat.** The ship's position may well be OUTSIDE the *Cocked Hat* (as demonstrated at Fig 8-30 above). There may be real danger in assuming that the ship's position will always be inside a *Cocked Hat*.

(0811) g. **The Douglas Protractor.** The *Douglas Protractor* is at Fig 8-31 (below), with bearings from Fig 8-30 (previous page) drawn on it.


N
320 40
330 30
340 20
350 10
10 350
20 340
30 330
40 320
310 50
300 60
290 70
280 80
270 90
260 100
250 110
240 120
230 130
50 310
60 300
70 290
80 280
90 270
100 260
110 250
120 240
130 230
220 160
210 150
200 190
190 170
180 180
170 190
160 200
150 210
140 220
4 0
3 0
2 0
1 0

Fig 8-31. The Douglas Protractor (*with bearings from Fig 8-30 drawn on*)

0812. Action on Obtaining a Cocked Hat

Assessment of the size of a *Cocked Hat* is a subjective judgement. Noting the danger from automatically assuming (potentially in error) that the ship's position is inside a *Cocked Hat* (see Para 0811f / Fig 8-30 previous page), the following actions should be taken:

a. **Small Cocked Hat.** If the *Cocked Hat* is small and the ship is not endangered, the centre may usually be taken as the ship's position, without undue risk.

b. **Large Cocked Hat.** If the *Cocked Hat* is large and it seems clear that the same error is NOT applicable to each bearing, then either the *Fix* position should be taken as the corner of the *Cocked Hat* nearest to danger (taking the ship's subsequent movements into account) or, the *Fix* should be disregarded and reliance placed on the *DR / EP* until another *Fix* is obtained. In any case, if a large *Cocked Hat* has been obtained, a new *Fix* should be taken as soon as possible. **If the ship is in the vicinity of immediate danger, it should be turned into safe water or stopped using astern power (as appropriate) until the uncertainty about its position is resolved.**

CHAPTER 9

AIDS TO NAVIGATION

CONTENTS

Para

0901. Scope of Chapter
0902. Coverage of Digital Navigation, Electronic Charts, Radar and its Applications

SECTION 1 - SATELLITE NAVIGATION, LORAN AND E-NAV / DIGITAL NAV

0910. GPS (NAVSTAR Global Positioning System)
0911. DGPS (Differential Global Positioning System)
0912. Eurofix - Transmitting DGPS Corrections on LORAN-C
0913. GLONASS
0914. Galileo
0915. GNSS (GPS, GLONASS, SBAS and Galileo)
0916. Vulnerability of Satellite Navigation Systems to Jamming / Interference / Spoofing
0917. GMDSS - Integral GPS Capability
0918. LORAN-C and ‘Enhanced LORAN’ (eLORAN)
0919. IMO ‘e-Navigation’ and RN / RFA ‘Digital Navigation’ - Definitions

SECTION 2 - COMPASSES, INERTIAL NAV SYSTEMS, ECHO SOUNDERS & LOGS

0920. Gyro Compass Principles
0921. Inertial Navigation Systems (INS) Principles
0922. Magnetic Compasses
0923. Echo Sounder Principles
0924. Echo Sounder Reporting Procedures
0925. Speed & Distance Measuring Equipment (Speed Logs)
0926. Night Vision Aids and Electro Optic Surveillance Systems (EOSS)

SECTION 3 - LIGHTS AND FOG SIGNALS

0930. Details, Characteristics and Nomenclature of Lights
0931. Admiralty List of Lights & Fog Signals - Paper and Digital Versions
0932. Maximum Ranges of Lights
0933. Using Lights - Aide Memoire
0934. Fog Signals - Types and Uses

SECTION 4 - BUOYS, OTHER FLOATING STRUCTURES AND BEACONS

0940. Buoy and Beacon Types
0941. IALA Maritime System of Buoyage - Regions A and B
0942. Using Buoys and Other Floating Structures for Navigation - Procedures

SECTION 5 - AUTOMATIC IDENTIFICATION SYSTEMS (AIS) AND VHF RADIO

0950. Concept of AIS and VHF Radio Use
0951. AIS - Operation
0952. Virtual (or Pseudo) AIS Contacts
0953. Incorrect AIS Data
0954. Collision Avoidance - Use of AIS and VHF Radio

INTENTIONALLY BLANK

CHAPTER 9

AIDS TO NAVIGATION

0901. Scope of Chapter

Chapter 9 provides a summary of 'Aids to Navigation', including definitions of *IMO* '*e-Nav*' and RN / RFA '*Digital Navigation*'. Further details are at BR 45 Volumes 3 and 8, and in *United Kingdom Hydrographic Office (UKHO*) publications, as specified in the appropriate paragraphs of this chapter. This chapter replaces Chapter 10 of the 1987 Edition of this book.

0902. Coverage of Digital Navigation, Electronic Charts, Radar and its Applications

Digital Navigation and '*Electronic Chart*' concepts are at Paras 0630-0633 and procedures for their use are at Paras 0720-0721. Use of radar is at Para 1232 *(Coastal Navigation*) and Paras 1316 / 1325 (*Blind Pilotage*). Radar and its applications is at Chapter 15.

0903-0909. Spare

SECTION 1 - SATELLITE NAVIGATION, LORAN AND E-NAV / DIGITAL NAV

0910. GPS (NAVSTAR Global Positioning System)

The following information on *Global Positioning System* (*GPS*) is a brief summary; for details see BR 45 Volume 3 and *Admiralty List of Radio Signals* (*ALRS*) Vol 2 (NP 282).

a. **GPS Configuration.** *NAVSTAR* in an acronym for 'NAVigation Satellite Timing And Ranging'. *NAVSTAR GPS* is a US Dept of Defence world-wide satellite navigation system providing very accurate continuous position, velocity and time. 24 operational satellites are uniformly distributed in 6 orbital planes, each inclined to the plane of the *Equator* at 55°, at a height of 20,200 km (10,900 *n.miles*). This configuration ensures that at least 4 satellites with suitable elevations are 'visible' to a receiver anywhere on the Earth's surface at any time (except in *Polar* regions where coverage is reduced).

b. **Levels of Accuracy.** There are 3 levels of *GPS* accuracy (*PPS, SPS*, *DGPS*). For details of *Dilution Of Precision (DOP)* / *Estimated Position Error (EPE)* see Para 1806g.

- **PPS.** Encrypted *Precise Positioning Service* (*PPS*) for military users.
- **SPS.** *Standard Positioning Service* (*SPS*) for commercial users. Accuracies in the order of 8-13 metres (95%) may be expected with modern receivers.
- **DGPS.** *Differential GPS* (*DGPS*) for all users(see Para 0911). Accuracies in the order of 3-4 metres (95%) or better may be expected.

c. **Spheroid and Datum.** *GPS* is referenced to *WGS 84*. Most modern charts and all *WECDIS / ECDIS / ECS* equipments are referenced to *WGS 84*, but if *GPS* positions are used with older charts referenced to other horizontal *Geodetic Datum*s, a '*Datum Shift*' must be applied to *GPS* (*WGS 84*) positions before they are plotted. Details of the appropriate *Datum Shift* are normally found on the chart.

d. **Pseudo Ranging.** '*Pseudo Ranging*' is used to calculate the geographical position of the *GPS* receiver, using atomic clocks in the satellites and the propagation time of each satellite transmission. To obtain a two-dimensional *Fix*, the receiver must obtain a minimum of 3 *Pseudo Ranges* so that the processor can remove the effects of receiver clock offset error, satellite clock / *GPS* system time errors and atmospheric propagation delays. A minimum of 4 *Pseudo Ranges* will give a three-dimensional *Fix*.

0911. DGPS (Differential Global Positioning System)

The following information on *Differential GPS* (*DGPS*) is a brief summary; for details see BR 45 Volume 3 and *ALRS* Volume 2 (NP 282).

a. **DGPS Method.** Fixed *DGPS* base stations determine real-time errors in received *GPS Pseudo Ranges* for each 'visible' satellite. The corrections are then transmitted directly to *DGPS* receivers in vehicles in the vicinity (typically within about 1000 km / 540 *n.miles*), normally using selected maritime radiobeacon frequencies to do so. Corrections may also be transmitted by satellite links (eg INMARSAT), or in certain areas by *Eurofix* (see Para 0912) using *LORAN-C* stations. *DGPS* receivers in receipt of corrections apply them automatically to *GPS* data before establishing a *DGPS Fix*. *DGPS* will only work when the vehicle is within range of the *DGPS* station and when using the satellites being monitored by that station.

b. **DGPS Accuracy.** As stated at Para 0910b, *DGPS* accuracies in the order of 3-4 metres (95%) or better may be expected.

0912. Eurofix - Transmitting DGPS Corrections on LORAN-C

The following information on *Eurofix* is a brief summary; for details see BR 45 Volume 3, and *ALRS* Volume 2 (NP 282).

a. **Eurofix Method.** *Eurofix* uses selected *Northwest European LORAN-C System (NELS)* stations to transmit *DGPS* corrections (see Para 0911 above), without corruption of the *LORAN-C* signal, to satellite receivers in vehicles within about 1000 km / 540 *n.miles*. *Eurofix* signal channel allocations include future provision for *DGLONASS* , *eLORAN* and *DChayka* (Russian *LORAN* -C equivalent) corrections.

b. **Eurofix Availabilty.** *Eurofix* is currently (2008) under development and may NOT yet be available from all *NELS* stations. *ALRS* Volume 2 (NP 282) should be consulted for details of available transmitting stations.

0913. GLONASS

The following information on *GLONASS* (an acronym for 'GLObal NAvigation Satellite System') is a brief summary; for details see *ALRS* Volume 2 (NP 282).

a. **GLONASS Configuration..** *GLONASS* is operated by the Russian Federation Space Forces and is similar in nature to *GPS* (see Para 0910), except that *WGS 84* is not used. When fully operational (planned for 2009), it will provide a world-wide satellite navigation system giving very accurate continuous position, velocity and time. 24 operational satellites will be uniformly distributed in 3 orbital planes, each inclined to the plane of the *Equator* at 64.8°, at a height of 19,100 km (10,313 *n.miles*). This configuration improves *Polar* region coverage, as compared to *GPS*. In March 2008, 16 operational satellites were in orbit. *GLONASS* provides encrypted and non-encrypted services.

b. **Spheroid and Datum.** The *Spheroid* and *Datum* used by *GLONASS* is *PZ 90*, referenced to the *Soviet Geocentric Co-ordinate System 1990* (*SGS 90*). Differences between *PZ 90* and *WGS 84* are less than 15m with a mean average of about 5m.

0914. Galileo

The following information on *Galileo* is a brief summary; for details see *ALRS* Volume 2 (NP 282).

a. **Galileo Origin.** The European Union is developing an independent satellite navigation constellation named '*Galileo*'. The system is not yet (2008) fully operational. *ALRS* Volume 2 (NP 282) should be consulted for details of available satellites.

b. **Galileo Configuration.** *Galileo* is a world-wide satellite navigation system, similar to *GPS* (see Paras 0910), providing extremely accurate continuous position, velocity and time. 27 satellites (plus 3 active spares) will be distributed in 3 orbital planes, each inclined to the plane of the *Equator* at 56˚, at an altitude of 23,222 km (12,540 *n.miles*). This configuration will provide good cover up to 75˚ *Latitude*.

c. **Levels of Service / Accuracy.** Five levels of service / accuracy will be available:

- **Open Service (OS).** The *Open Service* (*OS*) will be a basic level dedicated to consumer applications and general interest navigation.
- **Commercial Service (CS).** The restricted access *Commercial Service* (*CS*) will be used for commercial and professional applications that require superior performance. Accuracies in the order of 1 metre (95%) may be expected.
- **Public Regulated Service (PRS).** The restricted access *Public Regulated Service* (*PRS*) will be used for governmental applications that require high continuity characteristics. Accuracies in the order of 1 metre (95%) may be expected.
- **Safety of Life Service (SoL).** The highly stringent *Safety of Life Service* (*SoL*) will be used where passenger safety is critical.
- **Search and Rescue Service (SAR).** The *Search and Rescue Service* (*SAR*) will be used for pinpointing the location of world-wide distress messages.

0915. GNSS (GPS, GLONASS, SBAS and Galileo)

The following information on *Global Navigation Satellite Systems* (*GNSS*) is a brief summary; for details see *ALRS* Volume 2 (NP 282). *GNSS* is the generic term for satellite navigation systems that provide autonomous global geo-spatial coverage.

a. **GPS and GLONASS Integrated Use.** *GLONASS* provides advantages for high-*Latitude* cover (see Para 0913) while *GPS* favours mid-*Latitudes* (see Para 0910), thus a receiver able to operate with both systems would offer faster acquisition times, optimum results at all *Latitudes* and an increased number of 'visible' satellites. Although there are technical complications, dual receiver technology continues to make significant advances and a wide range of products are commercially available.

b. **Satellite Based Augmentation System (SBAS).** The *Satellite Based Augmentation Systems* (*SBAS*), primarily developed for aeronautical purposes, are overlay systems offering users greater reliability, accuracy, availability, integrity and continuity. *SBAS* signals are broadcast from several geo-stationary communications satellites and provide corrections for *GPS* measurements which enhance the accuracy of the *GPS* receiver.

(0915) c. **SBAS Components.** The 3 major components of *SBAS* are:

- *EGNOS* (*European Geostationary Navigation Overlay Service*)
- *WAAS* (*Wide Area Augmentation System*) [American]
- *MSAS* (*MTSAT Satellite Augmentation System)* [Japanese]
  (*MTSAT = Multi-functional Transport Satellite*]

These systems are currently (2008) under development. See also Paras 1806g/h.

d. **GNSS: SBAS + GPS + GLONASS (+ Galileo).** The current and future proposed *GNSS-1* structure is illustrated at Fig 9-1 (below). In summary, *SBAS* is composed of *EGNOS, WAAS* and *MSAS*; *GNSS-1* is composed of *GPS, SBAS* and *GLONASS*. The integration of *Galileo* (see Para 0914) into a proposed *GNSS-2* structure is currently (2008) still under discussion.


EGNOS
WAAS
MSAS
GPS
SBAS
GLONASS
Galileo (TBC)
GNSS-1
GNSS-2 (TBC)
GNSS
Note. The structure of GNSS-2 and the possible integration of Galileo into it, is currently (2008) still under discussion.

Fig 9-1. GNSS: SBAS + GPS + GLONASS (+ Galileo)

0916. Vulnerability of Satellite Navigation Systems to Jamming / Interference / Spoofing

a. **Threat.** Unless an anti-jamming antennae is fitted, *GPS/DGPS* and other satellite navigation systems are extremely vulnerable to degradation or denial (‘*GPS Denial*’), due to deliberate ‘Jamming’, accidental interference (eg TV stations) or ‘Spoofing’ (*deliberate introduction of a signal to seduce and mislead the GPS / DGPS receiver with graceful positional degradation*). Even simple defects (eg a break in the aerial leads or connection) can result in the receiver switching to *DR / EP* automatically; if this change is not noticed and allowance is not made for any *Currents* or *Tidal Streams*, serious positional errors can result (see incidents at Para 0805a [Note 8-4]).

b. **Remedy.** To guard against such events, in all circumstances *GPS / DGPS* (and other satellite navigation systems) should be checked frequently against other available *Fixing* sources and against the correct *DR / EP*, in accordance with Para 0805a.

0917. GMDSS - Integral GPS Capability

Global Maritime Distress and Safety System (*GMDSS*) equipments usually have an integral *GPS* (*SPS*) receiver and *GPS* position information can be accessed from the *GMDSS* equipment control screens. However, on some *GMDSS* equipments this position may only be displayed to the nearest whole minute; if so, it should normally only be used to check the veracity of other installed *GPS* equipments.

0918. LORAN-C and 'Enhanced LORAN' (eLORAN)

The following information on *LORAN* is a brief summary; for details, see BR 45 Volume 3 and *ALRS* Volume 2 (NP 282).

a. **LORAN Acronym.** *LORAN* in an acronym for 'LOng RAnge Navigation'; the earliest version (in 1957) was *LORAN-A*, but this was later superseded by *LORAN-C*.

b. **LORAN-C Configuration.** *LORAN-C* is a 100 kHz electronic position *Fixing* system using pulse transmission, covering the North West Atlantic including the Gulf of Mexico, the North Pacific including the South China Sea, North West Europe and the Arabian Sea. A *LORAN-C* chain consists of a master station and two, three or four slave stations sited around it at distances of about 600-1000 *n.miles*. Ground wave cover extends to a range of 800-1200 *n.miles*. Sky wave cover extends to 1800 - 2400 *n.miles* at night; there is usually some sky wave cover by day.

c. **LORAN-C Levels of Accuracy.** *Fixing* accuracy is better than 0.25 n miles (95%) within the ground wave and may be as good as 0.1 n mile close to the baseline between the stations of a pattern. *Fixing* accuracy is reduced to about 10-20 n miles (95%) when using the sky wave.

d. **LORAN-C Spheroid / Datum.** *LORAN-C* uses *WGS 84* (see Para 0910c).

e. **'Enhanced LORAN' (eLORAN).** *Enhanced LORAN (eLORAN)* is currently (2008) under development; it includes differential *eLORAN* corrections in the signal, with positional accuracy <10 metres achieved in trials. Operational systems are unlikely immediately but *eLORAN* may soon be a possible alternative to *GPS* in some areas.

0919. IMO 'e-Navigation' and RN / RFA 'Digital Navigation' - Definitions

The concept of '*e-Navigation*' is an *IMO* -led initiative based on the harmonisation of marine navigation systems and supporting shore services driven by user needs. It is currently (2008) under development at *IMO* and does not have any legal force at present.

a. **Possible Confusion between '*e-Navigation*' and *'Digital Navigation'*.** The term '*e-Navigation*' should NOT be confused with the term '*Digital Navigation*' used in this book. Their respective definitions (and source data) are at Paras 0919b/c (below)

b. **Provisional Definition of 'e-Navigation'.** The term '*e-Navigation*' has been defined provisionally (2007) by *IMO* as:

> "*'E-Navigation'* is the harmonised collection, integration, exchange, presentation and analysis of maritime information onboard and ashore by electronic means to enhance berth to berth navigation and related services, for safety and security at sea and protection of the marine environment." *[Source: IMO NAV 53 WP.8 e-NAV3 Output-11*].

c. **Digital Navigation.** The term '*Digital Navigation*' used in the RN / RFA does NOT change existing navigation planning / execution principles and is defined as:

> "*'Digital Navigation'* is navigation on *ENCs/RNCs* (or other electronic charting products) using *WECDIS / ECDIS* equipments, rather than on paper charts other than for back-up purposes." [*Repeated at Para 1911. Source: BR 45 Volume 8 Para 0102*].

SECTION 2 - COMPASSES, INERTIAL NAV SYSTEMS, ECHO SOUNDERS & LOGS

0920. Gyro Compass Principles

Details of *Gyro Compass* use and error correction are at Para 0121. The following information on *Gyro Compass* principles is a summary; for details see BR 45 Volumes 3 and 9.

a. **Gyroscope Properties.** A rotating body, such as a gyro wheel (*Gyroscope*), has two inherent properties, *Gyroscopic Inertia* and *Precession*, both of which are crucial to *Gyro Compasses*.

- **Gyroscopic Inertia.** A rotating body has angular momentum, and in accordance with Newton's First Law of Motion, its *Spin Axis* will point at a fixed position in space until an external force is applied. The larger its mass and higher its rotational speed, the larger will be the angular momentum and thus the more stable will be the *'Rigidity-in-Space*' of the body's *Spin Axis*.

- **Precession.** Any attempt to **Tilt** or **Turn** a rotating body (*Gyroscope*) by an external force results in a combination of the 'force vector' and the 'angular momentum vector' acting on the body. The effect is that the *Spin Axis* will always move in a plane that is 90° ahead of the applied force and in the direction of wheel rotation. This can be summarised as:
  - ▸ Attempt to **Tilt** a *Gyroscope* and it will **Turn.**
  - ▸ Attempt to **Turn** a *Gyroscope* and it will **Tilt**.

  This is easily demonstrated on a moving bicycle (the wheels of which are two simple *Gyroscope*s); to **Turn** left the rider leans (**Tilts**) inwards, and the front wheel **Turns** left automatically. The rear wheel would do the same but is constrained by the bicycle frame.

b. **North-Finding Gyro Compasses.** Unless started pointing directly at the *Celestial Pole*, the axis of a 'free' rotating *Gyroscope* on the Earth's surface will appear to rotate about the *Celestial Pole* with East-West 'Drift' and North-South 'Tilt', due to the rotation of the Earth beneath it. To make a free *Gyroscope* into a North-finding *Gyro Compass*, this 'Drift' rotation must be compensated, a 'Gravity Control' introduced for 'Tilt', and then 'Tilt' must 'damped' into a spiral which will settle on True North.

- **Earth's Rotation Drift Compensation.** The compensation necessary for the East-West'Drift' is proportional to both *Latitude* and Hemisphere. It is achieved by applying a suitable force to the side of the casing, originally as a weight called the '*Latitude Rider*', but now achieved electronically.

- **North-Seeking.** To make the *Gyro* 'North-seeking', a 'Gravity Control' was introduced for 'Tilt'; originally the casing was made top-heavy by a theoretical 'bail-weight', but is now achieved electronically. This resulted in the *Gyro* making an elliptical rotation about North and the horizontal (ie 'North-seeking' or 'undamped', but NOT 'North-finding'). See Fig 9-2a opposite.

- **North-Finding.** To make the *Gyro* North-finding, an unequal *Precession* must be introduced, resulting in the elliptical 'undamped' motion being changed into a spiral 'damped' motion, settling horizontally on True North. This was originally achieved by slightly offsetting the *Gyro*'s bottom cone bearing from the vertical plane, but is now achieved electronically. See Fig 9-2b opposite.



Fig 9-2a. North-Seeking Gyro Movement



Fig 9-2b. North-Finding Gyro Movement

(The Pole Star is used above as an approximation for the North Celestial Pole)

(0920) c. **Gyro Compasses - Other Controls.** The Earth rotates to the East at about 900 kn at the *Equator* and 0 kn at the *Poles*; at intermediate *Latitudes* it is proportional to the Cosine of the *Latitude.* Provided the Earth's rotational speed is not too small (see Para 0920f below), a *Gyro Compass* will settle in the *Meridian*, normal to the Earth's rotation, but ship's movement (speed / *Heading*) and acceleration errors as a result of turns (*Ballistic Deflection* and *Ballistic Tilt*) will affect this. Additional controls are thus necessary, in the form of *Speed Log* and accelerometer inputs respectively.

d. **Gyro Compasses - User Inputs / Checks.** The correct *Latitude* setting (see Para 0920b 1st bullet) and *Speed Log* inputs are essential for accurate *Gyro Compass* results. Both can be applied manually by the user, but speed is normally input automatically; the *Latitude* on start-up normally has to be initialised by the user, thereafter it is automatic on most modern systems. Automatic *Gyro Compass* settings should be checked periodically. *Gyro Compass* errors should be checked frequently (see Para 0121).

e. **Modern Gyro Compasses.** *Gyro Compasses* have evolved over the last century from simple rotating wheels, to rotating spheres on almost frictionless gas bearings to the current generation of *Ring Laser Gyros* (*RLGs*) and *Fibre Optic Gyros* (*FOGs*) which have virtually no moving parts and rely on two coherent light beams passing around a closed path in opposite directions. Due to changes in interference patterns, *RLG / FOGs* can behave as a rotational sensor and thus may be used as a very accurate *Gyro Compass.* The most sophisticated *Gyro Compasses* have more than one gyro with *Spin Axes* 90° apart, and can provide not only a very accurate heading output but also the local vertical; they may thus be used for weapon and other stabilisation purposes.

f. **Very High (Polar) Latitudes - Directional Gyro Mode.** At very high (*Polar*) *Latitudes*, typically above about 80°-84°, a North-finding *Gyro Compass* becomes ineffective, partly due the greatly reduced rotational speed of the Earth at such *Latitudes* (see Para 0920c) and partly due to the convergence of *Meridians* near the *Poles*. The requirement for a North-finding *Gyro Compass* is thus replaced by one which will indicate and maintain a *Great Circle* course. This is achieved by making the *Gyro Compass* behave as a simple *Gyroscope*, pointing in a fixed direction in space (see Para 0920a 1st bullet); this is known as '*Directional Gyro*' (*DG*) mode and most modern *Gyro Compasses* have this facility. Once in *DG* mode, '*Grid Navigation*' is conducted on a *Polar Stereographic* chart (see details at BR 45 Volume 9).

0921. Inertial Navigation Systems (INS) Principles

The following information on *Inertial Navigation Systems* (*INS*) principles is a brief summary; for details see BR 45 Volume 3.

a. **Principles of Inertial Navigation Systems (INS).** An *INS* comprises the equivalent of 3 *Gyro Compasses* with their *Spin Axes* at 90˚ from each other; in practice, one of these *Gyro Compasses* may be replaced or augmented by accelerometers. It works by measuring accelerations produced by changes in course and speed; its computer integrates these accelerations into the distance and direction that the ship has moved from the starting position and converts these to *Latitude* and *Longitude* to give the present position. As an *INS* cannot measure absolute position, it is necessary to initialise it with a start position, and usual to monitor its performance against other navaids.

b. **Modern INS - Ring Laser Gyros (RLGs).** The limitations of gyros and accelerometers in early systems necessitated mounting them on stabilised gimbal platforms. *RLGs* do NOT require to be fitted on a stabilised gimbal platform, and so can be ‘strapped down’ (bolted) to the ship or aircraft structure.

c. **Use of INS.** *INS* are widely fitted in commercial and military aircraft, submarines, other warships and in many survey vessels. As well as position, *INS* also provides a very accurate heading output and the local vertical, and thus may be used for weapon and other stabilisation purposes.

0922. Magnetic Compasses

a. **Application.** A summary of the principles of magnetism and its application for the uses, errors and error corrections of *Magnetic Compasses* is at Paras 0122-0125.

b. **Magnetism and Magnetic Compass Principles.** A full explanation of the principles of magnetism, *Degaussing, Magnetic Compass* adjustment and correction, and the theory / limitations of *Fluxgate (Magnetic) Compasses* is at BR 45 Volume 3.

0923. Echo Sounder Principles

The following information on *Echo Sounder*s is a brief summary; for details see BR 45 Volume 3. **Standard depth / sounding reporting procedures are at Para 0924.** Guidance on specific uses of *Echo Sounder*s in *Coastal Navigation, Pilotage, Blind Pilotage* and *Minor Surveys* are at Chapters 12, 13 and 18 respectively.

a. **Importance of the Echo Sounder.** At sea, the nearest point of land is almost always the sea-bed. For example, consider a position in the busy English Channel, some 20 *n.miles* south of Plymouth Sound; the charted depths there are about 70m, which is generally regarded as relatively ‘deep’ water. However, when seen in a horizontal context, 70m is about one-third of a cable, and few ships would willingly venture within that (horizontal) distance of the *Limiting Danger Line* (*LDL*) unless berthing. Even in deepest ocean, depths rarely exceed 3 *n.miles* and are frequently very much less (minimum depths across the Mid-Atlantic Ridge are only a few hundred metres). **Seen in that context, the nearest point of land is almost always the sea-bed and thus the *Echo Sounder* is a vitally important piece of equipment for navigational safety.**

(0923) b. **Outline Concept.** In a vertical *Echo Sounder*, a pulse of sound is transmitted towards the sea-bed from a transducer on the underwater hull of a ship. On reaching the sea-bed, part of the sound is reflected back. Given the speed of sound in water (usually 1500 m/s) and the time interval between transmission and reception, the depth may be easily calculated. Depth may be displayed graphically or numerically.

c. **Waterline Depth v. 'Keel' Depth.** The pulse from the transmitting transducer is picked up almost instantaneously by the receiving transducer and is displayed on the recorder as a continuous 'transmission mark' line.

- **Waterline Depth.** If the transmission mark is set to the distance of the transducers below the sea surface, the recorder will show the depth of water below the waterline (this is the recommended default setting for most RN surface ships - see Para 0924e). Ships operating in shallow water areas with little clearance under the keel may experience *Squat* (see BR 45 Volume 6 Chapter 2) and this may affect the waterline depth setting in some cases.
- **'Keel' Depth.** If the transmission mark is set to zero of the scale, depth is recorded below the transducers (this is the recommended default setting for submarines and surface ships with substantially variable draughts - see Para 0924e). If the transducers are level with the keel, this depth may be considered as the 'keel depth'. If they are not level, a further adjustment to the transmission mark will be necessary.

d. **Separation Correction.** It may be necessary to apply a correction to recorded soundings in shallow water if the transducers are some distance apart laterally. See details at BR 45 Volume 3.

e. **Calibration of Echo Sounders.** *Echo Sounders* should be checked against the hand leadline periodically (see below). Several readings at various depths should be obtained for constructing a graph of *Echo Sounder* readings against leadline readings. Adjustments can then be made to the *Echo Sounder*, or the soundings themselves corrected. An *Echo Sounder* should be calibrated on each of the following occasions:

- On completion of a refit.
- When any part of the equipment is changed.
- Before any survey is carried out or a line of soundings obtained.
- If there is doubt about its accuracy.
- Annually.

f. **Interpretation of Soundings - False Echoes.** In general, hard sand, coral, chalk and rock give a good echo; thick mud gives a bad echo. *Echo Sounders* which can sound to great depths are subject to '2nd phase' errors, by reading on the 2nd (or even 3rd) pulse. In this case, the returning echo is not received until after the *Echo Sounder* has transmitted the next pulse(s); the prudent mariner should assume the vessel is standing into danger until the correct depth is established. Other false echoes may be caused by shoals of fish, water layers of different temperatures and density, salt and fresh water submarine springs, kelp or weed, side echoes, turbulence in the water, interference from incorrect 'Gain' settings or other sonars, or multiple reflection echoes between the ship's hull and the sea-bed in shallow water. See details at BR 45 Volume 3.

0924. Echo Sounder Reporting Procedures

Unless otherwise ordered by the NO or OOW, reports by the *Echo Sounder* operator should be made as follows. A copy of this instruction should be displayed at the *Echo Sounder*.

a. **Reporting Terms ("Depths" or "Soundings").**

- **Ships.** In surface ships, readings should be reported as 'Depth' (eg "Depth 20 metres shoaling").
- **Submarines.** In submarines 'Depth' means the depth of the submarine below the surface, and so in submarines all *Echo Sounder* readings should be reported as 'Sounding' (eg "Sounding 20 metres shoaling").

b. **Standard Reports.** When *Special Sea Dutymen* (*SSD*) or their equivalents are closed up, or at any other times when ordered, an additional person should close up to monitor and report depths / soundings. Standard reports should be at intervals of not greater than 1 minute, or as follows:

Depths / Soundings 0-20 metres:	**Report every 1 metre**
Depths / Soundings 20-40 metres:	**Report every 5 metres**
Depths / Soundings greater than 40 metres:	**Report every 10 metres**

c. **Use of Suffixes with Standard Reports.** The operator should suffix the depth / sounding with 'Steady', 'Deepening','Shoaling' or 'Below Minimum Depth / Sounding'.

d. **Briefing and Acknowledgement.** In *Pilotage*, the *Echo Sounder* operator should be briefed by the NO on the minimum expected depth / sounding on each leg. Each depth / sounding report is to be acknowledged by the Command Team (ideally in the order Chart Assistant, NO or OOW and CO in ships). If a sounding below the briefed minimum expected depth is reported but not acknowledged, the *Echo Sounder* operator is to repeat the report more loudly and urgently, until an acknowledgement is given.

e. **Soundings From Waterline / Transducer Depths.** Except where exempted below or where equipment limitations dictate otherwise, *Echo Sounder*s are to be adjusted to read depths from the waterline, unless specifically ordered otherwise by the NO. Exceptionally, as an exemption, in vessels which have substantially variable draughts (ie submarines and ships with flooding docks or equivalent) the CO / NO should normally order depths / soundings to be reported as transducer depths / soundings, because waterline depths / soundings may lead to substantial errors. In all cases each *Echo Sounder* is to be clearly labelled with the position from which it is reading.

f. **Reporting Units.** *Echo Sounder* readings should be reported in the units shown on the navigational chart in use. In the rare event of using a chart with soundings in feet or fathoms, the *Echo Sounder* operator should transpose the units before reporting the depth / sounding, by using a conversion table (eg NP 720).

g. **Annotation of Echo Sounder Trace.** In submarines, when an *Echo Sounder* operator is closed up it is mandatory for the paper trace to be annotated on the occasions listed below. This procedure is NOT mandatory for use in ships but is recommended.

- Every 6 minutes with a four figure time.
- At every *Fix* with a four figure time.
- All alterations of course and speed.
- Any change in a surfaced submarine's draught (eg trimming down).
- Any incident or other useful information (eg buoys abeam, boat transfers etc).

0925. Speed & Distance Measuring Equipment (Speed Logs)

The following information on 'Speed & Distance Measuring Equipment' (*Speed Logs*) is a brief summary; for details see BR 45 Volume 3.

a. **Concepts and Capabilities.** *Speed Logs* are used to record the ship's speed and distance run. This is usually through the water (ie not allowing for *Leeway*, *Tidal Stream*, *Current* or *Surface Drift*), although *Sonar Speed Logs* of various types may be used to determine the *Ground Track*. Provided they are properly calibrated and well sited on the hull, the accuracy of *Speed Logs* should be better than 2% (95% probability) for speed and distance through the water.

b. **Single-Axis Electromagnetic Speed Logs.** Single-axis electromagnetic (EM) *Speed Logs* are widely fitted in warships and other vessels. They have an electromagnet mounted in a sensing head which is fitted on the hull of a ship; the head may be on a fixed probe, a retractable rodmeter, or in a sensor flush with the hull. Probes are more accurate than a flush sensor because they usually protrude beyond the ship's *Boundary Layer* water flow. A small alternating current energises the electromagnet to set up a magnetic field. As the ship moves through the water, the sensor's magnetic field induces a voltage in the water. This voltage, which is proportional to the relative speed of the sensor to the water, is picked up by electrodes in the sensor and applied to electronic circuits where it is converted into speed and distance. The faster the water moves past the sensor the greater the voltage generated and the higher the speed recorded.

c. **Two-Axis EM Speed Logs.** A two-axis EM *Speed Log* has similarities to the single-axis version but has a discus shaped sensor, aligned so that each axis measures the ship's forward and athwartships speed through the water. Two pairs of electrodes pick up the induced voltages, which are proportional to the fore-and-aft and athwartships components of the water flowing past the sensor; these are applied to electronic circuits where they are converted into the resulting *Ground Track*. A two-axis EM *Speed Log* will therefore produce a good *DR* track through the water, but suffers from inaccuracies at very low speeds.

d. **Two-Axis Sonar Speed Logs.** Two-axis *Sonar Speed Logs* are typically fitted in vessels where high accuracy *Ground Tracks* are required, particularly at low speeds. They measure speed by processing the echoes derived from sonar pulses projected towards the sea bed. The signal processor can be based on either *Doppler* or *Correlation* principles. There are two types of *Correlation Speed Logs*, one being based on time (*Temporal Correlation Log*s), the other based on separation distance (*Spatial Correlation Logs*). *Sonar Speed Logs* are superior to conventional EM *Speed Logs* in several respects:

- *Sonar Speed Logs* measure the ship's ground speed over the sea bed in suitable depths of water.
- The accuracy of *Sonar Speed Logs* is typically of an order better than conventional EM *Speed Logs*, particularly at low speed.
- *Sonar Speed Logs* may be flush mounted without loss of accuracy and are thus less likely to be damaged.

(0925) e. **Pitometer Logs.** *Pitometer Speed Logs* use the difference between the static water pressure when stationary and the impact water pressure from a moving ship acting on a rodmeter probe protruding below the hull. They have superseded by EM *Speed Logs* in most large vessels.

f. **Impeller (Chernikeef) Logs.** *Impeller Speed Logs* (often referred to for historical reasons as *'Chernikeef Logs'*) use the rotation of an impeller caused by the water flow around a moving ship. They have mostly been replaced by EM or *Sonar Speed Logs*, although *Impeller Speed Logs* may still be found in some merchant vessels and in some small craft.

g. **Calibration of Speed Logs.** It is essential to calibrate *Speed Logs* over the whole speed range of the ship, on first installation, after a refit if the underwater shape of the hull has changed, or if a different type of probe or sensor is fitted. Percentage errors should always be calculated as a percentage of log speed and NOT true speed. Log speed is usually calculated in knots (ie *n.miles* [1852m] per hour); *Sea Miles* (1' of *Latitude*) vary in length (see Para 0113) and should not normally be used for *Speed Log* calibration. The detailed procedure for *Speed Log* calibration is at BR 45 Volume 3.

h. **The Dutchman's Log**. The *Dutchman's Log* is the oldest and simplest method of measuring the ship's speed through the water, but it may still be useful on occasion. A piece of wood is thrown overboard from a forward position and the time is taken when it passes two other points stationed along the fore and aft line of the ship at a known distance apart. The speed of the ship is then determined from the interval of time. When manoeuvring very slowly, a *Dutchman's Log* is useful to indicate whether the ship has headway or sternway.

0926. Night Vision Aids and Electro Optic Surveillance Systems (EOSS)

'Night Vision Aids' are now widely available and can be used to advantage in *Pilotage*, particularly if there are no shore lights (see Para 1312c); however, there is a risk of losing night-adapted vision for a short period after using them. In many RN warships, powerful *Electro Optic Surveillance Systems* (*EOSS*) are fitted; although controlled from the Ops Room, they can be used to provide a continuous bearing of a chosen mark. An *EOSS* bearing accuracy check should be carried out just before use or as soon as possible thereafter.

0927-0929. Spare

SECTION 3 - LIGHTS AND FOG SIGNALS

0930. Details, Characteristics and Nomenclature of Lights

a. **Availability of Light Information.** Details of lights may be found as follows:

- **Charts.** Lights are shown on Admiralty paper charts and *ARCS* charts (*Raster Navigation Charts* [*RNCs*]) as a light star with a magenta flare. The greatest detail will usually be found on the largest *Scale* paper / *ARCS* charts; the amount of detail reduces as the *Scale* of the chart decreases. *Electronic Navigation Charts* (*ENCs*) may be interrogated to display full details.

- **Admiralty List of Lights & Fog Signals (ALLFS).** The *ALLFS* (NPs 74-84) provides additional information not shown on paper / *ARCS* charts.

- **Admiralty Sailing Directions.** The *Admiralty Sailing Directions* (‘*Pilots*’) usually only provide the height and description of important light structures.

b. **Characteristics of Lights.** The appearance of a light is called its ‘*Character*’ or ‘*Characteristic*’. The principal *Characteristics* are usually the sequence of light and darkness exhibited and, in some cases, the colour(s) of the light. Lights may be *Fixed, Rhythmic* and *Alternating*. See examples at Tables 9-1 to 9-3 (overleaf) and Fig 9-3.

- **Fixed Lights.** *Fixed* lights are those exhibited without interruption.

- **Rythmic Lights.** *Rythmic* lights show a sequence of intervals of light and dark, the whole sequence being repeated at regular intervals. Terms used to describe elements of *Rythmic* lights are:
    - **Period.** The *Period* is time taken to exhibit one complete sequence.
    - **Phase.** The *Phase* is one element (eg *Flash, Eclipse*) of a sequence.
    - **Flashing.** A *Flashing* light has a *Phase* of illumination shorter than that of darkness. *Quick, Very Quick* and *Ultra Quick Flashing* lights have flash rates per minute of 50-80, 80-160 and ‘over 160’ respectively.
    - **Eclipse.** An *Eclipse* is a *Phase* where no light is visible.
    - **Group Flashing.** A *Group Flashing* light is a *Flashing* light in which a group of flashes, specified in number, is regularly repeated.
    - **Isophase.** An *Isophase* light has a *Phase* of illumination the same length as that of darkness (*Eclipse*).
    - **Occulting.** An *Occulting* light has a *Phase* of illumination longer than that of darkness (eclipse).
    - **Group Occulting.** A *Group Occulting* light is a *Occulting* light in which a group of eclipses, specified in number, is regularly repeated.
    - **Composite Group Occulting.** A *Composite Group Occulting* light is similar to a *Group Occulting* light except that successive groups in a *Period* may have different numbers of eclipses.

- **Alternating Lights.** *Alternating* lights are *Rhythmic* lights showing different colours during each sequence.
    - **Period.** The *Period* of an *Alternating* light is the time taken to exhibit the complete sequence, including the change of colour.

(0930b continued)

Table 9-1. Illustration of (White) Fixed Light Characteristics

Character	Abbreviation	Illustration
Fixed	F W	

Table 9-2. Illustration of (White) Rhythmic Light Characteristics

Character	Abbreviation	Illustration
Occulting	Oc W	
Group Occulting	Oc(2)W	
Composite Group Occulting	Oc(3+4) W	
Isophase	Iso W	
Flashing	Fl W	
Long Flashing	L Fl W	
Group Flashing	Fl(3) W	
Composite Group Flashing	Fl(3+2) W	
Quick Flashing	Q W	
Group Quick Flashing	Q(9) W	
‘Group Quick’ character, for IALA South Marks only.	Q(6)+L Fl W	
Interrupted Quick Flashing	IQ W	
Very Quick Flashing	VQ W	
Group Very Quick Flashing	VQ(3) W	
Interrupted Very Quick	IVQ W	

(0930b continued)

Table 9-2 (continued). Illustration of (White) Rhythmic Light Characteristics

Character	Abbreviation	Illustration
Ultra Quick Flashing	UQ W	
Interrupted Ultra Quick	IUQ W	
Morse Code (example 'K') Morse Code (example 'AR') Flashing (example '4')	Mo(K) W Mo(AR) W Mo(4) W	  
Fixed and Flashing	FFl W	
Fixed and Group Flashing	FFl(2) W	

Table 9-3. Illustration of Alternating Light Characteristics

Character	Abbreviation	Illustration
Alternating	Al WGR	
Alternating and Flashing	AlFl WR	
Alternating Group Flashing Alternating Group Flashing	AlFl RW AlFl WWRR	 
Alternating Occulting	AlOc WR	
Alternating Group Occulting	AlOc WGR	
Alternating Fixed and Flashing Alternating Fixed and Flashing	AlF W Fl R AlF W Fl RG	 
Alternating Fixed and Group Flashing	AlF W Fl(3)G	
Alternating Fixed and Composite Group Flashing	AlF W Fl WRR	

(0930) c. **Nomenclature of Lights.** See *ALLFS* for full details of nomenclature of lights. All distances in *ALLFS* are in *Sea Miles*. See examples from charts at Fig 9-3 opposite.

- **Intensity.** The *Intensity* of a light is its 'brightness' and is either expressed in candelas or converted to *Nominal Range* (see below).
- **Elevation.** The *Elevation* of a light is the vertical distance between the focal plane of the light and the level of *Mean High Water Springs* (*MHWS*) or *Mean Higher High Water* (*MHHW*) or, on some charts, above *Mean Sea Level* (*MSL*).
- **Luminous Range.** The *Luminous Range* of a light is the maximum distance at which it can be seen, determined only by its intensity and the prevailing visibility. *Luminous Range* takes no account of *Elevation*, observer's height of eye or the curvature of the Earth.
- **Nominal Range.** The *Nominal Range* of a light is its *Luminous Range* for a meteorological visibility of 10 miles. The light's *Intensity* in candelas may be converted to *Nominal Range* with the *Luminous Range* diagram at Fig 9-4a.
- **Geographical Range.** The *Geographical Range* of a light is the maximum distance at which a light can reach an observer as determined by the height of the observer, the light's *Elevation* and the curvature of the Earth.
- **Loom.** The *Loom* of a light is the diffused glow observed from a light below the horizon or hidden behind an obstacle, due to atmospheric scattering.
- **Main Light.** The *Main Light* is the major of two lights on the same or adjacent supports.
- **Subsidiary (Auxiliary) Light.** A *Subsidiary (Auxiliary) Light* is one placed near a *Main Light* and having a special use in navigation.
- **Sector Light.** A *Sector Light* presents different colours or *Characteristics* in different directions. Sector limits are stated in true bearings (0˚-360˚) from seaward. If no sectors are stated it may be assumed to be visible all round.
- **Leading Lights.** *Leading Lights* are two or more lights forming a *Leading Line*; their alignment is stated in true bearings (0˚-360˚) from seaward.
- **Direction Light.** A *Direction Light* is a light showing over a very narrow sector, forming a single *Leading Light*. This sector may be flanked by sectors of greatly reduced intensity, or by sectors of different colours or *Character*.
- **Moiré Direction Light.** A *Moiré Direction Light* gives a yellow background to a screen on which a vertical black line is seen when on the centre-line; when off the centre-line, the vertical black line changes to black arrows indicating the direction to turn to regain the centre-line.
- **Vertical Lights.** *Vertical Lights* are two or more lights disposed vertically, horizontally or in a geometric shape, to distinguish them from single lights.
- **Occasional Lights.** *Occasional Lights* are only exhibited when needed.
- **Structure Descriptions - Heights, Bands, Stripes & Diagonal Stripes.** *Heights* are measured from the ground to the top of the structure. The terms '*Bands*', '*Stripes*' and '*Diagonal Stripes*' are used to describe horizontal, vertical or diagonal markings respectively.


Fathoms and Metric Charts
Lights
Light structures and positions
† This symbol and/or abbreviation is obsolescent
Position of light
Position of minor light
Lt †Lt
Light
Lt Ho †Lt Ho.
Lighthouse
Aero
Aero light (may be unreliable)
R
Bn
Lighted beacon
Lt V
Major floating light (light-vessel, major light float or LANBY)
Lighted offshore platform
Lights visible on certain bearings only
The bearings quoted are always from seaward
Leading Lts 090°30′
Oc.4s
Oc.8s
†Lights in line 090° 30′
Occ.4s
Occ.8s
Leading lights
Leading Lts 074°
Oc.6s
Oc.R.6s
Oc.W
Oc.R
Some large scale charts show the arcs of visibility
074°
Oc.W&R
Ldg Oc.W&R
Smaller scale charts
Lights in line 092°
Fl
Fl
Lights in line
Fl.R
Fl.R
2Fl.G
Marking the sides of a channel
F.R
F.R
2Fl
Marking a submarine cable
Fl(3)
F
Fl(2)
F, Fl(2), Fl(3)
Sector lights
R
W
G
R
W
G
Iso.WRG
Sectors emphasised where denoting fairway
Fl.5s 40m 20M
& F.R. 35m 12M
Main light visible all-round, with auxiliary light seen over danger
R
Dir 080°
095°
Iso
Oc
Directional lights
W
R
G
Dir Fl.WRG
Obscd
Obscured sector
Faint
Faint, or partially obscured sector
R(intens)
R
Intensified sector

Fig 9-3. Examples of Lights shown on Admiralty (Paper / ARCS) Charts

0931. Admiralty List of Lights & Fog Signals - Paper and Digital Versions

ALLFS Volumes A-L (NPs 274-284) and its digital equivalent provide details of lights / *Fog* signals worldwide, with instructions for their use. Light buoys with a height of 8m or more may be listed, but mobile Oil / Gas / Drilling Platforms are not. *ALLFS* are published annually and are updated weekly by *Notices to Mariners*. *ALLFS* uses the following terms:

- **Positions.** Positions of lights are referenced to *WGS 84* unless otherwise stated but may be approximate. Charts should be consulted for more authoritative positions.
- **Aeromarine Lights.** *Aeromarine Lights* included are marine-type lights in which part of the beam is deflected 10°-15° above the horizon for aircraft use.
- **Aero Lights.** *Aero Lights* are primarily for aircraft use; they are often of great intensity and *Elevation*. They are included where relevant for marine use, but details may change without notice and **they should be used with caution.**
- **Obstruction Lights.** *Obstruction Lights* mark radio towers, chimneys etc. Details may change without notice and **they should be used with caution.**
- **Daytime Lights.** *Daytime Lights* are operated throughout 24 hours.
- **Fog Lights.** Lights shown only in *Fog* are marked accordingly.
- **Fog Detector Lights.** *Fog Detector Lights* are often bluish in colour.

0932. Maximum Ranges of Lights

a. **Calculating the Maximum Range of Lights.** There are two criteria for determining the maximum range at which a light can be seen:

- **1st Criterion.** First, the light must be above the horizon. This depends on the *Geographical Range* (see definition at Para 0930c).
- **2nd Criterion.** Secondly, the light must be powerful enough to be seen. This depends on the *Luminous Range* (see definition at Para 0930c)

The range at which a light will be seen by the observer will be either the *Geographical* or the *Luminous Range*, **whichever is the less**. It is necessary to work out each range. Examples of the calculations are at Para 0932g overleaf.

b. **Geographical, Nominal and Luminous Ranges.** *Geographical, Nominal and Luminous Ranges* are defined at Para 0930c. The ranges quoted in *ALLFS* for nominated countries is the *Nominal Range,* but for other countries *Luminous Range* is used instead (in most cases with a meteorological visibility of 20 *Sea Miles*, equivalent to a transmission factor of 0.85); the list of nations for which *Nominal Range* is used is given in the preamble pages for each volume of *ALLFS*.

c. **Calculating Geographical Range.** *Geographical Range* may be calculated from a table in *ALLFS*, a copy which is at Fig 9-4b opposite.

d. **Calculating Luminous Range from Nominal Range and Visibility.** *Luminous Range* may be calculated from a diagram in *ALLFS* (see Fig 9-4a below). If *Nominal Range* is quoted in *ALLFS*, enter the diagram using *Nominal Range*, but if *Luminous Range* is quoted, enter using *Intensity* (candelas). **See also Note 9-2 (Para 0932g).**



Fig 9-4a. Luminous Range Diagram (reproduced from ALLFS) ***[Examples in colours]***

(0932 continued)

Elevation		Height of Eye of Observer in feet/metres												
ft		3	7	10	13	16	20	23	26	30	33	39	46	52
	m	**1**	**2**	**3**	**4**	**5**	**6**	**7**	**8**	**9**	**10**	**12**	**14**	**16**
		Range in Sea Miles												
0	**0**	2.0	2.9	3.5	4.1	4.5	5.0	5.4	5.7	6.1	6.4	7.0	7.6	8.1
3	**1**	4.1	4.9	5.5	6.1	6.6	7.0	7.4	7.8	8.1	8.5	9.1	9.6	10.2
7	**2**	4.9	5.7	6.4	6.9	7.4	7.8	8.2	8.6	9.0	9.3	9.9	10.5	11.0
10	**3**	5.5	6.4	7.0	7.6	8.1	8.5	8.9	9.3	9.6	9.9	10.6	11.1	11.6
13	**4**	6.1	6.9	7.6	8.1	8.6	9.0	9.4	9.8	10.2	10.5	11.1	11.7	12.2
16	**5**	6.6	7.4	8.1	8.6	9.1	9.5	9.9	10.3	10.6	11.0	11.6	12.1	12.7
20	**6**	7.0	7.8	8.5	9.0	9.5	9.9	10.3	10.7	11.1	11.4	12.0	12.6	13.1
23	**7**	7.4	8.2	8.9	9.4	9.9	10.3	10.7	11.1	11.5	11.8	12.4	13.0	13.5
26	**8**	7.8	8.6	9.3	9.8	10.3	10.7	11.1	11.5	11.8	12.2	12.8	13.3	13.9
30	**9**	8.1	9.0	9.6	10.2	10.6	11.1	11.5	11.8	12.2	12.5	13.1	13.7	14.2
33	**10**	8.5	9.3	9.9	10.5	11.0	11.4	11.8	12.2	12.5	12.8	13.5	14.0	14.5
36	**11**	8.8	9.6	10.3	10.8	11.3	11.7	12.1	12.5	12.8	13.2	13.8	14.3	14.9
39	**12**	9.1	9.9	10.6	11.1	11.6	12.0	12.4	12.8	13.1	13.5	14.1	14.6	15.2
43	**13**	9.4	10.2	10.8	11.4	11.9	12.3	12.7	13.1	13.4	13.7	14.4	14.9	15.4
46	**14**	9.6	10.5	11.1	11.7	12.1	12.6	13.0	13.3	13.7	14.0	14.6	15.2	15.7
49	**15**	9.9	10.7	11.4	11.9	12.4	12.8	13.2	13.6	14.0	14.3	14.9	15.5	16.0
52	**16**	10.2	11.0	11.6	12.2	12.7	13.1	13.5	13.9	14.2	14.5	15.2	15.7	16.2
56	**17**	10.4	11.2	11.9	12.4	12.9	13.3	13.7	14.1	14.5	14.8	15.4	16.0	16.5
59	**18**	10.6	11.5	12.1	12.7	13.2	13.6	14.0	14.4	14.7	15.0	15.7	16.2	16.7
62	**19**	10.9	11.7	12.4	12.9	13.4	13.8	14.2	14.6	14.9	15.3	15.9	16.5	17.0
66	**20**	11.1	12.0	12.6	13.1	13.6	14.1	14.5	14.8	15.2	15.5	16.1	16.7	17.2
72	**22**	11.6	12.4	13.0	13.6	14.1	14.5	14.9	15.3	15.6	15.9	16.6	17.1	17.7
79	**24**	12.0	12.8	13.5	14.0	14.5	14.9	15.3	15.7	16.0	16.4	17.0	17.6	18.1
85	**26**	12.4	13.2	13.9	14.4	14.9	15.3	15.7	16.1	16.4	16.8	17.4	18.0	18.5
92	**28**	12.8	13.6	14.3	14.8	15.3	15.7	16.1	16.5	16.8	17.2	17.8	18.3	18.9
98	**30**	13.2	14.0	14.6	15.2	15.7	16.1	16.5	16.9	17.2	17.5	18.2	18.7	19.2
115	**35**	14.0	14.9	15.5	16.1	16.6	17.0	17.4	17.8	18.1	18.4	19.1	19.6	20.1
131	**40**	14.9	15.7	16.4	16.9	17.4	17.8	18.2	18.6	18.9	19.3	19.9	20.4	21.0
148	**45**	15.7	16.5	17.1	17.7	18.2	18.6	19.0	19.4	19.7	20.0	20.7	21.2	21.7
164	**50**	16.4	17.2	17.9	18.4	18.9	19.3	19.7	20.1	20.5	20.8	21.4	22.0	22.5
180	**55**	17.1	17.9	18.6	19.1	19.6	20.0	20.4	20.8	21.2	21.5	22.1	22.7	23.2
197	**60**	17.8	18.6	19.3	19.8	20.3	20.7	21.1	21.5	21.8	22.2	22.8	23.3	23.9
213	**65**	18.4	19.2	19.9	20.4	20.9	21.4	21.7	22.1	22.5	22.8	23.4	24.0	24.5
230	**70**	19.0	19.9	20.5	21.1	21.5	22.0	22.4	22.7	23.1	23.4	24.0	24.6	25.1
246	**75**	19.6	20.5	21.1	21.7	22.1	22.6	23.0	23.3	23.7	24.0	24.6	25.2	25.7
262	**80**	20.2	21.0	21.7	22.2	22.7	23.1	23.5	23.9	24.3	24.6	25.2	25.8	26.3
279	**85**	20.8	21.6	22.2	22.8	23.3	23.7	24.1	24.5	24.8	25.1	25.8	26.3	26.9
295	**90**	21.3	22.1	22.8	23.3	23.8	24.2	24.6	25.0	25.4	25.7	26.3	26.9	27.4
312	**95**	21.8	22.7	23.3	23.9	24.3	24.8	25.2	25.5	25.9	26.2	26.8	27.4	27.9
328	**100**	22.3	23.2	23.8	24.4	24.9	25.3	25.7	26.1	26.4	26.7	27.3	27.9	28.4

Fig 9-4b. Geographical Range Table (reproduced from ALLFS) ***[Examples in RED]***

e. **Atmospheric Refraction.** The *Geographical Range* table in the *ALLFS* is based upon a particular allowance for *Atmospheric Refraction* (see Para 0803n, Note 8-3).

f. **Sighting of Lights at Ranges in Excess of Visibility.** From Examples 9-1 and 9-2 (overleaf), it can be seen that lights may be sighted at a range in excess of the estimated meteorological visibility, dependent on the light's *Intensity*.

(0932) g. **Calculating the Maximum Range of Lights - Examples.**

Example 9-1. Geographical Range less than Luminous Range

Height of eye 12 metres, estimated visibility 15 miles; disregarding *Height of Tide (HOT)*, at what range should the Lizard Light (A0060) be sighted? The *Elevation* of the light is 70 metres. *Nominal Range* is 26 *Sea Miles*.

Geographical Range. This can be established as 24.0 *Sea Miles* from the *Geographical Range* table (see Fig 9-4b) for an *Elevation* of 70 metres and height of eye 12 metres.

Luminous Range. Enter the *Luminous Range* diagram (see Fig 9-4a) from the top border for 26 *Sea Miles* (*Nominal Range*) and note where the vertical line from this point cuts the visibility range curve for 15 miles (which must be interpolated between the 20 mile and 10 mile visibility curves). From this second point move horizontally left and read off the *Luminous Range*; 34.0 *Sea Miles* in this case.

Maximum Range. The maximum range at which the light will be sighted is therefore the lesser of the *Geographical and Luminous Ranges*, and is thus 24.0 *Sea Miles*.

Example 9-2. Geographical Range greater than Luminous Range

Given the same situation as in Example 9-1 but with the visibility now reduced to 5 miles, at what range should the light be sighted?

Geographical Range. As before, *Geographical Range* is 24.0 *Sea Miles*.

Luminous Range. Follow the same procedure as in Example 9-1, but this time use the 5 mile visibility curve, move horizontally left and read off the *Luminous Range*; 15.0 *Sea Miles* in this case.

Maximum Range. The maximum range at which the light will be sighted is therefore the lesser of the *Geographical and Luminous Ranges*, and is thus 15.0 *Sea Miles*.

Example 9-3. Use of Luminous Range and Intensity (not Nominal Range)

Height of eye 10 metres, estimated visibility 5 miles. Disregarding *HOT*, at what range should Punta Gobernadora Light (J4836) be sighted? The *Elevation* of the light is 33 metres, *Luminous Range* 46 *Sea Miles*, *Intensity* 3 million candelas (see Note 9-2 below).

Geographical Range. This can be established as 18.0 *Sea Miles* from the *Geographical Range* table (see Fig 9-4b) for an *Elevation* of 33 metres and height of eye 10 metres.

Luminous Range. Enter the *Luminous Range* diagram (see Fig 9-4a) from the bottom border for 3 million candelas (*Intensity*) and note where the vertical line from this point cuts the visibility range curve for 5 miles, then move horizontally left and read off the *Luminous Range*; 16.4 *Sea Miles* in this case.

Maximum Range. The maximum range at which the light will be sighted is therefore the lesser of the *Geographical* and *Luminous Ranges*, and is thus 16.4 *Sea Miles*.

Note 9-2. Procedure for Obtaining Actual Luminous Range Without Intensity. *If Luminous Range is listed without Intensity, enter the Luminous Range diagram (see Fig 9-4a) at the left with the tabulated Luminous Range, move horizontally right until the 20 Sea Mile visibility curve is reached, then vertically up or down until the actual visibility curve is met, then read back across to the left, where actual Luminous Range for the prevailing visibility may be read.*

0933. Using Lights - Aide Memoire

The following aide memoire of practical tips is useful as a check-list when using lights for navigation.

- **Checking.** The *Characteristics* of a light should always be checked on initial sighting.
- **Actual Geographical Range.** *Atmospheric Refraction* and *HOT* may affect the *Geographical Range* expected.
- **Raising or Dipping Range.** The '*Rising or Dipping Range*' of a light can only be approximate, and must be used with **particular caution** if being used as a *Position Line*.
- **Obscured High Lights.** Lights placed at high *Elevations* are often obscured by cloud (eg lights on the Spanish coast).
- **Estimating Distances.** The distance of an observer from a light cannot be estimated from its apparent brightness.
- **Effect of Atmospheric Conditions.** The distance at which lights are sighted varies greatly with atmospheric conditions. It may be increased (or decreased) by *Abnormal Refraction*. It will be reduced by *Fog*, haze, dust, smoke or rain; a light of low *Intensity* may easily be obscured in any of these conditions and even the range of a light of great *Intensity* may be considerably reduced. **Thus ranges at which lights first appear can only be approximate.** There may also be *Fog* or rain in the vicinity of the light even though it is clear at the ship, and this may affect its initial sighting range.
- **Cold Weather.** In cold weather, and more particularly with rapid changes of weather, a shore-light's lantern glass and screens may be covered with moisture, frost or snow, which can greatly reduce the sighting range. Coloured sectors may appear more or less white, the effect being greatest with green lights of low intensity.
- **Sector Limits.** The limits of light sectors should not be relied upon and should always be checked by compass bearing. At the boundaries of sectors there may be a small arc in which the light may be obscured, indeterminate in colour or white; however, more modern lights usually define sector boundaries to a much greater degree of accuracy and precision than older lights.
- **Arcs of Visibility.** The limits of arcs of visibility of lights are rarely exact, especially at short ranges.
- **Reddish Hue.** In certain atmospheric conditions, white lights may have a reddish hue.
- **Glare from Background Lighting.** Glare from background lighting may considerably reduce the range at which lights are initially sighted. The approximate sighting range in such circumstances may be found by first dividing the *Intensity* of the light by 10 for minor background lighting, by 100 for major background lighting, and then using the *Luminous Range* diagram (Fig 9-4a) to establish a likely initial sighting range.

0934. Fog Signals - Types and Uses

ALLFS Volumes A-L (NPs 274-284) and its digital equivalent (DP 565) contain details of *Fog* signal and their operation. Brief details are also given on the chart.

a. **Fog Signal Types.** The following types of *Fog* signals are likely to be encountered.

- **Diaphone.** The *Diaphone* uses compressed air to issue a powerful low note, usually with a characteristic 'grunt' at the end of the note (a brief sound of suddenly reduced pitch). If the *Fog* signal does not end in this 'grunt', *ALLFS* will state 'No Grunt'.
- **Horn.** The *Horn* uses compressed air or electricity. *Horns* exist in many forms, differing greatly in sound and power. Some forms, particularly those at major *Fog* signal stations, simultaneously produce sounds of different pitch which are often very powerful. Others produce a single steady note, or vary continuously in pitch.
- **Siren.** The *Siren* uses compressed air and exists in many forms varying greatly in sound and power.
- **Reed.** The *Reed* uses compressed air and emits a weak (particularly if hand-operated) high-pitched sound.
- **Explosive.** This signal produces short reports by firing explosive charges.
- **Bell, Gong & Whistle.** *Bell, Gong & Whistle* may be operated by machinery, (sounding regularly), by hand (sounding irregularly) or by wave action (sounding erratically). *Bells, Gongs & Whistles* are frequently used as *Fog* signals on buoys.
- **Morse Code.** *Morse Code Fog* signals consist of one or more letters of the *Morse Code*. In a similar manner to lights, the abbreviation 'Mo' may be included in the abridged description of a *Fog* signal.

b. **Using Fog Signals - Cautions.** Sound travels through air in an unpredictable way and *Fog* signals should never be relied upon implicitly. *Fog* lookouts should be placed where noises in the ship are least likely to interfere with the hearing of a *Fog* signal.

- **Varying Distances.** *Fog* signals may be heard at greatly varying distances. *Fog* signal emitters vary greatly in power; reserve emitters are often weak.
- **Apparent Direction.** The apparent direction of a *Fog* signal is NOT always a correct indication of its true direction.
- **High and Low Notes.** If a *Fog* signal is a combination of high and low notes, one of the notes may be inaudible in certain atmospheric conditions.
- **Inaudible Areas.** There are occasionally areas around a station in which the *Fog* signal is quite inaudible.
- **Patchy Fog.** *Fog* may exist a short distance from a station and not be observable from it, so that the signal may not be operated.
- **Starting.** Some *Fog* signals cannot be started immediately *Fog* is detected.

0935-0939. Spare

SECTION 4 - BUOYS, OTHER FLOATING STRUCTURES AND BEACONS

0940. Buoy and Beacon Types

a. **Buoys.** Buoys are floating structures moored to the sea bed, used to mark channels and fairways, shoals, banks, rocks, wrecks and other dangers to navigation. Buoys have a distinctive colour and shape, they may carry topmarks and/or radar reflectors, exhibit lights and/or sound *Bells, Gongs, Whistles* or *Horns.*

b. **Beacons.** Beacons are navigational marks, erected as an aid to navigation. They may be placed on or in the vicinity of danger, or onshore. Beacons have a distinctive colour and shape, they may carry topmarks and/or radar reflectors and may exhibit lights; these features all have the same meaning as for buoys. Large unlit beacons are often referred to as *Daymarks* (*Daybeacons* in the USA and Canada). In its simplest form, a beacon is known as a 'Pile Beacon' and consists of a single wooden or concrete pile identified only by colour and possibly a number.

c. **Sources of Information.** The definitive guide to buoys and beacons for any area is the largest *Scale* paper chart or *ENC* / *RNC* of the place concerned. The *Admiralty Sailing Directions* ('*Pilots*') describe the buoyage system and *Direction of Buoyage* in use in the area covered by the particular volume and often refer in the text to individual light-buoys without giving a detailed description. Details of beacons may also be found in the *Admiralty Sailing Directions* ('*Pilots*'). *ALLFS* gives details of lighted beacons, and of most buoys with an of an *Elevation* of 8 metres or more.

0941. IALA Maritime System of Buoyage - Regions A and B

The *IALA Maritime Buoyage System* covers most (but not all) of the world and applies to buoys and beacons. It consists of *Lateral Marks, Cardinal Marks, Isolated Danger Marks, Safe Water Marks, Special Marks* and *Emergency Wreck Marking Buoys*. The following information is a brief summary; for full details, see '*IALA Maritime Buoyage System*' (NP 735).

a. **Regions A and B.** To reflect long-standing practices, the system is divided into *Region A* and *Region B* (see details in NP 735 and in the *Admiralty Sailing Directions* ['*Pilots*']). In broad terms, areas using *Region B* comprise N & S America, Japan, Korea and the Philippines; most of the rest of the world comprises *Region A*. The only differences are that the in *Region A* red is used for port hand *Lateral Marks* with green for starboard, and in *Region B* these colours are reversed; the shapes of *Lateral Marks* are the same in both *Regions* (can to port, conical to starboard).

b. **Direction of Buoyage.** *Lateral Marks* are generally used for well-defined channels with a '*Conventional Direction of Buoyage*', which indicates the port and starboard hand sides of the route to be followed. This is defined by either the *Local Direction of Buoyage* (used when approaching a harbour, estuary etc from seaward), or a *General Direction of Buoyage* (created on the principle of a clockwise direction around continents). The relevant *Direction of Buoyage* (if established) is normally shown on the chart and mentioned in *Admiralty Sailing Directions* ('*Pilots*') for a particular area.

c. **Retroflectors.** High-visibility *Retroflector* material is fitted to many unlit buoys.

(0941 continued)


LATERAL MARKS - REGION A
PORT HAND
Colour: Red
Shape: Can, Pillar or Spar
Topmark: Single red can (when fitted)
Retroflector: Red band or square
STARBOARD HAND
Colour: Green
Shape: Conical, Pillar or Spar
Topmark: Single green cone point up (when fitted)
Retroflector: Green band or triangle
DIRECTION OF BUOYAGE
Red Light
Q.R
Fl.R
L.Fl.R
Fl(2) R
Continuous quick light
Single-flashing light
Long-flashing light
Group-flashing light
Green Light
Q.G
Fl.G
L.Fl.G
Fl(2) G
PREFERRED CHANNELS
Preferred Channel to Starboard
Colour: Red with one broad green band
Shape: Can, Pillar or Spar
Topmark: Single red can (when fitted)
Retroflector: Red band or square
Preferred Channel to Port
Colour: Green with one broad red band
Shape: Conical, Pillar or Spar
Topmark: Single green cone point up (when fitted)
Retroflector: Green band or triangle
DIRECTION OF BUOYAGE
Red Light
Fl(2+1) R
Composite Group-flashing (2+1) light
Green Light
Fl(2+1) G

Fig 9-5. IALA Lateral Marks - Region A

(0941) d. **IALA Lateral Marks - Region A.** *Lateral Marks*, with colours, shapes and lights as in Fig 9-5 (above), are used in well defined channels in conjunction with *Direction of Buoyage* and indicate the port and starboard sides of the route to be followed. Where a channel divides to form two alternatives for the same destination, the 'Preferred Channel' is indicated by a modified *Lateral Mark*. In *Region A,* red is used for port hand *Lateral Marks* with green for starboard; the shapes of *Lateral Marks* are the same in both *Regions* (can to port, conical to starboard).

- **Features.** Fig 9-5 is schematic and buoy features may vary.
- **Shapes.** Where buoys do not rely on shape for identification, they carry the appropriate topmarks where practicable.
- **Numbers.** Numbering / lettering of buoys follows the *Direction of Buoyage*.

e. **IALA Lateral Marks - Region B.** As stated in Para 0941a, in *Region B Lateral Marks* are identical to those in *Region A* except that the colours are reversed with green used for port hand *Lateral Marks* and red for starboard; the shapes of *Lateral Marks* are the same in both *Regions* (can to port, conical to starboard).

(0941 continued)


CARDINAL MARKS
Colour: Black and Yellow
Shape: Pillar or Spar (if a buoy)
Topmark: Two black cones
Retroflector: Blue and / or Yellow
NW
NE
SW
SE
Q or VQ
Retroflector
Q(9) or VQ(9)
Q(3) or VQ(3)
N
W
E
S
Point of Interest
Retroflector
Retroflector
Retroflector
Q(6) + L.Fl.15s or VQ(6)+ L.Fl.10s

Fig 9-6. IALA Cardinal Marks

(0941) f. **IALA Cardinal Marks.** *Cardinal Marks*, with colours, shapes and lights as in Fig 9-6 (above), indicate that safe navigable water lies to the named side of the mark (ie safe water lies to the North of a North mark etc). *Cardinal Marks* are used to indicate that the deepest water in an area is on the named side of the mark, or to indicate the safe side on which to pass a danger (eg rocks, shoals or a wreck), or to draw attention to a feature in a channel such as a bend or junction, or the end of a shoal.

- **Topmarks.** *Cardinal Marks* are always painted in black and yellow bands, with black double-cone topmarks. The points of the cones indicate the position of the black-painted section relative to the yellow (see Fig 9-6).
- **Lights.** *Cardinal Marks* always show a white light based on a group of *Quick* (Q) or *Very Quick* (VQ) flashes using a clock face pattern which indicates the quadrant (ie North = continuous, East = groups of 3, South = groups of 6 plus a *Long Flash* (L Fl), and West = groups of 9) - see Fig 9-6 (above).

(0941) g. **IALA Isolated Danger Marks.** *Isolated Danger Marks*, with colours, shapes and lights as in Fig 9-7 (below), are placed at isolated dangers of limited extent surrounded by navigable water. On the chart, the position of the danger is the centre of the symbol or sounding indicating the danger; the symbol for the buoy will be slightly displaced.

- **Shape and Topmark.** *Isolated Danger Mark* buoys are pillar or spar in shape. A black double-sphere, topmark is fitted wherever practicable as an important feature.
- **Colours.** *Isolated Danger Marks* have horizontal stripes (red and black).


ISOLATED DANGER MARKS
Colour: Black and Red
Shape: Pillar or Spar (if a buoy)
Topmark: Two black spheres
Retroflector: Blue and Red
Retroflector
Light (when fitted):
White, Group-flashing (2)
Fl(2)

Fig 9-7. IALA Isolated Danger Marks

h. **IALA Safe Water Marks.** *Safe Water Marks*, with colours, shapes and lights as in Fig 9-8 (below), are used to indicate that there is navigable water all around the mark. They may be used as a centre-line, mid-channel or landfall mark or to indicate the best point of passage under a fixed Bridge.

- **Shape and Topmark.** If the *Safe Water Mark* is not spherical, a red spherical topmark is fitted wherever practicable as an important feature.
- **Colours.** *Safe Water Marks* have vertical stripes (red and white) and should not be confused with the *Emergency Wreck Marking Buoy* (see Para 0941j) which also has vertical stripes (blue and yellow).


SAFE WATER MARKS
Colour: Red and White
Shape: Spherical, Pillar or Spar
Topmark: Red sphere
Retroflector: Red and White
Retroflector
or
Light (when fitted):
White,
Isophase or Occulting, or
Long-flashing every 10 secs,
or Morse Code A.
Iso
Oc
L.Fl.10s
Mo(A)

Fig 9-8. IALA Safe Water Marks

(0941) i. **IALA Special Marks.** Yellow *Special Marks*, with shapes and lights as in Fig 9-9 (below) are used to indicate a special area or feature, the nature of which is apparent from a chart, the *Admiralty Sailing Directions* (‘*Pilots*’), or *Notices to Mariners (NM).* These include (but are not limited to): ‘Ocean Data’ marks, *Traffic Separation Schemes* (*TSS*), spoil grounds, recreation and military exercise zones, cables, pipelines, outfall pipes and ‘channels within a channel’.

- **Colour, Shape and Topmarks.** *Special Marks* are always yellow, can be a variety of shapes and may have lettered topmarks to indicate their purpose.


SPECIAL MARKS
Colour: Yellow
Shape: Optional
Topmark: Yellow diagonal cross - optional
Retroflector: Yellow
Retroflector
or
Light (when fitted):
Yellow,
and may have any rhythm
not used for white lights.
Examples
Fl.Y
Fl(4)Y

Fig 9-9. IALA Special Marks

j. **IALA Emergency Wreck Marking Buoys.** New *Emergency Wreck Marking Buoys* (see Fig 9-10 below) were introduced by *IALA* on a trial basis from 2006-2010 to provide clear and unambiguous marking of a new wreck, as a temporary response in the first 24-72 hours. Full incorporation of the buoy into the *IALA Maritime Buoyage System* will depend on the trial results.

- **Characteristics.** *Emergency Wreck Marking Buoy*s are fitted with alternating *Occulting* blue and yellow lights, a *Racon* (Morse Code ‘D’) and an *AIS* transponder. If multiple buoys are deployed, the lights will be synchronised
- **Retroflector.** As *Emergency Wreck Marking Buoy*s are always intended to be lit, they are NOT normally fitted with *Retroflectors*.
- **Colours.** *Emergency Wreck Marking Buoys* have vertical stripes (blue and yellow) and should not be confused with the *Safe Water Mark* (see Para 0941h) which also has vertical stripes (red and white).


EMERGENCY WRECK MARKING BUOYS
Colour: Blue and Yellow (vertical stripes)
Shape: Pillar or Spar Buoy
Topmark: Upright Yellow Cross
Light (when fitted):
Alternating Occulting
Blue and Yellow .
If multiple buoys deployed,
lights will be synchronised.
Alt.Occ.Bu.Y

Fig 9-10. IALA Emergency Wreck Marking Buoys

0942. Using Buoys and Other Floating Structures for Navigation - Procedures

a. **Limitations of Buoys and Other Floating Structures.** The position of buoys and other floating structures (ie Light vessels, light floats and LANBYs [Large Automatic Navigation BuoYs]) **must always be treated with caution**, even in narrow channels where buoys positions may be monitored by harbour authorities (etc) ashore. Buoys (and to some extent, other floating structures as above) are liable to the following:

- **Dragging and Moving.** Buoys may quite easily drag or break adrift and they are frequently moved as a shoal extends.
- **Charted Position.** The charted position can only show the approximate position of the buoy mooring and takes no account of the length of mooring chain used; this may result in the buoy being substantially away from its charted position, particularly at LW or where a large (tidal) *Range* or strong *Tidal Stream* is experienced.
- **Light Characteristics.** Buoys may not always display the correct light *Characteristics*.

b. **Advantages of Buoys.** Despite the known limitations of buoys (see Para 0942a above), buoys are still a useful aid to navigation, particularly in the following circumstances:

- **Pattern.** If buoys are in a pattern, their relative position to each other may be assessed or *Fixed* using identification techniques (see Para 0807d), thus enhancing confidence (or otherwise) in their position.
- **Shore Radar Monitoring.** If buoys (particularly if they are in a pattern) are monitored by radar from shore by an appropriate harbour authority (etc), it may be possible to confirm (eg by a VHF call) if they are all in position.
- **Supplementary Visual Checks.** Buoys provide an instant visual confirmation (or otherwise) of other position source information. The *Echo Sounder* depth of water should also be used for correlation of position.

c. **Use of Buoys with Caution.** Buoys should NOT be treated as infallible aids to navigation, particularly when in an exposed position. Whenever possible:

- **Fixing & Pilotage.** Navigate by *Fixing* from charted shore objects or high accuracy electronic systems, and in *Pilotage* also run a *Headmark / Sternmark* with *Clearing Lines (Clearing Bearings* or *Clearing Ranges*)
- **Echo Sounder.** Always monitor the *Echo Sounder* (as this measures the proximity of the nearest point of land) and correlate it to the charted position.
- **DR / EP.** Always check the *DR / EP* against the other positions indicated.
- **Cross Checking.** As with all navigation, the concept of cross-checking all available sources of positional information applies to buoys; **use buoys, but do NOT rely implicitly on them.**

0943-0949. Spare.

SECTION 5 - AUTOMATIC IDENTIFICATION SYSTEM (AIS) AND VHF RADIO

0950. Concept of AIS and VHF Radio Use

The following information on *Automatic Identification System (AIS)* and the use of VHF radio is a summary; for details, see BR 45 Volumes 3 & 8, and UK *Maritime and Coastguard Agency* (*MCA*) documents. Current *MCA* documents are available on the *MCA* website.

a. **AIS Summary.** *AIS* was introduced in 2002 and is a shipboard broadcast transponder system, using common digital VHF channel(s) by which ships continually transmit identity, course, speed and other data to other ships and coastal authorities.

b. **AIS - Aim and Objectives.** The aim and objectives of *AIS* are to enhance the following 3 areas of maritime activity:

- **Aim.** The aim of *AIS* is to enhance the safety of life at sea, the safety and efficiency of navigation, and the protection of the marine environment.
- **Objectives.** In support of the aim, the objectives of *AIS* are:
  - To help identify vessels.
  - To assist in contact tracking.
  - To simplify information exchange by reducing VHF verbal reporting.
  - To provide additional information to assist situation awareness.

c. **Classes of AIS - Features and Vessel Carriage Requirements.** Four classes of *AIS* are in use, with the following features and vessel carriage requirements:

- **AIS Class A.** *AIS* Class A provides full maritime functionality (see details at Para 0951) and must be carried by all vessels over 300 grt, from 1 July 2007. The baseline display of *AIS* data is by *Minimum Keyboard Display* (*MKD*), but *AIS* data may instead be interfaced to *Automatic Radar Plotting Aids* (*ARPA*) and *WECDIS / ECDIS*, for graphical display. An *AIS* 'Pilot Port' is required for an external *AIS* display (eg laptop) to be connected to the ships' system.
- **Warship AIS (W-AIS).** *Warship AIS* (*W-AIS*) is an enhanced version of *AIS* Class A and has additional military functionality. See BR 45 Volume 8(1).
- **Inland AIS (Derivative of AIS Class A).** *Inland AIS* is a derivative of *AIS* Class A, specifically authorised for use in inland waters. *Inland AIS* covers the main features of *AIS* Class A while covering the specific requirement of inland navigation and enabling direct data exchange between seagoing and inland vessels in mixed traffic areas. *Inland AIS* specifications may vary regionally but, typically, may replace the *MKD* with a graphical display, remove VHF *Digital Selective Calling* (*DSC*), add some facilities of specific relevance to inland navigation (eg dedicated *Persons on Board* [*POB*] data field) and increase the message transmission rate. See Note 9-1 (below).
- **AIS Class B.** *AIS* Class B provides a reduced maritime functionality and may be carried optionally by vessels not covered by *AIS* Class A. In summary, *AIS* Class B has much reduced message fields and transmission intervals; tracks may also be automatically inhibited in areas of high traffic density.

Note 9-1. Thames AIS. *An Inland AIS ('Thames AIS') is operated by the Port of London Authority (UK) in the River Thames, with mandatory carriage requirements from 1 June 2007.*

0951. AIS - Operation

a. **Operation of AIS.** *AIS* Class A should always be in operation when ships are underway or at anchor, although it may be switched off if the Master / CO considers its continued use may compromise the security of the ship (eg piracy areas). Such action should be noted in the Ship's Log with reasons; in mandatory reporting systems, the competent authority should also be informed unless security would be compromised.

b. **Modes of Operation.** *AIS* operates in 3 modes -'Static', 'Dynamic' and 'Voyage Related', as follows:

- **Static Mode.** In 'Static Mode', *AIS* Class A transmits the vessel's identity, size and type, and the precise location of the navaid antenna (usually *GPS*) in use on board.
- **Dynamic Mode.** In 'Dynamic Mode', *AIS* Class A transmits the vessel's Position, Position 'time stamp' in UTC, *Course Over the Ground* (*COG) / Ground Track*, *Speed Over the Ground* (*SOG*) / *Ground Speed,* heading, rate of turn and 'Navigational Status' (which may include Underway [power / sail], alongside, at anchor, 'Not under Command' [NUC], 'Restricted in Ability to Manoeuvre' [RAM], 'Constrained by Draught [CBD]', aground or fishing).
- **Voyage Related Mode.** In 'Voyage Related Mode', *AIS* Class A transmits the vessel's draught, any hazardous cargo, destination, ETA and *Waypoints*.

c. **Data Input.** Most *AIS* data is input automatically, either at installation set-up or from navaids / gyro compass. However, before sailing or when changes occur, the NO / OOW should manually input the following: draught, cargo, destination, *Waypoints*, ETA, navigational status and text messages. **Failure to input this data accurately may lead to incorrect information being broadcast** (see Paras 0953 [opposite] and 1320a).

d. **Data Transmission Slots.** *AIS* Classes A and B use a *Time Division Multiple Access* (*TDMA*) system to transmit *AIS* messages in slots, each of 29.7 milliseconds.

- **AIS Class A / Inland AIS.** *AIS* Class A vessels use *'Self Organising TDMA'* (*SOTDMA*) to organise transmission slots automatically. *AIS* Class A 'Base Stations' and 'Aids to Navigation' use *'Fixed Access TDMA'* (*FATDMA*) with reserved transmission slots. *Inland AIS TDMA* is based on *AIS* Class A *SOTDMA*, but regional variations in the transmission rate may occur.
- **AIS Class B.** *AIS* Class B vessels use *'Carrier Sense TDMA'* (*CSTDMA*) to listen for a free slot before transmitting.

e. **Range of Operation and AIS Loading.** *AIS* coverage is usually 20-30 *n.miles*, unless substantial shielding by high land masses occurs. If high traffic densities occur and the available *AIS* broadcast time-slots become overloaded, *AIS* will automatically drop contacts furthest away.

f. **Short Text Messages.** *AIS* may be used to send short (maximum 158 characters), safety-related text messages, addressed either to a specific addressee or broadcast to all ships and shore stations (eg iceberg sighted, buoy off station etc).

0952. Virtual (or Pseudo) AIS Contacts

a. **Virtual AIS Contact Facility.** Certain equipments, used primarily by coastal authorities (eg *VTS* Centres etc) may be fitted with a 'Base-Station' *AIS* capability, allowing them to provide *Virtual AIS* (or *Pseudo AIS*) symbols / data in any position. This allows the positions to be broadcast for:

- Vessels whose transmissions to other ships are shielded by land masses.
- Vessels which are not transmitting on *AIS* but whose positions are known and need to be disseminated (eg disabled vessel in distress etc).

b. **False AIS Contacts.** The *Virtual AIS* contact facility could lead to the appearance of false *AIS* contacts. The *Virtual AIS* contact facility also has the potential for misuse (eg spoofing) if such equipment comes under the control of those wishing to confuse, either for illegal purposes (eg piracy) or warfare. Particular care is necessary with *AIS* contacts (**see CAUTION below).**

CAUTION

FALSE AIS CONTACTS. The *Virtual AIS* contact facility could lead to the appearance of false *AIS* contacts. Particular care is necessary when an *AIS* contact is not complemented by a radar contact.

0953. Incorrect AIS Data

Since the introduction of *AIS*, many instances have occurred of incorrect *AIS* data being broadcast, due either to incorrect setting up of navaids and other interfaced equipment, or to incorrect manual inputs. One example of erroneous *AIS* data is at Fig 9-11 (below), where a ship broadcast its *AIS* position some 4.8 cables from its real position, causing a potentially dangerous situation in the busy approaches to the ports of Portsmouth and Southampton (UK). Many other examples of incorrect *AIS* data being broadcast have been reported.


Nab Tower
NAB CHANNEL
4.8c difference in AIS / ARPA positions, for same vessel
Vessel's AIS position (non-standard symbology for VTS use)
Vessel's ARPA position (VTS ARPA in process of acquisition)
VHF CH12
VHF CH20
0
0·5
1M
Scale: Nautical Miles

Fig 9-11. Example of Dangerously Incorrect AIS Information Transmitted by a Vessel
(Reproduced by kind permission of Associated British Ports, Southampton)

0954. Collision Avoidance - Use of AIS and VHF Radio

a. **Limitations of AIS.** *AIS* may not provide a complete picture of the situation around a vessel, for a variety of possible reasons. Not all ships are fitted with *AIS* (particularly small craft and fishing boats); in others, *AIS* may be switched off or be transmitting incorrect data. Other floating objects without *AIS* (eg navigational marks etc) may give a radar echo but will not give an *AIS* response. If a sensor is not installed (eg a gyro compass is not required in ships under 500grt) or fails, *AIS* cannot transmit its data. *AIS* positions are derived from the vessel's *GNSS* equipment (usually *GPS*) and may not exactly coincide with the radar contact.

b. **Misuse of AIS for Collision Avoidance.** Collision avoidance must be carried out strictly in compliance with the *International Regulations for Prevention of Collisions at Sea 1972* (the *'ColRegs'*). There is no direct provision in the *ColRegs* for the use of *AIS* data, except broadly under the 'all available means' provisions of *ColRegs* Rules 5 and 7 **(but see CAUTION below)**.

CAUTION

AIS DATA. Current (2008) UK (*MCA*) guidance is that *AIS* may be used to assist collision avoidance decision making, but only as an additional source of information; decisions should be based primarily on visual and/or radar data.

c. **Correlating Virtual AIS Contacts with Radar Contacts.** *AIS* 'Base-station' equipments are capable of providing *Virtual AIS* (or *Pseudo AIS*) contact symbols / data in any position on *AIS* displays (see Para 0952). Mariners should therefore take particular care if an *AIS* contact does not correlate with an appropriate radar contact.

d. **Misuse of VHF Radio for Collision Avoidance.** In a significant number of collisions, one or both parties had used VHF radio in an attempt to avoid collision, and this was later found to be a contributory cause. Time can be wasted making VHF contact and establishing the correct identity of each party, instead of complying with the *ColRegs*. Subsequent VHF conversations are open to misunderstanding. **See CAUTION below.**

e. **Misuse of AIS with VHF Radio for Collision Avoidance.** Notwithstanding availability of *AIS*, the uncertainties that can arise over the identification of vessels and the interpretation of VHF messages present a real danger (see Para 1954d above). **See CAUTION below.**

CAUTION

MISUSE OF VHF RADIO AND AIS. The use of VHF radio to discuss action to be taken between approaching ships is fraught with danger and is actively discouraged by the UK MCA; identification of a contact by *AIS* does NOT remove this danger.

CHAPTER 10

TIDES AND TIDAL STREAMS

CONTENTS

Para

1001. Scope of Chapter
1002. Primary Definitions

SECTION 1 - TIDAL THEORY

1010. Newton's Universal Law of Gravitation
1011. Earth-Moon System
1012. Gravitational Force
1013. Tide Raising Force
1014. Effect of the Earth's Rotation
1015. Change of Moon's Declination
1016. Earth-Sun System
1017. Springs and Neaps
1018. Summary of Tidal Theory

SECTION 2 - THE TIDES IN PRACTICE

1020. Diurnal and Semi-Diurnal Tides
1021. Shallow Water and Other Special Effects
1022. Meteorological Effects on Tides
1023. Seismic Waves (Tsunamis)

SECTION 3 - TIDAL HARMONICS AND SHM FOR WINDOWS

1030. Harmonic Constituents
1031. Principles of Harmonic Tidal Analysis
1032. Simplified Harmonic Method - 'SHM for Windows®' Software (DP 560)

SECTION 4 - TIDAL STREAMS AND CURRENTS

1040. Primary Definitions and Types of Tidal Streams
1041. Currents
1042. Tidal Stream Data, Atlases and Observations
1043. Tidal Stream at Depth
1044. Eddies, Races and Overfalls
1045. 'Percentage Springs' (Tides and Tidal Streams) - Calculation and Use
1046. 'Tidal Nurdle' - Construction and Use

SECTION 5 - ADMIRALTY TIDE TABLES AND ADMIRALTY TOTALTIDE

1050. Using Admiralty Tide Tables
1051. Admiralty TotalTide® Software
1052. Co-Tidal and Co-Range Charts / Atlases
1053. Scope of the Admiralty Tide Tables

SECTION 6 - LEVELS AND DATUMS

1060. Tidal Levels
1061. Chart Datum and Land Survey Datums
1062. Tidal Levels and Heights - Definitions

INTENTIONALLY BLANK

CHAPTER 10

TIDES AND TIDAL STREAMS

1001. Scope of Chapter

Chapter 10 summarises the theory and practice of *Tides* and *Tidal Streams*, including predictions from the Admiralty Tide Tables and Admiralty *TotalTide*® software. For further details see BR 45 Volume 2 (Astro Navigation) and 'The Admiralty Manual of Tides' (NP 120). This chapter replaces Chapter 11 of the 1987 Edition of this book.

1002. Primary Definitions

The terms '*Tides*' (vertical), *'Tidal Streams'* (horizontal), *Currents* and the American usage *'Tidal Currents'* are frequently mixed up; their definitions (repeated at Para 1040a) are as follows. Further information is at Paras 1040-1046 and Paras 1120-1125.

- **Tides.** '*Tides*' are **periodic vertical reversing** movements of the water on the Earth's surface, caused by the *Tide Raising Forces* of the Moon and Sun.
- **Tidal Streams.** *'Tidal Streams'* are the **periodic horizontal reversing** movements of the water accompanying the vertical rising and falling of *Tides*.
- **Currents.** Ocean *Currents* are **non-tidal** movements of water, which may flow **steadily** at all depths in the oceans and may have both horizontal and vertical components; a *Surface Current* can only have a horizontal component. In rivers and estuaries, there is often a permanent *Current* caused by the flow of river water.
- **Tidal Currents.** *'Tidal Currents'* is the American usage for *'Tidal Streams'*. The term *'Tidal Currents'* is NOT used in this book.

1003-1009. Spare

SECTION 1 - TIDAL THEORY

1010. Newton's Universal Law of Gravitation

Tides are caused by the gravitational attraction of other heavenly bodies on the Earth and on the water over the Earth. The two heavenly bodies which have the greatest *Tide Raising* effect are the Sun and the Moon, while the effect of other heavenly bodies is negligible.

a. **Magnitude.** The magnitude of the gravitational attraction between two bodies is defined in *Newton's Universal Law of Gravitation*, which states that:

> ***"For any two heavenly bodies, a force of attraction is exerted by each one on the other, the force being:***
> ***1. Proportional to the product of the masses of the two bodies.***
> ***2. Inversely proportional to the square of the distance between them.***
> ***3. Directed from the centre of the one to the centre of the other."***

b. **Calculation.** *Newton's Universal Law of Gravitation* may be expressed as:

$$F \propto \frac{m_1 m_2}{d^2}$$ **. . . 10.1 (1987 Ed . . . 11.1)**

where F is the force, m_1 and m_2 the masses of the two bodies, and d their distance apart.

1011. Earth-Moon System

a. **Barycentre.** The common *Centre of Gravity* of two bodies in a system is known as its *'Barycentre'*.

b. **Earth-Moon Barycentre.** The Earth and Moon form an independent system rotating about a common *Centre of Gravity* known as the Earth-Moon *Barycentre* (see Fig 10-1 below). The Earth-Moon *Barycentre* lies on a line joining the *Centres of Gravity* of the Earth and Moon (at a point about 1000 miles below the Earth's surface).


Orbit of the Moon around the Barycentre
Moon
Orbit of the Earth around the Barycentre
Perigee
Apogee
Earth
Earth-Moon Barycentre

Fig 10-1. The Earth-Moon System (*not to scale*)

c. **Earth-Moon Orbits.** The Earth describes a very small ellipse about the Earth-Moon *Barycentre*, while the Moon describes a much larger ellipse about the same *Barycentre*, taking approximately 27½ days to complete one orbit. The Moon revolves around the Earth with respect to the Sun approximately once every 29½ days; this period is known as the *Lunar Month* (see details at BR 45 Volume 2).

d. **Earth-Sun Orbits.** The explanation of Earth-Sun orbits is at Para 1016.

1012. Gravitational Force

a. **Gravitational Force of the Moon Acting on Water.** Although the *Gravitational Force* of the Moon acts on the Earth as a whole (affecting the structure of the Earth itself) and also on the atmosphere, its effect on the water on the Earth's surface is the important factor for the causes of *Tides*.

b. **Gravitational Force of the Moon Acting on the Earth.** In Fig 10-2 (below):

- MM_1 is the diameter of the Earth on the line joining the centres of the Earth and Moon.
- M is the point on the Earth's surface directly under the Moon and known as the *Sublunar Point*.
- M_1 is on the opposite side of the Earth away from M and is known as the *Antipode* (or *Antipodal Point)*.
- A and B are two points on the *Great Circle* whose plane is perpendicular to MM_1, and at all points on this *Great Circle* the distance from the Moon is effectively the same (see Note 10-1) as that from the centre of the Earth.

Thus, the *Gravitational Force* exerted by the Moon anywhere on AB is the same and is denoted by G. At M the distance to the Moon has decreased; thus, the *Gravitational Force* acting at M is increased by a small amount δG, while at M_1 the *Gravitational Force* has decreased by a similar amount. Thus, the total *Gravitational Force* acting at M is $(G + \delta G)$ and that at M_1 is $(G - \delta G)$.



Fig 10-2. Gravitational Force of the Moon Acting on the Earth (*not to scale*)

Note 10-1. *The distance of A and B from the Moon is very slightly more than that at C but, as the radius of the Earth is small compared with the distance of the Moon (approximately 1:60), the differences are also small.*

(1012) c. **Differential Gravitational Force on the Earth's Surface.** If it is assumed that the Earth is a smooth *Sphere* completely covered by water, the *Gravitational Force* acting on the waters may be considered as the difference between the *Gravitational Force G* acting at the centre of the Earth and the actual *Gravitational Force* anywhere else on the Earth's surface (see Fig 10-3 below).


A
Zero
Zero
Zero
C
-δG
M1
(Antipode or Antipodal Point)
+δG
M (Sublunar Point)
Moon
Zero
B

Fig 10-3. Differential Gravitational Force on the Earth's Surface at M / M_1 (*not to scale*)

d. **Direction of Gravitational Force at Antipodal Point.** At the *Antipodal Point* M_1, the differential *Gravitational Force* is negative (ie '-δG'). This is equivalent to the differential *Gravitational Force* at M_1 being positive (ie '+-δG') but acting in the opposite direction (see Fig 10-4 below).


A
D
+δG Cos Ø
+δG Cos Ø
D1
Zero
Moon
+δG
Zero
ϕ
C
M (Sublunar Point)
+δG
M1 (Antipode or Antipodal Point)
Zero
Zero
B

Fig 10-4. Differential Gravitational Force at Other Points (D etc) on Earth's Surface (*Not to scale*)

e. **Differential Gravitational Force at Other Points.** At some other point *D* on the Earth's surface (see Fig 10-4 above), the differential *Gravitational Force* acting on the waters must be somewhere between δG and zero. If *D* is ϕ ° above the *Sublunar-Antipodal* plane, then the differential *Gravitational Force* at *D* is equal to $\delta G \cos \phi$ °. Similarly, at D_1 it is also equal to $\delta G \cos \phi$ °, but acting in the opposite direction.

(1012) f. **Centrifugal Force.** As the Earth and Moon orbit around a *Barycentre*, *Centrifugal Force* acts at M_1 and M_2. The effect is to reinforce the differential *Gravitational Forces.*

1013. Tide Raising Force

a. **Vertical and Horizontal Components of Differential Gravitational Forces.** If it is assumed that the entire surface of the Earth is covered with a uniform layer of water, the differential *Gravitational Forces* may be resolved into a vertical component (*FV*) at right angles to the Earth's surface and a horizontal component (*FH*) directed towards the *Sublunar* or *Antipodal Points* (see Fig 10-5 below).



Fig 10-5. Vertical and Horizontal Components of Differential Gravitational Forces (*Not to scale*)

b. **Vertical and Horizontal Components.** The vertical component is only a very small portion of the Earth's gravity, so that the actual lifting of the water against gravity is infinitesimal. *Tides* are produced by the horizontal component which cause the water to move across the Earth and pile up at the *Sublunar* and *Antipodal Points* until an equilibrium position is found. The horizontal component of the differential *Gravitational Forces* is known as the *Tide Raising* (or *Tractive) Force*. Its magnitude at a given point (X in Fig 10-5) may be expressed as:

$$F_H \propto \frac{3}{2} \times \frac{m_2 r}{d^3} \sin 2\phi$$ **. . . 10.2 (1987 Ed . . . 11.2)**

where F_H is the magnitude of the horizontal *(Gravitational) Tide Raising Force;*
m_2 is the mass of the Moon;
r is the radius of the Earth;
d is the distance between the Earth's and Moon's centres;
ϕ is the angle at the centre of the Earth between the line joining the *Sublunar* and *Antipodal Points*, and the line joining the Earth's centre with point X.

From formula (10.2), it may be seen that the *(Gravitational) Tide Raising Force* caused by the Moon varies directly with the mass of the Moon and the radius of the Earth, but is inversely proportional to the cube of the distance between Earth and Moon.

(1013) c. **Effect of the Tide Raising (or Tractive) Force.** The effect of the *Tide Raising Force* is shown at Fig 10-6 (below).

- **Minimum (Zero).** The *Tide Raising Force* is zero at the *Sublunar* and *Antipodal Points M* and *M_1* and along the *Great Circle AB* the plane of which is perpendicular to *MM_1*.
- **Maximum.** The maximum *Tide Raising Force* may be found along the *Small Circles EF* and *GH*, which are 45˚ from the *Sublunar* and *Antipodal Points* respectively.


A
E
G
Moon
M (Sublunar Point)
M1 (Antipode or Antipodal Point)
F
H
B

Fig 10-6. Effect of the Tide Raising (or Tractive) Force (*not to scale*)

d. **Lunar Equilibrium Tide.** Equilibrium is reached when the *Tides* formed at the *Sublunar* and *Antipodal Points* are at such a level that the tendency to flow away from them is balanced by the *Tide Raising Force*. The *Tide* caused in these circumstances is known as the *Lunar Equilibrium Tide* (see Fig 10-7), with a ‘High Water’(HW) at *M* and *M_1* and a ‘Low Water’(LW) at *A* and *B*.


Low Water
N
A
P
W
High Water
High Water
M1
(Antipode or Antipodal Point)
(Sublunar Point) M
Moon
Equator
E
P1
B
Low Water
S

Fig 10-7. Lunar Equilibrium Tide (*not to scale*)

1014. Effect of the Earth's Rotation

a. **Moon's Declination Zero - Lunar Equilibrium Tide.** The effect of *Tide Raising Forces* on the Earth and at points *M* and *P* / P_1-P_4 when the Moon is above the Earth's *Equator* (ie the Moon's *Declination* is zero - see Note 10-2 below) gives a *Lunar Equilibrium Tide* (see Fig 10-8 below). However, the Earth rotates relative to the Moon once every *Lunar Day* (approximately 24 hours 50 minutes) and thus during this period observers at points *M* and P_1-P_4 will experience two equal HWs at intervals of 12 hrs 25 mins, interspersed with two equal LWs also 12 hrs 25 mins apart. Such *Tide*s, with 1 cycle per ½ day, are called *Semi-Diurnal Tide*s (see Para 1020 for further details).



Fig 10-8. Moon's Declination Zero and Effect of the Earth's Rotation (1) (*not to scale*)

b. **Lunar Equilibrium Tide - Parameters.** *Tide Raising Force* magnitudes vary with the cosine of *Latitude* ϕ ° (see Fig 10-9 below). HW occurs shortly after the Moon's transit (upper and lower) of the observer's *Meridian*; the slight delay is a side effect of the Earth's rotation. The (tidal) *Range* (ie HW minus LW heights) of the *Lunar Equilibrium Tide* is less than 1 metre at the *Equator*.



Fig 10-9. Moon's Declination Zero and Effect of the Earth's Rotation (2)

Note 10-2. *Declination is the angular distance of a heavenly body North or South of the Celestial Equator, and corresponds to Latitude on the Earth (see details at BR 45 Volume 2).*

1015. Change of Moon's Declination

a. **Diurnal Inequality.** When the Moon's *Declination* is NOT zero, maximum *Tides* still occur at the *Sublunar* and *Antipodal Points M* and M_1. But at any point *P* on the Earth's surface (see Fig 10-10 below), not only are the heights of successive HWs and LWs different, but the time intervals between them also change (see Fig 10-11 below). This effect is known as *Diurnal Inequality* and affects *Diurnal* and *Semi-Diurnal Tides*.



Fig 10-10. Effects of the Moon's Declination (*not to scale*)



Fig 10-11. Diurnal Inequality (Semi-Diurnal Tides)

b. **Diurnal Tides.** At a point *Q* on the Earth's surface, where its *Latitude* is greater than 90˚ minus the Moon's *Declination* (*90˚-D*) - (see Fig 10-10 above), the *Tide Raising Force* never reaches zero; from Fig 10-12 (opposite), it can be seen that at *Q* there is only one HW and one LW every *Lunar Day*. Such *Tide*s, with 1 cycle per day, are called *Diurnal Tide*s (see Para 1020 for further details).

c. **Declination Cycles.** The Moon's *Declination* changes between North - South maxima and back every 27⅓ days, causing a similar effect on the *Tide* to be experienced roughly every fortnight. In addition, over an 18.6 year cycle, the Moon's maximum monthly *Declination* oscillates between about 18½˚ and 28½˚.

(1015 continued)



Fig 10-12. Diurnal Tides

(1015) d. **Distance of the Moon.** As the Moon rotates around the Earth approximately once every 27½ days (see Fig 10-1), the *Tide Raising Force* is strongest when the Moon is closest to the Earth (ie *Perigee*), with a *Perigean Tide*. The *Tide Raising Force* is weakest when the Moon is furthest away (ie *Apogee*), with an *Apogean Tide*. Variation in the Moon's distance causes a 15% and 20% difference in the lunar *Tide Raising Force*; thus, *Tides* at *Perigee* are usually appreciably higher than those at *Apogee*.

1016. The Earth-Sun System

a. **Earth-Sun Barycentre.** The Earth and Sun form another independent *Tide Raising* system rotating around the Earth-Sun *Barycentre*. Similarly to the Earth-Moon system (see Para 1011), the Earth-Moon *Barycentre* describes an elliptical orbit around the Earth-Sun *Barycentre* (a point located inside the Sun) - see Fig 10-13 (below). It takes one year (about 365¼ days) for the Earth to complete one orbit around the Sun.


Orbit of the Earth-Moon Barycentre
around the Earth-Sun Barycentre
Earth-Moon
Barycentre
Moon
Earth
Sun
Earth-Sun
Barycentre

Fig 10-13. The Earth-Sun System (*not to scale*)

(1016) b. **Magnitude of the Sun's Tide Raising Force.** Although the Sun has a much greater mass than the Moon, the Sun's *Tide Raising Force* is only about 45% that of the Moon. This is because the *Tide Raising Force* is inversely proportional to the cube of the distance between the bodies [see formula (10.2)].

c. **Effect of the Sun's Tide Raising Force.** Although of lesser magnitude, the *Tide Raising* effects of the Sun on the Earth are similar to those of the Moon. Thus, *Tides* caused by the Sun will vary according to the following parameters:

- **Earth's Rotation.** The *Solar Day* is approximately 24 hours; thus when the Sun's *Declination* is zero, the *Semi-Diurnal* '*Solar Equilibrium Tide*' will have two HWs 12 hours apart, interspersed with two LWs also 12 hours apart. The time interval between successive HWs and LWs will be 6 hours.
- **Change of Sun's Declination.** The Sun's *Declination* changes much more slowly than that of the Moon and reaches a maximum of about 23½° North and South of the *Equator* on about 22nd June and 22nd December respectively, these dates being known as the *Solstices* (see details at BR 45 Volume 2).
- **Distance of the Sun.** It takes the Earth about 1 year (approx 365¼ days) to complete its elliptical orbit around the Sun. *Perihelion*, when the Earth is closest to the Sun, occurs on about 2nd January, and *Aphelion,* when the Earth is furthest away, occurs on about 1st July. Thus, the Sun's *Tide Raising* Force will be at its maximum in January and at its minimum in July. However, this variation in magnitude is very small, in the order of 3%.

1017. Springs and Neaps

a. **Spring Tides.** Twice every *Lunar Month*, the Earth, Moon and Sun are in line with each other when viewed in the *Ecliptic Plane* (see Fig 10-14 below). At '*New Moon*', the Moon is passing between the Sun and the Earth (which is not visible to an observer on Earth - effectively a 'black' Moon); the Moon's and Sun's *Tide Raising Forces* are thus working in '*Conjunction*'. About 14¾ days later, at '*Full Moon*' (when the Moon is seen as a bright full disc), the Earth is between the Moon and Sun; the Moon's and Sun's *Tide Raising Forces* are thus working in *'Opposition'*. The net result in both cases is a maximum *Tide Raising Force*, producing what are known as *Spring Tides*, when higher HWs and lower LWs than usual will be experienced; *Spring Tides* occur shortly after *New Moons* and *Full Moons* take place (see Para 1017d opposite). Details of the Moon's phases are at BR 45 Volume 2.



Fig 10-14. Spring Tides (*not to scale*)

(1017) b. **Neap Tides.** Twice every *Lunar Month* (ie about every 14¾ days), the Moon and Sun are at 90˚ to each other (see Fig 10-15 below). At these times the Moon and Sun are said to be in *Quadrature.* This occurs when the Moon is in the *First Quarter* and *Last Quarter*, and at this time the Moon's and Sun's *Tide Raising Forces* are working at 90˚ to each other. The net result in both cases is a minimum *Tide Raising Force*, producing what are known as *Neap Tide*s when lower HWs and higher LWs than usual will be experienced; *Neap Tide*s occur shortly after *First* and *Last Quarters* of the Moon take place (see Para 1017d below). Details of the Moon's phases are at BR 45 Volume 2.



Fig 10-15. Neap Tides (*not to scale*)

c. **Frequency of Springs and Neaps.** Two *Spring Tides* thus occur each *Lunar Month* interspersed with two *Neap Tides*, the interval between successive *Spring* and *Neap Tides* being about 7½ days. This occurs at many places in the world, although other inequalities sometimes alter these timings.

d. **Timing of Springs and Neaps.** *Spring* and *Neap Tides* usually follow the relevant phase of the Moon by 2 or 3 days. This is because there is always a time-lag between the action of the force and the reaction to it, caused by the time taken to overcome the inertia of the water surface and friction. *Spring* and *Neap Tides* will occur at approximately the same time of day at any particular place, since the Moon at that time is in a similar position relative to the Sun.

e. **Equinoctial and Solstitial Declinations.** When the *Declinations* of the Moon and the Sun are the same, their *Tide Raising Forces* act more in concert than when the *Declinations* are different. However, as stated at Para 1015c, the Moon's *Declination* changes rapidly over a 4 week period. It can be at any value at the actual *Equinox* or *Solstice*, although it is bound to reach zero or maximum *Declination* respectively within a few days.

f. **Equinoctial Tides.** At the *Equinoxes* (March and September), when the *Declinations* of Moon and Sun are both zero, the Semi-Diurnal *'Luni-Solar' Tide Raising Force* will be at its maximum, thus causing *Equinoctial Tides*. At these times *Semi-Diurnal Spring Tides* are normally higher than other *Spring Tides*.

(1017) g. **Solstitial Tides.** At the *Solstices* (June and December), when the *Declinations* of Moon and Sun are both maximum, the *Diurnal ‘Luni-Solar’ Tide Raising Force* is at its maximum, thus causing the *Solstitial Tides*. At these times *Diurnal Tides* and the *Diurnal Inequality* are at a maximum.

h. **Priming and Lagging.** It was explained at Para 1014 that the effect of the Earth’s rotation and that of the Moon relative to each other is to cause a HW at intervals of about 12 hours 25 minutes. The effect of the Earth’s rotation and that of the Sun relative to each other is to cause a (smaller) HW at intervals of about 12 hours. Thus, when the effects of both Moon and Sun are taken together, the intervals between successive HWs and LWs will be altered. When the Moon is in a position between *New Moon / Full Moon* and *Quadrature*, the Sun’s effect will be to cause the time of HW either to precede the time of the Moon’s transit of the *Meridian* or to follow the time of the Moon’s transit (see Fig 10-16 below); this is known as *Priming* and *Lagging*.

- **Priming.** The *Tide* is said to *‘Prime’* between the *New Moon* and the *First Quarter*, and between *Full Moon* and the *Last Quarter*; HW then occurs before the Moon’s transit of the *Meridian*.
- **Lagging.** The *Tide* is said to *‘Lag’* between the *First Quarter* and *Full Moon*, and between the *Last Quarter* and *New Moon*; HW then occurs after the Moon’s transit of the *Meridian*.



Fig 10-16. Priming and Lagging of the Tides (*not to scale*)

1018. Summary of Tidal Theory

a. **Tide Raising Forces.** *Semi-Diurnal Tide Raising Force* is maximum when the Moon’s *Declination* is zero and minimum when it is greatest. *Diurnal Tide Raising Force* is zero when the Moon’s *Declination* is zero and maximum when it is greatest. The Sun’s *Declination* has a similar effect, but with a different period. Changes in the Sun’s and Moon’s distances from the Earth each cause variations in the *Tide Raising Force*. The Sun’s *Tide Raising Force* is about 45% of the Moon’s.

b. **Spring and Neap Tides.** *Spring* and *Neap Tides* occur at intervals of about 14 days, caused by the Moon and Sun either working together at *Full Moon* / *New Moon* (*Springs*) or against each other at *First* and *Last Quarters* (*Neaps*).

1019. Spare

SECTION 2 - THE TIDES IN PRACTICE

1020. Diurnal and Semi-Diurnal Tides

In practice, actual *Tides* may differ considerably from theoretical *Luni-Solar Equilibrium Tides* (see Paras 1013-1018). This is because of the size, depth and configuration of the ocean basins, land masses, the friction and inertia to be overcome in any particular body of water, together with other complicating factors.

a. **Tidal Waves.** For an appreciable *Tide* to be raised in a body of water, it is essential to generate a large enough *Tide Raising Force*; to achieve this, the body of water must be large. The great oceans of the world - the Pacific, Atlantic and Indian Oceans - are large enough to permit *Tides* to be generated, although *Tides* do not appear as a single *Tidal Wave* form but rather as the sum of a number of oscillating *Tidal Wave* forms.

b. **Diurnal, Semi-Diurnal and Mixed Tides.** The natural period of *Tidal Wave* oscillation is the decisive factor in determining whether the body of water responds to *Diurnal* or *Semi-Diurnal Tide Raising Forces,* or a mixture of the two. Hence, *Tides* in practice are often referred to as being *Semi-Diurnal*, *Diurnal* or a mixture of both.

- **Atlantic Ocean.** The Atlantic is more responsive to *Semi-Diurnal Tide Raising Forces*; thus *Tides* on the Atlantic coast and around the British Isles tend to be *Semi-Diurnal* in character (ie two HWs and two LWs per day) and are more influenced by the phases of the Moon than by its *Declination*. 'Large' *Springs Tides* occur near *Full* or *New Moons* with 'small' *Neap Tides* near the *First* and *Last Quarters*. The largest *Tides* of the year occur at *Springs* near the *Equinoxes* when the *Declinations* of the Sun and Moon are both zero (ie they are over the *Equator*).
- **Pacific Ocean.** The Pacific is generally more responsive to the *Diurnal Tide Raising Forces*, and so *Tides* here tend to have a large *Diurnal* component. In these areas, the largest *Tides* are associated with the greatest *Declination* of Sun and Moon (ie at the *Solstices*). Areas in the West Pacific off New Guinea, Vietnam and in the Java Sea are predominantly *Diurnal* with one single HW and LW per day; on the North / East coasts of Java, *Tides* are purely *Diurnal*.
- **Mixed Tides.** *Mixed Tides*, where *Diurnal* and *Semi-Diurnal Tide Raising Force*s are both important, tend to be characterised by a large *Diurnal Inequality* (see Para 1015, Fig 10-11). This may be apparent in the heights of successive HWs, LWs or both; such *Tides* are common along the Pacific coast of the USA, the East coast of West Malaysia, Borneo, Australia and the waters of South-West Asia. Occasionally, the *Tides* may even be purely *Diurnal*.
- **Mediterranean and Baltic Seas.** The bodies of water of the Mediterranean and Baltic Seas are too small to enable any appreciable *Tide* to be generated.
    - **Strait of Gibraltar.** The Strait of Gibraltar is too restricted to allow the Atlantic *Tides* to have any appreciable effect other than at its extreme Western end.
    - **Adriatic Sea.** The greatest *Tides* are to be found in the Adriatic Sea, where they are predominantly mixed, with a *Diurnal Inequality* at both HW and LW water. The (tidal) *Range* may exceed 0.5 metre in several places in the Adriatic, but is rarely greater than 1 metre.

1021. Shallow Water and Other Special Effects

a. **Oscillating Tidal Wave Distortions.** *Tides* travel as oscillating *Tidal Waves* (see Para 1020a), and as they enter shallow water, they slow down. The trough is retarded more than the crest; thus there is a progressive steepening of the wave front accompanied by a considerable increase in the wave height (*Amplitude*). This distorts the timing, so that the period of rise becomes shorter than the period of fall. These *Shallow Water Effect*s are present to a greater or lesser degree in the *Tides* of all coastal waters.

b. **Estuaries.** The *Amplitude* (height) of the *Tidal Wave* increases even more if it travels up an estuary which narrows from a wide entrance. This may result in very large *Tides* such as those to be found in the Bay of Fundy (Nova Scotia), the Severn Estuary (UK) and around the Channel Islands (UK).

c. **Tidal Bores.** Where a river is fed from an estuary with a large (tidal) *Range*, a phenomenon known as a (tidal) '*Bore*' (Old English - '*Eagre*') may be found. The crest of the rising *Tide* overtakes the trough and tends to break. Should it break, a (tidal) *Bore* occurs in which half or more of the total rise of *Tide* occurs in only a few minutes. Notable (tidal) *Bores* are in the Rivers Severn (UK), Seine (France), Hooghly (India - West Bengal) and Chien Tang Kiang (China - Hangzhou,Yangtze Delta).

d. **Double HWs / LWs.** At certain places, *Shallow Water Effects* are such that more than 2 HWs or 2 LWs may be caused in a day. In UK, at Southampton (see Fig 10-17 below), double HWs occur with an interval of about 2 hours between them; further west, at Portland, double LWs occur (see Fig 10-18 below). Double HWs / LWs also occur on the Dutch coast and at other places. The practical effect of this is to create a longer *'Stand'* at HW / LW (a *'Stand'* is defined as the period at HW or LW between the *Tide* ceasing to rise / fall and starting to fall / rise, respectively).



Fig 10-17. Tidal Curves at Southampton (UK) showing Double HW at Springs



Fig 10-18. Tidal Curves at Portland (UK) showing Double LW at Springs

(1021) e. **Special Tidal Curves - Southern UK.** Because of the distortion of *Tidal Waves* caused by *Shallow Water Effects*, special curves based on LW for determining the *Height of Tide* (*HOT*) on the south coast of UK between Swanage and Selsey are contained in Admiralty Tide Tables Volume 1 (NP 201). The tidal curve at Southampton (a *Standard Port*) is also based on LW because of the complexity of the *Tides* around HW.

1022. Meteorological Effects on Tides

Non-standard meteorological conditions can substantially affect actual *Tides* experienced, as compared to predicted *Tides*. The effect of such conditions is complex and difficult to forecast, even with the resources of *National Hydrographic Offices* (*NHOs*) and Weather Centres. Apparently 'unexplained' changes to *Tides* can occur (eg the effect of a storm-centre hundreds of miles away, in otherwise benign conditions) and mariners should be aware that tidal predictions are indeed only 'predictions'; an adequate margin of safety should always be allowed when planning *Underkeel Clearances*. Some of the main meteorological conditions affecting *Tides* are as follows.

a. **Barometric Pressure.** Tidal predictions are computed for average barometric pressure in the local area; a 34 millibar change can cause a difference in *HOT* of about 0.3 metres. Low barometric pressure will tend to raise sea level and high barometric pressure will tend to depress it. The water level does not adjust itself immediately to a change of pressure and it responds to the average change in pressure over a considerable area. Changes in sea level due to barometric pressure rarely exceed 0.3 metres but when other factors are added, this effect can be important.

b. **Wind.** The effect of wind on *HOT* and HW / LW times is very variable; it depends largely on the topography of the area. In general, wind will raise the sea level in the direction to which it is blowing. A strong onshore wind piles up the water and causes HWs to be higher than predicted; this can have substantial effect in harbours (eg in Portsmouth [UK], where strong onshore winds with low barometric pressure can increase the *HOT* by up to 1.0 metre). Offshore winds have the reverse effect, drawing water away from a coastline, making LWs lower than predicted. Winds blowing along the coast tend to set up long *Tidal Waves* which travel along the coast, raising sea level where the crest of the *Tidal Wave* appears and lowering sea level in the trough.

c. **Seiches.** Abrupt changes in meteorological conditions (eg passage of an intense depression or line squall) may cause an oscillation in the sea level known as a *Seiche*. The period between successive *Tidal Waves* may vary from a few minutes to about 2 hours and the height of the *Tidal Waves* may vary from 1 centimetre to 1 metre.

d. **Positive and Negative Surges - Summary.** A rise in sea level superimposed on the normal tidal cycle, caused by a combination of wind and pressure or other factors, is referred to as a *Positive Surge* and a fall as a *Negative Surge*. Both *Positive* and *Negative Surges* may alter the predicted times of HW / LW, often by as much as 1 hour.

e. **Positive Surges.** *Positive Surges* have the greatest effect when confined to a gulf or bight (eg the North Sea [UK]). Unless they are *Storm Surges* (see Para 1022g), they rarely increase sea level height by more than 1 metre. In a bight (eg the North Sea), northerly winds will raise sea level at the southern end, causing a *Positive Surge*.

(1022) f. **Negative Surges.** *Negative Surges* are of great importance to vessels navigating with small *Underkeel Clearances*. *Negative Surges* are most evident in estuaries and areas of shallow water, and typically occur when strong winds blow water away from shore over a significant *Fetch* of shallow water. Falls in sea level of up to 1 metre are common, while 2 metres have been recorded. In the North Sea (UK), strong Southerly winds will lower sea level at the southern end. *Negative Surges* may also occur due to *Storm Surges*. *Negative Surge* warnings may be given in the Southern North Sea, Thames Estuary and Dover Straits from 6-12 hours (possibly up to 30 hours) ahead.

g. **UK Storm Surges.** *Storm Surges* in the North Sea are wave forms which occur if an intense depression with storm force winds sets up a wave running down the UK coast at a speed similar to that of the *Tidal Wave.* The *Tidal Wave* is reinforced by the storm and increases in amplitude, reaching up to 3 metres in height. If a *Storm Surge* crest coincides with HW *Springs*, a strong *Positive Surge* is created; flooding and damage may be caused along the coastline (see Note 10-3 below). If the trough of a *Storm Surge* coincides with LW *Springs*, a strong *Negative Surge* occurs. Lesser *Negative Surge*s can occur at any part of the tidal cycle, thus reducing *Underkeel Clearances.*

Note 10-3. *In1953 a Storm Surge in the Southern North Sea (UK) raised sea level by 2.7 to 3 metres. This coincided with HW Springs and caused severe flooding in East Anglia, Kent and London, with of loss of over 300 lives; as a result, the 'Thames Barrage' was built across the River Thames east of London and other flood defences were improved. In 2007, a Storm Surge of 2.8 metres occurred in the same area but did not quite coincide with HW Springs; it was held back by the improved flood defences. Storm Surges are also likely in the Bay of Bengal.*

1023. Seismic Waves (Tsunamis)

Tsunamis (often incorrectly called '*Tidal Waves*') are groups of *Seismic Waves* with a very high wave speed (300 to 500 knots) and are entirely unconnected with *Tides*; they are formed by seismic action (earthquake or 'seaquake') on the ocean floor. These eruptions are concentrated at the boundaries of *Tectonic Plates* and Japan is particularly vulnerable to them, although they can affect anywhere with an uninterrupted *Fetch* to a *Tectonic Plate* boundary. They cause great damage and loss of life ashore, and are a serious hazard to coastal shipping and ships in port. See NP 100 (The Mariners Handbook) and BR 45 Volume 6 Chapter 6.

a. **Open Ocean.** At the epicentre, *Tsunamis* have a wave height under 1 metre and a wave length of over 100 miles, so are largely undetectable in the open ocean.

b. **Shallow Water / Shore.** On entering shallow water, the waves become shorter and higher, reaching a wave height of up to 17 metres when they strike the shore. The first indication of a *Tsunami's* approach may be a sudden drop in sea level. A group of waves may then strike at intervals of 10 to 40 minutes ; the second and third waves are usually higher than the first, with the rest gradually decreasing over an extended period.

Note 10-4. *Satellite observation of the 2004 Tsunami which devastated Indian Ocean coastlines with the loss of over 250,000 lives, established that in open ocean the wave height was 0.9 metres with a wave speed of 450 knots. On approaching shallow coastal water, wave height increased to 10 metres while the wave speed reduced to 20 knots.*

1024-1029. Spare

SECTION 3 - TIDAL HARMONICS AND SHM FOR WINDOWS

1030. Harmonic Constituents

a. **Scope of Harmonic Constituents.** The *Tide Raising Force*s comprise a large number of *Harmonic Constituent* cosine curves, the periods and relative *Amplitude*s of which can be calculated from astronomical theory. Some 400 *Harmonic Constituents* have been identified but in practice it is unnecessary to use so many. Up to 160 *Harmonic Constituents* are used for major *Standard Ports* and up to 36 for *Secondary Ports*. The *Harmonic Constituents* are given symbols from which their general significance may be deduced (eg the letter *M* is used for lunar constituents, *S* for solar constituents, the subscript $_1$ for *Diurnal* and the subscript $_2$ for *Semi-Diurnal* components).

b. **Tidal Observations.** To predict with accuracy the *HOT* at any place, extensive tidal observations must be carried out and the results analysed to identify a number of *Harmonic Constituents* making up the *Tide Raising Force*s at that place. Due to the various cycles involved, a period of 18.6 years, equal to the longest cycle, is desirable if all the necessary *Harmonic Constituents* are to be identified. However, adequate predictions may be made over shorter periods, as follows:

- **Admiralty Tide Tables - Standard Ports.** For *Standard Port* predictions in the Admiralty Tide Tables (NPs 201-204), the general rule is for at least 1 complete year's observations to be analysed. This permits the identification of up to 160 *Harmonic Constituents*.
- **Admiralty Tide Tables - Secondary Ports.** For *Secondary Ports*, analysis of at least 1 month's observations is the aim, as this permits the identification of up to 36 *Harmonic Constituents* (see Para 1031 below).

1031. Principles of Harmonic Tidal Analysis

a. **Principal Harmonic Constituents.** The four principal *Harmonic Constituents* with which the user will come into contact are:

- **M_2** - is the principal *Lunar Semi-Diurnal Harmonic Constituent*, which permits calculations of the *Amplitude* caused by a theoretical Moon in circular orbit around the Earth at the average speed of the real Moon, halfway between *Apogee* and *Perigee* and at an average Northerly or Southerly *Declination*.
- **S_2 -** is the principal *Solar Semi-Diurnal Harmonic Constituent*, which permits calculation of the *Amplitude* caused by a theoretical Sun in similar circumstances to that for the Moon (at M_2 above).
- **K_1** - is the *Luni-Solar Declinational Diurnal Harmonic Constituent*, which allows for part of the Moon's and Sun's *Declinations*.
- **O_1** - is the Lunar *Declinational Diurnal Harmonic Constituent*, which allows for the remainder of the Moon's *Declination*.

(1031) b. **Components of Harmonic Constituents.** Each *Harmonic Constituent* has a speed, (°/ hour, when 1 cycle = 360°), an *Amplitude 'H'* and a *Phase Lag 'g'*. Cycle and speed details for the 4 main *Harmonic Constituent* components are at Table 10-1 (below).

Table 10-1. Cycle and Speed Details for the 4 Main Harmonic Constituents

Harmonic Constituent	Cycles per Day	Speed (Degrees per Hour)	Time to Complete 1 Cycle
M_2	2	28°.98	12 h 25 min
S_2	2	30°	12 h 00 min
K_1	1	15°.04	23 h 56 min
O_1	1	13°.94	25 h 50 min

c. **Harmonic Constants.** The *Amplitude 'H'* and *Phase Lag 'g'* of a *Harmonic Constituent* are known as the Harmonic Constants of that *Harmonic Constituent.*

- **Amplitude 'H'.** The *Amplitude 'H'* is equal to half the (tidal) *Range* (ie half of HW minus LW heights for each oscillation).
- **Phase Lag 'g'.** The phase of a *Harmonic Constituent* is its position in time, in relation to its theoretical position as deduced from astronomical theory. *Tide Raising Force*s do not act instantaneously (see Para 1017d), thus each *Harmonic Constituent* has a (time) *Phase Lag 'g'*.

d. **Tidal Analysis and Predictions.** The purpose of tidal analysis is to determine the *Harmonic Constants* for a particular location (ie *Amplitude 'H'* and *Phase Lag 'g'*). Tidal predictions are then made using an appropriate number of *Harmonic Constituents*. In many places (eg Portsmouth [UK]), the *Harmonic Constituents* for *Shallow Water Effect*s (see Para 1021) are very complex and extra *Shallow Water Corrections* are applied. The authority for the observations, *Harmonic Constants*, predictions, method of prediction and year of observation are in the Admiralty Tide Tables (NPs 201-204).

1032. Simplified Harmonic Method - 'SHM for Windows®' Software (DP 560)

'*SHM for Windows®*' is a simple Windows-based tidal prediction program using the *UKHO's Simplified Harmonic Method* (*SHM*) of tidal prediction. It is supplied by *UKHO* on a CD-ROM as DP 560. A variation of *SHM* is also published in the Admiralty Tide Tables (NPs 201-204) for those who wish to use it with a pocket calculator.

a **Operation.** '*SHM for Windows®*' is safe, accurate, fast and user-friendly. The user is required to input *Harmonic Constants* and *Shallow Water Corrections*, principally from the 'Admiralty Tide Tables' (NPs 201-204) or 'Tidal Harmonic Constants - European Waters' (NP 160). Predictions are then displayed as a graph of heights against time, for up to 24 hours and up to 7 consecutive days; these results may be printed.

b. **Program Duration and Storage of Data.** The calculation software is everlasting, but does require up to date *Harmonic Constants* to be stored or input. Data for any number of ports or *Tidal Streams* may be stored within the software.

1033-1039. Spare.

SECTION 4 - TIDAL STREAMS AND CURRENTS

1040. Primary Definitions and Types of Tidal Streams

a. **Primary Definitions.** The terms '*Tides*' (vertical), *'Tidal Streams'* (horizontal), *Currents* and the American usage *'Tidal Currents'* are frequently mixed up; their definitions are stated at Para 1002, but are repeated for the convenience of readers.

(Extract from Para 1002):

- **Tides.** '*Tides*' are **periodic vertical reversing** movements of the water on the Earth's surface, caused by *Tide Raising Forces* of the Moon and Sun.
- **Tidal Streams.** *'Tidal Streams'* are the **periodic horizontal reversing** movements of the water accompanying the vertical rising and falling of *Tides* .
- **Currents.** Ocean *Currents* are **non-tidal** movements of water, which may flow **steadily** at all depths in the oceans and may have both horizontal and vertical components; a *Surface Current* can only have a horizontal component. In rivers and estuaries, there is often a permanent *Current* caused by the flow of river water.
- **Tidal Currents.** *'Tidal Currents'* is the American usage for *'Tidal Streams'*. The term *'Tidal Currents'* is NOT used in this book.

b. **Types of Tidal Stream.** *Tidal Stream*s are of two types: *'Rectilinear'* and '*Rotary*'.

- **Rectilinear Tidal Streams.** *Rectilinear Tidal Streams* have only two directions (with small variations), which may be called the *'Flood*' (the incoming *Tidal Stream*) or the *'Ebb*' (the outgoing *Tidal Stream*). Ideally, instead of the terms '*Flood*' and '*Ebb*', the water flow should be described by its direction (eg East-going or 090˚), with its rate (eg 090˚ 2.0 kn).

- **Rotary Tidal Streams.** *Rotary Tidal Streams* continually change in direction; they rotate through 360˚ in a complete cycle. The rate of the *Tidal Stream* usually varies throughout the cycle, with two maxima in approximately opposite directions interspersed with two minima about halfway between the maxima in time and direction.

c. **Occurrences of Tidal Stream Types.**

- **Rectilinear Tidal Streams.** *Rectilinear Tidal Streams* are normally found in port approaches, estuaries, channels and straits, where the direction of the flow of the *Tidal Stream* is constricted by the surrounding land and shoals.

- **Rotary Tidal Streams.** *Rotary Tidal Streams* are normally found offshore where constraints to the water flow are absent.

d. **Semi-Diurnal and Diurnal Components of Tidal Streams.** *Tidal Streams* may have *Semi-Diurnal* and *Diurnal* components, including *Diurnal Inequality*, and can be analysed harmonically or non-harmonically. In European waters (where *Tides* are *Semi-Diurnal*) *Tidal Stream* rates are usually related to the *Range* of the *Tide,* and the times of 'Slack Water' are usually related to (but not necessarily the same as) the times of HW and LW at the nearest *Standard Port* (eg In UK, 'Slack Water' occurs at 'Half Tide' on the East coast but at HW / LW on the South coast). Significant differences in the times of 'Slack Water' may occur between ports / harbours and adjacent offshore areas.

1041. Currents

The causes of *Tides* and *Tidal Streams* due to *Tide Raising Forces* have already been fully explained at Paras 1002-1022 . However, *Currents* (non-tidal movements of water) are caused by a variety of factors quite separate from *Tide Raising Forces*.

a. **Causes of Currents.** *Currents* are caused by meteorological factors (eg wind and barometric pressure), oceanographic factors (eg water of differing sea levels, salinity and/or temperatures) and by topographical factors (eg irregularities in the sea-bed, run-off of water from the land in rivers and estuaries). A detailed explanation of ocean *Current* types (ie *Drift Currents* and *Gradient Currents*) and a summary of the characteristics of the principal ocean *Currents* is at Chapter 11 (Paras 1120-1125).

b. **Causes of River Currents.** In rivers and estuaries, there is often a permanent (but variable) *Current* caused by the flow of river water from the land. The flow of river water in such *Current*s is heavily dependent on rainfall inland.

c. **Assessment of Currents for Chartwork.** The practical assessment of the rate and direction of *Currents* for chartwork is at Chapter 7.

1042. Tidal Stream Data, Atlases and Observations

a. **Semi-Diurnal Tidal Streams.** *Semi-Diurnal Tidal Streams* (eg European waters) may be predicted from *Mean High Water Springs (MHWS) / Mean High Water Neaps (MHWN)* at a *Standard Port*. *Tidal Stream* predictions are displayed in tables on the chart, in *ENC* databases and in *Tidal Stream Atlases* (see Fig 10-19 overleaf), showing the rate and direction at *MHWS / MHWN*, by reference to the time of HW at a suitable *Standard Port*. The rate on occasions other than *MHWS / MHWN* may be found by using the (tidal) *'Range of the Day*' to interpolate or extrapolate from the two mean rates (see Para 1045), thus avoiding the need for date-specific predictions to be published.

b. **Tidal Stream Atlases.** Where the *Tidal Stream* is related to a *Standard Port* (see Para 1042a above), *Tidal Stream Atlases* show *Tidal Streams* in pictorial form (see Fig 10-19 overleaf); they are available from *UKHO* (with instructions for their use) for the waters around UK and the west coast of France. RN / RFA vessels have access to more detailed (classified) *Tidal Stream Atlases* and guidance for HM Naval Bases.

c. **Admiralty Sailing Directions (Pilots).** Limited *Tidal Stream* information is also contained in *Admiralty Sailing Directions* (*Pilots*).

d. **Tidal Streams with Large Diurnal Inequality.** Where the *Diurnal Inequality* of the *Tidal Stream* is large (eg Malacca and Singapore Straits), the procedure at Para 1042a (above) is not possible and individual date-specific predictions are needed.

- **Tidal Stream Tables.** Daily *Tidal Stream* predictions for important areas are published as 'Tidal Stream Tables' in Volumes 3 and 4 of the Admiralty Tide Tables (NPs 203-204).
- **TotalTide®.** *UKHO's TotalTide*® software can predict all *Tidal Streams* with the integrity of the Admiralty Tide Tables; see details at Para 1051.
- **SHM.** *Harmonic Constants* for some *Tidal Streams* are also published in Volumes 2, 3 and 4 of the Admiralty Tide Tables (NPs 202-204) so that predictions may be made using *SHM for Windows*® software; see Para 1032.

(1042) e. **Tidal Stream Observations and Predictions.** *Tidal Stream* predictions for UK waters are generally based on observations extending over a period of 25 hours, which is a far shorter period than the equivalent observations for *Tide* predictions. Permanent *Curren*ts in rivers and estuaries are included, but for coastal predictions any variable *Curren*t is removed before the predictions are compiled. The observation of *Tidal Streams* presents greater difficulties than the observation of *Tides* and a lesser degree of observational accuracy is achievable for the following reasons:

- **Sea-bed Topography.** Because of the rapidly changing effect of sea-bed topography on the direction and rate of the *Tidal Stream*, it is often impossible to give more than an indication of how a vessel will be affected by *Tidal Stream*s.
- **Channels.** In a channel, the *Tidal Stream* may be running strongly (eg 3 kn) in the centre with virtually no *Tidal Stream* (or even a *Tidal Stream* running in the opposite direction) at the edges of the channel. The *Tidal Stream* may vary significantly (eg from zero to 3 kn) in the navigable part of the channel. Thus *Tidal Stream* predictions for any given position in a channel will be correct for that exact position, but may well be incorrect for a position a few metres either side.
- **Complexity.** While the *Tidal Stream* predictions must be accurate enough for navigational purposes, the methods of prediction to achieve an adequate result are not as complex as those for *Tide* predictions.

f. **International Regulations for Charts, Tide Tables and Tidal Stream Data.** Certain countries and ports may make the carriage and use of specified Tide Tables, *Tidal Stream Atlases,* charts and diagrams compulsory for ships proceeding to and from their ports. Mariners are advised to check the necessary regulations in good time.

1043. Tidal Stream at Depth

Published *Tidal Stream* data normally refers to the uppermost 10 metre layer of the sea. The following guidance is of necessity generalised and local conditions may vary from it.

a. **0% to 75% of Depth of Water.** Except for areas fed by river water in addition to the *Tides* (see Para 1043c below), *Tidal Streams* at depths below 10 metres tend to be very similar to those on the surface to a depth of about 75% of the total depth of water. However, the times of Slack Water may be different by as much as 1 hour compared with surface Slack Water times; Slack Water at depth is usually early but sometimes late.

b. **75% to 100% of Depth of Water.** At depths greater than 75% of the total depth of water, until about 1 metre above the sea-bed, *Tidal Streams* fall away in strength to a value which may be about 50% to 60% of the surface rate, and also change direction slightly by about 10° to 20°. In the bottom metre to the sea-bed, *Tidal Streams* may undergo a marked change from those on the surface.

c. **Effect of River Water.** The situation at Para 1043a may be quite different in ports which are fed by river water in addition to the *Tides* (eg Devonport [UK]). The strength and direction of the *Tidal Stream* may vary considerably with depth, dependent on the amount of fresh water flowing down-river, and the depth to which it penetrates.

1044. Eddies, Races and Overfalls

a. **Causes of Eddies, Races and Overfalls.** *Eddies, Tide-Rips, Overfalls* and *Races* are different forms of water turbulence caused by any of the following:

- Abruptly changing topography of the sea-bed.
- Configuration of the coastline.
- Constriction of channels.
- Sudden changes in *Tide* or *Tidal Stream* characteristics.

b. **Eddies.** An *Eddy* is a circular movement of water, the diameter of which may extend from a few inches to a few miles (eg at Portland [UK] there is an anti-clockwise *Eddy* of the *Tidal Stream* South East of Portland between 1 and 5 hours after HW Devonport [UK] - see Fig 10-19 below). Where the effect of *Eddies* are of a permanent nature, they are taken into account when predicting *Tidal Streams*.

c. **Overfalls.** An *Overfall* is another name for a *Tide-Rip* and is caused by a strong *Tidal Stream* near the sea-bed being deflected upwards by obstructions on the bottom, thus causing a confused sea on the surface.

d. **Races.** A *Race* is an exceptionally turbulent *Tidal Stream*, usually caused by a strong water flow round a headland or where *Tidal Streams* converge from different directions. The *Tidal Stream Atlas* for Portland [UK] shows an almost permanent *Race* (for 9 out of 12 hours), south of Portland Bill (see Fig 10-19 below).


35′
2° 30′
25′
20′
15′
50° 35′
30′
WEYMOUTH
Chesil Beach
The Nothe
N. Ship Chan
E. Ship Chan
02,07
05,10
Redcliff Pt
Ringstead Pt
White Nothe
Durdle Door
Worbarrow Tout
Lulworth Banks
05,11
08,16
06,13
08,16
West Bay
08,18
09,18
PORTLAND
03,06 04,07
03,07
07,14
05,10
11,22
Adamant Shoal
Circular 'Eddy'
04,08
09,19 05
08,15
08,16
09,19
12,25
16,32
10,20
30,60
13,26
12,25
The Shambles
Race (decreasing)
28,56
12,24
19,39
24,48
14,28
13,26
Turbulent 'Race'
12,25
18,36
14,28
1 AFTER HW DEVONPORT
4h 40m before HW DOVER
Longitude 2° 30′ West from Greenwich
NP 250

Fig 10-19. Tidal Stream Atlas - showing Circular 'Eddy' (to South East) and Turbulent 'Race' (to South) off Portland - both 1 Hour after HW Devonport (UK)

1045. 'Percentage Springs' (Tides and Tidal Streams) - Calculation and Use

This method applies to *Semi-Diurnal Tidal Streams* only, but can be adapted for use with reasonable accuracy if moderate *Diurnal Inequality* is present. If large *Diurnal Inequality* is present, *Tidal Stream* predictions must be made iaw Para 1042d. See also the 'Computation of Rates' diagram / worked example in each *Tidal Stream Atlas* (NPs 209-266,337 & 628-636).

a. **Definitions.** *Mean Spring Range (MSR)* and *Mean Neap Range* (*MNR*) are:

- **MSR.** *MSR* is the difference between *MHWS* and *MLWS. Tide Level* definitions are at Para 1062.
- **MNR.** *MNR* is the difference between *MHWN* and *MLWN. Tide Level* definitions are at Para 1062.

b. **Reason for Calculation.** *Semi-Diurnal Tidal Stream* predictions are linked to the *MSR* / *MNR*. In order to calculate the *Tidal Stream* at any particular time and date, it is necessary to establish the tidal '*Range of the Day*' between successive HWs / LWs at the port to which the data is referenced, compare it to the *MSR / MNR* and interpolate or extrapolate appropriately to give a *'Percentage Springs'* (*% Springs*) figure.

c. **Nomenclature.** It is convenient to refer to *MSR* as 100% *Springs* and to *MNR* as 0% *Springs*. The *Range of the Day* may thus be given a '*% Springs'* figure (ie *Percentage of the Day*) by interpolation / extrapolation, and this may be used to interpolate / extrapolate from the *MSR / MNR Tidal Stream* rates given at the *Tidal Stream* diamond or in the *Tidal Stream Atlas*. When the *Range of the Day* exceeds the *MSR* at the port to which the data is referenced, '% *Springs*' may be greater than 100%. Similarly, when the *Range of the Day* is less than *MNR,* '% *Springs*' will be negative (and *Tidal Streams* will be less than the lower figure given on the chart / atlas).

Example 10-1. MSR and MNR for Portsmouth are 3.9m and 1.9m respectively. At Portsmouth the heights of HW and LW are as follows:

18 February	1446 HW 4.2m	2008 LW 1.3

In this case, the '*Range of the Day*' is 2.9m; interpolation by inspection gives *50% Springs*.

27 February	1112 HW 4.7m	1653 LW 0.5

In this case, the '*Range of the Day*' is 4.2m; interpolation by inspection gives *115% Springs*.

2 September	0618 HW 3.7m	1206 LW 2.2

In this case, the '*Range of the Day*' is 1.5m; interpolation by inspection gives *-20% Springs*.

d. **Formula.** Although accurate interpolation or extrapolation by inspection is usually straightforward, '% *Springs*' may be calculated precisely, using the following formula:

$$\% \, Springs = \left(\frac{Range\ of\ Day - MNR}{MSR - MNR} \right) \text{ x } 100 \qquad \textbf{. . . 10.3}$$

Thus in Example 10-1 for 18 February (above), formula (10.3) gives**:**

$$\% \, Springs = \left(\frac{2.9 - 1.9}{3.9 - 1.9} \right) \text{ x } 100 = \left(\frac{1.0}{2.0} \right) \text{ x } 100 = 50\% \qquad \text{. . . (formula 10.3)}$$

Similar treatment may be applied to the other calculations for 27 Feb and 2 Sep.

e. **Use.** Care must be taken to use *% Springs* correctly when extrapolating (ie *50% Springs* indicates a result half-way between the *MNR* and *MSR* rates).

1046. 'Tidal Nurdle' - Construction and Use

This method applies to *Semi-Diurnal Tidal Stream* only, but can be adapted for use with reasonable accuracy if moderate *Diurnal Inequality* is present. If large *Diurnal Inequality* is present, *Tidal Stream* predictions must be made by the methods outlined at Para 1042d.

a. **Purpose.** A '*Tidal Nurdle*' diagram may be shown on the chart (at suitable *Scale*) as a representation of the *Tidal Stream* vectors applicable for a particular position over a period of several hours. It is based on *Tidal Stream* diamond or *Tidal Stream Atlas* data, and may be applied to any chartwork to allow instant assessment of future *Tidal Stream*s or comparison of the predicted *Tidal Stream*s to those actually experienced.

b. **Construction.** A '*Tidal Nurdle*' diagram is constructed as follows (see Figs 10-20 and 10-21 (opposite):

- **Step 1.** Select the *Tidal Stream* diamond on the chart (or *Tidal Stream Atlas* pages) appropriate to the area for which tidal information is required.
- **Step 2.** From the Admiralty Tide Tables or *TotalTide*® software, obtain the time of HW at the *Standard Port* to which the chart refers. From this, determine whether tidal information is required before or after HW. Calculate the '*Percentage Springs'* figure (see Para 1045 - previous page).
- **Step 3.** For the appropriate *Tidal Stream* diamond (or appropriate *Tidal Stream Atlas* data), note the *MSR / MNR* rates and direction:
  - **Interpolate.** Using the '*Percentage Springs*' figure from Step 2, interpolate between *MSR / MNR* rates to obtain the *Rates for the Day*.
  - **Vector Diagram.** In a convenient and suitable place on the chart draw a vector diagram in the direction of the *Tidal Stream*, **using a suitable *Scale Factor* with the *Rates for the Day*.** Annotate the diagram (boldly) with the selected *Scale Factor*. **The length of each vector will be the result of multiplying the *Tidal Stream* rate by the *Scale Factor*, plotted using the distance *Scale* of the chart in use.**
- **Step 4.** At the mid-point of the vector produced in Step 1, annotate the vector with the interval from HW and the direction to which the *Tidal Stream* is flowing. Add a small table summarising the *Rates for the Day*.
- **Step 5.** Repeat Steps 3 and 4 for times before and after HW, noting that:
  - **Times Before HW.** If the diagram is for times before HW, then vectors are plotted backwards from the previous one (see Fig 10-20 opposite).
  - **Times After HW.** If the diagram is for times after HW, then vectors are plotted on from the last one produced (see Fig 10-21 opposite).

c. **Precautions before Use.** The *Scale Factor* of the *Tidal Nurdle* diagram (see Step 3 above) must be taken into account when it is used.

(1046 continued)


(270°) 0900
HW
(315°)
0800
-1
0300
-6
(195°)
SCALE: x5
(000°)
-2
0700
0400
-5
(165°)
-3
(040°)
0600
-4
0500
(105°)

Rates for the Day
(Interpolated)

HW	270	0.8
-1	315	0.7
-2	000	0.7
-3	040	0.9
-4	105	0.6
-5	165	0.7
-6	195	0.6

Fig 10-20. 'Tidal Nurdle' Vector Diagram - Times Before HW


(270°) 0900
HW
1000
(240°)
+1
1100
(215°)
+2
SCALE: x5
1200
+3
(180°)
+6
(020°)
1500
+4
1300
(150°)
+5
1400
(075°)

Rates for the Day
(Interpolated)

HW	270	0.8
+1	240	0.7
+2	215	0.8
+3	180	0.6
+4	150	0.7
+5	075	0.8
+6	020	0.7

Fig 10-21. 'Tidal Nurdle' Vector Diagram - Times After HW

Notes:

10-5. Annotation at Mid Point of Vector. *All references to intervals before or after HW, are at the mid-point of each vector produced (see Para 1046b - Step 4 opposite).*

10-6. Precautions before Use - Scale Factor. *Attention is drawn to Para 1046c (opposite).*

1047-1049. Spare

SECTION 5 - ADMIRALTY TIDE TABLES AND ADMIRALTY TOTALTIDE

1050. Using Admiralty Tide Tables

Full instructions for use are included in each Volume of the Admiralty Tide Tables (NP 201-204). The following information provides a summary of these procedures.

a. **Intermediate HOT / Times at Standard Ports.** To find the *HOT* at a *Standard Port* at a given time (see Example 10-2 / Fig 10-22 below), or vice versa:

- **HW / LW Heights.** Plot the heights of HW and LW on the appropriate side of the required time and join by a sloping line.
- **HW Time.** Enter HW time (or LW in certain cases in UK [eg Southampton]) and other times before / after HW to cover the required time / event.
- **Answers.**
  - ▸ **For Heights.** From the required time, go vertically to the curves, interpolating between *MSR* and *MNR* curves (but not extrapolating outside them). Then go horizontally to sloping line, thence vertically to height scale and read off the height required.
  - ▸ **For Times.** From the required height, go vertically to the sloping line, thence horizontally to the curves, interpolating between *MSR* and *MNR* curves (but not extrapolating outside them). Then go vertically to time scale and read off the time required.

Example 10-2. Find the *HOT* at Ullapool at 1900. HW / LW times and heights are: HW 0420 4.6m, LW 1033 1.6m, HW 1641 4.6m, LW 2308 1.2m. (Answer: Height 3.7m)



Fig 10-22. Example 10-2: Finding the Height of Tide (HOT) at a Standard Port

b. **Standard Tidal Curves.** Where an individual tidal curve is not provided for a *Standard Port*, the standard tidal curve (at front of tables) may be used provided that:

- The duration of the rise or fall of the *Tide* is between 5 and 7 hours.
- There is no shallow water correction.

If either of these criteria is not met, *TotalTide*® or *SHM for Windows*® should be used.

c. **Special Tidal Curves - Southern UK.** Special curves based on LW are used for some ports on the south coast of UK. See details at Para 1021e.

(1050) d. **HW and LW at Secondary Ports.** For calculating heights at *Secondary Ports*, use data from the Admiralty Tide Tables (NPs 201-204) Parts I and II as follows:

- **Step 1.** Establish the predicted HW and LW heights at the *Standard Port*
- **Step 2.** Algebraically SUBTRACT *Seasonal Variation* for *Mean Sea Level* (*MSL*) (see Para 1060c/d) at the *Standard Port*.
- **Step 3.** Establish the *Secondary Port* height differences (interpolating or extrapolating as necessary) and apply them
- **Step 4.** Algebraically ADD *Seasonal Variation* for *MSL* (see Paras 1060c/d) at the *Secondary Port*.

e. **Intermediate HOT / Times at Secondary Ports.** Once having established the correct *HOT* / times of HW and LW at a *Secondary Port* (Para 1050d above), use this data with the procedures at Para 1050a/b/c (opposite), to calculate the intermediate *HOT* / times required.

f. **Tidal Prediction Form - Secondary Ports HW / LW.** Copies of *UKHO's* 'Tidal Prediction Form' are at the back of each volume of Admiralty Tide Tables to assist users in correctly applying the tabulated differences and *MSL Seasonal Variations* for HW / LW at *Secondary Ports*.

g. **Tabulation of Secondary Port Differences.**

- **Semi-Diurnal Tides.** Where the *Tide* is mainly *Semi-Diurnal* in character, the differences are tabulated for *MHWS, MLWS, MHWN, MLWN* at the Standard Port. *Tide Level* definitions are at Para 1062.
- **Large Diurnal Inequality.** When the *Diurnal Inequality* is large, the differences are tabulated for *Mean Higher High Water* (*MHHW*), *Mean Lower High Water* (*MLHW*), *Mean Higher Low Water* (*MHLW*) and *Mean Lower Low Water* (*MLLW*). *Tide Level* definitions are at Para 1062.

h. **SHM / SHM for Windows® / TotalTide®.** Details of the *Simplified Harmonic Method* (*SHM*) and *SHM for Windows®* software are at Para 1032. Copies of a *UKHO* form to assist users in correctly utilising the *Harmonic Constants*, to compute a tidal prediction by calculator or spreadsheet, are at the back of each volume of Admiralty Tide Tables. For certain *Secondary Ports* (which are annotated accordingly in the Admiralty Tide Tables) no suitable *Standard Port* is available and thus simple time / height differences for these *Secondary Ports* cannot be applied; in such cases predictions must be made with *TotalTide®* or by using *Harmonic Constants* with *SHM / SHM for Windows®*.

i. **Co-Tidal / Co-Range Charts or Atlases.** *Co-Tidal* and *Co-Range* charts or atlases should be used for tidal predictions for offshore areas and coastlines between *Secondary Ports*. See Para 1052 (overleaf).

1051. Admiralty TotalTide® Software

The Admiralty *TotalTide*® software program provides predictions for all ports and *Tidal Stream* data currently available in *UKHO* publications. The accuracy of its predictions has the integrity of the Admiralty Tide Tables, provided the latest software edition is used. *HOTs* for multiple ports may be calculated for up to 7 consecutive days; results may be printed. Outputs include periods of daylight, *Nautical Twilight*, phases of the Moon, *Springs / Neaps* indicators and *Underkeel / Vertical Clearances*. *TotalTide*® runs under MS Windows and may be interfaced to certain *WECDIS / ECDIS* equipments for the display of *HOTs / Tidal Streams*.

1052. Co-Tidal and Co-Range Charts / Atlases

Co-Tidal and *Co-Range* charts / atlases show lines of equal time and *Range* of *Tides* in the open sea (see Figs 10-23a/b below). They are only available for limited areas, but are of great importance to vessels with small *Underkeel Clearances* in those areas. However, as it is difficult to obtain data offshore, interpolation from inshore stations is also used; thus the data on *Co-Tidal* and *Co-Range* charts / atlases must be used with caution.

a. **Amphidromic Points.** At *Amphidromic Point*s the (tidal) *Range* is zero or very small. *Co-Tidal* lines radiate outwards from them, with HW / LW times progressing clockwise or anti-clockwise (see Fig 10-23a below); *Co-Range* lines surround *Amphidromic Point*s (see Fig 10-23b opposite). Near *Amphidromic Point*s, the *Range* of the *Tide* may alter considerably within a short distance.

b. **Co-Tidal Lines.** *Co-Tidal* lines (12h, 11h, 10h etc) are drawn through points of equal *Mean High Water Interval* (*MHWI*). *MHWI* is the mean time interval between the passing of the Moon over the *Meridian* of Greenwich and the time of the next HW at the place concerned. See Fig10-23a (below).

c. **Co-Range Lines.** *Co-Range* lines (5m, 4m, 3m etc) are drawn through positions of equal *MSRs*). See Fig 10-23b (opposite).



MEAN HIGH WATER INTERVAL

Lines of equal Mean High Water Time Interval referred to the time of the Moon's Meridian Passage at Greenwich

Mean High Water Time Interval at Standard Ports

North Shields	03h 01
Immingham	05h 29
Margate	11h 49
Vlissingen	00h 51
Helgoland	10h 35

NOTE
In the area enclosed by the dotted line the tidal curve is very distorted at High Water. There is a tendency for a stand of at least one hour's duration. The predicted times obtained by using the chart for positions in this area will give some point during the period of the stand.

Fig 10-23a. Co-Tidal Chart (Southern North Sea [UK])

(1052c continued)


Esbjerg
North Shields
Newcastle
Amphidromic Point
1m
2m
3m
4m
5m
6m
6h
Helgoland
Immingham
Amphidromic Point
Bremen
Kings Lynn
Lowestoft
MEAN SPRING RANGE
Lines of equal Mean Spring Range in Metres
Mean Spring Range at Standard Ports
North Shields 4.3m
Immingham 6.4m
Margate 4.3m
Vlissingen 4.3m
Helgoland 2.8m
Harwich
Rotterdam
Vlissingen
Chatham
Margate

Fig 10-23b. Co-Range Chart (Southern North Sea [UK])

1053. Scope of the Admiralty Tide Tables

The Admiralty Tide Tables (NPs 201-204) are set out in 4 Volumes and cover the whole world. Information in this paragraph is based on the Admiralty Tide Tables dated 2008.

a. **Standard and Secondary Ports.** The Admiralty Tide Tables cover about 250 *Standard Ports,* nearly 7,000 *Secondary Ports* and 125 *Tidal Stream* systems (see Paras 1030b / 1042e for tidal observation criteria). The authority for the observations, method of prediction and year of observation are stated in each volume.

b. **Content of the Admiralty Tide Tables.** There are slight differences in the content of the 4 volumes to reflect the tidal characteristics of different parts of the world.

- **Part I.** Part I gives daily predictions of the times and heights of HW and LW at a selected number of *Standard Ports*.
- **Part Ia.** Part Ia gives hourly height predictions for a few *Standard Ports* in Vol 1, but, it gives daily predictions of *Tidal Streams* in Vols 3 & 4.
- **Part II.** Part II gives data for prediction at a large number of *Secondary Ports*, as height and time differences from a *Standard Port*.
- **Part III.** Part III lists *Harmonic Constants* for use with *SHM* predictions.
- **Part IIIa.** Part IIIa lists *Harmonic Constants* for *Tidal Stream* prediction in Vols 2, 3 and 4.
- **Tables.** Up to 8 Supplementary Tables are included in each Volume.

1054-1059. Spare

SECTION 6 - LEVELS AND DATUMS

1060. Tidal Levels

a. **Tidal Levels for Standard and Secondary Ports.** A list of *Tidal Levels* for *Standard Ports* is given at Supplementary Table V in the Admiralty Tide Tables (NP 201-204); *Tidal Levels* (*Vertical Datums*) for a large number of *Secondary Ports* are at Part II of the Admiralty Tide Tables.

b. **Tidal Levels for Tidal Prediction.** The *Tidal Level* for tidal predictions must be the same as *Chart Datum* (see Para 1062c), to ensure that the depth of water is equal to the charted depth plus the *HOT*. *Tidal Levels* established at *Standard Ports* vary widely; they do not conform to any uniform standard. Modern charting practice is to establish *Tidal Levels* at or near the level of *Lowest Astronomical Tide* (*LAT*), but when planning passages, the *Tidal Levels* printed on the chart and in Supplementary Table V in the Admiralty Tide Tables should be checked for agreement. Where the *UKHO* is the surveying authority, *Tidal Level*s have been adjusted to approximate to *LAT*.

c. **Mean Sea Level (MSL).** *Tidal Levels* for *Standard Ports* do not necessarily remain constant, due to changes in *Mean Sea Level (MSL)*; a number of *MSLs* have risen by 0.1 metres over the past 40 years. In addition, regular *Seasonal Variations* can occur to *MSL*, due either to established meteorological patterns (barometric pressure, wind strength and direction), or the effect of river water (ports with a temperate climate).

d. **Allowance for Seasonal Variations in Mean Sea Level (MSL).** Regular *Seasonal Variations* in *MSL* greater than 0.1 metres are tabulated in the HW and LW predictions for *Standard Ports* in Part II of the Admiralty Tide Tables. See Para 1050d for details of calculations necessary to allow for *Seasonal Variations* in *MSL.*

1061. Chart Datum and Land Survey Datums

Tidal Levels are referred to *Chart Datum* (see Para 1062c) of the largest *Scale* Admiralty chart. A variety of '*Land Survey Datums*' are in use worldwide; in UK, *Ordnance Datum* is used for this purpose.

a. **Tide Tables.** The connection between *Chart Datum* and *Ordnance Datum* in UK is given at Supplementary Table III. Where known, the equivalent information for other *Tidal Levels* outside UK is given at Supplementary Table IV.

b. **Charts.** On large and medium *Scale* charts for which *UKHO* is the primary authority, the panel giving tidal height may also tabulate the difference between *Chart Datum* and *Ordnance Datum* for the area.

c. **Lack of Data.** If absolute heights are required at a point on the coast where no tidal data is given, or where there is no connection to the *Land Survey Datum*, they may be obtained by interpolation from heights obtained from places on either side where data is available.

1062. Tidal Levels and Heights - Definitions

Definitions of *Tidal Levels* and heights are defined below and overleaf, and are shown diagrammatically at Fig 10-24 (below).


Bridge
Overhead Power Cables
Structure Height
Bench Mark
Charted Elevation
Charted Height
Vertical Clearance
Safe Vertical Electrical Discharge Clearance
Vertical Clearance
HAT
HAT
MHWS / MHHW
MHWS / MHHW
MHWN / MLHW
Sea Level at any time
MSL
MSL
Land Survey Datum (Ordnance Datum in UK)
MNR
MSR
HOT
Soundings
Drying Height
MLWN / MHLW
MLWS / MLLW
CHART DATUM
CHART DATUM
(usually approximating to LAT)
(usually approximating to LAT)
Charted Depth

Fig 10-24. Tidal Levels and Heights (*not to scale*)

a. **Heights.** Except for *Vertical Clearances*, heights on Admiralty charts are given above *MHWS* in areas where the *Tides* are *Semi-Diurnal* and *MHHW* where there is a *Diurnal Inequality*. *Mean Sea Level* (*MSL*) is used where there is negligible *Tide*.

b. **Vertical Clearances.** Since 2004, *Vertical Clearances* have been quoted above *Highest Astronomical Tide* (*HAT*) in all areas where there is an appreciable (tidal) *Range*. *MSL* is still used where there is negligible *Tide*. The '**Heights**' statement beneath the title of each information panel makes it quite clear which *Vertical Datum* (*HAT, MHWS* or *MSL*) is being used for *Vertical Clearances* on that particular chart. Where a 'Safe' *Vertical Clearance* has been obtained to avoid the risk of electrical discharge from overhead power cables, it is shown on charts in magenta; however the deduction used may vary with changes in transmission voltage and should be used with caution.

c. **Chart Datum.** By international agreement, *Chart Datum* is defined as a level so low that the *Tide* will not frequently fall below it. In areas for which *UKHO* is the authority, *Chart Datum* is the approximate level of *Lowest Astronomical Tide* (*LAT*).

d. **Variation in Values.** The average values of *MHWS, MHWN, MLWS, MLWN, MHHW, MLHW, MHLW* and *MLLW* (see definitions at Para 1062e overleaf) vary from year to year in a cycle of approximately 18.6 years (the 'Metonic Cycle'). *Tidal Levels* shown in Supplementary Table V of the Admiralty Tide Tables are average values over the whole cycle.

(1062) e. **Tidal Levels.** *Tidal Levels* are referred to *Chart Datum* (see Para 1062c - previous page). *MSR / MNR* are defined at Para 1045a. Definitions of other *Tidal Levels* are:

- **Highest Astronomical Tide (HAT) and Lowest Astronomical Tide (LAT).** *Highest* and *Lowest Astronomical Tides* (*HAT* and *LAT*) are the highest and lowest levels respectively which can be predicted to occur under average meteorological considerations and any combination of astronomical conditions. *HAT* and *LAT* are not the extreme levels which can be reached; *Storm Surges* (see Para 1022) may cause considerably higher and lower levels to occur.

- **Mean High Water Springs (MHWS).** The height of *Mean High Water Springs* (*MHWS*) is the average throughout a year when the average maximum *Declination* of the Moon is 23½°, of the heights of two successive HWs during those periods of 24 hours (approximately every fortnight) when the *Range* of the *Tide* is greatest.

- **Mean Low Water Springs (MLWS).** The height of *Mean Low Water Springs* (*MLWS*) is the average height obtained from two successive LWs during the same period as *MHWS.*

- **Mean High Water Neaps (MHWN).** *Mean High Water Neaps* (*MHWN*) is the average throughout a year, as defined for *MHWS,* of the heights of two successive HWs during those periods (approximately every fortnight) when the *Range* of the *Tide* is least.

- **Mean Low Water Neaps (MLWN).** *Mean Low Water Neaps* (*MLWN*) is the is the average height obtained from two successive LWs during the same period as *MHWN.*

- **Mean Tide Level (MTL).** *Mean Tide Level* (*MTL*) is the mean of the heights of *MHWS, MHMW, MLWS* and *MLWN.*

- **Mean Sea Level (MSL).** *Mean Sea Level* (*MSL*) is the average level of the sea surface over a long period, preferably 18.6 years, or the average level which would exist in the absence of *Tides.*

- **Mean Higher High Water (MHHW).** *Mean Higher High Water* (*MHHW*) is the mean of the higher of the two daily HWs over a long period of time. When only one HW occurs in a day, this is taken as the higher HW.

- **Mean Lower High Water (MLHW).** *Mean Lower High Water* (*MLHW*) is the mean of the lower of the two daily HWs over a long period of time. When only one HW occurs on some days, ▵ is printed in the *MLHW* column of the Admiralty Tide Tables to indicate that the *Tide* is usually *Diurnal.*

- **Mean Higher Low Water (MHLW).** *Mean Higher Low Water* (*MHLW*) is the mean of the higher of the two daily LWs over a long period of time. When only one LW occurs on some days, ▵ is printed in the *MHLW* column of the Admiralty Tide Tables to indicate that the *Tide* is usually *Diurnal.*

- **Mean Lower Low Water (MLLW).** *Mean Lower Low Water* (*MLLW*) is the mean of the lower of the two daily LWs over a long period of time. When only one LW occurs on a day, this is taken as the lower LW.

APPENDIX 1

PLANE TRIGONOMETRY

1. Scope of Appendix

Trigonometry is the branch of mathematics dealing with the relations between the angles and sides of a triangle and with the relevant functions of any angles. Appendix 1 contains the following information:

- **Para 2: Units - The Degree, Radian and π**
- **Para 3: Trigonometric Functions 0˚ to 90˚ - Sin, Cos and Tan**
- **Para 4: Trigonometric Functions 0˚ to 360˚ - Sin, Cos and Tan**
- **Para 5: Sin & Cos Curves -180˚ to 540˚ and Tan Curves -180˚ to 270˚**
- **Para 6: Inverse Trigonometric Functions - Sin, Cos and Tan**
- **Para 7: Pythagorean Relationships between Trigonometric Functions**
- **Para 8: Non-Right Angled Triangles - Sine, Cosine and Area Formulae**
- **Para 9: Functions of Sum and Difference of Two Angles**
- **Para 10: Sine and Cosine of Small Angles**

2. Units - The Degree, Radian and π

a. **The Degree.** The angle between two intersecting lines is the inclination of one line to the other, and this inclination is commonly measured in ‘degrees’ and sub-divisions of a degree. In one complete revolution there are 360 degrees; when the two arms of the angle are perpendicular, the angle is said to be a ‘right angle’, in which there are 90 degrees (see Fig A1-1 below). The sub-divisions of the degree are the ‘minute’ and ‘second’, the relation between them is:

1˚ = 60 minutes (′)
1' = 60 seconds (″)

In navigation, angles are measured clockwise from North (000˚), through East (090˚), South (180˚) and West (270˚) to North (see Fig A1-1 below).



Fig A1-1. Degrees in a Right Angle and in One Revolution

(2) b. **The Radian and π.** The 'Radian' is defined as the angle subtended at the centre of a circle by a length of arc equal to the radius (see Para 0127). 'π' is defined as the ratio of the circumference of a circle to its diameter; this ratio is constant in all cases and π is approximately equal to 3.1415927 (see Para 0127). From this it follows that:

- **Radians to Degrees.** The angle subtended by an arc equal to the radius is also constant and equal to 360˚ ÷ 2π, or approximately 57˚ 17' 45".
- **Radians in a Right Angle.** The number of radians in a right angle is ½π.
- **Length of any Arc of a Circle.** The length of any arc of a circle is equal to the radius multiplied by the angle in radians.

3. Trigonometric Functions 0˚ to 90˚ - Sin, Cos and Tan

a. **The Right-Angled Triangle.** In Fig A1-2 (opposite), the *Plane Triangle ABC* is right-angled at *C*; the sides *BC, CA* and *AB* are of length *a, b* and *c* respectively; and the angle *CAB* is of size θ. For navigational convenience *AC* is taken as due north so that the (true) bearing of *B* from *A* is θ.

b. **The Six Trigonometric Functions of a Right-Angled Triangle.** There are six trigonometric functions of a right-angled *Plane Triangle*. Two of these, the sine and cosine, are of fundamental importance while the other 4, tangent, cotangent, secant and cosecant are derived from them. The six functions are defined and abbreviated thus:

$$\sin\,\theta = \frac{\text{side opposite the angle}}{\text{hypotenuse}} = \frac{a}{c} \qquad \ldots \textbf{A1.1}$$

$$\cos\,\theta = \frac{\text{side adjacent to the angle}}{\text{hypotenuse}} = \frac{b}{c} \qquad \ldots \textbf{A1.2}$$

$$\tan\,\theta = \frac{\text{side opposite}}{\text{side adjacent}} = \frac{a}{b} = \frac{a}{c} \times \frac{c}{b} = \frac{\sin\,\theta}{\cos\,\theta} \qquad \ldots \textbf{A1.3}$$

$$\cot\theta = \frac{b}{a} = \frac{1}{\tan\theta} = \frac{\cos\theta}{\sin\theta} \qquad \ldots \textbf{A1.4}$$

$$\sec\,\theta = \frac{c}{b} = \frac{1}{\cos\,\theta} \qquad \ldots \textbf{A1.5}$$

$$\operatorname{cosec}\,\theta = \frac{c}{a} = \frac{1}{\sin\,\theta} \qquad \ldots \textbf{A1.6}$$

The last four trigonometric functions are defined in terms of sine and/or cosine. The last three functions are reciprocals of the first three.

In Fig A1-2, where angle *BCA* is 90˚ and angle *CAB* equals θ,

$a = c \sin\,\theta$
$b = c \cos\,\theta$

Thus, if *AC* points North, *B* is both '$c \sin\,\theta$' East of *A* and '$c \cos\,\theta$' North of *A*.



Fig A1-2. The Right-Angled Triangle



Fig A1-3. Complimentary Angles

(3) c. **Complementary Angles.** Angles that add together to make 90˚ are said to be 'complementary'. Thus, if one angle is 34˚, its complementary angle is 56˚. In any right-angled triangle the two acute angles are complementary, since the sum of the three angles, of which one is 90˚, must be 180˚. It can also be shown from Fig A1-3 that:

$$\sin\theta = \frac{a}{c} = \cos(90^\circ - \theta) \qquad (eg\ \sin 34^\circ = \cos 56^\circ) \qquad \ldots\ \mathbf{A1.7}$$

$$\cos\theta = \frac{b}{c} = \sin(90^\circ - \theta) \qquad (eg\ \cos 34^\circ = \sin 56^\circ) \qquad \ldots\ \mathbf{A1.8}$$

$$\tan\theta = \frac{a}{b} = \cot(90^\circ - \theta) \qquad (eg\ \tan 34^\circ = \cot 56^\circ) \qquad \ldots\ \mathbf{A1.9}$$

d. **Trigonometric Functions of Specific Angles.** Fig A1-4 and Table A1-1 show the relationship between the trigonometric functions of specific angles and the length of sides of right-angled triangles.



Fig A1-4. Trigonometric Functions of Specific Angles

Table A1-1. Trigonometric Functions of Specific Angles

θ	0˚	30˚	45˚	60˚	90˚
sin θ	0	0.5	$\frac{1}{\sqrt{2}} \simeq 0.707$	$\frac{\sqrt{3}}{2} \simeq 0.866$	1
cos θ	1	$\frac{\sqrt{3}}{2} \simeq 0.866$	$\frac{1}{\sqrt{2}} \simeq 0.707$	0.5	0
tan θ	0	$\frac{1}{\sqrt{3}} \simeq 0.577$	1	$\sqrt{3} \simeq 1.732$	∞

4. Signs and Values of the Trigonometric Functions Between 000˚ and 360˚. The definitions at formulae (A1.1 to A1.6) of the six trigonometric functions for acute angles may be extended to angles up to 360˚.

a. **Sign Conventions between 000˚ and 360˚.** Bearing and direction are measured clockwise from 000˚ to 360˚. In can be shown from Fig A1-5 (below) that Northerly and Easterly directions may be considered as +ve, while Southerly and Westerly are −ve . South may be said to be the equivalent of negative North and west the equivalent of negative East. Tangent, cotangent, secant and cosecant may be defined in terms of sine and/or cosine (see Para 3b).

b. **Signs of Trigonometric Functions - The Four Quadrants.** Bearing and direction 000˚ to 360˚ may be divided into 4 quadrants (see Fig A1-5 below) for the purposes of establishing the signs of functions.



Fig A1-5. Signs of Trigonometric Functions - The Four Quadrants

- **Explanation of Fig A1-5.** B_1 is in the '1st Quadrant', at a distance r and on a bearing θ_1 from A, where θ_1 equals angle θ; B_1 is $r \sin \theta$ East of A and $r \cos \theta$ North of A. Equivalent points B_2, B_3, and B_4 are in the 2nd, 3rd and 4th quadrants.
- **Example - 3rd Quadrant.** In Fig A1-5 (above), B_3 is South and West of A at a distance r on a bearing θ_3 (equal to angle 180˚ + θ). Thus:

$$\sin\,\theta_3\ (\sin\,[180°+\theta]) = \frac{-\,r\,\sin\,\theta}{r} = -\sin\,\theta$$

$$\cos\,\theta_3\ (\cos\,[180°+\theta]) = \frac{-\,r\cos\theta}{r} = -\cos\,\theta$$

$$\tan\,\theta_3 \quad = \quad \frac{\sin\theta_3}{\cos\theta_3} \quad = \frac{-\,\sin\theta}{-\,\cos\theta} \quad = \frac{\sin\theta}{\cos\theta} = \tan\theta$$

In summary, B_3 is $r \sin \theta$ West of A, which is thus equivalent to $-r \sin \theta$. B_3 is also $r \cos \theta$ South of A, and thus equivalent to $-r \cos \theta$.

(4) c. **Signs in Each Quadrant.** Reciprocals of sine, cosine and tangent (ie cosecant, secant and cotangent respectively) take the same sign as their original function. From Fig A1-5 (opposite) it may be shown that:

- **1st Quadrant.** Bearings between 000° and 090° lie between North (+ve) and East (+ve). For direction θ_1, sine, cosine and tangent are all +ve.
- **2nd Quadrant.** Bearings between 090° and 180° lie between East (+ve) and South (−ve). For direction θ_2, sine is (+ve), cosine and tangent are (−ve).
- **3rd Quadrant.** Bearings between 180° and 270° lie between South (−ve) and West (−ve). For direction θ_3, tangent is (+ve), sine and cosine are (−ve).
- **4th Quadrant.** Bearings between 270° and 360° lie between West (-ve) and North (+ve). For direction θ_4, cosine is (+ve), sine and tangent are (−ve).

d. **Summary of Signs and Mnemonic "All Stations To Crewe".** The signs of sine, cosine and tangent (plus their reciprocals, which take the same sign as their original functions) are summarised at Fig A1-5a (below) for the four quadrants. The mnemonic ***"All Stations To Crewe"*** provides a reminder of the signs of the trigonometric functions.


000°
(C) Cosine is positive
Sine & tangent are negative, reciprocals follow originals.
(A) All functions are positive
270°
090°
(T) Tangent is positive
Sine & cosine are negative, reciprocals follow originals.
(S) Sine is positive
Cosine & tangent are negative, reciprocals follow originals.
180°

Fig A1-5a. Summary of Signs of Trigonometric Functions 000° to 360°

e. **Values of Trigonometric Functions.** The value (as distinct from the sign) of any trigonometric function of an angle greater than 90° is equal to the value of the trigonometric function of the angle made with the North−South axis. For example, the value of sin 127° equals sin 53° (180° − 127°), while the value of cosine 296° equals cosine 64° (360° − 296°). The angle (180° − θ) is known as the 'Supplement' of θ. 'Supplementary Angles' add together to 180°. The signs and values of the trigonometric functions of angles in each quadrant are summarised in Table A1-2 (below). See also examples at Fig A1-6 / Table A1-3 (overleaf).

Table A1-2. Values of Trigonometric Functions

Direction	Angle	Sine Angle	Cosine Angle	Tangent Angle
θ_1	θ	$\sin\theta$	$\cos\theta$	$\tan\theta$
θ_2	$180^\circ-\theta$	$\sin(180^\circ-\theta)$ $=\sin\theta$	$\cos(180^\circ-\theta)$ $=-\cos\theta$	$\tan(180^\circ-\theta)$ $=-\tan\theta$
θ_3	$180^\circ+\theta$	$\sin(180^\circ+\theta)$ $=-\sin\theta$	$\cos(180^\circ+\theta)$ $=-\cos\theta$	$\tan(180^\circ+\theta)$ $=\tan\theta$
θ_4	$360^\circ-\theta$ $(=-\theta)$	$\sin(360^\circ-\theta)$ $=-\sin\theta$ $=\sin(-\theta)$	$\cos(360^\circ-\theta)$ $=\cos\theta$ $=\cos(-\theta)$	$\tan(360^\circ-\theta)$ $=-\tan\theta$

(4) f. **Examples of Values of Trigonometric Functions.** The signs and values of the trigonometric functions of some (example) angles in each quadrant are and demonstrated at Fig A1-6 / Table A1-3 (below).



Fig A1-6. Examples of Signs and Values of Trigonometric Functions 000˚ to 360˚

Table A1-3. Examples of Signs and Values of Trigonometric Functions 000˚ to 360˚

Angle	**Sign**	**Cosine**	**Tangent**
106˚	+ sin 74˚	- cos 74˚	- tan 74˚
233˚	- sin 53˚	- cos 53˚	+ tan 53˚
341˚	- sin 19˚	+ cos 19˚	- tan 19˚

5. Sin & Cos Curves -180˚ to 540˚ and Tan Curves -180˚ to 270˚

a. **Angles Greater than 360.** Although, in navigation, angles outside the range 0˚ to 360˚ are rarely encountered, the definitions given earlier may be extended to angles greater than 360˚. The value 360˚ (or multiples of 360˚) may be subtracted from the angle concerned to reduce it to an angle between 0˚ and 360˚.

b. **Negative Angles.** Negative angles may be taken as angles measured anti-clockwise from North and brought to an angle between 0˚ and 360˚ by the addition of 360˚ (or multiples of 360˚).

c. **Sin, Cos and Tan Curves.** The graphs of sin θ, cos θ and tan θ may be deduced for any given range. Fig A1-7 (opposite) shows the graphs of sin θ and cos θ between −180˚ and +540˚, and the graph of tan θ between −180˚ and +270˚. The following points should be noted:

- Both sin θ and cos θ repeat every 360˚.
- Tan θ repeats every 180˚.
- In any 360˚, there are two angles which have the same value for any trigonometric function:
  (eg sin 35˚ = sin 145˚, cos 134˚ = cos 226˚, tan 213˚ = tan 33˚, etc).

(5c continued)



Fig A1-7. Sin & Cos Curves 0˚ to 540˚ and Tan Curves 0˚ to 270˚

6. Inverse Trigonometric Functions - Sin, Cos and Tan

a. **Principal Values.** As there are two angles in any 360˚ which have the same value for any trigonometric function, it follows that the inverse function has more than one value. However, a calculator / spreadsheet can only give what is called the 'Principal Value' of the inverse trigonometric function. The principal value ranges for sine, cosine and tangent are:

$\sin^{-1}$: $-90^\circ \leq \theta \leq 90^\circ$
$\cos^{-1}$: $0^\circ \leq \theta \leq 180^\circ$
$\tan^{-1}$: $-90^\circ < \theta < 90^\circ$

b. **Selection of Appropriate Value.** The principal value may not be the one required in a particular problem, and the graph of the appropriate trigonometric function should be used to determine other values. For example:

$\sin^{-1} +0.5 = 30^\circ$ (the angle could be 030˚ or 150˚.)
$\sin^{-1} -0.5 = -30^\circ$ (the angle could be 210˚ or 330˚.)
$\cos^{-1} +0.866 \simeq 30^\circ$ (the angle could be 030˚ or 330˚.)
$\cos^{-1} -0.866 \simeq 150^\circ$ (the angle could be 150˚ or 210˚.)
$\tan^{-1} +0.577 \simeq 30^\circ$ (the angle could be 030˚ or 210˚.)
$\tan^{-1} -0.577 \simeq -30^\circ$ (the angle could be 150˚ or 330˚.)

(6) c. **Assessment of Appropriate Value by Inspection and/or Comparison.** When assessing values of trigonometric functions, care must be taken to ensure that, if necessary, the displayed angle reading is adjusted to the correct value.

- **Inspection.** Assessment may often be achieved by inspection. For example, if a bearing θ is such that tan $\theta \simeq -0.577$, but it is also known that the bearing is in the 4th (North-West) quadrant, then the angle required must be 330° (and not 150°, nor the −30° given by a calculator).
- **Comparison.** The two trigonometric functions corresponding to the displayed value may also be compared. For example, if the sine of the displayed value is −ve, while the cosine is also −ve, the angle corresponding to both values can only be in the 3rd (South-West) quadrant, where sine and cosine are both negative.

7. Pythagorean Relationships between Trigonometric Functions

By the theorem of Pythagoras, the square on the hypotenuse of a right-angled triangle is equal to the sum of the squares on the other two sides. Using the notation from Fig A1-3:

$$a^2 + b^2 = c^2$$

thus:

$$\frac{a^2}{c^2} + \frac{b^2}{c^2} = 1$$

or

$$\sin^2\theta + \cos^2\theta = 1 \qquad \ldots \textbf{A1.10}$$

Further division by $\cos^2\theta$ gives:

$$\tan^2\theta + 1 = \sec^2\theta \qquad \ldots \textbf{A1.11}$$

or, if (**A1.10**) is divided by $\sin^2\theta$:

$$1 + \cot^2\theta = \mathrm{cosec}^2\,\theta \qquad \ldots \textbf{A1.12}$$

Formulae (A1.10 to A1.12) hold for all values of θ, because the square of any quantity is always positive, although the quantity itself may be negative.

8. Non-Right Angled Triangles - Sine, Cosine and Area Formulae

a. **Non-Right Angled Triangles.** There are several formulae connecting the sides and angles of acute and obtuse triangles (Fig A1-8) and the choice of formula is governed, as a rule, by the data available and the requirements of the problem to be solved.



Fig A1-8. Non-Right Angled Acute and Obtuse Triangles ABC

b. **The Sine Formula.** The *Sine Formula* is established by dropping a perpendicular from any vertex on to the opposite side (see Fig A1-8 above). In Fig A1-8, the perpendicular is *CD*, denoted by 'p'. Then:

$$\sin A = \frac{p}{b}$$

also $$\frac{p}{a} = \sin B \text{ (acute triangle) or } \sin(180^\circ - B)\text{(obtuse triangle)} = \sin B$$

ie $$p = b \sin A \quad \text{and} \quad p = a \sin B$$

$$\therefore \; b \sin A = a \sin B$$

or $$\frac{a}{\sin A} = \frac{b}{\sin B}$$

Similarly, if a perpendicular is dropped from *A* to *BC*, or *BC* produced:

$$\frac{b}{\sin B} = \frac{c}{\sin C}$$

Hence $$\frac{a}{\sin A} = \frac{b}{\sin B} = \frac{c}{\sin C} \qquad \text{. . . } \mathbf{A1.13}$$

- **Summary.** Thus, in a triangle, if two angles *A* and *B* and one side are given, by simple arithmetic the third angle is 180° − (*A* + *B*); the *Sine Formula* may be used to calculate the remaining sides.

(8) c. **Ambiguity in the Sine Formula.** Ambiguity arises if the *Sine Formula* is used for solving the triangle when two sides and an angle other than the included angle are given, when the given angle is opposite the smaller side (see Fig A1-9 below). If, in Fig A1-10, the sides b and c and the angle C are given, the angle found from the formula is either ABC or its supplement AB_1C, because the sine of an angle is equal to the sine of its supplement.



Fig A1-9. Ambiguity in the Sine Formula

d. **The Cosine Formula.** The *Cosine Formula* is established by applying the theorem of Pythagoras to the right-angled triangles ADC and BDC in Fig A1-8. Thus:

$$\begin{aligned} a^2 &= p^2 + BD^2 \\ \mathrm{b}^2 &= \mathrm{p}^2 + AD^2 \\ \therefore a^2 &= (b^2 - AD^2) + BD^2 \\ &= b^2 - AD^2 + (c - AD)^2 \\ &= b^2 - AD^2 + c^2 - 2cAD + AD^2 \\ &= b^2 + c^2 - 2cAD \\ &= b^2 + c^2 - 2bc\cos A \qquad \ldots \textbf{A1.14} \end{aligned}$$

In the same way it can be established that:

$$\begin{aligned} b^2 &= c^2 + a^2 - 2ca\cos B \qquad \ldots \textbf{A1.15} \\ c^2 &= a^2 + b^2 - 2ab\cos C \qquad \ldots \textbf{A1.16} \end{aligned}$$

- **Negative Cosines.** The *Cosine Formula* is true for any triangle, but if the angle A, B or C is greater than 90˚, the angle lies in the 2nd quadrant and its cosine is negative.

- **Summary.** Thus, in a triangle, the *Cosine Formula* gives the third side when two sides and the included angle are known, or any angle when the three sides are known.

e. **Area of a Triangle.** The area of a triangle is equal to half the base multiplied by the perpendicular height. The area of the triangle ABC (see Fig A1-8, previous page) may also be found by transposing this value using the *Sine Formula* to give:

$$\begin{aligned} \text{Area} &= \tfrac{1}{2} ab\sin C \qquad \ldots \textbf{A1.17} \\ \text{Area} &= \tfrac{1}{2} bc\sin A \qquad \ldots \textbf{A1.18} \\ \text{Area} &= \tfrac{1}{2} ca\sin B \qquad \ldots \textbf{A1.19} \end{aligned}$$

9. Functions of Sum and Difference of Two Angles

a. **Trigonometric Functions of Combined Angles.** The trigonometric functions of combined angles may be determined. For example, the sine, cosine and tangent of the angles *A* + *B* in Fig A1-10 (below) may be found as follows:



Fig A1-10. Trigonometric Functions of Combined Angles.

In Fig A1-10 (above), triangle PQR is right-angled at *R*. The line *QS* divides the angle *Q* into the angles *A* and *B*. *PS* is a perpendicular from *P* to *QS* and *SV* is a perpendicular from *S* to *QV*. *ST* is the perpendicular from *S* to *PT*. The angle *SPT* equals the angle *B*.

Thus:

$$\begin{aligned} r\sin(A+B) &= PR = PT + TR = PS\cos B + SV \\ &= r\sin A\cos B + QS\sin B \\ &= r\sin A\cos B + r\cos A\sin B \\ \therefore \sin(A+B) &= \sin A\cos B + \cos A\sin B \end{aligned} \qquad \text{. . . A1.20}$$

and:

$$\begin{aligned} r\cos(A+B) &= QR = QV - RV = QS\cos B - TS \\ &= r\cos A\cos B - PS\sin B \\ &= r\cos A\cos B - r\sin A\sin B \\ \therefore \cos(A+B) &= \cos A\cos B - \sin A\sin B \end{aligned} \qquad \text{. . . A1.21}$$

and:

$$\tan(A+B) = \frac{\sin(A+B)}{\cos(A+B)}$$

Dividing top and bottom by (cos *A* cos *B*):

$$\tan(A+B) = \frac{\tan A + \tan B}{1 - \tan A \tan B} \qquad \text{. . . A1.22}$$

Sin (A − B), cos (A − B) and *tan (A − B)* may be found from formulae A1.20 to A.122, as *sin (−B) = −sin B, cos (−B) = cos B* and *tan (−B) = −tan B*, and substituting these values.

Thus:

$$\sin(A-B) = \sin A\cos B - \cos A\sin B \qquad \text{. . . A1.23}$$

$$\cos(A-B) = \cos A\cos B + \sin A\sin B \qquad \text{. . . A1.24}$$

$$\tan(A-B) = \frac{\tan A - \tan B}{1 + \tan A \tan B} \qquad \text{. . . A1.25}$$

(9) b. **Double and Half-Angle Formulae.** If *A* is equal to *B*, it follows from formulae A1.20 to A1.22, that:

$$\sin 2A = 2 \sin A \cos A \qquad \text{. . . }\mathbf{A1.26}$$

$$\begin{aligned}\cos 2A &= \cos^2 A - \sin^2 A \qquad \text{. . . }\mathbf{A1.27}\\ &= 1 - 2\sin^2 A\\ &= 2\cos^2 A - 1\end{aligned}$$

$$\tan 2A = \frac{2 \tan A}{1 - \tan^2 A} \qquad \text{. . . }\mathbf{A1.28}$$

In terms of the half-angle these formulae become:

$$\sin A = 2 \sin \tfrac{1}{2}A \cos \tfrac{1}{2}A \qquad \text{. . . }\mathbf{A1.29}$$

$$\begin{aligned}\cos A &= \cos^2 \tfrac{1}{2}A - \sin^2 \tfrac{1}{2}A \qquad \text{. . . }\mathbf{A1.30}\\ &= 1 - 2\sin^2 \tfrac{1}{2}A\\ &= 2\cos^2 \tfrac{1}{2} A - 1\end{aligned}$$

$$\tan A = \frac{2 \tan \tfrac{1}{2}A}{1 - \tan^2 \tfrac{1}{2}A} \qquad \text{. . . }\mathbf{A1.31}$$

c. **Sum and Difference of Functions.** The above formulae, relating to the sines and cosines of sums and differences, may be combined to give other formulae which relate to the sums and differences of sines and cosines.

- **Adding Formulae (A1.20) and (A1.23).** By adding formulae (A1.20) and (A1.23), and writing *P* for (*A* + *B*) and *Q* for (*A* − *B*) so that *A* is equal to ½(*P* + *Q*) and *B* to ½(*P* − *Q*):

$$\begin{aligned}\sin (A + B) + \sin (A - B) &= 2 \sin A \cos B\\ \sin P + \sin Q &= 2 \sin \tfrac{1}{2}(P + Q) \cos \tfrac{1}{2}(P - Q) \qquad \text{. . . }\mathbf{A1.32}\end{aligned}$$

- **Subtracting Formula (A1.23) from Formula (A1.20).** By subtracting formula (A1.23) from formula (A.1.20):

$$\begin{aligned}\sin (A + B) - \sin (A - B) &= 2 \cos A \sin B\\ \sin P - \sin Q &= 2 \cos \tfrac{1}{2}(P + Q) \sin \tfrac{1}{2}(P - Q) \qquad \text{. . . }\mathbf{A1.33}\end{aligned}$$

- **Use of Formulae (A1.21) and (A1.24).** By using formulae (A1.21) and (A1.24), it can be shown that:

$$\cos P + \cos Q = 2 \cos \tfrac{1}{2}(P + Q) \cos \tfrac{1}{2}(P - Q) \qquad \text{. . . }\mathbf{A1.34}$$

$$\cos P - \cos Q = -2 \sin \tfrac{1}{2}(P + Q) \sin \tfrac{1}{2}(P - Q) \qquad \text{. . . }\mathbf{A1.35}$$

10. Sine and Cosine of Small Angles

Certain approximations are possible in the sine and cosine of angles, provided the angle is small.

a. **Sine of Small Angles.** In Fig A1-11 (below), *AOB* is a small angle θ, measured in radians. *AB* is the arc of a circle which subtends this small angle. The radius of a circle is *r*, and *BC* is perpendicular to *OA* at *C*. The length of arc of a circle is equal to the radius multiplied by the angle subtended in radians (see Appendix 1, Para 2b). Thus:

$$AB = r \times \theta$$

or

$$\theta = \frac{AB}{r}$$

but

$$\sin\theta = \frac{BC}{r}$$

Therefore, when θ is sufficiently small for *AB* to approximate to *BC*:

$$\sin\theta = \theta$$



Fig A1-11. The Sine of a Small Angle

If there are *x* minutes in this small angle of θ radians, then there must be $\frac{x}{\theta}$ minutes in 1 radian. But 1 radian is equal to $\frac{360°}{2\pi}$ or 3437.7468 minutes of arc.

hence

$$\frac{x}{\theta} = 3437'.7468$$

or

$$\theta = \frac{x}{3437'.7468}$$

The relation sin $\theta = \theta$ therefore becomes:

$$\sin x' = \frac{x}{3437'.7468}$$

Since this relation holds for any value of *x* that is small:

$$\sin 1' = \frac{1}{3437'.7468}$$

$$\therefore \quad \sin x' = x \sin 1' \qquad \text{. . . A1.36}$$

(10) b. **Cosine of a Small Angles.** In Fig A1-12 (below), when θ is small, *OC* approximates to *OA*, which is the same as *OB*.

But: $\cos\theta = \dfrac{OC}{OB}$

Therefore, when θ is small, $\cos\theta$ is equal to 1.



Fig A1-12. The Cosine of a Small Angle

A second approximation can be obtained if $\cos\theta$ is expressed in terms of the half-angle (in radians), for then:

$$\cos\theta = 1 - 2\sin^2 \tfrac{1}{2}\theta$$

$$\cos\theta = 1 - 2(\tfrac{1}{2}\theta)^2$$

$$\therefore \quad \cos\theta = 1 - \tfrac{1}{2}\theta^2 \qquad \text{. . . A1.37}$$

APPENDIX 2

SPHERICAL TRIGONOMETRY

1. Scope of Appendix

Trigonometry is the branch of mathematics dealing with the relations between the angles and sides of a triangle and with the relevant functions of any angles. Appendix 2 contains the following information:

- **Para 2: Spherical Trigonometry Definitions**
- **Para 3: Properties of a Spherical Triangle**
- **Para 4: The Solution of a Spherical Triangle**
- **Para 5: The Cosine Formula**
- **Para 6: The Sine Formula**
- **Para 7: Polar Spherical Triangles and the Polar Cosine Rule**
- **Para 8: The Four-Part Formula**
- **Para 9: Right-Angled Spherical Triangles**
- **Para 10: Napier's Mnemonic Rules for Right-Angled Spherical Triangles**
- **Para 11: Quadrantal Spherical Triangles**
- **Para 12: The Versine and Haversine**
- **Para 13: The Haversine Formula**
- **Para 14: The Half-Log Haversine Formula**
- **Para 15: Haversine / Half Log Haversine Solution - Example**

2. Spherical Trigonometry Definitions

a. **Spherical Trigonometry**. Spherical trigonometry is the science of trigonometry (see Appendix 1) when applied to triangles marked on the surface of a *Sphere* by planes through its centre.

b. **Axis (of the Earth).** The Earth's *Axis* is its shortest diameter (*PP*'), about which it rotates in space (defined at Para 0110c).

c. **Sphere.** A *Sphere* is defined as a surface, every point on which is equidistant from one and the same point, called the 'centre'. The distance of the surface from the centre is called the 'radius' of the *Sphere*.

d. **Great Circle.** A *Great Circle* is the intersection of a *Spherical* surface and a plane which passes through the centre of the *Sphere*. It is the shortest distance between two points on the surface of a *Sphere* (defined at Para 0110c).

e. **Small Circle.** A *Small Circle* is the intersection of a *Spherical* surface and a plane which does NOT pass through the centre of the *Sphere* (defined at Para 0110c).

f. **Spherical Triangle.** Any three-sided figure *ABC* in Fig A2-1 (overleaf), formed by the minor arcs of three *Great Circle*s on the *Spherical* surface is known as a *Spherical Triangle.* The side of a *Spherical Triangle* is the angle it subtends at the centre of the *Sphere* and may be measured in degrees and minutes, or radians. In Fig A2-1, *ABC* is a *Spherical Triangle* formed by the minor arcs of three *Great Circle*s, *AB*, *AC* and *BC*. The length *a* of the side *BC* is equal to the angle subtended at the centre of the *Sphere*, that is, *BOC*. Similarly, *b* and *c* are equal to the angles *AOC* and *AOB*.



Fig A2-1. The Spherical Triangle

(2) g. **Spherical Angles.** In a *Spherical Triangle* (see Fig A2-1), the angle *A* is the angle between the planes containing the *Great Circle*s *AB* and *AC*, that is, the angle between the plane *AOB* and the plane *AOC*. Similarly, the angle *B* is the angle between the planes *AOB* and *COB*, and the angle *C* is the angle between the planes *AOC* and *COB*. In a *Spherical Triangle ABC*, it is customary to refer to its angles as *A, B* and C, and to the sides opposite these angles as *a, b* and *c*. This is analogous to the conventions adopted in a *Plane Triangle* set out in Appendix 1.

3. Properties of a Spherical Triangle

Certain properties of a *Spherical Triangle* are equivalent to those of a *Plane Triangle*: the largest angle is always opposite the largest side, the smallest angle is always opposite the smallest side and one side is always less than the sum of the other two sides (eg $c < a + b$ in Fig A2-1). However, there are two very important differences between *Spherical Triangle*s and *Plane Triangle*s.

a. **The Sum of the Three Angles of the Spherical Triangle.** The sum of the three angles of the *Spherical Triangle* $A + B + C$ is always greater than 180˚ (π radians) and always less than 540˚ (3π).

b. **The Sum of the Three Sides of the Spherical Triangle.** The sum of the three sides of the *Spherical Triangle* $a + b + c$ is always less than 360˚ (2π).

4. The Solution of a Spherical Triangle

A *Spherical Triangle* has six dimensions: the sizes of its three angles and the lengths of its three sides. Various formulae connect these angles and sides so that, if sufficient of them are given, the rest can be found. The common calculations are those of finding the third side when two sides and their included angle are known, and finding a particular angle when the three sides are known.

5. The Cosine Formula

In Fig A2-2 (below), *O* is the centre of the *Sphere* of radius *R*. *AB, BC* and *CA* are the minor arcs of three *Great Circle*s forming the *Spherical Triangle ABC* on the surface of the *Sphere*. *OA* = *OB* = *OC* = *R*. Angle *BOC* = *a*, angle *AOC* = *b* and angle *BOA* = c .



Fig A2-2. Spherical Trigonometry - The Cosine and Sine Formulae

CD is the perpendicular from *C* to the plane *OAB* and *CE* is the perpendicular from *C* to the line *OB*. ∴ *DE* is perpendicular to OB and angle *CED* = *Spherical* angle at *B*.

Similarly, *CG*, is the perpendicular from *C* to the line OA. ∴ *DG* is perpendicular to *OA*, and angle *CGD* = *Spherical* angle at *A*.

GH is the perpendicular from *G* on to *OB*, and *DJ* is the perpendicular from *D* on to *GH*. *JD* is parallel and equal to HE. Angle *JGD* = *c*.

In the triangle *COE*, which is right-angled at *E*:

$$\frac{OE}{OC} = \cos a \qquad \therefore \quad OE = R \cos a$$

$$\begin{aligned} \text{but } OE &= OH + HE \\ &= OG \cos c + GD \sin c \\ &= R \cos b \cos c + CG \cos A \sin c \\ &= R \cos b \cos c + R \sin b \cos A \sin c \end{aligned}$$

∴ **Cosine Rule:** $\cos a = \cos b \cos c + \sin b \sin c \cos A$ . . . **A2.1**

and Similarly: $\cos b = \cos c \cos a + \sin c \sin a \cos B$ . . . **A2.2**

$\cos c = \cos a \cos b + \sin a \sin b \cos C$ . . . **A2.3**

Thus, if any two sides and their included angle are given, the third side may be found, this side being the one opposite the only *Spherical* angle in the formula. Such formulae are analagous to the *Cosine Formulae* for the *Plane Triangle* set out in Appendix 1. When all three sides of the *Spherical Triangle* are known, the angle may be found by transposing the relevant *Cosine Formula*. For example, from formula (A2.1):

$$\cos A = \frac{\cos a - \cos b \cos c}{\sin b \sin c} \qquad \text{. . . A2.4}$$

6. The Sine Formula

In Fig A2-2 (previous page), in the triangles *CED* and *CGD*, which are both right-angled at *D*:

$$\frac{CD}{CE} = \sin B \quad \text{and} \quad \frac{CD}{CG} = \sin A$$

$$\text{thus: } CE \sin B = CD = CG \sin A$$

$$\therefore \quad R \sin a \sin B = R \sin b \sin A$$

$$\text{ie} \quad \frac{\sin a}{\sin A} = \frac{\sin b}{\sin B} \quad \text{and, by symmetry:}$$

$$\therefore \textbf{ Sine Rule: } \quad \frac{\sin a}{\sin A} = \frac{\sin b}{\sin B} = \frac{\sin c}{\sin C} \qquad \ldots \textbf{A2.5}$$

The *Sine Formula* for the *Spherical Triangle* is analogous to the *Sine Formula* for the *Plane Triangle* set out in Appendix 1, and has the same limitation in that ambiguity arises if it is used to solve the triangle when two sides and one angle are given. It must be remembered that as sin $\theta = \sin(180^\circ - \theta)$, there is no way of knowing from the formula alone whether the quantity found is greater or less than 90°.

In the example at Fig A2-3 (below), *a* is 66°, *b* is 50° and *B* is 40°.

$$\sin A = \frac{\sin a}{\sin b} \times \sin B$$

$$= \sin a \sin B \operatorname{cosec} b$$

$$= \sin 66^\circ \sin 40^\circ \operatorname{cosec} 50^\circ = 0.76657$$

$$A = 50^\circ 02'.8 \text{ or } 129^\circ 57'.2$$



Fig A2-3. Spherical Trigonometry - Ambiguity in Sine Formula

Fig A2-3 (above) shows that *ABC* and A_1BC are possible triangles. The ambiguity, however, may often be resolved in practice and the formula is easier and quicker to use on a calculator than the *Cosine Formula*. The *Sine Formula* may therefore often be used to find the *Great Circle* course, having first found the *Distance*.

When the complete solution of the *Spherical Triangle* is found using the *Cosine Formula*, the sine rule is a useful cross-check against the accuracy of its workings:

$$\text{ie:} \quad \frac{\sin a}{\sin A}, \ \frac{\sin b}{\sin B} \ \text{and} \ \frac{\sin c}{\sin C}$$

7. Polar Spherical Triangles and the Polar Cosine Rule

The *Polar Cosine Rule* may be used to calculate a side of the *Spherical Triangle* given all three angles. It may also be used to calculate an angle given the other two angles and the opposite side.



Fig A2-4. Polar Triangles

In the same way as the *Equator* is related to the Earth's *Axis* (which cuts the Earth's surface at the North and South *Poles* - see definition at Para 2b), so every *Great Circle* has an *'Axis'* and two '*Poles'*. *Polar Triangle* $A_1B_1C_1$ of the *Spherical Triangle ABC* (see Fig A2-4 above) is formed as follows:

- A_1 is the '*Pole*' of the *Great Circle BC* on the same side of *BC* as *A*. OA_1 is perpendicular to the plane of the *Great Circle* through *BC*.
- B_1 is the '*Pole*' of the *Great Circle AC*. OB_1 is perpendicular to the plane of the *Great Circle* through *AC*.
- C_1 is the '*Pole*' of the *Great Circle AB*. OC_1 is perpendicular to the plane of the *Great Circle* through *AB*.

The two triangles *ABC* and $A_1B_1C_1$ are mutually *Polar*. In the *Polar Triangle* $A_1B_1C_1$:

$$\begin{array}{ll} a_1 = \pi - \mathrm{A} & A_1 = \pi - a \\ b_1 = \pi - \mathrm{B} & B_1 = \pi - b \\ c_1 = \pi - \mathrm{C} & C_1 = \pi - c \end{array}$$

If these values are substituted in the *Cosine Rule* (formula A2.1), the *Polar Cosine Rule* formula is obtained:

Polar Cosine Rule:
$$\cos a = \frac{\cos A + \cos B \cos C}{\sin B \sin C} \quad \ldots \mathbf{A2.6}$$

Formula (A2.6) may be used to calculate a side of the *Spherical Triangle* given all three angles. It may also be used to calculate an angle given the other two angles and the opposite side.

8. The Four-Part Formula

The *Four-Part Formula* is one in which the terms are four consecutive angles and sides of any *Spherical Triangle* (see Fig A2-5 below). It may be used to find the initial *Course* or final *Course* direct from *Latitude* and *Longitude* without first finding the *Great Circle Distance*.



Fig A2-5. The Four-Part Spherical Triangle

In Fig A2-5 (above), the four parts to be considered are *C*, *a*, *B* and *c*. The angle *B*, contained by the two sides *a* and *c*, is called the 'inner angle' or 'IA'. The side *a*, common to the angles *B* and *C*, is called the 'inner side' or 'IS'. The others are the 'other angle' *C*, denoted by '*OA*', and the 'other side' *c*, denoted by 'OS'.

The *Four-Part Formula* (A2.7) states that:

$$\cos(IS)\cos(IA) = \sin(IS)\cot(OS) - \sin(IA)\cot(OA) \qquad \text{. . . }\mathbf{A2.7}$$

It may be proved thus:

$$\cos b = \cos c \cos a + \sin c \sin a \cos B$$
$$\cos c = \cos a \cos b + \sin a \sin b \cos C$$

By substituting for cos *b*:

$$\cos c = \cos a\,(\cos c \cos a + \sin c \sin a \cos B) + \sin a \sin b \cos C$$
$$\cos c = \cos c\,(1 - \sin^2 a) + \sin a \cos a \sin c \cos B + \sin a \sin b \cos C$$

Therefore, since cos *c* cancels out and sin *a* is common to the remaining terms:

$$\sin a \cos c = \cos a \sin c \cos B + \sin b \cos C$$

$$\sin a \frac{\cos c}{\sin c} = \cos a \cos B + \frac{\sin b \cos C}{\sin c}$$

Hence, by the *Sine Formula*:

$$\sin a \cot c = \cos a \cos B + \frac{\sin B \cos C}{\sin C}$$

$$\cos a \cos B = \sin a \cot c - \sin B \cot C$$

9. Right-Angled Spherical Triangles

If one angle of a *Spherical Triangle* is a right angle, the formulae for solving the triangle are greatly simplified.

Thus, if the angle *C* in the triangle *ABC* is a right angle (see Fig A2-6 below), the *Cosine Formula* (A2.3) becomes:

$$\cos c = \cos a \cos b \qquad \text{. . . A2.8}$$

And, the *Sine Formula* (A2.5) becomes:

$$\frac{\sin a}{\sin A} = \frac{\sin b}{\sin B} = \sin c \qquad \text{. . . A2.9}$$

The numerous formulae thus obtainable are best summarised by *Napier's Rules* (see Para 10 below).

10. Napier's Mnemonic Rules for Right-Angled Spherical Triangles

Right-angled *Spherical Triangle*s may be used:

- To find the position of the *Vertex* on a *Great Circle*.
- To solve an isosceles triangle where two points are in the same *Latitude*, by bisecting the triangle.
- To find where a *Great Circle* cuts the *Equator*.
- To solve the *Composite Track*.

Triangle *ABC* (see Fig A2-6) is 'extended' to form symbolic five quantities [displayed clockwise: *a, b,* $(90^\circ - A)$, $(90^\circ - C)$ and $(90^\circ - B)$]. These quantities may also be shown as the sectors of a circle having a vertical radius that represents the right angle at *C*.



Fig A2-6. Napier's Right-Angled Triangles

If any one of the quantities at Fig A2-6 (above) is taken as the 'middle' quantity, two of the other four quantities become 'adjacent' and the remaining two quantities become 'opposite', *Napier's Rules* thus become:

Napier's Rules: *sin middle = products of tans of adjacents* . . . **A2.10**
Napier's Rules: *sin middle = products of cosines of opposites* . . . **A2.11**

(10 - Napiers' Rules continued)

In triangle *ABC* (see Fig A2-6 previous page), which is right-angled at *C*, *Napier's Rules* give ten formulae (see Table A2-1 below), which may also be derived from the various formulae described earlier.

Table A2-1. Napier's Ten Rules

MIDDLE	FORMULA	ALSO DERIVED FROM
a	$\sin a = \tan b \cot B$ $\sin a = \sin c \sin A$	Four-Part Formula Sine Rule
b	$\sin b = \tan a \cot A$ $\sin b = \sin c \sin B$	Four-Part Formula Sine Rule
$(90^\circ - A)$	$\cos A = \tan b \cot c$ $\cos A = \cos a \sin B$	Four-Part Formula Polar Cosine Rule
$(90^\circ - c)$	$\cos c = \cot A \cot B$ $\cos c = \cos a \cos b$	Polar Cosine Rule Cosine Rule
$(90^\circ - B)$	$\cos B = \tan a \cot c$ $\cos B = \cos b \sin A$	Four-Part Formula Polar Cosine Rule

11. Quadrantal Spherical Triangles

A *Quadrantal Spherical Triangle* is a *Spherical Triangle* where one side is equal to 90˚ (eg side *c* in Fig A2-7 below). As with the right-angled *Spherical Triangle*, the *Quadrantal Spherical Triangle* may be 'extended' and a five-part figure constructed. The symbolic five quantities are now [A, B, $(90^\circ - a)$, $(C - 90^\circ)$, $(90^\circ - b)$]. These quantities may also be combined in accordance with *Napier's Rules* (formulae A2.10 and A2.11), as follows:

$$\sin A = \tan B \cot b$$
$$\sin A = \sin a \sin C$$
$$\cos a = \cos A \sin b$$
(etc)



Fig A2-7. Napier's Quadrantal Spherical Triangles

12. The Versine and Haversine

If obliged to use logarithmic tables (instead of a calculator, when the *Cosine / Sine Rules* are more useful), it is more convenient to solve a *Spherical Triangle* using a function called the '*Haversine*' of the angle. This function is half the 'versine' − hence the name *Haversine* − and the versine of an angle is defined as the difference between its *Cosine* and unity, that is:

Versine: $\text{versine}\ \theta = 1 - \cos\theta$ . . . **A2.12**

and it follows that:

Haversine: $\text{haversine}\ \theta = \tfrac{1}{2}(1 - \cos\theta)$ . . . **A2.13**

The *Haversine* of an angle is thus always positive, and increases from 0 to 1 as angles increase from 0° to 180°. Fig A2-8 shows the *Haversine* curve in relation to the *Cosine* curve from which it is derived. Norie's Tables give the values of *Haversines* between 0° and 360°.



Fig A2-8. The Haversine Curve

13. The Haversine Formula

To express the *Cosine Rule* in terms of *Haversines* instead of *Cosines*, substitute for the appropriate *Cosines* their values in terms of the *Haversines.*

Thus *cos A* can be written ($1 - 2\ \text{hav}\ A$), and the formula becomes:

$$\cos a = \cos b \cos c + \sin b \sin c\ (1 - 2\ \text{hav}\ A)$$
$$\cos a = \cos b \cos c + \sin b \sin c - 2 \sin b \sin c\ \text{hav}\ A$$
$$\cos a = \cos (b \sim c) - 2 \sin b \sin c\ \text{hav}\ A$$

Similar substitutions for *cos a* and *cos (b ~ c)* give:

$$1 - 2\ \text{hav}\ a = 1 - 2\ \text{hav}\ (b \sim c) - 2 \sin b \sin c\ \text{hav}\ A$$

Haversine: $\text{hav}\ a = \text{hav}\ (b \sim c) + \sin b \sin c\ \text{hav}\ A$ . . . **A2.14**

Great Circle Distance.

When calculating the *Great Circle Distance* between two points, *F* and *T*, with known *Latitudes* and *Longitudes*, the *Haversine Formula* (A2.14) becomes:

$$\text{hav}\ FT = \text{hav}\ FPT \sin PF \sin PT + \text{hav}\ (PF \sim PT)$$

$$\text{hav}\ FT = \text{hav (d.long)} \sin (90^\circ - \text{lat F}) \sin (90^\circ \pm \text{lat T}) + \text{hav}\ [(90^\circ - \text{lat F}) \sim (90^\circ \pm \text{lat } T)]$$

F may be in either North or South *Latitudes*, thus:

GC Distance: $\text{hav dist} = \text{hav d.long} \cos \text{lat } F \cos \text{lat } T + \text{hav (co-lat } F \sim \text{co-lat } T)$
. . . **A2.16**

14. The Half-Log Haversine Formula

The *Half-Log Haversine Formula*, which gives one of the angles when the three sides are known, is derived from the *Cosine Rule* by making substitutions similar to those used in building the *Haversine Formula*.

As before, the first substitution gives:

$$\cos a = \cos (b \sim c) - 2 \sin b \sin c \operatorname{hav} A$$

$$2 \sin b \sin c \operatorname{hav} A = \cos (b \sim c) - \cos a$$

By the rule for the subtraction of two *Cosines*, this equation becomes:

$$2 \sin b \sin c \operatorname{hav} A = 2 \sin \tfrac{1}{2} [a + (b \sim c)] \sin \tfrac{1}{2} [a - (b \sim c)]$$

Therefore, by division:

$$\operatorname{hav} A = \operatorname{cosec} b \operatorname{cosec} c \sin \tfrac{1}{2} [a + (b \sim c)] \sin \tfrac{1}{2} [a - (b \sim c)]$$

But, from the definition of the *Haversine*:

$$\operatorname{hav} x = \tfrac{1}{2} (1 - \cos x) = \tfrac{1}{2} [1 - (1 - 2 \sin^2 \tfrac{1}{2}x)]$$

$$\operatorname{hav} x = \sin^2 \tfrac{1}{2}x$$

Therefore, by analogy:

$$\sin\tfrac{1}{2} [a + (b \sim c) = \sqrt{\operatorname{hav} [a + (b \sim c)]}$$

$$\sin\tfrac{1}{2} [a - (b \sim c) = \sqrt{\operatorname{hav} [a - (b \sim c)]}$$

By substitution:

$$\operatorname{hav} A = \operatorname{cosec} b \ \operatorname{cosec} c \sqrt{\operatorname{hav} \left[a + (b \sim c)\right] \operatorname{hav} \left[a - (b \sim c)\right]}$$

In logarithmic form the *Half-Log Haversine Formula* becomes:

Half-Log Haversine Formula:

$$\log \operatorname{hav} A = \log \operatorname{cosec} b + \log \operatorname{cosec} c + \tfrac{1}{2} \log \operatorname{hav} [a + (b \sim c)] + \tfrac{1}{2} \log\operatorname{hav} [a - (b \sim c)] \qquad \ldots \textbf{A2.15}$$

Initial Great Circle Course / Great Circle Bearing.

When calculating the *Great Circle* initial *Course* when sailing on a *Great Circle* track from one point to another (or the bearing of one point on the Earth's surface from another), the *Half-Log Haversine Formula* (A2.15) is applied. Thus, the bearing of *T* from *F* is given by:

$$\operatorname{hav} PFT = \operatorname{cosec} PF \ \operatorname{cosec} FT \sqrt{\operatorname{hav} \left[PT + (PF \sim FT)\right] \operatorname{hav} \left[PT - (PF \sim FT)\right]}$$

$$\log \operatorname{hav} PFT = \log \operatorname{cosec} PF \ \log \operatorname{cosec} FT + \tfrac{1}{2}\log \operatorname{hav} [PT + (PF \sim FT)] + \tfrac{1}{2}\log \operatorname{hav} [PT - (PF \sim FT)]$$

Initial GC Course:

$$\begin{aligned} \log \operatorname{hav} \text{initial course} &= \log \operatorname{cosec} \text{co-lat } F + \log \operatorname{cosec} \text{distance} \\ &\quad + \tfrac{1}{2} \log \operatorname{hav}[\text{co-lat } T + (\text{co-lat } F \sim \text{distance})] \\ &\quad + \tfrac{1}{2} \log \operatorname{hav}[\text{co-lat } T - (\text{co-lat } F \sim \text{distance})] \qquad \ldots \textbf{A2.17} \end{aligned}$$

The *haversine* / *Half-Log Haversine* solution to Example 2-6 from Para 0211 is set out opposite.

15. Haversine / Half Log Haversine Solution to Example 2-6 from Para 0211

A ship proceeds from position F (45˚N, 140˚E) to T (65˚N, 110˚W). Find the *Great Circle Distance* and the initial *Course*.



Fig A2-9 (Copy of Fig 2-14). Ship's Great Circle Track from Example 2-6

Great Circle Distance:

From formula (A2.16):

$$\begin{aligned}
\textit{hav dist} &= \text{hav d.long} \cos \text{lat } F \cos \text{lat } T + \text{hav}(\text{co-lat } F \sim \text{co-lat } T) \\
\textit{Thus:} \quad \textit{hav dist} &= \text{hav } 110^\circ \cos 45^\circ \cos 65^\circ + \text{hav}(45^\circ \sim 25^\circ) \\
&= \text{hav } 110^\circ \cos 45^\circ \cos 65^\circ + \text{hav } 20^\circ \\
&= 0.67101 \times 0707107 \times 0.422618 + 0.030154 \\
&= 0.230676 \\
&= \text{hav } 57^\circ 24.5' \\
\therefore \textbf{\textit{Great Circle Distance}} &= \mathbf{3444.5'}
\end{aligned}$$

Initial Great Circle Course:

From formula (A2.17):

$$\begin{aligned}
\textit{log hav initial course} &= \log \text{cosec co-lat } F + \log \text{cosec distance} \\
&\quad + \tfrac{1}{2} \log \text{hav}[\text{co-lat } T + (\text{co-lat } F \sim \text{distance})] \\
&\quad + \tfrac{1}{2} \log \text{hav}[\text{co-lat } T - (\text{co-lat } F \sim \text{distance})]
\end{aligned}$$

Thus:

$$\begin{aligned}
\textit{log hav initial Course} &= \log \text{cosec } 45^\circ + \log \text{cosec } 57^\circ 24.5' \\
&\quad + \tfrac{1}{2} \log \text{hav}[25^\circ - 12^\circ 24.5'] \\
&\quad + \tfrac{1}{2} \log \text{hav}[25^\circ + 12^\circ 24.5'] \\
&= \log \text{cosec } 45^\circ + \log \text{cosec } 57^\circ 24.5' \\
&\quad + \tfrac{1}{2} \log \text{hav } 12^\circ 35.5' + \tfrac{1}{2} \log \text{hav } 37^\circ 24.5' \\
&= 0.150515 + 0.074414 + \bar{1}.040056 + \bar{1}.506074 \\
&= \bar{2}.771059 \\
\therefore \textbf{\textit{Initial GC Course}} &= \mathbf{N\ 28^\circ 07.3'E} = \mathbf{028^\circ}
\end{aligned}$$

INTENTIONALLY BLANK

APPENDIX 3

THE SPHERICAL EARTH

1. Scope of Appendix

Appendix 3 contains the following information:

- **Para 2: Meridional Parts for the Sphere**
- **Para 3: Construction of the 'Mer Parts' Formula for the Sphere**
- **Para 4: Evaluation of the 'Mer Parts' Formula for the Sphere**
- **Para 5: Corrected Mean Latitude for the Sphere**

2. Meridional Parts for the Sphere

As stated at Para 0422b:

> ***The Meridional Parts of any Latitude are the number of 'Longitude Units' in the length of a Meridian between the Parallel of that Latitude and the Equator. A 'Longitude Unit' is the length on the chart representing one minute of arc in Longitude.***

3. Construction of the 'Mer Parts' Formula for the Sphere

In Fig A3-1 (below), *X* is any point on the Earth in *Latitude* ϕ, and *Y* is a neighbouring point differing from it in *Latitude* by the small amount $\Delta\phi$. X_1 and Y_1 are the corresponding points on the *Mercator Projection* chart. As all *Meridians* are straight lines at right angles to the *Equator*, A_1B_1 is equal to X_1Z_1.



Fig A3-1. Construction of the 'Mer Part' Formula

a. **Scale of the Chart.** The ratio that the chart length A_1B_1 bears to the geographical distance *AB* decides the *Longitude Scale* of the chart. That is, when *AB* and A_1B_1 are expressed in the same units, A_1B_1 is some fraction of *AB* (ie *AB* is equal to kA_1B_1 where *k* is some constant).

(3) **Example A3-1.** If AB is 1 minute of arc and A_1B_1 is 1 mm, 1 mm on the chart is equivalent to 1 minute of arc or approximately 1,853,300 mm on the Earth, and k is 1,853,300. The value of k thus determines the size of the chart.

b. **Actual Measurement of Meridional Parts.** However, for the actual measurement of *Meridional Parts*, it is sufficient to know the chart unit that represents 1 minute of arc along the *Equator*. In the Example A3-1 (above), where 1 mm represents 1 minute, the *Meridional Parts* of X_1 are simply the number of millimetres in X_1A_1.

c. **Calculation of Chart Length.** To calculate this chart length and so determine the number of minutes of arc along the *Equator* to which it is equivalent, consider the distortion that occurs away from the *Equator*:

XZ is the *Parallel* through X, and XY the *Rhumb Line* joining X to Y. On the chart X_1Z_1 is the *Parallel* and X_1Y_1 the *Rhumb Line*, both lines being straight. Then, if all lengths XZ, AB, A_1B_1 ... are measured in the same units:

$$XZ = AB\cos\phi \qquad \text{. . . (formula 2.1)}$$

$$= kA_1B_1\cos\phi$$

$$= kX_1Z_1\cos\phi$$

$$\text{ie}\quad X_1Z_1 = \frac{1}{k}XZ\sec\phi$$

d. **Stretching of Distance Scale.** Any arc of a *Parallel*, the *Latitude* of which is ϕ, is thus represented on the chart by a line proportional to the actual length of the arc multiplied by $\sec\phi$, a quantity greater than unity. The distance *Scale* along the *Parallel* is therefore stretched, as follows:

If Y is taken sufficiently close to X for XYZ to be considered a plane triangle right-angled at Z:

$$\frac{Z_1Y_1}{ZY} = \frac{X_1Z_1}{XZ}$$

$$= \frac{1}{k}\sec\phi$$

$$\text{Thus:}\quad Z_1Y_1 = \frac{1}{k}ZY\sec\phi$$

Any small element of a *Meridian* in near *Latitude* ϕ is thus represented on the chart by a line proportional to the actual length of the element multiplied by $\sec\phi$; the distance *Scale* along the *Meridian* is therefore stretched.

As the actual distance between Z and Y on the Earth is $\Delta\phi$ in circular measure:

$$\text{Actual Distance} = \frac{180 \times 60}{\pi}\Delta\phi = 3437.747\,\Delta\phi \quad \text{(minutes of arc)}$$

$$\text{Hence:}\quad Z_1Y_1 = \frac{1}{k}3437.747\sec\phi\,\Delta\phi \quad \text{(minutes of arc)}$$

(3d) But, 1 minute of arc is equal to *k* millimetres (or whatever the *Scale* units are).

Therefore: $Z_1Y_1 = \left(\frac{1}{k} 3437.747 \; sec \; \phi \Delta \phi\right) k$ (in millimetres or *Scale* units)

The actual chart length of Z_1Y_1 in millimetres, or whatever the *Scale* units are, is thus:

$$Z_1Y_1 = 3437.747 \; sec \; \phi \Delta \phi$$

The chart length of any particular *Parallel* from the *Equator*, measured along a *Meridian* is clearly the sum of all the component elements of which the expression just found is typical. If the *Latitude* of the *Parallel* is ϕ measured in radians, this sum, in the chosen units, is given by:

$$3437.747 \int_0^{\phi} sec\phi \, d\phi \quad (radians)$$

The number of *Meridional Parts* or *Longitude Units* (a *Longitude Unit* is the length on the chart that represents 1 minute of arc in *Longitude*) in the length of a *Meridian* between ***Latitude*** L_F measured in degrees and the *Equator* is thus:

$$3437.747 \; log_e \; tan\left(45^\circ + ½L_F{}^\circ\right) \qquad \textbf{. . . A3.1}$$

e. **Evaluation of the 'Mer Parts' Formula for the Sphere.** From formula (A3.1), the actual evaluation of the '*Mer Parts'* formula for the *Sphere* may be accomplished more easily if the logarithm is expressed to base 10. Thus, if *y* is the number of *Meridional Parts*:

$$= 7915.7045 \; log_{10} tan\left(45^\circ + ½L_F{}^\circ\right) \qquad \text{. . . (formula 4.1)}$$

Suppose the *Latitude* is 40˚. Then:

$$y = 7915.7045 \; log_{10} \; tan \; 65^\circ$$

$$= 7915.7045 \times 0.33132745$$

$$= 2622.69$$

......................................(continued overleaf)

4. Corrected Mean Latitude for the Sphere

At Paras 0205a/b it was established that in some circumstances, the *Mean Latitude* must NOT be used to determine *d.long* by means of formula (2.5), but that a correction to the *Mean Latitude* must first be applied.



Fig A3-2. The Corrected Mean Latitude

In Fig A3-2 (above), a ship travels from *F* to *T*. Since the *Departure* is greater than *HT* and less than *FG*, it must be exactly equal to the arc of some *Parallel UV*. The *Latitude* of this *Parallel* is called the *Corrected Mean Latitude*, and if it is denoted by *L*, then:

$$QR = UV \sec L$$
$$d.long = Departure \sec L$$

This is an accurate formula, but *L* must be known before it can be used. The problem is therefore to find *L*.

The *Latitude*s of *F* and *T* may be denoted by L_F and L_T, and the difference of *Latitude* between them, *FH*, divided into *n* equal parts of length *x*. *JK* is one of these parts. Then:

$$d.lat = nx = L_T - L_F$$

If *Parallel*s of *Latitude* are now drawn through the points *J, K . . .* , intersecting the *Rhumb Line FT* in *A, B,* etc and the *Meridians* through these points of intersection in A_1, B_1, etc, *n* small triangles are formed. These triangles are equal because in each the side of which AA_1 is typical is *x*, the angle at A_1 is 90˚, and the angle at *A* is the course (which is constant between *F* and *T*). The length of the arc of which A_1B is typical is thus the same for each triangle and if the triangles are made sufficiently small (that is, if *n* if made sufficiently large) for the conditions for evaluating an accurate *Departure* to be realised, the *Departure* between *F* and *T* is the sum of the elements A_1B.

(4) Thus:

$$Departure = ny \quad \text{(where } y \text{ is the length of } A_1B.)$$

Also, the *d.long* corresponding to the element A_1B is *ab* and:

$$ab = A_1B \sec (\text{Latitude } B)$$
$$ab = y \sec (\text{Latitude } K)$$

By adding all these elements *ab, bc* etc, the *d.long* is obtained, the formula being:

$$d.long = y[\sec (L_F + x) + \sec (L_F + 2x) + \ldots + \sec L_T]$$

Or, since the *Departure* is equal to *ny*:

$$d.long = Departure \frac{\sec \left(L_F + x\right) + \sec \left(L_F + 2x\right) + \ldots + \sec L_T}{n}$$

But the *Corrected Mean Latitude L* is given by:

$$d.long = Departure \sec L$$

Hence, by equating these two values of the *d.long*:

$$\sec L = \frac{1}{n}\left[\sec\left(L_F + x\right) + \sec\left(L_F + 2x\right) + \ldots + \sec L_T\right]$$

The quantity *sec L* is thus the mean of the secants of the *Latitude*s of the successive *Parallel*s. Written in the integral form in order that the value of *sec L* may be found, the equation is:

$$\sec L = \frac{1}{nx}\left[\sec \left(L_F + x\right) + \sec\left(L_F + 2x\right) + \ldots + \sec L_T\right]x$$
$$= \frac{1}{\left(L_T - L_F\right)}\left[\sec\left(L_F + x\right) + \sec\left(L_F + 2x\right) + \ldots + \sec L_T\right]x$$

Then, as *n* becomes larger, *x* grows progressively smaller and, in the limit:

$$\sec L = \frac{1}{d.lat}\int_{LF}^{LT} \sec L \, dL \ldots$$

And, if *d.lat* is expressed in radians:

$$\sec L = \frac{1}{d.lat}\left[\log_e \tan\left(\frac{\pi}{4} + \frac{L}{2}\right)\right]_{L_F}^{L_T}$$

Or, if *d.lat* is expressed in minutes of arc:

$$\sec L = \frac{1}{d.lat} \times \frac{180 \times 60}{\pi} \times \log_e 10[\log_{10} \tan(45^\circ + \tfrac{1}{2}L_T{}^\circ) - \log_{10} \tan(45^\circ + \tfrac{1}{2}L_F{}^\circ)]$$

Thus it may be seen that:

$$\frac{180 \times 60}{\pi} \times \log_e 10[\log_{10} \tan(45^\circ + \tfrac{1}{2}L_T{}^\circ) - \log_{10} \tan(45^\circ + \tfrac{1}{2}L_F{}^\circ)]$$

corresponds to the *Meridional Parts* formula (4.1) and is equal to the *Difference of Meridional Parts* (*DMP*). Thus:

$$\sec L = \frac{DMP}{d.lat\ (\text{minutes of arc})} \qquad \ldots \text{(formula 2.7)}$$

INTENTIONALLY BLANK

APPENDIX 4

PROJECTIONS

1. Scope of Appendix

Appendix 4 contains the following information:

- **Para 2: Conical Orthomorphic Projection on the Sphere.**
- **Para 3: Deduction of the 'Mer Part' Formula for the Sphere.**
- **Para 4: Mercator Projection Chart - Position Circles.**
- **Para 5: Modified Polyconic Projection.**
- **Para 6: Polar Stereographic Projection.**
- **Para 7: Gnomonic Projection.**
- **Para 8: Transverse Mercator Projection - Conversion of Geographical / Grid Coordinates.**

2. Conical Orthomorphic Projection on the Sphere

On *Projections* of the simple *Conical* type, all *Meridians* are equally spaced straight lines meeting in a common point beyond the limits of the chart or map; the *Parallels* (of *Latitude*) are concentric circles, the common centre of which is the point of intersection of the *Meridians* (see Fig A4-1 below). In Fig A4-1:

- The *Cone AVG* is tangential to the *Sphere* along the *Standard Parallel AFGH.*
- *AV* is the radius r_o of the *Standard Parallel* at *Latitude* ϕ_0 (*Co-Latitude* Z_o) on the *Projection*.
- Radius *AV* is equal to R tan Z_o where R is the radius of the *Sphere*.
- The angles *EVF* and *WVF* on the *Projection* are equal, each representing 180˚ of *Longitude* on the *Sphere*.



This scale is correct at the standard parallel AG.
Away from AG, the scale becomes increasingly large

Fig A4-1. The Simple Conical Orthomorphic Projection

(2) a. **Simple Conical Orthomorphic Projection.** The *Meridians* and *Parallels* of the *Simple Conical Orthomorphic Projection* intersect at right angles and thus angles are preserved. Although this is necessary for *Orthomorphism*, it is not sufficient to make the *Projection Orthomorphic*; for this, the *Scale* along the *Meridian* must be equal to the *Scale* along the *Parallel* at any point on the *Projection*.

- **Fig A4-2.** In Fig A4-2 (opposite), *ABCD* is an infinitely small quadrilateral on the *Sphere*, while $A_1B_1C_1D_1$ is its plane representation on the *Conical Projection*.

- **Constant of the Cone.** The small change in the *Meridian* on the *Projection* ($d\theta$) is only a fraction of the equivalent change in the *Meridian* on the *Sphere* ($d\lambda$) and this fraction may be referred to as *n* (the *Constant of the Cone*).

  where: $d\theta = n d\lambda$ . . . **A4.1**

  See also further details at Para 2b (opposite).

- **Scale Along the Meridian at A_1.** The *Scale* along the *Meridian* at A_1 is the relationship:

  $$\frac{A_1B_1}{AB} = \frac{-\,dr}{Rd\phi} = \frac{dr}{RdZ}$$ . . . **A4.2**

  The negative sign must be allocated to *dr* if ϕ is used, because *r* increases as ϕ decreases. The positive sign must be allocated if *Z* is used, as *r* increases as *Z* increases.

- **Scale along the Parallel at A_1.** The *Scale* along the *Parallel* at A_1 is the relationship:

  $$\frac{A_1D_1}{AD} = \frac{rd\theta}{R\ \cos\ \phi\ d\lambda}$$

  $$\frac{A_1D_1}{AD} = \frac{rd\theta}{R\ \sin\ Z\ d\lambda} = \frac{nr}{R\ \sin\ Z}$$ . . . **A4.3**

- **Orthomorphism.** To be *Orthomorphic*, the *Scales* along the *Parallel* and the *Meridian* must be equal, and where *k* is a constant defining the *Scale*:

  ie: $$\frac{dr}{RdZ} = \frac{nr}{R\ \sin\ Z}$$

  $$\frac{1}{r}dr = n\,\mathrm{cosec}\ Z\ dZ$$

  ie: $$\int \frac{1}{r}dr = \int n\ \mathrm{cosec}\ Z\ dZ$$

  $$\log_e r = n\ \log_e\ \tan\frac{Z}{2} + C\ = n\ \log_e\ \tan\frac{Z}{2} + \log_e\ k$$

  $$r = k\left(\tan\frac{Z}{2}\right)^n$$ . . . **A4.4**

- **General Properties.** The general properties of a system of conformal *Conical Projection*s may be defined by formula (A4.4).

(2a continued)



Fig A4-2. Scale on the Conical Orthomorphic Projection

(2) b. **The Constant of the Cone.** From Fig A4-1, it may be seen that the length of the *Standard Parallel AFGH* is $2\pi R \cos\phi_0$, whilst the radius of the *Parallel* on the *Projection* is $R \tan Z_o$ or $R \cot\phi_0$. When this *Conical* shape is displayed for the whole 360˚ of *Longitude* for the Earth, the angle on the *Projection* represents 2π. Thus:

$$R \cot\phi_0 \, d\theta = 2\pi R \cos\phi_0$$
$$d\theta = 2\pi \sin\phi_0$$

But, in this case,

$$d\lambda = 2\pi$$

So, from formula (A4.1),

$$2\pi n = 2\pi \sin\phi_0$$
$$\therefore \quad n = \sin\phi_0 = \cos Z_o \qquad \text{. . . } \mathbf{A4.5}$$

Thus for the simple *Conical Projection*, the *Constant of the Cone* (*n*), equals $\sin\phi_0$, which is the sine of the *Standard Parallel*.

.... (continued overleaf)

(2) c. **Conical Orthomorphic Projection with Two Standard Parallels.** Since the *Scale* at any point not on the *Standard Parallel* is too large on a *Simple Conical Orthomorphic Projection*, two *Standard Parallels* may be chosen where the *Scale* is correct (see Fig A4-3 below). However, between the two *Parallels* (AG and A_1G_1 at Fig A4-3 below), the *Scale* of the chart is too small, while beyond them the *Scale* is too large. This *Projection* is known as *Lambert's Conical Orthomorphic Projection*.



The *Scale* is correct at the *Standard Parallels AG and A1G1*.
Between them, the *Scale* is too small; outside them it becomes increasingly large.

Fig A4-3. Lambert's Conical Orthomorphic Projection, two Standard Parallels

3. Deduction of the Meridional Parts ('Mer Parts') Formula for the Sphere

The formula giving the *Meridional Parts* ('*Mer Parts*') of any *Latitude* may be derived from the general formula (A4.4) for conformal *Conical Projections*.

If Z_o is the *Co-Latitude* of the *Standard Parallel*, the radius of the *Parallel* on the *Projection* is given from formula (A4.4), thus:

$$r_o = k\left(tan\,\frac{Z_o}{2}\right)^n$$

The distance between the *Standard Parallel* and any other *Parallel* is given by:

$$r_o - r = k\left[\left(tan\,\frac{Z_o}{2}\right)^n - \left(tan\,\frac{Z}{2}\right)^n\right]$$

And approximating by expanding the right-hand side in its exponential form, given that *n* ultimately tends to zero, becomes:

$$r_o - r \simeq kn\left(log_e\;tan\,\frac{Z_o}{2} - log_e\;tan\,\frac{Z}{2}\right)$$

The value of *k* follows at once from the fact that $r_o\;cos\;Z_o$ is equal to $R\;sin\;Z_o$ and is given by:

$$k = \frac{R\;sin\;Z_o}{cos\;Z_o} \times \frac{1}{\left(tan\,\frac{Z_o}{2}\right)^n}$$

and since: $n = cos\;Z_o$

then: $$kn = \frac{R\;sin\;Z_o}{\left(tan\,\frac{Z_o}{2}\right)^n}$$

When the *Conical Projection* becomes a *Cylindrical Projection*, the *Standard Parallel* becomes the *Equator*; this being the *Mercator Projection,* Z_o becomes 90°.

thus: $kn = R$

The value of $(r_o - r)$, which is now the chart length of a *Parallel* in *Latitude* ϕ from the *Equator*, measured along a *Meridian*, is therefore given by:

$$r_o - r = -R\;log_e\;tan\,\frac{Z}{2} = R\;log_e\;cot\,\frac{Z}{2}$$

$$= \frac{10800}{p}\;log_e\;tan\left(\frac{\pi}{4} + \frac{\phi}{2}\right)\;\text{radians}$$

$$= 3437.747\;log_e\;tan\left(45° + \frac{1}{2}\phi°\right) \qquad \text{. . . (formula A3.1)}$$

$$= 7915.7045\;log_{10}\;tan\left(45° + \frac{1}{2}\phi°\right) \qquad \text{. . . (formula 4.1)}$$

Note A4.1. *Symbol ϕ is used for Latitude at formulae (A3.1) and (4.1) above, although elsewhere it may be represented by T or L_F, depending on the context.*

4. Mercator Projection Chart - Position Circles

If a *Position Circle* is drawn on the Earth's surface as a circle with the *Geographic Position* of the heavenly body as centre, it will be *Small Circle* (see Fig A4-4 below). When plotted on a *Mercator Projection* chart, the shape of the *'Position Circle'* will no longer be a circle but a curve (see Figs 4-5 and 4-6 opposite); the problem is to find formula (A4.7) to establish the resulting curve path:

Fig A4-4 (below) shows the relative positions of the *Pole P*, the observer Z, and the *Geographic Position* of the heavenly body *U*, when the *True Altitude* (obtained from a *Sextant*) is *a*, and the *Declination* is *d*. The *Latitude* of Z is ϕ . Then, if X and x are the easterly *Longitude*s of Z and *U*, the *Hour Angle* of the heavenly body is $(x - X)$.

The *Cosine Formula* applied to the *Spherical* triangle *PZU* gives:

$$\cos UZ = \cos PU \cos PZ + \sin PU \sin PZ \cos UPZ \quad \text{. . . (formula A2.1)}$$

ie:

$$\sin a = \sin d \sin \phi + \cos d \cos \phi \cos (x - X)$$

or:

$$\cos (x - X) = \sin a \sec d \sec \phi - \tan d \tan \phi \quad \text{. . . } \mathbf{A4.6}$$



Fig A4-4. A Position Circle Drawn on the Earth's Surface

If the coordinates of Z on the chart are x and y, then:

$$\sec \phi = \tfrac{1}{2}(e^{y} + e^{-y})$$

and:

$$\tan \phi = \tfrac{1}{2}(e^{y} - e^{-y})$$

Hence, by substitution:

$$2 \cos (x - X) = e^{y} (\sin a \sec d - \tan d) + e^{-y} (\sin a \sec d + \tan d) \quad \text{. . . } \mathbf{A4.7}$$

Formula (A4.7) is the general equation of the curve on the chart that represents the *Position Circle*; the curve itself is defined by the values of *a, d* and *X*.

Fig A4-5 (opposite) shows the curve as it appears on a *Mercator Projection* chart when the *Declination* is zero, and Fig A4-6 (opposite) shows three typical curves representing *Position Circle*s for three values of the *Altitude* when the *Geographic Position* is in *Latitude* 40˚N, *Longitude* 60˚W.

(3 continued)


Latitude (90° – a)N
Equator
(90°– a)
(90°– a)
Latitude (90° – a)s

Fig A4-5. Position Circle Plotted on a Mercator Projection Chart with Declination Zero


150°
180°
150°
120°
90°
60°
30°
0°
30°
60°
90°
120°
60°
30°
0°
30°
60°
60°
30°
0°
30°
60°
150°
180°
150°
120°
90°
60°
30°
0°
30°
60°
90°
120°
East
West
East

Fig A4-6. Typical Position Circles (for three values of the Altitude), when the Geographic Position is in Latitude 40˚N, Longitude 60˚W.

5. Modified Polyconic Projection

Although new charts on a *Scale* 1:50,000 or larger are now drawn on the *Transverse Mercator Projection*, there are 290 *UKHO* harbour plans / approaches in use (2008), traditionally described on the chart as being *Gnomonic,* while actually *Modified Polyconic Projections*.

a. **Polyconic Projection Properties.** In the *Polyconic Projection*, the *Central Meridian* alone is straight; distances between consecutive *Parallels* are made equal to the real distances along the surface of the *Spheroid,* to the *Scale* required for the chart.

b. **Polyconic Projection Construction.** Each *Parallel* is constructed as if it were the *Standard Parallel* of a simple *Conical Projection*. This means (see Chapter 4) that the circular arcs in which the *Parallels* are developed are not concentric, but their centres lie on the *Central Meridian*. The other *Meridians* are concave towards the *Central Meridian* and, except near the corners of maps or charts showing large areas, they intersect the *Parallels* at angles differing only slightly from right angles.

c. **Modified Polyconic Projection Construction.** In practice, all *Meridians* are drawn as straight lines on Admiralty charts and to this extent the *Polyconic Projection* has been modified, although the normal curvature of the limiting *Meridians* would be extremely small in any case, having regard to the *Scale* of the chart.

The coordinates (*x, y*) of any point *Q* on the *Modified Polyconic Projection* (Fig A4-7) may be found from the formulae:

$$x = v\Delta\lambda \cos\phi \qquad \ldots \textbf{A4.8}$$

$$y = \tfrac{1}{4}v(\Delta\lambda)^2 \sin 2\phi \qquad \ldots \textbf{A4.9}$$

where: ϕ is the *Latitude* of the *Parallel*,
$\Delta\lambda$ is the difference of *Longitude* from the *Central Meridian*,
v is the (transverse) radius of curvature at right angles to the *Meridian* at *Latitude* ϕ (see Fig A4-7 below); it should not be confused with the *Meridional* radius of curvature ρ (see Para 0314).

These formulae are accurate for *Projections* covering 2° of *Latitude* and 1° of *Longitude*. This may be extended to 2° of *Longitude* without appreciable inaccuracy by laying off coordinates from each of the extreme *Meridians*, to cover a further 30' of *Longitude*.



Fig A4-7. The Modified Polyconic Projection

6. Polar Stereographic Projection

The *Polar Stereographic Projection* (see Fig A4-8 below) is a *Perspective Conformal Projection* on a plane tangential to the *Sphere* at the *Pole*, obtained by projecting from the opposite *Pole*. Angles are correctly represented; *Parallels* of *Latitude* are represented by circles radiating outwards from and centred on the *Pole*. *Meridians* appear as straight lines originating from the *Pole*.



Fig A4-8. The Polar Stereographic Projection

If R is the Earth's radius and ϕ the *Latitude* of G, the angle PP_1G_1 is ½ (90° – ϕ °) and the radius PG_1 of the projected *Parallel* is $2R$ tan ½ (90° – ϕ °).

If the radius PG_1 is r, and the *Co-Latitude* of ϕ is Z, the *Scale* along the *Parallel* is G_1 is given by:

$$\frac{r}{R\ sin\ Z} = \frac{2R\ tan\ \frac{1}{2}Z}{R\ sin\ Z} = sec^2\,\tfrac{1}{2}Z$$

The *Scale* along the *Meridian* at G_1 where dr is a small increase in r and dz a small increase in Z is:

$$\frac{dr}{Rdz} = \frac{2R\ \frac{1}{2}\ sec^2\,\frac{1}{2}Z}{R} = sec^2\,\tfrac{1}{2}Z$$

The *Scale* is the same in each direction; thus the *Orthomorphic* property is established.

7. Gnomonic Projection

The *Gnomonic Projection* projects the Earth's surface from the Earth's centre onto the tangent plane. The *Gnomonic Projection* is only applied to a *Sphere* which represents the Earth. The *Gnomonic Projection* is NOT *Orthomorphic* and it does NOT have *Equal Area* properties. *Great Circles* are represented by straight lines on this *Projection* . (This summary is repeated from Para 04440d).

a. **Principal or Central Meridian.** The plane on which the *Parallels* and *Meridians* are projected is a tangent plane and, to avoid distortion, the tangent point *K* should be chosen in the centre of the area to be shown (see Fig A4-9 opposite).

Since the *Gnomonic Projection* is a *Perspective Projection*, the point on the tangent plane that corresponds to a point on the *Sphere* that represents the Earth is found by producing the radius at the point until it cuts the tangent plane. Thus (at Fig A4-9 opposite) *p* corresponds to *P* (the *Pole*), and all points on the *Meridian PK* project into the straight line *pK. PK* is known as the *Principal Meridian* or the *Central Meridian*.

If *B* is any point and *ABC* any *Great Circle* through it, the arc *AB* projects into the straight line *ab*. The *Meridian* through *B* is *PBL* and, since it is part of a *Great Circle*, *pbl* is also a straight line. The *Meridians* on the *Gnomonic Graticule* are thus straight lines radiating from *p*.

The straight line *Kl* corresponds to the *Great Circle* arc *KL*.

If ϕ_K and ϕ_A are the *Latitude*s of *K* and *A*, then:

$$KOP = arc\ KP = 90^\circ - \phi_K$$

And: $$AOP = arc\ AP = 90^\circ - \phi_A$$

Also: $$\begin{aligned} KOA &= KOP - AOP \\ &= (90^\circ - \phi_K) - (90^\circ - \phi_A) \\ &= \phi_A - \phi_K \end{aligned}$$

In triangle OKa:

$$Ka = OK\ tan\ KOa = OK\ tan\ KOA$$

$$Ka = R\ \tan\left(\phi_A - \phi_K\right) \qquad \ldots \mathbf{A4.10}$$

The chart distances of the *Pole* (*Kp*) and any point on the *Central Meridian* (*Ka*) from the tangent point are thus known.

It is thus clear from Fig A4-9 (opposite) that, if the *Latitude* of *A* is greater than that of *K*, *a* will lie on the line *K*p between *K* and *p*. If the *Latitude* of *A* is less, *a* will lie beyond *K* on *pK* produced.

(7a continued)



Fig A4-9. Gnomonic Projection - The Principal (or Central) Meridian

b. **Angle Between Two Meridians on the Chart.** The difference of *Longitude* between the *Meridians PBL* and *PAK* in Fig A4-9 (above) is the angle *LPK*, denoted by λ, and this angle is projected into the angle *lpK*, denoted by α.

Suppose the great circle *ABC* is chosen so that it cuts the *Meridian PK* at right angles. Its projection *ab* will then be at right angles to *Kp* and, from the plane right-angled triangle *pab*:

$$ab = ap \tan \alpha$$

Also, of the plane of the great circle *KLM* is made to cut the *Central Meridian* at right angles, the angle *pKl* is a right angle and, from the plane right-angled triangle *pKl*:

$$Kl = Kp \tan \alpha$$

From the plane right-angled triangles *lKO* and *pKO*:

$$Kl = OK \tan KOL$$

And: $$Kp = OK \tan KOP = R \cot \phi_K$$

By Napier's rules applied to the *Spherical* triangle *LKP*, right-angled at *K*:

$$\tan KL = \sin KP \tan \lambda$$

Hence, by combining these relations:

$$\tan \alpha = \sin \phi_K \tan \lambda \qquad \text{. . . A4.11}$$

From this relation it is apparent that when ϕ_K is 90˚, (ie when the *Pole* is the tangent point), α is equal to λ and there is no distortion in the chart angles between the *Meridians*: they are equal to exact differences of *Longitude*. When the tangent point is not at the *Pole*, there is distortion and the angles between the *Meridians* are not represented correctly on the chart.

If the distance *ab* is required, it can be found by substitution. Thus:

$$\begin{aligned} ab &= ap \tan \alpha \\ &= (Kp - Ka) \sin \phi_K \tan \lambda \\ &= R [\cot \phi_K - \tan (\phi_A - \phi_K)] \sin \phi_K \tan \lambda \\ &= R \tan \lambda \cos \phi_A \sec (\phi_A - \phi_K) \end{aligned} \qquad \text{. . . A4.12}$$

(7) c. **Parallels of Latitude.** As *Parallels* of *Latitude* are not *Great Circles*, they form a series of curves on the *Gnomonic Graticule*. In Fig A4-10 (below) *ABC* is a *Parallel* in *Latitude* ϕ , and *b* is the projection of *B*. As *B* moves along the *Parallel*, *b* describes a path which is not a straight line. The problem is to find formula (A4.13) to establish the path, and this can be done by referring *b* to the rectangular axes *KX* and *Kp*.



Fig A4-10. Gnomonic Projection - The Parallel of Latitude

If the angle *AKB* is denoted by η, the angle *bKp* will also be η because the *Great Circles KB* and *KP* can be regarded as '*Meridians*' radiating from '*Pole*' *K* which is a tangent point. There is thus no distortion when this angle is projected. Hence, if *x* and *y* are the coordinates of *b*:

$$x = Kb \sin \eta$$

And: $$y = Kb \cos \eta$$

And: $$x^2 + y^2 = Kb^2$$

From the right-angled *Plane Triangle KOb*:

$$Kb = OK \tan KOb$$

From the *Spherical Triangle PBK,* by the *Cosine Formula*:

$$\cos PB = \cos KB \cos KP + \sin KB \sin KP \cos \eta$$

ie: $$\sin\phi \sec KB = \sin \phi_K + \tan KB \cos \phi_K \cos \eta$$

For convenience take the radius of the *Sphere* as unity. Then:

$$\sin\phi \sec KB = \sin \phi_K + y \cos \phi_K$$

And: $$\tan^2 KB = x^2 + y^2$$

ie $$\sec^2 KB = 1 + x^2 + y^2$$

$$\therefore \sin^2 \phi (1 + x^2 + y^2) = \sin^2 \phi_K + 2y \sin \phi_K \cos \phi_K + y^2 \cos^2 \phi_K$$

Thus: $$x^2 \sin^2 \phi + y^2 (\sin^2 \phi - \cos^2 \phi_K) - 2y \sin \phi_K \cos \phi_K = \sin^2 \phi_K - \sin^2 \phi \quad \ldots \textbf{A4.13}$$

For all points on the *Parallel ABC*, ϕ is constant and ϕ_K is also constant. Thus the formula (A4.13) is therefore the equation of the curve that represents the *Parallel ABC* on the chart.

(7) d. **To Construct a Gnomonic Graticule.** When the tangent point is on the *Equator* or at the *Pole*, the *Graticule* admits a simple geometrical construction. When the tangent point is elsewhere, formula (A4.13) must be employed.



Fig A4-11. The Gnomonic Graticule

Fig A4-11 (above) shows the *Graticule* when the tangent point is in *Latitude* 45˚S, *Longitude* 120˚W. *MK* is the *Central Meridian*, and the other *Meridians* are inclined to it at angles given by:

$$\tan\alpha = \sin\phi_K \tan\lambda$$

where ϕ_K is 45˚ and λ has successive values 10˚, 20˚, 30˚, etc.

The position of the *Pole* (not shown in Fig A4-11) is given by:

$$Kp = OK\cot\phi_K$$

Kp can therefore be marked according to the chosen *Scale*, and the *Meridians* drawn as lines radiating from *p* at the angles discovered.

If *b* is the point corresponding to *Latitude* 50˚S, *Longitude* 130˚W, and *ba* is the perpendicular from *b* to *MK*, the length of *Ka* in the chosen *Scale* is given by:

$$Ka = \tan(\phi_A - \phi_K)$$

where ϕ_A is the *Latitude* of *A*, the point that *a* represents on the chart (see Fig A4-10 opposite).

If ϕ_B is the *Latitude* of *B*, the point that *b* represents on the chart, *Napier's Rules* applied to the triangle *PBA* give:

$$\tan\phi_A = \tan\phi_B \sec\lambda$$

where λ is the difference of *Longitude* between *A* and *B*.

This formula gives ϕ_A since ϕ_B is 50˚ and λ is 10˚. Hence *Ka* can be found. Also, in the chosen units:

$$ab = \tan\lambda\cos\phi_A \sec(\phi_A - \phi_K)$$

Thus: $$ab = \tan 10^\circ \cos\phi_A \sec(\phi_A - 45^\circ)$$

The point *b*, corresponding to *Latitude* 50˚S, *Longitude* 130˚W, can therefore be plotted with other points where this *Parallel* cuts the *Meridians*.

In this way all the *Parallels* can be inserted.

(7) e. **Equatorial Gnomonic Graticule.** When the tangent point is on the *Equator*, ϕ_K is zero, and the general formulae are simplified considerably. The *Graticule*, however, lends itself to a geometrical construction.



Fig A4-12. Gnomonic Projection - The Equatorial Graticule (1)

In Fig A4-12 (above) the *Central Meridian* is *KP*, and this is represented on the chart by *KM* which is at right angles to *OK*. The *Equator KA* projects into the straight line *Ka* at right angles to *KM*, and any other *Meridian*, *AP*, projects into a line at right angles to *Ka* and therefore *Parallel* to *KM*.

The distance between the projected *Meridian ab* and the *Central Meridian* is given by:

$$Ka = OK \tan KOA$$
$$= R \tan (\text{d.long between } K \text{ and } A)$$

Thus the positions of the *Meridians* can be decided.

If *B* is any point on the *Meridian AP* in *Latitude* ϕ , B projects into *b*, and *ab* represents this *Latitude* on the chart. Fig A4-13 (opposite) shows the geometrical construction for finding the position of *b*.

The plane of *Projection* is represented by *MKa* in the plane of the paper, and *Ka* is a tangent to the *Equatorial* circle at *K*. *A* is fixed on this circle by its exact difference of *Longitude* from *K*, and it projects into *a*. If ab_1 is now drawn at right angles to *Oa*, so that the angle aOb_1 is equal to the *Latitude* of *B*, the triangle aOb_1 is equal in all respects to the triangle *aOb* in Fig A4-12 (above). The position of *b* can thus be marked merely by making *ab* equal to ab_1.

Other points on the *Projection* of the *Parallel* through *B* can be found in the same way. Since, however, a *Graticule* is usually drawn for equal angular intervals of *Latitude* and *Longitude*, the work can be shortened by drawing radials at the required interval and using them for both *d.long* and *Latitude* as shown in Fig A4-14 (opposite).



Fig A4-13. Gnomonic Projection - The Equatorial Graticule (2)



Fig A4-14. Gnomonic Projection - The Equatorial Graticule (3)

(7e cont)

This same construction can be used for finding the position of the *Vertex* and the *Latitude* of any point on a *Great Circle*, the *Longitude* of which is known.

Any *Great Circle* projects into a straight line. Also, a *Great Circle* cuts the *Equator* in two points 180˚ apart. In Fig A4-15 (below), *Q* is one of these points, and *q* its projection. Then, since the *Vertex Longitude* is 90˚ from the *Longitude* of *Q*, the position of the *Vertex v* is found merely by making the angle *QOU* a right angle. The angle uOv_1 measures the *Vertex Latitude*.

If the *Latitude* of any point *x* is required, it can be found in the same way, that is, by drawing *xy* at right angles to *uq* and yx_1 at right angles to *Oy*, and making yx_1 equal to *xy*. The angle yOx_1 then measures the *Latitude* of the point *X* on the Earth to which *x* corresponds on the chart.



Fig A4-15. Gnomonic Projection - The Equatorial Graticule (4)

8. Transverse Mercator Projection - Conversion of Geographical / Grid Coordinates

The symbols and formulae to be used in the appropriate computer program for the conversion of *Geographic Position* to *Grid* coordinates and vice versa on the *Transverse Mercator Projection* are set out below and overleaf.

a. **Symbols.** The symbols used in these formulae, which correspond to those in use in *UKHO*, are as follows:

a = semi-major axis of *Spheroid* (metres)
b = semi-minor axis of *Spheroid* (metres)
e = *Eccentricity* of *Spheroid*

$$n = \frac{a-b}{a+b}$$

ϕ = *Latitude* (radians)
λ = *Longitude* (radians)
λ_o = *Longitude* of *Central Meridian* of *Grid* (radians)
$\Delta\lambda = \lambda - \lambda_o$
$t = \tan\phi$
ρ = radius of curvature of *Meridian* (metres)

$$\rho = \frac{a\left(1-e^2\right)}{\left(1-e^2\sin^2\phi\right)^{3/2}}$$

ν = radius of curvature at right angles to *Meridian* (metres)

$$\nu = \frac{a}{\left(1-e^2\sin^2\phi\right)^{1/2}}$$

$$\eta^2 = \frac{\nu}{\rho} - 1 = \frac{e^2\cos^2\phi}{\left(1-e^2\right)}$$

S_ϕ = length of *Meridian* arc from *Equator* to *Latitude* ϕ (metres)

$$\theta = \frac{S_\phi}{b(1+n)\left(1+\frac{5n^2}{4}+\frac{81n^4}{4}\right)}$$

ϕ_1 = 'footpoint' *Latitude*
t_1 = variable, defined above, corresponding to ϕ_1
ρ_1 = variable, defined above, corresponding to ϕ_1
ν_1 = variable, defined above, corresponding to ϕ_1
η_1 = variable, defined above, corresponding to ϕ_1
E = *Grid Easting* (metres)
N = *Grid Northing* (metres)
FE = *False Easting* of True *Grid Origin*
FN = *False Northing* of True *Grid Origin*
E′ = *True Easting*
and: E′ = E − FE (points East of *Central Meridian*)
or: E′ = FE − E (points West of *Central Meridian*)
N′ = *True Northing*
N′ = N − FN
k_o = *Scale Factor* on *Central Meridian* (= 0.9996 for *UTM*)

(8) b. **To Find the Length of the Meridional Arc Given the Latitude.** The length of the *Meridional Arc* is set out in formula (A5.8d) at Appendix 5 Para 6, but is repeated here for convenience, in a slightly different form as formula (A4.14a).

$$S_\phi = a(1-e^2)\left[-\frac{35}{3072}e^6 \ \sin\ 6\phi + \left(\frac{15e^4}{256}+\frac{105e^6}{1024}\right)\ \sin\ 4\phi \right.$$
$$\left. -\left(\frac{3e^2}{8}+\frac{15e^4}{32}+\frac{525e^6}{1024}\right)\ \sin\ 2\phi \ + \left(1+\frac{3e^2}{4}+\frac{45e^4}{64}+\frac{175e^6}{256}\right)\phi \right] \quad \ldots \textbf{A4.14a}$$

c. **To Find the 'Footpoint' Latitude, Given the True Grid Coordinates.** If S_o is the length of the *Meridian* arc from the *Equator* to the true *Grid Origin*, then:

$$S_{\phi 1} = S_o \pm \frac{N'}{k_o}(+\ in\ N\ hemisphere,\ -\ in\ S\ hemisphere)$$

And where ϕ_1 is the *Latitude* of the foot of the perpendicular drawn from a point on the *Projection* to the *Central Meridian*, ϕ_1 can be found from $S_{\phi 1}$ using the formula:

$$\phi_1 = \frac{8011}{2560}n^5\ \sin\ 10\theta_1 + \frac{1097n^4}{512}\ \sin\ 8\theta_1 + \left(\frac{151n^3}{96}-\frac{417n^5}{128}\right)\ \sin\ 6\theta_1$$
$$+\left(\frac{21n^2}{16}-\frac{55n^4}{32}\right)\ \sin\ 4\theta_1 + \left(\frac{3n}{2}-\frac{27n^3}{32}+\frac{269n^5}{512}\right)\ \sin\ 2\theta_1 + \theta_1 \quad \ldots \textbf{A4.14}$$

d. **To Convert From Geographical to Grid Coordinates.** If an accuracy of ± 0.01 metre is acceptable, terms containing $\Delta\lambda^6$ and higher powers of $\Delta\lambda$ may be ignored.

$$\frac{E'}{k_o\nu} = \Delta\lambda\ \cos\ \phi + \frac{\Delta\lambda^3\cos^3\phi}{6}\left(1-t^2+\eta^2\right)+\frac{\Delta\lambda^5\ \cos^5\phi}{120}\left(5-18t^2+t^4+14\eta^2-58t^2\eta^2\right)$$
$$+\frac{\Delta\lambda^7\ \cos^7\phi}{5040}\left(61-479t^2+179t^4-t^6\right) \quad \ldots \textbf{A4.15}$$

And:

$$\frac{N'}{k_o n} = \frac{S_\phi}{n}+\frac{\Delta\lambda^2}{2}\ \sin\ \phi\ \cos\ \phi + \frac{\Delta\lambda^4}{24}\ \sin\ \phi\ \cos^3\phi\left(5-t^2+9\eta^2+4\eta^4\right)$$
$$+\frac{\Delta\lambda^6}{720}\ \sin\ \phi\ \cos^5\ \phi\left(61-58t^2+t^4+270\eta^2-330t^2\eta^2\right)$$
$$+\frac{\Delta\lambda^8}{40320}\ \sin\phi\ \cos^7\phi\left(1385-3111t^2+543t^4-t^6\right) \quad \ldots \textbf{A4.16}$$

e. **To Convert From Grid to Geographical Coordinates.** If an accuracy of ± 0.001" is acceptable, terms containing $(E')^7$ and higher powers of E' may be ignored.

$$\frac{\phi}{t_1} = \frac{\phi_1}{t_1} - \frac{(E')^2}{2k_o^{\ 2}\rho_1\nu_1} + \frac{(E')^4}{24k_o^{\ 4}\rho_1\nu_1^{\ 3}}\left(5+3t_1^{\ 2}+\eta_1^{\ 2}-9t_1^{\ 2}\eta_1^{\ 2}-4\eta_1^{\ 4}\right)$$
$$-\frac{(E')^6}{720k_o^{\ 6}\rho_1\nu_1^{\ 5}}\left(61+90t_1^{\ 2}+45t_1^{\ 4}+46\eta_1^{\ 2}-252t_1^{\ 2}\eta_1^{\ 2}-90t_1^{\ 4}\eta_1^{\ 2}\right)$$
$$+\frac{(E^1)^8}{40320k_0^{\ 8}\rho_1\nu_1^{\ 7}}\left(1385+3633t_1^{\ 2}+4095t_1^{\ 4}+1575t_1^{\ 6}\right) \quad \ldots \textbf{A4.17}$$

And:

$$\Delta\lambda\ \cos\phi_1 = \frac{E'}{k_0\nu_1} - \frac{(E')^3}{6k_0^{\ 3}\nu_1^{\ 3}}\left(1+2t_1^{\ 2}+\eta_1^{\ 2}\right)+\frac{(E')^5}{120k_0^{\ 5}\nu^5}\left(5+28t_1^{\ 2}+24t_1^{\ 4}+6\eta_1^{\ 2}+8t_1^{\ 2}\eta_1^{\ 2}\right)$$
$$-\frac{(E')^7}{5040k_0^{\ 7}\nu_1^{\ 7}}\left(61+662t_1^{\ 2}+1320t_1^{\ 4}+720t_1^{\ 6}\right) \quad \ldots \textbf{A4.18}$$

APPENDIX 5

THE SPHEROIDAL EARTH

1. Scope of Appendix

Appendix 5 contains the following information for the *Spheroidal* Earth:

- **Para 2: The Equation of the Ellipse.**
- **Para 3: Geodetic Latitude, Geocentric Latitude & Parametric Latitude.**
- **Para 4: The length of the Earth's radius in various Latitudes.**
- **Para 5: The length of one minute of Latitude - The Sea Mile.**
- **Para 6: The Length of the Spheroidal Meridional Arc.**
- **Para 7: Meridional Parts for the Spheroidal Earth.**

2. The Equation of the Ellipse

When a point *M* (see Fig A5-1 below) moves so that its distance from a fixed point *S* (the focus) is always in a constant ratio *e* (less than unity) to its perpendicular distance from a fixed straight line *AB* (the directrix), the locus of *M* is called an ellipse of *Eccentricity (e)*. The *Equation of the Ellipse* takes its simplest form when the co-ordinates of *S* are ($-ae$, 0) and the directrix *AB* is the line:

$$x = -\frac{a}{e}$$



Fig A5-1. The Ellipse

From Fig A5.1: $MS = eMC$ and $MC = x + \frac{a}{e}$

$$(MS)^2 = y^2 + (x + ae)^2$$

$$\therefore\ e^2\left(x + \frac{a}{e}\right)^2 = (x + ae)^2 + y^2$$

ie $(1 - e^2)x^2 + y^2 = a^2(1 - e^2)$

This may be written in the form:

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1 \qquad \text{. . . \textbf{A5.1}}$$

(2 continued)

where: $$b^2 = a^2(1 - e^2) \qquad \text{. . . } \mathbf{A5.2}$$

ie $$e = \left(\frac{a^2 - b^2}{a^2}\right)^{1/2} \qquad \text{. . . (formula 3.2)}$$

The ellipse corresponds to a cross-section of the Earth, where *a* is the *Equatorial* and *b* the *Polar* radius. As *b* is less than *a*, the Earth is 'flattened' in the *Polar* regions.

The *Flattening* or ellipticity of the Earth may be defined by a quantity *f* where:

$$f = \frac{a - b}{a} \qquad \text{. . .(formula 3.1)}$$

From formulae (3.1) and (3.2):

$$e = \left(2f - f^2\right)^{1/2} \qquad \text{. . . (formula 3.3)}$$

The quantities *a, e* and *f* are used regularly in the solution of *Rhumb Line* and *Great Circle* sailing problems on the *Spheroid.*

3. Geodetic Latitude, Geocentric Latitude and Parametric Latitude

a. **Geodetic Latitude and Geocentric Latitude.** As stated at Para 0312 and shown in Fig A5-2 (below), ϕ is the *Geodetic Latitude* and θ is the *Geocentric Latitude* of *M*.



Fig A5-2. Geodetic Latitude and Geocentric Latitude

In Fig A5-2 (above), if the distance of the point *M* from the *Polar* axis *OP* is *x*, and its distance from the major axis *OA* is *y*, these distances or co-ordinates are connected by the *Equation of the Ellipse* on which *M* lies, ie:

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1 \qquad \text{. . . (formula A5.1)}$$

(3 continued)

Thus:
$$\frac{y^2}{b^2} = 1 - \frac{x^2}{a^2}$$
$$y^2 = b^2 - \frac{x^2 b^2}{a^2}$$

By differentiation:
$$2y\frac{dy}{dx} = -2x\frac{b^2}{a^2}$$
$$\frac{dy}{dx} = -\frac{x}{y}\frac{b^2}{a^2}$$

If ψ is the angle which the tangent *MK* makes with the X-axis, then, since the slope of the tangent is measured by the differential coefficient:
$$\tan\psi = \frac{dy}{dx} = -\frac{b^2}{a^2}\frac{x}{y}$$

But ψ is equal to (ϕ + 90˚) since *ML* is perpendicular to *MK*:

Hence:
$$\tan\psi = -\cot\phi$$
$$\therefore \cot\phi = \frac{b^2}{a^2}\frac{x}{y} \qquad \text{. . . \textbf{A5.3}}$$
$$= \frac{b^2}{a^2}\cot\theta$$

But ϕ and θ are connected by formulae (3.4), (3.5) and (3.6):
$$\tan\theta = \frac{b^2}{a^2}\tan\phi \qquad \text{. . . (formula 3.4)}$$
$$= (1-f)^2 \tan\phi \qquad \text{. . . (formula 3.5)}$$
$$= (1-e^2)\tan\phi \qquad \text{. . . (formula 3.6)}$$

The difference between the *Geodetic Latitude* and *Geocentric Latitude* is zero at the *Equator* and the *Poles* and has a greatest value when ϕ = 45˚.

For the *WGS 84 Spheroid*, where *f* = 1/298.257223563, the greatest value of the angle *OML* $(\phi - \theta)$ is approximately 11.54 minutes of arc (see Para 0312d).

(3) b. **The Parametric Latitude.** As stated at Para 0313 and shown in Fig A5-3 (below), β is the *Parametric Latitude* of *M*.



Fig A5-3. Parametric Latitude

If the co-ordinates of *M* are (*x, y*) and *WBE* is a semi-circle of radius *a*, centre *O*.

$$OH = OU\cos\beta$$

ie $$x = a\cos\beta$$

But: $$\frac{y^2}{b^2} = 1 - \frac{x^2}{a^2} = 1 - \cos^2\beta$$ from . . . (formula A5.1)

$$y^2 = b^2\left(1 - \cos^2\beta\right) = b^2\sin^2\beta$$

$$y = b\sin\beta$$

$$\therefore \frac{y}{x} = \frac{b}{a}\tan\beta$$

From Fig A5-2: $$\frac{y}{x} = \tan\theta$$

And, $$\frac{x}{y} = \frac{b^2}{a^2}\tan\phi$$ from . . . (formula 3.4)

$$\therefore \tan\beta = \frac{b}{a}\tan\phi$$ . . . (formula 3.7)

$$= \left(1 - f\right)\tan\phi$$ . . . **A5.5**

The difference between the *Geodetic Latitude* and *Parametric Latitude* is zero at the *Equator* and at the *Poles* and has a greatest value when $\phi = 45^\circ$.

For the *WGS 84 Spheroid*, where f = 1/298.257223563, the greatest value is approximately 5.85 minutes of arc (see Para 0313b).

4. The Length of the Earth's Radius in Various Latitudes

In Fig A5-2 (see Para 3a), the required *Geocentric* radius is *OM* and, if this length is denoted by *R*, it follows that $x = R\cos\theta$ and $y = R\sin\theta$. Hence, by substituting for *x* and *y* in the equation of the ellipse:

$$\frac{R^2\cos^2\theta}{a^2} + \frac{R^2\sin^2\theta}{b^2} = 1$$

But, as: $b^2 = a^2(1-f)^2$ then:

$$R^2\left[(1-f)^2\cos^2\theta + \sin^2\theta\right] = a^2(1-f)^2$$

When terms in f^2 (10^{-5} x 1.1) are neglected, this equation becomes:

$$R^2\left(1-2f\cos^2\theta\right) = a^2(1-2f)$$

$$R = a\left(\frac{1-2f}{1-2f\cos^2\theta}\right)^{1/2}$$

When the right-hand side is expanded by the binomial theorem, terms in f^2 and higher powers again being omitted, the equation becomes:

$$R = a(1-f)\left(1+f\cos^2\theta\right)$$

$$= a\left(1-f\sin^2\theta\right)$$

Since θ varies from ϕ by a small quantity, *R* may be expressed in terms of the *Geodetic Latitude* (Para 3a) without appreciable error by direct substitution:

$$R = a\left(1-f\sin^2\phi\right) \qquad \textbf{. . . A5.13}$$

5. The Length of One Minute of Latitude - The Sea Mile

The length of the *Sea Mile* (one minute of *Latitude* on the *Spheroid*) may be found from the general formula $\rho d\phi$ (see Fig A5-4 below) where ρ is the radius of curvature in the *Meridian* and $d\phi$ a small increase (in radians) in the *Geodetic Latitude* ϕ.


Note: Position 'C' is the centre of a circle and arc 'ρdø' is part of its circumference. Thus on the Spheroid (Ellipsoid), the position of 'C' will move relative to 'O' as arc 'ρdø' moves over the surface of the Spheroid.
P
ρdø
M
dø
ρ
ø
W
O
E
C
Geodetic Lat Ø
P1

Fig A5-4. The Length of One Minute of Latitude (1)

Fig A5-5 (below) shows an expanded version of Fig A5-4, where $d\phi$ is a very small increase in ϕ. The co-ordinates of *M* are (*x, y*); those of M_1, representing this small increase, are $(x - dx)$, $(y + dy)$.


M1(x-dx, y+dy)
Ø
dℓ
dy
M(x,y)
Q
dx
dØ
Ø
O
C
Geodetic Lat Ø

Fig A5-5. The Length of One Minute of Latitude (2)

(5 continued)

The triangle MQM_1 (see Fig A5-5 opposite) may be considered plane and, if the length of MM_1 is denoted by dℓ then:

$$\frac{d\ell}{dx} = -\frac{1}{\sin\phi}$$

But, as: $d\ell = \rho d\phi$

$$\frac{d\ell}{d\phi} = \rho \quad = \frac{dx}{d\phi} \text{x} \frac{d\ell}{dx}$$

$$\therefore \rho = -\frac{1}{\sin\phi} \text{x} \frac{dx}{d\phi}$$ ... **A5.6**

$\frac{dx}{d\phi}$ may be found as follows:

$$y = \frac{xb^2}{a^2}\tan\phi$$ from ... (formula A5.3)

Thus: $= x\left(1 - e^2\right)\tan\phi$ from ... (formula A5.2)

If this value of *y* is substituted in the general *Equation of the Ellipse* formula (A5.1) and the value of *b* from formula (A5.2) also substituted, then:

$$\frac{x^2}{a^2} + \frac{x^2\left(1 - e^2\right)^2 \tan^2\phi}{a^2\left(1 - e^2\right)} = 1$$

$$x^2 + \left(1 - e^2\right)x^2\tan^2\phi = a^2 \quad = x^2\left(1 + \tan^2\phi - e^2\tan^2\phi\right) = x^2\left(\sec^2\phi - e^2\tan^2\phi\right)$$

$$x^2\left[\frac{1}{\cos^2\phi} - \frac{e^2\sin^2\phi}{\cos^2\phi}\right] = a^2$$

$$x = \frac{a \cos\phi}{\left(1 - e^2\sin^2\phi\right)^{1/2}}$$

$$= a \cos\phi\left(1 - e^2\sin^2\phi\right)^{-1/2}$$ ... **A5.7**

Differentiating:

$$\frac{dx}{df} = \frac{-a\left(1 - e^2\right)\sin\phi}{\left(1 - e^2\sin^2\phi\right)^{3/2}}$$

Substituting in formula (A5.6):

$$\rho = \frac{a\left(1 - e^2\right)}{\left(1 - e^2\sin^2\phi\right)^{3/2}}$$ ... (formula 3.8)

Thus, when $d\phi$ equals 1' of arc:

$$1' \; of \; Latitude = \frac{a\left(1 - e^2\right)}{\left(1 - e^2\sin^2\phi\right)^{3/2}} \sin 1'$$ ... (formula 3.9)

(5 continued)

Formula (3.9) is the theoretical expression for the *Sea Mile*. The expression may be expanded as follows:

$$1'\ of\ Latitude = a\sin 1'(1-e^2)\left(1+\frac{3e^2}{2}\sin^2\phi+\frac{15e^4}{8}\sin^4\phi+\ldots\right)$$

Approximating by disregarding terms of e^4 (10^{-5} x 4.5) and higher powers:

$$\begin{aligned}1'\ of\ Latitude &= a\ \sin\ 1'\left(1+\frac{3e^2}{2}\sin^2\phi-e^2\right)\\ &= a\ \sin\ 1'\left[1-e^2+\frac{3e^2}{4}\left(1-\cos\ 2\phi\right)\right]\\ &= a\ \sin\ 1'\left(1-\frac{e^2}{4}-\frac{3e^2}{4}\cos\ 2\phi\right)\\ &= a\ \sin\ 1'\left[1-\frac{e^2}{4}\left(1+3\ \cos\ 2\phi\right)\right]\end{aligned}$$

When figures for *a* and *e* for the *WGS 84 Spheroid* are given:

$1'\ of\ Latitude = 1852.22 - 9.315\cos 2\phi$ *(metres)* . . . **A5.8**

Or: $1'\ of\ Latitude = 1.00012 - 0.00503\cos 2\phi$ *(n. miles)* . . . **A5.8**

$\therefore$ $1'\ of\ Latitude = 1852.22$ *(metres) or* 1.00012 (*n.miles*) *(at Latitude 45°)*

Compared to the precise formula (3.9), this approximation gives a solution for the *Sea Mile* which is correct (for *WGS 84 Spheroid*) at the *Equator*, is 0.00127% in error at *Latitude* 45° and is 0.00169% in error at Latitude 90°.

6. The Length of the Spheroidal Meridional Arc

In Fig A5-6 (below), where ϕ is the *Geodetic Latitude* and ρ the radius of curvature in the *Meridian*, the length R of the *Meridional Arc EM* may be found from formula (A5.8a):

$$\ell = \int_0^{\phi}\rho\,d\phi \qquad \text{. . . \textbf{A5.8a (1987 Ed . . . 5.17)}}$$

The value of ρ is given in formula (3.8) at Para 0314.



Fig A5-6. The Length of the Spheroidal Meridional Arc (Copy of Fig 5-6)

(6 continued)

Following from Fig A5.6 (opposite) and formula (A5.8a), the *Meridional Arc* length ℓ along a *Meridian* between two *Geodetic Latitudes* ϕ_1 and ϕ_2 may be found from formula (A5.8b):

$$\ell = \int_{\phi 1}^{\phi 2} \rho d\phi \qquad \text{. . . A5.8b}$$

$$= a\left(1 - e^2\right)\int_{\phi 1}^{\phi 2} \frac{1}{\left(1 - e^2 sin^2 \phi\right)^{3/2}} d\phi \qquad \text{. . . A5.8c (1987 Ed . . . 5.18)}$$

Expanding by the binomial theorem:

$$= a\left(1 - e^2\right)\int_{\phi 1}^{\phi 2}\left(1 + \frac{3e^2}{2} sin^2 \phi + \frac{15e^4}{8} sin^4 \phi + \frac{35e^6}{16} sin^6 \phi + ...\right) d\phi$$

Each term in the integral may now be integrated separately where:

$$\int sin^2 \phi \, d\phi = \int \left(½ - ½ \ cos \ 2\phi\right) d\phi \ = \frac{\phi}{2} - \frac{sin \ 2\phi}{4} + c$$

$$\int sin^4 \ \phi \ d\phi = \int \left(\frac{3}{8} - \frac{cos \ 2\phi}{2} + \frac{cos \ 4\phi}{8}\right) d\phi \ = \frac{3\phi}{8} - \frac{sin \ 2\phi}{4} + \frac{sin \ 4\phi}{32} + c$$

$$\int sin^6 \phi \ d\phi = \left(\frac{10}{32} - \frac{15 \ cos \ 2\phi}{32} + \frac{3 \ cos \ 4\phi}{16} - \frac{cos \ 6\phi}{32}\right) d\phi$$

$$= \frac{10\phi}{32} - \frac{15 \ sin \ 2\phi}{64} + \frac{3 \ sin \ 4\phi}{64} - \frac{sin \ 6\phi}{192} + c \qquad \text{etc, etc.}$$

Thus:

$$\ell = a\left(1 - e^2\right)\Bigg[\phi + \frac{3e^2}{2}\left(\frac{\phi}{2} - \frac{sin \ 2\phi}{4}\right) + \frac{15e^4}{8}\left(\frac{3\phi}{8} - \frac{sin \ 2\phi}{4} + \frac{sin \ 4\phi}{32}\right)$$
$$+ \frac{35e^6}{16}\left(\frac{10\phi}{32} - \frac{15sin2\phi}{64} + \frac{3sin4\phi}{64} - \frac{sin6\phi}{192}\right) + ... \Bigg]_{\phi 1}^{\phi 2} \qquad \text{. . . A5.8d}$$

The *Meridional Arc* length ℓ may be determined from formula (A5.8e) for any *Spheroid* of known *Equatorial* semi-major axis a and *Eccentricity* e (see Para 0322, Table 3-1), and expressed, dependent on what unit is used for a (metres, *International Nautical Miles* etc).

$$\ell \ = \int_O^{\phi} \rho df \ = a\left(A_O \phi - A_2 sin2\phi + A_4 sin4\phi - A_6 sin6\phi + ...\right)$$

. . . A5.8e (1987 Ed . . . 5.19)

This may be expanded in the form:

$$\ell = a\left[A_o \phi - A_2 sin2\phi + A_4 sin4\phi - A_6 sin6\phi + ...\right]_{\phi 1}^{\phi 2} \qquad \text{. . . A5.8f}$$

Thus:

$$\ell = a\Big[A_o\left(\phi_2 - \phi_1\right) - A_2\left(sin2\phi_2 - sin2\phi_1\right)$$
$$+ A_4\left(sin4\phi_2 - sin4\phi_1\right) - A_6\left(sin6\phi_2 - sin6\phi_1\right) + ... \ \Big] \text{. . . A5.9}$$

Where, ϕ is measured in radians and A_0, A_2, A_4, A_6 are given by:

$$A_o = 1 - \frac{1}{4}e^2 - \frac{3}{64}e^4 - \frac{5}{256}e^6 - ...$$

(6 continued)

$$A_2 = \frac{3}{8}\left(e^2 + \frac{1}{4}e^4 + \frac{15}{128}e^6 + \ldots\right)$$

$$A_4 = \frac{15}{256}\left(e^4 + \frac{3}{4}e^6 + \ldots\right)$$

$$A_6 = \frac{35}{3072}e^6 + \ldots$$

Formula (A5.9) [previous page] is large and complex, and ideally a computer is needed to calculate the *Meridional Arc* distance ℓ. However, the *Meridional Arc* distance ℓ may be calculated to a reasonably high degree of accuracy by disregarding terms of e^6(10^{-7} x 3.1) and higher powers. With this approximation, the *Meridional Arc* distance ℓ from the *Equator* to *Latitude* ϕ may be found from formula (5.24):

$$\ell = a\left[\phi - \frac{e^2\phi}{4} - \frac{3e^2}{8}sin2\phi - \frac{3e^4}{64}\phi - \frac{3e^4}{32}\ sin\ 2\phi + \frac{15e^4}{256}\ sin\ 4\phi\right]$$

. . . (formula 5.24)

Tables giving the length of the *Meridional Arc* for any *Latitude* (eg at minute of arc intervals) may be constructed by computer from the general formula (A5.8e). Tables may be computed for any *Spheroid* and may be expressed in the same units of distance used for *a*. The length of the *Meridional Arc* between the two different *Latitudes* can then be obtained, and the course and distance calculated between two positions using formulae (5.22) and (5.23). Conversely, if the course, distance and initial positions are known, the final *Latitude* may be computed from the length of the *Meridional Arc* and the final *Longitude* from the difference of *Meridional Parts*.

An error can arise from the assumption that a distance in *International Nautical Miles* (n miles) can be said to equate to a *d.lat* measured in minutes of arc or *Sea Miles*. The maximum error in this assumption is of the order of 0.5%. For most purposes, little account need be taken of this difference between the n mile and the *Sea Mile* except when precise distances are required, particularly near the *Equator* or the *Poles*.

7. Meridional Parts for the Spheroidal Earth

Tables of *Meridional Parts* used by cartographers to compute the *Graticules* for *Mercator Projection* charts must be for *Spheroidal Meridional Parts*. Astronomical observations at sea are made with reference to a horizon which is part of the *Spheroidal* surface of the Earth; thus, tables of *Spheroidal Meridional Parts* are consistent with the co-ordinates of positions found from astronomical observations.

In Fig A5-7 (below), where $x = a \cos \beta$ and $y = b \sin \beta$, the elliptic *Meridional* section of the Earth may be expressed by the equation:

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$



Fig A5-7. Meridional Section of the Spheroidal Earth

At a point *M* which has co-ordinates (*x, y*) with reference to *O*, the centre of the ellipse, let the *Geographic Latitude* be ϕ. If the radius of curvature at *M* is ρ, the length of an element of the *Meridian* is $\rho d\phi$.

In order to measure the *Meridional Parts* of ϕ, the *Meridional Element* $\rho d\phi$ must be expressed in terms of the length of 1 minute of *Longitude* at *Latitude* ϕ. The *Longitude Scale* for this *Latitude* is *x/a* times the *Longitude Scale* at the *Equator*, and the unit of *Longitude* at the *Equator* is the length of that *Equatorial Element* which subtends an angle of 1 minute of arc at the centre of the Earth. The length of this element is *a* divided by the number of minutes in 1 radian, that is: $\frac{a\pi}{10800}$

The length of a minute of *Longitude* at *Latitude* ϕ is thus:

$$\frac{x}{a} \times \frac{a\pi}{10800} \quad \text{or} \quad \frac{x\pi}{10800}$$

(7 continued)

And, the number of *Longitude* units in the *Meridional Element* $\rho d\phi$ is:

$$\rho d\phi \div \frac{x\pi}{10800} \quad \text{or} \quad \frac{10800}{\pi} \text{ x } \frac{\rho}{x} d\phi$$

The *Meridional Parts* at *Latitude L* are given by the equation:

$$Mer\ Parts\ L = \frac{10800}{\pi} \int_{O}^{L} \frac{\rho}{x} d\phi$$

Which, from formulae (3.8) and (A5.7):

$$Mer\ Parts\ L = \frac{10800}{\pi} \int_{O}^{L} \frac{a(1-e^{2})}{(1-e^{2}\sin^{2}\phi)^{3/2}} \text{ x } \frac{1}{a\ \cos\ \phi(1-e^{2}\sin^{2}\phi)^{-1/2}} d\phi$$

$$= \frac{10800}{\pi} \int_{O}^{L} \sec\phi \left(\frac{1-e^{2}}{1-e^{2}\sin^{2}\phi} \right) d\phi \qquad \text{. . . } \mathbf{A5.11}$$

$$Mer\ Parts\ L = \frac{10800}{\pi} \int_{O}^{L} \sec\phi \left[1 - e^{2}\cos^{2}\phi \left(1 + e^{2}\sin^{2}\phi + e^{4}\sin^{4}\phi + e^{6}\sin^{6}\phi + \ldots \right) \right] d\phi$$

$$Mer\ Parts\ L = \frac{10800}{\pi} \int_{O}^{L} \left(\sec\phi - e^{2}\cos\phi - e^{4}\sin^{2}\phi\cos\phi - e^{6}\sin^{4}\phi\cos\phi - \ldots \right) d\phi$$

$$Mer\ Parts\ L = \frac{10800}{\pi} \left[\log_{e}\ \tan\left(45^{\circ} + \frac{L^{\circ}}{2} \right) - e^{2}\sin L - \frac{1}{3}e^{4}\sin^{3}L - \frac{1}{5}e^{6}\sin^{5}L - \ldots \right]$$

. . . (formula 5.21a)

From formula (5.21a), a simplified numerical formula (ignoring e^6 and higher powers) for the *WGS 84 Spheroid*, giving the *Meridional Parts* '*m*' correct to three decimal places is:

$$Mer\ Pats\ L = 7915.7045\log_{10}\tan\left(45^{\circ} + \frac{L^{\circ}}{2} \right) - 23.01358\ \sin\ L - 0.05135\ \sin^{3}L$$

. . . (formula 5.21b)

APPENDIX 6

VERTICAL AND HORIZONTAL SEXTANT ANGLES

1. Scope of Appendix

Appendix 6 contains the following information:

- **Para 2: Vertical Sextant Angles (VSAs).**
- **Para 3: Horizontal Sextant Angles (HSAs).**

2. Vertical Sextant Angles (VSAs)

a. **Base of the Object Visible to the Observer.** As stated at Para 0803h, a *Position Line* may be obtained from the observation of the *Vertical Sextant Angle* (*VSA*) of an object (eg 10 foot pole, lighthouse etc) whose base is visible to the observer, by multiplying the known height of the object by the 'cot' of the observed angle.

Distance = Visible Height of Object x *Cot (Observed Angle)* . . . (formula 8.1)

A table of 'Distance by Vertical Angle' for ranges up to 7 *n. miles* is provided in Norie's Nautical Tables, for objects whose base is visible to the observer. At such short ranges, the effect of *Atmospheric Refraction* is ignored.

b. **Base of the Object Beyond the Observer's Horizon.** A *Position Line* may also be obtained from the observation of the *VSA* of an object (eg distant mountain peak) where the base is out of sight beyond the observer's horizon, but the calculation is more complex, and some approximations are necessary.

Parameters. At Fig A6-1 (overleaf), the following parameters are established:

- *C* is the *Centre of Curvature* of the Earth, with a local *Radius of Curvature R*.
- *AD* is the height of eye *h*.
- *B* is a mountain summit whose height *BE* is *H* above the prevailing sea level.
- *DE* is the required distance *d*, while the angle measured between the mountain top and the observer's horizon is represented by the angle *JAF*.

Terrestrial Atmospheric Refraction. The angle *JAF* takes account of the terrestrial *Atmospheric Refraction r*, which 'bends' the ray of light as it proceeds through the atmosphere between object and observer. Thus, the top of the mountain *B* is seen in the direction *AJ*, while the horizon *G* is seen in the direction *AF*. These two lines *AJ* and *AF* are tangential to their respective curved rays of light (shown as pecked lines in Fig A6-1). At long range with high objects, terrestrial *Atmospheric Refraction* amounts to approximately 8% of the distance in *n.miles* of the object, expressed in minutes of arc; thus an initial approximate estimate of distance is required.

Dip. AK is the horizontal at the observer's position and the angle *KAF* is known as the *Angle of Dip* (*Dip*), defined as the angle between the horizontal plane through the eye of the observer and the apparent visible horizon. It is always present when the observer's eye is above sea level. *Dip* is tabulated in the Nautical Almanac and in Norie's Tables. *Dip* and *Atmospheric Refraction* are explained fully in BR 45 Volume 2 Chapter 8; both must be subtracted from the *Observed Altitude* of the object to obtain its *True Altitude*.

(2b continued)



Fig A6-1. Position Line by Vertical Sextant Angle – Base of the Object Beyond Horizon(1)

Explanation. The apparent altitude of *B* as measured from the sea horizon, when reduced by *Dip*, is the angle *JAK*, α. The *True Altitude* of *B*, the angle *BAK*, is (α – *r*), where *r* is the amount of *Atmospheric Refraction JAB*.

Earth's Radius. The *Radius of Curvature* of the Earth varies slightly with both *Latitude* and the *Azimuth* of the cross-section concerned. However, for most practical purposes it is sufficiently accurate to use a fixed *Radius of Curvature* of 3437.75 *n. miles;* this may result in a distance error which should not exceed 0.32%. The calculated distance *d* would then be expressed directly in *n. miles*, regardless of *Latitude* or *Azimuth*.

Calculation. At Fig A6-1 (above) and at Fig A6-2 (opposite) in the triangle *CAB*:

$$CA = R + h$$

$$CB = R + H$$

$$CAB = 90° + \alpha - r$$

$$CBA = 180° - (d + 90° + \alpha - r) = 90° - d - \alpha + r$$

$$\frac{\sin\ CBA}{\sin\ CAB} = \frac{R+h}{R+H} = \frac{\sin\ 90° - (d + \alpha - r)}{\sin\ 90° + (\alpha - r)} = \frac{\cos\ (d + \alpha - r)}{\cos\ (\alpha - r)}$$

$$\cos\ (d + \alpha - r) = \frac{R+h}{R+H}\ \cos\ (\alpha - r) \qquad \text{. . A6.1}$$

Distance *d* may be found from formula (A6.1): see Example A6-1 (opposite). If the estimated distance is too much in error, a second approximation will be necessary.

(2b continued)



Fig A6-2. Position Line by Vertical Sextant Angle − Base of the Object Beyond Horizon(2)

Example A6-1. A mountain 1646 m (5400 ft) high is observed at a range of about 25 *n.miles*. The observer's height of eye is 7.6 m (25 ft). The *VSA* of the summit is 1˚59'.3. *Index Error* of the sextant is -1'.3. What is the range of the mountain?

Observed angle	1˚59.3	
Index error	-1'.3	
	1˚58'.0	
Dip	-4'.9	
Apparent Altitude (α)	1˚53'.1	
Refraction correction (r) (8% of 25 = 2.0)	-2'.0	
True altitude (α - r)	1˚51'.1	(1.8517˚)

R = 3437.75 *n. miles*
H = 0.8888 *n. miles*
h = 0.0041 *n. miles*

$$\cos\left(d + 1.8517°\right) = \frac{3437.7541}{3438.6388} \cos\ 1.8517°$$ . . . (formula A6.1)

$$d = 2.2621° - 1.8517° = 0.4104° = 24.6\ \text{n. miles}$$

Effect of Abnormal Refraction on Accuracy of Calculation. Long-range *Position Line*s obtained in this way are of little value if *Abnormal Refraction* is suspected (see BR 45 Volume 2 Chapter 8). *Abnormal Refraction* is likely to be present when the temperature of the water and that of air differ considerably.

CAUTION

PRACTICAL USE. This method of obtaining a *Position Line* has a limited application and while useful in giving a reasonably satisfactory long-range *Position Line* on a single isolated peak (eg Mount Teide at Tenerife in the Canaries), it should ALWAYS be used with PARTICULAR CAUTION, and should NOT be used with a mountain peak which forms part of a mountain chain unless it has been positively identified.

3. Horizontal Sextant Angles (HSAs)

a. **Rapid Plotting Without Instruments - HSA Lattice.** To enable *Fixes* obtained by *Horizontal Sextant Angle*s (*HSAs*) to be plotted rapidly without instruments, a lattice of *HSA* curves (*HSA Lattice*) may be constructed on a chart. Each curve gives the constant angle between a pair of suitably placed *Fixing* marks, and is an arc of a circle. If a set of curves is plotted for each of two pairs of marks, then, having observed the angle between each pair simultaneously, the observer can plot the resultant *Fix* immediately at the intersection of the two curves corresponding to the two angles. A sufficient number of curves must be drawn to enable the observed angles to be plotted conveniently by interpolation between the *HSA Lattice* lines.

b. **Preparation of an HSA Lattice.** The preparation of an *HSA Lattice* is illustrated at Fig A6-3 (opposite). At Fig A6-3, consider the pattern of arcs which may be generated from one pair of objects *A* and *B*. Three arcs are shown: *AEB, ADB, ACB*. Their centres *O*, *P, Q* respectively, all lie along the perpendicular bisector *FQ* of the base line *AB*. Then, consider one arc *AEB*. Let *QO* (the distance of the centre of the arc from the base line) be x, where d is the length of the base line and θ is the angle subtended by the chord *AB* on the circumference of the circle through *AEB*.

Thus: $x = ½d \cot \theta$ . . . **A6.2**

Formula (A6.2) may now be used to construct the lattice for all required angles.

c. **Fixing Objects Within the Boundaries of the Chart - Chart D6472.** Chart D6472 (Diagram for Facilitating the Construction of Curves of Equal Subtended Angles) is issued by *UKHO* and enables the observer to plot any lattice of *HSA* curves on any chart or plotting sheet, provided that all the *Fixing* objects lie within the boundaries of the chart. Full instructions as to how to use Chart D6472 are printed on it.

d. **Fixing Objects Outside the Boundaries of the Chart.** If the *Fixing* objects do not lie within the area of the chart, the following procedure will enable the observer to plot a customised *HSA Lattice*.

- Lay out on an appropriate space, such as the floor or deck, the chart or plotting sheet on which the *HSA Lattice* is required. Represent the *HSA* marks with pins placed in their correct relative positions.
- From the largest *Scale* navigational chart which shows the *Fixing* marks, measure, as accurately as possible, the distance between them. Convert these distances to the desired *Scale* of the *HSA Lattice* to obtain the distances between the pins on the floor. The simplest method for this *Scaling* up is to find a multiplication factor (eg if the navigational chart has a natural *Scale* of 1:50,000 and the *HSA Lattice* is to have a *Scale* of 1:10,000, then all chart lengths taken off the former must be multiplied by 5 [ie 50,000 / 10,000]. If two objects, *A* and *B*, are found to be 150 mm apart of the navigational chart, the pins should be placed 750 mm apart (ie 150 x 5) on the *HSA Lattice*).
- Measure the angle between the base lines (α in Fig A6-4 opposite) and lay this off on the floor. Measure the appropriate floor lengths and mark the position of the third object *C*. If the grid co-ordinates of the *Fixing* marks are known, the accuracy of all these measurements should be checked by calculation.


F
E
Y
θ
D
C
O
θ θ
P
x
Q
½d
½d
A
B
Z
Circle centred on O
Circle centred on P
Circle centred on Q
Angles above the baseline (ie at 'Y') represent HSAs of less than 90°
Angles below the baseline (ie at 'Z') represent HSAs of more than 90°

Fig A6-3. Pattern of Arcs Generated From One Pair of Objects


A
B
C
α
d1
d2
½d1 Cot θ
½d1 Cot β
½d2 Cot δ
½d2 Cot λ
Centres of Arcs for Angles θ and β
Centres of Arcs for Angles δ and λ
a
b
c
d
Angle θ
Angle δ
Angle λ
Angle β
Proposed Lattice Chart

Fig A6-4. Construction of an HSA Lattice

(3d continued)

- Next, the exact position on the floor for the *HSA Lattice* chart must be found. On the largest *Scale* navigational chart which shows both the *HSA Lattice* area and the *Fixing* marks, draw in the limits of the *HSA Lattice* chart. Measure the distances from each of the *Fixing* marks to all four corners of the *HSA Lattice* (*Aa, Ab, Ad, Ac, Ba, Bb,* etc). Scale up these distances by the appropriate multiplication factor, and then, by striking off arcs on the floor, *Fix* the positions of the corners of the *HSA Lattice*. Pin down the outline *HSA Lattice* chart in this position.

- On the floor, draw the base lines and their perpendicular bisectors. Where the floor surface is unsuitable for drawing, tightly stretched thread can be used.

- On the perpendicular bisectors of the base lines mark the centres of the arcs to be drawn ($\frac{1}{2}d \cot \theta$ from the base line). Strike off two arcs from each pair of objects giving an intersection at each end of the *HSA Lattice* area. As a check, compare for accuracy the geographical positions of the intersections thus obtained with *Fixes* plotted by *Station Pointer* using the same angles on a navigational chart which shows the objects and *HSA Lattice* area. This will reveal any inaccuracy in the construction of the *HSA Lattice*.

- Finally, complete the *HSA Lattice*, using red ink for the curves generated from the left-hand angles as viewed from seaward, and green for the right-hand angles. On large-scale *HSA Lattice*s, an alteration of firm and pecked lines in each pattern may improve the clarity of the *HSA Lattice*. If the curves do not cut at a satisfactory angle or are too widely spaced in any part of the chart, other objects can be taken and the curves generated from them drawn in the appropriate area, with colours other than red or green being used. The general form of the completed *HSA Lattice* is shown in Fig A6-5 (below).



Fig A6-5. Lattice of HSA Curves

APPENDIX 7

DOUBLING THE ANGLE ON THE BOW

1. Scope of Appendix

Appendix 7 contains *'Doubling the Angle on the Bow'* and the effect of *Current* and/or *Tidal Stream* on this technique.

2. Doubling the Angle on the Bow and Effect of Current / Tidal Stream

a. **Doubling the Angle on the Bow - Concept.** If a ship holds a steady course until the bearing of an object on its bow is doubled, the position at which this occurs forms an isosceles triangle with the first position and the object, and its distance from the object is equal to the run between the observations. If the ship experiences a *Current* or *Tidal Stream* in the meantime, an allowance must be made to avoid an error in the final position calculation. In practice, it will usually be more convenient to solve a problem of this type by plotting it on the chart and transferring the position lines as necessary. However, the following theory may be regarded as general.

b. **Doubling the Angle on the Bow in a Current / Tidal Stream.** In Fig A7-1 (below), *AB* is the course of the ship, and *BC* is the *Tidal Stream*. *AB* and *BC* combine to give the *Ground Track*, *AC*.



Fig A7-1. Doubling the Angle on the Bow in a Current / Tidal Stream

If *X* is some object observed from the ship, when the ship is at *A*, the angle on the bow is *XAB*, denoted by α. When the ship is at *C*, it is assumed for the purpose of this problem that the angle on the bow has been doubled. At this point the fore-and-aft line is in the direction *CE*, parallel to *AD*, and the angle *XCE* is thus 2α.

(2b continued)

EC produced meets *AX* in *F*. The angle *CFX* is therefore equal to the angle *CXF*, and *FC* is equal to *CX*. *CG* is drawn parallel to *XA*. The angle *CGB* is therefore equal to α, and, since *FAGC* is a parallelogram:

$$CX = AG = AB - GB$$

AB, the distance resulting from the ship's known speed and the duration of the run, can be found at once, but *GB* must be calculated from the triangle *GCB*.

Thus: $\dfrac{GB}{BC} = \dfrac{sin\ GCB}{sin\ BGC}$ And: $GB = BC\dfrac{sin\ GCB}{sin\ \alpha}$

If *BC* is denoted by *d* (the amount of *Drift* during the run) and the angle *CBD* by ϕ, the angle *GCB* is $(\phi - \alpha)$ and:

$$CX = AB - \frac{d\ sin(\phi - \alpha)}{sin\ \alpha} \ldots(\phi > \alpha)$$ **. . . A7.1a (1987 Ed . . . A7.8)**

If ϕ is less than α, *CX* is given by:

$$CX = AB + \frac{d\ sin(\alpha - \phi)}{sin\ \alpha}$$ **. . . A7.2a (1987 Ed . . . A7.9)**

These formulae are correct when the *Current* or *Tidal Stream* carries the ship to the same side as the object. However, when the *Current* or *Tidal Stream* carries the ship to the opposite side to the object, it can easily be shown that *CX* is given by:

$$CX = AB + \frac{d\ sin(\phi + \alpha)}{sin\ \alpha}$$ **. . . A7.3a (1987 Ed. . . A7.10)**

The distance of the ship from the object at the instant of the second observation can therefore be found in both cases.

Example A7-1. At 1000 an object is seen to bear 040˚ to an observer on board a ship steering 075˚ at 16 knots in a *Tidal Stream* setting 300˚ at 3 knots. At 1030 the same object bears 005˚. How far is the ship from the object at 1030?

At 1000 the angle on the port bow is (075˚−040˚) or 35˚. At 1030 the angle is (075˚−005˚) or 70˚. Also, the angle ϕ is (75˚−300˚ + 360˚) or 135˚. The ship's run in 30 minutes is 8', and d is 1'.5. Both the *Set* of the *Tidal Stream* and the object are to port. The distance of the ship from the object at 1030 is therefore:

$$Distance = 8' - \frac{1'.5\ sin\ (135° - 35°)}{sin\ 35°}$$ . . . (formula A7.1a)

$$= 8' - \frac{1'.5\ sin\ 100°}{sin\ 35°} = 8' - 2.6' = 5.4'$$ . . . (formula A7.3a)

The position of the ship at 1030 is thus *Fixed* by a bearing and distance of 005˚ and 5'.4, and it is necessary to plot only the true bearing. If the *Set* had been in the opposite direction, 120˚, ϕ would have been equal to (120˚ − 75˚) or 45˚, and the distance would have been:

$$Distance = 8' + \frac{1'.5\ sin\ (45° + 35°)}{sin\ 35°} = 8' + 2.6' = 10.4'$$ . . . (formula A7.3a)

(2) c. **Effect of the Tidal Stream when ϕ has Particular Values.** The general formula is simplified considerably when ϕ has certain values. These values and adjustments are:

- **When ϕ is Equal to Zero.** This means that the direction of the *Current* or *Tidal Stream* is the same as the course steered. Then, by substitution:
  $CX = AB + d$
- **When ϕ is Equal to 180°.** The *Current* or *Tidal Stream* is now in a direction opposite to the course steered, and:
  $CX = AB - d$
- **When ϕ is Equal to α.** This means that the direction of the *Current* or *Tidal Stream* is that of the first true bearing, and:
  $CX = AB$
- **When ϕ is Equal to $(180^\circ - \alpha)$.** The *Current* or *Tidal Stream* is now in a direction opposite to the first true bearing, and again:
  $CX = AB$
- **When ϕ is Equal to 2α.** This means that the direction of the *Current* or *Tidal Stream* is that of the second true bearing, and:
  $CX = AB - d$
- **When ϕ is Equal to $(180^\circ - 2\alpha)$.** The *Current* or *Tidal Stream* is now in a direction opposite to the second true bearing, and:
  $CX = AB + d$

INTENTIONALLY BLANK

(APPENDICES 8 & 9 ARE SPARE AND APPENDIX 10 IS IN PART 2)

INDEX-GLOSSARY

1. Purpose - 'Technical Terms'

The purpose of this 'Index-Glossary' is to provide a quick method of locating the primary definition and/or explanation of each of the 'technical terms' used in BR 45 Volume 1, together with the location of other occurrences of their use.

2. Italicised Terms.

'Technical terms' (as described above) are indicated in the text of BR 45 Volume 1 by being italicised. Exceptionally,'Notes', 'Examples' and 'lettered notations' referring to diagrams or included in formulae are also italicised to enhance clarity, but are NOT included in the Index-Glossary.

3. Primary and Secondary References.

Within this Index-Glossary, the primary definition and/or explanation of an 'italicised technical term' is given in **bold type**, with secondary occurrences given in ordinary type.

4. Explanatory Notes in the Index Glossary

Some words have more than one meaning (eg 'compass Bearing ....' and 'bearing in mind ....', or 'Sphere [Earth's shape]' and 'Sphere [soft-iron, for magnetic compass]'). Where appropriate, to avoid the risk of confusion between similar terms, a brief explanatory note to indicate the context is included in the Index-Glossary, in addition to the paragraph locations.

5. Scope

This Index-Glossary gives the paragraph location of instances of the italicised technical terms used in BR 45 Volume 1. Instances of words used in a sense which is NOT a technical term (eg 'bearing in mind ....' see Para 4 above) are NOT included in the Index-Glossary.

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
2nd and/or 3rd Trace Echoes (Radar)	**1515, 1518, 1530.**
ABC Table Method	**0210.**
Abnormal Refraction	**0803,** 0933, 1603, App 6.
Abnormal Waves	**1125,** 1812.
Absolute Position (Naval Command Systems)	**0111.**
Absolute Position (Navigational Errors)	**1602.**
Acceleration Distance (Manoeuvring Data)	**0714,** 1314
Accuracy (Navigational Errors)	**1602-1603, 1611,** 1620, **Anx 16A.**
Acquisition (Radar / ARPA)	**1703.**
Additional Military Layers	See AML.
Admiralty Digital Publications	See ADP.
Admiralty List of Lights and Fog Signals	See ALLFS.
Admiralty List of Radio Signals	See ALRS.
Admiralty Raster Chart Service	See ARCS.
Admiralty Sailing Directions (Pilots)	See Sailing Directions.
ADPs (Admiralty Digital Publications)	**0640.**
Advance (Manoeuvring Data)	**0714,** 1310-1311, **1314,** 1315.
Advising (Management)	**1910.**
Aerial Rotation (Radar)	**1510.**
Aero Lights (Light characteristics)	**0931.**
Aeromarine Lights (Light characteristics)	**0931.**
AGC (Automatic Gain Control - Radar)	**1514.**

Primary / Secondary References (Primary References in BOLD)

Agulhas Current	**1124-1125.**
AHO (Australian Hydrographic Office)	**0632.**
Airy Spheroid	**0322,** 0331.
AIS (Automatic Identification System)	0331, **0950-0954, 1230,** 1240-1241, 1317, 1319-1320, 1520, 1921, 1923.
Aleutian Current	**1124 -1125.**
ALLFS (Adm. List of Lights and Fog Sigs)	0612, **0640,** 0803, 0930-0931, **0932, 0934,** 0940, 1311.
ALRS (Admiralty List of Radio Signals)	0322, 0323, **0640,** 0910, 0912-0913, 1111, 1240-1241, 1311, 1518.
Alternating (Light characteristics)	**0930.**
Altitude (Sextant)	**0803,** App 4. See also Observed Altitude, True Altitude.
AMLs (ENC - Additional Military Layers)	**0632.**
Amphidromic Points (Tides)	**1052.**
Amplitude (Tidal Wave Height)	**1021.**
Amplitudes (Tidal Harmonic Constituents)	**1030-1031.**
Anchor Bearings	**1415.**
Anchoring	1401, **1410-1419,** 1501.
Angle of Dip	See Dip.
Angle on the Bow	**1527, 1703, 1722.**
Annual Notices to Mariners (UKHO)	**1221.**
Annual Summary of Notices to Mariners	1111, **1211.**
Antipodal / Antipodal Point (Tides)	**1012-1013,1015.**
Antipode (Tides)	See Antipodal / Antipodal Point.
Aphelion (Tides)	**1016.**
Apogean Tide (Tides)	**1015.**
Apogee (Tides)	**1015.**
Apparent Angle (Hydrographic Survey)	See Cocked-up Angle.
ARCS (Admiralty Raster Chart Service)	**0614,** 0930.
Arcs (S African Regional Datum)	**0322.**
Area (Projection property)	0410, **0411,** 0413-0414, 0451.
Areas to be Avoided (Traffic routing system)	1111, **1221.**
ARPA (Automatic Radar Plotting Aids)	0950, 1317, 1324, **1525, 1526,** 1701, 1702, 1921, 1923.
Arrival Gates	1112, **1214, 1312, 1330.**
Arrival Point	**1112.**
Aspect	See Angle on the Bow.
Astronomical Position Line	See Position Line.
Atmospheric Refraction (Radar)	**1515.**
Atmospheric Refraction (Visual)	**0803, 0932,** 0933, 1515, App 6.
Attenuation (Radar)	**1510, 1516.**
Australian Hydrographic Office	See AHO.
Automatic Gain Control (Radar)	See AGC.
Automatic Identification System	See AIS and W-AIS.
Automatic Radar Plotting Aids	See ARPA.
Auxiliary Light (Light characteristics)	See Subsidiary (Auxiliary) Light.
Axis (Earth)	**0111,** App 2.
Azimuth	0324, 0541, **1326,** App 6.
Azimuth Circle	**0802.**
Ballistic Deflection (Gyro)	**0920.**
Ballistic Tilt (Gyro)	**0920.**
Bands (Light Structure Descriptions)	**0930.**
Bands of Latitude (UTM)	**0451.**
Bandwidth (Radar)	**1513,** 1523, **1529.**
Bank Effect (Canal Effect / Interaction)	**1220, 1332.**
Barycentre (Tides)	**1011-1012, 1016.**
Base Extension (Hydrographic Survey)	**1820, 1825.**
Base Extension Triangulation (Hyd. Survey)	**1820.**
Base Line (Hydrographic Survey)	**1820-1822, 1825, 1831.**
Bathymetric Charts	**0611.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Beam Mark / Marks (Anchoring)	**1410, 1413.**
Beam Width (Radar)	**1510, 1512,** 1519, 1522, 1523.
Bearing (Projection property)	**0411,** 0414.
Bearing Error (Navigational Errors)	**1603-1623.**
Bearing Lattices	**0808-0809,** 1313.
Bell (Fog signal)	**0934 0940.**
Benguela Current	**1124 -1125.**
Bergy Bits (Ice)	**1531.**
Bernoulli Phenomenon (Interaction)	**1220.**
Bias (Navigational Errors)	**1611,** 1612, Anx 16A.
Blind Pilotage	0902, 0923, 0612, 0715, 0720, 1111, 1233-1234, 1301, **1310,** 1311-1315, **1316,** 1317-1320, **1321,** 1323-1325, 1327-1328,1401, 1413, 1415, 1501, 1520, 1521, 1911-1912, 1921-1925, 1931-1933.
Block Coefficient (Cb)	**1220.**
Blockage Factor (Interaction)	**1220.**
Blunders (Navigational Errors)	1603, **1610,** 1621.
Bore (Tides)	**1021.**
Boundary Layer (Water flow)	**0925.**
Bow Dome (Warship sonar)	1332, 1412, **1414, 1418-1422, 1423, 1425.**
Bracketed Corrections (Obsolete from 1986)	**0624.**
Brazil Counter-Current	**1125.**
Brazil Current	**1124 -1125.**
Breast (Berthing)	**1422, 1425.**
Bridge Swinging Circle	**1415,** 1418.
British National Grid	0331, 0431, **0452.**
British Standard Nautical Mile	**0113.** This term is discontinued - see International Nautical Mile.
BSB (NGA RNC format)	**0632.**
Bubble Times	**0715, 1214,** 1234, **1312, 1330, 1415.**
Buoyage System	See IALA Maritime Buoyage System.
Cable (Distance)	**0113.**
CADET (Compass to True Add East)	**0124,** 0125, 0811.
California Current	**1124 -1125.**
Canal Effect	**1220,** 1234, 1322, **1332.**
Canal Speed (Canal Effect / Interaction)	**1220.**
Canary Current	**1125.**
Cardinal Marks (Buoyage System)	**0941.**
Carrier Sense TDMA (AIS)	See CSTDMA.
Cartesian Coordinates	**0206, 0324,** 0333, 0412, 0414, 0450.
Category of Zone of Confidence (ENCs)	See CATZOC.
CATZOC (Categories: Zones of Confidence)	**0625-0626,** 0805.
Cb	See Block Coefficient.
CDMVT (Cadbury's Dairy Milk Very Tasty)	**0124,** 0811.
Celestial Pole	**0920.**
Celestial Sphere	**0116.**
Central Meridian (Transverse Mercator)	**0414,** 0421, **0431,** 0450, **0451, 0452,** App 4.
Centre of Curvature (Earth)	**App 6.**
Centre of Gravity (Ship)	**1220.**
Centre of Gravity (Tides)	**1011.**
Centre of Windage (Ship)	**1334.**
Centrifugal Force (Tides)	**1012.**
CEP (Circular Error Probable - Nav. Errors)	**1602, 1615-1616, Anx 16B.**
Character / Characteristic (Lights)	**0930,** 0933, 0942.
Charge (Navigational Charge of a vessel)	**1312,** 1323, 1326, **1910, 1912, 1923-1924, 1931-1932.**
Chart Correction Log	**1311.**
Chart Datum	**0624, 1060-1061,** 1233, 1321, 1813, **1820, 1828.**
Chart Lengths (Meridional Parts)	**0422,** 0424.

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Chernikeef (Speed) Logs	**0925.**
Circle of Error (Navigational Errors)	**1615, Anx 16B.**
95% Circle of Error (Nav Errors)	**1613, Anx 16B.**
Circular Error Probable (Navigational Errors)	See CEP.
Circular Normal Distribution (Nav. Errors)	**Anx 16B.**
Clarke Spheroid (1880)	0424, **0531.**
Clearing Bearings (See also Clearing Lines)	**0715,** 0720, 0942, 1310, 1312, **1315,** 1319, **1322,** 1328, 1330
Clearing Lines (Clearing Ranges / Bearings)	**0715,** 0720 0942, **1210, 1214, 1233,** 1310, 1312, **1315, 1317,** 1319-1320, **1322,** 1328, 1330, 1413, 1923, 1931
Clearing Marks	**1233.**
Clearing Ranges (See also Clearing Lines)	**0715,** 0720, 0942, 1232, **1233,** 1310, 1315, **1316-1317,** 1319, 1322, 1328, 1330.
Clipping (Radar)	**1514,** 1520.
Closest Point of Approach	See CPA.
Clutter (Radar)	**1510, 1513-1514,** 1515, **1523,** 1526.
Coastal Navigation	0714, 0716, **0721,** 0902, 0923, 1101, 1110-1111, 1201, **1210-1214, 1222, 1230-1238,** 1301, 1311, 1316, 1320, 1327, **1527, 1911, 1920, 1930.**
Coastal Warnings (Radio)	**0615.**
Coastlining Board (Hydrographic Survey)	**1829.**
Cocked Hat	0805, **0811-0812, Anx 16B, 1814,** App 10.
Cocked-up Angle (Hydrographic Survey)	**1824, 1826.**
COG (Course Over G'd / Ground Track AIS)	**0951**
Co-Latitude	**0208,** App 4
Cold Moves (HM Dockyard Ports only)	**1304.**
Collimation Error (Sextant)	**App 10.**
ColRegs (Int. Regs: Prevention of Collision)	**0954, 1221, 1235,** 1240, 1312, **1520,** 1526, **1722.**
Command (Command of Ship)	**1910-1913, 1923-1924, 1931-1933.**
Commercial Service (Galileo)	See CS.
Compass North	**0122, 0123.**
Compass Rose	**0124,** 0411, 0624, 0711, 1312.
Compass Rose Correction (Rose Correction)	**0124.**
Composite Errors (Navigational Errors)	**1610.**
Composite Group Flashing (Lights)	**0930.**
Composite Group Occulting (Lights	**0930.**
Composite Track	0201, 0202, 0207, **0209, 0442, 0520, 0522,** 0622, App 2.
Con (Conning orders)	**1304, 1312,** 1316, 1319, 1322, **1910.**
Conduct (Navigational Conduct of Ship)	**1238, 1910, 1912.**
Cone (Projections)	**App 4.**
Conformal Projection	See Orthomorphic Projection.
Conical Projections	**0413,** 0414, App 4.
Conjunction (Tides)	**1017.**
Conning (Manoeuvring orders)	See Con (Conning orders).
Conning (Systems - IBS)	**1236.**
Constant of the Cone (Mercator Projection)	**0421,** App 4.
Contiguous Zones	**1111.**
Continuous Uniform Distribution (Nav Error)	See Rectangular Distribution.
CONTRARY Name (Hemispheres)	**0208, 0211.**
Control (Hydrographic Survey)	**1820.**
Control / Controlling (Manoeuvre of ship)	**1910, 1912, 1924, 1932.**
Control Points (Hydrographic Survey)	**1820.**
Controllable Pitch Propellers	See CPP.
Conventional Direction of Buoyage	**0941.**
Convergence (Meridians)	**0421.**
Coral	0803, **1222, 1237,** 1328.
Co-Range (Charts)	1050, **1052.**
Coriolis Force	**1122.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Corpos Mortos (Stern-To Berthing)	**1420.**
Corrected Mean Latitude	**0205,** 0207, 0511, App 3.
Corrected Mean Latitude Sailing	0201, **0205,** 0207, 0501.
Correlation Speed Logs	**0925.**
Cosine Formula / Method / Rule etc	0210, **0211,** 0811, **Apps 1- 2,** App 4.
Co-Tidal (Charts)	1050, **1052.**
Course (Chart projections)	**0414.**
Course (Geodesic - Spheroidal)	**0540, 0541.**
Course (Great Circle)	**App 2.**
Course (Naval Command Systems)	**0120.**
Course (Rhumb Line - Spherical)	**0511,** 0520, **0522.**
Course (Rhumb Line - Spheroidal)	**0530, 0531.**
Course (Sailings)	0204-0206, 0210-0211.
Course Made Good	See Ground Track.
Course Over Ground (Ground Track - AIS)	See COG.
Courses to Steer	1310, **1312, 1314,** 1316, 1319, 1323, 1413, 1415.
Course-Up (Radar / ARPA)	**1526.**
CPA (Closest Point of Approach)	0713, 1316, 1526, **1527,** 1703, 1733.
CPP(Controllable Pitch Propellers)	1332, **1334.**
Cross Index Range (Parallel Index)	**1232,** 1238.
Cross Track Error (Hydrographic Survey)	**1827.**
Cross Track Error (Nav Errors - Bias)	**1611.**
CS (Commercial Service - Galileo)	**0914.**
CSTDMA (Carrier Sense TDMA - AIS)	**0951.**
Current / Currents	**0712,** 0713, 0715-0716, 0804, **0805,** 0806, 0916, 0925, **1002, 1040-1042,** 1110-1112, 1120, **1121-1125,** 1210, 1212, 1214, 1222, 1231, 1234, 1236, 1238, 1312, 1314, 1316, 1320, 1330-1331, 1333, 1411-1412, 1527, 1603, 1621, App 7.
Cyclone / Cyclones	**1812.**
Cylindrical Orthomorphic Projections	See Cylindrical Projections.
Cylindrical Projections	**0413, 0420,** App 4.
d.lat	**0112, 0204-0206,** 0207, 0511, App 5.
d.long	**0112,** 0203-0204, **0205-0206**, 0207, **0208,** 0511, 0522, 0541, Apps 3-4.
d[rms] (Navigational Errors)	**1602 1612.**
1d[rms] (Navigational Errors)	**1615, Anx 16B.**
2d[rms] (Navigational Errors)	**1615, 1620, Anx 16B.**
Datum / Datums (Geodetic)	0101, 0110, **0311, 0320-0321,** 0322, **0323,** 0324, 0331, 0452, 0550, 0551, 0711, 0807, 0910, 0913, 1222, 1321, 1330, 1602, **1820, 1829,** 1921-1922.
Datum Shift	**0323, 0324,** 0624, **0805,** 0910.
Daybeacons (USA / Canada)	**0940**
Daymarks	**0940**
Daytime Lights (Light characteristics)	**0931**
DChayka (Russian *LORAN* -C equivalent)	**0912**
Dead Range (Blind Pilotage)	**1316**
Dead Reckoning	See DR.
Declination (Projections)	**App 4.**
Declination (Tides)	**1014-1018, 1020,** 1062.
Deep Water Routes (Traffic routing systems)	**1221.**
Degausing (Magnetic Compasses)	See DG (Magnetic Compasses)
Departure (Sailings)	**0202-0206,** 0421, **0511,** App 3.
Detection (Radar / ARPA)	**1703.**
Deviation (Magnetic)	**0122-0125,** 0807, 0811, **1113, 1230,** 1610, App 10
DG (Degausing)	0922, **1230**
DG (Directional Gyro)	**0920**
DGLONASS (Satellite navigation)	**0912.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
DGPS / GPS (Satellite navigation)	0323, 0331, 0423, 0451, 0714, 0716, 0803, **0805,** 0808, **0910 0911-0912, 0916,** 0918, 1110, 1111, 1210, **1211**, 1212, 1222, 1231, 1234-1236, 1313, 1316, 1321, **1521,** 1527, 1803, **1806-1807, 1810,** 1811, 1813-1814, 1820-1821, 1826, **1827, 1829,** 1922-1933.
Diagonal Stripes (Structure Descriptions)	**0930.**
Diamond of Error (Navigational Errors)	**1614,** 1620, **Anx 16B.**
Diaphone (Fog signal)	**0934.**
Difference of Latitude	See d.lat.
Difference of Longitude	See d.long.
Difference of Meriodinal Parts (DMP)	See DMP.
Differential Chayka	See DChayka.
Differential GLONASS	See DGLONASS
Differential GPS	See DGPS.
Differentiation (Radar)	**1513, 1514,** 1520.
Digital Navigation	0901- 0902, **0919,** 1903, 1910, **1911, 1923-1924.**
Digital Selective Calling (VHF Comms)	See DSC.
Dilution of Precision (GPS)	See DOP.
Dip (Magnetic)	**1610.**
Dip (Sextant)	**0803,** App 6.
DIPCLEAR (Diplomatic Clearance)	**1110-1111, 1210 1211, 1802.**
Diplomatic Clearance	See DIPLCLEAR.
Dipping Range (Lights)	**0933.**
Direction (Naval Command Systems)	**0120.**
Direction Light (Light characteristics)	**0930.**
Direction of Buoyage	0940, **0941.**
Directional Gyro	See DG (Directional Gyro).
Distance (Between anchor berths)	**1412.**
Distance (Geodesic - Spherical)	**0540, 0541.**
Distance (Geodesic - Spheroidal)	**0541.**
Distance (Great Circle)	**App 2.**
Distance (Rhumb Line - Spherical)	**0511, 0522, 0541.**
Distance (Rhumb Line - Spheroidal)	**0530, 0531.**
Distance (Sailings)	0201, **0202,** 0203-0206, 0208, 0210-0211.
Distance Error (Navigational Errors)	**1603, 1623.**
Distance Meters	**0803.**
Distance to New Course (Manoeuvring)	See DNC.
Diurnal (Tidal Streams)	**1040.**
Diurnal (Tides)	**1015, 1017, 1018, 1020,** 1062.
Diurnal Inequality (Tidal Streams)	**1040 1042, 1045,** 1816.
Diurnal Inequality (Tides)	**1015, 1017, 1020, 1030,** 1062.
Dived Navigation	**1911.**
DMP (Difference of Meriodinal Parts)	0207, **0422,** 0424, 0510, **0511,** App 3.
DNC (Distance to New Course - Manoeuvre)	**0714.**
DNC (Manoeuvring Data)	**1314.**
DNC (NGA [non-ENC] Vector chart format)	**0632,** 0902.
Doldrums	**1122,** 1125.
DOP (GPS - Dilution Of Precision)	0910, **1806, 1829.**
Double Normal MSR (Anchoring)	**1412.**
Double Reduced MSR (Anchoring)	**1412.**
Doubling the Angle on the Bow	**0806,** App 7.
Douglas Protractor	**0808, 0811.**
DR (Dead Reckoning)	**0710, 0712,** 0713-0716, 0805, 0806-0807, 0810, 0812, 0916, 0925, 0942, **1231,** 1328, 1603, 1610, 1623, 1921.
DR Stations (Running Survey)	**1814.**
Drift / Drift Rate	**0713, 0713,** 0720, 0806, 1322, 1527, 1603.
Drift Current	**1041, 1121, 1125.**
Dropping Anchorage	**1414,** 1417, **1421.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
DSC (Digital Selective Calling-VHF Comms)	0950, **1240.**
Duration of Turn (Manoeuvring Data)	**0714**, 1314.
Dutchman's (Speed) Log	**0925.**
Eagre (Tides)	See Bore
Earth Curvature Graph (Nomograph)	**1524.**
East Greenland Current	**1124.**
East Australian Coast Current	**1124-1125.**
Ebb (Tidal Streams)	**1040.**
EBL (Electronic Bearing Line)	**1317,** 1720, 1933.
Eccentricity (Spheroid)	**0311, 0322,** 0422, Apps 4-5
ECDIS (Electronic Chart Display Information System)	See also WECDIS. 0210, **0311**, 0451, 0550, **0551, 0631, 0632,** 0701, 0712, 0714, 0715- 0716, **0720-0721,** 0805, 0808, 0811, 0910, 0919, 0950, 1051, 1102, 1110, 1113, 1202, 1210, 1214, 1222, 1230, **1231,** 1232, 1236, **1238,** 1302, **1311,** 1312-1316, **1317,** 1319-1320, **1321,** 1323-1325, 1327-1328, 1402, 1413, 1415, 1502, **1528,** 1701, 1702, **1810, 1814-1815,** 1903, **1911,** 1920, **1921-1922, 1925.**
Echo Sounders	0613, 0626, 0803, 0805, **0923-0924,** 0942, **1211,** 1222, 1235, 1310, **1312, 1315,** 1319-1320, **1323,** 1324-1325, 1328, 1416, **1807, 1810,** 1813-1814**, 1821, 1827, 1831, 1923-1924, 1931-1933.**
Eclipse (Light characteristics)	**0930.**
Ecliptic Plane (Tides)	**1017.**
ECS (Electronic Chart System)	**0311, 0631,** 0701, 0720, 0910.
ED 50 (European Datum 1950)	**0322.**
Eddy / Eddies (Tides)	**1044.**
EGNOS (European Geostationary Navigation **Overlay Service)**	**0915, 1806.**
El Niño (variable) Current	**1124-1125.**
Electro Optic Surveillance Systems	See EOSS.
Electronic Bearing Line	See EBL.
Electronic Chart Display Information System	See ECDIS and WECDIS.
Electronic Chart System	See ECS.
Electronic Charts (Generic term)	See ENCs, RNCs and DNCs.
Electronic Navigation Charts (Database)	See ENC..
Electronic Plotting Aid	See EPA.
Electronic Tracking Aid	See ETA.
Elevation	**0624, 0803, 0930,** 0931, 0932-0933, 0940, 1233, **1820,** 1823, 1830.
Ellipsoid (Earth - Oblate Spheroid)	**0311.**
eLORAN	0716, **0805,** 0912, **0918,** 1111, 1231.
Emergency Position Indicating Radio Beacon	See EPIRB.
Emergency Wreck Marking Buoys (Buoyage)	**0941.**
e-Nav / e-Navigation	0901, **0919.**
ENC (Electronic Navigation Charts)	0331, 0614, 0615-0616, 0625, 0631, **0632-0633**, 0712, 0720, 0902, 0919, 0930, 0940, **1042,** 1110, 1210, 1214, 1317, 1321, 1911.
Enhanced LORAN	See eLORAN.
EOSS (Electro Optic Surveillance Systems)	**0926,** 1312, 1316, 1320, 1323, 1325.
EP (Estimated Position)	**0710, 0712,** 0713, 0715-0716, 0805-0807, 0810, 0812, 0916, 0942, **1231,** 1234, 1312- 1314, 1323-1325, 1328, 1603, **1610,** 1623,1814, 1921, 1931, 1932.
EPA (Electronic Plotting Aid)	**1525.**
EPE (GPS - Estimated Position Error)	0910, **1806, 1829.**
EPIRB (Emergency Position Indicating Radio Beacon)	**1518.**
Equal Area (Projection property)	**0414,** 0622, App 4.
Equation of the Ellipse	**App 5.**
Equator / Equatorial (General)	**0110,** 0111-0116, 0121, 0202-0203, 0205, 0211, 0312-0314, 0324, 0411, 0414, 0420, 0421, 0422, 0423, 0424, 0425 0431, 0440, 0441, 0451, 0511, 0910, 0913, 0914, 0920, 1014, 1016, 1020, 1122, 1125, Apps 2-5.

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Equatorial (Radius / Axis)	**0110,** 0115, 0310, **0311**, 0541, App 5.
Equatorial Counter-Current	**1122, 1125.**
Equatorial Currents (North and South)	**1124-1125.**
Equatorial Element (Spheroid)	**App 5.**
Equatorial Trough	**1122, 1125.**
Equinoctial Tides	**1017.**
Equinox / Equinoxes (Tides)	**1017, 1020.**
Equipotential Surface (Geoid)	**0311.**
Equivalent Probability Circle (Nav Errors)	**1615,** 1620, **1623, Anx 16B.**
50% Equivalent Probability Circle	**Anx 16B.**
70% Equivalent Probability Circle	**1610.**
95% Equivalent Probability Circle	**1615-1616,** 1620, **1622-1623, Anx 16B.**
Error Circle (Navigational Errors)	**Anx 16B.**
Error Ellipse (Navigational Errors)	**1614-1616,** 1620, **Anx 16B.**
95% Error Ellipse	1614, 1620, **Anx 16B.**
Estimated Position	See EP.
Estimated Position Error (GPS)	See EPE.
ETA (Electronic Tracking Aid)	**1525.**
ETRS 89 (European Regional Datum)	**0321-0322.**
Eurofix	0911, **0912.**
European Datum (1950)	See ED 50.
European Geostationary Navigation Overlay Service	See EGNOS.
European Regional Geodetic Datum	See ETRS 89.
Exclusive Economic Zones	**1111.**
Execution / Executing (Navigation)	**1910-1912.**
Falkland Current	**1124-1125.**
False Easting (Transverse Mercator Grids)	**0451-0452,** App 4.
False Northing (Transverse Mercator Grids)	**0451-0452,** App 4.
False Origin (Transverse Mercator Grids	0431, **0450, 0452.**
FATDMA (,ed Access TDMA - AIS)	**0951.**
Faults (Navigational Errors)	1603, **1610,** 1620, **Anx 16B.**
Fetch	**0712, 1022-1023.**
Fibre Optic Gyro	See 'FOG'.
Final Diameter (Manoeuvring Data)	**0714.**
First Quarter (Moon)	**1017-1018, 1020.**
Fisheries Zones	**1111.**
Fix / Fixed / Fixing (Position)	0120, **0710-0711,** 0712-0714, 0716, 0721, 0801, **0803, 0805-0812,** 0910-0911, 0916, 0918, 0924, 1113, 1211-1212, 1222, **1231-1232,** 1234, **1238,** 1310, 1312-1314, 1316, 1323, 1325, 1328, 1413, 1415, 1418, **1521,** 1527, 1602-1603, 1610-1612, 1620, 1623, Anx 16B, 1804, **1806, 1811,**1813-1814, 1820-1821, 1823-1824, **1827, 1829,** 1830, 1921, 1923-1924, 1931-1932, Apps 6-7, App 10.
Fixed (Light characteristics)	**0930,** 0942.
Fixed Access TDMA (AIS)	See FATDMA.
Fixed Pitch Propellers	**1334.**
Flash / Flashing (Light characteristics)	**0930.**
Flat Earth	**0330, 0333,** 0411, 0550.
Flattening (Spheroid)	**0311, 0322,** 0422, 0541, App 5
Fleet Operating Orders (BRd 9424)	See FLOOs.
Flood (Tidal Streams)	**1040.**
FLOOs (Fleet Operating Orders - BRd 9424)	**1111,** 1113.
Florida Current	**1125.**
Fluxgate (Magnetic) Compasses	**0922.**
FOG (Fibre Optic Gyro)	0121, **0920.**
Fog (Signals)	**0934, 1235,** 1310.
Fog (Visibility - Restricted)	0933, 1110 -1111, 1124, 1210, **1211,** 1212, 1232, **1235,** 1311, 1531.
Fog Detector Lights (Light characteristics)	**0931.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Fog Lights (Light characteristics)	**0931.**
Foreign Charts	**0611,** 0624, **1110-1111, 1310-1311.**
Four-Part Formula (Trigonometry)	**App 2.**
Four-Point Bearing (Distance abeam)	**0806.**
FPP (Fixed Pitch Propellers)	**1334.**
Full Moon (Tides)	**1017, 1018, 1020.**
Gain (DGPS / GPS)	**1806.**
Gain (Radar)	**1514,** 1520.
Galileo (Satellite navigation)	**0914-0916.**
Gauss Conformal Projection	See Transverse Mercator Projection.
General Direction of Buoyage	**0941.**
Geocentric (Radius)	**App 5.**
Geocentric Latitude	**0312,** 0331, App 5.
Geodesic (Great Circle equivalent)	**0110,** 0115, 0208, 0210, 0313, **0315, 0540,** 0551.
Geodesic Azimuth	**0541.**
Geodesic Course	See Course (Geodesic - Spheroidal).
Geodesic Distance	See Distance (Geodesic - Spheroidal).
Geodesy	**0301.**
Geodetic / Geodetically	**0321, 0331,** 0805.
Geodetic Coordinates	**0323,** 0331.
Geodetic Datum	See Datum.
Geodetic Latitude	**0111, 0312-0314, 0321,** 0331, 0540, **0541,** App 5.
Geodetic Longitude	**0321,** 0331.
Geographic Latitude	**0111,** App 5.
Geographic Mile	**0113,** 0114.
Geographic Position	**0803, 1814, 1820,** 1826, App 4.
Geographical Range (Light characteristics)	0803, **0930, 0932** 0933.
Geoid (Earth - Oblate Spheroid)	**0311, 0321.**
Global Maritime Distress and Safety System	See GMDSS.
Global Navigation Satellite Systems	See GNSS.
Global Positioning System	See GPS.
GLONASS (Satellite navigation)	0913, **0915, 0916.**
GMDSS (Global Maritime Distress and Safety System)	**0917, 1230,** 1240.
Gnomonic / Gnomonic Projection (charts)	**0413-0414, 0440-0442,** 0521, 0551, 0611, **0622,** 0624, App 4.
Gnomonic Graticule / Projection Graticule	**0413, 0414 0440,** 0622, App 4.
GNSS (Global Navigation Satellite System)	0321, 0323, **0915,** 0954.
GNSS-1	See GNSS.
GNSS-2	See GNSS.
Gong (Fog signal)	**0934, 0940.**
GPS (Satellite navigation)	GPS-specific instances: **0910,** 0913-0914, **0915-0917,** 0954, 1610, **1806, 1829.** Otherwise, see DGPS, GPS 'Assisted' Accidents, GPS Denial, GPS Lattice.
GPS 'Assisted' Accidents	**0805,** 1231.
GPS Denial	**0805,** 0808, **0916, 1211,** 1222, 1231, 1234, 1313, 1921-1922.
GPS Lattice	**0805,** 1313.
Gradient Current	1041, **1121.**
Graticule (Projections)	**0412,** 0414, 0420, **0421,** 0423, **0424,** 043,0 0450, Apps 4-5.
Graticule Shape (Projections)	See Graticule (Projections).
Gravitational Force (Tides)	**1012-1013.**
Great Circle	**0110,** 0111, 0113, 0115, 0120, 0122, 0201, **0208-0211,** 0315, 0414, **0425,** 0440, **0441- 0442,** 0520, 0521, 0522, 0540, 0551, 0622, 0920, 1012-1013, 1110 -1111, App 2, Apps 4-5.
Greenwich Meridian	See Prime Meridian.
Grid / Grids (see also UTM Grid)	0320, 0331, 0401, **0412,** 0414, 0421, 0430-0431, **0450-0451,** 0621, 0805.
Grid (Coordinates)	**App 4.**
Grid Convergence	**0450, 0452.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Grid Eastings	0450, **0451,** App 4.
Grid Length (Transverse Mercator Grids)	**0450**.
Grid Navigation (Polar regions)	**0920.**
Grid Northings	**0421,** 0450, **0451,** 0454, App 4.
Grid Orientation	See Grid Convergence.
Grid Origin	**0333,** 0431, **0450, 0452,** App 4.
Grivation	**0454.**
Gross Tonnage	**1525.**
Ground Speed (Speed made good)	**0713, 0716,** 1214, 1231, **1703.**
Ground Stabilised (Radar / ARPA)	1316, **1526-1527, 1703,** 1722, **1933.**
Ground Track (Course made good)	0710, **0713,** 0925, 1236, 1314, 1322, 1415, 1527, 1610, **1611, 1703,** App 7.
Group Anchorages	**1401.**
Group Flashing (Light characteristics)	**0930.**
Group Occulting (Light characteristics)	**0930.**
Group Quick Flashing (Light characteristics)	**0930.**
Group Very Quick Flashing (Light characteristics)	**0930.**
Growlers (Ice)	**1531.**
Guard Zones (ARPA)	**1526.**
Guinea Current	**1125.**
Gulf Stream	**1124-1125.**
Gyro / Gyro Compass	0120, **0121,** 0122, 0125, 0712, 0811, **0920,** 0921, 1113, **1230,** 1522, 1526-1527, 1603, 1610-1611, 1622, Anx 16A, 1722.
Gyroscope	**0121, 0920,** 1811, 1814, 1816, 1820.
Gyroscopic Inertia	**0920.**
Half Beam Width Error (Radar)	1232, **1512, 1522-1523.**
Half Log Haversine Method (Trigonometry)	**0210, App 2.**
Handbrake Turn (Manoeuvring)	**1315.**
Harmonic Constants (Tides)	**1030-1032, 1042, 1050,** 1053.
HAT (Highest Astronomical Tide)	**0624, 1062,** 1820.
Haversine Formula / Method (Trigonometry)	**0210, App 2.**
HCRF (UKHO / AHO RNC format)	**0632.**
Head Rope (Berthing)	1333, **1425.**
Heading (General)	**0120,** 0122, 0124-0126, 0920.
Heading (Naval Command Systems)	**0120.**
Headmark / Headmarks	0942, 1310, 1312-1314, 1319, 1321, **1322,** 1324, 1410, 1413, 1923, 1931.
Head-Up (Radar / ARPA)	**1526.**
Heave-To / Heaving-To	**1211.**
Heavy Weather	**1211.**
Heights (Hydrographic Survey)	**1820.**
Heights (Light Structure Descriptions)	**0930.**
Highest Astronomical Tide	See HAT.
Homogeneous Geodetic Datums	**0324.** See also Non-Homogeneous Geodetic Datums.
Horizontal Control (Hydrographic Survey)	**1820.**
Horizontal Danger Angle	**0803, 1233.**
Horizontal Sextant Angle	See HSA.
Horn (Fog signal)	**0934, 0940.**
HOT (Height of Tide)	**0715,** 0803, 0805, 0932-0933, **1021-1022, 1030,** 1050-1051, 1060, **1210, 1213,** 1233-1234, 1310-1312, 1316, 1319, 1320, 1323, 1330, 1410, 1411, **1521, 1820, 1827.**
Hour Angle (Projections)	**App 4.**
HSA (Horizontal Sextant Angle)	**0803, 0805, 0808, 0810,** 0811, **1233, 1521,** 1811, **1827, 1829,** 1830, App 6, App 10.
HSA Lattice	**0808, 0810,** 1313, App 6, App 10.
Humbolt Current	See Peru Current.
Hurricanes	**1812.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Hydrographic Chart Raster Format (HCRF)	See HCRF.
Hydrographic Note / Notes	**0616, 1804-1805, 1810, 1812,** 1832.
Hydrolapse	**1515.**
IALA (Fog signals - Policy / Use)	**1211,** 1235.
IALA Maritime Buoyage System	**0941.**
IBS (Integrated Bridge Systems)	**1236.**
Icebergs	**1531.**
IHO (International Hydrographic Organisation)	0614, **0630,** 0632.
IMO (International Maritime Organisation)	0331, **0630-0631,** 0714, 0901, 0919, **1211,** 1221, 1240, 1304, 1321, 1525, 1902.
Impede / Impeded (ColRegs - TSS)	**1221.**
Impeller Speed Logs	**0925.**
Impounded Water (Hydrographic Survey)	**1828.**
Index Error (Radar)	1232, 1310, 1316, 1520, **1521.**
Index Error (Sextant)	0803, 0810, App 6, **App 10.**
Inertial Navigation Systems	See INS.
Inland AIS	**0950,** 0951.
Innocent Passage	**1110-1111, 1210-1211.**
INS (Inertial Navigation Systems)	**0921, 1230,** 1611, 1921.
Inshore Traffic Zone	See ITZ.
Install / Installed (ENCs / RNCs)	**1110, 1210, 1214, 1311, 1320.**
Integrated Bridge Systems	See IBS.
Intensity (Light characteristics)	**0930,** 0932-0933.
Interaction	**1220,** 1234, 1310- 1312, 1319.
Intermediate Course (Manoeuvring Data)	**0714,** 1314.
Intermediate Distance (Manoeuvring Data)	**0714,** 1314.
International Date Line	0451, **1214.**
International Hydrographic Organisation	See IHO.
International Maritime Organisation	See IMO.
International Nautical Mile / Miles	Specific instances of importance (general usage not listed): 0110, **0113,** 0115, 0310, 0422, **0541, 0803,** App 5.
International Regulations for Prevention of Collisions	See ColRegs
International Spheroid (1924)	**0322,** 0331, 1111.
Interrupted Quick Flashing (Lights)	**0930.**
Intersection (Fixing)	**1811, 1824,** 1830.
Intertidal (Tides)	**1521.**
Inverse (Oblique) Mercator Projection	0411, **0414.**
Irish Grid (Transverse Mercator Projection)	**0453.**
Isogonal / Isogonic	**0122.**
Isolated Danger Marks (Buoyage System)	**0941.**
Isophase (Light characteristics)	**0930.**
ITZ (Inshore Traffic Zone - TSS)	**1221.**
Jack / Jackstaff	**1230.**
Japan (Kuro Shio) Current	**1124-1125.**
Kamchata (Oya Shio) Current	**1124 -1125.**
kn	See Knot.
Knot (kn)	**0113.**
Kuro Shio Current	See Japan Current.
La Niña (variable) Current	**1124 -1125.**
Labrador Current	**1124 -1125.**
Lag / Lagging (Tides)	**1017.**
Lamberts Conical Orthomorphic Projection	0411, **0414,** 0421, App 4.
Land Mile	See Statute Mile.
Land Survey Datums (Tides)	**1060.**
Large Corrections (Obsolete from 1972)	**0624.**
Laser Rangefinder	**0803.**
Last Quarter (Moon)	**1017-1018, 1020.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
LAT (Lowest Astronomical Tide)	**0624, 1060-1062.**
Lateral Marks (Buoyage System)	**0941.**
Latitude	Specific instances of importance (general usage not listed): **0111, 0314, 0321, 0711, 1820.** See also Bands of Latitude (UTM), Co-Latitude, Corrected Mean Latitude, Corrected Mean Latitude Sailing, Difference of Latitude, Geocentric Latitude, Geodetic Latitude, Geographic Latitude, Latitude / Longitude Grid, Latitude Rider (Gyro), Latitude Scale, Linear Latitude, Magnetic Latitude, Mean Latitude, Mean Latitude Sailing, Parallels of Latitude, Parametric Latitude, Safe Parallel of Latitude, True Latitude, Vertex Latitude (Great Circle).
Latitude / Longitude Grid	**0805.**
Latitude Rider (Gyro)	**0920.**
Latitude Scale	**0414, 0421, 0422, 0424, 0623,** 0711.
LDL (Limiting Danger Line)	**0715,** 0720, **0721,** 0923, 1110, **1111, 1210, 1214,** 1231, 1310, **1311,** 1312, **1315,** 1316, 1328, 1410, **1413,** 1418, **1911.**
Leading Lights (Light characteristics)	**0930.**
Leading Lines	1313, **1322.**
Leading Marks	1313, **1322.**
Least Squares (Navigational Errors)	**App 10.**
Least Squares Minimum Variance (N. Error)	**Anx 16B.**
Leeway	**0712,** 0713, 0716, 0806, 0925, 1231, 1234, 1236, 1310, **1312,** 1314, 1323, 1417, 1527, 1603, Anx 16A, 1722, 1814.
Leeway Angle	**0712,** 0713, 1722.
Leeway Vector	**0712,** 0713,1322.
LEP (Linear Error Probable)	**Anx 16A.**
Light Characteristics	**0930.**
Limiting Danger Line	See LDL.
Linear Error Probable (Navigational Errors)	See LEP.
Linear Latitude	**0114,** 0115.
Linear Longitude	**0114,** 0115.
Linear SD (Linear Standard Deviation - 1σ)	**1602, 1611, 1613,** 1614, **1615,** 1620, **Anx 16B.**
Linear Standard Deviation (Nav Errors)	See Linear SD.
Load / Loaded (ENCs / RNCs)	**1110, 1210, 1214, 1311, 1320.**
Load Line / Load Line Zones (Stability)	**1110-1111, 1210.**
Local Direction of Buoyage	**0941.**
Local Geodetic Datums (Spheroid)	**0311, 0321,** 0324.
Local Warnings (Radio)	**0615.**
Logline (Tidal Stream observation)	**1816.**
Long Flashing (Light characteristics)	**0930,** 0941.
Long Range Fixing (Radar)	1232, **1530.**
Longitude	Specific instances of importance (general usage not listed): **0111, 0314, 0321, 0711, 1820.** See also Difference of Longitude, Geodetic Longitude, Latitude / Longitude Grid, Linear Longitude, Longitude Scale, Longitude Units, Meridian, UTM Zones of Longitude, Vertex Longitude (Great Circle), Zones of Longitude (Transverse Mercator).
Longitude Scale	**0414, 0421-0424,** 0440, 0522, 0541, **0623,** 0711, App 3, App 5.
Longitude Units	**0422.**
Loom (Lights)	**0930.**
LORAN Denial	**1211, 1234.**
LORAN-A	**0918.**
LORAN-C	0716, **0805,** 0911, **0912, 0918,** 1111, 1231.
Lowest Astronomical Tide	See LAT.
Loxodromes	**0202.**
Lubbers Line	**0121, 0802, 1230,** 1319, 1610.
Luminous Range (Light characteristics)	**0930, 0932,** 0933.

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Lunar Day (Tides)	**1014-1015.**
Lunar Declinational Diurnal Harmonic Constituent	**1031.**
Lunar Equilibrium Tide (Tides)	**1013-1014.**
Lunar Month (Tides)	**1017.**
Lunar Semi-Diurnal Harmonic Constituent	**1031.**
Luni-Solar Declinational Diurnal Harmonic Constituent	**1031.**
Luni-Solar Tide Raising Force	**1017, 1020.**
Magnetic Anomaly	**1113, 1230.**
Magnetic Compass	0120, **0122-0125,** 0922, 1113, **1230,** 1238, 1313, 1322, 1610, 1820-1821, **1827, 1829,** App 10.
Magnetic Compass Rose	**0124.**
Magnetic Deviation	See Deviation.
Magnetic Dip	See Dip.
Magnetic Latitude	**0122,** 0125, **1113, 1230.**
Magnetic Meridian	**0122,** 0123-0124.
Magnetic North	**0122,** 0123-0124, 0454.
Magnetic Pole	**0122.**
Magnetic Signature	**1230.**
Magnetic Variation	See Variation.
Main Light (Light characteristics)	**0930.**
Man OverBoard	See MOB.
Manoeuvring (Plotting) Form	**1715.**
Manoeuvring Data	**0714,** 1314, 1319.
Marine Navigation	See Navigation.
Maritime and Coastguard Agency (UK)	See MCA.
Maritime Buoyage System	See IALA Maritime Buoyage System.
Maximum Unambiguous Range (Radar)	**1515, 1530.**
Maximum Likelihood (Navigational Errors)	See Least Squares Minimum Variance.
MCA (Maritime & Coastguard Agency - UK)	0950, 1525, 1902.
Mean Error Value (Navigational Errors)	**1611.**
Mean High Water Interval (Tides)	See MHWI.
Mean High Water Neaps (Tides)	See MHWN.
Mean High Water Springs (Tides)	See MHWS.
Mean Higher High Water (Tides)	See MHHW.
Mean Higher Low Water (Tides)	See MHLW.
Mean HW (Hydrographic Survey -Tides)	**1828.**
Mean Latitude	**0205-0207,** App 3.
Mean Latitude Sailing	0201, **0205,** 0501.
Mean Level (Hydrographic Survey -Tides)	**1828.**
Mean Low Water (Tides)	See MLW.
Mean Low Water Neaps (Tides)	See MLWN.
Mean Low Water Springs (Tides)	See MLWS.
Mean Lower High Water (Tides)	See MLHW.
Mean Lower Low Water (Tides)	See MLLW.
Mean LW (Hydrographic Survey -Tides)	**1828.**
Mean Neap Range (Tides)	See MNR.
Mean Sea Level (Tides)	See MSL.
Mean Spring Range (Tides)	See MSR.
Mean Square Deviation (Navigational Errors)	See Variance.
Mean Tide Level (Tides)	See MTL.
Mediterranean Moor (Anchoring)	See Stern-To Berthing.
Mer Parts	See Meridional Parts.
Mercator / Mercator Projection	0201, 0202, 0113, 0411, **0414,** 0420, **0421-0425,** 0430-0431, 0441-0442, 0450, 0511, 0521, 0551, 0611, 0620, 0624, 0805, Apps 3-4.
Mercator Graticule (Projections)	**0421-0424.**
Mercator Sailing	0201, 0205, **0207,** 0501, 0510, **0511.**
Meridian of Longitude	See Meridian.

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Meridian / Meridians / Meridional	**0110,** 0111-0115, 0120-0122, 0202, 0204, 0208-0209, **0312-0313,** 0314, 0411- 0412, 0414, 0421-0425, 0431, 0440, 0450, 0510-0511, 0520- 0522, 0920, 1014, 1017, 1052,1820, 1826, 1831, Apps 3- 5.
Meridional Arc	**0530, 0531,** Apps 4-5.
Meridional Element (Spheroid)	**App 5.**
Meridional Grid (Projections)	**0414.**
Meridional Parts (Projections)	0207, 0414, **0422-0423, 0510- 0511, 0530- 0531,** 0620, 0805, Apps 3- 5.
Messenger (Berthing)	**1420-1422**
MHHW (Mean Higher High Water - Tides)	0624, 0803, 0930, **1050-1062,** 1313.
MHLW (Mean Higher Low Water - Tides)	**1050-1062.**
MHWI (Mean High Water Interval - Tides)	**1052.**
MHWN (Mean High Water Neaps - Tides)	**1042, 1045-1046, 1050, 1062,** 1319.
MHWS (Mean High Water Springs - Tides)	0624, 0803, 0930, **1042, 1045-1046, 1050, 1062,** 1233, 1313, 1319 1813.
Middle Latitude	See Corrected Mean Latitude.
Military Command (Ships et al)	**1910, 1912.**
Minimum Keyboard Display (AIS)	See MKD.
Minimum Range (Radar)	**1511.**
Minimum Swing Radius / Radii (Anchoring)	See MSR.
Mini-SOCs (Mini-Standard Operator Checks)	**1230.**
Minor Surveys (Hydrographic)	**0923.**
Mixed Tides	**1020.**
MKD (Minimum Keyboard Display - AIS)	**0950.**
MLHW (Mean Lower High Water - Tides)	**1050, 1062.**
MLLW (Mean Lower Low Water - Tides)	0624, **1050, 1062.**
MLW (Mean Low Water - Tides)	**0624.**
MLWN (Mean Low Water Neaps - Tides)	0624, **1045, 1050, 1062,** 1319.
MLWS(Mean Low Water Springs - Tides)	**1045, 1050, 1062,** 1319.
MNR (Mean Neap Range - Tides)	**1045-1046, 1050,** 1062.
MOB (Man OverBoard)	**1111.**
Modified Polyconic Projections	**App 4.**
Moiré Direction Light (Light characteristics)	**0930.**
Monsoon	**1125.**
Monsoon Current / Monsoon Drift	**1125.**
Mooring (Anchoring)	**1412.**
Mooring Swivel (Anchoring)	**1412.**
Morse Code (Fog signal)	**0934.**
Morse Code (Light characteristics)	**0930.**
Most Probable Position	See MPP.
Mozambique Current	**1124-1125.**
MPP (Most Probable Position)	**0712,** 1610, 1622, **1623, Anx 16B.**
MRE (Multiple Regression Equations)	**0324.**
MSAS (MTSAT Satellite Augmentation System)	**0915, 1806.**
MSL (Mean Sea Level - Tides)	**0311, 0624,** 0803, 0930, **1050, 1060, 1062,** 1313, 1820.
MSL Seasonal Variations (Tides)	See Seasonal Variation (MSL - Tides).
MSR (Mean Spring Range - Tides)	**1045-1046, 1050, 1052,** 1062.
MSR (Minimum Swing Radius - Anchoring)	1410, **1412.**
MTL (Mean Tide Level - Tides)	**1062.**
MTSAT **S**atellite **A**ugmentation **S**ystem	See MSAS.
MTSAT(Multi-functional Transport Satellite)	**0915,** 1806.
Multi-functional Transport Satellite	See MTSAT.
Multiple Regression Equations (MRE)	See MRE.
n.mile	See International Nautical Mile. General usage not listed.
NAD 27 (North American Datum 1927)	**0322.**
NAD 83 (North American Datum 1983)	**0321, 0322.**
Napier's Rules	0520, **App 2,** App 4.

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
National Hydrographic Offices	See NHO.
Nautical Charts (IMO - SOLAS)	**0632.**
Nautical Mile	See International Nautical Mile.
Nautical Twilight	**1051.**
Naval Gunfire Support	See NGS.
NAVAREA Warnings	**0615.**
Navigation	0622, **0630,** 0631-0632, 0701, 0716, 0721, 1231, 1238, **1910, 1912.**
Navigation Plan	See NavPlan.
Navigational Publications (UKHO)	See NP.
Navigational Record Book	**0716,** 0807-0808, **1238,** 1312, 1327, 1415, 1923, 1931-1932.
NAVPAC	0116, **0210,** 0211, 0521, 0550, **0551,** 0811, 1311.
Navplan / Navplans (Navigation Plan / Plans)	**1110, 1210, 1310-1312,** 1316-1320, 1323, **1330,** 1903, 1923, 1931.
NAVSTAR (GPS)	**0910.** See also GPS and DGPS.
NAVTEX	0615, **1230.**
NC (New Chart)	**0615, 0624,** 0626.
NE (New Edition - chart)	0611 **0615, 0624,** 0626. See also UNE.
NE Trade Winds	**1122.**
Neaps / Neap Tides	**1017-1018, 1020, 1051.**
Negative Surge (Tides)	**1022.**
NELS (NW European LORAN-C System)	**0912.**
New Chart	See NC.
New Edition (chart)	See NE.
New Moon (Tides)	**1017-1018, 1020.**
Newton's Universal Law of Gravitation	**1010.**
NGA (US National Geospatial & Chart Agency)	**0632.**
NGS (Naval Gunfire Support)	0322, **0331.**
NHO (National Hydrographic Offices)	**1022,** 1221, **1311.**
Night Vision Aids	**1531.**
nm / n.m	See International Nautical Mile. General usage not listed.
NMs (Notices to Mariners)	0611, 0614, **0615,** 0616, **0624,** 0626, 0931, 0941 1110-1111, 1210-1211, 1311, **1805, 1812.**
No Go Line	See LDL.
No Headmark (procedure)	**1313,** 1322.
NO's Pilotage Notebook	1210, **1238,** 1310, 1312, 1316, **1319,** 1322, 1413.
NO's Workbook	1110, 1210, **1214, 1238, 1312,** 1316, 1413.
Nominal Range (Light characteristics)	**0930-0932.**
Non-Homogeneous Geodetic Datums	**0324.** See also Homogeneous Geodetic Datums.
Nord Algerie Grid (Transverse Mercator)	**0453.**
Nord Maroc Grid (Transverse Mercator)	**0453.**
Nord Tunisie Grid (Transverse Mercator)	**0453.**
Normal Distribution (Navigational Errors)	**1611,** 1620-1621, **1623, Anxs 16A-16B.**
Normal MSR (Anchoring)	**1412.**
Normal Probability Distribution (Nav Errors)	See Normal Distribution.
North American Datum 1983	See NAD 83.
North Atlantic (Drift) Current	See North Atlantic Current.
North Atlantic Counter-Current	**1125.**
North Atlantic Current	**1125.**
North Equatorial Current	See Equatorial Currents (North and South).
North Pacific Current	**1125.**
North-Up (Radar / ARPA)	**1526-1527.**
Northwest European LORAN-C System	See NELS.
Notices to Mariners (NMs)	See NMs.
NP (Navigational Publication - UKHO)	0612, **0640.**
Oblate Spheroid	**0110, 0115,** 0208, 0310, 0540.
Observed Altitude (Sextant)	App 6. See also Altitude, True Altitude.
Observed Position (Astronomical)	**0711,** 0805.

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Obstruction Lights (Light characteristics)	**0931.**
Occasional Lights (Light characteristics)	**0930.**
Occulting (Light characteristics)	**0930.**
Ocean Navigation	**0721,** 1101, **1110-1111,** 1201, 1210-1211, 1234, **1911,** 1920, **1930.**
Officer in Tactical Command	See OTC.
Offset EBL (Offset Electronic Bearing Line)	**1317.**
Offset VRM (Offset Variable Range Marker)	**1317.**
One-way Routes (Traffic routing systems)	**1221.**
Onset Depth (SWE - Interaction)	**1220, 1234,** 1319.
% Onset Depth	See Onset Depth.
... % Onset Depth	See Onset Depth.
Open Service (Galileo)	See OS.
Oppos ition (Tides)	**1017.**
Optical Rangefinder	**0803.**
Ordnance Datum (Tides)	**1061.**
Ordnance Survey Great Britain 1936	See OSGB 36.
Orientation (Hydrographic Survey - charts)	**1803, 1813-1814, 1820, 1827.**
Orientation Modes (Radar / ARPA)	**1526, 1527,** 1722.
Orthogonal Position Lines	**1613-1616,** 1620, **Anx 16B.**
Orthomorphic / Orthomorphic Projection	**0411, 0414,** 0420- 0421, 0430, 0622, App 4.
Orthomorphism	See Orthomorphic / Orthomorphic Projection.
OS (Open Service - Galileo)	**0914.**
OSGB 36 (Ordnance Survey Great Britain 36)	**0322,** 0323-0324, 0331.
OSSN 80 (Datum)	**0322.**
OTC (Officer in Tactical Command)	**1110-1111, 1210.**
Overfall / Overfalls (Tides)	**1044.**
Overhead Clearances	**1310-1312, 1320.**
Oya Shio Current	See Kamchata Current.
Parallel / Parallels	See Parallels of Latitude.
Parallel Index / Parallel Indices	See PI.
Parallel Sailing	0201, **0203,** 0204, 0501.
Parallels of Latitude	**0111-0112,** 0115, 0202-0205, **0313,** 0411-0412, 0414, 0420, **0421,** 0422-0423, **0424,** 0431, 0450, 0511, 0520, 0521, 0540, 0541, Apps 3-5. See also Latitude.
Passage Graph	**1112,** 1113, 1214, 1234.
Patch Antenna (DGPS / GPS)	**1806.**
PCS (Propulsion Control System)	**1236.**
PDF (Probability Density Function)	**Anx 16A.**
Pelorus (Bridge)	**0802,** 1230, 1319, 1413.
Percentage of the Day (Tides)	See Percentage Springs.
Percentage Onset Depth (SWE - Interaction)	See Onset Depth.
Percentage Springs (Tidal Streams)	**1045-1046,** 1319.
% Springs	See Percentage Springs.
... % Springs	See Percentage Springs.
0% Springs (MNR)	**1045.**
100% Springs (MSR)	**1045.**
Perigean Tide (Tides)	**1015.**
Perigee (Tides)	**1015.**
Perihelion (Tides)	**1016.**
Period (Light characteristics)	**0930.**
Perpendicularity (Sextant)	**App 10.**
Personal Error (Sextant)	**App 10.**
Persons on Board (AIS field)	See POB.
Perspective Conformal Projection	See Perspective Projection.
Perspective Projection	**App 4.**
Peru (Humbolt) Current	**1124-1125.**
Phase (Light characteristics)	**0930.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Phase Lag (Tidal Harmonic Constituents)	**1031.**
Physical Surface (Earth - Oblate Spheroid)	**0311.**
Pilotage	0610, 0612, 0714, 0716, **0721,** 0807, 0808, 0923-0924, 0926, 0942, 1111, 1201, 1222, 1230, 1234, 1301, **1303-1305,1310-1319, 1320-1325, 1327-1328,** 1331, 1401, 1413, 1415, 1425, 1501, **1527, 1910-1912, 1921-1925, 1931-1933.**
Pilots (Admiralty Sailing Directions)	See Sailing Directions.
Pin-Mast	**1230.**
PIs (Parallel Index / Parallel Indices)	**1210, 1214,** 1231, **1232,** 1233-1234, 1310, **1316,** 1317, 1319, 1325, 1328, 1330, **1521,** 1522, 1527, **1528,** 1922, 1924, **1933.**
Pitometer Speed Logs	**0925.**
Pivot Point (Manoeuvring)	**0714,** 1314, 1332 **1334,** 1417.
Plane Sailing	0201, **0204,** 0206, 0501, 0511.
Plane Triangle	**Apps 1-2,** App 4.
Planning (Navigation)	**1910-1911.**
POB (Persons on Board - AIS field)	**0950.**
Point of No Return (Pilotage)	**1312.**
Points (Compass)	**0123,** 0126, 0806.
Polar (Axis / Radius)	**0110,** 0115, 0310, **0311, 0313,** 0541, App 5.
Polar (Charts)	See Polar Stereographic Projection.
Polar (Regions)	0910, 0913, **0920,** 1515.
Polar Coordinates	**0206.**
Polar Cosine Rule (Trigonometry)	**App 2.**
Polar Easterlies (Winds)	**1122.**
Polar Stereographic Projection	**0414,** 0450, 0621, 0920, App 4.
Polar Triangle (Trigonometry)	**App 2.**
Pole / Poles / Polar (North or South)	**0110,** 0113-0116, 0203, 0208-0209, 0211, 0311-0314, 0324, 0411, **0414,** 0421-0422, 0425, 0431, 0451, 0520, 1122, App 2, Apps 4-5.
Pole Logship (Tidal Stream observation)	**1816.**
Polyconic Projection	**0414, 0622,** App 4.
Portable Survey System (Hydrog. Survey)	See PSS.
Portugal Current	**1125.**
Position Circle / Circles	0620, **0808, 1603, 1623,** App 4, App 10.
Position Line / Lines	**0710, 0711,** 0712, 0803-0805, **0806,** 0808, 0933, 1212, 1312, 1415, **1530,** 1601-1603, 1610-1623, Anxs 16A-16B, App 6, App 10.
Position Probability Area	See PPA.
Positive Surge (Tides)	**1022.**
PPA (Position Probability Area)	**0710, 0712,** 1530, 1610, **1622-1623.**
PPS (GPS - Precise Positioning Service)	**0910.**
Precautionary Areas (Traffic routing system)	**1221.**
Precession (Gyroscopic)	**0920.**
Precise Navigation	**0324.**
Precise Positioning Service (GPS)	See PPS.
Precision (Navigational Errors)	**1602.**
Preliminary Notices to Mariners	See T&Ps.
Presentation Modes (Radar / ARPA)	**1526-1527,** 1722.
Pressure Zone (Interaction)	**1220,** 1332.
PRF (Pulse Repetition Frequency)	**1510.**
Prime / Priming (Tides)	**1017.**
Prime Meridian (Greenwich Meridian 0˚)	**0110,** 0111, 0114, **0423,** 0431, 0451-0452, 1214.
Principal Meridian	See Central Meridian.
Probability Density Function (Nav Errors)	See PDF.
Probability Heap (Navigational Errors)	**Anx 16B.**
Probable Error (Navigational Errors)	See LEP.
Projection / Projections / Projected (chart)	0401, **0410-0411,** 0412-0414, 0420, 0431, 0450, App 4.
Propulsion Control System	See PCS.
PRS (Public Regulated Service - Galileo)	**0914.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Pseudo AIS (contact)	See Virtual AIS.
Pseudo Ranging (GPS)	**0910, 0911.**
PSS (Portable Survey System)	**1827.**
Public Regulated Service (Galileo)	See PRS.
Pulse Length (Radar)	**1511, 1513,** 1519, **1521, 1523.**
Pulse Repetition Frequency (Radar)	See PRF.
PZ 90 (GLONASS Datum)	**0913.**
Quadrantal Spherical Triangle	**App 2.**
Quadrature (Tides)	**1017.**
Quadrifilar Helix Antenna (DGPS / GPS)	**1806.**
Quartering Bearings (Pilotage)	**1314,** 1322.
Quick Flashing (Light characteristics)	**0930,** 0941.
Race / Races (Tides)	**1044.**
Racon (Radar Transponder)	1518, **1529.**
Racon Flash (Radar Transponder)	**1529.**
Radar Image Overlay	See RIO.
Radar Reflectors	**1518.**
Radial Error (Nav Errors - RMS Error)	**1612, 1615, Anx 16B.**
Radial SD (Radial Standard Deviation)	**1612.**
Radial Standard Deviation (Nav Errors)	See Radial SD.
Radian Rule	**0127,** 0805-0806, 0811, 1312, 1319, **1322,** 1324, 1522, Anx 16B.
Radio Navigational Warnings	**0615,** 1311.
Radius of Curvature (Earth)	**0113, 0314, 0421,** App 6.
Ramark (Radar Beacon)	1518, **1529.**
Ramark Flash (Radar Beacon)	**1529.**
Random Errors (Navigational Errors)	0811, 1603, **1610-1611**, 1614, 1620, **1621, 1623 Anxs 16A-16B,** App 10.
95% Random Errors (Nav Errors)	**1623.**
Range (Tidal)	0624, 0942, **1014, 1020-1021, 1031, 1040, 1052,** 1062, 1313, 1820, 1828.
Range Discrimination (Radar)	**1511.**
Range Lattices (Fixing)	**0805.**
Range of the Day (Tidal Stream Predictions)	**1042, 1045.**
Rangefinders	See Optical Rangefinder and Laser Rangefinder.
RAS (Replenishment at Sea)	0811, 1110-1111, 1210, **1220,** 1238, 1327.
Raster / Raster Navigation Charts	See RNC.
Rate for the Day (Tidal Nurdle)	**1046.**
Recommended Tracks (Traffic routing)	**1221.**
Rectangular Distribution (Nav Errors)	**Anx 16A.**
Rectangular Errors (Navigational Errors)	1620, **Anx 16A.**
Rectilinear Tidal Streams	**1040.**
Reduced Latitude	See Parametric Latitude.
Reduced MSR (Anchoring)	**1412.**
Reed (Fog signal)	**0934.**
Region B (IALA Maritime Buoyage System)	**0941.**
Region A (IALA Maritime Buoyage System)	**0941.**
Regional Geodetic Datums (Spheroid)	**0311, 0321,** 0324.
Relative Bearing / Relative Bearings	**0126,** 0803,1230.
Relative Distance (Rel Vel)	**1735.**
Relative Motion (Radar / ARPA)	1316, **1526-1527, 1703,** 1712, 1720, 1721.
Relative Motion (Vector)	**1710,** 1712.
Relative Navigation	See RELNAV.
Relative Position (Navigational Errors)	**1602.**
Relative Speed (Rel Vel)	**1710, 1711,** 1712-1713, 1720, 1722, 1732-1736.
Relative Target Trails (Radar / ARPA)	**1526-1527.**
Relative Track (Radar)	0713, **1703, 1711,** 1712-1714, 1720, 1722, 1732-1736.
Relative Vectors (Radar / ARPA)	**1526-1527.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Relative Velocity	**1701, 1702, 1715, 1720, 1722, 1730.**
RELNAV (Relative Navigation)	**1321, 1922.**
Repeatability (Navigational Errors)	**1602.**
Replenishment at Sea	See RAS.
Resection (Fixing)	**1811.**
Restricted Visibility	See Fog.
Retroflector (Buoyage System)	**0941.**
Rhumb Line	0110, **0202,** 0204-0205, 0207, 0209-0210, 0414, 0421-0422, 0425, **0441- 0442,** 0511, 0521, 0530-0531, 0551, 1110, App 3, App 5. See also Course & Distance.
Rhythmic (Light characteristics)	**0930.**
Rigidity-in-Space (Gyroscope)	**0920.**
Ring Laser Gyros	See RLG.
RIO (Radar Image Overlay)	**0720,** 1231-1232, **1321,** 1323, 1415, 1528, 1921, 1923-1924.
Rising Range (Lights)	**0933.**
RLG (Ring Laser Gyros)	**0920,** 0921.
RMS Error (Root Mean Square Error)	**1611-1612, Anxs 16A-16B.**
RNC (Raster Navigation Charts)	0331, 0614- 0616, 0631, **0632-0633,** 0902, 0919, 0930, 0940, 1110, 1210, 1214, 1317, 1911.
Roaring Forties	**1122.**
Root Mean Square Distance (Nav Errors)	See d[rms].
Root Mean Square Error (Nav Errors)	See RMS Error.
Rose	See Compass Rose.
Rose Correction	See Compass Rose Correction.
Rotary Tidal Streams	**1040.**
Rounding-Off Error (Navigation Errors)	1611, **Anx 16A.**
Run-back (Transferred Position Line)	**0804,** 0805.
Running Anchorage	**1414,** 1418, **1420.**
Running Fix	0804, **0805, 0806.**
Running Survey	**1814.**
Run-on (Transferred Position Line)	**0804, 0805.**
Safe Latitude	See Safe Parallels of Latitude.
Safe Parallel	See Safe Parallels of Latitude.
Safe Parallels of Latitude	**0209, 0442, 0522,** 0622.
Safe Water Marks (Buoyage System)	**0941.**
Safety of Life Service (Galileo)	See SoL.
Safety Swinging Circle	**1410, 1412-1413, 1415.**
Sailing Directions (Admiralty Pilots)	0612, **0640,** 0712, 0930, 0940- 0941, 1042, 1110 -1111, 1221, 1234, 1311, 1323, **1812,** 1816, **1830,** 1831.
Sailings (Methods)	**0201,** 0207, **0208-0209,** 0501, **0511,** 0550.
SAME Name (Hemispheres)	**0208, 0211.**
Sandwaves	1213, **1234.**
SAR (Search and Rescue Service - Galileo)	**0914.**
SART (Search and Rescue Transponder)	**1518, 1529.**
Satellite Based Augmentation Systems	See SBAS.
SBAS (Satellite Based Augmentation Systems)	**0915.**
Scale (General)	0113, 0124, 0324, 0610-0611, 0620, **0622-0626,** 0631, 0713, 0716, 0805, 0810, 0930, 0940, 1046, 1060, 1110-1112, 1210, 1214, 1310-1312, 1321, 1410, **1521, 1803, 1813-1814, 1820,** 1822-1823, 1825-1828, 1830, 1924, App 3-4, App 6.
Scale (Projection property)	**0411,** 0413-0414, 0421, 0423-0424, 0431.
Scale Error (Hydrographic Survey)	**1820.**
Scale Factor (Tidal Nurdle)	**1046.**
Scale Factor (Transverse Mercator Grids)	**0450.**
Scend [or 'Send'] (Waves)	**1410.** Scend is the vertical movement of waves or *Swell* alongside a wharf, jetty, cliff, rocks etc.

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
SD (Standard Deviation)	**1611,** 1614, 1616, **Anxs 16A-16B.**
2SD (Twice Standard Deviation)	**1611.**
SE Trade Winds	**1122.**
Sea Command (Ships et al)	**1910.**
Sea Ice	**1531.**
Sea Mile	**0113,** 0114, 0202, 0314, 0421- 0422, 0424, 0623, **0803,** 0925, 0930, 0932, 1515, 1524, App 5.
Sea Orders / Sea Order Book (Command)	**1912.**
Sea Speed (Rel Vel)	**1703,** 1722.
Sea Stabilised (Radar / ARPA)	**1526, 1527, 1703,** 1722.
Seafarer (RNCs)	**0632.**
Search and Rescue Service (Galileo)	See SAR.
Search and Rescue Transponder (Radar)	See SART.
Seasonal Variation (MSL - Tides)	**1050-1060.**
Secant Projections	**0413.**
Secondary Ports (Tides)	**1030, 1050,** 1053, 1060, **1828.**
Sector Light (Light characteristics)	**0930.**
Seiche (Tides)	**1022.**
Seismic Waves (Tsunamis)	**1023.**
Self Organising TDMA (AIS)	See SOTDMA.
Semi-Diurnal / Semi-Diurnal Tidal Streams	**1040, 1042, 1045-1046,** 1816.
Semi-Diurnal / Semi-Diurnal Tides	**1014-1018, 1020, 1030, 1050,** 1062.
Semi-Systematic Errors (Navigational Errors)	**1610,** 1611, 1621.
Separation Line (TSS)	**1221.**
Separation Zone (TSS)	**1221.**
Set	**0713,** 0720, 0806, 1527, 1603, App 7.
Sextant	**App 10.**
SGS 90 (Soviet Geocentric Co-ord System)	**0913.**
Shadow Zones (Radar)	**1519, 1530.**
Shallow Water Effect (Interaction)	See SWE.
Shallow Water Effects / Corrections (Tides)	**1021, 1031-1032.**
Shape (Hydrographic Survey)	**1820.**
Shape (Projection property)	**0411,** 0414.
Ship Proximity Interaction	See Interaction.
Ship Reporting Systems (Routing Systems)	**1240.**
Ship's Head	See Heading.
Ship's Log	**0716,** 1230, **1238, 1415.**
SHM (Simplified Harmonic Method) - Tides	**1032 ,1050.**
SHM for Windows® (UKHO Tides software)	**1032 ,1042, 1050,** 1311.
Side Error (Sextant)	**App 10.**
Sight Reduction Method (Astro)	**0210.**
Sigma	See σ.
σ [Sigma] (Navigational Errors)	**1615-1616, 1621 Anx 16A, Anx 16B.**
1σ [1 Sigma] (Nav Errors - Linear SD)	**1602, 1611, 1613,** 1614, **1615, Anxs 16A-16B.**
2σ [2 Sigma] (Nav Errors)	**1602, 1611, 1615,** 1620, 1621, **Anx 16A.**
3σ [3 Sigma] (Nav Errors)	**1602,** 1621, **Anx 16A.**
σ_r [Sigma $_r$] (Nav Errors, Radial SD)	**1612, Anx 16B.**
$2\sigma_r$ [2Sigma $_r$] (Nav Errors)	**1615.**
Simple Conical Orthomorphic Projection	See Conical Projections.
Simplified Harmonic Method (UKHO Tides)	See SHM and SHM for Windows®.
Simplified Symbols (ENC - IHO S.52)	**0632.**
Sine Formula / Method / Rule etc	0210, **0211,** 1322, 1820, **1825, Apps1- 2.**
Single Normal MSR (Anchoring)	**1412.**
Single Reduced MSR (Anchoring)	**1412.**
Siren (Fog signal)	**0934**
SIRGAS (South American International Geodetic Reference System)	**0321.**
Skew Orthomorphic Projection	0411, **0414.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Small Circle	**0110,** 0111, 0115, 0208, 0803, 1013, App 2, App 4.
Small Corrections (Obsolete from 2000)	**0624,** 0626.
Smelling the Ground (Interaction)	**1220, 1332.**
SMG (Speed Made Good)	See Ground Speed.
SOA (Speed of Advance)	**1110-1112, 1210-1211, 1214,** 1234.
SOCs (Standard Operator Checks)	**1230.**
SOG (Speed Over the Ground / Ground Speed - AIS field)	**0951.**
SoL (Safety of Life Service - Galileo)	**0914.**
Solar Day (Tides)	**1016.**
Solar Equilibrium Tide (Tides)	**1016.**
Solar Semi-Diurnal Harmonic Constituent	**1031.**
SOLAS (Safety Of Life At Sea)	**0631, 0632,** 1525.
Solstice / Solstitial Tides (Tides)	**1016-1017, 1020,** 1902.
Somali Current	**1125.**
Sonar Speed Logs	**0925.**
SOTDMA (Self Organising TDMA - AIS)	**0951.**
Sounding Board (Hydrographic Survey)	**1821, 1827.**
Sounding Book (Hydrographic Survey)	**1827.**
Sounding Datum (Hydrographic Survey)	**1820, 1827-1828, 1831.**
Sounding Marks (Hydrographic Survey)	**1820, 1824, 1826.**
Source Data (Diagram - charts)	**0624-0626,** 0805.
South Equatorial Current	See Equatorial Currents (North and South)
Southern Ocean Current	**1122, 1124-1125.**
Soviet Geocentric Co-ordinate System 1990	See SGS 90.
Spatial Correlation (Speed) Logs	**0925.**
Special Marks (Buoyage System)	**0941.**
Special Sea Dutymen	See SSD.
Speed Factor (Manoeuvring Data)	See Acceleration Distance.
Speed Log	0712, 0920, **0925,** 1526-1527, 1603, 1622, 1722, 1814.
Speed Made Good	See Ground Speed.
Speed of Advance	See SOA.
Speed Over the Ground (Ground Speed - AIS)	See SOG.
Sphere / Spherical (Earth)	**0110,** 0114, **0115-0116,** 0201, 0203-0205, 0208-0211, 0310-0311, 0313, 0315, 0330, **0332,** 0413, 0414, 0420, 0422, 0440, 0510, 0520, 0530, 0550, 0551, 1012, App 2, App 4.
Sphere / Spheres (Soft-iron, Magnetic Compass)	**0122,** 0125, **1230.**
Spherical Distance (Geodesic)	See Distance (Geodesic - Spherical).
Spherical Great Circle Composite Track	0501, **0522.**
Spherical Great Circle Sailing	0501, **0521,** 0551. See also Great Circle.
Spherical Mercator Sailing	**0511.**
Spherical Meridional Parts	**0511.**
Spherical Sailing	0201, 0207, **0208-0209.**
Spherical Triangle	0520, **App 2,** App 4.
Spheroid / Spheroidal (Earth)	0101, 0111, 0114, **0116,** 0201, 0205, 0207-0208, 0210, **0311,** 0312-0313, 0315, 0320, **0321,** 0322, 0330-0331, 0332, 0410, 0413-0414, 0420-0422, 0424, 0440, 0450, 0452, 0530, 0531, 0540, 0541, 0550, 0551, 0711, 0913, Apps 4-5. See also Datum, Oblate Spheroid and WGS 84.
Spheroidal Arc (Transverse Mercator Grids)	**0450.**
Spheroidal Corrections (Geodesic)	**0541.**
Spheroidal Great Circle Sailing	**0501.**
Spheroidal Meridional Parts	App 5.
Spheroidal Projection	**0414.**
Spheroidal Rhumb Line Sailing	**0501.**
Spin Axis (Gyroscope / Gyro Compass)	**0121, 0920,** 0921
Spring Tides / Springs	0712, **1017-1018, 1020, 1051,** 1330, 1816.
SPS (Standard Positioning Service - GPS)	**0910, 0917.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
Square Corner Reflectors (Radar)	**1518.**
Squat (Interaction)	1213, **1220,** 1234, 1311, **1332, 1807, 1827.**
Squint Error (Radar)	**1522.**
SR (SunRise)	**0715, 1110, 1210,** 1214, 1311.
SS (SunSet)	**0715, 1110, 1210,** 1214, 1311.
SSD (Special Sea Dutymen)	0924, **1230,** 1312, 1327, **1912, 1923-1924, 1931-1933.**
Stabilisation Modes (Radar / ARPA)	**1526, 1527,** 1722.
Stand (Tides)	**1021.**
Standard Deviation (Navigational Errors)	See SD.
Standard Distance (NATO - Manoeuvring)	**1412.**
Standard Operator Checks	See SOCs.
Standard Parallel / Parallels (Projections)	**0413,** 0414, 0421, App 4.
Standard Port (Tides)	**1021, 1030, 1040, 1042, 1046, 1050,** 1053, **1828.**
Standard Positioning Service (GPS)	See SPS.
Station Pointer	**0808, 0810-0811,** 1811, 1820-1821, 1826-1827, App 6, App 10.
Statute Mile	**0113.**
Steady Turning Diameter (Manoeuvring)	**1314.**
Steadying Point (Manoeuvring Data)	**1314.**
Stereographic Projection	0411, **0414.**
Stern Rope (Berthing)	**1424-1425.**
Stern Swinging Circle	**1415,** 1418, **1816.**
Sternboard (Manoeuvring)	1417, **1420, 1422,** 1425. A *Sternboard* is a prolonged movement of a vessel astern under its own power, usually for a distance of at least 1 cable or more. *Sternboards* are often carried out by warships when unberthing.
Sternmark / Sternmarks	0942, 1310, 1312-1313, 1319, 1321, **1322,** 1324, 1923, 1931.
Stern-to Berthing (Anchoring)	1412, **1420-1424.**
Storm Surges	**1022,** 1060, 1062, 1812.
Stripes (Light Structure Descriptions)	**0930.**
Sublunar / Sublunar Point (Tides)	**1012-1013, 1015.**
Sub-Refraction	**1515.**
Subsidiary Light (Light characteristics)	**0930.**
Subtense Method (Hydrographic Survey)	**1820.**
Suction Zone (Interaction)	**1220,** 1332.
Sud Algerie Grid (Transverse Mercator)	**0453.**
Sud Maroc Grid (Transverse Mercator)	**0453.**
Sud Tunisie Grid (Transverse Mercator)	**0453.**
SunRise	See SR.
SunSet	See SS.
Super-Refraction	**1515,** 1529, 1530.
Surface Current / Surface Drift	**0712-0713,** 0715, 0925, **1002, 1040 1120,** 1121, **1122**.
Surface Drift	1603.
Surface Drift Current	See Surface Current / Surface Drift.
SWE (Shallow Water Effect - Interaction)	**1220,** 1234, 1312, 1319, 1322, 1332-1333.
SWE Onset Depth (Interaction)	See Onset Depth.
Swell	1213, **1410.** *Swell* is the wave motion caused by a meteorlogical disturbance, which persists after the disturbance has died down or moved away.
Swept Gain (Radar)	**1513, 1514,** 1520.
Systematic Errors (Navigational Errors)	1603, **1610,** 1611, 1620, App 10, **Anx 16B.**
T&Ps (Temporary and Preliminary NMs)	**0615,** 1110- 1111, 1210, 1311.
Tactical Diameter (Manoeuvring Data)	**0714,** 1314.
Tactical Miles	**1520.**
Tactical Navigation	**1911.**
Tangent Projections	**0413.**
Tangential Plane	**0330,** 0332-0333.
TCPA (Time to CPA)	**1526.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
TDMA (Time Division Multiple Access - AIS)	**0951.**
Tectonic Plates (Seismic Waves)	**1023.**
Temperature Inversion	**1515.**
Temporal Correlation (Speed) Logs	**0925.**
Temporary and Preliminary NMs	See T&Ps.
Temporary NMs	See T&Ps.
Ten-Foot Pole	**1813, 1821, 1827, 1829.**
Territorial Sea	1110, **1111, 1210-1211,** 1221, **1802.**
Thames AIS	See Inland AIS.
Threshold Level (Radar)	**1510,** 1526.
Tidal Bore	See Bore.
Tidal Nurdle (Tidal Stream Predictions)	**1046.**
Tidal Current (American for Tidal Stream)	**1002, 1040.**
Tidal Curve (Hydrographic Survey)	**1827, 1829.**
Tidal Levels	1050, **1060-1061.**
Tidal Stream / Tidal Streams	0624, **0712-0713,** 0715-0716, 0804- 0806, 0916, 0925, 0942, 1001, **1002, 1032, 1040,** 1041, **1042-1043, 1045-1046,** 1051, 1053, 1112, 1120, 1210, 1212, 1214,1222, 1231, 1234, 1236, 1238 1310-1312, 1314, 1316, 1319-1320, 1322-1324, 1328, 1330-1331, 1333, 1410-1412, 1414-1415, 1417-1419,1527, 1603, 1621, Anx 16A, 1722, 1804, 1811, 1813, **1816,** App 7.
Tidal Stream Atlas / Atlases	0712, **1042,** 1044, **1045,** 1046
Tidal Waves (Tides - NOT Seismic Waves)	**1020 -1023.**
Tide / Tides	0712, 1001, **1002, 1010, 1012-1017, 1020-1022, 1040,** 1042-1044, **1050, 1052,** 1062, 1213, 1234, 1240, 1323, 1410, 1415, 1420, 1816, 1820, 1828, 1830.
Tide Pole (Hydrographic Survey)	**1821, 1828.**
Tide Raising Force / Effect	1002, **1010, 1013-1018, 1020, 1030-1031,** 1040-1041.
Tide-Rip / Tide-Rips	See Overfall.
Time Division Multiple Access (AIS)	See TDMA.
Time to CPA	See TCPA.
Time Zones	**1110,** 1111, 1210, **1214,** 1238, **1828.**
TotalTide® (UKHO tides software)	0712, 1001, **1042,** 1046, **1050-1051,** 1214, 1311.
Track Control (Manoeuvring)	1211, **1236.**
Track Control System	**1236.**
Tracking (Radar / ARPA)	**1703.**
Tractive Force	See Tide Raising Force.
Trade Winds	**1122,** 1515.
Traditional Symbols (ENC - IHO S.52)	**0632.**
Traffic Lanes (TSS)	**1221.**
Traffic Separation Scheme	See TSS.
Transfer (Manoeuvring Data)	**0714,** 1310-1311, **1314,** 1315.
Transferred Position Line	**0710, 0804, 0805, 0806.**
Transponder (Radar)	**1518,** 1520, **1529.**
Transverse Mercator Projection	0411, **0414, 0430, 0431, 0450,** 0451, 0611, 0621-0622, **0623,** 0624, App 4.
Transverse Mercator Projection Grid	**0450, 0451.**
Traverse Sailing	0201, **0206,** 0501.
Trial Manoeuvres (ARPA)	**1526.**
Triangulation (Hydrographic Survey)	**1820,** 1821, **1822, 1825, 1827, 1831.**
Triangulation Station (Hydrographic Survey)	**1820, 1824- 1827, 1829.**
Trim (Squat / Interaction)	**1220.**
Tropical Storms	**1812.**
True Altitude (Sextant)	App 4, **App 6.** See also Altitude, Observed Altitude.
True Easting (Transverse Mercator Grid)	**App 4.**
True Horizontal Angle (Hydrographic Survey)	**1824.**
True Latitude	**0111.**

INDEX-GLOSSARY (*ITALICISED TERMS*)

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
True Motion (Radar / ARPA)	1316, **1526-1527, 1703,** 1712, 1721.
True North	**0120,** 0121-0122, 0450.
True Northing (Transverse Mercator Grid)	**App 4.**
True Speed (Rel Vel)	1711, **1712,** 1713, 1720, 1722, 1732, 1736.
True Target Trails (Radar / ARPA)	1316, **1526-1527, 1722.**
True Track (Rel Vel)	0713, 1711, **1712,** 1713, 1720, 1722, 1732, 1734-1736.
True Vectors (Radar / ARPA)	**1526-1527.**
TSS (Traffic Separation Scheme)	0611, 0941, 1110-1111, 1210- 1211, **1221,** 1240.
Tsunamis (Seismic Waves)	**1023,** 1812.
Turning at Rest (Manoeuvring)	0803, **1322.**
Turning Circle (Manoeuvring)	**0714,** 1314, 1322-1323.
Two-way Routes (Traffic routing systems)	**1221.**
Typhoons	**1812.**
UK Transverse Mercator Projection (UKTM)	**0452.**
UKHO (UK Hydrographic Office)	0111, 0207-0208, 0322, 0323, 0601, **0610,** 0611-0616, 0624, 0640, 0712, 0803, 0805, 0901, 1032, 1042, 1050,1060-1062, 1111, 1115, 1211, 1214, 1221, 1240, 1311, 1313, 1521, 1802-1803, 1805, 1812, 1814-1815, 1820, 1826-1829, 1831, App 6.
Ultra Quick Flashing (Light characteristics)	**0930.**
Underkeel Clearances	**1022,** 1051, **1052, 1210, 1212-1213, 1220, 1234,** 1310, **1311,** 1312, 1319, 1328, 1410.
UNE (chart - Urgent New Edition)	**0615, 0624.** See also NE.
Uninterruptible Power Supply	See UPS.
Union Jack	**1230.**
United Kingdom Hydrographic Office	See UKHO.
Universal Polar Stereographic Projection	**0414.**
Universal Transverse Mercator	See UTM .... (Grid, Projection, Zones etc).
UPS (Uninterruptible Power Supply)	**0631.**
Urgent New Edition (chart)	See UNE.
US National Geospatial & Chart Agency	See NGA.
UTM Grid (Universal Transverse Mercator)	**0431,** 0450, **0451,** 0452.
UTM Grid East / Eastings	**0451.**
UTM Grid North / Northings	**0421,** 0450, **0451.**
UTM Projection	**0414, 0451.**
UTM Zones of Longitude	**0451,** 0452. See also Zones of Longitude.
Variable Range Marker	See VRM.
Variance (Navigational Errors - Mean Square)	**Anx 16A.**
Variation (Magentic)	**0122-0124,** 0125, 0454, 0624, 0807, 0811, 1820.
Vector (chart)	0614, **0632.**
Velocity Of Sound (In water)	See VOS.
Velocity Triangle (Rel Vel)	**1713, 1720,** 1721-1722, 1730, 1734-1736.
Velocity Triangle Rules (Rel Vel)	**1714,** 1720, 1730.
Velocity Vector Modes (Radar / ARPA)	**1526-1527,** 1722.
Vertex / Vertices (Great Circle)	0201, 0207, **0209, 0442, 0520-0521,** 0522, App 2, App 4.
Vertex Latitude (Great Circle)	**0520,** App 4.
Vertex Longitude (Great Circle)	**0520,** App 4.
Vertex / Vertices (Great Circle)	0201, 0207, **0209, 0442, 0520-0521,** 0522, App 2, App 4.
Vertical Clearances	**0624,** 1051, **1062, 1820.**
Vertical Control (Hydrographic Survey)	**1820.**
Vertical Danger Angle	**0803, 1233.**
Vertical Datums (Tides)	**0320,** 1051, **1062.**
Vertical Lights (Light characteristics)	**0930.**
Vertical Sextant Angle	See VSA.
Very Quick Flashing (Light characteristics)	**0930,** 0941.
Vessel Traffic System	See VTS.
Vigias (Hydrographic Survey)	**1815.**
Virtual AIS (contact symbols)	**0952 0954.**

Italicised Technical Term	**Primary / Secondary References (Primary References in BOLD)**
VOS (Velocity Of Sound - in water)	**1807.**
VRM (Variable Range Marker)	**1317,** 1720, 1933.
VSA (Vertical Sextant Angle)	**0803,** 0805, **1813, 1829,** 1830, App 6.
VTS (Vessel Traffic System)	0952, **1221,** 1240-1241, 1320, 1323.
WAAS (Wide Area Augmentation System)	**0915, 1806.**
W-AIS (Warship AIS)	**0950.**
Warship Automatic Identification System	See W-AIS.
Warship Electronic Chart Display Information System (Warship ECDIS)	See WECDIS.
Water Track (Course steered)	**0713,** 0806, **1703,** 1722.
Wave of Translation (Canal Effect / Interaction)	**1220.**
Wavelength (Radar)	**1514, 1523**
Waypoint / Waypoints (Great Circle)	**0414, 0440-0441,** 0442, **0521,** 0622.
Waypoint / Waypoints (Track / Route)	0714, **0720, 0951, 1211, 1236, 1827, 1829.**
WECDIS (Warship ECDIS)	*WECDIS* comprises an *IMO*-approved *ECDIS* with additional functionality for military purposes in warships. **0210, 0331,** 0451, 0550, **0551,** 0613, **0631-0632,** 0701, 0712, 0714-0716, **0720-0721,** 0805, 0808, 0811, 0910, 0919, 0950, 1051, 1102, 1110, 1113, 1202, 1210, 1214, 1222, 1230, **1231,** 1232, 1236, **1238,** 1302, **1311,** 1312-1314, 1316, **1317,** 1319-1320, **1321,** 1323-1325, 1327-1328, 1402, 1413, 1415, 1502, **1528,** 1701, 1702, **1806, 1810, 1814-1815, 1827,** 1903, **1911,** 1920, **1921-1925.**
Weekly NMs	See NMs.
Weekly Notices to Mariners	See NMs.
West Australian Current	**1125.**
WGS 72 (Datum / Spheroid)	**0321-0322, 0324.**
WGS 84 (Datum / Spheroid)	0110, 0115, 0310, 0312- 0313, **0321-0322,** 0323, **0324,** 0331-0332, 0423, 0452, 0531, 0551, 0624, 0805, 0910, 0913, 0918, 0931, 1321, 1602, 1803, 1811, **1820,1829,** App 5. See also Datum, Oblate Spheroid and Spheroid.
Wheel-Over	0714, 0715, 0804, 0807, 1234, 1310, 1312, **1314, 1316,** 1319, **1322,** 1323, 1328, 1413, 1923-1924, 1932.
Whistle (Fog signal)	**0934, 0940.**
Wide Area Augmentation System	See WAAS.
Williamson’s Turn (Manoeuvring)	**1827.**
Wind Sheer	**1332, 1334.**
World Geodetic System (WGS)	See WGS 84 and GNSS.
Yaw / Yaws / Yawing	0120, **1418,** 1419.
Yaw (Naval Command Systems)	0120.
Zenith	**0116.**
Zenithal Projection	**0413,** 0440.
Zero-PIM (Zero Position / Intended Move’t)	1111, **1112.**
Zero-PIM	**1214.**
Zero Pitch (Controllable Pitch Propeller)	**1332**
Zero Position / Intended Movement	See Zero-PIM.
Zones of Longitude (Transverse Mercator)	**0431.**

INTENTIONALLY BLANK


END
START
LINE OF SIGHT

250,000CM
8CM





U.S. ARMY MAP READING AND LAND NAVIGATION HANDBOOK


UNKNOWN LOCATION
POSITION A
POSITION B


TICK MARK
TICK MARK
TICK MARK
TICK MARK



DEPARTMENT OF THE ARMY

RIDGELINE
RIDGELINE


W
E
90°
90°
180°
360°
90°


NORTH POLE
SOUTH POLE
NORTH POLAR AREA
SOUTH POLAR AREA

DEPARTMENT OF THE ARMY

MAP READING
AND
LAND NAVIGATION


B
250,000CM
A
B
8CM
A

Special contents of this edition copyright © 2004 by the Lyons Press

All Rights Reserved. No part of this book may be reproduced or transmitted in any form by any means, electronic or mechanical, including photocopying and recording, or by any information storage and retrieval system, except as may be expressly permitted in writing from the publisher. Requests for permission should be addressed to The Lyons Press, Attn: Rights and Permissions Department, P.O. Box 480, Guilford, CT 06437.

The Lyons Press is an imprint of The Globe Pequot Press.

10 8 6 4 2 1 3 5 7 9

Printed in the United States of America

ISBN 1-59228-382-9

The Library of Congress Cataloging-in-Publication Data is available on file.

Copyrighted material

DEPARTMENT OF THE ARMY

MAP READING AND LAND NAVIGATION

CONTENTS

Page

PREFACE v

Part One
MAP READING

CHAPTER 1. TRAINING STRATEGY

1-1. Building-Block Approach 1-1
1-2. Armywide Implementation 1-2
1-3. Safety 1-2

CHAPTER 2. MAPS

2-1. Definition 2-1
2-2. Purpose 2-1
2-3. Procurement 2-2
2-4. Security 2-3
2-5. Care 2-3
2-6. Categories 2-3
2-7. Military Map Substitutes 2-7
2-8. Standards of Accuracy 2-8

CHAPTER 3. MARGINAL INFORMATION AND SYMBOLS

3-1. Marginal Information on a Military Map 3-1
3-2. Additional Notes 3-5
3-3. Topographic Map Symbols 3-5
3-4. Military Symbols 3-6
3-5. Colors Used on a Military Map 3-6

CHAPTER 4. GRIDS

4-1. Reference System 4-1
4-2. Geographic Coordinates 4-1
4-3. Military Grids 4-10

Page
4-4. United States Army Military Grid Reference System 4-12
4-5. Locate a Point Using Grid Coordinates 4-17
4-6. Locate a Point Using the US Army Military Grid Reference System..4-21
4-7. Grid Reference Box...4-24
4-8. Other Grid Systems 4-25
4-9. Protection of Map Coordinates and Locations........................4-27

CHAPTER 5. SCALE AND DISTANCE
5-1. Representative Fraction...5-1
5-2. Graphic (Bar) Scales 5-3
5-3. Other Methods..5-11

CHAPTER 6. DIRECTION
6-1. Methods of Expressing Direction 6-1
6-2. Base Lines 6-1
6-3. Azimuths 6-2
6-4. Grid Azimuths 6-4
6-5. Protractor..6-5
6-6. Declination Diagram 6-8
6-7. Intersection...6-14
6-8. Resection 6-16
6-9. Modified Resection 6-19
6-10. Polar Coordinates 6-20

CHAPTER 7. OVERLAYS
7-1. Purpose...7-1
7-2. Map Overlay 7-1
7-3. Aerial Photograph Overlay 7-3

CHAPTER 8. AERIAL PHOTOGRAPHS
8-1. Comparison With Maps 8-1
8-2. Types..8-1
8-3. Types of Film 8-7
8-4. Numbering and Titling Information...8-7
8-5. Scale Determination 8-8
8-6. Indexing 8-10
8-7. Orienting of Photograph...8-13
8-8. Point Designation Grid...8-14
8-9. Identification of Photograph Features......................................8-17
8-10. Stereovision..8-18

Page

Part Two
LAND NAVIGATION

CHAPTER 9. NAVIGATION EQUIPMENT AND METHODS
9-1. Types of Compasses....9-1
9-2. Lensatic Compass....9-1
9-3. Compass Handling....9-2
9-4. Using a Compass....9-3
9-5. Field-Expedient Methods....9-7
9-6. Global Positioning System....9-12

CHAPTER 10. ELEVATION AND RELIEF
10-1. Definitions....10-1
10-2. Methods of Depicting Relief....10-1
10-3. Contour Intervals....10-2
10-4. Types of Slopes....10-5
10-5. Percentage of Slope....10-8
10-6. Terrain Features....10-11
10-7. Interpretation of Terrain Features....10-17
10-8. Profiles....10-20

CHAPTER 11. TERRAIN ASSOCIATION
11-1. Orienting the Map....11-1
11-2. Locations....11-6
11-3. Terrain Association Usage....11-7
11-4. Tactical Considerations....11-9
11-5. Movement and Route Selection....11-12
11-6. Navigation Methods....11-14
11-7. Night Navigation....11-18

CHAPTER 12. MOUNTED LAND NAVIGATION
12-1. Principles....12-1
12-2. Navigator's Duties....12-1
12-3. Movement....12-1
12-4. Terrain Association Navigation....12-3
12-5. Dead Reckoning Navigation....12-6
12-6. Stabilized Turret Alignment Navigation....12-7
12-7. Combination Navigation....12-8

CHAPTER 13. NAVIGATION IN DIFFERENT TYPES OF TERRAIN
13-1. Desert Terrain....13-1
13-2. Mountain Terrain....13-4
13-3. Jungle Terrain....13-6
13-4. Arctic Terrain....13-9

Page
13-5. Urban Areas 13-10

CHAPTER 14. UNIT SUSTAINMENT

14-1. Set Up a Sustainment Program 14-1
14-2. Set Up a Train-the-Trainer Program 14-2
14-3. Set Up a Land Navigation Course...14-2

APPENDIX A. FIELD SKETCHING..A-1
APPENDIX B. MAP FOLDING TECHNIQUES B-1
APPENDIX C. UNITS OF MEASURE AND CONVERSION FACTORS C-1
APPENDIX D. JOINT OPERATIONS GRAPHICS..D-1
APPENDIX E. EXPORTABLE TRAINING MATERIAL..E-1
APPENDIX F.ORIENTEERING..F-1
APPENDIX G. M2 COMPASS..G-1
APPENDIX H. ADDITIONAL AIDS..H-1
APPENDIX I. FOREIGN MAPS...I-1
APPENDIX J. GLOBAL POSITIONING SYSTEM J-1
APPENDIX K. PRECISION LIGHTWEIGHT GLOBAL POSITIONING SYSTEM RECEIVER K-1
GLOSSARY...Glossary-1
REFERENCES..References-1
INDEX Index-1

PREFACE

The purpose of this field manual is to provide a standardized source document for Armywide reference on *map reading* and *land navigation*. This manual applies to every soldier in the Army regardless of service branch, MOS, or rank. This manual also contains both doctrine and training guidance on these subjects. Part One addresses map reading and Part Two, land navigation. The appendixes include a list of exportable training materials, a matrix of land navigation tasks, an introduction to orienteering, and a discussion of several devices that can assist the soldier in land navigation.

Unless this publication states otherwise, masculine nouns and pronouns do not refer exclusively to men.

PART ONE
MAP READING

CHAPTER 1
TRAINING STRATEGY

This manual is in response to an Armywide need for a new map reading and land navigation training strategy based on updated doctrine. This chapter describes and illustrates this approach to teaching these skills.

1-1. BUILDING-BLOCK APPROACH

Institution courses are designed to prepare the soldier for a more advanced duty position in his unit. The critical soldiering skills of move, shoot, and communicate must be trained, practiced, and sustained at every level in the schools as well as in the unit. The map reading and land navigation skills taught at each level are critical to the soldiering skills of the duty position for which he is being school-trained. Therefore, they are also a prerequisite for a critical skill at a more advanced level.

a. A soldier completing initial-entry training must be prepared to become a team member. He must be proficient in the basic map reading and dead reckoning skills.

b. After completing the Primary Leadership Development Course (PLDC), a soldier should be ready to be a team leader. This duty position requires expertise in the skills of map reading, dead reckoning, and terrain association.

c. A soldier completing the Basic NCO Course (BNCOC) has been trained for the squad leader position. Map reading and land navigation at skill level 3 requires development of problem-solving skills; for example, route selection and squad tactical movement.

d. At skill level 4, the soldier completing the Advanced NCO Course (ANCOC) is prepared to assume the duty position of platoon sergeant or operations NCO. Planning tactical movements, developing unit sustainment, and making decisions are the important land navigation skills at this level.

e. Officers follow similar progression. A new second lieutenant must have mastered map reading and land navigation skills, and have an aptitude for dead reckoning and terrain association.

(1) After completing the Officer Basic Course, the officer must be prepared to assume the duties and responsibilities of a platoon leader. He is required to execute the orders and operations of his commander. Map reading and land navigation at this level require development of the problem-solving skills of route selection and tactical movement.

(2) After completing the Officer Advanced Course, the officer is prepared to assume the duties and responsibilities of a company commander or primary staff officer. The commander must plan and execute operations with full consideration to all aspects of navigation. The staff officer must recommend battlefield placement of all administrative, logistical, and personnel resources. These recommendations cannot be tactically sound unless the estimate process includes a detailed analysis of the area of operations. This ability requires expertise in all map reading and navigation skills to include the use of nonmilitary maps, aerial photographs, and terrain analysis with respect to both friendly and enemy

forces. The commander/staff officer must plan and execute a program to develop the unit's train-the-trainer program for land navigation.

f. A program of demonstrated proficiency of all the preceding skill levels to the specified conditions and standards is a prerequisite to the successful implementation of a building-block training approach. This approach reflects duty position responsibilities in map reading and land navigation. An understanding of the fundamental techniques of dead reckoning or field-expedient methods is a basic survival skill that each soldier must develop at the initial-entry level. This skill provides a support foundation for more interpretive analysis at intermediate skill levels 2 and 3, with final progression to level 4. Mastery of all map reading and land navigation tasks required in previous duty positions is essential for the sequential development of increasingly difficult abilities. This building-block approach is supported by scope statements. It is part of the training doctrine at each level in the institutional training environment of each course.

g. Exportable training and instructor support/certification packages are being developed based upon the updated map reading and land navigation field manual. Innovative training devices and materials are being developed for use in the institution, ROTC regions, and the field. (See Appendixes E and H.)

1-2. ARMYWIDE IMPLEMENTATION

A mandatory core of critical map reading and land navigation tasks and a list of electives will be provided to each TRADOC service school and FORSCOM professional development school. Standardization is achieved through the mandatory core. Exportable training material is made available to support Armywide implementation.

1-3. SAFETY

Unit leaders plan to brief and enforce all safety regulations established by local range control. They coordinate the mode of evacuation of casualties through the appropriate channels. They review all installation safety regulations. Unit leaders must complete a thorough terrain reconnaissance before using an area for land navigation training. They should look for dangerous terrain, heavy trafficked roads, water obstacles, wildlife, and training debris.

CHAPTER 2

MAPS

Cartography is the art and science of expressing the known physical features of the earth graphically by maps and charts. No one knows who drew, molded, laced together, or scratched out in the dirt the first map. But a study of history reveals that the most pressing demands for accuracy and detail in mapping have come as the result of military needs. Today, the complexities of tactical operations and deployment of troops are such that it is essential for all soldiers to be able to read and interpret their maps in order to move quickly and effectively on the battlefield. This chapter includes the definition and purpose of a map and describes map security, types, categories, and scales.

2-1. DEFINITION

A map is a graphic representation of a portion of the earth's surface drawn to scale, as seen from above. It uses colors, symbols, and labels to represent features found on the ground. The ideal representation would be realized if every feature of the area being mapped could be shown in true shape. Obviously this is impossible, and an attempt to plot each feature true to scale would result in a product impossible to read even with the aid of a magnifying glass.

a. Therefore, to be understandable, features must be represented by conventional signs and symbols. To be legible, many of these must be exaggerated in size, often far beyond the actual ground limits of the feature represented. On a 1:250,000 scale map, the prescribed symbol for a building covers an area about 500 feet square on the ground; a road symbol is equivalent to a road about 520 feet wide on the ground; the symbol for a single-track railroad (the length of a cross-tie) is equivalent to a railroad cross-tie about 1,000 feet on the ground.

b. The portrayal of many features requires similar exaggeration. Therefore, the selection of features to be shown, as well as their portrayal, is in accord with the guidance established by the Defense Mapping Agency.

2-2. PURPOSE

A map provides information on the existence, the location of, and the distance between ground features, such as populated places and routes of travel and communication. It also indicates variations in terrain, heights of natural features, and the extent of vegetation cover. With our military forces dispersed throughout the world, it is necessary to rely on maps to provide information to our combat elements and to resolve logistical operations far from our shores. Soldiers and materials must be transported, stored, and placed into operation at the proper time and place. Much of this planning must be done by using maps. Therefore, any operation requires a supply of maps; however, the finest maps available are worthless unless the map user knows how to read them.

2-3. PROCUREMENT

Most military units are authorized a basic load of maps. Local command supplements to AR 115-11 provide tables of initial allowances for maps. Map requisitions and distributions are accomplished through the Defense Mapping Agency Hydrographic and Topographic

Center's Office of Distribution and Services. In the division, however, maps are a responsibility of the G2 section.

a. To order a map, refer to the DMA catalog located at your S2/G2 shop. Part 3 of this catalog, Topographic Maps, has five volumes. Using the delineated map index, find the map or maps you want based upon the location of the nearest city. With this information, order maps using the following forms:

(1) *Standard Form 344*. It can be typed or handwritten; it is used for mailing or over-the-counter service.

(2) *Department of Defense Form 1348*. Same as SF 344. You can order copies of only one map sheet on each form.

(3) *Department of Defense Form 1348M*. This is a punch card form for AUDODIN ordering.

(4) *Department of Defense Form 173*. This is a message form to be used for urgent ordering.

With the exception of the message form (DD 173), the numbered sections of all forms are the same. For example: In block 1, if you are in CONUS, enter "AOD," if you are overseas, enter "AO4." In block 2, use one of the following codes for your location.

LOCATION	CODE
Europe	CS7
Hawaii	HM9
Korea	WM4
Alaska	WC1
Panama	HMJ
CONUS	HM8

Your supply section will help you complete the rest of the form.

b. Stock numbers are also listed in map catalogs, which are available at division and higher levels and occasionally in smaller units. A map catalog consists of small-scale maps upon which the outlines of the individual map sheets of a series have been delineated. Another document that is an aid to the map user is the gazetteer. A gazetteer lists all the names appearing on a map series of a geographical area, a designation that identifies what is located at that place name, a grid reference, a sheet number of the map upon which the name appeared, and the latitude and longitude of the named features. Gazetteers are prepared for maps of foreign areas only.

2-4. SECURITY

All maps should be considered as documents that require special handling. If a map falls into unauthorized hands, it could easily endanger military operations by providing information of friendly plans or areas of interest to the enemy. Even more important would be a map on which the movements or positions of friendly soldiers were marked. It is possible, even though the markings on a map have been erased, to determine some of the erased information. **Maps are documents that must not fall into unauthorized hands.**

a. If a map is no longer needed, it must be turned in to the proper authority. If a map is in danger of being captured, it must be destroyed. The best method of destruction is by burning it and scattering the ashes. If burning is not possible, the map can be torn into small pieces and scattered over a wide area.

b. Maps of some areas of the world are subject to third party limitations. These are agreements that permit the United States to make and use maps of another country provided these maps are not released to any third party without permission of the country concerned. Such maps require special handling.

c. Some maps may be classified and must be handled and cared for in accordance with AR 380-5 and, if applicable, other local security directives.

2-5. CARE

Maps are documents printed on paper and require protection from water, mud, and tearing. Whenever possible, a map should be carried in a waterproof case, in a pocket, or in some other place where it is handy for use but still protected.

a. Care must also be taken when using a map since it may have to last a long time. If it becomes necessary to mark a map, the use of a pencil is recommended. Use light lines so they may be erased easily without smearing and smudging, or leaving marks that may cause confusion later. If the map margins must be trimmed for any reason, it is essential to note any marginal information that may be needed later, such as grid data and magnetic declination.

b. Special care should be taken of a map that is being used in a tactical mission, especially in small units; the mission may depend on that map. All members of such units should be familiar with the map's location at all times.

c. Appendix B shows two ways of folding a map.

2-6. CATEGORIES

The DMA's mission is to provide mapping, charting, and all geodesy support to the armed forces and all other national security operations. DMA produces four categories of products and services: hydrographic, topographic, aeronautical, and missile and targeting. Military maps are categorized by scale and type.

a. **Scale.** Because a map is a graphic representation of a portion of the earth's surface drawn to scale as seen from above, it is important to know what mathematical scale has been used. You must know this to determine ground distances between objects or locations on the map, the size of the area covered, and how the scale may affect the amount of detail being shown. The mathematical scale of a map is the ratio or fraction between the distance on a map and the corresponding distance on the surface of the earth. Scale is reported as a representative fraction with the map distance as the numerator and the ground distance as the denominator.

$$\textit{Representative fraction (scale)} = \frac{\textit{map distance}}{\textit{ground distance}}$$

As the denominator of the representative fraction gets larger and the ratio gets smaller, the scale of the map decreases. Defense Mapping Agency maps are classified by scale into three categories. They are small-, medium-, and large-scale maps (Figure 2-1). The terms **"small scale," "medium scale,"** and **"large scale"** may be confusing when read in conjunction with the number. However, if the number is viewed as a fraction, it quickly becomes apparent that 1:600,000 of something is smaller than 1:75,000 of the same thing. Therefore, the larger the number after 1:, the smaller the scale of the map.

(1) ***Small***. Those maps with scales of 1:1,000,000 and smaller are used for general planning and for strategic studies (bottom map in Figure 2-1). The standard small-scale map is 1:1,000,000. This map covers a very large land area at the expense of detail.

(2) ***Medium***. Those maps with scales larger than 1:1,000,000 but smaller than 1:75,000 are used for operational planning (center map in Figure 2-1). They contain a moderate amount of detail, but terrain analysis is best done with the large-scale maps described below. The standard medium-scale map is 1:250,000. Medium scale maps of 1:100,000 are also frequently encountered.

(3) ***Large***. Those maps with scales of 1:75,000 and larger are used for tactical, administrative, and logistical planning (top map in Figure 2-1). These are the maps that you as a soldier or junior leader are most likely to encounter. The standard large-scale map is 1:50,000; however, many areas have been mapped at a scale of 1:25,000.



Figure 2-1. Scale classifications.

b. **Types**. The map of choice for land navigators is the 1:50,000-scale military topographic map. It is important, however, that you know how to use the many other products available from the DMA as well. When operating in foreign places, you may discover that DMA map products have not yet been produced to cover your particular area of operations, or they may not be available to your unit when you require them. Therefore, you must be prepared to use maps produced by foreign governments that may or may not meet the standards for accuracy set by DMA. These maps often use symbols that resemble those found on DMA maps but which have completely different meanings. There may be other times when you must operate with the only map you can obtain. This might be a commercially produced map run off on a copy machine at higher headquarters. In Grenada, many of our troops used a British tourist map.

(1) ***Planimetric Map***. This is a map that presents only the horizontal positions for the features represented. It is distinguished from a topographic map by the omission of relief, normally represented by contour lines. Sometimes, it is called a line map.

(2) ***Topographic Map***. This is a map that portrays terrain features in a measurable way (usually through use of contour lines), as well as the horizontal positions of the features represented. The vertical positions, or relief, are normally represented by contour lines on military topographic maps. On maps showing relief, the elevations and contours are measured from a specific vertical datum plane, usually mean sea level. Figure 3-1 shows a typical topographic map.

(3) ***Photomap***. This is a reproduction of an aerial photograph upon which grid lines, marginal data, place names, route numbers, important elevations, boundaries, and approximate scale and direction have been added. (See Chapter 8.)

(4) ***Joint Operations Graphics***. These maps are based on the format of standard 1:250,000 medium-scale military topographic maps, but they contain additional information needed in joint air-ground operations (Figure 2-2). Along the north and east edges of the graphic, detail is extended beyond the standard map sheet to provide overlap with adjacent sheets. These maps are produced both in ground and air formats. Each version is identified in the lower margin as either Joint Operations Graphic (Air) or Joint Operations Graphic (Ground). The topographic information is identical on both, but the ground version shows elevations and contour in meters and the air version shows them in feet. Layer (elevation) tinting and relief shading are added as an aid to interpolating relief. Both versions emphasize airlanding facilities (shown in purple), but the air version has additional symbols to identify aids and obstructions to air navigation. (See Appendix D for additional information.)



Figure 2-2. Joint operations graphic (air).

(5) ***Photomosaic***. This is an assembly of aerial photographs that is commonly called a mosaic in topographic usage. Mosaics are useful when time does not permit the compilation of a more accurate map. The accuracy of a mosaic depends on the method employed in its preparation and may vary from simply a good pictorial effect of the ground to that of a planimetric map.

(6) ***Terrain Model***. This is a scale model of the terrain showing features, and in large-scale models showing industrial and cultural shapes. It provides a means for visualizing the terrain for planning or indoctrination purposes and for briefing on assault landings.

(7) ***Military City Map***. This is a topographic map (usually at 1:12,550 scale, sometimes up to 1:5,000), showing the details of a city. It delineates streets and shows street names, important buildings, and other elements of the urban landscape important to navigation and military operations in urban terrain. The scale of a military city map depends on the importance and size of the city, density of detail, and available intelligence information.

(8) ***Special Maps***. These are maps for special purposes, such as trafficability, communications, and assault maps. They are usually in the form of an overprint in the scales smaller than 1:100,000 but larger than 1:1,000,000. A special purpose map is one that has been designed or modified to give information not covered on a standard map. The wide range of subjects that could be covered under the heading of special purpose maps prohibits,

within the scope of this manual, more than a brief mention of a few important ones. Some of the subjects covered are:

- Terrain features.
- Drainage characteristics.
- Vegetation.
- Climate.
- Coasts and landing beaches.
- Roads and bridges.
- Railroads.
- Airfields.
- Urban areas.
- Electric power.
- Fuels.
- Surface water resources.
- Ground water resources.
- Natural construction materials.
- Cross-country movements.
- Suitability for airfield construction.
- Airborne operations.

2-7. MILITARY MAP SUBSTITUTES

If military maps are not available, use substitute maps. The substitute maps can range from foreign military or commercial maps to field sketches. The DMA can provide black and white reproductions of many foreign maps and can produce its own maps based upon intelligence.

a. **Foreign Maps**. These are maps that have been compiled by nations other than our own. When these must be used, the marginal information and grids are changed to conform to our standards if time permits. The scales may differ from our maps, but they do express the ratio of map distance to ground distance and can be used in the same way. The legend must be used since the map symbols almost always differ from ours. Because the accuracy of foreign maps varies considerably, they are usually evaluated in regard to established accuracy standards before they are issued to our troops. (See Appendix I for additional information.)

b. **Atlases**. These are collections of maps of regions, countries, continents, or the world. Such maps are accurate only to a degree and can be used for general information only.

c. **Geographic Maps**. These maps give an overall idea of the mapped area in relation to climate, population, relief, vegetation, and hydrography. They also show general location of major urban areas.

d. **Tourist Road Maps**. These are maps of a region in which the main means of transportation and areas of interest are shown. Some of these maps show secondary networks of roads, historic sites, museums, and beaches in detail. They may contain road and time distance between points. Careful consideration should be exercised about the scale when using these maps.

e. **City/Utility Maps**. These are maps of urban areas showing streets, water ducts, electricity and telephone lines, and sewers.

f. **Field Sketches**. These are preliminary drawings of an area or piece of terrain. (See Appendix A.)

g. **Aerial Photographs**. These can be used as map supplements or substitutes to help you analyze the terrain, plan your route, or guide your movement. (See Chapter 8 for additional information).

2-8. STANDARDS OF ACCURACY

Accuracy is the degree of conformity with which horizontal positions and vertical values are represented on a map in relation to an established standard. This standard is determined by the DMA based on user requirements. A map can be considered to meet accuracy requirement standards unless otherwise specified in the marginal information.

CHAPTER 3

MARGINAL INFORMATION AND SYMBOLS

A map could be compared to any piece of equipment, in that before it is placed into operation the user must read the instructions. It is important that you, as a soldier, know how to read these instructions. The most logical place to begin is the marginal information and symbols, where useful information telling about the map is located and explained. All maps are not the same, so it becomes necessary every time a different map is used to examine the marginal information carefully.

3-1. MARGINAL INFORMATION ON A MILITARY MAP

Figure 3-1 (page 3-4) shows a reduced version of a large-scale topographic map. The circled numbers indicate the items of marginal information that the map user needs to know. These circled numbers correspond to the following listed items.

a. **Sheet Name (1)**. The sheet name is found in bold print at the center of the top and in the lower left area of the map margin. A map is generally named for the settlement contained within the area covered by the sheet, or for the largest natural feature located within the area at the time the map was drawn.

b. **Sheet Number (2).** The sheet number is found in bold print in both the upper right and lower left areas of the margin, and in the center box of the adjoining sheets diagram, which is found in the lower right margin. It is used as a reference number to link specific maps to overlays, operations orders, and plans. For maps at 1:100,000 scale and larger, sheet numbers are based on an arbitrary system that makes possible the ready orientation of maps at scales of 1:100,000, 1:50,000, and 1:25,000.

c. **Series Name (3)**. The map series name is found in the same bold print as the sheet number in the upper left corner of the margin. The name given to the series is generally that of a major political subdivision, such as a state within the United States or a European nation. A map series usually includes a group of similar maps at the same scale and on the same sheet lines or format designed to cover a particular geographic area. It may also be a group of maps that serve a common purpose, such as the military city maps.

d. **Scale (4).** The scale is found both in the upper left margin after the series name, and in the center of the lower margin. The scale note is a representative fraction that gives the ratio of a map distance to the corresponding distance on the earth's surface. For example, the scale note 1:50,000 indicates that one unit of measure on the map equals 50,000 units of the same measure on the ground.

e. **Series Number (5).** The series number is found in both the upper right margin and the lower left margin. It is a sequence reference expressed either as a four-digit numeral (1125) or as a letter, followed by a three- or four-digit numeral (M661; T7110).

f. **Edition Number (6)**. The edition number is found in bold print in the upper right area of the top margin and the lower left area of the bottom margin. Editions are numbered consecutively; therefore, if you have more than one edition, the highest numbered sheet is the most recent. Most military maps are now published by the DMA, but older editions of maps may have been produced by the US Army Map Service. Still others may have been drawn, at least in part, by the US Army Corps of Engineers, the US Geological Survey, or other agencies affiliated or not with the United States or allied governments. The credit line, telling who produced the map, is just above the legend. The map information date is found immediately below the word "LEGEND" in the lower left margin of the map. This date is important when determining how accurately the map data might be expected to match what you will encounter on the ground.

g. **Index to Boundaries (7).** The index to boundaries diagram appears in the lower or right margin of all sheets. This diagram, which is a miniature of the map, shows the boundaries that occur within the map area, such as county lines and state boundaries.

h. **Adjoining Sheets Diagram (8).** Maps at all standard scales contain a diagram that illustrates the adjoining sheets. On maps at 1:100,000 and larger scales and at 1:1,000,000 scale, the diagram is called the index to adjoining sheets. It consists of as many rectangles representing adjoining sheets as are necessary to surround the rectangle that represents the sheet under consideration. The diagram usually contains nine rectangles, but the number may vary depending on the locations of the adjoining sheets. All represented sheets are identified by their sheet numbers. Sheets of an adjoining series, whether published or planned, that are at the same scale are represented by dashed lines. The series number of the adjoining series is indicated along the appropriate side of the division line between the series.

i. **Elevation Guide (9).** This is normally found in the lower right margin. It is a miniature characterization of the terrain shown. The terrain is represented by bands of elevation, spot elevations, and major drainage features. The elevation guide provides the map reader with a means of rapid recognition of major landforms.

j. **Declination Diagram (10).** This is located in the lower margin of large-scale maps and indicates the angular relationships of true north, grid north, and magnetic north. On maps at 1:250,000 scale, this information is expressed as a note in the lower margin. In recent edition maps, there is a note indicating the conversion of azimuths from grid to magnetic and from magnetic to grid next to the declination diagram.

k. **Bar Scales (11).** These are located in the center of the lower margin. They are rulers used to convert map distance to ground distance. Maps have three or more bar scales, each in a different unit of measure. Care should be exercised when using the scales, especially in the selection of the unit of measure that is needed.

l. **Contour Interval Note (12)**. This note is found in the center of the lower margin normally below the bar scales. It states the vertical distance between adjacent contour lines of the map. When supplementary contours are used, the interval is indicated. In recent edition maps, the contour interval is given in meters instead of feet.

m. **Spheroid Note (13).** This note is located in the center of the lower margin. Spheriods (ellipsoids) have specific parameters that define the X Y Z axis of the earth. The spheriod is an integral part of the datum.

n. **Grid Note (14).** This note is located in the center of the lower margin. It gives information pertaining to the grid system used and the interval between grid lines, and it identifies the UTM grid zone number.

o. **Projection Note (15).** The projection system is the framework of the map. For military maps, this framework is of the conformal type; that is, small areas of the surface of the earth retain their true shapes on the projection; measured angles closely approximate true values; and the scale factor is the same in all directions from a point. The projection note is located in the center of the lower margin. Refer to DMA for the development characteristics of the conformal-type projection systems.

(1) Between 80° south and 84° north, maps at scales larger than 1:500,000 are based on the transverse Mercator projection. The note reads TRANSVERSE MERCATOR PROJECTION.

(2) Between 80° south and 84° north, maps at 1:1,000,000 scale and smaller are based on standard parallels of the lambert conformal conic projection. The note reads, for example, LAMBERT CONFORMAL CONIC PROJECTIONS 36° 40' N AND 39° 20' N.

(3) Maps of the polar regions (south of 80° south and north of 84° north) at 1:1,000,000 and larger scales are based on the polar stereographic projection. The note reads POLAR STEREOGRAPHIC PROJECTION.

p. **Vertical Datum Note (16).** This note is located in the center of the lower margin. The vertical datum or vertical-control datum is defined as any level surface (for example, mean sea level) taken as a surface of reference from which to determine elevations. In the United States, Canada, and Europe, the vertical datum refers to the mean sea level surface. However, in parts of Asia and Africa, the vertical-control datum may vary locally and is based on an assumed elevation that has no connection to any sea level surface. Map readers should habitually check the vertical datum note on maps, particularly if the map is used for low-level aircraft navigation, naval gunfire support, or missile target acquisition.

q. **Horizontal Datum Note (17).** This note is located in the center of the lower margin. The horizontal datum or horizontal-control datum is defined as a geodetic reference point (of which five quantities are known: latitude, longitude, azimuth of a line from this point, and two constants, which are the parameters of reference ellipsoid). These are the basis for horizontal-control surveys. The horizontal-control datum may extend over a continent or be limited to a small local area. Maps and charts produced by DMA are produced on 32 different horizontal-control data. Map readers should habitually check the horizontal datum note on every map or chart, especially adjacent map sheets. This is to ensure the products are based on the same horizontal datum. If products are based on different horizontal-control data, coordinate transformations to a common datum must be performed. UTM coordinates from the same point computed on different data may differ as much as 900 meters.

r. **Control Note (18).** This note is located in the center of the lower margin. It indicates the special agencies involved in the control of the technical aspects of all the information that is disseminated on the map.

s. **Preparation Note (19).** This note is located in the center of the lower margin. It indicates the agency responsible for preparing the map.

t. **Printing Note (20).** This note is also located in the center of the lower margin. It indicates the agency responsible for printing the map and the date the map was printed. The printing data should not be used to determine when the map information was obtained.

u. **Grid Reference Box (21).** This box is normally located in the center of the lower margin. It contains instructions for composing a grid reference.

v. **Unit imprint and Symbol (22).** The unit imprint and symbol is on the left side of the lower margin. It identifies the agency that prepared and printed the map with its respective symbol. This information is important to the map user in evaluating the reliability of the map.

w. **Legend (23).** The legend is located in the lower left margin. It illustrates and identifies the topographic symbols used to depict some of the more prominent features on the map. The symbols are not always the same on every map. Always refer to the legend to avoid errors when reading a map.


3
GEORGIA 1:50,000
4
COLUMBUS
1
6
5
2
6-DMATC
V745
4048 IV
27
7
22
4
11
12
13
14
15
16
17
18
19
20
21
23
9
8
10
24
25
26
4048 IV
V745
6-DMATC
COLUMBUS
2
5
6
1

Figure 3-1. Topographical map.

3-2. ADDITIONAL NOTES

Not all maps contain the same items of marginal information. Under certain conditions, special notes and scales may be added to aid the map user. The following are examples:

a. **Glossary**. This is an explanation of technical terms or a translation of terms on maps of foreign areas where the native language is other than English.

b. **Classification**. Certain maps require a note indicating the security classification. This is shown in the upper and lower margins.

c. **Protractor Scale**. This scale may appear in the upper margin on some maps. It is used to lay out the magnetic-grid declination for the map, which, in turn, is used to orient the map sheet with the aid of the lensatic compass.

d. **Coverage Diagram**. On maps at scales of 1:100,000 and larger, a coverage diagram may be used. It is normally in the lower or right margin and indicates the methods by which the map was made, dates of photography, and reliability of the sources. On maps at 1:250,000 scale, the coverage diagram is replaced by a reliability diagram.

e. **Special Notes (24).** A special note is any statement of general information that relates to the mapped area. It is normally found in the lower right margin. For example: This map is red-light readable.

f. **User's Note (25).** This note is normally located in the lower right-hand margin. It requests cooperation in correcting errors or omissions on the map. Errors should be marked and the map forwarded to the agency identified in the note.

g. **Stock Number Identification (26).** All maps published by the DMA that are in the Department of the Army map supply system contain stock number identifications that are used in requisitioning map supplies. The identification consists of the words "STOCK NO" followed by a unique designation that is composed of the series number, the sheet number of the individual map and, on recently printed sheets, the edition number. The designation is limited to 15 units (letters and numbers). The first 5 units are allotted to the series number; when the series number is less than 5 units, the letter "X" is substituted as the fifth unit. The sheet number is the next component; however, Roman numerals, which are part of the sheet number, are converted to Arabic numerals in the stock number. The last 2 units are the edition number; the first digit of the edition number is a zero if the number is less than 10. If the current edition number is unknown, the number 01 is used. The latest available edition will be furnished. Asterisks are placed between the sheet number and the edition number when necessary to ensure there are at least 11 units in the stock number.

h. **Conversion Graph (27).** Normally found in the right margin, this graph indicates the conversion of different units of measure used on the map.

3-3. TOPOGRAPHIC MAP SYMBOLS

The purpose of a map is to permit one to visualize an area of the earth's surface with pertinent features properly positioned. The map's legend contains the symbols most commonly used in a particular series or on that specific topographic map sheet. Therefore, the legend should be referred to each time a new map is used. Every effort is made to design standard symbols that resemble the features they represent. If this is not possible, symbols are selected that logically imply the features they portray. For example, an open-pit mining operation is represented by a small black drawing of a crossed hammer and pickax.

a. Ideally, all the features within an area would appear on a map in their true proportion, position, and shape. This, however, is not practical because many of the features would be unimportant and others would be unrecognizable because of their reduction in size.

b. The mapmaker has been forced to use symbols to represent the natural and man-made features of the earth's surface. These symbols resemble, as closely as possible, the actual features themselves as viewed from above. They are positioned in such a manner that the center of the symbol remains in its true location. An exception to this would be the position of a feature adjacent to a major road. If the width of the road has been exaggerated, then the feature is moved from its true position to preserve its relation to the road. Field Manual 21-31 gives a description of topographic features and abbreviations authorized for use on our military maps.

3-4. MILITARY SYMBOLS

In addition to the topographic symbols used to represent the natural and man-made features of the earth, military personnel require some method for showing identity, size, location, or movement of soldiers; and military activities and installations. The symbols used to represent these military features are known as military symbols. These symbols are not normally printed on maps because the features and units that they represent are constantly moving or changing; military security is also a consideration. They do appear in special maps and overlays (Chapter 7). The map user draws them in, in accordance with proper security precautions. Refer to FM 101-5-1 for complete information on military symbols.

3-5. COLORS USED ON A MILITARY MAP

By the fifteenth century, most European maps were carefully colored. Profile drawings of mountains and hills were shown in brown, rivers and lakes in blue, vegetation in green, roads in yellow, and special information in red. A look at the legend of a modern map confirms that the use of colors has not changed much over the past several hundred years. To facilitate the identification of features on a map, the topographical and cultural information is usually printed in different colors. These colors may vary from map to map. On a standard large-scale topographic map, the colors used and the features each represent are:

a**. Black.** Indicates cultural (man-made) features such as buildings and roads, surveyed spot elevations, and all labels.

b. **Red-Brown**. The colors red and brown are combined to identify cultural features, all relief features, non-surveyed spot elevations, and elevation, such as contour lines on red-light readable maps.

c. **Blue**. Identifies hydrography or water features such as lakes, swamps, rivers, and drainage.

d. **Green.** Identifies vegetation with military significance, such as woods, orchards, and vineyards.

e. **Brown.** Identifies all relief features and elevation, such as contours on older edition maps, and cultivated land on red-light readable maps.

f. **Red.** Classifies cultural features, such as populated areas, main roads, and boundaries, on older maps.

g. **Other**. Occasionally other colors may be used to show special information. These are indicated in the marginal information as a rule.

CHAPTER 4
GRIDS

This chapter covers how to determine and report positions on the ground in terms of their locations on a map. Knowing where you are (position fixing) and being able to communicate that knowledge is crucial to successful land navigation as well as to the effective employment of direct and indirect fire, tactical air support, and medical evacuation. It is essential for valid target acquisition; accurate reporting of NBC contamination and various danger areas; and obtaining emergency resupply. Few factors contribute as much to the survivability of troops and equipment and to the successful accomplishment of a mission as always knowing where you are. The chapter includes explanations of geographical coordinates, Universal Transverse Mercator grids, the military grid reference system, and the use of grid coordinates.

4-1. REFERENCE SYSTEM

In a city, it is quite simple to find a location; the streets are named and the buildings have numbers. The only thing needed is the address. However, finding locations in undeveloped areas or in unfamiliar parts of the world can be a problem. To cope with this problem, a uniform and precise system of referencing has been developed.

4-2. GEOGRAPHIC COORDINATES

One of the oldest systematic methods of location is based upon the geographic coordinate system. By drawing a set of east-west rings around the globe (parallel to the equator), and a set of north-south rings crossing the equator at right angles and converging at the poles, a network of reference lines is formed from which any point on the earth's surface can be located.

a. The distance of a point north or south of the equator is known as its latitude. The rings around the earth parallel to the equator are called parallels of latitude or simply parallels. Lines of latitude run east-west but north-south distances are measured between them.

b. A second set of rings around the globe at right angles to lines of latitude and passing through the poles is known as meridians of longitude or simply meridians. One meridian is designated as the prime meridian. The prime meridian of the system we use runs through Greenwich, England and is known as the Greenwich meridian. The distance east or west of a prime meridian to a point is known as its longitude. Lines of longitude (meridians) run north-south but east-west distances are measured between them (Figures 4-1 and 4-2, page 4-2).


N
GREENWICH MERIDIAN
PRIME MERIDIAN
NORTH LATITUDE
WEST LONGITUDE
EAST LONGITUDE
W
E
SOUTH LATITUDE
EQUATOR
S

Figure 4-1. Prime meridian and equator.


N
PARALLELS
GREENWICH MERIDIAN
MERIDIANS
W
E
PRIME MERIDIAN
EQUATOR
S

Figure 4-2. Reference lines.

c. Geographic coordinates are expressed in angular measurement. Each circle is divided into 360 degrees, each degree into 60 minutes, and each minute into 60 seconds. The degree is symbolized by °, the minute by ′, and the second by ″. Starting with 0° at the equator, the parallels of latitude are numbered to 90° both north and south. The extremities are the north pole at 90° north latitude and the south pole at 90° south latitude. Latitude can have the same numerical value north or south of the equator, so the direction N or S must always be given. Starting with 0°at the prime meridian, longitude is measured both east and west around the world. Lines east of the prime meridian are numbered to 180° and identified as east longitude; lines west of the prime meridian are numbered to 180° and identified as west longitude. The direction E or W must always be given. The line directly opposite the prime meridian, 180°, may be referred to as either east or west longitude. The values of geographic coordinates, being in units of angular measure, will mean more if they are compared with units of measure with which we are more familiar. At any point on the earth, the ground distance covered by one degree of latitude is about 111 kilometers (69 miles); one second is equal to about 30 meters (100 feet). The ground distance covered by one degree of longitude at the equator is also about 111 kilometers, but decreases as one moves north or south, until it becomes zero at the poles. For example, one second of longitude represents about 30 meters (100 feet) at the equator; but at the latitude of Washington, DC, one second of longitude is about 24 meters (78 feet). Latitude and longitude are illustrated in Figure 4-3.



Figure 4-3. Latitude and longitude.

d. Geographic coordinates appear on all standard military maps; on some they may be the only method of locating and referencing a specific point. The four lines that enclose the body of the map (neatlines) are latitude and longitude lines. Their values are given in degrees and minutes at each of the four corners. On a portion of the Columbus map (Figure 4-4), the figures 32°15' and 84°45' appear at the lower right corner. The bottom line of this map is latitude 32°15'00″N, and the line running up the right side is longitude 84°45'00"W. In addition to the latitude and longitude given for the four corners, there are, at regularly spaced intervals along the sides of the map, small tick marks extending into the body of the map. Each of these tick marks is identified by its latitude or longitude value. Near the top of the right side of the map is a tick mark and the number 20'. The full value for this tick marks is 32°20'00" of latitude. At one-third and two-thirds of the distance across the map from the 20' tick mark will be found a cross tick mark (grid squares 0379 and 9679) and at the far side another 20' tick mark. By connecting the tick marks and crosses with straight lines, a 32°20'00" line of latitude can be added to the map. This procedure is also used to locate the 32°25'00" line of latitude. For lines of longitude, the same procedure is followed using the tick marks along the top and bottom edges of the map.

e. After the parallels and meridians have been drawn, the geographic interval (angular distance between two adjacent lines) must be determined. Examination of the values given at the tick marks gives the interval. For most maps of scale 1:25,000, the interval is 2'30". For the Columbus map and most maps of scale 1:50,000, it is 5'00". The geographic coordinates of a point are found by dividing the sides of the geographic square in which the point is located into the required number of equal parts. If the geographic interval is 5'00" and the location of a point is required to the nearest second, each side of the geographic square must be divided into 300 equal parts (5'00" = 300"), each of which would have a value of one second. Any scale or ruler that has 300 equal divisions and is as long as or longer than the spacing between the lines may be used.

f. The following steps will determine the geographic coordinates of Wilkinson Cemetery (northwest of the town of Cusseta) on the Columbus map.

(1) Draw the parallels and meridians on the map that encloses the area around the cemetery.

(2) Determine the values of the parallels and meridians where the point falls.

Latitude 32°15'00" and 32°20'00".
Longitude 84°45'00" and 84°50'00".

(3) Determine the geographic interval (5'00" = 300").

(4) Select a scale that has 300 small divisions or multiples thereof (300 divisions, one second each; 150 divisions, two seconds each; 75 divisions, four seconds each, and so forth).

(5) To determine the latitude—

(a) Place the scale with the 0 of the scale on the latitude of the lowest number value (32°15'00") and the 300 of the scale on the highest numbered line (32°20'00") (1, Figure 4-4).

(b) While keeping the 0 and 300 on the two lines, slide the scale (2, Figure 4-4) along the parallels until the Wilkinson Cemetery symbol is along the edge of the numbered scale.

(c) Read the number of seconds from the scale (3, Figure 4-4), about 246.

(d) Convert the number of seconds to minutes and seconds (246" = 4'06") and add to the value of the lower numbered line (32°15'00" + 4'06" = 32°19'06") (4, Figure 4-4).

RESULTS:

- The latitude is 32°19'06", but this is not enough.
- The latitude 32°19'06" could be either north or south of the equator, so the letter N or S must be added to the latitude. To determine whether it is N or S, look at the latitude values at the edge of the map and find the direction in which they become larger. If they are larger going north, use N; if they are larger going south, use S.
- The latitude for the cemetery is 32°19'06"N.

(6) Determine the longitude, repeat the same steps but measure between lines of longitude and use E and W. The geographic coordinates of Wilkinson Cemetery should be about 32°19'06"N and 84°47'32"W (Figure 4-5, page 4-6).

g. To locate a point on the Columbus map (Figure 4-6, page 4-7) when knowing the geographic coordinates, many of the same steps are followed. To locate 32°25'28"N and 84°50'56"W, first find the geographic lines within which the point falls: latitude 32°25'00" and 32°30'0"; and longitude 84°50'00" and 84°55'00". Subtract the lower latitude/longitude from the higher latitude/longitude.

(1) Place the 0 of the scale on the 32°25'00" line and the 300 on the 32°30'00". Make a mark at the number 28 on the scale (the difference between the lower and higher latitude).

(2) Place the 0 of the scale on the 84°50′00″ line and the 300 on the 84°50′55″. Make a mark at the number 56 on the scale (the difference between the lower and higher longitude.

(3) Draw a vertical line from the mark at 56 and a horizontal line from the mark at 28; they intersect at 32 25’28”N and 84 50’56”W.


TICK MARK
①
②
③
④
246
32° 19′ 06″ N LATITUDE
300
290
280
270
260
240
230
220
210
200
190
180
170
160
150
140
130
120
110
100
90
80
70
60
50
40
30
20
10
0
3580
20′
79
78
77
76
75
74
73
72
71
32°15′
84°45′
04
05
06
07
08
710
11
TICK MARK
①

Figure 4-4. Determining latitude.


TICK MARK
4
84° 47′ 32″ W LONGITUDE
2
3
152
1
1
TICK MARK
300
290
280
270
260
250
240
230
220
210
200
190
180
170
160
150
140
130
120
110
100
90
80
70
60
50
40
30
20
10
0
3580
79
78
77
76
75
74
73
72
71
04
05
06
07
08
09
710
11
32°15′
84°45′

Figure 4-5. Determining longitude.


84°55'00"
32°30'00"
TICK MARK
TICK MARK
1
2
3
84°55'56" W
84°55'56" W
32°25'28" N
32°25'28" N
TICK MARK
TICK MARK
32°25'00"
84°50'00"
84°55'00"

Figure 4-6. Determining geographic coordinates.

h. If you do not have a scale or ruler with 300 equal divisions or a map whose interval is other than 5'00", use the proportional parts method. Following the steps determines the geographic coordinates of horizontal control station 141.

(1) Locate horizontal control station 141 in grid square (GL0784) (Figure 4-7, page 4-9).

(2) Find a cross in grid square GL0388 and a tick mark in grid square GL1188 with 25'.

(3) Find another cross in grid square GL0379 and a tick mark in grid square GL1179 with 20'.

(4) Enclose the control station by connecting the crosses and tick marks. The control station is between 20' and 25' (Figure 4-7, page 4-9).

(5) With a boxwood scale, measure the distance from the bottom line to the top line that encloses the area around the control station on the map (total distance) (Figure 4-7).

(6) Measure the partial distance from the bottom line to the center of the control station (Figure 4-7). These straight-line distances are in direct proportion to the minutes and seconds of latitude and are used to set up a ratio.

RESULTS:

- The total distance is 9,200 meters, and the partial distance is 5,125 meters (Figure 4-7).
- With the two distances and the five-minute interval converted to seconds (300"), determine the minutes and seconds of latitude using the following formula:
    - 5,125 x 300 = 1,537,500
    - 1,537,500 ÷ 9,200 = 167
    - 167 ÷ 60 = 2'47"
    - Add 2'47" to 32°20'00" = 32°20'47"

(7) Follow the same procedures to determine minutes and seconds of longitude (Figure 4-7).

RESULTS:

- The total distance is 7,830 meters, and the partial distance is 4,000 meters (Figure 4-7).
    - 4,000 x 300 = 1,200,000
    - 1,200,000 ÷ 7,830 = 153
    - 153 ÷ 60 = 2'33"
    - Add 2'33" to 84°45' = 84°47'33"N


GLO388
GRID SQUARE
GL1188
7,830 METERS
CONTROL STATION 141
4,000 METERS
9,200 METERS
5,125 METERS
MILITARY RESERVATION
04
05
06
07
08
09
10
11
89
88
87
86
85
84
83
82
81
3580
GL0379
GRID SQUARE
GL1179

Figure 4-7. Using the proportional parts method.

(8) The geographic coordinates of horizontal control station 141 in grid square GL0784 are 32°22'47"N latitude and 84°47'33"W longitude.

NOTE: When computing formulas, round off totals to the nearest whole number in step 2. In step 3, convert the fraction to seconds by multiplying the fraction by 60 and rounding off if the total is not a whole number.

i. The maps made by some nations do not have their longitude values based on the prime meridian that passes through Greenwich, England. Table 4-1, on page 4-10, shows the prime meridians that may be used by other nations. When these maps are issued to our soldiers, a note usually appears in the marginal information giving the difference between our prime meridian and the one used on the map.

Amsterdam, Netherlands	4°53’01”E
Athens, Greece	23°42’59”E
Batavia (Djakarta), Indonesia	106°48’28”E
Bern, Switzerland	7°26’22”E
Brussels, Belgium	4°22’06”E
Copenhagen, Denmark	12°34’40”E
Ferro (Hierro), Canary Islands	17°39’46”W
Helsinki, Finland	24°53’17”E
Istanbul, Turkey	28°58’50”E
Lisbon, Portugal	9°07’55”W
Madrid, Spain	3°41’15”W
Oslo, Norway	10°43’23”E
Paris, France	2°20’14”E
Pulkovo, Russia	30°19’39”E
Rome, Italy	12°27’08”E
Stockholm, Sweden	18°03’30”E
Tirane, Albania	19°46’45”E

Table 1. Table of prime meridians.

4-3. MILITARY GRIDS

An examination of the transverse Mercator projection, which is used for large-scale military maps, shows that most lines of latitude and longitude are curved lines. The quadrangles formed by the intersection of these curved parallels and meridians are of different sizes and shapes, complicating the location of points and the measurement of directions. To aid these essential operations, a rectangular grid is superimposed upon the projection. This grid (a series of straight lines intersecting at right angles) furnishes the map reader with a system of squares similar to the block system of most city streets. The dimensions and orientation of different types of grids vary, but three properties are common to all military grid systems: one, they are true rectangular grids; two, they are superimposed on the geographic projection; and three, they permit linear and angular measurements.

a. **Universal Transverse Mercator Grid**. The UTM grid has been designed to cover that part of the world between latitude 84°N and latitude 80°S, and, as its name implies, is imposed on the transverse Mercator projection.

(1) Each of the 60 zones (6 degrees wide) into which the globe is divided for the grid has its own origin at the intersection of its central meridian and the equator (Figure 4-8). The grid is identical in all 60 zones. Base values (in meters) are assigned to the central meridian and the equator, and the grid lines are drawn at regular intervals parallel to these two base lines. With each grid line assigned a value denoting its distance from the origin, the problem of locating any point becomes progressively easier. Normally, it would seem logical to assign a value of zero to the two base lines and measure outward from them. This, however, would require either that directions—N, S, E, or W—be always given with distances, or that all points south of the equator or west of the central meridian have negative values.

(2) This inconvenience is eliminated by assigning "false values" to the base lines, resulting in positive values for all points within each zone. Distances are always measured RIGHT and UP (east and north as the reader faces the map), and the assigned values are called "false easting" and "false northing." (Figure 4-9, page 4-12). The false eating value for each central meridian is 500,000 meters, and the false northing value for the equator is 0 meters when measuring in the northern hemisphere and 10,000,000 meters when measuring in the southern hemisphere. The use of the UTM grid for point designation will be discussed in detail in paragraph 4-4.


180°
90°W
Y
Z
90°E
0°
9°
21°
33°
3°
X W V U T S R Q P N M L K J H G F E D C
UP
RIGHT
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60
(▨ indicates area located)
0°
90°W
A
B
90°E
180°

Figure 4-8. UTM grid zone location.

b. **Universal Polar Stereographic Grid**. The UPS grid is used to represent the polar regions. (Figure 4-10, page 4-13)

(1) ***North Polar Area***. The origin of the UPS grid applied to the north polar area is the north pole. The "north-south" base line is the line formed by the 0-degree and 180-degree meridians; the "east-west" base line is formed by the two 90-degree meridians.

(2) ***South Polar Area***. The origin of the UPS grid in the south polar area is the south pole. The base lines are similar to those of the north polar area.



Figure 4-9. False eastings and northings for the UPS grid.

4-4. UNITED STATES ARMY MILITARY GRID REFERENCE SYSTEM

This grid reference system is designated for use with the UTM and UPS grids. The coordinate value of points in these grids could contain as many as 15 digits if numerals alone were used. The US military grid reference system reduces the length of written coordinates by substituting single letters for several numbers. Using the UTM and the UPS grids, it is possible for the location of a point (identified by numbers alone) to be in many different places on the surface of the earth. With the use of the military grid reference system, there is no possibility of this happening.

a. **Grid Zone Designation.** The world is divided into 60 grid zones, which are large, regularly shaped geographic areas, each of which is given a unique identification called the grid zone designation.

(1) ***UTM Grid***. The first major breakdown is the division of each zone into areas 6° wide by 8° high and 6° wide by 12° high. Remember, for the transverse Mercator projection, the earth's surface between 80°S and 84°N is divided into 60 N-S zones, each 6° wide. These zones are numbered from west to east, 1 through 60, starting at the 180° meridian. This surface is divided into 20 east-west rows in which 19 are 8° high and 1 row at the extreme north is 12° high. These rows are then lettered, from south to north, C through X (I and O were omitted). Any 6° by 8° zone or 6° by 12° zone is identified by giving the number and letter of the grid zone and row in which it lies. These are read RIGHT and UP so the number is always written before the letter. This combination of zone number and row letter constitutes the grid zone designation. Columbus lies in zone 16 and row S, or in grid zone designation 16S (Figure 4-8, page 4-11).

(2) ***UPS Grid***. The remaining letters of the alphabet, A, B, Y, and Z, are used for the UPS grids. Each polar area is divided into two zones separated by the 0-180° meridian. In the south polar area, the letter A is the grid zone designation for the area west of the 0-180° meridian, and B for the area to the east. In the north polar area, Y is the grid zone designation for the western area and Z for the eastern area (Figure 4-10).



Figure 4-10. Grid zone designation for UPS grid.

b. **100,000-Meter Square.** Between 84°N and 80°S, each 6° by 8° or 6° by 12° zone is covered by 100,000-meter squares that are identified by the combination of two alphabetical letters. This identification is unique within the area covered by the grid zone designation. The first letter is the column designation; the second letter is the row designation (Figure 4-11, page 4-14). The north and south polar areas are also divided into 100,000-meter squares by columns and rows. A detailed discussion of the polar system can be found in Technical Report 8358.1. The 100,000-meter square identification letters are located in the grid reference box in the lower margin of the map.


PLATE 12
96°
580,000m
90°
500,000m
84°
QV TQ UQ VQ WQ XQ YQ BV CV DV EV FV GV KQ
QU TP UP VP WP XP YP BU CU DU EU FU GU KP
QT TN UN VN WN XN YN BT CT DT ET FT GT KN
QS TM UM VM WM XM YM BS CS DS ES FS GS KM
QR TL UL VL WL XL YL BR CR DR ER FR GR K
QQ TK UK VK WK XK YK BQ CQ DQ EQ FQ GQ K
QP TJ UJ VJ WJ XJ YJ BP CP DP EP FP GP K
QN TH UH VH WH XH YH BN CN DN EN FN GN K
QM TG UG VG WG XG YG BM CM DM EM FM GM K
QL TF UF VF WF XF YF BL CL DL EL FL GL K
15S
16S

Figure 4-11. Grid zone designation and 100,000-meter square identification.

c. **Grid Coordinates**. We have now divided the earth's surface into 6° by 8° quadrangles, and covered these with 100,000-meter squares. The military grid reference of a point consists of the numbers and letters indicating in which of these areas the point lies, plus the coordinates locating the point to the desired position within the 100,000-meter square. The next step is to tie in the coordinates of the point with the larger areas. To do this, you must understand the following.

(1) ***Grid Lines***. The regularly spaced lines that make the UTM and the UPS grid on any large-scale maps are divisions of the 100,000-meter square; the lines are spaced at 10,000- or 1,000-meter intervals (Figure 4-12). Each of these lines is labeled at both ends of the map with its false easting or false northing value, showing its relation to the origin of the zone. Two digits of the values are printed in large type, and these same two digits appear at intervals along the grid lines on the face of the map. These are called the principal digits, and represent the 10,000 and 1,000 digits of the grid value. They are of major importance to the map reader because they are the numbers he will use most often for referencing points. The smaller digits complete the UTM grid designation.



Figure 4-12. Grid lines.

EXAMPLE: The first grid line north of the south-west corner of the Columbus map is labeled 3570000m N. This means its false northing (distance north of the equator) is 3,570,000 meters. The principal digits, 70, identify the line for referencing points in the northerly direction. The smaller digits, 35, are part of the false coordinates and are rarely used. The last three digits, 000, of the value are omitted. Therefore, the first grid line east of the south-west corner is labeled 689000m E. The principal digits, 89, identify the line for referencing points in the easterly direction (Figure 4-13, page 4-16).


73
72
71
SCALE 18 km
3570000m.N.
32°15'
85°00'
689000m.E.
690
91
92
93
HOLY TRINITY 6.9 km
FRYAR FIELD
(Jump area)
Swimming pool
BM
MIL. RES
Prepared and published by the Defense Mapping Agency
Topographic Center, Washington, D. C.
LEGEND
ROAD DATA 1973—OTHER INFORMATION 1973

Figure 4-13. Columbus map, southwest corner.

(2) ***Grid Squares***. The north-south and east-west grid lines intersect at 90°, forming grid squares. Normally, the size of one of these grid squares on large-scale maps is 1,000 meters (1 kilometer).

(3) ***Grid Coordinate Scales***. The primary tool for plotting grid coordinates is the grid coordinate scale. The grid coordinate scale divides the grid square more accurately than can be done by estimation, and the results are more consistent. When used correctly, it presents less chance for making errors. GTA 5-2-12, 1981, contains four types of coordinate scales (Figure 4-14).


GTA 5-2-12, 1981
DEPARTMENT of the ARMY
GRAPHIC TRAINING AID
This GTA supersedes
GTA 5-2-10, 1980
Title: COORDINATE SCALE
AND PROTRACTOR
Headquarters, Department of
the Army
OUTER SCALE — MILS
INNER SCALE — DEGREES
1/50,000 METERS
1/100,000 METERS
1/25,000 – 1/250,000 METERS
1000/10,000
1000 9 8 7 6 5 4 3 2 1 0
0 1 2 3 4 5 6 7 8 9 1000
1000 8 6 4 2 0
0 2 4 6 8 1000
5800 6000 6200 0 200 400 600 800
320 325 330 335 340 345 350 355 0 5 10 15 20 25 30 35 40 45

Figure 4-14. Coordinate scales.

(a) The 1:25,000/1:250,000 (lower right in figure) can be used in two different scale maps, 1:25,000 or 1:250,000. The 1:25,000 scale subdivides the 1,000-meter grid block into 10 major subdivisions, each equal to 100 meters. Each 100-meter block has five graduations, each equal to 20 meters. Points falling between the two graduations can be read accurately by the use of estimation. These values are the fourth and eighth digits of the coordinates. Likewise, the 1:250,000 scale is subdivided in 10 major subdivisions, each equal to 1,000 meters. Each 1,000-meter block has five graduations, each equal to 200 meters. Points falling between two graduations can be read approximately by the use of estimation.

(b) The 1:50,000 scale (upper left in Figure 4-14) subdivides the 1,000-meter block into 10 major subdivisions, each equal to 100 meters. Each 100-meter block is then divided in half. Points falling between the graduations must be estimated to the nearest 10 meters for the fourth and eighth digits of the coordinates.

(c) The 1:100,000 scale (lower left in Figure 4-14) subdivides the 1,000-meter grid block into five major subdivisions of 200 meters each. Each 200-meter block is then divided in half at 100-meter intervals.

4-5. LOCATE A POINT USING GRID COORDINATES

Based on the military principle for reading maps (RIGHT and UP), locations on the map can be determined by grid coordinates. The number of digits represents the degree of precision to which a point has been located and measured on a map—the more digits the more precise the measurement.

a. **Without a Coordinate Scale**. Determine grids without a coordinate scale by referring to the north-south grid lines numbered at the bottom margin of any map. Then read RIGHT to the north-south grid line that precedes the desired point (this first set of two digits is the RIGHT reading). Then by referring to the east-west grid lines numbered at either side of the map, move UP to the east-west grid line that precedes the desired point (these two digits are the UP reading). Coordinate 1484 locate the 1,000-meter grid square in which point X is located; the next square to the right would be 1584; the next square up would be 1485, and so forth (Figure 4-15). Locate the point to the nearest 100 meters using estimation. Mentally divide the grid square in tenths, estimate the distance from the grid line to the point in the same order (RIGHT and UP). Give complete coordinate RIGHT, then complete coordinate UP. Point X is about two-tenths or 200 meters to the RIGHT into the grid square and about seven-tenths or 700 meters UP.

RESULTS: The coordinates to the nearest 100 meters are 142847.



Figure 4-15. Determining grids without coordinate point.

b. **With a Coordinate Scale (1:25,000)**. In order to use the coordinate scale for determining grid coordinates, ensure that the appropriate scale is being used on the corresponding map, and that the scale is right side up. To ensure the scale is correctly aligned, place it with the zero-zero point at the lower left corner of the grid square. Keeping the horizontal line of the scale directly on top of the east-west grid line, slide it to the right until the vertical line of the scale touches the point for which the coordinates are desired (Figure 4-16). When reading coordinates, examine the two sides of the coordinate scale to ensure that the horizontal line of the scale is aligned with the east-west grid line, and the vertical line of the scale is parallel with the north-south grid line. Use the scale when precision of more than 100 meters is required. To locate the point to the nearest 10 meters, measure the hundredths of a grid square RIGHT and UP from the grid lines to the point. Point X is about 17 hundredths or 170 meters RIGHT and 84 hundredths or 840 meters UP. The coordinates to the nearest 10 meters are 14178484.


1/25,000 – 1/250,000
METERS
ZERO-ZERO
POINT
1000/10,000
85
84
14
15

Figure 4-16. Placing a coordinate scale on a grid.

NOTE: Care should be exercised by the map reader using the coordinate scale when the desired point is located within the zero-zero point and the number 1 on the scale. Always prefix a zero if the hundredths reading is less than 10. In Figure 4-17, the desired point is reported as 14818407.


OUTER SCALE → MILS
INNER SCALE → DEGREES
1/25,000 – 1/250,000
METERS
ZERO-ZERO
POINT
1000/10,000
85
84
14
15

Figure 4-17. Zero-zero point.

c. **1:50,000 Coordinating Scale**. On the 1:50,000 coordinate scale, there are two sides: vertical and horizontal. These sides are 1,000 meters in length. The point at which the sides meet is the zero-zero point. Each side is divided into 10 equal 100-meter segments by a long tick mark and number. Each 100-meter segment is subdivided into 50-meter segments by a short tick mark (Figure 4-18). By using interpolation, mentally divide each 50-meter segment into tenths. For example, a point that lies after a whole number but before a short tick mark is identified as 10, 20, 30, or 40 meters and any point that lies after the short tick mark but before the whole number is identified as 60, 70, 80, or 90 meters.



Figure 4-18. 1:50,000 coordinating scale.

d. **Example of Obtaining an Eight-Digit Coordinate Using 1:50,000 Scale**. To ensure the scale is correctly aligned, place it with the zero-zero point at the lower left corner of the grid square. Keeping the horizontal line of the scale directly on top of the east-west grid line, slide the scale to the right until the vertical line of the scale touches the point for which the coordinates are desired (Figure 4-19, page 4-21). Reading **right**, you can see that the point lies **530** meters to the right into the grid square, which gives a right reading of **7853**. Reading **up**, you can see that the point lies **320** meters up into the grid square, giving an up reading of **0032**.



Figure 4-19. Example of obtaining an eight-digit coordinate using 1:50,000 scale.

e. **Recording and Reporting Grid Coordinates**. Coordinates are written as one continuous number without spaces, parentheses, dashes, or decimal points; they must always contain an even number of digits. Therefore, whoever is to use the written coordinates must know where to make the split between the RIGHT and UP readings. It is a military requirement that the 100,000-meter square identification letters be included in any point designation. Normally, grid coordinates are determined to the nearest 100 meters (six digits) for reporting locations. With practice, this can be done without using plotting scales. The location of targets and other point locations for fire support are determined to the nearest 10 meters (eight digits).

NOTE: Special care should be exercised when recording and reporting coordinates. Transposing numbers or making errors could be detrimental to military operations.

4-6. LOCATE A POINT USING THE US ARMY MILITARY GRID REFERENCE SYSTEM

There is only one rule to remember when reading or reporting grid coordinates—always read to the RIGHT and then UP. The first half of the reported set of coordinate digits represents the left-to-right (easting) grid label, and the second half represents the label as read from the bottom to top (northing). The grid coordinates may represent the location to the nearest 10-, 100-, or 1,000-meter increment.

a. **Grid Zone**. The number 16 locates a point within zone 16, which is an area 6° wide and extends between 80°S latitude and 84°N latitude (Figure 4-8, page 4-11).

b. **Grid Zone Designation**. The number and letter combination, 16S, further locates a point within the grid zone designation 16S, which is a quadrangle 6° wide by 8° high. There are 19 of these quads in zone 16. Quad X, which is located between 72°N and 84°N latitude, is 12° high (Figure 4-8, page 4-11).

c. **100,000-Meter Square Identification**. The addition of two more letters locates a point within the 100,000-meter grid square. Thus 16SGL (Figure 4-11, page 4-14) locates the point within the 100,000-meter square GL in the grid zone designation 16S. For information on the lettering system of 100,000-meter squares, see TM 5-241-1.

d. **10,000-Meter Square**. The breakdown of the US Army military grid reference system continues as each side of the 100,000-meter square is divided into 10 equal parts. This division produces lines that are 10,000 meters apart. Thus the coordinates 16SGL08 would locate a point as shown in Figure 4-20. The 10,000-meter grid lines appear as index (heavier) grid lines on maps at 1:100,000 and larger.



Figure 4-20. The 10,000-meter grid square.

e. **1,000-Meter Square**. To obtain 1,000-meter squares, each side of the 10,000-meter square is divided into 10 equal parts. This division appears on large-scale maps as the actual grid lines; they are 1,000 meters apart. On the Columbus map, using coordinates 16SGL0182, the easting 01 and the northing 82 gives the location of the southwest corner of grid square 0182 or to the nearest 1,000 meters of a point on the map (Figure 4-21).


Cemetery
Water Tower
Theater
Stroud Field
Kearin Range
Gas
Fire Station
Fort Benning Trailer Court
Kunzie Field
Division Road
01
02
83
83
Grandstand
Broomfield Range
Water
Gas
Grandstand
Grindstan
82
82
Maertens Rifle Range
01
02
Monroe Field
Grandstand
Earth Range
Brinson Range

CORNER OF
16SGL0182

Figure 4-21. The 1,000-meter grid square.

f. **100-Meter Identification**. To locate to the nearest 100 meters, the grid coordinate scale can be used to divide the 1,000-meter grid squares into 10 equal parts (Figure 4-22, page 4-24).

g. **10-Meter Identification**. The grid coordinate scale has divisions every 50 meters on the 1:50,000 scale and every 20 meters on the 1:25,000 scale. These can be used to estimate to the nearest 10 meters and give the location of one point on the earth's surface to the nearest 10 meters.

EXAMPLE: 16SGL01948253 (gas tank) (Figure 4-22).


10 METERS
16SL01948253
(GAS TANK)
Water
Gas
Four digits 0182 = 1,000 meters
Six digits 019825 = 100 meters
Eight digits 01948253 = 10 meters
CORNER OF
16SGL019825
16SGL
0194
8253
100 METERS

Figure 4-22. The 100-meter and 10-meter grid squares.

h. **Precision.** The precision of a point's location is shown by the number of digits in the coordinates; the more digits, the more precise the location (Figure 4-22, insert).

4-7. GRID REFERENCE BOX

A grid reference box (Figure 4-23) appears in the marginal information of each map sheet. It contains step-by-step instructions for using the grid and the US Army military grid reference system. The grid reference box is divided into two parts.

a. The left portion identifies the grid zone designation and the 100,000-meter square. If the sheet falls in more than one 100,000-meter square, the grid lines that separate the squares are shown in the diagram and the letters identifying the 100,000-meter squares are given.

EXAMPLE: On the Columbus map sheet, the vertical line labeled 00 is the grid line that separates the two 100,000-meter squares, FL and GL. The left portion also shows a sample for the 1,000-meter square with its respective labeled grid coordinate numbers and a sample point within the 1,000-meter square.

b. The right portion of the grid reference box explains how to use the grid and is keyed on the sample 1,000-meter square of the left side. The following is an example of the military grid reference:

EXAMPLE: 16S locates the 6° by 8° area (grid zone designation).



SAMPLE 1,000-METER GRID SQUARE

100,000-METER SQUARE IDENTIFICATION

GRID ZONE DESIGNATION

16S

100-METER REFERENCE

1. Read large numbers labeling the VERTICAL grid line left of point and estimate tenths (100-meters) from grid line to point.
2. Read large numbers labeling the HORIZONTAL grid line below point and estimate (100-meters) from grid line.

Example: 123456

WHEN REPORTING ACROSS A 100,000-METER LINE, PREFIX THE 100,000-METER SQUARE IDENTIFICATION, IN WHICH THE POINT LIES.

Example: FL123456

WHEN REPORTING OUTSIDE THE GRID ZONE DESIGNATION AREA, PREFIX THE GRID ZONE DESIGNATION.

Example: 16SFL123456

Figure 4-23. Grid reference box.

4-8. OTHER GRID SYSTEMS

The military grid reference system is not universally used. Soldiers must be prepared to interpret and use other grid systems, depending on the area of operations or the personnel the soldiers are operating with.

a. **British Grids**. In a few areas of the world, British grids are still shown on military maps. However, the British grid systems are being phased out. Eventually all military mapping will be converted to the UTM grid.

b. **World Geographic Reference System (GEOREF).** This system is a worldwide position reference system used primarily by the US Air Force. It may be used with any map or chart that has latitude and longitude printed on it. Instructions for using GEOREF data are printed in blue and are found in the margin of aeronautical charts (Figure 4-24, page 4-26). This system is based upon a division of the earth's surface into quadrangles of latitude and longitude having a systematic identification code. It is a method of expressing latitude and longitude in a form suitable for rapid reporting and plotting. Figure 4-24 illustrates a sample grid reference box using GEOREF. The GEOREF system uses an identification code that has three main divisions.



TO REFERENCE BY GEOREF (SHOWN IN BLUE) TO MINUTES

Select nearest intersection south and west of point.

Sample Point: KIGYE

1. WJ identifies basic 15° quadrangle.
2. KG identifies 1° quadrangle.
3. 15 identifies Georef minute of longitude.
4. 03 identifies Georef minute of latitude.
5. Sample reference: WJKG 1503.

Figure 4-24. Sample reference using GEOREF.

(1) ***First Division***. There are 24 north-south (longitudinal) zones, each 15-degree wide. These zones, starting at 180 degrees and progressing eastward, are lettered A through Z (omitting I and O). The first letter of any GEOREF coordinate identifies the north-south zone in which the point is located. There are 12 east-west (latitudinal) bands, each 15-degree wide. These bands are lettered A through M (omitting I) northward from the south pole. The second letter of any GEOREF coordinate identifies the east-west band in which the point is located. The zones and bands divide the earth's surface into 288 quadrangles, each identified by two letters.

(2) ***Second Division***. Each 15-degree quadrangle is further divided into 225 quadrangles of 1 degree each (15 degrees by 15 degrees). This division is effected by dividing a basic 15-degree quadrangle into 15 north-south zones and 15 east-west bands. The north-south zones are lettered A through Q (omitting I and O) from west to east. The third letter of any GEOREF coordinate identifies the 1 degree north-south zone within a 15-degree quadrangle. The east-west bands are lettered A through Q (I and O omitted) from south to north. The fourth letter of a GEOREF coordinate identifies the 1 degree east-west band within a 15-degree quadrangle. Four letters identify any 1-degree quadrangle in the world.

(3) ***Third Division***. Each of the 1-degree quadrangles is divided into 3,600 one-minute quadrangles. These one-minute quadrangles are formed by dividing the 1-degree quadrangles into 60 one-minute north-south zones numbered 0 through 59 from west to east, and 60 east-west bands numbered 0 to 59 from south to north. To designate any one of the 3,600 one-minute quadrangles requires four letters and four numbers. The rule READ RIGHT AND UP is always followed. Numbers 1 through 9 are written as 01, 02, and so forth. Each of the 1-minute quadrangles may be further divided into 10 smaller divisions both north-south and east-west, permitting the identification of 0.1-minute quadrangles. The GEOREF coordinate for any 0.1-minute quadrangle consists of four letters and six numbers.

4-9. PROTECTION OF MAP COORDINATES AND LOCATIONS

A disadvantage of any standard system of location is that the enemy, if he intercepts one of our messages using the system, can interpret the message and find our location. It is possible and can be eliminated by using an authorized low-level numerical code to express locations. Army Regulation 380-40 outlines the procedures for obtaining authorized codes.

a. The authorized numerical code provides a capability for encrypting map references and other numerical information that requires short-term security protection when, for operational reasons, the remainder of the message is transmitted in plain language. The system is published in easy-to-use booklets with sufficient material in each for one month's operation. Sample training editions of this type of system are available through the unit's communications and electronics officer.

b. The use of any encryption methods other than authorized codes is, by regulation, unauthorized and shall not be used.

CHAPTER 5
SCALE AND DISTANCE

A map is a scaled graphic representation of a portion of the earth's surface. The scale of the map permits the user to convert distance on the map to distance on the ground or vice versa. The ability to determine distance on a map, as well as on the earth's surface, is an important factor in planning and executing military missions.

5-1. REPRESENTATIVE FRACTION

The numerical scale of a map indicates the relationship of distance measured on a map and the corresponding distance on the ground. This scale is usually written as a fraction and is called the representative fraction. The RF is always written with the map distance as 1 and is independent of any unit of measure. (It could be yards, meters, inches, and so forth.) An RF of 1/50,000 or 1:50,000 means that one unit of measure on the map is equal to 50,000 units of the same measure on the ground.

a. The ground distance between two points is determined by measuring between the same two points on the map and then multiplying the map measurement by the denominator of the RF or scale (Figure 5-1, page 5-2).

EXAMPLE:

The map scale is 1:50,000
RF = 1/50,000
The map distance from point A to point B is 5 units
5 x 50,000 = 250,000 units of ground distance

b. Since the distance on most maps is marked in meters and the RF is expressed in this unit of measurement in most cases, a brief description of the metric system is needed. In the metric system, the standard unit of measurement is the meter.

1 meter contains 100 centimeters (cm).
100 meters is a regular football field plus 10 meters.
1,000 meters is 1 kilometer (km).
10 kilometers is 10,000 meters.

Appendix C contains the conversion tables.

c. The situation may arise when a map or sketch has no RF or scale. To be able to determine ground distance on such a map, the RF must be determined. There are two ways to do this:

(1) ***Comparison with Ground Distance***.

(a) Measure the distance between two points on the map—map distance (MD).

(b) Determine the horizontal distance between these same two points on the ground—ground distance (GD).

(c) Use the RF formula and remember that RF must be in the general form:

$$RF = \frac{1}{X} = \frac{MD}{GD}$$



Figure 5-1. Converting map distance to ground distance.

(d) Both the MD and the GD must be in the same unit of measure and the MD must be reduced to 1.

EXAMPLE:

MD = 4.32 centimeters

GD = 2.16 kilometers
(216,000 centimeters)

$$RF = \frac{1}{X} = \frac{4.32}{216{,}000}$$

or

$$\frac{216{,}000}{4.32} = 50{,}000$$

therefore

$$RF = \frac{1}{50{,}000} \quad \textit{or} \quad 1{:}50{,}000$$

(2) ***Comparison With Another Map of the Same Area that Has an RF***.

(a) Select two points on the map with the unknown RF. Measure the distance (MD) between them.

(b) Locate those same two points on the map that have the known RF. Measure the distance (MD) between them. Using the RF for this map, determine GD, which is the same for both maps.

(c) Using the GD and the MD from the first map, determine the RF using the formula:

$$RF = \frac{1}{X} = \frac{MD}{GD}$$

d. Occasionally it may be necessary to determine map distance from a known ground distance and the RF:

$$MD = \frac{GD}{\text{Denominator or RF}}$$

$$\text{Ground Distance} = 2{,}200 \text{ meters}$$

$$RF = 1:50{,}000$$

$$MD = \frac{2{,}200 \text{ meters}}{50{,}000}$$

$$MD = 0.044 \text{ meters} \times 100 \text{ (centimeters per meter)}$$

$$MD = 4.4 \text{ centimeters}$$

e. When determining ground distance from a map, the scale of the map affects the accuracy. As the scale becomes smaller, the accuracy of measurement decreases because some of the features on the map must be exaggerated so that they may be readily identified.

5-2. GRAPHIC (BAR) SCALES

A graphic scale is a ruler printed on the map and is used to convert distances on the map to actual ground distances. The graphic scale is divided into two parts. To the right of the zero, the scale is marked in full units of measure and is called the primary scale. To the left of the zero, the scale is divided into tenths and is called the extension scale. Most maps have three or more graphic scales, each using a different unit of measure (Figure 5-2). When using the graphic scale, be sure to use the correct scale for the unit of measure desired.


EXTENSION SCALE
PRIMARY SCALE
Scale 1:50,000
Meters 1000 500 0 1 2 3 4 5 Kilometers
1 ½ 0 1 2 3 Statute Miles
1 ½ 0 1 2 3 Nautical Miles

Figure 5-2. Using a graphic (bar) scale.

a. To determine straight-line distance between two points on a map, lay a straight-edged piece of paper on the map so that the edge of the paper touches both points and extends past them. Make a tick mark on the edge of the paper at each point (Figure 5-3).


B
A
(a)
(b)
TICK MARKS ON PAPER STRIP
NOTE: When measuring distance, use center mass of symbol or object.

Figure 5-3. Transferring map distance to paper strip.

b. To convert the map distance to ground distance, move the paper down to the graphic bar scale, and align the right tick mark (b) with a printed number in the primary scale so that the left tick mark (a) is in the extension scale (Figure 5-4).


Scale 1:50,000
Meters 1000 500 0 1 2 3 4
Distance of 3 kilometers, 950 meters
(3,950 meters)
(a)
(b)

Figure 5-4. Measuring straight-line map distance.

c. The right tick mark (b) is aligned with the 3,000-meter mark in the primary scale, thus the distance is at least 3,000 meters. To determine the distance between the two points to the nearest 10 meters, look at the extension scale. The extension scale is numbered with zero at the right and increases to the left. When using the extension scale, always read right to left (Figure 5-4). From the zero left to the beginning of the first shaded area is 100 meters. From the beginning of the shaded square to the end of the shaded square is 100 to 200 meters. From the end of the first shaded square to the beginning of the second shaded square is 200 to 300 meters. Remember, the distance in the extension scale increases from right to left.

d. To determine the distance from the zero to tick mark (a), divide the distance inside the squares into tenths (Figure 5-4). As you break down the distance between the squares in the extension scale into tenths, you will see that tick mark (a) is aligned with the 950-meter mark. Adding the distance of 3,000 meters determined in the primary scale to the 950 meters you determined by using the extension scale, we find that the total distance between points (a) and (b) is 3,950 meters.

e. To measure distance along a road, stream, or other curved line, the straight edge of a piece of paper is used. In order to avoid confusion concerning the point to begin measuring from and the ending point, an eight-digit coordinate should be given for both the starting and ending points. Place a tick mark on the paper and map at the beginning point from which the curved line is to be measured. Align the edge of the paper along a straight portion and make a tick mark on both map and paper when the edge of the paper leaves the straight portion of the line being measured (Figure 5-5A, page 5-7).

f. Keeping both tick marks together (on paper and map), place the point of the pencil close to the edge of the paper on the tick mark to hold it in place and pivot the paper until another straight portion of the curved line is aligned with the edge of the paper. Continue in this manner until the measurement is completed (Figure 5-5B, page 5-7).

g. When you have completed measuring the distance, move the paper to the graphic scale to determine the ground distance. The only tick marks you will be measuring the distance between are tick marks (a) and (b). The tick marks in between are not used (Figure 5-5C, page 5-7).

h. There may be times when the distance you measure on the edge of the paper exceeds the graphic scale. In this case, there are different techniques you can use to determine the distance.

(1) One technique is to align the right tick mark (b) with a printed number in the primary scale, in this case the 5. You can see that from point (a) to point (b) is more than 6,000 meters when you add the 1,000 meters in the extension scale. To determine the exact distance to the nearest 10 meters, place a tick mark (c) on the edge of the paper at the end of the extension scale (Figure 5-6A, page 5-8). You know that from point (b) to point (c) is 6,000 meters. With the tick mark (c) placed on the edge of the paper at the end of the extension scale, slide the paper to the right. Remember the distance in the extension is always read from right to left. Align tick mark (c) with zero and then measure the distance between tick marks (a) and (c). The distance between tick marks (a) and (c) is 420 meters. The total ground distance between start and finish points is 6,420 meters (Figure 5-6B, page 5-8).


A
STARTING POINT
A
(a)
STEAM MILL ROAD
CREEK
BSA Camp
Barnett
Frey Range
McBride Bridge
B
Landing strip
FINISH POINT B
(b)
STARTING POINT
A
Long Branch
Airfield
TIS Camp
(a)
C
Scale 1:50,000
1000
500
0
1
2
3
4
(a)
(b)
Distance from (a) to (b) is 4,250 meters

Figure 5-5. Measuring a curved line.



Figure 5-6. Determining the exact distance.

(2) Another technique that may be used to determine exact distance between two points when the edge of the paper exceeds the bar scale is to slide the edge of the paper to the right until tick mark (a) is aligned with the edge of the extension scale. Make a tick mark on the paper, in line with the 2,000-meter mark (c) (Figure 5-7A). Then slide the edge of the paper to the left until tick mark (b) is aligned with the zero. Estimate the 100-meter increments into 10-meter increments to determine how many meters tick mark (c) is from the zero line (Figure 5-7B). The total distance would be 3,030 meters.

(3) At times you may want to know the distance from a point on the map to a point off the map. In order to do this, measure the distance from the start point to the edge of the map. The marginal notes give the road distance from the edge of the map to some towns, highways, or junctions off the map. To determine the total distance, add the distance measured on the map to the distance given in the marginal notes. Be sure the unit of measure is the same.

(4) When measuring distance in statute or nautical miles, round it off to the nearest one-tenth of a mile and make sure the appropriate bar scale is used.

(5) Distance measured on a map does not take into consideration the rise and fall of the land. All distances measured by using the map and graphic scales are flat distances. Therefore, the distance measured on a map will increase when actually measured on the ground. This must be taken into consideration when navigating across country.



Figure 5-7. Reading the extension scale.

i. The amount of time required to travel a certain distance on the ground is an important factor in most military operations. This can be determined if a map of the area is available and a graphic time-distance scale is constructed for use with the map as follows:

R = Rate of travel (speed)

D = Distance (ground distance)

T = Time

$$T = \frac{D}{R}$$

For example, if an infantry unit is marching at an average rate (R) of 4 kilometers per hour, it will take about 3 hours (T) to travel 12 kilometers.

$$\frac{12\ (D)}{4\ (R)} = 3\ (T)$$

j. To construct a time-distance scale (Figure 5-8A), knowing your length of march, rate of speed, and map scale, that is, 12 kilometers at 3 kilometers per hour on a 1:50,000-scale map, use the following process:

(1) Mark off the total distance on a line by referring to the graphic scale of the map or, if this is impracticable, compute the length of the line as follows:

(a) Convert the ground distance to centimeters: 12 kilometers x 100,000 (centimeters per kilometer) = 1,200,000 centimeters.

(b) Find the length of the line to represent the distance at map scale—

$$MD = \frac{1}{50{,}000} = \frac{1{,}200{,}000}{50{,}000} = 24 \text{ centimeters}$$

(c) Construct a line 24 centimeters in length (Figure 5-8A).

(2) Divide the line by the rate of march into three parts (Figure 5-8B), each part representing the distance traveled in one hour, and label.

(3) Divide the scale extension (left portion) into the desired number of lesser time divisions—

1-minute divisions — 60
5-minute divisions — 12
10-minute divisions — 6

(4) Figure 5-8C shows a 5-minute interval scale. Make these divisions in the same manner as for a graphic scale. The completed scale makes it possible to determine where the unit will be at any given time. However, it must be remembered that this scale is for one specific rate of march only, 4 kilometers per hour.


(Length of lines are illustrative only and not at 1:50,000 scale)
A
24 CENTIMETERS
B
1 HOUR
0
1 HOUR
2 HOURS
C
1 HOUR
0
1 HOUR
2 HOURS
24 centimeters (5-minute intervals)
(Rate of march: 4-kilometers per hour)

Figure 5-8. Constructing a time-distance scale.

5-3. OTHER METHODS

Determining distance is the most common source of error encountered while moving either mounted or dismounted. There may be circumstances where you are unable to determine distance using your map or where you are without a map. It is therefore essential to learn methods by which you can accurately pace, measure, use subtense, or estimate distances on the ground.

a. **Pace Count**. Another way to measure ground distance is the pace count. A pace is equal to one natural step, about 30 inches long. To accurately use the pace count method, you must know how many paces it takes you to walk 100 meters. To determine this, you must walk an accurately measured course and count the number of paces you take. A pace course can be as short as 100 meters or as long as 600 meters. The pace course, regardless of length, must be on similar terrain to that you will be walking over. It does no good to walk a course on flat terrain and then try to use that pace count on hilly terrain. To determine your pace count on a 600-meter course, count the paces it takes you to walk the 600 meters, then divide the total paces by 6. The answer will give you the average paces it takes you to walk 100 meters. It is important that each person who navigates while dismounted knows his pace count.

(1) There are many methods to keep track of the distance traveled when using the pace count. Some of these methods are: put a pebble in your pocket every time you have walked 100 meters according to your pace count; tie knots in a string; or put marks in a notebook. Do not try to remember the count; always use one of these methods or design your own method.

(2) Certain conditions affect your pace count in the field, and you must allow for them by making adjustments.

(a) *Slopes*. Your pace lengthens on a downslope and shortens on an upgrade. Keeping this in mind, if it normally takes you 120 paces to walk 100 meters, your pace count may increase to 130 or more when walking up a slope.

(b) *Winds*. A head wind shortens the pace and a tail wind increases it.

(c) *Surfaces*. Sand, gravel, mud, snow, and similar surface materials tend to shorten the pace.

(d) *Elements*. Falling snow, rain, or ice cause the pace to be reduced in length.

(e) *Clothing*. Excess clothing and boots with poor traction affect the pace length.

(f) *Visibility.* Poor visibility, such as in fog, rain, or darkness, will shorten your pace.

b. **Odometer**. Distances can be measured by an odometer, which is standard equipment on most vehicles. Readings are recorded at the start and end of a course and the difference is the length of the course.

(1) To convert kilometers to miles, multiply the number of kilometers by 0.62.

EXAMPLE:

16 *kilometers* = 16 x 0.62 = 9.92 *miles*

(2) To convert miles to kilometers, divided the number of miles by 0.62.

EXAMPLE:

10 *miles* = 10 *divided by* 0.62 = 16.12 *kilometers*

c. **Subtense**. The subtense method is a fast method of determining distance and yields accuracy equivalent to that obtained by measuring distance with a premeasured piece of wire. An advantage is that a horizontal distance is obtained indirectly; that is, the distance is computed rather than measured. This allows subtense to be used over terrain where obstacles such as streams, ravines, or steep slopes may prohibit other methods of determining distance.

(1) The principle used in determining distance by the subtense method is similar to that used in estimating distance by the mil relation formula. The field artillery application of the mil relation formula involves only estimations. It is not accurate enough for survey purposes. However, the subtense method uses precise values with a trigonometric solution. Subtense is based on a principle of visual perspective—the farther away an object, the smaller it appears.

(2) The following two procedures are involved in subtense measurement:

- Establishing a base of known length.
- Measuring the angle of that base by use of the aiming circle.

(3) The subtense base may be any desired length. However, if a 60-meter base, a 2-meter bar, or the length of an M16A1 or M16A2 rifle is used, precomputed subtense tables are available. The M16 or 2-meter bar must be held horizontal and perpendicular to the line of sight by a soldier facing the aiming circle. The instrument operator sights on one end of the M16 or 2-meter bar and measures the horizontal clockwise angle to the other end of the rifle or bar. He does this twice and averages the angles. He then enters the appropriate subtense table with the mean angle and extracts the distance. Accurate distances can be obtained with the M16 out to approximately 150 meters, with the 2-meter bar out to 250 meters, and with the 60-meter base out to 1,000 meters. If a base of another length is desired, a distance can be computed by using the following formula:

$$\textit{Distance} = \frac{\textit{1/2 (base in meters)}}{\textit{Tan (1/2) (in mils)}}$$

d. **Estimation**. At times, because of the tactical situation, it may be necessary to estimate range. There are two methods that may be used to estimate range or distance.

(1) ***100-Meter Unit-of-Measure Method***. To use this method, the soldier must be able to visualize a distance of 100 meters on the ground. For ranges up to 500 meters, he determines the number of 100-meter increments between the two objects he wishes to measure. Beyond 500 meters, the soldier must select a point halfway to the object(s) and determine the number of 100-meter increments to the halfway point, then double it to find the range to the object(s) (Figure 5-9).


100
200
300
400
500
600
700
800
THE HOUSE IS ABOUT 400 METERS... THE SILO IS ABOUT 800 METERS.

Figure 5-9. Using a 100-meter unit-of-measure method.

(2) ***Flash-To-Bang Method***. To use this method to determine range to an explosion or enemy fire, begin to count when you see the flash. Count the seconds until you hear the weapon fire. This time interval may be measured with a stopwatch or by using a steady count, such as one-thousand-one, one-thousand-two, and so forth, for a three-second estimated count. If you must count higher than 10 seconds, start over with one. Multiply the number of seconds by 330 meters to get the approximate range (FA uses 350 meters instead).

(3) ***Proficiency of Methods***. The methods discussed above are used only to estimate range (Table 5-1). Proficiency in both methods requires constant practice. The best training technique is to require the soldier to pace the range after he has estimated the distance. In this way, the soldier discovers the actual range for himself, which makes a greater impression than if he is simply told the correct range.

Factors Affecting Range Estimation	Factors Causing Underestimation of Range	Factors Causing Overestimation of Range
The clearness of outline and details of the object.	When most of the object is visible and offers a clear outline.	When only a small part of the object can be seen or the object is small in relation to its surroundings.
Nature of terrain or position of the observer.	When looking across a depression that is mostly hidden from view. When looking downward from high ground. When looking down a straight, open road or along a railroad. When looking over uniform surfaces like water, snow, desert, or grain fields. In bright light or when the sun is shining from behind the observer.	When looking across a depression that is totally visible. When vision is confined, as in streets, draws, or forest trails. When looking from low ground toward high ground. In poor light, such as dawn and dusk; in rain, snow, fog; or when the sun is in the observer's eyes.
Light and atmosphere	When the object is in sharp contrast with the background or is silhouetted because of its size, shape, or color. When seen in the clear air of high altitudes.	When object blends into the background or terrain.

Table 5-1. Factors of range estimation.

CHAPTER 6

DIRECTION

Being in the right place at the prescribed time is necessary to successfully accomplish military missions. Direction plays an important role in a soldier's everyday life. It can be expressed as right, left, straight ahead, and so forth; but then the question arises, "To the right of what?" This chapter defines the word azimuth and the three different norths. It explains in detail how to determine the grid and the magnetic azimuths with the use of the protractor and the compass. It explains the use of some field-expedient methods to find directions, the declination diagram, and the conversion of azimuths from grid to magnetic and vice versa. It also includes some advanced aspects of map reading, such as intersection, resection, modified resection, and polar plots.

6-1. METHODS OF EXPRESSING DIRECTION

Military personnel need a way of expressing direction that is accurate, is adaptable to any part of the world, and has a common unit of measure. Directions are expressed as units of angular measure.

a. **Degree**. The most common unit of measure is the degree (°) with its subdivisions of minutes (') and seconds (").

1 degree = 60 minutes.
1 minute = 60 seconds.

b. **Mil.** Another unit of measure, the mil (abbreviated m̸), is used mainly in artillery, tank, and mortar gunnery. The mil expresses the size of an angle formed when a circle is divided into 6,400 angles, with the vertex of the angles at the center of the circle. A relationship can be established between degrees and mils. A circle equals 6400 mils divided by 360 degrees, or 17.78 mils per degree. To convert degrees to mils, multiply degrees by 17.78.

c. **Grad.** The grad is a metric unit of measure found on some foreign maps. There are 400 grads in a circle (a 90-degree right angle equals 100 grads). The grad is divided into 100 centesimal minutes (centigrads) and the minute into 100 centesimal seconds (milligrads).

6-2. BASE LINES

In order to measure something, there must always be a starting point or zero measurement. To express direction as a unit of angular measure, there must be a starting point or zero measure and a point of reference These two points designate the base or reference line. There are three base lines—true north, magnetic north, and grid north. The most commonly used are magnetic and grid.

a**.** **True North.** A line from any point on the earth's surface to the north pole. All lines of longitude are true north lines. True north is usually represented by a star (Figure 6-1, page 6-2).

b**.** **Magnetic North**. The direction to the north magnetic pole, as indicated by the north-seeking needle of a magnetic instrument. The magnetic north is usually symbolized by a line ending with half of an arrowhead (Figure 6-1). Magnetic readings are obtained with magnetic instruments, such as lensatic and M2 compasses.

c. **Grid North.** The north that is established by using the vertical grid lines on the map. Grid north may be symbolized by the letters GN or the letter "y" (Figure 6-1).



Figure 6-1. Three norths.

6-3. AZIMUTHS

An azimuth is defined as a horizontal angle measured clockwise from a north base line. This north base line could be true north, magnetic north, or grid north. The azimuth is the most common military method to express direction. When using an azimuth, the point from which the azimuth originates is the center of an imaginary circle (Figure 6-2). This circle is divided into 360 degrees or 6400 mils (Appendix G).



Figure 6-2. Origin of azimuth circle.

a. **Back Azimuth**. A back azimuth is the opposite direction of an azimuth. It is comparable to doing "about face." To obtain a back azimuth from an azimuth, add 180 degrees if the azimuth is 180 degrees or less, or subtract 180 degrees if the azimuth is 180 degrees or more (Figure 6-3). The back azimuth of 180 degrees may be stated as 0 degrees or 360 degrees. For mils, if the azimuth is less than 3200 mils, add 3200 mils, if the azimuth is more than 3200 mils, subtract 3200 mils.



EXAMPLE:

Azimuth	±		Back Azimuth
115°	+180°	=	295°
337°=	- 180°	=	157°

Figure 6-3. Back azimuth.

WARNING

When converting azimuths into back azimuths, extreme care should be exercised when adding or subtracting the 180 degrees. A simple mathematical mistake could cause disastrous consequences.

b. **Magnetic Azimuth.** The magnetic azimuth is determined by using magnetic instruments, such as lensatic and M2 compasses. Refer to Chapter 9, paragraph 4, for details.

c. **Field-Expedient Methods**. Several field-expedient methods to determine direction are discussed in Chapter 9, paragraph 5.

6-4. GRID AZIMUTHS

When an azimuth is plotted on a map between point A (starting point) and point B (ending point), the points are joined together by a straight line. A protractor is used to measure the angle between grid north and the drawn line, and this measured azimuth is the grid azimuth (Figure 6-4).

WARNING

When measuring azimuths on a map, remember that you are measuring from a starting point to an ending point. If a mistake is made and the reading is taken from the ending point, the grid azimuth will be opposite, thus causing the user to go in the wrong direction.


OUTER SCALE – MILS
INNER SCALE – DEGREES
A
B
DRAWN LINE
MILITARY
Lawson Field
Dixie Village
DIXIE ROAD
Amtreville Field
CHATTAHOOCHEE
87
88
89
90

Figure 6-4. Measuring an azimuth.

6-5. PROTRACTOR

There are several types of protractors—full circle, half circle, square, and rectangular (Figure 6-5). All of them divide the circle into units of angular measure, and each has a scale around the outer edge and an index mark. The index mark is the center of the protractor circle from which all directions are measured.



SEMICIRCULAR

RECTANGULAR

CIRCULAR

SQUARE

Figure 6-5. Types of protractors.

a. The military protractor, GTA 5-2-12, contains two scales: one in degrees (inner scale) and one in mils (outer scale). This protractor represents the azimuth circle. The degree scale is graduated from 0 to 360 degrees; each tick mark on the degree scale represents one degree. A line from 0 to 180 degrees is called the base line of the protractor. Where the base line intersects the horizontal line, between 90 and 270 degrees, is the index or center of the protractor (Figure 6-6).


BASE LINE
DEGREES
MILS
INDEX
GTA 5-2-12, 1981
DEPARTMENT of the ARMY
GRAPHIC TRAINING AID
This GTA supersedes
GTA 5-2-10, 1980
Title: COORDINATE SCALE
AND PROTRACTOR
Headquarters, Department of
the Army
OUTER SCALE — MILS
INNER SCALE — DEGREES
1/50,000 METERS
1/25,000 - 1/250,000 METERS
1/100,000 METERS
1000/10,000

Figure 6-6. Military protractor.

b. When using the protractor, the base line is always oriented parallel to a north-south grid line. The 0- or 360-degree mark is always toward the top or north on the map and the 90° mark is to the right.

(1) To determine the grid azimuth—

(a) Draw a line connecting the two points (A and B).

(b) Place the index of the protractor at the point where the drawn line crosses a vertical (north-south) grid line.

(c) Keeping the index at this point, align the 0- to 180-degree line of the protractor on the vertical grid line.

(d) Read the value of the angle from the scale; this is the grid azimuth from point A to point B (Figure 6-4).

(2) To plot an azimuth from a known point on a map (Figure 6-7)—

(a) Convert the azimuth from magnetic to grid, if necessary. (See paragraph 6-6.)

(b) Place the protractor on the map with the index mark at the center of mass of the known point and the base line parallel to a north-south grid line.

(c) Make a mark on the map at the desired azimuth.

(d) Remove the protractor and draw a line connecting the known point and the mark on the map. This is the grid direction line (azimuth).

NOTE: When measuring an azimuth, the reading is always to the nearest degree or 10 mils. Distance does not change an accurately measured azimuth.



Figure 6-7. Plotting an azimuth on the map.

c. To obtain an accurate reading with the protractor (to the nearest degree or 10 mils), there are two techniques to check that the base line of the protractor is parallel to a north-south grid line.

(1) Place the protractor index where the azimuth line cuts a north-south grid line, aligning the base line of the protractor directly over the intersection of the azimuth line with the north-south grid line. The user should be able to determine whether the initial azimuth reading was correct.

(2) The user should re-read the azimuth between the azimuth and north-south grid line to check the initial azimuth.

(3) Note that the protractor is cut at both the top and bottom by the same north-south grid line. Count the number of degrees from the 0-degree mark at the top of the protractor to this north-south grid line and then count the number of degrees from the 180-degree mark at the bottom of the protractor to this same grid line. If the two counts are equal, the protractor is properly aligned.

6-6. DECLINATION DIAGRAM

Declination is the angular difference between any two norths. If you have a map and a compass, the one of most interest to you will be between magnetic and grid north. The declination diagram (Figure 6-8) shows the angular relationship, represented by prongs, among grid, magnetic, and true norths. While the relative positions of the prongs are correct, they are seldom plotted to scale. Do not use the diagram to measure a numerical value. This value will be written in the map margin (in both degrees and mils) beside the diagram.

a. **Location.** A declination diagram is a part of the information in the lower margin on most larger maps. On medium-scale maps, the declination information is shown by a note in the map margin.

b. **Grid-Magnetic Angle.** The G-M angle value is the angular size that exists between grid north and magnetic north. It is an arc, indicated by a dashed line, that connects the grid-north and magnetic-north prongs. This value is expressed to the nearest 1/2 degree, with mil equivalents shown to the nearest 10 mils. The G-M angle is important to the map reader/land navigator because azimuths translated between map and ground will be in error by the size of the declination angle if not adjusted for it.

c. **Grid Convergence**. An arc indicated by a dashed line connects the prongs for true north and grid north. The value of the angle for the center of the sheet is given to the nearest full minute with its equivalent to the nearest mil. These data are shown in the form of a grid-convergence note.

d. **Conversion.** There is an angular difference between the grid north and the magnetic north. Since the location of magnetic north does not correspond exactly with the grid-north lines on the maps, a conversion from magnetic to grid or vice versa is needed.

(1) ***With Notes***. Simply refer to the conversion notes that appear in conjunction with the diagram explaining the use of the G-M angle (Figure 6-8). One note provides instructions for converting magnetic azimuth to grid azimuth; the other, for converting grid azimuth to magnetic azimuth. The conversion (add or subtract) is governed by the direction of the magnetic-north prong relative to that of the north-grid prong.


GN
MAGNETIC NORTH
GRID NORTH
1960 G-M ANGLE
5° (90 MILS)
TRUE NORTH
TO CONVERT A
MAGNETIC AZIMUTH
TO GRID AZIMUTH
SUBTRACT G-M ANGLE
GRID CONVERGENCE
1° 19' (23 MILS)
FOR CENTER OF SHEET
TO CONVERT A
GRID AZIMUTH TO A
MAGNETIC AZIIMUTH
ADD G-M ANGLE
GN
MAGNETIC NORTH
TRUE NORTH
GRID NORTH
1960 G-M ANGLE
7 1/2° (130 MILS)
TO CONVERT A
MAGNETIC AZIMUTH
TO GRID AZIMUTH
SUBTRACT G-M ANGLE
GRID CONVERGENCE
2° 26' (43 MILS)
FOR CENTER OF SHEET
TO CONVERT A
GRID AZIMUTH TO A
MAGNETIC AZIIMUTH
ADD G-M ANGLE
GN
GRID NORTH
1960 G-M ANGLE
8° (140 MILS)
TRUE NORTH
MAGNETIC NORTH
TO CONVERT A
MAGNETIC AZIMUTH
TO GRID AZIMUTH
ADD G-M ANGLE
GRID CONVERGENCE
1°24' (25 MILS)
FOR CENTER OF SHEET
TO CONVERT A
GRID AZIMUTH TO A
MAGNETIC AZIIMUTH
SUBTRACT G-M ANGLE

Figure 6-8. Declination diagrams.

(2) ***Without Notes***. In some cases, there are no declination conversion notes on the margin of the map; it is necessary to convert from one type of declination to another. A magnetic compass gives a magnetic azimuth; but in order to plot this line on a gridded map, the magnetic azimuth value must be changed to grid azimuth. The declination diagram is used for these conversions. A rule to remember when solving such problems is this: **No matter where the azimuth line points, the angle to it is always measured clockwise from the reference direction (base line). With this in mind, the problem is solved by the following steps:**

(a) Draw a vertical or grid-north line (prong). Always align this line with the vertical lines on a map (Figure 6-9).



Figure 6-9. Declination diagram with arbitrary line.

(b) From the base of the grid-north line (prong), draw an arbitrary line (or any azimuth line) at a roughly right angle to north, regardless of the actual value of the azimuth in degrees (Figure 6-9).

(c) Examine the declination diagram on the map and determine the direction of the magnetic north (right-left or east-west) relative to that of the grid-north prong. Draw a magnetic prong from the apex of the grid-north line in the desired direction (Figure 6-9).

(d) Determine the value of the G-M angle. Draw an arc from the grid prong to the magnetic prong and place the value of the G-M angle (Figure 6-9).

(e) Complete the diagram by drawing an arc from each reference line to the arbitrary line. A glance at the completed diagram shows whether the given azimuth or the desired azimuth is greater, and thus whether the known difference between the two must be added or subtracted.

(f) The inclusion of the true-north prong in relationship to the conversion is of little importance.

e. **Applications.** Remember, there are no negative azimuths on the azimuth circle. Since 0 degree is the same as 360 degrees, then 2 degrees is the same as 362 degrees. This is because 2 degrees and 362 degrees are located at the same point on the azimuth circle. The grid azimuth can now be converted into a magnetic azimuth because the grid azimuth is now larger than the G-M angle.

(1) When working with a map having an east G-M angle:

(a) To plot a magnetic azimuth on a map, first change it to a grid azimuth (Figure 6-10).


GN
12°E
MAGNETIC NORTH = 210°
G-M ANGLE EAST = +12°
GRID AZIMUTH = 222°
M210°
?
Arbitrary line or any azimuth

Figure 6-10. Converting to grid azimuth.

(b) To use a magnetic azimuth in the field with a compass, first change the grid azimuth plotted on a map to a magnetic azimuth (Figure 6-11).


GN
10°E
GRID AZIMUTH = 303°
G-M ANGLE = -10°
MAGNETIC AZIMUTH = 293°
M ?
303°
Arbitrary line or any azimuth

Figure 6-11. Converting to magnetic azimuth.

(c) Convert a grid azimuth to a magnetic azimuth when the G-M angle is greater than a
grid azimuth (Figure 6-12).


GN
16°E
GRID AZIMUTH = 2° or 362°
G-M ANGLE EAST = -16°
MAGNETIC AZIMUTH = 346°
M ?
2° OR 362°
Arbitrary line or any azimuth

Figure 6-12. Converting to a magnetic azimuth when the G-M angle is greater.

(2) When working with a map having a west G-M angle:

(a) To plot a magnetic azimuth on a map, first convert it to a grid azimuth (Figure 6-13).


GN
8°W
MAGNETIC AZIMUTH = 65°
G-M ANGLE WEST = -8°
GRID AZIMUTH = 57°
M=65°
?
Arbitrary line or any azimuth

Figure 6-13. Converting to a grid azimuth on a map.

(b) To use a magnetic azimuth in the field with a compass, change the grid azimuth plotted on a map to a magnetic azimuth (Figure 6-14).


GM
14°W
GRID AZIMUTH (MAP) = 93°
G-M ANGLE WEST = +14°
MAGNETIC AZIMUTH = 107°
?
93°
Arbitrary line or any azimuth

Figure 6-14. Converting to a magnetic azimuth on a map.

(c) Convert a magnetic azimuth when the G-M angle is greater than the magnetic azimuth (Figure 6-15).


GN
12°W
MAGNETIC AZIMUTH = 5° or 365°
G-M ANGLE WEST = -12°
GRID AZIMUTH = 353°
M5° OR 365°
?
Arbitrary line or any azimuth

Figure 6-15. Converting to a grid azimuth when the G-M angle is greater.

(3) The G-M angle diagram should be constructed and used each time the conversion of azimuth is required. Such procedure is important when working with a map for the first time. It also may be convenient to construct a G-M angle conversion table on the margin of the map.

NOTE: When converting azimuths, exercise extreme care when adding and subtracting the G-M angle. A simple mistake of 1° could be significant in the field.

6-7. INTERSECTION

Intersection is the location of an unknown point by successively occupying at least two (preferably three) known positions on the ground and then map sighting on the unknown location. It is used to locate distant or inaccessible points or objects such as enemy targets and danger areas. There are two methods of intersection: the map and compass method and the straightedge method (Figures 6-16 and 6-17 on pages 6-14 and 6-15).

a. When using the map and compass method—

(1) Orient the map using the compass.

(2) Locate and mark your position on the map,

(3) Determine the magnetic azimuth to the unknown position using the compass.

(4) Convert the magnetic azimuth to grid azimuth.

(5) Draw a line on the map from your position on this grid azimuth.

(6) Move to a second known point and repeat steps 1, 2, 3, 4, and 5.

(7) The location of the unknown position is where the lines cross on the map. Determine the grid coordinates to the desired accuracy.

b. The straight edge method is used when a compass is not available. When using it—

(1) Orient the map on a flat surface by the terrain association method.

(2) Locate and mark your position on the map.

(3) Lay a straight edge on the map with one end at the user's position (A) as a pivot point; then, rotate the straightedge until the unkown point is sighted along the edge.

(4) Draw a line along the straight edge

(5) Repeat the above steps at position (B) and check for accuracy.


UNKNOWN LOCATION
POSITION A
POSITION B
86
87
88
89
9
GN
5°
Magnetic azimuth from position A 71°+5° E =76°G
Magnetic azimuth from position B 35° +5° E =40°G
Hangar
Lawson Field
Fort Mitchell

Figure 6-16. Intersection, using map and compass.

(6) The intersection of the lines on the map is the location of the unknown point (C). Determine the grid coordinates to the desired accuracy (Figure 6-17).



Figure 6-17. Intersection, using a straightedge.

6-8. RESECTION

Resection is the method of locating one's position on a map by determining the grid azimuth to at least two well-defined locations that can be pinpointed on the map. For greater accuracy, the desired method of resection would be to use three or more well-defined locations.

a. When using the map and compass method (Figure 6-18)—

(1) Orient the map using the compass.

(2) Identify two or three known distant locations on the ground and mark them on the map.

(3) Measure the magnetic azimuth to one of the known positions from your location using a compass.

(4) Convert the magnetic azimuth to a grid azimuth.

(5) Convert the grid azimuth to a back azimuth. Using a protractor, draw a line for the back azimuth on the map from the known position back toward your unknown position.

(6) Repeat 3, 4, and 5 for a second position and a third position, if desired.

(7) The intersection of the lines is your location. Determine the grid coordinates to the desired accuracy.


CONTROL TOWER
KNOWN DISTANT
LOCATION
HILL 408
KNOWN DISTANT
LOCATION
YOUR UNKNOWN LOCATION
137°
198°
GN
3°
Hangar
Control tower
Hangar
INDIANHEAD ROAD
MILITARY
RESERVATION
CHATTAHOOCHEE
GEORGIA
ALABAMA
Power substation
Oswichee Bridge
86

1. From your unknown location to hilltop 408 magnetic azimuth 312° + 5° E = 317° G - 180° = 137° back azimuth
2. From your unknown location to control tower magnetic azimuth 13° + 5° E = 18°G + 180° = 198° back azimuth

Figure 6-18. Resection with map and compass.

a. When using the straightedge method (Figure 6-19)—

(1) Orient the map on a flat surface by the terrain association method.

(2) Locate at least two known distant locations or prominent features on the ground and mark them on the map.

(3) Lay a straightedge on the map using a known position as a pivot point. Rotate the straightedge until the known position on the map is aligned with the known position on the ground.

(4) Draw a line along the straightedge away from the known position on the ground toward your position.

(5) Repeat 3 and 4 using a second known position.

(6) The intersection of the lines on the map is your location. Determine the grid coordinates to the desired accuracy.



Figure 6-19. Resection with straightedge.

6-9. MODIFIED RESECTION

Modified resection is the method of locating one's position on the map when the person is located on a linear feature on the ground, such as a road, canal, or stream (Figure 6-20). Proceed as follows:

a. Orient the map using a compass or by terrain association.

b. Find a distant point that can be identified on the ground and on the map.

c. Determine the magnetic azimuth from your location to the distant known point.

d. Convert the magnetic azimuth to a grid azimuth.

e. Convert the grid azimuth to a back azimuth. Using a protractor, draw a line for the back azimuth on the map from the known position back toward your unknown position.

f. The location of the user is where the line crosses the linear feature. Determine the grid coordinates to the desired accuracy.


Violet Prairie Grange
Violet Prairie Church
87
Mound Prairie
Scatter Cr
GN
7°
86
Church Of God
85
84
01
02
03
04
05
06
07
08
Prairie Creek
YOUR UNKNOWN LOCATION
LINEAR FEATURE

1. Your unknown location is along Prairie Creek.
2. From your unknown location to the Church of God, the magnetic azimuth is 20° + 7° E = 27° G + 180° = 207° back azimuth.

Figure 6-20. Modified resection.

6-10. POLAR COORDINATES

A method of locating or plotting an unknown position from a known point by giving a direction and a distance along that direction line is called polar coordinates. The following elements must be present when using polar coordinates (Figure 6-21).

- Present known location on the map.
- Azimuth (grid or magnetic).
- Distance (in meters).


GN
GRID AZIMUTH
24°
DISTANCE (METERS)
WATER TANK
Known location — WATER TANK
Grid azimuth — 24°
Distance — 3,600 Meters

Figure 6-21. Polar plot.

Using the laser range finder to determine the range enhances your accuracy in determining the unknown position's location.

CHAPTER 7

OVERLAYS

An overlay is a clear sheet of plastic or semi-transparent paper. It is used to display supplemental map and tactical information related to military operations. It is often used as a supplement to orders given in the field. Information is plotted on the overlay at the same scale as on the map, aerial photograph, or other graphic being used. When the overlay is placed over the graphic, the details plotted on the overlay are shown in their true position.

7-1. PURPOSE

Overlays are used to display military operations with enemy and friendly troop dispositions, and as supplements to orders sent to the field. They show detail that will aid in understanding the orders, displays of communication networks, and so forth. They are also used as annexes to reports made in the field because they can clarify matters that are difficult to explain clearly in writing.

7-2. MAP OVERLAY

There are three steps in the making of a map overlay—orienting the overlay material, plotting and symbolizing the detail, and adding the required marginal information (Figure 7-1).



Figure 7-1. Registering the overlay.

a**. Orienting.** Orient the overlay over the place on the map to be annotated. Then, if possible, attach it to the edges of the map with tape. Trace the grid intersections nearest the two opposite corners of the overlay using a straightedge and label each with the proper grid coordinates. These register marks show the receiver of your overlay exactly where it fits on his map; without them, the overlay is difficult to orient. It is imperative that absolute accuracy be maintained in plotting the register marks, as the smallest mistake will throw off the overlay.

b. **Plotting of New Detail.** Use pencils or markers in standard colors that make a lasting mark without cutting the overlay to plot any detail (FM 101-5-1).

(1) Use standard topographic or military symbols where possible. Nonstandard symbols invented by the author must be identified in a legend on the overlay. Depending on the conditions under which the overlay is made, it may be advisable to plot the positions first on the map, then trace them onto the overlay. Since the overlay is to be used as a supplement to orders or reports and the recipient will have an identical map, show only that detail with which the report is directly concerned.

(2) If you have observed any topographic or cultural features that are not shown on the map, such as a new road or a destroyed bridge, plot their positions as accurately as possible on the overlay and mark with the standard topographic symbol.

(3) If difficulty in seeing through the overlay material is encountered while plotting or tracing detail, lift the overlay from time to time to check orientation of information being added in reference to the base.

c. **Recording Marginal Information.** When all required detail has been plotted or traced on the overlay, print information as close to the lower right-hand corner as detail permits (Figure 7-2). This information includes the following data:

(1) ***Title and Objective***. This tells the reader why the overlay was made and may also give the actual location. For example, "Road Reconnaissance" is not as specific as "Route 146 Road Reconnaissance."

(2) ***Time and Date***. Any overlay should contain the latest possible information. An overlay received in time is very valuable to the planning staff and may affect the entire situation; an overlay that has been delayed for any reason may be of little use. Therefore, the exact time the information was obtained aids the receivers in determining its reliability and usefulness.

(3) ***Map Reference***. The sheet name, sheet number, map series number, and scale must be included. If the reader does not have the map used for the overlay, this provides the information necessary to obtain it.

(4) ***Author***. The name, rank, and organization of the author, supplemented with a date and time of preparation of the overlay, tells the reader if there was a time difference between when the information was obtained and when it was reported.

(5) ***Legend***. If it is necessary to invent nonstandard symbols to show the required information, the legend must show what these symbols mean.

(6) ***Security Classification***. This must correspond to the highest classification of either the map or the information placed on the overlay. If the information and map are unclassified, this will be so stated. The locations of the classification notes are shown in Figure 7-2, and the notes will appear in both locations as shown.

(7) ***Additional Information***. Any other information that amplifies the overlay will also be included. Make it as brief as possible.


CLASSIFICATION
BM 325
McKenna Hill
07
84
BM 431
HOURGLASS RD
BM 291
BLACKHAWK
TITLE: LOCATION OF MINEFIELD
DATE AND TIME OF INFORMATION
MAP REFERENCE
SHEET NAME
SHEET NO:
MAP SERIES NO:
SCALE:
PREPARED BY
NAME AND RANK
ORGANIZATION
DATE AND TIME
LEGEND:
ROAD
Sulphur Spring
Craston Hill
04
BM 304
BM
06
BM 414
Grandstand
ROAD
369
Grandstand
man Hill
402
CLASSIFICATION
300

Figure 7-2. Map overlay with marginal information.

7-3. AERIAL PHOTOGRAPH OVERLAY

Overlays of single aerial photographs are constructed and used in the same way as map overlays. The steps followed are essentially the same, with the following exceptions:

a. **Orienting of Overlay.** The photograph normally does not have grid lines to be used as register marks. The borders of the photograph limit the area of the overlay, so the reference marks or linear features are traced in place of grid register marks. Finally, to ensure proper location of the overlay with respect to the photograph, indicate on the overlay the position of the marginal data on the photograph as seen through the overlay.

b. **Marginal Information.** The marginal information shown on photographs varies somewhat from that shown on maps. Overlays of photographs (Figure 7-3, page 7-4) should show the following information:

(1) ***North Arrow***. This may be obtained in two ways—by comparing with a map of the area or by orienting the photograph by inspection. In the latter case, a compass or expedient direction finder must be used to place the direction arrow on the overlay. Use the standard symbol to represent the actual north arrow used—grid, magnetic, or true north.

(2) ***Title and Objective***. This tells the reader why the photo overlay was made and may also give the actual location.

(3) ***Time and Date***. The exact time the information was obtained is shown on a photo overlay just as on a map overlay

(4) ***Photo Reference***. The photo number, mission number, date of flight, and scale appear here, or the information is traced in its actual location on the photograph.

(5) ***Scale***. The scale must be computed since it is not part of the marginal data.

(6) ***Map Reference***. Reference is made to the sheet name, sheet number, series number, and scale of a map of the area, if one is available.

(7) ***Author***. The name, rank, and organization of the author are shown, supplemented with a date and time of preparation of the overlay.

(8) ***Legend***. As with map overlays, this is only necessary when nonstandard symbols are used.

(9) ***Security Classification***. This must correspond to the highest classification of either the photograph or the information placed on the overlay. If the information and photograph are unclassified, this will be so stated. The locations of the classification notes are shown in Figure 7-3, and the notes will appear in both locations.

(10) ***Additional Information***. Any other information that amplifies the overlay will also be included. Make it as brief as possible.


CLASSIFICATION
A
26
N
BOX SPRINGS ROAD
RED DIAMOND ROAD
MARGINAL DATA
CLASSIFICATION
TITLE: LOCATION OF CP
DATE & TIME OF INFORMATION
PHOTO REFERANCE:
PHOTO NO:
MISSION NO:
DATE:
SCALE:
MAP REFERENCE:
SHEET NAME:
SHEET NO:
MAP SERIES NO:
SCALE:
PREPARED BY:
NAME & RANK
ORGANIZATION
DATE & TIME
LEGEND
CLASSIFICATION

Figure 7-3. Photographic overlay with marginal information.

CHAPTER 8

AERIAL PHOTOGRAPHS

An aerial photograph is any photograph taken from an airborne vehicle (aircraft, drones, balloons, satellites, and so forth). The aerial photograph has many uses in military operations; however, for the purpose of this manual, it will be considered primarily as a map supplement or map substitute.

8-1. COMPARISON WITH MAPS

A topographic map may be obsolete because it was compiled many years ago. A recent aerial photograph shows any changes that have taken place since the map was made. For this reason, maps and aerial photographs complement each other. More information can be gained by using the two together than by using either alone.

a. **Advantages.** An aerial photograph has the following advantages over a map:

(1) It provides a current pictorial view of the ground that no map can equal.

(2) It is more readily obtained. The photograph may be in the hands of the user within a few hours after it is taken; a map may take months to prepare.

(3) It may be made for places that are inaccessible to ground soldiers.

(4) It shows military features that do not appear on maps.

(5) It can provide a day-to-day comparison of selected areas, permitting evaluations to be made of enemy activity.

(6) It provides a permanent and objective record of the day-to-day changes with the area.

b. **Disadvantages.** The aerial photograph has the following disadvantages as compared to a map:

(1) Ground features are difficult to identify or interpret without symbols and are often obscured by other ground detail as, for example, buildings in wooded areas.

(2) Position location and scale are only approximate.

(3) Detailed variations in the terrain features are not readily apparent without overlapping photography and a stereoscopic viewing instrument.

(4) Because of a lack of contrasting colors and tone, a photograph is difficult to use in poor light.

(5) It lacks marginal data.

(6) It requires more training to interpret than a map.

8-2. TYPES

Aerial photography most commonly used by military personnel may be divided into two major types, the vertical and the oblique. Each type depends upon the attitude of the camera with respect to the earth's surface when the photograph is taken.

a. **Vertical.** A vertical photograph is taken with the camera pointed as straight down as possible (Figures 8-1 and 8-2 on page 8-2). Allowable tolerance is usually + 3° from the perpendicular (plumb) line to the camera axis. The result is coincident with the camera axis. A vertical photograph has the following characteristics:

(1) The lens axis is perpendicular to the surface of the earth.

(2) It covers a relatively small area.

(3) The shape of the ground area covered on a single vertical photo closely approximates a square or rectangle.

(4) Being a view from above, it gives an unfamiliar view of the ground.

(5) Distance and directions may approach the accuracy of maps if taken over flat terrain.

(6) Relief is not readily apparent.



Figure 8-1. Relationship of the vertical aerial photograph with the ground.



Figure 8-2. Vertical photograph.

a. **Low Oblique.** This is a photograph taken with the camera inclined about 30° from the vertical (Figure 8-3, and Figure 8-4 on page 8-4). It is used to study an area before an attack, to substitute for a reconnaissance, to substitute for a map, or to supplement a map. A low oblique has the following characteristics:

(1) It covers a relatively small area.

(2) The ground area covered is a trapezoid, although the photo is square or rectangular.

(3) The objects have a more familiar view, comparable to viewing from the top of a high hill or tall building.

(4) No scale is applicable to the entire photograph, and distance cannot be measured. Parallel lines on the ground are not parallel on this photograph; therefore, direction (azimuth) cannot be measured.

(5) Relief is discernible but distorted.

(6) It does not show the horizon.



Figure 8-3. Relationship of low oblique photograph to the ground.



Figure 8-4. Low oblique photograph.

c. **High Oblique.** The high oblique is a photograph taken with the camera inclined about 60° from the vertical (Figures 8-5 and 8-6). It has a limited military application; it is used primarily in the making of aeronautical charts. However, it may be the only photography available. A high oblique has the following characteristics:

(1) It covers a very large area (not all usable).

(2) The ground area covered is a trapezoid, but the photograph is square or rectangular.

(3) The view varies from the very familiar to unfamiliar, depending on the height at which the photograph is taken.

(4) Distances and directions are not measured on this photograph for the same reasons that they are not measured on the low oblique.

(5) Relief may be quite discernible but distorted as in any oblique view. The relief is not apparent in a high altitude, high oblique.

(6) The horizon is always visible.


FILM
CAMERA LENS
HORIZON
CAMERA AXIS
PLUMB
60°

Figure 8-5. Relationship of high oblique photograph to the ground.



Figure 8-6. High oblique photograph.

d. **Trimetrogon.** This is an assemblage of three photographs taken at the same time, one vertical and two high obliques, in a direction at right angle to the line of flight. The obliques, taken at an angle of 60° from the vertical, sidelap the vertical photography, producing composites from horizon to horizon (Figure 8-7).



Figure 8-7. Relationship of cameras to ground for trimetrogon photography (three cameras).

e. **Multiple Lens Photography.** These are composite photographs taken with one camera having two or more lenses, or by two or more cameras. The photographs are combinations of two, four, or eight obliques around a vertical. The obliques are rectified to permit assembly as verticals on a common plane.

f. **Convergent Photography.** These are done with a single twin-lens, wide-angle camera, or with two single-lens, wide-angle cameras coupled rigidly in the same mount so that each camera axis converges when intentionally tilted a prescribed amount (usually 15 or 20°) from the vertical. Again, the cameras are exposed at the same time. For precision mapping, the optical axes of the cameras are parallel to the line of flight, and for reconnaissance photography, the camera axes are at high angles to the line of flight.

g. **Panoramic.** The development and increasing use of panoramic photography in aerial reconnaissance has resulted from the need to cover in greater detail more and more areas of the world.

(1) To cover the large areas involved, and to resolve the desired ground detail, present-day reconnaissance systems must operate at extremely high-resolution levels. Unfortunately, high-resolution levels and wide-angular coverage are basically contradicting requirements.

(2) A panoramic camera is a scanning type of camera that sweeps the terrain of interest from side to side across the direction of flight. This permits the panoramic camera to record a much wider area of ground than either frame or strip cameras. As in the case of the frame cameras, continuous cover is obtained by properly spaced exposures timed to give sufficient overlap between frames. Panoramic cameras are most advantageous for applications requiring the resolution of small ground detail from high altitudes.

8-3. TYPES OF FILM

Types of film generally used in aerial photography include panchromatic, infrared, and color. Camouflage detection film is also available.

a. **Panchromatic.** This is the same type of film that is used in the average hand-held small camera. It records the amount of light reflected from objects in tones of gray running from white to black. Most aerial photography is taken with panchromatic film.

b. **Infrared.** This is a black-and-white film that is sensitive to infrared waves. It can be used to detect artificial camouflage materials and to take photographs at night if there is a source of infrared radiation.

c. **Color.** This film is the same as that used in the average hand-held camera. It is limited in its use because of the time required to process it and its need for clear, sunny weather.

d. **Camouflage Detection.** This film is a special type that records natural vegetation in a reddish color. When artificial camouflage materials are photographed, they appear bluish or purplish. The name of this film indicates its primary use.

8-4. NUMBERING AND TITLING INFORMATION

Each aerial photograph contains in its margin important information for the photo user. The arrangement, type, and amount of this information is standardized; however, the rapid development of cameras, film, and aeronautical technology since World War II has caused numerous changes in the numbering and titling of aerial photographs. As a result, the photo user may find that the marginal information on older photographs varies somewhat from the standard current practice. With certain camera systems, some of the data are automatically recorded on each exposure, while other systems require that all titling data be added to the film after processing.

a. Standard titling data for aerial photography prepared for the use of the Department of Defense are as follows. For reconnaissance and charting photography, items 2 through 14 and item 19 are lettered on the beginning and end of each roll of film. Items 1 through 9 and item 19 are lettered on each exposure. For surveying and mapping photography, items 2 through 19 are lettered on the beginning and end of each roll of film, and items 1, 2, 3, 5, 6, 7, 8, 9, 13, and 19 are lettered on each exposure.

(1) Negative number.
(2) Camera position.
(3) Taking unit.
(4) Service.
(5) Sortie/mission number.
(6) Date (followed by a double hyphen [=]).
(7) Time group and zone letter (GMT).
(8) Focal length.
(9) Altitude.
(10) Kind of photography or imagery.
(11) Geographic coordinates.
(12) Descriptive title.
(13) Project number and or name.
(14) Camera type and serial number.

(15) Cone serial number (if any).
(16) Lens type and serial number.
(17) Magazine type and serial number.
(18) Type of photographic filter used.
(19) Security classification.

b. Automatically recorded data may differ somewhat in arrangement from the sequence listed above, but the same information is available to the photo user. A detailed explanation of the titling items and the codes used to indicate them is found in TM 5-243.

8-5. SCALE DETERMINATION

Before a photograph can be used as a map supplement or substitute, it is necessary to know its scale. On a map, the scale is printed as a representative fraction that expresses the ratio of map distance to ground distance, For example: $RF = \frac{MD}{GD}$

On a photograph, the scale is also expressed as a ratio, but is the ratio of the photo distance (***PD***) to ground distance**.** For example: $RF = \frac{PD}{GD}$

The approximate scale or average scale (***RF***) of a vertical aerial photograph is determined by either of two methods; the comparison method or the focal length-flight altitude method.

a. **Comparison Method.** The scale of a vertical aerial photograph is determined by comparing the measured distance between two points on the photograph with the measured ground distance between the same two points.

$$\text{SCALE (RF} = \frac{\text{Photo Distance}}{\text{Ground Distance}}$$

The ground distance is determined by actual measurement on the ground or by the use of the scale on a map of the same area. The points selected on the photograph must be identifiable on the ground or map of the same area and should be spaced in such a manner that a line connecting them will pass through or nearly through the center of the photograph (Figure 8-8).



Example:
Photo distance = 8 centimeters
Ground distance = 2 kilometers

$$\frac{8cm}{2km \times 100{,}000\ (cm\ in\ 1km)} = \frac{8}{200{,}00}\ or\ \frac{8/8}{8/200{,}000} = \frac{1}{25{,}000}\ or\ RF = 1{:}25{,}000$$

Figure 8-8. Selection of points for scale determination.

b. **Focal Length-Flight Altitude Method.** When the marginal information of a photograph includes the focal length and the flight altitude, the scale of the photo is determined using the following formula (Figure 8-9).

$$SCALE\ (RF) = \frac{f\ (focal\ leingth)}{H\ (flight\ altitude) - h\ (average\ ground\ elevation)}$$

Example:
f = 6 inches or 15.2 centimeters
H =10,000 feet or 3,048 meters
f =850 feet or 259.08 meters

With metric measures:

$$\frac{15.2}{(3{,}048 - 259.08) \times 100} = \frac{15.2}{278{,}900} = \frac{1}{18{,}300}\ (approximately)$$

or 1:18,300

With English measurements:

$$\frac{0.5}{10{,}000\ feet - 850\ feet} = \frac{0.5}{9150} = \frac{1}{18{,}300}$$

or 1:18,300


FILM
LENS
FOCAL LENGTH 6 inches
FLIGHT ALTITUDE 10,000 FEET
AVERAGE TERRAIN ELEVATION - 850 FT
GROUND LEVEL
SEA LEVEL

Figure 8-9. Computation of scale from terrain level.

When the ground elevation is at sea level, H becomes zero, and the formula is as shown in Figure 8-10.



Figure 8-10. Basic computation of scale from sea level.

8-6. INDEXING

When aerial photos are taken of an area, it is convenient to have a record of the extent of coverage of each photo. A map on which the area covered by each photo is outlined and numbered or indexed to correspond to the photo is called an index map. There are two methods of preparing index maps.

a. The four-corner method (Figures 8-11 and 8-12) requires location on the map of the exact point corresponding to each corner of the photo. If a recognizable object such as a house or road junction can be found exactly at one of the corners, this point may be used on the map as the corner of the photo. If recognizable objects cannot be found at the corners, then the edges of the photo should be outlined on the map by lining up two or more identifiable objects along each edge; the points where the edges intersect should be the exact corners of the photo. If the photo is not a perfect vertical, the area outlined on the map will not be a perfect square or rectangle. After the four sides are drawn on the map, the number of the photograph is written in the enclosed area for identification. This number should be placed in the same corner as it is on the photo.


POINTS SELECTED

Figure 8-11. Four-corner method (selection of points).


83
82
BENNING MILITARY RESERVATI
POINTS SELECTED

Figure 8-12. Plotting, using the four-corner method.

b. The template method is used when a large number of photos are to be indexed, and the exact area covered by each is not as important as approximate area and location. In this case, a template (cardboard pattern or guide) is cut to fit the average area the photos cover on the index map. It is used to outline the individual area covered by each photo. To construct a template, find the average map dimensions covered by the photos to be indexed as follows. Multiply the average length of the photos by the denominator of the average scale of the photos; multiply this by the scale of the map. Do the same for the width of the photos. This gives the average length and width of the area each photo covers on the map--or the size to which the template should be cut (Figure 8-13).


TEMPLATE
8.2 cm
22.8 cm
22.8 cm
Example:
Size of Photograph = 8.2CM
Scale of Photo = 1:18,000
Scale of Map = 1:50,000
LENGTH = 22.8 X 18,000 X 1/50,000 = 41/5 = 8.2 cm
WIDTH = 22.8 X 18,000 X 1/50,000 = 41/5 = 8.2 cm

Figure 8-13. Constructing a template.

c. To index the map, select the general area covered by the first photo and orient the photo to the map. Place the template over the area on the map and adjust it until it covers the area as completely and accurately as possible. Draw lines around the edges of the template. Remove the rectangle and proceed to the next photo (Figure 8-14).


01
02
03
04
Terrace
MUSCOGEE
CHATTAHOO
FORT
UPATOI
94
96
FORT BENNING
Davis Hill
Smyth Hill
Eckert Hill
Davidson Hill

Figure 8-14. Indexing with a template.

d. After all photos have been plotted, write on the map sufficient information to identify the mission or sortie. If more than one sortie is plotted on one map or overlay, use a different color for each sortie.

e. In most cases, when a unit orders aerial photography, an index is included to give the basic information. Instead of being annotated on a map of the area, it appears on an overlay and is keyed to a map.

8-7. ORIENTING OF PHOTOGRAPH

Orienting the photograph is important because it is of very little value as a map supplement or substitute if its location and direction are not known by the user.

a. If a map of the same area as the photograph is available, the photograph is oriented to the map by comparing features common to both and then transferring a direction line from the map to the photograph.

b. If no map is available, the shadows on a photograph may be used to get an approximate true-north line. This method is not recommended in the torrid zone (Figure 8-15).



Example:
This photograph was taken on 29 December 1985 at 14:15 in the afternoon. The long shadows of the towers are to the right of north.

By measuring back 35° with a protractor, an approximate true-north line will be found.

Figure 8-15. Using shadows on a photograph to find north.

(1) ***North Temperate Zone***. The sun moves from the east in the morning through south at noon to west in the afternoon. Conversely, shadow fall varies from west through north to east. Before noon, therefore, north is to the right of the direction of shadow fall; at noon, north is the direction of shadow fall; and after noon, north is to the left of shadow fall. On an

average, the amount of variation in shadow fall per hour is 15 degrees. From marginal information, determine the number of hours from noon that the photo was taken and multiply that number by 15°. With a protractor, measure an angle of that amount in the proper direction (right to left) from a clear, distinct shadow, and north is obtained. For photographs taken within three hours of noon, a reasonable accurate north direction can be obtained. Beyond these limits, the 15° must be corrected, depending on time of year and latitude.

(2) ***South Temperate Zone***. The sun moves from east through north at noon to west. Shadows then vary from west through south to east. Before noon, south is to the left of shadow fall; at noon, south is shadow fall; and after noon, south is to the right of shadow fall. Proceed as in (1) above to determine the direction of south.

c. On a photograph that can be oriented to the surrounding ground features by inspection, a magnetic-north line can be established using a compass.

(1) Orient the photograph by inspection.

(2) Open the compass and place it on the photograph.

(3) Without moving the photograph, rotate the compass until the north arrow is under the stationary black line.

(4) Draw a line along the straight edge of the compass. This is a magnetic-north line.

8-8. POINT DESIGNATION GRID

Since aerial photographs are seldom exactly the same scale as a map of the same area, it is not feasible to print military grids on them. A special grid is used for the designation of points on photographs (Figure 8-16). This grid, known as the point designation grid, has no relation to the scale of the photo, to any direction, or to the grid used on any other photograph or map. It has only one purpose, to designate points on photographs.


12-30-85 1:19200 108501 R1 3-13
NOTE: Marginal information in normal reading position.
53
52
51
50
49
48
47
47
48
49
50
51
52
53

Figure 8-16. Point designation grid.

a. The point designation grid is rarely printed on photographs; therefore, it becomes the responsibility of each user to construct the grid on the photograph. All users must construct the grid in exactly the same way. Before the grid can be constructed or used, the photograph must be held so that the marginal information, regardless of where it is located, is in the normal reading position (Figure 8-17, step 1).

(1) Draw lines across the photograph joining opposite reference marks at the center of each photograph (fiducial marks). If there are no fiducial marks, the center of each side of the photograph is assumed to be the location of the marks (Figure 8-17, step 2).

(2) Space grid lines, starting with the center line, 4 centimeters (1.575 inches) apart (a distance equal to 1,000 meters at a scale of 1:25,000). The 1:25,000 map coordinate scale can be used for this dimension and to accurately designate points on the photograph, but this does not mean that distance can be scaled from the photograph. Extend the grid past the margins of the photograph so that a horizontal and vertical grid line fall outside the picture area (Figure 8-17, step 3).

(3) Number each center line "50" and give numerical values to the remaining horizontal and vertical lines so that they increase to the right and up (Figure 8-17, step 4).



Figure 8-17. Constructing a point designation grid.

b. The point designation grid is used, once the photograph is oriented, in the same manner as the grid on a map (Figure 8-18), **read right and up**. The coordinate scale used with the UTM grid on maps at the scale of 1:25,000 may be used to subdivide the grid square in the same manner as on a map. However, because the same point designation grid is used on all photographs, the coordinates of a point on the photograph must be prefixed by the identifying marginal information of the photograph.


FOURTH: Estimate tenths between line and points
4
THIRD: Read number labeling this line
51
SECOND: Estimate tenths between line and point
6
FIRST: Read number labeling this line
50
REFERENCE: MARGINAL INFORMATION PLUS 506514
12-30-85 1:19200
MARGINAL INFORMATION
506514
13
53
52
51
50
49
48
47
47
48
49
50
51
52
53

Figure 8-18. Reading point designation grid coordinates.

c. A grid coordinate using the point designation grid (Figure 8-19) consists of three parts:

(1) The letters "PDG" to indicate an aerial photograph rather than a map grid coordinate.

(2) The mission and photo negative number to identify which photograph is being used.

(3) The six numerical digits to locate the actual point on the photograph.



Figure 8-19. Locating the grid coordinate on a point designation grid.

8-9. IDENTIFICATION OF PHOTOGRAPH FEATURES

The identification of features on a photograph is not difficult if the following facts are remembered. The view that is presented by the aerial photograph is from above and, as a result, objects do not look familiar. Objects that are greatly reduced in size appear distorted. Most aerial photography is black and white, and all colors appear on the photograph in shades of gray. Generally speaking, the darker the natural color, the darker it will appear on the photograph.

a. The identification of features on aerial photographs depends upon a careful application of five factors of recognition. No one factor will give a positive identification; it requires the use of all five.

(1) ***Size***. The size of unknown objects on a photograph, as determined from the scale of the photograph or a comparison with known objects of known size, gives a clue to their identity. For example, in a built-up area the smaller buildings are usually dwellings, and the larger buildings are commercial or community buildings.

(2) ***Shape (Pattern)***. Many features possess characteristic shapes that readily identify the features. Man-made features appear as straight or smooth curved lines, while natural features usually appear to be irregular. Some of the most prominent man-made features are highways, railroads, bridges, canals, and buildings. Compare the regular shapes of these to the irregular shapes of such natural features as streams and timber lines.

(3*)* ***Shadows***. Shadows are very helpful in identifying features since they show the familiar side view of the object. Some excellent examples are the shadows of water towers or smoke stacks. As viewed directly from above, only a round circle or dot is seen, whereas the shadow shows the profile and helps to identify the object. Relative lengths of shadows also usually give a good indication of relative heights of objects.

(4) ***Shade (Tone or Texture)***. Of the many different types of photographic film in use today, the film used for most aerial photography, except for special purposes, is

panchromatic film. Panchromatic film is sensitive to all the colors of the spectrum; it registers them as shades of gray, ranging from white to black. This lighter or darker shade of features on aerial photographs is known as the tone. The tone is also dependent on the texture of the features; a paved highway has a smooth texture and produces an even tone on the photograph, while a recently plowed field or a marsh has a rough, choppy texture and results in a rough or grainy tone. It is also important to remember that similar features may have different tones on different photographs, depending on the reflection of sunlight. For example, a river or body of water appears light if it is reflecting sunlight directly toward the camera, but appears dark otherwise. Its texture may be smooth or rough, depending on the surface of the water itself. As long as the variables are kept in mind, tone and texture may be used to great advantage.

(5) ***Surrounding Objects***. Quite often an object not easily recognized by itself may be identified by its relative position to surrounding objects. Large buildings located beside railroads or railroad sidings are usually factories or warehouses. Identify schools by the baseball or football fields. It would be hard to tell the difference between a water tower next to a railroad station and a silo next to a barn, unless the surrounding objects such as the railroad tracks or cultivated fields were considered.

b. Before a vertical photograph can be studied or used for identification of features, it must be oriented. This orienting is different from the orienting required for the construction or use of the point designation grid. Orienting for study consists of rotating the photograph so that the shadows on the photograph point toward yourself. You then face a source of light. This places the source of light, an object, and its shadow in a natural relationship. Failure to orient a photograph properly may cause the height or depth of an object to appear reversed. For example, a mine or quarry may appear to be a hill instead of a depression.

8-10. STEREOVISION

One of the limitations of the vertical aerial photograph is the lack of apparent relief. Stereoscopic vision (or as it is more commonly known, stereovision or depth perception) is the ability to see three-dimensionally or to see length, width, and depth (distance) at the same time. This requires two views of a single object from two slightly different positions. Most people have the ability to see three-dimensionally. Whenever an object is viewed, it is seen twice--once with the left eye and once with the right eye. The fusion or blending together of these two images in the brain permits the judgment of depth or distance.

a. In taking aerial photographs, it is rare for only a single picture to be taken. Generally, the aircraft flies over the area to be photographed taking a series of pictures, each of which overlaps the photograph preceding it and the photograph following it so that an unbroken coverage of the area is obtained (Figure 8-20). The amount of overlap is usually 56 percent, which means that 56 percent of the ground detail appearing on one photo also appears on the next photograph. When a single flight does not give the necessary coverage of an area, additional flights must be made. These additional flights are parallel to the first and must have an overlap between them. This overlap between flights is known as side lap and usually is between 15 and 20 percent (Figure 8-21, page 8-20).



Figure 8-20. Photographic overlap.



Figure 8-21. Side lap.

b. The requirement for stereovision can be satisfied by overlapping photographs if one eye sees the object on one photograph and the other eye sees the same object on another photograph. While this can be done after practice with the eyes alone, it is much easier if an optical aid is used. These optical aids are known as stereoscopes. There are many types of stereoscopes, but only the two most commonly used are discussed in this manual.

(1) ***Pocket Stereoscope***. The pocket stereoscope (Figure 8-22), sometimes known as a lens stereoscope, consists of two magnifying lenses mounted in a metal frame. Because of its simplicity and ease of carrying, it is the type used most frequently by military personnel.



Figure 8-22. Pocket stereoscope.

(2) ***Mirror Stereoscope***. The mirror stereoscope (Figure 8-23) is larger, heavier, and more subject to damage than the pocket stereoscope. It consists of four mirrors mounted in a metal frame.



Figure 8-23. Mirror stereoscope.

c. A method to orient a pair of aerial photographs for best three-dimensional viewing is outlined below:

(1) Arrange the selected pair of photos in such a way that the shadows on them generally appear to fall toward the viewer. It is also desirable that the light source enters the side away from the observer during the study of the photographs (Figure 8-24, page 8-22).

(2) Place the pair of photographs on a flat surface so that the detail on one photograph is directly over the same detail on the other photograph (Figure 8-24, page 8-22).

(3) Place the stereoscope over the photographs so that the left lens is over the left photograph and the right lens is over the right photograph (Figure 8-24).



Figure 8-24. Placement of stereoscope over stereopair.

(4) Separate the photographs along the line of flight until a piece of detail appearing in the overlap area of the left photograph is directly under the left lens and the same piece of detail on the right photo is directly under the right lens.

(5) With the photograph and stereoscope in this position, a three-dimensional image should be seen. A few minor adjustments may be necessary, such as adjusting the aerial photographs of the stereoscope to obtain the correct position for your eyes. The hills appear to rise and the valleys sink so that there is the impression of being in an aircraft looking down at the ground.

(6) The identification of features on photographs is much easier and more accurate with this three-dimensional view. The same five factors of recognition (size, shape, shadow, tone, and surrounding objects) must still be applied; but now, with the addition of relief, a more natural view is seen.

PART TWO
LAND NAVIGATION

CHAPTER 9
NAVIGATION EQUIPMENT AND METHODS

Compasses are the primary navigation tools to use when moving in an outdoor world where there is no other way to find directions. Soldiers should be thoroughly familiar with the compass and its uses. Part One of this manual discussed the techniques of map reading. To complement these techniques, a mastery of field movement techniques is essential. This chapter describes the lensatic compass and its uses, and some of the field expedient methods used to find directions when compasses are not available.

9-1. TYPES OF COMPASSES

The **lensatic compass** is the most common and simplest instrument for measuring direction. It is discussed in detail in paragraph 9-2. The **artillery M2 compass** is a special-purpose instrument designed for accuracy; it will be discussed in Appendix G. The **wrist/pocket compass** is a small magnetic compass that can be attached to a wristwatch band. It contains a north-seeking arrow and a dial in degrees. A **protractor** can be used to determine azimuths when a compass is not available. However, it should be noted that when using the protractor on a map, only grid azimuths are obtained.

9-2. LENSATIC COMPASS

The lensatic compass (Figure 9-1) consists of three major parts: the cover, the base, and the lens.


LUMINOUS MAGNETIC ARROW
SHORT LUMINOUS LINE
FIXED INDEX LINE
LUMINOUS SIGHTING DOTS
SIGHTING SLOT
LENS
LENS OR REAR SIGHT
THUMB LOOP
FLOATING DIAL
BEZEL RING
SIGHTING WIRE
GRADUATED STRAIGHT EDGE
COVER
BASE

Figure 9-1. Lensatic compass.

a. **Cover.** The compass cover protects the floating dial. It contains the sighting wire (front sight) and two luminous sighting slots or dots used for night navigation.

b. **Base.** The body of the compass contains the following movable parts:

(1) The floating dial is mounted on a pivot so it can rotate freely when the compass is held level. Printed on the dial in luminous figures are an arrow and the letters E and W. The arrow always points to magnetic north and the letters fall at east (E) 90° and west (W) 270° on the dial. There are two scales; the outer scale denotes mils and the inner scale (normally in red) denotes degrees.

(2) Encasing the floating dial is a glass containing a fixed black index line.

(3) The bezel ring is a ratchet device that clicks when turned. It contains 120 clicks when rotated fully; each click is equal to 3°. A short luminous line that is used in conjunction with the north-seeking arrow during navigation is contained in the glass face of the bezel ring.

(4) The thumb loop is attached to the base of the compass.

c. **Lens.** The lens is used to read the dial, and it contains the rear-sight slot used in conjunction with the front for sighting on objects. The rear sight also serves as a lock and clamps the dial when closed for its protection. The rear sight must be opened more than 45° to allow the dial to float freely.

NOTE: When opened, the straightedge on the left side of the compass has a coordinate scale; the scale is 1:50,000 in newer compasses.

WARNING

Some older compasses will have a 1:25,000 scale. This scale can be used with a 1:50,000-scale map, but the values read must be halved. Check the scale.

9-3. COMPASS HANDLING

Compasses are delicate instruments and should be cared for accordingly.

a. **Inspection.** A detailed inspection is required when first obtaining and using a compass. One of the most important parts to check is the floating dial, which contains the magnetic needle. The user must also make sure the sighting wire is straight, the glass and crystal parts are not broken, the numbers on the dial are readable, and most important, that the dial does not stick.

b. **Effects of Metal and Electricity.** Metal objects and electrical sources can affect the performance of a compass. However, nonmagnetic metals and alloys do not affect compass readings. The following separation distances are suggested to ensure proper functioning of a compass:

High-tension power lines	55 meters.
Field gun, truck, or tank	18 meters.
Telegraph or telephone wires and barbed wire	10 meters.
Machine gun	2 meters.
Steel helmet or rifle	1/2 meter.

c. **Accuracy.** A compass in good working condition is very accurate. However, a compass has to be checked periodically on a known line of direction, such as a surveyed azimuth using a declination station. Compasses with more than 3° + variation should not be used.

d. **Protection.** If traveling with the compass unfolded, make sure the rear sight is fully folded down onto the bezel ring. This will lock the floating dial and prevent vibration, as well as protect the crystal and rear sight from damage.

9-4. USING A COMPASS

Magnetic azimuths are determined with the use of magnetic instruments, such as lensatic and M2 compasses. The techniques employed when using the lensatic compass are as follows:

a. **Using the Centerhold Technique.** First, open the compass to its fullest so that the cover forms a straightedge with the base. Move the lens (rear sight) to the rearmost position, allowing the dial to float freely. Next, place your thumb through the thumb loop, form a steady base with your third and fourth fingers, and extend your index finger along the side of the compass. Place the thumb of the other hand between the lens (rear sight) and the bezel ring; extend the index finger along the remaining side of the compass, and the remaining fingers around the fingers of the other hand. Pull your elbows firmly into your sides; this will place the compass between your chin and your belt. To measure an azimuth, simply turn your entire body toward the object, pointing the compass cover directly at the object. Once you are pointing at the object, look down and read the azimuth from beneath the fixed black index line (Figure 9-2). This preferred method offers the following advantages over the sighting technique:

(1) It is faster and easier to use.

(2) It can be used under all conditions of visibility.

(3) It can be used when navigating over any type of terrain.

(4) It can be used without putting down the rifle; however, the rifle must be slung well back over either shoulder.

(5) It can be used without removing eyeglasses.



Figure 9-2. Centerhold technique.

b. **Using the Compass-to-Cheek Technique.** Fold the cover of the compass containing the sighting wire to a vertical position; then fold the rear sight slightly forward. Look through the rear-sight slot and align the front-sight hairline with the desired object in the distance. Then glance down at the dial through the eye lens to read the azimuth (Figure 9-3).

NOTE: The compass-to-cheek technique is used almost exclusively for sighting, and it is the best technique for this purpose.



Figure 9-3. Compass-to-cheek technique.

c. **Presetting a Compass and Following an Azimuth.** Although different models of the lensatic compass vary somewhat in the details of their use, the principles are the same.

(1) During daylight hours or with a light source:

(a) Hold the compass level in the palm of the hand.

(b) Rotate it until the desired azimuth falls under the fixed black index line (for example, 320°), maintaining the azimuth as prescribed (Figure 9-4).

(c) Turn the bezel ring until the luminous line is aligned with the north-seeking arrow. Once the alignment is obtained, the compass is preset.

(d) To follow an azimuth, assume the centerhold technique and turn your body until the north-seeking arrow is aligned with the luminous line. Then proceed forward in the direction of the front cover's sighting wire, which is aligned with the fixed black index line that contains the desired azimuth.



Figure 9-4. Compass preset at 320 degrees.

(2) During limited visibility, an azimuth may be set on the compass by the click method. Remember that the bezel ring contains 3° intervals (clicks).

(a) Rotate the bezel ring until the luminous line is over the fixed black index line.

(b) Find the desired azimuth and divide it by three. The result is the number of clicks that you have to rotate the bezel ring.

(c) Count the desired number of clicks. If the desired azimuth is smaller than 180°, the number of clicks on the bezel ring should be counted in a counterclockwise direction. For example, the desired azimuth is 51°. Desired azimuth is 51°÷ 3 = 17 clicks counterclockwise. If the desired azimuth is larger than 180°, subtract the number of degrees from 360° and divide by 3 to obtain the number of clicks. Count them in a clockwise direction. For example, the desired azimuth is 330°; 360°-330° = 30 ÷3 = 10 clicks clockwise.

(d) With the compass preset as described above, assume a centerhold technique and rotate your body until the north-seeking arrow is aligned with the luminous line on the bezel. Then proceed forward in the direction of the front cover's luminous dots, which are aligned with the fixed black index line containing the azimuth.

(e) When the compass is to be used in darkness, an initial azimuth should be set while light is still available, if possible. With the initial azimuth as a base, any other azimuth that is a multiple of three can be established through the use of the clicking feature of the bezel ring.

NOTE: Sometimes the desired azimuth is not exactly divisible by three, causing an option of rounding up or rounding down. If the azimuth is rounded up, this causes an increase in the value of the azimuth, and the object is to be found on the left. If the azimuth is rounded down, this causes a decrease in the value of the azimuth, and the object is to be found on the right.

d. **Bypassing an Obstacle**. To bypass enemy positions or obstacles and still stay oriented, detour around the obstacle by moving at right angles for specified distances.

(1) For example, while moving on an azimuth of 90° change your azimuth to 180° and travel for 100 meters. Change your azimuth to 90°and travel for 150 meters. Change your azimuth to 360°and travel for 100 meters. Then, change your azimuth to 90°and you are back on your original azimuth line (Figure 9-5).



Figure 9-5. Bypassing an obstacle.

(2) Bypassing an unexpected obstacle at night is a fairly simple matter. To make a 90° turn to the right, hold the compass in the centerhold technique; turn until the center of the luminous letter E is under the luminous line (*do not* move the bezel ring). To make a 90° turn to the left, turn until the center of the luminous letter W is under the luminous line. This does not require changing the compass setting (bezel ring), and it ensures accurate 90° turns.

e. **Offset.** A deliberate offset is a planned magnetic deviation to the right or left of an azimuth to an objective. Use it when the objective is located along or in the vicinity of a linear feature such as a road or stream. Because of errors in the compass or in map reading, the linear feature may be reached without knowing whether the objective lies to the right or left. A deliberate offset by a known number of degrees in a known direction compensates for possible errors and ensures that upon reaching the linear feature, the user knows whether to go right or left to reach the objective. Ten degrees is an adequate offset for most tactical uses. Each degree offset moves the course about 18 meters to the right or left for each 1,000 meters traveled. For example, in Figure 9-6, the number of degrees offset is 10. If the distance traveled to "x" in 1,000 meters, then "x" is located about 180 meters to the right of the objective.


STRAIGHT LINE
ROUTE 90°
OBJ
10°
100 METERS
ROUTE TO BE
USED 100°
(FOR 1,000 METERS)
W
E

Figure 9-6. Deliberate offset to the objective.

9-5. FIELD-EXPEDIENT METHODS

When a compass is not available, different techniques should be used to determine the four cardinal directions.

a. **Shadow-Tip Method.**

(1) This simple and accurate method of finding direction by the sun consists of four basic steps (Figure 9-7).


N
E
W
S
SECOND
SHADOW TIP
MARK
FIRST
SHADOW TIP
MARK
APPROXIMATE
EAST-WEST
LINE
N
1100
1200
1300
1400
1500
1600
1700
1800
1000
0900
0800
0700
0600
W
E
S

Figure 9-7. Determining directions and time by shadow.

Step 1. Place a stick or branch into the ground at a level spot where a distinctive shadow will be cast. Mark the shadow tip with a stone, twig, or other means. This first shadow mark is always the west direction.

Step 2. Wait 10 to 15 minutes until the shadow tip moves a few inches. Mark the new position of the shadow tip in the same way as the first.

Step 3. Draw a straight line through the two marks to obtain an approximate east-west line.

Step 4. Standing with the first mark (west) to your left, the other directions are simple; north is to the front, east is to the right, and south is behind you.

(2) A line drawn perpendicular to the east-west line at any point is the approximate north-south line. If you are uncertain which direction is east and which is west, observe this simple rule--the first shadow-tip mark is always in the west direction, everywhere on earth.

(3) The shadow-tip method can also be used as a shadow clock to find the approximate time of day (Figure 9-7 on page 9-7).

(a) To find the time of day, move the stick to the intersection of the east-west line and the north-south line, and set it vertically in the ground. The west part of the east-west line indicates 0600 hours, and the east part is 1800 hours, anywhere on earth, because the basic rule always applies.

(b) The north-south line now becomes the noon line. The shadow of the stick is an hour hand in the shadow clock, and with it you can estimate the time using the noon line and the 6 o'clock line as your guides. Depending on your location and the season, the shadow may move either clockwise or counterclockwise, but this does not alter your manner of reading the shadow clock.

(c) The shadow clock is not a timepiece in the ordinary sense. It makes every day 12 unequal hours long, and always reads 0600 hours at sunrise and 1800 hours at sunset. The shadow clock time is closest to conventional clock time at midday, but the spacing of the other hours compared to conventional time varies somewhat with the locality and the date. However, it does provide a satisfactory means of telling time in the absence of properly set watches.

(d) The shadow-tip system is not intended for use in polar regions, which the Department of Defense defines as being above 60° latitude in either hemisphere. Distressed persons in these areas are advised to stay in one place so that search/rescue teams may easily find them. The presence and location of all aircraft and ground parties in polar regions are reported to and checked regularly by governmental or other agencies, and any need for help becomes quickly known.

b. **Watch Method.**

(1) A watch can be used to determine the approximate true north and true south. In the north temperate zone only, the hour hand is pointed toward the sun. A south line can be found midway between the hour hand and 1200 hours, standard time. If on daylight saving time, the north-south line is found between the hour hand and 1300 hours. If there is any doubt as to which end of the line is north, remember that the sun is in the east before noon and in the west after noon.

(2) The watch may also be used to determine direction in the south temperate zone; however, the method is different. The 1200-hour dial is pointed toward the sun, and halfway

between 1200 hours and the hour hand will be a north line. If on daylight saving time, the north line lies midway between the hour hand and 1300 hours (Figure 9-8).



Figure 9-8. Determining direction by using a watch.

(3) The watch method can be in error, especially in the lower latitudes, and may cause *circling*. To avoid this, make a shadow clock and set your watch to the time indicated. After traveling for an hour, take another shadow-clock reading. Reset your watch if necessary.

c. **Star Method.**

(1) Less than 60 of approximately 5,000 stars visible to the eye are used by navigators. The stars seen as we look up at the sky at night are not evenly scattered across the whole sky. Instead they are in groups called constellations.

(2) The constellations that we see depends partly on where we are located on the earth, the time of the year, and the time of the night. The night changes with the seasons because of the journey of the earth around the sun, and it also changes from hour to hour because the turning of the earth makes some constellations seem to travel in a circle. But there is one star that is in almost exactly the same place in the sky all night long every night. It is the North Star, also known as the Polar Star or Polaris.

(3) The North Star is less than 1° off true north and does not move from its place because the axis of the earth is pointed toward it. The North Star is in the group of stars called the Little Dipper. It is the last star in the handle of the dipper. There are two stars in the Big Dipper, which are a big help when trying to find the North Star. They are called the Pointers, and an imaginary line drawn through them five times their distance points to the North Star. There are many stars brighter than the North Star, but none is more important because of its location. However, the North Star can only be seen in the northern hemisphere so it cannot serve as a guide south of the equator. The farther one goes north, the higher the North Star is in the sky, and above latitude 70°, it is too high in the sky to be useful (Figure 9-9).


BIG DIPPER
NORTH STAR
NORTH POLE
BIG M OR W
SOUTHERN CROSS
4½A
A
POINTERS
POINT ABOVE SOUTH POLE
SOUTH POLE

Figure 9-9. Determining direction by the North Star and Southern Cross.

(4) Depending on the star selected for navigation, azimuth checks are necessary. A star near the north horizon serves for about half an hour. When moving south, azimuth checks should be made every 15 minutes. When traveling east or west, the difficulty of staying on azimuth is caused more by the likelihood of the star climbing too high in the sky or losing itself behind the western horizon than it is by the star changing direction angle. When this happens, it is necessary to change to another guide star. The Southern Cross is the main constellation used as a guide south of the equator, and the above general directions for using north and south stars are reversed. When navigating using the stars as guides, the user must know the different constellation shapes and their locations throughout the world (Figure 9-10 and Figure 9-11 on page 9-12).


OCTOBER
NOVEMBER
DECEMBER
JANUARY
FEBRUARY
MARCH
APRIL
MAY
JUNE
JULY
AUGUST
SEPTEMBER
AQUARIUS
PISCES
CETUS
PEGASUS
EQUULEUS
DELPHINUS
ANDROMEDA
ARIES
TRIANGULUM
AQUILA
LACERTA
TAURUS
VULPECULA
CYGNUS
CASSIOPEIA
SCUTUM
LYRA
CEPHEUS
CAMELO-PARDALIS
ORION
SERPENS CAUDA
AURIGA
HERCULES
DRACO
URSA MINOR
OPHIUCHUS
GEMINI
LYNX
MONOCEROS
CORONA BOREALIS
URSA MAJOR
CANIS MINOR
BOOTES
LEO MINOR
CANES VENATICI
CANCER
SERPENS CAPUT
COMA BERENICES
LEO
HYDRA
VIRGO
SEXTANS

Figure 9-10. Constellations, northern hemisphere.


OCTOBER
NOVEMBER
SEPTEMBER
DECEMBER
AUGUST
JULY
JANUARY
FEBRUARY
JUNE
MARCH
MAY
APRIL
PISCES
AQUARIUS
CETUS
PISCIS AUSTRINUS
SCULPTOR
CAPRICORNUS
FORNAX
AQUILA
ERIDANUS
PHOENIX
GRUS
MICROSCOPIUM
HOROLOGIUM
TUCANA
INDUS
SAGITTARIUS
RETICULUM
HYDRUS
SCUTUM
LEPUS
DORADO
CORONA AUSTRALIS
MAGELLANIC CLOUD
OCTANS
PAVO
SERPENS CAUDA
ORION
COLUMBA
PICTOR
MENSA
APUS
ARA
CANIS MAJOR
VOLANS
TRIANGULUM AUSTRALE
PUPPIS
CARINA
MUSCA
SCORPIUS
MONOCEROS
CIRCINUS
OPHIUCHUS
LUPUS
VELA
CRUX
PYXIS
CENTAURUS
LIBRA
ANTLIA
HYDRA
CORVUS
CRATER
VIRGO
SEXTANS

Figure 9-11. Constellations, southern hemisphere.

9-6. GLOBAL POSITIONING SYSTEM

The GPS is a space-based, global, all-weather, continuously available, radio positioning navigation system. It is highly accurate in determining position location derived from signal triangulation from a satellite constellation system. It is capable of determining latitude, longitude, and altitude of the individual user. It is being fielded in hand-held, manpack, vehicular, aircraft, and watercraft configurations. The GPS receives and processes data from satellites on either a simultaneous or sequential basis. It measures the velocity and range with respect to each satellite, processes the data in terms of an earth-centered, earth-fixed coordinate system, and displays the information to the user in geographic or military grid coordinates.

a. The GPS can provide precise steering information, as well as position location. The receiver can accept many checkpoints entered in any coordinate system by the user and convert them to the desired coordinate system. The user then calls up the desired checkpoint and the receiver will display direction and distance to the checkpoint. The GPS does not have inherent drift, an improvement over the Inertial Navigation System, and the receiver will automatically update its position. The receiver can also compute time to the next checkpoint.

b. Specific uses for the GPS are position location; navigation; weapon location; target and sensor location; coordination of firepower; scout and screening operations; combat resupply; location of obstacles, barriers, and gaps; and communication support. The GPS also has the potential to allow units to train their soldiers and provide the following:

- Performance feedback.
- Knowledge of routes taken by the soldier.
- Knowledge of errors committed by the soldier.
- Comparison of planned versus executed routes.
- Safety and control of lost and injured soldiers.

(See Appendix J for more information of the GPS.)

CHAPTER 10

ELEVATION AND RELIEF

The elevation of points on the ground and the relief of an area affect the movement, positioning, and, in some cases, effectiveness of military units. Soldiers must know how to determine locations of points on a map, measure distances and azimuths, and identify symbols on a map. They must also be able to determine the elevation and relief of areas on standard military maps. To do this, they must first understand how the mapmaker indicated the elevation and relief on the map.

10-1. DEFINITIONS

The reference or start point for vertical measurement of elevation on a standard military map are the **datum plane** or **mean sea level**, the point halfway between high tide and low tide. **Elevation** of a point on the earth's surface is the vertical distance it is above or below mean sea level. **Relief** is the representation (as depicted by the mapmaker) of the shapes of hills, valleys, streams, or terrain features on the earth's surface.

10-2. METHODS OF DEPICTING RELIEF

Mapmakers use several methods to depict relief of the terrain.

a. **Layer Tinting.** Layer tinting is a method of showing relief by color. A different color is used for each band of elevation. Each shade of color, or band, represents a definite elevation range. A legend is printed on the map margin to indicate the elevation range represented by each color. However, this method does not allow the map user to determine the exact elevation of a specific point—only the range.

b. **Form Lines.** Form lines are not measured from any datum plane. Form lines have no standard elevation and give only a general idea of relief. Form lines are represented on a map as dashed lines and are never labeled with representative elevations.

c. **Shaded Relief.** Relief shading indicates relief by a shadow effect achieved by tone and color that results in the darkening of one side of terrain features, such as hills and ridges. The darker the shading, the steeper the slope. Shaded relief is sometimes used in conjunction with contour lines to emphasize these features.

d. **Hachures.** Hachures are short, broken lines used to show relief. Hachures are sometimes used with contour lines. They do not represent exact elevations, but are mainly used to show large, rocky outcrop areas. Hachures are used extensively on small-scale maps to show mountain ranges, plateaus, and mountain peaks.

e. **Contour Lines.** Contour lines are the most common method of showing relief and elevation on a standard topographic map. A contour line represents an imaginary line on the ground, above or below sea level. All points on the contour line are at the same elevation. The elevation represented by contour lines is the vertical distance above or below sea level. The three types of contour lines (Figure 10-1, page 10-2) used on a standard topographic map are as follows:

(1) ***Index.*** Starting at zero elevation or mean sea level, every fifth contour line is a heavier line. These are known as index contour lines. Normally, each index contour line is numbered at some point. This number is the elevation of that line.

(2) ***Intermediate.*** The contour lines falling between the index contour lines are called intermediate contour lines. These lines are finer and do not have their elevations given. There are normally four intermediate contour lines between index contour lines.

(3) ***Supplementary***. These contour lines resemble dashes. They show changes in elevation of at least one-half the contour interval. These lines are normally found where there is very little change in elevation, such as on fairly level terrain.



Figure 10-1. Contour lines.

10-3. CONTOUR INTERVALS

Before the elevation of any point on the map can be determined, the user must know the contour interval for the map he is using. The contour interval measurement given in the marginal information is the vertical distance between adjacent contour lines. To determine the elevation of a point on the map—

a. Determine the contour interval and the unit of measure used, for example, feet, meters, or yards (Figure 10-2).



ELEVATION IN METERS
CONTOUR INTERVAL 20 METERS

Figure 10-2. Contour interval note.

b. Find the numbered index contour line nearest the point of which you are trying to determine the elevation (Figure 10-3).



Figure 10-3. Points on contour lines.

c. Determine if you are going from lower elevation to higher, or vice versa. In Figure 10-3, point (a) is between the index contour lines. The lower index contour line is numbered 500, which means any point on that line is at an elevation of 500 meters above mean sea level. The upper index contour line is numbered 600, or 600 meters. Going from the lower to the upper index contour line shows an increase in elevation.

d. Determine the exact elevation of point (a), start at the index contour line numbered 500 and count the number of intermediate contour lines to point (a). Locate point (a) on the second intermediate contour line above the 500-meter index contour line. The contour interval is 20 meters (Figure 10-2), thus each one of the intermediate contour lines crossed to get to point (a) adds 20 meters to the 500-meter index contour line. The elevation of point (a) is 540 meters; the elevation has increased.

e. Determine the elevation of point (b). Go to the nearest index contour line. In this case, it is the upper index contour line numbered 600. Locate point (b) on the intermediate contour line immediately below the 600-meter index contour line. Below means downhill or a lower elevation. Therefore, point (b) is located at an elevation of 580 meters. Remember, if you are increasing elevation, add the contour interval to the nearest index contour line. If you are decreasing elevation, subtract the contour interval from the nearest index contour line.

f. Determine the elevation to a hilltop point (c). Add one-half the contour interval to the elevation of the last contour line. In this example, the last contour line before the hilltop is an index contour line numbered 600. Add one-half the contour interval, 10 meters, to the index contour line. The elevation of the hilltop would be 610 meters.

g. There may be times when you need to determine the elevation of points to a greater accuracy. To do this, you must determine how far between the two contour lines the point lies. However, most military needs are satisfied by estimating the elevation of points between contour lines (Figure 10-4).



Figure 10-4. Points between contour lines.

(1) If the point is less than one-fourth the distance between contour lines, the elevation will be the same as the last contour line. In Figure 10-4, the elevation of *point a* will be 100 meters. To estimate the elevation of a point between one-fourth and three-fourths of the distance between contour lines, add one-half the contour interval to the last contour line.

(2) *Point b* is one-half the distance between contour lines. The contour line immediately below *point b* is at an elevation of 160 meters. The contour interval is 20 meters; thus one-half the contour interval is 10 meters. In this case, add 10 meters to the last contour line of 160 meters. The elevation of *point b* would be about 170 meters.

(3) A point located more than three-fourths of the distance between contour lines is considered to be at the same elevation as the next contour line. *Point c* is located three-fourths of the distance between contour lines. In Figure 10-4, *point c* would be considered to be at an elevation of 180 meters.

h. To estimate the elevation to the bottom of a depression, subtract one-half the contour interval from the value of the lowest contour line before the depression. In Figure 10-5, the lowest contour line before the depression is 240 meters in elevation. Thus, the elevation at the edge of the depression is 240 meters. To determine the elevation at the bottom of the depression, subtract one-half the contour interval. The contour interval for this example is 20 meters. Subtract 10 meters from the lowest contour line immediately before the depression. The result is that the elevation at the bottom of the depression is 230 meters. The tick marks on the contour line forming a depression always point to lower elevations.



Figure 10-5. Depression.

i. In addition to the contour lines, bench marks and spot elevations are used to indicate points of known elevations on the map.

(1) Bench marks, the more accurate of the two, are symbolized by a black X, such as X BM 214. The 214 indicates that the center of the X is at an elevation of 214 units of measure (feet, meters, or yards) above mean sea level. To determine the units of measure, refer to the contour interval in the marginal information.

(2) Spot elevations are shown by a brown X and are usually located at road junctions and on hilltops and other prominent terrain features. If the elevation is shown in black numerals, it has been checked for accuracy; if it is in brown, it has not been checked.

NOTE: New maps are being printed using a dot instead of brown Xs.

10-4. TYPES OF SLOPES

Depending on the military mission, soldiers may need to determine not only the height of a hill, but the degree of the hill's slope as well. The rate of rise or fall of a terrain feature is known as its slope. The speed at which equipment or personnel can move is affected by the slope of the ground or terrain feature. This slope can be determined from the map by studying the contour lines—the closer the contour lines, the steeper the slope; the farther apart the contour lines, the gentler the slope. Four types of slopes that concern the military are as follows:

a. **Gentle.** Contour lines showing a uniform, gentle slope will be evenly spaced and wide apart (Figure 10-6, page 10-6). Considering relief only, a uniform, gentle slope allows the defender to use grazing fire. The attacking force has to climb a slight incline.



Figure 10-6. Uniform, gentle slope.

b. **Steep.** Contour lines showing a uniform, steep slope on a map will be evenly spaced, but close together. Remember, the closer the contour lines, the steeper the slope (Figure 10-7). Considering relief only, a uniform, steep slope allows the defender to use grazing fire, and the attacking force has to negotiate a steep incline.



Figure 10-7. Uniform, steep slope.

c. **Concave.** Contour lines showing a concave slope on a map will be closely spaced at the top of the terrain feature and widely spaced at the bottom (Figure 10-8, page 10-7). Considering relief only, the defender at the top of the slope can observe the entire slope and the terrain at the bottom, but he cannot use grazing fire. The attacker would have no cover from the defender's observation of fire, and his climb would become more difficult as he got farther up the slope.



Figure 10-8. Concave slope.

d. **Convex.** Contour lines showing a convex slope on a map will be widely spaced at the top and closely spaced at the bottom (Figure 10-9). Considering relief only, the defender at the top of the convex slope can obtain a small distance of grazing fire, but he cannot observe most of the slope or the terrain at the bottom. The attacker will have concealment on most of the slope and an easier climb as he nears the top.



Figure 10-9. Convex slope.

10-5. PERCENTAGE OF SLOPE

The speed at which personnel and equipment can move up or down a hill is affected by the slope of the ground and the limitations of the equipment. Because of this, a more exact way of describing a slope is necessary.

a. Slope may be expressed in several ways, but all depend upon the comparison of vertical distance (VD) to horizontal distance (HD) (Figure 10-10). Before we can determine the percentage of a slope, we must know the VD of the slope. The VD is determined by subtracting the lowest point of the slope from the highest point. Use the contour lines to determine the highest and lowest point of the slope (Figure 10-11).



Figure 10-10. Slope diagram.



NOTE: Be sure to use the same unit of measure for vertical and horizontal distances.

CONTOUR INTERVAL: 20 METERS

Figure 10-11. Contour line around a slope.

b. To determine the percentage of the slope between points (a) and (b) in Figure 10-11, determine the elevation of point (b) (590 meters). Then determine the elevation of point (a) (380 meters). Determine the vertical distance between the two points by subtracting the elevation of point (a) from the elevation of point .The difference (210 meters) is the VD between points (a) and (b). Then measure the HD between the two points on the map in Figure 10-12. After the horizontal distance has been determined, compute the percentage of the slope by using the formula shown in Figure 10-13.



Figure 10-12. Measuring horizontal distance.


590 METERS
(b)
VD
210 METERS
380 METERS
(a)
HD 3,000 METERS
VD =b −a = 210 METERS
H D =3,000 METERS
% SLOPE = V D X 100 / H D or (V D) 210 X 100 / (H D) 3,000 = 21,000 / 3,000 = 7%
Multiply the distance by 100. Divide the total by the horizontal distance. The result is the percentage of slope.

Figure 10-13. Percentage of slope in meters.

c. The slope angle can also be expressed in degrees. To do this, determine the VD and HD of the slope. Multiply the VD by 57.3 and then divide the total by the HD (Figure 10-14). This method determines the approximate degree of slope and is reasonably accurate for slope angles less than 20º.


GRADIENT = V D / H D
V D = b − a = 150 METERS
H D = 3,000 METERS
150 X 57.3 / 3,000 = 8575 / 3,000 = 2.9 or 3 DEGREES of SLOPE
590 METERS
(b)
VD
210 METERS
380 METERS
(a)
HD 3,000 METERS

Figure 10-14. Degree of slope.

d. The slope angle can also be expressed as a gradient. The relationship of horizontal and vertical distance is expressed as a fraction with a numerator of one (Figure 10-15).


GRADIENT = VD / HD
V D = b − a = 150 METERS
H D = 3,000 METERS
150 / 3,000 = 1 / 20 = 1 METER RISE FOR EVERY / 20 METERS OF HORIZONTAL DISTANCE
700 METERS
(b)
550 METERS
(a)
HD 3,000 METERS

Figure 10-15. Gradient.

10-6. TERRAIN FEATURES

All terrain features are derived from a complex landmass known as a mountain or ridgeline (Figure 10-16). The term ridgeline is not interchangeable with the term ridge. A ridgeline is a line of high ground, usually with changes in elevation along its top and low ground on all sides from which a total of 10 natural or man-made terrain features are classified.


RIDGELINE
RIDGELINE

Figure 10-16. Ridgeline.

a. **Major Terrain Features.**

(1) ***Hill***. A hill is an area of high ground. From a hilltop, the ground slopes down in all directions. A hill is shown on a map by contour lines forming concentric circles. The inside of the smallest closed circle is the hilltop (Figure 10-17).



Figure 10-17. Hill.

(2) ***Saddle***. A saddle is a dip or low point between two areas of higher ground. A saddle is not necessarily the lower ground between two hilltops; it may be simply a dip or break along a level ridge crest. If you are in a saddle, there is high ground in two opposite directions and lower ground in the other two directions. A saddle is normally represented as an hourglass (Figure 10-18).



Figure 10-18. Saddle.

(3) ***Valley***. A valley is a stretched-out groove in the land, usually formed by streams or rivers. A valley begins with high ground on three sides, and usually has a course of running water through it. If standing in a valley, three directions offer high ground, while the fourth

direction offers low ground. Depending on its size and where a person is standing, it may not be obvious that there is high ground in the third direction, but water flows from higher to lower ground. Contour lines forming a valley are either U-shaped or V-shaped. To determine the direction water is flowing, look at the contour lines. The closed end of the contour line (U or V) always points upstream or toward high ground (Figure 10-19).



Figure 10-19. Valley.

(4) ***Ridge***. A ridge is a sloping line of high ground. If you are standing on the centerline of a ridge, you will normally have low ground in three directions and high ground in one direction with varying degrees of slope. If you cross a ridge at right angles, you will climb steeply to the crest and then descend steeply to the base. When you move along the path of the ridge, depending on the geographic location, there may be either an almost unnoticeable slope or a very obvious incline. Contour lines forming a ridge tend to be U-shaped or V-shaped. The closed end of the contour line points away from high ground (Figure 10-20).



Figure 10-20. Ridge.

(5) ***Depression***. A depression is a low point in the ground or a sinkhole. It could be described as an area of low ground surrounded by higher ground in all directions, or simply a hole in the ground. Usually only depressions that are equal to or greater than the contour interval will be shown. On maps, depressions are represented by closed contour lines that have tick marks pointing toward low ground (Figure 10-21).



Figure 10-21. Depression.

b. **Minor Terrain Features.**

(1) ***Draw***. A draw is a less developed stream course than a valley. In a draw, there is essentially no level ground and, therefore, little or no maneuver room within its confines. If you are standing in a draw, the ground slopes upward in three directions and downward in the other direction. A draw could be considered as the initial formation of a valley. The contour lines depicting a draw are U-shaped or V-shaped, pointing toward high ground (Figure 10-22).



Figure 10-22. Draw.

(2) ***Spur***. A spur is a short, continuous sloping line of higher ground, normally jutting out from the side of a ridge. A spur is often formed by two rough parallel streams, which cut

draws down the side of a ridge. The ground sloped down in three directions and up in one direction. Contour lines on a map depict a spur with the U or V pointing away from high ground (Figure 10-23).



Figure 10-23. Spur.

(3) ***Cliff***. A cliff is a vertical or near vertical feature; it is an abrupt change of the land. When a slope is so steep that the contour lines converge into one "carrying" contour of contours, this last contour line has tick marks pointing toward low ground (Figure 10-24A). Cliffs are also shown by contour lines very close together and, in some instances, touching each other (Figure 10-24B, page 10-16).



Figure 10-24A. Cliff.



Figure 10-24B. Cliff.

c. **Supplementary Terrain Features.**

(1) ***Cut***. A cut is a man-made feature resulting from cutting through raised ground, usually to form a level bed for a road or railroad track. Cuts are shown on a map when they are at least 10 feet high, and they are drawn with a contour line along the cut line. This contour line extends the length of the cut and has tick marks that extend from the cut line to the roadbed, if the map scale permits this level of detail (Figure 10-25).

(2) ***Fill***. A fill is a man-made feature resulting from filling a low area, usually to form a level bed for a road or railroad track. Fills are shown on a map when they are at least 10 feet high, and they are drawn with a contour line along the fill line. This contour line extends the length of the filled area and has tick marks that point toward lower ground. If the map scale permits, the length of the fill tick marks are drawn to scale and extend from the base line of the fill symbol (Figure 10-25).


CUT
FILL
CUT
FILL

Figure 10-25. Cut and fill.

10-7. INTERPRETATION OF TERRAIN FEATURES

Terrain features do not normally stand a lone. To better understand these when they are depicted on a map, you need to interpret them. Terrain features (Figure 10-26) are interpreted by using contour lines, the SOSES approach, ridgelining, or streamlining.


1. HILL
2. VALLEY
3. RIDGE
4. SADDLE
5. DEPRESSION
6. DRAW
7. SPUR
8. CLIFF
9. CUT
10. FILL

Figure 10-26. Terrain features.

a. **Contour Lines**. Emphasizing the main contour lines is a technique used to interpret the terrain of an area. By studying these contour lines, you able to obtain a better understanding of the layout of the terrain and to decide on the best route.

(1) The following description pertains to Figure 10-27 on page 10-20. Running east to west across the complex landmass is a ridgeline. A ridgeline is a line of high ground, usually with changes in elevation along its top and low ground on all sides. The changes in elevation are the three hilltops and two saddles along the ridgeline. From the top of each hill, there is lower ground in all directions. The saddles have lower ground in two directions and high ground in the opposite two directions. The contour lines of each saddle form half an hourglass shape. Because of the difference in size of the higher ground on the two opposite sides of a saddle, a full hourglass shape of a saddle may not be apparent.

(2) There are four prominent ridges. A ridge is on each end of the ridgeline and two ridges extend south from the ridgeline. All of the ridges have lower ground in three directions and higher ground in one direction. The closed ends of the U's formed by the contour lines point away from higher ground.

(3) To the south lies a valley; the valley slopes downward from east to west. Note that the U of the contour line points to the east, indicating higher ground in that direction and lower ground to the west. Another look at the valley shows high ground to the north and south of the valley.

(4) Just east of the valley is a depression. There is higher ground in all directions when looking from the bottom of the depression.

(5) There are several spurs extending generally south from the ridgeline. They, like ridges, have lower ground in three directions and higher ground in one direction. Their contour line U's point away from higher ground.

(6) Between the ridges and spurs are draws. They, like valleys, have higher ground in three directions and lower ground in one direction. Their contour line U's and V's point toward higher ground.

(7) Two contour lines on the north side of the center hill are touching or almost touching. They have ticks indicating a vertical or nearly vertical slope or a cliff.

(8) The road cutting through the eastern ridge depicts cuts and fills. The breaks in the contour lines indicate cuts, and the ticks pointing away from the roadbed on each side of the road indicate fills.

b**. SOSES.** A recommended technique for identifying specific terrain features and then locating them on the map is to make use of five of their characteristics known by the mnemonic SOSES. Terrain features can be examined, described, and compared with each other and with corresponding map contour patterns in terms of their shapes, orientations, sizes, elevations, and slopes.

(1) ***Shape***. The general form or outline of the feature at its base.

(2) ***Orientation***. The general trend or direction of a feature from your viewpoint. A feature can be in line, across, or at an angle to your viewpoint.

(3) ***Size***. The length or width of a feature horizontally across its base. For example, one terrain feature might be larger or smaller than another terrain feature.

(4) ***Elevation***. The height of a terrain feature. This can be described either in absolute or relative terms as compared to the other features in the area. One landform may be higher, lower, deeper, or shallower than another.

(5) ***Slope***. The type (uniform, convex, or concave) and the steepness or angle (steep or gentle) of the sides of a terrain feature.

Through practice, you can learn to identify several individual terrain features in the field and see how they vary in appearance.

NOTE: Further terrain analysis using SOSES can be learned by using the Map Interpretation and Terrain Association Course. It consists of three separate courses of instruction: basic, intermediate, and advanced. Using photographic slides of terrain and other features, basic instruction teaches how to identify basic terrain feature types on the ground and on the map. Intermediate instruction teaches elementary map interpretation and terrain association using real world scenes and map sections of the same terrain. Advanced instruction teaches advanced techniques for map interpretation and terrain association. The primary emphasis is on the concepts of map design guidelines and terrain association skills. Map design guidelines refer to the rules and practices used by cartographers in the compilation and symbolization of military topographic maps. Knowledge of the selection, classification, and symbolization of mapped features greatly enhances the user's ability to interpret map information.

c. **Ridgelining.** This technique helps you to visualize the overall lay of the ground within the area of interest on the map. Follow these steps:

(1) Identify on the map the crests of the ridgelines in your area of operation by identifying the close-out contours that lie along the hilltop.

(2) Trace over the crests so each ridgeline stands out clearly as one identifiable line.

(3) Go back over each of the major ridgelines and trace over the prominent ridges and spurs that come out of the ridgelines.

The usual colors used for this tracing are red or brown; however, you may use any color at hand. When you have completed the ridgelining process, you will find that the high ground on the map will stand out and that you will be able to see the relationship between the various ridgelines (Figure 10-27, page 10-20).

d**. Streamlining.** This procedure (Figure 10-27, page 10-20) is similar to that of ridgelining.

(1) Identify all the mapped streams in the area of operations.

(2) Trace over them to make them stand out more prominently.

(3) Then identify other low ground, such as smaller valleys or draws that feed into the major streams, and trace over them.

This brings out the drainage pattern and low ground in the area of operation on the map. The color used for this is usually blue; but again, if blue is not available, use any color at hand so long as the distinction between the ridgelines and the streamlines is clear.



Figure 10-27. Ridgelining and streamlining.

10-8. PROFILES

The study of contour lines to determine high and low points of elevation is usually adequate for military operations. However, there may be a few times when we need a quick and precise reference to determine exact elevations of specific points. When exactness is demanded, a profile is required. A profile, within the scope and purpose of this manual, is an exaggerated side view of a portion of the earth's surface along a line between two or more points.

a. A profile can be used for many purposes. The primary purpose is to determine if line of sight is available. Line of sight is used—

(1) To determine defilade positions.

(2) To plot hidden areas or dead space.

(3) To determine potential direct fire weapon positions.

(4) To determine potential locations for defensive positions.

(5) To conduct preliminary planning in locating roads, pipelines, railroads, or other construction projects.

b. A profile can be constructed from any contoured map. Its construction requires the following steps:

(1) Draw a line on the map from where the profile is to begin to where it is to end (Figure 10-28).



Figure 10-28. Connecting points.

(2) Find the value of the highest and lowest contour lines that cross or touch the profile line. Add one contour value above the highest and one below the lowest to take care of hills and valleys.

(3) Select a piece of lined notebook paper with as many lines as was determined in (2) above. The standard Army green pocket notebook or any other paper with 1/4-inch lines is ideal. Wider lines, up to 5/8-inch, may be used. If lined paper is not available, draw equally spaced horizontal lines on a blank sheet of paper.

(4) Number the top line with the highest value and the bottom line with the lowest value as determined in (2) above.

(5) Number the rest of the lines in sequence, starting with the second line from the top. The lines will be numbered in accordance with the contour interval (Figure 10-29).

(6) Place the paper on the map with the lines next to and parallel to the profile line (Figure 10-29).

(7) From every point on the profile line where a contour line, stream, intermittent stream, or other body of water crosses or touches, drop a perpendicular line to the line having the same value. Place a tick mark where the perpendicular line crosses the number line (Figure 10-29). Where trees are present, add the height of the trees to the contour line and place a tick mark there. Assume the height of the trees to be 50 feet or 15 meters where dark green tint is shown on the map. Vegetation height may be adjusted up or down when operations in the area have provided known tree heights.

(8) After all perpendicular lines have been drawn and tick marks placed where the lines cross, connect all tick marks with a smooth, natural curve to form a horizontal view or profile of the terrain along the profile line (Figure 10-29).

NOTE: The profile drawn may be exaggerated. The spacing between the lines drawn on the sheet of paper determines the amount of exaggeration and may be varied to suit any purpose.


END
2
400
LINE OF SIGHT
START
1
400
400
300
300
300
420
400
380
360
340
320
300
280
260
240
220

Figure 10-29. Dropping perpendiculars.

(9) Draw a straight line from the start point to the end point on the profile. If the straight line intersects the curved profile, line of sight to the end point is not available (Figure 10-30).


END
2
400
300
LINE OF SIGHT
START
1
A
B
C
D
E
F
G
H
I
J
420
400
380
360
340
320
300
280
260
240
220

Figure 10-30. Drawing lines to additional points.

(10) Determine the line of sight to other points along the profile line by drawing a line from the start point to additional points. In Figure 10-31 on page 10-24, line of sight is available to—

A—Yes
B—No
C—No
D—Yes
E—No
F—No
G—Yes
H—No
I—No

The vertical distance between navigable ground up to the line of sight line is the depth of defilade.

c. When time is short, or when a complete profile is not needed, one may be constructed showing only the hilltops, ridges, and if desired, the valleys. This is called a hasty profile. It is constructed in the same manner as a full profile (Figure 10-31).


END
START
LINE OF SIGHT
2
1
A
B
C
D
E
F
400
400
400
300
300
420
400
380
360
340
320
300
280
260
240
220

Figure 10-31. Drawing a hasty profile.

CHAPTER 11

TERRAIN ASSOCIATION

Failure to make use of the vast amounts of information presented by the map and available to the eye on the ground reduces the chances for success in land navigation. The soldier who has repeatedly practiced the skills of identifying and discriminating among the many types of terrain and other features knows how these features are mapped. He can begin to visualize the shape of the land by studying the map, estimate distances, and perform quick resection from the many landmarks he sees is the one who will be at the right place to help defeat the enemy on the battlefield. This chapter tells how to orient a map with and without a compass, how to find locations on a map as well as on the ground, how to study the terrain, and how to move on the ground using terrain association and dead reckoning.

11-1. ORIENTING THE MAP

The first step for a navigator in the field is orienting the map. A map is oriented when it is in a horizontal position with its north and south corresponding to the north and south on the ground. Some orienting techniques follow:

a. **Using a Compass**. When orienting a map with a compass, remember that the compass measures magnetic azimuths. Since the magnetic arrow points to magnetic north, pay special attention to the declination diagram. There are two techniques used.

(1) ***First Technique***. Determine the direction of the declination and its value from the declination diagram.

(a) With the map in a horizontal position, take the straightedge on the left side of the compass and place it alongside the north-south grid line with the cover of the compass pointing toward the top of the map. This procedure places the fixed black index line of the compass parallel to north-south grid lines of the map.

(b) Keeping the compass aligned as directed above, rotate the map and compass together until the magnetic arrow is below the fixed black index line on the compass. At this time, the map is close to being oriented.

(c) Rotate the map and compass in the direction of the declination diagram.

(d) If the magnetic north arrow on the map is to the left of the grid north, check the compass reading to see if it equals the G-M angle given in the declination diagram. The map is then oriented (Figure 11-1, page 11-2).


LEFT
MAGNETIC NORTH
TRUE NORTH
GRID NORTH
04 50'
05
06
07
GRID CONVERGENCE
1°8' (20 MILS)
FOR CENTER OF SHEET
1970
G-M ANGLE
10°

Figure 11-1. Map oriented with 11 degrees west declination.

(e) If the magnetic north is to the right of grid north, check the compass reading to see if it equals 360 degrees minus the G-M angle (Figure 11-2).


360°
-21°
339°
RIGHT
TRUE NORTH
GRID NORTH
MAGNETIC NORTH
511
512
50'
513
514
517
GRID CONVERGENCE
0°5' (1 MIL)
1975
G-M ANGLE

Figure 11-2. Map oriented with 21 degrees east declination.

(2) ***Second Technique***. Determine the direction of the declination and its value from the declination diagram.

(a) Using any north-south grid line on the map as a base, draw a magnetic azimuth equal to the G-M angle given in the declination diagram with the protractor.

(b) If the declination is easterly (right), the drawn line is equal to the value of the G-M angle. Then align the straightedge, which is on the left side of the compass, alongside the drawn line on the map. Rotate the map and compass until the magnetic arrow of the compass is below the fixed black index line. The map is now oriented (Figure 11-3).



Figure 11-3. Map oriented with 15 degrees east declination.

(c) If the declination is westerly (left), the drawn line will equal 360 degrees minus the value of the G-M angle. Then align the straightedge, which is on the left side of the compass, alongside the drawn line on the map. Rotate the map and compass until the magnetic arrow of the compass is below the fixed black index line. The map is now oriented (Figure 11-4, page 11-4).

NOTES:
1. Once the map is oriented, magnetic azimuths are determined using the compass. Do not move the map from its oriented position since any change in its position moves it out of line with the magnetic north. [See paragraph 11-6b(1).]
2. Special care should be taken whenever orienting your map with a compass. A small mistake can cause you to navigate in the wrong direction.


360°
-10°
350°
DRAW LINE
350°
MAGNETIC ARROW
ALIGNED WITH THE
BLACK INDEX LINE
MAGNETIC NORTH
GRID NORTH
TRUE NORTH
1971
G-M ANGLE
10°W (6220
MILS)
METERS
W
E

Figure 11-4. Map oriented with 10 degrees west declination.

b. **Using Terrain Association**. A map can be oriented by terrain association when a compass is not available or when the user has to make many quick references as he moves across country. Using this method requires careful examination of the map and the ground, and the user must know his approximate location (Figure 11-5). Orienting by this method is discussed in detail in paragraph 11-3.



Figure 11-5. Terrain association.

c. **Using Field-Expedient Methods.** When a compass is not available and there are no recognizable terrain features, a map may be oriented by any of the field-expedient methods described in paragraph 9-5. Also see Figure 11-6.



Figure 11-6. Field-expedient method.

11-2. LOCATIONS

The key to success in land navigation is to know your location at all times. With this basic knowledge, you can decide what direction and what distance to travel.

a. **Known Position**. Most important of all is the initial location of the user before starting any movement in the field. If movement takes place without establishing the initial location, everything that is done in the field from there on is a gamble. Determine the initial location by referring to the last known position, by grid coordinates and terrain association, or by locating and orienting your position on the map and ground.

b. **Known Point/Known Distance (Polar Plot)**. This location can be determined by knowing the starting point, the azimuth to the desired objective, and the distance to it.

c. **Resection**. See Chapter 6.

d. **Modified Resection**. See Chapter 6.

e. **Intersection**. See Chapter 6.

f. **Indirect Fire**. Finding a location by indirect fire is done with smoke. Use the point of impact of the round as a reference point from which distances and azimuth can be obtained.

11-3. TERRAIN ASSOCIATION USAGE

The technique of moving by terrain association is more forgiving of mistakes and far less time-consuming than dead reckoning. It best suits those situations that call for movement from one area to another. Errors made using terrain association are easily corrected because you are comparing what you expected to see from the map to what you do see on the ground. Errors are anticipated and will not go unchecked. You can easily make adjustments based upon what you encounter. Periodic position-fixing through either plotted or estimated resection will also make it possible to correct your movements, call for fire, or call in the locations of enemy targets or any other information of tactical or logistical importance.

a. **Matching the Terrain to the Map by Examining Terrain Features**. By observing the contour lines in detail, the five major terrain features (hilltop, valley, ridge, depression, and saddle) should be determined. This is a simple task in an area where the observer has ample view of the terrain in all directions. One-by-one, match the terrain features depicted on the map with the same features on the ground. In restricted terrain, this procedure becomes harder; however, constantly check the map as you move since it is the determining factor (Figure 11-5).

b. **Comparing the Vegetation Depicted on the Map**. When comparing the vegetation, a topographic map should be used to make a comparison of the clearings that appear on the map with the ones on the ground. The user must be familiar with the different symbols, such as vineyards, plantations, and orchards that appear on the legend. The age of the map is an important factor when comparing vegetation. Some important vegetation features were likely to be different when the map was made. Another important factor about vegetation is that it can change overnight by natural accidents or by man (forest fires, clearing of land for new developments, farming, and so forth).

c. **Masking by the Vegetation**. Camouflage the important landforms using vegetation. Use of camouflage makes it harder for the navigator to use terrain association.

d. **Using the Hydrography**. Inland bodies of water can help during terrain association. The shape and size of lakes in conjunction with the size and direction of flow of the rivers and streams are valuable help.

e. **Using Man-made Features**. Man-made features are an important factor during terrain association. The user must be familiar with the symbols shown in the legend representing those features. The direction of buildings, roads, bridges, high-tension lines, and so forth make the terrain inspection a lot easier; however, the age of the map must be considered because man-made features appear and disappear constantly.

f. **Examining the Same Piece of Terrain During the Different Seasons of the Year**. In those areas of the world where the seasons are distinctive, a detailed examination of the terrain should be made during each of the seasons. The same piece of land does not present the same characteristics during both spring and winter.

(1) During winter, the snow packs the vegetation, delineating the land, making the terrain features appear as clear as they are shown by the contour lines on the map. Ridges, valleys, and saddles are very distinctive.

(2) During spring, the vegetation begins to reappear and grow. New vegetation causes a gradual change of the land to the point that the foliage conceals the terrain features and makes the terrain hard to recognize.

(3) During summer months, the effects are similar to those in the spring.

(4) Fall makes the land appear different with its change of color and gradual loss of vegetation.

(5) During the rainy season, the vegetation is green and thick, and the streams and ponds look like small rivers and lakes. In scarcely vegetated areas, the erosion changes the shape of the land.

(6) During a period of drought, the vegetation dries out and becomes vulnerable to forest fires that change the terrain whenever they occur. Also during this season, the water levels of streams and lakes drop, adding new dimensions and shape to the existing mapped areas.

g. **Following an Example of Terrain Association**. Your location is hilltop 514 in the lower center of the map in Figure 11-7.



Figure 11-7. Example of terrain association.

(1) ***To The North***. The contour lines indicate that the hill slopes down for about 190 meters, and that it leads into a small valley containing an intermittent stream. On the other side of the stream as you continue with your northerly inspection, the terrain starts a gradual ascent, indicating a hilltop partially covered with vegetation, until an unimproved road is reached. This road runs along a gradual ridgeline with north-west direction. Then the contour line spacings become narrow, indicating a steeper grade that leads to a narrow valley containing a small intermittent stream. As you continue up, you find a small but prominent ridge with a clearing. The contour lines once again show a steeper grade leading to a moderate valley containing an intermittent stream running in a south-east direction.

(2) ***To The East***. There is a clearing of the terrain as it slopes down to Schley Pond. An ample valley is clearly seen on the right side of the pond, as indicated by the "U" and "V" shape of the contour lines. This valley contains some swamp areas and there is a long ridgeline on the north portion of the valley.

(3) ***To The South***. The terrain gently slopes downward until a clear area is reached. It continues in a downward direction to an intermittent stream running south-east in a small valley. There is also an improved road running in the same direction as the valley. At the intersection of the roads as you face south, there is a clearing of about 120 meters on the ridge. At the bottom of it, a stream runs from Schley Pond in a south-west direction through an ample valley fed by two intermittent streams. As you continue, a steep, vegetated hill is found with a clearing on its top, followed by a small saddle and another hilltop.

(4) ***To The West***. First, you see a small, clear valley. It is followed by a general ridgeline running north-west in which an unimproved road is located just before a hilltop. Continuing on a westerly direction, you will find a series of alternate valleys and ridges.

11-4. TACTICAL CONSIDERATIONS

Military cross-country navigation is intellectually demanding because it is imperative that the unit, crew, or vehicle survive and successfully complete the move in order to accomplish its mission. However, the unnecessary use of a difficult route makes navigation too complicated, creates more noise when proceeding over it, causes wear and tear on equipment and personnel, increases the need for and needlessly complicate recovery operations, and wastes scarce time. On receipt of a tactical mission, the leader begins his troop-leading procedures and makes a tentative plan. He bases the tentative plan on a good terrain analysis. He analyzes the considerations covered in the following mnemonics—OCOKA and METT-T.

a**. OCOKA**. The terrain should be analyzed for observation and fields of fire, cover and concealment, obstacles, key terrain, and avenues of approach.

(1) ***Observation and Fields of Fire***. The purpose of observation is to see the enemy (or various landmarks) but not be seen by him. Anything that can be seen can be hit. Therefore, a field of fire is an area that a weapon or a group of weapons can cover effectively with fire from a given position.

(2) ***Cover and Concealment***. Cover is shelter or protection (from enemy fire) either natural or artificial. Always try to use covered routes and seek cover for each halt, no matter how brief it is planned to be. Unfortunately, two factors interfere with obtaining constant cover. One is time and the other is terrain. Concealment is protection from observation or surveillance, including concealment from enemy air observation. Before, trees provided good concealment, but with modern thermal and infrared imaging equipment, trees are not always effective. When you are moving, concealment is generally secondary; therefore, select routes and positions that do not allow covered or concealed enemy near you.

(3) ***Obstacles***. Obstacles are any obstructions that stop, delay, or divert movement. Obstacles can be natural (rivers, swamps, cliffs, or mountains) or they may be artificial (barbed wire entanglements, pits, concrete or metal antimechanized traps). They can be ready-made or constructed in the field. Always consider any possible obstacles along your movement route and, if possible, try to keep obstacles between the enemy and yourself.

(4) ***Key Terrain***. Key terrain is any locality or area that the seizure or retention of affords a marked advantage to either combatant. Urban areas that are often seen by higher

headquarters as being key terrain because they are used to control routes. On the other hand, an urban area that is destroyed may be an obstacle instead. High ground can be key because it dominates an area with good observation and fields of fire. In an open area, a draw or wadi (dry streambed located in an arid area) may provide the only cover for many kilometers, thereby becoming key. You should always attempt to locate any area near you that could be even remotely considered as key terrain.

(5) ***Avenues of Approach***. These are access routes. They may be the routes you can use to get to the enemy or the routes they can use to get to you. Basically, an identifiable route that approaches a position or location is an avenue of approach to that location. They are often terrain corridors such as valleys or wide, open areas.

b**. METT-T.** Tactical factors other than the military aspects of terrain must also be considered in conjunction with terrain during movement planning and execution as well. These additional considerations are mission, enemy, terrain and weather, troops, and time available.

(1) ***Mission***. This refers to the specific task assigned to a unit or individual. It is the duty or task together with the purpose that clearly indicates the action to be taken and the reason for it—but not how to do it. Training exercises should stress the importance of a thorough map reconnaissance to evaluate the terrain. This allows the leader to confirm his tentative plan, basing his decision on the terrain's effect on his mission.

(a) Marches by foot or vehicle are used to move troops from one location to another. Soldiers must get to the right place, at the right time, and in good fighting condition. The normal rate for an 8-hour foot march is 4 kmph. However, the rate of march may vary, depending on the following factors:

- Distance.
- Time allowed.
- Likelihood of enemy contact.
- Terrain.
- Weather.
- Physical condition of soldiers.
- Equipment/weight to be carried.
- A motor march requires little or no walking by the soldiers, but the factors affecting the rate of march still apply.

(b) Patrol missions are used to conduct combat or reconnaissance operations. Without detailed planning and a thorough map reconnaissance, any patrol mission may not succeed. During the map reconnaissance, the mission leader determines a primary and alternate route to and from the objectives.

(c) Movement to contact is conducted whenever an element is moving toward the enemy but is not in contact with the enemy. The lead element must orient its movement on the objective by conducting a map reconnaissance, determining the location of the objective on both the map and the ground, and selecting the route to be taken.

(d) Delays and withdrawals are conducted to slow the enemy down without becoming decisively engaged, or to assume another mission. To be effective, the element leader must know where he is to move and the route to be taken.

(2) ***Enemy***. This refers to the strength, status of training, disposition (locations), doctrine, capabilities, equipment (including night vision devices), and probable courses of action that impact upon both the planning and execution of the mission, including a movement.

(3) ***Terrain and Weather***. Observation and fields of fire influence the placement of positions and crew-served weapons. The leader conducts a map reconnaissance to determine key terrain, obstacles, cover and concealment, and likely avenues of approach.

(a) Key terrain is any area whose control affords a marked advantage to the force holding it. Some types of key terrain are high ground, bridges, towns, and road junctions.

(b) Obstacles are natural or man-made terrain features that stop, slow down, or divert movement. Consideration of obstacles is influenced by the unit's mission. An obstacle may be an advantage or disadvantage, depending upon the direction of attack or defense. Obstacles can be found by conducting a thorough map reconnaissance and study of recent aerial photographs.

(c) Cover and concealment are determined for both friendly and enemy forces. Concealment is protection from observation; cover is protection from the effects of fire. Most terrain features that offer cover also provide concealment from ground observation. There are areas that provide no concealment from enemy observation. These danger areas may be large or small open fields, roads, or streams. During the leader's map reconnaissance, he determines any obvious danger areas and, if possible, adjusts his route.

(d) Avenues of approach are routes by which a unit may reach an objective or key terrain. To be considered an AA, a route must provide enough width for the deployment of the size force for which it is being considered. The AAs are also considered for the subordinate enemy force. For example, a company determines likely AAs for an enemy platoon; a platoon determines likely AAs for an enemy squad. Likely AAs may be either ridges, valleys, or by air. By examining the terrain, the leader determines the likely enemy AAs based on the tactical situation.

(e) Weather has little effect on dismounted land navigation. Rain and snow could possibly slow down the rate of march, that is all. But during mounted land navigation, the navigator must know the effect of weather on his vehicle. (See Chapter 12 for mounted land navigation.)

(4) ***Troops***. Consideration of your own troops is equally important. The size and type of the unit to be moved and its capabilities, physical condition, status of training, and types of equipment assigned all affect the selection of routes, positions, fire plans, and the various decisions to be made during movement. On ideal terrain such as relatively level ground with little or no woods, a platoon can defend a front of up to 400 meters. The leader must conduct a thorough map reconnaissance and terrain analysis of the area his unit is to defend. Heavily wooded areas or very hilly areas may reduce the front a platoon can defend. The size of the unit must also be taken into consideration when planning a movement to contact. During movement, the unit must retain its ability to maneuver. A small draw or stream may reduce the unit's maneuverability but provide excellent concealment. All of these factors must be considered.

(a) Types of equipment that may be needed by the unit can be determined by a map reconnaissance. For example, if the unit must cross a large stream during its movement to the objective, ropes may be needed for safety lines.

(b) Physical capabilities of the soldiers must be considered when selecting a route. Crossing a large swampy area may present no problem to a physically fit unit, but to a unit that has not been physically conditioned, the swampy area may slow or completely stop its movement.

(5) ***Time Available***. At times, the unit may have little time to reach an objective or to move from one point to another. The leader must conduct a map reconnaissance to determine the quickest route to the objective; this is not always a straight route. From point A to point B on the map may appear to be 1,000 meters, but if the route is across a large ridge, the distance will be greater. Another route from point A to B may be 1,500 meters—but on flat terrain. In this case, the quickest route would be across the flat terrain; however, concealment and cover may be lost.

11-5. MOVEMENT AND ROUTE SELECTION

One key to success in tactical missions is the ability to move undetected to the objective. There are four steps to land navigation. Being given an objective and the requirement to move there, you must know where you are, plan the route, stay on the route, and recognize the objective.

a**. Know Where You Are (Step 1).** You must know where you are on the map and on the ground at all times and in every possible way. This includes knowing where you are relative to—

- Your directional orientation.
- The direction and distances to your objective.
- Other landmarks and features.
- Any impassable terrain, the enemy, and danger areas.
- Both the advantages and disadvantages presented by the terrain between you and your objective.

This step is accomplished by knowing how to read a map, recognize and identify specific terrain and other features; determine and estimate direction; pace, measure, and estimate distances, and both plot and estimate a position by resection.

b**. Plan the Route (Step 2)**. Depending upon the size of the unit and the length and type of movement to be conducted, several factors should be considered in selecting a good route or routes to be followed. These include—

- Travel time.
- Travel distance.
- Maneuver room needed.
- Trafficability.
- Load-bearing capacities of the soil.
- Energy expenditure by troops.
- The factors of METT-T.
- Tactical aspects of terrain (OCOKA).
- Ease of logistical support.
- Potential for surprising the enemy.
- Availability of control and coordination features.
- Availability of good checkpoints and steering marks.

In other words, the route must be the result of careful map study and should address the requirements of the mission, tactical situation, and time available. It must also provide for ease of movement and navigation.

(1) Three route-selection criteria that are important for small-unit movements are cover, concealment, and the availability of reliable checkpoint features. The latter is weighted even

more heavily when selecting the route for a night operation. The degree of visibility and ease of recognition (visual effect) are the key to the proper selection of these features.

(2) The best checkpoints are linear features that cross the route. Examples include perennial streams, hard-top roads, ridges, valleys, railroads, and power transmission lines. Next, it is best to select features that represent elevation changes of at least two contour intervals such as hills, depressions, spurs, and draws. Primary reliance upon cultural features and vegetation is cautioned against because they are most likely to have changed since the map was last revised.

(3) Checkpoints located at places where changes in direction are made mark your **decision points**. Be especially alert to see and recognize these features during movement. During preparation and planning, it is especially important to review the route and anticipate where mistakes are most likely to be made so they can be avoided.

(4) Following a valley floor or proceeding near (not on) the crest of a ridgeline generally offers easy movement, good navigation checkpoints, and sufficient cover and concealment. It is best to follow terrain features whenever you can—not to fight them.

(5) A lost or a late arriving unit, or a tired unit that is tasked with an unnecessarily difficult move, does not contribute to the accomplishment of a mission. On the other hand, the unit that moves too quickly and carelessly into a destructive ambush or leaves itself open to air strikes also have little effect. Careful planning and study are required each time a movement route is to be selected.

c. **Stay on the Route (Step 3).** In order to know that you are still on the correct route, you must be able to compare the evidence you encounter as you move according to the plan you developed on the map when you selected your route. This may include watching your compass reading (dead reckoning) or recognizing various checkpoints or landmarks from the map in their anticipated positions and sequences as you pass them (terrain association). A better way is to use a combination of both.

d**. Recognize the Objective (Step 4).** The destination is rarely a highly recognizable feature such as a dominant hilltop or road junction. Such locations as this are seldom missed by the most inexperienced navigators and are often dangerous places for soldiers to occupy. The relatively small, obscure places are most likely to be the destinations.

(1) Just how does a soldier travel over unfamiliar terrain for moderate to great distances and know when he reaches the destination? One minor error, when many are possible, can cause the target to be missed.

(2) The answer is simple. Select a checkpoint (reasonably close to the destination) that is not so difficult to find or recognize. Then plan a short, fine-tuned last leg from the new *expanded objective* to the final destination. For example, you may be able to plan and execute the move as a series of sequenced movements from one checkpoint or landmark to another using both the terrain and a compass to keep you on the correct course. Finally, after arriving at the last checkpoint, you might follow a specific compass azimuth and pace off the relatively short, known distance to the final, pinpoint destination. This procedure is called *point navigation*. A short movement out from a unit position to an observation post or to a coordination point may also be accomplished in the same manner.

11-6. NAVIGATION METHODS

Staying on the route is accomplished through the use of one or two navigation techniques—dead reckoning and terrain association. These methods are discussed in detail below.

a. **Moving by Dead Reckoning.** Dead reckoning consists of two fundamental steps. The first is the use of a protractor and graphic scales to determine the direction and distance from one point to another on a map. The second step is the use of a compass and some means of measuring distance to apply this information on the ground. In other words, it begins with the determination of a polar coordinate on a map and ends with the act of finding it on the ground.

(1) Dead reckoning along a given route is the application of the same process used by a mapmaker as he establishes a measured line of reference upon which to construct the framework of his map. Therefore, triangulation exercises (either resection or intersection) can be easily undertaken by the navigator at any time to either determine or confirm precise locations along or near his route. Between these position-fixes, establish your location by measuring or estimating the distance traveled along the azimuth being followed from the previous known point. You might use pacing, a vehicle odometer, or the application of elapsed time for this purpose, depending upon the situation.

(2) Most dead reckoned movements do not consist of single straight-line distances because you cannot ignore the tactical and navigational aspects of the terrain, enemy situation, natural and man-made obstacles, time, and safety factors. Another reason most dead reckoning movements are not single straight-line distances is because compasses and pace-counts are imprecise measures. Error from them compounds over distance; therefore, you could soon be far afield from your intended route even if you performed the procedures correctly. The only way to counteract this phenomenon is to reconfirm your location by terrain association or resection. Routes planned for dead reckoning generally consist of a series of straight-line distances between several checkpoints with perhaps some travel running on or parallel to roads or trails.

(3) There are two advantages to dead reckoning. First, dead reckoning is easy to teach and to learn. Second, it can be a highly accurate way of moving from one point to another if done carefully over short distances, even where few external cues are present to guide the movements.

(4) During daylight, across open country, along a specified magnetic azimuth, never walk with the compass in the open position and in front of you. Because the compass will not stay steady or level, it does not give an accurate reading when held or used this way. Begin at the start point and face with the compass in the proper direction, then sight in on a landmark that is located on the correct azimuth to be followed. Close the compass and proceed to that landmark. Repeat the process as many times as necessary to complete the straight-line segment of the route.

(5) The landmarks selected for this purpose are called *steering marks*, and their selection is crucial to success in dead reckoning. Steering marks should never be determined from a map study. They are selected as the march progresses and are commonly on or near the highest points that you can see along the azimuth line that you are following when they are selected. They may be uniquely shaped trees, rocks, hilltops, posts, towers, and buildings—anything that can be easily identified. If you do not see a good steering mark to the front, you might use a back azimuth to some feature behind you until a good steering mark appears out in front. Characteristics of a good steering mark are:

(a) It must have some characteristics about it, such as color, shade of color, size, or shape (preferably all four), that will assure you that it will continue to be recognized as you approach it.

(b) If several easily distinguished objects appear along your line of march, the best steering mark is the most distant object. This procedure enables you to travel farther with fewer references to the compass. If you have many options, select the highest object. A higher mark is not as easily lost to sight as is a lower mark that blends into the background as you approach it. A steering mark should be continuously visible as you move toward it.

(c) Steering marks selected at night must have even more unique shapes than those selected during daylight. As darkness approaches, colors disappear and objects appear as black or gray silhouettes. Instead of seeing shapes, you begin to see only the general outlines that may appear to change as you move and see the objects from slightly different angles.

(6) Dead reckoning without natural steering marks is used when the area through which you are traveling is devoid of features, or when visibility is poor. At night, it may be necessary to send a member of the unit out in front of your position to create your own steering mark in order to proceed. His position should be as far out as possible to reduce the number of chances for error as you move. Arm-and-hand signals or a radio may be used in placing him on the correct azimuth. After he has been properly located, move forward to his position and repeat the process until some steering marks can be identified or until you reach your objective.

(7) When handling obstacles/detours on the route, follow these guidelines:

(a) When an obstacle forces you to leave your original line of march and take up a parallel one, always return to the original line as soon as the terrain or situation permits.

(b) To turn clockwise (right) 90 degrees, you must add 90 degrees to your original azimuth. To turn counterclockwise (left) 90 degrees from your current direction, you must subtract 90 degrees from your present azimuth.

(c) When making a detour, be certain that only paces taken toward the final destination are counted as part of your forward progress. They should not be confused with the local pacing that takes place perpendicular to the route in order to avoid the problem area and in returning to the original line of march after the obstacle has been passed.

(8) Sometimes a steering mark on your azimuth of travel can be seen across a swamp or some other obstacle to which you can simply walk out around. Dead reckoning can then begin at that point. If there is no obvious steering mark to be seen across the obstacle, perhaps one can be located to the rear. Compute a back azimuth to this point and later sight back to it once the obstacle has been passed in order to get back on track.

(9) You can use the deliberate offset technique. Highly accurate distance estimates and precision compass work may not be required if the destination or an intermediate checkpoint is located on or near a large linear feature that runs nearly perpendicular to your direction of travel. Examples include roads or highways, railroads, power transmission lines, ridges, or streams. In these cases, you should apply a deliberate error (offset) of about 10 degrees to the azimuth you planned to follow and then move, using the lensatic compass as a guide, in that direction until you encounter the linear feature. You will know exactly which way to turn (left or right) to find your destination or checkpoint, depending upon which way you planned your deliberate offset.

(10) Because no one can move along a given azimuth with absolute precision, it is better to plan a few extra steps than to begin an aimless search for the objective once you reach the linear feature. If you introduce your own mistake, you will certainly know how to correct it. This method will also cope with minor compass errors and the slight variations that always occur in the earth's magnetic field.

(11) There are disadvantages to dead reckoning. The farther you travel by dead reckoning without confirming your position in relation to the terrain and other features, the more errors you will accumulate in your movements. Therefore, you should confirm and correct your estimated position whenever you encounter a known feature on the ground that is also on the map. Periodically, you should accomplish a resection triangulation using two or more known points to pinpoint and correct your position on the map. Pace counts or any type of distance measurement should begin anew each time your position is confirmed on the map.

(a) It is dangerous to select a single steering mark, such as a distant mountaintop, and then move blindly toward it. What will you do if you must suddenly call for fire support or a medical evacuation? You must periodically use resection and terrain association techniques to pinpoint your location along the way.

(b) Steering marks can be farther apart in open country, thereby making navigation more accurate. In areas of dense vegetation, however, where there is little relief, during darkness, or in fog, your steering marks must be close together. This, of course, introduces more chance for error.

(c) Finally, dead reckoning is time-consuming and demands constant attention to the compass. Errors accumulate easily and quickly. Every fold in the ground and detours as small as a single tree or boulder also complicate the measurement of distance.

b. **Moving by Terrain Association**. The technique of moving by terrain association is more forgiving of mistakes and far less time-consuming than dead reckoning. It best suits those situations that call for movement from one area to another. Once an error has been made in dead reckoning, you are off the track. Errors made using terrain association are easily corrected, however, because you are comparing what you expected to see from the map to what you do see on the ground. Errors are anticipated and will not go unchecked. You can easily make adjustments based upon what you encounter. After all, you do not find the neighborhood grocery store by dead reckoning—you adjust your movements according to the familiar landmarks you encounter along the way (Figure 11-8). Periodic position-fixing through either plotted or estimated resection will also make it possible to correct your movements, call for fire, or call in the locations of enemy targets or any other information of tactical or logistical importance.



Figure 11-8. Terrain association navigation.

(1) ***Identifying and Locating Selected Features***. Being able to identify and locate the selected features, both on the map and on the ground, are essential to the success in moving by terrain association. The following rules may prove helpful.

(a) Be certain the map is properly oriented when moving along the route and use the terrain and other features as guides. The orientation of the map must match the terrain or it can cause confusion.

(b) To locate and identify features being used to guide the movement, look for the steepness and shape of the slopes, the relative elevations of the various features, and the directional orientations in relation to your position and to the position of the other features you can see.

(c) Make use of the additional cues provided by hydrography, culture, and vegetation. All the information you can gather will assist you in making the move. The ultimate test and the best practice for this movement technique is to go out in the field and use it. The use of terrain, other natural features, and any man-made objects that appear both on the map and on the ground must be practiced at every opportunity. There is no other way to learn or retain this skill.

(2) ***Using Handrails, Catching Features, and Navigational Attack Points***. First, because it is difficult to dead reckon without error over long distances with your compass, the alert navigator can often gain assistance from the terrain.

(a) **Handrails** are linear features like roads or highways, railroads, power transmission lines, ridgelines, or streams that run roughly parallel to your direction of travel. Instead of using precision compass work, you can rough compass without the use of steering marks for as long as the feature travels with you on your right or left. It acts as a handrail to guide the way.

(b) Second, when you reach the point where either your route or the handrail changes direction, you must be aware that it is time to go your separate ways. Some prominent feature located near this point is selected to provide this warning. This is called a *catching feature*; it can also be used to tell you when you have gone too far.

(c) Third, the catching feature may also be your *navigational attack point*; this point is the place where area navigation ends and point navigation begins. From this last easily identified checkpoint, the navigator moves cautiously and precisely along a given azimuth for a specified distance to locate the final objective. The selection of this navigational attack point is important. A distance of 500 meters or less is most desirable.

(3) ***Recognizing the Disadvantages of Terrain Association***. The major disadvantage to navigation by terrain association is that you must be able to interpret the map and analyze the world around you. Recognition of terrain and other features, the ability to determine and estimate direction and distance, and knowing how to do quick-in-the-head position fixing are skills that are more difficult to teach, learn, and retain than those required for dead reckoning.

c. **Combination of Techniques.** Actually, the most successful navigation is obtained by combining the techniques described above. Constant orientation of the map and continuous observation of the terrain in conjunction with compass-read azimuths, and distance traveled on the ground compared with map distance, used together make reaching a destination more certain. One should not depend entirely on compass navigation or map navigation; either or both could be lost or destroyed.

NOTE: See Appendix F for information on orienteering.

11-7. NIGHT NAVIGATION

Darkness presents its own characteristics for land navigation because of limited or no visibility. However, the techniques and principles are the same as that used for day navigation. The success in nighttime land navigation depends on rehearsals during the planning phase before the movement, such as detailed analysis of the map to determine the type of terrain in which the navigation is going to take place and the predetermination of azimuths and distances. Night vision devices (Appendix H) can greatly enhance night navigation.

a. The basic technique used for nighttime land navigation is dead reckoning with several compasses recommended. The point man is in front of the navigator but just a few steps away for easy control of the azimuth. Smaller steps are taken during night navigation, so remember, the pace count is different. It is recommended that a pace count obtained by using a predetermined 100-meter pace course be used at night.

b. Navigation using the stars is recommended in some areas; however, a thorough knowledge of constellations and location of stars is needed (paragraph 9-5c). The four cardinal directions can also be obtained at night by using the same technique described for the shadow-tip method. Just use the moon instead of the sun. In this case, the moon has to be bright enough to cast a shadow.

CHAPTER 12

MOUNTED LAND NAVIGATION

A vehicle commander should be able to navigate from one point on the ground to another with or without a compass. If separated from his unit and given an azimuth and distance from their position to his, he should be able to reach the unit and continue the mission. To move effectively while mounted, he must know the principles of mounted navigation.

12-1. PRINCIPLES

The principles of land navigation while mounted are basically the same as while dismounted. The major difference is the speed of travel. Walking between two points may take one hour, but riding the same distance may only take 15 minutes. To be effective at mounted land navigation, the travel speed must be considered.

12-2. NAVIGATOR'S DUTIES

The duties of a navigator are so important and exacting that he should not be given any other duties. The leader should never try to be the navigator, since his normal responsibilities are heavy, and one or the other job would suffer.

a. **Assembling Equipment.** The navigator must gather all the equipment that will help him perform his job (maps, pencils, and so forth). He must do this before the mission starts.

b. **Servicing Equipment.** It is the navigator's duty to make sure that all the equipment he may use or require is working.

c. **Recording Data for Precise Locations.** During movement, the navigator must make sure that the correct direction and distance are recorded and followed. Grid coordinates of locations must be recorded and plotted.

d. **Supplying Data to Subordinate Leaders**. During movement, any change in direction or distance must be given to the subordinate leaders in sufficient time to allow them to react.

e. **Maintaining Liaison with the Commander.** The commander normally selects the route that he desires to use. The navigator is responsible for following that route; however, there may be times when the route must be changed during a tactical operation. For this reason, the navigator must maintain constant communication with the commander. The navigator must inform the commander when checkpoints are reached, when a change in direction of movement is required, and how much distance is traveled.

12-3. MOVEMENT

When preparing to move, the effects of terrain on navigating mounted vehicles must be determined. You will cover great distances very quickly, and you must develop the ability to estimate the distance you have traveled. Remember that 0.1 mile is roughly 160 meters, and 1 mile is about 1,600 meters or 1.6 kms. Having a mobility advantage helps while navigating. Mobility makes it much easier if you get disoriented to move to a point where you can reorient yourself.

NOTE: To convert kmph to mph, multiply by .62. (9 kmph x .62 = 5.58 mph). To convert mph to kmph, divide mph by .62 (10 mph ÷ 0.62 = 16.12 kmph).

a. **Consider Vehicle Capabilities.** When determining a route to be used when mounted, consider the capabilities of the vehicles to be used. Most military vehicles are limited in the degree of slope they can climb and the type of terrain they can negotiate. Swamps, thickly wooded areas, or deep streams may present no problems to dismounted soldiers, but the same terrain may completely stop mounted soldiers. The navigator must consider this when selecting a route.

(1) Most vehicles will knock down a tree. The bigger the vehicle, the bigger the tree it can knock down. Vehicles cannot knock down several trees at once. It is best to find paths between trees that are wide enough for your vehicle. Military vehicles are designed to climb 60 percent slopes on a dry, firm surface (Figure 12-1).

(2) You can easily determine approximate slope; just look at the route you have selected. If there is a contour line in any 100 meters of map distance on that route, it is a 10 percent slope. If there are two contour lines, it is 20 percent, and so forth. If there are four contour lines in any 100 meters, look for another route.

(3) Side slope is even more important than the slope you can climb. Normally, a 30 percent slope is the maximum in good weather. If you traverse a side slope, do it slowly and without turns. Rocks, stumps, or sharp turns can cause you to throw the downhill track under the vehicle, which would mean a big recovery task.

(4) For tactical reasons, you will often want to move in draws or valleys because they give you cover. However, side slopes force you to move slowly.

NOTE: The above figures are true for a 10-meter or a 20-foot contour interval. If the map has a different contour interval, just adjust the arithmetic. For instance, with one contour line in 100 meters, a 20-meter interval would give a 20 percent slope.

b**. Know the Effects of Weather on Vehicle Movement.** Weather can halt mounted movement. Snow and ice are obvious dangers, but more significant is the effect of rain and snow on soil load-bearing ability. Cross-country vehicles may be restricted to road movement in heavy rain. If it has rained recently, adjust your route to avoid flooded or muddy areas. A mired vehicle only hinders combat capability.

c. **Prepare Before Movement.** Locate the start point and finish point on the map. Determine the map's grid azimuth from start point to finish point and convert it to a magnetic azimuth. Determine the distance between the start point and finish point or any intermediate points on the map and make a thorough map reconnaissance of that area.



Figure 12-1. Tracked vehicle capabilities.

12-4. TERRAIN ASSOCIATION NAVIGATION

This is currently the most widely used method of navigation. The navigator plans his route so that he moves from terrain feature to terrain feature. An automobile driver in a city uses this technique as he moves along a street or series of streets, guiding on intersections or features such as stores and parks. Like the driver, the navigator selects routes or *streets* between key points or *intersections*. These routes must be capable of sustaining the travel of the vehicle or vehicles, should be relatively direct, and should be easy to follow. In a typical move, the navigator determines his location, determines the location of his objective, notes the position of both on his map, and then selects a route between the two. After examining the terrain, he adjusts the route by the following actions:

a**. Consider Tactical Aspects.** Avoid skylining, select key terrain for overwatch positions, and select concealed routes.

b. **Consider Ease of Movement.** Use the easiest possible route and bypass difficult terrain. Remember that a difficult route is harder to follow, is noisier, causes more wear and tear (and possible recovery problems), and takes more time. Tactical surprise is achieved by doing the unexpected. Try to select an axis or corridor instead of a specific route. Make sure you have enough maneuver room for the vehicles (Figure 12-2).


CLASSIFICATION
N
OBJECTIVE
84
11
LEG 4
AZ 14° DIST. .9K
CP3
AZ 330° DIST. 4.1K
LEG 3
CP2
LEG 2
AZ 76° DIST. 1.7K
CP1
LEG 1
AZ 52° DIST. 6.7K
START POINT
CLASSIFICATION
TITLE:
MAP REFERENCE
SHEET NAME:
SHEET NUMBER:
MAP SERIES NO:
SCALE:
PREPARED BY
NAME AND RANK:
ORGANIZATION:
DATE;
LEGEND:
NOTE: ALL AZIMUTHS IN THIS ARE GRID
03
75
CLASSIFICATION

Figure 12-2. Primary route.

c. **Use Terrain Features as Checkpoints.** These checkpoints must be easily recognizable in the light and weather conditions and at the speed at which you will move. You should be able to find a terrain feature from your location that can be recognized from almost anywhere and used as a guide. An example is checkpoint 2, the church, and checkpoint 3, the orchard, in Figure 12-2.

(1) The best checkpoints are linear features that cross your route. Use streams, rivers, hard-top roads, ridges, valleys, and railroads.

(2) The next best checkpoints are elevation changes, such as hills, depressions, spurs, and draws. Look for two contour lines of change. You will not be able to spot less than two lines of change while mounted.

(3) In wooded terrain, try to locate checkpoints at no more than 1,000-meter intervals. In open terrain, you may go to about 5,000 meters.

d. **Follow Terrain Features.** Movement and navigation along a valley floor or near (not necessarily on) the crest of a ridgeline is easiest.

e. **Determine Directions.** Break the route down into smaller segments and determine the rough directions that will be followed. You do not need to use the compass; just use the main points of direction (north, northeast, east, and so forth). Before moving, note the location of the sun and locate north. Locate changes of direction, if any, at the checkpoints picked.

f. **Determine Distance.** Get the total distance to be traveled and the approximate distance between checkpoints. Plan to use the vehicle odometer to keep track of distance traveled. Use the pace-count method and keep a record of the distance traveled. When using a pace count, convert from map distance to ground distance by adding the conversion factors of 20 percent for cross-country movement.

g. **Make Notes.** Mental notes are usually adequate. Try to imagine what the route is like and remember it.

h. **Plan to Avoid Errors**. Restudy the route selected. Try to determine where errors are most apt to occur and how to avoid any trouble.

i. **Use a Logbook.** When the routes have been selected and the navigator has divided the distance to be traveled into legs, prepare a logbook. The logbook is an informal record of the distance and azimuth of each leg, with notes to aid the navigator in following the correct route. The notes list easily identifiable terrain features at or near the point where the direction of movement changes (Figure 12-3, page 12-6).



ODOMETER READING AT START	ODOMETER READING AT FINISH	DISTANCE IN MILES	AZIMUTH	DEVIATION CORRECTION	NOTES

SAMPLE FORMAT

Figure 12-3. Sample of a logbook format.

12-5. DEAD RECKONING NAVIGATION

Dead reckoning is moving a set distance along a set line. Generally, it involves moving so many meters along a set line, usually an azimuth in degrees. There is no accurate method of determining a direction in a moving vehicle. A magnetic vehicle-heading reference unit may be available in a few years; for now, use a compass.

a. **With Steering Marks.** This procedure is the same for vehicle travel as on foot.

(1) The navigator dismounts from the vehicle and moves away from the vehicle (at least 18 meters).

(2) He sets the azimuth on the compass and picks a steering mark (rock, tree, hilltop) in the direction on that azimuth (Figure 12-4).

(3) He remounts and has the driver identify the steering mark and proceeds to it in as straight a line as possible.

(4) On arrival at the steering mark or on any changes in direction, he repeats the first three steps above for the next leg of travel.



Figure 12-4. Determining an azimuth, dismounted.

b. **Without Steering Marks.** This procedure is used only on flat, featureless terrain.

(1) The navigator dismounts from the vehicle, which is oriented in the direction of travel, and moves at least 18 meters to the front of the vehicle.

(2) He faces the vehicle and reads the azimuth to the vehicle. By adding or subtracting 180º, he determines the forward azimuth (direction of travel).

(3) On order from the navigator, the driver drives on a straight line to the navigator.

(4) The navigator remounts the vehicle, holds the compass as it will be held while the vehicle is moving, and reads the azimuth in the direction of travel.

(5) The compass will swing off the azimuth determined and pick up a constant deviation. For instance, say the azimuth was 75º while you were away from the vehicle. When you remounted and your driver drove straight forward, your compass showed 67º. You have a deviation of -8º. All you need to do is maintain that 67º compass heading to travel on a 75º magnetic heading.

(6) At night, the same technique can be used. From the map, determine the azimuth you are to travel. Convert the grid azimuth to a magnetic azimuth. Line the vehicle up on that azimuth, then move well in front of it. Be sure it is aligned correctly. Then mount, have the driver move slowly forward, and note the deviation. If the vehicle has a turret, the above procedure works unless you traverse the turret; this changes the deviation.

(7) The distance factor in dead reckoning is easy. Just determine the map distance to travel and add 20 percent to convert to ground distance. Use your vehicle odometer to be sure you travel the proper distance.

12-6. STABILIZED TURRET ALIGNMENT NAVIGATION

Another method, if you have a vehicle with a stabilized turret, is to align the turret on the azimuth you wish to travel, then switch the turret stabilization system on. The gun tube remains pointed at your destination no matter which way you turn the vehicle. This technique has been proven; it works. It is not harmful to the stabilization system. It is subject to stabilization drift, so use it for no more than 5,000 meters before resetting.

NOTE: If you have to take the turret off-line to engage a target, you will have to start all over, re-do the entire process.

12-7. COMBINATION NAVIGATION

Some mounted situations may call for you to combine and use both methods. Just remember the characteristics of each.

a. Terrain association is fast, is error-tolerant, and is best under most circumstances. It can be used day or night if you are proficient in it.

b. Dead reckoning is very accurate if you do everything correctly. You must be very precise. It is also slow, but it works on very flat terrain.

c. You frequently will combine both. You may use dead reckoning to travel across a large, flat area to a ridge, then use terrain association for the rest of the move.

d. You must be able to use both methods. You should remember that your probable errors, in order of frequency, will be—

- Failure to determine distance(s) to be traveled.
- Failure to travel the proper distance.
- Failure to properly plot or locate the objective.
- Failure to select easily recognized checkpoints or landmarks.
- Failure to consider the ease of movement factor.

CHAPTER 13

NAVIGATION IN DIFFERENT TYPES OF TERRAIN

The information, concepts, and skills already presented will help you to navigate anywhere in the world; however, there are some special considerations and helpful hints that may assist you in various special environments. The following information is not doctrine.

13-1. DESERT TERRAIN

About 5 percent of the earth's land surface is covered by deserts (Figure 13-1). Deserts are large arid areas with little or no rainfall during the year. There are three types of deserts—mountain, rocky plateau, and sandy or dune deserts. All types of forces can be deployed in the desert. Armor and mechanized infantry forces are especially suitable to desert combat except in rough mountainous terrain where light infantry may be required. Airborne, air assault, and motorized forces can also be advantageously employed to exploit the vast distances characteristic of desert warfare.



Figure 13-1. Deserts.

a. **Desert Regions.** In desert regions, terrain varies from nearly flat to lava beds and salt marshes. Mountain deserts contain scattered ranges or areas of barren hills or mountains. Table 13-1, on page 13-2, lists some of the world's major desert regions and their locations.

REGION	LOCATION
Sahara	North Africa
Kalahari	Southwest Africa
Arabian	Southwest Asia
Gobi	Mongolia and Northern China
Rub'al Khali	South Arabia
Great Basin, Colorado, Chihuahua, Yuma Sonoran, and Mohave	Northern Mexico and Western United States
Takla Makan	Northern China
Kyzyl Kum	Southwest USSR
Kara Kum	Southwest USSR
Syrian	Saudi Arabia, Jordan, and Iraq
Great Victoria	Western and South Australia
Great Sandy	Northwestern Australia
Patagonia	Southern Argentina and Chile
Atacama	Northern Chile

Table 13-1. Major desert regions.

(1) Finding the way in a desert presents some degree of difficulty for a person who has never been exposed to this environment. Desert navigators have learned their way through generations of experience.

(2) Normally, desert people are nomadic, constantly moving in caravans. Navigating becomes second nature to them. Temperature in the tropical deserts reaches an average of 110° to 115° during the day, so most navigation takes place at night using the stars. Most deserts have some prevailing winds during the seasons. Such winds arrange the sand dunes in a specific pattern that gives the navigator the opportunity to determine the four cardinal directions. He may also use the sun's shadow-tip method.

(3) A sense of direction can be obtained by watching desert animals on their way to and from water holes (oases). Water, navigation, and survival are closely related in desert areas. Most deserts have pigeons or doves, and their drinking habits are important to the navigator. As a rule, these birds never drink in the morning or during the day, making their evening flights the most important. When returning from the oases, their bodies are heavier from drinking and their flight is accompanied by a louder flapping of their wings.

(4) Visibility is also an important factor in the desert, especially in judging distance. The absence of trees or other features prevents comparison between the horizon and the skyline.

b. **Interpretation and Analysis.** Many desert maps are inaccurate, which makes up-to-date air, aerial photo, and ground reconnaissance necessary. In desert mountain areas contour intervals are generally large, so many of the intermediate relief features are not shown.

(1) The desert normally permits observation and fire to maximum ranges. The terrain is generally wide open and the exceptionally clear atmosphere offers excellent long-range

visibility. Combine this with a powerful sun and low cloud density and you have nearly unlimited light and visual clarity, which often contribute to gross underestimations of ranges. Errors of up to 200 or 300 percent are not uncommon. However, visibility conditions may be severely affected by sandstorms and mirages (heat shimmer caused by air rising from the extremely hot daytime desert surface), especially if the observer is looking into the sun through magnifying optical instruments.

(2) Cover can be provided only by terrain feature masking because of the lack of heavy vegetation and man-made objects. It only takes a few meters of relief to provide cover. Concealment in the desert is related to the following factors:

(a) *Shape*. In order not to be observed by the enemy, attempt to alter the standard shapes of vehicles so they and their shadows are not instantly recognized.

(b) *Shine*. Shine or glitter is often the first thing that attracts the observer's eye to movement many kilometers away. It must be eliminated.

(c) *Color and texture*. All equipment should either be pattern painted or mudded to blend in with the terrain.

(d) *Light and noise*. Light and noise discipline are essential because sound and light travel great distances in the desert.

(e) *Heat*. Modern heat image technology makes shielding heat sources an important consideration when trying to hide from the enemy. This technology is especially important during night stops.

(f) *Movement*. Movement itself creates a great deal of noise and dust, but a rapid execution using all the advantages the topography offers can help conceal it.

c. *Navigation*. When operating in the broad basins between mountain ranges or on rocky plateau deserts, there are frequently many terrain features to guide your movement by. But, observing these known features over great distances may provide a false sense of security in determining your precise location unless you frequently confirm your location by resection or referencing close-in terrain features. It is not uncommon to develop errors of several kilometers when casually estimating a position in this manner. Obviously, this can create many problems when attempting to locate a small checkpoint or objective, calling for CAS, reporting operational or intelligence information, or meeting CSS requirements.

(1) When operating in an area with few visual cues, such as in a sandy or dune desert, or restricted visibility by a sandstorm or darkness, you must proceed by dead reckoning. The four steps and two techniques for navigation presented earlier remain valid in the desert. However, understanding the special conditions found there are extremely helpful as you apply them.

(2) Tactical mobility and speed are key to successful desert operations. Obstacles and areas such as lava beds or salt marshes, which preclude surface movements, do exist. But most deserts permit two-dimensional movement by ground forces similar to that of a naval task force at sea. Speed of execution is essential. Everyone moves farther and faster on the desert. Special navigation aids sometimes used in the desert include:

(a) *Sun compass*. It can be used on moving vehicles and sextants. It requires accurate timekeeping. However, the deviation on a magnetic compass that is caused by the metal and electronics in the vehicle is usually less than +10°.

(b) *Gyro compass*. The gun azimuth stabilizer is in fact a gyro compass. If used on fairly flat ground, it is useful for maintaining direction over limited distances.

(c) *Fires*. Planned tracer fire or mortar and artillery concentrations (preferably smoke during the day and illumination at night) provide useful checks on estimated locations.

(d) *Prepositioned lights*. This method consists of placing two or more searchlights far apart, behind the line of contact, beyond enemy artillery range, and concealed from enemy ground observation. Units in the area can determine their own locations through resection, using the vertical beams of the lights. These lights must be moved on a time schedule known to all friendly units.

(3) One final note on desert navigation is that the sand, hard-baked ground, rocky surfaces, thorny vegetation, and heat generally found in the desert impose far greater demands for maintenance than you would plan for in temperate regions. It may also take longer to perform that maintenance.

13-2. MOUNTAIN TERRAIN

Mountains are generally understood to be larger than hills. Rarely do mountains occur individually; in most cases, they are found in elongated ranges or circular groups. When they are linked together, they constitute a mountain system (Figure 13-2). Light forces (infantry, airborne, and air assault forces) can operate effectively in mountainous regions because they are not terrain limited. Heavy forces must operate in passes and valleys that are negotiable by vehicle.



Figure 13-2. Mountain systems.

a. **Major Systems**. Major systems are listed in Table 13-2.

SYSTEM	LOCATION
The Andes	Central and South America
The Rockies	North America (USA-Canada)
The Appalachians	North America (USA-Canada)
The Alps	Central Europe
The Himalayas	Asia
The Caucasus	Western Asia and Europe (Russia)

Table 13-2. Major systems.

b. **Minor Systems.** Some other systems are in Antarctica, Hawaii, Japan, New Zealand, and Oceania. Mountain systems are characterized by high, inaccessible peaks and steep slopes. Depending on the altitude, they may be snow covered. Prominent ridges and large valleys are also found. Navigating in this type of terrain is not difficult providing you make a careful examination of the map and the terrain.

c. **Climate.** Because of the elevations, it is always colder (3° to 5° per 300-meter gain in altitude) and wetter than you might expect. Wind speeds can increase the effects of the cold even more. Sudden severe storms and fog are encountered regularly. Below the tree line, vegetation is heavy because of the extra rainfall and the fact that the land is rarely cleared for farming.

d. **Interpretation and Analysis.** The heights of mountainous terrain permit excellent long-range observation. However, rapidly fluctuating weather with frequent periods of high winds, rain, snow, or fog may limit visibility. Also, the rugged nature of the terrain frequently produces significant dead space at mid-ranges.

(1) Reduced mobility, compartmented terrain, and the effects of rapidly changing weather increase the importance of air, ground, aerial photo, and map reconnaissance. Since mountain maps often use large contour intevals, microrelief interpretation and detailed terrain analysis require special emphasis.

(2) At first glance, some mountainous terrain may not appear to offer adequate cover and concealment; however, you can improve the situation. When moving, use rock outcroppings, boulders, and heavy vegetation for cover and concealment; use terrain features to mask maneuvers. Use harsh weather, which often obscures observation, to enhance concealment.

(3) Since there are only a few routing options, all-round security must be of primary concern. Natural obstacles are everywhere, and the enemy can easily construct more.

e. **Navigation.** Existing roads and trails offer the best routes for movement. Off-road movement may enhance security provided there is detailed reconnaissance, photo intelligence, or information from local inhabitants to ensure the route is negotiable. Again, the four steps and two techniques for navigation presented earlier remain valid in the mountains. Nevertheless, understanding the special conditions and the terrain will help you navigate. Other techniques that are sometimes helpful in mountains are:

(1) ***Aspect of Slope***. To determine the aspect of slope, take a compass reading along an imaginary line that runs straight down the slope. It should cut through each of the contour lines at about a 90° angle. By checking the map and knowing the direction of slope where you are located, you will be able to keep track of your location, and it will help guide your cross-country movement even when visibility is poor.

(2) ***Use of an Altimeter***. Employment of an altimeter with calibrations on the scale down to 10 or 20 meters is helpful to land navigators moving in areas where radical changes in elevation exist. An altimeter is a type of barometer that gauges air pressure, except it measures on an adjustable scale marked in feet or meters of elevation rather than in inches or centimeters of mercury. Careful use of the altimeter helps to pinpoint your position on a map through a unique type of resection. Instead of finding your position by using two different directional values, you use one directional value and one elevation value.

13-3. JUNGLE TERRAIN

These large geographic regions are found within the tropics near the equator (Central America, along the Amazon River, South-Eastern Asia and adjacent islands, and vast areas in the middle of Africa and India) (Figure 13-3). Jungles are characterized as rainy, humid areas with heavy layers of tangled, impenetrable vegetation. Jungles contain many species of wildlife (tigers, monkeys, parrots, snakes, alligators, and so forth). The jungle is also a paradise for insects, which are the worst enemy of the navigator because some insects carry diseases (malaria, yellow fever, cholera, and so forth). While navigating in these areas, very little terrain association can be accomplished because of the heavy foliage. Dead reckoning is one of the methods used in these areas. A lost navigator in the jungle can eventually find his way back to civilization by following any body of water with a downstream flow. However, not every civilization found is of a friendly nature.



Figure 13-3. Jungles and savannas.

a. **Operations.** Operations in jungles tend to be isolated actions by small forces because of the difficulties encountered in moving and in maintaining contact between units. Divisions can move cross-country slowly; but, aggressive reconnaissance, meticulous intelligence collection, and detailed coordination are required to concentrate forces in this way. More commonly, large forces operate along roads or natural avenues of movement, as was the case in the mountains. Patrolling and other surveillance operations are especially important to ensure security of larger forces in the close terrain of jungles.

(1) Short fields of observation and fire, and thick vegetation make maintaining contact with the enemy difficult. The same factors reduce the effectiveness of indirect fire and make jungle combat primarily a fight between infantry forces. Support by air and mechanized forces can be decisive at times, but it will not always be available or effective.

(2) Jungles are characterized by high temperatures, heavy rains, high humidity, and an abundance of vegetation. The climate varies with location. Close to the equator, all seasons are nearly alike with heavy rains all year. Farther from the equator (India and Southeast Asia), there are distinct wet (monsoon) and dry seasons. Both zones have high temperatures (averaging 75 to 95+ degrees Fahrenheit), heavy rainfall (as much as 400+ inches annually, and high humidity (90 percent) all year.

(3) In temperate climates, it is the areas of vegetation that are most likely to be altered and incorrectly portrayed on a map. In jungle areas, the vegetation grows so rapidly that it is more likely to be cleared and make these areas be shown incorrectly.

b. **Interpretation and Analysis.** The jungle environment includes dense forests, grasslands, swamps, and cultivated areas. Forests are classified as primary and secondary based upon the terrain and vegetation. Primary forests include tropical rain forests and deciduous forests. Secondary forests are found at the edges of both rain forests and deciduous forests and in areas where jungles have been cleared and abandoned. These places are typically overgrown with weeds, grasses, thorns, ferns, canes, and shrubs. Movement is especially slow and difficult. The extremely thick vegetation reaches a height of 2 meters and severely limits observation to only a few meters.

(1) Tropical rain forests consist mostly of large trees whose branches spread and lock together to form canopies. These canopies, which can exist at two and three different levels, may form as low as 10 meters from the ground. They prevent direct sunlight from reaching the ground, causing a lack of undergrowth on the jungle floor. Extensive above-ground root systems and hanging vines are common and make vehicular travel difficult; foot movement is easier. Ground observation is limited to about 50 meters and air observation is nearly impossible.

(2) Deciduous forests are in semitropical zones that have both wet and dry seasons. In the wet season, trees are fully leaved; in the dry season, much of the folliage dies. Trees are usually less dense than in rain forests, which allows more sunlight to filter to the ground. This procedure produces thick undergrowth. During the wet season, air and ground observation is limited and movement is difficult. During the dry season, both improve.

(3) Swamps are common to all low, jungle areas where there is poor drainage. When navigating in a swampy area, a careful analysis of map and ground should be taken before any movement. The soldiers should travel in small numbers with only the equipment required for their mission, keeping in mind that they are going to be immersed in water part of the time. The usual technique used in swamp navigation is dead reckoning. There are two basic types of swamps—mangrove and palm. Mangrove swamps are found in coastal areas wherever tides influence water flow. Mangrove is a shrub-like tree that grows 1 to 5 meters high. These trees have a tangled root system, both above and below the waterline, which

restricts movement either by foot or small boat. Observation on the ground and from the air is poor, but concealment is excellent.

(4) Grassy plains or savannas are generally located away from the equator but within the tropics. These vast land areas are characterized by flatlands with a different type of vegetation than jungles. They consist mainly of grasses (ranging from 1 to more than 12 feet in height), shrubs, and isolated trees. The most difficult areas to navigate are the ones surrounded by tall grass (elephant grass); however, vehicles can negotiate here better than in some areas. There are few or no natural features to navigate by, making dead reckoning or navigation by stars the only technique for movement (Figure 13-3). Depending on the height of the grass, ground observation may vary from poor to good. Concealment from air observation is poor for both soldiers and vehicles.

(5) Bamboo stands are common throughout the tropics. They should be bypassed whenever possible. They are formidable obstacles for vehicles, and soldier movement through them is slow, exhausting, and noisy.

(6) Cultivated areas exist in jungles also. They range from large, well-planned, well-managed farms and plantations to small tracts, cultivated by farmers. The three general types of cultivated areas are rice paddies, plantations, and small farms.

c. **Navigation.** Areas such as jungles are generally not accurately mapped because heavy vegetation makes aerial surveys difficult. The ability to observe terrain features, near or far, is extremely limited. The navigator must rely heavily upon his compass and the dead reckoning technique when moving in the jungle. Navigation is further complicated by the inability to make straight-line movements. Terrain analysis, constant use of the compass, and an accurate pace count are essential to navigation in this environment.

(1) Rates of movement and pace counts are particularly important to jungle navigators. The most common error is to overestimate the distance traveled. The distances below can be used as a rough guide for the maximum distances that might be traveled in various types of terrain during one hour in daylight.

Type of Terrain	Maximum Distance (In Meters)
Tropical rain forest	up to 1,000
Deciduous forest	500
Secondary jungle	100 to 500
Tall grass	500
Swamps	100 to 300
Rice paddies (wet)	800
Rice paddies (dry)	2,000
Plantations	2,000
Trails	up to 3,000

Table 13-3. Guide for maximum distance.

(2) Special navigation strategies that are helpful in jungles include:

(a) Personal pace table. You should either make a mental or written personal pace table that includes your average pace count per 100 meters for each of the types of terrain through which you are likely to navigate.

(b) Resection using indirect fire. Call for mortar or artillery fire (airbursts of white phosphorous or illumination) on two widely separated grids that are not on terrain features like the one you are occupying and are a safe distance from your estimated location. Directions to the airbursts sometimes must be determined by sound.

(c) Modified area/point navigation. Even when making primary use of the compass for dead reckoning, you are frequently able to area navigate to an expanded objective, which is easily identified by terrain association. Then, simply develop a short, point-navigation leg to your final destination.

13-4. ARCTIC TERRAIN

Arctic terrain includes those areas that experience extended periods of below freezing temperatures. In these areas, the ground is generally covered with ice or snow during the winter season. Although frozen ground and ice can improve trafficability, a deep accumulation of snow can reduce it. Vehicles and personnel require special equipment and care under these adverse conditions.

a. **Operations.** Both the terrain and the type and size of unit operations vary greatly in arctic areas. In open terrain, armored and mechanized forces will be effective although they will have to plan and train for the special conditions. In broken terrain, forests, and mountains, light forces will predominate as usual. However, foot movement can take up to five times as long as it might under warmer conditions.

b. **Interpretation and Analysis.** Both the terrain and cultural features you may confront in winter may vary to any extreme, as can the weather. The common factor is an extended period of below-freezing temperatures. The terrain may be plains, plateaus, hills, or mountains. The climate will be cold, but the weather will vary greatly from place to place. Most arctic terrain experiences snow, but some claim impressive accumulations each season, such as the lake-effected snow belts off Lake Ontario near Fort Drum, New York. Other areas have many cold days with sunshine and clear nights, and little snow accumulation.

(1) In areas with distinct local relief and scattered trees or forests, the absence of foliage makes movement by terrain association easier; observation and fields of fire are greatly enhanced except during snowstorms. But in relatively flat, open areas covered with snow (especially in bright sunlight), the resulting lack of contrast may interfere with your being able to read the land. With foliage gone, concealment (both from the ground and from the air) is greatly reduced. As in desert areas, you must make better use of the terrain to conceal your movements.

(2) Frozen streams and swamps may no longer be obstacles, and thus identification of avenues of approach may be difficult in winter. However, the concept as to what is key terrain is not likely to be affected.

c. **Navigation.** Special skills may be required in arctic terrain, such as the proper use of winter clothing, skis, and snowshoes; but this does not affect your navigation strategies. There are no special techniques for navigating in arctic terrain. Just be aware of the advantages and disadvantages that may present themselves and make the most of your opportunities while applying the four steps and two techniques for land navigation.

(1) Remember, the highest caliber of leadership is required to ensure that all necessary tasks are performed, that security is maintained, and that soldiers and their equipment are protected from the physical effects of very low temperatures. There is a great temptation to do less than a thorough job at whatever the task may be when you are very cold.

(2) Night navigation may be particularly enhanced when operating in arctic terrain. Moonlight and starlight on a clear night reflect off the snow, thus enabling you to employ daytime terrain association techniques with little difficulty. Even cloudy winter nights are often brighter than clear moonlit summer nights when the ground is dark and covered with foliage. Movements with complete light discipline (no black-out drives) can often be executed. On the other hand, areas with severe winter climates experience lengthy periods of darkness each day, which may be accompanied by driving snow and limited visibility.

13-5. URBAN AREAS

The world continues to become more urbanized each year; therefore, it is unlikely that all fighting will be done in rural settings. Major urban areas represent the power and wealth of a particular country in the form of industrial bases, transportation complexes, economic institutions, and political and cultural centers. Therefore, it may be necessary to secure and neutralize them. When navigating in urban places, it is man-made features, such as roads, railroads, bridges, and buildings that become important, while terrain and vegetation become less useful.

a. **Interpretation and Analysis.** Military operations on urbanized terrain require detailed planning that provides for decentralized execution. As a result of the rapid growth and changes occurring in many urban areas, the military topographic map is likely to be outdated. Supplemental use of commercially produced city maps may be helpful, or an up-to-date sketch can be made.

(1) Urbanized terrain normally offers many AAs for mounted maneuver well forward of and leading to urban centers. In the proximity of these built-up areas, however, such approach routes generally become choked by urban sprawl and perhaps by the nature of adjacent natural terrain. Dismounted forces then make the most of available cover by moving through buildings and underground systems, along edges of streets, and over rooftops. Urban areas tend to separate and isolate units, requiring the small-unit leader to take the initiative and demonstrate his skill in order to prevail.

(2) The urban condition of an area creates many obstacles, and the destruction of many buildings and bridges as combat power is applied during a battle further limits your freedom of movement. Cover and concealment are plentiful, but observation and fields of fire are greatly restricted.

b. **Navigation.** Navigation in urban areas can be confusing, but there are often many cues that will present themselves as you proceed. They include streets and street signs; building styles and sizes; the urban geography of industrial, warehousing, residential housing, and market districts; man-made transportation features other than streets and roads (rail and trolley lines); and the terrain features and hydrographic features located within the built-up area. Strategies for staying on the route in an urban area include:

(1) ***Process Route Descriptions***. Write down or memorize the route through an urban area as a step-by-step process. For example, "Go three blocks north, turn left (west) on a wide divided boulevard until you go over a river bridge. Turn right (north) along the west bank of the river, and. . . "

(2) ***Conceptual Understandings of the Urban Area***. While studying the map and operating in a built-up area, work hard to develop an understanding (mental map) of the entire area. This advantage will allow you to navigate over multiple routes to any location.

It will also preclude your getting lost whenever you miss a turn or are forced off the planned route by obstacles or the tactical situation.

(3) ***Resection***. Whenever you have a vantage point to two or more known features portrayed on the map, do not hesitate to use either estimated or plotted resection to pinpoint your position. These opportunities are often plentiful in an urban setting.

CHAPTER 14

UNIT SUSTAINMENT

Land navigation is a skill that is highly perishable. The soldier must continually make use of the skills he has acquired to remain proficient in them. The institution is responsible for instruction in the basic techniques of land navigation. The institution tests these skills each time a soldier attends a leadership course. However, it is the unit's responsibility to develop a program to maintain proficiency in these skills between institution courses. The unit sustainment program provides training that builds on and reinforces the skills the soldier learned in the institution. It should use the building-block approach to training: basic map reading instruction or review, instruction on land navigation skills, dead reckoning training, dead reckoning practice, terrain association training, terrain association practice, land navigation testing, and building of leader skills. These leader skills should include following a route selected by the commander and planning and following a route selected by the leader. The unit trainer should be able to set up a sustainment program, a train-the-trainer program, and a land navigation course for his unit's use. It is recommended that units develop a program similar to the one outlined in this chapter. Complete lesson outlines and training plans are available by writing to Commander, 29th Infantry Regiment, ATTN: ATSH-INB-A, Fort Benning, GA 31905-5595.

14-1. SET UP A SUSTAINMENT PROGRAM

The purpose of setting up a sustainment program in the unit is to provide soldiers with training that reinforces and builds on the training that they have received in the institution. All soldiers should receive this training at least twice a year. The program also provides the unit with a means of identifying the areas in which the soldiers need additional training.

a. **Training Guidance**. The unit commander must first determine the levels of proficiency and problems that his unit has in land navigation. This determination can be done through after-action reports from the unit's rotations to NTC/JRTC, ARTEP final reports, feedback from his subordinates, personal observation, and annual training. Once the unit commander decides where his training time should be concentrated, he can issue his training guidance to his subordinate leaders. He also directs his staff to provide training sites, resources, and time for the units to train land navigation. It is recommended that land navigation be trained separately, not just included as a subtask in tactical training.

b. **Certification**. The unit commander must also provide his subordinate commanders with a means of certifying training. The unit staff must provide subject matter experts to ensure the training meets the standards decided upon by the unit commander. Instructors should be certified to instruct, and courses should be certified before the unit uses it.

c. **Program Development**. The sustainment program should meet the requirements of all of the unit's soldiers. It should address all skills from basic map reading to leaders' planning and executing a route. The program should cover the following:

- Diagnostic examination.
- Map reading instruction/review.

- Land navigation skills training.
- Dead reckoning training/practice.
- Terrain association training/practice.
- Land navigation written/field examination.
- Leaders' training and testing.

The sustainment program should be developed and then maintained in the unit's training files. The program should be developed in training modules so that it can be used as a whole program or used separately by individual modules. It should be designed so the commander can decide which training modules he will use, depending on the proficiency of the unit. The unit commander need only use those modules that fit his training plan.

14-2. SET UP A TRAIN-THE-TRAINER PROGRAM

The purpose of a train the trainer program in the unit is to develop trainers capable of providing soldiers with the confidence and skills necessary to accomplish all assigned land navigation tasks.

a. **Development of the Program**. The unit commander should appoint a cadre of officers and NCOs to act as primary and alternate instructors for land navigation training. Use the training modules the unit has developed and have these soldiers go through each module of training until they can demonstrate expertise. Determine which instructors conduct each module of training and have them practice until they are fully prepared to give the training. These instructors act as training cadre for the entire unit. They train their peers to instruct the subordinate units, and they certify each unit's training.

b. **Conduct of Training**. Conduct training at the lowest level possible. Leaders must be included in all training to keep unit integrity intact.

14-3. SET UP A LAND NAVIGATION COURSE

The unit commander provides specific guidance on what he requires in the development of a land navigation course. It depends upon the unit's mission, training plan, and tasks to be trained. There are basic guidelines to use when setting up a course.

a. **Determine the Standards**. The unit commander determines the standards for the course. Recommended standards are as follows:

(1) Distance between points: no less than 300 meters; no more than 1,200 meters.

(2) Total distance of lanes: no less than 2,700 meters; no more than 11,000 meters.

(3) Total number of position stakes: no less than seven for each lane; no more than nine for each lane.

(4) Time allowed: no less than three hours; no more than four hours.

b. **Decide on the Terrain.** The unit should use terrain that is similar to terrain they will be using in tactical exercises. Terrain should be different each time training is conducted; the training area for a dismounted course needs to be at least 25 square kilometers. Mounted courses require twice as much terrain so that vehicles are not too close to each other.

c. **Perform a Map and Ground Reconnaissance**. Check the terrain to determine position stake locations, look for hazards, and to develop training briefings.

(1) Plot the locations of your position stakes on a 1:50,000-scale map.

(2) Fabricate or order position stakes.

(3) Request support from the local engineer or field artillery unit to survey the position stakes in.

(4) Survey the position stakes in and emplace them.

(5) Certify the course by having your SMEs negotiate each lane of the course.

(6) Prepare course requirement sheets and print them.

(7) Complete a risk assessment of the training area.

(8) Begin teaching.

This sequence can be used to develop any type of land navigation course. The difference in each course depends on the commander's guidance.

APPENDIX A
FIELD SKETCHING

A sketch is a free-hand drawing of a map or picture of an area or route of travel. It shows enough detail and has enough accuracy to satisfy special tactical or administrative requirements.

A-1. PURPOSE

Sketches are useful when maps are not available or the existing maps are not adequate, or to illustrate a reconnaissance or patrol report. Sketches may vary from hasty to complete and detailed, depending upon their purpose and the degree of accuracy required. For example, a sketch of a large minefield will require more accuracy than a hasty sketch of a small unit's defensive position.

A-2. MILITARY SKETCHES

The scale of a sketch is determined by the object in view and the amount of detail required to be shown. The sketch of a defensive position for a platoon or company normally calls for a sketch of larger scale than a sketch for the same purpose for a division. Military sketches also include road and area sketches.

a. **Field Sketches**. A field sketch (Figure A-1) must show the north arrow, scale, legend, and the following features:

- Power lines.
- Rivers.
- Main roads.
- Towns and villages.
- Forests.
- Rail lines.
- Major terrain features.

b. **Road Sketches**. These sketches show the natural and military features on and in the immediate vicinity of the road. In general, the width of terrain sketches will not exceed 365 meters on each side of the road. Road sketches may be used to illustrate a road when the existing map does not show sufficient detail.

c. **Area Sketches**. These sketches include those of positions, OPs, or particular places.

(1) ***Position Sketch***. A position sketch is one of a military position, campsite, or other area of ground. To effectively complete a position sketch, the sketcher must have access to all parts of the area being sketched.

(2) ***Observation Post Sketch***. An OP sketch shows the military features of ground along a friendly OP line as far toward the enemy position as possible.

(3) ***Place Sketch***. A place sketch is one of an area made by a sketcher from a single point of observation. Such a sketch may cover ground in front of an OP line, or it may serve to extend a position or road sketch toward the enemy.


LAKE
SPILLWAY
CANAL WITH LOCKS

Figure A-1. Sketch map.

APPENDIX B
MAP FOLDING TECHNIQUES

One of the first considerations in the care of maps is its proper folding.

B-1. FOLDING METHODS

Figures B-1 and B-2 show ways of folding maps to make them small enough to be carried easily and still be available for use without having to unfold them entirely.



Figure B-1. Two methods of folding a map.

B-2. PROTECTION METHOD

After a map has been folded, it should be pasted in a folder for protection. Apply adhesive to the back of the segments corresponding to A, F, L, and Q (Figure B-2, page B-2).


A
B
E
F
C
D
G
H
J
K
N
O
L
M
P
Q
A
B
F
C
D
G
H
J
K
M
O
L
M
P
Q
A
B
C
D
J
N
O
L
P
Q
A
B
N
O
P
Q
N
O
P
Q
A
B
C
D

Figure B-2. How to slit and fold a map for special use.

B-3. PRACTICE CUT

It is suggested that before attempting to cut and fold a map in the manner illustrated in Figure B-2, make a practice cut and fold with a piece of paper.

APPENDIX C

UNITS OF MEASURE AND CONVERSION FACTORS

This appendix provides conversion tables for units of measure and conversion factors that are used in military operations.

12 inches	=	1 foot
36 inches	=	1 yard
3 feet	=	1 yard
1,760 yards	=	1 mile statute
2,026.8 yards	=	1 mile nautical
5,280 feet	=	1 mile statute
6,080.4 feet	=	1 mile nautical
63,360 inches	=	1 mile statute
72,963 inches	=	1 mile nautical

Table C-1. English system of linear measure.

1 millimeter	=	0.1 centimeter	=	0.0393 inches
10 millimeters	=	1.0 centimeter	=	0.3937 inches
10 centimeters	=	1.0 decimeter	=	3.937 inches
10 decimeters	=	1.0 meter	=	39.37 inches
10 meters	=	1.0 decameter	=	32.81 feet
10 decameters	=	1.0 hectometer	=	328.1 feet
10 hectometers	=	1.0 kilometer	=	0.62 mile
10 kilometers	=	1.0 myriameter	=	6.21 miles

Table C-2. Metric system of linear measure.

1 mil	=	1/6400 circle	=	0.05625°	=	0.0625 grad
1 grad	=	1/400 circle	=	16.0 mils	=	0°54' = 0.9°
1 degree	=	1/360 circle	=	about 17.8 mils	=	about 1.1 grad

Table C-3. Equivalent units of angular measure.

ONE	INCHES	FEET	YARDS	STATUTE MILES	NAUTICLE MILES	mm
Inch	1	0.0833	0.0277	-	-	25.40
Foot	12	1	0.333	-	-	304.8
Yard	36	3	1	0.00056	-	914.4
Statute Mile	63,360	5,280	1,760	1	0.8684	-
Nautical Mile	72,963	6,080	2,026	1.1516	1	-
Millimeter	0.0394	0.0033	0.0011	-	-	1
Centimeter	0.3937	0.0328	0.0109	-	-	10
Decimeter	3.937	0.328	0.1093	-	-	100
Meter	39.37	3.2808	1.0936	0.0006	0.0005	1,000
Decameter	393.7	32.81	10.94	0.0062	0.0054	10,000
Hectometer	3,937	328.1	109.4	0.0621	0.0539	100,000
Kilometer	39,370	3,281	1,094	0.6214	0.5396	1,000,000
Myriameter	393,700	32,808	10,936	6.2137	5.3959	10,000,000

ONE	cm	dm	M	dkm	hm	km	mym
Inch	2.540	0.2540	0.0254	0.0025	0.0003	-	-
Foot	30.48	3.048	0.3048	0.0305	0.0030	0.0003	-
Yard	91.44	9.144	0.9144	0.0914	0.0091	0.0009	-
Statute Mile	160,930	16,093	1,609	160.9	16.09	1.6093	0.1609
Nautical Mile	185,325	18,532	1,853	185.3	18.53	1.8532	0.1853
Millimeter	0.1	0.01	0.001	0.0001	-	-	-
Centimeter	1	0.1	0.01	0.001	0.0001	-	-
Decimeter	10	1	0.1	0.01	0.001	0.0001	-
Meter	100	1	1	0.1	0.01	0.001	0.0001
Decameter	1,000	10	10	1	0.1	0.01	0.001
Hectometer	10,000	100	100	10	1	0.1	0.01
Kilometer	100,000	1,000	1,000	100	10	1	0.1
Myriameter	1,000,000	10,000	10,000	1000	100	10	1

Table C-4. Conversion factors.

Example I

Problem: Reduce 76 centimeters to (?) inches.
76 cm x 0.3937 = 29 inches

Answer: There are 29 inches in 76 centimeters.

Example II

Problem: How many feet are there in 2.74 meters?

$$\frac{2.74}{.3048} = 9 \text{ feet}$$

Answer: There are approximately 9 feet in 2.74 meters.

SCALE	1 INCH EQUALS	1 CENTIMETER EQUALS
1:5,000	416.67 feet 127.00 meters	164.00 feet 50.00 meters
1:10,000	833.33 feet 254.00 meters	328.10 feet 100.00 meters
1:12,500	1,041.66 feet 317.00 meters	410.10 feet 125.00 meters
1:20,000	1,666.70 feet 508.00 meters	656.20 feet 200.00 meters
1:25,000	2,083.30 feet 635.00 meters	820.20 feet 250.00 meters
1:50,000	4,166.70 feet 1,270.00 meters	1,640.40 feet 500.00 meters
1:63,360	5,280.00 feet 1,609.30 meters	2,078.70 feet 633.60 meters
1:100,000	8,333.30 feet 2,540.00 meters	3,280.80 feet 1,000.00 meters
1:250,000	20,833.00 feet 6,350.00 meters	8,202.00 feet 2,500.00 meters
1:500,000	41,667.00 feet 12,700.00 meters	16,404.00 feet 5,000.00 meters

Table C-5. Ground distance at map scale.

APPENDIX D
JOINT OPERATIONS GRAPHICS

Joint operations graphics (paragraph 2-6b[4]) are based on the format of the standard 1:250,000-scale military topographic maps. They contain additional information needed in present-day joint air-ground operations.

D-1. TYPES

Each JOG is prepared in two types; one is designed for air operations and the other for ground operations. Each version is identified in the lower margin as JOINT OPERATIONS GRAPHIC (AIR) or JOINT OPERATIONS GRAPHIC (GROUND).

D-2. BASIC CONTENTS

The basic topographic information is the same on both JOG versions.

a. Power transmission lines are symbolized as a series of purple pylons connected by a solid purple line.

b. Airports, landing facilities, and related air information are shown in purple. The purple symbols that may be unfamiliar to the user are shown in the legend in the margin.

c. The top of each obstruction to air navigation is identified by its elevation above sea level and its elevation above ground level.

d. Along the north and east edges of the graphic, detail is extended beyond the standard sheet lines to create an overlap with the graphics to the north and to the east.

e. Layer tinting (paragraph 10-2a) and relief shading (paragraph 10-2c) are added as an aid to interpreting the relief.

f. The incidence of the graphic in the world geographic reference system (paragraph 4-8b) is shown by a diagram in the margin.

D-3. JOINT OPERATIONS GRAPHIC (AIR)

The JOG (AIR) series, prepared for air use, contains detailed information on air facilities such as radio ranges, runway lengths, and landing surfaces. The highest terrain elevation in each 15-minute quadrangle is identified by the large open-faced figures shown in the legend. Elevations and contours on JOG (AIR) sheets are given in feet.

D-4. JOINT OPERATIONS GRAPHIC (GROUND)

The JOG (GROUND) series is prepared for use by ground units, and only stable or permanent air facilities are identified. Elevations and contours are located in the same positions as on the air version, but are given in meters.

APPENDIX E
EXPORTABLE TRAINING MATERIAL

This appendix provides information on the exportable training material available for unit training in basic land navigation skills. These materials are available from the Army Research Institute, Fort Benning Field Unit, Fort Benning, Georgia 3l905.

E-1. PLANNING TO NAVIGATE

This training material describes the planning process in detail. Planning may be the most important aspect of land navigation. Planning to navigate includes background information for map interpretation, a practical example in planning to navigate, and a description of how to train these skills.

E-2. HOW TO TRAIN BASIC LAND NAVIGATION SKILLS

This training material offers guidance for unit training in basic land navigation skills. It includes training modules for distance and location skills. Each module is self-contained, so training can be given in each skill separately from other skills.

E-3. DISMOUNTED LAND NAVIGATION TECHNIQUE

This training material describes the process of navigating with an emphasis on movement skills and the techniques and strategies that should be used while navigating. Critical training covers how to put skills together for movement and how to decide which technique to use in a certain situation.

E-4. MAP INTERPRETATION TERRAIN ASSOCIATION COURSE

The MITAC program is designed to teach terrain association through a "building block" approach starting with simple elements first, then adding more complex information as the soldier progresses from one level to another. The MITAC consists of three systematic courses of instruction: basic, intermediate, and advanced.

E-5. ROUTE PLANNING GUIDE

The route planning guide provides the small-unit leader with a comprehensive reference document, which he can use in learning to plan dismounted administrative or tactical moves. It offers him a planning procedure that he can use in the field without any notes to plan successful moves over unfamiliar terrain.

E-6. LAND NAVIGATION SUSTAINMENT PROGRAM

The land navigation sustainment program is designed to develop trainers that are capable of providing soldiers with the confidence and skills necessary to accomplish all assigned land navigation tasks and therefore to develop soldiers capable of accomplishing these tasks.

APPENDIX F
ORIENTEERING

What is orienteering? Orienteering is a competitive form of land navigation. It is for all ages and degrees of fitness and skill. It provides the suspense and excitement of a treasure hunt. The object of orienteering is to locate control points by using a map and compass to navigate through the woods. The courses may be as long as 10 km.

F-1. HISTORY

Orienteering began in Scandinavia in the nineteenth century. It was primarily a military event and was part of military training. It was not until 1919 that the modern version of orienteering was born in Sweden as a competitive sport. Ernst Killander, its creator, can be rightfully called the father of orienteering. In the early thirties, the sport received a technical boost with the invention of a new compass, more precise and faster to use. The Kjellstrom brothers, Bjorn and Alvan, and their friend, Brunnar Tillander, were responsible for this new compass. They were among the best Swedish orienteers of the thirties, with several individual championships among them. Orienteering was brought into the US in 1946 by Bjorn Kjellstrom.

F-2. DESCRIPTION

Each orienteer is given a 1:50,000 topographic map with the various control points circled. Each point has a flag marker and a distinctive punch that is used to mark the scorecard. Competitive orienteering involves running from checkpoint to checkpoint. It is more demanding than road running, not only because of the terrain, but because the orienteer must constantly concentrate, make decisions, and keep track of the distance covered. Orienteering challenges both the mind and the body; however, the competitor's ability to think under pressure and make wise decisions is more important than speed or endurance.

F-3. THE COURSE

The orienteering area should be on terrain that is heavily wooded, preferably uninhabited, and difficult enough to suit different levels of competition. The area must be accessible to competitors and its use must be coordinated with appropriate terrain and range control offices.

a. The ideal map for an orienteering course is a multi-colored, accurate, large-scale topographic map. A topographic map is a graphic representation of selected man made and natural features of a part of the earth's surface plotted to a definite scale. The distinguishing characteristic of a topographic map is the portrayal of the shape and elevation of the terrain by contour lines.

b. For orienteering within the United States, large-scale topographic (topo) maps are available from the Defense Mapping Agency Hydrographic Topographic Center. The scale suitable for orienteering is 1:50,000 (DMA).

F-4. SETTING UP THE COURSE

The challenge for the course setter is to keep the course interesting, but never beyond the individual's or group's ability. General guidance is to select locations that are easily identifiable on the map and terrain, and accessible from several routes.

a. Those who set up the initial event should study a map for likely locations of control points and verification of the locations. Better yet, they should coordinate with an experienced competitor in selecting the course.

b. There are several forms of orienteering events. Some of the most common are route, line, cross-country, and score orienteering.

(1) ***Route Orienteering***. This form can be used during the training phase and in advanced orienteering. In this type of event, a master or advanced competitor leads the group as they walk a route. The beginners trace the actual route walked on the ground on their maps. They circle the location of the different control points found along the walked route. When they finish, the maps are analyzed and compared. During training, time is not a factor. Another variation is when a course is laid out on the ground with markers for the competitor to follow. There is no master map, as the course is traced for the competitor by flags or markers. The winner of the event is the competitor who has successfully traced the route and accurately plotted the most control points on his map.

(2) ***Line Orienteering***. At least five control points are used during this form of orienteering training. The competitor traces on his map a preselected route from a master map. The object is to walk the route shown on the map, circling the control points on the map as they are located on the ground (Figure F-1).


Oliver Hill
6
80
Cunningham Hill
Bonford Hill
McClusky Hill
Mill Creek
Mason Hill
5
78
4
McMurrin Pond
Bailey Hill
Harps Pond
3
78
Grandsland
Galloway Range
Grandsland
McMurrin Branch
Harps Creek
YANKEE ROAD
77
1
2
Hess Hill
Ross Hill
Burks Hill
Hutchcraft Hill
Osnichee Creek

Figure F-1. Line orienteering.

(3) ***Cross-Country Orienteering***. This is the most common type of orienteering competitions. It is sometimes called free or point orienteering and is considered to be the most competitive and intriguing of all events (Figure F-2). In this event, all competitors must visit the same controls in the same order. With the normal one-minute starting interval, it becomes a contest of route choice and physical skill. The winner is the contestant with the fastest time around the course.



Control Number	Coordinates	Control Code	Description of Clues
1	GL01589334	WE	Cemetery, nothern part
2	GL02709323	WT	Creek junction-center
3	GL03509260	DA	Draw, center
4	GL02229155	WK	South end of runway
5	GL01709046	CM	East end of pond
6	GL00659125	RD	Hilltop 134-top
7	GL01509218	JD	Spur-150 southeast of hilltop

Figure F-2. A cross-country orienteering map.

(a) After selecting the control points for the course, determine the start and finish locations. The last control should be near the finish. In describing each control's location, an eight-digit grid coordinate and a combination of two letters identifying the point (control code) should be included in each descriptive clue list that is normally given to each competitor at least two minutes before his start time.

(b) There are usually 6 to 12 control markers on the course in varying degrees of difficulty and distances apart so that there are no easy, direct routes. Instead, each competitor is faced with many choices of direct but difficult routes, or of indirect but easier routes. Each control's location is circled, and the order in which each is to be visited is clearly marked on the master map. The course may be a closed transverse with start and finish collocated, or the start and finish may be at different locations. The length of the course and difficulty of control placement varies with the competitors' degree of expertise. Regardless of the class of event, all competitors must indicate on their event cards proof of visiting the control markers. Inked stamps, coded letters, or punches are usually used to do this procedure.

NOTE: The same orienteering range may serve in both cross-country and score events. However, a separate set of competitor maps, master maps, and event cards are necessary.

(4) *Score orienteering.* In this event, the area chosen for the competition is blanketed with many control points (Figure F-3). The controls near the start/finish point (usually identical in this event) have a low point value, while those more distant or more difficult to locate have a high point value. (See Figure F-6 for a sample card.) This event requires the competitor to locate as many control markers as he can within the specified time (usually 90 minutes). Points are awarded for each control visited and deducted for exceeding the specified time. The competitor with the highest point score is the winner.


3
Higley Hill
ITARY
RESERVATION
Walter Hill
Gow Hill
85
7
McKenna Hill
McKenna Leyte Heliport
84
05
06
07
08
10
09
10
11
83
8
4
6
Kings Pond
Crastor Hill
2
82
Bardman Hill
Grandstand
5
81
1
9
Ray Hill

Control Number	Coordinates	Control Code	Description of Clues
1	GL06938085	TK	Railroad bridge-north
2	GL08608218	RZ	Top of hill
3	GL06508535	CD	North of pond-swamp
4	GL09608265	PR	Center-creek junction
5	GL09858109	AC	Building-dead end
6	GL10968245	SM	Ruins
7	GL09208430	WN	Road junction-north
8	GL06338275	YV	Building-west end of pond
9	GL07858050	NT	Top of hill
10	GL08158350	YM	East end of lake

Figure F-3. A score orienteering map.

(a) Conducting a score event at the start is basically the same as the cross-country event. The competitor is given a map and an event card. The event card lists all the controls with their different point values. When released to the master map, the competitor finds the circles and numbers indicating the location of all the controls listed on his event card. He copies all the red circles on his map. Then he chooses any route he wishes to take in amassing the highest possible point score in the time available. The course is designed to ensure that there are more control points than can possibly be visited in the allotted time. Again, each control marker visited must be indicated on the event card.

(b) It is important for the competitor to take time initially to plot the most productive route. A good competitor may spend up to 6 minutes in the master map area while plotting the ideal route.

(c) There is no reward for returning early with time still available to find more points, so the good competitor must be able to coordinate time and distance with his ability in land navigation in running the course.

F-5. OFFICIALS

The same officials can be used at the start and finish. More officials or assistants can be used; the following material lists the minimum that can be used for a competition. They include the following:

a. **At The Start.**

(1) ***Course Organizer***—Briefs the orienteers in the assembly area, issues event cards and maps, and calls orienteers forward to start individually.

(2) ***Recorder***—Records orienteer's name and start time on recorder's sheet, checks orienteer's name and start number on his event card, and issues any last-minute instructions.

(3) ***Timer***—Controls the master clock and releases the orienteers across the start line at their start time (usually at one-minute intervals) to the master map area.

b. **At The Finish.**

(1) ***Timer***—Records finish time of each orienteer on the orienteer's event card and passes card to recorder.

(2) ***Recorder***—Records finish time of each orienteer on the orienteer's event card and passes card to recorder.

(3) ***Course Organizer***—Verifies correctness of names, finish times, and final score; posts orienteers' positions on results board; and accounts for all orienteers at the end of event.

F-6. START/FINISH AREA

The layout of the start/finish areas for orienteering events is basically the same for all forms.

a. **Assembly Area.** This is where orienteers register and receive instructions, maps, event cards, and start numbers. They may also change into their orienteering clothes if facilities are available, study their maps, and fill out their event cards here. Sanitation facilities should be available in this area.

b. **Start.** At the start, the orienteer reports to the recorder and timer's table to be logged in by the recorder and released by the timer.

c. **Master Map Area.** There are three to five master maps 20 to 50 meters from the start. When the orienteer arrives at this area, he must mark his map with all the course's control points. Having done this, he must decide on the route that he is to follow. The good orienteer takes the time to orient his map and carefully plot his route before rushing off. It is a good idea to locate the master map area out of sight of the start point to preclude orienteers tracking one another.

d. **Equipment.** The following is a list of equipment needed by the host of an orienteering event:

- Master maps, three to five, mounted.
- Competitor maps, one each.
- Event cards, one each.
- Recorder's sheets, two.
- Descriptive clue cards, one each.
- Time clocks, two.
- Rope, 100 to 150 feet, with pegs for finish tunnel.
- Card tables, one or two.
- Folding chairs, two or three.
- Results board.
- Control markers, one per point.
- Extra compasses.
- Whistle, for starting.
- First aid kit.
- Colored tape or ribbon for marking route to master map and from last control point to finish.

e. **Control Markers.** These are orange-and-white markers designating each control point (Figure F-4). Ideally, they should have three vertical square faces, forming a triangle with the top and bottom edges. Each face should be 12 inches on a side and divided diagonally into red and white halves or cylinders (of similar size) with a large, white, diagonal stripe dividing the red cylinder. For economy or expediency, 1-gallon milk cartons, 5-gallon ice cream tubs, 1-gallon plastic bleach bottles, or foot-square plaques, painted in the diagonal or divided red and white colors of orienteering, may be used.



Figure F-4. Control markers.

(1) Each marker should have a marking or identification device for the orienteer to use to indicate his visit to the control. This marker may be the European-style punch pliers, a self-inking marker, different colored crayons at each point, different letter combinations, different number combinations, or different stamps or coupons. The marking device must be unique, simple, and readily transcribable to the orienteers' event cards.

(2) The control marker should normally be visible from at least 10 meters. It should not be hidden.

f. **Recorder's Sheets.** A suggested format for the recorder's sheet is depicted in Figure F-5.


SAMPLE FORMAT

RECORDER'S SHEET

NAME	No.	Team-Class	Start Time	Finish Time	Time Taken	Controls Missed	Position

Figure F-5. Recorder's sheet.

g. **Event Card.** The event card can be made before the event and should be as small as possible, as it is carried by the competitor. It must contain the following items: name, start number, start time, finish time, total time, place, and enough blocks for marking the control points. As indicated earlier, it may also contain a listing of descriptive clues (Figure F-6).



CROSS-COUNTRY ORIENTEERING TEAM

NAME ____________ COMPANY ____________ COURSE ____________ TEAM ____________
NAME ____________ COMPANY ____________ START TIME ____________ FINISH TIME ____________

CHECKPOINTS

1	2
3	4
5	6

DESCRIPTION CLUES

NOTE: All control signes are located at eye level on trees.

Total Value of Points ____________
Penalty Points ____________
Final Score ____________

1. All work is individual team effort.
2. You must not join with or coordinate with any other team.
3. You must personally visit each point you indicate on your scorecard.

SAMPLE FORMAT

Figure F-6. Cross-country orienteering event card.

h. **Results Board.** This board displays the orienteer's position in the event at the finish (Figure F-7). There are a variety of ways of displaying the results, from blackboard to ladder-like to a clothesline-type device where each orienteer's name, point score, and times are listed.


··RESULTS··
SR. MEN
J. Pitts 71:01
C. Shoemaker 72:00
R. Beardon 74:07
K. Liberty 76:14
J. Harvey 79:13
R. Jones 81:02
RESULTS SR MEN
FOGARTY 70:00
McGUIRE 70:47
LENNOX 71:21
BARNEBY 72:02
GIBBART 72:54
KING R. 73:04

Figure F-7. Results board.

i. **Clue Description Card.** These cards are prepared with the master maps after the course is set. They contain the descriptive clues for each control point, control code, grid coordinate references, returning time for competitors, removal times for each location, and panic azimuth (Figure F-8). The terminology on these must be identical to that listed in the definition section. These cards and the master maps must be kept confidential until the orienteers start the event.



SAMPLE FORMAT

SCORE ORIENTEERING EVENT

NAME ____________ COMPANY ________

NAME ____________ COMPANY ________

TEAM ______________

STARTING TIME ____________

FINISHING TIME ____________

1	6	11	16
2	7	12	17
3	8	13	18
4	9	14	19
5	10	15	20

Total Value of Points

Penalty Points

Final Score

LAND NAVIGATION II

SCORE ORIENTEERING

Description Clues of Control Signs

POINTS	VALUE	DESCRIPTION CLUE
1	10	SE SLOPE OF HILL 1211
2	10	CREST OF HILL 1211
3	10	SADDLE
4	10	EDGE OF RIDGE
5	10	NW CREST OF RIDGE
6	20	CREST OF HILL
7	20	CREST OF HILL
8	20	TOP OF SEVERE DRAW
9	20	SW CREST OF RIDGE
10	10	10 METERS N OF RJ
11	15	CREST OF NW SPUR OF RIDGE
12	10	HIGH POINT OF KNOLL
13	20	HIGH POINT ON HILL SIDE
14	20	NE CORNER OF BLACK CAP MOUNTAINS
15	20	CREST OF SMALL HILL
16	15	NW CREST OF RIDGE
17	10	50 METERS OFF RJ
18	10	10 METERS OFF ROAD
19	10	20 METERS SE OF RJ
20	10	CENTER OF RJ

NOTE: All control signs are located at eye level on trees.

1. ALL WORK IS INDIVIDUAL TEAM EFFORT.
2. YOU MUST NOT JOIN WITH OR COORDINATE WITH ANY OTHER TEAM.
3. YOU MUST PERSONALLY VISIT EACH POINT YOU INDICATE ON YOUR SCORECARD.

Figure F-8. Clue description card.

j. **Scoring.** The cross-country or free event is scored by the orienteer's time alone. All control points must be visited; failure to visit one results in disqualification. In this event, the fastest time wins.

(1) A variation that can be introduced for novices is to have a not-later-than return time at the finish and add minutes to the orienteer's final time for minutes late and control points not located.

(2) The score event requires the amassing of as many points as possible within the time limit. Points are deducted for extra time spent on the course, usually one point for each 10 seconds extra.

k. **Prizes.** A monetary prize is not awarded. A suggested prize for beginners is an orienteering compass or some other practical outdoor-sports item.

F-7. SAFETY ON THE COURSE

A first aid kit must be available at the start and finish. One of the officials should be trained in first aid or have a medic at the event. Other safety measures include:

a. **Control Points.** Locate the controls where the safety of the competitor is not jeopardized by hazardous terrain or other circumstances.

b. **Safety Lane.** Have a location, usually linear, on the course where the competitor may go if injured, fatigued, or lost. A good course will usually have its boundary as a safety lane. Then a competitor can set a panic azimuth on the compass and follow it until he reaches the boundary.

c. **Finish Time.** All orienteering events must have a final return time. At this time, all competitors must report to the finish line even if they have not completed the course.

d. **Search-and-Rescue Procedures.** If all competitors have not returned by the end of the competition, the officials should drive along the boundaries of the course to pick up the missing orienteers.

F-8. CONTROL POINT GUIDELINES

When the control point is marked on the map as well as on the ground, the description of that point is prefaced by the definite article **the**; for example, **the pond**. When the control point is marked on the ground but is not shown on the map, then the description of the point is prefaced by the indefinite article **a**; for example, **a trail junction**. In this case, care must be taken to ensure that no similar control exists within at least 25 meters. If it does, then either the control must not be used or it must be specified by a directional note in parentheses; for example, a depression (northern). Other guidelines include:

a. Points of the compass are denoted by capital letters; for example, S, E, SE.

b. Control points within 100 meters of each other or different courses are not to be on the same features or on features of the same description or similar character.

c. For large (up to 75 meters across) features or features that are not possible to see across, the position of the control marker on the control point should be given in the instructions. For example, the east side of the pond; the north side of the building.

d. If a very large (100 to 200 meters) feature is used, the control marker should be visible from most directions from at least 25 meters.

e. If a control point is near but not on a conspicuous feature, this fact and the location of the marker should be clearly given; for example, 10 meters E of the junction. Avoid this kind of control point.

f. Use trees in control descriptions only if they are prominent and a totally different species from those surrounding. Never use bushes and fauna as control points.

g. Number control points in red on the master map.

h. For cross-country events, join all control points by a red line indicating the course's shape.

F-9. MAP SYMBOLS

The map symbols in Figure F-9 are typical topographic and cultural symbols that can be selected for orienteering control points. The map cutouts have been selected from DMA maps.


1.
ROAD JUNCTION
Where one road joins another
2.
ROAD INTERSECTION
Where one road crosses another
3.
CURVE
A bend in the road
Higley Hill
400
Hill
430

Figure F-9. Map symbols.


4.
DEAD END
Where a road stops with no outlets
5.
TRAIL JUNCTION
Where two trails join
Saxton
315
300
6.
TRAIL DEAD END
Where the trail stops
400
350
300
350
7.
TRAIL CURVE
300
350
8.
ROAD AND TRAIL JUNCTION
Where a road intersects with two trails
350
350
400
400
400

Figure F-9. Map symbols (continued).


300
300
350
Griswold Hill
427

9.
ROAD AND TRAIL INTERSECTION
Where a road crosses a trail



10.
INTERMITTENT STREAM JUNCTION


MIL RES
300
300

11.
STREAM JUNCTION


250
COUNTY
300

12.
BEND IN STREAM



13.
POND'S EASTERNMOST POINT

Figure F-9. Map symbols (continued).


TRAIL
300
Pond
316
350
Pond
Oswichee
350
350
220
219
250
N
Creek

14.
POND

15.
OUTLET
Where water flows out of pond

16.
INLET
Where water flows into a pond

17.
MARSHY OR SWAMPY POND

18.
TRAIL AND STREAM
INTERSECTION
Where a trail crosses a stream
(in most cases, there is no bridge)

Figure F-9. Map symbols (continued).



19.
ISLAND
Land surrounded by water





20.
HILLTOP
The highest elevation of a landmark




Tally Hill
356

21.
RIDGE
The trail follows the path of a ridge





22.
SADDLE
The low point between two or more points of higher ground





23.
STEEP SIDE OF A HILL



Figure F-9. Map symbols (continued).


24.
DRAWS
350
25.
SPUR
300
350
26.
DRAW OR BEGINNING OF A VALLEY
300
27.
SEMILEVEL GROUND ALONG THE PATH OF A RIDGE
28.
JUNCTION OF STREAMS
Two intermittent streams join another stream
350
400

Figure F-9. Map symbols (continued).


29.
VALLEY
In both directions of a creek
Mill Creek
300
280
30.
CREEK JUNCTION
350
300
31.
DRAW WITH INTERMITTENT
STREAM
400
32.
HILLTOP
400
33 .
VALLEY
350
400
350

Figure F-9. Map symbols (continued).

34.
SPOT ELEVATION


400
500
BM
431



35.
ORCHARD





36.
MARSH OR SWAMP





37.
DEPRESSION



Figure F-9. Map symbols (continued).



Figure F-9. Map symbols (continued).

F-10. ORIENTEERING TECHNIQUES

The orienteer should try not to use the compass to orient the map. The terrain association technique is recommended instead. The orienteer should learn the following techniques:

a. **Pacing.** One of the basic skills that the orienteer should develop early is how to keep track of distance traveled while walking and running. This is done on a 100-meter pace course.

b. **Thumbing.** This technique is very simple, but the map has to be folded small to use it. The orienteer finds his location on the map and places his thumb directly next to it. He moves from point to point on the ground without moving his thumb from his initial location. To find the new location, the only thing that he has to do is look at the map and use his thumb as a point of reference for his last location. This technique prevents the orienteer from looking all over the map for his location.

c. **Handrails.** This technique enables the orienteer to move rapidly on the ground by using existing linear features (such as trails, fences, roads, and streams) that are plotted along his route. They can also be used as limits or boundaries between control points (Figure F-10).



Figure F-10. Handrails.

d. **Attack Points.** These are permanent known landmarks that are easily identified on the ground. They can be used as points of reference to find control points located in the woods. Some examples of attack points are stream junctions, bridges, and road intersections.

F-11. CIVILIAN ORIENTEERING

Civilian orienteering is conducted under the guidelines of the United States Orienteering Federation with at least 70 clubs currently affiliated. Although civilian orienteering is a form of land navigation, the terms, symbols, and techniques are different from the military.

a. An expert military map reader/land navigator is by no means ready to compete in a civilian orienteering event. However, military experience in navigating on the ground and reading maps will help individuals to become good orienteers. Several orienteering practices and complete familiarization with the map symbols and terms before participating in a real orienteering event is recommended.

(1) ***Map***. The standard orienteering map is a very detailed, 1:15,000-scale, colored topographical map. All orienteering maps contain only north-south lines that are

magnetically drawn; this eliminates any declination conversions. Because of the absence of horizontal lines, grid coordinates cannot be plotted and therefore are not needed.

(2) ***Symbols (Legend)***. Despite standard orienteering symbols, the legend in orienteering maps has a tendency to change from map to map. A simple way to overcome this problem is to get familiar with the legend every time that a different map is used.

(3) ***Scale***. The scale of orienteering maps is 1:15,000. This requires an immediate adjustment for the military land navigator, especially while moving from point to point. It takes a while for a person that commonly uses a 1:50,000 scale to get used to the orienteering map.

(4) ***Contours***. The normal contour interval in an orienteering map is 5 meters. This interval, combined with the scale, makes the orienteering maps so meticulously detailed that a 1-meter boulder, a 3-meter shallow ditch, or a 1-meter depression will show on the map. This may initially shock a new orienteer.

(5) ***Terms and Description of Clues***. The names of landforms are different from those commonly known to the military. For example, a valley or a draw is known as a reentrant; an intermittent stream is known as a dry ditch. These terms, with a description of clues indicating the position and location of the control points, are used instead of grid coordinates.

b. The characteristics of the map, the absence of grid coordinates, the description of clues, and the methods used in finding the control points are what make civilian orienteering different from military land navigation.

APPENDIX G
M2 COMPASS

The M2 compass (Figure G-1) is a rustproof and dustproof magnetic instrument that provides slope, angle of site, and azimuth readings. One of the most important features of the M2 compass is that it is graduated in mils and does not require a conversion from degrees to mils as does the M1 compass. It can be calibrated to provide a grid azimuth or it can be used uncalibrated to determine a magnetic azimuth.

G-1. MAGNETIC NEEDLE

Except for the magnetic needle and its pivot, the compass is made of nonmagnetic materials. When the cover is closed, the magnetic needle is automatically lifted from its pivot and held firmly against the glass window. When the compass is open and leveled, the needle floats freely upon its pivot and points to magnetic north. Note that both ends of the needle are shaped like an arrow, and that one arrow is painted white and the other is black. It is the white end of the needle that points to magnetic north. Because the needle is magnetic, it will also be attracted to large iron or steel objects in the near vicinity, to electrical power lines, and to operating generators (see paragraph 9-3b). Magnetic compass readings measured near such objects are apt to be in error due to the magnetic attraction of these objects.



Figure G-1. M2 compass.

G-2. CIRCULAR LEVEL

The M2 compass has a circular level that is used to level the instrument when measuring azimuths. The circular level bubble must be centered before reading the azimuth. The compass is equipped with front and rear sights for aligning on the object to which the azimuth is desired.

G-3. COMPASS AZIMUTH SCALE

The compass azimuth scale is a circle divided into 6400 mils. Beginning with zero, the graduations are numbered every 200 mils. The long, unnumbered graduations appearing halfway between the numbered graduations are the odd-numbered hundreds (100, 300, 500, and so forth). Short graduation marks divide each 100-mil segment into equal portions of 20 mils.

a. **Reading the Azimuth Scale.** Azimuths are read from the azimuth scale from the black end of the compass needle.

b. **Setting Up the Compass.** To set up the M2 compass, open the cover and fold the rear sight holder out parallel with the face of the compass. Fold the rear sight up, perpendicular with its holder. Fold the front sight up, parallel with the mirror. Then fold the cover (mirror) toward the compass until it is at an angle of approximately 45 degrees to the face of the compass so that, with your eye behind the rear sight, the black end of the compass needle can be readily viewed in the mirror. The compass is now set up for measuring an azimuth.

c. **Measuring an Azimuth.** Once the compass is set up and all steel objects are at least 18 meters away from your position, you are ready to measure an azimuth. Hold the compass in both hands at eye level with your arms braced against your body and with the rear sight nearest your eyes. Sight through the rear sight and the window in the mirror and align the hairline at the reflection of the face of the compass. Center the circular level bubble. With the bubble centered and the hairline aligned on the object, look at the mirror reflection of the compass scale and read the azimuth to which the black end of the needle is pointing. Remember, magnetic attractions or movement by you may cause errors in your readings.

APPENDIX H
ADDITIONAL AIDS

This appendix provides information on the operation and function of already fielded, and soon to be fielded, devices that can be used as aids to navigation.

H-1. AN/PVS-5, NIGHT VISION GOGGLES

These goggles are passive night vision devices. An infrared light source and positive control switch permit close-in viewing under limited illumination. The AN/PVS-5 has a field of view of 40 degrees and a range of 150 meters.

a. The device has the capability for continuous passive operation over a 15-hour period without battery replacement. It weighs 1.5 pounds and is face-mounted. An eyepiece diopter is provided so the device can be worn without corrective lenses.

b. The device is designed to assist the following tasks: command and control, fire control, reconnaissance, close-in surveillance, terrain navigation, first aid, operation and maintenance of vehicles, selection of positions, traffic control, rear and critical area security, patrolling, combat engineer tasks, radar team employment, resupply activities, and flight-line functions.

c. It is a fielded system used by combat, CS, and CSS elements. The infantry, armor, air defense, field artillery, aviation, engineer, intelligence, military police, transportation, signal, quartermaster, chemical, maintenance, missile, and munitions units all use the device to help accomplish their missions.

d. The AN/PVS-5 can assist the land navigator under limited visibility conditions. Chemical lights may be placed at selected intervals along the unit's route of movement, and they can be observed through the AN/PVS-5. Another navigation technique is to have one person reading the map while another person reads the terrain, both using AN/PVS-5's. This allows the map reader and the terrain interpreter to exchange information on what terrain is observed, both on the map and on the ground. It allows each user to concentrate his AN/PVS-5 on one task. Land navigation, especially mounted, is a task better performed by more than one person. The above technique allows one soldier to perform map interpretation in the cargo portion of the vehicle while another soldier, possibly the driver, transmits to him information pertaining to the terrain observed on the ground.

H-2. AN/PVS-7, NIGHT VISION GOGGLES

The AN/PVS-7 is a lightweight (1.5 pounds), image intensification, passive night-vision device that uses ambient light conditions. It has the same applications as the AN/PVS-5. It is designed to be used in the same way as, and by the same units as, the AN/PVS-5. The AN/PVS-7 has a field of view of 40 meters and a range of 300 meters in moonlight and 150 meters in starlight.

H-3. ENHANCED PLRS USER UNIT

The enhanced position location reporting system (EPLRS)/joint tactical information distribution system (JTIDS), hybrid (PJH), is a computer-based system. It provides near real-time, secure data communications, identification, navigation, position location, and automatic reporting to support the need of commanders for information on the location, identification, and movement of friendly forces.

a. The EPLRS is based on synchronized radio transmissions in a network of users controlled by a master station. The major elements of a EPLRS community include the airborne, surface vehicular, and man-pack users; the EPLRS master station; and an alternate master station. The system can handle 370 user units in a division-size deployment per master station with a typical location accuracy at 15 meters. The man-pack unit weighs 23 pounds and includes the basic user unit, user readout, antenna, backpack, and two batteries.

b. The EPLRS are deployed at battalion and company level. Its use allows—

(1) Infantry or tank platoons to locate their positions, know the location of their friendly units, navigate to predetermined locations, and be informed when near or crossing boundaries.

(2) Artillery batteries to locate forward observers and friendly units, and position firing batteries.

(3) Aircraft to locate their exact positions; know the location of other friendly units; navigate to any friendly units, or a location entered by pilot; navigate in selected flight corridors; and be alerted when entering or leaving corridors or boundaries.

(4) Command and control elements at all echelons to locate and control friendly units/aircraft.

c. The network control station is located at brigade level to provide position location/navigation and identification services. It also provides interface between the battalion and company systems, and the JTIDS terminals.

d. It is fielded to infantry, armor, field artillery, military police, engineer, intelligence, aviation, signal, and air defense artillery units.

e. The EPLRS is a system that allows units to navigate from one point to another with the capability of locating itself and other friendly units equipped with the same system.

H-4. GLOBAL POSITIONING SYSTEM

The GPS is a space-based, radio-positioning navigation system that provides accurate passive position, speed, distance, and bearing of other locations to suitably equipped users.

a. The system assists the user in performing such missions as siting, surveying, tactical reconnaissance, sensor emplacement, artillery forward observing, close air support, general navigation, mechanized maneuver, engineer surveying, amphibious operations, signal intelligence operations, electronic warfare operations, and ground-based forward air control.

b. It can be operated in all weather, day or night, anywhere in the world; it may also be used during nuclear, biological, and chemical warfare.

c. It has been widely fielded in both active and reserve component units. (See Appendix J for more information on GPS.)

H-5. POSITION AND AZIMUTH DETERMINING SYSTEM

The PADS is a highly mobile, self-contained, passive, all-weather, survey-accurate position/navigation instrument used by field artillery and air defense artillery units for fire support missions. Its basis of issue is two sets per artillery battalion. The device is about the size of a 3-kilowatt generator and weighs 322.8 pounds in operational configuration.

a. The two-man PADS survey party uses the high-mobility, multipurpose, wheeled vehicle, the commercial utility cargo vehicle, the small-unit support vehicle, or the M151 1/4-ton utility truck. The system can be transferred while operating into the light observation helicopter (OH-58A) or driven into the CH-47 medium cargo helicopter.

b. The system provides real-time, three-dimensional coordinates in meters and a grid azimuth in mils. It also gives direction and altitude.

c. The PADS can be used by the land navigator to assist in giving accurate azimuth and distance between locations. A unit requiring accurate information as to its present location can also use PADS to get it. The PADS, if used properly, can assist many units in the performance of their mission.

WARNING

Laser devices are potentially dangerous. Their rays can and will burn someone's eyes if they look directly at them. Users should not direct the beams at friendly positions or where they could reflect off shiny surfaces into friendly positions. Other soldiers must know where lasers are being used and take care not to look directly at the laser beam.

H-6. GROUND-VEHICULAR LASER LOCATOR DESIGNATOR

The G/VLLD is the Army's long-range designator for precision-guided semi-active laser weapons. It is two-man portable for short distances and can be mounted on the M113A1 interim FIST vehicle when it has the vehicle adapter assembly. The G/VLLD provides accurate observer-to-target distance, vertical angle, and azimuth data to the operator. All three items of information are visible in the operator's eyepiece display.

a. The G/VLLD is equipped with an AN/TAS-4 night sight. This night sight increases the operator's ability to detect and engage targets during reduced visibility caused by darkness or battlefield obscuration.

b. The G/VLLD can give the navigator accurate line-of-sight distance to an object. The system can be used to determine its present location using resection and can assist the navigator in determining azimuth and distance to his objective.

H-7. QUICK RESPONSE MULTICOLOR PRINTER

The QRMP is a self-contained, laser, xerography printer capable of reproducing maps, photographs, annotated graphics, transparent originals, and digital terrain data in full color on transparent material or standard map paper. The QRMP system will consist of a QRMP housed in an 8' by 8' by 20' ISO shelter mounted on a 5-ton truck with a dedicated military-standard 30-kilowatt generator. Each system will carry at least a seven-day supply of all necessary materials.

a. The QRMP system has map size (24" by 30" paper size and 22.5" by 29" image size), color printing, scanning and electronics subsystems. It produces the first copy in less than five minutes in full color and sustains a copy rate of 50 to 100 copies per hour for full color products. The system uses a charged couple device array for scanning and sophisticated electronic signal processing to electrostatically discharge a selenium photoreceptor drum.

b. The QRMP has the capability to print terrain and other graphics directly from digital output from the digital topographic support system or another QRMP. The first unit is scheduled to be equipped with the QRMP in 1QFY97, and the initial operating capability is scheduled for 4QFY97. The QRMP system is used by the engineer topographers at division, corps, and echelons above corps.

APPENDIX I
FOREIGN MAPS

The use of foreign maps poses several problems to the land navigator. These products are often inferior in both content reliability and topographic accuracy to those produced by the DMA. Clues to these weaknesses are the apparent crudeness of the maps, unusually old compilation dates, or differences in mapped and actual terrain. The following characteristics should be examined closely.

I-1. HYDROGRAPHY

Of all the symbols on foreign maps, those for hydrography conform most closely to DMA usage. The use of blue lines and areas to depict streams, rivers, lakes, and seas seems to be universally accepted. The one caution to be observed is that foreign cartographers use different sets of rules to govern what is and what is not included on the map. Distinction between perennial and intermittent streams is usually not made.

I-2. VEGETATION

The classification and symbols for vegetation on most foreign maps are different to those used on DMA maps. The vegetation included on many foreign maps is often extensive, identifying not only vegetated areas--but also the specific types of vegetation present. Green is the predominant color used to represent vegetation; but, blue and black are sometimes used. The symbols that depict the various types of vegetation differ greatly from one foreign map to another.

I-3. CULTURAL AND LINEAR FEATURES

Perhaps the most striking difference between DMA and foreign maps is the set of symbols used to portray cultural features. Some symbols found on foreign maps are very unusual. Symbols for linear features on foreign maps are also likely to confuse the user who is accustomed to DMA symbols. DMA uses 10 basic road symbols to portray different classes of roads and trails; foreign mappers use many more.

I-4. TERRAIN RELIEF

Foreign maps generally use contour lines to portray terrain relief, but substantial variability exists in the contour intervals employed. They may range from 5 to 100 meters.

I-5. SCALE

Scales found on foreign maps include 1:25,000, 1:63,360, 1:63,600, 1:75,000, and 1:100,000. Most foreign large-scale topographic maps have been overprinted with 1,000-meter grid squares; so, it is unlikely that the variable scales will have much effect on your ability to use them. However, you must learn to estimate grid coordinates because your 1:25,000 and 1:50,000 grid coordinate scales may not work.

I-6. STEPS TO INTERPRETING FOREIGN MAPS

After discussing the many difficulties and limited advantages encountered when using foreign maps, it is only appropriate that some strategy be offered to help you with the task.

a. In the August 1942 issue of The Military Engineer, Robert B. Rigg, Lieutenant, Cavalry, suggested a five-step process for reading and interpreting foreign maps. It is as appropriate today as it was when he first proposed it.

Step 1. Look for the date of the map first. There are generally four dates: survey and compilation, publication, printing and reprinting, and revision. The date of the survey and compilation is most important. A conspicuous date of revision generally means that the entire map was not redrawn—only spot revisions were made.

Step 2. Note whether the publisher is military, government, or civilian. Maps published by the government or the military are generally most accurate.

Step 3. Look at the composition. To a great extent, this will reveal the map's accuracy. Was care taken in the cartography? Are symbols and labels properly placed? Is the draftsmanship precise? Is the coastline or river bank detailed?

Step 4. Observe the map's color. Does it enhance your understanding or does it obscure and confuse? The importance of one subject (coloring) must warrant canceling others. If it confuses, the map is probably not very accurate.

Step 5. Begin to decode the various map colors, symbols, and terms. Study these items by examining one feature classification at a time (culture, hydrography, topography, and vegetation). As an accomplished navigator, you should already have a good understanding of your area of operations, so translation of the map's symbols should not present an impossible task. Use your notebook to develop an English version of the legend or create a new legend of your own.

b. In dealing with the challenge of using a foreign map, be certain to use these five steps. In doing so, you are also encouraged to bring to bear all that you know about the geographic area and your skills in terrain analysis, map reading, map interpretation, and problem solving. After careful and confident analysis, you will find that what you do know about the foreign map is more than what you do not know about it. The secret often lies in the fact that the world portrayed on a map represents a kind of international language of its own, which allows you to easily determine the map's accuracy and to decode its colors, symbols, and labels.

APPENDIX J
GLOBAL POSITIONING SYSTEM

> *The ability to accurately determine position location has always been a major problem for soldiers. However, the global positioning system has solved that problem. Soldiers will now be able to determine their position accurately to within 10 meters.*

J-1. DEFINITION

The GPS is a satellite-based, radio navigational system. It consists of a constellation with 24 active satellites that interfaces with a ground-, air-, or sea-based receiver. Each satellite transmits data that enables the GPS receiver to provide precise position and time to the user. The GPS receivers come in several configurations, hand-held, vehicular-mounted, aircraft-mounted, and watercraft-mounted.

J-2. OPERATION

The GPS is based on satellite ranging. It figures the users' position on earth by measuring the distance from a group of satellites in space to the users' location. For accurate three-dimensional data, the receiver must track four or more satellites. Most GPS receivers provide the user with the number of satellites that it is tracking, and whether or not the signals are good. Some receivers can be manually switched to track only three satellites if the user knows his altitude. This method provides the user with accurate data much faster than that provided by tracking four or more satellites. Each type receiver has a number of mode keys that have a variety of functions. To better understand how the GPS receiver operates, refer to the operators' manual.

J-3. CAPABILITIES

The GPS provides worldwide, 24-hour, all-weather, day or night coverage when the satellite constellation is complete. The GPS can locate the position of the user accurately to within 21 meters—95 percent of the time. However, the GPS has been known to accurately locate the position of the user within 8 to 10 meters. It can determine the distance and direction from the user to a programmed location or the distance between two programmed locations called way points. It provides exact date and time for the time zone in which the user is located. The data supplied by the GPS is helpful in performing several techniques, procedures, and missions that require soldiers to know their exact location. Some examples are:

- Sighting.
- Surveying.
- Sensor or minefield emplacement.
- Forward observing.
- Close air support.
- Route planning and execution.
- Amphibious operations.
- Artillery and mortar emplacement.

- Fire support planning.

J-4. LIMITATIONS

A constellation of 24 satellites broadcasts precise signals for use by navigational sets. The satellites are arranged in six rings that orbit the earth twice each day. The GPS navigational signals are similar to light rays, so anything that blocks the light will reduce or block the effectiveness of the signals. The more unobstructed the view of the sky, the better the system performs.

J-5. COMPATABILITY

All GPS receivers have primarily the same function, but the input and control keys vary between the different receivers. The GPS can reference and format position coordinates in any of the following systems:

- **Degrees, Minutes, Seconds (DMS):** Latitude/longitude-based system with position expressed in degrees, minutes, and seconds.
- **Degrees, Minutes (DM):** Latitude/longitude-based system with position expressed in degrees and minutes.
- **Universal Traverse Mercator (UTM):** Grid zone system with the northing and easting position expressed in meters.
- **Military Grid Reference System (MGRS):** Grid zone/grid square system with coordinates of position expressed in meters.

The following is a list of land navigation subjects from other sections of this manual in which GPS can be used to assist soldiers in navigating and map reading:

a. **Grid Coordinates (Chapter 4).** GPS makes determining a 4-, 6-, 8-, and 10-digit grid coordinate of a location easy. On most GPS receivers, the position mode will give the user a 10-digit grid coordinate to their present location.

b. **Distance (Chapter 5) and Direction (Chapter 6).** The mode for determining distance and direction depends on the GPS receiver being used. One thing the different types of receivers have in common is that to determine direction and distance, the user must enter at least one way point (WPT). When the receiver measures direction and distance from the present location or from way point to way point, the distance is measured in straight line only. Distance can be measured in miles, yards, feet, kilometers, meters, or nautical knots or feet. For determining direction, the user can select degrees, mils, or rads. Depending on the receiver, the user can select true north, magnetic north, or grid north.

c. **Navigational Equipment and Methods (Chapter 9).** Unlike the compass, the GPS receiver when set on navigation mode (NAV) will guide the user to a selected way point by actually telling the user how far left or right the user has drifted from the desired azimuth. With this option, the user can take the most expeditious route possible, moving around an obstacle or area without replotting and reorienting.

d. **Mounted Land Navigation (Chapter 12).** While in the NAV mode, the user can navigate to a way point using steering and distance, and the receiver will tell the user how far he has yet to travel, and at the current speed, how long it will take to get to the way point.

e. **Navigation in Different Types of Terrain (Chapter 13).** The GPS is capable of being used in any terrain, especially more open terrain like the desert.

f. **Unit Sustainment (Chapter 14).** The GPS can be used to read coordinates to quickly and accurately establish and verify land navigation courses.

APPENDIX K

PRECISION LIGHTWEIGHT GLOBAL POSITIONING SYSTEM RECEIVER

The precision lightweight global positioning system receiver (PLGR) is a highly accurate satellite signal navigation set (referred to in this appendix as AN/PSN-11).

K-1. CONCEPT OF OPERATION

The AN/PSN-11 is designed for battlefield use anywhere in the world. It is sealed watertight for all weather day or night operation. The AN/PSN-11 is held in the left hand and operated with the thumb of the left hand. Capability is included for installation in ground facilities, and air, sea, and land vehicles. The AN/PSN-11 is operated stand-alone using prime battery power and integral antenna. It can be used with external power source and external antenna.

a. The AN/PSN-11 provides the user with position coordinates, time, and navigation information under all conditions, if**—**

- No obstructions block the line-of-sight satellite signal from reaching the antenna.
- Valid crypto keys are used to protect the AN/PSN-11 from intentionally degraded satellite signals.

b. Many data fields, such as elevation, display units of information. The format of the units can be changed to your most familiar format.

c. Map coordinates are entered as a way point. When a way point is selected as a destination, the AN/PSN-11 provides steering indications, azimuth, and range information to the destination. A desired course to a way point is entered. Offset distance from this course line is shown.

d. Up to 999 way points can be entered, stored, and selected as a destination. A route is defined for nav either start-to-end or end-to-start. The route consists of up to nine legs (10 way points) linked together.

K-2. CAPABILITIES

Data provided by the AN/PVS-11 helps complete missions such as:

- Siting.
- Surveying.
- Tactical reconnaissance.
- Sensor emplacement.
- Artillery forward observing.
- Close air support.
- General navigation.
- Mechanized maneuvers.
- Engineer surveying.
- Amphibious operations.
- Parachute operations.
- Signal intelligence.
- Electronic warfare.

- Ground-based forward air control.

This data is displayed on the AN/PSN-11display. It is also available from a serial data port.

K-3. CHARACTERISTICS

The AN/PSN-11 is less than 9.5 inches long, 4.1 inches wide, and 2.6 inches deep. It weighs 2.75 pounds with all batteries in place. The small size and lightweight make the set easy to carry and use. The durable plastic case is sealed for all-weather use. The AN/PSN-11 features make it easy to use. (These features are highlighted in the physical description in Figure K-1).


KYK-13/KOI-18/SINCGARS Connector (J1)/Cover
Mates with ON199138
Pop-off operation
Protects connector
Power Battery Cover
Twists off for easy field replacement of power battery
Rear Panel Connectors (J2, J3, & J4)
Provide access for serial data ports, external antenna, external power
Display
4-line x 16-character alphanumeric Mode dependent, variable format Flashing field selection
FIX FOM 1
N 42°01' 46.12"
W 091°38' 54.36"
EL +00852ftD P
1 ON BRT
2
3 MENU
4
5
6
7 WP
8 POS
9 NAV
CLR MARK
0 OFF
NUM LOCK
ZEROIZE
Integral Antenna
Flip-up swivel Compact storage Facilitates optimum view angle while receiving satellite signals
Handle
Easy one-handed operation
Adjustable
Facilitates thumb keying
Memory Battery Cover
Screws out for easy replacement of memory battery
Keypad
Oversized keys for ease of operation
Dual Modes:
Control - for one-handed use
Numeric - for quick two-handed data entry

Figure K-1. Physical features.

K-4. SETUP AND CONTROL

Setting up the operation parameters of the PLGR is critical. This section describes the display, procedures, and principles used in setting the AN/PSN-11displays to suit the needs of the user. This display consists of seven pages that allows the user to control the following parameters:

- Operating mode.
- Type of satellites to use.
- Coordinate system.
- Units.
- Magnetic variation.
- Display customization.
- Navigation Display mode.
- Elevation hold mode.
- Time and error formats.
- Datum.
- Automatic off timer.
- Datum port configuration.
- AutoMark mode.

To set the PLGR up for continuous operation:

a. Turn the PLGR **ON**. Once it has completed its built-in-test (BIT) press the **MENU** key and move the cursor to **SETUP** (Figure K-2). Activate the SETUP function.

```
<move>          select
 STATUS          SETUP
 INIT             TEST
 HELP       <MORE> P
```

Figure K-2. SETUP.

b. The first screen (Figure K-3) allows the operator to set the operating mode and SV-Type. Scroll through the operating modes and select **CONT** and for the SV-Type **Mixed**.

```
SETUP  MODE: CONT
Continuous       POS
and    VEL    update
SV-TYPE:  mixed    P
```

Figure K-3. Operating mode and SV-type.

c. The second screen (Figure K-4) allows the operator to setup the units. Scroll through the available coordinates and select **MGRS-New** and **Metric**. For the Elevation select **meter** and **MSL** and for the Angle select **Degrees** and **Magnetic**.

```
SETUP              UNITS
MGRS-New          Metric
Elev:  meter         MSL
ANGL:  Deg    Mag      P
```

Figure K-4. Setup the units.

d. The third screen (Figure K-5) should be set for the MAGVAR (Magnetic variation or GM Angle for your area). The operator can select Calculate the degree or manually enter degrees as an Easterly or Westerly GM Angle; for example, **E021.0** for the TENINO Map Sheet.

```
SETUP         MAGVAR
TYPE:  Calc      deg
       WWM      1995
                   P
```

Figure K-5. Magnetic variation or GM angle setup.

e. The fourth screen (Figure K-6) of setup allows the operator to set the Elevation Hold, Time, and Error. The operator should set the ELHOLD to **automatic**. As for time the operator needs to know, from their present location, how many hours they are ahead of or behind Greenwich Mean Time. For example, during Daylight savings time, Fort Benning, GA. is **Loc=Z-0400**. To set the ERR, the operator selects **-+m** to let him know in meters how accurate the PLGR is operating.

```
SETUP
ELHold :     automatic
TIME:       Loc=Z-0400
ERR: +-m             P
```

Figure K-6. Set elevation, time, hold, and error.

f. The fifth screen (Figure K-7) of setup allows the operator to set the PLGR Datum to their area of operation and to set the Automatic Off Timer. The PLGR has fifty-two map Datum sets available. The operator should set the PLGR Datum to their area of operation. For example, if your map Datum is WGS-84, the operator sets the PLGR to WGS-84. If the map is 1927 North America Datum, the operator sets the Datum to NAS-C. The automatic timer off is used to turn the PLGR off after a prescribed time once it has acquired a fixed position. The operator should set this mode to **OFF**.

SETUP DTM:**NAS-C**
NA27CONUS /Clk66
AUTOMATIC OFF
TIMER: **off** P

Figure K-7. Set the PLGR Datum.

g. The sixth screen (Figure K-8) in setup is the In/Out Port screen. This page allows the operator to control serial communications, HAVEQUICK and 1PPS options. Select **Standard** unless otherwise directed and select **OFF** for Havequick and 1PPS.

SETUP I/O
SERIAL: **Standard**
HAVEQUICK: **Off**
1PPS: **Off** P

Figure K-8. In/out port screen.

h. The seventh screen (Figure K-9) is setup AUTOMARK. This feature allows the operator to have the PLGR periodically wake-up, acquire a position fix, store the position as a way point, or return to the mode of operation it was previously in. The operator should set this mode to **OFF**. The remaining pages for SETUP are for advance GPS users.

SETUP AUTOMARK
MODE: **off** WP002
26-04-01 0935L
REPEAT 00h00m P

Figure K-9. AUTOMARK setup.

i. Once the PLGR is SETUP, the operator can now obtain a position. This procedure is accomplished by activating the Position (POS) key. The position displayed is *OLD* information until the receiver collects and calculates satellite data and displays the current position. The receiver must be tracking three satellites to obtain a two-dimensional fix position and four or more satellites for a three-dimensional fix position. The third dimension is elevation.

K-5. WAY POINT OPERATIONS

A way point is the location of a point on a desired course described by coordinates or a physical location. A normal mission consists of a series of way points. The way points available on the AN/PSN-11 are 999 (numbered 01 through 999).

a. This paragraph describes the AN/PSN-11 way point displays and way point operations. The way point display pages are used to perform the following operations:

- Enter, edit, or review way points.
- Copy way points.
- Determine the distance between way points.
- Calculate a new way point.
- Clear way points.
- Define a mission route.

b. To enter a way point, the operator needs to press the way point **(WP)** key (Figure K-10). When the way point menu appears, the ENTER function flashes. The operator presses the down arrow key to activate this field. Now the operator enters a way point name, grid zone designator, 100,000-meter grid square identifier, 10-digit grid coordinate, and elevation.


WP <move> sel
ENTER EDIT COPY
SR-CALC RNG CALC
DIST CLEAR ROUTE

Figure K-10. Enter a way point.

c. To enter a way point name, the operator presses the right arrow key until the first letter of the word UNUSED(WP#) is flashing (Figure K-11). Scroll up or down through the alphabet changing the letter U to whatever is desired. For example, if the operator wanted to name their way point NORTH STAR, the operator scrolls down the alphabet until the letter U is changed to the letter N (Figure K-12). The operator repeats this process for the remaining letters.


WP002 UNUSED002
B MGRS-New
AN 00000e 00000n
No EL CLR P

Figure K-11. Unused.


WP002 **NORTHSTAR**
10T MGRS-New
EG 13130e 95750n
No EL CLR **N**

Figure K-12. Change a name.

d. Second line, the operator enters the grid zone designator for their area of operation. For example, the Fort Benning area falls in the 16S zone.

e. Third line, the operator must enter a 10-digit grid coordinate with its 100,000-meter grid square identifier. For example, if the way point location is Offutt Lake, Tenino map sheet, the 100,000-meter grid square identifier is EG. Then, the operator plots the grid coordinates on the map and enters it into the PLGR.

NOTE: Operator plots 8-digit grid coordinates, however a 10-digit coordinate is entered. Therefore, the 5th and 10th digit entered is a zero (0).

f. For the fourth line, if the elevation of the way point is known, the operator can enter it. If the elevation is not known the operator can just leave the data as zero or No EL. The operator moves the cursor until the Up and Down arrow symbol appears before the letter P or N in bottom right corner. When activating the down arrow key the operator stores the way point into the PLGR's memory. The PLGR notifies the operator that the way point has been stored.

NOTE: When entering numbers, the NUM LOCK can be activated. The letter N appears in the bottom right corner allowing the operator to use the numbers on the keypad rather then scrolling up/down (Figure K-12).

K-6. NAVIGATION

Navigation (nav) is using the AN/PSN-11 to find your present position, relative to other points. The AN/PSN-11 provides azimuth, range, and steering information in a variety of formats. There are four navigation display modes that may be accessed and selected. The navigation display mode selected determines the type of information shown on the navigation displays. These navigation displays give the user the most useful information for a certain mission profile: *SLOW, 2D FAST, 3D FAST OR CUSTOM.*

- In **SLOW** nav mode, the AN/PSN-11 performs two-dimensional (2D) nav. Slow nav mode is used for land or sea nav, when the user cannot maintain the minimum speed necessary (about 1.5 kmph).
- In **2D FAST** nav mode, the AN/PSN-11 performs two-dimensional (2D) nav. 2D FAST nav mode is used for land or sea nav, when the user can maintain the minimum speed necessary for GPS to compute navigation parameters based on velocity.
- In **3D FAST** nav mode, the AN/PSN-11 performs three-dimentional (3D) nav. 3D FAST nav mode has an APPROACH sub-mode. 3D FAST nav mode is used for air nav, when the user can travel in three dimensions and can maintain the minimum speed necessary for GPS to compute navigation parameters based on velocity.
- In **CUSTOM** nav mode, the AN/PSN-11 performs the users navigational display pages as so desired. It can be set-up to support the individual user's performances or mission requirements. The following custom display modes are available:
  - Direct.
  - Course To.
  - Course From.

- Route.
- Approach.

To navigate with the PLGR on land in a Dead-Reckoning method, the PLGR nav mode is accomplished as follows.

a. The operator presses the NAV key activating the nav function. The first screen that appears is the nav mode (Figure K-13). For example, SLOW, 2D FAST, 3D FAST, CUSTOM, DIRECT, CRS TO, and CRS FROM.

```
2D   FAST        DIRECT
WP002  NORTHSTAR002


                      P
```

Figure K-13. Navigation mode.

b. The operator selects the **2D FAST and DIRECT**. The second line is the way point desired to be navigated. (Scroll through the way points that are stored to choose the desired way point.)

c. To see the azimuth that the navigator should be traveling on, go to the next page by pressing the down arrow key (Figure K-14). This page tells the navigator what azimuth they are heading on (TRK=tracking), and the actual azimuth the navigator should be heading on (AZ). The fourth line tells the navigator Steering (STR). A direction (< >) and a number of degrees the navigator needs to move to travel on their actual azimuth.

```
NORTHSTAR002   +-30m
TRK   305.3 M
AZ     311.3 M
STR   > 6              P
```

Figure K-14. Azimuth.

d. The third screen (Figure K-15) tells the navigator the range or distance to their way point and how much time (TTG2) it will take them to get to their way point. This page also lets the navigator know what is the elevation difference from their present location to the way point and by how much they will miss their way point by (MMD).

```
RNG  3598.55km
TTG2     0036:05
ELD      -00050m
MMD2   30m            P
```

Figure K-15. Range or distance.

GLOSSARY

AA	avenue of approach
ANCOC	advanced noncommissioned officer course
AR	Army regulation
BNCOC	basic noncomissioned officer course
BT	basic training
cm	centimeter
CONUS	continental United States
CS	combat support
CSS	combat service support
CUCV	commercial utility cargo vehicle
DD	Department of Defense
DMA	Defense Mapping Agency
E	east
EPLRS	enhanced position location reporting system
FIST	fire support team
FM	field manual
FORSCOM	United States Army Forces Command
GD	ground distance
GEOREF	geographic reference system
G-M	grid-magnetic
GPS	global positioning system
GSR	ground surveillance radar
GTA	graphic training aid
G/VLLD	ground/vehicular laser locator designator
HD	horizontal distance
HHC	headquarters and headquarters company
HMMWV	high-mobility multipurpose wheeled vehicle
JOG	joint operations graphics
JTIDS	joint tactical information distribution system
km	kilometer
LAT	latitude

MD	map distance
METT-T	mission, enemy, terrain, troops and time available
MITAC	map interpretation and terrain association course
N	north
NCO	noncommissioned officer
OAC	officer advanced course
OBC	officer basic course
OCS	officer candidate school
OSUT	one station unit training
PADS	position and azimuth determining system
PD	photo distance
PJH	hybrid (PLRS and JTIDS)
PLDC	primary leadership development course
PLGR	Precision Lightweight Global Positioning System Receiver
POI	program of instruction
PRE	precommission
QRMP	quick response multicolor printer
ROTC	Reserve Officers' Training Corps
S	south
SF	standard form
SOSES	shapes, orientations, sizes, elevations, and
slopes	
SUSV	small-unit support vehicle
tan	tangent
TM	technical manual
TOW	tube-launched, optically tracked, wire-guided missile
TRADOC	Training and Doctrine Command
topo	topographic
UPS	universal polar stereographic
US	United States
USGS	United States Geological Survey
UTM	universal transverse mercator
VD	vertical distance
VNAS	vehicular navigation aids system
W	west

REFERENCES

SOURCES USED

These are the sources quoted or paraphrased in this publication.

FM 21-31.	Topographic Symbols, 19 June l961.
FM 25-4.	How to Conduct Training Exercises. 10 September 1984.
FM 25-100.	Training the Force. 15 November 1988.
FM 25-101.	Battle Focused Training. 30 September 1990.
FM 101-5-1.	Operational Terms and Graphics. 30 September l997.

DOCUMENTS NEEDED

These documents must be available to the intended users of this publication.

AR 115-11.	Army Topography. 30 November 1993.
AR 380-5.	Department of the Army Information Security Program. 29 September 2000.
AR 380-40.	Policy for Safeguarding and Controlling Communications and Security (COMSEC) Material. 30 June 2000.
FM 5-33.	Terrain Analysis. 11 July 1990.
FM 34-1.	Intelligence and Electronic Warfare Operations. 27 September 1994.
FM 34-3.	Intelligence Analysis. 15 March 1990.
FM 101-10-1.	Staff Officers Field Manual: Organizational, Technical, and Logistical Data. 1 July 1976.
TC 6-40.	Field Artillery Manual Cannon Gunnery. 27 December 1988.
TM 5-240.	Compilation and Color Separation of Topographic Maps. 15 June 1971.
TM 5-243.	Cartographic Aerial Photography. 2 January 1970.
TM 11-5825-291-13	Operations and Maintenance Manual for Satellite Signals Navigation Sets. 15 September 1995.
TB 11-5825-291-10-2	Soldiers' Guide for the Precision Lightweight GPS Receiver (PLGR) AN/PSN-11. 1 December 1996.
TB 11-5825-291-10-3	The PLGR Made Simple. 1 November 1997.

INDEX

azimuth
  back, 6-3 (illus)
  grid, 6-2, 6-3 (illus), 6-4, 6-8
  magnetic, 6-3, 6-11 (illus)
  origin, 6-3 (illus)
  plotting, 6-8 (illus)

base lines, 6-2 (illus)
  grid north, 6-2
  magnetic north, 6-1
  true north, 6-1
bench marks, 10-5

codes, numerical, 4-25, 4-27
colors, map, 3-6
compass, lensatic
  handling, 9-1, 9-2
  orienting a map, 11-1
  parts, 9-1, 9-2 (illus)
  techniques, 9-2 thru 9-6
compass, M2, G-1
contour intervals, 10-2 (illus)
conversion tables, C-1 thru C-3
course, land navigation, 14-2

dead reckoning, 11-14, 12-6, 12-7
declination
  conversion, 6-9 thru 6-14
  diagram, 6-9 (illus), 11-1, 11-2
degree, 6-1
distance determiners
  estimation, 5-12 (illus)
  odometer, 5-11
  pace count, 5-11
  subtense, 5-12

elevation depicting method
  bench marks, 10-5
  contour intervals, 10-2 (illus)
  spot elevations, 10-5
EPLRS (enhanced position location reporting system), H-1, H-2
extension scale, 5-3 thru 5-8, 5-9 (illus)

false easting, 4-11, 4-12 (illus)
false northing, 4-11, 4-12 (illus)
field expedient methods
  shadow-tip method, 9-7 (illus)
  star method, 9-9, 9-10 (illus)
  watch method, 9-8, 9-9 (illus)
folding a map, B-1
foreign map, 2-7

G/VLLD (ground/vehicular laser locator designator), H-3
geographic coordinates, 4-1
geographic interval, 4-3
GEOREF (World Geographic Reference System), 4-25, 4-26 (illus)
global positioning system, 9-12, H-2, J-1, J-2
grad, 6-1
graphic (bar) scales, 5-3 (illus)
  extension scale, 5-3 thru 5-9 (illus)
  primary scale , 5-3 thru 5-6
  time-distance scale, 5-10 (illus)
grid coordinates, 4-14 thru 4-21
grid-magnetic angle, 6-9
grid north, 6-2
grid reference box, 4-13, 4-24, 4-25 (illus)
grids, military, 4-10
  coordinates, 4-1 thru 4-10
  lines, 4-11, 4-14, 4-15 (illus)
  reference system, 4-1
  squares, 4-3, 4-10, 4-14 (illus)
  Universal Polar Stereographic, 4-11, 4-12 (illus)
  Universal Transverse Mercator, 4-10, 4-11 (illus)

intersection methods
  map and compass, 6-15 (illus)
  straightedge, 6-16 (illus)

joint operations graphic, 2-5 (illus), 2-6
  air, D-1
  ground, D-1

latitude, 4-1 thru 4-4
longitude, 4-1 thru 4-4

M2 compass, G-1, G-2
magnetic north, 6-1
maps
  foreign, I-1

    military city map, 2-6
    photomap, 2-5
    planimetric, 2-5
    special, 2-6
    substitutes for military maps, 2-7
    topographic, 2-5
    types, 2-1
marginal information, 3-1 thru 3-4, 3-4 (illus)
    colors, 3-6
    symbols, 3-6
measures
    angular, C-1
    conversion factors, C-2 (table)
    English system, C-1 (table)
    metric system, C-1 (table)
mil, 6-1
military city map, 2-4
mounted navigation
    combination, 12-4
    dead reckoning, 12-6
    duties, 12-1
    effects of terrain, 12-1
    terrain association, 12-3, 12-4
    vehicle capabilities, 12-2

navigation methods
    arctic, 13-9
    combination of techniques, 11-8
    dead reckoning, 11-14
    deserts, 13-1
    jungles, 13-6
    mountains, 13-4
    mounted, 12-1
    night, 11-15
    terrain association, 11-16
    urban areas, 13-10
night vision goggles
    AN/PVS-5, H-1
    AN/PVS-7, H-1

orienteering, civilian, F-20
orienteering, military
    control points, F-10
    course, F-2 thru F-5
    equipment, F-5, F-6
    map symbols, F-1 thru F-19 (illus)

  officials, F-5
  safety, F-10
  scoring, F-4
  start/finish area, F-5
  techniques, F-19
orienting the map methods
  using a compass, 11-1, 11-2 (illus)
  using field expedients, 11-6
  using terrain association, 11-5 (illus)
overlay
  aerial photograph, 7-3, 7-4 (illus)
  map, 7-1, 7-3 (illus)

PADS (position and azimuth determining system), H-3
photographs, aerial
  advantages, 8-1
  disadvantages, 8-1
  features, 8-17
  film types, 8-7
  indexing, 8-10 thru 8-13
  numbering and titling, 8-7
  scale determination, 8-8, 8-9 (illus)
  stereovision, 8-18 thru 8-22 (illus)
  types, 8-1 thru 8-7
photomap, 2-5
photomosaic, 2-6
planimetric map, 2-5
point designation grid, 8-14 thru 8-17 (illus)
polar coordinates, 6-20, 6-20 (illus)
polar plot, 6-20 (illus)
prime meridian, 4-9, 4-10 (illus), 4-10 (table)
procurement, 2-1, 2-2
profiles, construction, 10-20
protractor, 6-5
  types, 6-6 (illus)
  usage, 6-7, 6-8

QRMP (quick response multicolor printer), H-3, H-4

range estimation, factors of, 5-1 (table), 5-14
relief depicting methods
  contour lines, 10-1
  form lines, 10-1
  hachures, 10-1
  layer tinting, 10-1
  shaded relief, 10-1

representative fraction (scale), 2-2, 2-3, 2-4, 5-1
    large
    medium
    small
resection method
    map and compass, 6-17 (illus)
    modified, 6-10 (illus)
    straightedge, 6-18 (illus)
ridgeline, 10-11 (illus)
ridgelining, 10-19, 10-20 (illus)

safety, 1-2
scale (representative fraction), 2-3, 2-4, 5-1
sketches, military, A-1
skill progression, navigation
    enlisted, 1-1
    officer, 1-1
slopes (all illus)
    concave, 10-6 (illus)
    convex, 10-7 (illus)
    gentle, 10-5, 10-6
    percentage, 10-8, 10-9
    steep, 10-5 (illus)
SOSES (shape, orientation, size, elevation, slope), 10-18, 10-19
special map, 2-6
stereovision
    mirror stereoscope, 8-21 (illus)
    overlap, 8-10 (illus)
    pocket stereoscope, 8-20 (illus)
    side lap, 8-20 (illus)
    stereopair, 8-21 (illus)
streamlining, 10-19, 10-20 (illus)
sustainment program
    certification, 14-1
    development, 14-1
    training guidance, 14-1
symbols, map
    military, 3-6
    topographic, 3-4 (illus)

terrain analysis, tactical
    METT-T, 11-7
    OCOKA, 11-6
    route selection 11-12, 11-13
terrain association, 11-7, 11-8 (illus), 12-3 thru 12-6, 12-8
terrain features, 10-11 thru 10-16, 10-17 (illus)

    interpretation, 10-17 thru 10-20
    major, 10-12 thru 10-14 (illus)
    minor, 10-14, 10-16 (illus)
    profiles, 10-20 thru 10-24
    supplementary, 10-16, 10-17 (illus)
terrain model, 2-6
terrain types
    arctic, 13-9, 13-10
    deserts, 13-1 thru 13-4
    jungles, 13-6 thru 13-9
    mountains, 13-4, 13-6
    urban, 13-10
topographic map, 2-5
train-the-trainer program, 14-1, 14-2
training material, exportable, E-1
true north, 6-1

Military/Reference

$18.95
($28.95 in Canada)

The U.S. Army's official guide to map reading, determining location, and navigating.

For a soldier, knowing where you are is a matter of life and death, and so it comes as no surprise that the Army has produced the most complete, clear, and thorough guide to map reading and navigation available.

The book starts with a comprehensive explanation of the meaning and uses of maps, whether photographic, planimetric (standard-style), or topographic, then proceeds to the use of those maps, discussing compass techniques, celestial navigation, and determination of distance. There is a detailed section on interpreting topographic maps, with notes on tactical considerations for differing terrain, as well as determining the ease of movement through an area.

The book's crucial, well-illustrated chapters have invaluable information on:

Training Strategy • Maps • Marginal Information and Symbols
Grids • Scale and Distance • Direction • Overlays
Aerial Photographs • Navigation Equipment and Methods
Elevation and Relief • Terrain Association • Mounted Land Navigation
Navigation in Different Types of Terrain • Unit Sustainment

There is also information on field sketching, the tricky art of map folding, units of measure and conversion factors, map symbols, orienteering, and the global positioning system (GPS).

For the adult outdoorsman venturing into the wild, the Boy Scout, or the serious military buff, the **U.S. Army Map Reading and Land Navigation Handbook** is an indispensable, must-have book.

THE LYONS PRESS
Guilford, CT 06437
www.LyonsPress.com

The Lyons Press is an imprint
of The Globe Pequot Press

Cover design by Peter Blossom
Printed in the United States of America

$18.95
ISBN 1-59228-382-9

UPC
00382
6 60813 01895 3

EAN
51895>
9 781592 283828

Copyrighted Material

Celestial Navigation in a Teacup

Rodger E Farley

Teacup Navigation

C-PLATH HAMBURG

Celestial Navigation in a Teacup

Formerly "The Armchair Celestial Navigator"

Concepts, Math, History, the Works, but Different

Teacup Navigation

Rodger E. Farley

Contents

Preface
Variable and Acronym List
Chapter 1 Early Related History
Chapter 2 Review of Fundamentals
Chapter 3 Celestial Navigation Concepts
Chapter 4 Calculations for Lines of Position
Chapter 5 Measuring Altitude with the Sextant
Chapter 6 Corrections to Measurements
Chapter 7 Reading the Nautical Almanac
Chapter 8 Sight Reduction
Chapter 9 Putting it Together and Navigating
Chapter 10 Star Identification
Chapter 11 Special Topics
Chapter 12 Lunars
Chapter 13 Coastal Navigation using the sextant

Appendix 1 Generalized Sight Reduction and Intercept Work Sheet
Appendix 2 Making your very own Octant
Appendix 3 On-Line Resources for Celestial Navigation
Appendix 4 Celestial Navigation via the S-Tables and Ageton's Method

6th Edition

Copyright 2002, 2009, 2010, 2011 Rodger E. Farley
Teacup Navigation Publishing. All rights reserved.
My web site: http://mysite.verizon.net/milkyway99/index.html
I assume no liabilities of any form from any party: Warning, user beware!
This is for educational purposes only.

Preface

Growing up I had always been fascinated by the thought of navigating by the stars. However, it instinctively seemed to me an art beyond my total understanding. Why, I don't know other than celestial navigation has always had a shroud of mystery surrounding it (no doubt to keep the hands from mutiny). Some time in my 40s I began to discard my preconceived notions regarding things that required 'natural' talent, and thus I began a journey of discovery. This book represents my efforts at teaching myself 'celestial', although it is not comprehensive of all my studies in this field. Like most educational endeavors one may sometimes plunge too deeply in seeking arcane knowledge and risk losing the interest and attention of the reader. With that in mind this book is dedicated simply to removing the cloak of mystery; to teach the concepts, some interesting history, the techniques, and computational methods using the simple pocket scientific calculator (or better yet make your own navigation software). And yes, also how to build your own navigational tools.

My intention is for this to be used as a self-teaching tool for those who have a desire to learn celestial from the intuitive, academic, and practical points of view. This book should also interest experienced navigators who are tired of simply 'turning the crank' with tables and would like a better behind-the-scenes knowledge. With the prevalence of hand electronic calculators, the traditional methods of using sight-reduction tables with pre-computed solutions will hardly be mentioned here. I am referring to the typical Hydrographic Office methods H.O. 249 and H.O. 229. Rather, the essential background and equations to the solutions will be presented such that the reader can calculate the answers precisely with a hand calculator and understand the *why*. You will need a scientific calculator, those having trigonometric functions and their inverse functions. Programmable graphing calculators such as the TI-86 and TI-89 are excellent for the methods described in the book. To those readers familiar with 'celestial', they will notice that I have departed the usual norms found in celestial navigation texts. I use a consistent sign convention which allows me to discard same-name and opposite-name rules.

Rodger Farley 2002

Variable and Acronym List

Hs	Altitude angle as reported on the sextant scale
Ha	Apparent altitude angle
Ho	Observed, or true altitude angle
Hc	Calculated altitude angle
IC	Index correction
SD	Angular semi-diameter of sun or moon
UL	Upper limb of sun or moon
LL	Lower limb of sun or moon
GHA	Greenwich hour angle
GHA_{hour}	Greenwich hour angle as tabulated at a specific integer hour
DEC	Declination angle
DEC_{hour}	Declination angle as tabulated at a specific integer hour
SHA	Sidereal hour angle
LHA	Local hour angle
Zo	Uncorrected azimuth angle
Zn	Azimuth angle from true north
v	Hourly variance from the nominal GHA rate, arcmin per hour
d	Hourly declination rate, arcmin per hour
h_{eye}	Eye height above the water, meters
Corr^{DIP}	Correction for dip of the horizon due to eye height
Corr^{v}	Correction to the tabular GHA for the variance v
Corr^{d}	Correction to the tabular declination using rate d
Corr^{GHA}	Correction to the tabular GHA for the minutes and seconds
Corr^{ALT}	Correction to the sextant altitude for refraction, parallax, and semidiameter
R	Correction for atmospheric refraction
D_{offset}	Offset distance using the intercept method, nautical miles
LAT	Latitude
LON	Longitude
LAT_{A}	Assumed latitude
LON_{A}	Assumed longitude
LAT_{DR}	Estimated latitude, or dead-reckoning latitude
LON_{DR}	Estimated longitude, or dead-reckoning longitude
LOP	Line of position
LAN	Local apparent noon
LMT	Local mean time

Chapter One

Early Related History

Why 360 degrees in a circle?

If you were an early astronomer you would have noticed that the stars rotate counterclockwise (ccw) about Polaris at the rate of seemingly once per day. And that as the year moved on the constellation's position would slowly crank around as well, once per year ccw. The planets were mysterious and thought to be gods as they roamed around the night sky, only going thru certain constellations named the zodiac (in the ecliptic plane). You would have noticed that after ¼ of a year had passed, or ~ 90 days, that the constellation had turned ccw about ¼ of a circle. It would have seemed that the angle of rotation per day was 1/90 of a quarter circle. A degree could be thought of as a heavenly angular unit, which is quite a coincidence with the Babylonian base 60 number system which established the angle of an equilateral triangle as 60º.

The Egyptians had divided the day into 24 hours, and the Mesopotamians further divided the hour into 60 minutes, 60 seconds per minute. It is easy to see the analogy between angle and clock time, since the angle was further divided into 60 arcminutes per degree, and 60 arcseconds per arcminute. An arcminute of a great circle on the surface of our planet defined the unit of distance; a nautical mile, which = 1.15 statute miles. By the way, mile comes from the Latin *milia* for 1000 double paces of a Roman soldier.

Size of the Earth

In the Near East during the 3rd century BC lived an astronomer-philosopher by the name of Eratosthenes, who was the director of the Egyptian Great Library of Alexandria. In one of the scroll books he read that on the summer solstice June 21 in Syene (south of Alexandria), one could see the sun's reflection at the bottom of deep wells (on tropic of Cancer). He wondered that on the same day in Alexandria, a stick would cast a measurable shadow. The ancient Greeks had hypothesized that the earth was round, and this observation by Eratosthenes confirmed the curvature of the Earth. But how big was it? On June 21 he measured the angle cast by the stick and saw that it was approximately 1/50th of a full circle (7.2 degrees). He hired a man to pace out the distance between Alexandria and Syene, who reported it was 500 miles. If 500 miles was the arc length for 1/50 of a huge circle, then the Earth's circumference would be 50 times longer, or 50 • 500 = 25000 miles. Simple tools and an enlightened mind can produce extraordinary results, considering he was less than 1% off.

Calendar

Very early calendars were based on the lunar month, 29 ½ days. This produced a 12-month year with only 354 days. Unfortunately, this would 'drift' the seasons backwards 11 ¼ days every year according to the old lunar calendars. Julius Caesar abolished the lunar year, used instead the position of the sun and fixed the true year at 365 ¼ days, and decreed a leap day every 4 years to make up for the ¼ day loss per Julian year of 365 days. Their astronomy was not accurate enough to know that a tropical year is 365.2424 days long; 11 minutes and 14 seconds shorter than 365 ¼ days. This difference adds a day every 128.2 years, so in 1582 the Gregorian calendar was instituted in which 10 days that particular October were dropped to resynchronize the calendar with the seasons, and 3 leap year days would not be counted every 400 years to maintain synchronicity.

Early Navigation

The easiest form of navigating was to never leave sight of the coast. Species of fish and birds, and the color and temperature of the water gave clues, as well as the composition of the bottom. When one neared the entrance to the Nile on the Mediterranean, the bottom became rich black, indicating that you should turn south. Why venture out into the deep blue water? Because of coastal pirates, and storms that pitch your boat onto a rocky coast. Presumably also to take a shorter route. One could follow flights of birds to cross the Atlantic, from Europe to Iceland to Greenland to Newfoundland. In the Pacific, one could follow birds and know that a stationary cloud on the horizon meant an island under it. Polynesian navigators could also read the swells and waves, determine in which direction land would lie due to the interference in the wave patterns produced by a land mass.

And then there are the stars. One in particular, the north pole star, Polaris. For any given port city, Polaris would always be more or less at a constant altitude angle above the horizon all year at any hour. Latitude hooks, the kamal, and the astrolabe are ancient tools that allowed one to measure the altitude of the Pole Star. So long as your last stage of sailing was due east or west, you could get back home if Polaris was at the same altitude angle as when you left. If you knew the altitude angle of Polaris for your destination, you could sail north or south to pick up the correct Polaris altitude, then 'run down the latitude' until you arrive at the destination (interestingly Polaris was not always the Pole Star). Determining longitude would remain a mystery for many ages until accurate clocks could be made. Techniques used in surveying were adopted for use in navigation, two of which are illustrated on the next page.


POLARIS
North Star
N pole
lower angle
higher angle


Home
From
Trade Winds
To
Destination

'Running down the latitude' from home to destination,changing latitude where safe to pick up trade winds

Surveying techniques with absolute angles and relative angles


A
B
120°
160°
80°
C
a
b
N
magnetic compass
N ←
MAP of
Mountains
A,B,C
80°
120°
160°
Observer Location

Fix by magnetic bearings


B
A
C
a
b
Observer Location
Equal angles inside of circular arc
Map of mountain peaks A,B,C

Fix by 3-body circular arc technique

Chapter Two

Review of Fundamentals

Orbits

The Earth's orbit about the Sun is a slightly elliptical one, with a mean distance from the Sun equal to 1 AU (AU = Astronomical Unit = 149,597,870. km). This means that the Earth is sometimes a little closer and sometimes a little farther away from the Sun than 1 AU. When it's closer, it is like going downhill where the Earth travels a little faster thru its orbital path. When it's farther away, it is like going uphill where the Earth travels a little slower. If the Earth's orbit were perfectly circular, and was not perturbed by any other body (such as the Moon, Venus, Mars, or Jupiter), in which case the orbital velocity would be unvarying and it could act like a perfect clock. This brings us to the next topic…

Mean Sun

The mean Sun is a fictional Sun, the position of the Sun in the sky if the Earth's axis was not tilted and its orbit were truly circular. We base our clocks on the mean Sun, and so the mean Sun is another way of saying the year-averaged 24 hour clock time. This leads to the situation where the true Sun is up to 16 minutes too fast or 14 minutes too slow from clock reckoning. This time difference between the mean Sun and true Sun is known as the Equation of Time. The Equation of Time at local noon is noted in the Nautical Almanac for each day. For several months at a time, local noon of the true Sun will be faster or slower than clock noon due to the combined effects of Earth's orbital eccentricity and orbital velocity. When we graph the Equation of Time in combination with the Sun's declination angle, we produce a shape known as the analemma. The definition and significance of solar declination will be explained in a later section.



The Analemma: a graphical presentation of the equation of time

Time

With a sundial to tell us local noon, and the equation of time to tell us the difference between solar and mean noon, a simple clock could always be reset daily. We think we know what we mean when we speak of time, but how to measure it? If we use the Earth as a clock, we could set up a fixed telescope pointing at the sky due south with a vertical hair line in the eyepiece and pick a guide star that will pass across the hairline. After 23.93 hours (a sidereal day, more later) from when the guide star first crossed the hairline, the star will pass again which indicates that the earth has made a complete revolution in inertial space. Mechanical clocks could be reset daily according to observations of these guide stars. A small problem with this reasonable approach is that the Earth's spin rate is not completely steady, nor is the direction of the Earth's spin axis. It was hard to measure, as the Earth was our best clock, until atomic clocks showed that the Earth's rate of rotation is gradually slowing down due mainly to tidal friction, which is a means of momentum transference between the Moon and Earth. Thus we keep fiddling with the definition of time to fit our observations of the heavens. But orbital calculations for planets and lunar positions (ephemeris) must be based on an unvarying absolute time scale. This time scale that astronomers use is called Ephemeris Time. Einstein of course disagrees with an absolute time scale, but it is relative to Earth's orbital speed.

Time Standards for Celestial Navigation

Universal Time (UT, solar mean time, GMT)

This standard keeps and resets time according to the mean motion of the Sun across the sky over Greenwich England, the prime meridian, (also known as Greenwich Mean Time GMT). UT is noted on a 24-hour scale, like military time. The data in the nautical almanac is based on UT.

Universal Time Coordinated (UTC)

This is the basis of short wave radio broadcasts from WWV in Fort Collins Colorado and WWVH in Hawaii (2.5, 5,10,15, 20 MHz). It is also on a 24-hour scale. It is synchronized with International Atomic Time, but can be an integral number of seconds off in order to be coordinated with UT such that it is no more than 0.9 seconds different from UT. Initial calibration errors when the atomic second was being defined in the late 1950's, along with the gradual slowing of the Earth's rotation, we find ourselves with one more second of atomic time per year than a current solar year. A leap second is added usually in the last minute of December or June to be within the 0.9 seconds of UT. UTC is the time that you will use for celestial navigation using the nautical almanac, even though strictly speaking UT is the proper input to the tables. The radio time ticks are more accessible, and 0.9 seconds is well within reasonable error.

Sidereal Year, Solar Year, Sidereal Day, Solar Day

There are 365.256 solar days in a sidereal year, the Earth's orbital period with respect to an inertially fixed reference axis (fixed in the 'ether' of space, or in actuality with respect to very distant stars). But due to the backward clockwise precession drift of the equinox (the Earth orbits counterclockwise as viewed above the North Pole), our solar year (also referred to as tropical year) catches up faster at 365.242 solar days. We base the calendar on this number as it is tied into the seasons. With 360 degrees in a complete circle, coincidentally (or not), that's approximately 1 degree of orbital motion per day (360 degrees/365.242 days). That means inertially the Earth really turns about 361 degrees every 24 hours in order to catch up with the Sun due to orbital motion. That is our common solar (synodic) day of 24 hours. However, the true inertial period of rotation is the time it takes the Earth to spin in 360 degrees using say, the fixed stars as a guide clock. That is a sidereal day, 23.93447 hours (~ 24 x 360/361). The position of the stars can be measured as elapsed time from when the celestial prime meridian passed, and that number reduced to degrees of celestial longitude (SHA) due to the known rotational period of the Earth, a sidereal day. As a side note, this system of sidereal hour angle SHA is the negative of what an astronomer uses, which is right ascension (RA).


Earth's Spin Direction
GREENWICH AT NOON
ONE DAY LATER
361 degrees of rotation per 24 hours
1 degree of orbital motion
1 degree to catch up with the Sun
DIRECTION OF ORBIT
Sun

The difference between a Sidereal day and a Solar day

Latitude and Longitude

I will not say much on this, other than bringing your attention to the illustration, which show longitude lines individually, latitude lines individually, and the combination of the two. This gives us a grid pattern by which unique locations can be associated to the spherical map using a longitude coordinate and a latitude coordinate. The prime N-S longitude meridian (the zero longitude) has been designated as passing thru the old royal observatory in Greenwich England (established 1884). East of Greenwich is positive longitude, and west of Greenwich is negative longitude. North latitude coordinates are positive numbers, south latitude coordinates are negative.


N pole
Longitude Lines
W
E
-30 -20 -10 0 10 20 30
Prime Meridian
180
150
- LON
+ LON
N pole
-90
90
-30 -20 -10 10 20 30 40 50
W
0
E
Latitude Lines
80 70 60 50 40 30 20 10 0 -10 -20
Equator
N pole
70 60 50 40 30 20 10 0
LAT
- LAT
-10 -20 -30
S pole
Combined Lines for
a Spherical Grid
0 Longitude, 0 Latitude

LONGITUDE and LATITUDE
REVIEW of DEFINITIONS

Maps and Charts

The most common chart type is the modern *Mercator projection*, which is a mathematically modified version of the original cylindrical projection. On this type of chart, for small areas only in the map's origin, true shapes are preserved, a property known as *conformality*. Straight line courses plotted on a Mercator map have the property of maintaining the same bearing from true north all along the line, and is known as a *rumb line*. This is a great aid to navigators, as the course can be a fixed bearing between waypoints.

If you look at a globe and stretch a string from point A to point B, the path on the globe is a *great circle* and it constitutes the shortest distance between two points on a sphere. The unfortunate characteristic of a great circle path is that the bearing relative to north changes along the length of the path, most annoying. On a Mercator map, a great circle course will have the appearance of an arc, and not look like the shortest distance. In fact, a rumb line course mapped onto a sphere will eventually spiral around like a clock spring until it terminates at either the N or S pole, known mathematically as a loxodrome.

Chapter Three

Celestial Navigation Concepts

There are three common elements to celestial navigation, whether one is floating in space, or floating on the ocean. They are; 1) knowledge of the positions of heavenly bodies with respect to time, 2) measurement of the time of observation, and 3) angular measurements (altitudes) between heavenly objects and a known reference. The reference can be another heavenly object, or in the case of marine navigation, the horizon. If one only has part of the required 3 elements, then only a partial navigational solution will result. In 3 dimensions, one will need 3 independent measurements to establish a 3-D position fix. Conveniently, the Earth is more or less a sphere, which allows an ingeniously simple technique to be employed. The Earth, being a sphere, means we already know one surface that we must be on. That being the case, all we need are 2 measurements to acquire our fixed position on the surface.

Here listed is the Generalized Celestial Navigation Procedure:
Estimate the current position
Measure altitude angles of identified heavenly bodies
Measure time at observation with a chronometer
Make corrections to measurements
Look up tabulated ephemeris data in the nautical almanac
Employ error-reduction techniques
Employ a calculation algorithm
Map the results, determine the positional fix

The 4 basic tools used are the sextant, chronometer, nautical almanac, and calculator (in lieu of pre-calculated tabulated solutions).

In this book and in most celestial navigation texts, altitudes (elevation angle above the horizon) of the observed heavenly object s are designated with these variables:
Hs = the raw angle measurement reported by the sextant's scale.
Ha = the apparent altitude, when instrument errors and horizon errors are accounted for.
Ho = the true observed altitude, correcting Ha for atmospheric refraction and geometric viewing errors (parallax) associated with the heavenly object.

THE FOUR BASIC CELESTIAL NAVIGATION TOOLS

NAUTICAL ALMANAC
2003 COMMERCIAL EDITION
2003
JAN. 1 2003 THRU DEC. 31 2003

Sextant, Chronometer (time piece), Nautical Almanac, and a Calculator

Geographical Position (GP)

The geographical position of a heavenly object is the spot on the Earth's surface where an observer would see the object directly over head, the zenith point. You can think of it as where a line connecting the center of the Earth and the center of the heavenly object intersects the Earth's surface. Since the Earth is spinning on its axis, the GP is always changing; even for Polaris since it is not exactly on the axis (it is close…)

Circles of Position (COP)

Every heavenly object seen from the Earth can be thought of as shining a spotlight on the Earth's surface. This spotlight, in turn, cast concentric circles on the Earth's surface about the GP. At a given moment anybody anywhere on a particular circle will observe the exact same altitude for the object in question. These are also known as circles of constant altitude.
For the most part, stars are so far away that their light across the solar system is parallel. The Sun is sufficiently far away that light from any point on the Sun's disk will be more or less parallel across the face of the Earth. Not so for the Moon.


DISTANT OBJECT CENTER
CENTER-to-CENTER LINE
PARALLEL RAYS OF LIGHT
GEOGRAPHICAL POSITION AT ZENITH POINT
ALTITUDE A
ALTITUDE B
BOAT B
BOAT A
LOCAL HORIZON
SAME AS ALTITUDE B
EARTH CENTER
SAME AS ALTITUDE A
CIRCLES OF CONSTANT ALTITUDE
CIRCLES OF CONSTANT ALTITUDE
CIRCLES OF CONSTANT ALTITUDE FOR A DISTANT OBJECT

Parallax

This is a geometrical error that near-by heavenly objects, namely the Moon, are guilty of. Instead of a spotlight of parallel light, a near-by object casts more of a conical floodlight. The reason why parallax matters to us is because in the nautical almanac, the center-to-center line direction from the Earth to the heavenly object is what is tabulated. The particular cone angle is not tabulated, and needs to be calculated and added to the observed altitude to make an apples-to-apples comparison to the information in the almanac. The Moon's parallax can be almost 1 degree, and needs to be accounted for. The parallax can be calculated easily, if we know how far away the heavenly object is (which we do). From the illustration, it should be apparent that the parallax is a function of the altitude measurement. It is a constant number for anyone on a particular circle of constant altitude. The particular parallax angle correction corresponding to the particular altitude is known as *parallax-in-altitude* PA. The maximum parallax possible is when the altitude is equal to zero (moonrise, moonset) and is designated as the *horizontal parallax* HP.


NEAR OBJECT CENTER
CONICAL RAYS OF LIGHT
CENTER-to-CENTER LINE
PARALLAX PA for boat B
PARALLAX PA for boat A
GEOGRAPHICAL POSITION
AT ZENITH POINT
ALTITUDE A
ALTITUDE B
SAME AS
ALTITUDE B
EARTH CENTER
SAME AS
ALTITUDE A
HP
CIRCLES OF
CONSTANT ALTITUDE
CIRCLES OF
CONSTANT ALTITUDE
CIRCLES OF CONSTANT ALTITUDE
FOR A NEAR OBJECT

Line of Position (LOP)

Circles of Position can have radii thousands of miles across, and in the small vicinity of our estimated location on the map, the arc looks like a line, and so we draw it as a line tangent to the circle of constant altitude. This line is necessarily perpendicular to the azimuth direction of the heavenly object. One could be anywhere (within reason) on that line and measure the same altitude to the heavenly object.


Celestial Sphere
Ntrue
NE
NW
E
Azimuth Angle
H altitude
W
LOP
SE
SW
HORIZON
S
N
Heading
Azimuth Zn
W
E
LOP
90°
S
H altitude

Navigational Fix

To obtain a 'fix', a unique latitude and longitude location, we will need two heavenly objects to observe. Reducing the measurements to 2 LOPs, the spot where it crosses the 1st line of position is our pin-point location on the map, the navigational fix. This is assuming you are stationary for both observations. If you are underway and moving between observations, then the first observation will require a '*running fix*' correction. See the illustration of the navigational fix to see the two possibilities with overlapping circles of constant altitude. The circles intersect in two places, and the only way to be on both circles in the same place is to be on one of the two intersections. Since we know the azimuth directions of the observations, the one true location becomes obvious. Measurement errors of angle and time put a box of uncertainty around that pinpoint location, and is called the *error box*.

We could of course measure the same heavenly object twice, but at different times of the day to achieve the same end. This will produce two different circles of constant altitude, and where they intersect is the fix, providing you stay put. If you're not, then running fix corrections can be applied here as well. In fact, this is how navigating with the Sun is done while underway with observations in the morning, noon, and afternoon.

More often than not, to obtain a reliable fix, the navigator will be using 6 or more heavenly objects in order to minimize errors. Stars or planets can be mistakenly identified, and if the navigator only has 2 heavenly objects and one is a mistake, he/she may find themselves in the middle of New Jersey instead of the middle of the Atlantic. It is improbable that the navigator will misidentify the Sun or Moon (one would hope…), but measurement errors still need to be minimized. The two measurements of time and altitude contain *random errors* and *systematic errors*. One can also have calculation errors and misidentification errors, correction errors, not to mention that you can simply read the wrong numbers from the almanac.

The random errors in measurement are minimized by taking multiple 'shots' of the same object (~3) at approximately one minute intervals, and averaging the results in the hope that the random errors will have averaged out to zero. Systematic errors (constant value errors that are there all the time) such as a misaligned sextant, clocks that have drifted off the true time, or atmospheric optical effects different from 'normal' viewing conditions all need to be minimized with proper technique and attention to details, which will be discussed later. Another source of systematic error is your own 'personal error', your consistent mistaken technique. Perhaps you are always reading a smaller angle, or you are always 1 second slow in the clock reading. This will require a 'personal correction'.


THE NAVIGATIONAL FIX
with 2 CELESTIAL OBJECTS
Azimuth Direction of Object #2
You are here (see inset for details)
OBJECT #2
Azimuth Direction of Object #1
Geographical Position of Object #2
Circles of Constant Altitude
Geographical Position of Object #1
OBJECT #1


#2
N TRUE
#1
NE
NW
LOP #2
E
H2
H1
Azimuth Line #2
Azimuth Line #1
W
LOP #1
SE
SW
HORIZON
S

Surfaces of Position (SOP)

If you were floating in space, you could measure the angle between the Sun and a known star. There will exist a conical surface with the apex in the Sun's center with the axis of the cone pointing in the star's direction whereby any observer on that conical surface will measure the exact same angle. This is a Surface of Position, where this one measurement tells you only that you are somewhere on the surface of this imaginary cone. Make another measurement to a second star, and you get a second cone, which intersects the first one along two lines. Now, the only way to be on both cones at the same time is to be on either of those 2 intersection lines. Make a third measurement between the Sun and a planet, and you will create a football shaped Surface of Position, with the ends of the football centered on the Sun and the planet (see pg 7). This third SOP intersects one of the two lines at one point. That is your position in 3-D.


1st Observation, angle A
from star #1 to Sun
STAR #1
A
Sun
2nd Observation, angle B
from star #2 to Sun
STAR #2
Sun
B
3rd Observation, angle C
from Sun to Planet
Sun
C
Planet

Merge the 2 cones together to produce
2 Lines of Position (LOP)



Merge the 2 lines of position and the
'football' shape to intersect the position fix


Sun
Sun
Observer
Position Fix

Notice that if the football shape enlarges to infinity, the end points locally resemble cones. This is what star cones 1&2 actually are. If you used a third star instead of a planet, you would create another pair of intersection lines, one of which will be collinear with one of the 1st pair. It will not get you a point. You need to have a nearby object for the final fix. The football shape is merely the circular arc method revolved about an axis to create a 3-D surface.

Celestial Sphere

The *celestial sphere* is our star map. It is not a physical sphere like the Earth's surface. It is a construction of convenience. The stars do have a 3-dimensional location in space, but for the purposes of navigation we mostly need to know only their direction in the sky. For stars, their distance is so great that their dim light across the solar system is more or less parallel. With that thought, we can construct a transparent sphere which is like a giant bubble centered over the Earth's center where the fixed stars are mapped, painting the stars, Sun and our solar system planets on the inside of this sphere like a planetarium. We are on the inside of the bubble looking out. The celestial sphere has an equatorial plane and poles just like the Earth. In fact, we define the *celestial poles* to be an extension of Earth's poles, and the two equatorial planes are virtually the same. It just does not spin. It is fixed in space while the Earth rotates inside it.

In our lifetimes, the stars are more or less fixed in inertial space. Their very slow movement is called *proper motion*. However, the apparent location of a star changes slightly on the star map due to *precession* and *nutation* of the Earth's axis, as well as *annual aberration*. That is, the Earth's spin axis does not constantly point in the same direction. We usually think of the North Pole axis always pointing at Polaris, the North Star (it's currently 41' off from the pole). It wiggles (nutates) around it now, but in 10000 years it will point and wiggle about Deneb. However, 5000 years ago it pointed at Thuban and was used by the ancient Egyptians as the Pole Star! The Earth wobbles (precesses) in a cone-like shape just like a spinning top, cycling once every 25800 years. We know the cone angle to be the same as the 23.44 degree tilt angle of the Earth's axis, but even that tilt angle wiggles (nutates) up and down about 0.15 arcminutes. There are two periods of nutation, the quickest equal to ½ year due to the Sun's influence, and the slowest (but largest) lasting 18.61 years due to the Moon's precessing (wobbling) orbital plane tugging on the earth.

Aberration is the optical tilting of a star's apparent position due to the relative velocity of the earth vs. the speed of light. Think of light as a stream of particles like rain (photons) speeding along at 299,792 kilometers/s. The Earth is traveling at a mean orbital velocity of 29.77 kilometers/s. When you run in the rain, the direction of the rain seems to tilt forward. The same effect is true of light, with the least effect from stars near the ecliptic plane, and the most effect from stars with the highest elevation from the ecliptic plane. This effect can be as great as 20.5 arcseconds (3600 x arcTan(29.77/299792)).

The *ecliptic plane* (Earth's orbital plane at a given reference date, or *epoch*) mapped onto the celestial sphere is where you will also see the constellations of the *zodiac* mapped. These are the constellations that we see planets traverse across in the night sky, and therefore got special attention from the ancients. Instead of describing the location of a star on the celestial sphere map with longitude and latitude, it is referred to as Sidereal Hour Angle (SHA) and declination (DEC) respectively. Sidereal Hour Angle is a celestial version of west longitude, and declination is a celestial version of latitude. But this map needs a reference, a zero point where its *celestial prime meridian* and celestial equator intersect. That point just happens to be where the Sun is located on the celestial sphere during the spring (*vernal*) equinox, and is known as the *Point of Aries*. It is the point of intersection between the mean equatorial plane and the ecliptic plane. Since the Earth's axis wiggles and wobbles, a reference mean location for the equatorial plane is used. Due to precession of the Earth's axis, that point is now in the zodiacal constellation of Pisces, but we say Aries for nostalgia. That point will travel westward to the right towards Aquarius thru the zodiac an average of 50.3 arcseconds per year due to the 25800 year precession cycle. Fortunately, all of these slight variations are accounted for in the tables of the nautical and astronomical almanacs.

Local Celestial Sphere

This is the celestial sphere as referenced by a local observer at the center with the true horizon as the equator. *Zenith* is straight up, *nadir* is straight down. The local meridian circle runs from north to zenith to south. The prime vertical circle runs from east to zenith to west.



Local celestial sphere for a ground observer


EARTH'S PRECESSION and NUTATION
23.44 °
Mean Precession motion is clockwise in a conical shape; 25800 years per cycle
Wiggley motion is Nutation
Basic nutation periods range from 0.5 years to 18.6 years
Earth's Daily Rotation counter clockwise (CCW)


The Celestial Sphere
Celestial North Pole
CELESTIAL PRIME MERIDIAN
Zero Hour Angle
Sidereal Hour Angle
12th Hour Angle
Celestial Equator
SPRING EQUINOX
Point of Aries
Aries
Pisces
SHA
Aquarius
Declination
EQUATORIAL PLANE
Capricorn
Tarus
23.44°
September
Sagittarius
N
Gemini
December
June
S
ECLIPTIC PLANE
(ORBIT PLANE)
March
Cancer
ZODIAC
Scorpio
Leo
Libra
Virgo
FALL EQUINOX
Celestial South Pole

Greenwich Hour Angle GHA

The *Greenwich Hour Angle* (GHA) of a heavenly object, is the west longitude of that object at a given instant in time relative to the Earth's prime meridian. The Sun's GHA is nominally zero at noon over Greenwich, but due to the slight eccentricity of Earth's orbit (mean vs. true sun) it can vary up to 4 degrees. GHA can refer to any heavenly object that you are using for navigation, including the position of the celestial prime meridian, the point of Aries.

Bird's-eye view above the North Pole



Greenwich Hour Angle of Aries $\boldsymbol{GHA_{Aries}}$ ***(or*** $\boldsymbol{GHA\gamma}$***)***

The point of Aries is essentially the zero longitude and latitude of the celestial sphere where the stars are mapped. The sun, moon, and planets move across this map continuously during the year. SHA and declination relate the position of a star in the star map, and $\mathbf{GHA_{Aries}}$ relates the star map to the Earth map. GHA_{Aries} is the position of the zero longitude of the star map, relative to Greenwich zero longitude, which varies continuously with time because of Earth's rotation. The relationship for a star is thus:

$GHA = GHA_{Aries} + SHA$ = the Greenwich hour angle of a star. The declination (celestial latitude) of the star needs no 'translation' as it remains the same in the Earth map as in the star map.

Bird's-eye view above the North Pole



Local Hour Angle LHA

The *Local Hour Angle* (LHA) is the west longitude direction angle of a heavenly object relative to a local observer's longitude (not Greenwich). This leads to the relationship:

LHA = GHA + East Longitude Observer, or
LHA = GHA - West Longitude Observer

If the calculated value of LHA > 360, then $\text{LHA} = \text{LHA}_{\text{CALCULATED}} - 360$

Bird's-eye view above the North Pole



When we are speaking of the Sun, a pre-meridian passage (negative LHA or 180<LHA < 360) means that it is still morning. A post-meridian passage (positive LHA, or 0<LHA<180) means that it is literally after noon.
At exact local noon, LHA = 0

Declination DEC

As stated earlier, the *declination* of an object is the celestial version of latitude measured on the celestial sphere star-map. Due to the tilt of the Earth's axis of 23.44 degrees, the sun and planets change their declinations on the celestial sphere continuously during the year. The stars do not. The Sun's declination follows nearly a perfect sine wave where over the course of 365.24 days it varies northwards 23.44 degrees and southwards –23.44 degrees. This is a crucial piece of information for the determination of latitude using the Sun.



As one can see, maximum declination occurs with the summer solstice which has the longest hours of daily sun, the minimum declination with the winter solstice having the shortest hours of sun, and the spring and fall equinox ("equal night") having equal day and night times corresponding to zero solar declination. During the equinoxes, the sun will rise directly from the east and set directly in the west. At 40 degrees latitude, there are 6 more hours of daylight in the summer as compared to the winter.


Local Apparent Noon
Equinox solar noon
Summer Solstice
Spring,Fall Equinox
Winter Solstice
+ 23.44
- 23.44
East
South
90^0 - Latitude
North
Local Horizon
West

Solar declination as seen by an observer on the ground varying seasonally

Sign Convention

We should digress momentarily to establish the proper signs for numbers, which make the mathematics consistent and unambiguous.

For Declination:	North is positive (+)	South is negative (-)
For Latitude:	North is positive (+)	South is negative (-)
For Longitude:	East is positive (+)	West is negative (-)

For GHA, it is a positive number between 0 and 360 degrees westward

For LHA, it is positive westwards (post meridian passage) $0 < LHA < 180$, and negative eastwards (pre meridian passage) $-180 < LHA < 0$, or $180 < LHA < 360$

For observed altitude, **Ho**, above the horizon is positive (+)

Also if you are not aware, in an equation $A \cdot B$ means A multiplied by B.

Concepts in Latitude

The simplest example to illustrate how latitude is determined is to consider Polaris, the North Star. Now Polaris is not exactly on the north celestial pole, but close enough for our intuition to work here. If we were sitting on Earth's north pole (avoiding polar bears), we would observe that Polaris would be directly overhead, at the zenith point. Relative to the horizon, it would have an altitude of approximately 90 degrees of angle. Our latitude at the North Pole coincidentally is also 90 degrees. If now instead we were sweating somewhere on the equator on a hill in Ecuador at night, we would see Polaris just on the northern horizon. The altitude relative to the horizon would be approximately zero. Coincidentally, the latitude on the equator is zero. To see why this is not really a coincidence, see the illustration to understand the geometry involved. We could say generally that the observed altitude of Polaris is equal to the latitude of the observer (actually small corrections need to be made since Polaris is slightly off center from the pole). Also note that the declination of Polaris in the celestial sphere is about 90 degrees. We can generalize the matter by taking into account the declination of any particular star, as shown in the illustration. Such a star can be the Sun, and if we know the declination for every hour of the year, we can wait until the Sun is at its meridian passage (local apparent noon LAN) to make an altitude measurement Ho. The Latitude is then 90 + DEC - Ho.

For a star that passes right overhead at the zenith, the star's declination is equal to your latitude. That makes for good emergency navigation.



CONCEPTS IN LATITUDE DETERMINATION

Concepts in Longitude

If we think of a car traveling at 60 mph, in 2 hours it will have traveled 120 miles (60 · 2). To determine distance, all we needed was knowledge of the speed, and a clock. For a rotating object, it is the same. If we know the rotational speed, say ¼ revolutions per minute (RPM), and we have a stopwatch, in 2 minutes it should have rotated ½ revolution(0.25 · 2), or 180 degrees(0.25 · 2 · 360 degrees per rev). Now let's think of the Earth. It rotates once in 24 hours with respect to the position of the mean Sun in the sky. That's 360 degrees in 24 hours, or 15 degrees per hour (360/24). If a person on the Earth observes the Sun passing across the local N-S meridian line (in other words, local noon), and observes the time to be 15:00 UT, that's 3 hours past noon in Greenwich. You will recall, UT is based on the time in Greenwich, zero longitude. The difference in angle between the observer and Greenwich, is 15 deg/hour x 3 hours = 45 degrees of longitude in the westward direction. This is why the chronometer needs to be synchronized with Greenwich time, so the observer can determine the difference in angle (longitude) with respect to the prime meridian (zero longitude). This idea was noted as early as 1530 by the Flemish professor Gemma Frisius. Pendulum clocks were not suitable for the motion of ships, and it was John Harrison in 1735 that made the first semi portable clock, with its 'grasshopper' escapement and twin balance-arm oscillator. What a contraption! But, it was the start of marine chronometers that could take the rocking and rolling of a ship and not lose a beat.

It is no coincidence that along a *great arc* on the Earth (such as the equator), one minute of arc (1/60 degree) corresponds to one *nautical mile* (n mi) of distance. One nautical mile is equal to 1.15 statute miles. The Earth's circumference is then equal to 21600 n mi (1nm per arcmin x 60 arcmin per deg x 360 deg per full circle). The maximum surface speed of rotation for Sun observations will occur along the equator at 15 n mi per minute of time (21600 n mi per day/(24hr per day x 60 min per hr)). This is also equivalent to ¼ n mi per second of time. It is easy to see now how a time error (either the clock is off or the time is read wrong) can put the longitude determination way off. In mid latitudes, a time error of 60 seconds will put the longitude off by 10 n mi.

You get the general picture, but actually the true position of the Sun does not correspond with clock time as we have already described earlier. It is a little off due to Earth's elliptical orbit.

The upshot of all this explanation is that to know longitude, one then needs to have a clock set to the time in Greenwich England.

Traditional Noon Sighting

The *noon sighting* is an old way of determining latitude and (with misgivings) longitude, as the azimuth is unambiguously known as either due south or due north. The method has certain steps to maintain accuracy. Here, the trigonometry disappears and reduces down to mere arithmetic. The technique is to predict approximate *local apparent noon* (LAN) for your estimated longitude from *dead reckoning* navigation. Take sightings with your sextant several minutes before LAN, and with a sighting every minute, capture the highest point in the sky that the Sun traveled plus some sightings after meridian passage. You make corrections to obtain the true altitudes, and plot this information as true altitude versus time. From the plot you can smooth the curve and determine the highest point (Ho_{noon}) and estimate the time of LAN to within several minutes or better of Universal Time (~10-20 n miles of longitude error). Using the nautical almanac, obtain the GHA and declination of the Sun (DEC) at the time of LAN. Remember the sign convention and apply it. We will now make a distinction regarding the direction of meridian passage, whether the sun peaked in the south or in the north, by introducing a new variable $Sign_{noon}$. In keeping with the consistent sign convention, when the meridian passage is northwards such as commonly occurs in S. latitudes, the value of $Sign_{noon}$ is +1. When the meridian passage is southwards such as commonly occurs in N. latitudes, the value of $Sign_{noon}$ is -1. Thus:

$$\text{Latitude} = Sign_{noon} \cdot Ho_{noon} + DEC + 90$$

If this calculated latitude is greater than 90 degrees, then subtract 180 from it.

If $Sign_{noon} \cdot Ho_{noon} + DEC$ is equal to zero, then you are exactly on either the north or south pole. If you don't know which pole you're on then you should have stayed home.

This equation works whether you are in the northern or southern hemispheres, in or out of the tropics. *Just follow the sign convention, and it will all come out fine.*

For longitude, the local hour angle LHA is zero, and so, determine the sun's GHA at the instant of LAN using the almanac:

Longitude = - GHA if GHA is less than 180
Longitude = 360 – GHA if GHA is greater than 180

Remember, if your chronometer is inaccurate then the longitude will be off considerably since you are in essence comparing the local time with time in Greenwich. It will be off considerably anyway due to the plotting estimates.

3-Measurement Noon Sighting: Double Altitudes

There is an antiquated technique to determine latitude and longitude with a noon sighting using 3 measurements. 15 minutes before LAN, you can shoot the sun for a reference point of altitude and time. Record this as your measurement #1. Then keep track of the sun with the sextant and when it reaches the maximum altitude, record this as your measurement #2. Finally, set the sextant to the altitude setting that you had in measurement #1, and observe the sun. The moment the altitude matches the pre-positioned setting, record the time (UTC). Noon will be at the average between time measurements #1 and #3. The latitude will be derived from measurement #2.

From the almanac, determine the sun's declination DEC. For southwards meridian passage, $\text{Sign}_{\text{noon}} = +1$, and a northerly passage = -1.

Latitude = $\text{Sign}_{\text{noon}} \cdot \text{Ho}_{\#2} + \text{DEC} + 90$ (remember the sign for DEC)
If this calculated latitude is greater than 90 degrees, then subtract 180 from it.

Time of LAN = (Time #1 + Time #2) *0.5

For longitude, the local hour angle LHA is zero, and so determine the sun's GHA at the instant of LAN using the almanac:

Longitude = - GHA if GHA is less than 180
Longitude = 360 – GHA if GHA is greater than 180

If for example T#1 = 19:27:31, and T#3 = 19:48:43, then the difference between them is 21 min and 12 sec. Half that is 0:10:36 difference, so add that to T#1 and you get 19:37:67 which is 19:38:07 as LAN (67 seconds = 1 min+7 sec).



Plane Trigonometry

The simplest notion of 'trig' is the relationship of the sides and angles in a triangle. All you have to know are these three basic relationships:



sine (α) = Lo / R shorthand is **sin(α)**
cosine (α) = La / R shorthand is **cos(α)**
tangent (α) = Lo / La shorthand is **tan(α)**

The values of these trigonometric functions can be expressed as an infinite series, which your calculator will approximate by truncating the series after evaluating only a few terms. ArcSin or arcCos is the inverse function. On your calculator it might be ASIN, or InvSIN.

Useful identities:
$\sin(\alpha) = \cos(90^\circ - \alpha)$
$\cos(\alpha) = \sin(90^\circ - \alpha)$

Spherical Trigonometry



Three Great Circles on a sphere will intersect to form three inner corner angles a, b, c, and three surface angles A, B, C. Every intersecting pair of Great Circles is the same as having two intersecting planes. The angles between the intersecting planes are the same as the surface angles on the surface of the sphere. Relationships between the corner angles and surface angles have been worked out over the centuries, with the law of sines and the law of cosines (spherical trigonometry) being the most relevant to navigation.

Law of Sines: $\sin(a)/\sin(A) = \sin(b)/\sin(B) = \sin(c)/\sin(C)$

Law of Cosines: $\cos(a) = \cos(b) \cdot \cos(c) + \sin(b) \cdot \sin(c) \cdot \cos(A)$

Law of Cosines in terms of co-angles by using the useful identies:
$\sin(90-a) = \sin(90-b) \cdot \sin(90-c) + \cos(90-b) \cdot \cos(90-c) \cdot \cos(A)$

The Navigational Triangle

The navigational triangle applies spherical trigonometry, in that the inner corner angles a, b, c are related to altitude, latitude, and declination angles, and the surface angles are related to azimuth and LHA angles.


GEOGRAPHICAL POSITION OF OBJECT
Co-Declination
Co-Latitude
Co-Altitude
OBSERVER LOCATION


N. POLE
PRIME MERIDIAN
GEOGRAPHICAL POSITION OF OBJECT
OBSERVER LOCATION
Z
Azimuth, Zn
90-H
DIRECTION of HEAVENLY OBJECT
Object Center
Earth Center
LATITUDE
DEC
DECLINATION ANGLE
LHA
WEST LONGITUDE
GHA

The inner corner angles corresponding to the arc sides are modifications of the altitude, latitude and declinations. As can be seen in the drawing the "co-angles" are 90° – the inner corner angle:

Co-altitude = 90° – H
Co-declination = 90° – DEC
Co-latitude = 90° - LAT

Most authorities will examine 4 cases concerning North or South declination and latitude. But if a consistent sign convention is used, we need only concern ourselves with the one picture. If you substitute a co-altitude (like 90-H) into the co-altitude formula (90-a), a = 90-H, so 90-(90-H) = H . The modified law of cosines formula for co-altitudes becomes:

$\sin(H) = \sin(Lat) \cdot \sin(DEC) + \cos(Lat) \cdot \cos(DEC) \cdot \cos(LHA)$.

Chapter Four

Calculations for Line of Position

The *calculated altitude* is a way of predicting the altitude of a heavenly object by first assuming a latitude and longitude for a hypothetical observer and working out the problem backwards. The math becomes direct and unambiguous when done in this manner. The obvious choice of assumed latitude and longitude is the estimated position by dead reckoning. *Dead reckoning* is the method of advancing from a last known position by knowing the direction you headed in, how fast you were going, and how long you went. You will eventually compare this calculated altitude to a measured altitude, and so the calculated altitude must correspond to the same time as the measured altitude. This is important to extract the proper values of GHA and declination from the nautical almanac. You must be talking about the same instant in time for a correct comparison. Remembering to use the sign convention, the law of cosines gives us this relationship for the calculated altitude Hc:

$$\mathbf{Hc = arcSin[\ Sin(Lat_A) \cdot Sin(DEC)\ +\ Cos(Lat_A) \cdot Cos(DEC) \cdot Cos(LHA)\ ]}$$

Where $\mathbf{Lat_A}$ is the assumed latitude, $\mathbf{Lon_A}$ is the assumed longitude and the calculated local hour angle $\mathbf{LHA = GHA + Lon_A}$
If LHA is greater than 360, then subtract 360 from the calculated LHA.
DEC is of course the declination of the heavenly object.

The uncorrected azimuth angle **Zo** of a heavenly object can also be calculated as thus:

$$\mathbf{Zo = arcCos[\{Sin(DEC) - Sin(Lat_A) \cdot Sin(Hc)\}/\{Cos(Lat_A) \cdot Cos(Hc)\}]}$$

Corrected azimuth angle **Z** (not used in any of the equations here)
If N. latitudes, then **Z = Zo** If S. latitudes, then **Z = 180 – Zo**

True Azimuth Angle from True North **Zn**
If LHA is pre-meridian passage (-, or 180<LHA < 360), **Zn = Zo**
If LHA is post-meridian passage (0<LHA < 180), **Zn = 360 – Zo**
Post meridian check can also be established if: **Sin(LHA) > 0**
Remember, arcSin or arcCos on your calculator could also be designated as ASIN, ACOS, or INVSIN, INVCOS.

By using the sign convention, we only have two cases to examine to obtain the true azimuth angle. All texts on celestial that I know of will list 4 cases due to the inconsistently applied signs on declination and latitude. Classical same name (N-N, S-S) or opposite name (N-S, S-N) rules do not apply here.

Line of Position by the Marcq Saint-Hilaire Intercept Method

This clever technique determines the true line of position from an *assumed line of position* and is the basis of modern sight reduction. Let's say you measured the altitude of the Sun at a given moment in time. You look up the GHA and declination of the Sun in the nautical almanac corresponding to the time of your altitude measurement. From an assumed position of latitude and longitude, you calculate the altitude and azimuth of the Sun according to the preceding section and arrive at **Hc** and **Zn**. On your map, you draw a line thru the pin-point assumed latitude and longitude, angled perpendicular to the azimuth angle. This is your assumed line of position. The true line of position will be offset from this line either towards the sun or away from it after comparing it to the actual *observed altitude* **Ho** (the raw sextant measurement is **Hs**, and needs all the appropriate corrections applied to make it an 'observed altitude').

The offset distance $\mathbf{D_{OFFSET}}$ to determine the true line of position is equal to:

$\mathbf{D_{OFFSET} = 60 \cdot (Ho - Hc)}$, altitudes **Ho** and **Hc** in decimal degrees, or
$\mathbf{D_{OFFSET} = (Ho - Hc)}$, altitudes in minutes of arc. $\mathbf{D_{OFFSET}}$ is in nautical miles for both cases.

If $\mathbf{D_{OFFSET}}$ is positive, then parallel offset your assumed line of position in the azimuth direction towards the heavenly object. If negative, then draw it away from the heavenly object. If the offset is greater than 25 nautical miles, you may want to assume a different longitude and latitude to minimize errors.

By calculating an altitude, you have created one circle of constant altitude about the geographical position, knowing that the actual circle of constant altitude is concentric to the calculated one. The difference in observed altitude and calculated altitude informs you how much smaller or larger the actual circle is. Offsetting along the radial azimuth line, the true circle will cross the azimuth line at the *intercept point*. You could also simply remember that a higher observed altitude means you are closer to the geographical position GP. If not, you are further away.

LINE OF POSITION METHODS
Intercept from Calculated Altitude


Near or far object, in the short distances of Doffset the light is more or less parallel
Assumed Position
Hc
Ho
Doffset (+)
(Ho-Hc)
Intercept Point
LOP perpendicular to the page at this point


Assumed Longitude
INTERCEPT DETAILS
Assumed LOP
Assumed Latitude
Bearing of Heavenly Object
DR Point
Intercept Point
INTERCEPT LOP
Doffset (+)
Observed Circle of Constant Altitude
Calculated Circle of Constant Altitude


Assumed Latitude
Circle of Constant Altitude Calculated
Assumed Longitude
Azimuth direction (Bearing) of Heavenly Object
Circle of Constant Altitude Observed
Geographical center of Heavenly Object
GP

Line of Position by the Sumner Line Method

If we measure the altitude of a heavenly object and make all the proper corrections, this reduces to the observed altitude **Ho**. As we should know by now, there is a circle surrounding the geographical position of the heavenly object where all observed altitudes have the same value Ho. We could practically draw the entire circle on the map, but why bother? What if instead, we draw a small arc in the vicinity of our dead reckoning position. In fact, why an arc at all, since at the map scale that interest us, a straight line will do just fine. All we need do is to rearrange the equation of calculated altitude, to make it the observed altitude instead and to solve the equation for LHA, which will give us longitude. The procedure is to input an assumed latitude, the GHA and declination for the time of observation, and out pops a longitude. Mark longitude and latitude on the map. Now input a slightly different latitude, and out pops a slightly different longitude. Mark the map, connect the dots and you have a *Sumner Line*. These are two points on the circle in the vicinity of your dead reckoning position. Or were they? Was the answer for longitude unreasonably off? Notice that for every latitude line that crosses the circle, there are 2 solutions for longitude, an east and west solution. In the arcCos function, the answer can be the angle A or the angle -A. Check both just to make sure.

East side of the circle when the object is westwards (post meridian):

$$\mathbf{Lon_C = arcCos[\{ Sin(Ho) - Sin(DEC) \cdot Sin(Lat_A)\}/\{Cos(Lat_A) \cdot Cos(DEC)\}] - GHA}$$

West side of the circle when the object is eastwards (pre meridian):

$$\mathbf{Lon_C = -arcCos[\{ Sin(Ho) - Sin(DEC) \cdot Sin(Lat_A)\}/\{Cos(Lat_A) \cdot Cos(DEC)\}] - GHA}$$

Where $\mathbf{Lat_A}$ is the assumed latitude, $\mathbf{Lon_C}$ is the calculated longitude **DEC** is of course the declination of the heavenly object.

The two values for assumed latitude could be the dead reckoning latitude $\mathbf{Lat_{DR}}$ + 0.1 and – 0.1 degree.

The advantage to this method is that the LOP comes out directly without offsets. There is no azimuth calculation, just two calculations with the same equation having slightly differing latitude arguments. Also, the fact that only the assumed latitude is required means no estimated position of the longitude is needed at all. This method turns into an E-W LOP when near the meridian passage, just like a noon shot.

LINE OF POSITION METHODS

SUMNER LINE METHOD


SUMNER LINE DETAILS
Longitude #1
Latitude Argument #1
Observed Circle of Constant Altitude
Assumed Latitude
SUMNER LOP
Latitude Argument#2
Longitude #2


Calculated Longitude #1
Assumed Latitude
Latitude trial #1
Calculated Longitude #2
Latitude trial #2
Circle of Constant Altitude Observed
Geographical center of Heavenly Object
GP

History of the Sumner Line

The Sumner line of position takes its name from Capt. Thomas H. Sumner, an American ship-master, who discovered the technique serendipitously and published it. I recount here his discovery, paraphrased from his book:

Capt. Sumner sailed from Charleston S.C. on November 25th, 1837, and was bound for Greenock, Ireland. After passing 21 deg west longitude, he had no observations due to thick weather until he came close to land. He was within 40 miles of the Tuskar lighthouse off the coast of Ireland by dead reckoning with the weather getting worse at around midnight December 17th. At that point the wind backed from the south to the south east making the coast a lee shore. He kept close to the wind tacking back and forth until daylight, and then kept on a course of ENE. At about 10 am local time he was able to make a sun shot observation, but going so long since the last observation, he was unsure of his dead reckoning latitude. A longitude (Lon1) with his uncertain latitude (Lat1) was calculated:

$$\mathrm{Lon}_1 = -\mathrm{arcCos}[\{ \mathrm{Sin(Ho)} - \mathrm{Sin(DEC)} \cdot \mathrm{Sin}(\mathrm{Lat}_1)\}/\{\mathrm{Cos}(\mathrm{Lat}_1) \cdot \mathrm{Cos(DEC)}\}] - \mathrm{GHA}$$

Declination and GHA of the sun was from the almanac and the time mark from the sun shot. The longitude was 15’ east of his dead reckoning position. He then assumed a second latitude (Lat2) 10’ north of his dead reckoning towards the coast:

$$\mathrm{Lon}_2 = -\mathrm{arcCos}[\{ \mathrm{Sin(Ho)} - \mathrm{Sin(DEC)} \cdot \mathrm{Sin}(\mathrm{Lat}_2)\}/\{\mathrm{Cos}(\mathrm{Lat}_2) \cdot \mathrm{Cos(DEC)}\}] - \mathrm{GHA}$$

Marking the chart with the location Lat1, Lon1, and then with Lat2, Lon2, he noticed the 2nd position was 27 miles ENE of the 1st position

He did this a 3rd time with another 10’ more northerly latitude assumption and calculated a 3rd longitude:

$$\mathrm{Lon}_3 = -\mathrm{arcCos}[\{ \mathrm{Sin(Ho)} - \mathrm{Sin(DEC)} \cdot \mathrm{Sin}(\mathrm{Lat}_3)\}/\{\mathrm{Cos}(\mathrm{Lat}_3) \cdot \mathrm{Cos(DEC)}\}] - \mathrm{GHA}$$

After plotting this third point on the chart (Lat3, Lon3), he noticed that all three of the points were on a line. This line just happened to cross Smalls Light as well. Capt. Sumner rightfully concluded that all three points saw the same observed altitude of the Sun, and so where he might not know exactly where he was, he knew he was somewhere on that line. Coincidentally his course was on that line as well, and he continued to sail ENE; within an hour he saw Smalls Light and made his landfall. Thus the Sumner Line method was discovered accidently by practice.

Chapter 5 *Measuring Altitude with the Sextant*

The sextant is a wonderfully clever precision optical instrument for which we can thank Sir Issac Newton for the design. It reflects the image of the Sun (or anything, really) twice with two flat mirrors in order to combine it with a straight-thru view, allowing you to see the horizon and heavenly object simultaneously in the same pupil image. This allows for a ‘shake-free’ view, as the horizon and Sun move together in the combined image. The straight-thru view is accomplished with the second mirror *(horizon mirror)*, which is really a half mirror, silvered on the right and clear on the left. You see the horizon unchanged on the left, and the twice-reflected sun on the right if you use a *‘traditional’* mirror as opposed to a *‘whole horizon’* mirror. With a whole horizon mirror, both horizon and Sun will be in the entire view. It does this by partial silvering of the entire horizon mirror like some sunglasses are, reflecting some light and transmitting the rest. This makes the easy shots easier, but the more difficult shots with poor illumination or star shots more difficult. Even with the traditional mirror, curiously, you will see a whole image of the sun in the pupil that you can move to the right or left by rocking the sextant side to side. The glass surface itself is reflective. When it is at its lowest point, you are correctly holding the sextant and can take a reading. The horizon however, will only be on the left side of the image. In order to determine the altitude of the Sun, you change the angle of the first mirror *(index mirror)* with the *index arm* until the Sun is close to the horizon in the pupil image. Now turn the precision index drum (knob) until the lower *limb* of the Sun just kisses the horizon. Rock it back and forth to make sure you have the lowest reading. In order not to burn your eye out (that would be stupid…), there are *filters* (shades) that can be rotated over the image path of the index mirror. Likewise, there are other filters that cover the horizon mirror to remove the glare and increase the contrast between horizon and sky.

SUN SHOT, VIEW THRU THE SEXTANT EYE PIECE







The Nautical Sextant

Index mirror
Sky filters
Horizon mirror
Horizon
Horizon filters
arc
low magnification telescope
combined view
Handle
130
120
110
100
90
80
70
60
40
20
10
0
degree scale
Index arm
0
5
20
25
30
Vernier scale
Index drum
micrometer adjustment of arcminute scale
Squeeze to disengage micrometer thread

Mirror Alignments

Even an expensive precision instrument will give you large errors (although consistent systematic error) unless it is adjusted and calibrated. Before any round of measurements are taken, you should get into the habit of calibrating and if necessary adjusting the mirrors to minimize the errors.

The first check is to see if the index mirror is perpendicular to the sextant's arc. Known as *Perpendicularity Alignment*, it is checked in a round-about manner by finding the image of the arc in the index mirror when viewed externally at a low angle. Set the arc to about 45 degrees. The reflected arc in the index mirror should be in line with the actual arc. This can be tricky, as it only works if the mirrored surface is exactly along the pivot axis of the index arm. Since most mirrors are *secondary surface* mirrors (the silvering is on the back of the glass), you need to compare the position of the rear of the glass to the pivot axis first to see if this technique will work. *First surface* mirrors (the silvering is on the front of the glass) seem to be an upgrade, but the sextant's manufacturer may not have necessarily redesigned the mirror-holding mount. This positions the index mirror reflecting surface 2 to 3 mm or so in front of the pivot axis. In that case, the reflected image of the arc should be slightly below the viewed actual arc. There are precision-machined cylinders about an inch high that you can place on the arc and view their reflections. The reflections should be parallel to the actual cylinders. If not, then turn the set screw behind the index mirror to bring it into perpendicular alignment.

The next alignment is *Side Error Alignment* of the horizon mirror. This can be done two ways after setting the arc to the zero angle point such that you see the same object on the left and right in the pupil image. First, at sea in the daytime, point the sextant at the horizon. You will see the horizon on the left and the reflected horizon on the right. Adjust the index drum until they are in perfect alignment while holding the sextant upright. Now roll (tilt) the sextant side to side. Is the horizon and reflected image still line-to-line? If not, then side error exists. This is corrected with adjustments to the set screw that is perpendicularly away from the plane of the arc on the horizon mirror. Second method is to wait until nighttime, where a point source that is nearly infinitely far away presents itself (yes, I mean a star). Same procedure as before except that you need not roll the sextant. What you will see is two points of light. The horizontal separation is the *side error*, and the vertical separation is the *index error*. Adjust the drum knob to negate the index error effect until the star and its reflection are vertically line-to-line but still separated horizontally. Make adjustments to the side-error set screw until the points of light converge to a single image point.



SEXTANT SET AT ZERO, SHOWING INDEX ERROR VIEWING THE HORIZON UPRIGHT



SEXTANT WITH INDEX ERROR REMOVED VIEWING HORIZON TILTED AT ANGLE TO REVEAL SIDE ERROR

You could stop here at this point, reading the drum to determine the index error IE (Note: index correction IC = - IE). Or you could continue to zero out the index error as well with a last series of adjustments. In which case, for the *Index Error Alignment*, set the arc to zero (index arm and drum to the zero angle position). You will notice that the star image now has two points separated vertically. Adjusting the remaining set screw on the horizon mirror (which is near the top of the mirror), you can eliminate the vertical separation. Unfortunately this last set screw does not only change the vertical separation, but it slightly affects the horizontal separation as well. Now you need to play around with both set screws until you zero-in the two images simultaneously. With a little practice these procedures will be easy and routine. A word of caution: the little wrench used to adjust the set screws maybe very difficult to replace if you should drop it overboard. Making a little hand lanyard for the wrench will preserve it. Maybe…

Note: I have also used high altitude jet aircraft, their contrails, and even cloud edges to adjust the mirrors (low accuracy…). If you have dark enough horizon shades, you can even use the sun's disk to adjust the mirrors.



SEXTANT SET AT ZERO VIEWING A STAR

Sighting Techniques

Bringing the object down
Finding the horizon is much easier than finding the correct heavenly object in the finder scope. So, the best technique is to first set the index arm to zero degrees and sight the object by pointing straight at it. Then keeping it in view, 'lower' it down to the horizon by increasing the angle on the index arm until the horizon is in sight. Careful with the sun, as you don't want to see it unfiltered thru the horizon glass; keep the sun on the right hand side of the mirror using the darkest shade over the index mirror.

Rocking for the lowest position
Rocking the sextant from side to side will help you determine when the sextant is being pointed in the right direction and held proper, as the object will find its lowest point. This will give the true sextant altitude Hs.

Letting her rise, letting her set
Often it is easier to set the sextant 'ahead' of where the heavenly object is going, and to simply let her rise or set as the case may be to the horizon. At that point you mark the time. That way you can be rocking the sextant to get the true angle without also fiddling with the index drum. This leaves a hand free, sort of, to hold the chronometer such that at the time of mark, you just have to glance to the side a little to see the time.

Upper limb, lower limb
With an object such as the Sun or Moon, you can choose which limb to use, the lower limb or upper limb. Unless the Sun is partially obscured by clouds, the lower limb is generally used. Depending on the phase of the moon, either lower limb or upper limb is used.



Brief History of Marine Navigational Instruments

The earliest instrument was the *astrolabe*, constructed in the Middle East during the 9th century AD. It was a mechanical rotating slide rule with a pointer to determine the altitude of stars against a protractor. Contemporary was a very simple instrument, the *quadrant*. It was a quarter of a circle protractor with a plumb-bob and a pair of peep sights to line up with Polaris. The first real ancestor to the modern sextant was the *cross staff*, described in 1342. A perpendicular sliding cross piece over a straight frame allowed one to line up two objects and determine the angle. Of course one had to look at both objects simultaneously by dithering the eyeball back and forth – a bit of a problem. Also one had to look into the blinding sun. Since a cross staff looked like a crossbow, one was said to be 'shooting the sun', an expression still used today. The *Davis backstaff* in 1594 was an ingenious device where sun shots were taken with your back to the sun, using the sun's shadow over a vane to cast a sharp edge (so the navigator wouldn't go blind!). The navigator would line up the horizon opposite the sun azimuth with a pair of peep holes, and rotated a shadow vane on an arc until the shadow edge lined up on the forward peep hole. This limited one to only sun shots to determine latitude. In the 1600's a French soldier-mathematician by the name of Vernier invented the *vernier scale*, whereby one could easily interpolate between degree scales to a 1/10 or 1/20 between the engraved lines on the protractor scale. The search for determining longitude created bizarre proposals, but it was recognized that determining the time was the answer, and so one needed an accurate clock. A clock could be mechanical, or astronomical. The Moon is about ½ degree of arc across its face, and moves across the celestial sphere at the rate of about one lunar diameter every hour (~0.5 arcminute per minute of time). Therefore its arc distance to another star could be used as a sort of astronomical clock. Tables to do this were first published in 1764. The calculations and corrections are indeed frightening, and this method of determining time to within several minutes of Greenwich Mean Time is called doing *Lunars*, and those who practice it are *Lunarians*. Undoubtedly if you used this method too often you would have been branded a *Lunatic*. Fortunately in 1735 John Harrison invented the first *marine chronometer*, having some wood elements and weighing 125 lbs. He worked on it for 40 years (until he produced the alarm-clock size H4)! The *Hadley Octant* in 1731 was the first to use the double reflecting principle as described by Isaac Newton a century before. It could measure across 90 degrees of arc, even though it was only physically 45 degrees arc, an 1/8 of a circle. The sextant with it's ability to record angles of 120 degrees came about for use in doing lunars, and so was a contemporary of the octant. By 1780, refinements such as tangential screws, vernier scales, and shades glasses, fixed the design of sextants and octants for the next 150 years.

VARIOUS ANTIQUE INSTRUMENTS


Hadley Octant
Fine Brass Octant
C
A
B
Back Staff
Cross Staff
Quadrant
Astrolabes
Kamal

Octants, Back Staff, Cross Staff, Quadrant, Astrolabes, Kamal

Chapter 6 *Corrections to Measurements*

There are numerous corrections to be made with the as-measured altitude **Hs** that you read off of the sextant's arc degree scale and arc minute drum and vernier. Your zero point on the scale could be off, the same as the bathroom scale when you notice that it says you weigh 3 lbs even before you get on it. This is known as index error, and the correction is **IC**. For our example of the bathroom scale, **IC** = -3. The other major corrections are **parallax, semi-diameter, refraction**, and **dip**, listed from the largest effect to the smallest. Lunar parallax can be at most a degree, semi-diameter ¼ degree, refraction and dip are on the order of 1/20th degree.


THIS IS WHAT YOU WANT !
YOU
Ho
TRUE HORIZON
EARTH


APPARENT LOCATION
THIS IS WHAT YOU GET !
ATMOSPHERIC REFRACTION
TRUE LOCATION
YOU
SEMI-DIAMETER
H_S
EYE HEIGHT ABOVE HORIZON
TRUE HORIZON
DIP
EARTH
VISUAL HORIZON

The **Hs** in the figure does not account for the index error, **IC**.

The sextant basically has an index correction **IC** and an instrument correction **I**. The instrument error is due to manufacturing inaccuracies and distortions, and should be listed on a calibration sheet from the manufacturer. Generally it's negligible. Index error is due to the angular misalignment of the index mirror, with respect to the zero point on the scale. The correction IC is negative when the zero is "on the scale", and positive when "off the scale". By adjusting the drum knob as described on pages 39 and 40 to negate the optical index error, one can see if the zero is on or off the scale.

Dip Correction

Dip is the angle of the visual horizon, dipping below the true horizon due to your eye height above it. This is also tabulated in the nautical almanac. An approximate equation for dip correction that incorporates a standard horizon refraction is thus:

$\mathbf{Corr}^{\mathbf{DIP}} = -0.0293 \cdot \mathrm{SquareRoot}(h_{eye})$ Decimal Degrees
$\mathbf{Corr}^{\mathbf{DIP}} = -1.758 \cdot \mathrm{SquareRoot}(h_{eye})$ arc minutes
Where $\mathbf{h}_{\mathbf{eye}}$ is the eye height above the water, meters.
Corr ^{DIP} is always negative.

Distance to visible horizon as a function of eye height above the water:

$$d_{horiz} = 2.118 \cdot \sqrt{h_{eye}}$$

Distance to horizon d_{horiz}, n.mi
eye height h_{eye}, meters

Altitude Corrections

Let us first define the apparent altitude, $\mathbf{Ha = Hs + IC + Corr}^{\mathbf{DIP}}$
Ha is the altitude without corrections for refraction, semi-diameter, or parallax. The atmosphere bends (refracts) light in a predictable way. These corrections are tabulated on the 1st page of the nautical almanac based on the apparent altitude Ha. The corrections vary for different seasons, and whether you are using the lower or upper *limb* of the Sun for your observations. Since measurements are made to the edge (limb) and not the center of the Sun, the angle of the Sun's visual radius (semi-diameter) must be accounted for. The table also lists slight deviations from the nominal for listed planets. There are special lunar correction tables at the end of the almanac, which include the effects of lunar semi-diameter, parallax and refraction. The variable name for all of these combined altitude error corrections, lunar, solar or otherwise, is $\mathbf{Corr}^{\mathbf{ALT}}$, sometimes called the 'Main Correction'.
The true observed altitude is a matter of adding up all the corrections:
$\mathbf{Ho = Ha + Corr}^{\mathbf{ALT}}$

Tables of Altitude and Dip Correction, averaged values

For simplified corrections, use these tables instead of the Nautical Almanac.

Altitude correction for sun and stars
Corr^{ALT}

Ha, deg	**Sun LL**	**Sun UL**	**Stars**
10	+11'	-21'	-5'
13	+12'	-20'	-4'
15	+12.5'	-19.5'	-3.5'
17	+13'	-19'	-3'
20	+13.5'	-18.5'	-2.5'
24	+14'	-18'	-2'
31	+14.5'	-17.5'	-1.5'
41	+15'	-17'	-1'
59	+15.5'	-16.5'	-0.5'
85	+16'	-16'	0

Dip Correction

Height	**Corr^{DIP}**
0.7m	-1.5'
1.3m	-2'
2.0m	-2.5'
2.9m	-3'
3.9m	-3.5'
5.1m	-4'
6.4m	-4.5'

Graph of Dip Correction, for when land is used as horizon



Refinements

Corrections for observations can be calculated instead of using tables, and refinements can be employed for non-standard conditions.

Start with the apparent altitude Ha:

$\mathbf{Ha = Hs + IC + Corr^{DIP}}$ (assume instrument correction I ~ 0)

The *horizontal parallax* for the Moon is given in the nautical almanac tables as the variable **HP** in minutes of arc, and you must convert it to decimal degrees. HP for the Sun = 0.0024 degrees, but this is rarely included as being so small a value. For Venus, the HP is hidden in the altitude correction tables, listed as 'Additional Corr^{n}'. Use the largest number at zero altitude to = HP_{Venus}. To determine the *parallax-in-altitude* **PA**, use this equation:

$\mathbf{PA = HP \cdot Cos(Ha) \cdot (1 - (Sin^2(Lat))/298.25)}$ includes earth oblateness

The semi-diameter of the Sun **SD** is given at the bottom of the page of the tables in the nautical almanac in minutes of arc, and you must convert it to decimal degrees. So is the semi-diameter daily average of the Moon, but you can calculate one based on the hourly value of **HP**:

The semi-diameter of the Moon: $\mathbf{SD = 0.2724 \cdot HP \cdot (1 + Sin(Ha)/60.5)}$

The terms in the parenthesis are "augmentation", meaning the observer is a very little closer to the moon with greater altitude angle. This is a small term.

Atmospheric refraction is standardized to surface conditions of 10 deg C and 1010mb pressure. This standard refraction correction **Ro** is thus:

$\mathbf{Ro = -\ 0.0167 / Tan[Ha + 7.31/(Ha+4.4)]}$ degrees

The correction for non-standard atmospheric conditions is referred to as **f**:

$\mathbf{f = 0.28 \cdot Pressure_{mb} / (Temperature_{DEG\ C} + 273)}$

The final refraction correction **R** is thus:

$\mathbf{R = Ro \cdot f}$ This number is always negative.



If the lower limb were observed, then $\mathbf{sign_{limb} = +1}$

If the upper limb were observed, then $\mathbf{sign_{limb} = -1}$

Observed altitude with refinements:

$\mathbf{Ho = Ha + R + PA + SD \cdot sign_{limb}}$

Here we see that the altitude correction $\mathbf{Corr^{ALT}} = \mathbf{R + PA + SD \cdot sign_{limb}}$

Note: Convert arcminutes to decimal degrees for consistent calculations

Artificial horizon

A fun way of practicing sighting the Sun while on land is to use an artificial horizon. This is simply a pan of water or old motor oil that you place down on the ground in view of the Sun. Since the liquid will be perfectly parallel with the true horizon (no dip corrections here), it can be used as a reflecting plane. In essence you point the sextant to the pan of liquid where you see the reflection of the Sun. Move the index arm until you bring the real Sun into the pupil image with the index mirror. With the micrometer drum bring both images together (no semi-diameter corrections either) and take your reading. This gives a reading nearly twice the real altitude. Undoubtedly you will need to position extra filters over the horizon mirror to darken the Sun's image, as normally you would be looking at a horizon. Correct the reading by taking the apparent altitude Ha and divide by two, then add the refraction correction:

Ha = (Hs + IC)/2 no dip correction
Ho = Ha + R no semi-diameter correction

The wind is very bothersome, as it will ripple the water's surface and therefore the reflected image. Protective wind guards around the pan work somewhat, but generally you may have to wait minutes for a perfect calm. What works best is **mineral oil in a protected pan set up on a tripod** so that you can get right up to it. The ripples dampen out almost immediately.

To be very accurate, you can let the sun touch limb-to-limb. If pre meridian (morning) then let the bottom image rise onto the reflected image, measure the time, and SUBTRACT a semidiameter (UL): **Ho = Ha + R - SD**
If post meridian (afternoon), let the top image set onto the reflected image, measure the time, and ADD a semidiameter (LL): **Ho = Ha + R + SD**





Chapter 7 *Reading the Nautical Almanac*

The nautical almanac has detailed explanations in the back regarding how to read the tabular data and how to use the interpolation tables (increments and corrections). The data is tabulated for each hour on the dot for every day of the year, and you must interpolate for the minutes and seconds between hours. Every left hand page in the almanac is similar to all other left hand pages, and the same for all right hand pages. Three days of data are presented for every left and right hand page pairs. The left page contains tabular data of GHA and declination for Aries (declination = 0), Venus, Mars, Jupiter, Saturn and 57 selected stars. The right page has similar data for the Sun and Moon. It also provides the **Local Mean Time** (LMT) for the events of sunrise, sunset, moonrise, and moonset at the prime meridian. For your particular locality, you can express the event time in UT with the following equation:

$\mathbf{EventTime_{LOCAL} = LMT - Longitude/15}$. Hours UT at your longitude. Remember the sign convention, West -, East +.

Interpolation tables, *v* and *d* corrections

Probably the most confusing part of the tables is *interpolation* for times between hourly-tabulated data, and how to properly apply the mysterious ***v*** and ***d*** corrections. The interpolation tables ('increments and corrections') are based on nominal rates of change of GHA for the motions of the Sun and planets, Moon, and Aries. This way, only one set of interpolation tables is required, with variances to the rates compensated with the *v* and *d* values. These are hourly variances, and their applicable fraction (the correction $\mathbf{Corr}^{V}$ and $\mathbf{Corr}^{d}$) is given in the interpolation tables for the minute of the hour. The *v* number refers to *v*ariances in the nominal GHA rate. There is no nominal rate for changes in declination, so *d* is the direct hourly rate of change of declination. For GHA, the interpolation tables will tabulate increments ($\mathbf{Corr}^{\mathbf{GHA}}$) down to the second of each minute. The *v* and *d* correction is interpolated only for every minute. Take the hourly data in the tables, GHA, add the interpolated increment for the minutes and seconds, and finally add the interpolated *v* correction. Similarly for declination, take the tabulated hourly value Dec and add the interpolated *d* correction. Our sign convention imposes that a south declination is negative, and a north declination is positive. A word of caution, the value of *d* (with our sign convention) may be positive or negative. If the tabulated hourly data for declination is advancing northwards (less southwards), then the sign is positive. We could have a negative declination (south), but have a positive *d* if declination is becoming less southwards. Along the same line, we could have a positive declination (north) but a negative *d* if the declination is heading south (less northwards). Unfortunately the almanac has no sign for *d* so you must devine the correct sign by looking at the progression of DEC.

The final values at the particular hour, minute, and second are thus:
$\mathbf{GHA = GHA_{hour} + Corr^{GHA} + Corr^{\mathit{V}}}$
$\mathbf{DEC = DEC_{hour} + Corr^{\mathit{d}}}$
Where GHA_{hour} and DEC_{hour} are the table values in the almanac for the hour.

After all the interpolations and corrections are performed, convert the angles to decimal degrees and make sure the sign convention was applied consistently to the declination value.

Note: In the nautical almanac, liberal use is made of the correction factor $\mathbf{Corr^n}$. It seems to appear everywhere and applied to everything. The n is actually a variable name for any of the parameters that require 'correction'. Notably, $\mathbf{Corr^{DIP}}$, $\mathbf{Corr^{ALT}}$, $\mathbf{Corr^{GHA}}$, $\mathbf{Corr^{\mathit{V}}}$, and $\mathbf{Corr^{\mathit{d}}}$.

Since we like to use our calculators, instead of using the 'increments and corrections' table (it's actually very easy) we can interpolate for ourselves in the following manner. Lets say we shot an observation at Universal Time **H** hours, **M** minutes, and **S** seconds (H:M:S). The nautical almanac tables for the particular day gave us a GHA in degrees and arcminutes at the UT hour. We convert it to decimal degrees and call it $\mathbf{GHA_{hour}}$. We do the same for the declination and call it $\mathbf{DEC_{hour}}$. Note the hourly variance *v* and declination rate *d* in arcminutes per hour. We can also define the hour fraction, $\mathbf{\Delta t}$, which are the minutes and seconds in decimal form: $\mathbf{\Delta t = (M/60) + (S/3600)}$. Now, the correct interpolated value for our specific time of observation is thus:
$\mathbf{GHA = GHA_{hour} + \{Rate + (\mathit{v}/60)\} \cdot \Delta t}$ decimal degrees

Where **Rate** = 15.00000 (degrees/hour) for Sun or planets
Rate = 14.31667 (degrees/hour) for Moon
Rate = 15.04107 (degrees/hour) for Aries

In a similar line, declination is interpolated thus:
$\mathbf{DEC = DEC_{hour} + (\mathit{d}/60) \cdot \Delta t}$ (DEC_{hour} and *d* with the proper sign)

Note, *v*/60 and *d*/60 converts arcminutes per hour to degrees per hour. Carry out all calculations to 4 decimal places, and make sure the sign convention was applied correctly (carpenter's rule: measure twice, cut once).
Visit an on-line Nautical Almanac at: http://www.tecepe.com.br/scripts/AlmanacPagesISAPI.isa


Left Page
DEGREES
ARCMINUTES
Brightness Magnitude
DAY
UT HOUR
North Declination
South Declination
LMT of meridian passage
GHA variance per hour
DECLINATION change per hour

2000 JUNE 8, 9, 10 (THURS., FRI., SAT.)

UT d	h	ARIES GHA	VENUS −3.9 GHA	VENUS Dec	MARS +1.6 GHA	MARS Dec	JUPITER −2.0 GHA	JUPITER Dec	SATURN +0.2 GHA	SATURN Dec
		° ′	° ′	° ′	° ′	° ′	° ′	° ′	° ′	° ′
8 THURSDAY	00	256 40.9	181 15.5	N22 43.6	172 58.3	N24 01.4	203 42.5	N18 13.5	204 32.3	N16 50.2
	01	271 43.4	196 14.7	44.0	187 58.9	01.5	218 44.4	13.6	219 34.4	50.3
	02	286 45.8	[illegible]	[illegible]	[illegible]	01.6	233 46.3	13.7	234 36.6	50.3
	03	301 48.3	[illegible]	[illegible]	[illegible]	01.7	248 48.2	. . 13.9	249 [illegible]	[illegible]
	04	316 50.8	[illegible]	[illegible]	[illegible]	01.8	263 50.1	14.0	264 [illegible]	[illegible]
	05	331 53.2	256 11.5	45.6	248 01.5	01.9	278 52.0	14.2	279 [illegible]	[illegible]
	06	346 55.7	271 10.5	N22 46.0	263 02.0	N24 02.0	293 53.8	N18 14.3	294 [illegible]	[illegible]
	07	1 58.2	286 09.7	46.4	278 02.6	02.0	308 55.7	14.4	309 [illegible]	[illegible]
	08	17 00.6	301 08.8	[illegible]	[illegible]	[illegible]	[illegible]	14.6	324 [illegible]	[illegible]
	09	32 03.1	316 08.0	[illegible]	[illegible]	[illegible]	[illegible]	14.7	339 51.7	. . 50.8
	10	47 05.5	331 07.1	[illegible]	[illegible]	[illegible]	[illegible]	14.8	354 53.8	50.9
	11	62 08.0	346 06.3	48.0	338 05.0	02.4	9 03.2	15.0	9 56.0	51.0
	12	77 10.5	1 05.4	N22 48.4	353 05.6	N24 02.5	24 05.1	N18 15.1	24 58.1	N16 51.1
	13	92 12.9	16 04.6	48.8	8 06.3	02.6	39 07.0	15.2	40 00.3	51.1
	14	107 15.4	31 03.8	49.2	23 06.9	02.7	54 08.9	15.4	55 02.4	51.2
	15	122 17.9	46 02.9	. . 49.6	38 07.5	. . 02.7	69 10.8	. . 15.5	70 04.6	. . 51.3
	16	137 20.3	61 02.1	49.9	53 08.1	02.8	84 12.7	15.7	85 06.7	51.4
	17	152 22.8	76 01.2	50.3	68 08.7	02.9	99 14.5	15.8	100 08.9	51.4
	18	167 25.3	91 00.4	N22 50.7	83 09.3	N24 03.0	114 16.4	N18 15.9	115 [illegible]	[illegible]
	19	182 27.7	[illegible]	[illegible]	98 10.0	03.1	129 18.3	16.1	130 [illegible]	[illegible]
	20	197 30.2	[illegible]	[illegible]	113 10.6	03.2	144 20.2	16.2	145 [illegible]	[illegible]
	21	212 32.6	[illegible]	[illegible]	128 11.2	. . 03.3	159 22.1	. . 16.3	160 [illegible]	[illegible]
	22	227 35.1	150 57.0	52.2	143 11.8	03.3	174 24.0	16.5	175 [illegible]	[illegible]
	23	242 37.6	165 56.2	52.6	158 12.4	03.4	189 25.8	16.6	190 [illegible]	[illegible]
9 FRIDAY	00	257 40.0	180 55.3	N22 53.0	173 13.0	N24 03.5	204 27.7	N18 16.7	205 24.0	N16 51.9
	01	272 42.5	195 [illegible]	[illegible]	[illegible]	03.6	219 29.6	16.9	220 26.2	52.0
	02	287 45.0	210 [illegible]	[illegible]	[illegible]	03.7	234 31.5	17.0	235 28.3	52.1
	03	302 47.4	225 [illegible]	[illegible]	[illegible]	03.8	249 33.4	. . 17.2	250 30.5	. . 52.2
	04	317 49.9	240 51.9	54.5	233 15.5	03.8	264 35.3	17.3	265 32.6	52.2
	05	332 52.4	255 51.1	54.9	248 16.1	03.9	279 37.1	17.4	280 34.8	52.3
	06	347 54.8	270 50.2	N22 55.3	263 16.7	N24 04.0	294 39.0	N18 17.6	295 36.9	N16 52.4
	07	2 57.3	285 49.4	55.6	278 17.3	04.1	309 40.9	17.7	310 [illegible]	[illegible]
	08	17 59.8	300 48.5	56.0	293 17.9	04.2	324 42.8	17.8	325 [illegible]	[illegible]
	09	33 02.2	315 47.7	. . 56.4	308 18.6	. . 04.3	339 44.7	. . 18.0	340 [illegible]	[illegible]
	10	48 04.7	330 46.8	56.7	323 19.2	04.3	354 46.6	18.1	355 [illegible]	[illegible]
	11	63 07.1	345 46.0	57.1	338 19.8	04.4	9 48.4	18.2	10 [illegible]	[illegible]
	12	78 09.6	0 45.1	N22 57.5	353 20.4	N24 04.5	24 50.3	N18 18.4	25 [illegible]	[illegible]
	13	93 12.1	15 44.3	57.8	8 21.0	04.6	39 52.2	18.5	40 52.0	52.9
	14	108 14.5	30 43.5	58.2	23 21.6	04.6	54 54.1	18.6	55 54.2	52.9
	15	123 17.0	45 42.6	. . 58.6	38 22.3	. . 04.7	69 56.0	. . 18.8	70 56.3	. . 53.0
	16	138 19.5	60 41.7	58.9	53 22.9	04.8	84 57.9	18.9	85 58.5	53.1
	17	153 21.9	75 40.9	59.3	68 23.5	04.9	99 59.7	19.1	101 00.7	53.2
	18	168 24.4	90 40.0	N22 59.6	83 24.1	N24 05.0	115 01.6	N18 19.2	116 02.8	N16 53.2
	19	183 26.9	105 39.2	23 00.0	98 24.7	05.0	130 03.5	19.3	131 05.0	53.3
	20	198 29.3	120 38.3	00.4	113 25.3	05.1	145 05.4	19.5	146 07.1	53.4
	21	213 31.8	135 37.5	. . 00.7	128 25.9	. . 05.2	160 07.3	. . 19.6	161 09.3	. . 53.4
	22	228 34.3	150 36.6	01.1	143 26.6	05.3	175 09.2	19.7	176 11.4	53.5
	23	243 36.7	165 35.8	01.4	158 27.2	05.3	190 11.1	19.9	191 13.6	53.6
10 SATURDAY	00	258 39.2	180 34.9	N23 01.8	173 27.8	N24 05.4	205 12.9	N18 20.0	206 15.8	N16 53.7
	01	273 41.6	195 34.1	02.1	188 28.4	05.5	220 14.8	20.1	221 17.9	53.7
	02	288 44.1	210 33.2	02.5	203 29.0	05.6	235 16.7	20.3	236 20.1	53.8
	03	303 46.6	225 32.4	. . 02.8	218 29.6	. . 05.6	250 18.6	. . 20.4	251 22.2	. . 53.9
	04	318 49.0	240 31.5	03.2	233 30.3	05.7	265 20.5	20.5	266 24.4	53.9
	05	333 51.5	255 30.7	03.5	248 30.9	05.8	280 22.4	20.7	281 26.6	54.0
	06	348 54.0	270 29.8	N23 03.9	263 31.5	N24 05.9	295 24.2	N18 20.8	[illegible]	[illegible]
	07	3 56.4	285 29.0	04.2	278 32.1	05.9	310 26.1	20.9	[illegible]	[illegible]
	08	18 58.9	300 28.1	04.6	293 32.7	06.0	325 28.0	21.1	[illegible]	[illegible]
	09	34 01.4	315 27.3	. . 04.9	308 33.3	. . 06.1	340 29.9	. . 21.2	[illegible]	[illegible]
	10	[illegible]	[illegible]	[illegible]	[illegible]	06.1	355 31.8	21.3	[illegible]	[illegible]
	11	[illegible]	[illegible]	[illegible]	[illegible]	06.2	10 33.7	21.5	[illegible]	[illegible]
	12	[illegible]	[illegible]	[illegible]	[illegible]	N24 06.3	25 35.6	N18 21.6	26 41.7	N16 54.5
	13	[illegible]	[illegible]	[illegible]	[illegible]	06.4	40 37.4	21.7	41 43.8	54.6
	14	[illegible]	[illegible]	[illegible]	[illegible]	06.4	55 39.3	21.9	56 46.0	54.7
	15	124 16.1	45 22.1	. . 06.9	38 37.0	. . 06.5	70 41.2	22.0	71 48.1	. . 54.7
	16	139 18.6	60 21.3	07.3	53 37.7	[illegible]	[illegible]	[illegible]	[illegible]	54.8
	17	154 21.1	75 20.4	07.6	68 38.3	[illegible]	[illegible]	[illegible]	[illegible]	54.9
	18	169 23.5	90 19.5	N23 07.9	83 38.9	[illegible]	[illegible]	[illegible]	[illegible]	N16 54.9
	19	184 26.0	105 18.7	08.2	98 39.5	[illegible]	[illegible]	[illegible]	[illegible]	55.0
	20	199 28.5	120 17.8	08.6	113 40.1	[illegible]	[illegible]	[illegible]	[illegible]	55.1
	21	214 30.9	135 17.0	. . 08.9	128 40.7	. . 06.9	160 52.5	. . 22.8	162 01.1	. . 55.2
	22	229 33.4	150 16.1	09.2	143 41.4	07.0	175 54.4	23.0	177 03.2	55.2
	23	244 35.9	165 15.3	09.6	158 42.0	07.0	190 56.3	23.1	192 05.4	55.3
Mer. Pass.		h m 6 48.2	*v* −0.8	*d* 0.4	*v* 0.6	*d* 0.1	*v* 1.9	*d* 0.1	*v* 2.2	*d* 0.1

STARS Name	SHA	Dec
	° ′	° ′
Acamar	315 26.4	S40 18.2
Achernar	335 34.7	S57 14.0
Acrux	173 20.5	S63 06.3
[illegible]	255 20.9	S28 58.5
[illegible]	291 01.4	N16 30.5
[illegible]	166 29.3	N55 57.8
[illegible]	153 06.6	N49 19.0
[illegible]	27 56.3	S46 57.4
Alnilam	275 57.0	S 1 12.2
Alphard	218 06.2	S 8 39.7
Alphecca	126 19.3	N26 43.0
Alpheratz	357 54.1	N29 05.3
Altair	62 17.9	N 8 52.1
Ankaa	353 25.9	S42 18.1
Antares	112 38.4	S26 25.9
[illegible]	[illegible] 04.8	N19 11.0
[illegible]	[illegible] 48.8	S69 01.7
[illegible]	[illegible] 22.6	S59 30.9
[illegible]	[illegible] 43.3	N 6 20.9
[illegible]	[illegible] 12.7	N 7 24.3
Canopus	264 01.2	S52 41.9
Capella	280 50.0	N45 59.8
Deneb	49 38.1	N45 16.7
Denebola	182 44.0	N14 34.3
Diphda	349 06.2	S17 59.1
Dubhe	194 04.2	N61 45.3
[illegible]	[illegible] 25.9	N28 36.4
[illegible]	[illegible] 50.3	N51 29.4
[illegible]	[illegible] 57.0	N 9 52.5
[illegible]	[illegible]	S29 37.1
[illegible]	[illegible] 12.1	S57 07.1
Gienah	176 02.7	S17 32.7
Hadar	149 02.0	S60 22.6
Hamal	328 12.5	N23 27.6
Kaus Aust.	83 56.9	S34 23.0
Kochab	137 18.6	N74 09.5
Markab	13 48.5	N15 12.3
Menkar	314 26.0	N 4 05.3
Menkent	148 19.3	S36 22.4
Miaplacidus	221 42.3	S69 43.4
Mirfak	308 55.4	N49 51.5
Nunki	76 10.6	S26 17.7
Peacock	53 34.8	S56 43.8
Pollux	243 40.5	N28 01.6
Procyon	245 10.7	N 5 13.4
[illegible]	[illegible]	[illegible] 33.6
[illegible]	[illegible]	[illegible] 58.0
[illegible]	[illegible]	[illegible] 12.2
[illegible]	[illegible]	[illegible] 50.3
[illegible]	[illegible]	[illegible] 43.5
Schedar	349 52.4	N56 32.0
Shaula	96 35.3	S37 06.2
Sirius	258 43.0	S16 43.1
Spica	158 41.8	S11 09.8
Suhail	223 00.2	S43 26.3
Vega	80 45.4	N38 47.0
Zuben'ubi	137 16.4	S16 02.6

	SHA	Mer. Pass.
	° ′	h m
Venus	283 15.3	11 57
Mars	275 33.0	12 27
Jupiter	306 47.7	10 21
Saturn	307 44.0	10 17



Right Page

Lunar Horizontal parallax

Lunar variance

Lunar declination change, negative (less northerly)

Solar events good for a 3 day period

day

hour

minute

Events of sunset and moonset at the particular latitude

LMT of noon on the 8th

Solar declination hourly change

Solar semi diameter

Lunar semi-diameter for 3 days

2000 JUNE 8, 9, 10 (THURS., FRI., SAT.)

	UT	SUN GHA	SUN Dec	MOON GHA	MOON v	MOON Dec	MOON d	MOON HP
	d h	° ′	° ′	° ′	′	° ′	′	′
	8 00	180 15.0	N22 51.1	100 37.4	9.4	N13 23.9	10.4	58.8
	01	195 14.9	51.3	115 05.8	9.4	13 13.5	10.4	58.7
	02	210 14.8	51.5	129 34.2	9.6	13 03.1	10.4	58.7
	03	225 14.7	. . 51.8	144 02.8	9.6	12 52.7	10.6	58.7
	04	240 14.5	52.0	158 31.4	9.7	12 42.1	10.5	58.6
	05	255 14.4	52.2	173 00.1	9.8	12 31.6	10.7	58.6
	06	270 14.3	N22 52.4	187 28.9	9.9	N12 20.9	10.7	58.6
	07	285 14.2	52.7	201 57.8	10.0	12 10.2	10.7	58.5
T	08	300 14.1	52.9	216 26.8	10.1	11 59.5	10.8	58.5
H	09	315 13.9	. . 53.1	230 55.9	10.1	[illegible]	10.9	58.5
U	10	330 13.8	53.3	245 25.0	10.2	11 37.8	10.9	58.4
R	[illegible]	[illegible]	[illegible]	[illegible]	10.3	11 26.9	10.9	58.4
S	[illegible]	[illegible]	[illegible]	[illegible]	10.4	N11 16.0	11.1	58.4
D	[illegible]	[illegible]	[illegible]	[illegible]	10.5	11 04.9	11.0	58.3
A	[illegible]	[illegible]	[illegible]	[illegible]	10.5	10 53.9	11.1	58.3
Y	[illegible]	[illegible]	[illegible]	[illegible]	10.6	10 42.8	11.1	58.3
	16	60 13.1	54.6	332 21.5	10.7	10 31.7	11.2	58.2
	17	75 13.0	54.8	346 51.2	10.8	10 20.5	11.3	58.2
	18	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11.2	58.2
	19	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11.3	58.1
	20	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11.4	58.1
	21	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11.3	58.1
	22	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11.5	58.0
	23	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11.4	58.0
	9 00	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11.5	58.0
	01	195 12.0	56.5	102 51.6	11.3	8 49.6	11.5	57.9
	02	210 11.9	56.7	117 21.9	11.5	8 38.1	11.6	57.9
	03	225 11.8	. . 56.9	131 52.4	11.5	8 26.5	11.5	57.9
	04	240 11.6	57.1	146 22.9	11.5	8 15.0	11.7	57.8
	05	255 11.5	57.3	160 53.4	11.7	8 03.3	11.6	57.8
	06	270 11.4	N22 57.5	175 24.1	11.7	N 7 51.7	11.7	57.8
	07	285 11.3	57.7	189 54.8	11.7	7 40.0	11.6	57.7
	08	300 11.1	57.9	204 25.5	11.9	7 28.4	11.8	57.7
F	09	315 11.0	. . 58.1	218 56.4	11.9	7 16.6	11.7	57.7
R	10	330 10.9	58.3	233 27.3	11.9	7 04.9	11.7	57.6
I	11	345 10.8	58.5	247 58.2	12.0	6 53.2	11.8	57.6
D	12	0 10.6	N22 58.7	262 29.2	12.1	N 6 41.4	11.8	57.6
A	13	15 10.5	58.9	277 00.3	12.2	6 29.6	11.8	57.5
Y	14	30 10.4	59.1	291 31.5	12.2	6 17.8	11.9	57.5
	15	45 10.3	. . 59.3	306 02.7	12.2	6 05.9	11.8	57.5
	16	60 10.1	59.5	320 33.9	12.3	5 54.1	11.9	57.4
	17	75 10.0	59.7	335 05.2	12.4	5 42.2	11.9	57.4
	18	90 09.9	N22 59.9	349 36.6	12.4	N 5 30.3	11.9	57.4
	19	105 09.8	23 00.1	4 08.0	12.5	5 18.4	11.9	57.3
	20	120 09.7	00.3	18 39.5	12.5	5 06.5	11.9	57.3
	21	135 09.5	. . 00.4	33 11.0	12.6	4 54.6	12.0	57.3
	22	150 09.4	00.6	47 42.6	12.6	4 42.6	11.9	57.2
	23	165 09.3	00.8	62 14.2	12.7	4 30.7	12.0	57.2
	10 00	180 09.2	N23 01.0	76 45.9	12.7	N 4 18.7	11.9	57.2
	01	195 09.0	01.2	91 17.6	12.8	4 06.8	12.0	57.2
	02	210 08.9	01.4	105 49.4	12.8	3 54.8	12.0	57.1
	03	225 08.8	. . 01.6	120 21.2	12.9	3 42.8	11.9	57.1
	04	240 08.7	01.8	134 53.1	12.9	3 30.9	12.0	57.1
	05	255 08.5	02.0	149 25.0	12.9	3 18.9	12.0	57.0
	06	270 08.4	N23 02.1	163 56.9	13.0	N 3 06.9	12.0	57.0
	07	285 08.3	02.3	178 28.9	13.1	2 54.9	12.0	57.0
S	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	2 42.9	12.0	56.9
A	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	2 30.9	12.0	56.9
T	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	2 18.9	12.0	56.9
U	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	2 06.9	11.9	56.9
R	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	12.0	56.8
D	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	1 43.0	12.0	56.8
	14	30 07.4	03.6	280 14.0	[illegible]	[illegible]	[illegible]	[illegible]
	[illegible]	[illegible]	[illegible]	294 46.3	[illegible]	[illegible]	[illegible]	[illegible]
	[illegible]	[illegible]	[illegible]	309 18.7	[illegible]	[illegible]	[illegible]	[illegible]
	[illegible]	[illegible]	[illegible]	323 51.1	[illegible]	[illegible]	[illegible]	[illegible]
	[illegible]	[illegible]	[illegible]	338 23.5	[illegible]	[illegible]	[illegible]	[illegible]
	19	105 06.8	04.5	352 55.9	[illegible]	[illegible]	[illegible]	[illegible]
	20	120 06.6	04.7	7 28.4	[illegible]	[illegible]	[illegible]	[illegible]
	21	135 06.5	. . 04.8	22 00.9	[illegible]	[illegible]	[illegible]	[illegible]
	22	150 06.4	05.0	36 33.4	13.5	S 0 04.6	[illegible]	56.5
	23	165 06.3	05.2	51 05.9	13.6	S 0 16.5	11.9	56.5
		SD 15.8	d 0.2	SD	15.9	15.7		15.5

Lat.	Twilight Naut.	Twilight Civil	Sunrise	Moonrise 8	Moonrise 9	Moonrise 10	Moonrise 11
°	h m	h m	h m	h m	h m	h m	h m
N 72	▭	▭	▭	08 58	11 03	12 57	14 48
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11 13	13 00	14 43
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11 21	13 02	14 39
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11 28	13 03	14 35
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11 34	13 05	14 32
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11 39	13 06	14 30
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	11 43	13 07	14 28
N 58	////	01 47	02 59	10 24	11 47	13 08	14 26
56	////	02 15	03 15	10 30	11 50	13 08	14 24
54	00 59	02 36	03 29	10 35	11 53	13 09	14 22
52	01 38	02 53	03 41	10 40	11 56	13 10	14 21
50	02 04	03 07	03 51	10 45	11 59	13 10	14 20
45	02 47	03 36	04 13	10 54	12 04	13 12	14 17
N 40	03 17	03 58	04 31	11 02	12 09	13 13	14 15
35	03 40	04 16	04 46	11 09	12 12	13 14	14 13
30	[illegible]	04 31	04 58	11 15	12 16	13 14	14 11
20	[illegible]	04 55	05 20	11 25	12 22	13 16	14 08
N 10	[illegible]	05 15	05 38	11 34	12 27	13 17	14 06
0	[illegible]	05 33	05 56	11 42	12 32	13 18	14 03
S 10	[illegible]	05 50	06 13	[illegible]	[illegible]	13 19	14 01
20	[illegible]	06 07	06 31	[illegible]	[illegible]	13 21	13 59
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	13 22	13 56
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	12 51	13 23	13 54
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	12 54	[illegible]	13 52
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
[illegible]	[illegible]	[illegible]	[illegible]	12 43	13 06	13 27	13 47
[illegible]	[illegible]	[illegible]	[illegible]	12 48	13 09	13 28	13 46
56	06 51	07 40	08 27	12 53	[illegible]	[illegible]	[illegible]
58	06 58	07 50	08 41	12 59	[illegible]	[illegible]	[illegible]
S 60	07 05	08 01	08 58	[illegible]	[illegible]	[illegible]	[illegible]

Lat.	Sunset	Twilight Civil	Twilight Naut.	Moonset 8	Moonset 9	Moonset 10	Moonset 11
°	h m	h m	h m	h m	h m	h m	h m
N 72	▭	▭	▭	02 21	02 00	01 44	01 29
N 70	▭	▭	▭	01 58	01 47	01 39	01 30
68	▭	▭	▭	01 40	01 37	01 34	01 31
66	23 32	////	////	01 25	01 29	01 31	01 32
64	22 20	////	////	01 13	01 22	01 28	01 33
62	21 45	////	////	01 03	01 15	01 25	01 33
60	21 20	22 57	////	00 54	01 10	01 23	01 34
N 58	21 00	22 13	////	00 47	01 05	01 20	01 34
56	20 44	21 45	////	00 40	01 01	01 19	01 35
54	20 30	21 24	23 02	00 34	00 57	01 17	01 35
52	20 18	21 06	22 22	00 28	00 53	01 15	01 36
50	20 08	20 52	21 56	00 23	00 50	01 14	01 36
45	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
N 40	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
35	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
30	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
20	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
N 10	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
0	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
S 10	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]
20	17 28	17 52	18 19	23 52	24 48	00 48	01 41
30	17 07	17 33	18 03	23 44	24 44	00 44	01 42
35	16 55	17 23	17 54	23 40	24 42	00 42	01 42
40	16 41	17 11	17 45	23 34	24 39	00 39	01 43
45	16 25	16 58	17 35	23 28	24 37	00 37	01 43
S 50	16 04	[illegible]	[illegible]	[illegible]	[illegible]	00 33	01 44
52	15 55	[illegible]	[illegible]	[illegible]	[illegible]	00 31	01 44
[illegible]	15 44	[illegible]	[illegible]	[illegible]	[illegible]	00 30	01 44
[illegible]	15 32	[illegible]	[illegible]	[illegible]	[illegible]	00 28	01 45
[illegible]	15 17	[illegible]	[illegible]	[illegible]	[illegible]	00 26	01 45
[illegible]	15 01	15 57	16 54	22 58	24 23	00 23	01 45

	SUN Eqn. of Time 00ʰ	SUN Eqn. of Time 12ʰ	SUN Mer. Pass.	MOON Mer. Pass. Upper	MOON Mer. Pass. Lower	MOON Age		MOON Phase
d	m s	m s	h m	h m	h m	d	%	
8	01 00	00 55	11 59	17 54	05 29	06	43	◐
9	00 49	00 43	11 59	18 43	06 19	07	54	
10	00 37	00 31	11 59	19 29	07 06	08	64	

Chapter 8 *Sight Reduction*

The process of taking the raw observational data and turning the information into a Line Of Position (LOP) is called *sight reduction*. Even though the equations and methods have been described all throughout the book, what is needed here most is organization to minimize the calculation random errors.

History

Trigonometric tables were first published by Regiomontanus in the mid 1400's, followed by the early logarithm tables of Edmund Gunter in the late 1600's, which allowed multiplication to be treated as addition problems. This is the basis of the slide rule (does anybody remember those??). French almanacs were published in the late 1600's where the original zero longitude 'rose line' ran thru Paris. The English almanacs were published later in the 1700's. The altitude-difference method of determining a line of position introduced the age of improved navigation, described in 1875 by Commander Adolphe-Laurent-Anatole Marcq de Blonde de Saint-Hilaire, of the French Navy. This 'Marcq Saint-Hilaire' method remains the basis of almost all celestial navigation used today. But the Sumner line method may be considered equally easy, 2 computations for the Saint-Hilaire method, and 2 for the Sumner line method. Computed altitude and azimuth angle have been calculated by means of the log sine, cosine, and haversine (½ [1-cos]), and natural haversine tables.

Sight reduction was greatly simplified early in the 1900's by the coming of the various short-method tables - such as the Weems Line of Position Book, Dreisonstok's *Hydrographic Office* method H.O. 208 (1928), and Ageton's H.O. 211 (1931). Almost all calculations were eliminated when the inspection tables, H.O. 214 (1936), H.O. 229, and H.O. 249 were published, which tabulated zillions of pre-computed solutions to the navigational triangle for all combinations where LHA and latitude are whole numbers. The last two methods, H.O. 229 and H.O. 249 developed in the mid 1940's and early 1950's remain the principle tabular method used today. The simplest tabular method of all is to use a shorthand version of Ageton's tables known as the S-tables, which are only 9 pages long. No whole number assumptions are required, and the answers are the same as a navigational calculator. You must do some minor addition, though, and the tables are a bit of a maze (takes practice).

The following page is an example of a sight-reduction form using the "calculator method" instead of the typical HO 229, 249 tabular methods.

SIGHT REDUCTION BY CALCULATOR, INTERCEPT METHOD

Sun / Moon / Planet / Star   LL / UL   UT Date _____m _____d______yr
Time of observation   UTC = _____h _____m _____s
DR position (1)   Lat = _____________   Lon = ______________
Eye height   Heye ______meters
Index correction   IC = ______ arcmin
Sextant measured altitude Hs = ___________deg _________arcmin

Dip correction from the corrections table: Corr^{DIP} = ____________
Apparent altitude Ha = Hs + IC + Corr^{DIP} **Ha** = _____________
Altitude correction from the corrections table: Corr^{ALT} = ____________
True altitude Ho = Ha + Corr^{ALT} **Ho** = _____________

From the almanac tabular data, at the h hour on the UT date:
GHA table = _____________   *v* = ____________
DEC table = _____________ (1)   *d* = ____________ (careful of the sign)
SHA = ______________ if star
Increment of GHA for the m minutes and s seconds Corr^{GHA} = ____________
Additional increment due to variation *v* Corr^{v} = ____________
(2) GHA = GHA table + Corr^{GHA} + Corr^{v} **GHA** = ____________

Increment of DEC for m minutes due to rate *d* is Corr^{d} = ____________
DEC = DEC table + Corr^{d} **DEC** = ____________

Local Hour angle LHA = GHA + Lon   **LHA** = ____________

(repeat Ho here to subtract Hc from)   **Ho** _______________

arcSin[Sin(DEC) · Sin(Lat) + Cos(Lat) · Cos(DEC) · Cos(LHA)] = **Hc** _______________

Ho – Hc = _______________ · 60 = Offset Distance **= Doffset** _________n.miles

arcCos[{Sin(DEC) – Sin(Lat) · Sin(Hc)}/{Cos(Lat) · Cos(Hc)}] = **Zo** _______________

True Azimuth Angle from True North **Zn**
If LHA is pre-meridian passage (-, or 180<LHA < 360), **Zn = Zo**
If LHA is post-meridian passage (0<LHA < 180), **Zn = 360 – Zo**   **Zn =** ___________

Notes: (1) North is+, South is -. East is +, West is -
(2) GHA table = SHA + GHA Aries for a star

Sun Shot Example

Let’s say this is the data:
DR position Lat = 44.025° N, Lon = -67.850° W
Eye height = 2 meters Greenwich date 7/15/2001
Index correction IC = +3.4’
Time of observation UTC = 14h 15m 37s
Sextant measured altitude of the sun Hs = 52° 52.3’ Lower Limb

Altitude corrections from the abridged corrections table:
Corr^{DIP} = -2.5’ Corr^{ALT} = +15.3’ (interpolate in your head)
Observed true altitude Ho = 52° 52.3’ + 3.4’ -2.5’ +15.3’ = 53° 8.5’ = 53.1416°

From the almanac tabular data, at the 14th hour July 15 2001:
GHA table = 28° 30.6’
DEC table = +21° 27.3’ N d = -0.4’ moving less northerly

Increment of GHA for the 15 minutes and 37 seconds Corr^{GHA} = 3° 54.3’
GHA = 28° 30.6’ + 3° 54.3’ = 32° 24.9’ = 32.4150°

Increment of DEC for 15 minutes due to rate d is Corr^{d} = - 0.1’
DEC = +21° 27.3’ - 0.1’ = 21° 27.2’ = 21.4533°

Calculations:

Local Hour angle LHA = GHA + Lon = 32.415° + - 67.850° = - 35.435°

Calculated Altitude
Hc = arcSin[Sin(21.453°) • Sin(44.025°) + Cos(44.025°) • Cos(21.453°) • Cos(- 35.435°)]
Hc = 53.0767° = 53° 4.6’

Intercept Offset distance Doffset = 60 • (53.1416° – 53.0767°) = +3.9 n mile
Offset the assumed LOP towards the Sun azimuth.

Calculated Azimuth direction of sun
Zo = arcCos[{Sin(21.453°) – Sin(44.025°) • Sin(53.0767°)}/{Cos(44.025°) • Cos(53.0767°)}]
Zo = 116°, and since LHA is negative (pre-meridian), Zn = Zo = 116°

Moon Shot Example

Let’s say this is the data:
DR position Lat = 44.025° N,   Lon = -67.850° W
Eye height = 2 meters   Greenwich date 7/15/2001
Index correction IC = +3.4’
Time of observation UTC = 14h 20m 21s
Sextant measured altitude of the moon Hs = 44° 22.1’   Upper Limb (UL)

Altitude corrections from almanac moon correction tables, in two parts:
Corr^{DIP} = -2.5’
Corr^{ALT} = +50.9’ + 3.2’ –30.0’ (the –30’ is for using the UL)   = 24.1’
True altitude Ho = 44° 22.1’ + 3.4’ -2.5’ +24.1’ = 44° 47.1’ = 44.7850°

From the almanac tabular data, at the 14th hour July 15 2001:
GHA table = 100° 23.7’   v = +12.2’
DEC table = +12° 9.4’ N   d = +11.2’   HP = 56.8’

Increment of GHA for the 20 minutes and 21 seconds Corr^{GHA} = 4° 51.3’
Additional increment due to variation v Corr^{v} = 4.2’
GHA = 100° 23.7’ + 4° 51.3’ + 4.2’ = 105° 19.2’ = 105.3200°

Increment of DEC for 20 minutes due to rate d is Corr^{d} = +3.8’
DEC = +12° 9.4’ + 3.8’ = 12° 13.2’ = 12.2200°

Calculations:

Local Hour angle LHA = GHA + Lon = 105.32° + - 67.850° = 37.470°

Calculated Altitude
Hc = arcSin[Sin(12.22°) · Sin(44.025°) + Cos(44.025°) · Cos(12.22°) · Cos(37.470°)]
Hc = 44.817° = 44° 49.0’

Intercept Offset distance Doffset = 60 · (44.368° – 44.817°) = -2.0 n mile
Offset the assumed LOP away from the moon’s azimuth.

Calculated Azimuth direction of moon
Zo = arcCos[{Sin(12.22 °) –   Sin(44.025°) · Sin(44.817°)}/{Cos(44.025°) · Cos(44.817°)}]
Zo = 123°, and since 0 < LHA <180 (post-meridian), Zn = 360 - Zo = 237°

Star Shot Example

You took a shot of Deneb in the constellation of Cygnus, morning twilight:
DR position Lat = 44.025° N, Lon = -67.850° W
Eye height = 2 meters Greenwich date 7/15/2001
Index correction IC = +3.4’
Time of observation UTC = 8h 31m 24s
Sextant measured altitude of Deneb, Hs = 59° 47.8’

Altitude corrections from the abridged corrections table:
Corr$^{\mathrm{DIP}}$ = -2.5’
Corr$^{\mathrm{ALT}}$ = -0.5’
True altitude Ho = 59° 47.8’ +3.4’ –2.5’ – 0.5’ = 59° 48.2’ = 59.8033°

From the almanac tabular data, at the 8th hour July 15 2001:
GHA$_{\mathrm{Aries}}$ table = 53° 14.4’ SHA$_{\mathrm{DENEB}}$ = 49° 37.4’
DEC$_{\mathrm{DENEB}}$ = +45° 17.1’ N
No *v* or *d* corrections for stars
Increment of GHA for the 31 minutes and 24 seconds Corr$^{\mathrm{GHA}}$ = 7° 52.3’
GHA = 53° 14.4’ + 7° 52.3’ + 49° 37.4’ = 110° 44.1’ = 110.735°

DEC = DEC$_{\mathrm{DENEB}}$ = +45° 17.1’ N = +45.2850°

Calculations:

Local Hour angle LHA = GHA + Lon = 110.735° + – 67.850° = 42.885°

Calculated Altitude
Hc = arcSin[Sin(45.285°) · Sin(44.025°) + Cos(44.025°) · Cos(45.285°) · Cos(42.885°)]
Hc = 59.830° = 59° 49.8’

Intercept Offset distance Doffset = 60 · (59.8033° –59.830°) = –1.6 n mile
Offset the assumed LOP away from the star’s azimuth.

Calculated Azimuth direction of star
Zo = arcCos[{Sin(45.2850°) – Sin(44.025°) · Sin(59.83°)}/{Cos(44.025°) · Cos(59.83°)}]
Zo = 72°, and since 0 < LHA <180 (post-meridian), Zn = 360 - Zo = 288°

Planet Shot Example

Mars in the evening, same local day, but the next day in GMT:
DR position Lat = 44.025° N, Lon = -67.850° W
Eye height = 2 meters Greenwich date 7/16/2001
Index correction IC = +3.4’
Time of observation UTC = 01h 11m 24s
Sextant measured altitude of Mars, Hs = 18° 40.0’

Altitude corrections from the abridged corrections table:
Corr^{DIP} = -2.5’
Corr^{ALT} = -3.0’
True altitude Ho = 18° 40.0’ +3.4’ –2.5’ – 3.0’ = 18° 37.9’ = 18.632°

From the almanac tabular data, at the 1st hour July 16 2001:
GHA_{MARS} table = 55° 30.6’ DEC_{MARS} table = –26° 50.5’ S
v = +2.6’ and *d* =0
Increment of GHA for the 11 minutes and 24 seconds Corr^{GHA} = 2° 51.0’
Additional increment due to variation v Corr^{v} = 0.5’
GHA = 55° 30.6’ + 2° 51.0’ + 0.5’ = 58° 22.1’ = 58.368°

DEC = DEC_{MARS} = –26° 50.5’ = –26.842°

Calculations:

Local Hour angle LHA = GHA + Lon = 58.368° + – 67.850° = – 9.482°

Calculated Altitude
Hc = arcSin[Sin(-26.842°) · Sin(44.025°) + Cos(44.025°) · Cos(-26.842°) · Cos(-9.482°)]
Hc = 18.602° = 18° 36.1’

Intercept Offset distance Doffset = 60 · (18.632° – 18.602°) = +1.8 n mile
Offset the assumed LOP towards Mars’s azimuth.

Calculated Azimuth direction of Mars
Zo = arcCos[{Sin(-26.842°) – Sin(44.025°) · Sin(18.602°)}/{Cos(44.025°) · Cos(18.602°)}]
Zo = 171°, and since LHA is negative (pre-meridian), Zn = Zo = 171°

Plots of the Lines Of Position (LOP) from the previous 4 examples

The observer was stationary during all of the observations. The arrows indicate the azimuth direction (bearing from true north) of the heavenly objects. These observations are over the course of a day, from early morning twilight to mid morning to evening twilight. The ellipse represents the 95% probability area of the position fix using all 4 LOPs.



Chapter 9 *Putting it Together and Navigating*

I encourage you the navigator to program your simple calculators to provide the calculated altitude Hc and calculated uncorrected azimuth Zo from inputs of latitude, longitude, GHA, and DEC. It's too easy to make mistakes punching in numbers and doing the trig. A simple programmable calculator mechanizing the simple steps in the calculations will go a long way in reducing the silly arithmetic errors.

Plane Sailing and Dead Reckoning (DR)

With the celestial methods described so far, an important element was the estimated position, also known as the *dead reckoning* (DR) position. Undoubtedly, if you didn't reckon correctly, you would sooner or later regret it. Strictly speaking, an estimated position is not needed, just as it is not needed with the *Global Positioning System.* In the case of GPS, orbiting spacecraft have geographical positions and circles of constant altitude, but electronically it is circles of constant timing. Three spacecraft, three circles and you are pinpointed. But since intersecting straight LOPs is a lot easier than solving simultaneous equations for intersecting circles, an estimated position is essential for our simple methods. In our day-to-day wanderings, flat-Earth approximations are close enough to advance the estimated position from a previously known fix. These approximation methods are known as *plane sailing.*

Dead reckoning is simple to understand on a flat earth, say using your car. If you head northwest at 60 mph, and you drove for 2 hours, you should be 120 miles to the northwest of your last position. But on a spherical surface, the longitude lines start to crowd in on each other as they reach the poles. The 'crowding in' at the current latitude can be thought of as being more or less fixed for short distances. Just think, on the north or south pole, you could wander across all 360 longitude lines in just a few short steps!



Plane Sailing Shorthand

True course from true north TC

Speed of vessel, knots

Time interval from last fix, hours

$D = \text{Speed} \cdot \text{Time}$ *distance traveled nmile*

$D_{EW} = D \sin(TC)$ *east-west distance*

$D_{NS} = D \cos(TC)$ *north-south distance*

$\Delta\text{Lat} = D_{NS}$ *arcmin latitude change*

$\Delta\text{Lon} = D_{EW} / \cos(\text{Lat})$ *arcmin longitude change*

Plane Sailing Work Sheet

Last Known Latitude, decimal degrees N+, S-

$\mathbf{Lat_O =}$ →

Last Known Longitude, decimal degrees E+, W-

$\mathbf{Lon_O} =$ →

Speed of vessel, corrected for current, knots (kts)

$\mathbf{V} =$ →

Time interval between the present desired fix and the last fix, decimal hours

$\mathbf{\Delta Time =}$ →

True course made good (heading, compensated for leeway and current), decimal degrees from true north

$\mathbf{TC} =$ →

Estimate of distance, nautical miles (nm)

$\mathbf{D = V \cdot \Delta Time}$ →

Change in latitude, arcminutes

$\mathbf{\Delta Lat = D \cdot Cos(TC)}$ →

New estimated latitude, decimal degrees

$\mathbf{Lat_{DR} = Lat_O + \Delta Lat/60}$ →

Change in longitude, arcminutes

$\mathbf{\Delta Lon = D \cdot Sin(TC)/Cos(Lat_O + \Delta Lat/120)}$ →

New estimated longitude, decimal degrees

$\mathbf{Lon_{DR} = Lon_O + \Delta Lon/60}$ →

Running Fix

The *running fix* is a method by which two or more line of positions (LOPs) taken at different times on a moving vessel can be coalesced together to represent a navigational fix at any single arbitrary time between the observations. Most frequently, it is used to advance an old LOP to get a fix with a new LOP while the ship is under way. Quite simply, the old LOP is parallel-advanced in the direction of the true course-made-good (TC) to the DR distance between the last LOP and the new one. With a quick study of the figure, the reader should discern the mechanics involved. Essentially, if you produced a 'good' LOP earlier, you can 'drag it' along with your moving vessel as if it were pinned to the stern using the simple distance = rate x time for the distance to drag, and it gets dragged in the same course direction as the vessel.


LOP # 1
at time t_1
LOP #1 advanced to
time-coincide with
LOP #2
RUNNING FIX
N_T
TC
True Course
Direction
W
E
S
LOP # 2
at time t_2
Roffset
Distance-made-good
between observations
= Speed(Kts) x Time(Hrs)

Daily Observation Schedule

During your typical navigating in-the-blue sort of day, you would follow a procedure similar to this:

1) Pre-dawn sighting of planets and stars, providing a definite fix.
2) Mid-morning Sun observation, advancing a dawn LOP for a running fix.
3) Noonish sighting, advancing the mid-morning LOP for a running fix.
4) Mid-afternoon Sun observation, advancing the noon LOP for a running fix.
5) Twilight observation of planets and stars, providing a definite fix.

Note: Morning and evening twilight observations need to be carefully planned. It is a time when both night objects and the horizon are visible simultaneously. That's not a whole lot of time for off-the-cuff navigation. Plan the objects, their estimated altitudes and azimuth angles. Double check with the compass, so that you are sure of what you are looking at.

A Sun-Moon fix is nice when available. When the moon is a young moon, it will be in the sky east of the sun in the late afternoon. When it is an old moon, it will share the sky west of the sun during the morning hours.


DAYTIME CELESTIAL NAVIGATION
OBSERVATION PLAN
LOP#7
LOP#6
TWILIGHT
D4
RUNNING FIX
LOP#4
LOP#5
RUNNING FIX
D3
NOON
LOP#4
RUNNING FIX
D2
LOP#3
DAWN
LOP#2
D1
LOP#3
LOP#1
LOP#2

Plotting Multiple Lines of Position (LOP) with Running Fixes

Plotting the LOPs is best done on a **universal plotting** sheet, which is a sheet of paper with a graduated compass rose in the center. This is very convenient, as you can do everything necessary to plot a LOP, requiring in addition a drafting triangle and a scaled ruler. Let us say that we have the true course **TC**, the speed **V** (kts), the times of the observation $\mathbf{t_1}$, $\mathbf{t_2}$, $\mathbf{t_3}$ (decimal hrs), etc., the observed altitudes $\mathbf{Ho_1}$, $\mathbf{Ho_2}$, $\mathbf{Ho_3}$, and an assumed position **LATa**, **LONa**. From sight reduction, we also have the calculated altitudes $\mathbf{Ha_1}$, $\mathbf{Ha_2}$, $\mathbf{Ha_3}$, the intercept distances $\mathbf{Doffset_1}$, $\mathbf{Doffset_2}$, $\mathbf{Doffset_3}$ and the calculated azimuths $\mathbf{Zn_1}$, $\mathbf{Zn_2}$, $\mathbf{Zn_3}$. Since the vessel is continuously underway, we define an arbitrary time that we want the newest fix to apply to. We were at such-and-such location at such-and-such time, even though that time does not correspond exactly to any of the observation times. This selected time for the fix is called the **time of fix**, $\mathbf{t_{fix}}$. We calculate the running fix distance corrections that each observation will require, and designate it $\mathbf{Roffset_1}$, $\mathbf{Roffset_2}$, $\mathbf{Roffset_3}$. The corrections are calculated thus:

$\mathbf{Roffset_1 = V \cdot (t_{fix} - t_1)}$, $\mathbf{Roffset_2 = V \cdot (t_{fix} - t_2)}$, etc.. (n.miles)

Notice that for observation times after the time of fix, the offset is negative.

The procedure seems complicated, but after trying it once, the mechanics will seem obvious. Basically you draw the Roffset vector from the center of the compass rose along the direction of the true course, then draw the Doffset vector from the head of the Roffset vector, then draw the LOP from that point. Here are the detailed steps:

1) The very center of the compass rose on the plotting sheet is designated as the assumed position LATa, LONa. All else is relative to this location.
2) Draw a line thru the center in the direction of the true course TC going both ways, but with an arrow showing the forward direction.
3) Generally there are two scales you can use. The plotting sheet has a built-in scale of 60 n.miles which could just as easily be 6 n.miles for those close encounters. Staying in either the 60 or 6 n.m. scale makes corresponding latitude and longitude measurements possible without calculations.
4) For the first observation, measure along the true course line in the forward direction (if Roffset is +, backwards if Roffset is -) the distance Roffset and mark it with a dot.
5) Then from that mark, draw a line in the azimuth direction Zn, the length being the distance Doffset. If Doffset is negative, draw the line in the opposite direction (180 degrees different). Mark the spot.

6) Draw a line perpendicular to the Zn, passing thru the last mark. This is the LOP compensated for intercept and running to an arbitrary time.
7) Repeat for all the other LOPs.

Plotting a Line Of Position (LOP) on a Universal Plotting Sheet with a running-fix correction Roffset and the intercept offset Doffset


Roffset and Doffset in n.miles
LON A
N T
Center point is the assumed longitude and latitude
W
LAT A
E
Roffset
Construction Lines
Course Direction
Doffset
LOP
S
Azimuth Direction

MULTIPLE INTERCEPT LOP with RUNNING FIX CORRECTIONS

Roffset #1 = $V \times (t_{fix} - t_1)$

Roffset #2 = $V \times (t_{fix} - t_2)$

Roffset #3 = $V \times (t_{fix} - t_3)$

Times of Observation: t_1 t_2 t_3 (hours)

Desired Time of Fix: t_{fix} (hours)

Time t is expressed in decimal hours,
for example, 1.073, 0.374, etc..

Speed V is expressed in knots (n.mi./hr)

Altitude H is expressed in decimal degrees

Doffset #1 = $60\times(Ho_1 - Hc_1)$

Doffset #2 = $60\times(Ho_2 - Hc_2)$

Doffset #3 = $60\times(Ho_3 - Hc_3)$


LOP#1
LOP#2
D_{LON}
Best Fix
LOP#3
D_{LAT}
TC
Doffset #2
Doffset #3
Assumed Position
LAT_A LON_A
Course Direction at Velocity V
Doffset #1
Roffset #3 (if −)
Roffset #2
Roffset #1
Negative (−) Running Fix Correction (AfterTime of Fix)
Positive (+) Running Fix Correction (Before Time of Fix)

Once all the LOPs are plotted, you can mark what appears to be the best solution of the fix. Measure the distance with the linear scale you are using for the plot from the center. The north-south distance we will designate as $\mathbf{D_{LAT}}$, and the east-west distance as $\mathbf{D_{LON}}$ in nautical miles. Following the sign conventions, if northwards or eastwards, the number is +. If southwards or westwards, the number is -. The corrective change Δ in latitude and longitude from the assumed position **LATa**, **LONa** is thus:

$$\mathbf{LAT_{\Delta} = (D_{LAT} / 60)} \qquad \text{decimal degrees}$$

$$\mathbf{LON_{\Delta} = (D_{LON} / 60) / Cos(LATa + LAT_{\Delta}/2)} \quad \text{decimal degrees}$$

The position of the new fix is thus:

$\mathbf{LAT_{FIX} = LATa + LAT_{\Delta}}$

$\mathbf{LON_{FIX} = LONa + LON_{\Delta}}$

The corrective change can also be deduced graphically, from the universal plotting sheet, as it is really set up for this. The compass rose lets you set up your own custom longitude scale for your latitude. Where the latitude angle intersects the circle, you draw the custom longitude line for that position. Remember, 1 nautical mile N-S is equivalent to 1 arcminute of latitude.


Universal Plotting Sheet
Custom-made longitude increments
for the particular latitude
intersection with circle
LATITUDE ANGLE
LAT
LATITUDE INCREMENT
60 arcMinutes
60 n.miles
LONGITUDE INCREMENT
60 arcMinutes
60 x Cos(Lat) n.miles
LON

CALCULATING A FIX FROM MULTIPLE LOPs FROM A FIXED ASSUMED POSITION WHILE RUNNING

N = total number of LOPs participating in the fix

Form the quantities A,B,C,D,E,G from these summations:

$$A = \sum_{n=1}^{N} \operatorname{Cos}\left(AZM_n\right)^2 \qquad B = \sum_{n=1}^{N} \operatorname{Cos}\left(AZM_n\right)\cdot\operatorname{Sin}\left(AZM_n\right)$$

$$C = \sum_{n=1}^{N} \operatorname{Sin}\left(AZM_n\right)^2 \qquad D = \sum_{n=1}^{N} \operatorname{Cos}\left(AZM_n\right)\cdot\left(p1_n + p2_n\right)$$

$$G = A\cdot C - B^2 \qquad E = \sum_{n=1}^{N} \operatorname{Sin}\left(AZM_n\right)\cdot\left(p1_n + p2_n\right)$$

Where $p1_n = \dfrac{Doffset_n}{60}$ and $p2_n = \dfrac{Roffset_n}{60}\cdot\operatorname{Cos}\left(AZM_n - TC\right)$

$Doffset_n$ is the nth intercept offset distance, n.miles

$Roffset_n$ is the nth running-fix offset distance, n.miles

AZM_n is the nth azimuth direction of the nth heavenly body

TC is the true course angle from true north

$$LON_I = LON_A + \frac{(A\cdot E - B\cdot D)}{G\cdot\operatorname{Cos}\left(LAT_A\right)}$$

Improved Longitude estimate from the assumed position

$$LAT_I = LAT_A + \frac{(C\cdot D - B\cdot E)}{G}$$

Improved Longitude estimate from the assumed position

$$dist = 60\cdot\sqrt{\left(LON_I - LON_A\right)^2\cdot\cos\left(LAT_A\right)^2 + \left(LAT_I - LAT_A\right)^2}$$

Distance from assumed fix to calculated fix, nm. Should be < 20 nm.
If not, use the improved fix as the new assumed position and start all over again

Good Practice and Error Reduction Techniques

There are many sources of error, not the least misidentification of the heavenly object. Slim chance of that happening with the Sun or Moon. With objects that you are sure of, a set of 3 or 4 shots of each known object can reduce random measurement errors. With stars at twilight, perhaps it is better to take single shots but have many targets to reduce the effects of misidentification. This type of error has the distinction of putting you hundreds of miles off, and so are easy to catch, allowing you to disregard the specific data.


Hs
pick this Hs and time for the LOP calculation
Hs avg
mid-time is the most accurate place to pick Hs average
time
Time avg
Hs
calulate slope and move up to fit data
time

Graphically averaging with slope

Graphically averaging

Handling measurement random errors graphically

Random Errors

The effect of multiple shots of the same object are such that the random errors, some +, some -, will average to zero. Random measurement errors of plus or minus several miles are handled several basic ways for a set of shots of the same object:

1) Calculate all the LOPs in a set and average them graphically on the map.
2) Arithmetically average the times and altitudes for a set of shots, and calculate one LOP using the averaged value of time and altitude.
3) Graph the set of shots with time on the horizontal and altitude on the vertical. Draw a line representing the average and from that pick one time and altitude from the line to calculate one LOP. This is the easiest.
4) Graph the shots as in 3), but calculate a slope and fit it to the data. The slope is determined by calculating Hc for two different times in the range of the data set with your estimated position. With these two new points, draw a line between them. Parallel offset this new line until it fits best in the data points already drawn. Then, as in 3), pick one time and altitude from the line to calculate one LOP.

Using technique 4) should result in the most accurate LOP, however there are more calculations making it the same trouble as 1). On the other hand, practical navigation is not usually concerned with establishing a position to within ¼ mile, so unless you are particular, **graphing your measurements as in technique 3) may be the easiest to implement with a good payoff for reducing random errors**. Arithmetically averaging instead of graphically averaging is a good way to introduce unwanted calculation mistakes, so I would steer away from technique 2) for manual calculations.

Systematic Errors

This species of error, where a constant error is in all of the measurements, can come from such things as an instrument error, a misread index error, your personal technique and bias, strange atmospheric effects, and clock error. All but clock error can be handled with the following technique. If you have many objects to choose from, choose 4 stars that are ~90 degrees apart from each other in azimuth, or with 3 stars make sure they are ~120 degrees apart. This creates a set of LOPs where the effect of optical systematic errors cancels.

LOPs 90° apart reveal a constant offset from the true position



LOPs 60° apart falsely implying position x with systematic error





LOPs 120° apart canceling systematic error

The steps for good practice

1) For a good fix, pick 3 or more clearly identified heavenly objects.

2) Pick objects that are spaced in azimuth 90 to 120 degrees apart for systematic error reduction.

3) If you can, make a tight spaced grouping of 3 shots per object.

4) Apply averaging techniques for random error reduction.

5) Advance the LOPs with a running fix technique to time coincide with the time of your last shots.

Chapter 10 *Star Identification*

There are various star finding charts, the 2102-D and Celestaire star chart come to mind. However, you could use the equations for calculated altitude and azimuth, rearranged, to help you identify stars. Now this only applies to the bright 58 'navigational stars', as data for their position on the celestial sphere (star globe) is given.
Rearranging the azimuth equation, we get the declination DEC:

$$\mathbf{DEC = arcSin[cos(AZM) \cdot cos(Lat) \cdot cos(H) + sin(Lat) \cdot sin(H)]}$$

If the declination is +, it is North, if – then it is South.
AZM is the approximate azimuth angle (magnetic compass + magnetic variation), Lat is the assumed latitude, and H is the altitude angle (don't bother with dip and refraction corrections).
Rearrange the calculated altitude equation to get local hour angle LHA:

$$\mathbf{LHA = (+/-)\ arcCos[\{sin(H) - sin(DEC) \cdot sin(Lat)\} / \{cos(Lat) \cdot cos(DEC)\}]}$$

If the azimuth is greater than 180°, then LHA is **+**.
If the azimuth is less than 180°, then LHA is **–**.
The sidereal hour angle ('longitude' on the star globe) is then:

$$\mathbf{SHA = LHA - GHA_{Aries} - Lon}$$

Where GHA aries is the Greenwich hour angle of aries (zero 'longitude' on the star globe) at the time of this observation from the almanac, and Lon is the assumed longitude position.

Once you have the essential information, SHA and DEC, then you can look it up in the star chart data to match it with the closest numbers. If the numbers still don't match any stars, then look in the almanac to match up SHA and DEC with any planets listed.

Star magnitudes refer to their brightness. Numerically, the larger the number, the dimmer the star. The brightest stars actually have negative magnitudes, such as Sirius (the brightest star) has a magnitude of -1.6.

It's actually best to this by software, or have constellation charts handy.

The 58 Navigational Stars Listing

SHA	DEC	Star	magnitude	color	constellation
358	+29	Alpheratz	2.2		Great Square
354	-42	Ankaa	2.4	Orange	Phoenix
350	+57	Schedar	2.5	Orange	Cassiopeia
349	-18	Diphda	2.2		Cetus
336	-57	Achernar	0.6		Eridanus
328	+23	Hamal	2.2	Orange	Aries
324	+89	Polaris	2.1		Little Dipper
315	-40	Acamar	3.1		Eridanus
315	+4	Menkar	2.8		Cetus
309	+50	Mirfak	1.9		Perseus
291	+16	Aldebaran	1.1	Orange	Taurus
281	-8	Rigel	0.3	Blue	Orion
281	+46	Capella	0.2	Yellow	Auriga
279	+6	Bellatrix	1.7		Orion
279	+29	Elnath	1.8		Taurus
276	-1	Alnilam	1.8		Orion
271	+7	Betelgeuse	1.0	Red	Orion
264	-53	Canopus	-0.9	White	Carina
259	-17	Sirius	-1.6	White	Canis Major
255	-29	Adhara	1.6		Canis Major
245	+5	Procyon	0.5	Yellow	Canis Minor
244	+28	Pollux	1.2		Gemini
234	-59	Avior	1.7		Carnia
223	-43	Suhail	2.2		Vela
222	-70	Miaplacidus	1.8		Carnia
218	-9	Alphard	2.2		Hydra
208	+12	Regulus	1.3		Leo
194	+62	Dubhe	2.0		Big Dipper
183	+15	Denebola	2.2		Leo
176	-18	Gienah	2.8		Cygnus
173	-63	Acrux	1.1		S. Cross
172	-57	Gacrux	1.6		S. Cross
167	+56	Alioth	1.7		Big Dipper
159	-11	Spica	1.2	Blue	Virgo
153	+49	Alkaid	1.9		Big Dipper
149	-60	Hadar	0.9		Centarus

SHA	DEC	Star	magnitude	color	constellation
148	-36	Menkent	2.3		Centarus
146	+19	Arcturus	0.2	Orange	Bootes
140	-61	Rigil Kent	0.1		Centarus
137	-16	Zuben'ubi	2.9	White	Libra
137	+74	Kochab	2.2	Orange	Little Dipper
126	+27	Alphecca	2.3		Corona Borea.
113	-26	Antares	1.2	Red	Scorpio
108	-69	Atria	1.9		S. Triangle
103	-16	Sabik	2.6		Ophiuchus
097	-37	Shaula	1.7		Scorpio
096	+13	Raselhague	2.1		Ophiuchus
091	+51	Eltanin	2.4		Draco
084	-34	Kaus Australis	2.0		Sagittarius
081	+39	Vega	0.1	White	Lyra
076	-26	Nunki	2.1		Sagittarius
062	+9	Altair	0.9		Aquila
054	-57	Peacock	2.1		Pavo
050	+45	Deneb	1.3		Cygnus
034	+10	Enif	2.5	Orange	Pegasus
028	-47	Al Na'ir	2.2		Grus
016	-30	Fomalhaut	1.3		Piscis Austrin.
014	+15	Markab	2.6		Great Square

If one waits until the Little Dipper is in this orientation, then the 41' that Polaris is off from the celestial pole won't matter and then the observed altitude will equal the latitude. Kochab is just slightly lower than Polaris.



THE CELESTAIRE STAR CHART


POLARIS
THE LITTLE DIPPER
KOCHAB
THE BIG DIPPER
DUBHE
ALIOTH
ALKAID
ARCTURUS
DENEBOLA
REGULUS
LEO
SPICA
GIENAH
CORVUS
MENKENT
RIGIL KENTAURUS
HADAR
GACRUX
CRUX
ACRUX
ALPHARD
SUHAIL
MIAPLACIDUS
AVIOR
PROCYON
POLLUX
BETELGEUSE
ORION
SIRIUS
ADHARA
CANOPUS
CAPELLA
ELNATH
BELLATRIX
ALNILAM
RIGEL
ALDEBARAN
PLEIADES
MENKAR
HAMAL
MIRFAK
ANDROMEDA
CASSIOPEIA
SCHEDAR
CAPH
ALPHERATZ
THE GREAT SQUARE
MARKAB
ENIF
EQUINOCTIAL
DIPHDA
ACAMAR
ACHERNAR
ANKAA
PHOENIX
FOMALHAUT
GRUS
AL NA'IR
PEACOCK
DENEB
CYGNUS
JOB'S COFFIN
ALTAIR
VEGA
DRACO
ELTANIN
CORONA BOREALIS
ALPHECCA
RASALHAGUE
NUNKI
SAGITTARIUS
KAUS AUSTRALIS
SABIK
SHAULA
SCORPIUS
ANTARES
ZUBENELGENUBI
ATRIA
TRIANGULUM AUSTRALE
N
S
E
W
♈

THE NAVIGATIONAL STARS

Courtesy of Celestaire Inc.


Capella
Auriga
7 Sisters
Elnath
Tarus
Aldebaran
Pollux
Gemini
Bellatrix
Betelgeuse
Orion
Alniliam
Canis Minor
Rigel
Procyon
Sirius


Little Dipper
Kochab
Alkaid
Polaris
Alioth
Big Dipper
Dubhe


towards Polaris
Markab
Cassiopeia
"The Great Square"
Pegasus
Schedar
Alpheratz


Deneb
Cygnus
Delphinus
Draco
Eltanin
Lyra
Vega
Altair
Aquila

The "summer triangle"


Antares
Scorpius
Nunki
Sagittarius
Shaula
Kaus Australis


Regulus
Leo
Denebola
Big Dipper
"Arc to Arcturus"
Arcturus
Bootes

Chapter 11 *Special Topics*

Determining Longitude and Latitude Individually

Some simplified methods can be used at specific times of the day to calculate latitude and longitude individually, then combining them with running fix techniques. A scenario like this presents itself: take the height of Polaris at dawn twilight for a latitude fix, then with the timing of sunrise or just after with the *prime vertical sight* determine longitude. Use the running fix technique to 'drag' along the latitude LOP to time coincide with the longitude LOP.

These techniques are probably not used so much anymore, since with tabular methods and calculators the complexity of the navigational triangle is not so daunting. In other words, the only limitations now are ones of visibility of the heavenly object, not mathematical.

Latitude Determination, a purely East-West LOP

By meridian transit

This has already been covered in the discussion of the noon sighting for the sun. One could do it for any heavenly body, but the sun is the favorite.

By the height of Polaris

Since Polaris is not exactly on the celestial north pole, corrections for this slight offset and annual aberration must be accounted for. The nautical almanac has tables where:
Latitude = Ho -1° + ao + a1 + a2, where $Ho = Hs + IC + Corr^{DIP} + Corr^{ALT}$
ao is a function of local hour angle LHA
a1 is a function of estimated latitude
a2 is a function of what month it is

By the length of time of day

If you measure the time of day from sunup to sunset in hours, minutes, and seconds, you can calculate your latitude. Start the timing and end the timing when the sun's lower limb is about ½ diameter above the horizon. Convert the time into decimal hours, and name it ElapsedTime.

Lat = arcTan[-cos(7.5 · ElapsedTime) / tan(DEC)]

You may be off by 10 arcminutes latitude depending on your timing technique.

Longitude Determination, a purely North-South LOP

By the timing of sunrise or sunset

The equations simplify when the true altitude Ho is zero. But due to dip, refraction, semi-diameter and index error, the sextant altitude needs to be preset at a low but specific angle to catch the sun at true horizon sunrise or sunset.

If:

$Ho = Hs + IC + Corr^{DIP} + Corr^{ALT}$ then $Hs = Ho - IC - Corr^{DIP} - Corr^{ALT}$

So, for Ho = 0:

$Hs = - IC - Corr^{DIP} - Corr^{ALT}$

It should be apparent that:

$Ha = - Corr^{ALT} = -R - SD_{LL}$ or $= -R + SD_{UL}$

Since the average sun semi-diameter is 16’, we can figure the refraction correction for when Ho = 0. Refraction correction is a function of Ha, so we need to do a little iteration. Fortunately I’ve done it for you, so here are the results:

Using the sun’s lower limb (LL), the $Corr^{ALT} = - 15.5'$ LL

Using the sun upper limb (UL), the $Corr^{ALT} = - 43'$ UL

In short, set the sextant to:

$Hs = - IC - Corr^{DIP} + 15.5'$ (LL) or $Hs = - IC - Corr^{DIP} + 43.0'$ (UL)

The dip correction is always negative, but in this equation the double negative will make this number a positive. Same with the altitude corrections in this case. With the sextant preset to this angle, when the sun’s limb kisses the horizon, observe the time UTC. In the almanac, look up the GHA and declination, adding the increments for the minutes and seconds. Longitude is then:

$Lon = \{(+ / -) \arccos[-Tan(Lat) \cdot Tan(DEC)]\} - GHA$,

(+ / -) negative if sunrise or positive if sunset

Example:

$IC = -2.1'$, $h = 2$ meters, so $Corr^{DIP} = - 0.5'$. Latitude = 41.75°

With the sun’s LL $Corr^{ALT} = - 15.5'$

So, preset the sextant angle to $Hs = -(-2.1') - (-0.5') - (- 15.5') = + 0° 18.1'$

When the sun is at this altitude, the time was 11h 30m 10s. From the almanac let’s say that GHA =345.390°, and DEC = 10.235° N

So: $Lon = - \arccos[-Tan(41.75°) \cdot Tan(10.235°)] - 345.39° = - 444.664°$

Add 360 to it, $Lon = 360° - 444.664° = - 84.664°$ West Longitude

By the prime vertical sight

If you will recall the illustration on page 21, the prime vertical circle goes from due east to the zenith to due west. In the summer months, the sun will rise a bit to the north of east (northern hemisphere) and it may be some time after sunrise that the sun crosses this imaginary line. When it does, the azimuth is exactly 90°. This simplifies the equations such that:

$$\mathbf{Ho = \arcsin[Sin(DEC) / Sin(Lat)]}$$

Work out the sextant angle by:

$$\mathbf{Hs = Ho - IC - Corr^{DIP} - Corr^{ALT}}$$

Determine the UTC time when this condition occurs by waiting for the object to attain Hs, then look up in the almanac GHA for the sun. Then:

$$\mathbf{Lon = (+ / -) \arcsin[Cos(Ho) / Cos(DEC)] - GHA}$$

(+ / -) negative if sunrise or positive if sunset

Example:
$IC = -2.1'$, $h = 2$ meters, so $Corr^{DIP} = -0.5'$. Latitude = 41.75°
If $Ha \sim 15^\circ$ then $Corr^{ALT} = +12.5'$
For the approximated time, from the almanac $DEC = 10.260^\circ$ N
$Ho = \arcsin[Sin(10.260^\circ) / Sin(41.75^\circ)] = 15.515^\circ$
When the sun is at this altitude, the time was 12h 54m 3s. From the almanac let's say that $GHA = 6.365^\circ$, and $DEC = 10.260^\circ$ N
$Lon = -\arcsin[Cos(15.515^\circ) / Cos(10.260^\circ)] - 6.365^\circ = -84.664^\circ$ West

By the time sight

This uses the Sumner line equation, used only once by imputing your best estimate for latitude. Be careful of the (+/-) sign, determine if the object is pre or post meridian. Easily done with the sextant, if the object continues to rise, it is pre meridian. The closer to meridian transit the less accurate the answer since at meridian transit the LOP is East-West, not North-South. In these circumstances, a little error in latitude will translate into a large longitude error from the calculation.

East side of the circle when the object is westwards (post meridian):

$$\mathbf{Lon = \arccos[\{ Sin(Ho) - Sin(DEC) \cdot Sin(Lat)\}/\{Cos(Lat) \cdot Cos(DEC)\}] - GHA}$$

West side of the circle when the object is eastwards (pre meridian):

$$\mathbf{Lon = -\arccos[\{ Sin(Ho) - Sin(DEC) \cdot Sin(Lat)\}/\{Cos(Lat) \cdot Cos(DEC)\}] - GHA}$$

Chapter 12 *Lunars*

These days, with quartz watches and radio time-ticks, lunars are for the hard-core celestial zealot. This is a method whereby you can reset your untrustworthy chronometer if you are in the middle of the ocean (or anywhere) without friends or a short-wave radio. Or perhaps you just want to feel challenged.

Essentially the arc-distance between the moon's limb and a heavenly object close to the ecliptic plane (such as a planet) is measured. Since the arc distance is changing with time relatively fast (~0.508 deg per hour), one can infer a particular time in UT to a particular arc distance. The nautical almanac contains predictions for both objects, and so the arc distance between the two objects can be worked out as a function of time. The almanac many years ago contained these functions, but stopped in 1907. It must be done by calculation or by special lunar tables.

Since the moon appears to orbit about the Earth once every 29 ½ days (27 1/3 days in inertial space), the angular closing speed between the moon and a planet or star near the ecliptic plane, from our earthly point of view, is about 0.5 arcminute per minute of time. Practically speaking, between messy observations and even messier calculations, this means you won't get any closer to the real time by a minute or so. Still, that's not bad, it just means you'll have to make allowances in your longitude estimate to the tune of 15 · Cos(Lat) n.miles per minute of time error. But you won't know the error, so you'll just have to assume something like 2 minutes of time.

The tabular data in the almanac does not consider refraction or parallax, and so the observer will have to correct for it. In order to do that, the observer must nearly simultaneously obtain the altitudes of both the moon and star (or planet) as well as the actual measured arc distance between the two. Whew! It helps to have two friends in the same boat with sextants. It is possible that the errors will be small if you take three consecutive measurements within a few minutes, since the altitude measurements are for refraction and parallax *corrections*, which won't change fast. By small, I mean the time estimate may be off by several minutes per degree of altitude change. A degree of altitude change at it's worst will take 4 minutes (at the equator). But if the measurements are taken with the objects near the meridian line, you may have quite a bit of time to make measurements sequentially. In fact, one can measure sequentially and correct the altitude measurements to time coincide with the arc distance measurement, a sort of 'running fix' correction on altitude.

If the time difference between the arc measurement and altitude measurement is δT minutes of time, then add this increment to the altitude measurement:

$$\delta H = 15 \cdot [-\mathrm{Cos}(LAT) \cdot \mathrm{Cos}(DEC) \cdot \mathrm{Sin}(LHA)/\mathrm{Cos}(Ho)] \cdot \delta T \text{ arcminutes}$$

where $\delta T = T_{arc} - T_{altitude}$ in minutes of time. **Tarc** refers to the time you took the arc distance measurement, and **Taltitude** is the time you took the altitude measurement. The absolute time is not important; rather the time difference is what should be accurate. Since there are 2 altitude measurements, there will be a **δH**star, and **δH**moon increment based on time increments **δT**star, **δT**moon.
LAT is your latitude, DEC is the declination of the observed object, LHA is your best guess at the local hour angle for the object, and Ho is the observed altitude for the object (Hs + SD is close enough). This way, the parallax and refraction corrections will be identical had you done simultaneous measurements.
When the measured arc distance **Ds** is corrected for index error, refraction, and semi-diameter, it is referred to the apparent arc distance **Da**. When final corrections are made for parallax, the resulting number is the arc distance as seen from an observer at the Earth's center. That final arc distance is designated as $\mathbf{D}_{\mathbf{cleared}}$ and the entire procedure is known as **clearing the lunar distance**. The equation for $\mathbf{D}_{\mathbf{cleared}}$ presented here was first published in 1856 by J.R. Young, although I derived the exact same equation independently when approaching the problem.

The case presented is for when you don't know the exact time and you have made the three necessary measurements as though you were doing it for real. Besides, it's fun. Well, sort of. This entire task is simplified if you have a computer and use MathCad software to write and evaluate the equations. By the way, good luck. Oh, as far as sequencing the observations to minimize errors if you don't feel like making the 'running fix' corrections, do this:

1) measure the arc distance first
2) measure the altitude of the most east/west next, quickly
3) measure the altitude of the southern/northern most object last

The objects farthest away from meridian passage change altitude the quickest and should be measured soonest after the arc distance measurement.

There is a second method using one measurement and an assumed position. Here the method assumes that the latitude assumed is very accurate, but the longitude is as far off as the chronometer. Employed best by computer.

LUNARS, ILLUSTRATION OF ANGLES


Celestial Sphere
D_S
Far Limb
Lower Limb
Hs_{star}
Hs_{moon}
TRUE HORIZON
D_S
Far Limb
STAR SHOULD BE
CLOSE TO THIS LINE
Near Limb
D_S

-------------------------------- Clearing the distance from a lunar observation --------------------------------------

Change all angle data into decimal degrees

IC **Index Error Correction, degrees**

h_{eye} **Eye Height above seal level, meters**

Hs_{star} **Measured Altitude of star or planet with Sextant Scale, deg**

Hs_{moon} **Measured Altitude of the Moon with Sextant Scale, deg**

Ds **Measured arc distance from Lunar limb to star or planet center with Sextant Scale, deg**

UT_s **Your imperfect clock time noted at the observation of Ds, convert to decimal hours**

sgn_{limbH} **When measuring altitude, lower limb is +1. upper limb is -1**

sgn_{limbD} **When measuring arc distance, near limb is +1. far limb is -1**

HP **Horizontal Parallax HP, from the nautical almanac, degrees**

$SD_{moon} = 0.2724 \cdot HP$ **Lunar semi-diameter, degrees**



Dip Correction

Heye	DipC
0.7m	-1.5'
1.3m	-2'
2.0m	-2.5'
2.9m	-3'
3.9m	-3.5'
5.1m	-4'
6.4m	-4.5'
8.1m	-5.0'
9.8m	-5.5'
11.6m	-6.0'



Refraction correction

Ha	R
10 deg	-5'
13 deg	-4'
15 deg	-3.5'
17 deg	-3'
20 deg	-2.5'
24 deg	-2'
31 deg	-1.5'
41deg	-1'
59 deg	-0.5'
85 deg	0

From this table, determine the refraction correction for the star and the moon

Record values for:

R_{star}

R_{moon}

Convert the dip and refraction corrections to decimal degrees !!

$$Ha_{star} = Hs_{star} + IC + DipC$$

Apparent Altitude of star or planet corrected for dip and sextant errors

$$Ho_{star} = Ha_{star} + R_{star}$$

True observed altitude of star corrected for refraction

Apparent Altitude of moon corrected for dip, semidiameter and sextant errors

$$Ha_{moon} = Hs_{moon} + IC + DipC + sgn_{limbH} \cdot SD_{moon} \cdot \left(1 + \frac{\sin(Ha_{moon})}{60.5}\right)$$

$$PA = HP \cdot \cos(Ha_{moon}) \cdot \left(1 - \frac{\sin(Lat)^2}{300}\right)$$

Parallax in altitude, degrees

$$Ho_{moon} = Ha_{moon} + R_{moon} + PA$$

True observed altitude of moon correcte for refraction and parallax

----

Apparent distance from observer point of view before refraction corrections to the arc measurement, degrees

$$Da = Ds + IC + sgn_{limbH} \cdot SD_{moon} \cdot \left(1 + \frac{\sin(Ha_{moon})}{60.5}\right)$$

$$C_{ratio} = \left[\frac{(\mathrm{Cos}(Ho_{star}) \cdot \mathrm{Cos}(Ho_{moon}))}{(\mathrm{Cos}(Ha_{star}) \cdot \mathrm{Cos}(Ha_{moon}))}\right]$$

Ratio of cosine values

Arc distance from the Earth's center point of view, no more corrections, degrees

$$D_{cleared} = \mathrm{arcCos}\left[(\cos(Da) + \cos(Ha_{moon} + Ha_{star})) \cdot C_{ratio} - \cos(Ho_{moon} + Ho_{star})\right]$$



Next we get tabular values for GHA and declination for the moon and the star in the UT hour we think we are in. We will designate that hour as "UT1".

$GHA1_{moon}$ $DEC1_{moon}$ $GHA1_{star}$ $DEC1_{star}$

Calculate the arc distance at UT1, no parallax, or refraction (geocentric)

$$D_1 = \mathrm{arcCos}\left(\mathrm{Cos}\left(GHA1_{moon} - GHA1_{star}\right)\cdot\mathrm{Cos}\left(DEC1_{moon}\right)\cdot\mathrm{Cos}\left(DEC1_{star}\right) + \mathrm{Sin}\left(DEC1_{moon}\right)\cdot\mathrm{Sin}\left(DEC1_{star}\right)\right)$$

Next we get tabular values for GHA and declination for the moon and the star at the next UT hour from UT1. We will designate that hour as "UT2". (UT2 = UT1 + 1.0)

$GHA2_{moon}$ $DEC2_{moon}$ $GHA2_{star}$ $DEC2_{star}$

Calculate the arc distance at UT2, no parallax, or refraction (geocentric)

$$D_2 = \mathrm{arcCos}\left(\mathrm{Cos}\left(GHA2_{moon} - GHA2_{star}\right)\cdot\mathrm{Cos}\left(DEC2_{moon}\right)\cdot\mathrm{Cos}\left(DEC2_{star}\right) + \mathrm{Sin}\left(DEC2_{moon}\right)\cdot\mathrm{Sin}\left(DEC2_{star}\right)\right)$$

The fraction of time in decimal hours before (-) or ahead (+) of UT1 hour is :

$$ATIME = \frac{\left(D_{cleared} - D_1\right)}{D_2 - D_1}$$

Decimal hours, this value can be positive or negative

$$UT_{observation} = UT1 + ATIME$$

Best estimate of the time of observation when the arcdistance Ds was measured, decimal hours

$$TIME_{error} = UT_s - UT_{observation}$$

Clock error, decimal hours.
Positive means clock is fast, negative clock is slow

NO ITERATION REQUIRED

Convert the decimal hour to minutes by multiplying by 60
For example, TIMEerror = - 0.14765 is:
60 x - 0.14765 = 8.859 minutes slow = 8 minutes 52 seconds slow

The 2nd method with one measurement (the arc distance) will calculate the altitudes based on the assumed position and imperfect chronometer reading. With the new corrected time, you can also correct the assumed longitude, and iterate once or twice more with the better time and longitude results. The basic assumption is that the latitude is more accurate.

Derivation of the equations used in clearing the lunar distance

Law of Sines: $\sin(a)/\sin(A) = \sin(b)/\sin(B) = \sin(c)/\sin(C)$

Law of Cosines: $\cos(a) = \cos(b) \cdot \cos(c) + \sin(b) \cdot \sin(c) \cdot \cos(A)$

(these laws are for spherical trigonometry; there are similar ones for plane trig)

Useful identities:
$\sin(\alpha) = \cos(90^\circ - \alpha)$
$\cos(\alpha) = \sin(90^\circ - \alpha)$

Law of Cosines in terms of co-angles:
$\sin(90-a) = \sin(90-b) \cdot \sin(90-c) + \cos(90-b) \cdot \cos(90-c) \cdot \cos(A)$


Local Celestial Sphere
R_s
D
d
R_m
PA
$SD_{augmented}$
SD
S
s
m
M
δ
Local Horizon Plane

$S = s + R_S$
$M = m + R_m + PA$
$d = d_{sextant} + IC + SD_{aug}$

s = Ha_{star} S = Ho_{star} m = Ha_{moon} M = Ho_{moon}

$$\cos(d) = \sin(s)\cdot\sin(m) + \cos(s)\cdot\cos(m)\cdot\cos(\delta)$$
$$\cos(D) = \sin(S)\cdot\sin(M) + \cos(S)\cdot\cos(M)\cdot\cos(\delta)$$

Rearrange cos(*d*): $\cos(\delta) = \dfrac{\cos(d) - \sin(s)\cdot\sin(m)}{\cos(s)\cdot\cos(m)}$

Now substitute into cos(*D*):

$$\cos(D) = \sin(S)\cdot\sin(M) + \cos(S)\cdot\cos(M)\cdot\left[\frac{\cos(d) - \sin(s)\cdot\sin(m)}{\cos(s)\cdot\cos(m)}\right]$$

Rearrange:

$$\cos(D) = \sin(S)\cdot\sin(M) + \left(\cos(d) - \sin(s)\cdot\sin(m)\right)\cdot\left[\frac{\cos(S)\cdot\cos(M)}{\cos(s)\cdot\cos(m)}\right]$$

But using the trig identity:

$$\sin(a)\cdot\sin(b) = -\cos(a+b)$$

And substituting this definition:

$$C_{ratio} = \left[\frac{\cos(S)\cdot\cos(M)}{\cos(s)\cdot\cos(m)}\right]$$

$$\cos(D) = \left(\cos(d) + \cos(s+m)\right)\cdot C_{ratio} - \cos(S+M)$$

$$D = arcCos\left[\left(\cos(d) + \cos(s+m)\right)\cdot C_{ratio} - \cos(S+M)\right]$$

The key to the problem is to realize that the parallax and refraction corrections only change the altitudes, not the ‘wedge angle’ δ. When the corrections are applied, and using the law of cosines, the equation with s, m can be related to S, M with the common angle δ. Even though refraction corrections are negative, the picture is drawn in the positive direction to establish a consistent sign convention.

Chapter 13 *Coastal Navigation Using the Sextant*

Early in this book a surveyor's technique was mentioned, and it is useful in costal navigation where the relative angle between the observer and 3 identified costal objects are measured. This is the *3 body fix* technique, and will be described in detail.

A wonderful property of a simple circular arc with 2 end points is that a line drawn from one end point to anywhere on the arc back to the other end point, is the same angle as any other line similarly drawn to another point on the arc.



If you are an observer measuring the relative angle between two known objects on the map, there will exist one unique circle of position where anyone on that arc will measure the same angle between the two known coastal objects. Include another observation for a third coastal object and make a second angle measurement. Take for example points A and B on the map (maybe they are water towers or prominent points). An observer measures the relative angle 'a' between them using the sextant held sideways. Then the observer measures an angle 'b' between points B and C (or A and C). The navigator then constructs the two arcs on the map, and where they cross is the position fix. For any arc, if D is the distance between A and B, then the circle's radius R:

$$R = 0.25 \cdot D \cdot [\tan(a/2) + 1 / \tan(a/2)]$$





Constructing the arcs by graphical means


Step 1 Draw baseline from point A to point B
B
A
Step 2 Draw perpendicular bisector between points A and B

The first step is to draw the baseline between points A and B. Recalling how to draw perpendicular bisectors from middle school geometry using a bow compass, do so for the baseline.

After the bisector is constructed, use a protractor and measure an angle away from the baseline of (90-a/2) from point 'A', if the measured angle with the sextant was 'a' degrees. Where it intersects the bisector, call this point 'X'.


B
A
90 - $\frac{a}{2}$
X
Step 3 With protractor, draw line to bisector with angle 90 - $\frac{a}{2}$ from baseline


Step 4 Draw perpendicular bisector between points A and X.
Carry it to the 1st bisector
B
Y
A
X

Then draw another perpendicular to split the line A-X, carrying this line until it intersects the first bisector. Call this point 'Y'. It represents the center point of the circle of position.


Step 5 Draw arc with Y as the center, including points A,X and B
B
Y
A
X

Finally, using point Y as the center, use the bow compass to draw an arc by setting the radius to include either points A, B, or X. This is the circle of position. Repeat steps for drawing the circle of position for points B and C with included angle 'b'. Voila!

Appendix 1 *Generalized Sight Reduction and Intercept Work Sheet*

CELESTIAL NAVIGATION SIGHT REDUCTION EQUATIONS

OBSERVED DATA

True Course **C**		degrees
Speed **V**		knots
Eye Height $\mathbf{H}_{eye}$		meters
Temperture >>		deg C
Pressure >>		mbars

Last fix Latitude >>	$\mathbf{Lat}_o$		dec.deg.	
Last fix Longitude >>	$\mathbf{Lon}_o$		dec.deg.	
UT of Last Fix >>	$\mathbf{Time}_o$		dec. hours	if yesterday, subtract 24
UT Time of this Fix >>	$\mathbf{Time}_{fix}$		dec. hours	

$\mathbf{sign}_{limb}$ >>		Which limb, upper or lower	lower limb = +1 upper limb, = -1
UT (**H:M:S**) >>		Universal Time of observation	

Time = Hour + (Minute + Second / 60) / 60 Observation time converted to decimal, from hour, minute, second

Hs >>		Measured sextant altitude
I + IC >>		Index and instrument correction
PC >>		Personal correction

$\mathbf{Corr^{DIP} = -0.0293 \times SquareRoot(H_{eye})}$ Dip correction, decimal degrees

$\mathbf{Ha = Hs + (IC + I + PC) + Corr^{DIP}}$ Apparent altitude

SD >>		Semi-diameter	$\mathbf{SD_{moon} = 0.2724 \times HP_{moon}}$ Calculated lunar semi-diameter
HP >>		Horizontal parallax	

$$\mathbf{R} = \frac{-0.0167}{\tan\left(\mathbf{Ha} + \frac{7.31}{\mathbf{Ha}+4.4}\right)} \times \left[0.28 \times \frac{\mathbf{Pressure}}{(\mathbf{Temperature}+273)}\right]$$

Refraction correction, decimal degrees

PA = HP x Cos(Ha) Parallax-in-Altitude

$\mathbf{Corr^{ALT} = R + SD \times sign_{limb} + PA}$ Total altitude corrections, or just get directly from the almanac and convert to dec.deg.

$\mathbf{Ho = Ha + Corr^{ALT}}$ Observed altitude, all corrections accounted for

ESTIMATED POSITION

$\mathbf{\Delta Time = (Time_{fix} - Time_o)}$ Time interval from last fix to present fix

$\mathbf{D = V \times \Delta Time}$ Distance traveled from last fix to present fix

$\mathbf{\Delta Lat = (D/60) \times Cos(C)}$ Change of latitude from last fix, decimal degrees

$\mathbf{\Delta Lon = (D/60) \times Sin(C) / Cos(Lat_o + \Delta Lat/2)}$ Change of longitude from last fix, decimal degrees

$\mathbf{DR\ Latitude = (Lat_o + \Delta Lat)}$ Estimated latitude at time of fix, decimal degrees

$\mathbf{DR\ Longitude = (Lon_o + \Delta Lon)}$ Estimated longitude at time of fix, decimal degrees

$\mathbf{Roffset = V \times (Time_{fix} - Time)}$ Offset distance for a running fix correction, n.m.

NAUTICAL ALMANAC DATA, GHA and Declination

Determine GHA at the specific Universal Time

GHA$_{HR}$ >>					GHA at the hour, decimal degrees
variance ***v*** >>					arc-minutes/hr
GHA **rate** >>					<<<<<<<<<<<<<<<<<<<
SHA >>					if sun or planets, leave blank

GHA nominal hourly rates

Sun, planets	Aries	Moon
15.0000	15.0411	14.3167

Δt = Time - Integer(Time) Hour fraction, mantissa of decimal observation time: **M/60 + S/3600**

Corr^{GHA} **= rate x Δt** GHA increment due to minutes and seconds

Corr^{v} **= v x Δt/60** Applicable variance correction, decimal degrees

GHA = SHA + GHA$_{HR}$ **+ Corr**^{GHA} **+ Corr**^{v} GHA at the Universal Time of observation

Determine Declination at the specific Universal Time

DEC$_{HR}$ >>					Declination at the hour, dec. deg.
rate ***d*** >>					arc-minutes/hr

N +, S -
if the rate is northwards +
if the rate is southwards -

Corr^{d} **= *d* x Δt/60** decimal degrees

DEC = DEC$_{HR}$ **+ Corr**^{d} Declination at the Universal Time of observation, degrees

Using The GHA and Declination Values, Determine Calculated Altitude Hc

Lat$_{A}$ >>		dec.deg.	Assumed Latitude
Lon$_{A}$ >>		dec.deg.	Assumed Longitude

LHA = GHA +Lon$_{A}$ Local hour angle, post meridian if 0 < LHA < 180, and pre meridian otherwise (which includes - LHA)

$$\mathbf{Hc} = \mathbf{arcSin}\left(\mathbf{Sin}(\mathbf{DEC})\cdot\mathbf{Sin}(\mathbf{Lat_A}) + \mathbf{Cos}(\mathbf{Lat_A})\cdot\mathbf{Cos}(\mathbf{DEC})\cdot\mathbf{Cos}(\mathbf{LHA})\right)$$

Calculated Altitude, decimal degrees

$$\mathbf{Zo} = \mathbf{arcCos}\left(\frac{\mathbf{Sin}(\mathbf{DEC}) - \mathbf{Sin}(\mathbf{Lat_A})\cdot\mathbf{Sin}(\mathbf{Hc})}{\mathbf{Cos}(\mathbf{Lat_A})\cdot\mathbf{Cos}(\mathbf{Hc})}\right)$$

Uncorrected azimuth angle, decimal degrees

Azimuth = Zo if LHA is pre-meridian
Azimuth = 360- Zo if LHA is post-meridian (0 < LHA < 180)

Corrected Azimuth angle from true north, decimal degrees

Doffset = 60 x (Ho - Hc) Offset distance to the intercept LOP, nm (+ move towards, - move away)

Appendix 2 *Making Your Very Own Octant*

Frames for octants can be made from just about any clear wood. In the case of the author's octant, it was made from ¾ inch thick clear maple, and epoxied to form the fine-boned frame shown here. The mirrors are indexed to their position using 3 brads, 2 along the bottom forming a horizontal line, and the third brad along the side to index side-to-side motion. Brass shim stock cut into rectangles and formed over a round pencil produced the U-shaped mirror retaining springs. One-inch long #4-40 screws and nuts are used to make a 3-point adjustable platform for mirror alignment



Farley Octant
12" radius

The arc degree scale and Vernier scale were drawn in a 2-D computer aided design program and printed out at 1:1 scale. The laser and bubble jet printers of today are amazingly accurately. The Vernier scale should not go edge to edge with the degree scale, but rather overlap it on a tapered ramp. This means that you do not need to sand the wood edge perfectly arc-shaped, so only the degree scale needs to be placed with accuracy. The Vernier scale is moved radially in and out until it lines up perfectly with the degree scale, only then is it glued to the index arm.

Mirrors

Surprisingly good mirrors can be found in craft stores, 2"x2" for about 25¢ each. Terrible mirrors can be had at the dollar store out of compacts. The quality can be surmised by tilting the mirror until you are seeing a small glancing reflection of something. Ripples (slope errors) will be quite evident at these high reflection angles. The ripples may be just in one direction, and so the mirror can be oriented on the sextant to minimize altitude distortions. The next best is to order a second surface mirror (50mm square) from an optics house such as Edmunds Scientifics for about $4. In their specialty house, you can order first surface mirrors for maybe $20. The second surface mirrors are good enough for a homemade (and professional) sextant. Removing the aluminized surface for the horizon mirror requires patience, and is best accomplished with a fixture to hold the mirror and a guide for the tool. The back has a protective coating that must be removed to get to the reflective material. For a tool, I use a very well sharpened/honed 1" wide wood chisel. The edges should be slightly rounded so as not to dig in. Under no circumstances should you use a scotch-brite pad to remove the silvering, as it will scratch glass. The silvering can best be removed with a metal polisher such as Brasso, using a soft cloth.

Shades

Shades for the sky and horizon filters can be made from welder's mask replacement filter plates, available at welding supply houses for about $1.65. They cut out 99.9% of harmful UV and infrared heat as well as act as neutral density filters to reduce the over-all amount of visible light. The welding shades are numbered 1 thru 16, 1 being the lightest and 16 the darkest. Shades can be additive, that is a #5 shade plus a #6 shade is equivalent to a #11 shade. A #4 shade allows about 13% visible transmission, while a #5 allows around 5%. Shades equivalent to a commercial sextant (by unscientific methods) is approximately 14, 10, 4 for the sky filters and 8, 4 for the horizon filters. Most of these welder's shades will turn the Sun green. Replacement shade filter plates typically can be found for 4 thru 14. Use a 5, a 10, and a 14, which would seem to cover all viewing situations without having to double-up on filters (the glass is not perfect, and more than one filter will distort the Sun's image slightly). A 4 and 6 for the horizon will give 4, 6, and 10. The problem of contrast arises, a green sun disk on a green horizon. But safety of your eyes is paramount, no sense of increasing chances of cataracts due to ultraviolet overexposure. Buy the plates in a 2 by 4.25 inch size, and cut them in half to make 2 squares. Now glass cutting these thick plates is no laughing matter. I have found that if you score lines with a handheld glass cutter on the front and back (and edges too) so that the lines are right over each other, you stand a much better chance of a successful cut. This will require practice…

Springs

Torsion springs to hold the mirrors in place can be easily made by wrapping thin (0.015”) music wire around larger diameter music wire or brad nails. Leaf type springs can be cut out from 0.010” brass sheet stock or tin can lids, and wrapped around a pencil to get a ‘U’ shape.

Sighting telescope

A simple Galilean telescope can be made with a convex lens for the objective lens, and a concave lens for the eyepiece. The image will be upright, and the magnification need not be greater than 3. The convex lens has a positive focal length (FL1), while the concave lens has a negative focal length (FL2). The spacing ‘S’ between the lenses should be FL1+FL2, and the magnification ‘M’ is -FL1/FL2. For example, if the objective lens has a focal length of 300mm and the eyepiece lens has a focal length of -150mm, then:

Spacing S = FL1 + FL2 = 300 + (-150) = 150mm

Magnification M = - (FL1/FL2) = -(300 / (-150)) = 2

Edmunds Scientifics sells 38mm diameter lenses for about $3 to $4 each. The tubes can be made with a square cross section using basswood or thin hobby plywood.



BOX TELESCOPE

Paint the insides of the tube flat black. The baffles are used to keep stray light from glaring up the insides of the tube, which then reflect into the eyepiece. These baffles effectively trap the unwanted light. Generally speaking, the more baffles, the better the image contrast.

Photos of the Octant

Making of the telescope

Horizon mirror and mount




0
10
20
30
40
50
80
90

The completed Octant

Appendix 3 *On-Line Resources for Celestial Navigation*

Star Path navigational school
http://www.starpath.com/resources/cellinks.htm

Celestaire
http://celestaire.com/catalog/

On-line nautical almanac
http://www.tecepe.com.br/scripts/AlmanacPagesISAPI.isa

US Naval Observatory
http://aa.usno.navy.mil/data/docs/celnavtable.html

Celestial navigation net- good all around source
http://www.celestialnavigation.net/index.html

A short guide to celestial navigation and freeware
http://home.t-online.de/home/h.umland/index.htm

Official UTC time
http://nist.time.gov/timezone.cgi?UTC/s/0/java

International Earth Rotation Service, gives delta T for Ephemeris Time
http://maia.usno.navy.mil/

Edmunds Scientifics, supplier of mirrors and lenses
http://www.scientificsonline.com/

Edmund Optics, higher grade of optics
http://www.edmundoptics.com/catalog/

American Science and Surplus, with all sorts of spare optical stuff
http://www.sciplus.com/

My web site: http://mysite.verizon.net/milkyway99/index.html

Appendix 4

Celestial Navigation via the S-Tables and Ageton's Method

By Teacup Navigation

Rodger E. Farley

Contents

Introduction

Determining Local Hour Angle

Corrections to Altitude

Individual Steps

Work Sheets

Tables

Appendix: The Intercept

1st Edition

Copyright 2010 Rodger E. Farley
My web site: http://mysite.verizon.net/milkyway99/index.html

All rights reserved.
I assume no liabilities of any form from any party: Warning, user beware!
This is for educational purposes only.

Introduction

Ageton devised a method of dividing the navigational triangle into 2 simpler right-angle triangles to solve. Using the Ageton equations for calculated altitude and meridian angle, a step by step solution to the problem can be implemented using tables and simple addition/subtraction. Ageton reformulated his equations with secant and co-secant functions, but I have retained the original with sine, cosine. The tables represent the log (base 10) of sine and cosine of angles, then multiplied by -100 for ease.

These are the basic Ageton equations:

$$R := \operatorname{asin}(\sin(LHA)\cdot\cos(DEC))$$

$$K := \operatorname{asin}\left(\frac{\sin(DEC)}{\cos(R)}\right)$$

$$H_c := \operatorname{asin}(\cos(R)\cdot\cos(K - Lat))$$

$$Z_o := \operatorname{asin}\left(\frac{\sin(R)}{\cos(H_c)}\right) \quad \text{Meridian angle}$$

if $|K| > |Lat|$, then $K_{type} = 1$, else it equals 0

if $\operatorname{sign}(Lat) \times \operatorname{sign}(DEC) \times K_{type} = 1$, then Zo is correct, else the corrected Zo equals 180-Zo

Corrected meridian angle then needs to be converted to true azimuth angle, Zn.



Determining Local Hour Angle LHA

North Lat is +, South Lat is - East Lon is +, West Lon is -

The Nautical Almanac hourly tabular values of Greenwich Hour Angle ($\mathbf{GHA_{hour}}$)is corrected for minutes and seconds increments ($\mathbf{Corr}^{\mathbf{GHA}}$) plus any hourly variances ***v*** ($\mathbf{Corr}^{V}$ for the minutes). For stars **GHA = SHA +** $\mathbf{GHA}^{\mathbf{Aries}}$

Hourly values of declination ($\mathbf{DEC_{hour}}$) are corrected for minutes with hourly rate **d** ($\mathbf{Corr}^{d}$ for the minutes). Beware of using the correct sign [+/-] in rate **d**. If the declinations are moving in a northerly direction, then the sign of **d** is positive (+) even if the declination is still southern. If **d** is moving in a southerly direction (DEC becoming more southerly in the next hour) then d is negative (-), even if the declination is still northern.

$$\mathbf{GHA = GHA_{hour} + Corr^{GHA} + Corr^{V}}$$
$$\mathbf{DEC = DEC_{hour} + Corr^{d}}$$

If **DEC** is N then it is +, if S, then **DEC** is -

Using the correct sign (+/-) for longitude **LON**:

LHA = GHA + LON

If LHA > 360, then subtract 360.

LHA is divided into two camps: post-meridian passage and pre-meridian passage. Post meridian angles range from zero to 180 degrees (0<LHA<180), and pre meridian angles range from 180 to 360 (180<LHA<360). For a compute program, pre-meridian LHAs need to be converted to a negative angle (-180<LHA<0) by subtracting 360 from a pre-meridian angle(for example 276 is equivalent to - 84) . The tables and rules can handle both forms if you are careful!



Corrections to Altitude

Apparent Altitude:
$Ha = Hs + IC + Corr^{DIP}$
Note: index correction **IC** is + when off the arc, and – when on the arc.

Corrected Observed Altitude
$Ho = Ha + Corr^{ALT}$



Tables of Altitude Correction, averaged values, summer/winter

Altitude correction for sun and stars $Corr^{ALT}$

Ha, deg	**Sun LL**	**Sun UL**	**Stars**
10	+11'	-21'	-5'
13	+12'	-20'	-4'
15	+12.5'	-19.5'	-3.5'
17	+13'	-19'	-3'
20	+13.5'	-18.5'	-2.5'
24	+14'	-18'	-2'
31	+14.5'	-17.5'	-1.5'
41	+15'	-17'	-1'
59	+15.5'	-16.5'	-0.5'
85	+16'	-16'	0

Dip Correction

Height	**$Corr^{DIP}$**
0.7m	-1.5'
1.3m	-2'
2.0m	-2.5'
2.9m	-3'
3.9m	-3.5'
5.1m	-4'
6.4m	-4.5'

$Ha = Hs + IC + Corr^{DIP}$

$Ho = Ha + Corr^{ALT}$

For the moon, use the almanac which will include SD, R, and PA

Individual Steps

In the following algorithm, the arrows with "tables" mean go to the S-tables and look at the numbers in the columns. In each column there are 2 numbers side-by-side. If the number sought is an S number, then the one in the same column next to it is a C number. If you have an arrow with "tables/angle", it means locate the given S number, and note the corresponding angle. There are 4 choices of angle, but you will select from the 2 bold numbers, and the given rules will make it clear which of the two to use. Also note that calculated altitude Hc is always less than 90 deg.

1) With |LHA| in tables → S1
2) With |DEC| in tables → S2, C2
3) S3 = S1 + C2, in tables find corresponding C3
4) S4 = S2 - C3, in tables corresponding angle = K
   K > 90 if LHA between 90 and 270
5) K' = |K - LAT x sign(DEC) |, in tables → C5
6) S6 = C5 + C3, in tables → C6
7) Also, in tables corresponding angle of S6 = Hc
8) S7 = |S3 – C6|, in tables corresponding angle = Zo
   Choose the bold-faced angle greater than 90, unless LAT and DEC same name AND |K| > |LAT|, in which case choose the angle less than 90.

Notes:
A variable in straight brackets, for example |LHA|, means to take the absolute value of LHA. In that if it is negative, then make it positive. If LHA = -12, then |LHA| = 12. A greater-than sign is > and a less-than sign is < (K>90 means K greater than 90). When there is a variable prefixed with sign(variable), it means determine the sign and assign it a +1 value if it's positive, or a -1 value if the sign of the number is negative.

Converting Corrected Meridian angle Zo to true azimuth Zn
Name of LAT to select **N** or **S** prefix. For **E** or **W** suffix:
If LHA pre-meridian (-180<LHA<0 or 180<LHA<360) then **E**
If LHA post-meridian (0<LHA<180) then **W**

NW: Zn = 360 - Zo	**NE**: Zn = Zo
SE: Zn = 180 - Zo	**SW**: Zn = Zo + 180



Log Entry ____ UTC Date ____ Body and Limb ____

Approx Azimuth ____

DR Lat ____ N / S DR Lon ____ W / E

Eye height ____ meters

Tables of Altitude Correction, averaged values, summer/winter

Altitude correction for sun and stars — Corr^{ALT}

Ha, deg	Sun LL	Sun UL	Stars
10	+11'	-21'	-5'
13	+12'	-20'	-4'
15	+12.5'	-19.5'	-3.5'
17	+13'	-19'	-3'
20	+13.5'	-18.5'	-2.5'
24	+14'	-18'	-2'
31	+14.5'	-17.5'	-1.5'
41	+15'	-17'	-1'
59	+15.5'	-16.5'	-0.5'
85	+16'	-16'	0

Dip Correction

Height	Corr^{DIP}
0.7m	-1.5'
1.3m	-2'
2.0m	-2.5'
2.9m	-3'
3.9m	-3.5'
5.1m	-4'
6.4m	-4.5'

$$Ha = Hs + IC + Corr^{DIP}$$

$$Ho = Ha + Corr^{ALT}$$

For the moon, use the almanac which will include SD, R, and PA

N LAT is +
S LAT is -

N DEC is +
S DEC is -

E LON is +
W LON is -

Sextant Altitudes deg	Sextant Altitudes arc min	Clock Time H	Clock Time M	Clock Time S
Use this altitude		Use this time		

corrections						
Ho						**UTC**

index corr	
dip corr	
alt corr	
Total corr	

clock corr ____

	deg	arc min	
SHA			
GHA hr			
increment			min and sec
GHA			
Lon			W LON is - E LON is +
LHA			=GHA+Lon
DEC hr			
increment			minutes
DEC			

Ho = ____

from work sheet below → **Hc =** ____

Doffset = ____

The offset distance D_{OFFSET} to determine the true line of position is equal to:

D_{OFFSET} = **(Ho - Hc)**, altitudes in minutes of arc. D_{OFFSET} in nautical miles for both cases. If D_{OFFSET} is positive, then parallel offset your assumed line of position in the azimuth direction towards the heavenly object.

If negative, then draw it away from the heavenly object.

LHA = + / - ☐ deg ☐ arcmin absolute value of |LHA| tables → S1

LAT = + / - ☐ deg ☐ arcmin

DEC = + / - ☐ deg ☐ arcmin absolute value of |DEC| tables → S2, C2



S1
+ C2
= S3
tables
C3
S2
- C3
= S4
tables
angle
K
deg arcmin
note
K > 90 if LHA between 90 and 270
(or between -90 and 90 [-90,-170,150,110, etc])
deg arcmin
K
+/- |LAT|
=
If LAT and DEC same name then subtract (-)
absolute value
K′
deg arcmin
tables
C5
+ C3
= S6
tables
angle
Hc
deg arcmin
tables
C6
S3
- C6
=
absolute value
S7
tables
angle
Zo
less than 90 if
☐ LAT and DEC same name
☐ AND |K| > |LAT|

The arrows with "tables" means go to the S-tables and look at the numbers in the columns. In each column there are 2 numbers side-by-side. If the number sought is an S number, then the one in the same column next to it is a C number. If you have an arrow with "tables/angle", it means locate the given S number, and note the corresponding angle. There are 4 choices of angle, and the given rules will make it clear. When in doubt, use the bold-faced numbers. Also, Hc is always less than 90 deg.

N or S prefix: name of LAT determines N or S

E or W suffix:

If LHA pre-meridian (-180<LHA<0 or 180<LHA<360) then **E**

If LHA post-meridian (0<LHA<180) then **W**

NW: Zn = 360 - Zo

NE: Zn = Zn

SE: Zn = 180 - Zo

SW: Zn = Zo + 180

Zn ☐ deg

Zo ☐ deg



LHA = + ⊖ - 9 deg 2 arcmin absolute value of |LHA| tables → S1 80.408
LAT = + / ⊖ 40 deg 12 arcmin
DEC = ⊕ / - 11 deg 59 arcmin absolute value of |DEC| tables
+ C2 0.957
= S3 81.364 tables → C3 0.518
- S2 68.272
- C3 0.518
= S4 67.753 tables angle → K 12 deg 7.5 arcmin (note)
K > 90 if LHA between 90 and 270 (or between -90 and 90 [-90,-170,150,110, etc])
K 12 7.5
⊕ - |LAT| 40 12
= 52 19.7
If LAT and DEC same name then subtract (-)
absolute value → K′ 52 19.7
C5 21.391
+ C3 0.518
= S6 21.909 tables angle → Hc 37 deg 9 arcmin
tables → C6 9.851
S3 81.364
- C6 9.851
= 71.513 absolute value → S7 71.513
tables angle Zo
less than 90 if greater than 90
☐ LAT and DEC same name
☐ AND |K| > |LAT|
Zo 169 deg
Zn 11 deg

The arrows with "tables" means go to the S-tables and look at the numbers in the columns. In each column there are 2 numbers side-by-side. If the number sought is an S number, then the one in the same column next to it is a C number. If you have an arrow with "tables/angle", it means locate the given S number, and note the corresponding angle. There are 4 choices of angle, and the given rules will make it clear. When in doubt, use the bold-faced numbers. Also, Hc is always less than 90 deg.

N or S prefix: name of LAT determines N or S

E or W suffix:

If LHA pre-meridian (-180<LHA<0 or 180<LHA<360) then E

If LHA post-meridian (0<LHA<180) then W

NW: Zn = 360 - Zo   NE: Zn = Zn

SE: Zn = 180 - Zo   SW: Zn = Zo + 180

This is an example where the LHA was already figured from the GHA and assumed longitude. The assumed latitude is -40° 12' S. Just work it out line by line to see the genesis of the numbers with the corresponding tabular values.

Using the S-Tables

In this section I will provide examples of how to navigate the tables.
In the tables, these are the equations tabulated to the arc minute:
If x is the angle, then S(x) = -100*log(sin(x)), and C(x) = -100*log(cos(x)).
S(x) and C(x) are the S and C values associated with the angle x. Why go to this trouble? Because logarithms change multiplication into addition, and addition is much easier!

If declination **DEC** is 20° 13' S, that means **DEC** = -(20° 13'), and |**DEC**| = 20° 13'. In the tables look up the bold-faced degree **20** (S-Tables, P5). That heading is on the top of the table which means the arc minutes to use are on the left hand side as indicated by the double arrows. Go down to minute 13 and look across to the column for the 20 deg. That number (46.146) is the S number, and the one next to it in the same column is the C number (2.762). If the number you were looking up was 110° 13', then 2.762 would be the S number, and 46.146 would be the C number. Get it?



←	200°	290°	201°
←	**20°**	**110°**	**21°**
0′	46.595	2.701	44.567
1	46.560	2.706	44.534
2	46.526	2.711	44.501
3	46.491	2.715	44.469
4	46.456	2.720	44.436
5	46.422	2.724	44.403
6	46.387	2.729	44.370
7	46.353	2.734	44.337
8	46.318	2.738	44.305
9	46.284	2.743	44.272
10	46.249	2.748	44.239
11	46.215	2.752	44.207
12	46.181	2.757	44.174
13	46.146	2.762	44.142
14	46.112	2.766	44.109
15	46.078	2.771	44.077

Using the bottom row of numbers is equally easy. If you are looking up 85° 5', then 0.160 is the S number and 106.699 is the C number. The bottom row of numbers means you use the right-hand minutes.



0.101	106.846	0.159	**6**
0.102	106.699	0.160	**5**
0.102	106.552	0.161	**4**
0.103	106.406	0.162	**3**
0.104	106.260	0.163	**2**
0.105	106.115	0.164	**1**
0.106	105.970	0.166	**0′**
86°	**175°**	**85°**	→
266°	355°	265°	→

Follow the calculation steps from top to bottom, adding or subtracting where indicated. For the values of K, Hc, and Zo you have "go backwards" thru the tables (an S value is given and you have to determine the corresponding angle).

←	180°	270°	181°	271°	182°	272°	183°	273°	184°	274°	
←	**0°**	**90°**	**1°**	**91°**	**2°**	**92°**	**3°**	**93°**	**4°**	**94°**	
0′	1000.000	0.000	175.815	0.007	145.718	0.026	128.120	0.060	115.642	0.106	**60′**
1	353.627	0.000	175.097	0.007	145.358	0.027	127.880	0.060	115.461	0.107	**59**
2	323.524	0.000	174.391	0.007	145.001	0.027	127.641	0.061	115.282	0.108	**58**
3	305.915	0.000	173.696	0.007	144.646	0.028	127.403	0.062	115.103	0.109	**57**
4	293.421	0.000	173.012	0.008	144.295	0.028	127.166	0.062	114.925	0.109	**56**
5	283.730	0.000	172.339	0.008	143.946	0.029	126.931	0.063	114.748	0.110	**55**
6	275.812	0.000	171.676	0.008	143.600	0.029	126.697	0.064	114.571	0.111	**54**
7	269.118	0.000	171.023	0.008	143.257	0.030	126.465	0.064	114.395	0.112	**53**
8	263.318	0.000	170.379	0.008	142.916	0.030	126.233	0.065	114.220	0.113	**52**
9	258.203	0.000	169.745	0.009	142.579	0.031	126.003	0.066	114.045	0.114	**51**
10	253.627	0.000	169.121	0.009	142.243	0.031	125.774	0.066	113.872	0.115	**50**
11	249.488	0.000	168.505	0.009	141.911	0.032	125.546	0.067	113.699	0.116	**49**
12	245.709	0.000	167.897	0.010	141.581	0.032	125.320	0.068	113.526	0.117	**48**
13	242.233	0.000	167.298	0.010	141.253	0.033	125.095	0.068	113.355	0.118	**47**
14	239.015	0.000	166.708	0.010	140.928	0.033	124.870	0.069	113.184	0.119	**46**
15	236.018	0.000	166.125	0.010	140.605	0.033	124.647	0.070	113.013	0.120	**45**
16	233.216	0.000	165.550	0.011	140.285	0.034	124.425	0.071	112.844	0.121	**44**
17	230.583	0.001	164.982	0.011	139.967	0.034	124.205	0.071	112.675	0.121	**43**
18	228.100	0.001	164.422	0.011	139.651	0.035	123.985	0.072	112.506	0.122	**42**
19	225.752	0.001	163.869	0.011	139.338	0.036	123.766	0.073	112.339	0.123	**41**
20	223.525	0.001	163.322	0.012	139.027	0.036	123.549	0.074	112.172	0.124	**40**
21	221.406	0.001	162.783	0.012	138.718	0.037	123.333	0.074	112.005	0.125	**39**
22	219.385	0.001	162.250	0.012	138.411	0.037	123.117	0.075	111.839	0.126	**38**
23	217.455	0.001	161.724	0.013	138.106	0.038	122.903	0.076	111.674	0.127	**37**
24	215.607	0.001	161.204	0.013	137.804	0.038	122.690	0.077	111.510	0.128	**36**
25	213.834	0.001	160.690	0.013	137.504	0.039	122.478	0.077	111.346	0.129	**35**
26	212.131	0.001	160.182	0.014	137.205	0.039	122.267	0.078	111.183	0.130	**34**
27	210.491	0.001	159.680	0.014	136.909	0.040	122.057	0.079	111.020	0.131	**33**
28	208.912	0.001	159.184	0.014	136.615	0.040	121.848	0.080	110.858	0.132	**32**
29	207.388	0.002	158.693	0.015	136.322	0.041	121.640	0.080	110.697	0.133	**31**
30	205.916	0.002	158.208	0.015	136.032	0.041	121.433	0.081	110.536	0.134	**30**
31	204.492	0.002	157.728	0.015	135.744	0.042	121.226	0.082	110.375	0.135	**29**
32	203.113	0.002	157.254	0.016	135.457	0.042	121.021	0.083	110.216	0.136	**28**
33	201.777	0.002	156.784	0.016	135.173	0.043	120.817	0.083	110.057	0.137	**27**
34	200.480	0.002	156.320	0.016	134.890	0.044	120.614	0.084	109.898	0.138	**26**
35	199.221	0.002	155.861	0.017	134.609	0.044	120.412	0.085	109.740	0.139	**25**
36	197.998	0.002	155.406	0.017	134.330	0.045	120.211	0.086	109.583	0.140	**24**
37	196.808	0.003	154.956	0.017	134.053	0.045	120.010	0.087	109.426	0.141	**23**
38	195.650	0.003	154.511	0.018	133.777	0.046	119.811	0.087	109.270	0.142	**22**
39	194.522	0.003	154.070	0.018	133.503	0.046	119.612	0.088	109.115	0.143	**21**
40	193.422	0.003	153.634	0.018	133.231	0.047	119.415	0.089	108.960	0.144	**20**
41	192.350	0.003	153.202	0.019	132.961	0.048	119.218	0.090	108.805	0.145	**19**
42	191.304	0.003	152.774	0.019	132.692	0.048	119.022	0.091	108.651	0.146	**18**
43	190.282	0.003	152.350	0.019	132.425	0.049	118.827	0.091	108.498	0.147	**17**
44	189.283	0.004	151.931	0.020	132.160	0.049	118.633	0.092	108.345	0.148	**16**
45	188.307	0.004	151.515	0.020	131.896	0.050	118.440	0.093	108.193	0.149	**15**
46	187.353	0.004	151.104	0.021	131.633	0.051	118.248	0.094	108.041	0.150	**14**
47	186.419	0.004	150.696	0.021	131.373	0.051	118.056	0.095	107.890	0.152	**13**
48	185.505	0.004	150.292	0.021	131.114	0.052	117.866	0.096	107.739	0.153	**12**
49	184.609	0.004	149.892	0.022	130.856	0.052	117.676	0.096	107.589	0.154	**11**
50	183.732	0.005	149.496	0.022	130.600	0.053	117.487	0.097	107.439	0.155	**10**
51	182.872	0.005	149.103	0.023	130.346	0.054	117.299	0.098	107.290	0.156	**9**
52	182.029	0.005	148.713	0.023	130.093	0.054	117.112	0.099	107.141	0.157	**8**
53	181.202	0.005	148.327	0.023	129.841	0.055	116.925	0.100	106.993	0.158	**7**
54	180.390	0.005	147.945	0.024	129.591	0.056	116.739	0.101	106.846	0.159	**6**
55	179.593	0.006	147.566	0.024	129.342	0.056	116.554	0.102	106.699	0.160	**5**
56	178.811	0.006	147.190	0.025	129.095	0.057	116.370	0.102	106.552	0.161	**4**
57	178.042	0.006	146.817	0.025	128.849	0.058	116.187	0.103	106.406	0.162	**3**
58	177.287	0.006	146.448	0.026	128.605	0.058	116.004	0.104	106.260	0.163	**2**
59	176.544	0.006	146.081	0.026	128.362	0.059	115.823	0.105	106.115	0.164	**1**
60′	175.815	0.007	145.718	0.026	128.120	0.060	115.642	0.106	105.970	0.166	**0′**
	179°	**89°**	**178°**	**88°**	**177°**	**87°**	**176°**	**86°**	**175°**	**85°**	→
	359°	269°	358°	268°	357°	267°	356°	266°	355°	265°	→

←	185°	275°	186°	276°	187°	277°	188°	278°	189°	279°	
←	**5°**	**95°**	**6°**	**96°**	**7°**	**97°**	**8°**	**98°**	**9°**	**99°**	
0′	105.970	0.166	98.077	0.239	91.411	0.325	85.645	0.425	80.567	0.538	**60′**
1	105.826	0.167	97.957	0.240	91.308	0.326	85.555	0.426	80.487	0.540	**59**
2	105.683	0.168	97.837	0.241	91.205	0.328	85.465	0.428	80.408	0.542	**58**
3	105.539	0.169	97.717	0.243	91.103	0.330	85.376	0.430	80.328	0.544	**57**
4	105.397	0.170	97.598	0.244	91.001	0.331	85.286	0.432	80.249	0.546	**56**
5	105.254	0.171	97.480	0.245	90.899	0.333	85.197	0.434	80.170	0.548	**55**
6	105.113	0.172	97.361	0.247	90.798	0.334	85.109	0.435	80.091	0.550	**54**
7	104.971	0.173	97.243	0.248	90.696	0.336	85.020	0.437	80.012	0.552	**53**
8	104.830	0.175	97.126	0.249	90.595	0.337	84.931	0.439	79.933	0.554	**52**
9	104.690	0.176	97.008	0.251	90.494	0.339	84.843	0.441	79.855	0.556	**51**
10	104.550	0.177	96.891	0.252	90.394	0.341	84.755	0.443	79.777	0.558	**50**
11	104.411	0.178	96.774	0.253	90.294	0.342	84.667	0.444	79.698	0.560	**49**
12	104.272	0.179	96.658	0.255	90.193	0.344	84.579	0.446	79.620	0.562	**48**
13	104.133	0.180	96.542	0.256	90.094	0.345	84.492	0.448	79.542	0.564	**47**
14	103.995	0.181	96.426	0.258	89.994	0.347	84.404	0.450	79.465	0.566	**46**
15	103.857	0.183	96.310	0.259	89.894	0.349	84.317	0.452	79.387	0.568	**45**
16	103.720	0.184	96.195	0.260	89.795	0.350	84.230	0.454	79.309	0.571	**44**
17	103.583	0.185	96.080	0.262	89.696	0.352	84.143	0.455	79.232	0.573	**43**
18	103.447	0.186	95.966	0.263	89.598	0.353	84.056	0.457	79.155	0.575	**42**
19	103.311	0.187	95.852	0.264	89.499	0.355	83.970	0.459	79.078	0.577	**41**
20	103.175	0.188	95.738	0.266	89.401	0.357	83.884	0.461	79.001	0.579	**40**
21	103.040	0.190	95.624	0.267	89.303	0.358	83.797	0.463	78.924	0.581	**39**
22	102.905	0.191	95.510	0.269	89.205	0.360	83.712	0.465	78.847	0.583	**38**
23	102.771	0.192	95.397	0.270	89.107	0.362	83.626	0.467	78.771	0.585	**37**
24	102.637	0.193	95.285	0.272	89.010	0.363	83.540	0.468	78.695	0.587	**36**
25	102.504	0.194	95.172	0.273	88.913	0.365	83.455	0.470	78.618	0.589	**35**
26	102.371	0.196	95.060	0.274	88.816	0.367	83.369	0.472	78.542	0.591	**34**
27	102.238	0.197	94.948	0.276	88.719	0.368	83.284	0.474	78.466	0.593	**33**
28	102.106	0.198	94.836	0.277	88.623	0.370	83.199	0.476	78.390	0.596	**32**
29	101.974	0.199	94.725	0.279	88.526	0.371	83.114	0.478	78.315	0.598	**31**
30	101.843	0.200	94.614	0.280	88.430	0.373	83.030	0.480	78.239	0.600	**30**
31	101.712	0.202	94.503	0.282	88.334	0.375	82.945	0.482	78.164	0.602	**29**
32	101.581	0.203	94.393	0.283	88.239	0.376	82.861	0.483	78.088	0.604	**28**
33	101.451	0.204	94.283	0.284	88.143	0.378	82.777	0.485	78.013	0.606	**27**
34	101.321	0.205	94.173	0.286	88.048	0.380	82.693	0.487	77.938	0.608	**26**
35	101.192	0.207	94.063	0.287	87.953	0.382	82.609	0.489	77.863	0.610	**25**
36	101.063	0.208	93.954	0.289	87.858	0.383	82.526	0.491	77.789	0.612	**24**
37	100.934	0.209	93.845	0.290	87.764	0.385	82.442	0.493	77.714	0.615	**23**
38	100.806	0.210	93.736	0.292	87.669	0.387	82.359	0.495	77.639	0.617	**22**
39	100.678	0.211	93.628	0.293	87.575	0.388	82.276	0.497	77.565	0.619	**21**
40	100.550	0.213	93.519	0.295	87.481	0.390	82.193	0.499	77.491	0.621	**20**
41	100.423	0.214	93.412	0.296	87.388	0.392	82.110	0.501	77.417	0.623	**19**
42	100.296	0.215	93.304	0.298	87.294	0.393	82.027	0.503	77.343	0.625	**18**
43	100.170	0.217	93.196	0.299	87.201	0.395	81.945	0.505	77.269	0.628	**17**
44	100.044	0.218	93.089	0.301	87.108	0.397	81.863	0.506	77.195	0.630	**16**
45	99.918	0.219	92.982	0.302	87.015	0.399	81.780	0.508	77.122	0.632	**15**
46	99.793	0.220	92.876	0.304	86.922	0.400	81.698	0.510	77.048	0.634	**14**
47	99.668	0.222	92.769	0.305	86.829	0.402	81.617	0.512	76.975	0.636	**13**
48	99.544	0.223	92.663	0.307	86.737	0.404	81.535	0.514	76.902	0.638	**12**
49	99.420	0.224	92.558	0.308	86.645	0.405	81.453	0.516	76.829	0.641	**11**
50	99.296	0.225	92.452	0.310	86.553	0.407	81.372	0.518	76.756	0.643	**10**
51	99.172	0.227	92.347	0.311	86.461	0.409	81.291	0.520	76.683	0.645	**9**
52	99.049	0.228	92.242	0.313	86.370	0.411	81.210	0.522	76.610	0.647	**8**
53	98.926	0.229	92.137	0.314	86.278	0.412	81.129	0.524	76.538	0.649	**7**
54	98.804	0.231	92.032	0.316	86.187	0.414	81.048	0.526	76.465	0.652	**6**
55	98.682	0.232	91.928	0.317	86.096	0.416	80.967	0.528	76.393	0.654	**5**
56	98.560	0.233	91.824	0.319	86.006	0.418	80.887	0.530	76.321	0.656	**4**
57	98.439	0.235	91.720	0.320	85.915	0.419	80.807	0.532	76.249	0.658	**3**
58	98.318	0.236	91.617	0.322	85.825	0.421	80.727	0.534	76.177	0.660	**2**
59	98.197	0.237	91.514	0.323	85.734	0.423	80.647	0.536	76.105	0.663	**1**
60′	98.077	0.239	91.411	0.325	85.645	0.425	80.567	0.538	76.033	0.665	**0′**
	174°	**84°**	**173°**	**83°**	**172°**	**82°**	**171°**	**81°**	**170°**	**80°**	→
	354°	264°	353°	263°	352°	262°	351°	261°	350°	260°	→

←	190°	280°	191°	281°	192°	282°	193°	283°	194°	284°	
←	**10°**	**100°**	**11°**	**101°**	**12°**	**102°**	**13°**	**103°**	**14°**	**104°**	
0′	76.033	0.665	71.940	0.805	68.212	0.960	64.791	1.128	61.633	1.310	**60′**
1	75.961	0.667	71.875	0.808	68.153	0.962	64.737	1.131	61.582	1.313	**59**
2	75.890	0.669	71.810	0.810	68.093	0.965	64.682	1.133	61.531	1.316	**58**
3	75.819	0.672	71.746	0.813	68.034	0.968	64.627	1.136	61.481	1.319	**57**
4	75.747	0.674	71.681	0.815	67.975	0.970	64.573	1.139	61.430	1.322	**56**
5	75.676	0.676	71.616	0.818	67.916	0.973	64.519	1.142	61.380	1.325	**55**
6	75.605	0.678	71.552	0.820	67.857	0.976	64.464	1.145	61.330	1.329	**54**
7	75.534	0.681	71.488	0.823	67.798	0.978	64.410	1.148	61.279	1.332	**53**
8	75.464	0.683	71.423	0.825	67.739	0.981	64.356	1.151	61.229	1.335	**52**
9	75.393	0.685	71.359	0.828	67.681	0.984	64.302	1.154	61.179	1.338	**51**
10	75.323	0.687	71.295	0.830	67.622	0.987	64.248	1.157	61.129	1.341	**50**
11	75.252	0.690	71.231	0.833	67.563	0.989	64.194	1.160	61.079	1.344	**49**
12	75.182	0.692	71.167	0.835	67.505	0.992	64.140	1.163	61.029	1.348	**48**
13	75.112	0.694	71.104	0.838	67.447	0.995	64.086	1.166	60.979	1.351	**47**
14	75.042	0.696	71.040	0.840	67.388	0.998	64.032	1.169	60.929	1.354	**46**
15	74.972	0.699	70.976	0.843	67.330	1.000	63.979	1.172	60.879	1.357	**45**
16	74.902	0.701	70.913	0.845	67.272	1.003	63.925	1.175	60.830	1.360	**44**
17	74.832	0.703	70.850	0.848	67.214	1.006	63.871	1.178	60.780	1.364	**43**
18	74.763	0.706	70.786	0.850	67.156	1.009	63.818	1.181	60.731	1.367	**42**
19	74.693	0.708	70.723	0.853	67.098	1.011	63.764	1.184	60.681	1.370	**41**
20	74.624	0.710	70.660	0.855	67.040	1.014	63.711	1.187	60.632	1.373	**40**
21	74.555	0.712	70.597	0.858	66.982	1.017	63.658	1.190	60.582	1.377	**39**
22	74.486	0.715	70.534	0.860	66.925	1.020	63.605	1.193	60.533	1.380	**38**
23	74.417	0.717	70.471	0.863	66.867	1.022	63.552	1.196	60.483	1.383	**37**
24	74.348	0.719	70.409	0.865	66.810	1.025	63.498	1.199	60.434	1.386	**36**
25	74.279	0.722	70.346	0.868	66.752	1.028	63.445	1.202	60.385	1.390	**35**
26	74.210	0.724	70.284	0.870	66.695	1.031	63.393	1.205	60.336	1.393	**34**
27	74.142	0.726	70.221	0.873	66.638	1.033	63.340	1.208	60.287	1.396	**33**
28	74.073	0.729	70.159	0.876	66.580	1.036	63.287	1.211	60.238	1.399	**32**
29	74.005	0.731	70.097	0.878	66.523	1.039	63.234	1.214	60.189	1.403	**31**
30	73.937	0.733	70.035	0.881	66.466	1.042	63.182	1.217	60.140	1.406	**30**
31	73.869	0.736	69.972	0.883	66.409	1.045	63.129	1.220	60.091	1.409	**29**
32	73.801	0.738	69.911	0.886	66.353	1.047	63.076	1.223	60.042	1.412	**28**
33	73.733	0.740	69.849	0.888	66.296	1.050	63.024	1.226	59.994	1.416	**27**
34	73.665	0.743	69.787	0.891	66.239	1.053	62.972	1.229	59.945	1.419	**26**
35	73.597	0.745	69.725	0.894	66.182	1.056	62.919	1.232	59.897	1.422	**25**
36	73.530	0.748	69.664	0.896	66.126	1.059	62.867	1.235	59.848	1.426	**24**
37	73.462	0.750	69.602	0.899	66.069	1.062	62.815	1.238	59.800	1.429	**23**
38	73.395	0.752	69.541	0.901	66.013	1.064	62.763	1.241	59.751	1.432	**22**
39	73.328	0.755	69.479	0.904	65.957	1.067	62.711	1.244	59.703	1.435	**21**
40	73.261	0.757	69.418	0.907	65.900	1.070	62.659	1.247	59.654	1.439	**20**
41	73.194	0.759	69.357	0.909	65.844	1.073	62.607	1.250	59.606	1.442	**19**
42	73.127	0.762	69.296	0.912	65.788	1.076	62.555	1.254	59.558	1.445	**18**
43	73.060	0.764	69.235	0.914	65.732	1.079	62.503	1.257	59.510	1.449	**17**
44	72.993	0.767	69.174	0.917	65.676	1.081	62.451	1.260	59.462	1.452	**16**
45	72.927	0.769	69.113	0.920	65.620	1.084	62.400	1.263	59.414	1.455	**15**
46	72.860	0.771	69.053	0.922	65.565	1.087	62.348	1.266	59.366	1.459	**14**
47	72.794	0.774	68.992	0.925	65.509	1.090	62.297	1.269	59.318	1.462	**13**
48	72.727	0.776	68.932	0.928	65.453	1.093	62.245	1.272	59.270	1.465	**12**
49	72.661	0.779	68.871	0.930	65.398	1.096	62.194	1.275	59.222	1.469	**11**
50	72.595	0.781	68.811	0.933	65.342	1.099	62.142	1.278	59.175	1.472	**10**
51	72.529	0.783	68.751	0.936	65.287	1.102	62.091	1.281	59.127	1.475	**9**
52	72.463	0.786	68.690	0.938	65.231	1.104	62.040	1.285	59.079	1.479	**8**
53	72.398	0.788	68.630	0.941	65.176	1.107	61.989	1.288	59.032	1.482	**7**
54	72.332	0.791	68.570	0.944	65.121	1.110	61.938	1.291	58.984	1.485	**6**
55	72.266	0.793	68.510	0.946	65.066	1.113	61.887	1.294	58.937	1.489	**5**
56	72.201	0.796	68.451	0.949	65.011	1.116	61.836	1.297	58.889	1.492	**4**
57	72.136	0.798	68.391	0.952	64.956	1.119	61.785	1.300	58.842	1.495	**3**
58	72.070	0.800	68.331	0.954	64.901	1.122	61.734	1.303	58.795	1.499	**2**
59	72.005	0.803	68.272	0.957	64.846	1.125	61.683	1.306	58.748	1.502	**1**
60′	71.940	0.805	68.212	0.960	64.791	1.128	61.633	1.310	58.700	1.506	**0′**
	169°	**79°**	**168°**	**78°**	**167°**	**77°**	**166°**	**76°**	**165°**	**75°**	**→**
	349°	259°	348°	258°	347°	257°	346°	256°	345°	255°	→

←	195°	285°	196°	286°	197°	287°	198°	288°	199°	289°	
←	**15°**	**105°**	**16°**	**106°**	**17°**	**107°**	**18°**	**108°**	**19°**	**109°**	
0′	58.700	1.506	55.966	1.716	53.407	1.940	51.002	2.179	48.736	2.433	**60′**
1	58.653	1.509	55.922	1.719	53.365	1.944	50.963	2.183	48.699	2.437	**59**
2	58.606	1.512	55.878	1.723	53.324	1.948	50.924	2.188	48.663	2.442	**58**
3	58.559	1.516	55.834	1.727	53.283	1.952	50.885	2.192	48.626	2.446	**57**
4	58.512	1.519	55.790	1.730	53.242	1.956	50.847	2.196	48.589	2.450	**56**
5	58.465	1.523	55.747	1.734	53.200	1.960	50.808	2.200	48.553	2.455	**55**
6	58.419	1.526	55.703	1.738	53.159	1.964	50.769	2.204	48.516	2.459	**54**
7	58.372	1.529	55.659	1.741	53.118	1.967	50.731	2.208	48.480	2.464	**53**
8	58.325	1.533	55.615	1.745	53.077	1.971	50.692	2.212	48.443	2.468	**52**
9	58.278	1.536	55.572	1.749	53.036	1.975	50.653	2.216	48.407	2.472	**51**
10	58.232	1.540	55.528	1.752	52.995	1.979	50.615	2.221	48.371	2.477	**50**
11	58.185	1.543	55.485	1.756	52.955	1.983	50.576	2.225	48.334	2.481	**49**
12	58.139	1.547	55.441	1.760	52.914	1.987	50.538	2.229	48.298	2.485	**48**
13	58.092	1.550	55.398	1.763	52.873	1.991	50.500	2.233	48.262	2.490	**47**
14	58.046	1.553	55.354	1.767	52.832	1.995	50.461	2.237	48.226	2.494	**46**
15	57.999	1.557	55.311	1.771	52.791	1.999	50.423	2.241	48.189	2.499	**45**
16	57.953	1.560	55.267	1.774	52.751	2.003	50.385	2.246	48.153	2.503	**44**
17	57.907	1.564	55.224	1.778	52.710	2.007	50.346	2.250	48.117	2.508	**43**
18	57.861	1.567	55.181	1.782	52.670	2.011	50.308	2.254	48.081	2.512	**42**
19	57.814	1.571	55.138	1.785	52.629	2.014	50.270	2.258	48.045	2.516	**41**
20	57.768	1.574	55.095	1.789	52.589	2.018	50.232	2.262	48.009	2.521	**40**
21	57.722	1.578	55.052	1.793	52.548	2.022	50.194	2.266	47.973	2.525	**39**
22	57.676	1.581	55.009	1.796	52.508	2.026	50.156	2.271	47.937	2.530	**38**
23	57.630	1.585	54.966	1.800	52.467	2.030	50.118	2.275	47.901	2.534	**37**
24	57.584	1.588	54.923	1.804	52.427	2.034	50.080	2.279	47.865	2.539	**36**
25	57.539	1.591	54.880	1.808	52.387	2.038	50.042	2.283	47.829	2.543	**35**
26	57.493	1.595	54.837	1.811	52.346	2.042	50.004	2.287	47.793	2.547	**34**
27	57.447	1.598	54.794	1.815	52.306	2.046	49.966	2.292	47.758	2.552	**33**
28	57.401	1.602	54.751	1.819	52.266	2.050	49.928	2.296	47.722	2.556	**32**
29	57.356	1.605	54.709	1.823	52.226	2.054	49.890	2.300	47.686	2.561	**31**
30	57.310	1.609	54.666	1.826	52.186	2.058	49.852	2.304	47.651	2.565	**30**
31	57.265	1.612	54.623	1.830	52.146	2.062	49.815	2.309	47.615	2.570	**29**
32	57.219	1.616	54.581	1.834	52.106	2.066	49.777	2.313	47.579	2.574	**28**
33	57.174	1.619	54.538	1.838	52.066	2.070	49.739	2.317	47.544	2.579	**27**
34	57.128	1.623	54.496	1.841	52.026	2.074	49.702	2.321	47.508	2.583	**26**
35	57.083	1.627	54.453	1.845	51.986	2.078	49.664	2.326	47.473	2.588	**25**
36	57.038	1.630	54.411	1.849	51.946	2.082	49.627	2.330	47.437	2.592	**24**
37	56.993	1.634	54.368	1.853	51.906	2.086	49.589	2.334	47.402	2.597	**23**
38	56.947	1.637	54.326	1.856	51.867	2.090	49.552	2.338	47.366	2.601	**22**
39	56.902	1.641	54.284	1.860	51.827	2.094	49.514	2.343	47.331	2.606	**21**
40	56.857	1.644	54.242	1.864	51.787	2.098	49.477	2.347	47.295	2.610	**20**
41	56.812	1.648	54.199	1.868	51.748	2.102	49.439	2.351	47.260	2.615	**19**
42	56.767	1.651	54.157	1.871	51.708	2.106	49.402	2.355	47.225	2.619	**18**
43	56.722	1.655	54.115	1.875	51.668	2.110	49.365	2.360	47.190	2.624	**17**
44	56.677	1.658	54.073	1.879	51.629	2.114	49.327	2.364	47.154	2.628	**16**
45	56.633	1.662	54.031	1.883	51.589	2.118	49.290	2.368	47.119	2.633	**15**
46	56.588	1.666	53.989	1.887	51.550	2.122	49.253	2.372	47.084	2.637	**14**
47	56.543	1.669	53.947	1.890	51.511	2.126	49.216	2.377	47.049	2.642	**13**
48	56.498	1.673	53.905	1.894	51.471	2.130	49.179	2.381	47.014	2.647	**12**
49	56.454	1.676	53.864	1.898	51.432	2.134	49.142	2.385	46.979	2.651	**11**
50	56.409	1.680	53.822	1.902	51.393	2.139	49.104	2.390	46.944	2.656	**10**
51	56.365	1.683	53.780	1.906	51.353	2.143	49.067	2.394	46.909	2.660	**9**
52	56.320	1.687	53.738	1.910	51.314	2.147	49.030	2.398	46.874	2.665	**8**
53	56.276	1.691	53.697	1.913	51.275	2.151	48.994	2.403	46.839	2.669	**7**
54	56.231	1.694	53.655	1.917	51.236	2.155	48.957	2.407	46.804	2.674	**6**
55	56.187	1.698	53.614	1.921	51.197	2.159	48.920	2.411	46.769	2.678	**5**
56	56.143	1.701	53.572	1.925	51.158	2.163	48.883	2.416	46.734	2.683	**4**
57	56.099	1.705	53.531	1.929	51.119	2.167	48.846	2.420	46.699	2.688	**3**
58	56.054	1.709	53.489	1.933	51.080	2.171	48.809	2.424	46.664	2.692	**2**
59	56.010	1.712	53.448	1.937	51.041	2.175	48.773	2.429	46.630	2.697	**1**
60′	55.966	1.716	53.407	1.940	51.002	2.179	48.736	2.433	46.595	2.701	**0′**
	164°	**74°**	**163°**	**73°**	**162°**	**72°**	**161°**	**71°**	**160°**	**70°**	→
	344°	254°	343°	253°	342°	252°	341°	251°	340°	250°	→

←	200°	290°	201°	291°	202°	292°	203°	293°	204°	294°	
←	**20°**	**110°**	**21°**	**111°**	**22°**	**112°**	**23°**	**113°**	**24°**	**114°**	
0′	46.595	2.701	44.567	2.985	42.642	3.283	40.812	3.597	39.069	3.927	**60′**
1	46.560	2.706	44.534	2.990	42.611	3.289	40.782	3.603	39.040	3.933	**59**
2	46.526	2.711	44.501	2.995	42.580	3.294	40.753	3.608	39.012	3.938	**58**
3	46.491	2.715	44.469	2.999	42.549	3.299	40.723	3.613	38.984	3.944	**57**
4	46.456	2.720	44.436	3.004	42.518	3.304	40.693	3.619	38.955	3.950	**56**
5	46.422	2.724	44.403	3.009	42.486	3.309	40.664	3.624	38.927	3.955	**55**
6	46.387	2.729	44.370	3.014	42.455	3.314	40.634	3.630	38.899	3.961	**54**
7	46.353	2.734	44.337	3.019	42.424	3.319	40.604	3.635	38.871	3.966	**53**
8	46.318	2.738	44.305	3.024	42.393	3.324	40.575	3.640	38.842	3.972	**52**
9	46.284	2.743	44.272	3.029	42.362	3.330	40.545	3.646	38.814	3.978	**51**
10	46.249	2.748	44.239	3.034	42.331	3.335	40.516	3.651	38.786	3.983	**50**
11	46.215	2.752	44.207	3.038	42.300	3.340	40.486	3.657	38.758	3.989	**49**
12	46.181	2.757	44.174	3.043	42.269	3.345	40.457	3.662	38.730	3.995	**48**
13	46.146	2.762	44.142	3.048	42.238	3.350	40.427	3.667	38.702	4.000	**47**
14	46.112	2.766	44.109	3.053	42.207	3.355	40.398	3.673	38.674	4.006	**46**
15	46.078	2.771	44.077	3.058	42.176	3.360	40.368	3.678	38.646	4.012	**45**
16	46.044	2.776	44.044	3.063	42.146	3.366	40.339	3.684	38.618	4.018	**44**
17	46.009	2.780	44.012	3.068	42.115	3.371	40.310	3.689	38.590	4.023	**43**
18	45.975	2.785	43.979	3.073	42.084	3.376	40.280	3.695	38.562	4.029	**42**
19	45.941	2.790	43.947	3.078	42.053	3.381	40.251	3.700	38.534	4.035	**41**
20	45.907	2.794	43.915	3.083	42.022	3.386	40.222	3.706	38.506	4.040	**40**
21	45.873	2.799	43.882	3.088	41.992	3.392	40.192	3.711	38.478	4.046	**39**
22	45.839	2.804	43.850	3.093	41.961	3.397	40.163	3.716	38.450	4.052	**38**
23	45.805	2.808	43.818	3.097	41.930	3.402	40.134	3.722	38.422	4.058	**37**
24	45.771	2.813	43.785	3.102	41.900	3.407	40.105	3.727	38.394	4.063	**36**
25	45.737	2.818	43.753	3.107	41.869	3.412	40.076	3.733	38.366	4.069	**35**
26	45.703	2.822	43.721	3.112	41.838	3.418	40.046	3.738	38.338	4.075	**34**
27	45.669	2.827	43.689	3.117	41.808	3.423	40.017	3.744	38.311	4.080	**33**
28	45.635	2.832	43.657	3.122	41.777	3.428	39.988	3.749	38.283	4.086	**32**
29	45.601	2.837	43.625	3.127	41.747	3.433	39.959	3.755	38.255	4.092	**31**
30	45.568	2.841	43.592	3.132	41.716	3.438	39.930	3.760	38.227	4.098	**30**
31	45.534	2.846	43.560	3.137	41.686	3.444	39.901	3.766	38.200	4.103	**29**
32	45.500	2.851	43.528	3.142	41.655	3.449	39.872	3.771	38.172	4.109	**28**
33	45.466	2.855	43.496	3.147	41.625	3.454	39.843	3.777	38.144	4.115	**27**
34	45.433	2.860	43.464	3.152	41.594	3.459	39.814	3.782	38.117	4.121	**26**
35	45.399	2.865	43.432	3.157	41.564	3.465	39.785	3.788	38.089	4.127	**25**
36	45.365	2.870	43.401	3.162	41.534	3.470	39.756	3.793	38.061	4.132	**24**
37	45.332	2.874	43.369	3.167	41.503	3.475	39.727	3.799	38.034	4.138	**23**
38	45.298	2.879	43.337	3.172	41.473	3.480	39.698	3.804	38.006	4.144	**22**
39	45.265	2.884	43.305	3.177	41.443	3.486	39.670	3.810	37.979	4.150	**21**
40	45.231	2.889	43.273	3.182	41.412	3.491	39.641	3.815	37.951	4.155	**20**
41	45.198	2.893	43.241	3.187	41.382	3.496	39.612	3.821	37.924	4.161	**19**
42	45.164	2.898	43.210	3.192	41.352	3.502	39.583	3.826	37.896	4.167	**18**
43	45.131	2.903	43.178	3.197	41.322	3.507	39.554	3.832	37.869	4.173	**17**
44	45.097	2.908	43.146	3.202	41.292	3.512	39.526	3.838	37.841	4.179	**16**
45	45.064	2.913	43.114	3.207	41.261	3.517	39.497	3.843	37.814	4.185	**15**
46	45.031	2.917	43.083	3.212	41.231	3.523	39.468	3.849	37.787	4.190	**14**
47	44.997	2.922	43.051	3.217	41.201	3.528	39.439	3.854	37.759	4.196	**13**
48	44.964	2.927	43.020	3.222	41.171	3.533	39.411	3.860	37.732	4.202	**12**
49	44.931	2.932	42.988	3.228	41.141	3.539	39.382	3.865	37.704	4.208	**11**
50	44.898	2.937	42.956	3.233	41.111	3.544	39.354	3.871	37.677	4.214	**10**
51	44.864	2.941	42.925	3.238	41.081	3.549	39.325	3.877	37.650	4.220	**9**
52	44.831	2.946	42.893	3.243	41.051	3.555	39.296	3.882	37.623	4.225	**8**
53	44.798	2.951	42.862	3.248	41.021	3.560	39.268	3.888	37.595	4.231	**7**
54	44.765	2.956	42.831	3.253	40.991	3.565	39.239	3.893	37.568	4.237	**6**
55	44.732	2.961	42.799	3.258	40.961	3.571	39.211	3.899	37.541	4.243	**5**
56	44.699	2.965	42.768	3.263	40.931	3.576	39.182	3.905	37.514	4.249	**4**
57	44.666	2.970	42.736	3.268	40.902	3.581	39.154	3.910	37.487	4.255	**3**
58	44.633	2.975	42.705	3.273	40.872	3.587	39.125	3.916	37.459	4.261	**2**
59	44.600	2.980	42.674	3.278	40.842	3.592	39.097	3.921	37.432	4.267	**1**
60′	44.567	2.985	42.642	3.283	40.812	3.597	39.069	3.927	37.405	4.272	**0′**
	159°	**69°**	**158°**	**68°**	**157°**	**67°**	**156°**	**66°**	**155°**	**65°**	→
	339°	249°	338°	248°	337°	247°	336°	246°	335°	245°	→

←	205°	295°	206°	296°	207°	297°	208°	298°	209°	299°	
←	**25°**	**115°**	**26°**	**116°**	**27°**	**117°**	**28°**	**118°**	**29°**	**119°**	
0′	37.405	4.272	35.816	4.634	34.295	5.012	32.839	5.406	31.443	5.818	**60′**
1	37.378	4.278	35.790	4.640	34.271	5.018	32.815	5.413	31.420	5.825	**59**
2	37.351	4.284	35.764	4.646	34.246	5.025	32.792	5.420	31.397	5.832	**58**
3	37.324	4.290	35.738	4.652	34.221	5.031	32.768	5.427	31.375	5.839	**57**
4	37.297	4.296	35.712	4.659	34.196	5.038	32.744	5.433	31.352	5.846	**56**
5	37.270	4.302	35.687	4.665	34.172	5.044	32.721	5.440	31.329	5.853	**55**
6	37.243	4.308	35.661	4.671	34.147	5.051	32.697	5.447	31.306	5.860	**54**
7	37.216	4.314	35.635	4.677	34.122	5.057	32.673	5.454	31.284	5.867	**53**
8	37.189	4.320	35.609	4.683	34.098	5.064	32.650	5.460	31.261	5.874	**52**
9	37.162	4.326	35.583	4.690	34.073	5.070	32.626	5.467	31.238	5.881	**51**
10	37.135	4.332	35.558	4.696	34.048	5.077	32.602	5.474	31.216	5.888	**50**
11	37.108	4.337	35.532	4.702	34.024	5.083	32.579	5.481	31.193	5.895	**49**
12	37.082	4.343	35.506	4.708	33.999	5.089	32.555	5.487	31.171	5.902	**48**
13	37.055	4.349	35.481	4.714	33.975	5.096	32.532	5.494	31.148	5.910	**47**
14	37.028	4.355	35.455	4.721	33.950	5.102	32.508	5.501	31.125	5.917	**46**
15	37.001	4.361	35.429	4.727	33.925	5.109	32.485	5.508	31.103	5.924	**45**
16	36.974	4.367	35.404	4.733	33.901	5.115	32.461	5.515	31.080	5.931	**44**
17	36.948	4.373	35.378	4.739	33.876	5.122	32.438	5.521	31.058	5.938	**43**
18	36.921	4.379	35.353	4.746	33.852	5.129	32.414	5.528	31.035	5.945	**42**
19	36.894	4.385	35.327	4.752	33.827	5.135	32.391	5.535	31.013	5.952	**41**
20	36.867	4.391	35.302	4.758	33.803	5.142	32.367	5.542	30.990	5.959	**40**
21	36.841	4.397	35.276	4.764	33.779	5.148	32.344	5.549	30.968	5.966	**39**
22	36.814	4.403	35.251	4.771	33.754	5.155	32.320	5.555	30.945	5.973	**38**
23	36.787	4.409	35.225	4.777	33.730	5.161	32.297	5.562	30.923	5.980	**37**
24	36.761	4.415	35.200	4.783	33.705	5.168	32.274	5.569	30.900	5.988	**36**
25	36.734	4.421	35.174	4.789	33.681	5.174	32.250	5.576	30.878	5.995	**35**
26	36.708	4.427	35.149	4.796	33.657	5.181	32.227	5.583	30.856	6.002	**34**
27	36.681	4.433	35.123	4.802	33.632	5.187	32.204	5.590	30.833	6.009	**33**
28	36.655	4.439	35.098	4.808	33.608	5.194	32.180	5.596	30.811	6.016	**32**
29	36.628	4.445	35.073	4.815	33.584	5.201	32.157	5.603	30.788	6.023	**31**
30	36.602	4.451	35.047	4.821	33.559	5.207	32.134	5.610	30.766	6.030	**30**
31	36.575	4.457	35.022	4.827	33.535	5.214	32.110	5.617	30.744	6.037	**29**
32	36.549	4.463	34.997	4.833	33.511	5.220	32.087	5.624	30.722	6.045	**28**
33	36.522	4.469	34.971	4.840	33.487	5.227	32.064	5.631	30.699	6.052	**27**
34	36.496	4.475	34.946	4.846	33.463	5.233	32.041	5.638	30.677	6.059	**26**
35	36.469	4.481	34.921	4.852	33.438	5.240	32.018	5.644	30.655	6.066	**25**
36	36.443	4.487	34.896	4.859	33.414	5.247	31.994	5.651	30.632	6.073	**24**
37	36.417	4.493	34.870	4.865	33.390	5.253	31.971	5.658	30.610	6.080	**23**
38	36.390	4.500	34.845	4.871	33.366	5.260	31.948	5.665	30.588	6.088	**22**
39	36.364	4.506	34.820	4.878	33.342	5.266	31.925	5.672	30.566	6.095	**21**
40	36.338	4.512	34.795	4.884	33.318	5.273	31.902	5.679	30.544	6.102	**20**
41	36.311	4.518	34.770	4.890	33.294	5.280	31.879	5.686	30.521	6.109	**19**
42	36.285	4.524	34.745	4.897	33.269	5.286	31.856	5.693	30.499	6.116	**18**
43	36.259	4.530	34.719	4.903	33.245	5.293	31.833	5.700	30.477	6.124	**17**
44	36.233	4.536	34.694	4.910	33.221	5.300	31.810	5.707	30.455	6.131	**16**
45	36.207	4.542	34.669	4.916	33.197	5.306	31.787	5.714	30.433	6.138	**15**
46	36.180	4.548	34.644	4.922	33.173	5.313	31.764	5.720	30.411	6.145	**14**
47	36.154	4.554	34.619	4.929	33.149	5.320	31.741	5.727	30.389	6.153	**13**
48	36.128	4.560	34.594	4.935	33.125	5.326	31.718	5.734	30.367	6.160	**12**
49	36.102	4.566	34.569	4.941	33.101	5.333	31.695	5.741	30.345	6.167	**11**
50	36.076	4.573	34.544	4.948	33.078	5.340	31.672	5.748	30.323	6.174	**10**
51	36.050	4.579	34.519	4.954	33.054	5.346	31.649	5.755	30.301	6.181	**9**
52	36.024	4.585	34.494	4.961	33.030	5.353	31.626	5.762	30.279	6.189	**8**
53	35.998	4.591	34.469	4.967	33.006	5.360	31.603	5.769	30.257	6.196	**7**
54	35.972	4.597	34.444	4.973	32.982	5.366	31.580	5.776	30.235	6.203	**6**
55	35.946	4.603	34.420	4.980	32.958	5.373	31.557	5.783	30.213	6.211	**5**
56	35.920	4.609	34.395	4.986	32.934	5.380	31.534	5.790	30.191	6.218	**4**
57	35.894	4.616	34.370	4.993	32.910	5.386	31.511	5.797	30.169	6.225	**3**
58	35.868	4.622	34.345	4.999	32.887	5.393	31.489	5.804	30.147	6.232	**2**
59	35.842	4.628	34.320	5.005	32.863	5.400	31.466	5.811	30.125	6.240	**1**
60′	35.816	4.634	34.295	5.012	32.839	5.406	31.443	5.818	30.103	6.247	**0′**
	154°	**64°**	**153°**	**63°**	**152°**	**62°**	**151°**	**61°**	**150°**	**60°**	→
	334°	244°	333°	243°	332°	242°	331°	241°	330°	240°	→

←	210°	300°	211°	301°	212°	302°	213°	303°	214°	304°	
←	**30°**	**120°**	**31°**	**121°**	**32°**	**122°**	**33°**	**123°**	**34°**	**124°**	
0′	30.103	6.247	28.816	6.693	27.579	7.158	26.389	7.641	25.244	8.143	**60′**
1	30.081	6.254	28.795	6.701	27.559	7.166	26.370	7.649	25.225	8.151	**59**
2	30.059	6.262	28.774	6.709	27.539	7.174	26.350	7.657	25.206	8.160	**58**
3	30.037	6.269	28.753	6.716	27.518	7.182	26.331	7.665	25.188	8.168	**57**
4	30.016	6.276	28.732	6.724	27.498	7.190	26.311	7.674	25.169	8.177	**56**
5	29.994	6.283	28.711	6.731	27.478	7.197	26.292	7.682	25.150	8.185	**55**
6	29.972	6.291	28.690	6.739	27.458	7.205	26.273	7.690	25.132	8.194	**54**
7	29.950	6.298	28.669	6.747	27.438	7.213	26.253	7.698	25.113	8.202	**53**
8	29.928	6.305	28.648	6.754	27.418	7.221	26.234	7.707	25.094	8.211	**52**
9	29.907	6.313	28.627	6.762	27.398	7.229	26.215	7.715	25.076	8.219	**51**
10	29.885	6.320	28.607	6.770	27.378	7.237	26.195	7.723	25.057	8.228	**50**
11	29.863	6.327	28.586	6.777	27.357	7.245	26.176	7.731	25.039	8.237	**49**
12	29.842	6.335	28.565	6.785	27.337	7.253	26.157	7.740	25.020	8.245	**48**
13	29.820	6.342	28.544	6.793	27.317	7.261	26.137	7.748	25.001	8.254	**47**
14	29.798	6.350	28.523	6.800	27.297	7.269	26.118	7.756	24.983	8.262	**46**
15	29.776	6.357	28.502	6.808	27.277	7.277	26.099	7.764	24.964	8.271	**45**
16	29.755	6.364	28.481	6.816	27.257	7.285	26.079	7.773	24.946	8.280	**44**
17	29.733	6.372	28.461	6.823	27.237	7.293	26.060	7.781	24.927	8.288	**43**
18	29.712	6.379	28.440	6.831	27.217	7.301	26.041	7.789	24.909	8.297	**42**
19	29.690	6.386	28.419	6.839	27.197	7.309	26.022	7.798	24.890	8.305	**41**
20	29.668	6.394	28.398	6.846	27.177	7.317	26.003	7.806	24.872	8.314	**40**
21	29.647	6.401	28.378	6.854	27.157	7.325	25.983	7.814	24.853	8.323	**39**
22	29.625	6.409	28.357	6.862	27.137	7.333	25.964	7.823	24.835	8.331	**38**
23	29.604	6.416	28.336	6.869	27.118	7.341	25.945	7.831	24.816	8.340	**37**
24	29.582	6.423	28.315	6.877	27.098	7.349	25.926	7.839	24.798	8.349	**36**
25	29.561	6.431	28.295	6.885	27.078	7.357	25.907	7.848	24.779	8.357	**35**
26	29.539	6.438	28.274	6.892	27.058	7.365	25.888	7.856	24.761	8.366	**34**
27	29.518	6.446	28.253	6.900	27.038	7.373	25.868	7.864	24.742	8.375	**33**
28	29.496	6.453	28.233	6.908	27.018	7.381	25.849	7.873	24.724	8.383	**32**
29	29.475	6.461	28.212	6.916	26.998	7.389	25.830	7.881	24.706	8.392	**31**
30	29.453	6.468	28.192	6.923	26.978	7.397	25.811	7.889	24.687	8.401	**30**
31	29.432	6.475	28.171	6.931	26.959	7.405	25.792	7.898	24.669	8.409	**29**
32	29.410	6.483	28.150	6.939	26.939	7.413	25.773	7.906	24.650	8.418	**28**
33	29.389	6.490	28.130	6.947	26.919	7.421	25.754	7.914	24.632	8.427	**27**
34	29.367	6.498	28.109	6.954	26.899	7.429	25.735	7.923	24.614	8.435	**26**
35	29.346	6.505	28.089	6.962	26.879	7.437	25.716	7.931	24.595	8.444	**25**
36	29.325	6.513	28.068	6.970	26.860	7.445	25.697	7.940	24.577	8.453	**24**
37	29.303	6.520	28.048	6.978	26.840	7.454	25.678	7.948	24.559	8.462	**23**
38	29.282	6.528	28.027	6.986	26.820	7.462	25.659	7.956	24.541	8.470	**22**
39	29.261	6.535	28.007	6.993	26.800	7.470	25.640	7.965	24.522	8.479	**21**
40	29.239	6.543	27.986	7.001	26.781	7.478	25.621	7.973	24.504	8.488	**20**
41	29.218	6.550	27.966	7.009	26.761	7.486	25.602	7.982	24.486	8.496	**19**
42	29.197	6.558	27.945	7.017	26.741	7.494	25.583	7.990	24.467	8.505	**18**
43	29.176	6.565	27.925	7.024	26.722	7.502	25.564	7.998	24.449	8.514	**17**
44	29.154	6.573	27.904	7.032	26.702	7.510	25.545	8.007	24.431	8.523	**16**
45	29.133	6.580	27.884	7.040	26.682	7.518	25.526	8.015	24.413	8.531	**15**
46	29.112	6.588	27.863	7.048	26.663	7.527	25.507	8.024	24.395	8.540	**14**
47	29.091	6.595	27.843	7.056	26.643	7.535	25.488	8.032	24.376	8.549	**13**
48	29.069	6.603	27.823	7.064	26.623	7.543	25.469	8.041	24.358	8.558	**12**
49	29.048	6.610	27.802	7.071	26.604	7.551	25.451	8.049	24.340	8.567	**11**
50	29.027	6.618	27.782	7.079	26.584	7.559	25.432	8.058	24.322	8.575	**10**
51	29.006	6.625	27.762	7.087	26.565	7.567	25.413	8.066	24.304	8.584	**9**
52	28.985	6.633	27.741	7.095	26.545	7.575	25.394	8.075	24.286	8.593	**8**
53	28.964	6.640	27.721	7.103	26.526	7.584	25.375	8.083	24.267	8.602	**7**
54	28.942	6.648	27.701	7.111	26.506	7.592	25.356	8.092	24.249	8.611	**6**
55	28.921	6.656	27.680	7.119	26.487	7.600	25.338	8.100	24.231	8.619	**5**
56	28.900	6.663	27.660	7.126	26.467	7.608	25.319	8.109	24.213	8.628	**4**
57	28.879	6.671	27.640	7.134	26.448	7.616	25.300	8.117	24.195	8.637	**3**
58	28.858	6.678	27.620	7.142	26.428	7.624	25.281	8.126	24.177	8.646	**2**
59	28.837	6.686	27.599	7.150	26.409	7.633	25.263	8.134	24.159	8.655	**1**
60′	28.816	6.693	27.579	7.158	26.389	7.641	25.244	8.143	24.141	8.664	**0′**
	149°	**59°**	**148°**	**58°**	**147°**	**57°**	**146°**	**56°**	**145°**	**55°**	**→**
	329°	239°	328°	238°	327°	237°	326°	236°	325°	235°	**→**

←	215°	305°	216°	306°	217°	307°	218°	308°	219°	309°	
←	**35°**	**125°**	**36°**	**126°**	**37°**	**127°**	**38°**	**128°**	**39°**	**129°**	
0′	24.141	8.664	23.078	9.204	22.054	9.765	21.066	10.347	20.113	10.950	**60′**
1	24.123	8.672	23.061	9.213	22.037	9.775	21.050	10.357	20.097	10.960	**59**
2	24.105	8.681	23.043	9.223	22.020	9.784	21.034	10.367	20.082	10.970	**58**
3	24.087	8.690	23.026	9.232	22.003	9.794	21.017	10.376	20.066	10.980	**57**
4	24.069	8.699	23.009	9.241	21.987	9.803	21.001	10.386	20.051	10.991	**56**
5	24.051	8.708	22.991	9.250	21.970	9.813	20.985	10.396	20.035	11.001	**55**
6	24.033	8.717	22.974	9.259	21.953	9.822	20.969	10.406	20.019	11.011	**54**
7	24.015	8.726	22.957	9.269	21.937	9.832	20.953	10.416	20.004	11.021	**53**
8	23.997	8.734	22.939	9.278	21.920	9.841	20.937	10.426	19.988	11.032	**52**
9	23.979	8.743	22.922	9.287	21.903	9.851	20.921	10.436	19.973	11.042	**51**
10	23.961	8.752	22.905	9.296	21.887	9.861	20.905	10.446	19.957	11.052	**50**
11	23.943	8.761	22.888	9.306	21.870	9.870	20.889	10.456	19.942	11.063	**49**
12	23.925	8.770	22.870	9.315	21.853	9.880	20.872	10.466	19.926	11.073	**48**
13	23.907	8.779	22.853	9.324	21.837	9.889	20.856	10.476	19.911	11.083	**47**
14	23.889	8.788	22.836	9.333	21.820	9.899	20.840	10.486	19.895	11.094	**46**
15	23.872	8.797	22.819	9.343	21.803	9.909	20.824	10.495	19.880	11.104	**45**
16	23.854	8.806	22.801	9.352	21.787	9.918	20.808	10.505	19.864	11.114	**44**
17	23.836	8.815	22.784	9.361	21.770	9.928	20.792	10.515	19.849	11.125	**43**
18	23.818	8.824	22.767	9.370	21.754	9.937	20.776	10.525	19.834	11.135	**42**
19	23.800	8.833	22.750	9.380	21.737	9.947	20.760	10.535	19.818	11.145	**41**
20	23.782	8.842	22.733	9.389	21.720	9.957	20.744	10.545	19.803	11.156	**40**
21	23.764	8.851	22.715	9.398	21.704	9.966	20.728	10.555	19.787	11.166	**39**
22	23.747	8.859	22.698	9.408	21.687	9.976	20.712	10.565	19.772	11.176	**38**
23	23.729	8.868	22.681	9.417	21.671	9.986	20.696	10.575	19.756	11.187	**37**
24	23.711	8.877	22.664	9.426	21.654	9.995	20.681	10.585	19.741	11.197	**36**
25	23.693	8.886	22.647	9.435	21.638	10.005	20.665	10.595	19.726	11.207	**35**
26	23.676	8.895	22.630	9.445	21.621	10.015	20.649	10.605	19.710	11.218	**34**
27	23.658	8.904	22.613	9.454	21.605	10.024	20.633	10.615	19.695	11.228	**33**
28	23.640	8.913	22.595	9.463	21.588	10.034	20.617	10.625	19.680	11.239	**32**
29	23.622	8.922	22.578	9.473	21.572	10.044	20.601	10.635	19.664	11.249	**31**
30	23.605	8.931	22.561	9.482	21.555	10.053	20.585	10.646	19.649	11.259	**30**
31	23.587	8.940	22.544	9.491	21.539	10.063	20.569	10.656	19.634	11.270	**29**
32	23.569	8.949	22.527	9.501	21.522	10.073	20.553	10.666	19.618	11.280	**28**
33	23.552	8.958	22.510	9.510	21.506	10.082	20.537	10.676	19.603	11.291	**27**
34	23.534	8.967	22.493	9.520	21.490	10.092	20.522	10.686	19.588	11.301	**26**
35	23.516	8.977	22.476	9.529	21.473	10.102	20.506	10.696	19.572	11.312	**25**
36	23.499	8.986	22.459	9.538	21.457	10.112	20.490	10.706	19.557	11.322	**24**
37	23.481	8.995	22.442	9.548	21.440	10.121	20.474	10.716	19.542	11.332	**23**
38	23.463	9.004	22.425	9.557	21.424	10.131	20.458	10.726	19.527	11.343	**22**
39	23.446	9.013	22.408	9.566	21.408	10.141	20.443	10.736	19.511	11.353	**21**
40	23.428	9.022	22.391	9.576	21.391	10.151	20.427	10.746	19.496	11.364	**20**
41	23.410	9.031	22.374	9.585	21.375	10.160	20.411	10.756	19.481	11.374	**19**
42	23.393	9.040	22.357	9.595	21.358	10.170	20.395	10.767	19.466	11.385	**18**
43	23.375	9.049	22.340	9.604	21.342	10.180	20.379	10.777	19.451	11.395	**17**
44	23.358	9.058	22.323	9.614	21.326	10.190	20.364	10.787	19.435	11.406	**16**
45	23.340	9.067	22.306	9.623	21.309	10.199	20.348	10.797	19.420	11.416	**15**
46	23.323	9.076	22.289	9.632	21.293	10.209	20.332	10.807	19.405	11.427	**14**
47	23.305	9.085	22.273	9.642	21.277	10.219	20.316	10.817	19.390	11.437	**13**
48	23.288	9.094	22.256	9.651	21.261	10.229	20.301	10.827	19.375	11.448	**12**
49	23.270	9.104	22.239	9.661	21.244	10.239	20.285	10.838	19.359	11.458	**11**
50	23.253	9.113	22.222	9.670	21.228	10.248	20.269	10.848	19.344	11.469	**10**
51	23.235	9.122	22.205	9.680	21.212	10.258	20.254	10.858	19.329	11.479	**9**
52	23.218	9.131	22.188	9.689	21.196	10.268	20.238	10.868	19.314	11.490	**8**
53	23.200	9.140	22.171	9.699	21.179	10.278	20.222	10.878	19.299	11.501	**7**
54	23.183	9.149	22.155	9.708	21.163	10.288	20.207	10.888	19.284	11.511	**6**
55	23.165	9.158	22.138	9.718	21.147	10.297	20.191	10.899	19.269	11.522	**5**
56	23.148	9.168	22.121	9.727	21.131	10.307	20.175	10.909	19.254	11.532	**4**
57	23.130	9.177	22.104	9.737	21.114	10.317	20.160	10.919	19.238	11.543	**3**
58	23.113	9.186	22.087	9.746	21.098	10.327	20.144	10.929	19.223	11.553	**2**
59	23.096	9.195	22.070	9.756	21.082	10.337	20.128	10.939	19.208	11.564	**1**
60′	23.078	9.204	22.054	9.765	21.066	10.347	20.113	10.950	19.193	11.575	**0′**
	144°	**54°**	**143°**	**53°**	**142°**	**52°**	**141°**	**51°**	**140°**	**50°**	→
	324°	234°	323°	233°	322°	232°	321°	231°	320°	230°	→

←	220°	310°	221°	311°	222°	312°	223°	313°	224°	314°	
←	**40°**	**130°**	**41°**	**131°**	**42°**	**132°**	**43°**	**133°**	**44°**	**134°**	
0′	19.193	11.575	18.306	12.222	17.449	12.893	16.622	13.587	15.823	14.307	**60′**
1	19.178	11.585	18.291	12.233	17.435	12.904	16.608	13.599	15.810	14.319	**59**
2	19.163	11.596	18.277	12.244	17.421	12.915	16.595	13.611	15.797	14.331	**58**
3	19.148	11.606	18.262	12.255	17.407	12.927	16.581	13.623	15.784	14.343	**57**
4	19.133	11.617	18.248	12.266	17.393	12.938	16.568	13.634	15.771	14.355	**56**
5	19.118	11.628	18.233	12.277	17.379	12.950	16.554	13.646	15.758	14.368	**55**
6	19.103	11.638	18.219	12.288	17.365	12.961	16.541	13.658	15.745	14.380	**54**
7	19.088	11.649	18.204	12.299	17.351	12.972	16.527	13.670	15.732	14.392	**53**
8	19.073	11.660	18.190	12.310	17.337	12.984	16.514	13.682	15.718	14.404	**52**
9	19.058	11.670	18.175	12.321	17.323	12.995	16.500	13.694	15.705	14.417	**51**
10	19.043	11.681	18.161	12.332	17.309	13.007	16.487	13.705	15.692	14.429	**50**
11	19.028	11.692	18.146	12.343	17.295	13.018	16.473	13.717	15.679	14.441	**49**
12	19.013	11.702	18.132	12.354	17.281	13.030	16.460	13.729	15.666	14.453	**48**
13	18.998	11.713	18.118	12.365	17.267	13.041	16.446	13.741	15.653	14.466	**47**
14	18.983	11.724	18.103	12.376	17.253	13.053	16.433	13.753	15.640	14.478	**46**
15	18.968	11.734	18.089	12.387	17.239	13.064	16.419	13.765	15.628	14.490	**45**
16	18.954	11.745	18.074	12.399	17.225	13.075	16.406	13.777	15.615	14.503	**44**
17	18.939	11.756	18.060	12.410	17.212	13.087	16.393	13.788	15.602	14.515	**43**
18	18.924	11.766	18.046	12.421	17.198	13.098	16.379	13.800	15.589	14.527	**42**
19	18.909	11.777	18.031	12.432	17.184	13.110	16.366	13.812	15.576	14.540	**41**
20	18.894	11.788	18.017	12.443	17.170	13.121	16.352	13.824	15.563	14.552	**40**
21	18.879	11.799	18.002	12.454	17.156	13.133	16.339	13.836	15.550	14.564	**39**
22	18.864	11.809	17.988	12.465	17.142	13.144	16.326	13.848	15.537	14.577	**38**
23	18.849	11.820	17.974	12.476	17.128	13.156	16.312	13.860	15.524	14.589	**37**
24	18.834	11.831	17.959	12.487	17.115	13.168	16.299	13.872	15.511	14.601	**36**
25	18.820	11.842	17.945	12.499	17.101	13.179	16.285	13.884	15.498	14.614	**35**
26	18.805	11.852	17.931	12.510	17.087	13.191	16.272	13.896	15.485	14.626	**34**
27	18.790	11.863	17.916	12.521	17.073	13.202	16.259	13.908	15.472	14.639	**33**
28	18.775	11.874	17.902	12.532	17.059	13.214	16.245	13.920	15.460	14.651	**32**
29	18.760	11.885	17.888	12.543	17.045	13.225	16.232	13.932	15.447	14.663	**31**
30	18.746	11.895	17.874	12.554	17.032	13.237	16.219	13.944	15.434	14.676	**30**
31	18.731	11.906	17.859	12.566	17.018	13.248	16.206	13.956	15.421	14.688	**29**
32	18.716	11.917	17.845	12.577	17.004	13.260	16.192	13.968	15.408	14.701	**28**
33	18.701	11.928	17.831	12.588	16.990	13.272	16.179	13.980	15.395	14.713	**27**
34	18.686	11.939	17.817	12.599	16.977	13.283	16.166	13.992	15.382	14.725	**26**
35	18.672	11.949	17.802	12.610	16.963	13.295	16.152	14.004	15.370	14.738	**25**
36	18.657	11.960	17.788	12.622	16.949	13.306	16.139	14.016	15.357	14.750	**24**
37	18.642	11.971	17.774	12.633	16.935	13.318	16.126	14.028	15.344	14.763	**23**
38	18.628	11.982	17.760	12.644	16.922	13.330	16.113	14.040	15.331	14.775	**22**
39	18.613	11.993	17.745	12.655	16.908	13.341	16.099	14.052	15.318	14.788	**21**
40	18.598	12.004	17.731	12.666	16.894	13.353	16.086	14.064	15.306	14.800	**20**
41	18.583	12.014	17.717	12.678	16.881	13.365	16.073	14.076	15.293	14.813	**19**
42	18.569	12.025	17.703	12.689	16.867	13.376	16.060	14.088	15.280	14.825	**18**
43	18.554	12.036	17.689	12.700	16.853	13.388	16.046	14.100	15.267	14.838	**17**
44	18.539	12.047	17.674	12.711	16.839	13.400	16.033	14.112	15.255	14.850	**16**
45	18.525	12.058	17.660	12.723	16.826	13.411	16.020	14.124	15.242	14.863	**15**
46	18.510	12.069	17.646	12.734	16.812	13.423	16.007	14.136	15.229	14.875	**14**
47	18.495	12.080	17.632	12.745	16.798	13.435	15.994	14.149	15.216	14.888	**13**
48	18.481	12.091	17.618	12.757	16.785	13.446	15.980	14.161	15.204	14.900	**12**
49	18.466	12.102	17.604	12.768	16.771	13.458	15.967	14.173	15.191	14.913	**11**
50	18.451	12.112	17.590	12.779	16.758	13.470	15.954	14.185	15.178	14.926	**10**
51	18.437	12.123	17.576	12.791	16.744	13.481	15.941	14.197	15.166	14.938	**9**
52	18.422	12.134	17.561	12.802	16.730	13.493	15.928	14.209	15.153	14.951	**8**
53	18.408	12.145	17.547	12.813	16.717	13.505	15.915	14.221	15.140	14.963	**7**
54	18.393	12.156	17.533	12.825	16.703	13.517	15.902	14.233	15.127	14.976	**6**
55	18.379	12.167	17.519	12.836	16.690	13.528	15.888	14.246	15.115	14.988	**5**
56	18.364	12.178	17.505	12.847	16.676	13.540	15.875	14.258	15.102	15.001	**4**
57	18.349	12.189	17.491	12.859	16.662	13.552	15.862	14.270	15.089	15.014	**3**
58	18.335	12.200	17.477	12.870	16.649	13.564	15.849	14.282	15.077	15.026	**2**
59	18.320	12.211	17.463	12.881	16.635	13.575	15.836	14.294	15.064	15.039	**1**
60′	18.306	12.222	17.449	12.893	16.622	13.587	15.823	14.307	15.052	15.051	**0′**
	139°	**49°**	**138°**	**48°**	**137°**	**47°**	**136°**	**46°**	**135°**	**45°**	→
	319°	229°	318°	228°	317°	227°	316°	226°	315°	225°	→

Appendix

The Intercept


LINE OF POSITION METHODS
INTERCEPT FROM CALCULATED ALTITUDE
Near or far object, in the short distances of Doffset the light is more or less parallel
Assumed Position
Hc
Ho
(Ho-Hc)
Doffset (+)
Intercept Point
LOP perpendicular to the page at this point
Assumed Longitude
INTERCEPT DETAILS
Assumed LOP
Assumed Latitude
Bearing of Heavenly Object
DR Point
Intercept Point
INTERCEPT LOP
Doffset (+)
Observed Circle of Constant Altitude
Calculated Circle of Constant Altitude
Assumed Latitude
Circle of Constant Altitude Calculated
Assumed Longitude
Azimuth direction (Bearing) of Heavenly Object
Circle of Constant Altitude Observed
Geographical center of Heavenly Object
GP

Microsoft

Second Edition


No. 186
DRILL & WIRE GAUGE
DECIMAL EQUIVALENTS

Microsoft

ENCYCLOPEDIA of NETWORKING

Mitch Tulloch
Ingrid Tulloch

PUBLISHED BY
Microsoft Press
A Division of Microsoft Corporation
One Microsoft Way
Redmond, Washington 98052-6399

Copyright © 2002 by Microsoft Corporation

All rights reserved. No part of the contents of this book may be reproduced or transmitted in any form or by any means without the written permission of the publisher.

Library of Congress Cataloging-in-Publication Data
Tulloch, Mitch.
Microsoft Encyclopedia of Networking, Second Edition / Mitch Tulloch, Ingrid Tulloch.--2nd ed.
p. cm.
Includes index.
ISBN 0-7356-1378-8
1. Computer networks--Encyclopedias. I. Tulloch, Ingrid. II. Title.

TK5102 .T85 2002
004.6'03--dc21 2002020190

Printed and bound in the United States of America.

1 2 3 4 5 6 7 8 9 QWT 7 6 5 4 3 2

Distributed in Canada by Penguin Books Canada Limited.

A CIP catalogue record for this book is available from the British Library.

Microsoft Press books are available through booksellers and distributors worldwide. For further information about international editions, contact your local Microsoft Corporation office or contact Microsoft Press International directly at fax (425) 936-7329. Visit our Web site at www.microsoft.com/mspress. Send comments to *mspinput@microsoft.com*.

Active Desktop, Active Directory, ActiveX, Authenticode, BackOffice, bCentral, BizTalk, ClearType, DirectX, DriveSpace, Encarta, FoxPro, FrontPage, IntelliMirror, IntelliSense, JScript, Microsoft, Microsoft Press, MS-DOS, MSDN, MSN, NetMeeting, Outlook, PowerPoint, SharePoint, Visual Basic, Visual C++, Visual FoxPro, Visual InterDev, Visual J++, WebTV, Win32, Win64, Windows, and Windows NT are either registered trademarks or trademarks of Microsoft Corporation in the United States and/or other countries. Other product and company names mentioned herein may be the trademarks of their respective owners.

The example companies, organizations, products, domain names, e-mail addresses, logos, people, places, and events depicted herein are fictitious. No association with any real company, organization, product, domain name, e-mail address, logo, person, place, or event is intended or should be inferred.

Acquisitions Editor: Juliana Aldous Atkinson
Project Editor: Maureen Williams Zimmerman

Body Part No. X08-22423

Dedicated to our dear friends
Ken and Bonnie Lewis, who have
stuck by us through difficult times

Contents

Acknowledgments . . . . *xxxv*
Preface to the Second Edition . . . . *xxxvii*
Introduction . . . . *xxxix*
  What Is Networking? . . . . *xxxix*
  The History of Networking . . . . *xliii*
  The Scope of This Encyclopedia . . . . *lv*
  Who This Work Is For . . . . *lv*
  How This Work Is Organized . . . . *lv*
  Disclaimer . . . . *lvi*
  Comments and Questions . . . . *lvi*

Alphabetical Reference of Terms

Numbers and Symbols

1Base5 1
2B+D 1
2B1Q 1
2G 1
2.5G 1
3G 2
3.1 kHz bearer service 4
4G 4
5-4-3 rule 4
6bone 5
6to4 5
8mm 6
10Base2 6
10Base5 7
10BaseF 8
10BaseT 9
10GbE 10
10G Ethernet 10
24 x 7 14
64-bit architecture 14
64-bit Windows 15
80/20 rule 16
100BaseFX 16
100BaseT 17
100BaseT4 17
100BaseTX 18
100BaseVG 19
100BaseX 19
100VG-AnyLAN 19
568-A 21
568-B 21
802.1 22
802.1p 22
802.1Q 23
802.2 23
802.3 23
802.3ab 24
802.3ad 24
802.3ae 24
802.3af 24
802.3u 25
802.3z 25
802.4 25
802.5 25

802.6. 25
802.7 26
802.8 26
802.9 26
802.10 26
802.11 26
802.11a 27
802.11b 28
802.12 31
802.13 31
802.14 31
802.15 31
802.16 32
802.17 32
1000BaseCX 32
1000BaseLX 33
1000BaseSX 35
1000BaseT 35
1000BaseTX 37
1000BaseX 37
1394 37
1822 37
3270 37
5250 38

A

A+ Certification 39
A record 39
A6 record 39
AAA 40
AAAA record 40
AAL 40
AATP 40
Abilene 40
absolute path 41
Abstract Syntax Notation One (ASN.1) 41
acceptable use policy 42
access 42
access control 43
access control entry (ACE) 44
access control list (ACL) 44
Accessibility Options 45
Accessibility Wizard 46
access list 46
access mask 48
access method 48
access mode 49
access point (AP) 49
access provider 50
access token 50
account 51
account domain 51
account lockout 52
account operator 53
Account Operators group 53
ACE 53
ACK 53
ACL 54
ACM 54
ACPI 54
ACR 54
Active Desktop 54
Active Digital Profile (ADPr) 55
Active Directory. 55
Active Directory Client 58
Active Directory Domains and Trusts 58
Active Directory Installation Wizard 58
Active Directory schema 60
Active Directory Service Interfaces (ADSI) 60
Active Directory Sites and Services 61
Active Directory Users and Computers 62
active hub 62
active partition 62
Active Platform 63
active scripting 63
Active Server Pages (ASP) 63
Active Setup 64
active volume 65
active window 65
ActiveX 65
ActiveX component 65
ActiveX controls 66
ActiveX Data Objects (ADO) 66
adapter 67
adaptive acceleration 68
Adaptive Differential Pulse-Code
    Modulation (ADPCM) 68
ADC 68

address book view 69
address record 69
Address Resolution Protocol (ARP) 69
ADMD 70
ADMIN$ 70
administrative alert 70
Administrative Management Domain (ADMD) . . . 70
administrative share 70
administrative tools (Windows 2000, Windows XP, and Windows .NET Server) . . . 71
administrative tools (Windows NT) 71
administrator 72
Administrators group 72
ADO 73
ADO+ 73
ADO.NET 73
ADPCM 73
ADPr 73
ADR 73
ADSI 74
ADSL 74
ADSL modem 74
Advanced Configuration and Power Interface (ACPI) 74
Advanced Data Recording (ADR) 75
Advanced Encryption Standard (AES) 75
Advanced Infrared (AIr) 76
Advanced Intelligent Tape (AIT) 76
Advanced Mobile Phone Service (AMPS). 76
Advanced Peer-to-Peer Networking (APPN) 78
Advanced Power Management (APM) 78
Advanced Program-to-Program Communications (APPC) protocol 79
Advanced Streaming Format (ASF) 79
Advanced Technology Demonstration Network (ATDnet) 79
AES 80
AFTP 80
agent 80
AGLP 80
AH 81
AIM 81
AIr 81
Air Interface 81
AIT 82
AIX 82
Alerter service 82
alias 82
Always On/Dynamic ISDN (AO/DI) 83
Alpha platform 83
American National Standards Institute (ANSI) . . . 83
American Registry for Internet Numbers (ARIN) 84
AMP 84
AMPS 85
analog 85
analog modem 85
analog-to-digital converter (ADC) 85
analog transmission 86
anchor 86
announcement 86
Announcement Manager 87
anonymous access 87
anonymous user 87
ANSI 87
ANSI C/C++ 87
ANSI character set 88
answer file 88
antenna 88
Anycast 89
AO/DI 89
AOL Instant Messenger (AIM) 89
AP 90
Apache 90
Apache Software Foundation 91
Apache XML Project 91
API 91
APIPA 91
APM (Advanced Power Management) 92
APM (Application Performance Management) . . . 92
APNIC 92
APPC 92
APPC File Transfer Protocol (AFTP) 92
Apple Open Transport 92
AppleShare 93
AppleShare IP 93
applet 93
AppleTalk 94

appliance . . . 95
Application Center . . . 95
application layer . . . 95
application layer proxy . . . 96
application level gateway . . . 96
application log . . . 97
Application Performance Management (APM) . . . 97
application programming interface (API) . . . 98
application service provider (ASP) . . . 98
APPN . . . 101
archive attribute . . . 101
archiving . . . 101
ARCNET . . . 102
ARC path . . . 102
ARIN . . . 102
ARP . . . 103
ARPANET . . . 103
Arp command . . . 103
AS . . . 103
AS/400 . . . 103
ASCII . . . 104
ASCII file . . . 106
ASF . . . 106
Asia Pacific Network Information Center (APNIC) . . . 107
ASN . . . 107
ASN.1 . . . 107
ASP (Active Server Pages) . . . 107
ASP (application service provider) . . . 107
ASP.NET . . . 107
ASR . . . 108
Association for Computing Machinery (ACM) . . . 108
Asymmetric Digital Subscriber Line (ADSL) . . . 108
asymmetric multiprocessing (AMP) . . . 111
async . . . 111
Asynchronous Transfer Mode (ATM) . . . 111
asynchronous transmission . . . 116
ATDnet . . . 117
ATM . . . 117
ATM Adaptation Layer (AAL) . . . 117
ATM Forum . . . 117
ATM over SONET . . . 118
ATM/SONET . . . 118
attenuation . . . 118
attenuation to crosstalk ratio (ACR) . . . 119
attrib command . . . 119
attribute (file system) . . . 119
attribute (Active Directory) . . . 120
ATU-C . . . 120
ATU-R . . . 120
auditing . . . 121
Audit policy . . . 121
AUI connector . . . 121
Authenticated Users group . . . 122
Authentication Header (AH) . . . 122
authentication protocol . . . 122
authentication provider . . . 123
Authenticode . . . 123
Authorized Academic Training Provider (AATP) . . . 123
auto-application . . . 124
AutoComplete . . . 124
autodial . . . 124
automatic logon . . . 125
Automatic Private IP Addressing (APIPA) . . . 125
Automatic System Recovery (ASR) . . . 126
Automatic Version Synchronization (AVS) . . . 126
Automation . . . 126
Automation client . . . 126
Automation controller . . . 127
Automation server . . . 127
auto naming . . . 127
autonomous system (AS) . . . 127
autonomous system number (ASN) . . . 128
autosensing . . . 128
availability . . . 128
AVS . . . 129
AWG . . . 129
AXFR request . . . 129

B

B2B . . . 131
B2C . . . 134
backbone . . . 134
backboning . . . 135
background . . . 136
BackOffice . . . 137

BackOffice Server . . . 137
Back Orifice . . . 137
backup . . . 138
backup agent . . . 141
backup browser . . . 141
backup catalog . . . 141
backup domain controller (BDC) . . . 142
Backup Operator . . . 143
Backup Operators built-in group . . . 143
backup set . . . 144
backup strategy . . . 144
backup type . . . 145
Backup Wizard . . . 146
BACP . . . 146
balanced line . . . 146
balun . . . 147
bandwidth . . . 147
Bandwidth Allocation Control Protocol (BACP) . . . 148
Bandwidth Allocation Protocol (BAP) . . . 148
bandwidth on demand . . . 149
bandwidth throttling . . . 149
Banyan VINES . . . 150
BAP . . . 150
baseband transmission . . . 151
baseline . . . 151
Basic authentication . . . 151
basic disk . . . 152
Basic Rate Interface ISDN (BRI-ISDN) . . . 152
basic volume . . . 153
bastion host . . . 153
batch commands . . . 154
batch file . . . 155
bCentral . . . 155
B channel . . . 156
BDC . . . 156
beaconing . . . 156
BEEP . . . 157
benchmarking . . . 157
BeOS . . . 158
BER . . . 158
Berkeley Internet Name Domain (BIND) . . . 158
BERT . . . 158
best effort . . . 159
BGP . . . 159
Binary Runtime Environment for Wireless (BREW) . . . 159
Binary Tulloch Transport Protocol (BTTP) . . . 159
BIND . . . 160
bindery . . . 160
bindings . . . 160
biometric authentication . . . 161
B-ISDN . . . 161
Bit/Block Error Rate Tester (BERT) . . . 161
Bit Error Rate (BER) . . . 162
bits per second (bps) . . . 162
BizTalk . . . 162
BizTalk Framework . . . 163
BizTalk Server 2000 . . . 164
Blackcomb . . . 164
black hole . . . 165
BLEC . . . 165
block coding . . . 165
Blocks Extensible Exchange Protocol (BEEP) . . . 165
blue screen . . . 166
Bluetooth . . . 166
BNC connector . . . 170
B-node . . . 170
bonding . . . 171
boot . . . 172
boot files . . . 172
Boot.ini . . . 173
boot loader menu . . . 173
BOOTP . . . 174
boot partition . . . 174
boot process . . . 174
Bootsect.dos . . . 175
bootstrap protocol (BOOTP) . . . 175
boot volume . . . 176
Border Gateway Protocol (BGP) . . . 176
border router . . . 177
bottleneck . . . 178
bounce . . . 179
bps . . . 179
breakout box . . . 180
BREW . . . 180
bridge . . . 180
bridgehead server . . . 181
BRI-ISDN . . . 181
broadband . . . 181

broadband Internet access 182
broadband ISDN (B-ISDN) 183
broadband transmission 183
broadband wireless communications 184
broadcast domain 186
broadcast frame 186
broadcasting 186
broadcast packet 187
broadcast storm 187
brouter 188
browse list 188
browser (Computer Browser service) 188
browser (Web browser) 188
browsing 188
BSD 189
BSP 189
building-block services 189
Building-centric Local Exchange Carrier (BLEC) 190
built-in account 191
built-in domain local group 192
built-in global group 192
built-in group 192
built-in identities 193
burst 193
bus 193
business logic 195
business-to-business 195
business-to-consumer 195
bus topology 195

C

C++ 197
C# 197
C2 198
CA 199
cabinet 199
cabinet file 200
cable modem 200
cable run 202
cable tester 203
cabling 204
CA certificate 206
caching 206
Caching Array Routing Protocol (CARP) 210
caching-only name server 210
caching service provider (CSP) 211
CAL 211
callback 211
Callback Control Protocol (CBCP) 212
campus area network (CAN) 212
CAN 212
CAP 213
capture 213
capture window 213
Carnivore 213
CARP 214
carrier 214
carrierless amplitude and phase modulation (CAP) 215
Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA) 216
Carrier Sense Multiple Access with Collision Detection (CSMA/CD) 216
carrier signal 217
cascaded star topology 217
cascading style sheets (CSS) 217
Cat5 cabling 218
Cat5e cabling 218
Cat6 cabling 218
Cat7 cabling 218
catalog 218
Category 1 (Cat1) cabling 219
Category 2 (Cat2) cabling 219
Category 3 (Cat3) cabling 219
Category 4 (Cat4) cabling 220
Category 5 (Cat5) cabling 220
Category 6 (Cat6) cabling 221
Category 7 (Cat7) cabling 222
CBCP 223
CBQ 223
CBT 223
CDDI 223
CDE 223
CDF 223
CDF file 223
CDFS 224
CDMA 224

CDMA2000 224
cdmaOne 225
CDN 225
CDO 225
CDP 225
CDPD 225
CD-ROM File System (CDFS) 225
CDSL 226
cell (ATM) 226
cell (cellular communications) 227
Cellular Digital Packet Data (CDPD) 227
cellular communications 228
central office (CO) 231
Centrex 232
certificate 233
certificate authority (CA) 233
certificate mapping 234
certificate request 234
certificate revocation list (CRL) 235
Certified Technical Education Center (CTEC) . . . 235
CGI 235
Challenge Handshake Authentication
Protocol (CHAP) 235
challenge/response 236
Change and Configuration Management 237
channel (Active Channel) 237
channel bank 237
channel bar 238
Channel Definition Format (CDF) 238
channel (Microsoft Windows Media Player) 239
Channel Service Unit (CSU) 239
Channel Service Unit/Data
Service Unit (CSU/DSU) 240
CHAP 241
child domain 241
CICS 241
CIDR 241
CIFS 241
CIM 241
CIM Object Manager (CIMOM) 241
CIMOM 242
CIP 242
CIR 242
circuit 242
circuit layer proxy 242
circuit-level gateway 243
circuit-switched services 243
circular logging 245
class 245
Class A 245
Class B 246
class-based queuing (CBQ) 246
Class C 247
Class D 247
Class E 248
classful domain 248
classful routing protocol 248
Classical IP (CIP) 248
Classic desktop 249
classless domain 249
classless interdomain routing (CIDR) 250
classless routing protocol 251
CLB 252
cleartext 252
cleartext authentication 252
ClearType 252
CLEC 252
client 252
client access license (CAL) 253
client certificate 253
Client for Microsoft Networks 254
Client for NetWare Networks 254
client installation point 255
client/server 255
Client Services for NetWare (CSNW) 256
cloud 256
cluster 257
cluster-aware application 257
clustering 257
CMAK 259
CMP cabling 260
CN 260
CNAME record 260
CNRP 260
CO 260
coax 260
coaxial cabling 260
codec 261
Code Division Multiple Access (CDMA) 261
Coded Orthogonal Frequency
Division Multiplexing (COFDM). 263
code-operated switch 263

COFDM 264
cold boot. 264
Cold Fusion 265
Collaboration Data Objects (CDO) 265
collapsed backbone 265
collision 266
collision domain 266
COM 267
COM+ 267
COM component object 267
command 268
command interpreter 269
command line 269
command prompt 269
Commerce Server 2000 270
commercial service provider (CSP) 270
Committed Information Rate (CIR) 270
Common Desktop Environment (CDE) 270
Common Gateway Interface (CGI) 271
Common Information Model (CIM) 272
Common Internet File System (CIFS) 273
Common Name Resolution Protocol (CNRP) . . . 273
Common Object Request Broker
Architecture (CORBA) 274
community 275
Competitive Local Exchange Carrier (CLEC) . . . 275
complete trust model 278
Component Load Balancing (CLB) 278
Component Object Model (COM) 279
CompTIA 281
computer account 281
Computer Browser service 281
Computer Management 283
computer name 283
computer-telephony integration (CTI) 284
Computing Technology Industry
Association (CompTIA) 284
COMTI 284
COM Transaction Integrator (COMTI) 284
concurrency 285
connected network (CN) 285
connection 285
connectionless protocol 285
Connection Manager Administration Kit (CMAK) 286
connection-oriented protocol 286
connection pooling 287
connectivity server 287
connector (device) 287
Connector for Lotus cc:Mail 289
Connector for Lotus Notes 289
connector (Microsoft Exchange) 289
Consumer DSL (CDSL) 290
container (Active Directory) 290
container (Microsoft Management Console) 290
container (NTFS) 290
Content Advisor 291
Content Analyzer 291
content caching 291
content delivery network (CDN) 292
Content Delivery Provider (CDP) 293
content filter 294
contention 294
content rating 294
control message 294
Control Panel 295
control set 297
convergence 297
cookie 297
copper cabling 298
Copper Distributed Data Interface (CDDI) 298
copy backup 299
copying files 299
CORBA 299
Core-Based Trees (CBT) 299
counter 300
country code 300
coupler 302
CPE 302
CRC 302
Creator Owner 302
credentials 302
crimper 303
CRL 303
CRM 303
crossover cable 303
crosstalk 304
CryptoAPI 304
Cryptographic Message Syntax Standard 304
cryptography 305
CSMA/CA 305

CSMA/CD 305
CSNW 305
CSP (caching service provider) 305
CSP (commercial service provider) 306
CSS 306
CSU 306
CSU/DSU 306
.csv file 306
CTEC 306
CTI 306
Ctrl+Alt+Delete 306
custom authentication 307
Customer Information Control System (CICS) . . . 307
customer premises 307
customer premises equipment (CPE) 307
Customer Relationship Management (CRM) 308
custom recipient 308
cyclical redundancy check (CRC) 308

D

DAB 309
DACL 309
daemon 309
daily copy 309
D-AMPS 310
DAO 310
DAP 310
dark fiber 310
Data Access Objects (DAO) 311
data alarm 311
database 312
database owner (DBO) 313
data communications equipment (DCE) 313
Data Encryption Standard (DES) 314
datagram 315
data integrity 315
data isolator 315
data line protector 316
Data Link Control (DLC) 316
data-link layer 317
Data Manipulation Language (DML) 318
Data Over Cable Interface
Specification (DOCSIS) 318
Data Provider 319
Data Service Unit (DSU) 320
data source name (DSN) 320
Data Space Transfer Protocol (DSTP) 321
data tap 321
data terminal equipment (DTE) 322
DAWS 323
DB connector 323
DBO 323
DCE 323
D channel 324
DCOM 324
DCOM Configuration Tool 324
DDNS 325
DDoS 325
DDR (Demand-Dial Routing) 325
DDR (Dial-on-Demand Routing) 325
DDS (digital data service) 325
DDS (Digital Data Storage) 325
dead spot 325
decibel 326
DECnet 326
dedicated line 327
Dedicated Token Ring (DTR) 327
default gateway 327
Defense Messaging System (DMS) 328
defragmentation 328
delegation 329
Delegation of Control Wizard 330
Demand-Dial Routing (DDR) 330
demand priority 330
demarc 331
demilitarized zone (DMZ) 332
DEN 332
denial of service (DoS) 332
dense mode 334
dense wavelength division multiplexing
(DWDM) 335
DES 335
desktop 336
Desktop Management Interface (DMI) 336
destination address 337
device 337
Dfs 337
DHCP 337

DHCP client 338
DHCP client reservation 338
DHCP Client service 338
DHCP console 339
DHCP lease 339
DHCP options 340
DHCP relay agent 340
DHCP scope 341
DHCP server 341
DHCP Server service 342
DHTML 342
Dial-on-Demand Routing (DDR) 342
dial-up line 343
DID 343
differential backup 343
Differentiated Services (DS) 344
Diffie-Hellman (DH) 344
digital 344
Digital Advanced Mobile Phone
Service (D-AMPS) 344
Digital Advanced Wireless System (DAWS) 345
Digital Audio Broadcasting (DAB) 345
digital certificate 346
digital dashboard 347
digital data service (DDS) 347
Digital Data Storage (DDS) 348
digital line 349
Digital Linear Tape (DLT) 349
digital modem 349
digital nervous system 349
Digital Signal Zero 350
digital signature 350
Digital Subscriber Line (DSL) 352
Digital Subscriber Line Access
Multiplexer (DSLAM) 357
digital transmission 357
DIME 358
direct burial fiber-optic cabling 358
Direct Cable Connection 359
directed frame 359
directed packet 359
Direct Internet Message Encapsulation
(DIME) 359
direct inward dialing (DID) 360
directory 360
Directory Access Protocol (DAP) 362
directory database 363
Directory Enabled Network (DEN) 363
directory export 364
directory hierarchy 364
directory import 365
directory replication (Windows 2000
and Windows .NET Server) 365
directory replication (Windows NT) 366
directory service log 367
Directory Service Manager for NetWare
(DSMN) 367
Directory Service Markup Language (DSML) . . . 367
Directory Service Migration Tool (DSMigrate) . . 368
directory synchronization (Microsoft Mail) 368
directory synchronization (Windows NT) 368
Direct Sequence Spread Spectrum (DSSS) 369
direct sequencing 369
disaster recovery 369
discrete multitone (DMT) 371
discretionary access control list (DACL) 371
disk duplexing 372
disk imaging 372
disk mirroring 373
Diskperf command 373
disk quotas 374
disk status 375
Distance Vector Multicast Routing
Protocol (DVMRP) 375
distance vector routing algorithm 376
distance vector routing protocol 377
distinguished name (DN) 377
distributed application 378
Distributed Component Object Model
(DCOM) 378
distributed computing 379
Distributed Denial of Service (DDoS) 380
Distributed file system (Dfs) 381
Distributed Management Task Force (DMTF) . . . 382
distribution box 382
distribution group 383
distribution list 383
distribution server 383
DLC 383
DLL 383

DLT . . . 383
DMI . . . 383
DML . . . 383
DMS . . . 384
DMT . . . 384
DMTF . . . 384
DMZ . . . 384
DN . . . 384
DNA . . . 384
DNS . . . 384
DNS client . . . 384
DNS console . . . 384
DNS database . . . 385
DNS namespace . . . 385
DNS query . . . 386
DNSSEC . . . 386
DNS Security Extensions (DNSSEC) . . . 386
DNS server . . . 388
DOCSIS . . . 388
Document Object Model (DOM) . . . 389
document type definition (DTD) . . . 389
DoD model . . . 389
DOM . . . 390
Domain Admins . . . 390
domain blocking . . . 390
domain controller . . . 391
domain (DNS) . . . 392
domain forest . . . 392
Domain Guests . . . 393
domain local group . . . 393
domain master browser . . . 394
domain (Microsoft Windows) . . . 394
domain model . . . 395
domain modes . . . 396
domain name . . . 396
Domain Name System (DNS) . . . 397
domain tree . . . 400
domain user account . . . 401
Domain Users . . . 401
DoS . . . 401
DOS . . . 402
down . . . 402
drain wire . . . 402
drop . . . 402
drop cable . . . 402
Dr. Watson . . . 402
DS . . . 403
DS-0 . . . 403
DS-1 . . . 403
DS-3 . . . 404
DSL . . . 405
DSLAM . . . 405
DSMigrate . . . 405
DSML . . . 405
DSMN . . . 405
DSN . . . 405
DSSS . . . 405
DSTP . . . 405
DSU . . . 405
DTD . . . 405
DTE . . . 405
DTMF . . . 406
DTR . . . 406
dual boot . . . 406
Dual Tone Multiple Frequency (DTMF) . . . 406
duplex . . . 406
DVMRP . . . 407
DWDM . . . 407
dynamic disk . . . 407
dynamic DNS (DDNS) . . . 407
Dynamic Host Configuration Protocol (DHCP) . . . 408
Dynamic HTML (DHTML) . . . 410
dynamic-link library (DLL) . . . 410
dynamic packet filtering . . . 410
dynamic routing . . . 411
dynamic routing protocol . . . 411
dynamic volume . . . 412

E

EAP . . . 413
EBGP . . . 413
e-business . . . 413
ebXML . . . 413
E-carrier . . . 413
EDGAR . . . 414
EDGE . . . 415
edge router . . . 415

EDI 415
eDirectory 415
effective permissions 416
EFI 416
EFS 416
EGP (exterior gateway protocol) 416
EGP (Exterior Gateway Protocol) 416
EIA 416
EIA/TIA wiring standards 417
EIGRP 417
EIP 417
EJB 417
EKP 417
election 417
electromagnetic interference (EMI) 418
Electronic Business Extensible Markup Language (ebXML) 418
Electronic Data Gathering, Analysis, and Retrieval 419
electronic data interchange (EDI) 419
Electronic Industries Alliance (EIA) 421
electronic tape vaulting 422
e-mail 422
e-mail address 425
embedded system 425
Emergency Management Services (EMS) 426
emergency repair disk (ERD) 427
emergency startup disk 427
EMI 428
EMS 428
emulation 428
Encapsulating Security Payload (ESP) 428
encapsulation 428
Encrypting File System (EFS) 429
encryption 430
encryption algorithm 432
End-User License Agreement (EULA) 433
enhanced Category 5 (Cat5e) cabling 433
Enhanced Data Rates for Global Evolution (EDGE) 433
Enhanced Interior Gateway Routing Protocol (EIGRP) 434
enterprise 435
Enterprise Admins 436
Enterprise Information Portal (EIP) 436
Enterprise Java Beans (EJB) 437
Enterprise Knowledge Portal (EKP) 437
enterprise resource planning (ERP) 438
enterprise server 439
environmental subsystems 440
environment variables 440
ERD 441
ERP 441
ESMTP 441
ESP 441
EtherLEC 441
Ethernet 441
Ethernet address 444
Ethernet Industrial Protocol (Ethernet/IP) 444
Ethernet/IP 445
Ethernet switch 445
ETRN 449
EULA 449
e-vaulting 449
event 449
Everyone group 450
Exchange Server 450
experience 451
extended partition 452
Extended Turn (ETRN) 452
extender 452
Extensible Authentication Protocol (EAP) 453
Extensible Firmware Interface (EFI) 453
Extensible Markup Language (XML) 454
extension cable 454
Exterior Border Gateway Protocol (EBGP) 454
exterior gateway protocol (EGP) 454
Exterior Gateway Protocol (EGP) 455
exterior routing protocol 456
extranet 456

F

failback 459
failover 459
fallback switch 460
FAQ 461
Fast Ethernet 461
FAT 463

FAT32 . . . 464
FAT volume . . . 464
fault tolerance. . . 465
FCC . . . 465
FDDI . . . 465
FDDI token passing . . . 465
FDM . . . 465
FDMA . . . 465
Federal Communications Commission (FCC) . . . 465
Federal Information Processing Standard (FIPS) . . . 466
FHSS . . . 466
Fiber Distributed Data Interface (FDDI) . . . 466
fiber exhaust . . . 469
fiber-optic cabling . . . 469
fiber to the curb (FTTC) . . . 473
Fibre Channel . . . 474
file . . . 476
file allocation table (FAT) . . . 476
File and Printer Sharing for Microsoft Networks . . . 477
File and Printer Sharing for NetWare Networks . . . 478
File and Print Services for Macintosh (FSM) . . . 478
File and Print Services for NetWare (FPNW) . . . 478
file extension . . . 479
file permissions . . . 480
file system . . . 481
File-Transfer Access and Management (FTAM) . . . 482
File Transfer Protocol (FTP) . . . 482
Find . . . 483
finger . . . 484
FIPS . . . 484
firewall . . . 484
FireWire . . . 489
flapping . . . 490
flexible single-master operation (FSMO) . . . 490
flooding . . . 490
flow control . . . 491
folder permissions . . . 491
foreign host . . . 492
foreign mail system . . . 493
forest . . . 493
form . . . 493
forwarder . . . 493
FORTEZZA . . . 494
FPNW . . . 494
FQDN . . . 494
fractional T1 . . . 494
FRAD . . . 495
frame . . . 495
frame relay . . . 495
Frame Relay Access Device (FRAD) . . . 502
frame relay cloud . . . 502
frame tagging . . . 503
frame type . . . 503
Free Space Optics (FSO) . . . 503
Frequency Division Multiple Access (FDMA) . . . 504
frequency-division multiplexing (FDM) . . . 505
frequency hopping . . . 505
Frequency Hopping Spread Spectrum (FHSS) . . . 506
frequently asked questions (FAQ) . . . 507
FSM . . . 507
FSMO . . . 507
FSO . . . 507
FTAM . . . 507
FTP . . . 507
FTP service . . . 507
FTTC . . . 508
full backup . . . 508
full-duplex . . . 508
full-duplex Ethernet . . . 508
fully qualified domain name (FQDN) . . . 510
Fusion . . . 510

G

G.703 . . . 511
gateway . . . 511
Gateway Service for NetWare (GSNW) . . . 512
GbE . . . 513
GBIC . . . 513
gender changer . . . 513
General Packet Radio Service (GPRS) . . . 514
Gigabit Ethernet (GbE) . . . 516
Gigabit Interface Converter (GBIC) . . . 521
G.Lite . . . 522

Global.asa 522
global catalog 523
global catalog server 524
global group 524
global load balancer 524
globally unique identifier (GUID) 526
Global System for Mobile Communications (GSM). 526
global user account 529
GNOME 530
GNU General Public License (GPL) 530
GNU Object Modeling Environment (GNOME) 530
Gopher 530
GPL 531
GPRS 531
grep. 531
ground loop 532
group 532
group account 535
Group Policy 535
GSM 536
GSNW 536
Guest account 536
Guests group 536
GUID 536

H

H.323 537
H.323 gateway 538
hacking 539
Hailstorm 540
HAL 541
half-duplex 541
HAN 542
handheld 542
Handheld Device Markup Language (HDML) . . . 542
handshaking 543
hardware abstraction layer (HAL) 544
hardware address 545
Hardware Compatibility List (HCL) 545
hardware profile 545
hashing algorithm 546
HBA 546
H channel 546
HCL 546
HDLC 547
HDML 547
HDSL 547
header 547
heartbeat 547
Help 547
heterogeneous network 548
hidden share 548
Hierarchical Storage Management (HSM) 549
High-bit-rate Digital Subscriber Line (HDSL) . . . 550
High-level Data Link Control (HDLC) 552
High Performance File System (HPFS) 553
High-Performance Parallel Interface (HIPPI) 553
High-Speed Circuit Switched Data (HSCSD) 554
High-Speed Serial Interface (HSSI) 555
High-Speed Token Ring (HSTR) 555
HiperLAN/2 555
HIPPI 556
History 556
hive 557
H-node 557
home area network (HAN). 558
home folder 559
HomeRF 559
homogeneous network 560
honey pot 561
hood 562
hop count 562
horizontal cabling. 563
host 565
host bus adapter (HBA) 565
Host Data Replicator 565
host header names 566
host ID 566
Host Integration Server 566
host name 567
host name resolution 567
host routing 568
hosts file 569
hot. 570
hotfix 570
Hot Standby Router Protocol (HSRP) 570

HPFS 571
HP-UX 571
HSCSD 571
HSM 572
HSRP 572
HSSI 572
HSTR 572
HTML 572
HTMLA 572
HTML-based administration (HTMLA) 572
HTML Extension (HTX) 572
HTTP 573
HTTP Keep-Alives 573
HTTPS 573
HTTP status codes 573
HTX 574
hub 574
HybridAuth 577
HyperTerminal 577
Hypertext Markup Language (HTML) 577
Hypertext Transfer Protocol (HTTP) 579

I

I2O 581
IAB 581
IAD 581
IANA 581
IB 581
IBGP 581
ICA 581
iCal 581
ICANN 582
ICF 582
ICMP 582
ICMP Traceback Messages 582
ICP (integrated communications provider) 583
ICP (Internet Cache Protocol) 583
ICQ 583
IDS 583
IDSL 583
IE 583
IEAK 584
IEEE 584
IEEE 488 584
IEEE 802 standards 584
IEEE 1284 584
IEEE 1394 585
IETF 585
iFS 585
IGMP 585
IGP 585
IGRP. 586
IIOP 586
IIS. 586
IIS Object Cache 586
IISP 586
IKE 586
IL 586
ILEC 586
ILS 586
IM 587
IMA 587
IMAP4 587
i-mode 587
impedance 587
impersonation 587
IMT-2000 588
IMUX 588
in-addr.arpa 588
in-band signaling 588
incremental backup 589
incremental zone transfer 589
Incumbent Local Exchange Carrier (ILEC). 590
Independent Computing Architecture (ICA) 591
index 592
Infiniband (IB) 592
Infrared Data Association (IrDA) 594
infrared transmission 594
infrastructure 595
inheritance 595
INI files 596
instance 596
instant messaging (IM) 596
Institute of Electrical and
    Electronics Engineers (IEEE) 598
Integrated Access Device (IAD) 599
integrated communications provider (ICP) 599

Integrated Services Digital Network (ISDN) 600
Integrated Windows Authentication 605
Intel-based platform 605
intelligent hub.............................. 605
Intelligent Input/Output (I2O) 605
IntelliMirror 606
Interactive................................... 606
interactive logon 606
inter-exchange carrier (IXC) 607
interface 608
interface card 609
interface converter 609
interference 610
Interim Interswitch Signaling Protocol (IISP) ... 610
Interior Border Gateway Protocol (IBGP) 611
interior gateway protocol (IGP) 611
Interior Gateway Routing Protocol (IGRP) 611
interior routing protocol 612
intermediary device 612
Intermediate Language (IL) 613
International Mobile
Telecommunications-2000 (IMT-2000) 613
International Organization for
Standardization (ISO) 614
International Telecommunication Union (ITU) .. 615
Internet 615
Internet2 617
Internet access 617
Internet Architecture Board (IAB) 618
Internet Assigned Numbers Authority (IANA) ... 618
Internet Cache Protocol (ICP) 619
Internet Connection Firewall (ICF) 619
Internet Control Message Protocol (ICMP) 620
Internet Corporation for Assigned
Names and Numbers (ICANN) 621
Internet Engineering Task Force (IETF) 621
Internet Explorer 622
Internet Explorer Administration Kit (IEAK) 622
Internet File System (iFS) 623
Internet Group Management Protocol (IGMP) ... 623
Internet guest account 624
Internet Information Services (IIS) 625
Internet Inter-Orb Protocol (IIOP) 626
Internet Key Exchange (IKE) 626
Internet Locator Service (ILS) 626
Internet Mail Access Protocol
version 4 (IMAP4) 627
Internet Printing Protocol (IPP) 628
Internet Protocol (IP) 628
Internet protocols 629
Internet Protocol Security (IPsec) 630
Internet Relay Chat (IRC) 631
Internet Research Task Force (IRTF) 632
Internet Security and Acceleration
Server (ISA Server) 632
Internet Server API (ISAPI) 632
Internet service provider (ISP) 633
Internet Society (ISOC) 634
internetwork 634
Internetwork Operating System (IOS) 634
Internetwork Packet Exchange (IPX) 636
interprocess communication (IPC) 637
Inter-Switch Link (ISL) 638
intranet 638
intrusion detection system (IDS) 638
inverse multiplexer (IMUX) 640
inverse multiplexing 640
Inverse Multiplexing over ATM (IMA) 641
inverse query 641
IOS 642
IP 642
IP address 642
IP/ATM 643
IPC 643
Ipconfig 643
IP Fax 644
IPng 644
IP over ATM 644
IPP 645
IP PBX 645
IPsec 645
IP storage 645
IP telephony 646
IPv4 646
IPv6 646
IPX 647
IPX/SPX-Compatible Protocol 647
IRC 647
IrDA 648
IrDA Control 648

IrDA Data 648
Irix 649
IRTF 649
ISAPI 649
ISAPI extension 649
ISAPI filter 649
ISA Server 650
iSCSI 650
ISDN 650
ISDN Digital Subscriber Line (IDSL) 651
ISDN fallback adapter 651
ISDN router 651
ISDN terminal adapter 652
ISL 653
ISM 653
ISO 653
ISOC 653
isoEthernet 653
ISP 654
iterative query 654
itrace 654
ITU 654
IXC 654

J

jabber 655
jack 655
jacket 656
jam signal 656
Java 657
Java Database Connectivity (JDBC) 659
Java Online Analytical Processing (JOLAP) 660
JavaScript 660
Java Server Pages (JSP) 661
JBOD 661
JDBC 662
Jet 662
Jini 662
jitter 663
join 663
Joint Engine Technology (Jet) 664
JOLAP 664
JScript 664
JSP 665
jumbo frames 665
JXTA 666

K

KCC 667
KDE 667
K Desktop Environment (KDE) 667
keepalives 667
Kerberos 668
kernel 669
kernel mode 670
keyboard emulator 671
Keyboard Video Mouse (KVM) switch 671
key (cryptography) 673
key (database) 673
key management 674
key pair 674
key (registry) 674
KM 675
Knowledge Consistency Checker (KCC) 675
knowledge management (KM) 675
KVM switch 675

L

L2CAP 677
L2F 677
L2TP 677
L2TP/IPsec 677
LADC 677
lambda switching 677
LAN 677
LANE 678
LAN Emulation (LANE) 678
LAN-host integration 679
LAN security switch 680
LAN segment 681
LAN switch 681
LAPD 681

Last Known Good configuration 681
LATA 681
late collision 681
latency 682
Layer 2 Forwarding (L2F) 683
Layer 2 switch 684
Layer 2 Tunneling Protocol (L2TP) 685
Layer 3 switch 687
Layer 4 switch 691
Layer 4+ switch 692
Layer 7 switch 692
LCP 693
LDAP 693
leased line 694
LEC 695
license 696
Lightweight Directory Access Protocol (LDAP) 697
Linear Tape Open (LTO) 700
line booster 700
line coding 701
line conditioner 703
line driver 704
line filter 705
Line Printer Daemon (LPD) 705
Line Printer Queue (LPQ) 706
Line Printer Remote (LPR) 707
line sharer 707
line sharing 708
Link Access Protocol, D-channel (LAPD) 709
link aggregation 709
Link Control Protocol (LCP) 710
link state routing algorithm 711
Linux 712
list server 715
LLC layer 716
LMDS 716
lmhosts file 716
load balancing 716
Local Access and Transport Area (LATA) 718
local address 718
Local Area Data Channel (LADC) 719
local area network (LAN) 719
local exchange carrier (LEC) 720
local group 721
localhost 722
local loop 722
Local Multipoint Distribution Service (LMDS) 722
local network 723
LocalSystem 724
LocalTalk 724
local user account 724
local user profile 725
Local Users and Groups 725
locking 725
log 726
Logical Link Control and Adaptation Layer Protocol (L2CAP) 727
logical link control (LLC) layer 727
logoff 727
logon 728
logon script 728
long packet error 729
Long Reach Ethernet (LRE) 729
loop 730
loopback 730
loopback address 731
LPD 731
LPQ 731
LPR 731
LRE 731
LTO 731

M

MAC address 733
Macintosh 734
MAC layer 734
MADCAP 734
mail client 735
mailslot 735
mail system 735
mainframe 736
MAN 737
Management Information Base (MIB) 737
Management Information Format (MIF) 739
Management Service Provider (MSP) 740

Manchester coding 740
mandatory user profile 741
manual switch 741
MAPI 742
mapped network drive 743
markup language 743
master boot record (MBR) 744
master browser 744
master domain 745
master index 745
master name server 745
master station 746
matrix switch 746
MAU 747
MBone 747
MBR 748
MBS 748
MBSP 748
MCP 748
MCS 748
MDA. 748
MDAC 748
MDHCP 748
media 748
media access control (MAC) layer 749
media access control method 749
media converter 750
media-dependent adapter (MDA). 751
Megaco 752
member server 753
mesh topology 753
message 754
message digest (MD) algorithms 755
Message Tracking Query Protocol (MTQP) 755
Messaging Application Programming
Interface (MAPI) 756
metabase 756
metadirectory 756
metasearching 758
metropolitan area network (MAN) 758
metropolitan Ethernet 759
MExE 762
MFC 762
MFR 762
MIB 762
microkernel 762
Microsoft Certified Partner 762
Microsoft Certified Professional (MCP) 762
Microsoft Challenge Handshake
Authentication Protocol (MS-CHAP) 764
microsoft.com. 764
Microsoft Consulting Services (MCS) 767
Microsoft Corporation 767
Microsoft Data Access Components (MDAC) . . . 769
Microsoft Developer Network (MSDN) 770
Microsoft Disk Operating System (MS-DOS) . . . 770
Microsoft Foundation Classes (MFC) 772
Microsoft Management Console (MMC) 773
Microsoft Market 774
Microsoft Office User Specialist (MOUS) 774
Microsoft Official Curriculum (MOC) 774
Microsoft Operations Framework (MOF) 775
Microsoft RAS Protocol 775
Microsoft Research (MSR) 775
Microsoft Solutions Framework (MSF) 776
Microsoft Technology Center (MTC) 776
Microsoft Windows 776
middleware 778
MIF 778
Millennium 778
MIME 779
mirrored volume 779
mirroring 779
mirror set 780
mixed mode 781
MLP 781
MLS 781
MMC 781
MMDS 782
M-node 782
Mobile Broadband System (MBS) 782
Mobile Execution Environment (MExE) 782
Mobile Information Server 783
Mobile Services Initiative (M-Services) 783
Mobile Transport Serving Office (MTSO) 783
MOC 784
modem 784
modem eliminator 785
modem sharing 785
modulation 786

MOF 788
MOSPF 788
MOUS 788
moving files 788
Mozilla 788
MP 788
MPLS 788
MPOA 789
MPPP 789
MSAU 789
MS-CHAP 789
MSDN 789
MS-DOS 789
MS-DOS mode 789
M-Services 789
MSP 789
MSF 789
MSR 790
MTC 790
MTQP 790
MTSO 790
MTU 790
Multicast Address Dynamic Client Allocation Protocol (MADCAP) 790
Multicast Dynamic Host Configuration Protocol (MDHCP) 791
multicasting 791
Multicast Open Shortest Path First (MOSPF) 793
multicast routing 793
multicast routing protocol 793
multihoming 794
Multilayer Switching (MLS) 796
Multilink Frame Relay (MFR) 796
Multilink Point-to-Point Protocol (MPPP) 797
multimaster replication 798
multimode fiber-optic cabling 799
multiple master domain model 800
Multiple Virtual Storage (MVS) 801
multiplexer (MUX) 801
multiplexing 802
multipoint 803
Multipoint Multichannel Distribution Service (MMDS) 804
multiport repeater 804
Multiprotocol Label Switching (MPLS) 804
Multiprotocol over ATM (MPOA) 806
Multipurpose Internet Mail Extensions (MIME) . 806
multiservice switch 807
Multistation Access Unit (MAU or MSAU) 807
multitasking 809
Multitenant Broadband Service Provider (MBSP) 809
multitenant unit (MTU) 809
MUX 810
MVS 810
MX record 810
My Computer 810
My Documents 811
My Network Places 811

N

Nagle's algorithm 813
named pipe 813
name lookup 814
name resolution 814
name server 815
namespace 815
naming context 817
naming convention 817
NAP 818
NAPT 818
NAS (network access server) 818
NAS (network attached storage) 818
NAT 818
National Electric Code (NEC) 818
National Institute of Standards and Technology (NIST) 818
native mode 819
NBF 820
NBNS 820
Nbtstat 820
NCP (NetWare Core Protocol) 820
NCP (Network Control Protocol) 820
NDIS 820
NDS 820
near-end crosstalk (NEXT) 820
NEC 821

.NET 822
NetBEUI 822
NetBEUI Frame (NBF) 822
NetBIOS 822
NetBIOS Extended User Interface (NetBEUI) . . . 823
NetBIOS name 824
NetBIOS name resolution 824
NetBIOS Name Server (NBNS) 826
NetBIOS over TCP/IP (NetBT) 826
NetBIOS over TCP/IP node types 827
NetBIOS scope ID 827
NetBT 828
Net commands 828
.NET Enterprise Servers 829
.NET experience 830
.NET Framework 830
NetLogon Share 831
.NET platform 831
netstat 832
NetWare 832
NetWare Core Protocol (NCP). 833
NetWare Directory Services (NDS) 833
NetWare protocols 834
network 835
Network Access Point (NAP) 837
network access server (NAS) 837
network adapter card 838
network address translation (NAT) 838
network architecture 841
network attached storage (NAS) 842
network client 843
Network Client 3 for MS-DOS 843
Network Control Protocol (NCP) 844
network design 844
network driver interface specification (NDIS) . . . 847
Network File System (NFS) 847
network ID 848
Network Information System (NIS) 849
network interface card (NIC) 849
network layer 850
network management 851
Network Monitor 854
Network News Transfer Protocol (NNTP) 854
network numbers 855
network operating system (NOS) 855
network probe 856
network protocol 856
network security 856
network service type 858
Networks file 858
Network Termination Unit (NTU) 859
Network Time Protocol (NTP) 859
network transmission method 860
network troubleshooting 860
network utilization 861
newsfeed 861
newsgroup 861
NEXT 862
Next Generation I/O (NGIO) 862
NFS 862
NGIO 862
NIC 862
NIS 863
NIST 863
NNTP 863
node 863
noise 863
normal backup 863
NOS 864
Novell Directory Services (NDS) 864
Nslookup 864
NS record 864
NTFS 865
NTFS file system (NTFS) 865
NTFS permissions (Windows 2000, Windows XP, and Windows .NET Server) 866
NTFS permissions (Windows NT) 868
NTFS special permissions (Windows 2000, Windows XP, and Windows .NET Server) 869
NTFS special permissions (Windows NT) 870
NTLM protocol 871
NTP 871
NTU 871
NTVDM 871
NT Virtual DOS Machine (NTVDM) 871
null modem cable 872
NWLink 872
NWLink IPX/SPX-Compatible Transport (NWLink) 872

O

OASIS 875
object (Active Directory) 875
object identifier (OID) 876
object linking and embedding (OLE) 877
object (programming) 878
OBM 878
OCSP 878
OC-x 878
ODBC 878
ODI 878
OFDM 878
offline browsing 878
Offline Files 879
OID 879
OLAP 879
OLE 879
OLE DB 879
OLE DB for OLAP 881
online analytical processing (OLAP) 881
Online Certificate Status Protocol (OCSP) 882
OnNow 882
OOB 883
OpenBSD 883
open database connectivity (ODBC) 883
Open Data-link Interface (ODI) 884
Open Shortest Path First (OSPF) 884
open source 887
Open Systems Interconnection (OSI)
    reference model 888
optical carrier (OC-x) level 890
optical Ethernet 890
optical networking 890
opto isolator 891
Orange Book 892
organizational unit (OU) 893
Organization for the Advancement of
    Structured Information Systems (OASIS) . . . 894
Orthogonal Frequency Division
    Multiplexing (OFDM) 895
OS/2 895
OSI model 895
OSPF 895
OS X 896
OU 896
Outlook 896
Outlook Express 896
out-of-band management (OBM) 897
out-of-band (OOB) signaling 898
outsourcing 899
owner 899

P

P2P 901
P3P 902
package 902
packet 903
packet assembler/disassembler (PAD) 903
packet filtering 904
packet forwarding 906
packet switching 906
packet-switching services 908
PAD 909
PAN 910
PAP 910
parallel transmission 910
parent domain 910
parity information 910
partition (Active Directory) 911
partition (disk) 911
passive hub 911
passive optical network (PON) 911
passive termination 912
pass-through authentication 913
password 913
Password Authentication Protocol (PAP) 914
PASTE 914
PAT 914
patch cable 914
patch panel 915
path 916
pathping 917
PBX 918
PCM 918
PCS 918

PCT 918
PDA 918
PDC 918
peer server 918
peer-to-peer network 918
PEM 919
perimeter network 919
Perl 919
permanent virtual circuit (PVC) 920
permissions 920
persistent connection 921
Personal Area Network (PAN) 921
Personal Communications Services (PCS) 922
Personal Digital Assistant (PDA) 922
PGP 923
PHP 923
physical address 924
physical layer 924
piconet 924
PIM-DM 924
PIM-SM 924
ping 924
PKCS 925
PKCS #7 925
PKCS #12 926
PKI 926
Plain Old Telephone Service (POTS) 926
Platform for Privacy Preferences (P3P) 926
plenum cabling 927
Plug and Play (PnP) 927
P-node 928
PnP 929
pointer (PTR) record 929
point of presence (POP) 929
point-to-multipoint 929
point-to-point 930
Point-to-Point Protocol (PPP) 931
Point-to-Point Tunneling Protocol (PPTP) 932
polyvinyl chloride (PVC) cabling 933
PON 933
POP 933
POP3 933
port 933
portal 933
port number 934
POSIX 935
POST 935
postoffice 935
Post Office Protocol version 3 (POP3) 935
POTS 936
power-on self test (POST) 936
Power Users group 937
PPP 937
PPP Multilink 937
PPTP. 937
Practical Extraction and Reporting Language (Perl) 937
premise cabling 937
presentation layer 938
Pretty Good Privacy (PGP) 938
PRI-ISDN 939
primary domain controller (PDC) 939
primary name server 939
primary partition 940
Primary Rate Interface ISDN (PRI-ISDN) 940
primary ring 940
printing pool 940
printing terminology 941
Print Operators group 941
print permissions 942
print server 942
print sharer 943
privacy 943
Privacy Enhanced Mail (PEM) 944
Private Branch Exchange (PBX) 945
Private Communication Technology (PCT) 946
private IP address 946
Project 802 947
promiscuous mode 947
protocol 948
protocol converter 948
protocol file 949
Protocol Independent Multicast-Dense Mode (PIM-DM) 950
Protocol Independent Multicast-Sparse Mode (PIM-SM) 950
protocol suite 950
Provider Architecture for Differentiated Services and Traffic Engineering (PASTE) 950
provisioning 951

proxy cache server 951
proxy server 952
P-series protocols 953
PSTN 953
PTR 953
public key cryptography 953
Public Key Cryptography Standards (PKCS) 954
public key infrastructure (PKI) 954
Public Switched Telephone Network (PSTN) 956
publishing 956
pulse code modulation (PCM) 957
PVC 957
PVC cabling 957

Q

QIC 959
QoS 959
QoS ACS 959
QoS Admission Control Service (QoS ACS) 959
Q-series protocols 960
quality of service (QoS) 960
Quarter Inch Cartridge (QIC) 963
quartet signaling 964
queue 964
queuing methods 965
quota management 965

R

RA 967
rack 967
RADIUS 968
RADSL 968
RAID 968
RAIT 968
Rate-Adjusted Digital Subscriber Line (RADSL) 968
RBOC 969
Rcp 969
RDP 969
Recreational Software Advisory Council (RSAC) 969
recursive query 969
redirection 970
redirector 970
redundant array of independent disks (RAID) . . . 970
redundant array of independent tapes (RAIT) . . . 972
Regional Bell Operating Company (RBOC) 973
registration authority (RA) 974
registry 974
relative path 975
remailer 975
remote access 975
remote administration 977
Remote Authentication Dial-In User Service (RADIUS) 978
remote bridge 980
remote client impersonation 980
remote control 981
Remote Desktop Protocol (RDP) 981
Remote Network Monitoring (RMON) 982
remote procedure call (RPC) 984
repeater 984
replay attack 985
Request for Comments (RFC) 985
reservation 986
residential gateway 986
resilient packet ring (RPR) 987
resolver 987
resource 988
resource domain 988
resource record (RR) 988
Resource Reservation Protocol (RSVP). 989
reverse hosting 989
reverse name lookup 989
reverse proxy 990
Rexec 990
RFC 990
RG 991
Rijndael 991
ring topology 991
RIP 992
RIPE 992
Rivest-Shamir-Adelman (RSA) algorithm 992
RJ connectors 993

RMON 994
roaming user profile 994
root 994
root certificate 995
root domain 995
root name server 996
routable protocol 996
route 996
router 997
router routing 1000
routing 1000
routing algorithm 1001
Routing Information Protocol (RIP) 1003
routing interface 1005
routing metric 1005
routing protocol 1005
routing table 1007
RPC 1008
RPC Ping 1008
RPR 1008
RSA 1009
RS-232 1009
RS-422 1010
RSAC 1010
Rsh 1010
RSVP 1011
runt 1011

S

SACL 1013
safe mode 1013
SAM database 1013
SAN 1013
SAP 1013
SAS 1014
SATAN 1014
Satellite Internet Backbone (SIBone) 1014
schema 1014
scope 1015
scripting 1015
SCSI 1016
SC/ST connectors 1016
SDLC 1017
SDSL 1017
secondary name server 1017
secondary ring 1018
secure attention sequence (SAS) 1018
Secure Hypertext Transfer Protocol
    (S-HTTP) 1019
Secure/Multipurpose Internet Mail
    Extensions (S/MIME) 1019
Secure Sockets Layer (SSL) 1019
security 1021
Security Account Manager (SAM) database 1023
Security Administrator Tool for
    Analyzing Networks (SATAN) 1024
security descriptor 1024
security group 1024
security identifier (SID) 1025
security log 1025
security principal 1025
security protocols 1025
security provider 1026
segmentation 1026
separator page 1027
serial encapsulation protocols 1027
serial interface 1028
Serial Line Internet Protocol (SLIP) 1028
serial transmission 1028
server 1029
server-based network 1029
server farm 1030
serverless backup 1030
Server Message Block (SMB) 1030
Server Operators 1031
service 1031
Service Advertising Protocol (SAP) 1034
service-level agreement (SLA). 1034
service pack 1034
services file. 1034
Services for Macintosh 1035
session initiation protocol (SIP). 1036
session layer 1036
share 1036
shared folder 1037
shared folder permissions 1037
shared SCSI bus 1039

share-level security 1039
shell 1040
shielded twisted-pair (STP) cabling 1040
shielding 1041
short 1041
Shortest Path First (SPF) 1041
Short Message Service (SMS) 1042
S-HTTP 1042
SIBone 1042
SID 1042
signal 1042
signaling 1043
signal loss 1043
Simple Mail Transfer Protocol (SMTP) 1044
Simple Network Management Protocol (SNMP) 1044
Simple Object Access Protocol (SOAP) 1046
simple volume 1047
simplex 1047
single domain model 1047
single master domain model 1048
single-mode fiber-optic cabling 1048
Single Sign On (SSO) 1049
SIP 1049
SLA 1049
SLIP 1049
Small Business Server 1049
Small Computer System Interface (SCSI) 1050
smart card 1052
SMB 1052
SMDS 1052
S/MIME 1052
SMS (Short Message Service) 1053
SMS (System Management Server) 1053
SMTP 1053
SNA 1053
SNADS 1053
snap-in 1053
SNA Server 1054
sniffing 1054
SNMP 1055
SOAP 1055
SOA record 1055
socket 1055
SOCKS 1055
softswitch 1056
solid conductor wire 1057
SONET 1057
source address 1057
spam 1057
spanned volume 1058
spanning tree algorithm (STA) 1058
sparse mode 1059
special identity 1059
SPF 1059
SPM 1060
spoofing 1060
spooling 1060
spread spectrum 1060
SQL 1061
SQL Server 1061
SSL 1062
SSO 1062
SSP 1062
STA 1063
stackable hubs 1063
stand-alone server 1063
standard Ethernet 1063
standards organizations 1063
star bus topology 1064
StarLAN 1064
start of authority (SOA) record 1064
star topology 1065
static address 1066
static mapping 1066
static routing 1066
statistical multiplexing (STM) 1067
STDM 1067
STM 1067
stop screen 1067
storage 1069
storage area network (SAN) 1070
storage over IP 1072
storage service provider (SSP) 1073
stored procedure 1073
STP cabling 1074
stranded conductor wire 1074
striped volume 1074

stripe set 1074
stripe set with parity 1074
Structured Query Language (SQL) 1074
structured wiring 1075
subnet 1075
subnet mask 1075
subnetting 1076
subtree 1077
supernetting 1078
surge protector 1078
SVC 1079
switch 1079
Switched 56 1079
Switched Multimegabit Data Services (SMDS) 1080
switched virtual circuit (SVC) 1081
Symmetric Digital Subscriber Line (SDSL) 1082
SYN attack 1083
sync 1083
Synchronous Data Link Control (SDLC) 1084
Synchronous Optical Network (SONET) 1084
synchronous transmission 1086
SYN flooding 1086
system access control list (SACL) 1086
system group 1087
system log 1087
system partition 1087
system policy 1087
Systems Management Server (SMS) 1088
Systems Network Architecture (SNA) 1089
SYSVOL share 1090

T

T1 1091
T1 channel bank 1094
T3 1095
T.120 1095
TACACS 1097
taking ownership 1097
tape drive 1097
tape format 1098
tape library 1100
TAPI 1100
T-carrier 1101
TCP 1102
TCP/IP 1103
TCP three-way handshake 1103
TDM 1103
TDMA 1103
TDR 1103
TechNet 1103
telco 1104
Telecommunications Industry Association (TIA) 1105
telecommunications services 1105
telecommuting 1106
Telephony Application Programming Interface (TAPI) 1106
Telnet 1107
terminal 1107
Terminal Access Controller Access Control System (TACACS) 1108
terminal emulator 1110
terminal server 1110
Terminal Services 1111
terminator 1112
Terrestrial Trunked Radio (Tetra) 1114
test equipment 1114
Tetra 1116
text file 1116
TFTP 1116
thick coax 1116
thicknet. 1116
thin client 1116
thin coax 1118
thinnet 1118
TIA 1118
Time Division Multiple Access (TDMA) 1119
time-division multiplexing (TDM). 1120
time domain reflectometry (TDR) 1120
TLD 1121
TLS 1121
TN3270 1121
TN5250 1121
Token Ring 1121

top-level domain (TLD) 1124
topology 1124
tracert 1125
transaction 1126
transaction log 1126
Transact-SQL 1127
transceiver 1127
transceiver cable 1127
Transmission Control Protocol (TCP) 1127
Transmission Control Protocol/Internet Protocol (TCP/IP) 1128
transport layer 1130
Transport Layer Security (TLS) 1130
tree 1130
Trivial File Transfer Protocol (TFTP) 1130
trunking 1131
trust. 1132
T-SHARE 1134
tunneling. 1134
twinax cabling 1134
twisted-pair cabling 1135
two-way transitive trust 1135

U

UART 1137
UDA 1137
UDDI 1137
UDF (Uniqueness Database File) 1137
UDF (Universal Disk Format) 1137
UDFS 1137
UDP 1137
ULS 1137
UM 1137
UMTS. 1137
unattended installation 1138
Unattend.txt 1139
unbalanced line 1139
UNC 1139
unicasting 1139
Unicode 1140
Unified Messaging (UM) 1140
Uniform Resource Locator (URL) 1142
uninterruptible power supply (UPS) 1142
Uniqueness Database File (UDF) 1144
Universal Asynchronous Receiver/Transmitter (UART) 1144
Universal Data Access (UDA) 1144
Universal Description, Discovery, and Integration (UDDI) 1145
Universal Disk Format (UDF) 1145
Universal DSL 1146
universal group 1146
Universal Mobile Telecommunications System (UMTS) 1146
Universal Naming Convention (UNC) 1146
universal serial bus (USB) 1147
Universal Wireless Communications (UWC-136) 1149
UNIX 1149
UNIX commands 1151
UNIX-to-UNIX Copy (UUCP) 1153
unshielded twisted-pair (UTP) cabling 1153
update sequence number (USN). 1154
uplink port 1155
UPN 1155
UPS 1155
URL 1155
URL switching 1155
USB 1155
Usenet 1155
user account 1157
User Datagram Protocol (UDP) 1157
user-level security 1158
User Locator Service (ULS) 1159
user mode 1159
username 1160
user principal name (UPN) 1160
user profile 1160
Users group 1161
USN 1161
UTP cabling 1161
UUCP 1161
uuencoding 1161
UWC-136 1162

V

V.35 1163
V.90 1163
V.92 1165
value entry 1165
variable-length subnet mask (VLSM) 1166
VBScript 1167
vCalendar 1168
vCard 1168
VDSL 1168
Very-high-rate Digital Subscriber Line (VDSL) 1168
virtual circuit 1169
virtual directory 1170
virtual hosting 1170
virtual LAN (VLAN) 1170
virtual memory 1174
virtual private network (VPN) 1174
virtual server 1176
virus 1177
VLAN 1179
VLSM 1180
Voice over IP (VoIP) 1180
voice profile for Internet mail (VPIM) 1184
VoIP 1185
VoIP gateway 1185
volume 1187
volume set 1187
VPIM 1187
VPN 1187
V-series 1187

W

W3C 1189
wall plate 1189
WAN 1190
WAN services 1190
WAP 1191
wavelength division multiplexing (WDM) 1191
WBEM 1192
W-CDMA 1192
WDM 1192
Web 1192
Web application 1192
Web-Based Enterprise Management (WBEM) 1192
Web browser 1193
Web content switch 1194
Web hosting 1194
Web page 1195
Web server 1195
Web-to-host 1196
well-known port numbers 1197
WEP 1203
wide area network (WAN) 1203
Wideband Code Division Multiple Access (W-CDMA) 1204
WiFi 1205
Windows 3.1. 1205
Windows 3.11 1207
Windows 95 1207
Windows 98 1209
Windows 2000 1209
Windows CE 1211
Windows commands 1212
Windows Distributed interNet Applications Architecture (Windows DNA) 1214
Windows DNA 1215
Windows Explorer 1215
Windows for Workgroups 1216
Windows Internet Name Service (WINS) 1217
Windows Management Instrumentation (WMI) 1218
Windows Me (Windows Millennium Edition) 1219
Windows Millennium Edition (Windows Me) 1219
Windows .NET Server 1219
Windows NT 1219
Windows NT Challenge/Response Authentication 1222
Windows NT Directory Services (NTDS) 1222
Windows NT LAN Manager Authentication . . . 1223
Windows Script Host (WSH) 1223
Windows Sockets 1223

Windows Update 1224
Windows XP 1224
WINS 1224
Winsock 1224
WINS proxy agent 1224
WINS record 1225
WINS server 1225
Wired Equivalent Privacy (WEP) 1226
Wireless Application Protocol (WAP) 1227
wireless local area network (WLAN) 1229
Wireless Markup Language (WML) 1229
wireless networking 1230
wiring closet 1233
WLAN 1233
WMI 1234
WML 1234
workgroup 1234
World Wide Web (WWW) 1234
World Wide Web Consortium (W3C) 1235
WOW 1235
WSH 1236
WWW 1236

X

X.25 1237
x86 platform 1239
X.121 address 1239
X.400 1240
X.500 1242
xDSL 1243
Xerox Network Systems (XNS) 1243
XHTML 1244
XML 1244
XNS 1248
X-series 1248
xSP 1249
X Window System 1249

Y

Y2K 1251
Y-connector 1252
Y-splitter 1252

Z

ZAK 1255
Zero Administration Kit (ZAK) 1255
zone 1256
zone file 1256
zone of authority 1257
zone transfer 1258

Index *1261*

Acknowledgments

I would like to welcome and acknowledge my wife, Ingrid Tulloch, as co-author for this second edition of the Microsoft Encyclopedia of Networking. Ingrid is a skilled researcher whose research has contributed extensively to both this edition and the previous one, and I thank Microsoft Press for their willingness to recognize her contribution to this project by adding her name next to mine.

My thanks also to the terrific team at Microsoft Press, including Juliana Aldous (Acquisions Editor) and Maureen Zimmerman (Project Editor), and at nSight, especially Susan McClung (Project Manager), Ari Globerman and John Panzarella (Technical Editors), and Joseph Gustaitis (Copy Editor).

Thanks to David L. Rogelberg and Neil Salkind, my agents at Studio B Literary Agency, and to all the other wonderful people there.

Finally, thanks to my many readers and friends whose suggestions and comments regarding the first edition have been incorporated into this new edition and have helped make it what it is—the BEST networking encylopedia EVER!

Mitch Tulloch
www.mtit.com

Preface to the Second Edition

Welcome to the second edition of the popular *Microsoft Encyclopedia of Networking*, the premier resource for network architects, system engineers, network administrators, and IT professionals. The purpose of this Preface is to briefly describe the new and exciting changes found in this new edition, which can be summarized by the simple word *more*. Specifically, in this new edition of this encyclopedia you'll find

- **More coverage of key networking concepts and technologies**. We've added hundreds of new articles covering the latest networking technologies, including wireless networking, 3G cellular communication, broadband Internet access, LAN-host integration, network management, network security, network troubleshooting, disaster recovery, enterprise applications, P2P technologies, virus protection, carriers and service providers, and e-business standards and technologies. In addition, coverage of basic networking standards, protocols, architectures, and technologies has been enhanced and extended throughout the work by including new articles on cabling standards, routing protocols, security protocols, signal encoding methods, encryption schemes, component architectures, WAN services, multilayer switching, tape formats, multiplexing methods, remote access, terminal-based computing, Voice over IP, and the organization and operation of the Internet. And that's only scratching the surface!
- **More depth of coverage in key articles**. Essential technologies and standards, such as 802.11b wireless, ATM, Bluetooth, cellular communications, Classless Interdomain Routing, DSL, DNS, Ethernet, frame relay, Gigabit Ethernet, GSM, and ISDN, are covered in much more detail than they were in the first edition. In addition to a brief definition and overview of the subject, longer articles are frequently divided into a number of different subsections for greater clarity and more logical treatment of the subject. Headings for these subsections include Overview, History, Types, Uses, Comparison, Architecture, Implementation, Examples, Advantages and Disadvantages, Issues, Notes, and For More Information.
- **More coverage of key platforms**. Coverage of the Microsoft Windows NT platform and applications has been de-emphasized in this edition to make room for coverage of Windows 2000, Windows XP, and Microsoft's new .NET framework. In addition, increased coverage of popular UNIX platforms and open-source technologies such as Linux and Apache has been included. Overall, this new edition is less Microsoft-centric than the first edition, and instead focuses more on general networking concepts, technologies, and services with fair coverage of competing platforms from many different vendors.
- **Up-to-date coverage of standards, products, and services**. The networking world has changed considerably since the first edition of this encyclopedia came out, with the Application Services Provider marketplace exploding and then imploding, homegrown intranets evolving into powerful Enterprise Knowledge Portals, Token Ring and FDDI going the way of the dinosaur, 3G expectations being replaced by 2.5G realities, XML standards proliferating but failing to displace EDI in the marketplace, and new vendors and service providers appearing, merging, and going bankrupt faster than fruit flies can multiply. As a result of these changes, every article in this work has been thoroughly revised and updated to include the latest and most accurate information possible. In addition, many articles include two special subsections: Marketplace,

which provides a snapshot of vendors and products available at the time of writing; and Prospects, which offers our best prediction of how technologies and services will evolve over the next few years.

- **Expanded cross-references**. The list of cross-references at the end of each article has been greatly expanded to enhance the usefulness of this work as the essential reference guide for networking professionals of all levels, ranging from students pursuing their MCSE to senior network architects with years of field experience.
- **Revised introduction**. The introduction to the book has been revised and updated, and the section called History of Networking has been brought up to date with developments that have taken place since the first edition.

In conclusion, we hope you enjoy using this new edition of the *Microsoft Encyclopedia of Networking* as much as we have enjoyed writing it!

Introduction

Welcome to the second edition of the *Microsoft Encyclopedia of Networking*, a general survey of computer networking concepts, technologies, and services. This work is intended to be a comprehensive, accurate, and up-to-date resource for students, system engineers, network administrators, IT (information technology) implementers, and computing professionals from all walks of life. Before we outline this work's scope and coverage, we will ask a simple question that is surprisingly difficult to answer: what is networking?

What Is Networking?

In the simplest sense, networking means connecting computers so that they can share files, printers, applications, and other computer-related resources. The advantages of networking computers are fairly obvious:

- Users can save their important files and documents on a file server. This is more secure than storing them on workstations because a file server can be backed up in a single operation.
- Users can share a network printer, which costs much less than having a locally attached printer for each user's computer.
- Users can share groupware applications running on application servers, which enables users to share documents, send messages, and collaborate directly.
- The job of administering and securing a company's computer resources is simplified since they are concentrated on a few centralized servers.

The above definition of networking focuses on the basic goals of networking computers together: increased manageability, security, cost-effectiveness, and efficiency over non-networked systems. However, we could also focus our discussion on the different *types* of networks, including

- Personal area networks (PANs), once the stuff of science fiction but rapidly becoming a reality as the mobile knowledge workers of today carry around an array of cell phones, Personal Digital Assistants (PDAs), pagers, and other small devices
- Local area networks (LANs), which can range from a few desktop workstations in a Small Office/Home Office (SOHO) to several thousand workstations and dozens of servers deployed throughout dozens of buildings on a university campus or in an industrial park
- Metropolitan area networks (MANs), which span an urban area and are generally run by telcos and other service providers to provide companies with high-speed connectivity between branch offices and with the Internet
- Wide area networks (WANs), which might take the form of a company's head office linked to a few branch offices or an enterprise spanning several continents with hundreds of offices and subsidiaries
- The Internet, the world's largest network and the "network of networks"

On the other hand, we could also focus on the different networking *architectures* in which these various types of networks can be implemented, including

- Peer-to-peer networking, which might be implemented in a workgroup consisting of computers running Microsoft Windows 98 or Windows 2000 Professional
- Server-based networking, which might be based on the domain model of Windows NT, the domain trees and forests of Active Directory directory

service in Windows 2000, or another architecture such as Novell Directory Services (NDS) for Novell NetWare

- Terminal-based networking, which might be the traditional host-based mainframe environment; the UNIX X Windows environment; the terminal services of Windows NT Server 4 Enterprise Edition; Windows 2000 Advanced Server; or Citrix MetaFrame

Or we could look at the various networking *technologies* used to implement these architectures, including

- LAN technologies such as Ethernet, Token Ring, Fiber Distributed Data Interface (FDDI), Fast Ethernet, Gigabit Ethernet (GbE), and the emerging 10G Ethernet (10GbE)
- WAN technologies such as Integrated Services Digital Network (ISDN), T-carrier leased lines, X.25, frame relay, Asynchronous Transfer Mode (ATM), Synchronous Optical Network (SONET), Digital Subscriber Line (DSL), and metropolitan Ethernet
- Wireless communication technologies such as the wireless LAN (WAN) standards 802.11a and 802.11b, and the consumer wireless technologies HomeRF and Bluetooth
- Cellular communication systems such as Time Division Multiple Access (TDMA), Code Division Multiple Access (CDMA), Global System for Mobile Communications (GSM), and the emerging 3G cellular communication standards

In addition, we could consider the *hardware* used to implement these different networking technologies, including

- LAN devices such as repeaters, concentrators, bridges, hubs, Ethernet switches, and routers
- WAN devices such as modems, ISDN terminal adapters, Channel Service Units (CSUs), Data Service Units (DSUs), packet assembler/disassemblers (PADs), frame relay access devices (FRADs), multiplexers (MUXes), and inverse multiplexers (IMUXes)
- Equipment for organizing, protecting, and troubleshooting LAN and WAN hardware, such as racks, cabinets, surge protectors, line conditioners, uninterruptible power supplies (UPSs), KVM switches, and cable testers
- Cabling technologies such as coaxial cabling, twinax cabling, twisted-pair cabling, fiber-optic cabling, and associated equipment such as connectors, patch panels, wall plates, and splitters
- Unguided media technologies such as infrared communication, wireless cellular networking, and satellite networking, along with their associated hardware
- Data storage technologies such as redundant array of independent disks (RAID), network-attached storage (NAS), and storage area networks (SANs) along with their associated hardware, plus various enabling technologies, including Small Computer System Interface (SCSI) and Fibre Channel

Or we could talk about various technologies that *enhance the reliability, scalability, security, and manageability* of computer networks, including

- Technologies for implementing network security, including firewalls, proxy servers, and virtual private networking (VPN), and such devices as smart cards and firewall appliances
- Technologies for increasing availability and reliability of access to network resources, such as clustering, caching, load balancing, Layer 7 switching, and terminal services
- Network management technologies such as Simple Network Management Protocol (SNMP), Remote Network Monitoring (RMON), Web-Based Enterprise Management (WBEM), Common Information Model (CIM), and Windows Management Instrumentation (WMI)

Returning to a more general level, networking can also be thought of as the various *standards* that underlie the different networking technologies and hardware mentioned above, including

- The Open Systems Interconnection (OSI) networking model from the International Organization for Standardization (ISO)
- The G-series, H-series, I-series, T-series, V-series, and X-series standards from the International Telecommunication Union (ITU)
- Project 802 of the Institute of Electrical and Electronics Engineers (IEEE)
- The Requests for Comment (RFC) series from the Internet Engineering Task Force (IETF)
- Various standards developed by the World Wide Web Consortium (W3C), the Frame Relay Forum, the ATM Forum, the Gigabit Ethernet Alliance, and other standards organizations

Networking *protocols* deserve special attention in any definition of the word *networking*. These protocols include:

- LAN protocols such as NetBEUI, Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX), Transmission Control Protocol/Internet Protocol (TCP/IP), and AppleTalk
- WAN protocols such as Serial Line Internet Protocol (SLIP), Point-to-Point Protocol (PPP), Point-to-Point Tunneling Protocol (PPTP), and Layer 2 Tunneling Protocol (L2TP)
- Protocols developed within mainframe computing environments, such as Systems Network Architecture (SNA), Advanced Program-to-Program Communications (APPC), Synchronous Data Link Control (SDLC), and High-level Data Link Control (HDLC)
- Routing protocols such as the Routing Information Protocol (RIP), Interior Gateway Routing Protocol (IGRP), Open Shortest Path First (OSPF) Protocol, and Border Gateway Protocol (BGP)
- Internet protocols such as the Hypertext Transfer Protocol (HTTP), File Transfer Protocol (FTP), Network News Transfer Protocol (NNTP), and the Domain Name System (DNS)
- Electronic messaging protocols such as X.400, Simple Mail Transfer Protocol (SMTP), Post Office Protocol version 3 (POP3), and Internet Mail Access Protocol version 4 (IMAPv4)
- Directory protocols such as X.500's Directory Access Protocol (DAP) and the Lightweight Directory Access Protocol (LDAP)
- Security protocols such as Password Authentication Protocol (PAP), Challenge Handshake Authentication Protocol (CHAP), Windows NT LAN Manager (NTLM) Authentication, Kerberos, IP Security Protocol (IPsec), Secure Sockets Layer (SSL), and public key cryptography standards and protocols
- Serial interface standards such as RS-232, RS-422/423, RS-485, V.35, and X.21

We could dig still deeper and discuss the *fundamental engineering concepts* that underlie the various networking technologies and services previously discussed, including

- Impedance, attenuation, shielding, near-end crosstalk (NEXT), and other characteristics of cabling and other transmission systems
- Signals and how they can be multiplexed using time-division, frequency-division, statistical, and other multiplexing techniques
- Transmission parameters including bandwidth, throughput, latency, jabber, jitter, backbone, handshaking, hop, dead spots, dark fiber, and late collisions
- Balanced vs. unbalanced signals, baseband vs. broadband transmission, data communications equipment (DCE) vs. data terminal equipment (DTE), circuit switching vs. packet switching, connection-oriented vs. connectionless communication, unicast vs. multicast and broadcast, point-to-point vs. multipoint links, direct sequencing vs. frequency hopping methods, and switched virtual circuit (SVC) vs. permanent virtual circuit (PVC)

We could also talk about the different types of *providers* of networking services, including

- Internet service providers (ISPs), application service providers (ASPs), and integrated communications providers (ICPs)
- Telcos or local exchange carriers (LECs), including both Regional Bell Operating Companies (RBOCs) and competitive local exchange carriers (CLECs), that offer such popular broadband services as Asymmetric Digital Subscriber Line (ADSL) and High-bit-level Digital Subscriber Line (HDSL) through their central office (CO) and local loop connection
- Inter-exchange carriers (IXCs) that provide popular WAN services such as dedicated leased lines and frame relay for the enterprise (large companies)
- Local loop alternatives including cable modems, fixed wireless, and satellite networking companies

We could also list the various *software technologies* vendors have developed that make computer networking both useful and possible, including

- Network operating systems such as Windows, Novell NetWare, UNIX, and Linux
- Specialized operating systems such as Cisco Systems' Internetwork Operating System (IOS), which runs on Cisco routers, and the variant of IOS used on Cisco's Catalyst line of Ethernet switches
- Directory systems such as Microsoft Corporation's domain-based Active Directory, Novell Directory Services (NDS), and various implementations of X.500 and LDAP directory systems
- File systems such as NTFS file system (NTFS) on Windows platforms and distributed file systems such as the Network File System (NFS) developed by Sun Microsystems for the UNIX platform
- Programming languages and architectures for developing distributed computing applications, such as the C/C++ and Java languages, Microsoft's ActiveX and Sun's Jini technologies, component technologies such as Distributed Component Object Model (DCOM) and COM+, interprocess communication (IPC) technologies such as Remote Procedure Calls (RPCs) and named pipes, and Internet standards such as the popular Hypertext Markup Language (HTML) and the Extensible Markup Language (XML) family of standards
- Tools for integrating networking technologies in heterogeneous *environments*, such as Gateway Services for NetWare (GSNW), Services for Macintosh, Services for UNIX on the Windows 2000 platforms, and Microsoft Host Integration Server, all of which provide connectivity with mainframe systems

On an even deeper level, we could focus on the various *administration tools* for managing networking hardware, platforms, services and protocols, including

- The Microsoft Management Console (MMC) and its various snap-ins in the Windows 2000 and Windows .NET Server platforms
- The various ways routers and network appliances can be administered using Telnet, terminal programs, and the universal Web browser interface
- Popular TCP/IP command-line utilities such as arp, ping, ipconfig, traceroute, netstat, nbtstat, finger, and nslookup
- Platform-specific command-line utilities such as various Windows commands used for automating common administration tasks
- Cross-platform scripting languages that can be used for system and network administration, including JavaScript, VBScript, and Perl

We could also look at various *enterprise applications* widely used in networked environments, including

- Enterprise Resource Planning (ERP) and Customer Relationship Management (CRM) platforms
- Enterprise Information Portal (EIP) and Enterprise Knowledge Portal (EKP) platforms
- The Microsoft .NET Enterprise Server family of applications that includes Microsoft Application Center Server, BizTalk Server, Commerce Server,

Exchange Server, Host Integration Server, Internet Security and Acceleration Server, Mobile Information Server, and SQL Server

I think that you can see by now that we could go on and on, slowly unpeeling our answer to the question "What is networking?" like the many layers of an onion. And it is pretty obvious by now that there is more to networking than just hubs and cables! In fact, the field of computer networking today is almost overwhelming in its breadth and complexity, and one could spend a lifetime studying only one small aspect of the subject.

This has not always been the case. Let's take a look now at how the field of computer networking has reached the amazing point where it is today.

The History of Networking

Because networking is such a broad and complex subject, no single event represents its point of origin. However, we can arbitrarily decide on the 1960s as the formative period for the field, since that is when the computer began to affect significantly the lives of ordinary individuals and the day-to-day operation of both business and government.

1960s

In the 1960s computer networking was essentially synonymous with mainframe computing, and the distinction between local and wide area networks did not yet exist. Mainframes were typically "networked" to a series of dumb terminals with serial connections running on RS-232 or some other electrical interface. If a terminal in one city needed to connect with a mainframe in another city, a 300-baud long-haul modem would use the existing analog Public Switched Telephone Network (PSTN) to form the connection. The technology was primitive indeed, but it was an exciting time nevertheless. I remember taking a computer science class in high school toward the end of the decade, and having to take my box of punch cards down to the mainframe terminal at the university and wait in line for the output from the line printer. Alas, poor Fortran, I knew thee well!

To continue the story, the quality and reliability of the PSTN increased significantly in 1962 with the introduction of pulse code modulation (PCM), which converted analog voice signals into digital sequences of bits. A consequent development was the first commercial touch-tone phone, which was introduced in 1962. Before long, digital phone technology became the norm, and DS-0 (Digital Signal Zero) was chosen as the basic 64-kilobit-per-second (Kbps) channel upon which the entire hierarchy of the digital telephone system was built. A later development was a device called a channel bank, which took 24 separate DS-0 channels and combined them together using time-division multiplexing (TDM) into a single 1.544-Mbps channel called DS-1 or T1. (In Europe, 30 DS-0 channels were combined to make E1.) When the backbone of the Bell telephone system finally became fully digital years later, the transmission characteristics improved significantly for both voice and data transmission due to higher quality and less noise associated with Integrated Services Digital Network (ISDN) digital lines, though local loops have remained analog in many places. But that is getting a little ahead of the story.

The first communication satellite, Telstar, was launched in 1962. This technology did not immediately affect the networking world because of the high latency of satellite links compared to undersea cable communications, but it eventually surpassed transoceanic underwater telephone cables (which were first deployed in 1965 and could carry 130 simultaneous conversations) in carrying capacity. In fact, early in 1960 scientists at Bell Laboratories transmitted a communication signal coast-to-coast across the United States by bouncing it off the moon! By 1965 popular commercial communication satellites such as Early Bird were being widely deployed and used.

As an interesting aside, in 1961 the Bell system proposed a new telecommunications service called TELPAK, which it claimed would lead to an "electronic highway" for communication, but it never pursued the idea. Could this have been an early portent of the "information superhighway" of the mid-1990s?

The year 1969 witnessed an event whose full significance was not realized until more than two decades later: namely, the development of the ARPANET packet-switching network. ARPANET was a project of the U.S. Department of Defense's Advanced Research Projects Agency (ARPA), which became DARPA in 1972. Similar efforts were underway in France and the United Kingdom, but it was the U.S. project that eventually evolved into the present-day Internet. (France's MINTEL packet-switching system, which was based on the X.25 protocol and which aimed to bring data networking into every home, did take off in 1984 when the French government started giving away MINTEL terminals; by the early 1990s, more than 20 percent of the country's population was using it.) The original ARPANET network connected computers at Stanford University, the University of California at Los Angeles (UCLA), the University of California at Santa Barbara (UCSB), and the University of Utah, with the first node being installed at UCLA's Network Measurement Center. A year later, Harvard University, the Massachusetts Institute of Technology (MIT), and a few other prominent institutions were added to the network, but few of those involved could imagine that this technical experiment would someday profoundly affect modern society and the way we do business.

The year 1969 also saw the publication of the first Request For Comments (RFC) document, which specified the Network Control Protocol (NCP), the first transport protocol of ARPANET. The informal RFC process evolved into the primary means of directing the evolution of the Internet and is still used today.

That same year, Bell Laboratories developed the UNIX operating system, a multitasking, multiuser network operating system (NOS) that became popular in academic computing environments in the 1970s. A typical UNIX system in 1974 was a PDP-11 minicomputer with dumb terminals attached. In a configuration with 768 kilobytes (KB) of magnetic core memory and a couple of 200-megabyte (MB) hard disks, the cost of such a system would have been around $40,000. I remember working in those days on a PDP-11 in the cyclotron lab of my university's physics department, feeding in bits of punched tape and watching lights flash. It was an incredible experience.

Many important standards for computer systems also evolved during the 1960s. In 1962, IBM introduced the first 8-bit character encoding system, called Extended Binary-Coded Decimal Interchange Code (EBCDIC). A year later the competing American Standard Code for Information Interchange (ASCII) was introduced. ASCII ultimately won out over EBCDIC even though EBCDIC was 8-bit and ASCII was only 7-bit. The American National Standards Institute (ANSI) formally standardized ASCII in 1968. ASCII was first used in serial transmission between mainframe hosts and dumb terminals in mainframe computing environments, but it was eventually extended to all areas of computer and networking technologies.

Other developments in the 1960s included the development in 1964 of IBM's powerful System/360 mainframe computing environment, which was widely implemented in government, university, and corporate computing centers. In 1966, IBM introduced the first disk storage system, which employed 50 metal platters, each of which was 2 feet (0.6 meter) wide and had a storage capacity of 5 MB. IBM created the first floppy disk in 1967. In 1969, Intel Corporation released a RAM chip that stored 1 KB of information, which at the time was an amazing feat of engineering.

1970s

Although the 1960s were the decade of the mainframe, the 1970s gave birth to Ethernet, which today is by far the most popular LAN technology. Ethernet was born in 1973 in Xerox Corporation's research lab in Palo Alto, California. (An earlier experimental network called ALOHAnet was developed in 1970 at the University of Hawaii.) The original Xerox networking system was known as X-wire and worked at 2.94 Mbps. X-wire was experimental and was not used commercially, although a number of Xerox Palo Alto workstations used for word processing were networked together in the White House using X-wire during the Carter administration. In 1979, Digital Equipment Corporation (DEC), Intel, and Xerox formed the DIX consortium and developed the specification for standard 10-Mbps Ethernet, or thicknet, which was published in 1980. This standard was revised and additional features were added in the following decade.

The conversion of the backbone of the Bell telephone system to digital circuitry continued during the 1970s and included the deployment in 1974 of the first digital data service (DDS) circuits (then called the Dataphone Digital Service). DDS formed the basis of the later deployment of ISDN and T1 lines to customer premises, and AT&T installed its first digital switch in 1976.

In wide area networking, a new telecommunications service called X.25 was deployed toward the end of the decade. This new system was packet-switched, in contrast to the circuit-switched PSTN, and later evolved into public X.25 networks such as GTE's Telenet Public Packet Distribution Network (PDN), which later became SprintNet. X.25 was widely deployed in Europe, where it still maintains a large installed base, especially for communications in the banking and financial industry.

In 1970 the Federal Communications Commission (FCC) announced the regulation of the fledgling cable television industry. Cable TV remained primarily a broadcast technology for delivering entertainment to residential homes until the mid-1990s, when technologies began to be developed to enable it to carry broadband services to residential subscribers. Cable modems now compete strongly with Digital Subscriber Line (DSL) as the main two forms of broadband Internet access technologies.

Despite all these technological advances, however, telecommunications services in the 1970s remained unintegrated, with voice, data, and entertainment carried on different media. Voice was carried by telephone, which was still analog at the customer premises; entertainment was broadcast using radio and television technologies; and data was usually carried over RS-232 or Binary Synchronous Communication (BSC) serial connections between dumb terminals and mainframes (or, for remote terminals, long-haul modem connections over analog telephone lines).

The 1970s were also notable for the growth of ARPANET, which grew throughout the decade as additional hosts were added at various universities and government institutions. By 1971 the network had 19 nodes, mostly consisting of a mix of PDP-8, PDP-11, IBM S/360, DEC-10, Honeywell, and other mainframe and minicomputer systems linked together. The initial design of ARPANET called for a maximum of 265 nodes, which seemed like a distant target in the early 1970s. The initial protocol used on this network was NCP, but this was replaced in 1982 by the more powerful TCP/IP protocol suite. In 1975 the administration of ARPANET came under the authority of the Defense Communications Agency.

ARPANET protocols and technologies continued to evolve using the informal RFC process developed in 1969. In 1972 the Telnet protocol was defined in RFC 318, followed by FTP in 1973 (RFC 454). ARPANET became an international network in 1973 when nodes were added at the University College of London in the United Kingdom and at the Royal Radar Establishment in Norway. ARPANET even established an experimental wireless packet-switching radio service in 1977, which two years later became the Packet Radio Network (PRNET).

Meanwhile, in 1974 the first specification for the Transmission Control Protocol (TCP) was published. Progress on the TCP/IP protocols continued through several iterations until the basic TCP/IP architecture was formalized in 1978, but it was not until 1983 that ARPANET started using TCP/IP instead of NCP as its primary networking protocol.

The year 1977 also saw the development of UNIX to UNIX Copy (UUCP), a protocol and tool for sending messages and transferring files on UNIX-based networks. An early version of the USENET news system using UUCP was developed in 1979. (The Network News Transfer Protocol [NNTP] came much later, in 1987.)

In 1979 the first commercial cellular phone system began operation in Japan. This system was analog in nature, used the 800-MHz and 900-MHz frequency bands, and was based on a concept developed in 1947 at Bell Laboratories.

An important standard to emerge in the 1970s was the public-key cryptography scheme developed in 1976 by Whitfield Diffie and Martin Hellman. This scheme underlies the Secure Sockets Layer (SSL) protocol developed by Netscape Communications, which is still the predominant approach for ensuring privacy and integrity of financial and other transactions over the World Wide Web (WWW). Without SSL, popular e-business sites such as Amazon and eBay would have a hard time attracting customers!

Among other miscellaneous developments during this decade, in 1970 IBM researchers invented the relational database, a set of conceptual technologies that has become the foundation of today's distributed application environments. In 1971, IBM demonstrated the first speech recognition technologies—which have since led to those annoying automated call handling systems found in customer service centers! IBM also developed the concept of the virtual machine in 1972 and created the first sealed disk drive (the Winchester) in 1973. In 1974, IBM introduced the Systems Networking Architecture (SNA) for networking its mainframe computing environment. In 1971, Intel released its first microprocessor, a 4-bit processor called the 4004 that ran at a clock speed of 108 kilohertz (kHz), a snail's pace by modern standards but a major development at the time. Another significant event was the launching of the online service CompuServe in 1979, which led to the development of the first online communities.

The first personal computer, the Altair, went on the market as a kit in 1975. The Altair was based on the Intel 8080, an 8-bit processor, and came with 256 bytes of memory, toggle switches, and light-emitting diode (LED) lights. Although the Altair was basically for hobbyists, the Apple II from Apple Computer, which was introduced in 1977, was much more. A typical Apple II system, which was based on the Motorola 6502 8-bit processor, had 4 KB of RAM, a keyboard, a motherboard with expansion slots, built-in BASIC in ROM, and color graphics. The Apple II quickly became the standard desktop system in schools and other educational institutions. A physics classroom I taught in had one all the way into the early 1990s (limited budget!). However, it was not until the introduction of the IBM Personal Computer (PC) in 1981 that the full potential of personal computers began to be realized, especially in businesses.

In 1975, Bill Gates and Paul Allen licensed their BASIC computer programming language to MITS, the Altair's manufacturer. BASIC was the first computer language specifically written for a personal computer. Gates and Allen coined the name "Microsoft" for their business partnership, and they officially registered it as a trademark the following year. Microsoft Corporation went on to license BASIC to other personal computing platforms such as the Commodore PET and the TRS-80. I loved BASIC in those early days, and I still do!

1980s

In the 1980s the growth of client/server LAN architectures continued while that of mainframe computing environments declined. The advent of the IBM PC in 1981 and the standardization and cloning of this architecture led to an explosion of PC-based LANs in businesses and corporations around the world, particularly with the release of the IBM PC AT hardware platform in 1984. The number of PCs in use grew from 2 million in 1981 to 65 million in 1991. Novell, which appeared on the scene in 1983, soon became a major player in file and print servers for LANs with its Novell NetWare platform.

However, the biggest development in the area of LAN networking in the 1980s was the continued evolution and standardization of Ethernet. While the DIX consortium worked on Ethernet standards in the late 1970s, the IEEE with its Project 802 initiative tried working toward a single unified LAN standard. When it became clear that this goal was impossible, Project 802 was divided into a number of separate working groups, with 802.3 focusing on Ethernet, 802.4 on Token Bus, and 802.5 on Token Ring technologies and standards. The work of the 802.3 group resulted in the first Ethernet standard, called 10Base5 or thicknet, which was almost identical to the version developed by DIX. 10Base5 was called thicknet because it used thick coaxial cable, and in 1985 the 802.3 standard was extended to include 10Base2 using thin coaxial cable, commonly called thinnet.

Through most of the 1980s, coaxial cable was the main form of cabling used for implementing Ethernet. A company called SynOptics Communications, however, developed a product called LattisNet that was designed for transmitting 10-Mbps Ethernet over twisted-pair wiring using a star-wired topology that was connected to a central hub or repeater. This wiring was cheaper than coaxial cable and was similar to the wiring used in residential and business telephone wiring systems. LattisNet was such a commercial success that in 1990 the 802.3 committee approved a new standard called 10BaseT for Ethernet that ran over twisted-pair wiring. 10BaseT soon superseded the coaxial forms of Ethernet because of its ease of installation and because its hierarchical star-wired topology was a good match for the architectural topology of multistory buildings.

In other Ethernet developments, fiber-optic cabling, first developed in the early 1970s by Corning, found its first commercial networking application in Ethernet networking in 1984. (The technology itself was standardized as 10BaseFL in the early 1990s.) In 1988 the first fiber-optic transatlantic undersea cable was laid and greatly increased the capacity of transatlantic communication systems.

Ethernet bridges became available in 1984 from DEC and were used both to connect separate Ethernet LANs to make large networks and to reduce traffic bottlenecks on overloaded networks by splitting them into separate segments. Routers could be used for similar purposes, but bridges generally offered better price and performance, as well as less complexity, during the 1980s. Again, market developments preceded standards, as the IEEE 802.1D Bridge Standard, which was initiated in 1987, was not standardized until 1990.

In the UNIX arena, the development of the Network File System (NFS) by Sun Microsystems in 1985 resulted in a proliferation of diskless UNIX workstations having built-in Ethernet interfaces. This development helped drive the demand for Ethernet and accelerated the evolution of Ethernet bridging technologies into today's switched networks. By 1985 the rapidly increasing numbers of UNIX hosts and LANs connected to the ARPANET began to transform it from what had been mainly a network of mainframe and minicomputer systems into something like what it is today. The first UNIX implementation of TCP/IP came in v4.2 of Berkeley's BSD UNIX, from which other vendors such as Sun Microsystems quickly ported their versions of TCP/IP. Although PC-based LANs rapidly grew in popularity in business and corporate settings during the 1980s, UNIX continued to dominate in academic and professional high-end computing environments as the mainframe environment declined.

IBM introduced its Token Ring networking technology in 1985 as an alternative LAN technology to Ethernet. IBM had submitted its technology to the IEEE in 1982 and the 802.5 committee standardized it in 1984. IBM soon supported the integration of Token Ring with its existing SNA networking services and protocols for IBM mainframe computing environments. The initial Token Ring specifications delivered data at 1 Mbps and 4 Mbps, but it dropped the 1-Mbps version in 1989 when it introduced a newer 16-Mbps version. Interestingly, no formal IEEE specification exists for 16-Mbps Token Ring—vendors simply adopted IBM's technology for the product. Efforts were made to develop high-speed Token Ring, but these have finally been abandoned and today Ethernet reigns supreme.

Also in the field of local area networking, in 1982 the American National Standards Institute (ANSI) began standardizing the specifications for Fiber Distributed Data Interface (FDDI). FDDI was designed to be a high-speed (100 Mbps) fiber-optic networking technology for LAN backbones on campuses and industrial parks. The final FDDI specification was completed in 1988, and deployment in campus LAN backbones grew during the late 1980s and the early 1990s. But today FDDI is considered legacy technology and has been superseded in most places by Fast Ethernet and Gigabit Ethernet (GbE).

In 1983 the ISO developed an abstract seven-layer model for networking called the Open Systems Interconnection (OSI) reference model. Although some commercial networking products were developed based on OSI protocols, the standard never really took off, primarily because of the predominance of TCP/IP. Other standards from the ISO and ITU that emerged in the 1980s included the X.400 electronic messaging standards and the X.500 directory recommendations, both of which held sway for a while but have now largely been superseded—X.400 by the Internet's Simple Mail Transfer Protocol (SMTP) and X.500 by Lightweight Directory Access Protocol (LDAP).

A major event in the telecommunications/WAN field in 1984 was the divestiture of AT&T as the result of the seven-year antitrust suit brought against AT&T by the U.S. Justice Department. AT&T's 22 Bell operating companies were formed into 7 new RBOCs (only 4 are left today). This meant the end of the old Bell telephone system, but these RBOCs soon formed the Bellcore telecommunications research establishment to replace the defunct Bell Laboratories. The United States was then divided into Local Access and Transport Areas (LATAs), with intra-LATA communication handled by local exchange carriers (the Bell Operating Companies or BOCs) and inter-LATA communication handled by inter-exchange carriers (IXCs) such as AT&T, MCI, and Sprint Corporation.

The result of the breakup was increased competition, which led to new WAN technologies and generally lower costs. One of the first effects was the offering of T1 services to subscribers in 1984. Until then, this technology had been used only for backbone circuits for long-distance communication. New hardware devices were offered to take advantage of the increased bandwidth, especially high-speed T1 multiplexers, or muxes, that could combine voice and data in a single communication stream. The year 1984 also saw the development of digital Private Branch Exchange (PBX) systems by AT&T, bringing new levels of power and flexibility to corporate subscribers.

The Signaling System #7 (SS7) digital signaling system was deployed within the PSTN in the 1980s, first in Sweden and later in the United States. SS7 made new telephony services available to subscribers, such as caller ID, call blocking, and automatic callback.

The first trials of ISDN, a fully digital telephony technology that runs on existing copper local loop lines, began in Japan in 1983 and in the United States in 1987. All major metropolitan areas in the United States have since been upgraded to make ISDN available to those who want it, but ISDN has not caught on in the United States as a WAN technology as much as it has in Europe.

The 1980s also saw the standardization of SONET technology, a high-speed physical layer (PHY) fiber-optic networking technology developed from time-division multiplexing (TDM) digital telephone system technologies. Before the divestiture of AT&T in 1984, local telephone companies had to interface their own TDM-based digital telephone systems with proprietary TDM schemes of long-distance carriers, and incompatibilities created many problems. This provided the impetus for creating the SONET standard, which was finalized in 1989 through a series of Comité Consultatif International Télégraphique et Téléphonique (CCITT; anglicized as International Telegraph and Telephone Consultative Committee) standards known as G.707, G.608, and G.709. By the mid-1990s almost all long-distance telephone traffic in the United States used SONET on trunk lines as the physical interface.

The 1980s brought the first test implementations of Asynchronous Transfer Mode (ATM) high-speed cell-switching technologies, which could use SONET as the physical interface. Many concepts basic to ATM were developed in the early 1980s at the France-Telecom laboratory in Lannion, France, particularly the PRELUDE project, which demonstrated the feasibility of end-to-end ATM networks running at 62 Mbps. The CCITT standardized the 53-byte ATM cell format in 1988, and the new technology was given a further push with the creation of the ATM Forum in 1991. Since then, use of ATM has grown significantly in telecommunications provider networks and has become a high-speed backbone technology in many enterprise-level networks around the world. However, the vision of ATM on users' desktops has not been realized because of the emergence of cheaper Fast Ethernet and GbE LAN technologies and because of the complexity of ATM itself.

The convergence of voice, data, and broadcast information remained a distant vision throughout the 1980s and was even set back because of the proliferation of networking technologies, the competition between cable and broadcast television, and the slow adoption of residential ISDN. New services did appear, however, especially in the area of commercial online services such as America Online (AOL), CompuServe, and Prodigy, which offered consumers e-mail, bulletin board systems (BBSs), and other services.

A significant milestone in the development of the Internet occurred in 1982 when the networking protocol of ARPANET was switched from NCP to TCP/IP. On January 1, 1983, NCP was turned off permanently—anyone who had not migrated to TCP/IP was out of luck. ARPANET, which connected several hundred systems, was split into two parts, ARPANET and MILNET.

The first international use of TCP/IP took place in 1984 at the Conseil Européen pour la Recherche Nucléaire (CERN), a physics research center located in Geneva, Switzerland. TCP/IP was designed to provide a way of networking different computing architectures in heterogeneous networking environments. Such a protocol was badly needed because of the proliferation of vendor-specific networking architectures in the preceding decade, including "homegrown" solutions developed at many government and educational institutions. TCP/IP made it possible to connect diverse architectures such as UNIX workstations, VMS minicomputers, and Cray supercomputers into a single operational network. TCP/IP soon superseded proprietary protocols such as Xerox Network Systems (XNS), ChaosNet, and DECnet. It has since become the de facto standard for internetworking all types of computing systems.

CERN was primarily a research center for high-energy particle physics, but it became an early European pioneer of TCP/IP and by 1990 was the largest subnetwork of the Internet in Europe. In 1989 a CERN researcher named Tim Berners-Lee developed the Hypertext Transfer Protocol (HTTP) that formed the basis of the World Wide Web (WWW). And all of this developed as a sidebar to the real research that was being done at CERN—slamming together protons and electrons at high speeds to see what fragments appeared!

Also important to the development of Internet technologies and protocols was the introduction of the Domain Name System (DNS) in 1984. At that time, ARPANET had more than 1000 nodes and trying to remember their numerical IP addresses was a headache. DNS greatly simplified that process. Two other Internet protocols were introduced soon afterwards: NNTP was developed in 1987, and Internet Relay Chat (IRC) was developed in 1988.

Other systems paralleling ARPANET were developed in the early 1980s, including the research-oriented Computer Science NETwork (CSNET), and the Because It's Time NETwork (BITNET), which connected IBM mainframe computers throughout the educational community and provided e-mail services. Gateways were set up in 1983 to connect CSNET to ARPANET, and BITNET was similarly connected to ARPANET. In 1989, BITNET and CSNET merged into the Corporation for Research and Educational Networking (CREN).

In 1986 the National Science Foundation NETwork (NSFNET) was created. NSFNET networked the five national supercomputing centers together using dedicated 56-Kbps lines. The connection was soon seen as inadequate and was upgraded to 1.544-Mbps T1 lines in 1988. In 1987, NSF and Merit Networks agreed to jointly manage the NSFNET, which had effectively become the backbone of the emerging Internet. By 1989 the Internet had grown to more than 100,000 hosts, and the Internet Engineering Task Force (IETF) was officially created to administer its development. In 1990, NSFNET officially replaced the aging ARPANET and the modern Internet was born, with more than 20 countries connected.

Cisco Systems was one of the first companies in the 1980s to develop and market routers for Internet Protocol (IP) internetworks, a business that today is worth billions of dollars and is a foundation of the Internet. Hewlett-Packard was Cisco's first customer for its routers, which were originally called gateways.

In wireless telecommunications, analog cellular was implemented in Norway and Sweden in 1981. Systems were soon rolled out in France, Germany, and the United Kingdom. The first U.S. commercial cellular phone system, which was named the Advanced Mobile Phone Service (AMPS) and operated in the 800-MHz frequency band, was introduced in 1983. By 1987 the United States had more than 1 million AMPS cellular subscribers, and higher-capacity digital cellular phone technologies were being developed. The Telecommunications Industry Association (TIA) soon developed specifications and standards for digital cellular communication technologies.

A landmark event that was largely responsible for the phenomenal growth in the PC industry (and hence the growth of the client/server model and local area networking) was the release of the first version of Microsoft's text-based, 16-bit MS-DOS operating system in 1981. Microsoft, which had become a privately held corporation with Bill Gates as president and chairman of the board and Paul Allen as executive vice president, licensed MS-DOS version 1 to IBM for its PC. MS-DOS continued to evolve and grow in power and usability until its final version, MS-DOS 6.22, which was released in 1993. (I still carry around a DOS boot disk wherever I go in case I need it—don't you?) Anyway, one year after the first version of MS- DOS was released in 1981, Microsoft had its own fully functional corporate network, the Microsoft Local Area Network (MILAN), which linked a DEC 206, two PDP-11/70s, a VAX 11/250, and a number of MC68000 machines running XENIX. This type of setup was typical of the heterogeneous computer networks that characterized the early 1980s.

In 1983, Microsoft unveiled its strategy to develop a new operating system called Windows with a graphical user interface (GUI). Version 1 of Windows, which shipped in 1985, used a system of tiled windows that allowed users to work with several applications simultaneously by switching between them. Version 2 was released in 1987 and supported overlapping windows as well as expanded memory.

Microsoft launched its SQL Server relational database server software for LANs in 1988. In its current version, SQL Server 2000 is an enterprise-class application that competes with other major database platforms such as Oracle and DB2. IBM and Microsoft jointly released their 32-bit OS/2 operating system in 1987 and released OS/2 1.1 with Presentation Manager a year later.

In miscellaneous developments, IBM researchers developed the Reduced Instruction Set Computing (RISC) processor architecture in 1980. Apple Computer introduced its Macintosh computing platform in 1984 (the successor of its Lisa system), which introduced a windows-based GUI that was the precursor to Windows. Apple also introduced the 3.5-inch floppy disk in 1984. Sony Corporation and Philips developed CD-ROM technology in 1985. (Recordable CD-R technologies were developed in 1991.) IBM released its AS/400 midrange computing system in 1988, which continues to be popular to this day.

1990s

The 1990s were an explosive decade in every aspect of networking, and we can only touch on a few highlights here. Ethernet continued to evolve as a LAN technology and began to eclipse competing technologies such as Token Ring and FDDI. In 1991, Kalpana Corporation began marketing a new form of bridge called a LAN switch, which dedicated the entire bandwidth of a LAN to a single port instead of sharing it among several ports. Later known as Ethernet switches or Layer 2 switches, these devices quickly found a niche in providing dedicated high-throughput links for connecting servers to network backbones. Layer 3 switches soon followed, eventually displacing traditional routers in most areas of enterprise networking except for WAN access. Layer 4 and higher switches are now popular in server farms for load balancing and fault tolerance purposes.

The rapid evolution of the PC computing platform and the rise of bandwidth-hungry applications created a need for something faster than 10-Mbps Ethernet, especially on network backbones. The first full-duplex Ethernet products, offering speeds of 20 Mbps, became available in 1992. In 1995 work began on a standard for full-duplex Ethernet; it was finalized in 1997. A more important development was Grand Junction Networks' commercial Ethernet bus, introduced in 1992, which functioned at 100 Mbps. Spurred by this advance, the 802.3 group produced the 802.3u 100BaseT Fast Ethernet standard for transmission of data at 100 Mbps over both twisted-pair copper wiring and fiber-optic cabling.

Although the jump from 10-Mbps to 100-Mbps Ethernet took almost 15 years, a year after the 100BaseT Fast Ethernet standard was released work began on a 1000-Mbps version of Ethernet popularly known as Gigabit Ethernet (GbE). Fast Ethernet was beginning to be deployed at the desktop, and this was putting enormous strain on the FDDI backbones that were deployed on many commercial and university campuses. FDDI also operated at 100 Mbps (or 200 Mbps if fault tolerance was discarded in favor of carrying traffic on the redundant ring), so a single Fast Ethernet desktop connection could theoretically saturate the capacity of the entire network backbone. Asynchronous Transfer Mode (ATM), a broadband cell-switching technology used primarily in telecommunication/WAN environments, was briefly considered as a possible successor to FDDI for backboning Ethernet networks together, and LAN emulation (LANE) was developed to carry LAN traffic such as Ethernet over ATM. However, ATM is much more complex than Ethernet, and a number of companies saw extending Ethernet speeds to 1000 Mbps as a way to provide network backbones with much greater capacity using technology that most network administrators were already familiar with. As a result, the 802 group called 802.3z developed a GbE standard called 1000BaseX, which it released in 1998. Today GbE is the norm for LAN backbones, and Fast Ethernet is becoming ubiquitous at the desktop level. Work is even underway on extending Ethernet technologies to 10 gigabits per second (Gbps). A competitor of GbE for high-speed collapsed backbone interconnects, called Fibre Channel, was conceived by an ANSI committee in 1988 but is used mainly for storage area networks (SANs).

The 1990s saw huge changes in the landscape of telecommunications providers and their services. "Convergence" became a major buzzword, signifying the combining of voice, data, and broadcast information into a single medium for delivery to businesses and consumers through broadband technologies such as metropolitan Ethernet, Digital Subscriber Line (DSL), and cable modem systems. The cable modem was introduced in 1996, and by the end of the decade broadband residential Internet access through cable television systems had become a strong competitor with telephone-based systems such as Asymmetric Digital Subscriber Line (ADSL) and G.Lite, another variant of DSL.

Also in the 1990s, Voice over IP (VoIP) emerged as the latest "Holy Grail" of networking and communications and promised businesses huge savings by routing voice telephone traffic over existing IP networks. VoIP technology works, but the bugs are still being ironed out and deployments remain slow. Recent developments in VoIP standards, however, may help propel deployment of this technology in coming years.

The first public frame relay packet-switching services were offered in North America in 1992. Companies such as AT&T and Sprint installed a network of frame relay nodes across the United States in major cities, where corporate networks could connect to the service through their local telco. Frame relay began to eat significantly into the deployed base of more expensive dedicated leased lines such as the T1 or E1 lines that businesses used for their WAN solutions, resulting in lower prices for these leased lines and greater flexibility of services. In Europe frame relay has been deployed much more slowly, primarily because of the widespread deployment of packet-switching networks such as X.25.

The Telecommunications Act of 1996 was designed to spur competition in all aspects of the U.S. telecommunications market by allowing the RBOCs access to long-distance services and IXCs access to the local loop. The result has been an explosion in technologies and services offered by new companies called competitive local exchange carriers (CLECs), with mergers and acquisitions changing the nature of the service provider landscape almost daily.

The 1990s saw a veritable explosion in the growth of the Internet and the development of Internet technologies. As mentioned earlier, ARPANET was replaced in 1990 by NSFNET, which by then was commonly called the Internet. At the beginning of the 1990s, the Internet's backbone consisted of 1.544-Mbps T1 lines connecting various institutions, but in 1991 the process of upgrading these lines to 44.735-Mbps T3 circuits began. By the time the Internet Society (ISOC) was chartered in 1992, the Internet had grown to an amazing 1 million hosts on almost 10,000 connected networks. In 1993 the NSF created Internet Network Information Center (InterNIC) as a governing body for DNS. In 1995 the NSF stopped sponsoring the Internet backbone and NSFNET went back to being a research and educational network. Internet traffic in the United States was routed through a series of interconnected commercial network providers.

The first commercial Internet service providers (ISPs) emerged in the early 1990s when the NSF removed its restrictions against commercial traffic on the NSFNET. Among these early ISPs were Performance Systems International (PSI), UUNET, MCI, and Sprintlink. (The first public dial-up ISP was actually The World, with the URL *www.world.std.com*.) In the mid-1990s, commercial online networks such as AOL, CompuServe, and Prodigy provided gateways to the Internet to subscribers. Later in the decade, Internet deployment grew exponentially, with personal Internet accounts proliferating by the tens of millions around the world, new technologies and services developing, and new paradigms evolving for the economy and business. It would take a whole book to talk about all the ways the Internet has changed our lives.

Many Internet technologies and protocols have come and gone quickly. Archie, an FTP search engine developed in 1990, is hardly used today. The WAIS protocol for indexing, storing, and retrieving full-text documents, which was developed in 1991, has been eclipsed by Web search technologies. Gopher, which was created in 1991, grew to a worldwide collection of interconnected file systems, but most Gopher servers have now been turned off. Veronica, the Gopher search tool developed in 1992, is obviously obsolete as well. Jughead later supplemented Veronica but has also become obsolete. (There never was a Betty.)

The most obvious success story among Internet protocols has been HTTP, which, with HTML and the system of URLs for addressing, has formed the basis of the Web. Tim Berners-Lee and his colleagues created the first Web server (whose fully qualified DNS name was info.cern.ch) and Web browser software using the NeXT computing platform that was developed by Apple pioneer Steve Jobs. This software was ported to other platforms, and by the end of the decade more than 6 million registered Web servers were running, with the numbers growing rapidly.

Lynx, a text-based Web browser, was developed in 1992. Mosaic, the first graphical Web browser, was developed in 1993 for the UNIX X Windows platform by Marc Andreessen while he was a student at the National Center for Supercomputing Applications (NCSA). At that time, there were only about 50 known Web servers, and HTTP traffic amounted to only about 0.1 percent of the Internet's traffic. Andreessen left school to start Netscape Communications, which released its first version of Netscape Navigator in 1994. Microsoft Internet Explorer 2 for Windows 95 was released in 1995 and rapidly became Netscape Navigator's main competition. In 1995, Bill Gates announced Microsoft's wide-ranging commitment to support and enhance all aspects of Internet technologies through innovations in the Windows platform, including the popular Internet Explorer Web browser and the Internet Information Server (IIS) Web server platform of Windows NT. Another initiative in this direction was Microsoft's announcement in 1996 of its ActiveX technologies, a set of tools for active content such as animation and multimedia for the Internet and the PC.

In cellular communications technologies, the 1990s were clearly the "digital decade." The work of the TIA resulted in 1991 in the first standard for digital cellular communication, the TDMA Interim Standard 54 (IS-54). Digital cellular was badly needed because the analog cellular subscriber market in the United States had grown to 10 million subscribers in 1992 and 25 million subscribers in 1995. The first tests of this technology, based on Time Division Multiple Access (TDMA) technology, took place in Dallas, Texas, and in Sweden, and were a success. This standard was revised in 1994 as TDMA IS-136, which is commonly referred to as Digital Advanced Mobile Phone Service (D-AMPS).

Meanwhile, two competing digital cellular standards also appeared. The first was the CDMA IS-95 standard for CDMA cellular systems based on spread spectrum technologies, which was first proposed by

QUALCOMM in the late 1980s and was standardized by the TIA as IS-95 in 1993. Standards preceded implementation, however; it was not until 1996 that the first commercial CDMA cellular systems were rolled out.

The second system was the Global System for Mobile Communication (GSM) standard developed in Europe. (GSM originally stood for Groupe Spéciale Mobile.) GSM was first envisioned in the 1980s as part of the movement to unify the European economy, and the European Telecommunications Standards Institute (ETSI) determined the final air interface in 1987. Phase 1 of GSM deployment began in Europe in 1991. Since then, GSM has become the predominant system for cellular communication in over 60 countries in Europe, Asia, Australia, Africa, and South America, with over 135 mobile networks implemented. However, GSM implementation in the United States did not begin until 1995.

In the United States, the FCC began auctioning off portions of the 1900-MHz frequency band in 1994. Thus began the development of the higher-frequency Personal Communications System (PCS) cellular phone technologies, which were first commercially deployed in the United States in 1996.

Establishment of worldwide networking and communication standards continued apace in the 1990s. For example, in 1996 the Unicode character set, a character set that can represent any language of the world in 16-bit characters, was created, and it has since been adopted by all major operating system vendors.

In client/server networking, Novell in 1994 introduced Novell NetWare 4, which included the new Novell Directory Services (NDS), then called NetWare Directory Services. NDS offered a powerful tool for managing hierarchically organized systems of network file and print resources and for managing security elements such as users and groups. NetWare is now in version 6 and NDS is now called Novell eDirectory.

In other developments, the U.S. Air Force launched the twenty-fourth satellite of the Global Positioning System (GPS) constellation in 1994, making possible precise terrestrial positioning using handheld satellite communication systems. RealNetworks released its first software in 1995, the same year that Sun Microsystems announced the Java programming language, which has grown in a few short years to rival C/C++ in popularity for developing distributed applications. Amazon.com was launched in 1995 and has become a colossus of cyberspace retailing in a few short years. Microsoft WebTV (now MSN TV), introduced in 1997, is beginning to make inroads into the residential Internet market.

Finally, the 1990s were, in a very real sense, the decade of Windows. No other technology has had as vast an impact on ordinary computer users as Windows, which brought to homes and workplaces the power of PC computing and the opportunity for client/server computer networking. Version 3 of Windows, which was released in 1990, brought dramatic increases in performance and ease of use over earlier versions, and Windows 3.1, released in 1992, quickly became the standard desktop operating system for both corporate and home users. Windows for Workgroups 3.1 quickly followed that same year. It integrated networking and workgroup functionality directly into the Windows operating system, allowing Windows users to use the corporate computer network for sending e-mail, scheduling meetings, sharing files and printers, and performing other collaborative tasks. In fact, it was Windows for Workgroups that brought the power of computer networks from the back room to users' desktops, allowing them to perform tasks previously possible only for network administrators.

In 1992, Microsoft released the first beta version of its new 32-bit network operating system, Windows NT. In 1993 came MS-DOS 6, as Microsoft continued to support users of text-based computing environments. That was also the year that Windows NT and Windows for Workgroups 3.11 (the final version of 16-bit Windows) were released. In 1995 came the long-awaited release of Windows 95, a fully integrated 32-bit desktop operating system designed to replace MS-DOS, Windows 3.1, and Windows for Workgroups 3.11 as the mainstream desktop operating system for personal computing. Following in 1996 was Windows NT 4, which included enhanced networking services and a new Windows 95–style user interface. Windows 95 was superseded by Windows 98 and later by Windows Millennium Edition (Me).

At the turn of the millennium came the long-anticipated successor to Windows NT, the Windows 2000 family of operating systems, which includes Windows 2000 Professional, Windows 2000 Server, Windows 2000 Advanced Server, and Windows 2000 Datacenter Server. The Windows family has how grown to encompass the full range of networking technologies, from embedded devices and Personal Digital Assistants (PDAs) to desktop and laptop computers to heavy-duty servers running the most advanced, powerful, scalable, business-critical, enterprise-class applications.

2000 and Beyond

It is early in the new millennium—where are we now and where are we going? The first question is relatively easy to answer:

- In the LAN field, Ethernet reigns supreme. Token Ring and FDDI are dead-end technologies, and ATM never caught on.
- Microsoft continues to be by far the dominant player on the desktop, and Windows XP has finally united the separate Windows 95, Windows 98, Windows Me, and Windows NT/2000 code streams into a single platform.
- In the enterprise (large companies), Windows NT and Windows 2000 have proved enormously popular as file, print, and application server platforms. Microsoft Exchange has eclipsed Lotus Notes as the dominant messaging platform, and Microsoft SQL Server is giving Oracle and DB2 a run for their money. IIS and Apache continue to fight it out for Web server supremacy, with each side claiming victory in different market segments. And Linux has established a niche for itself in the enterprise and continues to grow, mostly at the expense of Novell NetWare and UNIX platforms.
- Wireless networking using the 802.11b standard has exploded across the enterprise, but security continues to be a big concern for these networks, as "drive-by hackers" have shown with their laptops and BMWs. Data transmission over cellular communication systems is still incredibly slow in most areas, as 2G technologies are slowly superseded by 2.5G ones.
- Metropolitan Ethernet is the hottest WAN technology, letting companies access GbE services with plug-and-play simplicity. DSL is having trouble establishing itself as a viable enterprise option, mainly due to reliability issues. T1 prices are still ridiculously high, but not likely to change much due to consolidation in the service provider industry. And despite its lack of glamour, frame relay is going strong and still growing in the enterprise WAN.
- The Internet is now the blood and backbone of most businesses, but the number of Internet businesses that failed in the dot-com bust defies description. The Internet access market continues to consolidate, and broadband Internet access is now in the tens of millions of subscribers and rising rapidly. The "Big Three" online portals—MSN, Yahoo!, and AOL—now comprise an estimated 20 percent of all Internet traffic. Apart from eBay and Amazon, the number of truly great e-business success stories is amazingly small.
- B2B (business to business) e-business is on the rise but mostly hidden from view in the form of e-marketplaces for different corporate sectors. And XML, which promised to revolutionize e-business, is still a distant second in popularity to good old EDI.

We could say a lot more, but let's briefly address the questions, "Where are we going? What might the rest of this decade hold as far as the growth and evolution of networking in all its forms?" Here are a few "hedged-bet" predictions for you to consider:

- Will we have 3G wireless broadband connectivity for everyone, everywhere, all the time? Or will most major cellular providers go bankrupt, throwing a monkey wrench into 3G deployments and putting them years behind schedule?
- Will 10 GbE provide users and companies with unparalleled amounts of bandwidth? Or will demand for bandwidth rise even more rapidly than new technologies can accomodate?

- Will P2P file sharing platforms finally bring the Internet (and most enterprises) to its knees? Or will Dense Wavelength Division Multiplexing (DWDM) be a knight in shining armor riding to the rescue?
- Will viruses, worms, Trojans, and other forms of "malware" continue to wreak havoc with the world economy? Or will a solution be found to this growing problem that does not involve disconnecting the network cable from your computer and locking it in your closet?
- Will Bluetooth usher in an exciting high-tech world of bionic humans carrying dozens of spontaneously networked devices all the time? Or will somebody finally invent a single device that does it all?
- And will rapid evolution in computer technologies, programming paradigms, networking architectures, and the Internet make us less human? Or more?

Let the reader decide—we will give you a partial answer when the third edition of this book comes out!

The Scope of This Encyclopedia

Now that you have an idea of what networking is all about and how it has evolved over the years, you probably realize that the scope of this encyclopedia is fairly broad. Most of the information found in this book falls into these categories:

- Information about networking concepts, technologies, standards, and hardware—including such things as Ethernet, Token Ring, bandwidth, latency, hubs, switches, OSI, and X.500.
- Information about the telecommunications industry, including WAN services such as frame relay, leased lines, and ATM. Also included is coverage of various wireless networking and cellular communication technologies.
- Information about the Internet and its standards, protocols, services, architecture, and implementation—including such things as HTTP, SMTP, Web servers, Web browsers, TCP/IP, BGP, and ASP.
- Information about popular software technologies used in developing network-aware solutions, including such platforms as Windows and Linux and such applications as Apache.

Also included in this book are numerous entries from areas that are usually considered peripheral to networking per se, including network-aware programming technologies such as Java and ActiveX and cryptography standards used in networking and communication, such as Advanced Encryption Standard (AES) and Public Key Cryptography Standards (PKCS). Networking professionals and students are likely to encounter many of these terms in their daily work and reading and will benefit from the inclusion of this material.

Finally, since this is the *Microsoft* Encyclopedia of Networking, there is extensive coverage of Microsoft platforms and products, including all versions of Windows, the .NET platform and .NET Server family, services such as TechNet and MSDN, the Microsoft Web site (one of the largest in the world), and Microsoft Corporation itself.

Who This Work Is For

This book will be an invaluable reference and learning tool for all levels of networking professionals, ranging from the seasoned professional with many years of hands-on experience to the individual pursuing an entry-level certification such as CompTIA's Network+. Individuals working toward the popular Microsoft Certified Systems Engineer (MCSE) will find the book particularly helpful in their endeavors.

Many other professionals will also find this work useful, including consultants, IT implementers, sales and marketing people, and the interested lay reader.

How This Work Is Organized

The articles in this work are listed in alphabetical order, of course, and their lengths range from a few paragraphs to several pages. Longer articles are organized for readability into a number of subsections, including Overview, History, Uses, Types, Comparison, Architecture, Implementation, Examples, Advantages and Disadvantages, Marketplace, Issues, Prospects, and Notes. Figures are included in many articles to help explain key concepts. Most articles end with a section called See Also that has cross-references to related entries elsewhere in the encyclopedia. The section called For More Information provides URLs where you can find further information online.

An effort has been made to minimize technical jargon while maintaining technical accuracy. Coverage has included up-to-the-minute developments at the time of writing, but remember that networking technologies and products change rapidly. Microsoft Press provides short updates and corrections for its books at *www.mspress.microsoft.com/support*, but major updates in material will have to wait until the next edition.

Disclaimer

Information contained in this work has been obtained from sources believed to be reliable. Although the authors and Microsoft Press have made every effort to be accurate, neither the authors nor the publisher assume any liability or responsibility for any inaccuracy or omissions contained in this book, or for any loss or damage arising from the information presented. In other words, the information provided in this book is presented on an "as is" basis. Mention of companies, service providers, vendors, and products in this work are not to be viewed as endorsements by either the authors or by Microsoft.

Comments and Questions

If you have comments, questions, or ideas regarding this encyclopedia, please direct them to Microsoft Press at *MSPInput@microsoft.com* or at the following postal address:

Microsoft Press
Attn: Microsoft Encyclopedia of Networking Editor
One Microsoft Way
Redmond, WA 98052-6399

Please note that product support is not offered through the above addresses.

You can also contact the authors of this work directly through their web site, *www.mtit.com*.

Numbers and Symbols

1Base5

An obsolete 1 megabit per second (Mbps) local area network (LAN) networking technology.

Overview

1Base5 was actually developed after the 10Base5 Standard Ethernet specification was ratified but before the ratification of the 10BaseT standard. It was developed as an initial attempt to deploy computer networking over existing unshielded twisted-pair (UTP) cabling at a time when Ethernet was still based on coaxial cabling. The popular name for 1Base5 networking technologies was StarLAN because it was wired in a hierarchical star topology. When 10BaseT was ratified as an Institute of Electrical and Electronics Engineers (IEEE) standard in 1990, however, StarLAN and similar technologies quickly became obsolete and fell into disuse.

See Also: *10BaseT, Ethernet*

2B+D

Basic Rate Integrated Services Digital Network (ISDN) service, which uses two B channels and one D channel for signaling and communications.

See Also: *Integrated Services Digital Network (ISDN)*

2B1Q

Stands for Two Binary One Quaternary, a physical layer encoding mechanism for translating digital information into electrical signals, standardized by the American National Standards Institute (ANSI) and used in Integrated Services Digital Network (ISDN) networks. In 2B1Q, four electrical amplitude and polarity values are used to represent binary information.

See Also: *line coding*

2G

Stands for second generation and refers to widely deployed cellular communications systems such as Digital Advanced Mobile Phone Service (D-AMPS), Time Division Multiple Access (TDMA), Code Division Multiple Access (CDMA), Global System for Mobile Communications (GSM), and Personal Communication Services (PCS) systems.

See Also: *3G*

2.5G

A label some vendors use to refer to several interim cellular communications systems currently being deployed as a prelude to full third-generation (3G) systems.

Overview

For many cellular systems, upgrading immediately from existing second-generation (2G) systems to full 3G functionality is costly and complex. Furthermore, some vendors question whether there is a need for the high (2 megabits per second) data rates promised by 3G and suggest that lower data rates in the hundreds of kilobits per second (Kbps) are more than sufficient for the majority of current applications. They cannot justify the enormous cost of an upgrade considering the insufficient demand for the type of interactive multimedia communications that 3G will support. Even 2.5G would be a significant leap forward from today's current 2G systems, where typical data rates are a mere 9.6, 14.4, or 19.2 Kbps.

As a result, some cellular service providers have opted to migrate from 2G to 3G in stages by first upgrading their existing Time Division Multiple Access (TDMA) and Code Division Multiple Access (CDMA) networks to interim technologies which offer much higher data transmission rates. These interim 2.5G systems include Enhanced Data Rates for Global Evolution (EDGE), developed by Ericsson, and High Data Rate (HDR), developed by Qualcomm.

For example, some TDMA networks that can carry data at only 19.2 Kbps are being upgraded first to General Packet Radio System (GPRS) overlaid on Global System for Mobile Communications (GSM) to support data transmission at 144 Kbps, and from there to EDGE which supports transmission rates of 384 Kbps. In fact, GPRS is a natural upgrade path for GSM-based systems to support Wireless Application Protocol (WAP)–based data communications easily and inexpensively at speeds from 10s to 100s of Kbps.

Similarly, many CDMA systems carrying data at 14.4 Kbps are being upgraded to intermediate technologies such as HDR before being fully upgraded to Wideband CDMA (W-CDMA) with its 2 megabits-per-second (Mbps) data rate.

In addition to the increased data rates of 2.5G systems compared to 2G (about an order of magnitude faster), another advantage is that 2.5G systems utilize packet-switching technologies that are more efficient in the transmission of IP data over cellular systems as opposed to the circuit-switching technologies in use by existing 2G systems.

Notes

Most 2.5G systems are asymmetric in their transmission speeds, supporting faster downloads than uploads. In this way they bear some similarity to cable modems and Asymmetric Digital Subscriber Line (ADSL).

Some vendors market their 2.5G systems as 3G, but this is a misnomer because they fall short of complying with the International Telecommunication Union (ITU)'s IMT-2000 standard that defines 3G technologies and systems.

See Also: *3G*

3G

Stands for third generation, an umbrella name for the latest generation of cellular phone networks capable of high-speed wireless data transmission rates of up to 2 megabits per second (Mbps). 3G technologies are occasionally referred to by the name broadband wireless.

Overview

The history of wireless cellular communications has had three distinct generations since its beginnings in the early 1980s. These generations are typically identified as follows:

- **1G (first generation of cellular communications):** This involved analog transmission of voice only (did not support data) over circuit-switched networks. 1G is represented by legacy systems such as the Advanced Mobile Phone Service (AMPS) introduced by AT&T in the early 1980s and still in use in some parts of North and South America. Other 1G systems included the Extended Total Access Communications System (E-TACS) used in Europe and Asia, the Nordic Mobile Telephone system used in Scandinavia, and the Total Access Communication System (TACS) used in Great Britain, Hong Kong, and Japan. 1G systems transmitted their traffic in clear (unencrypted) form.
- **2G (second generation):** This saw the development of digital cellular systems for transmitting digitally encoded voice and data (though data transmission speeds are limited to about 19.2 kilobits per second [Kbps]). Examples of 2G systems include Digital AMPS (D-AMPS), Time Division Multiple Access (TDMA), Code Division Multiple Access (CDMA), Global System for Mobile Communications (GSM), and Personal Communication Services (PCS) systems. 2G systems are circuit switched and support a variety of extended features such as encryption, Short Message Service (SMS), and fax transmission.
- **3G (third generation):** This was first envisioned by the International Telecommunication Union (ITU) in 1992 and had two aims. The first was to be a truly global digital packet-switched cellular system (as opposed to the circuit-switched 2G systems) for voice and data communications, where users could roam between continents without requiring new phones. The second was to provide consistent high-speed data transmission rates of up to 2 Mbps. Unfortunately, neither of these goals has been completely achieved.

In 1992 the ITU proposed a system called IMT-2000 as the single global 3G-based standard for cellular communications. In 1999 conflicts between carriers, regulators, and vendors in different countries and regions led to a compromise version of the IMT-2000 standard. The agreed-upon standard incorporated a mix of three different proposed versions, two of which use CDMA technologies and the third using TDMA. Existing CDMA providers will find it easier to upgrade to 3G technologies than TDMA providers will.

Types

Qualcomm has proposed a 3G upgrade for its popular 2G system cdmaOne, used throughout much of Asia and North America. The upgrade is called cdma2000 3XMC. It has recently been ratified by the ITU and is expected to provide real data rates of 1.117 Mbps. Other CDMA providers have proposed that an initial upgrade called cdma2000 1XMC be deployed first as an interim "2.5G" cellular system before full deployment of cdma2000 3XMC is achieved. The cdma2000 1XMC technology only supports real data rates of 144 Kbps, although vendor-proprietary extensions have been proposed to extend this.

Another 3G CDMA system similar to cdma2000 3XMC and currently being rolled out in some countries and regions is called Universal Mobile Telecommunications System (UMTS) or Wideband CDMA (W-CDMA) (carriers in Europe prefer the UMTS designation, but those in North America prefer W-CDMA or WCDMA). UMTS is designed to interoperate with existing GSM networks and will provide a natural upgrade path for these networks from 2G to 3G. The first country widely rolling out W-CDMA is Japan, which is using it to replace its Personal Digital Cellular (PDC) system, whose capacity is saturated. Unfortunately, UMTS/W-CDMA cannot be provisioned in the United States because the frequencies this technology requires have already been allocated by the Federal Communications Commission (FCC) for other uses. UTMS/W-CDMA supports wireless data transmission at 2 Mbps. Note, however, that this speed will be achievable for stationary users only—for mobile environments this slows to 384 Kbps and for fast-moving vehicles such as a car on the highway, it is down to 144 Kbps.

Another proposed 3G system based on TDMA instead of CDMA is called EDGE (Enhanced Data Rates for Global Evolution). EDGE is an upgrade to existing General Packet Radio Services (GPRS) systems and supports data rates of 384 Kbps.

Prospects

3G was originally envisioned to become widespread by 2000 (hence the name of the original proposed IMT-2000 system), but these systems are only beginning to be deployed (now pushed back to between 2003 and 2005, depending on the country or region). They provide data rates less than those anticipated, and have developed interoperability problems that may not be easily resolved.

3G technology is also expensive to develop and deploy. In this regard, Europe has a head start on the United States; however, the total cost of deploying 3G throughout the European Union (EU) has been estimated to be as high as $1 trillion. The long-term viability of many European 3G carriers may be affected by the high licensing fees imposed by governments for use of suitable radio spectrum. Most industry watchers expect a shakeout in the next few years, leaving only giants such as Deutsche Telekom, France Telecom, Vodafone, and a few others.

Many countries and regions, including the United Kingdom, Belgium, Germany, and Sweden, hold auctions to parcel off portions of 3G spectrum to the highest bidders. Carriers must quickly recoup these up-front costs to remain viable. Some countries and regions, such as Norway, Finland, France, and Spain, allocate spectrum on a fixed-fee basis to first-comers, but this practice is being challenged in the EU courts as a type of subsidy that is unfair and anticompetitive.

In the United States, AT&T laid out a road map in December 2000 for its deployment of 3G wireless that involves several intermediate steps. First, its existing TDMA network, which carries data at only 19.2 Kbps, will be upgraded to GSM with an overlay of GPRS to support data transmission at 144 Kbps. Then GSM/GPRS will be upgraded to EDGE to support data transmission rates of 384 Kbps. Finally, W-CDMA will be deployed to support data at 2 Mbps. Meanwhile, CDMA carriers such as Sprint Corporation and Verizon Communications are upgrading their systems to cdma2000 and beyond. This split between W-CDMA, supported by AT&T, and cdma2000, supported by Verizon and Sprint, presents some interoperability problems for users in North America, but efforts are underway to resolve these issues.

Ultimately, when 3G systems are fully operational, they will provide mobile users with the equivalent of broadband Internet access, opening up a new world of wireless Web-based services and applications.

Notes

Although 3G wireless systems such as UMTS will be capable of supporting data transmission speeds of 2 Mbps, this will be for stationary clients only, which includes laptop computers equipped such as 3G PC cards. Transmission speeds for mobile clients such as 3G cell phones and handsets will likely top out at 384 Kbps or lower, depending on the environment's reception characteristics.

Because of the high costs and technical challenges associated with rolling out 3G systems, some cellular communications providers are rolling out unofficial "2.5G" systems as a kind of intermediate step along the way to the high-speed data rates of 3G. For more information, see the article "2.5 G" elsewhere in this chapter.

For More Information

An alliance of regulators and vendors committed to remaining neutral in the 3G standards war is the Third Generation Partnership Project, whose site can be found at *www.3gpp.org*.

Details of the ITU's IMT-2000 standard can be found at *www.itu.int/imt2000*.

See Also: *2.5G, cellular communications*

3.1 kHz bearer service

A service provided by some telcos for transmitting data over voice trunk lines.

Overview

When supporting 3.1 kHz bearer service communications, telco switches must have trunk-line echo cancellation turned off because echo cancellation will corrupt data transmissions sent over voice lines. This service is a legacy telecommunications technology that is no longer widely implemented.

Notes

Some carriers call this service data-over-voice (DOV).

4G

An envisioned fourth-generation wireless cellular system to supersede 3G (third-generation) cellular.

Overview

4G is a term sometimes applied to proposed wireless networking systems using Orthogonal Frequency Division Multiplexing (OFDM). OFDM is a modulation scheme theoretically capable of transmitting data at rates of 622 megabits per second (Mbps), which is much higher than the 2 Mbps of the 3G wireless systems that are only now beginning to be deployed. OFDM is currently defined in two implementations, one supported by the Institute of Electrical and Electronics Engineers (IEEE) and the other by the European Telecommunications Standards Institute–Broadband Radio Access Networks (ETSI-BRAN). These two implementations are different in some respects, and efforts are underway by the OFDM Forum to harmonize these systems to reduce the incompatibilities that could result once 4G systems begin to materialize. Apart from these difficulties, 4G wireless networking systems are more of a dream than a reality.

See Also: *3G*

5-4-3 rule

A specification describing limitations on constructing certain kinds of Ethernet networks. The 5-4-3 rule applies specifically to Ethernet networks based on either the thinnet or thicknet cabling option.



5-4-3 rule. *This rule restricts bus-style Ethernet networks to five total segments, four repeaters, and three populated segments.*

Overview

According to the Ethernet specifications, thinnet (or thicknet) Ethernet network segments can be joined using repeaters to form larger networks, but there are limitations on how you can do this. The maximum number of segments you can join is five. To join these segments, you need to use four repeaters because Ethernet typically uses a bus topology in which all segments are joined linearly. However, in this configuration, no more than three of the segments can actually have computers attached to them, leaving two segments that are used only for extending distances rather than hosting computers. These two unpopulated segments are called inter-repeater links. You should not violate this rule when implementing Ethernet networks; otherwise, unreliable network communications might result.

See Also: *Ethernet*

6bone

A testbed for development of the next generation of the Internet Protocol (IP) protocol, IPv6.

Overview

The 6bone grew out of the IP Next Generation (IPng) project of the Internet Engineering Task Force (IETF) that led to the development of IPv6. It is an informal collaborative project among a number of groups around the world, operating under the oversight of the IETF's Next Generation Transition (NGtrans) Working Group. The 6bone began operation as a virtual network in which IPv6 packets were encapsulated in and tunneled over IPv4, but migration to native IPv6 is underway and should soon be completed.

The 6bone has been playing an important role in testing IPv6 before widespread migration from the current IPv4 (standard IP) networking protocol is recommended for public use. Projects such as FreeNet6, developed by Viagénie, and vendors such as Nortel Networks and 3Com Corporation have provided IPv6 researchers with gateways for tunneling from their IPv6 testbed deployments through the IPv4 Internet and over the 6bone to test and become familiar with the new IPv6 protocol.

For More Information

The official site for the 6bone can be found at *www.6bone.net.* You can also find information there about how to join your network to the 6bone.

If you want to connect an individual workstation to the 6bone, you can use Freenet6, which can be found at *www.freenet6.net*. This site enables IPv6 end stations to connect to the 6bone through IPv4 tunneling over the Internet. You must have a dual IPv4/6 stack to connect. You can download a preliminary IPv6 stack from Microsoft Research at *www.research.Microsoft.com/msripv6.*

See Also: *IPv6*

6to4

A mechanism for connecting networks running IPv6 by tunneling through the IPv4 Internet.

Overview

6to4 was developed as a transitional scheme to support the operation of IPv6 within an IPv4 world until the backbone of the Internet is completely migrated to IPv6. 6to4 works by encapsulating IPv6 packets inside IPv4 packets and transmitting them over the existing IPv4 Internet. In this way, different islands of IPv6 connectivity can be linked across the IPv4 ocean that constitutes the Internet.

A special IPv6 prefix is used to identify an encapsulated 6to4 packet. This header is represented in IPv6 address notation as 2002::/16 and identifies the IPv6 address space specially reserved by IANA for 6to4 tunneling.

For More Information

In order to use 6to4, you must install a dual IPv4/6 protocol stack on your machine. Microsoft is integrating basic support for IPv6 into its Windows XP and Windows .NET Server operating system platforms. You can also download a pre-liminary IPv6 stack from Microsoft Research at *www.research.microsoft.com/msripv6.*

See Also: *IPv6*

8mm

A format for tape backup developed by Exabyte Corporation.

Overview

8mm is the standard tape format for videotape, and Exabyte developed this format into a tape backup solution to take advantage of this medium's low cost. Typical 8mm tape drives can store up to 40 gigabytes (GB) of data on a tape, and data can be written to tape at speeds in excess of 6 megabytes per second (MBps) using compression or 3 MBps without compression. Exabyte 8mm tape drives are inexpensive, have high performance, and make an attractive tape backup solution for companies developing a disaster recovery plan.

For More Information

See Exabyte online at *www.exabyte.com.*

See Also: *tape format*

10Base2

An Institute of Electrical and Electronic Engineers (IEEE) standard for implementing 10 megabits per second (Mbps) Ethernet over thin coaxial cabling.

Overview

10Base2 is based on the 802.3 specifications of Project 802 developed by the IEEE. It was ratified as an IEEE standard in 1985 and quickly found its way into corporate networks for small local area networks (LANs) connected to larger 10Base5 backbones.

10Base2 is sometimes referred to as thinnet or thin coax because it uses thin coaxial cabling for connecting stations to form a network (as compared to 10Base5, which uses a thicker form of cabling and hence is called thicknet). The designation 10Base2 is derived from the network's speed (10 Mbps), the signal transmission method (baseband transmission), and the maximum segment length (185 meters, rounded off to 200 with the zeros removed). Another popular nickname for this technology was Cheapernet because thinnet cabling was considerably less costly than thicknet cabling.



10Base2. *A typical 10Base2 network.*

Implementation

10Base2 networks are wired together using a bus topology, in which individual stations (computers) are connected directly to one long cable. The maximum length of any particular segment of a 10Base2 network is 607 feet (185 meters). If distances longer than this are required, two or more segments must be connected using repeaters. Altogether, a total of five segments can be connected using four repeaters, as long as only three of the segments have stations (devices) attached to them. This is referred to as the 5-4-3 rule.

A 10Base2 segment should have no more than 30 stations wired to it. The minimum distance between these stations is 1.6 feet (0.5 meters). Stations are attached to the cable using BNC (British Naval Connector or Bayonet-Neill-Concelman) connectors, and the ends of the cabling have BNC cable connectors soldered or crimped to them.

10Base2 supports a maximum theoretical bandwidth of 10 Mbps, but in actuality the presence of collisions reduces this to more like 4 to 6 Mbps.

Notes

10Base2 networks are not deployed much anymore for two reasons. First, because their speed is limited to 10 Mbps, the networks perform poorly in today's bandwidth-hungry, Internet-connected world. Second, 10Base2 networks have a single point of failure—the long, linear bus cable used to connect the stations. A single break or loose connection brings down the entire network, thus every cable segment and station connection must be checked to determine the problem. If you are wiring an office for a small LAN with low bandwidth requirements, use 10BaseT instead, which is easier to manage and troubleshoot. For moderate to high bandwidth requirements, try using Fast Ethernet instead.

The two ends of a 10Base2 bus must be properly terminated. If they are not, signals will bounce and network communication will come to a halt.

See Also: *5-4-3 rule, 10Base5, 10BaseF, 10BaseT, Ethernet*

10Base5

An Institute of Electrical and Electronic Engineers (IEEE) standard for implementing 10 megabits per second (Mbps) Ethernet over coaxial cabling.

Overview

10Base5 is based on the 802.3 specifications of Project 802 developed by the IEEE. It was developed as a standard in the early 1980s and became hugely popular in corporate and campus networks. An earlier form of 10Mbps Ethernet developed by the DIX Consortium was superseded by 10Base5 when the IEEE 802.3 standard was created in 1983.

10Base5 is sometimes referred to as thicknet because it uses thick coaxial cabling for connecting stations to form a network (compared to 10Base2, which uses a thinner form of cable and is hence called thinnet). Another name for 10Base5 is Standard Ethernet because it was the first type of Ethernet to be implemented (it is also sometimes referred to as Original Ethernet, for obvious reasons). The designation 10Base5 is derived from the network's speed (10 Mbps), the signal transmission method (baseband transmission), and the maximum segment length (500 meters).

Implementation

10Base5 networks are wired together in a bus topology—that is, in a linear fashion using one long cable. The maximum length of any particular segment of a 10Base5 network is 1640 feet (500 meters). If distances longer than this are required, two or more segments must be connected using repeaters. Altogether, there can be a total of five segments connected using four repeaters, as long as only three of the segments have stations (computers) attached to them. This is referred to as the 5-4-3 rule.

A 10Base5 segment should have no more than 100 stations wired to it. These stations are not connected directly to the cable as in 10Base2 networks. Instead, a transceiver is attached to the cable, usually using a cable-piercing connector called a vampire tap. From the transceiver, a drop cable is attached, which then connects to the network interface card (NIC) in the computer. The minimum distance between transceivers attached to the cable is 8 feet (2.5 meters), and the maximum length for a drop cable is 164 feet (50 meters). Thicknet cable ends can have N-series connectors soldered or crimped on them for connecting segments together.

10Base5 was often used for backbones for large networks. In a typical configuration, transceivers on the thicknet backbone would attach to repeaters, which would join smaller thinnet segments to the thicknet backbone. In this way a combination of 10Base5 and 10Base2 standards could support sufficient numbers of stations for the needs of a moderately large company.

10Base5 supports a maximum bandwidth of 10 Mbps, but in actual networks, the presence of collisions reduces this to more like 4 to 6 Mbps.

Notes

10Base5 networks are legacy networks that are no longer being deployed, although some companies might choose to maintain existing ones for cost reasons. The complexity and bandwidth limitations of 10Base5 networks render them largely obsolete. If you are wiring an office for a small local area network (LAN) with low bandwidth requirements, use 10BaseT instead. For moderate to high bandwidth requirements, try using Fast Ethernet. If you are implementing a backbone for today's high-speed enterprise networks, Gigabit Ethernet (GbE) is now the preferred technology.

The two ends of a 10Base5 bus must be properly terminated. If they are not, signals will bounce and network communication will come to a halt.

See Also: *5-4-3 rule, 10Base2, 10BaseF, 10BaseT, 802.3, Ethernet, Fast Ethernet*

10BaseF

An Institute of Electrical and Electronic Engineers (IEEE) standard for implementing 10 megabits per second (Mbps) Ethernet over fiber-optic cabling.

Overview

10BaseF is based on the 802.3 specifications of Project 802 developed by the IEEE and differs from other forms of 10-Mbps Ethernet by using fiber-optic cabling instead of copper unshielded twisted-pair (UTP) cabling. The designation 10BaseF is derived from the network's speed (10 Mbps), the signal transmission method (baseband transmission), and the physical media used (fiber-optic cabling).

The 10BaseF standard actually consists of three separate standards describing different media specifications:

- **10BaseFB:** Defines how the synchronous data transmission occurs over the fiber-optic cabling.

  Using 10BaseFB segments, you can cascade or link synchronous fiber-optic hubs in configurations that are longer than traditional 10BaseT Ethernet networks and contain up to 1024 stations. This standard is more expensive and is not as widely implemented as 10BaseFL.
- **10BaseFL:** Defines the characteristics of the fiber-optic link between the nodes and the hub or concentrator. 10BaseFL replaces the older standard for fiber-optic link segments, Fiber-Optic Inter-Repeater Link (FOIRL) segments, which was developed in the 1980s. 10BaseFL is the most commonly implemented version of 10BaseF.
- **10BaseFP:** Defines the implementation of a star topology that does not use repeaters. 10BaseFP stands for Fiber Passive, and its segments can be only 500 meters (1640 feet) in length with a maximum of 33 stations connected. This standard is rarely used today.

Implementation

10BaseF is similar to 10BaseT in that each station is wired into a hub in a star topology to form the network. The maximum length of any segment of 10BaseF fiber-optic cabling is 6600 feet (2000 meters), compared to the 328 feet (100 meters) supported by 10BaseT, making 10BaseF suitable for long-haul interconnects.

The recommended cabling type for 10BaseF networks is 62.5-micron diameter fiber-optic cabling. This cable can be terminated with either ST connectors or SMA connectors, depending on the vendor and the hub configuration. Two-strand multimode fiber-optic cabling is used, with one strand allotted for transmitting data and the other for receiving data.

Marketplace

Nowadays, 10BaseF is only supported in legacy 10 Mbps Ethernet equipment and has been superseded by 100 Mbps Fast Ethernet in most circumstances for network backbones and interconnects.

Notes

10BaseF is preferable to 10BaseT in environments that are electrically noisy, such as in industrial areas, near elevator shafts, or around other motors or generators.

Fiber-optic cabling is often used for running cables between buildings. Differences in ground potential between the ends of copper cabling can induce voltages that can damage networking equipment if the ends are not grounded properly. Fiber-optic cabling also supports faster speeds than copper UTP cabling and provides a more suitable upgrade option to Fast Ethernet and beyond.

The maximum signal loss or attenuation on a given segment should be no more than 12.5 decibels. Using too many connectors in a segment of fiber-optic cabling can cause the attenuation to exceed this figure, which can lead to signal loss.

See Also: *10Base2, 10Base5, 10BaseT, 802.3, Ethernet*

10BaseT

An Institute of Electrical and Electronic Engineers (IEEE) standard for implementing 10 megabits per second (Mbps) Ethernet over twisted-pair cabling.

Overview

10BaseT is based on the 802.3 specifications of Project 802 developed by the IEEE and is the most popular form of 10-Mbps Ethernet. 10BaseT is deployed over structured cabling systems consisting of unshielded twisted-pair (UTP) cabling used for connecting end stations to centralized hubs to form a network. (Shielded twisted-pair [STP] cabling can also be used, but it never is.) The designation 10BaseT comes from the network's speed (10 Mbps), the signal transmission method (baseband transmission), and the physical medium used for transmission (twisted-pair cabling).

10BaseT became widely popular because of the earlier success of the Public Switched Telephone Network (PSTN), a hierarchical structured-wiring system to which 10BaseT bears many similarities. An advantage of 10BaseT over earlier 10 Mbps Ethernet systems such as 10Base5 and 10Base2 is that it is easier to manage because of the centralization of network traffic in hubs.

Implementation

In10BaseT networks, end stations such as workstations and servers are wired together in a star topology to a central hub. The UTP cabling used for wiring should be Category 3 (Cat3) cabling, Category 4 (Cat4) cabling, or Category 5 (Cat5) cabling, terminated with RJ-45 connectors. Patch panels can be used to organize wiring and provide termination points for cables running to wall plates in work areas. Patch cables then connect each port on the patch panel to the hub. Usually most of the wiring is hidden in a wiring cabinet and arranged on a rack for easy access.

The maximum length of any particular segment of a 10BaseT network is 328 feet (100 meters). In practice this is not a limitation because a survey by AT&T indicated that about 99 percent of desktops in commercial buildings are located within 328 feet (100 meters) of a wiring closet. If distances longer than that are required, two or more segments may be connected using repeaters. The minimum length of any given segment is restricted to 8 feet (2.5 meters).

By using stackable hubs or by cascading regular hubs into a cascaded star topology, you can network large numbers of computers using 10BaseT cable. Although 10BaseT can support up to 1024 nodes, networks with no more than 200 or 300 nodes will yield the best performance by keeping collision domains small. Hubs can be hierarchically arranged to a depth of up to three levels in order to accommodate much larger networks, but performance declines significantly as the number of stations exceeds several hundred.

Notes

Although 10BaseT theoretically supports a maximum bandwidth of 10 Mbps, in actual networks the presence of collisions reduces throughput to about 4 to 6 Mbps.

The maximum length of a 10BaseT cable segment is not a result of the specifications for round-trip communications on an Ethernet network but rather a limitation caused by the relatively low signal strength of 10BaseT systems. With enhanced Category 5 (Cat5e) cabling, you might be able to sustain network communications effectively with cable lengths up to about 490 feet (150 meters), although this is not normally recommended.


Work area
Wall plates
Wiring closet
Patch panel
Hub
Patch cables
Rack

10BaseT. *A typical 10BaseT network.*

When wiring a new 10BaseT network, always use Cat5e cabling. This will make it unnecessary to rewire your network should you decide to upgrade later to Fast Ethernet and beyond.

See Also: *10Base2, 10Base5, 10BaseF, 802.3, Ethernet*

10GbE

An abbreviation for 10G Ethernet.

See: *10G Ethernet*

10G Ethernet

Also known as 10GbE, an emerging form of networking technology based on Ethernet and operating at a speed of 10 gigabits per second (Gbps). 10GbE, which stands for 10 Gigabit Ethernet, is the successor to Gigabit Ethernet (GbE) and will be standardized under the Institute of Electrical and Electronic Engineers (IEEE) 802.3ae working group.

Overview

10GbE is a switched-based technology that has similarities to and differences from earlier versions of Ethernet. It abandons the Carrier-Sense Multiple-Access with Collision Detection (CSMA/CD) Media Access Control (MAC) method of earlier versions, using instead separate send and receive channels. In other words, 10GbE operates only in full-duplex communications mode, similar to GbE and Full-Duplex Fast Ethernet. This does not eliminate contention, however, because 10GbE is designed to interoperate with slower forms of Ethernet where collisions may occur.

10GbE uses the same 48- to 1518-byte frame format as standard 10 megabits per second (Mbps) Ethernet and 100 Mbps Fast Ethernet, abandoning the jumbo frames supported by GbE. And unlike earlier versions of Ethernet, 10GbE operates exclusively over fiber-optic cabling, although efforts are being made to develop a form of 10GbE over copper cabling that can be used over the short distances needed within wiring closets. The maximum range for 10GbE will be 328 to 984 feet (100 to 300 meters) over multimode fiber and 25 miles (40 kilometers) over single-mode fiber. Laser wavelengths of 1310 and 1550 nanometers are used for medium- and long-haul transmission respectively.

Types

The driving force behind the development of 10GbE is twofold:

- Enterprise-level local area networks (LANs) that have deployed core switches with GbE interconnects (and even multiplexed GbE interconnects) are approaching saturation and require the higher backbone speed promised by 10GbE. Many server farms and clusters are being deployed today using 1000BaseT connections to network backbones. As a result, these backbones will soon face saturation unless a technology such as 10GbE can provide the necessary bandwidth to support these GbE farms (the Link Aggregation Control Protocol of 802.3ad only supports up to 8 Gbps aggregated links between switches). The impending arrival of 64-bit PC architectures such as Intel's Itanium also promises to increase the rate at which servers will be able to process data, and new servers are appearing that are able to just saturate a 1 Gbps 1000BaseT NIC. The promise here is that 10GbE will enable network architects to build Ethernet wide area networks (WANs) as easily as they build Ethernet LANs today, without having to learn more complex technologies such as Asynchronous Transfer Mode (ATM) or Synchronous Optical Network (SONET).
- WAN service providers (carriers) see 10GbE as a simpler, less costly replacement for SONET/Synchronous Digital Hierarchy (SDH), and envisage a world of end-to-end Ethernet incorporating both LAN and WAN technologies. Although Ethernet gear only costs about a fifth of what SONET gear costs, incumbent carriers have invested heavily in SONET technologies and ATM, which may affect how quickly they adopt 10GbE. Startup carriers are therefore more likely to jump on the 10GbE bandwagon than existing carriers.

As a result of this twofold need of the carriers (for SONET-compatibility) and enterprise networks (for easy upgrading of core switches from GbE to 10GbE), two different versions of 10GbE are envisioned under the emerging IEEE 802.3ae standard. These versions, listed below, operate differently at the physical layer (PHY):

- **LAN version:** This is essentially just speeded-up GbE and will operate at exactly 10.0 Gbps and use standard Ethernet frames. The primary difference with GbE is that only full-duplex communications will be supported. This version is designed to be an easy upgrade for backbone switches in enterprise LANs.
- **WAN version:** This provides a method of transporting Ethernet frames over SONET/SDH at a speed of 9.58464 Gbps (identical to the current OC-192). This version is designed to maximize compatibility with carrier's existing SONET deployments in their long-haul lines.



① Aggregation of GbE backbone switches in enterprise LAN

② High-speed WAN access to remote sites

Server farm
GbE switch with
10 Gbps backbone
GbE switch with
10 Gbps backbone
Fast Ethernet
switch
Fast Ethernet
switch
Fast Ethernet
switch
Workstations
Head-
quarters
LAN
10GbE
switch
10GbE switch
Dark fibre
10GbE switch
10GbE
switch
Branch
office
LAN
Customer
premises
Metropolitan network of
10GbE carrier
Customer
premises

10G Ethernet. *Some scenarios where 10GbE could be deployed.*

Implementation

Some envisioned uses for 10GbE include

- High-speed interconnects between GbE backbone switches in enterprise LANs
- Aggregation of multiple short-haul GbE links and high-speed campus-wide interconnects
- Switched connections to server farms and high-performance clusters

Some telecom carriers plan to replace their SONET/ATM rings with 10GbE in their Metropolitan Area Networks (MANs) to provide high-speed connections in the local loop between Central Offices (COs) and customer premises. These carriers will then be able to provision corporate users with 10GbE Ethernet WAN links to provide end-to-end Ethernet services across the WAN. Because this eliminates the need for costly packet-conversion equipment such as frame relay assembler/disassemblers (FRADs) or ATM access routers at the customer premises, 10GbE WAN services are likely to be much less costly than current T1 and frame relay services. Furthermore, 10GbE has almost no protocol overhead compared to ATM/SONET, which can have as much as 56 percent protocol overhead when implementing Automatic Protection Switching (APS) routines. The desire of carriers to implement 10GbE to save cost is a major force driving vendors to quickly develop 10GbE switching technologies. Due to its distance limitations, however, 10GbE is not expected to replace SONET/SDH for long-haul telecommunications links between cities or continents.

Issues

Most servers are not yet capable of utilizing the full potential of 10GbE because of limitations in processing power and bus speed, though advances in bus, memory, and storage technologies are closing the gap. With standard 1500-byte Ethernet frames being employed, servers would need to be able to process 833,000 frames per second, which is beyond their current limitations. One solution would be to employ Jumbo Frames similar to those used in GbE, but the 802.3ae standard does not cover this feature. The result is that some vendors are starting to implement their own proprietary Jumbo Frame technologies, which raises concerns for future prospects of interoperability between 10GbE equipment from different vendors.

Prospects

Many users are looking forward to the day when carriers can provision their corporate networks with 10GbE. Carriers will likely supply these services using a bandwidth-on-demand model, allowing customers to replace their costly T1 and T3 lines with blocks of purchased bandwidth that can scale in real time to accommodate bursts of traffic. Application Service Providers (ASPs) are also waiting to take advantage of 10GbE to offer outsourced email and workflow applications that will perform as well as LAN-based implementations.

The IEEE published a draft standard (802.3ae) for 10GbE in September 2000, and the final standard is expected to be ratified in 2002. Until then, 10GbE equipment provided by vendors may involve proprietary technologies, and network architects should consider interoperability issues before committing budgets to this emerging technology. Another cost issue to consider is that existing copper and multimode fiber infrastructures would have to be replaced with more costly single-mode fiber if anything more than backbone switch interconnects is considered in a proposed 10GbE deployment.

Some of the vendors developing 10GbE plug-in backplane modules for their carrier-class backbone switches include Nortel Networks, Extreme Networks, and Foundry Networks. Because there is already demand in the corporate WAN market, service providers such as Yipes (*www.yipes.com*) are rapidly rolling out infrastructure to provide 10GbE carrier services in a number of cities across the United States and compete with local telco carriers selling T-carrier and frame relay services.

Notes

10GbE will support Simple Network Management Protocol (SNMP) and (Remote Network Monitoring) RMON at the PHY layer. This will enable carriers to remotely manage provisioned 10GbE services and should be a boon to enterprise network managers as well.

For More Information

You can find the 10 Gigabit Ethernet Alliance (10GEA) at *www.10gea.org*.

Also find out about the IEEE 802.3ae working group at *www.ieee.org*.

See Also: *Ethernet, Fast Ethernet, Gigabit Ethernet (GbE)*

24 x 7

A term implying the uninterrupted running of network services. A 24 x 7 network is a network whose services and resources are available 24 hours a day, seven days a week, with virtually no downtime. A similar term is *24 x 7 x 365*, which implies virtually no downtime during the entire year.

Overview

In today's emerging e-business economy, availability of the network and its resources and applications can make the difference between business success and failure. A variety of technologies can be used to approach the goal of 24 x 7 availability. One of the most successful is clustering, a technology in which an application runs redundantly on multiple servers. When one of the nodes in a cluster fails, the other nodes take on the workload of the failed node so that there's no interruption in service while the failed node is being repaired or replaced. Windows 2000 and .NET Server Advanced Server editions offer clustering services for high-availability line-of-business applications.

Other technologies important to the 24 x 7 goal include fault-tolerant hardware technologies. Examples are hot-swappable components, such as power supplies and hard disks that can be removed and replaced without the system having to power down or reboot. Fault-tolerant storage technologies such as RAID 1 or RAID 5 guard against data loss from disk failure. Cellular phones and pagers also play a role in attaining the 24 x 7 goal, as they allow businesses to keep in touch with administrators and technical support staff around the clock.

Notes

If you are an MIS (Manager of Information Services) or CIO (Chief Information Officer) running an e-business that requires 24 x 7 uptime, it is wise to make sure your network administrators and support staff are adequately compensated—they must work hard to maintain a 24 x 7 networking environment. Also, such people can be difficult to replace, so it is advisable to do what you can to minimize turnover.

See Also: *network management*

64-bit architecture

Any computing hardware based on a processor capable of manipulating 64 bits of information at a time and directly accessing up to 2^{64} bytes (16 exabytes) of different physical memory addresses.

Overview

The PC revolution of the 1990s was based to a large degree upon the x86 processor platform, a series of 32-bit processors developed by Intel Corporation. Compared to their 16-bit predecessors, these new processors could manipulate twice as many bits simultaneously and access up to 4 gigabytes (GB) of directly addressable memory, which provided more than enough processing power and memory space for most PC-based applications.

As the PC platform began to push its way into the high-end server platform previously dominated by Reduced Instruction Set Computing (RISC) processors, the demand for greater power and memory addressability grew. This need has been felt most in the area of enterprise-level database applications, which are processor and memory intensive in their requirements. To address these needs, two leading processor vendors, Intel and AMD, began development of 64-bit processors in the late 1990s.

Comparison

AMD's x86-64 architecture can run today's 32-bit operating systems and applications, but only when running in Legacy mode. Unfortunately, this mode limits addressable memory to 4 GB and provides no processing gain over the present Pentium III platform. In order to run true 64-bit operating systems and applications, the x86-64 architecture must be running in Long mode, which does not support backward compatibility with existing 32-bit applications and operating systems.

In order for Intel's IA-64 architecture to run legacy 32-bit software, an x86 hardware emulation mode is provided. When 32-bit software is run using emulation mode, however, performance is generally slower than that of a typical Pentium III processor.

In order to properly run legacy software on Itanium (or on Sledgehammer running in Long mode) and enable such software to address the full 64-bit address space, the software needs to be recompiled to produce a binary bit-image appropriate to the selected 64-bit platform. Unfortunately, these binary images are different for the two architectures, so either a single architecture will win out or vendors will need to compile two different versions for the two platforms. Until existing software is recompiled, or until 64-bit operating systems and applications are developed from scratch, the usefulness of these two new architectures will be limited as far as the business enterprise is concerned.

Architecture

Intel's new 64-bit Itanium chip uses a radically new architecture called IA-64 that differs in fundamental ways from the x38 architecture used in all of its earlier 32-bit processors, from the 386 through the Pentium III Xeon. Itanium uses a Very Long Instruction Word (VLIW) algorithm that allows it to read strings containing multiple instructions. Using a technique called Explicitly Parallel Instruction Computing (EPIC), Itanium can then execute up to six instructions per clock cycle, which greatly enhances performance over 32-bit processors (not just Intel x86 processors, but also 32-bit RISC and complex instruction set computing [CISC] processors) and eliminates the need for complicated algorithms such as the Out-of-Order Processing implemented in Pentium chips.

Itanium processors are capable of performing 6 billion floating-point operations per second (6 gigaflops) and support up to 512-way symmetric multiprocessing (SMP) for the most transaction-intensive e-commerce and database applications. Itanium uses a new motherboard interface and requires a bus speed of 366 MHz.

AMD's new 64-bit Sledgehammer chip uses an architecture called x86-64 that is a natural evolution from the x86 standard, and AMD's 32-bit Athlon processor. Sledgehammer operates in two modes: long mode, which runs native 64-bit operating systems and applications, and legacy mode, which supports existing 16-bit and 32-bit operating systems and applications. Sledgehammer uses a motherboard with a Plastic Pin Grid Array (PPGA) processor slot and requires a 266 MHz system bus.

Prospects

Both architectures have their camps supporting them. Intel's IA-64 architecture is supported by Microsoft Corporation, Hewlett-Packard, IBM, Compaq Computer Corporation, and others, and is likely to be the platform of choice for users of Microsoft Windows once Microsoft releases its 64-bit version of Windows currently under development. AMD's x86-64 architecture is supported by Sun Microsystems, which has plans to port Solaris (a version of UNIX) to x86-64, and by the Linux community, which is working on a similar port.

Notes

Some software vendors have developed ways of going beyond the hardware limitations of 32-bit processors that limit addressable physical memory to 4 GB. Examples include Microsoft Windows 2000 Advanced Server and Microsoft Windows 2000 Datacenter Server, both of which employ a technique called Physical Address Extension (PAE) to enable them to address 8 GB and 64 GB of memory respectively.

For More Information

More information on these two platforms can be found at *www.intel.com/ebusiness/products/ia64* and *www.amd.com/products/cpg/64bit.*

See Also: *64-bit Windows*

64-bit Windows

A version of Microsoft Windows 2000, Windows XP, and Windows .NET Server designed to operate on computers using Intel's new IA-64 (64-bit) processor architecture.

Overview

64-bit Windows is designed to support today's most processor- and memory-intensive business applications. These applications include e-commerce, data mining, online transaction-processing, high-end graphics, and high-performance multimedia applications. Based on Intel's 64-bit processor architecture called IA-64, which is first realized in the Itanium chip, 64-bit Windows is fully compatible with the Win32 API, allowing developers to develop and compile code for both the 32-bit and 64-bit platforms with equal ease. The main advantage of using a 64-bit processor architecture is that the amount of directly addressable physical memory increases from 64 GB for 32-bit Windows 2000 and Windows .NET Server Datacenter Server to a staggering 16 terabytes (TB) for the new platform. (A terabyte equals 1024 gigabytes.) This means that large databases can be preloaded in-to memory to provide vastly improved data access times, improving the performance and efficiency of enterprise-level applications.

For More Information

For more information on the current state of the 64-bit Windows platform, see *www.microsoft.com/hwdev/64bitwindows/ and www.microsoft.com/windowsxp/pro/techinfo/howitworks/64bit/default.asp.*

See Also: *64-bit architecture, Microsoft Windows*

80/20 rule

A rule of thumb that says that 80 percent of network traffic is local and only 20 percent is destined for remote networks.

Overview

The 80/20 rule was developed in the era of traditional routed Ethernet networks and is now considered a classical description of local area network (LAN) traffic patterns that no longer applies. The main consideration here is the Internet, and corporate use of Internet access means that ever-increasing amounts of remote traffic are being routed through LANs. The 80/20 rule was used in the 1980s to help enterprise network architects plan and design large-scale routed networks.

Notes

Other types of 80/20 rules exist. For example, in programming, the 80/20 rule says that 80 percent of the benefit in coding an application comes from 20 percent of the work involved. In other words, prioritize your development tasks to achieve the most in the time available. The original 80/20 rule seems to have originated with Vilfredo Pareto, an early 20th-century economist who stated that 80 percent of the volume of product produced comes from only 20 percent of the producers who make it. Another modern variant says that 80 percent of your business comes from only 20 percent of your customers, so identify these customers and give them premier service.

See Also: *local area network (LAN)*

100BaseFX

An Institute of Electrical and Electronics Engineers (IEEE) standard for implementing 100 megabits per second (Mbps) Ethernet over fiber-optic cabling.

Overview

100BaseFX is based on the 802.3u standard, which is an extension of the 802.3 standard of Project 802 developed by the IEEE. It's a type of Fast Ethernet that is often used for wiring campus backbones using fiber-optic cabling. The designation 100BaseFX is derived from the network's speed (100 Mbps), the signal transmission method (baseband transmission), and the physical medium used for transmission (fiber-optic cabling).

Implementation

100BaseFX networks are wired together in a star topology using fiber-optic cabling and 100-Mbps fiber-optic hubs or Ethernet switches. 100BaseFX systems may be interconnected with 100BaseTX, 100BaseT4, and 10BaseT systems using auto negotiating hubs and switches with suitable ports. Two-strand fiber-optic cabling is required, and ST, SC, and MIC connectors are all supported. Signaling is at 125 megahertz (MHz), which when combined with the 80 percent efficiency of the 4B5B line coding mechanism used results in an overall transmission speed of 100 Mbps.

The maximum length of any segment of fiber-optic cabling connecting a station (computer) to a hub in 100BaseFX is 1350 feet (412 meters), and not 1480 feet (450 meters) as some sources indicate. The grade of fiber-optic cabling used is usually two-strand multimode fiber-optic cabling, with one strand carrying transmitted data and the other strand receiving data. However, you can also use two-strand single-mode fiber-optic cabling. If multimode fiber-optic cabling is used, the variety used is typically a grade with a 62.5-micron core diameter.

Repeaters can be used to extend the length of cabling and for interfacing between 100BaseFX/TX and 100BaseT4 segments. The maximum allowable distances with repeaters are 2 kilometers using multimode fiber-optic cabling and 10 kilometers using single-mode fiber-optic cabling. Only one or two repeaters can be used per collision domain, depending on whether Class I or Class II repeaters are used.

Notes

100BaseFX and a related standard, 100BaseTX, are sometimes collectively referred to as 100BaseX.

When using 100BaseFX with repeaters for backbone cabling runs, Ethernet switches cannot be more than 1350 feet (412 meters) apart when running in half-duplex mode and 6600 feet (2000 meters) apart when running in full-duplex mode.

See Also: *100BaseT4, 100BaseTX, Fast Ethernet*

100BaseT

Another name for Fast Ethernet and thus for all 100 megabits per second (Mbps) Ethernet varieties. Also sometimes used interchangeably with 100BaseT4.

See: *Fast Ethernet*

100BaseT4

An Institute of Electrical and Electronics Engineers (IEEE) standard for implementing 100 megabits per second (Mbps) Ethernet over twisted-pair cabling.

Overview

100BaseT4 is based on 802.3u, which is an extension of the 802.3 specifications of Project 802 developed by the IEEE. 100BaseT4 is the most commonly used implementation of Fast Ethernet today. The designation 100BaseT4 is derived from the network's speed (100 Mbps), the signal transmission method (baseband transmission), and the physical medium used for transmission (all four pairs of wires in standard twisted-pair cabling). 100BaseT4 is now considered legacy technology and has been largely superseded by 100BaseTX.



100BaseT4. *A typical 100BaseT4 network.*

Implementation

100BaseT4 networks are wired together in a star topology using unshielded twisted-pair (UTP) cabling and 100-Mbps hubs or Ethernet switches. The UTP cabling involved may be Category 3 (Cat3), Category 4 (Cat4), or Category 5 (Cat5) cabling—with Cat5 cabling and enhanced Category 5 (Cat5e) cabling being the most commonly used solutions nowadays.

100BaseT4 uses all four pairs of wire in standard UTP cabling, for signaling with signaling rates of 25 megahertz (MHz) and an 8B6T line coding mechanism. One pair is used exclusively for transmission and a second pair for reception. The other two pairs are bidirectional and can be used either to transmit or to receive data as required. In this way, three of the four wire pairs are used at any given time to provide half-duplex transmission or reception of signals. Sharing three pairs of wires for data transfer allows 100BaseT4 to make use of lower-grade Cat3 cabling already installed in many older buildings.

The maximum length of any segment of cabling connecting a station (computer) to a hub is 328 feet (100 meters). This ensures that round-trip signaling specifications are met, because violating these specifications can produce late collisions that disrupt network communications. The Electronic Industries Alliance/Telecommunications Industry Association (EIA/TIA)– recommended length of cabling between the station and the wiring closet is only 295 feet (90 meters), allowing up to 32 feet (10 meters) more of cabling for patch cables used to connect patch panels to hubs or switches. The pinning of the RJ-45 connectors used for 100BaseT4 wiring is the same as for 10BaseT wiring.

Notes

Make sure all your cabling, connectors, and patch panels are fully Cat5-compliant. For example, ensure that when UTP cabling is connected to patch panels, wall plates, or connectors, the wires are not untwisted more than half an inch at the termination point.

100BaseT4 hubs and switches are typically available in an autosensing 10/100-Mbps variety for interoperability with older 10BaseT networks and to facilitate an easy upgrade from 10BaseT to 100BaseT.

See Also: *100BaseFX, 100BaseTX, Fast Ethernet*

100BaseTX

An Institute of Electrical and Electronics Engineers (IEEE) standard for implementing 100 megabits per second (Mbps) Ethernet over twisted-pair cabling.

Overview

100BaseTX is based on 802.3u, which is an extension of the 802.3 specifications of Project 802 developed by the IEEE. The designation 100BaseTX is derived from the network's speed (100 Mbps), the signal transmission method (baseband transmission), and the physical medium used for transmission (the same two pairs of wires in standard four-wire twisted-pair cabling that are used for 10BaseT Ethernet).

Implementation

100BaseTX networks are wired together in a star topology using either unshielded twisted-pair (UTP) cabling or data-grade shielded twisted-pair (STP) cabling. If UTP cabling is used (which is the most common scenario), it must be Category 5 (Cat5) cabling or enhanced Category 5 (Cat5e) cabling. Stations are connected together using hubs or switches. Unlike 10BaseT hubs, which can be hierarchically connected up to three levels deep, 100BaseTX hubs can only be connected two layers deep, which imposes additional distance limitations and may necessitate rewiring of existing cabling before upgrading from 10BaseT to 100BaseTX.



100BaseTX. *A typical 100BaseTX network.*

100BaseTX uses the two pairs of wires in twisted-pair cabling that are used by 10BaseT networks, with one pair of wires used for transmission and the other used for reception. With the appropriate equipment, 100BaseTX is capable of supporting both the familiar half-duplex Ethernet used by 10BaseT and newer full-duplex Ethernet signaling technologies. 100BaseTX employs a signaling rate of 125 megahertz (MHz) for each pair of wires, which, because the 4B5B line coding algorithm used is only 80 percent efficient, translates into a data transmission speed of 100 Mbps.

The maximum length of any segment of cabling connecting a station to a hub is 328 feet (100 meters). This ensures that round-trip signaling specifications are met, because violating these specifications can produce late collisions that disrupt network communications. The pinning of the RJ-45 connectors used for 100BaseTX wiring is the same as for 10BaseT wiring with wires 1 and 2 used for transmission and wires 3 and 6 used for reception. This enables 100BaseTX autosensing hubs and switches to operate in mixed 10/100 Mbps Ethernet networks.

Notes

The maximum distance between 100BaseTX hubs and bridges or switches is 738 feet (225 meters), further than the maximum hub-station distance of only 328 feet (100 meters).

100BaseTX and a related standard, 100BaseFX, are sometimes collectively referred to as 100BaseX.

Although the maximum length of segments joining stations to hubs is 328 feet (100 meters), the Electronic Industries Alliance/Telecommunications Industry Alliance (EIA/TIA) recommends only 295 feet (90 meters) of cabling between the station (computer) and the wiring closet, allowing up to 32 feet (10 meters) more of cabling for patch cables used to connect patch panels to hubs or switches.

Make sure all your cabling, connectors, and patch panels are fully Cat5-compliant. Make sure that when UTP cabling is connected to patch panels, wall plates, or connectors, the wires are not untwisted more than half an inch at the termination point.

See Also: *100BaseFX, 100BaseTX, Fast Ethernet*

100BaseVG

Another name for 100VG-AnyLAN.

See: *100VG-AnyLAN*

100BaseX

An umbrella term that includes 100BaseFX and 100BaseTX Fast Ethernet technologies.

See: *100BaseFX, 100BaseTX, Fast Ethernet*

100VG-AnyLAN

Also called 100BaseVG, a 100 megabits per second (Mbps) networking technology that at one time was a serious alternative to Fast Ethernet, but which now is considered legacy technology.

Overview

100VG-AnyLAN is defined by the 802.12 standard of the Institute of Electrical and Electronics Engineers (IEEE) Project 802. It is a local area network (LAN) communications technology developed by Hewlett-Packard and AT&T around 1994. 100VG-AnyLAN is similar to Fast Ethernet in its speed (100 Mbps) and ability to be deployed in both shared-media (hub-based) and switched implementations. It differs, however, in its media access method, because it uses demand priority instead of the Carrier-Sense Multiple-Access with Collision Detection (CSMA/CD) method used by Ethernet.

Implementation

100VG-AnyLAN networks are wired together in a star topology using unshielded twisted-pair (UTP) cabling, shielded twisted-pair (STP) cabling, or fiber-optic cabling. If UTP cabling is used, it can be Category 3 (Cat3), Category 4 (Cat4), or Category 5 (Cat5) cabling—with Cat5 cabling or enhanced Category 5 (Cat5e) cabling preferred. When using UTP Cat3 or Cat4 cabling, the maximum length of a segment is 100 meters (328 feet). With UTP Cat5 cabling or STP cabling, the maximum length of a segment is 656 feet (200 meters). When using multimode fiber-optic cabling, the maximum length is 6600 feet (2000 meters).

100VG-AnyLAN uses all four pairs of wires in UTP cabling with 25 megahertz (MHz) signaling for each pair. 100VG-AnyLAN uses a special coding scheme called quartet signaling, which makes it possible to transmit data over all four pairs of wires in a UTP cable simultaneously. This means that special 100VG-AnyLan hubs are required to support demand priority media access. Otherwise, the frame format, topology, and other specifications of 100VG-AnyLAN are the same as for Ethernet.



100VG-AnyLAN. *A typical 100VG-AnyLAN network.*

100VG-AnyLAN employs the demand priority Media Access Control (MAC) method specified by the IEEE 802.12 standard. Demand priority means that the central hub controls which station is allowed to transmit data (only one station is allowed to transmit at any given moment). This eliminates the overhead of collisions and means that 100VG-AnyLAN networks have an efficiency of 100 percent compared to the 60-70 percent efficiency of contention-based Fast Ethernet networks. Demand priority works by having the hub poll each station successively in round-robin fashion until a station indicates it has data to transmit, whereupon control is passed temporarily to the transmitting station.

If multiple hubs are used, these are connected hierarchically with the top hub, called the root hub, being the master controller for the network. If a station is connected to a local hub other than the root hub in a large 100VG-AnyLAN network, the local hub detects the station's request to transmit data during regular polling and then forwards this request to the next highest hub in its hierarchy until it reaches the root hub, which communicates with the local hub, telling it when it is allowed to service the station's request. Thus even in a large 100VG-AnyLAN network with a hierarchy of hubs, only one station is allowed to transmit data at any given time. 100VG-AnyLAN supports five levels of hubs in a hierarchy, but performance is best if cascading is limited to only three levels.

Because demand priority is a deterministic rather than contention-based media access method, stations cannot join the network on their own and begin transmitting data. Instead, when a station is first connected, it waits to be polled by the hub and then transmits a training sequence of special frames that enables the station to determine the frame type in use and other network restrictions. This training sequence temporarily suspends polling by the hub, but takes only 5 msec to be completed and so does not seriously disrupt network communications.

Advantages and Disadvantages

100 VG-AnyLAN offers greater efficiency due to elimination of collisions, but another advantage that it has over Fast Ethernet is that it supports both 802.3 Ethernet frames and 802.5 Token Ring frames, although a

single hub cannot support both at the same time (all hubs on any given 100VG-AnyLAN network must be configured to support the same frame type, either 802.3 or 802.5).

Yet another advantage 100VG-AnyLAN has over Ethernet is that it has built-in support for traffic prioritization. Two levels of traffic are recognized by 100VG-AnyLAN hubs: normal priority and high priority. High-priority traffic requests are serviced immediately by the local hub without the need for that hub to first communicate with the network's root hub. All network traffic is then suspended until the high-priority transmission is completed.

Marketplace

Although 100VG-AnyLAN is in some ways a superior technology to Fast Ethernet due to its greater efficiency and inherent support for traffic prioritization, it has not been widely deployed. This is mainly due to limited vendor support, which has kept prices high and made Fast Ethernet more affordable. Furthermore, Fast Ethernet is simpler and is completely compatible with widely deployed 10BaseT Ethernet networks and forms the natural upgrade path for these networks.

See Also: *demand priority, Fast Ethernet*

568-A

A wiring standard for twisted-pair cabling defined by the Telecommunications Industry Association (TIA).

Overview

The 568-A standard was originally intended for analog voice applications but is generally used in data networks as well. The main difference between 568-A and the competing 568-B standard is in the pin layouts for RJ45 jacks, which generally terminate unshielded twisted-pair (UTP) cabling. The pin layout for 568-A wiring is technically referred to as T568A. For a comparison of these two wiring schemes, see the next article, "568-B."

Notes

The T568A wiring scheme is preferred in Canada, although this has been changing recently.

See Also: *568-B, UTP cabling*

568-B

A wiring standard for twisted-pair cabling defined by the Telecommunications Industry Association (TIA).

Overview

The 568-B standard was designed for data transmission over building wires used in computer network and telecommunications systems. It differs from the competing 568-A standard mainly in the pin layouts for the RJ45 jacks that are normally used to terminate unshielded twisted-pair (UTP) cabling. The pin layout for 568-B wiring is technically referred to as T568B, and that for 568-A cabling systems is called T568A. The drawing illustrates these differences between the two wiring systems.



Key		
Pair number	Color	Symbol
1	Blue	——
2	Orange	------
3	Green	——
4	Brown	------

568-B. *Comparison of pin layouts in RJ45 connectors between 568-A and 568-B.*

Notes

For 10BaseT and 100BaseT Ethernet networks, only two pairs of wires are used for data transmission, but 1000BaseT Gigabit Ethernet (GbE) uses all four pairs. As a result, running GbE over a cabling infrastructure that contains a mixture of 568-A and 568-B terminations will cause signaling problems that can be hard to troubleshoot.

See Also: *568-A, UTP cabling*

802.1

The Institute of Electrical and Electronics Engineers (IEEE) working group dealing with general local area network/wide area network (LAN/WAN) networking architectures and protocols and their standards.

Overview

This group is responsible for developing standards and recommending practices for LAN architectures, LAN/metropolitan area network (MAN)/WAN internetworking, network management, and all protocol layers above the media access control (MAC) and Logical Link Control (LLC) layers. The three main standards ratified by this group include

- **802.1D:** MAC bridging
- **802.1G:** Remote MAC bridging
- **802.1Q:** Virtual LANs (VLANs)

Some of the projects this group is currently involved in include

- **802.1p:** Prioritization scheme for 802.1Q VLAN traffic
- **802.1s and 802.1w:** Issues relating to the Spanning Tree Algorithm
- **802.1t:** Further MAC bridging issues
- **802.1u and 802.1v:** Issues relating to VLANs and their classification.
- **802.1x:** Port-based network access control

See Also: *media access control method, Project 802, virtual LAN (VLAN)*

802.1p

An Institute of Electrical and Electronics Engineers (IEEE) standard specifying a prioritization scheme for Ethernet networks that support the 802.1Q virtual local area network (VLAN) standard. The 802.1p standard allows a rudimentary form of quality of service/class of service (QoS/CoS) on Layer-2 switched networks.

Overview

One of Ethernet's biggest drawbacks is its lack of an inherent mechanism for prioritizing network traffic. The new 802.1p standard tries to resolve this by making use of three reserved bits in the tags appended to packets by devices that support the 802.1Q VLAN standard. Employing these three bits enables $2^3=8$ different priority levels to be assigned to each packet of data, allowing switches and routers to handle these different types of traffic according to preconfigured schemes. The table shows the eight different traffic classes that correspond to priorities 0 (binary 000) through 7 (binary 111) according to IEEE recommendations.

Traffic Classes by Priority

Priority	*Type of Traffic*
0	Standard best-effort LAN traffic (default priority setting)
1	Lowest priority, used primarily for traffic that should not be allowed to affect other forms of traffic, for example, bulk file transfers
2	Unallocated at present
3	Excellent effort—in other words, best-effort delivery for important data
4	Controlled load—supports admission control for mission-critical business traffic
5	Low-priority multimedia traffic with jitter and latency less than 100 ms
6	High-priority multimedia traffic with jitter and latency less than 10 ms
7	Highest priority for traffic that controls the network infrastructure

Marketplace

An example of an Ethernet switch that supports the 802.1p standard is the ProCurve 8000M from Hewlett-Packard. These switches also support 802.1Q, 802.3ad, QoS, and port security.

Notes

Ethernet networks that use Layer 3 switches can implement more sophisticated CoS/QoS schemes such as Differentiated Services (DiffServ) and Integrated Services with resource Reservation Protocol (IntServ/RSVP). For mixed Layer 2/3 networks, the 802.1p standard provides standard mappings between these Layer-3 CoS/QoS mechanisms and the Layer-2 802.1p prioritization scheme.

See Also: *802.1Q, virtual LAN (VLAN)*

802.1Q

An Institute of Electrical and Electronics Engineers (IEEE) standard defining the architecture and operation of virtual local area networks (VLANs).

Overview

The 802.1Q VLAN standard ratified in 1999 allows a tag of 4 bytes to be appended to packets by network hosts and Layer 2/3 switches in Ethernet networks. This tag identifies the VLAN to which the given packet belongs. For a more detailed explanation, see the article "virtual LAN (VLAN)" elsewhere in this book. The 4 bytes of tag information are embedded into the standard Ethernet header by dividing them between the 2-byte tag protocol identifier (TPID) field and the 2-byte tag control information (TCI) field. The TCI field consists of

- **User priority field:** This three-bit field forms the basis of 802.1p traffic prioritization schemes in Level-2 switched networks.
- **Canonical format indicator:** This is a one-bit field that is used to toggle VLAN formats.
- **VLAN Identifier (VID):** This is a 12-bit field that identifies the VLAN to which the packet belongs. Up to 212 (4096) VLANs can be defined.

Marketplace

Many vendors produce Ethernet switches compatible with the 802.1Q standard, although mostly at the high end of their switching gear offerings. At the workgroup level, fewer vendors support this standard in their switches. For example, the low-end Catalyst 2900 switches from Cisco Systems do not support 802.1Q, but Hewlett-Packard's new ProCurve 10/100 stackable switches with Gigabit Ethernet (GbE) backbone transceivers do.

See Also: *802.1p, virtual LAN (VLAN)*

802.2

The Institute of Electrical and Electronics Engineers (IEEE) standards for the Logical Link Control (LLC), defining its operation for all network architectures that follow the Open Systems Interconnection (OSI) model. The physical layer (PHY) and media access control (MAC) layer specifications are specified for a particular technology under the 802 committee that deals with them (for example, 802.3 deals with Ethernet and 802.5 with Token Ring). The IEEE 802.2 working group is no longer active.

See Also: *logical link control (LLC) layer, Project 802*

802.3

The Institute of Electrical and Electronics Engineers (IEEE) working group concerned with Ethernet in its many forms. Although this set of standards is generically referred to as Ethernet, this term is actually a trademarked version of 802.3.

Overview

The 802.3 standards cover those relating to local area networks (LANs) based on Carrier-Sense Multiple-Access with Collision Detection (CSMA/CD) as their Media Access Control (MAC) method, in other words with

- 10 Mbps Ethernet (original 802.3 standard)
- 100 Mbps Fast Ethernet (802.3u)
- 1 Gigabit Ethernet (GbE) (802.3z and 802.3ab)
- 10 Gigabit Ethernet (under development)

Some recently ratified standards of the 802.3 working group include

- **802.3z:** Gigabit Ethernet (1998)
- **802.3ab:** 1000Base-T (GbE over copper) (1999)
- **802.3ac:** Tag switching in virtual local area networks (VLANs) (1998)
- **802.3ad:** Link aggregation (2000)

Some of the projects the 802.3 working group is currently involved with include

- **802.3ae:** 10 Gigabit Ethernet (10GbE)
- **802.3af:** Transmission of electrical power over unshielded twisted pair (UTP) cabling to power Ethernet devices

Notes

802.3 is also used to refer to the frame format used in Ethernet frames. See the article “frame type” elsewhere in this book for more information.

See Also: *Ethernet, frame type, Project 802*

802.3ab

The Institute of Electrical and Electronics Engineers (IEEE) standard for Gigabit Ethernet (GbE) over copper, also known as 1000BaseT or 1000BaseTX. This standard was ratified in June 1999.

See Also: *10BaseT, Gigabit Ethernet (GbE)*

802.3ad

An Institute of Electrical and Electronics Engineers (IEEE) standard for link aggregation of Ethernet switch ports and network interface cards (NICs) to combine multiple data streams into a single large stream.

Overview

Prior to 802.3ad, many vendors of Fast Ethernet and Gigabit Ethernet (GbE) gear developed their own proprietary trunking protocols for aggregating multiple links together into a single higher speed link. Examples include Adaptec’s Duralink technology and Cisco Systems’ Inter-Switch Link Trunking (ISL) protocol. The 802.3ad standard was developed to promote interoperability between switches from different vendors. The need for such technology is increasingly apparent in a world of streaming media and outsourcing Line of Business (LOB) functions to Application Service Providers (ASPs).

The 802.3ad standard covers all versions of Ethernet (10, 100, and 1000 megabits per second [Mbps]) and enables multiple links of the same or different speeds to be aggregated into a single logical link. For example, two 1-gigabit-per-second (Gbps) GbE ports can be combined to make a single 2-Gbps link, or a 1-Gbps GbE port and a 100-Mbps Fast Ethernet port can be combined to create a single 1100-Mbps link. The maximum bandwidth supported by aggregated 802.3ad links is 8 Gbps—in other words, up to eight full duplex 1-Gbps GbE ports can be combined into a single fat data pipe. The protocol used to accomplish this is called the Link Aggregation Control Protocol (LACP).

Advantages and Disadvantages

The main advantage of 802.3ad is that additional bandwidth for network backbones and connections to server farms can be added incrementally as needed, thus providing greater scalability at minimum cost. The 802.3ad standard includes a mechanism for load balancing traffic across aggregated links. It also supports fault tolerance to handle the failure of any link within an aggregated set of links by automatically rerouting traffic through a different link. This fault-tolerant failover feature makes 802.3ad ideal for mission-critical point-to-point links.

Marketplace

The 802.3ad standard was ratified in July 1999, and 802.3ad-compliant products are just beginning to appear, primarily GbE backbone switches and GbE NICs for high-end server clusters.

See Also: *Gigabit Ethernet (GbE)*

802.3ae

The proposed Institute of Electrical and Electronics Engineers (IEEE) standard for 10 Gigabit Ethernet (10GbE).

See Also: *10G Ethernet*

802.3af

An emerging Institute of Electrical and Electronics Engineers (IEEE) standard that allows data-carrying unshielded twisted pair (UTP) cabling to carry not only data but also electricity for powering Ethernet networking devices.

Overview

Traditionally, in networking devices the wires carrying power to run the device and the wires carrying data to and from the device are kept separate. This is done to isolate the sensitive data-handling electronics from the high power levels required by the device. Many newer network-capable devices such as hubs, Internet Protocol (IP) telephones, and Personal Digital Assistants (PDAs) require only a few watts to operate, and 802.3af promises to simplify the operation of these devices. Instead of separate cables for carrying data and power, 802.3af devices will require only data connections and will receive their power over these connections. The advantage is that fewer cables need to be deployed and used for compliant networking devices, which promises to make Voice over IP (VoIP) telephone equipment as easy to deploy and use as traditional Plain Old Telephone Service (POTS) telephones, which communicate through and are powered by the same RJ-11 outlet found in private homes.

802.3af allows up to 10 watts of power to be carried over Category 3 (Cat3) or Category 5 (Cat5) cabling when running 10BaseT or 100BaseTX Ethernet on the network. The standard provides for the transmission of both AC and DC power as required. To protect non-802.3af devices from damaging power levels that could fry their electronics, the 802.3af standard includes a handshaking protocol to enable 802.3af-compliant devices to be recognized before transmitting power to them.

Marketplace

PowerDsine, Siemens, and Lucent Technologies are vendors that have developed early versions of 802.3af-compliant switches, hubs, and IP telephony equipment. Refer to these vendors' Web sites for the latest information on these products.

Notes

Cisco Systems already has its own proprietary scheme called Inline Power for power transmission over data lines. The Cisco version supports DC power transmission over UTP cabling.

See Also: *Category 5 (Cat5) cabling, Ethernet, UTP cabling*

802.3u

The Institute of Electrical and Electronics Engineers (IEEE) standard for Fast Ethernet that was ratified in 1995. This standard defines the physical layer (PHY) and media access control (MAC) layer specifications for this technology.

See Also: *Fast Ethernet*

802.3z

The Institute of Electrical and Electronics Engineers (IEEE) standard for Gigabit Ethernet (GbE) over fiber, which was ratified in June 1998. This standard defines the physical layer (PHY) and media access control (MAC) layer specifications for this technology.

See Also: *Gigabit Ethernet (GbE)*

802.4

The Institute of Electrical and Electronics Engineers (IEEE) standard for the Token Bus networking architecture. This legacy architecture is now found only in some industrial settings. The IEEE 802.4 working group is no longer active.

See Also: *Project 802*

802.5

The Institute of Electrical and Electronics Engineers (IEEE) standard for the Token Ring networking architecture.

Notes

802.5 is also used to refer to the frame format used in Token Ring frames. See the article "frame type" elsewhere in this book for more information.

For More Information

The Institute of Electrical and Electronics Engineers (IEEE) 802.5 Web site is actually not found at the IEEE Web site (*www.ieee.org*). Instead, it can be found at *www.8025.org.*

See Also: *frame type, Token Ring*

802.6

The Institute of Electrical and Electronics Engineers (IEEE) standard for the Metropolitan Area Networks (MANs). The IEEE 802.6 working group is no longer active.

See Also: *Project 802*

802.7

The Institute of Electrical and Electronics Engineers (IEEE) Broadband Technical Advisory Group (TAG). The IEEE 802.7 working group is no longer active.

See Also: *Project 802*

802.8

The Institute of Electrical and Electronics Engineers (IEEE) Technical Advisory Group (TAG) for developing standards and recommending practices for fiber-optic networking. The IEEE 802.8 working group is no longer active.

See Also: *Project 802*

802.9

The Institute of Electrical and Electronics Engineers (IEEE) standards for isochronous local area networks (LANs) for simultaneous transmission of data and voice/video. The only developed form of this standard is the 802.9a isoEthernet specification.

Overview

Isochronous means "at a precise time," which indicates that 802.9 technologies operate using clocked signals in order to deliver data according to a rigid time schedule. In this fashion 802.9 resembles the Public Switched Telephone Network (PSTN), a circuit-switched network operating at 8 kilohertz (kHz) clocking rate and transmitting one byte every 125 microseconds to produce an overall channel (called a B channel) whose bandwidth is 64 kilobits per second (Kbps).

The isoEthernet standard developed in conjunction with National Semiconductor combines traditional 10BaseT Ethernet data transmission at 10 megabits per second (Mbps) with a separate 6.144 Mbps isochronous data channel for transporting time-sensitive traffic such as voice and video. The isochronous data channel (called the Circuit channel) consists of 96 B-channels of 64 Kbps each. IsoEthernet's total bandwidth, therefore, is 16 Mbps, but this is split between the two types of transmission: data and voice/video. There are also some additional channels (D-, M-, and P-channels) that are used for control and maintenance, but these use only about 200 Kbps of bandwidth. The 10 Mbps of 10BaseT data and 6.144 Mbps of isochronous transmission are carried on the same unshielded twisted pair (UTP) cabling system by incorporating time-division multiplexing (TDM) techniques.

Notes

The IEEE 802.9 working group is no longer active and isoEthernet is now considered a legacy technology.

See Also: *Project 802, time-division multiplexing (TDM)*

802.10

The Institute of Electrical and Electronics Engineers (IEEE) working group for local area network (LAN) security standards. The IEEE 802.10 working group is no longer active.

See Also: *Project 802*

802.11

A set of Institute of Electrical and Electronics Engineers (IEEE) standards for wireless networking designed to do for wireless networking what the 802.3 standards have done for Ethernet: provide clear guidelines for vendors to develop technologies that are standards-based, interoperable, and can operate at different speeds and frequencies and also can use different encoding mechanisms.

Overview

Three standards are currently ratified under 802.11:

- **802.11:** The original wireless networking standard supporting data rates of up to 2 megabits per second (Mbps) and now superseded by 802.11b. This standard was approved in June 1997 and provided for both direct sequence spread spectrum (DSSS) and frequency hopping spread spectrum (FHSS) physical-layer (PHY) transmission methods. 802.11 also supported transmission over infrared, but no products were developed for this method. 802.11 allows data to be transmitted at either 1 Mbps or 2 Mbps, depending on which is the highest rate negotiable in a given configuration of client and access point (the further the distance between them, the lower the possible data rate).

- **802.11b:** A standard for wireless networking supporting data rates of up to 11 Mbps and operating in the unlicensed 2.4 GHz Industrial, Scientific, and Medical (ISM) band. 802.11b transmission is standardized on DSSS.
- **802.11a:** A standard supporting higher data rates of up to 54 Mbps and operating in the 5 GHz UNII (Unlicensed National Information Infrastructure) band. 802.11a transmission is similarly standardized on DSSS.

Of these standards, 802.11b is currently the most widely deployed, with support from over 20 vendors, and 802.11 is considered legacy and is being phased out. Part of the success of 802.11b is due to the successful lobbying of the Wireless Ethernet Compatibility Alliance (WECA), which has helped ensure adherence to standards and interoperability between equipment from different vendors. The 802.11a standard is newer and is seen as the next generation for wireless networking and the natural upgrade path for companies needing its higher data transmission rates.

All these standards use the same Media Access Control (MAC) method, Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA), to allow multiple users to share a single communications channel. Note that this is not the MAC method used by Ethernet (it uses CSMA/CD), so it is a misnomer to call 802.11 technology wireless Ethernet.

Notes

If you upgrade your 802.11 base stations to 802.11b, they will still support legacy 802.11 clients—but only at their maximum data rate of 2 Mbps, which in actual practice is more like 1 Mbps.

For secure wireless transmission, data needs to be encrypted. The most popular solution is Wired Equivalent Privacy (WEP), which now is included as a standard feature with most wireless network interface cards (NICs), PC cards, and access points.

For More Information

You can find information about the Wireless LAN Alliance at *www.alana.com* and the Wireless Ethernet Compatibility Alliance (WECA) at *www.wirelessethernet.org*.

See Also: *802.11a, 802.11b, wireless networking*

802.11a

An Institute of Electrical and Electronics Engineers (IEEE) wireless networking communications standard that supports data transmission rates of up to 54 megabits per second (Mbps). 802.11a is widely seen as the successor to 802.11b.

Overview

The 802.11a standard uses the same Media Access Control (MAC) layer mechanism as the more commonly deployed 802.11b, namely Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA), which allows multiple users to share a single channel at the same time. The encoding scheme used at the physical layer differs, however, because 802.11b uses the same physical-layer (PHY) encoding scheme as Ethernet, but 802.11a uses a different scheme: Coded Orthogonal Frequency Division Multiplexing (COFDM or Coded OFDM).

The frequency bands used by 802.11a also differ from 802.11b, because 802.11b uses the 2.4 GHz Industrial, Scientific, and Medical (ISM) band for its operation, and 802.11a employs portions of the 5 GHz Unlicensed National Information Infrastructure (UNII) band recently allocated by the Federal Communications Commission (FCC).

A single 802.11a communications channel consists of a 20 megahertz (MHz)-wide block of frequencies divided up into 52 subchannels each 300 kilohertz (KHz) wide, 48 of which are used for carrying data, with the remaining 4 subchannels reserved for error correction. By encoding data using 64-level quadrature amplitude modulation (64QAM), a data rate of 1.125 Mbps per subchannel can be achieved, which translates into a maximum overall transmission speed of 48 x 1.125 = 54 Mbps. Due to the limitations of the MAC layer mechanism, however, actual data rates are only about 70 percent of theoretical, so that sustained data rates for 802.11a are rarely above 35 Mbps. Nevertheless, these high attainable speeds are sufficient to enable 802.11a systems to support some types of broadband applications, including Web browsing and multimedia.

The frequencies used by 802.11a cover three 200 MHz blocks of the 5 gigahertz (GHz) band:

- **5.15 to 5.25 GHz:** This band supports five independent channels with a maximum power output of 50 megawatts (mW).
- **5.25 to 5.35 GHz:** This band also supports five independent channels but with a maximum power output of 250 mW for greater distance and penetration of building materials.
- **5.725 to 5.825 GHz:** This upper band is designed for outdoor communications, supports five independent channels, and a maximum power output of 1 watt.

Advantages and Disadvantages

The main advantage of 802.11a over 802.11b is the increased data rate. By way of analogy, 802.11a is to 802.11b as Fast Ethernet is to standard 10 Mbps Ethernet. In fact, both of these standards are sometimes referred to as wireless Ethernet, but this is a misnomer because they use CSMA/CA instead of Ethernet's Carrier-Sense Multiple-Access with Collision Detection (CSMA/CD) mechanism at the MAC layer.

Besides the higher data rates supported by 802.11a as compared to 802.11b, another advantage of 802.11a is that the COFDM encoding mechanism includes greater error correction, which means better recovery from multipath reflection.

Implementation

As a result of these differences in signal encoding mechanisms, 802.11b and 802.11a are incompatible standards. Devices using one standard cannot communicate with devices supporting the other standard. Yet because these two technologies operate at different frequency bands, they can be deployed together and overlap without interference. 802.11b is already widely deployed in many corporate enterprises; the logical migration path to 802.11a is to deploy 802.11a in small pockets where it is most required and gradually extend this as needed.

Marketplace

Two vendors pioneering in 802.11a hardware include Radiata Communications (now owned by Cisco Systems) and Atheros Communications. Both vendors offer devices supporting 6, 12, 24, 36, 48, and 54 Mbps transmission speeds, with different rates being achieved by using different encoding mechanisms. Atheros also supports bonding two channels to achieve a theoretical maximum transmission rate of 108 Mbps, and other vendors are developing proprietary extensions to 802.11a that may boost speeds up to 155 Mbps.

Issues

Because of the higher frequencies used, 802.11a devices are not susceptible to the kind of electromagnetic interference, including interference from microwave ovens and cell phones, that plagues 802.11b devices. However, because of different governmental policies regarding allocation of frequencies in the 5 GHz band, interoperability issues exist for 802.11a technologies used in different parts of the world.

For example, in Europe the upper 100 MHz portion (5.725 to 5.825) is already allocated for other uses, limiting operation of 802.11a gear to only 10 clear channels instead of 15. The 802.11a standard is also incompatible with the competing HiperLAN/2 standard being developed in Europe, which also uses frequencies from the 5 GHz band. In Japan only the lower 100 MHz portion is unallocated, which allows only five channels for 802.11a to work with. Other countries and regions use portions of the 5 GHz spectrum for military or satellite communications purposes, limiting the capability of 802.11a devices within their borders.

See Also: *802.11, 802.11b, wireless networking*

802.11b

An Institute of Electrical and Electronics Engineers (IEEE) wireless networking communications standard that supports data transmission rates of up to 1 megabit per second (Mbps). 802.11b is sometimes called wireless Ethernet, but this is a misnomer because the two technologies use different Media Access Control (MAC) methods.

Overview

The 802.11b standard was developed over a number of years by Lucent Technologies, Intersil Corporation, and other industry partners and ratified as an IEEE standard in 1999. It is the most popular and widely deployed wireless networking standard currently in use, though it may be superseded over the next few years by 802.11a, which supports higher data transmission rates.

802.11b is capable of supporting data transmission rates of 1, 2, 5.5, and 11 Mbps. The actual transmission rate used will depend on the distance between the client adapter (PC card or network interface card [NIC]) and access point (base transmitting station) and upon interference due to obstacles in the transmission path. In general, the further the distance from the base station, the slower the data rate. For directional antennae operating with clear line-of-sight in point-to-point transmission, the top speed of 11 Mbps can be sustained for distances up to about 10 miles (16 km). Within a building using omnidirectional antennae, however, devices may need to be within 100 feet (15 meters) in order to maintain their highest transmission rate. If a device exceeds this range, the transmission rate drops to the progressively lower levels until a sustained transmission rate can be successfully negotiated. Each data rate uses its own characteristic modulation scheme, such as Binary Phase Shift Keying (BPSK) for 1 Mbps transmission, Quadrature Phase Shift Keying (QPSK) for 2 Mbps, and so on.

Although the theoretical top transmission speed for 802.11b is 11 Mbps, in practice the media access control (MAC) layer mechanism (Carrier Sense Multiple Access with Collision Avoidance [CSMA/CA]) and protocol overhead reduce efficiency to 60-70 percent. The result is that data rates of more than 6 Mbps are rarely achieved and 4-5 Mbps is more common. Note that this is the total shared bandwidth for all 802.11b clients within the same service area (serviced by the same set of access points or base stations), so actual throughput may be much less when many clients are active. The 802.11b standard allows multiple users to share a single communications channel at the same time by using the CSMA/CA method as its MAC layer protocol. The 802.11b standard supports Request to Send/Clear to Send (RTS/CTS) as a MAC enhancement for transmission in environments where coverage is distorted by obstacles and interference, but this mechanism adds significant overhead to the protocol, especially during the transmission of small packets.

The drawing shows a typical 802.11b packet. This consists of a 30-byte header containing information for addressing, sequencing, and frame control. This is followed by a data or payload section that may range from zero to 2312 bytes in length, followed by a 4-byte checksum trailer.



802.11b. *Typical structure of an 802.11b packet.*

As far as frequency and transmission method are concerned, 802.11b employs direct-sequence spread spectrum (DSSS) transmission over an 83-MHz-wide chunk of the unlicensed 2.4 GHz Industrial, Scientific, and Medical (ISM) band of the electromagnetic spectrum, specifically the frequency band from 2.400 to 2.483 GHz. Because this frequency band overlaps with emissions from microwave ovens and some cell phones, proximity of these devices can affect the transmission speed achieved.

Under Federal Communications Commission (FCC) regulations, 802.11b provides 11 separate channels for communications. Theoretically, this means that the total maximum bandwidth for an 802.11b local area network (LAN) utilizing all channels would be 11 x 11 Mbps = 121 Mbps. In practice, due to interference between channels, a given service area can only support three simultaneous channels, which limits total available bandwidth to 3 x 11 = 33 Mbps in theory, or about 14 Mbps in practice once protocol overhead is factored in.

A typical 802.11b wireless LAN segment may support up to 65 different clients, but the contention involved in the CSMA/CA media access method means that one busy client downloading a large file can utilize the segment’s entire available bandwidth, leaving the other stations unable to communicate. Adding additional access points to the service area provides fault tolerance and load balancing but does not increase the total available bandwidth.

Implementation

When deciding whether you should immediately deploy 802.11b equipment in your enterprise or wait for the faster 802.11a to gain greater vendor support, you have several issues to consider. Small- and mid-sized companies might find 802.11b a cheap, easy, turnkey solution to deploy and might not need the higher data rates of 802.11a. And although both systems can be deployed in parallel, 802.11b equipment cannot be upgraded to 802.11a. Dual-radio access points are under development, but their deployment is complicated by the two standards’ different transmission characteristics. Finally, enterprise architects may want to wait for 802.11a products that are certified by the Wireless Ethernet Compatibility Alliance (WECA) before committing large portions of their budget to a massive rollout of 802.11a.

Marketplace

More than 20 different vendors sell 802.11b-compliant hardware, and the standard‘s success is evident in the high degree of interoperability between equipment supplied by different vendors. A client network adapter (NIC or PC card) from one vendor is likely to work well with an access point (base station hub) from a different vendor without needing any modifications. Access points from different vendors are less likely to work together, particularly if they need to be configured for roaming users that move from one service area (cell) to another and require seamless networking during the transition. So the best solution is still to purchase all of your 802.11b devices from the same vendor in order to achieve the highest level of interoperability, particularly in large, geographically dispersed deployments with multiple access points spanning multiple subnets.

As a result of increased competition, prices for 802.11b equipment have fallen drastically of late. Client adapters are now available for $99 or less, and access points can be had for under $299. Some popular vendor products include

- **3Com Corporation:** AirConnect PC card and companion AirConnect Wireless Access Point designed for the enterprise, which supports Mobile IP and Microsoft Point-to-Point Encryption
- **Apple Computer:** AirPort client adapter and companion Airport access point, a bargain system designed for Small Office Home Office (SOHO) environments and including Ethernet and V.90 modem support
- **Intel Corporation:** PRO/Wireless LAN PC card and companion PRO/Wireless LAN Access Point, with integrated Web server and 128-bit Wired Equivalent Privacy (WEP) support. Intel also recently acquired Xircom, which makes a wireless Ethernet adapter that is popular with Notebook users and supports 40- and 120-bit WEP.

Issues

While the maximum allowed power output for an 802.11b-compliant device is 1 watt, most 802.11b-compliant NICs and PC cards emit only about 30 milliwatts (mW) to conserve battery life in laptops and avoid excessive heat dissipation. This is generally considered too low to constitute any health hazard to individuals using this equipment—for comparison, a typical cell phone may generate an electromagnetic power output of half a watt or more.

Notes

For an explanation of the different components needed in the deployment of a wireless network and how they operate, see the article "wireless networking" elsewhere in this book.

Do not operate 802.11b devices in an aircraft during flight—turn your device off when boarding. The signals transmitted by your device could adversely affect the aircraft's electronic systems.

Look for the "WiFi" seal of approval on vendor packaging of 802.11b equipment. This designation indicates that the vendor's equipment is approved by WECA as being fully compliant with 802.11b standards.

Wireless networks based on 802.11b can be susceptible to electromagnetic interference produced by microwave ovens, particularly if the clients are located far from the base station. If this occurs, move the oven, move the client adapter, or increase the transmission strength of the access point until you can achieve reliable communications.

To conserve power, especially for 802.11b PC cards in laptops, these client adapters should be set to run in Polled Access Mode (PAM). Clients configured for PAM go to sleep when not communicating with the base station and wake up according to a predefined schedule to check for an inbound Traffic Information Map (TIM) packet from the base station indicating that it has data ready to send the client. PAM typically uses about 10 percent of the power consumed when running in Constant Access Mode (CAM), where the client is always listening.

If your buildings have metal floors, wireless networking using 802.11b systems may not operate beyond 100 feet (30 meters) due to signal absorption. In such buildings you may also require an access point on each floor.

802.11b and Bluetooth devices operate on the same frequencies, so using both systems in the same service area may cause dropouts and transmission errors to occur.

See Also: *802.11, 802.11b, Bluetooth, wireless networking*

802.12

The Institute of Electrical and Electronics Engineers (IEEE) standards outlining the architecture and operation of the Demand Priority Media Access Control (MAC) method. This access method is employed by the legacy 100VG-AnyLAN technology developed in 1994 by Hewlett-Packard and AT&T. The IEEE 802.12 working group is presently in hibernation and is no longer active.

See Also: *100VG-AnyLAN, demand priority, Project 802*

802.13

The Institute of Electrical and Electronics Engineers' (IEEE's) Project 802 includes a number of standards and working groups relating to networking. These standards and working groups currently range from 802.1 through 802.17, but for some reason 802.13 was not used.

See Also: *Project 802*

802.14

The Institute of Electrical and Electronics Engineers (IEEE) working group on cable modems. This working group is no longer active.

See Also: *Project 802*

802.15

A set of standards being developed by the Institute of Electrical and Electronics Engineers (IEEE) for Wireless Personal Area Networks (Wireless PANs or WPANs).

Overview

The 802.15 working group is currently divided into a number of Task Groups (TGs) that are actively working on different aspects of wireless PANs. These TGs include

- **TG1:** This group is working to develop standards for WPANs based on Bluetooth 1.x wireless technologies.
- **TG2:** This group is trying to get 802.15 WPANs to coexist with 802.11 WLANs by overcoming issues

related to electromagnetic interference between the two technologies.

- **TG3:** This group is trying to develop High Rate (HR) WPANs with speeds in excess of 20 megabits per second (Mbps).
- **TG4:** This group deals with developing Low Rate (LR) WPANs with speeds in the range of 10–200 kilobits per second (Kbps). These LR WPANs will be used for things such as home automation, remote control, interactive toys, sensors, and similar systems.

See Also: *Personal Area Network (PAN), Project 802*

802.16

A set of emerging Institute of Electrical and Electronics Engineers (IEEE) standards being developed for fixed broadband wireless networking.

Overview

Broadband wireless, also called Wireless MAN (WMAN), involves wireless high-speed data transmission between fixed points at various frequency bands. In other words, 802.16 is to the metropolitan area network (MAN) what 802.11 is to the local area network (LAN): similar technology but operating at higher speeds and over longer distances. WMAN is the wireless equivalent of broadband wired technologies such as Digital Subscriber Line (DSL).

The IEEE working group on 802.16 is subdivided into a number of Task Groups (TGs) to work at these different frequencies, specifically:

- **TG1:** This group is working on air interfaces in the 10– 66gigahertz (GHz) region of the electromagnetic spectrum.
- **TG2:** This group is working on ensuring coexistence between different wireless broadband access systems.
- **TG3:** This group is working on air interfaces in the 2–11 GHz region of the spectrum.
- **TG4:** This group is working on the Wireless High-Speed Unlicensed Metropolitan Area Network (Wireless HUMAN) standard, which involves transmission in license-exempt portions of the spectrum in the 5– 6GHz range.

See Also: *Project 802*

802.17

The Institute of Electrical and Electronics Engineers (IEEE) working group on Resilient Packet Ring (RPR) technologies.

See Also: *Project 802*

1000BaseCX

An Institute of Electrical and Electronics Engineers (IEEE) standard for implementing 1000 megabits per second (Mbps) Ethernet (that is, Gigabit Ethernet, or GbE) over shielded twisted-pair (STP) cabling.

Overview

The CX in 1000BaseCX stands for short-haul copper and indicates that this version of GbE is intended for short cable runs over copper cabling. 1000BaseCX technologies are in the beginning stages of being widely implemented in enterprise-level networks and are primarily used for collapsed backbones and high-speed interconnects within wiring closets and equipment rooms. 1000BaseCX and other GbE standards are defined in the 802.3z series of standards of Project 802 developed by the IEEE.

Implementation

1000BaseCX is to some degree simply an extension of standard Ethernet technologies to Gigabit-level network speeds. 1000BaseCX is implemented using STP cabling. This STP cabling must be standard 150-ohm balanced cabling and should have a quality slightly better than IBM Type I cabling. Cable segments can have a maximum length of only 82 feet (25 meters).


Servers with
1000-Mbps
network
interface
cards
1000BaseCX
connection
Gigabit
Ethernet switch
Fast
Ethernet hub
Fast
Ethernet hub
Fast
Ethernet hub
Workstations
Workstations
Workstations

1000BaseCX. *A typical 1000BaseCX network.*

Like other forms of GbE, 1000BaseCX employs 8B/10B coding with a transmission frequency transmission of 1.25 GHz. 1000BaseCX is intended mainly for connecting high-speed hubs, Ethernet switches, and routers together in wiring closets. Common implementations for 1000BaseCX are in switch-switch and switch-server connections, with switch-server connections being the most frequently implemented use for 1000BaseCX.

See Also: *1000BaseLX, 1000BaseSX, 1000BaseT, Gigabit Ethernet (GbE)*

1000BaseLX

An Institute of Electrical and Electronics Engineers (IEEE) standard for implementing 1000 megabits per second (Mbps) Ethernet (that is, Gigabit Ethernet, or GbE) over fiber-optic cabling.

Overview

The *LX* in 1000BaseLX stands for long and indicates that this version of GbE is intended for use with long-wavelength (1300 nm) laser transmissions over long cable runs of fiber-optic cabling. 1000BaseLX technologies are in the beginning stages of being widely implemented in enterprise-level networks and are primarily used for long cable runs between pieces of equipment on a campus or within a building. 1000BaseLX and other GbE standards are defined in the 802.3z standards of Project 802 developed by the IEEE.

Implementation

1000BaseLX can be implemented using either single-mode fiber-optic cabling or multimode fiber-optic cabling. Transmission requires two optical fibers due to the full-duplex operation of 1000BaseLX. Cable segment lengths depend on the cable grade used, as shown in the table on the following page.


Gigabit Ethernet
100/1000 switch
1000BaseLX
connection
Gigabit Ethernet
100/1000 switch
Server farm
Fast Ethernet
10/100 hub
Fast Ethernet
10/100 hub
Workstations
Fast Ethernet
10/100 hub
Workstations
Workstations

1000BaseLX. *A typical 1000BaseLX network.*

Cable Segment Lengths

Cable Grade	*Maximum Segment Length*
10-micron single-mode fiber	10 kilometers (6.2 miles)
50-micron multimode fiber	550 meters (1800 feet)
62.5-micron multimode fiber	440 meters (1440 feet)

1000BaseLX is intended mainly for connecting high-speed hubs, Ethernet switches, and routers together in different wiring closets or buildings using long cabling runs. 1000BaseLX is most commonly implemented in a switch-switch configuration.

Notes

When you use multimode fiber-optic cabling in 1000BaseLX implementations, a condition called differential mode delay (DMD) can sometimes occur. This condition occurs only in cabling of uneven quality, and it leads to signal jitter that can disrupt network communications. To resolve this problem, newer 1000BaseLX transceivers condition the signal to distribute its power equally among all transmission modes of the cable.

See Also: *1000BaseCX, 1000BaseSX, 1000BaseT, Gigabit Ethernet (GbE)*

1000BaseSX

An Institute of Electrical and Electronics Engineers (IEEE) standard for implementing 1000 megabits per second (Mbps) Ethernet (that is, Gigabit Ethernet, or GbE) over fiber-optic cabling.

Overview

The *SX* in 1000BaseSX stands for short and indicates that this version of GbE is intended for use with short-wavelength (850-nanometer) laser transmissions over short cable runs of fiber-optic cabling. 1000BaseSX technologies are in the beginning stages of being widely implemented in enterprise-level networks and are primarily used for shorter cable runs between pieces of equipment within a building.

1000BaseSX is an extension of standard Ethernet technologies to gigabit-level network speeds. 1000BaseSX and other GbE standards are defined in the 802.3z standards of Project 802 developed by the IEEE.

Implementation

1000BaseSX is implemented using only multimode fiber-optic cabling. Cable segment lengths depend on the cable grade used, as shown in the table.

Cable Segment Lengths

Cable Grade	*Maximum Segment Length*
50-micron multimode fiber	500 meters (1640 feet)
62.5-micron multimode fiber	220 meters (720 feet)

1000BaseSX is intended mainly for connecting high-speed hubs, Ethernet switches, and routers together in different wiring closets or buildings using long cabling runs. 1000BaseSX is most commonly implemented in a switch-switch configuration.

Notes

When multimode fiber-optic cabling is used in 1000BaseSX implementations, a condition called differential mode delay (DMD) can sometimes occur. This condition occurs only in cabling of uneven quality, and it leads to signal jitter that can disrupt network communications. To resolve this problem, newer 1000BaseSX transceivers condition the signal to distribute its power equally among all the cable's transmission modes.

See Also: *1000BaseCX, 1000BaseLX, 1000BaseT, Gigabit Ethernet (GbE)*

1000BaseT

An Institute of Electrical and Electronics Engineers (IEEE) standard for a form of Gigabit Ethernet (GbE) involving transmission over copper cabling.

Overview

The *T* in 1000BaseT identifies it as operating over twisted-pair copper cabling and makes it an extension of the traditional 10BaseT and 100BaseT Ethernet technologies for transmission over unshielded twisted-pair (UTP) cabling. 1000BaseT is based on the IEEE 802.3ab standard and is intended to provide the simplest upgrade path for legacy 10BaseT and 100BaseT Ethernet networks.

1000BaseT is implemented using the commonly installed Category 5 (Cat5) cabling or enhanced Category 5 cabling version of UTP cabling. Cable segments for 1000BaseT must have a maximum length of 328 feet (100 meters). Category 6 (Cat6) cabling is expected to provide enhanced transmission characteristics for 1000BaseT networks when it becomes available.

1000BaseT uses all four pairs of wires in standard UTP cabling, as opposed to the two pairs of wires used in 10BaseT and 100BaseT networks. Using all four pairs of wires brings certain problems because of attenuation, crosstalk, and echoes arising from full-duplex transmission over single wires. Full-duplex transmission is used to enable each pair of wires to simultaneously transmit and receive data at a rate of 250 megabits per second (Mbps). The resulting four pairs of wires means that the total data rate is 4 x 250 = 1000 Mbps or 1 Gbps. Although each pair of wires carries data at 250 Mbps, the signaling is only at 125 Mbps. This is accomplished by using five-level pulse amplitude modulation (PAM) as the line coding mechanism, which encodes two bits of information for each signal pulse. The reason for this choice is that Cat5 cabling works well up to 125 megahertz (MHz) in standard installations.

1000 BaseT has been standardized by the IEEE under the 802.3ab specification since June 1999. This specification provides for the implementation of automatic link negotiation so that problems such as crossed cables can be detected and corrected for, that 100 Mbps interface can be detected and accommodated when connected to 1000BaseT ports, and that half-duplex network interface cards (NICs) and hub/switch ports can be recognized and used when detected. The standard also specifies special filters for hybrid circuits used in full-duplex transmission over single wires, a special five-level PAM encoding mechanism instead of binary signals, forward error correction techniques, and pulse shaping technologies to make 1000BaseT a functional and reliable networking technology.

Implementation

One popular use for 1000BaseT (also referred to as GbE over copper) is in wiring closets of enterprise networks. 1000BaseT GbE switches can be used to aggregate Fast Ethernet workgroup switches by first connecting the workgroup switches to 100/1000 Mbps ports on the GbE switches using Cat5 cabling and then uplinking the GbE switches to the network's GbE backbone switches using fiber.



1000BaseT. *A typical 1000BaseT network.*

Another growing use for 1000BaseT GbE switches is for connecting high-performance multimedia workstations and Web server clusters to the network backbone. The main limitation for 1000BaseT workstations is that they must be located within 100 meters of the switch. For interbuilding GbE links you need to use fiber. Note, however, that 1000BaseT only supports cable runs up to 328 feet (100 meters) in length, which means that you may need to modify existing cabling infrastructures in some large buildings when migrating from Fast Ethernet to 1000BaseT. Despite the potential application for supporting high-performance workstations, the most popular uses for 1000BaseT remain for backbone uses such as installing vertical risers between floors and horizontal cable runs between wiring closets, for interconnecting workgroup switches, and for connecting server farms and clusters to backbone switches.

Marketplace

Adapting the Ethernet standard to transmission at rates of 1 Gbps over existing Cat5 wiring means lower costs for companies planning to upgrade their switched backbones from 100 Mbps Fast Ethernet to GbE. A typical 1000BaseSX fiber port costs about 50 percent more than a comparable 1000BaseT copper port, so considerable cost savings can be achieved by implementing GbE over copper instead of fiber. However, copper is more susceptible to noise than fiber for gigabit transmission, and Cat5 cabling must be of the highest standard and deployed according to standards to ensure maximum reliability.

1000BaseT solutions are beginning to be implemented for short, high-speed interconnects within wiring closets in enterprise networks, for consolidating server farms in data centers, and for interconnects in carrier colocation sites. Some also envision using it for connecting high-performance workstations as well. Vendors of 1000BaseT equipment include Cisco Systems, 3Com Corporation, Hewlett-Packard, Asante Technologies, Nortel Communications, Extreme Networks, Intel Corporation, and Foundry Networks. Cisco's Catalyst 6500 for its Catalyst 6506 switch chassis module provides 16 1000BaseT ports and is popular with Internet service providers (ISPs) deployed at carrier colocation sites because of its fault-tolerant load balancing and realtime code upgrade capabilities. Foundry's eight-port 1000BaseT modules for its BigIron 8000 switch chassis is another popular choice with excellent performance.

A number of vendors are also providing 1000BaseT NICs for use in high-speed servers and high-performance networks connected to GbE backbones. These vendors include 3Com, Intel, Sun Microsystems, and SysKonnect. A popular choice in enterprise server farms is the SysKonnect 9822 64-bit 66 MHz PCI card, which comes in single-port and dual-port configurations. Alteon WebSystems also has a 10/100/1000BaseT NIC with support for auto-negotiation and jumbo frames.

Currently 1000BaseT is the fastest growing type of GbE being deployed in enterprise networks, because it leverages the investment of existing Cat5 cabling installations. In the second quarter of 2000, GbE over copper accounted for 25 percent of GbE port sales.

Notes

1000BaseT is also sometimes referred to as 1000BaseTX.

Before installing 1000BaseT switches in a building wired with older Cat5 cabling (as opposed to newer enhanced Category 5 [Cat5e] cabling), be sure to test the cabling using a cable tester to make certain the installation fully complies with IEEE TSB95 field specifications. Common reasons for existing wiring failing to support GbE are crosstalk caused by improper cable termination in punch-down block and wall plates. Hewlett-Packard and Fluke Corporation are two vendors that sell suitable cable test equipment. Also, be sure also to use high-quality Cat5e patch cables for connecting patch panels to switches in wiring closets and for connecting servers or workstations to wall plates in work areas.

See Also: *1000BaseCX, 1000BaseLX, 1000BaseSX, Gigabit Ethernet (GbE)*

1000BaseTX

Another name for 1000BaseT Gigabit Ethernet (GbE) over copper.

See: *1000BaseT*

1000BaseX

A generic designation used to describe all forms of Gigabit Ethernet (GbE), including 1000BaseCX, 1000BaseLX, 1000BaseSX, and 1000BaseT. 1000BaseX actually is the technical designation for the family of physical layer (PHY) technologies used in GbE and evolved directly from the Fiber Channel ANSI94 standards.

See Also: *1000BaseCX, 1000BaseLX, 1000BaseSX, 1000BaseT, Gigabit Ethernet (GbE)*

1394

An Institute of Electrical and Electronics Engineers (IEEE) standard for a high-speed serial transmission technology also known as FireWire (a popular term coined by Apple Computer) and iLink (a Sony Corporation trademark).

See Also: *FireWire*

1822

The original host-to-IMP (interface message processor) interface for the Advanced Research Projects Agency Network (ARPANET), the precursor of the Internet.

See Also: *ARPANET*

3270

An information display protocol for IBM mainframe computers.

Overview

The 3270 protocol is a family of protocols that includes separate specifications for terminal display and printer output. The 3270 protocol enables text-based connection-oriented conversations to take place between centralized mainframe hosts and supported peripherals, including terminals, printers, and controllers. These conversations originally took place over dedicated serial transmission links between the terminal and the mainframe controller. For long-distance computing, transmission over private wide area networks (WANs) such as the IBM Global Network enabled mainframe

COBOL programmers to work from home instead of having to commute to the office.

Private WAN services such as IBM Global Networks have now been dismantled and replaced with the Internet, and Web-based access to mainframe hosts has led to the development of hardware-based and software-based emulators. A 3270 emulator is a device or program that enables a workstation to communicate with a mainframe as if it were a dedicated 3270 terminal. A typical 3270 software emulator might use ActiveX controls or Java applets to display the 3270 terminal interface running within a Web browser window. These controls or applets are downloaded from a Web server acting as an intermediary between the Transmission Control Protocol/Internet Protocol (TCP/IP) local area network (LAN) on which the workstations reside and the mainframe host's Systems Network Architecture (SNA) network. Web-based 3270 emulators are popular in many corporate intranets where they can help leverage the usefulness of legacy mainframes and enable offsite users to access mainframe databases through the Internet.

Notes

You can use Microsoft SNA Server to enable a Windows 2000 or Windows .NET Server network to access a mainframe's hierarchical SNA network. SNA Server accomplishes this by defining and assigning dependent 3270 Logical Units (LUs). SNA Server client software must also be installed on each Windows 2000, Windows XP, or Windows .NET Server client that uses these SNA Server LU services. The SNA Server client software enables communication between 3270 applications on the client and the SNA server that provides a gateway to the mainframe.

The original 3270 protocol transmits streams of clear text information. If you are running terminal emulation software on a remote workstation and accessing the mainframe over the Internet, you need to make sure you are using Secure Sockets Layer (SSL) or some other method of securing your transmission.

See Also: *Web-to-host*

5250

An information display protocol for IBM AS/400 systems.

Overview

The 5250 protocol enables text-based connection-oriented conversations to take place between AS/400 hosts and supporting peripherals, including terminals, printers, and controllers. The 5250 protocol is a family of protocols that includes separate protocols for terminal display and printer output. AS/400 display sessions use 5250 data streams over Advanced Peer-to-Peer Networking (APPN).

Recent years have seen the proliferation of Web-based software for enabling local area network (LAN) workstations to access information on AS/400 hosts. These solutions are called terminal emulators and may be either hardware- or software-based. A typical 5250 emulator is an application that uses ActiveX controls or Java applets to display the 5250 terminal interface running within a Web browser window. Emulation controls or applets are downloaded from a Web server acting as an intermediary between the Transmission Control Protocol/Internet Protocol (TCP/IP) LAN on which the workstations reside and the AS/400 host.

Notes

Printer emulation is the ability to print locally from a workstation running a terminal emulator. In order for 5250 terminal emulators to support printer emulation, they must conform to the TN5250 Telnet protocol. Otherwise, workstations must print to a centralized printer attached to the AS/400.

Microsoft SNA Server supports both 3270 and 5250 sessions between Microsoft Windows clients and IBM mainframes and AS/400 systems.

The 5250 protocol transmits streams of clear text information, so if you are running terminal emulation software on a remote workstation to access your company's AS/400 over the Internet, you need to make sure you are using Secure Sockets Layer (SSL) or some other method for securing your transmission.

See Also: *Web-to-host*

A

A+ Certification

A certification for computer service technicians from the Computing Technology Industry Association (CompTIA).

Overview

A+ Certification certifies service technicians for competency in troubleshooting, repairing, and installing stand-alone and networked PCs. A+ is an internationally recognized certification that identifies minimum competency for entry-level computer technicians, typically those who have a minimum of six months of practical hands-on and interpersonal support experience. The Association for Services Management International (AFSMI) and a number of prominent hardware and software vendors back the A+ Certification.

A+ Certification was created by CompTIA to benefit all groups involved in the recruiting and hiring process. Specifically, it has the following advantages:

- A+ benefits managers and recruiters by helping them identify trained, competent individuals to fill vacant positions.
- A+ benefits job seekers by identifying skills they need to learn and develop and by providing a recognizable career path for self-advancement and employment.
- A+ benefits educational institutions by providing goals and objectives for developing industry-relevant technical training programs.

The A+ exam consists of two parts: a core section covering general computer hardware and software that is not vendor-specific and a module covering Microsoft operating system technologies for MS-DOS and Microsoft Windows platforms.

For More Information

Find out about the Computer Technology Industry Association at *www.comptia.org.*

A record

A Domain Name System (DNS) record mapping a host name to an Internet Protocol (IP) address.

Overview

Also known as Address records, A records are the most common type of DNS records in name server databases. A records are used to resolve queries where host names need to be translated into IP addresses in order to establish network communications with the target host.

Examples

A typical A record looks like this:

```
MARGE    IN    A    172.16.22.155
```

Here, MARGE is the friendly name of the host, IN indicates the record is part of the Internet family (the default), A indicates the type of resource record (address record), and the IP address for MARGE is last.

See Also: *DNS, resource record (RR)*

A6 record

A Domain Name System (DNS) record for identifying Internet Protocol version 6 (IPv6) hosts on a network.

Overview

The A6 record is used to map a host's name to its 128-bit IPv6 address. To use this record, a host on an IPv6 network can query a name server by specifying the name of a target host, and the name server responds to the query by returning the IPv6 address of the target host. The “A” in A6 stands for address.

Examples

If the name of a host is BART and the IPv6 address is 3dd4:2500:12af:0302:edef:6d52, then the A6 record would be

```
BART    3dd4:2500:12af:0302:edef:6d52
```

Notes

A6 records are supported on BIND version 9.

See Also: *DNS, resource record (RR)*

AAA

Sometimes called triple-A; stands for Authentication, Authorization, and Accounting, a security framework for controlling access to network resources.

Overview

The three components of an AAA system are the following:

- **Authentication:** This is the process by which users are identified as being entitled to access specific network resources.
- **Authorization:** This process determines the level of access a user has to a specific resource.
- **Accounting:** This process determines which resources are being used and who uses them.

An AAA Server is a server providing authentication, authorization, and accounting services for a network. In a typical AAA implementation, users connect to an access server (for example, a Cisco router) using an authentication protocol such as Password Authentication Protocol (PAP) or Challenge Handshake Authentication Protocol (CHAP). The access server then interacts with the AAA server; for instance, Cisco Secure using security protocols such as Kerberos, Remote Authentication Dial-In User Service (RADIUS), or Terminal Access Controller Access Control System (TACACS). Cisco AAA protocols can then be configured on the access server using Internetwork Operating System (IOS) and applied to a particular interface.

See Also: *network security*

AAAA record

Sometimes called quad-A, a Domain Name System (DNS) resource record that helps transition networks from Internet Protocol (IP) to IPv6.

Overview

The Internet Engineering Task Force (IETF) has developed several enhancements to DNS to help network managers migrate their IP networks to IPv6. These enhancements are outlined in RFC 1886. The AAAA record is one such item, and maps a 32-bit IP address to a newer 128-bit IPv6 address.

AAAA records are supported by Berkeley Internet Name Daemon (BIND) 4.9.5 and later. When networks are fully migrated to IPv6, AAAA records can be replaced by A6 records, which are supported in BIND 9.

See Also: *DNS, resource record (RR)*

AAL

Stands for ATM Adaptation Layer, an Asynchronous Transfer Mode (ATM) protocol that performs the functions of the Open Systems Interconnection (OSI) model's Data Link layer.

See: *ATM Adaptation Layer (AAL)*

AATP

Stands for Authorized Academic Training Provider, a Microsoft training program offered to accredited academic institutions.

See: *Authorized Academic Training Provider (AATP)*

Abilene

An advanced high-speed backbone network that was developed to support the Internet2 initiative.

Overview

Abilene was developed through a partnership between Cisco Systems, Nortel Communications, and Quest Communications and is a project of University Corporation for Advanced Internet Development (UCAID). Abilene's goal is to provide an advanced high-speed backbone for research and development testing of advanced applications relating to Internet2 prior to their intended real-world deployment. To this end, Abilene provides a high-speed Synchronous Optical Network (SONET) and Internet Protocol (IP)-over-SONET backbone network that connects gigaPOPs (high-speed regional network aggregation points of presence) scattered around the world. For an administrative fee, universities and other institutions conducting Internet2 research can connect to Internet2 through Abilene's gigaPOPs for research and development purposes.

Abilene is wholly funded by university and corporate agencies affiliated with the Internet2 research project, but Abilene also supports the U.S federal Next Generation Internet (NGI) initiative and connects with the very high performance Backbone Network Service (vBNS) and other federal research networks.

For More Information

Find out more about Abilene at *www.ucaid.org/abilene.*

See Also: *Internet2*

absolute path

The hierarchical path that locates a file or folder in a file system starting from the root.

Overview

A file's absolute path enables that file's location to be precisely specified, independent of where the user's current directory is located. In Microsoft Windows, a file's absolute path is specified starting with a drive letter, followed by the hierarchy of directories in which the file is contained (with each directory separated by a backslash) and concluding with the exact filename. For example, on a computer running Windows Millennium Edition (Me), the absolute path to the executable for the game of Solitaire, which is typically located in the Windows directory on the C drive, would be the following:

```
C:\Windows\sol.exe
```

If the user opens a command prompt and the current directory is C:\Windows, the user can simply type sol.exe to run the Solitaire program. From any other current directory though, the user must either type the absolute path to execute the program, or specify the relative path from the current directory to the executable file.

On UNIX platforms, path names are specified using forward rather than backward slashes and absolute paths do not start with a drive letter. For example, the absolute path to the file script12, located in the /bin subdirectory of the /usr directory, would be

```
/usr/bin/script12
```

See Also: *relative path, Universal Naming Convention (UNC)*

Abstract Syntax Notation One (ASN.1)

A standard from the International Standards Organization (ISO) that provides a mechanism for encoding human-readable symbols into condensed binary form.

Overview

Abstract Syntax Notation One (ASN.1) is a standard with several real-world uses:

- In X.400, it provides a standard way of formatting and encoding X.400-based e-mail messages for transmission over a network.
- In Simple Network Management Protocol (SNMP), the Management Information Base (MIB) is specified in ASN.1 notation.

More generally, ASN.1 is a method of specifying abstract objects that are intended for any form of serial transmission. ASN.1 is also used for defining objects in MIB files for SNMP.

ASN.1 is similar in syntax to a programming language, and it allows the definition of different data types, data structures, arrays, classes, and other structures similar to those found in the C++ programming language. The presentation layer (Layer 6) of the Open Systems Interconnection (OSI) reference model uses ASN.1 as the standard for specifying the syntax of information exchanged between applications at this layer. ASN.1 data types can be either simple or structured. An example of a definition of a simple data type and its value might be

```
EmployeeAddress ::= ISO646STRING    "99
Microsoft Way"
```

A more complex structured data type might be

```
EmployeeRecord ::= SET
{
 name     [0]ISO646STRING  "Bob Smith"
 title    [1]ISO646STRING  "Support Specialist"
 idNumber [2]INTEGER       "116427"
   }
```

ASN.1 data structures are encoded as octets in hexadecimal notation. These structures are then transmitted over the network as binary information.

Notes

Microsoft Exchange Server uses ASN.1 for its X.400 Connector to provide standards-based connectivity with foreign X.400 messaging systems.

See Also: *Simple Network Management Protocol (SNMP), X.400*

acceptable use policy

A policy created by management to specify acceptable usage for corporate network services as well as the consequences of violating these standards.

Overview

Acceptable use policies have lately become an important feature of corporate IT (information technology) culture for a number of reasons, but mainly because of the widespread implementation of Internet access for desktop users. Management often becomes concerned about the possibilities of employees surfing the Internet for personal use on company time, using company e-mail to send personal messages, sending spam or mail bombs, and so on. Another concern is management's possible legal liability if employees should access illegal or pornographic material on the Internet using their corporate Internet accounts.

Even if a company does not provide desktop Internet access for its employees, it should still have an acceptable use policy governing access to shared network resources such as file servers and color laser printers. To be effective, an acceptable use policy needs to have the following characteristics:

- Acceptable and unacceptable usage must be simply and clearly explained in the policy.
- A graded series of consequences of unacceptable usage must be clearly stated in the policy.
- The policy itself must be clearly visible in employees' work areas.
- Management should regularly call employees' attention to the policy.

In addition, users should be informed if management is utilizing monitoring practices such as logging all employee Internet access or archiving all employee e-mail. Management should consult its legal department in the drafting of an acceptable use policy, and this policy should be reviewed frequently and kept up-to-date as corporate network access evolves.

See Also: *security*

access

Generally, the process of connecting to and using resources on a network.

Overview

To provide a user with access to network resources, permissions must first be granted to the user. For example, if a user is granted the read permission (and only this permission) for a file on the NTFS file system (NTFS), the user is said to have read-only access to the file. An important part of a network administrator's job is to configure appropriate levels of access control—that is, to manage access to network resources such as shared files, printers, and applications so that

- Users who need access to these resources have the appropriate level of access to them
- Users who do not need access to the resources—as well as distrusted users or hackers—are prevented from accessing them

Examples

In Microsoft Windows 2000, when a user or process attempts to access an object such as a file on an NTFS volume, a component of the Windows 2000 operating system called the Security Reference Monitor compares the access token attached to the process with the access control list (ACL) attached to the object. Through this comparison, the Security Reference Monitor determines whether to grant access to the user or process.

See Also: *access control, access control list (ACL), access list, access token*

access control

Any mechanism that controls who can access securable objects and what actions they can perform on them.

Overview

Securable objects are objects whose access can be controlled by an operating system. For example, in Microsoft Windows 2000, Windows XP, and Windows .NET Server, the following are a few of the types of objects that can be secured:

- File system objects such as files and directories
- Service objects (installed services)
- Printer and print server objects
- Registry keys
- Shared directories
- Directory service objects in Active Directory directory service
- Objects exposed to Windows Management Instrumentation (WMI)
- Security provider objects
- Kernel objects such as processes, threads, jobs, semaphores, events, mutexes, named pipes, access tokens, and such

Access control consists of those mechanisms used to control access to the various types of securable objects listed above. In Windows 2000, Windows XP, and Windows .NET Server, access control is performed mainly through the assignment of permissions and rights.

Permissions are assigned to an object to determine who can access that object and at what level. Permissions can be set by an administrator or by the owner of the object. The kind of permission that can be applied depends on the type of object. Some of the objects to which permissions can be applied include

- NTFS file system (NTFS) objects such as files, folders, and volumes
- Local system objects such as processes and programs
- Local or Active Directory objects such as user, group, and printer objects

The issue of inheritance is related to permissions. When permissions are assigned to a folder on an NTFS volume, they are also inherited by default by all existing child folders and files within the folder, and by any new child folders or files created later. Similarly, when permissions are assigned to a container in Active Directory, they are also inherited by default by all existing child objects within the container and by any new child objects created later.

Rights are assigned to user or group accounts to provide them with authorization to perform a specific system task, such as backing up a volume, shutting down the system, or logging on to the console interactively. Rights are most often assigned to groups rather than individual users to simplify administration. Rights can be specified at either the local or domain level.

Another aspect of access control is the issue of *ownership.* When a user creates an object in Active Directory or a file on an NTFS volume, that user becomes the owner of that object or file. The owner has the right to set and modify the permissions of the object. Every object in Active Directory and every file or folder on an NTFS volume has an owner.

One additional aspect of access control is the issue of *auditing.* Files and folders on an NTFS volume can be audited to keep track of failures or successes in accessing them. This can be important in detecting security breaches in your network.

Notes

When assigning permissions to objects in Active Directory, you can assign them either to the object itself (and therefore to all its attributes) or to specific attributes of the object. For example, you could allow all users to have read access to the Phone Number attribute of users in Active Directory, while granting the clerical group read/write access to that attribute so that they can modify users' phone numbers if necessary.

See Also: *access control list (ACL), auditing, owner, permissions*

access control entry (ACE)

A single entry in an access control list (ACL).

Overview

An access control entry (ACE) is part of an ACL applied to an object, and it contains information that is used to control that object's access. Both discretionary access control lists (DACLs) and system access control lists (SACLs) consist of sequential lists of ACEs. For example, an ACE could specify the access or auditing permissions to an object in Active Directory directory service or on a volume formatted using the NTFS file system (NTFS) for a particular user or group.



Access control entry (ACE). *A simplified example.*

An ACE generally specifies two kinds of information:

- The security identifier (SID) of the security principal (user, group, or computer) to which the ACE applies
- The level of access to the object permitted for that security principal

An access mask specifying the possible permissions that can be assigned to the object is included with each ACE. An ACE can provide one of the following:

- Discretionary access control for explicitly granting or denying access to a specific user or group (AccessAllowed and AccessDenied entries)
- System security access control for generating security audit logs (SystemAudit entry)

See Also: *access control list (ACL), access mask*

access control list (ACL)

Any mechanism for implementing access control on a file system object, directory object, or other operating system object.

Overview

Access control lists (ACLs) are a feature of most operating systems and provide a flexible and granular method for securing different operating system objects. This article will look at two examples of ACL implementations: Microsoft Windows 2000 and Sun Microsystems' Solaris operating system.

ACLs are incorporated into the basic operating system architecture of Windows 2000 and Windows NT operating system platforms and are used to control access to objects in Active Directory directory service as well as files on NTFS file system (NTFS) volumes. An ACL is basically a list attached to an object specifying which security principals (users, groups, computers, and so on) are allowed to access the object and what level of access they are allowed to have.

In Windows 2000, ACLs are more properly called discretionary access control lists (DACLs) because administrators can configure and manage them at their discretion. There's also another type of ACL in Windows called a system access control list (SACL), which is used to control the generation of audit messages when object auditing has been configured on a file system.

In traditional UNIX environments, access to file system objects is controlled using the Chmod (change mode) command, which allows read, write, and execute permissions to be allowed or denied for three different entities: the user (owner), the other users that belong to the same group as the user (group), and every other user on the system (other). This permission-based access control mechanism is extremely limited, and as a result most UNIX systems implement ACLs as an alternative method for securing files and other operating system objects.

Sun's UNIX-based Solaris operating system first implemented ACLs in version 2.5.1. These ACLs can be used to control access to files on various different file systems, including:

- UNIX File System (UFS)
- Network File System (NFS) version 2 and higher
- Loopback File System (LOFS)
- Cache File System (CacheFS)

In Solaris, ACLs can be applied to files, directories, and symbolic links, and default permissions can be defined for directories to give all newly created files in the directory the same ACLs. To set and display access control lists on Solaris, use the setfacl and getfacl commands.

ACLs are also available as third-party software for other UNIX platforms. Other UNIX packages and add-ons may use different commands such as setacl and getacl.

See Also: *access control entry (ACE), discretionary access control list (DACL), system access control list (SACL)*

Accessibility Options

A utility in Control Panel for most versions of Microsoft Windows that allows you to adjust the behavior of the keyboard, mouse, and display to suit the needs of individuals with impaired eyesight, hearing, or motor skills.

Overview

Accessibility Options are part of Microsoft Corporation's initiative to provide access to computer technology to all individuals, regardless of their physical impairments. Settings for Accessibility Options include the following:

- **StickyKeys:** Makes it possible to use a key combination such as Ctrl+Alt+Delete without pressing more than one key at a time
- **FilterKeys:** Makes it more difficult to bounce keys by telling the system to ignore brief or repeated keystrokes
- **ToggleKeys:** Generates sounds when certain toggle keys, such as Caps Lock, are turned on
- **SoundSentry:** Flashes a specified part of the screen when the system generates sounds
- **ShowSounds:** Displays icons or text captions to accompany the sounds that programs generate
- **HighContrast:** Makes reading text easier
- **MouseKeys:** Controls the pointer using the numeric keypad
- **SerialKey:** Enables the use of alternative input devices connected to the computer's serial port instead of the keyboard and mouse



Use StickyKeys if you want to use Shift, Ctrl, or Alt key by pressing one key at a time.

☐ Use StickyKeys

Use FilterKeys if you want Windows to ignore brief or repeated keystrokes, or slow the repeat rate.

☐ Use FilterKeys

Use ToggleKeys if you want to hear tones when pressing Caps Lock, Num Lock, and Scroll Lock.

☐ Use ToggleKeys

☐ Show extra keyboard help in programs

Accessibility Options. *Accessibility Options in Windows 2000.*

Windows includes an additional wizard called the Accessibility Wizard that allows you to configure accessibility options on your computer. Additional accessibility utilities include Magnifier, Narrator, and On-Screen Keyboard.

For More Information

Microsoft product documentation and books from Microsoft Press are available in alternative formats from Recording for the Blind and Dyslexic and the Microsoft Accessibility and Disabilities Group.

You can find out about the Microsoft Accessibility and Disabilities Group at *www.microsoft.com/enable.*

Visit the site of Recording for the Blind and Dyslexic at *www.rfbd.org.*

See Also: *Accessibility Wizard*

Accessibility Wizard

A Microsoft Windows utility for configuring a computer for individuals with impaired visual or motor skills.

Overview

Accessibility Wizard is an alternative to Accessibility Options for configuring computers for individuals with disabilities. To start the Accessibility Wizard, choose Accessories from the Start menu. Then, from the Accessibility program group, choose Accessibility Wizard. Note that in Windows Millennium Edition (Me), you might have to install the Accessibility Tools to gain access to the wizard.


Welcome to the Accessibility Wizard

This wizard helps you configure Windows for your vision, hearing, and mobility needs.

If you are using an input device other than a mouse, instead of clicking, use the appropriate action to complete commands or select items throughout the wizard.

To continue, click Next

Accessibility Wizard. *The Accessibility Wizard for Windows 98.*

The wizard leads the user through a series of questions concerning his or her disability and configures mouse, keyboard, and display properties to meet that person's particular need. This tool gives administrators the ability to configure workstations for individuals with physical impairments by leading the user through a series of screens that the user can then respond to in real time. Using the Accessibility Wizard is generally more convenient than using the Accessibility Options property sheet to configure accessibility settings. The wizard's final screen lists the accessibility options that have been enabled.

See Also: *Accessibility Options*

access list

A mechanism by which routers can determine which packets should be forwarded and which should be blocked.

Overview

Routers route packets to their destination by examining the destination address of packets received and then determining which port the packet should be forwarded to. However, sometimes packets should not be forwarded to their destinations at all or should be forwarded to different ports using criteria other than a simple destination address. For example, certain incoming packets may constitute a security hazard to the network and should be blocked and dropped. Load balancing may require that packets be distributed across multiple ports in round-robin fashion instead of delivered to a fixed address. And certain types of traffic have high priority and need special handling. Access lists are a mechanism for handling these issues and provide a packet filtering capability that enhances the power and functionality of routers.

An access list is basically an ordered (sequential) series of rules or filters, each of which either permits or denies the flow of packets across an interface depending on the rule's nature and the packet's contents. When a packet arrives at an interface on which an access list has been created and applied, the rules in the list are applied to the packet in order from the top of the list downward. If the packet's contents match the conditions in a rule, that rule is applied and the packet is either forwarded or dropped. If a rule does not apply, the next rule in the list is tried until either a match is found and the packet processed or the end of the list is reached and the packet is finally dropped (in other words, there is an implicit "deny all" at the end of every access list).

You should consider several things when using access lists to filter packets through a router:

- For an access list to function, it must first be created in the router's memory and then explicitly assigned to a router interface.
- When an access list is applied to an interface, the access list's direction must be specified. That is, you must decide whether the access list will be applied to inbound traffic, outbound traffic, or both.
- The order in which the rules are organized within an access list is important. Two access lists with identical rules but in different order can have significantly different effects.
- Each rule either permits a matching packet to be forwarded or denies a packet from being forwarded.
- By default, an access list implicitly denies everything. In other words, when a packet is being processed by an access list, if a match occurs that allows the packet to be forwarded, the packet is allowed to pass across the interface. If no match is found (the contents of the packet do not explicitly match any of the criteria specified in the rules within the access list), the packet is blocked from passing over the interface and is thus dropped by the router.

Examples

The Internetwork Operating System (IOS) by Cisco Systems, the operating system used by all Cisco routers, has commands for creating access lists and applying them to an interface. IOS supports two different types of access lists:

- **Standard:** A standard access list filters packets based only on their source address.
- **Extended:** An extended access list filters packets based both on their source address and on a number of other criteria including destination address, protocol type, traffic priority, and application type.

A simple example of an IOS access list rule that allows traffic from source address 172.16.15.33 to pass across a specified interface would be

```
access-list 1 permit host 172.16.15.33
```

Here the number "1" specifies that this rule is part of the first access list created on the router, and all rules that have this number belong to the same list. Access list numbers identify what kind of access list is used (see the table).

Examples of Different Kinds of IOS Access Lists

Type of Access List	*Range of Access List Numbers*
Standard Internet Protocol (IP)	1–99
Extended IP	100–199
AppleTalk	600–699
Standard Internetwork Packet Exchange (IPX)	800–899
Extended IPX	900-999

To take another example, if your network is class C and has addresses belonging to the 172.16.44.0 network, to allow stations on your network to have unrestricted access to the Internet through your packet-filtering router, you could use the rule

```
access-list 1 permit 172.16.44.0 0.0.0.255
```

Note that 0.0.0.255 is the binary complement of the default subnet mask of your class C network (255.255.255.0).

As a final example, the following access list blocks incoming traffic from the malicious host 133.16.1.11 but allows all other traffic to enter through the router:

```
access-list 1 deny host 133.16.1.11 log
access-list 1 permit any
```

The *log* keyword specifies that all packets dropped from the malicious host will be logged in the router log and can be viewed using the IOS logging console.

IOS access lists can be created using a simple ASCII text editor and transferred to the router using Trivial File Transfer Protocol (TFTP) or some other mechanism. The Interface command is used to apply an access list to an interface once the list has been created, and the Access-group command is used to specify the direction over the interface for which the list applies.

Notes

One limitation of IOS access lists is that if you want to modify a list by removing or changing a statement in the middle of the list, you cannot. Instead you must create a new access list, remove the old one from the interface, and apply the new list to the interface. You can, however, add rules to the bottom of an existing list, if this meets your needs. To get around having to create an access list from scratch when you need to modify a rule, use TFTP to copy the existing router configuration to a text file on a workstation, modify the file, delete the original configuration on the router, and copy the modified configuration onto the router.

IOS version 12 includes a new feature that allows for the creation and application of time-based access lists, which allows different access lists to be applied to routers at different times and days.

Access lists are sometimes called access control lists, but this can be confusing because the term *access control list (ACL)* also refers to a mechanism for securing file system objects and other operating system objects.

The table in this article shows that there can be only 100 possible access lists for each type of access list. In some circumstances (for example, with complex backbone routers) this is not sufficient, and you can use named access lists instead. Named access lists are referenced using an alphanumeric name instead of a number, and you can create as many of them as you need.

Placement is an important issue to consider when applying access lists to ports. Standard access lists should be placed as close as possible to the destination, but enhanced access lists should be placed as close as possible to the source.

See Also: *Internetwork Operating System (IOS), router*

access mask

A double-word value (32-bit entry) contained within each access control entry (ACE) that defines all possible access rights for a particular type of object (file, folder, and so on).

Overview

Microsoft Windows 2000, Windows XP, and Windows .NET Server use access masks that support several types of access rights. Three examples are:

- **Specific access rights:** These access rights include FILE_READ_DATA and FILE_APPEND_DATA, which provide permission to read and write data in a file. Objects can have up to 16 different specific access rights, depending on the object type.
- **Standard access rights:** These apply to all objects and include DELETE, which grants or denies delete access to an object, and WRITE_OWNER, which grants or denies access to the owner security identifier (SID) of an object.
- **Generic access rights:** These map to specific access rights and standard access rights. Each type of securable object maps generic access rights to its own specific and standard access rights. Generic access rights for file objects include FILE_GENERIC_READ, FILE_GENERIC_WRITE, and FILE_GENERIC_EXECUTE. These three types are listed in Windows Explorer in Windows 2000, Windows XP, and Windows .NET Server and in Windows NT Explorer in Windows NT as the special permissions read (R), write (W), and execute (X).

See Also: *access control entry (ACE), access control list (ACL)*

access method

Any method that allows devices to transmit signals over media in a way that ensures that communications can occur between stations.

See: *media access control method*

access mode

A mode of running a console created with the Microsoft Management Console (MMC).

Overview

Different access modes are provided for MMC consoles in order to allow or restrict access to administrative functionality. This enables senior administrators to create custom consoles for junior administrators that have only the functionality needed to perform specified tasks, while preventing them from using functionality that could cause problems if not handled correctly.

Selecting Options from the Console menu configures access modes for MMC consoles. The two modes available for running consoles are

- **Author mode:** This mode grants the user full access to all the functionality of the MMC, including adding snap-ins, removing snap-ins, creating new console windows, and accessing the entire console tree. Only senior administrators should have this access mode.
- **User mode:** This mode does not allow the user to add snap-ins to or remove snap-ins from the console and restricts access to some of the functionality of the MMC, depending on the options selected. For example, by selecting the Limited Access, Single Window option, the MMC displays only a single console window. User mode has three submodes:
    - **Full Access:** This submode allows the user to view the whole console tree but restricts the user from adding new snap-ins or changing the console's properties.
    - **Limited Access, Multiple Window:** This submode allows the user to view portions of the console tree in different windows.
    - **Limited Access, Single Window:** This submode restricts the user to a single console window.

Notes

If an MMC console is set to user mode, you can start it in author mode by running it from the command line with the /a switch. You can also right-click on the console file (*.msc file) in Windows Explorer and use the shortcut menu to start the console in author mode. However, an administrator can also use Group Policy to prevent the user from opening a console in author mode.

See Also: *Microsoft Management Console (MMC)*

access point (AP)

A device connected to a local area network (LAN) that enables remote wireless stations to communicate with the LAN.

Overview

A wireless networking implementation consists of two parts:

- A wired network such as an Ethernet LAN with an access point attached to it. The access point acts as a bridge between the wired LAN and the remote wireless stations.
- Remote wireless stations with wireless network adapters attached to them.



Access point (AP). *How an access point works.*

An access point (AP) is basically a network-capable device containing a transceiver and antenna for transmitting signals to and receiving signals from the remote stations. The access point thus provides a "point of access” to the wired network for the remote stations. The access points allow wireless stations to be quickly and easily connected to a wired LAN.

An example of a remote station might be a laptop computer. The laptop can communicate with the access point using a wireless Personal Computer Memory Card International Association (PCMCIA) card or wireless network interface card (NIC). An alternative is the station adapter, a device that plugs in to the laptop’s standard 10BaseT port.

A single AP can generally support 15 to 25 wireless stations while still maintaining optimal data transfer rates. The area covered by a single AP is called a cell. The transceiver within an access point uses spread spectrum transmission, which may be either direct sequencing or frequency hopping. For spread spectrum communication in the 2.4 gigahertz (GHz) frequency band, APs typically support data rates of 1 to 3 megabits per second (Mbps) over distances of up to about 2 miles (3 kilometers).

Marketplace

Most commercial APs consist of a combination of an Ethernet port and a transceiver, which allows the AP to be easily connected into an existing wired LAN for bridging to remote wireless stations. Prices for wireless networking equipment based on the 802.11b standard have fallen dramatically in the last few years. A typical AP can cost as low as $300 or as high as $2,000, while wireless network adapters can be as low as $100 each. Examples of APs for small-office home-office (SOHO) use include the Apple Airport, the D-Link DWL-1000AP, and the Lucent RG-1000, and examples of enterprise-class access points include 3Com’s AirConnect Wireless AP, the Cisco AIR-AP341 series, Enterasys’s RoamAbout AP 2000, and the Intel PRO/Wireless LAN AP.

The higher-priced APs provide faster speeds, support more users, and include better management features. For coverage of large areas, several APs may be required to create a pattern of overlapping cells—in this case it is best to purchase the more expensive ones because these include features to support remote stations that roam between cells covered by different APs. The more expensive APs also support connection to external antennas for better transmission coverage.

Many APs include other advanced features including Dynamic Host Configuration Protocol (DHCP), network address translation (NAT), and routing functions. These APs fall under the general category of network appliance because of their simplicity and ease of use.

Notes

When purchasing an 802.11b AP, you may want to consider if it can be easily upgraded to the newer 802.11a standard, which uses 5 GHz transmission.

For best coverage within an office environment, mount APs on ceilings. If this is difficult because of lack of electrical outlets, look for APs that can be powered over Category 5 (Cat5) cable.

If multiple APs are used to provide redundant coverage for an area, then they should be connected using a wired LAN. This will provide better performance for stations within the coverage area than having the APs connected as wireless repeaters.

See Also: *802.11b, wireless networking*

access provider

Also known as Internet service provider (ISP), a company that provides individual users and businesses with connectivity to the Internet.

See: *Internet service provider (ISP), xSP*

access token

An object assigned to a user that successfully logs on to a network and that identifies the level of security privileges assigned to that user.

Overview

An access token is like a card key. Your card key will provide you with access to doors that have been configured to grant you permission to open them. The list of card keys that a door will accept is analogous to an access control list (ACL).



Access token. *A simplified example of an access token at work.*

When you log on to Microsoft Windows NT, Windows XP, Windows 2000, or Windows .NET Server, you are granted an access token that is attached to all your user processes. Your access token contains the security identifier (SID) of your user account and every group to which you belong. When your application tries to access an object such as a file on a volume formatted with the NTFS file system (NTFS), Windows NT, Windows 2000, Windows XP, or Windows .NET Server compares the SIDs in your application's access token to those in the access control entries (ACEs) in the object's ACL. If it finds a match, the system grants access to that object.

See Also: *access control list (ACL)*

account

A set of credentials for gaining access to resources in a network or logging on to a system.

Overview

In a typical network, each user needs an account to access resources on the network, such as shared folders, printers, or applications. Accounts provide a way of identifying users on a network and are the foundation of network security. An administrator or another user with high security privileges typically creates accounts.

Accounts are generally used in server-based networks where a central computer such as a Microsoft Windows 2000 or Windows .NET Server domain controller keeps track of each user's account and grants or denies access to the network based on the credentials entered by the user during the logon process. Accounts are used less frequently in peer-to-peer networks or workgroups because the security requirements are usually much less stringent.

A Windows 2000 or Windows .NET Server network contains various kinds of accounts, including

- **User account:** Identifies users who belong to the domain by storing their names, passwords, the groups they belong to, the permissions they have for accessing system resources, and other personal information
- **Group account:** Identifies a specific group of users and is used to assign them permissions to objects and resources
- **Computer account:** Identifies machines that belong to the domain

See Also: *logon, network security*

account domain

A type of Microsoft Windows NT domain containing accounts for global users and groups.

Overview

Account domains are usually master domains and are typically used in a single or multiple master domain model implementation of Windows NT. The account domain contains user accounts for every user in the enterprise and is usually located at corporate headquarters. Servers and workstations at company branch offices belong to other domains called resource domains. Users at branch offices who want to log on to the network must log on to the account domain, even though their workstations are located within a resource domain.


All enterprise accounts
JohnS
JudyM
KarenL
Domain controller
Account domain
Authentication
Trust
Trust
Authentication
Domain controller
Domain controller
JudyM
JohnS
Resource domain #1
Resource domain #2

G0AXX06 (was G0Aui06.bmp in 1E)

Account domain. *Account domains in Windows NT.*

For this scenario to work, a trust relationship must be established so that each resource domain trusts the account domain. In this way all user accounts can be centralized in the account domain, which eases account management for administrators located at headquarters.

Account domains simplify account administration by centralizing administration to a single domain.

See Also: *resource domain, trust*

account lockout

A condition in which a user is prevented from logging on to the network.

Overview

If account lockout restrictions are set on a network, a user who fails successively to log on will be locked out of the network after a predetermined number of attempts. For example, if a user forgets the password and repeatedly attempts to log on, the authentication provider (a domain controller on a Microsoft Windows 2000 network) assumes that unauthorized access is being attempted and shuts out the user by locking out the account. The account can either remain locked until an administrator unlocks it or it can be configured to unlock after a specified period of time.

Account lockout restrictions are typically part of the account policy that can be set for domains. Account lockout is used to prevent unauthorized access to the network by preventing distrusted users from attempting to guess a trusted user's password. If you set up account lockout on your network, you will probably also want to configure auditing to record failed logon attempts.

Use account lockout only for high-security networks. In a low-security environment, users can become frustrated if they lock themselves out by mistyping their passwords, and administrators must cope with the additional overhead and bother of unlocking these accounts.

See Also: *auditing*

account operator

A user who is assigned the responsibility of administering user and group accounts for a network.

Overview

In Microsoft Windows 2000, Windows XP, or Windows .NET Server, if you want to make an individual an account operator, simply make that person a member of the Account Operators group. Account operators can administer accounts only on a domain controller, not on a member server or workstation.

Account operators have the preassigned rights to log on locally to a domain controller and to shut down the system. In addition, account operators have the built-in capacity to create and manage user accounts, global group accounts, and local group accounts, as well as to keep local profiles.

Account operators should be assigned in enterprise-level networking environments only. In small to medium-sized networking environments, creating and configuring user accounts is usually the administrator's responsibility.

See Also: *user account*

Account Operators group

A built-in security group in Microsoft Windows 2000, Windows XP, and Windows .NET Server where users are account operators.

Overview

Members of the Account Operators group can create, delete, and modify the properties of users, global groups, and local groups. The Account Operators group exists only on domain controllers and has an empty initial membership. The Account Operators group has the following preassigned rights:

- Log on locally
- Shut down the system

Additionally, members of the Account Operators group have the ability to create, delete, and modify user and group accounts using the Active Directory Users and Computers console.

Members of the Account Operators group cannot modify the membership or rights of the following built-in groups:

- Administrators
- Account Operators
- Server Operators
- Print Operators
- Backup Operators

See Also: *built-in group*

ACE

Stands for access control entry, a single entry in an access control list (ACL).

See: *access control entry (ACE)*

ACK

Stands for acknowledgment, a transmission from a receiving station to a transmitting station telling it that the transmitted data has been received without errors.

Overview

ACKs play an important role in most network protocols. For example, Transmission Control Protocol (TCP) is a connection-oriented protocol that relies on acknowledgments for successful transmission of data. When a stream of TCP packets is being sent over the network, each packet contains an acknowledgment number indicating the sequence number of the next packet that the receiving station should expect to receive. TCP can use an ACK to acknowledge a series of TCP packets (instead of just a single packet) that have been received. A TCP packet sent as an acknowledgment has its ACK flag set to 1 to indicate that the acknowledgment numbers of the packets received are valid.

During a transmission, if the receiving station determines that the data transmission is late or has not arrived, a negative acknowledgment (NAK) is generated to indicate to the transmitting station that the data should be sent again.

See Also: *Transmission Control Protocol (TCP)*

ACL

Stands for access control list, any mechanism for implementing access control on a file system object, directory object, or other operating system object.

See: *access control list (ACL)*

ACM

Stands for the Association for Computing Machinery, the oldest and largest educational and scientific computing society in the world.

See: *Association for Computing Machinery (ACM)*

ACPI

Stands for Advanced Configuration and Power Interface, a specification for power management of computer hardware.

See: *Advanced Configuration and Power Interface (ACPI)*

ACR

Stands for attenuation to crosstalk ratio, the ratio of the received strength of a signal on a pair of wires (attenuation) to the amount of crosstalk between the wires.

See: *attenuation to crosstalk ratio (ACR)*

Active Desktop

A feature of Microsoft Windows that enables active content from Web sites or channels to be displayed directly on the desktop.

Overview

Active Desktop was first introduced with Microsoft Internet Explorer version 4, and made possible the dynamic downloading and display of content such as graphics, Hypertext Markup Language (HTML) pages, Microsoft ActiveX controls, Java applets, and channels. For example, you could have a stock ticker applet placed directly on your desktop that updates its information continually using a live Internet connection.

Active Desktop integrates the Web and your desktop, allowing you to launch programs, switch between files, and customize your desktop using active Web content. Active Desktop makes your desktop and its folders look and work like the Web, allowing you to browse resources on your computer or local network the same way you browse for content on the World Wide Web. Information about volumes, folders, and files can be displayed as Web pages within folders, and you can move up and down the folder hierarchy using a single click instead of a double click.

Active Desktop is included with Windows 98, Windows Millennium Edition (Me), Windows 2000, Windows XP, and Windows .NET Server and is available for Windows 95 and Windows NT 4 as an option by installing Internet Explorer 4 and the Windows Desktop Update.

The Active Desktop is implemented as an application programming interface (API) called the IActiveDesktop interface, which is part of the Windows Shell API. This interface is designed to allow client programs to manage desktop items and wallpapers on local computers. It also provides methods for adding desktop items (with or without a user interface, allowing the user to decide whether to accept the addition), adding desktop items associated with a Uniform Resource Locator (URL), applying changes by writing settings to the registry, and so on.


Network Neighborhood
File Edit View Go Favorites Help
Back Forward Up Cut Copy Paste Undo
Address Network Neighborhood
Network Neighbor
\\Schatz
Ingrid's standalone workstation
Entire Network
Schatz
Selkirk
1 object(s) selected
Inbox
Recycle Bin
MT IT
MTIT Enterprises
Enterprises
About Us
channel guide
broadcast
news & technology
sports
business
entertainment
lifestyle & travel
The Microsoft Network
News
Start
Network Neighborhood
8:48 PM

Welcome to **MTIT Enterprises**, a registered business based in Winnipeg, Manitoba, Canada. My name is **Mitch Tulloch**, and I am President of MTIT Enterprises. I am:

Active Desktop. *Web elements on Active Desktop.*

The Active Desktop consists of two layers:

- **HTML layer:** This is the background layer that hosts active Web content items. The Hypertext Markup Language (HTML) layer has three components: a file named desktop.htm that contains HTML tags for each active Web component on the desktop, an ActiveX control that lets you move or resize components on your desktop, and any other static HTML element you want to display in the background.
- **Icon layer:** This transparent foreground layer integrates a Web-type environment with familiar Windows 95 shell features such as double-clicking, drag-and-drop, file associates, and so on.

Users can add new items to the Active Desktop on their machines by using the display utility in Control Panel (or by right-clicking a blank area of the desktop and choosing Properties from the context menu). Either specify the URL of the object you want to add to your Active Desktop or browse to locate it on your network or on the Internet (if you are connected). Programmers can use the ActiveDesktop interface to write routines that add, remove, or modify items on the Active Desktop. You can also add items to the Active Desktop using a Channel Definition Format (CDF) file.

See Also: *Active Platform*

Active Digital Profile (ADPr)

An Extensible Markup Language (XML) specification for automating the provisioning of IT (information technology) resources.

Overview

XML is becoming the de facto standard for exchange of electronic information, superseding previous standards such as Electronic Data Interchange (EDI). To standardize exchange in different business areas, XML schema are used. Active Digital Profile (ADPr) is a proposed XML schema that allows for the electronic allocation and deployment of IT (information technology) resources such as hardware and software. As an XML schema, ADPr provides a vendor-neutral and platform-independent model for these business processes to take place at a high level.

ADPr is based on software created by Business Layers in conjunction with Novell, CheckPoint Software, and other companies. ADPr has been submitted to the Organization for the Advancement of Structured Information Standards (OASIS) as a proposed XML standard.

See Also: *Organization for the Advancement of Structured Information Systems (OASIS), XML*

Active Directory

The directory service for the Microsoft Windows 2000 and Windows .NET Server network operating systems.

Overview

Active Directory directory service consists of both a database and a service. Active Directory is a database of information about resources on the network, such as computers, users, shared folders, and printers. It is also a service that makes this information available to users and applications.

Active Directory provides the basic features needed for an enterprise-level directory service, including an extensible information source, naming conventions for directory objects, a common set of policies, and tools for administering the service from a single point of access. Administrators can configure Active Directory to control access to network resources by users and applications. Active Directory provides network administrators with centralized administration of all information about resources on the network, and it provides both users and administrators with advanced search capabilities for locating resources on the network.

Information in Active Directory is maintained for each domain on the network. Active Directory database information is stored and maintained on machines called domain controllers. This information is replicated automatically between domain controllers to ensure that every portion of the distributed directory is up to date. By default, the replication of updates to Active Directory occurs automatically every five minutes. Automatic replication of Active Directory information occurs only within the security boundary of a specific domain. Domain controllers in one domain do not automatically replicate with those in another domain.

Architecture

Active Directory's basic element is the object. An object can represent a user, computer, printer, application, file, or another resource on the network. Active Directory objects possess attributes, which are their properties. For example, some user attributes might include first name, last name, e-mail address, and phone number. Some attributes must have mandatory values, and others can be left undefined. A printer's attributes might include its location, its asset number for accounting purposes, its type, and so on. Active Directory also has a set of rules governing which objects can be stored in the directory and which attributes these objects can possess. This set of rules is known as the schema.

A special type of Active Directory object is the organizational unit (OU). An OU is a type of object that can contain other objects. An OU can either contain a specific object, such as a user or an application, or it can contain another OU. Using OUs, you can organize Active Directory into a hierarchical directory of network information based on the X.500 directory recommendations of the International Telecommunication Union (ITU). You can assign users permissions on subtrees of OUs for management and resource access purposes.

Organizational units are contained within domains, which are Active Directory's basic security and organizational structure. Every object in Active Directory must belong to a domain. Domains usually mirror the organizational structure of your enterprise and act as a security boundary in it. For example, privileges granted in one domain are not automatically carried over to another domain. Domains can be joined into larger structures called trees using two-way transitive trusts, and these tree structures can be grouped into forests. Typically one forest is created per enterprise when Active Directory is deployed.

The collection of objects, OUs, domains, trees, and forests represent Active Directory's logical structure. Active Directory's physical structure consists of various layers of programming elements on servers called domain controllers. These programming elements include

- **Directory System Agent (DSA):** The process that provides access to the Active Directory store where directory information is stored on the domain controller's hard drive.
- **Database Layer:** This layer provides a uniform interface for the DSA for accessing the store.
- **Extensible Storage Engine (ESE):** This is a version of the database engine on Microsoft Exchange Server 5.5 and is used to provide access to the Active Directory store, which is capable of storing information about many millions of directory objects.

Above these layers are various interfaces and protocols by which various clients can access Active Directory. These include

- **Lightweight Directory Access Protocol (LDAP):** Supports LDAP clients such as Microsoft Outlook and Active Directory Services Interface (ADSI).
- **Replication transports (REPL):** Supports replication transports such as remote procedure call (RPC) and Simple Mail Transfer Protocol/Internet Protocol (SMTP IP) for Active Directory replication.
- **Security Accounts Manager (SAM):** Supports Windows NT 4 networking application programming interfaces (APIs) and replication with Windows NT backup domain controllers (BDCs).
- **Messaging Application Programming Interface (MAPI):** Supports Outlook and other MAPI-compliant clients.

Other protocols whose implementation is of crucial importance for Active Directory include Domain Name System (DNS) and Transmission Control Protocol/Internet Protocol (TCP/IP).

Implementation

Before implementing Active Directory in your enterprise, you will need to gather information about your organization's structure because Active Directory usually mirrors this structure in some fashion. A good way to proceed is to use a centralized planning approach with a team consisting of both technical and management representatives. You must develop a naming strategy, plan your domain structure, and consider how you will delegate administrative duties concerning Active Directory. When you delegate administrative control to Active Directory, do so at the OU level instead of at the individual object level. This makes it easier to control portions of the OU hierarchy within Active Directory. In particular, you probably want to delegate control to individuals responsible for creating users, groups, computers, and similar objects.

Consider the speed of the various links between your different geographical locations and how any systems that are not interoperable with Active Directory will be integrated into your new system. You should also profile your user community to determine what sort of domain hierarchy you will be implementing. Also consider integrating your DNS zone information into Active Directory because this will store your DNS zone information in the distributed Active Directory. Plus, it will facilitate and simplify updates of zone information through replication of domain controllers.

An important planning issue is determining where to locate domain controllers and global catalog servers for your enterprise because after Active Directory is installed and configured, the majority of Active Directory traffic is related to Active Directory clients querying Active Directory for information. Directory replication traffic is usually a less important consideration, unless the organization is in a constant state of flux. Placing a domain controller at each site will optimize queries but can increase replication traffic. Nevertheless, placing a domain controller at a site that has users in that domain is usually the best solution. If the domain tree is large, you should not place a global catalog server at each site because this can create a lot of replication traffic. Place global catalog servers only at large regional sites. Remember that replication of modifications made to your Active Directory might take some time to propagate throughout your enterprise. For example, if you create a new user account object, it might be a few minutes before the user can actually log on to the network using the account.

Notes

The default naming convention for objects stored in Active Directory is an Active Directory canonical name of the object. This defines the object's position in a domain tree from left to right, starting with the object's name and delimited by slashes. For example, the User Account JSmith in the Marketing OU of the northwind.microsoft.com domain would have the Active Directory canonical name

```
Jsmith/users/marketing/northwind.microsoft.com
```

Active Directory supports non-DNS naming conventions for interoperability with non-DNS environments. An example is the LDAP naming convention. An LDAP Uniform Resource Locator (URL) is composed of the name of the server with the distinguished name of the object appended to it. Other naming conventions include the following:

- **User principal name:** This convention consists of the user's SAM account name with an object's user principal name suffix appended to it. The user principal name suffix is the name of the domain tree or the name of the domain above the object in the domain tree.
- **Request for Comments (RFC) number 822 name:** This naming convention is essentially the user's e-mail address.
- **Universal Naming Convention (UNC):** This convention can be used for shared resources.

Discretionary access control lists (DACLs) and system access control lists (SACLs) protect Active Directory objects. DACLs and SACLs specify which user or application has permission to access attributes of directory objects and work in a similar fashion to access control lists (ACLs) that are implemented in the version of NTFS file system (NTFS) used in Windows NT 4. DACLs and SACLs can be used to propagate their permissions to connected directory objects. They also provide a simple way for administrators to grant access and usage rights for Active Directory to users and groups.

See Also: *domain (DNS), forest, organizational unit (OU), tree, trust, Windows 2000*

Active Directory Client

Client software running on a machine and enabling it to access information published in Active Directory directory service.

Overview

Microsoft Windows 2000, Windows XP, and Windows .NET Server come with a built-in Active Directory client so that they can participate immediately in an Active Directory–based network. Some other versions of Windows may require an Active Directory client to be installed prior to participating in such a network.

A version of Active Directory Client called the Directory Services client is available for computers running Windows 95 and Windows 98. This client allows them to log on to a Windows 2000 or Windows .NET Server domain and access information published in Active Directory. The Directory Services client can be found in the \clients folder on the Windows 2000 Server compact disc. Microsoft Internet Explorer version 5.0 or later must be installed on the machine running Windows 95 or Windows 98 prior to installing the Directory Services client. A similar client is also available for Windows NT version 4 machines.

See Also: *Active Directory*

Active Directory Domains and Trusts

A management console in Microsoft Windows 2000 and Windows .NET Server that can be used for administering domains and trust relationships.



Active Directory Domains and Trusts. *The Active Directory Domains and Trusts console.*

Overview

Active Directory Domains and Trusts provide administrators with a graphical representation of all the domain trees in a domain forest. Using the Active Directory Domains and Trusts, you can perform common administrative tasks such as

- Creating an explicit domain trust and managing existing trust relationships between domains
- Changing the domain mode from mixed mode to native mode
- Adding user principal name suffixes for a forest

Notes

You can also use the Active Directory Domains and Trusts to open Active Directory Users and Computers by right-clicking on a domain and then selecting Manage from the shortcut menu.

See Also: *administrative tools (Windows 2000, Windows XP, and Windows .NET Server)*

Active Directory Installation Wizard

A wizard in Microsoft Windows 2000 Server and Windows .NET Server that installs the Active Directory directory service on a machine.

Overview

Active Directory Installation Wizard promotes member servers or stand-alone servers into domain controllers. You can use Active Directory Installation Wizard to



Welcome to the Active Directory Installation Wizard

This wizard helps you install Active Directory services on this server, making the server a domain controller.

To continue, click Next.

Active Directory Installation Wizard. *Using the Active Directory Installation Wizard to install Active Directory.*

- Create a new domain controller with a new domain tree
- Create a new domain controller with a new child domain that islocated under a parent domain in an existing domain tree
- Create a replica domain controller for an existing domain

You must be an administrator to run Active Directory Installation Wizard. Start the wizard by running the Dcpromo utility from the command prompt or choose the Run command from the Start menu, enter *dcpromo* in the Run dialog box, and then click OK. This opens the wizard's welcome screen, where you are required to make a number of decisions concerning the following:

- Whether to create a new domain or add a replica domain controller to an existing domain
- If you choose to create a new domain, whether to create a new domain tree or add a child domain to an existing tree
- If you choose to create a new domain tree, whether to create a new domain forest or add the new tree to an existing forest

Names you specify for new or existing domains, domain trees, or domain forests are based on the Domain Name System (DNS) naming system. Other steps in the wizard allow you to specify the path to the Active Directory database, the location of the System Volume (SYSVOL) share, and so on.

Running Active Directory Installation Wizard has the following results:

- The machine on which the wizard is run becomes a domain controller. If it is the first domain controller in your domain, the wizard also creates a new site for that controller. If it is the first domain in your enterprise, it is also the root domain for any domain tree that will be created. You can use the wizard to create the first domain forest in your enterprise, too.
- The first domain controller is also your global catalog server.
- Active Directory files are located in %SystemRoot%\Ntds with the associated log files.
- The shared system volume SYSVOL, which stores scripts used for implementing group policies for your domain, is located in %SystemRoot%\Sysvol.
- A number of default organizational units (OUs) are created, namely the Users, Builtin, Computers, and Domain Controllers.

Notes

You must make sure that DNS is already installed and configured prior to running Active Directory Installation Wizard in order to create the first domain controller for your network. A DNS name will be needed for your new domain controller, and a DNS server must be available on the network during the installation process.

Active Directory files also require an NTFS file system (NTFS) volume, which must be configured as a basic volume. Dynamic volumes cannot be used for Active Directory files. Running the wizard creates a log file in the %SystemRoot%\Debug folder that shows the results of the installation procedure.

If you are creating a new child domain, an available domain controller must be in the existing parent domain. If you are creating a replica domain controller, an available domain controller must be in the target domain.

See Also: *Active Directory, domain controller*

Active Directory schema

The formal term for all object classes that can be stored in Active Directory directory service and all attributes that make up these object classes.

Overview

The schema defines which kinds of objects are permitted to be published in Active Directory and states their possible attributes. The schema consists of two types of objects:

- **Classes:** These objects are predefined collections of attributes. For example, every user account on a network is represented in Active Directory by a User class object.
- **Attributes:** This is the actual information stored in an object. For example, a User class object is composed of attributes such as Name, PhoneNumber, and so on.

Attributes are defined separately from classes. This allows each attribute to be defined only once and then used in many different classes. Class definitions (such as the User class) and attribute definitions (such as the Name attribute) are themselves objects within Active Directory. This means you can manage class and attribute definitions in Active Directory with the same tools you use to manage other objects (user and group accounts, computers, and so on).

The Windows 2000 and Windows .NET Server Active Directory includes a default schema that defines commonly used object classes such as users, groups, computers, domains, organizational units (OUs), and security policies. Active Directory is extensible and can be modified using Active Directory Schema. Specifically, you can modify the schema by

- Defining new object types and their attributes
- Defining new attributes for existing object classes
- Removing attributes from existing object classes
- Removing existing object classes

Some applications such as Microsoft Exchange Server 2000 are also designed to extend the Active Directory schema for application-specific purposes.

Notes

Members of the Schema Admins group, of which the default Administrator account is automatically a member, are the only users who can make changes to the schema. A typical reason for modifying the Active Directory schema might be adding new attributes to an existing User object—for example, a SeniorityLevel attribute.

Before you can use this tool to modify the schema, you must add a registry setting to your machine and specify the one domain controller that can be used to modify the schema for your enterprise. This prevents unauthorized access to the schema and inconsistencies that can occur when the schema is simultaneously modified in more than one place.

Another way of modifying Active Directory schema is to write a script that uses Active Directory Service Interfaces (ADSI) to make calls that modify the schema. This is the best solution if you want to modify the schema for an entire enterprise or if you want to automate modifications to the schema.

Existing object classes and their attributes cannot actually be deleted; they are simply marked “defunct” in Active Directory and can no longer be used.

The schema is located under the rootDSE object, which contains information about the directory and is located at the top of the Lightweight Directory Access Protocol (LDAP) directory naming structure. You can access this object using the LDAP Uniform Resource Locator (URL):

```
LDAP://rootDSE
```

See Also: *Active Directory*

Active Directory Service Interfaces (ADSI)

A set of object-oriented programming interfaces for providing programmatic access to Active Directory objects.

Overview

Active Directory Service Interfaces (ADSI) consist of a set of general interfaces built on the Component Object Model (COM) that lets applications work with various types of directories using a single access method. ADSI works by abstracting the capabilities of directory services from different network providers to present a single set of interfaces for managing network resources in a distributed computing network. ADSI provides a simple, open, functionally rich, and scriptable method for interfacing with any directory service, independent of the vendor.

Programmers and administrators can use ADSI to create directory-enabled applications using tools such as Microsoft Visual Basic or Microsoft Visual C++. ADSI can be used to create new users and groups, locate and manage printers, and perform other administrative functions on a Windows 2000 or Windows .NET Server network.

ADSI is only a part of a more general Microsoft family of APIs called the Windows Open Directory Services Interfaces (ODSI). Other OSDI interfaces include the Network Provider Interface, Windows Sockets Registration and Resolution (RnR), and RPC OLE DB.

Architecture

ADSI consists of two types of COM objects (directory service leaf objects and directory service container objects) that clients can manipulate with interfaces. ADSI providers are used to implement these objects and their interfaces. Each object in a given namespace is identified using a unique name. For example, file system objects can be specified using their absolute path, and directory objects are usually specified using their X.500 address. However, ADSI is flexible enough to handle any naming system used by third-party vendors' directory service implementations.

Advantages and Disadvantages

Using ADSI for directory access has the following benefits:

- **Open:** ADSI is an open platform for which any directory vendor can develop an ADSI provider.
- **Simple:** ADSI consists of a small collection of easy-to-learn programming interfaces.
- **Extensible:** Independent software vendors (ISVs) and directory service (DS) vendors can enhance ADSI by developing their own objects and functions.
- **Language independence:** ADSI is based on COM and can be used by any programming language that supports COM.
- **DS independence:** ADSI is independent of the DS being used, so developers using ADSI do not have to learn the underlying machinery of the directory they are using ADSI to access.
- **Scriptable:** Automation-compatible languages such as VBScript and Perl can be used to automate directory tasks using ADSI.
- **OLE DB aware:** ADSI can be used to access data sources through OLE DB.

Notes

Windows 2000, Windows XP, and Windows .NET Server contain ADSI providers for accessing the following types of directories:

- Active Directory directory service
- Lightweight Directory Access Protocol (LDAP)
- Novell Directory Services (NDS)
- Windows NT directory services

ADSI supports the LDAP C API defined in Request for Comments (RFC) number 1823, which specifies a low-level interface for C language programming and provides support for the Messaging Application Programming Interface (MAPI) so that legacy MAPI applications will work with Active Directory.

ADSI was formerly known as OLE DS.

See Also: *Active Directory, directory*

Active Directory Sites and Services

A management console in Microsoft Windows 2000 and Windows .NET Server that can be used for administering sites, domain trees, domain controllers, subnets, and intersite links.

Overview

Using Active Directory Sites and Services, you can perform common administrative tasks such as

- Creating a new site and configuring replication within the site
- Configuring directory service (DS) objects and licensing site settings


AD Sites and Services
Console
Window
Help
Action
View
Tree
Active Directory Sites and Services
Sites
Calgary-Site
Inter-Site Transports
IP
SMTP
Subnets
Toronto-Site
Winnipeg-Site
Servers
MAIN
PORTAGE
PEMBINA

Name	Domain	Type	Description
MAIN		Server	
PORTAGE		Server	
PEMBINA		Server	

Active Directory Sites and Services. *The Active Directory Sites and Services console.*

- Adding servers, domain controllers, intersite links, and subnets to a site
- Moving and repairing domain controllers
- Delegating control of a site

See Also: *administrative tools (Windows 2000, Windows XP, and Windows .NET Server)*

Active Directory Users and Computers

A management console in Microsoft Windows 2000 and Windows .NET Server that can be used for administering Active Directory objects and information published in the directory.

Overview

Using Active Directory Users and Computers, you can perform common administrative tasks such as

- Creating a new user, group, shared folder, computer, printer, or other resource
- Creating new organizational units (OUs) for organizing directory objects
- Moving directory objects to different OUs
- Deleting objects from the directory
- Displaying and editing the properties of directory objects
- Managing group policies and changing domain controllers


Active Directory Users and Computers
Console
Window
Help
Action
View
Tree
Active Directory Users and Compu
northwind.microsoft.com
Builtin
Computers
Domain Controllers
ForeignSecurityPrincipals
Users
Users 16 objects

Name	Type	Description
Administrator	User	Built-in account for ad...
Cert Publishers	Security Group - Global	Enterprise certification...
Domain Admins	Security Group - Global	Designated administra...
Domain Computers	Security Group - Global	All workstations and s...
Domain Controllers	Security Group - Global	All domain controllers i...
Domain Guests	Security Group - Global	All domain guests
Domain Users	Security Group - Global	All domain users
Enterprise Admins	Security Group - Global	Designated administra...
Group Policy Cre...	Security Group - Global	Members in this group...
Guest	User	Built-in account for gu...
IUSR_RUMPUS7	User	Built-in account for an...
IWAM_RUMPUS7	User	Built-in account for Int...
krbtgt	User	Key Distribution Cente...
RAS and IAS Ser...	Security Group - Domai...	Servers in this group ...
Schema Admins	Security Group - Global	Designated administra...

Active Directory Users and Computers. *The Active Directory Users and Computers console.*

- Finding objects within the Active Directory database

Notes

If you want to quickly assign permissions to network resources such as file shares, printers, users, and groups in your enterprise, simply move their associated directory objects to different servers that require the same permissions to the same OU. Objects inherit permissions from their new OU and lose permissions from their old OU. However, permissions assigned directly to an object are moved together with the object.

See Also: *administrative tools (Windows 2000, Windows XP, and Windows .NET Server)*

active hub

A hub that has electronic circuitry to regenerate weak signals.

Overview

Active hubs function as multiport repeaters, allowing computers to be networked together in a star topology. Virtually all hubs sold today are active hubs, so one generally refers to them nowadays simply as hubs.

See Also: *hub, passive hub*

active partition

The partition that contains the boot files for an operating system.

Overview

The active partition is the one from which the operating system boots. On a machine running Microsoft Windows 2000, Windows XP, or Windows .NET Server, the active partition must also be a primary partition and must be located on a basic disk.

Depending on the Microsoft operating system used, you can use any of the following tools to make a partition active:

- The Fdisk utility from the command prompt for MS-DOS and all Microsoft Windows platforms
- The Disk Administrator administrative tool in Windows NT
- The Computer Management administrative console in Windows 2000

Notes

Alpha-based computers running Windows NT have no active partitions. Instead, the boot volume is configured by a manufacturer-supplied configuration program.

See Also: *partition (Active Directory), system partition*

Active Platform

A set of Microsoft technologies for developing applications for the Internet.

Overview

Active Platform is actually an umbrella term for three key Microsoft technologies:

- **Active Desktop:** Integrates the Microsoft Windows desktop with the Internet, providing a seamless connection between local and remote applications and resources. Active Desktop is a core technology of Internet Explorer.
- **Active Server:** The Active Platform component of Microsoft Internet Information Services (IIS) version 5 or later. Using Active Server technologies, core Windows NT services can be extended to the Internet using applications developed with Microsoft Active Server Pages (ASP) technologies.
- **Microsoft ActiveX:** A component software technology based on the Component Object Model (COM). ActiveX allows distributed Web-based applications to be developed in any programming language and then run from within an ActiveX-enabled browser such as Internet Explorer.

Applications developed using Active Platform technologies can be accessed and run from any client platform independent of the operating system, as long as a standard Web browser such as Microsoft Internet Explorer is installed on the client.

See Also: *Active Desktop, Active Server Pages (ASP), ActiveX*

active scripting

Using a scripting language to drive Component Object Model (COM) components.

Overview

Host applications such as Microsoft Internet Information Services (IIS) with Microsoft Active Server Pages (ASP) and Microsoft Internet Explorer have scripting engines for running scripts written in VBScript or JScript. Active scripting engines can be developed for other interpretive scripting languages, such as Perl, to build upon a developer's existing knowledge of these programming platforms. Scripting engines for client software, such as Internet Explorer, are specially designed to eliminate the authoring components that are not needed in a nonauthoring host environment. This makes the client-side scripting engine lightweight, which yields better performance.

In a typical scenario, the host application loads the script document and calls an application programming interface (API) to create a new instance of a scripting engine. The host application feeds the script to the engine and executes the script.

See Also: *Active Server Pages (ASP)*

Active Server Pages (ASP)

An open, compile-free application environment for developing Web applications using Microsoft Internet Information Server (IIS) version 3 and later, including Internet Information Services (IIS) in Windows 2000, Windows XP, and Windows .NET Server.

Overview

Active Server Pages (ASP) can be used to build powerful, distributed Web-based applications that combine Hypertext Markup Language (HTML), script, and Microsoft ActiveX technologies to provide dynamic Web sites. ASP combines the ease of HTML with familiar programming tools such as Microsoft Visual Basic Scripting Edition (VBScript) and Microsoft JScript, along with reusable Component Object Model (COM) components. These components can be used to build powerful, dynamic Web sites. ASP executes on the Web server, and the output returned to the Web browser is a plain HTML file.

Architecture

ASP is implemented in IIS as an Internet Server Application Programming Interface (ISAPI) filter called Asp.dll, which resides in the same memory space as IIS. User requests for ASP pages, which have the suffix .asp appended to them, are processed by the filter which loads the necessary language dynamic-link libraries (DLLs) for interpreting script on the page, executes server-side script on the server, and returns the remaining HTML and client-side script to the browser requesting the page.

ASP pages have the file extension .asp and typically contains a mixture of HTML, scripts, and other components written in any programming language. The scripts can reference components running on either the local server or any other accessible server and can perform actions such as accessing a database, sending e-mail, or processing information in another fashion. The result is then returned by the server to the client as a standard HTML file and displayed in the usual way.

The Asp.dll also includes an object model that encapsulates properties and methods for seven built-in objects: Application, ASPError, ObjectContext, Request, Response, Server, and Session. These objects are available for any .asp page requested. For example, the Response object can be used to control how data is sent to the requesting client.

ASP organizes collections of ASP pages into applications, which are typically groups of files within a given virtual directory and its subdirectories. ASP applications (also known as Web applications) can have global variables and can save state information so that a session can exist across several requested pages in succession. Session-level data is initiated by reference to a file called Global.asa, which is checked whenever a new client makes a request to pages in an ASP application.

Examples

For example, when requested, the following ASP file will return the current time and browser type to the requesting client:

```
<HTML>
<HEAD><TITLE>Sample Web Page</TITLE></HEAD>
<BODY>
The time right now is <% = now %>
Your browser type is <%
=Request.ServerVariables("http_user_agent")
%>
</BODY>
</HTML>
```

You can use ASP to develop Web content that is customized for user preferences and demographics and that uses Microsoft ActiveX Data Objects (ADO) and open database connectivity (ODBC) to provide access to multiple data sources. ASP provides a browser-neutral approach to the design of Web applications where all of the application logic resides on the server.

Notes

Active Server Pages was first introduced as a beta technology code-named “Delani” for the Microsoft Internet Information Server 2 platform.

Unlike the stateless Hypertext Transfer Protocol (HTTP), ASP is a session-based technology. When a user connects to an ASP file on a Web server, a session object is created. After the session expires, the session object is destroyed. The default time-out for ASP applications is 20 minutes, although Outlook Web Access uses a time-out of 60 minutes.

For More Information

To learn more, visit Charles Carroll’s ASP site at *www.activeserverpages.com.*

See Also: *Active Platform*

Active Setup

A Microsoft ActiveX engine that can be used to download and install software over the Internet interactively using a Web browser.

Overview

Active Setup makes use of the fact that source files of the application to be installed are partitioned into segments, the traditional cabinet installation files (*.cab files). Active Setup begins by downloading a small, self-extracting setup package to the browser client. This file also collects information about the client's computer to help determine which components already exist on the system and whether the desired application is compatible with the system's configuration. The user specifies a location from which to download the desired application and the types of components to be installed. The application's *.cab files are then downloaded as needed, after which Active Setup is completed and normal installation can continue.

One advantage of Active Setup is that if the download is interrupted, it can be resumed at the interruption point rather than at the beginning.

See Also: *ActiveX*

active volume

The volume in Microsoft Windows 2000, Windows XP, and Windows .NET Server from which a computer boots.

Overview

In Windows 2000, Windows XP, and Windows .NET Server disk terminology, active volumes on dynamic disks are what active partitions are on basic disks. The active volume for a system must be a simple volume; in other words, it cannot be a striped set or mirrored volume.

You can upgrade the basic disk that contains the active partition to a dynamic disk, making it a simple volume that is active, but you cannot mark an existing dynamic volume as the active volume.

See Also: *active partition, dynamic disk*

active window

The particular open window that has the focus on a Microsoft Windows desktop.

Overview

The active window is the window belonging to the application in which the user is currently working. If several windows are open on a user's desktop, only one of these windows can be the active window. A unique color on the active window's title bar distinguishes it from other windows. If the user enters commands or text using the keyboard, these commands or text will be routed to the program displaying the active window. To make a window the active window on the desktop, simply click on it using the mouse, or cycle through the windows on the desktop using Alt+Tab.

Notes

You can capture a bitmap image of the active window to the clipboard by pressing Alt+PrintScreen. Then open Paint, paste the contents of the clipboard into the program, and save it as a *.bmp image.

See Also: *Microsoft Windows*

ActiveX

An umbrella term for Microsoft technology for building lightweight reusable software components.

Overview

The term *ActiveX* was first coined at the Internet Professional Developers Conference (Internet PDC) in 1996 and was based on the conference slogan "Activate the Internet."

Microsoft ActiveX is built on the Component Object Model (COM) and Distributed Component Object Model (DCOM) technologies, which enable software components to interact with each other across a network. ActiveX does not replace object linking and embedding (OLE) but broadens and enlarges it to include the Internet and intranet technologies.

ActiveX is supported by most Microsoft development and productivity applications, including Visual Basic, Visual C++, and Office.

For More Information

Visit the Microsoft COM site at *www.microsoft.com/com.*

See Also: *Component Object Model (COM), OLE*

ActiveX component

A Component Object Model (COM)–based application that allows other applications to use the classes it contains.

Overview

An ActiveX component represents a server application because it can serve other applications that call it. An application that calls an ActiveX component thus functions as a client application. Other names for ActiveX components are ActiveX servers, ActiveX DLLs, and COM components.

You can create ActiveX components using tools from Microsoft Visual Studio such as Microsoft Visual Basic and Microsoft Visual C++.

See Also: *ActiveX, COM component object*

ActiveX controls

Compiled, reusable software components based on Microsoft Corporation's Component Object Model (COM).

Overview

ActiveX controls can be used as prefabricated components to help developers rapidly build user interfaces for applications. ActiveX controls can draw themselves in their own windows, respond to events such as mouse clicks, and be managed through properties and methods. An ActiveX control cannot run as a stand-alone program but must be loaded into a control container such as Microsoft Visual Basic or Microsoft Internet Explorer.

History

The earliest form of custom controls in the Microsoft Windows platform were Visual Basic Extension (VBX) controls, which were 16-bit dynamic-link libraries (DLLs) in Windows 3.1 that had specific entry points and designed to work with VB forms to provide specific graphical user interface (GUI) functionality. With the introduction of object linking and embedding (OLE), VBX controls were replaced by 32-bit OLE Custom Extension (OCX) controls that supported type libraries and had better C++ support. Unfortunately, OCX controls tended to be bloated because they contained a large number of COM interfaces, whereas the applications calling them may only require a few of these interfaces. This was a particular concern when downloading controls over the Internet, so ActiveX controls, which were basically OCX controls in which the interfaces were optional, were created. ActiveX controls are thus lightweight controls and may even have no interface at all, as in ActiveX Data Objects (ADO).

Uses

ActiveX controls are often used to provide dynamic features for Web pages—for example, a stock ticker control that adds a live stock ticker to a Web page, an advanced user interface navigation tool, and an animation control that adds animation functionality to a page.

ActiveX controls can be embedded into a Hypertext Markup Language (HTML) page by using the HTML <OBJECT> tag. If a user tries to access such a page using a Web browser and the embedded ActiveX control is not installed on the user's system, the control can be automatically downloaded by using the URL specified in the CODEBASE attribute of the <OBJECT> tag. Once the ActiveX control is downloaded and installed on the user's system, the browser will continue to use the cached control until an updated version becomes available on the server.

Here is an example of a typical <OBJECT> tag that includes a CODEBASE attribute:

```
<OBJECT ID="BoomButton" WIDTH=225 HEIGHT=35
CLASSID="clsid:56F1BF40-B2D0-11d0-A6D6-
00AA00A70FC2"
CODEBASE="http://example.microsoft.com/
AControl.cab#Version=1,0,0,1">
</OBJECT>
```

Notes

A malicious ActiveX control can potentially damage software or data on a user's computer. To help users determine whether an ActiveX control is safe to install, Microsoft has developed a code-signing technology called Authenticode, which identifies the creator of a control using a digital signature issued by a well-known security authority such as VeriSign.

ActiveX Data Objects (ADO)

A data access interface developed by Microsoft Corporation and used for communicating with OLE DB-compliant data sources.

Overview

ActiveX Data Objects (ADO) is a high-level object-based interface to OLE DB, in other words, an OLE DB consumer (OLE DB is a generic data access technology from Microsoft). Using ADO and OLE DB, a client application can connect to a variety of data sources using the same programming model. These data sources include relational databases, hierarchical databases, indexed sequential access method (ISAM) databases, and virtually any other kind of data source for which an open database connectivity (ODBC) driver exists. In other words, ADO is intended to be a universal information interface.

In order to communicate with these unique data sources, ADO and OLE DB employ components called OLE DB providers, which are designed for specific data sources. If a native OLE DB provider is not available for a data source, but an ODBC driver is available, it should be possible to access the data source using the ODBC driver and an OLE DB provider designed to communicate with ODBC drivers.

Uses

ADO is supported in a variety of programming environments. For example, ADO can be used in Microsoft Visual C++ and Microsoft Visual Basic to access data in an OLE DB data source such as Microsoft SQL Server. ADO can also be used in conjunction with IIS to create Microsoft Active Server Pages (ASP) applications that access data sources.

In a Web-based environment, ADO is basically a server-based solution for data access. All data operations, such as changes to database records and filtering, must take place on the server. The client can then receive the data but cannot easily manipulate it. For applications in which the client must be able to manipulate the data being accessed, use remote data binding with Remote Data Service (RDS) instead. RDS is a technology that enables the user to manipulate data on the client and have any changes automatically made on the server. Allowing data to be manipulated on the client makes Web applications faster and more responsive.

ADO 2.5 is an integral part of the Microsoft Windows 2000 platform.

Architecture

ADO is based on a collection of Component Object Model (COM) and COM+ interfaces, and its object model is a simple COM-based architecture, which consists of static and dynamic object models. ADO communicates with a database through type libraries. Choosing the right library can significantly improve data access performance. For example, if Microsoft SQL Server is running on the same machine as Microsoft Internet Information Services (IIS), using named pipes can provide better performance than using the Transmission Control Protocol/Internet Protocol (TCP/IP) networking library.

The ADO 2.5 object model includes the following object types: Connection, Command, Errors, Fields, Record, Recordset, Parameters, and Stream.

Notes

Microsoft distributes ADO as part of the Microsoft Data Access Components (MDAC), a package that includes drivers and providers for ADO, OLE DB, and ODBC.

ADO 2.5 can also be used with ExOLEDB to provide access to the Web Storage System on Exchange 2000.

See Also: *ADO+, ADO.NET*

adapter

A device for connecting two different types of electronic hardware without losing information.

Overview

In local area network (LAN) networking, an adapter is a small device with two different connectors that provide data transmission back and forth between two different types of media (cabling). Adapters come in many varieties and are typically specified by stating the two connector types used and whether these connectors are male or female. For example, a DB9(f)-DB25(m) adapter means an adapter with a DB9 female and a DB25 male connector.

Adapters are a necessary part of the network administrator’s toolkit because of the large number of connectivity options provided by networking equipment vendors.

Notes

The term *adapter* is also used in a number of different contexts in networking, including the following examples:

- Network interface cards (NICs) are sometimes called network adapter cards because they provide connectivity between computers and network cabling.
- Cigarette lighter adapters can be used to power cellular phones or laptops from an automobile battery.
- Digital phone adapters allow analog modems to be connected directly to Private Branch Exchange (PBX) phone outlets without damage.
- SC/ST adapters provide connectivity between fiber-optic connectors of differing types.

See Also: *connector (device)*

adaptive acceleration

An umbrella name for a group of technologies that expands the capacity of data channels.

Overview

Adaptive acceleration expands the amount of data that can be delivered over a given amount of bandwidth. This boosts network performance and helps overcome bottlenecks due to bandwidth limitations, a condition that affects most Internet service providers (ISPs), application service providers (ASPs), and other types of service providers. While throwing bandwidth at the problem is one way of handling the issue, adaptive acceleration tries to squeeze the best performance out of a fixed amount of bandwidth without dramatically increasing costs.

Adaptive acceleration works by combining several different techniques. These techniques can be incorporated into switching or routing gear or into stand-alone appliances and are targeted particularly towards traffic carried over the Internet. Some of the techniques used in adaptive acceleration include

- **Adaptive packet compression:** This assigns a different data compression algorithm to different types of data. For example, Hypertext Markup Language (HTML) files compress differently from Microsoft Word files, and adaptive packet compression scans packets for different kinds of files and compresses them in the most efficient manner for each type.
- **Selective caching:** This technique makes use of advanced algorithms to determine which files (or portions of files) can benefit most by being cached. For example, an entire Word file might be cached, or only the properties of the file. As another example, a .gif image might be cached, or only its palette.
- **Vertical data analysis:** This technique uses an algorithm that parses the different level protocol headers in packets, compresses it, repackages it, and applies rules to handle it more efficiently. This makes data transfer more efficient and can enhance and prioritize time-sensitive traffic such as voice or video over IP.

See Also: *caching*

Adaptive Differential Pulse-Code Modulation (ADPCM)

A technique for converting analog sound, such as speech, into binary digital information by frequently sampling the sound and expressing its modulation in binary form.

Overview

Adaptive Differential Pulse-Code Modulation (ADPCM) codecs convert analog signals into digital information by quantizing the differences between the actual analog signal and a predicted signal. The result is that analog signals encoded into files using ADPCM have a smaller size than many other formats. ADPCM enables speech information to be compressed into small files for storage and transmission.

Personal Communications Services (PCS) cellular telephony systems use a 32-kilobits per second (Kbps) ADPCM coding system to provide the same quality of voice communication that isavailable in wired telephone networks. This standard was developed by the International Telecommunication Union (ITU) and is known as G.721.

See Also: *modulation*

ADC

Stands for analog-to-digital converter, any device for changing analog signals into digital transmission.

See: *analog-to-digital converter (ADC)*

address book view

A virtual container in Microsoft Exchange that lets Microsoft Exchange Server administrators group recipients according to common attributes.

Overview

Address book views are created automatically when you establish the defining attributes for the address book view. For example, using the Exchange Administrator program, you could create an address book view called By Department and use the Department attribute of the recipients in your Exchange organization to automatically generate various address book view containers called Sales, Marketing, Management, and so on. Each address book view container will contain only those recipients that belong to a specific department.

For instance, when users access the global address list using Microsoft Outlook, these containers will be visible in their address books, along with their recipients. This allows users to more quickly address e-mail to recipients in a particular department instead of scrolling down the entire global address list.

You can also create multilevel address book views. For example, you could create a first level of virtual containers sorted by Country, followed by a second level sorted by State.

Notes

If you use the Exchange Administrator program to move a recipient from one address book view to another, the recipient takes on the defining attributes of the new address book view.

See Also: *Exchange Server*

address record

A Domain Name System (DNS) record mapping a host name to an Internet Protocol (IP) address.

See: *A record*

Address Resolution Protocol (ARP)

The Transmission Control Protocol/Internet Protocol (TCP/IP) network layer protocol responsible for resolving Internet Protocol (IP) addresses into Media Access Control (MAC) addresses.

Overview

When a TCP/IP-aware application tries to access another TCP/IP host using its IP address, the destination host's IP address must first be resolved into a MAC address so that the frame can be addressed and placed on the wire and then be recognized by the destination host's network interface card (NIC). This is because NICs operate at the physical layer (Layer 1) and data-link layer (Layer 2) of the Open Systems Interconnection (OSI) reference model and must use physical addresses (such as MAC addresses) instead of logical addresses (such as IP addresses) for network communication.



Address Resolution Protocol (ARP). *How ARP works.*

Address Resolution Protocol (ARP) broadcasts an ARP request packet that effectively says, "Who has the following IP address?" This broadcast requests the MAC address of the destination host. The destination host then responds with an ARP reply packet containing its own MAC address. The requesting host next temporarily stores the IP-to-MAC-address mapping in its local ARP cache in case this is required again within a short time.

Notes

If the destination host is on a remote network, ARP obtains the MAC address of the local router interface that connects the local network to the remote network.

ARP is defined in RFC 826.

See Also: *Arp command*

ADMD

Stands for Administrative Management Domain; in X.400 messaging, a message-handling system (MHS) that is managed by a registered private agency.

See: *Administrative Management Domain (ADMD)*

ADMIN$

A special administrative share created during installation on computers running Microsoft Windows 2000, Windows XP, and Windows .NET Server and used for remote administration of the computer.

Overview

The Administrators group is assigned full control permissions on the ADMIN$ share on a Windows 2000, Windows XP, or Windows .NET Server system. This allows administrators to access the share and remotely administer the system without needing to know where the system files are stored. Only the Administrators group has access to the ADMIN$ share.

This share's path is always the path to the %SystemRoot% directory (usually C:\Winnt).

See Also: *administrative share*

administrative alert

A pop-up dialog box in Microsoft Windows 2000, Windows XP, and Windows .NET Server that notifies users of problems or issues.

Overview

Administrative alerts are generated by the Alerter service in Windows 2000, Windows XP, and Windows .NET Server. These alerts can be directed towards specified users and computers.

Administrative alerts are typically displayed when problems with security, access, sessions, directory replication, or printing occur or when a server is shut down by an uninterruptible power supply (UPS) device.

See Also: *service*

Administrative Management Domain (ADMD)

In X.400 messaging, a message-handling system (MHS) that ismanaged by a registered private agency.

Overview

Administrative Management Domains (ADMDs) are usually large public telecommunications carriers such as MCI/WorldCom and AT&T. This is in contrast to a Private Management Domain (PRMD), which represents a message-handling system managed by a private corporation. In the X.400 world, PRMDs cannot communicate directly with each other; instead, they must communicate through ADMDs. All the ADMDs in the world therefore form a kind of messaging backbone for global X.400 communication.

Notes

The ADMD is the second field in a typical X.400 originator/recipient (O/R) address and is located right after the country field.

See Also: *X.400*

administrative share

A share created during setup by Microsoft Windows 2000, Windows XP, and Windows .NET Server for system purposes and remote administration.

Overview

Administrative shares end in the "$" character, which makes them hidden shares. You cannot modify the permissions on these shares and you cannot remove the shares.

Some examples of administrative shares include

- **C$, D$, and so on:** The shares used by administrators to connect to the root of each volume on a network server and perform remote administration such as creating and deleting files and folders

- **ADMIN$:** The share name for the %SystemRoot% folder, used by the system during remote administration
- **IPC$:** A share used by interprocess communication (IPC) resources for sharing the named pipe interface, which allows applications running on different computers to communicate over the network
- **PRINT$:** A share used to support shared printers
- **REPL$:** A share used by the Directory Replicator Service that allows directory trees to be exported
- **NETLOGON:** A share used by the NetLogon service that enables the processing of domain requests

See Also: *hidden share*

administrative tools (Windows 2000, Windows XP, and Windows .NET Server)

A program group in Microsoft Windows 2000, Windows XP, and Windows .NET Server containing tools for administering a network based on these versions of Windows.

Overview

Most Windows 2000 administration tools are primarily implemented as preconfigured snap-ins for the Microsoft Management Console (MMC). Such tools are commonly referred to as consoles. Each administrative tool corresponds to an MMC console with a particular snap-in installed.

The set of available tools for a particular machine running Windows 2000, Windows XP, or Windows .NET Server depends on how that machine was installed and configured. Commonly installed tools for Windows 2000 Server, Windows XP, and Windows .NET Server, which can be used for both local and remote administration, include

- Component Services
- Computer Management
- Configure Your Server
- Data Sources (ODBC)
- Distributed File System
- Event Viewer
- Internet Services Manager
- Licensing
- Local Security Policy
- Performance
- Routing and Remote Access
- Server Extensions Administrator
- Services
- Telnet Server Administration

Notes

As an administrator, you can create your own administrative tools by opening a blank MMC console and installing the various snap-ins you need. When you save this tool, it will automatically be saved in the Administrative Tools program group.

See Also: *Windows 2000*

administrative tools (Windows NT)

A program group in Microsoft Windows NT containing tools for administering a Windows NT–based network.

Overview

The basic set of tools for Windows NT Server 4 consists of the following:

- Administrative Wizards
- Backup
- Disk Administrator
- Event Viewer
- License Manager
- Migration Tool for NetWare
- Network Client Administrator
- Performance Monitor
- Routing and Remote Access Admin

- Server Manager
- System Policy Editor
- User Manager for Domains
- Windows NT Diagnostics

You can extend these basic tools by installing additional Windows NT services using the Network utility in Control Panel, which provide the following additional tools:

- DHCP Manager
- DNS Manager
- File Manager
- Network Monitor
- WINS Manager

Notes

You can install a subset of these administrative tools on Windows NT Workstation 4 and a smaller subset on Windows 95 or Windows 98. The files required to install the client-based network administrative tools on Windows NT Workstation 4 and Windows 95 or Windows 98 are available in the \Clients\Srvtools directory on the Windows NT Server 4 compact disc.

See Also: *Windows NT*

administrator

A user who has full rights and permissions to manage any resources on the network.

Overview

The administrator is usually responsible for tasks such as installing, managing, and controlling servers and networking components. Administrators can also modify the properties of user accounts and the membership of groups, create and manage security printers, install printers, share resources, and assign permissions to those resources.

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, the Administrator account is a built-in account whose password is defined during installation. The Administrator account is a member of the Domain Admins group and the Administrators group on the domain controller on which it is defined, and it has full rights and permissions on all user-accessible system resources.

Notes

On a domain controller, the Administrator account is a global user account, while on a stand-alone server or workstation, the Administrator account is a local user account.

You can rename the default Administrator account, but you cannot delete it. If you rename the account, make sure you remember what the new name is!

See Also: *Administrators group*

Administrators group

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, a built-in group whose default membership consists of the Domain Admins group.

Overview

The Administrators group has full rights on all user-accessible processes on a computer running Windows 2000, Windows XP, or Windows .NET Server. For example, on a domain controller, the Administrators group has the right to

- Log on locally
- Access the computer over the network
- Take ownership of files
- Change the system time
- Configure auditing and manage the security log
- Shut down the system
- Back up and restore files and directories
- Force shutdown from a remote system
- Load new device drivers
- Add computers to the domain in Windows NT and Windows 2000

See Also: *administrator, built-in group*

ADO

Stands for ActiveX Data Objects, a data access interface used to communicate with OLE DB–compliant data sources.

See: *ActiveX Data Objects (ADO)*

ADO+

A version of Microsoft ActiveX Data Objects (ADO) for the Microsoft Windows Distributed interNet Applications Architecture (Windows DNA).

Overview

ADO+ is a more scalable, more interoperable, and more strongly typed version of ADO. The programming and object model for ADO+ is radically different from ADO because ADO is designed from the ground up to work with disconnected data sets (ADO included some support for disconnected record sets starting with ADO 2.0). An ADO+ data set is a disconnected in-memory view of a database. Data sets can be created dynamically without any interaction with a database management system (DBMS), so data sets are an evolution of the previous concept of ADO record sets. Data sets can contain any number of tables, and these do not need to correspond to a particular database table or view. ADO+ thus models data, not databases or data providers the way ADO did.

What particularly distinguishes ADO+ is that it utilizes Extensible Markup Language (XML) as its universal format for data transmission. This gives ADO+ its wide interoperability with any platform supporting XML, and receivers no longer need to be COM objects as they were with ADO.

See Also: *ActiveX Data Objects (ADO), Windows Distributed interNet Applications Architecture (Windows DNA)*

ADO.NET

The evolution of Microsoft Corporation’s Active X Data Objects (ADO) for its new .NET platform.

Overview

ADO.NET provides the classes necessary to ADO to enable access to Extensible Markup Language (XML) documents and relational data stores. Some of the differences between ADO.NET and ADO are the following:

- While ADO uses the RecordSet object, which looks like a single table, ADO.NET uses the DataSet object, which can contain one or more tables represented by DataTable objects.
- While ADO uses Component Object Model (COM) marshalling to transmit a disconnected record set, ADO.NET transmits a DataSet with an XML file (the XML format places no restrictions on data types and requires no type conversion).
- While ADO has trouble transmitting data through firewalls because firewalls are typically configured to prevent system-level requests such as COM marshalling, ADO.NET can easily transmit data through firewalls because ADO.NET DataSet objects use Hypertext Markup Language (HTML)–based XML, which can pass through firewalls.

See Also: *ActiveX Data Objects (ADO), .NET platform*

ADPCM

Stands for Adaptive Differential Pulse-Code Modulation, a technique for converting analog sound, such as speech, into binary digital information by frequently sampling the sound and expressing its modulation in binary form.

See: *Adaptive Differential Pulse-Code Modulation (ADPCM)*

ADPr

Stands for Active Digital Profile, an Extensible Markup Language (XML) specification for automating the provisioning of IT (information technology) resources.

See: *Active Digital Profile (ADPr)*

ADR

Stands for Advanced Data Recording, a tape backup technology developed by Philips.

See: *Advanced Data Recording (ADR)*

ADSI

Stands for Active Directory Service Interfaces, a set of object-oriented programming interfaces for providing programmatic access to Active Directory objects.

See: *Active Directory Service Interfaces (ADSI)*

ADSL

Stands for Asymmetric Digital Subscriber Line, a form of Digital Subscriber Line (DSL) technology that provides subscribers with high-speed voice and data services over twisted-pair copper phone lines.

See: *Asymmetric Digital Subscriber Line (ADSL)*

ADSL modem

A modem used to terminate an Asymmetric Digital Subscriber Line (ADSL) connection between the customer premises and the ADSL provider.

Overview

ADSL modems are customer premises equipment (CPE) for connecting subscribers to telcos offering ADSL services. ADSL modems are typically used to provide high-speed Internet access for residential and business customers.

ADSL modems operate by dividing the available bandwidth in Plain Old Telephone Service (POTS) telephone lines into separate upstream and downstream channels. This is typically done in one of two ways:

- **Frequency division multiplexing (FDM):** This technique separates upstream and downstream communications into two separate channels with a band of unused frequency between them to prevent crosstalk and reduce interference. If you need to, you can then further divide each of these two channels using time-division multiplexing (TDM).
- **Echo cancellation:** This technique employs overlapping upstream and downstream channels and separates them using V.32/V.34 echo cancellation methods used in modems.

Of these two techniques, echo cancellation offers better utilization of bandwidth but is more complex to implement.

To separate the two data channels from the voice channel used for ordinary telephone communications, ADSL modems include a POTS splitter, a type of filter placed at the carrier side of the modem which splits off the first 4 kilohertz (kHz) of bandwidth and routes it to the telephone. This way, if an ADSL provider goes down and data communications cease, regular POTS telephone service still works at the customer premises.

See Also: *Asymmetric Digital Subscriber Line (ADSL), modem*

Advanced Configuration and Power Interface (ACPI)

A specification for power management of computer hardware.

Overview

Advanced Configuration and Power Interface (ACPI) is an open industry specification that was designed to enable software designers to integrate power management features through all parts of a computer system, including the hardware, the operating system, and application software. ACPI is the successor to the Advanced Power Management (APM) specification and differs by allowing the operating system to control hardware power consumption instead of the basic input/output system (BIOS).

Microsoft Windows 2000, Windows XP, and Windows .NET Server support Advanced Configuration and Power Interface (ACPI), and it enables Windows to handle all the power-management resources for computer subsystems and peripherals. ACPI works with subsystems and peripherals for a wide range of mobile, desktop, and server platforms. ACPI is also the foundation for the OnNow industry initiative that enables computers to start at the touch of the keyboard.

Notes

Your PC must be fully compatible with ACPI for you to use it, regardless of whether your operating system supports it. To find out if your PC supports ACPI, go into the BIOS, look for an ACPI option, and turn it on.

You can also enable ACPI support for Windows 98 by running Setup using the command-line switch Setup /p j. Running Setup in this mode adds the ACPIOption string value with a value data of 1 to the Windows 98 registry and causes hardware devices to be queried for ACPI support during setup. Note that Windows 98 does not support all ACPI features—Passive Cooling Mode, for example.

For More Information

Find out about ACPI at *www.teleport.com/~acpi.*

Find out about the Microsoft OnNow initiative at *www.microsoft.com/hwdev/onnow.htm.*

See Also: *Advanced Power Management (APM)*

Advanced Data Recording (ADR)

A tape backup technology developed by Philips.

Overview

Advanced Data Recording (ADR) is a technology that writes eight tracks of data simultaneously to a single tape. This gives ADR tape drives a very high throughput. Tapes move slowly in ADR tape drives, which makes for minimal tape wear and quieter operation.

ADR tape drives are available from OnStream and popular models include:

- **ADR30:** Has a capacity of 15 gigabytes (GB) and a transfer rate of 60 megabytes (MB)/min.
- **ADR50:** Has a capacity of 25 GB and a transfer rate of 120 MB per minute.

For More Information

Visit OnStream at *www.onstream.com*.

See Also: *tape format*

Advanced Encryption Standard (AES)

The new U.S. government encryption standard adopted to replace the aging Data Encryption Standard (DES) standard, which no longer offers sufficient security.

Overview

Until recently the U.S. government has used DES as the encryption scheme for security sensitive electronic transmissions. However, a 56-bit DES key was successfully cracked in 1997 using idle processing cycles on thousands of machines distributed across the Internet. Advances in computing in the last few years have made DES even more vulnerable as an encryption mechanism, and as a result an initiative was put forward by the U.S. government to develop a scheme that could not be cracked.

The result of this initiative is the Advanced Encryption Standard (AES), which officially replaced DES in the spring of 2001. AES supports key lengths of 128, 192, and 256 bits, which offers a vast improvement in security over 56-bit DES and even 168-bit Triple DES, in which three DES keys are applied in succession. The National Institute of Standards and Technology (NIST) has calculated that it would take about 149 trillion years to crack an AES-coded message using an algorithm that could crack DES in one second (no such algorithm currently exists), so AES is likely to remain secure for some time to come. Using the maximum level of encryption (256-bit), a cracker would have to generate and test 1.1×10^{77} unique keys in order to crack an AES message, which is currently beyond conception for brute-force computing power.

Architecture

AES is a block cipher, which means that it encrypts data in fixed-length blocks of 128 bits at a time. AES uses the Rijndael algorithm developed by Vincent Rijmen and Joan Daemen. This algorithm was chosen over four competing algorithms because it is easy to implement and is efficient with regard to calculation, making AES suitable for use even in devices such as cell phones and Personal Digital Assistants (PDAs) that have limited processing power. The Rijndael algorithm executes 10 rounds of encryption when using a key length of 128 bits.

Prospects

Although AES has become the official standard for U.S. government encryption, it will continue to coexist with DES and Triple DES for a number of years as hardware and software vendors update their encryption schemes. However, industry is expected to quickly upgrade to AES because DES is no longer secure and Triple DES is inherently slow. AES will also be licensed for commercial use by industry.

Notes

Web browsers, the ubiquitous interface to Web applications, mostly use RC4 encryption. Although the next generation of Web browsers will likely license AES for use, millions of desktop computers are likely to continue to use older browsers for years.

For More Information

Find out more about AES at the site of the National Institute of Standards and Technology at *csrc.nist.gov/encryption/aes.*

See Also: *Data Encryption Standard (DES), encryption*

Advanced Infrared (AIr)

A wireless networking technology for high-speed, low-cost infrared (IR) networking.

Overview

Advanced Infrared (Air) allows ad hoc multipoint wireless peer-to-peer connections to be formed simultaneously between multiple wireless information appliances such as Personal Digital Assistants (PDAs), cellular phones, laptops, and digital cameras. The devices must be within 26 feet (8 meters) of each other to reliably communicate without interference.

AIr ports can receive signals within a 120-degree cone, which means that the ports need not be precisely aimed at each other to achieve reliable transmission.

AIr currently supports data throughput of up to 4 megabits per second (Mbps) for direct line-of-sight communication, but it can interoperate with the existing slower Infrared Data Association (IrDA) 1.1 standard, and it supports the Very Fast Infrared (VFIR) standard currently under development.

IBM developed AIr and was the first vendor to release products based on this standard. IBM is working with the IrDA to standardize the technology.

See Also: *Infrared Data Association (IrDA), infrared transmission*

Advanced Intelligent Tape (AIT)

A tape backup technology developed by Sony Corporation.

Overview

Advanced Intelligent Tape (AIT) is a popular tape backup format that has a native capacity of 25 gigabytes (GB) (uncompressed) per tape and supports transfer speeds of 6 megabits per second (Mbps). AIT supports high data compression rates—typically 2:1 or higher. Access times are low because the tape's spine contains embedded 16-kilobyte (KB) nonvolatile memory chips that store the backup set headers. Thus, when a particular backup set is requested, the tape can spool directly to the required spot without having to search through the data. This results in longer life for the tape. Another feature of AIT is that the heads are self-cleaning and only occasionally require maintenance, which also extends media life.

Sony's AIT tape drives are typically cheaper than Quantum's digital linear tape (DLT) drives, and they have gained a solid foothold in large companies. AIT tape libraries are also available from various vendors for terabyte storage needs.

AIT 2 is a second-generation AIT standard and supports up to 50 GB (uncompressed) per tape, but this can often translate into up to 125 GB compressed. AIT 2 transfer speeds are typically 7 megabytes per second (MBps) or higher. AIT 3 is emerging as the next generation of AIT standards, and it should be competitive with the 100 GB native capacity and 13 MBps transfer rates of the competing Linear Tape Open (LTO) tape backup technology.

See Also: *tape format*

Advanced Mobile Phone Service (AMPS)

The original first-generation (1G) analog cellular phone service. Still used in some parts of North and South America.

Overview

Bell Laboratories invented the technology for Advanced Mobile Phone Service (AMPS) in the 1970s, and AT&T introduced it as a commercial service in

1983. AMPS represents the first generation of cellular phone technology widely deployed throughout the United States and was the first fully standardized automatic mobile telephone service in the world. In addition to the United States, AMPS was also deployed in South America, Australia, and China.

AMPS uses frequencies in the 800 megahertz (MHz) band (from 824.04 to 893.7 MHz) of the radio spectrum. AMPS uses Frequency Division Multiple Access (FDMA) to create individual communications channels. FDMA is used to modulate a 3 kilohertz (kHz) voice channel onto a 30 kHz carrier signal using frequency modulation (FM). This creates a series of 30 kHz wide channels for one-way transmission (by contrast, an FM radio station uses a 150 kHz bandwidth channel). Separate channels are used for base station to mobile transmission (forward channels) and mobile station to base transmission (backward channels). In fact, forward channels fall within the range 869.04 to 893.97 MHz and backward channels are found from 824.04 to 848.97 MHz. The 45 MHz between these two bands helps separate forward and reverse transmission and reduces interference and crosstalk.

AMPS can assign only a single subscriber at a time to each channel, so the resulting allocation of bandwidth results in a maximum of 832 simultaneous phone conversations per operator. Because the population of most cities would suggest that 800 simultaneous phone conversations is far from enough, the idea was developed to partition the coverage of cities into a number of small areas called “cells” (this explains the origin of the terms “cellular communications” and “cell phone”). Each base station uses a limited-power transmitter with a directional antenna to provide coverage for a small geographical cell. A typical cell ranges from 1640 feet (500 meters) to 12.5 miles (20 kilometers) in size, depending on whether the coverage is in a densely populated urban area or a sparsely populated rural one.

Because cell phones have limited transmission power, communication is limited to the base station servicing the immediate cell the user is currently in. As a user moves from one cell to another, the signal strength gradually decreases until a threshold limit is reached. Once this threshold is reached, the base station informs the Mobile Telephone Switching Office (MTSO) that the subscriber is leaving the service area of that base station. The MTSO hands off the call to the base station that the subscriber is starting to enter (adjacent cells overlap), which smoothly picks up the call so service is not interrupted. Adjacent cells employ different frequencies to help prevent interference from occurring between them.

Handheld AMPS cellular phones have power levels generally under 0.6 watts with a range of about 5 miles (8 kilometers) from the base station, but power levels in vehicle-mounted phones reach up to 3 watts with a range of 15 miles (24 kilometers). Base stations themselves generally have power levels up to about 1 kilowatt.

Prospects

Because of the need for data transmission and security (encryption), digital cellular phone services such as Time Division Multiple Access (TDMA) and Code Division Multiple Access (CDMA) systems are steadily increasing in popularity as AMPS continues to decline. Nevertheless, market statistics indicate that as recently as 1999 AMPS remained the cellular communications service with the greatest area of coverage across North America. However, the success of AMPS has been its downfall—the limited number of channels per cell means that when too many people subscribe to the service, blocking (the inability to make a call because no channel is available) becomes a problem. Another problem is that when a subscriber roams into a cell where no channels are available, the subscriber’s call is dropped (suddenly disconnected without warning).

Notes

Other 1G analog cellular phone systems included Total Access Communication System (TACS) and Extended TACS (E-TACS) used in the United Kingdom and Nordic Mobile Telephone (NMT) used in the Scandinavian countries. AMPS, however, was by far the most popular and widely deployed 1G service.

AMPS can also be used for data transmission, but it is capable of supporting data rates of only about 9.6 kilobits per second (Kbps).

For More Information

Visit the site of the Universal Wireless Communication Consortium at *www.uwcc.org* for information on all types of cellular communications systems.

See Also: *cellular communications, Code Division Multiple Access (CDMA), Digital Advanced Mobile Phone Service (D-AMPS), Global System for Mobile Communications (GSM), Time Division Multiple Access (TDMA)*

Advanced Peer-to-Peer Networking (APPN)

A protocol developed by IBM as the second generation of Systems Network Architecture (SNA).

Overview

Advanced Peer-to-Peer Networking (APPN) is an extension of SNA that was developed for several reasons:

- To enable SNA traffic to flow concurrently with other protocols.
- To provide for prioritization of SNA traffic through it is class-of-service (CoS) features.
- To allow users to establish communication sessions without mainframe involvement.

APPN provides a mechanism for peer-to-peer networking and session establishment between any two logical units (LUs) on an SNA network. APPN provides greater distributed network control than legacy SNA by isolating the effects of single-point failures. It supports the dynamic exchange of information about network topology to facilitate connection, reconfiguration, and route selection. APPN also supports the dynamic definition and automated registration of network resources.

Prospects

APPN was a promising technology that for various reasons ended up failing to make much of an impact on mainframe computing environments. APPN equipment was costly and difficult to manage, and IBM's marketing scheme of requiring third-party developers of APPN hardware and software to contribute royalties from earnings to IBM led to a famous clash between IBM and Cisco Systems in 1994 over this issue. APPN is today considered a legacy technology that is being phased out.

See Also: *Systems Network Architecture (SNA)*

Advanced Power Management (APM)

A legacy specification for power management of computer hardware.

Overview

Advanced Power Management (APM) was the precursor to Advanced Configuration and Power Management (ACPI) and was implemented in versions of Microsoft Windows prior to Windows 2000. APM used the basic input/output system (BIOS) to manage all computer hardware and peripherals. This had several disadvantages that motivated the development of ACPI, namely

- Different hardware platforms from different vendors often used different BIOS chips, which meant that in a large enterprise power management capabilities varied from machine to machine, making troubleshooting more difficult.
- Suspend mode is supported poorly because the BIOS cannot know whether the user or the system initiated the suspend.
- Universal serial bus (USB) and Institute of Electrical and Electronics Engineers (IEEE) 1394 peripherals were not supported by APM.

ACPI addresses these concerns by enabling the operating system to control power to devices, not the BIOS.

Notes

If your machine's BIOS uses APM 1 or 1.1, try to flash upgrade the BIOS to support APM 1.2 if possible to resolve certain issues relating to system instabilities when in standby mode.

Microsoft Windows 2000, Windows XP, and Windows .NET Server support both APM and ACPI, with ACPI being the preferred option. The tool Ampstat.exe in the Support/Tools folder on the Windows 2000 CD can be used to troubleshoot issues relating to APM.

See Also: *Advanced Configuration and Power Interface (ACPI)*

Advanced Program-to-Program Communications (APPC) protocol

A set of protocols developed by IBM that enables transactional programs to communicate with each other.

Overview

The Advanced Program-to-Program Communications (APPC) protocol was originally designed for Systems Network Architecture (SNA) networks and has been implemented in Multiple Virtual Storage (MVS), Operating System/2 (OS/2), Advanced Interactive Executive (AIX), and OS/400. APPC is also supported over Transmission Control Protocol/Internet Protocol (TCP/IP) using IBM's Anynet architecture. APPC was first introduced into the AS/400 series as its native communications platform and was called LU 6.2.

Applications that use APPC to communicate are called transaction programs (TPs) and utilize a package of APPC routines called Common Programming Interface–Communications (CPIC). APPC services are available for applications written in C++, REXX, COBOL, and other languages.

APPC is not a widely deployed platform and is most often employed for its file transfer services.

Notes

Microsoft Host Integration Server provides services necessary for APPC connectivity with AS/400 systems and mainframe hosts.

See Also: *Systems Network Architecture (SNA)*

Advanced Streaming Format (ASF)

A method of streaming data supported by Windows Media Player.

Overview

Advanced Streaming Format (ASF) supports video, audio, images, Uniform Resource Locators (URLs), and scripts. ASF streams can combine different types of data, allowing you to stream presentations involving slides and audio narration. Using the Windows Media Encoder, you can generate live ASF streams that contain audio and video.

You can also use tools provided with Windows Media Encoder to create and store ASF files that you can later stream.

Windows Media Services can deliver ASF streams using either multicasting or unicasting.

Notes

When multicasting an ASF stream, configure Windows Media Services to provide a supplemental unicast source for the stream for any clients that cannot receive multicasts.

Advanced Technology Demonstration Network (ATDnet)

A high-speed test bed network that is part of SuperNet, the cross-country network funded by the Next Generation Internet (NGI) program.

Overview

Advanced Technology Demonstration Network (ATDnet) is deployed in the Washington D.C. area and was developed as a prototype for the next generation of Metropolitan Area Networks (MANs). It is funded by the Defense Advanced Research Projects Agency (DARPA) and serves as an experimental test bed platform for research and development. ATDnet network transport consists of Synchronous Optical Network (SONET) and Asynchronous Transfer Mode (ATM) running over fiber and currently uses a double ring topology that supports 20 gigabits per second (Gbps).

For More Information

You can visit ATDnet at *www.atd.net.*

AES

Stands for Advanced Encryption Standard, the new U.S. government encryption standard adopted in the spring of 2001 to replace the aging Data Encryption Standard (DES) standard, which no longer offers sufficient security.

See: *Advanced Encryption Standard (AES)*

AFTP

Stands for APPC File Transfer Protocol, a protocol that provides file transfer capabilities for the Advanced Program-to-Program Communications (APPC).

See: *APPC File Transfer Protocol (AFTP)*

agent

Simple Network Management Protocol (SNMP) client software that runs on a hub, a router, or another networking component.

Overview

Agents collect information about Transmission Control Protocol/Internet Protocol (TCP/IP) statistics and conditions and can supply this information when requested to an SNMP management system. Agents can also alert management systems to errors and other conditions when a trap occurs. SNMP agents are identified by the community to which they belong. By default, SNMP agents listen to TCP port number 161 for SNMP messages and to port number 162 for SNMP traps.

An agent must be installed on each networking component or host that will be managed in an SNMP-managed network. The agent program can then perform operations such as

- Get operations initiated by the SNMP management console for obtaining information about a specific managed object in the host Management Information Base (MIB)
- Get-next operations initiated by the management console to continue traversing the MIB database from the point at which it was accessed by a get operation
- Set operations initiated by the management console to set a value for a managed object (if permissions allow this)
- Trap operations initiated by the managed host itself when an error condition occurs, such as when the computer's disk becomes full

Notes

Windows 98 also includes an SNMP agent conforming to SNMP 1 specifications that lets you monitor remote connections to machines running Windows 98 from an SNMP management console. This agent is implemented as a Win32 service using Windows Sockets over TCP/IP. You can install the Microsoft SNMP agent on Windows 98 using the Network utility in Control Panel.

See Also: *Simple Network Management Protocol (SNMP)*

AGLP

A mnemonic for managing an enterprise-level Microsoft Windows NT network.

Overview

AGLP means that user **A**ccounts are organized by placing them in **G**lobal groups, which are then placed into **L**ocal groups that have appropriate **P**ermissions and rights assigned to them.

In practice, the steps for administering a Windows NT enterprise-level network are the following:

1. Create global user accounts for users in the account domains or master domains.
2. Create global groups in these domains to organize users according to function, location, or some other criteria (or use the Windows NT built-in groups if these suffice).
3. Assign global users to their respective global groups.
4. Determine who needs access to network resources in the resource domains.

5 Create local groups on domain controllers and member servers within the resource domains (or use the Windows NT built-in groups if these suffice).

6 Assign rights and permissions to each local group as desired to provide access to network resources.

7 Place global groups into local groups as desired to provide users with permissions to access resources.


A
Accounts are organized by placing them into...
G
Global groups, which are then placed into...
L
Local groups that have...
P
Permissions and rights assigned to them

AGLP. *Using AGLP to administering a Windows NT–based network.*

Notes

On Windows 2000– and Windows .NET Server–based networks, the mnemonic is AGDLP because local (L) groups are referred to as domain local (DL) groups. However, because Windows 2000 and Windows .NET Server include an additional type of group (universal groups) and have a more flexible architecture for deployment, these mnemonics do not have as much significance for these versions of Windows as they did for Windows NT.

See Also: *account, group, permissions*

AH

Stands for Authentication Header, a protocol in the IPSec suite of protocols that handles authentication of Internet Protocol (IP) traffic.

See: *Authentication Header (AH)*

AIM

Stands for AOL Instant Messenger, a popular instant messaging service from America Online (AOL).

See: *AOL Instant Messenger (AIM)*

AIr

Stands for Advanced Infrared, a wireless networking technology for high-speed, low-cost infrared (IR) networking.

See: *Advanced Infrared (AIr)*

Air Interface

Generally, the lower levels of the protocol stack in a wireless communications system.

Overview

Different wireless communications systems use different types of air interfaces, but these all generally map well with the Open Systems Interconnection (OSI) model for networking. For example, Personal Communications Service (PCS) cellular service uses a three-level air interface:

- **Physical Layer:** This bottom layer of the interface is responsible for encoding and framing data, interleaving and slotting it into available time slots, and mapping these slots onto a channel for transmission as a burst.
- **Data-link Layer:** This middle layer is responsible for packaging the data, transporting the message to its destination, and performing error correction.
- **Message Layer:** This top layer handles messages transmitted over the air and formats the messages as data elements that are then packaged and transported by the lower levels.

In addition to these three levels, typical wireless messaging systems include higher levels for control purposes, metering, and providing additional services.

See Also: *cellular communications, wireless networking*

AIT

Stands for Advanced Intelligent Tape, a tape backup technology developed by Sony Corporation.

See: *Advanced Intelligent Tape (AIT)*

AIX

A version of the UNIX operating system developed by IBM.

Overview

AIX runs on IBM RS/6000 and systems based on IBM PowerPC processors (a version for Intel Corporation's 64-bit IA-64 processor is also planned). AIX, which stands for Advanced Interactive Executive, was originally based on release 2 of the Unix System V operating system and is compliant with the Unix98 standard. The current release AIX 4.3 is a solid platform for e-business and supports IBM's VisualAge, Java, and C++ developer tools.

Project Monterey is an initiative from IBM for the development of the next version of AIX called AIX 5L. Combining the time-tested reliability of AIX with UnixWare, DYNIX/ptx, and Linux support, AIX 5L promises to make AIX a major contender for high-end 64-bit computing using Intel's 64-bit IA-64 platform.

For More Information

Find out more about AIX at *http://www-1.ibm.com/servers/aix*.

See Also: *UNIX*

Alerter service

A Microsoft Windows 2000, Windows XP, and Windows .NET Server service responsible for sending administrative alerts to users and computers.

Overview

The Alerter service generates an alert when potentially dangerous conditions occur, such as when disk space is running out. You can configure which users or computers receive these alerts by using Server Manager (or by using the Server utility in Control Panel). Pop-up alert messages appear if the administrator is logged on or is at the appropriate computer when the alert occurs. The administrator can then consult the system log for information about what caused the alert.

Notes

The Server service must be running for the Alerter service to function. The Messenger service should also be running on both the sending and receiving computers. Also, restart the Server service and Alerter service on the computer after modifying the list of users and computers to whom alert conditions on that computer should be sent.

See Also: *service*

alias

A form of nickname that identifies a user for e-mail purposes.

Overview

An alias is usually a shortened form of the user's full name, such as the alias JSmith or JeffS for user Jeff Smith.

Aliases are a convenient way of identifying users and form the user-specific portion of an e-mail address. For example, if Jeff Smith belongs to a company whose Domain Name System (DNS) domain on the Internet is northwind.microsoft.com, his e-mail address would be either JSmith@northwind.microsoft.com or, instead, JeffS@northwind.microsoft.com, depending on which alias is selected.

Notes

What if both a Jeff Smith and a Jeff Smythe work at the same company? If JeffS is the alias for the first user, you could use JeffS2 for the second. It all depends on your choice of naming convention.

See Also: *e-mail*

Always On/Dynamic ISDN (AO/DI)

A modified form of Integrated Services Digital Network (ISDN) that supports transmission of data over the ISDN control channel (D channel).

Overview

The ISDN D-channel is always active and is normally used to carry the control information for setting up, managing, and tearing down ISDN B channel connections. Always On/Dynamic ISDN (AO/DI) takes advantages of this by reserving a portion of the D channel's bandwidth for transmitting X.25 packets. This is done by encapsulating X.25 packets within Point-to-Point Protocol (PPP) and allows an X.25 Packet Assembler/Disassembler (PAD) at the subscriber's premises to transmit and receive information through ISDN to the carrier's X.25 network.

The ISDN D channel has a total bandwidth of 16 kilobits per second (Kbps). This is more than enough for carrying ISDN control signals, so in AO/DI 9.6 kbps of this bandwidth is used for X.25 signaling. When an X.25 packet is sent from the customer premises over an ISDN D channel to the telco's central office (CO), a packet handler positioned in front of the carrier's ISDN switch strips off the X.25 packet and relays it to the carrier's X.25 network.

Uses

Although 9.6 Kbps seems like a small amount of useful bandwidth, one use for AO/DI is to provide always-on Internet access to subscribers who can utilize this small bandwidth for practical purposes, such as periodically polling fire alarm sensors over the Internet from a central monitoring station or remotely monitoring electricity and gas meters. From the telco's point of view, the main advantage of AO/DI is to reduce the usage of ISDN B channels, freeing up more circuits and saving costs.

Despite its promised usefulness, real-world deployments of AO/DI are few, primarily due to the communications industry's current focus on developing high-speed broadband access solutions for home and business.

See Also: *Integrated Services Digital Network (ISDN)*

Alpha platform

A computer hardware platform whose processor is based on the Alpha Reduced Instruction Set Computing (RISC) microprocessor architecture originally developed by Digital Equipment Corporation (DEC).

Overview

Alpha-based systems, which are used primarily for high-performance servers and workstations, can run operating systems such as Microsoft Windows NT, Digital UNIX, and OpenVMS. For example, the Alpha 21164 processor was specifically designed for running Windows NT desktop applications and includes a new set of motion video instructions (MVI) for high-performance multimedia applications. The superscalar design of this processor integrates a 16-kilobyte (KB) instruction cache, an 8-KB data cache, and a 96-KB second-level cache and can issue four instructions for each clock cycle. It uses 0.35-micron complementary metal-oxide semiconductor (CMOS)–integrated circuit technology and a fully pipelined 64-bit RISC architecture to provide the highest performance for Windows NT systems. The processor is housed in a 499-pin ceramic package and generates 28 watts of heat and is designed to work with the AlphaPC 164LX motherboard. The latest Alpha chips run at speeds of 833 megahertz (MHz) and higher.

Notes

Windows 2000 does not support the Alpha platform.

For More Information

Visit the Alpha Server home at *www.compaq.com/alphaserver*.

See Also: *x86 platform*

American National Standards Institute (ANSI)

A U.S. standards organization that facilitates and governs the development of standards in many areas, including computing and communication.

Overview

The American National Standards Institute (ANSI) was founded as a private sector voluntary standards association in 1918. It is a nonprofit private association with almost 1,400 member organizations.

ANSI does not create standards itself but oversees groups and organizations in the development of standards. ANSI is a member organization of the International Organization for Standardization (ISO) and provides the charter for the Institute of Electrical and Electronics Engineers (IEEE).

Standards that are approved by ANSI are called ANSI Standards. Examples include the ANSI C/C++ programming language standards, ANSI-89 SQL standards, and ANSI character set. ANSI has approved more than 13,000 standards to date.

Notes

ANSI is also used to refer to the ANSI character set.

For More Information

Visit the American National Standards Institute at *www.ansi.org.*

American Registry for Internet Numbers (ARIN)

A nonprofit organization that administers the registration and allocation of numbers relating to the operation of the Internet in North and South America.

Overview

The American Registry for Internet Numbers (ARIN) was formed in 1997 through the joint efforts of the Internet Assigned Numbers Authority (IANA), the Internet Engineering Task Force (IETF), the National Science Foundation (NFS), and other organizations. ARIN exists primarily to provide a number of critical functions related to the operation of the Internet:

- It oversees the registration and administration of Internet Protocol (IP) addresses. This is probably ARIN's most important function, which it took over from IANA when it was formed in 1997. ARIN works diligently to conserve the pool of available IP addresses and determines the size and scope of blocks of IP addresses granted in response to requests. The careful maintenance of the IP address system is critical to the Internet's health, and ARIN works hard to ensure that the routing tables maintained on the core routers of the Internet remain manageable in size. Internet service providers (ISPs) can contact ARIN to purchase blocks of IP addresses that they can then assign to their customers—ARIN does not supply individual IP addresses directly to individuals (the smallest block available from ARIN is 4096 hosts in scope).
- It is responsible for registration and management of autonomous system numbers (ASNs) to public and enterprise networks.
- It maintains a central routing registry to which network operators can submit and obtain information relating to routing across the Internet.
- It maintains the IN-ADDR-ARPA and IP6.INT inverse mappings for Domain Name System (DNS).

ARIN is actually only one of three Regional Internet Registries (RIRs) that handle the above functions for different parts of the global Internet. ARIN's areas of responsibility are the regions of North and South America, the Caribbean, and sub-Saharan Africa. The other two RIRs are

- **Reseaux IP Europeans (RIPE):** Responsible for Europe, the Middle East, and other parts of Africa.
- **Asia Pacific Network Information Center (APNIC):** Responsible for the Asia/Pacific region.

Notes

ARIN does not handle the registration of domain names but instead manages the underlying IP addresses for which domain names are friendly handles. There are also two delegated name registries within ARIN: the Brazilian Registry (RNP) and the Mexican Registry (NIC-Mexico).

For More Information

You can find ARIN at *www.arin.net.*

See Also: *autonomous system number (ASN), Internet, IP address*

AMP

Stands for asymmetric multiprocessing, a processing architecture in which processes are specifically assigned to different processors.

See: *asymmetric multiprocessing (AMP)*

AMPS

Stands for Advanced Mobile Phone Service, the original first-generation (1G) analog cellular phone service. Still used in some parts of North and South America.

See: *Advanced Mobile Phone Service (AMPS)*

analog

Transmission of electrical signals that vary smoothly with time.

See: *analog transmission*

analog modem

A type of modem used for asynchronous transmission of information over Plain Old Telephone Service (POTS) telephone lines.

Overview

The word *modem* stands for modulator/demodulator, which refers to the fact that modems convert digital transmission signals to analog signals and vice versa. An analog modem performs this modulation, but a digital modem does not perform modulation and simply transports digital signals as they are. In effect the phrase "digital modem" is a misnomer because no modulation occurs, and "analog modem" can simply be termed "modem" instead.

To transmit computer data over a telephone channel, a modem modulates the incoming digital signal received from the computer into an analog signal whose frequency lies within the carrying range of analog phone lines (between 300 hertz [Hz] and 3.3 kilohertz [kHz]). To accomplish this, modulation of the digital signal from the computer with an analog carrier signal is performed. The resulting modulated signal is then transmitted into the local loop and carried over the Public Switched Telephone Network (PSTN) until it arrives at its destination station, where a similar modem demodulates the modulated analog signal into a stream of digital data that the remote computer can understand.

However, this basic modulation/demodulation process over POTS lines can transmit data only at speeds of about 1,200 bits per second (bps). To achieve the much higher speeds of today's modems, advanced technologies must be applied, including echo canceling, training, data compression, and special modulation algorithms such as quadrature amplitude modulation (QAM). Using these technologies, modem speeds of 56 kilobits per second (Kbps) are now common.

Bell Laboratories in the 1960s and 1970s originally formulated modem standards, but after the breakup of Bell Telephone, the task of developing modem standards was taken over by the International Telegraph and Telephone Consultative Committee (CCITT), which is now called the International Telecommunication Union (ITU). According to ITU specifications, modem standards are classified by a series of specifications known as the V series.

See Also: *modem, modulation, V-series*

analog-to-digital converter (ADC)

Any device used for changing analog signals into digital transmission.

Overview

An example of analog-to-digital conversion is recording someone singing onto a CD. The pressure waves in the air produced by the vibration of the person's vocal cords are analog in form and continually vary in strength within a certain range of values. The recording equipment samples this continually varying information at discrete time intervals and converts it to digital form.

Analog-to-digital converters (ADCs) are used in industry to convert environmental variables (temperature, pressure, density, speed, and so on) that vary continuously over time to digital information, which can then be analyzed using computer programs. ADCs are used in analog modems to convert digital signals into audio and vice versa.

See Also: *analog, digital*

analog transmission

Transmission of electrical signals that vary smoothly with time.

Overview

An analog signal can take on any value in a specified range of values as shown in the diagram. A simple example is alternating current (AC), which continually varies between about +110 volts and -110 volts in a sine wave fashion 60 times per second. A more complex example of an analog signal is the time-varying electrical voltage generated when a person speaks into a dynamic microphone or telephone. Analog signals such as telephone speech contain a wealth of detail but are not readily accessible to computers unless they are converted to digital form using a device such as an analog-to-digital converter (ADC). Old-fashioned vinyl records store sound information in the form of a continuously varying analog groove, but modern musical CDs store their information in digital form. Some people claim they can tell the difference between an analog and a digital recording and generally agree that the analog recording sounds “warmer.”



Analog transmission. *Example of an analog transmission.*

Analog signals are usually specified as a continuously varying voltage over time and can be displayed on a device known as an oscilloscope. The maximum voltage displacement of a periodic (repeating) analog signal is called its amplitude, and the shortest distance between crests of a periodic analog wave is called its wavelength.

See Also: *digital transmission*

anchor

In Hypertext Markup Language (HTML), a source or target of a hypertext link.

Overview

Anchors are the key feature of HTML that enables hypertext (linked documents) to be constructed. Without anchor tags, Web pages could not be linked together.

An anchor can be either text or a graphic and is specified using the tag formation <A>…</A>. There are two types of anchor tag. The first type creates a hypertext link that refers to a document. For example, the following HTML element will display the word “contents” as a hyperlink. If the user clicks on the link, the browser will load the contents.htm page specified in this tag:

```
<A HREF="http://www.northwind.microsoft.com /
contents.htm">Contents</A>
```

The second type of anchor tag marks a portion of text as a destination for a hyperlink. You can place the following element at the end of the contents.htm page:

```
<A NAME="bottom">This is the end of the page</A>
```

To load the contents.htm page and jump directly to the bottom of the page, the user needs to click a hyperlink such as this one:

```
<A HREF="http://www.northwind.microsoft.com /
contents.htm#bottom">Contents</A>
```

See Also: *Hypertext Markup Language (HTML)*

announcement

A feature that enables Windows Media Player to receive streaming multimedia information.

Overview

An announcement’s function depends on whether the transmission method is multicasting or unicasting. If the transmission method is multicasting, announcements enable Windows Media Player to retrieve the channel file containing channel information. If the transmission method is unicasting, announcements supply the client with information on how to connect to the Windows Media Server.

Announcements, which are used only with Advanced Streaming Format (ASF) transmissions, are text files that have the extension .asx. Once created, an announcement can be distributed to clients by several means: over the Web, through e-mail, or on a network share.

Announcement Manager

A service in Microsoft Windows 98 that automatically runs in the background when you have WebTV for Windows installed on your computer.

Overview

Announcement Manager receives broadcast announcements from TV networks or Web sites that notify your computer about the time and address of the broadcast and which software applications must be running to receive the broadcast. When Announcement Manager receives an announcement, it directs it to the broadcast filters you have configured for your WebTV service. The broadcast filters then determine whether to ignore the broadcast or schedule its reception.

Announcement Manager is part of the Microsoft Broadcast Architecture, a specification for receiving Web information broadcast to your computer through a TV tuner interface.

See Also: *Windows 98*

anonymous access

An authentication scheme in which the user's identity is not verified.

Overview

Anonymous access is one of several authentication protocols supported by Microsoft Internet Information Services (IIS) and is strictly speaking not an authentication scheme at all because the users' credentials are not requested and, if supplied, are ignored. Anonymous access is typically used to allow anonymous users (that is, everyone) to gain access to public content hosted on a Web server. Anonymous access is typically used on low-security public Web sites where the identity of the person visiting the site is not important. By enabling anonymous access to the site, distrusted users from the Internet can access content on the site.

Anonymous access on IIS works by making use of a default anonymous user account called IUSR_machinename. This account is a local user account that iscreated during Setup and is used exclusively to authenticate anonymous users and grant them access to resources on the machine. The IUSR_machinename account requires the Log On Locally system right in order to grant anonymous access to machine resources.

See Also: *authentication protocol*

anonymous user

Any user who attempts to access network resources without providing a username or password.

Overview

Some applications such as Microsoft Internet Information Services (IIS) can be configured to allow anonymous users to access their resources. This allows distrusted users from unsecure networks such as the Internet to access data that ismade available for the public at large.

Access to network resources by anonymous users can be controlled by assigning permissions to a special anonymous user account IUSR_ComputerName. Windows 2000, Windows XP, and Windows .NET Server then provide anonymous users access to resources by impersonating the user utilizing the anonymous user account.

See Also: *anonymous access*

ANSI

Stands for American National Standards Institute, a U.S. standards organization that facilitates and governs the development of standards in many areas, including computing and communication.

See: *American National Standards Institute (ANSI)*

ANSI C/C++

A standard published by the American National Standards Institute (ANSI) for writing C and C++ code.

Overview

Programs written in ANSI C or ANSI C++ are portable to a large number of computing platforms. Most commercial C/C++ programming tools, such as Microsoft Visual C++, contain extensions to ANSI C/C++ that simplify common programming tasks considerably but restrict the portability of the resulting code to different platforms.

You can use Visual C++ to write strict ANSI C/C++ code by following these guidelines:

- Call Win32 application programming interfaces (APIs) directly in your program instead of using the Microsoft Foundation Classes (MFC) libraries.
- Disable the Microsoft extensions to C++ by running Visual C++ using the /Za command-line option.
- Use the isostream and standard template libraries from the ANSI Standard C++ library and the appropriate #include statements in your code.

See Also: *American National Standards Institute (ANSI)*

ANSI character set

An eight-bit character set developed by used by the American National Standards Institute (ANSI).

Overview

The ANSI character set uses 256 characters (numbered 0 through 255). The American Standard Code for Information Exchange (ASCII) character set is a subset of the ANSI character set with characters numbered 32 through 126, each representing a displayable character.

ANSI uses a single byte to represent a character, in contrast to the Unicode standard supported by Microsoft Windows NT, which uses 2 bytes to represent a character. For example, the ANSI character “A” would be represented in hexadecimal notation by the single byte 41h. ANSI’s 256-character limit supports only a few international characters, such as accented French and German vowels, but the Unicode’s 65,536-character limit supports virtually every alphabet in the world. For example, the Unicode character “A” would be represented in hexadecimal notation by the 2-byte string {41h, 00h}.

The following table shows which Windows environments support ANSI and Unicode for character encoding.

Windows Environments and Character Encoding

ANSI	*Unicode*
16-bit Windows object libraries	32-bit Windows object libraries
Windows 95 and Windows 98 API	Windows NT and Windows 2000 API
	Automation in Windows 95, Windows 98, Windows NT, Windows 2000, Windows XP, and Windows .NET Server

Notes

Some ANSI character codes cannot be displayed by Microsoft Windows applications and are generally displayed as solid blocks in the application interface.

See Also: *American National Standards Institute (ANSI), ASCII*

answer file

A text file that can be used to perform an unattended installation of Microsoft Windows 2000.

Overview

In the answer file you specify in advance the answers to the user prompts that occur during a normal installation. These prompts can include specifications such as what keyboard layout to use, whether the computer should join a domain or belong to a workgroup, what network protocols should be installed, and so on. The answer file is invoked using the /u switch when running the Winnt or Winnt32 setup utility. Answer files can be customized for individual machines by using Uniqueness Database Files (UDFs). The UDFs can be used to specify computer-specific parameters such as the computer name.

A sample answer file Unattend.txt is located in the \I386 folder on the source CD. You can customize this file using Notepad or another text editor to suit your needs.

See Also: *Windows 2000*

antenna

A device used to enhance the transmission and reception of radio signals.

Overview

A full treatment of antenna theory is beyond the scope of this book, and antenna considerations have only become an issue for local area network (LAN) administrators with the recent proliferation of wireless LANs (WLANs), wireless bridges, and wireless cellular data transmission technologies. Just a few issues and developments are considered here.

The first notebook computer to incorporate a built-in factory-installed antenna for wireless networking was the iBook from Apple Computer. The iBook uses the AirPort wireless networking technology, and although the antenna is included, an AirPort add-on card must be purchased to connect the machine to a WLAN. Other vendors such as Dell Computer Corporation have quickly followed Apple's lead in this area. PC board mountable antennae are often flat dielectrically loaded omnidirectional antenna and require no external tuning components.

For a wireless network to be effective, the base station also needs a suitable antenna. The range of antennae available for base stations is large, and the latest ones support multiband operation for the 900-megahertz (MHz) band, 2.4-gigahertz (GHz) Industrial, Scientific, and Medical (ISM) band, and 5-GHz UNI band.

A primary issue regarding antennas for wireless devices is placement. For transmission stations, this means placing antennas as high as possible—on the roof, for example—to ensure the widest possible area of coverage. For end stations, obstacles such as concrete walls and iron girders within buildings can absorb, scatter, and attenuate signals so that practical networking becomes difficult or impossible. To overcome this, more powerful transmissions can be used, but the strength of end-station transmissions are limited for health reasons.

Another issue regards whether unidirectional or omnidirectional antennas are used. For wireless bridges connecting networks in different buildings, unidirectional antennas are used and must be aligned properly with no line-of-sight obstructions. Mobile devices such as laptops, Personal Digital Assistants (PDAs), and cell phones require omnidirectional antennas to function properly, particularly when roaming.

See Also: *wireless networking*

Anycast

A network service for delivering datagrams to any one server belonging to a group of servers on a network.

Overview

Anycast was first proposed in RFC 1546 as a way to direct a network request to the closest (in the network sense of hops) server in a set of mirrored servers for servicing the request. Because fewest hops may not necessarily mean the server that responds best (due to latency, throughput, and host load), other Anycast-related initiatives have arisen in the last few years. These initiatives include Application-Aware Anycast, Global IP-Anycast, Simple Internet Protocol Plus, and others.

AO/DI

Stands for Always On/Dynamic ISDN, a modified form of Integrated Services Digital Network (ISDN) that supports transmission of data over the ISDN control channel (D channel).

See: *Always On/Dynamic ISDN (AO/DI)*

AOL Instant Messenger (AIM)

A popular instant messaging service from America Online (AOL).

Overview

AOL Instant Messenger (AIM) is a free instant messaging service that boasts more than 84 million users worldwide. The service allows users to send messages instantly to other users online, receive alerts and bulletins, have online chat conversations, receive news and other information, share files, and perform other useful activities.

The current version of client software is AIM 4.3, which supports additional features including participating in online games and accessing your buddy list from any computer. AIM is available for various platforms including Microsoft Windows and Windows CE, Mac OS, Linux, and PalmOS. AIM operates using AOL's proprietary AIM Protocol, and AIM competes with other popular Instant Messaging (IM) systems including Microsoft Corporation's MSN Messenger.

For More Information

You can download the current version of AIM from *www.aol.com/aim.*

MSN Messenger can be found at *messenger.msn.com.*

See Also: *instant messaging (IM)*

AP

Stands for access point, a device connected to a local area network (LAN) that enables remote wireless stations to communicate with the LAN.

See: *access point (AP)*

Apache

Short for Apache Web server, an open-source Hypertext Transfer Protocol (HTTP) server whose code was developed and is maintained by the Apache Software Foundation.

Overview

Apache started out as a patch for the original National Center for Supercomputing Applications (NCSA) httpd server—hence the new server was "a patchy" server. The NCSA httpd server was stuck at version 1.3 and had some security issues, and so a group of people took the 1.3 code, which was in the public domain, and patched it. The group later rewrote most of the base code from scratch in order to support external modules written in C language.

One of the Apache platform's strengths is its modular design, which consists of a central Apache kernel interacting with various code modules that provide additional functionality. This architecture speeds the development cycle and makes it easy for third-party developers to build custom modules to meet their needs and compile them into the Apache source.

Security is a top priority for administrators who run Web servers, and Apache includes support for a number of advanced security features through various security modules:

- **Access control:** The default security setting for Apache is "deny all," after which selective access can be provided to specific users through the Access.conf file.
- **Authentication:** Apache supports basic authentication using a number of password file formats, starting with /bin/htpasswd. Modules are also available for host-based authentication where access is granted based on Internet Protocol (IP) address and anonymous access using a user's e-mail address as a password.
- **Encryption:** Support for Secure Sockets Layer (SSL) encryption in Apache is provided by freeware packages such as Apache-SSL and mod_ssl, and by commercial packages such as Stronghold from C2Net Software.
- **Logging:** Apache includes support for comprehensive logging of server events. Logs are kept in two files, access_log and error_log.

Apache is one of the most popular Web servers in use, with an estimated more than 6 million Web sites deployed on it. Some market watchers estimate that about 60 percent of all Web servers are running Apache. Apache is widely deployed wherever UNIX is found, including universities and large enterprise networks, and is available for more than a dozen different operating system platforms, including Microsoft Windows.

Notes

The most common vulnerability of Apache servers is running the core process using root privileges. This makes the server vulnerable to what is called a "root exploit," which can allow a malicious remote user to run Common Gateway Interface (CGI) scripts using root privileges. The way to avoid this is to include the following lines in the Httpd.conf configuration file:

```
user  nobody

group nobody
```

For More Information

The Apache Software Foundation can be found at *www.apache.org.*

A good source for timely new and information on the Apache platform is Apache Week (*www.apacheweek.com*).

For information on the Apache conference, see *www.apachecon.org*.

See Also: *open source, UNIX, Web server*

Apache Software Foundation

An open-source community guiding the development of the Apache Web server and other open-source tools and programs.

Overview

The Apache Software Foundation, formerly the Apache Group, is a nonprofit organization that provides legal, organizational, and financial backing toward the development of open-source software projects that use Apache Web server software. Some of the projects the foundation is working on include

- Apache Server
- Apache XML Project-Apache
- Jakarta
- Java-Apache
- mod_perl
- PHP
- Apache Tcl

See Also: *Apache, Apache XML Project, open source*

Apache XML Project

An initiative of the Apache Software Foundation to create open-source tools for developing Extensible Markup Language (XML) business solutions.

Overview

The Apache XML Project is an initiative with three goals:

- Developing tools for creating commercial-class XML-based business solutions that are standards-compliant and follow the open source model.
- Provide helpful feedback to the World Wide Web Consortium (W3C) and other bodies involved in the development of XML standards.
- Provide XML resources for other initiatives of the Apache Software Foundation.

Several commercial companies have contributed technology to this initiative, including Sun Microsystems, IBM, and Lotus Software (formerly Lotus Development Corporation, now part of IBM), and other contributes have come from the Open Source community at large.

Some of the subprojects within this initiative include

- **Cocoon:** XML-based Web publishing using Java.
- **FOP:** Extensible Stylesheet Language (XSL)–formatting objects using Java.
- **Xalan:** XSL Transformation (XSLT) stylesheet processing using Java and C++.
- **Xang:** Dynamic server pages using Java.
- **Xerces:** XML parsing using Java, C++, and Perl.

For More Information

Visit the site of the Apache Software Foundation (*www.apache.org*).

See Also: *Apache Software Foundation, open source*

API

Stands for application programming interface, any collection of programming routines and functions that an application can use to access low-level machine services.

See: *application programming interface (API)*

APIPA

Stands for Automatic Private IP Addressing, a feature of Microsoft Windows 2000, Windows XP, and Windows .NET Server that enables machines to be automatically assigned Internet Protocol (IP) addresses without the use of Dynamic Host Configuration Protocol (DHCP).

See: *Automatic Private IP Addressing (APIPA)*

APM (Advanced Power Management)

Stands for Advanced Power Management, a legacy specification for power management of computer hardware.

See: *Advanced Power Management (APM)*

APM (Application Performance Management)

Stands for Application Performance Management, a set of technologies, business processes, and services for guaranteeing what subscribers experience from service providers.

See: *Application Performance Management (APM)*

APNIC

Stands for Asia Pacific Network Information Center, the counterpart of American Registry for Internet Numbers (ARIN) and the agency responsible for administering the registration and allocation of Internet numbers for the Asia/Pacific region.

See: *Asia Pacific Network Information Center (APNIC)*

APPC

Stands for Advanced Program-to-Program Communications protocol, a set of protocols developed by IBM that enables transactional programs to communicate with each other.

See: *Advanced Program-to-Program Communications (APPC) protocol*

APPC File Transfer Protocol (AFTP)

A protocol that provides file transfer capabilities for the Advanced Program-to-Program Communications (APPC).

Overview

APPC File Transfer Protocol (AFTP) servers are the APPC equivalent of File Transfer Protocol (FTP) servers in the Transmission Control Protocol/Internet Protocol (TCP/IP) world. Microsoft SNA Server can be used to establish AFTP connections to AS/400 or mainframe computers running the APPC applications suite. Users can then utilize standard FTP client software to transfer files between the SNA server and the AS/400 or mainframe host. The optional AFTP service must first be installed on the SNA server. The installation can be configured so that the SNA server performs the function of an FTP-to-AFTP gateway. This will enable standard FTP clients to transfer files to and from the mainframe host.

See Also: *Advanced Program-to-Program Communications (APPC) protocol*

Apple Open Transport

An Apple networking technology for transport-independent networking that ispart of the networking and communication subsystem of the Apple Macintosh operating system.

Overview

Apple Open Transport is designed to make it easy to set up and configure networking on the Macintosh computer and to increase the performance of file, print, and other networking services on a MacOS server. Open Transport provides a consistent interface for configuring network services across supported protocols and a uniform set of application programming interfaces (APIs) for accessing networking and communication services on the Macintosh.

Open Transport enables protocols to be loaded and unloaded on demand, provides a networking naming scheme plus consistent network services over the Transmission Control Protocol/Internet Protocol (TCP/IP) and AppleTalk protocols, and includes support for TCP/IP services such as Dynamic Host Configuration Protocol (DHCP) and Domain Name System (DNS). Open Transport also provides consistent API access to serial communication on the Macintosh, while third-party support is available for Point-to-Point Protocol (PPP), Network Control Protocol over Internetwork Packet Exchange (NCP/IPX), Server Message Block over Transmission Control Protocol (SMB/TCP), NetBIOS, DECnet, LAT, and X.25.

The Open Transport/AppleTalk protocol stack supports both the dynamic self-addressing of traditional AppleTalk clients and newer manually assigned static addressing. The Open Transport/TCP/IP protocol stack supports DHCP, bootstrap protocol (BOOTP), both local hosts files and DNS, Internet Protocol (IP) multicasting, both Ethernet Version 2 and Institute of Electrical and Electronics Engineers (IEEE) 802.3 framing, TCP wildcard source port assignments, Point-to-Point Protocol (PPP) connectivity, IP multihoming, and almost unlimited simultaneous TCP connections (limited only by installed memory and processor power).

Notes

An Apple Macintosh running Open Transport/TCP/IP can function as a DHCP client to a Microsoft Windows NT server running as a DHCP server, but not as a Windows Internet Naming Service (WINS) client.

See Also: *AppleTalk*

AppleShare

The file sharing protocol for AppleTalk networks.

Overview

AppleShare provides the following functions:

- Enables sharing of volumes, folders, and printers
- Provides auditing information on which resources have been accessed
- Supports password-based control of access to shared resources

Notes

By installing Services for Macintosh on a Microsoft Windows 2000 server, the Windows 2000 server can emulate an AppleShare server so that Macintosh clients can access shared resources on the Windows 2000 server.

See Also: *AppleTalk*

AppleShare IP

An Apple networking technology that supports native Transmission Control Protocol/Internet Protocol (TCP/IP) on the Apple Macintosh platform.

Overview

AppleShare IP provides Web, file, print, and e-mail services for departmental and workgroup- level environments. The latest version, AppleShare IP v6.1, features a single integrated administration console for local server management, remote administration using a standard Web browser, IP address filtering, Sherlock searching support, multihosting, Simple Mail Transfer Protocol (SMTP) and point of presence (POP) protocol support, shared Internet Mail Access Protocol (IMAP) folders, Domain Name System (DNS) services, and full compatibility with MacOS 8.5 and higher.

AppleShare IP client software must be installed on Macintosh client machines to enable them to access AppleShare IP services on a server over the network. AppleShare IP supports both Server Message Block (SMB) and File Transfer Protocol (FTP) protocols in addition to AppleShare file sharing, and is compatible with both Macintosh and Microsoft Windows clients.

See Also: *AppleTalk*

applet

A program written using the Java programming language that can be accessed through a Web page and downloaded to the client machine, where it is run within the Web browser window.

Overview

Java applets can be used to add dynamic functionality to static Web pages provided users view these pages with a Java-enabled Web browser.

When an applet is created, its Java statements are compiled into an intermediate pseudo- machine-code language called a bytecode. The bytecode file is stored as a class file on a Web server such as Microsoft Internet Information Services (IIS), and a Web page can reference the class file using an <APPLET> tag. When a Web browser requests the page and encounters the <APPLET> tag, the bytecode in the class file is executed in a Java virtual machine on the browser.

See Also: *Java*

AppleTalk

The original networking protocol for Apple Macintosh networks.

Overview

AppleTalk is a suite of networking protocols that work together to provide file and print sharing services to Macintosh networks. AppleTalk enables users to share folders and printers for access by other network users. AppleTalk is a legacy technology that has been largely replaced by Apple Open Transport, which supports AppleTalk, Transmission Control Protocol/Internet Protocol (TCP/IP), and other popular network protocols.

Architecture

AppleTalk is a workgroup-level networking technology that supports up to 254 network nodes per physical network. AppleTalk can run on top of the legacy LocalTalk data-link protocol, which was built into the Macintosh RS-449/RS-422 serial interface. In the more recent AppleTalk Phase II, the data-link protocols supported include EtherTalk, TokenTalk, and FDDITalk for connectivity with Ethernet, Token Ring, and Fiber Distributed Data Interface (FDDI) networks, respectively.

Addresses of machines on AppleTalk networks are randomly self-assigned when the machine is first attached to the network and then broadcast to ensure they are not already being used. This dynamic addressing feature is based on the AppleTalk Address Resolution Protocol (AARP).

AppleTalk internetworks are logically partitioned into zones whose main function is to make network resources easier for users to access. A *zone* is a logical representation of AppleTalk network nodes that can span multiple physical networks. The mapping between zones and network numbers is maintained by the Zone Information Protocol (ZIP), which creates Zone Information Tables (ZITs) that are stored on AppleTalk routers.



OSI Layer	Protocols
Application	AppleShare
Presentation	AppleTalk Filing Protocol (AFP)
Session	Zone Information Protocol (ZIP) AppleTalk Session Protocol (ASP) AppleTalk Data Stream Protocol (ADSP) Password Authentication Protocol (PAP)
Transport	AppleTalk Echo Protocol (AEP) Name Binding Protocol (NBP) AppleTalk Transaction Protocol (ATP) Routing Table Maintenance Protocol (RTMP)
Network	Datagram Delivery Protocol (DDP)
Data Link	LocalTalk EtherTalk TokenTalk FDDITalk
Physical	Physical transmission media (coax, twisted-pair, fiber-optic)

AppleTalk. *The AppleTalk protocol suite.*

appliance

A general term referring to any network-capable or Internet-capable computing device that can be deployed with plug-and-play ease.

Overview

The market for appliances ranges from home users to the largest enterprise. At the small end of the scale are Internet access appliances that allow users to connect home networks to the Internet using dial-up, digital subscriber line (DSL), or cable modem technologies. Many of these Internet access appliances include advanced features such as built-in firewalls, Web-based management consoles, built-in hubs, and so on.

At the larger end are appliances built for large companies and for service providers, for example:

- **Server appliances:** These include Web server appliances running Apache/Linux or IIS/Windows 2000 and file server appliances such as Cobalt's Qube and Compaq NeoServer. Server appliances are typically 1U or 2U rack-mountable devices and can often be set up in minutes or even seconds. These appliance servers fill specific needs for business, and their market is growing rapidly.
- **Storage appliances:** An example here is Novell's Network Attached Storage (NAS), a rack-mountable appliance that provides up to 1 terabyte of storage, supports all major server platforms, and has integrated Novell Directory Services (NDS) eDirectory and ZENworks management applications.

Application Center

One of Microsoft Corporation's new .NET Enterprise Servers, Microsoft Application Center is used for deploying and managing Web applications and Web services.

Overview

Application Center is a platform for deploying and managing high-availability Web applications and Web services. Application Center 2000 is built on the Microsoft Windows 2000 operating system platform and makes managing of clusters of application servers as easy as managing a single server.

Application Center provides simplified application management by allowing administrators to create logical groupings of application components and configuration information. These groupings can be easily managed, regardless of how they are deployed across the cluster, and changes made to one server in a cluster can be automatically applied to other servers. Migration and upgrading of applications can be automated, which simplifies the development cycle as applications are moved from test bed to production phase. Application Center is thus ideal for simplifying the staging and deployment of complex Web-based e-business applications.

Application Center provides built-in support for software scaling to increase the capacity of applications as the business need arises. This is possible through the underlying reliance on clustering technologies in which a group of servers is managed as a single resource, and Application Center simplifies and accelerates the deployment of clusters over traditional clustered server platforms. Application Center also supports load-balancing technologies such as Network Load Balancing (NLB), Component Load Balancing (CLB), and third-party load balancing solutions. With Application Center, your Web applications have no single point-of-failure and consequently high availability and reliability.

Application Center provides the enterprise with mission-critical availability and allows any server in a cluster to be brought down without affecting the integrity or operation of the applications running on the cluster. Application Center includes tools for monitoring cluster health and supports browser-based remote administration. Automated event response allows corrective action to be taken automatically when a component or server fails, without the need for human intervention.

For More Information

You can find out more about Application Center at *www.microsoft.com/applicationcenter.*

See Also: *.NET Enterprise Servers, Web server*

application layer

The top layer (Layer 7) of the Open Systems Interconnection (OSI) reference model for networking.

Overview

The application layer is the layer in which network-aware, user-controlled software is implemented—for example, e-mail, file transfer utilities, and terminal access applications. The application layer represents the window between the user and the network and translates between the user running the application and the presentation layer (Layer 6). In the OSI model the application layer is also responsible for integrating the functionality of different applications together and determining the availability of resources.

Examples of protocols that operate at the application layer include File Transfer Protocol (FTP), Hypertext Transfer Protocol (HTTP), telnet, and similar protocols that can be implemented as utilities the user can interface with.

Notes

Originally the OSI model consisted of two kinds of application layer services with their related protocols:

- **Common Application Service Elements (CASE):** These enable users to initiate or terminate peer (Layer 7 to Layer 7) connections between different machines on the network, enable reliable transfer of information between them, initiate remote operations, and support recovery from failure and rollback steps.
- **Specific Application Service Elements (SASE):** These can include file transfer, message handling, terminal access, and other services that make use of the CASE elements and protocols.

These terms have largely been replaced with the term Application Service Elements (ASE) to describe the elements of the application layer. Note also that in most real-world networking, such as Transmission Control Protocol/Internet Protocol (TCP/IP) networking, these application layer services have no meaning.

See Also: *Open Systems Interconnection (OSI) reference model*

application layer proxy

Any service or server that acts as a proxy for client computer requests at the application's protocols.

Overview

Application layer proxies provide security by hiding internal network addresses from the outside world. An example of an application layer proxy is illustrated in Microsoft Proxy Server. Here the Web Proxy Service is an application layer proxy for the Hypertext Transfer Protocol (HTTP), Secure Hypertext Transfer Protocol (S-HTTP), and File Transfer Protocol (FTP). Microsoft Proxy Server can grant users access to selected application layer protocols and can restrict access to remote Web sites by domain name, Internet Protocol (IP) address, and subnet mask.

Application layer proxies provide more support for the additional capabilities of each protocol than circuit layer proxies do. For example, application layer proxies can support virus scanning. Application layer proxies are also client-neutral and require no special software components or operating system on the client computer to enable the client to communicate with servers on the Internet using the proxy server.

See Also: *proxy server*

application level gateway

A type of firewall that provides application-level control over network traffic.

Overview

Application level gateways examine incoming packets at the application level and use proxies to create secure sessions with hosts on the other side of the firewall. For example, when an external user with a Web browser tries to access the company's internal Web server, the application level gateway runs a proxy application that simulates the internal Web server. A session is established between the remote user and the proxy application, while a separate, independent session is established between the proxy application and the internal Web server. The remote user makes a request to the proxy, the proxy acts as a go-between and obtains the information from the internal web server, and then the proxy returns the result to the remote user.

The advantage of using application level gateways over packet-filtering routers is that although in packet filtering a direct network connection still exists between the remote user and the internal network resource, an application level gateway prevents the remote user from directly accessing the internal network resource. This layer of additional security comes at some cost—namely, that application gateways are generally slower and require a separate proxy application for each internal network service you want to make available through the firewall. These proxy applications are sometimes known as translation agents because they enable an application on one side of the firewall to connect with a similar or complementary application on the other side.

Application gateways are typically used to deny access to the resources of private networks to distrusted users over the Internet. Application level gateways can operate across firewalls or routers using Network Address Translation (NAT), but they must be configured to do so on an application-by-application basis.

See Also: *firewall, network address translation (NAT)*

application log

A Microsoft Windows 2000, Windows XP, and Windows .NET Server log that records events generated by applications running on the system.



Type	Date	Time	Source	Category	Event
Information	11/29/1999	2:47:42 AM	SceCli	None	1701
Information	11/29/1999	2:47:42 AM	SceCli	None	1500
Information	11/29/1999	2:47:22 AM	ESENT	General	101
Information	11/29/1999	2:47:06 AM	ESENT	General	100
Information	11/29/1999	2:47:06 AM	ESENT	General	101
Information	11/29/1999	2:47:03 AM	LoadPerf	None	1000
Warning	11/29/1999	2:47:03 AM	LoadPerf	None	2000
Information	11/29/1999	2:47:00 AM	ESENT	General	100
Information	11/29/1999	2:47:00 AM	ESENT	General	101
Information	11/29/1999	2:46:53 AM	ESENT	General	100
Information	11/29/1999	2:46:52 AM	LoadPerf	None	1000
Information	11/29/1999	2:46:51 AM	LoadPerf	None	1000
Warning	11/29/1999	2:32:51 AM	LicenseService	None	213
Warning	11/29/1999	2:17:51 AM	LicenseService	None	213
Warning	11/29/1999	2:02:50 AM	LicenseService	None	213

Application log. *Displaying the application log in the Event Viewer console.*

Overview

You can view and manage the application log using Event Viewer, and it can contain three types of events:

- **Error event:** Indicated by a red stop sign and signals a serious condition, such as a failed service
- **Warning event:** Indicated by a yellow warning sign and signals a potentially serious condition, such as low disk space
- **Information event:** Indicated by a blue information sign and signals a noteworthy event, such as a service successfully starting up

Microsoft BackOffice applications typically log events to the application log. Administrators should review the application log regularly to ensure that applications are running properly. The screen capture shows the application log as viewed by the Event Viewer management console for Windows 2000.

See Also: *security log, system log*

Application Performance Management (APM)

A set of technologies, business processes, and services for guaranteeing what subscribers experience from service providers.

Overview

Application Performance Management (APM) carries Service Level Agreements (SLAs) to the next level, providing a model for guaranteeing the end-user experience for customers of application service providers (ASPs). To accomplish this, APM integrates a number of business models and services:

- Traditional help desk services for problem resolution.
- Monitoring of SLAs.
- Network and system management tools working at the application level.
- Professional services to handle serious IT (information technology)–related crises.
- Services for processing management data.
- Support and training services.

A service provider that specializes in APM is sometimes referred to as a management service provider (MSP).

See Also: *application service provider (ASP)*

application programming interface (API)

Any collection of programming routines and functions that an application can use to access low-level machine services.

Overview

When you write applications for a high-level operating system such as Microsoft Windows, you use standard Windows application programming interfaces (APIs) to access standard operating system and networking services and functions. One application can then issue an API call to another application in order to execute that API function. Details of APIs are primarily of interest to developers.

Windows operating systems provide predefined sets of APIs for various purposes, such as Telephony Application Programming Interface (TAPI) for accessing functions related to making voice, data, or fax calls; Messaging Application Programming Interface (MAPI) for messaging functions; and so on.

An example of an API function in Windows NT is NetServerEnum. When a computer on a network issues a net view command to obtain the list of resources or computers that can be accessed using Network Neighborhood or Windows Explorer, the client computer issues a NetServerEnum API call to the Computer Browser service.

Microsoft Windows platforms include two basic sets of APIs:

- **Win16:** These 16-bit APIs were used by Windows 3.1.
- **Win32:** These 32-bit APIs are used on Windows 95, Windows 98, Windows Millennium Edition (Me), Windows NT, Windows 2000, Windows XP, and Windows .NET Server.

Notes

API also represents any set of calling conventions in a programming language that specifies how such a service is invoked through an application. Application programming interfaces (APIs) let C and assembly language routines interact with services and programming tools.

application service provider (ASP)

A general term for a company that offers software services to business customers across the Internet, particularly services involving outsourcing of Web and e-business applications.

Overview

A simple way of understanding the application service provider (ASP) model is to consider an ASP to be a company that hosts software applications for client companies and delivers them using the Internet for a monthly service fee. These applications are typically Web-based applications accessed by clients through a simple Web browser, although other delivery methods may be used, including Windows 2000 Terminal Services and Citrix MetaFrame. Once a client leases an application, the ASP is then responsible for day-to-day administration of the application and for maintenance and upgrades. ASPs may also be responsible for storing client data as well, although companies performing this service are more commonly called Storage Service Providers (SSPs). In contrast with simple Web hosting companies that offer their clients access to database applications and scripting tools but little else, ASPs also host the client's business logic and data at their remote data centers and provide a full range of supporting services to the client.

ASPs generally target one of two different market areas:

- **Vertical-market ASPs:** These target small to medium-sized business (the SMB, or small-to-medium business, segment of the market) by offering them packaged services such as Internet/Intranet hosting, e-mail and workflow applications, and scaled-down Customer Relations Management (CRM) and Enterprise Resource Planning (ERP) applications. Some small companies might not have the resources even to hire a single full-time IT (information technology) person, yet by using an ASP, they can quickly and easily obtain and use the necessary Line-Of-Business (LOB) applications they need to compete in the Internet economy in a cost-effective fashion. ASPs targeting this market tend to offer one-size-fits-all applications based on business logic templates that offer few customization options. This approach is taken to reduce costs for the ASP and make servicing this market level profitable.

- **Horizontal-market ASPs:** These target enterprise-level customers and offer similar applications but with more customization to fit these customers' needs.

When the ASP craze took off in 1999, most ASPs were dot-com startups targeting the small to mid-sized business market, which was itself growing rapidly due to the dot-com revolution then underway. The ASP revolution was driven largely by the increasing shortage of IT professionals in the marketplace which left hundreds of thousands of IT positions unfilled, the rapid proliferation of new IT technologies based on the Internet, and by the proliferation of dot-com startups that needed to deploy business applications and to deploy them fast in the highly competitive Internet economy of the late 20th century. But with the dot-com crash of 2001 many of the ASPs failed as their market space dried up, and some survivors instead began targeting large enterprises by offering the application customization these businesses required. The attraction of these enterprise-level customers for ASPs is their long-term stability and broad capital base, but such clients tend to be more conservative in their outlook and more cautious about embracing new service models. Meanwhile, large software companies such as Microsoft Corporation and Oracle Corporation began to reposition themselves as service providers instead of software vendors. With their proven track record and large resources, many analysts expect these large companies to dominate the ASP business in a few years, with smaller companies focusing on niche areas where their services can be most effectively marketed. Furthermore, companies such as Microsoft and Oracle are developing a next generation of Web-enabled software that can be easily deployed by new ASP startups without the extensive customization required by the earlier generation of ASP applications. A good example is Microsoft Exchange 2000, which is an ASP-ready platform for providing Web-based messaging and collaborative applications.

When the ASP market was just emerging, the major attraction for customers was saving money. As the market began to mature, other issues became important for customers to consider when shopping for an ASP:

- **Security:** In the beginning, many ASPs failed to address security concerns adequately. This has changed considerably, and the current generation of ASPs offers a full range of authentication and public-key infrastructure (PKI) services, virtual private networks (VPNs), firewall services, virus protection services, and intrusion detection services. Make sure the ASP you select can provide the level of security your company needs for its data.
- **Availability:** Make sure you negotiate a suitable service-level agreement (SLA) with your ASP to ensure that should their services be interrupted or terminated unexpectedly your business will still be able to function. If some of your staff will need to access ASP applications remotely using mobile clients through a VPN, make sure your SLA has a connectivity clause as well.
- **Performance:** Web-based applications mean high-bandwidth requirements for proper performance, both at the client end (usually T-1 or higher connections) and at the ASP's data center. Look for ASPs that colocate their servers at major Internet service providers (ISPs) for best performance and that have multiple redundant connections to the Internet with sufficient bandwidth to support the number of customers they service.
- **Track record:** With many of the first generation ASP startups having failed, companies are developing a "once-bitten, twice-shy" attitude towards outsourcing mission-critical business applications to ASPs. Talk to some of the ASPs larger clients and ask to see their financials to ensure their long-term viability before committing to using their services. When they start up, ASPs typically invest huge amounts of money in data centers, and they need to recover this investment quickly in order to survive. Some tier-1 Internet infrastructure providers offer ASP-level services, and these do not have as much of a capital risk associated with data center buildout as does a startup ASP.

Architecture

The data center is the heart of an ASP. Data centers are often colocated at ISP Points of Presence (POPs) to provide optimal high-speed connections to the backbone of the Internet. Data centers typically contain the following:

- File servers and database servers for storing structured data.
- Directory servers, Domain Name System (DNS) servers, and authentication servers for managing domains.
- Clustered or load-balanced Web servers for hosting Web applications in a redundant fashion.
- Terminal servers for supporting remote administration by customers.
- Storage area networks (SANs) and network attached storage (NAS) for storing data.
- Backup servers for archiving company data.

Advantages and Disadvantages

The advantages for client companies using ASPs are numerous and compelling to the management departments of most companies:

- They do not need to purchase the software themselves, which saves considerably on up-front costs.
- They do not need to hire additional IT staff to deploy and manage the new applications, which means considerable savings on labor costs.
- They can get new LOB applications up and running in a few days or weeks by relying on the expertise and infrastructure of the ASPs they are leasing these applications from.

The disadvantages of using ASPs are also important to consider when you are looking to outsource your LOB applications:

- You lose direct control over your company's software infrastructure and sometimes your data. This may be an issue with companies for which security is a strong concern.
- Many ASPs are new startups that may be acquired in the near future by larger companies or may fail if managed poorly. When your ASP fails, you might be left hanging with no software infrastructure to support your company's operations.

Marketplace

Some of the larger independent ASPs that have established themselves in the marketplace recently include the following:

- USinternetworking (*www.usi.com*)
- Corio (*www.corio.com*)
- Interliant (*www.interliant.com*)

Prospects

Although some industry watchers are predicting that the shakeout in the fledgling ASP industry will continue until only a few major players remain, the ASP model for outsourcing IT services has undeniably changed the IT landscape forever, as companies seek for cost-effective ways to economize on software purchasing by leasing LOB applications instead of purchasing them or developing them in-house.

One sector of the IT economy hit hard by the ASP revolution are the old-guard Independent Software Vendors (ISVs) that have spent years building and enhancing their line of client/server business applications. The Enterprise Resource Planning (ERP) industry has been one of the hardest hit, and established ERP vendors have had to move quickly to Web-enable their products and offer them as services in order to compete with upstart ASPs offering similar services. Some examples of ERP vendors who have repositioned themselves as ASPs include the following:

- SAP, with its SAP Hosting services
- PeopleSoft, with its eCenter
- Oracle, with its Oracle Business Online

Although the first two years of the new millennium have seen the demise of many ASP startups, industry analysts still predict strong growth in the ASP sector. The sector had a total worldwide market value of $300 million in 1999 and some analysts predict this could grow to as much as $25 billion by 2004. Much of the success or failure of this growth depends on broadband Internet access becoming cheap and ubiquitous at all business levels.

Nevertheless, because things change so fast in the new Internet economy, it is hard to know whether to trust long-term predictions such as these. After all, the ASP market went from infancy to maturity in about a year, so five years seems like a long time to predict its future growth and evolution!

Notes

Other terms used by different vendors to describe the ASP model include hosted applications, e-services, and "software as a service."

For More Information

You can find an ASP to meet your company's needs using the ASP portals WebHarbor (*www.webharbor.com*) and ASPScope (*www.aspscope.com*).

For the latest news on the ASP industry, see ASPNews (*www.aspnews.com*) and ASPPlanet (*www.aspplanet.com*).

An established source of independent information for the ASP community is ASPI, the ASP Industry Consortium (*www.aspindustry.org*). This consortium has taken on the role of policing the rapidly growing ASP market, whose companies range from responsible to vendors of snake oil. ASPI has defined a series of best practices that new ASPs should follow as guidelines for responsible success.

A notable company that provides a meta-infrastructure that enables new ASPs to grow and flourish is Loudcloud (*www.loudcloud.com*), a brainchild of Marc Andreesen of Netscape fame.

See Also: *xSP*

APPN

Stands for Advanced Peer-to-Peer Networking, a protocol developed by IBM as the second generation of Systems Network Architecture (SNA).

See: *Advanced Peer-to-Peer Networking (APPN)*

archive attribute

An attribute of files and folders that isused for managing backups.

Overview

When an archive bit is marked or set for a file by a backup program, it indicates that the file or folder has been backed up. Then, when the backup program is run again, if the archive bit is still set, the file is not backed up because it has not been modified. If the file is modified in the interim, the archive attribute is cleared, indicating that the file needs to be backed up again.

In Microsoft Windows you can also manually set or clear the archive attribute for a file by opening the file's property sheet.

See Also: *backup*

archiving

The process of long-term storage of important data for security and recovery reasons.

Overview

Archived data is usually stored in a compressed format because it is not required frequently. Some of the files that a Microsoft Windows 2000 administrator might consider archiving regularly include

- Event log files for the system, security, and application logs
- Performance monitor files for monitoring trends in memory, disk, processor, and network usage over time
- Log files for applications such as Microsoft Internet Information Services (IIS)

Notes

When you archive event log files, you can save these files in log file format, text file format, or comma-delimited text file format. An event's actual binary data is saved only if you archive it in event log format, but saving the information in a comma-delimited text file format allows you to import these logs into a spreadsheet program to analyze trends.

See Also: *backup, security*

ARCNET

Stands for Attached Resource Computer Network, an early local area network (LAN) architecture.

Overview

ARCNET was developed in 1976 by Datapoint Corporation and became an American National Standards Institute (ANSI) standard in 1982. ARCNET predates Ethernet by several years and can be implemented using a variety of media including RG/62 93-ohm coaxial cabling, RS-485 unshielded twisted-pair cabling, or fiber-optic cabling. ARCNET is a baseband networking technology that is similar to standards for token-passing bus networks running over broadband cabling. ARCNET uses a token-passing bus architecture with nodes forming a logical ring but a physical bus or star pattern. The core of an ARCNET network is a device called an active hub. Each of these hubs can support up to four connected devices. Multiple active hubs can then be interconnected using coaxial cable to support a maximum of 255 stations.

Classic ARCNET carries data at a rate of 2.5 megabits per second (Mbps). On coaxial cable, ARCNET cable runs can be up to 2000 feet (600 meters), but unshielded twisted pair supports distances of 400 feet (120 meters) and fiber-optic cabling distances of 8000 feet (2440 meters). A newer implementation called ARCNET Plus operates at a data rate of 20 Mbps and can support a maximum of 2047 nodes.

Notes

ARCNET is a legacy LAN technology occasionally found in some older networks.

Microsoft Windows 95, Windows 98, and Windows NT all support ARCNET. Sometimes a computer running Windows NT on an ARCNET network will have difficulty communicating with computers running Windows 95 and Windows 98 on the same network. This is because Windows NT uses Raw ARCNET and Windows 95 and Windows 98 use Encapsulated ARCNET. The workaround solution is to install the 16-bit Transmission Control Protocol/Internet Protocol (TCP/IP) stack with Novell Open Data-link Interface (ODI) drivers on the machines running Windows 95 and Windows 98.

ARC path

Stands for Advanced Reduced Instruction Set Computing (RISC) path, a syntax for naming partitions.

Overview

ARC paths are used in the Boot.ini file of Microsoft Windows 2000, Windows XP, and Windows .NET Server. The ARC path specifies the location of the partition that contains the Windows 2000 operating system files. In other words, the ARC path locates the system partition on the machine.

A typical ARC path on a Windows 2000 system might be the following:

```
multi(0)disk(0)rdisk(0)partition(1)\
WINNT="Microsoft Windows 2000 Server"/fastdetect
```

In the above statement:

- Multi(0) indicates that the system is using Integrated Device Electronics (IDE), Enhanced Small Device Interface (ESDI), or Small Computer System Interface (SCSI) drives and that it relies on the computer basic input/output system (BIOS) to load system files using INT 13 BIOS calls. The number in parentheses here should always be 0.
- Disk(0) is always zero when multi() is used; otherwise it refers to the physical disk when scsi() is used instead of multi(). Multi() means that Windows 2000 must use the system BIOS to load system files, and scsi() means that a SCSI device driver must be loaded to access the boot partition.
- Rdisk(0) indicates that the ordinal number for the system disk is 0. This value is usually between 0 and 3.
- Partition(2) indicates the number of the partition where the system files are located.

ARIN

Stands for American Registry for Internet Numbers, a nonprofit organization that administers the registration and allocation of numbers relating to the operation of the Internet in North and South America.

See: *American Registry for Internet Numbers (ARIN)*

ARP

Stands for Address Resolution Protocol, the Transmission Control Protocol/Internet Protocol (TCP/IP) network layer protocol responsible for resolving IP addresses into MAC addresses.

See: *Address Resolution Protocol (ARP)*

ARPANET

Stands for Advanced Research Projects Agency Network, a U.S. Department of Defense project begun in 1969 that was designed to provide high-speed network communication links between supercomputers located at different sites around the country.

Overview

ARPANET was a test bed for the development of the Transmission Control Protocol/Internet Protocol (TCP/IP) protocol suite. The first node on the ARPANET was established in 1969 at UCLA. Soon afterward, more nodes were created at other institutions, including Stanford University and BBN Technologies. The first Request for Comments (RFC) was proposed in the same year by Steve Croker and was entitled “Host Software.”

By 1971, ARPANET had grown to over 20 hosts, including MIT, NASA, and the RAND Corporation. The first international nodes were established two years later in Norway and England. In 1983, Military Network (MILNET) was split off from ARPANET, and TCP/IP officially became the standard protocol for ARPANET, at which time ARPANET started to become widely known as the Internet. ARPANET continued to evolve until NSFNET was established in 1986.

ARPANET was finally shut down in 1989.

For More Information

Read about the history of ARPANET at *www.securenet.net/members/shartley/history/arpanet.htm.*

See Also: *Internet*

Arp command

A Transmission Control Protocol/Internet Protocol (TCP/IP) utility for viewing and modifying the local Address Resolution Protocol (ARP) cache, which contains recently resolved MAC addresses of Internet Protocol (IP) hosts on the network.

Overview

When one host on a TCP/IP network wants to communicate with a second host, the first host begins by using the ARP to resolve the IP address of the second host into its associated MAC address. The MAC address is needed for communication to take place over the network.

Typing arp -a displays the MAC addresses of recently resolved IP addresses. A sample display could be

```
Interface: 172.16.8.50
Internet Address    Physical Address   Type
172.16.8.25         00-20-af-b4-a1-4e  dynamic
172.16.8.200        00-40-95-d1-29-6c  static
```

One of these entries is static, meaning the Internet Protocol–to-MAC address mapping has been manually added to the ARP cache using arp –s.

See Also: *Transmission Control Protocol/Internet Protocol (TCP/IP)*

AS

Stands for autonomous system, a group of Internet Protocol (IP) networks administered under a single administrative (routing) policy.

See: *autonomous system (AS)*

AS/400

Stands for Application System/400, a midrange IBM server computing platform for business computing.

Overview

IBM’s AS/400 platform is a 64-bit Reduced Instruction Set Computing (RISC) system available in a variety of configurations for different business needs. Until recently seen as a legacy platform similar to mainframes, AS/400 has been revamped in the last few years and is now one of the leading Web application and e-business platforms available for an enterprise.

AS/400 uses the OS/400 operating system but includes support for UNIX through the Portable Application

Solution Environment (PASE). Systems Network Architecture (SNA) support is also available for providing connectivity with IBM mainframe computing environments.

Some of the popular configurations in which AS/400 is offered include

- **AS/400e Model 250:** An entry-level single-processor machine with no support for logical partitioning. Suitable for running packaged Web applications for small businesses.
- **AS/400e Model 820:** A mid-tier four-way symmetric multiprocessing (SMP) server supporting up to 16 gigabytes (GB) of RAM and 4 terabytes of storage.
- **AS/400e Model 840:** Top-of-the-line enterprise-level server for high-transaction, high-volume e-business, supply chain and Enterprise Resource Planning (ERP) applications, supporting up to 24-way SMP, 96 GB of RAM, and up to 18.9 terabytes of storage.

Notes

The newest offerings in IBM's AS/400 line incorporate IBM's new high-performance copper-wired chips.

For More Information

You can find IBM's AS/400 home page at *www-1.ibm.com/servers/eserver/iseries.*

ASCII

Stands for American Standard Code for Information Interchange, a widely accepted system for coding U.S. English text using numeric values.

Overview

The purpose of ASCII is to allow human-readable documents to be stored and processed as binary information by computers. ASCII assigns a unique numeric value to each lowercase and uppercase alphabet letter, number, punctuation mark, and to certain other characters. For example, the capital letter "A" has the ASCII code 65 and a blank space has the code 32.

ASCII is a 7-bit character set that isthe same as the first 128 characters (numbers 0 to 127) of the American National Standards Institute (ANSI) character set. The following table shows the various characters in the ASCII character set. The first 32 characters are non-printing control characters that can be executed from the keyboard by using the Control key combined with other keys.

The ASCII Character Set

Char	*Dec*	*Oct*	*Hex*	*Control Key Combination*	*Description*
NUL	0	0	0	^@	Null character
SOH	1	1	1	^A	Start of heading
STX	2	2	2	^B	Start of text
ETX	3	3	3	^C	End of text
EOT	4	4	4	^D	End of transmission
ENQ	5	5	5	^E	Enquiry
ACK	6	6	6	^F	Acknowledge
BEL	7	7	7	^G	Bell
BS	8	10	8	^H	Backspace
HT	9	11	9	^I	Horizontal tab
LF	10	12	a	^J	Line feed
VT	11	13	b	^K	Vertical tab
FF	12	14	c	^L	Form feed
CR	13	15	d	^M	Carriage return
SO	14	16	e	^N	Shift out
SI	15	17	f	^O	Shift in
DLE	16	20	10	^P	Data link escape
DC1	17	21	11	^Q	Device control 1 (XON)
DC2	18	22	12	^R	Device control 2
DC3	19	23	13	^S	Device control 3 (XOFF)
DC4	20	24	14	^T	Device control 4
NAK	21	25	15	^U	Negative acknowledge
SYN	22	26	16	^V	Synchronous idle
ETB	23	27	17	^W	End transmission block
CAN	24	30	17	^X	Cancel line
EM	25	31	19	^Y	End of medium
SUB	26	32	1a	^Z	Substitute
ESC	27	33	1b	^[	Escape

(continued)

The ASCII Character Set *continued*

Char	*Dec*	*Oct*	*Hex*	*Control Key Combination*	*Description*
FS	28	34	1c	^\	File separator
GS	29	35	1d	^]	Group separator
RS	30	36	1e	^^	Record separator
US	31	37	1f	^_	Unit separator
SP	32	40	20		Space
!	33	41	21		Exclamation mark
"	34	42	22		Quotation mark
#	35	43	23		Cross hatch
$	36	44	24		Dollar sign
%	37	45	25		Percent sign
&	38	46	26		Ampersand
‘	39	47	27		Apostrophe
(	40	50	28		Opening parenthesis
)	41	51	29		Closing parenthesis
*	42	52	2a		Asterisk
+	43	53	2b		Plus
,	44	54	2c		Comma
-	45	55	2d		Hyphen
.	46	56	2e		Period
/	47	57	2f		Forward slash
0	48	60	30		Zero
1	49	61	31		One
2	50	62	32		Two
3	51	63	33		Three
4	52	64	34		Four
5	53	65	35		Five
6	54	66	36		Six
7	55	67	37		Seven
8	56	70	38		Eight
9	57	71	39		Nine
:	58	72	3a		Colon
;	59	73	3b		Semicolon
<	60	74	3c		Less than sign
=	61	75	3d		Equals sign
>	62	76	3e		Greater than sign
?	63	77	3f		Question mark
@	64	100	40		At sign

(continued)

The ASCII Character Set *continued*

Char	*Dec*	*Oct*	*Hex*	*Control Key Combination*	*Description*
A	65	101	41		Uppercase A
B	66	102	42		Uppercase B
C	67	103	43		Uppercase C
D	68	104	44		Uppercase D
E	69	105	45		Uppercase E
F	70	106	46		Uppercase F
G	71	107	47		Uppercase G
H	72	110	48		Uppercase H
I	73	111	49		Uppercase I
J	74	112	4a		Uppercase J
K	75	113	4b		Uppercase K
L	76	114	4c		Uppercase L
M	77	115	4d		Uppercase M
N	78	116	4e		Uppercase N
O	79	117	4f		Uppercase O
P	80	120	50		Uppercase P
Q	81	121	51		Uppercase Q
R	82	122	52		Uppercase R
S	83	123	53		Uppercase S
T	84	124	54		Uppercase T
U	85	125	55		Uppercase U
V	86	126	56		Uppercase V
W	87	127	57		Uppercase W
X	88	130	58		Uppercase X
Y	89	131	59		Uppercase Y
Z	90	132	5a		Uppercase Z
[	91	133	5b		Opening square bracket
\	92	134	5c		Backslash
]	93	135	5d		Closing square bracket
^	94	136	5e		Caret
_	95	137	5f		Underscore
‘	96	140	60		Opening single quote
a	97	141	61		Lowercase a
b	98	142	62		Lowercase b
c	99	143	63		Lowercase c
d	100	144	64		Lowercase d
e	101	145	65		Lowercase e
f	102	146	66		Lowercase f
g	103	147	67		Lowercase g
h	104	150	68		Lowercase h

(continued)

The ASCII Character Set *continued*

Char	*Dec*	*Oct*	*Hex*	*Control Key Combination*	*Description*
i	105	151	69		Lowercase i
j	106	152	6a		Lowercase j
k	107	153	6b		Lowercase k
l	108	154	6c		Lowercase l
m	109	155	6d		Lowercase m
n	110	156	6e		Lowercase n
o	111	157	6f		Lowercase o
p	112	160	70		Lowercase p
q	113	161	71		Lowercase q
r	114	162	72		Lowercase r
s	115	163	73		Lowercase s
t	116	164	74		Lowercase t
u	117	165	75		Lowercase u
v	118	166	76		Lowercase v
w	119	167	77		Lowercase w
x	120	170	78		Lowercase x
y	121	171	79		Lowercase y
z	122	172	7a		Lowercase z
{	123	173	7b		Opening curly brace
|	124	174	7c		Vertical line (pipe)
}	125	175	7d		Closing curly brace
~	126	176	7e		Tilde
DEL	127	177	7f		Delete

Notes

When you download files using File Transfer Protocol (FTP), you can choose whether to transfer the files as binary files or text files (ASCII files). Use only the ASCII file setting when downloading plain text files; otherwise, files will not be correctly transferred.

Some people create e-mail signatures for themselves using ASCII text characters, a practice called ASCII art. If you have the time and want to become an expert at this, read the FAQs (frequently asked questions) on the Web at *non.com/news.answers/ascii-art-faq.html.*

For More Information

There is an online ASCII table at *www.asciitable.com.*

See Also: *Unicode*

ASCII file

A file that contains unformatted American Standard Code for Information Interchange (ASCII) text.

Overview

An ASCII (text) file contains only characters, numbers, punctuation, tabs, and carriage return characters. You can create and edit an ASCII file using Microsoft Notepad. If you save it with the extension .txt, it is usually referred to as a text file, but you can save it with other extensions such as .bat or .cmd for batch files and .ini for initialization files.

Uses

ASCII files are often used for logon scripts and other batch files. Another common use is storing configuration information for operating systems and applications. Microsoft Windows 3.1 platforms used ASCII files for storing system and software configuration settings. These configuration files have the extension .ini and are referred to as INI (initialization) files. More recent Windows operating systems save this information in the registry. Most versions of the UNIX operating system still store their configuration settings in ASCII files.

Because ASCII files contain unformatted text, they can be read and understood by any platform and are useful for sharing information between platforms and between applications. Shared information is often saved in a comma-delimited text file, or .csv file, with the fields separated by commas. Microsoft Exchange Server can export mailbox properties and other information in .csv files, which can then be imported into spreadsheet programs such as Microsoft Excel for manipulation and analysis.

See Also: *ASCII*

ASF

Stands for Advanced Streaming Format, a method of streaming data supported by Windows Media Player.

See: *Advanced Streaming Format (ASF)*

Asia Pacific Network Information Center (APNIC)

A counterpart of the American Registry for Internet Numbers (ARIN), this is the agency responsible for administering the registration and allocation of Internet numbers for the Asia/Pacific region.

Overview

The Asia Pacific Network Information Center (APNIC) is one of the three Regional Internet Registries (RIRs) that provide Internet numbers allocation and registration services to support the operation of the global Internet. These Internet numbers include IPv4 and IPv6 addresses, autonomous system (AS) numbers, and reverse Domain Name System (DNS) delegations. APNIC is responsible for allocation of these numbers for the Asia Pacific region, which comprises 62 different economies.

APNIC is a nonprofit, membership-based organization whose members include National Internet Registries, Internet Service Providers (ISPs), and similar bodies. Membership in APNIC is fee-based.

For More Information

Visit APNIC at *www.apnic.org.*

See Also: *American Registry for Internet Numbers (ARIN)*

ASN

Stands for autonomous system number, a unique number used to identify an autonomous system (AS), that is, a network that can exchange exterior routing information with neighboring networks.

See: *autonomous system number (ASN)*

ASN.1

Stands for Abstract Syntax Notation One, a standard from the International Standards Organization (ISO) that provides a mechanism for encoding human-readable symbols into condensed binary form.

See: *Abstract Syntax Notation One (ASN.1)*

ASP (Active Server Pages)

Stands for Active Server Pages, an open, compile-free application environment for developing Web applications using Microsoft Internet Information Server (IIS) version 3 and later.

See Also: *Active Server Pages (ASP)*

ASP (application service provider)

Stands for application service provider, a company that offers software services to business customers across the Internet, particularly services involving outsourcing of Web and e-business applications.

See Also: *application service provider (ASP)*

ASP.NET

The evolution of Microsoft Corporation's Active Server Pages (ASP) technology for the new .NET platform.

Overview

ASP.NET is an advanced platform for developing Web applications, Web Services, and Web Forms under the Microsoft .NET platform. ASP.NET solutions can be developed using Microsoft Visual Studio .NET and other tools, and ASP.NET supports application authoring in C#, Visual Basic .NET, and other programming languages.

ASP.NET is Microsoft's successor to ASP and ASP+ (Active Server Pages Plus) and is to a large degree backward-compatible with the syntax of these earlier platforms. Unlike ASP and ASP+, however, ASP.NET is a compiled platform rather than an interpreted one, which offers better run-time performance. ASP.NET is also easily factorable so that developers can remove modules that are not required for a particular application, making applications more code-efficient and giving them a smaller footprint.

ASP.NET provides two levels of programming models:

- **Low-level:** ASP.NET provides a programming model similar to Internet Server Application

Programming Interface (ISAPI) but easier to use for rapid development.

- **High-level:** ASP.NET enables the easy building of Web Forms, a high-level programming model for building Web applications.

ASP.NET also supports a number of different authentication schemes including Basic, authentication, Digest authentication, NT Lan Manager (NTLM) authentication, custom cookie-based authentication, and Microsoft Passport authentication.

For More Information

Find out more about ASP.NET at *msdn.microsoft.com/net/aspnet.*

See Also: *Active Server Pages (ASP), .NET platform*

ASR

Stands for Automatic System Recovery, a feature of Microsoft Windows 2000, Windows XP, and Windows .NET Server that allows you to restore your system in the event of hard disk failure or corruption of system files.

See: *Automatic System Recovery (ASR)*

Association for Computing Machinery (ACM)

The oldest and largest educational and scientific computing society in the world.

Overview

The Association for Computing Machinery (ACM) provides a forum for the exchange of information, ideas, and discoveries relating to many aspects of computing. The ACM has a worldwide membership of 80,000 computer professionals representing a wide variety of interests. The ACM sponsors a number of special interest groups (SIGs) that bring together ACM members with shared interests. These SIGs publish technical newsletters, host conferences, and help develop standards.

One SIG of interest to networking professionals is the ACM Special Interest Group on Data Communication (SIGCOMM), which provides a forum for data communication professionals. SIGCOMM focuses on standards for network protocols and architectures. SIGCOMM publishes the ACM/IEEE Transactions on Networking Journal, sponsors conferences, and publishes a quarterly newsletter called the Computer Communication Review (CCR) in conjunction with the Institute of Electrical and Electronics Engineers (IEEE).

For More Information

Find out about the ACM at *www.acm.org* and the SIGCOMM at *www.acm.org/sigcomm.*

Asymmetric Digital Subscriber Line (ADSL)

A form of Digital Subscriber Line (DSL) technology that provides subscribers with high-speed voice and data services over twisted-pair copper phone lines.

Overview

Asymmetric Digital Subscriber Line (ADSL) was developed by Bellcore in 1989 as a means of transmitting digital information over ordinary twisted-pair Plain Old Telephone Service (POTS) telephone lines to subscribers at speeds faster than 1 megabit per second (Mbps). The original vision of ADSL was to provide residential subscribers with high-quality digital multimedia content, particularly Moving Pictures Experts Group (MPEG) movies through Video On Demand (VOD) services. This was intended to allow phone companies to compete with the emerging cable television market for delivering video to residential areas. This goal has since faded, and now the main push for deploying ADSL is residential broadband Internet access.

ADSL specifies how to implement high-speed, full-duplex transmission over the existing twisted-pair copper cabling of POTS. ADSL can be used to simultaneously transmit voice and data over a single telephone line and can be used to provide high-speed Internet access for both homes and businesses. Even should the data link to the Internet go down, POTS voice service would still be available using ADSL.

The *asymmetric* in ADSL refers to the fact that the upstream and downstream transmission rates in ADSL are not equal. Over best-quality copper phone lines, ADSL can achieve upstream speeds of up to 1.5 Mbps and downstream speeds of up to 9 Mbps, usually in a 10:1 ratio. This asymmetry makes ADSL ideal for providing high-speed Internet access to homes and businesses where fast download speeds are more important than upload speeds.


1. Typical ADSL Configuration
HOME
Telephone
Workstation
ADSL modem
POTS Local Loop
TELCO CENTRAL OFFICE
Splitter
PSTN switch
DSLAM
Voice Network
Router
Internet
2. ADSL Bandwidth Allocation
Percentage of Bandwidth Allocation
100
50
0
A
B
C
4
300
700
1000
5000
10000
KHz
A = POTS
B = Upstream channel
C = Downstream channel

Asymmetric Digital Subscriber Line (ADSL). *Implementing ADSL.*

Uses

ADSL has many advantages over standard analog modem access to the Internet, including much higher data rates, instant-on connection, simultaneous transmission of voice and data over a single phone line, and greater security. The negative side of ADSL is the higher equipment cost and the fact that customers must be located within 18,000 feet (5500 meters) of the carrier's CO for ADSL to work. ADSL Internet services typically cost between $40 and $100 per month, depending on the carrier and the area being serviced.

Besides providing residential and business Internet access, ADSL also has other uses, including the following:

- Connectivity with branch offices.
- B2B secure communications (using Point-to-Point Tunneling Protocol [PPTP] or Layer 2 Tunneling Protocol [L2TP]).
- Telecommuting.

An external ADSL modem with support for Network Address Translation (NAT) allows a single modem to connect a network of machines to the Internet using only one carrier-granted Internet Protocol (IP) address. Some ADSL appliances include a built-in Ethernet hub to make this process simpler.

Cable modem technologies are currently competing with ADSL in the residential broadband Internet access, but ADSL offers greater security than cable modems and provides guaranteed bandwidth that shared-network cable modems cannot currently provide.

Implementation

The great advantage of ADSL as a high-speed access service is the ubiquity of the existing twisted-pair POTS wiring system. ADSL providers do not have to build a delivery infrastructure because the wires are already there; they just have to install the switches and modems to make it work.

ADSL uses frequency-division multiplexing (FDM) to separate voice and data into three separate communications channels:

- A baseband voice channel
- An upstream data channel
- A downstream data channel

The range of frequencies used for each channel vary depending on the carrier's particular implementation. Each channel occupies a different portion of the frequency spectrum, as shown in the figure, which illustrates a possible implementation of ADSL. The baseband voice channel is split off from the data channels to guarantee phone services in case the data channel fails. Data transmission rates in the upstream direction range from 128 kilobits per second (Kbps) to 1.54 megabits per second (Mbps), and those in the downstream direction range from 384 Kbps to 7.1 Mbps, depending on the length of the local loop—the distance from the customer premises to the telco's (CO) central office—and the telephone cable's wire gauge. The longer the distance from the customer premises to the CO, the slower the ADSL speed that can be achieved (this feature is why ADSL is referred to as a "best effort" service). ADSL speeds start to drop significantly when the subscriber is beyond 10,000 feet from the CO due to interference, attenuation, and crosstalk, and ADSL becomes almost totally ineffectual beyond 18,000 feet. ADSL speeds also vary depending on the AWG gauge of the twisted-pair telephone wires in the subscriber's local loop and residence, with 24 gauge wire providing better performance than 26 gauge.

In a typical ADSL implementation, an ADSL modem (technically called an ADSL Transmission Unit-Remote, or ATU-R) is used to connect a subscriber's computer or network to a standard analog POTS phone line. The ADSL modem contains a POTS splitter chip that splits the bandwidth of the phone line into a voice and a data channel. The data channel is then split, using a channel separator chip, into a separate upstream and downstream channel, with the downstream channel having the larger portion of allocated bandwidth. The voice band typically uses frequencies from 0 to 3.4 kilohertz (kHz), while the data channels use higher frequencies anywhere from above 26 kHz to beyond 1100 kHz, depending on the carrier's implementation. Carrying capacity depends on the wire's thickness and other line conditions.

At the other end of the subscriber's local loop is another ADSL modem (properly called an ADSL Transmission Unit-Central Office or ATU-C) at the telco's CO. The telco's modem separates the voice signal from the data stream using a splitter and routes voice calls through the POTS system of telco switches, while the data is routed to a Digital Subscriber Line Access Multiplexer (DSLAM) unit. The DSLAM unit combines multiple ADSL lines into a single pipe for transmission over the carrier's fiber-optic Asynchronous Transfer Mode (ATM) backbone network to the Internet or to other DSL provider networks. This process is known as ATM over ADSL.

ADSL can employ several different modulation systems for encoding the data channels:

- Carrierless amplitude/phase (CAP)
- Discrete multitone (DMT)
- Discrete wavelet multitone (DWMT)

For More Information

Find out more about ADSL at the site of the ADSL Forum, *www.adsl.com.*

See Also: *Digital Subscriber Line (DSL), G.Lite*

asymmetric multiprocessing (AMP)

A processing architecture in which processes are specifically assigned to different processors.

Overview

When asymmetric multiprocessing (AMP) is used on a multiprocessor computer (a computer with more than one CPU), each processor is assigned specific tasks to perform. For example, one processor might be dedicated to managing input/output (I/O) requests, another to executing network requests, another to running a user application, and so on.

AMP contrasts with symmetric multiprocessing (SMP), in which the operating system evenly distributes the application load across multiple processors. In SMP, individual processes are not mapped to specific processors but instead are assigned to available processors by the operating system.

Notes

Microsoft Windows 2000 supports SMP but not AMP.

async

Short for asynchronous transmission, a form of data transmission in which the transmitting and receiving stations do not explicitly coordinate their transmissions with each other.

See: *asynchronous transmission*

Asynchronous Transfer Mode (ATM)

A high-speed, broadband transmission data communication technology based on packet switching and multiplexing technologies, and used by telcos, long distance carriers, and campus-wide backbone networks to carry integrated data, voice, and video information.

Overview

Asynchronous Transfer Mode (ATM) technology originated in the late 1970s and early 1980s through research into broadband Integrated Services Digital Network (ISDN) (B-ISDN). Like Internet Protocol (IP), ATM is basically a packet-switching technology, but unlike IP with its variable-length packets, ATM uses fixed-size packets called "cells." The fixed size of an ATM cell makes ATM traffic simple and predictable, and makes it possible for ATM to operate at high speeds.

ATM works primarily at Layer 2 of the Open Systems Interconnection (OSI) reference model and so its operation is independent of the Physical Layer (PHY) transport used. The speeds at which ATM operate depend on the transmission medias being used. The various speeds available include:

- 1.544 megabits per second (Mbps) to 25 Mbps over unshielded twisted-pair (UTP) Category 5 (Cat5) cabling, also known as "ATM to the desktop." This early ATM initiative was derailed by the rapid advances in Fast Ethernet, which won out over ATM because of its simplicity and lower cost.

- 155 Mbps (OC-3) over either UTP or fiber-optic cabling, used primarily for connecting wiring closets to backbone networks.
- 622 Mbps (OC-12), 2.4 Gbps (OC-48), and 4.8 Gbps (OC-96) over fiber-optic cabling only, used exclusively for ATM core (backbone) networks and Synchronous Optical Network/Synchronous Digital Hierarchy (SONET/SDH) as PHY layer transport.

The *asynchronous* in *ATM* means ATM devices do not send and receive information at fixed speeds or using a timer but instead negotiate transmission speeds based on hardware and information flow reliability. The *transfer mode* in *ATM* refers to the fixed-size cell structure used for packaging information. This cell-based transmission is in contrast to typical local area network (LAN) variable-length packet mechanisms, which means that ATM connections are predictable and can be managed so that no single data type or connection can monopolize the transmission path. As a result, ATM is suitable for transmitting all types of traffic from “bursty” data transmissions to real-time and packaged voice and video playback.

Different “classes of service” are used to accommodate transmission of different traffic types in optimal ways, and ATM optimizes traffic flow performance through these various classes of service, which can be allocated on a per-connection basis by using ATM’s Quality of Service (QoS) settings. In this fashion, ATM is different from frame relay, which is essentially a classless service. Note that not all carriers or ATM switching gear support all of these service categories.

The six service categories currently defined for ATM defined by the ATM Forum are

- **Constant Bit Rate (CBR):** This level is suitable for applications that require a relatively static amount of bandwidth over the duration of a connection. An example might be network control traffic.
- **Real-time Variable Bit Rate (rt-VBR or VBR-RT):** This level is suitable for real-time applications such as video and voice that are sensitive to delay and use large amounts of bandwidth.
- **Non-real-time Variable Bit Rate (nrt-VBR or VBR-NRT):** This level is suitable for bursty traffic that is not real-time in nature. An example might be data acquisition in experiments or playback of canned video presentations.
- **Unspecified Bit Rate (UBR):** This level is suitable for traffic that is not delay sensitive and non-real-time. Examples might include e-mail and file transfers.
- **Available Bit Rate (ABR):** This level includes a flow-control mechanism and is therefore suitable for non-real-time traffic where the transmission characteristics are subject to change over the life of the connection. An example might be file transfers over a noisy link.
- **Guaranteed Frame Rate (GFR):** This level allows additional bandwidth to be allocated dynamically when needed.

ATM also includes a mechanism for allocating bandwidth dynamically; that is, bandwidth is allocated only in required amounts and the required direction. As a result, when an ATM link is idle, it utilizes no bandwidth, which can result in considerable cost savings depending on the needs of your network. ATM networks use bandwidth at maximum efficiency, while maintaining guaranteed QoS for users and applications that require it.

The evolution of ATM has been guided since 1991 in large measure by the efforts of the ATM Forum. ATM is also based on a group of international signaling and interface standards defined by the International Telecommunication Union (ITU). These standards include the user network interface (UNI) standards that specify how users connect to ATM networks, and the broadband intercarrier interface (B-ICI) and public network-to-network interface (P-NNI) standards for establishing connectivity between different ATM networks.

Uses

ATM was originally envisioned as an end-to-end networking architecture that would supersede Ethernet and Token Ring in enterprise LANs because of its built-in support for QoS. Initial deployments included backbones for enterprise LANs with the vision to carry ATM directly to the desktop, but the rapid evolution, simplicity, and lower cost of Fast Ethernet and, later, Gigabit Ethernet (GbE) have prevented ATM from fulfilling its original vision. Few enterprises deploy new ATM backbones today, and the emergence of 10 Gigabit Ethernet (10 GbE) makes this even more unlikely in the future.

If ATM in the backbone is declining in the enterprise, ATM for WAN access remains relatively strong. GbE backbone switches with core ATM ports can be used to connect enterprise networks to carrier's ATM networks for remote access to branch offices and subsidiaries. Alternatively, an Integrated Access Device (IAD) aggregates network traffic at the customer premises into a single ATM WAN pipe for connection to the carrier.

ATM has been widely adopted in the communications networks of telecommunication carriers (telcos). ATM metropolitan area networks (MANs) are widespread, and ATM is viewed as the de facto technology for long distance fiber-optic communication lines stretching thousands of kilometers across continents.

ATM hardware spans the whole range of networking infrastructure, including ATM backbone switches and edge switches, ATM multiplexers, ATM remote access devices, and ATM network interface cards.

Architecture

ATM uses fixed-size 53-byte cells. Each cell contains 48 bytes of payload (data) and 5 bytes of control and routing information in the header. The 5-byte header provides addressing information for switching the packet to its destination and can be implemented in one of two formats: User to Network Interface (UNI) or Network Node Interface (NNI).

The 48-byte payload section carries the actual information, which can be data, voice, or video. The payload is properly called the user information field. The reason for choosing 48 bytes as the payload size is to compromise between the optimal cell sizes for carrying voice information (32 bytes) and data information (64 bytes).

ATM uses a layered architecture for its protocol stack, similar in some respects to the lower portions of the OSI model. There are three main layers in the ATM architecture:

- **ATM Adaptation Layer (AAL):** This is the top layer in ATM and is responsible for guaranteeing service characteristics of transmission and for building different types of data into the 48-byte cell payload. It is called the Adaptation Layer because it adapts the ATM Layer beneath it to the particular services that will be using it. The ATM Adaptation Layer consists of two sublayers, the Convergence Sublayer (CS) and the Segmentation and Reassembly (SAR) sublayer. The ATM Adaptation Layer supports five different AAL protocols from AAL 1 through AAL 5, with the last one being the most widely used. The ATM Adaptation Layer is equivalent to the OSI model's Data Link Layer.
- **ATM Layer:** This middle layer takes the payload formed by the ATM Adaptation Layer and adds the 5-byte header information and routes the packet to its destination.
- **Physical Layer:** This bottom layer defines the electrical characteristics of the network interface and media over which the ATM cell is transmitted and converts the ATM cell into electrical signals. In other words the Physical Layer "puts the bits onto the wire." ATM supports a variety of different PHY level transports, including SONET, SDH, DS3/E3, Fiber Distributed Data Interface (FDDI), and Fibre Channel. The ATM Layer and Physical Layer are together equivalent to the OSI model's Physical layer.

ATM supports a variety of address formats. Public ATM networks implemented by telecommunications carriers use the same 19-byte E.164 addresses used by Narrowband ISDN. Private ATM networks can use three different address formats: Network Service Access Point (NSAP) encapsulated E.164, Data Country Code (DCC), and International Code Designator (ICD).

ATM is generally deployed in a star topology with the ATM switch at the center acting as a concentrator. The advantages of this topology are that troubleshooting is simplified and the network can easily be reconfigured if required. ATM switches can provide bandwidth on demand, and additional connections can be formed with the switch when more bandwidth needs to be added.

ATM is a connection-oriented technology that supports both point-to-point and point-to-multipoint connections, but multipoint connections require multicasting (ATM does not support broadcasts). ATM requires the establishment of a specific network path between two points before data can be transported between them. This path is negotiated by the transmitting station, which specifies the type of connection (service classes discussed above), speed (bandwidth) required, and other attributes.

The paths with which ATM connects end stations are called virtual channels (VCs). Virtual channels consist of one or more physical ATM links connected in a series for transmitting data between remote stations. A VC exists only while data is being transmitted on it, and all cells in a given ATM transmission follow the same VC to ensure reliable data transmission. A virtual path (VP) is a collection of VCs having the same source and destination points that can be used to pool traffic being transmitted to a given destination. The header of an ATM cell contains routing information that defines the VC being used for the connection. This routing information is called the Virtual Path Identifier/Virtual Channel Identifier (VPI/VCI).

VCs and VPs are the basic building blocks of ATM networks and provide end-to-end connections with well-defined end points and traffic routes. VCs may be of two types: permanent virtual circuits (PVCs) and switched virtual circuits (SVCs). ATM can work with either PVCs or SVCs, depending on your wide area network (WAN) traffic needs. PVCs are more commonly used by ATM service provider networks but are less efficient with respect to bandwidth costs.

Typically a subscriber needing an ATM WAN link for their company leases a T1 or T3 line to connect their customer premises equipment (CPE) to the telecommunication carrier's ATM network, but frame relay or SONET can also be used to connect a site to an ATM network. The kind of CPE needed varies with the access method employed—for example, Channel Service Unit (CSU) for T1 line, frame relay access device (FRAD) or router for frame relay, and so on. Large corporate networks using an ATM backbone might use a switch-to-switch connection to the carrier's network instead of CPE.

Advantages and Disadvantages

ATM's two main benefits are its high transmission speeds and its flexible bandwidth-on-demand capability. ATM has the following advantages over competing high-speed networking technologies:

- High-speed, fast-switched integrated data, voice, and video communication that is not bound by the physical or architectural design constraints of traditional LAN networking technologies.
- A standards-based solution formalized by the ITU that allows ATM to easily replace existing telephony network infrastructures. ATM provides a global telephony standard, and more than 70 percent of U.S. telcos have migrated their internal networks to ATM.
- A fixed-length cell-based transmission that is suitable for transport of real-time traffic such as voice and video and which allows high-speed bulk encryption mechanisms to be implemented easily and in an affordable way.
- Interoperability with standard LAN/WAN technologies. ATM networks can be interconnected with Ethernet and token ring LANs using LAN emulation (LANE) services to provide Transmission Control Protocol/Internet Protocol (TCP/IP) over ATM.
- Built-in support for QoS that enables a single ATM network connection to reliably carry voice, data, and video simultaneously and manage bandwidth on a per connection basis depending on the priority of the service required. By assigning a bandwidth profile to an ATM connection, the performance of the connection can be guaranteed.

- A connection-oriented architecture that makes it resistant to the kind of denial of service (DoS) attacks for which Internet Protocol (IP) networks are famous. ATM is a more secure solution than IP for the trust boundary where WAN links are found in enterprise networks.

On the other hand, ATM has some significant disadvantages that have hindered its widespread adoption in enterprise networks:

- ATM switching equipment is more expensive than gear for competing technologies such as GbE.
- ATM is more complex in its architecture and operation than competing technologies. By contrast, GbE is an easy step upwards from Fast Ethernet.
- The ATM vision of integrated voice/video/data throughout the enterprise (a.k.a. "convergence") is not driven by market pressure, so in some ways ATM remains "a solution in search of a problem."
- Support for ATM in the WAN market has also been hindered by the fact that most carriers have not yet deployed switched virtual circuits (SVCs) and instead continue to rely upon static permanent virtual circuits (PVCs), which are less flexible and provide a fixed amount of bandwidth at a relatively high cost. Moving to SVCs would reduce costs for customers by enabling bandwidth-on-demand, but most carriers are reluctant to make the capital outlay for upgrading their switching equipment if the end result is to reduce immediate revenue by lowering costs.

Marketplace

Some of the larger carriers offering ATM services for the WAN/MAN environment include AT&T, Bell Atlantic/GTE, MCI WorldCom/UUNET, Qwest/US WEST, and Sprint. These carriers all offer high-performance services with minimal transit delays, and some of them offer ATM-to–frame relay services as an option as well, allowing multiple remote sites connected by frame relay to have their links aggregated into a single fat ATM pipe.

Marconi is the leading vendor of ATM switching equipment, with a 30 percent share of the market in 1999. Cisco Systems came second with a 25 percent share and has lately been focusing its research and development on packet-over-ATM, the next generation of ATM technologies. Other switch vendors offering ATM modules include Nortel Communications and Enterasys.

The region of the world that currently has the highest investment in ATM technologies is the Asia/Pacific region, where leased lines are expensive and ATM is seen as an affordable solution for the needs of the corporate WAN. By contrast, in North America the cost of leased lines is lower, making carrier-based ATM services unattractive and tending to drive large companies to running ATM over their own private circuits.

Prospects

ATM was once hailed as a revolutionary technology superior to Ethernet and essential for enterprises seeking "convergence," that is, the transmission of voice, video, and data over network backbones. However, its growth in deployment has been hindered by the high cost of ATM equipment and the complexity of implementing and managing it. Meanwhile, bandwidth supported by Ethernet has continued to grow, with the result that few enterprises are contemplating the deployment of new ATM backbones, with most favoring GbE instead. The early dream of corporate ATM networks stretching from the server room to the desktop has all but vanished.

ATM's largest installed base remains in telcos, and ATM or SONET/ATM remains the standard high-speed networking solution for these companies. Most MANs deployed by carriers are still ATM, and attempts by GbE to encroach on this territory have been hindered by the still nascent QoS features currently available for Ethernet. With the advent of 10 GbE, however, the picture may change as new carriers such as Yipes (*www.yipes.com*) move into the MAN space offering enterprises end-to-end Ethernet across the WAN. The long-distance carrier market, however, is destined to remain purely ATM for the foreseeable future, and most Incumbent Local Exchange Carriers (ILECs) have invested too heavily in ATM technologies for them to easily make the switch to 10 GbE.

ATM has received a boost in the last couple of years through increasing deployment of business and residential

Digital Subscriber Line (DSL) for providing Internet access to the customer premises. Many local telcos aggregate DSL traffic from subscribers into ATM pipes for transport to their backbone ATM carriers. However, DSL is itself facing stiff competition from cable modem providers, and which technology will win out is unclear.

The greatest threat to ATM's survival in the industry is the development of QoS mechanisms for IP traffic. Standards such as Multiprotocol Label Switching (MPLS) and Differentiated Services (DiffServ) have shown some initial promise but cannot compete at this point with ATM, which is still king of the QoS hill. Solutions such as 10 GbE may succeed by simply throwing bandwidth at the problem, but ultimately incorporating QoS into IP is essential if the vision of enterprise convergence is to be attained.

Notes

A number of different approaches are available for building IP internetworks with ATM backbones. These include

- **Classical IP (CIP):** Based on RFC 1577, this supports only the IP protocol and requires a special Address Resolution Protocol (ARP) Server to handle the broadcasts required to support IP (ATM does not support broadcasts because it is connection-oriented in nature). When CIP is deployed over ATM WAN connections using permanent virtual circuits, it is called CIP over PVC.
- **LANE (LAN Emulation):** Lets you build bridged virtual LAN segments for enabling an ATM network to emulate an Ethernet or Token Ring network. LANE is an early solution developed by the ATM Forum.
- **MPOA (Multiprotocol Over ATM):** Provides a virtual router for creating virtual IP subnets over ATM. MPOA is a more recent initiative of the ATM Forum.
- **MPLA (Multiprotocol Label Switching):** A technology developed by the Internet Engineering Task Force (IETF) for a label-based routing system for carrying IP and other traffic over ATM.

For more information on each of these technologies, see their respective articles elsewhere in this book.

ATM can also be used as the underlying technology for FDDI.

Microsoft Windows 2000, Windows XP, and Windows .NET Server support direct connectivity to ATM networks with up to four ATM adapters in a single computer.

For More Information

A good source of information on current developments in ATM technology is the ATM Forum (*www.atmforum.com).*

See Also: *ATM Forum, Gigabit Ethernet (GbE), LAN Emulation (LANE), Multiprotocol Label Switching (MPLS), Multiprotocol over ATM (MPOA), quality of service (QoS)*

asynchronous transmission

A form of data transmission in which the transmitting and receiving stations do not explicitly coordinate their transmissions with each other.

Overview

Asynchronous transmission (async) is used in serial transmission for modems and other telecommunication devices. Data is transmitted as streams of bytes terminated by start and stop bits, and the transmitting station can wait an arbitrary period of time between transmissions. This contrasts with synchronous transmission (sync), in which a timing or clocking mechanism is used to ensure a steady flow of data between the devices.

In asynchronous communication, only about 80 percent of the transmitted bits actually contain data, while the other 20 percent contain signaling information in the form of start and stop bits. Each data frame starts with a start bit and ends with a stop bit, with data bits in between. When the receiving station receives a start bit, it knows that pure data will follow. When it receives a stop bit, it knows the data frame has ended and waits for the next one.

Asynchronous transmission is essentially character-based with additional bits between characters to enable synchronization and error correction. An optional parity bit for error checking can be located immediately before the stop bit in each frame. With parity correction, an 8-bit character requires 3 bits of control information (start, stop, and parity bits), which means an actual overhead of 3/8, or 38 percent.

Asynchronous communication is not synchronized by a timer mechanism or clock, and asynchronous devices are not bound to send or receive information at an exact transmission rate. Instead, the sender and receiver negotiate transmission speeds based on hardware limitations and the need to maintain a reliable flow of information. Asynchronous transmission is mainly suitable for low-speed transmission, but speeds can also be increased by using data compression.

Notes

Cisco routers may use any of four different kinds of async ports:

- RJ-45 jack for standard console and aux ports.
- DB-25 serial connector for Cisco 4000 series routers.
- DB-60 connector, switchable from sync to async using Internetwork Operating System (IOS).
- 68-pin Small Computer System Interface (SCSI) II connector for providing eight serial ports (acts as a serial port concentrator) and typically found on access servers.

See Also: *synchronous transmission*

ATDnet

Stands for Advanced Technology Demonstration Network, a high-speed test bed network that ispart of SuperNet, the cross-country network funded by the Next Generation Internet (NGI) program.

See: *Advanced Technology Demonstration Network (ATDnet)*

ATM

Stands for Asynchronous Transfer Mode, a high-speed, broadband transmission data communication technology based on packet switching and multiplexing technologies, and used by telcos, long distance carriers, and campus-wide backbone networks to carry integrated data, voice, and video information.

See: *Asynchronous Transfer Mode (ATM)*

ATM Adaptation Layer (AAL)

An Asynchronous Transfer Mode (ATM) protocol that performs the functions of the Open Systems Interconnection (OSI) model's Data Link layer.

Overview

The function of the ATM Adaptation Layer (AAL) is to adapt the ATM Layer protocol to high-level networking protocols above it. The AAL consists of two sublayers:

- **Convergence Sublayer (CS):** Top sublayer, responsible for performing functions relating to the class of service specified for the traffic being transported over ATM.
- **Segmentation And Reassembly (SAR):** Bottom sublayer, responsible for breaking up high-level data streams into 48-byte segments for packaging into ATM cells. If there's insufficient data to form a cell, SAR pads the cell to make a full cell.

The ATM Adaptation Layer supports five different AAL protocols from AAL 1 through AAL 5, with the last one being the most widely used.

See Also: *Asynchronous Transfer Mode (ATM)*

ATM Forum

An international not-for-profit organization dedicated to promoting the deployment of Asynchronous Transfer Mode (ATM) products and services.

Overview

The ATM Forum was founded in 1991 by a consortium of four companies (Cisco Systems, Northern Telecom [now Nortel Communications], Sprint Corporation, and Net/Adaptive). The ATM Forum's goal is to help steer the course of the development of ATM standards and technologies with the cooperation of over 600 industry partners (the Forum is itself not a standards body but instead develops specifications and submits them to the International Telecommunication Union [ITU]).

The ATM Forum works by committees, some of which include

- **The Technical Committee:** Works with other standards bodies such as the ITU to develop and evolve ATM standards and ensure interoperability between them. A number of different working groups are under this committee's umbrella.

- **Market Awareness Committees:** Three of these committees cover the North America, Europe, and Asia/Pacific regions.
- **The User Committee:** This consists of ATM users and allows them to provide input to the other committees based on their real-world experience of using ATM.

The ATM Forum also has an Ambassador Program for providing speakers knowledgeable about ATM for conferences and other events. The ATM Forum also has a newsletter called "53 Bytes," which helps keep people informed of developments in the ATM field.

For More Information

The ATM Forum can be found at *www.atmforum.com.*

See Also: *Asynchronous Transfer Mode (ATM)*

ATM over SONET

Also called ATM/SONET, a data transmission technology in which Asynchronous Transfer Mode (ATM) cells are transmitted over Synchronous Optical Network (SONET) circuits.

Overview

ATM over SONET is a technology used by telecommunications carriers when individual circuits have to carry multiple different kinds of traffic such as voice, video, Internet Protocol (IP), and so on. Implementing ATM over SONET adds an additional 5 bytes of overhead to 53-byte ATM cells, so this is done only when necessary. If a SONET circuit carries only one type of traffic—such as IP packets or circuit-switched voice—the ATM layer is not required, thus saving the additional overhead.

ATM over SONET can be implemented either with or without Automatic Protection Switching (APS), the traditional SONET ring-based redundancy technology.

See Also: *Asynchronous Transfer Mode (ATM), Synchronous Optical Network (SONET)*

ATM/SONET

Stands for ATM over SONET, a data transmission technology in which Asynchronous Transfer Mode (ATM) cells are transmitted over Synchronous Optical Network (SONET) circuits.

See Also: *ATM over SONET*

attenuation

The loss of signal strength over long distances when signals travel along cabling.

Overview

Attenuation values for actual cables are measured in units of decibels (dB)—a standard measurement value used in communication for expressing the ratio of two values of voltage, power, or some other signal-related quantity. For example, a drop of 3 dB corresponds to a decrease in signal strength of 50 percent or 2:1, while a drop of 6 dB corresponds to a decrease of 75 percent or 4:1. Attenuation values for cabling media are expressed in units of decibels per 1000 feet, which express the amount of attenuation in decibels for a standard 1000-foot (305-meter) length of cabling composed of that medium.



Attenuation. *Attenuation of analog and digital signals.*

Copper cabling has much greater attenuation than fiber-optic cabling, which makes copper suitable only for relatively short cable runs. Typical attenuation values for copper Category 5 (Cat5) cabling vary with frequency and are shown in the following table. Attenuation for lower-grade cable is slightly higher.

Attenuation Values for Copper Cat5 Cabling

Signal Frequency	*Attenuation*
4 megahertz (MHz)	13 dB/1000 feet
10 MHz	20 dB/1000 feet
20 MHz	28 dB/1000 feet
100 MHz	67 dB/1000 feet

Notes

Attenuation is caused by signal absorption, connector loss, and coupling loss. To minimize attenuation, use high-grade cabling such as enhanced category 5 (Cat5e) cabling. Also try to minimize the number of connector devices or couplers, ensuring that these are high-grade components as well. When a signal attenuates a large amount, the receiving device might not be able to detect it or might misinterpret it, therefore causing errors.

attenuation to crosstalk ratio (ACR)

The ratio of the received strength of a signal on a pair of wires to the amount of crosstalk between the wires.

Overview

The attenuation to crosstalk ratio (ACR) is calculated as the difference between the attenuation value and the near-end crosstalk value at a specific frequency. This is because both attenuation and crosstalk are usually expressed in units of decibels for cabling media. The decibel scale is logarithmic in nature, which means that a difference in decibel values corresponds to a ratio of actual signal voltage or power levels.

The higher the ACR for a given cable, the less chance of signal errors. For copper Category 5 (Cat5) cabling, the ACR value is typically about 10 decibels (dB), at a frequency up to about 100 megahertz (MHz). This value decreases slightly with increasing frequency until crosstalk and attenuation values converge, at which point transmission becomes error prone and the cabling ineffective for communication.

See Also: *attenuation, crosstalk*

attrib command

A Microsoft Windows command that can be used to display and modify the attributes of files and directories.

Overview

You can use the attrib command to display and modify the archive, system, hidden, and read-only attributes that can be assigned to files and directories. For example, if you need to manually modify the boot.ini file on a machine running Windows 2000, you can use the attrib command to remove its read-only, hidden, and system attributes.

Examples

```
attrib -r -h -s boot.ini
```

This removes the read-only, hidden, and system attributes from the boot.ini file, allowing you to edit the file manually.

See Also: *attribute (file system)*

attribute (file system)

A type of marker that can be set or cleared for files on a file system such as NTFS file system (NTFS).

Overview

On NTFS, attribute markers determine whether a file is

- Read-only, meaning that it cannot be modified
- Hidden, meaning that the file will not appear when its parent directory is listed at the command line
- System, meaning that the file is a critical operating system file and should not be moved or modified
- Archived, meaning that the file has been backed up
- Encrypted using Microsoft Corporation’s Encrypting File System (EFS) (Windows 2000, Windows XP, and Windows .NET Server only)
- Compressed (Windows 2000, Windows XP, and Windows .NET Server only)

To view or modify the attributes of a file, open the file’s property sheet and check or clear the appropriate check box.

Notes

The term *attribute* can also refer to other more granular file system information, such as time stamps, file size, or link counts.

See Also: *attrib command*

attribute (Active Directory)

A property of an object in Active Directory directory service.

Overview

Attributes are information relating to objects stored in Active Directory. For example, a user class object is composed of attributes, such as a First Name attribute for a user account object.

Attributes define the actual characteristics of objects in Active Directory. Every class of objects has its own defining set of attributes. Different objects within this class are distinguished by the values of their attributes. Some attributes, such as the First Name attribute for a user account object, must have a value assigned to them when they are created. Other attributes, such as Phone Number, can optionally be left unvalued.

Each attribute in Active Directory is defined only once and can be used for many different object classes. All objects of the same type have the same set of attributes. Different objects of the same type are distinguished by different attribute values. It is therefore the values of the attributes of a particular object that make that object unique in Active Directory.

Attributes are defined in a special portion of Active Directory. An attribute definition includes

- The syntax (type of information) of the attribute, such as integer, date, or string
- Whether the attribute is single-valued or multivalued

Each syntax type is specified by an object identifier, which is a globally unique identifier (GUID) issued by the International Organization for Standardization (ISO). The allowable syntax types for attributes of objects in Active Directory are shown in the following table.

Allowable Syntax Types for Object Attributes

Syntax	*Object Identifier*	*Description*
Undefined	2.5.5.0	Not a legal syntax
Distinguished name	2.5.5.1	The fully qualified name of an object in the directory
Object identifier	2.5.5.2	Identifies an object
Case-sensitive string	2.5.5.3	Differentiates uppercase and lowercase
Case-insensitive string	2.5.5.4	Does not differentiate uppercase and lowercase
Print case string	2.5.5.5	Printable string
Numeric string	2.5.5.6	A sequence of digits
OR name	2.5.5.7	An x400 e-mail address
Boolean	2.5.5.8	TRUE or FALSE
Integer	2.5.5.9	A 32-bit number
Octet string	2.5.5.10	A string of bytes
Time	2.5.5.11	The number of seconds elapsed since 1/1/1970
Unicode	2.5.5.12	Wide string
Address	2.5.5.13	Internal
Distname-address	2.5.5.14	Internal
NT security descriptor	2.5.5.15 66	Microsoft Windows NT Security Descriptor
Large integer	2.5.5.16	A 64-bit number
Security identifier (SID)	2.5.5.17 4	SID

See Also: *Active Directory, Active Directory schema*

ATU-C

Stands for Asymmetric Digital Subscriber Line (ADSL) Transceiver Unit, Central Office end, an ADSL modem that terminates a subscriber's ADSL connection at the ADSL provider's Central Office (CO).

See Also: *Asymmetric Digital Subscriber Line (ADSL)*

ATU-R

Stands for Asymmetric Digital Subscriber Line (ADSL) Transceiver Unit, remote terminal end, an

ADSL modem that terminates a subscriber's ADSL connection at the customer premises.

See Also: *Asymmetric Digital Subscriber Line (ADSL)*

auditing

The process of tracking and monitoring actions performed on servers or networks for security purposes.

Overview

Auditing is an important component of a general security policy for a corporate network. Auditing can be used to detect attempts at unauthorized access to network resources and to track the usage of shared resources. Auditing creates a record of which files have been accessed, who has logged on to the network, who has attempted to use a shared resource, and so on. Specifically, auditing records information in the security log about

- What action was performed
- Who performed the action
- When the action occurred
- Whether the action succeeded or failed

Notes

Microsoft Windows 2000, Windows XP, and Windows .NET Server record two kinds of auditing information in the security log:

- **Success audits:** Symbolized by keys and usually used to track resource usage for capacity and resource planning
- **Failure audits:** Symbolized by padlocks and usually used to monitor network resources for unauthorized access attempts

See Also: *Audit policy, event, security log*

Audit policy

A policy established on a Microsoft Windows 2000 or Windows .NET Server domain that specifies the kinds of security-related events that will be recorded in the security log.

Overview

The following table indicates the kinds of events that can be audited in Windows 2000, Windows XP, and Windows .NET Server.

Events That Can Be Audited

Type of Event	*Description*
Logon and logoff	Users logging on and off and forming network connections
File and object access	Users accessing a file, folder, or printer on a network
Use of user rights	A right has been exercised—for example, backing up files and directories
User and group management	An account has been modified, created, or deleted
Security policy changes	A change has been made to an Audit policy, a trust relationship, or user rights
Restart, shutdown, and system	The system has been shut down or restarted, or system security has changed
Process tracking	A process has been started or stopped, or some related activity has occurred

Notes

Be careful when enabling auditing for File And Object Access or Process Tracking because logging these events can generate a large amount of overhead on your system, especially when auditing for successes. To audit access to a file, folder, or printer, first enable File And Object Access auditing in your Audit policy, and then access the Security tab on the object's property sheet.

See Also: *auditing, event, security log*

AUI connector

Stands for Attachment Unit Interface connector, a standard 15-pin connector device for thicknet.

Overview

The AUI connector on the free end of a 10Base5 drop cable attaches to the DB15 connector on the network interface card (NIC). The NIC has an AUI port connector for connecting the drop cable. The other end of the drop cable typically connects to a transceiver. The transceiver is then joined to the thicknet cabling using a vampire tap that pierces the cable jacket and insulation to make a connection.

See Also: *connector (device), Ethernet*

Authenticated Users group

A built-in group in Microsoft Windows 2000, Windows XP, and Windows .NET Server for controlling access to resources.

Overview

The Authenticated Users group is similar to the built-in Everyone group, except that anonymous logon users are never members of the Authenticated Users group. The built-in security identifier (SID) for this group is S-1-5-11.

The Authenticated Users group can be used to provide additional security when running Microsoft Internet Information Services (IIS) because the anonymous user account has the ability to enumerate share names and list domain usernames. Using the Authenticated Users group provides an additional layer of security and is one way to restrict access to objects in the file system.

You should generally use the Authenticated Users group instead of the Everyone group if you want to carefully control anonymous access to your network resources.

See Also: *built-in group*

Authentication Header (AH)

A protocol in the IPSec suite of protocols that handles authentication of Internet Protocol (IP) traffic.

Overview

The Authentication Header (AH) header immediately follows the IP header of an IP packet and includes the following fields:

- **Next Header (1 byte):** This field indicates which protocol (Transmission Control Protocol [TCP] or User Datagram Protocol [UDP]) is used in the payload immediately following the AH header.
- **Payload Length (1 byte):** This field indicates the length of the payload following the AH header.
- **Reserved Area (2 bytes):** Not currently used.
- **Security Parameters Index or SPI (4 bytes):** Specifies which security protocols are being used for the transmission of the packet.
- **Sequence Number (4 bytes):** Indicates the position of the packet in the sequence of packets having the same SPI.
- **Authentication Data (variable):** Contains the digital signature for the packet.

Notes

AH usually uses MD5 as its encryption algorithm, but other more secure encryption algorithms can also be used.

See Also: *IPsec*

authentication protocol

Any protocol used for validating the identity of a user to determine whether to grant the user access to resources on a network.

Overview

Authentication protocols can be classified according to how the credentials are passed over the network. Some common kinds of authentication protocols include

- **Anonymous access:** This method is supported by Microsoft Internet Information Services (IIS) and allows anonymous users on the Internet access to Web content on your server.
- **Basic authentication:** This method transmits passwords as clear text and is often used in Unix networks and for File Transfer Protocol (FTP) services. It is also supported by IIS.
- **Digest authentication:** This method hashes (digests) the user's password before transmitting it, making it more secure than Basic authentication. Digest authentication is part of the Hypertext Transfer Protocol (HTTP) 1.1 protocol and is also supported by IIS.
- **Windows NT Challenge/Response:** This is the standard secure authentication method for Windows NT domains. In IIS this protocol is referred to as Integrated Windows authentication. Also called Windows NT Lan Manager or NTLM.

- **Kerberos v5:** This is the standard authentication security protocol for Windows 2000 and Windows .NET Server domains.
- **X.509 Client Certificate authentication:** This is used in conjunction with Secure Sockets Layer (SSL) and digital certificates and is also supported by IIS.

Notes

On a Microsoft Windows NT, Windows 2000, or Windows .NET Server network, authentication can be handled in one of two ways:

- When logging on to a member server or stand-alone workstation, authentication is performed by the member server or workstation itself using its local Security Accounts Manager (SAM) database.
- When logging on to a domain, authentication is performed by a domain controller on the network.

See Also: *anonymous access, Basic authentication, Kerberos, Windows NT Challenge/Response Authentication*

authentication provider

In Internet Connection Services for Microsoft Remote Access Service (RAS), a database for providing AAA (authentication, access, and accounting) information for the users in a given realm.

Overview

An authentication provider is a server that isused by Internet Authentication Service (IAS) to map a Remote Authentication Dial-In User Service (RADIUS) authentication request to a database containing user credentials. The authentication provider can verify or deny whether the individual exists in the database and return this information to the IAS server.

Choices for authentication providers are

- A Microsoft Windows NT, Windows 2000, or Windows .NET Server domain controller
- A Local Users file on the IAS server
- An open database connectivity (ODBC)–compliant database
- A Microsoft Commercial Internet System (MCIS) membership database

See Also: *AAA*

Authenticode

A Microsoft security technology that certifies the identity of the publisher of software to ensure the software has not been tampered with.

Overview

To use Authenticode, an Internet software publisher first obtains a digital certificate from a certificate authority (CA). They then use Authenticode signing tools to digitally sign the application.

When a user tries to download the application from the Internet, client-side Authenticode software in Microsoft Windows displays the publisher's certificate information to help the user make a more informed decision about whether to install the software on his or her machine.

Authenticode can be used to sign Microsoft ActiveX controls, .cab files, Java applets, or any other executable files.

See Also: *security*

Authorized Academic Training Provider (AATP)

A Microsoft training program offered to accredited academic institutions.

Overview

An Authorized Academic Training Provider (AATP) is an educational institution approved for delivery of training on Microsoft platforms and applications. AATPs can include secondary schools, vocational schools, community colleges, and universities. Microsoft Corporation provides participating institutions with tools to facilitate courseware delivery that prepares students for Microsoft Certified Professional (MCP) certifications. This enables schools to serve their communities by educating future employees to fill demands for technically certified computer professionals.

There's no fee for joining the AATP program. Some of the benefits of joining the program include the following:

- A 100-user software license received upon purchase of a Microsoft product—provided the product is the subject of a course being taught that uses a Microsoft Official Curriculum or Microsoft Approved Study Guides. Note that these licenses are for student and instructor use in the classroom only.
- Special academic pricing on Microsoft Official Curriculum and Microsoft Approved Study Guides.
- Online course outlines, evaluation tools, curriculum materials, certification fact sheets, and preparatory exams.
- Access to the private AATP Internet site.

Notes

An organization or institution cannot participate simultaneously in both the AATP and Certified Technical Education Center (CTEC) programs.

For More Information

Find out more about Microsoft's AATP program at *www.microsoft.com/education/aatp/default.asp*.

See Also: *Certified Technical Education Center (CTEC), Microsoft Certified Professional (MCP)*

auto-application

An application that can be automatically started on the user's computer by Microsoft Connection Manager (CM) after a connection is established.

Overview

Auto-applications automatically launch and close upon the start and end of a connection. This lets administrators configure services to trigger when users open their e-mail or Web browser.

You can specify auto-applications using a wizard that allows you to specify the name of the application, command-line switches or parameters, and other information.

An auto-application must be a complete program file. It cannot require other files to work, and it cannot be a self-extracting executable.

AutoComplete

A feature of Microsoft Internet Explorer that attempts to complete a partial Uniform Resource Locator (URL) entered into the browser's Address field.

Overview

When you begin to enter a URL, the AutoComplete function checks the browser's history folder for any URLs that match your partial URL and displays the closest match to what you have entered. This saves users from having to retype long URLs when attempting to revisit a site.

AutoComplete can be viewed as both an accessibility feature and a way to avoid time-wasting mistakes. If the URL that AutoComplete suggests for you is incorrect, just keep typing the URL you want.

AutoComplete is based on the same IntelliSense technology that is implemented in certain features of Microsoft Office, such as the AutoFill feature in Microsoft Excel.

Notes

If you clear your history folder, AutoComplete will not be able to function because it uses URLs stored in that folder. The longer you leave your history folder unemptied, the larger its contents become and the more effectively AutoComplete operates.

See Also: *Internet Explorer*

autodial

A feature of remote access in Microsoft Windows 2000, Windows NT, Windows XP, and Windows .NET Server that maps network resources to phonebook entries.

Overview

When a user or application tries to access a network resource, autodial automatically tries to establish a connection to the resource. To configure autodial in Windows 2000, go to Control Panel in My Computer, and then open Network And Dial-up Connections. Choose Dial-Up Preferences from the Advanced menu. On the Autodial tab, select the check box next to the location where you want to enable autodial, and then click OK. To configure AutoDial in Windows NT, use the User Preferences dialog box for your phonebook entry.

Notes

Certain actions will not trigger autodial. These include

- Pinging an Internet Protocol (IP) address. (Pinging a fully qualified domain name, however, will cause autodial to engage.)
- Using both a dial-up and a local area network (LAN) connection. (AutoDial engages only after an attempt to connect over the LAN has failed.)

See Also: *remote access*

automatic logon

A logon process whereby the user gains access to the network through user credentials previously stored in the registry.

Overview

Automatic logon can be enabled on a machine running Microsoft Windows NT by editing the registry. Use registry editor (Regedit.exe) to open the following key:

```
HKEY_LOCAL_MACHINE
     \Software
         \Microsoft
             \Windows NT
                 \CurrentVersion
                        \Winlogon
```

and modify or create the following REG_SZ type values:

- DefaultDomainName
- DefaultUserName
- DefaultPassword
- AutoAdminLogon

Set AutoAdminLogon equal to 1 to enable automatic logon.

You can bypass the automatic logon process by holding down the Shift key upon startup or logoff.

Notes

Use extreme care when making changes to the registry, as improper use of Registry Editor can make your system unbootable.

See Also: *interactive logon*

Automatic Private IP Addressing (APIPA)

A feature of Microsoft Windows 2000, Windows XP, and Windows .NET Server that enables machines to be automatically assigned Internet Protocol (IP) addresses without the use of Dynamic Host Configuration Protocol (DHCP).

Overview

Automatic Private IP Addressing (APIPA) is designed for use on small networks where fewer than 25 machines are deployed. Such networks are too big to easily manage using static (manual) IP addressing and too small to warrant the use of a dedicated DHCP server for automatic IP addressing. APIPA was developed as an alternative to these two addressing methods.

If a Windows 2000, Windows XP, or Windows .NET Server client starts up and is configured for DHCP but finds no DHCP server to lease it an address, APIPA randomly assigns a machine an IP address. This randomly assigned address is in the range 169.254.*x*.*y*, which is reserved by Microsoft Corporation for this purpose and is not used on the Internet (in case your client has a direct connection to the Internet). A subnet mask of 255.255.0.0 is additionally assigned to the client.

Notes

One disadvantage of using APIPA is that machines whose addresses have been assigned using APIPA periodically poll the network for the presence of a DHCP server. Should a DHCP server be found, the machine yields its APIPA-generated address and leases a new address from the DHCP server. APIPA networks are thus particularly susceptible to interference from rogue DHCP servers, and APIPA should not be used in mission-critical or enterprise networks. You can disable this polling feature, however, by editing the registry.

APIPA is also available on the Windows 98SE platform.

See Also: *Dynamic Host Configuration Protocol (DHCP), IP address*

Automatic System Recovery (ASR)

A feature of Microsoft Windows 2000, Windows XP, and Windows .NET Server that allows you to restore your system in the event of hard disk failure or corruption of system files.

Overview

Automatic System Recovery (ASR) is designed to replace the emergency repair disk (ERD) of Windows NT as the main tool for restoring systems after boot failures. ASR integrates the processes of repair, backup, and restore into a single recovery solution in the event of a disaster.

To use ASR, you must first configure it by running the Disaster Recovery Preparation Wizard, which is part of the Backup utility in Windows 2000, Windows XP, and Windows .NET Server. The resulting ASR disk contains configuration information that will be critical if you need to recover your system as a result of system volume damage or corruption. If you need to reinstall the system software, the ASR disk enables you to bring the system to the same configuration it had before the disaster.

Notes

Always run the Automatic System Recovery Wizard immediately before and after you make any changes to your system configuration using the Disk Management tool. If you do this, you will be able to return your system to the stable configuration that existed prior to your change.

See Also: *Windows 2000*

Automatic Version Synchronization (AVS)

A feature of the Microsoft Internet Explorer Administration Kit (IEAK).

Overview

Automatic Version Synchronization (AVS) runs each time the IEAK administrator runs the IEAK Wizard and checks Microsoft Corporation's Web site for updates to Microsoft Internet Explorer. These updates are automatically downloaded and the administrator can distribute them to users throughout the enterprise.

Automation

A Microsoft technology that enables applications to expose their functionality to other applications.

Overview

Automation, formerly known as OLE Automation, is based on the Component Object Model (COM) and allows run-time binding of components. Automation is used exclusively by scripting languages, such as Microsoft Visual Basic for Applications (VBA), Microsoft Visual Basic Scripting Edition (VBScript), and Microsoft JScript, to access COM components that support Automation. The advantage of Automation is that it allows various languages to access COM components at run time. The drawbacks to Automation are that it is slow and that compile-time data type checking cannot be performed.

An application that exposes its functionality through Automation is called an Automation server. An application that communicates with the server through Automation is called an Automation controller or Automation client.

An Automation server is a COM component that typically implements the IDispatch interface. An Automation controller is a client that communicates with the Automation server, typically using IDispatch. IDispatch is a COM interface that allows a client to indirectly access all of the component's exposed methods and properties. Therefore, IDispatch enables a client to discover and access all a component's various methods and properties at run time through a single interface.

Notes

In the past, Automation required communication using the IDispatch interface. Now the term Automation is more generic and refers to the programmability of an application or component.

See Also: *Automation controller, Automation server*

Automation client

Also called an Automation controller, a client that accesses the functionality of an Automation server.

See: *Automation controller*

Automation controller

A client that accesses the functionality of an Automation server.

Overview

Automation is a way for one application to manipulate the exposed objects (properties and methods) of another application. Automation controllers are client applications that can manipulate the exposed objects of another application called an Automation server. Examples of Automation controllers include Microsoft Word, Microsoft Excel, and Microsoft Visual Basic.

There are two kinds of Automation clients:

- Clients that have static information about the properties and methods of the Automation server bound to them at compile time.
- Clients that dynamically obtain information about the properties and methods of the Automation server at run time. These clients do this by querying the Automation server's IDispatch interface.

See Also: *Automation, Automation server*

Automation server

A Component Object Model (COM) component that exposes its functionality to other applications.

Overview

An example of an Automation server might be a word processing program that can expose its spell-checking functions so that Automation controllers can access them. This allows the functionality of one program (the Automation server) to be used by other programs (the Automation clients or controllers).

An Automation server typically implements the IDispatch interface.

See Also: *Automation, Automation controller*

auto naming

A feature of Microsoft Exchange Server that enables administrators to configure how e-mail aliases and other information are automatically generated when mailboxes are created.

Overview

Using auto naming, you could, for example, automatically generate any of the following e-mail aliases for Jeff Smith's mailbox:

- JSmith
- JeffS
- JS

You could also devise some other custom naming scheme. These e-mail aliases then would be combined with the Domain Name System (DNS) domain name of the Exchange organization to form the user's standard e-mail address. For example, if the domain name of the company is northwind.microsoft.com, JSmith would be combined with it to form the e-mail address JSmith@northwind.microsoft.com.

See Also: *Exchange Server*

autonomous system (AS)

A group of Internet Protocol (IP) networks administered under a single administrative (routing) policy.

Overview

An autonomous system (AS) is part of the routing infrastructure of a large IP internetwork. An AS is essentially a portion of a large internetwork whose routing is administered by a single authority. Typically, this means one AS per enterprise network. An autonomous system can be under the authority of a particular corporation or institution, or it can be defined by the uniform use of a particular routing protocol such as Open Shortest Path First (OSPF).

The Internet is the de facto example of a large IP internetwork divided into different autonomous systems such as AT&T Enhanced Network Services (formerly AT&T CERFnet), SprintLink, AlterNet, and so on. These autonomous systems are connected by the Internet's core routers, which use an exterior routing protocol called Border Gateway Protocol (BGP) for communication among themselves.

Each autonomous system must be identified using a globally unique number called an autonomous system number (ASN). A BGP uses ASNs to avoid routing loops and implement policy-based routing on the Internet backbone. ASNs are required for autonomous systems connected to the Internet, and are obtained from Internet numbers registries such as the American Registry for Internet Numbers (ARIN) and the Asian-Pacific Network Information Center (APNIC). Autonomous systems exchange exterior routing information with one another by using these ASNs to identify themselves to other autonomous systems. Autonomous systems can be further subdivided into routing domains (areas) for more granular routing.

There are three basic types of autonomous systems:

- **Stub AS:** This AS is connected to only one other AS. A corporate network that isconnected to an AS is considered to have the same AS number as the AS it is connected to.
- **Transit AS:** This AS is connected to more than one other AS and can be used for transit traffic between autonomous systems. A Transit AS is usually administered by a large Internet service provider (ISP).
- **Multihomed AS:** This AS is connected to more than one other AS but does not let transit traffic from another AS pass through itself. An example might be a corporate network with several Internet connections to different ISPs.

See Also: *autonomous system number (ASN), Border Gateway Protocol (BGP), routing*

autonomous system number (ASN)

A unique number used to identify an autonomous system (AS), that is, a network that can exchange exterior routing information with neighboring networks.

Overview

Every autonomous system (AS) connected to the global Internet must have a uniquely assigned autonomous system number (ASN). This ASN is required so that your AS can identify itself to other ASs on the Internet and exchange exterior routing information with their routers. ASNs are 16-bit numbers that are assigned to networks by the American Registry for Internet Numbers (ARIN). As of 2000 there were more than 12,000 ASNs assigned to public and enterprise networks, and the number is rising rapidly as more and more enterprises implement multihoming, the use of multiple ISPs for providing Internet access for their networks. To obtain an ASN, contact ARIN and pay the one-time registration fee and the annual maintenance fee. Note that ISPs are not charged the annual maintenance fee for their ASNs.

See Also: *autonomous system (AS), multihoming*

autosensing

Technology by which a local area network (LAN) device can determine the characteristics of an attached device and configure itself accordingly.

Overview

As an example, a port on an autosensing 10/100-Mbps Ethernet switch can automatically detect whether the attached station has a 10-megabits per second (Mbps) or 100-Mbps network interface card (NIC). This is a useful feature that allows a combination of 10BaseT and Fast Ethernet connections in a single LAN.

Often during migration and system upgrades you will find a combination of slower, legacy networking equipment and faster, more modern devices. These devices might need to coexist for months or years, depending on the budget available for upgrades. Using autosensing hubs and switches makes this coexistence cheap and simple and allows a full upgrade to the faster configuration later—without purchasing additional equipment.

See Also: *hub, Ethernet switch*

availability

The degree to which network resources operate without interruptions resulting from scheduled maintenance or unexpected failure.

Overview

Availability has become an important issue in the modern Internet economy in which online electronic businesses are made or broken on the basis of reliable, fault-tolerant technologies.

Clustering is one tool for ensuring continuous uninterrupted 24 x 7 x 365 availability of network resources. Windows 2000, Windows XP, and Windows .NET Server include support for clustering that provides the basic platform for building high-availability e-business and electronic commerce applications that can compete in today's world. Cluster services can automatically detect when an application or server fails and quickly restart it on the surviving cluster node. Users connected to the server will experience only a brief pause in service.

See Also: *24 x 7, clustering*

AVS

Stands for Automatic Version Synchronization, a feature of the Microsoft Internet Explorer Administration Kit (IEAK).

See: *Automatic Version Synchronization (AVS)*

AWG

Stands for American Wire Gauge, a specification for the diameter of conducting wires.

Overview

The higher the AWG number, the thinner the wire. Category 5 (Cat5) cabling is usually AWG 24 wire (0.020 inch or 0.511 millimeter in diameter), while thicknet generally uses AWG 12 wire (0.080 inch or 2.050 millimeters in diameter). Twisted-pair telephone wire at the customer premises is typically 24 or 26 gauge, with 24 giving better performance for high-speed services such as Asymmetric Digital Subscriber Line (ADSL).

The table below shows some of the various AWG gauges for different diameters of wires. Note that the thinner the wire, the higher its electrical resistance and hence the shorter the transmission distance (because resistance varies inversely with thickness).

AWG Gauges for Various Diameters of Wires

AWG Gauge	*Diameter (Inches)*	*Diameter (Millimeters)*
12	0.080	2.050
14	0.064	1.630
16	0.051	1.290
18	0.040	1.020
20	0.032	0.813
22	0.025	0.643
24	0.020	0.511
30	0.010	0.254

AXFR request

A type of Domain Name System (DNS) request in which a secondary DNS server requests the update of information from a master DNS server.

Overview

An AXFR request always results in a full zone transfer. This can take time and use considerable network bandwidth if the zone files are large.

An alternative to AXFR is the incremental zone transfer protocol described in RFC 1995. Incremental zone transfers use an IXFR request and transfer only those portions of the zone file that have been changed.

Incremental zone transfers are supported by the DNS service running on Microsoft Windows 2000 and Windows .NET Server.

See Also: *Domain Name System (DNS)*

B

B2B

Stands for business-to-business and refers to e-commerce between different companies that have some sort of partnering arrangement, in contrast to B2C, or business-to-consumer, relationships in which individuals or companies purchase the products or services of another company.

Overview

Companies traditionally negotiate special business relationships with other companies that can provide them with the raw materials, tools, and services that they need for the success of their businesses. Such relationships are known as a value chain, which typically includes activities such as obtaining raw materials, processing these materials into finished products, shipping products to distributors, servicing customers, and marketing. To support a value chain, several business activities are essential, including procurement, research and development, manufacturing, and managing of human resources, operations, finances, and customer needs.

B2B is basically the use of the Internet to streamline and automate these business processes to enhance the value chain. This can result in streamlined business-cycle processes that are faster-to-market and in substantial cost savings by eliminating traditional paper-based invoicing and communications used in procurement channels. B2B can benefit companies in many different scenarios, including corporate purchasing, supply chain trading, and direct marketing.

Architecture

The technologies at the heart of B2B are the Internet, virtual private networks (VPNs) and Extensible Markup Language (XML). The Internet now provides a ubiquitous communications infrastructure that allows companies anywhere to connect with each other for exchange of business information. This can be accomplished through a variety of means, including leased lines, xDSL, dial-up modem connections, and wireless satellite links. Just as the existing public switched telephone network (PSTN) catalyzed the explosive growth of fax technology after it was introduced, the Internet is revolutionizing the way business partners communicate to buy and sell goods and services.

VPNs are a popular technology that is widely used to secure communications over the Internet. Without the Internet itself, business partners would have to purchase costly leased lines for secure, reliable electronic communications between them, and many companies still use leased lines to support their Electronic Data Interchange (EDI) platforms. Using VPNs, however, companies can send these communications securely over the public Internet, allowing them to reduce costs by eliminating leased lines in favor of better-positioned technologies such as xDSL.

XML is a third component of most emerging B2B solutions platforms, as it provides a standardized way of encoding business communications for transmission over the Internet.

In addition to these technologies, other elements of successful B2B relationships include establishing credit relationships between companies and building B2B technology into legacy systems.

An emerging standard that may help promote B2B overall is an initiative from Ariba, Microsoft, and IBM called Universal Description, Discovery, and Integration (UDDI). UDDI is a proposed directory service that will make it easier for companies to find business partners that offer specific types of goods and services.

Implementation

You can implement B2B in three basic ways: build a custom solution, buy a packaged solution, or lease services from an online marketplace.

Building a custom B2B solution in conjunction with business partners is an approach that is often taken by large companies that require custom solutions that are integrated deeply into their existing legacy business systems and that have pockets deep enough to implement this type of solution. The disadvantage is the longer time-to-market period required for realizing benefits from this solution, and with the rapidly changing Internet economy this is a concern that needs to be seriously addressed by enterprise e-implementers. B2B solution providers pursuing this market segment are basically pursuing a vertical market in which they will handle a small number of large clients with extensive integration needs.

Buying an off-the-shelf B2B solution is another approach that can take several forms, from purchasing and deploying a software platform for developing B2B solutions such as Microsoft BizTalk Server to hiring a B2B consulting company to implement its own off-the-shelf solution. This approach is often taken by mid-sized companies with reduced capital availability and limited IT (information technology) resources, and especially so by dot-com startups seeking rapid time-to-market. A startup company might outsource all of their procurement needs to a B2B consulting service that will implement a packaged Web-based system for procurement and supply-chain management for them.

Leasing services from an existing B2B exchange is a third solution. Numerous online marketplaces supply B2B services for narrowly targeted market segments such as the food industry and the plastics industry. These B2B exchanges (or online marketplaces) provide packaged B2B solutions that include online catalog publishing services, secure transactions, direct marketing, and related services. An example is the food industry, where a B2B exchange can help grocery store chains manage procurement and speedy delivery of perishable goods.

A B2B exchange with a specific industry focus such as this is often called an Industry-Sponsored Marketplace (ISM), and a B2B solution provider with a more general focus of providing packaged B2B solutions for small-sized or mid-sized companies is generally referred to as a “pure player.” These providers are competing in a horizontal market—that is, trying to gain as many customers as they can—and most first-generation B2B marketplaces took this approach to growing their ventures. Many of them provide B2B services on a transaction-fee basis, though there’s movement away from this model toward flat-rate pricing that makes B2B costs more predictable for clients.

B2B exchanges come in all flavors, from online shopping portals such as the healthcare industry portal PointStore, to industry-partnered ventures in which several companies form a cooperative exchange such as Hyatt International Corporation and Marriott International’s Avendra marketplace for the hospitality industry, to pure-play independent B2B exchanges such as Chemdex for the chemical industry built on B2B software from Commerce One and Ariba. Of these different approaches, the most successful ventures are generally the cooperatives in which the narrow industry focus and high alignment with partner needs generate the best results.

Marketplace

Commerce One and Ariba are two major players in the B2B marketplace arena, and between them they have more than 500 corporate customers. Ariba has partnered with IBM and i2 Technologies to provide software and services, and Commerce One has done the same with SAP AG.

Some of the bigger players in the ISM market include

- **e2Open:** An online marketplace for high technology supported by IBM, Nortel Networks, and others.
- **Altrade:** A B2B exchange developed by Altra Energy Technologies for the energy industry that includes high-profile partners such as Dow Chemical Company and ExxonMobil Corporation and which did over $4 billion in trades in 1999.
- **Covisint:** An online supply-chain procurement marketplace being developed by the Big Three

automakers Ford Motors, General Motors, and DaimlerChrysler.

Companies that provide full-featured packaged B2B platforms include Ironside Technologies, Yantra Corporation, and many others.

Prospects

The future of the emerging B2B market overall is probably bright despite the shakeout of many startups that occurred in 2001. Many early proponents followed the horizontal market strategy of building one-size-fits-all B2B exchanges and then trying to attract customers along the "build it and they will come" paradigm. Unfortunately, most larger companies have legacy business systems that require a great deal of customization to participate effectively in B2B, and, as a result, most public B2B exchanges attracted only small and mid-sized companies whose resources were limited.

The main issues that tend to make many companies slow to jump on the bandwagon of public B2B exchanges are the unpredictable costs of transaction-based fees for involvement in these marketplaces, the complexity of integrating B2B solutions into existing supply chain systems (especially for companies that have progressed little in developing Web-based intranet and extranet solutions for their businesses), and issues relating to branding and customer loyalty that make suppliers reluctant to offer their wares at cut-rate prices in the new online marketplaces. As a result, successful B2B exchanges tend to be those that can build community—that is, a group of buyers and sellers loyal to one another. Private exchanges (those built upon preexisting business relationships) thus tend to fare well but offer few avenues for market growth for suppliers involved, and public exchanges offer a way of helping suppliers find new markets and new customers.

Another issue that has restrained many from the wholesale plunge into B2B is the snake-oil syndrome: new technologies breed startups that offer end-to-end solutions that are ready to implement "yesterday." Due diligence is required of companies contemplating aligning themselves with a B2B solution or platform, and decision-makers should obtain financials and customer testimonials to avoid getting caught in the web of fly-by-night operations that are here today and gone tomorrow.

With the failure of numerous public B2B marketplaces, companies that were early adopters are taking a more cautious view of further involvement, so that while recognizing the need to pursue B2B solutions in order to compete in the future economy, they are now more effectively taking care in investigating the financial viability of exchanges before jumping on board again. Nevertheless, while getting your company involved with a specific B2B provider is a tactical solution that requires good thought and due diligence, getting your company involved generally in B2B solutions is a strategic requirement for any company that hopes to survive in the Internet economy that is here and yet to come.

Notes

Microsoft Corporation has its own internal B2B solution called the Microsoft Market, which allows employees to quickly and easily procure goods and services from a wide variety of partner businesses. Microsoft Market has enabled Microsoft to lower average procurement costs by more than 90 percent.

Many B2B marketplaces provide procurement services based on either forward (sell-side) auctions which benefit suppliers or reverse (buy-side) auctions in which buyers submit a Request for Quotation (RFQ) and wait for the lowest bid to come in from suppliers. These services have not been as successful as anticipated, however, mainly because companies generally negotiate trusted long-term contractual business relationships with partners rather than just bid for the best-priced solution.

See Also: *BizTalk Server 2000, Commerce Server 2000, Digital Subscriber Line (DSL), electronic data interchange (EDI), Microsoft Market, Universal Description, Discovery, and Integration (UDDI), virtual private network (VPN)*

B2C

Stands for business-to-consumer, relationships in which individuals or companies purchase the products or services of another company.

See: *B2B*

backbone

The portion of a network that ties different departmental networks into a single whole.

Overview

Backbones are primarily used in medium to large networks, such as those occupying a building or a group of buildings on a campus. The backbone carries the bulk of the network traffic and must be designed accordingly. Backbone designs generally fall into two basic categories:

- **Distributed backbone:** Refers to using cabling to join different departmental networks in a bus topology or mesh topology. This cabling is referred to as backbone cabling, and it connects the hubs, switches, or routers of each network into a single whole. In a typical scenario, each floor or building might have a local area network (LAN) and wiring closet containing, among other things, a main hub or router. Backbone cabling is then run between floors or buildings, connecting the main hub or router for each department into a bus-style network (see illustration).
- **Collapsed backbone:** Refers to using cabling to directly join each departmental network's main hub or router using backbone cabling to a central hub, switch, or router in a star topology (see illustration). The central unit is often referred to as the collapsed backbone, although this term properly describes the entire configuration. The central unit can be located in the building's main equipment room or, in a campus scenario, in the IS (Information Services) department's building.


Distributed Backbone
Collapsed Backbone
Third floor management LAN
Second floor support LAN
First floor marketing LAN
Wiring closet
Wiring closet
Wiring closet
Backbone
hub/switch/router
Collapsed backbone (switch/router)

Backbone. *Two basic types of network backbone: distributed and collapsed.*

Distributed backbones generally have a greater degree of fault tolerance than collapsed ones, because the collapsed backbone unit forms a single point of failure. However, collapsed backbones usually have better traffic flow than distributed backbones because of the underlying star topology. Collapsed backbones generally offer better performance because of the reduced number of hops that traffic must make when passing between departmental LANs. Collapsed backbones are also easier to manage because they bring all the backbone switching and routing equipment into a single room or building. Collapsed backbones are used frequently for connecting departmental LANs within a single building, but less often for connecting building LANs across a campus network because of the increased distances and cabling costs.

Backbone cabling should have the highest bandwidth of any cabling in your network, since backbones are used to join together hubs, switches, and routers, linking departmental LANs or subnetworks into building-wide or campus-wide internetworks. In buildings, backbone cabling often refers to the vertical cabling running through the risers or elevator shafts that connects the hubs and switches in each floor's wiring closet. Depending on performance requirements, anticipated growth, and cost, any of the following might be suitable for backbone cabling:

- Category 5 (Cat5) unshielded twisted pair (UTP) cable
- Type 1A shielded twisted pair (STP) cable
- Thinnet coaxial cabling
- Multimode fiber-optic cabling
- Single-mode fiber-optic cabling

Notes

The term *backbone* is also used to refer to the collection of networking components (cabling, hubs, switches, and routers) that form the supporting network into which workgroup and departmental LANs are connected. A mesh topology is often used for network backbones to provide fault tolerance for critical high-speed data paths.

You should put considerable thought and planning into the design and implementation of your network's backbone, because the overall performance of networking services is largely dependent on the backbone's bandwidth and reliability. Design your backbone with network expansion in mind. Planning for growth is especially important if the cost of cable reinstallation is high. Fiber-optic cabling is preferred for most network backbones because of its high bandwidth, security, and resistance to electromagnetic interference.

See Also: *collapsed backbone*

backboning

Sending messages between similar messaging systems by using an intermediate messaging system of a different type.

Overview

A simple backboning example is the connecting of two or more Lotus cc:Mail postoffices using a Microsoft Exchange Server organization as the messaging backbone. By installing the cc:Mail Connector on Exchange Server, messaging connectivity can be established with connected cc:Mail postoffices. Messages can then be routed from one postoffice through the Exchange organization to other postoffices on the network.

Another example of backboning is connecting different sites in an Exchange Server organization using a public or private messaging network. Here are two possible scenarios:

- Using Simple Mail Transfer Protocol (SMTP) hosts on the Internet to connect Exchange sites.
- Using a public or private X.400 messaging system for connecting Exchange sites using the X.400 Connector.


①
Using Exchange to backbone Lotus cc:Mail postoffices
Lotus cc:Mail postoffices
Lotus cc:Mail postoffices
Exchange site
Exchange site
②
Backboning Exchange over the Internet SMTP system
SMTP host
SMTP host
Internet
Exchange site
Exchange site

Backboning. *Connecting similar messaging systems by backboning over a different messaging system.*

When using a public messaging backbone (or a private one owned by a different company) for connecting your Exchange sites, you should consider the following:

- Installing and configuring appropriate messaging connectors on suitable messaging bridgehead servers
- Establishing and maintaining directory replication between Exchange sites
- Handling background traffic from other users of the backbone
- Tuning messaging performance to optimize use of the backbone
- Implementing a suitable topology for the messaging backbone

For very large Exchange organizations, use a hub and spoke topology instead of a mesh topology. Hub and spoke topologies have less redundancy and fault tolerance, but mesh topologies have routing tables that grow exponentially with the number of sites involved. Mesh topologies for large organizations can lead to routing tables that are so large they degrade the performance of the message transfer agents, even on high-performance servers.

Notes

The term *backboning* is sometimes used to describe the core messaging paths set up for a large Exchange organization, regardless of whether messaging systems other than Exchange are involved.

See Also: *Exchange Server*

background

A context for running applications or services on a computer.

Overview

A program that runs in the background is unnoticed while the user performs another task on a different program in the foreground. For example, a spreadsheet that calculates data could be hidden and running in the background while the user types a letter using a word processor program running in the foreground. If the user switches from the letter to the spreadsheet, the roles of the two programs become reversed.

Operating systems usually assign fewer CPU resources to background programs than to foreground ones. In Microsoft Windows 2000, Windows XP, and Windows .NET Server, the System utility in Control Panel offers you several Performance options on the Advanced tab for optimizing performance between background and foreground tasks:

- **Applications:** Provides more CPU resources to the foreground program and allocates short, variable quanta to running applications
- **Background Services:** Divides CPU resources equally among the foreground program and any running background programs and allocates long, fixed-length quanta to applications

In addition, you can tune or enhance performance by modifying the total paging file size on all drives.

BackOffice

A suite of integrated server products from Microsoft Corporation.

Overview

The Microsoft BackOffice suite of server products is built upon the foundation of the Microsoft Windows 2000 Server and Advanced Server platform and provides a scalable, reliable solution for the needs of departments, branch offices, and medium-sized businesses. BackOffice is provided in an integrated package called BackOffice Server 2000, which provides tools for building directory, networking, messaging, Web services, database, proxy and firewall services, and Systems Network Architecture (SNA) host integration infrastructures.

BackOffice Server 2000 includes the following Microsoft server products:

- Windows 2000 Server or Advanced Server with Service Pack 1
- Exchange Server 2000
- SQL Server 2000
- Systems Management Server 2
- Internet Security and Acceleration Server 2000
- Host Integration Server 2000

In addition, BackOffice Server 2000 offers a host of additional tools for deploying and managing BackOffice components such as BackOffice Server management consoles, various wizards, reporting tools, and Microsoft FrontPage and Microsoft Outlook client software. For additional information on each of the server applications listed above, see their respective articles elsewhere in this book.

For More Information

Visit the BackOffice site at *www.microsoft.com/backoffice.*

See Also: *Small Business Server*

BackOffice Server

A suite of integrated server products from Microsoft Corporation.

See: *BackOffice*

Back Orifice

A remote administration tool for Microsoft Windows developed by the hacker group Cult of the Dead Cow.

Overview

Back Orifice was first released for the Microsoft Windows NT platform in 1997 by Cult of the Dead Cow (CDC), a professed hacker group. Although the tool is basically a form of Trojan horse that can be used to gain control of a target machine, it is also a full-featured remote administration system for computers that run Windows NT and Windows 2000.

Back Orifice consists of two parts:

- **Server component:** This is a small-footprint application that can be installed in a stealthy fashion on target systems and can also attach itself to any Windows executable on the target machine or run as a separate service using any name designed. The server runs invisibly in the background and is not visible to users logged on to the target machine even in the task list or close-program dialog box.
- **Client component:** This application is used by the administrator (or hacker) to control the remote Windows 2000 computer. The client component can be used either in graphical user interface (GUI) or command-line mode and can be used to send commands to the server component to perform directory listings, copy or delete files, display or kill running processes,

log all keystrokes entered at the remote machine's console, reboot or lock the system, edit the registry, and perform other actions. By default the client sends commands to the server through User Datagram Protocol (UDP) port 31337 but can be configured to use any available UDP port instead.

Back Orifice is a powerful remote administration tool, but because of its stealth features it is also a serious threat to systems running Windows NT and Windows 2000. Administrators who are concerned about this threat should consult article Q237280 in the Knowledge Base on Microsoft TechNet, which explains how to detect when the server component of Back Orifice is present on a system and how to remove it.

For More Information

You can find Back Orifice 2000 at *www.cultdeadcow.com.* Microsoft TechNet can be found at *www.microsoft.com/technet.*

See Also: *virus*

backup

The process of making reliable copies of important data so that the data can be recovered in the event of a disaster.

Overview

Performing regular backups is perhaps the system or network administrator's least glamorous but most important task. Data loss on a corporate network can occur for various reasons, including

- Disk failures caused by hardware failure, power outages, or improper use
- Network problems leading to lost packets that are not acknowledged because of router congestion or other situations
- Virus infection, resulting in corrupted files
- Sabotage by hackers or disgruntled employees, resulting in erased data
- Theft of hardware from the premises

In each of these scenarios, having reliable backups of your company data is essential to recover from the disaster and continue normal business functioning.


① Network backup
SCSI or Fibre Channel link
Backup server
Fast Ethernet switch
Tape library
Backup LAN
Servers
Regular LAN
② LAN-free backup
Tape library
Fibre Channel links
Fibre Channel router
Tape library
Fibre Channel links
Servers
LAN

Backup. *Network and LAN-free backup scenarios in the enterprise.*

At the enterprise level, backups can be performed using a variety of technologies, each of which have their own advantages. These technologies are a blend of backup device hardware and how these devices are implemented. The next section of this article looks at a few common scenarios. First, backup solutions can be characterized by the devices used to store the backed-up data. These devices can include

- **Tape drives:** A tape drive is a device that stores data on magnetic tape. Many kinds of tape drives and tape formats are supported by different vendors, and these are discussed more fully in the articles “tape drive” and “tape format” elsewhere in this book. Generally speaking, however, tape drives have capacities in the tens of gigabytes range and are suitable for backing up data from individual servers or small groups of servers.
- **Tape libraries:** A tape library consists of a set of tape drives, a large collection of tapes, and a robotic mechanism for loading and unloading tapes into drives. Tape libraries are common in large companies and can typically store several terabytes (one terabyte equals 1000 gigabytes) of data from groups of servers. For more information, see the article “tape library” elsewhere in this book.
- **Optical drives:** Another medium for backing up data is optical drives, which range from simple CD-R/W drives to DVD-W drives and libraries containing many such drives. Optical drives are not as common as tape drives and libraries.
- **Storage appliances:** These are generally rack-mountable black-box solutions in which the underlying operation is not important. Storage appliances are generally used for live data storage but can also be used for small-scale backup purposes.
- **Storage Area Networks (SANs):** While SANs are primarily used for live storage of data, they can also be used for archiving backup data. See the article “storage area network (SAN)” elsewhere in this book for more information.

Besides these different backup devices, there are also various ways of implementing them for backing up data from network servers:

- **Server-based backups:** In this scenario each server that holds valuable data has a tape drive directly attached to it, usually through a Small Computer System Interface (SCSI) connection. The disadvantage of this scenario is that it scales poorly for large companies—administrators would need to run around each morning to collect tapes from drives scattered all over the network.
- **Network backups:** This is the most common scenario in most large companies. In a typical network backup scenario, a group of servers on a local area network (LAN) are connected using a second network interface card (NIC) in each server to a separate LAN dedicated for backup purposes. This dedicated backup LAN is concentrated using a Fast or Gigabit Ethernet Switch, which is also connected to a dedicated server called the backup server. The backup server has special software running on it that initiates and manages the job of backing up data on the production servers. The backup server itself is then connected by SCSI or FiberChannel to a tape library (see illustration).
- **LAN-free backup:** This is a simplified form of network backup in which there’s no second backup LAN. Instead, fiber channel cards are added to servers needing to be backed up and these are connected using fiber-optic cabling to a fiber-channel router, which then forwards the information directly over Fibre Channel links to tape libraries (see illustration). LAN-free backup is an emerging approach that is gaining in popularity due to its simplicity and high performance.
- **Serverless backups:** This is a further refinement of LAN-free backups that takes the actual task of processing the backup from the servers and moves it to a Fibre Channel switch or router used to connect the servers to the tape libraries. This can provide significant relief to the servers since generating backups is a processor-intensive and memory-intensive job that limits other functions they can perform while the backup is occurring. Serverless backup solutions are just emerging in the marketplace.
- **Storage over IP:** This technology backs up data from network servers directly to backup devices such as tape libraries and SANs using only an Ethernet

network. No backup server is required to convert the data from Ethernet frames for transmission over SCSI or Fibre Channel connections to the backup device. Storage over IP is an emerging technology that promises to have a large impact on the backup market, and it is discussed further in the article “storage over IP” elsewhere in this book.

- **Internet backups:** Backups can also be outsourced over the Internet to a Storage Service Provider (SSP) that is responsible for managing actual backup hardware and securely storing your data. For more information on this, see the article “televaulting” elsewhere in this book.

Finally, a third component of a backup system is the backup software itself. Some of the more popular backup software products used in the enterprise include

- ArcServeIT from Computer Associates
- Backup Exec and NetBackup from VERITAS Software Corporation
- Legato NetWorker from Legato Systems
- Storage Manager from Tivoli Systems
- Backup Express from Syncsort
- Hiback and Hibars from Hicomp Software Systems

Implementation

Instituting a regular backup plan is one of the main components of a company’s disaster recovery policy (see the article “disaster recovery” elsewhere in this book for more information), and the importance of doing so cannot be stressed enough. To guard against these unexpected losses of data—or rather, to prepare for them, since they are, to a certain extent, inevitable—establish a disaster recovery policy that includes a reliable backup plan. In today’s business world, where data is the lifeblood of the enterprise, a comprehensive plan is essential. The following steps are recommended when creating such a plan:

- Decide what kind of backup storage devices to use. Options range from small digital audio tape (DAT) drive units capable of backing up several gigabytes of data to large automated tape libraries capable of handling terabytes of centralized data storage. Other backup options include optical storage libraries and removable disks such as Iomega’s Zip drive disks or Imation SuperDisk disks.
- Decide whether to back up servers with dedicated, locally connected storage devices or over the network to centralized backup libraries. Network backup systems suffer from a single point of failure (the network itself) but are simpler to administer than a multitude of individual backup units.
- Decide whether individual users’ workstations should also be backed up. A more cost-effective option is to educate users to always save their work on a network share located on a server that is regularly backed up.
- Decide how to secure the storage of backup tapes and other media. Will duplicate copies be stored both on-site (for easy access if a restore is needed) and off-site (in case the company’s building burns down)? Make sure the storage facilities are climate-controlled and secure.
- Decide what kind of backup strategy to employ. A backup strategy is a combination of a backup schedule and various backup types, including normal, copy, incremental, differential, and daily copy backup types. Also consider whether you will verify all tapes immediately after each backup is performed. For further information, see the articles “backup strategy” and “backup type” elsewhere in this chapter.
- Assign various aspects of the backup procedure to the responsible party. One option some companies now use is to back up data over the Internet to a third-party backup service provider that stores and maintains the backed-up data. This method involves issues of trust and of the Internet connection as a point of failure.
- Test backups periodically to ensure that they are actually readable. Nothing is worse than thinking you have a backup when in fact it is unreadable.

Notes

To enable administrators to perform regular backups, Microsoft Corporation includes backup utilities with all versions of Microsoft Windows, such as the Backup tool in Windows XP.

See Also: *backup strategy, backup type, storage over IP, storage service provider (SSP), tape drive, tape format, tape library*

backup agent

A service that can be installed on a computer to allow files and folders stored on the computer to be backed up remotely over the network.

Overview

Backup agents enable backups to be performed across an entire network from a centralized location. In networks that utilize this type of storage retention architecture, where a backup agent is installed on each server, files are backed up over the network to a central storage location, which in enterprise environments is usually a tape library or some type of Network Attached Storage (NAS). This approach to backups makes it easier to manage enterprise storage requirements even for large scale corporate networks and Internet service providers (ISPs).

Backup agents are specific to the type of backup software being used and are usually supplied with that software when you purchase it from a vendor. Once an agent is installed on a computer, you can back it up over the network as easily as if a tape drive were connected directly to the computer.

See Also: *backup*

backup browser

A Windows 2000, Windows XP, and Windows .NET Server computer that participates in the Computer Browser service.

Overview

A backup browser is a computer that obtains a copy of the browse list from the master browser. The browse list contains information about which shared resources are available to client machines on the network and about which domains are on the network. Backup browsers automatically contact the master browser every 12 minutes to request a copy of the browse list. If the contact is successful, the master browser issues the list to the backup browser. If the backup browser cannot contact the master browser, it starts a browser election to force a new master browser to be selected.

Once the backup browser has obtained the browse list, it caches the list and distributes it to any client that requests it. To request the browse list from a backup browser, a client calls the NetServerEnum application programming interface (API) on the backup browser.



Backup browser. *How a client obtains the browse list from a backup browser.*

Notes

There will be one backup browser for every 32 systems in a given domain or workgroup on the network. The Computer Browser service determines the number of backup browsers necessary to ensure that clients can have efficient access to network resources.

See Also: *Computer Browser service, domain master browser, master browser*

backup catalog

A representation of the results of performing a backup of servers on a network.

Overview

Backup software, such as the Backup tool in Microsoft Windows 2000, Windows XP, and Windows .NET Server, creates catalogs so that the location and properties of backed-up files are documented and can be found easily when a restore needs to be performed. Windows 2000, Windows XP, and Windows .NET Server Backup stores its catalogs on the backup storage media themselves. These catalogs are then loaded into memory when the program is run. Catalogs can also be saved to disk and printed for documentation purposes.

Windows 2000, Windows XP, and Windows .NET Server Backup creates two different types of backup catalogs:

- **Tape catalog:** Lists the details of all backup sets that have been stored on the tape. If a backup operation spans several tapes, the tape catalog is located on the last tape of the series, because it is created at the end of the backup operation.
- **Backup set catalog:** Lists the details of files and folders included in a specific backup set. A backup set catalog is saved at the end of each backup set on the tape. This catalog is used by the Windows 2000, Windows XP, and Windows .NET Server Backup program to store a summary of the file and directory information for the backup set, the number of tapes in the backup set, and the date on which the backup was performed.

See Also: *backup set*

backup domain controller (BDC)

A Microsoft Windows NT domain controller containing a read-only copy of the Security Accounts Manager (SAM) database.

Overview

On the Windows NT platform, the only writable copy of the SAM database is located on the primary domain controller (PDC). In addition to this PDC, a Windows NT domain can have zero or more backup domain controllers (BDCs) as well. These BDCs are used to provide load balancing and redundancy for network authentication. These BDCs periodically undergo directory synchronization with the PDC by retrieving a copy of the directory database from the PDC.


Two choices for locating BDCs for user logons in WAN situations:
PDC
BDC
Client
Logon traffic adds to WAN link congestion
Efficient synchronization
Slow WAN link
HQ
Branch office
PDC
BDC
Client
Directory replication traffic adds to WAN link congestion
Efficient logons
Slow WAN link
HQ
Branch office

Backup domain controller (BDC). *Different ways to deploy a BDC over a WAN link.*

Every Windows NT network should have at least one BDC for fault tolerance. If the PDC fails, the BDC can be promoted to take its place. One BDC can support approximately 2000 users on a network, but many factors can affect this figure.

Note that a BDC can perform logon validation and authentication as a PDC can, but it cannot manage accounts—for example, it cannot change user passwords.

Implementation

The placement of BDCs in wide area networks (WANs) that are based on Windows NT is an important issue. In a master domain model scenario, user accounts are centralized in a master domain located at company headquarters, but users and shared network resources are distributed in resource domains located at branch offices in different locations. The users in this scenario must log on to the master domain in order to access resources in the enterprise. There are two ways of facilitating this:

- Locate all BDCs belonging to the master domain at headquarters. Unfortunately, when users at the branch offices want to log on, they will have to use the relatively slow WAN link to do so. The additional logon traffic can cause congestion on the WAN link, particularly at certain times of the day.
- Locate one or more BDCs belonging to the master domain at each branch office (resource domain). This will facilitate logons by users located at branch offices, since they can log on to one of these BDCs locally instead of being validated over the relatively slow WAN link by a domain controller at headquarters. However, directory replication traffic between the BDCs located at the branch offices and the PDC at headquarters can cause congestion over the WAN links. To make directory synchronization more efficient over the WAN link, registry parameters such as ReplicationGovernor and ChangeLogSize can be adjusted and batch files can be scheduled using the at command to configure different replication rates at different times of the day.

See Also: *domain controller, primary domain controller (PDC)*

Backup Operator

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, a user who is assigned the responsibility of backing up and restoring servers on a network.

Overview

To make an individual a Backup Operator, simply make him a member of the Backup Operators group. Backup Operators can exist on Windows NT domain controllers, on member servers, and on workstations. In Windows 2000, Windows XP, and Windows .NET Server, Backup Operators are members who have a similar function and belong to the built-in group called the Backup Operators built-in group.

Backup Operators have the preassigned right to log on locally to a computer and to back up and restore files and directories on the system. Backup Operators also have the right to shut down the system. Backup Operators do not need permissions assigned to them in order to back up a particular file or directory—they have a broad system right to do so.

Notes

Backup Operators should be assigned only in enterprise-level networking environments. In small to medium-sized networking environments, backing up and restoring servers is usually the responsibility of the administrator.

See Also: *Backup Operators built-in group, built-in group*

Backup Operators built-in group

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, a built-in group for containing users who need privileges to back up servers on the network.

Overview

Backup Operators is a built-in group existing on all Windows 2000–, Windows XP–, and Windows .NET Server–based servers and workstations. The Backup Operators built-in group is a local group with the following preassigned rights:

- Log on locally
- Back up files and directories
- Restore files and directories
- Shut down the system

Notes

If you want a user to be able to back up files and directories on any domain controller in a domain, place the user in the Backup Operators group on any domain controller. Since all domain controllers share the same directory database, the user will be a member of the Backup Operators built-in group for all domain controllers. However, if you want a user to be able to back up a member server, place the user in the Backup Operators built-in group that is a local group on that particular member server.

See Also: *built-in group*

backup set

A collection of files and folders on a backup media that were saved in a single Microsoft Windows 2000, Windows XP, and Windows .NET Server Backup operation.

Overview

There are several options for creating backup sets in Windows 2000, Windows XP, and Windows .NET Server:

- Multiple backup sets can be saved on a single backup tape by appending each new set to the last one.
- A backup set can span multiple tapes if you have a large quantity of information to back up.
- Tapes can be overwritten so that a new backup set replaces the old one.



Backup set. *A representation of a backup set.*

Windows 2000, Windows XP, and Windows .NET Server Backup creates a backup set catalog for each backup set. This catalog lists the various files and directories that have been backed up, and you can use it for restoring individual files or directories or print it for documentation purposes. The backup set catalog is saved at the end of each backup set on the tape. A backup set map at the end of the tape locates all backup sets on the tape.

Notes

A copy of the local system's registry can also be included in the backup set for a Windows 2000, Windows XP, and Windows .NET Server system. Backup sets are described with friendly names that can be up to 32 characters long.

See Also: *backup catalog*

backup strategy

A plan for performing backups to ensure against data loss.

Overview

Successful backup strategies take the following issues into account:

- The various backup types that can be performed
- The need to archive tapes for long-term data security
- The time needed to perform backups and restores

- The cost of tapes
- The cost of losing data

There's no one right way to implement a backup strategy for resources on a network of computers. To select the best backup strategy for your network, you must consider each of the items in the preceding list and balance them against one another. Your strategy should be simple, efficient, and reliable. The following table shows some examples of backup strategies:

Possible Backup Strategies

Backup Strategy	*Advantages*	*Disadvantages*
Normal backups Monday through Friday.	Most secure—every tape contains all backed up files	Longest time to back up
Normal backup Monday; differential backups Tuesday through Friday.	Less time to restore	More time to back up
Normal backup Monday; incremental backups Tuesday through Friday.	Less time to back up	More time to restore
Use a separate tape for each weekday and archive Monday's full backup tape weekly or monthly.	Less chance of data loss	Higher cost, since more tapes are needed
Use the same tape for each weekday and archive the tape each week or month.	Cheaper—only one tape required per week or month	Greater chance of data loss, since using only one tape

See Also: *backup, backup type*

backup type

A particular method for performing a backup of files and directories.

Overview

Each type of backup has a different function in an overall backup plan. Most network backup software (such as Microsoft Windows 2000, Windows XP, and Windows .NET Server Backup) supports five backup methods:

- **Normal backup:** Backs up volumes, folders, and files that have been specified by the administrator. Normal backups are the fastest and easiest to restore. Normal backups are sometimes referred to as "full backups." Use a normal backup when you want to ensure that all your critical system and data files are backed up in a single operation. If your backup cycle consists only of normal backups and you need to perform a restore, you need to use only the most recent normal backup to do so.
- **Copy backup:** Primarily used to produce an additional copy of a backup—for example, a copy to send to the accounting department for monthly archiving and reporting. While a copy backup backs up the same files as a normal backup, there is a difference between the two operations. Performing a normal backup clears the archive bit on each backed-up file and marks them as having been backed up. A copy backup, however, does not modify the archive bit on the files backed up. In other words, you can perform a copy backup at any time in a backup cycle without interrupting the cycle in any way—the copy backup is distinct from the backup cycle and is not required when a restore is performed from the cycle's set of tapes.
- **Incremental backup:** Backs up only files that have been created or modified since the last normal or incremental backup. Files that are backed up in an incremental backup have their archive attributes cleared in order to indicate that they have been backed up. Using a combination of normal and incremental backups takes less time and uses less storage space than performing only normal backups. However, if you need to perform a restore, you typically need to use the normal backup plus every incremental backup from the current backup cycle to do so.
- **Differential backup:** Copies those files that have been created or changed since the last normal or incremental backup. Files that are backed up by a

differential backup do not have their archive attributes cleared, which means that these files will be backed up again in any succeeding differential backups. Differential backups are cumulative with regard to changes—that is, each differential backup in a given backup cycle contains all the files from the last differential backup, plus any files that have been modified since the last differential backup. Thus, if you need to perform a restore, you will typically need to use only the normal backup and the most recent differential backup from the current backup cycle to do so.

- **Daily copy backup:** Copies all files that have been modified on the day the daily copy backup is performed. This method is sometimes used to make a copy of all files a user worked on in a day so that he or she can take them home to work on. Like a copy backup, the daily copy backup does not modify the archive bit of the files backed up; therefore, the daily copy backup does not interrupt the backup cycle in any way.

Notes

Different types of backup operations have different effects on the archive attributes of the files and directories they back up. A backup operation marks the archive attribute by clearing it to indicate that the file has been backed up. If the file is later modified in some way, its archive attribute is set (unmarked). The following table shows what each type of backup operation does to the archive attribute.

Effects of Backup Operations on the Archive Attribute

Backup Type	*Archive Attribute*
Normal	Cleared
Copy	No effect
Incremental	Cleared
Differential	No effect
Daily copy	No effect

See Also: *backup, backup strategy*

Backup Wizard

A wizard that is part of the Microsoft Windows 2000, Windows XP, and Windows .NET Server Backup tool.

Overview

You can use the Backup Wizard to configure, schedule, and execute a backup. The Backup Wizard starts by letting you choose among the following:

- Backing up all files on the computer on which it is running.
- Backing up files and folders that you specify. These files and folders can be either on the local computer or on any shared location on the network.
- Backing up Active Directory directory service information and the registry on the computer on which the wizard is running. Active Directory can be backed up only on a domain controller.

The wizard then leads you through the process of specifying a backup location and other advanced backup options, such as verification, compression, and remote storage. You can also schedule a backup job to run unattended at a later time when users have stopped working and all files are closed.

See Also: *backup*

BACP

Stands for Bandwidth Allocation Control Protocol, an enhanced version of Bandwidth Allocation Protocol (BAP), a protocol that manages bandwidth for Multilink Point-to-Point Protocol (MPPP) connections.

See: *Bandwidth Allocation Control Protocol (BACP)*

balanced line

An electrical cable consisting of pairs of conductors that have identical electrical characteristics with respect to each other and with respect to ground.

Overview

In a balanced line, both of the two wires are carrying current at any given instant. However, at any particular moment, the directions of the current in the wires are opposite each other. This condition is also described by saying that the currents in the wires are 180 degrees out of phase with each other at any given moment.

Both wires have voltages that are above ground potential, but the potentials of the wires are different with respect to ground, resulting in a flow of current. The wire pair is twisted in order to ensure that the electromagnetic radiation produced by both wires is effectively canceled out, reducing the overall electromagnetic interference (EMI) produced by the wires and reducing their sensitivity to induced currents from external sources of EMI.

The most common example in computer networking is the twisted-pair cabling used in 10BaseT Ethernet networks.

Notes

A balun can be used to connect a balanced line to an unbalanced line.

See Also: *balun, unbalanced line*

balun

Stands for balanced unbalanced, a device used to connect balanced lines and unbalanced lines.

Overview

Balanced and unbalanced lines have different electrical characteristics that prevent them from simply being connected to each other. A balun matches these different characteristics by providing impedance transformation between the two different lines.



Balun. *An example of a coxial-to-twisted-pair balun.*

Baluns can be used for various types of connections between different wiring systems:

- **Twisted-pair cabling to coaxial cabling:** Typically used for connecting 10BaseT networks with 3270 equipment running on coax or twinax networks
- **Twisted-pair cabling to Token Ring cabling:** Used for matching Token Ring Type 1 cabling to standard unshielded twisted-pair (UTP) cabling to connect 10BaseT or faster hubs or adapters with RJ-45 ports into a Token Ring network
- **Asynchronous Transfer Mode (ATM) cabling to Token Ring cabling:** Used for connecting Token Ring networks to high-speed ATM hubs in campus backbone networks

See Also: *balanced line, unbalanced line*

bandwidth

The information-carrying capacity of a signal or technology.

Overview

By definition, bandwidth equals the difference between the highest and lowest frequencies in a given range of frequencies. For example, if the lowest and highest frequencies a telephone line can carry are 300 hertz (Hz) and 3300 Hz, the bandwidth of the telephone line is 3300 – 300 = 3000 Hz, or 3 kilohertz (kHz).

The above definition of bandwidth applies to any signaling system, analog or digital. With digital systems such as computer data networks, the term *bandwidth* is often used to describe the capacity of a communication channel for carrying signals. The greater the bandwidth, the more data can be transferred in a given time. Since bandwidth is here synonymous with information, and digital information is conveyed in bits (1=on and 0=off), bandwidth for such systems is usually expressed in bits per second (bps) or some multiple thereof (including Kbps, Mbps, Gbps, and Tbps). This rate of flow of information in bits per second is more properly termed “throughput,” but bandwidth is the usual expression used in popular literature.

Shannon's Law can be used to determine the information-carrying capacity of a transmission channel as follows:

(Throughput in bps) = (Bandwidth in Hz) x log2 [1 + R]

where

R = (Signal power in Watts) / (Noise power in Watts)

This formula is only approximate since it does not take into account the medium's transmission properties and other considerations. The significant thing to notice, however, is that as noise (due to crosstalk, interference, or some other source) increases, the channel's capacity to carry information decreases.

For fiber-optic cabling, the bandwidth is usually expressed in units of MHz-km. For example, a cable rated at 500 MHz-km could carry 500 Mbps of data a distance of 1 kilometer (km), 250 Mbps of data a distance of 2 kilometers, 100 Mbps of data a distance of 5 kilometers, and so on. A similar explanation holds for measurements in units of MHz-miles.

Notes

Adequate bandwidth is a prerequisite for reliable communications, and ensuring sufficient bandwidth in today's Internet economy often drives upgrades for enterprise networks. When a new bandwidth need arises, such as deployment of streaming media across a network, the obvious solution may seem to be to "throw bandwidth at the problem," that is, to spend money on upgrading the network infrastructure from Ethernet to Fast Ethernet to Gigabit Ethernet (GbE) and beyond. This is really only one solution—another, sometimes better, approach is to implement Quality of Service (QoS) mechanisms to prioritize traffic so that certain forms of traffic receive preferential transport over less important forms. QoS is an elegant solution that sidesteps the brute-force approach of simply adding more bandwidth, but QoS can be difficult to configure and manage. Although Asynchronous Transport Mode (ATM) networks have the advantage of having QoS built into their operational fabric, the far more common Ethernet networks require new protocols such as DiffServ and Resource Reservation Setup Protocol (RSVP) to be implemented to support even rudimentary QoS features. And with the rapidly dropping prices of GbE switching gear and the appearance of 10 GbE on the horizon, simply adding more bandwidth when it is needed is still the most common solution for most large companies.

See Also: *quality of service (QoS), signaling*

Bandwidth Allocation Control Protocol (BACP)

An enhanced version of Bandwidth Allocation Protocol (BAP), a protocol that manages bandwidth for Multilink Point-to-Point Protocol (MPPP) connections.

Overview

Although BAP dynamically controls how bandwidth can be allocated for Multilink Point-to-Point Protocol (MPPP) connections, a condition can sometimes occur in which both hosts at the two ends of a MPPP connection try to add or remove an additional link at the same time. The Bandwidth Allocation Control Protocol (BACP) is an enhanced version of BAP that is designed to handle such a scenario. It does this by establishing ahead of time which MPPP host is the favored peer, that is, the one whose BAP request will be honored in case of a collision of two requests.

See Also: *Bandwidth Allocation Protocol (BAP), Multilink Point-to-Point Protocol (MPPP)*

Bandwidth Allocation Protocol (BAP)

An offshoot of Multilink Point-to-Point Protocol (MPPP) that allows new links to be added or removed dynamically when needed.

Overview

The Bandwidth Allocation Protocol (BAP) dynamically controls how bandwidth can be allocated for multilink connections using the Point-to-Point Protocol (PPP). BAP makes multilink remote access (RAS) connections more efficient by allocating lines only as required, thus eliminating wasted bandwidth. This can be especially useful if the telecommunications carrier provisioning the PPP connection charges by the amount of bandwidth being utilized by the customer.

BAP allows the administrator to configure the PPP server to specify which particular MPPP lines can be added or dropped. The administrator also specifies which bandwidth thresholds must be crossed before additional lines are added or existing ones are dropped. BAP is especially useful over Integrated Services Digital Network (ISDN) connections, because these dial-up services can almost instantly add or drop lines.

Notes

BAP is included in Microsoft Windows 2000 and Windows .NET Server as an enhancement to the Routing and Remote Access Service (RRAS) of Windows NT 4. BAP is outlined in detail in RFC 2125.

See Also: *Bandwidth Allocation Protocol (BAP), Multilink Point-to-Point Protocol (MPPP)*

bandwidth on demand

Any networking or telecommunications technology that provides both a permanent, dedicated connection and the capability of quickly increasing bandwidth when needed by users.

Overview

Many telecommunications devices incorporate bandwidth-on-demand features of various types. For example, some Integrated Services Digital Network (ISDN) devices used for Basic Rate Interface ISDN (BRI-ISDN) can be configured to use the second ISDN B channel only when the utilization of the first channel exceeds a certain threshold. If this threshold is exceeded for a specified period of time, the second B channel automatically opens up to facilitate and speed data transfer. Once the data rate has dropped below the threshold, the second B channel shuts down until it is needed again. The ISDN technology for accomplishing this combining of channels is called bonding. Many Asynchronous Transfer Mode (ATM) products also support various bandwidth-on-demand features.

Bandwidth-on-demand technologies are typically used in bursty networking situations in which high transmission speeds and capacities are required for transporting video, voice, and data on common networking circuits. Bandwidth-on-demand configurations often involve a mix of leased-line services and circuit-switched telecommunications services, and they can save users money by opening additional circuits only on an as-needed basis. Networks that make use of bandwidth on demand can be designed to supply additional bandwidth under conditions such as

- Exceeding a specified threshold of network traffic
- Scheduling for expected peak periods of the day
- Failover in case the permanent link goes down

See Also: *Asynchronous Transfer Mode (ATM), bandwidth, Integrated Services Digital Network (ISDN)*

bandwidth throttling

Generally, any networking technology that controls the amount of network bandwidth used by servers, applications, or network communication paths.

Overview

In the context of Microsoft Internet Information Services (IIS), for example, bandwidth throttling is a technique for controlling the amount of network bandwidth used by individual Web sites hosted on the server. You can use bandwidth throttling to prevent hits on a popular site from overwhelming the server and preventing other sites hosted on the server from being accessed by clients.

For example, if five Web sites are being hosted on a single machine running IIS but one of them is extremely popular, the other sites might get starved for bandwidth and users might have difficulty connecting to them. In order to rectify this situation, a specific maximum bandwidth level can be allocated to the popular site with the Internet Services Manager snap-in used for administering IIS using the Microsoft Management Console (MMC). If this maximum bandwidth is exceeded, no further connections to that site are allowed until the bandwidth utilization level drops below the threshold. This allows the unallocated bandwidth to be shared among the remaining less popular sites so that users can connect to them.

See Also: *bandwidth, Internet Information Services (IIS)*

Banyan VINES

Stands for Banyan Virtual Integrated Network Service (VINES), a legacy network operating system (NOS) for building enterprise-level networks.

Overview

VINES was originally based on a proprietary family of protocols that was derived from the Xerox Network Systems (XNS) protocol. VINES uses a client/server distributed networking architecture for allowing clients to access network resources on servers over the network. VINES includes such features as

- Basic file and print sharing
- A distributed directory service called StreetTalk for managing networks
- Support for the Transmission Control Protocol/ Internet Protocol (TCP/IP) protocol
- Graphical administration tools
- Support for Simple Network Management Protocol (SNMP) management

VINES includes clients for MS-DOS, OS/2, Microsoft Windows, and Macintosh platforms as well as optional applications for integrating Windows NT, AppleTalk, Novell, and UNIX networks into existing VINES-based networks.

VINES is built on a client/server model in which clients can make requests for services from servers on the network. The VINES protocol stack consists of five basic layers that map to the seven-layer Open Systems Interconnection (OSI) reference model as follows:

- **Physical and data-link layers:** VINES can operate over Ethernet, Token Ring, X.25, and other types of networking architectures.
- **Network layer:** The main protocol here is the VINES Internetwork Protocol (VIP), which is similar in function to the IP of the TCP/IP protocol suite. VIP encapsulates data and addresses it using a 48-bit address that contains a 32-bit network number and a 16-bit host number. Dynamic address assignment and address resolution are performed using VINES servers, which are referred to as service nodes. VINES clients obtain their addresses dynamically from the nearest server on the network. Multihomed servers function as routers, and routing tables are maintained by periodic announcements from clients and servers. Other network layer protocols include an Address Resolution Protocol (ARP), an Internet Control Protocol (ICP), and a Routing Table Protocol (RTP).
- **Transport layer:** For reliable delivery of data using acknowledgments and sequence numbers, VINES uses its Reliable Message Service. Another service, the Unreliable Datagram Service, supports only best-effort delivery of packets. Finally the Data Stream Service can be used to transmit large amounts of data using virtual circuits with flow-control mechanisms.
- **Session and presentation layers:** VINES implements the standard remote procedure call (RPC) mechanism for enabling communication between VINES client and server components on different stations on the network.
- **Application layer:** VINES supports standard file and print services, directory services (StreetTalk), and a number of other application layer services and protocols.

Notes

When connecting Windows 95 or Windows 98 clients to a VINES-based network, use the 32-bit client for Windows that comes with VINES instead of the 16-bit VINES client included with Windows 95 and Windows 98.

For More Information

Visit the Banyan home page at *www.banyan.com.*

BAP

Stands for Bandwidth Allocation Protocol, an offshoot of Multilink Point to Point Protocol (MPPP) that allows new links to be added or removed dynamically when needed.

See: *Bandwidth Allocation Protocol (BAP)*

baseband transmission

A signaling technology that sends digital signals over a single frequency as discrete electrical pulses.

Overview

The entire bandwidth of a baseband system carries only one data signal and is generally less than the amount of bandwidth available on a broadband transmission system. The baseband signal is bidirectional so that a baseband system can transmit and receive signals simultaneously.

Baseband signals can be regenerated using repeaters in order to travel longer distances before weakening and becoming unusable because of attenuation. Baseband transmission technologies do not use modulation but often use time-division multiplexing (TDM) to accommodate multiple channels over a single baseband transmission line.

Common local area network (LAN) networking technologies such as Ethernet use baseband transmission technology. All stations on a baseband network share the same transmission medium, and they use the entire bandwidth of that medium for transmission. As a result, only one device on a baseband network can transmit at a given instant, resulting in the need for a media access control method to handle contention.

See Also: *broadband transmission, Ethernet*

baseline

A set of data that indicates normal usage of monitored network resources.

Overview

You can use the Microsoft Windows 2000, Windows XP, or Windows .NET Server Performance console to collect data for the present performance of your network to establish a baseline. Then, if you upgrade hardware or add new users, you can measure the network's performance again and compared it with the baseline to determine trends, identify bottlenecks, and measure capacity.

Creating a baseline for server and network activity begins with the process of identifying which server and network resources should be systematically measured. Generally, you always want to measure at least the following four resources: memory, processor, disk, and network subsystems. Using the Performance console, you should collect data for the objects shown in the following table.

Resources and Corresponding Performance Objects to Monitor Performance

Resource	*Objects to Collect*
Memory	Memory, cache
Processor	Processor, system, server work queues
Disk	Logical disk, physical disk
Network	Server, network interface, network segment

These performance objects should be regularly captured for a period of time in order to collect the data needed to establish the baseline. Generally, you should append each log file collected to a master log file using relogging. Focus on periods of peak server and network activity and collect at least a week of measurements to establish your baseline.

Notes

If you want to collect disk subsystem data, first enable disk objects using the Diskperf command. Make sure you use a computer that is not being monitored to create your measurement baseline log files so that the activity of the computer doing the monitoring will not affect the data being collected.

Basic authentication

Also called cleartext or plaintext authentication, an authentication scheme that passes a user's credentials over a network in unencrypted form.

Overview

Basic authentication is defined as part of the Hypertext Transfer Protocol (HTTP) version 1 specification in RFC2617. It is not a secure authentication scheme, since anyone who can intercept network traffic and read it using a protocol analyzer can obtain the user's credentials. Although it is sometimes called cleartext authentication, Basic authentication actually encodes a user's credentials using a well-known public encoding algorithm known as Uuencoding or Base64. Because the algorithm for this encoding method is so well known, however, it is easy to decode encoded text and extract a user's credentials from a Basic authentication session.

Implementation

Basic authentication is one of several authentication schemes available on Microsoft Internet Information Services (IIS) for the Microsoft Windows 2000, Windows XP, and Windows .NET Server platforms. When a user tries to access content on a Web site hosted on IIS and the site implements Basic authentication, a dialog box appears on the user's browser asking for the user's credentials (username and password). The credentials are passed to IIS in the headers of the HTTP GET request, and are compared either to credentials in Active Directory directory service (if implemented) or to the Security Accounts Manager (SAM) database (on a workgroup server). If Active Directory is used, the user's User Principal Name (UPN) can be utilized for authentication purposes. Users who need to be able to access IIS using Basic authentication require the Log On Locally system right (although this can be changed using Active Directory Services Interface, abbreviated ADSI).

The problem with employing Basic authentication is that it is inherently insecure because of the cleartext transmission of the user's password. However, IIS does allow Basic authentication to be implemented with Secure Sockets Layer (SSL) encryption, in which case an encrypted session is first established for the user after which the user's credentials are passed to IIS in encrypted form.

The plus side of Basic authentication is that it can be performed through a firewall or proxy server (Integrated Windows authentication or Windows NTLM cannot work in this case).

Notes

Basic authentication is often used in a UNIX environment for authenticating remote HTTP users.

If you employ Basic authentication with IIS, make sure you also use the NTFS file system (NTFS) to secure access to files on your system.

See Also: *authentication protocol*

basic disk

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, a physical disk that can contain primary partitions, extended partitions, and logical drives.

Overview

Basic disks can be accessed by MS-DOS and legacy Windows platforms and are backward-compatible with these platforms for multiboot systems. Basic disks can also contain volumes created using Windows NT version 4 or earlier, such as spanned volumes (volume sets), striped volumes (stripe sets), mirrored volumes (mirror sets), and RAID 5 volumes (stripe sets with parity).

Basic disks are the default type of disk in Windows 2000 and Windows XP. All disks are basic disks unless you convert them to dynamic disks. Basic disks can have two kinds of partitions:

- **Primary partitions:** Basic disks support up to four primary partitions, only one of which can be marked as active.
- **Extended partitions:** Basic disks support only one extended partition, which can be further subdivided into logical drives or logical volumes.

Notes

You can create only basic volumes on basic disks. You cannot create new simple, spanned, striped, mirrored, or RAID 5 volumes on basic disks.

See Also: *basic volume, dynamic disk*

Basic Rate Interface ISDN (BRI-ISDN)

The slower version of Integrated Services Digital Network (ISDN) communications (the faster being Primary Rate Interface ISDN, abbreviated as PRI-ISDN).

Overview

Basic Rate Interface ISDN (BRI-ISDN, or simply BRI) communications links consist of two B channels and one D channel. The B channels carry the voice or data between the customer premises and the telco central office (CO), and the D channel (control channel) is used for establishing connections and signaling various conditions. BRI is often referred to as 2B+D because of the channels that it employs.

Since the bandwidth of each B channel is 64 kilobits per second (Kbps), the total bandwidth of BRI is twice that, or 128 Kbps. This bandwidth can be used as two separate communication links of 64 Kbps each (for example one for voice and the other for data), or it can be combined into a single 128-Kbps communication link using a technique called bonding. The bandwidth of the D channel is 16 Kbps.

Implementation

BRI connections at customer premises can be connected directly to a switch at the CO, an ISDN call controller that is linked to the CO, an ISDN Private Branch Exchange (PBX), or some other signaling and communication equipment.

If you plan to order a router or access server that supports BRI, make sure you find out from your telco of what kind of ISDN interface is used at your customer premises. The two most common interfaces are the U interface and the S/T interface, and they physically appear the same. Many ISDN access devices support both kinds of interfaces, but check to make sure first.

See Also: *bonding, Integrated Services Digital Network (ISDN), Primary Rate Interface ISDN (PRI-ISDN)*

basic volume

A type of volume in Microsoft Windows 2000, Windows XP, and Windows .NET Server that is compatible with earlier Windows operating systems.

Overview

A basic volume can be created only on a basic disk and can be

- A primary partition, extended partition, or logical drive that was created using the Disk Management portion of the Computer Management tool
- A volume set, mirror set, stripe set, or stripe set with parity that was created using Windows NT version 4 or earlier

See Also: *basic disk, dynamic volume*

bastion host

A network server that is hardened against attack from the outside world.

Overview

Bastion hosts are servers exposed to the outside world and fortified to protect them from attack by hackers. Bastion hosts usually reside on the edge of your corporate network where it connects to the Internet, and often within a specific area called the perimeter network, also known as the DMZ (demilitarized zone), which forms a kind of transition network between your corporate network and the public Internet.

There are many different kinds of bastion hosts:

- **Sacrificial hosts:** These are hosts whose security being compromised is not an issue of great importance. Examples might be a public Web server exposed only to the Internet and not to the corporate side of the perimeter network, or a test server running new applications whose security configuration is still under development, or a dummy host to distract attackers away from the real prize.
- **External service hosts:** These are servers that are primarily exposed to the Internet and may include mail servers, Web servers, and news servers. These hosts are sometimes called primary bastion hosts.
- **Internal service hosts:** These are servers that are primarily exposed to the corporate network and

may include name servers and logon servers. These hosts are sometimes called secondary bastion hosts.

- **Nonrouting multihomed hosts:** These are servers connected to both the internal and external networks but are configured to prevent routing between the two networks. It is essential to verify with this type of host that routing is in fact disabled.

Managing a bastion host involves several activities:

- The initial configuration of the host is important and usually involves removing unnecessary applications, disabling unnecessary services, and removing unnecessary user accounts from the host. In this sense, a bastion host can be thought of as a stripped-down server with limited but highly specific functionality. The motto “keep it simple” is a good rule of thumb when configuring a bastion host—the simpler the server’s configuration, the easier it is to monitor and troubleshoot.
- The implementation of a firewall is an essential step in securing a bastion host. The firewall may reside on the host itself or on some other server within the perimeter network, or it may be a multistage firewall residing on several hosts.
- Monitoring the bastion host once it is configured is essential to determine whether it has been attacked and whether any damage has occurred that might compromise the network. Network security is not a one-time affair but an ongoing commitment that involves auditing, performance monitoring, traffic capture and analysis, logging, and reporting.

Finally, it is essential to accept the fact that bastion hosts are likely to be compromised as new operating system and application bugs are reported and fixes issued by vendors. As a result, never put anything on a bastion host that you would mind losing or which is not available somewhere else. Accept the worst—your host will be compromised someday.

Notes

Some additional tips on deploying bastion hosts:

- Use older, slower machines for bastion hosts if possible because they are less attractive targets for attack by hackers, and, if compromised, are less useful for executing code that can be used to attack the internal network.
- Use the operating system platform you are most familiar with for your bastion hosts, as you need an intimate knowledge of the platform’s services to be able to harden them against attack.
- Place bastion hosts on a separate network from the internal corporate one, usually the DMZ or some other perimeter network.
- Make sure you physically secure the bastion hosts as well—hardening a host and then leaving it an unlocked basement room does not make sense.
- Remove all user accounts from bastion hosts except a dedicated administrator account that is protected by a strong password. Use a machine-specific administrator account rather than a domain administrator account if possible.
- Keep abreast of all releases of service packs and patches for the operating system deployed on your bastion host and apply these when required.

See Also: *firewall, network security*

batch commands

A special set of commands generally found only in batch files.

Overview

Although batch files can essentially contain any commands that can be executed at the command line, a special set of batch commands enable special actions to be performed such as jumps, terminal echoing, and conditional processing.

The table on the following page lists special batch commands that are found only in batch files. These commands are all supported by Microsoft Windows 2000, Windows XP, and Windows .NET Server, but earlier versions of Windows might support only a subset of them.

Batch File Commands

Command	*Description*
Call	Calls one batch program from another while allowing the calling program to continue running
Echo	Toggles command-echoing on or off
Endlocal	Restores environment variables set by a Setlocal command
For	Used to run a specified command for each file in a set of files
Goto	Jumps to a specific line that is labeled in a batch file
If	Used to perform conditional processing of commands
Pause	Suspends processing of the batch file and waits for the user to respond
Rem	Used to insert remarks (comments) in a batch file for documentation purposes
Setlocal	Initiates localization of environment variables in a batch file
Shift	Used to change the position of replaceable parameters in a batch file

See Also: *batch file, Windows commands*

batch file

Also called a batch program, an ASCII file containing a series of commands.

Overview

The commands within a batch file are executed sequentially when the file is invoked. Generally, any command that can be entered at the command line can be used within a batch file as well. You can execute batch files either at the command prompt, by associating a shortcut with them and double-clicking on the shortcut, or by invoking them in a logon script or through some other script or program.

Batch files are traditionally identified using the extension .bat or .cmd. Batch files trace their origins back to MS-DOS, with the Autoexec.bat file being the best-known example. While batch files are still used by many administrators for logon scripts, the advent of the Windows Script Host (WSH) in Microsoft Windows 98, Windows NT Option Pack, Windows 2000, Windows XP, and Windows .NET Server allows more powerful administrative scripts to now be written using higher-level scripting languages such as Microsoft Visual Basic Scripting Edition (VBScript) and JavaScript. As a consequence of the WSH, the old paradigm of batch files may finally be about to disappear.

Examples

Batch files are used primarily to simplify the execution of routine or repetitive administrative tasks such as mapping drives, synchronizing system clocks, or performing backups. For example, on a Windows NT–based network, to control the rate at which directory information is replicated between a backup domain controller (BDC) and a primary domain controller (PDC), you can create a batch file that will change the value of the ReplicationGovernor parameter on the BDC. To do this, first create a script that has the full path to this parameter in the registry along with the value you want to assign to it and then create the following simple batch file:

```
regini <Script_Name>
net stop netlogon
net start netlogon
```

Two different scripts and batch files can be created for different times of the day, and the At command can be used to schedule the execution of each batch file at the appropriate time. This illustration is especially useful if directory replication must occur over a slow wide area network (WAN) link, and you can use it to ensure that most replication traffic occurs during off hours.

See Also: *batch commands, scripting, Windows Script Host (WSH)*

bCentral

An initiative from Microsoft Corporation to help small businesses get online by providing them with subscription-based services, tips and advice, technology consultants, and other aids.

Overview

Microsoft bCentral is designed to help small businesses get online so they can increase sales, improve their market share, and provide better services to customers. The bCentral initiative is an integral part of Microsoft's .NET strategy of providing software as a service to consumers and businesses.

Services available from bCentral include

- Web site hosting packages that range from basic sites to full e-mail services, online advertising, e-commerce, and e-mail newsletters.
- Tools and services for advertising your online business, including search engine submission tools, opportunities to advertise on larger well-known sites, and e-mail newsletters for building customer communities.
- Back-end business support, from online services for managing your customers and tracking sales leads to secure accounting services for managing your business's finances.

In addition, bCentral services are available to any computer having a Web browser and an Internet connection, so you can manage your online business from anywhere using a laptop computer. Partnerships with companies such as Office Depot provide value-added services such as purchasing office equipment and supplies over the Internet from any location. Many bCentral services have free 30-day trial periods that allow businesses to test these services. Finally, bCentral helps you sell your company's products and services at MSN eShop and through an online auction site developed by Microsoft Corporation and FairMarket.

For More Information

You can find bCentral at *www.bcentral.com.*

B channel

Stands for Bearer channel, a circuit-switched channel for carrying voice or data in Integrated Services Digital Network (ISDN) services.

Overview

Such channels are called Bearer channels because they "bear," or carry, the actual information being communicated between the customer premises and the telco's central office (CO). B channels are standard, bidirectional, digital telephone channels that can carry digital information at a rate of 64 kilobits per second (Kbps). Users with greater bandwidth needs can combine several B channels into larger data-carrying pipes. The two most common configurations are

- **2B+D:** Combines two B channels to form a single data pipe with a total bandwidth of 128 Kbps
- **23B+D:** Combines 23 B channels to form a high-speed data pipe equivalent to a T1 line with a total bandwidth of 1.438 megabits per second (Mbps)

Notes

B channels carry voice or data only, not signaling information. D channels carry information for establishment and control of ISDN connections.

See Also: *802.10, Integrated Services Digital Network (ISDN)*

BDC

Stands for backup domain controller, a Microsoft Windows NT domain controller containing a read-only copy of the Security Accounts Manager (SAM) database.

See: *backup domain controller (BDC)*

beaconing

A technique used on token-passing networks for monitoring the status of the token-passing process.

Overview

Beaconing is used in Token Ring and Fiber Distributed Data Interface (FDDI) networks to ensure that token passing is functioning properly. On a token-passing network such as FDDI, every station is responsible for monitoring the status of the token-passing process. If a station detects that a fault has occurred, it starts placing beacons onto the ring. When the next station on the ring detects a beacon, it in turn starts placing beacons on the ring and the first station stops transmitting them. This process will continue until the station immediately upstream of the fault location is the only station sending beacons.

Beaconing enables administrators to quickly locate the fault and repair it. Once the fault is fixed, the station emitting the beacon detects its own beacon returning to it after traveling around the ring, and the station stops beaconing.

See Also: *Fiber Distributed Data Interface (FDDI), Token Ring*

BEEP

Stands for Blocks Extensible Exchange Protocol, an emerging framework to replace Hypertext Transfer Protocol (HTTP) for transport of Extensible Markup Language (XML)–based information over the Internet.

See: *Blocks Extensible Exchange Protocol (BEEP)*

benchmarking

Any systematic method for performing comparative measurements of computer hardware, operating systems, and their components and subsystems.

Overview

Benchmarking began as system attempts to compare the speed and power of hardware, operating systems, and applications that had similar functions. For example, an early comparison between Microsoft Word and Corel WordPerfect might have been to compare how quickly both applications could spell-check the same 100-page document. In the early days, vendors themselves often performed benchmarking to highlight the superior performance of their products in the marketplace.

To elevate benchmarking to something more consistent and reliable, independent nonprofit organizations have been formed to benchmark certain aspects of system and application behavior. Two of these organizations have achieved a high degree of credibility in the industry, namely Standard Performance Evaluation Corporation (SPEC) and the Transaction Processing Performance Council (TPC).

SPEC's goal is to establish a suite of standardized benchmarks for comparing the performance of computer systems. SPEC licenses its tools for use by vendors, who can publish and report the results on SPEC's Web site. An example is the SPEC CPU2000 benchmark for comparing performance of CPU subsystems, which replaces the popular, but now retired, SPEC CPU95 benchmark.

TPC's goal is to develop standard benchmarking tools and procedures for comparing transactional processing between different database products. A transaction is a form of business action performed by a computer system—for example, an online purchase or sale. Database transactions include inventory control, books, account updates, and similar procedures. TPC benchmarks such as TPC-C for Online Transactional Processing (OLTP) and TCP-W for Web-based e-commerce transactions attempt to mirror real-world transaction processing to compare the performance of database systems from different vendors.

Another popular set of benchmarks are those of media company ZDNet, which has developed its set of Winbench and Winstone benchmarks for comparison of business and consumer computer systems and peripherals.

The main difficulty with most benchmarking systems is interpreting them. While trying to mirror real-world effects, benchmarks nevertheless operate under idealized conditions in which certain variables are controlled and others are changed to study the results. The challenge continues to be to develop reliable independent benchmarks that will test significant components of complex real-world systems while maintaining fairness and vendor-neutrality.

For More Information

You can find SPEC at *www.spec.org.* TPC can be found at *www.tpc.org.* ZDNet can be found at *www.zdnet.com.*

BeOS

Stands for Be Operating System, an operating system especially developed as a high-performance platform for multimedia applications.

Overview

BeOS was developed by Be, a company founded in 1991 by Jean-Louis Gassée, a former president of Apple Computer's product division. The first version of BeOS became available in 1995, and the current release is version 5.

BeOS is a preemptive multitasking operating system that incorporates pervasive multithreading in which every application has at least two threads, one for application logic and one for the user interface. BeOS also supports eight-way symmetric multiprocessing (SMP). BeOS also includes a 64-bit journaling file system that supports 18 petabytes of direct storage, protected memory, and a Portable Operating System Interface for UNIX (POSIX)-compliant subsystem.

BeOS has an object-oriented set of application programming interfaces (APIs) that are optimized for real-time digital multimedia and communication functions. Because of this, BeOS is sometimes called a "media OS" to emphasize its high-performance multimedia capabilities.

BeOS runs on Intel-based platforms and certain PowerPC-based hardware, and it includes basic Transmission Control Protocol/Internet Protocol (TCP/IP) support and services. On a PowerPC, you can even run the MacOS as a shell within the BeOS desktop interface.

A lightweight version of BeOS called BeIA (Be Internet Appliance) is also being developed for Internet appliances and similar devices.

For More Information

Visit the Be home page at *www.be.com.*

BER

Stands for Bit Error Rate, a measurement of the reliability of a networking architecture or device.

See: *Bit Error Rate (BER)*

Berkeley Internet Name Domain (BIND)

A popular software tool for administering and maintaining the Domain Name System (DNS) on UNIX platforms.

Overview

Berkeley Internet Name Domain (BIND) was originally written for 4.3BSD UNIX and replaced an earlier domain naming system called JEEVES. BIND is now maintained by the Internet Software Consortium (ISC) and its current major version is BIND 9.

Because most versions of UNIX include some sort of BIND with their distributions and a majority of Internet Service Providers (ISPs) still use the UNIX platform for much of their operations, BIND is still the most popular DNS server on the Internet. BIND is also freely distributed by the ISC and is available for AIX, HP-UX, Irix, Solaris, SunOS, and other operating systems such as Linux and Windows NT.

Notes

The DNS Server services of Microsoft Windows 2000 and Windows .NET Server are Request for Comments (RFC)–compliant implementations of DNS and are fully compatible with BIND. Active Directory directory service can also use BIND as its DNS naming service, provided BIND 8.1.2 or later is used. If you choose to use BIND with Active Directory, make sure you disable name checking on your BIND server because Active Directory uses the underscore character in its SRV records and BIND name checking flags this character as an illegal character.

For More Information

Visit the Internet Software Consortium at *www.isc.org.*

See Also: *Active Directory, Domain Name System (DNS), Internet, UNIX*

BERT

Stands for Bit/Block Error Rate Tester, a device used to troubleshoot serial lines.

See: *Bit/Block Error Rate Tester (BERT)*

best effort

Used to describe network communications in which delivery of data is not guaranteed.

Overview

Routable internetworking protocols such as Internet Protocol (IP) and Internetwork Packet Exchange (IPX) use best effort delivery based on datagrams. In other words, delivery of data by these protocols is not guaranteed. The reason is that these protocols are connectionless in operation, and acknowledgements are not returned as they pass from one hop to the next across a routed internetwork.

An example where communications may fail is what is called a "black hole." In this situation, a failed router drops packets it is supposed to forward, and the station from which the packets originated is unaware that these packets never reached their destination.

See Also: *black hole, Internet Protocol (IP), routing*

BGP

Stands for Border Gateway Protocol, an exterior routing protocol used on the Internet to provide loop-free routing between different autonomous systems (ASs).

See: *Border Gateway Protocol (BGP)*

Binary Runtime Environment for Wireless (BREW)

A platform from QUALCOMM for developing applications for cellular communications systems.

Overview

Binary Runtime Environment for Wireless (BREW) was developed by QUALCOMM as an alternative to Java 2 Micro Edition (J2ME) from Sun Microsystems. Although both platforms enable downloading of applications over wireless phones, BREW has been designed from the ground up to work effectively in the cellular environment and J2ME is a general-purpose developer environment for small devices. BREW's main disadvantage is that it was designed with QUALCOMM's Code Division Multiple Access (CDMA) cellular technology in mind, but J2ME is device- and technology-independent.

A number of companies have committed to building products and services that use BREW, including Wireless Knowledge and Visto Corp.

For More Information

Find out more about BREW at QUALCOMM's Web site at *www.qualcomm.com/brew.*

See Also: *cellular communications*

Binary Tulloch Transport Protocol (BTTP)

A draft specification for a routing protocol to save the Internet from its projected meltdown on or around April 1, 2003.

Overview

Because of the proliferation of Autonomous System Numbers (ASNs) used to identify internetworks connected to the Internet and due to the limited pool of possible ASNs, which is quickly drying up, analysts predict that no more ASNs will be available on or around April 1, 2003. At that point the Internet is expected to collapse.

A proposed solution soon to be presented to the Internet Engineering Task Force (IETF) is the Binary Tulloch Transport Protocol (BTTP). BTTP addresses the underlying issue of ASNs running out by assigning a binary flag (1=on and 0=off) to each ASN, allowing half the ASNs connected to the Internet to be temporarily revoked while the other half remain available at any given time. The protocol switches ASNs between these two states at a frequency of 1000 times per second; in other words, autonomous systems are online one millisecond and off the next, effectively reducing the size of the Internet by half at any given moment and thus giving room for several more years of expansion and growth of the Internet before the problem becomes critical again. Since the average latency for establishing Internet connections is around 20 milliseconds for wired connections (and several hundred milliseconds for satellite links), this is clearly sufficient time for connections to be established with Internet hosts whose networks are rapidly switching on and off.

For More Information

You can find out more about BTTP and its creator, Mitch Tulloch, at *www.mtit.com.*

BIND

Stands for Berkeley Internet Name Domain, a popular software tool for administering and maintaining the Domain Name System (DNS) on UNIX platforms.

See: *Berkeley Internet Name Domain (BIND)*

bindery

In Novell's NetWare version 3.*x* and earlier networking operating systems, the database containing network security information (such as users, groups, and rights) for a particular server.

Overview

Each NetWare 3.*x* server has its own bindery for controlling access to that server's file and print resources. In version 4.*x* and later, the bindery is replaced by the Novell Directory Services (NDS), although 4.*x* servers are also capable of running in bindery emulation mode.

Microsoft's optional Microsoft Windows 2000 Server service Gateway Services for NetWare (GSNW) can be used to implement gateways to resources located on NetWare file and print servers that are using bindery security. This allows Windows users to access volumes, directories, and print queues on NetWare servers without requiring NetWare client software to be installed on them. Client Services for NetWare (CSNW) can also be installed on client machines running Windows 2000 Professional and Windows XP to enable them to directly access bindery-based NetWare 2.*x*, 3.*x*, or 4.*x* servers that are running in bindery emulation mode.

See Also: *Client Services for NetWare (CSNW), Gateway Service for NetWare (GSNW), Novell Directory Services (NDS)*

bindings

A mechanism for linking the various components of an operating system that make network communications possible.

Overview

Bindings link together network interface card (NIC) drivers, network protocols (such as Transmission Control Protocol/Internet Protocol [TCP/IP]), and networking services (such as Workstation service). Microsoft Windows 2000, Windows XP, and Windows .NET Server let you optimize network communication by selectively enabling, disabling, and modifying the order of the bindings between these different networking components. Windows 2000, Windows XP, and Windows .NET Server support Network Driver Interface Specification (NDIS) version 5, which allows multiple protocols to be independently bound to multiple NICs.



Connections are listed in the order in which they are accessed by DNS and other network services.

Connections:

- Private
- Internet
- [Remote Access connections]

Bindings for Private:

- ☑ File and Printer Sharing for Microsoft Networks
  - ☑ Internet Protocol (TCP/IP)
- ☑ Client for Microsoft Networks
  - ☑ Internet Protocol (TCP/IP)

Binding. *Configuring bindings in Windows 2000.*

To configure bindings for Windows 2000, choose Advanced Settings from the Advanced menu of the Network And Dial-Up Connections window, which is accessed from Control Panel. In this way bindings can be easily enabled, disabled, or reordered. To optimize network performance, disable any unnecessary bindings on your workstations.

See Also: *network driver interface specification (NDIS)*

biometric authentication

Any authentication scheme that uses an aspect of a person's physical body or behavior to verify that person's identity.

Overview

Biometric authentication (or biometric identification) has been employed for years for entry-access control of high-security environments such as military compounds and virology laboratories, but only recently have commercial products become available for securing computer networks. Biometric authentication mechanisms take many forms, including

- Fingerprint or thumbprint identification devices
- Face-recognition systems (measure dimensions of prominent facial features)
- Iris-scanning devices (retina scanners are much more rare and expensive)
- Voice-print identification systems (usually a sound card, microphone, and software)
- Biometric trackballs and mice (measures vein patterns, creases on the palm, or density of fatty tissue using infrared lasers)

Some biometric authentication systems measure behavior patterns instead of physical features. An example is BioPassword from Net Nanny Software International, which requires a user to enter a password on a keyboard and then compares the way the user typed the password with information stored in a database.

Biometric authentication systems must be designed carefully in order for them to be truly secure. For example, a simple voice-print authentication system could be fooled by using a tape recording of the user's voice. To guard against this, these systems commonly ask the user to speak a randomly generated series of words into the microphone, which renders such tape recordings useless.

Biometrics will probably soon make their way into the wireless arena as well. Cellular communications vendor Nokia has prototyped a biometric-enabled cell phone, which would make stealing such a phone useless. The main barrier against this development is cost—cell phones are mass-produced cheaply and even a biometric component costing $10 per phone could break the cost model.

Another general barrier to all forms of biometric authentication systems are privacy issues regarding having digital information about your physical makeup stored on a device that could be stolen or misused. Despite these concerns, the biometrics market in 1999 was $166 million and is rising rapidly.

Notes

When implementing biometric authentication systems, be sure to consider fallback authentication options should the biometric device fail. Costs of purchasing and deploying such systems across an enterprise may also be considerable, and help desk departments might find it more time-consuming to troubleshoot a faulty sound card of a voice-print authentication system than simply resetting a user's traditional text-based password.

See Also: *network security*

B-ISDN

Stands for broadband ISDN, the broadband transmission counterpart of Integrated Services Digital Network (ISDN).

See: *broadband ISDN (B-ISDN)*

Bit/Block Error Rate Tester (BERT)

A device used to troubleshoot serial lines.

Overview

A Bit/Block Error Rate Tester (BERT) is a kind of cable tester specially designed for testing serial lines. BERTs can be connected to serial ports on PCs, routers, and other devices to provide a visual indication of the condition of the serial interface.

A typical BERT is a small box with a 25-pin serial connector and 25 light-emitting diodes (LEDs), one for each lead of the interface. A quick visual inspection can provide information about whether data is being reliably transmitted across the interface. You can also use jumpers to make or break specific leads to see the effect—this simulates the effect of crossed wires and can be used to detect such wires in miswired serial cables or connectors.

See Also: *test equipment*

Bit Error Rate (BER)

A measurement of the reliability of a networking architecture or device.

Overview

Bit Error Rate (BER) is expressed in terms of probability of a bit of data being lost while being transported over a network or processed by a device. As an example, standard (10 megabits per second [Mbps]) Ethernet over copper specifies a maximum BER of 10^{-8}, which means only 1 out of every 100,000,000 (100 million) bits transported can be allowed to be lost. This is actually a worst-case scenario, however, as actual Ethernet networks generally have a BER of 10^{-11} or better, meaning that only 1 out of every 100,000,000,000 (100 billion) bits is lost. Fast Ethernet and Gigabit Ethernet (GbE) have BERs an order of magnitude smaller.

An associated measure for Ethernet reliability is Frame Loss Rate (FLR), which for Ethernet networks is typically 10^{-7}, or 1 frame lost in every 10,000,000 (10 million) frames transported. Lost frames are handled by higher-level layers of the Open Systems Interconnection (OSI) model and are ignored by the Data Link Layer.

See Also: *Ethernet*

bits per second (bps)

A unit used for measuring the speed of transmission of data on a network of computers.

Overview

Bits per second, or bps, represents the rate at which information is being sent or received. A bit is a single unit of digital information, represented by either a 1 or a 0. The total number of bits per second that can be transmitted over a network link describes the bandwidth or throughput of that link.

Because most network communication takes place at thousands or millions of bits per second, the following related units are commonly used:

- Kbps = kilobits per second (10^3 bps)
- Mbps = megabits per second (10^6 bps)
- Gbps = gigabits per second (10^9 bps)

See Also: *bandwidth*

BizTalk

An initiative from Microsoft Corporation to standardize the exchange of electronic documents between businesses.

Overview

Businesses exchange information for various reasons:

- Product invoicing and delivery
- Supply-chain management
- Electronic catalogs and ordering systems

BizTalk is designed to standardize these processes using Extensible Markup Language (XML) as a foundation for creating a standard "electronic envelope" for exchanging electronic documents between businesses.

BizTalk actually consists of four interlocking facets:

- **BizTalk Framework:** A framework for developing XML schemas to serve different sectors of business and industry. BizTalk Framework provides a set of rules and a collection of base XML tags for building new schema for B2B e-commerce. These tags provide the “envelope” that ensures electronic documents reach their intended recipient. See the article “BizTalk Framework” later in this chapter for more information.

- **BizTalk server:** Any software that can read and process documents formatted according to the BizTalk Framework is called a BizTalk server. BizTalk servers can be third-party applications developed using any programming language and running on any operating system platform and can be designed for either front-end or back-end exchanges of B2B documents.
- **BizTalk Server 2000:** Microsoft’s own version of a BizTalk server, which runs on the Windows 2000 platform and provides orchestration of business processes and XML document exchange. BizTalk Server 2000 can transmit XML and Simple Object Access Protocol (SOAP)–based messages over a variety of transports including Hypertext Transfer Protocol (HTTP), Simple Mail Transfer Protocol (SMTP), and others.
- **BizTalk.org:** A site devoted to the support and proliferation of BizTalk.

For More Information

Visit the BizTalk resource site at *www.biztalk.org.*

See Also: *B2B, BizTalk Framework, BizTalk Server 2000, XML*

BizTalk Framework

A specification describing the architecture of BizTalk messages.

Overview

BizTalk Framework is part of the BizTalk initiative from Microsoft Corporation to facilitate the exchange of electronic documents and orchestration of business processes between trading partners, supply-chain partners, and other business partners. BizTalk Framework is designed to be the underlying document standard for B2B e-commerce and is based on the standard Extensible Markup Language (XML) specification.

Architecture

When two businesses in a B2B relationship need to exchange information electronically, the first step is to decide on a common XML schema to use that both can understand. A schema defines the type of content being transmitted and the structure of the document containing it. Microsoft has established the site *www.biztalk.org* as a resource site for businesses to develop and publish BizTalk schemas for their industry sectors.



BizTalk Framework. *Format for a BizTalk Message.*

A BizTalk message consists of two parts: the Transport Envelope and the BizTalk Document.

The Transport Envelope specifies the transport protocol used to deliver the message. BizTalk Server 2000, Microsoft’s own implementation of a platform for building BizTalk solutions, supports a number of different transports, including

- Hypertext Transport Protocol (HTTP)
- HTTP over Secure Sockets Layer (SSL), or HTTPS

- Simple Mail Transfer Protocol (SMTP)
- File Transfer Protocol (FTP)
- Microsoft Message Queue Server (MSMQ)
- Application Integration Components (COM building blocks)
- Fax

The other portion of a BizTalk message, the BizTalk Document itself, consists of the following parts:

- **BizTalk Header:** Specifies the source address, destination address, subject, transmission time and date, and document manifest describing the type of document being transmitted (such as invoice, purchase order, or service request).
- **Document Body:** Contains the actual business documents formatted in XML using the agreed-upon schema. If the manifest indicates an invoice, the body describes things such as type of item sent, quantity, payment requested, and sales tax.

See Also: *BizTalk, BizTalk Server 2000, XML*

BizTalk Server 2000

Microsoft Corporation's platform for exchange of business documents and orchestration of business processes using the BizTalk Framework.

Overview

BizTalk Server 2000 is one of the new Microsoft Windows 2000 Server applications. BizTalk Server 2000 is used for building B2B e-commerce through using Extensible Markup Language (XML) to deliver business documents such as sales orders, invoices, and service requests. BizTalk Server 2000 can transmit both XML and Simple Object Access Protocol (SOAP)–based messages. It can use a variety of transports for accomplishing this, including Hypertext Transport Protocol (HTTP), Simple Mail Transfer Protocol (SMTP), File Transfer Protocol (FTP), and others.

For More Information

Find out more about BizTalk Server 2000 at *www.microsoft.com/biztalk.*

See Also: *BizTalk, BizTalk Framework, XML*

Blackcomb

Microsoft Corporation's code name for its upcoming successor to the Windows .NET Server family of operating system platforms.

Overview

"Blackcomb" is planned for release sometime after the release of Windows .NET Server, which had the code name "Whistler." "Blackcomb" will be the first fully .NET version of Microsoft Windows and will be an integral platform for developing and deploying Microsoft's .NET vision of software-as-services.

At this point, little is known about "Blackcomb," but at the Windows Hardware Engineering Conference (WinHEC) in March 2001, Microsoft unveiled some of its intended features, including

- New services for Application Service Providers (ASPs) to deploy and manage .NET Web services running on Blackcomb.
- Dynamic partitioning of servers for greater reliability in mission-critical scenarios.
- Greater communications capabilities and an enhanced user interface.

Notes

Whistler and Blackcomb are two ski resorts in British Columbia, Canada, only a few hours away from Microsoft's headquarters at Redmond, Washington.

For More Information

Find out about the latest developments with the Microsoft Windows series of operating system platforms at *www.microsoft.com/windows.*

See Also: *Microsoft Windows*

black hole

A network condition in routed internetworks where packets are dropped without any explanation to the transmitting host.

Overview

A black hole is generally caused by a router that goes down and whose absence from the network is not detected by other routers. Packets that are forwarded to the black hole are dropped—that is, they never reach their destination and give no indication to the stations sending them of the situation—therefore, the data is lost. Normally, a router will issue an "ICMP Destination Unreachable" message when it cannot forward a packet. However, with a black hole, these messages are not generated, so the transmitting host does not know that data is being permanently lost.

If static routing is being used, a black hole persists until the affected router is brought back on line or until other static routers have their routing tables reconfigured to take the downed router into account. If dynamic routing is used, other routers soon detect the presence of the black hole and adjust their routing tables accordingly to favor other paths.

Black holes can also originate when routers that are active nevertheless drop certain packets for specific reasons. An example is when the Path Maximum Transmit Unit (PMTU) is configured for a router so that it discards Internet Protocol (IP) packets that need to be fragmented in order to be forwarded. If a PMTU router is not configured to also forward indications of dropped packets to transmitting hosts (and by default they are not so configured), then the network problems they produce can be difficult to detect since some (smaller) packets get through successfully while other (larger) packets mysteriously disappear.

The reason, of course, why this condition is known as a "black hole" is its parallel with black holes in Einstein's theory of General Relativity. Einstein's black holes are collapsed stars that swallow everything and from which not even light can return.

See Also: *routing*

BLEC

Stands for Building-centric Local Exchange Carriers, a telecommunications carrier focused on the Multitenant Unit (MTU) market.

See: *Building-centric Local Exchange Carrier (BLEC)*

block coding

An encoding scheme whereby groups of data bits are encoded into a larger number of code bits.

Overview

A variety of block codes are used for encoding transmissions for networking and telecommunications systems. Examples of some common ones include

- **4B/5B:** This packages four bits of data into five code bits and is used by 100 megabits per second (Mbps) Ethernet and Fiber Distributed Data Interface (FDDI).
- **8B/6T:** This packages eight bits of data into six ternary (base-three) code symbols and is used by 100BaseT4 Ethernet.
- **5B/6B:** This packages five bits of data into six code bits and is used by 100VG-AnyLAN.

The reasons for making the "code space" larger than the "bit space" in these encoding schemes are to allow for additional data characteristics to be included in transmissions and to make room for control signals to manage the flow of data or check for error conditions.

See Also: *line coding*

Blocks Extensible Exchange Protocol (BEEP)

An emerging framework to replace Hypertext Transport Protocol (HTTP) for transport of Extensible Markup Language (XML)–based information over the Internet.

Overview

Blocks Extensible Exchange Protocol (BEEP) is a proposed framework for a protocol that would run on top of Transmission Control Protocol (TCP) as an alternative to HTTP. It is designed to facilitate the exchange of

XML-framed information for a variety of uses, including file transfer, instant messaging (IM), and network management.

BEEP has been proposed because HTTP was not originally intended for XML data transport and performs poorly when performing this function. BEEP uses a peer-to-peer (P2P) architecture instead of the client-server one used by HTTP. In a typical scenario, BEEP first establishes a connection between two hosts on a network. The hosts alternate between client and server roles to allow two-way communications between them over a channel. Hosts can choose either to push or pull data between themselves. An advantage of BEEP is that unlike HTTP, a single BEEP connection can open multiple channels for exchange of XML data, which means, for instance, that files could be transferred through one channel while an IM chat session occurs on another.

The BEEP framework also includes a toolkit for rapid development of custom application protocols that would run on top of BEEP to efficiently handle specific types of communications tasks. In effect, BEEP would provide reusable code that would greatly facilitate the development of such special-purpose protocols.

BEEP is being presented as a draft standard to the Internet Engineering Task Force (IETF) for consideration, and the framework is outlined by RFCs 3080 and 3081. BEEP's development has been spearheaded by the company Invisible Worlds.

Notes

BEEP was formerly known by the acronym BXXP.

For More Information

Visit Invisible Worlds at *www.invisibleworlds.com.*

See Also: *Hypertext Transfer Protocol (HTTP), XML*

blue screen

In Microsoft Windows platforms, a blue screen on a user's monitor indicates that something has gone seriously wrong with the system.

Overview

In Windows 2000, Windows XP, and Windows .NET Server, blue screens are normally called stop screens. A stop screen contains complex information that qualified support technicians can use to diagnose the problem. A reboot might get the system going again, but the stop screen might reappear if the problem is not resolved. The problem causing the stop screen to appear can be either hardware-related or software-related, but the stop screen itself is generated by the operating system in response to the underlying problem.

In Windows 95 and Windows 98, the blue-colored screen normally appears when parity errors or memory violations occur. Parity errors can indicate that your system random access memory (RAM) has mismatched single inline memory modules (SIMMs) on your motherboard—for example, RAM with different speeds or a mix of parity and nonparity RAM. Also, systems from some manufacturers require special proprietary RAM in order to function. You should consult the documentation from your computer's manufacturer or your RAM's manufacturer to ensure that you have the correct type of RAM in each slot. The Windows 98 blue screen requests that you either shut down the offending application or restart your system using Ctrl+Alt+Delete.

Bluetooth

An evolving specification for short-range wireless transmission between small portable devices in a Personal Area Network (PAN).

Overview

Bluetooth is a wireless networking technology that promises to provide a simple, low-cost method of linking together cellular phones with headsets, Personal Digital Assistants (PDAs) with printers, and similar ad hoc associations between devices in a PAN. A PAN is essentially a network of portable devices carried by a user or devices within which a user comes into close proximity by movement. The vision of Bluetooth actually extends beyond personal data networking to a nirvana world of wireless devices that includes milk containers that signal refrigerators when they are almost empty, whereupon the refrigerator orders more milk using an Internet connection.

Needless to say, not everyone expects (or even wants) this brave new world to happen!

Original work on the Bluetooth specification dates back to 1994 when cellular phone manufacturer Ericsson first outlined the technology. The original intention was to provide a way to connect wireless headsets with cellular phones, but the Bluetooth specification has evolved far past this initial goal. In 1998 a consortium called the Bluetooth Special Interest Group (SIG) was created, and it published its first specification in 1999. The original members included Ericsson, its rival Nokia, and other industry leaders such as IBM, Intel Corporation, and Toshiba Corporation. This consortium has grown to include over 2000 different vendors, and the current Bluetooth specification is version 1.1.

The success of the Bluetooth SIG is based largely on the fact that companies that join must grant a royalty-free license to all other members of the alliance for any Bluetooth-related technology they develop. The SIG's main purpose is to develop specifications for real-world interoperable Bluetooth products—it is not a standards body, and the intention is that any specifications developed by the SIG will be passed on to the Institute of Electrical and Electronics Engineers (IEEE) for final standardization.

Because of the original vision of Bluetooth for small handheld devices, a consistent goal of the Bluetooth SIG has been to develop Bluetooth technology that can be implemented on a single chip. Much success has been achieved in that respect, with chip prices in large lots coming down to the $4 range.

Architecture

Bluetooth is based on baseband FM transmission using frequencies between 2.4 and 2.4835 gigahertz (GHz) within the unlicensed 2.4-GHz Industrial, Scientific, and Medical (ISM) band. Bluetooth divides this band of frequencies into 79 separate channels, and transmission uses a frequency-hopping scheme to hop between channels randomly at a rate of 1,600 hops per second. The result is that a different frequency is used to transmit each packet of a Bluetooth transmission. The advantage of such aggressive frequency-hopping is to provide smooth operation by minimizing the effects of fading due to reflecting obstacles and overcoming noise due to electromagnetic interference (EMI) generated by microwave ovens and other devices. Bluetooth also uses short packets and fast acknowledgments to increase reliability and employs forward error correction to reduce the effects of random noise.

Bluetooth's data transmission rate is 1 megabit per second (Mbps), but with protocol overhead the resultant practical maximum transmission rate is more like 780 kilobits per second (Kbps) or lower. Bluetooth uses a shared-media transmission scheme similar to Ethernet in which only one device in a group of connected devices can transmit at any one time, and duplex transmission is simulated through time-division multiplexing of simplex transmissions. The result is that a PAN with many Bluetooth devices will perform more poorly than one with only a few devices, but this is not considered a serious disadvantage since the specification was designed to be a lightweight one from the beginning.

Given its aim of supporting devices in PANs, Bluetooth is a low-power technology with a maximum range of transmission of 33 feet (10 meters). Bluetooth's automatic power adaptation adjusts transmission power to the minimum needed for reliable transmission in any given situation to enhance battery life in portable devices.

The Bluetooth protocol suite is centralized around the Logical Link Control and Adaptation Protocol (L2CAP). This protocol supports two data transmission modes:

- Asynchronous packet-switched communications with simplex speeds of 721 Kbps in the forward direction and 57.6 Kbps in the reverse.
- Synchronous circuit-switched communications for duplex communications over three 128 Kbps channels for a total bandwidth of 432.6 Kbps in each direction.

The Application Layer of the Bluetooth protocol suite is implemented as a series of "profiles" representing operating parameters for different kinds of uses of Bluetooth. Currently, 13 different application layer profiles have been developed under the specification, and Bluetooth systems are required only to implement a core subset of these together with other profiles needed for their operation.

Other Bluetooth protocols include the Link Manager Protocol (LMP), which manages device authentication for forming new connections, and the Service Discovery Protocol (SDP), which maintains the browse list of accessible devices.

Security is built into Bluetooth at the data-link level and provides the following services:

- **Authentication:** Bluetooth has built-in device authentication, while user authentication needs to be implemented at the application level. Once a device has been authenticated, it is then considered “trusted” by all other devices in the ad hoc PAN.
- **Authorization:** This is used to control which services are accessible from which devices. For example, a Bluetooth-enabled PDA is authorized to print to a similarly enabled printer but not to a Bluetooth cell phone.
- **Encryption:** Bluetooth includes support for 128-bit encryption. In addition, the frequency-hopping transmission scheme employed by Bluetooth helps guard against eavesdropping by unauthorized users.

Implementation

Bluetooth supports concurrent connections among up to eight devices, forming what is called a piconet. Each device in a piconet is temporarily assigned a unique 3-bit MAC address for the duration of the connection. A master/slave relationship exists between one device and all other devices in the piconet for the duration of the connection. The purpose of this is for establishing clocking to synchronize devices for using the hopping sequence. In all other respects, the devices operate as peers during a connection.

Unconnected Bluetooth devices are always on in a standby mode where they listen for connection attempts every 1.28 seconds on each of 32 preassigned hopping frequencies. Once a compatible device is found, link setup and authentication is then performed using the Link Manager Protocol (LMP), which uses the link controller services built into the Bluetooth chip. Connections between Bluetooth devices can be either point-to-point or point-to-multipoint, and groups of piconets can be joined together into larger associations called scatternets, with each piconet within a scatternet having a uniquely different hopping sequence.

Marketplace

The Bluetooth marketplace is still in its infancy, but some of the highlights are as follows:

- Bluecore, the first working Bluetooth chip, was developed by British startup Cambridge Silicon Radio. This was incorporated into the first commercial Bluetooth product, a Bluetooth-capable CompactFlash expansion card named Bluecore CF+, which was developed by California-based Socket Communications for the Microsoft Windows CE platform of portable devices. Since then other Bluetooth chips have been developed by major players such as Ericsson, Intel Corporation, and Motorola.
- RocketChips (*www.rocketchips.com*) has developed a vision for integrating Bluetooth onto CPU chips within PCs; in other words, a no-chip solution instead of the usual single-chip solution. If this vision is implemented, Bluetooth could become as ubiquitous as the PC.
- Red-M (*www.red-m.com*) has developed a complete Bluetooth solution including access server, access point, and PC cards for clients.
- Ensure Technologies has developed a Bluetooth security card that users wear and that can automatically unlock their PCs when they come near them.
- Major vendors developing Bluetooth PC cards include Toshiba, Compaq, Hewlett-Packard, and others. Motorola is producing a PC combo card with a V.90 modem and a Bluetooth chip combined.
- IBM is currently licensing Bluetooth device driver software for the Linux platform and plans similar software for Microsoft Windows platforms. IBM has also prototyped a Bluetooth-enabled PDA called WatchPad that a user wears on the wrist like an ordinary watch.

- 3Com Corporation and Extended Systems are planning on delivering a set of management tools, protocol stacks, and software development kits (SDKs) for developing Bluetooth-based solutions for the Microsoft Windows platform.
- Palm plans on integrating support for Bluetooth in its next version of the PalmOS.
- Intesil Corporation is working on dual 802.11b/Bluetooth chipsets for overcoming issues relating to interference between the two wireless networking technologies.
- Ericsson, the initial force behind Bluetooth's development, has released Bluetooth adapters for some of its cellular phone models that enable wireless connectivity between phone and headset.

The Bluetooth SIG holds a yearly conference called Unplugfest where old and new vendors of Bluetooth products meet to test interoperability between their different implementations of the specifications. Because of the specification's evolving nature, early-to-market products based on the 1.0 specification may have compatibility issues with products based upon the newer 1.1 standard.

Issues

Using the ISM band for Bluetooth communications has been problematic. The ISM band is supposedly reserved worldwide for unlicensed communications, but governments in some countries and regions have licensed portions of this band for specific uses. The problem is of special concern in Spain and France, which have only a narrow portion of the band available, and the Bluetooth specifications have been massaged to produce a special version of the specification technically able to function under these restrictions, but legal restrictions prohibit its use in these two countries to prevent the jamming of other services. The reason this is such an issue is that, due to the multiplication of different specifications, Bluetooth cellular phones will not be able to easily function throughout Europe as originally envisioned by Ericsson.

Another issue is that not only is the ISM band also used by other wireless networking technologies such as 802.11b and HomeRF, but it is also used for non-networking applications such as garage door openers, microwave ovens, cordless telephones, telco local loop systems, baby monitors, medical scanners, and various other business and consumer devices. By using an aggressive frequency-hopping scheme, Bluetooth is fairly resistant to interference from these different systems, but that very fact means that Bluetooth easily interferes with the operation of these other systems. Tests have shown, in fact, that communications over 802.11b wireless networks can be degraded and even disrupted by nearby Bluetooth devices. The result has been that large companies that rely heavily on 802.11b wireless networks have instituted policies to ban Bluetooth devices from the premises.

Besides the threat to 802.11b local area networks (LANs), Bluetooth poses dilemmas for other industries as well. The airline industry has voiced particular concern that Bluetooth devices carried by different passengers might detect each other during a flight, turn themselves on, and generate transmissions that could disrupt an aircraft's sensitive navigation equipment. The Bluetooth SIG is attempting to allay these concerns through further refinement of the specifications.

Prospects

Despite issues relating to interference with 802.11b wireless local area networks (WLANs) and whether ad hoc always-on wireless networking is desirable or even safe, Bluetooth has a great deal of momentum from industry and products are likely to be widely available soon. In addition to consumer-oriented applications for PANs and wireless public access kiosks, Bluetooth may also find some place in the enterprise as a cable-replacement technology.

Only time will tell, however, whether a Bluetooth-enabled can of beer will someday communicate with a similarly enabled refrigerator to ask it to lower the temperature for just the right taste.

Notes

The goals of Bluetooth and 802.11b are different: although 802.11b was specifically developed mainly for laptop computers as a wireless replacement for wired Ethernet LANs, Bluetooth is optimized for forming short-range ad hoc networks for connecting smaller portable devices such as cell phones and PDAs. The implementations of these technologies, although confined to the same ISM frequency band, are also different: Bluetooth uses frequency-hopping, but 802.11b uses spread-spectrum transmission.

The interesting name "Bluetooth" comes from Harald Bluetooth, the Viking who in the 10th century unified Norway and Denmark.

Bluetooth also supports voice transmission that use up to three concurrent synchronous 64-Kbps voice-only channels or one channel that simultaneously supports both asynchronous data and synchronous voice transmission. The voice channels use the continuous variable-slope delta modulation-coding scheme.

A competing technology for PANs besides Bluetooth is the Infrared Data Association (IrDA) protocol, but while IrDA devices require line-of-site communication, Bluetooth devices overcome this restriction. IrDA does have certain advantages however, including much greater data transmission rates.

For More Information

You can find the Bluetooth SIG at *www.bluetooth.com.*

See Also: *802.11b, 802.15, Infrared Data Association (IrDA), Personal Area Network (PAN), piconet, wireless networking*

BNC connector

A group of connectors used for joining thinnet cable segments together and for connecting thinnet cabling to 10Base2 network cards.

Overview

BNC connectors are used on 10Base2 (thinnet) Ethernet networks and use a twist-and-lock mechanism that provides a secure connection between network cabling and components. The male connector has a center pin with a rotating ring with projections that mate with the female connector.

The various types of BNC connectors include the following:

- **BNC cable connector:** Soldered or crimped to the ends of a thinnet cable
- **BNC T-connector:** Used to connect a network interface card (NIC) to a thinnet cable segment
- **BNC barrel connector:** Used to connect two pieces of thinnet cable
- **BNC terminator:** Provides a 50-ohm termination for the free end of a thinnet cable

Notes

Several possibilities are usually suggested as to the origin of the term *BNC*:

- British Naval Connector
- Bayonet Nut Connector
- Bayonet-Neill-Concelman (probably the correct explanation since the connector was named after Neill and Concelman, its two creators)

For situations where large mechanical loads may affect cabling, a threaded form of the connector is available called TNC.

See Also: *connector (device), terminator*

B-node

A NetBIOS name resolution method used by Microsoft Windows NT in which broadcast messages are used for name registration and resolution.

Overview

Name resolution is the process of converting the name of a host on the network into a network address (such as an Internet Protocol [IP] address). Name resolution must be performed in order to establish communication over a Windows NT network. B-node is one of four basic methods supported by Windows NT for resolving NetBIOS host names—that is, computer names—into IP addresses.

If a computer running Windows NT is configured as a B-node machine, it always uses broadcasts to resolve names of other hosts on the network. For example, if a B-node machine wants to communicate with another machine with the NetBIOS name SERVER7 (for example, if it wants to connect to a shared resource on SERVER7), the B-node machine broadcasts a packet containing a NetBIOS name query request. If SERVER7 receives the packet, it responds by returning a frame containing its IP address. If SERVER7 is off line or fails to return a response, the B-node client will be unable to establish a connection with SERVER7.

As a name resolution method, B-node is flawed in two ways:

- Since broadcast packets are used, B-node consumes network bandwidth and can degrade overall network communication in a busy network.
- Since routers are usually configured to not forward broadcast packets, B-node clients can resolve only the NetBIOS names of hosts on the client's local subnet.

A better approach to NetBIOS name resolution on Windows NT networks is to configure clients as H-node machines and use a Windows Internet Naming Service (WINS) server. H-node is a NetBIOS name resolution method that combines B-node and P-node.

Notes

On Windows 2000 and Windows .NET Server networks, the Domain Name System (DNS) is the preferred name resolution scheme, and NETBIOS can be disabled when there are no longer any downlevel Windows NT machines left after an upgrade is complete. Note, however, that Windows 2000, Windows XP, and Windows .NET Server systems based on the Active Directory directory service must be configured with the IP address of a WINS server in order to communicate with any Windows-based systems that are not Active Directory–based, including other Windows 2000, Windows XP, and Windows .NET Server systems.

See Also: *H-node, M-node, NetBIOS name resolution, P-node*

bonding

A term used to describe a variety of different technologies for aggregating multiple wide area network (WAN) links together to form a single fatter pipe.

Overview

In Integrated Services Digital Network (ISDN) and T-carrier transmission technologies, bonding provides a way of combining multiple DS0 channels from different circuits into a single, faster data transmission channel. This is accomplished using inverse multiplexing technologies together with special techniques for resolving the timing differences found among groups of different circuits.

ISDN Bonding is typically found in Basic Rate Interface ISDN (BRI-ISDN) where it is used to combine the two 64-kilobits-per-second (Kbps) B channels into a single 128-Kbps data transmission channel. Several different bonding protocols can be implemented for BRI-ISDN services, a common one being Multilink PPP (MPPP), which is used for asynchronous bonding.

Bonding must be supported by the ISDN devices at both ends of the ISDN link. Typically, one of the B channels is designated as responsible for initiating the bonding process. Many ISDN terminal adapters can override bonding when the user wants to place a regular Plain Old Telephone Service (POTS) phone call. For example, you might be using ISDN for high-speed Internet access with both B channels bonded to give you 128-Kbps (or 14-kilobyte-per-second [KBps]) access. Then, if you suddenly pick up a phone connected to the terminal adapter's POTS jack, bonding stops and the second B channel is freed up for the phone call. Once the call is complete, bonding will resume.

Another WAN technology that uses bonding is digital subscriber line (DSL). By configuring the DSL Access Multiplexer (DSLAM) at the service provider's central office (CO), hardware bonding can be implemented to link multiple DSL connections into a single high-bandwidth pipe.

An alternative to hardware bonding for DSL is customer premises equipment (CPE) bonding in which Multilink PPP is used to aggregate multiple DSL circuits at the customer premises instead of the DSLAM. This newer form of bonding has the advantage of being easier to deploy and configure than hardware bonding, which often requires costly upgrades of DSLAMs. A market example is Netopia, a DSL service provider that offers bonding of up to four Internet Digital Subscriber Line (IDSL) lines.

DSL bonding has several advantages:

- Customers requiring greater bandwidth than can be afforded by a single DSL link can use bonding to deploy better than T1 services for much less the cost of a T1 line.
- Customers who are too far from their telco CO can use bonding to boost DSL carrying capacity to typical DSL speeds at twice the normal distance from customer premises to CO. For example, Netopia's IDSL bonding can provide up to 576 Kbps at distances up to 35,900 feet (10,940 meters) from the CO, which is almost double the normal DSL limiting distance of 18,000 feet (5500 meters).

See Also: *Digital Subscriber Line (DSL), Integrated Services Digital Network (ISDN), Multilink Point-to-Point Protocol (MPPP)*

boot

A term used to refer to the process of starting a computer, as in the phrase, "Please boot the computer."

Overview

The term *boot* also refers specifically to the series of steps by which a computer locates and loads the operating system once the power is turned on. This series of steps is usually referred to as the boot sequence or boot process, and it depends on both the type of operating system installed on the machine and the type of hardware platform (for example, x86 platform or Alpha platform).

The term *warm boot* refers to resetting the system or rebooting using Ctrl+Alt+Delete. The power to the system is not interrupted during a warm boot, but the boot process starts again from the beginning using the system basic input/output system (BIOS).

The term *cold boot* refers to shutting down a computer and actually turning off the power source and then turning it back on. Cold boots are sometimes necessary after installing or configuring some legacy hardware devices to ensure that the devices are properly initialized. For example, if you change the configuration parameters of an internal modem, you sometimes need to cold boot your system for these changes to take effect.

See Also: *boot files, boot process*

boot files

Files needed to boot an operating system on a computer.

Overview

Every operating system has its own set of boot files needed to locate, load, and initialize the operating system during the boot sequence. For example, MS-DOS and Windows 3.*x* use the hidden files Io.sys and Msdos.sys and the file Command.com. Configuration information stored in the text files Config.sys and Autoexec.bat is also used during the process.

On Windows 95, Windows 98, and Windows Millennium Edition (Me), the files used for booting are Io.sys, Msdos.sys, and Win.com, with the files Config.sys and Autoexec.bat used optionally to support legacy hardware.

The files needed to boot Windows NT vary depending on whether the x86 or Alpha processor platform is used.

The files needed to boot Windows 2000, Windows XP, and Windows .NET Server (and Windows NT on x86) include the following:

- Boot.ini
- Bootsect.dos
- Hal.dll
- Ntdetect.com
- Ntbootdd.sys
- Ntldr
- Ntoskrnl.exe

The Windows 2000, Windows XP, and Windows .NET Server boot process also makes use of other files, including device drivers and the system hive.

See Also: *boot, boot process*

Boot.ini

A file used to create the boot loader menu in Windows 2000, Windows XP, and Windows .NET Server.

Overview

Boot.ini is a hidden, read-only text file on the root of the system partition of a Microsoft Windows 2000, Windows XP, or Windows .NET Server machine. The boot loader menu is used on dual-boot and multiboot systems to select which operating system (Windows 2000 or some other operating system) to boot. The Boot.ini file creates this menu, which normally is only displayed if more than one operating system is installed on the machine.

Examples

A typical Boot.ini file for a default Windows 2000 installation might look like this:

```
[boot loader]
timeout=30
default=multi(0)disk(0)rdisk(0)partition(1)\
WINNT
[operating systems]
multi(0)disk(0)rdisk(0)partition(1)\
WINNT="Microsoft Windows 2000 Professional"
/fastdetect
```

You can see a close correspondence between the appearance of the Boot.ini file and the boot loader menu, which the Ntldr program creates during the Windows NT boot sequence.

A Boot.ini file for a dual-boot system configured to boot to either Windows 2000 or Windows 98 usually looks like this:

```
[boot loader]
timeout=30
default=multi(0)disk(0)rdisk(0)partition(1)\
WINNT
[operating systems]
multi(0)disk(0)rdisk(0)partition(1)\
WINNT="Microsoft Windows 2000 Professional"
/fastdetect
C:\="Microsoft Windows"
```

The last line of the file is the same for booting to any MS-DOS–based operating system, including Windows 95, Windows 98, and Windows Millennium Edition (Me).

See Also: *boot, boot files, boot loader menu, boot process*

boot loader menu

A menu that appears when you boot a Microsoft Windows 2000, Windows XP, or Windows .NET Server computer configured for dual-boot or multiboot operation with other operating systems.

Overview

The boot loader menu appears during the boot loader phase of Windows NT startup, and it is displayed by the Windows 2000, Windows XP, and Windows .NET Server loader program called Ntldr. The boot loader menu allows you to select the particular operating system you want to run on a dual-boot or multiboot system and to use optional boot-time switches for booting Windows 2000, Windows XP, and Windows .NET Server in various enhanced ways or for troubleshooting purposes. The table summarizes some of the more commonly used boot-time switches used in Boot.ini.

Some Common Boot-Time Switches Used in Boot.ini

Switch	*Description*
/3GB	Used only with Windows 2000 Advanced Server to increase user address space from 2 gigabytes (GB) to 3 GB
/basevideo	Starts Windows 2000 using generic Video Graphics Adapter (VGA) video
/bootlog	Creates a log, called Ntbtlog.txt, of steps in the boot process
/fastdetect	Skips enumeration of serial and parallel devices during the boot process (included by default)
/numproc=	Specifies the number of CPUs to use on a symmetric multiprocessing (SMP) system
/sos	Lists the device drivers marked to load at boot time and displays other information

Notes

The boot loader menu is created by the Boot.ini file. This file can be edited using a text editor such as Notepad, but this should be done with care as mistakes could render your system unbootable.

See Also: *boot, boot files, Boot.ini, boot process*

BOOTP

Stands for bootstrap protocol, a Transmission Control Protocol/Internet Protocol (TCP/IP) protocol and service that allows diskless workstations to obtain their IP address, other TCP/IP configuration information, and their boot image file from a bootstrap protocol (BOOTP) server.

See: *bootstrap protocol (BOOTP)*

boot partition

The partition of a disk on which Microsoft Windows 2000, Windows XP, or Windows .NET Server installs its core operating system files.

Overview

The core operating system files for Windows 2000, Windows XP, and Windows .NET Server are typically stored in \Winnt and its subdirectories. The \Winnt directory and its system files are located on what is referred to as the boot partition (by a strange choice of terminology, the boot files in Windows 2000, Windows XP, and Windows .NET Server are stored on the system partition).

The choice of which partition is to be the boot partition is made during installation of Windows 2000, Windows XP, and Windows .NET Server and cannot be changed afterward. An important consideration when installing Windows 2000, Windows XP, and Windows .NET Server is designating a boot partition that has sufficient free space to contain the various operating system files together with all the optional and future components such as device drivers.

Notes

The boot partition can be the same as or different from the system partition.

See Also: *boot process, system partition*

boot process

The series of steps that occurs when an operating system boots on a machine.

Overview

Each operating system has its own particular boot sequence and uses its own specific set of boot files. Knowledge of the boot sequence for a particular operating system can aid in troubleshooting problems booting a machine on which that operating system is installed. For example, from messages displayed during the boot process, a technician can often determine whether a particular boot file is missing or corrupt.

The following is a brief summary of the boot sequence for the Microsoft Windows 2000 operating system (the Windows XP and Windows .NET Server boot sequences are similar). Note that the actual boot process involves more than 100 different steps and that this description gives only an overview of the process.

- **Preboot:** The boot process can take place only because during installation Windows 2000 Setup writes boot code (a short series of executable instructions) on the master boot record (MBR) located on the first sector of the first hard disk. The MBR also contains the partition table identifying which partition is the active (bootable) partition that contains the operating system boot files. Setup also creates a file called Boot.ini that is used to display a boot loader menu on systems configured for dual-booting or multibooting to Windows 2000 and other operating systems.
- **Ntldr:** When a Windows 2000 system is powered on, the basic input/output system (BIOS) reads the MBR into memory and transfers control to the MBR, which then finds, loads, and executes Ntldr, a key Windows 2000 executable boot file. When

Ntldr starts, the processor is still running in 16-bit real mode, and the first thing Ntldr does is switch the processor to 32-bit protected mode. Ntldr then creates page tables and enables paging. At this point, if the boot or system drive is on a Small Computer System Interface (SCSI) drive, Ntldr loads Ntbootdd.sys, which functions as a device driver for the drive. Once this stage is passed, Ntldr clears the screen and if the system is configured for multiboot operation, it then displays the boot loader menu generated using Boot.ini (this menu is not displayed if the only operating system installed is Windows 2000 itself). Assuming single-boot mode, Ntldr then locates the system directory (usually \Winnt), clears the screen again, displays the "Starting Windows" progress bar, and begins loading additional files including the kernel (Ntoskrnl.exe); and the hardware abstraction layer, or HAL (Hal.dll), reads the SYSTEM hive to determine which other device drivers to load, loads and initializes the file system and device drivers needed, and various other tasks. Then Ntldr calls Ntoskrnl.exe for the next stage of the boot process.

- **Ntoskrnl.exe:** The operating system kernel Ntoskrnl.exe performs a two-phase initialization that consists of more than 30 different steps that are too involved to explain here. As these steps are performed, the Starting Windows progress bar moves toward 100 percent, at which time the Session Manager subsystem (Smss) is initialized.
- **Smss:** The role of Smss is to create the user-mode environment that provides the graphical user interface (GUI) by which the user completes the boot process and accesses the system. Smss performs a whole series of steps ending in its main thread waiting for the Winlogon process to generate the logon dialog box.
- **Logon:** Once the logon dialog box is generated, the user enters the necessary credentials, is authenticated, and the desktop user interface appears. The boot process is now complete.

See Also: *boot, boot files*

Bootsect.dos

A boot file in Microsoft Windows 2000, Windows XP, and Windows .NET Server used to support dual-boot scenarios with MS-DOS–based operating systems such as Windows Millennium Edition (Me).

Overview

When the boot loader menu appears during the boot process on a dual-boot Windows 2000, Windows XP, or Windows .NET Server machine, the user selects the operating system to boot. If an MS-DOS–based operating system such as Windows 95, Windows 98, or Windows Me is selected, the Ntldr program immediately switches the processor back to 16-bit real mode and then loads Bootsect.dos and turns control of the boot process over to it. Bootsect.dos then continues with an MS-DOS-specific boot process leading to initialization of the selected operating system.

Bootsect.dos contains the location of the partition boot sector that existed on the partition prior to the installation of Windows 2000, Windows XP, or Windows .NET Server. Thus, Bootsect.dos enables the system to locate and load the alternate operating system. Bootsect.dos is not loaded during a normal boot of the Windows 2000, Windows XP, or Windows .NET Server operating system.

See Also: *boot files, boot process*

bootstrap protocol (BOOTP)

A Transmission Control Protocol/Internet Protocol (TCP/IP) protocol and service that allows diskless workstations to obtain their IP address, other TCP/IP configuration information, and their boot image file from a bootstrap protocol (BOOTP) server.

Overview

The network interface card (NIC) on these diskless workstations contains a programmable read-only memory (PROM) chip containing code necessary to initialize the client.

When a bootstrap protocol (BOOTP) client is started, it has no IP address, so it broadcasts a message containing its MAC address onto the network. This message is called a "BOOTP request," and it is picked up by the

BOOTP server, which replies to the client with the following information that the client needs:

- The client's IP address, subnet mask, and default gateway address
- The IP address and host name of the BOOTP server
- The IP address of the server that has the boot image, which the client needs to load its operating system

When the client receives this information from the BOOTP server, it configures and initializes its TCP/IP protocol stack, and then connects to the server on which the boot image is shared. The client loads the boot image and uses this information to load and start its operating system.

BOOTP is defined in RFCs 951 and 1084. The Dynamic Host Configuration Protocol (DHCP) was developed as an extension of BOOTP.

Notes

The term *bootstrap protocol* (or *boot protocol*) comes from the idea of lifting yourself up by your own bootstraps—something that is obviously difficult to do. In other words, how does a client machine start up when it initially has neither an IP address nor an operating system? BOOTP makes this difficult task possible.

Most UNIX servers support diskless workstations using the BOOTP protocol. BOOTP is implemented on UNIX servers using the bootpd daemon. Certain aspects of BOOTP are supported by Microsoft Windows 2000, Windows XP, and Windows .NET Server, but the protocol is rarely used in Windows networks.

See Also: *Dynamic Host Configuration Protocol (DHCP)*

boot volume

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, the volume that has the operating system files.

Overview

The boot volume can be the same as or different from the system volume, and it can be formatted in either NTFS file system (NTFS) or file allocation table (FAT). The term *volume* indicates that we are referring here to dynamic storage, which enables volumes to be created and managed. By contrast, basic storage enables the creation and management of partitions instead.

See Also: *boot partition*

Border Gateway Protocol (BGP)

An exterior gateway protocol (EGP) used on the Internet to provide loop-free routing between different autonomous systems (ASs).

Overview

The Internet consists of large, independently administered networks called ASs connected by routers to form a single, enormous internetwork. ASs themselves are smaller internetworks and contain routers that exchange routing information with each other using various interior gateway protocols (IGPs) such as Routing Information Protocol (RIP) and Interior Gateway Routing Protocol (IGRP). These IGPs do not scale well enough to handle exchange of routing information between the border routers that join various ASs together, however, and for such purposes exterior gateway protocols (EGPs) are used, the de facto standard EGP for the Internet being the Border Gateway Protocol (BGP).

Like RIP and IGRP, BGP is based on the distance vector routing algorithm (or more specifically on a variant called path-vector), which enables groups of routers to share their routing information in a highly efficient and scalable manner. The routing information BGP exchanges between boundary routers is called Network Layer Reachability Information (NLRI), and specifies which other AS's data can be forwarded to from the local AS and the most efficient routes (best path) for doing this. BGP also can ensure against routing loops occurring.

BGP was developed in 1982 as the successor to EGP and was formalized in RFCs 827 and 904. Since then it has gone through several versions, with the current version being BGP 4, specified by RFC 1771. BGP 4 includes a number of enhancements over earlier versions, including support for

- Route and path aggregation
- Route, path, and community filtering
- Routing policies
- Advertising Internet Protocol (IP) prefixes
- Classless Interdomain Routing (CIDR)

Architecture

BGP is a connection-oriented protocol that runs on top of Transmission Control Protocol (TCP) to provide reliable transport of routing updates. TCP port 179 is used for forming connections between BGP-enabled routers, and incremental updates to routing tables only are transmitted, which makes BGP efficient in terms of bandwidth utilization (other distance-vector routing protocols exchange entire routing tables at regular intervals, which makes them scale poorly to internetworks the size of the Internet).

To use BGP, your internetwork must first be assigned an Autonomous System Number (ASN). You can get one by contacting your regional Internet registry, such as the American Registry for Internet Numbers (ARIN) for North and South America, Reseaux IP Européens (RIPE) for Europe, or the Asian-Pacific Network Information Center (APNIC) for Asia. ASNs for public internetworks are assigned from the range 1 through 64511.

BGP-speaking routers within an AS establish peering relationships with each other to form a loop-free routing mesh. The first update between two peers includes all known routes on the network, while succeeding updates are incremental.

Implementation

BGP needs to be implemented only in very large internetworks. When smaller internetworks using IGRP grow to the point that IGRP performs poorly, BGP can be used to partition the internetwork into two autonomous systems for better routing performance.

Another situation where you might implement BGP is if your corporate internetwork is multihomed, that is, has several dedicated connections to the Internet using different Internet service providers (ISPs). In this case, you can use BGP to balance the load between the Internet connections and provide redundancy.

Finally, if your corporate internetwork is being used as a transit network to connect other networks to the Internet, you need to employ BGP.

If you plan to implement BGP, make sure your router is powerful enough to handle it, especially if your internetwork will be directly connected to a regional ISP's network.

Notes

There are actually two flavors of BGP, though this distinction is not widely used in the literature:

- **EBGP (Exterior BGP):** The form used for communication between different ASs for BGP-enabled routers. This is also simply known as BGP and is the version described in this article.
- **IBGP (Interior BGP):** The form used for communication within an AS for BGP-enabled routers.

See Also: *autonomous system (AS), exterior gateway protocol (EGP), routing protocol*

border router

A router that connects two different autonomous systems (ASs).

Overview

The Internet consists of a collection of thousands of different independently administered large internetworks called ASs. Border routers are high-speed backbone routers that connect these different internetworks.



Border router. *Using a border router to connect two autonomous systems.*

Border routers use the Border Gateway Protocol (BGP) as the routing protocol for exchanging route information between them. Since the routing tables for border routers are large and rapidly growing as the Internet itself expands and evolves, border routers need to be high-performance, with at least 64 kilobytes (KB) of memory to hold these routing tables. Without these border routers and BGP, the Internet would be limited to a much smaller size than it is.

See Also: *autonomous system (AS), Border Gateway Protocol (BGP), Internet, router*

bottleneck

A situation that occurs when computer and network systems and components are unable to meet the demand placed upon them by real-world situations.

Overview

A bottleneck is essentially the particular network component or server subsystem that is causing the problem. For example, if users on a Microsoft Windows 2000–based network are complaining that it takes too long to log on when they arrive at the office in the morning, the bottleneck and its potential resolution might be

- Not enough domain controllers to handle logon requests (A solution: add more domain controllers)
- The domain controller does not have enough memory to process large numbers of simultaneous logons (A solution: add more random access memory [RAM])
- Network bandwidth is saturated in the morning with directory replication traffic (A solution: reschedule directory replication or upgrade to 100 megabits per second (Mbps) Ethernet)

The etymological reason for describing each of the above situations as a “bottleneck” is that a bottle’s thinnest point is its neck and hence the neck controls the flow of liquid should the bottle be inverted. In the same way, the performance of an application running on a computer system can be limited by the amount of physical memory, read/write speed of the disk subsystem, throughput of the network interface card, speed of the CPU, and other parameters—any of these components (or several of them) could be a bottleneck that prevents the application from performing as desired. Or more generally, the performance of a browser accessing Web content on a corporate Intranet could be affected by overworked name servers for Domain Name System (DNS) name resolution, an insufficient number of domain controllers to handle authentication requests, slow or faulty routers joining subnets within an internetwork, misconfigured firewalls, and a host of other issues that could represent bottlenecks.

Notes

Troubleshooting bottlenecks is the science (sometimes the art) of identifying, isolating, and correcting issues that limit application performance. Valuable tools for ferreting out bottlenecks in Windows 2000–, Windows XP–, and Windows .NET Server–based networks are the Performance console, one of the administrative tools in Windows 2000, Windows XP, and Windows .NET Server, and Task Manager. For system performance, there are four main types of bottlenecks:

- **Processor bottlenecks:** If a CPU's utilization is constantly running near 100 percent when a certain application is running, it might indicate a processor bottleneck, in which case the application is said to be processor-bound. Upgrading to a faster processor or adding a second processor to a multiprocessor-capable motherboard might correct the problem.
- **Memory bottlenecks:** These bottlenecks arise when the system has insufficient RAM, which generally results in excessive paging and overall poor performance. Adding more RAM is often the simplest and cheapest solution to improve performance of most computer systems.
- **Disk bottlenecks:** Sometimes the hard disk subsystem cannot keep up with read/write requests generated by an application. In such a case the application is said to be disk-bound, and upgrading to a faster disk subsystem, implementing disk striping, or using a storage area network (SAN) can improve performance. Often, however, when disk activity is consistently too high, this simply indicates excessive paging caused by insufficient RAM. In this situation, what appears at first to be a disk bottleneck is actually one of memory instead.
- **Network bottleneck:** With today's Gigabit Ethernet (GbE) networks, older servers simply cannot pipe data fast enough from their system bus into their GbE network cards to get it onto the network. What seems to be a network bottleneck here is really caused by the inadequate speed of the system bus, and upgrading the motherboard is the only real option. True network bottlenecks are more difficult to find and may result from misconfigured routers, network cards running in promiscuous mode, excessive broadcast overhead from using too many protocols on the network, poor planning of network topologies, and many other issues.

bounce

An effect that happens to signals on a bus topology network when the ends of the bus are improperly terminated or unterminated.

Overview

A signal that is placed on a bus that is unterminated will continue to reflect from the end of the bus until that signal is attenuated by the impedance of the cable. Another situation that can cause signals to bounce is a break in the cable, which essentially creates two unterminated ends for the two segments.

The effect of signal bounce on baseband networks such as Ethernet is serious, since the transceivers on the network interface cards (NICs) attached to the bus interpret the problem as a collision and stop transmitting. This collision occurs because the signal is colliding with its own reflection. Once the proper termination is applied to the bus, network communication can resume.

See Also: *terminator*

bps

Stands for bits per second, a unit used for measuring the speed of transmission of data on a network of computers.

See: *bits per second (bps)*

breakout box

A troubleshooting tool used to determine the wiring of an RS-232 interface on a networking device or computer.

Overview

A breakout box can be inserted between two RS-232 devices to determine which wires are active. Breakout boxes are useful in troubleshooting RS-232 connection problems resulting from a manufacturer's device not using standard pinning.

Breakout boxes are specific examples of a more general category of network testing equipment called "status monitors." Status monitors are available for testing a variety of serial interfaces, including RS-232, RS-449, V.35, and X.21. They generally come with a variety of connectors and are quick and easy to use for isolating problems with serial transmission connections in networking, telecommunications, and industrial settings.

See Also: *serial transmission*

BREW

Stands for Binary Runtime Environment for Wireless, a platform from QUALCOMM for developing applications for cellular communications systems.

See: *Binary Runtime Environment for Wireless (BREW)*

bridge

A networking component used either to extend or to segment networks.

Overview

Bridges work at the data-link layer of the Open Systems Interconnection (OSI) model of networking. They can be used to

- Segment networks into smaller collision domains
- Join dissimilar media such as unshielded twisted-pair (UTP) cabling and fiber-optic cabling
- Join together different network architectures such as Token Ring and Ethernet (called a translation bridge)



Bridge. *The three basic types of bridge.*

Bridges regenerate signals but do not perform any protocol conversion, so the same networking protocol (such as Transmission Control Protocol/Internet Protocol [TCP/IP]) must be running on both network segments connected to the bridge. Bridges can also support Simple Network Management Protocol (SNMP), and they can have other diagnostic features.

Bridges come in three basic types:

- **Local bridges:** Directly connect local area networks (LANs) (called a transparent bridge for Ethernet networks and a source-routed bridge for Token Ring networks)
- **Remote bridges:** Can be used to create a wide area network (WAN) link between two LANs
- **Wireless bridges:** Can be used to join LANs or connect remote stations to LANs without wiring between them

Architecture

Bridges operate by sensing the source MAC addresses of the transmitting nodes on the network and automatically building an internal routing table. This table is used to determine which connected segment to route packets to, and it provides the filtering capability that bridges are known for.

If the bridge knows which segment a packet is intended for, it forwards the packet directly to that segment. If the bridge does not recognize the packet's destination address, it forwards the packet to all connected segments except the one it originated on. And if the destination address is in the same segment as the source address, the bridge drops the packet.

Bridges also forward broadcast packets to all segments except the originating one.

Advantages and Disadvantages

Bridges are less expensive than routers and can easily be used to add more stations to a network. They are transparent to high-level protocols and can even be used with nonroutable protocols that routers cannot handle.

Bridges have the disadvantages, however, of increasing the chance of broadcast storms occurring on a network and are not as efficient in larger networks as routers are.

Implementation

Use bridges to reduce network congestion and improve performance by segmenting busy Ethernet networks into smaller collision domains. You can also use bridges to connect segments more efficiently than repeaters and to join dissimilar networks such as Ethernet and Token Ring. Remote bridges can be used to create WAN links.

A poorly placed bridge can actually worsen network performance. For example, if you use a bridge to divide users who belong to the same department and frequently communicate with one another over the network, this might actually slow down communication among users by creating a bottleneck. It is better to use bridges to join together separate departmental LANs on which intradepartmental traffic is greater than interdepartmental traffic.

When using bridges to connect networks, make sure that only one path leads to any destination node on the network; otherwise, frames could become locked in loops and circle the network endlessly, causing a network storm.

Notes

Switches and bridges function similarly, but although switches can have many ports, bridges only have two.

See Also: *remote bridge, wireless networking*

bridgehead server

A server that acts as an endpoint of communications with another site.

Overview

In Microsoft terminology, bridgehead servers occur in several contexts. For example, in Microsoft Exchange Server, a bridgehead server in one site is responsible for routing messages through a connector to a similar server in a different site. More generally, in Microsoft Windows 2000 and Windows .NET Server, a bridgehead server is a domain controller that replicates Active Directory directory service information with domain controllers in other sites. The first domain controller in each site assumes the role of Inter-Site Topology Generator and determines which domain controllers in the site will be selected as bridgehead servers.

BRI-ISDN

Stands for Basic Rate Interface ISDN, the slower version of Integrated Services Digital Network (ISDN) communications (the faster being Primary Rate Interface [PRI]-ISDN).

See: *Basic Rate Interface ISDN (BRI-ISDN)*

broadband

A signaling technology that sends signals simultaneously over a range of different frequencies as electromagnetic waves. The opposite of baseband.

See: *broadband transmission*

broadband Internet access

Generally refers to various technologies such as digital subscriber line (DSL) and cable modems that provide high-speed Internet access for residential and business customers.

Overview

The growth and evolution of the Internet and World Wide Web over the last 10 years has seen simple text-based Web pages become replaced with media-rich content that includes graphic files, sound clips, Shockwave animations, and streaming media. In addition text-based Simple Mail Transfer Protocol (SMTP) e-mail has become heavy with large attachments including Microsoft Word files, spreadsheets, images, and other content. These changes in content forms require high-bandwidth Internet connections, and traditional dial-up modem connections (even 56K) feel inadequate to many users.

As a result, the broadband Internet access market has taken off in the last couple of years, with widespread deployment of cable modem and DSL connections now in the millions. In addition, for remote locations, companies such as StarBand Communications and Digistar provide satellite-based broadband Internet access with download speeds in the 2-megabit-per-second (Mbps) range (for more on satellite-based broadband, see the article "broadband wireless communications" elsewhere in this chapter).

The two most commonly deployed broadband Internet access solutions are cable modems and variants of DSL. Cable modems are a low-cost solution that is easier to deploy than DSL, but they are generally only available in residential markets where the cabling infrastructure has already been widely deployed. DSL is a more complex solution offered by telcos but has the advantage that connections are dedicated rather than shared: a DSL connection offers guaranteed bandwidth, while the effective bandwidth for a cable modem connection depends on the number of users to which it is deployed in a given area (cable modem users are essentially connected in a LAN and so share the available bandwidth of the LAN).

Speed is the main benefit of various broadband Internet access technologies, and a comparison is useful:

- **Copper DSL:** Running various flavors of DSL such as Asymmetric Digital Subscriber Line (ADSL) and Symmetric Digital Subscriber Line (SDSL) over the copper local loop to subscribers can offer speeds of up to 8 Mbps, but download speeds of 1 or 2 Mbps are more common (upload speeds may be less).
- **Fiber DSL:** By running fiber to the curb, significantly higher DSL speeds of up to 60 Mbps or higher can be achieved, but the cost is high due to the need to deploy a new fiber infrastructure. This is an attractive solution for businesses, however, especially where telcos are rolling out such infrastructures.
- **Cable modem:** Typical cable modem speeds are between 2 and 6 Mbps, but effective speeds may be much less for users due to the shared-bandwidth nature of this solution.

Uses

In addition to providing the ability to surf the Web at high speeds or send Christmas card images through e-mail, broadband Internet access is seen by increasing numbers of companies as an idea solution for supporting the remote workforce of home-based telecommuters. By using a cable modem or DSL connection and setting up a Virtual Private Network (VPN) connection using Microsoft Windows 2000, Windows XP, and Windows .NET Server, or some other platform, employees can work from home across secure connections to their company intranet.

Large companies that choose DSL or other broadband solutions as replacements for or backups to existing leased-line wide area network (WAN) links need to consider things such as service level agreements (SLAs), Quality of Service (QoS) guarantees (usually nonexistent for DSL), the number of Internet Protocol (IP) addresses that can be provided with the connection (usually under 150 for DSL), deployment times (usually weeks, but sometimes months), and business pricing (which is significantly more than residential pricing).

Advantages and Disadvantages

One important limitation of DSL as a broadband Internet access solution is that it is only viable within a small distance from the telco's central office (CO). This distance is typically about 18,000 feet (5500 meters) for the most popular implementation of DSL; that is, ADSL. Cable modem provisioning does not suffer from this distance limitation, but its deployment is limited to areas where the necessary cabling infrastructure is already present, which excludes most business and industrial parks.

Cable modems also have the additional advantage of being simpler to implement than DSL, which often requires professional installation services. On the other hand, DSL is intrinsically more secure than cable modems since DSL connections are dedicated—it is just your customer premises and the DSL provider on the network. With cable modems, all users in a given service area are on a shared LAN, and if your connection is not secured using a firewall, then other users in your neighborhood may be able to view and access shared files on your system.

Marketplace

Copper DSL is available from most telcos and carriers, including Sprint Corporation, Covad Communications Company, the various "baby Bells," and many others. Fiber DSL is being piloted by Pacific Bell Telephone Company and others.

Most cable companies provide cable modem access now, with AT&T being a major player in this market.

Prospects

While broadband Internet access services are becoming more and more widely deployed in the United States, the marketplace tends to be fractured, and solutions and equipment from one vendor often have interoperability issues with those from other vendors. This is especially the case with broadband wireless technologies.

One country that is taking a more aggressive approach to broadband is Japan. While the Japanese economy largely missed out on the narrowband Internet and PC revolution of the 1990s, the country is making strong efforts to become the world leader in implementing broadband Internet technologies, with companies such as Sony taking the lead.

See Also: *broadband transmission, broadband wireless communications, cable modem, Digital Subscriber Line (DSL), Internet access, xDSL*

broadband ISDN (B-ISDN)

The broadband transmission counterpart of Integrated Services Digital Network (ISDN).

Overview

Broadband ISDN (B-ISDN) encompasses a set of International Telecommunication Union (ITU) standards and services designed to provide an integrated digital network for audio, video, and data transmission. Instead of using the copper media used in ordinary ISDN, broadband ISDN uses fiber-optic and radio media.

Broadband ISDN is designed to use the cell-switching transport technology of Asynchronous Transfer Mode (ATM) together with the underlying physical transport mechanisms of Synchronous Optical Network (SONET). Broadband ISDN standards and technologies were intended to provide high-speed digital connectivity for homes and businesses, but the technology was never widely deployed and has been superseded by Digital Subscriber Line (DSL) and other high-speed telco services.

See Also: *Digital Subscriber Line (DSL)*

broadband transmission

A signaling technology that sends signals simultaneously over a range of different frequencies as electromagnetic waves. The opposite of baseband transmission.

Overview

Broadband transmissions are divided into multiple bands or channels by multiplexers using a multiplexing scheme such as frequency-division multiplexing (FDM). Each channel has a carrier frequency that is modulated to carry the signal from a given source. At the receiving station, multiplexers separate the various signals. Guard bands are used to prevent interference among channels.

Broadband signals are unidirectional—traveling in only one direction at a time—so a broadband system can generally either transmit or receive but cannot do both simultaneously. Broadband signals can be regenerated using amplifiers in order to travel longer distances before becoming attenuated.

Uses

Broadband transmission is typically used for environments in which video, audio, and data need to be transmitted simultaneously. Cable television systems are based on broadband transmission technologies, as are satellite-based television services. Examples of broadband services in the computer networking arena include T-carrier services, Asynchronous Transfer Mode (ATM), and the various flavors of Digital Subscriber Line (DSL).

See Also: *Asynchronous Transfer Mode (ATM), baseband transmission, broadband Internet access, broadband wireless communications, Digital Subscriber Line (DSL), T-carrier*

broadband wireless communications

Generally refers to high-speed wireless communications systems where data rates are approximately 1 megabit per second (Mbps) or higher.

Overview

Broadband wireless (or wireless broadband) is an emerging high-speed communications technology that is being largely driven by the Internet access market. Broadband wireless systems achieve data rates comparable to Digital Subscriber Line (DSL) or cable modems and can be used in environments where these technologies are unavailable or difficult to deploy, such as isolated rural areas. And like DSL and similar technologies, broadband wireless is an always-on solution that provides fast access to the Internet and can be used in other corporate wide area network (WAN) scenarios as well.

Broadband wireless basically comes in three forms: fixed wireless, mobile wireless, and satellite-based.

Fixed broadband wireless is a technology that is gaining significant market share at all levels, from small businesses to the enterprise. In a typical fixed wireless scenario, a business requiring high-speed Internet access or a WAN connection deploys a broadband radio transmitter/receiver with a fixed unidirectional dish or horn antenna pointed toward the service provider's antenna. A clear line of sight is required between the customer premises antenna and the provider's antenna, which generally means customers deploy their antenna on their rooftop and providers deploy antennas on high towers, skyscrapers, or nearby mountains. Fixed wireless broadband can be based on various different technologies including Local Multipoint Distribution System (LMDS), Multichannel Multipoint Distribution System (MMDS), and others. Fixed broadband wireless communications systems are based on spread-spectrum communications technologies and may use frequencies from the Industrial, Scientific, and Medical (ISM) band's 2.5 GHz range up to millimeter wavelengths in the 66 gigahertz (GHz) range. Dedicated point-to-point microwave links can offer data transmission speeds of 10 Mbps or higher, but speeds of 1 or 2 Mbps are more common.

Mobile broadband wireless solutions are still in planning stages in most countries and regions, with Europe and Asia in the lead with planned rollouts of 3G cellular technologies such as Wideband Code Division Multiple Access (WCDMA) and Universal Mobile Telecommunication System (UMTS). Nevertheless, widespread deployment of these technologies probably will not happen until 2005 or later.

Mobile broadband services are also expected to provide significantly slower speeds than fixed solutions. For example a WCDMA system that provides 2 Mbps for fixed transmission can only support 384 Kbps for mobile (walking) transmission when handoffs are required, and may go as low as 144 Kbps for highway travel.

Satellite-based broadband wireless solutions generally offer speeds of around 2 Mbps, are easy to deploy, and are rapidly becoming more widely available. An in-depth discussion of how this technology works can be found in the article "satellite networking" elsewhere in this book.

Uses

Companies may implement broadband wireless in a variety of scenarios:

- Fixed broadband wireless is often used for providing high-speed Internet access, for streaming video broadcasting from remote locations, and for backup links to leased-lines used for WAN links between branch offices.
- Mobile broadband wireless, when deployed, will probably be used for high-speed Internet access for cell phones, Personal Digital Assistants (PDAs), and other hand-held information appliances.
- Satellite-based broadband wireless is primarily intended to replace enterprise WAN links and for providing high-speed Internet access in remote locations.

Advantages and Disadvantages

A primary advantage of broadband wireless over competing wired broadband technologies such as DSL or cable modems is their ease of setup and the speed at which they can be deployed. Industry reports indicate that DSL services sometimes take weeks to set up, but fixed broadband wireless solutions typically take only a day or two. In the rapidly evolving Internet economy where time-to-market is critical for new startups, deployment speed is a factor that has influenced many new companies in adopting broadband wireless solutions. In addition, many large companies are turning to broadband wireless to replace or provide backup for expensive leased lines such as T1 or E1 at a fraction of the cost of these lines. Some broadband wireless carriers are also looking at providing value-added services such as Voice over IP (VoIP) in the near future as part of their integrated package of services. Broadband wireless systems are also relatively secure because most are based on spread-spectrum wireless communications technologies, which means that signals are scrambled across a large number of frequencies, making it difficult to eavesdrop (a firewall is nevertheless recommended when implementing broadband wireless as this is an always-on solution). Finally, broadband wireless is often the only solution for customers in remote areas requiring broadband Internet access or WAN links.

Besides the line-of-site limitation, broadband wireless does have other disadvantages that need to be considered before deployment. High-frequency broadband wireless platforms such as LMDS are more easily influenced by environmental factors such as weather than systems that use the low-frequency ISM or other low-frequency bands, and that can be a consideration in certain locations. Satellite-based broadband services have a latency on the order of several hundred milliseconds (compared with under 20 msec for most wired land-based systems), which is fine for corporate data transmission but annoying to users for Web browsing.

Marketplace

In the fixed wireless broadband marketplace, many carriers and service providers are starting to provision broadband wireless for business and enterprise customers. Sprint Broadband Direct provisions 2 Mbps MMDS services, typically in a matter of days. MCI WorldCom is also making significant inroads into the MMDS market. Players in the higher-frequency LMDS market include Teligent, NextLink Communications, WinStar Communications, and others. AT&T is, of course, also a major player in the fixed wireless broadband market.

In the mobile wireless broadband market, the emerging players are currently Ericsson and Nokia, with their pre–third generation (3G) broadband cellular initiatives known as 2.5G.

In the satellite-based broadband wireless market, major players include DirecPC and StarBand Communications, both of which offer nationwide coverage. Tachyon also provides 2 Mbps service across the United States.

Notes

The Institute of Electrical and Electronics Engineers (IEEE) is standardizing fixed broadband wireless technologies under the new 802.16 group of standards.

See Also: *802.16, broadband transmission, Digital Subscriber Line (DSL), Internet access, Local Multipoint Distribution Service (LMDS), Multipoint Multichannel Distribution Service (MMDS)*

broadcast domain

The collection of all stations on a network that can receive broadcast messages from any station among them.

Overview

Broadcast domains and collision domains are two different things:

- **Broadcast domains:** These are defined by broadcasting only as all those stations that can receive a broadcast.
- **Collision domains:** These are defined by any type of transmission, including unicasting, multicasting, and broadcasting.

Examples of broadcast domains include

- All stations connected to a given group of hubs or switches
- All stations on an internetwork whose routers are configured to forward broadcasts (not a desirable configuration)
- All stations in a given virtual local area network (VLAN) configured on a group of Ethernet switches.

Notes

Bridges used to segment Ethernet networks divide collision domains but do not divide broadcast domains.

See Also: *collision domain*

broadcast frame

In Ethernet networks, a frame broadcast to every station on the network.

Overview

An Ethernet media access control (MAC)–layer broadcast frame has a hexadecimal MAC address of FF-FF-FF-FF-FF-FF. This hexadecimal address is equivalent to 48 binary “ones.” The meaning of this address in Ethernet is simply that this frame is intended to be received and processed by every connected node on the network.

Broadcast frames are typically generated when network services make announcements of their presence and availability to other hosts on the network. Too many broadcast frames on a network can degrade communication between nodes on the network.

Notes

In routed internetworks, routers are usually configured not to forward broadcast frames to other subnets. The reason is to prevent broadcast storms in one subnet from overwhelming hosts in other connected subnets. As a result of this limitation, however, broadcast frames used as service announcements are usually limited in scope to the local subnet on which the host providing the services is located.

See Also: *broadcasting, broadcast packet, broadcast storm, directed frame, frame*

broadcasting

A network communications method in which a packet or frame is sent simultaneously to all stations on the network.

Overview

Broadcasts take place when broadcast frames (or packets) are sent out over the network. These frames contain a special address that instructs every station on the network to accept and process the frame’s contents.

Broadcasts have various functions on a network, including

- Announcing the availability of network services
- Resolving host names into addresses
- Troubleshooting and testing network connectivity

Examples of Internet Protocol (IP) services that employ broadcasts include

- Address Resolution Protocol (ARP)
- Dynamic Host Configuration Protocol (DHCP)
- Domain Name System (DNS)
- NETBIOS

Broadcasts are usually not an efficient use of network bandwidth, since only one or a few network stations might actually be interested in the information being broadcast. For this reason, directed frames (or packets) are used for most network communication, which involves targeting a packet directly for the intended station. (All other stations ignore the directed packet.) Another alternative is multicasting, which involves a form of limited broadcast to a select group of hosts.

Notes

Certain network conditions, such as certain types of device failure, can generate large numbers of unwanted broadcasts. These broadcast storms can sometimes bring down a network if the condition is not resolved.

Applications that are poorly designed may sometimes employ unnecessary amounts of broadcasting, with resulting degradation of overall network services.

See Also: *broadcast frame, broadcast packet, multicasting, unicasting*

broadcast packet

In Internet Protocol (IP) networks, an IP packet broadcast to every host on the network.

Overview

Broadcasts can be used in any type of IP network, including class A, B, C, D, and E networks. The actual broadcast address depends on the class of network under consideration. For example:

- For a class A network 27.0.0.0 the address for a broadcast packet would be 27.255.255.255.
- For a class B network 139.65.0.0 the broadcast address is 139.65.255.255.
- For a class C network 207.17.125.0 the broadcast address is 207.17.125.255.

The general broadcast address 255.255.255.255 is called a local area network (LAN) broadcast and can be routed to every host on an internetwork if routers are allowed to forward broadcasts. A faulty device that produces excessive 255.255.255.255 packets is said to be “flooding” the internetwork with broadcasts, and this can lead to a condition called a “broadcast storm.”

The common denominator in these examples is 255, which is the decimal representation of the binary octet 11111111. Thus, the LAN broadcast address 255.255.255.255 in binary notation is a series of 32 binary “ones.”

See Also: *broadcasting, broadcast frame, broadcast storm, directed packet, packet*

broadcast storm

A network condition in which so many broadcasts are occurring that normal communication between hosts is disrupted.

Overview

Broadcast storms commonly occur on Ethernet networks where baseband transmission technologies allow only one station to transmit at a time. The presence of broadcast storms often indicates that a networking component is malfunctioning and is continually sending out broadcast messages. A typical situation might be a failed transceiver on a network interface card (NIC) that is continually sending out a stream of binary “ones.”

During a broadcast storm, the wire is continually busy and no other station is able to transmit information over the network. As a result, a broadcast storm essentially brings down the network. Since routers often are not configured to forward broadcast frames between subnets, broadcast storms usually are confined to a single subnet (configuring routers to forward broadcasts is thus a bad idea as a broadcast storm in one subnet could bring down the entire internetwork).

Broadcast storms might also indicate that your network’s bandwidth is nearly saturated and needs to be upgraded.

See Also: *broadcasting*

brouter

Any network device having the capabilities of both a bridge and a router.

Overview

Usually, a brouter acts as a router for one protocol (for example, Transmission Control Protocol/Internet Protocol [TCP/IP]) and a bridge for all other protocols (for example, Internetwork Packet Exchange/Sequenced Packet Exchange [IPX/SPX]). Network services often send their announcements over every protocol on the network, which generates additional traffic and makes it generally disadvantageous to run more than one protocol on a single network.

Brouters are not common anymore, however, and the solution adopted by most network designers nowadays is to use a single protocol for all network communication on the main portion of the network, with gateways connecting to segments running other protocols. The protocol of choice for most internetworking today is TCP/IP.

See Also: *bridge, router*

browse list

The list of available shared network resources on a Microsoft Windows network.

Overview

The browse list is maintained and distributed by the Computer Browser service. The browse list contains a list of all available domains, workgroups, and servers on the network. This list is then distributed to clients who desire to connect to shared resources on the network so that they can locate and connect to these resources.

Essentially, when you are browsing Network Neighborhood in Windows NT or My Network Places in Windows 2000, Windows XP, or Windows .NET Server, you are looking at a representation of the browse list for your locally accessible network.

Notes

The browse list is maintained by the master browser computer, but clients that need it obtain it from backup browsers on the network. If a server or domain is not heard from by the master browser after three announcement periods (amounting to approximately 45 minutes), the server or domain is removed from the browse list.

See Also: *Computer Browser service, election*

browser (Computer Browser service)

Any Microsoft Windows machine that is running the Computer Browser service and participates in updating and maintaining the browse list of shared resources available on the network.

See: *Computer Browser service*

browser (Web browser)

A client application that supports Hypertext Transfer Protocol (HTTP), the language of the World Wide Web.

See: *Hypertext Transfer Protocol (HTTP), Web browser*

browsing

Generally, the process of exploring the shared resources available on a network or the Web content available on the Internet.

Overview

You can browse for shared resources on a Microsoft Windows network using Windows Explorer, My Network Places, and other tools. Browsing a Windows network is made possible by the Computer Browser service, which keeps track of all shared resources on a Windows NT network and communicates this information to clients when they need to access a resource. The Computer Browser service is at the core of the ability to locate shared file and printer resources on a network and maintains the browse list, the list of available shared resources.

Regarding the Internet, the term *browsing* refers to the process of using a Web browser such as Microsoft Internet Explorer, Netscape Navigator, or Opera Software's Opera to view and download Web pages from the Internet. The origin of the term probably stems from the idea of reading magazines, in which you pick up one magazine and skim through its contents, then go to another magazine, and so on. On the Internet, it is even easier. You do not have to "pick up" anything; you simply keep clicking the links.

See Also: *Computer Browser service, Web browser*

BSD

Stands for Berkeley Software Distribution, a family of UNIX operating systems.

Overview

BSD UNIX was developed in the 1970s at the University of California at Berkeley, which licensed the UNIX operating system from AT&T and then made a number of modifications and enhancements, including many common UNIX features such as the vi editor, the C shell, and Transmission Control Protocol/Internet Protocol (TCP/IP) networking.

BSD UNIX and its offshoots constitute one of the two most popular families of UNIX in use today, the other family being UNIX System V and its offshoots. BSD UNIX formed the basis of the SunOS from Sun Microsystems, but Sun later combined features of both BSD and System V into their popular Solaris operating system. BSD UNIX is older than Linux but has not attracted as much attention as Linux has lately.

The major flavors of BSD UNIX popular today include

- **FreeBSD:** A free version of BSD UNIX available for the Intel x86, DEC Alpha, and PC-98 architectures. FreeBSD is the most popular of the BSDs and has a large and active developer community. FreeBSD has been popular with many Internet service providers (ISPs) as the base platform for their Web and mail servers. The current release of FreeBSD is version 4.3.
- **OpenBSD:** A popular version that stresses security with integrated cryptography and support for SSH1 and SSH2. The current release of this operating system is OpenBSD 2.9, and it is also available for free.
- **NetBSD:** Another free version of BSD UNIX that has been incorporated as the base operating system of a number of commercial products. The current release is NetBSD 1.5.1.

Notes

The commercial version BSDi is now known as iXsystems and is licensed by Wind River Systems.

For More Information

For a general overview of BSD flavors, see *www.bsd.org.* FreeBSD can be found at *www.freebsd.org.* OpenBSD can be downloaded from *www.openbsd.org.* NetBSD can be found at *www.netbsd.org.*

See Also: *UNIX*

BSP

Stands for business service provider, an application service provider (ASP) that offers a wide range of online business services that include not just Web hosting and e-commerce services typical of ASPs but also customer relations management, desktop maintenance support, system integration and consulting services, and other value-added business services.

See Also: *application service provider (ASP), xSP*

building-block services

A component of Microsoft Corporation's .NET platform that provides core Extensible Markup Language (XML) Web services.

Overview

Building-block services provide consistency and ease of use across services and applications developed for the .NET platform. These services are used to move the control of data from applications to the users who use these applications and ensure that user content forms the basis of all transactions.

Microsoft is developing a number of different building-block services to empower developers for rapid development of .NET Web services. Examples of these include services for

- User identification (for example, Microsoft Passport)
- User preference management
- Message delivery
- Calendar management
- File storage

While Microsoft is developing the core set of .NET services, third-party partners will develop additional services to build in enhanced functionality to .NET applications and services.

See Also: *.NET platform*

Building-centric Local Exchange Carrier (BLEC)

A telecommunications carrier focused on the Multitenant Unit (MTU) market.

Overview

With the increasing deregulation of the U.S. telecommunications industry over the last decades, several different types of local exchange carriers (LECs) have emerged in the marketplace, including Incumbent Local Exchange Carriers (ILECs) and Competitive Local Exchange Carriers (CLECs). The latest of these is the Building-centric Local Exchange Carrier (BLEC), which represents a carrier focused on providing broadband telco services within multitenant units (MTUs). An MTU is essentially a building or group of buildings that primarily host small and medium-sized businesses with between 10 and 200 employees. Examples of business environments serviced by BLECs include office skyscrapers, industrial parks, and hotels. Some BLECs also target residential apartment blocks and malls as well. By targeting MTUs, BLECs are essentially focusing on a market that ILECs have generally neglected (ILECs have historically focused on the large-enterprise and individual consumer markets instead). The requirements of BLEC clients are usually diverse, and typically include Internet Protocol (IP) data, Web hosting, e-mail, and Internet access, which BLECs offer as value-added data services to traditional voice telephone connectivity.

BLECs can typically be grouped into two categories:

- Those focused on retail services to end-user business clients.
- Those focused on the wholesale end of purchasing broadband access for MTUs from inter-exchange carriers (IXCs) who provision these wholesale services. Note that some IXCs themselves are getting into the MTU market by deploying high-speed metropolitan area networks (MANs) to service such customers and are in effect competitors to BLECs.

Implementation

Typically a single business client within an MTU cannot justify the cost of having a leased line such as T1 deployed to service its needs. That is where BLECs come in, however—they provision such services for all clients within a given MTU.



Building-centric Local Exchange Carrier (BLEC). *How a BLEC provisions customers with broadband services.*

Typically, a BLEC first has to provide new fiber to an MTU to provide clients with high-speed services brokered from larger LECs and IXCs. This first step is necessary because the majority of large office buildings in the United States do not currently have fiber-optic cabling deployed to them. Once fiber has been laid by the BLEC from the building to the central office (CO) of the LEC or IXC from which the BLEC obtains wholesale broadband provisioning, the BLEC then purchases T1 or T3 services from the LEC or IXC to run over the fiber. Switching gear (usually a DSLAM, an Asynchronous Transfer Mode [ATM] access switch, or some form of high-speed Ethernet switch) is then deployed by the BLEC in the basement of the MTU to provide broadband services to clients throughout the building. This arrangement is preferable to co-locating such equipment at LECs and IXCs and often give BLECs a competitive edge in the speed at which new services can be deployed and problems troubleshot.

Another technology option for BLECs is fixed broadband wireless, which bypasses the initial step of laying fiber to the building. This is often a method for cost-effective provisioning of broadband services for MTUs that is easy to implement rapidly and is often the only solution when the MTU is too far from a central office (CO) for DSL or T-carrier services to be effective.

To provision either of these scenarios, BLECs first have to negotiate right-of-way through revenue-sharing agreements with building owners to gain access to basement wiring closets or deploy rooftop antennas, and this is usually factored into the price for services offered by BLECs to tenants.

Marketplace

Some of the major players among BLECs include Broadband Office, which has right-of-way to a large portion of U.S. commercial office space; Comactive, which is an offshoot of Intermedia Communications; and many others.

Prospects

With increasing deregulation of the telecommunications industries, BLECs find themselves squeezed by rising customer expectations on the one hand, high levees from building owners for fiber and rooftop right-of-way on another hand, and direct competition from CLECs, ILECs, and IXCs higher up on the carrier feeding chain. Customers owning multiple MTUs desire simultaneous rollout regardless of the up-front costs to BLECs for servicing smaller premises. Some building owners (usually real estate companies) are also consider deploying their own broadband switching gear instead of partnering with BLECs to do so and thus bypass BLECs entirely by going to LECs and IXCs directly. Future rulings of the Federal Communications Commission (FCC) might also affect how this all works out in the marketplace.

Notes

Another common name for BLECs is Multitenant Broadband Service Providers (MBSPs).

See Also: *broadband Internet access, broadband wireless communications, carrier, inter-exchange carrier (IXC), local exchange carrier (LEC), multitenant unit (MTU)*

built-in account

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, a type of user account that is created during installation.

Overview

All computers running Windows 2000, Windows XP, and Windows .NET Server, have two built-in user accounts:

- **Administrator account:** Used to provide administrative access to all features of the operating system
- **Guest account:** Intended to provide occasional users with access to network resources

Depending on whether the computer is a domain controller, a member server, or a workstation, built-in accounts will be either local user accounts or global user accounts. A built-in account on a domain controller is a global user account that exists everywhere within the domain. Users can log on to any machine in the domain using such an account, which provides administrators with the capability of administering a Windows 2000–based network from anywhere on the network. On a member server or workstation, the Administrator and Guest accounts are local user accounts and exist only on those machines.

Notes

Rename the Administrator built-in user account to make it more secure.

See Also: *built-in group*

built-in domain local group

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, a domain local group created during installation that has preassigned rights and permissions. Built-in local groups are used to simplify the administrative task of assigning users and groups rights to perform system tasks and permissions to access network resources. Some of these groups include

- **Users:** Contains the Domain Users global group and is used to assign rights and permissions to all ordinary users.
- **Administrators:** Contains the Domain Admins global group and the Administrator account created during setup.
- **Guests:** Contains the Domain Guests global group.
- **Power Users:** Members have the right to share folders and printers.
- **Backup Operators:** Members have the right to back up and restore servers.
- **Account Operators:** Members have the right to administer accounts.
- **Server Operators:** Members have the right to administer servers.
- **Print Operators:** Members have the right to administer printers.

See Also: *built-in global group*

built-in global group

A type of global group created during installation of Active Directory directory service.

Overview

Built-in global groups are created in order to organize common groups of users for administrative purposes. These built-in global groups are created within either Active Directory (when implemented) or in the Security Accounts Manager (SAM) database (for stand-alone servers). The four types of built-in global groups are

- **Domain Admins:** Initially, this group contains only the Administrator account that was created during setup. Only people with administrative responsibilities should be assigned to this group.
- **Domain Guests:** This group contains the Guest account and is designed for organizing temporary users of network resources and granting them access.
- **Domain Users:** When a new user account is created, it is automatically added to this group, whose function is to collect all ordinary users for the purpose of assigning them permissions to resources on the network.
- **Enterprise Admins:** This group contains users who are assigned administrative rights over the entire network. The Enterprise Admins global group should be added to the Administrators domain local group in each of your network's domains. By default, the Administrator account is a member of the Enterprise Admins group.

See Also: *built-in group, built-in domain local group*

built-in group

In Microsoft Windows 2000 and Windows .NET Server, a type of group created during installation to simplify the delegation and assignment of common administrative tasks.

Overview

Built-in groups have preassigned sets of user rights, and some also have preassigned members.

Windows 2000 and Windows .NET Server contain three kinds of built-in groups:

- **Built-in domain local groups:** These are used to assign predefined sets of rights and permissions to users and groups of users, and they exist on all computers running Windows 2000 and Windows .NET Server.

- **Built-in global groups:** These groups are used to automatically organize users into common groups for administrative purposes, and they exist only on Windows 2000 and Windows .NET Server domain controllers.
- **Built-in identities:** These are used by the operating system to automatically group users for system purposes, and they exist on all computers running Windows 2000 and Windows .NET Server.

Notes

You cannot rename or delete a built-in group, and you cannot change the membership of a built-in identity.

See Also: *built-in global group, built-in domain local group*

built-in identities

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, a term used to refer to what were known in Windows NT as system groups.

Overview

Built-in identities can represent different subsets of users in different situations, and they do not have a specific membership that administrators can modify. However, you can assign built-in identities rights and permissions for accessing resources or performing system tasks. Examples of built-in identities include

- **Everyone:** Represents all users who can be, or are, on the network, whether from trusted or distrusted domains.
- **Network:** Represents all users who can access, or are accessing, network resources over the network. It does not include users logged on locally to a machine and accessing those resources locally.
- **Interactive:** Represents all users who can be, or are, currently logged on locally to a computer to access local resources on it. It does not include users who can access, or are accessing, network resources over the network.

See Also: *built-in group*

burst

A condition in which network activity rises suddenly for a short period of time.

Overview

A burst is a transient elevation in network activity, and a network on which a lot of bursts occur is said to be bursty. Bursty networks have different bandwidth requirements than networks on which the traffic is steady, and they need to be designed accordingly. For example, a network on which large video files are frequently transmitted tends to be bursty in its traffic flow.

Bursts can be indicative of a sudden increase in demand for network resources, or they can indicate hardware or software problems. Some networking components are capable of briefly sending data at speeds greater than normal transmission speeds; this is referred to as “operating in burst mode.”

A good first step in accommodating bursty conditions is to use Ethernet switches instead of hubs for concentrating your network connections.

bus

A linear circuit path that can be used to connect multiple devices for exchange of data.

Overview

The idea of a bus in computer networking technology is analogous to that of a bus as a means of transportation: a bus travels over a fixed route across a city, carrying people and stopping at various points for people to get on or off. In the same way, computers and networks use buses to transport data from one device to another. The point on a bus where a device can be connected is generally called a slot.

Buses generally fall in three categories: system buses, peripheral buses, and network buses (or bus topology networks).

System buses are internal to computer systems and are used to carry data between the processor, chipset, memory, disk subsystem, video subsystem, and peripheral cards such as network adapters and sound cards. Examples of different types of system buses include

- **Processor bus:** This transports data between the CPU (central processing unit) and the chipset.
- **Memory bus:** This transport data between the memory subsystem, CPU, and chipset.
- **I/O bus:** This transports data between the CPU, chipset, memory subsystem, and internally attached peripherals such as network adapters, video adapters, and disk controllers.
- **Cache bus:** This transports data between the CPU and the L2 cache (present only in sixth-generation processors such as the Pentium III).

When the term *bus* is used in conjunction with computer systems, it is commonly interpreted as meaning input/output (I/O) bus. The I/O bus has gone through many changes over the years, including the following:

- **Industry Standard Architecture (ISA) bus:** The 8-bit ISA bus was developed by IBM in 1981 for the original IBM PC. A 16-bit version was then developed in 1984 for the newer IBM AT. Some desktop systems still include an ISA bus and slots for backward compatibility of legacy peripheral devices, but the presence of an ISA bus is problematic because it does not support plug and play (PnP).
- **VESA Local Bus (VLB):** This was used by some 486 systems but had the disadvantage that the bus was essentially an extension of the CPU's leads, which resulted in poor performance.
- **Peripheral Component Interconnect (PCI) bus:** This is the most common form of I/O bus in use today, and it comes in both 32-bit (PCI 2.0) and 64-bit (PCI 2.1) versions.

Peripheral buses are buses whose primary use is for connecting peripherals to computer systems or network switches. Examples of this type include Small Computer System Interface (SCSI) and Fibre Channel.

Network buses (or bus topology networks) represent any form of network in which devices are connected together in linear fashion. Examples include 10Base2 and 10Base5 Ethernet and Token Bus networks, all three of which are obsolete. Most networks today are based on a star topology, which is easier to manage than bus topology because of its centralized nature.

Prospects

The state of system bus technology is currently in flux. Whereas previously networks could not keep up with their servers, now the server has become the bottleneck: a Peripheral Component Interface (PCI) local bus has a difficult time performing I/O fast enough to fully utilize a Gigabit Ethernet (GbE) network connection. The result has been various industry initiatives to speed up the I/O bus to match rapidly growing network capacity (10 GbE is now on the horizon). Another source of pressure has been the increasing need for modern servers to be able to rapidly access large amounts of database storage, sometimes in the terabyte range.

Some of the newer industry initiatives for evolving system buses include

- **PCI-X (or PCIx) bus:** This proposed next-generation PCI bus will have a theoretical data transfer rate of 1 gigabit per second (Gbps), based on a clock speed of 133 megahertz (MHz), and is backward-compatible with existing PCI peripherals. A draft standard for PCIx was produced in 1999.
- **Infiniband:** Unlike legacy bus systems (including PCI), which are shared-bus systems in which connected devices must contend with each other for the right to transmit data, Infiniband is a switched-bus fabric that is capable of data transfer rates of 6 Gbps or higher and is supported by industry heavyweights such as IBM and Intel Corporation.
- **Ethernet:** Since high-speed switched Ethernet performs so well in the network, why not use it for I/O within computer systems? This is the thinking of Performance Technologies, which has joined with other manufacturers in proposing a new form of PCI bus called cPCI based on switched Ethernet technologies that provides 2 Gbps of dedicated bandwidth per slot.

Other proposals include using high-speed SCSI technologies (such as Ultra160 SCSI) and FiberChannel for internal system buses, but these initiatives have not gained much momentum.

Notes

A bus and a port are both similar in that they transport data between devices, but although a port can be used only to connect two devices, a bus can connect three or more devices.

See Also: *10Base2, 10Base5, Fibre Channel, Infiniband (IB), Small Computer System Interface (SCSI)*

business logic

That portion of an application that reflects the actual way the enterprise does business.

Overview

Business logic is a term used in writing applications for Microsoft Transaction Server (MTS) using reusable COM+ components. These components represent a combination of logon verifications, policies, database lookups, validation edits, and other processes that constitute how business is done in the enterprise. An application's business logic specifies how the component's programming logic reflects the actual way the enterprise does business. Business logic enables consistent and logical processing of business data.

A representation of a real-world component of the enterprise's business is called a "business object." Examples of business objects include customers, orders, products, invoices, and anything else that can be encapsulated in an application's business logic and manipulated by its users.

business-to-business

Also known as B2B, e-commerce between different companies that have a partnering arrangement.

See: *B2B*

business-to-consumer

Also known as B2C, a relationship in which individuals or companies purchase the services of another company.

See: *B2B*

bus topology

A networking topology that connects networking components along a single cable or that uses a series of cable segments that are connected linearly.

Overview

A network that uses a bus topology is referred to as a "bus network." Bus networks were the original form of Ethernet networks, using the 10Base5 cabling standard. Bus topology is used for

- Small workgroup local area networks (LANs) whose computers are connected using a thinnet cable
- Trunk cables connecting hubs or switches of departmental LANs to form a larger LAN
- Backboning, by joining switches and routers to form campus-wide networks



Bus topology. *A simple example of a bus topology network.*

Bus topology is the cheapest way of connecting computers to form a workgroup or departmental LAN, but it has the disadvantage that a single loose connection or cable break can bring down the entire LAN.

Notes

A hub or concentrator on an Ethernet network is really a collapsed bus topology. Physically, the network appears to be wired in a star topology, but internally the hub contains a collapsed bus, creating a configuration called a star-wired bus. However, in this case, a failure in one of the cables does not affect the remaining network.

Communication problems on bus networks might indicate that the bus ends are improperly terminated. A break in the cable will produce a similar result, since the ends of the break are not terminated. Use a cable tester to determine the problem's nature and location.

See Also: *mesh topology, ring topology, star topology*

C

C++

The most widely used object-oriented programming language.

Overview

C++ is the standard programming language used for developing tools and applications for high-speed networking. This is because it is a compiled language whose object code is essentially native assembly language and hence runs extremely fast. For example, a form handler written for a Hypertext Markup Language (HTML) form that runs on a UNIX Apache Web server will run much faster if it is written in a compiled language such as C or C++ than if it is written in an interpretive language such as Perl or Microsoft Visual Basic, Scripting Edition (VBScript).

High-performance Internet Server API (ISAPI) applications and dynamic-link libraries (DLLs) written for Microsoft Internet Information Services (IIS) generally perform best when written in C++. Powerful distributed Web-based applications for the Internet can be developed using a combination of Active Server Pages (ASP) scripts in VBScript or JScript, with Microsoft ActiveX components and ISAPI dynamic-link libraries (DLLs) written in C++ using Microsoft Visual C++.

C++ programs for Windows network operating system platforms can be developed using a variety of tools:

- Traditional C++ development tools using editors, compilers, and debuggers support low-level application programming interface (API) access, Microsoft Foundation Classes (MFC), software development kits (SDKs), and other supporting elements.
- Rapid application development (RAD) tools provide integrated development environments (IDEs) that focus on providing developers with ease-of-use features.
- Component deployment tools take a component-based approach to generating and reusing C++ code for building distributed and multitier applications.

C++ is based on the earlier C language that is used for developing applications, including Win32 applications for Microsoft Windows platforms. The standard form of C++ is called ANSI C++ and is defined by the American National Standards Institute (ANSI).

Notes

Microsoft Visual C++ combines the best features of these various classes of tools. It is an excellent choice for developing large-scale distributed networking applications based on the C++ language and Microsoft Corporation's own specific extensions to ANSI C++ that are designed for the Win32 platform.

See Also: *C#*

C#

Pronounced "C sharp," a programming language developed by Microsoft Corporation for its new .NET platform.

Overview

C# is an offshoot of C and C++ that is designed for rapid development of Web services for Microsoft's new .NET platform. C# is derived from C++ and has much of the power of C++ while improving on it in many respects from the point of view of the developer who needs to rapidly create and deploy applications in the e-economy.

The main weaknesses of C++ as a development environment are its complicated code-compile-debug development cycle, its potential of creating memory leaks that are difficult to troubleshoot, and the requirement of having applications explicitly manage memory resources. C# is similar to the Java platform developed by Sun Microsystems in that memory resources and garbage collection (object lifetime management) are automatically handled by the language itself, freeing developers to work on creating applications instead of being bothered by handling these intricate details. C# also simplifies access to external objects and simplifies the object creation process compared with C++. And although C++ applications require frequent use of include files to allow access to system services, in C# these services are transparently wrapped in objects. Like Java, C# thus relieves programmers of much of the chore of object and memory management, speeding up the development cycle in the process.

On the other hand, C# is unlike Java in that it maintains powerful features such as pointers, passing arguments through reference, overloading operators, and manually allocating memory. These features, basic to C++, are included in C# to provide programmers with the functionality should they need it, but they are deemphasized in C# compared to their common use in C++. For example, when pointers are used in C#, they need to be tagged in a section of code marked as "unsafe," making it easier to troubleshoot difficulties that may arise from their misapplication. Furthermore, C# has the advantage over Java of providing direct access to native Microsoft Windows services, and C# is easier to learn than Java for C++ programmers because its syntax is derived from and is similar to C++, whereas the syntax for Java has many differences from C++ that make it difficult for C++ programmers to use easily.

It is relatively simple to port existing C++ programs to C# (by contrast, it is much more difficult to port such applications to Java). The main disadvantage of C# as a development environment is a weakness shared with Java: unlike C++, which compiles programs into native machine code, C# compiles programs into an intermediate bytecode called intermediate language (IL) that is then interpreted by the .NET runtime. This means C# shares a performance hit similar to Java, which is also an interpreted platform. C++ will still be used for writing code modules where the best performance possible is required (such as device drivers), but C# performs sufficiently well on today's hardware platforms to be used as a primarily development platform. And because C# executes on the .NET runtime, it shares the interoperability features of this runtime, which allows modules written in C# to communicate with code written using other programming languages.

Microsoft plans to submit the C# language to the standards board of the European Computer Manufacturers Association (ECMA). The ECMA will then manage the language as a standard, which means that third parties wanting to use C# to develop applications will not be required to pay licensing fees to Microsoft. This will keep the cost of development tools and applications development low.

Notes

The Object Management Group (OMG), the creators of Common Object Request Broker Architecture (CORBA), is developing a language mapping for C# to enable it to communicate through CORBA with applications written in other languages such as C, C++, Cobol, Java, Python, and Ada.

See Also: *C++, .NET platform*

C2

A security standard for computer systems established by the National Computer Security Center (NCSC).

Overview

The NCSC is a U.S. government agency responsible for evaluating the security of software products. The C2 security standard is defined in the Trusted Computer Systems Evaluation Criteria (TCSEC) manual (or Orange Book) published by the NCSC.

The NCSC rated Microsoft's Windows NT 3.5 (with Service Pack 3) C2-compliant. The C2 designation assures that the base operating system satisfies a number of important security criteria. This designation also represents an independent, unbiased evaluation of the system architecture's security with regard to the government's operating and implementation standards. Windows 2000 also supports C2, but is still undergoing the NCSC evaluation process.

A C2 rating does not indicate that a system is free of security bugs; instead, this rating certifies that the computer system's underlying architecture is suitable for high-security environments in specific networking configurations. It is incorrect to say that Windows NT is C2-certified or runs in C2 mode. Only a complete computer system (including hardware) can be rated C2. A rating of C2 means that in a particular implementation, in a particular networking environment and configuration, using specific hardware and software, a computer network using a Windows NT operating system can apply for, and might receive, C2 certification.

According to the Orange Book, in a C-level system, the security policy must be based on what is known as Discretionary Access Control (DAC), which essentially means that users of the system can own objects (such as files and directories) and can control access to these objects by other users. A user who establishes control over an object is responsible for granting or denying all access rights to that object. In other words, the owner of an object grants or denies users access to the object at his or her discretion. This is in contrast to a B-level system, in which Mandatory Access Control (MAC) specifies that all objects have security levels that are defined independent of the object's owner.

For More Information

Visit the NCSC at *www.radium.ncsc.mil.*

See Also: *security*

CA

Stands for certificate authority, any entity (individual, department, company, or organization) that issues digital certificates to verify the identity of users, applications, or organizations.

See: *certificate authority (CA)*

cabinet

An enclosure with a built-in rack for holding and organizing patch panels, switches, hubs, routers, servers, and any other networking equipment within a wiring closet.

Overview

Cabinets can be wall-mounted or freestanding, come in various heights, and are usually standardized for 19-inch-wide shelving and paneling. They generally come in 83-inch and 48-inch heights, although many vendors offer custom-designed cabinets. The reason for standardizing the width to 19 inches (18.31 inches to be precise) is that hubs, switches, routers, and other networking devices are produced in this width so that they can be organized in racks and cabinets designed for this purpose. Cabinets come with a variety of accessories for organizing cables, power strips, and other equipment. Because heat can accumulate in cabinets, they usually include vented walls and have an exhaust fan on top. A cabinet will often have a locking front panel made of clear plastic so that status lights on equipment are easily visible. Shelves can be fixed, mounted, or sliding to enable easy access to the sides and backs of equipment.

Cabinet. *A typical cabinet for mounting networking and telecommunications equipment.*

Notes

When should you choose a cabinet instead of a rack? Choose a cabinet for equipment that is exposed to user traffic, and then you can lock equipment away when the room itself is not locked. Cabinets are also best for expensive networking equipment that you do not want anyone but authorized administrators to touch. Cabinets with filter fans installed can protect equipment in environments where dust is a problem. Use filler panels to enclose areas of the cabinet that are not occupied by equipment.

See Also: *premise cabling, rack*

cabinet file

A file with the extension .cab that stores compressed files, usually for distributing software on Microsoft platforms.

Overview

Cabinet files can contain multiple files in a compressed state, or a single compressed file can be spread over several cabinet files. During installation of software, the setup program decompresses the cabinet files and copies the resulting files to the user's system.

Cabinet files can be digitally signed using a Microsoft technology called Authenticode. This allows setup files to be downloaded safely over distrusted networks such as the Internet. Cabinet files are compressed using a compression algorithm called MSZIP, which is based on the Lempel-Ziv algorithm.

Notes

Cabinet files in Microsoft Windows 95 were located in the Win95 directory on the source CD, and most were represented as a series of large files with names such as Win95_1.cab and Win95_2.cab. Windows 98 uses a different naming convention and names many of its smaller cabinet files by function rather than by the order in which they are used during setup. Naming by function makes the extraction of files easier, which in turn makes the setup process smoother.

In Windows 95, if you want to extract specific operating system files from a cabinet file (for example, to replace a missing or corrupt file), you have to use the command-line utility called extract. Using Windows 98 and later versions, you can simply double-click on a cabinet file using Windows Explorer to view its contents in a new window, double-click on the specific file you want to extract, and specify the destination folder to send it to. You can also use the System File Checker tool to extract files without knowing which specific cabinet file they are located in.

See Also: *Authenticode*

cable modem

A device that allows your computer to access the Internet through dedicated broadband transmission networking services by means of your home cable TV (CATV) connection.

Overview

Cable modems modulate and demodulate analog signals like regular modems, but for transmission over broadband video services instead of telephone voice services. A cable modem can be internal or external and can interface with the coaxial cable connection at the user's end and the Cable Modem Termination System (CMTS) at the cable provider's head office.

Cable modem and Asymmetric Digital Subscriber Line (ADSL) are competing technologies for bringing high-speed broadband Internet services to homes and businesses. Cable modems offer downstream speeds of 10 megabits per second (Mbps) and higher, but competing technologies, lack of standards, and implementation costs have slowed widespread deployment and use of this technology.

There are two basic types of cable modem services:

- **One-way cable modems:** These are used by unidirectional cable service providers. Most cable TV services are designed to carry information in one direction only—from the broadcaster to the customer premises. With one-way cable modems, the customer uses a regular telephone modem to send information to the cable company but uses the cable TV system with cable mode to receive signals from the company. The telephone modem handles all upstream communication, and the cable modem handles all downstream communication. One-way cable modems are typically cards installed inside a subscriber's computer.

- **Two-way cable modems:** These require that the broadcasting cable company has converted its cabling and repeater infrastructure for bidirectional communication. Two-way cable modems are typically external devices connected to a network interface card (NIC) that is installed in the subscriber's computer. The cable modem is used for both upstream and downstream communication in this configuration. Most cable companies currently have initiatives under way to make such a conversion, but it requires a large capital investment. Therefore, it will be several years before these systems become widely available.

Implementation

In a typical one-way cable modem implementation, the CMTS uses separate subsystems for upstream and downstream connections that terminate at a router. The downstream subsystem is designed for converting incoming Internet Protocol (IP) traffic into radio frequency broadband signals that are broadcast using a broadband network hub (BNH) over cable TV wiring to local groups of connected subscribers. The upstream subsystem usually consists of banks of ordinary telephone modems to allow for easy expansion of services to additional subscribers. The router is used to route network traffic between clients and local content servers hosted by the cable provider, and to the Internet.

Downstream traffic is typically modulated using 64 or 256 Quadrature Amplitude Modulation (QAM) and can achieve speeds of 27 Mbps or higher. Upstream traffic is encoded using 16 QAM or Quadrature Phase Shift Keying (QPSK) and typically ranges from 320 kilobits per second (Kbps) to several Mbps.

Marketplace

Excite@Home was an early player in the cable modem marketplace, and many local cable companies followed offering high-speed Internet access to their cable TV subscribers. Consolidation in the industry has led to the emergence of several major players, including AT&T Broadband and AOL/Time Warner.



Cable modem. *A one-way cable modem service.*

Cable modem Internet access costs around $40 a month in most locations but, because their operation depends on the wiring infrastructure of cable TV systems, cable modems are almost exclusively offered for residential customers and home-based businesses. Some cable modem providers such as Cox Communications also compete with telcos by offering voice as well as data services.

The cable modem market is growing more rapidly than the Digital Subscriber Line (DSL) market, its main competitor. This is happening despite the security and bandwidth issues associated with cable modems (see below), and is driven largely by the complexity of DSL compared to the simplicity of cable modems and by the fact that cable modems are not limited by the 3-mile (4.8-kilometer) distance restriction that governs how far a DSL customer can be from the DSL provider's central office (CO). A Federal Communications Commission (FCC) survey found that cable modem subscribers in the United States grew from just over 100,000 in 1998 to almost 1 million in 1999. In 2000 worldwide cable modem usage was estimated at over 6 million subscribers, almost twice that of DSL.

Issues

Most cable television companies have jumped on the cable modem bandwagon to offer Internet access for their customers, but this has not been without problems. Existing tree-and-branch coaxial systems were built for one-way transmission and often require expensive upgrades to make them suitable for two-way data transmission. Some of the steps typically involved in the upgrade are upgrading core distribution networks to fiber (creating a hybrid fiber-coax network) and troubleshooting ingress noise due to poor shielding and loose connectors.

Many cable operators, although they support multimegabit upstream data speeds, have instead restricted upstream speeds to 128 Kbps or lower to help prevent customers from running rogue Web servers on their network in violation of their customer agreements. Also, all subscribers in a one-way cable modem local service area are essentially on a local area network (LAN) and, if they have a packet sniffer, they can see one another. If you are using a one-way cable modem with Microsoft Windows on your computer, you should disable file and print sharing so that other users in your local service area cannot see your system or access resources on it. The cable modem industry itself has proposed a solution to the security issue through an initiative called Data Over Cable Service Interface Specification (DOCSIS) that specifies encryption of all cable modem traffic using 56-bit Data Encryption Standard (DES), although DES is no longer secure.

Furthermore, although in theory a cable modem might support downstream transmission speeds of 10 Mbps or higher, in practice downstreams may be significantly less than 1 Mbps. This is because all cable modems serviced by a given neighborhood Cable Modem Termination System (CMTS) are essentially on a LAN and share the available bandwidth. Thus, the more modems deployed in a given neighborhood, the slower the system performs for Internet access, especially when some users are downloading large files or streaming media (a common occurrence among cable modem users). In this respect DSL has an advantage because it is a secure, private connection directly to the Internet.

Notes

If you have a one-way cable modem installed on a computer running Microsoft Windows 2000, Windows XP, or Windows .NET Server and it is not working properly, you might have IP Auto-Configuration Addressing enabled, causing an addressing problem that prevents packets from being routed successfully to your machine. Also, try checking with your cable service provider to determine whether you have correctly configured the line-in frequency, line-out phone number, and proxy server address.

For More Information

Visit Cablemodems.com at *www.cablemodems.com.*

See Also: *Asymmetric Digital Subscriber Line (ADSL), broadband Internet access, Data Over Cable Interface Specification (DOCSIS), modem*

cable run

A length of installed cable connecting two network components that are not in immediate proximity to one another.

Overview

Laying cable runs is the main work of installing premise cabling in a customer premises. Types of cable runs include

- **Horizontal cable:** Runs through building plenums (the space between the floor and the ceiling) and false ceilings, connecting wiring closets together and connecting patch panels to wall plates

- **Vertical cable:** Runs through vertical building rises, connecting wiring closets on each floor with the building's main equipment room

Different grades of cabling must be used for different runs to ensure compliance with building codes and safety standards. Examples include polyvinyl chloride (PVC) cabling and plenum cabling. The Electronic Industries Association/Telecommunications Industry Association (EIA/TIA) wiring standards specify guidelines for using cable types and grades.

Notes

Cables connecting computers to patch panels (drop cables) and connecting patch panels with hubs and switches (patch cables) are not generally referred to as cable runs because they are not permanently installed and are usually quite short. The term *cable run* generally applies to cables that run from the patch panels in a wiring closet to other parts of the building.

When installing horizontal or vertical cable runs, use the highest grade that your budget will allow in order to accommodate future upgrades of your network's speed and bandwidth. Use the enhanced Category 5 (Cat5e) cabling—which is a variety of unshielded twisted-pair (UTP) cabling—for all copper cabling installations. If you can, install parallel vertical runs of fiber-optic cabling with copper cabling in vertical rises to allow for future expansion of your network backbone. Installing two cables at once saves costs later, even if you need only the copper cabling now.

See Also: *cabling, premise cabling*

cable tester

Any device for measuring the integrity and transmission characteristics of cabling.

Overview

Cable testers perform various functions to test network cabling for compliance with cabling standards developed by bodies such as the Telecommunications Industry Association (TIA), the International Organization for Standardization (ISO), and the International Electrotechnical Commission (IEC). Cable testers are useful to local area network (LAN) administrators, cable installers, and field service providers for testing and certifying cabling installations as compliant with these standards.

F1
F2
F3
F4
Escape
TEST
1
2
3
Function 1
4
5
6
Function 2
7
8
9
Function 3
*
0
hold
POWER
?

Cable tester. *A handheld cable tester.*

Cable testers come in a variety of forms, ranging from handheld to briefcase size. They are generally divided between those used for testing fiber-optic cabling and those used for testing copper cabling. Different testers have different capabilities, but their general function is to measure various electrical characteristics across different ranges of frequencies. Testers will typically measure some or all of the following parameters at various frequencies from 100 megahertz (MHz) to 350 MHz and beyond:

- Attenuation, which is the decibel decrease in signal strength as a signal propagates through a physical medium
- Impedance, which is the resistance to the flow of alternating current
- Noise, indicated by the floor values for randomly generated electrical signals

- Near-end crosstalk (NEXT), which is a decibel measurement of crosstalk taken at the end where a signal is injected
- Attenuation to crosstalk ratio (ACR), which is the decibel difference between NEXT and attenuation values
- PowerSum NEXT, which measures the crosstalk between a single pair of wires and all other pairs in the cable
- The distance to a short or unterminated cable end, used for link-testing the continuity of circuits

Uses

Cable testers are particularly important for testing Category 5 (Cat5) and enhanced Category 5 (Cat5e) structured wiring deployments to see if they will properly support Gigabit Ethernet (GbE) networking. GbE pushes unshielded twisted-pair (UTP) cabling to its limits and requires top-quality properly installed cabling to operate as expected. Particularly in older buildings with existing Cat5 wiring, use a cable tester to measure such parameters as cross-talk and NEXT to determine if packet loss will occur over portions of the network. Particularly vulnerable portions include cable termination at RJ-45 wall jacks and at patch panels inside wiring closets. Poor quality patch cables between workstations and wall jacks are a common problem, as are patch panel connections that have been untwisted beyond the specified limits.

Marketplace

A number of vendors produce different kinds of test equipment for cable testing. Two of the top vendors of such equipment include Fluke Corporation, which offers a wide range of cable testers, and Hewlett-Packard.

Today's cable testers can perform comprehensive and programmable sets of autotests for a variety of cable types. A good cable tester can tell you at the push of a button whether installed wiring can support different kinds of networking architectures—such as coax, 10BaseT, 100BaseT, 100BaseVG, and Token Ring. Cable testers can also store measurements taken so that they can be analyzed separately afterward.

The most accurate types of cable testers for UTP cabling are those that can test and certify Category 5 (Cat5) cabling to Level II TSB-67 compliance and support the Institute of Electrical and Electronics Engineers (IEEE) TSB95 field testing specifications. An all-in-one cable tester is an invaluable tool and a good investment for the network administrator. It can make up for its cost in higher network availability.

Notes

Use a fiber-optic tester and an optoelectronic light source to test both ends of a new spool of fiber-optic cabling before beginning an installation with this cable. A good fiber-optic cable test should give you not only a pass/fail analysis of an installed cabling setup, but also quantitative values of the optical link capabilities of your wiring configuration.

See Also: *cabling, network troubleshooting, test equipment*

cabling

Any wires used for connecting computers and networking devices together to enable them to communicate.

Overview

Cabling constitutes the passive portion of any computer network—the active portion consists of the servers, workstations, switches, routers, and other components. Good cabling provides the foundation for creating reliable local area networks (LANs). Cabling is also used for connecting LANs into wide area networks (WANs). Network administrators are usually involved in the deployment of LAN cabling, but WAN cabling is usually the responsibility of the telecommunications carriers whose services are being leased.

Two basic types of cabling are used in LAN networking environments:

- **Copper cabling:** This type consists of insulated copper conductors that transmit signals using electrical voltages and currents. Copper cabling can be either coaxial cabling (such as thinnet or thicknet) that is used mainly in industrial environments, or the more commonly employed twisted-pair cabling. Twisted-pair cabling comes as either unshielded twisted-pair (UTP) cabling (commonly used in Ethernet or Fast Ethernet environments) or the less common shielded twisted-pair (STP) cabling (employed for token ring networks and sometimes for Gigabit Ethernet [GbE] installations). Copper cabling is mainly used for shorter cable runs such as horizontal cable runs between wiring closets and wall plates in work areas, for patch cables, and for equipment interconnects.

- **Fiber-optic cabling:** This type is made of glass strands that transmit signals as light waves or pulses. Fiber-optic cabling can be either single-mode, which is used for the longest cable runs, or multimode, which has a much higher carrying capacity. Fiber-optic cabling is generally used for backbone cable runs such as vertical rises in buildings and building-to-building interconnects on a campus, for high-speed interconnects between networking devices in a wiring closet, and for connections to high-speed servers and workstations.

Implementation

The process of installing cabling in a building for purposes of computer networking is called establishing premise wiring. Unfortunately, cabling is only as good as the way it is deployed and only as good as the connectors and other elements that help make a computer network. Poor quality cabling, improperly installed cabling, or cheap wall plates and patch panels can make a cabling system perform more poorly than expected, particularly at GbE speeds.

The Telecommunications Industry Association (TIA) and the Electronic Industries Alliance (EIA) have defined a series of standards on the required electrical characteristics of commercial cabling for computer networking and also standards for the proper layout and organization of premise cabling. These standards are called the EIA/TIA wiring standards. The EIA/TIA-568A Commercial Building Telecommunication Cabling Standard specifies standards for each of the following:

- Establishing wiring closets on each floor of the building to contain rack-mounted equipment such as hubs, switches, and patch panels
- Running vertical backbone plenum cabling through building risers and building plenums, for connecting wiring closets to the main equipment room
- Running horizontal polyvinyl chloride (PVC) cabling for each floor through false ceilings
- Connecting the patch panels in the wiring closet to wall plates in computer work areas

Cabling installed in a building must also meet all legal requirements, including federal and local building regulations for fire safety. Do not attempt to wire a building unless you are fully familiar with the regulations.

Choosing the right kind of cabling at the beginning of an installation can save considerable expense when you later upgrade networking equipment for higher transmission speeds. Some tips for successfully outsourcing cabling installations for computer networks in buildings include

- Hiring a qualified cabling consultant to review the scope and details of your plans and procedures. Hire cabling consultants who either have vendor certification (if you are using “channel cabling,” that is, all the cabling components are being purchased from a single vendor) or an independent consultant affiliated with BICSI.
- Ensure that if you outsource your cabling installation that the company you hire is properly licensed and insured for such work.

If you plan to lay cable yourself for your building, here are a few more guidelines:

- Use no more than 30 to 40 pounds of pull when pulling cabling through a conduit or a plenum.
- Do not excessively bend wiring (especially fiber-optic cabling), and be sure not to untwist UTP wires more than specifications allow.

- Make sure data wiring and power cables are at least 6 inches (15 centimeters) apart, and, if they need to cross each other, they do this at a 90 degree angle.

Notes

Specialized cables—such as serial, parallel, or Small Computer System Interface (SCSI) cables—are used to connect peripherals and therefore do not serve the same purpose as the cables just discussed. Serial cables and other special purpose cables are generally very short and are not permanently installed.

Note that not all networks use physical cabling. Wireless networks can use infrared, microwave, radio, or some other form of electromagnetic radiation to allow networking components to communicate with each other. A cabled network is sometimes referred to as a wireline network, as opposed to a wireless network.

For More Information

Look at *www.cablingstandards.com*. You can also visit the BICSI Web site at *www.bicsi.org*.

See Also: *copper cabling, fiber-optic cabling, premise cabling*

CA certificate

Also called a root certification, a digital certificate that can be used to verify the identity of the certificate authority (CA) itself.

Overview

The CA certificate contains the identification information and public key for the certificate authority it identifies. A certificate authority that is part of a hierarchical public key infrastructure (PKI) receives its CA certificate from the CA directly above it in the hierarchy. A root CA at the top of a PKI hierarchy must self-sign its own certificate, in effect certifying itself.

The CA certificate plays an important part in the workings of the Secure Sockets Layer (SSL) protocol. The CA's public key, contained in the CA certificate, is used to validate all other digital certificates that have been issued by that CA for entities (individuals, systems, companies, and organizations). When an entity such as a Web browser (perhaps Microsoft Internet Explorer) or a Web server (perhaps Microsoft Internet Information Services) requests a digital certificate from a CA, the CA certificate identifies the CA that issues the certificate.

This CA certificate is downloaded from a shared storage location at the certificate authority and installed onto the Web server or browser. Later, when the Web browser tries to access the Web server using the SSL protocol, the Web browser uses the CA certificate to validate the Web server's certificate. Similarly, the server can use the CA certificate to validate the browser client's certificate, if it has one.

Notes

The digital CA certificate for a CA must be kept in a location that is readily available for all servers and clients that will access it and install it on their Web browser or Web server. From this location, Web servers and Web clients that need to use the SSL protocol must obtain and install the CA certificate in their certificate stores. On Microsoft Certificate Server, this location is the default Web location http://Server_Name/certsrv, where Server Name is the name of the Microsoft Windows NT server on which Microsoft Certificate Server is installed.

Internet Explorer comes with the CA certificates of a number of certificate authorities preinstalled. These root certificates enable Internet Explorer to be used for functions such as SSL authentication and sending secure e-mail. If you want to use the services of a CA that does not have its CA root certificate installed in Internet Explorer, you can visit that CA's Web site to find instructions on how to obtain its root certificate. Administrators can also use the Internet Explorer Administration Kit (IEAK) for importing and installing root certificates on Web browsers prior to installation on client machines.

See Also: *certificate authority (CA), client certificate, digital certificate*

caching

Generally, any mechanism for storing frequently needed information in accessible memory so that it can be quickly retrieved. This article focuses on caching as the temporary storage of Web content to enable faster access by users.

Overview

While caching in general has been around a long time and has been implemented in various ways in computer systems and networks (see Notes at the end of this article), caching of Web content has exploded over the last few years into a big industry. In the context of the Internet, caching means the copying of Web content to storage locations near the client so that the client's Web browser can more quickly access the information. Caching speeds up accessing Web content and makes better use of available bandwidth (especially important when the Internet is accessed over slow and costly wide area network [WAN] connections).

While the emergence of broadband Internet access may seem to sidestep the need for caching, this is not really so. Most analysts agree that with the Internet, providing faster access simply drives up demand further and raises expectations, leading to even greater traffic congestion and frustration for users. The solution to bogged-down Internet access is caching.

Implementation

Caching can be implemented in a variety of ways using different systems. The simplest arrangement is deploying cache servers on the network. A cache server is used to speed corporate access to Web content on the Internet by caching the Web pages that users most frequently request. Cache servers reduce network traffic and speed up access to frequently requested content by caching such content. If a user requests a page that has recently been cached, the page will be retrieved from the cache server instead of from the Internet. Pages are held in the cache until they expire.

The cache server locates the content closer to the users who need it than the Web servers that contain the original version of this content. In general, the closer the cache to the user, the faster the response time the user will experience when trying to access this content in a browser. In the enterprise, cache servers are typically deployed at the edge of the corporate network, thus reducing overall WAN link traffic and congestion and saving money. Many firewalls and proxy servers include some form of content caching. Although firewalls and proxy servers are mainly concerned with securing access between a private corporate network and an distrusted public network such as the Internet, including cache server functionality in these products enhances their overall performance.


Request satisfied from cache
5
Client
4
Second request
Cache
Proxy server with content caching
3
Corporate LAN
1
Initial request
3
Saved in cache and returned to client
1
3
Internet
Web server
1
2
Response

Caching. *How a simple cache server can improve access time for clients.*

Caching servers are also useful in situations where a sudden increase in Web traffic is anticipated, as when a major sports or fashion event will be covered on the Web. In this case, simply throwing bandwidth at the problem of Internet traffic congestions is not a viable solution because increased bandwidth simply leads to increased demand from users. Instead, by preloading content from Web servers to caching servers, users will not overwhelm the Web servers on the day of the event and be disappointed. This use for caching servers is sometimes called "dealing with flash crowd control" or the "instant popularity problem." By using a network of cache servers in such situations and configuring replication appropriately between them, supply can be scaled for demand at virtually any level.

Dedicated cache servers are also used in high-traffic situations within the Internet backbone itself to reduce congestion on the backbone. Caching servers are often located at Internet service providers (ISPs) and Network Access Points (NAPs) for improving the overall performance and responsiveness of the Internet. This can be used to reduce the effect of bottlenecks on ISP networks and to reduce the cost of local ISPs buying bandwidth from regional ISPs.

Cache servers can even be deployed at the customer premises and configured with preloaded content to speed access to corporate intranets. Such a scenario is similar to the built-in content caching capability of Web browsers, but in this case the content is cached locally on a machine separate from the client machine to improve performance even more.

Types

As far as administrators are concerned, caching servers come in two basic types:

- **Caching appliances:** These are preconfigured servers with preloaded caching software that can easily be dropped into the network by simply connecting them to a backbone switch and turning them on.
- **Caching software:** This includes software from different vendors that can be loaded onto servers and deployed as needed within the network by the administrator. Caching software is especially targeted toward the needs of the corporate enterprise for improving remote access to corporate intranets.

In addition, from the user's perspective, cache servers can be implemented in different ways:

- **Transparent caching:** Here cache servers filter Internet Protocol (IP) traffic to find out which Web pages are most requested in order to determine which pages should be cached and for how long. Transparent cache servers require no special modification or configuration of the client in order to operate, but the cache server itself must be placed at the edge of the WAN, typically by connecting it to a Layer 4 switch or WAN access router so that every request sent by a client is examined by the cache server first before routing it over the Internet to its intended destination.
- **Proxy caching:** Here the administrator configures the client browsers to send their requests for Web content directly to the cache servers., If these cannot respond to the request (for example, if the page has not been cached or has expired from the cache), the cache server refers the client to the actual Web server hosting the content. This option requires more configuration but gives administrators greater control over what content users can access and provides an extra layer of security.
- **Reverse proxy caching:** Here a group of cache servers typically serves as a front-end to the Web server on the Internet, which hides behind them. User requests go directly to the cache servers, which appear as Web servers to the client. Reverse proxy caching is typically used to deal with flash crowd control discussed earlier.

Cache servers also determine whether to flush content from their cache in different ways:

- **Active caching:** Here the cache server uses intelligent heuristics to determine how long to keep a page in the cache before marking it expired. Many factors can be taken into account, including the requesting IP address, the hit statistics for the page, and how long the page has been cached.
- **Passive caching:** When a client requests a page from the cache, the cache server issues an HTTP GET IF MODIFIED command to the originating Web server to determine if the cache contains the latest version of the page. If not, the cache requests the current version and then forwards this to the client. If the cache does hold the current version, this is returned immediately to the client. The main disadvantage of passive caching is that it introduces the extra step of having the cache server contact the Web server each time a client requests a page, which, unless the cache server is close (in a network sense) to the Web server,

will have the opposite effect from what caching was intended to do—it will slow down the response time instead of speeding it up.

- **Forced caching:** In this case the cache server is preloaded with content that users are expected to frequently access. Forced caching is typically used for improving access to corporate intranets for remote users.

Marketplace

The caching industry has exploded over the last few years, driven by the tremendous growth of the Internet and the demand of users for fast performance in accessing Web sites. In the arena of general caching software, the top players include Microsoft Corporation's Internet Acceleration and Security Server (IAS Server), the successor to Microsoft Proxy Server; Novell's Internet Caching System; and several UNIX-based solutions.

In the arena of prepackaged caching appliances, offerings are available from Dell Computer Corporation's (PowerApp.cache), Compaq (TaskSmart), Cobalt Networks (Qube), Network Appliance (NetCache), and many others. Caching appliances range from those targeted for corporate intranets to powerful caching solutions for ISPs and telecoms.

A number of pure-play caching vendors have had a large impact on the caching market. Some of the big players here include Inktomi Corporation, CacheFlow, and Network Appliance. Inktomi offers routers and load balancers from Alteon WebSystems and Foundry Networks bundled together with Inktomi's Traffic Server caching software. Cisco Systems and Lucent Technologies also offer high-end caching appliances with proprietary operating system kernels tuned for top performance in this application.

A relatively new approach is called predictive client-side caching and involves configuring a plug-in for client browsers that determines what kinds of content the client accesses and then attempts to preload such content during idle times so that when the client requests it the content is already in the browser cache. Blueflame, a product from Fireclick, is one example of predictive client-side caching technology. Fireclick also has a hosted version of this application called Netflame. Packeteer has a product called AppCelera Internet Content Accelerator (ICX) that boosts performance by adapting requested content to the type of browser requesting it and by compressing content to make better utilization of available bandwidth.

Issues

Caching of dynamic Web content presents an ever-greater challenge as more and more Web sites move away from static informational content to deploying database-driven e-commerce Web applications. Dynamic Web pages are generated from databases in response to user queries and often include some form of personalization as well. Dynamic content cannot be cached the way static content can, but a number of vendors have come up with various methods for improving the performance of dynamic Web applications by using caching. For example, the components of a Web application can be cached for reuse across multiple user sessions. Another approach is to dynamically monitor the configuration of Web applications to better manage stale cache content. Vendors of dynamic caching systems include Xcache Technologies, Chutney Technologies, and SpiderSoftware. NetScaler offers a caching device that routes requests for static content to traditional cache servers while multiplexing requests for dynamic content over persistent connections with Web servers to improve performance.

Notes

Caching in a general sense is used in various ways by operating systems, applications, and network devices to improve performance by providing temporary storage of information that needs to be quickly accessed. Some common examples include

- The file system cache for the Microsoft Windows 2000 operating system, which speeds up file access from hard disk drives
- Offline Files in Windows 2000, which allows users to browse network file system content when disconnected from the network
- Domain Name System (DNS) cache for caching recently resolved host names on a name server, which speeds up the resolution of host names for the DNS on the Internet

- Address Resolution Protocol (ARP) cache on a host connected to an IP internetwork, which is used for caching IP addresses that have recently been resolved into MAC addresses, thus speeding up network communications between hosts
- Microsoft Internet Security and Acceleration (ISA) Server, which allows Web content obtained from the Internet to be cached locally for faster access and reduction of WAN link congestion
- Caching of open database connectivity (ODBC) connections for improved access to Microsoft SQL Server databases for Active Server Pages (ASP) applications written for Microsoft Internet Information Services (IIS)

For More Information

Find out more about caching technologies at these sites: *www.caching.com* and *www.web-caching.com.*

See Also: *Content Delivery Provider (CDP), Web server*

Caching Array Routing Protocol (CARP)

A protocol developed by Microsoft Corporation that allows multiple proxy servers to be arrayed as a single logical cache for distributed content caching.

Overview

Caching Array Routing Protocol (CARP) is implemented as a series of algorithms that are applied on top of Hypertext Transfer Protocol (HTTP). CARP allows a Web browser or downstream proxy server to determine exactly where in the proxy array the information for a requested Uniform Resource Locator (URL) is stored.

CARP enables proxy servers to be tracked through an array membership list that is automatically updated using a Time to Live (TTL) countdown function. This function regularly checks for active proxy servers in the array. CARP uses hash functions and combines the hash value of each requested URL with each proxy server. The URL/proxy server hash with the highest value becomes the owner of the information cached. This results in a deterministic location for all cached information in the array, which enables a Web browser or downstream proxy server to know exactly where a requested URL is locally stored or where it will be located after it has been cached. The hash functions result in cached information being statistically distributed (load balanced) across the array. Using hashing means that massive location tables for cached information need not be maintained—the Web browser simply runs the same hashing function on the object to locate where it is cached.

Advantages and Disadvantages

CARP provides two main benefits:

- It saves network bandwidth by avoiding the query messaging between proxy servers that occurs with conventional Internet Cache Protocol (ICP) networks.
- It eliminates the duplication of content that occurs when proxy servers are grouped in arrays, resulting in faster response times and more efficient use of server resources.

See Also: *caching, proxy server*

caching-only name server

A name server in the Domain Name System (DNS) that can resolve name lookup requests but does not maintain its own local DNS database or zone file of resource records.

Overview

Caching-only name servers do not have their own DNS databases. Instead, they resolve name lookup requests from resolvers by making iterative queries to other name servers. When the responses to these queries are received, the caching-only name server caches them, in case another resolver issues the same request within a short period of time.

A caching-only name server is not authoritative for any particular DNS domain. It can look up names that are inside or outside its own zone.

Notes

Caching-only name servers are not the only kind of name server that performs caching of resolved queries. For example, primary name servers also cache name lookups that they perform. This caching generally improves the primary name server's response to name lookup requests from resolvers. Caching-only name servers are distinguished by the fact that they perform only one function: issuing iterative queries to other name servers and then caching the results.

Caching-only name servers provide support for primary and secondary name servers in environments where name lookup traffic is heavy. Using caching-only name servers where possible also reduces the overhead of zone transfers between name servers on a network.

See Also: *Domain Name System (DNS), name server*

caching service provider (CSP)

A company that maintains caching servers that speed the transfer of information across the Internet's infrastructure and offers managed access to these servers for a fee.

Overview

Many companies think that if they host their Web site at an Internet service provider (ISP) or at a major Web hosting company, the site will always be accessible from anywhere on the Internet, but this is not necessarily true. Traffic congestion can cause access to a Web server to be slow and unreliable from various parts of the Internet at various times of the day, and equipment failures (such as routes going down at Internet peering points) can make a server completely inaccessible to certain portions of the Internet until the problem is fixed. ("Peering" means two ISPs or other providers passing traffic between each other's customers.)

One solution is to mirror (replicate) your Web server at various points around the globe so that a copy of your site is relatively close to any location on the Internet. For companies with a global presence, this is a fairly simple solution to implement, but most companies do not have the presence or the resources to implement global mirroring. A better solution might be to use the services of a caching service provider (CSP), which maintains cached copies of your Web site at various points in the Internet's infrastructure and provides tools for managing and load balancing the content to handle traffic spikes that occur at certain times of the day or year.

CSPs maintain data centers around the world with caching server farms that have high-speed connections to the Internet's backbone. These caching servers are usually designed to cache Web content and often support features such as content management and proxying. Caching servers can also be used within the corporate network to speed access to large, distributed corporate intranets.

See Also: *caching*

CAL

Stands for client access license, a license that grants a client machine access to a Microsoft BackOffice product running on a network of computers.

See: *client access license (CAL)*

callback

A security feature for remote access servers.

Overview

Callback provides an extra layer of security for users dialing in to a remote access server. When callback is configured, the client software dials in to a remote access server and has the user's credentials authenticated. The remote access server then disconnects the client and calls the client back at a previously specified phone number. Callback might be configured in the following ways:

- To ensure that the user matches his or her credentials by verifying the telephone location
- For accounting reasons—for example, to charge the phone bill to the remote access server instead of to the client



Callback. *How callback is used in remote access.*

Callback is an optional feature supported by the Routing and Remote Access service of Microsoft Windows 2000 and Windows .NET Server. Note that in Windows 2000 and Windows .NET Server, the phone number specified for callback is called the Caller ID number.

See Also: *remote access*

Callback Control Protocol (CBCP)

A protocol that enables callback for establishing Point-to-Point Protocol (PPP) connections.

Overview

The Callback Control Protocol (CBCP) is part of Microsoft Corporation's implementation of the Point-to-Point Protocol (PPP). CBCP makes it possible for a PPP server to call back the remote dial-in client to complete initiation of a PPP dial-up session. Callback is a useful security feature for ensuring that dial-in clients are authentic.

Implementation

The CBCP is used during the third phase of establishing a PPP connection. After the PPP link is established using the Link Control Protocol (LCP) and the user's credentials are authenticated using Microsoft Challenge Handshake Authentication Protocol (MS-CHAP) or some other authentication protocol supported by the client, the network access server (NAS) at the PPP service provider can optionally initiate a PPP callback control phase, provided that callback is configured on the server. The NAS and the PPP clients both disconnect from the PPP link, and the NAS calls the client back using the specified callback phone number. If the client responds, the link is reestablished; no further authentication is needed, and compatible network protocols are negotiated so that data transmission can begin.

See Also: *Point-to-Point Protocol (PPP)*

campus area network (CAN)

A group of connected local area networks (LANs) on a campus.

Overview

A campus area network (CAN) is intermediate in size between a LAN, which typically resides in a single room or building, and a metropolitan area network (MAN), which spans a city or metropolitan area. CANs exist on university campuses, in industrial parks, and in similar collections of buildings under a single administrative authority.

Implementation

CANs are typically built in hierarchical fashion starting from the top or inside with a core network (usually a collapsed backbone), a distribution network (routers or switches in different buildings), an access network (a collection of hubs and switches within wiring closets on each floor of the buildings), and finally end-user stations.

See Also: *local area network (LAN), metropolitan area network (MAN), Personal Area Network (PAN), wide area network (WAN)*

CAN

Stands for campus area network, a group of connected local area networks (LANs) on a campus.

See: *campus area network (CAN)*

CAP

Stands for carrierless amplitude and phase modulation, a line coding scheme in which data is modulated using a single carrier frequency.

See: *carrierless amplitude and phase modulation (CAP)*

capture

A collection of frames gathered from network traffic by a sniffer.

Overview

You can use packet-sniffing software such as Microsoft Network Monitor (which is included in Microsoft Systems Management Server and in a simplified form in Microsoft Windows 2000, Windows XP, and Windows .NET Server) for capturing all kinds of traffic on the network. This captured traffic is displayed in the capture window as a variety of statistics and details about the nature of the traffic. Additional windows can display details about individual packets that have been captured.

Capturing network traffic is a common troubleshooting technique on enterprise-level networks. Captures can show whether services such as Dynamic Host Configuration Protocol (DHCP), Windows Internet Name Service (WINS), Domain Name System (DNS), and other common network services are performing properly. Captures can also isolate servers that are generating excessive network traffic because of failed hardware. Captures can even be used to detect unauthorized traffic initiated by hackers and disgruntled employees and to profile network traffic for planning purposes.

See Also: *capture window, sniffing*

capture window

In Microsoft Network Monitor, the window that displays the statistics about the frames being captured on a network.

Overview

The capture window displays four kinds of real-time statistics concerning the traffic that an administrator captures using Network Monitor:

- **Graph statistics:** A graphical representation of current network activity that shows the percent of network utilization, frames captured per second, bytes captured per second, and broadcasts or multicasts captured per second
- **Session statistics:** Information about current sessions between computers on the network, showing which hosts have sent packets to each other
- **Station statistics:** Information about various stations involved in sending or receiving packets, showing how many of each type of packet they have sent or received
- **Total statistics:** Summary statistics about network activity since the capture began, including the number of frames, bytes, and frames dropped during the capture



Time Elapsed: 00:01:03.612

Network Statistics
Frames: 1476
Broadcasts: 17
Multicasts: 0
Bytes: 229143
Frames Dropped: 0
Network Status: Normal

Captured Statistics
Frames: 1476
Frames in Buffer: 1476
Bytes: 229143
Bytes in Buffer: 240951

Network Address 1	1-->2	1<--2	Network Address 2
48543300CD6A	174	182	R.P.T.D13290
48543300CD6A	54	50	R.P.T.D1296C
48543300CD6A	12		*BROADCAST
ADDTRN2216ED	1		*BROADCAST
ADDTRN2216ED	442	446	48543300CD6A

Network Address	Frames Sent	Frames Rcvd	Bytes Sent	Bytes Rcvd	Directed Frames Sent	Multicasts Sent	Broadcasts Sent
ADDTRN2216ED	443	446	54474	52820	442	0	1
ADDTRN2216ED	443	446	54474	52820	442	0	1
PICASSO	56	56	16090	8507	55	0	1
R.P.T.D1296C	52	54	9425	8140	50	0	2
R.P.T.D13290	183	174	57956	20319	182	0	1

Capture window. *The capture window in Network Monitor, which is included with Microsoft Systems Management Server.*

You can toggle these various windowpanes on and off during a capture to focus on statistics of interest.

See Also: *capture, sniffing*

Carnivore

An Internet surveillance system developed by the FBI (Federal Bureau of Investigation).

Overview

Carnivore was designed to help the FBI collect evidence to convict terrorists, drug smugglers, and hackers. Carnivore is a self-contained “black-box” Internet Protocol (IP) traffic filtering system that sniffs network traffic to find e-mail and other traffic that contains evidence of criminal activity.

Implementation

To use Carnivore, the FBI first obtains a court order to capture specific types of Internet traffic that may contain evidence of criminal wrongdoing by parties under consideration. The FBI then brings the Carnivore system to an Internet service provider (ISP) and connects the system to the backbone switches of the ISP’s network. Carnivore then monitors all traffic through the ISP, capturing only such traffic as matches the filter conditions established in the court order (this is called minimization—Carnivore does not snoop all traffic indiscriminately). For example, Carnivore might filter all messages coming from or going to a specific IP address block or having a certain keyword in the Subject line.

See Also: *sniffing, security*

CARP

Stands for Caching Array Routing Protocol, a protocol developed by Microsoft Corporation that allows multiple proxy servers to be arrayed as a single logical cache for distributed content caching.

See: *Caching Array Routing Protocol (CARP)*

carrier

A company that provides various kinds of telecommunication services to its customers.

Overview

A carrier provisions telecommunication services to the customer premises. These services include voice transmission, data transmission over analog modems, Integrated Services Digital Network (ISDN), digital subscriber line (DSL), frame relay, and anything else the carrier’s equipment supports. There are two basic kinds of carriers: LECs and IXCs.

A local exchange carrier (LEC) is a company that provides access to both local and long-distance telephone services through the local loop connecting the telco’s central office (CO) with the customer premises. In the United States, LECs are typically one of two kinds:

- Local phone companies, now usually called Incumbent Local Exchange Carriers (ILECs) but sometimes called Regional Bell Operating Companies (RBOCs).
- Competitive Local Exchange Carriers (CLECs), a new breed of LEC that has arisen in response to the Telecommunications Act of 1996. CLECs that offer primarily DSL voice/data services are often called DSL carriers.

An inter-exchange carrier (IXC), on the other hand, is a company that provides long-distance services only. IXCs own their own telecommunication facilities and provide long-distance services between LECs located in different toll-free areas. The big three in the IXC arena in order of size are AT&T, MCI WorldCom, and Sprint Corporation.

All long-haul carriers in the United States use Synchronous Optical Network (SONET) or ATM (Asynchronous Transfer Mode)/SONET as their backbone transport, and most local telcos use ATM in their own backbone networks also. Some LECs are also deploying Gigabit Ethernet (GbE) as an alternative to ATM for metropolitan area networks (MANs) that can bring GbE ports directly to the edge of corporate networks, providing end-to-end Ethernet connectivity for corporate wide area networks (WANs).

Outside the United States, most carriers use Synchronous Digital Hierarchy (SDH), essentially a variant of SONET.

Implementation

Almost all carriers rely on ATM as their underlying backbone transport and use this backbone to provision local and long-distance voice services, Internet access over DSL, leased-line WAN links, and other services. A large portion of the backbone of most long-haul carriers is currently at or near OC-48, providing maximum throughput of 2.488 gigabits per second (Gbps), but these backbone fiber connections are constantly being upgraded to support higher speeds such as OC-192 and OC-768.

Carriers usually house their high-speed switching equipment in large buildings called colocation centers. These centers have this name because under the Telecommunications Act of 1996, competitive local exchange carriers (CLECs) are allowed to lease space within carrier facilities for locating their own switching equipment. Another name for these centers is "data centers," and they are usually huge nondescript buildings that typically occupy hundreds of thousands of square feet. Sometimes several floors of existing buildings are used for data centers, but the trend is to build new centers to ensure that the highest standards of fire safety and security are used.

Marketplace

The global carrier market has become complex over the last decade, with traditional incumbent telcos in the United States and Post, Telegraph, and Telephone (PTT) companies in Europe being challenged on all sides by newcomers to the game. International carriers can be classified in different types, including

- **Incumbents:** These are traditional or established carriers such as public telephone companies, long distance companies, and PTTs in Europe.
- **Cross-border infrastructure owners:** These are companies that own the international lines carrying voice and data between countries, regions, and continents.
- **Resellers:** This includes companies reselling both local loop and long haul services purchased wholesale from other carriers.

To complicate things further, many large national carriers are constantly making efforts to expand into the international market by acquiring, or merging with, other carriers, upgrading their core equipment to provision new high-speed data services, while relegating some existing services to the legacy domain and trying to cope with the ever-exploding amounts of Internet bandwidth demanded by their customers. Because of the state of flux of the global telecommunications carrier market, the enterprise architect's dream of simple, seamless, global WAN connectivity remains a complicated reality of tariffs, interoperability issues, and politics.

See Also: *Competitive Local Exchange Carrier (CLEC), Incumbent Local Exchange Carrier (ILEC), inter-exchange carrier (IXC), local exchange carrier (LEC), telecommunications services*

carrierless amplitude and phase modulation (CAP)

A line coding scheme in which data is modulated using a single carrier frequency.

Overview

Carrierless amplitude and phase modulation (CAP) is used for transmission of voice information over a phone line. The transmission is considered "carrierless" because the carrier is suppressed before transmission and is reconstructed at the receiver. CAP is algorithmically similar to the quadrature amplitude modulation (QAM) line coding scheme, which encodes bits as discrete phase and amplitude changes, but it has different transmission characteristics.

Notes

Some competitive local exchange carriers (CLECs) deploy Asymmetric Digital Subscriber Line (ADSL) using CAP as the encoding method, but results of some independent tests suggest that CAP-encoded ADSL lines might cause spectral interference with proximate T1 lines and Integrated Services Digital Network (ISDN) circuits, resulting in bit errors that can reduce throughput. However, these tests might be misleading because of the limited number of ADSL circuits currently deployed by CLECs. Check with your carrier before signing up for ADSL services to get the latest information about this issue.

Such interference is not a problem with symmetric digital subscriber line (SDSL) technologies, which use the 2B1Q encoding scheme. Furthermore, ADSL deployed by incumbent local exchange carriers (ILECs) uses discrete multitone (DMT) technology, which does not produce the same degree of spectral interference as CAP.

Competitive local exchange carriers generally do not use DMT for ADSL because they must deal with the copper local loop, which effectively supports DMT only about half the time but can support CAP about 85 percent of the time. Furthermore, DMT has been adopted as the standard for ADSL by both the American National Standards Institute (ANSI) and the International Telecommunication Union (ITU).

See Also: *line coding*

Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA)

The media access control method used by AppleTalk.

Overview

Carrier Sense Multiple Access with Collision Avoidance (CDMA/CA) is a type of media access control method for placing signals on baseband transmission networks. Because baseband networks can carry only one data signal at a time, there must be some way of controlling which station has access to the media at any given time. CSMA/CA is one such control method.

Uses

CSMA/CA is the standard access method for AppleTalk networks based on LocalTalk. LocalTalk is a legacy network media technology that specifies the proprietary cabling components of the original AppleTalk networking architecture. LocalTalk uses a bus topology or tree topology that supports up to 32 stations on a network.

Implementation

In networking technologies that use CSMA/CA as their access method, stations announce their intention to transmit before they actually transmit their data onto the network media. Each station “listens” constantly to the wire for these announcements, and if it hears one, it avoids transmitting its own data. In other words, on a CSMA/CA network, stations try to avoid collisions with signals generated from other stations. The extra signaling generated by CSMA/CA makes it a slower access method than the Carrier Sense Multiple Access with Collision Detection (CSMA/CD) method used in Ethernet networking.

See Also: *AppleTalk, Carrier Sense Multiple Access with Collision Detection (CSMA/CD), Ethernet, media access control method*

Carrier Sense Multiple Access with Collision Detection (CSMA/CD)

The media access control method used by Ethernet.

Overview

Carrier Sense Multiple Access with Collision Detection (CSMA/CD) is a type of media access control method developed by Xerox Corporation in the 1970s for placing signals on baseband transmission networks. Because baseband networks can carry only one data signal at a time, there must be some way of controlling which station has access to the media at any given time. CSMA/CD is one such control method.

Implementation

In networking technologies that use CSMA/CD as their access method, a station first “listens” to the network media to make sure there is no signal already present from another station before it tries to place its own signal on the media. If a carrier signal is detected on the media, which indicates that a station is currently transmitting a signal, no other station can initiate a transmission until the carrier stops. If no carrier is detected, any station can transmit a signal.

If two stations listen to the wire and detect no carrier signal, they may both decide to send signals simultaneously. If this happens, a collision occurs between the two signals generated. Next, both stations detect the collision and stop transmitting their signals immediately, sending out a jamming signal that informs all other stations on the network that a collision has occurred and that they should not transmit. Meanwhile, the two stations whose signals created the collision cease transmitting and wait random intervals of time (usually a few milliseconds) before attempting to retransmit.

Issues

CSMA/CD is known as a contention method because computers contend for the chance to transmit data onto the network media. CSMA/CD is the standard access method for Ethernet networks. This method has two main drawbacks:

- Only a relatively small number of computers can exist within any one collision domain. More computers will produce more collisions and slow overall network traffic.
- CSMA/CD is not reliable beyond a distance of 1.5 miles (2.5 kilometers) because of signal attenuation.

Notes

The designation CSMA/CD derives from the following:

- CS means that stations first **s**ense a **c**arrier present on the media before transmitting their own signals.
- MA means that **m**ultiple stations can **a**ccess the network media.
- CD means that if a **c**ollision is **d**etected because of multiple simultaneous transmission of signals, the stations that are transmitting signals stop, and then retransmit a short time later.

See Also: *Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA), Ethernet, media access control method*

carrier signal

An alternating electromagnetic signal with a steady frequency upon which information is superimposed by some form of modulation.

Overview

The specific frequency at which a carrier signal runs is called the carrier frequency and is measured in hertz (Hz). The modulation of the carrier signal enables information such as voice or data traffic to be integrated into the carrier signal. The carrier signal thus “carries” the voice or data information using modulation technologies.

The type of modulation used in digital communication systems depends on whether the underlying carrier signal is analog or digital. For example, in digital radio or microwave communication, some form of digital-analog modulation, such as frequency-shift keying (FSK), is used to impose the digital (binary) information on the analog carrier wave. On the other hand, in Ethernet networking, a digital-digital encoding scheme called Manchester coding is used to enable the digital signal to carry binary 1s and 0s.

In Ethernet networks, the carrier signal plays an important role in the media access control method that Ethernet uses, namely the Carrier Sense Multiple Access with Collision Detection (CSMA/CD) method.

See Also: *Carrier Sense Multiple Access with Collision Detection (CSMA/CD)*

cascaded star topology

A layered form of star topology.

See Also: *star topology*

cascading style sheets (CSS)

A method for giving Web developers more control over how the pages of a Web site will look when displayed on a Web browser.

Overview

Cascading style sheets (CSS) is a standard from the World Wide Web Consortium (W3C) that gives Web developers control over design elements such as fonts and font sizes and allows two-dimensional overlapping and exact positioning of page elements. The CSS standard also makes it easier to globally change the style and appearance of a Web site without having to change elements on every page.

Implementation

Hypertext Markup Language (HTML) was designed for logical communication of linked information without much regard for its style or format, and it was not designed to provide a high degree of control over how that information is laid out on a page. Using CSS, a Web developer can control the appearance of an entire Web site, or a portion of it, using a single HTML page called a style sheet. The genius of CSS is that it separates the content of the page (formatted in HTML) from the page layout (defined in the style sheet using CSS).

Style sheets define the functions of different HTML tags on your site's Web pages and allow you to make global changes to your site's style by changing a single entry on a style sheet. Web pages then link to style sheets using a <LINK> tag.

For example, you can use a style sheet to define the <H1> tag as representing green, 18-point, Arial font text, and you can then apply this style to the entire site or a portion of it. Cascading style sheets involve the operation of several levels of style sheets that provide control over how an element on an HTML document is placed. CSS applies these settings in the following order:

- The STYLE attribute in the object's tag
- The STYLE element between the <TITLE> and <BODY> tags that specifies the style sheet to be used
- The settings of the browser accessing the page and its default style sheet

Issues

The main factor that has prevented CSS from being widely implemented on most Web sites is that neither Microsoft Internet Explorer nor Netscape Navigator fully supports all aspects of the CSS standard. Thus, a CSS-enabled site may look one way in Internet Explorer and another way in Netscape, and neither may be what the site designer intended. One Web browser that fully implements the CSS standard is Opera, developed by Hakon Lie, who has been involved in the W3C.

For More Information

You can find the W3C standard for CSS version 2 at *www.w3c.org/Style*.

See Also: *Hypertext Markup Language (HTML)*

Cat5 cabling

Stands for Category 5 cabling, the most common grade of unshielded twisted-pair (UTP) cabling used for structured wiring in commercial buildings.

See: *Category 5 (Cat5) cabling*

Cat5e cabling

Stands for enhanced Category 5, a form of Category 5 (Cat5) cabling that supports higher speeds.

See: *enhanced Category 5 (Cat5e) cabling*

Cat6 cabling

Stands for Category 6 cabling, the proposed next step up from enhanced Category 5 (Cat5e) cabling.

See: *Category 6 (Cat6) cabling*

Cat7 cabling

Stands for Category 7 cabling, a still-hypothetical next step up from the proposed Category 6 (Cat6) cabling.

See: *Category 7 (Cat7) cabling*

catalog

The top-level organizational structure for the Indexing service in Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Overview

The catalog contains the master index and other persistent indexes. The Index Server catalog is located by default in the directory %systemdrive%\inetpub\catalog.wci, but this can be overridden during installation. The maximum size of the catalog for Index Server is 40 percent of the size of the documents being indexed (the corpus), so it is important when installing Index Server to locate the catalog on a drive with sufficient free space. For example, if you will be indexing 10 gigabytes (GB) of documents, you will need about 4 GB of space for locating your catalog.

Notes

An Indexing service query can span only one catalog at a time, so do not create multiple catalogs unless you want to completely separate the indexing of their documents—for example, if you are hosting Web sites for multiple companies on your server.

If you are hosting more than one virtual server on a Microsoft Internet Information Services (IIS) machine, and these virtual servers represent different companies, you might want to create multiple catalogs for the Indexing service, one for each virtual server. Each catalog will then be used for indexing a specific virtual server, and queries based on a catalog will return only results for content on the associated virtual server.

Category 1 (Cat1) cabling

The lowest grade of unshielded twisted-pair (UTP) cabling.

Overview

Category 1 (Cat1) cabling was designed to support analog voice communication only. Cat1 cabling was used prior to 1983 for wiring installations of analog telephone systems, otherwise known as the Plain Old Telephone Service (POTS). The electrical characteristics of Cat1 cabling make it unsuitable for computer networking purposes, and it is never installed as premise wiring for structured cabling installations. Instead, all premise wiring should use either Category 3 (Cat3) cabling, Category 4 (Cat4) cabling, or Category 5 (Cat5) cabling, with Cat5 or enhanced Category 5 (Cat5e) cabling preferred for all new installations.

See Also: *cabling, premise cabling, structured wiring*

Category 2 (Cat2) cabling

The second-lowest grade of unshielded twisted-pair (UTP) cabling.

Overview

Category 2 (Cat2) cabling was designed to support digital voice and data communication. Cat2 cabling was capable of data transmissions up to 4 megabits per second (Mbps). It was used primarily in the installation of premise wiring for legacy Token Ring networks from IBM. The electrical characteristics of Cat2 cabling make it unsuitable for most networking purposes today, thus it is no longer installed as premise wiring. Instead, all premise wiring today should use only Category 3 (Cat3) cabling, Category 4 (Cat4) cabling, or Category 5 (Cat5) cabling, with Cat5 or enhanced Category 5 (Cat5e) cabling preferred for all new installations.

See Also: *cabling, premise cabling, structured wiring*

Category 3 (Cat3) cabling

The third-lowest grade of unshielded twisted-pair (UTP) cabling.

Overview

Category 3 (Cat3) cabling was designed to support digital voice and data communication at speeds up to 10 megabits per second (Mbps). It uses 24-gauge copper wires in a configuration of four twisted-pairs enclosed in a protective insulating sheath. Cat3 cabling is the lowest grade of UTP cabling that can support standard 10BaseT types of Ethernet networks and was often used for legacy 4-Mbps Token Ring installations.

Cat3 cabling still has a significant installed base in older buildings, and for basic 10BaseT Ethernet purposes, it is often cheaper to use existing Cat3 cabling than to upgrade to Category 5 (Cat5). Installing higher-grade cabling for backbone cabling in vertical rises and elevator shafts can extend the life of work areas that still use Cat3 cabling. However, if greater speeds are required at users' workstations, the best solution is to rewire the work areas using Cat5 cabling or enhanced Category 5 (Cat5e) cabling.

The following table summarizes the electrical characteristics of Cat3 cabling at different frequencies, which correspond to different data transmission speeds. Note that attenuation increases with frequency, while near-end crosstalk (NEXT) decreases.

Cat3 Cabling Characteristics

Characteristic	*Value at 10 MHz*	*Value at 16 MHz*
Attenuation	27 decibels (dB)/ 1000 feet	36 dB/1000 feet
NEXT	26 dB/1000 feet	23 dB/1000 feet
Resistance	28.6 ohms/1000 feet	28.6 ohms/1000 feet
Impedance	100 ohms (± 15%)	100 ohms (± 15%)
Capacitance	18 pF/feet	18 pF/feet

See Also: *cabling, Category 5 (Cat5) cabling, enhanced Category 5 (Cat5e) cabling, premise cabling, structured wiring*

Category 4 (Cat4) cabling

The grade of unshielded twisted-pair (UTP) cabling just below standard Category 5 (Cat5) cabling.

Overview

Category 4 (Cat4) cabling was designed to support digital voice and data communication at speeds up to 16 megabits per second (Mbps). It uses 22-gauge or 24-gauge copper wires in a configuration of four twisted-pairs enclosed in a protective insulating sheath. Cat4 cabling can support standard 10BaseT types of Ethernet networks. It was also commonly used in older 16-Mbps Token Ring installations.

Cat4 cabling still has some installed base in older buildings where it is often cheaper to use the existing cabling than to upgrade to newer grades. Installing higher-grade cabling for backbone cabling in vertical rises and elevator shafts can extend the life of work areas that still use Cat4 cabling. However, if greater speeds are required at users' workstations, the best solution is to rewire the work areas using Cat5 cabling or enhanced Category 5 (Cat5e) cabling.

The following table summarizes the electrical characteristics of Cat4 cabling at different frequencies, which correspond to different data transmission speeds. Note that attenuation increases with frequency, while near-end crosstalk (NEXT) decreases.

Cat4 Cabling Characteristics

Characteristic	*Value at 10 MHz*	*Value at 20 MHz*
Attenuation	20 decibels (dB)/ 1000 feet	31 dB/1000 feet
NEXT	41 dB/1000 feet	36 dB/1000 feet
Resistance	28.6 ohms/1000 feet	28.6 ohms/1000 feet
Impedance	100 ohms (± 15%)	100 ohms (± 15%)
Capacitance	18 pF/feet	18 pF/feet

See Also: *cabling, Category 5 (Cat5) cabling, enhanced Category 5 (Cat5e) cabling, premise cabling, structured wiring*

Category 5 (Cat5) cabling

The most common grade of unshielded twisted-pair (UTP) cabling used for structured wiring in commercial buildings.

Overview

Category 5 (Cat5) cabling was designed to support digital voice and data communication at speeds up to 100 megabits per second (Mbps). It uses 22-gauge or 24-gauge copper wires in a configuration of four twisted-pairs enclosed in a protective insulating sheath. It is still the highest official grade of UTP cabling currently recognized by the Electronic Industries Alliance (EIA) and Telecommunications Industry Association (TIA), although proposals have been made for higher Category 6 (Cat6) and Category 7 (Cat7) grades.

Cat5 cabling is the standard grade of UTP cabling for common networking architectures including 10BaseT Ethernet, Fast Ethernet, and 1000BaseT Gigabit Ethernet (GbE) over copper. Cat5 cabling typically makes up over 80 percent of the wiring in today's corporate network. Its continuing popularity in high-speed networks is because fiber-optic cabling is still about twice as expensive to deploy as Cat5 cabling. Because of its superior electrical characteristics, Cat5 cabling is recommended for all new structured wiring installations as well as for upgrading existing premise wiring to support higher-speed networks.

The following table summarizes the electrical characteristics of Cat5 cabling at different frequencies, which correspond to different data transmission speeds. Note that attenuation increases with frequency, while near-end crosstalk (NEXT) decreases.

Cat5 Cabling Characteristics

Characteristic	*Value at 10 MHz*	*Value at 100 MHz*
Attenuation	20 decibels (dB)/ 1000 feet	22 dB/1000 feet
NEXT	47 dB/1000 feet	32.3 dB/1000 feet
Resistance	28.6 ohms/1000 feet	28.6 ohms/1000 feet
Impedance	100 ohms (± 15%)	100 ohms (± 15%)
Capacitance	18 pF/feet	18 pF/feet
Structural return loss	16 dB	16 dB
Delay skew	45 nanoseconds (ns)/100 meters	45 ns/100 meters

Marketplace

There are a vast number of different brands of Cat5 cabling on the market today. One estimate is that there are over 150 different vendors of such cabling. Not all Cat5 cabling is alike, and before undertaking a costly large-scale deployment of structured wiring, the enterprise architect should carefully investigate and compare the different brands.

Notes

For typical installations of Ethernet and Fast Ethernet, Cat5 cables in work areas should be no more than 300 feet (90 meters) long, and Cat5 patch cords should be no longer than 33 feet (10 meters). Check the Ethernet specifications for exact lengths permitted.

Many vendors offer an enhanced Cat5 (Cat5e) cabling grade with electrical characteristics exceeding those of standard Cat5. Cat5e cabling typically supports data transmission up to frequencies of 350 MHz, and new standards are under development to allow even higher data transmission frequencies. Cat5e networking is recommended for Gigabit Ethernet (GbE) over copper, but properly installed Cat5 cabling should work in most GbE setups. For best performance of GbE networks, however, use Cat5e or Cat 6 cabling whenever possible.

There is widespread agreement that Cat5 cabling will not be able to support networks beyond GbE, such as the 10 GbE architecture currently under development. Such ultra-high speed networks will likely work only with fiber and will not support copper.

See Also: *cabling, enhanced Category 5 (Cat5e) cabling, premise cabling, structured wiring*

Category 6 (Cat6) cabling

The proposed next step up from enhanced Category 5 cabling (Cat5e).

Overview

Category 6 (Cat6) is a proposed Electronic Industries Association/Telecommunications Industry Association (EIA/TIA) cabling standard that represents the next step up from Cat5 and Cat5e cabling. The following table shows the current draft standard for Cat6 cabling characteristics.

Proposed Cat6 Cabling Characteristics

Characteristic	*Value at 250 MHz*
Attenuation	19.9 decibels (dB)/1000 feet
NEXT	44.3 dB/1000 feet
Impedance	100 ohms (± 15%)
Return loss	20.1 dB
Delay skew	45 nanoseconds (ns)/100 meters
PS-NEXT	42.3 dB

Implementation

Great care must be taken when installing Cat6 cabling in order to have it achieve its design goals because poorly installed Cat6 cabling may offer only Cat5 performance. To get best performance out of Cat6 cabling for high-speed networking, be sure to follow the following guidelines:

- Buy cabling that has a definite spline separating the cables to reduce crosstalk.
- Make sure twists in wires are kept flush with connections at all termination blocks to avoid return-loss issues.
- Liberally use a hook and loop fastener, such as Velcro, to prevent cable from becoming excessively crimped.

Issues

Despite the formation in 1999 of a TIA task force to develop an official standard for a proposed Cat6 cabling, this unshielded twisted-pair (UTP) cabling standard remains to be ratified. The inherent engineering difficulties of standardizing cabling transmission characteristics for transmissions at 250 MHz and above, coupled with the fact that many cabling vendors have released their own "Category 6 or better" cabling, has led to some confusion in the marketplace. A factor that has slowed the development of Cat6 standards was the successful implementation of 1000BaseT Gigabit Ethernet (GbE) over Cat5 cabling, which relaxed the immediate need for a higher Cat6 class of cable and slowed the momentum of the Cat6 standards process. Cat6 thus currently appears as a solution in search of a problem, and the emergence of 10 Gigabit Ethernet (10 GbE) may have little impact on this situation because 10 GbE is envisioned as a fiber-only architecture.

At present Cat6 cabling solutions are essentially "channel solutions," meaning that their successful implementation depends on purchasing cabling components (such as cabling, patch panels, jacks, and wall plates) from a single vendor. Until an official Cat6 standard emerges, networking architects are recommended to use such channel solutions from a singling cabling vendor. In fact, some believe that "mix and match" cabling solutions for Cat6 will never be achieved due to the careful tuning of components that must be performed to make such systems work.

Notes

Existing cable testing equipment will not be able to evaluate Cat6 cabling because Cat6 not only includes additional parameters that must be measured but also specifies at least 10 dB greater precision in measuring existing cabling transmission characteristics over that achieved by Cat5e test equipment.

Some experts believe that it may be possible in the future to run 10 gigabits per second (Gbps) over Cat6 cabling at distances up to 330 feet (100 meters). If this is the case, then Cat6 cabling may well serve as an alternate infrastructure solution to fiber for the emerging 10 GbE standard. Such uses of Cat6 cabling are likely to be restricted to niche applications such as switch-switch and switch-server interconnects and within some types of storage area networks (SANs).

Another name for the proposed Cat6 cabling standard is Class E.

See Also: *10GbE, cabling, enhanced Category 5 (Cat5e) cabling, premise cabling, structured wiring*

Category 7 (Cat7) cabling

A still-hypothetical next step up from the proposed Category 6 (Cat6) cabling.

Overview

There is as yet no official Telecommunications Industry Association (TIA) standard for unshielded twisted-pair (UTP) cabling above Cat6, and Cat6 itself is still under consideration and has not been ratified as a standard. Nevertheless, many cabling vendors are offering "Category 7 cabling solutions" that exceed the specifications of Cat6. Such marketing should be taken with a grain of salt, as they do not represent true Cat7 standards, but such "channel solutions" involving cabling system elements purchased from a single vendor can provide significantly better performance than standard enhanced Category 5 (Cat5e) cabling. It is likely that when a true Cat7 standard emerges, it may require the replacement of the ubiquitous RJ-45 connector, which is a weak point in the transmission architecture for UTP cabling. Unfortunately, this means that existing networking equipment such as switches and routers may not be able to support Cat7.

While the Electronic Industries Association/Telecommunications Industry Association (EIA/TIA) has currently abandoned efforts to standardize Cat7, standards efforts are underway on the international scene through the efforts of the International Standards Organization (ISO) and International Electrotechnical Commission (IEC).

Notes

Another name for proposed Cat7 cabling is Class F cabling.

See Also: *cabling, Category 6 (Cat6) cabling, premise cabling, structured wiring*

CBCP

Stands for Callback Control Protocol, a protocol that enables callback for establishing Point-to-Point Protocol (PPP) connections.

See: *Callback Control Protocol (CBCP)*

CBQ

Stands for class-based queuing, an emerging technology for WAN traffic management.

See: *class-based queuing (CBQ)*

CBT

Stands for Core-Based Trees, a multicast routing protocol.

See: *Core-Based Trees (CBT)*

CDDI

Stands for Copper Distributed Data Interface, a form of Fiber Distributed Data Interface (FDDI) deployed over copper cabling instead of fiber.

See: *Copper Distributed Data Interface (CDDI)*

CDE

Stands for Common Desktop Environment, a graphical user interface (GUI) or desktop environment developed for UNIX systems.

See: *Common Desktop Environment (CDE)*

CDF

Stands for Channel Definition Format, an open standard created by Microsoft Corporation for Microsoft Internet Explorer version 4 (and proposed as a standard to the World Wide Web Consortium) that defines a “smart pull” technology for webcasting information to users’ desktops.

See: *Channel Definition Format (CDF)*

CDF file

Text files used for creating Active Channels, Active Desktop items, and channel screen savers for managed webcasting of content to users’ desktops.

Overview

CDF files are based on the Channel Definition Format (CDF) standard. CDF files provide a mechanism for allowing users to select the content they want to download from a Web site, and they let administrators schedule content for delivery to users’ desktops.

CDF files are used to convert existing Web sites into Active Channels without the need to change the existing site in any way. You simply create a CDF file using a text editor such as Microsoft Notepad and include it in your site. This will allow the content of the site to be webcast to users’ browsers. The CDF file must be saved with the extension .cdf, and a link on your site should point to this file so that users can subscribe to the channel.

A typical CDF file defines a channel hierarchy for the different Web sites making up the Active Channel. This channel hierarchy contains a table of contents for webcasting the content and consists of a top-level channel, subchannels, and actual content items (Web pages). The simplest format for a CDF file is a list of Uniform Resource Locators (URLs) that point to specific Web pages in the site. More advanced CDF files can contain information such as the following:

- A map of the hierarchical structure of the URLs in the Web site
- Logical groupings of different content items within a site that can differ from the observable link structure of the site itself
- The title of each referenced Web page and a brief abstract of its contents
- Information controlling the scheduling of content updates

The syntax of advanced CDF file items is based on the Extensible Markup Language (XML), an open specification that provides extensibility to standard Hypertext Markup Language (HTML) files. More than one CDF file can be created for a site, allowing users to subscribe to information in different fashions. For example, a news site can have separate CDF files for news, sports, and weather subscriptions.

Notes

For specific information on the syntax of CDF files and how to create them, refer to the Microsoft Internet Client software development kit (SDK).

Channels in Active Channel enable personalized delivery of Web content using Web applications designed for Internet Information Service (IIS) for Windows 2000. Active Server Pages (ASP) can be used for dynamically generating personalized CDF files for users. Cookies can also be used for dynamically generating customized CDF files for users. These CDF files can be customized on the basis of preferences that a user specifies on an HTML form prior to subscribing to the channel.

See Also: *Channel Definition Format (CDF)*

CDFS

Stands for CD-ROM File System, a file system designed for read-only CD-ROM media.

See: *CD-ROM File System (CDFS)*

CDMA

Stands for Code Division Multiple Access, a second-generation (2G) digital cellular phone technology that uses spread-spectrum techniques, popular in the United States and some other parts of the world.

See: *Code Division Multiple Access (CDMA)*

CDMA2000

A proposed third-generation (3G) upgrade for existing Code Division Multiple Access (CDMA) cellular telephone systems.

Overview

CDMA2000 was developed by the Telecommunications Industry Association (TIA) and is part of the International Mobile Telecommunications 2000 (IMT-2000) initiative of the International Telecommunication Union (ITU). CDMA2000 will boost the bandwidth of existing cdmaOne cellular systems to 2 megabits per second (Mbps), making global broadband wireless communications a reality.

Because the proposed CDMA2000 upgrade includes only a small portion of the overall wireless communication market, the IMT-2000 initiative also includes proposed upgrades to Time Division Multiple Access (TDMA) systems such as Global System for Mobile Communications (GSM). A competing upgrade for TDMA systems is General Packet Radio Service (GPRS), which is closer to implementation than CDMA2000 and might therefore win more initial support than CDMA2000.

The term *CDMA2000 1x* is commonly used to describe various interim CDMA2000 systems that use existing IS-95a base stations to provide 2.5G cellular services. CDMA2000 1*x* systems expect to achieve data transmission speeds of between 144 kilobits per second (Kbps) and 307 Kbps and are therefore classed as 2.5G cellular services instead of the much faster 3G services envisioned by IMT-2000. The proposed 3G system Wideband CDMA (W-CDMA) is comparable to CDMA2000 2*x*, meaning the 3G version of CDMA2000.

The CDMA Development Group is also promoting a different CDMA2000 upgrade called High Data Rate (HDR) CDMA2000 1*x*. This platform is based on the American National Standards Institute (ANSI) IS-95c standard and is viewed as an alternative upgrade path from CDMAone toward 3G. It involves a hardware upgrade using chipsets produced by QUALCOMM (the originators of CDMA) and may provide data speeds up to 2.4 Mbps, even better than the 2 Mbps speeds anticipated by W-CDMA. In some respects HDR may be superior to W-CDMA, the 3G version of CDMA being proposed by the ITU in its IMT-2000 initiative. Specifically, while W-CDMA is expected to provide 2 Mbps service only for stationary users, and much slower speeds for mobile and roaming users, HDR is intended to provide the same 2.4 Mbps speed for all users whether mobile or stationary. However, W-CDMA has the advantage of being a proposed standard for implementing compatible systems throughout the world. Only time will tell which system achieves market dominance.

For More Information

Visit the CDMA Development Group at *www.cdg.org.*

See Also: *3G, cellular communications, cdmaOne, Code Division Multiple Access (CDMA)*

cdmaOne

The commercial name for the Code Division Multiple Access (CDMA) cellular communications system used in North America and parts of Asia.

See: *Code Division Multiple Access (CDMA)*

CDN

Stands for content delivery network, a method for efficiently pushing out content over the Internet to users.

See: *content delivery network (CDN)*

CDO

Stands for Collaboration Data Objects, a collection of Component Object Model (COM) objects that allow developers to create Microsoft Internet Information Services (IIS) Web applications that send and receive electronic mail.

See: *Collaboration Data Objects (CDO)*

CDP

Stands for Content Delivery Provider, a company that builds and operates a content delivery network (CDN).

See: *content delivery network (CDN)*

CDPD

Stands for Cellular Digital Packet Data, a type of packet-switched data transmission network operating as an overlay for a cellular communications system.

See: *Cellular Digital Packet Data (CDPD)*

CD-ROM File System (CDFS)

A file system designed for read-only CD-ROM media.

Overview

CD-ROM File System (CDFS) is an International Organization for Standardization (ISO) standard (ISO 9660) for a read-only formatting standard for CD-ROM media. CDFS provides the same kind of file and directory management for CD-ROM devices that the file allocation table (FAT) and NTFS file systems (NTFS) do for hard disks.

CDFS is implemented on the Microsoft Windows 95, Windows 98, Windows Millennium Edition (Me), Windows NT, Windows 2000, Windows XP, and Windows .NET Server platforms. On 32-bit Windows systems, CDFS uses a 32-bit protected-mode driver that replaces the 16-bit real-mode Microsoft CD-ROM Extension (MSCDEX) driver that was used in the legacy 16-bit Windows and MS-DOS operating system platforms. In Windows 95 and Windows 98, the file system driver that supports CDFS is called Cdfs.vxd, and in Windows NT, Windows 2000, Windows XP, and Windows .NET Server, it is called Cdfs.sys.

CDFS is optimized for reading compact discs that have a standard data block size of 2048 bytes (2 KB). The Microsoft implementation of CDFS includes a dynamic, protected-mode cache pool for caching CD-ROM data to improve read performance. This allows CDFS to read ahead to ensure that playback of multimedia content from CDs is smooth and seamless. On Windows 95 OEM Service Release 2 (OSR2), Windows 98, Windows Me, Windows NT, Windows 2000, Windows XP, and Windows .NET Server platforms, CDFS includes a number of enhancements over the original version of CDFS for Windows 95, such as

- CD-XA support for optimized reading of Moving Picture Experts Group (MPEG) video CDs having larger block sizes of 2352 bytes.
- Auto-Run, which allows applications on CDs to start immediately when the CD is inserted into the drive. To do this, the operating system reads the Autorun.inf file that is stored in the root of the directory structure on the CD.

CDFS does have several limitations compared to disk file systems such as FAT and NTFS, namely:

- Names for files and directories can be no longer than 32 characters
- Directories can be nested only eight levels deep

CDFS is now considered a legacy format and is being replaced by the industry-standard Universal Disk Format (UDF), the new standard for read-only disk media.

Notes

Using Services for Macintosh, you can create an Apple Macintosh–accessible volume on a CDFS volume by following the same steps you would use to make an NTFS volume accessible to Macintosh clients. Of course, the CDFS volume has one difference: it is read-only.

See Also: *file system, Universal Disk Format (UDF)*

CDSL

Stands for Consumer DSL, a broadband transmission technology based on Digital Subscriber Line (DSL) technology.

See: *Consumer DSL (CDSL)*

cell (ATM)

A 53-byte packet of data, the standard packet size used by Asynchronous Transfer Mode (ATM) communication technologies.

Overview

Cells are to ATM technologies what frames are to Ethernet networking. In other words, they form the smallest element of data for transmission over the network.



Cell in ATM. *Details of an ATM cell.*

ATM cells are standardized at a fixed-length size of 53 bytes to enable faster switching than is possible on networks using variable-packet sizes (such as Ethernet). It is much easier to design a device to quickly switch a fixed-length packet than to design a device to switch a variable-length packet. (Switching a fixed-length packet is easier because the device knows in advance the packet's exact length and can anticipate the exact moment at which the last portion of the packet will be received. With variable-length packets, the device must examine each packet for length information.) Using fixed-length cells also makes it possible to control and allocate ATM bandwidth more effectively, making support for different quality of service (QoS) levels for ATM possible.

The functions of information stored in the 5-byte header of an ATM cell include the following:

- Providing information about the physical layer transmission method being used
- Providing flow control to enable a steady flow of cell traffic and to reduce cell jitter
- Specifying virtual path or channel identification numbers so that multiplexed cells belonging to the same ATM connection can be distinguished from cells belonging to other ATM connections and cells can be switched to their intended destination
- Specifying the nature of the payload contained in the cell—that is, whether it contains actual user data or ATM cell-management information
- Specifying the priority of the cell to determine whether the cell can be dropped in congested traffic conditions
- Providing error checking by means of an 8-bit field containing cyclical redundancy check (CRC) information for the header itself

Two kinds of header formats are used in ATM cells:

- **User-Network Interface (UNI) format:** Used for communication between end nodes and an ATM network

- **Network-Node Interface (NNI) format:** Used within the ATM network itself after the cell has been multiplexed for transmission over its virtual path

Notes

Why a 48-byte data payload for ATM cells? This is the result of a trade-off between larger 64-byte payloads that contain more data but take longer to package and unpackage— and are therefore not suitable for real-time transmissions such as voice or multimedia—and shorter 32-byte payloads that provide better real-time transmission but are inefficient for larger amounts of data. By compromising at a 48-byte payload size, ATM has good transmission capabilities for both voice and data communication, providing efficient packet transfer with low latency.

See Also: *Asynchronous Transfer Mode (ATM)*

cell (cellular communications)

In wireless communication technologies, the geographical region that is covered by a transmission facility.

Overview

The term **cell** is most often used in reference to cellular phone technology, but it can also be used in reference to the coverage areas for transmission of cordless telephones, satellite transmissions, wireless local area networks (LANs), packet radio, and paging technologies.

Cells range in size from a few dozen feet to thousands of miles in diameter, depending on the technology being used, the power of the transmission station, and the terrain topography. The following table summarizes typical cell size ranges for different wireless communication technologies. These figures are only approximate because wireless technologies are constantly evolving.

Satellite-based systems have by far the largest cell sizes and are rapidly increasing in popularity. Cellular phone technologies in rural areas typically use cells with a radius of 6 to 30 miles (10 to 50 kilometers), while cells in urban areas range in size from 0.6 to 6 miles (1 to 10 kilometers). For highly dense urban areas, cell sizes as small as 330 feet (100 meters) can be used, especially in high-tier Personal Communications Devices (PCD) cellular technologies.

Cell Radius Measures by Technology

Wireless Technology	*Cell Radius*
Wireless LANs	10 to 100 meters
Cellular telephone	0.1 to 50 kilometers
PCD	0.1 to 1 kilometer
Satellite-based	1000 kilometers or more

Notes

When a mobile caller using a cell phone passes from one cell to another, the cellular phone system transfers the call to the system servicing the adjacent cell, a process called roaming.

See Also: *cellular communications, wireless networking*

Cellular Digital Packet Data (CDPD)

A type of packet-switched data transmission network operating as an overlay for a cellular communications system.

Overview

Cellular Digital Packet Data (CDPD) is a specification for overlaying digital data transmissions on the existing circuit-switched Advanced Mobile Phone Service (AMPS) analog cellular phone service. CDPD was developed by IBM together with a consortium of Regional Bell Operating Companies and other organizations to leverage the existing installed base of AMPS cellular equipment in the United States to provide low-cost, packet-switched data services. CDPD was first offered in 1994 by Bell Atlantic Mobile.

Uses

CDPD is typically used to provide wireless access to public packet-switched networks such as the Internet so that mobile users can access their e-mail and other services. Multiple users can share the same channel; the user's modem determines which packets are destined for the user's machine. CDPD also supports IP multicasting and is an open standard based on the Open Systems Interconnection (OSI) reference model for networking.

Architecture

CDPD makes use of idle times between calls in cellular phone network channels for interleaving packets of digital data. In other words, CDPD makes use of the "bursty" nature of typical voice transmission on the AMPS cellular system. Voice communication has gaps or pauses where packet data can be inserted and transmitted without interfering with the communication taking place between customers.

CDPD uses the Reed-Solomon forward-error-correcting code to encode each block or burst of data sent, and includes built-in RC4 encryption to ensure security and privacy of the transmitted data. CDPD is also based on the industry standard Internet Protocol (IP), allowing data to be transmitted to and from the Internet.

Although CDPD supports data transmission rates of 19.2 kilobits per second (Kbps) and higher, actual data throughput is usually around 9.6 Kbps. This is because of the large overhead added by CDPD to each data block transmitted. This overhead is designed to ensure that communications are reliable and to maintain synchronization between the modems at each end of the transmission. In addition, a color code is added to every data block to detect interference resulting from transmissions on the same channel from neighboring cell sites.

Implementation

A typical implementation of CDPD consists of three components:

- **Mobile-End System (M-ES):** A user device such as a laptop equipped with a cellular modem. This system communicates in full-duplex mode with a Mobile Data Base Station (MDBS) using the Digital Sense Multiple Access protocol, which prevents collisions of data streams from multiple Mobile-End Systems.
- **Mobile Data Base Station (MDBS):** A telco device for receiving and transmitting CDPD data.
- **Mobile Data Intermediate System (MDIS):** Provides the central control for a CDPD network.

Marketplace

In the United States, the main providers of CDPD services are AT&T Wireless and Verizon Wireless. CDPD is also supported by several carriers in Canada and by AirData in New Zealand. CDPD is not widely deployed as a cellular data transmission technology, and coverage in the United States is spotty even in urban areas.

For More Information

You can find the CDPD Forum at *www.cdpd.org.*

See Also: *cellular communications, wireless networking*

cellular communications

A group of technologies that support roaming cell-based wireless communications.

Overview

Common to all forms of cellular communications is the concept of the cell. Instead of using one extremely powerful transmission to provide coverage for a geographical area (for example, a city, state, region, or country), the area is divided into a series of overlapping smaller areas called cells. Each cell has a relatively low-power base station that provides coverage for users within that cell, and when a user moves (roams) from one cell to another, the first base station seamlessly hands off servicing of the user to the second base station and the user experiences no interruption in communication.



Cellular communications. *How a cellular phone system works.*

Dividing the coverage area into many cells makes cellular communications systems more complicated than systems that use a single high-powered base station. Complex functions such as call setup and tear down, call authorization, call handoff, routing of call traffic, and call billing must operate seamlessly as users move between cells, and they require complex technology to implement. These functions are provided by connecting groups of base stations to a mobile switching center (MSC), which coordinates the activities of the base stations and connects them to the Public Switched Telephone Network (PSTN) so wireless users can call wireline users and vice versa.

Communications channels also need to be allocated to cells in such a way that no two adjacent cells use the same set of channels. This is necessary to ensure that signals from one base station do not interfere with those from base stations in adjacent cells. Repeating patterns of cells are used to optimize coverage of an area while maintaining the maximum number of available channels per cell. For example, in a typical cellular system, if you travel in a straight line every third cell utilizes the same set of frequencies.

Cells can also vary considerably in size. Because each cell can only support a certain number of users, cells in dense urban areas are much smaller than those in sparsely inhabited rural areas, and when population increases cells may need to be split to continue to provide adequate coverage. All this makes cellular communications complicated to implement, which explains why the technology took so many years to be widely deployed after the it was first conceived. The main advantage of such systems, however, is that, because cells are relatively small, the mobile client (cell phone or other device) does not need to be very powerful, which saves considerably on the size and the cost of the phone and has helped propel the widespread use and popularity of these systems.

History

The concept of a cellular phone system originated in 1947 at AT&T Bell Laboratories. AT&T first proposed a commercial cellular system to the Federal Communications Commission (FCC) in the late 1960s, and the FCC allocated the necessary frequency spectrum in 1974. A demonstration system was tested in Chicago in 1978, but the first actual cellular system was deployed in Japan in 1979 by the Nippon Telephone and Telegraph Company. This was followed by Europe in 1981, and finally in 1983 AT&T began deploying Advanced Mobile Phone Service (AMPS), the first nationwide cellular system in the United States.

AMPS was a first-generation (1G) analog cellular phone system that used frequency modulation for voice transmission and frequency-shift keying (FSK) for transmission of signaling information. AMPS uses channels within the 800 megahertz (MHz) frequency band of the electromagnetic spectrum, and channel access is provided by using Frequency Division Multiple Access (FDMA) as the media access method. AMPS achieved widespread implementation across the United States in the 1980s and is still widely used.

Another wave of cellular communications systems was developed in the 1990s and is still widely deployed. These second-generation (2G) systems differ from AMPS in being digital rather than analog in nature, and they can support not just voice but also data transmission, typically at 9.6 to 19.2 kilobits per second (Kbps). Several competing digital cellular systems have evolved and have become widely deployed:

- **Time Division Multiple Access (TDMA):** The main TDMA system deployed in the United States is AT&T Wireless Services, a subsidiary of AT&T. This TDMA system operates in the same 800 MHz frequency band as AMPS and is sometimes referred to as either Digital AMPS (D-AMPS) or North American TDMA (NA-TDMA).
- **Code Division Multiple Access (CDMA):** CDMA was developed by QUALCOMM, and its cdmaOne system is the most popular digital cellular system in North America. Other CDMA carriers include Bell Mobility, Sprint Corporation, and Verizon Communications. CDMA is more complex than TDMA, but it is more efficient in its utilization of the frequency spectrum.
- **Global System for Mobile Communications (GSM):** This system is based on TDMA and is the most popular digital cellular phone technology in Europe and much of Asia. GSM can operate in the 900, 1800, or 1900 MHz frequency bands. There are only a few GSM carriers in the United States, and they cover only a small portion of the market. An example is VoiceStream Wireless Corporation.
- **Personal Communications Services (PCS):** These systems can be TDMA-based or CDMA-based and operate in the higher 1900 MHz frequency band using smaller cell sizes than 800 MHz cellular systems. Sprint PCS, for example, is based on CDMA technology.

Issues

A major concern that has been receiving media attention lately is the safety of using cellular phones. While most agree that using a cellular phone while driving can increase the chances of an accident (and some civic and municipal governing bodies have passed laws regulating use of cellular phones while driving), scientists continue to debate whether other health hazards might be associated with the long-term use of cell phones. A particular concern is the possible link between cell phone use and brain cancer, particularly among children whose brains are still forming. Cell phones transmit microwave energy through their antennas, and microwaves have a known heating effect (think of a microwave oven, for example). When a cell phone is held next to the ear, some of the microwave energy penetrates into the brain, and while the FCC has mandated emission standards for cellular phones to keep these emissions below dangerous levels, some researchers believe that long-term exposure to even low-level microwave radiation may be harmful to the brain and other organs, particularly in children. On the other hand, many researchers believe that there is no conclusive link between brain cancer and cell-phone use, and in general such associations between cancer and environment factors are difficult to prove (consider how long it took to resolve the controversy over whether cigarettes caused lung cancer). The American Medical Association and other bodies continue to call for further study of these issues, but it will likely take years for studies to produce any significant results. Some governing bodies are already taking steps, however, such as the United Kingdom, which has mandated that mobile telephone handsets must now come with leaflets warning of potential health risks to children who use these devices over a prolonged period.

Impact

Cellular communications have revolutionized business and personal communications worldwide. About one-third of Americans now own cell phones, and this is growing at an annual rate of 25 percent. Use of cell phones in Europe and Asia is even higher on a percentage basis, and some analysts predict that by 2005 there will be more than 1.25 billion cell phones and other cellular communications devices used around the world.

Cell phones have helped catalyze the e-business revolution by providing employees with 24x7 connectivity with the office—something desirable from a management point of view but debatable in terms of the quality of life for workers. Using data-enabled cell phones and wireless Personal Digital Assistants (PDAs), workers can perform tasks such as sending and receiving e-mail, checking inventory and ordering products, reboot servers, and perform other essential tasks to keep an e-business operating. Nonbusiness uses of data-enabled cell phones including browsing the Web, checking weather reports, downloading news headlines, confirming airline reservations, checking stock quotations, and many other uses. Although many of these uses are exciting, most data operations are still tedious over slow 2G cellular systems, and the real promise of cellular Internet access will not be realized until 3G comes into full operation in the latter part of this decade.

Prospects

The current 2G cellular systems will be replaced over the next few years by broadband cellular systems that support much higher rates of data transmission than can now be achieved. Proposed 3G systems will support data transmission as fast as 2 megabits per second (Mbps) and include

- **Wideband CDMA (W-CDMA):** This system has the support of the International Telecommunication Union (ITU) as the upgrade for TDMA-based systems such as GSM, offers data rates of up to 2 Mbps, and is expected to become widely deployed in Europe and Asia.
- **CDMA2000:** This system has been proposed by QUALCOMM as the upgrade for CDMA systems, has the support of the ITU as an alternative to W-CDMA, offers data rates of up to 2 Mbps, and is expected to become widely deployed in North America.
- **Enhanced Data rates for Global Evolution (EDGE):** This system is a proposed upgrade by AT&T for its North American TDMA system but offers data rates of only 384 Kbps.

Because 3G technologies are not expected to be deployed until 2003 (or more likely 2005), some carriers are implementing interim 2.5G systems to provide increased data rates over 2G until 3G becomes a reality. Some 2.5G systems starting to be deployed include

- **CDMA2000 1X:** This system developed by QUALCOMM supports data transmission at 307 Kbps, and is an interim step toward the 3G version CDMA2000 (sometimes called CDMA2000 2X).
- **General Packet Radio Service (GPRS):** This system upgrades AT&T's existing TDMA system to support data rates of 115 Kbps and is an interim step toward EDGE.

For More Information

For the latest news about the cellular industry, visit the Cellular Telecommunications & Internet Association's (CTIA) World of Wireless at *www.wow-com.com.*

See Also: *2G, 2.5G, 3G, broadband wireless communications, CDMA2000, Code Division Multiple Access (CDMA), Enhanced Data Rates for Global Evolution (EDGE), General Packet Radio Service (GPRS), Global System for Mobile Communications (GSM), Personal Communications Services (PCS), Time Division Multiple Access (TDMA), wireless networking*

central office (CO)

A telco switching facility.

Overview

The central office (CO) provides access to the Plain Old Telephone Service (POTS), leased lines, and other services that a telco offers its customers in a given geographical area (usually a dozen square miles or so).

The CO contains the Class 5 switching equipment that connects telephone subscribers to both local and long-distance phone services. A telco typically has one CO servicing several dozen square miles in urban areas, so in large cities there may be many COs for each telco.

A typical CO may look like a fortress built to withstand an earthquake or any other natural disaster. Building standards for COs are high because of the importance of the communications infrastructure to a nation's economic health and safety. Banks of batteries and diesel generators provide backup power in case of blackouts so that phone communication will not be disrupted.

Multitudes of twisted-pair copper telephone lines from customer premises usually enter the building through the underground cable vault. These twisted-pair lines are grouped into bundles of thousands of lines, forming large cables 3 to 4 inches (7.5 to 10 centimeters) in diameter. The cables have grounding mesh to provide a drain for unwanted electrical surges and tough polyvinyl chloride (PVC) insulating jackets that are pressurized to prevent water from seeping in at cable junctions. Steel racks organize these cables as they enter the cable vault.

From the vault, the cables snake their way to the main cross-connect grid. It is in these steel-frame grids that all the individual twisted-pairs fan out and connect through feeders to the main switching equipment. The importance of the feeders is that they allow any incoming twisted-pair line to connect to virtually any switching bank. This makes it possible for customers to move to a different part of the city and maintain their old telephone number at their new location. It also allows for redundancy: if a switch fails, a CO technician can rewire the feeder blocks quickly and easily. The main switches are then used to route calls to other local subscribers or to a long-distance telecommunications carrier such as AT&T or MCI WorldCom. In the United States, these Class 5 telephone switches are usually Basic-5ESS switches, also called AT&T basic rate switches.

Subscribers are connected to their local CO through a segment of wiring called the local loop. This wiring is typically copper, but telcos lay fiber to the building for customers requiring high-speed services not supported by copper lines.

Finally, a telco may have dozens of COs in a dense urban area, all interconnected using cross-links and redundant switches. Each CO services subscribers within a specific geographical area and manages voice and data traffic in that area. When a call is made from a customer over the local loop to the CO, the call is either switched to another circuit within the same exchange (for local calls) or switched to a trunk line joining the CO to a CO belonging to a different company, typically a long-haul carrier such as Sprint or AT&T. For business customers needing multiple telephone lines at their location, the carrier typically deploys a private branch exchange (PBX) at the customer premises.

Notes

Not all of a telco's switching and telecommunications equipment is located at a central office. There are recent trends where telcos have pushed out their ATM switching gear to within 500 feet (150 meters) of residential neighborhoods in pursuit of better-quality Digital Subscriber Line (DSL) connections. These remote stations shorten the copper DSL connections between customer premises and the provider's switching gear, and the remote Asynchronous Transfer Mode (ATM) concentrators are then connected to the COs using fiber.

In countries and regions other than the United States, a CO is often referred to as a public exchange.

See Also: *telco*

Centrex

An acronym for **Centr**al Office **Ex**change Service, a business telephone service provided by telcos.

Overview

By using a Centrex instead of a Private Branch Exchange (PBX), a business can eliminate the necessity of having its own dedicated switching facilities at its customer premises. Centrex also eliminates the need for customers to upgrade to expensive new telephones because existing telephone lines and touch tone phones can be used with it. This frees the customer from the need to invest in the cost and management of customer premises equipment (CPE).

Centrex services partition the switching capabilities of the telco's central office (CO) equipment and allow a portion of these capabilities to be dedicated to a particular customer. In essence, the business customer is leasing dedicated switching facilities at the CO to enable a large number of employee telephones to be routed through a few telephone lines. All routing of calls to individual employee telephones takes place using the Centrex. Configuration changes can be performed at the CO instead of requiring technicians to visit the customer premises. This can save the cost of installing a local PBX at the customer premises.

Centrex can handle advanced communication features such as internal call handling, inbound and outbound call handling, and multiparty calling. Each individual connected can have customized calling features just as they can with a PBX. Maintenance is entirely the responsibility of the telco central office, which provides around-the-clock support.

Notes

Some carriers such as Pacific Bell Telephone Company also offer Integrated Services Digital Network (ISDN) as a Centrex service in addition to standard business ISDN lines.

See Also: *central office (CO), Private Branch Exchange (PBX), telco*

certificate

Also called digital certificate, a technology for verifying the identity of the user or service you are communicating with.

See: *digital certificate*

certificate authority (CA)

Any entity (individual, department, company, or organization) that issues digital certificates to verify the identity of users, applications, or organizations.

Overview

Before issuing a digital certificate to someone, the certificate authority (CA) must verify the user's identity according to a strictly established policy, which can involve face-to-face communication, examination of a driver's license with photograph, or another method of establishing a user's identity. When the user's identity has been verified, the certificate is issued to the user. This certificate can then be presented by the user as a "digital driver's license" to identify himself or herself during network transactions.

CAs can be trusted third parties such as the private companies VeriSign, CyberTrust, and Nortel Networks; or they can be established within your own organization using Microsoft Certificate Server. CAs can be standalone authorities with their own self-signed certificates (that is, they validate their own identity as a root CA), or they can be part of a hierarchy in which each CA is certified by the trusted CA above it (up to a root CA, which must always be self-certified).

For digital certificates to work as an identification scheme, both client and server programs must trust the CA. In other words, when a client program presents a certificate to a server program, the server program must be able to validate that the certificate was issued by a valid and trusted CA. Certificate authorities also maintain a certificate revocation list (CRL) of revoked certificates. Certificates issued by CAs expire after a specified period of time.

CAs are necessary for the functioning of a public key infrastructure (PKI), which is essential to the widespread acceptance and success of any public key cryptography system. Microsoft Windows 2000 and Windows .NET Server can use standard X.509 digital certificates to authenticate connections across unsecured networks such as the Internet and to provide single sign-on using smart card authentication systems.

For More Information

Visit VeriSign, Inc. at *www.verisign.com.*

See Also: *digital certificate, public key infrastructure (PKI)*

certificate mapping

A feature of Microsoft Internet Information Server (IIS) version 4 and Internet Information Services (IIS) version 5 (for Windows 2000) and later that allows mapping between user accounts and digital certificates.

Overview

Certificate mapping is useful when an organization issues client certificates to users. Client certificates are digital certificates that verify the identity of client software (Web browsers) belonging to users. Client certificates are often used in situations in which mobile clients using laptops require secure access to a corporate intranet site.

Before users can be granted remote access to the corporate intranet, they must be authenticated by the Web server they are connecting to. IIS supports four kinds of Web authentication mechanisms:

- **Anonymous access:** Allows anonymous users access to Web sites—such as public sites on the Internet.
- **Basic authentication:** Passes a user's credentials over the network as clear text. Although this mechanism is not very secure, it has the advantage of being able to work through a firewall or a proxy server.
- **Microsoft Windows NT Challenge/Response Authentication** (called Integrated Windows Authentication in Windows 2000): A secure authentication method that does not actually pass the user's credentials over the network but uses a cryptographic exchange instead. The only Web browser that supports this authentication method is Microsoft Internet Explorer. This method cannot work through a firewall or a proxy server.
- **Certificate mapping:** Uses the Secure Sockets Layer (SSL) protocol to authenticate users by examining the contents of their client certificate in order to log them on to the network without requiring them to enter their credentials.

Client certificates provide verification of identity, but certificate mapping associates a user's account with the user's client certificate and permits the user to log on to the network. The user typically utilizes a Web browser with SSL protocol to connect to a secure company Web site. The company Web server checks the Web browser's client certificate. If the certificate is valid, the user is automatically logged on using his or her user account without ever having to enter credentials and can access whatever intranet resources for which the account has permissions.

IIS allows two kinds of client certificate mappings:

- One-to-one mappings between user accounts and client certificates on the user's browser. This type of mapping is typically used to allow users secure access to corporate intranet resources—for example, to view or modify their employee information.
- Many-to-one mappings can map several client certificates to a single user account. Many-to-one mappings have the advantage of permitting administrators to allow multiple certificates to be used to grant users access to the corporate intranet utilizing a single Windows account. For example, you can set a rule that maps all certificates issued by the CA of an agency that provides your company with temps to a single Windows account.

Notes

Certificate mapping is also supported by Active Directory directory service in Microsoft Windows 2000, Windows XP, and Windows .NET Server operating systems. You can use the Active Directory Users and Computers administrative tool for this purpose.

See Also: *digital certificate*

certificate request

A file containing an entity's identification information and public key that is submitted to a certificate authority (CA) in order to obtain a digital certificate.

Overview

A certificate request is a text file encoded using Base64 encoding. This text file is generated by an application in response to the entity's request for a key pair and digital certificate. The entity here refers to the individual, system, company, or organization requesting the certificate. The certificate request is then submitted to a CA to obtain a digital certificate for the entity.

The Key Manager utility in Internet Services Manager (the utility used to manage Microsoft Internet Information Services) can be used to generate a key pair and a standard public key cryptography standards (PKCS) #10 format certificate request file. The certificate request file is a simple text file that can be viewed with Microsoft Notepad. If this file is submitted to a public certificate authority, such as VeriSign, or to the company's own certificate authority, such as Microsoft Certificate Server, a standard X.509 format digital certificate will be granted in return.

See Also: *digital certificate, public key infrastructure (PKI)*

certificate revocation list (CRL)

A list, maintained by a certificate authority (CA), of digital certificates that have been issued and later revoked.

Overview

A certificate revocation list (CRL) is similar to lists of revoked credit card numbers that credit card companies used to give to vendors. The certificate authority makes the CRL publicly available so that users can determine the validity of any digital certificate presented to them.

Creating and maintaining a CRL is an essential ingredient in running a public key infrastructure (PKI) to support public key cryptography systems. Microsoft Certificate Server includes a Web-based utility called the Certificate Administration Log Utility that can be used to revoke certificates and maintain a CRL.

See Also: *digital certificate, public key infrastructure (PKI)*

Certified Technical Education Center (CTEC)

An education-delivery company, such as a school or training center, that is qualified by Microsoft Corporation for the delivery of Microsoft Official Curriculum (MOC) courseware.

Overview

Certified Technical Education Centers (CTECs) are one of Microsoft's main channels for training on Microsoft products and technologies. CTECs can deliver training in a variety of forms, including instructor-led, self-paced, customized, and online training. CTECs are one of the ways that Microsoft contributes to solutions addressing the shortage of skilled IT professionals worldwide.

Network professionals who want to become familiar with Microsoft operating systems, applications, and development platforms can take MOC courses offered by CTECs at various locations around the world. Microsoft CTECs are also a source for the best in self-paced training materials on Microsoft products and services.

For More Information

Visit the Microsoft CTEC site at *www.microsoft.com/ctec.*

See Also: *Authorized Academic Training Provider (AATP)*

CGI

Stands for Common Gateway Interface, a mechanism by which a Web browser can request a Web server to execute an application.

See: *Common Gateway Interface (CGI)*

Challenge Handshake Authentication Protocol (CHAP)

A standard form of challenge/response authentication protocol.

Overview

Challenge Handshake Authentication Protocol (CHAP) is a standard authentication protocol defined in RFC 1994. CHAP is one of several authentication schemes used by the Point-to-Point Protocol (PPP), a serial transmission protocol for wide area network (WAN) connections. Other authentication schemes supported by PPP include Password Authentication Protocol (PAP), Shiva Password Authentication Protocol (SPAP), and

Microsoft Challenge Handshake Authentication Protocol (MS-CHAP). PAP is a widely implemented authentication protocol, but CHAP is more secure than PAP because CHAP encrypts the transmitted password and PAP does not. SPAP and MS-CHAP are vendor-specific implementations.

CHAP is an encrypted authentication scheme in which the unencrypted password is not transmitted over the network. A typical CHAP session during the PPP authentication process works something like this:

- The client connects to a network access server (NAS) and requests authentication.
- The server challenges the client by sending a session ID and an arbitrary string.
- The client uses the MD5 one-way hashing algorithm and sends the server the username, along with an encrypted form of the server's challenge, session ID, and client password.
- A session is established between the client and the server.

To guard against replay attacks, the challenge string is chosen arbitrarily for each authentication attempt. To protect against remote client impersonation, CHAP sends repeated, random interval challenges to the client to maintain the session.

Notes

CHAP is supported by the Routing and Remote Access (RRAS) service of Windows 2000 and Windows .NET Server as a way to allow non-Microsoft clients to dial in and receive authentication for a Remote Access Server (RAS) session, and to allow Microsoft RAS clients to connect to any industry-standard PPP server.

With Cisco routers, CHAP repeatedly challenges the connecting host every two minutes after the connection is established. This helps to prevent session hijacking by hackers on the network.

See Also: *authentication provider, challenge/response, Microsoft Challenge Handshake Authentication Protocol (MS-CHAP), Password Authentication Protocol (PAP), Point-to-Point Protocol (PPP)*

challenge/response

A mechanism for securely authenticating users over a network.

Overview

Challenge/response provides a way of employing user credentials to negotiate a connection over a network without actually passing these credentials over the network. Challenge/response forms the basis of the Integrated Windows authentication method supported by Internet Information Services (IIS) on Microsoft Windows 2000, Windows XP, and Windows .NET Server (Integrated Windows authentication was previously called Windows NT Challenge/Response authentication in Internet Information Server [IIS] on Windows NT).

Implementation

The basic steps of challenge/response are straightforward and independent of the actual platform they are implemented on. Here are the steps in a typical challenge/response authentication session:

- The client contacts the server to access a resource on the server.
- The server requests the client to authenticate itself and sends the "challenge," a randomly generated string, to the client.
- The client hashes the challenge string together with the client's password using a predetermined hashing algorithm. The result of this hash is called the "response."
- The client sends the response to the server, together with the client's name.
- The server meanwhile has performed the identical hashing operation as the client has, using the client's credentials, which are securely stored ahead of time in the server's security database.
- When the server receives the client's hash, it compares this with its own hash. If the hashes are identical, the client's identity is authenticated and the client is allowed to access the desired resource.

See Also: *authentication protocol, hashing algorithm, Integrated Windows Authentication*

Change and Configuration Management

A set of features in Microsoft Windows 2000, Windows XP, and Windows .NET Server for managing user settings and installing applications.

Overview

Change and Configuration Management is included in Windows 2000, Windows XP, and Windows .NET Server to provide support for tasks such as

- Installing initial operating systems on new computers
- Managing deployment of software on computers
- Managing user desktop configuration settings and user personal folders

Change and Configuration Management is an umbrella term for two underlying Microsoft technologies that make these things possible. These two technologies are

- **Intellimirror:** Enables management of user preferences, user documents, and software installation and maintenance.
- **Remote Operating System (OS) Installation:** Uses Remote Installation Services (RIS) to install Windows 2000, Windows XP, and Windows .NET Server on remote machines.

See Also: *IntelliMirror*

channel (Active Channel)

The delivery method in Active Channel, a technology for Microsoft Internet Explorer that allows Web content to be "webcast" to users.

Overview

Channels deliver content to users' Web browsers. The content is displayed as ordinary Web pages and can be viewed off line. Channels are delivered to users by way of Microsoft Corporation's Channel Definition Format (CDF) technology. Channels can contain Hypertext Markup Language (HTML); Microsoft ActiveX controls; Microsoft Visual Basic, Scripting Edition (VBScript); Java applets; and other dynamic Web elements. The channels that a user has subscribed to are listed as part of his or her channel bar.

See Also: *Channel Definition Format (CDF)*

channel bank

A telecommunications device that consolidates multiple Digital Signal Zero (DS0) channels into a larger single digital transmission.

Overview

Channel banks usually combine 24 different voice and data 64 kilobits per second (Kbps) DS0 channels into a single 1.544 megabits per second (Mbps) DS1 channel, though some channel banks are capable of combining up to 96 DS0 channels into a 6.312 Mbps DS2 channel. The channel bank combines the individual DS0 signals using a technique called multiplexing, which allows multiple signals to be combined for transmission over a single line. The resulting multiplexed digital signal can then be sent over a T1 line to the telco.

A channel bank interfaces with the wires of the local loop connection that carry the phone signals from the customer premises to the telco's central office (CO). In a typical business scenario, the channel bank would be connected to the front end of an analog Private Branch Exchange (PBX) to support multiple telephones within the company. The channel bank also includes circuits for converting the analog voice signals into digital data signals, usually using pulse code modulation (PCM). The resulting modulated digital signal conforms to the standard 64-Kbps DS0 format. The digital signals can then be routed through the digital switching backbone of the Public Switched Telephone Network (PSTN) as necessary.

Channel banks are typically located at the telco's CO and support the digital switching functions of the PSTN. However, channel bank equipment can also be installed at customer premises for larger enterprises.

Notes

Channel banks are becoming obsolete as older analog PBXs are being replaced by digital PBXs. When a digital PBX is used, the PBX can be connected directly to the T1 line using a Channel Service Unit (CSU), making a channel bank unnecessary.

See Also: *Channel Service Unit (CSU), DS-0, multiplexer (MUX), Private Branch Exchange (PBX), pulse code modulation (PCM), T1*

channel bar

A component of Microsoft Internet Explorer version 4 and later that displays the available user-subscribed Active Channels.

Overview

Active Channels provide a way of webcasting information to subscribers using Microsoft Corporation's Channel Definition Format (CDF) technology. When Internet Explorer is first installed on a user's machine, a selection of preloaded channels is stored in the channel bar according to the country or region preference the user specified during installation. These channels are stored by default in C:\Windows\Favorites\Channels on a computer running Microsoft Windows 95 or Windows 98 and in C:\Winnt\Profiles\<user>\Favorites\Channels on a computer running Windows NT, Windows 2000, Windows XP, or Windows .NET Server. When a user subscribes to a channel, a small red gleam appears next to the icon representing the channel. This gleam indicates that new content has been downloaded and is available for browsing.

Notes

Administrators who plan to deliver and install Internet Explorer on users' machines can use the Internet Explorer Administration Kit (IEAK) to customize the users' set of startup channels. Administrators can thus use the channel bar to deliver important information to users through the company's intranet site.

See Also: *Channel Definition Format (CDF)*

Channel Definition Format (CDF)

An open standard created by Microsoft Corporation for Microsoft Internet Explorer version 4 (and proposed as a standard to the World Wide Web Consortium [W3C]) that defines a "smart pull" technology for webcasting information to users' desktops.

Overview

Based on the Extensible Markup Language (XML), Channel Definition Format (CDF) lets administrators create Active Channels for delivery of content through the user's Web browser and Active Desktop elements and channel screen savers for delivery directly to the user's desktop. Channel content can be personalized, and delivery can be scheduled according to users' needs and preferences. Using CDF also reduces server load and allows delivery of just the needed content, instead of requiring users to download large quantities of unnecessary content.

Consider the delivery of Web content to the user's browser using Active Channels. A Web site can be made into an Active Channel through the addition of a CDF file, a simple text file formatted using XML. It forms a kind of table of contents of the logical subset of the Web site that comprises the Active Channel. A link is then created to the CDF file on the Web site. The user clicks the link to subscribe to the Active Channel and download the CDF file. The Active Channel then appears on the channel bar on the user's desktop. The content for the channel is downloaded to a cache on the user's system. Channel updates are accomplished by scheduled Web crawls, using either the publisher's predefined schedule or a user's customized one. Users can also receive updates to channels by e-mail.

Some of the advantages of using CDF for the distribution of Web information to users include

- **Simplicity:** Turning an existing Web site into a channel merely involves creating a CDF file with a text editor and creating a hyperlink to this file.
- **Structure:** CDF describes how to logically group information in a hierarchical structure, independent of the content format.
- **Personalization:** Standard Hypertext Transfer Protocol (HTTP) cookies can be used to deliver personalized information to users.
- **Administrator control:** The administrator can control how much of the site can be downloaded by users.

- **User control:** The user can use CDF to specify which portions of a site to download to his or her browser, instead of pulling a lot of content off the site and hoping that it contains the needed information.

Notes

CDF is not true webcasting in the sense of Internet Protocol (IP) multicasting because it is a "pull" technology. True webcasting is supported by Microsoft Windows Media Player for delivery of content using IP multicasting.

channel (Microsoft Windows Media Player)

In Microsoft Windows Media Player, a mechanism that supplies clients with information needed to receive and render Advanced Streaming Format (ASF) streams.

Overview

A Windows Media Player channel specifies the multicast address and port number the clients should listen to in order to receive the stream. The channel also specifies the data types and formats in the stream, enabling the client to correctly render the stream. Windows Media Player saves channel information as files with the extension .nsc. A Windows Media Player channel is analogous to a television channel or a radio frequency: if a Windows Media Player client is tuned to a channel at the right time, the client receives streaming information sent by the Windows Media Player server.

Windows Media Player channels also support additional features, such as

- **Roll over to unicast:** If clients cannot receive a multicast, you can configure the channel so that they automatically receive a unicast of the same program.
- **Stream distribution:** On corporate Transmission Control Protocol/Internet Protocol (TCP/IP) networks whose routers do not support multicasting, one Windows Media Player server can distribute a stream to other Windows Media Player servers that are each located on separate local area network (LAN) segments. These secondary servers can then multicast to clients on their own LAN segment.

Channel Service Unit (CSU)

A device that is used to connect a synchronous digital telecommunications line to a computer network.

Overview

Channel Service Units (CSUs) are used to link local area networks (LANs) into a wide area network (WAN) using telecommunications carrier services such as Digital Data Services (DDS), T-carrier services such as a T1 line, and frame relay links.

The function of a CSU is to terminate the carrier's digital line at the customer premises. It also provides signal amplification and allows the carrier to perform remote loopback testing to monitor and troubleshoot the integrity of the line. Some CSUs also support Simple Network Management Protocol (SNMP) features that allow the unit to be monitored by the service provider.



Channel Service Unit (CSU). *Using a CSU in a WAN link.*

CSUs are always used together with Data Service Units (DSUs), which convert signals from data terminal equipment (DTE) such as a router, switch, multiplexer (MUX), or dedicated server on the LAN to a signaling format suitable for transmission over the line.

Implementation

The service provider interface of the CSU terminates at the telco's digital line where it enters the customer premises. The other interface of the CSU then connects to a DSU, and then the DSU connects with data terminal equipment (DTE) on the LAN (a router, switch, or other LAN device). The DTE is typically an RS-232 or a V.35 serial transmission interface.

Typically, the telecommunications service provider will lease the CSU to the customer, having preconfigured it for the type of digital line to be supported. CSUs usually come in a dual Channel Service Unit/Data Service Unit (CSU/DSU) package that drops into the edge of the network to provide WAN link connectivity. Dedicated stand-alone CSUs are typically used only for interfacing with installed customer premises telecommunications equipment that contains integrated DSUs. This installed equipment could be a channel bank, Private Branch Exchange (PBX), T1 multiplexer, or some other device. Some access routers have built-in CSU/DSUs as well.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), Data Service Unit (DSU)*

Channel Service Unit/Data Service Unit (CSU/DSU)

A device that combines the functions of both a Channel Service Unit (CSU) and a Data Service Unit (DSU).

Overview

Channel Service Unit/Data Service Units (CSU/DSUs) are placed between the telephone company network and the customer network at the demarcation point and are the local interfaces between the data terminal equipment (DTE) at the customer premises and the telco's digital communications line (such as a T1 line).

CSU/DSUs package digital data into a format suitable for the particular digital transmission line they are servicing and buffer and rate-adapt digital signals going to and from the telephone company network. CSU/DSUs ensure that data frames are properly formed and timed for the telephone company network and provide a protective barrier to electrical disturbances that can harm customer premises equipment (CPE).



Channel Service Unit/Data Service Unit (CSU/DSU). *Using a CSU/DSU to connect two local area networks (LANs) over a wide area network (WAN) link*

Implementation

CSU/DSUs essentially function as the digital counterpart to analog modems. They are typically external units that look similar to an external modem, but they can also come in sizes that can be mounted in a rack. Unlike analog modems, CSU/DSUs do not perform signal conversion because the signal at both ends is already digital.

Digital lines usually terminate at customer premises with four-wire connections having various connector types, including RJ-45, four-screw terminal blocks, and M-block connectors (used for V.35 interfaces). The four-wire connection is joined to the appropriate connector on the CSU/DSU. The CSU/DSU typically adjusts itself to the line speed of the digital data service (DDS) line using an autosensing feature. The customer's CSU/DSU then connects directly to the customer's router and from there connects to the customer's network.

At the other end of the DDS line at the central office (CO), the telco has a similar CSU that interfaces with a multiplexer to feed into the carrier's backbone network.

Notes

When purchasing CSU/DSUs, consider first the traffic requirements of your wide area network (WAN) link and make sure they support the full range of data rates for the DDS lines you plan to use (56 K, 64 K, or T1 speed).

See Also: *Channel Service Unit (CSU), Data Service Unit (DSU)*

CHAP

Stands for Challenge Handshake Authentication Protocol, a standard form of challenge/response authentication protocol.

See: *Challenge Handshake Authentication Protocol (CHAP)*

child domain

A domain in a Microsoft Windows 2000 or Windows .NET Server domain tree whose Domain Name System (DNS) name is a subdomain of the parent domain.

Overview

As an example, if the name of the parent or company domain is microsoft.com, some typical names of child domains might include dev.microsoft.com, marketing.microsoft.com, and support.microsoft.com.

You can create new child domains using the Active Directory Installation Wizard. You must create a child domain in an existing domain tree, because creating a new tree automatically creates a new parent domain. A two-way transitive trust exists between a parent domain and its child domains.

See Also: *Active Directory, domain tree*

CICS

Stands for Customer Information Control System, the multipurpose transaction monitor for IBM mainframe computing environments.

See: *Customer Information Control System (CICS)*

CIDR

Stands for classless interdomain routing, an alternative way of classifying Internet Protocol (IP) addresses from the traditional class A-E system. Also called supernetting.

See: *classless interdomain routing (CIDR)*

CIFS

Stands for Common Internet File System, a public version of the Server Message Block (SMB) file-sharing protocol that has been tuned for use over the Internet.

See: *Common Internet File System (CIFS)*

CIM

Stands for Common Information Model, a schema for defining manageable network objects.

See: *Common Information Model (CIM)*

CIM Object Manager (CIMOM)

Part of the Microsoft Windows Management Information (WMI) architecture.

Overview

CIM Object Manager (CIMOM) functions as a broker for object requests within the WMI architecture. CIMOM supplies the required interfaces between management applications (WMI consumers) and a managed physical or logical network object (WMI providers).

CIMOM abstracts management information from a variety of different providers, including the Win32 programming interfaces for Windows applications and the Simple Network Management Protocol (SNMP) for managed network devices. CIMOM then employs the WMI application programming interface (API) to present the gathered information in a consistent fashion to the network management application.

A network management application can register with CIMOM in order to receive notifications when specific network events occur, such as a full disk or a saturated network path. If such a condition arises, the WMI provider for the managed device or application sends a notification to CIMOM, which notifies the registered management application of the condition.

See Also: *Common Information Model (CIM), Windows Management Instrumentation (WMI)*

CIMOM

Stands for CIM Object Manager, part of the Microsoft Windows Management Information (WMI) architecture.

See: *CIM Object Manager (CIMOM)*

CIP

Stands for Classical IP, a method for running Internet Protocol (IP) packets over Asynchronous Transfer Mode (ATM) networks.

See: *Classical IP (CIP)*

CIR

Stands for Committed Information Rate, a way of guaranteeing bandwidth in frame relay services.

See: *Committed Information Rate (CIR)*

circuit

A path between two points over which an electrical signal can pass.

Overview

In telecommunications, a circuit is a path over which voice, data, or other analog or digital signals can pass. A physical circuit is a collection of wires or cables that are connected with switches or other devices; it can be thought of as a straight line between the two endpoints.



Circuit. *Two basic types of circuits.*

For an electrical signal to actually flow between two points in a circuit, the circuit must be closed—that is, there must be a return path for the current. Two basic types of circuits are used in serial transmission for telecommunications technologies:

- Balanced circuits, such as those based on the RS-422 interface, use a separate signal path and return path, with two separate wires.
- Unbalanced circuits, such as those based on the RS-232 interface, use a single signal path, adding ground to complete the circuit.

Balanced circuits typically support higher data transmission rates because the are less susceptible to noise caused by electromagnetic interference (EMI) than unbalanced circuits.

Notes

A typical serial interface such as RS-232 includes specifications for a number of different types of circuits, including data circuits, control circuits, timing circuits, secondary circuits, and ground connections.

See Also: *circuit-switched services, virtual circuit*

circuit layer proxy

Any service or server that provides proxy services using a specially installed component on the client computer to form a circuit between the proxy server and the client computer.

Overview

Microsoft Proxy Server is a product that combines firewall and proxy server functions and has two services for providing circuit-level proxy functions:

- **Winsock Proxy Service:** This enables Microsoft Windows Sockets clients such as Microsoft Windows Media Player, RealAudio, and Internet Relay Chat (IRC) to function as if they are directly connected to the Internet. The Winsock Proxy Service provides Windows NT Challenge/Response Authentication with clients, regardless of whether the clients support it, and supports Windows Sockets version 1.1–compatible applications on computers running Windows. The Winsock Proxy Service can control access by port number, protocol, and user or group. Ports can be enabled or disabled for specific users or groups, and the list of users that can initiate outbound connections on a given port can differ from the list of users that can listen for inbound connections on that port.
- **SOCKS Proxy Service:** This includes support for the SOCKS 4.3a protocol. The SOCKS Proxy Service provides support for Macintosh-based and UNIX-based client computers, while the Winsock Proxy Service supports only Windows-based computers. SOCKS uses Transmission Control Protocol (TCP) and can be used to control access to the Telnet, File Transfer Protocol (FTP), Gopher, and Hypertext Transfer Protocol (HTTP) protocols. The SOCKS Proxy Service does not support RealAudio, streaming video, or Windows Media Player clients.

Notes

Circuit layer proxies support a wider variety of protocols than application layer proxies.

See Also: *application layer proxy*

circuit-level gateway

A type of firewall that provides session-level control over network traffic.

Overview

Similar in operation to packet filtering routers, circuit-level gateways operate at a higher layer of the Open Systems Interconnection (OSI) reference model protocol stack. Circuit-level gateways are host-based and reside on individual clients and servers inside the network, rather than on a dedicated machine as they do with other types of firewalls. Circuit-level gateways examine incoming Internet Protocol (IP) packets at the session level—Transmission Control Protocol (TCP) or User Datagram Protocol (UDP)—and act as relays by handing off incoming packets to other hosts. Circuit-level gateways are rarely used as a stand-alone firewall solution; instead, they are typically used in combination with application layer proxy services and packet filtering features in dedicated firewall applications.

Microsoft Proxy Server combines the features of packet filtering, circuit-level gateways, and application layer proxy to provide a full firewall solution for protecting your corporate network. Proxy Server supports both the SOCKS protocol, which provides nontransparent circuit-level gateway security, and the Winsock Proxy, which provides transparent circuit-level gateway security.

See Also: *firewall, proxy server*

circuit-switched services

A term describing any telecommunications service that provides switched connections between a telco and their customers.

Overview

Circuit switching is the oldest form of digital communications used by telecommunications carriers. Circuit-switched telecommunications services can be provided to businesses by both local telcos and long-distance carriers. The Public Switched Telephone Network

(PSTN) is the classic example of a circuit-switched service (even its earlier analog form as the Plain Old Telephone System [POTS], it was also circuit-switched in operation). Another common example, often used for wide area network (WAN) connectivity between companies and remote branch offices, is Integrated Services Digital Network (ISDN).



Circuit-switched services. *How typical circuit-switched services work.*

Circuit-switched services are generally more suitable than packet-switched services for real-time transport of delay-sensitive traffic such as voice and video. This is because, after the circuit has been set up for a given connection, traffic is routed with minimal delay to its destination. Circuit-switched services offer guaranteed delivery and differentiated services that are only beginning to be offered by packet-switched services such as Ethernet that carry best-effort Internet Protocol (IP) traffic.

Uses

In the enterprise, circuit-switched services are often used as backup lines for more expensive leased lines. For example, if your more expensive T1 line fails, you can switch to a dial-up ISDN line (if it comes from a different provider). When using circuit-switched services, it is a good idea to monitor their usage because when a certain usage level is reached, leased lines may become economically preferable. Leased lines such as T1 lines use dedicated switches that are set up in a permanent configuration for as long as the customer leases the services.

Implementation

With circuit-switched services, a new switched circuit must be established each time one local area network (LAN) attempts to connect to a remote LAN. Circuit-switched services are temporary circuits only, and when the connection is terminated the circuits are torn down. Different switches can be used for each connection established, depending on availability and traffic, so the quality of services can vary between connections.

Typically, your corporate LAN is connected to these services through bridges, routers, modems, terminal adapters, or other equipment, depending on the type of service being offered. At the other end of the connection is the telco central office (CO), which sets up switches on demand to connect you to your remote branch office LAN. When you disconnect the WAN link, the switches are freed up for other purposes.

Advantages and Disadvantages

One advantage of circuit-switched services is that they are generally less expensive than leased lines. This is because switches are not dedicated to your network as leased lines are, and can therefore be used for other purposes when you are not using them. The cost for circuit-switched services is usually based on usage.

Another advantage of circuit-switched services is that you are not restricted to a single destination as you are with leased lines; you can dial up any destination that supports services similar to yours.

A disadvantage with circuit-switched services is that they are usually dial-up in nature, and a dial-up connection takes time to be established. This connection time varies with the technology used. For example, analog modems might take 10 to 20 seconds to establish a connection, and an ISDN terminal adapter might take only 1 to 2 seconds. This latency interval tends to make circuit-switched lines unsuitable for dedicated services, such as those used for connecting company Web servers to the Internet.

Another disadvantage of circuit-switched services is that the quality can differ substantially between connections, because each circuit is a temporary connection that can exist along different paths, switches, and communication devices.

See Also: *Integrated Services Digital Network (ISDN), leased line, Multiprotocol Label Switching (MPLS), packet-switching services, T1*

circular logging

A feature of Microsoft Exchange Server whereby transaction logs can be overwritten when full. Circular logging lowers disk space usage but reduces the chances of successfully recovering from a system crash.

Overview

Exchange Server databases, such as the directory database and information store, maintain special log files called transaction log files. These log files improve the performance and fault tolerance of the databases, and help track and maintain changes made to them. Transactions are immediately written both to the log files and to memory, and only afterward to the database files. Transaction logs are normally kept on a different drive from the database files to ensure fault tolerance in case of a disaster that causes data loss, such as a crashed disk or a power failure.

When circular logging is enabled, only a few transaction log files are maintained, and these are overwritten when they become full. This prevents log files from continually building up, which saves disk space. However, circular logging has the disadvantage of allowing you to perform only full backups, rather than incremental or differential ones, because you can restore information only up to the last full backup.

Notes

Do not use circular logging if data recoverability is of high importance to your mail system, which is almost always the case with e-mail. Circular logging is enabled by default. You should always disable it and ensure that you have enough free disk space to hold the transaction files. The only reasons you might want to enable circular logging would be if you run low on disk space or if your server is being used for noncritical data only, such as a public news server.

class

More precisely called “object class,” a logical grouping of objects within Active Directory directory service in Microsoft Windows 2000 and Windows .NET Server.

Overview

Objects are organized within Active Directory by their classes. Examples of object classes can include users, groups, computers, domains, and organizational units (OUs). Each class of objects has its own defining properties or attributes, as laid out in the Active Directory schema. Grouping objects logically into classes makes it easier to find and access these resources on the network.

Active Directory comes with predefined object classes. You can create additional classes or modify existing ones using the Active Directory schema.

See Also: *Active Directory, object (Active Directory)*

Class A

A type of Internet Protocol (IP) network where the first octet of IP addresses ranges between 0 and 126 inclusive.

Overview

Class A networks were originally intended for very large internetworks. Using the default class A subnet mask of 255.0.0.0, each class A network can support a maximum of 16,777,214 individual hosts with unique IP addresses—large enough for the largest of enterprise networks. However, there are no longer any Class A networks available since all 125 of them were assigned in the 1980s to large corporate customers, organizations, and the military. None of these organizations actually has networks large enough to require the full 16 million host addresses provided by their Class A addresses, so classless interdomain routing (CIDR) was developed by the Internet Engineering Task Force (IETF) to allow unused Class A addresses to be reassigned to other users.

Notes

For a huge private network not directly connected to the Internet or hidden behind a firewall using Network Address Translation (NAT), the Internet Assigned Numbers Authority (IANA) recommends using Class A addresses whose first octet is 10. This provides millions of possible host addresses ranging from 10.0.0.1 to 10.255.255.254.

The Class A address 127.0.0.1 is reserved for loopback and represents the local host being used.

See Also: *Class B, Class C, Class D, Class E, classful domain, classless domain, classless interdomain routing (CIDR), IP address*

Class B

A type of Internet Protocol (IP) network where the first octet of IP addresses ranges between 128 and 191 inclusive.

Overview

Class B networks were originally intended for large internetworks. Using the default Class B subnet mask of 255.255.0.0, each Class B network can support up to 65,534 individual hosts with unique IP addresses—large enough for the largest of enterprise networks. There are 65,536 possible Class B networks that can be assigned, and in the early days of internetworking a number of these network IDs were assigned to large corporations and to the military by the Internet Assigned Numbers Authority (IANA). Today it is virtually impossible to obtain a class B network ID.

Notes

For a large private network not directly connected to the Internet or hidden behind a firewall using Network Address Translation (NAT), IANA recommends using Class B addresses whose first two octets range from 172.16 to 172.31. This provides many thousands of host addresses ranging from 172.16.0.1 through 172.31.255.254 and up to 16 different subnets if required.

See Also: *Class A, Class C, Class D, Class E, classful domain, classless domain, IP address*

class-based queuing (CBQ)

An emerging technology for wide area network (WAN) traffic management.

Overview

Traditionally, WAN traffic for different classes of service (CoS) have been managed using router-based schemes that provide best-effort control of bandwidth allocation. For example, a router might be configured to allow no more than 20 percent of available bandwidth for streaming video. Such a bandwidth allocation is relative (percentage) rather than absolute (bps) in nature, which does not give much granularity for control of traffic, particularly mission-critical network traffic.

Class-based queuing (CBQ) is an emerging technology for WAN access routers that allows network managers to classify traffic types into a hierarchy of classes and then assign absolute bandwidth allocations to each type. For example, CBQ could first be used to divide traffic types according to different kinds of business applications and then to create a second level classifying traffic according to the department using the application. The customer relationship management (CRM) software used by the marketing department could then be assured a given minimum bandwidth.

Implementation

CBQ operates at Level 2 (the network layer) for IP traffic and works with any IP protocol including Transmission Control Protocol (TCP), User Datagram Protocol (UDP), or Internet Control Message Protocol (ICMP). To implement CBQ in a corporate WAN setting, a CBQ-capable access router would be inserted at the WAN edge of each corporate local area network (LAN) and configured with suitable classes to control allocation of bandwidth for WAN traffic. CBQ classes are implemented on routers by using policies.



Class-based queuing (CBQ). *Implementing CBQ on a WAN.*

See Also: *wide area network (WAN)*

Class C

A type of Internet Protocol (IP) network where the first octet of IP addresses ranges between 192 and 223 inclusive.

Overview

Class C networks were originally intended for small internetworks. Using the default Class C subnet mask of 255.255.255.0, each Class C network can support up to 254 individual hosts with unique IP addresses. There are 16,777,216 possible Class C networks that can be assigned, and it is relatively easy to obtain a Class C network ID from your Internet Service Provider (ISP) should your company require it.

Notes

For a small private network not directly connected to the Internet or hidden behind a firewall using Network Address Translation (NAT), the Internet Assigned Numbers Authority (IANA) recommends using Class C addresses whose first three octets range from 192.168.0 through 192.168.255. This provides thousands of host addresses ranging from 192.168.0.1 through 192.168.255.254 and up to 256 different subnets if required.

See Also: *Class A, Class C, Class D, Class E, classful domain, classless domain, IP address*

Class D

A type of Internet Protocol (IP) network where the first octet of IP addresses ranges between 224 and 239 inclusive.

Overview

Class D addresses are used exclusively for multicasting purposes. Most Class D addresses whose first octet is 224 are reserved for special purposes, as shown in the table. For multicasting within a private network not directly connected to the Internet or hidden behind a firewall using Network Address Translation (NAT), the Internet Assigned Numbers Authority (IANA) recommends using Class D addresses whose first octet is 239. For multicasting over the Internet you must first obtain a multicast address from IANA.

Examples of Some Reserved Class D Addresses with First Octet 224.

Address	*Reserved for*
224.0.0.1	Multicasting to all hosts on the local subnet
224.0.0.2	Multicasting to all routers on the local subnet
224.0.0.4	Multicasting to all Distance Vector Multicast Routing Protocol (DVMRP) routers
224.0.0.5	Multicasting to all Multicast Open Shortest Path First (MOSPF) routers
224.0.0.9	Multicasting to all Routing Internet Protocol version 2 (RIPv2) routers
224.0.0.10	Multicasting to all Interior Gateway Routing Protocol (IGRP) routers
224.0.18.255	Dow Jones multicasting service

See Also: *Class A, Class B, Class C, Class E, classful domain, classless domain, IP address*

Class E

A type of Internet Protocol (IP) network where the first octet of IP addresses ranges between 240 and 255 inclusive.

Overview

Class E addresses are reserved for research and experimental purposes, and are not used in ordinary computer networking. Class E addresses have a first octet that ranges from 240 to 255. The only Class E address commonly used is 255.255.255.255, which represents a local area network (LAN) broadcast.

See Also: *Class A, Class B, Class C, Class D, classful domain, classless domain, IP address*

classful domain

An Internet Protocol (IP) network that uses a default subnet mask.

Overview

A classful domain is an IP network that contains only the single default subnet. All hosts on the network are therefore in the same broadcast domain. For example, a network that is using a Class A address such as 10.0.0.0 and the default subnet mask 255.0.0.0 is a classful domain. The same would be true of a network using a Class B address such as 172.11.0.0 with subnet mask 255.255.0.0 and a network using a Class C address such as 192.16.33.0 with subnet mask 255.255.255.0—all three of these are examples of classful domains and are networks with only one subnet and therefore one broadcast domain.

Generally speaking, classful domains are not the way to go as they are very busy places with respect to traffic and may be susceptible to broadcast storms. Large networks are thus subnetted into a group of subnets forming what is called a classless domain.

See Also: *classless domain, IP address, subnetting*

classful routing protocol

A routing protocol for classful networks.

Overview

Classful routing protocols require that all Internet Protocol (IP) addresses on a network have the same subnet mask. For example, if a Class B network ID of 172.24.0.0 is subnetted into several subnets such as 172.24.1.0, 172.24.2.0, and 172.24.3.0, then classful routing requires that all these subnets have the same subnet mask. The reason for this limitation is that when routers using classful routing protocols exchange routing table updates with one another, the subnet mask is not included in the updates.

Examples of common classful routing protocols include Routing Information Protocol (RIP) versions 1 and 2, and Interior Gateway Routing Protocol (IGRP).

See Also: *Interior Gateway Routing Protocol (IGRP), routing, Routing Information Protocol (RIP), routing protocol*

Classical IP (CIP)

A method for running Internet Protocol (IP) over Asynchronous Transfer Mode (ATM).

Overview

Classical IP (CIP) is an alternative to LAN Emulation (LANE) as a way of transporting IP packets over Asynchronous Transfer Mode (ATM) networks. CIP is based on RFC 1577 and supports only IP and no other network protocols (LANE can also be used to transport multiprotocol traffic such as IP and Internetwork Packet Exchange [IPX] over ATM). CIP has a number of benefits that make it an attractive solution in many situations:

- CIP is fast—speeds of 25 megabits per second (Mbps), 155 Mbps, 625Mbps, and 2.4 gigabits per second (Gbps) are supported, making it competitive with Fast Ethernet and Gigabit Ethernet (GbE) as a network transport.
- CIP is a circuit-switched technology that provides full bandwidth to each station on the network.
- CIP is simpler to implement, manage, and troubleshoot than LANE and utilizes fewer ATM resources (virtual circuits).
- CIP utilizes bandwidth effectively by eliminating broadcast traffic (as described later).

Implementation

CIP groups IP hosts together into groupings called logical IP subnets (LISs). Each LIS has an Address

Resolution Protocol (ARP) server to support IP broadcasts. Because broadcasts are essential to IP for the operation of the ARP, CIP implements a device called an ARP server to eliminate the need for these broadcasts. This is necessary because ATM in itself does not support broadcasts. When an IP host appears on a CIP network, it first registers itself with the ARP server so that IP communications can take place.

When an IP host needs to communicate with a target host on the network, it passes the IP address of the target host to the ARP server in the LIS, which returns the ATM address of the target host. To make this possible, the ARP server must be preconfigured with mappings of the IP and ATM addresses of each IP host in the LIS. When the host knows the target host's ATM address, a switched virtual circuit (SVC) can be established between the two hosts and IP packets can be transmitted to the target host.

An alternative implementation of CIP is called CIP over PVC (permanent virtual circuit). This is used primarily for wide area network (WAN) connections that are always on.

See Also: *Asynchronous Transfer Mode (ATM), LAN Emulation (LANE)*

Classic desktop

A way of displaying the desktop and its contents that was first used in Microsoft Windows 95.

Overview

The Classic desktop presents users with a graphical user interface (GUI) that allows icons, shortcuts, files, and folders to be placed on it. These desktop items provide a simple way for users to launch and access frequently used programs and network resources. The Start menu provides another tool for launching programs and accessing resources. The taskbar displays the programs currently running and the Windows-to-network resources that are open.

The choice of GUI for users' client computers can make a big difference in employee productivity. The following are two factors involved in determining whether network administrators should maintain the Classic desktop or upgrade to the newer Active Desktop included with Microsoft Internet Explorer beginning with version 4:

- The cost of introducing users to the new desktop paradigm
- The necessity for tight integration among the desktop, the corporate network, and the Internet



Classic desktop. *The Classic desktop, first used in Windows 95.*

classless domain

An Internet Protocol (IP) network that uses a variable-bit subnet mask.

Overview

A classful domain is an IP network that uses a default subnet mask such as 255.0.0.0 for Class A networks, 255.255.0.0 for Class B, or 255.255.255.0 for Class C. Classful domains thus have only one subnet and one broadcast domain. By contrast, a classless domain is an IP network that uses a variable-bit subnet mask (VBSM), also called a classless subnet mask, to divide the network into two or more subnets, each of which represents a different broadcast domain.

Classless domains are generally built using routers. Each subnet within a classless domain constitutes a unique broadcast domain and collision domain, which generally improves performance over using a single broadcast and collision domain. Switches operate at the data-link layer and can partition a network into different collision domains, but they do not create different broadcast domains.

See Also: *classful domain, IP address, subnetting*

classless interdomain routing (CIDR)

Also called supernetting, an alternative way of classifying Internet Protocol (IP) addresses from the traditional Class A-E system.

Overview

Classless interdomain routing (CIDR) is a more efficient routing mechanism than the original method of segregating network IP addresses into classes named Class A, B, and C. The trouble with the old system is that it leaves too many unused IP addresses. For example, while Class A networks support large numbers of network nodes, there are not enough Class A networks to go around and none of the owners of these networks make anywhere near full use of the large number of IP addresses available to them. As a result, large numbers of Class A (and Class B) IP addresses go unused, and CIDR was developed as a way of reclaiming those IP addresses for allocation elsewhere. Similarly, while many Class C network IDs are available, many companies require more than the 254 IP addresses available on a Class C network, but not nearly as many as the 65,534 IP addresses available on any Class B network.

History

In the late 1980s, prescient architects of the Internet foresaw that the standard Class A-E method for assigning IP addresses would eventually fail and that the routing tables used by the core routers of the Internet's backbones would eventually grow unmanageably large. The class system provides for a huge number of IP addresses, but for only about 2 million different IP networks. As the number of networks attached to the Internet grew exponentially, a time was anticipated when there would be no more network numbers left to assign for new Class B and C networks (all Class A networks were assigned early on).

In the early 1990s the Internet Engineering Task Force (IETF) produced a group of Requests for Comments (RFCs), namely RFCs 1517 to 1520, that brought a way out of the dilemma. These RFCs formed the basis of CIDR and provided a way of not only reducing the growing load on the Internet's core routing tables (another result of the Internet's rapid growth) but also of reusing unused IP addresses to make about 8 million additional IP networks of Class C size available for assignment to other companies and organizations.

Uses

CIDR is used primarily by routers and gateways on the backbone of the Internet for routing packets across the Internet. CIDR is not used much in private networks because most networks are hidden behind firewalls and can use any arbitrary block of IP addresses, such as the 10.*x.y.z* block allocated by Internet Network Information Center (InterNIC) for general, private use. Instead, CIDR comes into its own on the Internet backbone to facilitate routing and ensure the continued functioning of the Internet. However, CIDR is viewed only as a workaround to the issues of insufficient numbers of IP networks available for allocation and maintaining the routing tables of backbone routers at workable sizes. Most Internet architects see IPv6 as the real solution to these issues and expect the need to change over to this system of addressing in the next few years.

Implementation

CIDR replaces the old class method of allocating 8, 16, or 24 bits to the network ID, and instead allows any number of contiguous bits in the IP address to be allocated as the network ID. For example, if a company needs a few thousand IP addresses for its network, it can allocate 11 or 12 bits of the address for the network ID instead of 8 bits for a Class C (which would not work because you would need to use several Class C networks) or 16 bits for Class B (which is wasteful).

CIDR assigns a numerical prefix to each IP address. For example, a typical destination IP address using CIDR might be 177.67.5.44/13 (the last part being pronounced "slash thirteen"). The suffix /13 indicates that the first 13 bits of the IP address identify the network, while the remaining 32–13 = 19 bits identify the host. In subnetting notation, the CIDR address 177.67.5.44/13 would be equivalent to the combination of IP address 177.67.5.44 and subnet mask 255.255.128.0 (see the following table). As another example, in CIDR notation an old style class B network 132.16.0.0 with default subnet mask 255.255.0.0 would be represented simply as 132.16/16.

The prefix helps to identify the Internet destination gateway or group of gateways to which the packet will be forwarded. Prefixes vary in size, with longer prefixes indicating more specific destinations. Routers use the longest possible prefix in their routing tables when determining how to forward each packet. CIDR enables packets to be sent to groups of networks instead of to individual networks, which considerably simplifies the complex routing tables of the Internet's backbone routers. The table shows the different CIDR values and their subnet mask equivalents.

CIDR Values and Their Subnet Mask Equivalents

Class	*CIDR Value*	*Subnet Mask*
Class A	/8	255.0.0.0
	/9	255.128.0.0
	/10	255.192.0.0
	/11	255.224.0.0
	/12	255.240.0.0
	/13	255.248.0.0
	/14	255.252.0.0
	/15	255.254.0.0
	/16	255.255.0.0
Class B	/17	255.255.128.0
	/18	255.255.192.0
	/19	255.255.224.0
	/20	255.255.240.0
	/21	255.255.248.0
	/22	255.255.252.0
	/23	255.255.254.0
	/24	255.255.255.0
Class C	/25	255.255.255.128
	/26	255.255.255.192
	/27	255.255.255.224
	/28	255.255.255.240
	/29	255.255.255.248
	/30	255.255.255.252
	/31	255.255.255.254
	/32	255.255.255.255

Notes

There might seem to be an alternate solution for avoiding the waste of IP addresses from Class A and Class B networks. Consider, for example, a company with a network of 5,000 nodes. Assigning a single Class B network ID such as 166.33.0.0 to the network would provide 65,534 possible IP addresses for hosts, which is far too many—60,534 addresses would remain unused. A solution to this might seem to be assigning the company a contiguous set of 20 Class C network IDs. Because each Class C address provides 254 possible host addresses, 20 contiguous Class C network Ids, such as 198.15.1.0 through 198.15.20.0, would provide 20 x 254 = 5080 possible IP addresses, which is just right, plus a few to spare.

Using this technique does eliminate the wasting of IP addresses, but it creates a new problem: to handle routing between your corporate network and the Internet, you need to add 20 new entries to the routing tables on Internet routers, one entry for each network ID you are using. Following this method quickly overwhelms the routers that form the Internet's backbone because as their routing tables grow their performance slows down. CIDR was devised to address this very issue by decreasing the number of entries required in the Internet's routing tables. CIDR does this by supernetting the 20 Class C networks above into a single supernet, which needs only one entry in the routing tables.

See Also: *Internet, IP address, IPv6, routing*

classless routing protocol

A routing protocol for classless networks.

Overview

Classless routing protocols allow different portions of an Internet Protocol (IP) network to use different subnet masks for the same network ID. Then, when routers using classless routing protocols exchange routing table updates with one another, the subnet mask is included in each update. Thus, given a single IP network ID, variable length subnet masking (VLSM) may be used to create different subnets having different subnet masks. Classless routing protocols also help conserve network resources by using route summarization.

Examples of common classless routing protocols include Border Gateway Protocol (BGP), Enhanced Interior Gateway Routing Protocol (EIGRP), and Open Shortest Path First (OSPF).

See Also: *Border Gateway Protocol (BGP), Enhanced Interior Gateway Routing Protocol (EIGRP), Open Shortest Path First (OSPF), routing, routing protocol*

CLB

Stands for Component Load Balancing, a Microsoft clustering technology supported by Microsoft Windows 2000 Server and Windows .NET Server and provided by Microsoft Application Center 2000.

See: *Component Load Balancing (CLB)*

cleartext

The process of sending data over a network in an unencrypted form.

Overview

By using a packet sniffer or software such as Network Monitor, anyone who can capture cleartext packets can read the information within them. Cleartext authentication methods are sometimes the best choice in a heterogeneous network environment where users running different operating system platforms need to access resources on network servers. For example, UNIX clients that need to access a Microsoft Internet Information Services (IIS) machine using a Web browser will need to be authenticated using a cleartext method called Basic Authentication.

Notes

Basic Authentication is usually described as cleartext authentication, but in actuality Basic Authentication weakly encrypts data using the well-known Uuencoding algorithm. This algorithm is in the public domain and can easily be decrypted by knowledgeable users.

The standard AppleTalk protocol uses clear-text authentication for allowing Apple Macintosh clients to access shared folders on Macintosh file servers using AppleShare.

See Also: *Basic authentication*

cleartext authentication

Also called Basic authentication, an authentication scheme that passes a user's credentials over a network in encrypted form.

See: *Basic authentication*

ClearType

A new display technology from Microsoft Corporation designed for liquid crystal display (LCD) displays.

Overview

Microsoft ClearType is intended to provide more readable displays on LCD screens for laptops, tablet PCs, and Pocket PCs. ClearType does this by a process known as sub-pixel rendering, which triples the perceived number of pixels for vertical screen resolution (horizontal resolution remains unchanged). The results are easier-to-read text that appears more like a page out of a book than text displayed on a screen. ClearType was designed with Microsoft Reader in mind, a technology developed by Microsoft for eBooks.

ClearType technology was developed by Microsoft Research, but a similar subpixel rendering concept was developed in the 1970s by Steve Gibson for the Apple II platform. ClearType support will be included in all future releases of Microsoft Windows and Microsoft Office.

For More Information

You can find out more about ClearType at *research.microsoft.com.*

CLEC

Stands for Competitive Local Exchange Carrier, a telco that competes with existing incumbent telcos under the terms of the Telecommunications Act of 1996.

See: *Competitive Local Exchange Carrier (CLEC)*

client

A workstation or computer, usually belonging to a single user, as opposed to a server, which is shared by many users.

Overview

Planning the hardware, software, configuration, deployment, and maintenance of clients is as important to the network administrator as the other server-related activities.

Choice of a client operating system depends on various considerations. For example, in determining whether to install Microsoft Windows Millennium Edition (Me), Windows 2000 Professional, or Windows XP Professional on client computers, users should consider the following:

- Both client operating systems, in conjunction with Microsoft Internet Explorer versions 5 and later, offer the same desktop configuration options, similar utilities, and similar support for features such as user profiles, hardware profiles, and system policies.
- Windows 2000 Professional or Windows XP Professional will provide client machines with better performance, greater reliability, and more robust security, but they have higher hardware requirements than Windows Millennium Edition (Me).
- Windows Me supports a broader range of devices and legacy software applications, and includes power-management support—making it a better solution for mobile users.

Notes

In configuring clients to operate on a network, appropriate software must be installed on each client to allow it to access servers on the network. For example, to access Windows 2000 servers, client machines require Microsoft client software such as Client for Microsoft Networks. To access Novell NetWare servers, client machines require NetWare-compatible clients, such as Client for NetWare Networks.

See Also: *client/server, server*

client access license (CAL)

A license that grants a client machine access to a Microsoft BackOffice product running on a network of computers.

Overview

Every client computer on a network, regardless of whether it is running a Microsoft or non-Microsoft operating system, requires a client access license (CAL) if it will be accessing any of the following Microsoft Windows NT, Windows 2000, Windows XP, or Windows .NET Server services:

- File services, for accessing shared files and folders on a server
- Print services, for accessing shared network printers
- Remote Access Service (RAS) or Routing and Remote Access Service (RRAS)
- File and Print Services for NetWare (FPNW)
- File and Print Services for Macintosh (FSM)
- Microsoft Transaction Server (MTS) and Microsoft Message Queue (MSMQ) Server access
- Windows NT Terminal Server functionality

Client access licenses can operate in one of two modes:

- Per Server licensing, which is based on concurrency of access to network resources
- Per Seat licensing, which is the more commonly implemented solution and is supported by all BackOffice applications

See Also: *license*

client certificate

A digital certificate obtained for a client application (such as a Web browser) that can be used by the client to digitally sign data it transmits.

Overview

Client certificates can be used to enable client machine authentication for the purpose of secure communication over the Internet using the Secure Sockets Layer (SSL) protocol.



Ratings help you control the Internet content that can be viewed on this computer.

Use certificates to positively identify yourself, certificate authorities and publishers.

Microsoft Profile Assistant stores your name, address, and other personal information.

Microsoft Wallet provides a secure place to store private information for Internet shopping.

Client certificate. *Importing a client certificate in the Internet Explorer Properties dialog box.*

A client obtains a certificate from a certificate authority (CA) by submitting a certificate request file. The CA responds by issuing a client certificate, which contains the client's identification information in encrypted form, along with the client's public key. The client certificate must then be installed on the client's Web browser. Microsoft Internet Explorer can import client certificates into the browser's certificate store using the Personal button on the Content tab of the Internet Options dialog box. Administrators can also use the Internet Explorer Administration Kit (IEAK) for preconfiguring client certificates prior to installation on user computers.

In SSL communication, a Web server can validate the identity of a client using the certificate installed on the client. With Microsoft Internet Information Server (IIS) version 4, client certificates can be mapped to Microsoft Windows NT user accounts by way of a process called certificate mapping. (Windows 2000, Windows XP, and Windows .NET Server support a similar feature in their Internet Information Services.) Certificate mapping makes it easier for administrators to control access to content located on the Web server.

Notes

Use client certificates when it is important for servers to validate the identity of clients—for example, when your enterprise includes mobile users with laptops who need to remotely and securely access the company's intranet server using Internet Explorer.

See Also: *digital certificate, public key cryptography*

Client for Microsoft Networks

A networking component in Microsoft Windows 95, Windows 98, Windows Millennium Edition (Me), Windows 2000, Windows XP, and Windows .NET Server that makes it possible to access file and print services on all of the above versions of Windows, as well as Windows NT, Windows for Workgroups, and LAN Manager dedicated servers and peer servers.

Overview

Client for Microsoft Networks works with any combination of NetBEUI, IPX/SPX-Compatible Protocol, and Transmission Control Protocol/Internet Protocol (TCP/IP) protocols. Client for Microsoft Networks cannot be used for accessing non-Microsoft servers such as Novell NetWare servers. You must install Client for NetWare Networks to access these servers. Windows 95 and Windows 98 allow you to install more than one client at a time to access different kinds of servers on the network.

Use the Network utility in Control Panel to install Client for Microsoft Networks on a computer running Windows 95 or Windows 98. Then use the property sheet of Client for Microsoft Networks to configure the computer to either participate in a workgroup or log on to a Windows NT, Windows 2000, or Windows .NET Server domain.

Notes

In Windows NT, the equivalent component is called the Workstation service, but in Windows 2000, Windows XP, and Windows .NET Server, the component is Client for Microsoft Networks, as in Windows 95 and Windows 98.

Client for NetWare Networks

In Microsoft Windows 95, Windows 98, Windows Millennium Edition (Me), Windows 2000, Windows XP, and Windows .NET Server, a networking component that makes it possible to access file and print services on Novell NetWare servers.

Overview

Client for NetWare Networks requires that the IPX/SPX-Compatible Protocol be installed. Client for NetWare Networks cannot be used for accessing Microsoft servers such as Windows NT, Windows 2000, and Windows .NET Server. You must install Client for Microsoft Networks to access these servers. Windows 95 and Windows 98 allow you to install more than one client at a time to access different kinds of servers on the network.

Use the Network utility in Control Panel to install Client for NetWare Networks on a computer running Windows 95 or Windows 98. Then use the property sheet of Client for NetWare Networks to configure the preferred NetWare server, to select the first drive letter to use for mapping network drives from NetWare command-line utilities, and to enable processing of logon scripts on the preferred server.

Notes

Client for NetWare Networks can connect to NetWare 3 and earlier servers, or NetWare 4 servers running in bindery emulation mode. If you want to use Client for NetWare Networks to connect to a NetWare 4 server running Novell Directory Services (NDS), you must also install Service for NetWare Directory Services on the Windows 95 or Windows 98 client. This service is available with Windows 95 OSR2 or Service Pack 1 for Windows 95, and is included with Windows 98.

Before installing Client for NetWare Networks on a computer running Windows 95 or Windows 98, make sure you remove any real-mode NetWare requestor software running on the machine, such as NETX (the NetWare 3.*x* client shell) or VLM (the NetWare 4.*x* client shell).

client installation point

A shared directory on a network file server to which users on your network can connect to install client software locally on their client computers.

Overview

Creating a client installation is the first step in preparing to install software over the network. To create a client installation point, create a directory on a server and share the folder with full permissions for administrators and read-only permissions for ordinary users. Either copy the installation files for the software from the CD to the shared directory, or run the setup program using a special switch to copy the files so that they can be used for network installation—for example, to uncompress the cabinet files on the CD. Users can then connect to the shared directory, run the setup program, and complete the installation process.

client/server

A paradigm for deploying two-tiered distributed applications.

Overview

In the client/server model, an application is split into a front-end client component and a back-end server component. The front-end client part of the application runs on a workstation and receives data that is input by the user. The client component prepares the data for the server by preprocessing it in some fashion, and then sends the processed information to the server, usually in the form of a request for some service. The back-end server component receives the client's request, processes it, and returns information to the client. The client receives the information returned from the server and presents it to the user by way of its user interface. Usually most of the processing is done at the back end (server end) where database servers, messaging servers, file servers, and other resources are located.

An example of a simple client/server application is a Web application that is designed for Microsoft Internet Information Services (IIS) using a combination of server-side Active Server Pages (ASP) programming and client-side scripting. The ASP scripts run on the Web server, while the client-side scripts run on the client Web browser.

See Also: *distributed application*

Client Services for NetWare (CSNW)

A Microsoft Windows 2000, Windows XP, and Windows .NET Server service that provides Windows clients with access to Novell NetWare file, print, and directory services.

Overview

Client Services for NetWare (CSNW) is an optional service that can be installed on Windows 2000, Windows XP, and Windows .NET Server machines to enable them to directly connect to file and print resources on Novell NetWare servers. In other words, CSNW is a Microsoft version of the NetWare redirector for Windows 2000, Windows XP, and Windows .NET Server.



Client Services for NetWare (CSNW). *How CSNW works.*

CSNW is a full-featured, 32-bit client for NetWare networks that can be installed on Windows 2000 Professional or Windows XP Professional by using the Network and Dial-Up Connections utility in Control Panel. If you are connecting to a NetWare 3.12 or earlier server, you must specify a preferred NetWare server for access to its bindery. If you are connecting to NetWare 4, specify the Novell Directory Services (NDS) tree and default context. CSNW supports browsing NDS trees, but it does not support administration of NDS trees.

CSNW supports connections to servers running version 2, 3, or 4 of NetWare, including both bindery emulation and NDS on NetWare 4. CSNW includes support for NetWare Core Protocol (NCP), Large Internet Protocol (LIP), and Long filenames (LFNs). Additional options are included for printing and login script support. CSNW requires installation of the NWLink protocol, but if it is not installed already, it will be added automatically when you install CSNW on a machine.

Notes

On a machine running Windows 2000 Server, NetWare connectivity is provided by Gateway Services for NetWare (GSNW). Use CSNW to provide your Windows 2000 Professional or Windows XP Professional clients with dedicated access to Novell NetWare servers; use GSNW only to provide occasional access to NetWare servers from Windows 2000 Professional or Windows XP Professional clients.

An alternative to using CSNW on Windows 2000 Professional machines is to use the Novell Client for Windows 2000.

See Also: *bindery, Gateway Service for NetWare (GSNW), Novell Directory Services (NDS), NWLink*

cloud

In networking, any part of the network whose data transmission paths are unpredictable and vary from session to session.

Overview

Clouds are often used in networking diagrams to represent packet-switching services. In these services, a packet sent from one node to another follows an unpredictable path because, at any given moment, different routers or other devices can be used to forward the packet toward its destination. The Internet is an example of a packet-switching cloud for Transmission Control Protocol/Internet Protocol (TCP/IP) networking because data sent between two points can travel over many possible paths. This is why the Internet is graphically represented as a cloud in drawings of wide area networks (WANs). Other examples of packet-switching services include frame relay and X.25 networks.



Cloud. *The Internet depicted as a cloud of paths and connections.*

Circuit-switched services are often represented as clouds as well. In circuit-switched services, communication switches at various telco and carrier central offices (COs) and switching facilities are temporarily used for establishing circuits between two communicating nodes. Each time communication is terminated and reestablished, different sets of switches can be used.

See Also: *telecommunications services*

cluster

A group of two or more nodes within a system supporting clustering.

Overview

When a client on a network tries to access shared resources or applications on a cluster, the cluster appears to the client as a single node or server instead of the group of nodes or servers it really is.

In the Cluster service of Microsoft Windows 2000 and Windows .NET Server Enterprise Server and Datacenter Server, each node in a cluster is a completely independent computer system that must be running Windows 2000 Enterprise Server. Typically, such nodes are connected by a shared storage bus such as an external Small Computer System Interface (SCSI) disk subsystem or RAID array.

See Also: *clustering*

cluster-aware application

An application that can run on a node of a cluster and can be managed as a cluster resource.

Overview

In the Cluster service on Microsoft Windows 2000 or Windows .NET Server Enterprise Server and Datacenter Server editions, a cluster-aware application is one that can run on a node of a cluster and can be managed as a cluster resource. Cluster-aware applications can be written to access the Windows 2000, or Windows .NET Server Cluster service by using its cluster application programming interface (API). Cluster-aware applications also implement the extension dynamic-link libraries (DLLs) of Cluster Administrator, which allow them to be managed using Cluster Administrator. These features allow developers to write high-scalability applications that can operate across the different nodes in a cluster.

A cluster-aware application is one that is aware of the fact that it is running on a cluster and can make use of the scalability, load balancing, and failover aspects of clustering to provide high availability for mission-critical business environments. Cluster-aware applications include database applications such as Microsoft SQL Server, messaging applications such as Microsoft Exchange Server, and Web applications for running on Web servers such as Microsoft Internet Information Services (IIS).

See Also: *clustering*

clustering

Any technology that enables two or more servers to appear to clients as a single system.

Overview

A cluster consists of a group of computers functioning together as a unit, running a common set of applications, and presenting a single image to client systems. Clustering can be implemented in various ways, but its basic goals are to provide businesses with high availability, high reliability, and high scalability solutions for mission critical business operations.

Clustering solutions generally come in two basic types:

- **Stateful clustering:** The goal of this type of clustering is to provide high availability and high reliability for fast, uninterrupted service in high-demand environments that can tolerate minimal downtime (stateful clustering is not designed to scale applications out to handle more users—this is the purpose of stateless clustering discussed next). Stateful clustering works by connecting independent computer systems into a single entity called a cluster, with each system within the cluster being called a node. Generally some multiple of two is used as the number of nodes within a cluster, for example, 2, 4, 8, 16, or 32 nodes. The different nodes within a cluster are usually connected using a shared disk subsystem which typically consists of a hard disk system or RAID-5 array connected to each node using a fast Small Computer System Interface (SCSI) bus or fiber channel connection. The result is a cluster of computer systems that acts and functions as if it were a single system. In stateful clustering, the nodes within a cluster generally share the workload, and when one node fails its workload fails over (transfers to) another node in the cluster with no interruption of services from the user's perspective. When the failed node comes back online, the workload fails back to this node and normal operation of the cluster resumes. Failover in stateful clustering systems can be implemented in different ways, and this is discussed below. An example of a platform supporting stateful clustering is the Cluster service of Microsoft Windows 2000 Enterprise Server and Datacenter Server. Another name for stateful clustering is shared storage or shared something clustering.
- **Stateless clustering:** The goal of this type of clustering is to provide high availability and high reliability by enabling administrators to scale out applications to meet increased demand as the number of users and traffic generated increase. Stateless clustering uses a group of nodes (servers) that are not connected in any way apart from the underlying network connectivity. No failover occurs between nodes when a node in the cluster fails. Instead, some form of load balancing is used to share the workload between the different nodes, and if one node fails the other nodes pick up the extra workload with no interruption of services. Stateless clustering is supported by three Microsoft products: Network Load Balancing (NLB), Component Load Balancing (CLB), and Application Center 2000. Another name for stateless clustering is shared-nothing clustering, and SQL Server 2000 supports a form of shared-nothing clustering known as Federated Server Groups.

Stateful clustering solutions themselves generally fall into three different categories, depending on if and how failover occurs between different nodes:

- **Active/active clustering:** This type of clustering makes the most efficient use of system resources because there are no redundant nodes: all nodes run active processes. If one node of a cluster fails, other nodes take on the failed cluster's workload. The latency for failover in this scenario is typically 15 to 150 seconds, depending on the hardware/software configuration. Active/active clustering is supported by the Cluster service of Microsoft Windows 2000 Enterprise Server and Datacenter Server, and by the Cluster service of Windows .NET Server (discussed later in this article).
- **Active/standby clustering:** Nodes are paired within a cluster, with one node designated to take over should another node fail. If an active node fails, a standby node assumes its workload. Latency for failover is also 15 to 150 seconds. Active/standby clustering is a more expensive solution than active/active because the standby node is essentially doing nothing unless the active node fails.

- **Fault-tolerant clustering:** Nodes are paired within a cluster, and all nodes perform all tasks simultaneously. This is an expensive solution from a hardware point of view, but latency for failover is reduced to a second or less.

Marketplace

Many different clustering solutions are in the marketplace, but this article focuses on four different clustering technologies delivered by Microsoft platforms and products, namely:

- Windows clustering, previously known as Microsoft Cluster Services (MCSC)
- Network Load Balancing (NLB)
- Application Center 2000
- Component Load Balancing (CLB)

You can find additional information in separate articles on each of these four solutions.

Windows clustering is a feature of Microsoft Windows 2000 Advanced Server and Datacenter Server and of Windows .NET Server. Windows clustering is probably Microsoft's best-known clustering platform and was originally developed for Microsoft Windows NT Server Enterprise Edition where it was code-named Wolfpack during its development. Windows clustering is a stateful clustering solution that enables system architects to create clusters from groups of independent computer systems and to run and manage cluster-aware applications. Using Windows clustering, you can build two-way clusters (that is, clusters with only two nodes) on Windows 2000 and Windows .NET Server Enterprise Server edition or four-way clusters on Windows 2000 and Windows .NET Server Datacenter Server edition (Windows NT Server Enterprise Edition supported only two-way clustering). In Windows clustering a cluster connects nodes together using a shared file system and clusters can utilize active/active clustering for maximum reliability and availability. Windows clustering makes an excellent choice for clustering database and messaging applications for enterprises.

Network Load Balancing (NLB) is a stateless clustering solution included with Windows 2000 and Windows .NET Server Enterprise Server and Datacenter Server editions, and it was formerly called Windows Load Balancing Services (WLBS) on the Windows NT Server 4 platform. NLB provides load balancing of Internet Protocol (IP) traffic to up to 32 independent network nodes (servers) and is typically used to build farms of Web servers or Exchange 2000 Outlook Web Access (OWA) servers for large enterprises. When one node in an NLB cluster goes down, the load is simply redistributed to the remaining nodes.

Application Center 2000 is a part of Microsoft Corporation's .NET Server family, and is a stateless clustering platform designed to provide a single point of management for farms of Web servers. Appcenter is typically used in conjunction with NLB and CLB to provide high availibity, high reliability clustering that can scale out to large numbers of users. Appcenter manages a collection of servers in a Web farm as a single entity and can be used to create new clusters, join servers to existing cluster, remove nodes from clusters, deploy applications and application components to different nodes within a cluster, move components between nodes of a cluster, monitor the performance of a cluster, and manage load balancing of network connections to cluster nodes and COM+ components within a cluster-aware application.

Component Load Balancing (CLB) is supported by all versions of Windows 2000 Server and is used to provide load balancing of COM+ objects across distributed applications deployed on up to 16 nodes (servers). CLB is a stateless clustering solution that requires no special hardware but needs Microsoft Application Center 2000 in order to operate.

See Also: *Application Center, cluster, cluster-aware application, Component Load Balancing (CLB)*

CMAK

Stands for Connection Manager Administration Kit, a wizard-based tool for creating custom connectivity solutions, and a component of Internet Connection Services for Microsoft Remote Access Service (RAS).

See: *Connection Manager Administration Kit (CMAK)*

CMP cabling

A grade of cabling that is resistant to combustion.

See Also: *plenum cabling*

CN

Stands for connected network; in Microsoft Message Queue (MSMQ) Server terminology, a name for a collection of computers in which any two computers can directly communicate.

See: *connected network (CN)*

CNAME record

Stands for Canonical Name record, a Domain Name System (DNS) resource record for assigning an alias to a host.

Overview

A CNAME record is used to map an alias to the canonical name (true name) of a host on the Internet or a private Internet Protocol (IP) internetwork. The CNAME record thus lets you use more than one name to refer to a single host on the network. If a name server is queried by a resolver to look up a host and the queried name is an alias in a CNAME record, the name server replaces the alias name with the canonical name of the host being looked up and then looks up the address of the canonical name.

Examples

Here is an address record for the host named server12 in the microsoft.com Internet domain. This record has the IP address 172.16.8.5, followed by a CNAME record indicating that the name bobby (or the fully qualified domain name bobby.microsoft.com) is an alias for the same host:

```
server12.microsoft.com  IN  A  172.16.8.55
bobby                   IN  CNAME  server12
```

Uses

CNAME records are generally used to hide the true names of important servers on your network from the outside world.

CNRP

Stands for Common Name Resolution Protocol, a proposed Internet Engineering Task Force (IETF) standard for a protocol to replace Uniform Resource Locators (URLs) with a simpler, more natural scheme for navigating the Web.

See: *Common Name Resolution Protocol (CNRP)*

CO

Stands for central office, a telco switching facility.

See: *central office (CO)*

coax

Short for coaxial cabling, a legacy form of network cabling.

See: *coaxial cabling*

coaxial cabling

A legacy form of network cabling.

Overview

Coaxial cabling (or simply coax) is a form of network cabling that was used in legacy 10Base2 and 10Base5 Ethernet networks. The name *coax* comes from its two-conductor construction in which the conductors run concentrically with each other along the axis of the cable. Coaxial cabling in local area networks (LANs) has been largely replaced by twisted-pair cabling (structured wiring installations) within buildings, and by fiber-optic cabling for high-speed network backbones.



Coaxial cabling. *Typical coax cabling.*

Coaxial cabling generally consists of a solid copper core for carrying the signal, covered with successive layers of inner insulation, aluminum foil, a copper braided mesh, and outer protective insulation. A solid conductor provides better conductivity than a stranded one, but is less flexible and more difficult to install. The insulation is usually polyvinyl chloride (PVC) or a nonstick coating; the aluminum foil and copper mesh provide shielding for the inner copper core. The mesh also provides the point of grounding for the cable to complete the circuit.

Types

Coaxial cabling comes in various types and grades. The most common are the following:

- Thicknet cabling, which is an earlier form of cabling used for legacy 10Base5 Ethernet backbone installations. This cabling is generally yellow and is referred to as RG-8 or N-series cabling. Strictly speaking, only cabling labeled as IEEE 802.3 cabling is true thicknet cabling.
- Thinnet coaxial cabling, which is used in 10Base2 networks for small Ethernet installations. This grade of coaxial cabling is generally designated as RG-58A/U cabling, which has a stranded conductor and a 53-ohm impedance. This kind of cabling uses bayonet Neill-Concelman (BNC) connectors for connecting to other networking components, and must have terminators at free ends to prevent signal bounce.
- ARCNET cabling, which uses thin coaxial cabling called RG-62 cabling with an impedance of 93 ohms.
- RG-59 cabling, which is used for cable television (CATV) connections.

In addition, a number of special types of coaxial cabling are sometimes used for certain networking purposes. An example is twinax cabling, which consists of two conductors first enclosed in their own insulation and then enclosed in a single copper mesh and insulating jacket. Twinax is used in legacy IBM networks for connecting AS/400 systems to 5250 terminals. Other more exotic varieties include triax, quadrax, and ribbon types of coaxial cables.

Notes

Coaxial cabling is often used in heavy industrial environments where motors and generators produce a lot of electromagnetic interference (EMI), and where more expensive fiber-optic cabling is unnecessary because of the slow data rates needed. Coaxial cabling is also used frequently in IBM mainframe and minicomputer environments. A device called a splitter can be used to fork one coaxial cable into two—for example, when connecting two 3270 terminals to one IBM mainframe system. A splitter is used at either end of the connection so that the signals for both terminals can be sent over a single coaxial cable. Coax multiplexers can be used to connect eight or more terminals to a single controller.

See Also: *cabling, fiber-optic cabling, twinax cabling, twisted-pair cabling*

codec

Short for **co**mpressor/**dec**ompressor, an encoding algorithm used for recording digital audio or video.

Overview

A codec compresses transmitted data at the sending end and decompresses it at the receiving end. Microsoft Windows Media Player uses different codecs to provide streaming multimedia information over a Transmission Control Protocol/Internet Protocol (TCP/IP) network such as the Internet. Windows Media Player provides a number of different codecs for different purposes. You can select a codec to give you the audio or image quality and image size that you want for your transmission.

Code Division Multiple Access (CDMA)

A second-generation (2G) digital cellular phone technology popular in the United States and parts of Asia.

Overview

Code Division Multiple Access (CDMA) can be used to refer both to a type of digital cellular phone system and to the specific media access method used by this kind of cellular system. CDMA was developed by QUALCOMM in 1993, and it was adopted and ratified by the Telecommunications Industry Association (TIA) as part of their Interim Standard 95, specifically as TIA standard IS-95a.

CDMA supports combined voice and data over a single channel and supports circuit-switched data transmission at a rate of 14.4 kilobits per second (Kbps), although in practice speeds are more typically around 13 Kbps. Speeds up to 19.2 Kbps are also possible by using special error detection and correction techniques.

Architecture

CDMA uses the spread spectrum wireless networking technology—first developed for military communication systems in the 1940s because it spreads its transmission over a large bandwidth, making it difficult to jam. Instead of dividing the available radio spectrum into a series of discrete channels using the older Time Division Multiple Access (TDMA) media access method, a CDMA channel occupies the entire available frequency band. In other words, all CDMA users on a given network utilize the same frequency band.

What enables users to share the same spectrum is that CDMA assigns a special digital code sequence to each user. Users thus share time and frequency resources on the available bandwidth, and their individual communications are channeled using these codes. The code tag identifies the conversation to the transmission station and enables multiple users to simultaneously access the network and divide its frequency resources between them—hence the name Code-Division Multiple Access.

Without knowledge of a conversation's code tag, eavesdropping on CDMA conversations is difficult, making CDMA a more secure cellular phone technology than the Advanced Mobile Phone Service (AMPS) still used widely in the United States. CDMA also has a much higher call capacity than AMPS and is comparable to the Global System for Mobile Communications (GSM) standard for cellular communication used in Europe. The disadvantage is that CDMA is more complex to implement than TDMA digital cellular technologies.

Marketplace

The main CDMA-based system in the market today is QUALCOMM's cdmaOne, the operation of which is now supervised by the CDMA Development Group and independent organization. The cdmaOne system uses 64 different codes called Walsh sequences, and in theory thus supports up to 64 concurrent users talking over a single 1.25-megahertz (MHz)-wide channel. In practice, however, this works out to more like 20 concurrent users, especially when data transmissions are included. The cdmaOne system has approximately 30 million users in the United States and Asia, with its competitors being Global System for Mobile Communications (GSM), which has 150 million users worldwide; Digital Advanced Mobile Phone Service (D-AMPS), with 15 million users in the United States; and Personal Digital Cellular (PDC), with 45 million users in Japan.

A special upgrade to cdmaOne called IS-95b provides improved data speeds of up to 115 Kbps, though real speeds are usually more like 64 Kbps (the version of IS-95b in Japan and Korea supports packet-switched data rates of only 64 Kbps). Further proposed 2.5G and third-generation (3G) improvements fall under the umbrella name of CDMA2000, and the CDMA technology itself forms the basis of much of the proposed IMT-2000 standard for 3G cellular communications from the International Telecommunication Union (ITU).

Another cellular system in the United States based on CDMA technologies is Sprint PCS from Sprint Corporation, which operates at a higher frequency band than cdmaOne but uses CDMA as its media access control method.

Notes

CDMA does not assign specific frequencies to each user as do other competing systems. Instead, CDMA uses a unique technique where every channel uses the entire available spectrum. CDMA was developed and first used by the military during World War II by the English to thwart German attempts at jamming transmissions. The Allies utilized CDMA to transmit over different frequencies, instead of one, which made it extremely difficult for the Germans to pick up entire signals.

For More Information

You can find the CDMA Development Group at *www.cdg.org.* QUALCOMM is at *www.qualcomm.com.*

See Also: *2G, 2.5G, 3G, Advanced Mobile Phone Service (AMPS), CDMA2000, cellular communications, Global System for Mobile Communications (GSM), Time Division Multiple Access (TDMA)*

Coded Orthogonal Frequency Division Multiplexing (COFDM)

A technique for enhancing the speed of wireless networking.

Overview

Coded Orthogonal Frequency Division Multiplexing (COFDM) is employed by the 802.11a wireless networking standard as a way to work around the difficulty of radio frequency (RF) interference caused by scattering and reflection off of buildings, walls, and similar objects. The problem with wireless networking, as opposed to wireline (wired) networking, is that although wireline networks usually have a single path between different stations, wireless communication is often multipath. As the figure shows, a signal can travel between a wireless client and a base station along different paths due to reflection of RF signals off walls and other objects. The result is that when the signal arrives it is spread out in time. If the time over which a signal can be spread out by interference (the delay spread) is less than the time between individual packet transmissions (the symbol rate), then the receiver can still be processing one packet while the next one arrives, creating a problem.

COFDM works around this problem not only by slowing down the symbol rate (the rate of packet transmission) but also by cramming as much information as possible into each packet. COFDM thus transmits data in a massively parallel fashion, ensuring that each symbol can be processed in a time less than the delay spread between divergent signal paths. Each symbol transmitted is proceeded and followed by a cyclic prefix called a guard interval, which helps give the baseband processor time to receive and process the information. Additional error-correcting information is encoded to help reduce the effects of interference.



Coded Orthogonal Frequency Division Multiplexing (COFDM). *COFDM helps overcome the delay spread caused when signals are reflected off of interfering objects.*

Using COFDM, wireless networks based on 802.11a can break through their current speeds of 10 to 20 megabits per second (Mbps) to achieve speeds of 155 Mbps or even higher.

See Also: *802.11a, wireless networking*

code-operated switch

A switch with a combination of input and output ports, the connections between which can be remotely reconfigured by commands entered into a computer.

Overview

Code-operated switches are useful in environments where remote switching is needed for file-sharing or monitoring purposes. For example, you could use an RS-232 serial code-operated switch to remotely switch between pieces of data terminal equipment (DTE), such as servers or routers for running diagnostics from a remote console.



Code-operated switch.

Implementation

Internal dual inline package (DIP) switches are usually used to configure the code-operated switch so that a different arming character can be used to trigger each connected device. The code-operated switch then examines the incoming data stream for these special text-string codes in order to determine to which device it should route data. An example might be the remote switching between printers. A remote computer could send an embedded switching character to specify which printer connected to the code-operated switch should be used for printing the data.

A remote user can connect to the company network using a modem that interfaces with a code-operated switch, and then use the switch to control a variety of serial-controlled devices in an industrial environment, such as a group of laboratory instruments. Code-operated switches are available from different vendors in configurations supporting up to 64 different serial devices from one remote connection.

Besides embedding switching characters in the data stream, embedded control characters can also be used to directly control the code-operated switch.

See Also: *switch*

COFDM

Stands for Coded Orthogonal Frequency Division Multiplexing, a technique for enhancing the speed of wireless networking.

See: *Coded Orthogonal Frequency Division Multiplexing (COFDM)*

cold boot

Restarting the computer by turning the power switch off and then on, or by shutting down the computer, turning it off, and then turning it on again.

Overview

If you perform the first type of rebooting, open files will not be properly closed and data can be lost. However, this method ensures that memory is cleared and devices are properly reset. An example might be when you reconfigure the settings of a legacy modem using the modem utility in Control Panel. You might find that you must cold boot your machine in order for the new configuration settings to fully take effect.

See Also: *boot*

Cold Fusion

A popular tool for developing dynamic Web applications.

Overview

Cold Fusion from Allaire Corporation lets developers rapidly create and deploy dynamic Web applications that can access information from databases and other data sources. Cold Fusion uses a set of proprietary tags that are similar to Hypertext Markup Language (HTML) tags. The resemblance to HTML tags makes Cold Fusion a comfortable platform for experienced HTML users to develop database-driven applications that can be accessed from Web browsers. Cold Fusion is available for both UNIX and Microsoft Windows platforms, and it is an alternative to Microsoft Corporation's Active Server Pages (ASP) technology for developing dynamic Web applications.

For More Information

Find out more about Cold Fusion at *www.allaire.com.*

See Also: *Active Server Pages (ASP)*

Collaboration Data Objects (CDO)

A collection of Component Object Model (COM) objects that allow developers to create Microsoft Internet Information Services (IIS) Web applications that send and receive electronic mail.

Overview

Collaboration Data Objects (CDO) is a Microsoft object library that provides messaging capability for applications written in Microsoft Visual Basic, Microsoft Visual C++, and Win32 Virtual Machine for Java. CDO provides distributed Web applications with a standard way to quickly and easily create, send, post, receive, read, and manipulate messages using interfaces based on standard Internet protocols such as Simple Mail Transfer Protocol (SMTP), Network News Transfer Protocol (NNTP), and Multipurpose Internet Mail Extensions (MIME).

CDO was formerly known as Active Messaging, and on the Microsoft Windows NT platform was called Collaboration Data Objects for Windows NT Server (CDONTS). CDONTS actually provides a subset of CDO functionality that includes messaging services but omits the calendaring and workflow functions that CDO on Microsoft Exchange 2000 provides.

CDO 2 is included with IIS in Windows 2000, Windows XP, and Windows .NET Server to support the built-in SMTP and NNTP services. CDO 2 does not support mailboxes, but it does support protocol events to enable programmers to write routines that respond to incoming messages and process outgoing messages. Developing mail-enabled applications using CDO is easier and faster than building custom Common Gateway Interface (CGI) mail programs, and CDO applications have more flexibility than typical CGI applications.

CDO is also a powerful development tool for Exchange Server 2000 and is the premier application programming interface (API) for building collaborative solutions using Exchange. CDO in Exchange 2000 consists of three components:

- **CDO for Exchange 2000:** Used for building collaborative solutions that make use of e-mail, contact management, and scheduling.
- **CDO Workflow Objects for Exchange:** Used to build workflow and routing applications.
- **CDO for Exchange Management:** Used for creating and managing mailboxes and recipients.

Notes

For security reasons, scripts running on Microsoft Internet Explorer cannot access CDO.

See Also: *Exchange Server, Internet Information Services (IIS)*

collapsed backbone

An enterprise networking methodology in which the network backbone consists of a single device.

Overview

In a traditional network, local area networks (LANs) are multipoint connections connected using a backbone cable. For example, in a building, a fiber-optic backbone might run from floor to floor and connect with a hub in a wiring closet on each floor. In contrast, collapsed backbones make use of centralized switches, which provide virtual point-to-point connections for LAN connections. These switches are located in the same place as the network servers—in fact it was the move toward centralized location of network servers that helped drive the development of collapsed backbones.

In a typical collapsed backbone scenario, instead of having a hub for each floor located in that floor's wiring closet, a set of stackable Ethernet switches would be located in the equipment room in the basement, with individual cables running from this closet through vertical rises to wiring closets on each floor where hubs distribute connections to stations in work areas.

Advantages and Disadvantages

The advantages of using a collapsed backbone are that they eliminate the costs of backbone cabling installation, they require fewer devices, their equipment administration is more centralized, and they offer higher available bandwidth for each station. The disadvantages are that collapsed backbones generally are not feasible for use in more than one building, they require more cabling, they use more expensive devices, and they have a more limited distance capability.

See Also: *backbone, network*

collision

A condition that occurs when two or more computers on a network try to transmit signals over the same wire at the same time.

Overview

Collisions are inevitable on a network as long as there is more than one computer on the network. Handling collisions is one of the main functions of a network access method. For example, in Ethernet networks, collisions often occur when two or more stations attempt to place frames on the wire at the same time. To handle this situation, Ethernet uses the access method called Carrier Sense Multiple Access with Collision Detection (CSMA/CD).

When a station begins transmitting a signal and detects a collision, the station stops transmitting and issues a jam signal to tell the other station that a collision has occurred. Both stations then stop transmitting and wait a random length of time before retransmitting their signals. The amount of time the stations wait before retransmitting increases with the number of collisions occurring on the network.

See Also: *Carrier Sense Multiple Access with Collision Detection (CSMA/CD), collision domain, Ethernet*

collision domain

An area of a network where signals transmitted by different stations with that area can collide.

Overview

In Carrier Sense Multiple Access with Collision Detection (CSMA/CD) networks such as Ethernet, a collision can occur if two computers on the network attempt to transmit signals at the same time. When a collision occurs, the network is momentarily offline and no computers can communicate on it.

The larger the collision domain of an Ethernet network, the more computers present and the higher the probability of collisions occurring and negatively affecting network performance. When collision domains become too large, so many collisions occur that network communications become possible. As a result, it is important to segment Ethernet networks to keep collision domains small enough that the effect of collisions is minimized on the network.

Segmenting a collision domain can be accomplished using bridges, switches, routers, and other devices. For example, if two Ethernet hubs are connected directly to a third hub, the resulting local area network (LAN) is still only a single collision domain because only hub connections are used between segments of the network. But if the two hubs are directly connected to an Ethernet switch, you have two collision domains because the switch enables the two networks to function independently. Routers also segment networks into broadcast domains to prevent the occurrence of broadcast storms.

See Also: *broadcast domain, broadcast storm, Carrier Sense Multiple Access with Collision Detection (CSMA/CD), collision, Ethernet*

COM

Stands for Component Object Model, an object-based software architecture developed by Microsoft Corporation that allows applications to be built from binary software components.

See: *Component Object Model (COM)*

COM+

An extension of Microsoft Corporation's Component Object Model (COM).

Overview

COM was originally designed for building component-based applications to run on single systems. Distributed COM (DCOM) was an evolution of COM that enabled COM components to reside on different machines and communicate with each other over the network. COM+ takes DCOM a step further by providing services and features that enable large, distributed, multitier applications to be built for enterprise-wide systems and the Internet.

COM+ is part of the Microsoft Windows Distributed Network Architecture (DNA) programming paradigm. The COM+ that is supported by the Microsoft Windows 2000, Windows XP, and Windows .NET Server operating system platforms is basically COM plus Microsoft Transaction Server (MTS) and Microsoft Message Queue Server (MSMQ), minus some legacy COM functionality no longer needed. Some of the enhancements of COM found in COM+ include the following:

- Dynamic load balancing, which distributes client requests across multiple equivalent COM components
- Registration of COM+ objects that is cached in memory to speed up the process of locating and instantiating components
- In-memory database (IMDB), which provides quicker data access to applications by lowering overhead
- Publish and subscribe services, which provide an event mechanism enabling multiple clients to subscribe to published events and send notification to subscribers when events are fired
- Integration of Microsoft Message Queue Server (MSMQ) to support queued asynchronous calls issued to COM components, which let clients invoke methods on COM components using an asynchronous model for increased reliability over poor network connections and in disconnected usage scenarios
- Integration of Microsoft Transaction Server (MTS) into COM, which supports attribute-based programming, improvements in transactions, security and administration services, and improved interoperability with other transaction environments through support for the Transaction Internet Protocol (TIP)
- Inclusion of basic COM services in the COM+ runtime to simplify and speed up application development.

See Also: *Component Object Model (COM), Distributed Component Object Model (DCOM)*

COM component object

A compiled software component based on Microsoft Corporation's Component Object Model (COM) technology.

Overview

COM components generally refer to the physical files that contain the classes that define COM objects. COM components also include additional code, such as code to register the component in the registry and code for loading the component.

COM components can be written in many languages using tools such as Microsoft Visual Basic, Microsoft Visual J++, Microsoft Visual C++, and Microsoft Visual FoxPro. COM components that support Automation can be called by scripting languages such as Microsoft Visual Basic, Scripting Edition (VBScript) or Microsoft JScript.



COM component object. *In-process, local, and remote COM components.*

COM components can be run on an application server, a Web server, a Microsoft Transaction Server (MTS), or a client. COM components can be stand-alone applications or reusable software components, and they make the development of Web applications comparable to the development of system applications.

COM components interact with each other and with user applications in a client/server fashion. The client therefore uses the functionality of the server component by creating instances of classes that the server component provides and calling their properties and methods.

COM components can be designed to run in three different modes:

- **In-process:** The component executes in the calling application's process space.
- **Local:** The component executes in its own process space.
- **Remote:** The component executes in a process space on another machine.

An in-process COM component has the extension .ocx or .dll, while an out-of-process COM component (one running outside the calling application process) has the extension .exe. COM components can run on another machine in a manner transparent to the calling application by using the Distributed Component Object Model (DCOM).

When developing applications based on COM components, use in-process components to optimize the speed of object access but use out-of-process components to maximize thread safety.

See Also: *Component Object Model (COM)*

command

A method by which actions can be performed on a computer running Microsoft Windows by typing text into a command prompt window. The commands that are available depend on which version of Windows is used.

Overview

Examples of commands common to most Windows platforms include the Attrib command, Cacls command, Copy command, Dir command, and Diskcopy command. In addition to these Windows commands, some special commands are available only when certain networking services or protocols are installed. For example, if Transmission Control Protocol/Internet Protocol (TCP/IP) is installed on a computer running Windows, a number of TCP/IP commands are available, including the Arp command, Ping, Tracert, and Nbtstat.

Commands are useful for administering different aspects of a system or network using a command-line interface, such as a telnet connection or a command prompt. Commands are also often used in writing batch files that can perform a group of operations on a system or network service. You can run such a batch file directly, or you can schedule its operation for a predetermined time.

Finally, many Windows programs can be started in different ways from the command prompt using optional switches. For example, Windows Explorer can be run by typing explorer.exe from the command prompt. These programs are normally run using a graphical user interface (GUI), are started by desktop shortcuts, and are not usually referred to as commands.

See Also: *UNIX commands, Windows commands*

command interpreter

The underlying service or daemon that supports a command-line interface.

Overview

The command interpreter is a system process that allows users to type text commands into the command line or command prompt and execute them to perform various routines and manage system and networking resources. Traditional UNIX systems make heavy use of the command line, while MS-DOS, the legacy Microsoft operating system, is basically a command shell for running text-based commands to control operating system processes.

On Microsoft Windows 2000, Windows XP, or Windows .NET Server systems, users can open a command prompt window to issue text-based commands to the underlying command interpreter Cmd.exe. These text-based Windows commands represent only a subset of the full functionality of the GUI-based administration tools available on the Windows 2000, Windows XP, and Windows .NET Server platforms.

The command interpreter is sometimes referred to as the operating system shell, especially on UNIX platforms. Entering a command into the command interpreter is referred to as "working at the command line."

See Also: *command line, command prompt*

command line

A general name for any user interface that allows text-based commands to be entered and executed on a system. The term *command line* is popular in UNIX environments, but Microsoft Windows systems use *command prompt* to mean essentially the same thing.

See Also: *command interpreter, command prompt*

command prompt

A Microsoft Windows application that allows text-based Windows commands to be entered and executed.

Overview

The Windows command prompt provides a command-line interface (CLI) similar to those provided by UNIX systems. The command prompt can be used for running operating system tasks, configuring networking services, and even accessing resources and applications over the network. Many common administrative tasks can be performed from the command prompt, although the command prompt itself provides a more complex and less intuitive interface than the usual desktop graphical user interface (GUI) of Windows operating systems. However, administrators who have spent significant time working in UNIX networking environments often find the command prompt a more familiar paradigm for administering a Windows-based network.



```
Microsoft(R) Windows NT(TM)
(C) Copyright 1985-1996 Microsoft Corp.

C:\>
```

Command prompt. *The command prompt in Windows 2000.*

Notes

In Windows 2000, Windows XP, and Windows .NET Server, the command prompt application is Cmd.exe, located in the %SystemRoot%\system32 folder. In Windows Millennium Edition (Me), it is called the MS-DOS prompt, has the executable filename Command.com, and is in the \Windows folder. The Windows 2000, Windows XP, and Windows .NET Server versions can be configured using the Console utility in Control Panel.

For security reasons, should you wish as an administrator to disable the command prompt on a Windows 2000, Windows XP, or Windows .NET Server machine, you can accomplish this by either renaming Cmd.exe to something only you yourself are aware of, set NTFS file system (NTFS) permissions so that only Administrators can access it, or (not recommended) delete Cmd.exe entirely from the system.

See Also: *command interpreter*

Commerce Server 2000

Microsoft Corporation's platform for building and managing e-commerce solutions.

Overview

Commerce Server 2000 reduces the time it takes to develop and deploy complex e-commerce solutions. Commerce Server is based on Microsoft Site Server version 3 Commerce Edition (SSCE), and it builds on the strength of this earlier product. Commerce Server is part of the Microsoft Windows .NET Server family.

Commerce Server provides core services for managing your e-commerce site, including

- **Profile system:** Used to profile and manage customers and trading partners
- **Product catalog system:** Lets you manage millions of different products and find them quickly
- **Targeting system:** Lets you target customers with personalize one-on-one marketing
- **Business processing pipelines system:** Lets you customize your products to meet your customers' needs

In addition to these services, Commerce Server includes administration and development tools for building and managing your site, sample e-commerce sites you can use as templates and models, a data-warehousing decision-making system, help-desk customer support functionality, and much more.

For More Information

Find out more at *www.microsoft.com/commerceserver/*.

See Also: *.NET platform*

commercial service provider (CSP)

Internet service providers (ISPs), online service providers, telephone and cable network operators, and other companies.

Overview

CSPs provide software services such as community access to mail, news, chat, and conferencing services. By utilizing these services of a CSP, customers do not have to acquire licenses for the software the CSP provides.

See Also: *xSP*

Committed Information Rate (CIR)

A way of guaranteeing bandwidth in frame relay services.

Overview

Committed Information Rate (CIR) provides a way of guaranteeing minimum bandwidth for frame relay customers. Because customers on a frame relay network share the network, it is possible that service providers might oversubscribe the service—with the result that some customers receive insufficient bandwidth. Another situation where this can be a problem is if many customers try to access the frame relay network at the same time.

CIR guarantees that data throughput on frame relay connections will not drop below a previously agreed-upon contractual lower limit. However, CIR does permit short bursts of traffic to occupy greater amounts of bandwidth.

See Also: *frame relay*

Common Desktop Environment (CDE)

A graphical user interface (GUI) or desktop environment developed for UNIX systems.

Overview

Common Desktop Environment (CDE) was developed by IBM, Sun Microsystems, and Hewlett-Packard under the Common Open Software Environment (COSE) initiative. CDE is a paradigm that is widely used in the UNIX industry. CDE is based on various industry standards including the X Window System (X11) release 5, X/OPEN, OSF/Motif 1.2, and others.

CDE is designed to provide UNIX users with a simple and consistent desktop interface that includes

- Standard Windows-management features

- File-system browsing tools supporting multiple views
- Customizable user interface–management tools for changing backdrops, mouse and keyboard settings, and screen savers
- Extensive and easily accessed online help features
- Multiple workspaces for increasing available desktop area

See Also: *UNIX, X Window System*

Common Gateway Interface (CGI)

A mechanism by which a Web browser can request a Web server to execute an external application.

Overview

Common Gateway Interface (CGI) was developed in the UNIX networking environment to allow Web browsers to execute "gateway" applications on Web servers. These gateway programs are typically written either in a compiled language such as C or in an interpreted language such as Perl. CGI allows Web servers to run scripts or programs on the server and send the output to the client Web browser, thus turning the Web into a platform for running dynamic applications instead of merely presenting static information to clients.

Architecture

CGI programs are called "gateway" programs because the Web server passes the CGI request to the external program, which then runs as a separate process to process the input data, generate the results, and pass these results back to the Web server, which then returns them properly formatted in Hypertext Markup Language (HTML) to the client.

The main disadvantage of CGI is that each request must spawn a new CGI process and that, after the request is satisfied, the process is killed. Thus a Web server experiencing multiple simultaneous requests from clients will spawn multiple copies of the gateway process, each of which consumes memory and processing overhead. The fact that processes are terminated at the end of each request limits CGI to single-step Web applications and requires much ingenuity to handle data across a multistep user session.

Examples

CGI applications are often used as form handlers for Web forms, and are executed using a <FORM> tag embedded in the form document. When a Web client such as Microsoft Internet Explorer submits a form or otherwise passes information to a Web server using CGI, the Web server receives the information from the client and passes it to the gateway program for processing. The gateway program then returns the result of the processing to the server, which returns it to the Web browser as an HTML page. Here's a simple example:

```
<FORM METHOD=POST ACTION=
"http://www.northwind.microsoft.com/cgi-bin/
results.pl">
```

In this example, the Perl script results.pl in the cgi-bin directory functions as the form handler for processing the information submitted using the form.



Common Gateway Interface (CGI). *How CGI works.*

Notes

Although CGI was developed for UNIX-based systems, it is supported by most Web servers, including Microsoft Internet Information Services (IIS). Microsoft Internet Server API (ISAPI) is a set of server extensions for IIS that functions similarly to those of CGI but uses fewer resources. The main difference is that with CGI the system creates a unique process for every CGI request, but ISAPI extensions do not require separate processes. This makes ISAPI applications generally more responsive than CGI applications.

See Also: *Internet Server API (ISAPI), UNIX, Web server*

Common Information Model (CIM)

A schema for defining manageable network objects.

Overview

The Common Information Model (CIM) defines a set of schema for describing information collected for network and systems management purposes. CIM was developed by the Distributed Management Task Force (DMTF), formerly named the Desktop Management Task Force, as an extensible, object-oriented schema for managing information collected from computers, networking devices, protocols, and applications.

CIM supports management of two types of objects:

- **Hardware objects:** This includes router interfaces and disks.
- **Software objects:** This includes applications, application components, and services.

Another way of defining the different types of information that can be described by CIM is as follows:

- **Static information:** Examples include the capacity of a hard drive on a desktop computer or the specific applications installed on a server.
- **Dynamic information:** Examples include the current bandwidth being used on a port on a switch or router.

Uses

CIM is similar to the Simple Network Management Protocol (SNMP) and Desktop Management Interface (DMI) standards. However, unlike SNMP and DMI, CIM is able to manage the widest possible range of hardware and software systems. CIM also shows the relationships between the different hardware and software components of an enterprise network more completely, making it easier to troubleshoot complex distributed systems and applications.

CIM information that is collected can be shared between systems on a peer-to-peer basis. This information sharing allows network devices to not only be managed from a centralized management console but also to talk to one another to resolve problems as they arise.

CIM was designed by the DMTF to operate together with their Web-Based Enterprise Management (WBEM) initiative to provide a broad WBEM/CIM framework for managing resources across a network.

Architecture

CIM is based on an object-oriented programming model that allows inheritance to be used to grant subclasses the characteristics of their parent classes. CIM classes have the properties, methods, and associations typical of object classes. CIM supports both physical and logical objects and models these objects for purposes of network management applications. CIM is also extensible and allows vendors to define the features of their products using inherited subclasses. The fact that these subclasses are inherited from standard parent classes ensures that data collected from different vendors' systems will be compatible with the CIM standard.

CIM consists of two parts: a language definition specifying the constructs and methods that can be used to model network and system resources, and a set of schema that describes how specific types of resources will be represented.

CIM supports three kinds of schema:

- **Core schema:** These define general areas of network and system management, and core CIM classes are platform-independent.
- **Common schema:** These define specific areas of management.
- **Extension schema:** These define the management of vendor-specific technologies.

Notes

Microsoft Systems Management Server (SMS) 2 is capable of collecting CIM data from managed systems and exporting this data to other enterprise management applications, such as NetView from Tivoli Systems and Unicenter from Computer Associates.

See Also: *Distributed Management Task Force (DMTF), Web-Based Enterprise Management (WBEM)*

Common Internet File System (CIFS)

A public version of the Server Message Block (SMB) file-sharing protocol that has been tuned for use over the Internet.

Overview

Common Internet File System (CIFS) is a remote file system access protocol that enables groups of users to collaborate and share documents over the Internet or within corporate intranets. CIFS is an open, cross-platform technology that is based on the native file-sharing protocols of Microsoft Windows platforms. It is supported by other platforms such as UNIX.

CIFS has been viewed as a possible replacement for both the File Transfer Protocol (FTP) and the Network File System (NFS) file system protocols. CIFS supports encrypted passwords and Unicode filenames, and it can be used to mount a remote file system as a directory or drive on the local machine. CIFS also includes features not supported by NFS, including write-ahead and native support for locks. Microsoft Corporation's Distributed file system (Dfs) is covered as part of the CIFS specification. Microsoft has submitted CIFS to the Internet Engineering Task Force (IETF). CIFS client and server software is available for the Windows 2000 operating system platform.

See Also: *Server Message Block (SMB)*

Common Name Resolution Protocol (CNRP)

A proposed Internet Engineering Task Force (IETF) standard for a protocol to replace Uniform Resource Locators (URLs) with a simpler, more natural scheme for navigating the Web.

Overview

The existing Internet naming systems (domain names and URLs) are not particularly user friendly, as anyone knows who has ever picked up the phone and heard someone ask, "What is the URL for [name of Web page]?" After tediously repeating a long string of characters and slashes, you begin to wish the Internet community could come up with something different.

Enter the proposed Common Name Resolution Protocol (CNRP), an initiative of Network Solutions, AT&T, and other companies. Using CNRP, users could enter the name of a company into their browsers to reach the company home page, then enter a product name to reach the page for a particular product, and enter "2000 Sales Figures" to retrieve a document with these figures. Areas where CNRP might excel include government and public information portals and corporate intranets. Wireless Internet access may also benefit by eliminating the need to enter long, complex URLs on small keypads in order to access specific content on the Internet.

Architecture

CNRP basically runs on top of Hypertext Transfer Protocol (HTTP) as an Extensible Markup Language (XML)–encoded service. A user could enter "Go:2000 Sales Figures" into the browser's address bar, and the browser would encode this request in XML and forward it to a CNRP name server. The name server would then return the URL of the requested page to the browser, which would then request the actual content from where it is located on the Internet or corporate intranet.



Common Name Resolution Protocol (CNRP). *How the CNRP works.*

Current Web browsers do not support CNRP, and until they do, users who want to use this service will have to download a plug-in for their browser to provide this functionality. Network Solutions offers a free, downloadable CNRP plug-in, as do several other vendors. Whether CNRP will become widely used will depend largely on social inertia (most people are used to URLs despite being fed up with them) and on whether CNRP is natively supported by the next release of Microsoft Internet Explorer and other Web browsers.

See Also: *Uniform Resource Locator (URL)*

Common Object Request Broker Architecture (CORBA)

A component architecture that specifies technologies for creating, distributing, and managing component programming objects over a network.

Overview

Common Object Request Broker Architecture (CORBA) was developed by the Object Management Group and its member companies and was designed to provide interoperability between applications in heterogeneous distributed environments.

In a CORBA environment, programs request services through an object request broker (ORB), which allows components of distributed applications to find each other and communicate without knowing where applications are located on the network or what kind of interface they use. ORBs are the middleware that enable client and server programs to establish sessions with each other, independent of their location on the network or their programming interface.

The process of a client invoking a call to an application programming interface (API) on a server object is transparent. The client issues the call, which is intercepted by the ORB. The ORB takes the call and is responsible for locating a server object that is able to implement the request. When it has located such an object, the ORB invokes the object's method and passes it any parameters submitted by the client. The results are then returned to the client. ORBs communicate among themselves using the General Inter-ORB Protocol (GIOP) or the Internet Inter-ORB Protocol (IIOP) so that any ORB can fulfill any client request on the network.

Uses

CORBA is primarily used in the UNIX world as an underlying architecture for developing distributed applications. CORBA is not natively supported by Microsoft Windows, which uses its own distributed object management architecture called Distributed Component Object Model (DCOM). The OMG has indicated, though, that it plans to include support for Microsoft's new C# programming language in CORBA, which should promote interoperability between UNIX applications using CORBA and Web services developed under Microsoft Corporation's new .NET platform.

For More Information

Find out more about CORBA from the Object Management Group at *www.omg.org.*

See Also: *C#, Distributed Component Object Model (DCOM), .NET platform, UNIX*

community

A group of hosts managed by Simple Network Management Protocol (SNMP) running SNMP agents.

Overview

Communities provide a simple way of partitioning and securing a network for SNMP management. SNMP agents and management systems use community names as the mechanism for authenticating SNMP messages. All SNMP agents belonging to the same community share the same community name, which functions as a kind of shared password for those agents so that they can be recognized by the SNMP management program and other agents. SNMP messages sent by SNMP management systems to a specific community are accepted only by hosts configured to belong to that community. If an SNMP agent program receives an SNMP message with a community name that it is not configured to recognize, it typically drops the message and sends a trap message to the SNMP management program indicating that a message was not authenticated on that machine.

Notes

An agent can be a member of one or more communities. By default, all agents belong to the public community. If all community names including public names are removed from an SNMP-managed host, the host will accept all SNMP messages sent to it.

See Also: *agent, Simple Network Management Protocol (SNMP)*

Competitive Local Exchange Carrier (CLEC)

A telco that competes with incumbent telcos under the terms of the Telecommunications Act of 1996.

Overview

Before 1996, the U.S. telecommunications market was dominated by a small group of telcos called Incumbent Local Exchange Carriers (ILECs) or Regional Bell Operating Companies (RBOCs) and a group of long-distance carriers or inter-exchange carriers (IXCs). The Telecommunications Act of 1996 was designed to open things up by allowing new companies to compete with the established ones in both the local and long-distance markets.

Competitive Local Exchange Carriers (CLECs) generally compete with ILECs for provisioning the local loop market, but unlike ILECs, which focus more on residential and large enterprise customers, many CLECs have targeted the small to mid-sized business market that has traditionally been poorly served by ILECs. CLECs generally offer high-speed data services and often focus on specific niche services such as Digital Subscriber Line (DSL)—these are often known instead as DSL providers—but many CLECs also offer a much wider spectrum of services including voice (local and long-distance), high-speed Internet access (using DSL), virtual private networks (VPNs), and business-to-business data links.

CLECs come in many types and range from smaller start-ups that piggyback on ILECs and purchase services wholesale from them for reselling purposes, to larger start-ups building out new fiber from their own switching centers, to large IXCs such as AT&T (which acquired Teleport, a pioneering CLEC) and MCI WorldCom (which bought MFS, another pioneer CLEC) competing in the local telco market.

Like ILECs, CLECs are generally concerned about provisioning buildings, not individual users. However, some CLECs are also getting into the Building Local Exchange Carrier (BLEC) markets by offering to-the-desktop services for building-out wiring and deploying services not just to buildings but also within them.

Advantages and Disadvantages

One of the advantages that CLECs have over traditional ILECs is that, instead of competing directly with ILECs by building switching centers, building out wiring to customer premises, and purchasing expensive Class 5 telephone switches to handle all-important voice traffic, they can save implementation costs considerably by colocating their switching equipment at ILEC COs, sharing the existing local loop infrastructure owned by ILECs, and focusing on purchasing more modern, less expensive switching gear dedicated to specific uses such as DSL. Using less expensive and more modern equipment theoretically means the CLEC can offer its services at a discount compared to the ILEC, but CLECs also have to pay the ILECs for the right to use their services, including line provisioning and maintenance, switching interconnects, and colocation services.



① CLEC provisioning DSL services

② CLEC provisioning ATM over T1

Competitive Local Exchange Carrier (CLEC). *Two ways CLECs can provision customers with voice and data services.*

On the other hand, contracting CLECs to provision telecommunication services for your company instead of ILECs has an element of risk. This is evidenced by the changing nature of the CLEC market, in which some startups have failed and others have been acquired, and by litigation initiated by some CLECs against ILECs. An example is Pronto, a project of mega-bell SBC Communications, which is building out thousands of neighborhood DSL remote terminals to shorten customer DSL connections, thereby improving DSL reliability and data rates. CLECs that want to provide their own DSL services to the same customers have complained to the Federal Communications Commission (FCC) that Pronto cuts them out of the loop because they cannot service Pronto customers using DSLAMs colocated at SBC's COs. Other RBOCs are contemplating similar projects, which could undercut the operations of many CLECs.

Implementation

Because the ILECs own the infrastructure of the last-mile (local loop) wiring serving residential and business markets in the United States, the Telecommunications Act required ILECs to open up use of the local loop to CLECs, allow CLECs to colocate their equipment at the ILEC central offices (COs), and allow CLECs to lease use of the local loop from the ILECs that provision it. CLECs can architect to provision services in many ways, two of which are shown in the diagram.

The top part of the diagram shows a DSL modem at the customer premises that connects the customer's local area network (LAN) over the local loop to a DSL Access Multiplexer (DSLAM) colocated by the CLEC at the CO of the customer's incumbent telco. The CLEC's DSLAM is connected to the ILEC's switching backbone to provide the customer with voice and data services. Such an arrangement is typical of a CLEC that functions as a DSL provider.

The bottom part shows an Integrated Access Device (IAD) at the customer premises. The IAD converts the Internet Protocol (IP) packets of the customer's Ethernet LAN to Asynchronous Transfer Mode (ATM) cells for transmission over the T1 line to an ATM switch colocated by the CLEC at the ILEC's CO. In this case, the ILEC is responsible for provisioning the T1 for the CLEC and acts as a wholesaler of T1 services toward the ILEC. The CLEC's ATM switch then filters the voice and data traffic from the customer. The voice traffic is routed either to the ILEC's telephone switch or directly to an IXC, while the data traffic is routed to an ISP for Internet access or to an IXC for long-haul wide area network (WAN) connections to branch offices.

Marketplace

The CLEC landscape is constantly changing, but some of the bigger players include Covad Communications Company (*www.covad.com*), Intermedia Communications (*www.intermedia.com*), Cogent Communications (*www.cogentco.com*), and others. Despite these big players and the large number of smaller CLECs on the market, analysts estimate that CLECs currently have less than 10 percent of the local telecom market, with more than 90 percent still in the hands of the incumbent ILEC/RBOCs.

CLECs that provision DSL services typically pay RBOCs about $15 to $25 per month to use their local loop connection for deploying such services, the cost of which must be recovered when they resell such services to businesses and consumers, typically at $40 to $60 per month. A newer technology called line sharing may lower the cost for CLECs to lease lines from ILECs, and the savings might be passed on to consumers.

Prospects

Times have gotten tough in the telecommunications industry in general at the start of the new millennium. After the dot-com crash of 2000, sources of venture capital for new telecom startups has dried up, leaving some CLECs in financial difficulty (the same difficulties are faced by 3G wireless vendors and other segments of the telecom sector). Although a few CLECs have failed and others have been acquired, there were still about 200 different CLECs in the marketplace in 2001, with a market capitalization of about $6 billion.

One aim of the Telecommunications Act of 1996 was to open the doors for cable TV companies and utilities to begin competing with ILECs for residential and business voice and data services. When the act was passed, these companies were slow to build out these services, and a diverse host of CLECs appeared to compete in the residential, office, and metropolitan marketplaces. Now, however, cable companies and utilities are beginning to deploy high-speed data services in large rollouts, and so now many CLECs face competition on two fronts instead of from just the ILECs. Finally, FCC rulings have begun to come down on the side of large carriers, which may squeeze many smaller startups out of the marketplace or lead to their being acquired by big carriers such as AT&T and SBC.

The shakeout in the CLEC market and its uncertain future makes it advisable for businesses to use due diligence in investigating the financially viability of CLECs before deploying mission-critical WAN services just to save costs over similar services offered by RBOCs. Many enterprise network architects believe that leasing reliable services for WAN and Internet access from large RBOCs is more important than saving a few dollars by using CLECs. On the other hand, some e-commerce companies have chosen to go with CLECs because they can typically provision services much faster than traditional RBOCs. CLECs that are building out their own infrastructure (own their own fiber) are probably more likely to succeed in the long term. Enterprise network architects should also consider purchasing redundant services from different carriers to provide fault-tolerance for their WAN connections, but they should realize that as the CLEC market consolidates, their options may narrow.

For More Information

You can find industry news on CLECs at *www.clec.com* and *www.clec-planet.com*. A current list of CLECs can be found at *www.dslreports.com/clecs*.

See Also: *carrier, Digital Subscriber Line (DSL), Incumbent Local Exchange Carrier (ILEC), inter-exchange carrier (IXC), line sharing, local loop, Regional Bell Operating Company (RBOC), telco*

complete trust model

A domain model in Microsoft Windows NT in which every domain trusts every other domain with two-way trusts.



Complete trust model. *Shown for Windows NT.*

Overview

The complete trust model is rarely implemented in Windows NT–based networks unless the motivation for using Windows NT is being driven from the bottom up. For example, if a number of individual departments start implementing domains, the company might soon find itself implementing the complete trust model in order to make administration of these domains more efficient. This model also might be used in a situation in which two companies using Windows NT merge into a single company. Because of the large number of trusts in a complete trust model, there are additional security concerns about who is able to administer what. The following table outlines the pros and cons of using this domain model.

Advantages and Disadvantages of Using the Complete Trust Model

Advantages	*Disadvantages*
Scalable to any number of user accounts.	Complex to set up and administer.
Suitable for merging companies or organizations with no central MIS department.	Multiple local groups must be created in each resource domain.

Notes

When you upgrade a Windows NT network based on the complete trust model to a Windows 2000 or Windows .NET Server network, you can maintain the relative independence of each domain by migrating each domain to be the root domain of a domain tree. Each domain tree would have a single domain, namely the root domain. Two-way transitive trusts can then be established between the trees to form a domain forest.

See Also: *multiple master domain model, single domain model, single master domain model*

Component Load Balancing (CLB)

A Microsoft clustering technology supported by Microsoft Windows 2000 and Windows .NET Server Server and provided by Microsoft Application Center 2000.

Overview

Component Load Balancing (CLB) is a Microsoft clustering solution that is designed to increase the availability and reliability of distributed applications developed using Microsoft COM+ technologies. A CLB cluster consists of a group of up to 16 nodes (servers) running a distributed COM+ application whose components are distributed across the cluster. A CLB cluster is connected together by a network and is managed by Application Center 2000. When one node in a CLB cluster fails, its workload is distributed to the remaining nodes and the COM+ application keeps running.

Implementation

CLB is usually used in conjunction with other forms of clustering such as Network Load Balancing (NLB) and Microsoft Cluster Services (MCSC) for Microsoft Windows 2000 and Windows .NET Server Enterprise Server edition. This scenario is often used for farms of Web servers running mission-critical Web applications. Typically, NLB is used to handle load balancing of Web servers at the front-end, while CLB load balances COM+ application logic in the middle tier and MCSC provides clustering for back-end database servers. Application Center 2000 is then used to manage the CLB middle tier of the Web farm.


GbE
switch
Database
servers
Internet
Firewall
Switch
Switch
COM+ app
servers
RAID5
shared
storage
Back-end
Web servers
Mid-tier
Front-end
Key
NLB Cluster
CLB Cluster
MCSC Cluster

Component Load Balancing (CLB). *Using CLB to provide high reliability and availability for distributed COM+ applications.*

To distribute the load across the nodes of the CLB cluster, CLB uses round-robin techniques and polling algorithms based on server response time. Because CLB uses frequent polling, be sure to implement your CLB cluster on a fast network (100 megabits per second [Mbps] or faster).

See Also: *Application Center, clustering*

Component Object Model (COM)

An object-based programming architecture developed by Microsoft Corporation that allows applications to be built from binary software components.

Overview

Component Object Model (COM) is both a set of specifications for building application components and a group of underlying services for supporting these components. COM defines a standard method for building components and specifies what these components will look like at the binary level. Because it is a binary standard, COM is language-neutral and COM components can be written using a variety of programming languages including C++, Visual Basic, Java, COBOL, SmallTalk, and other languages. COM also has the following features:

- Support for object-oriented programming features including encapsulation, inheritance, and polymorphism.
- Location transparency, which allows COM components to be moved from one system to another.
- Portability, which lets you port COM applications to other operating system platforms.
- Code reuse, the result of encapsulation of COM functionality and a way to speed up application development.
- Loose coupling, which lets you replace components with new ones that have similar interfaces for accessing them.
- Stable version transitioning, which lets you upgrade some components within an application without breaking the application.

History

Microsoft released an earlier technology, Object Linking and Embedding (OLE), in 1991. OLE enabled functionality from one application to be embedded into another application. For example, a Microsoft Excel spreadsheet could be embedded into a Microsoft Word document and still maintain its spreadsheet functionality. OLE used an underlying technology called Dynamic Data Exchange (DDE) that was complicated in its operation.

In 1995, OLE 2 was released, which replaced DDE with COM as an underlying architecture for OLE. It was soon realized that COM had more uses than embedding one document within another, and COM became the fundamental technology while OLE withdrew to the background. COM has continued to evolve, and its present version is called COM+, which is discussed in a separate article in this chapter.

Implementation

The basic unit of COM is the COM component object, a binary programming object that complies with the COM standards. COM objects can be implemented as either executable (.exe) files or dynamic-link libraries (DLLs) and can function in one of two roles: COM servers (providers) and COM clients (consumers). COM servers and clients interact with each other by using COM interfaces.

A COM interface is a set of methods by which a COM object exposes its functionality to other COM objects. COM interfaces allow COM objects to invoke one another through the methods and properties residing in these interfaces. COM interfaces consist of groups of related functions implemented by the COM class. An interface is basically a table of pointers to functions that are implemented by the object. The table represents the interface, and the functions to which the table points represent the methods of that interface. COM objects can expose multiple interfaces. Each interface has its own unique interface ID (IID), and COM interfaces begin with the letter "I." For example, IUnknown is an important COM interface that must be included in every COM object. IUnknown provides reference counting and interface querying mechanisms and allows navigation to all other interfaces exposed by COM objects.

When COM-based applications are written, COM components are identified by globally unique identifiers (GUIDs), a 16-byte (128-bit) alphanumeric string that is uniquely generated using the current data and time and other information. COM component objects must be registered in order for location transparency to work. You can manually register a COM component object using Regsrv32.exe and other tools.

COM also includes a set of COM services implemented as Win32 library routines (DLLs). These DLLs are used to create new instances of COM components, find and keep track of the location of COM component objects, and perform remote procedure calls (RPCs) for communicating between component objects.

Notes

An alternate component object technology found primarily in the UNIX world is Common Object Request Broker Architecture (CORBA).

For More Information

Learn more about COM at the Microsoft COM site at *www.microsoft.com/com.*

See Also: *ActiveX, COM+, COM component object, Distributed Component Object Model (DCOM), globally unique identifier (GUID), object linking and embedding (OLE)*

CompTIA

Stands for Computing Technology Industry Association, a computer industry trade association formed in 1982.

See: *Computing Technology Industry Association (CompTIA)*

computer account

An account in the Active Directory directory service of Microsoft Windows 2000 and Windows .NET Server that signifies that a particular computer is a part of a Windows 2000 or Windows .NET Server domain.

Overview

Windows 2000 and Windows .NET Server domain controllers can store three types of accounts: user accounts, group accounts, and computer accounts. Windows 2000 and Windows .NET Server use computer accounts to determine whether a particular system that a user is employing to attempt to log on to the network is part of the domain. When the NetLogon service running on a client computer connects to the NetLogon service on a domain controller in order to authenticate a user, the NetLogon services challenge each other to determine whether they both have valid computer accounts. This allows a secure communication channel to be established for logon purposes.

In order for a Windows 2000, Windows XP, or Windows .NET Server machine to join a domain, the machine must have a computer account created for it in Active Directory. There are two ways to create this account:

- Use Active Directory Users and Computers in Windows 2000 and Windows .NET Server to create a computer account for the machine, and then have the machine join the domain.
- Use an administrator account to create a computer account while installing Windows 2000, Windows XP, or Windows .NET Server on the machine.

Notes

Machines running Windows 95, Windows 98, and Windows Millennium Edition (Me) can participate in domain authentication, but they do not have computer accounts in Active Directory. This is why the logon box for a Windows 95 or Windows 98 machine has a hard-coded domain name and can log on to only one domain.

If you reinstall Windows 2000 on a machine, you must delete the old computer account and create a new computer account, even if the machine has the same name as before.

See Also: *account*

Computer Browser service

In Microsoft Windows 2000, Windows XP, or Windows .NET Server, a service responsible for enabling the browsing of network resources using Network Neighborhood and Windows Explorer.

Overview

The Computer Browser service simplifies the user task of locating and accessing network resources by eliminating the need for users to remember Universal Naming Convention (UNC) paths or other network syntax and by eliminating the need for all computers on the network to maintain their own list of all available network resources.

The Computer Browser service maintains a distributed series of lists called browse lists that contain information about shared resources available on the network.

Different computers on the network have different roles. These computers include the following:

- **Domain master browser:** Collects and maintains the master browse list for the domain, and synchronizes this list with other domain master browsers in different domains. In a Windows NT network, the domain master browser must be the Primary Domain Controller (PDC).
- **Master browser:** Collects and maintains the master browse list for the domain and distributes this list to backup browsers in the domain. This can be a computer running Windows 2000, Windows XP, Windows .NET Server, Windows NT, Windows 95, Windows 98, or Windows for Workgroups.
- **Backup browser:** Maintains copies of the browse list received from the master browsers and distributes this list to any network client requesting a network resource. This can be a computer running Windows 2000, Windows XP, Windows .NET Server, Windows NT, Windows 95, Windows 98, or Windows for Workgroups.
- **Potential browser:** Any computer on the network configured so that it can assume the role of a master browser or backup browser if required. This can be a computer running Windows 2000, Windows XP, Windows .NET Server, Windows NT, Windows 95, Windows 98, or Windows for Workgroups.
- **Nonbrowser:** Any computer that cannot be a browser but can share resources with the network.


Master browser
Server information for browse list
Request for browse list information
Browse list
File server
Backup browser
1
Request for browse list
List of backup browsers
2
5
Request for share list
3
Request for browse list
Share list
6
Browse list
4
Client

Computer Browser service. *How the Computer Browser service works.*

When a client tries to access a shared resource on the network, such as a shared folder on a file server, it first contacts the master browser for a list of backup browsers. Then it contacts a backup browser for a copy of the browse list. When the client has the browse list, it contacts the file server for a list of shares, and then connects to the desired share.

Notes

The Workstation service and Server service must be started for the Computer Browser service to function.

See Also: *browse list, browsing*

Computer Management

A Microsoft Windows 2000, Windows XP, and Windows .NET Server management console that provides a single integrated desktop tool for managing local and remote machines.



compmgmt - [Computer Management (Local)\Storage\Disk Management]
Action
View
Computer Management (Local)
System Tools
Local User Manager
System Information
Services
Group Policy Editor
File Service Management
Event Viewer
Device Manager
Certificate Manager
Storage
Logical Drives
Disk Management
Server Applications and Services
Default SMTP Site
Indexing Service on Local Mac
DNS Manager
Internet Information Services
Disk 0
Basic
4.77 GB
Online
(C:)
1.47 GB N
Healthy (S.
(D:)
753 MB
Healthy
251 M
Free S
New Volu
1.95 GB N
Healthy
377 MB
Unalloca
CDRom 0
CDRom (E:)
619 MB
Online
TN9902 (E:)
619 MB CDFS
Healthy
Unallocated
Primary Partition
Extended Partition
Free Space
Logica

Volume	Layout	Type	File System	Status	Capacity
(C:)	Partition	Basic	NTFS	Healthy (System)	1.47 GB
(D:)	Partition	Basic		Healthy	753 53
New Volume (H:)	Partition	Basic	NTFS	Healthy	1.95 GB
TN9902 (E:)	Partition	Basic	CDFS	Healthy	618 MB

Computer Management. *A typical Computer Management console.*

Overview

Computer Management combines a number of administrative utilities from Windows NT with additional Windows 2000, Windows XP, and Windows .NET Server tools to provide an easy way of viewing and managing properties of any computer running Windows 2000, Windows XP, or Windows .NET Server on the network. Using Computer Management, an administrator can perform the following actions on local and remote machines:

- Create and manage shares
- Display a list of connected users
- Manage services such as Dynamic Host Configuration Protocol (DHCP) and Domain Name System (DNS)
- Start and stop system services
- Configure properties of storage devices
- Monitor system events and application errors
- Display device settings and add new device drivers

To use Computer Management for modifying administrative settings, you must be a member of the Administrators group.

See Also: *Microsoft Management Console (MMC)*

computer name

For computers running Microsoft Windows, a name that identifies a computer on the network.

Overview

Computer names can be up to 15 characters in length. In Windows NT, Windows 95, and Windows 98, you specify a computer's name using the Network utility in Control Panel. (In Windows 2000, Windows XP, and Windows .NET Server, use the Network Identification tab of the System utility in Control Panel.) The computer must be restarted if its name is changed. This name is used by services that perform NetBIOS name resolution on the network, such as the Windows Internet Name Service (WINS). Computer names provide a friendly way of accessing network resources without having to remember complex numerical addresses such as IP addresses.

A hidden 16th character is appended to the computer name to form the NetBIOS name for NetBIOS-aware networking services on the machine. Each NetBIOS-aware service has a different NetBIOS name, some of which are based on the name of the computer and others of which are based on the name of the domain in which the computer resides.

Notes

Give friendly names, derived from some common source such as *A Midsummer Night's Dream*, to groups of computers offering related services. For example, you could call your servers Puck, Oberon, and Titania. This makes it easy to remember that these computers all belong to the same group.

computer-telephony integration (CTI)

A general term describing the integration of computer and telephone technologies.

Overview

By joining computer systems with switched telephone services, users can access advanced functions such as automatic incoming call routing, call display, and power dialing. For example, a computer can use computer-telephony integration (CTI) to issue commands to a telephone switch to control call routing of calls.

CTI applications generally fall into one of two categories:

- **Call-control applications:** Allow computers to dial numbers, establish conference calls, and other functions. The computer essentially replaces the touch-tone telephone keypad.
- **Media-processing applications**: Deal with more complex issues, such as voice recognition, speech synthesis, and converting fax messages to e-mail. These applications pursue the goal of completely integrated unified messaging in which voice, fax, e-mail, and video conferencing features are combined.

CTI is made possible on Microsoft Windows platforms by operating system application programming interfaces (APIs) such as Microsoft Corporation's Telephony Application Programming Interface (TAPI). The range of products and technologies that support CTI continues to evolve. Cross-platform, vendor-neutral standards have not yet been established.

Computing Technology Industry Association (CompTIA)

A computer industry trade association formed in 1982.

Overview

The Computing Technology Industry Association (CompTIA) currently has more than 7500 members. CompTIA membership includes resellers, value-added resellers (VARs), distributors, manufacturers, and training companies in the United States and Canada. The goals of CompTIA are to foster professional competence and business ethics among its members and throughout the computer industry. CompTIA provides its members with educational opportunities, a professional network, and a forum for the development of ethical, professional, and business standards in the computing industry. A number of committees meet to consider issues such as software licensing and electronic warranty forms.

For More Information

Visit the CompTIA online at *www.comptia.org.*

COMTI

Stands for COM Transaction Integrator, a component of Microsoft SNA Server version 4 that provides client applications with access to two popular mainframe transaction processing (TP) environments, Customer Information Control System (CICS) and Information Management System (IMS).

See: *COM Transaction Integrator (COMTI)*

COM Transaction Integrator (COMTI)

A component of Microsoft SNA Server version 4 that provides client applications with access to two popular mainframe transaction processing (TP) environments, Customer Information Control System (CICS) and Information Management System (IMS).

Overview

COM Transaction Integrator (COMTI) works in conjunction with Microsoft Transaction Server (MTS), making CICS and IMS programs appear as MTS components that can be used with other MTS components to build distributed applications. COMTI includes both a Microsoft Windows NT Server run-time environment and a development tool called Component Builder, which can import mainframe COBOL code and automatically generate an object compatible with MTS. This lets developers program in the visual, object-oriented environments they are accustomed to, allowing them access to host transactions without needing to learn the intricacies of Systems Network Architecture (SNA).

See Also: *SNA Server, Systems Network Architecture (SNA)*

concurrency

A term referring to the simultaneous access to a network resource by more than one client.

Overview

Concurrency is an important issue in the licensing of a server operating system or application. For example, the Per Server licensing mode for Microsoft Windows NT Server is based on concurrency. If you purchase 10 client access licenses (CALs) for your Windows NT Server, a maximum of 10 concurrent connections can legally be formed with that server for accessing network resources.

Notes

Some products, such as Microsoft Outlook 98, do not support concurrent access. In other words, you cannot install a central copy of Outlook 98 on a server and have thin clients run this program from the centralized location. Instead, you must install one copy of Outlook 98 on each client that needs to run it.

connected network (CN)

In Microsoft Message Queue (MSMQ) Server terminology, a name for a collection of computers in which any two computers can directly communicate.

Overview

Computers in the same connected network must be running the same network protocol. A connected network (CN) is essentially a label describing how MSMQ servers are related in an enterprise. CNs are logical groupings of computers that can communicate directly using MSMQ messages. When you install an MSMQ server, you specify a connected network for each network address on the server.

When you specify connected networks for your MSMQ enterprise, it is a good idea to use meaningful labels so that administrators can easily select a connected network from a list when they need to override the default connected network settings.

connection

A link between two computers for the purpose of exchanging information.

Overview

An example would be a Microsoft Windows NT Workstation, Windows 95, or Windows 98 client computer accessing a shared folder or printer on a Windows 2000 server. The term *connection* is also used to describe the establishment of communication over a WAN link, as in using a dial-up connection over a modem.

When a client computer tries to connect to a server, the success or failure of the attempt can depend upon whether

- The server has shared the resource that the client wants to connect to
- The client has been properly authenticated or has permission to access the resource
- The client is properly licensed to connect to the server, and free licenses are available

See Also: *client access license (CAL), license*

connectionless protocol

Any transport layer protocol that relies on broadcast packets instead of directed packets.

Overview

Connectionless protocols can only offer “best-effort” delivery and cannot guarantee that packets will arrive in the correct order or even at all. Connectionless protocols cannot guarantee delivery of packets. Instead, reliability of packets is handled by the application itself or some higher layer of the protocol stack.

An example of a connectionless protocol is the User Datagram Protocol (UDP), which is part of the Transmission Control Protocol/Internet Protocol (TCP/IP) protocol suite. UDP provides connectionless services for delivering small packets of information commonly called datagrams. Another connectionless transport layer protocol is the Appletalk Transaction Protocol (ATP), part of the AppleTalk suite of protocols.

Notes

The term *connectionless* is also used to describe any delivery mechanism where complete addressing information (the address of the source and the address of the destination) is included in every packet. Packets are then placed on the network and are delivered to their destination independently, sometimes taking different routes and arriving in a mixed-up order that needs to be sorted out using packet numbers.

In this more general context, we can also examine protocols at other layers such as the network layer and data link layer. Most local area network (LAN) protocols at these layers are connectionless. For example, at the network layer we have IP, Internetwork Packet Exchange (IPX), Datagram Delivery Protocol (DDP), which is part of the legacy AppleTalk protocol suite, and DECnet Routing Protocol (DRP), which is part of the legacy DECnet protocol suite, all connectionless. At the datalink layer we have Ethernet, Token Ring, Fiber Distributed Data Interface (FDDI), and others, again all connectionless. An example of a data-link layer protocol that is connection-oriented instead of connectionless is Asynchronous Transfer Mode (ATM).

See Also: *connection-oriented protocol, protocol*

Connection Manager Administration Kit (CMAK)

A wizard-based tool for creating custom connectivity solutions, and a component of Internet Connection Services for Microsoft Remote Access Service (RAS).

Overview

The Connection Manager Administration Kit (CMAK) is used to customize the Microsoft Connection Manager (CM) client component. Internet service providers (ISPs) can use this tool to customize dial-up installation packages for their customers. Customization features include

- Animated logon screen, which can include a custom logo
- Desktop icons
- The language the dialer displays to the customer
- Support numbers and help files
- Various connect actions that the dialer performs when dialing, such as shutting down applications or downloading files

connection-oriented protocol

Any transport layer protocol that establishes a connection first in order to reliably send packets over the network.

Overview

Connection-oriented protocols guarantee delivery of packets by making use of acknowledgments and retransmission of data. Connection-oriented protocols are used primarily for reliable delivery of large packets of data, as opposed to the unreliable connectionless protocols that are used to deliver small datagrams.

An example of a connection-oriented protocol is TCP, which is part of the Transmission Control Protocol/Internet Protocol (TCP/IP) protocol suite. The TCP protocol uses a TCP three-way handshake to establish a connection between two hosts on a network. During session establishment, the hosts negotiate the TCP window size, segment size, and other information needed to ensure reliable and efficient communication. A TCP connection is terminated using a similar handshake procedure. Another example of a connection-oriented transport layer protocol is Sequenced Packet Exchange (SPX), part of the NetWare suite of protocols. The legacy network service provider (NSP) protocol of the DECnet suite of protocols is also a connection-oriented transport layer protocol.

Notes

At lower Open Systems Interconnection (OSI) levels such as the network layer and data link layer, most local area network (LAN) protocols are connectionless instead of connection-oriented. Asynchronous Transfer Mode (ATM) is an exception and is connection-oriented. In ATM a virtual circuit (data pathway) is first established prior to sending any data. Instead of addressing data packets (actually cells) with source and destination addresses as in a connectionless protocol, ATM assigns the circuit number to the cells to ensure they reach their destination. Because circuit numbers are much smaller than network addresses, connectionless protocols such as ATM have less overhead than connection-oriented protocols such as IP or Ethernet.

See Also: *connectionless protocol, protocol*

connection pooling

A technique for optimizing Active Server Pages (ASP) applications running on Microsoft Internet Information Server (IIS) version 4 and Internet Information Services (IIS).

Overview

Connection pooling allows more efficient implementation when connecting ASP front-end applications to a back-end database. Connection pooling involves the pooling of open database connectivity (ODBC) connections to reduce the frequency at which ODBC connections need to be opened and closed on heavily accessed servers. Connection pooling improves ASP performance for ODBC-enabled Web applications and provides a graceful way to manage connection timeouts.

To use ODBC connection pooling on IIS, perform the following steps:

1. Configure the database driver using ODBC in Control Panel.
2. Enable connection pooling in the Microsoft Windows NT registry.
3. Open individual connections in your Microsoft ActiveX Data Objects (ADO) code right before data access is needed for an ASP page and release connections as soon as the data has been accessed.

When connection pooling is enabled, the ODBC driver will check the connection pool for idle connections it can reuse before creating a new connection in response to an ODBC request. When connections are released, they are returned to the connection pool instead of being closed.

Notes

You can control the amount of time an idle connection remains in the pool using the CPTimeout registry setting, which has a default setting of 60 seconds.

See Also: *Active Server Pages (ASP)*

connectivity server

A computer running Microsoft Exchange Server that is dedicated for routing messages to other sites and foreign mail systems using Exchange connectors.

Overview

Large companies often require servers that are dedicated to message routing because of the high volume of message traffic they experience. In a typical high-volume site configuration, one server might be optimized as a home server for users' mailboxes, another server for dedicated public-folder replica hosting, and a third for providing dedicated messaging connectivity with other sites and foreign messaging systems. A connectivity server can have one or more connectors installed on it to provide connectivity with Exchange sites, Simple Mail Transfer Protocol (SMTP) hosts, X.400 messaging systems, or Microsoft Mail postoffices. The more connectors you have on a server, the greater its hardware requirements become.

Notes

On Exchange 5.5 systems, run the Performance Optimizer wizard after you have installed your connectors on the Exchange server. This will allow your server to take maximum advantage of its particular hardware configuration.

connector (device)

A device that terminates a segment of cabling or provides a point of entry for networking devices such as computers, hubs, and routers.

Overview

Connectors can be distinguished according to their physical appearance and mating properties, such as jacks and plugs (male connectors) or sockets and ports (female connectors). They can also be distinguished by their different pinning configurations, such as DB9 and DB15 connectors, which have 9 and 15 pins, respectively. In addition, connectors are distinguished by the kind of electrical interfaces they support. Examples of different types of connectors include

- Connectors for serial interfaces, such as RS-232 and V.35
- Ethernet connectors, such as RJ-45 and bayonet Neill-Concelman (BNC) connectors
- Fiber-optic cabling connectors, such as SC and ST connectors


BNC
BNC
BNC-T
DB
DB9
DB15
DB25
DB37
DB50
V series
V.35
V.24
M/50
Modular
RJ-11 (4-wire)
RJ-12 (6-wire)
R-J-45 (8-wire)
Centronics
Centronics (36-pin)
Centronics (parallel)
Fiber-optic
SMA 905
SMA 906
ST
SC
HD
HD 15
HD 15-pin 1
HD 15-pin video
HDI 30-pin
SCSI
SCSI-1
(Telco or Centronics 50)
SCSI-2
(Mini D50 or Micro DB50)
SCSI-3
(Micro DB68)

Connector (device). *Common networking and telecommunications connectors.*

A single connector may be used for a variety of purposes and different interfaces. For example, the DB-60 connector supports any of the following interfaces: V.35, X.21, EIA-530, EIA/TIA-232, and EIA/TIA-449. So you cannot always tell from the appearance of a connector what its function is—it depends on the interface it implements.

There are literally dozens of types of connectors used in networking, and the networking professional needs to be familiar with many of them. The illustration shows some of the common connector types used in different aspects of networking and telecommunications. Many of these connectors are discussed in separate articles elsewhere in this book.

Connector for Lotus cc:Mail

A component of Microsoft Exchange Server 5.5 that enables message transfer and directory synchronization between Exchange Server and Lotus cc:Mail systems.

Overview

Lotus cc:Mail uses a shared-file messaging architecture similar to that of Microsoft Mail. The Connector for Lotus cc:Mail is implemented as a Microsoft Windows NT service on Exchange Server and supports the following functions:

- Message transfer between Exchange Server and cc:Mail messaging systems
- Synchronization of directory information between Exchange Server and cc:Mail servers

Only one Connector for Lotus cc:Mail can be installed on a given computer running Exchange Server, and that connector can connect to only one cc:Mail postoffice. However, multiple computers running Exchange Server can each have a cc:Mail connector installed in order to connect to multiple postoffices throughout a cc:Mail messaging system. The Lotus cc:Mail programs export.exe and import.exe must be installed on the computer running Exchange Server for connectivity to be established.

The Connector for Lotus cc:Mail can be used to provide connectivity with database versions 6 or 8 cc:Mail postoffices.

Connector for Lotus Notes

A component of Microsoft Exchange Server 5.5 that enables message transfers and directory synchronization between Exchange Server and Lotus Notes systems.

Overview

The Connector for Lotus Notes allows either single or multiple Lotus Notes servers to be accessed from a single machine running Exchange Server. The Connector for Lotus Notes is implemented as a Microsoft Windows NT service on Exchange Server and supports

- Message transfer between Exchange Server and Lotus Notes
- Synchronization of directory information between Exchange Server and Lotus Notes

The Connector for Lotus Notes also converts message content to Rich Text Format (RTF) and converts Object Linking and Embedding (OLE) objects on Exchange Server to Lotus Doclinks objects.

The Connector for Lotus Notes supports Lotus Notes 3.*x* and Lotus Notes/Domino 4.*x*.

Notes

Be sure to install the Lotus Notes client on the computer running Exchange Server prior to attempting to install the Connector for Lotus Notes on the machine. The connector needs this client to log on to the Lotus Notes mail server. If you have trouble establishing connectivity, check that the connector has a valid Lotus Notes ID and that this ID has the appropriate permissions needed to access the databases on the machine running Lotus Notes.

connector (Microsoft Exchange)

A component of Microsoft Exchange Server 5.5 used to connect Exchange sites or to connect an Exchange organization to foreign mail systems.

Overview

Connectors are components of Exchange that can be used to route messages over a messaging system.

Connectors are implemented on Exchange as Microsoft Windows NT services and can be stopped and started using the Services utility in Control Panel.

Various types of connectors can be installed on Exchange, including the following:

- **Site Connector:** Used for establishing high-speed messaging links between different sites in an Exchange organization
- **X.400 Connector:** Used for establishing connectivity with a foreign X.400 messaging system such as those found in different parts of Europe
- **Dynamic RAS Connector:** Used for establishing dial-up connectivity between sites in an Exchange organization
- **Internet Mail Service:** Used for establishing connectivity with the Internet's Simple Mail Transfer Protocol (SMTP) messaging system
- **Microsoft Mail Connector:** Used for establishing messaging connectivity with legacy Microsoft Mail networks
- **Connector for Lotus cc:Mail:** Used for establishing connectivity with a foreign cc:Mail system
- **Connector for Lotus Notes:** Used for establishing connectivity with a Lotus Notes network

See Also: *Connector for Lotus cc:Mail, Connector for Lotus Notes*

Consumer DSL (CDSL)

A broadband transmission technology based on Digital Subscriber Line (DSL) technologies.

Overview

Consumer DSL (CDSL) was developed by Rockwell and is a slower technology than the more common DSL variant called Asymmetric Digital Subscriber Line (ADSL). CDSL provides data rates of about 1 megabit per second (Mbps) downstream (about 128 kilobits per second [Kbps] upstream) to the customer premises over standard Plain Old Telephone Service (POTS) local loop wiring. However, CDSL has the advantage of not requiring installation of a splitter at the customer premises. CDSL can operate only at distances of up to 18,000 feet (5500 meters) from the telco's central office (CO).

See Also: *Digital Subscriber Line (DSL)*

container (Active Directory)

In Microsoft Windows 2000 and Windows .NET Server, an object in Active Directory directory service that can contain other objects.

Overview

Examples of containers include organizational units (OUs), domains, and local networks. Domains are the core containers for organizing the structure of Active Directory. The other kinds of objects in Active Directory are leaf objects, which cannot contain other objects.

Objects created in a container inherit the discretionary access control list (DACL) of the container itself. In other words, a child object obtains its permissions from its parent object by inheritance.

Notes

Groups are not containers; they are security principals.

See Also: *Active Directory*

container (Microsoft Management Console)

In Microsoft Management Console (MMC), any node in a console tree to which other nodes can be added.

Overview

The usual icon for a container in MMC is the folder icon. The highest-level container in a console is the console root node. Beneath this node in the hierarchy are the top-level nodes for individual snap-ins that have been installed. Administrators who are creating new MMC consoles can create additional containers (folders) for organizing their console trees as desired.

See Also: *Microsoft Management Console (MMC)*

container (NTFS)

In NTFS file system (NTFS), a file system object (such as a directory) that can contain other objects (such as files).

Overview

Objects created in a container inherit the access control list (ACL) of the container itself. In other words, a child object obtains its permissions from its parent object by inheritance. For example, if a directory on an NTFS volume has read permission assigned to the Everyone group, any new file that you create or save in the directory will inherit the same permission. Using containers therefore simplifies the assignment of permissions to objects in the file system.

See Also: *NTFS file system (NTFS)*

Content Advisor

A feature of Microsoft Internet Explorer that allows you to control user access to Web sites based on the content ratings of the sites.

Overview

The Internet provides individuals with access to a wide variety of information, but some of this information might be unsuitable for certain viewers. For example, parents are often concerned about their children being exposed to violent or sexually explicit material on the Internet.

Content Advisor lets you control the kind of Internet content that can be accessed using Internet Explorer. This is a useful feature in corporate networks that have high-speed connectivity to the Internet because it can be used to discourage improper use of Web browsers on employee machines, thus helping to implement a company's acceptable use policy for the Internet. With Content Advisor, you can specify ratings settings to indicate acceptable levels of content to view with regard to sex, nudity, violence, and offensive language, and you can password-protect these settings.

Notes

Content Advisor functions properly only with Web sites that are rated.

Content Analyzer

A tool included with Microsoft Site Server and Microsoft Site Server Express that lets Web server administrators perform content analysis and link management of Web sites.

Overview

Content Analyzer can visually display the structure and integrity of a site in the form of a diagram called a Web map. Web maps allow administrators to visually examine a site's structure and quickly identify problems, such as loops and broken links. Web maps display various Web content items using different icons and can use a variety of colors to convey different kinds of information. You can also use Content Analyzer to search Web maps for various kinds of information using predefined Quick Searches. When you find an item of interest on a Web map, you can open your Web page editing tool directly from the Web map. You can also export Web map information into a database or spreadsheet file for further analysis.

Content Analyzer can also generate predefined site reports you can use to identify broken links and analyze the structure of Web sites. These site reports can be generated in Hypertext Markup Language (HTML) format for easy reading and evaluation and can identify changes to the content of a site, broken links, and other information.

content caching

A feature of a proxy server such as Microsoft Proxy Server.

Overview

Content caching allows a proxy server to cache the results of a client request. The next time a client requests the same content, it is retrieved from the cache to improve performance. Content remains in the cache for a predetermined period of time, or until the cache becomes full and old content is moved to allow new content to be cached.

Microsoft Proxy Server makes use of distributed caching, which lets content caching take place closer to users and allows caching activity to be load-balanced across several Proxy Servers for scalability and fault tolerance. For example, within corporate intranets, caching can be moved toward the branch office and workgroup levels of the organization. For Internet service providers (ISPs), caching can be moved toward regional points of presence (POPs). Distributed caching is particularly effective for solving network bandwidth problems associated with Internet push technologies.

Microsoft Proxy Server's distributed caching can be implemented in two ways:

- **Array-based caching:** In this approach, an array or group of proxy servers works together and is administered as a single, logical entity. A cache array provides load balancing, fault tolerance, scalability, and ease of administration. Cache arrays can provide a higher cache hit rate than an individual proxy server because of the larger size of the virtual cache.
- **Hierarchical caching:** In this approach, you arrange proxy servers in a hierarchy by branch office or department. Requests from clients are then forwarded up the hierarchy until the requested object is found in a proxy server's cache.

See Also: *proxy server*

content delivery network (CDN)

A method for efficiently pushing out content over the Internet to users.

Overview

The idea of content delivery networks originated as the next evolutionary step up from caching of Web content on the Internet. Like caching, the idea of CDN is to deliver content to users over the Internet as efficiently and quickly as possible. CDN takes caching a step further by actively pushing content out rather than passively caching frequently-requested content. A company that builds and operates a CDN is sometimes called a Content Delivery Provider (CDP).

Akamai Technologies developed the first CDN solution to efficiently deliver streaming media content over the Internet. Akamai accomplished this through alliances with regional Internet service providers (ISPs) for hosting their caching servers around the globe and setting up their own advanced Web hosting centers. Akamai then used forward-proxy caching servers at their hosting centers to push content out to caching servers at the edges of the Internet, allowing users around the globe to access streaming media presentations from nearby caching servers instead of from centralized streaming media servers many network hops away. The result was a system with better performance than existing implementations of streaming media.

CDNs are now used not just for streaming media but for supporting a wide variety of different kinds of content delivered over the Internet including static and dynamic Web content, video-on-demand, and other services.

Implementation

There are many ways to implement a CDN, and the technology continues to evolve rapidly. A simple example would be a CDP that hosts content for a company on Web and media servers in its data center and then uses a private network to push this content out to caching servers colocated at points of presence (POPs) of regional ISPs located near the company's customers. The private network could be a satellite link, leased lines, private backbone networks (such as those owned by AT&T Wireless), or a leased portion of Internet backbone bandwidth (usually an expensive solution). Private peering arrangements between ISPs and the CDP enable the CDN to work. Personalization servers keep track of user personalization data for customers in different regions.

The resulting CDN can be envisioned as a "content island" within the ocean representing the Internet—only subscribers on this island can make use of the CDN to improve access to hosted content. With many CDNs in existence around the globe and run by different CDPs, interoperability between them becomes an issue—what if a subscriber of one CDN wants to access content in a different CDN? To solve this problem, the Content Bridge is a vendor consortium of CDNs and CDPs whose aim is to move toward developing new protocols to enable interoperability between different CDNs so that a subscriber of one CDN can access content from the network of a different CDN. The Internet Engineering Task Force (IETF) is also working on a number of draft protocols to support interoperability between different CDNs.


CDP data center
Content servers
Content is pushed to cache servers over private network or satellite link.
POP of regional ISP
Corporate customers
Content is retrieved from cache servers.
Cache servers
Internet

Content delivery network (CDN). *A simple example of how a CDN works.*

Marketplace

Since Akamai blazed the path, a plethora of new CDNs have arisen and are vying for market dominance. These include

- CDNs built by private companies such as Yahoo! that have put together their own custom CDNs using technologies from vendors such as Cisco Systems.
- Companies such as Inktomi Corporation, CacheFlow, and Network Appliance that create hardware and software tools that can be used to build custom CDNs.
- Pure-play CDPs who build virtual CDNs by leasing bandwidth needed to push out their content to cache servers from bandwidth providers (BPs) such as Exodus Communications and Globix Corporation.

Despite the proliferation of CDN vendors and solution providers, Akamai and Inktomi, two early comers to the market, have established their platforms as cornerstone solutions for many large ISPs and enterprise customers. Akamai has more than 4000 caching servers distributed at POPs in over 50 countries. Other prominent players include new companies such as Digital Island. Existing networking companies are also releasing CDN solutions to the marketplace, though, including Cisco and Lucent Technologies.

A number of vendors are offering turnkey CDN solutions that can be easily implemented to improve content hosting performance for corporate intranets, ISPs, carriers, and others who need it. A leading vendor of CDN-in-a-box solutions is EdgeStream.

See Also: *caching*

Content Delivery Provider (CDP)

A company that builds and operates a content delivery network (CDN).

See: *content delivery network (CDN)*

content filter

A component of Microsoft Indexing service that can read a specific document format and turn it into a stream of text characters.

Overview

Content filters are an essential part of the indexing process on Indexing service because they determine which types of documents can be read and indexed. Indexing service includes content filters for popular file formats such as

- ASCII text
- Hypertext Markup Language (HTML) pages
- Microsoft Word documents
- Microsoft Excel spreadsheets

In addition, many third-party companies have produced content filters for their own document formats, allowing these documents to be indexed by Indexing service when their content filters have been installed. Content filters also handle the presence of embedded objects in documents and recognize when a language shift occurs in a multilingual document.

contention

A condition that occurs when two or more stations on a network try to access the network medium simultaneously. In other words, the stations are contending for control of the medium.

Overview

There are different ways of resolving contention issues on a network. One way is to use a single station as the master or primary station that controls all communication on the network. Other devices on the network function as slave, or secondary, stations. The entire system is known as a master-slave system. The master station normally functions in transmit mode, while the slave stations operate in receive mode. The master station tells individual slave stations when they should switch to transmit mode in order to transmit information over the network. This kind of scenario is used in networks based on IBM’s Systems Network Architecture (SNA).

In Ethernet networks, the Carrier Sense Multiple Access with Collision Detection (CSMA/CD) method is used to resolve contention on the network by allowing collisions to occur, and then resolving them successfully.

See Also: *Carrier Sense Multiple Access with Collision Detection (CSMA/CD)*

content rating

A mechanism for preventing users of Microsoft Internet Explorer from viewing Web sites that contain objectionable language, violence, nudity, or sexually explicit content.

Overview

These ratings are configured on the Web server on a site-by-site basis. Ratings for each category have been established at four levels of acceptable use. The Webmaster who creates the site can then include information about the levels of objectionable language, violence, nudity, or sexually explicit content present on their site. Content ratings are defined by the Recreational Software Advisory Council (RSAC). The user can configure her browser to a specified accessibility level for each type of content by using the Content Advisor feature of Internet Explorer.

For More Information

RSAC can be found at *www.rsac.org.*

control message

A command sent from one Usenet host to another.

Overview

Control messages are defined in the Network News Transfer Protocol (NNTP) specifications. Control messages can be issued by Usenet hosts to perform actions such as

- Creating a new newsgroup on the host
- Deleting a newsgroup
- Canceling messages that have already been posted

Control messages are simple text commands. You can troubleshoot a Usenet host by using telnet to connect to port 119 and manually typing various control messages and examining their results.

See Also: *Network News Transfer Protocol (NNTP), Usenet*

Control Panel

A Microsoft Windows feature consisting of a number of utilities for configuring hardware devices and operating system services.

Overview

The following table shows some of the more common Control Panel utilities in Windows 95, Windows 98, Windows NT, Windows 2000, Windows XP, and Windows .NET Server and briefly describes their function. Note that some utilities are named differently in the various Windows versions, such as 32-bit ODBC for Windows NT and ODBC (32 bit) for Windows 95 or 98; these utilities are listed separately here. Note also that some Control Panel utilities are present only when additional Windows components have been installed. For example, the GSNW utility is present only when Gateway Services for NetWare has been installed. Finally, installing additional third-party software can add new utilities to Control Panel associated with that software.


Control Panel
File
Edit
View
Favorites
Tools
Help
Back
Search
Folders
History
Address
Control Panel
Go
Control Panel
Windows Update
Windows 2000 Support
Accessibility Options
Add/Remove Hardware
Add/Remove Programs
Administrative Tools
Date/Time
Display
Folder Options
Fonts
Game Controllers
Internet Options
Keyboard
Licensing
Mail
Mouse
Network and Dial-up Co...
Phone and Modem ...
Power Options
Printers
Regional Options
Scanners and Cameras
Scheduled Tasks
Sounds and Multimedia
System
25 object(s)

Use the settings in Control Panel to personalize your computer.

Select an item to view its description.

Control Panel. *Windows 2000 Control Panel.*

Common Control Panel Utilities

Control Panel Utility	*Function*	*Windows 95 and 98*	*Windows NT*	*Windows 2000*	*Windows XP and .NET Server*
32-bit ODBC	Database connectivity		x	x	x
Accessibility Options	Help for visually or motor-impaired individuals	x		x	x
Add New Hardware	Hardware installation wizard	x			
Add/Remove Hardware	Hardware installation wizard			x	x
Add/Remove Programs	Installs new software or Windows components	x	x	x	x
Administrative Tools	Shortcut to Administrative Tools program group			x	x
Console	Command prompt window		x		
Date/Time	Date, time, time zone	x	x	x	x
Desktop Themes	Configures appearance of desktop	x			
Devices	Startup profiles for hardware devices		x		
Dial-Up Monitor	Monitors RAS connections		x		
Display	Screen and desktop settings	x	x	x	x
Folder Options	Enables Active Desktop and determines how folders are displayed			x	x
Fonts	Installs new fonts	x	x	x	x
Game Controllers	Configures joysticks	x		x	x
GSNW	Gateway Services for NetWare		x	x	x
Internet	Internet Explorer options	x	x		

(continued)

Common Control Panel Utilities *continued*

Control Panel Utility	*Function*	*Windows 95 and 98*	*Windows NT*	*Windows 2000*	*Windows XP and .NET Server*
Internet Options	Internet Explorer options			x	x
Keyboard	Style and response rate	x	x	x	x
Licensing	Changes licensing mode and configures replication		x	x	x
MacFile	Services for Macintosh		x		
Mail	Messaging profiles	x	x	x	x
Message Queuing	Configuration options for Microsoft Message Queue Server			x	x
Modems	Modem settings	x	x		
Mouse	Mouse settings	x	x	x	x
Multimedia	Audio/video settings	x	x		
Network	Networking clients, services, protocols, and adapters	x	x		
Network and Dial-up Connections	Creates and configures network connections			x	x
ODBC (32-bit)	Database connectivity	x			
Passwords	Configures passwords, enables remote administration, and enables user profiles	x			
PC Card	Settings for Personal Computer Memory Card International Association (PCMCIA) cards	x	x	x	x
Phone and Modem	Modem and TAPI location settings			x	x
Ports	COM port settings		x		

(continued)

Common Control Panel Utilities *continued*

Control Panel Utility	*Function*	*Windows 95 and 98*	*Windows NT*	*Windows 2000*	*Windows XP and .NET Server*
Power Management	Advanced power management settings	x		x	x
Power Options	Advanced power management settings			x	x
Printers	Adds printer wizard and manages printers	x	x	x	x
Regional Options	Currency and other settings for countries and regions			x	x
Regional Settings	Currency and other settings for countries and regions	x	x		
Scanners and Cameras	Configures these devices			x	x
Scheduled Tasks	Schedule system management tasks			x	x
SCSI Adapters	SCSI device settings		x		
Server	Server role		x		
Services	Starting and stopping services		x		
Sounds	System sounds	x	x		
Sounds and Multimedia	Audio/visual hardware/software and system sounds			x	x
System	Boot, file system, profiles, devices, environment, network identification, and other functions (depending on the version of Windows)	x	x	x	x
Tape Devices	Tape drive settings		x		
Telephony	TAPI location settings	x	x		
UPS	Uninterruptible Power Supply settings		x		
Users	User profiles	x			

control set

Refers to a set of registry keys in Microsoft Windows 2000, Windows XP, and Windows .NET Server that contain configuration information used for system startup.

Overview

Control sets define certain aspects of the Windows 2000, Windows XP, and Windows .NET Server boot process to allow Windows 2000, Windows XP, and Windows .NET Server to boot up successfully. Up to four control set subkeys are located under the HKEY_LOCAL_MACHINE\SYSTEM registry key, including the following:

- ControlSet001, ControlSet002, and so on, which represent backup copies of control sets that successfully started the system.
- CurrentControlSet, which refers to the control set that was used to successfully boot the system under its current configuration. The key here is a pointer to one of the ControlSet00x registry keys.

The Select registry key found under HKEY_LOCAL_MACHINES\SYSTEM identifies which of the control set keys corresponds to the current, default, failed, and Last Known Good configurations. If the current control set cannot start the system, you can press the Spacebar when indicated during the boot process to select the last known good configuration, which is the last control set that worked for sure.

See Also: *registry*

convergence

The process of updating routing tables after a change in the routing topology of an internetwork.

Overview

When a change occurs in the routing infrastructure of an internetwork, information concerning the change needs to be replicated to all routers that need to know about it. The process by which all routers gradually become aware of the change that occurred is called convergence.

Examples of occurrences that affect the routing infrastructure of an internetwork include adding a new router to the network, having an existing router fail on the network, and adding a new route to the routing table of a router on the network. When any of these situations arise, the routing protocol used to provide communications between the routers on your network is used to communicate these changes to all the routers that need to be aware of them. It typically takes time (from minutes to hours) for such changes to propagate completely through the internetwork's routing infrastructure, and as routers become updated with the new routing information, the network is said to "converge" toward its final state.

Convergence is important—if it does not occur fully, some routes may be unavailable on the network, making some parts of the network inaccessible. Furthermore, some packets may end up disappearing into "black holes" instead of arriving at their destination.

Notes

A more popular usage of the term *convergence* is to describe the merging of voice, data, and video services for transmission over a single network.

See Also: *black hole, internetwork, routing*

cookie

A small text file that the Web server saves the Web browser during a Hypertext Transfer Protocol (HTTP) session.

Overview

Cookies were originally intended to enable session state information to be maintained for Web applications across multiple HTTP requests. However, most commercial Web sites also use cookies to record information about the client's usage patterns, including the date and time the client visited the site, which pages were accessed, and Web browser preferences. Other uses for cookies include providing custom or personalized pages for users visiting Web sites, targeting advertising to users according to the pattern of their previous visits to a site, and enabling online shopping carts to function.

Cookies use the storage system of the client for saving this information instead of storing it on the server. Because the vast number of clients might visit the site only once, it would be inefficient to dedicate a large portion of server storage to tracking anonymous clients who might never return. Furthermore, client preferences (such as IP address) might change between sessions, especially for dial-up clients, so servers would have no way of recognizing clients if cookie information were saved on the server. Cookies therefore provide a way for the server to recognize that the client previously visited the site and record what the client did during previous visits, allowing the server to customize the HTTP session to meet the needs of the client (or the needs of the site's advertisers!).

Cookies are harmless text files and cannot be used to transmit a virus to the client. Cookies are simply passive holders of information; they cannot be used by hackers and other unauthorized users to "get" information off your computer such as your e-mail address. Nevertheless, most Web browsers, such as Microsoft Internet Explorer, have an optional setting that allows users to reject cookies. However, rejecting cookies can result in poorer browsing experiences on sites that are cookie-dependent. You can also delete any cookies on a computer running Microsoft Windows by deleting the contents of the Cookies subdirectory within the user profile directory on your hard drive (do not delete the directory itself, however!)

Notes

Web applications written using Microsoft Active Server Pages (ASP) technology can use cookies for maintaining session state information.

Shareware sites offer a variety of third-party browser plug-ins for managing or disabling cookies.

See Also: *Hypertext Transfer Protocol (HTTP), Web browser, Web server*

copper cabling

One of the two basic types of physical cabling media (the other being glass, or fiber-optic, cabling).

Overview

Copper cabling is cheap and flexible, but it is susceptible to electromagnetic interference (EMI), has limited range because of attenuation, and generates electromagnetic radiation that can be intercepted by nearby equipment. The types of copper cabling commonly used in networking include

- Twisted-pair cabling, such as unshielded twisted-pair (UTP) cabling and shielded twisted-pair (STP) cabling
- Coaxial cabling, such as thinnet and thicknet

For more information on these types of copper cabling, refer to their individual entries in this book.

Implementation

UTP cabling of Category 5 (Cat5) grade is the most commonly used copper cabling in networking environments today. Cat5 cabling comes in either solid core or stranded cabling. Solid core cabling is stiffer, but it has better conductivity and less attenuation, and it is simpler to terminate than stranded cabling. Stranded cabling is more flexible and easier to work with than solid cabling, and it is more resistant to breaking or fracturing. Use solid core UTP cabling for fixed horizontal cable runs, cross-connects, and backbone cabling; use stranded UTP cabling for locations where equipment is frequently moved, for short cable runs between computers and wall plates, or as patch cables in the wiring closet.

See Also: *cabling, coaxial cabling, fiber-optic cabling, unshielded twisted-pair (UTP) cabling*

Copper Distributed Data Interface (CDDI)

A form of Fiber Distributed Data Interface (FDDI) deployed over copper cabling instead of fiber.

Overview

Copper Distributed Data Interface (CDDI) can send data over unshielded twisted-pair (UTP) cabling at 100 megabits per second (Mbps), but cable lengths are limited to about 330 feet (100 meters). The architecture and operation are similar to FDDI, but CDDI is not as commonly implemented as FDDI (and because FDDI is usually considered a legacy networking architecture now, CDDI is also likely to fade away quickly.

If cost is an issue, CDDI offers an alternative to FDDI. CDDI still provides a 100-Mbps network with redundancy, but at reduced cost because copper cabling is cheaper than fiber-optic cabling. Note that CDDI does not provide the security that FDDI does: copper cabling can be tapped, but fiber-optic cabling cannot.

See Also: *Fiber Distributed Data Interface (FDDI)*

copy backup

A backup type in which all the selected files and folders are backed up, but the archive attribute is not marked for each file and folder.

Overview

Copy backups (or simply copies) do not interrupt the normal backup schedule because they do not change the state of the archive bit on files being backed up. Copy backups are typically used to produce additional copies of backup tapes. Copy backups might be used for

- Archiving information in a different location
- Generating tapes of month-end financials, which can then be given to the accounting department
- Providing branch offices with copies of information on file servers

See Also: *backup, backup type*

copying files

Making a replica of files.

Overview

On Microsoft Windows platforms, files can be copied using a graphical user interface (GUI) tool such as Windows Explorer or from the command prompt using the copy command. Some inheritance issues are associated with copying files on Windows NT, Windows 2000, Windows XP, and Windows .NET Server platforms that use the NTFS file system (NTFS). Specifically, copying a file within or between different NTFS volumes causes the file to inherit the permissions of the folder into which it is copied. For example, if a file on the NTFS drive C has read permission for everyone and it is copied to a directory on the NTFS drive D, which has change permission for everyone, the copy of the file inherits the change permission from the directory it is moved to.

See Also: *moving files*

CORBA

Stands for Common Object Request Broker Architecture, a component architecture that specifies technologies for creating, distributing, and managing component programming objects over a network.

See: *Common Object Request Broker Architecture (CORBA)*

Core-Based Trees (CBT)

A multicast routing protocol.

Overview

Internet Protocol (IP) multicasting relies on the spanning tree algorithm to ensure delivery of information to intended recipients. Spanning-tree technologies can be implemented in two basic ways:

- **Dense mode:** Used for Webcasting and other large-scale multicast events.
- **Sparse mode:** Used for delivering multicast information to specific, small pockets of users on a large internetwork.

Core-Based Trees (CBT) is one of two sparse-mode protocols commonly used, the other being Protocol Independent Multicast Sparse Mode (PIM-SM).

Architecture

CBT works by having a single core router create a single multicast routing tree, regardless of the multicast transmission's source. Then, when a multicast client wants to register to receive a multicast transmission, the client contacts the nearest upstream multicast router by sending an Internet Group Membership Protocol (IGMP) packet to the router. If the member router is already receiving the multicast transmission, it registers the client and forwards the transmission to the client. If the router is not receiving the transmission, it contacts the next router upstream, and this continues until, if necessary, the core router is reached. The core router then adds the member routers to the multicast group and forwards the transmission to the member router, which then passes it to the client.

See Also: *dense mode, multicasting, Protocol Independent Multicast-Sparse Mode (PIM-SM), routing, sparse mode*

counter

An aspect of an object in Performance for which usage statistics can be collected.

Overview

Performance is a Microsoft Windows 2000, Windows XP, and Windows .NET Server administrative console for monitoring system resources. It can be used to collect status information about various objects. For example, if the object Processor is being studied, the Performance Monitor collects information on all counters that belong to this object. This includes counters such as

- **% User Time:** The percentage of the time the processor is in user mode executing a nonidle thread
- **% Privileged Time:** The percentage of the time the processor is in kernel mode executing a nonidle thread
- **Interrupts/sec:** The number of device interrupts a processor receives per second

If the machine is a multiprocessor system, each instance of each counter can be monitored. Performance Monitor counters are usually one of two types:

- Instantaneous counters, which display the most recent value of a measurement— for example, Processor: % Processor Time
- Average counters, which display the average of the last two measured values— for example, LogicalDisk: Avg. Disk Bytes/Read

country code

A two-letter code identifying top-level domains for countries and regions in the Domain Name System (DNS).

Overview

Country codes are a way of geographically identifying a domain name as belonging to a particular country or region. They are an alternative to the more commonly used organizational codes such as .com, .org, and .net. This table lists the various country codes in the DNS system.

Country Codes

Code	*Country/Region*	*Code*	*Country/Region*
ad	Andorra	ca	Canada
ae	United Arab Emirates	cc	Cocos (Keeling Islands)
af	Afghanistan	cf	Central African Republic
ag	Antigua and Barbuda	cg	Congo (Congo Republic)
ai	Anguilla	ch	Switzerland
al	Albania	ci	Cote d'Ivoire
am	Armenia	ck	Cook Islands
an	Netherlands Antilles	cl	Chile
ao	Angola	cm	Cameroon
aq	Antarctica	cn	China
ar	Argentina	co	Colombia
as	American Samoa	cr	Costa Rica
at	Austria	cu	Cuba
au	Australia	cv	Cape Verde
aw	Aruba	cx	Christmas Island
az	Azerbaijan	cy	Cyprus
ba	Bosnia and Herzegovina	cz	Czech Republic
bb	Barbados	de	Germany
bd	Bangladesh	dj	Djibouti
be	Belgium	dk	Denmark
bf	Burkina Faso	dm	Dominica
bg	Bulgaria	do	Dominican Republic
bh	Bahrain	dz	Algeria
bi	Burundi	ec	Ecuador
bj	Benin	ee	Estonia
bm	Bermuda	eg	Egypt
bn	Brunei Darussalam	er	Eritrea
bo	Bolivia	es	Spain
br	Brazil	et	Ethiopia
bs	Bahamas	fi	Finland
bt	Bhutan	fj	Fiji Islands
bv	Bouvet Island	fk	Falkland Islands (Islas Malvinas)
bw	Botswana	fm	Micronesia
by	Belarus	fo	Faroe Islands
bz	Belize		

(continued)

Country Codes *continued*

Code	*Country/Region*	*Code*	*Country/Region*
fr	France	jp	Japan
fx	France (Metropolitan)	ke	Kenya
ga	Gabon	kg	Kyrgyzstan
gd	Grenada	kh	Cambodia
ge	Georgia	ki	Kiribati
gf	French Guiana	km	Comoros
gh	Ghana	kn	Saint Kitts and Nevis
gi	Gibraltar	kp	Korea (North)
gl	Greenland	kr	Korea (South)
gm	Gambia	kw	Kuwait
gn	Guinea	ky	Cayman Islands
gp	Guadeloupe	kz	Kazakhstan
gq	Equatorial Guinea	la	Laos
gr	Greece	lb	Lebanon
gs	South Georgia and South Sandwich Islands	lc	Saint Lucia
gt	Guatemala	li	Liechtenstein
gu	Guam	lk	Sri Lanka
gw	Guinea-Bissau	lr	Liberia
gy	Guyana	ls	Lesotho
hk	Hong Kong SAR	lt	Lithuania
hm	Heard and McDonald Islands	lu	Luxembourg
hn	Honduras	lv	Latvia
hr	Croatia (Hrvatska)	ly	Libya
ht	Haiti	ma	Morocco
hu	Hungary	mc	Monaco
id	Indonesia	md	Moldova
ie	Ireland	mg	Madagascar
il	Israel	mh	Marshall Islands
in	India	mk	Macedonia, Former Yugoslav Republic of
io	British Indian Ocean Territory	ml	Mali
iq	Iraq	mm	Myanmar
ir	Iran	mn	Mongolia
is	Iceland	mo	Macau SAR
it	Italy	mp	Northern Mariana Islands
jm	Jamaica	mq	Martinique
jo	Jordan	mr	Mauritania

(continued)

Country Codes *continued*

Code	*Country/Region*	*Code*	*Country/Region*
ms	Montserrat	ru	Russian Federation
mt	Malta	rw	Rwanda
mu	Mauritius	sa	Saudi Arabia
mv	Maldives	sb	Solomon Islands
mw	Malawi	sc	Seychelles
mx	Mexico	sd	Sudan
my	Malaysia	se	Sweden
mz	Mozambique	sg	Singapore
na	Namibia	sh	St. Helena
nc	New Caledonia	si	Slovenia
ne	Niger	sj	Svalbard and Jan Mayen Islands
nf	Norfolk Island	sk	Slovak Republic
ng	Nigeria	sl	Sierra Leone
ni	Nicaragua	sm	San Marino
nl	Netherlands	sn	Senegal
no	Norway	so	Somalia
np	Nepal	sr	Suriname
nr	Nauru	st	Sao Tome and Principe
nu	Niue	sv	El Salvador
nz	New Zealand	sy	Syria
om	Oman	sz	Swaziland
pa	Panama	tc	Turks and Caicos Islands
pe	Peru	td	Chad
pf	French Polynesia	tf	French Southern Territories
pg	Papua New Guinea	tg	Togo
ph	Philippines	th	Thailand
pk	Pakistan	tj	Tajikistan
pl	Poland	tk	Tokelau
pm	St. Pierre and Miquelon	tm	Turkmenistan
pn	Pitcairn	tn	Tunisia
pr	Puerto Rico	to	Tonga
pt	Portugal	tp	East Timor
pw	Palau	tr	Turkey
py	Paraguay	tt	Trinidad and Tobago
qa	Qatar	tv	Tuvalu
re	Reunion	tw	Taiwan
ro	Romania	tz	Tanzania

(continued)

Country Codes *continued*

Code	*Country/Region*	*Code*	*Country/Region*
ua	Ukraine	vi	Virgin Islands (US)
ug	Uganda	vn	Viet Nam
uk	United Kingdom	vu	Vanuatu
um	US Minor Outlying Islands	wf	Wallis and Futuna Islands
us	United States	ws	Samoa
uy	Uruguay	ye	Yemen
uz	Uzbekistan	yt	Mayotte
va	Vatican City State	yu	Yugoslavia
vc	Saint Vincent and The Grenadines	za	South Africa
ve	Venezuela	zm	Zambia
vg	Virgin Islands (British)	zr	Congo (Democratic Republic of Congo)
		zw	Zimbabwe

coupler

A small device for connecting two cables to make a longer cable, sometimes called an inline coupler.

Overview

Inline couplers do not provide any amplification or signal boost, and can cause attenuation and signal degradation unless they are of high quality. One example would be a small box that accepts two Category 5 (Cat5) cables with RJ-45 connectors and links them to form a longer cable. Another example would be the BNC barrel connector for joining two lengths of thinnet cabling. A third example would be a coupler with two RJ-11 connectors for joining two phone lines.



Coupler. *A Category 5 UTP (unshielded twisted-pair) coupler.*

The term *coupler* is also used to refer to modular connectors that can snap into customizable patch panels to allow different kinds of cabling to be mixed in one patch panel.

CPE

Stands for customer premises equipment (CPE), telecommunications equipment that is installed at the customer's location.

See: *customer premises equipment (CPE)*

CRC

Stands for cyclical redundancy check, an error-checking technique for ensuring packets are successfully delivered over a network

See: *cyclical redundancy check (CRC)*

Creator Owner

A Microsoft Windows 2000, Windows XP, or Windows .NET Server built-in identity that is used as a security context for running services and operating system functions.

Overview

The membership of the Creator Owner system group cannot be modified directly. The Creator Owner system group includes only the user who created or took ownership of a network resource and is functionally equivalent to that user's primary group. The Creator Owner system group has full permissions on the resource, but the rights of the Creator Owner system group cannot be modified. Whoever creates a file system object or print job becomes the Creator Owner of that object or job.

See Also: *built-in identities*

credentials

Information required from users who want to log on to a network and access its resources.

Overview

Credentials, which are formed by combining a user's username and password, identify users so that they can be authenticated by the network security provider. Credentials for access to one network do not guarantee access to another network.

In networks that are based on Microsoft Windows NT, Windows 2000, and Windows .NET Server, computers called domain controllers are responsible for authentication of user's credentials. In addition, trust relationships can be established between Windows NT domains to allow user's credentials to be authenticated from anywhere in the enterprise. Windows NT, Windows 2000, Windows XP, and Windows .NET Server support single-user logon, which allows a user to use a single set of credentials for accessing resources anywhere on a network.

See Also: *authentication protocol, password, username*

crimper

A cabling installation tool used for attaching connectors to cabling.

Overview

Crimpers are used to terminate cables by applying appropriate pressure to contacts within a connector so that it remains physically attached to the cable without soldering. A crimper is an essential component of a network administrator's toolkit. Crimpers can include built-in strippers for removing the outer insulation from a cable. They can include a set of dies for crimping different kinds of connectors, or they can be specialized for a single type of termination. Crimpers are most often used for terminating Category 5 (Cat5) unshielded twisted-pair (UTP) cabling with RJ-45 connectors. A good crimper should be made of heavy-duty metal and be able to cut, strip, and terminate a cable easily.



Crimper. *A crimper with connector set.*

See Also: *cabling, connector (device)*

CRL

Stands for certificate revocation list, a list, maintained by a certificate authority (CA), of digital certificates that have been issued and then later revoked.

See: *certificate revocation list (CRL)*

CRM

Stands for Customer Relations Management, a type of business application used to manage business-to-consumer (B2C) connections

See: *Customer Relationship Management (CRM)*

crossover cable

Twisted-pair cabling with the send and receive pairs of wires crossed.

Overview

Crossover cables are primarily used for connecting hubs to each other. In addition, a small, two-station local area network (LAN) can be established by connecting two computers together with 10BaseT network interface cards (NICs) and a crossover cable. This configuration is often utilized when one computer is used to test the networking functions of another because it allows the computer being tested to be isolated from the network. The illustration shows the pinning configuration of a crossover cable.



Crossover cable. *Pinning for a crossover cable.*

See Also: *cabling, twisted-pair cabling*

crosstalk

A form of interference in which signals in one cable induce electromagnetic interference (EMI) in an adjacent cable.

Overview

The ability of a cable to reject crosstalk in Ethernet networks is usually measured using a scale called near-end crosstalk (NEXT). NEXT is expressed in decibels (dB), and the higher the NEXT rating of a cable, the greater its ability to reject crosstalk. A more complex scale called Power Sum NEXT (PS NEXT) is used to quantify crosstalk in high-speed Asynchronous Transfer Mode (ATM) and Gigabit Ethernet (GbE) networks.

The twisting in twisted-pair cabling reduces the amount of crosstalk that occurs, and crosstalk can be further reduced by shielding cables or physically separating them. Crosstalk is a feature of copper cables only—fiber-optic cables do not experience crosstalk. Crosstalk can be a problem for unshielded twisted-pair (UTP) cabling. To minimize crosstalk, make sure that

- You do not untwist or sharply bend the UTP cabling
- The cable ends connected to a patch panel or wall plate are untwisted no more than 0.5 inch (1.3 centimeters)

See Also: *cabling, near-end crosstalk (NEXT)*

CryptoAPI

A core component of the latest versions of Microsoft Windows that provides application programming interfaces (APIs) for cryptographic security services that provide secure channels and code signing for communication between applications.

Overview

CryptoAPI provides a set of standard Win32 libraries for managing cryptographic functions using a single consistent interface independent of the underlying cryptographic algorithms and ciphers. CryptoAPI interfaces with modules called cryptographic service providers (CSPs), such as the Microsoft RSA Base Cryptographic Provider, to provide cryptography functions such as hashing, data encryption and decryption, key generation and exchange, digital signature issuance and verification, and so forth.

CryptoAPI is natively supported by the latest versions of Windows NT, Windows 98, Windows 2000, Windows XP, and Windows .NET Server. Microsoft Internet Explorer version 4 provides CryptoAPI support for Windows 95. The current version of CryptoAPI is version 2.

See Also: *cryptography*

Cryptographic Message Syntax Standard

A standard that defines the general syntax for data that includes cryptographic features such as digital signatures, encryption, and certificate chains.

Overview

Cryptographic Message Syntax Standard, also known as PKCS #7, specifies the format in which the data is signed and encrypted, and the types of encryption algorithms used.

Data encrypted according to the PKCS #7 standard can have multiple digital certificates attached, including certificate revocation lists (CRLs). Certificates include information concerning the issuer and serial number of the public key of the signer so that the recipient can decrypt the message.

See Also: *cryptography, digital certificate, encryption*

cryptography

In networking and telecommunications, the process of securely transmitting data over a network in such a way that if the data is intercepted, it cannot be read by unauthorized users.

Overview

Cryptography involves two complementary processes:

- **Encryption:** The process of taking data and modifying it so that it cannot be read by distrusted users.
- **Decryption:** The process of taking encrypted data and rendering it readable for trusted users.

Encryption and decryption are performed using algorithms and keys. An algorithm, a series of mathematical steps that scrambles data, is the underlying mathematical process behind encryption. There are a variety of cryptographic algorithms that have been developed based on different mathematical processes.

Some algorithms result in stronger encryption than others—the stronger the algorithm, the more difficult the encrypted data is to crack. For example, Network and Dial-up Connections in Microsoft Windows 2000 supports standard 40-bit RAS RC4 encryption, but if you are located in the United States or Canada, you can get a stronger 128-bit version. Similar versions are offered for Windows NT.

Encryption algorithms involve mathematical values called keys. Earlier cryptography systems were secret key encryption systems in which only the hosts involved in transmitting and receiving the encrypted transmission knew the key. This key had to somehow be transported securely to anyone needing to decrypt a message. This was the main disadvantage with secret key cryptosystems.

Most cryptography today involves a process called public key encryption, which uses two different keys:

- A public key that is distributed to any user (or to any client program) requesting it
- A private key that is known only to the owner (or the owner's client program)

To send an encrypted message, the sender uses his or her private key to encrypt the data, and the recipient uses the sender's public key to decrypt it. Similarly, the recipient can return a response to the original sender by using the sender's public key to encrypt the response, and the original sender uses his or her private key to decrypt it.

See Also: *digital certificate, public key cryptography*

CSMA/CA

Stands for Carrier Sense Multiple Access with Collision Avoidance, the media access control method used by AppleTalk.

See: *Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA)*

CSMA/CD

Stands for Carrier Sense Multiple Access with Collision Detection, the media access control method used by half-duplex Ethernet networks.

See: *Carrier Sense Multiple Access with Collision Detection (CSMA/CD)*

CSNW

Stands for Client Services for NetWare, a Windows 2000, Windows XP, and Windows .NET Server service that provides Microsoft Windows clients with access to Novell NetWare file, print, and directory services.

See: *Client Services for NetWare (CSNW)*

CSP (caching service provider)

Stands for caching service provider, a company that maintains caching servers that speed the transfer of information across the Internet's infrastructure and offers managed access to these servers for a fee.

See: *caching service provider (CSP)*

CSP (commercial service provider)

Stands for commercial service provider, typically Internet service providers (ISPs), online service providers, telephone and cable network operators, and other companies.

See: *commercial service provider (CSP)*

CSS

Stands for cascading style sheets, a method for giving Web developers more control over how the pages of a Web site will look when displayed on a Web browser.

See: *cascading style sheets (CSS)*

CSU

Stands for Channel Service Unit, a device that is used to connect a synchronous digital telecommunications line to a computer network.

See: *Channel Service Unit (CSU)*

CSU/DSU

Stands for Channel Service Unit/Data Service Unit, a device that combines the functions of both a Channel Service Unit (CSU) and a Data Service Unit (DSU).

See: *Channel Service Unit/Data Service Unit (CSU/DSU)*

.csv file

A text file having the extension .csv, which contains fields of data separated by commas and a carriage return/linefeed at the end of each record. The extension .csv stands for comma-separated values.

Overview

These files are often used as a standard format for importing and exporting information between applications. For example, in Microsoft Exchange Server you can modify the properties of a group of mailboxes by exporting the properties of the mailboxes to a .csv file, opening this file as a spreadsheet in Microsoft Excel, modifying the properties using string functions and search/replace, exporting the information back into another .csv file, and then importing the modified file back into Exchange. Many applications can export log files or other information as .csv files. These files can then be imported into a spreadsheet or database program where they can be subjected to further inspection and analysis. Graphics and charts can also be generated from the imported information.

CTEC

Stands for Certified Technical Education Center, an education-delivery company such as a school or training center that is been qualified by Microsoft Corporation for the delivery of Microsoft Official Curriculum (MOC) courseware.

See: *Certified Technical Education Center (CTEC)*

CTI

Stands for computer-telephony integration, a general term describing the integration of computer and telephone technologies.

See: *computer-telephony integration (CTI)*

Ctrl+Alt+Delete

A control sequence that has different effects depending upon the operating system involved.

Overview

Holding down the Control, Alt, and Delete keys simultaneously produces the following results (depending upon the operating system being used):

- **MS-DOS:** Restarts the computer.
- **16-bit Microsoft Windows, Windows 95, and Windows 98:** Shows running tasks and allows you to terminate a task. A second Ctrl+Alt+Delete will restart the computer.
- **Windows NT:** Brings up the Windows NT Security dialog box.
- **Windows 2000:** Brings up the Windows Security dialog box.
- **Windows XP and Windows .NET Server:** Brings up the Windows Security dialog box.

See Also: *secure attention sequence (SAS)*

custom authentication

Any user-created method for authentication of clients on a network.

Overview

Microsoft Internet Information Services (IIS) lets you create custom authentication schemes to control access to Web content. These can be implemented using several different technologies, including Active Server Pages (ASP), Internet Server API (ISAPI) authentication filters, or Common Gateway Interface (CGI) applications. For example, using any of these technologies, you can create an authentication scheme to

- Perform a search of a client's credentials in a custom user database
- Examine a client's digital certificate to determine whether to allow access
- Use cookies or some other mechanism to establish whether the client should be authenticated

See Also: *authentication protocol*

Customer Information Control System (CICS)

Customer Information Control System (CICS) enables transaction-based applications to operate on IBM mainframe systems. More than half of all mainframes running today still use some CICS applications. Traditionally CICS-based applications are accessed using legacy IBM 3270 text-based terminals, but newer products allow CICS transactions to be wrapped in Hypertext Markup Language (HTML) for access by Web browsers. One such product is Shadow AutoHTML for CICS/TS from Neon Systems, which also supports Open Database Connectivity (ODBC) interfaces for CICS applications.

For More Information

Find Neon Systems at *www.neonsys.com.*

See Also: *Systems Network Architecture (SNA)*

customer premises

A general term referring to your local company's networking environment.

Overview

The term *customer premises* is typically used by service providers who provide leased or contractual services to help you implement and support your network. For example, a cabling company would install cabling at your customer premises and call this installation "premise wiring." A telecommunications company might send a representative to a customer premises in order to install a Channel Service Unit/Data Service Unit (CSU/DSU) or other device in the wiring closet to enable wide area network (WAN) communication. Typically, your company is responsible for the physical security of such installed equipment, but the actual configuration and monitoring of the equipment often takes place at the telco's central office (CO).

See Also: *customer premises equipment (CPE), enterprise resource planning (ERP)*

customer premises equipment (CPE)

Telecommunications equipment that is installed at the customer's location.

Overview

Customer premises equipment (CPE) is installed to terminate wide area network (WAN) links and local loop connections between the customer and the carrier's central office (CO) and to route traffic between the customer premises and the carrier from which telecommunications services are leased. Common examples of customer premises equipment include telephones, modems, Channel Service Unit/Data Service Units (CSU/DSUs), Private Branch Exchanges (PBXs), and Integrated Access Devices (IADs) routers.

Generally, the telecommunications service provider is responsible for configuring and monitoring the equipment, which is purchased or leased by the customer from the carrier. For example, when installing a CSU/DSU as a termination for a T1 line, the configuration of the CSU/DSU is likely to have been done previously by the service provider. The carrier then uses Simple Network Management Protocol (SNMP) and loopback monitoring to determine, from its central office, whether the remotely installed equipment is functioning correctly.

Alternatively, customers may purchase or lease their own CPE from third-party vendors. In this case the customer is usually responsible for configuring and monitoring the equipment. In general, cost/benefit is usually on the side of leasing CPE from the provisioning carrier because the cost of replacing defective or failed equipment or upgrading equipment to support enhanced services is the burden of the carrier.

See Also: *carrier, customer premises, local loop, telecommunications services, wide area network (WAN)*

Customer Relationship Management (CRM)

A type of business application used to manage business-to-consumer (B2C) connections.

Overview

Customer Relationship Management (CRM) software is used to manage mission-critical business information concerning the direct relationship between a business and its clients. CRM enables business users to quickly and easily access up-to-date information concerning client accounts, and it provides the tools for managing and growing a company's relationship with its customers. CRM software enables a business to manage leads, distribute timely information to customers, and coordinate a multitude of other customer-centric activities.

Marketplace

Some of the bigger players among CRM vendors include Onyx Technology, Pivotal Software, and Siebel Systems. CRM software takes a variety of forms depending on whether it is being implemented in small, mid-sized, or enterprise-level businesses. Some CRM vendors build their products around customer databases, while newer players and CRM startups often use the application service provider (ASP) model for outsourcing CRM needs.

The worldwide market revenue for all forms of CRM software and services was estimated at over $10 billion in 2000 and may reach $25 billion by 2003, according to some analysts.

Notes

A recent offshoot of CRM is partner relationship management (PRM), which helps companies to manage the more indirect relationship they have with business channels and supply chain partners, among others. Besides the big CRM players, a number of emerging pure-play PRM vendors are attracting market share. These include Allegis, ChannelWave, and many others.

See Also: *B2B, enterprise resource planning (ERP)*

custom recipient

A recipient in Microsoft Exchange Server that does not reside in the Exchange organization.

Overview

When creating a custom recipient, you specify the e-mail address of the remote user first, and then configure the properties of the recipient. An example of a custom recipient is the Simple Mail Transfer Protocol (SMTP) address of a user on the Internet.

Custom recipients are often created on Exchange servers to place frequently used foreign addresses in the global address book so that users do not have to specify the recipient's e-mail address manually or maintain their own personal address books. Custom recipients can be used for various other purposes in Exchange, such as to enable a user's Internet mail to be forwarded to his or her Exchange mailbox.

cyclical redundancy check (CRC)

An error-checking technique for ensuring that packets are successfully delivered over a network.

Overview

A cyclical redundancy check (CRC) is a number that is mathematically calculated for a packet by its source computer and then recalculated by the destination computer. If the original and recalculated versions at the destination computer differ, the packet is corrupt and needs to be resent or ignored.

The mathematical procedure for performing a CRC is specified by the International Telecommunication Union (ITU) and involves applying a 16-bit polynomial to the data being transmitted by the packet for packets of 4 KB of data or less, or a 32-bit polynomial for packets larger than 4 KB. The results of this calculation are appended to the packet as a trailer. The receiving station applies the same polynomial to the data and compares the results to the trailer appended to the packet. Implementations of Ethernet use 32-bit polynomials to calculate their CRC.

D

DAB

Stands for Digital Audio Broadcasting, a specification for broadband digital radio.

See: *Digital Audio Broadcasting (DAB)*

DACL

Stands for discretionary access control list, an access control list (ACL) that can be configured by administrators.

See: *discretionary access control list (DACL)*

daemon

The UNIX equivalent of a Microsoft Windows 2000, Windows XP, or Windows .NET Server service.

Overview

A daemon is a program associated with the UNIX operating system that runs in the background and performs some task without instigation from the user. An example of a daemon is the telnet daemon, which runs continuously in the background, waiting for a connection request from a telnet client. The telnet daemon facilitates the remote connection and makes it possible for the user to control the machine.



Daemon. *How the nfsd daemon works.*

Another example is the HTTPd daemon for the Apache Web server, which waits for Hypertext Transfer Protocol (HTTP) requests from Web browser clients and fulfills them.

A third example of a daemon is the nfsd daemon, which supports the remote file access aspect of the Network File System (NFS) in a UNIX environment. The nfsd daemon runs in the background on UNIX servers, waiting for remote procedure calls (RPCs) from NFS clients.

Daemons typically use RPCs for communication with clients. Because NFS is implemented as daemon processes at the user level instead of at the kernel level, NFS is thread-safe for execution, allowing multiple NFS processes to run as independent threads of execution.

Notes

The Microsoft equivalent of daemon is service. For example, the Workstation service of Windows 2000 would be known in UNIX as a daemon instead of a service.

See Also: *service*

daily copy

A type of tape backup in which only files and folders that have changed on that day are backed up.

Overview

When a daily copy is performed during a backup, files and folders modified on that day are backed up but their archive attribute is not marked.

Daily copies are not a common type of backup operation. They are typically used only if a user wants to take home copies of the files she has been working on during the day. Few administrators would be willing to schedule and run the system backup software just to make copies of these files, so users taking advantage of this backup type usually have a locally attached backup device along with a similar device attached to their systems at home.

Daily copy backups are likely to be performed on media such as Iomega Zip or Jaz disks rather than on tape.

Notes

Daily copy backups are supported by the Microsoft Windows 2000 Backup utility.

See Also: *backup, backup type*

D-AMPS

Stands for Digital Advanced Mobile Phone Service, the digital version of the Advanced Mobile Phone Service (AMPS) cellular communications system.

See: *Digital Advanced Mobile Phone Service (D-AMPS)*

DAO

Stands for Data Access Objects, a Microsoft technology that enables you to use a programming language to access and manipulate data stored in both local and remote databases.

See: *Data Access Objects (DAO)*

DAP

Stands for Directory Access Protocol, a protocol for accessing information in a directory service based on the X.500 recommendations.

See: *Directory Access Protocol (DAP)*

dark fiber

Any fiber-optic cabling or fiber device such as a repeater that is installed but not currently in use.

Overview

When no light is being transmitted through fiber-optic cabling, it is called dark fiber since it is, in effect, dark. When a carrier or cabling company first provisions fiber, it is called dark fiber. Then once all the components of the system are installed, including connectors, amplifiers, repeaters, switches, routers, and such, the light can be turned on and the fiber is no longer dark. Dark fiber is thus simply unused fiber or fiber that is not yet ready to be used.

Before dark fiber is activated, the system is usually tested using an optical time domain reflectometer (which measures and analyzes a fiber link) and other measuring devices to determine whether the system has integrity, and to measure its bandwidth and attenuation parameters.

Implementation

When an enterprise needs a fiber connection for wide area usage, it can take three possible approaches:

- **Lay their own fiber:** This is an expensive solution, not only because large amounts of fiber may be required, but also because expertise in fiber-optic cabling technologies is needed and is often in short supply. Right of way must also often be purchased in order to lay the fiber, and this is often difficult or downright impossible. Only the largest enterprises can afford this approach, and it is rarely implemented beyond campus networks.
- **Lease dark fiber:** This involves paying a telecommunications carrier for one or more strands of fiber-optic cabling from the carrier's own system. Companies that want to maintain total control of their wide area network (WAN) links can choose this route. They first lease dark fiber from a carrier, and then install switches and repeaters to build their own long-haul fiber-optic network. Leasing dark fiber was a popular solution for many enterprises in the 1990s, especially for financial institutions that required the highest level of privacy and security for their WANs. Also, in the 1990s carrier networks were almost exclusively Asynchronous Transfer Mode/Synchronous Optical Network (ATM/SONET)–based, and the WAN services they offered were expensive; enterprises saw leasing dark fiber as a way of controlling costs and simplifying their WANs.
- **Leasing managed wavelength services:** With the advent of dense wavelength division multiplexing

(DWDM) on carrier networks at the end of the 1990s, the carrying capacity of carrier networks increased dramatically. This, and the emergence of new carriers such as Metropolitan Gigabit Ethernet providers, drove down the cost of carrier WAN services, making leasing WAN services more cost attractive to some enterprises than leasing their own dark fiber. New providers called managed wavelength services providers quickly arose as resellers of fiber capacity from traditional carriers. Some of these managed wavelength services providers include 360networks, Global Crossing, Level 3, Metromedia, XO Communications, and others. AT&T also directly leases managed wavelength services up to 2.4 gigabits per second (Gbps) to large companies.

Notes

Although the term *dark fiber* at first sounds like there is a problem in the fiber-optic cabling system, this is not the case. However, various problems can occur in a fiber-optic cabling system that can cause it to remain dark once the system is turned on. These can include the following:

- Microfractures in the glass core or cladding caused by improper installation techniques, such as excessive bending or stretching of a segment of cable
- Improper terminations for the fiber or loose connectors
- Malfunctioning repeaters

See Also: *dense wavelength division multiplexing (DWDM), fiber-optic cabling*

Data Access Objects (DAO)

A Microsoft technology that enables you to use a programming language to access and manipulate data stored in both local and remote databases.

Overview

Data Access Objects (DAO) lets you access and manage databases, along with their structure and objects, by providing a framework called an object model that uses code to create and manipulate different kinds of databases.

DAO supports two different interfaces, which are known as workspaces:

- **ODBCDirect workspace:** This lets you can access database servers such as Microsoft SQL Server through open database connectivity (ODBC). This workspace lets you execute queries or stored procedures against a database server, perform batch updates, and execute asynchronous queries. ODBCDirect makes it possible for you to take advantage of Remote Data Objects (RDO) technology in your DAO code.
- **Microsoft Jet workspace:** This lets you access databases based on Jet technology or on installable indexed sequential access method (ISAM) data sources in other formats such as Paradox, dBase, and Btrieve. You use this workspace to access a single database, such as a .mdb database from Microsoft Access, or to join together data originating from several different database formats.

Prospects

DAO and RDO are both available now, but these technologies are being superseded by Microsoft ActiveX Data Objects (ADO) and Remote Data Service (RDS). All these components can be found in the Microsoft Data Access Software Development Kit.

See Also: *ActiveX Data Objects (ADO), open database connectivity (ODBC)*

data alarm

A device for alerting network administrators to network problems relating to serial transmission.

Overview

Data alarms typically monitor serial lines such as RS-232 connections for the presence or absence of certain signals. For example, you can monitor the connection between a print server and its attached printer or between an access server and a modem or a Channel Service Unit/Data Service Unit (CSU/DSU).



Data alarm. *Implementing a data alarm for alerting administrators to problems with serial links.*

A data alarm can be a simple device that monitors one serial line for the presence or absence of data. If the data flow stops, a flashing LED or audible alarm signals the problem to the administrator. More complex data alarms can support multiple serial lines or other serial interfaces such as RS-449 and V.35, can have programmable functions and menu-driven commands, and can monitor other devices, such as Time to Live (TTL) devices. These more complex devices can be configured to dial a remote station when a problem arises and to generate a report of the condition or even activate an alphanumeric pager.

Notes

Some vendors use the term *data alarm* to describe a device that senses network problems associated with the flow of data in other networks such as Ethernet.

See Also: *network management*

database

In its simplest form, a file used to store records of information, with each record containing multiple data fields. More generally, any application used to manage structured information.

Overview

Databases are an essential component of every business, representing the back-end of a company's information structure. Databases are used to store a broad range of information including inventory, customer contacts, sales records and invoices, catalogs, and so on. Without databases, modern businesses could not operate with the scope and range that they have, as they would be overwhelmed with information they could not manage.

Databases allow information to be stored, updated, manipulated, and queried. Sales figures for a given month can be extracted from a database using a standard programming language for building queries called Structured Query Language (SQL), versions of which are built into products from every database vendor.

Implementation

The most popular type of database is the relational database, in which the records are stored in tables that are related to each other using primary and foreign keys. A primary key is the field in each record that uniquely defines the record. (For example, a part number might be used as the primary key in a table that holds the price of each item a company sells.) A foreign key is a field in another table that matches the first table's primary key, creating a relationship between the two. An application for creating and managing relational databases is called a relational database management system (RDBMS).

Records are like the rows of a table. Each record is a collection of information about some physical system or logical object. Field names are like the column names of a table. Each field name represents a property or attribute of the system or object. Databases are widely used by businesses for storing information about inventory, orders, shipping, accounting, and so forth.

Microsoft SQL Server is Microsoft Corporation's enterprise-level RDBMS. SQL Server databases are stored on devices. Each computer running SQL Server has four system databases plus one or more user databases installed on it. The system databases are as follows:

- The master database, which is used for tracking system-wide information.
- The tempdb database, which is used for temporary working storage and sort operations.
- The model database, which is a template for creating new databases.
- The msdb database, which is used to store system data and transaction logs and to support the SQL Server Agent service and its scheduling information. The msdb database is stored on two devices, the Msdbdata system device and the Msdblog system device.

Marketplace

Major players in the enterprise database market include Microsoft Corporation with its SQL Server, Oracle Corporation with its Oracle 9i, IBM with its DB2, and others. These database products frequently compete for mindshare in the enterprise arena by surpassing each other in TCP-C benchmark figures.

Competing with these major players are open-source databases such as MySQL from NuSphere Corporation and PostgreSQL from Great Bridge, which run on the Linux and Berkeley Software Distribution (BSD) platforms and build upon the stability of those platforms.

Given the ubiquity and importance of databases to business, a wide spectrum of tools is available for planning, implementing, managing, tuning, monitoring, and troubleshooting database platforms. For example, pocketDBA has a module for the wireless Palm OS handheld device which allows an administer to remotely monitor and manage Oracle databases using a Palm. Similar applications will soon be available for the PocketPC platform as well.

Notes

The term *database* can have different meanings for different vendors. In Oracle products, for example, *database* refers to the entire Oracle DBMS environment. In SQL Server, databases provide a logical separation of data, applications, and security mechanisms, but in Oracle this separation is achieved using *tablespaces*.

See Also: *SQL Server*

database owner (DBO)

In Microsoft SQL Server, the user account that created the database and is responsible for managing administrative tasks related to the database.

Overview

Each SQL Server database is considered to be a self-contained administrative domain and is assigned a database owner (DBO) who is responsible for managing the permissions for the database and performing tasks such as backing up and restoring the database's information. The DBO also applies to any database object, including tables, indexes, views, functions, or stored procedures.

Essentially, the DBO can do anything within the database. By default, the SA (system administrator) account is also a DBO account for any database on a computer running SQL Server. The DBO has full permissions inside a database that it owns.

Notes

To avoid the complexity of managing separate DBO accounts for each SQL Server database, you might want to perform all administration tasks—both server-wide and specific to the database—using only the SA account.

See Also: *SQL Server*

data communications equipment (DCE)

Any device that supports data transmission over a serial telecommunications link.

Overview

Typically, data communications equipment (DCE) refers to analog and digital modems, Integrated Services Digital Network (ISDN) terminal adapters, Channel Service Units (CSU), multiplexers, and similar devices. The purpose of a DCE is to provide termination for the telecommunications link and to provide an interface for connecting data terminal equipment (DTE) to the link.

The term *DCE* specifically refers to serial transmission, which generally occurs over links such as a local loop Plain Old Telephone Service (POTS) connection, an ISDN line, or a T1 line. An example of a DCE is an analog modem, which provides a connection between a computer (the DTE) and the local loop POTS phone line (the serial transmission line). A DCE accepts a stream of serial data from a DTE and converts it to a form that is suitable for the particular transmission line medium being used. The DCE also works in reverse, converting data from the transmission line to a form the DTE can use.

On a Cisco router, the DCE interface is typically an RJ-45 jack on the back of the router.

See Also: *data terminal equipment (DTE), Integrated Services Digital Network (ISDN), serial transmission, T-carrier*

Data Encryption Standard (DES)

The former U.S. government standard for encryption, now replaced by Advanced Encryption Standard (AES).

Overview

In 1972 the National Bureau of Standards called for proposals for an encryption standard to enable secure transmission of government documents by electronic means. IBM responded to the call with a 128-bit key algorithm called Lucifer, which was accepted in 1976, reduced to 56-bit key length, renamed Data Encryption Algorithm (DEA), and then further developed by the National Security Agency (NSA). In 1977, DEA was officially adopted as the Data Encryption Standard (DES) and became the official encryption standard of the U.S. government. DES is formally defined by Federal Information Processing Standard FIPS 46-1.

Implementation

DES is a symmetric encryption scheme in which both the sender and the receiver need to know the secret key in order to communicate securely. DES is based on a 56-bit key (actually a 64-bit key with 8 parity bits stripped off) that allows for approximately 7.2 x 10^{16} possible keys. When a message is to be encrypted using DES, one of the available keys is chosen and applied in 16 rounds of permutations and substitutions to each 64-bit block of data in the message. Because DES encrypts information 64 bits at a time, it is known as a block cipher.

Issues

DES was originally designed for hardware encryption (dedicated devices that encrypt information at high speeds). The newer AES standard is more flexible in its application, and performs well in a variety of different environments from small-footprint devices such as smart cards to ordinary desktop computers running standard operating systems.

While the large number of keys available makes DES fairly secure, it was known early on that DES was crackable in theory. In 1997, Whitfield Diffie and Martin Hellman (developers of Diffie-Hellman public key encryption) proposed a DES cracking machine that could in principle be built with existing hardware at a cost of about $20 million. Then in 1997 a DES key was successfully cracked using the idle processing cycles of 14,000 computers cooperating over the Internet. The next year a DES cracking machine costing only $210,000 was created by the Electronic Frontier Foundation (EFF). The EFF machine was capable of cracking a DES key in about four days. Despite these accomplishments, DES is still viewed in practice as a secure encryption algorithm because so far no other method for cracking DES keys than simple brute force (trying every possible key) has been found.

Notes

A more secure variant of DES, Triple DES, encrypts each message using three different 56-bit keys in succession. Triple DES thus extends the DES key to 168 bits in length, providing for a total of approximately 6.2 x 10^{57} different keys. Unfortunately Triple DES is a relatively slow encryption mechanism that is not suitable for some situations, such as cell phones having limited processing power.

Another symmetric encryption scheme is IDEA (International Data Encryption Algorithm), which uses a 128-bit key and performs 8 cipher rounds on 64 bit blocks of information. Other symmetric encryption schemes include Blowfish, CAST, RC2, RC4, and others. The most common examples of asymmetric encryption schemes are Diffie-Hellman and Rivest-Shamir-Adleman encryption (RSA).

See Also: *Advanced Encryption Standard (AES), encryption*

datagram

A term sometimes used as a synonym for packet, but most often meaning a packet that is sent across a network using connectionless services, where the delivery does not depend on the maintenance of specific connections between computers.

Overview

Networking protocol suites such as Transmission Control Protocol/Internet Protocol (TCP/IP) generally support both connection-oriented and connectionless delivery services. In TCP/IP, the Transmission Control Protocol (TCP) is responsible for providing connection-oriented services that guarantee delivery of Internet Protocol (IP) packets. On the other hand, the User Datagram Protocol (UDP) handles connectionless services that guarantee only "best-effort" delivery of datagrams. For networking services that use connectionless datagrams, higher-layer protocols must ensure delivery. Datagrams are generally small packets sent over the network to perform functions such as announcements.

See Also: *connectionless protocol, connection-oriented protocol, packet, Transmission Control Protocol/Internet Protocol (TCP/IP), User Datagram Protocol (UDP)*

data integrity

The correctness and consistency of data stored in a database.

Overview

Maintaining integrity is essential, because a database is only useful if its contents can be retrieved and manipulated as expected. For example, without data integrity, data could be input into the system and then be inaccessible. Data integrity must be enforced on the database server. The following items are among those that should be verified:

- Individual field contents during insertion, updating, or deletion of data
- The values of one field relative to another (especially for primary keys) and of data in one table relative to another (especially for foreign keys)
- Successful completion of database transactions

Database systems employ many features to ensure data integrity. For example, Microsoft SQL Server 7 makes use of data types, constraints, rules, defaults, declarative referential integrity (DRI), stored procedures, and triggers. All these play a role in keeping the integrity of the database intact.

See Also: *database, SQL Server*

data isolator

A device that protects serial equipment from voltage surges.

Overview

If two pieces of data terminal equipment (DTE) are connected by a long serial line, voltage differences with respect to ground between the devices can cause surges over the line that can damage the devices. This can be a problem in a mainframe environment when you connect terminals to asynchronous mainframe hosts using long RS-232 cables. The problem is especially troublesome when the cabling has to run outdoors between buildings or when nearby generators or other equipment induce voltages.



Data isolator. *Using a data isolator.*

The solution to these problems is to insert a data isolator between the mainframe host and the terminal. This isolator provides electrical isolation between the two devices, somewhat like an opto isolator for fiber-optic cabling. Data isolators typically use transformers to electrically isolate the two connected circuits from voltage surges. Data isolators can support high data transfer speeds, and they come with a variety of interfaces, such as RS-232, RS-422, and Time to Live (TTL) connections.

See Also: *data terminal equipment (DTE), serial transmission*

data line protector

A device that provides surge protection for network cables carrying data.

Overview

Data line protectors prevent voltage spikes and surges from damaging costly hubs, switches, routers, and other devices. They are essentially surge protectors that are placed inline between stations on the network and concentrating hubs or other devices in the wiring closet. Data line protectors are available from different vendors for virtually every kind of networking connection, including RJ-45 connections for Ethernet networks, RJ-11 connections for telephone lines, and RS-232 connections for serial lines.

You connect a data line protector directly to one of the two connected devices, and then you attach the ground wire to a good ground connection so that there will be a path for voltage surges to flow down. For Ethernet networks using unshielded twisted-pair (UTP) cabling, data line protectors are available with multiple ports that are attached directly to the hub or the switch. Additional 10BaseT surge protectors can also be installed directly on the stations on the network for more protection.



Data line protector. *Using a data line protector.*

Notes

Most newer hubs, switches, routers, and other networking devices include built-in data line protection circuitry, which eliminates the need for additional data line protectors.

See Also: *Ethernet*

Data Link Control (DLC)

Generally, the services that the data-link layer of the Open Systems Interconnection (OSI) reference model provides to adjacent layers of the OSI protocol stack. Specifically, Data Link Control (DLC) is a specialized network protocol.

Overview

The DLC protocol is used primarily for two purposes:

- To provide connectivity with IBM mainframe or AS/400 environments, such as Systems Network Architecture (SNA), which are configured to run

DLC. DLC complements SNA because SNA operates only at higher levels of the OSI model.

- To provide connectivity for network print devices (such as certain Hewlett-Packard printers that have their own network cards and are connected directly to the network).

DLC is not used as a network protocol in the usual sense of enabling communication among computers on the network. It is not used by the redirector by the Microsoft Windows 2000 operating system and so cannot be used for session-level communication over a network. DLC is not routable; it is designed only to give devices direct access to the data-link layer. DLC is supported by most Windows operating systems, including Windows 95, Windows 98, Windows Millennium Edition (Me), Windows NT, and Windows 2000. DLC is no longer supported on Windows XP and Windows .NET Server. Windows 95 OSR2 includes both a 16-bit and a 32-bit version of DLC.

Implementation

To use DLC on Windows 2000 to connect to a Hewlett-Packard network print device, perform the following steps:

1. Connect the printer to the network, and run the self-test routine to obtain the printer's MAC address. Also, think of a friendly name for the printer.
2. Install the DLC protocol on the Windows NT or Windows 2000 server that will be used as a print server for the network print device. (Use the Network utility or the Windows 2000 Network and Dial-Up Connections utility in Control Panel.)
3. Run the Add Printer Wizard on the print server, choosing My Computer, Add Port, Hewlett-Packard Network Port, and New Port. Enter the friendly name for the printer, and select its MAC address from the list (or type it if the print device is offline). In Windows 2000, run the Add Printer Wizard, then right-click on the printer in the Printers folder and choose Properties. In the Property sheet for the printer, click the Ports tab, click Add Port, select Hewlett-Packard Network Port, and then click New Port. Enter the friendly name for the printer and select its MAC address from the list (or type it if the print device is offline).

See Also: *data-link layer, Open Systems Interconnection (OSI) reference model, printing terminology*

data-link layer

Layer 2 of the Open Systems Interconnection (OSI) reference model.

Overview

The data-link layer converts frames of data into raw bits for the physical layer and is responsible for framing, flow control, error correction, and retransmission of frames. media access control (MAC) addresses are used at this layer, and bridges and network interface cards (NICs) operate at this layer.


Data-link layer
Logical link control (LLC) layer
Media access control (MAC) layer

Data-link layer. *Two sub-layers of the data link layer.*

The data-link layer establishes and maintains the data link for the network layer above it. It ensures that data is transferred reliably between two stations on the network. It is responsible for packaging data from higher levels into frames, which are basically constructs containing data, a header, and a trailer.

Uses

A variety of network protocols can be implemented at the data-link layer. These differ depending on whether you are establishing local area network (LAN) or wide area network (WAN) connections between stations. Data-link protocols are responsible for functions such as addressing, frame delimiting and sequencing, error detection and recovery, and flow control.

Examples of data-link protocols for local area networking include the following:

- IEEE 802.3, which provides the Carrier Sense Multiple Access with Collision Detection (CSMA/CD) access method for baseband Ethernet networks

- IEEE 802.5, which provides the token-passing access method for baseband token ring implementations

For WANs, data-link layer protocols encapsulate LAN traffic into frames suitable for transmission over WAN links. Common data-link encapsulation methods for WAN transmission include the following:

- Point-to-point technologies such as Point-to-Point Protocol (PPP) and High-level Data Link Control (HDLC) protocol
- Multipoint technologies such as frame relay, Asynchronous Transfer Mode (ATM), Switched Multimegabit Data Services (SMDS), and X.25

Implementation

For LANs, the Project 802 standards of the Institute of Electrical and Electronics Engineers (IEEE) separate the data-link layer into two sublayers. The reason for doing this is to make it simpler for network equipment vendors to develop drivers for data-link layer services. The two sublayers of the data-link layer are the following:

- **Logical link control (LLC) layer:** This is the upper of the two layers, which is responsible for flow control, error correction, and resequencing functions for connection-oriented communication, but which also supports connectionless communication. Programming of the LLC layer is generally done by software vendors.
- **Media access control (MAC) layer:** This is the lower of the two layers, which is responsible for providing a method for stations to gain access to the medium. Programming of the MAC layer is generally done by manufacturers of network cards and similar devices.

See Also: *Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA), High-level Data Link Control (HDLC), Open Systems Interconnection (OSI) reference model, Point-to-Point Protocol (PPP)*

Data Manipulation Language (DML)

A subset of Structured Query Language (SQL).

Overview

Generally speaking, the term *Data Manipulation Language (DML)* can apply to any nonprocedural computer language designed specifically for the manipulation of structured data. In common use, DML refers to a subset of SQL commands used specifically for manipulating data in a database. The four SQL commands that comprise DML are

- **SELECT:** Lets you retrieve rows from tables
- **INSERT:** Lets you add rows to tables
- **DELETE:** Lets you remove rows from tables
- **UPDATE:** Lets you modify rows in tables

See Also: *Structured Query Language (SQL)*

Data Over Cable Interface Specification (DOCSIS)

A specification defining standards for implementation of cable modem systems.

Overview

Data Over Cable Interface Specification (DOCSIS) is a set of standards developed by CableLabs together with a consortium of cable system vendors and operators to promote interoperability between different cable modem systems. The DOCSIS standards focus on the interaction between equipment at cable providers and their customers.

DOCSIS is also a certification issued by CableLabs to cable modem system vendors meeting DOCSIS specifications and requirements. CableLabs is responsible for certifying DOCSIS-compliant cable modems and related equipment.

Architecture

In its original and widely implemented version, DOCSIS 1 provides a specification for transmission of a single stream of data from a Cable Modem Termination System (CMTS) router at the provider, through a distribution system of more routers, to a cable modem at the customer premises. The cable modem data stream defined by DOCSIS is a best-effort shared-media system that uses contention on upstream traffic and has limited support for class of service (CoS) differentiation between different types of traffic. DOCSIS defines the physical and data-link layers for cable modem systems and solves the problem of eavesdropping due to the shared nature of the network by supporting 56-bit Data Encryption Standard (DES) encryptions of all cable modem traffic.



Data Over Cable Interface Specification (DOCSIS). *How DOCSIS works.*

DOCSIS 1 specifies the characteristics of upstream and downstream transmission as follows:

- **Downstream:** Data rates of 27 to 36 megabits per second (Mbps) using frequencies between 50 and 750 megahertz (MHz)
- **Upstream:** Data rates of 320 kilobits per second (Kbps) and 10 Mbps using frequencies between 5 and 42 MHz

A newer version of the specification, DOCSIS 1.1, has a number of enhancements over the original DOCSIS standard, specifically

- **Multiple data streams:** DOCSIS 1.1 supports creating multiple data streams from CMTS to customer premises. Each application can be assigned its own data stream and priority using multiprotocol label switching (MPLS) or Diffserv, and providers can assign service level agreements (SLAs) to business customers to guarantee bandwidth for each stream.
- **Classification of traffic:** Different forms of traffic can now be mapped to specific service flows according to their content. Thus a specific Web application could be assigned a specific service flow to ensure adequate class of service for that application. Service flows themselves can be preconfigured or can be dynamically established and torn down.
- **Network access:** Access to the network can be scheduled using several different schemes including real-time polling, non-real-time polling, and constant bit rate (CBR). This provides better performance for applications that perform poorly on the simple, contention-based shared network defined in DOCSIS 1.
- **Packet fragmentation:** Large packets can be fragmented to provide better quality of service (QoS) for applications such as Voice over IP (VoIP) that require low latency.

See Also: *cable modem*

Data Provider

A tool that simplifies data access to different kinds of data sources such as relational databases.

Overview

Also known as the OLE DB Provider for AS/400 and Virtual Storage Access Method (VSAM), Data Provider is included with Microsoft SNA Server version 4. It gives Web applications written with Microsoft Active Server Pages (ASP) technology the ability to access record-level mainframe AS/400 and VSAM file systems.

Using Data Provider, you can write applications that access legacy file data on mainframes and minicomputers running Systems Network Architecture (SNA). You can also directly access AS/400 file structures and

VSAM data sets using the IBM DDM protocol native to many IBM host systems without needing to install additional Microsoft software on the host system. You can also integrate unstructured legacy file data on host systems with data stored in a Microsoft Windows 2000 networking environment.

See Also: *Systems Network Architecture (SNA)*

Data Service Unit (DSU)

A digital communication device that works with a Channel Service Unit (CSU) to connect a local area network (LAN) to a telecommunications carrier service.

Overview

Data Service Units (DSUs) provide a modem-like interface between data terminal equipment (DTE) such as a router and the CSU connected to the digital service line. DSUs also serve to electrically isolate the telco's digital telecommunication line from the networking equipment at the customer premises. While the CSU connects to the termination point of the carrier's digital line at the customer premises, the DSU connects to the access device (typically a router) at the border of the customer's LAN.



Data Service Unit (DSU). *Using a DSU.*

Implementation

As an example, in T1 transmission technologies, the DSU converts network data frames that are received from the router's RS-232, RS-449, or V.35 serial transmission interface into the standard DSX framing format, encoding scheme, and voltages of the T1 line. The DSU also converts the unipolar networking signal into a bipolar signal suitable for transmission over the digital line. The DSU is also responsible for handling signal regeneration and for controlling timing errors for transmission over the T1 line. DSUs usually provide other functions such as line conditioning of the T1 line, as well as remote diagnostic capabilities such as Simple Network Management Protocol (SNMP), which allows the telco central office (CO) to monitor the state of the line at the customer premises.

Notes

DSUs are usually integrated with CSUs to create a single device called a CSU/DSU (Channel Service Unit/Data Service Unit). If these devices are separate, the telco usually supplies and configures the CSU, while the customer supplies the DSU. If the devices are combined, the telco usually supplies, configures, and maintains the CSU/DSU for the customer premises.

The DSUs (or CSU/DSUs) at either end of a digital data transmission line should be from the same manufacturer. If they are not, they might not communicate with each other correctly because different vendors employ different multiplexing and diagnostic technologies that are often incompatible with those of other vendors.

See Also: *Channel Service Unit (CSU), Channel Service Unit/Data Service Unit (CSU/DSU), T-carrier*

data source name (DSN)

A unique name used to create a data connection to a database using open database connectivity (ODBC).

Overview

Data source names (DSNs) are used by applications that need to access or manage data in its associated database. All ODBC connections require that a DSN be configured to support the connection. When a client application wants to access an ODBC-compliant database, it references the database using the DSN.



Create a New Data Source to SQL Server

This wizard will help you create an ODBC data source that you can use to connect to SQL Server.

What name do you want to use to refer to the data source?

Name: barney

How do you want to describe the data source?

Description: DSN for our new e-store that sells toys

Which SQL Server do you want to connect to?

Server: SQLSRV99

Data source name (DSN). *Configuring a DSN.*

You can configure a DSN for an ODBC-compliant database using the Microsoft Windows 2000, Windows XP, or Windows .NET Server Administrative Tools\Data Sources (ODBC) utility in Control Panel. You can create three kinds of DSNs:

- **User DSN:** This is visible only to the user who creates it and can be used only on the current machine.
- **System DSN:** This is visible to all users on the machine and is also accessible to Windows NT, Windows 2000, Windows XP, or Windows .NET Server services. A system DSN is stored in the registry.
- **File DSN:** This can be shared by users who have the same ODBC drivers installed. A file DSN is stored in a file.

Notes

When you design Web applications that use Microsoft ActiveX Data Objects (ADO) for accessing database information, be sure to use either a file DSN or a system DSN because ADO does not work with user DSNs.

See Also: *open database connectivity (ODBC)*

Data Space Transfer Protocol (DSTP)

A protocol for accessing large amounts of information stored in distributed locations.

Overview

The Data Space Transfer Protocol (DSTP) is a new protocol designed to transport gigabits of information at high speeds around the globe. DSTP finds typical applications in international research projects between different universities where large amounts of data are generated and need to be shared and analyzed. Typical applications include human genome analysis and particle physics.

Implementation

DSTP is derived from Network News Transfer Protocol (NNTP) and uses a similar stream architecture augmented by a command set similar to Simple Mail Transfer Protocol (SMTP). DTSP enables information stored in different formats on servers in different locations to be indexed and retrieved in the form of a database file consisting of rows and columns. Indexing and retrieval is facilitated using a key called a Universal Correlation Key (UCK), which is used to create an Extensible Markup Language (XML) index file by tagging columns in databases.

DSTP is capable of transferring multiple flat-file databases simultaneously at high speeds.

For More Information

Find out more about DSTP at *www.www.ncdm.uic.edu/dstp.*

See Also: *Network News Transfer Protocol (NNTP), Simple Mail Transfer Protocol (SMTP)*

data tap

A type of networking device that you can use to monitor the flow of data in serial lines.

Overview

Data taps provide an easy way to connect monitoring equipment such as data scopes to serial interfaces such as RS-232. These serial connections are used for a variety of networking purposes, including connecting data terminal equipment (DTE) such as servers and routers to data communications equipment (DCE), such as modems, and CSU/DSUs (Channel Service Unit/Data Service Units) for implementing wide area networks (WANs); connecting dumb terminals to asynchronous mainframe hosts; and connecting servers to plotters and other serial devices. Data taps generally display network traffic in binary, hexadecimal, or character format and are used for troubleshooting various kinds of network connections.



Data tap. *Using a data tap to troubleshoot a serial connection.*

A data tap is essentially a three-way connector in which the third connector interfaces with the test equipment. For RS-232 serial lines, data taps come in a variety of configurations, with mixtures of male and female DB-9 and DB-25 connectors.

See Also: *serial transmission*

data terminal equipment (DTE)

Any device that is a source of data transmission over a serial telecommunications link.

Overview

The term *data terminal equipment (DTE)* specifically refers to a device that uses serial transmission such as the transmissions involving the serial port of a computer. Most serial interface devices contain a chip called a universal asynchronous receiver-transmitter (UART) that can translate the synchronous parallel data transmission that occurs within the computer's system bus into an asynchronous serial transmission for communication through the serial port. The UART also performs other functions in a DTE, including the following:

- **Error detection:** Ensures that data arrives at its destination uncorrupted
- **Clocking:** Ensures that data is sent at the correct rate in order to be received at its destination

Typically, data terminal equipment (DTE) can be a computer, a terminal, a router, an access server, or some similar device. The earliest form of DTE was the teletype machine.

Implementation

To connect a DTE to a telecommunications link, you use data communications equipment (DCE). The DCE provides termination for the telecommunications link and an interface for connecting the DTE to the link. In other words, the DCE connects to the carrier's phone line and the DTE connects to the customer's network or system. The DTE and DCE are then joined together using a serial cable. Typical serial interfaces for DCE-to-DTE connections include RS-232, RS-449, RS-530, X.21, V.35, and HSSI.

An example of a DCE would be an analog modem, which can be used for connecting a DTE such as the serial port on a computer or router to the local loop connection of the Plain Old Telephone Service (POTS).


Data terminal equipment (DTE)
Data communications equipment (DCE)
LAN
UART
RS-232
Electrical isolation
Digital telecommunication link

Data terminal equipment (DTE). *Example of DTE.*

While the usual configuration is to connect DTE with DCE, there are situations where DTE may need to be connected to DTE, for example when a computer needs to be connected to a router using a serial interface. In this situation a null modem cable is required.

See Also: *data communications equipment (DCE), serial transmission*

DAWS

Stands for Digital Advanced Wireless System, a proposed standard for a multimegabit packet-switching radio network from the European Telecommunications Standards Institute (ETSI).

See: *Digital Advanced Wireless System (DAWS)*

DB connector

A common family of connectors used for connecting data terminal equipment (DTE).

Overview

The letters *DB* stand for *data bus* and are followed by a number that indicates the number of lines or pins in the connector. DB connectors were formerly called D-series connectors. DB connectors can be used for either serial or parallel connections between devices.

Common members of the DB family include the following:

- **DB-9:** A 9-pin serial connector for connecting modems, serial printers, mouse devices, and so on
- **DB-15:** A 15-pin connector for connecting such devices as Macintosh monitors and network interface cards (NICs) for 10Base5 drop cables
- **DB-25:** A 25-pin connector for connecting Macintosh Small Computer System Interface (SCSI) devices, modems, serial printers, parallel cables, and switch boxes, among other equipment
- **DB-37:** A 37-pin connector for connecting such devices as routers and Channel Service Units (CSUs)
- **DB-60:** A 60-pin connector for connecting such devices as Cisco routers

See Also: *connector (device), data terminal equipment (DTE)*

DBO

Stands for database owner, the user account in Microsoft SQL Server that created the database and is responsible for managing administrative tasks related to the database. The DBO also owns any database object, including tables, indexes, views, functions, or stored procedures.

See: *database owner (DBO)*

DCE

Stands for data communications equipment, which refers to any device that supports data transmission over a serial telecommunications link.

See: *data communications equipment (DCE)*

D channel

One of two channels used in Integrated Services Digital Network (ISDN).

Overview

An ISDN D-channel is a circuit-switched channel that carries signaling information between the customer premises termination and the central office (CO) of the telecommunications service provider, or telco. The letter *D* here stands for *data* or *delta*. The D channel is used to signal the telco CO when connections need to be created or terminated. The D channel is thus a control channel for ISDN call setup and tear down.



D channel. *How the D channel works.*

The D channel forms the "D" part of a 2B+D Basic Rate Interface ISDN (BRI-ISDN) line and carries signaling information at a rate of 16 kilobits per second (Kbps). On a 23B+D Primary Rate Interface ISDN (PRI-ISDN) line, the D channel carries signaling information at the faster rate of 64 Kbps.

Implementation

D channel communication uses a completely separate out-of-band communication network called the Signaling System 7 (SS7) network, as shown in the illustration. This telco network is dedicated solely to servicing system functions that are overhead as far as voice or data communication is concerned. The SS7 network on which D channel communication takes place makes possible the low latency of dial-up ISDN connections, which are typically 1 or 2 seconds (compared to a latency of 15 to 30 seconds for analog phone connections).

The data-link layer of the D channel is defined by the Q.921 standard and uses LAPD (Link Access Protocol, D-channel) for full-duplex, synchronous, serial communications. The physical layer of the D channel is no different from that of the B channel.

Notes

In ISDN voice communication, D channels are also used to activate special calling features such as line call forwarding and caller ID.

See Also: *B channel, Integrated Services Digital Network (ISDN), Link Access Protocol, D-channel (LAPD), out-of-band (OOB) signaling*

DCOM

Stands for Distributed Component Object Model, a Microsoft programming technology for developing distributed applications.

See: *Distributed Component Object Model (DCOM)*

DCOM Configuration Tool

A Microsoft Windows NT, Windows 2000, Windows XP, Windows .NET Server, and Windows 98 utility used to configure 32-bit Windows applications for Distributed Component Object Model (DCOM) communication between components of distributed applications on a network.

Overview

You can use the DCOM Configuration Tool to configure DCOM applications to run across computers on a network. Computers can be configured to operate as DCOM clients (making calls to DCOM servers), DCOM servers, or both. Using this tool, you can configure the locations of components of distributed applications and the security settings for those components.

Implementation

To start the tool, choose Run from the Start menu, and then type **dcomcnfg**. To use the tool to configure a distributed application, you must specify the security and location properties of both the calling client application and the responding server application. For the client application, you specify the location of the server application that will be called by the client. For the server application, you select a user account that will have permission to start the application and the user accounts that will run it.



☑ Enable Distributed COM on this computer

☐ Enable COM Internet Services on this computer

Default Distributed COM communication properties

The Authentication Level specifies security at the packet level.

Default Authentication Level: Connect

The Impersonation Level specifies whether applications can determine who is calling them, and whether the application can do operations using the client's identity.

Default Impersonation Level: Identify

☐ Provide additional security for reference tracking

DCOM Configuration Tool. *Using the DCOM Configuration Tool.*

Notes

Before you can use the DCOM Configuration Tool on Windows 98, you must be sure that user-level security is being used.

See Also: *Distributed Component Object Model (DCOM)*

DDNS

Stands for Dynamic DNS, a new feature of the Domain Name System (DNS) that enables DNS clients to automatically register their DNS names with name servers.

See: *dynamic DNS (DDNS)*

DDoS

Stands for Distributed Denial of Service, a form of Denial of Service (DoS) attack that employs a large number of intermediate hosts to multiply the effect of the attack.

See: *Distributed Denial of Service (DDoS)*

DDR (Demand-Dial Routing)

Stands for Demand-Dial Routing, a method of forwarding packets on request across a Point-to-Point Protocol (PPP) wide area network (WAN) link.

See: *Demand-Dial Routing (DDR)*

DDR (Dial-on-Demand Routing)

Stands for Dial-on-Demand Routing, a method for connecting two remote networks together using Integrated Services Digital Network (ISDN) and dial-up Public Switched Telephone Network (PSTN) connections.

See: *Dial-on-Demand Routing (DDR)*

DDS (digital data service)

Stands for digital data service, a family of leased line data communication technologies that provides a dedicated synchronous transmission connection at speeds of 56 kilobits per second (Kbps).

See: *digital data service (DDS)*

DDS (Digital Data Storage)

Stands for Digital Data Storage, a tape backup technology that evolved from Digital Audio Tape (DAT) technologies.

See: *Digital Data Storage (DDS)*

dead spot

In wireless networking, a location within the coverage area where a signal is not received.

Overview

Dead spots are typically caused by physical barriers (such as buildings or concrete structures) that absorb or reflect radio or microwave frequencies. The receiving station must relocate or the barrier must be moved if the station is to receive a signal. Dead spots can also be caused by high levels of electromagnetic interference (EMI) from heavy machinery (such as motors and generators) or broad-spectrum sources of radiation (such as microwave ovens). In these cases, too, the solution is to relocate the receiver or eliminate the source of interference.

See Also: *wireless networking*

decibel

A mathematical way of representing power ratios.

Overview

A decibel (dB) is the ratio of two values that measure signal strength, such as voltage, current, or power. This ratio is expressed using base 10 logarithms. In mathematical terms, this means that the decibel is defined as follows, where P1 and P2 are the power (signal strength) measurements:

$$\text{dB} = 10 \log_{10} (P1/P2)$$

Uses

In computer networking and telecommunications, decibels are the units used for measuring signal loss within a circuit. Decibels are also used in network cabling systems for measuring signal losses. In addition, quantities such as attenuation and near-end crosstalk (NEXT) for fiber-optic cabling are expressed in units that contain decibels. In this scenario, P1 is the strength of the signal when it enters the cabling system, and P2 is its strength at some later point, after it has traversed segments of cable, repeaters, connectors, and other cabling system components. The following table shows signal strength ratios expressed both as ratios and as decibels for conversion purposes.

Signal Strength Ratios

Signal Strength Ratio (P1:P2)	*Decibels (dB)*
1:1 (no signal loss)	0 dB
2:1 (50 percent signal loss)	-3 dB
4:1 (75 percent signal loss)	-6 dB
10:1 (90 percent signal loss)	-10 dB
100:1 (99 percent signal loss)	-20 dB
1000:1 (99.9 percent signal loss)	-30 dB

Notes

The Category 5 (Cat5) cabling version of unshielded twisted-pair (UTP) cabling has an attenuation rating of 30 dB/1000 feet. This means that after traveling 1000 feet (304 meters) along a UTP cable, the electrical strength of the signal typically diminishes by 99.9 percent and is only 0.1 percent of its original strength at the far end of the cable.

See Also: *cabling, fiber-optic cabling, unshielded twisted-pair (UTP) cabling*

DECnet

A protocol suite developed by Digital Equipment Corporation (DEC).

Overview

DECnet was originally designed in 1975 to allow PDP-11 minicomputers to communicate with each other. DECnet conforms to the Digital Network Architecture (DNA) developed by DEC, which maps to the seven-layer Open Systems Interconnection (OSI) reference model for networking protocols.



DECnet. *Overview of DECnet.*

DECnet is essentially a peer-to-peer networking protocol for all DEC networking environments. DECnet supports various media and link-layer technologies, including Ethernet, Token Ring, and Fiber Distributed

Data Interface (FDDI). The current release of DECnet is called Phase V, but DECnet is essentially a legacy protocol that is rarely used nowadays.

dedicated line

Any telecommunications line that is continuously available for the subscriber with little or no latency.

Overview

Dedicated lines are also referred to as leased lines, since businesses lease these lines from telcos so that they can have continuous, uninterrupted communication with branch offices and with the Internet. The opposite of a dedicated line is a dial-up line, which costs less because it is used intermittently and requires fewer telco resources. However, dial-up lines suffer from the delaying effects of latency as well as less available bandwidth. Dial-up lines are generally local loop Plain Old Telephone Service (POTS) connections that use modems and provide backup services for more expensive leased lines. Dedicated lines, on the other hand, use specially conditioned phone lines and are allocated to the subscriber's private domain with dedicated switching circuits. By contrast, circuits for dial-up lines are shared with all other subscribers in the Public Switched Telephone Network (PSTN) domain.

Dedicated lines can be either point-to-point or multipoint communication paths. They are generally synchronous digital communication lines, and are terminated with one of the following serial interfaces: RS-232, RS-449, RS-530, X.21, V.35, or HSSI.

Advantages and Disadvantages

The main advantages of dedicated lines are the following:

- They involve minimal connection delays and minimal latency for establishing communication.
- They provide a consistent level of service.
- They are always available without any busy signals.

The main disadvantage of dedicated lines is that they cost more than dial-up lines.

See Also: *dial-up line, leased line, T-carrier*

Dedicated Token Ring (DTR)

A high-speed Token Ring networking technology.

Overview

Dedicated Token Ring (DTR) is an extension of 802.5 Token Ring technologies developed as an evolutionary upgrade to higher speeds for Token Ring users. It defines a set of signaling protocols and topologies that are backward-compatible with standard Token Ring networking.

DTR uses the same 802.5 frame format as standard Token Ring and supports full-duplex communications using the Transmit Intermediate (TXI) protocol to allow simultaneous transmission and reception of frames by stations.

DTR uses special concentrators to create high-speed ring topology networks. A traditional Token Ring Multistation Access Unit (MAU) can be joined to a DTR concentrator to enable 802.5 stations to communicate over the high-speed ring.

Prospects

Although DTR began development in 1995, it has fallen into eclipse in recent years along with standard Token Ring technologies due to the continued evolution of Ethernet into its Fast Ethernet and Gigabit Ethernet (GbE) varieties.

See Also: *802.5, Multistation Access Unit (MAU or MSAU), Token Ring*

default gateway

An address in a routing table to which packets are forwarded when there is no specific route for forwarding them to their destination.

Overview

In an internetwork, a given subnet might have several router interfaces that connect it to other, remote subnets. One of these router interfaces is usually selected as the default gateway of the local subnet. When a host on the network wants to send a packet to a destination subnet, it consults its internal routing table to determine whether it knows which router to forward the packet to in order to have it reach the destination subnet. If the routing table does not contain any routing information about the destination subnet, the packet is forwarded to the default gateway (one of the routers with an interface on the local subnet). The host assumes that the default gateway knows what to do with any packets that the host itself does not know how to forward.


Router
Router
Local subnet
R
R
? Host ?
Host forwards packets if it doesn't know how to route them itself
Router
R
Default gateway interface

Default gateway. *How a default gateway works.*

When configuring a client machine on a TCP/IP internetwork, the client must know the Internet Protocol (IP) address of the default gateway for its network. On Microsoft Windows NT, Windows 95, and Windows 98 clients, you configure this information on the TCP/IP property sheet for the client. The property to configure is known as the Default Gateway Address. In Windows 2000, Windows XP, and Windows .NET Server, you can have a default gateway assigned automatically using Dynamic Host Configuration Protocol (DHCP).

See Also: *IP address, routing table*

Defense Messaging System (DMS)

A global messaging system for the U.S. Department of Defense (DoD).

Overview

The Defense Messaging System (DMS) is a program established by the U.S. Undersecretary of Defense (Acquisition) to develop an integrated, global messaging system for transferring classified and unclassified data. The Defense Messaging System (DMS) will replace the existing Automatic Digital Network (AUTODIN) system currently in use by the U.S. Department of Defense.

Microsoft Exchange DMS, a version of Microsoft Exchange Server, complies with the DMS specification. It is suited for government agencies that are required to use DMS-compliant products and for companies that do defense business with the U.S. government. Exchange DMS technology can be purchased only through Lockheed Martin Federal Systems.

See Also: *Exchange Server*

defragmentation

The process of reorganizing information written on disk drives to make reading the information more efficient.

Overview

When files on disk drives are frequently written, copied, moved, and deleted, the information stored on the drive tends to become fragmented over time. Instead of storing a file across several contiguous (successive) sectors of the drive, files tend to become split up into discontiguous (disconnected) portions scattered all over the drive. Then when the file needs to be accessed again, the drive heads need to skip around a lot to find and read the successive portions of the file, which is a slower process than if the file was located in only one continuous section of the drive. Fragmented drives thus perform more poorly for disk reads (and writes) than drives that are not significantly fragmented. And the more often files are modified on a drive, the more fragmented it tends to become and the more poorly it performs (you can hear the sound of a fragmented drive "thrashing" as it reads files while loading programs and data into memory).

To improve performance of a fragmented drive, the drive should be defragmented. A defragmentation tool is an application that reads portions of fragmented files, copies them to memory, erases them from the disk, and then copies them back to the disk in successive sectors or clusters for better performance. Defragmentation can be performed on files, free space, or both for best performance, and should be done regularly on all computers and particularly those (such as file servers) that experience a lot of disk reads and writes.

Marketplace

Studies by industry analysts have estimated that as much as $50 billion per year is being lost by businesses simply by failing to defragment computers regularly on their networks. While best gains are achieved by defragmenting servers regularly (performance gains of 10 percent to 20 percent are typical), workstations also perform better when periodically defragmented. In spite of these estimates, the present penetration of network defragmentation software in enterprise environments is currently less than 15 percent, so much work remains to be done alerting IT (information technology) administrators to the problem.

While Windows 2000 and other operating systems have their own built-in defragmentation tools, several third-party vendors offer defragmentation tools that are more powerful and manageable and allow an administrator to centrally configure and schedule defragmentation of computers across a network. Some of the more popular tools include Diskeeper from Executive Software (Windows 2000 includes a "light" version of this tool that lacks scheduling capability), PerfectDisk from Raxco Software, and Norton Speed Disk from Symantec Corporation.

delegation

A feature of Microsoft Windows 2000 and the Windows .NET Server family that simplifies the administration of Active Directory directory service.

Overview

Delegation is a process for simplifying the assignment of permissions and rights to an object, container, or subtree of containers or organizational units (OUs) within Active Directory. These permissions and rights can be assigned for the following purposes:

- Delegating management of a portion of Active Directory to a user or group of users by assigning permissions or rights to a portion of Active Directory
- Protecting a portion of Active Directory from unauthorized access by denying permissions or rights to a portion of Active Directory

Using delegation, the network administrator can distribute the job of managing an Active Directory enterprise-level implementation among a group of individuals, each with the appropriate permissions and rights to manage her or his portion of the directory. For example, users can be granted permissions and rights on the Users container so that they can create new users or modify the attributes of existing ones. In this fashion, the network administrator can be relieved of the tiresome duty of creating and configuring new user accounts by delegating the job to a junior administrator. Delegation is designed to relieve the network administrator of the burden of managing the entire Active Directory and is an important security management feature in Windows 2000 and Windows .NET Server.

You can perform delegation using the Delegation of Control Wizard, which is part of the Active Directory Users and Computers administrative tool, and you can use it to delegate administration of portions of Active Directory to other administrators and users.

Delegation is part of the security framework of Active Directory. Along with other features such as the discretionary access control list (DACL), inheritance, and trust relationships, it enables Active Directory to be administered securely, protected from unauthorized access.

Notes

Always delegate administrative control at the level of OUs, not at the level of individual objects. This allows you to better manage access to Active Directory because OUs are used to organize objects in the directory. One good idea is to delegate authority to those who are responsible for creating users, groups, computers, and other objects that commonly change in an enterprise.

Always assign permissions to groups instead of to individual users. Groups can be nested within one another and, together with inheritance of permissions, they provide a powerful tool for organizing the administration of Active Directory.

See Also: *Active Directory, Delegation of Control Wizard, permissions*

Delegation of Control Wizard

A wizard that you can run using the Active Directory Users and Computers administrative tool for networks in Microsoft Windows 2000 and the Windows .NET Server family.

Overview

The Delegation of Control Wizard facilitates delegating control of different portions of Active Directory directory service to other administrators and users. The wizard simplifies the process by allowing only the administrator to assign permissions at the level of organizational units (OUs). Assigning permissions to OUs rather than to particular directory objects ultimately simplifies the Active Directory administrator's work.

To start the wizard, open the Active Directory Users and Computers tool, select the OU for which you want to delegate control, and on the Action menu, choose Delegate Control. Specify the users or groups to whom you want to delegate control, the subset of object types in the OU for which this should take place, and the kinds of permissions you want to assign.

See Also: *Active Directory, delegation, permissions*

Demand-Dial Routing (DDR)

A method for forwarding packets on request across a Point-to-Point Protocol (PPP) wide area network (WAN) link.

Overview

Demand-Dial Routing (DDR) is a technology in Microsoft Windows 2000 and the Windows .NET Server family that uses PPP links to create on-demand connections for transferring packets to remote networks. DDR works with a variety of dial-up technologies, including Public Switched Telephone Network (PSTN), Integrated Services Digital Network (ISDN), and X.25.

DDR is used to connect networks and uses Windows 2000 and Windows .NET Server's Routing and Remote Access Service (RRAS). DDR links are represented by RRAS as demand-dial interfaces and can be either persistent or on-demand and either one-way or two-way initiated. DDR is different from remote access—in remote access a single user connects to a remote network, but in DDR two networks connect. Like remote access connections, however, DDR connections can use the same security and encryption mechanisms, be implemented using remote access policies, support Remote Authentication Dial-In User Service (RADIUS) authentication, and use advanced PPP features such as Multilink PPP (MPPP), Microsoft Point-to-Point Compression (MPPC), and Bandwidth Allocation Protocol (BAP).

Notes

Demand-Dial Routing (DDR) is not the same as Dial-on Demand Routing (DDR), a Cisco router technology for connectivity-on-demand between Cisco routers.

See Also: *Point-to-Point Protocol (PPP)*

demand priority

The media access control method used by 100VG-AnyLan networks.

Overview

100VG-AnyLan is a high-speed networking architecture developed by Hewlett-Packard and based on the Institute of Electrical and Electronics Engineers (IEEE) standard 802.12. Demand priority is the method by which stations on a 100VG-AnyLan network gain access to the wire for transmitting data.

Implementation

A 100VG-AnyLan network based on the demand priority access method consists of end nodes (stations), repeaters (hubs), switches, routers, bridges, and other networking devices. A typical 100VG-AnyLan network consists of a number of stations plugged into a cascading star topology of repeaters (hubs). Because of timing, a maximum of five levels of cascading of the physical wiring is permitted. Hubs are connected using uplink ports. Each hub is aware only of the stations directly connected to it and any hubs that are uplinked from it.


100VG-AnyLan hub
③ Client takes control of media to transmit, then relinquishes control
② Hub signals it is OK to transmit
① Client requests access to media

Demand priority. *How the demand priority media access method works.*

The key feature of the demand priority access method, as shown on the illustration, is that the 100VG-AnyLan hubs control which computers are allowed to transmit signals on the network at any given moment. Hubs can be thought of as servers and end nodes as computers (clients). With demand priority, a client (a computer with a 100VG-AnyLan network interface card installed in it) must first request access to the network media (cabling) before transmitting data. The server (hub) processes this request and decides whether to allow the client access to the media. If the hub decides to grant the client access to the wire, it sends the client a signal informing it of this decision. The client then takes over control of the media and transmits its data.

Demand priority is considered a contention method, but it operates differently from the Carrier Sense Multiple Access with Collision Detection (CSMA/CD) access method used in Ethernet networks. Cables in a 100VG-AnyLan network are capable of transmitting and receiving data at the same time using all four pairs of twisted-pair cabling in a quartet signaling method. Each pair of wires in a twisted-pair cable transmits and receives data at 25 megahertz (MHz), for a total bandwidth of 100 MHz. All contention on the network occurs at the hub. If two computers attempt to transmit signals at the same time, the hubs can either choose between the two signals based on priority or alternate between them if the priorities are equal. The hubs can do this because demand priority provides mechanisms for prioritizing transmission of different data types. Computers in demand priority networks can simultaneously transmit and receive data, and they do not need to listen to the network because the hubs control access to the wire.

See Also: *100VG-AnyLAN, Carrier Sense Multiple Access with Collision Detection (CSMA/CD), media access control method*

demarc

The point in a carrier's wide area network (WAN) service at which the customer's responsibility for line management ends and the carrier's responsibility begins.

Overview

Demarc is short for *demarcation point* and indicates the point at which the carrier assumes responsibility for troubleshooting the WAN connection. For example, if a carrier provides the customer with a Channel Service Unit/Data Service Unit (CSU/DSU) for a leased line, the CSU/DSU is included within the carrier's responsibility and the demarc point is the serial interface on the CSU/DSU to which the customer's router is connected. If the demarc point instead is the RJ-48 connector that terminates the leased line at the customer premises, then the customer is responsible for managing and troubleshooting (and possibly also providing) the CSU/DSU that connects to this connector.

See Also: *telecommunications services*

demilitarized zone (DMZ)

Also called a perimeter network, a security network at the boundary between a corporate local area network (LAN) and the Internet.

See: *perimeter network*

DEN

Stands for Directory Enabled Network, an initiative toward a platform-independent specification for storing information about network applications, devices, and users in a directory.

See: *Directory Enabled Network (DEN),*

denial of service (DoS)

Any attack conducted against a system that tries to prevent legitimate users from accessing it.

Overview

Denial of service (DoS) refers to a broad family of different methods that hackers use to try to prevent legitimate users from accessing Web servers, mail servers, networks, and other systems. DoS attacks exploit weaknesses inherent in the Transmission Control Protocol/ Internet Protocol (TCP/IP) suite, bugs in operating systems and applications, and holes in firewalls and other security devices. Over the last half dozen years, holes have been discovered in Apache, Berkeley Internet Name Domain (BIND), Sendmail, Internet Information Services (IIS), Common Gateway Interface (CGI), Simple Network Management Protocol (SNMP), and other systems that make them vulnerable to DoS attacks. Vendors of these systems have issued patches to guard against these attacks, but new ones are often being discovered. Generally speaking, DoS attacks occur when a malicious user consumes so many resources on a remote network or system that none are left for legitimate users who need them. The resources attacked might include processors, disk space, memory, network connections, modems, and telephone lines. In a way, a DoS attack is like driving an extra-wide truck down a freeway—the truck blocks legitimate traffic from getting through to its destination.

Another general goal of DoS attacks is to disable critical services on a machine. Once these services are disabled, requests from legitimate users cannot be serviced until the machine is rebooted. For example, if an attacker can send malformed packets to a Web server to shut down its Hypertext Transfer Protocol (HTTP) service, the attacker has succeeded in denying access to the server by its real clients.

History

DoS attacks are not new in theory—a similar technique, jamming, was used during World War II to render enemy radar systems unusable by overwhelming them with useless information. The developers of TCP/IP envisioned the possibility of DoS attacks early on as an inevitable result of the open nature of TCP/IP, but it was not until 1996 that DoS attacks caught widespread public attention when an Internet service provider (ISP) called PANIX in New York experienced a sustained DoS attack on its servers that denied Internet services to legitimate users for more than a week. This attack demonstrated the Internet's fragility and led many vendors to patch weaknesses in their products that could be exploited by DoS attacks.

DoS again made the front page in 1999 when a number of U.S. government Web sites (including the FBI's Web site) were attacked by disgruntled hackers as retaliation for an FBI crackdown on some of their members.

More recently, a new and deadlier type of attack called Distributed Denial of Service (DDoS) made headlines in February 2000 when a young Canadian nicknamed Mafiaboy allegedly denied service for several hours to a number of major commercial Web sites, including Yahoo!, eBay, Amazon.com, Buy.com, E-Trade.com, ZDNet, and CNN.com. Also in 2000, a coordinated Distributed Denial of Service (DdoS) attack was launched against the Internet's Internet Relay Chat (IRC) system, crippling the system for several weeks.

The Internet Engineering Task Force (IETF) is currently working on a new Internet protocol called ICMP Traceback Messages that, if implemented widely, would allow networks experiencing DoS attacks to better determine the source of the attacks. Until then, network managers and system administrators need to be vigilant in applying the latest patches to systems and monitoring their networks for evidence of intrusion and DoS attacks.

Types

There are a number of different types of DoS attacks. Some of these are described in some detail below, but others are mentioned only briefly.

- **Synchronous idle character (SYN) flooding:** This famous attack exploits weaknesses in the three-way handshaking protocol of TCP. Typically, SYN flooding is used to render a Web server's networking services unavailable. SYN flooding is a type of attack in which TCP connection request packets (SYN packets) are sent in large numbers to a Web server. These packets use a false or "spoofed" source IP address to hide the attacker to fool the server into sending responses to a nonexistent client. SYN packets are used to place the TCP ports in the SYN _RECEIVED, or "half-open," state on the Web server and then do nothing with them until they time out. If enough of these ports are half-opened, the server cannot handle requests from normal clients until the unused ports expire. Unfortunately, it takes time for the half-opened ports to time out because when a SYN packet is received, the server generates a SYN-ACK packet to acknowledge the request and then waits for a final ACK from the requester before fully opening the port for a communication session. (This is called a TCP three-way handshake.) However, that final ACK is not received because the source address in the SYN packet was spoofed. The SYN-ACK packet is thus retransmitted several times at increasingly longer time intervals until, after a total time of 189 seconds (in the implementation of TCP/IP on Microsoft Windows platforms), the server finally gives up and closes the half-open port. For that time period, the requested port is unavailable to perform any other services.
- **Ping of Death:** This type of attack floods a machine or network with malformed Packet Internet Groper (PING) packets to crash remote systems. Many operating systems are vulnerable to this type of attack, as are some routers and network printers. Check with your vendor for any patches that have been released to deal with this type of attack. Also be sure to configure your routers not to allow broadcasts to pass into your network from outside.
- **Smurf attack:** This variant of the Ping of Death employs an intermediate network to send broadcast pings to tie up a system. A broadcast ping is an Internet Control Message Packet (ICMP) directed to a subnet broadcast address and is received by all hosts on the subnet. The source address of the broadcast ping is spoofed to appear as the address of the machine being targeted. The effect is for the targeted system to receive a flood of ICMP Echo response packets, depending on how many intermediate systems are employed. For more information, see the article "Distributed Denial of Service (DDoS)" elsewhere in this chapter.
- **Overlapping fragment attack:** This attack fragments packets into small pieces and then reassembles them starting from the middle of a packet instead of the beginning. The resulting bad packets are held in the receiving system's buffer until the system's memory resources are full, causing the machine to hang up.
- **Address Resolution Protocol (ARP) cache poisoning:** This attack preloads false information into a system's ARP cache, preventing it from communicating over the network with other systems.
- **Domain Name System (DNS) cache poisoning:** This attack fills the cache on name servers with name lookup information about nonexistent hosts, causing legitimate name lookup requests to be dropped. Upgrading to the latest version of BIND solves this problem.
- **User Datagram Protocol (UDP) attack:** This attack causes two systems to send a continuous flood of UDP packets to each other, preventing legitimate network communications from being able to occur.

- **Mail bombs:** This type of attack tries to overwhelm mail servers by sending them large amounts of useless messages. Mail filters are the usual method for dealing with such attacks.

Notes

If users try to connect to an IIS Web server and receive error messages such as "The connection has been reset by the remote host," a SYN attack might be under way on your machine. (When the maximum number of TCP ports are in use [open or half-open] on a machine, the machine usually responds to any further connection attempts with a reset.)

To determine whether such an attack is in progress, type netstat -n -p tcp at the command prompt to see whether there are a large number of ports in the half-open SYN_RECEIVED state. If so, try using a network protocol analyzer such as Network Monitor to further examine the situation. You might need to contact your ISP to investigate the problem more closely.

If your server is under a heavy SYN attack, one fix you can try on Windows NT platforms running Microsoft IIS is to decrease the default timeout for terminating half-open TCP connections. Open the TcpMaxConnectResponseRetransmissions parameter in the registry and set it to 3, 2, or even 1 to reduce the timeout to 45, 21, or 9 seconds, respectively. However, if you set this parameter too low, legitimate connections might experience timeouts. Windows 2000 and Windows NT 4 Service Pack 3 have corrected this problem. A fix is available for Windows NT version 3.51 from Microsoft Corporation.

If your Cisco router is experiencing a SYN attack, use the TCP Intercept feature to validate incoming TCP connection requests to counter the flood.

For More Information

Visit these Web sites for useful information about DoS issues: CERT Coordination Center at *www.cert.org,* SANS Institute at *www.sans.org,* International Computer Security Association at *www.icsa.net,* FBI National Infrastructure Protection Center at *www.nipc.gov,* and Forum of Incident Response and Security Teams at *www.first.org.*

See Also: *Distributed Denial of Service (DDoS), hacking, security, spoofing*

dense mode

One of two forms of the spanning tree algorithm used in multicasting.

Overview

While sparse mode routing is designed to be efficient in routing multicast packets to clusters of hosts across a network, dense mode is intended for large-scale multicasting where hosts are spread out across every corner of the network. Dense mode thus assumes that hosts are densely concentrated in large subnets. An example of a situation where dense mode multicasting is required would be a large-scale webcast of a corporate presentation or sports event.

Implementation

Dense mode multicasting creates multiple routing trees, one for each multicast group. Dense mode multicasting floods the network with multicast packets and so assumes that a large amount of bandwidth is available for transmission. Packets are multicast to every area of the network, and then the unneeded branches of the routing tree are pruned for more efficiency.

Dense mode multicasting can employ several different routing protocols to handle the flow:

- Distance Vector Multicast Routing Protocol (DVMRP)
- Multicast Open Shortest Path First (MOSPF)
- Protocol Independent Multicast Dense Mode (PIM-DM)

See Also: *Distance Vector Multicast Routing Protocol (DVMRP), multicasting, Multicast Open Shortest Path First (MOSPF), Protocol Independent Multicast-Dense Mode (PIM-DM), routing protocol, spanning tree algorithm (STA), sparse mode*

dense wavelength division multiplexing (DWDM)

A multiplexing technology for achieving extremely high data rates over fiber-optic cabling.

Overview

Also known sometimes as simply wavelength division multiplexing (WDM), dense wavelength division multiplexing (DWDM) modulates multiple data channels into optical signals that have different frequencies and then multiplexes these signals into a single stream of light that is sent over a fiber-optic cable. Each optical signal has its own frequency, so up to 160 separate data streams can be transmitted simultaneously over the fiber using only eight different light wavelengths. In addition, each data stream can employ its own transmission format or protocol. This means that, using DWDM, you can combine Synchronous Optical Network (SONET), Asynchronous Transfer Mode (ATM), Transmission Control Protocol/Internet Protocol (TCP/IP), and other transmissions and send them simultaneously over a single fiber. At the other end, a multiplexer demultiplexes the signals and distributes them to their various data channels.



Dense wavelength division multiplexing (DWDM). *How DWDM is implemented.*

Marketplace

Many networking vendors now offer switching equipment that supports DWDM. Big players in this area include Lucent Technologies and Nortel Networks, with numerous smaller players being attracted to the market.

An example of a DWDM deployment is AT&T, which has implemented DWDM switching equipment through much of its long-haul backbone network to carry up to 80 different channels per strand of fiber, and is planning to upgrade this soon to 160 and eventually 320 channels per fiber. This managed DWDM service from AT&T is called Ultravailable Broadband Network, and it can provide 2.4 gigabits per second (Gbps) of bandwidth for metropolitan-area connections where it is available. AT&T targets mainly large enterprises that enter into long-term contracts for these services.

Prospects

DWDM is rapidly replacing time-division multiplexing (TDM) as the standard transmission method for long-haul high-speed fiber-optic carrier links. The main deployment issue for many carriers is cost: devices that support DWDM are more expensive because the laser light sources for generating signals over fiber must be extremely stable. The benefits are so great, however, that many carriers are moving toward implementing it on their backbone networks, particularly long-distance carriers (inter-exchange carriers, or IXCs) who see the greatest benefit/cost ratio in deploying it. DWDM is less likely to be used by competitive telcos (competitive local exchange carriers or CLECs) or baby bells (regional bell operating companies, or RBOCs) for their access networks because of the cost of upgrading equipment to support DWDM compared to simply laying additional fiber to meet their needs.

A newer all-optical switching technology called lambda switching has recently evolved from DWDM and promises significant advantages over traditional DWDM. As a result of these developments, some carriers are holding back on further DWDM deployments while they wait for the new technology to mature.

See Also: *fiber-optic cabling, lambda switching, time-division multiplexing (TDM)*

DES

Stands for Data Encryption Standard, the former U.S. government standard for encryption. It now has been replaced by Advanced Encryption Standard (AES).

See: *Data Encryption Standard (DES)*

desktop

The graphical user interface (GUI) for Microsoft Windows 95, Windows 98, Windows NT version 4, Windows 2000, Windows XP, and Windows .NET Server operating system platforms.

Overview

The desktop is the user's on-screen work area; its various icons and menus are arranged as if on top of a physical desk. Users can place items on the desktop, drag them around, move them into folders, and start and stop tasks using simple mouse actions such as clicking, double-clicking, dragging, and right-clicking.

When the Active Desktop feature of many of these platforms is selected, Web browser functions also appear on the desktop. Users can browse local and network file system objects along with content on the Internet using a familiar Web browser paradigm. Active Web content can be placed directly on the desktop and updated automatically.

See Also: *Active Desktop*

Desktop Management Interface (DMI)

A standard for managing desktop systems developed by the Desktop Management Task Force (DMTF), now the Distributed Management Task Force.

Overview

Desktop Management Interface (DMI) was designed to allow information to be automatically collected from system components such as network interface cards (NICs), hard disks, video cards, operating systems, and applications that comply with the DMI standard. DMI was designed to be operating system-independent and protocol-independent and was designed for use on local systems that do not have a network installed.

Implementation

DMI by itself does not specify a protocol for managing systems over the network. Instead, DMI must use an existing network management protocol such as Simple Network Management Protocol (SNMP) to send and receive information over the network. DMI is in fact similar in design to SNMP. Each component to be managed must have a Management Information Format (MIF) file that specifies the location of the component, name of vendor and model, firmware revision number, interrupt request line (IRQ), input/output (I/O) port address, and so on. MIF files are formatted as structured ASCII flat-file databases; the Desktop Management Task Force has defined several standard MIFs, including the Desktop System MIF file, the Adapter Card MIF file, and the Printer MIF file.

DMI service layer software running on the desktop collects information from DMI-enabled components and stores this information in the appropriate MIF file. The service layer thus acts as an intermediary between the DMI-enabled components and the DMI management application, and it coordinates shared access to the various MIFs installed on the desktop system. DMI management applications can then query the service layer on the desktop to obtain the various system components and applications from these MIF files. The service layer allows the management layer to interact with the MIFs by using commands such as

- **Get:** Obtains information from a MIF
- **Event:** Alerts the management application when certain events occur
- **Set:** Modifies the contents of a MIF

One advantage of DMI over SNMP is that DMI management applications can access MIF files even when they have no prior information about them.

DMI management applications include Intel Corporation's LANDesk and Microsoft Systems Management Server (SMS). SMS 1.2 uses standard DMI 4.5 MIF files to expose inventory data for systems it manages and then stores this information in a Microsoft SQL Server database.

Prospects

DMI is now considered a legacy specification, and the newer Web-Based Enterprise Management (WBEM) initiative from the DMTF has largely replaced it. WBEM specifies a Common Information Model (CIM) as a common abstraction layer for unifying the various existing data providers for system and network management, including DMI and SNMP. Microsoft Corporation has implemented WBEM into the Windows 2000, Windows XP, and Windows .NET Server family operating systems as Windows Management Instrumentation (WMI) and in Microsoft System Management Server 2.

See Also: *Common Information Model (CIM), Distributed Management Task Force (DMTF), Web-Based Enterprise Management (WBEM), Windows Management Instrumentation (WMI)*

destination address

The address to which a frame or packet of data is sent over a network.

Overview

The destination address is used by hosts on the network to determine whether the packet or frame is intended for them or for other hosts. The destination address is also used by routers to determine how to forward the packet or frame through an internetwork. The destination address can be one of the following:

- **Physical address:** For example, the media access control (MAC) address of an Ethernet frame
- **Logical address:** For example, the Internet Protocol (IP) address of an IP packet

Destination addresses can be either specific or general. Specific addresses point to a specific host on the network. A general address points the packet or frame to all hosts on the network or multicasts it to a specific multicast group of hosts on the network.

You can see the destination address of a packet or frame by using a network sniffer device such as Network Monitor, a tool included with Microsoft Systems Management Server (SMS). Network Monitor displays destination addresses in both ASCII and hexadecimal form.

Notes

The other kind of address in a packet or frame is the source address. This is the address of the host from which the packet originates (unless the source address is being spoofed).

See Also: *source address*

device

Generally, any hardware component that can be driven by software. In Microsoft SQL Server, a file used to store databases.

Overview

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, you can manage devices and their drivers using Device Manager, which you access through the System utility in Control Panel. In Windows NT, you can view, enable, disable, stop, and start devices using the Devices utility in Control Panel. You can also install and uninstall devices and update device drivers in Device Manager.

In Microsoft SQL Server, a device is a file used to store SQL Server databases. Multiple SQL Server databases can be stored on a single device, and a single database can span multiple devices.

The master system device contains four databases:

- The master system database, which is used for tracking system-wide information
- The tempdb system database, which is used for temporary storage purposes
- The model system database, which is a template for generating new databases
- The msdb database, which is used by SQL Server Agent for scheduling alerts and jobs, and recording operators

Dfs

Stands for distributed file system, a network file system that makes many shares on different file servers look like a single hierarchy of shares on a single file server.

See: *Distributed file system (Dfs)*

DHCP

Stands for Dynamic Host Configuration Protocol, a protocol that enables the dynamic configuration Internet Protocol (IP) address information for hosts on an internetwork.

See: *Dynamic Host Configuration Protocol (DHCP)*

DHCP client

Software running on an Internet Protocol (IP) host that enables the host to have its IP address information dynamically assigned using Dynamic Host Configuration Protocol (DHCP).

Overview

The term *DHCP client* can also describe the software component on a computer that is capable of interacting with a DHCP server to lease an IP address.

Microsoft Windows comes with DHCP client software that you can configure when you install the TCP/IP protocol suite. This software allows a machine to immediately take its place in TCP/IP internetworks using DHCP. Other operating systems might require that the DHCP client software be installed and configured separately.

Microsoft operating systems that can function as DHCP clients include the following:

- Windows .NET Server
- Windows XP
- Windows 2000
- Windows NT
- Windows 98
- Windows 95
- Windows for Workgroups with the Microsoft TCP/IP-32 add-on installed
- Network Client 3 for MS-DOS
- LAN Manager 2.2c

Notes

On machines running Windows 2000, Windows XP, and Windows .NET Server, the DHCP client is DNS-aware and uses dynamic update for registering addresses, which allows the IP address and fully qualified domain name (FQDN) of client machines to be assigned and supported together.

Windows NT, Windows 95, and Windows 98 clients can release and renew their IP address leases using the ipconfig command. This command can also be useful for resolving IP address conflicts or for troubleshooting DHCP clients and servers.

See Also: *DHCP server, Dynamic Host Configuration Protocol (DHCP)*

DHCP client reservation

A process for configuring a Dynamic Host Configuration Protocol (DHCP) server so that a particular host on the network always leases the same Internet Protocol (IP) address.

Overview

You can create a client reservation on a DHCP server if you want the server to always assign the same IP address to a specific machine on the network. You might do this to assign IP addresses to servers on the network because the IP addresses of servers should not change. (If they do, client machines might have difficulty connecting with them.) An alternative and more common way to assign a client reservation to a server is to manually assign a static IP address to the server.

On Microsoft Windows 2000– and Windows .NET Server–based networks you can create DHCP client reservations using the DHCP console, and in Windows NT you use DHCP Manager. Enter the media access control (MAC) address as the client's unique identifier. When the client with that address contacts the DHCP server to request an IP address, the server leases the reserved address to the client.

See Also: *DHCP console*

DHCP Client service

The service in Microsoft Windows 2000, Windows XP, Windows .NET Server, and Windows NT that implements the client component of the Dynamic Host Configuration Protocol (DHCP) on workstations and servers.

Overview

You can use the DHCP Client service to obtain Internet Protocol (IP) addresses and other Transmission Control Protocol/Internet Protocol (TCP/IP) configuration information from a DHCP server (such as a Windows 2000 or Windows NT server running the DHCP Server service).

Microsoft Windows includes support for DHCP and provides client software that lets you manage a machine's IP address over a network. This software runs as a service under Windows 2000, Windows XP, Windows .NET Server, and Windows NT. DHCP simplifies the administration and management of IP addresses for machines on a TCP/IP network.

See Also: *DHCP Server service, Dynamic Host Configuration Protocol (DHCP)*

DHCP console

A Microsoft Windows 2000 and Windows .NET Server administrative tool for managing the DHCP Server service on Windows 2000 Server and Windows .NET Server.

Overview

The DHCP console is the main tool used for managing and configuring all aspects of the Dynamic Host Configuration Protocol (DHCP) on a Windows 2000– and Windows .NET Server–based network and is implemented as a snap-in for the Microsoft Management Console (MMC).



Start IP Address	End IP Addr...	Description
172.16.11.249	172.16.11.249	IP Addresses excluded from distribution
172.16.11.240	172.16.11.254	Address range for distribution

DHCP console. *The DHCP console for Windows 2000 Server.*

You can use the DHCP console for the following standard DHCP administration tasks:

- Creating a scope of Internet Protocol (IP) addresses to lease to DHCP clients
- Creating a set of scope options, which are passed on to clients
- Configuring the lease duration for IP addresses leased to clients
- Viewing and terminating active leases on a network
- Creating reservations for servers that need specific IP addresses
- Monitoring DHCP statistics

The DHCP console also includes the following advanced features, which are new to Windows 2000 and are also included with Windows .NET Server:

- Automatic detection of rogue DHCP servers on the network
- Automatic self-assignment of temporary IP addresses to clients if a lease cannot be obtained from a DHCP server
- New DHCP options for multicast groups (class D IP addresses), superscopes for grouping together DHCP scopes for management purposes, and other vendor-specific functions
- Integration of DHCP and Domain Name System (DNS), allowing clients to use dynamic update to update their host names to IP address mappings in DNS server zone files

See Also: *Dynamic Host Configuration Protocol (DHCP)*

DHCP lease

The duration for which a Dynamic Host Configuration Protocol (DHCP) server lends an IP address to a DHCP client.

Overview

You can configure the lease duration using the Microsoft Windows NT administrative tool DHCP Manager or the Windows 2000 or Windows .NET Server console snap-in. If your Transmission Control Protocol/Internet Protocol (TCP/IP) network configuration does not change often or if you have more than enough IP addresses in your assigned IP address pool, you can increase the DHCP lease considerably beyond its default value of three days. However, if your network configuration changes frequently or if you have a limited pool of IP addresses that is almost used up, keep the reservation period short—perhaps one day. The reason is that if the pool of available IP addresses is used up, machines that are added or moved might be unable to obtain an IP address from a DHCP server and thus will be unable to participate in network communication.

See Also: *DHCP console*

DHCP options

Additional Internet Protocol (IP) address settings that a Dynamic Host Configuration Protocol (DHCP) server passes to DHCP clients.

Overview

When a DHCP client requests an IP address from a DHCP server, the server sends the client at least an IP address and a subnet mask value. Additional information can be sent to clients if you configure various DHCP options. You can assign these options globally to all DHCP clients, to clients belonging to a particular scope, or to an individual host on the network.

You can configure a number of different DHCP options using the Microsoft Windows 2000 or Windows .NET Server snap-in DHCP console, but the options listed in the following table are the ones most commonly used by Microsoft DHCP clients. In Windows 2000– and Windows .NET Server–based networks, options 3, 6, and 15 are commonly used.

DHCP Options

Number	*Option*	*What It Configures*
003	Router	Default gateway IP address
006	DNS Servers	IP addresses of DNS servers
015	DNS Domain Name	Parent domain of associated DNS servers
044	NetBIOS over TCP/IP Name Server	IP addresses of Windows Internet Name Service (WINS) server
046	NetBIOS over TCP/IP Node Type	Method of NetBIOS name resolution to be used by the client
047	NetBIOS over TCP/IP Scope	Restricts NetBIOS clients to communication with clients that have the same scope ID

See Also: *DHCP console*

DHCP relay agent

A host that enables a Dynamic Host Configuration Protocol (DHCP) server to lease addresses to hosts on a different subnet than the one the server is on.

Overview

DHCP relay agents make it unnecessary to maintain a separate DHCP server on every subnet in an internetwork. Without DHCP agents, every subnet on an internetwork would need at least one DHCP server to provide address leases to hosts on that subnet. With DHCP agents, you can manage with only a single DHCP server for your entire internetwork (though two are recommended in case of failure).



DHCP relay agent. *How a DHCP relay agent works.*

Implementation

The DHCP relay agent is a machine with the DHCP Relay Agent service installed and configured to forward DHCP requests to a DHCP server on a different subnet (as shown in the illustration). The process happens as follows:

1. A DHCP client on the subnet where the DHCP relay agent is configured broadcasts a request for a lease from a DHCP server.

2. Since there is no DHCP server on the client's subnet, the DHCP relay agent picks up the client's request and forwards it directly to the DHCP server on another subnet.
3. The DHCP server responds to the request by offering a lease directly to the client.

Notes

You can configure Microsoft Windows NT, Windows 2000 and Windows .NET Server machines to operate as DHCP relay agents. To configure a machine running Windows NT Server as a DHCP relay agent, you must do the following steps:

1. Install the DHCP Relay Agent service using the Services tab of the Network utility in Control Panel.
2. Configure the DHCP server that the agent will pass requests to. Do this on the DHCP Relay tab of the Microsoft TCP/IP Properties sheet of the TCP/IP protocol.

To configure a Windows 2000 server as a DHCP relay agent, follow these steps:

1. Open the Routing and Remote Access console from the Administrative Tools program group.
2. Expand the server node to display General beneath IP Routing in the console tree.
3. Right-click General, and select New Routing Protocol from the context menu.
4. Specify DHCP Relay Agent in the New Routing Protocol dialog box, and click OK.
5. Open the property sheet for DHCP Relay Agent under IP Routing in the console tree, specify the IP address of the DHCP server to which lease requests should be relayed, and click OK.
6. Right-click DHCP Relay Agent in the console tree, and select New Interface to specify a router interface on which relay will be enabled.

See Also: *Dynamic Host Configuration Protocol (DHCP)*

DHCP scope

A range of Internet Protocol (IP) addresses that a Dynamic Host Configuration Protocol (DHCP) server can lease out to DHCP clients.

Overview

You configure the DHCP scope using the Microsoft Windows NT administrative tool DHCP Manager or the Windows 2000 and Windows .NET Server snap-in DHCP console. The IP addresses are leased for a specific Time to Live (TTL), usually three days. Information about scopes and leased IP addresses is stored in the DHCP database on the DHCP server. The values for IP address scopes created on DHCP servers must be taken from the available pool of IP addresses allocated to the network. Errors in configuring the DHCP scope are a common reason for problems in establishing communication on Transmission Control Protocol/Internet Protocol (TCP/IP) networks.

Notes

If non-DHCP clients have static IP addresses that fall within the range of the server's DHCP scope, these static IP addresses must be excluded from the scope. Otherwise, two hosts might end up with the same IP address, one assigned statically and the other assigned dynamically, resulting in neither host being able to communicate on the network.

See Also: *DHCP console*

DHCP server

A server that dynamically allocates Internet Protocol (IP) addresses to client machines using the Dynamic Host Configuration Protocol (DHCP).

Overview

DHCP servers perform the server-side operation of the DHCP protocol. The DHCP server is responsible for answering requests from DHCP clients and leasing IP addresses to these clients.

DHCP servers should have static IP addresses. A DHCP server gives DHCP clients at least two pieces of Transmission Control Protocol/Internet Protocol (TCP/IP) configuration information: the client's IP address and the subnet mask. Additional TCP/IP settings can be passed to the client as DHCP options.

Implementation

To have Microsoft Windows 2000 or Windows .NET Server function as a DHCP server, install the DHCP Server service and manage it using the DHCP console snap-in for the Microsoft Management Console (MMC). To have Windows NT Server function as a DHCP server, install the DHCP Server service and configure it using the administrative tool DHCP Manager. Note that a DHCP server should generally not be a DHCP client—that is, it should have a static IP address.

Notes

If hosts on a TCP/IP network are randomly losing connectivity with the network one by one, the DHCP server might be down and unable to renew leases for IP addresses obtained by the clients. Without a valid IP address leased to them, DHCP clients cannot communicate over the network.

See Also: *DHCP client, DHCP Server service, Dynamic Host Configuration Protocol (DHCP)*

DHCP Server service

The service in Microsoft Windows 2000, Windows .NET Server, and Windows NT that implements the server component of the Dynamic Host Configuration Protocol (DHCP) on Windows 2000, Windows .NET Server, or Windows NT Server.

Overview

The DHCP Server service is an optional networking component that can be installed on

- Windows NT Server by using the Network utility in Control Panel, selecting the Services tab, and adding the Microsoft DHCP Server service. When this service is installed on a machine running Windows NT Server, the administrative tool DHCP Manager is also installed.
- Windows 2000 Server and Windows .NET Server by using the Add/Remove Programs utility in Control Panel, selecting Add/Remove Windows Components, and selecting Dynamic Host Configuration Protocol (DHCP) from Networking Services. When this service is installed on a machine running Windows 2000 Server or Windows .NET Server, the DHCP console administrative tool is implemented as a snap-in for the Microsoft Management Console (MMC).

Notes

The DHCP Server service should generally be installed only on a machine that has a manually assigned static IP address.

See Also: *Dynamic Host Configuration Protocol (DHCP)*

DHTML

Stands for Dynamic HTML, a proposed World Wide Web Consortium (W3C) standard developed by Microsoft Corporation for creating interactive multimedia Web content.

See: *Dynamic HTML (DHTML)*

Dial-on-Demand Routing (DDR)

A method for connecting two remote networks together using Integrated Services Digital Network (ISDN) and dial-up Public Switched Telephone Network (PSTN) connections.

Overview

Dial-on-Demand Routing (DDR) is a procedure used in Cisco routers to connect two remote networks only when there is traffic to forward between them. DDR uses circuit-switched dial-up connections that must first be established for communications to take place and that are torn down when communications are finished. DDR is not the same as remote access: in remote access a computer connects with a remote network, but in DDR two networks are being connected together using routers.

DDR is a way of minimizing costs over wide area network (WAN) links. DDR is only active when data needs to be sent to the remote network, and this is generally cheaper than having a dedicated or leased line connecting the networks that is on all the time.

Implementation

DDR is typically implemented using ISDN for backup WAN connections when the primary WAN link is a dedicated T1 line. DDR allows ISDN calls to be placed to one or more remote networks as required. These calls typically take less than 5 seconds to connect and begin transferring data. During the connection phase a switched circuit must be established between the networks. After the call is finished, this circuit is torn down after a prespecified idle time period has elapsed to save money. Since different circuits may be used for each DDR session, the quality of the connection can vary from session to session.

When used with ISDN, DDR allows different service types to be assigned to different kinds of traffic. Only traffic classified as "interesting" causes a dial-up session to be initiated—all other traffic is ignored by the DDR-capable router. A typical scenario might be to use DDR to connect when Simple Mail Transfer Protocol (SMTP) mail needs to be forwarded to a remote network. On a Cisco router you use the dialer-list command from the Internetwork Operating System (IOS) command set to specify which kinds of traffic are "interesting" from the standpoint of DDR. For IOS 11 and higher, DDR supports a number of different protocols including Internet Protocol (IP), Internetwork Packet Exchange (IPX), and Appletalk.

When implementing DDR for a WAN link, make sure you configure static routes to your remote network. Using dynamic routing will generate routing table advertisements that may trigger unwanted DDR sessions.

Notes

Dial-on Demand Routing (DDR) is different from Demand-Dial Routing (DDR), a Microsoft technology for forwarding packets on request across a Point-to-Point Protocol (PPP) WAN link.

See Also: *Integrated Services Digital Network (ISDN), routing*

dial-up line

Any telecommunications link that is serviced by a modem.

Overview

Dial-up lines are ordinary phone lines used for voice communication, but dedicated or leased lines are digital lines with dedicated circuits. Dial-up lines are generally much less expensive to use, but they have less available bandwidth.

Companies often use dial-up lines for occasional, low-bandwidth usage (such as remote access networking) or as a backup for more costly dedicated lines. Dial-up lines are shared with all subscribers in the Public Switched Telephone Network (PSTN) domain, while dedicated or leased lines are allocated solely to the subscriber's private telecommunications domain.

Besides dial-up lines using analog modems over local loop connections, there are also some digital services that can be dial up (instead of dedicated) in nature. These services include

- ISDN (Integrated Services Digital Network)
- X.25

See Also: *dedicated line*

DID

Stands for direct inward dialing, a service provided by a local exchange carrier (LEC) to a corporate client.

See: *direct inward dialing (DID)*

differential backup

A backup type in which the only files and folders that are backed up are those that have changed since the last normal backup occurred.

Overview

Unlike an incremental backup, a differential backup does not clear the archive attribute for each file and folder. You can use differential backups in conjunction with normal backups to simplify and speed up the process. If a normal backup is done on a particular day of the week, differential backups can be performed on the remaining days of the week to back up the files that have changed since the first day of the schedule. Differential backups are faster than normal backups and use less tape or other storage media.

Notes

Differential backups are cumulative (unlike incremental backups), so when you need to do a restore, you need only the normal backup and the most recent differential backup. Differential backups take longer to complete than incremental backups, but you can restore data from them faster.

See Also: *backup type, incremental backup*

Differentiated Services (DS)

A system for service classification of network traffic.

Overview

Differentiated Services (DS) was developed by the diff-serv working group of the Internet Engineering Task Force (IETF) as a framework for standardizing service classification mechanisms. DS manages network traffic based on the forwarding behaviors of packets instead of by traffic priority or application. DS is rule-based and can be used for policy-based traffic management.

Implementation

DS works by packaging Differentiated Services Code Point (DSCP) information within standard Internet Protocol (IP) headers. This DSCP information specifies the level of service required for the packet, and supports up to 64 different traffic forwarding behaviors. DSCP maps a particular packet to a packet hop behavior (PHB) applied by a policy to a DS-compliant router.

See Also: *quality of service (QoS)*

Diffie-Hellman (DH)

An encryption scheme used in public key cryptography.

Overview

Diffie-Hellman (DH) is an asymmetric encryption scheme that uses a key pair consisting of different public and private keys. The private key is used to encrypt the message, and the public key is used to decrypt it. DH also specifies a key exchange mechanism that allows private keys to be used over the Internet.

Another asymmetric encryption algorithm is RSA, developed by Ron Rivest, Adi Shamir, and Leonard Adleman. Asymmetric encryption schemes typically have much larger keys than symmetric schemes such as DES (Data Encryption Standard). A key for an asymmetric scheme is typically 10^{24} bits or larger. Asymmetric encryption schemes form the basis of the Secure Sockets Layer (SSL) protocol used on the Internet.

See Also: *Data Encryption Standard (DES), public key cryptography*

digital

Transmission of signals that vary discretely with time.

See Also: *digital transmission*

Digital Advanced Mobile Phone Service (D-AMPS)

The digital version of the Advanced Mobile Phone Service (AMPS) cellular communications system.

Overview

AMPS is the oldest cellular phone system still widely deployed. It is an analog system operating in the 800 megahertz (MHz) band and is based on the EIA-533 standard.

Digital Advanced Mobile Phone Service (D-AMPS) is the digital version of AMPS and is based on the IS-54 standard. D-AMPS has been around since 1992, and it builds on the large installed base of AMPS cellular network installations. D-AMPS is used in North and South America and in parts of Asia and the Pacific region. The technical name for D-AMPS is Time Division Multiple Access/IS-136.

Implementation

D-AMPS uses the same 800 Mhz frequency band as AMPS, specifically frequencies between 824 and 891 MHz (although a dual-band 800/1900 MHz system has also been implemented). D-AMPS also uses 30-kilohertz (kHz) channels as AMPS does, but whereas AMPS can carry only one conversation per channel, D-AMPS can carry between three and six conversations. As a result, D-AMPS extends the capacity of AMPS from 50 conversations per cell to up to 300 conversations per cell, making D-AMPS more efficient in bandwidth utilization than AMPS.

While AMPS transmits information continuously, D-AMPS transmits in bursts over a time-shared system based on Time Division Multiple Access (TDMA) technology as the media access method. D-AMPS is more immune to interference from noise than AMPS and can be scrambled to make it more secure (AMPS is very easy to eavesdrop on).

D-AMPS is cheaper and easier to implement than other digital cellular systems such as Code Division Multiple Access (CDMA), but its transmissions are not as secure as CDMA. D-AMPS represents a simpler upgrade path from AMPS than Global System for Mobile Communications (GSM), which also uses TDMA technology but does so in an incompatible format.

See Also: *Advanced Mobile Phone Service (AMPS), cellular communications, Code Division Multiple Access (CDMA), Global System for Mobile Communications (GSM), Time Division Multiple Access (TDMA)*

Digital Advanced Wireless System (DAWS)

A proposed standard for a multimegabit packet-switching radio network from the European Telecommunications Standards Institute (ETSI).

Overview

The Digital Advanced Wireless System (DAWS) will be compatible with the existing packet radio system called the Terrestrial Trunked Radio (Tetra), which enables terminals to communicate directly with each other in regions without cellular coverage.

DAWS is being developed in response to the rapid deployment of Global System for Mobile Communications (GSM) wireless cellular communication systems and the increasing demand for high-speed wireless mobile data services in response to the phenomenal growth of the Internet in recent years. The ultimate goal of the DAWS effort is to provide mobile wireless Asynchronous Transfer Mode (ATM) data communication services with full-terminal mobility over wide areas of roaming. ATM has been selected by ETSI as the technology of choice for the backbone of the future envisaged European Information Infrastructure (EII).

DAWS will be designed to support applications that require data rates in excess of the 2-megabit-per-second (Mbps) rate supported by the International Mobile Telecommunications-2000 (IMT-2000) standards, with eventual planned support for full ATM rates of 155 Mbps envisioned. Examples include wireless networking, Internet browsing, video conferencing, file transfer, and Voice over IP (VoIP).

See Also: *Global System for Mobile Communications (GSM), International Mobile Telecommunications-2000 (IMT-2000), Terrestrial Trunked Radio (Tetra)*

Digital Audio Broadcasting (DAB)

A specification for broadband digital radio.

Overview

Digital Audio Broadcasting (DAB) is a specification for broadband transmission of digital information at speeds up to 2.4 megabits per second (Mbps). DAB is designed for transmission of digital audio and is envisioned as a replacement for existing analog AM/FM radio systems. DAB is a European specification only; however, a similar (but not interoperable) specification called IBOC (In Band, On Channel) is being developed in the United States.

Uses

Although DAB is intended mainly for audio broadcasting and is regulated as such, the possibility of it supporting digital data broadcasts, and even Internet access, are currently being explored. Since digital audio only requires 56 kilobits per second (Kbps), DAB's 2.4 Mbps bandwidth leaves lots of room for broadcasting location-based information such as weather reports, traffic information, airline arrivals and departures, stock quotes, and so on.

Britain leads the world in DAB deployment, with five channels already allocated to the BBC. Other European countries and regions are following with their own deployments. Psion has introduced a DAB receiver that plugs into the USB port of a PC to provide users with reception of DAB broadcasts, and other vendors are developing similar devices.

Although DAB is a broadcast (one-way) service, some carriers are envisioning using DAB to provide users with high-speed Internet access by using conventional or wireless modems for the upstream connection and DAB for downstream.

Prospects

DAB may gain the advantage over 2.5G and third-generation (3G) cellular systems such as General Packet Radio Services (GPRS) and Universal Mobile Telecommunications System (UMTS) by being first-to-market with high-speed location-based digital broadcast services. Spectrum licenses for DAB have cost only a small fraction of what carriers have bid for 3G licenses, allowing DAB providers more liquidity for rolling out deployments rapidly.

See Also: *2.5G, 3G*

digital certificate

A technology similar to an identification card that can be used for verifying the identity of a user or service you are communicating with electronically.

Overview

Digital certificates are entities issued by certificate authorities (CAs), public or private organizations that manage a public key infrastructure (PKI). Digital certificates are the networking equivalent of driver's licenses, and they go hand in hand with encryption to ensure that communication is secure. Digital certificates verify the authenticity of the holder, and they can also indicate the holder's privileges and roles within secure communication. They can be used like driver's licenses for identification purposes or like bank cards (together with a password) to perform financial transactions in e-commerce and online banking. Digital certificates enable various rights, permissions, and limitations to be applied to their holders for various kinds of trusted communication purposes such as purchasing, government banking, benefits, and voting rights. The main function of a digital certificate is to associate a specific user with his public/private key pair.

Implementation

A digital certificate consists of data that definitively identifies an entity (an individual, a system, a company, or an organization). Digital certificates are issued by and digitally signed with the digital signature of the CA (once the CA has verified the identity of the applying entity). In addition to identification data, the digital certificate contains a serial number, a copy of the certificate holder's public key, the identity and digital signature of the issuing CA, and an expiration date. The CA also maintains a copy of the user's public key in its centralized certificate storage facility.

Digital certificates are formatted according to an International Organization for Standardization (ISO) standard called X.509 v3. The X.509 standard specifies that a digital certificate must contain the following information fields:

- Version number
- Certificate serial number
- Signature algorithm ID used
- Name of certificate issuer
- Validity period (for certificate expiration)
- Subject name (name of certificate owner)
- Public key information for subject
- Unique identifier of certificate issuer
- Unique identifier of subject
- Extensions
- Digital signature for all the above fields

Uses

Digital certificates and public key cryptography are used in the popular Secure Sockets Layer (SSL) protocol, which provides secure transactions over the Internet. Several types of digital certificates are involved in this process, including

- CA certificate, which identifies the certificate authority, such as those based on Microsoft Certificate Server, and is used by Web browsers and Web servers to validate client and server certificates
- Server certificate, which identifies a Web server such as Microsoft Internet Information Services (IIS)
- Client certificate, which identifies a Web browser such as Microsoft Internet Explorer

Notes

A digital certificate is not the same as a digital signature. A digital certificate is a file that certifies the owner's identity, contains the owner's public key, and can be used to support encrypted communication. The purpose of a digital certificate is to certify that the user has the right to use the public/private key pair that has been issued by the CA. A digital signature, on the other hand, contains identity information along with the message or document itself (which has been hashed using the private key of the sender), and it confirms the identity of the sender and ensures that the content of the message has not been modified in transit.

In other words, to send an encrypted transmission, a user signs the message with a digital signature. But in order to be able to do this at all, the user must first be issued a key pair and its associated digital certificate.

See Also: *certificate authority (CA), digital signature, public key cryptography*

digital dashboard

A technology based on Microsoft Office for customizing a user's interface to contain information from multiple data sources.

Overview

Digital dashboards allow users to consolidate business information from different sources such as personal folders, team folders, databases, messaging systems, Web sites, and so on. They provide a single, customizable user interface that helps users sift through and organize the mass of information crying for their attention in today's busy office environment.

Digital dashboards are designed to make knowledge workers more productive and help facilitate collaboration between teams of individuals. They are easy to build and customize and are based on standard Microsoft technologies, with Microsoft Outlook at the center of things.

Implementation

A digital dashboard in its simplest sense is a dynamic Web page displayed in Outlook. Outlook is the messaging and collaboration component of Office and acts as the infrastructure on which digital dashboards are constructed. Using Office Web Components (OWCs), developers can build systems that can allow documents, messages, spreadsheets, databases, and charts to be generated and published from back-end systems and displayed through digital dashboards. Typical back-end systems that can support digital dashboards include Microsoft Exchange Server, which lets users create and share team folders for collaboration purposes, and Microsoft SQL Server, an online analytical processing (OLAP) repository for storing and analyzing business data.

For More Information

You can download the Digital Dashboard Starter Kit from *www.microsoft.com/business.*

See Also: *Exchange Server, Outlook, SQL Server*

digital data service (DDS)

A family of leased line data communication technologies that provides a dedicated synchronous transmission connection at speeds of 56 kilobits per second (Kbps).

Overview

DDS was originally a trademark for an AT&T all-digital service running at 56 Kbps, but it has evolved into a general descriptor for a variety of digital services offered by different carriers under various names. Digital data service (DDS) is available in both a dial-up version called Switched 56 and a dedicated leased line service for continuous connections. The dial-up version can serve as a backup for the dedicated version. The more common dedicated version are lines with negligible connection establishment latency; they are always on and never busy.

Implementation

Typically, DDS uses four wires to support digital transmission speeds of 56 Kbps, but it is actually a 64-Kbps circuit that uses 8 Kbps for sending signaling information. Some vendors provide a variant of DDS with a data transmission rate of a full 64 Kbps—this service is sometimes called Clear 64.

To use DDS services for wide area network (WAN) connectivity, route packets from your local area network (LAN) through a bridge or a router, which is connected by means of a V.35 or RS-232 serial interface to a Channel Service Unit/Data Service Unit (CSU/DSU). The CSU/DSU is connected to the four-wire termination of the DDS line by means of an M-block connector, a screw terminal block, or some other connection mechanism. The Channel Service Unit (CSU) converts the data signal into a bipolar signal suitable for transmission over the telecommunications link. The DDS lines themselves use four wires and support speeds of 64 Kbps, but 8 Kbps of bandwidth is usually reserved for signaling, so the actual data throughput is usually only 56 Kbps.



Digital data service (DDS). *Implementing DDS.*

(DDS is only one example of a type of digital line; others include Integrated Services Digital Network (ISDN) and T1. DDS can be used in either multipoint or point-to-point communications and requires dedicated digital lines. DDS lines can also be used to connect buildings on a campus, usually with a maximum distance of about 3 miles (5 kilometers).

Notes

Another name for DDS is Dataphone Digital Service.

See Also: *Switched 56, telecommunications services*

Digital Data Storage (DDS)

A tape backup technology that evolved from Digital Audio Tape (DAT) technologies.

Overview

Digital Data Storage (DDS) is a tape backup technology broadly used in all levels of businesses. DDS provides high capacity and performance at a relatively low cost. Although commonly called DAT instead of DDS, this is a misnomer and refers only to the type of tape employed.

Implementation

DDS records information on tapes using a helical scan method similar to that used in VCRs. Tracks are laid down at an angle in sweeps across the width of the tape, which allows DDS tape drives to operate at slower speeds than parallel-scan drives. The result of lower tape speeds is less wear and tear on both the tape and the drive.

DDS tape drives use a Small Computer System Interface (SCSI) interface to connect to backup servers. Most DDS tape drives are capable of simultaneous reading and writing of information.

DDS comes in different flavors that determine capacity and backup speed. For example, DDS-2 supports backup of 4 gigabytes (GB) of data at a transfer rate of 46 megabytes (MB) per minute, and DDS-3 lets you back up 12 GB at 70 MB per minute. Higher levels, such as DDS-4, exist for large enterprise networks. These storage figures are for uncompressed data (double them for compressed data).

DDS tapes are cheap (usually costing under $10), which means that DDS is best used when your company's tape rotation scheme demands that a large number of tapes be used. DDS is a good solution for small to mid-sized companies implementing their first tape backup solution because it is inexpensive, easy to use, and performs well. The price of DDS tape drives starts at around $1,000.

See Also: *tape format*

digital line

An umbrella term for various kinds of digital telecommunications services.

Overview

The distinguishing feature of a digital line is that it is digital from end to end and does not employ any kind of analog modem technologies. As a result, digital lines have higher traffic-carrying capacities, less noise, and better error-handling features than analog lines. The term *digital line* can refer to circuits based on the following:

- Digital data service (DDS)
- Integrated Services Digital Network (ISDN)
- T-carrier services such as T1 lines, fractional T1, and T3
- Switched 56 services

See Also: *digital data service (DDS), Integrated Services Digital Network (ISDN), Switched 56, T-carrier*

Digital Linear Tape (DLT)

A tape backup technology.

Overview

Digital Linear Tape (DLT) was developed in 1991 by Conner (later acquired by Quantum Corporation) as a tape backup solution for large companies. DLT tape drives can typically back up information at rates as high as 300 megabytes (MB) per minute. DLT tape drives typically cost $10,000 or more and are available in robotic tape libraries as well as standard single-tape units. DLT was designed as an enterprise backup solution and is comparable to Exabyte Corporation's 8mm format in that respect.

Implementation

DLT is a channelized tape backup technology that allows multiple channels to be backed up simultaneously in parallel on a single tape. A DLT drive's tape head is stationary and has multiple read/write channels on it. As a result, DLT can back up information much more quickly than many other types of tape backup technologies such as 8mm or Digital Data Storage (DDS). An example is Quantum's DLT 7000 series, which supports backup of 35 gigabytes (GB) uncompressed (70 GB compressed) at transfer speeds up to 5 MBps.

Notes

Quantum has recently developed an upgrade to DLT called SuperDLT, which competes with linear tape open (LTO) tape drive technology in speed and storage capacity.

See Also: *tape format*

digital modem

Any type of modem used for synchronous transmission of data over circuit-switched digital lines.

Overview

Unlike analog modems, which convert analog signals into digital ones using analog-to-digital converter (ADC) technologies, digital modems operate on end-to-end digital services.

A common example of a digital modem is an Integrated Services Digital Network (ISDN) terminal adapter, which uses advanced digital modulation techniques for changing data frames from a network into a format suitable for transmission over a digital line such as an ISDN line. Terminal adapters are thus basically data framing devices, rather than signal modulators such as analog modems, so in some sense the term *digital modem* is a misnomer because no modulation actually occurs.

See Also: *Integrated Services Digital Network (ISDN)*

digital nervous system

A paradigm created by Microsoft Corporation for electronic connectivity between businesses.

Overview

A digital nervous system enables businesses to create efficient, integrated systems that are easy to use and manage. The digital nervous system can be viewed as the next evolutionary phase of the Information Age.

The idea of this business paradigm is that businesses connect to each other in a way that is similar to the organization of a living organism. Digital information—

whether it is text, graphics, audio, or video—flows between businesses much as electrical impulses flow between parts of the body. A stimulus of information entering one business that is generated by another business produces a response. The greater the complexity and the more interconnected the nervous system, the higher the organism—and the same applies to business. Greater interflow of digital information can lead to the evolution of new forms of doing business. The Internet and its related paradigms "intranet" and "extranet" serve as examples of this evolution. These concepts grew naturally—almost organically—from the complex interconnectedness fostered by advances in software and networking.

For More Information

You can visit the Digital Nervous System site at *www.microsoft.com/dns.*

Digital Signal Zero

More usually known simply as DS-0, a transmission standard for digital telecommunications having a transmission rate of 64 kilobits per second (Kbps) and intended to carry one voice channel.

See: *DS-0*

digital signature

An electronic signature that you can use to validate the identity of the sender of a digital transmission.

Overview

Digital signatures can be used to sign a document being transmitted by electronic means such as e-mail. Digital signatures validate the identity of the sender and ensure that the document they are attached to has not been altered by unauthorized parties during the transmission.

Uses

Digital signatures are mainly intended for signing documents that have a relatively short lifespan of no more than a few years. Examples include business contracts, invoices, and similar documents. They are not generally suited for documents requiring long-term archiving, such as medical or financial documents, because advances in cryptography might render them insecure within the next decade or so. If you use digital signatures for documents that have to be archived for the long term, you need to also include a verification trail of how the documents are transmitted and stored. This evidentiary trail might be necessary should the authenticity of these signatures ever be challenged in court.

Implementation

Digital signatures are based on public key cryptography. In order for digital signatures to work, the sender must have both a digital certificate and a key pair issued by a certificate authority (CA) such as VeriSign.

A digital signature for a particular document is created by first performing a mathematical hash of the document. A hash is an iterative cryptographic process that employs a complex one-way mathematical function. To create digital signatures, a special hash called SHA-1 (Secure Hash Algorithm-1) is employed, and the end result of this process is a 160-bit text file called a message digest (MD). The MD is then encrypted using the sender's private key to create the digital signature, and the resulting signature is then attached to the document, which is then transmitted to its intended recipient. Note that each digital signature is unique and depends on the document being transmitted.

When the recipient receives the signed message, the same hash is performed on the received document to create a new message digest. The sender's public key is then applied to the MD, and the result is compared with the signature of the received message to determine whether the message is from its expressed recipient and whether it is intact or has been tampered with during transmission.

Marketplace

The complexity of public key cryptography and the wide variety of CAs in the marketplace have slowed the general adoption of digital signatures for sender verification purposes. In 2000, however, the U.S. government passed legislation called Esign (the Electronic Signatures in Global and National Commerce Act) that should speed widespread adoption of digital signatures. Esign basically makes digital signatures carry the same weight in law as regular signatures.


① Creating a digital signature
Sender's private key
Document
SHA-1 hash
Message digest
Encryption
Digital signature
Attach signature to document and send
② Verifying a digital signature
Sender's public key
Signed document
Remove signature
Document
SHA-1
Message digest
Decryption
Signature
Compare to verify sender
Verification string

Digital signature. *How a digital signature is created and verified.*

As a result of Esign, several vendors have started offering turnkey solutions for signing electronic documents that are designed to be as easy to use as sealing and stamping an envelope. Examples of such vendors include Digital Applications International, Silanis Technology, and signOnline. The first of these vendors to receive approval from a government agency was Silanis, whose Approvelt software was approved by the Food and Drug Administration (FDA) for government use.

A second group of vendors to emerge as a result of Esign consists of consulting companies whose products and services are designed to help large enterprises integrate digital signatures into their business processes. These vendors include Digital Signature Trust, NewRiver, Entrust Technologies, ValiCert, and DataCert.com.

A recent development that might lead to much wider use of digital signatures for signing documents is the implementation of public key infrastructure (PKI) technology by the United States Postal Service (USPS). In 2001, the USPS announced NetPost.Certified, a service that uses an electronic postmark based on digital signatures and stored on smart cards to guarantee the identity and integrity of electronic transmissions. NetPost.Certified is currently available only when one of the parties involved (sender or receiver) is the U.S government (where it should help streamline government by reducing the vast amount of paperwork needed for traditional document processing), but in a few years it is expected that the service will become more widely deployed in business use for signing contracts, deeds, affidavits, and other legal documents. The first U.S. government agency to use NetPost.Certified is the Social Security Administration, which uses it for vital statistics collections.

Issues

The weakest point in the digital signature process is making sure that the sender's private key is secure. The private key is normally stored on the hard disk of the sender's machine and is secured using a secret PIN (personal identification number) code known only to the sender. Because of its location on the hard drive, however, the private key is often vulnerable to hackers who break into networks to collect such information. Should hackers obtain a copy of your private key and somehow guess or determine your PIN code, they can sign electronic documents using your identity, and unless there is an evidential trail to the contrary, these signed documents would be legally enforceable.

To better protect the sender's private key, another new technology has emerged that may help propel the widespread use of digital signatures. This new technology is called Universal Serial Bus (USB) crypto-tokens, and it consists of a small device such as a smart card that securely stores the sender's private key in a medium inaccessible to hackers (you could, of course, still lose your USB token and land in trouble, but you could lose your driver's license as well, with similar results).

See Also: *cryptography, digital certificate, message digest (MD) algorithms, public key cryptography*

Digital Subscriber Line (DSL)

A group of broadband telecommunications technologies supported over copper local loop connections.

Overview

Digital Subscriber Line (DSL) was originally designed to provide high-speed data and video-on-demand services to subscribers. DSL is an always-on service such as Integrated Services Digital Network (ISDN) but works at much faster speeds compared to T1 (and even T3) leased lines for a fraction of the cost.

DSL uses the same underlying PHY layer as ISDN Basic Rate Interface (BRI) and is basically a form of modem technology that specifies a signaling process for high-speed, end-to-end digital transmission over the existing copper twisted-pair wiring of the local loop. DSL accomplishes this feat by using advanced signal processing and digital modulation techniques. DSL uses digital modems in which the digital signals are not converted to analog or vice versa; instead, the signals remain digital for the complete communication path from the customer premises to the telco's central office (CO).

DSL actually represents a family of related services commonly referred to as "*x*DSL," which includes the following:

- **Asymmetric Digital Subscriber Line (ADSL):** This flavor of DSL is asymmetric in nature, with different upstream (customer to carrier) and downstream (carrier to customer) speeds. ADSL theoretically supports data rates of up to 6.1 megabits per second (Mbps) downstream and 640 kilobits per second (Kbps) upstream at distances of 18,500 feet (5340 meters) from the telco CO. In practice, however, typical ADSL speeds are more like 1 Mbps downstream and several hundred Kbps upstream. Because of its faster downstream speeds, ADSL is ideal for high-speed Internet access. ADSL is an American National Standards Institute (ANSI) standard called T1.413.
- **G.Lite:** This is a variety of ADSL that was designed to be simpler to install at the customer's premises than regular ADSL (an external ADSL modem is used, and a splitter is not required at the customer's premises). G.Lite is an International Telecommunication Union (ITU) standard called G.992.2 and is sometimes called DSL Lite or ADSL Lite. Transmission rates for G.Lite range from 1.544 to 6 Mbps downstream and 128 to 384 Kbps upstream. GLite is growing in popularity as a "plug and play" form of DSL that customers can install themselves using DSL modems provided by providers. The disadvantage is that G.Lite generally has to be deployed using a second phone line because it provides unacceptable performance for voice transmission.
- **Rate-adjusted Digital Subscriber Line (RADSL):** This is a form of ADSL that dynamically negotiates the best possible speed based on changing line conditions. Speeds for RADSL are comparable to those for ADSL.
- **ISDN Digital Subscriber Line (IDSL):** This is essentially ISDN with no voice service, only data. IDSL provides 144 Kbps throughput in both directions, and unlike ISDN, it is always on and has no need for call setup.

- **High-bit-rate Digital Subscriber Line (HDSL):** This flavor supports high-speed, full-duplex communications over four-wire telephone lines at distances up to 12,000 feet (3650 meters) from a telco CO. HDSL provides equal upstream and downstream speeds of up to 1.544 Mbps, equal to a T1 line in throughput (it usually requires a conditioned line such as a T1 line as well). HDSL is usually deployed using bridges or routers instead of modems, and is best suited for wide area network (WAN) links.
- **Symmetric Digital Subscriber Line (SDSL):** This is a two-wire variety of HDSL that is the same in every respect except that it is half-duplex instead of full-duplex. Another name for this service is HDSL II.
- **Very-high-rate Digital Subscriber Line (VDSL):** This form of ADSL supports speeds of up to 54 Mbps upstream and 2.3 Mbps upstream over short distances of up to 1000 feet (305 meters). At longer distances the speed drops rapidly, and VDSL can rarely be provisioned beyond 4500 feet (1,370 meters) from the CO. VDSL is currently vendor-specific technology that has not been standardized, and because of its high speed and short distances, it is essentially a solution in search of a problem.

Uses

In the last few years, the use of DSL for residential broadband Internet access has skyrocketed, and DSL is currently the main competition for cable modem services to provide such services. DSL also can deliver other services to homes and businesses, including digital TV and Voice over DSL (VoDSL).

Another common use of DSL is for telecommuting (working remotely from home). DSL modems provide a cheap and easy way of gaining high-speed access to corporate intranets for telecommuters. DSL offers good security, performance, and reliability for telecommuters, but its distance limitation means that they must reside in metropolitan areas.

Many small to mid-sized businesses look on DSL as a replacement for aging 56 Kbps synchronous lines, ISDN lines, frame relay, and other traditional WAN services. DSL provides much higher bandwidth than these services, typically at half the cost or less. For example, although a T-1 line might cost more than $1,000 a month, HDSL can provide similar throughput for less than $400 a month.

Implementation

DSL can be deployed in different ways depending on the flavor being used. In ADSL, for example, an ADSL modem and a signal splitter are installed at the customer's premises and connected to the copper phone line. The splitter separates voice and data signals so that a single phone line can carry both voice and data. At the telco's CO, a Digital Subscriber Line Access Multiplexer (DSLAM) connects subscribers to a high-speed Asynchronous Transfer Mode (ATM) backbone, which typically uses a permanent virtual circuit (PVC) connection to an ISP for Internet access.

DSL modems can use a variety of signal coding methods, including carrierless amplitude and phase modulation (CAP) or discrete multitone (DMT) technology modulation, depending on the vendor's implementation, with CAP currently being the most popular modulation scheme used. DSL modems are simple Layer-2 devices that generally have few security features, lack remote management capability, and are intended for connecting a single computer to the Internet. For connecting an office LAN, a DSL router with built-in firewall and Network Address Translation (NAT) support is used instead of a DSL modem. All customer premises equipment (CPE) DSL devices are technically called ADSL Transmission Unit-Remote (ATU-R), and DSLAMs and similar DSL equipment at telco COs are known as ADSL Transmission Unit-Central office (ATU-C).

Advantages and Disadvantages

The main advantage DSL has over cable modem technology for delivering high-speed Internet access is that DSL uses ordinary phone lines to accomplish this, and such phone lines are everywhere. By contrast, cable TV, the service on which cable modem Internet access rides, has been widely deployed in residential areas but is rare in business districts and industrial parks. As a result, DSL has the advantage of having a ready-made wiring infrastructure, while cable companies have to invest money and effort to build their infrastructure out to business customers.



Digital Subscriber Line (DSL). *Implementing DSL for residential and business customers.*

DSL is also inherently more secure than cable modem services and offers better throughput guarantees. This is because each DSL connection between subscriber and telco CO is a dedicated connection. By comparison, all cable modem users in a given neighborhood essentially operate as a shared local area network (LAN). As a result, cable modem users can often see each other's computers on the network, and the more cable modem users simultaneously accessing the Internet in a given neighborhood, the slower the download speed everyone will experience. By contrast, DSL line speeds are independent of other users and depend only on the distance from the CO and the backbone capacity of the carrier's connection to the Internet.

For businesses, DSL can provide wide area network (WAN) links that are faster and cost less than traditional WAN services such as Frame Relay and ISDN. Unlike ISDN and modem-based services, DSL is an always-on technology as well.

DSL does have several disadvantages, however, the most important being its distance limitations. DSL typically cannot be deployed beyond 18,500 feet (5340 meters) from a CO, and even within this distance, the farther the subscriber is from the CO, the worse the connection and slower the speed. DSL is thus restricted mainly to dense urban areas and is often not an option in rural areas. Using remote DSL access terminals, however, some regional bell operating companies (RBOCs) are pushing DSL farther out from the CO (see Issues below).

Another issue is that DSL may be impossible to deploy over older portions of the PSTN. This is because load coils and bridged taps often prevent DSL signals from passing between the customer's premises and the telco CO. Load coils are induction coils that shift frequencies upward for voice transmission to compensate for unwanted wire capacitance, and unfortunately this often shifts voice transmission into the frequency band used by DSL, causing interference. Bridged taps are a shortcut method for telcos to provide local loop phone services to customers without actually running dedicated lines to those customers. Instead, an existing local loop line is tapped somewhere in the middle to run a line to a second customer. Too many such taps cause excessive echoes that can create noise that interferes with DSL signals. Finally, if a telco has fiber deployed anywhere along a local loop, DSL cannot be provisioned since it works only over copper and not over fiber (see Issues below).

DSL is also more difficult to provision than cable modem services. This is because to provision DSL typically requires the cooperation of three different companies: the DSL provider, which deploys the connection at the customer premises, the RBOC or inter-exchange carrier (IXC) from which the DSL provider purchases wholesale DSL services to retail to customers, and the ISP, which provides the actual connection to the Internet. As a result of this complexity, DSL provisioning can sometimes take weeks or even months, and when a connection goes down, finger-pointing among the different players can sometimes make for slow resolution of problems.

Finally, for business purposes traditional leased lines have a much better track record of reliability than DSL because of the aforementioned lack of cooperation among the DSL provider, RBOC, and ISP. T-1 lines are generally provisioned by a single company (the RBOC), which makes problems easier and quicker to troubleshoot. Medium and large companies often consider DSL an option for backup WAN services, but many are reluctant to make DSL their front-tier WAN service, despite the cost savings they can achieve by replacing their T-1 and fractional T-1 lines with DSL connections.

Marketplace

While most RBOCs offer DSL services, several independent DSL providers have recently appeared. However, some of these have failed or been acquired by RBOCs during the dot-com shakeout of 2000. Some of the larger players that remain in the pure-play DSL arena include Covad Communications Company, EarthLink, and Rhythms NetConnections. These providers are often classified as competitive local exchange carriers (CLECs), though their services are generally limited to DSL. Other names sometimes used to describe them include competitive DSL providers and DSL local exchange carriers (DLECs).

DSL providers generally offer high-speed residential Internet access for service charges in the range of $40 to $60 a month. Business customers generally pay up to 10 times more, primarily because of additional services supported, such as providing access to multiple users on a LAN, managed firewalls, service level agreements (SLAs), and top-tier customer support.

Some DSL providers offer a service called bonding, which allows two or more DSL connections to be combined into a higher throughput connection. In a typical bonding scenario, two or four 144 Kbps IDSL lines are connected to a DSL router and combined using MLPPP (Multilink PPP) into a single 576 Kbps connection. Bonding-enabled DSL routers are much cheaper to deploy at the customer premises than a DSLAM, which can accomplish the same thing but has greater space requirements.

Issues

A major issue that has hindered the widespread use of DSL is that different DSL vendors use proprietary solutions that make equipment from one vendor incompatible with that from another. This situation is particularly aggravating for businesses with offices scattered around geographically, as each office may use different equipment provided by different DSL providers or RBOCs. To overcome this issue, the OpenDSL initiative has been formed by 3Com Corporation, Cisco Systems, SBC Communications, Qwest Communications, and others. The goal of OpenDSL is to standardize all aspects of DSL the same way the Data Over Cable Service Interface Specification (DOCSIS) has done with cable modem technologies. Widespread acceptance of OpenDSL will likely drive DSL deployment further, especially in the business marketplace, but it is likely to take a few years for RBOCs and Competitive Local Exchange Carriers (CLECs) to replace their proprietary DSL systems with the new standard.

Although DSL appears to provide guaranteed throughput due to its dedicated connection (as opposed to shared-LAN cable modem services, where throughput decreases for each user as more users come online), such guarantees may not take into account the back-end configuration at the telco CO. For example, the DSLAM at the CO may become a bottleneck when multiple DSL subscribers all try to simultaneously download large files from the Internet. Even if the DSLAMs can scale to meet demand, the DSL provider's connection to the ISP can also be a bottleneck, particularly if the DSLAM is not colocated at the ISP's point of presence (POP). Business customers should be certain that the DSL provider they are considering working with has adequate DSL equipment at the CO end of the connection to guarantee the level of service they desire.

In an attempt to overcome DSL's distance limitation of 5.6 kilometers (3 miles) from the telco CO, some RBOCs have begun deploying remote DSL access terminals that are located within that distance of potential subscribers while being connected to the CO using fiber. This configuration allows RBOCs to push DSL out to remote neighborhoods to gain additional customers but has provoked a reaction from some pure-play DSL providers as it makes their own deployments difficult or impossible. This is because the fiber between the remote terminal and the CO makes it impossible for the DSL provider to provision DSL to customers directly from the CO (DSL cannot be provisioned over fiber). Furthermore, these remote terminals are often installed inside digital loop carrier (DLC) systems, small boxes deployed by RBOCs in neighborhoods, and these DLCs may not have sufficient space within them for DSL providers to deploy their own equipment to provision their own pushed-out DSL services (even if there is sufficient space, this means another costly expense for cash-strapped DSL providers). An example of this is Project Pronto, being deployed by SBC Communications, an RBOC. DSL remote terminals are sold by Alcatel, Lucent Technologies, and other vendors.

Prospects

Prospects are uncertain for some pure-play DSL providers. This is because the success of their DSL deployments depends on cooperation with both the RBOCs from which they lease local loop access and the ISPs they partner with to provide their DSL customers with Internet access. Nevertheless, DSL providers remain a popular choice for business customers seeking DSL services, mainly because such providers generally offer better service than some traditional RBOCs that have not yet adjusted to the new economy way of doing business. Pure-play DSL providers can also provide nationwide coverage compared to the regional coverage of most RBOCs, and this appeals to companies that have branch offices scattered geographically, but such rollouts are complicated by the fact that the DSL provider has to work with multiple RBOCs and ISPs to make everything work properly for such customers.

RBOCs, however, often have the advantage of having deeper pockets, which may give them a competitive edge in the long run over many competitive DSL providers. Furthermore, some larger RBOCs such as SBC Communications and Qwest are planning nationwide rollouts of DSL through partnerships and mergers with other providers.

An emerging technology that may help competitive DSL providers grow market share is line sharing. This technology lets a CLEC provision DSL to a customer over the same local loop connection that the RBOC uses to provide the customer with voice telephone service. In this way the DSL provider does not have to roll out a second phone line to the customer, which often takes weeks because it must be done in cooperation with the RBOC.

Notes

If you are using a DSL connection to the Internet, check with your DSL provider before you try to use it to deploy a public Web server, or else you might find your DSL service unexpectedly cut off once they discover what you are doing.

For More Information

You can find DSL news at *www.dslreports.com.* The DSL Forum Web site can be found at *www.adsl.com.*

See Also: *Asymmetric Digital Subscriber Line (ADSL), cable modem, G.Lite, High-bit-rate Digital Subscriber Line (HDSL), ISDN Digital Subscriber Line (IDSL), line sharing, Rate-Adjusted Digital Subscriber Line (RADSL), Symmetric Digital Subscriber Line (SDSL), Very-high-rate Digital Subscriber Line (VDSL)*

Digital Subscriber Line Access Multiplexer (DSLAM)

The DSL termination device at a telco central office (CO).

Overview

The Digital Subscriber Line Access Multiplexer (DSLAM) is an Asynchronous Transfer Mode (ATM) access device installed at the CO of a DSL provider. DSL lines coming from multiple subscribers terminate at the DSLAM and are multiplexed together to ride on the provider's ATM backbone, typically through a permanent virtual circuit (PVC) to an Internet service provider (ISP) to provide customers with Internet access.

A typical DSLAM can aggregate up to 100 DSL customer connections. Multiple DSLAMs are required for larger numbers of subscribers. DSLAMs usually have minimal support for quality of service (QoS) as they are often required to split off voice traffic from Internet Protocol (IP) data, and voice traffic is delay-sensitive in nature. Since DSLAMs usually package IP traffic into ATM cells, they cannot distinguish between different kinds of IP traffic to provide different levels of service to these different types of traffic. For service to customers who need to transport both voice and data traffic, telcos must set up a different PVC for each type of traffic and for each customer, which means that managing and configuring DSLAMs is a lot of work for a DSL provider that is rolling out thousands of DSL lines to customers. For example, if 50 customers need both voice and data DSL services, then 100 PVCs will need to be configured.

DSLAMs usually support only one kind of DSL service, but now reaching the market are newer DSLAMs are that support multiple services (including Asymmetric Digital Subscriber Line [ADSL], ISDN Digital Subscriber Line [IDSL], and Very-high-rate Digital Subscriber Line [VDSL]) across thousands of ports in a single device. These new DSLAMs have greater QoS support to enable them to carry Voice over DSL (VoDSL) services in addition to traditional wide area network (WAN) and Internet access services. Some new DSLAMs also act as concentrators, allowing traffic to be aggregated according to type. Thus if 50 customers require both voice and data DSL services, only two PVCs need to be configured, one for voice traffic and the other for data.

Marketplace

Some of the vendors offering state-of-the-art DSLAM equipment include Nortel Networks, Lucent Technologies, Paradyne, and Copper Mountain.

See Also: *Asynchronous Transfer Mode (ATM), Digital Subscriber Line (DSL), multiplexing, telco*

digital transmission

Transmission of signals that vary discretely with time.

Overview

Digital transmission signals vary between two discrete values of some physical quantity, one value representing the binary number 0 and the other representing 1. With copper cabling, the variable quantity is typically the voltage or the electrical potential. With fiber-optic cabling or wireless communication, variation in intensity or some other physical quantity is used. Digital signals use discrete values for the transmission of binary information over a communication medium such as a network cable or a telecommunications link. On a serial transmission line, a digital signal is transmitted 1 bit at a time.



Digital transmission.

The opposite of digital transmission is analog transmission, in which information is transmitted as a continuously varying quantity. An analog signal might be converted to a digital signal using an analog-to-digital converter (ADC) and vice versa using a digital-to-analog converter (DAC). ADCs use a method called “quantization” to convert a varying AC voltage to a stepped digital one.

See Also: *analog*

DIME

Stands for Direct Internet Message Encapsulation, a protocol for encapsulating attachments to Simple Object Access Protocol (SOAP) routing protocol messages.

See: *Direct Internet Message Encapsulation (DIME)*

direct burial fiber-optic cabling

Fiber-optic cable designed for burial.

Overview

Direct burial fiber-optic cable typically consists of multiple fiber-optic cables bundled together and enclosed in a protective sheath. Direct burial fiber-optic cabling is designed to be buried in trenches and contains a gel filling that protects the individual fibers from temperature and moisture variations. A strip of strengthening material runs axially down the cable to prevent excessive bending, which can fracture the individual fibers. Direct burial cabling can have steel-armor construction with heavy waterproof polyethylene jackets and can contain either multimode or single-mode fiber-optic strands.



Direct burial fiber-optic cabling. *Deploying direct burial fiber-optic cable to connect networks in different buildings.*

Uses

Direct burial cabling is more cost-effective than single-fiber cabling for long outdoor cable runs between buildings or across a campus because it allows for future bandwidth upgrades.

See Also: *fiber-optic cabling*

Direct Cable Connection

A Microsoft Windows tool that facilitates file transfers between two non-networked computers.

Overview

Direct Cable Connection can be used on Windows 95, Windows 98, Windows 2000, Windows XP, and Windows .NET Server to establish a temporary network connection for the purpose of transferring files between machines. Direct Cable Connection is implemented using a serial null-modem cable or a standard parallel cable. One computer must be designated as the host (the server) and the other as the guest (the client). The desired resources must be shared on the host computer, and Dial-Up Networking must be installed on the guest computer.

If desired, the host computer can also act as a router that allows the guest computer to access resources on other computers on the host computer's network.

See Also: *null modem cable*

directed frame

A frame that is being sent by one station to a specific destination station on the network.

Overview

On an Ethernet network, a directed frame is one that uses the hexadecimal MAC address of a specific target machine on the network as its destination address. The directed frame is picked up by the target machine and is ignored by all other machines on the network.

Directed frames are used for most network communication because they are the most efficient type of frame for communication. However, some services, such as network announcements, require that all stations on the network receive a frame. To send a frame to all stations on the network, you use a broadcast frame instead of a directed frame.

See Also: *broadcast frame, broadcast packet, directed packet*

directed packet

An Internet Protocol (IP) packet that is being sent by one host on a Transmission Control Protocol/Internet Protocol (TCP/IP) network to a specific destination host on the network.

Overview

A directed packet contains the IP address of a specific target host on the network as its destination address. The directed packet is picked up by the target host and is ignored by all other hosts on the network.

Directed packets are used for most network communication on a TCP/IP network because they are the most efficient method for communication. However, some services, such as network announcements, require that all hosts on the network receive a packet. To send a packet to all stations on the network, you use a broadcast packet instead of a directed packet.

See Also: *broadcast frame, broadcast packet, directed frame*

Direct Internet Message Encapsulation (DIME)

A protocol for encapsulating attachments to Simple Object Access Protocol (SOAP) routing protocol messages.

Overview

Direct Internet Message Encapsulation (DIME) is a protocol for encapsulating multiple payloads of arbitrary type and size for transmission in a single message construct. DIME is lightweight in nature and encapsulates binary information for transmission within SOAP messages. Since SOAP is based on Extensible Markup Language (XML), DIME performs a similar function to what Muiltipurpose Internet Mail Extensions (MIME) does for Simple Mail Transfer Protocol (SMTP) messages: provide a method for encoding binary attachments into text. The difference between DIME and MIME is that DIME is much simpler and faster to parse than MIME.

DIME can be used to encapsulate any binary information, including image files, XML data, and so on. DIME allows multiple logically connected records to be aggregated into a single message. DIME does not specify the type of messages being sent and can be used over any connection-oriented or virtual logical circuit.

Implementation

The DIME encapsulation format specifies only three additional pieces of information for each payload: the length of the payload in bytes, the type of payload (to allow routing of messages according to application type), and a payload identifier, which is basically a globally unique identifier (GUID).

See Also: *Simple Object Access Protocol (SOAP), XML*

direct inward dialing (DID)

A service provided by a local exchange carrier (LEC) to a corporate client.

Overview

Direct inward dialing (DID) uses a Private Branch Exchange (PBX) that allows outside callers to dial individuals within the company directly. Typically, the LEC allocates a block of phone numbers to the company, usually differing only in the last two, three, or four digits. For example, a company with 50 employees who each need a separate phone number could be assigned the numbers 555-1201 through 555-1250. Outside callers could dial the employees directly using these numbers, which are routed through perhaps only eight trunk lines that service the PBX, supporting a maximum of eight simultaneous calls. Inbound calls are routed by the PBX to the appropriate extension.

See Also: *local exchange carrier (LEC), Private Branch Exchange (PBX)*

directory

A tool designed to provide a single source for locating, organizing, and managing network resources within an enterprise.

Overview

Directories are used in enterprise networks to organize network resources so that they can easily be found and managed. These network resources typically include computers, disk volumes, folders, files, printers, users, groups, and other types of objects. Directories are typically used for one of two general purposes:

- **Internal directory:** These are directories used within the corporate network for publishing information about users and resources within the enterprise. A company's internal directory may be accessible to employees when they are outside the company network using a secure connection such as a virtual private network (VPN) connection, but it is not accessible to non-employees.
- **External directory:** These are directories typically located on servers in the perimiter network or demilitarized zone (DMZ) at the boundary between the corporate local area network (LAN) and the public Internet. External directories are typically made available to customers, clients, and business partners to provide them with selected business information such as catalogs and so on.

Network operating systems (NOSs) typically have their own directories built into them. This NOS directory functions much like the yellow pages of a phone book. For example, if you look up the word *printers*, you will find a list of available printers and information for accessing them. Examples of NOS directories include Windows NT Directory Services (NTDS) for Windows NT, Active Directory for Windows 2000, and Novell Directory Services (NDS) for Novell NetWare version 4 and higher.

Many applications use their own proprietary directories. An example is Microsoft Exchange 5.5, which uses a proprietary Exchange directory service based on the Microsoft Jet database. The more recent Exchange 2000 instead uses the Active Directory directory service of Windows 2000 for storing its hierarchy of information concerning Exchange directory objects.

An international standard has long existed for how directory services should operate and directory databases be structured. This standard, called X.500, was developed by the International Organization for

Standardization/International Electrotechnical Commission (ISO/IEC) in the 1980s. The X.500 standard specifies a protocol called Directory Access Protocol (DAP) that enables users and applications to search and modify an X.500 directory. Because DAP is complex and difficult to implement, a simpler protocol called Lightweight Directory Access Protocol (LDAP) was developed later on and has become the de facto standard for directory protocols. Active Directory, the directory service used by Windows 2000 and Windows .NET Server, is LDAP-compliant.

To function at the enterprise level, a directory should have the following essential characteristics:

- It should be scalable, so that it can grow to accommodate information and provide services as the enterprise itself grows.
- It should be extensible and have a schema that can be modified by adding new classes, objects, and attributes.
- It should provide simple ways of finding directory objects
- It should be possible to administer it from a single point on the network.

Active Directory for Windows 2000 and Windows .NET Server satisfies all these conditions.

Implementation

A directory typically consists of the following two components:

- **Directory database:** A hierarchical database structure that contains the actual information about the resources on the network.
- **Directory service:** Software that allows you to search for and locate information stored in the directory database.

In addition to these two components, consideration must be given to where the directory database is stored. This database is typically located on directory servers that are located at different points on the network. The database can be stored in the following ways on these servers:

- **Distributed:** In this scenario each directory server contains only a portion of the directory database for which it is authoritative. An example of a distributed directory service is the Domain Name System (DNS) found on the Internet.
- **Single-master:** Here one directory server contains a writeable master copy of the database, while all other directory servers contain read-only copies of this database. When changes need to be made to the directory, they are made first to the master server and then later copied to the other servers on the network. An example where this is used is in a Windows NT domain.
- **Multimaster:** Here each directory contains a writeable copy of the entire directory database. Modifications may be made to any directory server on the network, and these modifications are then automatically propagated by means of directory replication to all other servers on the network. An example of a multimaster directory is Windows 2000's Active Directory.

Marketplace

While Active Directory and NDS are the most popular general NOS directory products, there are also third-party directories that the enterprise architect may consider. One of the most popular of these is iPlanet's Directory Server, an LDAP server that is highly optimized for rapidly performing LDAP queries. Another is Novell's eDirectory, which is NDS uncoupled from the Novell NetWare NOS and made available for other platforms. Still another LDAP-compliant directory on the market is InJoin from Critical Path. Other popular directory vendors include Oracle Corporation and Innosoft International.

Some factors to consider when evaluating directory software for purchase for the enterprise environment include

- **Security:** Access to the directory can be managed by access lists and by policies. Some vendors provide additional tools for managing directory security. Examples of such vendors include Netegrity and Oblix.

- **Access method:** Nowadays everything needs to be Web-enabled, and information within an enterprise directory should be accessible by issuing LDAP queries over Hypertext Transfer Protocol (HTTP) through a simple Web browser.
- **Management tools:** Directories that can be managed using LDAP/HTTP are a distinct advantage over others where remote administration is concerned.
- **Namespace design:** Most general-purpose NOS directories map a company's geographical structure to its directory namespace. This may be the simplest and most logical thing to do, but whether it is most efficient for LDAP searching is something that you should consider before implementing the directory. For a company that has already implemented its directory but has trouble searching it efficiently, a product called RadiantOne from Radiant Logic can help by mapping a virtual LDAP namespace over the top of the existing namespace to speed search queries and maintain directory independence when the network configuration is changed.

Issues

The main issue confronting the enterprise concerning directories is interoperability. A large enterprise typically has many different directories implemented at various levels of its network, and consolidating all these directories into a single directory through migration is often impractical from the point of view of cost (large enterprises tend to be heterogeneous in many ways and for many reasons).

To allow directories from different vendors to share information with one another, a number of metadirectory products has appeared in the marketplace. Examples of metadirectory software include Microsoft Metadirectory Services (MMS) and Novell's DirXML.

Another issue regarding interoperability between directories is that the LDAP standard has certain limitations that require directory vendors to add their own proprietary extensions to LDAP if they want to give their LDAP directory products greater functionality. Thus even different LDAP-compliant directories from different vendors might not be able to interoperate to a desired degree. To solve this problem, an XML language called Directory Service Markup Language (DSML) is being developed to better allow different directories to communicate with one another. Other related initiatives include Simple Object Access Protocol (SOAP) and the Universal Description, Discovery, and Integration (UDDI) specification.

Finally, it must be mentioned that simply implementing a directory will not necessarily save costs for an enterprise or make the lives of administrators easier. Directories can be complex to implement, especially if legacy information needs to be migrated to them. Also, tools for managing directories can be difficult to use and require extensive training. As a result of such complexity, industry analysts estimated that as of 2000 less than 35 percent of all companies were using LDAP directories.

See Also: *Active Directory, Directory Access Protocol (DAP), directory database, directory replication (Windows 2000 and Windows .NET Server), Directory Service Markup Language (DSML), Lightweight Directory Access Protocol (LDAP), metadirectory, Novell Directory Services (NDS), Simple Object Access Protocol (SOAP), Universal Description, Discovery, and Integration (UDDI), Windows NT Directory Services (NTDS), X.500*

Directory Access Protocol (DAP)

A protocol for accessing information in a directory service based on the X.500 recommendations.

Overview

The Directory Access Protocol (DAP) specifies how an X.500 Directory User Agent (DUA) communicates with a Directory System Agent (DSA) to issue a query. Using DAP, users can view, modify, delete, and search for information stored in the X.500 directory if they have suitable access permissions.

DAP is a complex protocol with a lot of overhead, which makes it generally unsuitable for implementations in a Microsoft Windows environment. A simpler version called Lightweight Directory Access Protocol (LDAP) is growing in popularity and can be used to access and update directory information in X.500 directories. LDAP is more suitable than DAP for implementation on the Internet and has mostly superseded DAP as an access protocol for X.500-based directories (which are now often called LDAP directories).

See Also: *directory, Lightweight Directory Access Protocol (LDAP), X.500*

directory database

The central store of directory information on a network.

Overview

The directory database is one of two components of a typical directory application, the other being the directory service, which allows the directory database to be searched and modified.

In Microsoft Windows NT, Windows 2000, and Windows .NET Server, the directory database resides on the domain controllers, which manage all security-related aspects of the network. In Windows NT, the directory database is generally called the Security Accounts Manager (SAM) database. In Windows 2000 and Windows .NET Server, the directory database is the database component of Active Directory directory service.

Both the SAM database and the Active Directory directory service store information about objects on the network. The SAM is limited to storing information about users, groups, and computers that participate in the domain and security policy information such as password expiration policies and audit policies. The SAM stores its information in a privileged area of the registry. The practical upper limit for a SAM database is 40 megabytes (MB), which corresponds to approximately 26,000 user and computer accounts. If an enterprise has more than 26,000 users, the Windows NT directory database can be partitioned (split) into two or more portions and trust relationships can be configured according to a multiple master domain model.

Active Directory is considerably more flexible and powerful than the Windows NT SAM. Active Directory scales upward to tens of millions of objects, and these objects may be users, groups, computers, printers, shares, and many other forms of information.

See Also: *Active Directory, directory, directory replication (Windows 2000 and Windows .NET Server), Security Account Manager (SAM) database*

Directory Enabled Network (DEN)

An initiative toward a platform-independent specification for storing information about network applications, devices, and users in a directory.

Overview

Directory Enabled Network (DEN) was started by Microsoft Corporation and Cisco Systems in 1997 with the goal of developing standards for directory-based management of network resources. DEN is a policy-based mechanism that binds a user's name and network access profile to a policy. This procedure maps users to network services to make a more intelligent network that can better manage its resources, especially bandwidth. User rights on the network and bandwidth allocation can then be assigned to the user by using the profile.

DEN's goal is to unify the disparate network management platforms in existence today to provide a single, directory-based, cross-platform specification for the development of standard network management systems. The DEN initiative is now managed by the Distributed Management Task Force (DTMF) and is open to network device vendors, Internet service providers (ISPs), independent software vendors (ISVs), carriers, and others who might be interested.

Prospects

DEN has not materialized as fast as many had hoped, but the Desktop Management Task Force (DMTF) is still guiding it toward final release within the next few years. Part of this is because one of the major driving forces initially behind DEN was the hope of managing quality of service (QoS) policies using directories. This would allow bandwidth to be allocated to users and applications more easily. The pressure to do this has lessened in the last few years, however, as bandwidth costs continue to drop, especially with the emergence of Gigabit Ethernet (GbE). As a result, QoS issues can be sidestepped in many situations simply by overprovisioning bandwidth. Furthermore, simple Internet Protocol (IP) QoS techniques such as 802.1p have lessened the need for more complex directory-based QoS schemes.

Technical issues have also hindered the development of DEN as a real-life specification. One recent step forward involved the mapping of Common Information Model (CIM) schema to Lightweight Directory Access Protocol (LDAP) so that CIM object information could be stored and accessed in LDAP-compliant directories such as Microsoft's Active Directory directory service.

See Also: *Active Directory, Common Information Model (CIM), directory, Distributed Management Task Force (DMTF), Lightweight Directory Access Protocol (LDAP)*

directory export

The process of exporting information from a directory to another application.

Overview

An example of directory export can be found in Microsoft Exchange Server, which supports the exporting of information about recipients stored in its directory database. This information can be exported to a comma-delimited text file (.csv file), edited, and then imported into another system.



MS Exchange server: PICASSO
Home server: All
C:\exchsrvr\bin\test.CSV
Recipients
☑ Include subcontainers

Export objects
☑ Mailbox
☑ Custom recipient
☑ Distribution list

Logging level
○ None
● Low
○ High

Character set
● ANSI
○ Unicode

☐ Include hidden objects

Directory export. *Configuring directory export for Exchange Server.*

For example, you can import recipient information into a spreadsheet to print it out. Or you can export the information into a spreadsheet, use spreadsheet functions to mass-modify certain fields, and then use directory import for re-importing the modified account information back into Exchange. Using directory export/import is in fact the usual method in Exchange for modifying the properties of a large number of recipients at one time.

See Also: *directory, directory import, Exchange Server*

directory hierarchy

The hierarchy of objects in a directory.

Overview

Directories typically store information about the objects they manage in a hierarchical fashion. As an example we can consider the containers and leaf objects in a Microsoft Exchange Server directory, which is displayed and configured using the Exchange Administrator program. This hierarchy is based on the directory recommendations given by X.500.


Microsoft Exchange Administrator - [Server PICASSO in Site toronto - PICASSO]
File Edit View Tools Window Help
PICASSO
9 Object(s)
5:49 PM

- samplecorp
  - Address Book Views
  - Folders
  - Global Address List
  - **toronto**
    - Configuration
      - Add-Ins
      - Addressing
      - Connections
      - Directory Replication
      - Monitors
      - Protocols
      - Servers
        - PICASSO
    - Distribution Lists
    - Recipients

Display Name	Modified
Private Information Store	1/18/99 1:37 AM
Protocols	9/15/98 8:54 AM
Public Information Store	2/19/99 3:45 PM
Server Recipients	Not available
Directory Service	9/15/98 8:59 AM
Directory Synchronization	11/20/98 9:36 AM
Message Transfer Agent	9/15/98 8:54 AM
System Attendant	9/15/98 8:59 AM
TCP (PICASSO)	9/25/98 10:55 AM

Directory hierarchy.

The Exchange directory hierarchy begins at a root object called the Organization container, and then branches down into sites, servers, connectors, recipients, and other objects. To configure any object in the directory hierarchy, you use its property sheet.

Objects in the directory hierarchy of Exchange come in two types:

- **Containers:** These can contain other directory objects. Containers usually also have configurable properties.

- **Leaf objects:** These are end nodes in the directory tree and whose properties can be configured using their property sheets.

See Also: *directory, Exchange Server, X.500*

directory import

The process of importing information into a directory from another application.

Overview

An example of directory import can be seen in Microsoft Exchange. Here the information to be imported must be in a format that the importing system can understand, usually a delimited text file such as a .csv file. Microsoft Exchange Server allows recipient information to be imported into its directory database and allows recipients exported from other mail systems to be imported into Exchange. For example, you can use the Exchange Migration Wizard to extract mailbox information from a foreign mail system into a .csv file. You can then import this information into a spreadsheet program such as Microsoft Excel, modify it as needed, and import it into Exchange to create new mailboxes in your organization for users of the foreign mail system who are migrating to Exchange.

See Also: *directory, directory export*

directory replication (Windows 2000 and Windows .NET Server)

A process that ensures that all directory servers contain identical copies of the directory database.

Overview

In a typical implementation of a directory, the directory database is replicated to a number of servers called directory servers. These servers are located at different points around the network to provide accessible points for clients needing to search the directory for resources on the network.

Implementation

As an example of the directory replication process, consider the Active Directory directory service in Microsoft Windows 2000 or Windows .NET Server, which stores copies of the directory database on machines called domain controllers. In Windows 2000, directory replication is thus the process of replicating Active Directory updates to all the domain controllers on the network. Directory replication ensures that users have access to resources on the network by ensuring that information about users, groups, computers, file shares, printers, and other directory objects is current on all domain controllers in the network.

Directory replication of Active Directory on a Microsoft Windows 2000– or Windows .NET Server–based network takes place in two ways, depending on whether the participating domain controllers are in the same site.

- **Intrasite:** Within a site, intrasite replication between domain controllers uses remote procedure calls (RPCs) by means of a dynamically allocated port number. This replication takes place automatically every five minutes. Domain controllers within a site exchange update information in a ring fashion, from one domain controller to another. This ring topology is established by a process called the Knowledge Consistency Checker (KCC) and ensures a minimum of two replication paths between each pair of domain controllers and a maximum replication hop count of three to support efficient replication and fault tolerance.
- **Intersite:** Between sites, intersite replication can use RPCs if the local area network (LAN) or wide area network (WAN) connection supports them or some other method, such as Simple Mail Transfer Protocol (SMTP) e-mail messages. Intersite replication uses a compressed format for more efficient use of slow WAN links and is easier to schedule and manage than intrasite replication. To take advantage of the greater flexibility of intersite replication and to use it instead of intrasite replication, configure your domain controllers to belong to more than one physical site.

See Also: *Active Directory, directory, directory database*

directory replication (Windows NT)

In Microsoft Windows NT, the replication of a tree of folders from one server to another using the Directory Replicator Service.

Overview

The Directory Replicator service is a Windows NT service for replicating files and folders over the network. The Directory Replicator Service simplifies the task of updating key network configuration files needed by all users, such as system policies and logon scripts. You can also use directory replication to load balance between multiple servers when a large number of users need access to specific files or folders.

You can perform directory replication in Windows NT to create and manage identical directory structures on different Windows NT servers and workstations. When a change is made to the master directory structure, such as modification of a file or addition of a directory, that change is replicated to the other computers. One use for directory replication is to provide a means for load balancing file system information across several servers. This allows more clients to efficiently access the data stored in the replicated directory structure because identical data is stored on different machines. For example, you might replicate a database of customer information across several servers in your network to provide easier access. You can also use directory replication to copy logon scripts from a primary domain controller (PDC) to a set of backup domain controllers (BDCs). You can configure replication to occur between different computers in a domain or from one domain to another.

Implementation

The Directory Replicator Service replicates files from an export computer to an import computer. The export computer must be running the Windows NT Server operating system, but the import computer can run Windows NT Server, Windows NT Workstation, or LAN Manager for OS/2 servers.

The export server is the computer that contains the master copy of the directory tree to be replicated. This export server must be a machine running Windows NT Server. The computers that will replicate with the export server are called import servers. Import servers can be machines running Windows NT Server, Windows NT Workstation, or LAN Manager Server.

Prior to configuring directory replication, you must create a new user account as a security context within which the replicator service will run. This account should have a password that never expires and should be a member of the Replicator, Domain Users, and Backup Operators groups. The account should be accessible from both export and import machines. Use the Services utility in Control Panel to configure the Directory Replicator Service to start automatically upon system startup and to use your new account for logging on.

Server Manager is the administrative tool used for configuring replication in Windows NT. You can configure replication to occur either immediately after a change is made to the directory structure or after a stabilization period. When configuring replication, you select one of the following options:

- Replicate the entire subtree of directories and files beneath a specific directory on the export server.
- Replicate only specific files contained in the subtree by applying locks to its directories and files to prevent them from being exported.

By default, the export directory in which the master copy of the replicated data is contained is located in the path %SystemRoot%\system32\repl\export. The default path to which the directory structure is imported on the import server is %SystemRoot%\system32\repl\import.

Notes

Do not use directory replication as a substitute for a regular program of tape backups. The Directory Replicator Service can create a lot of network traffic and should not be used for backing up data across a network. If the data you are replicating contains large files that change frequently, replication traffic can cause network congestion unless you watch it carefully. Be especially careful when you replicate directory structures over slower wide area network (WAN) links to avoid congestion that interferes with other essential forms of traffic such as logon traffic.

The Directory Replicator Service on Windows NT can export only one directory tree from a given export server. It is a good idea to leave the default export location as it is and move the directory structure and information you want to replicate to this default export location. This allows you to also replicate logon scripts because by default these are located on a PDC in the location %SystemRoot%\system32\repl\export\scripts and on a BDC in the location %SystemRoot%\system32\repl\import.

Since these script directories are located within the default export and import paths, they can be replicated along with other data.

directory service log

A log that contains events written by the Active Directory directory service on machines running Microsoft Windows 2000 or Windows .NET Server.

Overview

The directory service log exists only on domain controllers because these are the only computers that have copies of Active Directory. The directory service log contains events such as informational, warning, and error events concerning operations that have been performed on or by Active Directory. These events reveal the state of Active Directory and can be used for diagnostic and troubleshooting purposes.

Information in the directory service log can be displayed using Event Viewer, a Windows 2000 and Windows .NET Server administrative tool that runs as a snap-in for the Microsoft Management Console (MMC). Event Viewer for Windows 2000 and Windows .NET Server supports a number of different kinds of logs in addition to the three supported in the Windows NT version of Event Viewer, namely, the system log, security log, and application log. The actual types of event logs available in Windows 2000 and Windows .NET Server Event Viewer depend on which optional networking components are installed on the machine.

See Also: *Active Directory*

Directory Service Manager for NetWare (DSMN)

An optional Windows 2000 utility for managing directory information stored on NetWare servers.

Overview

Directory Service Manager for NetWare (DSMN) enables Windows 2000 domain controllers to manage account information on NetWare 2.*x*, 3.*x*, and 4.*x* servers. It does this by copying NetWare account information to the primary domain controller (PDC) and then propagating changes back to the bindery on the NetWare servers. DSMN also synchronizes accounts across all NetWare servers allowing users to access any NetWare server using a single logon username. DSMN does not come with Windows 2000 but can be ordered separately from your Microsoft value-added reseller (VAR).

Notes

DSMN supports NetWare 4.*x* servers only when they are running in bindery emulation mode, not in Novell Directory Services (NDS) mode.

See Also: *Novell Directory Services (NDS)*

Directory Service Markup Language (DSML)

A specification based on XML (Extensible Markup Language) that enables different directory applications to share information.

Overview

Directory Service Markup Language (DSML) is a markup language (such as Hypertext Markup Language [HTML]) whose function is to allow directory information to be represented using XML. Its purpose in doing this is to make XML the common language for exchange of information between different directory systems.

DSML is an open specification, and its membership includes Microsoft, IBM, Novell, and Oracle. A draft standard is being developed by the Organization for the Advancement of Structured Information Standards (OASIS).

Implementation

DSML is essentially a set of extensions to XML that is expressed as a schema. The DSML schema for XML provides mechanisms for accessing information in directories even if the actual format of the data is unknown. Using a set of tags specific to directory services, DSML allows information in one proprietary directory to be exchanged with another proprietary directory without the need to pay attention to the mechanics happening underneath or how the directories operate.

The original DSML 1 specification was limited to specifying how to use XML to describe a directory's contents. The newer DSML 2 specification adds standard mechanisms for using XML to locate, access, and manipulate information stored in directories. Using DSML 2, developers will be able to build transactional applications that use XML to find and modify objects stored in a directory, regardless of the vendor from which the directory is obtained.

Notes

A related initiative is the Directory Interoperability Forum (DIF), whose aim is to establish a standard that will enable use of the Lightweight Directory Access Protocol (LDAP) for performing data queries across multiple directories. DSML and DIF are separate initiatives, but they might eventually merge or be subsumed within a wider objective.

For More Information

You can find out more about DSML at *www.dsml.org.*

See Also: *directory, XML*

Directory Service Migration Tool (DSMigrate)

A tool for migrating information from Novell NetWare networks to Microsoft Windows 2000.

Overview

Directory Service Migration Tool (DSMigrate) is a tool that you can use to migrate NetWare users, groups, files, and permissions to Active Directory directory service. DSMigrate can migrate both bindery-based NetWare 3.*x* servers and Novell Directory Services (NDS)–based NetWare 4.*x* and 5.*x* servers to Windows 2000.

DSMigrate lets you perform a test migration to assess any difficulties that might occur before you perform your final migration. DSMigrate is one of the NetWare tools included with Windows 2000.

See Also: *bindery, Novell Directory Services (NDS)*

directory synchronization (Microsoft Mail)

The process by which information stored in Microsoft Mail 3.*x* mail systems is replicated between postoffices.

Overview

There is only one directory server postoffice in a Microsoft Mail 3.*x* mail system; other postoffices that participate in directory synchronization are called requestor postoffices. Requestor postoffices send their address list updates to the directory server postoffice, which then sends cumulative changes back to the requestor postoffice. Directory synchronization also ensures that the global address list is updated.

When migrating legacy MS Mail systems to Microsoft Exchange Server, establishing directory synchronization between the old MS Mail directory and the new Exchange directory is a typical step in the process. To make this possible, Microsoft Exchange includes a dirsync component that emulates the MS Mail directory until the old directory information can be entirely migrated to the new system.

See Also: *Exchange Server*

directory synchronization (Windows NT)

The process of directory synchronization within a Microsoft Windows NT domain.

Overview

Directory synchronization is the process whereby the domain directory databases of backup domain controllers (BDCs) in a Microsoft Windows NT domain are synchronized with the master directory database on the primary domain controller (PDC). Accurate and reliable directory synchronization is the foundation for effective operation of Windows NT Directory Services (NTDS).

In Windows 2000 and Windows .NET Server, this process of replicating directory information between domain controllers is called directory replication.

Notes

If directory synchronization must be performed over slow wide area network (WAN) links, you can adjust some registry parameters to make directory synchronization more efficient and prevent it from consuming excessive bandwidth.

See Also: *directory replication (Windows NT), domain controller, Windows NT Directory Services (NTDS)*

Direct Sequence Spread Spectrum (DSSS)

A combination of two transmission technologies (direct sequencing and spread spectrum) used in wireless networking and cellular communications.

Overview

Direct Sequence Spread Spectrum (DSSS) is the most popular transmission scheme used in wireless networking and is widely deployed in cellular communications systems also. DSSS is the basis of the 802.11b wireless local area network (LAN) standard used around the world.

Implementation

DSSS transmits data 1 bit at a time. Each bit is processed by modulating it against a pattern called a chipping sequence. For example, in 802.11b the chipping sequence is an 11-bit binary sequence 10110111000 called the Barker code. This sequence is chosen as it has certain mathematical properties that make it suitable for modulation of radio waves. The sequence is exclusively ORd (XORd) with each bit of the data stream, which has the effect of multiplying the number of bits transmitted by a factor of 11 (each 11-bit transmission is called a “chip” and represents only a single bit of actual data). While this seems wasteful in terms of bandwidth, it has the advantage that if some of the transmitted bits are lost, the original data stream can still be reliably reconstructed by processing the remaining information. This feature, in addition to spread spectrum transmission, which sends the data over multiple frequencies simultaneously, makes DSSS strongly resistant to interference due to extraneous radio sources, multipath reflection, and atmospheric conditions.

See Also: *802.11b, cellular communications, direct sequencing, spread spectrum, wireless networking*

direct sequencing

A transmission method used for wireless networking.

Overview

Direct sequencing systems transmit data one bit at a time. Each bit of data is then transmitted simultaneously over a range of frequencies.



Direct sequencing. *How direct sequencing works.*

Direct sequencing is usually used in conjunction with spread spectrum, a transmission method where the data transmitted is spread over multiple frequencies to reduce signal loss due to noise and interference. The transmitter feeds each bit of the data stream into a signal spreader that multiplies the input, creating a wideband signal. The wideband signal is then amplified and broadcast by using an antenna.

Uses

Direct sequencing can be used for both wireless local area network (LAN) connections and as part of a cellular telephone system. Direct sequencing has a faster theoretical maximum data transmission rate than frequency hopping, another wireless transmission method, but in practice both methods provide similar throughput for wireless transmission of data because of protocol overhead in typical wireless communication systems.

See Also: *Direct Sequence Spread Spectrum (DSSS), frequency hopping, spread spectrum, wireless networking*

disaster recovery

The process of recovering IT (information technology) operations after a failure or disaster.

Overview

Because IT is the lifeblood of today's e-business economy, it is essential to be able to recover IT operations quickly after a disaster. An IT disaster can be something as small as a failed disk drive within a server or something as big as a data center burning to the ground. Other common examples of disasters include power failures, destruction due to viruses, theft, sabotage, accidental commands issued by administrators that result in files being deleted or modified, earthquakes, insurrections, and so on. Being prepared for eventualities such as these is the responsibility of IT management and is critical to the success of modern businesses.

The key to successful recovery from these situations is a comprehensive, tested disaster recovery plan. This is a business plan that involves not just redundant hardware but personnel, procedures, responsibilities, and issues of legal liability.

Implementation

The first step in such a plan involves risk assessment to determine which components are most vulnerable and how the company can function in response to loss of data or critical IT services. It is also important to determine what is acceptable to management in terms of a recovery window—many businesses today would suffer significant loss if it should take more than a day or two to recover from failed systems.

Disaster recovery plans can be implemented in different ways depending on the size and needs of the company involved. Three common approaches to implementing disaster recovery plans are traditional tape backup, e-vaulting, and mirroring.

The traditional approach of small to mid-sized businesses to disaster recovery is to create full backups to tape daily and archive these tapes off-site in secure locations. Most computer systems in businesses use this method, primarily due to its low cost and its well-known procedures. However, tape backups must be verified, and test restores must be performed periodically to ensure that this system is in fact working. Furthermore, businesses must realize that it typically takes up to 48 hours to restore a failed disk or system from tape backup, a recovery window that may be unacceptable from an e-business standpoint.

E-vaulting (or electronic vaulting or data vaulting) takes a different approach. Instead of archiving data to tape, it is sent over high-speed leased lines or Internet connections to a remote data center for safe storage. E-vaulting makes it possible to do more frequent backups and rapid restores, but the weak link is the wide area network (WAN) connection, for if that goes down, a restore might be difficult or impossible.

To make e-vaulting more effective, companies sometimes arrange for backup servers to be running at the remote site and back up data directly to those servers. Then if a failure occurs with the company's main servers, control can be switched over to the backup servers and business can continue without interruption. The problem is that having duplicate systems in place is an expensive proposition and complex to manage, and companies often try to save money by placing older hardware at the remote site. When disaster strikes, this hardware may not be able to perform as hoped and business will go down.

Another version of e-vaulting involves using a mobile data center (a network in a moving van) at the remote site. When disaster strikes the primary site, the mobile data center can be brought on location and managed by your staff.

Regardless of which form of e-vaulting is used, the main disadvantage in the eyes of most companies is the cost, which is typically many times that of using traditional tape backup solutions.

Extending the idea of e-vaulting is a method called mirroring, in which identical hardware is placed at a remote site and data is kept synchronized between servers in the primary and remote site. This is a costly solution both from the point of view of the redundant hardware required and the throughput needed for WAN links, but the restore window is typically under an hour when disaster strikes, so it is a good option from the perspective of e-businesses. Financial institutions such as banks and credit unions often employ this solution to ensure maximum availability and reliability for customer access to accounts.

Marketplace

While smaller companies tend to manage their own tape backup and e-vaulting solutions in-house, large enterprises generally outsource their disaster recovery needs, particularly if mainframe systems and AS/400s are involved. Three companies handle the lion's share of disaster recovery business at the enterprise level: Comdisco Continuity Services, SunGard Recovery Services, and IBM's Business Continuity Recovery Services (BCRS).

E-vaulting companies abound and their range of services varies greatly. One example of such a company is Imation, which offers its LiveVault services for small and medium-sized companies.

Businesses that host their business services with Web hosting companies often make use of disaster recovery services provided by these services. An example is Exodus Communications, which provides mirroring services for customers at remote data centers.

See Also: *backup, tape format*

discrete multitone (DMT)

A line coding technique used in Asymmetric Digital Subscriber Line (ADSL).

Overview

Discrete multitone (DMT) describes a specification for the physical layer transport for ADSL and is an efficient mechanism for transmitting data at high speeds at frequencies above the voice cutoff on ordinary copper phone lines. DMT offers good performance and resistance to crosstalk and electromagnetic interference, and it can be used to dynamically adapt data flow to line conditions. DMT is the most popular ADSL line coding scheme in use today.

History

DMT was developed by Bellcore in 1987 as a line coding scheme of Asymmetric Digital Subscriber Line (ADSL) services. DMT evolved from V.34 modem technology and was first commercially implemented in ADSL modem technology by Amati Corporation. At the time, DMT was one of several line coding schemes that had been proposed by carriers offering ADSL services. Another competing scheme used was carrierless amplitude phase modulation (CAP), which is based on quadrature amplitude modulation (QAM). But while CAP was more widely deployed initially in ADSL rollouts, DMT was adopted by standards bodies in the United States and Europe and is supported by the International Telecommunication Union (ITU).

Implementation

CAP employs a band of frequencies from 40 kilohertz (KHz) to 1.1 megahertz (MHz), well above the 4 KHz cutoff for voice transmission over the copper local loop. CAP divides this band into 4 KHz wide channels, with each channel being modulated independently and all of them simultaneously carrying data in parallel. An ADSL modem that uses CAP can thus be thought of as a collection of hundreds of tiny modems operating in parallel.

Each CAP channel can carry up to 15 bits/symbol/hertz (Hz) of information, using QAM as a modulation scheme (actual throughput per channel may be less due to electromagnetic interference and other conditions). Upstream transmission uses 25 channels giving a maximum throughput of

25 channels x 15 bits/symbol/Hz x 4 KHz = 1.5 Mbps

while downstream uses 249 channels giving a maximum throughput of

249 channels x 15 bits/symbol/Hz x 4 KHz = 14.9 Mbps

See Also: *Asymmetric Digital Subscriber Line (ADSL), line coding, modulation*

discretionary access control list (DACL)

An access control list (ACL) that can be configured by administrators.

Overview

In Microsoft Windows 2000, Windows XP, Windows .NET Server, and Windows NT, a discretionary access control list (DACL) is an internal list attached to a file or folder on a volume formatted using the NTFS file system (NTFS). The administrator can configure the DACL, and it specifies which users and groups can perform different actions on the file or folder. In Windows 2000, Windows XP, and Windows .NET Server, DACLs can also be attached to objects in Active Directory directory service to specify which users and groups can access the object and what kinds of operations they can perform on the object.

Implementation

In Windows 2000 and Windows .NET Server, each object in Active Directory or file on a local NTFS volume has an attribute called Security Descriptor that stores information about the following:

- The object's owner (the security identifier or the owner) and the groups to which the owner belongs
- The DACL of the object, which lists the security principals (users, groups, and computers) that have access to the object and their level of access
- The system access control list (SACL), which lists the security principals that should trigger audit events when accessing the list

The DACL for an object specifies the list of users and groups who are authorized to access the object and also what levels of access they have. The kinds of access that can be assigned to an object depend on the type of object under consideration. For example, a file object can have read access assigned to a user but a printer object cannot. (You cannot read a printer!)

The DACL for an object consists of a list of access control entries (ACEs). A given ACE applies to a class of objects, an object, or an attribute of an object. Each ACE specifies the security identifier (SID) of the security principal to which the ACE applies, as well as the level of access to the object permitted for the security principal. For example, a user or group might have permission to modify all or some of the attributes of the object, or might not even have permission to be aware of the object's existence. In common parlance, DACLs are sometimes simply referred to as access control lists or ACLs, although this is not strictly correct.

Notes

The owner of an object always has permission to modify its DACL by granting permissions to other users and groups.

See Also: *access control, access control entry (ACE), access control list (ACL), system access control list (SACL)*

disk duplexing

Disk mirroring using separate disk controllers.

Overview

Disk duplexing is a fault-tolerant disk technology that is essentially the same as disk mirroring, except that a separate disk drive controller is used for each mirrored drive. Disk duplexing thus provides two levels of fault tolerance:

- If one drive fails, the other contains a mirrored copy of the data.
- If one controller fails, the other controller continues to function.

Advantages and Disadvantages

Besides the additional level of fault tolerance, disk duplexing also provides slightly better read and write performance than disk mirroring because the two controllers provide two separate channels for data transmission. The down side is that disk duplexing is more expensive than disk mirroring since an extra controller card is required.

Microsoft Windows 2000, Windows XP, Windows .NET Server, and Windows NT Server support disk duplexing. You establish disk duplexing on Windows NT systems at the partition level and on Windows 2000, Windows XP, and Windows .NET Server at the volume level. In terms of system recovery and management, there is no difference between disk mirroring and disk duplexing.

See Also: *disk mirroring, fault tolerance, redundant array of independent disks (RAID)*

disk imaging

A method for creating an exact duplicate of the software installed on a computer system.

Overview

Disk imaging (also called cloning) is frequently used in enterprise environments as a way of rapidly deploying workstations (and occasionally servers) on a network. The first step in disk imaging is to create the reference system, a computer that has its operating system and applications installed and configured exactly as desired. A snapshot or image of this system is then taken using disk imaging software, and the image is stored on a server on the network. Agent software is then used to boot fresh systems (that is, computers with no operating system installed), connect to the server, download the image, and recreate it bit for bit on the new systems. The resulting systems are exact duplicates of the reference system.

Advantages and Disadvantages

Disk imaging is a much faster way of installing operating systems and applications on machines than the traditional methods of running setup programs. A traditional installation of an operating system and suite of applications might take hours—disk imaging often takes only a few minutes.

The downside of the process is that disk imaging is usually successful only when the cloned machines have the exact same hardware configuration as the reference machine. Nevertheless, disk imaging is a speedy and easy way to roll out large numbers of identical workstations and has become widely popular among enterprise administrators.

One further issue that must be considered is licensing—before using disk imaging to roll out a network, make sure that the operating system vendor supports this operation and that it does not violate your licensing agreement.

Marketplace

One of the earliest and still popular disk imaging applications is Ghost from Symantec Corp. In fact, disk imaging is often referred to as “ghosting” in reference to this product’s impact on the industry. Other popular tools include ImageCast IC3 from Innovative Software, DriveImage from PowerQuest Corporation, and RapiDeploy from Altiris.

See Also: *network management, storage*

disk mirroring

A fault-tolerant disk technology that employs two drives having identical information on them instead of just one.

Overview

In disk mirroring, both drives are controlled by the same disk controller, and when data is written to the controller, it is copied to both drives. Disk mirroring thus provides a measures of fault tolerance for disk subsystems, since if one drive in the mirror set fails, the other contains an up-to-date copy of all the data and can immediately take over without interruption of services.

Advantages and Disadvantages

In addition to fault tolerance, disk mirroring also provides better write performance than RAID-5 systems. On the other hand, disk mirroring read performance is worse than RAID-5 (though better than for a single disk).

Microsoft Windows 2000, Windows XP, Windows .NET Server, and Windows NT Server support disk mirroring. You establish disk mirroring on Windows NT systems at the partition level and on Windows 2000, Windows XP, and Windows .NET Server at the volume level. A more fault-tolerant form of disk mirroring is disk duplexing, which is discussed in its own article elswhere in the book.

See Also: *disk duplexing, fault tolerance, redundant array of independent disks (RAID)*

Diskperf command

A Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server command for starting and stopping disk performance counters for Performance Monitor (System Monitor in Windows 2000, Windows XP, and Windows .NET Server).

Overview

Counters for the objects Logical Disk (partition) and Physical Disk (drive) are disabled by default because a performance hit of a few percent can occur if they are enabled. You must run the Diskperf command prior to monitoring disk activity with Performance Monitor. On some disk subsystems, enabling these counters might produce a small decrease in system performance, so you should disable them when monitoring of the system is completed. You must reboot the system after running Diskperf.

Diskperf –n sets the system to not use any disk performance counters.

For the full syntax of this command, type **diskperf /?** on the command line.

See Also: *Windows commands*

disk quotas

A mechanism for managing how much data users can store on disks.

Overview

Disk quotas are a feature of Microsoft Windows 2000, Windows XP, and Windows .NET Server that administrators can use to track and control disk usage on a per-user basis for each NTFS file system (NTFS) volume that the user stores data on. Support for disk quotas is built into the new version of NTFS on Windows 2000, Windows XP, and Windows .NET Server.

Disk quotas are tracked independently for each NTFS volume even if several volumes are on the same physical disk. For purposes of managing disk quotas for users, disk space usage is based on file and folder ownership. Windows 2000, Windows XP, and Windows .NET Server ignore compression when it calculates how much disk space a user is utilizing. Whatever is unallocated in a user's disk quota is reported as free space for applications that allow the user to access disk space.

Depending on how disk quotas are configured, when a user exceeds the specified disk limit, one of two things can occur:

- An event is logged to the system log.
- Disk access is blocked and an event is logged. The user is presented with an "insufficient disk space" error.

Implementation

To use disk quotas on an NTFS volume, you must first enable this feature when the volume is created and before any users have access to it. Typically, you will begin by setting more restrictive settings for all users, and then relax these settings for users who need more disk space or work with large files.

To enable disk quotas, set quota limits, and specify what happens when users exceed their quotas, use the Quota tab on the property sheet for an NTFS volume. To configure disk quotas for users, you essentially specify two values:

- **Quota limit:** How much disk space the user is allowed to use
- **Quota threshold:** The conditions under which an event should be logged to indicate that the user is nearing his or her quota limit



Local Disk (C:) Properties

Status: Disk quotas are disabled

☑ Enable quota management

☑ Deny disk space to users exceeding quota limit

Default settings for new users:

○ Do not limit disk usage

● Limit disk space to 10 MB

Set warning level to 8 MB

Disk quotas. *Configuring disk quotas in Windows 2000.*

For example, if the quota limit for a user is set to 10 megabytes (MB) while the quota threshold is specified as 8 MB, an event is logged when the user stores more than 8 MB of data on the volume, and the user is prevented from storing more than 10 MB of data on the volume.

To view the status of disk quotas on an NTFS volume for which this feature has been enabled, open the volume's property sheet and examine the traffic light icon. The light is

- Red if quotas are disabled
- Yellow if the NTFS file system is recalculating the status of quota compliance
- Green if quotas are enabled

If you want to track disk usage by user but do not want to deny users access to a volume, you can enable disk quotas but specify that users can exceed their disk quota limit. Note also that enabling disk quotas incurs slight overhead in file system performance.

See Also: *NTFS file system (NTFS), storage*

disk status

Information about whether a disk is healthy or has a problem.

Overview

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, disk status is displayed in the Disk Management portion of the Computer Management console. The Status column shows the status indicators according to the following table. The letter *B* here indicates that the status indicator can apply to basic disks, and *D* indicates dynamic disks.

Disk Status

Disk Status	*Description/Prescription*
Online (BD)	The disk is accessible. There are no problems.
Online—Errors (D)	I/O errors detected. Try reactivating the disk to see whether the errors are transient.
Offline (D)	The disk is not accessible and might be corrupted, disconnected, or powered down. Try reactivating the disk, and check the cables and the controller.
Foreign (D)	The disk has been moved to this machine from another computer running Windows 2000 (same for Windows XP and Windows .NET Server). You must import the foreign disk before you can use it.
Unreadable (BD)	The disk is not accessible and might be corrupted, have I/O errors, or hardware failure. Try rescanning the disk or rebooting the system to see whether it recovers.
Unrecognized	The disk type is unknown, and the disk is probably from a different operating system, such as UNIX.
No Media	The drive is either a CD-ROM drive or some type of removable drive and has no media in it.

See Also: *storage*

Distance Vector Multicast Routing Protocol (DVMRP)

A multicast routing protocol based on the spanning tree algorithm.

Overview

Distance Vector Multicast Routing Protocol (DVMRP) is one of three routing protocols used for multicast routing, the other two being Protocol Independent Multicast Dense Mode (PIM-DM) and Multicast Open Shortest Path First (MOSPF). DVMRP is used for dense mode multicasting where the hosts receiving the multicast are densely congregated in large pockets of the network. DVMRP assumes that all hosts on connected subnets want to receive the multicast. A typical scenario where DVMRP might be used would be for webcasting sports events, concerts, or corporate presentations.

Implementation

DVMRP floods the network with multicast packets to try to get information out as rapidly as possible to the furthest corner of the network. DVMRP assumes that there is sufficient bandwidth to support this operation. Once a multicast session is established, DVMRP then prunes the routing tree by cutting off multicasts to routers whose connected networks have no hosts receiving them. If a router determines using Internet Group Membership Protocol (IGMP) that no downstream hosts or routers require the multicast transmission, it contacts the upstream DVMRP router and asks to be removed from its list for the multicast session.

DVMRP routers check their routing tables frequently to determine the optimal route to nearby DVMRP routers. DVMRP uses broadcasts to keep routing tables up to date, which tends to consume a lot of network bandwidth. As a result, DVMRP should only be implemented on connections that have sufficiently high bandwidth to support it.

See Also: *dense mode, Multicast Open Shortest Path First (MOSPF), multicasting, Protocol Independent Multicast-Dense Mode (PIM-DM), routing protocol*

distance vector routing algorithm

A routing algorithm used by certain types of routing protocols.

Overview

Also called the Bellman-Ford algorithm after its originators, the distance vector routing is an algorithm designed to enable routers to maintain up-to-date information in their routing tables. The main alternative to distance vector routing is link state routing, which is discussed in its own article elswhere in this book.

Implementation

Using the distance vector method, each router on the internetwork maintains a routing table that contains one entry for each possible remote subnet on the network. To do this, each router periodically advertises its routing table information to routers in adjacent subnets. Each routing advertisement contains the following information about each route in that routing table:

- The metric (hop count) for the route, which indicates the distance to the remote subnet
- The vector (direction) in which the route is located

These router advertisements are performed independently by all routers (that is, no synchronization exists between advertisements made by different routers). In addition, routers receiving advertisements do not generate acknowledgments, which reduces the overhead of routing protocol traffic.

Routers select the route with the lowest cost to each possible destination and add this to their own routing tables. Routers in adjacent subnets then propagate this information to more distant subnets hop by hop until information from all routers has spread throughout the entire internetwork and convergence (agreement between routing tables on all routers in the internetwork) is attained. The end result is that each router on the network is aware of all remote subnets on the network and has information concerning the shortest path to get to each remote subnet.

Uses

The Routing Information Protocol (RIP), which is supported by Microsoft Windows 2000, Windows XP, and Windows .NET Server, is one example of a dynamic routing protocol that uses the distance vector routing algorithm. Other examples are described in the article “distance vector routing protocol” elsewhere in this chapter.

Advantages and Disadvantages

Distance vector routing protocols (that is, protocols based on the distance vector routing algorithm) are generally simpler to understand and easier to configure than link state routing algorithm protocols. To configure a router that supports distance vector routing, you basically connect the interfaces to the various subnets and turn the router on. The router automatically discovers its neighbors, which add the new router to their routing tables as required.

The main disadvantage of the distance vector routing algorithm is that changes are propagated very slowly throughout a large internetwork because all routing tables must be recalculated. This is called the Slow Convergence Problem. When convergence is slow, it is possible that routing loops can temporarily form, which forward packets to black holes on the network, causing information to be lost. Most distance vector routing protocols implement use a technique such as the split horizon method to ensure that the chances of routing loops being formed are extremely small.

Another disadvantage of distance vector routing is that routing tables can become extremely large, making distance vector routing protocols unsuitable for large internetworks, and that route advertising generates a large amount of traffic overhead.

As a result of these issues, distance vector routing is generally best used in internetworks having 50 routers or fewer and in which the largest distance between two subnets is less than 16 hops. Despite these limitations, distance vector routing protocols are more popular than link state routing protocols, mainly because they are easier to set up and maintain (everything is automatic) and because their CPU processing requirements are small, which allows such protocols to be implemented on low-end and mid-end routers.

See Also: *distance vector routing protocol, link state routing algorithm, routing protocol*

distance vector routing protocol

Any routing protocol that is based on the distance vector routing algorithm.

Overview

The most popular routing protocols based on the distance vector routing protocol are

- **RIPv1 (Routing Information Protocol version 1):** This is a classful routing protocol that is suitable for small to mid-sized internetworks. RIPv1 supports both Internet Protocol (IP) and Internetwork Packet Exchange (IPX) routing.
- **RIPv2:** This is a newer version of RIP that supports variable length subnet masks (VLSMs).
- **IGRP (Interior Gateway Routing Protocol):** This is an interior gateway protocol (IGP) that uses a combination of different metrics for more efficient routing. IGRP was designed by Cisco Systems and is a proprietary routing protocol.
- **RTMP (Routing Table Maintenance Protocol):** This routing protocol is used in AppleTalk networks.

Advantages and Disadvantages

Distance vector routing protocols have some advantages over link state routing protocols: they are easier to configure and manage and their router advertisements are easier to understand and troubleshoot. On the other hand, distance vector routing protocols often have much larger routing tables, greater overhead of router traffic, long convergence times, and they scale poorly. As a result, they are most often used for small to mid-sized internetworks.

See Also: *distance vector routing algorithm, Interior Gateway Routing Protocol (IGRP), link state routing algorithm, Routing Information Protocol (RIP), routing protocol*

distinguished name (DN)

A method for uniquely naming objects within a directory.

Overview

Distinguished names (DNs) are part of the X.500 directory specifications and are used for locating and accessing objects using the Lightweight Directory Access Protocol (LDAP), and directories based on the X.500 or LDAP specifications are hierarchical in structure. For example, in an LDAP directory, the root or top node is a container that contains child nodes that can be either leaf nodes (end nodes) or containers themselves. An object that is a leaf node has a common name (CN) that identifies it, but this common name is not necessarily unique. By including with the common name the names of the root node (o node) and any containers and subcontainers (ou nodes) along the branch to the leaf node, a unique name can be constructed for the leaf node. This unique name is called the DN and is unique to the entire directory.

The DN for an object is thus formed by concatenation of the common name or relative distinguished name (RDN) of the object together with the names of each ancestor of the object all the way to the root object of the directory. As a result, if an object is renamed or moved to another container within a directory, its DN changes. Since this is undesirable from the point of view of applications accessing a directory, real-life directories such as Microsoft Corporation's Active Directory directory service use an internal naming scheme for objects that is invariant under object renames and moves (Active Directory uses globally unique identifiers [GUIDs] for internally naming objects).

Examples

DNs are one of the addressing formats for objects within Active Directory in Microsoft Windows 2000. In Active Directory, every object in the directory requires a unique name. Several kinds of names can be used to define a specific object in Active Directory, including

- **Distinguished name (DN):** This specifies the complete path to the object through the hierarchy of containers.
- **Relative distinguished name (RDN):** This is the portion of the distinguished name that is an attribute of the object itself.

- **User principal name (UPN):** This is the name used when a user logs on to the network.

For example, let's consider a User object within Active Directory. A User object is an example of a leaf object because it cannot contain other objects. User objects such as Jeff Smith are identified using CNs. A container is a directory object that can contain other objects. In Active Directory, containers are referred to as organizational units (OUs) because they are used to organize other objects into hierarchies of containers. For example, the user Jeff Smith would typically be contained within the Users container. At the top of the container hierarchy are the containers that represent different components of the domain itself. These components are called domain components (DCs). For example, if user Jeff Smith exists in the microsoft.com domain, the DN for this user is represented by the path DC=com,DC=microsoft,OU=Users,CN=Jeff Smith.

In Microsoft Exchange Server 5.5, which used its own proprietary directory instead of Active Directory, DNs were also used to identify recipients. Exchange automatically creates a DN for every recipient object in its directory database, including objects such as mailboxes, distribution lists, and public folders. For example, if a user Jeff Smith has a mailbox named JeffS located on an Exchange server in Redmond at the organization Microsoft, the DN for this user would be represented internally as O=Microsoft,OU=Redmond,CN=Recipients,CN=JeffS.

The Message Transfer Agent (MTA) uses a recipient's DN to determine how to route messages to that recipient within an Exchange organization.

See Also: *Active Directory, globally unique identifier (GUID), Lightweight Directory Access Protocol (LDAP), X.500*

distributed application

An application consisting of two or more parts that run on different machines but act together seamlessly.

Overview

In the simplest example of a distributed application, the user interface portion runs on a client machine while the processor- or storage-intensive portion runs on a server. This type of distributed application is called a client/server application. Examples of client/server applications include the following:

- Microsoft Exchange Server (back end) as a mail server with users running Microsoft Outlook (front end) on their client machines
- Microsoft Access (front end) as an interface for accessing database information stored in Microsoft SQL Server (back end)
- A Web application written using Active Server Pages (ASP) for Internet Information Services (IIS) (back end) that is accessed from a client machine running Microsoft Internet Explorer (front end)

In a more complex scenario, three tiers are used to create a distributed application. The back end may be an SQL database containing customer or sales information. The front end might be a simple Web browser, used by the employee to request sales information from the database. The middle tier of the distributed application would be the Web application running on an IIS machine.

See Also: *client/server, distributed computing*

Distributed Component Object Model (DCOM)

A Microsoft programming technology for developing distributed applications.

Overview

Distributed Component Object Model (DCOM) is a Microsoft technology developed in 1996 for component-based development of software that is network-aware. Using DCOM, developers can create network-aware applications using Component Object Model (COM) components. DCOM works under various network transports, including Transmission Control Protocol/Internet Protocol (TCP/IP), and is basically a set of extensions to COM. DCOM is the preferred method for building client/server applications in Windows 2000, Windows XP, and Windows .NET Server, and it was formerly known as Network OLE.

Implementation

DCOM functions as a client/server protocol that provides distributed network services to COM, allowing DCOM-enabled software components to communicate over a network in a similar fashion to the method by which COM components communicate among themselves on a single machine. DCOM client objects make requests for services from DCOM server objects on different machines on the network using a standard set of interfaces.



Distributed Component Object Model (DCOM). *How DCOM works.*

The client object cannot call the server object directly. Instead, the operating system intercepts the DCOM request and uses interprocess communication mechanisms such as remote procedure calls (RPCs) to provide a transparent communication mechanism between the client and server objects. The COM run time provides the necessary object-oriented services to the client and server objects. The COM run time also uses the security provider and RPCs to create network frames that conform to the DCOM standard.

In Microsoft Windows 2000, DCOM requests are sent using RPCs. Windows 2000 use security features such as permissions to enable software components to securely and reliably communicate over the network.

See Also: *client/server, Component Object Model (COM), distributed application*

distributed computing

A programming model that distributes processing across a network.

Overview

The architecture of programming applications has gone through several evolutionary steps over the last few decades. The original mainframe computing model had all the processing done centrally on the mainframe, with dumb terminals used for input and displaying results. The next evolutionary step was client/server computing where the client and server shared different aspects of the processing. Applications had to be specially tailored to take advantage of the client/server processing model. Recently a three-tier model has become dominant, which augments the client/server paradigm with a middle tier that encapsulates business logic in programming constructs.

The next evolutionary step in business computing is the distributed computing model. In distributed computing, there is no single centralized server. Instead, network communications are used to connect servers, clients, handheld devices, and other smart devices into a processing fabric. The different components of this fabric may be scattered widely across a network.

Microsoft Corporation's new .NET platform is designed to maximize processing gains through implementing a distributed computing model for building Web services and applications. Distributed computing is poised to revolutionize business services and how they are developed, and .NET supports peer-to-peer (P2P) computing as one manifestation of its distributed computing model.

See Also: *client/server, .NET platform, peer-to-peer network*

Distributed Denial of Service (DDoS)

A type of denial of service (DoS) attack that employs a large number of intermediate hosts to multiply the effect of the attack.

Overview

Although a DoS attack typically uses the attacker's machine or group of machines to launch it, a DDoS attack uses unwitting third-party hosts instead. The result can be devastating if hundreds—or thousands—of machines are involved.



Distributed Denial of Service (DDoS). *How a DDoS attack works.*

To launch a DDoS attack against a specific Web server, an attacker first finds a vulnerable network and installs DDoS tools on hundreds or even thousands of hosts on that network. Common tools used include Tribe FloodNet (TFN), TFN2K, trinoo, Stacheldraht, and many others easily downloaded from locations on the Internet. These compromised hosts become "zombies" under the attacker's control (other terms used to describe them include agents, daemons, or DDoS servers). Linux and Solaris systems have been the most popular systems exploited as zombies so far. A good indicator that an attacker might be trying to compromise your network by installing DDoS tools on hosts is a sudden increase in Rcp (remote copy protocol) traffic, which is often used to install these tools remotely. This kind of activity can be detected by a network intrusion detection system (firewall logs are less help, as attackers usually compromise a single host on the network and then use Rcp to install the tools on other hosts internally on the network from that point on).

Once the intermediate network is compromised and tools installed, the attacker launches the attack using a remote management console, and the zombies then attack the target host using a DoS attack method such as synchronous idle character (SYN) flooding, User Datagram Protocol (UDP) flooding, a smurf attack, or Internet Control Message Protocol (ICMP) flooding. The attack is usually overwhelming, usually bringing down the targeted server and often saturating the target's network so that other servers on the network are unable to communicate as well. Address spoofing is used to make it difficult to trace the machines launching the attack, and even if these zombies are identified, it is usually even more difficult to trace the single machine from which the attacker is managing the attack. An even more insidious version of DDoS makes it even harder to track the attacker by employing another layer of intermediate machines called masters, which are controlled by the attacker's management console and which themselves control the zombies. A master is typically the first host compromised on an intermediate network, and a full-scale DDoS attack may employ dozens of intermediate networks, each with their own master and hundreds of zombies.

Prospects

The most famous DDoS attack was instituted by Mafiaboy, a Canadian teenager who allegedly brought down a number of major Web sites for hours in February 2000, including Amazon.com, Buy.com, CNN.com, eBay, E-Trade.com, Yahoo!, and ZDNet. The attack was performed using tools that are easily downloadable from a number of sites on the Internet.

There is still no simple solution for protecting sites against DDoS attacks. The main problem is the large number of networks connected to the Internet that are poorly secured and are open to exploitation for using their machines as zombies for launching DDoS attacks on other, better-secured sites. Lack of vigilance on the part of the administrators of these vulnerable networks thus affects the success of everyone's sites on the Internet. Omissions such as allowing directed inbound broadcasts to networks and failing to implement ingress and egress filtering properly on routers on a network's border are typical mistakes by administrators that render corporate networks vulnerable to hijacking for performing DDoS attacks.

One step forward was the establishment in 2001 of the Information Technology Information Sharing and Analysis Center (ITISAC) by the U.S. Department of Commerce. ITISAC is designed to help companies share information about DDoS attacks to better defend against them. Another issue is the impending prospect of organizations being held liable for their poorly secured corporate networks should hackers establish zombies on these networks and use them to launch DDoS attacks against other sites. The Internet Engineering Task Force (IETF) is also involved and has established a working group RFC 2267+ to help strategize on the best way to deal with DDoS attacks. Despite these initiatives, the Internet remains vulnerable to such attacks and will likely continue to be so for the immediate future.

See Also: *denial of service (DoS), hacking, network security*

Distributed file system (Dfs)

A network file system that makes many shares on different file servers look like a single hierarchy of shares on a single file server.

Overview

Distributed file system (Dfs) is a feature of the Microsoft Windows 2000 and Windows .NET Server operating systems and a separately available add-on for the Windows NT operating system. Dfs allows file servers and network shares to be logically organized into a single Dfs directory tree. This simplifies management of network resources and makes it easier for users to locate and access network resources. From the user's perspective, Dfs makes it appear that there is only one server containing a hierarchical tree of resources, while in fact these resources might be distributed across multiple servers in different locations.

Dfs simplifies directory browsing, offers search tools that simplify locating network resources, and offers administrative tools for building and managing Dfs directory trees. It also eliminates the need for Windows 95, Windows 98, or Windows NT Workstation clients to form multiple persistent network connections because users require only one persistent connection to the directory tree.

Implementation

In the Windows 2000 and Windows .NET Server implementation, you first open the Dfs snap-in for Microsoft Management Console (MMC) to create a Dfs root node. You can then create Dfs child nodes under the root node. Each child represents a shared folder that can be located anywhere on the network. When users want to access a resource on the network, they navigate through the Dfs tree and do not need to know the particular server the resource is located on. Users must have Dfs client software installed on their machines. Dfs client software is included with Windows 2000, Windows XP, Windows .NET Server, Windows NT, and Windows 98. An optional Dfs client can be downloaded for Windows 95 from the Microsoft Web site.

You can configure Dfs to operate in two ways:

- **Stand-alone Dfs:** This type of Dfs stores the description of the Dfs file system topology on a single computer. If that computer fails, the entire Dfs system goes down, although users can still access resources the traditional way using mapped network drives or Universal Naming Convention (UNC) paths if they know which servers these resources are stored on and the names of the shares.

- **Fault-tolerant Dfs:** This type of Dfs stores the Dfs topology information in Active Directory directory service on Windows 2000 and Windows .NET Server domain controllers. This configuration is better for fault tolerance and file replication.

Notes

If a server containing Dfs shares fails, you can simply move the files to another machine, create new shares, and map the existing Dfs child nodes to the new shares. Your users will not even know that anything has changed. If you assign a user permission to access a shared folder, that person automatically has permission to access it through the Dfs tree as well.

See Also: *file system, storage*

Distributed Management Task Force (DMTF)

An industry consortium that develops specifications for cross-platform management standards.

Overview

The Distributed Management Task Force (DMTF) is a consortium of industry players that are developing specifications and standards for managing disparate systems using a common and ubiquitous tool, the Web browser. The DMTF was formerly known as the Desktop Management Task Force, and it has the support of most major networking and operating system vendors.

The DMTF has been working on several initiatives since its inception in 1996:

- **Web-Based Enterprise Management (WBEM):** A set of standards for developing systems to manage networks and systems using simple Web browsers.
- **Common Information Model (CIM):** A set of schema for describing information collected for network and systems management purposes.
- **Directory Enabled Networking (DEN):** A specification for how to store network and systems management information in a directory.

A complementary set of standards for cross-platform network and system administration is being developed by the Internet Engineering Task Force's (IETF) Policy Framework Working Group.

Notes

Windows Management Interface (WMI) is Microsoft Corporation's implementation of the DMTF'S WBEM architecture. WMI is a core feature of the Microsoft Windows 2000, Windows XP, and Windows .NET Server operating system platforms.

For More Information

You can find the DMTF at *www.dmtf.org.*

See Also: *browser (Web browser), Common Information Model (CIM), Directory Enabled Network (DEN), network management, Web-Based Enterprise Management (WBEM), Windows Management Instrumentation (WMI)*

distribution box

A fixed or freestanding miniature patch panel in an enclosure.

Overview

Typically, horizontal cable runs are connected to the punchdown blocks within the distribution box, and drop cables are plugged into the RJ-45 ports of the box. You can thus use distribution boxes to provide central cabling points away from walls. Stations can then be plugged and unplugged from an accessible location in the work area instead of from the back of the workstations (after you bend down and crawl behind the machine) or from the land drops in the wall (which are often hidden behind desks or other obstacles).

Uses

Use distribution boxes for classrooms and work areas in which computers frequently need to be moved around and rearranged.

See Also: *patch cable, patch panel*

distribution group

One of two types of groups within Active Directory directory service in Microsoft Windows 2000, the other type being security groups.

Overview

While security groups can be listed in discretionary access control lists (DACLs) for controlling access to resources or sending e-mail to users, distribution groups can be used only for e-mail purposes. By sending e-mail to a distribution group, you send e-mail to every member of that group.

Distribution groups can be converted to security groups and vice versa as long as the domain is in native mode. You cannot perform conversion if the domain is in mixed mode.

See Also: *group, security group*

distribution list

A grouping of recipients in Microsoft Exchange Server that you can use to send a single message to multiple users simultaneously.

Overview

When a message is sent to a distribution list, it is sent to all recipients on the list. Distribution lists provide a convenient way of performing mass mailings to users. For example, a marketing department might create several hundred custom recipients for regular customers outside the Exchange organization. These custom recipients can then be included as members within a single distribution list. When the department wants to send e-mail to its customers announcing new products or services, the e-mail can be sent to the distribution list. A computer running Exchange Server (configured to expand distribution lists) makes sure that each custom recipient receives a copy of the message.

distribution server

A server that contains the source files for a software product and that is used to perform remote installations.

Overview

As an example, if you want to perform remote installations of Microsoft Windows 2000 Professional on client machines, you can copy the I386 folder from the CD onto a folder called NTWKS on your file server, and then share this folder. Windows NT Workstation clients can then connect to this share and run the Setup program to upgrade their systems to Windows 2000 Professional.

Notes

When you copy files from the CD to a folder on the server, use the Xcopy command or, if you are using Windows Explorer, be sure to first choose Options from the View menu and select Show All Files. Otherwise, some hidden files will not be copied, and installation will fail.

DLC

Generally refers to the services that the data-link layer of the Open Systems Interconnection (OSI) reference model provides to adjacent layers of the OSI protocol stack. Specifically, a Data Link Control (DLC) is a specialized network protocol.

See: *Data Link Control (DLC)*

DLL

Stands for dynamic-link library, a file containing executable routines that can be loaded on demand by an application.

See: *dynamic-link library (DLL)*

DLT

Stands for Digital Linear Tape, a tape backup technology.

See: *Digital Linear Tape (DLT)*

DMI

Stands for Desktop Management Interface, a standard for managing desktop systems developed by the Desktop Management Task Force (DMTF), now the Distributed Management Task Force.

See: *Desktop Management Interface (DMI)*

DML

Stands for Data Manipulation Language, a subset of Structured Query Language (SQL)

See: *Data Manipulation Language (DML)*

DMS

Stands for Defense Messaging System, a global messaging system for the U.S. Department of Defense (DoD).

See: *Defense Messaging System (DMS)*

DMT

Stands for discrete multitone, a line coding technique used in Asymmetric Digital Subscriber Line (ADSL).

See: *discrete multitone (DMT)*

DMTF

Stands for Distributed Management Task Force, an industry consortium that develops specifications for cross-platform management standards.

See: *Distributed Management Task Force (DMTF)*

DMZ

Stands for demilitarized zone, a former name for perimeter network, a security network at the boundary between a corporate local area network (LAN) and the Internet.

See: *perimeter network*

DN

Stands for distinguished name, a method for uniquely naming objects within a directory.

See: *distinguished name (DN)*

DNA

Short for Windows DNA, an application development model from Microsoft Corporation for highly adaptable business solutions that use Microsoft's digital nervous system paradigm.

See: *Windows Distributed interNet Applications Architecture (Windows DNA)*

DNS

Stands for Domain Name System, a hierarchical naming system for identifying Transmission Control Protocol/Internet Protocol (TCP/IP) hosts on the Internet.

See: *Domain Name System (DNS)*

DNS client

A client machine configured to send name resolution queries to a name server.

Overview

A Domain Name System (DNS) client is also called a resolver because it uses name servers to resolve a remote host's name into its Internet Protocol (IP) address. To accomplish this, it sends such a request to a name server (a DNS server), which then returns the IP address of the remote host.

DNS client software is built into operating systems that support TCP/IP to enable client machines to issue DNS queries to name servers. For example, on Microsoft Windows platforms, the DNS client software makes possible the use of DNS names for browsing the Internet using Microsoft Internet Explorer.

In Windows operating systems, you must configure the IP address of the DNS server in the client's TCP/IP property sheet in order for the DNS client software to work properly. With dial-up networking connections to the Internet, this information can be communicated to the client machine during negotiation of the Point-to-Point Protocol (PPP) connection with the Internet service provider (ISP).

See: *Domain Name System (DNS), name server*

DNS console

A snap-in for the Microsoft Management Console (MMC) in Microsoft Windows 2000 and Windows .NET Server that enables administrators to manage Windows 2000 Servers and Windows .NET Server running as Domain Name System (DNS) servers.

Overview

You can use the DNS console to

- Create and maintain the DNS database of host name to Internet Protocol (IP) address mappings
- Create and manage zones of authority
- Create start of authority (SOA), name server (NS), address (A), CNAME, and other resource records in the DNS database
- View DNS server statistics

- Control how zones are stored and replicated between DNS servers
- Configure how DNS servers will process DNS queries and handle dynamic updates
- Configure security for specific zones and resource records



Name	Type	Data
_msdcs		
_sites		
_tcp		
_udp		
(same as parent folder)	Start of Au...	[22], hq.northwind.microsof...
(same as parent folder)	Name Server	hq.northwind.microsoft.com.
HQ.northwind.microsoft.com.	Host	172.16.11.177
(same as parent folder)	Host	172.16.11.177
HQ	Host	172.16.11.177
Server1	Host	172.16.11.190
Server2	Host	172.16.11.191
WWW1	Host	172.16.11.160
WWW2	Host	172.16.11.161
FTP1	Host	172.16.11.162

DNS console. *The DNS console in Windows 2000.*

Notes

Windows 2000 Server and Windows .NET Server include a new command-line utility, Dnscmd, which can be used for managing certain aspects of DNS servers. This utility can be run from the command prompt or scripted into batch files to automate certain aspects of DNS administration. To use this command, you must install the Windows 2000 Support Tools from the \Support\Tools folder on the Windows 2000 product CD (Windows .NET Server also supports Dnscmd and is also part of the Windows .NET Server Support Tools). Type **dnscmd /?** to see the syntax for this command.

See Also: *Domain Name System (DNS), DNS server, Microsoft Management Console (MMC)*

DNS database

The collection of database files, or zone files, and associated files that contain resource records for a domain.

Overview

Zone files are stored on a name server and are used to provide name resolution in response to name lookup requests. On Berkeley Internet Name Domain (BIND) name servers and Microsoft Windows NT Domain Name System (DNS) servers, these DNS database files are stored as flat-file database (text) files, that is, simple ASCII files.

On a Windows NT server with the Microsoft DNS Service installed, DNS database files are located in the \System32\DNS directory. The DNS database files in this directory are

- The zone file, which has the extension .dns and contains the resource records that the DNS server manages
- The reverse lookup file, which resolves Internet Protocol (IP) addresses into host names
- The cache file, which has the names and IP addresses of the root name servers for DNS
- The boot file, which is used for startup configuration of the DNS server and is needed only for resolving the names of hosts that are located outside the zones for which the DNS server is authoritative

On a Windows 2000 or Windows .NET Server DNS server, DNS database information can be either stored in the preceding standard text files or can be integrated into Active Directory directory service, depending on how DNS is installed and configured on the machine. Using Active Directory for storing DNS database information has the benefits of Active Directory's enhanced security features and multimaster replication, providing faster and more efficient replication of DNS zone information than using standard DNS text files.

See Also: *Active Directory, Domain Name System (DNS), zone*

DNS namespace

The collection of domains, subdomains, and fully qualified domain names (FQDNs) within the Domain Name System (DNS).

Overview

DNS uses a namespace that is hierarchical in structure and is stored as a distributed database on servers called name servers. The term *namespace* can have two meanings:

- The abstract space of FQDNs that are used to identify hosts on the Internet or on a private corporate TCP/IP internetwork

- The physical space of DNS database files (zone files) that exist on name servers and that actually define or contain the abstract DNS namespace

Notes

Active Directory directory service in Microsoft Windows 2000 and Windows .NET Server requires that a DNS namespace be configured in a domain-based implementation of Windows 2000 or Windows .NET Server in an enterprise.

See Also: *Domain Name System (DNS), fully qualified domain name (FQDN), name server*

DNS query

A request to a name server for name lookup.

Overview

DNS queries can occur two ways:

- Between resolvers and name servers
- Between name servers and other name servers

Queries can be answered by the queried name server from its local Domain Name System (DNS) database, from previously cached query results, or by a referral to another name server.

The three basic kinds of DNS queries are recursive queries, iterative queries, and inverse queries. For more information on these types of DNS queries, see their respective entries in this book.

See Also: *Domain Name System (DNS), host name resolution, inverse query, iterative query, recursive query*

DNSSEC

Stands for DNS Security Extensions, an enhancement of the Domain Name System (DNS) that supports cryptographic authentication of domain names.

See: *DNS Security Extensions (DNSSEC)*

DNS Security Extensions (DNSSEC)

An enhancement of the Domain Name System (DNS) that supports cryptographic authentication of domain names.

Overview

DNS Security Extensions (DNSSEC) uses public-key encryption and digital signatures to enable name servers to verify the identity of domain names. DNSSEC is a set of enhancements to existing name servers that will allow users to be certain that the Web site they are seeing in response to looking up a URL is in fact the one they desired and not some other "spoofed" site.

History

DNS has long been viewed in many quarters as the weak link in the Internet's chain of protocols. DNS's lack of security makes spoofing domain names easy, allowing malicious users to hijack Web traffic and redirect it to sites different from the ones users intended to access.

The most famous incident of Web site spoofing occurred in 1997. An IT (information technology) consultant in Washington State named Eugene Kashpureff set up servers to hijack Web traffic on the Internet and redirect it away from Network Solution's InterNIC name servers to his own name servers, dubbed AlterNIC. As a result, a large segment of legitimate traffic on the Internet was disrupted for about a week, with significant financial loss to many involved.

Many other Web site spoofing incidents have occurred since then, highlighting the fundamental weakness with the security of DNS and driving forward the search for solutions that culminated in RFC 2535, which defines DNSSEC.

Implementation

DNSSEC works by enabling name servers to verify the information they exchange with each other using public key cryptography and digital signatures. Typically, a user enters a URL into his or her Web browser to access a site on the Internet. The browser's Hypertext Transfer Protocol (HTTP) GET request is forwarded to the local name server, which is either a corporate name server in a large enterprise or a name server at a small to medium-sized company's Internet service provider (ISP). This local name server then contacts a root name server to locate a name server authoritative for the top-level domain listed in the URL, which then directs the local name server to the name server authoritative for the second-level domain in the URL, and so on until the Internet Protocol (IP) address of the desired Web site can be looked up and communications established. The role of DNSSEC in all this is that when these exchanges are going on between name servers, digital signatures are issued and verified at each stage to verify that the responses are being received from the actual name servers rather than spoofing name servers.



DNS Security Extensions (DNSSEC). *How DNSSEC works.*

DNSSEC works at both the zone and resource record levels to secure DNS information. DNSSEC requires several new resource records in name server databases:

- **SIG:** This resource record supplies digital signatures signed with private keys to encrypt resource record information.
- **PUB:** This resource record supplies the necessary public keys to decrypt encrypted resource record information.
- **NXT:** This resource record determines which records are mapped to which names.

Marketplace

The first DNS name server software to support DNSSEC is also the most popular in the Internet community, the Berkeley Internet Name Domain (BIND). DNSSEC is included in BIND 9, the latest release of the name server software, and is being packaged with most major UNIX operating systems including those from Sun Microsystems, Hewlett-Packard, and Red Hat Linux. The funding for developing DNSSEC for BIND 9 was provided by the U.S. Defense Information Systems Agency (DISA) and the work was done by NAI Labs and the Internet Software Consortium (ISC).

Although larger enterprises will likely move quickly to upgrade their name servers to support DNSSEC, smaller businesses may balk at the expense involved, particularly in the management of DNSSEC name servers. To meet this need, companies such as Nominum and UltraDNS Corporation are planning to offer outsourced DNSSEC services to such businesses.

Issues

A number of issues may delay the full-scale deployment of DNSSEC on name servers all across the Internet (DNSSEC must be widely deployed for it to work reliably):

- DNSSEC has greater processor and memory requirements than standard DNS in order to support the additional load of issuing and managing digital certificates and cryptographic keys.
- DNSSEC utilizes greater network bandwidth for its communications, both with DNS clients (resolvers) and with other name servers.
- DNSSEC is more complicated to install and maintain than standard DNS, particularly because of the key management issues involved.
- The root name servers of the Internet must be upgraded first for DNSSEC to properly operate, and this requires political decisiveness on the part of the Internet Corporation for Assigned Names and Numbers (ICANN), the agency that runs most of these servers.
- Regional and local ISPs must upgrade their name servers next in order for DNSSEC to succeed, and this involves additional costs due to hardware and management overhead that some ISPs may feel reluctant to commit.
- Finally, name servers have traditionally been managed on an “ If it ain’t broke, don’t fix it” basis, where network administrators are reluctant to upgrade a server that is critical for the successful operation of a dot-com enterprise.

Despite all of these issues, there is still tremendous pressure for DNSSEC to go ahead, and it is likely to be fully deployed across the Internet in the next few years.

Prospects

DNSSEC is seen by many as an essential upgrade for the Internet's DNS infrastructure. Governments, B2B exchanges, financial servers, and others are likely to be early adopters of this technology. The U.S. military is already taking steps to implement DNSSEC by enhancing existing BIND 8 name servers with additional software to make the .mil top-level domain more secure.

See Also: *Berkeley Internet Name Domain (BIND), Domain Name System (DNS), name server*

DNS server

A server that is used to resolve host names or fully qualified domain names (FQDNs) into Internet Protocol (IP) addresses on a TCP/IP network.

Overview

A Domain Name System (DNS) server, which is also called a name server, accomplishes name resolution by accepting DNS queries from DNS clients (called resolvers) and by performing DNS queries among other DNS servers, depending on how the servers have been configured.

The most common type of name server in use on the Internet is the Berkeley Internet Name Domain (BIND) name server, which runs on the UNIX operating system. For Windows 2000 and Windows .NET Server deployments using Active Directory directory service, Microsoft Windows 2000 Server and Windows .NET Server can function as a DNS server and are managed using an administrative tool, DNS console, which is a snap-in for the Microsoft Management Console (MMC). Windows 2000 and Windows .NET Server DNS servers include advanced capabilities such as dynamic update, which allows DNS servers to update their DNS database files automatically using Dynamic Host Configuration Protocol (DHCP). Another feature of Windows 2000 and Windows .NET Server is tight integration of DNS and Active Directory. For example, when a Windows 2000, Windows XP, or Windows .NET Server client needs to locate a Windows 2000 or Windows .NET Server domain controller, the NetLogon service uses the DNS server's support for the SRV resource record to allow registration of domain controllers in the local DNS namespace.

Notes

DNS servers can provide a simple means of load balancing connections to heavily used file or application servers such as Internet Information Services (IIS). The method is called Round Robin DNS, and it works as its name implies. Say you have three Web servers hosting identical content and you want to load balance incoming Hypertext Transfer Protocol (HTTP) requests across these servers. You can create three A records in the DNS zone file, each with the same host name but different IP addresses, one IP address for each Web server, as shown in this example:

```
www.northwind.microsoft.com        172.16.8.33
www.northwind.microsoft.com        172.16.8.34
www.northwind.microsoft.com        172.16.8.35
```

When a DNS client requests resolution of the name www.northwind.microsoft.com into its IP address, the DNS server returns all three IP addresses (.33, .34, .35), and the client chooses the first address (.33) and sends the HTTP request to the Web server associated with this address. The next time the DNS server receives the same name resolution request, it rotates the IP addresses in round-robin fashion (.34, .35, .33) and returns them to the client. The client picks the first address, which is now .34. This way, each DNS name resolution returns a different IP address, and the load is balanced between the Web servers.

The drawback to using Round Robin DNS is that if a server fails, DNS will continue to return the address of the failed server.

See Also: *Berkeley Internet Name Domain (BIND), Domain Name System (DNS)*

DOCSIS

Stands for Data Over Cable Interface Specification, a specification defining standards for implementation of cable modem systems.

See: *Data Over Cable Interface Specification (DOCSIS)*

Document Object Model (DOM)

A set of programming interfaces for developing and managing Extensible Markup Language (XML) documents.

Overview

Document Object Model (DOM) has been a major driving force behind the development and proliferation of XML tools and standards. This is because DOM provides programmers with standard application programming interfaces (APIs) for representing and manipulating XML data. XML parsers based on DOM are widely implemented in Web browsers and other Web client tools, and the evolution of DOM is in large part driving the development of these tools.

DOM is a recommendation of the World Wide Web Consortium (W3C), and in its original version, it lets programmers model the data hierarchy of XML documents as objects that can be manipulated in Java, JavaScript, C++, and other languages. Using these and other languages, programmers can write scripts and applications that can dynamically modify the content, style, and structure of XML documents.

DOM was originally targeted toward small XML documents that could be loaded in entirety into memory and manipulated using repetitive operations. Because XML documents can be relatively large, a newer version called DOM 2 has been developed that includes a number of new features not supported by the original DOM, including support for

- Programmatically loading and saving XML documents
- Searching APIs for programmatic querying of properties and data in XML documents
- Programmatic implementation of custom namespaces for combining XML from different sources
- Programmatic management of cascading style sheets (CSS 1 and 2)

The W3C DOM Working Group is currently at work on DOM 3.

Marketplace

Support for DOM is included in products from many vendors of XML products, including Microsoft Corporation, Oracle Corporation, IBM, SoftQuad, and others. Microsoft Internet Explorer 5.5 also supports key aspects of DOM 2, including APIs for custom namespaces and cascading style sheets.

See Also: *World Wide Web Consortium (W3C), XML*

document type definition (DTD)

A file that defines the allowed structure of an Extensible Markup Language (XML) document.

Overview

Document type definitions (DTDs) are used in XML to specify the structure of documents. For example, Hypertext Markup Language (HTML) documents are defined by the HTML DTD, which is implemented in Web browsers such as Microsoft Internet Explorer and Web page editing software such as Microsoft FrontPage. The DTD specifies which kinds of tags are mandatory and which are optional, and also the range of allowed values for each type of tag.

DTD originated as part of the Standard Generalized Markups Language (SGML) specification developed by the International Standards Organization (ISO) in the 1980s. DTD is now a basic part of the XML specification.

Implementation

DTDs are implemented as plain-text files. They use a highly condensed language or syntax, which is very concise and can be parsed rapidly and efficiently. Schemas are another feature of XML and provide functionality similar to DTDs. The main difference is that schemas are more verbose than DTDs since they are written in XML instead of the more concise (but less readable) DTD language.

See Also: *Hypertext Markup Language (HTML), XML*

DoD model

A networking model developed by the U.S. Department of Defense (DoD).

Overview

The DoD model was developed in the 1970s as the networking model for the Transmission Control Protocol/Internet Protocol (TCP/IP), which was first deployed by in the ARPANET project and is now the worldwide de facto standard for the Internet. The DoD model is older than the seven-layer Open Systems Interconnection (OSI) model, which was developed in the 1980s by the International Organization for Standardization (ISO) to provide a more detailed framework for developing network protocols.

Architecture

The DoD model consists of four layers. These layers map loosely to the seven-layer OSI model in the fashion described below. Describing the DoD layers from the top down, they are

- **Application/Process Layer:** Also called simply Application Layer, this layer covers the functions of the top three layers of the OSI model. TCP/IP protocols at this layer include Hypertext Transfer Protocol (HTTP), File Transfer Protocol (FTP), Simple Mail Transfer Protocol (SMTP), Simple Network Management Protocol (SNMP), and many others.
- **Host-to-Host Layer:** Also called the Transport Layer, this layer functions similarly to the OSI model Transport layer. Protocols at this layer include Transmission Control Protocol (TCP) and User Datagram Protocol (UDP).
- **Internetworking Layer:** This layer functions similarly to the OSI model Network Layer. Protocols at this layer include Internet Protocol (IP), Internet Control Message Protocol (ICMP), Internet Group Membership Protocol (IGMP), and Address Resolution Protocol (ARP).
- **Network Interface Layer:** This layer functions similarly to the OSI model Data Link and Physical layers. There are no TCP/IP protocols at this layer. Instead, TCP/IP runs over standard networking architectures such as Ethernet and Token Ring, which are defined at this layer.

See Also: *OSI model, Transmission Control Protocol/Internet Protocol (TCP/IP)*

DOM

Stands for Document Object Model, a set of programming interfaces for developing and managing Extensible Markup Language (XML) documents.

See: *Document Object Model (DOM)*

Domain Admins

A built-in group on Microsoft Windows NT, Windows 2000, and Windows .NET Server networks for users who need administrator-level access to systems.

Overview

The Domain Admins group simplifies administration of users on the network. It is a global group and does not have any preassigned system rights. The initial membership of the group is the sole user account called Administrator. Other user accounts that are added to this group gain rights and privileges equivalent to those of the Administrator account and can perform actions similar to those of the Administrator account. All network administrators in a given domain should be members of this group.

Notes

On Windows 2000– and Windows .NET Server–based networks, the Domain Admins group is created by default in the Users organizational unit (OU) within Active Directory directory service.

See Also: *built-in group*

domain blocking

The ability to block traffic from a specific Domain Name System (DNS) domain.

Overview

Domain blocking is a security technology used in Microsoft Internet Information Server (IIS) Web servers to protect them from undesirable traffic. It was first introduced with IIS4.

Domain blocking allows IIS administrators to grant or deny access to content on the server based on a client's Internet Protocol (IP) address, subnet, or Internet domain name. This is a useful security feature for protecting machines running Internet Information Server from repeated attack by hackers. Domain blocking can be applied at various levels, including the following:

- All virtual servers on the machine (master level)
- A specific virtual server
- A specific virtual directory
- A specific file

See Also: *domain name, IP address, subnet*

domain controller

A server running Microsoft Windows NT, Windows 2000, or Windows .NET Server that manages security for the domain.

Overview

Users and computers that need to obtain access to network resources within the domain must be authenticated by a domain controller in the domain. Windows NT domain controllers are the foundation of Windows NT Directory Services (NTDS), and Windows 2000 and Windows .NET Server domain controllers are based on Active Directory directory service.

In a Windows NT–based network, the domain controllers form a hierarchy. There are two types of Windows NT domain controller:

- **Primary domain controller (PDC):** This contains a writeable master copy of the domain directory database. A domain can have only one PDC, which is at the top of the domain controller hierarchy. All changes to directory information (such as user accounts or passwords) must be made on the PDC.
- **Backup domain controller (BDC):** This contains read-only replicas of the domain directory database stored on the PDC. There can be zero or more BDCs per domain. BDCs provide redundancy and load balancing for the domain. Periodically, the BDCs in a domain undergo directory synchronization with the PDC to ensure that the BDCs contain an accurate copy of the domain directory database. This replication ensures the proper functioning of the NTDS.

A Windows 2000 or Windows .NET Server domain controller is any Windows 2000 server or Windows .NET Server with the optional Active Directory installed. Windows 2000 and Windows .NET Server domain controllers contain a complete, writeable copy of the Active Directory information for the domain in which they are installed. Run the Active Directory Installation Wizard to promote any Windows 2000 or Windows .NET Server member server to the role of a domain controller. A domain controller manages information in the Active Directory database and enables users to log on to the domain, be authenticated for accessing resources in the domain, and search the directory for information about users and network resources. A Windows 2000 or Windows .NET Server domain controller contains a writeable copy of the domain directory database.

Unlike in a Windows NT–based network, where domain controllers are in a hierarchy, all domain controllers in a Windows 2000– or Windows .NET Server–based network are equal, and changes to the domain directory database can be made at any domain controller. Replication of directory information between Windows 2000 and Windows .NET Server domain controllers follows a multimaster model. In this configuration, each domain controller acts as a peer to all other domain controllers. In other words, there are no primary or backup domain controllers in Windows 2000 or Windows .NET Server, only domain controllers.

Although most domain controller options (sending and receiving updates that add, move, copy, and delete objects from the directory) are multimaster in nature, a few domain controller operations function on only certain domain controllers. These special functions are called flexible single-master operations (FSMO) and perform functions such as modifying the schema, assigning pools of relative identifiers to other domain controllers within a domain, emulating a Windows NT PDC for downlevel compatibility with Windows NT domain controllers, updating security identifiers and distinguished names in cross-domain objects when such an object is moved or deleted, and ensuring that all domain names within a forest are unique.

Uses

An important issue regarding domain controllers in Windows 2000– and Windows .NET Server–based networks is where to place them. After an administrator implements Active Directory and populates its initial information, most Active Directory–related traffic will come from users querying for network resources. The key to optimizing user queries is in how you locate the domain controllers and the global catalog servers on your network. Placing a domain controller at each physical site optimizes query traffic but increases replication traffic between sites. Nevertheless, the best configuration is usually to place at least one domain controller at each site with a significant number of users and computers.

In a pure Windows 2000 networking environment, all domain controllers can be configured to run in native mode. If you have a mix of Windows NT 4 and Windows 2000 domain controllers, the Windows 2000 domain controllers must be configured to run in mixed mode.

Notes

To upgrade a Windows NT–based network to Windows 2000, upgrade the PDC first. This allows the domain to immediately join a domain tree, and administrators can administer the domain using the administrative tools of Windows 2000 and create and configure objects in Active Directory.

If you need to move a Windows NT domain controller to a new domain, you must reinstall Windows NT. Domain controllers cannot migrate from one domain to another because when you create a domain, a unique security identifier (SID) is created to identify the domain, and domain controllers have this SID hard-coded into their domain directory database.

You can use the administrative tool Active Directory Users and Computers to convert a Windows 2000 domain controller from mixed mode to native mode. However, domain controllers running in native mode cannot be changed to mixed mode. If you create a new domain controller for an existing Windows 2000 domain, this new domain controller is referred to as a replica domain controller. Replica domain controllers are typically created to provide fault tolerance and better support for users who access resources over the network.

See Also: *Active Directory, domain modes, flexible single-master operation (FSMO)*

domain (DNS)

A collection of related hosts in the hierarchical Domain Name System (DNS).

Overview

Domains are the building blocks of DNS. A domain consists of a group of nodes in the DNS namespace that have the same domain name. Domains are organized hierarchically in the DNS namespace, with the topmost domain called the root domain.

DNS domains can be classified as one of the following:

- A parent domain, which contains other domains. An example of a parent domain is microsoft.com.
- A child domain, or subdomain, which is contained within a parent domain. Examples of child domains in the microsoft.com parent domain are northwind.microsoft.com and marketing.microsoft.com.

Domain names can include only the characters a–z, A–Z, and 0–9, the dash (-), and the period. A name that completely identifies a host in the DNS namespace is called a fully qualified domain name (FQDN).

See Also: *Domain Name System (DNS)*

domain forest

Also called simply a forest, a logical structure formed by combining two or more Microsoft Windows 2000 or Windows .NET Server domain trees.

Overview

Forests provide a way of administering enterprise networks for a company whose subsidiaries each manage their own network users and resources. For example, a company called Contoso, Ltd. might have a domain tree with the root domain contoso.com, and a subsidiary company called Fabrikam, Inc. might have a domain tree with the root domain fabrikam.com. Note that these two companies do not share a contiguous portion of the DNS namespace; this is typical of trees in a forest. The two companies might want to administer their own users and resources but make those resources available to each other's users. They can combine the two domain trees into a forest by establishing a two-way transitive trust between the root domains of the two trees.



Domain forest. *Example of a domain forest.*

All trees in a forest must share a common directory schema and global catalog. The global catalog holds information about all objects in all domains of the forest and acts as an index of all users and resources for all domains in the forest. By searching the global catalog, a user in one domain can locate resources anywhere in the forest. The global catalog contains only a subset of the attributes of each object. This ensures fast searches for users trying to locate network resources.

See Also: *domain (Microsoft Windows), domain tree*

Domain Guests

A built-in group on Microsoft Windows 2000 and Windows .NET Server networks.

Overview

The Domain Guests group simplifies administration of users on the network. It is a global group and does not have any pre-assigned system rights. The initial membership of the Domain Guests group is the sole user account called Guest. Other user accounts that are added to this group gain the rights and privileges equivalent to those of the Guest account and can perform actions similar to those of the Guest account. Domain Guests are typically users who are given occasional, temporary access to network resources.

Notes

The Domain Guests group is created by default in the Users organizational unit (OU) within Active Directory directory service. Normally, the only member of this group is the Guest account, but when Internet Information Services (IIS) is installed, additional guest accounts are created for use by IIS.

See Also: *built-in group*

domain local group

A type of group in a Microsoft Windows 2000– or Windows .NET Server–based network.

Overview

Windows 2000 and Windows .NET Server use groups to organize users or computer objects for administrative purposes. Groups can have different scopes, or levels of functionality. The scope of a group can be a single domain, a group of domains connected by trust relationships, or the entire network.

Domain local groups are Windows 2000 and Windows .NET Server groups whose scope is restricted to the specific domain in which they are defined. Domain local groups are used to provide users with access to network resources and to assign permissions to control access to these resources. Domain local groups have open mem bership, which means that you can add members from any domain to them.

To use a domain local group, you first determine which users have similar job responsibilities in your enterprise. Then you identify a common set of network resources in a domain that these users might need to access. Next, you create a domain local group for the users and assign the group appropriate permissions to the network resources. This procedure is called A-G-DL-P (access, group, domain local, permissions), which is a variation of the AGLP administration paradigm used in Windows NT–based networks.

Notes

If network resources within a domain are used only within the domain, you can group users in the domain using domain local groups. If your scope of resource usage is several domains linked by trust relationships, use global groups instead. If your network is a pure Windows 2000– or Windows .NET Server–based network and your domain controllers are running in native mode, you can use universal groups as well.

See Also: *global group, universal group*

domain master browser

A role of a browser computer on a Microsoft Windows–based network.

Overview

Domain master browser is one of the browser roles for the computer browser service on Windows networks. A domain master browser must be a machine running Windows NT, Windows 2000, or Windows .NET Server.

The role of the domain master browser is to collect the master list of available network resources in the domain. The domain master browser then distributes this list to master browsers on each subnet. If the domain has only one subnet, the domain master browser is also the master browser for that subnet.

Notes

A Windows NT domain has only one domain master browser, which is always the primary domain controller (PDC).

See Also: *Computer Browser service*

domain (Microsoft Windows)

A model developed by Microsoft Corporation for grouping computers together for administrative and security purposes.

Overview

Computers on a Microsoft Windows NT, Windows 2000, or Windows .NET Server network that are in the same domain share a common directory database of security information such as user accounts, passwords, and password policies. Domains can span geographical boundaries and networks; an enterprise can have branches in several continents with all machines belonging to a single domain. Alternatively, a single network or location can have multiple domains installed, with or without trust relationships between them.

Domain-based networks have the following features:

- **Centralized administration:** The entire network can be administered from a single location.
- **Single-user logon:** Users need only one user account to access any workstation on the network.
- **Universal resource access:** Users can access any network resource for which they have the appropriate permissions.

Implementation

Domains can contain different types of computers, that is, computers performing various different roles. Typically, the following kinds of computers are members of the domain:

- **Domain controllers:** These computers maintain the database of directory information for the domain. In Windows NT, this database is called the Security Accounts Manager (SAM) database, while in Windows 2000 and Windows .NET Server, this information is stored in Active Directory directory service. Domain controllers periodically exchange directory information using directory replication so that the information in any given domain controller is kept up to date. (If the information stored in a domain controller is out of date, users might have trouble logging on with that particular domain controller or finding recently shared resources on the network.)

- **Member servers:** These are stand-alone servers typically used for file and print services, Web services, or running applications such as Microsoft SQL Server. Member servers cannot authenticate users as domain controllers can.
- **Workstations or client computers:** These participate in the security policies of the domain and are members of the domain, but they are used as desktop machines for users instead of as network servers.

A Windows NT or Windows 2000 network can be installed as either a domain or a workgroup. The domain model is preferable because it allows computers to share a common security policy and a common domain directory database. Machines running Windows Millennium Edition (Me), Windows 98, Windows 95, and legacy 16-bit Windows machines can also participate in domain security on Windows NT and Windows 2000 networks but are not considered full members of the domain because they have no computer accounts within the domain directory database.

A Windows NT domain requires only one primary domain controller (PDC) and can have a number of backup domain controllers (BDCs). By creating a PDC, you create a new domain. Windows NT member servers and workstations can join a domain. Other systems, such as computers running Windows 95 and Windows 98, can participate in a domain but are not considered members of the domain because they have no computer accounts in the domain directory database.



Domain (Microsoft Windows). *This illustration shows a Windows 2000 domain.*

Windows 2000 domains use peer domain controllers, which are all equal in status. In Windows 2000, domains are core entities within Active Directory and act as a boundary for network security and for the replication of directory information over the network. If you establish a security policy in one domain, the settings, rights, and discretionary access control lists (DACLs) of that policy are limited to that domain. Domains are also the fundamental containers for all network objects within them. Domains contain users, groups, computers, and other directory objects. These objects can be grouped together using a hierarchy of organizational units (OUs).

See Also: *Active Directory, domain controller, domain (DNS), workgroup*

domain model

A model for building an enterprise-level network using Microsoft Windows NT or Windows 2000 domains.

Overview

Windows NT uses domain models for building enterprise networks radically different from those used by Windows 2000 and Windows .NET Server. In Windows NT networks, four main domain models can be implemented:

- **Single domain model:** This model keeps all of the machines in the network in a single domain and is usually implemented in smaller companies
- **Single master domain model:** This model separates resource domains from a master or accounts domain and is suitable for companies with a hierarchical organizational structure
- **Multiple master domain model:** This model uses multiple accounts or master domains and is suitable for large organizations that span different countries, regions, or continents
- **Complete trust model:** This model is used by very decentralized organizations or during the transition period when two companies merge

Because of their two-way transitive trusts between domains, Windows 2000 and Windows .NET Server are capable of building more flexible domain structures than Windows NT. In addition to the single domain model above, Windows 2000 and Windows .NET Server domains can be linked together hierarchically in domain trees, and domain trees can be joined at their roots to form domain forests.

Windows NT, Windows 2000, and Windows .NET Server can be scaled for implementation in enterprise-level businesses that support thousands of users and cover geographically diverse regions, with Windows 2000 and Windows .NET Server being the more scalable platforms. Choosing the correct domain model for implementing your network can greatly simplify administration of your network.

See Also: *domain (Microsoft Windows), domain tree, forest*

domain modes

A mode of operation for domain controllers in Microsoft Windows 2000– and Windows .NET Server–based networks.

Overview

Windows 2000 and Windows .NET Server domain controllers are computers that contain a writeable copy of Active Directory directory service. You can convert a Windows 2000– or Windows .NET Server–based server to a domain controller by running the Active Directory Installation Wizard on that machine. You can run Windows 2000 or Windows .NET Server domain controllers in either of two modes (though .NET Server introduces a new mode called "Windows .NET version 2002," which is exclusively for .NET Server–based networks):

- **Mixed mode:** This mode provides backward compatibility with Windows NT domain controllers (downlevel domain controllers). This mode supports networks with a mixture of Windows 2000, Windows .NET Server and Windows NT domain controllers and allows them to interoperate. Multimaster replication cannot be used in mixed-mode environments.
- **Native mode:** This mode interoperates only with other Windows 2000 or Windows .NET Server domain controllers. Native mode should be used when there are no longer any downlevel domain controllers on the network.

Notes

By default, Active Directory is installed on a Windows 2000 server or Windows .NET Server in mixed mode. You can change a domain controller from mixed mode to native mode, but not vice versa. Use the administrative tool Active Directory Users and Computers to perform the change.

See Also: *Active Directory, domain controller, mixed mode, native mode*

domain name

A name for a domain within the Domain Name System (DNS).

Overview

Domain names are used by companies and organizations to provide a uniform naming scheme for hosts on their Transmission Control Protocol/Internet Protocol (TCP/IP) internetworks and for providing friendly names for Web servers, mail servers, and other servers that are exposed to the Internet.

Domain names must be registered with a domain name registry before they can be used. Formerly this meant registering with the Internet Network Information Center (InterNIC), and later on Network Solutions. Today a number of different domain name registrars exist, each of which must be accredited by the Internet Corporation for Assigned Names and Numbers (ICANN) in order to operate. ICANN is the ultimate controlling organization for domain names and determines both generic and country-specific top-level domains (TLDs).

Uses

Owning a domain name is essential in today's business world as the dot-com enterprise becomes the standard model for business. A company's domain name typically reflects the company's trademark name or logo—for example, the microsoft.com domain owned by Microsoft Corporation. Because company names can be registered at the state or federal level, companies in different states or countries might want to register identical domain names. Unfortunately, the DNS was not established with consideration of these trademark issues, and the courtroom has become a common arena for resolving domain name ownership disputes.

The most popular domain names that companies register are the .com domain names. These were originally intended for commercial enterprises only, but they are also used by individuals, nonprofit organizations, and other entities that want to establish a clear presence on the Internet. About 75 percent of all registered domain names belong to the .com top-level domain. As of 2000, there were about 15 million registered domain names worldwide, and this figure is climbing rapidly.

Prospects

The Internet and its Domain Name System were developed in the United States, and the fact that the Internet is now a worldwide entity has put new pressures on DNS. Countries and regions have pressed for modifications to DNS to allow domain names to be registered in languages other than English, including languages that do not use Roman alphabet characters, such as Chinese. The IETF has established an Internationalized Domain Name (IDN) working group to develop such a system, which is likely to be based on the Unicode standard for internationalization of alphabets. The goal is to implement non-English DNS with minimal modifications to existing DNS itself.

ICANN is also in the process of creating additional top-level domains as alternatives for companies that are unable to register suitable .com domain names and for other purposes such as personal home pages. For the latest developments in this regard, see the ICANN Web site at *www.icann.org.*

Notes

In an interesting development, a commercial company called New.net has created its own new set of TLDs and is selling domain names based on them without the ICANN's approval. This is probably an attempt to apply market pressure to what is often perceived as ICANN's slow, politically based decision-making process of creating new TLDs. New.net is collaborating with commercial DNS provider UltraDNS to provide support for these new TLDs on name servers. To do this, Internet service providers (ISPs) install special software on their own name servers that allows client lookups for these new TLDs to be forwarded directly to UltraDNS's name servers. Users whose ISPs do have such software installed on their name servers can download a free plug-in from New.net to allow them to access sites using these TLDs.

For More Information

You can find a list of ICANN-accredited domain name registrars at *www.ispworld.com/isp/ICANN.htm.*

See Also: *Domain Name System (DNS), fully qualified domain name (FQDN), top-level domain (TLD)*

Domain Name System (DNS)

A hierarchical naming system for identifying Transmission Control Protocol/Internet Protocol (TCP/IP) hosts on the Internet.

Overview

The Domain Name System (DNS) is a distributed, hierarchical system that provides

- A method for identifying hosts on the Internet using alphanumeric “friendly” names called fully qualified domain names (FQDNs) instead of using difficult to remember numeric Internet Protocol (IP) addresses
- A distributed mechanism for storing and maintaining a database of the FQDNs and their associated IP addresses for all hosts on the Internet
- A method for locating hosts on the Internet by resolving their FQDN into their associated IP address so that network communication can be initiated with the host

History

Until 1983 the Internet computers used locally stored Hosts files to perform name resolution. Hosts files are text files that are basically lists of FQDNs and their associated IP addresses for remote hosts that the local host may need to communicate with. With the rapid growth of the Internet, however, updating these Hosts files became an unmanageable chore—each machine had to have its own local Hosts file that needed to be kept up to date, and whenever a host was added to the Internet or removed from it, the Hosts file needed an appropriate modification.

To solve this problem, the hierarchical DNS naming system was invented in 1984 and name servers were deployed across the Internet. The original RFCs 882 and 883 that defined DNS have since been replaced by RFCs 1034 and 1035, and additional RFCs have been added for additional features added to DNS.

Today DNS functions like a backbone for the Internet—without DNS, network communications over the Internet would not be possible.

Uses

Although the primary use of DNS is as the naming system for the Internet, large private TCP/IP internetworks sometimes used DNS internally with their own private name servers. This practice is rare now, however, as most private networks are now connected to the Internet.

DNS is essential to the operation of Active Directory directory service in Windows 2000 and Windows .NET Server. Active Directory uses the DNS as its naming system for Windows 2000 and Windows .NET Server hosts, and DNS servers provide name resolution services to enable network communications to take place on a Windows 2000– or Windows .NET Server–based network.

Not all name servers support the necessary DNS features that Active Directory requires. In order to implement Active Directory, name servers must support SRV records described in RFC 2052bis (SRV records enable Windows 2000 and Windows .NET Server clients, including Windows XP, to locate a domain controller for network authentication purposes). In addition, the following advanced DNS features are recommended for name servers that will support Active Directory:

- DNS dynamic updates described in RFC 2136.
- DNS change notification described in RFC 1996.
- Incremental zone transfer (IXFR) described in RFC 1995.

Windows 2000 and Windows .NET Server DNS service supports all of the above features by default. If you want to use Berkeley Internet Name Domain (BIND) name servers to support an Active Directory implementation, you must use at least BIND 8.1.2 and preferably BIND 8.2 or higher. Make sure you also disable name checking so your BIND name servers will ignore the illegal underscore character used by Active Directory's version of DNS.

Note that in BIND, name servers zone information is stored in text files. In Windows 2000 and Windows .NET Server, zone information can be stored either in text files or stored in and replicated using Active Directory.

Implementation

For DNS to work, four elements are required:

- A naming system that uniquely assigns each host on the Internet a DNS name.
- Name servers that keep track of the DNS namespace (collection of DNS names).
- Resolvers that can query the name servers asking what IP address corresponds to a particular DNS name.
- A way of assigning domain names to companies and organizations that have networks that need to be connected to the Internet.



Domain Name System (DNS). *The hierarchical structure of DNS.*

The DNS naming system assigns a unique name to each TCP/IP host on the Internet. Here the word host typically refers to servers, workstations, routers, TCP/IP printers, and similar devices. This unique name for a host is called the fully qualified domain name (FQDN) of the host.

The DNS namespace is defined as the collection of all FQDNs for all hosts on the Internet. This DNS namespace is hierarchical in structure, beginning with the root domain, which branches to top-level domains, then second-level domains, and so on to the individual host name. The FQDN barney.northwind.microsoft.com can be broken down as follows:

- **Host name:** barney
- **Third-level domain:** northwind (stands for Northwind Traders Ltd., a fictitious Microsoft subsidiary)
- **Second-level domain:** microsoft (Microsoft Corporation)
- **Top-level domain:** com (commercial domain)

The root domain has a null label and is not expressed in the FQDN.

The DNS namespace is stored as a distributed database on name servers located at various points on the Internet. Each name server on the Internet is responsible for a subset of the DNS namespace known as a zone. Each zone can consist of one or more domains and subdomains over which the zone is said to be authoritative.

The most important name servers on the Internet are the dozen or so root name servers, which are responsible for maintaining the infrastructure of the domain name system. These root name servers are maintained mostly by the Internet Network Information Center (InterNIC) and by U.S. military agencies (because the Internet evolved from the ARPANET project of the U.S. Defense Department in the 1970s).

Name servers typically store their DNS information in text files called zone files, which consist of a series of resource records (but Microsoft Windows 2000 and Windows .NET Server can do this differently, as discussed later in this article). There are many types of resource records, but the most common type is the A (address) record, which maps the host name or FQDN of a single host to its IP address.

The main function of a name server is to answer queries from DNS clients called resolvers. A resolver contacts a name server, asking it for the IP address associated with a given host name or FQDN. The name server then replies to the resolver with the IP address of the host or contacts a different name server for this information if it is unable to provide it itself.

All name servers can answer queries from resolvers or forward these queries to other name servers. However, name servers also function in four specific roles within the Domain Name System:

- **Primary name server:** This type of name server stores the master copy of the zone file for the zones that the name server has authority over
- **Secondary name server:** This type obtains its zone files by means of a zone transfer from a master name server
- **Master name server:** This type of name server is capable of providing zone information to secondary name servers
- **Caching-only name server:** This type contains no zone information of its own but can cache names resolved by other name servers and then use this cached information to respond to subsequent name lookups

Finally, companies and organizations can obtain domain names for their networks from domain name registrars. These registrars are accredited by the Internet Corporation for Assigned Names and Numbers (ICANN), which used to maintain the DNS system itself until recently.

Marketplace

Most ISPs run their own name servers (usually BIND) and implement registered DNS domains for a small fee to allow companies to run Web servers and mail servers accessible to the Internet. A new type of player is the pure-play DNS service provider, which runs its own dedicated DNS name servers and provides managed, high-availability DNS services to companies for a monthly service charge. Once such company is UltraDNS, which uses a network of redundant DNS servers for failover support and locates these servers near the Internet's backbone for best performance.

Issues

Security is the most important issue regarding DNS. Since DNS was designed to be completely open (any host on the Internet may query any name server), it is inherently insecure and open to attack. The most important type of attack is the denial of service (DoS) attack, which floods a name server with so many false DNS queries that it is unable to respond to real queries. Access to a company's Web server can be completely stopped through DoS attacks on name servers.

Since DNS is critical to the operation of the Internet, it is also viewed sometimes as a prize target by hackers seeking to disrupt the Internet's operation (actually these are more like anarchists than hackers, since a true hacker needs DNS in order to intrude into networks connected to the Internet). BIND name servers, which are the primary form of name server used on the Internet, have had a number of well-publicized vulnerabilities discovered in recent years, and an essential task of Internet service providers (ISPs) is keeping up with patches for their BIND name servers to protect them against attack.

Prospects

DNS will continue to play an essential role for the Internet, but with the transition to the new IPv6 addressing scheme, DNS needs a few modifications. The most important modifications are the inclusion of two new resource record types:

- **A6 record:** This is the counterpart for the A (address) record for IPv4 and maps a host name or FQDN to its IPv6 address to support name lookups.
- **DNAME:** This is the IPv6 counterpart of the CNAME record in IPv4.

In addition, reverse name resolution using PTR (pointer) records is different in IPv6 DNS. Specifically, while IPv4 DNS uses the in-addr.arpa domain for such reverse name resolution, IPv6 DNS uses a new domain called IP6.INT.

Finally, during the transition between IPv4 to IPv6 both versions of DNS will need to be supported (probably for many years), and to make this possible, the AAAA record was created to enable IPv4 name servers to provide IPv6 addresses to resolvers performing name lookups.

AAAA records are supported by BIND 8.1 and higher, while IPv6 DNS is supported by BIND 9.

Notes

On smaller TCP/IP networks, Hosts files can be used instead of DNS to support name lookups, while on legacy Windows NT–based networks, Windows Internet Name Service (WINS) provided NetBIOS name resolution as an alternative to DNS. WINS is also supported by Windows 2000 and Windows .NET Server but only for downlevel compatibility with Windows NT in networks that have not been fully upgraded from Windows NT to Windows 2000 or Windows .NET Server.

Windows 2000 and Windows .NET Server also use other naming conventions besides DNS. For example, to locate objects within Active Directory, the following naming conventions can be used:

- The Lightweight Directory Access Protocol (LDAP) naming convention of distinguished names and relative distinguished names (RDNs). This includes LDAP Uniform Resource Locators (URLs).
- User principal names for identifying users and groups.
- Security Accounts Manager (SAM) account names for user accounts.
- Universal Naming Convention (UNC) paths for shared network resources.

See Also: *domain (DNS), domain name, fully qualified domain name (FQDN), hosts file, name server, resource record (RR), root name server, zone*

domain tree

A hierarchical grouping of Microsoft Windows 2000 or Windows .NET Server domains.

Overview

Domain trees are created by adding one or more child domains to an existing parent domain. Domain trees are used to make a domain's network resources globally available to users in other domains.



Domain tree. *Example of a domain tree.*

In a domain tree, all domains share their resources and security information to act as a single administrative unit. A user who logs on anywhere in a domain tree can access file, printer, and other shared resources anywhere in the tree if he or she has appropriate permissions. A domain tree has only one Active Directory, but each domain controller in a tree maintains only the portion of Active Directory directory service that represents the objects in that particular domain.

Domains in a domain tree are joined using two-way transitive trusts. These trusts enable each domain in the tree to trust the authority of every other domain in the tree for user authentication. This means that when a domain joins a domain tree, it automatically trusts every domain in the tree.

For child domains to be part of a domain tree, they must share a contiguous namespace with the parent domain. The namespace of a Windows 2000 or Windows .NET Server domain is based on the Domain Name System (DNS) naming scheme. For example, in the illustration, the child domains proseware.contoso.com and adatum.contoso.com share the same namespace as the parent domain contoso.com. In this example, contoso.com is also the name of the root domain—the highest-level parent domain in the tree. The root domain must be created first in a tree.

All domains in a domain tree have their directory information combined into a single directory: Active Directory. Each domain provides a portion of its directory information to an index on the domain controllers. By searching this index, users can locate and access shared resources, applications, and even users anywhere in the domain tree.

Notes

Two or more domain trees that do not share a contiguous namespace can be combined into a domain forest.

See Also: *Active Directory, domain (Microsoft Windows), domain forest, namespace*

domain user account

One of two types of user accounts available on a Microsoft Windows 2000– or Windows .NET Server–based network.

Overview

User accounts enable users to log on to domains or computers and access any resources in the domain for which they have appropriate permissions. This is in contrast to local user accounts, which are used only for logging on to a specific machine (such as a member server) and accessing resources on that machine.

Domain user accounts are created in Active Directory directory service and stored in organizational units (OUs). Domain user account information is replicated to all domain controllers in a domain using directory replication. This replication enables the user to quickly and easily log on from any part of the domain.

You create domain user accounts using the administrative tool called Active Directory Users and Computers, a snap-in for the Microsoft Management Console (MMC). You can create domain user accounts in the default Users OU or in any other OU that you have created in Active Directory.

Notes

Windows 2000 and Windows .NET Server also include a number of built-in accounts that simplify the task of administering users on a network. The two built-in user accounts are the Administrator and Guest accounts.

Domain Users

A built-in group on Microsoft Windows NT, Windows 2000, and Windows .NET Server networks.

Overview

The Domain Users group simplifies administration of users on the network. It is a global group and does not have any preassigned system rights. Its initial membership is empty until ordinary network users are created for the domain. User accounts that are added to this group gain the rights and privileges that are assigned to ordinary users in the network, such as the right to log on over the network. All ordinary users on the network should be members of this group.

Notes

On Windows 2000– and Windows .NET Server–based networks, the Domain Users group is created by default in the Users organizational unit (OU) within Active Directory.

See Also: *built-in group*

DoS

Stands for Denial of Service, any attack conducted against a system that tries to prevent legitimate users from accessing the system.

See: *denial of service (DoS)*

DOS

Stands for Disk Operating System, which is short for Microsoft Disk Operating System (MS-DOS), the venerable operating system created by Microsoft Corporation for the first IBM personal computer in 1981.

See: *MS-DOS*

down

The state of a network when some or all network communications are disrupted.

Overview

Common reasons for networks being down include

- Loose connectors on cables
- Breaks or shorts in cables
- Failed networking components

Indications that the network might be down include

- Users complain that they cannot log on to the network or access certain network resources.
- Alarm systems in Simple Network Management Protocol (SNMP) management software start sending administrative alerts or e-mail to administrators.
- The uninterruptible power supply (UPS) unit in the wiring closet generates its annoying high-pitched tone.

See Also: *network troubleshooting*

drain wire

An uninsulated wire included in shielded cabling that runs the length of some coaxial cabling or shielded twisted-pair (STP) cabling.

Overview

The drain wire makes contact with the foil sleeve or mesh along the wire. The externally exposed portion of the drain wire should be connected to a secure ground connection. This ensures that the wire is properly grounded and that the shielding in the wire operates effectively. It also helps to maintain the two ends of the wire at the same voltage with respect to ground. If voltage differences form between the ends of a network cable, they can lead to a sudden voltage surge or discharge that can damage attached networking devices.

See Also: *coaxial cabling, shielded twisted-pair (STP) cabling*

drop

Another name for a wall plate or some other receptacle for connecting workstations to a local area network (LAN).

Overview

For example, a network administrator might say, “This room has 24 drops, and 6 are still available.” This means that there are 24 wall plate connections on the walls of the room, and 18 of them have drop cables attached to them to connect them to computers in the room. The other end of the drops usually terminates at a patch panel in the wiring closet. Another name for a drop is a *LAN drop*.

See Also: *premise cabling, wall plate*

drop cable

In Standard Ethernet networks, a cable connecting a computer’s network interface card (NIC) to a transceiver attached to a thicknet cable.

Overview

In Standard Ethernet networks, a drop cable is also called a transceiver cable. More generally, a drop cable is any short cable connecting a computer’s NIC to a wall plate. Drop cables allow computers to be easily disconnected and reconnected from the network so that you can move them around in the room. Drop cables are generally needed because horizontal cabling connecting patch panels in wiring closets terminates at wall plates in the work areas, but computers in the work areas are distributed throughout the entire room. In a more permanent networking configuration, wall plates might be located on floors and very short drop cables might be used to connect the computers to the network.

See Also: *Ethernet*

Dr. Watson

A Microsoft Windows utility that intercepts software faults and provides the user with information on which software faulted and why the fault occurred.

Overview

In earlier versions of Windows, this information was terse and cryptic, but it was greatly expanded and reorganized in the version of Dr. Watson included with Windows 98, as shown in the screen capture. However, this information is usually not helpful to the person running the software. Dr. Watson is primarily of interest to the providers of the software to determine what caused the software to crash. A piece of software that frequently generates Dr. Watson messages can be considered buggy, and you should contact your software vendor for a fix or a replacement.



Dr. Watson found nothing obviously unusual.

To help support technicians analyze the problem, describe what you were doing when the problem occurred.

System snapshot taken on 2/22/99 6:08:45 PM.

Dr. Watson. *A report generated by Dr. Watson.*

DS

Stands for Differentiated Services, a system for service classification of network traffic.

See: *Differentiated Services (DS)*

DS-0

Also known as DS0, stands for Digital Signal Zero, a transmission standard for digital telecommunications.

Overview

DS-0 defines a transmission rate of 64 Kbps and can carry either a single voice channel or data. Telecommunication carriers transmit digital signals in multiples of DS-0 called DS-1, DS-2, and so on. These multiples differ depending on whether you are dealing with the T-carrier system of North America or the E-carrier system of Europe and other continents. The following table lists the common DS-series transmission rates and their T-series or E-series equivalents (when defined). For example, you can see that a T1 data transmission is equivalent to 24 DS-0 transmissions multiplexed together and can transmit data at a rate of 1.544 Mbps.

DS-Series Transmission Rates

DS Type	*Multiple of DS0*	*Data Rate*	*T-Series*	*E-Series*
DS0	1	64 Kbps	N/A	N/A
DS1	24	1.544 Mbps	T1	N/A
N/A	32	2.048 Mbps	N/A	E1
DS1C	48	3.152 Mbps	N/A	N/A
DS2	96	6.312 Mbps	T2	N/A
N/A	128	8.448 Mbps	N/A	E2
N/A	512	34.368 Mbps	N/A	E3
DS3	672	44.736 Mbps	T3	N/A
N/A	2048	139.264 Mbps	N/A	E4
DS4	4032	274.176 Mbps	N/A	N/A
N/A	8192	565.148 Mbps	N/A	E5

DS-1

Also known as DS1, a transmission standard for digital telecommunications.

Overview

A DS-1 circuit consists of 24 DS-0 circuits multiplexed together into a circuit. The bandwidth of a DS-1 circuit is 1.544 Mbps, and a common name for such an arrangement is a T1 line. DS-1 is also a typical signaling rate for frame relay links.

Implementation

DS-1 circuits can be implemented singly or multiplexed together to form fatter pipes for carrying data faster. Multiple DS-1 circuits can be bonded together to create NxDS-1 circuits. Here N can be from 2 up to 8, providing a maximum throughput of 12 Mbps. In this arrangement, the first DS-1 circuit is the one responsible for managing the link, and if this circuit goes down the entire link fails.



DS-1. *Implementing DS-1 and NxDS-1 on a Frame Relay network.*

NxDS-1 is typically used when you do not expect your data requirements to radically increase for several years. If you are expecting much faster growth in data rates, consider moving to DS-3 or fractional DS-3 instead of NxDS-1.

Issues

When you want to upgrade form DS-1 to NxDS-1, you typically need to give up your old DS-1 circuits and obtain all new ones. This is because carriers terminate single and multiplexed DS-1 circuits differently at their end. Furthermore, it is a good idea to upgrade to the highest value of N you might require immediately because adding additional DS-1 circuits later could cause problems if these circuits follow different paths and experience different latencies at the multiplexor.

You may also need to upgrade your router if you move from DS-1 to NxDS-1. This is because the V.35 interface on most Cisco routers only supports speeds up to 3 Mbps, which corresponds to 2xDS-1. For higher speeds, obtain a router with High Speed Serial Interface (HSSI).

See Also: *DS-0, DS-3, frame relay, High-Speed Serial Interface (HSSI), T1, V.35*

DS-3

Also known as DS3, a transmission standard for digital telecommunications.

Overview

A DS-3 circuit consists of 672 DS-0 circuits multiplexed together into a circuit. The bandwidth of a DS-3 circuit is 44.736 Mbps, and a common name for such an arrangement is a T3 line.

Implementation

DS-3 circuits are typically connected to enterprise local area networks (LANs) using an Asynchronous Transfer Mode (ATM) switch. DS-3 is rarely available for frame relay links and is usually reserved for dedicated leased lines only.

DS-3 is usually available in several forms:

- **Channelized DS-3:** This consists of multiplexed DS-1 lines that terminate at the customer premises at a device called an M13 (DS-1 to DS-3 multiplexor). You can implement from 1 to 28 DS-1 circuits in channelized DS-3, which is cost-efficient because you pay only for what you need.
- **Fractional DS-3:** This is similar to channelized DS-3 but lets you add or remove bandwidth in 3-Mbps chunks (equivalent to a pair of DS-1 circuits).
- **Full DS-3:** In this scenario an M13 is not required, and the coax cable at the demarc point where the circuit enters the customer's wiring closet is simply connected directly to the router (only the most powerful routers support this arrangement).

Notes

Most companies do not have a need for DS-3, and a slower (and cheaper) alternative is NxDS-1, which uses multiplexed DS-1 circuits.

See Also: *DS-0, DS-1, frame relay*

DSL

Stands for Digital Subscriber Line, a group of broadband telecommunications technologies supported over copper local loop connections.

See: *Digital Subscriber Line (DSL)*

DSLAM

Stands for Digital Subscriber Line Access Multiplexer, the DSL termination device at a telco central office (CO).

See: *Digital Subscriber Line Access Multiplexer (DSLAM)*

DSMigrate

Stands for Directory Service Migration Tool, a tool for migrating information from Novell NetWare networks to Microsoft Windows 2000.

See: *Directory Service Migration Tool (DSMigrate)*

DSML

Stands for Directory Service Markup Language, a specification based on Extensible Markup Language (XML) that enables different directory applications to share information.

See: *Directory Service Markup Language (DSML)*

DSMN

Stands for Directory Service Manager for NetWare, an optional Microsoft Windows 2000 utility for managing directory information stored on NetWare servers.

See: *Directory Service Manager for NetWare (DSMN)*

DSN

Stands for data source name, a unique name used to create a data connection to a database using open database connectivity (ODBC).

See: *data source name (DSN)*

DSSS

Stands for Direct Sequence Spread Spectrum, a combination of two transmission technologies, direct sequencing and spread spectrum, used in wireless networking and cellular communications.

See: *Direct Sequence Spread Spectrum (DSSS)*

DSTP

Stands for Data Space Transfer Protocol, a new protocol for rapidly transporting large amounts of information.

See: *Data Space Transfer Protocol (DSTP)*

DSU

Stands for Data Service Unit, a digital communication device that works with a Channel Service Unit (CSU) to connect a local area network (LAN) to a telecommunications carrier service.

See: *Data Service Unit (DSU)*

DTD

Stands for document type definition, a file that defines the allowed structure of an Extensible Markup Language (XML) document.

See: *document type definition (DTD)*

DTE

Stands for data terminal equipment, any device that is a source of data transmission over a serial telecommunications link.

See: *data terminal equipment (DTE)*

DTMF

Stands for Dual Tone Multiple Frequency, the audio signaling method used by Touch-Tone phones.

See: *Dual Tone Multiple Frequency (DTMF)*

DTR

Stands for Dedicated Token Ring, a high-speed Token Ring networking technology.

See: *Dedicated Token Ring (DTR)*

dual boot

A computer that can boot one of several operating systems by means of a startup menu.

Overview

An example of a dual boot configuration is a machine on which Windows 98 and then Windows 2000 has been installed. The user can utilize the Windows NT boot loader menu to choose which operating system to run at startup.

Windows 2000, Windows XP, and Windows .NET Server support dual booting with other operating systems, but this is neither recommended nor supported by Microsoft Corporation. Dual boot systems are typically used in hobbyist and test networks in which a variety of operating systems are used to test different networking functions or when the number of available machines is fewer than needed to perform the tasks.

Notes

The Windows 2000, Windows XP, and Windows .NET Server boot loader menus can include up to 10 operating systems.

See Also: *boot*

Dual Tone Multiple Frequency (DTMF)

The audio signaling method used by Touch-Tone phones.

Overview

Each DTMF signal generated by pressing a key on a Touch-Tone phone generates two simultaneous audible tones of different frequencies, as shown in the table below. The advantage of this scheme is that faster and better accuracy of tone recognition (and hence recognition of what number is dialed) is achieved than if single tones were used.

Frequencies of DTMF Signals

	697 Hz	*770 Hz*	*852 Hz*	*941 Hz*
1209 Hz	1	4	7	*
1336 Hz	2	5	8	0
1477 Hz	3	6	9	#

DTMF was developed by AT&T; the term Touch-Tone was originally an AT&T trademark.

Uses

Microsoft Corporation's Telephony Application Programming Interface (TAPI) can recognize and interpret Dual Tone Multiple Frequency (DTMF) signals, allowing Microsoft Windows–based applications to integrate with telephony. Some networking vendors also supply hardware devices called DTMF/ASCII converters, which convert DTMF tones directly into different ASCII characters, which can then be fed as input into a program that routes telephone calls accordingly.

See Also: *Telephony Application Programming Interface (TAPI)*

duplex

A telecommunications term referring to bidirectional communication.

Overview

In full-duplex communication, both stations send and receive at the same time, and usually two communication channels are required. However, you can also achieve full-duplex communication using a multiplexing technique whereby signals traveling in different directions are placed into different time slots. The disadvantage of this technique is that it cuts the overall possible transmission speed by half.

In half-duplex communication, only one station can transmit at any given time while the other station receives the transmission. The opposite of duplex communication is simplex communication, which can occur only in one direction.

DVMRP

Stands for Distance Vector Multicast Routing Protocol, a multicast routing protocol based on the spanning tree algorithm.

See: *Distance Vector Multicast Routing Protocol (DVMRP)*

DWDM

Stands for dense wavelength division multiplexing, a multiplexing technology for achieving extremely high data rates over fiber-optic cabling.

See: *dense wavelength division multiplexing (DWDM)*

dynamic disk

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, a new kind of disk management technology for hard disks.

Overview

Dynamic disks are different from basic disks, which are disk systems that function similarly to earlier versions of Windows (basic disks are also supported by Windows 2000, Windows XP, and Windows .NET Server). Dynamic disks support advanced features such as online management, disk reconfiguration, and fault tolerance.

While basic disks are divided into partitions, a dynamic disk is divided into volumes. A simple volume consists of one or more regions of space on a dynamic disk (these regions need not be contiguous). Although a multidisk system using basic disks has a single partition table describing the data structure of all disks on the system, things are different with dynamic disks. When a system contains multiple dynamic disks, each dynamic disk reserves 1 MB of space at the end of the drive, and this space stores configuration information concerning all of the disks in the system. This provides a measure of fault-tolerance, for if one disk fails the configuration information is not lost concerning the other disks in the system.

When changes are made to a dynamic disk, such as extending a volume to add more space for storage, no reboot is required for the changes to take effect (basic disks must be rebooted when changes are made). You can also use dynamic disks in hot-swappable systems to add or remove drives without requiring a reboot.

Uses

Dynamic disks are intended for use on servers where high-availability and fault tolerance are essential. Workstations gain little by using dynamic instead of basic disks, and dynamic disks are not supported on laptops since they would bring no benefit there.

Dynamic disks are not supported by removable drives such as Zip and Jaz drives, USB and firewire drives, SyQuest drives, and so on.

Dynamic disks also cannot be used on dual-boot systems, as earlier versions of Windows cannot recognize them even if they are formatted using FAT or FAT32.

Implementation

You create and manage dynamic disks in three ways:

- Use the Disk Management console to convert an existing basic disk to a dynamic one.
- Add a new drive to a system and configure it as a new dynamic disk.
- Import a dynamic disk from a different Windows 2000, Windows XP, or Windows .NET Server system into your own system.

Note that the only way to convert a dynamic disk back to a basic disk is to back up all your information, reinitialize the disk by creating partitions, and restore.

See Also: *basic disk, partition (disk), storage, volume*

dynamic DNS (DDNS)

A feature of the Domain Name System (DNS) that enables DNS clients to automatically register their DNS names with name servers.

Overview

Ordinary DNS must be administered manually, with administrators typically making changes directly to zone files on name servers. Information in zone files needs to be updated whenever a new host appears on the network or a host leaves, so the more the network changes, the more work this entails for DNS administrators. Once a zone file is updated on a name server, the updated information is then propagated to other name servers by zone transfers, which are typically scheduled to occur periodically.

Dynamic DNS (DDNS) lets changes to zone files to be made automatically instead of manually, saving DNS administrators the labor-intensive work of maintaining up-to-date zone information concerning all hosts on their network. To accomplish this, DDNS uses a process called dynamic updates outlined in RFC 2136.

Uses

DDNS in Microsoft Windows 2000, Windows XP, and Windows .NET Server is used in two scenarios:

- **Registration of DHCP clients:** When DDNS is enabled and used in conjunction with DHCP, Windows 2000, Windows XP, and Windows .NET Server machines that initialize on the network dynamically acquire an Internet Protocol (IP) address and then automatically register their DNS name and IP address with the DNS server by adding an A record for the client to the name server's zone file.
- **Registration of domain controllers**. When a domain controller boots up for the first time, it registers an SRV record with the DNS server. This SRV record is needed by DNS clients so they can locate the domain controller in order to log on to the network.

Implementation

DDNS is supported by the Windows 2000 and Windows .NET Server implementation of DNS and greatly simplifies the administration of DNS zone information in Windows 2000 and Windows .NET Server networks. DDNS is recommended for Windows 2000– and Windows .NET Server–based networks because Active Directory directory service uses DNS as its name locator service for locating hosts on the network and DDNS also reduces the chances of error that occur when DNS is administered manually.

Dynamic update lies at the heart of Active Directory because domain names in Windows 2000 and Windows .NET Server are also DNS names. For example, northwind.microsoft.com can be both a legal DNS name and the name of a Windows 2000 domain. When DNS is integrated with Active Directory and configured for dynamic updates, the root zone and forward lookup zones are created and configured automatically for each domain, but administrators must enable and manage reverse lookup zones.

DDNS is similar to ordinary DNS in that zone update operations occur using primary or master servers only. DDNS, however, allows primary servers to receive updates initialed by a specified list of "authorized servers," which can include secondary zone servers, domain controllers, and other servers that perform name registration services, such as Windows Internet Name Service (WINS) or DHCP servers.

Most name servers on the Internet either do not yet support or are configured not to support DDNS because of the extra security issues involved when using it. DDNS is currently most popular in corporate networks using Windows 2000 and Active Directory.

Notes

You can use the DNS Manager snap-in for the Microsoft Management Console (MMC) to enable Active Directory integration on an existing DNS server. The zone file information will be written into Active Directory.

Note that by default DDNS on Windows 2000 and Windows .NET Server does not automatically scavenge (purge) old resource records for clients no longer on the network—you need to manually enable and schedule scavenging.

See Also: *Active Directory, Domain Name System (DNS), name server, zone*

Dynamic Host Configuration Protocol (DHCP)

A protocol that enables the dynamic configuration Internet Protocol (IP) address information for hosts on an internetwork.

Overview

Dynamic Host Configuration Protocol (DHCP) is an extension of the bootstrap protocol (BOOTP). DHCP is implemented as a client-server protocol that uses DHCP servers and DHCP clients.



Dynamic Host Configuration Protocol (DHCP). *How a DHCP client leases an IP address from a DHCP server.*

A DHCP server is a machine that runs a service that can lease out IP addresses and other Transmission Control Protocol/Internet Protocol (TCP/IP) information to any DHCP client that requests them. For example, on Microsoft Windows 2000 servers, you can install the Microsoft DHCP Server service to perform this function. The DHCP server typically has a pool of IP addresses that it is allowed to distribute to clients, and these clients lease an IP address from the pool for a specific period of time, usually several days. Once the lease is ready to expire, the client contacts the server to arrange for renewal.

DHCP clients are client machines that run special DHCP client software enabling them to communicate with DHCP servers. All versions of Windows include DHCP client software, which is installed when the TCP/IP protocol stack is installed on the machine.

DHCP clients obtain a DHCP lease for an IP address, a subnet mask, and various DHCP options from DHCP servers in a four-step process:

1. **DHCPDISCOVER:** The client broadcasts a request for a DHCP server.
2. **DHCPOFFER:** DHCP servers on the network offer an address to the client.
3. **DHCPREQUEST:** The client broadcasts a request to lease an address from one of the offering DHCP servers.
4. **DHCPACK:** The DHCP server that the client responds to acknowledges the client, assigns it any configured DHCP options, and updates its DHCP database. The client then initializes and binds its TCP/IP protocol stack and can begin network communication.

DHCP lease renewal consists only of steps 3 and 4, and renewal requests are made when 50 percent of the DHCP lease time has expired.

Implementation

When you implement DHCP on a network, you should consider the following:

- DHCP servers do not share their database of leased IP addresses, so if your network has more than one DHCP server, be sure that their DHCP scopes do not overlap.
- Assign DHCP options to the DHCP server if clients need them.
- Assign static IP addresses to non-DHCP clients, and exclude these addresses from the scope on the DHCP server if necessary.
- Assign static IP addresses to all servers on your network or assign them DHCP client reservations on the DHCP server to ensure that they always lease the same IP address.
- Configure DHCP relay agents if one DHCP server must serve hosts on several subnets.

Marketplace

Although network operating system platforms such as Microsoft Windows 2000 and Novell NetWare include their own DHCP services, enterprise network architects may also want to consider self-contained DHCP applications from third-party vendors as well. Some of these third-party DHCP products include additional features such as query and reporting tools that make them attractive to use in an enterprise environment. Some examples of such products include Shadow Ipserver from Network TeleSystems (recently acquired by Efficient Networks), IP AddressWorks from Process Software, NetID from Nortel Networks, network Registrar from Cisco Systems, and Meta IP from CheckPoint Software Technologies.

For More Information

Find out more about DHCP at *www.dhcp.org.*

See Also: *BOOTP, Domain Name System (DNS), IP address*

Dynamic HTML (DHTML)

A proposed World Wide Web Consortium (W3C) standard developed by Microsoft Corporation for creating interactive multimedia Web content.

Overview

Developers can use Dynamic HTML to make Web pages look and behave more like typical desktop applications. Dynamic HTML supports features such as

- Document Object Model (DOM), a standard whereby every element of a Web page is exposed for scripting. Each element on a Hypertext Markup Language (HTML) page can function as an object that can be modified using scripts and other programs. For example, Dynamic HTML can make the appearance of an object on a Web page change during an onmouseover or onclick event.
- Cascading Style Sheets (CSS) positioning, which allows HTML content developers to control the style and layout of objects on a Web page using style sheets. These style sheets can then be cascaded to define different levels of precedence.
- Dynamic Content and Dynamic Styles, which HTML content developers can use to dynamically change the content or style of every HTML element on a Web page based on mouse events or other forms of user interaction.
- Data Binding, which integrates data with HTML elements. For example, table rows can be automatically generated from data records and data-bound fields.

See Also: *cascading style sheets (CSS), Document Object Model (DOM)*

dynamic-link library (DLL)

A file containing executable routines that can be loaded on demand by an application.

Overview

Dynamic-link libraries (DLLs) offer the advantage of providing standard services for many different calling applications, and they simplify and modularize application development by providing component–based services. DLLs are loaded into RAM only when needed by the calling application, which reduces the memory requirements of large applications. DLLs are files that have the extension .dll.

See Also: *application programming interface (API)*

dynamic packet filtering

The process of filtering packets according to real-time criteria.

Overview

Dynamic packet filtering is a feature of firewalls, routers, and proxy servers such as Microsoft Proxy Server. Using dynamic packet filtering, a system can

- Determine dynamically whether to accept a packet from the Internet while minimizing the number of exposed ports in both directions and the length of time the port is open to the Internet
- Drop all packets on an external interface by default

Implementation

In Microsoft Proxy Server, dynamic packet filtering involves two components:

- **Packet Filter Driver:** This component talks directly to the external network interface
- **Packet Filter Manager:** This component provides the high-level interface for interaction between Proxy Server services and the driver

In a typical scenario, a client with the Winsock Proxy client might attempt to connect to an Internet server using Telnet. The Winsock Proxy client intercepts the Telnet connection request and remotes the request to the Winsock Proxy server, which verifies that the client has proper Microsoft Windows NT permissions to use Telnet to access servers on the Internet and opens a local socket. The Winsock Proxy server then informs the Packet Filter Manager that an outbound connection request from the socket to a remote Telnet service has been approved, and the Packet Filter Manager orders the Packet Filter Driver to open the socket and the

Winsock Proxy server to start a Telnet session on behalf of the client. When the Winsock Proxy determines that the client has closed the Telnet session, it tells the Packet Filter Manager to close the socket and thus blocks any further packets from the remote system.

See Also: *firewall, packet filtering, proxy server, router*

dynamic routing

A routing mechanism for dynamically exchanging routing information among routers on an internetwork.

Overview

Dynamic routing operates using a dynamic routing protocol, such as Routing Information Protocol (RIP) or Open Shortest Path First (OSPF) Protocol. Routers that use dynamic routing are sometimes called dynamic routers.

For dynamic routing to work, the routing protocol must be installed on each router in the internetwork. The routing table of one router is manually seeded with routing information for the first hop, and then the routing protocol takes over and dynamically builds the routing table for each router. Dynamic routers periodically exchange their routing information so that if the network is reconfigured or a router goes down, the routing tables of each router are automatically modified accordingly.

Advantages and Disadvantages

Dynamic routers are much simpler to administer than static routers, but they are sometimes less secure because routing protocol information can be spoofed. If the network is reconfigured or a router goes down, it takes a certain period of time for this information to propagate between the various routers on the network. This router reconfiguration process is usually referred to as convergence. However, getting a dynamic router up and running is often as simple as connecting the interfaces and turning it on—routes are discovered automatically by communications with other routers on the network. Dynamic routers are also fault-tolerant, for when a router fails the other routers soon learn about it and adjust their routing tables accordingly to maintain communications across the network. Using dynamic routing protocols also creates additional network traffic due to routing table updates and exchanges, and different dynamic routing protocols offer their own advantages and disadvantages in this regard.

Dynamic routers cannot exchange information with static routers. To configure static and dynamic routers to work together on the same internetwork, you must add manual routes to the routing tables of both types of routers.

Notes

You can configure a multihomed Microsoft Windows 2000 or Windows .NET Server server as a dynamic RIP router by selecting Enable IP Forwarding on the Routing tab of the Transmission Control Protocol/Internet Protocol (TCP/IP) property sheet and then using the Services tab of the Network property sheet to add the RIP for Internet Protocol (IP) service to the server. Another example of a dynamic router is a multihomed computer running Windows 2000 Server with Routing and Remote Access Service (RRAS) and either RIP or OSPF configured.

See Also: *router, routing table, static routing*

dynamic routing protocol

A protocol that enables dynamic routing to be used to simplify management of a routed network.

Overview

If we focus on Internet Protocol (IP) routing, which is the standard for the Internet and most corporate networks, several kinds of dynamic routing protocols can be deployed. These routing protocols can be classified in a hierarchical scheme as shown in the illustration.

First, dynamic routing protocols can be one of two types:

- **Interior Gateway Protocols (IGPs):** These are used to manage routing within autonomous systems (ASs). IGPs are further classified below.
- **Exterior Gateway Protocols (EGPs):** These are used to manage routing between different ASs. The de facto example of an EGP is the Border Gateway Protocol (BGP) used on the Internet.


Dynamic routing protocols
Interior gateway protocols
Exterior gateway protocols
Distance vector
Link state
BGP
RIP IGRP EIGRP
OSPF IS-IS

Dynamic routing protocol. *Classification of popular dynamic routing protocols.*

IGPs can be further classified according to the type of algorithm used to build and distributed routing table information. Specifically, IGPs can employ the

- **Distance vector routing algorithm:** Examples of dynamic routing protocols that use this algorithm include Routing Information Protocol (RIP), Interior Gateway Routing Protocol (IGRP), and Enhanced Interior Gateway Routing Protocol (EIGRP).
- **Link state routing algorithm:** Examples of dynamic routing protocols that use this algorithm include Open Shortest Path First (OSPF) and Integrated System to Integrated System (IS-IS).

See Also: *autonomous system (AS), Border Gateway Protocol (BGP), distance vector routing algorithm, Enhanced Interior Gateway Routing Protocol (EIGRP), exterior gateway protocol (EGP), interior gateway protocol (IGP), Interior Gateway Routing Protocol (IGRP), link state routing algorithm, Open Shortest Path First (OSPF), Routing Information Protocol (RIP)*

dynamic volume

In Microsoft Windows 2000, Windows XP, or Windows .NET Server, a volume created on a dynamic disk.

Overview

Windows 2000, Windows XP, and Windows .NET Server support several kinds of dynamic volumes including

- **Simple volumes:** These consist of one or more regions of contiguous space on a single drive.
- **Spanned volumes:** These consist of one or more regions of contiguous space from two or more drives.
- **Striped volumes:** RAID 0 or disk striping using dynamic disks.
- **Mirrored volumes:** RAID 1 or disk mirroring using dynamic disks.
- **RAID 5 volumes:** Disk striping with parity using dynamic disks.

You can create dynamic volumes using the Disk Management portion of the Computer Management administrative tool. You can create dynamic volumes only on dynamic disks.

See Also: *basic disk, basic volume, dynamic disk, RAID, storage, volume*

E

EAP

Stands for Extensible Authentication Protocol, a security enhancement of Point-to-Point Protocol (PPP).

See: *Extensible Authentication Protocol (EAP)*

EBGP

Stands for Exterior Border Gateway Protocol, the version of Border Gateway Protocol (BGP) used for exchanging routing information between different autonomous systems.

See: *Exterior Border Gateway Protocol (EBGP)*

e-business

Refers generally to the process of using the Internet for conducting key activities of your business.

In the new Internet economy two terms are generally confused:

- **e-commerce:** This refers specifically to the process of buying and selling goods and services over the Internet.
- **e-business:** This more general term may include e-commerce activity, but also includes using the Internet for additional core business processes, including management of supply-line services, customer relations, and human resources.

E-commerce is generally B2C (business-to-consumer) in orientation, but e-business includes B2B (business-to-business) activities that join separate businesses entities over the Internet into value chains using negotiated agreements. In an e-business scenario, the basic activities of business (including invoicing, transactions, and procurement) are all performed electronically over the Internet. Technologies such as Electronic Data Interchange (EDI) and Extensible Markup Language (XML) are employed to facilitate the exchange of information between business partners. Because the Internet is a public network, security is a high priority for e-business, and technologies such as virtual private networks (VPNs) and Internet Protocol Security (IPsec) are used to ensure the privacy, integrity, and authenticity of electronic business transactions.

In addition to businesses forming their own private negotiated business arrangements, a large number of public and private e-business marketplaces have emerged in the last few years to facilitate B2B relationships. An example is the Microsoft Market, which is Microsoft Corporation's internal Web-based procurement system.

For companies migrating from the old brick-and-mortar model to the new e-business model, there are many advantages incurred in the move. These include lowered procurement costs, shorter business cycles, more efficient customer service, and new kinds of sales opportunities.

See Also: *B2B, electronic data interchange (EDI), XML*

ebXML

Stands for Electronic Business Extensible Markup Language, an XML standard that allows businesses to locate each other on the Internet, form partnerships, and exchange business information.

See: *Electronic Business Extensible Markup Language (ebXML)*

E-carrier

The digital telecommunications services backbone system of Europe, a format standardized by the International Telecommunication Union (ITU).

Overview

The E-carrier service rates are specified by the organization CEPT (Conférence Européenne des Administration des Postes et des Télécommunications, or European

Conference of Postal and Telecommunications Administrations). The most popular of these services, E1, is also the slowest. E1 transmits data at speeds of up to 2.048 megabits per second (Mbps) over two pairs of twisted wires. It consists of 32 separate 64-kilobits-per-second (Kbps) DS-0 channels multiplexed together, each of which can carry either a voice conversation or a stream of data. E1 is sometimes referred to as 2-Meg.



E-carrier. *Connecting to an E-carrier service.*

E-carrier transmissions are graded E1, E2, and so on, in order of increasing transmission speeds. These different service grades are multiples of the basic DS-0 data transmission rate, similar to the T-carrier system of North American telecommunications carriers. The E-carrier transmission rates are shown in the table included in the article "DS-0" elsewhere in this book. E-carrier lines use 8 bits per channel for encoding signals and do not rob bits for control signals as T-carrier lines do.

E-carrier services were developed in the 1970s and became widely available in the 1980s. E-carrier services can be used for wide area network (WAN) connections, for high-speed Internet connections, for private videoconferencing services, and for public frame relay services. E-carrier services are generally available wherever the parallel T-carrier services are not.

Notes

If the E1 service entering your customer premises needs to connect directly to a different building, you have two options. First, you could have the service provider extend the E1 line to the other building, thus moving the demarcation point (termination point) of the line. This could be costly, however. A simpler solution might be to connect the E1 line to a fiber-optic line driver, install a fiber-optic cable from the line driver to a similar driver in the other building, and then connect the remote line driver to your E1 equipment (see diagram).

See Also: *T-carrier*

EDGAR

Stands for Electronic Data Gathering, Analysis, and Retrieval, an online document management system used by the U.S. Securities and Exchange Commission (SEC).

Overview

EDGAR is an online service with two main functions:

- To provide corporations with an electronic method for filing public disclosures such as quarterly earnings statements, annual reports, and so on. This is the "private" side of EDGAR, and companies currently file this information by means of the Web, through virtual private network connections (VPN) or through dial-up modem connections.
- To provide a clearinghouse that allows individuals and organizations to view archived reports of publicly traded companies. This is the "public" side of EDGAR, which receives almost 1 million visitors daily.

EDGAR was upgraded in 2000 from its older OS/2 system to Microsoft Windows NT, and the SEC is looking into ways to use Extensible Markup Language (XML) to help EDGAR submissions search for information in its vast database more easily.

For More Information

Visit the SEC at *www.sec.gov.*

EDGE

Stands for Enhanced Data Rates for Global Evolution, a third-generation (3G) upgrade for General Packet Radio Service (GPRS).

See: *Enhanced Data Rates for Global Evolution (EDGE)*

edge router

A device in an Asynchronous Transfer Mode (ATM) network that routes data between an ATM backbone network and local area networks (LANs).

Overview

Edge routers can be used to translate Ethernet or Token Ring data for transmission over ATM backbones. This allows ATM to be used as a backbone for connecting multiple LANs into a metropolitan area network (MAN) or wide area network (WAN).



Edge router. *Using an edge router to connect LANs to an ATM backbone.*

An alternative and more commonly used configuration is to connect LAN networking equipment directly to ATM backbone switches, which provide points of contact with an ATM provider's backbone network.

An edge router can function as an ATM switch and provide routing capabilities for LAN networking protocols—all in one hybrid device.

See Also: *Asynchronous Transfer Mode (ATM), backbone*

EDI

Stands for electronic data interchange, the industry standard format for exchanging business information electronically.

See: *electronic data interchange (EDI)*

eDirectory

The latest version of Novell Directory Services (NDS).

Overview

Novell eDirectory is the new name for NDS version 8.*x* and emphasizes the enhanced Internet functionality of NDS. Novell eDirectory is a key part of Novell's "One Net" strategy and includes the following enhancements over previous versions of NDS:

- Native support for Lightweight Directory Access Protocol version (3LDAPv3) and LDAP Data Interchange Format (LDIP)
- An internal schema that more closely conforms to the LDAPv3 standard than earlier versions
- Support for enhanced Domain Name System (DNS) naming conventions
- Extensible support for management using the ConsoleOne utility
- Increased scalability to support more than a billion objects per directory tree

Novell eDirectory is available for the Novell NetWare, Microsoft Windows NT, Windows 2000, UNIX, AIX, Compaq Tru64 UNIX, Solaris, and Linux platforms. The current version is eDirectory 8.5.

See Also: *directory*

effective permissions

In Microsoft Windows 2000, Windows XP, and Windows .NET Server, the cumulative permissions a user has for accessing a resource based on a user's individual permissions, group permissions, and group membership.

Overview

The effective permissions a user experiences in trying to access a file or folder depend on the various permissions granted to the user expressly or by virtue of membership in a particular group. When a permissions conflict exists between one group and another, or between the user and a group, rules are applied that resolve the issue.

In networks based on Windows 2000, Windows XP, and Windows .NET Server, calculation of effective permissions can be determined using three simple rules:

First, if a user belongs to two (or more) groups, and these groups have different NTFS file system (NTFS) standard file permissions on a given file, the user's ability to access the file both locally and over the network is determined as follows: the effective NTFS permission is the least restrictive (most permissive) NTFS standard permission. For example,

```
read (NTFS) + change (NTFS) = change (NTFS)
```

The exception to this is that the no-access permission overrides all other permissions. For example,

```
read (NTFS) + no access (NTFS) = no access (NTFS)
```

Second, if a user belongs to two (or more) groups, and these groups have different shared folder permissions on a given shared folder, the user's ability to access the shared folder over the network is determined as follows: the effective shared folder permission is the least restrictive (most permissive) shared folder permission. For example,

```
read (shared folder) + change (shared folder)
= change (shared folder)
```

The exception to this is that the no-access permission overrides all other permissions. For example,

```
read (shared folder) + no access (shared
folder) = no access (shared folder)
```

Third, when a user attempts to access a folder or file over a network that has both NTFS permissions (the first example) and shared folder permissions (the second example) configured on it, the effective permission is the most restrictive (least permissive) permission. For example,

```
read (NTFS) + change (shared folder)
= read (combined)
```

See Also: *NTFS permissions (Windows 2000, Windows XP, and Windows .NET Server), shared folder permissions*

EFI

Stands for Extensible Firmware Interface, a firmware standard for 64-bit Intel processors.

See: *Extensible Firmware Interface (EFI)*

EFS

A feature of Microsoft Windows 2000, Windows XP, and Windows .NET Server that allows files stored on NTFS file system (NTFS) volumes to be secured through encryption.

See: *Encrypting File System (EFS)*

EGP (exterior gateway protocol)

Stands for exterior gateway protocol, any routing protocol used to distribute routing information among different autonomous systems.

See: *exterior gateway protocol (EGP)*

EGP (Exterior Gateway Protocol)

Stands for Exterior Gateway Protocol, the original exterior routing protocol used to connect autonomous systems on the Internet.

See: *Exterior Gateway Protocol (EGP)*

EIA

Stands for Electronic Industries Alliance, the main trade organization representing the U.S. high-tech community.

See: *Electronic Industries Alliance (EIA)*

EIA/TIA wiring standards

Standards for commercial and telecommunications wiring developed by the Electronic Industries Alliance (EIA) and Telecommunications Industry Association (TIA).

Overview

The EIA/TIA wiring standards actually comprise a group of standards covering different aspects of premise cabling and other wiring practices. These standards include

- **EIA/TIA 570:** Residential/Light Commercial Wiring Standard
- **EIA/TIA 568A:** Commercial Building Telecommunications Cabling Standard
- **EIA/TIA 569:** Commercial Building Standard for Telecommunications Pathways and Spaces
- **EIA/TIA 606:** Design Guideline for Administration of Telecommunications Infrastructure in Commercial Buildings
- **EIA/TIA 607:** Commercial Building Grounding and Bonding Requirements for Telecommunications

When installing wiring for your network, be sure to follow the EIA/TIA standards to ensure that your network functions as expected and that it complies with all local and state building codes and regulations.

The EIA/TIA wiring standards are also supported by the American National Standards Institute (ANSI).

For More Information

Visit the Electronic Industries Alliance (EIA) at *www.eia.org and the* Telecommunications Industry Association (TIA) at *www.tiaonline.org.*

See Also: *premise cabling, structured wiring*

EIGRP

Stands for Enhanced Interior Gateway Routing Protocol, a popular interior routing protocol developed by Cisco Systems.

See: *Enhanced Interior Gateway Routing Protocol (EIGRP)*

EIP

Stands for Enterprise Information Portal, a business software system used to provide a single point of access to information stored in different corporate databases.

See: *Enterprise Information Portal (EIP)*

EJB

Stands for Enterprise Java Beans, a Java-based technology from Sun Microsystems for building transactional e-commerce systems.

See: *Enterprise Java Beans (EJB)*

EKP

Stands for Enterprise Knowledge Portal, a business software system that couples knowledge management tools with an Enterprise Information Portal (EIP) to provide a powerful way of handling the flood of information that characterizes large businesses today.

See: *Enterprise Knowledge Portal (EKP)*

election

The process of selecting a new master browser from a Microsoft Windows network's potential browsers.

Overview

If a client machine cannot locate a master browser on the network in Windows NT, Windows 2000, Windows XP, or Windows .NET Server, it initiates an election to select a new master browser. Elections ensure that a master browser is always available on the network, since the absence of a master browser means that clients will be unable to locate and access network resources such as shared files and folders.

If a client machine cannot locate a master browser on the network, it broadcasts an election datagram. When a machine that is a potential browser receives this datagram, it examines the election criteria in the datagram. If its election criteria are better than those of the datagram's sender, the potential browser broadcasts its own election datagram and an election is declared to be in progress. The election criteria for becoming a master browser include many factors, such as the machine's operating system, version, and role. Eventually, one potential browser prevails over other machines on the network because it has superior election criteria, and the election ends.

Notes

Elections also occur when domain controllers are restarted.

See Also: *browsing, Computer Browser service*

electromagnetic interference (EMI)

Electrical noise induced in cabling by the presence of nearby electrical equipment such as motors, air conditioners, fluorescent lights, and power lines.

Overview

Electromagnetic interference (EMI) can interfere with the transmission of signals and render network communications unreliable or impossible. EMI is only a problem if copper cabling is used-fiber-optic cabling is immune to sources of EMI.

EMI is caused when the changing electromagnetic fields generated by one cable induce extraneous currents or interference in adjacent or nearby cables. EMI in copper cabling can be reduced to acceptable levels by

- Avoiding bunching of unshielded cabling
- Keeping all cabling away from power cords and transformers
- Using shielded twisted-pair (STP) cabling instead of unshielded twisted-pair (UTP) cabling
- Enclosing cabling in external mesh or wire shielding
- Properly grounding electrical equipment and external shielding
- Taking care not to excessively untwist the terminating ends of twisted-pair cabling

EMI can be a greater concern in heavy industrial settings where high voltages and equipment, such as motors and generators, produce high levels of electrical noise. Using coaxial cabling in these settings affords greater resistance to the effects of EMI than using twisted-pair cabling. Fiber-optic cabling is an even better solution in heavy industrial settings because it is wholly resistant to EMI. (Changing electromagnetic fields has no effect on the light waves traveling along a glass fiber.)

See Also: *cabling, noise, signal*

Electronic Business Extensible Markup Language (ebXML)

An Extensible Markup Language (XML) standard that allows businesses to locate each other on the Internet, form partnerships, and exchange business information.

Overview

The ebXML standard specifies protocols and mechanisms that allow businesses to use the Internet and XML to create and centrally store business profiles of their companies, find other companies providing desired types of business services, enter into partnership agreements, and collaborate through electronic document exchange such as invoicing, receipts, shipping notices, and so on. The ebXML standard is designed to promote electronic business between companies of any size located anywhere in the world using a common infrastructure (the Internet) and a common language for sharing structured information (XML).

The ebXML standard provides open specifications for how companies define their business processes, create and register company profiles and business processes, enter into trading agreements, and exchange business information using XML messages. Businesses can use ebXML to exchange business information with each other without being concerned about the structure of the underlying data processes of other partners in the process.

The ebXML standard is an initiative of the Organization for the Advancement of Structured Information and Standards (OASIS) and a United Nations (UN) standards body called UN/CEFACT (United Nations Center for Trade Facilitation and Electronic Business). Development of the ebXML standard began in 1999 with the backing and support of IBM, Sun Microsystems, BEA Systems, Commerce One, and a number of other companies.

Implementation

The ebXML standard specifies a set of protocols for packaging business information as high-level messages and routing them to required destinations. Any kind of business transactional message can be encapsulated by ebXML, including electronic data exchange (EDI) X12 messages, EDIFACT messages, XML messages, or some proprietary transactional message schemes.

The ebXML protocol suite is modular in architecture and consists of several protocols that enable encapsulation, transport, and routing of XML messages. To help promote uniform standards in the B2B arena and prevent fracturing of the market, the ebXML group has agreed not to compete with the developers of Simple Object Access Protocol (SOAP), but instead to incorporate SOAP 1.1 as its underlying protocol for enabling remote activation of software components over the Internet. SOAP 1.1 was developed by Microsoft in conjunction with IBM.

For More Information

Visit the ebXML initiative at *www.ebxml.org.*

See Also: *Simple Object Access Protocol (SOAP), XML*

Electronic Data Gathering, Analysis, and Retrieval

An online document management system used by the U.S. Securities and Exchange Commission (SEC), better known by its acronym, EDGAR.

See: *EDGAR*

electronic data interchange (EDI)

The industry standard format for exchanging business information electronically.

Overview

Electronic data interchange (EDI) is a well-established standard by which companies can exchange business data and perform financial transactions using electronic means. EDI is commonly used by large companies to link their financial systems to supply-chain partners to automate and speed procurement for assembly line processing. Some analysts estimate there are more than 300,000 companies worldwide using some form of EDI to streamline their procurement processes.

EDI is a compact format that allows information to be structured in a way that it can easily mapped to traditional business forms such as invoices, purchase orders, receipts, and so on. EDI is used mostly by large companies that process high volumes of business transactions, and it can save these companies considerable costs by greatly reducing paperwork, mail, and fax charges.

History

EDI was born in the 1970s when large companies such as Kmart Corporation and Sears, Roebuck, and Company saw the need for a standard way of exchanging business information with trading and supply-chain partners. Developing custom solutions for electronic business document exchange was costly, so the Data Interchange Standards Association (DISA) was formed, consisting of government, transportation, and private sector companies, to address this issue. In 1979, EDI was approved as an American National Standards Institute (ANSI) standard called X.12. The X.12 standard defines the data dictionary used by EDI for formatting messages for standard communications between business partners. Other standards competing with EDI for electronic exchange of business documents were concurrently developed, but by the mid-1980s, X12 had become a widely recognized standard and EDI began to be widely deployed, especially in large companies.

Architecture

The basic unit of an EDI transmission is the message, which consists of a transaction set with a header and footer attached. An EDI message adheres to a standard format called the Electronic Data Interchange for Administration, Commerce, and Transport (EDIFACT) protocol.

An EDI transaction set is roughly equivalent to a typical business form, such as a purchase order, and consists of data segments, each containing various fields delimited by some character. These fields represent individual elements of the business transaction, such as company name, account number, quantity, and so on; they are formatted according to a standard code. This code is then implemented as a map between your business application's data fields and the type of EDI standard appropriate to the transaction performed.

EDI transactions are typically processed in batch form. Some forms of interactive EDI have emerged, but the basic architecture of EDI was designed around the concept of mainframe batch processing.

Implementation

EDI-enabled systems communicate through translation software that formats the data into standard EDI encoding format. This information is then exchanged using one of several methods:

- Using a dedicated leased line between the business partners. This method is expensive but is often employed by large enterprises that have high volumes of EDI transactions to process.
- Using a dial-up modem connection between business partners. This method saves costs by using EDI's strength batch-processing strength. Transactions can be queued and then sent as a batch job over a dial-up connection to save money. Small to medium-sized supply-chain partners often use this method to exchange business information with a large company purchasing their goods or services.
- Through an external third-party value-added network (VAN) service provider that acts as a clearinghouse for EDI transactions. The VAN processes EDI messages and routes them to the appropriate electronic mailbox for the destination business partner, who can then retrieve the EDI messages from the mailbox and process the transactions using business applications. The VAN is responsible for message routing, delivery, security, auditing, and archiving. This approach has grown in popularity over the last decade and is probably the most popular EDI implementation in use today.

A newer method used by small suppliers to exchange EDI information with large manufacturers is Web-enabled EDI. Typically, a VAN will offer a Web forms front end that the supplier can use to submit invoices and issue receipts to the purchasing company. This saves suppliers considerable costs over having to build EDI into the back end of their business processes but involves additional expenditure of manual labor in entering data into the forms. Nevertheless, this is a popular scheme that has become widely implemented in some sectors.

Advantages and Disadvantages

Besides its entrenched usage in the big business marketplace, particularly in government, manufacturing, transport, and warehouse sales, EDI has other advantages over such emerging technologies as Extensible Markup Language (XML). For one thing, EDI messages are compact, using a highly condensed format that makes them difficult to read. XML messages, by comparison, are plain text and tend to be much larger than EDI messages. As a result, small businesses that use dial-up connections for exchanging business information with their purchasers and suppliers can save online costs using EDI compared to XML. Because EDI mainly uses leased lines, the technology is intrinsically more secure than a technology such as XML that uses an insecure public network such as the Internet. However, by employing virtual private network (VPN) technology for tunneling over the Internet, the level of security in using XML has been made comparable to that of EDI.

While the costs of implementing EDI or leasing VAN services might at first glance seem higher than XML, this is not actually true because XML is not yet an established standard for communication of business transactions. In particular, XML has the same hidden costs as EDI due to the expense of building either system into a company's back-end business processes, which usually requires much customized programming and tinkering.

EDI's disadvantages are more perception than reality. That EDI is difficult to implement is acknowledged, but so is any translation system that must be deeply integrated into the back end of a company's business software, and nowadays EDI-enabled Enterprise Resource Planning (ERP) and customer relationship management CRM systems are commonly available, as are tools for helping developers custom-build EDI into existing business processes. Another perceived disadvantage of EDI is that it is complex and difficult to learn, but most EDI programmers would disagree with this assessment.

Marketplace

Some of the bigger VANs in the EDI marketplace include GE Information Services and IBM's Advantis. General Electric also offers a Web-based EDI service called GE TradeWeb, which provides companies with browser-based access to a library of EDI-enabled Web forms and an EDI mailbox for exchanging transactions with their business partners. Another player in this market is Sterling Commerce with its Gentran Web Suite, which uses Microsoft ActiveX technologies.

For the foreseeable future, both EDI and XML are expected to coexist, and as a result efforts are under way by both standards bodies and vendors to harmonize the two. Vitria Technology offers a kind of universal translation system for changing EDI information into XML and vice versa. General Electric is implementing the XMLSolutions Business Integration Platform to streamline its online procurement system. Another player in this hybrid EDI/XML service provider market is Paper-Free Systems, now acquired by Sybase.

Prospects

Some analysts view the emergence of XML as a threat to the very existence of EDI, supposedly relegating EDI to the arena of legacy systems. This is hardly the case, and most of the electronic business world still gets by using EDI. However, XML has some advantages over EDI; namely, it is more flexible, easier to work with, and more open in its specifications. On the other hand, just as there are different flavors of EDI that hinder interoperability, XML itself has more than 100 different variants, and it might take an initiative such as ebXML (Electronic Business Extensible Markup Language) to bring order to the XML chaos and make XML a truly viable alternative to EDI.

Most large companies are somewhat reluctant to migrate wholesale form EDI to XML. Besides the considerable investment they have already made in EDI systems and the "if it ain't broke, don't fix it" attitude that results, a big concern is the reliability of using XML for exchange of business information over the Internet. Because large businesses usually implement EDI using leased lines, carriers can provide these companies with service-level agreements (SLAs) guaranteeing minimal downtime. The Internet is another factor, however, and it is hard to guarantee bandwidth and availability for information transmitted over the Internet. For batch processing of EDI transactions this is not a big issue, but for companies with delay-sensitive assembly-line processes that use real-time EDI for procurement of direct materials, the XML/Internet combination does not offer the same guarantees as the leased-line/VAN implementations of EDI. As a result, large companies that depend on EDI have been reluctant to open their supply chains to replace EDI with XML, and many are taking a wait-and-see attitude, believing that if they fall behind in the short run they can always use their deep pockets to catch up in the long run.

For More Information

Visit the Data Interchange Standards Association (DISA) at *www.disa.org.*

See Also: *B2B, e-business, XML*

Electronic Industries Alliance (EIA)

The main trade organization representing the U.S. high-tech community.

Overview

The Electronic Industries Alliance (EIA) was founded in 1924 as the Radio Manufacturers Association. The EIA plays an important role in enabling U.S. electronics producers to be competitive by developing technical standards, hosting trade shows and seminars, performing market analyses, and facilitating relations with the government. The EIA represents a broad spectrum of U.S. electronics manufacturing interests.

The EIA is organized along the lines of specific electronic products and markets, with each sector, group, or division having its own board of directors and its own agenda for enhancing competitiveness. Major divisions include the components, consumer electronics, electronic information, industrial electronics, government, and telecommunications divisions.

An important computer networking function of the EIA is the series of standards for residential and commercial network cabling that are collectively known as the EIA/TIA wiring standards. Individuals and companies installing cabling for computer networks must follow these standards to meet government legal and safety requirements.

For More Information

Visit the Electronic Industries Alliance (EIA) at *www.eia.org.*

electronic tape vaulting

The practice of backing up data directly to a remote backup facility.

Overview

Classic backup procedures involve backing up data regularly to network tape drives and libraries. In addition, daily copy backups are made of critical business data on servers and these tapes are taken off-site to a secure storage facility. When a disaster occurs, recovery using these off-site daily copies typically takes 48 to 72 hours because the hardware failure must be repaired or the server replaced, the operating system installed, and tapes shipped in from the off-site storage location. Some data is typically lost permanently under this scenario because the tapes are written only once a day but business transactions take place continually.

Electronic tape vaulting, or e-vaulting, is a technique that helps make recovery times faster and restores more up-to-date. In a typical scenario, e-vaulting supplements an existing backup plan similar to the one described above. Information written to local storage on servers is also transmitted over the network through a wide area network (WAN) link to a remote e-vaulting site, where it is written to tape. Data can be e-vaulted periodically (once an hour, for example), or even continuously as each transaction occurs. This transactional information, coupled with traditional daily copy backups, allows databases and other business information to be restored with little or no data loss.

Marketplace

Large enterprises have been using e-vaulting for some time, but recently with the proliferation of storage service providers (SSPs) even small to medium-sized businesses can lease e-vaulting services from a provider. An example of such a service is provided by CNT, a specialist in storage area networking and other storage technologies, and Iron Mountain, a global leader in records management services. Using UltraNet, CNT's storage networking solution, a company can e-vault information incrementally to Iron Mountain's tape vaulting sites.

Notes

E-vaulting can also be used to back up data directly to mirror servers running at remote locations controlled either by the company itself or by storage service providers. This form of e-vaulting is more properly called mirroring.

See Also: *backup, disaster recovery, mirroring*

e-mail

Stands for electronic mail; any system for electronically sending and receiving messages.

Overview

E-mail is arguably the technology that has had the greatest impact on how companies conduct businesses in modern times. E-mail has become the lifeblood of business, with some analysts estimating that fully one-third of all business-related information resides on mail servers, users' personal folders, and mail archiving systems.

E-mail is used for virtually every type of business communication, including marketing, invoicing, and customer service. E-mail saves businesses millions of dollars through the elimination of costly paper contracts, invoices, and receipts. E-mail also costs businesses millions of dollars in wasted time dealing with spam (unsolicited commercial e-mail) and undoing the effects of e-mail viruses. Despite these negative aspects, however, most companies would be at a standstill if their e-mail systems went down.

Estimates suggest that the number of commercial and private e-mail mailboxes globally was more than 500 million in 1999 and may well top 1 billion by the end of 2002. With the advent of wireless messaging, this figure may increase much more rapidly in the next few years. E-mail today is what the telephone was at the beginning of the century—a technology that shaped the evolution of business and commerce worldwide.

History

While e-mail had its roots in the early 1970s with the UNIX community and ARPANET, the first widely-used commercial e-mail system was the IBM mainframe host-based system called PROFS. Early e-mail systems were purely text-based and were expensive to deploy and complex to maintain, but they had an immediate impact on business.

With the move from mainframe systems to a client/server environment in the 1980s, a new breed of e-mail system arose called workgroup mail or LAN mail. Notable products in this area included Microsoft Mail, Lotus cc:Mail, and Novell GroupWise. Over time, these were replaced with collaborative systems that allowed users to exchange not only messages but also schedule and task information. Popular examples of these third-generation systems included Microsoft Exchange and Lotus Notes.

While these developments were occurring, efforts were under way to develop global standards for electronic messaging. These efforts resulted in two main systems: Simple Mail Transfer Protocol (SMTP), developed by the Internet community, and X.400, developed by the International Telecommunication Union (ITU). X.400 rapidly became a popular messaging format that is still used in parts of Europe, but SMTP mail, which was developed in the United States as part of the ARPANET project, eventually superseded X.400 and now enjoys worldwide popularity and acceptance as the universal e-mail system. Messaging and collaboration platforms, such as Microsoft Exchange, now support SMTP by default.

Implementation

Early local area network (LAN) mail systems such as Microsoft Mail and Lotus cc:Mail were essentially passive systems where the mail server was nothing more than a set of folders for containing users' mail. It was up to the mail client to deliver messages to the server and retrieve waiting messages. All processing was thus done by the client, which would periodically poll the server to see if any mail was waiting for it to download. These systems were cheap and easily set up and maintained, but they scaled poorly and had difficulty supporting more than a few hundred users effectively.

The next evolution of e-mail was client/server messaging. Here the passive mail server was replaced by an active server that contacted the client when mail was ready to be picked up. This push model of message delivery was more effective than the old pull model of constant server polling by the client, and it also made messaging more secure. In a client/server system, the client and the server both share the processing and transport of messages.

The X.400 messaging standards introduced a set of standard terminology and concepts into the messaging arena. The most notable of these new terms was MTA (message transport agent or mail transport agent), which was responsible for routing, or forwarding, messages across the network to its destination mail server. A complex messaging system would have a number of MTAs handling mail delivery. In the UNIX world where SMTP mail was born, a popular MTA was developed called Sendmail, which is still widely used on the Internet. Early UNIX mail clients such as Pine and Elm soon became popular, especially at universities and among government researchers. To augment the functionality of SMTP mail, a number of other Internet mail protocols were developed, including Post Office Protocol (POP) and Internet Message Access Protocol (IMAP), which enabled individual mailboxes to be assigned to users, and Multipurpose Internet Mail Extensions (MIME), which made it possible for text-based e-mail to contain binary information such as multimedia files and executables. SMTP itself was extended through SMTP Service Extensions and e-mail was made secure with such new technologies as Pretty Good Privacy (PGP) and Secure MIME (S/MIME).

Marketplace

For corporate messaging and collaboration, the market leader today is probably Microsoft Exchange 2000, a powerful platform that supports a host of features and can be deployed in a wide range of environments, from workgroups to enterprises to service providers. On the Internet, however, Sendmail is still the most popular program for forwarding SMTP mail.

Web-based e-mail allows users to access their personal mailboxes from anywhere on the Internet using a PC with a Web browser and a modem. Microsoft Exchange

2000 Server includes a feature called Outlook Web Access (OWA) that supports this kind of e-mail, as do Lotus iNotes R5, Novell GroupWise 5.5e, Imail Server from Ipswitch, and InScribe Internet Messaging Server Web Mail from Critical Path.

In the wireless messaging arena, a major player is Research In Motion (RIM) with its BlackBerry messaging system. The BlackBerry server application works with Microsoft Exchange or Lotus Notes mail servers and allows messages to be relayed to BlackBerry handheld devices. This allows mobile professionals such as IT (information technology) administrators, to be alerted when systems go down, and it is a more effective way of communicating than using simple pagers. BlackBerry is also a very secure messaging platform because it uses Triple Data Encryption Standard (Triple DES) for encrypting all transmissions.

Service providers, too, now offer various commercial e-mail services to businesses. For businesses that need to send out mass mailings and do not want to overwhelm their mail servers with these duties, companies such as BoldFish offer server software that simplifies the creation and transmission of large volumes of e-mail. Businesses can also outsource this activity to service providers.

Issues

The greatest obstacle to wider use of e-mail in business has been security. Traditionally, SMTP mail has been transmitted in clear text across the Internet, a notoriously unsafe place for such an action to be performed. The slow evolution toward universally trusted public key infrastructure (PKI) systems has hindered the widespread deployment of encrypted messaging and has led to other solutions such as PGP being adopted by some businesses in the meantime. Another solution called Privacy Enhanced Mail (PEM) was developed by the Internet Engineering Task Force (IETF) and is commercially offered by vendors such as RSA Data Security and Trusted Information Systems.

Besides the encryption issue, the last few years have seen the proliferation of what many thought could never occur: e-mail viruses. Some of these viruses have wreaked terrific havoc on corporate and commercial messaging systems around the world. The first such instance was the Internet worm developed by Robert Morris in 1988, which took advantage of a weakness in Sendmail to bring down 6,000 SMTP mail servers around the globe in only 24 hours. More recent examples include the Melissa and LoveLetter viruses, which exploited enhanced collaboration features of Microsoft Outlook to crash mail servers at major Internet service providers (ISPs) and large corporations.

The growing trend toward Hypertext Markup Language (HTML) mail instead of plaintext messaging has also had its associated issues. For example, some marketing companies now send out their HTML messages with a tiny 1-pixel scripted image called a bug in them. The result is that when a user opens the message to read it in his mail program, information such as his Internet Protocol (IP) address and Web site visiting habits is collected from his machine and transmitted to the company. Some companies deal with such issues by simply disabling HTML mail altogether or preventing scripts from running on mail clients, but this seriously hinders the collaborative power of modern mail applications.

Prospects

E-mail continues to gain ground in the business world through such innovative technologies as Web-based messaging, which allows a user to access his personal mailbox from any Internet-enabled PC that has a Web browser on it, and wireless messaging, the “next big thing,” is starting to make big inroads in the enterprise through BlackBerry and Personal Digital Assistants (PDAs) Palm and PocketPC.

On the other hand, the next big thing may be the legal issues associated with the growing mountain of old e-mail residing on mail servers in back rooms of corporate networks. In regulated industries such as banking and securities trading, the law requires that all documents relating to business activity be retained for a number of years. Companies often archive old mail in user folders to file servers, but this makes it difficult to search for specific messages when required. In several instances, companies that were sued have been forced to settle because it was simply not cost-feasible for them to search through hundreds of millions of old e-mail messages for documentation that could have won their case. It is important for companies to develop digital records management policies that articulate how old e-mail should be handled and to enforce these policies to limit their legal liability when challenged in court.

Even from a business point of view, having so much critical information stored in nonrelational database management system (RDBMS) systems such as mail servers means that executives and management sometimes lack the information necessary to make truly informed decisions. The emergence of Enterprise Knowledge Portals (EKPs) is one bright spot here, as these systems are designed in part to help tap the unrealized potential of business information stored in old e-mail.

See Also: *ESMTP, Exchange Server, Internet Mail Access Protocol version 4 (IMAP4), Multipurpose Internet Mail Extensions (MIME), Post Office Protocol version 3 (POP3), Pretty Good Privacy (PGP), Privacy Enhanced Mail (PEM), Secure/Multipurpose Internet Mail Extensions (S/MIME), Simple Mail Transfer Protocol (SMTP), X.400*

e-mail address

Any address that ensures that an e-mail message reaches its intended recipient.

Overview

An e-mail address must contain sufficient information so that the message can be routed to its specific recipient. There are various kinds of e-mail address formats depending on the e-mail system in use. Address formats typically include at least two parts:

- **User portion:** This indicates the name or alias of the user to whom the mail is directed.
- **Routing portion:** This indicates the information needed to route the message to the particular mail system where the user's mailbox resides.

The following table shows some examples of e-mail address formats.

E-Mail Address Formats

Type of Address	*Example*
SMTP (Internet)	JeffS@Northwind.Microsoft.com
Microsoft Mail	Northwind/MICROSOFT/JEFFS
Lotus cc:Mail	JeffS at Northwind
X.400	C=US;a=SPRINT;p=Microsoft; o=Northwind;s=JeffS

embedded system

Any type of small-footprint specialized computer system used in industrial, commercial, and consumer applications.

Overview

An embedded system is essentially a way of making ordinary industrial and consumer devices "smart" by embedding computer technology in them. An embedded system typically consists of a single microprocessor, a small amount of memory, a specialized operating system, and applications. These applications are used to control and manage certain functions of the device that contains the embedded system. Typical uses for embedded systems are control and monitoring of industrial machinery and automated management of plant and assembly line operations.

Embedded systems typically have limited processing power and task-specific applications that are used to control and manage larger systems. They may be responsive to environmental or user-controlled conditions and may operate alone or be networked to other systems by wireline or wireless networks, including the Internet.

Examples of embedded systems abound, including

- Industrial sensors and control equipment
- Automobile antilock brake systems
- Automobile Global Positioning Systems (GPSs)
- DVD and VCR players
- Digital cameras
- Microwave ovens

Some analysts estimate there are over 5 billion embedded systems in operation today in industrial, commercial, and consumer devices.

Marketplace

In the 1980s and 1990s, most embedded systems were variants on the 8086 and 8088 processors and used DOS as their operating system platform. In recent years the market has opened up, and a number of vendors are competing in the embedded operating systems marketplace. Big players include

- Microsoft Corporation, with its Windows CE and Embedded NT operating systems platforms. Microsoft's embedded operating systems have the advantages of having mature integrated development environments (IDEs) that allow developers to quickly create and deploy applications for embedded systems, and support Transmission Control Protocol/Internet Protocol (TCP/IP) networking, Internet, and wireless networking application programming interfaces (APIs) for building distributed networks of smart devices.
- Sun Microsystems, with its Java 2 Micro Edition (J2ME). J2ME exploits the ease of development of the Java platform and has a moderate memory footprint (128 kilobytes [kB] or higher). Third-party vendor Metrowerks has an IDE for J2ME called CodeWarrior that allows embedded J2ME applications to be developed rapidly and easily. Because of the sandbox implementation of the Java VM, however, J2ME is considered by some analysts to be unsuitable for time-sensitive deterministic embedded systems such as microprocessor control systems for spacecraft or automobiles.
- Red Hat Linux, with its Linux for Embedded Developers, offers the advantages of Linux's stability and small-footprint operation (32 KB or more).
- Wind River Systems, whose VxWorks embedded operating system has been used in devices as diverse as digital cameras, Hewlett-Packard printers, and the Mars Lander space vehicle built for the National Aeronautics and Space Administration (NASA).

Prospects

An impetus has been given to the embedded systems market in recent times through the widespread availability of the Internet. Most analysts expect that the greatest growth of embedded systems in the next few years will be in the area of small Internet appliances such as Web-enabled Personal Digital Assistants (PDAs) and cell phones. The continuing advancements in processor technology that have led to continually more powerful chips for continually lower prices have also provided impetus to the growth of the embedded sector.

For More Information

Visit Microsoft's embedded systems site at *www.microsoft.com/embedded.*

See Also: *Java, Linux, Windows CE*

Emergency Management Services (EMS)

A feature of the Microsoft Windows .NET Server family that allows servers to run in headless operation.

Overview

Traditionally, UNIX enterprise systems have been configurable for headless operation—that is, running servers without a keyboard, mouse, or video card. Such headless servers are typically used for greater security and are run behind closed doors. Administrators manage these systems by using Telnet to connect to them over the network and issue administrative commands.

Windows .NET Server supports headless operation through its Emergency Management Services (EMS) feature. EMS allows a Windows .NET server to be run in headless mode and managed using a Telnet-based administration console. All management instructions are sent to the headless server using text-based commands.

Implementation

To implement a headless server, you must first enable EMS on the server, either through selecting this option during setup or by configuring the boot loader file afterward. A null modem is then used to connect the headless system through its serial port to VT100 terminal emulation software on a client machine. If the hardware supports it, the VT100 client can also manage the headless server through the universal serial bus (USB) port or over an Ethernet network using an RJ-45 jack.

Notes

To run Windows .NET Server in headless mode, the system's basic input/output system (BIOS) must allow operation without a video card, keyboard, or mouse.

See Also: *Telnet, terminal emulator, Windows .NET Server*

emergency repair disk (ERD)

A Microsoft Windows 2000 recovery tool for repairing missing or corrupt files and restoring the registry.

Overview

In Windows NT, the emergency repair disk (ERD) was a valuable recovery tool for restoring the registry or replacing boot files on a corrupted system. The Windows NT ERD contained compressed versions of registry hive, default user profile, setup.log, and other system configuration files, and it could be created from the command line using the Rdisk command.

In Windows 2000, the ERD is a little different. Instead of containing registry hives, it contains only boot files and some pointers to operating system files. When a Windows 2000 system is first installed, the registry hives are backed up to \Winnt\repair directory. Also, the ERD is created by selecting an option in the Windows 2000 Backup tool. When the Backup tool is used to back up the registry, this backup is placed in \Winnt\repair\regback.

You can use the ERD to restore a corrupted master boot record (MBR), restore missing or corrupted boot files such as Ntldr, or restore the registry from backup. However, when ERD is used to restore the registry, it does so from \Winnt\repair instead of \Winnt\repair\regback, using the pristine form of the registry that is backed during the initial installation. For more fine-grained control of restoring the registry, use the new Recovery Console tool of Windows 2000 instead of the ERD.

Having a current copy of the ERD for each server on your network is a critical part of preparing for disaster recovery. Always create a new ERD after installing new services or software or upgrading hardware or device drivers on a system.

Uses

To perform a system recovery on a machine running Windows 2000, try booting to Safe Mode first by pressing the F8 function key during startup. If this fails or if the system cannot be repaired, boot the system using the four boot floppies, select the Repair option by pressing the R key when prompted, and then either use the ERD to attempt a repair or press C to open the Recovery Console. The Recovery Console is a powerful command-line interface to the operating system designed for use only by advanced administrators.

Notes

If you cannot find your four Windows 2000 boot floppies, insert the Windows 2000 compact disc and a blank floppy into any machine running MS-DOS or Windows, click Start, select Run, and enter the following path into the Run box:

```
<cdrom_drive>\bootdisk\makeboot a:
```

In Windows XP and Windows .NET Server, ERD is being replaced by a feature called Automated System Recovery (ASR).

See Also: *Automatic System Recovery (ASR)*

emergency startup disk

A floppy disk created during the setup process for Microsoft Windows 98 and Windows Millennium Edition (Me) that can be used to troubleshoot boot problems.

Overview

The emergency startup disk contains files necessary to load a command-line version of Windows, plus other useful system-recovery utilities, including a real-mode registry editor. When you insert an emergency startup disk into your computer and reboot, the computer starts from the disk instead of from the hard drive.

Having a current copy of the emergency startup disk for each machine running Windows 98 or Windows Me on your network helps with disaster recovery if these machines fail to boot properly. You should create a new emergency startup disk whenever you make a configuration change to a machine running Windows—for example, when you install new hardware or update device drivers.

EMI

Stands for electromagnetic interference, electrical noise induced in cabling by the presence of nearby electrical equipment such as motors, air conditioners, fluorescent lights, and power lines.

See: *electromagnetic interference (EMI)*

EMS

Stands for Emergency Management Services, a feature of the Windows .NET Server family that allows a server to run in headless operation.

See: *Emergency Management Services (EMS)*

emulation

Any process by which one device mimics the functions of another device.

Overview

In computer networks, emulation usually refers to protocol conversion, a process by which a device that understands one protocol can speak with a device that understands a different, incompatible protocol. The environment in which emulation is chiefly used is mainframe computing, where asynchronous terminal emulators are used to emulate and replace more expensive synchronous terminals. For example, a PC with a modem and VT100 terminal emulation software can replace a synchronous VT100 terminal, eliminating the need for a dedicated serial connection between the mainframe and the terminal.

Common types of mainframe terminal emulators include

- **3270:** The 3270 synchronous protocol is used by IBM mainframe hosts that use the Systems Network Architecture (SNA).
- **5250:** The 5250 synchronous protocol is used in the IBM S-series mainframe environment and in AS/400 midframe environments.

See Also: *3270, 5250*

Encapsulating Security Payload (ESP)

A protocol in the IPsec suite of protocols that handles encryption.

Overview

IPsec is actually a suite of protocols that consists of two main protocols:

- **Authentication Header (AH):** This protocol ensures that IPsec packets have not been altered during transmission and to verify the sender's identity. AH is included in IPsec to provide authenticity.
- **Encapsulating Security Payload (ESP):** This protocol ensures that IPsec packets cannot be read except by their intended recipients. ESP is included in IPsec to provide privacy.

ESP is generally used in conjunction with AH to provide maximum security and integrity for IPsec transmissions. However, either ESP or AH can be used alone if sufficient for the intended purposes.

By default, ESP uses the symmetric encryption algorithm Data Encryption Standard (DES) to encrypt the payload of an IPsec packet. ESP can also be configured to use Triple DES, depending upon encryption export restrictions of the business involved.

See Also: *Authentication Header (AH), Internet Protocol Security (IPsec)*

encapsulation

Generally, the process of enclosing one type of data packet using another type of data packet.

Overview

Encapsulation occurs when a lower-layer protocol receives data from a higher-layer protocol and then places the data into the data portion of its packet format. Encapsulation at the lowest levels of the Open Systems

Interconnection (OSI) reference model is usually referred to as framing. Examples of different types of encapsulation include

- An Ethernet frame that encapsulates an Internet Protocol (IP) packet, which itself encapsulates a Transmission Control Protocol (TCP) packet, which then encapsulates the actual data being transmitted over the network
- An Ethernet frame encapsulated in an Asynchronous Transfer Mode (ATM) frame for transmission over an ATM backbone

The data-link layer (Layer 2) of the OSI networking model is responsible for encapsulating or framing data for transmission over the physical medium. In local area network (LAN) technologies, this is usually Carrier Sense Multiple Access with Collision Detection (CSMA/CD) for Ethernet networks. For wide area network (WAN) technologies, the data-link protocols used depend on whether the communications are point-to-point or multipoint:

- For point-to-point communications, possible WAN data-link protocols include Point-to-Point Protocol (PPP) and High-level Data Link Control (HDLC) protocol.
- For multipoint communications, possible WAN data-link protocols include frame relay, ATM, Switched Multimegabit Data Services (SMDS), and X.25.

See Also: *frame, Open Systems Interconnection (OSI) reference model*

Encrypting File System (EFS)

A feature of Microsoft Windows 2000, Windows XP, and Windows .NET Server that allows files stored on NTFS file system (NTFS) volumes to be secured through encryption.

Overview

Encrypting File System (EFS) is designed to protect data on NTFS volumes from local access by unauthorized user EFS which does not work on FAT or FAT32 volumes encrypts information in files at the bit level so that if a hard drive is stolen from a user's system and placed in another system, the information on the drive will be unreadable. In this way, EFS ensures the privacy of a user's information stored on disk and finds particular application with systems vulnerable to theft, such as laptop computers.

EFS is integrated in the NTFS used by Windows 2000, Windows XP, and Windows .NET Server; it is not available for older forms of NTFS, such as the one used in Windows NT 4. EFS operates transparently from the point of view of users: files are automatically encrypted when they are created or moved to encrypted folders and are automatically decrypted when the user needs to access the information stored within them.

EFS also includes a Data Recovery System that employs a trusted recovery agent (usually the Administrator account) that can decrypt any user's encrypted files in an emergency.

The following EFS features have been added to Windows XP Professional and Windows .NET Server editions:

- Additional users can be authorized to access encrypted files.
- Offline files can now be encrypted.
- Data recovery agents are recommended options.
- The Triple-DES encryption algorithm can be used to replace DESX.
- A password reset disk can be used to safely reset a user's password.
- Encrypted files can be stored in Web folders.

Implementation

EFS employs a combination of private and public key cryptography schemes. When EFS receives a request to encrypt a file, a secret (private) key is automatically generated in the form of a random number string. This secret key is called the File Encryption Key (FEK) and is generated using a modified version of the Data Encryption Standard (DES). The FEK itself is secured by encrypting it using the user's private key—a public/private key pair is automatically generated for each user and stored in Active Directory directory service. The encrypted FEK is stored on disk with the user's encrypted files.

The advantage of using this combination of two encryption schemes is that the faster symmetric encryption scheme is used for actual encryption and decryption of file data and the slower public key scheme is used only to protect the user's own private key from theft and misuse. Although EFS employs public key encryption, it does not require a certificate authority (CA) to issue public/private key pairs. Instead, EFS automatically generates these key pairs for individual users and for trusted recovery agents.

Notes

If you are working with applications that create temporary files, you might want to enable encryption at the folder level instead of the file level to guard against unauthorized access to your temporary files. With folder-level encryption, all files in the folder are encrypted.

See Also: *encryption, encryption algorithm*

encryption

The process of rendering information unreadable to all but the intended recipients, who have the ability to decrypt it.

Overview

Cryptography is the science of creating workable procedures for encrypting and decrypting messages. Encrypting messages and transmissions ensures their

- **Privacy:** No one can read an encrypted message other than its intended recipients.
- **Integrity:** An encrypted messages that is intercepted in transit and modified generally becomes garbage when received by its intended recipient—a simple test of whether the message has been tampered with.
- **Authenticity:** A good encryption scheme will help you verify that the message was indeed sent by the person it says it is from by authenticating the identity of the sender.

Cryptography's goal is to ensure that an encrypted message intercepted by a distrusted user cannot be decrypted in a feasible amount of time. Encryption is synonymous with cryptography and has been the basis of all secure communications since ancient times. With the rapid growth in recent years of the Internet as the de facto medium for businesses and consumers to exchange information, encryption has taken on new importance resulting in an explosion of cryptographic technologies and standards has resulted.

Uses

Symmetric key encryption is widely used for securing digital transmission of information. For example, the DES encryption scheme used by the U.S. government since 1974 is a symmetric key encryption algorithm, as is its recent successor, the Advanced Encryption Standard (AES). Symmetric key encryption is also employed in the Windows NT LAN Manager (NTLM) authentication scheme of Microsoft Windows NT and in Kerberos, the default authentication scheme of Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Asymmetric or public key encryption, on the other hand, is widely used on the Internet in the form of the SSL protocol discussed previously. Public key encryption was developed by Whitefield Diffie and Martin Hellman in 1976, and it was made popular by Phil Zimmerman with his Pretty Good Privacy (PGP) encryption scheme for e-mail messaging, which was first released in 1991.

Asymmetric encryption is much slower than symmetric encryption, so many encryption technologies use a combination of the two. In SSL, for example, asymmetric encryption is used during SSL session initialization to securely exchange a secret key between users so that the remaining encryption performed during the session is done using the much faster symmetric encryption scheme.

Implementation

The basic element that makes possible both encryption and decryption is the key. A key is typically a numeric value that is employed in a mathematical procedure called an encryption algorithm to convert ordinary text (plaintext) into encrypted text (ciphertext) and vice versa (encryption algorithms are discussed separately in the corresponding article in this chapter). The number of keys used and the details of how they are employed distinguishes two basic types of encryption, namely symmetric and asymmetric (public) key encryption.



Encryption. *The public key encryption method.*

Symmetric key encryption uses a secret key known only to the sender and the recipient of the message (and perhaps to others whom they trust). The secret key is used to encrypt the message when it is sent and to decrypt it when it is received. The actual encryption process involves mathematically combining (hashing or transforming) the message and the key in some complex fashion that is virtually impossible to undo unless the recipient also has the key. Symmetric key encryption is very secure, but suffers from one problem—if you want to send a message to someone who does not have your key, you must also find a way to securely transmit a copy of the key. This difficulty makes symmetric key encryption generally unworkable for electronic communication over a network or telecommunications service, except where only the original sender and recipient will need the key. For example, symmetric key encryption works in cellular phone communication when only the subscriber and the service provider need a copy of the user's key. Symmetric key encryption is the oldest form of encryption, dating from at least Roman times.

Asymmetric or public key encryption is a newer method that is becoming widely used in many computer networking and telecommunications systems. For example, public key encryption is employed by the Secure Sockets Layer (SSL) protocol used for transmitting sensitive information such as credit card numbers over the Internet. SSL establishes a secure communications session over the Internet by using public key encryption, which provides every participating user with a public key and a private key. Users are the only ones who know their private keys, whereas their public keys are generally available to anyone who wants them. Remember that if a message is encrypted with a user's public key, it can be decrypted only with the same user's private key, and vice versa.

For example, in public key encryption, if user A wanted to send an encrypted message to user B, it would typically work like this:

1. User A requests user B's public key or obtains this key from a certificate authority (CA) that both users trust.
2. User A encrypts his message using user B's public key and sends the encrypted message to user B.
3. User B receives the encrypted message from user A and decrypts it with user B's private key.

The preceding approach outlines the steps used for encrypting and decrypting the actual message being transmitted during a secure communication session. A different approach, called a digital signature, is used to confirm the sender's authenticity and the message's integrity. Digital signatures are encrypted in a reverse fashion to the message itself. Specifically, if user A wants to send his digital signature to user B, then

1. User A creates a hash of his message using a hashing algorithm. This hash forms the basis of the digital signature, which user A then encrypts using his own private key.
2. User A appends the encrypted digital signature and his own public key to the message, which is then encrypted using user B's public key.
3. User B receives the message and attachments, decrypts its contents using her own private key, and uses user A's public key to decrypt the digital signature that he attached to the message. User B then generates a hash of the received message and compares this to the digital signature that user A sent. If the two are identical, it is unlikely that the message has been tampered with in transit.

Issues

Export of encryption technology is controlled by U.S. law. Certain encryption schemes can be exported only to trusted nations and might require a government review before such export is allowed.

See Also: *Advanced Encryption Standard (AES), Data Encryption Standard (DES), encryption algorithm, Pretty Good Privacy (PGP), public key cryptography, Secure Sockets Layer (SSL)*

encryption algorithm

A mathematical procedure for encrypting data using a key.

Overview

Encryption algorithms form the basis by which encryption can take place and are fundamental to cryptography. Encryption algorithms generally use some kind of mathematical key (chosen from a large set of available keys) to transform plaintext (the data being encrypted) into ciphertext (the resulting encrypted data). An encryption algorithm must be reversible so that the recipient can use another mathematical key to decrypt the data. A good encryption algorithm should be difficult to decrypt if you do not know the decrypting key, and the only method that should be possible to force decryption should be the brute force method of simply trying every possible decryption key (in other words, there must be no shortcuts or back doors for decryption). If an encryption algorithm is really good, it would take massively parallel computers centuries, or even eons, of intense processing, trying all possible keys, to decrypt a single message if they do not know the specific decryption key.

Implementation

Encryption algorithms typically perform their encryption process on multibyte segments of data instead of on one byte at a time. Such an algorithm is known as a block cipher because it encrypts data one block at a time. For example, the Data Encryption Standard (DES) algorithm, a 56-bit key algorithm used for many years by the U.S. government, encrypts data 64 bytes at a time.

Encryption algorithms employ mathematical procedures called hash functions, which are repeatedly applied to plaintext to scramble it into ciphertext. The combination of a hash function and a key form the basis for the encryption process.

Examples

Encryption algorithms are of two basic types: symmetric and asymmetric.

Symmetric algorithms employ the same key, called a secret key, for both encryption and decryption of a message. This process is also known as asymmetric or secret key cryptography. Examples of symmetric algorithms include

- **DES:** This uses a 56-bit key and was the U.S. government standard for encryption until 2001, when it was replaced by the Advanced Encryption Standard (AES). DES is no longer considered secure and was first cracked in 1997.
- **AES:** This can use keys up to 256 bits in length, and it has replaced DES as the official U.S. government encryption standard.

Asymmetric algorithms employ a different key for encrypting and decrypting data. The two keys are mathematically related and are called a key pair, with the private key used for encrypting the message and the public key used for decrypting it. Examples of asymmetric algorithms include

- **Diffie-Hellman:** Developed by Whitefield Diffie and Martin Hellman in 1976, this is the original public key encryption algorithm and is used in the Secure Sockets Layer (SSL) protocol on the Internet for securely exchanging secret keys between remote systems.
- **Rivest-Shamir-Adelman (RSA):** Developed in 1997 by the Ron Rivest, Adi Shamir, and Leonard Adelman, this algorithm can be used both for encryption and secure authentication. It is used in SSL, Transport Layer Security (TLS), and IPsec communications in virtual private networks (VPNs) and over the Internet.

See Also: *Advanced Encryption Standard (AES), Data Encryption Standard (DES), encryption, public key cryptography*

End-User License Agreement (EULA)

A type of contract between a computer software publisher and the purchaser of the software that outlines the various rights granted to the purchaser for legal use of the software.

Overview

The End-User License Agreement (EULA) for a software product is usually found on a separate piece of paper accompanying the product, inside the front cover of the user manual, or onscreen prior to installing the software. You should read and become familiar with the terms of your EULA for the software you purchase. Failure to follow the terms of the EULA might expose you or your company to prosecution for software piracy.

You can access the EULA for Microsoft Windows Millennium Edition (Me) by opening the text file License.txt. It is located in the \Windows folder. In Windows 2000, Windows XP, and Windows .NET Server, the file is called eula.txt and is located in the \System32 folder.

For More Information

Visit Microsoft Corporation's antipiracy site at *www.microsoft.com/piracy.*

See Also: *license*

enhanced Category 5 (Cat5e) cabling

Also known simply as Cat5e, a recently ratified standard for structured local area network (LAN) wiring.

Overview

Enhanced Category 5 (Cat5e) cabling is the only ratified cabling standard that is capable of supporting transmission speeds faster that 100 megabits per second (Mbps), although Category 6 (Cat6) and Category 7 (Cat7) specifications have been proposed. Supporting frequencies up to 350 megahertz (MHz) or higher, Cat5e cabling is typically four-pair solid conductor 24-gauge unshielded twisted-pair (UTP) cabling that has a low capacitance in the range of 13 to 14 pF/foot, as compared with regular Category 5 (Cat5) cabling that has a capacitance of around 17 pF/feet. The impedance of Cat5e cabling is 100 ohms, the same as for regular Cat5 cable.

Other specifications of Cat5e include

- Attenuation less than 22 decibels (dB) at 100 MHz (same as Cat5)
- Near-end crosstalk (NEXT) less than 35.3 dB (3 dB higher than Cat5)
- Power-sum NEXT (PS-NEXT) less than 32.3 dB (unspecified for Cat5)
- Return loss less than 20.1 dB (unspecified for Cat5)

Uses

The electrical characteristics of Cat5e cabling make it the recommended type of cabling for most new installations of structured wiring, especially companies planning an eventual migration from Fast Ethernet to 1000BaseTX Gigabit Ethernet (GbE). Cat5e cabling can be used for Ethernet, Integrated Services Digital Network (ISDN) wiring, and 155-Mbps Asynchronous Transfer Mode (ATM) networks.

If you plan to use Cat5e cabling in your network, you should ensure that all your other wiring components match these specifications. This means purchasing and installing enhanced Cat5 patch panels, wall plates, and other components. Also, be sure to strictly follow wiring guidelines because improper installation of Cat5e cabling will result in loss of potential bandwidth. The real key to operating a successful high-speed UTP wiring system is careful installation.

See Also: *cabling, Category 5 (Cat5) cabling, premise cabling, structured wiring*

Enhanced Data Rates for Global Evolution (EDGE)

A third-generation (3G) upgrade for the 2.5G General Packet Radio Service (GPRS).

Overview

Enhanced Data Rates for Global Evolution (EDGE) was designed as a way of easily upgrading certain second-generation (2G) cellular systems to 3G systems with little additional cost. EDGE can be used to upgrade both Time-Division Multiple Access (TDMA) systems such as AT&T Wireless and Global System for Mobile Communications (GSM), which are also based on TDMA technologies. EDGE cannot be used to upgrade Code-Division Multiple Access (CDMA) systems. The official 3G upgrade for CDMA systems is instead the International Telecommunication Union's (ITU) Wideband CDMA (W-CDMA) standard. EDGE is designed to provide mobile users with wireless roaming data services of up to 400 kilobits per second (Kbps).

EDGE comes in two flavors:

- **Enhanced Circuit-Switched Data (ECSD):** This is EDGE technology applied to circuit-switched GSM systems, which provide direct connection to the Public Switched Telephone Network (PSTN) backbone.
- **Enhanced GPRS (EGPRS):** This is EDGE technology applied to packet-switched General Packet Radio Services (GPRS) systems, which routes Internet Protocol (IP) packets over the Internet.

Implementation

EDGE works by modifying the physical layer of GSM and GPRS to increase data transmission rates threefold. This is accomplished by replacing the Gaussian Minimum Shift Keying (GMSK) encoding mechanism of GSM and GPRS, which only allows one bit of information to be encoded per symbol, to 8-bit Phase Shift Keying (8-PSK), which encodes 3 bits per symbol. The result is that the theoretical transmission speed of GPRS is raised from 171 Kbps to 513 Kbps, with similar effect for GSM (these theoretical speeds are not realized in practice due to bandwidth being used for error correction).

Above the physical layer, EDGE uses the same technologies as GSM and GPRS. Existing GSM and GPRS cellular networks are easy to upgrade to EDGE, because the same equipment can be used for both the older 2G services and the newer 3G EDGE (though some hardware and software upgrades are required). In addition, costs remain low because no additional frequency licenses are required for EDGE. Although the 400-Kbps data rates offered by EDGE fall short of the envisioned 2-megabit-per-second (Mbps) speeds for 3G cellular systems, EDGE has been ratified as an official 3G system by the ITU in its IMT-2000 specifications.

Marketplace

In North America, EDGE will soon be deployed by AT&T, the major Time Division Multiple Access (TDMA) cellular provider. This will be done in stages, first by upgrading the TDMA system to GSM together with an overlay of GPRS to support data rates of 144 Kbps. The GSM/GPRS system will then be upgraded to EDGE to provide data rates of 384 Kbps. Further 3G upgrades are likely down the road, pushing speeds to 2 Mbps.

Prospects

Although EDGE is an official standard, it is not likely to be supported in many areas outside North America because most other countries having 2G TDMA systems are likely to upgrade them to W-CDMA instead, which is incompatible with EDGE.

See Also: *2G, 2.5G, 3G, General Packet Radio Service (GPRS), Global System for Mobile Communications (GSM), Time Division Multiple Access (TDMA)*

Enhanced Interior Gateway Routing Protocol (EIGRP)

A popular interior routing protocol developed by Cisco Systems.

Overview

Enhanced Interior Gateway Routing Protocol (EIGRP) is a proprietary interior routing protocol developed by Cisco to overcome certain weaknesses of IGRP (Interior Gateway Routing Protocol), an earlier proprietary routing protocol also developed by Cisco. EIGRP is a reliable, efficient dynamic routing protocol that converges quickly and avoids routing loops. EIGRP is intended for classless routing within an autonomous system (AS) and provides a way for routers within an AS to exchange routing table information with each other.

EIGRP is a hybrid protocol that employs features of both distance vector and link state routing protocols. EIGRP is similar to IGRP in several ways:

- EIGRP is a classless interior routing protocol used inside an autonomous system.
- EIGRP uses a distance vector algorithm for calculating route metrics based on link characteristics instead of hops.

- Metrics can be based on values of bandwidth, route latency, reliability, and load.

But EIGRP also differs from IGRP in many ways, and most of these differences involve the incorporation of features common to link state routing protocols. For example:

- EIGRP includes a mechanism for automatically discovering neighboring routers using HELLO packets and downloading necessary routing information from these neighbors.
- Instead of using periodic broadcasts of entire routing tables, which consumes valuable network bandwidth, EIGRP sends out only incremental updates for routing tables and only when a change in the tables requires such updates.
- Routing table information is contained within a topology database similar to that used by link state routing protocols. Only information about adjacent routers is kept in the database, not the routing table for the entire network. This helps keep the topology database small and efficient for fast routing and helps an EIGRP router to recover quickly after a failure.

Other features of EIGRP include

- **Diffusing Update Algorithm (DUAL):** This complex routing algorithm that is similar to Dijkstra's algorithm provides fast convergence and avoids routing loops.
- **Reliable Transport Protocol (RTP):** This protocol guarantees delivery of EIGRP packets to neighboring routers.
- **Protocol-dependent modules:** This feature allows an EIGRP router to support multiple network protocols including Internet Protocol (IP), Internetwork Packet Exchange (IPX), and AppleTalk.
- **MD5 authentication:** Each EIGRP packet contains an MD5 checksum to secure routing communications from outside monitoring.

Notes

Although EIGRP and IGRP share some characteristics and can work together, they are essentially different protocols (by contrast, RIPv2 is simply Routing Information Protocol [RIP] with a few added features). EIGRP can also work seamlessly with IGRP to allow routing information to be shared across boundaries of autonomous systems, which simplifies the setup and configuration of EIGRP routers considerably.

See Also: *autonomous system (AS), classless routing protocol, dynamic routing protocol, Interior Gateway Routing Protocol (IGRP), routing protocol*

enterprise

A large, geographically distributed company with a high number of users.

Overview

In a computer networking context, an enterprise-level network of computers refers to the network belonging to an enterprise; that is, a network that typically consists of thousands of computers distributed across several geographically remote locations and connected by wide area network (WAN) links.

Enterprise-level networks generally use Transmission Control Protocol/Internet Protocol (TCP/IP) and are divided into a number of smaller networks called subnets, which are linked by routers. Enterprise-level networks are often heterogeneous networks consisting of different protocols and operating systems such as Microsoft Windows NT, Windows 2000, Windows XP, Windows .NET Server, Novell NetWare, and varieties of UNIX, all interoperating to various degrees. Enterprise-level networks can include legacy mainframe and minicomputer systems as well.

This mixture of systems and protocols can make it challenging to administer and manage an enterprise-level network and offers a strong argument for upgrading legacy systems to newer, standardized ones. Companies can save considerable costs in the long run by upgrading their networks to secure, reliable, scalable network operating systems such as Windows NT, Windows 2000, Windows XP, or Windows .NET Server. The initial cost of upgrades and training are quickly recouped through lower maintenance and administration costs, the result of migrating an enterprise's heterogeneous combination of systems and protocols to a homogeneous network consisting of computers running Windows NT, Windows 2000, Windows XP, or Windows .NET Server and running TCP/IP.

Enterprise Admins

A built-in group for the Microsoft Windows 2000 and Windows .NET Server operating system platforms.

Overview

Enterprise Admins is one of four global groups that Windows 2000 and Windows .NET Server create by default to help administrators organize users in their network. The other three groups are Domain Users, Domain Guests, and Domain Admins.

Although Domain Admins are users who can perform administrative tasks on any computer belonging to the domain, the Enterprise Admins group is intended to have an even larger scope. Enterprise Admins must be able to perform administrative tasks on any computer in the enterprise.

A Windows 2000– or Windows .NET Server–based enterprise can consist of a number of domains interconnected in a domain tree, or even several domain trees connected into a domain forest. Enterprise Admins can administer the entire network for the enterprise.

Just as with the Domain Admins group, the Enterprise Admins group has one initial member: the Administrator user account that belongs to the domain. The Enterprise Admins group exists only in the root domain of the forest.

See Also: *built-in group*

Enterprise Information Portal (EIP)

A business software system used to provide a single point of access to information stored in different corporate databases.

Overview

Enterprise Information Portals (EIPs) are an evolution of corporate intranets that apply portal technologies to help manage the flood of information that fuels business. Although the intranet revolutionized the way businesses handled information by providing a standard interface (the Web browser) for accessing such information, portals provide other tools such as user profiles, personalization services, workgroup and collaboration tools, automatic indexing, and push/pull information delivery that help manage large amounts of information residing in the diverse data sources of a typical enterprise.

EIPs are simply a wedding of these two technologies, turning corporate intranets into collaborative tools that deliver personalized business information to users as they need it. EIPs generally focus on managing structured information found in databases of two common types of business applications: enterprise resource planning (ERP) and customer relationship management (CRM) applications. EIPs excel in helping users identify, analyze, and present useful information mined from diverse databases used by businesses, and are in many ways simply an extension of data warehousing (DW) and data mining (DM) technologies with an additional emphasis on integrated content management (CM) technologies. EIPs generally excel in bringing together data found in structured data sources such as structured query language (SQL)– and open database connectivity (ODBC)–compliant databases. A further evolution of these systems called Enterprise Knowledge Portals (EKPs) can also mine unstructured sources such as e-mail message repositories and document management systems.

Marketplace

Many new players have appeared since the EIP market exploded in 1999. Some of the early pioneers that have gained significant market share with their packaged EIP offerings include HummingBird International, Epicentric, and Plumtree Software. Some examples of popular EIP offerings in the marketplace include Brio.Portal from Brio Technology, Corporate Portal from Plumtree, DataChannel server from DataChannel, Freedom from InfoImage, iPlanet Portal server from Sun-Netscape Alliance, and many others.

Major operating system and business applications vendors such as IBM, Oracle Corporation, Microsoft

Corporation, and Sun Microsystems also offer suites of business applications that can be used to help build EIP solutions for corporate customers. Some EIP applications are more focused on providing corporate users with workgroup tools for collaborative use, and others focus more on enabling decision-makers in a company to access the information they need to map their company's future.

Prospects

The EIP market, which started in 1998, has grown to a multibillion-dollar industry and is expected to rival the traditional ERP and CRM markets in the next few years in scope and deployment.

See Also: *Enterprise Knowledge Portal (EKP), enterprise resource planning (ERP), intranet, portal*

Enterprise Java Beans (EJB)

A Java-based technology from Sun Microsystems for building e-commerce systems.

Overview

Enterprise Java Beans (EJB) is a set of Java specifications that can be used for building Web-based distributed transactional applications typical of e-commerce and e-business solutions. EJB is a core component of Java 2 Enterprise Edition (J2EE) and works with Java Server Pages (JSP) technologies to provide tools for developers to meet the needs of businesses in today's Internet economy. EJB is particularly popular in the UNIX environment as an alternative to Common Gateway Interface (CGI) solutions based on PERL and C/C++, but EJB applications can run on any Java-supporting platform, including Linux, Solaris, AIX, Windows NT and Windows 2000.

EJB was developed under the umbrella of the Java Community Process, and its current version 1.1 is being revised toward version 2.

Implementation

EJB is implemented as an object-oriented component programming model based on the Java programming language. As a result, EJB is a platform-independent and vendor-neutral solution for building transactional applications. EJB supports both stateful and stateless transactions through its different types of session beans. It can be used to build scalable, distributed applications that run on farms of application servers, and its component-based technology speeds and simplifies the development process to gain better time-to-market advantage.

EJB operates as a server-side component technology. It includes a number of services that make it easy for developers to write middleware supporting distributed transactional processing over the Internet. These services include database connectivity, support for distributed transactions, and security functions.

Marketplace

IBM and Inprise/Borland Corporation both offer EJB server platforms for building e-business solutions. Another company that is a popular player in this market is BEA Systems. The open-source movement is contributing its own EJB server platform, called jBoss, as well.

See Also: *Java*

Enterprise Knowledge Portal (EKP)

A business software system that couples knowledge management tools with an Enterprise Information Portal (EIP) to provide a powerful way of handling the flood of information that characterizes large businesses today.

Overview

Information is at the center of today's business, but this information is typically stored in diverse places, such as:

- **Structured data sources:** This includes information in enterprise resource planning (ERP), customer relations management (CRM), and various structured query language (SQL) and open database connectivity (ODBC) databases scattered on servers throughout an enterprise.
- **Unstructured data sources:** This includes e-mail, scheduling, and journaling information stored on mail servers and groupware servers, document management systems that include file servers and document archive systems, and Web-based information repositories such as intranets, extranets, and public Web sites.

- **Legacy data sources:** This covers all forms of data stored on legacy systems such as IBM mainframe and AS/400 systems.

Enterprise Knowledge Portals (EKPs) are systems that gather all these sources of information and allow corporate users to locate, analyze, deliver, and present personalized information through a single point of access. Using the simple Web browser as the universal front end for these systems, users can pull useful information from these sources to help them make informed business decisions or have this information pushed out to them on a regular basis using automatic search engines that parse the data sources using intelligent criteria to determine what users might need. User profiles allow EKPs to personalize the information delivered to users to present what they need, when they need it, and how they need it.

Implementation

EKPs work by combining two technologies:

- **Enterprise Information Portals (EIPs):** These systems are essentially portals to corporate intranets and provide features such as user profiles, personalization services, single sign-on, customizable interface, automatic indexing, and push/pull delivery of information to basic Web-based intranet systems.
- **Knowledge Management (KM):** These tools enable useful information to be combined and mined from sources as diverse as SQL databases, Word documents, spreadsheets, slide-show presentations, text files, and e-mail repositories.

By combining these two kinds of tools, EKP allows information of every form within a company to be unlocked and made available for making informed business decisions.

Advantages and Disadvantages

Although an EKP's advantages are clear in that it provides a unified single point of access to a company's varied sources of business information, the disadvantages are also clear, in that EKP systems are costly to set up and complex to implement. In particular, building an EKP into a company's varied sources of data could require months, or even years, to implement fully, with much of that time spent on custom development work. On the other hand, once these systems are fully implemented, they are easy to maintain and they bring significant long-term cost savings by enabling faster, more informed decision-making and improved communications among corporate users.

Marketplace

A number of companies are offering turnkey EKP solutions that can fit the needs of medium-sized companies without much development work. Portal-in-a-Box from Autonomy Corporation is one example of a turnkey EKP system that automatically classifies, links, and personalizes information and then delivers it to users as they need it.

Big players such as Lotus Development Corporation and OpenText Corporation also offer EKP systems that focus more on the collaborative aspect of business decision-making. And major business application vendors such as Microsoft Corporation, IBM, Sun Microsystems, and Oracle Corporation offer their own suites of applications that can be used to build EKP systems for large enterprises.

See Also: *Enterprise Information Portal (EIP), enterprise resource planning (ERP), intranet, portal*

enterprise resource planning (ERP)

A term describing software systems for managing a broad scope of an enterprise's business functions.

Overview

Enterprise resource planning (ERP) includes tasks such as planning, purchasing, tracking orders, supplying customers, managing inventory, servicing customer requests, producing financial reports, and bookkeeping. ERP software is modular software designed to integrate these various business functions and simplify their management.

ERP software typically consists of an integrated suite of tools for performing standard line-of-business functions such as payroll, accounting, inventory management, and order entry. ERP software is used in transportation and automotive businesses, industrial environments, and other large industrial settings. ERP software lets these businesses manage diverse business resources across the enterprise to plan more effectively for growth and expansion.

History

ERP has its roots in the software-controlled inventory control systems developed and used by large companies in the 1960s. These systems evolved in the 1970s to include scheduling features for automating procurement for assembly-line systems and were then called Material Requirement Planning (MRP) systems. During the 1980s, MRP systems continued to evolve to include distribution and shop floor control and management capabilities and became known as Manufacturing Resources Planning (MRP-II) systems. In the 1990s, these systems were further extended to include the full gamut of business functions, including project planning, engineering, finance, and human resources. The term *enterprise resource planning* emerged at this time to represent the wider scope of these large software systems.

Marketplace

The three big players in the traditional ERP marketplace are Oracle Corporation, PeopleSoft, and SAP. The biggest of these vendors is Germany's SAP AG, which has an estimated 35 percent share of the ERP market, mainly with its SAP R/3 suite of ERP applications. Another big player is Baan, which has both a traditional ERP offering and an initiative to integrate Extensible Markup Language (XML)– ERP platform through their Baan OpenWorld Integration Framework.

Traditional ERP systems are expensive and often take years to implement fully for large enterprises. In the last few years, a flood of new companies entered the marketplace offering applications that would provide Web-based front ends for traditional ERP software to Internet-enable this software for simplifying enterprise business management. One example of this is the Online Information System (OIS) from Impress Software, which uses the application programming interfaces (APIs) from the big three ERP software vendors to provide businesses access to their SAP R/3 manufacturing systems and other enterprise applications over the Internet. OIS has support for both XML and electronic data interchange (EDI) information exchange, and it is available for diverse platforms, including Windows NT, UNIX, and Linux.

With the proliferation of third-party solutions, the big three have also moved recently to Internet-enable their traditional ERP offerings to make them more competitive. An example is mySAP from SAP AG, which integrates customer relations management (CRM) functions with ERP and provides a portal front end. Although previously most ERP deployments were performed by consulting companies, the Big Three have moved recently to offer their professional services.

Prospects

The most obvious trend in the ERP market is the continuing effort to fully Internet-enable ERP systems and processes. Although early attempts at this represented no more than embedding legacy client ERP interfaces within Web browsers, ERP systems continue to evolve to make their Web-based interface friendlier and easier to use.

ERP was more than a $20-billion market in 2000 and is expected to grow over the next few years. A large portion of this represents planning, consulting, licensing, and maintenance fees for such systems. One recent development is Enterprise Information Portals (EIPs), which provide a new and innovative way of managing the flood of business data that traditional ERP applications expose. EIPs integrate the functions of ERP, CRM, and SCM (supply-chain management) systems into a single Web-based system. Many analysts believe that traditional ERP implementations are on their way out and more sophisticated and powerful EIP systems will grow rapidly, but because of the huge investment most large enterprises have put into ERP systems and the ongoing costs of maintaining them, ERP is likely to be with us for many years.

See Also: *Enterprise Information Portal (EIP)*

enterprise server

A designated server running Microsoft Windows NT, Windows 2000, or Windows .NET Server in an enterprise, which is used as a central repository for software licensing information regarding Windows NT, Windows 2000, Windows .NET Server, and Microsoft BackOffice.

Overview

In Windows NT networks an enterprise server is typically a primary domain controller (PDC), yet can also be a stand-alone server that is not part of any domain in the enterprise. All PDCs in the enterprise replicate their licensing information with the enterprise server, so the enterprise server contains a master database of this information. If there is only one domain in the enterprise, the PDC for that domain is the master licensing server. If there are several domains, each domain's PDC keeps track of licenses for that domain, and all PDCs then replicate their licensing information to the specifically designated enterprise server. Stand-alone member servers that are not part of any domain also must replicate their licensing information with the enterprise server.

They can be more than one enterprise server in an enterprise, but it is simplest to have only one because enterprise servers cannot replicate with each other.

See Also: *license*

environmental subsystems

Components of Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server that support the running of applications from different operating system architectures.

Overview

Environmental subsystems provide the necessary "environment" in which these applications can run. They are an essential part of the Windows NT operating system that enables cross-platform support for applications written for different operating systems. Windows NT, Windows 2000, Windows XP, and Windows .NET Server include the following environmental subsystems:

- Win32 subsystem for running 32-bit Windows applications
- OS/2 subsystem for running OS/2 1.X character-based applications (does not support the OS/2 Presentation Manager GUI or Warp versions)
- POSIX subsystem for running POSIX.1-compliant applications

Notes

MS-DOS–based applications run on Windows NT, Windows 2000, Windows XP, and Windows .NET Server in the context of a Win32 application called a Virtual DOS Machine (VDM) that emulates an MS-DOS environment.

environment variables

String variables containing information that an operating system uses to control services and applications.

Overview

Environment variables have been used in Microsoft operating systems since MS-DOS, where the PATH and TEMP variables used in the Autoexec.bat file were early examples. Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server offer a far more extensive selection of environment variables, including the following types:

- System (predefined) environment variables such as USERNAME, USERDOMAIN, WINDIR, and HOMEPATH. These variables are set on the system no matter who logs on and cannot be changed by any user. They specify particular parameters pertaining to the system itself, such as the location of the operating system files. They can be used in logon scripts because they are always present when any user logs on.
- User (user-defined) environment variables, such as the path to application files. User environment variables take precedence over system environment variables when the two conflict.
- Autoexec.bat environment variables, such as those used in path statements.

You can view and specify environment variables in Windows NT, Windows 2000, Windows XP, and Windows .NET Server by using the System utility in Control Panel. Environment variables may be used in logon scripts by enclosing them within percent symbols; for example, %USERNAME% contains the currently logged-on user name.

Notes

The System utility in Control Panel shows only a portion of the system environment variables defined on a system running Windows NT, Windows 2000, Windows XP, or Windows .NET Server.

ERD

Stands for emergency repair disk, a Microsoft Windows 2000 recovery tool for repairing missing or corrupt files and restoring the registry.

See: *emergency repair disk (ERD)*

ERP

Stands for enterprise resource planning, software systems for managing a broad scope of business functions for an enterprise.

See: *enterprise resource planning (ERP)*

ESMTP

Stands for SMTP Service Extensions, a set of extensions to the Simple Mail Transfer Protocol (SMTP) protocol.

Overview

ESMTP provides a series of enhancements to SMTP, including authentication between SMTP hosts, the ability to resume a connection that is interrupted without having to begin all over again (called checkpointing), and the ability to transmit multiple SMTP messages at once (called pipelining).

The ESMTP standard is defined in RFC 1869.

Implementation

ESMTP works by enabling the receiving host in an SMTP transmission to inform the sending host of what extensions it supports. Instead of beginning the session with the HELO command, the receiving host issues the EHLO command. If the sending host accepts this command, the receiving host then sends it a list of SMTP extensions it understands, and the sending host then knows which SMTP extensions it can use to communicate with the receiving host.

Implementing ESMTP requires no modification of the SMTP configuration of either the client or the mail server. Most modern SMTP mail systems, including Microsoft Exchange, support ESMTP.

See Also: *Simple Mail Transfer Protocol (SMTP)*

ESP

Stands for Encapsulating Security Payload, a protocol in the IPsec suite of protocols that handles encryption.

See: *Encapsulating Security Payload (ESP)*

EtherLEC

A Competitive Local Exchange Carrier (CLEC) offering metropolitan optical Ethernet services to businesses.

See: *metropolitan Ethernet*

Ethernet

The most popular network architecture for local area networks (LANs).

Overview

Ethernet is a baseband networking technology that sends its signals serially 1 bit at a time. In its most basic form, Ethernet operates in half-duplex mode, in which a station can either transmit or receive but cannot do both simultaneously. Another form of Ethernet is full-duplex Ethernet, which uses two pairs of wires with Ethernet switches to allow stations to send and receive data simultaneously without collisions.

Ethernet specifications define the functions that occur at the physical layer and data-link layer of the Open Systems Interconnection (OSI) reference model and package data into frames for transmission on the wire. It is available in three speeds:

- 10 megabits per second (Mbps), which is simply called Ethernet
- 100 Mbps, which is called Fast Ethernet
- 1000 Mbps or 1 gigabit per second (Gbps), which is called Gigabit Ethernet (GbE)

Because of its simplicity and reliability, Ethernet is by far the most popular networking architecture used today.

History

Ethernet was originally developed by Xerox Corporation in the 1970s and was proposed as a standard by Xerox, Digital Equipment Corporation (DEC), and Intel Corporation in 1980. A separate standardization process for Ethernet technologies was established in 1985 in the Institute of Electrical and Electronics Engineers (IEEE) 802.3 standard known as Project 802. The IEEE standard was then adopted by the International Organization for Standardization (ISO), making it a worldwide standard for networking.

Ethernet in its original form, called Standard Ethernet (or 10Base5 or thicknet), was first commercially available in 1981 and standardized as 10Base5 in 1984. A version running on thinner coaxial cable called thinnet (or 10Base2) emerged in 1985 for workgroup LAN deployments, while thicknet remained the providence of campus backbones. The first commercial Ethernet bridges also appeared about 1985.

The next major advance was deploying Ethernet over unshielded twisted-pair (UTP) cabling. This occurred in 1990 with the standardization of 10BaseT Ethernet. A fiber version called 10BaseF was developed in 1993 but never really caught on as advances in technology allowed the speed of Ethernet to be increased tenfold two years later with the development of Fast Ethernet or 100BaseT. Meanwhile, in 1992 the first commercial full-duplex Ethernet products appeared in the marketplace.

The next advance was another tenfold increase in speed to 1000 Mbps or 1 Gbps. This was standardized in 1998 as GbE or 1000BaseX, which initially ran only over fiber but was extended in 1999 to run over copper as well in the form 1000BaseT.

Other significant advances in Ethernet technologies in the last decade include

- **Auto-negotiation:** This was developed in 1996 to support hybrid 10/100 Mbps Ethernet gear and has been extended to 10/100/1000 Mbps as well.
- **Ethernet switching:** The first Layer-2 switches became available in 1992, and VLAN (virtual LAN) features were added in 1998.

Architecture

Ethernet uses the Carrier Sense Multiple Access with Collision Detection (CSMA/CD) media-access control method for determining which station can transmit at a given time over the shared medium. In an Ethernet network, each station (computer) listens to the network and transmits data only if no other station is using the network. If the wire is free of signals, any station can contend (try to take control of) the network to transmit a signal. Ethernet networks are thus based on the concept of contention and operate on a first-come, first-served basis, rather than relying on a master station that controls when other stations can transmit. If two stations try to transmit data at the same time, a collision occurs, and both stations stop transmitting. They wait a random interval of time (measured in milliseconds) and then try again. The more stations on an Ethernet network, the higher the number of collisions, and the worse the network's performance. Typical performance of a 10-Mbps Ethernet network with 100 stations will support a bandwidth of only about 40 to 60 percent of the expected value of 10 Mbps. One way of solving the collision problem is to use Ethernet switches to segment an Ethernet network into smaller-collision domains.



Ethernet. *The Ethernet II frame format.*

Ethernet stations transmit data over the wire in packages called frames. An Ethernet frame has a minimum size of 64 bytes and a maximum size of 1518 bytes. A total of 18 bytes are used for information such as source and destination addresses, network protocol being used, and other frame overhead. Thus, the maximum payload size (amount of data carried) for an Ethernet frame is

1500 bytes. Ethernet packages data into a frame by four different Ethernet encapsulation methods:

- Ethernet II, used for Transmission Control Protocol/Internet Protocol (TCP/IP)
- Ethernet 802.3, called Raw 802.3 in Novell networking and used for connectivity with NetWare 3.11 and earlier
- Ethernet 802.2, also called Ethernet 802.3/802.2 without subnetwork access protocol (SNAP) and used for connectivity with NetWare 3.12 and later
- Ethernet SNAP, also called Ethernet 802.3/802.2 with SNAP and created for compatibility with Macintosh and TCP/IP systems

Implementation

Ethernet can use virtually any physical networking topology and cabling system (medium). Although a star topology (stations that are wired in a star-like configuration to a central hub) is often used from the physical point of view, all Ethernet networks are logical bus-topology networks at heart. One station places a signal on the bus, and that signal travels to every other station along the bus.

Ethernet is available in three speeds and can be further differentiated by media and other considerations, as shown in the table.

Ethernet Speeds, Types, Standards, and Specs

Speed	*Type of Ethernet*	*IEEE Standards*	*IEEE Specs*
10 Mbps	Ethernet	10Base2 10Base5 10BaseF 10BaseT	802.3
100 Mbps	Fast Ethernet	100BaseFX 100BaseT 100BaseT4 100BaseTX	802.3u
1000 Mbps or 1 Gbps	GbE	1000BaseCX 1000BaseLX 1000BaseSX 1000BaseT	802.3z

Ethernet media specifications such as 10BaseT may seem strange and obscure but can be easily interpreted. For example, 10BaseT means **10**-Mbps baseband transmission over Twisted-pair cabling media.

Prospects

The prospects for the continuing evolution of Ethernet look strong. On the horizon is 10 GbE (10 Gbps Ethernet), which will probably become the next upgrade for enterprise network backbones. Another advance is the recent incorporation of Quality of Service (QoS) features into Ethernet using the 802.1p standard, making Ethernet more suitable for carrying delay-sensitive traffic such as voice an area that until now has been dominated by Asynchronous Transfer Mode (ATM).

Optical Ethernet is a new development that sees carriers such as Yipes extend high-speed Ethernet metropolitan area network (MAN) and wide area network (WAN) connections to businesses in metropolitan areas, eliminating the need for costly Ethernet-to-ATM/Synchronous Optical Network (SONET) access devices and turning corporate WANs into large Ethernet local area networks (LANs).

Another amazing development is that Ethernet is being considered in some quarters as a bus technology to replace PCI for computer system buses. One company involved in this development is Performance Technologies.

Where Ethernet will finally hit the wall and be replaced by some other technology is anyone’s guess. In the past 20 years, Ethernet has delivered all but knockout blows to its competitors in the LAN arena, including Token Ring, Fiber Distributed Data Interface (FDDI), and ATM. Whether it can do the same in the WAN arena reamins still in question, but it is bound to be an exciting fight.

Notes

The various Ethernet framing formats are incompatible, so if you have a heterogeneous Ethernet network, you must specify the correct frame type to allow machines running Microsoft Windows NT to see your Novell NetWare servers. Windows NT allows you to select Auto Detect from the Frame Type drop-down list on the NWLink IPX/SPX-Compatible Transport protocol configuration property sheet if you do not know what frame type your NetWare servers are using. (In Windows 2000, Windows XP, and Windows .NET Server, select the check box next to Auto Frame

Type Detection in the NWLink IPX/SPX/NetBIOS-Compatible Transport protocol configuration property sheet.) You might also need to configure your routers for the proper frame type. Older Cisco routers running Internetwork Operating System (IOS) version 10 or earlier do not support Ethernet 802.3/802.2 with SNAP.

The table shows some troubleshooting tips for Ethernet media problems.

Troubleshooting Tips for Ethernet Media Problems

Problem	*Suggestion*
No link integrity	Check that you have not mismatched 10BaseT and 100BaseT (or 100BaseTX and 100BaseT4) cables, hubs, or network interface cards; that ensure no crossover cables are used for station-to-hub cable connections.
Too much noise	Check for damaged cables; ensure you are using Category 5 (Cat5) cabling (or enhanced Cat5 [Cat5e] cabling for 100BaseT) and that all your cabling interface components (patch panels, wall plates, terminal blocks, and so on) are Cat5 certified.
Too many collisions (greater than 0.1 percent of total frames on the network)	Check for unterminated cables using a time-domain reflectometer; use a protocol analyzer to look for a jabbering transceiver (a network interface card that is continually broadcasting); and ensure that cables exceed the maximum specified length.

For More Information

Visit Charles Spurgeon's Ethernet Web site at *www.ots.utexas.edu/ethernet.*

See Also: *10Base2, 10Base5, 10BaseF, 10BaseT, 10G Ethernet, 100BaseFX, 100BaseT, 100BaseT4, 100BaseTX, 1000BaseCX, 1000BaseLX, 1000BaseSX, 1000BaseT, Ethernet switch, Fast Ethernet, Gigabit Ethernet (GbE)*

Ethernet address

A unique 6-byte (48-bit) address that is usually permanently burned into a network interface card (NIC) or other physical-layer networking device and that uniquely identifies the device on an Ethernet-based network.

See: *MAC address*

Ethernet Industrial Protocol (Ethernet/IP)

A new standard that allows Ethernet and Transmission Control Protocol/Internet Protocol (TCP/IP) to be used for automation networks within industrial plants.

Overview

The Ethernet Industrial Protocol (Ethernet/IP) was developed by the Open DeviceNet Vendor Association, spearheaded by Rockwell Automation. Ethernet/IP is designed to allow commodity Ethernet equipment and TCP/IP software to be used for connecting industrial controllers and automation devices on factory floors. For example, using Ethernet/IP, a programmable logic controller and sensor can be used to remotely control an assembly-line robot tool using IP running over a switched Ethernet network. Other devices that might be used on an Ethernet/IP network include bar-code readers, automated weigh scales, stepping motors, and so on. More generally, Ethernet/IP can be used to tie in a company's industrial control network with its corporate business network, thus automating the exchange of information between inventory control systems and shipping systems for assembly-line processes.

Ethernet/IP is designed to replace an existing industrial controller network protocol called ControlNet, which was developed some years ago by Rockwell Automation and has found widespread acceptance in robotic and industrial environments.

Implementation

Ethernet/IP works by encapsulating messages from two industrial automation protocols, ControlNet and DeviceNet. Ethernet/IP employs the same application layer protocol as these two protocols, namely Control and Information Protocol (CIP). The CIP protocol runs on top of the network layer protocols TCP (used for explicit messaging between controllers and devices) and User Datagram Protocol (UDP) (used for implicit messaging). Ethernet/IP supports both real-time and asynchronous messaging as well as client/server and peer-to-peer messaging.

Ethernet/IP is usually implemented as a switched Ethernet fabric using full-duplex communications. This is necessary because the latency caused by contention in traditional Ethernet networks can have a detrimental effect on time-sensitive industrial assembly-line processes.

Advantages and Disadvantages

The advantage of Ethernet/IP over traditional automation networks is that cost savings can be achieved by running both the corporate network and the automation network using the same technology, namely Ethernet. Ethernet/IP allows control messages to be delivered across a plant floor using off-the-shelf Ethernet gear and without the need to develop custom Ethernet-to-ControlNet gateways. This helps industrial businesses leverage Ethernet's low cost, proven operation, and high bandwidth.

Special training in automation protocols is not required, and only one set of gear needs to be deployed and kept in stock.

Marketplace

Some of the bigger vendors that offer Ethernet/IP-enabled controllers and interfaces are Rockwell, MicroLogix Information Systems, and FLEX I/O.

For More Information

Visit the Open DeviceNet Vendor Association at *www.odva.org.*

See Also: *Ethernet*

Ethernet/IP

Stands for Ethernet Industrial Protocol, a new standard that allows Ethernet and Transmission Control Protocol/Internet Protocol (TCP/IP) to be used for automation networks within industrial plants.

See: *Ethernet Industrial Protocol (Ethernet/IP)*

Ethernet switch

A multiport device based on bridging technologies that is mainly used to segment Ethernet networks.

Overview

Often simply called switches (when referring implicitly to Ethernet networking), these devices are used to enhance the performance of Ethernet networks. An Ethernet switch basically resembles a hub, and consists of a box with a number of RJ-45 jacks on the front to provide ports for network connections. Inside, however, are advanced electronics that generally make switches more costly than hubs.

In a hub, a packet entering one port is regenerated and forwarded to every other port. While the packet is being forwarded, no other port can receive packets, so a hub can be thought of as a shared-media device in which all ports are connected using a shared bus. If a collision occurs on a hub-based Ethernet network, no port on the hub can receive traffic until the collision is resolved. The set of stations connected to a hub is thus called a collision domain. On the average, if a 10-megabits-per-second (Mbps) Ethernet hub has 10 ports, each port effectively gets one-tenth of the total bandwidth, or 1 Mbps. In reality this can be much worse, however, for a single station actively transferring files can consume a large percentage of the available 10 Mbps bandwidth of the hub, leaving other stations starved for bandwidth for their communications. Hub-based Ethernet networks are thus based on contention in which every station must fight for its share of bandwidth.

If you connect several hubs and their networks by uplinking them to a main hub, the situation only gets worse because the new larger network remains a single collision domain. With the increased number of nodes on the network, however, more collisions are likely to occur and network traffic congestion can result, slowing the network to a crawl.

The solution to this congestion problem is to strategically use Ethernet switches in place of, or in addition to, hubs. When a packet enters a port of an Ethernet switch, the switch looks at the frame's destination address, compares it to a table of address-to-port mappings maintained internally by the switch, internally establishes a temporary internal logical connection between the incoming port where the packet arrived and the outgoing port where the packet is destined, and forwards the packet along this internal connection to its destination. Only the port where the packet arrived and the destination port are involved in this process; all other ports on the switch have no part in the connection.

The result of this process is that each port on the switch corresponds to an individual collision domain, and network congestion is therefore avoided. Thus, if a 10-Mbps Ethernet switch has 10 ports, each port effectively gets the entire bandwidth of 10 Mbps, and to an incoming packet the switch's port appears to provide a dedicated connection to the destination node on the network.

In other words, replacing switches with hubs does not add bandwidth to your network. Instead, it reduces the size of collision domains to allow bandwidth to be used more efficiently. If 12 stations are connected to a 12-port 10 Mbps hub, the maximum bandwidth any one station can theoretically use is 10 Mbps, but if a station were actually using this much bandwidth, all remaining stations connected to the hub (except for the station being communicated with) would have zero bandwidth available to them. If a 12-port, 10 Mbps switch were used instead of the hub, however, all 12 stations could participate in 10 Mbps conversations simultaneously, which means the switching fabric supports 12 ports = 6 communications x 2 ports/communication = 6 x 10 Mbps = 60 Mbps throughput. However, the total bandwidth available to any one station is still only 10 Mbps, no more than for the hub. The difference is that this 10 Mbps bandwidth is guaranteed to be always available for each station!

Architecture

A basic Ethernet switch operates at Layer 2 (the data link layer) of the Open Systems Interconnection (OSI) model. Like a bridge, an Ethernet switch is a smart device that can learn the media access control (MAC) address of each connected station by listening to network traffic. The switch builds an internal table listing the MAC address of each port and consults this table when it needs to forward incoming packets.



Ethernet switch. *Comparison between how a hub and an Ethernet switch work.*

When an Ethernet frame arrives at a port, the destination MAC address is read from the first 64 bits of the frame. This destination address is then found in the switch's internal address table to determine the correct destination port for the frame. Once this is determined, the switching fabric (a mesh-like connection) inside the switch establishes a temporary logical connection between the incoming and destination ports, forwards the frame, and then tears down the connection. Ethernet switches are also capable of establishing multiple internal logical connections simultaneously between different pairs of ports. The result is that each port receives the switch's full dedicated bandwidth at all times, giving Ethernet switches intrinsically much more bandwidth than shared hubs.

The actual mechanism by which switching (the forwarding of the packet between the ports) occurs divides Ethernet switches into two general device classes:

- **Store-and-forward switches:** This type waits until the entire incoming frame arrives, buffers the frame, reads the destination address from the buffered frame, performs cyclical redundancy check (CRC) error checking to verify that the frame is valid, and either forwards the frame to the destination port using the switching fabric or drops the frame if it represents a runt, jabber, or some other invalid frame. Store-and-forward is the same method by which most bridges work. The advantages of this method are that bad frames are eliminated and collisions are handled well, while the disadvantage is that it suffers from high latency (delay) because the frame must be entirely read and buffered before being processed. Nevertheless, most switches used today are of the store-and-forward type, and Transmission Control Protocol/Internet Protocol (TCP/IP) is generally well able to handle any additional latency that arises in networks due to use of these switches.
- **Cut-through switches:** This type reads the frame as it comes into the receiving port, and after the source and destination addresses are read from the first 64 bits, the switch then checks the internal address table and immediately forwards the frame to the correct destination port. Error checking is not performed by cut-through switches, since to perform this check the CRC byte would have to be read first, and this is located at the end of the frame. As a result of not performing error checking, cut-through switches reduce latency and accelerate performance over store-and-forward switches, but the result is that collisions can affect overall communications and bad frames are passed rather than dropped. The earliest Ethernet switches were of the cut-through type and found particular application in NetWare 3.*x* networks where Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX) was less tolerant to delay than Internet Protocol (IP). Limitations in bridging electronics also made cut-through switching appealing in the earliest implementations, but advances in electronics have made store-and-forward switching more appealing. The first commercial Ethernet switches were cut-through switches developed in 1990 by Kalpana, which is now a subsidiary of Cisco Systems.

Implementation

Ethernet switching (or switched Ethernet) can be implemented in various ways depending on the OSI layers at which the switches operate. These include

- **Layer-2 switch:** This basic Ethernet switch operates at the OSI data-link layer (Layer 2) and is based on bridging technologies as explained above. Layer-2 switches establish logical connections between ports based on MAC addresses and are generally used for segmenting an existing network into smaller collision domains to improve performance.
- **Layer-3 switch:** This type operates at the OSI network layer (or Layer 3) and is based on routing technologies. Layer-3 switches establish logical connections between ports based on network addresses such as IP addresses. You can use Layer-3 switches instead of routers for connecting different networks into an internetwork, and they generally perform better than routers due to their enhanced electronics. Layer-3 switches are sometimes called routing switches, multilayer switches, or sometimes simply routers.
- **Layer-4 switch:** This is basically an enhanced Layer-3 switch that has the additional capability of examining the source and destination ports of Transmission Control Protocol (TCP) and User Datagram Protocol (UDP) connections and making forwarding decisions based on this information. They are called Layer-4 switches because they examine OSI transport layer (Layer 4) information within frames and determine how to forward the frames based on this information.

- **Layer-7 switch:** In this type of device the entire frame is unpackaged to determine OSI application layer (Layer 7) information such as what application layer protocol is being used, such as Hypertext Transfer Protocol (HTTP) or File Transfer Protocol (FTP). Frames can then be forwarded or dropped based on this information.
- **Multilayer switch:** This is simply a switch that uses unpackaged frame information from several OSI layers to determine how to forward frames. For example, most Layer-4 switches are actually Layer-3/4 switches since they operate at both layers.

Ethernet switches are also distinguished in other ways, such as by the number of ports they have, whether they operate in half-duplex or full-duplex mode, their transmission speed (for example, 10 Mbps, 1/100 Mbps, or 100/1000 Mbps), ports for connectivity with high-speed Fiber Distributed Data Interface (FDDI) backbones, and so on. Advanced features can include Simple Network Management Protocol (SNMP), out-of-band management (OBM), and custom packet filtering.

Uses

Ethernet switches have two basic uses: segmenting networks to improve performance and interconnecting networks of different speeds. The most common use is network segmentation, and introducing Ethernet switches will provide the most obvious benefit for parts of your network where the most contention occurs. For example, if you have several heavily used servers on the same hub-based local area network (LAN) as clients, the clients have to contend for use of the servers and the result is poor performance. To improve things, segment your LAN into several collision domains, one for each hub and one for each group of clients, as shown in the figure. Now several clients can connect to different servers simultaneously and receive the full throughput of those servers. A good rule of thumb for deciding whether to use switches to segment your existing network is that switches can improve your network's performance if the current network utilization level is higher than 35 percent or if collisions are running at more than 10 percent.



A hub-based LAN is a single collision domain, and clients have poor access to the servers.

Replacing the main hub with an Ethernet switch segments the network into four collision domains, and client access to servers is improved.

Ethernet switch. *Improving performance of a hub-based LAN by using an Ethernet switch.*

The second main use for switches is to connect fast workgroup hubs to slower hubs on a network. Again, the main hub is replaced by an Ethernet switch, typically 10/100 or 100/1000 Mbps, and the performance of stations on the fast hub is no longer hindered by the presence of the slower parts of the network. Another related use for Ethernet switches is to connect 100-Mbps Ethernet "islands" to an existing 10-Mbps Ethernet LAN. Simply use a 10/100-Mbps Ethernet switch with two ports to connect them. You can also connect two LANs several kilometers apart by using two Ethernet switches, both having one 100BaseT port and one 100BaseFX port. Connect the switches to the LANs, and then connect a fiber-optic cable between the FX ports.

If users in a department have high bandwidth needs, such as those running computer-aided design (CAD) or multimedia applications, consider replacing their workgroup hub with an Ethernet switch, or if the number of users is small, connect their stations directly to the main Ethernet switch.

When purchasing Ethernet switches, make sure they have Remote Monitoring (RMON) agents built into each port, which will considerably ease remote network troubleshooting.

Marketplace

Ethernet switches are made all shapes and sizes from dozens of different vendors. They vary from small 12-port 10/100 workgroup switches to modular 1 Gbps backbone switches supporting Asynchronous Transfer Mode (ATM) and Synchronous Optical Network (SONET) connectivity. Probably the most popular 10/100 Ethernet switches are those of the Cisco Catalyst 3500 Series XL, which by some counts are deployed twice as often as any other type of similar switch from other vendors. A popular enterprise switch used for collapsed backbones is the Big Iron 4000 switch from Foundry Networks. Another widely deployed backbone switch is the Hewlett-Packard 9304.

Issues

Although Ethernet switches relieve traffic congestion by segmenting collision domains, they do have some disadvantages:

- They are generally several times more expensive than hubs of the same speed.
- Networks involving switches are more difficult to monitor and troubleshoot.

Ethernet switches should generally be implemented judiciously within Ethernet networks. Simply replacing every hub with a switch is an unnecessary expense that brings negligible performance enhancement over just replacing a few key hubs with switches.

See Also: *Ethernet, hub*

ETRN

Stands for Extended Turn, an enhancement for Simple Mail Transfer Protocol (SMTP) to enable SMTP hosts to initiate mail transfers with one another.

See: *Extended Turn (ETRN)*

EULA

A type of contract between a computer software publisher and the purchaser of the software that outlines the various rights granted to the purchaser for the legal use of the software.

See: *End-User License Agreement (EULA)*

e-vaulting

Stands for electronic tape vaulting, the practice of backing up data directly to a remote backup facility.

See: *electronic tape vaulting*

event

Any operating system or software condition that is logged by the Event Logging service of Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Overview

You can view events by using the administrative tool called Event Viewer. There are five basic types of events:

- **Errors:** These events represent a significant problem that can lead to loss of data or functionality in the operating system, such as failure of a service to start upon reboot. The corresponding symbol in the system or application log is a red stop sign.
- **Warnings:** These events indicate some impending problem such as low remaining disk space. The

corresponding symbol in the system or application log is an exclamation point superimposed on a yellow circle.

- **Information:** These events indicate that a significant system operation has successfully occurred for example, a service has started. The corresponding symbol in the system or application log is an information sign—that is, the letter *i* superimposed on a blue circle.
- **Successes:** These events are recorded only in the security log and represent auditing information concerning the successful completion of attempts to access secured resources, such as when a user logs on to the network.
- **Failures:** These events are recorded only in the security log and represent auditing information concerning failed attempts to access secured resources, such as when a user attempts to access a shared folder and fails.

Everyone group

A system group existing on all Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server servers and workstations.

Overview

The Everyone group is one of seven (additional new groups exist on Windows XP and Windows .NET Server) built-in system groups that are defined on networks based on the Windows 2000, Windows XP, and Windows .NET Server operating system and includes all local and remote users. This includes users from distrusted domains and non-Windows networks. By default, the Everyone system group has the sole preassigned system right "Access this computer from network." You can grant additional rights to this group if desired. You cannot modify the membership of system groups such as the Everyone group directly.

Notes

When you share a folder on a server running Windows 2000 or Windows .NET Server, or on a workstation running Windows XP, full control permission is initially assigned to the Everyone group. It is advisable to remove this group and assign appropriate permissions to other groups, such as Administrators and Users.

Be careful about assigning additional permissions to the Everyone group. If you allow users who do not have valid user accounts to access the network using the Guest account, they will gain any permissions and rights assigned to the Everyone group.

See Also: *built-in group, special identity*

Exchange Server

Microsoft Exchange Server 2000 is Microsoft Corporation's premier messaging and collaboration solutions-building platform for Windows 2000. Exchange 2000 is part of the Microsoft BackOffice suite of server applications. Exchange Server is designed for mission-critical enterprise-level messaging solutions and includes such features as

- Intelligent message rerouting
- Transaction-based directory services
- Fault-tolerant message store
- Built-in server and link monitoring tools
- Connectors and gateways for connectivity with foreign mail systems

Exchange 2000 can coexist with most popular and legacy mail systems and can be used for messaging connectivity with the following:

- Microsoft Mail
- Internet mail (Simple Mail Transfer Protocol [SMTP])
- X.400
- Lotus cc:Mail
- IBM PROFS and SNADS

Exchange 2000 supports all key industry messaging standards, including:

- Internet messaging standards such as SMTP, Post Office Protocol 3 (POP3), Internet Message Access Protocol 4 (IMAP4), Lightweight Directory Access

Protocol (LDAP), Hypertext Transfer Protocol (HTTP), Network News Transfer Protocol (NNTP), Secure Sockets Layers (SSL), Multipurpose Internet Mail Extensions (MIME), and Secure/Multipurpose Internet Mail Extensions (S/MIME)

- X.400 messaging standards
- Microsoft's Messaging Application Programming Interface (MAPI)

The Microsoft Outlook 2000 client software, part of the Microsoft Office 2000 suite of business productivity tools, complements Exchange Server by providing users with a full desktop information-management tool for managing messages, appointments, tasks, and contacts. Although the preferred client for Exchange 2000 is Outlook 2000, Exchange clients are available for all the popular operating systems, including MS-DOS, Windows 3.*x*, Windows 95, Windows 98, Windows NT, Windows 2000, Apple Macintosh, UNIX, and OS/2. Note that the features supported by different clients vary with the platform used.

History

Exchange 4 replaced Microsoft Mail 3.51 in 1996 as Microsoft's client/server messaging and collaboration system. Exchange 4 employed an X.500-based directory and natively supported the SMTP, MIME, MAPI, and X.400 messaging standards, with X.400 being the underlying message transport protocol. In 1997, Exchange 5 was released, which supported additional Internet standards such as POP3 for mailbox access, NNTP for Usenet newsgroups, LDAP for X.500 directory access, HTTP and HTML for Web browser access, and SSL for secure authentication and encryption. Later in 1997 Exchange Server 5.5 added support for Microsoft Cluster Server, IMAP4 and S/MIME protocols, Key Management services, Virtual Organizations, and unlimited message store size.

Exchange 2000 was a radical departure from early versions because it eliminated the proprietary Exchange directory and instead tightly integrated Exchange with Windows 2000's Active Directory directory service. Exchange 2000 includes the Web Storage System, which provides a hierarchical data storage mechanism that incorporates Extensible Markup Language (XML) as part of its specification. Exchange 2000 also tightly integrates with Internet Information Services (IIS), Microsoft's Web services platform and uses IIS as its Internet messaging protocol handler. Exchange 2000 is available in several editions and can be deployed in various ways, including as a messaging system for small companies, a platform for building collaborative workflow applications for large enterprises, Internet mail servers for Internet service providers (ISPs), and hosted messaging and collaboration services offered by Application Service Providers (ASPs).

For More Information

Find our more about Exchange 2000 at *www.microsoft.com/exchange.*

See Also: *BackOffice, e-mail*

experience

A modern term used to describe applications that have an interface designed for the user.

Overview

The term *experience* has recently come into common use in programming parlance to describe any application that has a customizable user interface. Developers who work on client software are thus "developing experiences" for the users of their software.

The term *experience* is also used in the discussion of Microsoft Corporation's .NET platform to mean the delivery of integrated functionality to users through Web services. The .NET platform is designed to allow developers to build compelling user experiences that will provide sets of targeted functionality to bring about the next phase of the Internet's evolution. Some of the pieces already in place to provide this experience include

- bCentral, a resource for small businesses
- MSN (the Microsoft Network), targeted for consumers
- Microsoft Office, aimed at knowledge works
- Visual Studio.NET, targeted for developers

Notes

The term *user experience* is also commonly used to describe the visual appearance and interactivity of software for the Apple Macintosh platform, particularly Aqua in Mac OS X.

See Also: *.NET platform*

extended partition

A physical disk partition on which a series of logical drives can be created.

Overview

You can create an extended partition on a disk to overcome the limitation of having only four partitions per disk. Information about the various partitions on a disk is stored in a structure called the partition table. The partition table is 64 bytes in size and is located on cylinder 0, head 0, sector 1 of your hard drive, in the same sector as the Master Boot Record. The partition table has the same format no matter what operating system is used on the disk. Up to four partitions can be created on a disk, but only one partition can be extended per disk. In Microsoft Windows 2000, Windows XP, and Windows .NET Server, you can create an extended partition using Disk Management console. For earlier Windows platforms, use the fdisk utility.

Notes

In Windows 2000 and Windows XP, and Windows .NET Server, extended partitions can be created only on basic disks.

See Also: *partition (disk)*

Extended Turn (ETRN)

An enhancement for Simple Mail Transfer Protocol (SMTP) to enable SMTP hosts to initiate mail transfers with one another.

Overview

SMTP hosts were originally envisioned as machines that always had to be connected to the Internet using dedicated connections such as leased lines. In this scenario, when a host must send mail to another host on the Internet, it simply does so, assuming the other host is there and is listening to receive any mail forwarded to it. With the advent of companies wanting to connect their SMTP hosts to the Internet using dial-up connections to save money over leased lines, some mechanism had to be developed to allow a host to tell other hosts that it was online and ready to receive mail. Extended Turn (ETRN) was developed for this purpose. For example, a company may configure its SMTP host to dial up to the company's Internet service provider (ISP) and issue an ERTN command to the ISP's remote host to deliver mail queued on the remote host.

Issues

ERTN is a stopgap solution that was added to SMTP to work around the problem described above. ERTN has several disadvantages, including its complexity to configure and its requirement for a permanent Internet Protocol (IP) address for the dial-up server. A much better solution for downloading corporate mail from an ISP's SMTP host is to use a Post Office Protocol 3 (POP3) server instead.

See Also: *Post Office Protocol version 3 (POP3), Simple Mail Transfer Protocol (SMTP)*

extender

A general name for a class of networking devices that extend the distances over which stations (computers) can typically be connected to concentrators such as hubs and switches.

Overview

An example of an extender is a 10BaseT extender for Ethernet networks. In 10BaseT networks, stations should be located no more than 328 feet (100 meters) from a hub, but by using an extender, you can increase this to about 600 feet (183 meters). A 10BaseT extender can thus be used for connecting a remote station, such as a station located in a nearby building, to the network. Extenders are essentially a simplified form of bridge designed to support only a few remote stations. They must be installed in pairs, one at the remote location and one at the main network. Some extenders can be used to carry network data over installed phone lines, connecting remote stations without installing additional network cabling.



Extender. *Using an extender to join a remote station to a local area network (LAN).*

Extenders are also available for increasing the maximum connection distance for other data transmission technologies such as the Small Computer System Interface (SCSI) bus. A normal SCSI bus is limited to about 20 feet (6 meters), but a fiber-optic SCSI extender can increase this distance to 0.6 mile (1 kilometer) or more using duplex fiber-optic cable. You can use parallel extenders for directly connecting to printers located in a different building. You can use serial extenders to connect computers to remote RS-232 serial test equipment located in laboratories in different buildings.

Extensible Authentication Protocol (EAP)

A security enhancement of Point-to-Point Protocol (PPP).

Overview

Extensible Authentication Protocol (EAP) is an extension to PPP specified in RFC 2284. EAP allows for an arbitrary authentication method to be negotiated during initialization of a PPP session. This is accomplished during the Link Control Protocol (LCP) negotiation portion of the PPP session establishment sequence. EAP allows third-party security products to be used to provide additional security to PPP sessions using special application programming interfaces (APIs) built into operating systems whose implementation of PPP supports EAP.

EAP is designed to make remote access and virtual private network (VPN) communications more secure by allowing any kind of authentication to be used, including

- Smart cards such as Fortezza, SecurID, and other token technologies.
- MD5-CHAP, which provides 128-bit encryption during authentication.
- Kerberos authentication, the standard authentication method for Windows 2000, Windows XP, and Windows .NET Server.
- Transport Layer Security (TLS), which is implemented in Web browsers, smart cards, biometric authentication devices, and so on.

In Microsoft Windows 2000 and Windows .NET Server, EAP is supported by both the Routing and Remote Access Service (RRAS) and Internet Security and Acceleration (IAS) services and by dial-up networking (DUN). Each type of EAP authentication method allowed is implemented through specific plug-in modules designated dynamic-link libraries (DLLs) on both the client and the server. So if you purchase a smart card system from a vendor for use with Windows 2000 or Windows .NET Server remote access, you run the vendor's Setup program on both your DUN client and Remote Access Service (RAS) server to install the necessary EAP DLLs.

See Also: *Point-to-Point Protocol (PPP)*

Extensible Firmware Interface (EFI)

A new firmware standard for 64-bit Intel processors.

Overview

Extensible Firmware Interface (EFI) is a new standard for the firmware that is used to boot PCs using Intel Corporation's new 64-bit Itanium processor family. EFI is required for all Itanium-based systems that will run

Microsoft's new 64-bit Windows platform because these systems cannot boot using the basic input/output system (BIOS) or System Abstraction Layer (SAL) alone. EFI will be supported in all 64-bit versions of Microsoft Windows.

For More Information

See *www.microsoft.com/hwdev/EFI.*

See Also: *64-bit architecture, 64-bit Windows*

Extensible Markup Language (XML)

A meta-language used as a universal standard for electronic data exchange.

See: *XML*

extension cable

A cable used to extend a length of cabling.

Overview

Extension cables are available in all types with various connector devices and can be used to extend serial lines, parallel lines, network cables, power cables, and other cords.

Extending a cable using an extension cable is not always a good idea because the additional interface introduced by the connection usually results in some signal loss. Furthermore, extending network cables can cause problems if the new, longer cable exceeds the maximum length of the specifications for that type of network. For example, extending unshielded twisted-pair (UTP) cabling beyond 328 feet (100 meters) in a 10BaseT Ethernet network can result in unreliable communication between hosts on the network.

Exterior Border Gateway Protocol (EBGP)

The version of Border Gateway Protocol (BGP) used for exchanging routing information between different autonomous systems.

Overview

There are two versions of BGP, the classless dynamic routing protocol used on the Internet. These versions are

- **Exterior Border Gateway Protocol (EBGP):** This is an exterior routing protocol that is used for exchanging routing information dynamically between border routers connecting autonomous systems (ASs) on the Internet or in a large private Transmission Control Protocol/Internet Protocol (TCP/IP) internetwork. When referring simply to BGP, the variant EBGP is always implied. In other words, EBGP is usually just called BGP.
- **Interior Border Gateway Protocol (IBGP):** This is an interior routing protocol that is used for exchanging routing information between routers within an AS.

See Also: *autonomous system (AS), Border Gateway Protocol (BGP), classless routing protocol, dynamic routing*

exterior gateway protocol (EGP)

Any routing protocol used to distribute routing information between autonomous systems.

Overview

Also known as exterior routing protocols, exterior gateway protocols (EGPs) specify how different autonomous systems (ASs) within large Transmission Control Protocol/Internet Protocol (TCP/IP) internetworks such as the Internet communicate with each other to exchange routing information. EGPs facilitate the exchange of inter-autonomous-system routing information between different autonomous systems, independent of which interior gateway protocols (IGPs) are used within these autonomous systems.

There are two EGPs for IP internetworks:

- **Exterior Gateway Protocol (EGP):** This is the original EGP developed in the early days of the Internet to facilitate the Internet's growth. Note the confusing use of the term *Exterior Gateway Protocol (EGP)* here—EGP stands both for the general category of inter-AS routing protocols and also for the first actual protocol developed within this category. In other words, EGP is one of two examples of an EGP! For more information, see the second article titled "Exterior Gateway Protocol (EGP)," which is the next entry in this chapter.

- **Border Gateway Protocol (BGP):** This is a newer EGP that has replaced the Exterior Gateway Protocol for inter-AS communication on the Internet.

See Also: *autonomous system (AS), Border Gateway Protocol (BGP), dynamic routing, Exterior Gateway Protocol (EGP), interior gateway protocol (IGP), Internet, routing protocol*

Exterior Gateway Protocol (EGP)

The original exterior routing protocol used to connect autonomous systems on the Internet.

Overview

Exterior Gateway Protocol (EGP) was the original interdomain routing protocol developed for communicating routing information between autonomous systems on the Internet. In fact, the idea of autonomous systems was developed in conjunction with EGP.

EGP was developed in 1982 for the ARPANET, the precursor to the Internet, and was conceived at a time when the Internet was envisioned as a single core network to which various other networks were connected. The developers of the Internet saw early on that scaling problems would occur as the Internet grew in size and complexity, and so the idea of apportioning the Internet into separate sections called autonomous systems (ASs), each under someone else's authority, was developed. Large private internetworks connected to the Internet were assigned autonomous system numbers (ASNs), and the core network itself was divided into several ASs.

To facilitate exchange of routing information between routers connecting these different networks, the concept of dynamic routing was introduced and two kinds of dynamic routing protocols were developed:

- **Interior gateway protocols (IGPs):** These are used for routing within an AS and are thus intra-AS routing protocols. IGPs allow the routers within an AS to exchange routing table information with each other dynamically. Examples of IGPs include Routing Information Protocol (RIP) and Open Shortest Path First (OSPF).
- **Exterior gateway protocols (EGPs).** These are used for routing between different ASs and are thus inter-AS or interdomain routing protocols. EGPs allow routers on the borders between different ASs to exchange routing table information with each dynamically. Examples of EGPs include Exterior Routing Protocol (EGP), from which the more general category EGP was later derived, and Border Gateway Protocol (BGP), the EGP commonly in use on the Internet today.

Implementation

Exterior Gateway Protocol, as defined in RFC 904, is based on the distance vector routing algorithm, but has the limitation that it only maintains information about a single route between two different ASs. EGP thus assumes that only a single path exists between any two ASs within the Internet, a condition that was seen early on as unrealistic. EGP also does not indicate the cost of the route between two ASs, only whether the route is reachable or unreachable. Furthermore, EGP supported only classless routing, and when it was implemented it was already obvious that the class A/B/C system of allocating Internet addresses would soon exhaust available addresses. As the Internet grew it became more complex in its structure as multipath connections between ASs began to develop. EGP's weakness was quickly realized and BGP was developed to replace it. BGP also supports Classless Interdomain Routing (CIDR), which superseded the Internet's earlier classful routing system.

Today EGP is considered a legacy routing protocol and is no longer used on the public Internet, although it is probably still used in some large private Internet Protocol (IP) internetworks that have seen no real need for upgrading to BGP. Interestingly enough, as of 2001 EGP was still being used for MILNET, the public portion of the U.S. Defense Data Network.

See Also: *autonomous system (AS), autonomous system number (ASN), Border Gateway Protocol (BGP), classless interdomain routing (CIDR), dynamic routing protocol, Exterior Gateway Protocol (EGP), interior gateway protocol (IGP), Internet, Open Shortest Path First (OSPF), Routing Information Protocol (RIP), routing protocol*

exterior routing protocol

Another name for an Exterior Gateway Protocol (EGP), any routing protocol used to distribute routing information between autonomous systems.

See: *Exterior Gateway Protocol (EGP)*

extranet

A private Transmission Control Protocol/Internet Protocol (TCP/IP) network that securely shares information using Hypertext Transfer Protocol (HTTP) and other Internet protocols with business partners.

Overview

An extranet is basically a corporate intranet that is securely exposed over the Internet to specific groups that need access to it. Extranets are powerful tools because they let businesses share resources on their private networks over the Internet with suppliers, vendors, business partners, and wholesale customers. Extranets are typically used for supporting real-time supply chains, for enabling business partners to work together, and to share information such as catalogs with customers. Extranets basically comprise the B2B (business-to-business) portion of an e-business system, and building an extranet is an essential step for companies who want to compete in today’s Internet economy.

Implementation

Extranets built on the corporate intranet model follow the client/server paradigm, with Web servers such as Microsoft Internet Information Services (IIS) functioning as the server, and Web browsers such as Microsoft Internet Explorer functioning as the client. Other extranet models exist, however, such as a peer-to-peer business connection for electronic data interchange (EDI). Peer-to-peer extranets between business partners typically use virtual private networks (VPNs) to establish secure, encrypted communication over the unsecured Internet for the transmission of sensitive business information, such as EDI between partners, or between headquarters and branch offices. These extranets act as dedicated gateways between business partners and generally do not allow private access to individual users. Peer-to-peer extranets can use Internet Protocol Security (IPsec) with a public key infrastructure (PKI) to provide IP-based authentication and encrypted transmission of information.

Client/server extranets have different requirements, however, because individual users must be authenticated before receiving secure, encrypted access to company resources. Instead of authenticating on the basis of IP addresses as in peer-to-peer extranets, users must be authenticated using user accounts or digital certificates mapped to accounts. Client/server extranets might support HTTP access only or might allow other client/server applications to run. Encryption for HTTP access is performed using the Secure Sockets Layer (SSL) protocol.

Although a basic extranet can be built easily by scripting a Web server to run as a front end for a corporate database, real-world extranets are often more complex. The difficult part is to build the extranet back into the back-end database systems and other sources of business information that business partners need to access. Virtual Private Network (VPN) and firewall technologies are commonly used to provide secure access between different partners over the Internet, and Extensible Markup Language (XML) is emerging as an essential tool for structuring business information for exchange between partners. Extranets also often need to be coupled with directory services for managing access to information through policy-based mechanisms.

Advantages and Disadvantages

The power of the extranet is that it leverages the Internet's existing technology to increase the power, flexibility, and competitiveness of businesses using well-known and easily used tools such as Web servers and Web browsers. Extranets also save companies money by allowing them to establish business-to-business connectivity over the Internet instead of using expensive dedicated leased lines. Extranets can also save money by reducing phone and fax costs.

Marketplace

A new breed of policy-based access management tools has emerged for providing the infrastructure needed to build large directory-enabled extranets. Two popular products in this arena are GetAccess from enCommerce and SiteMinder from Netegrity. The Microsoft BizTalk framework and its associated server platform is seen as a key player in the emerging XML-ization of business extranets and other B2B services.

See Also: *electronic data interchange (EDI)*

failback

In clustering technology, the action of moving resources back to a failed node or primary node (a computer in a cluster) once it has been recovered. This action can take place manually or automatically depending on how the cluster is configured.

Overview

Suppose you have a cluster that has two nodes, each containing different resources. If Node A experiences failure, failover occurs and the workload of Node A (its set of resources) is transferred to Node B. When Node A reboots, it checks with Node B to see which resources are running on Node B and discovers that some of these cluster groups would "prefer" to reside on Node A. At this point failback will occur if the cluster is configured to failback automatically if the primary node recovers. The preferred groups are then moved from Node B back to Node A. Failback might be configured to occur immediately or at a scheduled time if access to resources is low.

Notes

Failback is sometimes known as "rebalancing the workload."

See Also: *clustering, failover*

failover

Any technology that allows one device to take over for a similar device that has failed.

Overview

An example of a typical failover system would be a failover cluster. Failover is also often used to ensure that a break in a communication line does not cause a break in communication between networked systems.



Failover. *How failover works.*

Suppose you have a cluster that has two nodes, each containing different resources. If Node B experiences failure, failover occurs and the workload of Node B (its set of resources) is transferred to Node A. In Microsoft Corporation's clustering services (Microsoft Cluster Server for Microsoft Windows NT 4 Enterprise Edition and the Cluster service for Windows 2000 Enterprise Server and Datacenter Server and Windows .NET Server Enterprise Server and Datacenter Server), the cluster resources (network applications, data files, and other tools installed on the nodes of the cluster) provide services to clients on the network. A resource can be hosted on only one node at any given time, but by using the Cluster Administrator program, you can configure the resource to failover to the second node if the first node fails. This causes the resource and its operation to move from one node to the other if a failure of one node occurs.

Failover is initiated automatically by the Cluster service when a failure is detected on one of the nodes. This process can take up to 10 seconds to initiate. Failover is transparent to the users if they are accessing cluster resources using stateless protocols such as Hypertext Transfer Protocol (HTTP) and does not require any special client software to be installed on users' machines. If a client is connected using a tool such as Windows Explorer, it will be notified that the connection is unavailable. The user should abort, retry, or cancel the connection attempt. (To connect to the resource on the failover node, retry the connection attempt.) For other Cluster service applications, users might have to log on again to the resource.

Notes

Microsoft's clustering services support failover at the level of virtual servers, which means items such as Web sites, print queues, file shares, and applications can be protected from system failure.

See Also: *clustering*

fallback switch

A class of switches used to provide failover support for critical network communication lines.

Overview

Fallback switches are an essential component of a fault-tolerant network system with resources that must have a high availability. In such a scenario, resources can be connected to your network using two circuits:

- A primary line that normally provides access to the resource
- A secondary line to which the fallback switch reroutes the moment the primary line fails



Fallback switch. *Using a fallback switch.*

Uses

Fallback switches can also be used to provide fault tolerance for a high-speed backbone for Fast Ethernet, Fiber Distributed Data Interface (FDDI), or Asynchronous Transfer Mode (ATM) networking. For example, you can use fallback switches to run two multimode fiber-optic cables between a pair of Ethernet switches, instead of having only one cable connecting them. If one fiber-optic cable goes dark, the fallback switch immediately detects the problem and switches over to the backup cable.

Fallback switches that can be managed using Simple Network Management Protocol (SNMP) management consoles are very useful. For example, you could use a remote SNMP terminal to cause a fallback switch to change from a primary to a secondary line if you need to take the primary line down for maintenance. Ganged fallback switches can be used to control multiple serial or local area network (LAN) devices simultaneously. For example, you could schedule a ganged switch to switch over from a set of primary Web servers to a backup Web server every night during a period of low traffic while maintenance or backups are performed on the primary servers. Be sure to use a fallback switch with some form of password protection on its SNMP management functions.

Examples

An example of a resource requiring high availability is a high-speed T1 line that is used by remote clients for accessing a corporate intranet. If the primary T1 line goes down, there must be a backup line that provides instant, transparent failover support for clients. The solution is to use two T1 lines connected to a fallback switch by a serial interface such as RS-232 or V.35. The fallback switch detects a failure the moment the primary line goes down and can perform a remedial action such as

- Automatically switching over to the backup line
- Sounding an audible alarm to notify administrators
- Generating an alert to an SNMP management console

FAQ

Stands for frequently asked questions, a list of commonly asked questions and their answers.

See: *frequently asked questions (FAQ)*

Fast Ethernet

A set of Ethernet standards for 100-megabit-per-second (Mbps) data transmission.

Overview

Ratified as the IEEE 802.3u specification in 1995, Fast Ethernet is an evolution of regular 10 Mbps Ethernet that transmits data at 10 times the speed of standard Ethernet. Fast Ethernet uses the same contention-based media access control method (Carrier Sense Multiple Access with Collision Detection, or CSMA/CD) and the same framing format as standard Ethernet. It also runs over the same structured wiring systems as well, including twisted pair and fiber-optic cabling, with the exception that there is no shared media (physical bus) cabling option as in 10Base2 and 10Base5 Ethernet.

Fast Ethernet is actually a group of standards collectively known as 100BaseT. Like the various 10 Mbps forms of Ethernet, Fast Ethernet also comes in full- and half-duplex varieties and can be implemented as shared media using hubs or in switched networks.

Uses

Fast Ethernet is used mainly for switch uplinks and interconnects for high-speed backbones, switch connections to high-speed servers in server farms, and islands of high-performance workstations running bandwidth-intensive software such as computer-aided design (CAD) or multimedia applications.

Fast Ethernet switches can also be used for segmenting your network to reduce bottlenecks caused by users trying to access key servers on the network. Simply connect each 10/100 autosensing hub to a Fast Ethernet switch, and connect the servers directly to the switch.

Architecture

Fast Ethernet increases its speed tenfold over standard Ethernet by decreasing the bit time (the time duration of each transmitted bit) by a factor of 10. This allows Fast Ethernet to maintain all of the main characteristics of 10 Mbps Ethernet and be compatible with 10 Mbps Ethernet to allow mixed networks of 10 and 100 Mbps segments to coexist. The Fast Ethernet specifications also include a mechanism for autonegotiation of frame speed called autosensing, which lets vendors build dual 10/100-Mbps hubs, switches, and bridges for easily incorporating Fast Ethernet into legacy 10 Mbps Ethernet networks.

Implementation

Fast Ethernet can be implemented in four different media (cabling) formats, which are collected under the umbrella designation of 100BaseT. These four formats are

- **100BaseTX:** This is the most popular implementation of Fast Ethernet. 100BaseTX uses two pairs of wires in Category 5 (Cat5) unshielded twisted-pair (UTP) cabling (the same cabling as the popular but lower-speed 10BaseT variety of Ethernet). 100BaseTX also supports w-pair shielded twisted-pair (STP) cabling as well, but this is rarely used and is available in both half-duplex and full-duplex signaling.
- **100BaseFX:** This form can use duplex (two-strand) 50 or 62.5 micron multimode fiber-optic cable or 9 micron single mode cabling, typically terminated with ST connectors. It is used mainly for backbone wiring such as switch-switch connections and is available in both half-duplex and full-duplex signaling.
- **100BaseT4:** This form uses all four pairs of wires in twisted-pair cabling and enables Fast Ethernet to be used over inexpensive Category 3 (Cat3) UTP cabling. 100BaseT4 supports half-duplex signaling only.
- **100BaseT2:** This form uses two pairs of wires in either Cat3, Category 4 (Cat4), or Cat5 UTP cabling and supports both half- and full-duplex signaling. This option was developed by the Institute of Electrical and Electronics Engineers (IEEE) but was never implemented in commercial Fast Ethernet equipment.



Fast Ethernet. *Fast Ethernet island connected to legacy 10BaseT network.*

Repeaters (hubs) for Fast Ethernet networks come in two varieties:

- **Class I repeaters:** Perform internal signal translation that introduces slight propagation delays but allows different types of Fast Ethernet media, such as 100BaseTX and 100BaseFX, to be connected. You can use only one Class I repeater per Fast Ethernet segment.
- **Class II repeaters:** Take incoming signals and repeat them immediately (without translation) to all outgoing ports, thus minimizing port latency. Class II repeaters require that all ports connect to the same media, such as 100BaseTX. You can use up to two Class II repeaters per Fast Ethernet segment.

For 100BaseTX, attached stations cannot be more than 328 feet (100 meters) from a hub or repeater (same as 10BaseT) with the maximum network diameter being 690 feet (210 meters), compared to 1640 feet (500 meters) for 10BaseT. 100BaseFX supports longer distances up to 1.25 miles (2 kilometers). In reality, building Fast Ethernet networks is a trifle more complex because the distance limitations of different media options often depend on the class of repeaters used and whether station-hub or hub-hub connections are under consideration.

There are also nonstandard vendor-specific external transceivers available that allow Fast Ethernet to be extended over long-haul multimode fiber for distances as long as 62 miles (100 kilometers).

Advantages and Disadvantages

Switching to Fast Ethernet is probably the easiest and cheapest way of upgrading your network to meet increasing bandwidth needs. The advantages of upgrading 10 Mbps Ethernet networks to Fast Ethernet include the following:

- Fast Ethernet integrates easily into existing 10 Mbps Ethernet networks without requiring reinvestment in new network-management and troubleshooting software.
- Fast Ethernet is based on the same simple technology as standard 10 Mbps Ethernet, which makes equipment cheap and easy to produce and reduces the amount of training needed to implement it.
- Fast Ethernet can carry voice, data, and video at 100 Mbps, which is 10 times faster than traditional 10 Mbps Ethernet.
- Fast Ethernet can operate over the same installed media used for a traditional 10 Mbps Ethernet network.
- The network can be migrated slowly to Fast Ethernet by using autosensing 10/100 hubs and network interface cards (NICs).

These advantages have made Fast Ethernet the natural successor to standard 10 Mbps Ethernet and have led to the eclipse of competing high-speed networking technologies such as Fast Token Ring and Fiber Distributed Data Interface (FDDI).

Marketplace

The list of vendors offering Fast Ethernet equipment is too long to mention here. One example of the technology's popularity is that every version of Cisco Catalyst switch available supports Fast Ethernet.

Analysts estimate that more than 100 million Fast Ethernet ports were shipped in 2000, a figure that is expected to double by 2004. Price per port has dropped to below $100, making Fast Ethernet an attractive and affordable option for small and mid-sized businesses that need to upgrade their networks. Despite the current market excitement over Gigabit Ethernet (GbE) and the predicted arrival of 10 GbE, Fast Ethernet is likely to remain the primary networking technology for corporate networks for at least the next five years.

Notes

An alternative to Fast Ethernet developed by Hewlett-Packard is 100VG-AnyLAN, also called 100BaseVG and standardized as IEEE 802.12. 100VG-AnyLAN is a 100 Mbps transmission technology that uses a media access control technology called demand priority that Hewlett-Packard originally developed for transporting both Ethernet and Token Ring frames. 100VG-AnyLAN is now considered a legacy technology compared to Fast Ethernet.

See Also: *100BaseFX, 100BaseT4, 100BaseTX, 100VG-AnyLAN, Ethernet, Gigabit Ethernet (GbE)*

FAT

Stands for file allocation table; specifically, a table maintained on a hard disk by MS-DOS and Microsoft Windows operating systems that acts as a table of contents, showing where directories and files are stored on the disk. By extension, the acronym FAT is also used to refer to the file system itself for MS-DOS and Windows platforms.

See: *file allocation table (FAT)*

FAT32

An enhanced version of a file allocation table (FAT), supported by Microsoft Windows 95 OSR2, Windows 98, Windows Millennium Edition (Me), Windows 2000, Windows XP, and Windows .NET Server.

Overview

FAT32 theoretically supports drives of up to 2 terabytes (2048 gigabytes [GB]) in size, although for Windows 2000, Windows XP, and Windows .NET Server the actual size limit is 32 GB. If the installation partition is smaller than 2 GB, it will automatically be formatted using FAT. If the installation partition size is equal to or greater than 2 GB, it will automatically be formatted as FAT32.

FAT32 uses a smaller cluster size than FAT so is more efficient at utilizing disk space on large volumes (those greater than 512 megabytes [MB] in size) than FAT. The savings in disk space using FAT32 instead of FAT for large volumes is typically 20 to 30 percent. The following two tables show the difference in cluster sizes between the original FAT and FAT32.

FAT Cluster Sizes

Drive Size	*FAT Cluster Size*
0 MB–32 MB	512 bytes
33 MB–64 MB	1 kilobyte (KB)
65 MB–128 MB	2 KB
129 MB–256 MB	4 KB
257 MB–512 MB	8 KB
513 MB–1024 MB	16 KB
1025 MB–2048 MB	32 KB

FAT32 Cluster Sizes

Drive Size	*FAT32 Cluster Size*
260 MB–8 GB	4 KB
9 GB–16 GB	8 KB
17 GB–32 GB	16 KB
More than 32 GB	32 KB

Notes

Using FAT32 (or FAT) with the Windows 2000, Windows XP, and Windows .NET Server operating system platforms is not recommended because it does not offer the security features that are provided by the NTFS file system (NTFS). FAT32 also does not support disk compression. The only time you'd use FAT32 with Windows 2000, Windows XP, or Windows .NET Server is in a dual-boot situation, which Microsoft Corporation does not recommend. Note that in a dual-boot system, FAT32 volumes cannot be accessed by any operating systems other than Windows 95 OSR2, Windows 98, Windows 2000, Windows XP, or Windows .NET Server. For dual-boot with Windows 95, Windows 98, or Windows NT, drive C must be a FAT partition.

Remember, a client that connects over the network to a shared folder in Windows 2000, Windows XP, or Windows .NET Server can access files in that folder regardless of whether the folder is stored on an NTFS, FAT, or FAT32 volume—provided the client has the appropriate permissions to do so.

See Also: *file allocation table (FAT), NTFS file system (NTFS)*

FAT volume

A partition on a physical disk formatted using the file allocation table (FAT) file system.

Overview

FAT volumes can be used to share folders for users to access over the network, but they lack the advanced security control and auditing features of NTFS file system (NTFS) volumes. The maximum file partition size is 4 gigabytes (GB) in Microsoft Windows NT and 2 GB in MS-DOS, Windows 3.*x*, Windows 95, and Windows 98. Windows 2000, Windows XP, and Windows .NET Server will actually format a partition as FAT32 if the partition is larger than 2 GB.

Notes

Be sure to regularly defragment heavily used FAT volumes because the FAT file system can easily become fragmented when files are deleted and created. Use FAT volumes instead of NTFS volumes when you want to dual-boot Windows NT, Windows 2000, Windows XP, or Windows .NET Server systems with earlier MS-DOS, Windows 3.*x*, Windows 95, or Windows 98 systems.

See Also: *file allocation table (FAT), NTFS file system (NTFS)*

fault tolerance

Any mechanism or technology that allows a computer or operating system to recover from a failure.

Overview

In fault-tolerant systems, the data remains available when one component of the system fails. Here are some examples of fault-tolerant systems:

- Transactional log files that protect the Microsoft Windows registry and allow recovery of hives
- Redundant array of independent disks (RAID)-5 disk systems that protect against data loss
- Uninterruptible power supply (UPS) to protect the system against primary power failure

Notes

Just because your system is fault tolerant does not mean you are fully prepared for disaster. You still need to perform regular backups of important data. For example, a RAID-5 disk system will protect against data loss if one disk drive fails, but not if two or more drives fail simultaneously.

See Also: *disaster recovery, redundant array of independent disks (RAID)*

FCC

Stands for Federal Communications Commission, a U.S. government agency regulating all aspects of telecommunications.

See: *Federal Communications Commission (FCC)*

FDDI

Stands for Fiber Distributed Data Interface, a high-speed network technology used mainly for campus backbones.

See: *Fiber Distributed Data Interface (FDDI)*

FDDI token passing

The token-passing access method for Fiber Distributed Data Interface (FDDI) networking.

Overview

The token-passing method used by FDDI is generally similar to the token-passing definition outlined in the IEEE 802.5 specification for Token Ring networks. However, in an FDDI ring, each host holds the token for a predetermined amount of time and can transmit as many frames as it can produce during this time. When the time interval expires, the host must release the token for the next host on the ring to use. This differs from the IEEE 802.5 specification in that many frames from each host can exist on the ring at the same time, instead of only one frame per host, as is the case in Token Ring networks. This allows FDDI networks to support higher data traffic rates than Token Ring networks and makes FDDI more suitable for network backbones.

See Also: *Fiber Distributed Data Interface (FDDI), Token Ring*

FDM

Stands for frequency-division multiplexing, a signal transmission technology in which multiple signals can simultaneously be transmitted over the same line or channel.

See: *frequency-division multiplexing (FDM)*

FDMA

Stands for Frequency Division Multiple Access, the signal multiplexing technology used in the Advanced Mobile Phone Service (AMPS) analog version of cellular phone technology.

See: *Frequency Division Multiple Access (FDMA)*

Federal Communications Commission (FCC)

A U.S. government agency regulating all aspects of telecommunications.

Overview

The Federal Communications Commission (FCC) was established under the Communications Act of 1934 as an independent federal regulatory agency. Among other responsibilities, the FCC licenses portions of the electromagnetic spectrum for communication technologies such as cellular phones and wireless networking. For example, in 1994 the FCC auctioned off portions of the 1900-megahertz (MHz) radio wave section of the electromagnetic spectrum to enable companies to deploy Personal Communications Services (PCS) technologies for cellular communication. FCC auctions are intended to increase the number of cellular phone providers in the United States, foster growth and competition in the telecommunications industry, and raise money for the U.S. government treasury.

One role of the FCC is to implement communication legislation passed by Congress. The Telecommunications Act of 1996 represents the first major overhaul of the laws regarding telecommunications in more than 60 years. The FCC is tasked with enforcing this legislation, which is designed to open up competition in the telecommunications arena to foster innovation and economic progress.

For More Information

Visit the FCC at *www.fcc.gov.*

Federal Information Processing Standard (FIPS)

Any standard ratified by the National Institute of Standards and Technology (NIST).

Overview

NIST is a U.S. government organization responsible for developing standards in industry and commerce. Federal Information Processing Standard (FIPS) standards are one aspect of the work of NIST and represent standards relating to computing, networking, cryptography, and related subjects.

An example of a FIPS standard is FIPS-140, the “Security Requirements for Cryptographic Modules” standard whose compliance is required by the U.S. government by vendors developing hardware and software platforms for sensitive (but not classified) cryptographic purposes. Microsoft Windows 2000, Windows XP, and Windows .NET Server cryptographic services are FIPS 140-1 Level 1 compliant.

Notes

Another recent FIPS standard is the Advanced Encryption Standard (AES) that officially replaced the aging Data Encryption Standard (DES) in 2001.

For More Information

You can find FIPS publications at *www.itl.nist.gov/fipspubs.*

See Also: *cryptography, encryption, National Institute of Standards and Technology (NIST)*

FHSS

Stands for Frequency Hopping Spread Spectrum, any type of wireless communications system based on frequency hopping.

See: *Frequency Hopping Spread Spectrum (FHSS)*

Fiber Distributed Data Interface (FDDI)

A high-speed networking technology used mainly for campus backbones.

Overview

Fiber Distributed Data Interface (FDDI) was developed in the early 1980s as a high-speed networking technology for processor-to-processor communications. It was the first local area network/metropolitan area network (LAN/MAN) networking technology that could support data transmission speeds of 100 megabits per second (Mbps). (Until 1993, its only competitor was 16 Mbps Token Ring, a much slower technology.) Although developed originally for the host interconnection environment, FDDI quickly evolved into a popular technology for building high-speed distributed backbones for campus-wide networks and reached its peak of popularity in the mid-1990s.

FDDI transmits data at 100 Mbps over fiber-optic cabling (either single-mode or multimode) configured in a dual physical ring topology. The dual ring topology provides redundancy since the secondary ring is used as a standby for the primary ring. By utilizing the secondary ring for traffic instead of redundancy, FDDI is also capable of transporting data at 200 Mbps. There is also a version of FDDI called Copper Distributed Data Interface (CDDI) that is implemented using copper cabling instead of fiber-optic cabling, but this is not as popular as the fiber version.

FDDI is standardized by the X3T9 committee of the American National Standards Institute (ANSI) and is an International Organization for Standardization (ISO) standard.

Architecture

FDDI uses a token-passing technology similar to that of Institute of Electrical and Electronics Engineers (IEEE) 802.5 Token Ring networks. FDDI stations generate a three-octet token that controls the sequence in which other stations will gain access to the wire. The token passes around the ring, moving from one node to the next. When a station wants to transmit information, it captures the token, transmits as many frames of information as it wants within the specified access period and releases the token (this feature of transmitting multiple data frames per token capture is known as a timed token or capacity allocation scheme and differentiates it from the priority mechanism used in IEEE 802.5 Token Ring). Each node on the ring checks each and every frame to see if it is the frame's intended recipient, and the recipient node reads the information from the frame. When a frame completes its travel around the ring and returns to its originating node, the frame is stripped from the ring.

FDDI is a connectionless networking architecture that supports both asynchronous and synchronous transmission. FDDI packages data in frames that use 48-bit addressing similar to MAC addressing for Ethernet. The frame size for an FDDI frame can range from 32 to 4400 bytes. FDDI frames can encapsulate local area network (LAN) traffic such as Internet Protocol (IP) packets for transmission over FDDI backbones. Different FDDI implementations use one of three possible framing formats:

- **FDDI-raw:** Supported by Cisco routers running Internetwork Operating System (IOS) versions 11.1.*x* and later, and by some third-party vendors
- **FDDI with LLC:** Supported by IOS versions 10.0 and earlier
- **FDDI with LLC and SNAP:** Default format for encapsulating Internetwork Packet Exchange (IPX) packets on FDDI

Implementation

FDDI is usually implemented as a dual token-passing ring that uses a physical and logical ring topology for campus-wide backbone networks or a physical ring but logical star topology for FDDI LANs within a building. An FDDI dual ring consists of a primary and secondary ring operating in a counter-rotating fashion. While the primary ring always carries data, the secondary ring is usually reserved as a backup in case the primary ring goes down. This scheme provides FDDI with the degree of fault tolerance valuable for mission-critical network backbones. In the event of a failure on the primary ring, FDDI automatically reconfigures itself to use the secondary ring, as shown in the illustration. Faults can be located and repaired using a fault isolation technique called beaconing.

FDDI can also be implemented in a form where the secondary ring also carries data, but in the opposite direction from the primary ring. This configuration extends the maximum potential bandwidth of FDDI to 200 Mbps.

Nodes (or stations) on an FDDI backbone can connect to either one or both rings depending on the media interface connector (MIC) employed. These nodes may be directly attached computer systems, concentrators (similar to Token Ring Multistation Access Units [MAUs]), or bridges and switches for connecting FDDI to other LAN/WAN architectures. The two ways of attaching nodes to an FDDI backbone are

- **Dual-Attached Stations (DAS):** Also called Class A stations, these devices connect to both rings using dual fiber-optic connectors. The A port is the point at which the primary ring enters and the secondary ring leaves, and the B port is the reverse. Dual-attached stations use both rings, with the secondary ring serving as a backup for the primary. Dual-attached FDDI is used primarily for network backbones that require fault tolerance. Single-attached stations can be connected to dual-attached FDDI backbones using a dual-attached device called a concentrator or multiplexer.

- **Single-Attached Stations (SAS):** Also called Class B stations, these devices connect to either the primary or secondary ring using S ports. Single-attached FDDI uses only the primary ring and is not as commonly deployed for network backbones as dual-attached FDDI. Single-attached stations are used primarily to connect Ethernet LANs or individual servers to FDDI backbones.

FDDI supports up to 500 nodes in its normal dual-ring configuration with distances up to 1.25 miles (2 kilometers) between adjacent nodes. The maximum circumference for an FDDI ring is 62.5 miles (100 kilometers) (or 125 miles/200 kilometers for both rings combined), and there must be a repeater every 1.25 miles (2 kilometers) or less. Bridges or routers are used to connect the FDDI backbone network to Ethernet or Token Ring departmental LANs.

Prospects

In the late 1980s and early 1990s, FDDI was the most popular networking technology for building distributed high-speed campus backbones. Asynchronous Transfer Mode (ATM) was its only competition, but ATM's complexity resulted in slow adoption and relegation of this technology mainly to telecommunication carrier networks.

When Fast Ethernet emerged in 1993, it competed with FDDI with respect to speed but could not do so with respect to distance. Nevertheless, FDDI lost some ground to Fast Ethernet, mainly because Fast Ethernet could be deployed in a switched full-duplex form to build collapsed backbones, a new network backbone architecture that competed with FDDI's distributed backbone architecture. The result was that the market for FDDI technology peaked in 1995 and has been declining ever since.

With the emergence of Gigabit Ethernet (GbE) in 1997, however, the death knell for FDDI began to sound. Switched full-duplex GbE could replace legacy FDDI backbones in campus networks and provide speed increases of tenfold to better carry escalating network traffic.


A working FDDI backbone:
Primary ring
Secondary ring
FDDI concentrator/ bridge
FDDI concentrator/ bridge
LAN servers
LAN workstations
When a fault occurs in the primary ring:
Fault

Fiber Distributed Data Interface (FDDI). *Fault-tolerant operation of dual-ring FDDI.*

The final blow came in early 2001, when manufacturers of chips used in FDDI transceivers closed shop and stopped producing, which means that once the current supply of vendor's FDDI equipment is sold, no more will be manufactured. Because of these market developments, most large enterprises using FDDI have begun or already completed migrating their network backbones from FDDI to GbE. Although FDDI is a stable technology that has proved reliable in the enterprise, the impending unavailability of replacement equipment makes migration to GbE advisable.

Notes

When bridging between Ethernet LANs and FDDI backbones, be aware that there are two types of bridges:

- **Encapsulating bridges:** Encapsulate Ethernet frames into FDDI frames
- **Translating bridges:** Translate source and distention MAC addresses into FDDI addresses

Deploying these two FDDI bridging technologies together can result in incompatibilities. For example, although Cisco FDDI bridges can generally interoperate with translating bridges from other vendors, their encapsulation method is proprietary and usually will not work with encapsulating bridges from other vendors. Both types of bridging methods are commonly used in FDDI networks.

The following table shows some troubleshooting tips for FDDI networks.

FDDI Troubleshooting

Problem	*Suggestions*
FDDI ring is not functioning.	Check the status of the router's FDDI interface, making sure the interface and line protocol are up. Try pinging a remote router. Check the physical connections of the cable; use an optical time domain reflectometer to test for problems.
Signal is degraded.	Check whether the upstream FDDI neighbor has failed and the bypass switch has been activated.

See Also: *Asynchronous Transfer Mode (ATM), fiber-optic cabling, Gigabit Ethernet (GbE), Token Ring*

fiber exhaust

A term referring to the potential saturation of the fiber-optic backbone of the Internet due to the exponentially increasing demand for Internet services.

Overview

As high-speed residential Internet access using cable modems and Asymmetric Digital Subscriber Line (ADSL) technology becomes more and more widely deployed, this creates stress on the capacity of the Internet's backbone for carrying all this additional traffic. Another factor contributing to fiber exhaust is the move within the corporate arena toward new high-bandwidth services such as Internet Protocol (IP) telephony and video multicasting technologies delivered over the Internet. Some analysts foresee conditions arising within the next few years that could cause significant degradation in the performance of the Internet due to the proliferation of these services.

Strategies that telecommunications carriers can use to prevent fiber exhaust from occurring include

- Creating additional high-speed, fiber-optic backbone lines for the Internet by laying down more fiber
- Using dense wavelength division multiplexing (DWDM) technologies to enable existing fiber backbones to carry additional traffic
- Upgrading existing time-division multiplexing (TDM) fiber backbones to higher bit rates

See Also: *Internet*

fiber-optic cabling

A glass cabling media that sends network signals using light.

Overview

Fiber-optic cabling (or simply fiber) is the main alternative to copper cabling for building wired computer networks (a network build using wires is called a wireline network, as opposed to a wireless network that transmits data using radio transceivers). Fiber-optic cabling has higher bandwidth capacity than copper cabling and is used mainly for high-speed networking such as Asynchronous Transfer Mode (ATM) and Gigabit Ethernet

(GbE) backbone networks, long cable runs between buildings, and switched connections to high-speed server farms and high-performance workstations.



Fiber-optic cabling. *Composition of fiber-optic cabling.*

As shown in the illustration, fiber-optic cabling consists of a glass core between 5 and 100 microns in diameter (for comparison, a sheet of paper is about 25 microns thick and a human hair about 75 microns thick). This glass core is the signal-carrying medium of the cable, and its extreme purity and transparency allow light to travel along it for many miles before being attenuated.

The glass core is surrounded by a thin layer of pure silica called cladding, which prevents light from escaping from the core by a process called total internal reflection. Surrounding the cladding are protective layers of acrylic plastic coating that give the cable stiffness to prevent it from being excessively bent (bending a fiber-optic cable too much can cause the glass core to fracture), Kevlar fibers for providing additional strength to resist stretching during installation, and a waterproof protective polyvinyl chloride (PVC) jacket that is usually colored a distinctive orange.

Fiber optic-capable networking components such as network interface cards, bridges, switches, and routers convert electrical signals into light pulses for transmission over fiber-optic cables. These light pulses are generated using either light-emitting diode (LED) or laser-emitting diodes and associated electronic circuitry.

The bandwidth of a fiber-optic cable depends on the distance (length of the cable) as well as the frequency used for transmitting the signal. Fiber bandwidth is usually expressed in frequency-distance form—for example, in megahertz-kilometers, or MHz-km. In other words, a 500-MHz-km fiber-optic cable can transmit a signal a distance of 5 kilometers at a frequency of 100 MHz (5 x 100 = 500), or a distance of 50 kilometers at a frequency of 10 MHz (50 x 10 = 500). In other words, there is an inverse relationship between frequency and distance for transmission over fiber-optic cables—the higher the frequency, the shorter the distance supported.

Uses

Fiber-optic cabling is often used for campus-wide backbones, long cabling runs between buildings, and local area network (LAN) connections to heavily used servers or high-speed workstations. Fiber is still not used extensively at the LAN level because it is more expensive and more difficult to install than copper cabling, but the gain in capacity to support future network upgrades often compensates for the increased installation costs.



Fiber-optic cabling. *Connecting two local area networks (LANs) using fiber-optic cabling.*

Multimode fiber of 62.5 micron diameter is the main type of fiber used for GbE networking. This is because 62.5 micron multimode fiber is also the standard for widely deployed 10BaseF Ethernet and 100BaseFX Fast Ethernet (and also FDDI) networks. This type of fiber supports distances up to 1800 feet (550 meters), making it suitable for building GbE backbones within buildings. If gigabit transmission over longer distances is required, 50 micron multimode fiber can be used instead, but this reduces flexibility since this type cannot be used for slower Ethernet networks. For really long GbE fiber connections, such as between buildings on a campus or across a metropolitan area network (MAN), single-mode fiber must be used.

Fiber is used also in heavy industrial environments where machinery can cause high levels of electromagnetic interference (EMI). Long-distance telecommunications carriers such as Sprint Corporation, MCI Worldcom, and AT&T also use fiber-optic cabling extensively for their long-haul (long-distance) telecommunications trunk lines.

Different styles of fiber-optic cabling exist, depending on the intended use. Examples include the following:

- **Duplex multimode cable:** With 62.5-micron core and 125-micron cladding, this is the most common general purpose cable type for most networking environments that require fiber-optic cabling. These cables usually come already terminated with pairs of connectors attached at each end, but you can also buy the cabling in bulk form where you can separate the two cables for termination purposes just as you can with an appliance power cord.
- **Breakout style cable:** This style of cabling contains multiple individual simplex fibers that are stranded around a central strengthening member. It is used for work-area connections and does not require patch panels.
- **Distribution style cable:** This style of cabling contains multiple individual simplex color-coded fibers that are stranded around a central strengthening member. It is often used in backbone applications that require multiple fiber connections.
- **Steel-reinforced cable:** This type of cabling uses a corrugated steel inner tube for protecting cable that needs to be buried or run outdoors.

Fiber-optic cabling is also available for purchase in bulk for those who want the challenge of terminating it themselves, but most customers buy standard or custom preterminated cables from suppliers. These cables can be simplex or duplex; they can be single-mode or multimode (multimode is most common); and they can be terminated with ST-ST, ST-SC, SC-SC, or SMA connectors.

Implementation

There are two basic types of fiber-optic cabling:

- **Single-mode fiber-optic cabling:** Has a narrow core (typically 7.1, 8.5, or 9 microns in diameter) that allows only one signal (light beam) to be sent or received at a time. Single-mode fiber-optic cabling uses laser-emitting diodes operating at frequencies between 1270 and 1355 nanometers (in the infrared range) to transmit signals over distances up to about 30 miles (50 kilometers) before dispersion will distort signals. Single-mode fiber is therefore ideal for long cable runs (up to 50 times farther than for multimode fiber-optic cabling).
- **Multimode fiber-optic cabling**: Has a thicker core (50, 62.5, or 100 microns in diameter) with sufficient width to allow multiple signals (light beams) to be transmitted simultaneously with each signal following a different path or mode through the fiber. Light-emitting diodes are used to transmit signals operating at frequencies between 770 and 860 nanometers (the near infrared) over distances up to about 3000 feet (900 meters) (longer cable runs can distort signals through modal dispersion). The thicker the glass core, the shorter the distance signals can be carried over the cable before dispersion causes signals to be degraded.

There are also two different types of multimode fiber:

- **Step-index multimode fiber:** The less costly variety of multimode fiber, it uses a wide core with a uniform index of refraction, causing the light beams to reflect in mirror fashion off the core’s inside surface by the process of total internal reflection.

Because light can take many different paths down the cable and each path takes a different amount of time, signal distortion can result when step-index fiber is used for long cable runs, so use this type only for short cable runs.

- **Graded-index multimode fiber:** The more expensive type of multimode fiber, it uses a core made of multiple concentric layers of glass, each having a lower index of refraction than the layer it contains. In graded-index fiber, light beams follow curved paths and all rays reach the end of the fiber simultaneously, reducing the signal distortion that occurs in step-index fiber when long cable runs are used.

Connectors for fiber-optic cabling come in several varieties, including SC, ST, and SMA connectors. ST connectors have a wider installed base, but SC connectors are more versatile and more popular and are used in 100BaseFX, GbE, and Fibre Channel deployments. SMA connectors are sometimes used but do not conform to Electronic Industries Association/Telecommunication Industry Association (EIA/TIA) wiring standards. A newer type of connector is the MT-RJ, which has a snap latch fastener similar to an RJ-45 plug to simplify reconfiguring fiber networks from patch panels. Other connectors have appeared on the horizon for special purpose usage, but how popular these will become remains to be seen.

All forms of networking components are available in fiber-capable forms, including network cards, hubs, bridges, switches, and routers. Also available are line drivers, devices that enable you to extend or interconnect LANs in either point-to-point or multipoint configurations. Line drivers for fiber-optic cabling are available for synchronous or asynchronous transmission as well as for single-mode or multimode fiber.

Advantages and Disadvantages

Fiber-optic cabling has many advantages over copper cabling, including the following:

- Data transmission rates of up to 100 gigabits per second (Gbps) and higher are supported (copper transmission currently maxes out around 5 Gbps).
- Bit error rate (BER) for fiber is about 10^{-10} compared to 10^{-6} for copper, making fiber a much more reliable transmission media than copper.
- Low attenuation, allowing signals to be sent over distances measured in miles instead of feet.
- Less than 10 percent the weight of equivalent copper cabling.
- Immunity to crosstalk and noise caused by electromagnetic interference (EMI).
- Prevention of ground loops by electronically isolating transmitting and receiving stations.
- Greater signal security because signals cannot be picked up by electromagnetic induction as they can from copper cabling. Fiber must be tapped (physically opened) in order to eavesdrop on the transmission.

Prospects

Although copper has sufficed in many instances as LAN speeds have increased from 10 Mbps standard Ethernet to 1 Gbps GbE, it is not likely to be able to support speeds beyond 4 to 5 Gbps. The impending 10 GbE specification will likely be a fiber-only specification, and as a result, copper will probably be considered legacy technology in 5 to 10 years.

Although many have argued that fiber is prohibitively expensive for workgroup LAN deployments, recent case studies have suggested that this is not the case. The cost of laying fiber in a structured wiring scenario is only 10 to 20 percent higher than laying copper, and fiber network interface cards (NICs) for PCs are nearing prices of equivalent RJ-45 NICs. In structured wiring, however, laying fiber everywhere allows you to eliminate the traditional wiring closet on each floor and connect floors directly through patch panels and vertical rises to the main equipment room. This means you need far fewer switches and routers in a fiber-based structured wiring deployment than in a copper one. For example, ComputerWorld magazine reported that when George Washington University wired their 80-building campus using fiber, only 11 wiring closets were needed compared with an estimated 160 that would have been required had copper been used. The savings in equipment costs for new installations make fiber a logical choice over copper and also lay the groundwork for future upgrades when faster networking technologies become available. Enterprise network architects would do well to always seriously consider using fiber for both new deployments and when networks are being upgraded.

Another impetus toward the long-awaited goal of fiber to the desktop is technological improvements in fiber-optic cabling and connectors. Some new fiber-optic cabling is so flexible that it can be tied in a knot without fracturing the core, making installation simpler and less worrisome. New and simpler connectors such as the LC connector from Lucent Technologies, Fiber Jack from Panduit Corporation, and VF-45 from 3M Corporation, Corning, and Siemens make fiber installation and configuration a simple plug-and-play process, with some of these connectors rivaling RJ-45 in size.

Notes

Be careful not to stress fiber-optic cabling unduly during installation. The maximum acceptable bend radius is usually 10 times the diameter of the cable, or about 1.2 inches (3 centimeters). Use an optical time domain reflectometer (OTDR) to test for faults after installation. Loss of signal, or attenuation, in fiber-optic cables can be caused by absorption (no medium is completely transparent to light), cable microbending (especially in single-mode fiber if it is not installed correctly), connector loss because of poor splicing or poorly installed or misaligned connectors, or coupling loss at the transmitter or receiver.

For safety, never look down a fiber-optic cable connected to your network because the invisible laser light can injure your retinas. When splicing connectors onto fiber, be careful to avoid getting shards of glass in your eyes or on your hands—use double-sided tape to clean the connection and remove loose shards and always wear protective goggles.

For More Information

Find out what's happening in the fiber market at *www.fiberopticsonline.com.*

See Also: *copper cabling, dark fiber, SC/ST connectors, time domain reflectometry (TDR)*

fiber to the curb (FTTC)

The laying of fiber-optic cabling by telcos to the customer premises.

Overview

Fiber to the curb (FTTC) is viewed by telcos as the successor to the copper local loop and will allow high speed broadband voice, video, and data services to be delivered directly to the subscriber on all-fiber lines without requiring conversion to electrical signals for transmission over copper. FTTC is thus envisioned by telcos as the replacement for the aging Plain Old Telephone System (POTS).

Other versions of the acronym include

- **FTTB:** Fiber to the building, used to describe commercial (as opposed to residential) upgrades of the copper local loop.
- **FTTN:** Fiber to the neighborhood, used to describe laying fiber from the telco central office (CO) to distribution boxes in neighborhoods.

Prospects

FTTC has been talked about by telcos for years, but it has not been deployed much for two reasons:

- The cost of building an entirely new cabling system to replace the existing copper one is extremely high.
- Technologies such as Asymmetric Digital Subscriber Line (ADSL) have allowed telcos to deliver high-speed data services and Internet connections to subscribers using existing copper local loop lines, and demand for ADSL has not yet been saturated.

A recent change in this situation is Project Pronto, an FTTN deployment underway by SBC Communications (a Regional Bell Operating Company [RBOC]). Project Pronto is designed to bring ADSL to areas that are currently too far away from COs for this to be possible, and it involves replacing copper subloops with fiber that runs directly from COs to remote terminals in distant neighborhoods. Some other RBOCs are also pursuing similar projects, so the era of FTTC may in fact be only a few years away, at least in metropolitan areas of the United States.

See Also: *Asymmetric Digital Subscriber Line (ADSL), fiber-optic cabling, local loop, telco*

Fibre Channel

A high-speed networking technology mainly used for connecting storage devices to computer networks.

Overview

Fibre Channel is a gigabit networking technology developed in the late 1980s for connecting peripheral storage systems to mainframe hosts over long distances. The Fibre Channel specification was defined in 1994 by American National Standards Institute (ANSI) standard X3.230.

Fibre Channel typically provides data transfer at 1000 megabits per second (Mbps) or higher and is envisioned as the successor to Small Computer System Interface (SCSI) for connecting storage peripherals to computer systems and networks. Enterprise-level data storage technologies can benefit from Fibre Channel because the traditional SCSI interface has become a bottleneck in high-speed server-to-disk operations. Fibre Channel eliminates the limitations of bandwidth, distance, and scalability that are related to the SCSI standard and is becoming the industry standard for enterprise-level storage solutions involving high-performance redundant array of independent disks (RAID) arrays and storage area networks (SANs).

A simple Fibre Channel implementation could use a stackable hub or switch to connect a server or mainframe host to an external Fibre Channel RAID storage system using 100-Mbps redundant loops and hot-swappable disks. Servers can also use SCSI over Fibre Channel for connecting to legacy storage systems, and Fibre Channel can also carry Transmission Control Protocol/Internet Protocol (TCP/IP) and video traffic for server-to-server connections and high speed workstation connections in computer-aided design/computer-aided engineering (CAD/CAE) or multimedia environments.

Uses

Although Fibre Channel is viewed as the future replacement for the SCSI standard for connecting servers to external data storage units such as external hardware RAID arrays, it can also be used as a transport for high-speed data and video transmission over networks where Fibre Channel competes with other high-speed networking technologies, such as Gigabit Ethernet (GbE) and Asynchronous Transfer Mode (ATM).

Architecture

Fibre Channel is built in a layered architecture that has five layers:

- **FC-0:** This is the lowest layer or physical interface and defines the optical and electrical characteristics and media options for deployment.
- **FC-1:** This layer is responsible for signal encoding and link control. Fibre Channel uses an 8B/10B encoding scheme that packages 8 bits of data into 10 symbols for transmission, which results in 25 percent protocol overhead (for example, 125 megahertz [MHz] signaling can only transmit data at 100 Mbps). Commands can be sent over a Fibre Channel network by prefixing them with a special character called K28.5.
- **FC-2:** This layer is responsible for framing, flow control, and class of service. Fibre Channel frames are 2,148 bytes long, of which 2,112 bytes constitute payload. Fibre Channel currently supports five different service classes, only three of which are commonly implemented, namely, Class 1 (circuit-switched), Class 2 (connectionless frame-switched), and Class 3 (connectionless point-to-multipoint).
- **FC-3:** This layer is open for specifying various advanced services that might be needed.
- **FC-4:** This is the top layer and is responsible for interoperability with other protocols such as Internet Protocol (IP) and SCSI-3.

Fibre Channel is a serial transmission scheme (like SCSI) and supports various transmission speeds, including 133 Mbps, 266 Mbps, 532 Mbps, and 1.0625 gigabits per second (Gbps). The last speed is most commonly used, and with 8B/10B line coding results in data rates of 100 megabytes (MBps), or 200 MBps in full duplex mode). There are plans to increase speeds to 4 Gbps as well.

Implementation

Despite its name, Fibre Channel can operate over both fiber-optic and copper cabling depending on how it is implemented, with fiber being the norm. Fiber links can be 6.2 miles (10 kilometers) or longer using single-mode fiber or up to 1640 feet (500 meters) on multimode fiber. Copper links are used mainly for short interconnects and are limited to 100 feet (30 meters) in length.



Fibre Channel. *An example of using Fibre Channel to connect network storage systems to computer systems.*

Fibre Channel signaling is performed by special transceivers. A Fibre Channel transceiver is more commonly known as a gigabit interface converter (GBIC), and GBICs can be found in Fibre Channel hubs, switches, and interface cards.

Fibre Channel can be deployed in three different network topologies:

- **Point-to-point:** This involves a dedicated link between only two devices such as two servers, a server and a disk storage system, a router/switch and a SAN, and so on.
- **Arbitrated loop:** This implementation, commonly called Fibre Channel Arbitrated Loop (FC-AL), uses a shared media approach to allow multiple devices to be connected together. It is the most common implementation method for Fibre Channel networks because of its flexibility and efficient use of bandwidth. A special process called arbitration determines which node has control of the media at any moment and is allowed to transmit. The logical topology is a daisy-chained system of loops similar to Fiber Distributed Data Interface (FDDI) and Token Ring architectures, but the actual physical topology is more commonly a hierarchical system of hubs and switches similar to Ethernet. Arbitrated loops can support hundreds of attached devices, but the more devices there are the less average bandwidth available to each device.
- **Switched fabric:** This involves using Fibre Channel switches to provide 100 Mbps switched connections to all connected devices through virtual point-to-point connections. Fully meshed topologies are supported for complete redundancy, and any number of devices can be connected to the fabric. Switched fabrics can theoretically support up to 15 million attached devices (unique addresses), but in practice the limit is about 1000. A downside of this approach is the additional latency caused by the need for virtual connections to be established and torn down frequently.

Advantages and Disadvantages

Fibre Channel's strengths include its protocol-independent transport service (in contrast to GbE's frame format, which extends from the desktop to the network backbone) and its guaranteed delivery service (included in Class 4 Fibre Channel, which makes it competitive with ATM's Quality of Service features). Also, although GbE is limited to general networking transport solutions and ATM is limited to networking and video transport, Fibre Channel can carry both network and video traffic, connect computer systems and networks to network storage devices, and it can be used in high-performance clustering technology.

The main disadvantages are that Fibre Channel equipment is generally expensive, the technology is complex (compared to Ethernet), equipment from different vendors often suffers from interoperability problems, and native file sharing support is not provided.

Prospects

Interoperability issues between vendor implementations of Fibre Channel have been one factor slowing general adoption of the technology, but new specifications were released in 2000 to help make Fibre Channel equipment from different vendors work as simply as plug and play. The two most important of these new specifications are Direct Access File Specification (DAFS) and Fabric Shortest Path First (FSPF).

More seriously, Fibre Channel faces stiff competition from emerging new storage-over-IP network technologies including Service Specific Connection Oriented Protocol (SSCOP) from SAN Ltd., SCSI over TCP/IP from IBM and Cisco Systems, EtherStorage from Adaptec, and especially 10 GbE. This is somewhat ironic as the underlying physical layer technologies of GbE were in fact borrowed from the FC-0 and FC-1 layers of the earlier Fibre Channel standard!

These emerging storage-over-IP technologies promise several advantages over Fibre Channel, including more familiar underlying technology (Ethernet), better latency, lower packet loss, and transmission over longer distances. The industry debate is sometimes hot, from Fibre Channel proponents envisioning Fibre Channel being used for general local area network (LAN) transport to 10 GbE proponents declaring Fibre Channel as dead as FDDI.

But things are constantly changing in the networking world, and Fibre Channel may be down but not out. A new contender in the arena is Fibre Channel Over IP (FCOP), a scheme proposed by Lucent Technologies and other vendors. FCOP encapsulates Fibre Channel frames in IP packets to allow them to be carried over GbE or even long-haul ATM/Synchronous Optical Network (SONET) trunk lines, making FCOP a technology that could extend Fibre Channel links to transcontinental distances. Using FCOP, for example, a SAN in New York can be connected to a corporate network in California over an ATM/SONET wide area network (WAN) link. A similar standard called Fibre Channel Backbone has also been proposed as a possible ANSI standard. We will have to wait until the dust clears on this one!

For More Information

Visit the Fibre Channel Industry Association at *www.fibrechannel.com.*

See Also: *10G Ethernet, Gigabit Ethernet (GbE), Small Computer System Interface (SCSI), storage over IP*

file

Information assigned a name and stored on a disk or some other media.

Overview

Files are the primary unit of information stored on disk systems. Examples of files include

- Executable files (programs)
- Data files (documents, databases)
- Web pages (HTML files)

Files are generally stored in a file system, which provides a hierarchical way of saving, locating, and accessing information.

See Also: *file system*

file allocation table (FAT)

Specifically, a table maintained on a hard disk by MS-DOS and Microsoft Windows operating systems that acts as a table of contents, showing where directories and files are stored on the disk. By extension, the acronym FAT is also used to refer to the file system itself for MS-DOS and Windows platforms.

Overview

On Microsoft operating system platforms, when we refer to the file allocation table (FAT) file system, we often simply call it the FAT. The FAT is widely supported by all Windows platforms and can be installed on partitions of up to 2 gigabytes (GB) in size on Windows 95 and Windows 98, and on partitions of up to 4 GB on Windows NT. In Windows 2000, Windows XP, and Windows .NET Server, if the partition size is greater that 2 GB, it will automatically be formatted as FAT32. The FAT is often used in dual-boot scenarios or when the security and reliability of the NTFS file system (NTFS) is not required.

The FAT file system is based on the FAT, a structure that maps the locations of the clusters in which files and folders are stored on the disk. The FAT records the location of each cluster that makes up a given file and the sequence in which it is stored. This is necessary because files usually are not stored in a contiguous location on a hard disk because of the presence of disk fragmentation caused by the creation and deletion of files on the disk. For each file on a FAT volume, the FAT contains the entry point for the allocation unit in which the first segment of the file is stored, followed by a series of links called the allocation chain. The allocation chain indicates where succeeding segments of the file are located and is then terminated by an end-of-file (EOF) marker.

Two copies of the FAT are kept in fixed locations on the disk to provide redundancy. A disk formatted with the FAT file system is said to be a FAT volume. The sizes of the individual clusters in which file information is stored on a FAT volume depend on the size of the partition or logical drive formatted using FAT, as shown in the following table. For compatibility reasons, these cluster sizes are the same whether the FAT volume is on an MS-DOS or Windows platform. In the table, you will see that on small FAT partitions (under 15 megabytes [MB] in size) a special 12-bit FAT file system is used instead of the usual 16-bit FAT.

FAT Information for Different Volume Sizes

Drive Size	*FAT Type*	*Sectors/ Cluster*	*Cluster Size*
0 MB–15 MB	12-bit	8	4 kilobytes (KB)
16 MB–127 MB	16-bit	4	2 KB
128 MB–255 MB	16-bit	8	4 KB
256 MB–511 MB	16-bit	16	8 KB
512 MB–1023 MB	16-bit	32	16 KB
1024 MB–2047 MB	16-bit	64	32 KB
2048 MB–4095 MB	16-bit	128	64 KB

Different versions of Windows support different file systems. The original release of Windows 95 supports only FAT, but Windows 95 OSR2 and Windows 98 support FAT and FAT32. FAT32 is a newer 32-bit version of FAT that was first included with the OSR2 release of Windows 95. The original version of FAT is 16-bit and is sometimes referred to as FAT16. Windows NT supports both FAT and NTFS, but not FAT32. Windows 2000, Windows XP, and Windows .NET Server support FAT, FAT32, and NTFS. Possible advantages of using FAT volumes with Windows NT, Windows 2000, Windows XP, and Windows .NET Server include the following:

- **Multiboot capability:** If you need to dual boot between Windows 95 or Windows 98 and Windows NT, use FAT instead of NTFS because Windows 95 and Windows 98 cannot read or recognize NTFS volumes.
- **Efficiency on small partitions:** FAT requires less overhead than NTFS and is more efficient on smaller volumes (those under 400 MB in size).

Notes

The root directory on a FAT volume has a fixed size and can contain only a limited number of entries.

See Also: *FAT32, file system, NTFS file system (NTFS)*

File and Printer Sharing for Microsoft Networks

A Microsoft Windows networking component that allows computers running Windows to share folders and printers so that other clients can access them.

Overview

File and Printer Sharing for Microsoft Networks uses the Server Message Block (SMB) file sharing protocol and is compatible with clients such as

- Computers running Windows have Client for Microsoft Networks installed
- Windows NT, Windows 2000, Windows XP, and Windows .NET Server
- Windows for Workgroups
- LAN Manager

Use the Network utility in Control Panel to install Client for Microsoft Networks on a computer running Windows 95 or Windows 98.

Notes

You cannot install File and Printer Sharing for Microsoft Networks if File and Printer Sharing for NetWare Networks is already installed.

See Also: *File and Printer Sharing for NetWare Networks*

File and Printer Sharing for NetWare Networks

A Microsoft Windows networking component that allows computers running Windows to share folders and printers so that they can be accessed by Novell NetWare clients and by computers running Windows with Client for NetWare Networks.

Overview

Use the Network utility in Control Panel to install File and Printer Sharing for NetWare Networks on most versions of Windows. Installing File and Printer Sharing for NetWare Networks automatically installs the NWLink Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX)-Compatible Transport protocol and Client for NetWare Networks, if these have not already been installed. A bindery-based NetWare server must also be available as a network security provider because File and Printer Sharing for NetWare Networks does not support NetWare servers running Novell Directory Services (NDS).

Notes

You cannot install File and Printer Sharing for NetWare Networks if File and Printer Sharing for Microsoft Networks is already installed.

See Also: *File and Printer Sharing for Microsoft Networks*

File and Print Services for Macintosh (FSM)

A Microsoft Windows 2000 service that provides Apple Macintosh users with access to files stored on NTFS file system (NTFS) volumes on Windows 2000 file servers.

Overview

File and Print Services for Macintosh (FSM) is the Windows 2000 counterpart to Services for Macintosh on machines running Windows NT. FSM lets PC and Apple Macintosh clients share files and printers. With FSM on a server running Windows 2000, Macintosh client machines need nothing more than the Macintosh operating system software installed to access resources on the server.

FSM integrates the following three services:

- **File Services for Macintosh:** Also called MacFile, this service lets Macintosh clients access files stored on the server running Windows 2000. Use MacFile to specify a directory on an NTFS volume as a Macintosh-accessible volume.
- **Print Services for Macintosh:** This service lets Macintosh clients print to printers connected to the server running Windows 2000 and spools print jobs for AppleTalk printers such as the LaserWriter.
- **AppleTalk protocol:** This service can be installed on the server running Windows 2000 to enable it to function as an AppleTalk router.

Once FSM is installed on your server, you can make directories available as Macintosh volumes by using the Shared Folders node in the System Tools folder of the Computer Management tool.

Notes

You can install an optional authentication module for Macintosh clients so that they can securely log on to Windows 2000–based servers running FSM.

See Also: *AppleTalk*

File and Print Services for NetWare (FPNW)

A Microsoft Windows NT and Windows 2000 add-on utility for providing Internetwork Packet Exchange (IPX) file and print services to NetWare clients.

Overview

File and Print Services for NetWare (FPNW) enables a server running Windows NT or Windows 2000 to perform the following functions:

- Allow legacy NetWare 3.*x* IPX client machines to access resources on a server running Microsoft Windows NT
- Share directories and printers on a server running Windows NT so that NetWare 3.*x* clients can access them
- Manage NetWare 3.*x* printers from a server running Windows NT, making these printers also available to Microsoft clients



File and Print Services for NetWare (FPNW). *How FPNW works.*

Implementation

FPNW accomplishes these functions by mimicking the functionality of a NetWare 3.12 file and print server and providing file and print services directly to NetWare and compatible client computers. A server running Windows NT or Windows 2000 using FPNW appears to NetWare client machines as if it were really a NetWare server, and clients can access volumes, files, and printers just as they would on a NetWare server. Accounts for NetWare client users are stored in the Security Accounts Manager (SAM) database, instead of requiring maintenance in a separate NetWare server. The FPNW server supports both the Server Message Block (SMB) protocol for Windows client connections and the NetWare Core Protocol (NCP) for NetWare client connections. FPNW requires that the NWLink IPX/SPX-Compatible Transport protocol be installed on the server.

FPNW supports NetWare functions such as user-account creation, remote administration, secure logins, and print queue management. However, it does not support NetWare functions such as user disk volume restrictions or inherited rights masks.

Notes

FPNW is not included with Windows NT or Windows 2000, but you can obtain it as a separate utility from your Microsoft value-added reseller (VAR). FPNW can be installed only on server machines, not on workstations. The directory that will be used as a NetWare SYS volume should be on an NTFS file system (NTFS) partition.

file extension

In Microsoft operating systems, a string appended to a filename, consisting of a period followed by three alphanumeric characters.

Overview

File extensions usually identify the application that can open or run them. For example, text files end with the extension .txt and are opened with Microsoft Notepad. Other common file extensions include the following:

- .doc for Microsoft Word documents
- .exe for executable files
- .htm for Web pages created in Hypertext Markup Language (HTML)
- .gif for GIF 87/89 format images, commonly used on the Internet


Options
View
File Types
Registered file types:
Active Server Document
Adobe Acrobat Document
Adobe Acrobat Forms Document
Advanced Streaming Format File
Advanced Streaming Format File
Advanced Streaming Redirector File
Advanced Streaming Redirector File
Animated Cursor
Application
New Type...
Remove
Edit...
File type details
OK
Cancel
Apply

Extension: ASP

Content Type (MIME): text/asp

Opens with: PROGRAM

File extension. *Viewing file extension mappings.*

Associations between different file extensions and the programs used to open them are stored in the registry. Sometimes you might need to modify or remove a registered file extension. For example, if two different applications save files using the same file extension, you can easily modify file extensions in Microsoft Windows by using Windows Explorer. Just select Options from the View menu to open the Options dialog box, and select the File Types dialog box. Create, remove, or edit file extensions as desired. Be aware that using this tool might negatively affect the ability of applications on your system to function, so modify extensions with care. In Windows 2000, Windows XP, and Windows .NET Server, you can do the same by selecting Folder Options from the Tools menu.

file permissions

A method for controlling access to files stored on NTFS file system (NTFS) volumes in systems running Microsoft Windows 2000 and Windows XP.

Overview

File permissions govern access to files on an NTFS volume, and folder permissions govern access to folders on an NTFS volume. There are five standard file permissions on NTFS volumes for computers running Windows 2000, Windows XP, and Windows .NET Server: Full Control, Modify, Read & Execute, Read, and Write. For any given file on an NTFS volume, each of these file permissions can be allowed or denied for a specific user or group by using the Security tab of the file's property sheet in Windows Explorer (see the illustration).


test.txt Properties
General
Security
Summary
Add...
Remove
Advanced...
OK
Cancel
Apply

Name: Everyone

Permissions:	Allow	Deny
Full control	☐	☐
Modify	☐	☐
Read & execute	☐	☐
Read	☑	☐
Write	☐	☐

☐ Allow inheritable permissions from parent to propagate to this object

File permissions. *Viewing and configuring file permissions in Windows 2000.*

Each of these five standard file permissions is made up of a subset of the individual or special file permissions that are available on NTFS volumes on machines running Windows 2000, Windows XP, and Windows .NET Server. The following table lists the various special file permissions and how they are combined to form the five different standard file permissions.

Special File Permissions

Special Permissions	***Full Control***	***Modify***	***Read & Execute***	***Read***	***Write***
Execute File	x	x	x		
Read Data	x	x	x	x	
Read Attributes	x	x	x	x	
Read Extended Attributes	x	x	x	x	
Create Files/Write Data	x	x			x
Append Data	x	x			x
Write Attributes	x	x			x
Write Extended Attributes	x	x			x
Delete Subfolders and Files	x				
Delete	x	x			
Read Permissions	x	x	x	x	x
Change Permissions	x				
Take Ownership	x				
Synchronize	x	x	x	x	x

See Also: *folder permissions*

file system

Any technology for organizing, storing, and locating data on a system or network.

Overview

The file system for a computing platform defines the method by which the operating system stores, locates, and accesses files on its hard disk subsystem. File systems usually have a hierarchical structure consisting of a series of nested directories for storing files. Each directory can contain files, other subdirectories, or both. The top of the file system is called the root, and the various directories are its branches. The file system thus forms a tree.

File systems include conventions for the type and the maximum number of characters that can be used to name a file. A file can be located in the file system by specifying its absolute path—that is, its path starting from the root and traversing through the directory structure until the file is reached. Using graphical user interface (GUI) or command-line tools, files can be located, copied, moved, and deleted. Microsoft Windows Explorer is an example of a GUI tool that shows the hierarchical structure of the file system on a Windows-based machine. File systems can incorporate technologies for marking files with attributes such as hidden and read-only. Some file systems allow you to compress files, and some allow you to specify file system quotas for users.



File system. *A hierarchical file system.*

Types

File systems can generally be classified into two types, depending on where the stored resources are located:

- **Local file systems:** These systems are part of the operating system and manage locally attached storage devices such as disk drives and removable drives. Portions of local file systems can be shared to allow users on the network to access specific files, but users generally need to know the name or location of the share in order to access it.
- **Distributed file systems:** These systems are used to combine shared portions of local file systems on many different machines into a single network-wide hierarchical file system. Distributed file systems allow shared network resources located all over the network to appear as though they are located on a single "superserver," and they simplify the process of users locating and accessing shared network resources.

Examples

Examples of common file systems include the following:

- The file allocation table (FAT) file system for MS-DOS–based and Windows-based computers
- The NTFS file system (NTFS) for Windows NT, Windows 2000, Windows XP, and Windows .NET Server
- The Distributed file system (Dfs) for Windows NT, Windows 2000, and Windows .NET Server
- The standard hierarchical UNIX file system
- Sun's distributed Network File System (NFS) for UNIX platforms

File-Transfer Access and Management (FTAM)

The Open Systems Interconnection (OSI) reference model counterpart of the Internet standard File Transfer Protocol (FTP).

Overview

The File-Transfer Access and Management (FTAM) protocol is an OSI application layer (Layer 7) protocol that specifies a standard mechanism for access and management of a distributed network file system. FTAM enables users to

- Access file stores both locally and remotely, making FTAM a distributed file access protocol more similar to Gopher in this regard than to FTP
- Integrate management of both local and remote file stores, including the ability to manipulate both files and their attributes
- Access file stores on different kinds of machines that have different types of file systems
- Transfer files both synchronously and asynchronously

The FTAM model defines the architecture of a hierarchical virtual file store in terms of file structure, file attributes, and the kinds of operations that can be performed on files and their attributes. The FTAM standard does not specify the actual user interface for file access and management, simply the system's underlying architecture. Vendors are left free to create their own user interfaces to FTAM file systems or use existing interfaces for their vendor-specific file systems. Some third-party vendors have developed FTAM-based products for Microsoft Windows NT and other operating systems, but like many aspects of the OSI model, FTAM has not caught on the way Internet protocols such as FTP have, mainly because of its complexity.

See Also: *Open Systems Interconnection (OSI) reference model*

File Transfer Protocol (FTP)

An application-level protocol that can be used for transferring files between hosts on a Transmission Control Protocol/Internet Protocol (TCP/IP) network.



File Transfer Protocol (FTP). *How FTP works.*

Overview

File Transfer Protocol (FTP) is one of the earliest Internet protocols, and it is still used for uploading and downloading files between clients and servers. An FTP client is an application that can issue FTP commands to an FTP server, and an FTP server is a service or daemon running on a server that responds to FTP commands from a client. FTP commands can be used to change directories, change transfer modes between binary and ASCII, upload files, and download files.

Implementation

FTP uses TCP for reliable network communication by establishing a session before initiating data transfer. TCP port number 21 on the FTP server listens for connection attempts from an FTP client and is used as a control port for establishing a connection between the client and server, for allowing the client to send an FTP command to the server, and for returning the server's response to the command. Once a control connection has been established, the server opens port number 20 to form a new connection with the client for transferring the actual data during uploads and downloads.

Notes

Internet Information Services (IIS) supports virtual servers and virtual directories using FTP. You can view the status of open ports on IIS using the netstat command. If an FTP client has trouble accessing information on IIS, try changing the directory listing style for the FTP service on IIS. FTP supports only Basic Authentication or anonymous access for authentication schemes and does not support the more secure Microsoft Windows NT Challenge/Response Authentication method.

See Also: *Internet Information Services (IIS), Transmission Control Protocol/Internet Protocol (TCP/IP)*

Find

A dialog box in Microsoft Windows 2000, Windows XP, and Windows .NET Server that lets you locate objects in Active Directory directory service.

Overview

The Find dialog box allows you to query the global catalog server for objects such as users, groups, computers, shared folders, printers, and other objects in Active Directory.



Find: Users, Contacts and Groups

Find: Users, Contacts and Groups

In: sales

Name: Bob

Description:

Name	Type	Description
Bob Smith	User	

1 item(s) found

Find. *Using Find in Active Directory Users And Computers.*

To use the Find dialog box, open a console with the snap-in for Active Directory Users And Computers installed, right-click on a container or organizational unit, and select Find from the shortcut menu. Then specify what kinds of objects you want to search for within Active Directory, such as

- Users, contacts, and groups
- Computers
- Printers
- Shared folders
- Directory folders
- Routers
- Custom search

Next, specify whether you want to search the entire Active Directory, a particular domain, or a particular organizational unit (OU). Finally, specify the query parameters associated with the type of object you are looking for. For example, if you are looking for users, contacts, or groups, you can specify the name of the object, its description, or specific attributes of the object, such as home phone or e-mail address.

Notes

If you are performing a search based on an attribute of an object, you must specify a value for this attribute.

finger

A Transmission Control Protocol/Internet Protocol (TCP/IP) protocol and service for viewing information about a user.

Overview

For a user on the client machine to be able to “finger” someone using finger client software, the finger daemon (service) must be running on the remote system being queried. Then if you finger a user’s e-mail address, the result returned to you typically includes the user’s username, full name, whether and how long the user has been logged on, and other information depending on the configuration of the finger service you are querying.

Microsoft Corporation’s implementation of TCP/IP on Microsoft Windows 2000, Windows XP, and Windows .NET Server has finger client software but no finger service. In other words, you can run the finger client on a machine running Windows 2000, Windows XP, or Windows .NET Server that is connected to the Internet in order to obtain results from a UNIX server at an Internet service provider (ISP) running the finger daemon. For example, typing the command **finger jsmith@ s12.microsoft.com** displays information about user Jeff Smith on a server called s12.microsoft.com.

If an ISP makes its finger daemon publicly available on the Internet, it is commonly referred to as a finger gateway.

Notes

Finger is more of a security risk than a useful service in most cases and is not widely implemented anymore. A related service that also is not used much these days is whois.

For More Information

Visit Finger Lookup, a popular Internet finger gateway, at *alabanza.com/kabacoff/Inter-Links/cgi/finger.cgi.*

See Also: *Transmission Control Protocol/Internet Protocol (TCP/IP)*

FIPS

Stands for Federal Information Processing Standard, any standard ratified by the National Institute of Standards and Technology (NIST)

See: *Federal Information Processing Standard (FIPS)*

firewall

Any system or device that allows safe network traffic to pass while restricting or denying unsafe traffic.

Overview

Firewalls are usually dedicated machines running at the gateway point between your local network and the outside world and are used to control who has access to your private corporate network from the outside—for example, over the Internet. More generally, a firewall is any system that controls communication between two networks. In today’s networking environment in which corporate networks are connected to the Internet—inviting hackers to attempt unauthorized access to valuable business information—a corporate firewall is essential.

A firewall is an essential component of a company’s security policy and is one of the primary means for enforcing that policy. A firewall acts as a kind of police officer to monitor, control, arrest, and incarcerate malicious traffic, logging all questionable traffic to allow the administrator to determine the cause or source of the attack.

Types

A corporate firewall can either be a dedicated machine such as a packet filtering router or a rack mountable firewall appliance or firewall software that the administrator must install on a dual-home hardened system. Both approaches are popular and each has its advantages and disadvantages.

A personal firewall is a firewall used to protect a single machine, typically a home user connected to the Internet using dial-up, Asymmetric Digital Subscriber Line (ADSL), or cable modem connections. The personal firewall marketplace has exploded in the last few years as broadband Internet access services have become widely deployed. Personal firewalls are usually implemented as software to be installed on users' machines, but the first personal firewall that was offered in appliance form was Firebox from WatchGuard Technologies in 1997. Personal firewalls also come preinstalled on some ADSL and cable modem routers to protect home users and Small Office/Home Office (SOHO) networks.

An offshoot of personal firewalls is the agent-based firewall. Agent-based firewalls are installed on every machine on a network, but their configuration is managed remotely using policies configured on a central policy server. At the enterprise level, this scenario is called a distributed firewall, and it is becoming a popular approach to secure servers on a network. The advantage here is that servers can be protected not just from hackers on the Internet but also from malicious users inside the corporate network. The agent also serves as an extra level of protection if the regular network firewall has been compromised. Another name for this approach is host-resident firewall, since it involves moving firewall security from the network's perimeter to the hosts themselves, a process that scales much better as perimeter traffic increases.

A new type of firewall is a combination of virtual private networking (VPN) and firewall software. This combination can be used for different purposes from enabling mobile users to connect securely to a corporate intranet over the Internet (using VPN and firewall software installed on their laptops) to enabling e-commerce sites to provide their users with secure access to their services (using rack-mounted VPN/Firewall appliances). In general, the firewall software is placed in front of (nearer the Internet) than the VPN software to simplify configuration. The main problem with this combination is that the VPN slows down access through the firewall, so a method of implementing this combination that is growing more popular is using dedicated high-performance VPN/Firewall appliances.

Finally, a different approach to implementing firewalls is outsourcing your firewall services to a Managed Firewall Service Provider (MFSP). This is becoming a popular alternative for small to mid-sized companies that cannot afford to hire trained security experts to configure, monitor, and maintain a firewall. Some analysts expect this segment of the market to grow to $1.5 billion by the end of 2002.

Architecture

In its simplest form, a firewall is a router (or dual-homed computer with two network interface cards) that filters incoming network packets. This configuration is usually called a packet-filtering router. By comparing the source addresses of these packets with an access list specifying the firewall's security policy, the router determines whether to forward the packets to their intended destinations or stop them. The firewall can simply examine the Internet Protocol (IP) address or domain name from which the packet was sent and determine whether to allow or deny the traffic. To specify a list of IP addresses which the router will permit or deny, an access control list (ACL) or access list (AL) is configured on the router. The router can filter both inbound and outbound packets.

A related form of firewall is the network-level firewall because it operates at the network layer of the Open Systems Interconnection (OSI) reference model for networking. Network-level firewalls are transparent to users and use routing technology to determine which packets are allowed to pass and which will be denied access to the private network. Network-level routers can be configured to block certain types of IP traffic while permitting others to pass. Usually this is done by disabling or enabling different Transmission Control Protocol (TCP) and User Datagram Protocol (UDP) ports on the firewall system. For example, TCP port 25 is usually left open to permit Simple Mail Transfer Protocol (SMTP) mail to travel between the private corporate network and the Internet, while other ports (such as port 23 for Telnet) might be disabled to prevent Internet users from accessing other services on corporate network servers. The difficulty with this approach is that the size of the access list for the firewall can become huge if a large number of domains or ports are blocked and a large number of exceptions are configured, and a large access list can slow down the router. Another difficulty is that some ports are dynamically assigned at random to certain services (such as remote procedure call services) on startup, so it is more difficult to configure firewalls to control access to these ports using static access lists. Network-level firewalls are sometimes known as screening routers since they screen different types of traffic, and they are usually combined with packet-filtering using access lists for better security.

Routers that employ stateful filtering maintain an internal table of allowed TCP connections and only allow incoming connections to be established if they conform to this table. Stateful filtering is an alternative to access lists and is often used to control outbound traffic and reduce the size of access lists.



Firewall. *Two basic types of firewalls.*

Another type of firewall is the circuit-level gateway, which is usually implemented as part of a proxy server. Circuit-level gateways essentially operate at a higher level of the OSI model protocol stack than network-level firewalls do. With a circuit-level gateway, connections with the private network are hidden from the remote user. The remote user connects with the firewall, and the firewall forms a separate connection with the network resource being accessed after changing the IP address of the packets being transmitted in either direction through the firewall using a process called Network Address Translation (NAT). The result is a sort of virtual circuit between the remote user and the network resource. This is a safer configuration than a packet-filtering router because the external user never sees the IP address of the internal network in the packets he or she receives, only the IP address of the firewall. A popular protocol for circuit-level gateways is the SOCKS v5 protocol. Circuit-layer gateways are typically used in conjunction with packet-filtering and network-layer protection.

Another more advanced type of firewall is the application gateway, which is also usually included in a proxy server. Application gateways do not allow any packets to pass directly between the two networks they connect. Instead, proxy applications running on the firewall computer forward requests to services on the private network and then forward responses to the originators on the unsecured public network. Application gateways generally authenticate a user's credentials before allowing access to the network, and they use auditing and logging mechanisms as part of their security policy. Application gateways generally require lots of configuration by users to enable their client machines to function properly, but they are more granular in their configurability than network-level firewalls. For example, if a File Transfer Protocol (FTP) proxy is configured on an application gateway, it can be configured to allow some FTP commands but deny others. You could also configure an SMTP proxy on an application gateway that would accept mail from the outside (without revealing internal e-mail addresses) and then forward the mail to the internal mail server. However, because of the additional processing overhead, application gateways have greater hardware requirements and are generally slower than other types of firewalls.

Other advanced features used by firewalls include

- **Execution control lists (ECLs):** These are like access lists but instead control which applications can be executed over the firewall.
- **Intrusion Detection Systems (IDSs):** Usually separate systems from firewalls but sometimes packaged with them, IDSs complement a regular firewall by allowing administrators not just to

prevent intrusion into their private networks but also to detect and analyze the source of this intrusion.

Implementation

Before looking at implementing firewalls, it is a good idea to first review some firewall terminology:

- **Host:** Any computer attached to your network.
- **Bastion host:** A host directly exposed to the Internet. Bastion hosts need to be “hardened” to make them more secure by removing nonessential services and software. Web servers and mail servers are two examples of common types of bastion hosts.
- **Perimeter network:** An extra network located between your corporate network and the Internet. Also called a DMZ, which stands for demilitarized zone.

The simplest way of implementing a firewall is to use a packet-filtering router with port screening at the junction between your private network and the Internet. All traffic flows through this point, and the router handles the entire job of securing your network from attack.

For more extensive protection than a simple packet-filtering router, install circuit-level or application-gateway firewall software on a dual-homed hardened system and use it in place of (or in addition to) the dedicated router.

A screened-host firewall allows a bastion host located on the private network to be accessed from the Internet while preventing other hosts from being compromised. This is perhaps less secure than locating the bastion host outside the private network, but it allows easier access to the bastion host for configuration and maintenance.

A screened subnet architecture employs an intermediate network (the perimeter network) between the private and public networks, each of which are connected to the perimeter network using a separate screening router. One or more bastion hosts are then located on the perimeter network. For greater protection, the perimeter network may be split into two segments using another router or a dual-homed host running firewall software. Still another configuration makes each bastion host dual-homed, with one interface of each bastion host connected to the perimeter network segment adjacent to the Internet and the other interface connected to the perimeter network segment adjacent to the private network. You can make the topology even more complex by having separate perimeter networks for each bastion host, and so on.

Advantages and Disadvantages

Although firewalls are essential for networks connected to the Internet, a firewall is only as effective as its configuration. A misconfigured firewall is worse than no firewall at all since it provides the user with a false sense of security that the network is protected. In other words, firewalls cannot configure themselves and are only as smart as the administrators configuring them.

Another misconception is that a carefully configured firewall is all your network needs to be safe from attack. This is hardly the case. Network security begins with the development of a comprehensive security policy on paper and is implemented using a variety of systems and services including firewalls, perimeter networks, antivirus software, an intrusion detection system (IDS), and good network management practices. In addition, administrators need to be on top of possible new threats by subscribing to security newsletters, watching for notices of bugs and fixes from operating system and application vendors, reviewing firewall logs regularly, and educating users about the practices of safe computing.

Marketplace

For the corporate segment of the market, firewall products range from dedicated routers to software to install on hardened dual-homed hosts. A popular dedicated router firewall product is the PIX firewall service from Cisco Systems, included with IOS 11.2 and higher as the Cisco Firewall Feature Set. PIX comes in different flavors depending on whether the need is enterprise or Small Office/Home Office (SOHO) protection, and by some analysts’ estimates is used by half of all large companies.

In the enterprise software firewall market, popular products include Firewall-1 from CheckPoint Software Technologies, Microsoft Proxy Server from Microsoft Corporation, and many others. The new Microsoft Internet Security and Acceleration (ISA) Server integrates firewall and Web caching functionality and supports policy-based security.

In the personal firewall arena, some popular products include BlackICE Defender from Network Ice Corporation, Norton Personal Firewall from Symantec Corporation, eSafe from Aladdin Networks, ZoneAlarm from Zone Labs, Secure Desktop from Sybergen Networks, McAfee Personal Firewall from Network Associates, CyberArmor from InfoExpress, and PC Firewall from ConSeal. In general, personal firewalls come with a standardized default configuration that provides a basic level of security, but remember that firewalls are only as smart as the person who configures them. Personal firewalls are also not a substitute for antivirus software and are usually ineffective in dealing with Trojan horses.

Distributed firewalls are popular in corporate environments and are typically used to protect critical servers using firewall agents that are remotely managed from a central policy server. Examples in this market include CyberArmor Enterprise Personal Firewall from Info Express and McAfee Active Virus Defense Suite from Network Associates.

Several vendors offer combinations of firewall and VPN software that can be used to provide secure remote access to corporate networks. Examples include VPN-1 Gateway (a combination of Firewall-1 and VPN-1) from CheckPoint Software, Raptor Firewall with PowerVPN from Symantec, GuardianPro with Guardian IPSec VPN from NetGuard, and eTrust Firewall with eTrust VPN from Computer Associates.

In the VPN/Firewall appliance arena, Cobalt Networks and Axent Technologies have teamed up to provide a 1U-high rack-mountable VPN/Firewall appliance called VelociRaptor that is based on the Linux operating system. Gigabit products in this market include Cisco's PIX 535 firewall and NetScreen-1000ES from NetScreen Technologies, both of which support Triple DES encryption for greater security (although using 3DES slows down performance to about 600 megabits per second [Mbps]).

In the outsourced managed firewall services sector, two popular providers include DefendNet Solutions, whose DefendNet Enterprise solution uses CheckPoint Software's Firewall-1 product and targets companies with more than 250 users, and RIPTech, whose sentry monitoring system works with several popular firewalls including PIX, Raptor, and Firewall-1. Another managed firewall service provider is NetSolve.

Notes

TruSecure, in conjunction with ICSA Labs, acts as an independent standards body that certifies firewall products and provides a number of resources on their Web site relating to firewalls and network security. See *www.icsalabs.com* for more information.

The best way to begin configuring a packet-filtering firewall is to block all packets at first and then start allowing access to the internal network on a case-by-case basis. Make sure that internal network addresses do not cross the firewall to the outside world and do not store sensitive data on the machine running the firewall software itself. Treat your firewall machine as expendable—the worst possibility should be a hacker's damage to the firewall; this would simply leave your private network securely disconnected from the outside world. You can disable all unnecessary network services on your firewall machine to protect the firewall itself from attack.

If you are concerned only about controlling outgoing access from your network and your users do not need to be able to remotely access your network over the Internet, a packet-filtering router or circuit-level gateway type of firewall is probably sufficient. For users who frequently need to remotely access your network, however, an application gateway is generally best.

See Also: *appliance, network security, proxy server, router*

FireWire

A name trademarked by Apple Computer for the IEEE 1394 High Performance Serial Bus.

Overview

FireWire (or IEEE 1394 or simply 1394) is a serial transmission specification originally proposed by Apple for connecting high-speed peripherals to computers at speeds of up to 393 megabits per second (Mbps). FireWire supports hot-swapping of peripherals with up to 63 peripherals connected to a single FireWire bus. In addition, up to 1023 buses can be interconnected to form a vast array of peripherals if needed.

FireWire features simple plug-in connectors using thin serial cables that can be hot-plugged without interfering with your system's operation. FireWire connectors are based on the Nintendo Game Boy connector.

The main competitor for PC peripheral interconnection is Universal Serial Bus (USB). Although USB is targeted mainly toward computer peripherals running at speeds up to 12 Mbps, FireWire supports much higher speeds and can transport both asynchronous data and video streams and isochronous streams.

Other vendors have their own trademarked names for IEE 1394, including Sony Corporation with its popular i.Link technology.

Implementation

FireWire as defined in IEEE 1394 uses 64-bit device addresses. FireWire cables use two twisted-pair wires for data transmission and two wires for power. FireWire includes two different serial interfaces:

- **Backplane interface:** Runs at speeds between 12.5, 25, and 50 Mbps for bus connections within a computer system
- **Point-to-point interface:** Runs at speeds of 98.304 Mbps (S100 specification), 196.608 Mbps (S200), and 393.216 Mbps (S400) for connecting devices to computers using serial cables



FireWire. *Connecting peripherals using FireWire.*

The topology of a typical FireWire implementation can be complex, but it is typically a hierarchical or tree topology consisting of various IEEE 1394 components. More complex topologies, including several computers sharing portions of the peripheral network, are also possible. The illustration shows how you can use FireWire. The four types of components you can use in a FireWire implementation are

- **Devices:** Typically have 3 ports but can have up to 27 ports and can be daisy-chained up to 16 devices
- **Splitters:** Provide extra IEEE 1394 ports if needed to accommodate the number and arrangement of devices used

- **Repeaters:** Overcome distance limitations in IEEE 1394 cables
- **Bridges:** Isolate traffic within a specific portion of an IEEE 1394 bus

FireWire connections have a maximum distance of 15 feet (4.5 meters), but up to 16 components can be daisy-chained to a maximum distance of 236 feet (72 meters) without using repeaters.

FireWire is supported by the Microsoft Windows 98, Windows 2000, and Windows XP operating systems, along with the universal serial bus (USB) specification.

Notes

Windows 98 resets the FireWire bus and assigns new physical addresses to IEEE 1394 devices when

- Devices are added or removed from the bus
- The system is rebooted

For More Information

Visit the 1394 Trade Association at *www.1394ta.org.*

See Also: *serial transmission, universal serial bus (USB)*

flapping

A problem condition that can occur with dynamic routers on large internetworks.

Overview

When a router is flapping (called a flapping router), it broadcasts routing table updates that alternate between two different routes to a host. For example, the flapping router might indicate during the first broadcast that route A is the best route to a given host, indicate during the second broadcast that route B is the best route, indicate during the following broadcast that route A is best, and so on. Flapping routers thus generate unnecessary routing traffic over the network. This generally happens when a router is unnecessarily configured to load balance between paths with equal hop counts. To determine whether a router is flapping, use a network packet sniffer.

See Also: *router*

flexible single-master operation (FSMO)

A unique set of single-master roles for domain controllers in Microsoft Windows 2000 and Windows .NET Server networks.

Overview

Although domain controllers in a Windows 2000 or Windows .NET Server network mainly function in multimaster mode in which all of them are peers, a few special domain controllers in an Active Directory directory service forest have special roles and execute these in single-master mode. These special roles are known as flexible single-master operation (FSMO) or “fizmo” roles, and there are five of them:

- **Schema Operations Master:** There is only one of these domain controllers in the entire forest, and it is the only one that can be used to create new classes or attributes for the forest schema.
- **Domain Naming Master:** There is only one of these domain controllers in the entire forest, and it manages the names of every domain within the forest and is the only domain controller that can add or remove domains to the forest.
- **PDC Emulator or PDC Operations Master:** There is one of these domain controllers in each domain, and it is used to provide backward compatibility for downlevel Windows NT backup domain controllers (BDCs) within a mixed-mode network.
- **RID Master:** There is one of these in each domain, and it manages the assignment of domain-wide security IDs (SIDs).
- **Infrastructure Master:** There is one of these in each domain, and it updates the SIDs and distinguished names (DNs) in cross-domain references to objects.

See Also: *Active Directory, domain controller*

flooding

Generally, a condition where a network is being bombarded by packets. In routing technologies, a method by which routers communicate to exchange routing table updates.

Overview

Flooding is a mechanism used by dynamic routers for exchanging routing table information with one another across an internetwork. When a router's routing table has changed, it typically floods the network with update messages to alert other routers to modify their tables too. This information is flooded so that every possible recipient router on the internetwork is notified.

The update packets broadcast by the first router are specially formed so that they are received by each subnet only once (otherwise the network could become truly flooded with such broadcasts and communications would be brought to a standstill).

See Also: *dynamic routing, routing protocol*

flow control

The mechanism by which one asynchronous device controls the rate at which it receives data from another asynchronous device.

Overview

One common type of device where flow control is implemented is the modem, the most ubiquitous of asynchronous communications devices. Flow control is also used to describe data rate control mechanisms between other devices, such as computers and attached printers, or between Channel Service Unit/Data Service Units (CSU/DSUs) and routers.



Flow control. *Different types of flow control between modems.*

Flow control is sometimes equated with handshaking, but the term *handshaking* specifically refers to flow control negotiations that take place at the beginning of a communication session, although the term *flow control* also can apply to data transmission management during an active communication session.

In asynchronous communications technologies, two basic types of flow control exist:

- **Hardware flow control:** Also known as RTS/CTS (Request To Send/Clear To Send) control, this method uses special dedicated pinning on cables to leave flow control to the modem itself. In other words, a separate hard-wired signal link (wire) that does not carry data is used to enable one modem to send stop and start messages to the other modem by raising or lowering voltage levels on this wire. Hardware flow control is used with high-speed modems that can compress data and is usually the default setting for Microsoft Windows-based software, such as HyperTerminal, that uses modems.
- **Software flow control:** Also known as XON/XOFF control, this method uses special data characters (usually Ctrl+S to stop transmission, and Ctrl+Q to resume) sent within the data stream itself to enable a local modem to signal a remote modem to stop transmitting data so that the local modem can catch up.

Software flow control is slower and less reliable than hardware flow control because a user, program, or line noise might inadvertently generate a stop signal for the remote modem. In addition, software flow control is used only for transmitting ASCII text information, not for binary data files, because the binary data might contain the Ctrl+S stop character and cause the remote modem to stop transmitting data.

See Also: *asynchronous transmission, modem*

folder permissions

A method for controlling access to folders and their files stored on NTFS file system (NTFS) volumes in systems running Microsoft Windows 2000, Windows XP, or Windows .NET Server.

Overview

Folder permissions govern access to folders on an NTFS volume, and file permissions govern access to files on an NTFS volume. NTFS volumes for computers running Windows 2000, Windows XP, or Windows .NET Server have six standard folder permissions: Full Control, Modify, Read & Execute, List Folder Contents, Read, and Write.



Name

Everyone

Permissions:	Allow	Deny
Full control	☐	☐
Modify	☑	☐
Read & execute	☑	☐
List folder contents	☑	☐
Read	☑	☐
Write	☑	☐

☐ Allow inheritable permissions from parent to propagate to this object

Folder permissions. *Configuring folder permissions in Windows 2000.*

For any given folder on an NTFS volume, each of these folder permissions can be allowed or denied for a specific user or group by using the Security tab of the folder's property sheet in Windows Explorer (see the illustration).

Each of these six standard folder permissions is made up of a subset of the individual or special permissions that are available on NTFS volumes on machines running Windows 2000, Windows XP, or Windows .NET Server. The following table lists the various special permissions and how they are combined to form the six different folder permissions.

Special Folder Permissions

Special Permissions	*Full Control*	*Modify*	*Read & Execute*	*List Folder*	*Read*	*Write*
Traverse Folder	x	x	x	x		
List Folder	x	x	x	x	x	
Read Attributes	x	x	x	x	x	
Read Extended Attributes	x	x	x	x	x	
Create Files	x	x				x
Create Folders	x	x				x
Write Attributes	x	x				x
Write Extended Attributes	x	x				x
Delete Subfolders And Files	x					
Delete	x	x				
Read Permissions	x	x	x	x	x	
Change Permissions	x					
Take Ownership	x					

Notes

The List Folder Contents and the Read & Execute Folder permissions have the same special permissions. However, Read & Execute permission is inherited by both files and folders, but List Folder Contents permission is inherited only by folders.

See Also: *file permissions*

foreign host

In a Microsoft implementation of Transmission Control Protocol/Internet Protocol (TCP/IP), any host that uses a non-Microsoft operating system.

Overview

Examples of foreign hosts on Microsoft IP internetworks might be OS/2 workstations, Solaris servers, and VMS mainframes.

Connectivity with foreign hosts for the purpose of transferring files with the host requires

- A common networking protocol, such as TCP/IP or Internetwork Packet Exchange (IPX)

- A common file-sharing protocol, such as Server Message Block (SMB) or Network File System (NFS)

See Also: *Transmission Control Protocol/Internet Protocol (TCP/IP)*

foreign mail system

A mail system that belongs to a different company than your own and that might also be of a different type.

Overview

In Microsoft messaging terminology, the term *foreign mail system* usually refers to a mail system other than Microsoft Exchange Server. An example of a foreign mail system could be a public X.400 messaging system in Europe or the Internet's Simple Mail Transfer Protocol (SMTP) mail system. You can establish connectivity between an Exchange organization and a foreign mail system by installing and configuring an appropriate connector on an Exchange server in your organization. Examples include

- Using the Internet Mail Service to connect an Exchange organization to the SMTP mail system on the Internet
- Using the X.400 Connector to connect an Exchange organization to a public X.400 messaging network such as those common in Europe

See Also: *Exchange Server, X.400*

forest

Also called a domain forest, a logical structure formed by combining two or more Microsoft Windows 2000 or Windows .NET Server Active Directory directory service trees. The trees within a forest are usually organized as peers and are connected by two-way transitive trust relationships that span across the root domains of each tree. All trees within a forest share a common schema and Global Catalog.

See: *domain forest*

form

A feature of Hypertext Markup Language (HTML) that allows users to submit information to Web servers using Web browsers.

Overview

A form is a portion of a Web page that presents a series of fields for the Web browser user to complete, along with a Submit button to send the data to the Web server for processing. Forms are often used in Web sites for guest books, registration, and similar purposes. If you create an HTML form, you must create a corresponding form handler—an application that accepts the data from the form and processes it accordingly. Form handlers are typically written in Perl and implemented as Common Gateway Interface (CGI) scripts on UNIX Web server platforms such as Apache. On Internet Information Services (IIS), form handlers can be Internet Server API (ISAPI) applications written in C or Active Server Pages (ASP) scripts written in Microsoft Visual Basic, Scripting Edition (VBScript).

See Also: *Hypertext Markup Language (HTML)*

forwarder

A name server configured to perform iterative queries with other name servers on the Internet.

Overview

If one of your name servers is configured as a forwarder, all off-site queries for resolving Domain Name System (DNS) names are first sent to the forwarder. The forwarder then performs an iterative query with an off-site name server located at your Internet service provider (ISP) to resolve the query. The results of the query are cached by the forwarder. This caching of name query results by the forwarder speeds later name query requests and reduces traffic between your network and the ISP.



Forwarder. *How a forwarder resolves a DNS name lookup.*

Uses

Forwarders are useful for reducing name resolution traffic and speeding Domain Name System (DNS) name queries for large private Transmission Control Protocol/Internet Protocol (TCP/IP) internetworks that are connected to the Internet. They are also used to resolve name queries when a firewall between your network and the Internet prevents clients in your network from directly querying name servers located at your ISP or elsewhere on the Internet. In this case, a typical location for the forwarder is on the bastion host. (The bastion host is the host running the proxy server or application layer gateway application.)

See Also: *Domain Name System (DNS), name server*

FORTEZZA

A card-based system of cryptographic authentication.

Overview

FORTEZZA was developed by the National Security Agency (NSA) as a way of providing secure authentication to computer systems and services. FORTEZZA functions similarly to smart cards but has greater processing power and memory. The format for a FORTEZZA card is industry-standard Personal Computer Memory Card International Association (PCMCIA) interface, commonly used in laptop computers.

FORTEZZA cards are token-based authentication systems that are tamper-resistant and that protect the data stored on them using cryptography. FORTEZZA is supported by Microsoft Internet Explorer in Microsoft Windows 2000 and Windows XP to control secure Web communications.

You can obtain FORTEZZA card systems from a variety of vendors approved by the NSA. One such vendor is Litronic, which offers a variety of FORTEZZA products and services.

See Also: *cryptography, encryption, smart card*

FPNW

Stands for File and Print Services for NetWare, a Microsoft Windows NT and Windows 2000 add-on utility for providing Internetwork Packet Exchange (IPX) file and print services to NetWare clients.

See: *File and Print Services for NetWare (FPNW)*

FQDN

Stands for fully qualified domain name; in the Domain Name System (DNS), a dotted name that fully identifies a Transmission Control Protocol/Internet Protocol (TCP/IP) host on the Internet.

See: *fully qualified domain name (FQDN)*

fractional T1

A T-carrier digital circuit with a speed of less than 1.544 megabits per second (Mbps).

Overview
A fractional T1 line is a T1 line, leased by a T-carrier service provider to a customer, that carries only a fraction of the regular T1 bandwidth of 1.544 Mbps. Regular T1 lines consist of 24 DS0 channels multiplexed together, but fractional T1 lines consist of fewer than 24 channels. Fractional T1 lines typically consist of a combination of nailed-up channels and switched channels. The technology of fractional T-carrier services is the same as that of regular T-carrier services; the extra channels are simply unused. Customers might want to lease fractional T1 services when they do not require the entire bandwidth (or cost) of a regular T1 line.

See Also: *T-carrier*

FRAD
Stands for Frame Relay Access Device, a telecommunications device that enables a customer site to be connected to a telco's frame relay services.

See: *Frame Relay Access Device (FRAD)*

frame
A segment of data transmitted over a network or telecommunications link.

Overview
Frames are assembled and generated by the data-link layer and physical layer of the Open Systems Interconnection (OSI) reference model. This assembly process is called framing. In other words, packets from the network layer are encapsulated by the data-link layer into frames. Data segments generated by higher layers of the OSI model are generally referred to as packets, but the term *packet* is also sometimes used to include frames.

Architecture
A frame generally consists of a header with preamble (start of frame flag), destination and source addresses, data payload, and usually some form of error-checking information. Frames can be fixed-length or variable-length and have addressing information for multipoint connections or no addressing information for point-to-point connections. They can also have error correction, as in X.25, or no error correction, as in frame relay.

The format in which data frames are constructed depends on the particular data-link layer protocol being used. Thus, we can speak of Ethernet frames, Integrated Services Digital Network (ISDN) frames, X.25 frames, frame relay frames, and so on. Each particular local area network (LAN) or wide area network (WAN) data-link protocol has its own method of framing data for transmission over the network or telecommunications line.

See Also: *Ethernet, frame relay, Integrated Services Digital Network (ISDN), X.25*

frame relay
A high-speed packet-switching service offered by telcos and long-distance carriers and used primarily for corporate wide area network (WAN) links.

Overview
Frame relay technology is a packet-switching service with transmission speeds ranging from 56 kilobits per second (Kbps) for DS-0 or ISDN, to 1.544 Mbps for DS-1 or T1, and even sometimes to 45 Mbps for DS-3 or T3. Frame relay is independent of network-level protocols and can thus carry network traffic of all types, including Transmission Control Protocol/Internet Protocol (TCP/IP), Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX), AppleTalk, DECnet, and Systems Network Architecture (SNA).

Frame relay offers both guaranteed bandwidth necessary for most client/server communications and also accommodates "bursty" traffic when demand for bandwidth suddenly increases, as when a file transfer occurs. Because of these features, frame relay has been a popular solution in the enterprise to connect remote branch offices over frame relay WAN links to corporate headquarters.

Frame relay services are available from all major carriers and Regional Bell Operating Companies (RBOCs).

History

The standardization process for frame relay began in the late 1980s, but it was not until the start of the 1990s that commercial frame relay services began to be available from major telecommunications carriers. The impetus for frame relay originally came from Integrated Services Digital Network (ISDN) technologies—in fact the data-link layer of frame relay is Link Access Protocol-D (LAPD) and is borrowed directly from ISDN.

Frame relay is similar in operation to X.25, an earlier CCITT packet-switching technology from which it also evolved. Frame relay, however, is a more streamlined protocol that has lower latency and thus better performance than X.25. This improvement is possible because frame relay is transmitted over digital lines as opposed to analog lines for X.25. Since analog lines are "noisy," X.25 required additional protocol overhead for handling error correction and retransmission of bad packets. By contrast, the digital lines used by frame relay have very little noise, with the result that the error correction and retransmission functions can be moved from the protocol itself to the end stations. This results in much lower latency and hence faster transmission in frame relay than in X.25. Frame relay also does not support the hop-by-hop flow control functions that X.25 supports, which further streamlines the operation of frame relay.

Frame relay services were first offered in 1992 as a faster alternative to X.25 by AT&T, Sprint, and other long-distance carriers. These carriers established POPs (points of presence) major metropolitan locations to provide a means of connecting customers to frame relay services. Frame relay is now a popular solution for building corporate WANs and is available from Incumbent Local Exchange Carrier (ILECs), Competitive Local Exchange Carrier (CLECs), RBOCs, and European Post, Telephone, and Telegraph (PTT) companies all around the world.

Uses

Frame relay is primarily used for connecting corporate local area networks (LANs) into a WAN. In the early 1990s, WAN links were mainly used for batch transfers between remote offices and mainframes at corporate headquarters. For this scenario, frame relay was ideal since companies only accrued charges when the service was actually being used—in between batch transfers, no charges were incurred. With the rise of client/server computing, frame relay remained the best alternative to more expensive leased lines for WAN links between remote offices, and frame relay is today the most popular and widely deployed carrier service for such WAN links.

Most corporate frame relay WAN links use T1 circuits and carry data at rates between 64 kilobytes per second (Kbps) and 1.544 Mbps, with 256 and 512 Kbps being typical values. Until a few years ago, these values sufficed for most remote branch connectivity solutions, but with the explosion of the Internet the bandwidth requirements for corporate WAN links have risen. There are a number of solutions for providing frame relay links beyond T1 speeds (1.5434 Mbps), including

- **Bonding:** This method allows a maximum of two T1 circuits to be joined together to provide 3 Mbps throughput.
- **Multiplexing:** This method allows many DS-1 (another name for T1) circuits to be joined together to provide NxDS-1 frame relay at speeds from 3 Mbps upward. In this scenario the first DS-1 circuit functions as the management circuit for the entire multiplexed group of circuits—if this circuit goes down, connections are broken. Routers with V.35 interfaces support multiplexing of up to about 6 DS-1 circuits, beyond that routers having a faster High-Speed Serial Interface (HSSI) are required.
- **Channelized DS-3:** Multiplexing a large number of DS-1 circuits can be costly. Instead, a single DS-3 (that is T-3) circuit can be "channelized" to provide fractional DS-3—that is, only a portion of the 45 Mbps that a full DS-3 circuit can provide. Implementing channelized DS-3 for frame relay usually requires specialized equipment such as an M13 (DS-1 to DS-3 multiplexer).

- **Full DS-3:** This is the heavy hitter of frame relay services and involves deploying a T-3 circuit to connect a “big iron” frame relay router at your Customer Premises Equipment (CPE) to the carrier. Only a few carriers provide full DS-3 frame relay services.

Architecture

Frame relay is a connection-oriented service similar to X.25 and Asynchronous Transfer Mode (ATM). Frame relay differs from X.25 mainly in eliminating the complex layer-3 error detection and retransmission mechanisms of X.25. Frame relay is thus a simple layer-2 or data-link layer technology that is simple, fast, and independent of higher protocol layers. Although X.25 defines explicit processes for error correction, acknowledgements, packet sequencing, and so forth, in frame relay these functions are handled by the frame relay devices themselves, giving frame relay connections a much lower latency than X.25 connections. In fact, the protocol overhead for frame relay is only about 2 percent compared to almost 50 percent for X.25.

Frame relay is sometimes classified as an “unreliable” service because it performs no error checking or retransmission—if frames become corrupted or delayed by network congestion, they are silently dropped. To make frame relay a reliable service is the responsibility of the frame relay equipment at the ends of the connection, which performs error checking and retransmission and provides flow control.

A carrier’s frame relay network is typically depicted as a “cloud” of connections. This cloud is better known as a Frame Relay Bearer Service (FRBS) and physically consists of the collection of ATM/ Synchronous Optical Network (SONET) trunk lines and switches owned by the carrier. As in other packet-switching networks, frame relay operates by packaging network data into “packets” and tagging each packet with address information (discussed below). In frame relay these packets are called frames and are variable length in nature with payload up to 4 kilobytes (KB), making them especially suitable for carrying network traffic such as Internet Protocol (IP) traffic since entire IP packets can be packaged within individual frames without the need to fragment the packets.

Once frames are transmitted onto the FRBS, they are relayed through the switching nodes that make up the FRBS. Instead of relaying each frame individually, frame relay uses virtual circuits (VCs) that act as logical paths through the carrier cloud. These virtual circuits can be either switched virtual circuits (SVCs) that are set up and torn down on a call-by-call basis or permanent virtual circuits (PVCs) that are established in advance. PVCs are generally preferred because they provide a more reliable grade of service for the customer. PVCs provide dedicated point-to-point connections between local and remote customer premises through the cloud. The particular virtual circuit to which a frame belongs is determined by the frame’s address information or Data Link Connection Identifier (DLCI), a 10-bit binary value that identifies the frame to the carrier switches within the FRBS. The DLCI is a logical value that uniquely identifies the two end points of the virtual circuit.

Frame relay lets you establish multiple PVCs (and hence multiple logical WAN links) over one physical frame relay connection using statistical time-division multiplexing (STDM). You manage frame relay PVCs using the Local Management Interface (LMI) protocol, which provides features for verifying link integrity and managing the status of PVCs. Frame relay PVCs provide customers with services similar to those of dedicated leased lines such as T1 lines, but since frame relay PVCs are software-implemented instead of hardware-implemented on carrier switches, frame relay is faster and easier to provision and costs less than leased lines.

There are two ways of connecting to a frame relay network:

- **UNI:** Stands for User-Network Interface, this is a signaling method for connecting data terminal equipment (DTE) to an FRBS.
- **NNI:** Stands for Network-Network Interface, this is a signaling method for connecting trunk lines together from two different FRBSs (clouds belonging to different carriers).

Frame relay provides customers with a predefined level of service called the Committed Information Rate (CIR) that is agreed upon by the carrier and customer in advance. CIR is a negotiated level of service you purchase from the carrier that specifies the guaranteed minimum throughput for your frame relay connection. CIR acts as a kind of bandwidth throttling mechanism that facilitates the use of shared frame relay circuits by different users and prevents carriers from oversubscribing their services. Frame relay also allows temporary bursts of traffic to greatly exceed the CIR, thus providing bandwidth-on-demand for customer applications that require it. Bursts of traffic above the CIR are generally short (less than two seconds in duration) and are possible only during off-peak utilization times. When access to the service provider's frame relay network is heavy, your maximum bandwidth will generally be your CIR. Traffic above a higher service level called the Committed Burst Rate (CBR) is flagged as expendable and is dropped if the network is too busy to carry it.

Frame relay is capable of encapsulating IP traffic for transmission over a FRBS. The encapsulation of IP packets by frame relay frames is performed using the High-level Data Link Control (HDLC) protocol described in RFC 2427.

Implementation

The physical layer or Layer 1 for frame relay is the same as ISDN and T-carrier services, and as a result end stations are typically connected to a carrier's frame relay services using T1 or T3 circuits. Frame relay connections can thus be established using any customer premises equipment (CPE) that supports T-carrier services, including many bridges, routers, and switches. Alternatively, a dedicated frame relay device called a FRAD (Frame Relay Access Device) can be installed at the customer premises to connect the customer's network to an Edge Switch (ES) on the carrier side. Most frame relay–capable routers can be configured to operate either as customer-side or carrier-side equipment, but carriers themselves use special "big iron" routers and switches for establishing their cloud of frame relay circuits.



Frame relay. *A typical frame relay WAN link.*

To set up WAN links between several of your company's locations using frame relay, you typically lease the following services and equipment for each location:

- A FRAD or some other device, such as a Cisco router, that is capable of supporting frame relay connections. The FRAD at your customer premises is the data terminal equipment (DTE) side of the connection, and the frame relay/ATM switch at the telco end represents the data circuit-terminating equipment (DCE) end of the connection. Your CPE FRAD is usually connected to your network's backbone switch or router using an RS232, V.35, or X.21 serial interface.

- A T1 circuit to connect the FRAD to the carrier network. Even though you may only want to provision a 256 Kbps frame relay link, most carriers require you to purchase a full 1.544 Mbps T1 circuit to do this instead of a fractional T1 circuit.
- The required number of virtual circuits to support the number of WAN links you need and the speeds they require. Although frame relay intrinsically supports SVCs, few carriers offer this option because it is more expensive and complicated to implement and more complex for billing purposes than PVCs. A single frame relay physical port can have multiple PVCs configured on it.
- The CIR required for each of your WAN links to guarantee the necessary bandwidth for your applications to function optimally over these links. Choose a CIR that is just sufficient to handle your needs to minimize costs, because the higher the CIR, the greater the cost.

If you have more than two remote networks to connect using frame relay WAN links, you have to decide on the topology you want the carrier to provide for you. Frame relay implementations usually follow one of two networking topologies:

- **Fully meshed topology:** In this implementation, each remote location with a FRAD is connected to every other location with a FRAD using PVCs to form a fully meshed multipoint WAN. When an update is transmitted to one device, it is seen by every other device as well. The advantages of this configuration are the redundancy provided within a multipoint mesh network and that the entire frame relay network can be treated as a single data-link connection. The disadvantage is that the number of PVCs needed grows exponentially with the number of locations, and frame relay carriers usually charge per PVC. So this is not really a good solution for more than three remote locations.
- **Partially meshed topology:** This implementation uses a hub-and-spoke topology in which FRADs at branch offices (spokes) are connected by point-to-point connections to the FRAD at the head office (hub). There is no redundancy in this scenario, so typically redundancy is added by providing backup dial-up ISDN links between branch offices and headquarters in case a frame relay link goes down. This scenario must be carefully implemented to avoid split-horizon problems (routing loops).

Advantages and Disadvantages

Frame relay has several advantages over X.25 that has led to the almost complete demise of the earlier technology and its being superseded in the 1990s by frame relay. These advantages include low protocol overhead, low latency, and easy integration with ATM. Originally, when frame relay was developed in 1992, some observers thought that it would soon be superseded by Switched Multimegabit Data Services (SMDS), a packet-switched service that operates at faster speeds than frame relay and does not use PVCs. But apart from MCI Worldcom, few other carriers decided to provision SMDS and instead offer ATM as their top-speed WAN service. If we think of X.25 as the first generation of wide-area packet-switching carrier services, then frame relay is second generation (2G) and ATM is third generation (3G). Although many industry observers expected frame relay itself to be superseded by ATM for WAN connections, this has not occurred, mainly due to the complexity of implementing ATM. Frame relay has also superseded Digital Data Services (DDS), another early WAN service provided by carriers in the early 1990s.

Frame relay also has advantages over dedicated leased line services such as ISDN and T-carrier services. In general, frame relay is less than half the cost of leased lines of equivalent throughput, and, unlike some leased line services, frame relay’s cost is independent of distance. Frame relay PVCs are also easier to provision and can be configured more quickly than ISDN or T1 lines. Because frame relay provides bandwidth-on-demand and is charged the same way as regular long-distance services (that is, by usage), using it for WAN links can result in considerable cost savings over leased lines, which rack up charges even when not in use. Finally, frame relay only requires a single router or FRAD at each remote site, even in a fully redundant mesh topology, but deploying multiple leased lines at a site requires additional CPE for each line, incurring further cost and adding management headaches.

The many advantages of frame relay ensure its continued survival in the jungle of today's WAN marketplace. Frame relay is simple in concept and in implementation, has established itself as a reliable solution, has an easy-to-understand pricing structure, is cheaper than other comparable services, supports up to 1024 virtual circuits per WAN to meet the needs of even the largest enterprise, is offered by carriers around the world, and has the intrinsic security of point-to-point connections. The only real challenge to its dominance in the WAN is from upstart Digital Subscriber Line (DSL) coupled with IP VPN (virtual private network) technology, which is discussed later in this article.

Marketplace

The three largest providers of nationwide frame relay services in the United States are the Big Three long distance carriers—AT&T, Sprint Corporation, and MCI Worldcom. Sprint, in fact, was the first carrier to offer CIR for its frame relay subscribers, something that is now universally available. AT&T and Sprint between them have more than 1500 POPs nationwide, which provide good coverage for large enterprises using frame relay for their WAN service. Various RBOCs such as BellSouth Corporation, Bell Atlantic/GTE, and Qwest/US West also provide frame relay services, but with fewer POPs and covering specific geographical regions. Other providers of frame relay services include CLECs such as Intermedia Communications and WinStar Communications.

Although most carriers offer DS-1 frame relay services with CIR up to 1.544 Mbps, enterprises that need higher speeds for frame relay WAN links are more limited in their choice of providers. BellSouth now offers an NxDS-1 frame relay service called Subrate T3 that lets customers choose various frame relay rates between 2xT1 bonding (3 Mbps) and full T3 (45 Mbps). Instead of using a traditional conditioned copper T1 circuit at the customer premises, customers implementing this new service use a fiber T3 circuit, which allows them to upgrade to full T3 if eventually required. A few other carriers offer similar NxDS-1 frame relay services and fewer still offer full DS-3 frame relay. For the few customers requiring speeds higher than DS-3 (45 Mbps) for WAN connectivity, ATM can be used instead of frame relay. If a company has a mix of frame relay and ATM in its WAN, it must choose one of two methods for making these technologies interoperate: FRF.5, which tunnels frame relay over ATM, or FRF.8, which translates frame relay frames into ATM cells. An alternative to ATM for high-speed WAN connectivity that is just starting to emerge is Optical Ethernet, offered by carriers such as Yipes, which can provide Gigabit Ethernet (GbE) to the door WAN services. This is an attractive development that may shake the market up considerably in the next few years, but frame relay and ATM still reign supreme in the international arena and for long-haul WAN links.

The prohibitive costs of building a fully meshed frame relay topology for companies with multiple locations has recently been surmounted by a new service offered from AT&T called IP-enabled Frame Relay (IPFR) and a similar service from MCI WorldCom called Business Class IP. In these new scenarios, each branch office is connected to the carrier's frame relay cloud using a single PVC as in a normal hub-and-spoke implementation. However, each frame is tagged using Cisco Systems' proprietary Multi-Protocol Label Switching (MPLS) technology, which allows traffic to be routed across the cloud using destination IP addresses instead of virtual circuit identifiers. The result is the equivalent of a VPN in an IP network. In a hub-and-spoke network, each frame is first sent to the head office FRAD and then forwarded to the appropriate branch office LAN; in the MPLS scenario, however, frames can be routed directly to their destination LAN. All the switching is done by the carrier's core network (usually ATM), which relieves the FRADs of the additional processing they would otherwise need to do in a normal full-mesh network with multiple PVCs at each site.

Although frame relay supports the capability of billing customers according to usage, most providers bill at flat rates based on the number of frame relay ports, number of virtual circuits, and CIR.

Prospects

Frame relay, despite rumors to the contrary, is still on the rise. Industry analysts predict the frame relay market will be $6 billion in 2002, and this is expected to double over the next five years.

Although costs for leased lines in North America have fallen somewhat in recent years, frame relay still provides equivalent services for WAN connectivity for about half the cost as leased lines. In Europe, prices for leased lines have fallen much more sharply than in the United States, and frame relay is considered to be on a par with leased lines there. In the Asia/Pacific region, however, leased lines are still expensive and most companies use frame relay for linking their regional offices to U.S. offices.

The biggest challenge to frame relay is DSL services now being offered by telcos. DSL can provide frame relay speeds for rock-bottom costs of $50 a month or less. However, DSL is not seen yet to have the same reliability as frame relay, and although widely deployed for residential Internet access, it is not seen by most enterprises as ready for prime-time WAN links that carry mission-critical business traffic. Most DSL deployments involve the cooperation of several parties including CLECs, ILECs, and Internet service providers (ISPs). As a result, when DSL goes wrong, it can take weeks or even months to troubleshoot, with everyone pointing fingers at one another. With frame relay, however, the customer only needs to deal with one provider, or two if User-to-Network Implementation (UNI) services are provided since Network-to-Network Implementation (NNI) services are provisioned directly from the carrier. This makes both provisioning and troubleshooting of frame relay links a snap compared to DSL. Another advantage of frame relay in the WAN is security—frame relay links are point-to-point connections that cannot be hijacked or pirated. By contrast, for companies to use DSL in the WAN, they need to deploy a VPN over the connection to make it secure. Because of all these issues, frame relay is expected to remain a strong player in the corporate WAN marketplace for the next 5 to 10 years until an alternative technology such as DSL makes a compelling case for enterprises to migrate.

Being a packet-switching service, frame relay is inherently poor at carrying delay-sensitive traffic such as voice and video (frame relay was originally designed for carrying data only). Nevertheless, recent advances have led to the provisioning of Voice over Frame Relay (VoFR) services by some carriers, and it remains to be seen how these services will evolve in the marketplace.

Notes

The following table shows some possible strategies for troubleshooting frame relay links in different kinds of situations.

Troubleshooting Frame Relay Links

Problem	*Suggestions*
Frame relay link is down (connections fail)	Check cabling and connections, make sure you are using a data terminal equipment (DTE) cable, try connecting the cable to a different port, or try a different cable. Make sure you are using Internet Engineering Task Force (IETF) encapsulating if mixing frame relay devices from different vendors.
Cannot ping remote router	Check the status of PVC; contact carrier if this is down. Check the router's access list, disable access list, and retry. Make sure you are using IETF encapsulating if mixing frame relay devices from different vendors. Check the configuration of the frame relay address map.
Cannot ping device on remote network	Try pinging local router's frame relay address; check that a default gateway is specified. Check for split horizon conditions in a hub-and-spoke frame relay implementation.

For More Information

Visit the Frame Relay Forum at *www.frforum.com.*

See Also: *Asynchronous Transfer Mode (ATM), DS-0, DS-1, DS-3, Frame Relay Access Device (FRAD), Integrated Services Digital Network (ISDN), Switched Multimegabit Data Services (SMDS), T-carrier, wide area network (WAN), X.25*

Frame Relay Access Device (FRAD)

A telecommunications device that enables a customer site to be connected to a telco's frame relay services.

Overview

A Frame Relay Access Device (FRAD) is a device that accepts data packets from the customer's network and encapsulates them into a format acceptable for transmission over a T-carrier circuit to a telco's frame relay network. Some FRADs can also statistically multiplex several frame relay virtual circuits (logical data streams) into a single physical communication circuit to support fully meshed frame relay wide area networks (WANs). Statistical multiplexing enables FRADs to provide customers with greater flexibility in bandwidth use, in contrast to time-division multiplexing (TDM) techniques, which ensure a full level of service for each data stream, even when they carry no data. For example, if two data streams are multiplexed using TDM, frames from the two streams will alternate to form the single serial data link. If one of these streams has no data, empty frames will still be sent, resulting in a poor utilization of bandwidth. In statistical multiplexing, the multiplexed data stream contains only frames from data streams that are carrying data, and the higher the data transmission rate of a stream, the greater the number of frames that are multiplexed into the serial data link.

Implementation

A FRAD is typically connected to a bridge, router, or switch attached to your network backbone (some FRADs also have built-in switching and routing capabilities, too). The FRAD accepts network packets, buffers and frames them, and then transmits them over a T1 or T3 circuit to an Asynchronous Transfer Mode (ATM)/frame relay switch at the telco central office (CO).

The FRAD at the customer premises end is the data terminal equipment (DTE) end of the WAN link and typically connects to a router or switch on the customer's backbone network using a serial interface such as RS-232, X.21, or V.35. The switch at the CO end represents the data circuit-terminating equipment (DCE) end of the link and often interfaces directly to the telco's ATM trunk line network.

Some bridges and routers, such as many of those from Cisco Systems, have built-in FRAD technology and need to be connected only to a CSU/DSU (Channel Service Unit/Data Service Unit) through a V.35 or other serial transmission cable to provide customers with an all-in-one frame relay access solution for wide area networking. Use a bridge if you want an easy way to connect a branch office using frame relay. Use a router if you want to control traffic flow or reroute failed connections.

Marketplace

FRADs come in all shapes and sizes from networking vendors and often are described as switches, routers, or access devices instead of FRADs. The reason is that these devices tend to be able to perform several functions, and different vendors classify these functions differently.

Two popular FRADs in enterprise networks are the Netperformer SDM-8200 from ACT Networks and Cisco's 2600 series routers. 3Com Corporation, Openroute Networks, Motorola ING, Fastcomm Communications, IBM, Alcatel, and many other vendors also sell FRADs.

Notes

Sometimes called a Frame Relay Assembler/Disassembler.

See Also: *Asynchronous Transfer Mode (ATM), data communications equipment (DCE), data terminal equipment (DTE), frame relay*

frame relay cloud

The totality of frame relay circuits within a telecommunication carrier's frame relay network.

Overview

A carrier's frame relay network is commonly known as a frame relay cloud, but the more technically correct term is Frame Relay Bearer Service (FRBS). Typically, a frame relay cloud is a collection of packet-switching devices owned by the carrier and used as a shared public network for backboning wide area network (WAN) traffic for private customers. Frame relay clouds can also consist of frame relay circuits owned by private networking consortiums. The frame relay network is described as a "cloud" because of the large number of interconnections between the various edge switches, usually forming a fully connected mesh topology. In frame relay services, each frame of information contains the routing information needed to enable the frame to be routed to its destination through the cloud.

See Also: *frame relay*

frame tagging

A method developed by Cisco Systems for building multiswitch virtual local area networks (VLANs).

Overview

A VLAN consists of a collection of ports on an Ethernet switch that acts as if it were a separate LAN from the remaining ports. In other words, you can segment a network into several VLANs using only one Ethernet switch to create smaller broadcast domains.

Frame tagging is a mechanism developed by Cisco to identify which VLAN a packet belongs to. Frame tagging encapsulates a packet into a frame containing the VLAN ID of the packet. When a tagged packet leaves the switch and arrives at another switch, the second switch can determine which VLAN the packet belongs to and switch it accordingly. The result is that frame tagging can be used to build VLANs that span more than one switch, and the process is scalable to the enterprise level.

Frame tagging is implemented in Cisco Catalyst switches and is widely used for building enterprise VLANs.

See Also: *Ethernet switch, virtual LAN (VLAN)*

frame type

Specifies the data format for frames when using the NWLink IPX/SPX-Compatible Transport on machines running Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Overview

Two machines on a network using NWLink must be using the same frame type to communicate. NWLink on Windows 2000, Windows XP, and Windows .NET Server can listen to Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX) traffic on the network and automatically configure itself to use the network frame type, which is usually

- 802.3 for NetWare 2.2 through 3.11
- 802.2 for NetWare 3.12 and later

The following table shows the frame types supported by NWLink.

Supported NWLink Frame Types

Network Topology	*Frame Types Supported*				
	Ethernet II	802.2	802.3	SNAP	802.5
Ethernet	x	x	x	x	
Token Ring				x	x
FDDI		x		x	

Notes

NWLink on Windows 2000 Server and Windows .NET Server lets you configure multiple frame types if needed, but if multiple frame types are detected where one of them is 802.2, then the 802.2 frame type will be selected by default. NWLink on Windows 2000 Professional and Windows XP Professional can be configured for multiple frame types only by editing the registry.

See Also: *NWLink IPX/SPX-Compatible Transport (NWLink)*

Free Space Optics (FSO)

The transmission of data through free space using lasers.

Overview

Free Space Optics (FSO) was conceived 20 years ago when fiber-optic technology was still in its infancy. The promise of FSO has only begun to be commercially realized, however, in the last couple of years.

FSO sends data using modulated laser beams through the air without wires or cables. It can be used to connect networks together and to link networks to high-speed wide area network (WAN) services provided by carriers. It can work with any networking architecture but is most commonly used to transport Internet Protocol (IP) packets. It is fundamentally similar to microwave communications but operates in the terahertz frequency range of infrared and visible light.

Implementation

FSO is a line-of-site (LOS) technology that supports point-to-point, multipoint, and fully meshed networking topologies. Point-to-point connections enable data to be carried up to gigabit speeds over distances of several miles. Multipoint connections tend to be lower in speed, but fully meshed topologies can provide a measure of fault tolerance and resiliency in case of link failure.

Advantages and Disadvantages

The main advantage of FSO over traditional fiber networking is that it is cheaper and easier to deploy. The cost of laying new fiber from a telco central office (CO) to a customer's building can run in the hundreds of thousands of dollars, and it takes weeks or months to be provisioned. By contrast, a point-to-point FSO link can be established between two buildings in a matter of days and for a fraction of the cost.

Since FSO operates in an unregulated portion of the frequency band, no additional licensing costs are required to implement the technology. This cost savings can be passed down to customers, making FSO an attractive alternative to fiber. A factor in favor of FSO deployment is that some analysts estimate that 90 percent of buildings in the United States do not yet have fiber deployed to them by carriers.

On the negative side, FSO has some issues associated with its deployment and usage. Since it is a line of sight technology, interference from buildings, airplanes, birds, and weather can interrupt service, reducing FSO's reliability to well under the 99.999 percent rating of conventional fiber-based carrier services. Often the best solution for FSO providers is to establish a backup network to handle these situations, and a typical such network would be a set of point-to-point microwave links (microwaves can be affected by rain but are impervious to the fog and pollution that can interfere with FSO transmissions).

Another issue is that the buildings on which FSO transceivers are mounted tend to sway in the wind and even change size and shape with the seasons, making it complex to align FSO transmissions accurately. Obtaining rooftop right-of-way to deploy FSO equipment often proves costly, but some vendors have reacted by producing transceivers that can be mounted inside offices and transmit their laser beams through windows.

There is also the issue of public perception of safety hazards associated with FSO, namely of having invisible laser beams running all over the place. Although FSO transceivers typically generate less intensity than a laser pointer, safety is still considered an issue of public import and the U.S. Food and Drug Administration (FDA) will probably set specific guidelines in this area.

Marketplace

The number of vendors and service providers offering FSO has been exploding recently. Some of the vendors offering FSO equipment include AirFiber, LightPointe, Terabeam Corporation, and many others.

Service providers Tellaire and Broadband Highway also offer metropolitan area networking (MAN) services in a number of major cities across the United States.

See Also: *fiber-optic cabling*

Frequency Division Multiple Access (FDMA)

The signal multiplexing technology used in the AMPS (Advanced Mobile Phone Service) cellular phone system.

Overview

Frequency Division Multiple Access (FDMA) is one of three methods used for allocating channels to users over the shared wireless communications medium in cellular phone communication; the others are Time Division Multiple Access (TDMA) and Code Division Multiple Access (CDMA). FDMA is the oldest of these methods and is used in the analog AMPS cellular phone system still widely deployed throughout the United States and some other parts of the world. FDMA is also used by traditional AM and FM radio bands to allow broadcast by individual stations and by the CT2 communications system used for cordless telephone systems.

Implementation

FDMA is based on frequency-division multiplexing (FDM) and is implemented at the media access control (MAC) layer of the data-link layer in the Open Systems Interconnection (OSI) reference model. One way to understand FDMA is to imagine different people in the same room communicating in voices with different pitches, some high and some low; they'd all be able to talk simultaneously and (more or less) understand one another.



Frequency Division Multiple Access (FDMA). *How FDMA works.*

In the AMPS cellular system that is based on FDMA, each user is assigned a specific channel (frequency band) in the allotted electromagnetic spectrum, and during a call that user is the only one who has the right to access the specific band. These frequency bands are allocated from the electromagnetic spectrum as follows:

- **Transmission by mobile station:** 824 megahertz (MHz) to 849 MHz
- **Transmission by base station:** 869 MHz to 894 MHz

Two different frequency bands are used to allow full-duplex communication between base and mobile stations. Both of these bands are then divided into discrete channels that are 30 kilohertz (kHz) wide in bandwidth.

Advantages and Disadvantages

One disadvantage of FDMA is that only one subscriber can be assigned at a time to a particular channel within a cell. Once the channel is allocated, it remains the possession of the subscriber until the call is terminated or the subscriber roams outside the cell.

See Also: *cellular communications, Code Division Multiple Access (CDMA), frequency-division multiplexing (FDM), Time Division Multiple Access (TDMA)*

frequency-division multiplexing (FDM)

A signal transmission technology in which multiple signals can simultaneously be transmitted over the same line or channel.

Overview

Frequency-division multiplexing (FDM) can be used in both wired and wireless networking for transmitting large amounts of data at high speeds. FDM is the simplest and oldest form of multiplexing in wireless networking technology.

FDM involves simultaneously transmitting multiple signals on different frequencies. These different frequencies, called channels, share nonoverlapping portions of the total frequency band being used. Signals from different data sources are fed into a multiplexer that modulates each signal and transmits them at different frequencies. These signals are then transmitted over the wire or through wireless communication and are separated at the destination into individual data signals using a demultiplexer.

Uses

FDM is used in a number of popular technologies including cable television (primarily within Hybrid Fiber Coaxial [HFC] cable systems), microwave and satellite networking, and in the older Advanced Mobile Phone Service (AMPS) cellular phone system.

See Also: *Frequency Hopping Spread Spectrum (FHSS), multiplexing, time-division multiplexing (TDM)*

frequency hopping

A spread-spectrum transmission technology for wireless networking.



Frequency hopping. *How frequency hopping works.*

Overview

Spread-spectrum wireless technologies trade throughput for increased reliability and were originally developed by the U.S. military to provide communication that could not easily be jammed. Frequency hopping transmitters take the incoming data stream and segment it into multibit packets. These packets are then transmitted sequentially in a pseudo-random manner over the various frequency channels within the spread-spectrum band being used. In other words, the frequency of the carrier signal keeps hopping around. Synchronization between the master transmitter and slave devices is achieved by modulating the center or carrier frequency of the communication band according to a preset algorithm. Both the mobile and the base station know the modulation algorithm, which enables them to keep in communication with each other. For increased security, the modulation algorithm can be dynamically modified.

Frequency hopping is employed in cellular communications systems and some wireless networking systems. It is also used in Bluetooth PAN (personal area network) technologies.

See Also: *Bluetooth, direct sequencing, Frequency Hopping Spread Spectrum (FHSS), spread spectrum*

Frequency Hopping Spread Spectrum (FHSS)

Any type of wireless communications system based on frequency hopping.

Overview

Frequency Hopping Spread Spectrum (FHSS) is the earliest secure transmission mechanism used for the physical layer of wireless communications. FHSS was conceived as a technology by actress Hedy Lamarr and composer George Antheil during World War II and became popular as a secure communications system that was resistant to eavesdropping.

Implementation

FHSS employs a narrowband carrier and divides communications up into a number of discrete channels. Information is transmitted in a series of short bursts that hop from one frequency to another. To a non-FHSS receiver, the transmission seems to be random bursts of noise. To make FHSS work, both the transmitter and receiver are programmed with the same hopping sequence and are synchronized with each other so that the receiver always knows what frequency the transmitter is going to hop to next. If interference is encountered on a channel, the transmission for that channel is discarded and retransmitted on the next hop, making FHSS an efficient means of communication in noisy environments.

Uses

FHSS is one of the three PHY layer technologies defined by the 802.11 wireless networking standard, the others being Direct Sequence Spread Spectrum (DSSS) and infrared. Although early 802.11 radio equipment employed FHSS, the newer 802.11b standard does not support FHSS and uses DSSS instead.

Another technology that uses FHSS is Bluetooth, a short-range wireless networking technology for building personal area networks (PANs).

See Also: *Bluetooth, Direct Sequence Spread Spectrum (DSSS), spread spectrum, wireless networking*

frequently asked questions (FAQ)

A list of commonly asked questions and their answers.

Overview

Frequently asked questions (FAQ) are usually developed for beginners in a given subject to reduce the amount of customer technical support required. They are often available for computer products and services on company and organization Web sites on the Internet, as well as for many different Usenet newsgroups. Some Microsoft software documentation also includes FAQs to provide quick answers to commonly asked questions about the software. To ease your customer support requirements, create simple and highly usable FAQ for your clients.

FSM

Stands for File and Print Services for Macintosh, a Microsoft Windows 2000 service that provides Macintosh users with access to files stored on NTFS volumes on Windows 2000 file servers.

See: *File and Print Services for Macintosh (FSM)*

FSMO

Stands for flexible single-master operation, a unique set of single-master roles for domain controllers in Windows 2000 and Windows .NET Server networks.

See: *flexible single-master operation (FSMO)*

FSO

Stands for Free Space Optics, the transmission of data through free space using lasers.

See: *Free Space Optics (FSO)*

FTAM

Stands for File-Transfer Access and Management, the Open Systems Interconnection (OSI) reference model counterpart of the Internet standard File Transfer Protocol (FTP).

See: *File-Transfer Access and Management (FTAM)*

FTP

Stands for File Transfer Protocol, an application-level protocol that can be used for transferring files between hosts on a Transmission Control Protocol/Internet Protocol (TCP/IP) network.

See: *File Transfer Protocol (FTP)*

FTP service

A Microsoft Windows NT service on servers running Microsoft Internet Information Server, or a Windows 2000, Windows XP, or Windows .NET Server service on servers running Internet Information Services (IIS).

Overview

The FTP service supports the Internet standard File Transfer Protocol (FTP) and allows users to upload and download files between FTP clients and FTP servers. IIS FTP servers support only anonymous authentication or Basic Authentication. When an FTP client attempts to connect to an FTP server configured to use Basic Authentication, the user's name and password are transmitted as clear text over the network, which is insecure. The best way to secure FTP services is to enable anonymous authentication on all FTP servers, which requires users to log on with the username "anonymous." (They can enter anything for the password, but the FTP server's welcome message usually requests politely that they use their e-mail address as their password for logging purposes.) You should configure the FTP service on IIS to allow only anonymous logons to prevent users from passing their credentials over the network. Then simply avoid storing critical information on your FTP servers and use them for access to public information only.

You will probably also want to configure your FTP servers to allow only downloads and prohibit all uploads. If your corporate users must upload files remotely using FTP, you can create an FTP drop box for them. An FTP drop box is a folder on an NTFS volume, configured as a virtual directory that has write permission on it but not read permission. In other words, users can upload files to the directory but cannot read what has already been uploaded.

FTTC

Stands for fiber to the curb, the laying of fiber-optic cabling by telcos to the customer premises.

See: *fiber to the curb (FTTC)*

full backup

Commonly called a normal backup in Microsoft terminology, a backup type in which an entire volume or system is backed up.

See: *normal backup*

full-duplex

A mode of communication in which data is simultaneously transmitted and received between stations.

Overview

Full-duplex communication is twice as fast as half-duplex communication and typically uses two separate pairs of wires (or two channels for wireless networking) for supporting simultaneous transmission and reception by a host. An alternative arrangement is to use some multiplexing technique, such as time-division multiplexing (TDM), to interleave transmission and reception on a single channel. This does not produce true full-duplex communication, but to an ordinary user it might appear to do so if the interleaving process is fast enough.



Full-duplex. *Full duplex communications compared to simplex and half-duplex.*

Examples of full-duplex communication include cellular telephone technologies and full-duplex Ethernet. Examples of half-duplex communication are walkie-talkies, CB radios, and standard Ethernet networks. Examples of simplex communication technology include satellite broadcasting and cable TV broadcasting.

See Also: *full-duplex Ethernet, half-duplex, signaling, time-division multiplexing (TDM)*

full-duplex Ethernet

A form of Ethernet that supports full-duplex communication between stations on the network.

Overview

Full-duplex Ethernet lets stations send and receive data simultaneously, thus giving it twice the maximum throughput of traditional forms of Ethernet. Full-duplex Ethernet uses two wires for sending and receiving data simultaneously.


10-Mbps
Ethernet LAN
Full-duplex converter
(switch)
LAN
Duplex single-
mode fiber
15 km
Hub
Hub
LAN
Duplex single-
mode fiber
20-Mbps
full-duplex
Ethernet backbone
Full-duplex converter
(switch)
10-Mbps
Ethernet LAN

Full-duplex Ethernet. *Using full-duplex Ethernet to connect local area networks (LANs) using long-haul fiber.*

Full-duplex Ethernet does not use the traditional Carrier Sense Multiple Access with Collision Detection (CSMA/CD) media access control method of traditional half-duplex Ethernet since collisions cannot occur on a full-duplex, point-to-point link between two stations. Instead, full-duplex Ethernet uses dedicated point-to-point connections between stations where collisions cannot occur. To implement these point-to-point connections, you must use Ethernet switches instead of traditional hubs or repeaters since hubs are shared media devices and cannot provide dedicated connections.

Using switches means that full-duplex Ethernet avoids the collisions that can degrade the performance of standard half-duplex Ethernet. In theory, a full-duplex connection on a 100 megabits per second (Mbps) Fast Ethernet network has a maximum speed of 200 Mbps. In reality, however, full-duplex Ethernet tends to achieve only a 20 to 60 percent higher throughput than regular half-duplex Ethernet.

The table below shows which varieties of Ethernet support both half-duplex and full-duplex signaling and which are restricted to half-duplexing only.

Ethernet Media Options Supporting Full-Duplex Signaling

Media specification	*Full-Duplex Supported*
10Base2	
10Base5	
10BaseT	X
10BaseFL	X
10BaseFB	
10BaseFP	
100BaseTX	X
100BaseT2	X
100BaseT4	
100BaseFX	X
1000BaseCX	X
1000BaseLX	X
1000BaseSX	X
1000BaseTX	X

Uses

Because the distance limitations between two stations in full-duplex Ethernet depend only on the strength of the transceivers with respect to the medium used, station-to-station distances for full-duplex Ethernet connections can be much greater than for traditional Ethernet networks. For 100-Mbps full-duplex links, this is generally around 1.25 miles (2 kilometers) over fiber-optic cabling but using vendor-specific nonstandard repeaters, this can be extended to 62.5 miles (100 kilometers) or more.

You can also use 10-Mbps full-duplex Ethernet to connect two 10BaseT Ethernet networks over duplex single-mode fiber-optic cabling at distances of up to 15 kilometers. To do this, use a pair of half-to-full duplex converters at either end of the fiber-optic line. These converters should always be used in pairs, and they typically have an attachment unit interface (AUI) port that accepts the fiber-optic transceiver.

See Also: *Carrier Sense Multiple Access with Collision Detection (CSMA/CD), Ethernet, Fast Ethernet, full-duplex, half-duplex*

fully qualified domain name (FQDN)

In the Domain Name System (DNS), a dotted name that fully identifies a Transmission Control Protocol/Internet Protocol (TCP/IP) host on the Internet.

Overview

A fully qualified domain name (FQDN) of a host consists of its host name together with its domain name and any names of subdomains in which the host resides, all of which are separated by periods. FQDNs are used in Uniform Resource Locators (URLs) for accessing Web pages on the Internet and provide an absolute path through the DNS namespace to the target host on which the Web page resides. They are also sometimes called absolute domain names.

Examples

For the host having the FQDN

```
server7.microsoft.com
```

the host name is server7 and the domain is microsoft.com.

See Also: *domain name, Domain Name System (DNS)*

Fusion

An annual business symposium designed for the business experts and managers in the Microsoft Certified Solution Provider (MCSP) worldwide community.

Overview

The general purpose of Microsoft Fusion is to enable solution providers to

- Share information on the latest Microsoft Corporation products, technologies, and sales strategies from experts in the field
- Share their experiences and tips with other industry experts and peers
- Discover new methods for growing a business by capitalizing on Microsoft technologies and resources

For More Information

Visit Microsoft Fusion at *events.microsoft.com/events/fusion.*

G

G.703

A digital signaling specification from the International Telecommunication Union (ITU).

Overview

G.703 is an ITU recommendation for interfacing DCE (data communications equipment) with digital high-speed synchronous communication services. The G.703 interface covers signaling speeds from 64 kilobits per second (Kbps) to 2.048 megabits per second (Mbps) over a four-wire physical interface. G.703 also supports special data recover features that make it suitable for high-speed serial communications.



G.703. *Using a G.703 converter to interface a router to an E1 circuit.*

Although G.703 has been updated to include support for U.S. standard T-carrier service speeds, such as T1 transmission at 1.544 Mbps, it's not widely used in North America and is found mainly in Europe. Private Branch Exchange (PBX) systems often use 64-Kbps leased lines using the G.703 standard, as do E-carrier services such as E1 communication links. Some U.S. vendors sell converters for connecting synchronous V.35, RS-449, RS-232, or X.21 interfaces to G.703 in order to sell their switching equipment in Europe. G.703 converters are also used to interface digital microwave and satellite communication channels and for translating between 56 and 64 Kbps speeds for different serial interfaces. G.703 optical converters can handle speeds of 45 Mbps (E3) and higher.

See Also: *data communications equipment (DCE), serial transmission*

gateway

A term used to describe a variety of networking technologies that enable communication between different networking architectures and protocols.

Overview

Gateways generally operate at the higher levels of the Open Systems Interconnection (OSI) reference model for networking. They are commonly used to provide connectivity between two different protocol stacks that might be running on different systems. Examples include the following:

- E-mail gateways—for example, a gateway that receives Simple Mail Transfer Protocol (SMTP) e-mail, translates it into a standard X.400 format, and forwards it to its destination
- Gateway Service for NetWare (GSNW), which enables a machine running Microsoft Windows NT Server, or Windows 2000 Server to be a gateway for Windows clients so that they can access file and print resources on a NetWare server
- Gateways between a Systems Network Architecture (SNA) host and computers on a Transmission

Control Protocol/Internet Protocol (TCP/IP) network, such as the one provided by Microsoft SNA Server

- A packet assembler/disassembler (PAD) that provides connectivity between a local area network (LAN) and an X.25 packet-switching network

A gateway is usually a dedicated device or a set of services running on a dedicated computer. Gateways are essentially devices that direct network traffic in some fashion and translate that information.

See Also: *network*

Gateway Service for NetWare (GSNW)

A feature of Microsoft Windows 2000 Server that allows Windows clients access to NetWare servers.

Overview

When Gateway Service for NetWare (GSNW) is installed and configured on a machine running Windows 2000 Server, the server can act as a gateway to enable Windows clients to access file, print, and directory resources on Novell NetWare servers. The process is totally transparent to the users on the Windows client machines—to them the resources appear to be located on the Windows 2000 server itself instead of the NetWare server.

GSNW can perform gateway functions for all versions of Microsoft Windows client operating systems, including Windows for Workgroups, Windows 95, Windows 98, Windows Millennium Edition (Me), Windows NT Workstation, Windows 2000 Professional, and Windows XP. GSNW can provide gateway access for Windows clients to bindery-based NetWare 2.*x* and 3.*x* servers and to NetWare 4.*x* servers running either NDS (Novell Directory Services) or in bindery emulation mode. A Windows 2000 server that has GSNW installed also must have the NWLink protocol loaded. This protocol, which is an Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX)–Compatible Transport, makes it possible for the Windows 2000 server to communicate with the NetWare server. If it is not already installed, NWLink will install automatically on the Windows 2000 server when you install GSNW.

Implementation

To prepare the NetWare server for the gateway, you must create a group and a user account as follows:

- Create a group called Ntgateway on the NetWare server and give it the necessary rights for accessing the resources you want to make available on the server.
- Create a user account on the NetWare server and give it the necessary rights for accessing the resources you want to make available on the server. Make this user account a member of the Ntgateway group.



Gateway Service for NetWare (GSNW). *How GSNW provides Microsoft Windows clients with access to file and print resources on a Novell NetWare server.*

GSNW will use this user account for creating a connection to the NetWare server. The connection will appear on the server running Windows 2000 as a redirected drive that can be shared, as if it were a resource located on the Windows 2000 server. Windows clients can then connect to the shared resource by browsing My Network Places, by mapping a drive using Windows

Explorer, or by using the net use command. From the perspective of Windows clients on the network, the shared resources they access appear to reside on the Windows 2000 server. In actuality, the GSNW service on the server is performing protocol conversion between the Server Message Block (SMB) protocol, which the Windows clients understand, and the NetWare Core Protocol (NCP), which the NetWare file server uses.

After GSNW is installed, the first time you log on to the server for connectivity to a NetWare 4.*x* server using NDS, you are prompted to specify a default tree and context for connecting to the NetWare server. If the NetWare server is running in bindery-emulation mode or is an earlier 2.*x* or 3.*x* server, you must specify a preferred server when you log on. You can also configure these settings using the GSNW utility in Control Panel.

Uses

Because GSNW must process all requests directed through the gateway and perform protocol conversion between SMB and NCP, access is slower than if the clients actually had NetWare client software installed and could directly access the NetWare server. You should use GSNW only for occasional or temporary access to NetWare servers by Windows clients—for example, during a process of migrating NetWare servers to Windows 2000. When Windows clients need frequent access to resources on NetWare servers, as in a heterogeneous networking environment, install Client Services for NetWare (CSNW) instead of GSNW on Windows 2000 client machines to allow them direct access to resources on NetWare servers. On other versions of Windows, you can install Client for NetWare Networks to achieve the same result.

Notes

Both GSNW and CSNW are also available on the Windows NT platform.

See Also: *Client Services for NetWare (CSNW), File and Print Services for NetWare (FPNW), NetWare protocols*

GbE

Stands for Gigabit Ethernet, a form of Ethernet that operates at 1 gigabit per second (Gbps).

See: *Gigabit Ethernet (GbE)*

GBIC

Stands for Gigabit Interface Converter, a modular transceiver for Fibre Channel switches and other gigabit networking devices.

See: *Gigabit Interface Converter (GBIC)*

gender changer

An adapter with two connectors of the same type and gender.

Overview

A gender changer enables you to change the gender of the connector to which it is joined. For example, you could change the gender of a cable connector from male (with pins) to female (with sockets) or vice versa. This is typically done to allow two male or female cable ends to be joined together to form a longer cable or to allow equipment to be connected to a cable with the wrong gender.

Gender changers come in a variety of types and are specified by the connector type and gender involved. An example would be a V.35 to V.35 male/male gender changer, which can be used to connect two V.35 serial cables (or one cable and a Channel Service Unit/Data Service Unit [CSU/DSU]) that terminate with female connectors.



Gender changer. *Examples of V.35 gender changers.*

Some gender changers can also act as adapters for different data interfaces. For example, a V.35 to RS-232 male/male gender changer can be used to connect a V.35 connection on a CSU/DSU to a router using an RS-232 serial cable. Be sure that the pinning for such a gender changer is suitable for the type of equipment you want to connect because different pinnings might exist when different serial interfaces are connected.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), RS-232, V.35*

General Packet Radio Service (GPRS)

A 2.5G upgrade to existing Time Division Multiple Access (TDMA) cellular communications systems.

Overview

General Packet Radio Service (GPRS) was designed as an upgrade for existing second-generation (2G) cellular systems such as Global System for Mobile Communications (GSM) and other TDMA systems such as AT&T Wireless. GPRS is a packet-switching overlay that can support Internet Protocol (IP) data transmission at speeds up to 171 kilobits per second (Kbps), which is more than 10 times faster than currently supported data rates for these systems (data transmission on current GSM systems is typically 9.6 Kbps). In practice, however, the maximum data rates are usually more like 52 Kbps downstream and 13 Kbps upstream. This is because of the overhead of combining channels together, throttling of bandwidth by providers to enable more users to share channels, and the power limitations of handsets at the subscriber end.

GPRS will provide the first global high-speed mobile IP communications system and is intended as an interim solution until broadband third-generation (3G) cellular systems can be fully deployed. Using GPRS, a cellular phone can access Internet services by means of Wireless Application Protocol (WAP). WAP provides a richer format for information exchange than the existing Short Message Service (SMS), which is limited to a maximum of 160 characters per transmission. With its higher data rates, GPRS makes possible the kinds of wireless applications and services that simply have not been feasible on existing GSM and TDMA systems. Possible uses for GPRS include wireless mobile Web browsing, discussion groups, chat services, mobile commerce, and home automation through wireless remote control.

The GPRS standard 03.60 was developed by the European Telecommunications Standards Institute (ETSI). Trials of GPRS began in 1999, and the first commercial rollouts appeared in 2000. A number of European and Asian countries and regions are piloting GPRS systems and thus have an edge over the United States in the arena of wireless communication systems running at more than 20 Kbps.

Uses

Besides cellular phones, GPRS can be implemented in a wide variety of devices, including PCMCIA modems for laptops, expansion modules for Personal Digital Assistants (PDAs) and handheld computers. Research in Motion (RIM), makers of the popular BlackBerry handheld e-mail devices, is working with Microcell Telecommunications, a GSM provider, to use GPRS as a transport for its wireless messaging system.

Architecture

Most existing 2G cellular systems are circuit-switched services in which a dedicated connection must be established in order for communications to take place. As long as the session lasts, the subscriber owns the channel and is billed for its usage even if no data is being sent. By contrast, packet-switching is a more efficient technology because it allows several users to share a channel. No actual connection needs to be established in order to send data—from the point of view of the subscriber the system is “always on” and ready to transmit. And instead of billing for connection time, subscribers are billed according to the amount of data they transmit and receive instead.

GPRS uses the same underlying TDMA time slot architecture as GSM, but instead of assigning only a single time slot to each user for transmission or reception, it can multiplex up to eight slots (the maximum for a TDMA frame) to give a maximum possible data transmission rate of 171 Kbps. In most implementations, however, three or four slots can are multiplexed for downstream transmission and only one for upstream, which makes practical transmission speeds much slower (but still better than GSM alone).

When a GPRS user wants to send data, the handset finds the first available time slot and sends the first chunk of data, sending more chunks as further slots become available. In this respect, GPRS operates like an Ethernet network—the more users sharing the system, the less bandwidth available for each user to transmit or receive data. Collisions do not occur, however, since time-division multiplexing (TDM) prevents contention from occurring.

GPRS was designed to transport both IP and X.25 packet data, but all current implementations use IP to provide connectivity with the Internet. To provide this connectivity, a GPRS mobile phone needs an IP address, which can be either statically or dynamically assigned. All existing application-layer Internet protocols can run over GPRS, including Hypertext Transfer Protocol (HTTP), File Transfer Protocol (FTP), Simple Mail Transfer Protocol (SMTP), and so on. Most GPRS systems use WAP as their application layer protocol, however, because it is more efficient for devices with limited memory and small displays.

Implementation

Implementation of GPRS requires that existing TDMA hardware be upgraded, including handsets and base stations. In addition to the base stations and mobile switching centers of existing TDMA networks, GPRS adds two additional components:

- **Serving GPRS Support Node (SGSN):** This transmits and receives IP packets to mobile stations through the existing base stations, and exchanges these packets with the Gateway GPRS Support Node (GGSN) using a special tunneling protocol called GPRS Tunneling Protocol (GTP).
- **Gateway GPRS Support Node (GGSN):** This acts as a gateway between the SGSN and the Internet, forwarding packets between them.

GPRS handsets are similar to GSM handsets, and they require a Subscriber Identity Module (SID), a form of smart card containing the subscriber's ID, billing address, private key, and other information. GPRS supports several security schemes including Password Authentication Protocol (PAP), Challenge Handshake Authentication Protocol (CHAP), Secure Sockets Layer (SSL), and IPsec.

It is probable that GPRS upgrades will be easiest for carriers whose networks operate in the 1800-megahertz (MHz) or 1900-MHz frequency bands, because they usually have sufficient unused capacity to implement channel aggregation without having to upgrade their bearer equipment. Upgrading to GPRS is more expensive for carriers operating in the 800-MHz or 900-MHz bands because of the near-full capacity of those bands.

Another cost involved in the GPRS upgrade process is that of replacing the circuit-switched core network connecting existing base stations with an IP-based backbone network for interfacing between the wireless system and the Internet. You can create an interface between a GPRS network and an IP network by using a GGSN. You can also use GGSNs to connect GPRS networks with legacy X.25 packet-switching networks.

Prospects

GPRS is viewed as an interim solution to give mobile users a measure of access to the Internet. The GSM Alliance, representing 400 GSM providers and their 250 million subscribers worldwide, is a driving force behind the move toward upgrading existing GSM systems to GPRS. As an example, AT&T Wireless plans to migrate its existing TDMA system (a 2G system based on IS-136) in several stages over the next few years, starting first with GPRS, a 2.5G upgrade, then Enhanced Data Rates for Global Evolution (EDGE), an IMT-2000 3G upgrade to GPRS, and finally to Universal Mobile Telecommunications System (UMTS) which will support 3G speeds of 2 megabits per second (Mbps).

In late 2000, a large cellular operator in Hong Kong SAR called Pacific Century CyberWorks (PCCW) launched a 20 kilobits per second (Kbps) GSM-based GPRS overlay, which, in order to access, subscribers need to upgrade their handsets to Motorola P7389i.

Other GSM operators around the world are involved in similar upgrades, with GPRS handsets becoming available from Nokia and other vendors. Lucent Technologies and Sun Microsystems are also working together to provide a platform for GSM upgrades to GPRS.

Notes

EDGE is almost identical to GPRS, the main difference being that EDGE uses a more efficient encoding scheme (8-bit phase shift keying or 8-PSK) which encodes three bits per symbol instead of the Gaussian phase shift keying (GMSK) mechanism of GSM (and also GPRS) that encodes only one bit per symbol. The result is that EDGE theoretically supports data transmission rates up to 513 Kbps, three times the maximum possible for GPRS. Real speeds for EDGE systems will be much lower, however, due to protocol overhead, error correction, and bandwidth throttling by providers. Although EDGE speeds are lower than the 2 Mbps limit intended for 3G systems by the IMT-2000 recommendations from the International Telecommunication Union (ITU), EDGE is still classified under IMT-2000 as a 3G system.

GPRS cannot be used to easily upgrade existing Code Division Multiple Access (CDMA) cellular systems, which are widely in use throughout North America and some other parts of the world. These systems are expected to migrate to Wideband CDMA (W-CDMA) instead, a 3G recommendation from the ITU that offers speeds up to 2 Mbps.

See Also: *2G, 2.5G, 3G, cellular communications, Code Division Multiple Access (CDMA), Enhanced Data Rates for Global Evolution (EDGE), Global System for Mobile Communications (GSM), Time Division Multiple Access (TDMA), Wideband Code Division Multiple Access (W-CDMA)*

Gigabit Ethernet (GbE)

A form of Ethernet that operates at 1 gigabit per second (Gbps).

Overview

Gigabit Ethernet (GbE) is an evolution of standard Ethernet technologies that supports the transmission of data at 1 gigabit per second (Gbps) or 1000 megabits per second (Mbps) over both fiber-optic cabling and copper twisted-pair cabling. GbE was developed to solve the problem of increasing congestion on local area network (LAN) backbones currently running Fast Ethernet, Fiber Distributed Data Interface (FDDI), and Asynchronous Transfer Mode (ATM). Because of its simplicity and throughput, GbE has become the dominant LAN backbone technology, relegating the slower FDDI to the legacy arena and pushing the complicated ATM back into the wide area network (WAN) environment where it originated. Because of its close similarities to other forms of Ethernet, GbE provides a smooth upgrade path from 10 megabits per second (Mbps) Ethernet and 100 Mbps Fast Ethernet.

The Gigabit Ethernet Alliance is an open forum that promotes cooperation and industry standards for GbE. The Alliance includes a number of prominent companies, including Cisco Systems, Intel Corporation, Sun Microsystems, Nortel Networks, and 3Com Corporation. GbE is standardized by the IEEE specifications 802.3z in 1998 and 802.3ab in 1999.

Uses

GbE's main application is for building high-speed backbones for LANs and campus networks. An example would be for high-speed switch-switch connections where you might connect two 100 Mbps switches with 1 Gbps uplinks to create Fast Ethernet islands joined by a GbE backbone. Alternatively, you could connect several 10/100 switches to one 100/1000 switch. For collapsed backbones, 1000BaseT copper interconnects are sufficient to join switches together, but for campus-wide distributed backbones, 1000BaseLX running over single-mode fiber supports the long distances needed to build such infrastructure. The problem is that many existing FDDI campus backbones use multimode fiber, and GbE does not operate over long distances on this type of fiber. This usually necessitates pulling new fiber to replace existing multimode fiber campus backbones with single-mode fiber to enable GbE to run over these backbones. Single-mode fiber is more expensive than the multimode type, and pulling fiber is an expensive process itself, so these costs generally add a significant amount to the process of converting legacy FDDI campus backbones to newer GbE ones. On the other hand, upgrading switched Fast Ethernet backbones in small and mid-sized companies to GbE may simply be overkill. Overprovisioning of GbE is common by system integrators, and it provides small gains over existing Fast Ethernet networks with considerable added cost.

GbE is also finding an increasing place in server-switch connections for joining server farms to high-speed backbones. This configuration can theoretically provide users with 1-Gbps access to application or file servers, but there are limitations at present. The problem is that even with newer 1 Gbps network interface cards, most servers still cannot make full use of a gigabit link to a GbE switch. Various factors are at work here, including the existing 64-bit Peripheral Component Interconnect (PCI) bus being too slow to pump data out at gigabit speeds (the upcoming PCI-X standard may help here), hard disk subsystems being unable to keep up with the flow of data to and from the server (even 10,000 RPM hard disks cannot read/write at gigabit speeds), and the Transmission Control Protocol/Internet Protocol (TCP/IP) stacks of operating systems being unable to handle gigabit data transfer rates (though Microsoft Windows 2000 is a considerable improvement in this area over Windows NT). The bottom line is that aggregating two or three Fast Ethernet links is currently sufficient for handling data transfer to most Wintel servers and is a cheaper solution than adding a Gigabit network interface card (NIC) and connecting it to a Gigabit switch. This will probably change around 2002 as 64-bit Windows running on Itanium chips may finally perform to the point of needing a second Gigabit NIC to handle throughput, but keep your eyes on developments in hard disk technologies as their performance is usually the limiting factor or bottleneck in keeping file servers from pumping data at gigabit speeds.

Gigabit-to-the-desktop is a vision of deploying GbE end-to-end across a network, and involves installing 1 Gbps NICs into high-performance workstations to provide them with incredibly fast access to network servers. This is still more a dream than a reality, though, because such workstations suffer from the same limitations that were described for servers above, and even more so. The result is that deploying GbE end-to-end across a network generally results in only a marginal improvement over Fast Ethernet in applications performance and greatly complicates the already difficult task of troubleshooting high-speed switched networks. In the old days of shared Ethernet networks, a “sniffer” could be connected to the main hub and traffic on the entire LAN could be analyzed—capturing and analyzing traffic on a switched LAN is much more complicated, and protocol analyzers operating at gigabit speeds are expensive. In any case, gigabit-to-the-desktop is still several years from everyday reality, and most desktop applications can achieve sufficient bandwidth using only Fast Ethernet.

Another hindrance to completely migrating a network’s infrastructure from Fast Ethernet to GbE over copper (1000BaseTX) is cabling. Although GbE can theoretically run over existing Category 5 (Cat5) cabling, such cabling usually has not been installed with the care and precision needed to support gigabit signaling speeds. Also, GbE over copper requires the use of all four pairs of wires, whereas some flavors of Fast Ethernet only needed two pairs of wires. As a result, corporate networks often need considerable rewiring to support GbE, and even new deployments using enhanced Category 5 (Cat5e) or Category 6 (Cat6) wiring require exceptional care in how they are installed to ensure that GbE will perform as expected.

Architecture

Like earlier forms of Ethernet, the GbE standards specify only the physical (PHY) layer and data-link layer of network operation and support any protocols running at higher levels. This means that upgrading from Ethernet or Fast Ethernet to GbE is relatively straightforward and only involves insuring that GbE supports the cabling media, cable lengths, and cabling topology. No changes need to be made to higher-layer protocols such as TCP/IP during such an upgrade (although sometimes such network layer protocols can be “tuned” to provide better performance in a GbE environment).

GbE uses the same connectionless datagram delivery services as earlier forms of Ethernet. It uses the same frame format as other forms of Ethernet and likewise supports both unicast, multicast, and broadcast frames. It can operate in both shared (half-duplex) and switched (full-duplex) modes. GbE employs a line coding scheme called 8B/10B that packs 8 bits (1 byte) of data into 10 baud (symbols) for transmission, a system known as 1000BaseX. This means that in order to achieve a data transmission rate of 1 Gbps, a signaling frequency of 1.25 GHz is required. The 8B/10B encoding scheme for GbE was borrowed from Fibre Channel technologies. GbE actually borrows most of the characteristics of its PHY and data-link layers from the Fibre Channel's FC-0 and FC-1 sublayers, with the exception of using a signaling rate of 1.250 Gbaud instead of Fibre Channel's 1.0625 Gbaud.

GbE uses the same standard 802.3 framing structure as standard Ethernet, with frames between 64 and 1514 bytes in length and using the same 48-bit MAC addresses (jumbo frames up to 9000 bytes are also supported). It also supports the same Carrier Sense Multiple Access with Collision Detection (CSMA/CD) media access method supported by earlier versions of half-duplex Ethernet. To achieve the tenfold speed increase of GbE over Fast Ethernet while maintaining support for reasonably large networks, GbE makes some changes to the Ethernet MAC algorithm and how CSMA/CD operates. These changes are necessary because reducing the transmission time for a frame by a factor of 10 on an Ethernet network normally means that the size of the network (maximum distance between stations) would also decrease by the same factor.

One of the media access control (MAC) layer modifications introduced by GbE is called carrier extension, which involves extending the length of the carrier and slot times to pack out all frames to a minimum carrier length of 512 bytes to ensure that collisions can be properly detected and recovered from. In other words, the smallest possible frame (64 bytes) would have its carrier signal extended until it appears to the physical layer as 512 bytes in length. This is different from merely padding a 64-byte frame with an additional 448 bytes of junk to produce a 512-byte frame—instead, the carrier signal is extended for a time equivalent to 448 additional bytes, but the frame still appears to be 64 bytes in length from the point of view of layers above the MAC layer. As a result, if the frame is bridged from a GbE to a Fast Ethernet network segment, for example, the frame remains 64 bytes in length on the Fast Ethernet segment, instead of 512 bytes if the frame were merely padded. Another MAC layer modification in GbE is support for frame bursting, which allows multiple short frames to be grouped in a way that it allows a station to take temporary control of the wire to send out a number of small packets in succession, arbitrating the signal for the channel only once. This second feature is optional but results in better performance in many situations.

Both of these modifications are done to enable shared half-duplex implementations of GbE to support a network diameter of up to 655 feet (200 meters), instead of the inadequately small 65.5-foot (20-meter) wide network that would result if CSMA/CD were implemented without these modifications. When implementing switched full-duplex GbE, CSMA/CD is not used and these issues are irrelevant because no collisions can occur.

GbE also supports several schemes for autonegotiation, allowing hubs, switches, routers, and NICs capable of supporting 100/1000 Mbps or even 10/100/1000 Mbps speeds.

Implementation

GbE can be implemented in four different PHY layer options, all of which support both half-duplex and full-duplex operation:

- **1000BaseCX:** Uses 150-ohm balanced twinax cabling or shielded twisted-pair (STP) cabling with a maximum link length of 82 feet (25 meters). This version is designed primarily for device clustering and is not much used.
- **1000BaseLX:** Uses both long wavelength transmissions over single-mode fiber-optic cabling supporting distances of 3 miles (5000 meters) over 10 micron fiber and also short wavelength transmissions over multimode fiber supporting distances of 1640 feet (550 meters) over both 62.5 and 50 micron fiber. The single-mode version is used mainly for long cable runs; for example, to connect LANs across a campus.



Gigabit Ethernet. *Simple example of using a 100/1000 Mbps GbE switch.*

- **1000BaseSX:** Uses short wavelength transmissions over multimode fiber-optic cabling. This version is used mainly for short cable runs of up to 1805 feet/ 550 meters (over 50-micron fiber) or 900 feet/275 meters (over 62.5-micron fiber) and is intended for connecting workgroup switches in a building to a GbE backbone switch.
- **1000BaseTX or 1000BaseT:** Uses twisted-pair Cat5 cabling (all four pairs of wires are needed) with a maximum link length of 328 feet (100 meters), giving a maximum network diameter of 655 feet (200 meters). It is intended mainly for connecting high-speed servers to GbE switches and for switch-switch interconnects in collapsed backbones.

Note that the distances specified above are for full-duplex operation only, because they are the inherent or physical distance limitations of the media for Gigahertz signaling. For half-duplex networks, the distance restrictions are more severe and depend on the round-trip propagation delay supported by the MAC signaling method. For example, the maximum supported link length for 1000BaseLX and 1000BaseSX is only 364 feet (111 meters), well below the physical signaling distances supported by fiber medium.

Shared (half-duplex) implementations of GbE support only two simple topologies: a point-to-point connection between two stations and a star-wired topology with a hub (repeater) at the center, typically with 8, 12, or 24 ports on a hub. Cascaded hub topologies are not supported by shared GbE LANs, though some manufacturers sell stackable hubs whose backplanes can be connected to form a single collision domain. As a result of these topology restrictions, switched (full-duplex) implementations are much more common in real-world networks, and they support virtually any topology you can imagine as long as the length restrictions outlined above are adhered to (there are even ways around these length restrictions at times, as will be mentioned later).

Advantages and Disadvantages

Compared to other network backbone technologies, GbE has a number of distinct advantages. The most obvious advantage over FDDI is the superior speed offered by GbE. The result is that GbE has pushed FDDI from the corporate mainstay it was in the mid-1990s to being legacy technology today that most enterprises are phasing out. Most corporate FDDI network backbones have now migrated to GbE, and the remaining ones are not likely to last beyond a couple of years as chip manufacturers for FDDI equipment stopped producing as of 2001.

GbE also has several advantages over ATM that make it the current favorite for enterprise network backbones. Most ATM backbones operate at 155 or 625 Mbps and fall short of the 1 Gbps for shared half-duplex GbE and 2 Gbps of switched full-duplex GbE. ATM is also more expensive and difficult to deploy and maintain than GbE. Most network architects can transition from Fast Ethernet to GbE technologies as easily as they previously moved from 10BaseT to Fast Ethernet, since the technologies are so similar. On the other hand, ATM still holds the superior hand in the WAN where it can run over Synchronous Optical Network (SONET) for thousands of miles and for delay-sensitive applications such as voice and multimedia where GbE still falls short, although new quality of service (QoS) mechanisms for Ethernet, such as DiffServ and 802.1p VLAN tagging, may help narrow the gap.

Upgrading a Fast Ethernet backbone switch to a GbE 100/1000-Mbps switch is straightforward and will enable you to connect high-speed server farms using GbE NICs. Benefits include increased throughput and performance, more network segments, more bandwidth per segment, and more nodes per segment.

Marketplace

The growth of GbE market in the last few years has been impressive, with GbE port module shipments reaching 4 million in 2000, a quarter of which were 1000BaseTX copper ports. For comparison, however, these port figures only represent 3 percent of the total market for all forms of Ethernet, but the figures for GbE are more than doubling each year.

GbE hubs (repeaters) are not common, but GbE switches and routers are made by a wide variety of vendors. A popular example is the Catalyst 3500 series of switches from Cisco, which have a 10 Gbps backplane that provides high performance, come in 12 and 24 GbE port configurations, and support both full-duplex and half-duplex operation even over copper. 3Com's SuperStack 3 switches are another good choice, with the 4900 series providing 12 copper or fiber gigabit ports for aggregation of Fast Ethernet workgroups. A typical scenario might be to connect a dozen 3300 series 10/100 switches using gigabit fiber uplinks to a core 4900 switch. Enterasys has GbE through its entire product line of switches and routers, and Foundry gigabit products are also popular in the enterprise.

GbE switches come in two basic types:

- **Backbone switches:** These generally have 8 or 12 copper or fiber GbE ports and one or two GbE uplinks and are used for building collapsed backbones for high-speed networks. A popular example is the 12-port AT-9006LX switch from Allied Telesyn International, which has a lower per-port price than many comparable switches. Other popular backbone switches for mid-sized networks include the Intel 480T, the Catalyst 4908 from Cisco, and the Summit5i from Extreme Networks.
- **Workgroup switches:** These can have 8, 2, 24, or even 48 Fast Ethernet 10/100 ports and up to four GbE uplinks, and they are used for building Fast Ethernet islands by uplinking many Fast Ethernet switches to a single workgroup switch. Galileo Technologies has managed to cram 48 autosensing 10/100 ports and two GbE uplinks into a 1U rack-mountable device, which is quite an engineering feat.

In the distributed backbone market, the 1805-foot (550-meter) limitation for GbE over multimode fiber can be overcome by a GbE extender such as Allied Telesyn's AT-EX1001SC/GM1, which allows GbE to run over multimode fiber to a distance of 1.25 miles (2 kilometers). Campuses needing to upgrade their old FDDI-based distributed backbones to GbE can save money by using extenders like these instead of replacing existing multimode fiber with single-mode fiber.

Finally, network analyzers for troubleshooting GbE networks are available from Agilent Technologies (a spinoff from Hewlett-Packard), Network Associates, and Fluke Networks.

Prospects

GbE is here to stay. Most new enterprise networks being deployed these days are implemented with GbE backbones instead of FDDI or ATM (Fast Ethernet is still used for backbones in small to mid-sized companies). The only thing that can probably dethrone GbE is the emerging 10 GbE standard, an even faster version of Ethernet that finally discards the inefficient CSMA/CD media access method, operates instead only in switched full-duplex mode, and supports up to 40 kilometers (25 miles) using single-mode fiber. Meanwhile, prices per 1 Gbps port for GbE switches continue to fall, and even though the industry average was around $1,000 per port at the end of 2000, there were some vendors offering switches with prices as low as $300 per port. It will not be long until the price per port drops to the point where network architects may as well buy GbE switches instead of Fast Ethernet ones even if they achieve no immediate performance gains.

Another emerging use for GbE is as a transport for moving data between servers and storage area networks (SANs). GbE SANs encapsulate Small Computer System Interface (SCSI) traffic within Internet Protocol (IP) packets, making it possible to greatly extend the 165-foot (50-meter) limitation of SCSI and to locate SANs at remote data centers.

Gigabit in the metropolitan area network (MAN) is the latest development and provides an attractive alternative to telco T-carrier services to enterprises needing high-speed WAN connections. For more information on this exciting new technology, see the article “metropolitan Ethernet” elsewhere in this book.

Notes

By employing jumbo frames up to 9000 bytes in length, performance of gigabit server-switch connections can generally be improved significantly, provided the hard disk bottleneck has not been reached.

For More Information

You can visit the Gigabit Ethernet Alliance at *www.gigabit-ethernet.org.*

See Also: *1000BaseCX, 1000BaseLX, 1000BaseSX, 1000BaseTX, Carrier Sense Multiple Access with Collision Detection (CSMA/CD), Ethernet, Ethernet switch, Fast Ethernet, Fibre Channel, jumbo frames, MAC address, metropolitan Ethernet*

Gigabit Interface Converter (GBIC)

A modular transceiver for Fibre Channel switches and other devices.

Overview

Gigabit Interface Converters (GBICs) provide network architects with flexibility in choosing different media options for gigabit-speed switches. They support a variety of different cabling options, including unshielded twisted-pair (UTP) and single-mode or multimode fiber-optic and copper Fibre Channel cabling. By simply plugging the appropriate GBIC module into a port on a Fibre Channel or Gigabit Ethernet (GbE) switch, a different media option can be easily configured for that port, providing flexibility for configuring switches according to need. This is accomplished by having the GBIC convert the signals in the connected media (for example, light signals on a fiber-optic cable) into electrical signals compatible with the 1000BaseX port on the switch. GBICs can also regenerate signals, allowing transmission to occur over distances of 62 miles (100 kilometers) or greater over long-haul single-mode fiber.

Marketplace

An example is 1000BaseT GBIC from Cisco Systems, which can be used to provide flexibility in cabling options for Cisco Catalyst 2900 and 3500 Series XL GbE switches. Cisco 1000BaseT GBICs come in a wide variety of transceiver configurations that support copper, long-haul and short-haul fiber, and backplane interconnects for stacking switches. They are also hot-swappable, allowing cabling to be switched to different types on the fly in a simple plug-and-play fashion.

See Also: *Ethernet switch, Fibre Channel, Gigabit Ethernet (GbE)*

G.Lite

A splitterless version of Asymmetric Digital Subscriber Line (ADSL).

Overview

G.Lite is a form of ADSL that is targeted mainly for the residential Internet access market. G.Lite is easy to install—so easy that a home user can perform the installation, eliminating the need for a "truck roll" (technician visit) from the telco to the subscriber. This saves the telco considerable costs and allows them to pass this saving on to the subscriber. G.Lite was partly developed as a response to the challenge presented by cable modem technology, where subscribers can usually perform the installations themselves. G.Lite is intended to be a "plug and play" version of Digital Subscriber Line (DSL).

Like other forms of DSL, G.Lite connections are "always on"—once you turn your computer on, the connection is active and you can send or receive e-mail or browse the Web without having to dial up a connection. G.Lite is slower than regular ADSL and supports maximum downstream transmission of 1.536 megabits per second (Mbps) and upstream 384 kilobits per second (Kbps), depending on the implementation.

G.Lite is sometimes called DSL Lite or Universal ADSL, but the International Telecommunication Union (ITU) has endorsed the term *G.Lite* as official nomenclature for this technology under the G.992.2 standard. Commercial rollouts of G.Lite began in 1999, and the service is gaining popularity among DSL providers.

Implementation

G.Lite is sometimes referred to as splitterless ADSL because a splitter is not required at the customer premises to separate the voice and data signals being carried over the phone line. This is different from ordinary ADSL, which uses a splitter to separate the baseband analog Plain Old Telephone Service (POTS) voice channel from the upstream and downstream DSL simplex bearer signals. The splitter protects the ADSL signal from variations in impedance of the POTS signal and from dial tones and other forms of interference. Likewise, the splitter protects the POTS signal from interference due to intermodulation of the ADSL tones. In ordinary ADSL, a splitter must be installed at both the customer premises and the telco's central office (CO). G.Lite gets around the need for a splitter at the customer premises by incorporating a number of advanced signal processing techniques that help keep the bit error rate (BER) within reasonable tolerances. These advanced techniques include forward error correction, trellis encoding, and interleaving.

To use G.Lite, the customer obtains a G.Lite modem from the DSL provider and simply connects it to her computer and phone line. No second phone line or other form of rewiring of the customer premises is required, since G.Lite uses the existing local loop connection to the customer premises. Customers can make phone calls or send faxes while connected to the Internet over their G.Lite connection.

Notes

The quality of a G.Lite connection to your home can suffer if you have a large number of RJ-11 phone jacks installed. This is because each phone jack acts as a bridged tap that is run off the main phone line as a parallel connection. Signals traveling along your phone line can reflect off these jacks and affect the overall reliability of your G.Lite connection. Also, the farther your home is from the telco CO, the less bandwidth might be available for your G.Lite connection.

See Also: *Asymmetric Digital Subscriber Line (ADSL), Digital Subscriber Line (DSL)*

Global.asa

A file that contains global information for Active Server Pages (ASP) applications.

Overview

The Global.asa file is used to manage functions common to all users of an ASP application. Specifically, a Global.asa file includes

- Four event procedures common to all users of an ASP application, namely Application_OnStart, Application_OnEnd, Session_OnStart, and Session_OnEnd.
- Object declarations (using <OBJECT> tags) for defining application-level and session-level objects, variables, and event handlers.
- Type library declarations for COM components used by the application.

Global.asa files should not generate or contain any content that is visible to a client Web browser—Asp.dll will simply ignore any Hypertext Markup Language (HTML) placed in the Global.asa file. Furthermore, you can have only one Global.asa file per ASP application, and the file must be located in the root virtual directory of the application.

Notes

If your Global.asa file generates an error, you should ensure that any object declarations within the file have application-level or session-level scope, that any script in the file is enclosed within <SCRIPT> tags, and that any <OBJECT> tags are placed outside of <SCRIPT> tags.

See Also: *Active Server Pages (ASP)*

global catalog

A Microsoft Windows 2000 or Windows .NET Server domain controller that contains a read-only, partial replica of information from all domains in a forest.

Overview

The global catalog resides on a selected group of domain controllers in your Windows 2000 or Windows .NET Server enterprise called global catalog servers. The global catalog is automatically created the first time you run the Active Directory Installation Wizard and is installed on the first domain controller in the root domain by default. Other domain controllers must then be manually designated as global catalog servers by using the administrative tool Active Directory Sites and Services. The Active Directory directory service replication process then automatically maintains the contents of each global catalog server.

In a geographically distributed enterprise, each physical site should have at least one domain controller to speed network traffic. Most Active Directory–related traffic is the result of queries on Active Directory, so the domain controller for small sites should also be configured as a global catalog server. This will reduce traffic over wide area network (WAN) links to other sites by allowing the global catalog server to locally resolve queries for information on directory objects from other domains.

Every Active Directory object in the entire enterprise is represented in the global catalog, but only a subset of the attributes of each object is stored in the catalog. The properties represented are those most likely to be used as search attributes, such as the user's first or last name. However, administrators can specify storing additional object attributes in the catalog if desired. You can modify which attributes are represented for objects in the global catalog by editing the schema of Active Directory, but you must do so with care.

Uses

The global catalog enables users to easily locate objects in any domain with maximum speed and minimum network traffic. In effect, the global catalog acts as a kind of index for looking up objects stored in Active Directory anywhere on your network. Having the global catalog store only a subset of an object's attributes in Active Directory improves the response time for performing search queries on Active Directory. You can search the global catalog for Active Directory objects by using the Find dialog box in Active Directory Users and Computers. Note that the global catalog also includes the access permissions for directory objects, so if you search for an object and it does not show up, you probably do not have permission to access the object.

The global catalog also has another important function—in native-mode domains, users require access to a global catalog server in order to log on to the domain. If no global catalog server is in the local site, a global catalog server in a remote site may be used. If all global catalog servers are down in a native mode domain, users can only log on using their cached user credentials. An exception to this is that members of the Domain Admins group can log on to native domains even when no global catalog server is available.

See Also: *Active Directory, domain (DNS), domain controller, global catalog server*

global catalog server

A Microsoft Windows 2000 or Windows .NET Server domain controller that contains a copy of the global catalog.

Overview

Global catalog servers let users search for objects located anywhere in a forest and enable users to log on to the domain in native-mode networks. Information stored on global catalog servers is updated each time Active Directory directory service performs its directory replication process.

Global catalog servers should be located appropriately so that queries on Active Directory can be performed effectively. Ideally, you should have at least one global catalog server in each site within the enterprise. However, in a multidomain environment, the replication traffic generated by maintaining these servers can be a burden on overall network traffic, especially if slow wide area network (WAN) links are involved. In this case, consider placing your global catalog servers as follows:

- Place several global catalog servers in each major site where large numbers of users and resources can be found.
- Place a global catalog server at each small site where there are significant numbers of users and resources or where the WAN connection to major sites is slow.

See Also: *global catalog*

global group

A type of security group in Microsoft Windows NT, Windows 2000, and Windows .NET Server.

Overview

In Windows NT, global groups are used to simplify administration of user accounts by organizing them into groups. For example, you can use them to group users by function (such as the Accountants global group), by location (such as the Third-Floor global group), or by some other criteria. By contrast, local groups are designed to provide users with permissions for accessing network resources and rights for performing system tasks.

Global groups can contain only global user accounts from their own domain. They cannot contain global user accounts from other domains, nor can they contain other groups. Global groups are created on domain controllers and are stored within the Security Accounts Manager (SAM) database.

In Windows 2000 and Windows .NET Server mixed-mode domains, global groups operate much the same as in Windows NT, and they can be granted permissions on resources in any domain in the current forest. In native mode, however, global groups can contain both user accounts and global groups from the same domain.

See Also: *AGLP, group, local group*

global load balancer

A hardware-based or software-based solution that can direct requests for Web content to multiple geographical locations where the content is stored.

Overview

An example of using global load balancers might be for an e-business that has many data centers scattered around the world to use global load balancers to direct Web customers' traffic to centers that can provide the fastest response time for each customer's location. If a data center goes down as a result of a power outage or some other condition, traffic to that site can be transparently redirected to other sites. The overall effect of implementing global load balancers in an e-business enterprise is an increase in reliability and performance from the customer's point of view.

Implementation

Global load balancers essentially act as intelligent Domain Name System (DNS) name servers, performing name lookups for Uniform Resource Locators (URLs) and directing requests to the most appropriate Internet Protocol (IP) addresses. The five criteria listed below are typically used to determine which address to forward a request to. (Note that not all global load balancers support all of five of these criteria.)

- Proximity of the site to the client, usually measured in router hops and established by using the Border Gateway Protocol (BGP), Internet Control Message Protocol (ICMP), or User Datagram Protocol (UDP)
- Latency (the overall response time of the site), which is usually determined by pinging the site and calculating the delay
- Server load (how busy the site is and how much capacity the server has for responding to clients)
- Server health (whether the site is up and what its CPU and connection load are)
- Packet loss (the average quality of the Transmission Control Protocol [TCP] connection to the site), which is established by using ping

Of course, the DNS standard itself has built-in load balancing in the form of round-robin DNS. If multiple IP addresses are mapped to the same domain name, clients requesting the domain are directed to each IP address in a round-robin fashion. However, this rudimentary load-balancing scheme does not take into account such factors as which IP address belongs to the nearest host, the relative capability of the hosts to respond to requests, the availability of hosts, and so on. This is where global load balancers come in—they take over the role of authoritative name server for a company's domain.

Global load balancers come in three varieties:

- Layer 4 switches or routers with built-in support for global load balancing. Many Layer 4 switches and routers support some form of local load balancing, and software upgrades might be available that add such support. These switches tend to perform faster than appliances or software because they use hardware for packet forwarding and use software for routing purposes only. However, they also tend to be the most expensive solution.
- Network appliances, which are essentially self-contained, stripped-down servers running global load-balancing software on top of operating systems optimized for this particular function.
- Software that can run on standard servers running Microsoft Windows 2000, Windows NT, or UNIX that enables the servers to function as global load balancers. If you use this solution, be sure that your server is dedicated to running this software and does not run any other applications.

Global load balancers talk only to the local DNS server configured for the client, not to the client itself. This works well, except when mobile users travel to other cities and use their laptops to try to access the site. In this situation, if the client is still using a preconfigured DNS server at the home location, the global load balancer thinks that the client is still there as well. Also, once a DNS-based global load balancer has directed a client to the appropriate site or server, it is no longer involved in the client's session and cannot tell whether the server goes down or whether some problem occurs with the connection.

For this reason, some global load balancers also use Hypertext Transfer Protocol (HTTP) redirects to masquerade as the target site and redirect HTTP requests to different servers. The client actually talks to the load balancer itself, and performance is faster than using DNS because fewer TCP connections are required. If the client's connection to the server is interrupted, the global load balancer can redirect the client to a different server with minimal interruption. The downside of using HTTP redirects is that they work only with HTTP and not with other Internet protocols, such as File Transfer Protocol (FTP) or Network News Transfer Protocol (NNTP), or with streaming multimedia. This can be a limitation if your e-business delivers this type of content to the customer.

Other mechanisms can be used to perform global load balancing, including cookie-based and proprietary schemes. Windows NT 4, Enterprise Edition, provides a load-balancing service called Windows NT Load Balancing Service (WLBS). This IP load-balancing service employs a fully distributed clustering design that is ideal for creating highly available and scalable IP-based services such as Web, virtual private networking (VPN), streaming media, and proxy services.

See Also: *Domain Name System (DNS), Hypertext Transfer Protocol (HTTP), Uniform Resource Locator (URL)*

globally unique identifier (GUID)

In Microsoft Corporation operating system platforms and programming, a 128-bit value based on time and space that can be used to uniquely identify a component.

Overview

Globally unique identifiers (GUIDs) are employed by the Component Object Model (COM) to uniquely identify classes and interfaces so that naming conflicts will not occur. A GUID is virtually guaranteed to be unique across all systems at any time. For example, every object, class, and attribute in Active Directory directory service is assigned a unique GUID when it is created. The GUID of an entity in Active Directory never changes, even if the entity itself is renamed or moved to another location. The GUID acts as a kind of permanent name for the entity within the directory to ensure that it can be positively identified when needed.

Microsoft BackOffice products such as Exchange Server and SQL Server also use GUIDs to uniquely tag objects. For example, the information store in Exchange Server has a base GUID that is used to generate individual GUIDs for all messages, attachments, and folder contents kept in the store. If you restore the information store from a backup, you need to run the command isinteg-patch before restarting the information store to change the base GUID. Running this patch ensures that new objects created in the information store do not accidentally end up with GUIDs that are identical to those of objects already existing in the information store. This could cause inconsistencies in the information store database.

Notes

You can also manually generate GUIDs for components using the console-based Uuidgen utility or the Microsoft Windows–based Guidgen utility in Microsoft Visual C++.

See Also: *Active Directory, Component Object Model (COM)*

Global System for Mobile Communications (GSM)

A second-generation (2G) digital cellular communications technology popular in Europe, Asia, and other parts of the world.

Overview

Global System for Mobile Communications (GSM) is the only truly worldwide cellular communications system. More than 400 different GSM carriers have implemented GSM systems in more than 200 countries and regions, and there are more than 250 million subscribers worldwide (all other cellular systems combined account for only 150 million subscribers worldwide).

GSM cellular supports voice communications rivaling the analog Advanced Mobile Phone Service (AMPS) system in speech quality. GSM also supports other services, including

- Group 3 fax (ITU recommendation T.30)
- Circuit-switched and packet data communications at speeds up to 14.4 kilobits per second (Kbps)
- Short Message Service (SMS), a two-way paging service that supports store-and-forward delivery of short text messages up to 160 characters in length.

GSM also supports other services including caller ID, call waiting, call forwarding, and conference calling.

GSM operates in different frequency bands and is described by different names depending on the band used, including the following:

- **GSM 900 or simply GSM:** This is the original GSM system that began operation in 1992.
- **GSM 1800 or PCN (Personal Communications Network):** This is a high-frequency version of GSM found in parts of Europe and gradually becoming the standard there.
- **GSM 1900 or PCS (Personal Communications System):** This is the counterpart of GSM 1800 in the United States and Canada.

History

GSM began as an initiative of the Conference of European Posts and Telegraphs (CEPT) to develop a pan-European digital communications system that would allow users to roam between different countries and regions with no interruption in service. Work on the new standard was begun in 1982 by a body called Groupe Spéciale Mobile, which gave the technology its acronym, GSM (later on GSM was changed to mean Global System for Mobile Telecommunications). GSM standards development was turned over to the European Telecommunications Standards Institute (TESI) in 1989.

GSM was deployed in several phases, starting with GSM Phase 1, which was first commercially deployed in 1991 and which supported call forwarding, global roaming, call barring, and similar features. These initial 900-megahertz (MHz) GSM systems spread rapidly to 22 different countries and regions by 1993. GSM Phase 2 added additional features such as short message service, call holding, call waiting, caller ID, multiparty calling supporting up to five parties per call, and mobile fax and data services. GSM Phase 2+ deployments currently underway include support for data transmission at 64 Kbps and higher, packet radio, virtual private networks, enhancements to the Subscriber Identity Module (SIM) card, higher spectral efficiency, integration with satellite links, and even GSM services in the local loop.

Architecture

GSM uses a combination of Frequency Division Multiple Access (FDMA) and Time Division Multiple Access (TDMA) media access control methods to provide full-duplex communication. In the 862-to-960-MHz World Association of Radio Communications (WARC) portion of the electromagnetic spectrum, GSM communicates using two separate frequency bands:

- The 890- to 915-MHz band for mobile-to-base (uplink) communication
- The 935- to 960-MHz band for base-to-mobile (downlink) communication

Carrier signals are spaced 200 kilohertz (kHz) apart within these bands based on frequency-division multiplexing (FDM) to provide 124 pairs of superchannels (carriers). Each superchannel is then subdivided using time-division multiplexing (TDM) into eight traffic channels (time slots), some of which are used as communications channels and others as control channels. Each communications channel carries either digitized voice at 13 Kbps or data at either 9.6 or 14.4 Kbps. Altogether GSM provides 992 full-duplex channels for voice communication. By comparison AMPS cellular systems, which also use TDMA, employ three time slots instead of eight.

A single GSM time slot can carry a payload of 156 bits and is 0.577 microseconds in duration, a time interval called the burst period. This suggests that the total data carrying capacity of GSM could theoretically be 33.8 Kbps, but much of this is used for protocol and error correction overhead, reducing the maximum possible data transmission rate to only 14.4 Kbps. The short duration of a GSM time slot also restricts the maximum distance at which a GSM phone can communicate with its base station to about 22 miles (35 kilometers) regardless of the power used.

Power classes for GSM mobile units range from 0.8 through 2.0 watts transmission power for handsets to 8 through 20 watts for vehicle-mounted units. Approximately half of a GSM transmission consists of overhead for signaling, such as synchronization and error handling. Such high overhead is typical in cellular phone systems and is necessary—not so much because of external interference of buildings and other structures, but because of internal interference due to crosstalk between channels and across cell boundaries.



Global System for Mobile Communications (GSM). *The authentication process for GSM.*

Implementation

A basic GSM communications system consists of three parts:

- **Mobile station (MS):** This is a cellular phone or vehicle-mounted phone used for sending and receiving calls. The MS also contains the user's SIM, a small "smart card" about the size of a postage stamp that is issued when a user subscribes to a GSM service. The SIM contains a unique number called an International Mobile Subscriber Identity (IMSI) that uniquely identifies the MS, the user's private key for encrypting transmissions, and billing information, such as the subscriber's address. The MS itself is uniquely identified by a number called an International Mobile Equipment Identity (IMEI), and the IMEI and IMSI are independent of each other. When a user moves from his home location to one where a different GSM system is used, the user can simply remove the SIM from his own GSM phone and install it in a GSM phone rented from a service in that location.
- **Base station subsystem (BSS):** This is a fixed radio transmitter that provides coverage for a specific cell and handles call setup and tear down for mobile stations in the area.
- **Mobile switching center (MSC):** This is a switching center that coordinates the operation of all BSSs in its coverage area, coordinates billing for subscribers, handles roaming and handoffs between cells, and provides gateway connectivity with the Public Switched Telephone Service (PSTN) or Post, Telephone, and Telegraph (PTT) land-based telephone system.

GSM communications are secured by employing key-based encryption for authentication traffic (and optionally for data transfer as well). The diagram shows the process that occurs when a mobile user wants to place a call. When the user dials a number, the mobile unit connects with the base station requesting authorization. The base station generates a random number and transmits it to the mobile unit, which then combines the random number with the owner's secret key stored in the phone's SIM by using a secret ciphering algorithm called A3. The result of this process is transmitted to the base station. Meanwhile, the base station, which has the private keys for all its subscribers stored in a database, follows the same steps, using the A3 algorithm to combine the generated random number with the caller's private key. The result is compared with the result transmitted by the user. If the two results agree, the user is logged on to the system. Encryption of message traffic is similar to encrypted authentication, except that each transmitted frame is encrypted using a different random number. This makes encrypted GSM messages extremely difficult to crack, so much so that some countries and regions prohibit GSM providers from encrypting user messages!

Marketplace

Although GSM is the dominant cellular communications system in Europe and a major player in other parts of the world, such as Asia and the Pacific Rim, it ranks a distant third in North America behind the popular Code Division Multiple Access (CDMA) digital cellular systems such as Sprint PCS and behind Time Division Multiple Access (TDMA) systems best represented by AT&T Wireless Services and SBC Communications. This is changing, however, as U.S. GSM carriers such as VoiceStream Wireless Corporation (now owned by Deutsche Telekom) expand their coverage across areas connecting urban centers, especially in California, the Eastern seaboard states, Florida and the South, and the Texas-Minneapolis corridor.

With interoperability between these competing systems being a major issue for U.S. subscribers needing to travel abroad, QUALCOMM, the company behind CDMA cellular systems, has announced it plans to develop a chip that will enable cellular phones to work with both CDMA and GSM systems.

Prospects

GSM has fared well as a global standard communications technology apart from garnering little support in the United States. Initiatives are underway to enhance this 2G system into one capable of carrying data at speeds of 64 Kbps and higher. Two such upgrades are the General Packet Radio Service (GPRS) and High Speed Circuit Switched Data (HSCSD), both of which operate by multiplexing GSM’s existing TDM slots. These 2.5G initiatives are stepping stones toward the next generation high-speed third-generation (3G) broadband cellular systems that are just beginning to appear in parts of the world.

Notes

GSM has a counterpart service called Digital Communication Service (DCS) that works in essentially the same way as GSM, except at a higher 1.8-gigahertz (GHz) frequency band. DCS provides a total of 2992 channels for voice communication. One advantage DCS has over GSM is that it uses much lower power levels for mobile units, ranging from 0.25 to 1.0 watts transmission power.

For More Information

Visit the GSM Association at *www.gsmworld.com.*

See Also: *2G, 2.5G, 3G, Advanced Mobile Phone Service (AMPS), cellular communications, Code Division Multiple Access (CDMA), General Packet Radio Service (GPRS), High-Speed Circuit Switched Data (HSCSD), Time Division Multiple Access (TDMA)*

global user account

A Microsoft Windows NT account that has a domain-wide scope.

Overview

In Windows NT, global user accounts are stored in the Security Accounts Manager (SAM) database on domain controllers. You can create them using User Manager for Domains, a Windows NT administrative tool. Global accounts allow users to take full advantage of the Windows NT Directory Services (NTDS). Users who have global accounts can access resources anywhere in the domain, provided they have permissions for those resources.

The other type of user account in Windows, the local user account, exists only within the directory database of the machine on which it is created. Use only global accounts for users when implementing Windows NT domains as your security model. User Manager for Domains creates global accounts by default.

Notes

In Windows 2000 and Windows .NET Server, global user accounts are instead called domain user accounts and they are managed using the Active Directory Users and Computers snap-in for the Microsoft Management Console (MMC).

See Also: *local user account, user account*

GNOME

Stands for GNU Object Modeling Environment, a graphical desktop for UNIX and Linux platforms.

See: *GNU Object Modeling Environment (GNOME)*

GNU General Public License (GPL)

The open source licensing scheme of the Free Software Foundation (FSF).

Overview

The GNU Project was started in 1984 with the aim of developing a UNIX-like operating system that could be freely distributed. The acronym GNU itself recursively stands for GNU's Not UNIX (recursion is a feature of the UNIX operating system). The GNU General Public License (GPL) allows developers to freely copy and make changes to software as long as they provide the source code freely upon request and do not add any additional copyright restrictions to the modified software.

GPL is the licensing scheme used in all distributions of Linux, the popular free operating system developed by Linus Torvalds. The GNU gcc compiler is also the only C compiler that can be used to compile the Linux kernel. GPL forms the basis for licensing much of the free software that drives the Internet. GPL has also been chosen by Sun Microsystems as the licensing scheme for its free StarOffice suite of business applications.

See Also: *Linux, UNIX*

GNU Object Modeling Environment (GNOME)

A graphical desktop for UNIX and Linux platforms.

Overview

GNU Object Modeling Environment (GNOME) is an open-source graphical user interface (GUI) developed by the GNOME Foundation under the GNU General Public License (GPL) licensing scheme. The GNOME Foundation was modeled after the Apache Foundation and includes such members as the Free Software Foundations (the originators of GPL), IBM, Hewlett-Packard, Compaq Computer Corporation, Sun Microsystems, Red Hat, and many others.

GNOME's purpose is to make UNIX and Linux platforms easier to use. GNOME is a highly configurable windows–based user environment that includes a desktop with application icons, a status panel, a set of tools, and other elements. The GNOME session manager allows a user's desktop settings to be maintained across user sessions.

Prospects

A competing open-source alternative to GNOME is the K Desktop Environment (KDE) developed under the auspices of the KDE League. KDE has many supporters, but GNOME is backed by industry heavyweights and has been selected by Hewlett-Packard as the standard graphical user interface for HP-UX and by Sun as the GUI for Solaris.

For More Information

You can visit the GNOME Developer's Site at *developer.gnome.org.*

See Also: *GNU General Public License (GPL), K Desktop Environment (KDE), Linux, UNIX*

Gopher

A legacy Internet protocol used for distributed storage of documents.

Overview

Gopher is similar to another Internet protocol, File Transfer Protocol (FTP), because it remotely accesses files over a Transmission Control Protocol/Internet Protocol (TCP/IP) internetwork such as the Internet. But although an FTP site exists on only one server and there can be many different FTP sites, there's really only one distributed Gopher file system. The Gopher file system is a single collection of all Gopher servers in the world (although private Gopher subnetworks could also exist).

Gopher was popular in the late 1980s and early 1990s as a mechanism for storing and disseminating information across the Internet, especially for libraries and universities, but it has fallen out of favor because of the rising popularity of the World Wide Web (WWW). Not many Gopher servers still work, and most of them are not regularly updated with new information.


Gopher directory at gopher.tc.umn.edu - Microsoft Internet Explorer
File
Edit
View
Favorites
Tools
Help
Back
Forward
Stop
Refresh
Home
Search
Favorites
History
Mail
Print
Address
gopher://gopher.tc.umn.edu/11/Information%20About%20Gopher%09%09%2
Go
Links
Done
Internet

Gopher directory at gopher.tc.umn.edu

```
11/11/94 05:55PM          1,024 About Gopher
                          <DIR> Gopher News Archive
                          <DIR> GopherCON '95
                          <DIR> GopherCON '94
                          <DIR> Gopher Software Distribution
07/21/98 08:53PM          <DIR> Commercial Gopher Software
                          <DIR> Gopher Protocol Information
                                University of Minnesota Gopher softw
                                Frequently Asked Questions about Gop
                          <DIR> Gopher+ example server
                          <DIR> comp.infosystems.gopher (USENET news
```

Gopher. *The simple interface of the legacy Gopher protocol.*

Implementation

Any Gopher server can act as a logical root of the hierarchical Gopher distributed file system. To access a file or document, a person using a Gopher client (a standard Web browser such as Microsoft Internet Explorer will do) types the Uniform Resource Locator (URL) of an accessible Gopher server. For example, *gopher://gopher.tc.umn.edu* takes the user to a Gopher server for the University of Minnesota (where Gopher originated). The Gopher file system is presented as a series of folders, each of which can contain

- Additional folders
- Individual documents
- Links to other Gopher servers (displayed as folders)

Users then work their way down the "gopher hole" (to use the metaphor) until they locate the document they want, and then they display or download it. They can also use a search tool developed at the University of Nevada called Veronica (Very Easy Rodent-Oriented Netwide Index to Computerized Archives) to perform keyword searches to locate documents on the worldwide Gopher network.

See Also: *Uniform Resource Locator (URL), World Wide Web (WWW)*

GPL

Stands for GNU General Public License, the open source licensing scheme of the Free Software Foundation.

See: *GNU General Public License (GPL)*

GPRS

Stands for General Packet Radio Service, a 2.5G upgrade to second-generation (2G) Time Division Multiple Access (TDMA) cellular communications systems.

See: *General Packet Radio Service (GPRS)*

grep

Stands for global regular expression print, a powerful UNIX command.

Overview

Grep lets you search a file or multiple files for a specific pattern or string of characters and, if desired, replace it with a different string. Grep is also useful for searching for specific entries in text files such as log files, UNIX system error logs, or C program code files.

You can use wildcards and other meta-characters to perform complex search and replace operations with grep. The output of grep is a display of each line of the file that contains the desired character string.

Examples

Typing **grep 'a[b-f]' log.txt** searches the text file called log.txt for any lines that contain the character *a* immediately followed by *b*, *c*, *d*, *e*, or *f*.

Notes

Shareware versions of the grep utility are available from third-party vendors for Microsoft Windows platforms. Grep can also be combined with other UNIX commands in scripts that can perform more complex search functions. For example, you can pipe the output of a verbose command into grep to display a more selective form of output.

See Also: *UNIX*

ground loop

A condition created when two or more parts of a network are grounded at separate points, causing a voltage difference between connected networking components.

Overview

Voltage differences between different parts of a computer network typically occur because of nonuniformities in the electrical characteristics of the grounding at different locations. For example, consider two computers that are located some distance apart and are connected by coaxial cabling. Each device is also connected to the earth by the ground wire of its AC power cable, but the two devices are plugged into different power outlets. These power outlets are connected to different parts of your building's electrical distribution system, and these different parts are under different loads (have different currents being drawn from them by different configurations of devices). Thus they provide slightly different voltages.

You might also find slight differences in the ground potential at the two locations. These voltage differences can cause currents to be induced through the shielding of the network cabling, and these currents can be large because of the cable's low resistance. Large pulses of current can occur when other devices on the power circuits are switched on or off abruptly. This situation can be potentially damaging to sensitive networking components and might cause them to reset or lock up.

Implementation

You can prevent ground loops in two main ways:

- By using nonconducting fiber-optic cabling instead of copper cabling, especially for longer cable runs
- By employing opto isolators or isolation transformers to break electrical connections between networking components

One might think that you could eliminate ground loops entirely by not grounding networking equipment, but this is wrong for several reasons. Ground connections are essential for electrical equipment to ensure their safety in the case of a short, and all electrical equipment should be properly grounded to ensure against shock hazard. Grounding also reduces noise due to electromagnetic interference (EMI) that can affect the performance of hubs, switches, and cables. Noise can result in corrupted packets leading to retransmissions that eat up network bandwidth, and grounding equipment properly can reduce such noise and boost throughput.

Notes

Ground loops are especially problematic with serial connections such as RS-232 because cables using this interface have a second signal ground path between the devices. Ground loops can also be a problem with shielded cabling such as shielded twisted-pair (STP) cabling or coaxial cabling. These loops will occur if the cable's shielding is grounded by a direct connection to the chassis of the devices, because this provides a second ground path between the devices in addition to that produced by the ground portion of the AC power connection. The resulting current loops can build up until they are potentially damaging to the connected equipment. To prevent such damage, the shielding in a shielded cable should be grounded only at one end of its connection. Finally, when grounding a metal rack or cabinet that houses networking equipment, you should ground it using the same AC power cable ground connection that you used for the equipment itself. Note that ground loops are not a significant problem with unshielded twisted-pair (UTP) cabling because the wiring is transformer-isolated in the hub and network interface card (NIC) connections.

See Also: *opto isolator*

group

A collection of user accounts.

Overview

Groups simplify the task of network administration by allowing administrators to group similar user accounts together in order to grant them similar rights and permissions. In Microsoft Windows 2000 and Windows .NET Server, there are two types of groups:

- **Security groups:** Can contain members and can be granted permissions in order to control user access to network resources. Security groups can contain users, other groups, and even computers.
- **Distribution groups:** Used for nonsecurity functions, such as grouping users together to send mass

e-mail. Unlike security groups, these groups cannot be used to control user access to network resources.

In Windows NT there is only one type of group, which is equivalent to security groups in Windows 2000 and Windows .NET Server.

Implementation

In Windows 2000 and Windows .NET Server, you create groups using the Active Directory Users and Computers console, and these are stored as group objects within Active Directory directory service. In Windows NT, you create groups using User Manager for Domains, and they are stored in the Security Accounts Manager (SAM) database. Users can belong to multiple groups at the same time. A group does not actually contain its member user accounts; it is merely a list of user accounts.

The scope of a group is the portion of the network where the group can be granted rights and permissions. For example, a group whose scope is global can be granted permissions to resources in its own domain and to resources in trusting domains. On the other hand, a group whose scope is local can be granted permissions to resources only on the machine where it was created. In Windows 2000 and Windows .NET Server, there are three levels of scope for security groups:

- **Universal groups:** Can contain members from any domain and can be granted permissions to resources in any domain in the current domain forest. Universal groups can contain user accounts, global groups, and universal groups from any domain in the current forest. Note that you can create universal groups only when the domain is in native mode and not in mixed mode.
- **Global groups:** Can contain members only from their own domain but can be granted permissions to resources in any trusting domain. When the domain is in native mode, global groups can contain user accounts and global groups from the same domain. When the domain is in mixed mode, these groups can contain only user accounts.
- **Domain local groups:** Can contain members from any domain but can be granted permissions only to resources in their own domain. However, unlike the local groups of Windows NT, a domain local group can be granted permissions to resources on all servers (both the domain controllers and member servers) in its domain. When the domain is in mixed mode, domain local groups can contain user accounts and global groups from any domain in the forest. When the domain is in native mode, they can also contain domain local groups from their own domain and universal groups from any domain in the forest.

On Windows 2000 and Windows .NET Server member servers and client computers and Windows XP machines, you can also create a fourth scope of group called a local group, one that exists only within the local security database of the machine on which it is created. Local groups in Windows 2000, Windows .NET Server, and Windows XP are similar to local groups in Windows NT. They can contain user accounts that are local to the machine and user accounts and global groups from their own domain. A local group can be granted permissions only to resources on the machine where it was created. You use Local Users and Groups, a snap-in for Microsoft Management Console (MMC), to create local groups on a machine.

Windows NT groups have only two levels of scope:

- **Global groups:** A global group can be granted permissions to resources in its own domain and to resources in trusting domains. A global group can contain user accounts only from its own domain. Global groups are created on Windows NT domain controllers and exist in the domain directory database.
- **Local groups:** A local group created with Windows NT Workstation can be granted permissions only to resources on the machine where it was created. A local group created with Windows NT Server (on a domain controller) can be granted permissions only to resources on the domain controllers of its own domain. A local group can contain user accounts and global groups both from its own domain and from trusted domains. Network administrators of enterprise-level Windows NT networks can use a resource-access strategy called AGLP (Accounts are organized by placing them in Global groups, which are then placed in Local groups that have appropriate Permissions and rights assigned to them) to plan and implement local groups in their network.


Nesting of groups in Windows NT
G
L
Trusted domain
Trusting domain
Nesting of groups in Windows 2000 and Windows .NET Server
U
Any domain
U
G
Any domain
Any domain
G
G
Same domain
U
Any domain
DL
Same domain
DL
G
Any domain
U Universal
G Global
DL Domain local
L Local

Group. *Nesting of groups in Windows NT and in Windows 2000 and Windows .NET Server.*

In Windows 2000 and Windows .NET Server, you can change the scope of a group if you want (you cannot do this in Windows NT). For example,

- Global groups that are not members of other global groups can be converted to universal groups.
- Domain local groups that do not contain other domain local groups can be converted to universal groups. Do this if you want to enable users in other domains to access resources that have been made accessible to the domain local group under consideration.

Groups can also be nested by adding groups to other groups, with certain restrictions. For example, in Windows NT a local group can contain global groups (but not other local groups) as members, but a global group can contain only users as members, not other global or local groups. With Windows 2000 and Windows .NET Server, the nesting of groups is more complicated, as shown in the diagram. Furthermore, when running Windows 2000 or Windows .NET Server in native mode, you can nest groups inside groups to any level, although nesting to one level is the recommended practice for effective administration.

Notes

If your Windows 2000 or Windows .NET Server network has a single domain, use global groups and domain local groups to grant permissions to network resources. Create global groups according to function, add users to the global groups, create domain local groups according to groups of common resources, assign permissions to the domain local groups, and finally, place the global groups in the appropriate domain local groups. If you have a domain tree, use global and universal groups instead in a similar administrative approach.

On high-speed Windows 2000 and Windows .NET Server networks, using only universal groups simplifies network administration. But if you have slower wide area network (WAN) links within your enterprise, using global and domain local groups can reduce the size of the global catalog at each site and significantly reduce the WAN traffic required to keep the global catalog current. Using global and domain local groups further reduces WAN traffic by reducing the size of users' security tokens.

See Also: *domain local group, global group, local group, universal group*

group account

Another name for a group, a collection of user accounts.

See: *group*

Group Policy

A feature of Microsoft Windows 2000, Windows XP, and Windows .NET Server that simplifies management of user and computer settings.

Overview

Group Policy enables administrators of Windows 2000 and Windows .NET Server networks to define policies that manage the environment of users and computers. A typical use for group policies is to enforce a written company policy across all users in a specific site or domain. Group policies can used to simultaneously configure the desktop working environments for different groups of users, but they have many other uses as well. For example, group policies can be used to do the following:

- Manage applications—for example, by configuring policies to allow users to install applications published in Active Directory directory service or to automatically install or upgrade applications on their machines
- Redirect folders from the Documents and Settings folder on a user's local machine to a share on the network
- Assign scripts for startup, shutdown, logon, and logoff events
- Manage security—for example, to control users' access to files and folders, control user logon rights, and configure account lockout restrictions
- Manage software—for example, to configure user profiles such as desktop settings, Start menu, and other common settings

Implementation

Group policies can be assigned to domains, sites, or organizational units (OUs) and apply to all Active Directory objects (users, computers, printers, and so on) within these containers. To assign a group policy, first use the Group Policy snap-in for the Microsoft Management Console (MMC) to create a Group Policy object (GPO) and configure its settings, and then assign the GPO to the appropriate container. An object may have several GPOs influencing it (for example, one GPO assigned to the OU containing the object and another to the domain containing the OU). If this is the case, a conflict may occur, and then the last setting applied wins. Group policies are applied to users when they log on and to computers when they boot up. Users are subject to both GPO settings that apply to them as users and to GPO settings that apply to the computer at which they are working.


Group Policy
Console
Window
Help
Action
View
Favorites
Tree
Favorites
Console Root
Default Domain Controllers Policy [
Computer Configuration
Software Settings
Windows Settings
Administrative Templates
Windows Components
System
Network
Printers
User Configuration
Software Settings
Windows Settings
Administrative Templates
Policy
Logon
Disk Quotas
Group Policy
System File Protection
Remove Security option from Start menu (Terminal Server Only)
Remove Disconnect item from Start menu (Terminal Server Only)
Disable Boot / Shutdown / Logon / Logoff status messages
Verbose vs normal status messages
Enable\Disable CD-ROM automatic play feature
Disable Windows Welcome at Logon
Run these applications at startup
Disable the RunOnce at startup
Disable legacy Run at startup

Group Policy. *Using the Group Policy console to configure a Group Policy Object (GPO).*

GPOs are really abstractions whose contents are stored in two different locations:

- **Group Policy Container (GPC):** This is a container within the Active Directory database on domain controllers that contains information about the globally unique identifier (GUID), version number, permissions, and inheritance of the GPO.
- **Group Policy Template (GPT):** This is a folder within the SYSVOL volume on domain controllers. It contains the actual GPO settings themselves and is identified by the GUID of the GPO.

Every Windows 2000 or Windows .NET Server domain has a default GPO that applies to all users and computers in the domain. Computers that are moved to a different domain lose the GPO of their original domain and have the GPO of their new domain applied to them. The default GPO for a domain is the only GPO on which you can configure password restrictions, lockout restrictions, Kerberos, the Encrypting File System (EFS), and Internet Protocol (IP) security settings.

Notes

You cannot use Group Policy for Windows 2000 or Windows .NET Server to configure group policies for downlevel Windows NT, Windows 95, or Windows 98 clients. Instead, use System Policy Editor, a Windows NT tool that stores policy settings in a file called ntconfig.pol that modifies a portion of the Windows NT registry.

FullArmor offers a tool called FAZAM 2000 that simplifies the planning, deployment, and management of group policies. You can find more info at *www.fullarmor.com*.

See Also: *Active Directory, domain controller*

GSM

Stands for Global System for Mobile Communications, a second-generation (2G) digital cellular communications technology popular in Europe, Asia, and other parts of the world.

See: *Global System for Mobile Communications (GSM)*

GSNW

Stands for Gateway Services for NetWare, a feature of Windows 2000 Server that allows Windows clients access to NetWare file, print, and directory services.

See: *Gateway Service for NetWare (GSNW)*

Guest account

A built-in account in Microsoft Windows 2000, Windows XP, and Windows .NET Server used for guest access to network resources.

Overview

The Guest account is intended for occasional users who need temporary access to resources on the network. It is disabled by default and can be enabled using User Manager for Domains. The Guest user account is a member of the Domain Guests global group and is assigned a null password during installation.

The Guest account is a domain user account on a domain controller. On a member server or workstation, however, there's a separate Guest local user account.

You should not enable the Guest account unless you are sure you will need it. You should also make sure that all your shared resources have correct permissions assigned to them because enabling the Guest account otherwise could pose a security risk.

See Also: *Guests group*

Guests group

A built-in group in the Microsoft Windows 2000, Windows XP, and Windows .NET Server operating systems whose members can be assigned guest access to network access.

Overview

The Guests group is a domain local group whose initial membership is the built-in Guest domain user account. If a member server or workstation joins a domain, the global group called Domain Guests is added to the local Guests group.

The Guests group has no preassigned rights or permissions. You can assign any network resource permissions to this group in order to grant temporary or guest users the access they require. Members of the Guests group do not have the right to make permanent changes to their desktop settings.

See Also: *built-in group, Guest account*

GUID

Stands for globally unique identifier; in Microsoft operating system platforms and programming, a 128-bit value based on time and space that can be used to uniquely identify a component.

See: *globally unique identifier (GUID)*

H.323

A videoconferencing standard developed by the International Telecommunication Union (ITU).

Overview

H.323 is a comprehensive suite of protocols for voice, video, and data communications between computers, terminals, network devices, and network services. H.323 is designed to enable users to make point-to-point multimedia phone calls over connectionless packet-switching networks such as private Internet Protocol (IP) internetworks and the Internet. H.323 was designed to replace the earlier H.320 standard that ran over circuit-switched services such as Integrated Services Digital Network (ISDN) telephone systems.

H.323 is widely supported by manufacturers of videoconferencing equipment, Voice over IP (VoIP) equipment, and Internet telephony software and devices. Any hardware or software system that supports the H.323 standard can communicate easily with any other H.323 system. With ordinary telephone communications, you can purchase a telephone from any vendor, plug it into your phone system, and the equipment works and interoperates with other devices already on the system. The idea behind H.323 is to make multimedia communications over the Internet easy to set up and use.

Architecture

The H.323 protocol stack performs various functions related to establishing and maintaining real-time communications over voice, video, and data. H.323 does not represent a single standard, but rather an umbrella of many other ITU standards. The H.323 protocol stack includes more than two dozen G-level, H-level, and T-level protocols, including

- H.323 Conference Manager, which manages the establishment of multimedia conferencing connections
- The H.245 protocol, which controls communication with data terminal equipment (DTE)
- The H.225 protocol, which performs synchronization and framing mechanisms for multimedia data streams
- The T.120 protocol, which provides support for real-time, multipoint data communication

H.323 also specifies standard codecs for audio (G.723) and for video (H.263) that enable H.323 products to send and receive voice and video images. Specifically, H.323 defines standards for data codecs for audio transmission rates of 14.4 kilobits per second (Kbps) or faster, and video transmission rates of 28.8 Kbps or faster. H.323 recognizes the T.120 protocol for data conferencing and provides a set of standards-based conferencing features for audio and video conferencing.

Implementation

An H.323 network consists of four different types of entities:

- **Terminals:** These are the client end points for multimedia communications. An example would be an H.323-enabled Internet phone or PC.
- **Gateways:** These provide connectivity between H.323 networks and other communications services such as the circuit-switched Public Switched Telephone Network (PSTN).
- **Gatekeepers:** These provide services for call set up and tear down, and registering H.323 terminals for communications.
- **Multipoint control units (MCUs):** These support three-way and higher multipoint communications between terminals.

Marketplace

Many vendors provide H.323 videoconferencing systems and appliances. Examples include Polycom's

ViewStation MP, a popular system in many enterprise environments. Other vendors include Sony Corporation with its Contact system (which also works over ISDN) and VCON's MC6000 that is multicast-capable.



H.323. *Components of an H.323 network.*

PC-based H.323 collaboration software products include PictureTel Corporation's 900 Series appliances, which support both H.323 and H.320 communications; VCOM's MC8000; Intel Corporation's TeamStation; and VTEL Corporation's SmartStation.

Prospects

H.323 was extolled by industry in the 1990s but is now beginning to be considered legacy technology, suitable mainly for migrating legacy telephony systems to VoIP and for interoperating with legacy Private Branch Exchanges (PBXs). The problem is that H.323 was designed with videoconferencing strictly in mind and is not flexible enough to support a full range of VoIP features.

A newer protocol proposed by the Internet Engineering Task Force (IETF) is Session Initiation Protocol (SIP), which is seen in some quarters as preferable for newer VoIP deployments. SIP is designed from the ground up to support IP and is slimmer and more flexible than H.323, a protocol known to have excessive overhead.

Notes

The OpenH323 Project is an initiative of Equivalence Pty Ltd. to develop an open-source version of the H.323 protocol suite licensed under Mozilla Public License (MPL).

See Also: *session initiation protocol (SIP), T.120, Voice over IP (VoIP)*

H.323 gateway

A service that allows you to connect an H.323-based communication system on the Internet to a telephony system.



H.323 gateway. *Making a phone call using an H.323 gateway.*

Overview

You can use H.323 gateways to connect corporate networks to telephony systems for supporting integrated audio and video conferencing. For example, you can use an H.323 gateway to place a Microsoft NetMeeting call to someone's telephone. The Uniform Resource Locator (URL) format for doing so is "callto:<address>", in which <address> is the fully qualified domain name (FQDN), Internet Protocol (IP) address, or e-mail address of the person you are calling. You can use this URL as a link on a Web page or enter it directly in the address box of your Web browser.

NetMeeting does not include any H.323 gateway software, but third-party gateways are supported.

See Also: *gateway, H.323*

hacking

The action of trying to compromise the security of a computer system or network.

Overview

In the 1980s the term *hacker* was used to describe curious programmers who enjoyed getting into the nuts and bolts of how computer systems worked, usually UNIX systems and Transmission Control Protocol/Internet Protocol (TCP/IP) networks. In the 1990s hacking emerged as a malicious pursuit with the goal of stealing information, crashing systems, bringing down networks, and interfering with the daily activities of businesses and governments worldwide.

Various kinds of activities constitute hacking, but their overall similarity is that they are performed with malicious intent and without the knowledge or permission of the systems being hacked. Some of the different types of activities that hackers perform include

- **Footprinting:** The initial stage of a hacker's activities involves getting as much background information about the target system or network as possible. For example, a list of Internet Protocol (IP) addresses could be obtained through a simple whois query or by zone transfers from Domain Name System (DNS) servers.
- **Scanning:** Uses such tools as ping, traceroute, and netstat to identify the topology of a network and the types of hosts it contains. Port scanning involves testing hosts for open ports through which the attacker can gain access. Some common ports to scan include port 23 (telnet), 512 (rexec), and 513 (rlogin).
- **Enumeration:** The process by which hackers determine valid user accounts, names of shared resources, versions of installed applications, and other information.
- **Sniffing:** Using widely available tools, hackers can quietly capture traffic between clients and servers in order to obtain credentials and other useful information for breaking into systems.
- **Diffing:** This involves comparing two files for differences, and it is typically used to try to extract encrypted passwords from database files in which they are stored. Once extracted, these encrypted passwords can be subjected to dictionary and brute force attacks to try to crack them.
- **Back doors:** Software manufacturers sometimes leave secret user accounts created in their products so administrators have a "back door" to get in if they lock themselves out by invalidating their account. Hackers test commercial software to try to find such back doors. Also, once hackers have compromised a system, they generally try to create a back door for themselves on the system in case they are discovered and locked out.
- **Wardialing:** Using automated dialing software and modems to try to find entry points to remote networks.
- **Script Kiddies:** Novice hackers who employ scripts and other tools written by experienced hackers to test systems for vulnerabilities and launch automated attacks.
- **Social engineering:** A potentially devastating form of attack in which the hacker enters the building posing as a system administrator, repair person, or other trusted individual and gains unauthorized access to network resources. This takes more guts than the usual forms of hacking, though!

Types

Hacker attacks fall under a number of different categories, including the following:

- **Denial of Service (DoS):** Blocks access by legitimate users to a system or network by using up all available resources. Examples include LAND attacks, SYN flooding, Smurf attacks, and Teardrop attacks. The first famous DoS attack was the Internet Worm created by Robert Morris in 1988. Another notable attack was developed by Kevin Mitnick in 1995 to exploit weaknesses in the Internet Control Message Protocol (ICMP) and Transmission Control Protocol (TCP) protocols that had long been recognized in academic circles but had never been deliberately exploited.
- **Distributed Denial of Service (DDoS):** Employs large numbers of compromised intermediate machines called zombies to launch an overwhelming attack against a system or network. In February 2000, DDoS attacks were launched against a number of high-profile Web sites, including Yahoo!, and brought down these sites for several hours.
- **Elevation of privileges:** The goal is to enable the attacker to elevate his privilege level for accessing system resources from anonymous user to root (administrator), if possible.
- **Buffer overflow:** Flaws in software may cause systems to crash when invalid data is submitted through Uniform Resource Locators (URLs), Web forms, and other user interfaces. Besides crashing systems, buffer overflows can sometimes give hackers the ability to execute arbitrary code on the systems affected.
- **Spoofing:** Assuming the identity of a trusted user or of another system in order to gain access to a resource.
- **Session hijacking:** This involves taking the place of the client in an existing client/server connection such as a TCP connection. Session hijacking is a form of the man-in-the-middle attack.

Notes

The Openhack Project was developed by eWeek Labs to help publicize the issues around hacking of business networks. The project challenged people to try deliberately attacking a test bed network, and the results of these attempts were published to help educate people on how hackers perform their attacks.

For More Information

Visit the Microsoft Security site at *www.microsoft.com/security.*

See Also: *denial of service (DoS), security*

Hailstorm

An emerging platform for development of Internet-based services from Microsoft Corporation based on its new .NET platform.

Overview

In many ways, Microsoft Hailstorm represents the next evolutionary stage of the Internet. Hailstorm is a user-centric architecture based on Microsoft's .NET platform and on the open standards Extensible Markup Language (XML), Simple Object Access Protocol (SOAP), and Universal Description and Discovery Interface (UDDI).

Hailstorm provides users with a standard set of Web services that enables users to collaborate and participate in business transactions seamlessly and transparently. Hailstorm places control squarely in the user's court—data is not shared unless users explicitly grant their consent to do so. This makes Hailstorm a secure platform for 21st-century business communications in the Internet economy.

Initial support for Hailstorm is included in Microsoft's Windows XP, Office XP, and Xbox platforms. Hailstorm transforms MSN Messenger into an enterprise and consumer development platform for building advanced user experiences that leverage the power of Internet-based instant messaging.

Architecture

Hailstorm services are designed to allow users to access their data from a variety of platforms, including traditional PCs, Tablet PCs, handheld Personal Digital Assistants (PDAs), mobile phones, and other Web appliances. User data is stored in a distributed fashion and can be securely accessed from any device and any location with the user's consent.

Users and applications access Hailstorm services through end points, which may be applications, devices, or services. With a user's consent, Hailstorm automatically connects end points to widely distributed Web services to perform transactions desired by the user. Hailstorm services are XML-enabled Web services running on the .NET platform and are built upon the foundation service Microsoft Passport, which provides security and authentication to perform transactions. Other parts of a user's experience supported by Hailstorm's Web services include profile information, location information, and calendar information. The table lists the initial set of core Web services to be included in Hailstorm.

Initial Set of Web Services Included in Microsoft Hailstorm

Service	*Description*
myAddress	User's address
myApplication Settings	User's application settings
myCalendar	User's time and task management information
myContacts	User's list of contacts
myDevices	Settings and capabilities of user's devices
myDocuments	Location for storing user's personal files
myFavorite WebSites	User's favorite Uniform Resource Locators (URLs)
myInbox	User's inbox for e-mail and voice mail
myLocation	User's geographical location
myNotifications	User's subscriptions and notifications
myProfile	User's personal profile information such as nickname, birth date, etc.
myServices	Services provided to user by Hailstorm
myUsage	User's usage of Hailstorm services
MyWallet	Receipts, coupons, and payment instruments for user's transactions

For More Information

Find out more about Hailstorm at *www.microsoft.com/hailstorm.*

See Also: *.NET platform*

HAL

Stands for hardware abstraction layer, a thin layer of software at the base of the Microsoft Windows 2000, Windows XP, and Windows .NET Server operating systems that provides portability between different machine architectures and processor platforms.

See: *hardware abstraction layer (HAL)*

half-duplex

A mode of communication where at any given moment data can be either transmitted or received but cannot be transmitted and received simultaneously.

Overview

The simplest example of half-duplex communications is using a walkie-talkie: you have to press a button to talk and release the button to listen. When two people use walkie-talkies to communicate, at any given moment only one of them can talk while the other listens. If both try to talk simultaneously, a collision occurs and neither hears what the other says.

Communication through traditional hub-based Ethernet networks is another example of half-duplex communications. When one station on an Ethernet network transmits, the other stations detect the carrier signal and listen instead of transmitting themselves. If two stations transmit signals simultaneously, a collision occurs and both stations stop transmitting and wait random intervals of time before retransmitting.

By contrast, full-duplex communication enables stations to transmit and receive signals simultaneously, with the advantage of providing twice the bandwidth of equivalent half-duplex technologies. However, full-duplex requires two communication channels to achieve these results—one to transmit and one to receive signals. Hub-based Ethernet networks can only be used for half-duplex communications—for full-duplex Ethernet, you need switches instead of hubs.

A third mode of communications is called simplex, which involves transmission in one direction only, with one station transmitting signals and the other receiving them. A television broadcast is a simple example of simplex communications.

See Also: *Ethernet, full-duplex, simplex*

HAN

Stands for home area network, a network of several computers at a user's home.

See: *home area network (HAN)*

handheld

Generally used to refer to Personal Digital Assistants (PDAs) and other computers that can be held in the palm of the hand.

Overview

In the late 1990s the handheld market became popular among consumers for managing contacts, appointments, and other personal information. At the end of the decade, the issue arose as to which of the two common platforms, Palm and Microsoft Windows CE, would dominate in the enterprise market. The outcome is still uncertain. Palm has the advantage of a large installed base, a wide range of third-party applications, and support by such popular wireless services as AvantGo. The new PocketPC platform has made the Windows CE operating system competitive with the PalmOS by providing interoperability with Windows-based services, and pocket versions of Microsoft Office applications, Microsoft Internet Explorer. At the end of 2000, analysts reported that Palm held three-quarters of the handheld market share and Windows CE held only 18 percent, but the Windows CE has been gaining market share steadily.

A newcomer to the handheld market is the Linux PDA, represented by Agenda Computing's VR3. It is too soon to say what impact porting Linux to the handheld platform will have on market leaders Palm and PocketPC.

Handheld Device Markup Language (HDML)

A markup language loosely modeled on Hypertext Markup Language (HTML) and optimized for providing Internet access to cell phones and other handheld devices.

Overview

Handheld Device Markup Language (HDML) was developed by Unwired Planet (now Phone.com) to enable mobile communications devices such as cell phones and Personal Digital Assistants (PDAs) to access content on the Internet. Such devices usually have limited size displays (typically four lines by 20 characters or smaller) and limited processing power that make them require that information they download from the Internet be specially formatted to meet these requirements.

HDML is not intended as a means of delivering standard HTML-formatted Web content to such devices—most standard Web pages simply cannot be reformatted to fit on devices with such small display areas. HDML is not a subset or scaled-down version of HTML but an entirely new markup language specifically designed from the ground up for these devices.

HDML can be used to deliver a broad range of time-sensitive information to handheld wireless devices, including appointments, weather information, stock quotes, telephone directory white pages, inventory, catalog pricing, and similar business and commercial information. Scripts can be developed to extract this kind of information from the databases in which it resides and format it into HDML cards in much the same way that Perl can be used to write scripts to access database information stored on UNIX servers or that Active Server Pages (ASP) can be used to build Web-based applications that connect to Structured Query Language (SQL) databases.

HDML is an open standard guided and licensed by Phone.com. The current version of this technology is HDML 2.

Implementation

HDML provides a way to format information for delivery to handheld wireless devices that support packet-switched Internet Protocol (IP) services instead of traditional circuit-switched cellular services. HDML uses the same Hypertext Transfer Protocol (HTTP) as its application layer protocol, just as HTML does. The difference is that an HDML/HTTP system uses three components (client, server, and gateway) instead of the traditional two (client and server) used by HTML/HTTP.


Request
Response
Cell phone with HDML browser
UP.Link Gateway server at cellular service provider
Web server with HDML content

Handheld Device Markup Language (HDML). *How an HDML communications system works.*

When a user with an HDML-enabled client device (a device running an HDML browser) wants to access HDML-formatted content on a Web server, the client device communicates over the provider's cellular network with a special gateway server called an UP.Link Gateway. This gateway server then "gates" the user's request over a Transmission Control Protocol/Internet Protocol (TCP/IP) wireline connection to the Web server. The Web server responds with the requested content that is then "gated" back to the client over the cellular network.

HDML uses a navigation model that is based on a filing card metaphor. Cards of HDML-formatted information are grouped into "activities," which facilitates the development of HDML-based applications. The user can enter information and share it among cards using variables, and the user can parameterize cards so that a family of cards differing only in the value of a variable can be stored more efficiently in the limited-size cache of these devices. You can use variables to create forms for entering information in HDML applications. HDML currently does not support scripting, branching, or conditional statements.

Marketplace

HDML is currently used by more than 80 cellular and mobile carriers in the United States, including AT&T, Ameritech, and Bell Atlantic. Some analysts estimate that more than 90 percent of Internet-enabled phones sold in the United States support HDML and include Phone.com's HDML browser. Outside the United States, the competing Wireless Markup Language/Wireless Application Protocol (WML/WAP) combination is more popular (WAP shares many of the features of HDML and was developed from HDML).

Prospects

WAP is currently gaining popularity at the expense of HDML and may eventually replace it. One indication of this is Nokia and Ericsson, which are two major players in the world cellular market and which provide WAP-enabled phones. Nokia is even giving away the source code for its WAP browser to promote this standard. Meanwhile, enterprises that want to deploy mobile clients with Internet access have to support two interoperable solutions, HDML and WAP.

See Also: *Hypertext Markup Language (HTML), Hypertext Transfer Protocol (HTTP), Wireless Application Protocol (WAP), Wireless Markup Language (WML)*

handshaking

The process that establishes communication between two telecommunications devices.

Overview

When two computers first connect with each other through modems, the handshaking process determines which protocols, speeds, compression, and error-correction schemes will be used during the communication session. Handshaking is necessary at the start of each session because typically the modems differ in their vendor, model, or hardware/software configuration. The handshake ensures that communication is possible despite these differences.

The term *handshaking* arises from the analogy of two people meeting to conduct business. They first shake hands to greet each other, announcing their names, titles, and intentions. They might also "size each other up" to determine the other person's capacities and capabilities.

During the handshaking process, both modems send the other a series of control signals and respond to each other's signals. Handshaking is also referred to as "flow control" because the process establishes the ground rules for managing the flow of data between the two devices. Some of the parameters that the modems need to negotiate are

- The maximum transmission speed, taking into consideration the speed of both modems and the quality of the transmission
- The length of the line delay to apply echo cancellation
- The communication protocol

Modern modems transmit the control signals in full-duplex mode over the RS-232 interface that connects them to the computers.

See Also: *flow control, modem*

hardware abstraction layer (HAL)

A thin layer of software at the base of the Microsoft Windows 2000, Windows XP, and Windows .NET Server operating systems that provides portability between different machine architectures and processor platforms.

Overview

The hardware abstraction layer (HAL) hides hardware differences from the operating system so that uniform code can be used for all hardware. The HAL thus offers a uniform interface between the underlying hardware and the higher layers of the operating system. All underlying hardware looks the same to the Windows 2000, Windows XP, and Windows .NET Server operating systems because they "see" the hardware through the filtered glasses of the HAL.

The HAL is located at the base of the Executive Services, and it encapsulates most hardware-specific functions that are performed by the operating system. If another portion of the operating system wants to access a hardware device, it must refer its request to the HAL. The HAL handles all communication between the kernel of the operating system and the hardware, particularly those regarding processor commands, system interrupts, and input/output (I/O) interfaces.

Implementation

The HAL is implemented in Windows 2000, Windows XP, and Windows .NET Server as a loadable kernel mode module called hal.dll that is located in the System32 directory. If a hardware vendor needs to protect proprietary technology, the company can develop a custom implementation of the HAL. This means, for example, that different processor configurations such as multiprocessor machines might use different HAL drivers.



Hardware Abstraction Layer (HAL). *How a Windows 2000 application communicates with hardware through the HAL.*

Usually, what happens when Windows 2000, Windows XP, or Windows .NET Server want to access a hardware device is that the operating system issues a command to the appropriate device driver, which then talks to the HAL, which talks directly to the hardware.

Using the wrong HAL driver can result in degraded system performance since all hardware calls made by the operating system go through the HAL. Contact your vendor to make sure that you have the correct HAL for your system. To check which HAL is installed on your system, open the Setup.log file found in the \Winnt\Repair directory and examine the filename after the equal sign. The following table shows a list of HALs that can be installed from the Windows 2000, Windows XP, and Windows .NET Server compact disc.

HALs Found on the Windows 2000, Windows XP, and Windows .NET Server Compact Disc

File name	*Description*
hal.dll	Used for standard PCs
halacpi.dll	Used for PCs supporting Advanced Configuration and Power Interface (ACPI)
halapic.dll	Used for PCs supporting Advanced Programmable Interrupt Controller (APIC)
hapaacpi.dll	Used for PCs supporting both ACPI and APIC
halmps.dll	Used for multiprocessor PCs
halmacpi.dll	Used for multiprocessor PCs that support ACPI
halsp.dll	Used for Compaq SystemPro servers

For More Information

Find out about the HAL Development Kit at *www.microsoft.com/DDK/halkit.*

See Also: *Windows 2000, Windows .NET Server, Windows XP*

hardware address

Also called a MAC address, a unique 6-byte (48-bit) address that is usually permanently burned into a network interface card (NIC) or other physical-layer networking device and uniquely identifies the device on an Ethernet-based network.

See: *MAC address*

Hardware Compatibility List (HCL)

A list of hardware that is compatible with a Microsoft Windows operating system product.

Overview

The Hardware Compatibility List (HCL) for a Microsoft Windows platform defines all supported hardware, including computer systems as well as individual hardware components such as video cards, motherboards, and sound cards. When in doubt, you should consult the HCL before installing an operating system on a nonstandard or customized machine or installing new hardware into a system with an existing operating system. Using components not included on the HCL can lead to installation failures or system instabilities. Microsoft has determined that drivers for hardware devices listed on the HCL are compatible with that version of Windows; Microsoft supports only these drivers.

If you use drivers for devices that are not on the HCL, you might not be entitled to Microsoft product support for your system configuration. If you must use non-HCL devices, contact the device's manufacturer to see whether a supported driver exists for the particular Windows operating system you are using. If you contact Microsoft Product Support Services (PSS) about a problem and the support engineer determines that a hardware device in your system is not on the HCL, you will likely incur a charge for the call even if the problem cannot be resolved.

Notes

You can usually find the HCL for a particular Windows operating system on its distribution CD. (The file might be called hcl.txt.) A more up-to-date version of the HCL for all Windows operating system platforms is available on the Web at the HCL site listed in the "For More Information" section of this entry.

For More Information

You can visit Microsoft Product Support Services at *www.microsoft.com/support.* You can look at the Microsoft HCL site at *www.microsoft.com/hwtest/hcl.*

hardware profile

Information about the configuration of devices and services that are used to boot an operating system into a certain configuration.

Overview

A hardware profile tells the operating system which devices are present when the computer boots.

You can create several different hardware profiles on Microsoft Windows operating systems and select the one you want to use at boot time. For example, if

Windows 2000 is installed on a laptop computer, you can create two hardware profiles for that computer:

- One profile for when the computer is docked and connected to the network. (The profile will contain configuration information for the network adapter.)
- Another profile for when the computer is undocked and used in the field. (The profile will contain no configuration information about networking.)

When the laptop is booted, you select the appropriate hardware profile from a menu generated by the operating system.

Notes

Hardware profiles are usually not necessary for plug-and-play laptops running Windows 2000, Windows XP, or Windows .NET Server. These computers can recognize when new hardware becomes available (for example, by docking) and automatically configure themselves.

hashing algorithm

A mathematical procedure for randomizing (hashing) information to make it more secure in transmission.

Overview

Hasting algorithms take information and scramble it repeatedly to create a fixed-length string of numbers and characters called a hash. A good hashing algorithm has the following characteristic: if you apply a hashing algorithm to some data and then change only a few bits in the data and apply the algorithm again, the two resulting hashes will differ in almost every bit.

Hashing algorithms are used extensively in cryptography for encrypting keys or messages. Examples of popular cryptographic hashing algorithms include MD2, MD4, MD5, and SHA-1. Message Digest 5 (MD5) uses a 128-bit hash, and Secure Hash Algorithm (SHA) uses a 60-bit hash. The more bits in a hash, the greater the security of the encryption process.

Hashing is also used in some database technology for creating indexes of items in a database. Hashes of database objects are generally smaller than the objects themselves, so they can be indexed and searched more quickly. You can generate unique hashes of fixed length for each database record, creating a hash table that you can use for quick searches for records.

See Also: *cryptography, encryption*

HBA

Stands for host bus adapter, a device that converts Peripheral Component Interconnect (PCI) bus signals into Small Computer System Interface (SCSI) or Fibre Channel format.

See: *host bus adapter (HBA)*

H channel

A designation for groups of channels on Basic Rate Interface ISDN (BRI-ISDN) services.

Overview

H channel standards are defined by the International Telecommunication Union (ITU) and are composed of different combinations of Integrated Services Digital Network (ISDN) B channels. The most common configurations are as follows:

- **H0 channel:** This consists of six B channels multiplexed to provide a data transmission speed of 384 kilobits per second (Kbps). This service is sometimes called ISDN H0 or switched 384.
- **H11 channel:** This consists of 24 B channels to provide 1536 kilobits per second (Kbps) of bandwidth. This is sometimes called ISDN H11 or switched 1536.
- **H12 channel:** This consists of 30 B channels to provide 1920 Kbps of bandwidth. This is sometimes called ISDN H12 or switched 1920.

See Also: *B channel, Integrated Services Digital Network (ISDN)*

HCL

Stands for Hardware Compatibility List, a list of hardware that is compatible with a Microsoft Windows operating system product.

See: *Hardware Compatibility List (HCL)*

HDLC

Stands for High-level Data Link Control, an encapsulation protocol for point-to-point serial wide area network (WAN) links.

See: *High-level Data Link Control (HDLC)*

HDML

Stands for Handheld Device Markup Language, a markup language loosely modeled on Hypertext Markup Language (HTML) and optimized for providing Internet access to cell phones and other handheld devices.

See: *Handheld Device Markup Language (HDML)*

HDSL

Stands for High-bit-rate Digital Subscriber Line, a form of Digital Subscriber Line (DSL) technology that provides T-1 speeds in both directions.

See: *High-bit-rate Digital Subscriber Line (HDSL)*

header

The initial portion of a packet or a frame.

Overview

The header typically contains control information such as addressing, routing, and protocol version. The format of this information depends on the protocol being used. For example, an Internet Protocol (IP) header contains information about the version of the IP protocol, the length of the header, the type of service used, the packet's Time to Live (TTL), the source and destination address, and other data. Headers are used to control the flow of packets through the network or over the communication link.

The end of a frame sometimes has a smaller structure called a footer or trailer, but this usually contains only error-checking information. Control information is always placed in the header because this is the first portion of the packet or frame that is read by a networking device such as a switch or a router.

See Also: *frame, packet*

heartbeat

A polling feature of cluster servers.

Overview

An internal communications interface in Microsoft Cluster Server (MSCS) in Microsoft Windows NT Server, Enterprise Edition, and in the Cluster service in Windows 2000 Advanced Server and Windows .NET Enterprise Server, the heartbeat continuously provides interserver communication between cluster nodes in a cluster. One function of the heartbeat is to generate a message that the Cluster service running on one node regularly sends to the Cluster service on the other node to detect a failure within the cluster. Nodes in a cluster communicate status information with each other through the heartbeat using MSCS or the Cluster service. These messages appear as network traffic between the two nodes in the cluster on the dedicated network connection between the nodes, which is called the private network of the cluster. The primary heartbeat network interface is usually a crossover network cable directly attached between cluster nodes or in a private network. If the heartbeat is lost over the private connection, Cluster Server reverts to a public network or alternate connection for its heartbeat and other Cluster service traffic. You can configure the polling interval for the heartbeat using Cluster Administrator.

See Also: *clustering*

Help

Any of several systems of online help for Microsoft Corporation products.

Overview

The type of help features available depends on the nature of the product, the date of release, and the context in which it is invoked. Examples of help functions include the following:

- **Help:** Choose Help from the Start menu in Microsoft Windows 95, Windows 98, Windows NT, Windows 2000, Windows XP, and Windows .NET Server to open a Help Topics window (in Windows XP and Windows .NET Server, the window is called "Help And Support Center"). The window has three tabs: Contents (to browse the help database using a hierarchical set of book icons), Index (to type the topic you want help on and then display the appropriate entry), and Find (named Search in Windows 98 and Windows 2000, to conduct a full-text keyword search of the help database). Windows 2000 includes a fourth tab, Favorites, that lets you save links to Help topics.

In Windows XP and Windows .NET Server, Help has an entirely new look and setup. It now resembles Internet Explorer and offers many new features and customized user options. For example, the mechanism to search Microsoft Online has been integrated into the main search engine.

- **What's This?:** To find information about a setting in a dialog box or property sheet, right-click the item and choose What's This? from the context menu, or click the question mark button at the top right of the dialog box.
- **F1 key:** To get context-sensitive help at any point, press the F1 function key.
- **Browser-based help:** In Windows 2000, online help is provided through a new interface called Online Support and Information, which is accessible in Windows 2000 Help by selecting Web Help. The interface displays a new page within Windows 2000 Help that provides links to various Windows 2000 online support Web pages, including a new Windows 2000 Resource Kits Web page.
- **Books Online:** Many Microsoft products have additional user manuals in an online format that you can access from the Start menu.

heterogeneous network

A network that uses multiple network architectures and operating systems.

Overview

An example of a heterogeneous network at the hardware level is a combination of Ethernet and Token Ring local area networks (LANs) connected with a Fiber Distributed Data Interface (FDDI) backbone. An example at the network operating system (NOS) level is a server room in which some machines are running Microsoft Windows NT, others are running UNIX, and still others are running Novell NetWare. An example at the application level is a messaging system that includes Microsoft Exchange Server, Novell GroupWise, UNIX Sendmail, and IBM PROFS mail systems.

Heterogeneous networks are generally more complex to administer than homogeneous networks. Most networks are heterogeneous because they evolve over time. Most startup companies cannot afford to buy a completely homogeneous, state-of-the-art network platform, and even if they could, it would soon become out of date. One advantage of deliberately maintaining a heterogeneous network is that customers can use any product they choose instead of being locked into a single vendor's system. Networking and operating system choices can be made on a "best-served" basis instead of an "only buy from us" approach.

See Also: *homogeneous network*

hidden share

A share not visible when users browse the network for resources.

Overview

In Microsoft Windows operating systems, a share with a dollar sign ($) appended to the share name. Hidden shares are accessible on the network using Universal Naming Convention (UNC) paths or mapped network drives, but only if the user knows that they are present and knows their exact name. These shares do not show up in My Network Places or Windows Explorer or when you use the net view command. Users are unaware of their presence unless they are specifically informed.

It is a good idea not to acquaint ordinary users with hidden shares, because they might create such shares on their workstations if appropriate file and print services are installed. This can lead to secret, uncontrolled publishing of information within the company, which is usually against company policy.

Windows 2000, Windows XP, and Windows .NET Server also create certain hidden shares during the installation process that the operating system uses for specific purposes. These hidden shares are called administrative shares; permissions on them should not be modified.

See Also: *share*

Hierarchical Storage Management (HSM)

A data storage system for archiving infrequently needed data while still making it easily available.

Overview

A Hierarchical Storage Management (HSM) system is a way of providing users with seemingly endless amounts of storage space. This is accomplished by moving much of the data from hard disks to an archival storage system, such as an optical drive or tape library. Pointers are created on the hard disks indicating where the archived data is located. Users who need access to data need only request it from the disk, and if the requested data has been archived, the pointers allow the data to be found and returned to the user. The whole process is transparent from the user's viewpoint—all the data appears to be stored on the hard disks.



Hierarchical Storage Management (HSM). *How an HSM system works.*

Implementation

HSM defines two types of storage:

- **Online storage:** This is storage immediately accessible to users, typically hard disks on servers. Online storage is relatively expensive and provides almost instantaneous seek/return of requested data. In Microsoft terminology this form of storage is called local storage.
- **Nearline storage:** This is storage on archival media such as tape or optical disk and employs automated seek/return technologies such as robotic tape libraries. Nearline storage is cheaper than online storage but is slower in its ability to return requested data. In Microsoft parlance, this type of storage is known as remote storage.

Note that nearline storage differs from offline storage, which uses removable archive media (usually tape) that needs to be manually inserted in order to access information stored on the media. For HSM to work, the archival storage system employed must be automated or nearline in operation.

In HSM, when an online storage system approaches full capacity, HSM automatically starts to archive files, directories, or whole volumes to nearline storage. The particular data archived depends on the policies configured for HSM's operation, which typically initiate file archiving based on how frequently files have been accessed or when they have last been accessed. The archiving process happens automatically, and files moved from online storage are replaced with pointers to their nearline location. When a user tries to access a file stored nearline, the file is moved to online storage where the user can read it (the user cannot read nearline storage directly).

Marketplace

HSM systems have been around for some time in the UNIX world as third-party add-ons developed by different vendors for enterprise environments. Microsoft now includes an integrated HSM system in its Microsoft Windows 2000 Server platform called Remote Storage Service (RSS), which can archive data to Small Computer System Interface (SCSI) tape libraries using 4mm, 8mm, and digital linear tape (DLT) tape formats (quarter-inch cartridge [QIC] tapes and optical disk libraries are not supported). RSS works by using a new feature of NTFS version 5 called reparse points, which are similar to pointers used by UNIX file systems.

Issues

Traditional HSM loses its usefulness when used to archive large files such as video feeds and database files. This is because users sometimes need to access only a portion of such a file, but in order for them to access it, the entire file must be fetched from nearline storage and moved to online storage, a process that can take excessive time (for example, retrieving a 2 gigabyte (GB) file from a DLT tape library could take five minutes or more). A recent solution to this problem is the implementation of file segmentation to HSM systems. Using file segmentation, large files are broken up into smaller segments for archiving and retrieval, and when a part of a file is modified, only the segment modified needs to be rearchived. File segmentation can be implemented on UNIX-based HSM systems by employing a segmentation attribute—setting this attribute causes a file, directory, or volume to be broken into segments when moved to nearline storage, with pointers to each segment created on the online storage where the object previously resided. The whole process is again transparent to the user and typically reduces seek/return time for portions of large files to seconds instead of minutes.

Notes

Note that HSM systems such as Microsoft's RSS are not a substitute for regular tape backups. HSM will not archive critical operating system and application files, so regular backups are still necessary when using such systems.

See Also: *storage, tape format, tape library*

High-bit-rate Digital Subscriber Line (HDSL)

A form of Digital Subscriber Line (DSL) technology that supports high-speed symmetric data transmission.

Overview

High-bit-rate Digital Subscriber Line (HDSL) can be used to transmit data over existing copper local loop connections at T1 or E1 speeds. It is used to transport data only (HDSL signals overlap the voice portion of the Plain Old Telephone Service [POTS] spectrum and therefore cannot carry voice) and is generally used in wide area networking (WAN) scenarios. The maximum distance for HDSL transmission is typically 15,000 feet (4500 meters) when running over unconditioned copper twisted-pair telephone wiring. Some providers, however, claim that their devices support twice this distance. This maximum distance from the telco's central office (CO) to an HDSL customer's premises is sometimes called the Carrier Service Area (CSA).

HDSL was the earliest symmetric version of DSL to be widely implemented and was designed in the early 1990s as an alternative to traditional T-1 services. T1 lines originally required intermediate repeaters to be installed every 6000 feet (1830 meters) between termination points in order to ensure the signal strength necessary to transport data at such high speeds. HDSL was developed by Bellcore as a repeaterless form of T1 that would save the cost of installing repeaters and speed deployment of T1 lines for customers.

HDSL comes in various formats, including the following:

- 668-kilobit-per-second (Kbps) full-duplex transmission over a single unconditioned, unshielded copper twisted-pair phone line. This is an early form that is not used much anymore.
- 1.544-megabit-per-second (Mbps) full-duplex transmission (T1 speed) over unconditioned, unshielded copper twisted-pair cables. This is the most common configuration and is called Dual-Duplex HDSL. It uses twisted-pair phone lines with two pairs of wires (four wires) within the line, with full-duplex 784-Kbps transmission taking place over each pair of wires.
- 2.048-Mbps full-duplex transmission (E1 speed) over two or three unconditioned copper twisted-pair lines. This is the European form of HDSL, and two pairs is the usual form nowadays.

Implementation

The main different between HDSL and the original T1 specification is the line coding scheme employed. T1 lines originally used bipolar alternate mark inversion (AMI) for signal encoding, which has a spectral efficiency of only 1 bit/baud (in other words, to transmit one bit of data requires one symbol or character). By contrast, HDSL employs 2B1Q (2 Binary 1 Quaternary) line coding, which transmits information at 2 bits/baud (2B1Q is also the encoding scheme for Integrated Services Digital Network [ISDN]). Each pair of copper phone wires in an

HDSL implementation carry data at 784 Kbps over unconditioned lines without the need of repeaters. Two pairs of copper wires thus provide a throughput of 1.536 Mbps, which is the same as regular T1.

In a typical scenario, a line driver called an HTU-R terminates the lines at the customer premises end through a serial connection to a router that provides connectivity for the customer's local area network (LAN). At the telco end, a similar line driver called an HTU-C terminates the other end and provides a connection to the digital cross connect (DCC) that routes signals to trunk lines between central offices (COs). A group of HTU-Cs are typically combined in a rack to service more customers.


LAN
Bridge
HDSL line driver
V.35
4-wire twisted-pair unconditioned phone line
Line sharer
HDSL line driver
LAN
PBX
V.35
Bridge
Public Switched Telephone Network (PSTN)
Telephones

High-bit-rate Digital Subscriber Line (HDSL). *Some possible deployment scenarios for HDSL.*

Uses

Because it is a high-speed symmetrical service, HDSL is typically used to provide dedicated WAN links for enterprises. Many telcos now offer HDSL instead of traditional T1 lines because of reduced deployment costs associated with this repeaterless technology. An enterprise customer wanting to run a public Web server at her company site might use HDSL to provide a high-bandwidth connection between the server and the Internet.

HDSL can also be used for connecting bridges, routers, and telephone equipment such as Private Branch Exchanges (PBXs) over a campus using HDSL line drivers with built-in Channel Service Unit/Data Service Unit (CSU/DSU) functionality. It can also be used to build private data telecommunications networks, connections between points of presence (POPs), and other telecommunications services. You can use HDSL to connect campus networks and phone equipment at T1 speeds without the need for costly fiber-optic cabling. HDSL line drivers or line terminals generally support a variety of data interfaces, including V.35, G.703, and 10BaseT connections. They are configurable for Nx64 Kbps transmission speeds and sometimes include bridge or router functionality for framing of High-level Data Link Control (HDLC), Point-to-Point Protocol (PPP), Internet Protocol (IP), and other protocols. They can be used for LAN-LAN connections and for connecting LANs to frame relay networks or the Internet.

HDSL can also be used for other purposes such as videoconferencing, telecommuting, and shared Internet access for connecting business networks to the Internet. HDSL is not used for residential Internet access—Asymmetric Digital Subscriber Line (ADSL) is commonly used there instead. ADSL is able to provide line sharing (combined voice/data services over a single pair of copper lines), but HDSL carries only data and requires two pairs of lines.

Prospects

A newer form of HDSL called HDSL2 works similarly to HDSL but requires only one pair of copper lines in order to operate. HDSL2 is standardized by the International Telecommunication Union (ITU) as G.991.1 and by the American National Standards Institute (ANSI) as T1E1.4.

See Also: *Digital Subscriber Line (DSL), T-carrier*

High-level Data Link Control (HDLC)

An encapsulation protocol for point-to-point wide area network (WAN) links.

Overview

High-level Data Link Control (HDLC) is a data-link layer protocol for synchronous communication over serial links. HDLC was developed in the 1970s by IBM as an offshoot of the Synchronous Data Link Control (SDLC) protocol for their Systems Network Architecture (SNA) mainframe computing environment. It was later standardized by the International Organization for Standardization (ISO) as a standard Open Systems Interconnection (OSI) Layer-2 protocol.

Architecture

HDLC is called an encapsulation protocol because it encapsulates bit stream data into fixed-length frames for transmission over synchronous serial lines. HDLC is a bit-stream protocol (bit streams are streams of data not broken into individual characters) that uses a 32-bit checksum for error correction and supports full-duplex communication. HDLC frames consist of a special flag byte (01111110) followed by address and control information, data bits, and a cyclic redundancy check (CRC) byte. A control field at the start of a frame is used for establishing and terminating data link connections. As a data-link protocol, HDLC is responsible for ensuring that data is received intact, without errors, and in the proper sequence. HDLC also supports flow-control mechanisms for managing synchronous data streams. HDLC also supports multiple protocols but does not include any mechanisms for authentication (since authentication is not really needed in dedicated point-to-point communications).

An HDLC link typically consists of a primary station and a secondary station, with the primary station issuing the commands and the secondary station issuing the responses. HDLC is used mainly for point-to-point communication, in contrast to other WAN transports such as Asynchronous Transfer Mode (ATM), frame relay, and X.25, which can be used for both point-to-point and point-to-multipoint communication. Because HDLC is used mainly in point-to-point communication, it does not need to have addressing implemented at the data-link layer because the local and remote stations are connected directly. In this configuration, either one station is the primary and the other the secondary (unbalanced point-to-point link) or both stations function in a primary/secondary capacity (balanced point-to-point link). You can also use HDLC in a more complex configuration in which one primary links to several secondaries (unbalanced multipoint configuration), but this is not common.



High-level Data Link Control (HDLC). *Using HDLC for WAN communications over a leased line.*

Implementation

HDLC is the default encapsulation protocol employed by Cisco routers for synchronous transmission over serial links such as Integrated Services Digital Network (ISDN) and T-1 lines. For point-to-point communications over a leased line using Cisco routers at both ends, HDLC is a good choice. A typical leased-line configuration uses Channel Service Unit/Data Service Units (CSU/DSUs) to terminate the ends of the leased line, with Cisco routers connecting the CSU/DSUs to the two networks. The CSU/DSUs are nowadays often integrated into the routers for simplicity.

Issues

When HDLC was first developed, vendors made their own modifications to the protocol, with the result that versions of HDLC from different vendors cannot interoperate with each other. This was the driving force behind the development by the Internet Engineering Task Force (IETF) of Point-to-Point Protocol (PPP), a newer encapsulation protocol that has largely replaced HDLC in WAN environments. PPP supports both synchronous and asynchronous communications and has a standard implementation by every vendor to ensure interoperability between networking equipment from different vendors. Both PPP and Link Access Protocol, Balanced (LAPB), the data-link protocol for X.25, evolved from HDLC and were built upon its foundation.

Notes

A version of HDLC known as Normal Response Mode (NRM) HDLC is basically the same thing as Synchronous Data Link Control (SDLC), a protocol developed by IBM as a replacement for its BiSync protocol.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), leased line, Open Systems Interconnection (OSI) reference model, Point-to-Point Protocol (PPP), Synchronous Data Link Control (SDLC), wide area network (WAN), X.25*

High Performance File System (HPFS)

A file system designed for version 1.2 of the Microsoft/IBM OS/2 operating system as a successor to the file allocation table (FAT) file system used by MS-DOS.

Overview

High-Performance File System (HPFS) improves on the performance of the FAT file system for MS-DOS in the following ways:

- It locates file directory and allocation information in close physical proximity to the files themselves on the hard disk. (The FAT file system locates the root directory and allocation information on the outermost cylinders of the drive.)
- It has a more robust and efficient file system tree structure than FAT, so you can locate directories more quickly.
- It has multiple asynchronous read/write threads.
- It uses sector-based allocation instead of the more space-wasting, cluster-based allocation used by FAT.
- It uses large file cache sizes and lazy-writes.

Other features of HPFS that were considered advanced at the time of its development included the following:

- Long filenames—up to 256 characters in length. These long filenames are case preserving but not case sensitive. MS-DOS applications can still access HPFS volumes either over the network to an OS/2 LAN Manager server or from inside an MS-DOS compatibility box on an OS/2 workstation.
- Extended attributes—a series of name/value pairs associated with each directory or file. These extended attributes can be 64 kilobytes (KB) in size and support advanced kinds of search queries, such as by file type, version number, subject, or comments.
- Support for extended character sets.
- Maximum 64-gigabyte (GB) drive size. (The practical limit is 16 GB, however.)

Notes

HPFS is supported by Microsoft Windows NT version 3.51 but not by the Windows NT 4, Windows 2000, Windows XP, or Windows .NET Server operating systems, which use the more advanced NTFS file system (NTFS). HPFS was designed to function as an Installable File System (IFS), which is implemented as a dynamic-link library (DLL) that hooks into the file system component of the operating system kernel. In Windows NT 3.51, you configured HPFS through an IFS= line in the config.sys file. The CD file system (CDFS) was also designed to support IFS.

See Also: *file allocation table (FAT), file system, NTFS file system (NTFS)*

High-Performance Parallel Interface (HIPPI)

A gigabit networking technology for point-to-point communications.

Overview

High-Performance Parallel Interface (HIPPI) is an American National Standards Institute (ANSI) standard for point-to-point networking at gigabit speeds. HIPPI was developed in the 1980s as a technology for interconnecting supercomputers, mainframes, and their storage devices. Fibre Channel is the closest networking technology to HIPPI in terms of its use and capabilities and is more widely used than HIPPI.

Uses

While HIPPI is comparable in speed to Gigabit Ethernet (GbE), it is not widely used in general networking applications since it is basically a connection-oriented technology suitable for point-to-point communications due to latency involved in negotiating connections. HIPPI also lacks the multicasting capability provided by Internet Protocol (IP)–based GbE. HIPPI is mostly deployed in a few high-speed research projects by universities and for high-speed data collection in specialized scientific experiments, one of the most notable being at the European Center for Particle Physics (CERN), the world's largest particle physics facility.

Implementation

HIPPI operates at the physical and data-link layers to provide connection-oriented communications between two points. HIPPI can operate at either 800 megabits per second (Mbps) or 1.6 gigabits per second (Gbps), and it has a simple flow control command set that can establish or tear down a connection in under a microsecond using a HIPPI switch. There is also a new standard called HIPPI-6400 that supports speeds up to 6.4 Gbps for distances up to 164 feet (50 meters) over twisted pair copper and up to 0.62 miles (1 kilometer) over fiber-optic cabling.

In its original format, HIPPI was a parallel transmission technology that used 50-pair shielded twisted-pair (STP) copper cabling for transmission of 800 Mbps over a distance of up to 82 feet (25 meters). Because longer parallel cables are impractical, a newer version called Serial HIPPI was developed in 1997 that encoded HIPPI's parallel bit stream into a single serial bit stream over fiber-optic cabling. For 800 Mbps transmission, the signaling rate is 1.2 Gbaud and two fibers are used, one for simplex transmission in each direction, giving full-duplex communications. For 1.6 Gbps transmission, four fibers are used. The maximum distances over which Serial HIPPI can operate are:

- 0.62 miles (1 kilometer) over multimode fiber
- 6.2 miles (10 kilometers) over single-mode fiber

Marketplace

Vendors of HIPPI equipment include Ascend, Cray Research, GigaLabs, Hewlett-Packard Company, IBM, and Silicon Graphics, Inc. (SGI). Products offered include adapter boards and interfaces, frame buffers, storage devices, tape servers, switches and routers, cables, and test equipment.

For More Information

Find out more about HIPPI standards activities at *www.hippi.org.*

See Also: *Fibre Channel, Gigabit Ethernet (GbE)*

High-Speed Circuit Switched Data (HSCSD)

An interim upgrade for Global System for Mobile Communications (GSM) cellular communications systems.

Overview

High-Speed Circuit Switched Data (HSCSD) is the first upgrade available for GSM that boosts GSM's data-carrying capacity above its current maximum of 14.4 kilobits per second (Kbps). HSCSD is a pre-2.5G upgrade for GSM that has been deployed by a few carriers in lieu of General Packet Radio Service (GPRS), a 2.5G upgrade for GSM and other Time Division Multiple Access (TDMA) cellular systems that is just beginning to be widely deployed. Unlike GPRS, which requires that existing base station hardware be upgraded, HSCSD is a software-only upgrade and is easily implemented.

Implementation

HSCSD works by aggregating together groups of GSM time slots. Each GSM frame consists of eight time slots, each of which can provide up to 14.4 Kbps throughput for data transmission. HSCSD uses one slot for upstream communications and aggregates four slots for downstream communications. HSCSD is thus an asymmetrical data transmission technology that supports speeds of 14.4 Kbps upstream and 57.6 Kbps downstream. However, the overhead required by slot aggregation usually results in downstream bandwidth of only 28.8 Kbps instead of the theoretical 57.6 Kbps.

HSCSD supports two different transmission modes:

- **Transparent mode:** Offers a fixed bit rate for data transmission
- **Nontransparent mode:** Provides a variable bit rate

Prospects

HSCSD test deployments began in 1999. Some GSM operators that have upgraded their networks to HSCSD include Sonera in Finland and SingTel in Singapore. The majority of operators are upgrading directly to GPRS, however, and HSCSD is likely to be eclipsed quickly. This may be unfortunate, because HSCSD's circuit-switched transmission method has advantages over packet-switched GPRS in such applications as digital video, where low latency and guaranteed quality of service (QoS) are important.

See Also: *General Packet Radio Service (GPRS), Global System for Mobile Communications (GSM), Time Division Multiple Access (TDMA)*

High-Speed Serial Interface (HSSI)

A serial interface that supports speeds up to 52 megabits per second (Mbps).

Overview

High-Speed Serial Interface (HSSI) is defined by the standard EIA 612/613. HSSI supports serial transmission at speeds much higher than those supported by traditional serial interfaces such as RS-232 and V.35. At a top speed of 52 Mbps, HSSI is capable of supporting

- Synchronous Optical Network (SONET) transmission at 51.82 Mbps
- T3 lines at 45 Mbps
- E3 lines at 34 Mbps

Uses

HSSI is typically used to connect access servers and routers to T3 circuits for enterprise wide area network (WAN) connectivity. Top-end Cisco routers support HSSI through installable HSSI Interface Processor (HIP) cards that provide one HSSI port per router. HSSI is necessary for companies that want to deploy T3 WAN services such as DS-3 frame relay links because slower V.35 and RS-232 serial interfaces cannot operate at such speeds.

Notes

HSSI uses a 50-pin Centronics connector similar to a Small Computer System Interface (SCSI) connector, but you cannot use a SCSI cable to connect a HSSI router to a Data Service Unit (DSU)—you have to use a special HSSI cable instead.

See Also: *router, RS-232, serial transmission, T-carrier, V.35*

High-Speed Token Ring (HSTR)

A high-speed version of Token Ring that never got off the ground.

Overview

High-Speed Token Ring (HSTR) was a development project of the High-Speed Token Ring Alliance, which consisted of Token Ring hardware vendors IBM, Olicom, and Madge Networks. HSTR was initially intended as a 100 megabits per second (Mbps) version of 802.5 Token Ring networking architecture that would provide a logical upgrade for existing 4 and 16 Mbps Token Ring networks. Speeds up to 1 gigabit per second (Gbps) were envisioned as being possible down the line.

Unfortunately, customer interest in HSTR waned with the rapid development of Fast Ethernet and Gigabit Ethernet (GbE) technologies, and in 1998 IBM withdrew from the alliance and the effort collapsed. The effective result is that Ethernet has finally won the local area network (LAN) wars with Token Ring and Fiber Distributed Data Interface (FDDI) networking architectures, and these two architectures are now considered legacy technologies that have no real future.

See Also: *802.5, Ethernet, Fast Ethernet, Fiber Distributed Data Interface (FDDI), Gigabit Ethernet (GbE), Token Ring*

HiperLAN/2

An emerging high-speed wireless networking standard.

Overview

HiperLAN/2 is a global standard for broadband wireless networking developed by the Broadband Radio Access Networks (BRAN) group of the European Telecommunications Standards Institute (ETSI). HiperLAN/2 is designed to be an extension of Asynchronous Transfer

Mode (ATM) technology to the wireless networking arena and is expected to be ratified as a standard sometime in 2002. HiperLAN/2 is an alternative to the existing 802.11a high-speed wireless networking standard developed by the Institute of Electrical and Electronics Engineers (IEEE) and is intended as a worldwide wireless networking platform that is interoperable with ATM, third-generation (3G) cellular systems, and 1394 (Firewire) systems.

Adoption of HiperLAN/2 standards is being driven by the HiperLAN2 Global Forum (H2GF), an open industry forum launched in 1999 and whose founding members were Bosch, Dell Computer Corporation, Ericsson, Nokia, Telia, and Texas Instruments. Two other HiperLAN standards being promoted include

- **HiperAccess:** A standard for fixed outdoor use and for providing access to wireline networks
- **HiperLink:** A standard for building indoor radio backbones

Architecture

HiperLAN/2 provides raw data transfer speeds of up to 54 megabits per second (Mbps), which corresponds to roughly 20 Mbps actual sustained throughput. Instead of operating in the slower, crowded 2.5 gigahertz (GHz) Industrial, Scientific, and Medical (ISM) frequency band, HiperLAN/2 uses the higher 5 GHz frequency band for greater throughput. Actual frequencies used depend on the country in which the technology is deployed, for example:

- **United States:** 5.15–5.35 and 5.725–5.825 GHz
- **Europe:** 5.15–5.35 and 5.470–5.725 GHz
- **Japan:** 5.15–5.35 GHz currently proposed for an alternate standard similar to HiperLAN/2

HiperLAN/2 shares some similarities with the IEEE's 802.11n and 802.11a wireless networking standards, especially at the physical (PHY) layer. Specifically, both technologies use channels 20 megahertz (MHz) wide and employ orthogonal frequency division multiplexing (OFDM) at the PHY layer to support high data transfer rates. In HiperLAN/2, however, these 20 MHz channels are shared using Time Division Multiple Access (TDMA) at the media access control (MAC) layer, instead of the Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA) MAC employed by 802.11a. This makes HiperLAN/2 more like ATM than Ethernet in its operation, and, in fact, HiperLAN/2 supports Quality of Service (QoS) features similar to those found in ATM, something 802.11 does not.

Prospects

HiperLAN/2's QoS features make it an attractive solution for wireless transport of multimedia and video. The main issue with the technology, however, is its use of the 5 GHz frequency spectrum, which conflicts with the Federal Communication Commission's (FCC) spectrum allocation in the United States. This means that HiperLAN/2 is likely to be much more popular in Europe, where it was developed, than in the United States (HiperLAN/2 is accepted everywhere except Japan). Furthermore, 802.11a has the advantage of being first to market and is already beginning to be widely deployed, which may make it prevail over HiperLAN/2. Large enterprises may find it easier to deploy 802.11a globally throughout their offices than to try to support two different technologies.

A company called Atheros Communications has proposed a standard called 5-UP (5 GHz Unified Protocol) that would enable HiperLAn/2 and 802.11a technologies to interoperate. The 5-UP standard has been submitted to the IEEE for consideration.

See Also: *802.11a, Asynchronous Transfer Mode (ATM), Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA), Orthogonal Frequency Division Multiplexing (OFDM), quality of service (QoS), Time Division Multiple Access (TDMA), wireless networking*

HIPPI

Stands for High-Performance Parallel Interface, a gigabit networking technology for point-to-point communications.

See: *High-Performance Parallel Interface (HIPPI)*

History

A folder in Microsoft Internet Explorer that contains shortcuts to Web pages that you have recently browsed.

Overview

The History folder makes it simple to return to sites that you have recently visited but have not been designated as Favorites. By clicking the History button on the Internet Explorer toolbar, you can view the contents of the History folder and revisit any of the links. You can configure how many days items should be kept in the folder, and you can delete the files manually if desired. Using the offline browsing feature of Internet Explorer, you can browse the History folder while you are disconnected from the Internet.

hive

A physical file containing part of the registry in Microsoft Windows.

Overview

Hives are opposed to subtrees, which are logical sections of the registry. The term *hive* is loosely connected with the idea of the cellular structure of a beehive.

Hives consist of a discrete collection of keys and subkeys that have a root at the top of the registry. Five of these hives are located in the folder %SystemRoot%\system32\config; the sixth hive (Ntuser.dat), which contains user profile information, is stored on machines running Windows NT in the folder %SystemRoot%\Profiles\username. On machines running Windows 2000, Windows XP, or Windows .NET Server, it is stored in the folder

- %SystemRoot%\Documents and Settings\username if this is a new Windows 2000, Windows XP, or Windows .NET Server installation or an upgrade from Windows 95 or Windows 98
- %SystemRoot%\Profiles\username if this is an upgrade from Windows NT to Windows 2000, Windows XP, or Windows .NET Server

Each hive has an associated transactional .log file that logs all modifications made to the registry and provides fault tolerance. Each hive file also has a .sav file, which is a backup copy of the hive file. The functions of the hives and the logical key they map to are indicated in the following table.

Windows NT Hives

Hive	*Key*	*Function*
Default	HKEY_USERS\DEFAULT	Contains the default system profile used when the logon screen is displayed.
SAM	HKEY_LOCAL_MACHINE\SAM	Contains information for the Security Account Manager (SAM). This hive cannot be viewed with the registry editor and must be accessed using specific application programming interfaces (APIs).
Security	HKEY_LOCAL_MACHINE\SECURITY	Contains the computer's security policy information. This hive also cannot be viewed with the registry editor and must be accessed using specific APIs.
Software	HKEY_LOCAL_MACHINE\SOFTWARE	Contains global configuration information for installed software.
System	HKEY_LOCAL_MACHINE\SYSTEM and HKEY_CURRENT_CONFIG	Contains configuration information for installed hardware devices and services.
Ntuser.dat	HKEY_CURRENT_USER	Contains user-specific configuration settings for the user who is currently logged on interactively.

See Also: *registry*

H-node

A NetBIOS name resolution method used for name registration and resolution.

Overview

H-node is a type of NetBIOS over Transmission Control Protocol/Internet Protocol (TCP/IP) node defined in RFCs 1001 and 1002. It's supported by Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server. H-node is also one of four basic methods for resolving NetBIOS host names (computer names) into Internet Protocol (IP) addresses. Name resolution is the process of converting the name of a host on the network into a network address, such as an IP address. Name resolution must be performed to establish communication over a network.

Implementation

When a computer running Windows NT, Windows 2000, Windows XP, or Windows .NET Server is configured as an H-node machine, it first tries to use a NetBIOS name server to resolve names of other hosts on the network; this is the way a P-node machine functions. A server running Windows NT, Windows 2000, Windows XP, or Windows .NET Server with the Windows Internet Name Service (WINS) configured on it is the typical example of a NetBIOS name server. If name resolution fails this way (for example, if all WINS servers are down), an H-node machine tries to use broadcasts to resolve the names of the hosts; this is the way a B-node machine functions. H-node is thus a combination of P-node and B-node (in that order), which explains the origin of the term *H-node*: *H* stands for hybrid.

If no WINS server is on a network, machines running Windows NT, Windows 2000, Windows XP, and Windows .NET Server automatically configure themselves as B-nodes. If at least one WINS server is on the network, however, the systems default to H-node.

See Also: *B-node, M-node, NetBIOS name resolution, P-node*

home area network (HAN)

A network of several computers at a user's home.

Overview

With the rapid growth in the PC market, an estimated 20 percent of homes in the United States that have one PC have at least one additional PC. As a result, ordinary PC users are becoming interested in networking their home PCs to use them for purposes such as

- Dedicating one PC to the role of a file server
- Sharing a printer among multiple PCs
- Installing a home Web server connected to the Internet by means of a cable modem
- Playing network games with family and friends
- Using networked PCs to prepare for certifications such as Microsoft Certified Systems Engineer (MCSE)

Implementation

A variety of different technologies can be used for deploying home area networks (HANs). Examples include the following:

- **Ethernet:** Basic Ethernet networking kits are available from most computer vendors and home/office supply stores. These kits are reasonably easy to set up and provide 10-megabit-per-second (Mbps) throughput. The main disadvantage is that these kits require that users have enough computer expertise to be able to install a network interface card (NIC) inside the machine and load the appropriate drivers. Then there's also the issue of laying the cabling so that people do not trip over the cable or wear it away by walking on it. Make sure you purchase 10BaseT kits that contain a hub, NICs, and cables instead of older 10Base5 kits that use bulkier coaxial cable.
- **Power line networking:** This technology allows computers in different parts of the house to communicate using installed power wiring and AC outlets. Implementations range from special AC port interface cards that need to be installed in machines to plug-and-play adapters that connect to a machine's parallel (LPT) port. This technology's main disadvantage is that it is relatively slow—most devices support speeds of 2 Mbps or less at present.
- **Phone line networking:** This technology leverages your installed telephone wiring infrastructure and RJ-11 phone line jacks to connect computers to form a network. Unfortunately, it only works if

these jacks have been properly installed with wires connected correctly, which is not always the case. Phone line networking typically supports Ethernet speeds of about 1 Mbps and is available for Peripheral Component Interconnect (PCI), pulse code modulation (PCM), and universal serial bus (USB) format. Initiatives from the Home Phone Networking Alliance (HomePNA) aim at increasing speeds to 10 Mbps and higher. Phone line networking works by utilizing frequencies above 2 megahertz (MHz), well beyond the range of both voice communications and Asymmetric Digital Subscriber Line (ADSL).

- **Wireless networking:** Kits for building simple wireless networks are more expensive than other forms of home networking technologies but have the advantage of greater flexibility in deployment. These range from expensive 802.11b kits that contain transceivers for PCs and a central access point and support speeds up to 11 Mbps, to consumer products running in the Industrial, Scientific, and Medical (ISM) range of the frequency spectrum and supporting speeds of about 1.5 Mbps.
- **Infrared (IR) networking:** This technology is generally used only to connect peripherals to PCs in the same room and requires clear line-of-site for communications.

Marketplace

The number of vendors offering Ethernet kits for home networking is legion. Vendors for phone line networking kits include 3Com Corporation and Intel Corporation. In the wireless networking market, Proxim offers a product called Symphony that uses PCI or PCM cards with antennae attached and no central access point. Intel also offers a popular wireless solution called AnyPoint that features plug-and-play USB connectivity.

See Also: *10BaseT, 802.11b, Ethernet*

home folder

Also called home directory, a user's private folder for storing personal files.

Overview

Home folders for users are usually centrally located on a network server for the following reasons:

- To ensure that their contents are backed up regularly
- To make home folders available from any computer on the network
- To make home folders available from any client operating system

In Microsoft Windows 2000 and Windows XP, home folders are not part of the user profile of roaming users, so they must be specified. Use the Active Directory Users and Computers console to assign home folder locations. Open the property sheet for the user and specify the location of the user's home folder on the Profile tab.

HomeRF

A wireless networking specification targeted toward consumers.

Overview

HomeRF is a wireless networking technology that supports both voice and data transmission. HomeRF is designed for consumer applications such as wireless home networks, communication between Personal Digital Assistants (PDAs) and laptops, and similar uses.

HomeRF is based on a specification called RangeLan2 developed by Proxim. It operates in the same 2.4 gigahertz (GHz) unlicensed Industrial, Scientific, and Medical (ISM) band of the electromagnetic spectrum used by 802.11b and Bluetooth wireless networking technologies and by such devices as microwave ovens. HomeRF is less costly than these competing technologies due to the simplicity of its design and operation.

Implementation

The original HomeRF specification supports networking of PCs and other devices at data transfer rates up to 1.6 megabits per second (Mbps). In April 2001 the HomeRF Working Group released the HomeRF 2 specification, which boosts speeds to 10 Mbps. The

Working Group aims at releasing a HomeRF 3 standard in 2002 that will push data rates up to 22 Mbps.

In contrast to the competing 802.11 wireless networking technologies that use direct sequence spread spectrum (DSSS) radio transmission, HomeRF instead employs frequency hopping spread spectrum (FHSS) transmission. FHSS employs a signal that "hops" over a number of different frequencies to find one that is clear for transmission and provides better resistance to electromagnetic interference (EMI) than DSSS. Voice transmission is supported using time division multiple access (TDMA), but data uses Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA).

HomeRF is deployed by using a central device called a home gateway, which enables communications between various types of devices including PCs, display pads, Web appliances, PDAs, stereos, home automation devices, and cordless phones. HomeRF uses a new protocol called Shared Wireless Access Protocol (SWAP) to enable its home networking features. Using SWAP, a user can do such things as

- Network a variety of different devices together into an integrated home networking environment
- Share files, printers, and Internet connections among devices on a home network
- Control PCs, home automation, and other devices from handsets and cordless phones

Marketplace

HomeRF products are available from a number of vendors, including Cayman Systems, Compaq Computer Corporation, Intel Corporation, Motorola, and Proxim. Intel's AnyPoint wireless networking platform supports HomeRF networking and is a popular choice.

Issues

Proponents of 802.11 have criticized HomeRF because it can potentially interfere with 802.11-based wireless communications. To a DSSS 802.11 receiver, FHSS signals produced by a HomeRF transmitter appear as random noise that can disrupt communications channels. Proponents of HomeRF often respond by saying that their product is targeted to a different market, the home networking market, than is 802.11, which is aimed mainly at the enterprise. They also point out that HomeRF fills a niche for combined data-voice wireless networking that 802.11, which is strictly data-oriented, has not filled. The Federal Communications Commission (FCC) has tried to resolve these concerns by limiting HomeRF hardware to power transmission under 125 milliwatts. This limits the range of HomeRF transmission to about 150 feet (45 meters) and makes it less likely to interfere with a neighboring 802.11 network.

Market prospects for HomeRF look good, but it has to play catch up to 802.11, which already has a large installed base worldwide. Intel is one company that already has home network products available in the consumer market that are based on the HomeRF standard.

For More Information

Visit the HomeRF Working Group at *www.homerf.org.*

See Also: *802.11, Bluetooth, wireless networking*

homogeneous network

A network that uses a single network architecture and operating system.

Overview

Homogeneous networks are the simplest networks to administer, but most corporate networks are heterogeneous networks for the following reasons:

- Budgets are limited, so it is not always possible to upgrade an older heterogeneous network into a newer homogeneous one unless the ultimate cost savings can be justified to management.
- Products continually evolve, so what might be a state-of-the-art network operating system today will be a second-class system tomorrow.
- Management and user expectations and needs evolve, so upgrading a second-class system might

not be as appropriate as replacing it entirely with something newer.

- Decision making involves politics, and different groups might press for purchasing software that they are more comfortable with instead of making prudent long-term decisions.

A simple example of a homogenous network would be an Ethernet local area network (LAN) in which all machines are running Microsoft Windows 2000. Another example would be an enterprise-level messaging system based solely on Microsoft Exchange Server with no other mail systems used.

See Also: *heterogeneous network*

honey pot

A dummy server used to distract hackers from real targets.



Using port redirection

Hacker
Internet
Router
port 80
port 23
Web server
Honey pot

Catching attackers that sweep networks

Hacker
Internet
Firewall
Switch
LAN
Server
198.16.5.21
Server
198.16.5.22
Honey pot
198.16.5.23
Server
198.16.5.24
Perimeter
network
(DMZ)

Honey pot. *Two ways of setting up honey pots to attract and catch hackers.*

Overview

A honey pot emulates a real server, with the goal of drawing hackers away from your actual production servers. For example, you could set up a dummy Web server, mail server, or authentication server as a honey pot. Honey pots should include

- Data that makes them attractive to a hacker. Typically, this could be a small sampling of real data, such as authentic Web pages or a few real user accounts (without their passwords, of course!).
- Intrusion detection software that logs all suspicious activity with the server and alerts administrators to it.

Implementation

There are several ways to deploy honey pots on the perimeter of your corporate network:

- You could use a router or firewall with port redirection configured to make it look as though services running on a honey pot are running on a real server instead. For example, you could set up a honey pot for a Web server, leaving only Transmission Control Protocol (TCP) port 80 (HTTP) open on the Web server and opening port 23 (Telnet) on the honey pot. Using port redirection, it looks to the attacker like port 23 is open on the Web server, but this actually redirects the attacker to the honey pot instead.
- Alternatively, to deal with attackers who sweep entire ranges of Internet Protocol (IP) addresses for vulnerabilities, you could set up a honey pot among a group of real servers having sequential IP addresses. When the attacker scans the network, the honey pot detects the scan and warns an administrator that a possible attack is underway.

Honey pots require resources to be dedicated to them and are essentially useless unless you have the time and personnel to analyze their intrusion logs and respond to their alerts. In other words, a honey pot that is set up and then ignored is worse than no honey pot at all. Honey pots are designed to provide administrators with information not just for detecting attacks, but also for tracking down those performing the attacks, but this requires skill and time to accomplish.

See Also: *firewall, router, security*

hood

Sometimes called a boot, the protective enclosure at the ends of cabling that houses the pins.

Overview

The hood protects the contacts between the cable's wires and the pins in the enclosed connector. The term *hood* is usually applied to serial cables for serial transmission interfaces such as RS-232 and V.35. The RJ-45 termination of unshielded twisted-pair (UTP) cabling and the SC termination of fiber-optic cabling are simply called connectors or jacks. Hoods are generally made of metal or plastic. Metal hoods are used on shielded cabling to provide shielding against electromagnetic interference (EMI) at the cable ends. Removable metal hoods are also used for running cable through tight spaces, such as conduits, or for repinning connections. Plastic hoods, which are less expensive, are used primarily on unshielded cabling. Molded plastic hoods are also used to provide durable, tamper-proof housings for pins.


RS-232 cable with removable metal hoods
Open hood showing pinning

Hood. *An example of a hood.*

hop count

The logical distance between two networks based on the number of routers that must be traversed by packets sent between them.

Overview

In Transmission Control Protocol/Internet Protocol (TCP/IP) internetworking, the number of hops between two hosts would be the number of routers that an Internet Protocol (IP) packet would have to pass through in order to reach its destination.



Hop count. *Two hosts that are three hops apart on an internetwork.*

The illustration shows a network path that is three hops long. As the packet travels from source to destination, the packet's header maintains information about the "hop count" (the number of hops traversed). This information is stored as a Time to Live (TTL) parameter within each packet that typically starts with a value of 128 and is decremented by 1 at each router (that is, after each hop). If router congestion delays the packet at a router, the TTL might be decremented by more than 1 to indicate this. If the TTL is decremented to 0 before the packet reaches its ultimate destination, the next router drops the packet and retransmission is required from the source host.

Uses

Hop counts are used by dynamic routers to determine the best route for forwarding data across a large internetwork. The route that has the smallest total number of hops is generally the best route for sending the data. Hop counts are also used to prevent packets from endlessly circulating around an internetwork by having packets dropped (discarded) once they reach a certain maximum hop count (that is, once the TTL decrements to zero).

Notes

In Microsoft Windows 2000, you can use the tracert command to watch the hop count decrease as an IP packet traverses an internetwork toward its destination.

See Also: *routing*

horizontal cabling

In premise cabling, any cabling that is used to connect a floor's wiring closet to wall plates in the work areas to provide local area network (LAN) drops for connecting users' computers to the network.

Overview

Horizontal cabling is usually installed in a star topology that connects each work area to the wiring closet, as shown in the illustration. Four-pair 100-ohm unshielded twisted-pair (UTP) cabling (Category 5 [Cat5] cabling or enhanced Category 5 [Cat5e] cabling) is usually recommended for new installations because it supports both voice and high-speed data transmission. To comply with Electronic Industries Association/Telecommunications Industries Association (EIA/TIA) wiring standards, individual cables should be limited to 295 feet (90 meters) in length between the wall plate in the work area and the patch panels in the wiring closet. Patch cords for connecting the patch panel to hubs and switches in the wiring closet should be no longer than 23 feet (7 meters) total, with a maximum of two patch cords per line, neither of which can exceed 19.7 feet (6 meters) in length. Cables connecting users' computers to wall plates should be limited to 9.8 feet (3 meters) in length.


Wall plate
Work area
≤ 9.8 feet/3 meters
Wiring closet
Workstation
Patch panel
Hub
Patch cord
(≤ 19.7 feet/6 meters)
Horizontal cable run
(≤ 295 feet/90 meters)
Rack

Horizontal cabling. *Deploying horizontal cabling to connect a work area to a wiring closet on the same floor.*

Horizontal cabling is most easily installed during construction or renovation of the building because proper installation might require opening false ceilings or walls. If this is not feasible, installing external cable trays and conduits might be the best solution because loose cables on the floor pose a hazard and should be avoided at all costs.

Notes

Avoid installing cables near motors, generators, transformers, or power lines in order to minimize electromagnetic interference (EMI). Keep cables away from photocopying machines and elevators because these machines generate a lot of EMI. If you anticipate increased bandwidth needs in the near future, use multimode fiber-optic cabling instead of unshielded twisted pair (UTP) cabling for horizontal cabling. You probably want to install two four-pair UTP cables in each work area, one for voice and the other for data transmission. Be sure to use the right kind of wall plates (RJ-11 for voice and RJ-45 for data).

See Also: *cabling, premise cabling, structured wiring*

host

Any device on a Transmission Control Protocol/Internet Protocol (TCP/IP) network that has an Internet Protocol (IP) address.

Overview

Examples of hosts include servers, workstations, network-interface print devices, and routers. The terms *node* and *host* are often used interchangeably in this regard. Sometimes the term *host* specifically means a device on a TCP/IP network that can both receive data and initiate contact with other devices. For example, a computer configured as a Simple Mail Transfer Protocol (SMTP) host receives e-mail messages and forwards them to their destination.

Notes

In mainframe computing environments, a host is a mainframe computer that is accessed by users through remote terminals.

See Also: *IP address, Transmission Control Protocol/Internet Protocol (TCP/IP)*

host bus adapter (HBA)

A device that converts Peripheral Component Interconnect (PCI) bus signals into Small Computer System Interface (SCSI) or Fibre Channel format.

Overview

Host bus adapters (HBAs) have traditionally been SCSI-based devices used in Storage Area Networks (SANs). They are also used in Fibre Channel SANs to provide connectivity with Gigabit Ethernet (GbE) networks. The Storage Network Industry Association is developing a proposed set of standard application programming interfaces (APIs) for HBAs to ensure interoperability between products from different vendors. With the emergence of the new Infiniband bus standard, things are likely to change and host bus adapters may decline in importance.

Marketplace

A number of vendors produce host bus adapters for storage networking, including Emulex Corporation, whose LightPulse and Giganet Fibre Channel PCI host bus adapter is a popular choice for enterprise SANs. One new development in this market is the recent marriage of high-speed switching technology with host bus adapters, represented by companies such as Qlogic Corporation.

See Also: *Fibre Channel, Infiniband (IB), storage area network (SAN)*

Host Data Replicator

A Microsoft Corporation database replication tool that copies data from legacy DB2 database tables on an IBM mainframe to Microsoft SQL Server database tables.

Overview

The Host Data Replicator consists of a data replicator service implemented as a service in Microsoft Windows NT and Windows 2000 plus an administrative tool called the Data Replication Manager. The Host Data Replicator performs the replication by taking a snapshot of the entire source table. It then either copies the entire snapshot to the target database table, overwriting any records in the existing target table, or appends the information to the target table, depending on how it is configured. The Host Data Replicator can also replicate SQL Server tables back to a DB2 database. The Host Data Replicator can copy data either on demand or according to a predefined schedule.

The Host Data Replicator is supported by Microsoft SNA Server version 3 and later and Microsoft SQL Server version 6.5 and later.

host header names

A feature of Hypertext Transfer Protocol version 1 (HTTP/1.1) that enables multiple Web sites to be hosted on the same Web server.

Overview

Host headers are supported by Microsoft Internet Information Services (IIS) and allow multiple Web sites having the same Internet Protocol (IP) address and HTTP port number to be hosted on the same Web server. Web browsers such as Microsoft Internet Explorer also support host header names and can access such IIS Web sites seamlessly. Web browsers that support host header names include Internet Explorer 3 and later or Netscape Navigator 3 and later.

Implementation

To configure multiple Web sites on an IIS server to share one IP address and use host header names for client access to them, perform the following steps:

1. Open the property sheet for each virtual server in Internet Services Manager.
2. Select the Web Site tab and specify the IP address and port number (usually port 80), or select All Unassigned if your server has only one IP address.
3. Click the Advanced button, select the identity you want to use from the Multiple Identities For This Web Site list, and add a host header name. Note that each identity can have only one host header name, but each virtual server can have multiple identities.
4. Register the host header name with your Domain Name System (DNS) server or Internet service provider (ISP).

Once the IIS server and DNS name resolution environments are configured properly, a Web browser that supports host header names, such as Internet Explorer 4 and later, can use these names to access different virtual servers that have the same IP address and port number and are located on the same machine running IIS. The browser makes an HTTP 1.1–compliant GET request, which contains in its header the host header name being requested.

Notes

IIS 4 and later also support host header names for older noncompliant browsers through the mechanism of cookies. For very old browsers that do not support cookies, a tool in the IIS Resource Kit called the Cookie Munger enables these browsers to access such sites on IIS 4 as well.

Do not create host header names for the Default Web Site because this might affect other services installed on the server that expect the Default Web Site to have no host header names.

See Also: *Hypertext Transfer Protocol (HTTP), IP address, Web server*

host ID

The portion of an Internet Protocol (IP) address that uniquely identifies a host on a given Transmission Control Protocol/Internet Protocol (TCP/IP) network.

Overview

You can determine the host ID from a host's IP address by logically NANDing the binary form of the IP address with the binary form of the subnet mask for the network. The remaining part of an IP address is the network ID, which specifies the network to which the host belongs.

For example, if a host has an IP address of 172.16.8.55 on a network with a subnet mask of 255.255.0.0 (the default subnet mask), the host ID is 0.0.8.55 or simply 8.55. The host ID uniquely identifies the host but only within the boundary of the network ID for the network on which the host is installed.

See Also: *IP address, network ID*

Host Integration Server

Microsoft Corporation's gateway and application integration platform.

Overview

Microsoft Host Integration Server 2000 is the successor to Microsoft's previous BackOffice gateway platform, SNA Server. Host Integration Server is part of the new .NET Enterprise Server platform and provides access to applications and data stores on IBM mainframe and AS/400 platforms. Host Integration Server supports network interoperability between Microsoft Windows 2000 client/server networks and Systems Network Architecture (SNA)-based mainframe computing platforms. Host Integration Server helps enterprises maximize their existing investments in legacy mainframe systems while leveraging the power of the Windows 2000 Server platform.

Features of Host Integration Server include

- Enterprise scalability with support for up to 30,000 simultaneous host sessions per server
- Load balancing and hot failover for mission-critical reliability
- Seamless access by clients to host-based file, print, and application services
- Industry-standard clients plus Web-deployable 3270 and 5250 clients based on Microsoft ActiveX technology
- Turnkey gateway solutions for host-to-Internet and host-to-intranet connectivity
- Support for Microsoft Message Queue (MSMQ) and COM+ object-oriented development
- Drag-and-drop integration between Microsoft Transaction Server and IBM's CICS and IMS transactional development environments
- Object-oriented access to DB2 and flat file databases on hosts
- Support for virtual private networking (VPN) and single sign-on
- Integration with Microsoft SQL Server 2000, BizTalk Server 2000, and Commerce Server 2000

For More Information

Find out more about Host Integration Server at *www.microsoft.com/hiserver.*

See Also: *.NET Enterprise Servers*

host name

An alias given to a computer on a Transmission Control Protocol/Internet Protocol (TCP/IP) network to identify it on the network.

Overview

Host names are a friendlier way of identifying TCP/IP hosts than Internet Protocol (IP) addresses. Host names can be resolved into IP addresses by host name resolution using either a Domain Name System (DNS) server or the hosts file. Host names can include the characters a–z, A–Z, 0–9, period, and dash (-). To ensure full compatibility with DNS, do not use any other special characters in host names.

Notes

To find out the host name of a computer running any version of Microsoft Windows, type Hostname at the command prompt.

See Also: *Domain Name System (DNS), host name resolution, hosts file*

host name resolution

The process by which a host determines the Internet Protocol (IP) address of another host on a Transmission Control Protocol/Internet Protocol (TCP/IP) network given its host name or fully qualified domain name (FQDN).

Overview

Suppose you go to the command prompt of a machine running Microsoft Windows 2000 and type **ping** followed by a host name or FQDN of another host on the network. The host name or FQDN of the target host must first be resolved into its IP address before the TCP/IP utility ping can occur. This process is called host name resolution.

A number of different methods can be used to perform host name resolution. The following table shows the order in which these are attempted on a Microsoft network. The methods are tried in succession until the host name is resolved into its IP address or until name resolution finally fails. Some methods will not be available—for example, if there is no Domain Name System (DNS) server or NetBIOS Name Server (NBNS) on the network.

Host Name Resolution Methods in the Order Applied

Host Name Resolution Methods	*Comments*
Check whether the target host is the local host.	The local host knows its own host name!
Check local hosts file.	This check is performed only if a hosts file has been configured.
Contact DNS server.	This check is performed only if the DNS tab of the TCP/IP property sheet has a DNS server specified on it. The local host tries again at intervals of 5, 10, 20, and 40 seconds.
Check local NetBIOS name cache. (Unique to Microsoft networks.)	The cache contains recently resolved NetBIOS names. (On Microsoft networks, NetBIOS names and host names are usually the same.)
Contact NBNS. (Unique to Microsoft networks.)	This check is performed if NBNS has been configured by creating a Windows Internet Name Service (WINS) record within the DNS database. On a Microsoft network, this is usually a WINS server. The local host tries three times to contact the WINS server and then tries the secondary WINS server three times.
Perform local broadcast. (Unique to Microsoft networks.)	Local host broadcasts a NetBIOS name query request packet three times.
Check local lmhosts file. (Unique to Microsoft networks.)	This check is performed if a lmhosts file has been configured.

If all methods fail, an error message states that the computer could not be found on the network.

Notes

There is a separate series of steps for attempting to resolve NetBIOS names on a network that uses WINS. For more information, see the entry “NetBIOS name resolution” elsewhere in this book.

See Also: *Domain Name System (DNS), host name*

host routing

The routing process that occurs when a host (computer) on a network forwards a packet to a destination host on the network.

Overview

Host routing is different from router routing, which is what happens when a router receives a packet that needs to be forwarded to a destination host. Host routing essentially involves a simple decision: should the packet be forwarded directly to its destination host, or should it be forwarded to a router? The host makes this decision by comparing the packet’s destination address with entries in its internal routing table.

To perform host routing, the host must first obtain the internetwork address of the destination host using some form of name resolution. For example, in order for a host to forward a packet to a remote host called northwind.microsoft.com, it could first use the Domain Name System (DNS) to obtain the Internet Protocol (IP) address of the remote host. The host then compares this address with entries in its internal routing table to determine whether the destination has a local or remote network address. If the address is a local network address, the host forwards the packet directly to its destination using the physical layer or physical address of the remote host. This process is known as direct delivery. On Transmission Control Protocol/Internet Protocol (TCP/IP) networks, the physical address of a host is its MAC address, which is obtained by using the Address Resolution Protocol (ARP).

If, however, the host determines that the destination host has a remote network address (that is, the destination host is on a different network than the sending host), the host forwards the packet to a nearby router after first obtaining the physical address of the near-side interface of the router. This process is known as indirect delivery. It is the router's responsibility to ensure that the packet is forwarded toward its destination, although in a typical internetwork the destination might be several hops away, in which case the router's responsibility extends only to the next hop on the path.

See Also: *Address Resolution Protocol (ARP), Domain Name System (DNS), hop count, IP address, router, routing*

hosts file

A text file that provides a local method for name resolution of Internet Protocol (IP) hosts.

Overview

A hosts file can be used to resolve a host name or fully qualified domain name (FQDN) into its associated IP address. Hosts files are a local alternative to using distributed Domain Name System (DNS) name servers for performing name resolution on Transmission Control Protocol/Internet Protocol (TCP/IP) networks. Hosts files are used mainly on small networks where maintaining a DNS server is impractical or as a backup in case no name servers are available to perform name lookups.

History

Hosts files predated the DNS as a name resolution method. During the 1970s, when the ARPANET, the Internet's precursor, consisted of only a few hundred different hosts, using hosts files was a relatively painless way of enabling name resolution to be performed. When someone added a new host to the network, they would e-mail the Network Information Center (NIC), which would update the information in their master hosts file stored on a server called SRI-NIC. Users around the ARPANET typically checked this server a few times each week to see if an updated hosts file was updated and if so would download it to their own hosts using File Transfer Protocol (FTP).

When the ARPANET migrated to TCP/IP in the early 1980s, the number of hosts exploded and a new method of name resolution had to be found. This new method had to overcome the problems with hosts: it scaled poorly, had no automated process for registering new hosts, and had no way of pushing out updates from the master hosts file server. The result was the development of DNS, a distributed name resolution service that is still in use and forms the backbone of communications on the Internet.

Implementation

Hosts files consist of a series of FQDN-to-IP address mappings, one per line. Each line in the hosts file contains the IP address of a host followed by the FQDN of the host, followed by an optional comment prefixed with a pound sign (#). Hosts files should contain mappings for hosts on both local and remote networks. Mappings can consist of an IP address and one or more host names (aliases). If you are using hosts files to resolve host names on a network, each computer on the network should have a hosts file.

On a UNIX system, the hosts table is found in /etc/hosts, and on Microsoft Windows 2000, Windows XP, and Windows .NET Server systems, it is located in the %SystemRoot%\system32\ drivers\etc\Hosts directory.

Notes

Although DNS has largely eliminated the need for maintaining hosts files, they are still useful in two scenarios:

- On small TCP/IP networks not connected to the Internet, it may be easier to maintain a hosts file than to run a DNS server.
- Hosts files can be used as a backup in case DNS goes down. Typically, you would keep the hosts file small in this case, adding only entries for your servers and for gateways to remote networks, plus a line for localhost, which maps to 127.0.0.1, the loopback address for testing IP communications.

Notes

Place the host names that need to be most frequently resolved near the top of the hosts file because the file is parsed linearly from the beginning.

See Also: *lmhosts file, Networks file, protocol file, services file*

hot

An adjective referring to actions that can be performed on systems or hardware devices while the power for the device is still turned on or while the device still has a live network connection or telecommunications link.

Overview

"Hot" networking and system technologies are used in

- Fault-tolerant disk drive systems such as redundant array of independent disks (RAID) systems
- Redundant power supply systems
- Modular Ethernet switches and routers
- Redundant high-speed data communication links

Examples of disk storage systems that use "hot" technologies include the following:

- **Hot-rebuild system:** A drive subsystem that can automatically rebuild its original drive configuration after drive failure
- **Hot-spare system:** A drive subsystem that has additional unused drives that can be called into action when drive failure occurs
- **Hot-swap system:** A drive subsystem in which drives are mounted on trays and can be removed and replaced without shutting down the system

For example, when you buy a hardware RAID unit, you might want to be sure that it has hot-rebuild, hot-spare, and hot-swap capabilities.

hotfix

A fix for a bug in an application or operating system.

Overview

Hotfix is a term used by Microsoft Corporation to describe a software patch issued to correct a problem with a version of Microsoft Windows or a Microsoft application. For the BackOffice platform, hotfixes are now called Quick Fix Engineering (QFE).

Generally, you should apply a hotfix (QFE) only if you are experiencing a problem related to an issue the hotfix is designed to correct. In other words, if you are not experiencing the problem described in the documentation for a hotfix, it is generally best to wait for the next release of a service pack (a group of hotfixes applied in one shot) instead of applying the hotfix individually. This is especially true of hotfixes that have not been "regression tested," that is, whose interaction with other software is currently uncertain.

Some hotfixes are made available publicly through Microsoft's File Transfer Protocol (FTP) site. Others are only available from Microsoft Product Support Services (PSS) and require a support agreement to be in place before downloading them.

For More Information

You can find current hotfixes for Microsoft products at *ftp.microsoft.com*.

See Also: *service pack*

Hot Standby Router Protocol (HSRP)

A proprietary Cisco technology for implementing fault-tolerant routing.

Overview

Hot Standby Router Protocol (HSRP) was developed by Cisco Systems as a way of providing fault tolerance for routed internetworks. Normally, when a router goes down, routing protocols communicate this fact to all the routers on the network, which then reconfigure their routing tables to select alternate routes to avoid the downed router. The problem is that the process of convergence, the updating of all routing tables on the network, is slow and can take some time to complete. HSRP was designed to work around this problem of slow convergence by allowing a standby router take over from a router that has gone down and fill its role in a manner completely transparent to hosts on the network.

HSRP is outlined in RFC 2281 but is a proprietary standard and not an Internet Engineering Task Force (IETF) standard. The IETF has proposed its own vendor-independent fault-tolerant routing technology called Virtual Router Redundancy Protocol (VRRP), which is documented in RFC 2338.

Implementation

HSRP works by creating virtual groups that consist of two routers, an active router and a standby router. HSRP creates one virtual router in place of each pair of actual routers, and hosts need only to have their gateway address pointed to the virtual router. When a host forwards an Internet Protocol (IP) packet to its default gateway (the virtual router), it is actually handled by the active router. Should the active router go down, the standby router steps in and continues to forward packets it receives. To IP hosts on the network, the virtual router acts as a real router and everything works transparently whether the active or standby router actually does the forwarding.



Hot Standby Router Protocol (HSRP). *How HSRP works.*

HSRP allows for complex arrangements of virtual routers. For example, actual routers can belong to more than one virtual group, and there can be up to 255 virtual groups on the network. HSRP can also be used to provide backup default gateways for hosts capable of addressing only a single default gateway.

See Also: *default gateway, router, routing*

HPFS

Stands for High Performance File System, a file system designed for version 1.2 of the Microsoft/IBM OS/2 operating system as a successor to the file allocation table (FAT) file system used by MS-DOS.

See: *High Performance File System (HPFS)*

HP-UX

Hewlett-Packard's version of the UNIX operating system platform.

Overview

HP-UX is the only version of UNIX that supports application development on UNIX, Linux, and Microsoft Windows platforms. The most recent version HP-UX 11i includes such features as

- Support for 4 gigabytes (GB) of addressable RAM
- Integrated Apache Web server software
- Lightweight Directory Access Protocol (LDAP)–compliant Internet directory services
- Inktomi Internet caching software
- Ultraseek search engine from Infoseek
- Linux application programming interfaces (APIs) and GNU's Not UNIX (GNU) tools
- Nokia Wireless Application Protocol (WAP) server software
- Internet load balancing software from Resonate

For More Information

Visit Hewlett-Packard online at *www.hp.com.*

See Also: *Linux, UNIX*

HSCSD

Stands for High-Speed Circuit Switched Data, an interim upgrade for Global System for Mobile Communications (GSM) cellular communications systems.

See: *High-Speed Circuit Switched Data (HSCSD)*

HSM

Stands for Hierarchical Storage Management, a data storage system for archiving infrequently needed data while still making it easily available.

See: *Hierarchical Storage Management (HSM)*

HSRP

Stands for Hot Standby Router Protocol, a proprietary Cisco protocol for implementing fault-tolerant routing.

See: *Hot Standby Router Protocol (HSRP)*

HSSI

Stands for High-Speed Serial Interface, a serial interface that supports speeds up to 52 megabits per second (Mbps).

See: *High-Speed Serial Interface (HSSI)*

HSTR

Stands for High-Speed Token Ring, a 100 megabits per second (Mbps) version of Token Ring that never got off the ground.

See: *High-Speed Token Ring (HSTR)*

HTML

Stands for Hypertext Markup Language, a formatting or markup language used to create documents for the World Wide Web (WWW).

See: *Hypertext Markup Language (HTML)*

HTMLA

Stands for HTML-based administration, a method for remotely administering Microsoft Internet Information Services (IIS) Web servers.

See: *HTML-based administration (HTMLA)*

HTML-based administration (HTMLA)

A method for remotely administering Microsoft Internet Information Services (IIS) Web servers.

Overview

HTML-based administration (HTMLA) allows administrators to manage IIS Web servers using a standard Web browser such as Microsoft Internet Explorer as the client-side interface. IIS supports administration using HTMLA from any Web browser that supports the use of frames and JScript.

HTMLA is based on Microsoft Corporation's Component Object Model (COM) and Distributed Component Object Model (DCOM) programming architectures. The purpose of HTMLA is to simplify remote management of network resources and services by requiring that client machines used for remote administration of Web servers need only be running a standard Web browser. Most of today's networking products are moving toward one form or another of Web-based administration, and Microsoft's HTMLA feature of IIS was a pioneer in this area.

See Also: *Component Object Model (COM), Distributed Component Object Model (DCOM), Web server*

HTML Extension (HTX)

A text file with the extension .htx that is used by Indexing Service in Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Overview

HTML Extension (HTX) files are used to format the result set issued by Index Server in response to a catalog search query. These catalog search queries are issued using an Internet Data Query (IDQ) file. HTX files are also used by the Internet Database Connector (IDC) to format the result set of a database query.

The .htx file formats the result set of a query into a Hypertext Markup Language (HTML) page that the user who issued the query can read and understand. The .htx file acts as a template for formatting the result set and consists of HTML statements with additional tags and specific read-only variables such as

- CiMatchedRecordCount, which contains the number of records that match the query
- CiRecordsPerPage, which indicates the number of records on the next page

- CiContainsFirstRecord, which is 1 if the page contains the first record of query results and 0 otherwise

HTTP

Stands for Hypertext Transfer Protocol, a protocol that defines how Web browsers communicate and download information from Web servers.

See: *Hypertext Transfer Protocol (HTTP)*

HTTP Keep-Alives

An enhanced version of Hypertext Transfer Protocol (HTTP)–persistent connections supported by Microsoft Internet Information Services (IIS).

Overview

HTTP Keep-Alives allow a client Web browser to keep connections open with the Web server instead of closing them after the request has been answered and reopening them for each new Hypertext Transfer Protocol (HTTP) request, which consumes system resources. For this feature to work, however, both the client Web browser and the Web server must support HTTP Keep-Alives. Web browsers that support this feature include Microsoft Internet Explorer version 2 and later and Netscape Navigator 2 and later.

Notes

HTTP Keep-Alives are enabled by default in IIS. They are not the same as Transmission Control Protocol (TCP) Keep-Alives, which are periodic packets sent between machines to determine whether an idle connection is still active.

HTTPS

A secure version of Hypertext Transfer Protocol (HTTP).

Overview

Hypertext Transfer Protocol Secure (HTTPS) is essentially a combination of HTTP and the Secure Sockets Layer (SSL) protocol, and the designation *HTTPS* comes from the combination of the words *HTTP* and *secure*. HTTPS was originally developed by Netscape to enable the secure transmission of Web content over the Internet.

HTTPS is based on a public key cryptography system and allows information transmitted over the Internet to be encrypted for greater security. To run HTTPS on a Web server, you must first install a digital certificate on the server. Web browsers then connect to the server by providing a Uniform Resource Locator (URL) that begins with the prefix https:// rather than http://, which is usually used. HTTPS uses the TCP well-known port number 443 instead of port 80, which is used by standard HTTP.

Notes

Note that HTTPS is not the same as Secure Hypertext Transfer Protocol (S-HTTP), another protocol for secure HTTP transmission.

See Also: *Hypertext Transfer Protocol (HTTP), Secure Sockets Layer (SSL)*

HTTP status codes

Codes that Hypertext Transfer Protocol (HTTP) servers return in response to requests from HTTP clients.

Overview

HTTP status codes are three-digit codes that Web servers return in response to HTTP requests from clients. They are also known as HTTP error codes because most of them signify that some sort of error has occurred. An HTTP status code is one of the first pieces of information returned by a Web server in response to a request from a Web browser, and it informs the browser of the status of the request—whether the request was successful or not, and if not, why. When the server cannot satisfy the client’s request for some reason, a status code is returned to the client, which displays it for purposes of troubleshooting the problem. The client typically displays a message along with the status code to help the user understand the nature of the problem.

HTTP status codes are grouped into different categories by their first digit, as shown in the table on the following page.

HTTP Status Codes by Category

Status Code	*Category*	*Description*
1*xx*	Informational	An acknowledgement message from the server.
2*xx*	Success	The requested action was understood and completed.
3*xx*	Redirection	Further action must be taken to fulfill the request.
4*xx*	Client error	The request could not be performed because of client error.
5*xx*	Server error	The request could not be performed because of server error.

Examples

Some common status codes that are fairly self-explanatory include the following:

- 200 OK (not seen by the client)
- 301 Moved Permanently
- 400 Bad Request
- 401 Unauthorized
- 403 Forbidden
- 404 File Not Found
- 500 Internal Server Error

Notes

Web servers running Microsoft Internet Information Services (IIS) allow administrators to create customized HTTP status code pages that can be considerably more informative to users than traditional status codes such as "403 Forbidden."

See Also: *Hypertext Transfer Protocol (HTTP), Web server*

HTX

Stands for HTML Extension, a text file with the extension .htx that is used by Indexing Service in Windows 2000, Windows XP, and Windows .NET Server.

See: *HTML Extension (HTX)*

hub

A device used to connect shared Ethernet segments into a single local area network (LAN).

Overview

Hubs are the foundation of traditional 10/100BaseT shared Ethernet networks. They can be used to connect several dozen computers together to form a workgroup LAN, or they can be cascaded to create larger LANs of up to a hundred computers or more. Hubs typically have 4, 8, 12, or 24 ports for connecting stations using unshielded twisted pair (UTP) cabling terminated with RJ-45 connectors.

When a hub receives a signal from a station connected to a port, it repeats the signals to all other stations connected to the hub's ports (hence the alternative name "multiport repeater" is sometimes used to describe a hub). From a logical cabling point of view, stations wired into a hub form a star topology with the hub at the center and the stations at the points of the star. The physical topology of a hub, however, is bus topology, and all stations connected to a hub share the same bus connection.

Hubs were originally passive devices that simply repeated signals, but today's hubs are active hubs in which the signal received from one port is regenerated (amplified) and retransmitted to the other ports on the hub. Hubs typically have one or more uplink ports that are used for connecting the hub to other hubs in a cascaded star topology. You connect an uplink port on one hub to a regular port on another hub using a standard UTP cable. Alternatively, you can connect two hubs using the uplink ports by using a crossover cable.

Hubs generally have light-emitting diode (LED) indicator lights to indicate the status of each port, link status, collisions, and other information. Hubs with several different types of LAN connectors such as RJ-45, BNC, and AUI are commonly called combo hubs.

Types

There are numerous types of hubs for various specialized uses. These include the following:

- **Minihubs:** These typically have only four to eight ports and are used for quick or temporary LAN extensions. Minihubs can be as small as a cigarette pack and are often used for home area networks (HANs).

Stackable Hubs


Back
Front
RJ-45 ports

Using Hubs


10/100 dual-speed stackable hubs
10-Mbps stackable hubs
10BaseT LAN
100-Mbps fast hub
Mixture of 10-Mbps and 100-Mbps stations
100-Mbps servers
100BaseT LAN

Hub. *Stackable hubs and a diagram of hubs at work.*

- **Workgroup hubs:** These are the basic building blocks for creating workgroup LANs. Workgroup hubs typically have 8 or 16 ports on them, plus a BNC or an AUI port to provide more connectivity options within existing 10Base2 or 10Base5 networks. A hub is generally termed a workgroup hub if it supports up to 50 stations, a departmental hub if it supports up to 250 stations, and an enterprise hub if it supports more than 250 stations. Stackable hubs can also be used to provide these various capabilities.
- **Stackable hubs:** These hubs are modular in design and can be mounted in racks and cabinets within the wiring closet. The backplanes of stackable hubs can be connected together using special ribbon or DB-50 cables. Stackable hubs are available in configurations of 8, 16, and 24 ports and can be stacked to effectively form a single hub with 48, 72, 144, or more ports. Stackable hubs take less space and are easier to manage than regular workgroup hubs. Most stackable hubs also have an uplink switch that can be used to convert one of the ports into an additional uplink port, allowing you to connect another hub directly to the port. The opposite of a stackable hub is a simple stand-alone hub.
- **Intelligent hubs:** Also called managed hubs, these can be remotely managed and monitored using Simple Network Management Protocol (SNMP). Special connectors on the back of advanced hubs might provide features such as an RS-232 serial interface for connecting to an SNMP management console.
- **Dual-speed hubs:** These have autosensing ports that support combinations of both 100-megabit-per-second (Mbps) Fast Ethernet connections and 10-Mbps traditional Ethernet connections. Each port senses the speed of the attached station and configures itself to function at the appropriate speed. Advanced dual-speed hubs often contain internal Ethernet switch circuitry that segments the 10-Mbps and 100-Mbps connections into separate collision domains and forwards data between the domains to improve overall performance. These advanced hubs are sometimes called master hubs, and only one of these is required in a mixed 10/100-Mbps LAN.

  Dual-speed hubs are typically stackable hubs with 8 or 16 ports that can be stacked to support a total of 32 or 48 ports. They are useful in situations in which you are gradually migrating from 10BaseT to 100BaseT.
- **Fast Ethernet hubs:** These have 100-Mbps ports only for creating 100BaseT LANs. They are usually stackable hubs with advanced SNMP management functions, and they may also have built-in Ethernet switching functions. Often you can mix 100BaseTX and 100BaseT4 hubs in a stack that supports up to 144 stations, including fiber-optic ports for connecting to a high-speed fiber-optic backbone.
- **Modular hubs:** Also called enterprise hubs, these are expensive hubs that consist of a chassis in which cards or modules can be inserted to create custom hub configurations. Supported modules can include LAN cards for 10 and 100BaseT Ethernet, Token Ring, and Fiber Distributed Data Interface (FDDI); and wide area network (WAN) modules can include cards for frame relay, Integrated Services Digital Network (ISDN), X.25, and Asynchronous Transfer Mode (ATM). Enterprise hubs are intelligent, managed hubs that can be used to build complex network configurations.

Prospects

Hubs have largely been supplanted by switches in today’s enterprise-level Ethernet networks. Although a shared hub receives frames and blindly forwards them to all other attached stations, an Ethernet switch forms a temporary internal pathway to transmit the frame directly to the port belonging to the destination station. Shared hubs were still popular in the mid-1990s when price per port for switches was high, but with switch prices now comparable to those of hubs, any new enterprise deployment should consist mainly of switches instead of hubs. About the only remaining places where hubs can sensibly be deployed are in small workgroup scenarios and for home networks. In most other cases shared hubs usually represent a bad investment.

Notes

A device called a wiring concentrator or Multistation Access Unit (MAU) is similar to a hub but is used in Token Ring networks. Another device called a patch panel is used to organize UTP cabling in structured wiring implementations. Do not confuse either of these devices with a hub.

See Also: *10BaseT, 100BaseT, Ethernet, Ethernet switch*

HybridAuth

An authentication protocol proposed by the Internet Engineering Task Force (IETF) for Virtual Private Networking (VPN).

Overview

To deploy a secure VPN, companies must implement a public key infrastructure (PKI) for issuing and managing digital certificates. But deploying a PKI is complex, and the IETF has proposed a new protocol called HybridAuth to simplify the process.

The HybridAuth protocol is an extension to the Internet Key Exchange (IKE) protocol that defines how a user's credentials are exchanged over secure IPsec tunnels. IKE supports tunneling of two forms of authentication: digital certificates and preshared keys. HybridAuth enables digital certificates to be used asymmetrically between users and authentication servers and is simpler to deploy than a full-scale PKI solution.

See Also: *digital certificate, public key infrastructure (PKI), virtual private network (VPN)*

HyperTerminal

A communication utility included with Microsoft Windows that provides terminal access to remote computers using a modem.

Overview

HyperTerminal can be used to send and receive files between a local and remote computer over a modem and to connect to remote computer bulletin board systems. Network administrators can also use HyperTerminal to remotely connect to routers, switches, and other devices that support VT100 terminal emulation, and to enter text commands for configuring the device.

If you want to access files and printers on a remote computer running Windows 2000, Windows XP, or Windows .NET Server using a modem, use Network and Dial-Up Connections instead of HyperTerminal.

See Also: *router*

Hypertext Markup Language (HTML)

A formatting or markup language used to create documents for the World Wide Web (WWW).

Overview

Hypertext Markup Language (HTML) is the standard formatting language used to publish information on Web servers for delivery to Web browsers over the Internet. HTML allows linked sets of documents (that is, hypertext) to be created, stored, and accessed from Web servers using Uniform Resource Locators (URLs). HTML is simple to learn and was a key enabler in the explosion of the Internet in the 1990s.

History

HTML was created together with Hypertext Transfer Protocol (HTTP) in 1991 by Tim Berners-Lee as a means of disseminating information more easily among physicists and other scientists at CERN, the European Laboratory for Particle Physics. HTML was designed as a simplified version of Standardized Generalized Markup Language (SGML), a much more complicated formatting language that was developed previously but never widely implemented. HTML was created by combining the concept of hypertext, a concept created in the 1940s for linking documents together, with URLs, a method of uniquely naming hypertext documents so they could be easily accessed regardless of which servers they reside on. HTTP provides the additional protocol for communications between clients (called HTTP clients or Web browsers) and the servers (called Web servers or HTTP servers) on which HTML documents are stored.

In 1993, Marc Andreesen developed Mosaic at the National Center for Supercomputing Applications (NCSA). Mosaic was the first Web browser that supported documents containing both text and graphics (previous Web browsers supported only text documents). Andreesen left the NCSA to cofound Netscape Communications (now just Netscape), which produced the popular Netscape Navigator browser. Meanwhile, Microsoft Corporation licensed code from Mosaic through the commercial outlet Spyglass and developed its own popular browser, Microsoft Internet Explorer. Both Netscape and Microsoft pushed the evolution of HTML by introducing their own proprietary extension tags, the first being the

<font> tag from Netscape. The result was that HTML rapidly developed through several versions, including

- **HTML 2:** This was defined by RFC 1866 in 1995 and included various additional tags developed by Netscape and Microsoft.
- **HTTP 3.2:** Developed in 1996, this included support for tables, text flow around images, and other features.
- **HTTP 4:** Developed in 1997, this included support for style sheets that made <font> and other tags unnecessary (although they are still supported for backward compatibility).

To steer the evolution of HTML and prevent different vendor-specific versions from emerging, Berners-Lee formed the World Wide Web Consortium (W3C) in 1994. HTML 3.2 was the first version of HTML standardized by the W3C. Current work on HTML by the W3C involves development of the XHTML standard, a version of HTML written as an Extensible Markup Language (XML) application instead of an SGML one. The complementary HTTP protocol is standardized by a different group from the W3C, namely the Internet Engineering Task Force (IETF).

HTML has gone through several versions since it was created. At the time of this writing, the current version is HTML 4. The original HTML did not provide much control over how documents were formatted—that is, how objects such as text and graphics were laid out on a page. Its original set of tags was quite limited and was intended primarily for linking documents using hyperlinks to form hypertext. As the Web grew in popularity, however, first Netscape and then Microsoft introduced their own proprietary HTML tags to provide Web developers with more control over document formatting, thus increasing the pace at which the W3C developed the HTML standard. HTML 4 includes standards for creating cascading style sheets, which provides powerful formatting capabilities for precise placement of objects on a Web page.

Implementation

HTML in its simplest form uses tags to format ASCII text documents. These tags then indicate text that should be displayed as boldface, italic, bulleted, hyperlinked, and centered. HTML tags usually come in pairs, can be nested, can contain additional attributes, and are used to “mark up” the text. For example, the text “Save 50%” can be displayed on Web browsers in boldface by marking it up using the <STRONG> tag (which means “turn on the bold style”) and the </STRONG> tag (which means “turn off the bold style”). The resulting HTML would look like this:

```
<STRONG>Save 50%</STRONG>
```

HTML pages can be created using a broad range of tools from simple text editors such as Notepad to advanced publishing tools such as Microsoft FrontPage. HTML pages are saved as files with the extension .htm or .html to indicate they contain HTML text. Once created, HTML pages can be stored on Web servers such as Microsoft Windows 2000 servers running Microsoft Internet Information Services (IIS). When a Web browser such as Internet Explorer downloads an HTML page from a Web server, it interprets the tags and displays the document with the appropriate formatting.

Advantages and Disadvantages

The main advantage of HTML is its simplicity—a child can learn enough HTML to create a simple Web page. Because HTML was originally intended for exchanging information between scientists, support for formatting documents was initially limited. As the Web became more popular, new tags were introduced which made snazzy-looking documents possible. Together with style sheets, HTML documents can now be as complex in their formatting as documents produced for desktop publishing.

The main disadvantages of HTML are that it cannot easily create data hierarchies or structures, has a fixed set of tags, and cannot communicate information about the document’s content, only its format. As a result, a richer language called XML has been created to allow self-describing structured documents to be created. While HTML is designed for document presentation, XML is primarily designed to facilitate the exchange of hierarchically structured information, such as between businesses in a supply chain.

Prospects

Due to its simplicity, HTML will probably live on and not be replaced by the more powerful and complex XML. Several offshoots of HTML have been developed for mobile communications platforms that use devices whose display is too small to show traditional HTML pages. Some examples of these new platforms include

- Handheld Device Markup Language (HDML), developed by Phone.com
- Wireless Markup Language (WML), developed for use with the Wireless Application Protocol (WAP)
- cHTML, a subset of HTML developed for the I-mode cellular service of NTT DoCoMo in Japan

For More Information

You can see the W3C's HTML 4 Specification at *www.w3c.org/TR/REC-html40.*

See Also: *Handheld Device Markup Language (HDML), Hypertext Transfer Protocol (HTTP), Internet Engineering Task Force (IETF), Uniform Resource Locator (URL), Wireless Markup Language (WML), World Wide Web (WWW), World Wide Web Consortium (W3C), XML*

Hypertext Transfer Protocol (HTTP)

A protocol that defines how Web browsers download information from Web servers.

Overview

Hypertext Transfer Protocol (HTTP) is an application-level Transmission Control Protocol/Internet Protocol (TCP/IP) protocol first developed in 1990 as HTTP/0.9 and later standardized in 1996 by RFC 1945 as HTTP/1. The current version number for the protocol is HTTP/1.1 as defined by RFC 2616.

HTTP specifies the syntax for communication between HTTP clients and servers, which are defined as follows:

- **HTTP clients:** The most common example of an HTTP client is the Web browser, such as Microsoft Internet Explorer or Netscape Navigator, but any Web-enabled application can function as an HTTP client to request information from HTTP servers.
- **HTTP servers:** These are more informally known as Web servers, any servers that can communicate by means of HTTP with a client such as a Web browser. Examples of popular Web servers include Microsoft Internet Information Services (IIS) and Apache, the Open Source Web server.

Implementation

HTTP is implemented as a stateless request/response protocol. That is, clients make requests to servers, which then respond to the client. The HTTP protocol is called "stateless" because each request/response session is independent.



Hypertext Transfer Protocol (HTTP). *How a typical HTTP session works.*

An HTTP request consists of a message containing a request method, the file requested, and information about the client's capabilities. The request message consists of a series of headers encoded in plain text. The request method identifies the nature of the request and can be any of the following (not all methods may be supported by a particular HTTP server):

- **CONNECT:** Used by proxies for tunneling, for example, with Secure Sockets Layer (SSL) protocol
- **DELETE:** Deletes a file on the server
- **GET:** Requests a file from the server
- **HEAD:** Requests information concerning a file from the server (similar to GET, but the file itself is not returned in the response)
- **OPTIONS:** Requests information about the server's capabilities

- **POST:** Sends data to the server for processing, typically used with Hypertext Markup Language (HTML) forms
- **PUT:** Uploads a file to the server
- **TRACE:** Requests a loopback of the request message

An HTTP response may be either

- The information requested, encoded as a series of headers and an optional message body

or

- An error code indicating why the requested action could not be performed (see the article HTTP Status Codes elsewhere in this chapter)

The simplest example of an HTTP session is a client requesting a Web page from the server. The client sends an HTTP GET request over port 80 to the server. Other ports may be used, but port 80 is the default TCP port for HTTP requests, and Web servers typically listen to port 80 for such requests in order to fill them. When the server receives the request, it parses the headers and determines which file to return to the client. The file is then encoded using the appropriate Multipurpose Internet Mail Extensions (MIME) format and gets returned as a message body with a series of headers attached. The client receives the message, parses the headers, extracts the file from the message body, and displays the downloaded Web page.

In the HTTP/1 protocol, each request requires a separate TCP connection to be initiated and torn down afterward. This is slow—a Web page that has five images in it would need to be accessed using six requests, one for the text and one for each embedded image. As a result, a newer version, HTTP/1.1, was developed that allows a persistent TCP connection to be maintained so that many HTTP requests can be issued using it. This new feature is called HTTP Keep-Alives. Other features of HTTP/1.1 include

- Buffering of multiple HTTP GET requests into a single HTTP GET request
- Pipelining of multiple Internet Protocol (IP) packets to the server without waiting for the server to respond to each packet
- Support for caching of HTTP requests, proxies, and virtual hosts
- Host headers, a feature that enables a single Web server to host multiple Web sites using a single IP address

Notes

IIS supports the HTTP/1.1 version of HTTP.

HTTP's stateless nature makes it difficult to build Web applications that remember client requests across sessions. A common way of working around this issue is to use cookies, small files placed on the client by the server to store information across multiple sessions.

Do not confuse HTTP with HTML! HTTP is the protocol through which Web servers communicate with Web browsers. It is a control language for passing commands between clients and servers. HTML is Hypertext Markup Language, the language for constructing Web pages (the actual content passed from Web servers to Web clients in an HTTP request).

For More Information

Find out more about HTTP at the World Wide Web Consortium (W3C) Web site (*www.w3.org*).

See Also: *browser (Web browser), cookie, HTTP Keep-Alives, HTTP status codes, Web server*

I

I2O

Stands for Intelligent Input/Output (I2O), a hardware architecture developed by a consortium led by Intel that improves the input/output (I/O) performance of systems by relieving the CPU of interrupt-intensive I/O tasks.

See: *Intelligent Input/Output (I2O)*

IAB

Stands for Internet Architecture Board (IAB), a technical advisory group for the Internet Society (ISOC).

See: *Internet Architecture Board (IAB)*

IAD

Stands for Integrated Access Device, a wide area network (WAN) access device for consolidating voice and data, usually over Asynchronous Transfer Mode (ATM) circuits.

See: *Integrated Access Device (IAD)*

IANA

Stands for Internet Assigned Numbers Authority, the organization that coordinates the assignment of unique Internet Protocol (IP) parameters such as the IP address space and the Domain Name System (DNS).

See: *Internet Assigned Numbers Authority (IANA)*

IB

Stands for Infiniband, an emerging high-performance input/output (I/O) architecture.

See: *Infiniband (IB)*

IBGP

Stands for Interior Border Gateway Protocol, the version of Border Gateway Protocol (BGP) used for exchanging routing information within the same autonomous system (AS).

See: *Interior Border Gateway Protocol (IBGP)*

ICA

Stands for Independent Computing Architecture, a general-purpose presentation services protocol developed by Citrix Systems.

See: *Independent Computing Architecture (ICA)*

iCal

An Internet Engineering Task Force (IETF) standard for exchange of calendaring information.

Overview

The iCal standard defines a uniform data format for exchanging scheduling information. The intention is for iCal to be used by Internet-based applications so users can exchange information about meetings, appointments, and other events. The iCal standard replaces an earlier initiative called vCal or vCalendar.

The iCal standard is supported by Microsoft Outlook, the premier messaging and collaboration client from Microsoft. Specifically, Outlook uses a portion of iCal called iCalendar, together with an Outlook feature called Internet Free/Busy (IFB), to allow Outlook clients to exchange scheduling information over the Internet.

See Also: *vCard*

ICANN

Stands for Internet Corporation for Assigned Names and Numbers, a nonprofit corporation that has taken over some of the functions of the Internet Assigned Numbers Authority (IANA).

See: *Internet Corporation for Assigned Names and Numbers (ICANN)*

ICF

Stands for Internet Connection Firewall, a new integrated firewall application featured in Windows XP and Windows .NET Server.

See: *Internet Connection Firewall (ICF)*

ICMP

Stands for Internet Control Message Protocol, a Transmission Control Protocol/Internet Protocol (TCP/IP) network layer protocol used for various purposes.

See: *Internet Control Message Protocol (ICMP)*

ICMP Traceback Messages

An emerging standard from the Internet Engineering Task Force (IETF) for combating distributed denial of service (DDoS) attacks.

Overview

One of the Internet's greatest vulnerabilities is its exposure to DDoS, a form of attack in which hackers commandeer a large number of machines and turn them into "zombies" that are then used to attack Web servers with a flood of Internet Control Message Protocol (ICMP) packets. The source of these packets is difficult to track down because the packets contain spoofed Internet Protocol (IP) source addresses, making it difficult for administrators whose machines are under attack to trace the origin of these attacks. ICMP Traceback Messages, also known by the nickname itrace, is a protocol being developed by the IETF to make such tracking down possible.

Implementation

The itrace protocol is implemented on border and backbone routers deployed at Internet service providers (ISPs). Routers enabled with itrace occasionally tag regular IP packet traffic forwarded by routers with itrace messages. Typically, out of every 20,000 IP packets forwarded by a router, only one will have an itrace message attached to it. As a result, itrace has a negligible impact on network and router performance.


Hacker
Compromises and controls
Zombies
Router at ISP (itrace enabled)
Flood of ICMP packets
Internet
Target Web server
ICMP packets tagged with itrace
Administrator uses tagged packets to track down zombies

ICMP Traceback Messages. *How ICMP Traceback Messages can be used to track down the source of a DDoS attack.*

When a DDoS attack is underway, a flood of ICMP packets arrives at the target host. A small number (0.002 percent) of these packets will have itrace messages attached, and these messages can be used with a little ingenuity to trace the ICMP packets back to their sources on zombie machines, regardless of whether the source IP address of the packets is spoofed or not. Once the zombies can be identified, the administrator of the network on which they are located can be contacted to stop the attack and try to determine how their network was originally compromised. Note that itrace by itself can be used only to identify the zombies, not the hacker who originally compromised these machines.

To prevent hackers from spoofing the itrace messages themselves, a public key infrastructure (PKI) must guarantee the identity of the messages. This requirement, together with the cost of upgrading ISP routers, makes it probable that it may take a year or so after the ICMP Traceback Messages standard is ratified before it is widely deployed on key routers around the Internet. And for itrace to be effective in defeating DDoS attacks, it must be implemented on edge and backbone routers all over the Internet.

See Also: *Distributed Denial of Service (DDoS), hacking, Internet Control Message Protocol (ICMP), Internet service provider (ISP), router*

ICP (integrated communications provider)

Stands for integrated communications provider, a telecommunications service provider that offers one-stop shopping for voice and data telecommunications through a single integrated architecture.

See: *integrated communications provider (ICP)*

ICP (Internet Cache Protocol)

Stands for Internet Cache Protocol, a protocol that enables arrays of proxy servers to work together over a network.

See: *Internet Cache Protocol (ICP)*

ICQ

A popular Internet conferencing (chat) protocol.

Overview

ICQ is a proprietary protocol developed by Mirabilis and is similar to IRC (Internet Relay Chat). It enables users to locate other ICQ users on the Internet and communicate with them in real time. ICQ, which homophonically stands for "I seek you," lets you search for users currently online on ICQ networks and alerts you when friends go online. You can use ICQ to send real-time messages to other users, have group chat sessions, send e-mail, transfer files and URLs, play games, and perform other functions. ICQ can even function as a universal platform for launching any peer-to-peer application, such as Microsoft NetMeeting.

When you install ICQ and begin the registration process, you are connected to an ICQ server that belongs to a network of such servers distributed across the Internet. During registration, you are given a unique number called an ICQ#, which identifies you to all other users on the ICQ network. You use your ICQ# to register your presence with the ICQ network when you go online and start ICQ and to allow other ICQ users to recognize when you are online so that they can contact you. You can specify a list of ICQ friends, and an ICQ server will alert you when any of these friends go online.

For More Information

Visit ICQ Inc. at *www.icq.com.*

See Also: *instant messaging (IM), Internet Relay Chat (IRC)*

IDS

Stands for intrusion detection system, any system used to detect attacks on a host or network.

See: *intrusion detection system (IDS)*

IDSL

Stands for ISDN Digital Subscriber Line, a hybrid of Integrated Services Digital Network (ISDN) and Digital Subscriber Line (DSL) technologies.

See: *ISDN Digital Subscriber Line (IDSL)*

IE

Stands for Internet Explorer, Microsoft Corporation's integrated suite of client-side Internet software, which is included with all current versions of Microsoft Windows.

See: *Internet Explorer*

IEAK

Stands for Internet Explorer Administration Kit, a tool for customizing and deploying Microsoft Internet Explorer throughout an enterprise.

See: *Internet Explorer Administration Kit (IEAK)*

IEEE

Stands for Institute of Electrical and Electronics Engineers, a worldwide nonprofit association of technical professionals.

See: *Institute of Electrical and Electronics Engineers (IEEE)*

IEEE 488

A parallel interface standardized by the Institute of Electrical and Electronics Engineers (IEEE).

Overview

Also known as the General-Purpose Interface Bus (GPIB), the IEEE 488 parallel interface was developed by Hewlett-Packard and is used mainly for connecting computers to measurement sensors and test equipment for automatic data acquisition in a laboratory or industrial setting. Examples of such equipment include signal generators, frequency counters, voltmeters, and temperature sensors.

Architecture

IEEE 488 supports high-speed parallel communication using a 24-pin connector. An IEEE 488 cable generally has eight single wires for data transfer, eight twisted-pairs for interface handshaking and management, and a drain (ground) wire, all enclosed in an insulating protective jacket. This configuration provides eight bidirectional channels for transmitting 1 byte (8 bits) of information at a time, at a maximum bus speed of 1 megabit per second (Mbps) using tristate drivers.

The IEEE 488 standard lets you chain together up to 15 devices for a total length of 20 meters (66 feet), with no more than three connectors stacked and no more than 2 meters (6.5 feet) between adjacent devices. The master device acts as a controller that determines which device can transmit data over the bus at any given time, while the other devices are placed in standby mode. Only one device can transmit signals on the bus at any given time, but multiple devices can receive those signals.

Notes

If your industrial environment is dusty or has high levels of electromagnetic interference (EMI) from motors, generators, or other heavy equipment, you can obtain special shielding covers to protect your IEEE 488 connectors. You can also use switchboxes to alternate several industrial sensors on a single IEEE 488 cable.

IEEE 802 standards

Also called Project 802, an ongoing project of the Institute of Electrical and Electronics Engineers (IEEE) for defining local area network (LAN) and wide area network (WAN) standards and technologies.

See: *Project 802*

IEEE 1284

A high-speed bidirectional parallel interface standardized by the Institute of Electrical and Electronics Engineers (IEEE).

Overview

IEEE 1284 enables bidirectional communication between computers and attached printers and enables computers to spool jobs to printers at more than 10 times the speed of a traditional parallel port interface. Also called Enhanced Parallel Port (EPP), IEEE 1284 is compatible with the Centronics interface standard used for connecting parallel port printers to computers. This bidirectional communication allows the print device to return information to the computer that queried it for hardware information. This information can include device ID value, printer memory, installed fonts, and other information that the printer driver on the server can use to install and configure the printer. Bidirectional communication also allows the print device to send status messages (such as an “out of paper” message) to the server.

Architecture

IEEE 1284 specifies two electrical interfaces:

- Level I interface, which functions at a lower speed and provides only reverse-mode capabilities
- Level II interface, which functions at a higher speed and provides bidirectional communication

The connectors for the IEEE 1284 interface also come in various types:

- Type A connectors, which are standard 25-pin DB25 connectors
- Type B connectors, which are 36-pin centerline Champ connectors with bale locks to hold the cable in place for physical security
- Type C connectors, which are 36-pin centerline miniconnectors with clips for physical security

Implementation

Microsoft Windows 2000 can detect plug-and-play print devices by communicating with them using IEEE 1284. To make bidirectional printing work, you need

- A print device such as a laser printer that supports bidirectional printing.
- A correctly configured parallel port on the connected computer or print server. For example, if the parallel port is configured as AT-compatible, change it to PS/2 mode.
- An IEEE 1284–compliant cable having a DB25 male connector on one end and a Centronics 36 male connector on the other. IEEE 1284 cables are commonly used for connecting laser printers, scanners, tape drives, and portable storage devices (such as Iomega Zip drives) to a computer. An IEEE 1284 cable typically has “IEEE 1284” printed on its insulating jacket.

Notes

You can also obtain cables for converting the IEEE 1284 parallel interface to the universal serial bus (USB) interface to connect print devices with a Centronics connector to a computer with a USB connector. Special signal-powered IEEE 1284 cables can allow printers to be located up to 100 feet (30 meters) from the connected computer and still maintain reliable communication. Adapters are available for connecting 36-pin and DB25 connectors.

IEEE 1394

Better known by its trademarked name “FireWire,” a serial interface for connecting high-speed peripherals to computers.

See: *FireWire*

IETF

Stands for Internet Engineering Task Force, an international community of networking engineers, network administrators, researchers, and vendors whose goal is to ensure the smooth operation and evolution of the Internet.

See: *Internet Engineering Task Force (IETF)*

iFS

Stands for Internet File System, a technology developed by Oracle Corporation for sharing data over the Internet.

See: *Internet File System (iFS)*

IGMP

Stands for Internet Group Management Protocol, a Transmission Control Protocol/Internet Protocol (TCP/IP) network layer protocol used for informing routers of the availability of multicast groups on the network.

See: *Internet Group Management Protocol (IGMP)*

IGP

Stands for interior gateway protocol, any routing protocol used to distribute routing information within an autonomous system.

See: *interior gateway protocol (IGP)*

IGRP

Stands for Interior Gateway Routing Protocol, an interior gateway protocol (IGP) developed by Cisco Systems.

See: *Interior Gateway Routing Protocol (IGRP)*

IIOP

Stands for Internet Inter-Orb Protocol, a CORBA (Common Object Request Broker Architecture) technology for distributed computing over the Internet.

See: *Internet Inter-Orb Protocol (IIOP)*

IIS

Stands for Internet Information Services, a Microsoft Windows service that provides support for application-layer Internet protocols.

See: *Internet Information Services (IIS)*

IIS Object Cache

A cache maintained by Microsoft Internet Information Services (IIS).

Overview

The IIS Object Cache stores file objects that are frequently requested by the World Wide Web (WWW), File Transfer Protocol (FTP), and Simple Mail Transfer Protocol (SMTP) services and by Active Server Pages (ASP) applications. The IIS Object Cache contains handles for open file objects, directory listings, and other frequently used file system objects. The cache runs within the main inetinfo.exe process and provides improved performance for IIS services and ASP applications.

Notes

For performance reasons, you should keep the IIS Object Cache in the working set of the IIS process in RAM. Be sure that you have sufficient RAM to do this. If you do not have enough RAM, the IIS Object Cache will be paged to disk and performance will be impaired. You can observe the performance of the cache by using Performance Monitor. Look for counters relating to cache hits and cache misses for each IIS service.

See Also: *Internet Information Services (IIS)*

IISP

Stands for Interim Interswitch Signaling Protocol, an Asynchronous Transfer Mode (ATM) protocol that enables cells to be routed over a switched virtual network (SVC).

See: *Interim Interswitch Signaling Protocol (IISP)*

IKE

Stands for Internet Key Exchange, a protocol for managing keys in public key cryptography systems.

See: *Internet Key Exchange (IKE)*

IL

Stands for Intermediate Language, an intermediate byte code used by Microsoft Corporation’s new .NET platform.

See: *Intermediate Language (IL)*

ILEC

Stands for Incumbent Local Exchange Carrier, another name for local telephone companies or telcos.

See: *Incumbent Local Exchange Carrier (ILEC)*

ILS

Stands for Internet Locator Service, a Lightweight Directory Access Protocol (LDAP) directory service that enables Microsoft NetMeeting users to locate and contact other users for conferencing and collaboration over the Internet.

See: *Internet Locator Service (ILS)*

IM

Stands for instant messaging, a service that supports real-time call-based communications over the Internet.

See: *instant messaging (IM)*

IMA

Stands for Inverse Multiplexing over ATM, a high-speed Asynchronous Transfer Mode (ATM) technology.

See: *Inverse Multiplexing over ATM (IMA)*

IMAP4

Stands for Internet Mail Access Protocol version 4, a standard protocol for storage and retrieval of e-mail messages.

See: *Internet Mail Access Protocol version 4 (IMAP4)*

i-mode

A popular mobile communications service in Japan.

Overview

The i-mode service is currently the largest national packet-switched cellular service in the world. By the end of 2000 there were more than 10 million subscribers to this service and thousands of third-party applications and services developed for it. The i-mode service is a 2.5G cellular service operated by NTT DoCoMo and represents a model that's being considered by some providers that are currently implementing General Packet Radio Service (GPRS), such as Pacific Century CyberWorks (PCCW), a mobile services provider in Hong Kong SAR.

See Also: *2.5G, cellular communications*

impedance

In engineering, the measure of resistance to the flow of electric current.

Overview

Impedance to signal flow within a transmission line has three components: a resistive component, a capacitative component, and an inductive component. The value for each component varies with the frequency of the current, which means that the overall impedance of a transmission line also varies with frequency. A perfect transmission would have an impedance that does not change with frequency.

Characteristic impedance is the measure of resistance of a transmission line (such as a cable) calculated with the assumption that the cable is of infinite length. It is represented by the symbol Z_0. Each type of network cabling has its own characteristic impedance. Twisted-pair cabling can have a relatively constant impedance by virtue of its design and dimensional characteristics. The Electronic Industries Association/Telecommunications Industries Association (EIA/TIA) wiring standards, specifically EIA/TIA 568-A (Commercial Building Telecommunications Cabling Standard), mandate that Category 5 (Cat5) cabling should have an impedance of 100 ohms, plus or minus 15 percent, up to a frequency of 100 megahertz (MHz). It is important that cabling meet these standards because networking equipment, such as hubs, switches, and routers, is designed to match this impedance value. If wiring with a different impedance is used with such equipment, reflections of signals can occur that can distort signals, create signal loss, and degrade network communications—or even render them impossible.

Notes

Impedance is an issue only with copper cabling and is not a relevant physical characteristic for fiber-optic cabling.

See Also: *cabling*

impersonation

A security mechanism for client/server communication.

Overview

In Microsoft Windows 2000, Windows XP, and the Windows .NET Server family, impersonation is a method that a server uses to determine whether a client has sufficient rights to access a resource.

Impersonation involves temporarily altering the server's security context so that it matches that of the client. When the client attempts a connection to a resource on the server, it tells the server the impersonation level that the server can use to service the client's request. The client can offer four impersonation levels:

- **Anonymous:** The server does not receive any information about the client's security context.
- **Identification:** The server can authenticate the client but cannot use the client's security context for performing access checks.
- **Impersonation:** The server can both authenticate the client and use the client's security context to perform access checks.
- **Delegation:** The server authenticates the client and passes the client's security context to a remote server on the client's behalf. Delegation is not supported by the NTLM authentication method of Windows NT Server, but delegation is supported by the Kerberos authentication method of Windows 2000, Windows XP, and Windows .NET Server.

Examples

An example of impersonation occurs when anonymous access is enabled on a Web site hosted on Internet Information Services (IIS). Anonymous access uses the IUSR_ComputerName anonymous account on the IIS server, which is by default part of the Guests local group. If an IIS machine receives a Hypertext Transfer Protocol (HTTP) request from a remote Web browser, IIS impersonates the IUSR_ComputerName account so that it can allow the remote client to access the requested files or run the requested application. This prevents access to system files on the IIS machine by the remote client.

IMT-2000

Stands for International Mobile Telecommunications-2000, an initiative of the International Telecommunication Union (ITU) to create a global standard for third-generation (3G) wireless data networks.

See: *International Mobile Telecommunications-2000 (IMT-2000)*

IMUX

Stands for inverse multiplexer, a device that can perform inverse multiplexing of digital telecommunication channels.

See: *inverse multiplexer (IMUX)*

in-addr.arpa

A special domain in the Domain Name System (DNS) that is used for inverse queries.

Overview

The in-addr.arpa domain contains nodes whose names are based on Internet Protocol (IP) addresses with octets in the reverse order. For example, a host with the IP address 172.16.8.44 would be represented in the in-addr.arpa domain by 44.8.16.172.in-addr.arpa. Resource records for the in-addr.arpa domain are called pointer (PTR) records and are contained within a type of zone file called a reverse lookup file. Using the in-addr.arpa domain, a resolver can submit a request to a name server to resolve an IP address into its corresponding fully qualified domain name (FQDN).

See Also: *Domain Name System (DNS)*

in-band signaling

A method of transmitting control information through the same circuit or line that carries data.

Overview

Generally, any signaling transmission that takes place within a range of frequencies that is normally used only for data transmission is known as in-band signaling. Instead of using separate control and data channels, control information is transmitted using a portion of the data channel. If a separate control channel is used instead, the approach is called out-of-band signaling.

Implementation

As an example, in-band signaling is used in switched 56 services, in which a 64-kilobit-per-second (Kbps) digital communication link has 8 Kbps set aside for control signaling. This is sometimes referred to as "robbed-bit signaling" because the 8-Kbps bandwidth is "robbed" from the data channel for handling control functions such as wide area network (WAN) link synchronization. T1 lines that use switched channels also use in-band signaling techniques.



In-band signaling. *Comparison with out-of-band signaling.*

See Also: *out-of-band (OOB) signaling*

incremental backup

A form of partial backup used in between normal backups during a backup cycle.

Overview

In an incremental backup, only those files and folders that have changed since the last normal backup are backed up. The archive attribute is also marked for each file and folder backed up.

Incremental backups are typically used in conjunction with normal backups to simplify and speed up the overall backup process. If you do a normal backup on one particular day of the week, you can perform incremental backups on the remaining days to back up only the files that have changed during each day of the backup schedule. Incremental backups are faster than normal backups and use less tape.

Notes

Incremental backups are not cumulative, as differential backups are, so when you need to perform a restore, you need the normal backup and all incremental backups since the normal backup was done. Incremental backups are faster to perform but take longer to restore.

See Also: *backup type, differential backup*

incremental zone transfer

A method of updating zone information between name servers in the Domain Name System (DNS).

Overview

Incremental zone transfer is a more efficient method of propagating zone updates than the earlier standard DNS method of transferring the entire zone file using the AXFR request. Incremental zone transfer is defined in RFC 1995 and uses the IXFR request to transfer only the minimal information needed to keep the DNS servers within a given zone of authority in synchronization.

In incremental zone transfer, every primary or master DNS server maintains a full copy of the up-to-date zone file plus an additional version history that records any changes to resource records that occurred during recent updates of the zone file. When a secondary DNS server makes an IXFR request to a primary or master DNS server, the master server compares the zone version number of the secondary server's zone to its own current version number. The zone version number is the serial number stored in the start of authority (SOA) record of the DNS server. If the master server has a newer version number and incremental zone transfers are supported, the master server sends to the secondary server only those changes to resource records that have occurred in the time interval between the two version numbers. If the version numbers of the master and secondary servers match, no zone transfer takes place. And if incremental zone transfer is not supported, the normal full zone transfer takes place instead.

Notes

Incremental zone transfers are supported as part of the dynamic update features of Microsoft Windows 2000 and Windows .NET Server.

See Also: *Domain Name System (DNS), zone transfer*

Incumbent Local Exchange Carrier (ILEC)

Another name for local telephone companies or telcos.

Overview

Incumbent Local Exchange Carriers (ILECs) include

- Regional Bell Operating Companies (RBOCs), holding companies for about two dozen telephone companies that were created by the divestiture of AT&T in 1984.
- Other smaller independent telephone companies, especially in rural areas

The name *Incumbent Local Exchange Carrier* basically means that ILECs are

- **Incumbent:** They are the ones who own and control the local loop wiring infrastructure that provides telephone services to customers in their particular area.
- **Local:** They service specific regions of the United States, in contrast to inter-exchange carriers (IXCs), which provide long-distance services from coast to coast.
- **Exchange:** They provide telephone exchange services through their central office (CO) switching facilities, enabling customers to dial and make calls.
- **Carriers:** They "carry" phone line signals and generally provide a wide range of telecommunication services as well.

In contrast, Competitive Local Exchange Carriers (CLECs) are companies that either

- Lease local loop services from ILECs to provide customers with such services as Digital Subscriber Line (DSL), T-carrier, and frame relay (DSL is the most popular CLEC offering), or
- Provide their own connection to customers, typically fiber-optic connections for businesses in dense urban areas to provide such services as Voice over IP (VoIP) and Metropolitan Ethernet. Cable TV (CATV) operators generally are not referred to as CLECs even though they may provide services such as Internet access that "compete" with other Local Exchange Carriers (LECs).

Prospects

Despite the Telecommunications Act of 1996, which was intended to open up the telecom market by giving IXCs and CLECs access to ILEC's local loop wiring, the process has been far from smooth. Analysts have often seen ILECs as reactionary dinosaurs compared to the cutting-edge technologies offered by CLECs. For example, ILECs have not followed through on decades-old promises of replacing the existing copper loop wiring infrastructure with fiber-optic cabling to provide "fiber to the curb" services for business and residential customers. In addition, since the Telecommunications Act some ILECs have been slow in opening up their local loop networks to competitors, resulting in legal challenges that have led in some cases to Federal Communications Commission (FCC) rulings and penalties.

With the collapse of the dot-com bubble in 2001, however, investment in CLECs has declined precipitously, driving many out of the market and forcing others to merge or to be acquired by ILECs and IXCs. The result after five years is that the ILECs have had time to consolidate their positions as regulated monopolies and have begun modernizing their networks to provide high-demand services such as Asymmetric Digital Subscriber Line (ADSL) services for Internet access and High-bit-rate Digital Subscriber Line (HDSL) for enterprise wide area network (WAN) connectivity. ILECs are now offering broadband telecommunication services through Digital Subscriber Line (DSL) over the copper local loop.

Notes

Enterprise network architects looking for telecommunication carriers they can use to build reliable, fault-tolerant WANs should carefully investigate the current offerings before jumping in and making commitments. Wherever possible, each branch of a large enterprise should employ two LECs instead of one to provide redundancy for its WAN connection, but make sure that each LEC uses a different point of presence (POP). For example, if you use the services of an ILEC and a CLEC, make sure the CLEC is not simply reselling services from the same ILEC using the same POP, which would nullify the redundancy of the arrangement. If buying WAN services, such as frame relay, from an IXC, be sure to also consider incorporating a redundant arrangement from another IXC or RBOC to protect your investment.

If you want to provision your company with DSL services, you typically have to go through a CLEC because ILECs are effectively regulated monopolies and usually are not allowed to act as Internet service providers (ISPs). This double provisioning makes DSL services more complex to deploy and troubleshoot because you have to deal with two companies instead of one (although the CLEC will usually be your front-end contact in the matter).

See Also: *Competitive Local Exchange Carrier (CLEC), inter-exchange carrier (IXC), local exchange carrier (LEC), Regional Bell Operating Company (RBOC)*

Independent Computing Architecture (ICA)

An architecture for server-based computing from Citrix Systems.

Overview

Independent Computing Architecture (ICA) is similar to Microsoft Corporation's RDP (Remote Desktop Protocol) and the X Windows System from Sun Microsystems and X/Open in that it provides

- A centralized multiuser operating system that allows remote users to log on and run applications on the server from thin clients such as terminals and appliances.
- A presentation services protocol that displays a desktop generated by the server on the client.

Implementation

ICA enables the user interface of an application to run with minimal consumption of resources on a client device while the actual application logic executes on an ICA-enabled server (sometimes called a terminal server). The only data transferred over the network between the server and the client device are the user interface, keystrokes, and mouse movements. This results in minimal resource requirements for the client, allowing the use of a "thin client." An ICA presentation only requires about 5 Kbps throughput each direction, so ICA clients can access ICA servers over a wide variety of connections, including 14.4 Kbps and higher modems, ISDN terminal adapters, wireless 802.11b LANs, and traditional Ethernet local area networks (LANs).

ICA provides location independence because it runs the server operating system and application programs at a centralized location while displaying the user interface on supporting clients anywhere on the network. The ICA presentation services protocol also runs over most industry-standard networking protocols including Transmission Control Protocol/Internet Protocol (TCP/IP), NetBEUI, and Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX). ICA also runs over encapsulation transports such as Point-to-Point Protocol (PPP) on top of wide area network (WAN) transport protocols such as Integrated Services Digital Network (ISDN), frame relay, and Asynchronous Transfer Mode (ATM).

ICA also supports browser-based access, enabling applications to be launched from Web pages and making ICA a platform-independent solution. ICA also supports shadowing, which enables administrators to remotely take over control of thin clients for troubleshooting or instructional purposes.

Marketplace

Citrix makes a product called Metaframe that can be installed on different Microsoft Windows server platforms to allow ICA clients to access these servers. In the arena of thin clients, the first ICA appliance to reach the market was the Winterm 1200LE from Wyse Technology, which uses embedded BSD UNIX.

See Also: *Remote Desktop Protocol (RDP), terminal, terminal server*

index

In relational database terminology, a database object that enables efficient and rapid access to data in the rows of a table using key values.

Overview

Indexes are created on columns in a database table and provide a way to logically order rows in a database table. Because databases without indexes take much longer to query, planning and implementing indexes comprise an essential part of database design. Indexes can also be used to enforce the uniqueness of rows in a database table by building the index on a key value.

Notes

Although using indexes generally speeds queries, it is not a good idea to have an index for every column because building the index takes time and requires additional disk space, plus modifying the contents of the database causes modifications to the index. You should only create indexes for the following:

- Primary and foreign keys
- Data on which you frequently issue search queries
- Columns that are often retrieved in a sorted order or are used in joins

See Also: *database, join, key (database)*

Infiniband (IB)

An emerging high-performance input/output (I/O) architecture.

Overview

Infiniband (IB) is a new I/O architecture designed for connecting high-performance servers with distributed storage systems such as Storage Area Networks (SANs). IB is designed to overcome the limitations of the standard Peripheral Component Interconnect (PCI) system bus, which is often a bottleneck in enterprise computing systems as far as storage is concerned. The 32-bit 33 megahertz (MHz) PCI bus and its faster 64-bit 133 MHz PCI-X bus are system buses that are capable of transporting data at speeds up to 1 gigabit per second (Gbps). Unfortunately, this means that for high-performance servers using Gigabit Ethernet (GbE) network interface cards (NICs), the entire throughput of the bus could be eaten up by the NIC alone, leaving insufficient bandwidth for moving data between disk storage and RAM. In contrast, IB will offer bus speeds of 10 Gbps or more, sufficient for most current situations.

Another limitation of PCI and PCI-X is that they are shared-bus architectures in which attached devices contend for use of the bus (similar to half-duplex Ethernet). In contrast, IB is a switched architecture that provides each attached device the maximum possible bandwidth and high scalability. IB is not intended to replace PCI/PCI-X but rather to complement these architectures in high-end servers and network storage systems.

History

IB emerged from two earlier competing architectures: Next Generation I/O (NGIO) and Future I/O. These technologies were similar but were supported by different industry coalitions. In 1999, these coalitions joined forces to forge a new System I/O standard, which was renamed IB or Infiniband Architecture (IBA). The IB standards are steered by the Infiniband Trade Association, whose members include Compaq Computer Corporation, Dell Computer Corporation, Hewlett-Packard, IBM, Intel Corporation, Microsoft Corporation, and Sun Microsystems.

Implementation

IB employs a switched point-to-point architecture. Virtual channels are used for establishing communications between different IB-capable devices connected to an IB switch, and multiple channels can be established between two devices to provide fault tolerance in communications. Devices are connected to switches using channel adapters, of which there are two types:

- **Host channel adapter (HCA):** This is used within hosts (servers) to connect processors and memory with external storage systems and network connections. The HCA connects to the server's memory controller, which controls access to the PCI/PCI-X system bus, the processors, and memory.
- **Target channel adapter (TCA):** This is used to connect devices that provide a network service, such as a JBOD (just a bunch of disks) storage farm, a Small Computer System Interface (SCSI) drive array, a Fibre Channel Storage Area Network (SAN), or a local area network (LAN) connection.

IB currently runs only over fiber-optic cabling, although proposals have been made for running it over specialized copper cabling (not standard Category 5 cabling).

Marketplace

The first company to release a commercial product based on the IB 1 standard was the startup Mellanox Technologies, which produced switches and adapters in its InfiniBridge line of products. Since then a number of vendors have started to release similar products, and a flood of Infiniband products is expected to hit the market sometime in 2002.



Infiniband (IB). *A simple example of using the IB architecture in enterprise computing.*

Prospects

The main competitor for IB is Fibre Channel, which already has a head start through a large installed base in enterprise SANs. Although IB was developed mainly as an I/O bus for distributed storage, it can also be used for creating server clusters and to interface directly with LAN switches and wide area network (WAN) access devices. The advantage in speed that IB has over Fibre Channel may also be eroded as efforts are made to push Fibre Channel speeds to 10 Gbps. The biggest advantage IB has is probably its current wide support among major vendors. The next few years will decide which architecture wins out.

See Also: *Fibre Channel, storage, storage area network (SAN)*

Infrared Data Association (IrDA)

An international consortium of hardware and software manufacturers that creates and promotes interoperable solutions for infrared (IR) data networking for computer networks, communication, and other networking applications.

Overview

The Infrared Data Association (IrDA), which was formed in 1993, has more than 150 members from hardware, software, and communication sectors. It has developed and agreed on standard formats for communication between computers and infrared devices to ensure interoperability between different systems, platforms, and devices. The IrDA also schedules meetings, conferences, and other events relating to infrared networking technologies. IrDA standards include the IrDA Data and IrDA Control infrared communication standards.

Notes

The IrDA standards have not been as widely implemented as had been hoped, mainly because infrared communication is essentially a line-of-sight (LOS) communications technology that is suited only to stationary users and devices. Some analysts believe the emergence of Bluetooth wireless networking technologies may eventually relegate IrDA to legacy technology, but this remains to be seen.

For More Information

Visit the IrDA at *www.irda.org.*

See Also: *infrared transmission, IrDA Control, IrDA Data*

infrared transmission

The transmission of data or voice information over infrared (IR) light.

Overview

IR light is beyond the red end of the visible spectrum. Wavelengths in the range of 770 to 1400 nanometers (nm) are called the near infrared region of the electromagnetic spectrum, and longer wavelengths are called the far infrared. In computer networking, IR is often used to connect laptops or Personal Digital Assistants (PDAs) to peripherals (such as printers) without the use of wires. IR is also frequently used to connect laptops to desktop computers for synchronizing files.

Implementation

The most popular computer industry standard for infrared transmission is the IrDA Data standard developed by the Infrared Data Association (IrDA). In a typical IrDA scenario, IR communication makes use of devices called transducers, which consist of a driver and an emitter that can both transmit and receive infrared transmissions. The transducer is typically connected to an encoder/decoder that interfaces with the computer or peripheral's universal asynchronous receiver-transmitter (UART) for asynchronous serial transmission between the devices.

The IrDA Data protocol suite initiates a connection using the discovery functions of the Infrared Link Management Protocol (IrLMP) and then establishes the primary and secondary stations using the Infrared Link Access Protocol (IrLAP). The secondary station then adjusts its data speed to match the primary station and establishes a serial communication link.

Advantages and Disadvantages

The main disadvantages of IrDA devices are that they have severe distance limitations and require a direct line of sight between devices in order to communicate. Furthermore, outdoor communications can be adversely affected by fog and other bad weather conditions. The main advantage, of course, is that communications can be established without the bother of having to deploy wiring or cables, which makes IR mainly useful for transient (short time period) connections in a mobile or changing environment.

See Also: *Infrared Data Association (IrDA)*

infrastructure

A term that refers to the collection of hardware and cabling that makes network communications possible in an enterprise.

Overview

In computer networking and telecommunications, infrastructure generally consists of two aspects:

- **Passive portion:** The cabling and other wiring used to connect hardware devices. This also includes passive devices such as patch panels, connectors, and other devices. If wiring is mainly Category 5 (Cat5) or higher twisted pair copper cabling, the hierarchical structure of such wiring is typically referred to as structured wiring or structured cabling.
- **Active portion:** Hardware devices such as hubs, switches, routers, and other networking devices. If the enterprise is geographically distributed across multiple locations, then wide area network (WAN) access devices and carrier services may also be considered part of the company's infrastructure.

Marketplace

The infrastructure market is mainly dominated by large players. Examples include

- **Cisco Systems:** Holds a large share of the networking hardware market at three levels: service providers (such as Internet service providers [ISPs] and telcos), enterprise (large companies), and commercial (small and mid-sized companies). Popular vendor for switches, routers, integrated access devices (IADs), and other hardware.
- **Juniper Networks:** Popular switch/router vendor at the service provider level, with roughly one-third of this market.
- **Nortel Networks:** Top vendor in the optical networking market, and a major Voice over IP (VoIP) vendor through partnership with Cable & Wireless.
- **IBM:** Popular vendor in the Web-to-host networking environment.
- **EMC Corporation:** Heavyweight in the network storage arena, with 35 percent of the market. The network storage market, including both Storage Area Network (SAN) and network attached storage (NAS) approaches, is the fastest growing segment of the enterprise infrastructure market.

Other popular infrastructure vendors include Enterasys Networks, Lucent Technologies, and many others.

Prospects

One recent development is the emergence of online superstores where enterprise customers can purchase infrastructure products. Examples of these include Buy.com and cdw.com. Another development is online IT (information technology) exchanges, where infrastructure products and services can be purchased and provisioned. Examples here include Cymerc Exchange (switches and routers), Simplexity (telecom services), ITParade.com (refurbished equipment), and Tek-Sell.com (online auctions of IT equipment).

See Also: *router, structured wiring, switch*

inheritance

The process of child objects acquiring the security settings of parent objects.

Overview

In Microsoft Windows 2000, Windows XP, and the Windows .NET Server family, inheritance is a feature that allows the access control entry (ACE) for an object whose security settings are being configured to be propagated to other objects that are beneath it in the file system or directory hierarchy. Inheritance simplifies the administration of hierarchical file systems and directories by allowing administrators to configure ACEs globally and then modify them on an exception basis, rather than configure ACEs individually for each object in the system.

In Windows NT, inheritance is used in the NTFS file system for propagating the permissions assigned to a folder to the files and folders within that folder. In Windows 2000, inheritance also applies to the Active Directory directory service and allows permissions assigned to a container or an organizational unit (OU) within Active Directory to be propagated further down the directory tree. Inheritance also appears in other directory-based systems such as Microsoft Exchange Server, in which Exchange administrative permissions assigned to a container in the Exchange directory that is based on the Lightweight Directory Access Protocol (LDAP) can be applied to leaf objects and other containers within that container.

See Also: *delegation, discretionary access control list (DACL), permissions*

INI files

Text files used in legacy versions of Microsoft Windows.

Overview

Windows 3.1 and Windows for Workgroups stored configuration information about hardware, devices, and services in text files called INI (initialization) files. These files, which have the extension .ini, included

- WIN.INI, which stores information about the desktop environment, fonts, and printers, as well as other settings
- SYSTEM.INI, which stores boot settings and information specific to running in Standard and 386 Enhanced modes
- CONTROL.INI, which maintains the Windows color schemes
- PROGMAN.INI, which stores information about program groups
- WINFILE.INI, which stores status information for File Manager

In addition, individual applications often created their own INI files during installation to store application-specific settings.

In later versions of Windows, including Windows 95, Windows 98, Windows Millennium Edition (Me), Windows NT, and Windows 2000, INI files are replaced by the registry, a hierarchical structure used to store all system and application configuration settings. Nevertheless, INI files are still included in these operating systems to provide backward compatibility for running 16-bit Windows programs because such programs were designed to save their settings in INI files and cannot access the registry.

See Also: *Microsoft Windows, registry*

instance

A particular occurrence of a System Monitor counter in Microsoft Windows 2000, Windows XP, and the Windows .NET Server family.

Overview

As an example, if the %Privileged Time counter is being monitored for the Processor object on a symmetric multiprocessing (SMP) machine with four processors, individual instances of that counter are instances 0, 1, 2, and 3. By using instances, you can monitor the performance of processes, threads, and devices on a per-instance basis for detailed understanding of their resource use on a machine. Individual instances of a given counter can be displayed in the usual way using charts and graphs.

instant messaging (IM)

A service that supports real-time, call-based communications over the Internet.

Overview

The basic idea of instant messaging (IM) started in the early days of networked UNIX environments, where users who were logged on to the network could use UNIX commands such as Talk, Write, and Finger to determine who else was logged on and to send them short text messages. However, IM now generally refers to a set of technologies popularized by America Online (AOL), Microsoft Corporation, and other companies.

Types

The two most widely used IM services today are AOL Instant Messenger (AIM), developed by AOL, and ICQ ("I seek you"), developed by Mirabilis and now owned by AOL. Together, both services are used by more than 100 million people worldwide, and they support text-based messaging, voice, and file sharing/transfer. Other systems include Yahoo Messenger from Yahoo!, MSN Messenger from MSN (Microsoft Network), and Odigo from Odigo.

Implementation

Using AOL's AIM system as an example, AOL users can send instant messages to other AOL users online by using AIM client software. To use AIM messaging, an AOL user first signs on at an AIM central server, indicating that he or she is online and can receive instant messages from other users. The central server records the user's Internet Protocol (IP) address for that session. (The user's IP address is assigned by Dynamic Host Configuration Protocol [DHCP] and can vary from session to session.) Other users can then send instant messages to that user through the server. The user's AIM client sends the server a copy of the user's "buddy list" (a list of other users that he or she frequently exchanges messages with), and the server responds by telling the user which buddies are currently online and can receive messages. The user can select a buddy from the list and submit a message to the server, which forwards the message to the buddy.

Advantages and Disadvantages

IM exploded in popularity as a consumer-oriented service that allowed people to keep in touch with each other while surfing the Internet. The advantages of IM are similar to those of the telephone: simplicity and immediacy. IM is even more immediate than e-mail and include a wider range of communication methods, including voice, text, and file sharing. Since it uses the Internet as its carrier service, IM is effectively free for people already subscribed to an Internet service provider (ISP).

From a corporate perspective, though, some analysts see some disadvantages of IM, whose constant requests for communications can interfere with work even more than the telephone. Furthermore, as IM moves toward multimedia services, such communications can quickly swallow up network bandwidth in the enterprise. Policies also need to be in place and enforced to ensure that IM solutions are not misused, especially if they are outsourced to public service providers such as AOL or MSN. Another big concern about IM by corporate customers is security, as sensitive business information may be sent over the Internet through IM. Some vendors, however, are working to address this issue by encrypting IM communications. Finally, the main problem with all current IM systems is lack of interoperability between systems from different vendors. While AIM is the most widely used system, it is a proprietary system that AOL has not opened up to competing systems. This lack of ubiquity has hindered IM from being as widely useful as the telephone system, and attempts to develop vendor-independent standards for IM have so far been unsuccessful (see Prospects, later in this article).


① Login
② xxx.xxx.xxx.xxx Server records IP address
③ Buddy list
④ Message sent to buddy
⑤ Server looks up buddy's IP address
⑥ Server forwards message to buddy
AIM user
AIM server
AIM buddy

Instant messaging. *The instant messaging system used by AOL.*

Marketplace

Many enterprises are looking to set up their own IM solutions in order to better control with whom users are able to communicate. Packaged IM solutions are available from numerous vendors, including the IM features of Microsoft Exchange Server 2000, Lotus SameTime messaging for their Lotus Notes Domino platform, and Novell's instantme 2 secure IM platform. Other vendors have developed IM systems targeted directly for enterprise and not consumer use, including Planet Exchange with their Web-based IM system, NetLert from SoftBase Systems, and Interactive Messaging from 2WAY Corporation.

Prospects

Although IM is widely deployed as a consumer service, it has become attractive to businesses in the last few years. Analysts estimate that by 2002 almost half of Fortune 1000 companies will have either deployed corporate IM solutions in their enterprise or will outsource IM to existing service providers such as Microsoft or AOL. The next big thing will likely be mobile IM that allows users to send instant messages to each other over cellular phones and Personal Digital Assistants (PDAs). The Short Message Service (SMS) widely deployed among Global System for Mobile Communications (GSM) cellular systems in Europe is a first step in this direction and has proved enormously popular—and a revenue booster as well for cellular providers, since users are usually billed by the number of SMS messages sent. Evolution to multimedia IM such as that now available on the Internet is hampered, however, by the slowness of migrations of existing second-generation (2G) cellular systems to 2.5G and third-generation (3G) wireless.

The lack of a universal open standard for IM has resulted in a balkanization of the IM landscape and has prevented it from becoming as universal as the telephone. In 2000 the Internet Engineering Task Force (IETF) attempted to develop such a standard, called Instant Messaging and Presence Protocol (IMPP), and narrowed it down to three candidates: Instant Messaging Extensible Protocol (IMXP), Simple Instant Messaging Protocol (SIMP), and Instant Messaging and Presence using SIP (IMPSIP). This effort failed to produce an agreement, but other efforts toward a universal IM system continue, including the activities of the IMUnified coalition, which includes Microsoft, Yahoo!, and Tribal Voice. The IMUnified specification provides functional interoperability between popular proprietary IM systems but requires users to first sign up for accounts on those systems. Another approach to the problem of IM interoperability is Aimster, the peer-to-peer file-sharing program that has been updated to support buddy lists from such multiple IM systems as those of AOL, MSN, and Yahoo! The real solution to this problem, though, and the one that will eventually transform IM into an essential business tool for the enterprise, must come from the development of vendor-neutral IM specifications from standards bodies such as the IETF.

See Also: *AOL Instant Messenger (AIM), ICQ, Short Message Service (SMS)*

Institute of Electrical and Electronics Engineers (IEEE)

A worldwide nonprofit association of technical professionals.

Overview

The Institute of Electrical and Electronics Engineers (IEEE) promotes the development of standards and acts as a catalyst for new technology in all aspects of the engineering industry, including computer networking, telecommunications, electric power, aerospace, and consumer electronics. The IEEE has more than 365,000 individual members in 150 countries and regions. Its activities include standards committees, technical publishing, and conferences.

A major contribution of the IEEE in the field of computer networking is Project 802, a collection of standards for local area network (LAN) architectures, protocols, and technologies. These standards continue to evolve under the auspices of various IEEE working groups and committees.

For More Information

Visit the IEEE at *www.ieee.org.*

See Also: *Project 802*

Integrated Access Device (IAD)

A wide area network (WAN) access device for consolidating voice and data, usually over Asynchronous Transfer Mode (ATM) circuits.

Overview

Integrated Access Devices (IADs) are a type of WAN access device used for connecting corporate networks and voice telephone systems into wide area networks. A typical IAD can consolidate voice traffic, both analog and ISDN (Integrated Services Digital Network, together with Ethernet local area network (LAN) traffic, for transmission over frame relay or T1 links onto carrier ATM backbone networks. These different types of traffic are aggregated by the IAD into a single traffic flow for transmission over a single WAN link (access circuit). The advantages of IADs are that by integrating multiple WAN functions into a single box, costs are reduced through the elimination of redundant equipment and the traditional truck roll for carrier installation. Also, precious rack space in telecommunications closets can be saved by replacing multiple devices with a single integrated device. IADs provide a simple, cost-effective alternative to other WAN access devices, such as enterprise switches and WAN edge switches. They do not represent new WAN technology but rather an integration of existing technology into a single, easily managed device.

Implementation

IADs combine voice and LAN data traffic into a single data stream through Time Division Multiplexing (TDM) or some other scheme. IADs usually reside at the customer premises and can easily be connected to Private Branch Exchanges (PBXs) and Ethernet backbone switches. IADs are often supplied preconfigured by telecommunications carriers such as Competitive Local Exchange Carriers (CLECs) and Regional Bell Operating Companies (RBOCs).

The simplest form of IAD is essentially just a traffic aggregator, combining several data streams into one for transmission over frame relay, T-carrier, or Digital Subscriber Line (DSL) carrier services. Enhanced IADs include such features as Dynamic Host Configuration Protocol (DHCP), network address translation (NAT), integrated firewall, voice mail, multiprotocol routing, and many other features. High-end IADs are mainly ATM-based and support voice packetization for dynamic bandwidth allocation.

Marketplace

IADs first appeared on the market in 1998 and were expensive and aimed mainly at high-end enterprise customers. Since then, prices have fallen so that units under $2,000 are now available for small and mid-sized businesses. Some popular vendors of IADs include Cabletron Systems with its SmartSwitch 15000, Mariposa with its ATX series of ATM IADs, and offerings from Accelerated Networks, Lucent Technologies, Memotec Communications, Sonoma Systems, and many others.

See Also: *Asynchronous Transfer Mode (ATM), Competitive Local Exchange Carrier (CLEC), Integrated Services Digital Network (ISDN), Regional Bell Operating Company (RBOC), wide area network (WAN)*

integrated communications provider (ICP)

A telecommunications service provider that offers one-stop shopping for voice and data telecommunications through a single integrated architecture.

Overview

The main difference between an integrated communications provider (ICP) and a traditional carrier such as a Regional Bell Operating Company (RBOC), Competitive Local Exchange Carrier (CLEC), or Incumbent Local Exchange Carrier (ILEC) is that the ICP generally installs a single, all-in-one integrated access device (IAD) at the customer premises that enables voice and data traffic to be serviced over a single line. This provides for easier management than using multiple lines with different technologies and devices. The IAD typically connects to the provider by using Asynchronous Transfer Mode (ATM) over a single T1 line or Digital Subscriber Line (DSL) circuit at the local loop. (About 80 percent of the customer cost for ICP services is for the ICP's rental of local loop access from an RBOC). At the provider end, ICPs often build their own integrated ATM backbone networks so that they can better control the services they offer.



Integrated communications provider (ICP). *How an ICP provisions telecommunication services using an integrated access device (IAD).*

Advantages and Disadvantages

Using an ICP can save companies a considerable amount of money compared to leasing the services separately from traditional carriers. However, although the cost of using an ICP might be less than that of using an RBOC or a CLEC, the ICP might not offer some services, such as toll-free long distance and DSL services. You should also be sure that you understand how the various services are billed before you sign a contract.

Some ICPs use time-division multiplexing (TDM) to allow a single T1 line to carry voice, data, and video over 24 DS0 (Digital Signal Zero) channels. In this scenario, you might be paying for bandwidth that you are not using because TDM dedicates slots of bandwidth to services whether or not data is being carried in these slots. You can generally get better value from ICPs that use ATM circuits between the subscriber and provider because ATM can use statistical multiplexing, which allocates bandwidth dynamically between voice and data. However, the disadvantage of the ATM approach is that if the line goes down, all voice and data transmission is interrupted, while with the TDM approach, customers might still have access to analog phone lines if such lines are used.

Marketplace

The landscape for ICPs is in a state of flux, but players include CTC Communications, e.spire Communications, GST Telecommunications, ICG Telecommunications, Intermedia Communications, and many others.

See Also: *Competitive Local Exchange Carrier (CLEC), Incumbent Local Exchange Carrier (ILEC), Integrated Access Device (IAD), Regional Bell Operating Company (RBOC)*

Integrated Services Digital Network (ISDN)

A digital communication service provided by telephone companies (telcos).

Overview

Integrated Services Digital Network (ISDN) is an end-to-end digital telephone and telecommunications service provided by telcos to subscribers who request it. ISDN is a dial-on-demand (dial-up) service that has fast call setup and low latency. It is a circuit-switched service that can be used in both point-to-point and multipoint connections.

ISDN can be used to carry high-quality voice, data, and video transmissions. To do this, ISDN employs the existing widely deployed copper local loop wiring of the Public Switched Telephone Network (PSTN).

ISDN was developed in the 1970s by Bell Laboratories and standardized in the 1980s by the Comité Consultatif International Télégraphique et Téléphonique (CCITT), a precursor to the ITU (International Telecommunication Union). ISDN was originally envisioned as a digital replacement for the analog Plain Old Telephone System (POTS) and is available around the world with slight differences in architecture and operation.

Types

ISDN is available in a number of different interfaces (flavors) with the two most common being

- **Basic Rate Interface (BRI):** This uses two 64-kilobit-per-second (Kbps) B channels and one 16-Kbps D channel and is thus often referred to as 2B+D (B and D channels are explained later in this article). BRI can support combined voice and data with a maximum data transfer rate of 128 Kbps.
- **Primary Rate Interface (PRI):** This combines 23 64-Kbps B channels with one 64-Kbps D channel and is often referred to as 23B+D. PRI supports maximum data transfer rates up to the DS1 rate of 1.536 megabits per second (Mbps). PRI is generally used to provide the underlying transport for T1 lines.

Within PRI, however, there are also several ways in which ISDN B channels can be bundled together. These bundlings are called H-series configurations and common examples include

- **H0:** Combines 6 B channels for 384 Kbps throughput, equivalent to a fractional T1 line (fT1).
- **H11:** Combines 24 B channels for 1.536 Mbps throughput, equivalent to a T1 line.
- **H12:** Combines 30 B channels for 1.92 Mbps throughput, equivalent to an E1 line (used in Europe).

Another form of ISDN is known as Multirate ISDN, which allows subscribers to specify the bandwidth they need on a per-call basis in increments of 64 Kbps.

Comparison

Since ISDN is a dial-on-demand service, it has similarities to dial-up connections using analog modems. Both analog modem and ISDN use the same copper local loop and PSTN to allow connections to be established with distant stations. Both also require a call to be made before a connection can be established. With analog modems, this may take 15 to 30 seconds, but with ISDN, it is typically only 1 or 2 seconds. But although analog modems operate in an asynchronous fashion, ISDN uses a synchronous connection. And although analog modems transmit their control information (used for call setup and tear-down) in-band, ISDN uses out-of-band signal management with a separate channel called the D channel.

Uses

Because of its dial-on-demand nature, ISDN charges are typically based on a fixed monthly service fee plus usage charges. ISDN is thus ideal for applications where a dedicated (always-on) leased line is unnecessary and would be too costly. ISDN used to be popular with enterprise networks in the 1980s for connecting remote branch offices to company headquarters using ISDN wide area network (WAN) links. These remote offices would transfer their accumulated transactions several times a day over the WAN link for batch processing on mainframes located at headquarters. With the decline of the mainframe computing environment and the rise of client/server computing, however, many enterprises migrated their slow dial-up ISDN links to fast always-on T1 lines. ISDN remained popular with enterprise networks, however, as backup lines in case their dedicated T1 lines go down.

Architecture

The ISDN standards from the ITU define several different series of ISDN protocols, for example:

- **E-series:** These protocols define the addressing and telephone numbering system used by ISDN.
- **I-series:** These protocols cover the basic concepts of ISDN, including definition of the Basic Rate Interface (BRI) and Primary Rate Interface (PRI) interfaces.

- **Q-series:** These protocols describe how ISDN calls are set up and torn down and how switching occurs in an ISDN system.

ISDN uses a layered protocol architecture similar to the Open Systems Interconnection (OSI) model. The physical layer signaling is specific to ISDN and is the same for both B and D channels. For data transmission, ISDN uses a framing (encapsulation) format called V.120, which is the international standard for synchronous ISDN data stream framing. ISDN frames are 48 bits long and are transmitted at 4,000 frames per second. Each ISDN frame contains two 8-bit slots for the B1 channel and two 8-bit slots for the B2 channel, which alternate with each other and with one 1-bit D channel slot after each B channel slot using Time Division Multiplexing (TDM). Each B channel thus provides a data transfer rate of 2 x 8 bits x 4000 hertz (Hz) = 64 Kbps, while the D channel has a bandwidth of 4 x 1 bits x 4000 Hz = 16 Kbps. The remainder of the frame is used for line balancing, echo detection, activation, and padding.

Above the physical layer lies the data-link layer, which employs Link Access Protocol – D channel (LAPD) for flow control and signaling management. LAPD is derived from and is similar to the earlier High-level Data Link Protocol (HDLC) and Link Access Protocol – B channel (LAPB) used by X.25.

Above the data-link layer is the network layer, which employs ISDN-specific I-series protocols for such functions as call setup, establishment, and teardown, and for establishing point-to-point or multipoint circuit-switched or packet-switched connections between call endpoints.

As mentioned previously, there are two different types of ISDN channels:

- **B (bearer) channels:** These are full-duplex bearer (that is, carrying or “bearing” data) channels used for carrying either voice or data at 64 Kbps. The data transmission can be either circuit-switched (telco) or packet-switched (such as X.25) services. Each B channel can function as a completely separate connection, but you can also use a protocol called BONDING to dynamically combine the two B channels of BRI by using inverse multiplexing to produce a single 128-Kbps data channel.
- **D (delta) channels:** These are full-duplex 16 Kbps control channels for setting up connections and for other signaling purposes. For example, ISDN voice communication uses D channels to implement special services such as call forwarding and call display. The D channel uses a completely separate telco communication network called the Signaling System 7 (SS7). This out-of-band telco network is used exclusively for system overhead signaling for ISDN and digital data service (DDS) services, and it makes possible the low latency of ISDN dial-up connections. For example, it takes only 1 to 2 seconds for an ISDN dial-up connection to be established, compared to 15 to 30 seconds for a typical analog modem. D channels can also be used to connect ISDN subscribers to an X.25 network in a flavor of ISDN called Always-On Dynamic ISDN (AO/DI).

Implementation

Provisioning ISDN at a customer premises basically involves two steps:

- Installing and configuring ISDN customer premises equipment (CPE) at the subscriber’s location. The installation procedure involves setting up and testing the ISDN equipment and configuring the service profile identifier (SPID), which effectively represents the “phone number” of the subscriber’s ISDN setup. CPE for ISDN is further discussed later in this article.
- Changing the subscriber’s connection type at the telco central office (CO) from POTS to ISDN. This basically means disconnecting wires from an analog POTS switch to a digital ISDN switch at the CO. In North America, these ISDN CO switches are typically either 4ESS or 5ESS switches produced by AT&T or DMS-100 switches from Northern Telecom (now Nortel). Other types of switches are used in different parts of the world.


Two ways to connect to ISDN customer premises equipment
① Using ISDN data terminal equipment and phones/faxes
CO
S/T interface
ISDN line
U interface
NTU
ISDN phone
ISDN fax
ISDN NIC in computer
② Using serial cable and POTS phones/faxes
CO
RS-232
ISDN line
RJ-11
U interface
ISDN terminal adapter
POTS phone
Computer

Integrated Services Digital Network (ISDN). *Some examples of how to implement ISDN.*

The method of connecting CPE to the termination point of an ISDN line at the customer premises depends on the type of equipment you want to connect and which part of the world in which you are located (we will focus here on North American ISDN). The simplest case is if you are connecting “native” ISDN equipment such as an ISDN phone, which is referred to as Terminal Equipment type 1 (TE1), to your ISDN line. A bit more complicated is connecting non-ISDN equipment (known as Terminal Equipment type 2, or TE2) such as computers or routers—here you need to use an intermediary device called a Terminal Adapter (TA). The terminal adapter is usually connected to the TE2 using a serial interface such as RS-232 or V.35. ISDN terminal adapters can be external boxes, cards you plug into a computer’s motherboard, or modules you drop into the chassis of a router or integrated access device (IAD). ISDN terminal adapters are sometimes called ISDN modems, but they are not really modems because ISDN is an end-to-end digital communication service and no analog-to-digital signal modulation occurs within an ISDN setup.

The function of Terminal Equipment such as TE1 and TE2 described above is to convert signals received from CPE into BRI or PRI framing format. But to transmit these frames over the ISDN line, they need to be translated into electric signals that can be physically carried over the line. This translation is accomplished by means of a Network Termination Unit (NTU), which again comes in two types: NT1 devices that provide basic ISDN connectivity and NT2 devices used mainly for digital Private Branch Exchange (PBX) connections.

How all these different types of equipment are connected is determined by what are called ISDN interfaces, specifically:

- **R interface:** Specifies how non-ISDN CPE (TE2), such as standard analog telephones, are connected to an ISDN terminal adapter (TA).
- **S interface:** Specifies how ISDN CPE (TE1), such as an ISDN phone, ISDN PBX, or ISDN TA, is connected to ISDN network termination equipment (NTU).
- **T interface:** Specifies how NT1 connects with NT2 (this sometimes combined together as NT1/NT2 equipment, supporting what is called the S/T interface).

- **U interface:** Specifies how NTU connects to the local loop wiring.

Advantages and Disadvantages

For WAN links, ISDN has a couple of advantages over leased lines and analog modems:

- It is cheaper than leased lines such as T1 lines.
- It has faster call setup than analog modem dial-up connections.

On the downside, ISDN subscribers must be located within 3.5 miles (5.5 kilometers) of a telco CO or from a remote ISDN terminal, which means that ISDN is not always available, especially in rural areas. Also, in today's client/server and Internet networking environments, ISDN may provide insufficient bandwidth and excessive network latency to support today's distributed processing environments. As a result, some industry analysts have begun chanting an "ISDN is dead" mantra, but see the following Prospects section.

Prospects

Although ISDN BRI services may be relegated by the advent of Digital Subscriber Line (DSL) to backup WAN links for offices relying on DSL or T1 as their primary data link, ISDN PRI services are actually thriving worldwide. This is because PRI is an ideal platform for Internet service providers (ISPs) to use for connecting their banks of dial-up analog modems to the PSTN, and with the phenomenal growth of the Internet in the last few years, ISPs are buying up PRI at unprecedented rates. Another popular use for PRI is in corporate environments where it is used to connect digital PBXs at the customer premises to the PSTN. This is a more expensive arrangement than using analog trunk lines for this purpose (compare $1,000 to $2,000 a month for PRI to $50 to $100 a month for trunk lines), but it provides advanced features supported by digital telephones and native data transport at high speeds. So ISDN is definitely not dead as far as the new millennium is concerned, although the BRI version may be fading in usefulness in the enterprise.

Notes

Plug your ISDN network termination unit (NTU) into an uninterruptible power supply (UPS) so that you can use the phone during a power failure and so that your WAN link does not go down. If you have a large company and expect a lot of local telephone calls within your organization, you can sometimes obtain a Centrex ISDN service in which local calls have no usage charges. Microsoft Windows operating systems also have built-in support for ISDN.

Tips for Troubleshooting ISDN

Problem	*Suggestions*
ISDN router or terminal adapter fails to dial	Check the cabling, the line signal, and the dialer map on the router.
Dial fails to go through on a BRI line	Be sure that you are using a straight-through RJ-45 cable. Check other cables, make sure the speed is set correctly to 56 or 64 Kbps as necessary, verify the phone number and service profile identifier (SPID) assigned by the service provider, and check the router hardware.
Dial fails to go through on a PRI line	Be sure that you are using a straight-through DB15 cable and that the speed is set correctly to 56 or 64 Kbps as necessary. Check the dialer map on the router, the phone number of the remote PRI, and the status lights and framing on the Channel Service Unit (CSU). Power-cycle the CSU.
Dial is successful but cannot ping the remote router	Check the Point-to-Point Protocol (PPP) configuration (if used). Check the routing table and add a static route if necessary. Check that the dialer map has the correct remote router specified, and have the telco check the remote router configuration.

See Also: *Always On/Dynamic ISDN (AO/DI), B channel, bonding, BRI-ISDN, D channel, ISDN fallback adapter, ISDN router, ISDN terminal adapter, modem, PRI-ISDN, Public Switched Telephone Network (PSTN), T-carrier, time-division multiplexing (TDM), wide area network (WAN)*

Integrated Windows Authentication

A superset of Microsoft Windows NT Challenge/Response (NTLM) authentication.

Overview

Windows NT Challenge/Response authentication (also called NT LAN Manager or NTLM authentication) was the default authentication protocol used by all versions of Microsoft Windows prior to Windows 2000. The Windows 2000 platform now uses the Kerberos V5 authentication by default, which is faster and more secure than NTLM and authenticates both the client and the server (NTLM authenticates only the client). In Windows 2000, NTLM is retained for backward compatibility with earlier versions of Windows.

Integrated Windows Authentication was introduced in Windows 2000 as an enhanced version of NTLM that is backward-compatible with earlier versions of NTLM. The only difference in the new version is that IIS 5, the version of Internet Information Services (IIS) in Windows 2000, sends both an NTLM header and a Negotiate header to requesting clients using Microsoft Internet Explorer 5 or higher. In earlier versions of Windows, Microsoft Internet Information Server (IIS), and Internet Explorer, NTLM headers are used only, and not Negotiate headers.

See Also: *authentication protocol, Internet Information Services (IIS), Kerberos, Windows NT Challenge/Response Authentication*

Intel-based platform

A computer platform whose processor is based on the Intel 386 architecture microprocessor.

See: *x86 platform*

intelligent hub

A hub that can be remotely managed using Simple Network Management Protocol (SNMP) or some other management protocol.

Overview

An intelligent hub contains an SNMP Management Information Base (MIB) that specifies which hub functions can be managed and which conditions can be monitored. Examples include

- Setting alerts on problem conditions such as excessive collisions
- Isolating and disconnecting problem computers
- Providing network statistics to remote management consoles

Intelligent hubs are usually managed using in-band signaling methods, but they usually offer out-of-band management functions as well, such as being managed by a remote Telnet connection. Modular hubs often have SNMP modules that can be installed in the hub chassis to provide remote manageability and monitoring.

See Also: *hub, in-band signaling, Management Information Base (MIB), out-of-band (OOB) signaling, out-of-band management (OBM), Simple Network Management Protocol (SNMP), Telnet*

Intelligent Input/Output (I2O)

A hardware architecture developed by a consortium led by Intel that improves the input/output (I/O) performance of systems by relieving the central processing unit (CPU) of interrupt-intensive I/O tasks.

Overview

Intelligent Input/Output (I2O) makes use of a separate I2O processor such as the Intel i960 series of processors. This enables the CPU to offload interrupts received from peripherals to the I2O processor for handling. This scheme can improve the performance of servers by as much as 30 percent.

I2O also provides a way of standardizing I/O device drivers across different operating systems and hardware platforms. I2O standardizes device drivers by dividing them into two components:

- **Hardware Device Module (HDM):** This component directly interfaces with the peripheral being managed.

- **Operating System Service Module (OSM):** This component interfaces with the operating system on the machine.

In addition, an intermediate layer between the HDM and OSM provides independence between them by providing standard communication mechanisms that allow any HDM for any peripheral to interoperate with any OSM for any operating system.

Notes

The Microsoft Windows 2000, Windows XP, and Windows .NET operating systems support I2O.

IntelliMirror

A set of management technologies native to Microsoft Windows 2000, Windows XP, and the Windows .NET Server family that simplifies the task of configuring and maintaining applications, settings, and data at the client and server level.

Overview

IntelliMirror provides a distributed replication service that lets clients and servers “intelligently mirror” and share information stored on local and distributed file systems. IntelliMirror mirrors the workstation environment on the network server so that the environment can be easily managed. IntelliMirror also offers full roaming support by allowing a user to log on to any client machine and access his or her software, settings, and data. IntelliMirror is designed to simplify network administration and eliminate the need for administrators to “visit” desktop clients to upgrade operating systems and applications.

IntelliMirror is a combination of several features of Windows 2000 and depends on various aspects of the operating system’s architecture, including Active Directory directory service, Group Policy, and various services. IntelliMirror’s Change and Configuration Management (CCM) features are provided in three ways:

- **User data management:** Data can follow users wherever they roam on the network and even be available when the user is offline.
- **User settings management:** Enables administrators to use Group Policy to restrict and customize a user’s desktop working environment, including which software applications the user is allowed to use.
- **Software installation and maintenance:** Allows software applications to be installed either by assigning them (the first time the user clicks on the application shortcut in the Start menu, the application is downloaded and installed on his machine) or publishing them in Active Directory (the user employs Add/Remove Programs in Control Panel to install the software).

IntelliMirror can also use Remote Installation Services (RIS) to enable authorized clients to download fully configured operating systems, applications, and data from remote servers, thus performing unattended installations on the clients.

IntelliMirror technologies significantly reduce the total cost of ownership (TCO) of PC-based networks.

See Also: *Active Directory, Group Policy*

Interactive

A built-in identity in Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Overview

The Interactive built-in identity includes any user who has successfully logged on to the console of the local machine. The operating system uses this identity to enable the user to access resources on the machine. The name *Interactive* stems from the idea that the user who belongs to this group is “interacting” with the local computer through the console.

As with all built-in identities, administrators cannot directly modify the membership or assigned rights of the Interactive identity.

See Also: *built-in identities*

interactive logon

Logging on to a network through a local machine.

Overview

Interactive logon is a process whereby a user gains access to a network by entering credentials in response to a dialog box displayed on the local machine. This is in contrast to a remote logon, which occurs when a user who is already logged on locally tries to make a network connection to a remote computer—for example, using the Net Use command at the command prompt. Interactive logons are supported by all versions of Microsoft Windows.

In a Windows 2000 or Windows .NET network, the information that the user must specify during an interactive logon depends on the network's security model, as described in the following table. After successfully logging on interactively, the user is granted an access token that is assigned to the initial process created for her.

Required Logon Information for Security Models

Security Model	*What the User Must Specify*
Workgroup	Username and password
Domain	Username and password
Domain with a trust relationship trusting other domains	Username, password, and domain

Notes

When trust relationships are configured between Windows 2000 or Windows .NET Server domains, the interactive logon dialog box for Windows 2000 and Windows XP clients allows the user to select a logon domain—that is, the domain in which the user's user account is located. In contrast, the earlier Windows 98 and Windows Millennium Edition (Me) logon domains are hard-coded using Client for Microsoft Networks and offer only one domain to choose from at logon time.

See Also: *logon*

inter-exchange carrier (IXC)

A telecommunications carrier that provides long-distance services.

Overview

IXCs own or share the various high-bandwidth, fiber-optic trunk lines that cross different geographic areas and provide high-speed switched digital services for voice, data, and video communication. About 90 percent of the U.S. long-distance communication market is controlled by the Big Three IXCs: AT&T, MCI/WorldCom, and Sprint Corporation. These companies provide services such as long-distance telephone services, frame relay, virtual private networking (VPN), T-1 and T-3 lines, ATM (Asynchronous Transfer Mode) backbone services, and even Internet access.



Inter-exchange carrier (IXC). *Traditional relationship between IXCs and Incumbent Local Exchange Carriers (ILECs). This landscape is evolving as a result of the Telecommunications Act of 1996.*

While IXCs dominate the long-distance market, the local telephone companies (telcos) provide subscribers in their particular geographical service areas, called Local Access and Transport Areas (LATAs), with the actual local loop wiring that makes all telephony-based services possible. In other words, the telcos are dependent upon the IXCs for long-distance services, but the IXCs need the telcos' local loop in order to provide their services to customers. Each telco offers services only in their own specific LATA, but IXCs provide services connecting different LATAs. Telcos themselves are properly known as Local Exchange Carriers (LECs) and come in two varieties:

- **ILECs (Incumbent Local Exchange Carriers):** These include the Regional Bell Operating Companies (RBOCs) and rural telcos.
- **CLECs (Competitive Local Exchange Carriers):** These include Digital Subscriber Line (DSL) providers, Metropolitan Ethernet providers, and other kinds of carriers.

IXCs provide their own services through one of two methods:

- Colocating their equipment and sharing point of presence (POP) facilities at telco central offices (COs)

- Building their own POP facilities

Either way, IXCs need to share access with the local loop wiring owned by ILECs. This is facilitated by the government overseeing ILECs as regulated monopolies in their service areas.

Prospects

The Telecommunications Act of 1996 has opened up the market so that LECs can compete in long-distance markets by leasing services from IXCs, and IXCs can compete in local markets by leasing local loop connections from LECs. Some companies have also gained access to each other's services by merging. Other emerging competitors for IXCs are cable television companies, who have customer premises installations in most U.S. residences and who are upgrading their networks for bidirectional communication.

See Also: *Competitive Local Exchange Carrier (CLEC), Incumbent Local Exchange Carrier (ILEC), Local Access and Transport Area (LATA), local exchange carrier (LEC), Regional Bell Operating Company (RBOC)*

interface

In networking and telecommunication, a mechanism for communicating between two devices.

Overview

An interface specifies the nature of the boundary between two devices and determines the procedures and protocols that make it possible for the devices to exchange data.



Interface. *An example of an interface between data terminal equipment (DTE) and data communications equipment (DCE) devices.*

The most common type of interface in networking and telecommunication is the serial interface. A serial interface is one that transfers data one bit at a time between two devices. Serial interfaces are commonly used for connecting data terminal equipment (DTE), such as computers or routers, to data communications equipment (DCE), such as modems or Channel Service Unit/Data Service Units (CSU/DSUs). The most common type of serial interface is the RS-232 interface found on the back of most computers and used to connect modems. The following table shows other common examples of serial interfaces.

Types of Serial Interfaces

Serial Interface	*Description*
RS-232	A common interface for communication over unbalanced lines. Uses DB-9 or DB-25 connectors.
RS-422/485	For communication over balanced lines. More suitable than RS-232 for environments with significant electromagnetic interference (EMI) or with DB-9 or DB-37 connectors.
V.35	A high-speed serial interface for data transmission at 48 Kbps. Combines balanced lines with unbalanced lines and is used in Integrated Services Digital Network (ISDN) and frame relay connections. Uses a 24-pin block connector.
X.21	A high-speed serial interface that uses the International Telecommunication Union (ITU) standard for connecting DCE and DTE for synchronous communication. Uses a DB-15 connector.

Another type of interface is the parallel interface, which transfers data several bits at a time, usually one or more bytes at a time. The most common parallel interface is the one used for connecting printers to computers, which uses a female DB-25 or 36-pin Centronics connector.

Note that the type of interface a device uses is related to the kind of connector or cable used to connect to the device, but not in a one-to-one fashion. For example, you could say that a device has an RS-232 serial interface, but it is incorrect to say that you use an RS-232 connector or an RS-232 cable to connect to that device. RS-232 specifies the interface, but several cabling options can support it, such as a cable terminated with a DB-9 or a DB-25 male connector.

Notes

The term *interface* is also used in routing terminology, in which it describes the connection between a router and an attached network. In routing terminology, an interface is a remote network that can be reached from the local network. A router interface is said to be active if it provides connectivity with the remove network or inactive if connectivity is not possible at the time.

The term *interface* is also used in Microsoft Component Object Model (COM) programming to represent pointers through which clients invoke methods of COM objects. From the perspective of a client application, a COM object appears as a set of interfaces.

See Also: *connector (device), routing, RS-232, serial transmission, V.35*

interface card

A card you plug into a computer's motherboard to provide connectivity between the main system bus and an external serial or parallel bus.

Overview

Computers usually come with installed serial/parallel interface cards for connecting modems, printers, and other devices to your system, but in certain situations you might want to purchase a separate interface card. These situations include

- When you have an older computer whose serial interface card cannot support the newer fast 56-kilobit-per-second (Kbps) V.90 modems or whose parallel interface card cannot support IEEE 1284 bidirectional print devices such as the newer Hewlett Packard LaserJet print devices
- When you need a different serial interface such as RS-422/485 to connect your machine to special networking or industrial measurement equipment

Many different kinds of interface cards are available, including the following:

- RS-232 high-speed serial input/output (I/O) cards with 16550 universal asynchronous receiver-transmitter (UART) chips for connecting to high-speed modems and Integrated Services Digital Network (ISDN) terminal adapters. These cards can be either Industry Standard Architecture (ISA) or Peripheral Component Interconnect (PCI) bus cards and can support transfer speeds of up to 460.8 Kbps—much higher than the 115.2-Kbps rate supported by standard RS-232 interfaces.
- Enhanced Capabilities Port (ECP)/Enhanced Parallel Port (EPP) high-speed parallel I/O cards that support up to 2.5-megabit-per-second (Mbps) transfer speeds.
- RS-422/485 interface cards for connecting to industrial sensor and measuring equipment. These cards can support up to 31 separate devices that can be located up to 4000 feet (1220 meters) from the computer. Data transfer speeds are up to 460.8 Kbps.

See Also: *interface, RS-232, serial transmission*

interface converter

Any device that converts one interface to another.

Overview

Interface converters are generally stand-alone, powered devices for midline use or rack-mounted devices for use in wiring closets. There are interface converters for serial and parallel interfaces, asynchronous and synchronous communication, half-duplex and full-duplex communication, single-node and host converters, copper and fiber-optic converters, AC-powered or interface-powered devices, and other devices. Examples of interface converters include the following:

- RS-232 to RS-422 serial interface converters for directly connecting the RS-232 serial interface of a computer to an RS-422 programmable logic controller for synchronous data transmission. If handshaking is required, you should use an RS-232 to RS-422/449 serial interface converter instead.



Interface converter. *Using an interface converter to convert between an RS-232 interface and a V.35 interface.*

- RS-232 to RS-422/485 serial interface converters that allow RS-422/485 data collection equipment or industrial measurement devices to be connected to a computer using its built-in RS-232 serial interface. Alternatively, you can install an interface card in the computer to allow it to connect directly with the RS-422/485 device.
- RS-232 to V.35 serial interface converters for connecting RS-232 devices to V.35 lines.
- V.35 to G.703 or X.21 serial interface connectors for use in Europe.
- Small Computer System Interface (SCSI) to parallel converter for connecting SCSI peripherals to an Enhanced Capabilities Port (ECP)/Enhanced Parallel Port (EPP) parallel port.

See Also: *interface, RS-232, Small Computer System Interface (SCSI), V.35*

interference

Also called electromagnetic interference (EMI), electrical noise induced in cabling by nearby electrical equipment, such as motors, air conditioners, fluorescent lights, and power lines.

See: *electromagnetic interference (EMI)*

Interim Interswitch Signaling Protocol (IISP)

An Asynchronous Transfer Mode (ATM) protocol that enables cells to be routed over a switched virtual circuit (SVC).

Overview

The Interim Interswitch Signaling Protocol (IISP) is essentially a form of static routing for ATM networks. Normally, ATM is a connection-oriented architecture in which a switched connection is first established between the transmitting and receiving node, after which cells are delivered across that connection. When IISP is used, the result is more like Internet Protocol (IP) internetworks, where packets can be routed to their destination addresses by various paths.

IISP was created in 1994 and is an extension to the ATM UNI (user-to-network interface) specification.

Architecture

To use IISP, the ATM carrier network must employ switched virtual circuits (SVCs). Unfortunately most ATM carriers currently support only permanent virtual circuits (PVCs), as they are cheaper and easier to implement, which means that IISP is not a widely available solution for enterprises needing to route data over ATM carrier backbone networks.

IISP routes cells based on their 20-octet network service access point (NSAP) address. IISP employs channels 32 to 255 of virtual path identifier (VPI) zero. These channels function as trunk lines for routed transport of cells over ATM networks.

Notes

An alternative to IISP for routing cells over ATM backbone networks is to use Private Network-to-Network Interface (PNNI) protocol. You can combine both IISP and PNNI with multiprotocol label switching (MPLS) for enhanced functionality and performance.

See Also: *Asynchronous Transfer Mode (ATM)*

Interior Border Gateway Protocol (IBGP)

The version of Border Gateway Protocol (BGP) used for exchanging routing information within the same autonomous system (AS).

Overview

There are two versions of BGP, the classless dynamic routing protocol used on the Internet. These versions are

- **Exterior Border Gateway Protocol (EBGP):** This exterior routing protocol is used for exchanging routing information dynamically between border routers connecting different ASs on the Internet or in a large private Transmission Control Protocol/Internet Protocol (TCP/IP) internetwork. When referring simply to BGP, the variant EBGP is always implied. In other words, EBGP is usually just called BGP.
- **Interior Border Gateway Protocol (IBGP):** This interior routing protocol is used for exchanging routing information between routers within an AS. IBGP is less "chatty" than EBGP and does not communicate route information as frequently. Unlike EBGP, all IBGP routers within a particular AS must be configured as peers.

See Also: *autonomous system (AS), Border Gateway Protocol (BGP), classless routing protocol, dynamic routing*

interior gateway protocol (IGP)

Any routing protocol used to distribute routing information within an autonomous system (AS).

Overview

Also known as interior routing protocols, interior gateway protocols (IGPs) specify how routers within an AS exchange routing information with other routers within the same AS. This is in contrast to exterior gateway protocols (EGPs), which facilitate the exchange of routing information between routers in different ASs.



Interior gateway protocol (IGP). *A network using IGP to route information within an autonomous system and exterior gateway protocol (EGP) to route information between autonomous systems.*

Examples of IGPs include

- **Routing Information Protocol (RIP):** This is a popular protocol for small to medium-sized internetworks and is based on the distance-vector routing algorithm.
- **Open Shortest Path First (OSPF) Protocol:** This is used mainly on medium-sized to large-sized internetworks and is based on the link-state routing algorithm.
- **Interior Gateway Routing Protocol (IGRP):** This is a proprietary distance-vector routing protocol developed by Cisco Systems.

See Also: *autonomous system (AS), dynamic routing protocol, exterior gateway protocol (EGP), Internet, routing protocol*

Interior Gateway Routing Protocol (IGRP)

An interior gateway protocol (IGP) developed by Cisco Systems.

Overview

Interior Gateway Routing Protocol (IGRP) is a proprietary classful interior routing protocol that was developed by Cisco for two reasons:

- Routing Information Protocol (RIP) was widely deployed but had several deficiencies, including a simplistic metric that did not mirror real-world network topologies and a limitation in maximum hop count to 15 hops.

- Open Shortest Path First (OSPF) was being developed by the Internet Engineering Task Force (IETF) as a successor to RIP and as a routing protocol for larger internetworks, but development of OSPF was slow and the market needed a replacement for RIP.

As a result, Cisco developed IGRP as a proprietary protocol for exchange of routing information within an autonomous system (AS). IGRP was tuned to provide optimal routes to ensure that communications within a network would be minimally disrupted should a router go down. IGMP is a stable protocol capable of supporting very large networks, supports up to 255 hops (100 by default), has fast convergence, provides rudimentary load balancing between parallel routes, and prevents routing loops from occurring.

Architecture

IGRP is based on the same distance-vector routing algorithm used by RIP. In this algorithm a router uses IGRP to exchange routing table updates with adjacent (neighboring) routers only. In contrast to the simple metric of RIP, which forwards packets over the route having the least number of hops, IGRP uses a complicated formula to determine the best route to select, basing the decision on link characteristics that mirror the network's real topology and traffic flow. These factors include

- The time it would take a packet to reach its destination when the network is quiet (no traffic)
- The amount of bandwidth currently being used by each route (varies with time)
- The bandwidth of the slowest hop over the route
- The reliability of the route

IGRP routing updates are issued every 90 seconds, compared to every 30 seconds for RIP. In addition, IGRP routing updates are issued in a compressed form that requires fewer packets per update than RIP.

In addition, IGRP makes use of the following features to provide efficient routing:

- **Hold-down:** Prevents a route that has previously gone bad from being reinstated as a valid route
- **Split horizon:** Prevents routing loops from occurring between two routers
- **Poison reverse update:** Reduces the chance of routing loops occurring between three or more routers

Notes

Enhanced IGRP (EIGRP) is another proprietary interior routing protocol developed by Cisco. Despite the similarity in their names, EIGRP is a very different protocol from IGRP.

See Also: *dynamic routing protocol, Enhanced Interior Gateway Routing Protocol (EIGRP), interior gateway protocol (IGP), interior routing protocol, Routing Information Protocol (RIP)*

interior routing protocol

Another name for an interior gateway protocol (IGP), any routing protocol used to distribute routing information within an autonomous system (AS).

See: *interior gateway protocol (IGP)*

intermediary device

Any networking device positioned between a remote access server (RAS) and a remote client.

Overview

Intermediary devices are third-party devices for performing security-related tasks such as authentication, encryption, and other functions. An intermediary device such as a security host is typically positioned between the RAS server and the modem pool. Remote clients connecting to the modem pool must be authenticated by the security host before they can establish a connection with the RAS server. The security host thus provides an extra layer of security for remote access to the network. The security host might prompt the user for credentials, or the user might be required to use a security card to gain access to the network. Once you have configured the RAS server to work with intermediary devices such as third-party security hosts, you must then configure the client to work with the device. You can typically do this by activating terminal mode on the client so that it can respond to the special prompts issued by the device.



Intermediary device. *A security host as an intermediary device between an RAS server and a client.*

Notes

Microsoft Windows 2000 and the Windows .NET Server family support intermediary devices for its Routing and Remote Access Services (RRAS).

See Also: *remote access*

Intermediate Language (IL)

An intermediate byte code used by the Windows .NET platform.

Overview

Microsoft Corporation's new .NET platform is a language-independent programming framework for developing secure, scalable Web services. Applications and services can be developed for the .NET platform using a variety of programming languages, including Visual Basic (VB), C++, and Microsoft's new C# language. When compiled on the .NET platform, these languages all produce an architecture-independent intermediate byte code called Intermediate Language (IL). Code written in different languages can be mixed easily since they share the same architecture and data types—all compiled code is in the form of .NET objects.

See Also: *.NET platform*

International Mobile Telecommunications-2000 (IMT-2000)

An International Telecommunication Union (ITU) initiative to create a global standard for third-generation (3G) mobile communication networks.

Overview

The International Mobile Telecommunications-2000 (IMT-2000) initiative has its roots in 3G wireless research undertaken by the ITU in 1986. The goal of the initiative is to establish global mobile communication standards that support voice messaging services integrated with existing Public Switched Telephone Network (PSTN) services, integrated multipoint paging and dispatch services, and high speed data transmission at rates of up to 2 megabits per second (Mbps) for both packet-switched and circuit-switched communications (see table).

Proposed Data Rates for IMT-2000 Communications Systems

Mobility	*Minimum Data Rate*
Fixed	2 Mbps
Pedestrian	384 kilobits per second (Kbps)
Vehicular	144 Kbps

Because of differences in how the spectrum is regulated in different countries and regions and because of the fundamental inoperability between the two major types of cellular communication technologies—Time Division Multiple Access (TDMA) and Code Division Multiple Access (CDMA)—the ITU realizes that the initiative probably will not be able to unify worldwide mobile communication into a single global standard. As a result, the original IMT-2000 initiative has evolved somewhat to support several proposed standards, including the following:

- **Universal Mobile Telecommunications System (UMTS):** A standard for 3G wireless networks proposed by the European Telecommunications Standards Institute (ETSI)
- **Universal Wireless Communications (UWC-136):** A standard for 3G wireless networks proposed by the Telecommunications Industry Association (TIA)

- **CDMA2000:** A proposed hardware upgrade to the existing Code Division Multiple Access (CDMA) cellular phone systems used in the United States and in some parts of Asia
- **W-CDMA:** A proposed upgrade to Global System for Mobile Communications (GSM) networks that provides an alternative air interface to CDMA2000 for upgraded CDMA systems in Europe and Japan

The upgrade for CDMA bearers will be simpler and will move them directly from the current IS-95a standard called cdmaOne (the brand name used by the vendor consortium called the CDMA Development Group for existing data transmission at 16 Kbps) to the proposed CDMA2000. The upgrade for TDMA bearers may take several different paths—for example, from TDMA to General Packet Radio Service (GPRS) to Enhanced Data Rates for Global Evolution (EDGE) to UMTS. Some industry watchers predict that GPRS and IMT-2000 will be widely adopted worldwide in the next five years, which will give Europe and Asia an edge in high-speed wireless data communication over the United States, where as many as five competing systems might be deployed widely.

Notes

Note that the *2000* in the term *International Mobile Telecommunications-2000* refers to the transmission speed (approximately 2000 Kbps), not the final deployment date (which is likely to be around 2005).

For More Information

Find out more about IMT-2000 at *www.itu.int/imt.*

See Also: *CDMA2000, Universal Mobile Telecommunications System (UMTS), Universal Wireless Communications (UWC-136)*

International Organization for Standardization (ISO)

A nongovernmental organization based in Geneva, Switzerland, that has representatives from about 130 countries and regions and is responsible for developing a variety of international standards in science and engineering.

Overview

The International Organization for Standardization (ISO), established in 1947, runs almost 3000 different working groups and committees covering a broad range of standards issues. The ISO's goals are to develop cooperation in scientific, technological, intellectual, and economic activities and to facilitate the international exchange of goods and services. The ISO includes member agencies in more than 30 countries and regions. These member agencies include the American National Standards Institute (ANSI) and the European Computer Manufacturers Association (ECMA).

ISO standards include the following:

- Open Systems Interconnection (OSI) reference model for networking
- ISO/IEC SQL-92 standard for the transact-SQL language
- ISO codes for photographic film speeds
- ISO 9000 framework for business-management and quality-assurance standards
- ISO 216 international standard paper sizes
- Standards for telephone and bank cards
- ISO international country codes and currency codes

Notes

If you work with enterprise directory services, you might need to contact the ISO someday. For instance, if you plan to modify the schema of Active Directory directory service for Microsoft Windows 2000 and create new classes or attributes, you must obtain a unique object identifier for your enterprise to ensure that your new classes and attributes do not conflict with those defined by other directory services. This is especially important in a heterogeneous networking environment with multiple interoperating directory services such as Active Directory, Novell Directory Services (NDS), an X.500-based directory service, or Simple Network Management Protocol (SNMP). You can contact the ISO to receive an object identifier for your organization and then subdivide your object identifier space as you desire and assign object identifiers to your new classes and attributes.

For More Information

Visit the ISO at *www.iso.ch.*

See Also: *Active Directory, Novell Directory Services (NDS), Simple Network Management Protocol (SNMP), X.500*

International Telecommunication Union (ITU)

An international organization headquartered in Geneva, Switzerland, that coordinates global telecommunications networks and services with governments and the private sector.

Overview

Known until 1993 as the International Telegraph and Telephone Consultative Committee, also known by its French name, Comité Consultatif International Télégraphique et Téléphonique (CCITT), the International Telecommunication Union (ITU) is responsible for a number of important international networking and communication standards, including the following X series and V series standards:

- V.35 serial interface standard
- V.90 56-Kbps modem standard
- X.25 packet-switching network standard
- X.400 message-handling system (MHS) standard
- X.435 standard for electronic data interchange (EDI) over X.400
- X.500 directory service recommendations
- X.509 digital certificate and authentication standard
- Standards for Standardized Generalized Markup Language (SGML), the precursor to Extensible Markup Language (XML)

The ITU also hosts important study groups, meetings, and conferences and is a leading publisher of information on telecommunications technology and standards. The section of the ITU that is concerned with developing international standards for telecommunications is called the ITU Telecommunications Standardization Sector, or ITU-T.

For More Information

Visit the ITU at *www.itu.int.*

See Also: *American National Standards Institute (ANSI), V.35, V.90, X.25, X.400, X.500*

Internet

The global public Transmission Control Protocol/Internet Protocol (TCP/IP) internetwork.

Overview

The Internet has evolved in a single decade from an academic network to the backbone of today's economy. The Internet is synonymous in most people's minds with the World Wide Web (WWW) and has displaced most other early Internet protocols apart from Simple Mail Transfer Protocol (SMTP) and File Transfer Protocol (FTP).

The Internet is not owned by any one government, organization, or company. Nevertheless, various administrative bodies oversee different aspects of the Internet's operation. These groups include the following:

- Internet Society (ISOC), which coordinates a number of other bodies and gives them advice and direction.
- Internet Architecture Board (IAB), which is responsible to the ISOC and oversees the Internet's architecture.
- Internet Engineering Task Force (IETF), which is responsible to the IAB and develops Internet protocols that define such applications as the TCP/IP protocol suite and the Domain Name System (DNS).
- Internet Assigned Numbers Authority (IANA), which is responsible for coordinating the registration of DNS names and assigning Internet Protocol (IP) addresses. Many of the functions of IANA have

been replaced recently by a new body called the Internet Corporation for Assigned Names and Numbers (ICANN).

History

The Internet originated with the ARPANET project of the U.S. Department of Defense in the early 1970s. The original purpose of ARPANET was to create a wide area network (WAN) that would allow researchers at various defense and civilian research agencies to communicate with each other and to collaborate on projects. ARPANET originally consisted of a few hundred IP hosts joined together at several locations across the country.

When ARPANET grew larger and an increasing number of civilian agencies such as universities and networking companies wanted access to it, administration of the network was given to the National Science Foundation (NSF). The NSF then linked five national supercomputing centers together across the country using TCP/IP running over dedicated 56-kilobits-per-second (Kbps) links. This was essentially the birth of the public Internet as we know it. As more and more universities and private individuals became connected to this network, the NSF realized it had to upgrade the network to handle the new traffic. So in 1987 the NSF awarded a contract to Merit network, which in conjunction with MCI and IBM linked together 13 sites totaling 170 local area networks (LANs) using 1.544 megabit-per-second (Mbps) T1 lines. A year later the NSF terminated the original 56-Kbps backbone.

A few years later, traffic on the network had increased to such an extent that a further upgrade was needed. This was performed by Advanced Network and Services (ANS), a spin-off of the earlier Merit/MCI/IBM coalition. In 1990 the backbone was upgraded to T3 lines (45 Mbps) connecting 16 sites representing 3500 LANs. At this point, several other companies tried to get into the act. Alternet (now UUNET) and PSI created the Commercial Internet Exchange (CIX), which began as an alternative network but which soon was connected into the NSF backbone. Then a company called MFS began to set up fiber-optic ring networks called Metropolitan Area Ethernets (MAEs). These MAEs were connected to the Internet backbone in metropolitan areas. These soon became obvious places for companies to connect their corporate networks to the Internet, and MAE soon stood for Metropolitan Area Exchange instead. The first such exchange was called MAE-East, which is still operational and is located in Washington, D.C. Other MAEs include MAE-West in San Jose, California, and MAE-LA in Los Angeles.

By 1993 the NSF had decided to stop funding and managing the Internet backbone and to turn this job over to private operators. To facilitate this, the NSF established several network access points (NAPs) where backbone networks of these private operators could connect to the NSF's network. There are now several dozen NAPs in the United States (and many others around the world) and these include both the original MAEs and newer ones created by the NSF and by private companies. Finally, in 1995 NSF turned off its network and the Internet was reborn as a "core" of NAPs that are connected and owned by such companies as AT&T, Cable and Wireless, Genuity (formerly part of GTE Corporation), PSINet, Sprint Corporation, Qwest Communications International, and UUNET. Today, these NAPs are connected by fast OC-12, OC-48, and OC-192 connections, and traffic at the Internet's core is estimated by analysts as costing about $800 per megabit per second per month.

Architecture

From a network architecture point of view, the Internet's architecture is amazingly simple: the Internet can be viewed as a collection of thousands of large privately managed networks called Autonomous Systems (ASs). Each AS has a number (Autonomous System Number, or ASN) to identify it to other ASs. Different ASs are joined in a loose mesh configuration using powerful border routers that exchange routing information with each other using Border Gateway Protocol (BGP). IP packets traverse the Internet by being forwarded by these border routers and by routers within the ASs themselves. A typical request for a Web page from somewhere else in the world might result in your request making 15 or more hops across routers on the Internet.

For More Information

You can find interesting and useful information about the Internet at the following sites: *www.netsizer.com*, *www.isc.org*, and *www.cyberatlas.internet.com*.

See Also: *autonomous system (AS), autonomous system number (ASN), Border Gateway Protocol (BGP), Internet2, Internet access, Internet Architecture Board (IAB), Internet Assigned Numbers Authority (IANA), Internet Corporation for Assigned Names and Numbers (ICANN), Internet Engineering Task Force (IETF), Internet service provider (ISP), Internet Society (ISOC)*

Internet2

A project of the University Corporation for Advanced Internet Development (UCAID) to develop a high-speed network for research and collaboration and for developing innovative applications for education.

Overview

The Internet2 project is supported by more than 150 universities in the United States and is designed to create a leading-edge network for developing and testing new Internet applications for researchers. Its members consist of a collection of national, regional, and campus organizations whose networks are linked by new technologies and common research goals. Internet2 is not a successor to the present Internet, but rather new technologies to be used as part of the Internet. Internet2 is being developed by a consortium of institutions working to improve on existing Internet technologies. The knowledge and new technologies developed using Internet2 will be made available to the broader Internet community as they emerge.

Some of the potential benefits of new Internet technologies include advances in areas such as telemedicine, digital libraries, and virtual laboratories. Internet2 will also provide researchers with a test bed for developing new networking technologies, such as the following:

- Broadband networking
- Quality of service (QoS) networking technologies
- IPv6, the new 128-bit version of the Internet protocol
- Multicasting technologies

Notes

Other groups are working toward similar goals in cooperation with Internet2. Examples include the federally led Next Generation Internet (NGI) initiative, the National Science Foundation's High Performance Connections program, and the MCI/WorldCom vBNS network service.

Europe's version of the Internet2 is called GEANT and is intended as a backbone network joining 30 countries and regions together using 2.5-gigabit-per-second (Gbps) links for the purposes of academic research and industry collaboration.

For More Information

Visit the Internet2 site at *www.internet2.edu.*

Internet access

The process of connecting subscribers to Internet service providers (ISPs).

Overview

In the early 1990s, the ways in which businesses and consumers could connect to the Internet were limited, slow, and costly. These technologies included dial-up modems, Integrated Services Digital Network (ISDN) connections, and expensive leased lines such as T1 lines. By the end of the decade, the landscape had changed, however, and broadband Internet access technologies had become widespread, at least in dense urban areas. These new methods for providing Internet access to subscribers include:

- **Asymmetric Digital Subscriber Line (ADSL):** Provides downstream speeds up to about 10 megabits per second (Mbps)—upstream speeds are less—

over dedicated connections at about $50 a month. The main disadvantage is that it is available only within a few miles from the telco central office (CO).

- **Cable modem:** Provides symmetric speeds of up to 10 Mbps in theory, but because the system is a shared network, typical speeds are more like 1 Mbps. Cable modem access is widely available in residential areas but difficult to obtain in business and industrial parks.
- **Fixed wireless:** Provides downstream speeds typically of only a few hundred kilobits per second and has limited availability but can be deployed in locations too distant for ADSL or cable modems to function.

See Also: *Asymmetric Digital Subscriber Line (ADSL), cable modem, Integrated Services Digital Network (ISDN), T-carrier, wireless networking*

Internet Architecture Board (IAB)

A technical advisory group for the Internet Society (ISOC).

Overview

The Internet Architecture Board (IAB) was established in 1983 for the purpose of providing oversight for the development of Internet protocols and standards. It consists of 13 volunteer members, 6 of whom are nominated by the Internet Engineering Task Force (IETF) and approved by the ISOC. IAB members are part-time volunteers who provide the IETF community with advice and support. The IAB's functions include the following:

- Overseeing the evolution of the Internet's architecture and protocols from a long-term, strategic level. The most important of these issues is to ensure the continued scaling of the Internet's core services and protocols.
- Overseeing the process for developing Internet standards and for managing and publishing the Request for Comments (RFC) series of standards documents.
- Providing guidance to the ISOC on technical and procedural matters relating to the Internet.
- Selecting and appointing the chair of the IETF and candidates for the Internet Engineering Steering Group (IESG), which is responsible for the day-to-day operation of the IETF, and the Internet Assigned Numbers Authority (IANA), most of whose functions are now replaced by the Internet Corporation for Assigned Names and Numbers (ICANN).

For More Information

Visit the IAB at *www.iab.org.*

See Also: *Internet Assigned Numbers Authority (IANA), Internet Corporation for Assigned Names and Numbers (ICANN), Internet Engineering Task Force (IETF), Internet Society (ISOC)*

Internet Assigned Numbers Authority (IANA)

The organization that coordinates the assignment of unique Internet protocol parameters such as the Internet Protocol (IP) address space and the Domain Name System (DNS).

Overview

The Internet Assigned Numbers Authority (IANA) operates under the auspices of the Internet Society (ISOC) and is considered part of the Internet Architecture Board (IAB). IANA is the ultimate authority for managing the root name servers that maintain the central database of information for the DNS. IANA also controls the assignment of Transmission Control Protocol/Internet Protocol (TCP/IP) protocol identifiers such as IP addresses and the numbers for autonomous systems (ASs) on the Internet.

IANA delegates authority to other organizations and companies to grant users unique IP address blocks and register DNS domain names. IANA delegates these responsibilities to three regional bodies:

- The American Registry for Internet Numbers (ARIN), which manages North America, South America, and sub-Saharan Africa

- Réseaux IP Européens (RIPE), which manages Europe and North Africa
- The Asia Pacific Network Information Center (APNIC), which manages Asia and Australia

IANA is funded by the U.S. government. A new international nonprofit organization called the Internet Corporation for Assigned Names and Numbers (ICANN) has taken over the responsibilities of IANA because of the Internet's increasingly international and commercial nature.

Notes

Actual registration of IP addresses and DNS names is performed by network information centers, which in the United States include:

- Various accredited domain name registrars, which have replaced Internet Network Information Center (InterNIC) as the authorities for registering the .com, .org, .net, .gov, and .edu top-level domains
- The U.S. Domain Registration Service, which administers the .us top-level domain
- The U.S. Department of Defense Network Information Center, which manages the .mil top-level domain
- The .int top-level domain registry in Marina del Rey, California

For More Information

Visit IANA at *www.iana.org*.

See Also: *American Registry for Internet Numbers (ARIN), Asia Pacific Network Information Center (APNIC), Domain Name System (DNS), Internet Architecture Board (IAB), Internet Society (ISOC), RIPE*

Internet Cache Protocol (ICP)

A protocol that enables arrays of proxy servers to work together over a network.

Overview

The Internet Cache Protocol (ICP) was developed to allow individual proxy servers to query neighboring proxy servers to try to locate cached copies of requested objects. If these queries fail, the object is requested from the Internet. ICP has some inherent drawbacks:

- ICP arrays use queries to determine the location of cached information, a process that generates additional network traffic.
- ICP arrays have negative scalability—the more proxy servers in the array, the more query traffic is generated.
- ICP arrays tend to become highly redundant, with each cache containing similar information (the URLs of the most frequently visited sites).

Microsoft Corporation's solution to these problems is the Caching Array Routing Protocol (CARP), which it developed for its Microsoft Proxy Server version 2.

See Also: *Caching Array Routing Protocol (CARP), proxy server*

Internet Connection Firewall (ICF)

A new firewall feature of Windows XP and the Windows .NET Server family.

Overview

Internet Connection Firewall (ICF) is a software-based firewall application that is used to set restrictions on what type of network traffic or information is allowed to communicate between your home or small office network and the Internet. ICF is similar to a "stateful" firewall in that it monitors all aspects of the communications that cross its path and inspects the source and destination address of each message that it handles. Communications that originate from a source outside the ICF computer are dropped by the firewall unless an entry for the type of traffic being received is designated to allow passage. No notifications are created; ICF simply discards unsolicited communications, which prevents common hacking attempts such as port scanning. A security log can be created to allow viewing of the activity that ICF tracks.

See Also: *firewall, network security*

Internet Control Message Protocol (ICMP)

A Transmission Control Protocol/Internet Protocol (TCP/IP) network layer protocol used for various purposes.

Overview

The Internet Control Message Protocol (ICMP) is a simple TCP/IP protocol that operates at the network layer, the same layer at which Internet Protocol (IP) functions. Unlike IP, whose main function is to enable datagrams to be sent and received, ICMP has more restricted functions, including

- Testing of TCP/IP connectivity with remote hosts to make sure they are alive (using ping)
- Issuing simple control requests to routers and other hosts
- Reporting error conditions from routers and other hosts

In effect, ICMP complements IP by providing control messages and reporting errors on behalf of IP. ICMP is defined in RFCs 792 and 1700.

Architecture

ICMP messages are encapsulated in IP datagrams for transmission over a network. ICMP packets are thus connectionless and do not provide for guaranteed message delivery. ICMP supports broadcast traffic, but unlike both Transmission Control Protocol (TCP) and User Datagram Protocol (UDP), which operate at the higher Internet layer, ICMP does not use port numbers.

The function of an ICMP message is determined by the first 2 bytes of its message header. Some of the more common types of ICMP packets are

- **Echo Reply (ICMP type 0):** The Ping command uses this packet type to test TCP/IP connectivity.
- **Destination Unreachable (ICMP type 3):** Indicates that the destination network, host, or port cannot be reached.
- **Source Quench (ICMP type 4):** Routers send this packet type when they cannot process IP traffic as fast as it is sent. A Source Quench message essentially means “Slow down!” A Microsoft Windows NT or Windows 2000 host can respond to a Source Quench message by slowing down its rate of data transmission.
- **Redirect Message (ICMP type 5):** Used to redirect the host to a different network path. This message essentially tells the router to override the entry in its internal routing table for this packet.
- **Echo Request (ICMP type 8):** The Ping command uses this packet type to test TCP/IP connectivity.
- **Router Advertisement (ICMP type 9):** Sent at random intervals in response to an ICMP Router Solicitation request.
- **Router Solicitation (ICMP type 10):** Sent by routers to request router advertisement updates.
- **Time Exceeded (ICMP type 11):** Indicates that the Time to Live (TTL) has been exceeded because of too many hops. The Tracert command uses this message to test a series of routers between the local and remote hosts.
- **Parameter Problem (ICMP type 12):** Indicates an error processing the header of an IP packet.

Issues

Because of its broadcast nature, ICMP has been open to exploitation as a means of network attack. Many types of denial of service (DoS) attacks are based upon ICMP, including the Smurf attack, Tribe Flood Network (TFN) attack, Loki, and WinFreeze. For example, ICMP redirects can modify a router’s routing table, so sometimes hackers try to subvert routers by issuing forged ICMP redirects in order to perform a DoS attack. ICMP redirects are usually sent by routers only if all the following conditions occur:

- The router is configured to generate ICMP redirects.
- The incoming router interface for the packet is the same as the outgoing router interface.

- The subnet of the source IP address is identical to the next-hop IP address.
- The IP datagram is not source routed.

See Also: *denial of service (DoS), hacking, Internet Protocol (IP), Transmission Control Protocol (TCP), Transmission Control Protocol/Internet Protocol (TCP/IP), User Datagram Protocol (UDP)*

Internet Corporation for Assigned Names and Numbers (ICANN)

A nonprofit corporation that has taken over some of the functions of IANA (Internet Assigned Numbers Authority).

Overview

The Internet Corporation for Assigned Names and Numbers (ICANN) is responsible for

- Allocating portions of the Internet Protocol (IP) address space
- Managing the Domain Name System (DNS), including developing new top-level domains and managing root name servers
- Assigning Internet Protocol (IP) parameters

Until recently, a U.S. company, Network Solutions, exclusively managed the registration of domain names and maintained the DNS database. With the emergence of ICANN, however, these processes have been opened up to allow competition in the DNS registration arena through establishing guidelines for determining the following:

- Who can function as a domain name registry
- Policies on fees and privacy rights for domain name registries
- How disputes will be resolved between domain name registries
- What new top-level domain names will be allowed

Prospects

The transition from IANA to ICANN has not been entirely smooth. Some members of the international Internet community still see ICANN as largely dominated by U.S. government and corporate interests and would like to see a more radical redesign of the DNS to make it more international and to help reduce the tide of trademark litigation regarding domain names.

For More Information

Visit ICANN at *www.icann.org.*

See Also: *Domain Name System (DNS), Internet Assigned Numbers Authority (IANA)*

Internet Engineering Task Force (IETF)

An international community of networking engineers, network administrators, researchers, and vendors whose goal is to ensure the smooth operation and evolution of the Internet.

Overview

The Internet Engineering Task Force (IETF) receives its charter from the Internet Society (ISOC), and its daily operations are overseen by the Internet Architecture Board (IAB). The work of the IETF is performed by a number of working groups who are dedicated to such aspects of the Internet as routing, operations and management, transport, security, applications, and user services. These working groups interact primarily through mailing lists and are managed by area directors who belong to the Internet Engineering Steering Group (IESG). Some working groups develop extensions and newer versions of familiar protocols such as Hypertext Transfer Protocol (HTTP), Lightweight Directory Access Protocol (LDAP), Network News Transfer Protocol (NNTP), Point-to-Point Protocol (PPP), and Simple Network Management Protocol (SNMP). Others develop new protocols such as the Common Indexing Protocol, Internet Open Trading Protocol, and the Internet Printing Protocol.

The working groups produce documents called Internet Drafts, which have a life span of six months, after which they must be deleted, updated, or established as a Request for Comments (RFC) document.

For More Information

Visit the IETF at *www.ietf.org.*

See Also: *Internet Architecture Board (IAB), Internet Society (ISOC), Request for Comments (RFC)*

Internet Explorer

Microsoft Corporation's integrated suite of client-side Internet software, which is included with all current versions of Microsoft Windows.

Overview

Microsoft Internet Explorer has evolved from a simple Web browser to a full-featured suite of Internet tools. It provides access not only to information on Web sites on corporate intranets and the Internet but also to file system resources on the local machine and to shared folders on the network. When deployed using the Internet Explorer Administration Kit (IEAK), the following optional components can be installed or upgraded in addition to the basic Web browser:

- Microsoft Outlook Express
- Microsoft NetMeeting
- Microsoft FrontPage Express
- Microsoft Chat
- Web Publishing Wizard
- Connection Wizard

Features of Internet Explorer 5 and later include

- Support for the latest Internet standards and scripting languages, including Hypertext Markup Language (HTML) version 4; Microsoft Visual Basic, Scripting Edition (VBScript); JScript; ActiveX; Java; and Dynamic HTML
- Split-screen Search, History, Channel, and Favorites Explorer bars that can be toggled on and off
- Security zones for dividing intranets and the Internet into safe and unsafe regions with their own security settings
- Authenticode 2 code-signing technology that enables users to check the digital certificate of downloaded code before installing it on their system
- Offline browsing, which enables users to access Web content in their History or Subscribed Content folders when they are not connected to the Internet
- Scheduled, unattended dial-up for obtaining Web content from subscribed sites to view offline later
- Autocompletion of Uniform Resource Locators (URLs) typed into the address bar using Microsoft IntelliSense technology
- Dynamic HTML behaviors that allow Dynamic HTML functionality to be extended through hosted components
- Development enhancements that allow users to set the properties of items based on the value of an expression
- Enhancements to tables that allow users to create fixed-layout tables and collapsible borders
- Accessibility enhancements

For More Information

You can visit the Internet Explorer home page at *www.microsoft.com/windows/ie.*

See Also: *Internet Explorer Administration Kit (IEAK), Web browser*

Internet Explorer Administration Kit (IEAK)

A tool for customizing and deploying Microsoft Internet Explorer throughout an enterprise.

Overview

Some of the features of the Internet Explorer Administration Kit (IEAK) include

- IEAK Configuration Wizard, which is used to download, configure, and package Internet Explorer components for distribution to users in the enterprise.

- Automatic Version Synchronization (AVS) for notifying administrators when software updates for Internet Explorer 4 are available. Administrators can download these updates and distribute them to users.
- Profile Manager for centrally managing user desktop settings after deployment of Internet Explorer 4.
- Wizard-based configuration for determining which portions of Internet Explorer 4 will be deployed and how they will be configured.

The IEAK also supports deployment methods such as Microsoft Systems Management Server (SMS), e-mail, Web sites, floppy disks, and CDs.

Implementation

You first decide how you want to distribute your custom package for Internet Explorer: CD, floppy disks, or an Internet Uniform Resource Locator (URL) for users to download the package. You use the IEAK Configuration Wizard to build custom packages that include Internet Explorer, its related components, and up to 10 other custom components.

Once you create your package, you can distribute it using the appropriate method for the type of package: locate it on an Internet or file server or give users copies of CDs or floppy disks. Users can then run the Setup program to install Internet Explorer and the additional components on their systems. You can also use the IEAK Configuration Wizard to do the following:

- Create silent installation packages that do not allow users to change the configuration settings you have specified
- Create branded packages that customize users' browsers using a company-specific logo, title bar text, toolbar background bitmap image, or channel title bar for Internet Explorer
- Create packages with preconfigured browser settings such as a Start page, Search page, Support page, default favorites, Welcome page, desktop wallpaper, Active Channels, and proxy settings

See Also: *Internet Explorer*

Internet File System (iFS)

A technology developed by Oracle Corporation for sharing data over the Internet.

Overview

Oracle's Internet File System (iFS) leverages Extensible Markup Language (XML) to enable applications, services, and users to share data easily using standard Internet protocols. The iFS is included in the Oracle 9i database platform and provides a repository for all types of information including Web documents, e-mail messages, and other files. Using iFS, you can easily move data between Web applications and Oracle databases.

The iFS supports a number of standard Internet protocols, including

- Hypertext Transfer Protocol (HTTP)
- Web-based Distributed Authoring and Versioning (WebDAV)
- File Transfer Protocol (FTP)
- Simple Mail Transfer Protocol (SMTP)

The iFS also supports Server Message Block (SMB) protocol, the native file sharing protocol of the Microsoft Windows platform.

See Also: *File Transfer Protocol (FTP), Hypertext Transfer Protocol (HTTP), Simple Mail Transfer Protocol (SMTP), XML*

Internet Group Management Protocol (IGMP)

A Transmission Control Protocol/Internet Protocol (TCP/IP) network layer protocol used for informing routers of the availability of multicast groups on the network.

Overview

The Internet Group Management Protocol (IGMP) is used in a multicasting environment to exchange information on the status of membership in multicast groups between routers on the network. Once a router becomes aware that there are hosts on a locally attached network that are members of a particular multicast group, it advertises this information using IGMP to other routers on the internetwork so that multicast messages are forwarded to the appropriate routers. IGMP is thus used to maintain the group membership on a local subnet for an Internet Protocol (IP) multicast.

Architecture

There are two versions of IGMP: IGMPv1 and the newer IGMPv2. IGMPv1 is defined in RFC 1112 and supports only two types of IGMP messages:

- **Host membership report:** Hosts send this type of message to inform local routers that the host wishes to receive multicast IP traffic addressed to a specific group address.
- **Host membership query:** Routers send this message to poll a local area network (LAN) segment in order to determine if any hosts on the segment are listening for multicast traffic.

IGMPv2 is defined in RFC 2236 and includes several new message types, including

- **Leave group:** Used by a host to inform a router that it is the last member to leave a multicast group (so that the router knows it no longer needs to forward IP multicasts to that subnet).
- **Group-specific query:** Similar to the IGMP Host membership query, except that it checks for membership in a specific multicast group.
- **Multicast querier election:** This allows a single router to be selected for issuing IGMP Host membership query messages to a particular network segment.

IGMPv2 is fully backward-compatible with IGMPv1.

Implementation

Operation of IGMP is best illustrated with a simple example. To join a multicast group, a host must report its request for membership to nearby routers. These routers periodically poll the hosts in their locally attached networks to check on their membership status. When a host first joins a multicast group, it sends an IGMP Host Membership Report to the multicast address 244.0.0.1. The message contains the multicast address that identifies the group it wants to join. Routers connected to that host's local network then advertise to other routers throughout the internetwork that the particular network has hosts belonging to that multicast group. The routers poll the hosts regularly by sending IGMP Host Membership Query messages to determine whether any of them are still members of that group. If no hosts on the network belong to that group any longer, the router stops advertising the information to other routers on the internetwork so that multicast messages directed to that group are no longer forwarded to it.

Notes

IGMP is used by the Routing and Remote Access Service (RRAS) of Microsoft Windows 2000 for IP multicasting. IGMP is also used in Windows NT by the Windows Internet Naming Service (WINS)—at startup a WINS server sends IGMP packets to the multicast address 224.0.1.24 to seek out possible WINS replication partners on the network.

See Also: *Internet Protocol (IP), multicasting, Transmission Control Protocol/Internet Protocol (TCP/IP)*

Internet guest account

A user account in Microsoft Windows 2000, Windows XP, and the Windows .NET Server family used by Microsoft Internet Information Services (IIS).

Overview

The Internet guest account on Windows 2000 is usually an account named IUSR_ComputerName, where ComputerName is the name of the Windows 2000 server on which IIS is installed. The account is used to allow anonymous access to World Wide Web (WWW) and File Transfer Protocol (FTP) sites on IIS. The IUSR_ComputerName account is given a randomly assigned password and is made a member of the Guests local group. The account is also granted the sole system right "log on locally" so that when users on the Internet try to anonymously access a WWW or FTP site on IIS, they are authenticated as if they had logged on locally to the system console (instead of being authenticated as normal network users). This secures the computer against unauthorized network access. Once a user is authenticated as an anonymous user, he or she transparently uses the IUSR_ComputerName account to gain access to files on the WWW or FTP sites of interest.

The IUSR_ComputerName account is automatically included in the built-in Guests local group on the server on which IIS is installed, so be sure to review the permissions and rights that you have granted to the Guests group.

See Also: *Internet Information Services (IIS)*

Internet Information Services (IIS)

A Microsoft Windows service that provides support for application-layer Internet protocols.

Overview

Internet Information Services (IIS) enables Windows 2000 servers to function in the roles of Web servers, File Transfer Protocol (FTP) servers, Network News Transfer Protocol (NNTP) servers, and similar Internet and intranet servers. IIS is also a foundational component for a wide variety of other Microsoft server platforms, including Microsoft Exchange Server 2000, Microsoft Sharepoint Server, and other Microsoft .NET Enterprise Servers.

IIS was first released for Windows NT 3.51 as version 1. The highest version available for the Windows NT platform is version 4.01, which was included as part of the Windows NT Option Pack. On Windows 2000, the version of IIS is 5, but on Windows XP, it is 5.1 and on Windows .NET Server, it is 6.

All current versions of IIS support the following features:

- Fully integrated with Windows NT security and the version of NTFS file system (NTFS) used in Windows NT
- Full support for version 1.1 of Hypertext Transfer Protocol (HTTP)
- Support for File Transfer Protocol (FTP)
- Limited support for Simple Mail Transfer Protocol (SMTP)
- Support for Network News Transfer Protocol (NNTP)
- Support for advanced security using the Secure Sockets Layer (SSL) and related protocols
- Provides a platform for deploying scalable Web server applications using Active Server Pages (ASP); Internet Server API (ISAPI); Common Gateway Interface (CGI); Microsoft Visual Basic, Scripting Edition (VBScript); JScript; and other installable scripting languages, such as Perl
- Allows Web applications to be run as isolated processes in separate memory spaces to prevent one application crash from affecting other applications
- Integrates with Microsoft Transaction Server (MTS) and Microsoft Message Queue (MSMQ) Server for deploying transaction-based Web applications
- Can be managed using the Microsoft Management Console (MMC), through a standard Web browser such as Microsoft Internet Explorer, or by running administrative scripts using the Windows Scripting Host (WSH)
- Includes domain blocking for granting/denying access on the basis of IP address or domain
- Allows IIS activity to be logged in various formats, including IIS, World Wide Web Consortium (W3C), National Computer Security Association (NCSA), and open database connectivity (ODBC) logging
- Allows Web site operators to be assigned for limited administration of each Web site
- Bandwidth throttling to prevent one Web site from monopolizing a server's available bandwidth

Notes

The acronym *IIS* also stands for "Internet Information Server," the forerunner of this feature in the Windows NT platform.

See Also: *Active Server Pages (ASP), Common Gateway Interface (CGI), File Transfer Protocol (FTP), Hypertext Transfer Protocol (HTTP), Internet Server API (ISAPI), Network News Transfer Protocol (NNTP), Secure Sockets Layer (SSL), Simple Mail Transfer Protocol (SMTP), Web server*

Internet Inter-Orb Protocol (IIOP)

A Common Object Request Broker Architecture (CORBA) technology for distributed computing over the Internet.

Overview

CORBA is a technology for building object-oriented distributed applications. A CORBA application consists of objects that communicate with each other using orbs (object request brokers). The Internet Inter-Orb Protocol (IIOP) is an extension for CORBA that allows orbs to communicate with each other over the Internet.

IIOP uses Transmission Control Protocol (TCP) as its underlying network transport. IIOP supports bidirectional communications once a TCP session has been established. IIOP also supports callbacks to allow separate connections for client and server communications.

IIOP does not have a standard well-known TCP port number—instead, different orbs each have their own predefined port numbers. Some orbs also support dynamic allocation of port numbers, and some other orbs do not support IIOP at all.

IIOP does not include built-in authentication and encryption features. Instead, CORBA applications are responsible for secure communications using IIOP. An enhanced version of IIOP does exist, however, called IIOPS, standing for IIOP SSL and using the standard Secure Sockets Layer (SSL) protocol for secure communications over the Internet.

See Also: *Common Object Request Broker Architecture (CORBA), Secure Sockets Layer (SSL)*

Internet Key Exchange (IKE)

A protocol for managing keys in public key cryptography systems.

Overview

Internet Key Exchange (IKE) is used by the Internet Protocol Security (IPsec) protocol for generating and exchanging keys to enable secure IP network communications. IKE defines the procedures involved in the exchange of credentials necessary for establishing secure communications sessions. When IKE is used with IPsec, network authentication can employ either digital certificates or preshared keys. Preshared keys are used where the number of users is small, and digital certificates can scale effectively to the enterprise level. When digital certificates are used, however, IPsec must be rolled out in conjunction with a full public key infrastructure (PKI) to support the generation and management of such certificates.

The Internet Engineering Task Force (IETF) has recently developed several extensions to IKE to simplify how IPsec authentication is performed:

- **Hybrid Auth:** This uses tunneling to send client credentials to a central security server, which responds by returning a digital certificate to the client.
- **Xauth:** This is similar to Hybrid Auth, but the digital certificate resides on the client instead of the server.

See Also: *Internet Protocol Security (IPsec), public key infrastructure (PKI),*

Internet Locator Service (ILS)

A Lightweight Directory Access Protocol (LDAP) directory service that enables Microsoft NetMeeting users to locate and contact other users for conferencing and collaboration over the Internet.

Overview

Microsoft Commercial Internet System (MCIS) has an Internet Locator Service (ILS) that functions as a memory-resident database for storing dynamic directory information about NetMeeting users. This information, which includes a user's name, company, and Internet Protocol (IP) address, is stored in an Active Directory Global Catalog and can be accessed by any LDAP client, such as

NetMeeting. Clients periodically refresh the information in the ILS database. Users can access the ILS using LDAP to place a call to other NetMeeting users and to determine which NetMeeting users are currently logged on to the ILS. Using Active Server Pages (ASP), you can design a customizable Web interface that displays who is currently online and allows users to search for other users and initiate NetMeeting sessions with them.

Notes

ILS replaces the earlier User Locator Service (ULS) technology.

See Also: *Lightweight Directory Access Protocol (LDAP)*

Internet Mail Access Protocol version 4 (IMAP4)

A standard protocol for storage and retrieval of e-mail messages.

Overview

Simple Mail Transport Protocol (SMTP) provides the underlying message transport mechanism for sending e-mail messages over the Internet, but it does not provide any facility for storing and retrieving those messages. In order to communicate, SMTP hosts must be continuously connected to one another, but for ordinary users this is not always the case.

Internet Mail Access Protocol version 4 (IMAP4) complements SMTP by providing a mechanism for holding received messages in receptacles called mailboxes. An IMAP4 server stores messages received by each user in a personal mailbox until the user can connect to the server to download and read them. To do this, the user requires an IMAP4-capable mail client such as Microsoft Outlook or Microsoft Outlook Express.

IMAP4 provides functions similar to an earlier protocol called Post Office Protocol version 3 (POP3), but it includes a number of features that were not supported by POP3. Specifically, IMAP4 allows users to

- Access multiple folders, including public folders
- Create hierarchies of folders for storing messages
- Leave messages on the server after reading them so that they can access the messages again from another location
- Search a mailbox for a specific message to download
- Flag messages as read
- Selectively download portions of messages or attachments only
- Review the headers of messages before downloading them

Implementation

To retrieve a message from an IMAP4 server, an IMAP4 client first establishes a Transmission Control Protocol (TCP) session using TCP port 143. The client then identifies itself to the server and issues a series of IMAP4 commands:

- **LIST:** Retrieves a list of folders in the client's mailbox
- **SELECT:** Selects a particular folder to access its messages
- **FETCH:** Retrieves individual messages
- **LOGOUT:** Ends the IMAP4 session

To troubleshoot problems with remote IMAP4 servers, use Telnet to connect to port 143. Then try issuing various IMAP4 commands such as the ones described in this entry and examine the results.

Advantages and Disadvantages

Because IMAP4 clients can allow read messages to remain on the IMAP4 server, IMAP4 is especially useful for mobile users who dial up and access their mail from multiple locations. The downside is that IMAP4 servers require more resources than POP3 servers because users tend to leave large numbers of messages on the server. IMAP4 also is not as widely supported by Internet service providers (ISPs) as POP3.

Notes

IMAP4 is supported by Microsoft Exchange Server.

See Also: *e-mail, Post Office Protocol version 3 (POP3), Simple Mail Transfer Protocol (SMTP)*

Internet Printing Protocol (IPP)

A method for printing over the Internet.

Overview

The Internet Printing Protocol (IPP) is a standard method for printing files over Internet Protocol (IP) networks and is defined in RFCs 2565 through 2569 and RFC 2639. Using IPP, a user can specify a Uniform Resource Locator (URL) to print to instead of a Universal Naming Convention (UNC) path for the target print device.

Microsoft Windows 2000 supports using IPP to print to Microsoft Windows 2000 print servers running Microsoft Internet Information Services (IIS). Internet printers are represented in Active Directory directory service as printer objects and can be accessed by HTTP/1.1-compatible browsers such as Internet Explorer 4 or higher. IPP print commands run on top of text-based HTTP messages, which itself runs on top of IP.

IPP is a standards-based vendor neutral solution that allows any compatible client to print to any IPP-enabled print server. IPP is also extensible to allow notifications for blocking and job status.

See Also: *printing terminology, Universal Naming Convention (UNC)*

Internet Protocol (IP)

The network layer protocol used by Transmission Control Protocol/Internet Protocol (TCP/IP) for addressing and routing packets of data between hosts.

Overview

The Internet Protocol (IP) is one of the key protocols within the TCP/IP protocol suite. IP packets carry the actual data being sent across the network from one point to another. IP is a connectionless protocol that provides best-effort delivery of data. IP does not guarantee delivery of data; instead, the responsibility for guaranteeing delivery and sending acknowledgments lies with the higher-level transport layer protocol called Transmission Control Protocol (TCP).

Architecture

The diagram shows an IP packet's structure. Some of the more important header fields in the IP packet structure include

- **Source IP address:** The IP address of the host transmitting the packet.
- **Destination IP address:** The IP address of the host to which the packet is being sent, a multicast group address, or the broadcast IP address 255.255.255.255.
- **Header checksum:** A mathematical computation used for verifying that the packet received is intact.
- **Time to Live (TTL):** The number of router hops that the packet can make before being discarded.
- **Fragment offset:** The position of the fragment if the original IP packet has been fragmented (for example, by a router). This information enables the original packet to be reconstructed.

IP Packet Structure	Bytes
Version	$\frac{1}{2}$
Header length	$\frac{1}{2}$
Type of service	1
Total length	2
Identifier	2
Flags	$\frac{3}{8}$
Fragment offset	$1\frac{5}{8}$
Time to Live (TTL)	1
Protocol	1
Header checksum	2
Source IP address	4
Destination IP address	4
Options and padding	4
Data	varies

Internet Protocol (IP). *The structure of an IP packet.*

Implementation

IP packets are usually moved across a routed TCP/IP internetwork in the following fashion:

- If IP determines that the destination IP address is a local address, it transmits the packet directly to the destination host.
- If IP determines that the destination IP address is a remote address, it examines the local routing table for a route to the destination host. If a route is found, it is used; if no route is found, IP forwards the packet to the default gateway. In either case, the packet destined for a remote address is usually sent to a router.
- At the router, the TTL is decreased by 1 or more (depending on network congestion), and the packet might be fragmented into smaller packets if necessary. The router then determines whether to forward the packet to one of the router's local network interfaces or to another router. This process repeats until the packet arrives at the destination host or has its TTL decremented to zero and is discarded by a router.

See Also: *host, internetwork, routing, Transmission Control Protocol (TCP), Transmission Control Protocol/Internet Protocol (TCP/IP)*

Internet protocols

Application-layer Transmission Control Protocol/Internet Protocol (TCP/IP) protocols commonly used on the Internet.

Overview

The following table shows some of the standard Internet protocols in use today. Some of these protocols, such as Gopher, have declined in popularity and are now considered legacy protocols. To access a protocol such as Hypertext Transfer Protocol (HTTP) with a Web browser such as Microsoft Internet Explorer, you would use a Uniform Resource Locator (URL) beginning with http://.

Standard Internet Protocols

Protocol	*Protocol Name*	*Description*
http	Hypertext Transfer Protocol	Used for Web pages that contain text, graphics, sound, and other digital information stored on a Web server on the World Wide Web
ftp	File Transfer Protocol	Transfers files between two computers over the Internet
gopher	Gopher protocol	Displays information stored on a network of Gopher servers
wais	WAIS protocol	Used for accessing a Wide Area Information Servers database
file	File protocol	Opens a file on a local hard disk or a network share
https	Hypertext Transfer Protocol Secure	Establishes an encrypted HTTP connection using the Secure Sockets Layer (SSL) protocol
mailto	MailTo protocol	Starts a Simple Mail Transfer Protocol (SMTP) e-mail program to send a message to the specified Internet e-mail address
news	News protocol	Opens a Network News Transfer Protocol (NNTP) newsreader and the specified Usenet newsgroup
nntp	Network News Transfer Protocol	Performs the same function as the News protocol
midi	Musical Instrument Digital Interface (MIDI) protocol	Plays MIDI sequencer files if the computer has a sound card
telnet	Telnet protocol	Starts a Telnet terminal emulation program
rlogin	Rlogin protocol	Starts an Rlogin terminal emulation program

(continued)

Standard Internet Protocols *continued*

Protocol	*Protocol Name*	*Description*
tn3270	TN3270 protocol	Starts a TN3270 terminal emulation program
pnm	RealAudio protocol	Plays RealAudio streaming audio from a RealAudio server
mms	Microsoft Media Server (MMS) protocol	Plays .asf streams from a Microsoft Streaming Media server

Internet Protocol Security (IPsec)

A protocol for secure transmission over Transmission Control Protocol/Internet Protocol (TCP/IP).

Overview

Internet Protocol Security (IPsec) defines an end-to-end model for data encryption and integrity implemented at the Internet Protocol (IP) level. “End-to-end” means only that the hosts at the two endpoints of an IPsec session need to be IPsec-enabled; intermediate hosts only need to support TCP/IP communications. IPsec can be used to encrypt transmission of data and ensure that the data originated from the sender and was not modified in transit.

IPsec is frequently used to send information securely over the public Internet through a virtual private network (VPN). IPsec is an Internet Engineering Task Force (IETF) standard and is implemented in Microsoft Windows 2000, Windows XP, and the Windows .NET Server family.

Architecture

IPsec is a Layer-3 TCP/IP protocol that is managed by security policies installed on each machine and by an encryption scheme negotiated between the sender and the receiver. Devices and software configured to support IPsec can use either public key encryption using keys supplied by certificate authorities (CAs) or preshared keys for private encryption.

IPsec implements encryption and data integrity through two additional security protocols, which can be used either separately or together. These protocols are

- **Authentication Header (AH) protocol:** Provides user authentication and protection from replay attacks and supports data authentication and integrity functions. AH enables the recipient to be sure of the sender’s identity and that the data has not been modified during transmission. AH does not provide any encryption of the data itself. AH information is embedded in the IP packet’s header and can be used alone or with the Encapsulating Security Payload (ESP) protocol. AH is defined in RFC 2402.
- **Encapsulating Security Payload (ESP) protocol:** Encapsulates and encrypts user data to provide full data confidentiality. ESP also includes optional authentication and protections from replay attacks and can be used either by itself or with AH. ESP information is also embedded in the IP packet’s header. ESP is defined in RFC 2406.

To establish a security association (secure communication session) between two computers, a protocol framework called ISAKMP/Oakley can also be used. ISAKMP/Oakley includes a set of cryptographic algorithms and is extensible, supporting user-defined encryption algorithms. During the negotiation process, agreement is reached on the authentication and security methods to be used, and a shared key is generated for data encryption.

Implementation

IPsec security policies can be configured to meet the needs of securing users, sites, applications, or the enterprise in general. These security policies consist of a collection of filters with associated behaviors. When the IP address, port number, and protocol of an IP packet match a particular filter, the corresponding behavior is applied to the packet. In Windows 2000, for example, IPsec security policies are created and assigned at the domain level or for individual hosts using the IPsec Management snap-in for the Microsoft Management

Console (MMC). IPsec policies consist of rules that specify the security requirements for different forms of communication. These rules are used to initiate and control secure communication based on the nature of the IP traffic, the source of the traffic, and its destination. These rules specify authentication and negotiation methods, tunneling attributes, and connection types.

Advantages and Disadvantages

IPsec implements security differently from such tunneling protocols as Point-to-Point Tunneling Protocol (PPTP) and Layer 2 Tunneling Protocol (L2TP), which create secure tunnels and operate at the OSI data-link layer (Layer 2). Instead, IPsec secures information at the packet level and operates at the OSI network layer (Layer 3). IPsec also supports only IP traffic, which limits its use in some enterprise environments. PPTP and L2TP, by contrast, support any network protocol including TCP/IP, Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX), or NetBEUI.

Although the restriction to IP traffic is somewhat of a disadvantage, IPsec does have two significant advantages over tunneling protocols:

- Application-layer TCP/IP protocols such as Hypertext Transfer Protocol (HTTP) that reside above IPsec can take full advantage of the security offered by IPsec.
- Security policies for configuring IPsec make the protocol more powerful and flexible than tunneling protocols.

See Also: *data-link layer, Internet Protocol (IP), Layer 2 Tunneling Protocol (L2TP), network layer, Point-to-Point Tunneling Protocol (PPTP), Transmission Control Protocol/Internet Protocol (TCP/IP)*

Internet Relay Chat (IRC)

A text-based Internet conferencing protocol.

Overview

Internet Relay Chat (IRC) is a technology that can be used to send real-time, text-based messages over the Internet. IRC is a client/server technology in which users employ IRC client software to connect to an IRC server or hub. Clients can then connect to an existing chat group (also called chat room or channel) and type messages to other users currently in that group. Chat groups are identified using a pound sign (#) prefix. Messages are transmitted in real time and can appear character by character on the recipients' client software if the person sending the message types slowly enough. Depending on how the chat server is configured, users might be able to create their own chat rooms and hold private discussions. Some chat servers require that you register once to obtain a unique nickname, but others allow you to select a nickname for the current session only. Some Web sites also offer Web-based interfaces to their chat servers.

The network of IRC servers on the Internet is known as Undernet. These servers are generally owned and operated by Internet service providers (ISPs) that provide a free IRC environment to online users. The IRC protocol is defined in RFC 1459.

Prospects

In late 2000, the Undernet network was crippled by a lengthy Distributed Denial of Service (DDoS) attack that prevented IRC users from using the network and created havoc for ISPs hosting Undernet servers. The attack graphically illustrated the Internet's current vulnerability to DDoS attacks and has called into question the long-term viability of Undernet and IRC unless changes are made to the Internet's basic architecture to protect it from such attacks.

Notes

Microsoft Exchange Server includes an IRC-based chat service that you can use to set up public or private IRC sites.

For More Information

Find out more about IRC at *www.irc.net.*

See Also: *Distributed Denial of Service (DDoS), ICQ, instant messaging (IM)*

Internet Research Task Force (IRTF)

An umbrella organization for a number of long-term research groups that focus on standards for Internet protocols, architecture, applications, and technologies.

Overview

The Internet Research Task Force (IRTF) is overseen by the Internet Architecture Board (IAB) and includes research groups such as

- The End-to-End (E2E) group, which is concerned with end-to-end services and protocols implemented in hosts
- The Information Infrastructure Architecture group, which works to articulate a common information infrastructure for the Internet to support greater interoperability between applications
- The Internet Resource Directory group, which develops models for resource description on the Internet, including mechanisms for querying, indexing, and retrieval
- The Network Management group, which is concerned with issues relating to the management of the Internet from the perspectives of high-level management domains and customer-oriented services
- The Services Management group, which is concerned with the convergence of networking technologies relating to the Internet

For More Information

Visit the IRTF at *www.irtf.org.*

See Also: *Internet Architecture Board (IAB)*

Internet Security and Acceleration Server (ISA Server)

Microsoft Corporation's firewall, proxy, and Web-caching platform.

Overview

Microsoft Internet Security and Acceleration Server (ISA Server) 2000 replaces and extends its earlier Proxy Server 2 platform that was part of the BackOffice suite of server applications. ISA Server belongs to Microsoft's new .NET Enterprise Server platform and is designed to meet the security needs of Internet-based businesses. ISA Server provides

- A full-featured firewall set that includes stateful inspection, integrated intrusion detection, integrated virtual private network (VPN) support, and broad application support for circuit-level proxies.
- Web caching technology to speed the retrieval of frequently used Web content, saving valuable network bandwidth.
- Policy-based management for traffic management that can be scheduled and configured at the user, group, site, application, or content type level.

For More Information

Learn more about ISA Server at *www.microsoft.com/isa.*

See Also: *firewall, .NET Enterprise Servers, proxy server*

Internet Server API (ISAPI)

A set of standard application programming interfaces (APIs) for developing extensions to Microsoft Internet Information Services (IIS).

Overview

Internet Server API (ISAPI) provides Web developers with a powerful way to extend the functionality of IIS. ISAPI provides developers with low-level access to all Microsoft Win32 API functions, and ISAPI applications often have better performance than applications written using Active Server Pages (ASP) or Common Gateway Interface (CGI) . But as ISAPI dynamic-link libraries (DLLs) are generally written in a high-level programming language such as C or C++, ISAPI applications are usually more difficult to develop than ASP-based or CGI-based solutions and often do not scale as well.

There are two basic kinds of ISAPI DLLs, which have different uses on IIS:

- **ISAPI extensions:** Run-time DLLs that can run either in process or out of process on IIS. ISAPI extensions provide extended functionality to IIS.
- **ISAPI filters:** Used to preprocess packets of data before they enter or leave the IIS main process. An example of an ISAPI filter is the Secure Sockets Layer (SSL) protocol component on IIS 4.

Notes

You can create ISAPI extensions easily using the ISAPI Extension Wizard in Microsoft Visual C++.

See Also: *Active Server Pages (ASP), Common Gateway Interface (CGI), dynamic-link library (DLL), Internet Information Services (IIS), ISAPI extension, ISAPI filter*

Internet service provider (ISP)

A company that provides Internet access to consumers, businesses, or both.

Overview

Internet service providers (ISPs) come in various shapes and sizes, from volunteer-run freenets to local, regional, and national service providers such as AT&T WorldNet. ISPs can provide a wide range of services, including

- Dial-up Internet access
- Broadband Internet access—Digital Subscriber Line (DSL) or cable modem
- Leased lines and other wide area network (WAN) services.
- Web hosting services
- E-mail services
- Virtual private networking (VPN)

Types

ISPs can be classified into different types according to their size, service area, and particular business orientation. For example,

- **National:** These are often owned by or partnered with inter-exchange carriers (IXCs) to offer services across the country. Examples include AT&T WorldNet, EarthLink, Genuity, MSN, PSInet, Sprint, UUNET, and Verizon.
- **Regional:** These offer services in specific regions of the country and are often owned by or partnered with Regional Bell Operating Companies (RBOCs) or Incumbent Local Exchange Carriers (ILECs). Examples are Ameritech and BellSouth.
- **B2B:** These focus exclusively on the business-to-business market. Examples include GNS from AT&T and Gridnet from UUNET.

Implementation

Choosing an ISP for your enterprise or business is a process you should approach carefully. If your enterprise spans several locations, you need to consider your ISP as part of your network infrastructure, especially if you are using VPN. Be sure to ask potential ISPs questions about

- The capacity their backbone can handle and who owns it. OC-12 and OC-48 backbones are common, and OC-192 backbones are beginning to be deployed by large national carriers (the first ISP to deploy OC-192 was AT&T).
- Whether they employ redundant backbone connections to upstream providers and what sort of peering arrangements (public or private) they have with these providers. Most large ISPs use private peering arrangements to connect to similar ISPs, but small ISPs generally have to lease wholesale services from upstream ISPs.
- Whether they offer colocation for running your own Web servers at their point of presence (POP).
- Which advanced features (such as VPN and VoIP) they offer.
- What level of reliability or SLA (service level agreement) they offer.

Examples

One example of a national (Tier 1) ISP is UUNET (*www.uu.net*), which merged with MCI/WorldCom, an IXC. UUNET offers a wide range of services, including dial-up, Integrated Services Digital Network (ISDN), frame relay, Asynchronous Transfer Mode (ATM) access, leased lines, DSL, fast wireless Internet access, and more. UUNET's backbone stretches from North America to Europe and the Asia/Pacific region. Peering in the United States takes place at eight different network access points (NAPs), including MAE-East and MAE-West. All UUNET POPs have redundant links to their backbone.

Notes

If you are a consumer looking for an ISP in your area, try TheList (*www.thelist.com*).

See Also: *infrastructure, Internet, Internet access*

Internet Society (ISOC)

A professional society founded in 1992 that provides leadership for the development and evolution of the Internet.

Overview

The Internet Society (ISOC) comprises over 150 individual organizations, including government agencies and private companies, and is an umbrella organization for other Internet groups, including the Internet Engineering Task Force (IETF) and the Internet Architecture Board (IAB). The ISOC has more than 6,000 individual members in over 100 countries and regions. It is governed by a board of trustees elected from its membership. The ISOC hosts conferences and issues publications related to the development and management of the Internet. The ISOC has taken the lead in promoting the formation of a nonprofit constituency for the new Internet Corporation for Assigned Names and Numbers (ICANN), which oversees the Internet Domain Name System (DNS). The ISOC essentially functions as a legal umbrella for the standardization processes managed by the IETF and the IAB.

For More Information

Visit ISOC at *www.isoc.org.*

See Also: *Internet, Internet Architecture Board (IAB), Internet Corporation for Assigned Names and Numbers (ICANN), Internet Engineering Task Force (IETF)*

internetwork

A network, usually Transmission Control Protocol/Internet Protocol (TCP/IP), consisting of multiple networks joined by routers.

Overview

More generally, an internetwork is any network consisting of smaller networks joined in any fashion using bridges, switches, routers, and other devices. For example, an Internet Protocol (IP) internetwork could consist of a mix of Microsoft Windows NT or Windows 2000 and UNIX machines distributed over different subnets connected with standard IP routers from Cisco Systems or another vendor. An Internetwork Packet Exchange (IPX) internetwork could be a set of networks using Novell NetWare clients and servers running IPX that are connected using IPX-enabled routers.

Internetworking is the process of planning, implementing, and maintaining an internetwork. For IP internetworks, this involves such tasks as

- Determining which IP address classes and network IDs to use
- Dividing the internetwork into different subnets using a custom subnet mask
- Managing host IP address information using the Dynamic Host Configuration Protocol (DHCP)
- Configuring dynamic routers for efficient exchange of routing information
- Acquiring tools and skills for troubleshooting internetwork problems

Internetwork Operating System (IOS)

The operating system developed by Cisco Systems for its line of routers and access servers to provide a standard way to configure these devices.

Overview

Internetwork Operating System (IOS) is a text-based operating system that users access using a command-line interface (CLI) called EXEC. In this way IOS is similar to UNIX, but IOS commands are specific to router configuration and management functions instead of file system management and input/output (I/O). While IOS was originally designed as a monolithic, "router-centric" operating system, it has evolved into a modular operating system composed of different subsystems that can easily be upgraded and that support more complex distributed networking functions. The most recent release of Cisco IOS at the time of writing is IOS 12.2, which has support for IPv6 built into it across the board.

Note that the operating system used on Cisco Catalyst switches is somewhat different from the version used on routers and is referred to either as Catalyst IOS or Catalyst Operating System (COS) in various literature.

Implementation

IOS is typically stored as a system image within a router's flash memory. The startup configuration file called Startup-config is stored in nonvolatile RAM, and the router's actual operating configuration (its routing tables, queues, and other elements) is stored in ordinary RAM. Cisco routers can typically run in three different operating environments:

- **ROM monitor:** Also called the bootstrap program, this environment is accessed through the console port. The ROM monitor initiates the bootstrap process and can be used to run diagnostics, recover lost passwords, and recover from system failures.
- **Boot ROM:** This environment is used mainly to upgrade to new versions of IOS by loading a new image of IOS into flash memory.
- **Cisco IOS:** This is the normal operating environment, in which you can enter commands to configure and troubleshoot your router's operation. For example, you can enter the Show Version command to determine which version of IOS your router is running.

The normal IOS operating environment itself can run in four different modes:

- **User EXEC mode:** This mode is enabled by default when you connect to a router using a command-line console (for example, using a Telnet connection). Using EXEC, the IOS system command interpreter, you can type commands using a command-line interface. User EXEC mode supports a subset of IOS commands for performing basic actions such as configuring terminal settings, running tests, and displaying configuration information.
- **Privileged EXEC mode:** This mode lets you do everything you can do in User EXEC mode and more, including running the Setup command to enter configuration information, running the configure command to modify configuration information, and running the debug command to display event messages. Enter Privileged EXEC mode by typing the enable command.
- **Configuration mode:** This mode lets you configure your router's settings. You enter this mode by typing the configure terminal command.
- **Setup mode:** This mode is used to create new configuration files that enable features such as addressing, routing, and security.

Notes

You can quickly tell which command mode of IOS you are running by looking at your command prompt. The table shows the various IOS command modes and their prompts.

IOS Command Modes

Prompt	*IOS Mode*
Router>	User EXEC
Router#	Privileged EXEC
Router(config)#	Configuration
(A series of dialog box prompts)	Setup

You access most router functions by using EXEC mode, either User to view information in read-only format or Privileged to modify and configure router settings. User and Privileged modes also support different subsets of the IOS command set. Note that Privileged EXEC mode should always be password-protected because it lets you reconfigure key operating system parameters.

Do not run the debug command when you are connected to the network unless it is absolutely necessary because this increases the load on the processor. Type a question mark (?) at a prompt to determine which commands are available in the currently enabled IOS mode.

There are typically three ways you can connect to a router and issue IOS commands:

- **Console:** By connecting the serial port of a nearby PC to the router using a Cisco console cable, you can run IOS commands on the router using a terminal program such as Microsoft HyperTerminal on the PC.
- **Modem:** For routers in remote locations, you can use a modem to connect the router to the telephone system, allowing administrators to remotely dial-in and run IOS commands using a PC similarly equipped with a modem.
- **Telnet:** If the router has connectivity with a network, a user anywhere in the network can connect to the router and run IOS commands using Telnet.

For More Information

Find out more about Cisco IOS at *www.cisco.com/warp/public/732*.

See Also: *command line, router*

Internetwork Packet Exchange (IPX)

A NetWare protocol used for routing packets across an internetwork.

Overview

Internetwork Packet Exchange (IPX) is a network layer protocol that provides connectionless datagram services for Ethernet, Token Ring, and other common data-link layer protocols. IPX is the commonly used local area network (LAN) protocol on legacy NetWare 3.*x* and 4.*x* LANs but has now been replaced with native Transmission Control Protocol/Internet Protocol (TCP/IP) in NetWare 5.*x* and later.

Architecture

IPX packets use 32-bit (4-byte) network numbers to uniquely identify each data link (connected network) in an IPX internetwork. The administrator of each network assigns these network numbers, which must be unique for each connected network; all nodes on a connected network must have the same network number. Nodes discover their network number by communicating with routers attached to the local network. Routers use these network numbers to route IPX packets from one network to another within an internetwork. IPX is thus a routable protocol. The structure of an IPX packet is shown in the diagram.

IPX Packet Structure	Bytes
Checksum	2
Length	2
Transport control (hop count)	1
Packet type	1
Destination network	4
Destination node	6
Destination socket	2
Source network	4
Source node	6
Source socket	2
Data	varies

Internetwork Packet Exchange (IPX). *The structure of an IPX packet.*

IPX also uses 48-bit (6-byte) addresses for each node within a given network. An entire IPX network address is thus 4 + 6 = 10 bytes long. IPX packets are assigned a 16-bit (2-byte) socket number to identify the networking service they are communicating with—for example, Network Control Protocol (NCP), Service Advertising Protocol (SAP), or Routing Information Protocol (RIP). Thus, the following 12-byte triple completely identifies the networking service that a packet is communicating for:

```
{network number, node address, socket number}
```

When an IPX client is booted on a NetWare internetwork using IPX-enabled routers, the client broadcasts a

Get Nearest Server (GSN) request message to its locally connected network in order to locate the nearest NetWare server. If a NetWare server cannot be located on the connected network, the router informs the client of the nearest available server based on the cost of the connection. The router is familiar with this information because NetWare servers using IPX periodically notify the network of their presence using SAP, which allows IPX routers to construct server tables based on SAP numbers.

IPX is a connectionless protocol that works at the network layer of the Open Systems Interconnection (OSI) reference model, and IPX packets are connectionless datagrams. To function within connected networks, IPX works with a transport layer protocol called the Sequenced Packet Exchange (SPX) protocol. SPX is responsible for generating acknowledgments for IPX packets received over the network to ensure that no packets were lost during transport.

Notes

On Ethernet networks, NetWare clients and servers can communicate with each other using IPX only if they use compatible frame types (encapsulation formats). The terminology used to describe these frame types depends on whether you are discussing Novell NetWare clients and servers or IPX-enabled routers from Cisco Systems. The following table illustrates these differences.

Frame Type Terminology

Common Terminology	*Novell Terminology*	*Cisco Terminology*
Ethernet	Ethernet_II	arpa
raw	Ethernet_802.3	novell-ether
802.3	Ethernet_802.2	sap
snap	Ethernet_SNAP	snap

Ethernet_II is the default frame type for NetWare version 3.*x* and earlier, but NetWare 4.*x* uses the Ethernet_802.2 frame type.

See Also: *NetWare protocols*

interprocess communication (IPC)

A mechanism for establishing a connection between processes running on two computers or on a single multitasking computer to allow data to flow between those processes.

Overview

Interprocess communication (IPC) mechanisms are commonly used in client/server environments and are supported to various degrees by the different Microsoft Windows operating systems. An IPC generally consists of two components:

- An application programming interface (API) that defines the standard set of functions that can be called when software tries to use an IPC.
- A protocol that specifies the format in which the information is transmitted using the IPC. When IPCs are passed over the network, the format specified is the format of the packet or frame transmitted between the computers.

The following table lists some IPC mechanisms and the platforms that support them.

Built-in Support for IPC Mechanisms on Various Windows Platforms

Process	*Windows NT*	*Windows 95*	*Windows 98*	*Windows 2000*
Named pipes	x	x	x	x
Mailslots	x	x	x	x
NetBIOS	x	x	x	x
Windows Sockets	x	x	x	x
Remote procedure call (RPC)	x	x	x	x
Network Dynamic Data Exchange (NetDDE)	x	x	x	x
Distributed Component Object Model (DCOM)	x		x	x

Inter-Switch Link (ISL)

A Cisco technology that is used for frame tagging.

Overview

Inter-Switch Link (ISL) was developed by Cisco Systems to enable a single physical Ethernet interface to support multiple logical Virtual LAN (VLAN) interfaces. A device using ISL thus appears on the network as if it had multiple physical network interfaces present instead of one.

ISL works by tagging Ethernet frames with the logical VLAN address to which each frame belongs. This technique is more generally known as frame tagging. ISL is implemented in modules for Cisco Catalyst switches and also for special network interface cards (NICs) used in routers and high-performance servers.

Prospects

ISL is widely used in the enterprise but represents a proprietary Cisco solution. The Institute of Electrical and Electronics Engineers (IEEE) is developing a vendor-neutral standard for frame tagging called 802.1Q, but it may take time for this standard to replace ISL due to its large installed base.

See Also: *802.1Q, Ethernet, frame tagging, virtual LAN (VLAN)*

intranet

A private Transmission Control Protocol/Internet Protocol (TCP/IP) internetwork within an organization that uses Internet technologies such as Web servers and Web browsers for sharing information and collaborating.

Overview

Intranets can be used to publish company policies and newsletters, provide sales and marketing staff with product information, provide technical support and tutorials, and just about anything else you can think of that fits within the standard Web server/Web browser environment.

Microsoft Internet Information Services (IIS), with its support for Active Server Pages (ASP), is an ideal platform for building intranet applications that can be accessed using a standard Web browser such as Microsoft Internet Explorer.

See Also: *Internet, Internet Information Services (IIS), Web server*

intrusion detection system (IDS)

Any system used to detect attacks on a host or network.

Overview

Intrusion detection systems (IDSs) can detect, log, report, and even respond to a wide variety of attempts to compromise a network's security. IDSs range from simple tools such as network sniffers and application logs to complex, distributed systems costing thousands of dollars. They can be implemented as software installed on computers, blades inserted into enterprise Ethernet switches, or dedicated network appliances.

An IDS is an essential component of a network security policy and is complementary to a firewall—a firewall prevents certain kinds of intrusion, but an IDS detects what gets through the firewall. An IDS is not a "silver bullet" that solves all network security issues—a poorly implemented or unmonitored IDS is worse than no IDS at all because it provides a false sense of security. The reports generated by an IDS are typically 90 percent false positives and usually require human intelligence to distinguish the real attacks from the false ones.

There are two basic types of IDS:

- **Network IDS (NIDS):** These are systems that capture network traffic and analyze it looking for evidence of attacks. NIDS generally determines which traffic is hostile on the basis of predefined rules or signatures. These signatures must be kept up to date by downloading new versions from the vendor to ensure that NIDS continues to be effective in patrolling the network. NIDS are operating-system independent and can be implemented without modifying your network's infrastructure. On the downside, they increase network traffic, thus consuming valuable bandwidth, and are difficult to implement in a switched environment.



Intrusion detection system. *An example of how a network intrusion detection system might be implemented.*

- **Host-based IDS:** These are applications installed on critical hosts such as Web servers that monitor such things as Transmission Control Protocol (TCP) sessions, port activity, file integrity, and log files. Host-based IDSs are platform-specific solutions that must be installed on any servers considered in danger of attack.

This distinction between the two types of IDS is beginning to be blurred as vendors combine aspects of both types into newer IDS applications and appliances. Vendors are also beginning to add "intelligent" pattern-recognition functionality into their IDSs to enable them to detect attacks for which no signatures currently exist. The use of artificial intelligence (AI) in IDS systems is probably the big goal in the network security field for the next decade.

Implementation

This example deals with the implementation of a NIDS. A typical NIDS consists of two components:

- **Sensors:** These capture network traffic on various segments and forward it to the management station.
- **Management station:** This receives reports from sensors of possible intrusions and then logs the information in a database, generates reports for human inspection, notifies administrators of the occurrence, and (if configured to do so) shuns harmful traffic.

To detect intrusion at the perimeter of a network connected to the Internet, a sensor would typically be deployed in the perimeter network (otherwise known as a demilitarized zone [DMZ]) where the firewall is located.

Marketplace

The IDS market has exploded over the last few years, with the result that IDS has often become a buzzword that vendors use to market products that have little IDS functionality. Examples of host-based IDS include Intruder Alert from Axent Technologies, Dragon Squire from Enterasys Networks, Kane Security Enterprise from Intrusion.com, and RealSecure OS Sensor from Internet Security Systems. Popular network IDSs include NetProwler from Axent Technologies, Cisco Secure IDS from Cisco Systems (available as both a stand-alone appliance and as a module for Cisco Catalyst 6000 series switches), eTrust Intrusion Detection from Computer Associates, Armor from nCircle Network Security, BlackICE Sentry from Network Ice Corporation, and NFR from Network Flight Recorder. Some popular free UNIX-based IDS tools include Shadow, Snort, and Pakemon.

Issues

One of the main difficulties in deploying NIDS is that most enterprise networks are now switch-based instead of hub-based. All stations connected to a hub share the same broadcast and collision domain, and by connecting a NIDS sensor to a hub, traffic to and from every station can be easily monitored. Ethernet switches are different, however—each attached station forms its own private segment and to monitor traffic effectively would, in theory, require a NIDS sensor for each port.

One workaround for this problem is to use port mirroring (spanning) to copy portions of traffic from each port on the switch to a mirror port to which the sensor can then be attached. The problem with doing this, however, is that it adds an extra processing load to the switch and is difficult to implement in full-duplex configurations. Cisco solves this problem in its Catalyst 6000 series of enterprise switches by providing its Cisco Secure IDS product as a blade that can be installed in the switch to monitor traffic directly on the backplane. By configuring access control lists (ACLs), administrators can then pull up different kinds of traffic such as Hypertext Transfer Protocol (HTTP) to get more targeted information about possible intrusions. Another solution is provided by Shomiti Systems, which sells "taps" that let you unobtrusively listen in to traffic on any 10/100 Mbps Ethernet link and copy traffic to a second switch to which IDS sensors are attached. This way, no extra processing burden is placed on the network's backbone switches.

See Also: *firewall, network security*

inverse multiplexer (IMUX)

A device that can perform inverse multiplexing of digital telecommunication channels.

Overview

A typical inverse multiplexer (IMUX) might be capable of inverse multiplexing together four Basic Rate Interface ISDN (BRI-ISDN) lines, two T1 lines, or four T1 lines to provide a throughput of 512 kilobits per second (Kbps), 3.088 megabits per second (Mbps), or 6.176 Mbps, respectively. This saves the expense of having to purchase or lease equipment to individually terminate each Integrated Services Digital Network (ISDN) or T1 line, and it provides an efficient way to increase wide area network (WAN) speed for high-bandwidth uses such as videoconferencing, T1 backup, or large file transfers. IMUXes can include built-in Channel Service Unit/Data Service Unit (CSU/DSU) functionality, they have a 34-pin built-in V.35 LAN (data) interface, and they have an RJ-45 or DB25 connector for the line interface. They often feature load-sharing functions so that if one ISDN or T1 line goes down, no delays occur. IMUXes usually include diagnostic and loopback functions for both local and remote troubleshooting.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), Integrated Services Digital Network (ISDN), inverse multiplexing, T-carrier*

inverse multiplexing

A way of combining the bandwidths of a number of digital network or telecommunication lines into a single virtual pathway for high-speed communication.

Overview

Inverse multiplexing can be used to aggregate the bandwidth of digital data service (DDS), switched 56, Integrated Services Digital Network (ISDN), or T1 and higher T-carrier services into a single high-bandwidth data terminal equipment (DTE) interface. You can then connect this DTE interface to customer premises equipment such as routers or Channel Service Unit/Data Service Units (CSU/DSUs), which are connected to the customer's network.

Inverse multiplexing is the opposite of multiplexing, which combines data transmissions from multiple pieces of DTE into a single digital communication channel.

Implementation

By connecting a device called an inverse multiplexer, or IMUX, to the termination points of several leased digital lines, you can use inverse multiplexing to create a single virtual connection with a bandwidth equal to the sum of the bandwidths of the individual lines. To implement this, for example, with ISDN, an IMUX is required at both the customer premises and the telco central office (CO). When several ISDN subchannels are multiplexed into a single high-speed channel, a connection is initiated when the customer's IMUX dials a number to establish a connection with the CO IMUX. Once a single ISDN subchannel is established, the customer IMUX dials the remaining numbers and establishes the additional ISDN subchannels. Once all the subchannels are up, a protocol called BONDING establishes synchronization between the two stations using a handshaking mechanism to resolve any delays between the subchannels. These delays are primarily the result of the different circuit-switched communication subchannels having physical paths of different lengths, even though they have the same two endpoints. The bonding protocols also ensure that data sent over each subchannel arrives at its destination in the correct order.



Inverse multiplexing. *A simple example of using inverse multiplexing to provide a high-bandwidth wide area network (WAN) connection to a corporate network.*

Advantages and Disadvantages

The main advantage of inverse multiplexing is that it is often less expensive to lease several low-speed digital lines and inverse multiplex them together than to lease a single high-speed digital line with the same aggregate bandwidth. Inverse multiplexing is also useful in areas where high-speed digital services such as T1 are not readily available.

See Also: *multiplexing*

Inverse Multiplexing over ATM (IMA)

A high-speed Asynchronous Transfer Mode (ATM) technology.

Overview

Enterprises that need to connect their ATM backbones by means of wide area network (WAN) links to interexchange carriers (IXCs) such as AT&T, Sprint, and MCI/Worldcom have traditionally been limited to two main options:

- **T1 lines:** These operate at 1.544 megabits per second (Mbps), well below the speed of even a traditional 10 Mbps Ethernet LAN.
- **T3 lines:** These offer higher speeds of 44.736 Mbps, close to the range of 100 Mbps Fast Ethernet, but at a much higher cost than T1 lines.

Inverse Multiplexing over ATM (IMA) bridges the gap between these two solutions by allowing multiple T1 lines carrying ATM to be aggregated for transmission over a fractional T3 circuit. IMA is a good solution for enterprises needing ATM WAN connectivity faster than T1 but at costs much lower than T3.

See Also: *Asynchronous Transfer Mode (ATM), inverse multiplexing*

inverse query

A Domain Name System (DNS) query in which a resolver contacts a name server to perform a reverse name lookup, requesting a host name for a given Internet Protocol (IP) address.

Overview

An inverse query is a process whereby given a host's fully qualified domain name (FQDN), the host's IP address is looked up. This is the opposite of the usual DNS query where a FQDN is resolved into its associated IP address. Because of the hierarchical structure of the namespace of the DNS, inverse queries normally have to search all domains to resolve the IP address. To circumvent this, a special domain called in-addr.arpa exists for reverse name lookups. The nodes in this domain are named after the IP addresses of hosts but with the octets in reverse order to facilitate searching. However, inverse queries can take place only on the name server queried and cannot be forwarded to another name server. Because individual name servers manage only a small portion of the entire DNS namespace, there is no guarantee that a given inverse query issued against a specific name server will meet with a successful response.

Notes

Most names used on Internet servers are configured for reverse name lookups to avoid the extra overhead required. However, if you need to use the DNS troubleshooting utility Nslookup, you should configure the in-addr.arpa domain on name servers to support inverse queries. Otherwise, there is no need to configure this inverse domain.

See Also: *in-addr.arpa, iterative query, recursive query*

IOS

Stands for Internetwork Operating System, the operating system developed by Cisco Systems for its line of routers and access servers to provide a standard way to configure and administer these devices.

See: *Internetwork Operating System (IOS)*

IP

Stands for Internet Protocol, the network layer protocol used by Transmission Control Protocol/Internet Protocol (TCP/IP) for addressing and routing packets of data between hosts.

See: *Internet Protocol (IP)*

IP address

In IPv4, a 32-bit logical address for a host on an Internet Protocol (IP) network; in IPv6, IP addresses are 64 bits in length.

Overview

IP addresses allow packets to be routed over an IP network. Each IP packet has a header that contains the IP address of the source host that transmitted the packet and the destination host to which the packet is being sent. IP addresses can be one of three types:

- **Unicast:** This type forwards the packet to a single target host (one-to-one forwarding).
- **Multicast:** This type forwards the packet to all hosts that have joined a multicast group (one-to-many forwarding).
- **Broadcast:** This type forwards the packet to all hosts on a subnet or network (one-to-all forwarding).

In order for communication to take place reliably on an IP network, each host on the network needs a unique IP address assigned to it. IP addresses can be assigned either

- **Manually:** By using static IP addressing, or
- **Dynamically:** By using Dynamic Host Configuration Protocol (DHCP)

Architecture

IP addresses are usually expressed in four-octet, dotted-decimal form—w.x.y.z—in which each octet ranges in value from 0 to 255 (with some restrictions). The IP address of a host is partitioned by the network's subnet mask into two parts, a network ID and a host ID.

IP addresses belong to certain classes according to their first octet, as defined in the following table. The actual distinguishing feature of each class is the pattern of high-order bits in the first octet, but it is easier to remember these classes by their first octet decimal numbers. IP addresses whose first octet is 127 represent the loopback address and are used for troubleshooting purposes only, and cannot be assigned to hosts.

IP Address Classes

IP Address Class	*Possible First Octet*	*Used For*
Class A	1–126	Very large networks
Class B	128–191	Medium to large networks
Class C	192–223	Small networks
Class D	224–239	Multicasting
Class E	240–255	Reserved (experimental)

Networks that are directly connected to the Internet must have their IP addresses assigned by the Internet Network Information Center (InterNIC) or some other authority. Businesses usually obtain these addresses through their local Internet service provider (ISP). However, firewall and proxy server combinations, which are popular on today's networks, hide a network's IP addresses from other hosts on the Internet. These private networks can use any IP addresses they choose, although InterNIC recommends the following IP address blocks for private networks:

- **Class A networks:** 10.x.y.z
- **Class B networks:** 172.16.y.z through 172.31.y.z
- **Class C networks:** 192.168.0.z through 192.168.255.z

Note

Note the following considerations for valid IP addressing:

- The network ID cannot be 127.
- The network ID and host ID cannot both be 255.
- The network ID and host ID cannot both be 0.
- The host ID must be unique for a given network ID.

See Also: *Class A, Class B, Class C, Class D, Class E, Internet Protocol (IP), subnet mask, subnetting*

IP/ATM

Also called IP over ATM, a method for enabling Transmission Control Protocol/Internet Protocol (TCP/IP) networks to access Asynchronous Transfer Mode (ATM) networks.

Overview

The traditional way of connecting TCP/IP and ATM networks is to run LAN Emulation (LANE) services on the ATM network. IP/ATM is an alternative to LANE and allows TCP/IP networks to directly use ATM networks and take advantage of ATM's Quality of Service (QoS) features. IP/ATM is faster than LANE and is supported by Microsoft Windows 2000.

Implementation

IP/ATM is implemented as a client/server architecture that includes

- IP/ATM servers that include two components: ATM address resolution protocol (ARP) servers and multicast address resolution server (MARS). IP/ATM servers can reside either on an ATM switch or on a Windows 2000 server.
- IP/ATM clients, which support both static and dynamic IP addressing.

See Also: *Asynchronous Transfer Mode (ATM), LAN Emulation (LANE), Transmission Control Protocol/Internet Protocol (TCP/IP)*

I

IPC

Stands for interprocess communication, a mechanism for establishing a connection between processes running on two computers or on a single multitasking computer to allow data to flow between those processes.

See: *interprocess communication (IPC)*

Ipconfig

A utility for displaying the Internet Protocol (IP) configuration settings of a network interface.

Overview

The Ipconfig command is often one of the first commands you use to check the status of the connection when you experience communication problems on a Transmission Control Protocol/Internet Protocol (TCP/IP) network. When you type **ipconfig** at a Microsoft Windows 2000 command prompt, the following information is displayed for each network interface card (NIC):

- IP address
- Subnet mask
- Default gateway

You can display additional information, including the host name, physical address, and Dynamic Host

Configuration Protocol (DHCP), Windows Internet Name Service (WINS), and Domain Name System (DNS) configuration, using ipconfig /all. You can release and renew IP addresses obtained by DHCP using ipconfig /release and ipconfig /renew.

See Also: *default gateway, IP address, subnet mask*

IP Fax

Transmission of fax information over Internet Protocol (IP) networks.

Overview

Fax is a popular method of communications in large enterprises—analysts estimate that almost half of enterprise telephone charges come from faxing. IP Fax is a standard method for formatting fax images into frames for transmission over IP networks. IP Fax can save enterprises considerable costs in long-distance charges by routing faxes over either private IP wide area network (WAN) links or over the public Internet.

Implementation

IP Fax employs the T.37 protocol from the International Telecommunication Union (ITU), which is based on RFCs 2301 and 2305 from the Internet Engineering Task Force (IETF). This protocol implements a store-and-forward method for formatting and transmitting fax information over IP networks. Typically, a user will send a fax from her computer directly to a local fax server, which formats the information using the T.37 protocol. The fax server then sends the information as IP traffic over the private IP network or Internet to a remote fax server near the customer location. The remote fax server unpackages the information and reconstructs the fax and then transmits the fax over the Public Switched Telephone Network (PSTN) as a local call to the intended recipient of the fax. In this way, long-distance charges between the sender and recipient are avoided.



IP Fax. *How IP Fax is implemented.*

The general concept of transmitting faxes over IP networks is not new, but earlier solutions had used proprietary routing methods developed by different vendors. IP Fax is expected to promote interoperability between equipment from different fax vendors by providing a standards-based solution to the problem.

See Also: *Internet Protocol (IP)*

IPng

Stands for IP Next Generation, an early name for IPv6, next generation Internet Protocol (IP) addressing scheme for Transmission Control Protocol/Internet Protocol (TCP/IP) networks.

See: *IPv6*

IP over ATM

Also called IP/ATM, a method for enabling Transmission Control Protocol/Internet Protocol (TCP/IP) networks to access Asynchronous Transfer Mode (ATM) networks.

See: *IP/ATM*

IPP

Stands for Internet Printing Protocol, a method for printing over the Internet.

See: *Internet Printing Protocol (IPP)*

IP PBX

A private branch exchange (PBX) that uses an Internet Protocol (IP) network as its transport.

Overview

IP PBXs are alternatives to traditional telecom PBXs. They use IP networks for all or part of their transport of call information. IP PBXs come in two main types:

- Those that transport call information over the local area network (LAN) and employ special IP telephones and fax machines that plug directly into LAN drops in work areas.
- Those that employ IP networks (either dedicated leased lines or over the Internet) to connect branch offices but transport calls to work areas using conventional telephone lines.

Advantages and Disadvantages

IP PBXs are generally cheap compared to traditional PBXs and can save corporate clients from costly service contracts with telcos. They allow voice, fax, and data to be carried over a single wiring infrastructure (the network) instead of requiring an additional wiring infrastructure (telephone wiring). Finally, IP PBXs provide more flexibility than traditional PBXs by supporting Voice over IP (VoIP) and other options.

On the downside, the quality of IP PBXs and the range of features offered, particularly for voice, is often less than that of traditional PBXs. Furthermore, most IP PBXs support only a few hundred users, whereas traditional PBXs can support tens of thousands of users (at a price, of course).

Marketplace

A number of vendors produce IP PBX equipment, including Cisco Systems, 3Com Corporation, Vertical Networks, Shoreline Communications, Sphere Communications, Siemens, and many others. IP Exchange Systems from Lucent Technologies is a popular full-featured high-end IP PBX solution for the enterprise. Cisco’s AVVID platform is an enterprise-level IP PBX system that’s been around since 1999. A popular IP PBX in the small to mid-size business market is 3Com’s NBX 100, and 3Com has over half the share of this market, followed by Vertical Networks and Cisco.

Traditional PBX vendors such as Nortel Networks offer a competing solution to IP PBXs in the form of VoIP gateways that connect with installed traditional PBXs to provide similar services to IP PBXs.

A new offering in the market is the IP Centrex, which is basically outsourcing IP PBX services to a service provider. IP Centrex may appeal to small and mid-sized businesses whose traditional Centrex systems are aging. IP Centrex services are offered from MCI/WorldCom and others.

See Also: *Private Branch Exchange (PBX), Voice over IP (VoIP)*

IPsec

Stands for Internet Protocol Security, a protocol for secure transmission over Transmission Control Protocol/Internet Protocol (TCP/IP).

See: *Internet Protocol Security (IPsec)*

IP storage

A generic name for any method of sending block data over Internet Protocol (IP) networks.

Overview

IP storage is an emerging family of technologies that has great promise. The purpose of these technologies is to enable Ethernet local area networks (LANs) running IP to be directly connected to Storage Area Networks (SANs). IP storage is expected to simplify the management of distributed network storage systems in the enterprise. Another generic name for these technologies is storage-over-IP.

Two approaches to IP storage being considered by the Internet Engineering Task Force (IETF) are

- Encapsulation of Fibre Channel control codes in IP packets for communication between Fibre Channel SANs.
- Transport of native Small Computer System Interface (SCSI) commands over IP. This technology is generally known as iSCSI.

See Also: *Fibre Channel, iSCSI, storage*

IP telephony

An umbrella term for technologies that allow the transmission of voice and video over Transmission Control Protocol/Internet Protocol (TCP/IP) internetworks instead of the traditional Public Switched Telephone Network (PSTN).

Overview

The advantage of IP telephony is that it allows voice communication to be closely integrated with data transmission over corporate networks and allows long-distance communication to be established over the Internet instead of through private long-distance carriers such as Sprint and MCI/WorldCom. The primary difficulty with IP telephony is that the existing Internet Protocol (IP) internetwork is connectionless and suffers from latency that can cause annoying glitches (pauses) in voice and video transmission over IP packets. This happens because TCP/IP was not originally designed as a connection-oriented service capable of specific levels of quality of service (QoS), whereas the PSTN, with its circuit-switched connections, provides just that.

Marketplace

Many vendors have produced platforms and software for IP telephony, but the technology is still in its growth stage and standards are not clearly established yet. The biggest push in recent years has been by the interexchange carriers (IXCs) AT&T and MCI/WorldCom, who have made large overtures into the Voice over IP (VoIP) marketplace. IP private branch exchanges (PBXs) have proven popular among small and mid-sized businesses, with offerings from 3Com Corporation, Cisco Systems, and others.

See Also: *H.323, Voice over IP (VoIP)*

IPv4

The current version of Internet Protocol (IP).

Overview

IPv6 employs a 32-bit IP addressing scheme that is used on Transmission Control Protocol/Internet Protocol (TCP/IP) networks worldwide. Because the number of hosts connecting to the Internet has skyrocketed in recent years, however, unique IP addresses are running out. A new scheme called IPv6 has been proposed and is currently under review by the Internet community. However, with most corporate networks now hiding their networks behind firewalls, the pressure to move to IPv6 has lessened because companies can choose any network ID they want for their private network. The only assigned IP addresses they require from their Internet service provider (ISP) are for the public interfaces on their firewall machines. At this point, IPv4 seems to be firmly entrenched in the networking world for at least the next few years.

See Also: *Internet Protocol (IP), IPv6*

IPv6

The next generation Internet Protocol (IP) addressing scheme for Transmission Control Protocol/Internet Protocol (TCP/IP) networks.

Overview

IPv6 was developed to replace the current IPv4 scheme that has been running out of available addresses due to the explosion of the Internet. The features of IPv6 include

- 128-bit IP addresses to solve the problem of the available IP address pool being depleted
- A simplified header format to reduce network overhead and improve performance
- Support for preallocation of network resources to enable time-dependent services such as voice and video to receive guaranteed bandwidth and quality of service (QoS)

- Extensibility to account for future growth and evolution of Internet technologies and standards
- Built-in support for Internet Protocol Security (IPsec) and DiffServ

IPv6 is also sometimes referred to as IPng, which stands for “IP Next Generation.” A network called the 6Bone was set up in 1995 as a test bed for IPv6 and to investigate how the Internet can be migrated from IPv4 to IPv6.

Prospects

Japan has been in the forefront of implementing IPv6 as a real-world networking protocol, with products by Hitachi, Fujitsu, and others reaching the marketplace in early 2001. In fact, the first Internet service provider (ISP) to offer support for Ipv6 was Japan’s NTT telecommunications company. Cisco Systems fully incorporated IPv6 into its IOS operating system in the recent upgrade version 12.2. Microsoft Windows XP also includes built-in support for IPv6, and a downloadable IPv6 stack is available for Windows 2000 as well. All these developments will likely propel IPv6 to the forefront in the next few years, except for one important factor: the inertia of the corporate networking world. The cost of upgrading corporate networks from IPv4 to IPv6 will be high and may bring no immediate benefits. Consequently, many companies may put upgrading on the back burner for several years.

The proliferation of wireless Internet appliances is expected to put pressure on migration to IPv6 since traditional IPv4 will be hard-pressed to fill the need for addressing large numbers of such devices. For once, it may be consumers, and not the enterprise, who drive the evolution of the Internet’s core protocols forward.

See Also: *Internet Protocol (IP)*

IPX

Stands for Internetwork Packet Exchange, a NetWare protocol used for routing packets across an internetwork.

See: *Internetwork Packet Exchange (IPX)*

IPX/SPX-Compatible Protocol

Microsoft Corporation’s version of the Novell NetWare IPX/SPX (Internetwork Packet Exchange/Sequenced Packet Exchange) protocol.

Overview

Using IPX/SPX and Client for NetWare Networks, clients running Microsoft Windows can access shared resources on NetWare servers directly, as long as they have appropriate permissions and rights. IPX/SPX-Compatible Protocol can be used to access Windows 2000 servers running File and Printer Sharing for NetWare Networks. IPX/SPX-Compatible Protocol supports the 32-bit Windows Sockets 1.1 and NetBIOS over Internetwork Packet Exchange (IPX) programming interfaces. In Windows 2000, this protocol is commonly referred to as NWLink.

Notes

Although the Windows 95 and Windows 98 user interfaces allow you to configure multiple bindings for IPX/SPX-Compatible Protocol to multiple network interface cards (NICs), only the first binding is actually used. You cannot use IPX/SPX-Compatible Protocol for connecting to NetWare over an ARCNET network; you must install real-mode IPX drivers instead.

IPX/SPX-Compatible Protocol is set by default to autodetect the frame type used on a NetWare network. If no frame type is detected, the default 802.2 type is used. If multiple frame types are detected, the predominant one is selected.

See Also: *Internetwork Packet Exchange (IPX), NetWare protocols*

IRC

Stands for Internet Relay Chat, a text-based Internet conferencing protocol.

See: *Internet Relay Chat (IRC)*

IrDA

Stands for Infrared Data Association, an international consortium of hardware and software manufacturers that creates and promotes interoperable solutions for infrared (IR) data networking for computer networks, communication, and other networking applications.

See: *Infrared Data Association (IrDA)*

IrDA Control

A specification developed in 1998 by the Infrared Data Association (IrDA) for communication over infrared (IR) light between in-room cordless peripheral devices and a host computer.

Overview

IrDA Control is implemented using a suite of protocols that peripherals such as keyboards, joysticks, mouse devices, and other pointing devices can use for communicating with their host computer. IrDA Control includes the following protocols:

- **IrDA Control PHY (physical) layer:** This provides for data transmission that is bidirectional and error-correcting over IR light at speeds of up to 75 Kbps over distances of up to 5 meters (16 feet).
- **IrDA Control MAC (media access control) layer:** This enables host devices to communicate with multiple IrDA Control peripherals and up to eight peripherals simultaneously. IrDA Control MAC offers a fast response time by using a polling interval of 13.8 microseconds) and supports the dynamic assignment and reuse of addresses assigned to peripheral devices.
- **IrDA Control LLC (logical link control) layer:** This ensures proper sequencing of data and handles retransmissions when errors occur.

See Also: *Infrared Data Association (IrDA), IrDA Data*

IrDA Data

A specification developed by the Infrared Data Association (IrDA) in 1994 for two-way point-to-point communication over infrared (IR) light at speeds of up to 4 megabits per second (Mbps).

Overview

IrDA Data is implemented using a suite of protocols that can be used for communication between palm computers, digital cameras, cellular phones, and other devices. IrDA Data includes the following protocols:

- **IrDA Data PHY (physical) layer:** This provides low-level continuous bidirectional error-correcting operation from 9600 bits per second (bps) up to 4 Mbps over distances of at least 3.3 feet (1 meter). Specifically, asynchronous serial transmission is supported between 9600 bps and 115.2 kilobits per second (Kbps), synchronous serial transmission at 1.152 Mbps, and synchronous communication at 4 Mbps.
- **IrDA Data Infrared Link Access Protocol (IrLAP):** This is a serial link protocol adapted by the IrDA for infrared serial communication from the High-level Data Link Control (HDLC) protocol. IrLAP provides a single serial connection between two IrDA devices and manages the device-to-device discovery, connection, and reliable data transfer functions.
- **IrDA Data Infrared Link Management Protocol (IrLMP):** This is used for link control and multiplexing of IrDA devices. IrLMP allows multiple IrDA devices to communicate over a single infrared link and provides for protocol and service discovery through the Information Access Service (IAS).

In addition to the three mandatory IrDA Data protocols described, a number of optional protocols are available that support flow control, port emulation, object exchange services, image exchange, interfacing with telephony devices, and infrared wireless access to local area networks (LANs).

See Also: *Infrared Data Association (IrDA), IrDA Control*

Irix

A flavor of the UNIX operating system developed by Silicon Graphics, Inc. (SGI).

Overview

Irix was developed by SGI for their high-end graphics workstations and servers and has been an important factor in the company's success in the imaging and animation market. SGI workstations running Irix are used for creating film and TV animation, medical image processing, and for visualization of scientific concepts such as molecular structures and weather patterns. Irix is a version of UNIX that is tuned specifically for such applications and supports multiprocessing of up to 512 CPUs, up to 1 terabyte of RAM, and high-performance input/output (I/O) throughput. The current version of the platform is Irix 6.5.

Irix was designed to run on MIPS (millions of instructions per second) processors, which these days are slower than their Intel counterparts, bringing the long-term viability of Irix into question. With the broad base of installed SGI workstations and servers, however, SGI is likely to continue to support and develop Irix in the near future, even as it expands its hardware platform to support Microsoft Windows and Linux.

See Also: *Linux, Microsoft Windows, UNIX*

IRTF

Stands for Internet Research Task Force, an umbrella organization for several long-term research groups that focus on standards for Internet protocols, architecture, applications, and technologies.

See: *Internet Research Task Force (IRTF)*

ISAPI

Stands for Internet Server API, a set of standard application programming interfaces (APIs) for developing extensions to Microsoft Internet Information Services (IIS).

See: *Internet Server API (ISAPI)*

ISAPI extension

A dynamic-link library (DLL) that runs in the same address space as the Web server running Microsoft Internet Information Services (IIS) and can access all available resources on the Web server.

Overview

You can use ISAPI extensions wherever you might use Common Gateway Interface (CGI) applications, such as for a form handler for Hypertext Markup Language (HTML) forms. An ISAPI extension is generally called in a manner similar to calling a CGI application. For example, the following Uniform Resource Locator (URL) invokes the extension TEST.DLL on the Web site *www.northwind.microsoft.com* and passes it the parameters Value1 and Value2: *www.northwind.microsoft.com/isapie/TEST.DLL?Value1&Value2*.

ISAPI extensions can run either in process or out of process on IIS. Extensions are generally loaded on demand the first time a user requests them and remain in memory until the service is stopped.

See Also: *Common Gateway Interface (CGI), dynamic-link library (DLL), Internet Information Services (IIS), Internet Server API (ISAPI), ISAPI filter*

ISAPI filter

A dynamic-link library (DLL) that is loaded into Microsoft Internet Information Services (IIS) when it starts and that remains in memory until it stops.

Overview

ISAPI filters provide Web servers such as IIS with the ability to preprocess or postprocess information sent between the client and server, and they have no equivalent in the Common Gateway Interface (CGI) scheme. ISAPI filters receive special filter event notifications and respond based on these notifications. You use ISAPI filters for such tasks as custom authentication, encryption, and compression schemes or for updating logging statistics on the Web server. ISAPI filters are generally called for every Uniform Resource Locator (URL) that the Web server processes instead of being explicitly invoked by a URL, as are ISAPI extensions.

Custom ISAPI filters can be designed by third-party developers for such tasks as

- Custom authentication
- Data encryption
- Data compression
- Filtering
- Traffic analysis

See Also: *Common Gateway Interface (CGI), dynamic-link library (DLL), Internet Information Services (IIS), Internet Server API (ISAPI), ISAPI extension*

ISA Server

Stands for Internet Security and Acceleration Server, Microsoft Corporation's firewall, proxy, and Web-caching platform.

See: *Internet Security and Acceleration Server (ISA Server)*

iSCSI

An emerging standard for transfer of Small Computer System Interface (SCSI) commands and data over Internet Protocol (IP) networks.

Overview

Traditional SCSI is limited in distance to several meters and is thus suitable only for local storage systems and shared storage in clusters. The goal of iSCSI is to remove these distance limitations by enabling SCSI commands and data to be sent between hosts and storage units over a standard IP network.

The iSCSI standard is expected to be a popular IP storage technology in the next few years, propelled on the backs of Gigabit Ethernet (GbE) and the emerging 10 GbE standard.

Implementation

Consider the example of a client trying to remotely access data from a remote storage system such as a SCSI array over a network. With iSCSI, the client simply issues the request in the form of SCSI commands as if to a local SCSI drive. The operating system or dedicated iSCSI card then packages these SCSI commands into a stream of bytes separated by iSCSI headers. The byte stream is broken up into IP packets and transmitted over the network to the remote storage array. Once received by the array, the packets are reassembled into the byte stream and the iSCSI headers are parsed to produce a series of SCSI commands, which are then issued to the local SCSI storage system. The data is then retrieved from the storage system and returned to the client.



iSCSI. *How iSCSI allows clients to remotely access storage over an IP network.*

Marketplace

A number of vendors produce products and appliances based on the iSCSI standard. One example is the TotalStorage IP storage family of iSCSI storage appliances from IBM. These appliances are designed for workgroups and departments that need turnkey network storage solutions. The future of iSCSI looks good, as it is backed by such major players as Adaptec, Cisco Systems, Hewlett-Packard Company, IBM, Quantum Corporation, and SANgate Systems.

See Also: *IP storage, Small Computer System Interface (SCSI), storage*

ISDN

Stands for Integrated Services Digital Network, a digital communication service provided by telephone companies (telcos).

See: *Integrated Services Digital Network (ISDN)*

ISDN Digital Subscriber Line (IDSL)

A hybrid of Integrated Services Digital Network (ISDN) and Digital Subscriber Line (DSL) technologies.

Overview

ISDN Digital Subscriber Line (IDSL) is a form of DSL that is based on ISDN signal coding. IDSL transports data bidirectionally at a speed of 144 kilobits per second (Kbps), which is 16 Kbps more than normal ISDN. IDSL can be deployed at distances up to 6.8 miles (11 kilometers) from a telco central office (CO).

Unlike other forms of DSL that use the Public Switched Telephone Network (PSTN) as their underlying transport, IDSL uses the digital ISDN system. But unlike normal ISDN, there is no call delay setup in IDSL—it is an “always-on” service.

Prospects

Due to its slow speed compared to other forms of DSL, IDSL has not been widely deployed by telecommunication carriers to date, but a recent development called IDSL bonding may change this. Using IDSL bonding, up to four 144 Kbps IDSL links can be aggregated together using Multilink Point-to-Point Protocol (MPPP) into a respectable fat pipe of 576 Kbps. And because it supports distances up to 6.8 miles (11 kilometers) from a CO, IDSL provides an important option for customers too far from telco COs for Asymmetric Digital Subscriber Line (ADSL) or High-bit-rate Digital Subscriber Line (HDSL) to be deployed for wide area network (WAN) or Internet access. Netopia was the first DSL provider to commercially offer bonded IDSL services to its customers.

See Also: *Asymmetric Digital Subscriber Line (ADSL), Digital Subscriber Line (DSL), High-bit-rate Digital Subscriber Line (HDSL), Integrated Services Digital Network (ISDN)*

ISDN fallback adapter

A device that allows you to use an Integrated Services Digital Network (ISDN) line as a back up for a digital data service (DDS) line.



ISDN fallback adapter. *Using an ISDN fallback adapter to provide a backup for a DDS line.*

Overview

ISDN fallback adapters typically have built-in ISDN terminal adapter functionality and can sometimes provide backup support for multiple DDS lines. The fallback and restore settings are configurable using a built-in or serial-connected terminal interface.

To use a fallback adapter, you connect it to the ISDN line with the RJ-45 connector and to the local area network (LAN) bridge or router and the DDS CSU/DSUs (Channel Service Unit/Data Service Units) using the V.35 or RS-232 serial interfaces. When the DDS line fails, the ISDN fallback adapter automatically kicks in the ISDN line to maintain wide area network (WAN) connectivity.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), digital data service (DDS), Integrated Services Digital Network (ISDN), RS-232, V.35*

ISDN router

A router with built-in hardware for connecting directly to Integrated Services Digital Network (ISDN) lines.

Overview

ISDN routers—also called ISDN access routers because they provide direct connectivity to a wide area network (WAN) connection—are a popular way of providing SOHOs (Small Office/Home Offices) with 128-Kbps dial-up ISDN connectivity to the Internet or to a remote private corporate network through the industry-standard Point-to-Point Protocol (PPP). They typically support up to 10 users in a small workgroup Ethernet local area network (LAN) and might provide some firewall, network address translation (NAT), or Dynamic Host Configuration Protocol (DHCP) support.

ISDN routers include RJ-11 jacks for connecting several analog phones, fax machines, or other devices for simultaneous voice/fax/data connectivity. Built-in data compression can increase the effective bandwidth by a factor of 5 or higher. Some ISDN routers include built-in hubs for quick connectivity. Many are manageable using a remote Telnet connection or through Simple Network Management Protocol (SNMP).

See Also: *Dynamic Host Configuration Protocol (DHCP), Integrated Services Digital Network (ISDN), network address translation (NAT), Point-to-Point Protocol (PPP), router, Simple Network Management Protocol (SNMP)*

ISDN terminal adapter

A device used at the customer premises to terminate an Integrated Services Digital Network (ISDN) line and connect it to an analog telephone, computer, or local area network (LAN).

Overview

You must employ ISDN terminal adapters when you do not have telephone, computing, or networking equipment that are ISDN-ready. Another name for ISDN terminal adapters is *ISDN modems*, but this is a misnomer, since no modulation/demodulation is performed by the device.

ISDN terminal adapters can be stand-alone AC powered devices or interface cards that you install on your computer. They can provide 128-kilobit-per-second (Kbps) throughput using the Bandwidth On Demand Interoperability Group (bonding) protocol for high-speed Internet and wide area network (WAN) connectivity, with higher effective data transfer rates using built-in data compression. ISDN terminal adapters are dial-up and do not provide an "always on" network connection, but their latency time interval for establishing a connection is typically small (1 to 3 seconds). To save costs, you can usually also configure an idle timer for dropping idle connections.

When you buy ISDN terminal adapters, be sure that they support the ISDN standard used by your telco. Such standards can include the National ISDN-1, ISDN-2, and ISDN-3 standards for AT&T, Northern Telecom, and Siemens. An ISDN terminal adapter with automatic service profile identifier (SPID) detection generally works with most ISDN installations.



ISDN terminal adapter. *Using an ISDN terminal adapter.*

Implementation

A terminal adapter typically connects to the U interface of the ISDN line at the customer premises using an RJ-45 connector and provides electrical termination for this line. The other interface on the terminal adapter is typically an RS-232, RS-366, RS-530, or V.35 serial interface such as DB25, or a 34-pin connector for connecting the terminal adapter to a bridge, router, or computer at the customer premises. Terminal adapters can include several RJ-11 connectors for connecting an analog telephone or a fax machine so that you can transfer data, talk on the phone, and fax documents simultaneously over one ISDN line. Some newer terminal adapters have an S/T interface for connecting to an S/T videoconferencing unit.

Notes

If you need more speed than ISDN but cannot afford to upgrade to T1 lines, try using an inverse multiplexer (IMUX) to combine several ISDN lines into one high-speed data pipe.

See Also: *Integrated Services Digital Network (ISDN), inverse multiplexer (IMUX)*

ISL

Stands for Inter-Switch Link, a Cisco Systems technology that is used for frame tagging.

See: *Inter-Switch Link (ISL)*

ISM

Stands for the Industrial, Scientific, and Medical band of the electromagnetic spectrum.

Overview

The ISM band consists of 83 megahertz (MHz) of spectrum at the 2.4 gigahertz (GHz) range that is freely available to anyone who wants to use it.

The ISM band is used by common wireless technologies including cordless phones, microwave ovens, wireless local area networks (LANs) such as 802.11b, and emerging technologies such as Bluetooth and HomeRF. Many of these devices interfere with each other, so as a result, the ISM band has grown “crowded” in recent years. To alleviate this congestion, the Federal Communications Commission (FCC) has allocated another similar portion of spectrum called the UNII band, which provides 300 MHz of spectrum within the 5 GHz range. The UNII band is used by the newer 802.11a wireless networking standard.

Notes

The reason for selecting 2.4 GHz for the ISM band is that the resonant frequency of water molecules is about 2450 MHz, which means this is the optimal frequency for microwave ovens to work.

See Also: *802.11a, 802.11b, Bluetooth, Federal Communications Commission (FCC), wireless networking*

ISO

Stands for International Organization for Standardization, a nongovernmental organization based in Geneva, Switzerland, that has representatives from about 130 countries and regions and is responsible for developing a variety of international standards in science and engineering.

See: *International Organization for Standardization (ISO)*

ISOC

Stands for Internet Society, a professional society founded in 1992 that provides leadership for the development and evolution of the Internet.

See: *Internet Society (ISOC)*

isoEthernet

Stands for isochronous Ethernet, an offshoot of 10BaseT Ethernet.

Overview

IsoEthernet was developed in 1992 by National Semiconductor and was standardized by the Institute of Electrical and Electronics Engineers (IEEE) as 802.9a. IsoEthernet follows the cabling specifications of 10BaseT Ethernet but is capable of dedicating some circuits for transport of latency-sensitive multimedia traffic.

The signaling layer of isoEthernet is based on Integrated Services Digital Network (ISDN) protocols instead of those of standard Ethernet.

IsoEthernet never caught on with the industry, mainly because the problem it attacked (the issue of latency for time-sensitive traffic) has been largely solved by Fast Ethernet and Gigabit Ethernet (GbE)—in other words, by simply throwing bandwidth at the problem. IsoEthernet is thus now seen as a legacy networking architecture and is virtually gone from the enterprise scene.

See Also: *10BaseT, Ethernet, Fast Ethernet, Gigabit Ethernet (GbE), Integrated Services Digital Network (ISDN)*

ISP

Stands for Internet service provider, a company that provides Internet access to consumers, businesses, or both.

See: *Internet service provider (ISP)*

iterative query

A Domain Name System (DNS) query in which a name server contacts a second name server to perform a name lookup.

Overview

In a typical Internet name lookup (such as the URL *www.fabrikam.microsoft.com*), a resolver sends a recursive query to a locally accessible name server such as a name server maintained by your local Internet service provider (ISP). If the local name server cannot resolve the name because it is outside of its zone of authority and it is configured as a forwarder, the server performs an iterative query to a root name server, which responds with the Internet Protocol (IP) address of a name server whose zone of authority includes the desired top-level domain (.com). The local name server then performs an iterative query with this top-level name server, which responds with the IP address of a second-level name server whose zone of authority includes the desired second-level domain (expedia.com). The local name server contacts this second-level name server and resolves the fully qualified domain name (FQDN) into its IP address or returns an error if the query cannot be resolved.

See Also: *inverse query, recursive query*

itrace

Code name for ICMP Traceback Messages, an emerging standard from the Internet Engineering Task Force (IETF) for combating distributed denial of service (DDoS) attacks.

See: *ICMP Traceback Messages*

ITU

Stands for International Telecommunication Union, an international organization headquartered in Geneva, Switzerland, that coordinates global telecommunications networks and services with governments and the private sector.

See: *International Telecommunication Union (ITU)*

IXC

Stands for inter-exchange carrier, a telecommunications carrier that provides long-distance services.

See: *inter-exchange carrier (IXC)*

J

jabber

Random, malformed frames of data that are sent continuously by failed circuitry in a networking component.

Overview

A network interface card (NIC) or other device that is jabbering generates a continuous stream of unwanted signals that can disrupt communication between other devices on the network. This is especially common on Ethernet networks, in which each device must compete for use of the line using the Carrier Sense Multiple Access with Collision Detection (CSMA/CD) contention protocol. When a NIC jabbers on an Ethernet network, all network communication might cease until the offending NIC is replaced. Other causes of jabbering on a network include loose cabling or a poorly grounded cable (for shielded cabling).

Jabbering can also occur in Fast Ethernet networks, in which a combination of 100BaseT4 and 100BaseTX cabling schemes are employed in one network. The continuously generated idle stream signal of the TX network can appear to the T4 network as jabber and can bring down the entire network. This should not be a problem if all network devices implement autonegotiation in an IEEE-compliant fashion. In addition, Fast Ethernet repeaters generally implement jabber control by automatically disconnecting any port that transmits information in streams longer than 40 kilobits (Kb).

The term *jabber* is also used in the Institute of Electrical and Electronic Engineers (IEEE) 802.3 specification for any frame of data that exceeds the maximum frame length for that specification. For Ethernet networks, the maximum frame length is 1518 bytes (18 bytes of overhead and 1500 bytes of payload). A frame longer than 1518 bytes is often called a jabber frame. Another name for jabber is *long packet error*.

Notes

A frame shorter than 64 bytes on an Ethernet network is called a runt frame.

See Also: *Carrier Sense Multiple Access with Collision Detection (CSMA/CD), Ethernet, Fast Ethernet, frame*

jack

A receptacle into which you can insert a connector or plug to form a connection.

Overview

The best example of a jack in computer networking is the standard RJ-45 jack in which a connector (plug) on the end of a Category 5 (Cat5) cable can be inserted. RJ-45 jacks are typically built into Ethernet networking devices such as hubs, switches, and routers, but some devices also allow modular jacks to be inserted and removed in order to support other kinds of connectors. Patch panels and wall plates are other examples of items that may either be hardwired with RJ-45 jacks or allow modular jacks to be inserted into them for greater flexibility.



Jack. *Example of a modular RJ-45 jack.*

Notes

The terms *connector*, *jack*, and *plug* have some overlap and are often used interchangeably. Some vendors use *plug* to refer to the male connector and *jack* to refer to the female, but others use the terms *male jacks* and *female jacks*.

See Also: *cabling, Category 5 (Cat5) cabling, Ethernet*

jacket

The outer covering of cabling that protects it from physical damage.

Overview

A cable's jacket protects the wiring from various kinds of damage, including damage caused by

- Exposure to sun, heat, moisture, dust, and chemicals
- Contact with sharp edges of walls, furniture, or plenum ducts (such as ventilation ducts); by mechanical vibrations; or by mechanical stresses introduced during the cable installation process

The jacket is usually made of an insulating material, although its primary purpose is not insulation. (This function is provided by the insulation of individual wires within the jacket.) Common materials used for cable jackets include the following:

- **Polyvinyl chloride (PVC):** This is the most common material used for cable jackets. PVC is a tough, fire-resistant material formed from resins and plastics that can withstand a wide range of temperatures. PVC cables are typically used in vertical rises, but they should not be used in plenums because PVC gives off toxic fumes when burned.
- **Kynar plastic (polyvinylidene fluoride):** This material has good fire-retardant qualities, which makes it suitable for installation in plenums, but it is several times more costly than PVC.
- **Flamarrest:** This chloride compound has high fire retardance and is suitable for plenum installations.
- **Neoprene:** This dark-colored plastic is resistant to moisture and does not degrade in sunlight. It is a good choice for use in outdoor cable runs.
- **Polyethylene:** This soft, moisture-resistant plastic has poor fire retardance and is suitable only for outdoor cable runs.

See Also: *cabling*

jam signal

A signal sent by a device on an Ethernet network to indicate that a collision has occurred on the network.

Overview

Collisions occur on Ethernet networks because access to media (usually a cable) is based on contention—that is, stations on the network transmit on a first-come, first-served basis. If two stations attempt to take control of the medium at the same time and begin transmitting, both stations will detect each other's signal and realize that a collision has occurred. The two stations then issue a jam signal, which notifies all other stations on the network of the collision. They all must wait a short period of time before attempting to transmit again. The length of time is random for each station so that the retransmissions will not cause more collisions. The jam signal sent by one transmitting station must start with a 62-bit pattern of alternating 0s and 1s, followed by a 32-bit sequence that provides a dummy checksum value for the other transmitting station. This 32-bit sequence cannot be equal to the cyclical redundancy check (CRC) value for the frame preceding the jam.

See Also: *Carrier Sense Multiple Access with Collision Detection (CSMA/CD), collision, Ethernet,*

Java

An object-oriented programming language developed by Sun Microsystems.

Overview

Java was designed to reduce the amount of time needed to build robust, scalable object-oriented applications. Java is a powerful object-oriented programming (OOP) platform like C and C++, but it has several advantages over these languages, including

- **Portability:** Java is an interpreted language that runs on any platform for which the interpreter, the Java Virtual Machine (JVM), is available. This currently includes virtually every major operating system platform, including various flavors of UNIX, Linux, Microsoft Windows, and the Mac OS. The original Java mantra, "Write once, run anywhere," stressed the language's platform-independence and code portability.
- **Reliability:** Certain advanced features of C/C++ such as pointers have been eliminated in Java to reduce the likelihood of hard-to-trace errors from creeping into complex programs. Java also includes new features such as automatic garbage collection to simplify the complex programming task of reserving and releasing memory.
- **Security:** Java uses a "sandbox" model that implements security by running small, downloadable client-side programs called "applets" within a protected area of memory. This prevents hostile applets from adversely affecting users' systems and makes Java an ideal platform for developing dynamic Web applications that run within a user's Web browser.
- **Easy to learn:** Java's syntax is not too different from C/C++, making it relatively easy for developers experienced in these platforms to move to Java.

History

Version 1 of Sun's Java Developer Kit (JDK) was released in 1995 at the company's SunWorld conference. Although a full-featured programming language, this initial release was especially popular with Web developers, who used Java to build applets that could be embedded in Hypertext Markup Language (HTML) pages to enhance the user experience by providing interactive content. With the release of JDK 1.1 in 1997, Sun added support for database connectivity and other features that made Java a more powerful and attractive programming environment for developing server-side applications.

JDK 1.2 was released in 1999, and incorporated the Java Foundation Classes (JFC) into Java's core run-time libraries. JDK 1.2 also provided a number of other enhancements that made Java a more scalable and secure platform. As a result of these improvements, Sun renamed the platform Java2 with this release of the JDK. Later in 1999, Sun made the Java2 platform available to developers in three versions: Java2 Standard Edition (J2SE), Java2 Enterprise Edition (J2EE), and Java2 Micro Edition (J2ME). These editions are discussed in the Implementation section of this article.

The current release of Java is the JDK 1.3 version of Java2. The Java specification is currently controlled by Sun through its Java Community Process (JCP) initiative.

Uses

Although Java was originally designed for developing full-fledged enterprise applications, much of its initial appeal came from its ability to create applets that could be downloaded from Web sites by browsers. These applets would then run on the browser to provide interactive elements such as advanced user interfaces and exciting display elements such as rotating ad banners and animated stock tickers.

As Java has grown to include more enterprise features such as database connectivity and server-side execution elements, it has evolved into a popular platform for the development of commercial e-business applications that is widely used in today's enterprise and business world.

Architecture

When you write an application (or applet) in Java, the Java compiler takes your source code (which is usually saved with the extension .java) and compiles it into something called bytecode. Bytecode is not true machine code—it is a set of generic instructions that are not specific to any particular hardware platform or operating system. Bytecode files generally have the extension .class and are referred to as class files. The following is a simple example of a Java application called HelloThere.java:

```
Class HelloThere {
  Public static void main (String args[]) {
    System.out.println("Hello there");
  }
}
```

The HelloThere.java program defines a new class called HelloThere and contains only one method: main(). When this program is compiled into the class file HelloThere.class and then run, it displays the text "Hello there" on the screen (the standard output device).

To run the application (class file), you must have a bytecode interpreter called a Java Virtual Machine (JVM) on the system. The JVM reads your application's bytecode and executes it by converting each bytecode instruction into a machine-native instruction or set of instructions. This translation process takes place regardless of whether the particular piece of bytecode has been previously executed. If the application is an applet, the Web browser that accesses it must have a JVM installed. The use of a bytecode interpreter instead of a "true" compiler, which generates platform-specific machine code, means that applications written in Java are often slower than those written in C or C++, but the ease of development and portability of code offset these disadvantages in most cases. To obtain additional functionality, you can link native code to Java applications.

The JVM has special security features built into it to ensure that any malicious Java applet downloaded from the Internet cannot perform any harmful actions on the user's system. In this sense, you can consider the JVM running in the Web browser a "sandbox" that allows the applet to execute safely while preventing access to certain items, such as the client machine's file system.

Implementation

The Java2 specification is currently available from Sun in three different developer platforms:

- **Java2 Standard Edition (J2SE):** This includes the standard java.* packages, the Java Foundation Classes (JFC), the Abstract Window Toolkit (AWT) application programming interfaces (APIs) used for developing graphical user interfaces (GUIs), and other basic elements of the Java platform. J2SE is intended primarily as a platform for developing applets for Web sites.
- **Java2 Enterprise Edition (J2EE):** This edition has pushed Java into the forefront of enterprise application development by providing advanced features for development of server-side applications. J2EE includes advanced Java components such as Enterprise JavaBeans (EJB), Java Database Connectivity (JDBC), Java Server Pages (JSP), Java Servlets, and more. Some of these components of Java are further discussed later in this article.
- **Java2 Micro Edition (J2ME):** This version has a small footprint designed for developing applications for devices having limited processing power, memory, and display capability. Examples of devices where J2ME can be used include cell phones, Personal Digital Assistants (PDAs), pagers, smart cards, and embedded systems such as industrial control systems and intelligent sensors.

Some other key Java terminology includes the following:

- **Enterprise JavaBeans (EJB):** A component architecture for developing transactional server-side Java applications. EJBs can be either self-contained programs or small portions of programs and can be used as building blocks for building more complex Java applications. EJB is currently in version 1.1 (the EJB 2 specification is being developed) and is the Java counterpart of the Microsoft technology called Component Object Model (COM).
- **Java Foundation Classes (JFC):** Also known as Swing, these classes are building blocks for creating interfaces for Java applications.
- **Java Database Connectivity (JDBC):** This component provides standard APIs for connecting Structured Query Language (SQL) databases to Java applications. JDBC is currently in version 2 and is the counterpart of the Microsoft technology known as Open Database Connectivity (ODBC).

Marketplace

Java2 Micro Edition (J2ME) is emerging as a popular platform for developing distributed applications for the next generation of third-generation (3G) cellular communication systems. A consortium of over 20 industry partners, including Sun, Ericsson, Motorola, Nokia, and Siemens, has developed the Mobile Internet Device (MID) profile, a platform for developing interactive mobile services that is based on J2ME. The J2ME platform complements the existing Wireless Application Protocol (WAP) platform and uses WAP as its underlying transport mechanism. Motorola's iDEN handset was the first commercially available mobile device compliant with the J2ME specification. A popular platform for creating J2EE applications is Code Warrior from Metrowerks.

Java in the enterprise has recently been furthered by Sun's new Java Web Start (JWS) platform. JWS simplifies the deployment of applications developed with Java 2 Enterprise Edition (J2EE) to network clients. This is done packaging all the various components of a Java application into a Java Archive (JAR) file, which can be downloaded and installed on client machines through a simple click of a link on a Web page. JWS also automates the process of upgrading Java applications on client machines, lowering the costs of deploying and managing Java desktop applications across an enterprise.

Prospects

Java has established itself in the enterprise market and is widely used for developing server-side applications for e-business. The Java community includes more than 2.5 million developers, a tribute to the platform's ease of use and reliability. On the client side, however, the original expectation of Java transforming the Internet through dynamic interactive content has faded somewhat. The biggest prospect for Java's future is likely to be in the embedded device field, where it competes with platforms such as Wireless Markup Language, QUALCOMM's Binary Runtime Environment for Wireless (BREW), and Microsoft Corporation's Windows CE. In the near future, Java is likely to find its main competition to be Microsoft's new .NET platform with its powerful C# programming language.

For More Information

Visit Sun Microsystems Java site at *java.sun.com.*

See Also: *C#, Java Database Connectivity (JDBC), Java Server Pages (JSP), .NET platform*

Java Database Connectivity (JDBC)

A data access interface developed by Sun Microsystems that allows Java applications to access information stored in databases.

Overview

The Java Database Connectivity (JDBC) application programming interface (API) is a standard component of Java 2 Enterprise Edition (J2EE) development platform. The JDBC API specifies a set of Java classes that represent database connections, Structured Query Language (SQL) queries and their result sets, and other objects associated with accessing databases. Multiple drivers for JDBC exist that allow access to different database formats, and the JDBC drivers themselves can be implemented either within applets or as native methods on the operating system. JDBC also supports drivers that act as a bridge between Open Database Connectivity (ODBC) and JDBC. This type of driver translates JDBC function calls into native ODBC calls, but this bridge cannot be run by distrusted applets within a Web browser environment.

Notes

JDBC is to the Java platform what ODBC is to Microsoft Windows.

See Also: *application programming interface (API), Java, open database connectivity (ODBC), Structured Query Language (SQL)*

Java Online Analytical Processing (JOLAP)

A Java-based interface for online analytical processing (OLAP) databases.

Overview

Java Online Analytical Processing (JOLAP) provides an interface for accessing, storing, and managing metadata stored in OLAP databases. JOLAP is intended to provide a uniform, platform-independent method for allowing clients to interact with OLAP servers. Just as the Java Database Connectivity (JDBC) specification allows data stored in relational databases to be accessed using Java, JOLAP provides similar functionality for accessing metadata stored in OLAP systems.

The JOLAP specification is an initiative of a company called Hyperion and is backed by an industry consortium that includes IBM, Oracle Corporation, and Sun Microsystems.

Notes

Microsoft Corporation's own specification for accessing OLAP systems is known as OLE DB.

See Also: *OLE DB, online analytical processing (OLAP)*

JavaScript

A scripting language developed for the Web by Netscape.

Overview

JavaScript is a cross-platform, object-based scripting language that is similar to C but much simpler in syntax. JavaScript was developed by Netscape Communications (now just Netscape) and built into the Netscape Navigator Web browser version 2 and later. JavaScript enables Web developers to produce Web pages with dynamic functionality such as animated graphics, browser detection, cookies, scrolling text, form handlers, and authentication without needing to write or invoke Common Gateway Interface (CGI) applications. JavaScript can be used to develop both client and server applications, but it is usually run on the client Web browser.

The European Computer Manufacturers Association (ECMA) based its ECMA-262 standard upon both Netscape's JavaScript 1.1 and Microsoft's JScript 2 scripting languages. This ECMA-standardized scripting language is known as ECMAScript, and JavaScript 1.5 fully complies with the ECMA 262 standard.

Examples

JavaScript scripts are placed in standard Hypertext Markup Language (HTML) files using special tags. Here is a simple example:

```
<HTML>
<HEAD><TITLE>Javascript Test</TITLE></HEAD>
<BODY>
<H1>Knock Knock</H1>
<SCRIPT LANGUAGE="JavaScript">
alert("Who's there?");
</SCRIPT>
</BODY>
</HTML>
```

The <SCRIPT> and </SCRIPT> tags identify and contain the actual JavaScript script. When this page is loaded into a Web browser such as Netscape Navigator version 3, the browser reads the script and interprets it, causing an alert dialog box to be displayed with the message "JavaScript Alert: Who's there?" and an OK button that closes the dialog box when clicked.

Notes

JavaScript is not the same as Java, which is an object-oriented programming language. A syntactically similar scripting language called JScript is supported on Microsoft Internet Explorer.

See Also: *Java, JScript, scripting*

Java Server Pages (JSP)

A technology from Sun Microsystems for creating dynamic Web applications.

Overview

Java Server Pages (JSP) is a Java-based technology that is part of the Java 2 Enterprise Edition (J2EE) specification from Sun Microsystems. JSP can be used to write server-side Web applications that dynamically generate Hypertext Markup Language (HTML) pages when accessed through a Web browser. Like the underlying Java programming environment on which it is based, JSP is a platform-independent, vendor-neutral development architecture that provides full access to Java's features, including standard Java APIs, Java servlets, and Java Database Connectivity (JDBC).

JSP also complements another Java server-side Web programming architecture called Java Servlets. Using JSP, you can include portions of Java code within an HTML page to call external Java components from the page. Java supports both tag-based programming similar to that used by Macromedia's Cold Fusion platform and embedded script blocks such as those used by Microsoft Corporation's Active Server Pages (ASP) platform.

Architecture

JSP separates the presentation (the display of HTML pages) layer from the business logic layer, simplifying the process of creating portable, scalable Web-based applications. JSP has a simple syntax that can be used to write applications that run on Web servers and dynamically generate Web content in response to requests from Web browsers. An example of a simple "Hello World" application written in JSP might be as follows:

```
<HTML>
<HEAD><TITLE>Sample JSP Application</TITLE>
</HEAD>
<BODY>
<%
String guest = request.getParameter("name");
if (guest == null) guest = "World";
%>
Hello <%= guest %>
</BODY>
</HTML>
```

In this example, a form on a Web page could request the user to input his or her name, which would then be passed as a parameter to the JSP application on the Web server. For example, if the user's name is Mary and the form uses the GET method, the Name parameter would be passed to the JSP application (which might be called Hello.jsp) by appending it to the URL, for example:

```
http://www.microsoft.com/JSPtest/
Hello.jsp?name=Mary
```

The client-side browser would then display a simple dynamically generated Web page that says "Hello Mary." If the user instead submitted the form without specifying a name, the browser would display simply "Hello World."

Marketplace

JSP has established itself as a popular platform for developing dynamic Web applications. As a server-side development platform, JSP competes in the commercial and enterprise environments with many similar platforms, including Macromedia's Cold Fusion, Personal Home Pages (PHP), the CGI/PERL combination popular in the UNIX world, and Microsoft Corporation's ASP platform.

For developers who want to create JSP applications, a variety of integrated development environments (IDEs) is available, including JRun and DreamWeaver UltraDev from Macromedia, and WebGain Studio from WebGain.

See Also: *Active Server Pages (ASP), Hypertext Markup Language (HTML), Java*

JBOD

Stands for "just a bunch of disks" and refers to an unstructured high-capacity disk-storage system.

Overview

A JBOD is essentially just an array of disks connected to a common backplane and arranged within an enclosure. The disks within the JBOD are usually controlled by an attached server called the host server, which may manage them as independent volumes or combine them into logical volumes in any way desired. JBODs are used anywhere a large amount of storage capacity is required but do not provide the fault tolerance of redundant array of independent disks (RAID) systems.

JBODs are more difficult to manage than Storage Area Networks (SANs) and Network Attached Storage (NAS) systems. As they rapidly expand their network, companies often implement JBODs without planning, creating storage management headaches for administrators. On the plus side, JBODs are cheaper to implement than SANs and can quickly provide additional network storage when needed.

Architecture

There is no one standard JBOD architecture. In its simplest form, a JBOD can be constructed by chaining together a series of external Small Computer System Interface (SCSI) disk drives, removable Jaz drives, optical drives, or any mixture of drives. In enterprise environments, Fibre Channel JBODs are more common; they generally have dual-loop DB9 copper interfaces and can be connected easily to a Fibre Channel hub or switch to provide additional network storage. Fibre Channel JBODs typically range from small 8-disk enclosures to large rackmount form factors that include several hot-swappable modules, each of which may contain 20 or more disks.

See Also: *Fibre Channel, network attached storage (NAS), Small Computer System Interface (SCSI), storage, storage area network (SAN)*

JDBC

Stands for Java Database Connectivity, a data access interface developed by Sun Microsystems that allows Java applications to access information stored in databases.

See: *Java Database Connectivity (JDBC)*

Jet

Stands for Joint Engine Technology, a database engine technology used in various Microsoft products.

See: *Joint Engine Technology (Jet)*

Jini

An on-demand networking architecture developed by Sun Microsystems.

Overview

Jini is designed to provide a simple way of spontaneously creating networks without the need to install drivers or configure network parameters. It provides an underlying infrastructure that allows a wide range of devices to connect to one another as needed to perform specific tasks. Jini devices can automatically discover, recognize, and form federations or communities with one another spontaneously without user intervention. Jini devices are always on and establish impromptu networks as needed. Jini can be implemented on a wide range of devices, including not only computing platforms such as PCs, Personal Digital Assistants (PDAs), and cell phones, but also VCRs and DVD players, stereo systems, copiers, thermostats, and security systems.

Jini is based on Java technology from Sun and can be implemented on any device running the Java Virtual Machine (VM). Java is the key enabler of Jini technology, and, like Java, is a fundamental component of the Sun Open Network Environment (Sun ONE) initiative.

Architecture

Jini's basic underlying architecture involves two components:

- **Services:** These are Jini-enabled devices that can provide resources to other Jini-enabled devices and can include core system services such as Java's VM, JavaBeans component technology, Java Naming and Directory Interface (JNDI), Java's Remote Method Invocation (RMI), and other services. Jini also supports other services, including a discovery and join-in protocol to enable clients to locate Jini services, distributed security services to manage user rights and privileges, database services, distributed garbage collection, and more.
- **Clients:** These are Jini-enabled devices that can find, request, and lease services from other Jini-enabled devices. Clients lease services for a specific task and for a limited time until the task is completed and then release the resource for other clients to use.

Jini uses a distributed architecture in which no single central server is needed. Jini devices can federate to form spontaneous communities without the need to have a central PC controlling them. For example, a Jini-enabled PDA and cell phone could communicate with each other when the user accesses the cell phone to dial a phone number. The cell phone could automatically network with the PDA using Jini to look up the phone number.

For More Information

Find out more about Jini at *www.sun.com/jini*.

See Also: *Java*

jitter

Distortion in transmission that occurs when a signal drifts from its reference position.

Overview

Jitter is inherent in all forms of communication because of the finite response time of electrical circuitry to the rise and fall of signal voltages. An ideal digital signal would have instantaneous rises and falls in voltages and would appear as a square wave on an oscilloscope. The actual output of a digital signaling device has finite rise and fall times and appears rounded when displayed on the oscilloscope, which can result in phase variation that causes loss of synchronization between communicating devices.

Jitter can also be caused by variations in the timing or the phase of the signal in an analog or digital transmission line. In this instance, jitter can be caused by poor connectors, malfunctioning repeaters, transient problems in switches, and variations in transmission characteristics of cabling. Jitter typically results in a loss of data because of synchronization problems between the transmitting stations, especially in high-speed transmissions. The goal in designing a transmission device is to ensure that the jitter remains within a range that is too small to cause appreciable data loss.

Jitter is different from a related concept called delay. Delay is the amount of time for a signal to reach its destination, but jitter represents unevenness in delay. For example, when you download a file from the Internet using File Transfer Protocol (FTP), the delay between transmission of packets from the FTP server to the client is typically several hundred milliseconds, but, due to jitter in the connection, the first half of the file may download much more quickly than the last half.

Jitter is particularly annoying in multimedia communications involving audio or video streaming. Jitter can render a communication unintelligible, and it can cause dropouts unless buffering is used to prevent them. Buffering introduces delay, however, and although this may be acceptable in one-way streaming transmission, it is unacceptable in two-way communications.

See Also: *noise, latency, signal*

join

A database operation that allows you to retrieve and modify data from more than one table at a time using a single Structured Query Language (SQL) SELECT statement.

Overview

You can use the Microsoft Query Analyzer tool for Microsoft SQL Server to graphically create joins for transact-SQL queries that join two or more tables or join a table to itself. Joins are a necessity because a single table might not provide all the information you want to retrieve about a specific database entity. By connecting tables using joins, you can retrieve information that resides in more than one table in a single operation.

You can create three kinds of joins:

- **Inner joins:** Connect two tables to form a result set that contains only the matching rows that satisfy the join condition. Inner joins can be equijoins or natural joins.
- **Cross or unrestricted joins:** Produce a result set that contains all combinations of all rows from the tables that are joined. A cross join between a table of 5 rows and another table of 4 rows creates a result set of 20 rows.
- **Outer joins:** Maintain information that does not match the join condition. For example, a left outer join contains at least all rows from the first table.

Notes

There are two kinds of syntax for creating joins, ANSI join syntax and SQL Server join syntax. You can use only one of these types of syntax in a given SELECT statement.

See Also: *database, Structured Query Language (SQL)*

Joint Engine Technology (Jet)

A database engine technology used in various Microsoft products.

Overview

Jet is an advanced 32-bit multithreaded database engine developed by Microsoft Corporation in 1992. The Jet database engine is employed in several Microsoft products, including Microsoft Exchange, Microsoft Access, Microsoft Visual Basic, and Active Directory directory service for Microsoft Windows 2000. The Jet engine is not available as a separate product.

Architecture

The Jet database engine employs transaction logs to track and maintain information and provide fault tolerance. Native Jet database files usually have the extension .mdb. Jet databases can be accessed using Data Access Objects (DAO) and open database connectivity (ODBC). DAO provides the Component Object Model (COM) interface for accessing indexed sequential access method (ISAM) databases such as Microsoft FoxPro, dBASE, or Paradox through Jet. Jet databases are best accessed through DAO (rather than ODBC) because they expose only a limited amount of functionality to ODBC drivers. Jet cannot use ODBC to build queries that use server-side cursors, and it has limited capability for stored procedures and multiple result sets.

See Also: *Component Object Model (COM), Data Access Objects (DAO), Exchange Server, open database connectivity (ODBC)*

JOLAP

Stands for Java Online Analytical Processing or Java OLAP, a Java-based interface for OLAP databases.

See: *Java Online Analytical Processing (JOLAP)*

JScript

Microsoft Corporation's implementation of the ECMA-Script standard.

Overview

JScript is an interpreted object-based Web scripting language originally developed as Microsoft's counterpart to Netscape's JavaScript scripting language. JScript was designed to allow Web developers to easily add dynamic, interactive content to static Hypertext Markup Language (HTML) pages.

JScript is a superset of the ECMA-262 specification, a standard for cross-platform, vendor-neutral scripting languages developed by the European Computer Manufacturers Association (ECMA). JScript complies with the ECMAScript standard and includes advanced features that make it a powerful scripting tool for the Microsoft Windows platform. In particular, JScript allows Component Object Model (COM) objects such as ActiveX controls to be called from within scripts and executed using the Windows Scripting Host (WSH), enabling the full power of the Windows operating system to be accessed.

Architecture

JScript is an interpreted programming language that is executed at run time. JScript files use the extension .js to identify themselves to WSH for execution. JScript supports standard programming elements such as statements, variables, constants, operators, conditionals, loops, functions, and arrays. It also supports a limited number of objects and methods. JScript supports six different data types including the variant data types. The language is thus loosely typed, meaning you do not have to declare a variable's data type before you use the variable. JScript has limited file input/output (I/O) features.

You can execute scripts written in JScript in several ways:

- By double-clicking on a shortcut to a .js file and executing them directly using the WSH
- By running them from the command line using the WSH
- By embedding them into HTML pages using <SCRIPT> tags

In the third scenario above, JScript is typically used to add functionality to HTML files stored on a Web server. When a Web browser such as Microsoft Internet Explorer accesses a page containing an embedded block of JScript script, it downloads the block of script and executes it locally on the client machine. Internet Explorer can do this because it has a built-in scripting engine that can understand and interpret scripts written in JScript and Microsoft Visual Basic, Scripting Edition (VBScript).

Examples

The following is a simple example of an embedded script written in JScript. The script is embedded in an HTML page between the <SCRIPT> and </SCRIPT> tags and displays a confirm message box when the user opens the file using Internet Explorer. When the user makes a selection, the remaining portion of the page loads.

```
<HTML>
<BODY>
<H1>Welcome to our restaurant!</H1>
<HR>
<SCRIPT>
var testing=window.confirm("Click OK for food,
Cancel for drink.");
if (testing) {
    window.alert("Hot dog");
} else window.alert("Beer");
</SCRIPT>
<H1>Thanks for coming!</H1>
</BODY>
</HTML>
```



C:\test.htm - Microsoft Internet Explorer
File
Edit
View
Favorites
Toc
Address
C:\test.htm
Go
Microsoft Internet Explorer
OK
Cancel
Done
My Computer

Welcome to our restaurant!

Click OK for food, Cancel for drink.

JScript. *A dialog box created using JScript.*

Notes

Unlike its cousin VBScript, JScript is a case-sensitive language.

For More Information

Visit the Microsoft Windows Script Technologies site at *msdn.microsoft.com/scripting.*

You can find the ECMA-262 specification at *www.ecma.ch/stand/ecma-262.htm.*

See Also: *JavaScript, scripting, Windows Script Host (WSH)*

JSP

Stands for Java Server Pages, a technology from Sun Microsystems for creating dynamic Web applications.

See: *Java Server Pages (JSP)*

jumbo frames

A feature of Gigabit Ethernet (GbE) that allows frames up to 9 kilobytes (KB) in size.

Overview

Standard 10Base5 Ethernet, created in the early 1980s, supports frames up to 1.5 KB in length. This standard has been supported by all subsequent versions of Ethernet, including 10BaseT Ethernet, Fast Ethernet, and GbE. Unfortunately, for the speeds of 1 gigabit per second (Gbps) supported by GbE, these standard frames become inefficient, and better performance can be achieved at these speeds by using larger frames. Consequently, the designers of the 802.3z GbE standard included support for jumbo frames as an option for gigabit networking.

Implementation

Jumbo frames can have payloads up to 9 KB in length and can result in much higher network utilizations for activities such as file transfers, where utilization of over 80 percent is achievable when using jumbo frames compared to typically under 20 percent when using standard Ethernet frames. Unfortunately, using jumbo frames adds issues of interoperability for enterprise networks, as these frames are not supported by slower 10 and 100 megabits per second (Mbps) versions of Ethernet. Since performing Layer-2 fragmentation and reassembly of jumbo frames is not a desirable solution, two standard methods are generally employed to incorporate GbE jumbo frames into typical enterprise networks:

- Dedicating all downstream traffic on specific ports of core GbE switches to devices supporting jumbo frames, such as GbE workgroup switches or server-switch interconnects
- Employing 802.1q virtual LANs (VLANs) to logically segregate those portions of the network that use jumbo and standard Ethernet frames

While Internet Protocol (IP) can intrinsically support frames of even larger size up to 64 KB (and IPv6 can support frames up to 4 gigabytes [GB] in length!) and using such monster frames could make gigabit networking even more efficient, there is an inherent obstacle to using such large frames. Ethernet uses a 32-bit cyclical redundancy check (CRC) at the end of each frame, and this error correction method is only efficient for frames up to about 12,000 bytes in length. The reason for choosing 9 KB as the maximum length for jumbo frames is to ensure the efficiency of such error correction while making possible the transmission of 8-KB Network File System (NFS) datagrams without the need of fragmentation.

Marketplace

The use of jumbo frames is increasing in enterprise networking environments. Vendors such as Nortel Networks offer autonegotiating 10/100/1000BaseT network interface cards (NICs) that feature support for jumbo frames to make implementing this feature in the enterprise easier.

See Also: *802.3z, Ethernet, Fast Ethernet, frame, Gigabit Ethernet (GbE)*

JXTA

A peer-to-peer (P2P) networking initiative from Sun Microsystems.

Overview

Project JXTA (pronounced “juxta”) is an outgrowth of work by Sun to extend and standardize P2P technology in computer networking. The JXTA architecture is designed to support heterogeneous systems and platforms from all levels, from enterprise servers to handheld personal devices. JXTA is designed to simplify P2P networking by providing a set of general, open protocols for communications between different kinds of devices including PCs, Personal Digital Assistants (PDAs), cell phones, and other devices. The aim of Project JXTA is to explore and advance the new paradigm of distributed computing popularized by the P2P movement.

JXTA is part of the Sun Open Network Environment (Sun ONE) initiative that includes the companion technologies Java and Jini. JXTA technology is licensed from Sun under the Sun Project JXTA Software License, which is based on version 1.1 of the open-source Apache Software License.

For More Information

Find out more about JXTA at *www.jxta.org.*

See Also: *Java, Jini*

K

KCC

Stands for Knowledge Consistency Checker, a feature of the Active Directory directory service that ensures that directory replication properly takes place.

See: *Knowledge Consistency Checker (KCC)*

KDE

Stands for K Desktop Environment, a graphical user interface for Linux.

See: *K Desktop Environment (KDE)*

K Desktop Environment (KDE)

A graphical user interface (GUI) for Linux.

Overview

K Desktop Environment (KDE) provides users with an integrated, graphical, open-source working environment suitable for Linux workstations. KDE is comparable in many ways to the power and functionality of the Microsoft Windows and Mac OS user interfaces. The latest version, KDE2, incorporates a number of applications and utilities that include

- **Konqueror:** A combination file manager and Web browser that features a two-pane tree-and-view similar to Windows Explorer on the Windows platform.
- **Koffice:** A suite of office productivity tools that includes word processing, spreadsheet, presentation, and drawing applications.

Prospects

Although Linux has established itself in the server side of the enterprise market, it has made little headway until now on the desktop. The KDE Project's aim is to promote the use of Linux in the desktop environment in particular. KDE is one of two main GUI environments for Linux, the other being Gnu Object Modeling Environment (GNOME). KDE currently has about 70 percent of the Linux market, and the KDE League is an industry consortium dedicated to promoting KDE on the Linux desktop.

For More Information

Find out more about KDE at *www.kde.org.*

See Also: *GNU Object Modeling Environment (GNOME), Linux*

keepalives

A feature of Hypertext Transfer Protocol (HTTP) version 1.1 that minimizes the number of connections that Web browsers need to make to access content on Web servers.

Overview

When a Web browser that supports keepalives (such as Microsoft Internet Explorer 4 or higher) makes an HTTP GET request to a Web server that supports keepalives (such as Microsoft Internet Information Services [IIS]), the Web browser includes a new "Connection: Keep-Alive" header in the list of HTTP headers that it sends to the Web server in the request. The Web server responds by giving the client the file it requested (usually a Hypertext Markup Language [HTML] page or an image file). After the server sends the file to the client, instead of closing the Transmission Control Protocol/Internet Protocol (TCP/IP) socket, it keeps the socket open for a period of time in case the client wants to download additional files. A typical Web page might include a dozen images, and normally up to four sockets are kept open for transferring files between the client and the server.

Keepalives, which are also known as persistent connections, are supported by both Microsoft Internet Information Services (IIS) and Internet Explorer. Note that keepalives do not work unless both the Web browser and the Web server support them.

Notes

The term *keepalives* also refers to special packets used to keep a TCP connection open on a TCP/IP internetwork.

See Also: *Hypertext Transfer Protocol (HTTP), Internet Explorer, Internet Information Services (IIS)*

Kerberos

A security protocol used for securing access to network services.

Overview

Kerberos was developed in the early 1980s at the Massachusetts Institute of Technology (MIT) by Project Athena, the same group responsible for the X Windows system for the UNIX platform. Kerberos is based on the Data Encryption Standard (DES) and uses security tickets to manage the authentication of users and applications on a network. The Kerberos protocol is defined by RFC 1510 and the security tickets it employs are covered by RFC 1964. The current version of Kerberos (Kerberos v5, or version 5) was developed in 1993.

Kerberos has been used in the UNIX world for some time, and Kerberos v5 is the default authentication protocol used by the Microsoft Windows 2000 network operating system platform. Kerberos is a powerful authentication method that allows mutual authentication of both client and server during an authentication session. This is unlike the earlier Windows NT LAN Manager (NTLM) authentication protocol used on the Windows NT platform. NTLM authenticated clients only; Kerberos is thus more secure, as it authenticates both the client and the server.

Kerberos is a strong authentication protocol suited for implementation in a distributed processing environment. Kerberos also supports delegation, in which one machine can contact another machine on behalf of a client request for authentication. Kerberos shifts the processing load for authentication from the server to the client, making it an efficient authentication method for large enterprises. Kerberos is also a cross-platform standard and can be implemented in heterogeneous networks where multiple operating system platforms are present.

Architecture

Kerberos is named after the mythical three-headed dog (Kerberos in Greek mythology, Cerberus in Roman mythology) that guarded the gates of Hades. This name was chosen because Kerberos requires three different entities to be present in order to operate:

- **Kerberos clients:** These are users, applications, or machines that need to be authenticated in order to access network resources.
- **Network servers:** These are Kerberos-enabled servers hosting the network resources that the Kerberos clients want to access.
- **Key Distribution Center (KDC):** This is a special server that's trusted by both Kerberos clients and network servers and is responsible for issuing Kerberos tickets to clients.

Kerberos uses a ticket-based method for granting a user access to a network service. When a Kerberos-enabled client wants to request a network service (such as network logon) from a Kerberos-enabled server, the client must first contact an authentication server (AS) to receive a ticket and an encryption key. The encryption key, called the session key, is generated using symmetric key encryption and is used to unlock communication between the client and the server and thereby authenticate that communication. The initial ticket, often called the ticket-granting ticket (TGT), contains a copy of the session key and an identity, which is a randomly generated number. The AS passes the TGT and the identity back to the client, which stores the ticket in its ticket cache. When the client wants to access a particular service, it sends the ticket to a ticket-granting server (TGS). (The TGS and AS are usually the same machine.) The TGS gives the client a ticket that securely identifies the client to the service it's requesting. Finally, the client presents the ticket to the network service it's trying to access and is granted access to the resource as many times as desired until the ticket expires. When the client sends a ticket, the ticket is always accompanied by an authenticator message that's encrypted with the session key. This authenticator includes a time stamp, which is used to ensure that the ticket is legitimate.



Kerberos. *The Kerberos v5 protocol defines the steps a client must take to be authenticated for gaining access to network services or resources.*

Implementation

In the Windows 2000 implementation of Kerberos, each domain controller has the Kerberos v5 service running on it. Kerberos client software is also built into each server and workstation running Windows 2000. The Kerberos service maintains encrypted user passwords and identities in the Active Directory directory service database. When a user logs on to a domain controller, the initial Kerberos authentication enables the user to access available resources anywhere in the enterprise because authentication credentials issued by the Kerberos services of one domain are accepted by all domains within a domain tree or a domain forest.

The Kerberos service issues an initial ticket for the logon domain when a user logs on to a Windows 2000 workstation. Any server running Windows 2000 can then validate the client's ticket without having to contact the domain Kerberos service. It can do this because servers running Windows 2000 share the encryption key that the Kerberos service uses to encrypt tickets. This encryption key is called the server key.

If a Windows 2000 client in one domain requests access to a resource in a remote domain that's part of the same domain tree or forest, the Kerberos service in the local domain issues a referral ticket that the client presents to the Kerberos service in the remote domain. The Kerberos service in the remote domain then issues an initial ticket that's valid for its own domain and identifies the domain. Using this ticket, the client can then access resources in the remote domain.

See Also: *authentication protocol, Data Encryption Standard (DES), Windows NT Challenge/Response Authentication*

kernel

The core of an operating system.

Overview

In most operating systems, the kernel is the part that is responsible for low-level (essential) activities such as multitasking, scheduling processes and threads, handling interrupts from devices, memory management, error handling, and managing input/output (I/O) operations. The kernel interfaces with other components of the operating system through system calls, which provide a standard interface to kernel functions. The kernel runs within protected mode memory in order to ensure the operating system's stability.

The term *kernel* is more often used in a UNIX environment and is contrasted with the term *shell*, which describes the outer portion of the operating system that is exposed to the user and provides a user interface for entering commands and receiving output. In Microsoft Windows operating systems, the shell is known as the desktop.

Architecture

The Windows 2000 kernel uses a microkernel architecture. This means that the kernel is a small component with limited functionality that loads other components such as drivers and services into memory only as required to complete requested system tasks. By contrast, a kernel constructed using a monolithic architecture has device drivers and services built right into it (Berkeley Software Distribution [BSD] UNIX follows this architecture).

The kernel for Windows 2000, Windows XP, and Windows .NET Server, called Ntoskrnl.exe, is located in the \Winnt\System32 directory in Windows 2000 and the \Windows\System32 directory in Windows XP and Windows .NET Server. It runs in nonpageable memory, which means that it's always resident in memory. The kernel is responsible for thread scheduling and dispatching threads to processors on a symmetric multiprocessing (SMP) platform. The kernel code itself is not preemptive—that is, no other thread or process can preempt the kernel's operations. Each thread is assigned a priority level from 0 to 31 by the kernel, as follows:

- Levels 0 through 15 indicate dynamic priority and are assigned to application and user threads.
- Levels 16 through 31 indicate real-time priority and are assigned only to key operating system threads.

The kernel adjusts priority levels for threads to ensure that no thread is starved and that each receives proper attention, with threads having a higher priority level getting the greater share of processor resources.

The kernel does its job by managing two classes of objects:

- Control objects, which control the operation of the kernel and include processes, interrupts, asynchronous procedure calls, and profiles
- Dispatcher objects, which manage thread dispatching and synchronization and include events, threads, timers, semaphores, mutants, and mutexes

The kernel communicates with the hardware abstraction layer (HAL) to interact with hardware and communicates with the Executive and its components for higher-level operating system functions. The kernel loads when the screen turns blue during the boot process.

Another example of a microkernel architecture is found in the Linux operating system, which uses device drivers that can be loaded into memory and unloaded from memory as required.

Notes

In Windows 95 and Windows 98, the kernel file is Kernel32.dll, and it's located in the \Windows\System directory. If the kernel is corrupt or missing, you can expand the file from the distribution CD and replace the damaged or missing file on your hard disk (as long as you can access that drive in a way that does not involve this file, such as through MS-DOS).

See Also: *desktop, hardware abstraction layer (HAL), kernel mode, shell*

kernel mode

A privileged mode of operation in which processes can execute within the Microsoft Windows 2000 operating system.

Overview

Kernel mode processes include components of the operating system that directly manage resources on the computer, such as the following:

- Windows 2000 executive, which contains operating system modules that manage objects, processes, security, memory, and devices
- The kernel, which manages core operating system services
- The hardware abstraction layer (HAL), which isolates operating system code from hardware differences


DOS/Win16 application
POSIX application
Win32 application
NTVDM
OS/2 application
Logon process
User mode
POSIX subsystem
Win32 subsystem
OS/2 subsystem
Security subsystem
Windows NT executive
Executive services
System services
I/O Manager
Object Manager
Security Reference Monitor
Process Manager
Local Procedure Call Facility
Virtual Memory Manager
Win32 Window Manager & GDI
Kernel mode
Microkernel
Hardware device drivers
Hardware abstraction layer (HAL)
Graphic device drivers
Hardware

Kernel mode. *Kernel mode of the Windows 2000 operating system architecture.*

Notes

Kernel mode is also known as supervisor mode, protected mode, or Ring 0.

See Also: *user mode*

keyboard emulator

A device that can be plugged into the keyboard port of a server to emulate the presence of a connected keyboard.

Overview

When a power outage causes the server to reboot, the server detects the presence of a keyboard and the reboot is allowed to occur. This is important when administrators are off site when servers need to be rebooted, because computers normally do not boot unless a keyboard is attached.

A keyboard emulator is used as a security device when the presence of an attached keyboard is not desirable, such as when the servers are in an unlocked room or can be tampered with in some other fashion. By removing the keyboard and installing a keyboard emulator, you can prevent unauthorized users from attempting a local logon to a server.

Keyboard Video Mouse (KVM) switch

A device that allows several computers to be controlled from a single keyboard, mouse, and monitor.

Overview

Keyboard Video Mouse (KVM) switches are typically employed in the enterprise to managed server farms, which are collections of rack-mounted servers grouped together for various purposes. They are also used in help desk environments and in data centers where large numbers of computers need to be centrally managed by a few people.

Using a KVM switch to control multiple computers has several advantages over using a separate keyboard, mouse, and monitor for each machine, specifically:

- Savings on the cost of additional keyboards, mice, and monitors. This includes both purchase costs and the cost of electricity to operate the monitors.
- Lessening the chance of equipment failure by reducing the amount of heat generated through elimination of unnecessary monitors (and thus also lowering air conditioning costs in equipment rooms).
- Preventing equipment clutter in already crowded server rooms.

KVMs typically support two, four, eight, or more computers and can often be daisy-chained to support hundreds—or even thousands—of computers.

Types

The simplest KVMs are manual switches that employ push buttons for switching between different computers. These analog switches are cheap, but the peripherals tend to become unsynchronized with the computers, often requiring a reboot to correct things.

More commonly, commercial KVMs employ electronics to switch between different machines, typically by using keyboard shortcuts or through an on-screen menu. The menu may also include some form of password protection for each computer and a master password that grants access to all computers attached to the switch. The switch is typically connected to the keyboard, mouse, and video ports on the computers using proprietary cables purchased with the switch. A single keyboard, mouse, and monitor are then connected to the switch to control the various machines. KVM switches generally send analog signals all the time to all connected computers in order to give each computer the illusion that it has a directly connected keyboard, monitor, and mouse. Keyboard signals are most important, for Intel PCs in particular require a keyboard signal in order to reboot.

Sometimes the computers that need to be controlled are located in another part of the building in a special "clean room" or other secure location. In this case, use an analog KVM switch with a built-in video extender, which amplifies the video signal so that the monitor can be connected to the computer using a cable that's 500 feet (150 meters) or longer. You actually need two video extenders, one at the server end and one at the remote monitor station. Video extenders can often be connected using a single interconnect line of Category 5 (Cat5) cabling.



Keyboard Video Mouse (KVM) switch. *Using a KVM switch to control several servers from a single keyboard, monitor, and mouse.*

Marketplace

A number of companies make KVM switches for various markets from small businesses to enterprise data centers. Some popular vendors include Avocent Corporation, Black Box Corporation, Rose Electronics, and Tron International.

A recent development is the digital KVM switch, whose operation resembles remote control software such as pcAnywhere but allows you to manage servers running any operating system. Digital KVM switches work by converting analog keyboard, video, and mouse signals into digital signals, which are then packaged in Internet Protocol (IP) packets and transmitted over a network. They can be used to control hundreds of computers at different locations and can even operate over the Internet. Instead of controlling the computers from a keyboard/mouse/monitor combination, they are instead controlled from a central management workstation that has special software installed on it.

When deploying a digital KVM switch, the management workstation controls the remote servers over a standard Ethernet local area network (LAN) or wide area network (WAN) connection, which can be configured in either of two ways:

- **In-band management:** This method employs the existing LAN on which the servers reside for sending control signals to the servers. The disadvantage of this method is that if the network goes down, you have no way of controlling the servers.
- **Out-of-band management:** This method employs a separate maintenance LAN for controlling the servers. The advantage here is that you can manage the servers even when the regular LAN or WAN connection is down, but the disadvantage is that you have to deploy a separate Cat5 wiring infrastructure to make this possible, which can incur considerable extra cost.

The first commercially available digital KVM switch was the DS1800 from Avocent. This market is likely to grow over the next several years, driven by demand mainly from Internet data centers and e-commerce companies.

See Also: *out-of-band management (OBM), switch*

key (cryptography)

A mathematical value used in cryptography for encrypting and signing messages.

Overview

The degree of security of a key depends on the type of mathematical algorithm used with the cryptosystem and the length of the key. Most cryptography algorithms employ transformations that use prime numbers and congruency. Key lengths typically range from 40 bits for the RC2 and RC4 cryptography algorithms to 512 bits for RSA public key systems.

The number of keys used depends on the kind of cryptographic system being employed. In secret (or symmetric) key cryptography, both the sender and the recipient use the same key for encrypting and decrypting messages. By contrast, public key cryptography employs a key pair that consists of the private and public keys of the message sender. In a public key system, these keys are usually obtained from a certificate authority (CA). This is accomplished by having the user submit a key request file, such as one generated by the Key Manager component of Microsoft Internet Information Services (IIS).

See Also: *encryption, key pair, public key cryptography*

key (database)

A column or group of columns used to uniquely identify records in a table of a relational database.

Overview

Two main types of keys are used in relational databases such as Microsoft SQL Server:

- **Primary keys:** These are columns or groups of columns that uniquely identify the rows of a table. Each row has a unique value in the primary key column or columns. Each table in a relational database should have one and only one primary key, and primary keys cannot allow nulls (NN), duplicates (ND), or no changes (NC).
- **Foreign keys:** These are columns or groups of columns in one table that match the primary key of a different table. Foreign keys are used to define relationships between tables and to enforce referential integrity in a database by ensuring that each value in the foreign key column is actually a valid entry in the primary key column of another table.

Note that a column in a database table can be both a primary key for its own table and a foreign key for a different table.

See Also: *database*

key management

A method for managing private keys within a public key infrastructure (PKI).

Overview

Key management is an essential function of any PKI system. This is because private keys issued to users must be kept secure and confidential to protect the PKI system's integrity. Should a user's private key be compromised, various consequences could result, depending on the privileges of the user within the enterprise, including the following:

- The user's reputation could be damaged by an impersonator sending harassing mail signed with the user's private key.
- Data could be stolen or other damage could be done if the user has high-level privileges on the network.
- Agreements could be signed without proper consent should the user have signing authority using his private key.

Implementation

The essential requirement for securely managing users' private keys is to make sure that these keys are stored in only one location and that no copies exist anywhere else. While many PKI implementations are software-based systems in which keys are stored on computers' hard disks, a better solution is hardware-based key management. A good example of this is smart cards, which you can use to store a single existing copy of a user's private key in a tamper-proof format. Besides secure key storage, another important aspect of key management is secure delivery of generated keys to their users.

See Also: *key (cryptography), public key cryptography, public key infrastructure (PKI), smart card*

key pair

A pair of keys generated for an individual, system, or organization within a public key cryptography system.

Overview

Public key systems always generate keys in pairs that consist of a private and a public key. The private key belongs to the user alone and must be kept secret and carefully guarded. Should a user's private key be compromised, it must immediately be revoked. Otherwise, the user's identity could be forged for e-mail, document signing, and other purposes, damaging the user's reputation and hurting the company.

By contrast, a user's public key is available to anyone who requests it. If a message is encrypted with someone's private key, it can be decrypted by the message recipient using the sender's public key. This is possible because each pair of private and public keys is bound together by a specific mathematical relationship.

See Also: *encryption, key (cryptography), public key cryptography*

key (registry)

An entity within the Microsoft Windows registry that can contain subkeys and values.

Overview

Registry keys are used to name and identify collections of registry values and to organize the registry into a hierarchical structure. Registry keys are thus analogous to directories in a file system; in fact, keys are displayed as folders by the Registry Editor just as directories are displayed in Windows Explorer.



```
CurrentUser : REG_SZ : USERNAME
SystemStartOptions : REG_SZ :
WaitToKillServiceTimeout : REG_SZ : 600000
```

Key (registry). *The Control key as displayed by the Windows 2000 Registry Editor (Regedt32.exe).*

The screen capture shows the Control key being displayed, which contains value entries (in the right pane) and subkeys (the series of items under it in the left pane). The Control key itself is a subkey of the CurrentControlSet key.

See Also: *hive, registry*

KM

Stands for knowledge management, a business strategy for using software to make all the knowledge contained in an enterprise easily accessible.

See: *knowledge management (KM)*

Knowledge Consistency Checker (KCC)

A feature of Active Directory directory service that ensures that directory replication takes place properly.

Overview

The Knowledge Consistency Checker (KCC) is an Active Directory process running on each domain controller within a Microsoft Windows 2000 network. The KCC generates a map of the replication topology for the network, enabling domain controllers to find and replicate with each other efficiently in order to ensure that information within Active Directory is up-to-date everywhere throughout the enterprise.

Implementation

The KCC is implemented as a dynamic-link library (DLL) that runs in the background every 15 minutes to generate and maintain the replication topology. Should a domain controller become unavailable for any reason, the KCC detects this change and modifies the topology to ensure that replication still takes place effectively and all domain controllers in the forest are properly synchronized.

The KCC manages the replication topology by creating connection objects between domain controllers. Replication topology is established at two different levels: forest-wide and domain-wide. Although the KCC runs automatically in the background and has no user interface, you can manually force the KCC to update the replication topology by using the Active Directory Sites and Services console. You might do this, for example, when you take down a DC for maintenance.

See Also: *Active Directory, Active Directory Sites and Services, directory replication (Windows 2000 and Windows .NET Server), domain controller*

knowledge management (KM)

A business strategy for using software to make all the knowledge contained in an enterprise easily accessible.

Overview

Knowledge management (KM) is used to refer both to a business goal and to various software applications used to reach this goal. KM's goal is to provide mechanisms for searching, retrieving, and analyzing all the different kinds of information found in today's commercial enterprise. These sources of information can include relational databases, file servers, e-mail servers, intranet and corporate Web sites, Enterprise Resource Planning (ERP) applications, Customer Relationship Management (CRM) applications, and other repositories of business information.

The first applications that performed limited KM functions were corporate portals, which focused mainly on consolidating databases, documents, and Web pages to make them easily accessible. Over the last few years, these portals have evolved into a new type of tool, the Enterprise Information Portal (EIP), which provides access to information stored in ERP and CRM systems. EIPs, however, have difficulty managing unstructured data such as documents stored on file servers and e-mail servers. As a result, a new type of portal has evolved called the Enterprise Knowledge Portal (EKP), which not only can consolidate information from both structured and unstructured sources but also can employ user profiles to dynamically push data to users who need it. EKPs employ Business Intelligence (BI) software that can turn raw corporate data into helpful knowledge upon which companies can base business decisions.

See Also: *Enterprise Information Portal (EIP), Enterprise Knowledge Portal (EKP), enterprise resource planning (ERP), intranet, portal, Web server*

KVM switch

Stands for Keyboard Video Mouse switch, a device that allows several computers to be controlled from a single keyboard, mouse, and monitor.

See: *Keyboard Video Mouse (KVM) switch*

L

L2CAP

Stands for Logical Link Control and Adaptation Layer Protocol, the data-link layer protocol for Bluetooth wireless networking.

See: *Logical Link Control and Adaptation Layer Protocol (L2CAP)*

L2F

Stands for Layer 2 Forwarding, a media-independent tunneling protocol developed by Cisco Systems.

See: *Layer 2 Forwarding (L2F)*

L2TP

Stands for Layer 2 Tunneling Protocol, a wide area network (WAN) protocol used for virtual private networking (VPN).

See: *Layer 2 Tunneling Protocol (L2TP)*

L2TP/IPsec

Stands for Layer 2 Tunneling Protocol (L2TP) over Internet Protocol Security (IPsec), which is the normal way of using L2TP for creating secure virtual private networks (VPNs).

See: *Layer 2 Tunneling Protocol (L2TP)*

LADC

Stands for Local Area Data Channel, a telco service for transmitting data using line drivers.

See: *Local Area Data Channel (LADC)*

lambda switching

An emerging optical switching technology.

Overview

Lambda switching is an emerging technology that represents the next stage in the development of high-speed switched optical networks. Lambda switching uses a combination of dense wavelength division multiplexing (DWDM), multiprotocol label switching (MPLS), and Resource Reservation Protocol (RSVP) to automatically connect the endpoints of an optical networking system without the setup and configuration required by DWDM by itself. Light paths between endpoints can be established on an ad hoc basis, providing better mechanisms for managing traffic flows through fiber-optic networks.

Like DWDM, lambda switching is likely to find its place of deployment mainly in long-haul fiber managed by inter-exchange carriers (IXCs). Several vendors are developing lambda switching equipment called optical cross connects (OCXs), with AT&T being one major player in this arena. Deployment of lambda switching technologies should eventually provide bandwidth on demand for the enterprise wide area network (WAN) and should speed up the provisioning process of OC-48 and higher WAN links.

See Also: *dense wavelength division multiplexing (DWDM), inter-exchange carrier (IXC), Multiprotocol Label Switching (MPLS), Resource Reservation Protocol (RSVP)*

LAN

Stands for local area network, typically a group of computers located in the same room, on the same floor, or in the same building, that are connected to form a single network.

See: *local area network (LAN)*

LANE

Stands for LAN Emulation, a technology that enables local area network (LAN) traffic such as Ethernet frames to be carried over an Asynchronous Transfer Mode (ATM) network.

See: *LAN Emulation (LANE)*

LAN Emulation (LANE)

A technology that enables local area network (LAN) traffic such as Ethernet frames to be carried over an Asynchronous Transfer Mode (ATM) network.

Overview

LAN Emulation (LANE) was designed to allow connectionless traffic on Ethernet networks to be transported over connection-oriented ATM backbones. LANE accomplishes this by fragmenting and encapsulating variable-length Ethernet frames into fixed-length ATM cells and by configuring mappings between ATM and Ethernet addresses. Using LANE, you can use ATM as a backbone transport for connecting widely separated Ethernet LANs. Since LANE operates at the data-link layer, it can use ATM to connect LANs using any network-layer protocol, such as Internet Protocol (IP) and Internetwork Packet Exchange (IPX). LANE can also be used for connecting Token Ring networks using an ATM backbone.

Implementation

LANE is implemented utilizing Emulated LANs (ELANs), which are essentially subsets of an ATM cloud in which all stations see each other as neighbors as if they were on the same LAN. An ELAN is thus a kind of "virtual" LAN, but do not confuse LANE ELANs with Virtual LANs (VLANs) in Ethernet switching—they are two different technologies. Stations on an ELAN are known in LANE terminology as LAN Emulation Clients (LECs) and can include servers with special ATM network interface cards (NICs), Ethernet switches such as Cisco Catalyst switches, or routers such as Cisco 7000 series routers. Two LECs on the same ELAN can communicate with each other using LANE, but LECs on different ELANs must communicate through a router.



LAN Emulation (LANE). *The architecture of a simple LANE implementation.*

To implement LANE on a combined ATM and Ethernet network, several special components must be present:

- **LAN Emulation Server (LES):** This component maintains a list of media access control (MAC)-to-ATM address mappings for LECs on the particular ELAN it manages. In other words, an LES maps ATM endpoint addresses (which are 20-byte network service access point or Network Service Access Protocol [NSAP] addresses) to non-ATM endpoint Ethernet MAC addresses. The LES is connected to the LECs on the ELAN it manages using a point-to-multipoint ATM virtual circuit (VC).
- **LAN Emulation Configuration Server (LECS):** This component tells new LECs that appear on the

network how to find the LES for their particular ELAN. A typical LANE deployment will have one LECS for the entire ATM cloud and as many LESs as the cloud is divided into ELANs.

- **Broadcast and Unknown Server (BUS):** Since ATM is a connection-oriented technology that does not inherently support broadcasts, some way of implementing broadcasts is required for interoperability with Ethernet. The BUS accomplishes this, and there is one BUS for each ELAN to handle broadcasts from LECs on that ELAN.

A basic LANE communication session between two LECs on an ELAN takes place something like this: when LEC#1 wants to communicate with LEC#2, it first contacts the LES for that ELAN and requests the ATM address that corresponds to the MAC address of LEC#2. The LES responds to the request, and LEC#1 then establishes an ATM virtual circuit with LEC#2 and begins to transmit.

Prospects

Just as ATM is a technology that never really established itself in the LAN and has largely been superseded by Fast Ethernet and Gigabit Ethernet (GbE), so also LANE is no longer widely used in enterprise networking. Part of this is due to ATM's complexity, but another reason has been limitations with LANE itself. The main problem is the lack of redundancy in LANE, where a single LECS for the ATM cloud and a single LES and BUS for each ELAN make for single points of failure. To resolve this, a new version of LANE called LANE2 has been developed that supports the following enhanced features:

- Multiple LECS per ATM cloud, using a single master LECS that communicates with multiple slave LECS using a new protocol called LANE Network-to-Network Interface (LNNI).
- Redundant LESs and BUSs on each ELAN. In LANE2, when a LEC tries to contact a LES or BUS and fails, it contacts the LECS again to find another LES or BUS to service its needs.

Notes

Microsoft Windows 2000 supports LANE and comes with a LEC that is installed automatically if an ATM network adapter is detected during startup.

See Also: *Asynchronous Transfer Mode (ATM), Ethernet, MAC address*

LAN-host integration

The integration of local area network (LAN)-based networks that use protocols such as Transmission Control Protocol/Internet Protocol (TCP/IP) or Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX) with host systems such as IBM mainframes and AS/400 systems that use Systems Network Architecture (SNA).

Overview

SNA-based networks originally developed separately from LANs, and as a result both architectures have unique adapters, cabling, and networking protocols. Today's LANs are typically built around the Ethernet networking architecture, use TCP/IP as their networking protocol, and run over structured cabling using Category 5 (Cat5) unshielded twisted-pair (UTP) cabling. LANs can be joined together into wide area networks (WANs) using routers, which provide access to telco communications networks. By contrast, SNA networks typically employ mainframe host systems with front-end controllers connected over serial links to remote terminals. As a result of these two different architectures, many large companies have developed a two-tier network, consisting of a traditional LAN-based Ethernet network and an entirely separate SNA host-based network. However, because of the cost of maintaining separate networks, many have merged their SNA-only networks with non-SNA networks.

Early attempts at LAN-host integration involved directly connecting PC computers to IBM host systems using SNA hardware adapters and SNA protocols across a dedicated SNA network. Each PC was connected to a local IBM control unit such as an IBM 3174 or IBM 5294 using coaxial or twinax cabling. Standards were developed to allow SNA and non-SNA protocols to share the same network, but networking engineers soon found that mixing SNA and TCP/IP was like mixing oil and water, especially with regard to WAN connections, in which Data Link Control (DLC) timeouts and other difficulties made network management complex.

One solution is to install a TCP/IP protocol stack on the mainframe host, but this often results in degradation of host performance and additional challenges in terms of IP address administration. A more workable solution is the LAN-to-SNA gateway. The gateway computer lets desktop PCs access applications and data on the mainframe host using traditional LAN protocols. TCP/IP is used to connect the desktop PC and the SNA gateway, and SNA is used to connect the SNA gateway and the mainframe host. This LAN-to-SNA gateway solution has become the de facto standard for providing host access to LAN-based PCs. An example of an SNA gateway application is Microsoft Host Integration Server, which provides LAN-to-SNA gateway services over a variety of network protocols that include NetBIOS Enhanced User Interface (NetBEUI), TCP/IP, IPX/SPX, Banyan VINES, and AppleTalk.

See Also: *Host Integration Server, Systems Network Architecture (SNA)*

LAN security switch

A manual switch that can be used to physically disconnect two or more local area network (LAN) segments.

Overview

LAN security switches are typically utilized in high-security networking environments that must meet the highest government or military security standards. For example, a network supervisor can use a LAN switch at the end of the day to physically disconnect a portion of the network that includes servers that store sensitive data, thus preventing users from accessing the servers during off hours. This is generally more convenient and safer than going into the server room and unplugging connectors from a hub.

Two Uses for LAN Security Switches



LAN security switch. *Two ways of using a LAN security switch.*

LAN security switches are available for both copper cabling and fiber-optic cabling. A fiber-optic LAN security switch has a small mirror inside that rotates when you manually flip a switch or rotate a dial to open or close the connection.

LAN security switches work by creating a physical break in a circuit, thus preventing the flow of data between connected LAN segments. LAN security switches must be operated manually—you cannot operate them remotely using electronic means.

See Also: *network security*

LAN segment

A physical portion of a local area network (LAN), usually separated from other portions by bridges or routers.

Overview

LANs such as Ethernet networks are often "segmented" using bridges in order to improve network performance. Segmentation improves performance by reducing the number of stations in each segment that must compete with one another for access to the network. Bridges are generally used for segmenting smaller LANs because they are cheaper than routers and require no special configuration. Bridges are smart devices that build media access control (MAC)-level routing tables that forward network traffic on the basis of each frame's destination MAC address. If a frame's destination address is a machine in the local LAN segment, bridges attached to that segment will not allow the frame to pass; this reduces unneeded network traffic in other segments attached to the bridge. In a typical scenario, you would place a bridge between your department or workgroup hub and the main network backbone to improve traffic on your local LAN segment.



LAN segment. *Segmenting a LAN using a bridge.*

See Also: *bridge, Ethernet, router*

LAN switch

Another name for Ethernet switch, a multiport device based on bridging technologies that is used mainly to segment Ethernet networks.

See: *Ethernet switch*

LAPD

Stands for Link Access Protocol, D-channel, the data-link layer protocol for Integrated Services Digital Network (ISDN).

See: *Link Access Protocol, D-channel (LAPD)*

Last Known Good configuration

The current configuration information for drivers and services when a user successfully logs on to a Microsoft Windows 2000 or Windows NT system.

Overview

In Windows 2000, the configuration information from the last successful logon is copied to the LastKnownGood control set in the registry. You can then use this configuration to recover your system if later on you find that you cannot log on to the system. This may occur, for example, if you add or upgrade a driver that is incorrect for your particular hardware configuration. If you modify your system and are unable to log on again, you can restart your system, press F8 at the beginning of the boot process in Windows 2000, and follow the prompts to select Last Known Good configuration to reset the Windows configuration information for your system.

See Also: *boot, logon*

LATA

Stands for Local Access and Transport Area, service boundaries for local exchange carriers (LECs).

See: *Local Access and Transport Area (LATA)*

late collision

A collision on an Ethernet network that is detected late in the transmission of the packet.

Overview

Signals on a network cable do not travel instantaneously from point to point; they travel at a fixed speed, which is near the speed of light on copper cabling. If segments of an Ethernet network are too long, collisions can occur that are not properly detected by the stations on the network. This can result in lost or corrupted data, and it can degrade network performance.

Collisions themselves are natural and inevitable on an Ethernet network and occur when two stations transmit their signals simultaneously or almost simultaneously. When two transmitting stations detect a collision (the concurrent signal from the other transmitting station), they both stop their transmission and wait a random time interval before attempting retransmission. The Ethernet standard, however, specifies that if a station on the network is able to transmit 64 bytes or more before another signal is detected, the first station is considered to be "in control" of the wire and can continue to transmit the remainder of its frame, while the second station must stop transmitting and wait. If the distance between two transmitting stations exceeds Ethernet specifications, the stations might not become aware soon enough that another station already has control of the wire. The resulting collision is called a late collision, and results in a data packet that is more than 64 bytes in length (which in itself is allowable) but which contains cyclical redundancy check (CRC) errors. Transmission errors and unreliable communication between the stations are the result.

Late collisions can result from defective Ethernet transceivers, having too many repeaters between stations, or exceeding Ethernet specifications for maximum node-to-node distances.

See Also: *collision, Ethernet*

L

latency

The delay that occurs when a packet or signal is transmitted over a communications system.

Overview

Latency is the amount of time it takes for information to travel between two stations on a network. A network with high latency causes users to experience unpredictable delays in transmission of voice, data, and video signals. This can lead to awkward conversations and time-outs in data transmissions that can cripple network performance. Latency is usually measured in milliseconds (msec) for computer networking and telecommunications systems.

Latency can be a serious issue, especially in voice communications where delays of more than about 250 msec make conversations awkward by creating pauses that cause parties to interrupt one another when speaking (The G.114 recommendation from the International Telecommunication Union [ITU] specifies that round-trip latency in a voice communications system should be less than 300 msec). Similar latency in multimedia transmission can be compensated for by buffering. Latency in data transmission is less serious, although excessive latency can result in Transmission Control Protocol (TCP) connections being closed and retransmissions occurring, which slows down overall network performance.

Types

Latency is an inevitable aspect of any communications system and generally has several possible causes:

- Intrinsic latency in a transmission is caused by the finite transmission speed of electrical signals through wires (or of light signals through fiber-optic cabling). Intrinsic latency cannot be eliminated but is usually quite small in a local area network (LAN) and usually less than a microsecond. In a wide area network (WAN), intrinsic latency is also generally small when transcontinental trunk lines or undersea cables are used and is usually between 10 and 100 msec. For satellite WAN links, however, latency can be 500 msec or even higher, and such high latency can sometimes be frustrating for users of satellite-based Internet access systems.
- Latency is also introduced into a communications path by devices used to switch or modulate signals.

The amount of latency varies greatly with the type of device. For example, the latency for a bridge (the time delay between the moment when the packet enters one port of the bridge and the moment when it leaves another port) is usually between 5 and 50 microseconds (a microsecond is one-thousandth of a millisecond). By contrast, the latency that is usually introduced into a network by routers and gateways that process packets and perform protocol conversion is usually an order of magnitude higher. Latency for signals passing through analog modems is typically about 150 msec due to signal modulation, compression, and error correction processes. See the table below for a comparison of latency introduced into communications paths by different kinds of networking and communications devices.

- Devices that establish a connection can introduce even greater amounts of latency into a communications channel. Integrated Services Digital Network (ISDN) terminal adapters typically take 1 to 2 seconds to establish a connection, but it can take as much as 15 to 30 seconds to establish an analog modem connection. The term *latency*, however, is sometimes restricted to delay over a preestablished communications channel, in which case these scenarios would not normally be identified as latency.

Typical Latency Introduced into Signal Paths by Networking Devices

Device	*Typical Latency*
Network interface card	< 5 msec
Asymmetric Digital Subscriber Line (ADSL) modem	5–10 msec
Plain Old Telephone Service (POTS) landline	< 20 msec
Integrated Services Digital Network (ISDN) terminal adapter	20–30 msec
V.90 analog modem	~ 150 msec
Global System for Mobile Communications (GSM) cellular	~ 150 msec
Voice over IP (VoIP) system	80–500 msec

Notes

Latency for bridges and LAN switches can actually be broken down into two types:

- **Bit-forwarding devices:** Latency here is measured from the moment the first bit of an incoming frame arrives at one port to the moment the first bit of an outgoing frame departs at another port.
- **Store and forward devices:** Latency for these devices is measured from the moment the last bit of an incoming frame arrives at one port to the moment the first bit of an outgoing port departs at another port.

For more information on these types of latency, see RFC 1242 (*www.faqs.org/rfcs/rfcs1242.html*).

See Also: *bridge, Ethernet switch, jitter, local area network (LAN), noise, router, signal, wide area network (WAN)*

Layer 2 Forwarding (L2F)

A media-independent tunneling protocol developed by Cisco Systems.

Overview

Layer 2 Forwarding (L2F) can be used to create virtual private networks (VPNs) that tunnel information securely over public networks such as the Internet using wide area network (WAN) data-link protocols such as Point-to-Point Protocol (PPP) or Serial Line Internet Protocol (SLIP). L2F supports such features as Remote Authentication Dial-In User Service (RADIUS), dynamic allocation of addresses, and quality of service (QoS).

L2F has been superseded by the newer Layer 2 Tunneling Protocol (L2TP), an Internet Engineering Task Force (IETF) standard that provides a vendor-neutral tunneling solution for virtual private networking. L2TP is an extension of PPP and supports the best features of the Point-to-Point Tunneling Protocol (PPTP) and the L2F protocol.

Implementation

As an example, when PPP is used with L2F, PPP provides the connection between a dial-up client and the network access server (NAS) that receives the call. A PPP connection initiated by a client terminates at a NAS located at a PPP service provider, usually an Internet service provider (ISP). L2F allows the connection's termination point to be extended beyond the NAS to a remote destination node, so the client's connection appears to be directly to the remote node instead of to the NAS. The function of the NAS in L2F is simply to project or forward PPP frames from the client to the remote node. This remote node is called a home gateway in Cisco's Internetwork Operating System (IOS) networking terminology.

See Also: *Layer 2 Tunneling Protocol (L2TP), Point-to-Point Protocol (PPP), Point-to-Point Tunneling Protocol (PPTP), virtual private network (VPN)*

Layer 2 switch

An Ethernet switch that forwards frames according to Layer-2 addresses.

Overview

Layer 2 switches operate at the data-link layer (Layer 2) of the Open Systems Interconnection (OSI) reference model. Layer 2 switches are essentially multiport bridges that forward frames based on their destination MAC address without any concern for the actual network protocol being used. Layer 2 switches operate near wire speed and have very low latency compared to Layer 3 devices such as routers.

Layer 2 switching originated in the 1980s with vendors such as Kalpana, which was acquired by Cisco Systems. Although originally developed for a variety of local area network (LAN) architectures including Ethernet, Token Ring, and Fiber Distributed Data Interface (FDDI), by far the most widespread use of these switches is in switched Ethernet, Fast Ethernet, and Gigabit Ethernet (GbE) networks. Layer 2 switches have displaced bridges, hubs, and routers in much of today's enterprise network.

Uses

There are two main kinds of Layer 2 switches, and each type is optimized for its own particular role in the network. These types are

- **Segmentation switches:** These are used to segment large networks into collections of smaller collision domains to reduce congestion and improve network performance. Routers have traditionally been used for segmenting enterprise networks, but Layer 2 switches are cheaper than routers, easier to deploy and manage, and have lower latency. As a result, most large companies have replaced much of their router infrastructure with Layer 2 switches, relegating routers mainly to the role of wide area network (WAN) access devices. In addition to segmenting large networks, such Layer 2 switches are also used to connect LANs across a campus network and to build collapsed backbone networks together with their more powerful cousins, Layer 3 switches.
- **Workgroup switches:** These are used to provide high-throughput switched connections to servers and high-performance workstations. A typical workgroup switch would have 12 or 24 autosensing 10/100 megabits per second (Mbps) or 100/1000 Mbps ports with one or more gigabit uplink ports for connection to the LAN backbone. Hubs have traditionally been used for concentrating servers and workstations into workgroups, but hubs use a shared-media approach that cannot match switches in throughput and latency. As a result of falling port prices in Layer 2 switches, most large companies have migrated their legacy hub infrastructure to Layer 2 switches.

Implementation

Layer 2 switches can generally be installed transparently into networks with no configuration required unless virtual LANs (VLANs) are needed. When Layer 2 switches first appeared, the mantra "switch when you can, route when you must" was promoted (this originated with Synoptics, which later became Bay Networks and has now been acquired by Nortel Networks).

Once installed, a Layer 2 switch dynamically learns about connected hosts and networks by examining the source addresses of frames it receives. The switch continually builds a cache or database of mappings between each port on the switch and the various MAC addresses of hosts and networks connected to that port. Then, when a frame arrives at a given switch port, the switch reads the destination MAC address and forwards the frame to the switch port to which the destination host or network is connected. If the frame's destination address is unfamiliar or if it is a broadcast frame, the switch forwards the frame to all of its ports except the port through which the frame originally entered.

If a Layer 2 switch has ports of different media types (for example, Ethernet and FDDI), frame forwarding is complicated. Frames that must be forwarded to destination ports having different media types must first be reformatted at Layer 1 (the PHY or physical layer) before being forwarded to their destination ports.

Layer 2 switches avoid routing loops by implementing a method first used in bridged networks, namely, the spanning tree protocol. This protocol works automatically to ensure that frames are not endlessly switched around in loops, which would make other network communications impossible.

Advantages and Disadvantages

Advantages of Layer 2 switches over traditional hubs and routers include higher throughput, lower latency, cheaper cost per port, and easier management. Disadvantages of such switches include the danger of broadcast storms and greater complexity in troubleshooting network problems (traditional packet sniffers work on shared media LANs where they can monitor traffic simultaneously from large numbers of stations). A broadcast storm occurs when broadcasts become so common that other forms of network communication are prevented. Broadcasts typically occur due to network advertisements from servers, routers, and other devices. Because Layer 2 switches (and bridges) allow broadcasts to pass, a network built entirely of Layer 2 switches represents a single broadcast domain. When the number of stations in a broadcast domain reaches several hundred, broadcast storms are likely to occur. Layer 2 switches by themselves therefore do not represent a scalable solution for building large enterprise networks. You can solve this broadcast problem in several ways:

- By combining newer Layer 2 switches with traditional routers in the network infrastructure. This brings some of the benefits of switches but leaves some of the problems relating to routers such as cost, and latency, and throughput.
- By configuring separate VLANs for ports or groups of ports on each Layer 2 switch. VLANs let you logically segment the network independently from its physical topology. This approach is functionally equivalent to flattening the network into a number of smaller broadcast domains, and it works well with traditional enterprise networks that followed the 80/20 rule of network traffic distribution. But with the ubiquity of Internet-related technologies in today's network, the pattern of network traffic has shifted to become more like 20/80 (20 percent of traffic is local and 80 percent travels along the backbone), and VLANs do not work well in such a situation, as the optimal network configuration becomes using a single VLAN again—which takes us back to the broadcast storm problem! Another issue with VLANs is that most approaches to creating them are vendor specific, and until the new 802.1Q VLAN standard becomes widely supported, VLANs will be difficult to implement unless all Layer 2 switches are obtained from a single vendor. Finally, VLANs make troubleshooting switched Ethernet networks even harder.
- By building collapsed network backbones using a combination of Layer 2 (bridging) switches with Layer 3 (routing) switches or by using switches combining Layer 2/3 functionality (called multiplayer switches). This is the most popular solution in today's enterprise—see the article "Layer 3 switch" elsewhere in this book for more information.

See Also: *bridge, Ethernet switch, Layer 3 switch, Layer 4 switch, Layer 7 switch, Open Systems Interconnection (OSI) reference model*

Layer 2 Tunneling Protocol (L2TP)

A wide area networking (WAN) protocol used for virtual private networking.

Overview

The Layer 2 Tunneling Protocol (L2TP) was developed as a vendor-neutral tunneling protocol that supersedes proprietary tunneling protocols such as Microsoft Corporation's Point-to-Point Tunneling Protocol (PPTP) and Cisco Systems' Layer 2 Forwarding (L2F) protocol. L2TP can be used to encapsulate Point-to-Point Protocol (PPP) frames for transmission over a variety of network transports, including Transmission Control Protocol/Internet Protocol (TCP/IP), X.25, frame relay, and Asynchronous Transfer Mode (ATM). L2TP is an Internet Engineering Task Force (IETF) standard defined in RFC 2661 and is typically used for creating virtual private networks (VPNs) to securely tunnel network traffic over the Internet and other public data networks.

L2TP supports the same authentication options supported by PPP, including Password Authentication Protocol (PAP), Challenge Handshake Authentication Protocol (CHAP), and Microsoft Challenge Handshake Authentication Protocol (MS-CHAP). L2TP is not a secure protocol in itself, however, for although secure authentication is supported, data encryption is not. As a result, L2TP is usually combined with Internet Protocol Security (IPsec), a Layer 3 protocol that performs encryption to ensure data integrity during transmission. This combination is sometimes referred to as L2TP over IPsec or L2TP/IPsec, but since this form is almost always used, it is more common to simply refer to the combination as L2TP.

L2TP is supported by both Cisco access routers and by the Routing and Remote Access Service (RRAS) of Microsoft Windows 2000.

Comparison

Both L2TP and PPTP are commonly used tunneling protocols in virtual private networking. L2TP has some advantages over PPTP, however:

- Although PPTP can only be used to create IP tunnels, L2TP supports a much wider variety of WAN transports, including X.25, frame relay, and ATM.
- Although PPTP supports only one tunnel between two endpoints, L2TP supports multiple tunnels between two points, each of which can have its own quality of service (QoS) level defined.
- L2TP has less overhead because L2TP headers are only 4 bytes in length and are compressed and PPTP uses uncompressed 6-byte headers.
- L2TP can also support multilink configurations in which each link terminates at a different L2TP server at the service provider. This provides more flexibility than Multilink PPP (MPPP), in which all the links from the customer premises must terminate at the same MPPP server at the service provider.

The main disadvantage of L2TP compared to PPTP is that it requires more processing power due to its use of compression and IPsec encryption.

L2TP is also a significant improvement over Cisco's earlier L2F tunneling protocol. Some of the differences between L2TP and L2F include

- Although L2F has no defined client, L2TP uses a well-defined client.
- Although L2F functions in compulsory tunnels only, L2TP can also use voluntary tunnels.
- L2TP provides additional features, such as flow control and Attribute Value Pair (AVP) hiding, which are not supported by L2F.



Layer 2 Tunneling Protocol (L2TP). *How L2TP is used to encapsulate an IP datagram.*

Architecture

As its name suggests, L2TP operates at Layer 2 of the Open Systems Interconnection (OSI) reference model. When used on IP networks, L2TP uses User Datagram Protocol (UDP) datagrams on port 1701 for both the establishment and management of tunnels and for data transmission. In other words, L2TP transmits its control information using in-band signaling through the same tunnel that data is transmitted over. To transmit data, an IP packet is first wrapped in a PPP frame, which is then encapsulated into a UDP datagram. An L2TP header is then added for transmission over the WAN. In a typical VPN, IPsec is then used to add security by encrypting the data and adding an additional header and trailer to the L2TP frame.

Implementation

Implementing L2TP requires an L2TP client and an L2TP server that both support IPsec. A VPN constructed using L2TP can be initiated in two ways:

- The client can initiate the tunnel in a similar fashion to PPTP tunnels. For example, Windows 2000 clients can initiate L2TP tunnels and connect with routers that support L2TP, such as Cisco routers. In a typical scenario, a dial-up tunnel is initiated by a client who connects with a network access server (NAS) at the client's telco central office (CO) or Internet service provider (ISP). The NAS performs the server-side function of PPP termination and acts as the receiver of incoming connections. In some implementations, the NAS is referred to as an L2TP access concentrator (LAC). The LAC then forwards its L2TP traffic to a remote node called an L2TP network server (LNS).
- A NAS can initiate the tunnel, enabling telcos and ISPs to provide corporate customers with complete VPN solutions. In this scenario, the remote client acts as the LNS.

See Also: *Internet Protocol Security (IPsec), Layer 2 Forwarding (L2F), Multilink Point-to-Point Protocol (MPPP), Point-to-Point Protocol (PPP), Point-to-Point Tunneling Protocol (PPTP), User Datagram Protocol (UDP), virtual private network (VPN)*

Layer 3 switch

An Ethernet switch that forwards frames according to Layer 3 addresses.

Overview

Layer 3 switches operate at the network layer (Layer 3) of the Open Systems Interconnection (OSI) reference model. Layer 3 switches have many of the characteristics of traditional routers and forward datagrams based on their network layer addresses. For example, on a Transmission Control Protocol/Internet Protocol (TCP/IP) network, Layer 3 switches forward IP packets based on their destination IP addresses, but on a legacy Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX) network, they forward IPX packets based on their destination IPX addresses.

Layer 3 switching originated in the early 1990s and was developed mainly in response to scaling problems with Layer 2 switches and the difficulty traditional routers had with keeping up with backbone traffic flows. 3Com Corporation pioneered the development of Layer 3 switching by incorporating routing functions in some of its Layer 2 switches in 1992. These early switches were mainly software-based and were superseded in the mid-1990s by hardware-based switches such as the popular CoreBuilder 3500 and 9000 series of switches, which employed application specific integrated circuits (ASICs) dedicated to high-speed bridging and routing functions.

Layer 3 switches are currently available from a wide variety of vendors for Ethernet, Fast Ethernet, and Gigabit Ethernet (GbE) networks. Layer 3 switches are also available for other networking architectures, including Token Ring, Fiber Distributed Data Interface (FDDI), and Asynchronous Transfer Mode (ATM), but these are not as common as Ethernet switches.

Uses

Using a combination of Layer 2 and Layer 3 switches, you can easily build and operate highly scalable collapsed backbones for enterprise-level networks. Due to their routing functionality, Layer 3 switches have largely replaced traditional routers in campus backbones and other large networks, relegating the router mainly to the role today of wide area network (WAN) access device.


Physical topology
Layer 3 switch
Core Layer 2 switch
Layer 3 switch
Layer 3 switch
Layer 3 switch
Layer 2 switches
Layer 2 switches
Layer 2 switches
Layer 2 switches
Core level
Distribution level
Access level
Logical topology
Broadcast domain
Core Layer 2 switch
Broadcast domain
Broadcast domain
Broadcast domain

Layer 3 switch. *Building a switched network backbone using Layer 2 and Layer 3 switches.*

A typical switched network backbone is built in a hierarchical fashion in several levels using a combination of Layer 2 and Layer 3 switches. At the periphery of the network is the access level, which uses multiple Layer 2 switches to provide connection points for workgroup collections of servers and workstations. These Layer 2 switches represent collision domains but pass broadcasts; consequently, to prevent broadcast storms from occurring they need to be consolidated using Layer 3 switches. These Layer 3 switches represent the distribution level of the network, as they are used to distribute traffic to different access points for workgroup connections. Layer 3 switches represent broadcast domains, and the number of connected devices downstream from each switch must be small enough to prevent broadcast storms from occurring (a good rule of thumb is a maximum of 2000 connected devices). Finally, these Layer 3 switches at the distribution level are connected using high-speed Layer 2 switches, which form the network's core level. The network's hierarchical physical structure is thus equivalent to a logical star network with multiple broadcast domains connected using one or more Layer 2 switches (see diagram on the previous page).

If you are migrating a legacy routed network to a modern switched one, you can also simply deploy a Layer 3 switch anywhere in your network a traditional router is used.

Implementation

This discussion will focus on Layer 3 switching in TCP/IP running on Ethernet, where the primary Layer 3 protocol is IP. Layer 3 switches essentially do the same thing traditional routers do—route (forward) packets to their destination based on their Layer 3 address (see the table for a comparison of routers and Layer 3 switches). However, traditional routers really perform two different functions:

- **Route calculation:** This is the process of building routing tables and usually takes place dynamically using a routing protocol such as Routing Information Protocol (RIP) or Open Shortest Path First (OSPF).
- **Packet forwarding:** This involves examining a packet's destination IP, looking up this address in the routing table, and determining which port (connected network) to forward the packet to so that it can eventually reach its destination.

The difficulty with traditional routers is that they are software-based devices that are slow and unable to keep up with today's gigabit speed networks. Vendors have found different ways around this problem, all of which generally fall under the umbrella name of Layer 3 switching. Some of the common solutions are

- **Wirespeed routers:** This involves replacing traditional software-based routing technology with hardware-based routing by using specialized ASICs developed specifically to perform route calculation and packet forwarding. In other words, a wirespeed router is simply a router that performs its routing functions using preprogrammed hardware instead of installable routing software. Wirespeed routers are typically an order of magnitude or more faster than traditional software routers and can keep up with gigabit data flows and route millions of packets per second. Another name for these devices is Packet-by-Packet Layer 3 (PPL3) switches since they individually examine and forward each packet in a train of packets. The name *switch* is really a misnomer in this case—these devices are actually routers, not switches.
- **Cut-through switches:** These devices operate on the principle of "Route once, switch many" and work by separating the two functions of traditional routers: calculating routes and forwarding frames to their destination. When a train of packets (a data stream or communications flow between two hosts or networks) reaches a port on a cut-through switch, the switch examines the train's first packet, reads the destination IP address, looks up the best route to the destination in its routing table, and determines which port to forward the packet to. The device then switches the entire series of packets in the train to the outgoing port without examining any further packets in the train. In other words, routing is performed on the first packet of the train, and

> switching is performed on the remaining packets. Switching means that an internal logical circuit is set up between the incoming and outgoing ports on the switch. Since switching is much faster than routing, cut-through switches perform significantly better than routers while accomplishing the same function: forwarding packets on the basis of their destination IP addresses.

Within the realm of cut-through switches, there are also many differences in operation depending on vendors. For example, some cut-through switches operate similarly to bridges in the sense that they dynamically learn the addresses of attached hosts and networks by "listening" to traffic. The difference is that instead of learning the Layer 2 (MAC) addresses of devices attached to each port, as bridges and Layer 2 switches do, these Layer 3 switches learn the Layer 3 (IP) addresses of connected devices instead. Such Layer 3 "learning" switches build their routing tables dynamically by listening to traffic on their ports, but they cannot exchange this information with similar switches the way routers do using routing protocols. The main use for this type of switch is to "front-end" for traditional routers. For example, if a packet arrives at the switch and the switch does not know what to do with it, the switch simply forwards the packet to the router for handling. Traditional routers are also still needed for routing legacy protocols such as DECnet and AppleTalk and for providing access to the WAN.

By contrast, some cut-through switches perform virtually all the functions that a traditional router performs, such as using the packet's checksum to verify its integrity, updating the packet's Time to Live (TTL) information after each hop, processing any option information in the packet's header, and sharing their routing table information with similar switches using a standard routing protocol, such as RIP or OSPF, so that they become aware of the network's overall topology. In short, they are identical to routers except that they route only the first packet of any train and switch the remainder to improve performance.

A common feature of Layer 3 switches is their support for Layer 2 switching or frame forwarding. This combination is called either a Layer 2/3 switch, a multiplayer switch, a routing switch, or simply a Layer 3 switch. These devices are becoming so common in the enterprise that many networking professionals simply call them switches, without any further qualifier.

Deploying Layer 3 switches in a network is usually as easy as doing so with Layer 2 switches, which are essentially plug-and-play in their simplicity, and it is much simpler than configuring a router. As a result, Layer 3 switches are rapidly displacing traditional routers in the enterprise, except in the role of WAN access devices where routers still predominate. Layer 3 switches are generally easy to manage also, and they typically support Simple Network Management Protocol (SNMP) and Remote Monitoring (RMON) management protocols.

Traditional Router vs. Layer 3 Switch

Feature	*Router*	*Layer 3 Switch*
Local area network (LAN) protocols supported	IP, IPX, AppleTalk	IP, IPX, AppleTalk
Packet-forwarding method	Software-based	Hardware-based
Throughput	Lower	Higher
Definition of subnet	Per port	Per Layer 2 switching domain
Support for policy-based routing	Less	More
Relationship with bridges	Peer	Layered
Cost	Higher	Lower

Marketplace

Layer 3 switches are typically sold in two configurations: fixed and modular. Fixed switches are simpler and cheaper and usually have 8, 12, or 24 autosensing 10/100 megabits per second (Mbps) or 10/100/1000 Mbps Ethernet ports. Modular switches are more complex and costly and typically consist of a chassis that supports various kinds of modules, each providing one or more ports of Ethernet, FDDI, Token Ring, or ATM connectivity.

Popular Layer 3 switches include offerings from large vendors, such as Cisco's popular Catalyst series of routing switches, and switches from second-tier vendors such as Allied Telesyn International, Asante Technologies, D-Link Systems, Hewlett-Packard, Network Peripherals, and many others. For core switching in network backbones, popular Layer 3 switches that are widely used in enterprise networks include the Catalyst 5000 and 6000 series of switches from Cisco, BigIron 4000 switches from Foundry Networks, BlackDiamond from Extreme Networks, Passport 8600 from Nortel Networks, and the SmartSwitch Router from Enterasys Networks.

Prospects

The growth of Layer 3 switches (and all types of LAN switches) is one of the most significant trends in the networking market. While overall sales of 10 Mbps Ethernet switches peaked in 1998 with 23 million ports sold, sales of Fast Ethernet and GbE switches continue to rise steadily. Sales of Fast Ethernet switches amounted to over 88 million ports sold in 2000 and are increasing at more than 33 percent a year. GbE switches sold almost 6 million ports in 2000 but are expected by some analysts to increase at a rate of more than 200 percent for the next few years. Sales of traditional routers would be expected to suffer in this market as enterprises migrate their router-based infrastructures to switched backbones, but router sales actually continue to increase, driven largely by the growth of the Internet and the needs of large Internet service providers (ISPs) for such devices and their enduring use as WAN access devices. Nevertheless, the days of routed networks are fading and the switch has risen to the dominant position in the infrastructure of enterprise networks, largely replacing traditional hubs, bridges, and routers.

See Also: *Ethernet switch, Layer 2 switch, Layer 4 switch, Layer 7 switch, Open Systems Interconnection (OSI) reference model, router*

Layer 4 switch

An Ethernet switch that forwards frames according to Layer 4 header information.

Overview

Layer 4 switches operate at the transport layer (Layer 4) of the Open Systems Interconnection (OSI) reference model. Layer 4 switches are capable of examining frames and reading their Layer 4 header information, such as Transmission Control Protocol (TCP) and User Datagram Protocol (UDP) port numbers, and then forwarding packets based on this information. In Transmission Control Protocol/Internet Protocol (TCP/IP), these port numbers are used to identify different applications—for example, Hypertext Transfer Protocol (HTTP) typically uses port 80 and Simple Mail Transfer Protocol (SMTP) typically uses port 25. By being able to switch packets according to port numbers, Layer 4 switches are thus able to prioritize the flow of IP traffic according to application. For example, to prioritize HTTP traffic, a Layer 4 switch would be configured to allocate greater bandwidth to IP packets where the Layer 4 header indicates TCP port number 80. Alternatively, a Layer 4 switch could be configured to block or restrict traffic over certain ports, fulfilling the role of a firewall. The key difference between Layer 4 switches and switches that operate at Layer 2 or Layer 3 is that Layer 4 switches provide the ability to prioritize traffic according to application.

Uses

Layer 4 switches are not intended to replace Layer 2 and Layer 3 switches as the basic building blocks of collapsed backbones in enterprise networks. Instead, they can be selectively deployed in the distribution level of the network (see the article "Layer 3 switch" elsewhere in this book) to add traffic prioritization and firewall services for the network when these features are needed or desired.

Implementation

Layer 4 switches typically perform bridging (forwarding by Layer 2 or MAC addresses) and routing (forwarding by Layer 3 or IP addresses) also. In other words, a typical Layer 4 switch is really a multilayer switch or Layer 2/3/4 switch. Alternatively, Layer 3 switches are sometimes marketed as featuring additional Layer 4 switching capabilities. Layer 4 switches thus need to be able to store a large number of mappings for each switch port, namely

- MAC addresses for each connected device
- IP addresses for each connected device
- Multiple port numbers for each connected device

As a result, Layer 4 switches require a great deal of processing power and memory and are more expensive than their Layer 2/3 cousins. Because of their ability to switch according to port numbers, Layer 4 switches enable multiple logical network connections to be established for each path to a device having a Layer 3 address. The combination of a Layer 3 address, such as an IP address and a port number, is usually called a socket, and a train of frames all having the same socket information is referred to as a flow. Most Layer 4 switches can enforce Layer 3 traffic flows on a policy basis, making management of complex traffic flows simple to implement.

Marketplace

Vendors of Layer 4 switches include Cisco Systems, with its Catalyst series of switches; Extreme Networks, with its Summit series; 3Com Corporation, with its CoreBuilder series; and companies such as Alteon WebSystems (acquired by Nortel Networks in 2000), F5 Networks, Foundry Networks, and Radware.

See Also: *bridge, Ethernet switch, Layer 2 switch, Layer 3 switch, Layer 7 switch, Open Systems Interconnection (OSI) reference model, router*

Layer 4+ switch

An Ethernet switch that forwards frames according to header information found in Layer 4 and higher.

Overview

Layer 4+ switches combine bridging (Layer 2), routing (Layer 3), and port mapping (Layer 4) with functionality derived from layers higher than 4 of the Open Systems Interconnection (OSI) reference model. What this usually means in reality is that they can use Layer 7 (application layer) information found in packet headers and make routing decisions based upon this information. Hence Layer 4+ switches are effectively just Layer 7 switches with a different name. For more information, see the article “Layer 7 switch” below.

See Also: *bridge, Ethernet switch, Layer 2 switch, Layer 3 switch, Layer 4 switch, Layer 7 switch, Open Systems Interconnection (OSI) reference model, router*

Layer 7 switch

Also called Layer 4+ or Layer 4/7 switch, an Ethernet switch that forwards frames according to Layer 4 header information.

Overview

Layer 7 switches operate at the application layer (Layer 7) of the Open Systems Interconnection (OSI) reference model. In this respect, they fill a niche in e-business networks that Layer 4 switches cannot. Considering Hypertext Transport Protocol (HTTP) traffic or Web traffic as an example, Layer 4 switches can use port numbers to distinguish Web traffic from other types of Internet traffic such as Simple Mail Transport Protocol (SMTP) traffic, but they cannot distinguish static HTTP traffic (which can be cached) from dynamic traffic (which is not easily cached). When Layer 4 switches are used to front-end a Web server farm, the result is that all forms of HTTP traffic get cached, which is wasteful and adds unnecessary latency to dynamic Web applications.

Enter Layer 7 switches, which can examine Layer 7 HTTP headers in detail and route traffic according to request type, Uniform Resource Locators (URLs), cookies, and other information. Layer 7 switches are thus capable of switching Web traffic to different servers according to URLs requested (called URL switching), caching different types of traffic differently (cache switching), and directing traffic to different servers in the farm to distribute the load (load balancing) or to servers hosting different types of content (content distribution). As a result, Layer 7 switches are variously marketed by different vendors under names such as Web switches, Web content switches, URL switches, and load balancers.

Uses

Layer 7 switches need be deployed only sparingly in an enterprise. A typical use for such a switch is to act as a front-end for a group of Web servers in a server farm used to support an e-commerce application. The Layer 7 switch provides a single Internet Protocol (IP) address for users to access over the Internet using their browsers, making the server farm appear to the user as a single Web server. The Layer 7 switch typically interfaces with a router that provides connectivity to the Internet (see diagram).



Layer 7 switch. *Using a Layer 7 switch to front-end a Web server farm.*

Marketplace

Most Layer 7 switches are special purpose devices dedicated to managing HTTP traffic more effectively for e-commerce systems—true Layer 7 switches that are fully configurable for any form of application traffic are rare. A Web content switch should typically support such additional features as application redirection, content-intelligent switching, local and global load balancing, packet filtering, quality of service (QoS) traffic routing, and Secure Sockets Layer (SSL) acceleration.

Popular makers of Layer 7 switches include Alteon WebSystems (acquired by Nortel Networks in 2000) with its Alteon 184 switch, ArrowPoint Communications (acquired by Cisco Systems) with its CS-800 switch, Foundry Networks with its ServerIronXL switch, F5 Networks with its Big-IP series of switches, and Intel Corporation with its NetStructure E-Commerce Director switches. Some vendors also claim that their Layer 2, 3, or 4 switches include limited Layer 7 switching capabilities, so the marketplace can be confusing to the newcomer.

Prospects

An emerging use for Layer 7 switches is to provide QoS for Voice over IP (VoIP) systems and load balancing for IP Private Branch Exchange (PBX) equipment. These switches use Layer 7 information in IP headers to identify packets containing H.323 and Session Initiation Protocol (SIP) voice traffic as payload and help to prioritize the forwarding of these packets in such a way as to provide better quality voice communications over IP networks. Two examples of such switches are AppSwitch from Top Layer Networks and a VoIP module for Web Server Director from Radware.

See Also: *bridge, Ethernet switch, Layer 2 switch, Layer 3 switch, Layer 4 switch, Open Systems Interconnection (OSI) reference model, router, Voice over IP (VoIP)*

LCP

Stands for Link Control Protocol, the portion of Point-to-Point Protocol (PPP) responsible for link management.

See: *Link Control Protocol (LCP)*

LDAP

Stands for Lightweight Directory Access Protocol, a standard protocol for accessing information in a directory.

See: *Lightweight Directory Access Protocol (LDAP)*

leased line

A permanent link leased from a telecommunications carrier.

Overview

Leased lines are dedicated point-to-point circuits that are installed between a customer premises and a telco central office (CO). Examples of leased line services include switched 56, T1, fractional T1, and T3 lines. Integrated Service Digital Network (ISDN) is also sometimes considered a leased line service, but ISDN is really a dial-up service unlike always-on T-carrier services. These services are provisioned, installed, and leased from a telecommunications carrier such as a local exchange carrier (LEC) or inter-exchange carrier (IXC).

Uses

Leased lines have been around since the 1980s and have long been the primary means for enterprises to connect their remote offices in a wide area network (WAN). In a traditional WAN the larger branch offices would be connected to headquarters by T1 or fractional T1 lines, sometimes with ISDN lines as backup, and smaller branch offices would get by with dial-up modem connections used for nightly transfers of batch jobs. With the explosion of the Internet in the 1990s, this picture has changed, and the rapid rise of WAN traffic has driven large companies to find solutions other than deploying additional expensive leased lines.

The main alternatives to leased lines during the 1990s included frame relay and Asynchronous Transfer Mode (ATM) circuits, but these technologies are complex and expensive to deploy and have not gained the same popularity in the enterprise as leased lines. Recently, Digital Subscriber Line (DSL) has emerged as a promising alternative to leased lines. By combining a DSL connection to the Internet with virtual private networking (VPN) technology, corporate networks can tunnel through the public Internet to connect securely with remote offices and mobile workers.

In the age of the Internet and e-commerce, leased lines are finding other popular uses:

- Providing reliable high-speed Internet access for corporate networks.
- Connecting e-businesses with hosting centers that host their e-commerce Web sites.

Advantages and Disadvantages

Leased lines have several advantages over competing WAN technologies:

- **Security:** Leased lines are dedicated point-to-point links between the customer premises and the telco, and are therefore difficult to eavesdrop on. By contrast, a VPN over DSL solution has to employ encryption to ensure data security and integrity, and holes have sometimes been found in encryption schemes—for example, in the Point-to-Point Tunneling Protocol (PPTP).
- **Availability and Reliability:** Leased lines have been around for a long time and are well understood. As a result, they are easy to set up and troubleshoot, and they provide virtually 100 percent uptime. Frame relay and ATM are more complex, and there have been well-publicized failures of the frame relay and ATM backbones of some of the largest carriers in recent years. And since a VPN over DSL solution uses the Internet as its transport, the reliability of a link depends on the reliability of the Internet itself—something that is open to question in the age of massive Distributed Denial of Service (DDoS) attacks and Internet backbone congestion.
- **Low latency and jitter:** Leased lines offer virtually latency-free connections, suitable for transmission of data, voice, and multimedia. By contrast, a VPN over DSL solution employs Internet Protocol (IP), which can have significant latency and jitter that can adversely affect both voice and multimedia communications.

By contrast, the main disadvantage of leased lines is their cost, which has remained high over the last decade. For example, a T1 line can cost well over $1,000 a month compared to perhaps $50 to $100 per month for a faster DSL connection. Despite these huge costs, leased lines still remain the most popular way for enterprises to connect their remote offices in a WAN, primarily because of their high reliability. For mission-critical or time-sensitive traffic, leased lines still rule—for less critical traffic, VPN over DSL is a good solution, however.



Leased line. *How a leased line is provisioned.*

Implementation

Provisioning a leased line involves steps at both the customer premises and telco ends:

- **Customer premises:** Special equipment is required to connect the customer's local area network (LAN) to the line termination point at the customer premises. This is typically either a combination of router and channel service unit/data service unit (CSU/DSU) or an access server (also called integrated access device, or IAD) that combines the functionality of a router and a CSU/DSU into a single device.
- **Telco CO:** The telecommunications carrier dedicates certain switches in its switching fabric to set up a permanent circuit between the local and remote customer premises. Data then flows along a single permanent path between the two locations.

Marketplace

Leased lines are generally available from both LECs and IXCs. Provisioning and service quality vary greatly but in general are good for large Regional Bell Operating Companies (RBOCs) such as BellSouth Corporation. IXCs such as AT&T and Sprint are logical choices for large enterprises wanting to deploy leased lines across the United States, but these carriers rely on LECs for the actual provisioning at the local loop level, and this introduces a second tier into the service end, which can sometimes cause delays and difficulties. For enterprises having a global presence in several countries and regions around the world, the largest player in the leased line market is Concert, a joint venture of AT&T and British Telecom (BT).

Charges for a leased line are typically based on the distance of the line and not on the bandwidth used—usually you pay for the available bandwidth even if you do not use it all. Actual provisioning of a leased line from time of order to deployment typically takes four to eight weeks, depending on demand.

See Also: *Asynchronous Transfer Mode (ATM), central office (CO), circuit-switched services, customer premises, Digital Subscriber Line (DSL), frame relay, Integrated Services Digital Network (ISDN), inter-exchange carrier (IXC), local exchange carrier (LEC), T-carrier, virtual private network (VPN), wide area network (WAN)*

LEC

Stands for local exchange carrier, any telco in the United States that provides telephone and telecommunication services for subscribers within a geographic region.

See: *local exchange carrier (LEC)*

license

A legal authorization to use software in a given networking scenario.

Overview

Purchasing most business software typically involves two steps:

- Purchasing media containing the installation files from which the software can be installed on your computers.
- Determining how your software will be used and how many users will use it, and then purchasing licenses to use the software legally in the manner you have chosen.

Licensing is a complex issue and varies from vendor to vendor and across product lines, but it is important to take licensing into account in the planning stage before purchasing software, as the cost of licenses can add significantly to the overall deployment cost.

History

Early licensing programs for commercial software usually used a per-server basis—that is, licenses were applied to the client instead of the server. A single per-server license authorized a single client connection to the server for file, print, or whatever server services were being licensed. Per-server licensing meant that administrators had to determine the maximum number of users who might want to access the server simultaneously and to purchase sufficient per-server licenses to ensure that licensing requirements were being met. The main problem with per-server licensing was that it did not scale well from a financial perspective. For example, if no more than five users were expected to access a file server at any given time, five per-server licenses would need to be purchased at a cost of *x* dollars. If two more file servers were added to the company network, 3 x 5 = 15 licenses would be required (five for each server), at a total licensing cost now of 3*x* dollars.

Per-seat licensing was developed to address the scalability issue of per-server licensing. With per-seat licensing, the client machines are licensed, rather than the servers (although the servers usually require additional licenses of their own). Each client machine requires only a single per-seat license to authorize it to access any server on the network. Per-seat licensing scales better than per-server licensing, and it is simple to calculate—a company requires as many per-seat licenses as it has client machines or users.

Prospects

With the widespread penetration into business networks of Internet technologies such as the World Wide Web, existing licensing schemes have begun to show signs of strain. Client machines are no longer simply desktop computers used by employees—they might also include users who connect to your company Web site over the Internet to access resources on your network. Both the per-server and per-seat licensing schemes break down here—licensing Internet applications would logically mean either buying billions of per-server licenses for each of your servers or buying a per-seat license for every individual on the planet!

One way around this issue is to offer Internet services freely to clients, with no licensing costs involved. While this may work with simple Web servers that serve static content, it fails to solve the problem that arises when Web servers host applications that access back-end databases. To address the issue of how Internet and e-commerce technologies are affecting traditional licensing systems, new models are starting to evolve:

- **Usage-based licensing:** Administrators pay licensing fees monthly instead of one-time fees. These monthly fees are based either on the number of users or on the number of transactions performed against the vendor's applications.
- **Leasing applications:** Instead of buying shrink-wrapped software and installing it on company servers, companies lease the e-commerce applications and services they need from application service providers (ASPs) and pay a flat monthly fee along with a surcharge based on usage.
- **Value-based licensing:** This scenario envisions licensing fees calculated on actual business results related to using the software—for example, based on number of units sold and number of solid sales leads generated.

The advantage of these new licensing paradigms are that licensing costs can be drastically reduced by basing costs upon actual rather than expected maximum usage—in other words, you pay only for what you use. The downside is that these schemes are more difficult to plan from an accounting perspective and make the IT (information technology) budgeting process more complex.

For More Information

For current information about Microsoft licensing practices, visit *www.microsoft.com/licensing*.

Lightweight Directory Access Protocol (LDAP)

A standard protocol for accessing information in a directory.

Overview

The Lightweight Directory Access Protocol (LDAP) defines processes by which a client can connect to an X.500-compliant or LDAP-compliant directory service to add, delete, modify, or search for information, provided the client has sufficient access rights to the directory. For example, a user could use an LDAP client to query a directory server on her network for information about specific users, computers, departments, or any other information stored in the directory.

The term *LDAP* can mean three different things, depending on the context:

- **LDAP data format:** This defines the manner in which information is stored and recalled in an LDAP-compliant directory. This is called the LDAP Data Interchange Format (LDIF).
- **LDAP protocol:** This defines the processes that are involved when an LDAP client and LDAP server interact with each other—for example, when a client queries a server for some information.
- **LDAP API:** This is a set of application programming interfaces (APIs) that defines how applications can programmatically interact with LDAP servers.

LDAP was developed by the Internet Engineering Task Force (IETF) and its current version, LDAPv3, is defined in RFC 2251. LDAP is designed to run over Transmission Control Protocol/Internet Protocol (TCP/IP) and is a subset of Directory Access Protocol (DAP), part of the X.500 recommendations from the International Telecommunication Union (ITU).

History

Directories store information in a hierarchical fashion. The first attempt at defining a directory standard that could scale to global proportions was X.500, which was developed by the ITU in a series of recommendations spanning 1984 to 1994. Unfortunately, these recommendations were so complex that they were seen as too difficult to implement on most computing systems of that era. For example, the Directory Access Protocol (DAP), a part of X.500 that defined how X.500 clients would communicate with X.500 directory services, was so complex that its footprint would be too large and too slow to implement on a standard PC workstation. As a result of these problems with X.500, a process was launched to develop a simpler directory standard that would be easy to implement on PCs while remaining fully backward-compatible with X.500. The result of this development process was an open standard called LDAP.

Initial work on the LDAP standard and the first LDAP-compliant server, called SLAPD, was developed by researchers at the University of Michigan in conjunction with PSINet and the ISODE Consortium. LDAP began as a simple replacement for DAP that was intended to work with X.500 directory services—it was not intended to define a separate standard for directory services themselves. Version 2 of LDAP, defined in RFC 1777, took things a step further by divorcing LDAP from the X.500 standard proper, and it allowed for the development of stand-alone LDAP directory servers to replace the more complex directory service agents (DSAs) of a full X.500 directory service. LDAPv2 directory servers were stand-alone in the sense that they could not perform referrals. For example, if a client queried an LDAPv2 server for information that the server did not possess, the server would return a negative response to the client and would not be able to refer the client to other LDAPv2 servers that might have the information. This limitation severely affected the scalability of LDAPv2 directory service systems.

To overcome the scalability issues and other limitations of LDAPv2, a new version, LDAPv3, was developed by the Internet Engineering Task Force (IETF) in 1997 and was standardized as RFC 2251. LDAPv3 is the version of LDAP widely used in today's directory products, including Microsoft's Active Directory directory service, and it is a superset of LDAPv2 that remains backward-compatible with DAP and X.500. LDAPv3 has the following enhancements over earlier versions:

- **Internationalization:** Support for Unicode instead of the American National Standards Institute (ANSI) used in previous versions.
- **Referrals:** An LDAP server that cannot answer a client's query can refer the client to a different LDAP server that knows the answer. This makes LDAPv3 a highly scalable standard that can be used in large enterprises.
- **Security:** LDAPv3 supports both Transport Layer Security (TLS) and Kerberos security protocols.
- **Extended operations:** LDAPv3 is extensible and supports extended searching operations.

Advantages and Disadvantages

Some of the qualities of LDAP that have enabled it to gain widespread popularity include

- **Open:** LDAP is an open standard running on TCP/IP that specifies a protocol for communication between LDAP clients and servers but leaves implementation details for servers up to the vendors themselves, who develop various LDAP products.
- **Secure:** LDAP supports various kinds of security to preserve the integrity of directory data on a network.
- **Extensible:** The LDAP schema can be extended by defining new classes of objects and attributes to support applications that need these.
- **Programmable:** LDAP employs a standard set of APIs written in C/C++ and defined by RFC 1832. These APIs specify how LDAP client applications can programmatically query and obtain information from LDAP servers.
- **Scalable:** LDAPv3 supports referrals that allow LDAP directory services to scale easily to millions of objects for enterprise deployments.

Architecture

To understand how LDAP works, you need to know its terminology first. A good way of understanding LDAP terminology is to compare it with terminology for relational databases. Despite the similarities between these two systems, LDAP is not intended to replace relational databases because it lacks features such as locking, transactional processing, reporting, and efficient storage of binary large objects (BLOBs). The following are the basic LDAP terms and concepts:

- **Object:** Also called entries, objects are anything about which you want to store data in the directory. Objects are typically users, groups, computers, printers, organizational units, and domains. Objects are for LDAP what records are for a relational database.
- **Attribute:** Information about an object. For example, a user object might have attributes such as last name, first name, address, phone number, and e-mail address. An attribute can sometimes have more than one value—for example, a user might have several e-mail addresses. Attributes are for LDAP what fields are for relational databases. An LDAP server stores the values of an object's attributes in name/value pairs.
- **Classes:** Define what attributes go with what objects. Classes are for LDAP what tables are for relational databases—but unlike tables, classes are extensible and allow additional attributes to be defined for objects as required.
- **Schema:** The collection of classes and attributes used for a particular implementation of an LDAP directory service. LDAP schemas are extensible and allow new classes and attributes to be defined as required. Schemas have no counterpart in relational database terminology.

- **Directory information tree (DIT):** The tree of objects stored within an LDAP directory.
- **Directory service agent (DSA):** An LDAP directory server.
- **Distinguished name (DN):** A unique name identifying an object within an LDAP directory.
- **Namespace:** The collection of possible names for objects within a specific LDAP directory.
- **Organizational unit (OU):** Containers within a namespace. OUs can contain leaf objects and other OUs. OUs are typically departments within a company, regions within a geographical area, and so on.
- **Domain:** Top-level names within a namespace. Domains can contain OUs and leaf objects, and they are typically names of things such as companies and countries.
- **Leaf object:** Any LDAP object that is not a domain or an OU. Examples of leaf objects include individual users, computers, and printers.

LDAP operates as a client/server protocol in which an LDAP client connects to an LDAP server over TCP port 389, issues a query, receives a response, and disconnects from the server. LDAP clients on LDAP servers can perform six operations:

- Binding (authenticating)
- Searching (querying)
- Adding an entry
- Modifying an entry
- Removing an entry
- Comparing entries

LDAP servers can perform three additional operations among themselves:

- Referral
- Replication
- Encryption

Examples

To understand LDAP naming conventions, the distinguished name (DN) for the object representing user Jeff Smith within Active Directory (Microsoft's implementation of an LDAP server) might be:

```
DC=com,DC=Microsoft,OU=Users,CN=Jeff Smith
```

You can read this as

```
Domain = com

Domain = Microsoft

Organizational unit (OU) = Users container

Common Name (CN) of user-type leaf object =
Jeff Smith
```

LDAP Uniform Resource Locators (URLs) are another naming convention that can be used to allow LDAP clients to access objects in an LDAP directory. An LDAP URL is formed by appending the distinguished name of the directory object to the fully qualified DNS domain name (FQDN) of the server containing the LDAP directory. The LDAP URL for referencing the above object would thus be

LDAP://Server7.Microsoft.com/CN=Jeff Smith/OU=Users/DC=Microsoft/DC=com

Marketplace

According to analysts, as of 2000, there were about 1.6 million LDAP servers deployed in enterprises worldwide. This figure is expected to grow to more than 4 million by 2003. The more popular LDAP products on the market include

- Active Directory, Microsoft's LDAP-compliant server that is part of the Microsoft Windows 2000 operating system platform
- iPlanet, formerly Netscape's Directory Server
- eDirectory, Novell's latest version of Novell Directory Services (NDS)
- eTrust, an X.500 directory with LDAP interface from Computer Associates

- Oracle Internet Directory, an LDAP directory built upon the Oracle database platform
- IDDS and Directory Portal, from Innosoft International and Sun Microsystems
- DirX, from Siemens
- Global Directory Server, from Critical Path

There is also an open source LDAP directory called OpenLDAP that is based on the University of Michigan's SLAPD server.

Notes

In Windows 2000, the standard C/C++ LDAP APIs of RFC 1823 are implemented in a library called Wldap32.dll. Applications can programmatically query Active Directory using either Active Directory Services Interface (ADSI), which is implemented as a Component Object Model (COM) interface that is layered on top of the LDAP library, or by employing the LDAP APIs directly.

See Also: *Active Directory, directory, Directory Access Protocol (DAP), distinguished name (DN), Uniform Resource Locator (URL), X.500*

Linear Tape Open (LTO)

A high-capacity tape backup technology.

Overview

Linear Tape Open (LTO) was developed in 1998 by a consortium that includes Hewlett-Packard, IBM, and Seagate Technology. LTO is intended to be an open, multivendor tape architecture comparable in speed and capacity to the more proprietary SuperDLT architecture developed by Quantum Corporation. LTO is intended for heterogeneous enterprise networking environments and has been implemented in both stand-alone tape drives and robotic tape libraries.

Architecture

LTO has a native data capacity of up to 100 gigabytes (GB) per tape uncompressed or 200 GB compressed with a standard 2:1 compression ratio. Using a standard single-reel drive architecture, LTO supports data transfer rates of 10–20 megabytes (MB)/sec uncompressed or 20–40 MB/sec compressed. LTO can also be implemented as a dual-reel system that offers the advantage of fast restores—data that is required can be usually retrieved from tape in less than 10 seconds.

Marketplace

More than 30 different storage vendors have licensed the LTO tape format for implementation in their tape backup products. The first vendor to ship an LTO tape library was Exabyte Corporation with their 110L tape library, which has since been replaced by the 221L tape library.

See Also: *backup, tape format*

line booster

A device for connecting peripherals to computers when distances are longer than cabling normally supports.

Overview

Line boosters work by regenerating or boosting the signal strength so you can use longer cables than specifications usually allow. Because the signal strength in a serial or parallel transmission line decreases with the length of the cable being used, line boosters are sometimes needed to connect peripherals to computers when the distances involved exceed normal cabling capabilities.



Line booster. *Using a line booster to connect a computer to a printer.*

For example, a typical line booster used with a serial RS-232 interface can generally double the distance over which an attached peripheral can transmit, increasing the limit from 49 feet (15 meters) to 98 feet (30 meters). For parallel printers, line boosters can typically increase allowed distances from 19.5 feet (6 meters) to 40 feet (12 meters).

Notes

When deploying line boosters, be sure to install them at the midway point between the computer and the peripheral, not at one end of the connection.

See Also: *RS-232, serial transmission*

line coding

Any algorithm for transforming binary information into discrete (digital) signals.

Overview

A line coding mechanism specifies a mathematical relationship between the binary information in a bitstream of data and the square-wave signal variations on the medium the signals are transmitted over. For copper wires, these signals are expressed as time-varying voltages, but on fiber-optic cabling, they are transmitted as discrete light pulses.

Types

Many types of line coding mechanisms are used in computer networking and telecommunication technologies. Some of these schemes are simple to encode and decode but unreliable in their transmission, and others are reliable even in the presence of external noise but require CPU-intensive processing to encode. Selecting the right line coding scheme for a particular technology requires a good understanding of information theory, electromagnetic theory, and engineering.

Encoding schemes are classified into two basic categories: digital signal codes and block codes. Digital signal codes specify the details of how the voltages (or light intensities) vary with time in copper (or fiber-optic) cabling. Common digital signal codes include

- **NRZ:** This stands for Non-Return to Zero and simply means that the discrete electrical signals (or light pulses) use two different voltages (or intensities) but not zero voltage (or intensity). NRZ is employed in serial interfaces such as RS-232 and by many of the block coding schemes described below, including those for Integrated Services Digital Network (ISDN), Fast Ethernet, and Gigabit Ethernet (GbE). NRZ requires that signal pulses all have equal duration with no gaps between them and that the transmitter and receiver be synchronized in order to communicate with each other.
- **NRZI:** This stands for Non-Return to Zero Inverted and uses a transition (either low-high or high-low) to indicate a binary 1, while a lack of transition indicates a zero. This scheme is more reliable than NRZ and requires less power to transmit.
- **Bipolar-AMI:** In this scheme, both a positive and negative pulse represents binary 1 and no pulse indicates a zero. Unlike NRZ and NRZI, there is no DC component to the signal. Bipolar-AMI is easy to synchronize between the transmitter and receiver and a lost pulse can be easily recovered. On the other hand, it requires more power to transmit than NRZ/NRZI.
- **Pseudoternary:** This is just the opposite of Bipolar-AMI and has the same advantages and disadvantages.
- **Manchester encoding:**. This scheme is the one used by standard 10 megabits per second (Mbps) Ethernet. In Manchester encoding, a low-high transition in the middle of a pulse interval represents binary 1 and a high-low transition represents binary zero. This kind of digital signal encoding scheme is known as a biphase scheme and has the advantage that no prior synchronization between transmitter and receiver is required, as in NRZ/NRZI. Manchester encoding is an inefficient scheme that encodes one bit of information into two baud or code bits, but this “wastefulness” actually makes Manchester simple to encode and decode and thus easy to implement in electronic devices. (An encoding scheme that is more efficient in converting bits to baud is said to be “rich,” but the downside is that the richer the encoding scheme, the more complex

and processor-intensive the actual encoding mechanism becomes.)

- **Differential Manchester encoding:** This is an offshoot of Manchester encoding in which either a high-low or low-high transition at the start of a pulse indicates binary 1 and no transition indicates binary 0.

By contrast to the digital signal codes above, the following line coding schemes are sometimes called block codings. This is because their purpose is to transform a block of data (collection of bits from a bitstream) into a block of electrical or light pulses. Some common examples of these encoding schemes include

- **4B/5B:** This scheme is used by the 100BaseX form of Fast Ethernet. The name *4B/5B* stands for "4 binary, 5 baud" and indicates in shorthand that four bits of data require five baud or code bits for transmission. The 4B/5B scheme is thus (5-4)/4 = 25% wasteful in terms of bandwidth compared to the (2-1)/1 = 100% wastefulness of Manchester encoding. Another way of describing it is to say that 4B/5B has a coding efficiency of 5/4 = 1.25 baud/bit. The 4B/5B scheme is also used by the Fiber Distributed Data Interface (FDDI) network architecture.
- **5B/6B:** This scheme is used by 100VG-AnyLAN and has a coding efficiency of 1.2 baud/bit.
- **8B/6T:** This scheme is used by the 100BaseT4 form of Fast Ethernet. The name *8B/6T* stands for "8 binary, 6 ternary" and indicates that eight bits of data require six ternary or three-level signals for transmission. By contrast, 4B/5B uses two-level signals in which there are only two voltages, not three, for each signal pulse. The 8B/6T scheme has a coding efficiency of 0.75 baud/bit, which means that more than one bit is crammed into each signal pulse.
- **PAM 5x5:** This is used by 100BaseT2 Fast Ethernet and encodes 4 bits of data into a two-dimensional 5x5 = 25 code point space. This scheme has a coding efficiency of 0.50 baud/bit.
- **8B/10B:** This scheme is used by GbE and Fibre Channel and is patented by IBM. The coding efficiency is 1.25 baud/bit.
- **2B1Q:** This stands for "2 binary, 1 quaternary" and is used by the U interface of the Basic Rate Interface ISDN (BRI-ISDN) flavor of ISDN. The U interface is located at the line termination point at the customer premises, where a two-wire metallic cable terminates with an RJ-11 jack. The 2B1Q encoding scheme is actually used only in the United States, as European ISDN uses a different 4 binary, 3 ternary (4B3T) for BRI-ISDN.
- **B8ZS:** This stands for Bipolar with 8 Zero Substitution and is used by the U interface of the Primary Rate Interface ISDN (PRI-ISDN) flavor of ISDN. The B8ZS encoding scheme is actually used only in the United States, as European ISDN uses a different High Density Bipolar 3 (HDB3) for PRI-ISDN.



Line coding. *How the 2B1Q line coding scheme works.*

Other schemes include Discrete Multitone (DMT), Carrierless Amplitude/Phase (CAP) modulation, and Quadrature Amplitude Modulation (QAM), all of which are used in various implementations of Asymmetric Digital Subscriber Line (ADSL) communications.

Examples

This example briefly considers one line coding scheme in more detail, namely BRI-ISDN's 2B1Q scheme.

In this scheme, a block of two binary bits can represent four different values: 00, 01, 10, and 11. These four values are mapped to one quaternary value, which is encoded using four different voltages. The first bit represents a positive or negative voltage, and the second bit represents either 1-volt or 3-volt line potential. The following table lists the four possible combinations. The result of using 2B1Q line coding for BRI-ISDN is that a single electrical pulse represents two binary bits instead of one binary bit. This effectively doubles the possible bandwidth of the communication channel, as shown in the illustration on the previous page.

Binary Data and Corresponding Voltage Level for 2B1Q Line Coding

Binary Data Represented	*Voltage of Electrical Pulse*
00	-3
01	-1
10	+3
11	+1

See Also: *100VG-AnyLAN, Asymmetric Digital Subscriber Line (ADSL), Ethernet, Fast Ethernet, Fiber Distributed Data Interface (FDDI), Fibre Channel, Gigabit Ethernet (GbE), Integrated Services Digital Network (ISDN), Manchester coding, signal*

line conditioner

Any device that is used to prevent undesirable electrical signals from damaging computer, networking, or telecommunication equipment and to guard against data loss due to electrical noise, sags, and surges.

Overview

Line conditioners contain circuitry that enables them to filter out noise caused by electromagnetic interference (EMI) and other sources. They typically contain isolation transformers that electrically isolate the circuitry from unwanted DC voltages, impedance-matching circuitry for reducing unwanted signal reflections, and surge suppressors to guard against high-voltage surges (6000 volts or more) caused by lightning strikes and power failures. Line conditioners can also correct sags (drops) in voltages caused by momentary brownouts, but they are not meant to replace or supply power during a power loss. They often include fault indicators and audible alarms.

Line conditioners also ensure that a transmission's signal parameters remain within specifications for the medium or interface being used, even over excessively long or noisy transmission lines. By maintaining signal integrity, line conditioners can thus allow communication devices to function at higher throughput rates than would normally be supported and ensure data integrity over noisy lines. Another common name for line conditioners is line shapers.

Uses

You typically use line conditioners in the following places:

- In power supplies and in uninterruptible power supply (UPS) systems (power conditioners) to protect computers and networking devices from AC surges coming through power lines.
- In local area networks (LANs) to protect hubs, routers, and other networking equipment from EMI and unwanted noise coming through the networking cables and to maintain the integrity of network data signals.
- In offices to protect modems, telephones, fax machines, and other equipment by filtering out electrical surges in phone lines and to reduce noise so that the devices can operate at their nominal throughput speeds.
- In wide area network (WAN) links for protecting Channel Service Unit/Data Service Units (CSU/DSUs) and access servers connected to Integrated Services Digital Network (ISDN), T1, and other copper telecommunication lines against EMI surges. T1 lines must have line conditioners at regular intervals to ensure the integrity of the signal transmitted over the line.

- With high-speed analog modems to enable them to function at their maximum transmission speeds over noisy telephone lines in the local loop.

See Also: *electromagnetic interference (EMI), Integrated Services Digital Network (ISDN), line filter, local loop, modem, T-carrier, uninterruptible power supply (UPS)*

line driver

Any device used to extend the distance over which a signal may be transmitted over a copper or fiber-optic cable.

Overview

A line driver is essentially a combination of a signal converter and an amplifier. The signal converter performs line conditioning, and the amplifier increases the signal strength.

Line drivers allow signals to be carried over a longer distance than the media or transmission interface normally allows. Line drivers are typically used to extend the maximum distance of serial communication protocols such as RS-232, V.35, X.21, and G.703 and can provide either synchronous or asynchronous communication in various vendor implementations.

Uses

A common type of line driver often used in mainframe computing environments is the RS-232 line driver. This device is used to extend the distance over which dumb terminals can be connected to mainframe computers located in different parts of a building or in different buildings on a campus. RS-232 line drivers support synchronous transmission of data over installed four-wire telephone cabling or fiber-optic cabling and are typically deployed on existing twisted-pair phone lines within a building or on custom-installed fiber-optic lines laid between buildings. These line drivers can extend the maximum distance of RS-232 serial transmission from 49 feet (15 meters) to several miles or more.

Another common use for line drivers is in Asymmetric Digital Subscriber Line (ADSL) and T-1 circuits between a customer and a telco central office (CO).



Line driver. *Using a line driver to connect a remote terminal to a server.*

Implementation

Line drivers are always used in pairs. One line driver is placed at the local site and is connected to the client or terminal, and the other is located at the remote site and is connected to the server or mainframe. For intrabuilding connections using line drivers, copper unshielded twisted-pair cabling or the installed telephone lines are typically used. For inter-building connections, fiber-optic cabling is preferred.

Line drivers are available for almost every kind of communication mode, from 19.2-kilobit-per-second (Kbps) RS-232 serial line drivers over 3.5 miles (6 kilometers) to 2-megabits per second (Mbps) single-mode fiber-optic line drivers over 11 miles (18 kilometers). Line drivers can also be used to extend parallel transmission of data from about 20 feet (6 meters) to several miles.

When you use line drivers, be aware that your maximum bandwidth and transmission distance are inversely related—that is, the longer the line, the less bandwidth you have. Considerations for purchasing a line driver include whether it supports full-duplex or half-duplex communication, 2-wire or 4-wire cabling options, and what kinds of connectors are used. Line drivers for customer premises generally are cheaper and have a smaller footprint than those used by service providers such as telcos at the COs.

Notes

For connecting data terminal equipment (DTE) such as two computers, you should use a modem eliminator instead.

See Also: *Asymmetric Digital Subscriber Line (ADSL), modem eliminator, RS-232, T-carrier*

line filter

A device used to suppress noise in a transmission line or cable, caused by electromagnetic interference (EMI).

Overview

EMI is produced by nearby power lines, motors, generators, and other sources. EMI can introduce noise into a transmission line or cable that can degrade a signal's quality or even make communication impossible. By inserting a line filter at the appropriate point, you can suppress the noise and potentially improve transmission speeds.



Line filter. *Using a line filter to screen out EMI.*

Line filters are sometimes needed in homes or small businesses that use modems to connect to the Internet through a dial-up connection over the local loop. High-speed V.90 modems sometimes have difficulty attaining their top data transfer speeds because of ambient line noise caused by nearby sources of EMI. By placing a line filter at the customer premises between the modem and the Plain Old Telephone Service (POTS) connection, you can filter out noise, which could improve modem speeds.

Notes

Before installing a line filter, you should use a radio frequency (RF) spectral analyzer to determine the general frequency of the source of EMI so that you can choose an appropriate line filter. Line filters typically filter out one of the following frequency ranges: low frequency (LF), high frequency (HF), very high frequency (VHF), or ultra high frequency (UHF) signals.

See Also: *electromagnetic interference (EMI), line conditioner, modem, Plain Old Telephone Service (POTS)*

Line Printer Daemon (LPD)

The UNIX daemon (background service) used for spooling print jobs.

Overview

Line Printer Daemon (LPD) is a daemon that resides on UNIX print servers. Its function is to simply wait and receive any print jobs submitted from clients using the Line Printer Remote (LPR) protocol. When LPD receives a job, it temporarily stores the job in the print queue, a file system subdirectory. There the job sits waiting to be serviced by LPD. When a print device becomes available, LPD retrieves the job from the queue and sends it to the device for printing.

UNIX sends print jobs to printers as raw data streams—for example, as a Postscript file and does not use print drivers the way Microsoft Windows does. However, sometimes print job formatting is required—for example, when you want to send a plain text file to a postscript printer. In this case, a printer filter is used to properly format the job so the output will not look garbled. Printer filters are specified in a UNIX system file called Printcap.

To view the status of jobs currently waiting in the queue, use the Line Printer Queue (LPQ) utility.

Implementation

Both Windows NT and Windows 2000 support UNIX LPD printing, although it is implemented differently on each platform.

Windows NT Server has an optional LPD service that you configure by installing the Microsoft TCP/IP Printing service. This service enables computers running UNIX to send print jobs to the Windows NT server by using the standard UNIX LPR command. Windows NT servers can also use LPR to submit print jobs to either a Windows NT server running LPD or a UNIX LPD print server. The Microsoft TCP/IP Printing service thus provides printing interoperability between the UNIX and Windows platforms for heterogeneous network environments.



Line Printer Daemon (LPD). *How UNIX-to-Windows and Windows-to-UNIX printing work.*

To support UNIX printing services, Windows 2000 Server and Windows .NET Server employ Microsoft Print Services for UNIX, which provides both LPD and LPR services through two services:

- **LPDSVC:** Runs on the Windows 2000 and Windows .NET Server print servers and receives print jobs from native LPR utilities running on UNIX workstations
- **LPRMON:** Runs on the Windows 2000 and Windows .NET Server print servers and forwards print jobs to native LPD processes running on UNIX computers with attached printers

The startup configuration for the LPD service on Windows 2000 and Windows .NET Server is set to Manual by default and should be changed to Automatic if this feature is used.

See Also: *daemon, Line Printer Queue (LPQ), Line Printer Remote (LPR), printing terminology, UNIX*

Line Printer Queue (LPQ)

A UNIX command used for querying the status of a print queue.

Overview

On the UNIX platform, print jobs are submitted to print servers using the Line Printer Remote (LPR) command, which sends them to the print queue to wait for spooling to an available print device. UNIX print servers employ a daemon called Line Printer Daemon (LPD), which waits in the background for print jobs to be submitted to the queue from LPR clients. It is often useful to be able to examine the queue to determine which jobs are still waiting for spooling—the LPQ command does just that. You can use the LPQ command on a UNIX platform to determine

- What jobs are waiting for spooling in the print queue
- Who submitted these jobs to the print server
- Which print device each job is destined for

Examples

The LPQ command displays a list of files on the server that are waiting to be printed, along with associated information. For example, the lpq -S Foxhound -P Laser12 command might be used to display the status of the print queue called Laser12 on a UNIX print server named Foxhound. Alternatively, Foxhound might be a Microsoft Windows NT server with the Microsoft TCP/IP Printing service installed, or a Windows 2000 server with Microsoft Print Services for UNIX installed. Both of these Windows platforms support UNIX LPD printing as an optional feature.

See Also: *daemon, Line Printer Daemon (LPD), Line Printer Remote (LPR), printing terminology, UNIX*

Line Printer Remote (LPR)

A UNIX networks command used to submit print jobs to print servers.

Overview

Line Printer Remote (LPR) is the standard protocol for submitting print jobs to print servers. On the UNIX platform, print servers use the Line Printer Daemon (LPD), a service that runs in the background waiting for print jobs to be received. When LPD receives a job, it temporarily places it in a queue. When a print device becomes available, the job is spooled or moved from the queue to the print device for printing. Note that files to be printed using LPR must be either text files or files specially formatted for the printer being used (for example, a PostScript file for a PostScript printer).

LPR is a Transmission Control Protocol/Internet Protocol (TCP/IP) protocol defined in RFC 1179 and is implemented on all UNIX platforms and on Linux. Microsoft Windows NT and Windows 2000 can also use LPR by installing optional components to support UNIX printing. In UNIX implementations, LPR connections (both inbound and outbound) are formed only on TCP ports 721 through 731. On Windows 2000 and on Windows NT 4 service pack 3 or later, however, LPR may use any port in the range 512 through 1023.

Examples

To print the file Readme.txt using the print queue called Laser12 on an LPD print server named Lazyboy, you would use the command lpr -S Lazyboy -P Laser12 readme.txt.

See Also: *daemon, Line Printer Daemon (LPD), Line Printer Queue (LPQ), printing terminology, UNIX*

line sharer

Any device that allows multiple devices to share the same communications line.


Host Line Sharer
Terminals (DTE)
V.35
V.35
V.35
V.35
Line sharer
Mainframe async host
V.35
PSTN Line Sharer
PC
Phone
Fax
RJ11
Modem
RJ11
Line sharer
RJ11
RJ11
Internet Line Sharer
Two phone lines
PSTN
PC
PC
RS-232
Line sharer
RS-232
RS-232
V-90 modem
PPP link
Internet

Line sharer. *Three varieties of line sharer.*

Overview

Many different types of devices function as line sharers. These vary from those used in mainframe computing environments to customer premises equipment (CPE) used in telephony and telecommunications. Some common examples of line sharers include the following:

- **Host line sharers:** Allow multiple terminals or other data terminal equipment (DTE) to be connected to an asynchronous mainframe host over a single, shared serial transmission line using V.35 adapters and cable. You can use host line sharers primarily to broadcast data to the DTEs. Data transmitted by the DTEs can also be buffered in the line sharer until the line is free and the data can be sent to the host. Host line sharers typically use either RS-232 or V.35 serial interface connections.
- **PSTN line sharers:** Allow multiple Public Switched Telephone Network (PSTN) devices, such as phones, fax machines, and modems, to share one or more phone lines by using RJ11 connectors and adapters. You can often program PSTN line sharers to switch between devices based on calling tones, so that you can remotely control data collection equipment over modems in industrial environments. A small line sharer might let you connect four phones or other devices to two shared phone lines for a Small Office/Home Office (SOHO). Other line sharers connect large numbers of phones to a relatively small number of phone lines on a first-come, first-served basis in modem-pooling environments.
- **Internet line sharers:** Typically stand-alone devices that together with RS-232 modem adapters allow several PCs to share one modem for dial-up connection to the Internet. Internet line sharers typically use one Internet Protocol (IP) address to allow multiple users to browse the Internet simultaneously.

See Also: *data terminal equipment (DTE), Internet access, Public Switched Telephone Network (PSTN), RS-232, V.35*

line sharing

An emerging telco technology for speeding up Digital Subscriber Line (DSL) provisioning.

Overview

In the aftermath of the Telecommunications Act of 1996, new companies known as Competitive Local Exchange Carriers (CLECs) have entered the marketplace. These CLECs frequently focus on provisioning DSL services to residential customers requiring high speed Internet access and to business customers as an alternative wide area network (WAN) technology to traditional (and expensive) leased lines. Because Incumbent Local Exchange Carriers (ILECs) such as Regional Bell Operating Companies (RBOCs) actually own the local loop wiring that enters homes and offices, however, CLECs have been forced to either resell DSL services from ILECs (the ILEC provisions the line for DSL) or request that the ILEC lay down an additional separate line to provision DSL to the customer.

Line sharing is an emerging approach that speeds up the provisioning process without incurring the cost of additional lines or leasing DSL from ILECs. In a line sharing scenario, a splitter is installed at the customer premises end of the existing local loop connection and at the telco central office (CO), separating DSL data transmission from voice traffic. In other words, both voice and DSL are carried on the same existing telephone line, but each is managed by a different carrier: DSL service by the CLEC and voice by the ILEC. No disruption in phone service occurs, and the cost to the ILEC is negligible, while the CLEC saves costs that can be passed on to the consumers.

Prospects

Line sharing is expected to breathe new life into the beleaguered CLEC marketplace and to allow for more aggressive rollouts of DSL to bring broadband Internet access to customers who need it. Several CLECs and ILECs have already formed agreements to implement this technology, and state regulators are holding hearings to set appropriate pricing policies.

See Also: *Competitive Local Exchange Carrier (CLEC), Digital Subscriber Line (DSL), local* *exchange carrier (LEC), Regional Bell Operating Company (RBOC), wide area network (WAN)*

Link Access Protocol, D-channel (LAPD)

The data-link layer protocol for D channel communications in Integrated Services Digital Network (ISDN).

Overview

ISDN uses two separate channels for communication: a D channel for signaling and control and one or more B channels for data transfer. As shown in the table, these different channels use different protocols at the data-link and network layers of the Open Systems Interconnection (OSI) reference model. Link Access Protocol, D-channel (LAPD) is the data-link protocol for the D channel and is defined by the Q.921 specification from the International Telecommunication Union (ITU).

ISDN Protocols for Bottom Three OSI Layers

OSI Layer	*B Channel*	*D Channel*
Physical layer	ITU's I.430 (Basic Rate Interface, BRI) or I.431 (Primary Rate Interface, PRI)	ITU's I.430 (BRI) or I.431 (PRI)
Data-link layer	High-level Data Link Control/Point-to-Point Protocol (HDLC)/PPP)	LAPD (Q.921)
Network layer	Internet Protocol/ Internetwork Packet Exchange (IP/IPX)	Q.931

Architecture

LAPD provides full-duplex transmission over synchronous serial links and supports both point-to-point and point-to-multipoint communications links. LAPD also supports multiplexing of multiple logical channels over a single physical D channel.

LAPD frames always begin with a standard flag (binary 01111110) to identify the start of the frame. This is followed by a 2-byte address that identifies the ISDN device transmitting the frame, a 1-byte or 2-byte control field, variable-length octet-aligned data payload, and a 2-byte frame check sequence (FCS).

See Also: *data-link layer, D channel, full-duplex, Integrated Services Digital Network (ISDN), multiplexing, Open Systems Interconnection (OSI) reference model, serial transmission, synchronous transmission*

link aggregation

Any technology for combining multiple physical data links into a single logical link.

Overview

Link aggregation occurs at Layer 2 (the data-link layer) of the Open Systems Interconnection (OSI) reference model. The basic idea is to combine two or more data-link connections into a single fat logical connection. An aggregated link has several advantages over a single physical link:

- **Scalability:** If demand for bandwidth increases, another physical link can simply be added to the logical bundle. Likewise, if demand for bandwidth decreases, a physical link can be deallocated from the aggregation and assigned elsewhere as needed.
- **Fault tolerance:** If one physical link goes down in a logical bundle, there is no interruption in transmission, just a reduction in allowed bandwidth. Link aggregation is also a useful way of implementing redundancy on point-to-point connections.
- **Load balancing:** Links from several sources can be load balanced by combining them into a single logical pipe.

Link aggregation is also known sometimes as port aggregation or trunking in vendor literature.

Uses

Link aggregation has two main uses in the enterprise:

- Increasing throughput of switch-switch connections in collapsed backbones.
- Combining data streams from multiple network interface cards (NICs) on a multihomed server into a single logical network connection.


① Switch-switch links
LAN
Layer 2
core switch
Four physical
links equals
one logical
link
Layer 2
core switch
LAN
② Server-switch links
High-performance server
LAN
Three
gigabit
NICs
Layer 2 core
switch
Three physical
links equals one
logical link

Link aggregation. *Two uses for link aggregation in the enterprise.*

Implementation

Early implementations of link (or port) aggregation were vendor-specific technologies that required solutions to be built and deployed using technologies from a single source. Examples of proprietary Layer 2 link aggregation technologies include

- Cisco Systems' proprietary Fast EtherChannel (FEC) and Giga EtherChannel (GEC) technologies, which enable up to four full-duplex Fast Ethernet or Gigabit Ethernet (GbE) links to be combined into a single logical link having throughputs of 800 megabits per second (Mbps) or 8 gigabits per second (Gbps). FEC and GEC employ Cisco's proprietary Port Aggregation Protocol (PagP) to automate the process of discovering and configuring link aggregation.
- Cisco's proprietary Inter-Switch Link (ISL) trunking technology, which allows link aggregation across Cisco Catalyst switches.
- Adaptec's proprietary Duralink port aggregation technology.

Prospects

Proprietary link aggregation technologies and interoperability problems are soon to be a thing of the past as vendors implement the new Institute of Electrical and Electronics Engineers (IEEE) 802.3ad standard, which defines a vendor-neutral approach to port aggregation. As more vendors implement this new standard in switching and NIC technologies, enterprise network architects will be able to aggregate links across equipment from different vendors.

See Also: *802.3ab, data-link layer, Ethernet switch, Fast Ethernet, Gigabit Ethernet (GbE)*

Link Control Protocol (LCP)

The portion of Point-to-Point Protocol (PPP) responsible for link management.

Overview

The Link Control Protocol (LCP) operates at the data-link layer (Layer 2) of the Open Systems Interconnection (OSI) reference model and is responsible for opening and closing PPP connections and negotiating their configuration.

During session establishment, LCP establishes the link, configures PPP options, and tests the quality of the line connection between the PPP client and PPP server.

Architecture

During the negotiation phase, LCP handles four main functions: authentication, callback, compression, and multilink establishment. After a PPP link has been established at the physical layer and a modulation method selected, the client must then be authenticated. Different authentication protocols are supported for satisfying the security needs of different networking environments. LCP can negotiate the following authentication protocols:

- **Password Authentication Protocol (PAP):** Transmits passwords in clear text using a two-way handshake
- **Shiva PAP (SPAP):** A vendor-specific implementation of PAP
- **Challenge Handshake Authentication Protocol (CHAP):** Passes a password hash using a three-way handshake and is more secure than PAP or SPAP
- **Microsoft Challenge Handshake Authentication Protocol (MS-CHAP):** Microsoft Corporation's implementation of CHAP, which is more secure than regular CHAP

Once an authentication method has been negotiated that is understood by both the PPP client and server and the client has been successfully authenticated by the server, the next phase is callback. This phase is optional and allows the client to request that the server hang up and call it back to ensure greater security or to reverse billing charges. After callback is complete, the next phase is compression. This phase is also optional and a variety of different compression algorithms are supported, including Predictor, Stacker, Microsoft Point-to-Point Compression (MPPC), and Transmission Control Protocol (TCP) header compression. The final phase of LCP is aggregation of multiple PPP links using Multilink PPP (MPPP). This last phase is also optional.

See Also: *Challenge Handshake Authentication Protocol (CHAP), Multilink Point-to-Point Protocol (MPPP), Password Authentication Protocol (PAP), Point-to-Point Protocol (PPP)*

link state routing algorithm

An algorithm for dynamic routing that was designed to address scalability limitations of distance-vector routing protocols.

Overview

The first dynamic routing protocols were based on the distance-vector routing algorithm, which required that routers periodically advertise their routing tables to neighboring routers. Routing protocols such as Routing Information Protocol (RIP) that are based on the distance-vector algorithm suffer from two main problems: large amounts of routing updates, which consume valuable network traffic, and slow convergence, which results in an inability to scale to large internetworks.

As a result of these problems, the link state routing algorithm was developed. Routing protocols that use link state include

- **Open Shortest Path First (OSPF):** This is the main link state protocol in use today and can be used to build large IP internetworks.
- **NetWare Link Services Protocol (NLSP):** This is a legacy protocol used on Internetwork Packet Exchange (IPX) networks but not much used anymore.
- **Intermediate System to Intermediate System (IS-IS):** This is not much used anymore.

Architecture

Link state routers advertise changes in network topology to other routers using link state packets (LSPs). The router advertises these LSPs only when changes occur in the network—for example, a router going down or a new router being brought up. When a network change occurs, LSPs are sent to all routers everywhere on the network, not just to neighboring routers as in distance-vector routing.

Using the LSPs a router receives from other routers on the network, link state routers use the Shortest Path First (SPF) algorithm to construct a logical tree that represents the topology of the entire network based on the local router as the root of the tree. The router then uses this tree to calculate the optimal paths to different parts of the network and populates routes in its internal routing table with this information. Every link state router on a network thus knows the exact router topology of the entire network.

Comparison of Link State and Distance Vector Routing Protocols

Link State	*Distance Vector*
Fast convergence	Slow convergence
Highly scalable	Small to mid-sized networks only
Broadcasts entire routing table	Broadcasts link status information
Sends updates periodically	Sends updates only when a change occurs to the network
Views network from perspective of itself	Views network from perspective of neighbors
Calculates optical routes based on lowest metric	Calculates optimal routes based on least cost factors, including hops, segment speeds, and traffic flow patterns

L

Advantages and Disadvantages

Link state routing protocols have several advantages over distance-vector protocols:

- Faster convergence
- Better scalability
- Less traffic due to router updates

On the other hand, there are some issues with link state protocols:

- They are more processor-intensive and memory-intensive in their operation, hence routers using link state are usually more expensive.
- They are more complex to configure than distance-vector routing protocols.
- When several link state routers start up, there can be a large amount of network traffic associated with router discovery, a problem called link state flooding. This can temporarily saturate the network and make other communications impossible.
- If LSPs are not synchronized properly, it is possible for routers to acquire wrong or incomplete link state information, causing black holes and other routing problems. Most link state routers now use time stamps and sequence numbers to ensure that convergence occurs properly.

Notes

Link state routing protocols are classless routing protocols, a feature that enhances their scalability by allowing discontiguous subnets and variable length subnet masks (VLSMs) to be employed to reduce the amount of interrouter traffic propagated on the network.

See Also: *distance vector routing algorithm, dynamic routing protocol, NetWare protocols, Open Shortest Path First (OSPF), Routing Information Protocol (RIP), routing protocol*

Linux

An open-source UNIX-like operating system.

Overview

Linux is a Portable Operating System Interface for UNIX (POSIX)–compliant operating system that is freely available from numerous sites on the Internet. Linux is available on a large number of hardware platforms including Intel, Alpha, MIPS, PowerPC, Sparc, and even IBM S/390 mainframe. Linux provides a multiuser multitasking operating system environment that supports symmetric multiprocessing (SMP) and clustering. The platform supports a wide range of file systems and standard architecture features such as interprocess communications (IPCs), remote procedures calls (RPCs), and dynamic and shared libraries.

History

Linux was developed in 1991 by Linus Torvalds, a student at the University of Helsinki in Finland. The platform's name is a contraction of Linus and UNIX and reflects the similarity between Linux and the UNIX operating system. Unlike UNIX, however, Linux was released under the GNU Public License (GPL) as open source software whose underlying code base is shared openly. Under this license, others can share in the Linux development process, and a whole community has arisen whose job is to refine and evolve Linux into a better and more powerful platform. Development of the standard Linux kernel development tree, however, is still controlled by Torvalds himself.

The first distribution of Linux to appear was Slackware, which became available in 1993. A distribution is typically a package that contains the Linux kernel and supporting modules, the GNU C/C++ compiler, Xfree86, or some other freeware version of the X Windows graphical interface, the Apache web server, various applications and tools, an installer, and source code for everything. Version 1 of the Linux kernel appeared in 1994. Since that time, the kernel has gone through several revisions and now stands at version 2.4.

Uses

Linux has found a niche in many companies for specific server-based needs, including Web servers, mail gateways, file servers, and Domain Name System (DNS) name servers. Although the fact that Linux is free would seem to make it an appealing solution for companies wanting to build out their server infrastructure while saving money, many companies have been reluctant until recently to embrace Linux in their mission-critical operations. Reasons for this reluctance have included the lack of a single company responsible for the platform's development and support, as well as the fact that trained Linux professionals are in high demand and are thus difficult and expensive to hire. Recently, however, Linux has consolidated its toehold in large companies through developments such as the appearance of easy-to-install Linux distributions such as Red Hat and Caldera, and through system management software that allows large numbers of Linux servers to be remotely managed from a central console. For example, companies such as Google.com have successfully deployed up to 5000 Linux servers to provide Internet services. Although the low cost of Linux distributions would seem an inducement to deploying Linux in a corporate environment, most IT (information technology) departments carefully weigh this against the cost of supporting and administering a Linux environment before choosing to deploy Linux servers.

Linux on the desktop is less visible in the enterprise than Linux on the server end. Reasons for this include a lack of device drivers (improved universal serial bus [USB] support is provided in current release 2.4 of the Linux kernel), lack of support for running widely used business applications such as Microsoft Office (even though Win4Lin from NeTraverse allows you to run a Microsoft Windows 98 emulator on a Linux box and the StarOffice suite from Sun Microsystems is also available for Linux), lack of implementers and administrators skilled in the Linux platform, limited support from commercial vendors (even though Red Hat has set an example of how a vendor can base a business on services and support of the Linux platform), and the slow desktop upgrade cycle of large IT departments. Some analysts estimate that Linux had less than 2 percent of the client operating system market in 2000, though it has passed the Apple Macintosh platform and now holds second place behind the dominant desktop platform, Microsoft Windows. Corel Corporation's departure from the Linux desktop market was probably another setback to Linux on the desktop; the fact that there are two competing Linux desktop environments, K Desktop Environment (KDE) and GNU Network Object Model Environment (GNOME), may be another.

Another tree of Linux platform development targets the embedded device space, where Linux's small footprint is an advantage. For example, Red Hat has developed a set of Linux APIs called EL/IX that can run Linux and applications having 32 kilobytes (KB) memory.

Architecture

The core of the Linux operating system is the kernel. Linux is built on a modular (as opposed to monolithic) kernel architecture, which enables custom kernels to be built using subsystem modules, device drivers, and protocol stacks. The Linux kernel follows two different development trees:

- **Odd-numbered versions:** Kernel builds having odd numbers such as 2.1, 2.3, and so on are development (experimental) builds. These are used for trying out new features of Linux and are generally not recommended for use in production systems.
- **Even-numbered builds:** These are builds intended for production systems and are tested until they are believed to be stable. Recent examples include versions 2.2 and 2.4.

Features of the most recent Linux kernel (version 2.4) include

- Improved symmetric multiprocessing (SMP) that supports up to 32 processors on Intel x86 servers and scales better than previous kernel versions
- Up to 64 gigabytes (GB) of addressable physical memory
- Support for large file systems up to terabytes of stored data
- Kernel-level Web daemon called kHTTPd that provides high-performance delivery of static Web pages
- Support for Intel's 64-bit Itanium (IA-64) processor architecture
- Support for Network File System (NFS) version 3
- Logical Volume Manager (LVM) that improves how files and volumes are handled
- Improved USB support

Marketplace

Although the core Linux platform is freely available for download from various places on the Internet, Linux is also available as commercial Linux distributions from a number of companies, including Red Hat, Caldera International, SuSE, Turbolinux, Debian, and many others. Some distributions include special tools or other "value-adds" to meet specific needs of enterprise users. For example, Turbolinux includes its TurboCluster tools for building clustering solutions, Red Hat Linux includes Red Hat PowerTools to enable administrators to remotely manage servers, and VALinux Systems provides vendor-neutral turnkey Linux systems. Both the Red Hat and Helixcode distributions have proved popular for deploying Linux on the desktop.

A thin-client version of Linux is also available from Neoware Systems and is designed for use in devices such as firewall appliances, smart card readers, and cash registers. This platform is called NeoLinux and is a customized version of Red Hat Linux. Korea's LG Electronics has a Linux tablet PC called Digital iPad, and Linux Personal Digital Assistants (PDAs) are also available. Linux also forms the basis for a number of server appliance platforms, such as the 1U rack-mountable Qube2 and RaQ 4r server appliances from Cobalt Networks. Preconfigured Linux servers are available from Penguin Computing and also from large vendors such as Compaq Computer Corporation and Dell Computer Corporation.

Linux on the mainframe is one new development that has given Linux greater credibility as an enterprise-class operating system. IBM's S/390 platform can run thousands of Linux virtual machines (VMs) on a single mainframe and provides significant cost savings over running Linux on thousands of separate PCs instead. A side effect of this is that stodgy old mainframes are now viewed as a cutting-edge platform for application development, giving a boost to the badly sagging mainframe market.

The most popular server-side applications for the Linux platform are probably the Apache Web server (still used by more than half of all public Web sites) and Samba, a program than enables a Linux server to provide file and print services to other platforms such as Windows and Apple Macintosh. Popular open-source network monitoring tools for Linux include NetSaint and Multi-Router Traffic Grapher (MRTG). Caldera International has released a systems management platform called Volution that allows secure remote administration of thousands of Linux servers and desktops. Volution employs a standard Web browser interface; uses a Lightweight Directory Access Protocol (LDAP)-compliant directory service for storing system object information; provides remote installation, inventory, and monitoring services; and supports policy-based and profile-based management similar to Microsoft's Active Directory directory service and Novell's ZENworks platforms.

Prospects

Some of the largest players in the enterprise computing market have embraced Linux to various degrees. Examples include IBM, Oracle Corporation, Sun Microsystems, Hewlett-Packard, and others. IBM has ported their DB2 Universal Database, WebSphere Application

Server e-commerce platform, and Lotus Notes groupware to Linux. Hewlett-Packard has done many Linux deployments, including running SAP AG's Enterprise Resource Planning (ERP) software on Linux. Compaq, Dell, and Hewlett-Packard all offer pre-installed Linux systems for customers who request it. And Oracle has ported its Oracle 8i database platform to Linux.

IBM's commitment to supporting the Linux platform is probably the biggest development in the Linux story. IBM has demonstrated a 512-node cluster running Linux at the Albuquerque High Performance Computing Center in New Mexico and has built in support for Linux using the SuSE distribution across its full range of computing platforms, from PC servers to its S/390 and zSeries mainframes.

Linux's most significant impact on the enterprise networking scene will probably be the displacement of most versions of the UNIX operating system by Linux. Industry analysts indicate that Linux is already outselling all versions of UNIX combined. Although Windows has firmly established itself as the market leader in application server platforms and is indisputably king of the desktop, Linux is likely to establish itself and remain the number two player in the server arena due to its entrenched use in specific niches of enterprise networking such as DNS name servers, public Web servers, and a few other popular applications.

Notes

An application that runs on one Linux distribution may not automatically run on another, as there are small differences between where different distributions store key system files and other issues. The Linux Development Platform Specification (LDPS) developed by the Linux Standard Base (LSB) project is expected to reduce these interoperability problems by ensuring that an application developed for one distribution runs on others.

The U.S. government, through the National Security Agency (NSA), is also developing a hardened version of Linux called Security-Enhanced Linux. This version will include mandatory access controls for type enforcement and role-based access.

For More Information

A good general source of Linux information is Linux Online at *www.linux.org.* Advanced Linux users can visit Linux Journal at *www.linuxjournal.com.* A popular event for Linux users is LinuxWorld, found at *www.linuxworldexpo.com.*

See Also: *Apache, GNU General Public License (GPL), GNU Object Modeling Environment (GNOME), K Desktop Environment (KDE), open source, POSIX, UNIX*

list server

A program that allows people to subscribe to an e-mail mailing list.

Overview

Organizations typically set up list servers for facilitating the discussion of marketing issues, asking and receiving answers from technical support, announcing new products and services, disseminating tips and tricks for using software, and similar activities. To use a list, users must first subscribe to the list using a special e-mail command, although nowadays many lists also have Web interfaces for doing things such as subscribing, unsubscribing, posting messages, and receiving help. Once a user successfully subscribes to the list, the user generally receives a copy of every message posted to the list, and every message the user posts is distributed to all members of the list. Other common list options include receiving daily collections of messages compacted into a single message and accessing archives of old messages.

Marketplace

Two common list server programs are Listserv and Majordomo. Of these, Listserv is the older and was originally developed for the BITNET/EARN network.

Notes

Do not subscribe to too many mailing lists, because the e-mail traffic might clog up your mailbox.

For More Information

Search CataList, the official catalog of LISTSERV lists at *www.lsoft.com/catalist.html.*

LLC layer

Stands for logical link control layer, a sublayer of the data-link layer in the Open Systems Interconnection (OSI) reference model.

See: *logical link control (LLC) layer*

LMDS

Stands for Local Multipoint Distribution Service, an emerging broadband wireless service with speeds up to 155 megabits per second (Mbps).

See: *Local Multipoint Distribution Service (LMDS)*

lmhosts file

A file used to resolve NetBIOS computer names into Internet Protocol (IP) addresses.

Overview

Lmhosts is a text file that provides a local method for name resolution of remote NetBIOS names into their respective IP addresses on a Transmission Control Protocol/Internet Protocol (TCP/IP) network. Using lmhosts files is an alternative to using WINS servers for name resolution on Microsoft Windows–based networks. Using a WINS server is generally preferable because it reduces administrative overhead.

The lmhosts file contains mappings for hosts on remote networks only. Mappings are not required for hosts on local networks because these can be resolved using broadcasts. If you are using lmhosts files to resolve NetBIOS names on a network, each computer on the network should have an lmhosts file.

Examples

Each line in the lmhosts file contains the IP address of a NetBIOS computer on the network, followed by the NetBIOS name of the computer. The computer name can be followed by optional prefixes that identify domains and domain controllers and allow entries to be loaded into the NetBIOS name cache at startup. Comments are prefixed with the pound sign (#). Here is an example taken from the sample lmhosts file included with Windows 98:

```
102.54.94.97   rhino     #PRE  #DOM:networking
#net group's DC
102.54.94.123   popular    #PRE  #source server
102.54.94.117   localsrv   #PRE  #needed for
                                 the include
```

You can find the lmhosts file in the %SystemRoot%\system32\drivers\etc directory in Windows NT, Windows 2000, Windows XP, Windows .NET Server, and in the \Windows directory in Windows 95 and Windows 98.

Notes

Place the NetBIOS names that need to be resolved most frequently near the top of the lmhosts file because the file is parsed linearly from the beginning.

See Also: *hosts file, Networks file, protocol file, services file*

load balancing

The process of distributing client connections across multiple servers.

Overview

Load balancing is a technique used to increase the reliability of server-based computing. In a typical load balancing scenario, incoming client requests are redirected to different servers on a server farm. The way in which redirection occurs varies with product and implementation, as in the following examples:

- **Round robin:** This method passes each incoming request to the next server in a series. When the final server is reached, the next request is passed to the first server of the series. Each server in a round-robin load balancing scenario receives an equal number of client connections averaged over time.
- **Weighted:** This form of load balancing employs a cost metric to determine how many client connections to direct to each server. For example, if server A has weight 10 and server B has weight 5, twice as many incoming requests will be redirected to server A than server B.
- **Least connected:** In this scenario, incoming requests are forwarded to the server that currently has the fewest number of connections.
- **Fastest:** Here requests are simply directed to the server that responds the quickest.

Uses

The primary use for load balancing in today's networks is in Web server farms. Load balancing increases the reliability of these farms for e-commerce applications by ensuring that user demand can be accommodated for and failure of any one server will not affect the application's overall functioning. The following figure illustrates a typical implementation of Web farm load balancing using a hardware load-balancing device such as Cisco LocalDirector (described later in this article).



Load balancing. *Using load balancing to increase reliability of a Web server farm.*

The biggest issue with Web server load balancing is ensuring that applications that employ persistent connections (a session that spans multiple Hypertext Transfer Protocol [HTTP] requests) work properly. Most modern Web server load balancers accomplish this by using sticky sessions, in which a request that is part of a session already opened is directed to the server in the farm that previously serviced it.

Other newer approaches to Web server load balancing on the market today include

- **Layer 4 load balancing:** Uses Layer 4 switches to ensure persistent HTTP connections are maintained between a client and a server having a specific Internet Protocol (IP) address and port.
- **Layer 5 (or Layer 4/5 or Layer 4/7) load balancing:** Similar to Layer 4 load balancing but includes the capability of differentiating traffic on the basis of Uniform Resource Locators (URLs), not just IP addresses and ports. This approach is sometimes called URL parsing, Web directing, and a dozen other vendor-specific names.

Implementation

The oldest form of load balancing is called Round Robin DNS and takes advantage of a feature of Domain Name System (DNS) name server that allows it to map multiple IP addresses to a single fully qualified domain name (FQDN). The main problem with this approach is that the name server directs clients to different servers without any regard to the availability of those servers. For example, if a server in the farm suddenly goes down, the name server has no way of knowing this and continues to redirect client requests to that server as it goes through the round-robin procedure. Because of this weakness, round-robin load balancing is seldom used anymore.

Hardware-based load balancers are more popular and are typically routers or switches that use application-specific integrated circuits (ASICs) to distribute load quickly and effectively to hundreds or even thousands of connected servers. In a typical scenario, a hardware load balancer will be assigned a "virtual" IP address while the real IP addresses of servers in the farm are hidden behind the load balancer. To the outside world, the farm of servers appears as a single server with a single IP address, the address of the load balancer. Hardware-based load balancers are expensive but provide best performance, and analysts estimate that they own over 60 percent of the load balancer market. Some newer hardware load balancers are better classified as network appliances than switches or routers due to their packaged functionality and ease of use.

Software-based load balancers are rising in popularity and consist of a load-balancing application that is installed on a standard PC or UNIX host. Software-based load balancers are slower than hardware-based ones and typically support only a few dozen servers, but they are cheaper and are an attractive solution for many e-businesses.

Marketplace

The first and still most popular hardware-based load balancer is the LocalDirector from Cisco Systems. LocalDirector sits in front of your server farm and bridges incoming traffic between the external network and the local area network (LAN) segment on which the servers all reside. If you need to load balance servers from several different sites or local area network (LAN) segments, you can use LocalDirector in conjunction with another Cisco product, DistributedDirector, to accomplish this. Other examples of hardware load balancers include ServerIron from Foundry Networks, BIG/ip and Edge-FX Local Cache Cluster from F5 Networks, and products from Alteon WebSystems (acquired by Nortel Networks in 2000), ArrowPoint Communications (now part of Cisco), Coyote Point Systems, and many others.

A popular software-based load balancing solution is Microsoft Corporation's network Load Balancing Service (NLBS), a feature that comes with Microsoft Windows 2000 Advanced Server and replaces the Windows Load Balancing Service (WLBS) of Windows NT 4 Enterprise Edition. NLBS can load balance up to 32 servers and provides basic load balancing functionality at a price anyone can afford (it is free with the Windows 2000 Advanced Server operating system). Other examples of software load balancers include WebSphere from IBM, WSD Pro from Radware, and Central Dispatch/Global Dispatch from Resonate.

See Also: *Domain Name System (DNS), Layer 4 switch, Layer 7 switch, name server, router*

Local Access and Transport Area (LATA)

Service boundaries for local exchange carriers (LECs).

Overview

When the divestiture of AT&T occurred in 1984, 197 separate LATAs were created to specify the service boundaries for different LECs. These LATAs are identified by three-digit numbers that are different from area codes and do not necessarily match the same geographical areas as these codes. Calls made within a LATA are handled by the LEC administering the LATA and are typically local calls but may be long distance if the LATA spans a large enough region. Calls made between LATAs are always long-distance calls and are handled by inter-exchange carriers (ICXs) such as AT&T, MCI/Worldcom, and Sprint Corporation.

The Telecommunications Act of 1996 made some changes to this landscape by allowing LECs to handle inter-LATA traffic under certain conditions. The act also gives the Federal Communications Commission (FCC) full jurisdiction over the boundaries between LATAs.

Examples

LATAs are used in other parts of North America as well. Some examples of LATAs and their associated numbers include

- New York Metro (132)
- San Francisco (722)
- Los Angeles (730)
- Puerto Rico (820)
- Mexico (838)
- British Columbia, Canada (886)

See Also: *inter-exchange carrier (IXC), local exchange carrier (LEC)*

local address

An Internet Protocol (IP) address on the local subnet.

Overview

A host that is located on the same subnet is said to have a local address (with respect to the particular host under consideration). A host with a local address can be reached without the need to traverse any routers. By contrast, a remote address is an address of a host located on a different subnet. To communicate with a host having a remote address, IP packets must be routed across subnet boundaries by routers or Layer 3 switches.

Examples

As an example of a local address, consider a Transmission Control Protocol/Internet Protocol (TCP/IP) network with the following subnetting scheme:

- Network ID = 181.55.0.0
- Subnet Mask = 181.255.240.0

Using the above class B network and custom subnet mask, there will be 16 different subnets of 4094 hosts each, specifically

- Subnet 1 has hosts 181.55.0.1 through 181.55.15.254.
- Subnet 2 has hosts 181.55.16.1 through 181.55.31.254.
- Subnet 3 has hosts 181.55.32.1 through 181.55.47.254.

  …

- Subnet 16 has hosts 181.55.240.1 through 181.55.255.254.

Now consider the following three hosts on the network:

- Host A = 181.55.22.147
- Host B = 181.55.28.12
- Host C = 181.55.43.6

From the point of view of Host A, which is located on Subnet 2:

- Host B is located on the local subnet (Subnet 2), so Host B's address is local to Host A.
- Host C is located on a remote subnet (Subnet 3), so Host C's address is remote to Host A.

See Also: *Internet Protocol (IP), IP address, routing, subnetting*

Local Area Data Channel (LADC)

A telco service for transmitting data using line drivers.

Overview

Also called telco restricted lines, Local Area Data Channel (LDAC) conforms to the Bell 43401 standard published by AT&T and basically specifies DC continuity. This means that metallic (copper) conductors must be used, typically the unshielded twisted-pair (UTP) cabling employed for phone lines. The LADC standard also indicates that these lines must also be unloaded—that is, without terminators, loading coils, or protection circuitry that can add to the inductance of the line and thus distort signals.

LADC lines are available to distances of 3 miles (5 kilometers) from the telco's central office (CO). The longer the distance for a line, the lower the carrying bandwidth supported.

See Also: *central office (CO), unshielded twisted-pair (UTP) cabling*

local area network (LAN)

Typically, a group of computers located in the same room, on the same floor, or in the same building that are connected to form a single network.

Overview

Local area networks (LANs) are the simplest forms of computer networks and enable groups of users to share storage devices, printers, applications, data, and other resources on the network. LANs are typically limited to a single location but can sometimes span several buildings or even a campus. The collection of cabling and networking devices used to build a LAN is known as its infrastructure.

LANs do not contain any telecommunications circuits such as phone lines in the infrastructure—if they do, they are properly called wide area networks (WANs) instead. LANs come in all shapes and sizes, including

- **Workgroup LANs:** Typically a group of workstations deployed in a single room or on a single floor.

- **Shared LANs:** These use legacy hubs and bridges to connect stations.
- **Switched LANs:** These use Ethernet switches to connect stations and have largely displaced shared LANs in the enterprise.
- **Campus LANs:** These LANs span several buildings across a few miles and usually consist of smaller workgroup LANs connected by routers or Layer 3 switches.

Implementation

Building a LAN from a group of stand-alone computers requires the assembly and configuration of a number of components:

- **Network architecture:** The vast majority of today's LANs are of the Ethernet type, usually 10BaseT or Fast Ethernet.
- **Cabling:** This is used to join the computers so they can communicate with one another. The most common type of cabling used in LANs is Category 5 (Cat5) unshielded twisted-pair (UTP) cabling. This cabling is typically installed in a topology called structured wiring, which is essentially a hierarchical or cascaded star topology employing hubs, switches, and routers.
- **Network protocol:** To communicate on a network, computers must speak a common "language" or protocol, the most popular of which is Transmission Control Protocol/Internet Protocol (TCP/IP), which is necessary for Internet connectivity.
- **Network-aware operating system:** This must be installed on the computers to enable them to share their resources with other computers (thus acting as a server) and access resources on other computers (acting as a client). The choice of operating system depends on whether the network will be a peer-to-peer network or a server-based network. Microsoft Windows 98 or Windows Millenium Edition (Me) is a good choice for small peer-to-peer workgroup LANs, while Windows 2000 offers the security and scalability needed to support a larger server-based network.
- **Network interface card (NIC):** This must be installed in each computer in an available slot on the motherboard, together with a software driver, to control the card's functions. The network cabling is then connected to the NIC in each computer to form the actual network.

See Also: *bridge, cabling, Category 5 (Cat5) cabling, Ethernet switch, hub, infrastructure, NetBEUI, network, protocol, router, server, Transmission Control Protocol/Internet Protocol (TCP/IP), unshielded twisted-pair (UTP) cabling, wide area network (WAN)*

local exchange carrier (LEC)

A telco in the United States that provides telephone and telecommunication services for subscribers within a geographic region.

Overview

Traditionally, the *local exchange* part of the term *local exchange carrier* is another word for the telco's central office (CO), and the *carrier* part means they are the company that "carries" telephone and data traffic for their customers. In other words, your local exchange carrier (LEC) is simply the company that sends you a telephone bill each month. The LEC owns the local loop wiring between their CO and their subscribers' premises, and these premises are in a geographic area known as the Local Access and Transport Area (LATA). Any calls that take place within a given LATA are considered local calls and are billed accordingly. A single LEC may have control over the local loop in one or more LATAs.

The largest LECs came into existence with the breakup of AT&T in the early 1980s, which led to the formation of a number of independent Regional Bell Operating Companies (RBOCs). However, a number of smaller, independent LECs in the United States, especially in rural areas, were never part of the Bell system.

LECs directly handle traffic, including both local and long distance types, only within their area of jurisdiction. For subscribers of one LEC to communicate with those in a different LEC, long-distance carriers called inter-exchange carriers (IXCs) are used. In the United

States, the “Big Three” IXCs are Sprint Corporation, AT&T, and MCI/WorldCom.

Types

Several different types of LECs are in the marketplace today:

- **Incumbent Local Exchange Carriers (ILECs):** These include the RBOCs that came into existence through the AT&T divestiture, plus various independent telcos such as Verizon Communications. They are called “incumbent” because they own the local loop wiring in their service areas.
- **Competitive Local Exchange Carriers (CLECs):** These arose as a result of the Telecommunications Act of 1996 and include mainly resellers of voice and Digital Subscriber Line (DSL) services. Some CLECs provide services regionally, but others, such as Intermedia Communications, have become a national presence or transformed themselves into other types of service providers.
- **Building Local Exchange Carriers (BLECs):** These are essentially offshoot CLECs that focus on provisioning voice and data services to office towers, hotels, industrial parks, and so on.

Prospects

The Telecommunications Act of 1996 changed the landscape of the telephone system in the United States by allowing LECs to compete in the deregulated long-distance market and by allowing IXCs to provide services directly to customer premises through mergers, acquisitions, and new technologies. Before 1996, each LEC was essentially an incumbent LEC (ILEC) that was the sole provider of telephone services to subscribers in its geographical region. The Telecommunications Act allowed new companies to become competitive LECs (CLECs) that could compete directly with ILECs in their areas of jurisdiction by mandating the leasing or purchasing of local loop and switching services from the ILECs or installing their own separate distribution and switching systems. LECs have an advantage over IXCs, however, in that they already own a right-of-access to customer premises, but IXCs have an advantage in that they are larger, more highly capitalized companies that can afford to invest heavily in new technologies and services or even acquire LECs outright.

The landscape is still changing after six years, but it appears to many analysts that the Telecommunications Act has largely failed to deliver on its promise of opening up more competition in the telephone and telecommunications industry. Many CLECs, particularly those that specialized in offering digital subscriber line (DSL) services, went out of business during the dot-com bust of 2001. Meanwhile, RBOCs, traditionally viewed as dinosaurs when it comes to implementing technological innovation, have modernized their services and consolidated their positions in the local loop. And the “Big Three” IXCs remain just three, with little expectation of things changing in that arena.

See Also: *central office (CO), Competitive Local Exchange Carrier (CLEC), Incumbent Local Exchange Carrier (ILEC), inter-exchange carrier (IXC), Local Access and Transport Area (LATA), Regional Bell Operating Company (RBOC), telco*

local group

A type of group that exists only on the Microsoft Windows 2000 computer on which it is created.

Overview

Local groups reside within the local security database of the computer on which they are created. Local groups are intended for use only on Windows 2000 computers that are not part of a domain and are used for granting users who are interactively logged on to the computer access to resources on that computer. Local groups can contain only local user accounts from the same machine. You create local groups on a stand-alone Windows 2000 machine using the Local Users and Groups console.

Notes

Another type of Windows 2000 group called domain local groups have a domain-wide scope and can be used to provide users with access to resources located anywhere in a domain.

See Also: *AGLP, built-in group, global group, group*

localhost

The friendly name used in the HOSTS file for the loopback address, a special Internet Protocol (IP) address used to test the protocol stack on a host.

See: *loopback address*

local loop

The portion of the telephone system that connects a subscriber to the nearest telco central office (CO).

Overview

The wiring used in the local loop is typically unshielded twisted-pair (UTP) four-wire copper cabling terminated at RJ-11 jacks in the customer premises. With traditional Public Switched Telephone Network (PSTN) lines that use analog transmission, the maximum distance allowed between the customer premises and the CO is about 3 miles (5 kilometers). In many urban and commercial areas, the local loop has been upgraded to Integrated Services Digital Network (ISDN), which employs the same wiring but provides all-digital transmission for better voice and data connections. Local loop wiring can also carry a combination of voice and data at high speeds using various forms of Digital Subscriber Line (DSL) technologies.



Local loop. *The local loop wiring between a telco CO and the customer premises.*

Prospects

In many respects, the local loop represents the bottleneck in providing subscribers with high speed voice, data, multimedia, and Internet access services. This is because of two issues:

- The copper nature of the local loop wiring makes it much less efficient than fiber-optic cabling at carrying large amounts of information.
- The local loop wiring is owned by the Incumbent Local Exchange Carrier (ILEC) in your area, typically a Regional Bell Operating Company (RBOC). This legislated monopoly means that the main competition for providing customers with broadband services generally has to come from technologies other than traditional copper local loop wiring. Furthermore, because of their monopoly, RBOCs have generally been slow to bring about promised innovation such as fiber to the curb (FTTC), which was promised decades ago but never delivered.

For residential customers, the main competition for the traditional copper local loop consists of cable modem and satellite dish systems. For business customers, cable modems are generally not an option due to the lack of cable television infrastructure in industrial parks and office towers. Instead, business customers have other alternatives, such as Local Multipoint Distribution System (LMDS), a fixed wireless broadband service, and optical Ethernet, which involves provisioning fiber to office towers in dense urban areas.

See Also: *analog transmission, central office (CO), Digital Subscriber Line (DSL), digital transmission, fiber to the curb (FTTC), Incumbent Local Exchange Carrier (ILEC), Integrated Services Digital Network (ISDN), Local Multipoint Distribution Service (LMDS), optical Ethernet, Public Switched Telephone Network (PSTN), Regional Bell Operating Company (RBOC), telco, unshielded twisted-pair (UTP) cabling*

Local Multipoint Distribution Service (LMDS)

An emerging wireless broadband technology operating in the millimeter band of the electromagnetic spectrum.

Overview

Local Multipoint Distribution Service (LMDS) is a new wireless telecommunications technology that can simultaneously carry voice, data, and multimedia at speeds as high as 155 megabits per second (Mbps). LMDS is primarily targeted toward the business market and is designed to help alleviate the bottleneck of the telco local loop. LMDS is simple to deploy and relatively inexpensive, and it provides businesses with speeds higher than those of Digital Subscriber Line (DSL) technologies. It can also be deployed where cable modem infrastructures generally do not exist, such as industrial parks and office towers.

Implementation

LMDS is a cellular communications system in which coverage areas are typically 2.5 to 6 miles (4 to 10 kilometers) in diameter. Each cell is served by one or more LMDS transmitters. A transceiver is deployed with a fixed antenna at the customer premises, usually on a rooftop or other high location (LMDS does not support mobile users and does not support roaming between cells).

LMDS operates in the millimeter range at frequencies between 27.5 and 31.3 gigahertz (GHz). Transmissions in this range require precise line of sight between transmitter and station and are strongly affected by reflections of walls and other surfaces. Since frequencies used by LMDS are those at which water molecules absorb energy (which is how a microwave oven works), rain and moisture can absorb and scatter LMDS transmissions, causing dropouts. Deploying multiple transmitters per coverage area may lessen this effect, however.

LMDS can operate in two configurations:

- **Point-to-multipoint (PMP):** This is the usual way of deploying LMDS and uses a single base station transmitter or “hub” broadcasting to multiple fixed end stations. Range is typically less than 6 miles (10 kilometers) for this configuration.
- **Point-to-Point (PTP):** This is used to connect two LMDS stations and can sustain longer distances up to about 12 miles (19 kilometers).

Prospects

Trial deployments of LMDS are currently underway. The technology is expected to be deployed mainly in dense urban areas by implementing wireless rings to serve a region of customers. The main issue with LMDS is that communications are easily affected by moisture and bad weather, but efforts are underway to work around these problems. Some companies that have licensed LMDS frequencies include Advanced Radio Telecom Corporation, NextLink Communications, Teligent, and WinStar Communications.

See Also: *cellular communications, Digital Subscriber Line (DSL), local loop*

local network

The network on which your computer resides, as opposed to a remote network.

Overview

The local network consists of all computers having the same network number as your machine. For example, on a Transmission Control Protocol/Internet Protocol (TCP/IP) network, if your computer is assigned the IP address 208.16.8.25, then your network ID number is 208.16.8.0, and your local network would consist of all computers having the same network ID number. Each computer on a network has the same network ID number but a different host ID to distinguish it from other hosts on the local network. In the above example, your host ID would be .25 and host IDs for other hosts on your local network might be .26, .27, and so on. The IP address of a host is a combination of the host ID and network ID. For example, if your network ID is 208.16.8.0 and your host ID is .25, your IP address would be 208.16.8.25.

The term *local network* is also used in another context to describe hosts that are on the same physical LAN segment, such as all the hosts connected to the same hub in an Ethernet network. The usage of the term is sometimes vague, and you must determine its meaning from the context in which it is used.

See Also: *IP address, network, subnet, Transmission Control Protocol/Internet Protocol (TCP/IP)*

LocalSystem

A built-in identity in Microsoft Windows 2000 that provides a security context for running operating system tasks.

Overview

The LocalSystem account is a special identity built into the Windows 2000 operating system. LocalSystem has the attributes of a user account but has special privileges:

- It is an implicit member of the Administrators group
- It has full permissions on every operating system object
- It can take ownership of any object
- It has the system right “act as part of the operating system”

LocalSystem is used as a security context for running operating system services. The LocalSystem account can run these services whether or not any user is interactively logged on to the machine.

Notes

The System account on the Windows NT platform was also used as a security context for running services, but it could only do so for individual computers. In other words, if you had five Windows NT computers on a network, there were five System accounts present, one on each computer. The System account on one computer could not be used as a security context for running services on a different computer. This scenario has changed in Windows 2000 and Windows .NET Server, where the LocalSystem account has forest-wide applicability.

See Also: *built-in identities*

LocalTalk

A legacy networking protocol for the Apple platform.

Overview

LocalTalk was originally called AppleBus and operated over serial connections at a speed of 230.4 kilobits per second (Kbps). A LocalTalk segment could have a maximum of only 32 nodes, and network addresses were assigned dynamically using AppleTalk Address Resolution Protocol (AARP). LocalTalk was strictly a Layer 2 protocol only—higher layer functions had to be managed by the operating system itself. LocalTalk is a legacy protocol that was later replaced by AppleTalk, initially in a configuration called AppleTalk over LocalTalk and later AppleTalk Phase II.

See Also: *AppleTalk*

local user account

A user account that exists only on the local machine on which it is defined.

Overview

In Microsoft Windows NT–based networks, a local user account is a user account that resides in the local security database of a particular Windows NT member server or workstation. When a user has a local account on a computer, the user can log on to the computer interactively. In a Windows NT–based network based on the workgroup security model, all user accounts are local user accounts and are created using the administrative tool called User Manager, the version of User Manager for Domains that is installed on stand-alone Windows NT member servers and workstations. In a Windows NT–based network that is based on the domain security model, new user accounts that are created using User Manager for Domains are by default global user accounts that are valid everywhere in the domain and are stored in the Security Accounts Manager (SAM) database on domain controllers. However, in a domain, you can also create a local account with User Manager for Domains by clicking the Account button in the New User dialog box and specifying Local Account as the Account Type. This is generally not recommended because local user accounts are not valid throughout the domain and are valid only for logging on interactively to the computer on which they are created.

In a Windows 2000–based or Windows .NET Server–based network, a local user account is one of three types of user accounts, the others being domain user accounts and built-in accounts. Local user accounts enable users to log on interactively to stand-alone Windows 2000 and Windows .NET servers or client computers in a workgroup and access system resources on the machine for which they have suitable permissions. Domain user accounts allow users to log on to a domain and access resources anywhere in the domain. Local user accounts are created using the Local Users and Groups tool, which is implemented as a snap-in for Microsoft Management Console (MMC). Local user accounts are stored in the local security database on the machine on which they are created, but domain user accounts are created in Active Directory directory service and stored in organizational units (OUs).

See Also: *Active Directory, built-in account, domain user account, global user account*

local user profile

A user profile stored locally on a computer.

Overview

In Microsoft Windows 2000, Windows NT, Windows XP, and Windows .NET Server, a local profile is created for a user the first time the user successfully logs on to his or her computer. If the user does not have a preconfigured roaming user profile at the time of the first logon, Windows 2000 copies the default user profile to the new local user profile folder.

Local profiles are created for all users who interactively log on to computers running Windows 2000 so that they can access their own personal settings on that machine. Each user who logs on to a machine thus has his or her own local profile stored on the machine. Local profiles are stored in the folder Documents and Settings. Each user's profile is stored in a subfolder that is named after the user's username and contains the user's personal settings. The personal settings include both the appearance of the desktop and Start menu and the user's network connections (such as mapped drives). Even if users have a roaming profile that allows them to log on from any machine in the network and obtain their personal settings, each machine also stores a local copy of their profiles in case the network is down when they try to log on.

See Also: *roaming user profile, user profile*

Local Users and Groups

A Microsoft Windows 2000 administrative tool for managing local user and group accounts on a standalone server or workstation.

Overview

Local Users and Groups is available on member servers running Windows 2000 Server and client computers running Windows 2000 Professional that you can use to create and manage local user accounts and local groups on the machine. Local Users and Groups is implemented as a snap-in for Microsoft Management Console (MMC), like other Windows 2000 administrative tools. You can use Local Users and Groups only if a workgroup security model is being used for your network. In a workgroup, each computer manages its own security and maintains its own local security database of account information. If your network uses a domain security model, all user accounts for the domain are stored in the Active Directory database, which contains a distributed domain directory database maintained by domain controllers on your network. You cannot install Local Users and Groups on domain controllers; on these machines, you should use Active Directory Users and Computers for creating domain user accounts.

See Also: *Active Directory, Active Directory Users and Computers, Microsoft Management Console (MMC)*

locking

A mechanism that protects data in a database from being overwritten.

Overview

Locking is a mechanism used to protects a database against data loss when users simultaneously attempt to modify the same database object. Locking synchronizes users' access to the database and prevents concurrent data manipulation problems to ensure that data remains consistent and query results are correct.

Locking provides concurrency in a multiuser environment—that is, it enables multiple clients to simultaneously access and modify a database without the danger of the data becoming corrupted. If one user locks a portion of the database to view or modify data, that data cannot be accessed or modified by any other user until the first user's updates have been committed.

Examples

The Microsoft SQL Server relational database platform employs multigranular locking, in which each database resource is locked at a level appropriate for that kind of resource. The following table shows the various database resources that can be locked in SQL Server, in order of decreasing granularity. This range of granularity allows a balance between concurrency (the ability of multiple clients to simultaneously access a database) and performance (speed). For example, highly granular locking such as row-level locking allows more concurrency (different users can simultaneously modify different rows in the same database table), but this increases system overhead because the server must manage more locks.

Database Resources That SQL Server Can Lock

Locked Resource	*Description*
DB	Locks the entire database
Table	Locks an entire database table, including its data and indexes
Extent	Locks a contiguous group of eight data pages or eight index pages
Page	Locks individual 8-kilobyte (KB) data pages or index pages
Key	Locks a row within an index
RID (row identifier)	Locks individual rows in a table

L

SQL Server uses a number of resource lock modes that specify how concurrent transactions can access different database resources. These include the following:

- **Shared locks:** Allow concurrent transactions to read data—for example, by using transact-SQL SELECT statements. Shared locks allow concurrent reads but lock the resource against modification until the reads are completed. After the data is read, the lock is removed unless a repeatable read is being performed.
- **Exclusive locks:** Lock data so that it can be modified—for example, by using INSERT, DELETE, or UPDATE statements. No other reads or modifications can be performed on the resource while it is exclusively locked.

Other locking modes include update locks, bulk update locks, and intent locks.

See Also: *database, Structured Query Language (SQL)*

log

Any file that contains records corresponding to application or operating system events or conditions, usually arranged sequentially by time.

Overview

Log files are usually delimited text files (such as .csv files) in which each line represents a transaction or logged event, with individual data fields separated by delimiting characters such as commas. Delimited text files can be imported into spreadsheet programs such as Microsoft Excel, database programs such as Microsoft Access, and report and analysis tools such as Crystal Reports for further analysis and graphical display of trends and usage patterns. Relogging is the process of taking a log file and sampling it at larger time intervals to reduce the size of the file for archiving purposes while maintaining the overall trend of data within the log.

Numerous processes within the Microsoft Windows operating systems and the Microsoft BackOffice applications maintain logs. Some log functions include the following:

- Keeping track of transactions performed on an information store or database (as in Microsoft SQL Server or Microsoft Exchange Server)
- Monitoring server or network performance over time when Performance Monitor is used on a Windows NT–based, Windows 2000–based, Windows XP–based, or Windows .NET Server–based network
- Recording details of visitors to Web sites when you use Internet Information Services (IIS)
- Recording the details of modem commands or Point-to-Point Protocol (PPP) transmissions when you use Network and Dial-up Connections to connect to an Internet service provider (ISP)

Regular inspection of log files is often an important component of insuring the security of a software platform or application.

See Also: *security*

Logical Link Control and Adaptation Layer Protocol (L2CAP)

The data-link layer protocol for Bluetooth wireless networking.

Overview

The Logical Link Control and Adaptation Layer Protocol (L2CAP) resides over the Baseband layer, which is the physical (PHY) layer mechanism for Bluetooth communications. L2CAP enables logical channels to be established between different Bluetooth devices. L2CAP identifies different devices using channel identifiers (CIDs), which are also used for sending control information (for example, the L2CAP signaling channel is designated as CID 0x0001).

L2CAP provides both connection-oriented and connectionless services at the data-link layer, provides segmentation and reassembly, and supports protocol multiplexing. L2CAP packages real-time data streams into packets that can be up to 64 kilobytes (KB) in length and employ a little endian byte ordering.

See Also: *Bluetooth*

logical link control (LLC) layer

A sublayer of the data-link layer in the Open Systems Interconnection (OSI) reference model.

Overview

For local area network (LAN) data-link protocols such as Ethernet, the data-link layer is divided into an upper layer called the logical link control (LLC) layer and a lower layer called the media access control (MAC) layer. The MAC layer coordinates access to the physical layer according to a media access control method, which for standard Ethernet is the Carrier Sense Multiple Access with Collision Detection (CSMA/CD) scheme. The MAC layer thus provides services to the LLC layer so that protocol data units can be transferred to the medium without any concern about the broadcast, framing, addressing, or error-detection schemes used. The LLC uses the MAC services to provide two types of data-link operations to the network layer above it: LLC1 for connectionless and LLC2 for connection-oriented data-link communication services (known as Type 1 and Type 2, respectively). These LLC services are grouped into two classes:

- **Class 1 services:** Connectionless services used by applications that do not require error detection or flow control.
- **Class 2 services:** Either connectionless (Type 1) or balanced-mode connection-oriented (Type 2) data transfer services. The LLC provides the error detection and recovery, flow control, and resequencing services needed for connection-oriented data transfer.

Notes

The LLC protocol is based on the earlier High-level Data Link Control (HDLC) protocol. The term *LLC* sometimes refers to the IEEE 802.2 protocol itself, which is the most common LAN protocol implemented at the LLC layer.

See Also: *Carrier Sense Multiple Access with Collision Detection (CSMA/CD), Ethernet, High-level Data Link Control (HDLC), media access control (MAC) layer, Open Systems Interconnection (OSI) reference model*

logoff

The process by which users notify their network's security authority (for example, domain controllers on a Microsoft Windows 2000 network) that they are terminating their session on the network. Users should always log off their computers when they are finished for the day to prevent unauthorized access to the network through their computers by others who might use the building at night. If, as an administrator, you find that users do not log off their computers, configure logon hours restrictions to forcibly disconnect users after work hours. You can also check whether your password policy is too strict, which might encourage users to stay logged on to avoid having to reenter a complex password each time they return to their stations.

Notes

If you are leaving your desk for only a short time, you can lock a machine running Windows 2000, Windows XP, or Windows .NET Server instead of logging off. You do this by pressing Ctrl+Alt+Delete followed by Lock Computer. You can unlock your workstation by pressing Ctrl+Alt+Delete again and reentering username and password. This approach is faster than logging off and allows applications such as your e-mail program to continue running in the background.

See Also: *Active Directory, logon*

logon

The process by which a user's credentials are verified by a network security authority so that the user can be granted access to resources on the local machine or network.

Overview

There are two basic types of logons:

- **Interactive logons:** Occurs when a user sit at the console of his local computer and enters credentials (usually username and password) in the logon dialog box.
- **Remote logons:** Occurs when a user has already logged on interactively to a machine but wants to establish a network connection with a remote computer. For example, if the user tries to map a drive letter to a shared folder on the remote computer, a remote logon must take place during the process so that the remote computer can be sure that the user has the right to perform the action.

L

When a user attempts an interactive logon on a local computer, the user's credentials are verified by a security authority. On Microsoft Windows networks, this security authority may be

- **The local machine itself:** This scenario typically occurs on computers that are configured to belong to a workgroup rather than a domain. In the workgroup security model, each machine maintains its own separate list of valid user accounts in its own local security database. For example, when a user performs an interactive logon to a stand-alone machine running Windows 2000, the machine itself validates the user's credentials.
- **A designated machine or group of machines on the network:** For example, on a Windows 2000–based network that has Active Directory directory service installed, special Windows 2000 servers called domain controllers store and maintain information about valid user accounts for all users on the network. These domain controllers are then used for validating users' logon attempts. When the user tries to log on interactively to his or her local machine, the machine forwards the user's credentials to a nearby domain controller using a mechanism called pass-through authentication. The domain controller authenticates the credentials and then builds and returns an access token to the user, granting that user suitable levels of access to resources on the network.

Notes

Windows 2000 includes a feature called Run As that lets an administrator temporarily log on to a client machine without requiring that the user first log off from his machine. This feature is useful, for example, if an administrator needs to install an application or troubleshoot some problem while at the user's machine.

See Also: *logoff*

logon script

A batch file that automatically runs on a user's client machine every time the user logs on to the network.

Overview

Logon scripts allow administrators to run a special series of commands each time a user logs on to her machine. These commands can perform functions such as

- Configuring the desktop working environment for the user
- Configuring legacy network clients and launching network connections
- Automatically launching certain applications the user will need
- Communicating a "message of the day" and other information to users

On the Microsoft Windows 2000 and Windows .NET Server platforms, logon scripts are primarily used for configuring legacy Windows clients and non-Windows clients that belong to a Windows 2000 network. On a pure Windows 2000 network, logon scripts are rarely needed because Windows 2000 employs Intellimirror technologies for performing tasks such as configuring the user's desktop, synchronizing home folders, and establishing network and printer connections.

Examples

On Windows NT networks, however, logon scripts still perform many useful functions. A typical Windows NT logon script might contain a series of Net.exe commands that synchronize the client computer's clock with a particular server, ensure that mapped network drives are available, restore printer connections, and perform other actions to configure the user's work environment.

The following simple script runs when a Windows client logs on to a Windows NT Primary Domain Controller (PDC). The script synchronizes the workstation's clock with the server, maps the drive letter K to a share on the server, and then exits.

```
net time \\pdc /set /yes >nul
net use k: \\pdc\home
exit
```

See Also: *IntelliMirror, scripting*

long packet error

A random, malformed frame of data that is sent continuously by failed circuitry in a networking component. Better known as jabber.

See: *jabber*

Long Reach Ethernet (LRE)

A new technology from Cisco Systems that supports Ethernet over older telephone wiring.

Overview

Provisioning new high-speed data services to multitenant units (MTUs) such as office towers and hotels can be complex and expensive. In-building digital subscriber line (DSL) is one solution, but this approach can be expensive due to costs of installing Digital Subscriber Line Access Multiplexer (DSLAM) equipment at the customer premises. DSL is also complex to provision because it involves Asynchronous Transfer Mode (ATM) technology and generally ties customers in to a single service provider, their Incumbent Local Exchange Carrier (ILEC). Fixed wireless services are another approach, but these services are currently limited to a few dense urban locations.

To open up the last mile marketplace, Cisco has developed a new technology called Long Reach Ethernet (LRE). This system provides customers with the plug-and-play simplicity of Ethernet running over existing in-building telephone wiring. In addition, LRE can be used to simultaneously carry voice, data, and video traffic over a single wiring infrastructure, and it can simultaneously support Plain Old Telephone System (POTS) analog voice, Integrated Services Digital Network (ISDN), and even asymmetric digital subscriber line (ADSL).

LRE supports data transmission at speeds between 5 and 15 megabits per second (Mbps). It can run over distances as long as 4970 feet (1515 meters), which is considerably greater than the 330 feet (100 meters) that can be achieved using standard 10 Mbps Ethernet. LRE thus allows Ethernet to be deployed in scenarios where previously it could not be used due to distance limitations and nonstandard wiring. LRE also saves money by eliminating the need to deploy a separate networking infrastructure by laying twisted pair or fiber-optic cabling throughout a building.

Implementation

LRE operates over existing telephone wiring and does not require deploying a parallel Category 5 (Cat5) cabling infrastructure or laying fiber. LRE makes use of several Cisco products working together, including

- **Cisco Catalyst 2900 LRE XL switches:** These are available in either 12-port or 24-port configurations.

- **Cisco 575 LRE Customer Premises Equipment (CPE):** These devices have an RJ-11 port for connecting to phone lines and an RJ-45 port for connecting to a computer or network.
- **Cisco LRE 48 POTS Splitters:** These are installed at the customer's private branch exchange (PBX) and allow coexistence of voice and data traffic on the telephone lines.

See Also: *Asymmetric Digital Subscriber Line (ADSL), Asynchronous Transfer Mode (ATM), Digital Subscriber Line (DSL), Digital Subscriber Line Access Multiplexer (DSLAM), Ethernet, Incumbent Local Exchange Carrier (ILEC), Integrated Services Digital Network (ISDN), Plain Old Telephone Service (POTS)*

loop

In routing terminology, a route that causes packets to be forwarded until they time out.

Overview

A routing loop—a packet that enters a loop circle endlessly until its Time to Live (TTL) value decrements to zero and it is dropped by a router interface—is an undesirable thing. Routing loops result in dropped packets and retransmissions and waste network bandwidth.

Early routing protocols such as the Exterior Gateway Protocol (EGP) lacked the intelligence to detect and eliminate loops from their routing topologies. For this reason, EGP was eventually replaced with a superior routing protocol called Border Gateway Protocol (BGP), which guaranteed loop-free forwarding of packets between autonomous systems (ASs) in an Internet Protocol (IP) internetwork. All routing protocols today include mechanisms for detecting and eliminating loops, which is essential in a strongly meshed network topology such as that of the Internet.

See Also: *Border Gateway Protocol (BGP), Exterior Gateway Protocol (EGP), routing*

loopback

A test circuit that goes from one device to another and back again.

Overview

Loopback tests are used to check line integrity and the proper functioning of customer premises equipment and to diagnose and troubleshoot problems with telecommunications equipment. Loopback tests can be performed by wide area network (WAN) access devices such as Channel Service Unit/Data Service Units (CSU/DSUs) and routers to place calls to themselves over a WAN to test the WAN link's integrity.

Implementation

In loopback testing, a test signal is typically sent from a service provider's central office (CO) to the customer premises and is returned or echoed by the customer premises equipment (CPE) back to the service provider. If the loopback signal fails to return, the WAN link is down and must be repaired. If the signal returns, the device compares the original signal with the returned one; any discrepancies can be used to troubleshoot communication problems.



Loopback. *An example of how loopback testing can be used to verify the integrity of a telecommunications link.*

Examples

One place where loopback testing is valuable is for testing Integrated Services Digital Network (ISDN) lines. If the Service Profile Identifiers (SPIDs) and ISDN directory numbers have been configured for your ISDN interface, a loopback test will determine whether

- You can connect with your provider's ISDN exchange. If not, you might have a cable or interface problem.
- Your ISDN numbers are correctly assigned.
- You have caller ID or other advanced ISDN services on your line.

Another type of loopback test is called a local loopback test. This is often used with WAN access devices to test networking connectivity with locally attached network devices. You can also implement a local loopback test by having network application software place a call to the WAN access equipment and having the equipment return an echo to the application.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), customer premises equipment (CPE), Integrated Services Digital Network (ISDN), router*

loopback address

A special Internet Protocol (IP) address used to test the protocol stack on a host.

Overview

In Transmission Control Protocol/Internet Protocol (TCP/IP) networking, the loopback address is the special IP address 127.0.0.1. The loopback address can be used to test the protocol stack on a host even when the host is not connected to a network. For example, to test whether TCP/IP is installed and configured correctly on a machine running Microsoft Windows, type **ping 127.0.0.1** at the command prompt. Alternately, you can type the command **ping localhost** to achieve the same result since the Hosts file on a Windows machine resolves the friendly name localhost into the IP address 172.0.0.1. Finally, you can even ping any legal IP address of the form 127.x.y.z to test your TCP/IP protocol stack. If this test produces an error, either your network interface card (NIC) is incorrectly configured or your protocol stack is corrupt. If the configuration looks correct, try removing and reinstalling TCP/IP on your machine to fix the problem. If that fails, try reinstalling the driver for your NIC or replacing the NIC.

See Also: *hosts file, IP address, ping, Transmission Control Protocol/Internet Protocol (TCP/IP)*

LPD

Stands for Line Printer Daemon, the UNIX daemon used for spooling print jobs.

See: *Line Printer Daemon (LPD)*

LPQ

Stands for Line Printer Queue, a UNIX command used for querying the status of a print queue.

See: *Line Printer Queue (LPQ)*

LPR

Stands for Line Printer Remote, a UNIX network command used to submit print jobs to print servers.

See: *Line Printer Remote (LPR)*

LRE

Stands for Long Reach Ethernet, a new technology from Cisco Systems that supports Ethernet over older telephone wiring.

See: *Long Reach Ethernet (LRE)*

LTO

Stands for Linear Tape Open, a high-capacity tape backup technology.

See: *Linear Tape Open (LTO)*

MAC address

A Layer 2 address for a network node.

Overview

On an Ethernet network, a MAC address is a unique 6-byte (48-bit) address that identifies a computer, router interface, or other node on the network. The *MAC* in the term *MAC address* stands for media access control, a sublayer of the Layer 2 or data-link layer of the Open Systems Interconnection (OSI) reference model for networking. MAC addresses are sometimes called Ethernet addresses, hardware addresses, or physical addresses.

MAC addresses enable devices on a network to communicate with each other. On an Ethernet network, for example, each frame contains a source MAC address and destination MAC address in its header information. Devices such as bridges and Layer 2 switches examine the source MAC address of every frame received and then use these MAC addresses to dynamically build internal routing tables for directing further traffic. They then use these tables to forward future frames received to the specific port or network segment on which the station having that particular destination MAC address resides.

Implementation

On a computer, the MAC address is assigned to the network interface card (NIC) that is used to connect the computer to the network. The MAC address is typically hard-coded into the card's read-only memory (ROM). Some cards come with a software utility that you can use to change the card's MAC address, but this is generally not a good idea. If you accidentally configure two network cards on your network to have the same MAC address, address conflict problems will result and the computers will not be able to communicate on the network. Token Ring cards, however, actually require you to assign a unique MAC address to them before they will work.

The uniqueness of MAC addresses for network devices is ensured by the Institute of Electrical and Electronics Engineers (IEEE), which allocates vendors of networking devices specific blocks of MAC addresses. The first 3 bytes (24 bits) represent the manufacturer of the card, and the last 3 bytes (24 bits) identify the particular card from that manufacturer. Each group of 3 bytes can be represented by 6 hexadecimal digits, forming a 12-digit hexadecimal number that represents the entire MAC address. Examples of manufacturer 6-digit numbers include the following:

- 00000C (Cisco Systems)
- 00001D (Cabletron Systems)
- 0004AC (IBM)
- 0020AF (3Com Corporation)
- 00C0A8 (GVC Corporation)
- 080007 (Apple Computer)
- 080009 (Hewlett-Packard Company)

In order for computers to communicate on a network, frames must be addressed using Layer 2 or MAC addresses. To simplify network communications, however, computers are given Layer 3 addresses instead, which in Transmission Control Protocol/Internet Protocol (TCP/IP) consist of IP addresses. A TCP/IP protocol called Address Resolution Protocol (ARP) is then used to translate Layer 3 addresses into Layer 2 addresses.

Notes

To determine the MAC address of your computer's NIC, use the following commands:

- Type **ipconfig /all** at the command prompt in Microsoft Windows 2000, Windows NT, Windows XP, and Windows .NET Server.
- Enter **winipcfg** at the Run box in Windows 95 or Windows 98.

See Also: *Address Resolution Protocol (ARP), Ethernet, frame, IP address, media access control (MAC) layer, Open Systems Interconnection (OSI) reference model*

Macintosh

A personal computing platform from Apple Computer.

Overview

The Apple Macintosh platform incorporates both a hardware platform and an operating system called MacOS. The original Macintosh hardware platform employed the 680x0 series of microprocessors from Motorola and now uses the Reduced Instruction Set Computing (RISC)-based PowerPC processor developed jointly by Apple, IBM, and Motorola.

The MacOS operating system incorporated a number of innovations into personal computing, including a graphical user interface (GUI) with resizable windows, a mouse, icons for applications, and common activities such as creating Notes and deleting files to the Trashcan. Many of these innovations had been developed earlier by the Stanford Research Institute and the Xerox Palo Alto Research Center (Xerox PARC) and were later licensed by Apple for use by Microsoft Corporation in its Microsoft Windows operating system platform.

History

The Macintosh was first released by Apple in 1984 and quickly became popular with high-end personal computer users. Starting from version 1 in 1984, the MacOS operating system has continued to evolve, as MacOS 8 introduced a new look for the desktop in 1997 and MacOS 9 made significant enhancements in the file system in 1999. The new MacOS X, released in 2001, marked a significant departure from earlier operating system versions by basing the kernel upon a free version of UNIX.

Uses

The Macintosh platform has established a niche for itself in a number of industry sectors, including desktop publishing, graphics, and animation. It is also popular among university professionals. While holding a much smaller share of the market than Microsoft Windows, the Macintosh is a popular alternative desktop platform, but it has made few inroads into the server marketplace. Popular Macintosh platforms include the iMac, iBook, and Power Macintosh versions.

Notes

Using Services for Macintosh, an optional feature of Microsoft Windows 2000, Macintoshes and Intel-based computers can operate together on the same network. Services for Macintosh enables Windows 2000 servers to support Macintosh client machines by emulating an AppleShare server and to provide Macintosh clients with file and print sharing service and AppleTalk routing capability. AppleShare is a file-sharing protocol that is a part of AppleTalk, a suite of networking protocols developed by Apple for its Macintosh computing platform.

For More Information

Visit Apple at *www.apple.com.*

See Also: *Apple Open Transport, AppleShare, AppleShare IP, AppleTalk, UNIX, Windows 2000*

MAC layer

Stands for media access control layer, a sublayer of the data-link layer.

See: *media access control (MAC) layer*

MADCAP

Stands for Multicast Address Dynamic Client Allocation Protocol, an extension to the Dynamic Host Configuration Protocol (DHCP) for dynamic assignment of multicast addresses.

See: *Multicast Address Dynamic Client Allocation Protocol (MADCAP)*

mail client

Software that provides users with an interface for creating, sending, receiving, viewing, and storing e-mail messages.

Overview

Most electronic messaging systems are client/server based, in which users send and receive messages using mail clients and mail servers are used to store and forward mail between users. An example of a client/server messaging system is the combination of Microsoft Exchange Server, a powerful platform for messaging and collaboration, and Microsoft Outlook, the premier messaging client from Microsoft Corporation.

Other popular mail clients include

- Microsoft Outlook Express, a free mail and news client included with Microsoft Windows platforms
- Eudora, developed by QUALCOMM, which is available in a full professional version and a shareware version
- Netscape Messenger, which is part of the Netscape Communicator suite of Internet tools
- Pine and Elm, which are command-line mail clients used in UNIX environments

See Also: *e-mail, Exchange Server, mail system, Simple Mail Transfer Protocol (SMTP)*

mailslot

An interprocess communication (IPC) mechanism.

Overview

Mailslots provide connectionless, datagram-based one-to-one or one-to-many communication between processes on different computers running versions of Microsoft Windows. Mailslots are implemented in Microsoft Windows as file system drivers and, therefore,

- Are opened by requests made from the redirector
- Take full advantage of the features of file system drivers, such as security and validation

Mailslots are similar to named pipes, another interprocess communication mechanism. Although named pipes support only point-to-point, bidirectional communications, mailslots support point-to-multipoint, unidirectional communications.

Uses

Mailslots were originally developed for Microsoft OS/2 LAN Manager and have been maintained in later versions of Microsoft Windows for purposes of backward compatibility. They are usually used for broadcast purposes, such as service announcements in the Computer Browser service on Windows 2000 and for the WinPopUp messaging tool in Windows 95 and Windows 98.

See Also: *interprocess communication (IPC), named pipe, point-to-multipoint, point-to-point*

mail system

Any set of applications used to support e-mail messaging between a group of users within an organization or between users in different organizations.

Overview

E-mail has become as indispensable to modern business as the telephone or fax machine. To implement e-mail within a company, you need to deploy the elements of a mail system. A typical mail system has two basic components:

- **Client software:** Employed by users for composing, sending, receiving, and viewing messages
- **Server software:** Used for storing and transporting messages across a network or telecommunications system

Architecture

Mail systems generally employ one of two kinds of architecture:

- **Shared-file mail systems:** Here the client software initiates and maintains all messaging activity. The server is essentially a passive file server and is usually called a postoffice. The client regularly polls the postoffice for new messages that have arrived for the user, and if they are found, the client downloads and displays them for the user to read. An example of a shared-file mail system is Microsoft Mail 3.*x*. Advantages of shared-mail systems include low server-end requirements and simple maintenance. Disadvantages include limited security, high processing load for the client, and poor scalability.

- **Client/server mail systems:** Here the mail server and client share the task of processing messages. An example of a client/server mail system is the Microsoft Exchange Server/Microsoft Outlook combination. Advantages of client/server mail systems include lower network traffic, scalability, and security. The main disadvantage is that they require more powerful servers than shared-file mail systems do.

Mail systems can also be distinguished by the address formats they employ. Examples of mail address formats include industry-standard formats such as the Simple Mail Transfer Protocol (SMTP) used on the Internet and the Originator/Recipient (O/R) format developed by the International Telecommunication Union (ITU) for its X.400 messaging standards. Examples of proprietary address formats include the Microsoft Mail version 3.*x* format and the Lotus cc:Mail format. The following table illustrates examples of these different address formats.

Examples of Address Formats Used in Electronic Messaging

Address Format	*Example*
SMTP	mitch@northwind.microsoft.com
X.400 O/R	C=US;a=Sprint;p=microsoft; o=northwind;s=Tulloch;g=Mitch;
Microsoft Mail	microsoft/northwind/mitch
cc:Mail	Tulloch, Mitch at northwind

Marketplace

The most popular mail system used in the corporate world today is Microsoft Corporation's Exchange Server platform, which can be deployed with a variety of clients, including

- **Microsoft Outlook:** A full-featured messaging, scheduling, and collaboration client
- **Microsoft Outlook Express:** A lightweight mail and news client included free with Microsoft Windows versions
- **Outlook Web Access (OWA):** A Web application for Microsoft Exchange Server that allows users to access their mail using a Web browser such as Microsoft Internet Explorer

Exchange Server provides a comprehensive messaging solution that supports

- Internet standard Simple Mail Transport Protocol (SMTP) messaging
- Connectivity with legacy mail systems such as Microsoft Mail and IBM PROFS/SNADS
- Connectivity with foreign mail systems such as Lotus cc:Mail, Novell GroupWise, and X.400 messaging systems

Exchange can be deployed as a messaging backbone within a heterogeneous mail system environment and also includes a Migration Wizard that lets you migrate users and mailboxes from legacy and foreign mail systems to Exchange. Consolidation of multiple disparate mail systems into a single messaging system through migration can both simplify administration and reduce costs.

See Also: *e-mail, Exchange Server, Simple Mail Transfer Protocol (SMTP), X.400*

mainframe

A general term for a high-level, typically large computer that is capable of performing demanding computational tasks.

Overview

Mainframes were the original computing platform developed at the dawn of the computer age in the 1950s and 1960s. Mainframe computers typically operated as centralized computing systems in which dumb terminals were attached through serial connections to a central mainframe computer. Users entered text-based commands into these terminals, and the terminal forwarded the commands to the mainframe, where all the processing was performed. The results of the processing were returned to the terminal and displayed. Modern mainframes typically offer standard 3270 or 5250 terminal communication and also support connections to "smart terminals"—desktop computers that are connected to the mainframe but also have their own computing power.

Mainframe computing established itself in government, industry, and large enterprises as the standard platform for information processing. Purchasing and running mainframes involved considerable expense and required specially trained personnel, so generally only the largest companies and organizations purchased them. Smaller businesses could access mainframe services by submitting batch jobs through remote terminals and paying the company owning the mainframe for processing cycles used.

Vendors of mainframes include IBM, Unisys Corporation, and Hitachi Data Systems, with IBM being the dominant player in today's marketplace. The most widely used mainframe platform is IBM's S/390 system, and a popular midframe platform is IBM's AS/400 system.

Prospects

Mainframe computing went into eclipse in the 1980s and 1990s with the emergence of the PC and client/server computing paradigm, but in recent years, mainframes have been making a comeback as a platform for running Web applications. Many corporations have repurposed older mainframes as Web application platforms, and modern mainframes can run thousands of UNIX or Linux "virtual servers" simultaneously on one physical machine. Once relegated to the role of legacy platform, "big-iron" mainframes are now viewed as fashionable platforms for e-commerce and other Internet-related business paradigms.

Despite the rapid evolution of computing over the last two decades, much of the information processing performed in the government, financial, and industrial sectors still employs traditional mainframes running large COBOL applications to perform functions such as records processing, accounting, and payroll functions.

Notes

Microsoft Host Integration Server can be used as a gateway to provide users on Microsoft Windows networks with access to data stored on IBM S/390 mainframes and AS/400 midframe systems.

For More Information

Learn about the IBM S/390 platform at *www.ibm.com/servers/s390/pes.*

See Also: *3270, 5250, Host Integration Server, terminal*

MAN

Stands for metropolitan area network, which traditionally represents a network spanning a metropolitan area.

See: *metropolitan area network (MAN)*

Management Information Base (MIB)

A database of information about a device that is managed using Simple Network Management Protocol (SNMP).

Overview

A Management Information Base (MIB) is a collection of information about managed devices, such as computers, hubs, routers, and switches. MIBs store information about the configuration of these networking components, such as the version of the software running on the component, the Internet Protocol (IP) address assigned to a port or interface, and the amount of available disk space for storage. MIBs thus function as a kind of directory containing information about network settings and resources on managed devices.

Architecture

The SMNP data within an MIB is organized in hierarchical fashion in the form of a tree. The structure of the MIB tree is defined by a number of Internet Engineering Task Force (IETF) standards, including RFCs 1155, 1213, 1514, and 1759.

The generalized MIB tree contains several kinds of branches:

- Public branches that are defined by RFCs and are the same for all SNMP managed devices
- Private branches that are defined by the companies and organizations to which these branches are assigned



Management Information Base (MIB). *The general structure of the SNMP MIB hierarchy.*

The diagram illustrates the general structure of the MIB tree, which consists of a number of objects represented in ASN.1 notation. Note that a managed device will typically contain only the portion of the entire MIB tree that is relevant to its particular operation. The root of the MIB tree is International Organization for Standardization (iso), followed by Organization (org), Department of Defense (dod), and then Internet (internet). The main public branch is then Management (mgmt), which defines network management parameters common to devices from all vendors. Underneath mgmt is MIB-II (mib-2), and beneath this are branches for common management functions such as system management, host resources, interfaces, and printers. For example, in the diagram we see that the root of the MIB branch that contains objects for SNMP manageable printers is called Printer. In MIB notation, this object is uniquely defined by the text string

```
.iso.org.dod.internet.mgmt.mib-2.printer
```

Alternatively, MIB objects are also assigned a numerical label (called an object identifier or OID) that provides a more compact representation of these objects than text strings can provide. Using the numerical values in the diagram, the root Printer object would be uniquely described by

.1.3.6.1.2.1.43

The Private branch of the MIB tree contains branches for large companies and organizations. These are organized under an object called Enterprise, and each vendor has a root branch node under this object. For example, IBM's root branch node is ibm (2), Cisco Systems is cisco (9), Sun Microsystems is sun (42), Microsoft LAN Manager MIB II is lanman (77), and Microsoft Corporation is microsoft (311). Vendors can apply to the Internet Assigned Numbers Authority (IANA) to have specific MIB numbers reserved for their enterprise. Each company or organization has complete authority over what objects will be created within their own branch of the MIB tree and what OIDs will be assigned to each object. All MIB objects must comply with a common definition of SNMP information called Structure of Management Information (SMI), which defines the various data types allowed.

Using Microsoft (.1.3.6.1.4.1.311) as an example of an enterprise, various MIB branches are defined under its root node, as seen here:

.1.3.6.1.4.1.311.1.3 for Dynamic Host Configuration Protocol (DHCP)

.1.3.6.1.4.1.311.1.7.2 for File Transfer Protocol (FTP)

.1.3.5.1.4.1.311.1.7.3 for Hypertext Transfer Protocol (HTTP)

and so on.

Implementation

MIBs are incorporated into special software called SNMP agents that run on SNMP-manageable devices. This is done by using MIB files, which are plain text files constructed using a special format. Once these MIB objects are compiled by the agent software, the device can be managed using a network management system that supports SNMP. You can use SNMP commands to retrieve the value of a MIB object or, in some cases, to change the object's value.

For More Information

Try out the MIB Browser at *www.ibr.cs.tu-bs.de/cgi-bin/sbrowser.cgi.*

See Also: *network management, Simple Network Management Protocol (SNMP)*

Management Information Format (MIF)

A standard format for describing hardware and software management information.

Overview

The MIF format and Desktop Management Interface (DMI) specification were developed by the Distributed Management Task Force (DMTF), an organization composed of computer industry leaders whose aim is to lead the development, adoption, and unification of standards for managing systems. MIF can be used in conjunction with DMI to manage networked PCs using systems management software such as Microsoft Systems Management Server (SMS).

Implementation

The MIF database on a computer system is implemented as a collection of plain text files called MIF files. MIF files are text files that are supplied with each manageable hardware or software component installed on the system and that contain information about the attributes of that component. These MIF files provide system management software with configuration information concerning the various hardware and software components on the system. A program called a DMI Service Provider that runs locally and is resident on the system being managed collects and manages the information from MIF files and delivers it to the central management station. You can retrieve and display the information in the MIF database using any standard management interface (MI) utility.

Notes

Microsoft SMS uses six types of MIF files for collecting and storing information in the SMS database:

- PersonalComputer (.mif)
- SMSEvent (.emf)
- UserGroup (.umf)
- JobDetails (.jmf)
- PackageLocation (.pmf)
- CustomArchitecture (.mif)

SMS can also use MIF files to add information to the SMS database about objects such as routers with custom architectures. Note that MIF files differ slightly in syntax between SMS 2 and the earlier SMS 1.2.

See Also: *Desktop Management Interface (DMI), Distributed Management Task Force (DMTF), Systems Management Server (SMS)*

Management Service Provider (MSP)

A company that manages the IT (information technology) infrastructure for other businesses.

Overview

Management Service Providers (MSPs) are a new breed of service provider that evolved out of the changing application service provider (ASP) marketplace. MSPs offer outsourced IT services that can include

- Managing desktop computers and their applications
- Monitoring and troubleshooting servers and their applications
- Managing network infrastructure devices such as routers and switches
- Managing network security and virus protection

MSPs are particularly appealing to startups, small and mid-sized businesses, and e-commerce companies where rapid time-to-market is essential and where the hiring or training of staff with the required expertise may be too expensive. Instead of purchasing expensive and complex systems management platforms such as HP Openview and IBM Tivoli, outsourcing system and network management tasks to an MSP is a viable option for companies that lack the capital resources or personnel to implement these systems. In addition, MSPs can keep rapidly evolving high-tech companies from being caught in the trap of technological obsolescence by obviating the need to lock in to management systems that may become legacy platforms.

MSPs are part of an evolving breed of xSPs that include ASPs and storage service providers (SSPs). MSPs generally provide their services to client companies on a subscription basis, helping smaller companies avoid the high capital outlay of running their own IT department. MSPs differ from ASPs, whose primary aim is servicing end users on behalf of companies—MSPs instead provide high-level services to businesses and IT departments.

Marketplace

The MSP marketplace is new and evolving rapidly, but some of the players that have made names for themselves include InteQ Corporation, Luminate (now part of EMC Corporation), Manage.Com, Nuclio Corporation, SilverBack Technologies, and Triactive.

For More Information

To learn more about the MSP marketplace and where it is headed, you can visit the MSP Association online at *www.mspassociation.org.*

See Also: *application service provider (ASP), storage service provider (SSP), xSP*

Manchester coding

A line coding mechanism used in 10 megabit per second (Mbps) versions of Ethernet.

Overview

Manchester encoding is the technology used since 1979 to convert information into electrical signals for all versions of 10 Mbps Ethernet, including 10Base2, 10Base5, and 10BaseT.



Manchester coding. *Example of how Manchester coding works for standard Ethernet.*

Manchester coding employs a two-state transition of line voltage to represent one bit of information. In other words, two baud (voltage changes) are used for one bit (piece of information). A binary 0 is represented by a transition from high to low voltage in the time set for transmitting one bit (that is, one “bit time”), while a binary 1 is represented by a transition from low voltage to high. For Ethernet networks, the high voltage is typically +0.85 volts and the low is typically -0.85 volts, making each voltage transition equal to 1.7 volts. This also results in Manchester encoding being balanced for DC operation, which enables signals to pass through devices such as transformers without being corrupted.

Manchester coding enables data to be transmitted between two stations without the need for an extra clocking signal to synchronize communications between the stations. This is possible because voltage transitions take place in the middle of each bit transmission interval, which establishes a timing pattern between stations. The mid-interval voltage changes thus allow the sending and receiving stations to maintain proper synchronization with each other in order to ensure the integrity of the transmission. Because of the extra transition per bit that is used for clocking purposes, Manchester coding is only 50 percent efficient—for example, a 20-megahertz (MHz) bandwidth is required to produce a 10-Mbps data transmission rate.

Advantages and Disadvantages

Manchester encoding has the advantage of being relatively easy to encode (or decode) information. Manchester encoding was selected as the line-coding mechanism for 10 Mbps Ethernet simply because in those days network devices such as hubs, bridges, and network interface cards (NICs) had limited processing capabilities and could easily support Manchester. Another factor in this choice was that coaxial cabling, the original media format used by Ethernet, had a high bandwidth capability and could easily support the 20 MHz signaling required to transmit Ethernet frames at 10 Mbps.

Because Manchester is a relatively wasteful encoding scheme, and with advances in processor power for network devices, newer flavors of Ethernet such as Fast Ethernet and Gigabit Ethernet (GbE) do not employ Manchester.

Notes

Another version of this line coding mechanism called differential Manchester encoding represents binary 0 by a voltage transition at the start of the bit-interval, and binary 1 by no transition at the start of the bit-interval. In both cases, a transition takes place in the middle of the interval for synchronization purposes. Differential Manchester encoding is used for IEEE 802.5 Token Ring networking.

mandatory user profile

A roaming user profile in Microsoft Windows 2000 and Windows .NET Server that the user cannot modify.

Overview

Mandatory user profiles are typically configured by administrators who want to prevent users from modifying their desktops so that administrators can reduce the time they spend troubleshooting modifications or enforcing uniformity because of company policies. Mandatory profiles can also be used for several users who require the same desktop configuration. The administrator can create a mandatory profile and use it for the entire group of users. Changing the mandatory user profile once affects all of the users assigned to it. This simplifies the administrator's job when desktops require upgrading or additional applications.

Because a mandatory user profile is a type of roaming user profile and is therefore stored on a network server, users can access their personal desktop settings from any machine on the network. Mandatory user profiles are configured as read-only, however, so that users cannot permanently change their desktop settings. They can reconfigure their desktop for the duration of the current logon session, but once they log off, their changes are lost.

Implementation

To change a roaming user profile into a mandatory one, simply place the user's roaming profile on the file server where user profiles are stored and rename Ntuser.dat to Ntuser.man. This makes the roaming user profile read-only from the user's perspective.

Notes

Windows 95 and Windows 98 also support mandatory user profiles in conjunction with networks based on Windows NT or Windows 2000.

See Also: *local user profile, roaming user profile, user profile*

manual switch

Any manually operated (as opposed to electronically operated) switch used for switching between peripherals or other network devices.

Overview

Manual switches generally cost less than electronic switches that have similar features and capabilities. They are available in a variety of configurations for different kinds of uses and typically have rotary switches on the front and connectors on the back. These connectors could be standard DB9, DB15, RJ-11, RJ-45, RS-232, V.35, BNC, or Centronics connectors.



Manual switch. *Two manual switch configurations: a many-to-one switch and an X switch.*

Manual switches are typically used in high-security environments in which a user can access a device only by physically switching to it. Some manual switches include key locks that control access.

Types

Examples of different types of manual switches include the following:

- **Stand-alone manual switches:** Generally small boxes with a rotary switch on the front and a set of connectors on the back. They can be used for switching connections between printers, monitors, keyboards, and other devices.
- **Rack-mounted manual switches:** Standard 19-inch (48-centimeter)-wide rack-mounted boxes, typically with a number of rotary switches on the front and connectors on the back. These are used more rarely and essentially combine a number of stand-alone switches into one rack-mounted box.
- **Many-to-one switches:** Allow several users to share one device or allow one user to access different devices. For example, a user can use a many-to-one switch to manually switch between a color laser printer and a black-and-white printer. Or an administrator can manually switch a server from a primary 10BaseT Ethernet network to a secondary network. These switches are typically either two-to-one or four-to-one switches.
- **X switches:** Allow several users to share several devices in different configurations. These switches are typically two-to-two switches.
- **Dual switches:** Allow you to switch two connectors at once.

See Also: *switch*

MAPI

Stands for Microsoft Application Programming Interface, a Microsoft technology that allows developers to use the Windows messaging subsystem for writing messaging applications.

See: *Messaging Application Programming Interface (MAPI)*

mapped network drive

A shared folder on a network that has been associated with an available drive letter on a local PC.

Overview

A mapped network drive enables a shared folder on a remote computer to behave as a logical drive on the local computer. Mapped drives can be created in all versions of Microsoft Windows, typically using procedures such as the following:

- Right-click on My Computer, Network Neighborhood, or My Network Places (depending on your version of Windows) on the desktop and select Map Network Drive from the shortcut menu. Choose an available drive letter, enter the Universal Naming Convention (UNC) path to the shared folder, and specify credentials to gain access to the shared folder.
- Click the Map Network Drive button on the toolbar in Windows Explorer and continue as described in the first procedure.
- From a command prompt, use the Net Use command.

Notes

An alternative way of accessing a shared folder on a network server is using the Run command. This method does not require you to use an available drive letter as mapping a drive does. Simply choose Run from the Start menu, and then type the UNC path to the network share you want to access.

See Also: *Universal Naming Convention (UNC)*

markup language

A language used to add information or provide additional meaning to a document.

Overview

Markup languages typically consist of a set of symbols called markup and a set of syntax rules defining how markup should be used. There are generally four types of markup:

- **Functional:** Markup that adds new functionality to a document, such as embedding images or hyperlinks
- **Semantic:** Markup that describes the document's content, such as the title or purpose of the document
- **Structural:** Markup that defines how a document is structured, such as headings, paragraphs, and lists
- **Stylistic:** Markup that adds style formatting to the document, such as words in bold or italic

History

Markup languages first appeared in the computing world in the 1960s. Soon afterward, attempts were made to unify different types of markup languages, an effort that led in 1986 to the Standardized Generalized Markup Language (SGML) becoming established as an International Organization for Standardization (ISO) standard called ISO 8879. In 1991 SGML was used by Tim Berners-Lee to create a simple markup language called Hypertext Markup Language (HTML) that could be used with the newly developed Hypertext Transfer Protocol (HTTP) to deliver hypertext (linked content) over the Internet. Limitations in HTML led the World Wide Web Consortium (W3C) to propose the new Extensible Markup Language (XML) in the late 1990s. XML is rapidly headed toward becoming the standard language for communicating information over the Internet.

Types

The three kinds of markup language described above have similarities and differences, such as the following:

- **SGML:** This is a complex language that was never implemented with any success in the computing field. SGML documents are difficult to interpret and require the use of a document type definition (DTD), which specifies the syntax rules by which SGML documents are created. SGML instead evolved to become a metalanguage used to define other markup languages, for example, HTML, which is considered an SGML application.
- **HTML:** This language has become more wildly popular than anyone could have imagined and is the foundation for most of the e-commerce and e-business done today. HTML lets you create

simple Web pages for communicating information and, in its basic essence, is so simple anyone can learn to use it. Most Web pages are created using special HTML editors instead, however, rather than requiring that HTML tags (markup) be added manually to plain text documents. The main drawbacks to HTML that led to the search for a replacement (later found in XML) are the limitations of the fixed tag set used by HTML, the fact that HTML can only be used to present information rather than to communicate the meaning of a document, and that data hierarchies are not supported (HTML is flat).

- **XML:** This markup language is basically a bare-bones version of SGML (the DTD for XML is only about 20 percent the size of that for SGML). XML has the expected advantages over HTML that a successor would be expected to have, namely, support for creating user-defined tags, ability to describe both the presentation and meaning of a document, and support for data hierarchies.

See Also: *document type definition (DTD), Hypertext Markup Language (HTML), Hypertext Transfer Protocol (HTTP), International Organization for Standardization (ISO), World Wide Web Consortium (W3C), XML*

master boot record (MBR)

A key data structure on a hard disk.

Overview

The master boot record (MBR) performs an essential role on a hard-disk system of a computer: when a computer boots up, the basic input/output system (BIOS) executes a small portion of code residing in the MBR. This code scans the partition table (found within the MBR) to determine which is the active partition, then scans the active partition to locate the boot sector on this partition, loads the code it found in this boot sector into RAM (random access memory), and then transfers control to this resident code to continue execution or the boot process.

Sometimes the MBR for a disk system can become corrupt—for example, when a system is invaded by an MBR virus. In this case, when you try to boot your system, you may see one of the following messages:

- Error loading operating system
- Invalid partition table
- Missing operating system

In Microsoft Windows 2000 and Windows .NET Server, you can sometimes repair corruption of the MBR by using the Recovery Console's Fixmbr command.

master browser

A Microsoft Windows 2000 computer that participates in the Computer Browser service.

Overview

The master browser collects and maintains a list of available servers that have shared network resources in its domain. This list, known as the browse list, is created when individual servers announce their presence on the network by sending a server announcement to the master browser.

The master browser also collects and maintains a list of all Windows 2000 domains on the network. If the domain of a master browser spans several subnets, the master browser maintains only the browse list for its own subnet and one master browser will exist for each subnet in the domain.

Backup browsers obtain a copy of the browse list from the master browser. Backup browsers automatically contact the master browser every 15 minutes to request a copy of both the browse list and a list of domains on the network. The backup browser caches this list and distributes it to any client on the network that requests it.

The master browser for a domain is usually the first domain controller installed in that domain.

See Also: *backup browser, Computer Browser service, domain master browser*

master domain

In Microsoft Windows NT–based networks, a trusted domain that contains user accounts for the enterprise.

Overview

Master domains are used in enterprise-level implementations of Windows NT to allow user accounts to be centralized and managed in one domain. The master domain is typically found at the company headquarters, while resource domains are implemented at branch offices. A trust relationship is established between the resource domains and the master domains, in which each resource domain trusts the master domain. Users who log on to their computers at headquarters automatically log on to the master domain to validate their credentials. Users at branch offices can log on to either their local resource domain or the trusted master domain, but they must choose the master domain because all user account information resides there. In a wide area network (WAN), one or more backup domain controllers (BDCs) belonging to the master domain are installed at each branch office to facilitate local logons and to prevent logon traffic from being routed over slow WAN links to headquarters.

Notes

Many companies use the Windows NT master domain model to administer users and groups in master domains and resources in second-tier (or resource) domains. Because the majority of reasons to use the Windows NT master domain model disappear when domains are migrated to Active Directory directory service in Windows 2000 and a domain tree is established, these companies might choose to dissolve existing second-tier domains into organizational units (OUs) in the master domains.

See Also: *Active Directory, domain (Microsoft Windows), organizational unit (OU), resource domain, trust*

master index

The final version of an index generated by Microsoft Indexing Service.

Overview

The indexing process first creates word lists, which are merged into shadow indexes and then become one master index. Unlike word lists, which reside in volatile memory, the shadow indexes and the master index are persistent indexes that are stored on disk. The process by which shadow indexes are combined into a master index is called a master merge. A master merge combines multiple shadow indexes with any old master index to create a new master index. The new master index is the most efficient form for the index of a corpus of documents being indexed by the Indexing Service.

The master index stores the indexing data in a highly compressed format in a structure called the catalog. The compressed nature of the master index provides the most efficient data structure for storing information and for issuing queries against the corpus, but the process of generating a master index is resource intensive and is generally performed by the Indexing Service when load on the server is low. However, the administrator can also force a merge to update the master index after new documents are added to the corpus being indexed.

See Also: *catalog*

master name server

A name server in the Domain Name System (DNS) that has authority over a given zone.

Overview

A master name server can be either a primary name server or a secondary name server. If it is a secondary name server, the master name server must obtain its own resource records from another master name server. If it is a primary name server, it contains the master copy of the resource records for its zone of authority.

Master name servers provide read-only copies of their DNS database to secondary name servers. A secondary name server must obtain and update its resource records from a master name server. The process by which these records are obtained and updated between name servers is called a zone transfer.

Notes

When you configure zone transfers between name servers, be sure that the start of authority (SOA) record for the secondary name server is correctly configured with the name of the master name server from which it will obtain its resource records. No configuration is required with the master name server itself.

See Also: *caching-only name server, Domain Name System (DNS), name server, primary name server, secondary name server*

master station

Any network device that controls the operation of other network devices.

Overview

The term *master station* is typically used in mainframe/terminal networking. For example, in a point-to-point connection between an IBM controller and a 3270 terminal, the controller is the master station while the terminal is a slave station. Or, in a multipoint circuit, one of the devices might function as a master station while all the rest are slaves.

Typically, the master station polls all the slave stations regularly in order to determine whether a slave wants to initiate communication with the master. This is different from a peer multipoint circuit such as an Ethernet network, where each station contends for control of the media.

Notes

Another scenario where the term *master station* sometimes is used is in Token Ring networks, where one of the devices can function as a master station and be responsible for detecting and replacing tokens lost by other stations.

See Also: *3270, Ethernet, mainframe, terminal, Token Ring*

matrix switch

A multiport switch that supports any-to-any connectivity.

Overview

The term *matrix switch* originates from a mathematical structure called a matrix, which is a two-dimensional structure with N rows and M columns representing N times M values. Likewise, a matrix switch with N input ports and M output ports has N x M switching possibilities. Typical configurations for these switches include 4 x 4 and 4 x 8 matrix switches, in which any input device can be connected to any output device by operating the switch.



Matrix switch. *Using a matrix switch to connect four printers to four computers.*

Types

A typical matrix switch would be an electronic switch that has multiple ports and that can be controlled using a keypad or some other front-panel interface on the switch. Another type of switch called a code-operated switch is basically a switch that can be operated using character codes embedded in the data stream sent from user workstations. Code-operated matrix switches can thus be operated remotely from computer terminals by entering ASCII commands into a text window.

Uses

Matrix switches are typically used in serial connections such as RS-232 to allow multiple computers to share a group of peripherals such as printers, modems, and other devices. A high-end matrix switch may consist of a chassis into which ports can be added as required to support different interfaces and may be packaged either as a desktop unit or a standard 19-inch (48-centimeter) rackmount enclosure.

A popular use of matrix switches is for Keyboard Video Mouse (KVM) switches, which incorporate matrix switching technology to allow multiple computers to access multiple monitors, keyboards, and mice simultaneously. Although low-end KVM switches may allow a single keyboard, monitor, and mouse to be switched between two, four, or eight different computers, higher-end KVM switches are essentially matrix switches that allow X keyboard/monitor/mouse combinations to actively control Y different computers, with high-end configurations supporting up to 128 computers and 128 different users. Examples of vendors providing KVM matrix switches include ITM Components, Network Technologies, and Lightwave Communications.

Also available are matrix switches that support Small Computer System Interface (SCSI) and parallel communications interfaces. For example, a 4 x 2 SCSI matrix switch could allow two hosts (computers) to switch between four different SCSI drive systems (such as redundant array of independent disks [RAID] arrays). SCSI matrix switches generally allow multiple hosts to access multiple drive systems concurrently, subject to an overall maximum throughput and to the 15 device SCSI limit. An example of a vendor of SCSI matrix switches is Avax International, which provides a modular SCSI matrix switch that can be customized for different host/device combinations.

Notes

The term *matrix switching* also describes the switching technology at the center of an Asynchronous Transfer Mode (ATM) network that functions by supplying needed bandwidth for end-to-end sessions. ATM matrix switching avoids contention by end stations on the network.

See Also: *code-operated switch, Keyboard Video Mouse (KVM) switch, parallel transmission, RS-232, serial transmission, Small Computer System Interface (SCSI), switch*

MAU

Stands for Multistation Access Unit, a wiring concentrator (passive hub) used in Token Ring networks.

See: *Multistation Access Unit (MAU or MSAU)*

MBone

An experimental portion of the Internet that is used to test multicasting technology.

Overview

The MBone platform was established to test and develop technology and software for multicasting audio and video information over the Internet. Although the MBone came into existence in 1992, Internet Protocol (IP) multicasting actually dates back to 1988, when the first multicast tunnel was established between Stanford University and BBN Technologies (now part of Verizon Communications). The MBone initially joined together 40 academic and research networks in four different countries but expanded rapidly to include thousands of networks in dozens of countries and regions.

The MBone is essentially a virtual multicasting network lying on top of the Internet and implemented using routers configured to support IP multicast transmission. These multicast-enabled routers can forward IP packets through nonmulticast routers using tunneling technologies that encapsulate multicast IP packets into unicast packets that the routers can understand. MBone IP addresses used for multicasting of audio and video information have been allocated by the Internet

Assigned Numbers Authority (IANA) as those in the range 224.2.y.z, which is a subset of the class D group of IP addresses ranging from 224.0.0.0 to 239.255.255.255.

Notes

The name *MBone* was selected because the network represents a multicast backbone; that is, a backbone network for multicasting.

See Also: *Internet, multicasting*

MBR

Stands for master boot record, a key data structure on a hard disk.

See: *master boot record (MBR)*

MBS

Stands for Mobile Broadband System, a proposed fourth-generation (4G) mobile cellular communication system.

See: *Mobile Broadband System (MBS)*

MBSP

Stands for Multitenant Broadband Service Provider, another name for a building-centric local exchange carrier, a telecommunications carrier focused on the Multitenant Unit (MTU) market.

See: *Multitenant Broadband Service Provider (MBSP)*

MCP

Stands for Microsoft Certified Professional, a family of technical certifications relating to proficiency in working with Microsoft products.

See: *Microsoft Certified Professional (MCP)*

MCS

Stands for Microsoft Consulting Services, a service from Microsoft Corporation that provides direct assistance to large enterprises for the planning, deployment, and support of solutions based on Microsoft technologies.

See: *Microsoft Consulting Services (MCS)*

MDA

Stands for media-dependent adapter, a standard for modular Ethernet switches.

See: *media-dependent adapter (MDA)*

MDAC

Stands for Microsoft Data Access Components, a set of Microsoft technologies that provide access to information stored in a broad range of data sources.

See: *Microsoft Data Access Components (MDAC)*

MDHCP

Stands for Multicast Dynamic Host Configuration Protocol, the former name for what is now called Multicast Address Dynamic Client Allocation Protocol (MADCAP).

See: *Multicast Address Dynamic Client Allocation Protocol (MADCAP)*

media

Anything over which signals can be transported.

Overview

In computer networking, the term *media* refers generally to the types of cabling over which data is transmitted. Types of cabling for networking and telecommunications include copper cabling and fiber-optic cabling. Copper cabling generally comes in two main forms:

- **Coaxial cabling:** Used mainly in industrial settings because of its resistance to interference.
- **Twisted-pair cabling:** The main kind of cabling used in most networks today. Popular forms include Category 5 (Cat5) and enhanced Category 5 (Cat5e) forms of unshielded twisted-pair (UTP) cabling. Shielded twisted-pair (STP) cabling is used mainly in electrically noisy environments.

Fiber-optic cabling is used mainly in campus backbones and for long-haul telecommunications. At one time, it was expected that fiber would supplant copper, but improvements in switching technologies has enabled copper-based networks to support gigabit speeds and higher.

Another type of media is not really media at all: wireless networking. This type of networking transports signals through empty space using radio and microwave frequency electromagnetic radiation traveling at the speed of light. Although most wireless networking signals travel near the Earth's surface and hence go through air, this air is not considered a medium—electromagnetic waves do not require a medium in which to travel. Wireless networking is sometimes said to employ "unguided media" in contrast to the "guided media" provided by wires and cables. Another way of saying this is to contrast "wireline" (guided) networks with wireless (unguided) ones.

Notes

Another common use of the term *media* is to refer to a combination of cabling and topology used for different types of Ethernet networks. Thus, for example, 10BaseT refers to a star topology using unshielded twisted-pair (UTP) cabling, and 10Base2 refers to a bus topology using thinnet cabling. You can loosely refer to these examples as 10BaseT and 10Base2 Ethernet media.

See Also: *cabling, coaxial cabling, fiber-optic cabling, twisted-pair cabling, wireless networking*

media access control (MAC) layer

A sublayer of the data-link layer.

Overview

The Project 802 specifications of the Institute of Electrical and Electronics Engineers (IEEE) subdivide the data-link layer (Layer 2) of the Open Systems Interconnection (OSI) reference model into two sublayers:

- **Logical link control (LLC) layer:** This is the top sublayer and interfaces with the network layer (Layer 3) above it.
- **Media access control (MAC) layer:** This is the bottom sublayer and interfaces with the physical layer (Layer 1) below it.

The function of the MAC layer is to decide which station on the network is allowed to use the media at any given moment. The MAC layer is therefore responsible for implementing the particular media access control method on a network and thus distinguishes different networking architectures such as Ethernet and Token Ring. The table illustrates the different types of MAC layers defined by Project 802.

MAC Layers Defined by Project 802

Project 802 Committee	*Type of LAN*	*Channel Management Algorithms Defined*
802.3	Carrier Sense Multiple Access with Collision Detection (CSMA/CD)	Binary backoff after collision detection, framing, error detection
802.4	Token bus LAN	Token passing, priority scheme, framing, error detection
802.5	Token ring LAN	Token passing, priority scheme, framing, error detection

As part of the OSI protocol stack, the MAC layer receives framed data from the LLC layer immediately above it, which is media independent, and reframes the data, adding a source and destination physical address or MAC address to the frame for transmission on the medium. The MAC layer is also responsible for making sure that data is delivered without errors to layers above it.

See Also: *802.3, 802.4, 802.5, Carrier Sense Multiple Access with Collision Detection (CSMA/CD), data-link layer, Ethernet, Institute of Electrical and Electronics Engineers (IEEE), logical link control (LLC) layer, media access control method, Open Systems Interconnection (OSI) reference model, Project 802, Token Ring*

media access control method

Any method for allowing multiple stations to transmit signals over a network without conflict.

Overview

If two computers simultaneously place signals on a network cable, a collision can occur. Collisions can result in data being lost or corrupted. The solution is to provide a media access control method for the network. Media access control methods act as traffic lights by permitting the smooth flow of traffic on a network and either prevent collisions entirely or provide a graceful way of dealing with them when they occur.

Media access control methods are implemented at Layer 2, the data-link layer, of the Open Systems Interconnection (OSI) reference model. Specifically, media access control methods are the responsibility of the media access control (MAC) layer, one of two sublayers of the data-link layer. Four main media access control methods are used in local area networks (LANs):

- **Carrier Sense Multiple Access with Collision Detection (CSMA/CD):** Used in half-duplex Ethernet (full-duplex Ethernet uses switched instead of shared media and hence does not require a media access control method). CSMA/CD is the most commonly used media access control method used in LANs, reflecting the dominance of Ethernet over other forms of LAN architectures. CSMA/CD is defined by the 802.3 committee of Project 802 of the Institute of Electrical and Electronic Engineers (IEEE).
- **Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA)**: Used in legacy AppleTalk networking and in some forms of wireless networking, such as 802.11a and 802.11b. CSMA is defined for AppleTalk by IEEE 802.3 and for wireless networking by IEEE 802.11.
- **Token passing:** Used in Token Ring and Fiber Distributed Data Interface (FDDI) networking. Token Ring employs a token passing method defined by IEEE 802.5, but FDDI uses a different method defined by the American National Standards Institute (ANSI).
- **Demand priority:** Used in 100VG-AnyLAN networking and defined by IEEE 802.12.

Implementation

In real-life networking devices such as network interface cards, switches, and routers, media access control methods are implemented using a MAC algorithm. Although the algorithms for Ethernet and Token Ring networks are publicly defined by the IEEE standards described above, those used in full-duplex Ethernet are usually patented by the companies that developed them and are hard-coded into application-specific integrated circuits (ASICs) to achieve the best possible performance. For example, in full-duplex Fast Ethernet and Gigabit Ethernet (GbE) networking, the most popular MAC layer is that designed by Alcatel, from which most switch and router vendors lease their MAC technology. The Alcatel MAC is used in more than half of all GbE ports on the market today and in more than 80 percent of all Fast Ethernet ports. Network engineers should note that mixing switching equipment from vendors that use different MACs can sometimes lead to interoperability problems.

See Also: *802.3, 802.4, 802.5, 802.11a, 802.11b, 802.12, AppleTalk, Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA), Carrier Sense Multiple Access with Collision Detection (CSMA/CD), demand priority, Fiber Distributed Data Interface (FDDI), Institute of Electrical and Electronics Engineers (IEEE), media access control (MAC) layer, Project 802, Token Ring*

media converter

A device that connects two different networking media.

Overview

Media converters are commonly used for Ethernet networks where each type of Ethernet has different specifications for the media that can be used. For example, 10Base2 and 10Base5 use different media types (thinnet and thicknet cabling, respectively) and 10BaseT employs unshielded twisted-pair (UTP) cabling. Media converters allow these different types of cabling to be joined together transparently.

Implementation

Media converters come in many types, with many different kinds of connectors. They range from simple two-port small boxes for connecting two different cables to expensive rack-mounted chassis units with 8 or 16 modular ports that support a wide range of configuration options. Some media converters also include bridging functionality and can be deployed wherever bridges or switches are used.



Media converter. *Using a media converter to connect unshielded twisted pair (UTP) and fiber optic cabling.*

Uses

Common uses of media converters in networks include

- Connecting two different wiring systems, such as 100BaseTX and 100BaseFX, without adding to the repeater count for your network
- Connecting two 10BaseT or 100BaseTX networks in different buildings using fiber-optic cabling runs as long as 9.3 miles (15 kilometers)
- Connecting a 100Base2 thinnet Ethernet segment to an RJ-45 port on a 10/100-Mbps hub
- Integrating a mix of cabling, including UTP cabling, thinnet, thicknet, and fiber-optic cabling

Media converters can often be valuable for companies that have a legacy thicknet or thinnet Ethernet local area network (LAN) but want to take advantage of Fast Ethernet switching technology. Instead of rewiring your entire LAN to unshielded twisted-pair (UTP) cabling, which is the standard cabling type for 100BaseT Ethernet, you can utilize some of your existing cabling by connecting your coaxial cabling to a media converter and then connecting the media converter to the Ethernet switch using UTP patch cables.

Media converters are also commonly used to join copper LANs together using long runs of fiber. Canoga Perkins Corporation offers its EdgeAccess Gigabit Ethernet Media Converter for connecting Gigabit Ethernet (GbE) backbone switches using fiber-optic cabling. Products such as this can be used to build custom metropolitan area networks (MANs) using dark fiber leased from telcos and are often used by service providers that are building metropolitan Ethernet backbone networks.

See Also: *10Base2, 10Base5, 10BaseT, 100BaseT, coaxial cabling, Ethernet, Fast Ethernet, fiber-optic cabling, Gigabit Ethernet (GbE), metropolitan Ethernet, thicknet, thinnet, unshielded twisted-pair (UTP) cabling*

media-dependent adapter (MDA)

A standard for modular Ethernet switches.

Overview

Ethernet switches come in two types:

- **Fixed**: These switches are self-contained units that generally provide a fixed number of ports for unshielded twisted-pair (UTP) cabling or fiber-optic cabling.
- **Modular**: These switches can be customized to support different numbers of UTP and fiber ports as needed.



Media-dependent adapter (MDA). *Inserting an MDA module into an MDA slot to customize a modular Ethernet switch.*

Modular Ethernet switches generally consist of a chassis with two to four media-dependent adapter (MDA) slots on the front panel. To customize these switches for your network, you simply insert MDA modules into the slots to provide the media configuration you require. A single MDA module might provide one of the following typical port configurations:

- Eight 100/10BaseT ports or 1000/100/10BaseT ports
- Two 100BaseTX or 100BaseFX ports
- A single Fiber Distributed Data Interface (FDDI) double-ring connection

By selecting and inserting different MDAs into a modular Ethernet switch, you can quickly reconfigure complex networks. Bridging between the different types of media is performed internally by the chassis circuitry inside the switch.

See Also: *10BaseT, 100BaseFX, 100BaseT, 100BaseTX, Ethernet, Fiber Distributed Data Interface (FDDI), fiber-optic cabling, unshielded twisted-pair (UTP) cabling*

Megaco

An emerging framework for connecting voice, fax, and videoconferencing systems to packet-switching networks.

Overview

Megaco is a standard developed jointly by the International Telecommunication Union (ITU) and the Internet Engineering Task Force (IETF). Megaco is designed to support convergence of telephone and data services and is especially targeted toward the Internet Protocol (IP) telephony sector to ensure interoperability between gateways and controllers supplied by different vendors. The name Megaco is short for Media Gateway Control, and the ITU standard for this framework is H.248.

Architecture

Integrating circuit-switched systems such as the Public Switched Telephone Network (PSTN) and packet-switched systems such as the Internet are complicated by the fact that the PSTN actually consists of two separate networks:

- **Traffic network:** The network that actually transports voice and data traffic between callers.
- **Signaling network:** The network responsible for control functions such as call setup and tear down. The signaling network for the PSTN is known as Signaling System 7 (SS7).

In a typical IP telephony system, the IP network interfaces with the two PSTN networks using two different kinds of devices:

- **Media gateway (MG):** Enables data on the PSTN to be converted into IP packets for transmission over the Internet and vice versa. The MG interfaces the IP network with the traffic portion of the PSTN, and MGs communicate with each other using protocols such as Real Time Protocol (RTP).

- **Media gateway controller (MGC):** Enables control signals on the PSTN to be converted into IP packets for transmission over the Internet and vice versa. The MGC interfaces the IP network with the SS7, and MGCs communicate with each other using protocols such as H.323 or Session Initiation Protocol (SIP). MGCs are sometimes known as softswitches or call agents.

Megaco's role in the IP telephony framework is to provide a standard protocol for communication between MGs and MGCs. Megaco allows MGCs to control MGs and enables the remote control of connection-aware devices across signaling domains. Megaco can be implemented on a wide range of devices, including

- Digital Subscriber Line Access Multiplexers (DSLAMs)
- Optical cross-connects in telecom switching centers
- Routers that support Multiprotocol Label Switching (MPLS)
- Voice over IP (VoIP) gateways

Prospects

Megaco is intended as an industry standard, vendor-independent protocol for MG/MGC communication and is expected to displace the proprietary Media Gateway Control Protocol (MGCP) defined in RFC 2705, which has established itself as a de facto standard but which lacks some of Megaco's advanced capabilities, such as peer-to-peer device control (MGCP supports only master/slave control). Megaco also replaces earlier protocols, including Internet Protocol Device Control (IPDC) and Simple Gateway Control Protocol (SGCP).

See Also: *Digital Subscriber Line Access Multiplexer (DSLAM), H.323, IP telephony, Multiprotocol Label Switching (MPLS), Public Switched Telephone Network (PSTN), Voice over IP (VoIP)*

member server

A server that does not perform logon authentication.

Overview

In Microsoft Windows 2000–based networks, a member server is any server that is not a domain controller. A member server, therefore, does not contain a copy of Active Directory directory service. Member servers do participate in domain security, however, by allowing folders and other resources on them to be shared with permissions assigned to different users and groups. However, member servers cannot be used to authenticate the credentials of users so they can log on to the network—domain controllers are required to perform this action.

Member servers are usually used for dedicated network purposes such as the following:

- File and print servers
- Application servers
- Database servers
- Web servers
- Mail servers

Notes

In Windows 2000, you can change a member server into a domain controller by running the Active Directory Installation Wizard.

See Also: *Active Directory, domain controller*

mesh topology

A network topology that has redundant data paths between nodes.

Overview

A mesh network (a network that has a mesh topology) is any network in which information typically has more than one route it can take between any two end stations. Meshed topologies are commonly used in backbone networks to provide fault tolerance—if a wire, hub, switch, or other component fails, data can always reach its destination by traveling along an alternate path. Meshed networks are common in older, routed Internet Protocol (IP) internetworks and prevent the failure of a single router from bringing down a portion of the network.



Mesh topology. Example of mesh topology for a routed internetwork.

There are two basic types of mesh networks:

- **Fully meshed:** This type of network provides a direct link between every pair of nodes on the network. Full mesh topologies have the highest possible level of fault tolerance, but when used in routed internetworks, they increase the computational strain on dynamic routers for calculating their routing tables. A full mesh network with N routers would in fact have N! (N factorial) paths (1 x 2 x 3 x . . . x N) to calculate, and N! increases very rapidly with N.
- **Partially meshed:** This type of network is more common than the fully meshed type and includes a certain number of redundant data paths to provide some degree of fault tolerance to the network.

See Also: *bus topology, fault tolerance, internetwork, ring topology, router, star topology*

message

Information sent between two entities.

Overview

The common definition of a message in computer networking is a communication sent by one user to another user by means of an e-mail system such as the Simple Mail Transfer Protocol (SMTP) mail system that is used on the Internet. More generally in computer networking, a message is any grouping of information at the application layer (Layer 7) of the Open Systems Interconnection (OSI) reference model that is exchanged between applications for various purposes. These Layer 7 messages can contain control information or report errors, or they can support the running of a network-aware application in some other fashion.

In Microsoft Message Queuing (MSMQ) terminology, a message is a unit of information or data that is sent between two applications, usually hosted on different computers on a network.

See Also: *application layer, e-mail, Internet, Open Systems Interconnection (OSI) reference model, Simple Mail Transfer Protocol (SMTP)*

message digest (MD) algorithms

A series of hashing algorithms used in cryptography.

Overview

Message digest (MD) algorithms are commonly used in cryptography to generate digital signatures for ensuring the integrity and authenticity of encrypted messages. The term *message digest* refers to a short string or hash value of fixed length that is computed from the longer variable-length message being hashed by the algorithm.

Types

The important message digest algorithms include MD2, MD4, and MD5, all of which produce a 128-bit hash value. The details of these different algorithms are as follows:

- **MD2:** Developed in 1989 for 8-bit encoders. It pads the message to be encoded until it is a multiple of 16 bytes in length, appends a 16-byte checksum, and computes the hash.
- **MD4:** Developed in 1990 for 32-bit encoders. It pads the message to be encoded until it is 56 bytes short of being a multiple of 512 bytes, appends an 8-byte message length value, and iteratively hashes the message in three rounds. MD4 can be broken fairly easily in a dedicated cryptographic attempt. It is implemented in the Microsoft Challenge Handshake Authentication Protocol (MS-CHAP) supported by the Remote Access Service (RAS) on Microsoft Windows NT.
- **MD5:** Developed in 1991 for 32-bit encoders. It is an extension of MD4 and uses four rounds of hashing instead of three. It is fairly difficult to crack. Windows NT RAS Client supports MD5-CHAP for connecting to third-party Point-to-Point Protocol (PPP) servers supporting MD5 authentication, but Windows NT RAS Server does not. However, Service Pack 3 for Windows NT provides limited support for MD5-CHAP PPP authentication. Microsoft Windows 2000 Routing and Remote Access Service (RRAS) supports MD5.

See Also: *cryptography, digital signature, encryption, hashing algorithm, Microsoft Challenge Handshake Authentication Protocol (MS-CHAP), Point-to-Point Protocol (PPP)*

Message Tracking Query Protocol (MTQP)

An emerging protocol for tracking e-mail messages over the Internet.

Overview

Message Tracking Query Protocol (MTQP) is a proposed standard from the Internet Engineering Task Force (IETF) to enable administrators to track the route that Simple Mail Transport Protocol (SMTP) messages take as they travel across the Internet. MTQP enables a message's sender to determine the specific host and router hops taken by SMTP messages, regardless of whether they reach their destination or not. MTQP thus provides the capability for determining whether messages have actually reached their intended recipients or where along the way they may have been prevented from reaching their destination.

MTQP solves a problem inherent with SMTP: the current best-effort delivery model of this protocol means that there is no guarantee that messages will reach their recipients and no way of knowing if they are delayed or lost. In this respect, X.400 messaging systems based on the X.400 recommendations developed in the 1980s by the International Telecommunication Union (ITU) have had a distinct advantage over SMTP, namely, messaging accountability. This accountability enables X.400 systems to be used for important purposes such as sending contracts and other legal documents—if the message is not received, the sender knows it and can act accordingly. As a result, X.400 continues to be used in situations where message integrity is vital, as in certain international and government organizations such as the North Atlantic Treaty Organization (NATO). Until now, however, SMTP lacked the essential accountability to make it a suitable medium for transmission of this kind of information. With a combination of MTQP, encryption, and digital signatures, the Internet might soon become the de facto medium for secure electronic transmission of legal information such as contracts, agreements, invoices, and bank statements.

MTQP was designed with input from AT&T Labs, MessagingDirect (now part of ACI Worldwide), and the Sendmail Consortium. The protocol operates in conjunction with SMTP Service Extensions (ESMTP), enabling the exact path that a message takes as it travels between hosts and across routers over the Internet.

Prospects

MTQP will be supported by upcoming versions of Sendmail and will likely be supported by other Internet mail platforms as well. MTQP's full value will only be realized, however, if it becomes widely implemented across the Internet and by major Internet service providers (ISPs). However, MTQP can be implemented on a limited basis between companies that frequently exchange e-mail and can alert them to problems with their messaging communications.

See Also: *ESMTP, Internet Engineering Task Force (IETF), Simple Mail Transfer Protocol (SMTP), X.400*

Messaging Application Programming Interface (MAPI)

A Microsoft technology that allows developers to use the Windows messaging subsystem for writing messaging applications.

Overview

The Messaging Application Programming Interface (MAPI) provides a generic programming interface for making Windows applications mail-enabled and standardizes how messages are handled by messaging applications. MAPI also provides a general messaging subsystem built into the Windows operating system that can function with any message transport mechanism. The messaging subsystem is thus similar to the printing subsystem that allows Windows to interface with any kind of print device and perform standard printing functions.

Implementation

MAPI is a kind of middleman between the messaging application running on the computer and the underlying messaging services. The client interface for accessing these services through MAPI is the same whether the services are local area network (LAN)-based messaging services, e-mail services, fax services, or any other messaging service. MAPI allows standard function calls to access general messaging functions such as sending, receiving, and reading messages in a uniform fashion regardless of the messaging subsystem used. MAPI provides two sets of interfaces: the client-side application programming interfaces (APIs) called by the messaging application, and the service-provider interfaces that the Windows messaging subsystem uses to connect with different messaging-handling systems.

Microsoft Outlook is an example of a MAPI-enabled client, and Microsoft Exchange Server supports MAPI messaging.

See Also: *application programming interface (API), Exchange Server, Outlook*

metabase

A database for storing configuration settings for Microsoft Internet Information Services (IIS).

Overview

The metabase is a hierarchical, memory-resident database that is used to store IIS configuration information. Prior to version 4 of IIS, such information was stored mainly in the Microsoft Windows NT registry. The metabase was introduced in IIS 4 as a more flexible and expandable repository than the registry, and being memory-resident, it also provides better performance than the disk-based registry. Some settings for IIS are still stored in the registry, however, for backward compatibility with older versions of IIS.

The metabase is stored as the file Metabase.bin in the \WINNT\system32\inetsrv directory on a Windows 2000 machine running IIS.

Notes

The Microsoft Internet Information Server Resource Kit includes a number of administrative scripts that you can use to back up and restore the metabase.

See Also: *Internet Information Services (IIS), registry*

metadirectory

A tool for combining diverse data sources into a single directory.

Overview

One of the realities of enterprise networks is heterogeneity, and this is particularly apparent in where and how an enterprise stores its data. A large enterprise might have several directory services such as Microsoft Active Directory directory service, Novell Directory Services (NDS) eDirectory, a homegrown Lightweight Directory Access Protocol (LDAP) directory, user account directories such as those found in Microsoft Windows NT and Novell NetWare, database platforms such as Oracle and Microsoft SQL Server, and messaging applications such as Lotus cc:Notes and Microsoft Exchange Server 5.5 that use their own proprietary directories. The task of a metadirectory is to integrate these various data sources into a single hierarchical directory that can be managed and queried as easily as if a single directory service were used across the enterprise.

Implementation

A metadirectory is really an integration strategy rather than a specific set of tools. Important decisions have to be made when thinking about integrating disparate directories together in the enterprise. For example, will one directory be chosen as the master and all others be slaves with respect to it? If this is the case, the directory chosen must be sufficiently scalable, robust, and extensible to enable it to integrate with all the other kinds of directories in the enterprise. In some situations, it may make sense for several directories to operate as masters with respect to different kinds of information. At other times, tools may be selected to enable several directories to operate as peers with each other, but this is rarer.

Another important question to decide is the level of integration to be achieved. For example, will updates be propagated across different directories or will queries simply be distributed across them instead? This question boils down to two basic ways of implementing integration of different directories: synchronization and brokering.

- **Synchronization:** In this approach, information that is updated on one directory is propagated to other directories or, more likely, to the master directory for the enterprise. The master directory, in this case, maintains an up-to-date repository of all the information stored in the various directories of the enterprise, and queries are issued against this master directory when information is required rather than querying individual directories. Metadirectory tools are used to enable the slave directories to talk to the master and to ensure that the slaves are properly synchronized with the master at all times. The master directory, in this case, becomes the authoritative information source for the enterprise. The downside of this approach is that the master directory becomes a single point of failure for information retrieval within the enterprise. This approach also has the tendency to make the master directory unwieldy due to the large amount of information it needs to store.
- **Brokering:** This approach avoids the issue of updating disparate directories with each other by allowing one directory to proxy requests to another directory. In this case, each directory maintains its own island of information, and queries issued against the master directory are forwarded to the appropriate slave directories for answering using metadirectory brokering tools. The slave directories then return their results to the master, which returns them to the client making the request. The advantage of this approach is that each directory can be kept small. The disadvantage is that querying can be slower due to the proxied requests that have to be issued.

Marketplace

Microsoft MetaDirectory Services (MMS) from Microsoft Corporation is a metadirectory product originally developed by Zoomit Corporation that can be used for integrating different directories together. MMS uses a core metadirectory service called Metaverse that communicates with other directories such as Microsoft Active Directory using management agents. MMS agents are available for a wide range of enterprise applications, including enterprise resource planning (ERP) and customer relationship management (CRM) applications from different vendors.

Another metadirectory product is Novell's new DirXML platform, which uses XML-based connectors to integrate Novell eDirectory to directory services from other vendors and to various messaging platforms. Connectors will be available for a wide range of enterprise applications, including those from SAP and PeopleSoft, X.500 directory services, and databases that support the Open Database Connectivity (ODBC) and Java Database Connectivity (JDBC) platforms.

Prospects

Although LDAP has securely replaced the complex and unwieldy X.500 directory recommendations from the International Telecommunication Union (ITU), the emergence of Extensible Markup Language (XML) has complicated the directory landscape somewhat. Most commercial directories, such as Microsoft Active Directory and Novell eDirectory, are LDAP-compliant and support LDAP application programming interfaces (APIs) that make it fairly simple to enable these directories to communicate with each other. Other applications that have non-LDAP data stores can often be integrated with LDAP directories by writing custom middleware that translates application-specific APIs into LDAP APIs. With the emergence of XML, however, new strategies are being tried for storing enterprise information, and an initiative called Directory Services Markup Language (DSML) is being developed to further support the integration of vendor-specific directories. Enterprises should not view metadirectories as a panacea for directory interoperability problems but as a workaround for lack of planning and unstructured growth of enterprise information sources, and these products are sometimes little more than veiled attempts by vendors to persuade customers to migrate to the vendor's own directory platform.

See Also: *Active Directory, directory, Directory Service Markup Language (DSML), Java Database Connectivity (JDBC), Lightweight Directory Access Protocol (LDAP), Novell Directory Services (NDS), open database connectivity (ODBC), X.500, XML*

metasearching

Integrating multiple search engines into a single search entity.

Overview

Search engines such as Google, AltaVista, and Yahoo! are popular tools for users to find helpful information on the Internet. Metasearching simply means integrating several of these tools using a single search interface. Metasearching can employ several architectures:

- **Metasearch servers:** Web sites to which users submit their search requests and which then proxy user requests to traditional search engines such as Google and AltaVista. The replies from these search engines are then consolidated by the metasearch server and returned to the user as a single result set. Examples of sites that use this approach include Metacrawler, the first metasearch engine and now owned by Go2Net; SavvySearch, now owned by CNET Networks and available from Search.com; Dogpile, which displays result sets for each search engine used separately; and Profusion, which allows you to select which traditional search engines to proxy your requests to.
- **Metasearch utilities:** Applications that run on the client and generally offer additional features such as sorting, highlighting, and automatic downloading of results pages. Examples of metasearch utilities include Copernic, available for both the Microsoft Windows and Apple Macintosh platforms; BullsEye, a popular Windows application from Intelliseek; and Sherlock, a metasearch utility integrated into the Macintosh operating system in versions 8.5 and later.

See Also: *Internet*

metropolitan area network (MAN)

Traditionally, a network spanning a metropolitan area.

Overview

Metropolitan area network (MAN) is a concept that can mean several things depending on the context. For example, a MAN could be

- A telco service that provides data transport across an urban area using ATM over SONET technology.
- Several local area networks (LANs) connected across an urban area using a high-speed fiber-optic backbone.
- Several connected networks within a city, forming a citywide network for a specific government organization or corporation.
- Any network bigger than a LAN but smaller than a wide area network (WAN).
- Any network that spans more than a single building.
- A Distributed Queue Dual Bus architecture network based on the IEEE 802.6 standard of Project 802 (this is the formal definition of a MAN, but it is now obsolete).

The first definition on this list is the one most familiar to enterprise network architects. To build a WAN consisting of LANs in different geographic locations, enterprises lease MAN services from their local telco. These MAN services thus enable LANs to be joined together into a WAN, and the MAN thus functions as the demarcation point between LAN and WAN. Common MAN services offered by telcos include Integrated Services Digital Network (ISDN), T1 and T3 lines, and Digital Subscriber Line (DSL) services. Enterprises typically interface their LANs with the telco MAN by deploying an access device (also called a WAN switch or access multiplexer) in the basement of their equipment room. The access device then aggregates company LAN traffic and backhauls it from the customer premises to the Point of Presence (POP) of the telco, where it typically traverses the metropolitan area over a dual SONET ring.

Prospects

A new development is the emergence of metropolitan Ethernet service providers, which compete with traditional telcos for hauling data traffic by building their own fiber MANs and provisioning fiber to businesses in downtown areas. Metropolitan Ethernet is cheaper than traditional telco WAN services that rely on ATM over SONET, is easier to deploy and manage, and is fast becoming a viable alternative for the MAN demarcation point between LAN and WAN.

See Also: *ATM over SONET, local area network (LAN), metropolitan Ethernet, wide area network (WAN)*

metropolitan Ethernet

A service that uses Gigabit Ethernet (GbE) to provision metropolitan areas with high-speed data services.

Overview

Metropolitan Ethernet represents a new kind of data service now offered in many dense urban areas. Traditionally wide area network (WAN) and metropolitan area network (MAN) services have been provisioned by telcos, particularly by Incumbent Local Exchange Carriers (ILECs) that own the local loop telephone wiring connecting customer premises to their services. Telecommunication services offered by telcos have included dial-up Internet access, Integrated Services Digital Network (ISDN), T1 and fractional T1 lines, and recently Digital Subscriber Line (DSL). The monopoly enjoyed by telcos as a result of local loop ownership has enabled them to maintain high prices for many of these services. For example, a T1 line typically costs around $1,000 a month and provides only 1.5 megabits per second (Mbps) bandwidth, but a T3 line offers a much higher bandwidth of 45 Mbps but at a correspondingly higher price of tens of thousands of dollars per month, which is beyond the budget of most businesses except the largest enterprises and large service providers. DSL is a relatively new technology that offers multimegabit data speeds, and competition with cable modem technologies has kept DSL prices low for residential customers, but the absence of cable television infrastructure buildout in business parks and downtown areas has meant that DSL prices for business customers can be kept artificially high.

The result of all this is that the MAN has become the bottleneck between the corporate local area network (LAN) and the WAN. Although LAN speeds have risen to 100 Mbps Fast Ethernet and higher and WAN speeds within the Synchronous Optical Network (SONET) backbones of carriers is also 100 Mbps or higher, companies trying to join their LANs into a WAN using traditional T1 lines find that these lines have become the bottleneck in the equation and that upgrading to T3 is too costly a solution.

Enter the metropolitan (or metro) Ethernet service providers, companies who are building their own separate MANs to compete with the existing SONET rings owned by telcos. These new service providers are building their MANs using GbE switching gear, laying their own fiber backbones in dense urban areas to connect their points of presence (POPs) with industrial parks, campuses, and downtown multitenant units (MTUs). The demarcation point at the customer premises now becomes as simple as an RJ-45 connection, and customers can simply use a Category 5 (Cat5) patch cord to connect their Ethernet LAN to their carrier's GbE backbone to build a WAN or receive high-speed Internet access. Other services supported by some metro Ethernet providers include high-speed connectivity to storage area networks (SANs), Web and application server hosting, and multicast Internet Protocol (IP) video services.

Implementation

Metro Ethernet is made possible by the use of new carrier-class GbE switches that can be deployed at either the service provider's POP or the basement of the customer's MTU, depending on the scenario. At the provider's end, these switches interface with telco SONET rings to provide connectivity for long-distance WAN links; within a downtown area of a city, however, the metro Ethernet provider maintains end-to-end Ethernet connectivity for customers without the need of telco SONET services.

Metro Ethernet service providers may either lay their own fiber downtown or lease dark fiber from other carriers. To get the most out of this fiber, providers are starting to employ Wavelength Division Multiplexing (WDM), which enables as many as eight full-duplex GbE channels to run over a single fiber pair. Dense Wavelength Division Multiplexing (DWDM) offers the potential of squeezing even greater bandwidth out of individual fiber strands.

With GbE now supporting distances up to 150 miles (240 kilometers) over single-mode fiber, metro Ethernet can be deployed across even the largest cities to provide a high-speed alternative to SONET for data transport. The emergence of 10 Gigabit Ethernet (10 GbE) promises to provide even greater capacity for this service.

Advantages and Disadvantages

Metro Ethernet offers a number of advantages over traditional SONET rings for building WANs:

- **Simplicity:** The fact that Ethernet is running on both sides of the access device at the customer premises makes installation, configuration, and management of WAN links easier.
- **Cost:** Metro Ethernet connections are typically only 25 to 50 percent of the cost of traditional telco data services, even taking into account the cost of laying new fiber. The cost of GbE switching equipment used for WAN access to metro Ethernet services is about a tenth the prices of traditional ATM over SONET access devices, which adds up to another cost savings for metro Ethernet over telco WAN services. Finally, GbE is a well-known technology to LAN administrators, and so the cost of hiring or training IT (information technology) people skilled in ATM over SONET technologies is eliminated, which further reduces the cost.
- **Scalability:** Metro Ethernet is typically provisioned in 1 Mbps increments up to 1 gigabit per second (Gbps), with prices scaled accordingly. Although upgrading a traditional T1 line to T3 can take weeks, increasing bandwidth on a metro Ethernet connection usually takes only a few hours. Some service providers even offer customers a Web interface from which they can provision additional bandwidth for themselves as required.

- **Manageability:** Metro Ethernet simplifies the task of data management by enabling packets to be processed at Layers 3 through 7 of the Open Systems Interconnection (OSI) reference model. This contrasts with SONET, where it is difficult to process packets on the backbone.
- **Fault-tolerance:** Traditional dual SONET rings deployed by telcos offer fault-tolerance that GbE networks do not intrinsically possess. By combining GbE with Dense Wavelength Division Multiplexing (DWDM), however, SONET's dual-ring architecture can be imitated to provide a robust, fault-tolerant backbone comparable to SONET.

The main disadvantage of metro Ethernet is availability: for the foreseeable future, this service will probably be available only in the downtown sections of large urban areas. Another disadvantage is that although dual SONET rings deployed by telcos are self-healing (typically in less than 50 milliseconds), GbE networks do not have such built-in recoverability features. Furthermore, while ATM over SONET is a cell-based connection-oriented technology that is optimized for voice but can also carry data easily, Ethernet is a connectionless packet-switched technology that suffers unpredictable delay and jitter, factors that have little effect on data traffic but which make it difficult to transport voice traffic (unless bandwidth is far below saturation point). Finally, SONET networks traditionally offer five-nines (99.999 percent) uptime, which is typically an order of magnitude better than the best metro Ethernet networks available today.

Marketplace

Metro Ethernet service providers offer a wide range of services from LAN-LAN interconnection within urban areas to high-speed Internet access and even Voice over IP (VoIP) services. They can provision a single fiber link to an MTU in such a way that each client within the building has its own secure connection and is billed separately according to usage. Popular service providers in the metro Ethernet marketplace include Yipes Communications, Telseon, FiberCity Networks, Cogent Communications, Everest Broadband Networks, IntelliSpace, XO Communications, and many others. Although some of these providers offer services only in a few urban centers, many of them are scaling out to offer services nationally in large cities across the United States. Some metro Ethernet service providers specialize only in high-speed Internet access or WAN connectivity, but others offer a full range of services comparable to telcos.

Carrier-class GbE switches for metro Ethernet rollouts are now available from a number of vendors, including Extreme Networks, Foundry Networks, Cisco Systems, Nortel Networks, and Riverstone Networks.

Prospects

Just as GbE has won out over competing LAN backbone technologies such as Fiber Distributed Data Interface (FDDI) and Asynchronous Transfer Mode (ATM), the same thing may happen in the WAN, at least for data services. ATM over SONET still offers a much higher Quality of Service (QoS) for voice communications, but the simplicity and price advantages of end-to-end Ethernet in the WAN make it the leading technology as far as data services are concerned. Unfortunately, metro Ethernet is likely to remain exactly that—Ethernet restricted to metropolitan areas where dense clusters of MTUs make laying fiber a cost-effective decision for service providers. Metro Ethernet is unlikely to be available in the foreseeable future in smaller urban or rural areas, which must continue to rely on telco services as their only option. Nevertheless, metro Ethernet is having a profound impact on the enterprise WAN cost model and may even eat into the traditional voice market of telcos as VoIP technologies become more standardized and widely deployed.

See Also: *Asynchronous Transfer Mode (ATM), ATM over SONET, dense wavelength division multiplexing (DWDM), Digital Subscriber Line (DSL), Fiber Distributed Data Interface (FDDI), Gigabit Ethernet (GbE), Incumbent Local Exchange Carrier (ILEC), Integrated Services Digital Network (ISDN), local area network (LAN), metropolitan area network (MAN), storage area network (SAN), Synchronous Optical Network (SONET), T-carrier, Voice over IP (VoIP), wide area network (WAN)*

MExE

Stands for Mobile Execution Environment, an emerging standard for running Java applications on mobile phones.

See: *Mobile Execution Environment (MExE)*

MFC

Stands for Microsoft Foundation Classes, a set of object-oriented interfaces to the Microsoft Windows application programming interface (API).

See: *Microsoft Foundation Classes (MFC)*

MFR

Stands for Multilink Frame Relay, a new frame relay aggregation technology.

See: *Multilink Frame Relay (MFR)*

MIB

Stands for Management Information Base, a database of information about a device that is managed by using the Simple Network Management Protocol (SNMP).

See: *Management Information Base (MIB)*

microkernel

An operating system architecture in which the kernel is a small component with limited functionality that loads other components such as drivers and services into memory only as required to complete requested system tasks.

See: *kernel*

Microsoft Certified Partner

An independent company that partners with Microsoft Corporation to provide IT (information technology) services to corporate, government, and small business customers.

Overview

The Microsoft Certified Partner Program is a partnership between Microsoft and independent companies where Microsoft provides IT services and products that enable these companies to provide solutions for their clients based on leading-edge Microsoft technologies. The program is global in scope and is the primary channel by which Microsoft solutions are provided. The Microsoft Certified Partner Program evolved primarily from the Microsoft Certified Solution Provider program formed in 1992, and it has over 31,000 partners worldwide.

Microsoft Certified Partners receive numerous benefits to help them deliver Microsoft solutions, including licenses for internal and marketing use of Microsoft products, access to prerelease software information and program codes, sales and marketing resources, technical training and support, and direct support from Microsoft staff. Partners participate in joint marketing ventures and receive valuable customer referrals.

The Microsoft Certified Partner Program has two levels of membership:

- **Member:** Companies that receive useful technical, marketing, and sales information, and also licenses for Microsoft products for internal testing and development purposes.
- **Gold:** Companies that have demonstrated a high level of proficiency in building solutions using Microsoft technologies within one or more solutions areas, including enterprise systems, support centers, e-commerce, and Application Service Provider (ASP) services.

For More Information

Find out more about the Microsoft Certified Partner program at *www.microsoft.com/certpartner.*

Microsoft Certified Professional (MCP)

A family of technical certifications relating to proficiency in working with Microsoft products.

Overview

Microsoft Certified Professionals (MCPs) are individuals who have demonstrated in-depth knowledge of specific Microsoft operating system and application platforms. Different Microsoft certifications relate to different areas of expertise, knowledge, and skill. The various types of technical certifications offered by Microsoft Corporation can be summarized as follows:

- **System Engineering:** Directed toward professionals who install, administer, and troubleshoot networks based on Microsoft operating systems. Certifications in this family range from the basic Microsoft Certified Professional (MCP) designation, which signifies that the holder has demonstrated proficiency by passing an exam in at least one Microsoft operating system, to the prestigious Microsoft Certified System Engineer (MCSE) designation, which requires the candidate to pass five core exams and two elective exams. The MCSE designation is used in the IT (information technology) industry as a benchmark for identifying individuals who have proficiency in skills related to occupations such as systems engineers, technical support engineers, systems analysts, network analysts, and technical consultants. A typical MCSE has expertise in Microsoft Windows 2000 (or Windows .NET Server) and in one or more Microsoft BackOffice (or Microsoft .NET Server) application platforms.
- **Solutions Development:** Directed toward professionals who design, build, and implement solutions using Microsoft application development technologies such as Visual Basic, Visual C++, C#, and other Microsoft programming platforms. Certifications in this family range from the basic MCP designation, which signifies that the holder has demonstrated proficiency by passing an exam in at least one Microsoft application development platform, to the Microsoft Certified Solution Developer (MCSD) designation, which requires the candidate to pass three core exams and one elective exam. The MCSD designation is used to identify individuals whose proficiency relates to occupations such as software engineers, software applications engineers, software developers, and technical consultants.
- **Database Administration:** Directed toward professionals who deploy, administer, and troubleshoot solutions using Microsoft database technologies based on Microsoft SQL Server. Certifications in this family range from the basic MCP designation, which signifies that the holder has demonstrated proficiency by passing at least one exam related to Microsoft database technologies, to the Microsoft Certified Database Administrator (MCDA) designation, which requires the candidate to pass three core exams and one elective exam. The MCDA designation is used to identify individuals whose proficiency relates to occupations such as database administrator, database analysts, and database developers.

A fourth area of Microsoft professional certification is the Microsoft Certified Trainer (MCT) designation, which is used to identify individuals qualified to deliver technical training in Microsoft platforms and applications using Microsoft Official Curriculum (MOC) courseware at a Microsoft-authorized training center.

Employers can use Microsoft certifications for screening candidates for technical positions in their IT departments, and current employees can be encouraged to achieve this designation as part of their career advancement path. Certifications are achieved by passing exams administered by independent organizations such as Sylvan Prometric and Virtual University Enterprises, which together have more than 1400 testing centers worldwide.

Notes

Microsoft also has a nontechnical certification for users, including the Microsoft Office User Specialist (MOUS) certification.

For More Information

You can find out about Microsoft certification at *www.microsoft.com/trainingandservices.*

See Also: *Microsoft Office User Specialist (MOUS), Microsoft Official Curriculum (MOC)*

Microsoft Challenge Handshake Authentication Protocol (MS-CHAP)

An encrypted authentication scheme for Point-to-Point Protocol (PPP) sessions.

Overview

Microsoft Challenge Handshake Authentication Protocol (MS-CHAP) is Microsoft Corporation's version of the Internet standard Challenge Handshake Authentication Protocol (CHAP) defined in RFC 1994. Remote access servers use MS-CHAP to encrypt authentication sessions with remote access clients. Although CHAP requires the plaintext version of the remote user's password to be available on the access server for comparison purposes, MS-CHAP requires only the MD4 hash of the user's password to be available. The user's password information is thus stored in encrypted form on the access server, which makes MS-CHAP more secure than CHAP. MS-CHAP also differs from CHAP in that it employs a challenge/response packet format specifically designed for Windows platforms.

There are two different versions of MS-CHAP:

- **MS-CHAPv1:** Used by Microsoft Windows NT 4.0. Supports one-way authentication of remote clients by access servers.
- **MS-CHAPv2:** Used in Microsoft Windows 2000 or later. Supports mutual authentication of both the remote client and the access server to guard against server impersonation. MS-CHAPv2 also includes the following new features:
  - Unique cryptographic keys are generated each time the user connects. These keys are based on a hash of the user's password and the arbitrary challenge string generated during the authentication session.
  - Separate keys are employed for data transmission and reception rather than the single key used in MS-CHAPv1.
  - LAN Manager encoding is no longer supported.

Implementation

Use of MS-CHAP is negotiated during the Link Control Protocol (LCP) portion of the PPP authentication process. Once the remote client requests authentication from the access server and negotiates MS-CHAP, the authentication process is encrypted in three steps:

1. The access server sends the remote client a Challenge message consisting of a session ID and an arbitrary challenge string.
2. The client sends the server a Response message consisting of the username (in plaintext), a hash of the challenge string, the session ID, and a one-way MD4 hash of the user's password.
3. The server generates a duplicate version of the hash of the user's password and compares this with the Response message received from the client. If these match, the client is authenticated and the PPP session is initiated.

See Also: *Challenge Handshake Authentication Protocol (CHAP), Link Control Protocol (LCP), Point-to-Point Protocol (PPP), remote access*

microsoft.com

The Web site for Microsoft Corporation, the worldwide leader in software for business and personal computing.

Overview

Microsoft's Web site is one of the largest and most complex in the world, as might be expected for a company having over 48,000 employees in over 60 regional offices worldwide. The *microsoft.com* site is also the main resource for those who use Microsoft products, including consumers, businesses, consultants, system integrators, and software developers. The staffs of IT (information technology) departments, sales and marketing, help desk, and business implementers can find useful information on *microsoft.com* about planning, designing, deploying, managing, maintaining, and troubleshooting solutions built using Microsoft products, platforms, and technologies.

Despite the size and complexity of the site, *microsoft.com* is actually amazingly simple to navigate! Nevertheless, finding information on a site as large as this is sometimes difficult, as many important Uniform Resource Locators (URLs) are not found on the site's home page. This article is designed to simplify this process of finding useful information for networking professionals by providing a summary of links to valuable information found on Microsoft's Web site. The URLs listed here are mostly top-level URLs that are unlikely to change frequently (many have remained the same for several years), and even if the site managers change them, these URLs are likely to be redirected automatically to the updated information. The URLs in the main table below are listed in short form as relative URLs; for example, */windows* is short for *www.microsoft.com/windows*.

Note that a few URLs listed below are redirections to other Microsoft Web sites, such as the Microsoft Developer Network (MSDN) site at *msdn.microsoft.com*. And information about Microsoft's suite of developer products is actually found on the MSDN site rather than on the main *www.microsoft.com* site. For example, the site for Microsoft Visual Studio is found at *msdn.microsoft.com/vstudio* instead of *www.microsoft.com/vstudio*, but the latter URL actually redirects you to the former.

Essential Links for Networking Professionals on Microsoft.com

Relative URL	***Information on . . .***
/backofficeserver	Microsoft BackOffice Server home
/backstage	Inside view of microsoft.com operations
/billgates	Bill Gates's home page
/business	Microsoft business products and services
/catalog	Catalog of all Microsoft products
/certpartner	Microsoft Certified Partners home
/college	Microsoft jobs for college students
/ddk	Microsoft Windows Driver Development Kits
/directx	Microsoft DirectX home
/diversity	Microsoft Diversity home
/downloads	Microsoft download center (redirection)
/ebooks	Microsoft eBooks home
/education	Microsoft education home
/embedded	Windows Embedded home (redirection)
/enable	Microsoft accessibility information
/games	Microsoft games official Web site
/giving	Microsoft giving programs
/hcl	Hardware compatibility list (HCL) for Microsoft products
/hwdev	Windows driver and hardware development site
/insider	Microsoft consumer products and services
/jobs	Jobs at Microsoft
/kids	Free stuff and special offers for kids
/mac	Mactopia, Microsoft products for Macintosh
/mba	Microsoft jobs for MBAs
/mindshare	Mindshare User Group Support Program
/mobile	Mobile Devices and Pocket PC home
/mscorp	Corporate information about Microsoft
/msft	Microsoft investor relations
/museum	Microsoft museum online
/net	Microsoft .NET platform home
/office	Microsoft Office main site (see Note 1 later in this article)
/partner	Microsoft for partners home
/piracy	Microsoft anti-piracy home
/presspass	Microsoft news and press releases
/reader	Microsoft Reader with ClearType
/security	Microsoft security home
/seminar	Microsoft Multimedia Central

(continued)

Essential Links for Networking Professionals on Microsoft.com *continued*

Relative URL	*Information on . . .*
/servers	Microsoft .NET Enterprise Servers (see Note 2 later in this article)
/serviceproviders	Microsoft service providers home
/support	Product support home (redirection)
/technet	Microsoft TechNet home for IT professionals
/trainingandservices	Microsoft training and certification home
/usability	Participate in product evaluations
/vstudio	Redirection to Microsoft Visual Studio .NET site on MSDN (see Note 3 later in this article)
/windows	Microsoft Windows main site (see Note 4 later in this article)
/winlogo	Microsoft Windows logo program
/worldwide	Microsoft worldwide information

The following table lists some other useful URLs in the microsoft.com domain; these, however, begin with a host prefix different from the usual *www.* prefix. Each of these sites represents a wealth of information useful to IT professionals.

Some Other Sites in the Microsoft.com Domain

URL	*Description*
communities.microsoft.com/home/	Microsoft newsgroups, technical chats, and user groups
dgl.microsoft.com	Microsoft Office Design Gallery Live (redirection)
office.microsoft.com	Office Update home
mcsp.microsoft.com/home	Microsoft Certified Partner home
mcspreferral.microsoft.com	Find a Microsoft Certified Partner
msdn.microsoft.com	Microsoft Developer Network home

(continued)

Some Other Sites in the Microsoft.com Domain *continued*

URL	*Description*
msdnisv.microsoft.com	Microsoft Business Connection for Partners
msevents.microsoft.com	Search for Microsoft events (redirection)
mspress.microsoft.com	Microsoft Press
murl.microsoft.com	Multi-University Research Laboratory
research.microsoft.com	Microsoft Research (MSR) home
search.microsoft.com	Search for info on microsoft.com (redirection)
shop.microsoft.com	Shop online at Microsoft
support.microsoft.com/directory	Microsoft product support home
support.microsoft.com/search	Microsoft Knowledge Base (KB)
terraserver.microsoft.com	Microsoft Terraserver (redirection)
windowsupdate.microsoft.com	Windows Update home

Finally, here are some interesting and useful URLs to Web sites that are managed by or connected with Microsoft but are not part of the microsoft.com domain.

Some Microsoft Sites Outside the Microsoft.com Domain

URL	*Description*
bcentral.com	Microsoft small business resource center
expedia.com	Expedia.com home
hotmail.com	Hotmail
msn.com	MSN
msnbc.com	MSNBC home
passport.com	Microsoft Passport home (redirection)
webtv.com	MSN TV Service
windowslogo.com	Windows Logo Program (redirection)
windowsmedia.com	MSN site for music, radio, video, and more

Notes

1 URLs for specific components of Microsoft Office are usually easy to guess. For example, to find the page for Microsoft Word, use *www.microsoft.com/office/word*, and to find the page for Microsoft Excel, use *www.microsoft.com/office/excel*. This does not always work, however; for instance, *www.microsoft.com/frontpage* for the Microsoft FrontPage home.

2 Although the URL *www.microsoft.com/servers* provides a starting point for information about any of Microsoft's .NET Enterprise Servers, you can usually reach the page for a specific server by using the name of the server in the URL. For example, to find information on Microsoft Application Center 2000, use *www.microsoft.com/applicationcenter*; for information on Microsoft BizTalk Server 2000, use *www.microsoft.com/biztalk*; and so on. Sometimes the URL can be a little more cryptic, as in *www.microsoft.com/isaserver* for Microsoft Internet Security and Acceleration Server 2000. And sometimes the URL requires a specific page, such as *www.microsoft.com/sharepoint/portalserver.asp,* for Microsoft SharePoint Portal Server, although in this case there is a link from the default page *www.microsoft.com/sharepoint* to the main SharePoint Portal Server page.

3 URLs for specific components of Microsoft Visual Studio are sometimes easy to guess. For example, the main page for Microsoft Visual Basic is *msdn.microsoft.com/vbasic*, but the page for Microsoft Visual C++ is *msdn.microsoft.com/visualc* instead. Do not forget to use *msdn* instead of *www* as the first portion of a URL for a developer product.

4 URLs for versions of Microsoft Windows are usually obvious; for example, *www.microsoft.com/windowsxp* for Windows XP, *www.microsoft.com/windows2000/* for Windows 2000, and so on. This pattern breaks, however, with Windows CE, where the URL is instead *www.microsoft.com/windows/embedded/ce*.

See Also: *Microsoft Corporation, Microsoft Developer Network (MSDN), TechNet*

Microsoft Consulting Services (MCS)

A service from Microsoft Corporation that provides direct assistance to large enterprises for planning, deploying, and supporting solutions based on Microsoft technologies.

Overview

Microsoft Consulting Services (MCS), in over 100 offices worldwide, has around 4000 Microsoft experts who can provide consulting services to help enterprises improve productivity, establish a competitive advantage, and make the most of their IT (information technology) investment. MCS offers a full range of programs, including enterprise application planning, distributed network architecture computing, e-commerce solutions, and more. Services offered by MCS include

- **Microsoft Consulting Services:** Integrated consulting and support services that includes on-site technical consulting and the support offered previously by Microsoft Product Support Services (PSS).
- **Microsoft Solutions Framework (MSF):** Provides training on how to plan, build, and deploy enterprise level solutions using Microsoft technologies.
- **Microsoft Operations Framework (MOF):** Provides self-paced training and reference materials addressing best practices for managing the people, processes, and technologies of the IT life cycle.
- **Microsoft Technology Centers (MTC):** Allow IT staff to work directly with Microsoft experts and partners in centers across North America.

For More Information

Visit *www.microsoft.com/business/services/mcs.asp*.

See Also: *Microsoft Operations Framework (MOF), Microsoft Solutions Framework (MSF), Microsoft Technology Center (MTC)*

Microsoft Corporation

The worldwide leader in software for business and personal computing.

Overview

Microsoft Corporation is organized around seven core groups focusing on different aspects of product services:

- **Microsoft Research (MSR):** Focuses on devising innovative ways of making computers easier to use, developing the software design process, designing software for the next generation of hardware, and advancing the mathematical underpinnings of computer science.
- **MSN & Personal Services Business Group:** Concentrates on programming, development, and worldwide sales and marketing for MSN and other services efforts, including MSN eShop, MSN Carpoint, MSN HomeAdvisor, MSNBC, *Slate*, and MSNTV.
- **Operations Group:** Responsible for overall business planning and managing business operations. Its functions include corporate finance, administration, human resources, and IT (information technology).
- **Personal Services Group (PSG):** Encompasses Microsoft's Personal .NET initiative, the Services Platform division, the Mobility group, the MSN Internet Access and Consumer Devices group, and the User Interface Platform division. This group's specialty is making it easy for consumers and businesses to deliver software as a service on a variety of platforms.
- **Platforms Group:** Includes the .NET Enterprise Server group, the Developer Tools division, and the Windows Digital Media division. The group's focus is on continuing to develop the Windows platform by making storage, communication, notification, and sharing services a natural extension of the Windows experience.
- **Productivity and Business Services Group:** Includes the Emerging Technologies group, the Business Tools division, and the Business Applications group, which includes bCentral and Great Plains. The group's goal is to develop and drive Microsoft's broad vision for productivity and business process applications and services.
- **Worldwide Sales, Marketing, and Services Group:** Includes Microsoft Product Support Services, the Network Solutions group, the Enterprise Partner group, the Central Marketing Organization and Microsoft's major business-sales regions worldwide. The group's focus is on integrating the activities of Microsoft's sales and service partners with the needs of Microsoft customers around the world.

The current business leadership team for Microsoft includes

- Bill Gates, Chairman and Chief Software Architect
- Steve Ballmer, Chief Executive Officer
- Rick Belluzzo, President and Chief Operating Officer
- plus many key vice presidents covering different platform and service areas

Microsoft is headquartered in a large campus located in Redmond, Washington. The main campus consists of 40 buildings that provide more than 4 million square feet (371,500 square meters) of office space. Microsoft employs more than 48,000 people worldwide, with almost half of these working in Washington State. Almost half of Microsoft's employees are involved in research and development, and most of the rest are in sales and marketing, with a small percentage in corporate operations and administration. The average age of a Microsoft employee is 34.3 years, and men outnumber women by almost three to one.

Microsoft operates subsidiary offices in more than 60 foreign countries and regions; more than half of Microsoft's revenue comes from these offices. Microsoft's net revenue for the fiscal year ending in June 2001 was $25.3 billion, with a net profit of $7.35 billion. Microsoft is traded on the Nasdaq using the symbol MSFT and has the largest capitalization of any corporation in the world.

History

September 2000 marked the 25th anniversary of Microsoft Corporation, and much has happened in those 25 years. In 1975, the personal computer (PC) was basically a toy for hobbyists, but today it represents the ubiquitous tool of business and consumers. Microsoft and its founder Bill Gates have played a major role in the evolution of the PC into what it has become. By striving to produce innovative products and services to meet customers' evolving needs, Microsoft seeks to realize its vision of "empowering people through great software—anytime, anyplace, and on any device."

Microsoft was founded as a partnership on April 4, 1975, by William H. Gates III and Paul G. Allen. Microsoft began its operations in Albuquerque, New Mexico, and earned only $16,005 in its first year of business. The company soon moved to the Seattle area, and by 1978 its sales had passed the $1 million mark. The company was incorporated on June 25, 1981, as Microsoft Corporation. Microsoft became a publicly traded company in 1986 at $21 per share.

In 1981, IBM decided to bundle Microsoft's MS-DOS operating system with the IBM PC. Microsoft continued to work with IBM throughout the 1980s to develop a successor to MS-DOS called OS/2 but abandoned this relationship in 1990. Meanwhile, Microsoft was developing its own graphical operating system called Microsoft Windows, the first version of which appeared in 1985. Version 3 of Windows was released in 1990, and in 1991 Windows 3.1 became the standard desktop operating system for PCs everywhere. Since then, Microsoft has released a series of successors to Windows 3.1, including the popular Windows 95, Windows 98, and Windows Millennium Edition (Me) platforms for consumers and the Windows NT and Windows 2000 platforms for businesses. The latest versions of Windows, Windows XP and the Windows .NET Server family, offer state-of-the-art technology and performance for business and consumer computing platforms.

In 1989, Microsoft launched its first version of Office, a suite of desktop business productivity software applications. Office has evolved to its present version, Office XP, a powerful suite of tools for business workflow and productivity. Microsoft Office has become the leading office productivity suite used in the workplace today, just as Microsoft Windows has become the dominant desktop operating system.

In 1993, Microsoft released the first version of its 32-bit business computing platform, Windows NT. This operating system soon became the foundation for a suite of server business applications developed by Microsoft and integrated into a single platform called Microsoft BackOffice. The BackOffice suite of server applications included Microsoft Exchange, which has become the leading enterprise messaging and collaboration platform, and Microsoft SQL Server, which is on its way to becoming the leading database platform for business knowledge management solutions. In 2000 a new vision was articulated by Microsoft for the enterprise to succeed BackOffice. This new vision of software as services is based on Microsoft's .NET family of server products and is the major focus of Microsoft research and development at the start of the new millennium.

Notes

Corporate contact information for Microsoft is

Microsoft Corporation
One Microsoft Way
Redmond, WA 98052-6399
USA
Tel: (425) 882-8080
E-fax: (425) 706-7329

For More Information

To find out more about Microsoft and Microsoft products, visit *www.microsoft.com.*

See Also: *BackOffice, microsoft.com, Microsoft Windows, .NET platform*

Microsoft Data Access Components (MDAC)

A set of Microsoft technologies that provide access to information stored in a broad range of data sources.

Overview

Microsoft Data Access Components (MDAC) include the following:

- **ActiveX Data Objects (ADO):** A simplified interface to OLE DB
- **OLE DB:** A low-level interface to multiple types of data sources, including relational databases, ISAM, spreadsheets, and delimited text files
- **Open database connectivity (ODBC):** A standard interface to relational data sources

Developers can use MDAC components for building distributed Web applications and e-commerce solutions.

See Also: *ActiveX Data Objects (ADO), OLE DB, open database connectivity (ODBC)*

Microsoft Developer Network (MSDN)

Microsoft Corporation's portal and support program for its developer community.

Overview

Microsoft Developer Network (MSDN) provides developers who work with Microsoft programming platforms with tools, information, training, and events to help them develop applications for Microsoft Windows platforms. The core of the MSDN program is the MSDN Web site, which provides developers with

- Timely information about Microsoft products and technologies
- MDSN Library, a vast collection of technical information and sample code
- Code Center, an online repository of useful code for Microsoft programming technologies
- Downloadable tools and service packs
- *MSDN Magazine*, helping developers keep up with current trends and developments in Microsoft technologies
- A variety of featured columns and news items on different subjects important to developers
- An online community of newsgroups, technical chats, and user groups
- Information about training, seminars, and special events

MSDN also offers paid subscriptions of various levels, providing developers through monthly CD shipments with news, product documentation, code samples, technical articles, and software for various Microsoft platforms, applications, and programming tools. Developers can also receive regular updates of information on the MSDN site by subscribing to MSDN Flash, a semimonthly e-mail newsletter with news, event listings, and important announcements.

For More Information

Visit MSDN online at *msdn.microsoft.com.*

See Also: *microsoft.com, TechNet*

Microsoft Disk Operating System (MS-DOS)

An operating system created by Microsoft Corporation in 1981 for the first IBM personal computer (PC).

Overview

Microsoft Disk Operating System (usually known only by its acronym, MS-DOS) was a 16-bit operating system that used a text-based command-line interface (CLI) for executing commands. The DOS part of MS-DOS indicates that the operating system is disk-based—that is, the operating code resides on a disk (initially a floppy disk and later the hard disk). MS-DOS revolutionized the nascent PC market by providing users with low-level access to operating system functions such as managing disk storage and memory resources, creating directories and manipulating files, and creating batch files for automating tasks. MS-DOS was so popular that other vendors soon produced their own versions of DOS, including IBM's PC-DOS and Novell's DR-DOS.

History

MS-DOS evolved rapidly and went through a number of revisions that added greater functionality and power to the basic operating system. Its final version, MS-DOS 6.22, was so stable and reliable that even though it had already been superseded for several years by Microsoft Windows 3.1, Microsoft's popular graphical operating system, in the late 1990s some companies could still be found running MS-DOS—some examples being conservative companies such as banks and other financial institutions.

Few companies still run MS-DOS today, however, as Microsoft Windows 2000 provides similar levels of stability and reliability, plus the ease of use of a graphical user interface (GUI) coupled with the processing power and storage capacity of modern Intel-based hardware platforms. Computer technicians still occasionally use MS-DOS, however, mainly in the form of MS-DOS boot disks for repairing problem systems.

History of MS-DOS Versions

Version	*Release Date*	*Features*
1	August 1981	Designed for the IBM PC, the initial version was distributed on a single 160-kilobyte (KB) floppy disk and ran in 8 KB of RAM.
1.1	May 1982	Support was added for double-sided 320-KB disks.
2	March 1983	Designed for the IBM PC/XT, this version added support for hard disks, hierarchical directories, background printing, and third-party device drivers.
2.1	October 1983	Designed for the short-lived IBM PCjr.
3	August 1984	Designed for the new IBM PC/AT, this version added support for 1.2-megabyte (MB) floppy disks and hard drives larger than 10 MB.
3.1	March 1985	Added support for networking and file sharing.
3.2	January 1986	Added support for the new 3.5-inch floppy disks.
3.3	April 1987	Designed for the IBM PS/2, this version added commands and support for international versions.
4.01	February 1988	This version added the Mem command, the MS-DOS shell, and support for hard drives larger than 32 MB.
5	May 1991	For this version, the MS-DOS shell was redesigned, task-swapping was added, and more extensive help, undelete, unformat, and memory-management tools were added.
6	March 1993	Added the MemMaker utility, real-time disk compression, multiple boot configurations, and antivirus and backup utilities.
6.2	October 1993	Added Scandisk for low-level disk checking.
6.22	February 1994	Added DriveSpace disk compression.

Architecture

MS-DOS commands come in two types:

- **Built-in commands:** Embedded in the MS-DOS command interpreter Command.com. Examples include Dir, Copy, and Date.
- **External commands:** MS-DOS utilities that reside as separate files. Examples include Doskey, Edit, and Smartdrv.



```
C:\DOS>dir s*

 Volume in drive C is MS-DOS_6
 Volume Serial Number is 2565-9A28
 Directory of C:\DOS

SCANDISK EXE       124,262 05-31-94   6:22a
SCANDISK INI         6,920 05-31-94   6:22a
SETUP    EXE        72,842 05-31-94   6:22a
SYS      COM         9,432 05-31-94   6:22a
SETVER   EXE        12,015 05-31-94   6:22a
SHARE    EXE        10,912 05-31-94   6:22a
SIZER    EXE         7,169 05-31-94   6:22a
SMARTDRV EXE        45,145 05-31-94   6:22a
SMARTMON EXE        28,672 05-31-94   6:22a
SMARTMON HLP        10,727 05-31-94   6:22a
SORT     EXE         6,938 05-31-94   6:22a
SUBST    EXE        18,526 05-31-94   6:22a
       12 file(s)        353,560 bytes
                     423,239,680 bytes free
```

MS-DOS. *Example of running Dir, an MS-DOS command.*

The core of the MS-DOS operating system consists of three primary files in the root of the system partition:

- **Io.sys:** Controls the boot process and contains basic input/output (I/O) drivers.
- **Msdos.sys:** Operating system kernel. Applications request operating system services through Msdos.sys, which translates them into actions that can be performed by Io.sys and device drivers.
- **Command.com:** Command interpreter, which provides a user interface for executing MS-DOS commands.

In addition, two other text files help control the MS-DOS boot process:

- **Config.sys:** Contains commands that configure hardware components such as memory, keyboard, mouse, and printer
- **Autoexec.bat:** Contains startup commands that configure your prompt and path and run memory-resident programs such as Doskey and Smartdrv

The remaining external MS-DOS commands and utilities are by default found in the directory C:\DOS.

Notes

You can add networking functionality to MS-DOS by using the Microsoft Network Client 3 for MS-DOS add-on. You can create installation disks for this software using the Network Client Administrator tool in Microsoft Windows NT.

See Also: *Microsoft Windows*

Microsoft Foundation Classes (MFC)

A set of object-oriented interfaces to the Microsoft Windows application programming interface (API).

Overview

Microsoft Foundation Classes (MFC) include classes, global functions, global variables, and macros that provide a framework for developing applications for Windows platforms. MFC encapsulates much of the Windows API by providing classes that represent key Windows objects, such as windows, controls, dialog boxes, brushes, and fonts. Programmers can develop Windows-based applications by using a combination of C++ code and MFC instead of calling Windows API functions directly. Many MFC class member functions actually call the encapsulated Windows API functions. Note that you cannot call MFC class member functions directly—you have to instantiate the class first.

Architecture

The majority of the MFC are derived by inheritance from the root class named CObject. CObject provides support for serializing data and obtaining run-time class information, although you do not need to derive new classes from CObject if you do not need these capabilities. Other classes in MFC include the following:

- MFC application architecture classes, which supply common functionality to most applications and create the framework for an application. The AppWizard uses these classes to create new applications.
- Windows, dialog, and control classes for creating and managing windows.
- Drawing and printing classes for encapsulating device contexts for graphical output and creating drawing tools such as brushes, palettes, and bitmaps.
- Data type, array, list, and map classes for handling data of various types.

- File and database classes for storing and retrieving files in databases or on disks. These include classes for file input/output (I/O), Data Access Objects (DAO), ActiveX Data Objects (ADO), and open database connectivity (ODBC).
- Internet and networking classes for exchanging information between computers and over the Internet. These include classes for Windows Sockets and Internet Server API (ISAPI).
- OLE classes for creating compound documents and OLE objects, using Automation, creating ActiveX controls, and other functions.
- Debugging and exception classes for error handling and debugging applications.

See Also: *ActiveX, application programming interface (API), Data Access Objects (DAO), open database connectivity (ODBC)*

Microsoft Management Console (MMC)

A tool and software framework for administering systems running Microsoft Windows 2000 or later.

Overview

The Microsoft Management Console (MMC) was first included with Microsoft Windows NT Option Pack to provide an integrated management framework for a wide range of administrative tasks. The MMC later became the standard administrative interface for managing the Microsoft Windows 2000 operating system and server applications such as Microsoft Exchange Server and Microsoft SQL Server.

MMC offers the following features:

- **Customization:** Administrators can create an MMC tool that contains the exact functionality they need.
- **Integration:** MMC integrates all management capability into a single common framework, making it easier to learn and perform network administration.
- **Flexibility:** Third-party companies can create their own snap-ins to further extend the capabilities of MMC.

Windows 2000 and later versions include a number of preconfigured consoles known as administrative tools. These tools are used for performing specific administrative tasks, and you can access them using the Administrative Tools shortcut in the Programs group of the Start menu.

Implementation

By itself, the MMC does not provide any system or network management capability. Instead, it provides an environment in which administrative tools called snap-ins can be run. A snap-in is a software component that provides some system or network management capability for administrators to perform standard tasks.



Directory	Alias	Include in Catalog
D:\Doc...		Yes
D:\		Yes
E:\		Yes
C:\		Yes
D:\Doc...		No
D:\Doc...		No
D:\Doc...		No

MMC console. *Computer Management, an example of an MMC console.*

When one or more snap-ins have been added to a blank console, the configuration can be saved as an .msc file and then shared with other administrators by e-mail or by sharing it on a file server. The MMC also supports deregulation of different levels of management capability to other administrators. For example, an administrator might

- Create a specific console for a specific administrative task. An administrator can thus create a custom administrative tool that is not cluttered with unnecessary functionality and provides just enough functionality to perform the task at hand.
- Create a console for unifying a set of different administrative tasks. An administrator can thus create a single console with which all common

administrative tasks can be performed instead of switching between different tools for different tasks.

- Create a read-only console that could be distributed to junior administrators so they can use only the functionality added to the console.

The MMC user interface presents a hierarchical view of your network resources in a two-pane view similar to that of Windows Explorer. The left pane (the Scope pane) shows a hierarchical view of the administrative namespace of manageable nodes (network objects), while the right pane (Results pane) shows the contents, services, or configuration items of the selected node in the Scope pane. You perform management tasks by using the menu or toolbars, opening property sheets for nodes, and accessing Web pages in the Results pane.

Microsoft Market

A business-to-business (B2B) procurement system created and used internally by Microsoft Corporation.

Overview

Microsoft Market is an Internet-based procurement system developed by Microsoft to streamline operations with its supply-chain partners. Although Microsoft Market is used internally by Microsoft and is not open to the public, it is an excellent example of how B2B systems using the Internet can reduce the cost of doing business with a company's business partners.

Before deploying Microsoft Market, Microsoft's procurement costs typically were $60 per transaction. With Microsoft Market implemented, this overhead fell to less than $5 per transaction. Using Microsoft Market, purchases of goods and services from partners and vendors can be performed using a standard Web browser interface. Microsoft Market has helped Microsoft lower its procurement costs and speed up its business cycle; it has also reduced sales and marketing costs and has created new sales opportunities and improved customer service. Microsoft Market puts Microsoft in the forefront of companies implementing B2B Internet technologies in streamlining business process to gain a competitive advantage in the marketplace.

See Also: *B2B, e-business*

Microsoft Office User Specialist (MOUS)

A Microsoft certification for users of Microsoft Office.

Overview

The Microsoft Office User Specialist (MOUS) certification enables individuals to demonstrate their in-depth knowledge of the Office suite of business productivity tools. The MOUS certification can be used for skills assessment to help them find the qualified knowledge workers they need for business success.

Depending on the version of Office considered, the MOUS program provides different levels of certification to help identify proficient, expert, and master levels of competency in using the product. MOUS certification is also available for Microsoft Project 2000.

For More Information

Find out more about MOUS at *www.microsoft.com/trainingandservices.*

See Also: *Microsoft Certified Professional (MCP)*

Microsoft Official Curriculum (MOC)

Courseware developed by Microsoft Corporation for training in Microsoft products and technologies.

Overview

Microsoft Official Curriculum (MOC) courseware is designed to provide comprehensive training in Microsoft products to IT (information technology) professionals who develop, implement, administer, and support business solutions based on Microsoft platforms, applications, and tools. MOC courseware are available for the full range of Microsoft products, including all versions of Microsoft Windows, the .NET Enterprise Server family, and Microsoft programming platforms. MOCs are available in different forms, including

- Instructor-led courseware designed for use at Microsoft Certified Technical Education Centers (CTECs) and taught by Microsoft Certified Trainers (MCTs).
- Self-paced training kits available through Microsoft Press.

- Online courseware.

MOCs are the standard means for IT professionals to prepare for exams leading to Microsoft Certified Professional (MCP) certifications.

For More Information

Find out more about MOCs at *www.microsoft.com/trainingandservices.*

See Also: *Certified Technical Education Center (CTEC), Microsoft Certified Professional (MCP)*

Microsoft Operations Framework (MOF)

A service by Microsoft Corporation that provides technical guidance on Microsoft technologies to large enterprises.

Overview

Microsoft Operations Framework (MOF) is part of the Microsoft Consulting Services (MCS) program and is designed to help enterprises achieve mission-critical reliability, availability, supportability, and manageability in their use of Microsoft products and technologies. MOF provides various tools to enterprises, including assessment tools, best practices, case studies, operations guides, support tools, templates, and white papers. Issues covered in these resources address the people, process, technology, and management issues that arise in large, heterogeneous IT (information technology) environments. MOF also provides structured support programs and other services that can enhance the capabilities of your in-house IT operations.

For More Information

Learn about MOF at *www.microsoft.com/business/services/mcsmof.asp.*

See Also: *Microsoft Consulting Services (MCS)*

Microsoft RAS Protocol

A legacy remote access protocol from Microsoft Corporation.

Overview

Microsoft RAS Protocol is a remote access protocol developed for Microsoft Windows for Workgroups 3.11 and Windows NT 3.1 as an alternative to Serial Line Internet Protocol (SLIP) that was in common use at that time on the UNIX platform. Microsoft RAS Protocol enables legacy Windows for Workgroups and Windows NT clients to dial in and connect to a remote access server (RAS) using the NetBIOS Enhanced User Interface (NetBEUI) protocol. Once the remote client establishes a connection, the remote access server acts as a NetBIOS gateway to enable the client to access other servers on the network using NetBEUI, NetBIOS over Internetwork Packet Exchange (IPX), or NetBIOS over Transmission Control Protocol/Internet Protocol (TCP/IP).

Microsoft RAS protocol is supported by later versions of Windows only for purposes of backward compatibility. You need RAS Protocol only if you are connecting to a Microsoft Windows remote access server from legacy Windows clients running Windows for Workgroups 3.11 or Windows NT 3.1. Apart from this usage, Microsoft RAS Protocol has been entirely superseded by the Point-to-Point Protocol (PPP), the industry-standard protocol for remote access.

See Also: *NetBEUI, NetBIOS, Point-to-Point Protocol (PPP), Serial Line Internet Protocol (SLIP), UNIX*

Microsoft Research (MSR)

A branch of Microsoft Corporation concerned with advanced research in computer science and technologies.

Overview

Microsoft Research (MSR) pursues research in a variety of different technologies that are viewed as having the potential to change the face of computing over the next decade. These technologies include artificial intelligence (AI), computer vision, speech processing, quantum computing, and advances in operating systems and programming language and tools that will make computers friendlier and easier to use.

MSR was founded in 1991 and was the first research laboratory for basic computer science established by any software company. MSR currently has over 600 researchers operating in four different laboratories around the world:

- Redmond, Washington
- San Francisco, California
- Cambridge, United Kingdom
- Beijing, China

For More Information

Visit MSR at *www.research.microsoft.com.*

Microsoft Solutions Framework (MSF)

A Microsoft Corporation training program for large companies that provides guidance on planning, building, and deploying solutions based on Microsoft products and technologies.

Overview

Microsoft Solutions Framework (MSF) addresses training in the areas of enterprise application development, architecture design, component design, and deployment of infrastructure. MSF training is based on best practices from real-life consulting done by Microsoft Consulting Services (MCS), Microsoft Certified Partners, and others who develop Microsoft solutions for business needs. The MSF program is offered to enterprises through MCS.

M

MSF is based on a series of guidelines-based models, including

- **Application Model:** Provides guidelines for software design and development to improve development, maintenance, and support.
- **Design Process Model:** Provides guidelines for project design based on a flexible, user-centric continuum and using a three-phase approach of conceptual, logical, and physical design.
- **Enterprise Architecture Model:** Provides guidelines for building enterprise architecture through versioned releases to shorten the enterprise architecture planning cycle.
- **Process Model:** Provides guidelines for structuring projects to improve project control, shorten delivery time, and minimize risk.
- **Risk Management Model:** Provides guidelines for assessment, prioritization, and risk management for projects.
- **Team Model:** Provides guidelines for organizing teams by project to improve internal teamwork.

For More Information

Visit *www.microsoft.com/business/services/mcsmsf.asp.*

See Also: *Microsoft Certified Partner, Microsoft Consulting Services (MCS)*

Microsoft Technology Center (MTC)

A state-of-the-art training center for learning about Microsoft technologies and solutions.

Overview

Microsoft Technology Centers (MTCs) are laboratories where enterprise IT (information technology) staff can work side by side with Microsoft experts and partners to design, develop, and test solutions based on Microsoft applications and platforms. MTCs are located in various cities across North America and offer a broad range of facilities, programs, and expertise for developing technology solutions for specific business needs. MTCs also offer boot camps to provide environments for rapid learning of state-of-the-art Microsoft technologies and solutions such as BizTalk and the .NET framework. MTCs are available to enterprises through Microsoft Consulting Services (MCS).

For More Information

Visit *www.microsoft.com/business/services/mtc.asp.*

See Also: *Microsoft Consulting Services (MCS)*

Microsoft Windows

Microsoft Corporation’s flagship operating system platform.

Overview

Microsoft Windows is a family of operating systems that lie at the core of Microsoft’s strategy to make PCs easier to use, reduce the cost of PC ownership, advance the PC platform in the enterprise, and integrate PCs with the Internet.

Windows operating systems evolved in the 1990s from the earlier MS-DOS, Microsoft's powerful text-based disk operating system for personal computers. The first versions of Windows were 16-bit operating systems that essentially ran on top of MS-DOS and provided an easy-to-use graphical user interface (GUI) that made computers easier to learn and use. These 16-bit versions included Windows 3.1 and Windows for Workgroups 3.11, the network-aware version of Window 3.1. In the middle of the decade, Microsoft released a new version of Windows called Windows 95, a desktop operating system that included a new and more powerful GUI, support for preemptive multitasking, and enhanced management of system resources. Windows 95 evolved into Windows 98 and then Windows Millennium Edition (Windows Me).

Meanwhile, Microsoft also developed a fully 32-bit operating system called Windows NT. This new operating system was more powerful, robust, and secure than the Windows 95/98/Me family and was intended for business users instead of consumers. Although Windows NT 3.51 was based on the Windows 3.1 GUI, the popular Windows NT 4 employed a GUI similar to Windows 95. Windows NT 4 was offered in a variety of flavors targeted at the desktop, local area network (LAN) server, and enterprise server operating system markets.

As the decade concluded, Windows NT was superseded by the powerful Windows 2000 family of operating systems, which offered great stability and powerful features foundational for building strategic e-business solutions for the enterprise. Most recently, two new Windows platforms have evolved:

- **Windows XP:** A completely new 32-bit desktop operating system that removes all remaining vestiges of MS-DOS and comes in two flavors: Windows XP Home Edition for home users and Windows XP Professional for corporate use. Windows XP is the natural desktop upgrade path for Windows 95/98/Me, Windows NT 4 Workstation, and Windows 2000 Professional.
- **Windows .NET Server family:** The next evolution of the Windows 2000 Server family of operating systems.

A separate evolutionary path for Windows has produced the Windows CE 3 operating system, a lightweight version of Windows designed for handheld PCs and appliances. Windows NT Embedded, another flavor of Windows, is a low-footprint version designed for industrial control systems and other devices with limited processing and memory.

The table below lists the current versions of Windows. For more information about particular versions, see the corresponding entries in Chapter W of this book.

Current Microsoft Windows Operating Systems

Version	*Description*
Windows .NET Server	Comes in Standard, Enterprise, Datacenter, and Web Server versions and is the successor to the Windows 2000 family of business operating systems
Windows XP	Comes in Professional and Home Edition and is the successor to both the Windows Me and Windows 2000 Professional lines of business and consumer Windows desktop operating systems
Windows 2000	Comes in Professional, Server, Advanced Server, and Datacenter Server versions and is the successor to the Windows NT 4 family of business operating systems
Windows Me	Successor to Windows 95 and Windows 98 consumer Windows desktop operating systems
Windows CE	Lightweight version of Windows designed for handheld computing devices and computer appliances
Windows NT Embedded	Small-footprint version of Windows NT designed for industrial control systems and small devices

For More Information

Visit the Windows home at *www.microsoft.com/windows.*

See Also: *Windows 3.1, Windows 95, Windows 98, Windows 2000, Windows CE, Windows Me (Windows Millennium Edition), Windows .NET Server, Windows NT, Windows XP*

middleware

Application logic between the client and data sources.

Overview

The concept of middleware emerged in the mid-1990s as a solution to scalability problems inherent in the traditional two-tier client/server computing paradigm. In a typical business computing system, client machines access information stored on back-end database servers for accessing inventory, sales, invoicing, and other business information. The scalability issue arises as databases grow in size and complexity—then the problem becomes where to implement the application logic for best performance. Choosing a “fat client” approach moves more of the processing load to the client, but the result is that whenever the business application is upgraded or patched, new software needs to be installed on every client across the enterprise. Another approach is to move application logic to the database servers by using centrally stored procedures, but this increases the processing load on the servers considerably.

A third approach is to use middleware, which represents a third tier of software stored on a special server separate from the client and the database server. Employing middleware means that thin clients can be used rather than fat ones, that desktop systems do not need to be updated as frequently, and that some of the processing load is siphoned off from the database servers. When application logic needs to be updated, it can be done quickly and easily on the servers running the middleware. The result of proper implementation of middleware in the enterprise is greater scalability and better performance of line-of-business applications that use database technologies, such as Enterprise Resource Planning (ERP) and Customer Relations Management (CRM) applications.

Middleware technologies are also used in other scenarios. For example, cellular systems can allow mobile users to access company intranets using personal digital assistants (PDAs) and other devices. This is generally done by implementing a middleware server that connects the mobile devices to the database servers. An example of such a middleware application is Microsoft Mobile Information Server, one of the new .NET Enterprise Servers from Microsoft Corporation. Another type of middleware system is a wireless e-mail gateway that connects mobile users with handheld devices such as Research In Motion’s Blackberry with Internet mail hosts. Such middleware servers are often available from vendors as either installable applications or as self-hosted (stand-alone) appliances.

As enterprise systems grow more complex, three-tiered systems often grow into *n*-tiered systems that employ several levels of middleware. The principles are still the same, though: improving performance and scalability by isolating application logic from both the client and the database server.

Notes

The term *middleware* is sometimes used in other contexts. For example, it can refer to the various technologies and protocols used to connect the clients with the back-end servers. These technologies can include remote procedure calls (RPCs), synchronous transactions, asynchronous message passing mechanisms, and distributed object oriented programming technologies such as Microsoft’s Distributed Component Object Model (DCOM), Sun Microsystems’ JavaBeans, and The OpenGroup’s Common Object Request Broker Architecture (CORBA).

See Also: *client/server, Common Object Request Broker Architecture (CORBA), Customer Relationship Management (CRM), Distributed Component Object Model (DCOM), enterprise resource planning (ERP), Java, Mobile Information Server, remote procedure call (RPC)*

MIF

Stands for Management Information Format (MIF), a standard format for describing hardware and software management information.

See: *Management Information Format (MIF)*

Millennium

An advanced distributed computing architecture being developed by Microsoft Research.

Overview

Millennium is a radically new vision for distributed computing in which the automatic distribution of application processing is the norm rather than the exception. The Millennium paradigm assumes that all applications are intrinsically distributed across the network rather than locally centralized on servers. Millennium is based on an advanced network-aware operating system than can dynamically distribute processing tasks and manage resources across the network. Millennium is based on four key concepts:

- **Abstract distribution of tasks:** The network automatically distributes tasks for execution to different processing nodes. Programmers do not need to worry about how network resources are managed for the applications they develop.
- **Abstract locality:** Applications do not need to know where they reside or are executed. Resources for applications are automatically located by the network and assigned as needed.
- **Automatic performance tuning:** The network dynamically monitors and adjusts how and where processing tasks are distributed in order to optimize application performance.
- **Dynamic resource management:** Hardware and software resources are automatically enlisted and bound to application processes at runtime and released when no longer required.

One of the Millennium prototype projects is called Coign, which supports the self-configuration and self-tuning of Component Object Model (COM) objects across a network. Coign supports the dynamic partitioning of applications to improve performance and simplify the management of distributed applications.

For More Information

Find out more at *www.research.microsoft.com/sn/millennium.*

See Also: *Component Object Model (COM), Jini, Microsoft Research (MSR)*

MIME

Stands for Multipurpose Internet Mail Extensions, extensions to Simple Mail Transport Protocol (SMTP) that allow multipart and binary messages to be sent using e-mail.

See: *Multipurpose Internet Mail Extensions (MIME)*

mirrored volume

A type of fault tolerance supported by Microsoft Windows 2000 and Windows .NET Server.

Overview

In Microsoft Windows 2000 and Windows .NET Server, a mirrored volume is a type of volume created with Disk Management that duplicates data on two separate physical disks. This provides a measure of fault tolerance, for if one physical disk fails, the data is still accessible from the second disk.

In Windows 2000 and Windows .NET Server, mirrored volumes cannot be extended and they must be created on dynamic disks. Although mirrored volumes perform read operations more slowly than RAID 5 volumes, they do execute write operations more quickly.

Notes

The Windows NT equivalent of a mirrored volume was called a mirror set.

See Also: *dynamic volume, mirroring, mirror set, redundant array of independent disks (RAID)*

mirroring

Maintaining an identical copy of an information store or disk system for fault tolerance purposes.

Overview

Mirroring is one of several different strategies for integrating fault tolerance into storage systems. Using mirroring, two identical copies of mission critical data are maintained, and if the primary system goes down, the secondary system can be brought online quickly with little or no loss of data. Mirroring can be implemented at various levels from disk mirroring (two identical disk drives within a server) to server mirroring (two identical servers having the same data and running at different locations) to mirroring of enterprise storage solutions such as storage area networks (SANs). Mirroring at higher levels is commonly used in financial institutions such as banks and brokerages to ensure speedy recovery in the event of a disaster.

Mirroring is not a replacement for tape backup systems; instead, it complements the standard backup cycle by providing additional redundancy and fault tolerance. Mirroring of enterprise servers is a popular solution in high availability environments because the recovery window (the time to bring a mirrored system online after a disaster) is typically less than an hour, while the time to restore a system completely from backup sets may be 24 to 48 hours. Mirroring does have the disadvantage of being expensive compared to tape backup, since duplicate storage systems are required to implement it.

Implementation

Mirroring can implemented using several techniques:

- **Symmetric mirroring:** Usually simply called mirroring, symmetric mirroring involves real-time replication of information using a transaction model to ensure the mirrors are identical at all times. In symmetric mirroring, data is written nearly simultaneously to both the primary and secondary mirrored systems. An example of symmetric mirroring is disk mirroring in Microsoft Windows 2000, which mirrors two volumes to provide fault tolerance for high-availability servers. In addition, symmetric mirroring can also be performed across a wide area network (WAN) between two network storage systems, a setup that requires a reliable, high-speed, low-latency WAN link such as Metropolitan Ethernet for best performance.
- **Asymmetric mirroring:** Also known as shadowing, asymmetric mirroring complements symmetric mirroring and generally employs three identical storage systems. In a typical scenario, systems 1 and 2 are colocated at your customer premises and symmetrically mirror each other. Systems 2 and 3 asymmetrically mirror each other, with system 3 being located at a secure remote location. Local data is always current on both mirrors, while the remote mirror is slightly out of sync by a time period called the “mirror gap.” The result is that if both local mirrors go down and the remote mirror is brought online, some transactions will inevitably be lost. The advantage is that the WAN link to the remote site does not have to be an expensive high-speed link as in remote symmetric mirroring, but can instead be a cheaper low-bandwidth link such as frame relay or Integrated Services Digital Network (ISDN). The remote storage system may even be managed by a separate company such as a storage service provider (SSP), eliminating the cost overhead of needing to purchase three identical storage systems.

See Also: *backup, electronic tape vaulting, fault tolerance, frame relay, Integrated Services Digital Network (ISDN), metropolitan Ethernet, mirrored volume, storage, storage area network (SAN), storage service provider (SSP), wide area network (WAN)*

mirror set

A type of fault tolerance supported by Microsoft Windows NT.

Overview

Mirroring is the process whereby data is written simultaneously to two disks, making one disk drive an exact mirror image of the other. This form of fault tolerance technology is properly known as RAID-1 but is called a mirror set in Windows NT (Windows 2000 calls this same configuration a mirrored volume).

The duplication of disk information in a mirror set provides the system with data redundancy, for if one half of the mirror set fails, the system can continue to operate using the duplicate of the failed disk. In Windows NT, mirror sets are commonly used to provide fault tolerance for the system and boot partitions. You can use Disk Administrator, the administrative tool in Windows NT, to create, break, and reestablish mirror sets. In Windows 2000, the corresponding administrative tool is called Disk Management.

For read operations, mirror sets are slower than other redundant array of independent disks (RAID) configurations such as stripe sets with parity, but on the other hand they are faster for write operations.

See Also: *fault tolerance, mirrored volume, mirroring, redundant array of independent disks (RAID)*

mixed mode

A mode of running Microsoft Windows 2000 domain controllers.

Overview

When Windows 2000 domain controllers are running in mixed mode, they are backward compatible with domain controllers running the Windows NT operating system. This is because Windows 2000 domain controllers running in mixed mode use Windows NT LAN Manager (NTLM) as their authentication protocol instead of Kerberos, which allows Active Directory directory service to communicate with downlevel Windows NT domain controllers.

Mixed mode has the following special considerations:

- It does not support the use of universal groups.
- It does not support unlimited nesting of groups—you can only add global groups to domain local groups with one level of nesting.
- It does not support policy-based management of remote access servers.
- Multimaster replication does not function between uplevel and downlevel domain controllers—downlevel Windows NT domain controllers replicate updates from the PDC to the backup domain controllers (BDCs) in the usual way.
- Some advanced management options for Windows 2000 domain controllers are not available for downlevel Windows NT domain controllers.

Implementation

Mixed mode is designed to be used mainly as a temporary solution during the process of migrating a Windows NT–based network to a Windows 2000–based one. Once the migration is complete, you can switch your Windows 2000 domain controllers from mixed mode to native mode. Note that this is a process that can be performed only once—you cannot change native mode domain controllers back to mixed mode.

Windows 2000 domain controllers are installed in mixed mode by default when you run the Active Directory Installation Wizard to upgrade a member server to a domain controller. To change domain controllers from mixed mode to native mode, use the Active Directory Users and Computers console. During a migration from Windows NT to Windows 2000, after you have upgraded all your downlevel domain controllers to Windows 2000 you should change your domain to native mode in order to take advantage of Windows 2000's special features, such as multimaster replication, nesting of groups, and universal groups. If you are deploying a pure Windows 2000–based network, however, you should configure your domain controllers to run in native mode from the start.

See Also: *Active Directory, Active Directory Users and Computers, domain controller, domain modes, Kerberos, native mode, universal group, Windows NT LAN Manager Authentication*

MLP

Stands for Multilink Point-to-Point Protocol, a wide area network (WAN) protocol for aggregating multiple Point-to-Point Protocol (PPP) connections.

See: *Multilink Point-to-Point Protocol (MPPP)*

MLS

Stands for Multilayer Switching, a LAN switching term that can have several meanings.

See: *Multilayer Switching (MLS)*

MMC

Stands for Microsoft Management Console, a tool and software framework for administering systems running Microsoft Windows 2000 or later.

See: *Microsoft Management Console (MMC)*

MMDS

Stands for Multipoint Multichannel Distribution Service, a fixed wireless broadband networking architecture.

See: *Multipoint Multichannel Distribution Service (MMDS)*

M-node

A NetBIOS name resolution method used by Microsoft Windows NT.

Overview

Name resolution is the process of converting the name of a host on the network into a network address (such as an Internet Protocol [IP] address). Name resolution must be performed in order to establish communication over a Windows NT network. M-node is one of four basic methods supported by Windows NT for resolving NetBIOS host names—that is, computer names—into IP addresses.

If a computer running Windows NT is configured as an M-node machine, it first tries to use broadcasts to resolve the names of the hosts, similar to a B-node machine. If name resolution fails this way (for example, if broadcasts are stopped by routers from reaching computers on other subnets), Windows NT tries to use a NetBIOS name server to resolve names of other hosts on the network, similar to a P-node machine. A Windows NT server with the Windows Internet Naming Service (WINS) configured on it is a typical example of a NetBIOS name server. The *M* in the term *M-node* stands for *mixed*, as M-node is a mixture of B-node and P-node, in that order.

Notes

M-node is defined in RFCs 1001 and 1002.

See Also: *B-node, H-node, NetBIOS name resolution, P-node*

Mobile Broadband System (MBS)

A proposed fourth-generation (4G) mobile cellular communication system.

Overview

The Mobile Broadband System (MBS) is a project of the Research and Technology Development in Advanced Communications Technologies in Europe (RACE) program. MBS is designed to extend mobile communications to support broadband communication at multimegabit data transmission rates of up to 155 megabits per second (Mbps). MBS is seen as a key enabler for transmission of multimedia video and audio content on cellular communications systems.

MBS is basically a wireless extension to broadband ISDN (B-ISDN), a technology that has been talked about for many years and is still in the developmental stage. The underlying transport used in MBS is Asynchronous Transfer Mode (ATM), and the proposed MBS standard from the International Telecommunication Union (ITU) is intended to fully integrate MBS with the ATM-based Integrated Broadband Communications Network (IBCN), also proposed for Europe.

See Also: *Asynchronous Transfer Mode (ATM), broadband ISDN (B-ISDN), cellular communications, International Telecommunication Union (ITU)*

Mobile Execution Environment (MExE)

An emerging standard for running Java applications on mobile phones.

Overview

Mobile Execution Environment (MExE) is a proposal of the European Telecommunications Standards Institute (ETSI) to enable mobile devices with limited processing power such as cell phones and personal digital assistants (PDAs) to run Java applications. Using MExE, for example, a mobile knowledge worker could easily access enterprise applications using his cell phone.

MExE is designed to reduce the footprint required for running Java on small mobile devices. This is done by partly compiling client-side Java applications on middleware servers, thus reducing the processing and memory requirements needed to run a full Java interpreter on these mobile devices. Wireless Application Protocol (WAP) is then used as a transport for delivery of information to the mobile devices.

See Also: *cellular communications, Java, Wireless Application Protocol (WAP)*

Mobile Information Server

Microsoft Corporation's .NET Enterprise Server for enabling wireless access to enterprise data.

Overview

Microsoft Mobile Information 2001 Server provides enterprises with a platform for allowing users to access data stored on corporate intranets and database servers from mobile devices such as cell phones and wireless personal digital assistants (PDAs). Mobile Information Server thus extends the reach of .NET enterprise applications by bringing content to the mobile knowledge worker. Using Mobile Information Server, people can have access to corporate e-mail, calendars, contacts lists, tasks, and any other desired information.

Mobile Information Server includes two components:

- A server application that acts as middleware between back-end .NET Enterprise Servers such as Microsoft Exchange 2000 Server and Microsoft SQL Server
- A client application called Microsoft Outlook Mobile Access that provides a Web-based portal to information residing on these servers

Mobile Information Server offers an extensible architecture that supports connectors for allowing mobile users to access information stored on any type of data server or information store. Mobile Information Server supports end-to-end security, load balancing and clustering, and content replication and delivery.

For More Information

Find out more at *www.microsoft.com/miserver.*

See Also: *cellular communications, Exchange Server, middleware, .NET Enterprise Servers, SQL Server*

Mobile Services Initiative (M-Services)

A proposed set of standards for broadband cellular Internet access.

Overview

Mobile Services Initiative (M-Services) is designed to speed the deployment of broadband cellular Internet access. The aim is to bring standards and consistency by providing guidelines for graphical displays on cellular handsets, transmission schemes for accessing music and video, and other functions. M-Services is designed to overcome some of the problems inherent in Wireless Application Protocol (WAP), the first generation of cellular Internet access technologies. WAP is generally viewed as too slow and complex for mobile platforms, and application development for this platform has tended to result in a variety of proprietary extensions.

M-Services focuses on providing guidelines for application development on General Packet Radio Services (GPRS), a 2.5G upgrade to existing second-generation (2G) Global System for Mobile Communications (GSM) cellular systems used widely in Europe and becoming more popular in North America. GPRS is viewed as a stepping stone to true third-generation (3G) broadband mobile communications systems, which are now not likely to be widely deployed until 2005.

M-Services is supported by the GSM Association, by manufacturers of mobile technologies such as Ericsson, Motorola, and Nokia, and by mobile operators such as France Telecom and Telecom Italia Mobile.

See Also: *2.5G, 3G, cellular communications, General Packet Radio Service (GPRS), Global System for Mobile Communications (GSM), Wireless Application Protocol (WAP)*

Mobile Transport Serving Office (MTSO)

A component of a cellular communications system.

Overview

In a cellular communications system, the region where coverage is desired is broken up into a series of small overlapping areas called cells. Each cell is serviced by a base station, which has a transceiver (transmitter/receiver) for sending and receiving calls with mobile users in that area. For communications to take place, however, frequencies or time slots (depending on the cellular technology used) must be allocated without conflict to users in different cells, a function performed by a central station called a Mobile Transport Serving

Office (MTSO). The MTSO thus coordinates the activities of the different transceivers within a given region and provides a land-based (wireline) link between these transceivers and the telco central office (CO) for connection to the Public Switched Telephone Network (PSTN). Connections between base stations and the MTSO, and between the CO and the MTSO, are usually made using telco trunk lines.



Mobile Transport Serving Office (MTSO). *How the MTSO connects a cellular communications system to the Public Switched Telephone Network (PSTN).*

See Also: *cellular communications, central office (CO), Public Switched Telephone Network (PSTN), telco*

MOC

Stands for Microsoft Official Curriculum, courseware developed by Microsoft Corporation for training in Microsoft products and technologies.

See: *Microsoft Official Curriculum (MOC)*

modem

A device that enables digital data transmission to be transmitted over telecommunications lines.

Overview

The term *modem*, which stands for modulator/demodulator, generally refers to analog modems, data communications equipment (DCE) that converts the digital signals used by data terminal equipment (DTE) such as computers into analog sound waves that can be transmitted over the analog local loop portion of the Public Switched Telephone Network (PSTN). Analog modems generally have two interfaces: an RS-232 serial transmission interface for connecting to the DTE, which is usually a computer; and an RJ-11 telephone interface for connecting to a standard four-wire PSTN telephone jack.

Analog modems are popular and come in various types:

- Internal modems, which are installed as interface cards inside the computer and might use some of the machine's CPU (central processing unit) processing power for functions such as encoding and data compression. One popular type of internal modem is the soft modem, an inexpensive modem that utilizes some of the processing power of the computer's CPU to operate.
- External modems, which are generally more expensive and connect to the serial port on the computer using a DB9 or DB25 connector. External modems are useful when several users need to share a modem.
- Personal Computer Memory Card International Association (PCMCIA) modems, which are credit-card-sized modems for laptop computers used by mobile workers. PCMCIA soft modems are also available.
- Voice/data/fax modems, which can be used for file transfer, sending and receiving faxes, and voice mail using associated software. These are available in internal, external, and PCMCIA formats.

Another kind of modem is the digital modem, one example of which is the Integrated Services Digital Network (ISDN) terminal adapter. Although a digital modem does not convert digital signals into analog and vice versa, a form of modulation called line coding does take place. Line coding is used to modulate the digital signals from the DTE, which is typically a switch or router connecting to a local area network (LAN), into digital signals that can be transmitted over the specially conditioned ISDN telephone. Other popular types of digital modems include cable modems and Digital Subscriber Line (DSL) modems. Digital modems use a variety of serial interfaces, including RS-232, RS-449, V.35, X.21, and High Speed Serial Interface (HSSI).

See Also: *analog modem, cable modem, data communications equipment (DCE), data terminal equipment (DTE), digital modem, Digital Subscriber Line (DSL), Integrated Services Digital Network (ISDN), ISDN terminal adapter, Public Switched Telephone Network (PSTN), RS-232, serial transmission*

modem eliminator

A device for connecting two pieces of data terminal equipment (DTE).

Overview

Modem eliminators provide an easy way to connect two pieces of DTE without a modem. Modem eliminators accomplish this by simulating a synchronous transmission data link through generating timing and handshaking signals. Modem eliminators can use a variety of serial interfaces, including RS-232, RS-422/485, RS-530, V.25, or X.21, and can operate at speeds of up to 2.048 megabits per second (Mbps).



Modem eliminator. *Using a modem eliminator to connect two DTE over a serial link.*

Modem eliminators are similar to line drivers, but modem eliminators simply connect two pieces of DTE and line drivers connect DTE to data communications equipment (DCE). Also, line drivers regenerate signals and thus extend the maximum possible distance, but modem eliminators do not. Finally, line drivers are used in pairs (one at each end of the line), and modem eliminators are used singly and are placed at the midpoint between the two devices being connected.

See Also: *data communications equipment (DCE), data terminal equipment (DTE), line driver, modem, serial transmission*

modem sharing

Any method for sharing a modem among several computers.

Overview

Modem sharing is an inexpensive method for small networks to share a single Internet or remote access connection. For example, in a Small Office/Home Office (SOHO) environment, a cable modem or Digital Subscriber Line (DSL) modem can be used to share a single high-speed Internet connection among several users. Another scenario is in remote branch offices where a single shared modem can be used for occasional remote access connectivity over a wide area network (WAN) link to the head office.

Modem sharing can be implemented in two ways:

- **Hardware-based:** Hubs and routers that have built-in 56K, DSL, or Integrated Services Digital Line (IDSN) modems often have modem sharing capability. In this scenario, you simply plug your phone line into a hub or a router, and then use a Category 5 (Cat5) patch cord to connect the hub or router to your local area network (LAN) hub or switch, and computers on your network transparently have access to the external network. In another approach, you can use a broadband router to connect your LAN to your DSL or cable modem to provide high-speed Internet access to users on your network.
- **Software-based:** By connecting a modem to one machine on the network and installing modem

sharing software on that machine, other machines on that network gain access to the external connection through that machine. Microsoft Corporation includes modem sharing software called Internet Connection Sharing with its Windows Millennium Edition (Me), Windows 2000, and Windows XP operating system platforms. Third-party modem sharing software is also available from a variety of vendors. The main disadvantage of the software-based approach to modem sharing is that if the computer having the modem goes down, other computers on the network cannot use the modem.

Marketplace

Modem sharing hardware for DSL and cable Internet services are becoming popular. Some examples of broadband routers from different vendors include the ZyXEL Prestige 310, Netopia 9100, and WatchGuard SOHO.

Notes

If you use modem sharing to provide your network with high-speed connectivity to the Internet, be sure to use a firewall to secure your network against outside intrusion. If you use Windows 2000, another good step is to turn off Internet File Sharing.

See Also: *broadband Internet access, cable modem, Digital Subscriber Line (DSL), hub, Integrated Services Digital Network (ISDN), modem, router*

modulation

Converting analog signals into digital signals (the reverse process is called demodulation).

Overview

Modulation is the process by which digital information is encoded into analog electrical signals for transmission over a medium. Digital information is usually binary information, as represented by a series of 1s and 0s, and must be converted into analog electrical signals (voltages) for transmission over wires (or into light waves for transmission over fiber-optic cabling).

Modulation is often confused with signal encoding or line coding, as these processes are inherently similar. However, for transmission using modems over the Public Switched Telephone Network (PSTN) lines, the process is generally called modulation, but for transmission over digital lines such as T1, frame relay, and Integrated Services Digital Network (ISDN) lines, the term *encoding* or *line coding* is usually used instead. Some reference works tend to blur this distinction, however, and there is usually some overlap between the concepts.

Types

Modulation forms the basis of the digital-to-analog converter (DAC) component of a standard analog modem. Modulation in modems allows digital binary information to be received from a serial interface on a computer and modulated into sound waves for transmission over the voice-grade PSTN.



Modulation. *Examples of different types of modulation.*

Common types of signal modulation that are used for converting digital to analog signals include

- **Amplitude modulation (AM):** Carries information by modulating the amplitude (voltage) of the carrier signal. Different amplitudes represent different information values. For example, an amplitude of 3 volts might represent a 1, while an amplitude of 1 volt represents a 0.
- **Frequency modulation (FM):** Carries information by modulating the frequency of the carrier signal. Different frequencies represent different information values. For example, a frequency of F might represent a 1, while a frequency of 2F represents a 0.
- **Frequency-shift keying (FSK):** A form of frequency modulation scheme in modem technologies is called in which four frequencies within the PSTN 3-kilohertz (kHz) line bandwidth are used for transmission and reception of binary data, as shown in the following table:

Frequencies Used in FSK Modulation

FSK Frequency	*Meaning*
1070 Hz	Transmitted binary 1
1270 Hz	Transmitted binary 0
2025 Hz	Received binary 0
2225 Hz	Received binary 1

- **Phase modulation (PM):** Carries information by modulating the phase of the carrier signal. Different phases represent different information values. For example, a phase of 0° might represent a 1, while a phase of 180° represents a 0.
- **Differential phase-shift keying (DPSK):** A form of phase modulation used in modem technologies in which relative phase changes instead of absolute phase values are used to represent encoded binary information.
- **Quadrature amplitude modulation (QAM):** A combination of amplitude and phase modulation which allows the encoding of pairs of binary values to be represented as different phase values, as shown in the following table:

QAM Encoding of Binary Value Pairs

QAM Phase Value	*Binary Information Represented*
45° phase shift	11
135° phase shift	10
225° phase shift	01
315° phase shift	00

- **Trellis encoding:** A form of differential phase-shift keying in which a 32-bit constellation of different state symbols for more efficient encoding of information and greater immunity to electromagnetic interference (EMI).

Notes

For modulation (line coding) over digital transmission lines, various techniques can be employed, depending on the networking technology under consideration. These include

- Manchester coding used for standard 10 megabits per second (Mbps) Ethernet networks.
- Carrierless amplitude and phase (CAP) modulation used in older Digital Subscriber Line (DSL) technologies.
- Discrete multitone (DMT) modulation standardized for use in Asymmetric Digital Subscriber Line (ADSL) by the American National Standards Institute (ANSI) and for DSL-Lite by the International Telecommunication Union (ITU).
- Discrete wavelet multitone (DWMT) modulation, used for Very high-rate Digital Subscriber Line (VDSL).

See Also: *Asymmetric Digital Subscriber Line (ADSL), Digital Subscriber Line (DSL), electromagnetic interference (EMI), line coding, modem, Public Switched Telephone Network (PSTN), signal, Very-high-rate Digital Subscriber Line (VDSL)*

MOF

Stands for Microsoft Operations Framework, a service from Microsoft Corporation that provides technical guidance on Microsoft technologies to large enterprises.

See: *Microsoft Operations Framework (MOF)*

MOSPF

Stands for Multicast Open Shortest Path First, a dense mode multicast routing protocol.

See: *Multicast Open Shortest Path First (MOSPF)*

MOUS

Stands for Microsoft Office User Specialist, a Microsoft certification for users of Microsoft Office.

See: *Microsoft Office User Specialist (MOUS)*

moving files

Changing the directory in which a file is stored.

Overview

On Microsoft Windows platforms, files can be moved using a graphical user interface (GUI) tool such as Windows Explorer or from the command prompt using the Move command. Some inheritance issues are associated with moving files on Windows NT and Windows 2000 platforms that use the NTFS file system (NTFS). In particular, the effect of moving a file depends on whether the file is moved within a volume or to a different volume:

- If you move a file within an NTFS volume, it retains its original permissions.
- If you move a file between volumes, it inherits the permissions of the folder it is moved to.

Notes

If you move an object within Active Directory directory service on a Windows 2000–based network, the object loses any permissions that were assigned to the organizational unit (OU) in which it resided and inherits the permissions assigned to the OU to which it is moved. Also, any permissions that were explicitly assigned to the object remain in effect after the object is moved. For example, you might move an object in Active Directory if a user has changed departments and you have to move the user object from the Sales OU to the Marketing OU. Use the Active Directory Users and Computers snap-in for Microsoft Management Console (MMC) to move objects in Active Directory.

See Also: *copying files*

Mozilla

An open-source Web browser.

Overview

Mozilla is an open-source project aimed at developing a free, standards-based Web browser. Mozilla is based on Netscape Navigator, a popular Web browser platform developed by Netscape in the mid-1990s which was itself based on the earlier NCSA Mosaic browser. Mozilla will run on a variety of operating system platforms, including Microsoft Windows, Apple Macintosh, and Linux. The development of the Mozilla browser is being coordinated by Mozilla.org, an open-source organization.

For More Information

Visit *mozilla.org* for details on Mozilla.

See Also: *Internet Explorer, open source, Web browser*

MP

Stands for Multilink Point-to-Point Protocol, a wide area network (WAN) protocol for aggregating multiple Point-to-Point Protocol (PPP) connections.

See: *Multilink Point-to-Point Protocol (MPPP)*

MPLS

Stands for Multiprotocol Label Switching, a protocol for efficiently routing traffic across a large Internet Protocol (IP) network such as the Internet.

See: *Multiprotocol Label Switching (MPLS)*

MPOA

Stands for Multiprotocol over ATM, a method for forwarding Internet Protocol (IP) packets over Asynchronous Transfer Mode (ATM) networks.

See: *Multiprotocol over ATM (MPOA)*

MPPP

Stands for Multilink Point-to-Point Protocol, a wide area network (WAN) protocol for aggregating multiple Point-to-Point Protocol (PPP) connections.

See: *Multilink Point-to-Point Protocol (MPPP)*

MSAU

Another acronym that stands for Multistation Access Unit, a wiring concentrator (passive hub) used in Token Ring networks. An alternative to MAU, the most common acronym for this term.

See: *Multistation Access Unit (MAU or MSAU)*

MS-CHAP

Stands for Microsoft Challenge Handshake Authentication Protocol, an encrypted authentication scheme for Point-to-Point Protocol (PPP) sessions.

See: *Microsoft Challenge Handshake Authentication Protocol (MS-CHAP)*

MSDN

Stands for Microsoft Developer Network, Microsoft Corporation's portal and support program for their developer community.

See: *Microsoft Developer Network (MSDN)*

MS-DOS

Stands for Microsoft Disk Operating System, an operating system created by Microsoft Corporation in 1981 for the first IBM personal computer (PC).

See: *Microsoft Disk Operating System (MS-DOS)*

MS-DOS mode

An operating system mode for some versions of Microsoft Windows that is compatible with running MS-DOS applications.

Overview

MS-DOS mode is a special operating system mode in Windows 95, Windows 98, and Windows Millennium Edition (Me) that allows applications to access hardware directly. This functionality is sometimes needed in order to run older MS-DOS applications (especially games) on these versions of Windows. You can also use MS-DOS mode when you have to run stubborn MS-DOS programs that will not run within an MS-DOS window on these versions of Windows 95.

To switch to MS-DOS mode from Windows, choose Shutdown from the Start menu, and then choose Restart In MS-DOS Mode. The Windows graphical user interface (GUI) vanishes, leaving only an MS-DOS prompt, which allows you to run a single MS-DOS-based application. A stub of the Windows operating system remains in memory and restores the Windows GUI when you type **exit** at the MS-DOS prompt.

See Also: *Microsoft Disk Operating System (MS-DOS), Microsoft Windows*

M-Services

Stands for Mobile Services Initiative, a proposed set of standards for broadband cellular Internet access.

See: *Mobile Services Initiative (M-Services)*

MSP

Stands for Management Service Provider, a company that manages the information technology (IT) infrastructure for other businesses.

See: *Management Service Provider (MSP)*

MSF

Stands for Microsoft Solutions Framework, a training program developed by Microsoft Corporation for large enterprises that provides guidance on planning, building, and deploying solutions based on Microsoft products and technologies.

See: *Microsoft Solutions Framework (MSF)*

MSR

Stands for Microsoft Research, a branch of Microsoft Corporation concerned with advanced research in computer science and technologies.

See: *Microsoft Research (MSR)*

MTC

Stands for Microsoft Technology Center, a state-of-the-art training center for learning about Microsoft technologies and solutions.

See: *Microsoft Technology Center (MTC)*

MTQP

Stands for Message Tracking Query Protocol, an emerging protocol for tracking e-mail messages over the Internet.

See: *Message Tracking Query Protocol (MTQP)*

MTSO

Stands for Mobile Transport Serving Office, a component of a cellular communications system.

See: *Mobile Transport Serving Office (MTSO)*

MTU

Stands for multitenant unit, a building with many tenants, such as a skyscraper.

See: *multitenant unit (MTU)*

Multicast Address Dynamic Client Allocation Protocol (MADCAP)

An extension to the Dynamic Host Configuration Protocol (DHCP) for dynamic assignment of multicast addresses.

Overview

MADCAP is an extension to DHCP that offers dynamic assignment and configuration of Internet Protocol (IP) multicast addresses on Transmission Control Protocol/Internet Protocol (TCP/IP) networks. The MADCAP extensions to DHCP are described in RFC 2131, which makes the earlier RFC 1541 obsolete. MADCAP is supported by the Microsoft Windows 2000 operating system platform.

Implementation

In the Windows 2000 and Windows .NET Server implementations, MADCAP allows DHCP servers to include class D multicast IP addresses in separate DHCP scopes. These class D addresses can range from 224.0.0.0 through 239.255.255.255, although some class D addresses are permanently reserved for specific multicast groups and others can be assigned as desired. MADCAP dynamically assigns available class D addresses to clients who need to temporarily join a multicast group in order to receive a multicast transmission. The DHCP clients must also support MADCAP in order to request and receive multicast addresses from the MADCAP service (client machines running Windows 2000 and Windows .NET Server also support MADCAP).

MADCAP operates separately from DHCP, and a client that has an IP address from a DHCP server (or has a static IP address that has been manually assigned to it) can request from the MADCAP service an additional multicast address so that it can receive a multicast transmission over the network. A client can lease only one unicast address, but it can request and obtain multiple multicast addresses and belong to multiple multicast groups simultaneously.

Notes

If a client does not support MADCAP, it cannot request addresses from the MADCAP service, but it might be able run multicast-enabled applications such as Windows Media Player to receive multicast transmissions over a network.

MADCAP was formerly known as the Multicast Dynamic Host Configuration Protocol (MDHCP).

See Also: *Dynamic Host Configuration Protocol (DHCP), multicasting, unicasting*

Multicast Dynamic Host Configuration Protocol (MDHCP)

The former name for what is now called Multicast Address Dynamic Client Allocation Protocol (MADCAP).

See: *Multicast Address Dynamic Client Allocation Protocol (MADCAP)*

multicasting

Also called IP multicasting, a method for sending one Internet Protocol (IP) packet simultaneously to multiple hosts.

Overview

Most communications between two hosts on an IP network are performed using one of two methods:

- **Unicasting:** One host transmits a packet directly to another host on the network. Unicasting is the main method for transmitting data from one host to another over an IP network. Unicasting is essentially a point-to-point form of communication—unless network interfaces are operating in promiscuous mode for troubleshooting purposes, a unicast packet is received only by the host it is specifically addressed to.
- **Broadcasting:** One host transmits a packet to all other hosts on the network. Broadcasting is used primarily for service announcements and for address registration and resolution and is not generally used for host-host communications. Broadcast packets are sent to a special broadcast address that informs every host on the network to receive and process the packet.

Unfortunately, neither of these two IP transport methods is suited to a rapidly growing segment of Internet traffic—multimedia presentations and videoconferencing. For example, consider one host transmitting an audio or video stream and 10 hosts that want to receive this stream. If unicasting were used, the sending host would need to transmit 10 separate IP packets, one for each receiving host. As the number of receiving hosts scales upward, this scenario rapidly results in saturation of network bandwidth. On the other hand, if broadcasting were used by the sending host, then only one IP packet (a broadcast packet) would need to be transmitted, not just the 10 hosts but all hosts on the network would receive and process the packet. The result is that network hosts would incur unnecessary processing, which is clearly also an undesirable situation.

The solution to this is multicasting—the sending host transmits a single IP packet with a specific multicast address, and the 10 hosts simply need to be configured to listen for packets targeted to that address to receive the transmission. Multicasting is thus a point-to-multipoint IP communication mechanism that operates in a connectionless mode—hosts receive multicast transmissions by “tuning in” to them, a process similar to tuning in to a radio station. Multicasting is supported by Ethernet, Token Ring, Fiber Distributed Data Interface (FDDI), and Asynchronous Transfer Mode (ATM) networking architectures.

Architecture

IP multicast addresses (also known as group addresses) are IP addresses belonging to class D, and therefore fall within the range 224.0.0.0 through 239.255.255.255. IP multicast addresses thus have their four high-order bits set to 1110 when viewed in binary notation. In Classless Inter-Domain Routing (CIDR) notation, the block of IP multicast addresses is expressed as 224.0.0.0/4.

Multicast addresses come in two types:

- **Permanent:** Addresses that are reserved for special uses, such as host and router announcements. A multicast group based on one of these addresses can have any number of hosts within it, including zero hosts. In other words, when the last host leaves a permanent multicast group, the group continues to exist even though it has no members. Permanent addresses are defined either in Requests for Comment (RFCs) defining IP multicasting standards, such as RFC 1112, or they can be reserved by the Internet Assigned Numbers Authority (IANA) for specific uses. Examples of such uses include topology and gateway discovery for multicast routing protocols, and group membership registration and reporting. The following table shows some common reserved multicast addresses and their uses. All multicast addresses within the range 224.0.0.0 through 224.0.0.255 are reserved for special use, although some of these addresses have not had their uses specifically assigned yet. Addresses within this range are reserved for local subnet use only and are not forwarded to other subnets by routers, regardless of the time-to-live (TTL) in the packet headers. Addresses that fall within the range 239.0.0.0 through 239.255.255.255 are similarly reserved. Some addresses in the 224.0.1.0 through 224.0.1.255 are also reserved, and, unlike other permanent addresses, these can be forwarded by routers. Additional addresses are also reserved for vendor-specific and service provider-specific multicast transmissions.

Examples of Reserved IP Multicast Addresses

Address	*Description*
224.0.0.0	Base address (not used)
224.0.0.1	All hosts on the local subnet
224.0.0.2	All routers on the local subnet
224.0.0.5	All Open Shortest Path First (OSPF) version 2 routers on the network
224.0.0.6	Designated Open Shortest Path First (OSPF) version 2 routers on the network
224.0.0.9	Routing Information Protocol (RIP) version 2 group address
224.0.0.18	Internet Group Management Protocol (IGMP) group address
224.0.1.1	Network Time Protocol (NTP)
224.0.1.24	WINS server group address
224.0.1.75	Session Initiation Protocol (SIP) group address
224.0.12.0 to 224.0.12.63	Used by MSNBC
224.0.18.0 to 224.0.18.255	Used by Dow Jones

- **Transient:** Addresses that are used to define multicast groups formed for specific multicast transmissions such as a videoconferencing session. Each transient address specifies a multicast group, and once the last host has left this group, the group ceases to exist and the address is released for other uses. Addresses for transient multicast groups are chosen from the range 224.0.1.0 through 238.255.255.255, as all other class D addresses are reserved as described previously.

IP hosts can support multicasts at one of three levels:

- **Level 0:** Cannot send or receive multicast traffic
- **Level 1:** Can send but not receive multicast traffic
- **Level 2:** Can send and receive multicast traffic

Microsoft Windows 2000 supports Level 2 multicast functionality for all forms of IP traffic.

Implementation

Membership in a multicast group is dynamic—hosts can join or leave a group as they choose. To join a multicast group, a host sends a message to the all hosts multicast group 224.0.0.1. This informs routers on the local subnet that the host wants to join a specific multicast group. Routers then periodically send queries to the same multicast group to ensure hosts are still interested in belonging to multicast groups. Hosts can belong to more than one multicast group simultaneously, and multicast groups can span multiple subnets.

When the host wants to leave a group, it sends a message to the All Routers multicast group 224.0.0.2. These messages between hosts and routers are sent using the Internet Group Management Protocol (IGMP).

Routers must be multicast-enabled to support multicasting. Multicast routers communicate using multicast routing protocols such as Multicast Open Shortest Path First (MOSPF) and Protocol Independent Multicast (PIM).

For More Information

Visit the IP Multicast Initiative at *www.ipmulticast.com.*

See Also: *broadcasting, Class D, classless interdomain routing (CIDR), Internet Group Management Protocol (IGMP), Internet Protocol (IP), IP address, multicast routing, multicast routing protocol, router, unicasting*

Multicast Open Shortest Path First (MOSPF)

A dense mode multicast routing protocol.

Overview

Multicast Open Shortest Path First (MOSPF) is a protocol that allows multicast-enabled routers to communicate with each other in order to build multicast forwarding tables. These tables contain trees of information specifying which subnets have hosts that belong to different multicast groups. This allows hosts belonging to a specific group to receive multicast transmissions directed toward that group.

MOSPF is designed to be used within a single routing domain or autonomous system (AS). Although it is classified as a dense mode multicast routing protocol, MOSPF does not work well for networks that have large numbers of active multicast groups due to the large amount of overhead involved in recalculating distribution trees when multicast groups are added or removed from the network. Performance is best for MOSPF when only a few multicast groups are active, and, as a result, MOSPF is not widely used for multicasting over the Internet.

MOSPF is based on the unicast Open Shortest Path First (OSPF) routing protocol and is defined in RFC 1584. Cisco routers do not support MOSPF.

See Also: *autonomous system (AS), multicasting, multicast routing, multicast routing protocol, Open Shortest Path First (OSPF)*

multicast routing

Routing of multicast packets across an internetwork from the sending host to the receiving group of hosts.

Overview

Ordinary routing is unicast routing—that is, the routing of unicast packets. Unicast routing involves forwarding Internet Protocol (IP) packets from the sending host to a specific, globally unique receiving host. Routing involves forwarding the packet across multiple subnets to its final destination, the number of subnets crossed being the number of hops required for the packet to reach its destination. From the point of view of unicasting, subnets are well-defined entities connected by routes.

Multicast routing is different: multicast packets are forwarded to multicast-enabled routers and these routers are responsible for ensuring that hosts belonging to the multicast group specified by the destination address receive the transmitted packet. Group members may be located in a single subnet or in many different subnets and may be concentrated either in a small portion of the larger internetwork or scattered all over the place. To ensure that multicast packets are not forwarded to subnets where no interested hosts reside and to ensure that they are forwarded from routers on noninterested subnets to other routers further downstream, multicast routing protocols are used to allow multicast-enabled routers to communicate with each other and exchange information.

Information about which subnets interested hosts reside on is maintained in multicast forwarding tables stored on multicast-enabled routers. An entry in this table indicates that there is at least one interested host (a host belonging to the multicast group to which the transmission is directed) in the subnet mapped to that entry. Multicast routing protocols generally store their multicast forwarding tables as hierarchical structures called multicast trees. A tree defines the distribution of multicast packets from the sending host to all receiving hosts within its multicast group. Mulitcast trees are created and maintained by processes known as grafting and pruning and can be either source trees which find the shortest path from the sending host to each potential receiving host, or shared trees which merge source trees into a single tree for each specific group. Multicast traffic is prevented from being sent to subnets where no interested hosts reside by a process known as scooping.

See Also: *multicasting, multicast routing protocol, routing, unicasting*

multicast routing protocol

Any protocol used for communication between multicast-enabled routers.

Overview

Multicasting on an Internet Protocol (IP) internetwork relies on special multicast-enabled routers. These routers enable hosts to register themselves for sending or receiving multicast transmissions. Multicast routers communicate with each other using multicast routing protocols in order to create multicast forwarding tables (multicast trees) that ensure that each host that joins a multicast group receives the transmission directed toward that group.

Types

There are two basic kinds of multicast routing protocols:

- **Dense mode:** Protocols used when large numbers of hosts grouped together in dense clusters need to receive multicast traffic. Dense mode protocols need a large amount of network bandwidth in order to operate because they periodically flood the network with multicast traffic. Examples of dense mode multicast routing protocols include
  - **Distance Vector Multicast Routing Protocol (DVMRP):** An early protocol based on Routing Information Protocol (RIP) and now rarely used. It is defined in RFC 1075.
  - **Multicast Open Shortest Path First (MOSPF):** A protocol based on the unicast Open Shortest Path First (OSPF) routing protocol. MOSPF is designed for use within a single autonomous system (AS) and is defined in RFC 1584.
  - **Protocol Independent Multicast-Dense Mode (PIM-DM):** Similar to DVMRP but uses a unicast routing protocol for building its multicast trees.
- **Sparse mode:** Protocols used when smaller numbers of hosts are widely scattered over the network. Sparse mode protocols utilize less bandwidth than dense mode ones, and they build multicast trees by joining branches to the main distribution tree. Examples of sparse mode multicast routing protocols include
  - **Protocol Independent Multicast-Sparse Mode (PIM-SM):** Similar to PIM-DM but optimized for sparse multicasting environments.
  - **Core-Based Trees (CBT):** Creates a single distribution tree for each multicast group. CBT is defined in RFC 2201.

See Also: *Core-Based Trees (CBT), Distance Vector Multicast Routing Protocol (DVMRP), multicasting, Multicast Open Shortest Path First (MOSPF), multicast routing, Protocol Independent Multicast-Dense Mode (PIM-DM), Protocol Independent Multicast-Sparse Mode (PIM-SM), routing protocol*

multihoming

The process of having more than one network interface on a device.

Overview

Networking devices that have more than one interface are called multihomed devices. A router is a good example of a multihomed device because it has several network interfaces, each usually connected to a different subnet.

Computers can also be multihomed by giving them multiple interfaces to a network. This is true even if the computer has only a single physical interface (network interface card, or NIC). For example, Microsoft Windows 2000 allows you to assign more than one Internet Protocol (IP) address to a single physical interface, resulting in multiple virtual interfaces and making the machine a multihomed host. When a computer is connected to both a local area network (LAN) using a NIC and the Internet using a dial-up connection, this can also be considered multihoming since the dial-up connection is also an interface (a wide area network [WAN] interface typically running Point-to-Point Protocol [PPP]), though the term multihoming is not always used in this scenario.

The most common way of multihoming a computer, however, is to install two or more physical interfaces (NICs) and assign separate IP addresses to each NIC. Windows 2000 supports all of these methods of multihoming. Note that the first method of using multiple virtual interfaces is sometimes called multinetting and is considered by some not to be true multihoming.

Uses

Multihoming has a number of possible uses:

- For turning a computer into a router. If you install multiple NICs in a Windows 2000 server computer, the machine can be used as a router on an IP internetwork. The Routing and Remote Access Service (RRAS) of Windows 2000 makes this scenario possible. If you enable Routing Information Protocol (RIP) on the computer, it can function as a dynamic router that can exchange routing table information with other RIP-enabled routers. Or if you do not enable RIP, the computer can function as a static router, in which case you would manually configure the server's routing table from the command prompt using the Route command.
- For increasing the bandwidth to critical servers by enabling them to connect to several networks simultaneously or to the same network using multiple interfaces having different IP address.
- For connecting Dynamic Host Configuration Protocol (DHCP) servers to several subnets simultaneously for dynamic IP address allocation to hosts.
- For connecting a privileged host to both a low-security LAN and a restricted high-security LAN.

Issues

Some issues can arise with multihomed hosts:

- **Multiple default gateways:** If you multihome a computer with two or more physical interfaces that are not aware of each other's presence and then assign different default gateway addresses to each interface, network communications problems can arise. To solve this, use only a single default gateway and assign the corresponding address to the interface carrying more traffic.
- **Remote access:** A typical remote access server has both a local area network (LAN) interface and a wide area network (WAN) interface. You should generally use static routing between these two interfaces to avoid routing problems.



Multihoming. *A multihomed server with two interfaces.*

Notes

The term *multihoming* is also used in a different sense in the modern enterprise: using several Internet Service Providers (ISPs) to connect your network to the Internet. A typical multihoming scenario would see two leased lines joining your network to the Internet. Each line is leased from a different ISP, and one line is used to bring IP traffic into your network while the other is used to carry traffic out of the network. The motive for this kind of multihoming is to ensure redundant connection for enterprise data centers to the high-speed backbone of the Internet through different points of presence (POPs) belonging to different carriers. This is desirable for companies that view the Internet as a mission-critical resource and cannot afford any downtime.

To implement Internet multihoming in this way generally requires high-end routers and an understanding of complex protocols, such as Border Gateway Protocol (BGP), that are used on the Internet's backbone. Often, the challenge in this scenario is to get the different ISPs to cooperate with one another to ensure your network does not have IP address space problems. This is because a multihomed network needs to have its own autonomous system number (ASN) assigned to it by an Internet registry such as the American Registry for Internet Numbers (ARIN). Many large ISPs usually will not agree to this kind of multihoming arrangement unless a minimum of a T3 connection is employed, which means that only large companies such as IBM, Hewlett-Packard Company, Amazon.com, and eBay can afford to implement this kind of multihoming. Nevertheless, the steady rise in the number of ASNs being allocated by ARIN over the last few years indicates the rise in popularity of Internet multihoming among large enterprises and e-business companies. A cheaper alternative to multihoming for enterprises that need redundancy is simply to lease several T1 or T3 lines from the same carrier and inverse multiplex them into a single connection.

See Also: *American Registry for Internet Numbers (ARIN), autonomous system number (ASN), Border Gateway Protocol (BGP), Dynamic Host Configuration Protocol (DHCP), interface, inverse multiplexing, network interface card (NIC), router*

Multilayer Switching (MLS)

A local area network (LAN) switching term that can have several meanings.

Overview

The term *Multilayer Switching (MLS)* can have several meanings within the context of LAN switching. Specifically, it can refer to

- The ability of a LAN switch to mimic the functions of a router. In other words, the term can be synonymous with Layer 3 switching.
- A switch that can operate at multiple layers of the Open Systems Interconnection (OSI) reference model. For example, a multilayer switch could bridge at Layer 2, route at Layer 3, and screen ports at Layer 4.
- A Cisco LAN switching architecture that allows switches and routers to work together within the high-speed core of an enterprise network. The MLS architecture is built using several components, including a Multilayer Switching Switch Engine (MLS-SE), Multilayer Switching Route Processor (MLS-RP), and Multilayer Switching Protocol (MLSP) from Cisco Systems.

See Also: *Ethernet switch, Layer 2 switch, Layer 3 switch, Layer 4 switch, Open Systems Interconnection (OSI) reference model, router*

Multilink Frame Relay (MFR)

A new frame relay aggregation technology.

Overview

Multilink Frame Relay (MFR) is a new standard from the Frame Relay Forum that allows multiple frame relay links to be aggregated using inverse multiplexing. The goal of MFR is to make frame relay an attractive technology in the market niche between T1 and T3 lines. Enterprises using multiplexed T1 lines that require more bandwidth often balk at the cost of upgrading to T3, which offers speeds of 45 megabits per second (Mbps) compared to T1's 1.5 Mbps. MFR is designed to provide a lower-cost option that can provide bandwidth intermediate between T1 and T3.

Implementation

MFR is implemented at the service provider end using MFR-enabled carrier-class frame relay switches and at the customer premises end using MFR-enabled Integrated Access Devices (IADs). Multilink Point-to-Point Protocol (MPPP) service providers include competitive local exchange carriers (CLECs), building local exchange carriers (BLECs), and large Internet service providers (ISPs). Service providers generally target midsize businesses and multitenant units (MTUs) for deploying MFR.

MFR is often used in conjunction with MPPP, a wide area network (WAN) protocol that allows scalable bandwidth allocation using dynamic bonding of multiple Point-to-Point Protocol (PPP) links. MPPP devices can aggregate up to 128 separate frame relay links into a single logical pipe, with individual links ranging from DS-0 to T1.

See Also: *Building-centric Local Exchange Carrier (BLEC), Competitive Local Exchange Carrier (CLEC), DS-0, frame relay, Integrated Access Device (IAD), Internet service provider (ISP), Multilink Point-to-Point Protocol (MPPP), multitenant unit (MTU), Point-to-Point Protocol (PPP), T-carrier*

Multilink Point-to-Point Protocol (MPPP)

A wide area network (WAN) protocol for aggregating multiple Point-to-Point Protocol (PPP) connections.

Overview

Multilink Point-to-Point Protocol (MPPP) can be used to bundle together multiple physical PPP links into a single logical link. This is accomplished by using inverse multiplexing on each end of the link, at both the customer premises, and at the service provider (for an MPPP connection to be established, both ends of the connection must support MPPP). MPPP's purpose is usually to provide greater bandwidth for a WAN connection than a single PPP link can provide, but since MPPP is a dynamic process, it can also be used to better utilize bandwidth and even load-balance between connections. The advantages of using MPPP on WAN links include increased bandwidth, dynamic bandwidth allocation, reduced latency, and fault tolerance. MPPP's main disadvantage is that it is difficult to support callback for remote access servers.

MPPP is an extension to the industry-standard PPP and is defined in RFC 1990. MPPP is supported by most access servers and routers and also by the Microsoft Windows 2000 operating system. Multilink Point-to-Point Protocol is variously abbreviated as MPPP, MP, or MLP, and is abbreviated occasionally (and wrongly) as MPP or even MLPPP. Sometimes it is simply called Multilink Protocol for short!

Uses

A popular use of MPPP is in Integrated Services Digital Network (ISDN) networking where it can be used to either bond (combine) the two 64-kilobits per second (Kbps) B channels of an ISDN-BRI interface into a single 128-Kbps logical channel or aggregate two or more BRI interfaces together for even greater throughput.



Multilink Point-to-Point Protocol (MPPP). *Using MPPP to bond two PPP links together.*

MPPP was the first industry-standard nonproprietary method for ISDN bonding, and as a result, it is popular where ISDN technologies are still used. Because MPPP is a dynamic protocol, it can also be used to dynamically bring online the second B channel whenever the bandwidth of a single channel is insufficient and then dynamically release the second channel when it is no longer required. This is done by configuring a traffic threshold above which the second channel will automatically be activated. MPPP is supported by most ISDN terminal adapters.

A newer use of MPPP is in ISDN Digital Subscriber Line (IDSL), a form of Digital Subscriber Line (DSL) technology based on ISDN signal coding. By installing an MPPP-enabled IDSL router at the customer premises and a similar router at the service provider's point of presence (POP), up to four 144 kilobits per second

(Kbps) IDSL links can be multiplexed into a single 576 Kbps link. MPPP IDSL is a technology pioneered by Netopia and is intended mainly for corporate WAN use and not for residential Internet access. Using MPPP IDSL eliminates the need for installing a costly Digital Subscriber Line Access Multiplexer (DSLAM) at the customer premises and is ideal for environments such as remote telco terminals that are too limited in size to house DSLAMs.

Implementation

MPPP can be implemented over a variety of interfaces, including asynchronous dial-up modem connections, Integrated Services Digital Network (ISDN), and even synchronous connections. MPPP is negotiated during the Link Control Protocol (LCP) portion of a PPP authentication session.

MPPP defines procedures for splitting a PPP data stream into packets, sequencing the packets into time slots, transmitting them over a logical data link, and reassembling them at the receiving station. MPPP works by inverse multiplexing data frames from multiple client PPP connections into a single PPP link, and then demultiplexing the link to recreate the individual connections at the service provider's router.

MPPP supports two kinds of PPP authentication: Challenge Handshake Authentication Protocol (CHAP) and Password Authentication Protocol (PAP).

Notes

A proprietary extension to MPPP supported by some vendors is called Multichassis Multilink Point-to-Point Protocol (MMP), which allows MPPP connections to be aggregated across multiple routers and network access servers (NASs) in a way that is transparent to the dial-up MPPP client. In other words, the client initiates an MPPP session but is actually connected to several MMP-enabled NASs at the ISP instead of only one NAS, as in the usual scenario. MMP enables the data stream to be split, sequenced, and recombined at several different points to provide a single logical connection between the client and the ISP.

Another proprietary extension to MPPP is called Multichannel PPP (MPP), which in addition to inverse multiplexing of PPP links also supports session and bandwidth management functions, including the dynamic addition or removal of channels without the need to reinitialize the link. Both the client and the server must support MPP for this to work.

See Also: *Challenge Handshake Authentication Protocol (CHAP), Digital Subscriber Line (DSL), Digital Subscriber Line Access Multiplexer (DSLAM), Integrated Services Digital Network (ISDN), inverse multiplexing, ISDN Digital Subscriber Line (IDSL), ISDN fallback adapter, Link Control Protocol (LCP), Password Authentication Protocol (PAP), Point-to-Point Protocol (PPP), wide area network (WAN)*

multimaster replication

Replication between peers.

Overview

Replication is an important aspect of many kinds of network services. For example, in network directory services, replication ensures that each directory server has an up-to-date version of directory information for the network. Replication between directory servers can take place in two ways: master/slave and multimaster replication.

In master/slave replication, the master server maintains the master copy of directory information and replicates this information with slave servers through periodic updates. Directory information can usually only be modified directly on the master server—slave servers usually have read-only versions of directory information. Master/slave replication is reliable but scales poorly and has a single point of failure—should the master server go down, the directory cannot be updated unless a slave server is promoted to the role of master. Master/slave replication is used by the Windows NT Directory Services (NTDS) of the Microsoft Windows NT 4.0 operating system, where master servers are called primary domain controllers (PDCs) and slaves are backup domain controllers (BDCs). In Windows NT, directory information is stored on domain controllers in the Security Account Manager (SAM) database, and although the PDC for each domain has a writable copy of the SAM database, the BDCs for that domain have read-only copies of the database.

In multimaster replication, however, there is no master directory server—all directory servers are peers of one another. Multimaster replication scales well and has no single point of failure, but it must be implemented properly using time stamping of updates and time synchronization between servers to ensure that replication occurs properly if collisions are to be avoided. A collision occurs when an object in Active Directory directory service has the same attribute modified almost simultaneously on two different domain controllers, and collisions are resolved using timestamps as a tie-breaking mechanism. Active Directory in Microsoft Windows 2000 uses multimaster replication to replicate directory information between all domain controllers in a domain. Multimaster replication, in fact, means that all domain controllers are "master" domain controllers—in other words, applications and users having sufficient privileges can update directory information on these servers directly.

The advantages of the multimaster replication method supported by Windows 2000 over the PDC/BDC master/slave replication method of Windows NT include the following:

- You can make updates to Active Directory as long as any domain controller is functioning on the network.
- When domain controllers are distributed at all sites, you can make updates to Active Directory anywhere on the network with a local domain controller, even when wide area network (WAN) links to other sites are down.

See Also: *Active Directory, directory*

multimode fiber-optic cabling

A type of fiber-optic cabling that can carry multiple signals simultaneously.

Overview

Multimode fiber-optic cabling allows large amounts of information to be transmitted over a single strand of fiber. This is accomplished by transmitting multiple light signals simultaneously through specially constructed fiber. This enables multimode fiber to sustain a much greater bandwidth than single-mode fiber, a type of fiber that supports only one light signal at a time.

The disadvantage of multimode cabling is that multimode transmission is more complex and incurs greater risk of signal loss. As a result, multimode fiber runs cannot be as long as single-mode fiber, which can carry signals for several kilometers without degradation. So although multimode fiber can carry many times more bandwidth than single-mode fiber, single-mode fiber can generally carry signals up to 50 times farther than multimode.

Implementation

Multimode fiber is fiber-optic cabling that has a glass core whose index of refraction varies in a specific fashion with the distance from the core axis. This variation in index of refraction is done to ensure that multiple separate light signals can be effectively transported down the fiber without interference or signal loss. The variation is implemented in one of two ways:

- **Step-index:** Here light rays reflect off the inner surface of the core by a mechanism called total internal reflection. By varying the angle at which the rays are incident on the inner surface of the core, different light paths can be transmitted down the fiber to carry additional light signals, thus increasing the bandwidth capacity of the fiber. In long step-index fiber runs, however, these light paths can get out of step with each other at the far end of the fiber and thus degrade overall signal quality. Step-index fiber is cheaper than graded-index fiber and should be used only for shorter cable runs or where less bandwidth is required.
- **Graded-index:** Here the core consists of concentric layers of homogeneous material, each successive layer having a lower index of refraction than the layer that it envelops. In this type of fiber, the rays of light travel along curved paths and all arrive in step with each other at the far end of the fiber, which means that graded-index fiber runs can be longer than step-index ones.



Multimode fiber-optic cabling. *How light travels along two kinds of multimode fiber.*

Multimode fiber is available with different core diameters, typically 50, 62.5, and 100 microns. Line drivers transmitting signals through multimode cables generally use light-emitting diodes (LEDs) to generate their signals.

Uses

Because of the length restrictions for multimode fiber, this type of cabling is generally restricted in use to small cable runs such as switch-switch and switch-server links and backbone connections within buildings (intrabuilding connections). Single-mode fiber is necessary for long cable runs such as inter-building connections and distributed campus backbones.

Multimode cable lengths are restricted to various distances depending on the networking technology used. For example, in Gigabit Ethernet (GbE), multimode fiber of the 50 and 62.5 micron size are supported (62.5 is preferred) with maximum cable run lengths supported being 1800 feet (550 meters). If this limit is exceeded, the light traveling along different paths through the fiber can produce a condition called modal dispersion, which results in parts of the signal arriving at unexpected times at the end station. This condition can quickly degrade the signal's quality, causing it to be unrecognizable so that communication is impossible. Note that older forms of Ethernet such as 10BaseT and Fast Ethernet support multimode links up to 6600 feet (2000 meters) in length due to their slower signaling speed.

See Also: *cabling, Ethernet, Fast Ethernet, fiber-optic cabling, Gigabit Ethernet (GbE), single-mode fiber-optic cabling*

multiple master domain model

A strategy for deploying large networks based on Microsoft Windows NT.

Overview

The multiple master domain model represents a Windows NT domain model in which all user and group accounts for the enterprise reside in two or more account domains that trust one another using two-way trusts. Network resources for the enterprise reside in separate resource domains, and each resource domain trusts every account domain in the enterprise. The goal of this structure is to ensure that users anywhere in the enterprise can access network resources anywhere in the enterprise provided they have suitable permissions.



Multiple master domain model. *Using the multiple master domain model to deploy Windows NT for a large enterprise.*

Large enterprises may use the multiple master domain model either because of limitations on the recommended number of users in a Windows NT domain (about 20,000) or because their company is spread across several geographically separate locations.

Advantages and Disadvantages

The advantages of the multiple master domain model are that it is scalable to any number of user accounts and that resource domains in this model manage their own resources. Among the disadvantages are the fact that the master domain model is complex to set up and administer and that multiple local groups must be created in each resource domain.

Notes

Enterprises can simplify network administration considerably by upgrading their large Windows NT–based networks to Windows 2000. Windows 2000 overcomes the limitations of Windows NT's multiple master domain model by supporting the storage of up to 10 million objects in Active Directory directory service and by allowing a single domain to be partitioned into multiple sites with intersite directory replication traffic being scheduled for times of low wide area network (WAN) usage. As a result, it is often the best approach and a relatively straightforward process to consolidate a large Windows NT–based network having multiple master domains and resource domains into a single large Windows 2000 domain having multiple sites. In this approach you can mirror the administrative structure of your former network by creating a hierarchy of organizational units (OUs) within Active Directory and assigning suitable permissions for these OUs to users and groups.

If you want to maintain the existing administrative structure of your company more closely, however, you can take a different approach in your migration. You can migrate each Windows NT master or resource domain to a distinct Windows 2000 domain. Here each master domain would become the root of a domain tree, and the resource domains that trusted them become child domains joined by two-way transitive trusts to their parent domain. This results in one new domain tree for each former master domain. You then establish two-way transitive trusts between the root domains of each tree, forming a domain forest. All users in your enterprise thus gain access to resources anywhere on the network.

See Also: *Active Directory, complete trust model, master domain, organizational unit (OU), single domain model*

Multiple Virtual Storage (MVS)

A legacy IBM mainframe operating system.

Overview

Multiple Virtual Storage (MVS) was originally developed for the System/360 series of IBM mainframes. The name comes from the fact that MVS uses virtual memory (storage) for sharing memory among multiple applications.

MVS is still used on many legacy mainframes found in government, finance, and industry for running accounting and payroll systems, large databases, and other legacy applications. MVS is mainly used to run applications written in COBOL, but it supports other languages, including FORTRAN, PL/1, and CICS.

MVS has been supplanted by the OS/390 operating system, which runs on IBM's System/390 mainframe models.

See Also: *mainframe*

multiplexer (MUX)

A device that combines multiple data streams into a single stream.

Overview

Multiplexers (MUXes) are used in wide area networks (WANs) to make optimum use of available bandwidth in leased lines. A multiplexer allows data streams from several pieces of data terminal equipment (DTE) to be multiplexed (combined) into a single stream that can be transmitted over the leased line. In addition, multiplexers allow leased lines to carry voice, video, and data traffic simultaneously.

An inverse multiplexer, or IMUX, takes a single input data channel from a DTE, such as a router, and spreads it to several digital transmission lines. A demultiplexer is simply a MUX at the remote end of a multiplexed communication system. A modular MUX allows you to expand your wide area network (WAN) link as your network grows by adding modules to provide additional V.35, RS-232, or RS-530 input ports.

Implementation

Multiplexers can save companies costs by eliminating the need for extra line termination devices such as Channel Service Unit/Data Service Units (CSU/DSUs). For example, a T1 MUX typically has several V.35 interfaces that can accept incoming data from switches or routers connected to your local area networks (LANs), plus a DSX-1 interface for connecting to a channel bank or private branch exchange (PBX) system. The MUX takes this serial data input and voice input and multiplexes them together into a single data stream using an integrated CSU/DSU and then transmits this stream over the T1 line, letting you use your

T1 line for voice and data combined. You can use a similar device to multiplex data and voice for transmission over a public frame relay carrier network.



Multiplexer (MUX). *Examples of using a T1 multiplexer and a fiber-optic MUX.*

These T1 MUXes often offer advanced management functions. For example, a T1 MUX can usually be remotely managed using the Simple Network Management Protocol (SNMP), and it can be configured to send a trap to an SNMP management console whenever a problem occurs with the MUX. Some MUXes are also used in mainframe environments for connecting remote terminals to async hosts without the need for individual cabling to each terminal. These kinds of MUXes are generally used in pairs and utilize time-division multiplexing (TDM). Examples include the following:

- Fiber-optic MUXes for combining several sync or async data channels onto one duplex fiber-optic cable. A typical fiber-optic MUX might have 12 or 24 RS-232 input ports and support speeds in excess of 115.2 kilobits per second (Kbps) per channel. These MUXes are typically used in pairs to connect remote terminals to an async mainframe host across a campus environment and are often referred to as short-haul or local MUXes.
- Twisted-pair MUXes for multiplexing several RS-232 serial channels over installed RJ-11 wiring to save costs.
- Coax MUXes for connecting several 3270 terminals to an IBM controller in order to reduce the costs of cabling.

Another type of multiplexer is the Ethernet MUX, which can multiplex signals from several ports from an Ethernet switch and transmit the multiplexed signal over a single fiber-optic cable at distances up to 1.25 miles (2 kilometers). Ethernet MUXes are also typically used in pairs.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), data terminal equipment (DTE), inverse multiplexing, multiplexing, Simple Network Management Protocol (SNMP), T1, T-carrier*

multiplexing

Combining multiple data streams into a single stream.

Overview

Multiplexing is used in networking and telecommunications to aggregate data streams from different sources into a single channel, typically for transmission over a wide area network (WAN) connection. For example, signals from several data terminal equipment (DTE) can be combined into a single signal using a multiplexer and transmitted over a leased line such as a T1 line. For information to be transmitted successfully, the leased line must have a bandwidth equal to or greater than the combined bandwidth of the signals from the various DTE.

Implementation

Several methods of multiplexing signals are commonly used in telecommunications and networking. Each method is suited to a specific form of communication. Some more common methods used include

- **Frequency-division multiplexing (FDM):** This method is used to multiplex analog signals. In this scenario, the total bandwidth of the carrier signal is subdivided into a series of channels having different frequencies.
- **Time-division multiplexing (TDM):** This is a common method for multiplexing digital signals used, for example, in T1 lines. Data from different bitstreams are placed in alternating fashion in different time slots in the carrier signal. One time slot is assigned to each incoming stream of data. The problem with this method is that if one source of data has nothing to transmit, the time slot for that source will not be used and the associated bandwidth will be wasted. TDM is suitable mainly for applications that transmit data in real time, such as voice, video, or multimedia transmissions. This is because TDM has predictable latency and can thus provide guaranteed levels of Quality of Service (QoS) for transmissions.
- **Statistical multiplexing (SM):** Also called statistical packet multiplexing (SPM) or statistical time division multiplexing (STDM), this method is similar to TDM but can reassign time slots to different sources when they are not needed. Statistical multiplexing thus makes better use of available bandwidth than TDM and is useful mainly for transmissions that have unpredictable latency, such as Internet Protocol (IP) transmissions. Statistical multiplexing is used in WAN technologies such as frame relay and Asynchronous Transfer Mode (ATM).
- **Dense wavelength division multiplexing (DWDM):** A multiplexing technology used in high-speed fiber-optic backbone networks. DWDM sends multiple bitstreams through a single strand of fiber using a different color (wavelength) of laser light for each stream. DWDM is emerging as the technology of choice for telcos and other carriers who need to enhance the carrying capacity of their trunk lines and backbone networks.



Multiplexing. *How multiplexing combines multiple physical data links into a single logical connection.*

See Also: *Asynchronous Transfer Mode (ATM), dense wavelength division multiplexing (DWDM), frame relay, frequency-division multiplexing (FDM), inverse multiplexing, leased line, multiplexer (MUX), statistical multiplexing (STM), time-division multiplexing (TDM)*

multipoint

Short for point-to-multipoint, communication from a single sending station to multiple receiving stations.

See: *point-to-multipoint*

Multipoint Multichannel Distribution Service (MMDS)

A fixed wireless broadband networking architecture.

Overview

Also known as fixed wireless, Multipoint Multichannel Distribution Service (MMDS) is a new broadband wireless service designed to compete with Digital Subscriber Line (DSL) and cable modem technologies. It can be used to provide enterprise with high-speed wireless wide area network (WAN) connections and for high-speed Internet access.

MMDS is a serious contender in the enterprise WAN arena and is a low-cost alternative to expensive leased lines such as T1 and fractional T1 lines. MMDS is generally considered superior to DSL and cable modem technologies for enterprise use for several reasons:

- It can be provisioned in a matter of days, compared to the weeks or months it can take to set up a DSL connection (or even frame relay, for that matter).
- It is stable and reliable compared to DSL and cable modem technologies, which have yet to provide the required 99.999 percent uptime needed by today's wired enterprise. Despite the dirt-cheap cost of DSL compared to costly leased lines and despite DSL's ability to provide more bandwidth than leased lines, most enterprises have stayed away from using DSL in their WAN links and for Internet access because of the reliability issues still associated with it.
- It can be provisioned without the need to install additional wiring, which is a costly expenditure in older buildings.

Implementation

MMDS operates in the 2.1, 2.5, and 2.7 gigahertz (GHz) portions of the electromagnetic spectrum. Typical speeds for MMDS are 384 kilobits per second (Kbps) to 1 megabit per second (Mbps) for downstream transmission and 384 Kbps to 512 Kbps upstream.

In a typical MMDS scenario, a base station with antenna is set up at a high location (building rooftop or hill) in or near an urban area. The base station provides coverage for customer sites within a 22-mile (35-kilometer) radius. Customer sites must have a clear line of sight with the base station's antenna in order for MMDS to work properly.

Marketplace

Currently, the two major players in the MMDS arena are Sprint Corporation and MCI/Worldcom, two interexchange carriers (IXCs). MMDS is being rolled out by these companies in major urban areas around the United States. A major producer of MMDS equipment is Vyyo Wireless Systems.

Prospects

The main issue with MMDS is the clear line of sight (LoS) requirement for transmission. One way of working around this is to implement orthogonal frequency division multiplexing (OFDM) on MMDS, which helps overcome the LoS, reach, and antenna size issues relating to MMDS.

See Also: *broadband Internet access, cable modem, Digital Subscriber Line (DSL), frame relay, Orthogonal Frequency Division Multiplexing (OFDM), T-carrier, wide area network (WAN), wireless networking*

multiport repeater

An older name for a hub, a device used to connect shared Ethernet segments into a single LAN.

See: *hub*

Multiprotocol Label Switching (MPLS)

A protocol for efficiently routing traffic across a large Internet Protocol (IP) network such as the Internet.

Overview

Multiprotocol Label Switching (MPLS) is an emerging standard from the Internet Engineering Task Force (IETF) designed for implementation on high-speed backbone routers in large IP networks such as the Internet. MPLS is an outgrowth of several proprietary vendor-based solutions to the problem of routing traffic through high-speed switched backbones. The most prominent of these proprietary solutions is the tag switching technology developed by Cisco Systems, from which much of MPLS was derived. Other companies whose technologies have contributed to the development of MPLS include Ipsilon Networks (now part of Nokia), Cascade Communications, 3Com Corporation, IBM, and Cabletron Systems.

MPLS is designed to bring some of the advantages of circuit-switched networks to switched IP networks. These advantages include predictable delay and latency, the ability to reserve bandwidth, and different levels of Quality of Service (QoS).

Implementation

The name MPLS defines two aspects of this protocol:

- **Multiprotocol (MP):** MPLS can work with any network transport. Although it is intended mainly for IP, it can work with Asynchronous Transfer Mode (ATM), IP over ATM, frame relay, and other transports.
- **Label Switching (LS):** MPLS works by attaching labels to packets, uniquely identifying the data flow or path that packet takes across a routed network such as the Internet.

An MPLS label is simply a four-octet binary number. The first 20 bits of the label uniquely identify the Forwarding Equivalence Class (FEC) to which the packet belongs, while the remaining bits specify the time to live of the packet and other information. Each data flow through the internetwork is mapped to an FEC—in other words, all packets belonging to the same FEC are handled similarly by MPLS-enabled routers. Multiple labels can be attached to each packet, which enables MPLS to support features such as tunneling and even stacked tunnels. A sequence of labels or a label stack is called a Label-Switched Path (LSP).

MPLS-enabled routers are called Label Switching Routers (LSRs), and for MPLS to work properly it must be supported by routers all across the internetwork. LSRs forward packets by examining their LSP and switching them accordingly, a process that can be much faster than traditional IP routing. Packets are introduced into an MPLS domain using a Label Edge Router (LER) connected to both the local network and the backbone network. Once the packet is on the backbone, it is label-switched to the LER adjacent to the destination network, at which point it is routed using traditional IP routing to its final destination. LSRs communicate with each other using the Label Distribution Protocol (LDP) to let each other know what labels they are assigning to different traffic flows.

Uses

Because MPLS is a complex protocol, it is unlikely to be used extensively in the enterprise. Instead, service providers and telcos are likely to deploy MPLS on their ATM backbones to increase the efficiency with which they carry IP traffic. MPLS offers an alternative to permanent virtual circuits (PVCs) commonly used in telco ATM networks. Using MPLS, ATM switches become routers that can dynamically switch traffic to their destination, taking the advantage of multiple redundant nondedicated paths to their destination.

When service providers offer customers MPLS on their WAN links, a number of features can be implemented at the IP level by the customer instead of having to implement them at the ATM level by the carrier. These features include the ability to perform traffic engineering, support for multiple independent private data streams over a single WAN connection, implementing bandwidth reservation and Quality of Service (QoS), and more.

An example of MPLS deployment at the telco level is AT&T, which has deployed MPLS running on Cisco switches on its frame relay backbone network for more efficient transport of IP traffic over that network. MPLS is used to define different Classes of Services (CoS) and supports virtual private networking (VPN). Another example of how MPLS can be used is demonstrated by CoSine, which combines MPLS with Internet Protocol Security (IPsec) for secure tunneling and virtual routing.

MPLS is also expected to find application in pure optical backbone networks, an emerging technology driven mainly by the demand for greater capacity for Internet backbone traffic.

See Also: *Asynchronous Transfer Mode (ATM), frame relay, Internet Protocol (IP), quality of service (QoS), routing*

Multiprotocol over ATM (MPOA)

A method for forwarding Internet Protocol (IP) packets over Asynchronous Transfer Mode (ATM).

Overview

Multiprotocol over ATM (MPOA) defines a standard for forwarding Layer 3 packets (such as IP packets) over ATM backbones. MPOA is intended to support any Layer 3 network transport, but IP is the main transport used with MPOA due to its ubiquitous use in the enterprise and on the Internet. The MPOA standard is being guided by the ATM Forum.

MPOA can be used to establish connections between different IP subnets using an ATM backbone. This contracts with LAN Emulation (LANE), another IP over ATM technology (and a technology from which MPOA was derived), which is used mainly to support IP communications within a subnet. Neither MPOA nor LANE are suitable for transmission of IP traffic over wide area network (WAN) connections, however, due to the large number of ATM virtual circuits (VCs) required—nine for each pair of hosts communicating using MPOA. MPOA can also be used to connect virtual LANs (VLANs) in a switched backbone network.

Architecture

The MPOA architecture involves MPOA Servers (MPSs), also called route servers, which operate as virtual routers to switch IP packets across the ATM network. Each subnet requires one or more route servers, and IP traffic is bridged from the sending host to a route server, switched across one or more additional route servers, and then bridged directly to its destination. These route servers have intelligence that enables them to track the overall topology of the ATM network and enable IP traffic to be switched across shortcut paths between end nodes on the network. The result is low latency and delay and greater Quality of Service (QoS) for IP traffic. This architecture enables MPOA to provide the "route once, switch many" functionality needed in the core switching backbone of today's high-speed networks.

See Also: *Asynchronous Transfer Mode (ATM), Internet Protocol (IP), quality of service (QoS), routing, virtual circuit, virtual LAN (VLAN)*

Multipurpose Internet Mail Extensions (MIME)

Extensions to Simple Mail Transport Protocol (SMTP) that allow multipart and binary messages to be sent using e-mail.

Overview

SMTP, the popular e-mail system used on the Internet, is defined in RFC 822 as a mechanism for forwarding simple text-based messages between hosts. An SMTP message consists of a single text file encoded in 7-bit ASCII format with headers attached. SMTP uses these headers to determine how the message is forwarded by SMTP hosts along the route to its destination.

Early on, two limitations of SMTP became apparent to users of the system:

- SMTP could only be used to send text messages, and some mechanism was needed to support sending other types of files, including word-processing documents, images, video clips, and other binary information.
- An SMTP message body could only have one part—it would be nice if multiple files could be embedded in, or attached to, a single message body.

Multipurpose Internet Mail Extensions (MIME) were developed to address these two concerns. MIME does not replace SMTP but simply extends it to include support for multipart message bodies and non-ASCII message content. MIME is defined in RFC 1521, and various MIME types are defined in later RFCs.

Implementation

MIME adds two additional types of headers for SMTP messages. These headers are

- **Content-Type:** Specifies the various kinds of content carried by SMTP messages
- **Content-Transfer-Encoding:** Specifies the various methods by which SMTP message content is encoded

RFC 1521 defines seven basic message content types that can be specified in the Content-Type header of SMTP messages. Each content type can have several subtypes to further specify the type of information carried by SMTP messages. Although RFC 1521 defined some of these subtypes, succeeding RFCs have defined many more subtypes. The main MIME content types are

- **Text:** Subtypes include plain, richtext, html, and other
- **Application:** Subtypes include octet-stream (8-bit chunks of binary data), Postscript (for Postscript printing), msword (for Microsoft Word documents), and almost a hundred others
- **Image:** Subtypes include gif, jpeg, tiff, and others
- **Audio:** Subtypes include basic and others
- **Video:** Subtypes include mpeg, quicktime, and others
- **Message:** Subtypes include rfc822 (a standard RFC 822 SMTP text message), http (for Hypertext Transfer Protocol [HTTP] traffic), and others
- **Multipart:** Subtypes include mixed (each part of the message body can have a different content type), alternative, parallel, digest, encrypted, and others

RFC 1521 also defines six basic data encoding methods that can be specified in the Content-Transfer-Encoding headers of SMTP messages. These are 7bit (ASCII text with line lengths less than 1000 characters), 8bit, binary, quoted-printable, base64 (Uuencoded data), and x-token. Later RFCs have defined other MIME encoding methods.

See Also: *e-mail, Simple Mail Transfer Protocol (SMTP)*

multiservice switch

A switch that can route packets and switch cells.

Overview

Multilevel switches are generally high-end switches that can support both Asynchronous Transfer Mode (ATM) circuit-switching and frame relay packet switching in a single chassis. Multilevel switches have been responsible in part for a rising interest in ATM backboning as a result of evolution in frame relay technologies such as Multilink Frame Relay (MFR).



Multiservice switch. *A wide area network (WAN) built using multiservice switches.*

In a typical wide area network (WAN) scenario, frame relay might be used at the edge of corporate local area networks (LANs) at the ingress and egress points, connecting the LANs using carrier ATM services as the internetwork backbone technology.

Multiservice switches conform to two frame relay specifications:

- **FRF.5:** Frame Relay Permanent Virtual Circuit to ATM
- **FRF.8:** Frame Relay Permanent Virtual Circuit to ATM Service Internetworking

See Also: *Asynchronous Transfer Mode (ATM), circuit-switched services, frame relay, Multilink Frame Relay (MFR), packet switching*

Multistation Access Unit (MAU or MSAU)

A wiring concentrator (passive hub) used in Token Ring networks.

Overview

Multistation Access Units (MAUs) are the core wiring components for building Token Ring networks. MAUs direct traffic from one station to the next around the ring of a Token Ring network. While the logical topology (electrical path) of a Token Ring network is a ring, the physical topology (wiring) is actually a star topology with the MAU at the center and the stations connected in a star pattern to the MAU. The MAU thus concentrates the wiring and contains circuitry that makes the logical star network operate as a physical ring.

Implementation

A typical MAU is a stand-alone device or a rack-mounted device that provides 8 or 16 ports for connecting stations to the ring. The MAU also generally includes two additional ports: a ring-out connector and a ring-in connector. These ports are used to connect MAUs together to form larger Token Ring networks. For example, a larger network can be constructed by joining several MAUs to form a larger ring by connecting the ring-out connector of one MAU to the ring-in connector of another and continuing to connect until the ring-out of the last MAU in a series is connected to the ring-in of the first to complete the loop. Using this method, you can connect up to 33 MAUs into a large Token Ring network. Some MAUs include ring-in/out connectors for both copper cabling (RJ-45 connectors) and fiber-optic cabling (typically ST connectors).

When interconnecting MAUs to form large Token Ring networks, use MAUs that have automatic loopback functions on their ring-in/out ports. If a break in the ring should then occur between two MAUs, the break is automatically detected and traffic is rerouted along a preconfigured backup path.

MAUs often support both 4 megabits per second (Mbps) and 16 Mbps Token Ring signaling. Note, however, that a common way to bring down a Token Ring network is to connect a Token Ring station that has the wrong speed for the given network—for example, connecting a 4-Mbps station to a 16-Mbps network. This speed mismatch causes beaconing that brings down the network. A smart MAU can detect a mismatched station and lock out the station before a problem can occur.



Multistation Access Unit (MAU). *Connecting several MAUs together to create a large Token Ring network.*

MAU connections typically use either proprietary IBM universal data connectors for IBM Type 3 cabling (Type 1 Token Ring) or RJ-45 lobe connectors for 100-ohm shielded twisted-pair (STP) cabling (Type 3 Token Ring). MAUs also usually include circuitry that provides fault tolerance so that if a station fails or is disconnected from the MAU Token Ring, traffic can still continue unaffected around the ring. If you need to locate Token Ring stations at distances greater than 328 feet (100 meters) from a MAU, you can use stand-alone repeaters or a powered (active) MAU that has built-in repeaters to support greater lobe distances.

Other types of MAUs include

- **Modular MAU:** Lets you add different connector or repeater modules for greater flexibility of network design
- **Stackable MAU:** Lets you easily create large Token Ring networks with up to 256 stations

- **Manageable MAU:** Includes modules that support Simple Network Management Protocol (SNMP) management through in-band or out-of-band connections
- **Active MAU:** Regenerates signals at each port in order to reduce jitter and extend signaling distances beyond recommended specifications

Notes

The acronym *MAU* also stands for Medium Access Unit or Media Attachment Unit, a term that refers to the circuitry in an Ethernet hub, Ethernet switch, or Ethernet network interface card (NIC) that enables the correct form of electrical or optical connection to be established with the particular type of media being used. This type of MAU, also known as a transceiver, detects the carrier signal and data signals on the media, notes when collisions between signals occur, and forwards this information to the remaining circuitry for processing. To distinguish the two different meanings of the acronym "MAU," the acronym *MSAU* is sometimes used to refer specifically to a Multistation Access Unit, as used in Token Ring networking.

See Also: *hub, loopback, shielded twisted-pair (STP) cabling, Simple Network Management Protocol (SNMP), Token Ring*

multitasking

Running two or more programs simultaneously.

Overview

From the point of view of the user, multitasking makes programs appear to be executing at the same time, but from the operating system's point of view, one of two things might be happening:

- **On multiprocessor machines:** Here each processor might be running a separate program simultaneously. This is true multitasking, which can only take place on machines with more than one processor and with operating systems that support multiple processors.
- **On single-processor machines:** Here the operating system time-slices between applications so that each application receives a small portion of time to run before giving this privilege to another application.

Types

There are two basic types of multiprocessing on machines that run versions of the Windows operating system:

- **Preemptive multitasking:** The operating system decides which thread or process is allowed to run at any specific time. Windows 95, Windows 98, and Windows NT support this form of multitasking.
- **Cooperative multitasking:** Each application is responsible for voluntarily relinquishing control to other applications. Windows 3.*x* supports this form of multitasking.

Notes

Windows 2000 supports symmetric multiprocessing (SMP) on multiprocessor machines, whereby the Windows 2000 kernel lets processors share memory and assign ready threads to the next available processor. This SMP support ensures that no processor is ever idle or running a low-priority thread when a high-priority thread is waiting. Windows 2000 also supports soft affinity, whereby a thread tries to run on the same processor it last ran on, all things being equal. You can even use Task Manager to assign a specific process to a particular processor, a feature called processor affinity.

See Also: *asymmetric multiprocessing (AMP)*

Multitenant Broadband Service Provider (MBSP)

Another name for a building-centric local exchange carrier, a telecommunications carrier focused on the Multitenant Unit (MTU) market.

See: *Building-centric Local Exchange Carrier (BLEC)*

multitenant unit (MTU)

A building with many tenants, such as a skyscraper.

Overview

Multitenant units are generally large office buildings in dense urban areas, but the term can also include apartment complexes, hotels, industrial parks, and other large buildings and complexes. The MTU market is one that is rapidly growing in importance as far as telcos and other carriers are concerned—estimates indicate there are about 120,000 MTUs in the United States, and many of these MTUs host businesses that are eager for broadband data services. Traditional incumbent local exchange carriers (ILECs) have been slow to provision broadband services such as Digital Subscriber Line (DSL) for this market segment, and, as a result, many competitive local exchange carriers (CLECs) are targeting them. These carriers targeting MTUs for broadband services are generally called Multitenant Broadband Service Providers (MBSPs) or building-centric local exchange carriers (BLECs).

See Also: *broadband Internet access, Building-centric Local Exchange Carrier (BLEC), Competitive Local Exchange Carrier (CLEC), Digital Subscriber Line (DSL), Incumbent Local Exchange Carrier (ILEC)*

MUX

Stands for multiplexer, a device that combines multiple data streams into a single stream.

See: *multiplexer (MUX)*

MVS

Stands for Multiple Virtual Storage, a legacy IBM mainframe operating system.

See: *Multiple Virtual Storage (MVS)*

MX record

A Domain Name System (DNS) record identifying Simple Mail Transfer Protocol (SMTP) hosts.

Overview

MX records specify the DNS name and Internet Protocol (IP) address of a host that can forward e-mail for a given domain. (The acronym *MX* stands for mail exchange.) MX records are required for SMTP hosts to enable them to forward SMTP mail over the Internet.

Examples

An MX record specifying that incoming mail directed toward the microsoft.com domain should be forwarded to the SMTP host called mail.microsoft.com might be expressed as

```
microsoft.com.   IN   MX   0
mail.microsoft.com.
```

Here the number 0 is the preference value that specifies the priority of the SMTP host. This is used if more than one SMTP mail exchanger exists for a given domain.

See Also: *Domain Name System (DNS), resource record (RR)*

My Computer

A desktop icon in Microsoft Windows that enables users to browse resources on their computer.

Overview

The My Computer icon provides a view that is different but complementary to Windows Explorer's view of system and network resources. My Computer gives users a simple way to view the resources on their computer. With Active Desktop installed, however, My Computer has an optional interface that supports browsing resources using a Web browser format.



MARCY01_ (C:)
Local Disk

Capacity: 1.99 GB

▨ Used: 1.53 GB

☐ Free: 473 MB

Free Space: 473 MB, Capacity: 1.99 GB

My Computer. *Typical contents of My Computer.*

See Also: *My Documents, My Network Places*

My Documents

A folder in Microsoft Windows that gives users a convenient location for storing their documents.

Overview

My Documents is the default location where applications such as Microsoft Office save the files you create. The desktop icon for My Documents is a folder containing a sheet of paper. My Documents is also part of the user profile on a machine running Windows 2000, Windows XP, and Windows .NET Server, and you can redirect (change) the location of the target folder for My Documents by right-clicking on My Documents and selecting Properties. For example, you could modify My Documents to point to a network share where the user's documents can be safely stored and regularly backed up. Users should generally be instructed to always save their personal documents in their My Documents folder even if their applications do not automatically do so.

See Also: *My Computer, My Network Places*

My Network Places

A desktop icon in Microsoft Windows 2000, Windows XP, and Windows .NET Server that displays various aspects of the network your computer resides on.

Overview

My Network Places can be used to browse resources on the network. When you open My Network Places, it may contain

- **Add Network Place:** Starts the Add Network Place Wizard. You use the wizard to create shortcuts to network resources such as shared folders, printers, and File Transfer Protocol (FTP) sites.
- **Entire Network:** Contains links to all computers on your network.
- **Microsoft Windows Network:** Included in Entire Network and provides access to computers belonging to Windows 2000 and Windows NT domains and workgroups.
- **Directory:** Included in Entire Network and provides access to information on users, groups, and computers stored in Active Directory directory service on domain controllers.
- **Computers Near Me:** Shows all computers in your local domain or workgroup.
- **Network shortcuts:** These point to shared network resources that you have created using the Add Network Place Wizard.



Use this folder to open files and folders on other computers and to install network printers.

To set up networking on your computer, click Network and Dial-up Connections.

Select an item to view its description.

See also:
My Documents
My Computer

8 object(s)

My Network Places. *Typical contents of My Network Places.*

Note also that if you right-click My Network Places and choose Properties, you can open your Network Connections folder, which displays the types of connections that your computer has with local area networks (LANs) or the Internet and allows you to configure these connections.

N

Nagle's algorithm

A Transmission Control Protocol (TCP) algorithm for controlling traffic congestion on a network.

Overview

Nagle's algorithm increases the efficiency of routers by reducing the latency of the routing process. This is accomplished by limiting the transmission of small Internet Protocol (IP) datagrams and by controlling the size of the TCP sending window. Nagle's algorithm is crucial in enabling IP networks to efficiently support applications such as Telnet that communicate using large numbers of small datagrams.

Nagle's algorithm is defined in RFC 896 and is implemented in common TCP/IP protocol stacks, including that of Microsoft Windows operating systems. Proposals have been put forth for improving the algorithm because it does not produce optimal results with certain kinds of TCP/IP interactions, such as those based on Hypertext Transfer Protocol (HTTP) version 1.1.

Implementation

To understand how the algorithm works, consider a Telnet client communicating with a Telnet server. When a user types a single character into the Telnet client window, TCP normally packages the character and sends it to the server as a very small IP packet. It would be highly inefficient if every character typed into a Telnet window were sent as such a packet, as this would flood the network with small packets. Using Nagle's algorithm, however, what actually happens is that when the user types the next character, one of two things occurs:

- If an acknowledgment has already been received for the first packet sent, TCP packages the second character into a second small packet and sends it immediately to prevent delay.
- If an acknowledgment has not been received for the first packet, TCP buffers the second character, then the third, and so on, until the acknowledgment is received or the buffer has reached a certain size, triggering TCP to package the buffered characters and send them. This process of buffering the TCP send buffer is sometimes called "nagling."

The other part of Nagle's algorithm addresses the problem of a network system getting bogged down when a large datagram is sent over and over again because it takes too long to fill a sending window (the receiving buffer) with the data from the datagram. According to the algorithm, when a client receives a message that datagrams are being dropped because of congestion at a particular host, the client responds by temporarily acting as if the host's window size has been reduced. This "throttles back" the amount of information sent to the host and enables the host to catch up.

See Also: *Hypertext Transfer Protocol (HTTP), Internet Protocol (IP), Telnet, Transmission Control Protocol (TCP)*

named pipe

A legacy interprocess communication (IPC) mechanism.

Overview

Named pipes are a client/server communication mechanism that provides reliable, connection-oriented, two-way communication between processes running on different computers. A named pipe is essentially a portion of memory reserved for one process to pass information to another.

Developed originally for Microsoft OS/2 LAN Manager and maintained as a feature in later versions of Microsoft Windows for backward compatibility, named pipes provide guaranteed delivery of data between computers for distributed applications in a client/server environment. They provide a reliable, one-to-one, bidirectional, connection-oriented form of communication between a client process running on one machine and a server process (service) running on a different machine. Named pipes are implemented as file system drivers and therefore are opened by requests made from the redirector. They take full advantage of the features of file system drivers, such as security and validation.

Examples of situations where named pipes are still used include

- WinLogon process of Windows NT Server
- Client/server applications designed on older versions of Microsoft SQL Server
- Windows 98 and Windows Millennium Edition (Me), which support client-side named pipes but not server-side named pipes

Notes

Named pipes consume more server-side memory than other IPC mechanisms (such as Windows Sockets) and generate a bit more network traffic.

See Also: *interprocess communication (IPC)*

name lookup

Resolving a fully qualified domain name (FQDN) into its associated Internet Protocol (IP) address.

Overview

In the Domain Name System (DNS), name resolution is the process of a resolver (DNS client) sending a request to a name server (DNS server). The resolver sends the name server the host name of an IP host on the network, and the name server returns the host's IP address. The name server is thus said to "resolve" the name of the host into its associated IP address.

The query sent by the resolver to the name server is most often a recursive query, which returns either the expected IP address or an error. This type of query makes it possible for a name server to forward the request on to other name servers if it cannot resolve the name and then return the result of that request to the resolver. If the queried name server is configured to forward requests, it can perform an iterative query, querying several name servers in succession until it resolves the name or runs out of name servers to query.

See Also: *Domain Name System (DNS), fully qualified domain name (FQDN), host name resolution, name server*

name resolution

The process of resolving the name of a host on a network into its associated network address.

Overview

Name resolution plays an important part of network communication because the logical names of hosts on the network must be resolved into their network addresses before actual communication can take place between them.

Transmission Control Protocol/Internet Protocol (TCP/IP) networks running Microsoft Windows operating systems support two basic name resolution methods:

- **NetBIOS name resolution:** Used to resolve NetBIOS names into IP addresses. Performed by using broadcasts or by querying a Windows Internet Name Service (WINS) server. NetBIOS name resolution was used in Microsoft Windows NT and is supported by Windows 2000, Windows XP, and Windows .NET Server for backward compatibility purposes only.
- **Host name resolution:** Used to resolve fully qualified domain names (FQDNs) in the Domain Name System (DNS) into IP addresses. Performed either by using a local Hosts file on the machine or by querying a name server.

Notes

Once the name of a host has been resolved into its associated IP address, a TCP/IP protocol called Address Resolution Protocol (ARP) is then used on Ethernet networks to resolve the host's IP address into its associated physical layer address (MAC address). Once ARP has completed this task, frames can then be placed on the wire with the destination MAC addresses embedded in their frame headers.

See Also: *Address Resolution Protocol (ARP), Domain Name System (DNS), Ethernet, frame, fully qualified domain name (FQDN), host name resolution, hosts file, MAC address, name server, NetBIOS name resolution, Transmission Control Protocol/Internet Protocol (TCP/IP), Windows Internet Name Service (WINS)*

name server

A host used to resolve fully qualified domain names (FQDNs) into their associated Internet Protocol (IP) addresses.

Overview

Name servers are hosts on the Internet (or on large IP internetworks) that can be used to resolve host names into IP addresses, a process known as a name lookup. Name servers are an essential part of the Domain Name System (DNS). Because of name servers, when you want to access or reference a host on a TCP/IP network, you can use its friendly DNS name instead of its IP address, which is generally harder to remember.

The distributed system of name servers positioned at various locations around the Internet makes it possible to share the load of name resolution among many such servers instead of relying on a single server. Just imagine if one machine had to track the name of every host on the Internet—not only would its hardware requirements be astronomical, but it also would represent a single point of failure for the entire Internet economy!

Implementation

DNS operates as a client/server-based system, with name servers forming the server part and resolvers forming the client part. Each name server has authority over a portion of DNS namespace known as a zone, which means that the name server can resolve name lookups for hosts located within that zone. A resolver sends a name lookup request to a name server by passing it the DNS name of a host on the network. The name server performs name resolution by determining the IP address that corresponds to the requested host's name. Name servers can also refer such queries to other name servers if they cannot answer them themselves, so a typical name lookup from a resolver might involve obtaining responses from several name servers in sequence.

Each zone has one name server called the master name server that is authoritative over hosts located in the zone. In addition, name servers can be classified on the basis of how they store zone information:

- **Primary name servers:** These name servers keep a local file of the information relating to their zone. This local file or DNS database contains resource records, which are mappings of host names to IP addresses for hosts in that zone. A DNS administrator must generally create and maintain the DNS database manually on a primary name server, although with dynamic DNS (DDNS), hosts can automatically register this information with name servers. Microsoft Windows 2000 and Windows .NET Server support DDNS.
- **Secondary name servers:** These name servers obtain their database of resource records from a master name server, which can be either a primary name server or another secondary name server. The process by which the DNS database is transferred from a master name server to a secondary name server is known as zone transfer. Secondary name servers are provided mainly for fault tolerance and load balancing.

See Also: *Domain Name System (DNS), dynamic DNS (DDNS), fault tolerance, load balancing, master name server, primary name server, resolver, secondary name server, zone, zone transfer*

namespace

An abstract space of names of nodes on a network.

Overview

The term *namespace* can be thought of as "the space of all names" for the particular type of network naming system under consideration. A simple example is Internet Protocol (IP) address space, the space of all possible IP addresses. This space is divided into class A, class B, and so on, which represent disjoint subgroups of the IP address space. Generally, every node on a Transmission Control Protocol/Internet Protocol (TCP/IP) network, internetwork, or the Internet must occupy a unique point in IP address space—that is, it must have a unique IP address. This ensures that a packet addressed to a particular node (such as a computer, network printer, or router interface) can be directed to the node using its IP address as the destination address. If two nodes on a network were to have the same IP address number, a packet intended for one might end up at the other. One exception to this is multicasting, in which a packet is sent to a group of hosts simultaneously and ignored by all other hosts. Another exception is when you have a private network connected to the Internet through a firewall that uses network address translation (NAT) to hide the addresses of hosts on the private network from hosts on the Internet. In this case, if no direct communication is expected between nodes in the two networks (except through the firewall), nodes in the private network can be assigned arbitrary IP addresses, such as 10.*x.y.z*, and two or more private networks can use the same addressing scheme without fear of confusion or lost packets.

Examples

Some other common examples of namespaces include the Domain Name System (DNS) namespace used on the Internet, the NetBIOS namespace used in legacy Microsoft Windows NT networks, and the LDAP namespace used by Active Directory. Unlike the space of IP addresses described above which is essentially flat, DNS namespace is hierarchical in nature and highly scalable. It also has the advantage of being a logical naming scheme that is easily remembered, in contrast to a physical naming scheme such as an IP address, which is hard to memorize and which is bound to the particular network structure being used. The root of the DNS namespace branches out to a relatively small number of top-level domains such as .com, .org, and .edu. Organizations, companies, and individuals can register a domain name in one of these domains and then subdivide their branch of the DNS namespace as they desire. For example, a company named Northwind Traders might register the domain name northwindtraders.com and then create three new subdomains under it named sales.northwindtraders.com, support.northwindtraders.com, and hq.northwindtraders.com. Specific servers and router interfaces exposed to the Internet might then be given specific DNS addresses to uniquely identify them in the DNS namespace. An address in the DNS namespace, called a fully qualified domain name (FQDN), maps to a unique node on the Internet. An example might be widgets.support.northwindtraders.com, which might map to the address 10.15.6.133. Names of domains, subdomains, and individual hosts are maintained on name servers located at various points across the Internet or within large private internetworks. If you want to locate a particular node in the DNS namespace, you query a name server. The process of locating a particular DNS node and resolving its FQDN into its associated IP address is called host name resolution.

The NetBIOS namespace used in Windows NT–based networks (and supported by Windows 2000 and Windows XP for backward compatibility) is simply the space of all NetBIOS names (computer names) of Microsoft Windows machines on the network. Unlike the hierarchical tree structure of the DNS namespace, the NetBIOS namespace is flat and is managed using the Windows Internet Name Service (WINS), which runs on WINS servers in the network. Because the NetBIOS namespace is flat, it is not as highly scalable as DNS. For example, say that you query a name server to resolve an FQDN such as widgets.support.northwindtraders.com into its associated IP address. The name server might first have to find another name server that is authoritative in the northwindtraders.com domain. Next, the name server must find a name server that is authoritative in the support.northwindtraders.com subdomain whose database contains a record for the widgets.support.northwindtraders.com host. Finally, the name server must resolve the information in the record into an IP address. The whole process might take only several referrals and a short inspection of a relatively small database of resource records because each name server on the Internet is authoritative over only a small portion of the DNS namespace. Once you locate the correct name server through a series of hierarchical queries, the final name lookup deals with only a small number of records. The NetBIOS namespace is different, however, because each WINS server maintains a database of records for all NetBIOS names on the network. So if you were to use WINS to manage a network the size of the Internet with its millions of hosts, each WINS server would have a flat-file database containing millions of records, which would need to be searched from top to bottom each time a query was issued against it.

An additional example of a namespace is the hierarchy of distinguished names (DNs) used to identify objects in a directory based on the Lightweight Directory Access Protocol (LDAP). The LDAP namespace is closely tied to the DNS namespace of the Internet, as the top-level LDAP containers are simply top-level domain names. The Active Directory directory service of Windows 2000 is based on LDAP and uses DNs to name objects stored within its directory.

Notes

Because of the flexibility and scalability of DNS and its association with the Internet, DNS is the primary naming system used by Windows 2000. Support for WINS is included only for backward compatibility with downlevel Windows NT stations and legacy Windows stations. Active Directory in Windows 2000 and Windows .NET Server uses DNS as the service for name resolution (for locating users, groups, computers, shared folders, printers, and other objects on the network). The namespace of Active Directory represents a bounded area within which the DNS name of the root of Active Directory is translated to all the objects within the directory. Within Active Directory, a domain tree represents a contiguous namespace of connected objects, but a domain forest is a disjointed namespace formed from two or more domain trees. Companies that have Windows 2000– or Windows .NET Server–based networks can use the same DNS namespace for both internal and external network connections, or they can use separate DNS names for the network from an internal or an external perspective.

See Also: *Active Directory, domain (DNS), Domain Name System (DNS), fully qualified domain name (FQDN), host name resolution, IP address, Lightweight Directory Access Protocol (LDAP), NetBIOS, NetBIOS name resolution, network address translation (NAT), Windows Internet Name Service (WINS)*

naming context

A contiguous subtree or branch of Active Directory directory service namespace.

Overview

Naming contexts are used in Microsoft Windows 2000 and Windows .NET Server to partition the Active Directory namespace into sections, each with its own security boundary. Naming contexts are used during the process of directory replication to form the basic unit of the replication process. During multimaster replication of Active Directory, any naming context that has been updated is replicated to other domain controllers. For example, if the schema is modified on one domain controller, the schema naming context is replicated to all other domain controllers in Active Directory and also to the global catalog server. Only those portions of the naming context that have changed are actually replicated.

Active Directory always includes at least three naming contexts:

- **Configuration:** Contains information about sites, services, partitions, and the Active Directory schema
- **Domain naming:** Contains information relating to directory data for the domain in which the Active Directory domain controller resides
- **Schema:** Contains the schema information that defines the classes, objects, and attributes used in Active Directory

See Also: *Active Directory, directory replication (Windows 2000 and Windows .NET Server), namespace, schema*

naming convention

A rule for ensuring that users have their own unique username.

Overview

A simple and consistent naming convention for users on a network is an important part of network administration. Examples of naming conventions applied to the user Jeff Smith might include the following:

- **Jsmith:** Here the first letter of the user's first name is concatenated with the user's full last name
- **Jeffs:** Here the user's first name is concatenated with the first letter of the user's last name

Two users on a network might have the same first or last name, so your naming convention should include a rule to break ties. For example, if Jeff Smith is "jsmith," James Smith might be "jsmith2." You might also want to establish a rule for easily identifying temporary employees, such as "T-jsmith" or "jsmith(temp)."

Notes

On Microsoft Windows 2000–based networks, usernames of domain user accounts must be unique within the given organizational unit (OU) in which they are created in the Active Directory database. Usernames can be more than 20 characters long, but only the first 20 characters are used as logon credentials.

See Also: *Active Directory, domain (DNS), organizational unit (OU), user account*

NAP

Stands for Network Access Point, a point where Internet traffic is exchanged between Internet service providers (ISPs).

See: *Network Access Point (NAP)*

NAPT

Stands for network address port translation, a form of network address translation (NAT) in which both Internet Protocol (IP) addresses and port numbers are translated.

See: *network address translation (NAT)*

NAS (network access server)

Stands for network access server, the server at the Internet service provider (ISP) end of a dial-up connection.

See: *network access server (NAS)*

NAS (network attached storage)

Stands for network attached storage, a storage appliance that attaches directly to the network.

See: *network attached storage (NAS)*

NAT

Stands for network address translation, a method of substituting one Internet Protocol (IP) address for another.

See: *network address translation (NAT)*

National Electric Code (NEC)

A series of specifications for protecting commercial and residential buildings from electrical hazards.

Overview

The National Electric Code is published by the National Fire Protection Association (NFPA), an international organization that advocates standards for fire safety and related issues. The NEC is one of hundreds of standards documents produced by the NFPA. The NEC, which is NFPA standard number 70, deals with how to properly install and maintain electrical and electronic equipment in order to minimize fire hazards. In the area of computer networking, the NEC covers the proper installation and construction of copper cabling, fiber-optic cabling, and other network infrastructure. The NEC also covers issues relating to the powering of network devices, such as proper grounding.

The NEC is legally enforced in every state in the United States and in a number of other countries and regions. Most U.S. municipalities have adopted NEC recommendations in local building codes. Testing of electrical equipment for compliance with NEC standards is performed by Underwriters Laboratories (UL).

For More Information

Visit the NFPA at *www.nfpa.org.*

See Also: *cabling, infrastructure*

National Institute of Standards and Technology (NIST)

A U.S. government organization that provides services and programs to help U.S. industries commercialize new technologies and compete internationally.

Overview

National Institute of Standards and Technology (NIST) certification identifies technologies as meeting federal government requirements. For example, in the area of relational database management systems (RDBMSs), NIST administers a test named Federal Information Processing Standard (FIPS) 127-2. FIPS 127-2 is based on the broader American National Standards Institute (ANSI) SQL92 standard, which ensures portability across heterogeneous RDBMSs by establishing a common set of structured query language (SQL) commands. There is no higher standard for SQL database languages than FIPS 127-2. Microsoft SQL Server 6.5 was the first RDBMS to pass the NIST version 5.1 validation tests for Entry Level FIPS 127-2, as it fully complied with both the ANSI SQL92 standard and the FIPS standards.

The following table shows some of the FIPS cryptography standards developed by NIST. One action of NIST that has had wide impact on the cryptography field is the contest recently hosted by NIST to find a successor to the Data Encryption Standard (DES), which has been shown to be no longer secure. NIST selected the Rijndael algorithm developed by Belgian cryptographers as the replacement for DES and as the basis of NIST's new Advanced Encryption Standard (AES).

Some Cryptography Standards from NIST

Standard	*Description*
FIPS 46-3	Data Encryption Standard (DES) and Triple DES
FIPS 81	DES Modes of Operation
FIPS 180-1	Secure Hash Standard (SHS)
FIPS 186-2	Digital Signature Standard (DSS)

For More Information

Visit NIST online at *www.nist.gov.*

See Also: *Advanced Encryption Standard (AES), cryptography, Data Encryption Standard (DES), encryption, Structured Query Language (SQL)*

native mode

A mode for running Microsoft Windows 2000 and Windows .NET Server domain controllers.

Overview

Windows 2000 domain controllers operate in mixed mode by default. Mixed mode allows Windows 2000 and Windows NT to interoperate, which is essential during the migration of a Windows NT–based network to Windows 2000. If your migration is complete, however, or if you have a pure Windows 2000 network, then you should switch your domain controllers to native mode. Domain controllers running in native mode can only be used to authenticate users on a pure Windows 2000–based network.

Native mode gives you more options than mixed mode about types of groups. Specifically, you can use universal groups and you can nest groups to any degree. Running in mixed mode means that universal groups are not available, and you can nest global groups only in domain local groups and only to one level of nesting.

Windows 2000 domain controllers running in native mode are incompatible with Windows NT domain controllers, and if you want to use native mode, all domain controllers must be running Windows 2000 and must be configured to run in native mode, but member servers and client workstations can still run either Windows 2000 or Windows NT.

To change domain controllers from mixed mode to native mode, use the administrative tool Active Directory Domains and Trusts. Note that if you change a domain controller to native mode, you cannot change it back to mixed mode, so do not make the change until all your domain controllers are running Windows 2000.

Notes

Windows .NET Server domain controllers can operate in one of three available modes: Windows 2000 mixed, the default; Windows 2000 native; and Windows .NET. The first mode is used for the greatest degree of backward compatibility, at the cost of new functionality. The second mode provides some enhanced functionality but remains limited. Windows .NET mode does not allow for backward compatibility with former OS domain controllers, but it provides functionality that can be found only in this latest version of Active Directory. Domain functional levels can be raised from lower to higher, but once they are, the backward compatibility with domain controllers of a former OS is eliminated.

See Also: *domain controller, domain modes, native mode, universal group*

NBF

Stands for NetBEUI Frame, an enhanced version of NetBIOS Extended User Interface (NetBEUI) supported by Microsoft Windows NT.

See: *NetBEUI Frame (NBF)*

NBNS

Stands for NetBIOS Name Server, a server responsible for maintaining a list of mappings between NetBIOS computer names and network addresses for a network that uses NetBIOS as its naming service.

See: *NetBIOS Name Server (NBNS)*

Nbtstat

A Transmission Control Protocol/Internet Protocol (TCP/IP) command that displays current connections and statistics using NetBIOS over TCP/IP (NBT).

Overview

Nbtstat can be run from the Microsoft Windows 2000 command prompt to view NBT statistics for the local computer and to display the status of TCP/IP connections on the computer. This is useful for troubleshooting certain NetBIOS name resolution problems.

N

You can also use Nbtstat to

- Preload #PRE entries in the Lmhosts file into the NetBIOS name cache, which contains NetBIOS name to IP address mappings for other hosts on the network
- View the NetBIOS name and NetBIOS scope ID of the machine

Examples

Some examples of using Nbtstat include

- **Nbtstat -n**, which shows the NetBIOS names of the host that have been registered on the system
- **Nbtstat -c,** which displays the current contents of the NetBIOS name cache
- **Nbtstat -a** *ComputerName*, which displays the local NetBIOS name table on the computer named *ComputerName* and also its MAC address

See Also: *NetBIOS, NetBIOS over TCP/IP (NetBT), Transmission Control Protocol/Internet Protocol (TCP/IP)*

NCP (NetWare Core Protocol)

Stands for NetWare Core Protocol, a legacy NetWare protocol.

See: *NetWare Core Protocol (NCP)*

NCP (Network Control Protocol)

Stands for Network Control Protocol, the portion of Point-to-Point Protocol (PPP) responsible for encapsulating network layer protocols.

See: *Network Control Protocol (NCP)*

NDIS

Stands for network driver interface specification, a specification for network driver architecture.

See: *network driver interface specification (NDIS)*

NDS

Stands for Novell Directory Services, the directory services platform from Novell Networks.

See: *Novell Directory Services (NDS)*

near-end crosstalk (NEXT)

A measurement of the ability of network cabling to reject crosstalk.

Overview

Crosstalk is an undesirable condition in which the signals traveling through adjacent pairs of wire in twisted-pair cabling interfere with each other. Near-end crosstalk (NEXT) measures the ability of a cable to reject crosstalk between pairs of wire at the near end of the circuit. The pair causing the interference is called the "disturbing pair," and the pair experiencing the interference is the "disturbed pair." Channel NEXT is the NEXT value measured between one wire pair and another in the same cable; it is measured at both ends of the wire.

The NEXT value for a given cable type is typically expressed in decibels (dB) per 1000 feet and varies with the frequency of transmission. The higher the NEXT value, the greater the cable's ability to reject crosstalk at its local connection. For example, the specifications for Category 5 (Cat5) cabling include the minimum NEXT values shown in the following table. Note that the NEXT value generally decreases with increasing frequency, indicating increasing interference due to crosstalk at higher frequencies.



Near-end crosstalk (NEXT). *Different types of NEXT.*

Desired Data Rate and the Cable's Minimum NEXT Value

Frequency	*Minimum NEXT Value*
4 megahertz (MHz)	53 dB/1000 feet
10 MHz	47 dB/1000 feet
20 MHz	42 dB/1000 feet
1000 MHz	32 dB/1000 feet

Types

The various types of NEXT that can be measured are as follows:

- **Pair-to-Pair NEXT:** NEXT between adjacent pairs of wire in a twisted-pair cable. A typical four-pair (eight-wire) unshielded twisted-pair (UTP) cable has six possible values for pair-to-pair NEXT, which are then averaged. This simple measurement is not adequate, however, because every pair of wire generates crosstalk with every other pair in the cable.
- **Power Sum NEXT (PS NEXT):** A more rigorous way of rating a cable's crosstalk that measures the total amount of crosstalk between one wire pair and all its neighboring pairs in the same cable. PS NEXT is particularly important for cabling used in high-speed networks such as Gigabit Ethernet (GbE) and Asynchronous Transfer Mode (ATM) networks.
- **Far-End Crosstalk (FEXT):** A measurement of how the far end of one wire pair affects the near end of another pair.

Notes

To minimize NEXT in installations of Cat5 cabling, do not expose more than 2 inches (6 centimeters) of wire pairs at the termination point of the cable (the patch panel, wall plate, or RJ-45 connector). Also, do not untwist the wire pairs more than 0.5 inches (1.27 centimeters).

See Also: *cabling*

NEC

Stands for National Electric Code, a series of specifications for protecting commercial and residential buildings from electrical hazards.

See: *National Electric Code (NEC)*

.NET

Stands for Microsoft .NET platform, Microsoft Corporation's new Extensible Markup Language (XML) Web services platform for building integrated service-oriented applications to meet the needs of today's Internet businesses.

See: *.NET platform*

NetBEUI

Stands for NetBIOS Extended User Interface, a networking protocol developed by IBM and Microsoft Corporation.

See: *NetBIOS Extended User Interface (NetBEUI)*

NetBEUI Frame (NBF)

An enhanced version of NetBIOS Extended User Interface (NetBEUI) supported by Microsoft Windows NT.

Overview

Some of the enhancements and special features of NetBEUI Frame (NBF) include

- Support for network driver interface specification (NDIS) version 3 for full 32-bit asynchronous transport layer communication using the transport driver interface (TDI) layer as a NetBIOS emulator
- Support for automatic memory tuning through dynamic memory allocation
- Support for dial-up clients through the Remote Access Service (RAS)
- An extension of NetBEUI's limit of 256 concurrent NetBIOS sessions to more than 1000 sessions

Notes

Although NetBEUI is essentially a nonroutable protocol, NBF supports Token Ring Source Routing on IBM Token Ring networks.

See Also: *NetBIOS, NetBIOS Extended User Interface (NetBEUI), network driver interface specification (NDIS)*

NetBIOS

A legacy protocol for network communications.

Overview

NetBIOS, which stands for Network Basic Input/Output System (though no one calls it that anymore), is a specification originally created by Sytec for IBM in the early 1980s. NetBIOS was originally designed to enable personal computers to communicate with mainframes running Systems Network Architecture (SNA). It was later adopted by Microsoft Corporation for its LAN Manager platform to enable distributed applications to access network services running on different machines independent of the transport protocol used.

NetBIOS is defined in RFCs 1001, 1002, and 1088. The original NetBIOS specification could support a maximum of only 72 nodes, though this was later extended to thousands of hosts through various enhancements. The current version of the NetBIOS specification is NetBIOS 3.

Architecture

From an architectural viewpoint, NetBIOS defines two things:

- An interprocess communication (IPC) mechanism and application programming interface (API) that allows applications that are NetBIOS-enabled to communicate remotely over a network and request services from lower levels of the protocol stack. This is the primary and original definition of NetBIOS.
- A network protocol operating at the session and transport layers of the Open Systems Interconnection (OSI) reference model that supports functions such as session establishment and termination as well as name registration, renewal, and resolution.

Implementation

NetBIOS formed an essential part of the Microsoft Windows NT platform. Each Windows NT machine required a unique NetBIOS name in order to communicate on a network. These NetBIOS names consisted of 15 characters plus a 16th character that is reserved to identify various network services to the operating system. Also, depending on the underlying network protocol over which it is running, NetBIOS on Windows NT could take different forms. The following table lists some common network protocols and the form that NetBIOS takes over each protocol.

Examples of NetBIOS Protocol Stacks

Network Protocol	*Name When Combined with NetBIOS*
NetBEUI	NBF (NetBEUI Frame protocol)
NWLink IPX/SPX-Compatible Transport	NWLink NetBIOS
TCP/IP	NetBT (NetBIOS over TCP/IP)

Issues

NetBIOS has been superseded in Windows 2000, Windows XP, and Windows .NET Server by the industry-standard Domain Name System (DNS), which is used for naming hosts and for name resolution (Windows NT also supported DNS but did not require it). Support for NetBIOS is still included, however, in Windows 2000, Windows XP, and Windows .NET Server to ensure backward compatibility with Windows NT, Windows 95, Windows 98, and Windows Millennium Edition (Me) computers. There are several instances where incompatibilities between the two naming systems can arise, however:

- In Windows 2000, Windows XP, and Windows .NET Server, host names can be 64 characters long, but NetBIOS names can only be 15 characters long. If host names are longer than 15 characters, they are truncated, which can lead to collisions.
- DNS names can use hyphens but not underscores to represent spaces, although NetBIOS names have traditionally used underscores for such purposes. Since the Windows 2000 and Windows .NET Server versions of DNS support Unicode characters, this is not really an issue unless support for downlevel name servers is required.

Another problem with leaving NetBIOS enabled on Windows 2000, Windows XP, and Windows .NET Server networks is that NetBIOS is not intrinsically secure. Using the Nbtstat command, for example, a user can easily find out the name, MAC address, services running, and other information about hosts on a network that supports NetBIOS. As a result, once a migration to Windows 2000 or later is complete, NetBIOS should be disabled if it is no longer required for communications with machines using earlier versions of Windows.

See Also: *application programming interface (API), Domain Name System (DNS), interprocess communication (IPC), Nbtstat, NetBIOS name, NetBIOS name resolution, NetBIOS Name Server (NBNS), NetBIOS over TCP/IP (NetBT), NetBIOS over TCP/IP node types, Open Systems Interconnection (OSI) reference model, Windows Internet Name Service (WINS)*

NetBIOS Extended User Interface (NetBEUI)

A networking protocol developed by IBM and Microsoft Corporation.

Overview

NetBIOS Extended User Interface (NetBEUI) is an extension of the NetBIOS specification that functions as a network protocol for workgroup-size local area networks (LANs) having up to 200 stations. This is because NetBEUI relies more heavily on broadcast packets than do protocols such as Transmission Control Protocol/Internet Protocol (TCP/IP) and NWLink Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX)-Compatible Transport protocols, which can support much larger networks. Because NetBEUI has a single-part naming scheme, it is also a nonroutable protocol and therefore generally unsuitable for wide area networks (WANs).

NetBEUI is a fast and efficient protocol with low overhead. NetBEUI is self-tuning and implements flow control and error detection. It also defines a framing mechanism at the transport layer and implements the Logical Link Control version 2 (LLC2) protocol of the Open Systems Interconnection (OSI) reference model.

NetBEUI supports two types of network communications:

- **Connection-oriented:** Used, for example, when mapping drives using the Net Use command and starting services remotely using the Net Start command

- **Connectionless:** Used, for example, when sending datagrams, registering NetBIOS names, and performing NetBIOS name resolution

Implementation

NetBEUI was developed in 1985 and was implemented as the main networking protocol for the Microsoft LAN Manager and Microsoft Windows for Workgroups operating system platforms. NetBEUI is supported by most Windows platforms for backward compatibility. The implementation of NetBEUI on Windows NT is properly known as NetBEUI Frame (NBF) protocol.

See Also: *NetBEUI Frame (NBF), NetBIOS, NetBIOS name resolution, Open Systems Interconnection (OSI) reference model, routing*

NetBIOS name

A 16-byte name for a node on a network supporting the NetBIOS specification.

Overview

NetBIOS names are a friendly way of identifying computers on a network that supports the NetBIOS specification. This is because alphanumeric names are easier for users to remember than network numbers, such as dotted Internet Protocol (IP) addresses. In Microsoft Windows NT, for example, NetBIOS names are used to identify individual machines and also the various networking services running on each machine. Each service that is NetBIOS-enabled requires a unique NetBIOS name to identify it on the network in order for other computers to access those services on the machine.

The NetBIOS name (computer name) for a Windows NT machine is assigned to it during installation and can be up to 15 characters long. A 16th character is then suffixed to the computer name (or domain name or current user name) to identify the particular network service being referenced. For example, the 16th character identifying the Messenger service is 03h in hexadecimal form, so on a computer named SERVER12 the Messenger service would be uniquely identified on the network by NetBIOS as SERVER12[03h].

NetBIOS names are also distinguished by whether they are

- A unique name, which applies to a single IP address
- A group name, which applies to a subnet group of IP addresses
- A multihomed name, which applies to a multicast group of IP addresses

The following table shows some of the more common suffixes that constitute the hidden 16th character of a NetBIOS name and the networking service with which they are associated.

Common Suffixes for NetBIOS Names

Suffix (Hex)	*First 15 Characters*	*Networking Service*
00	Computer name	Workstation service
00	Domain name	Domain name
03	Computer name	Messenger service
03	User name	Messenger service
06	Computer name	RAS Server service
20	Computer name	File Server service
21	Computer name	RAS Client service
1B	Domain name	Domain master browser
1C	Domain name	Domain controllers
1D	Domain name	Master browser
1E	Domain name	Browser service election

Notes

To view the NetBIOS names registered for your computer, use the Nbtstat command. NetBIOS names are also supported by Windows 2000, Windows XP, and Windows .NET Server, but only for interoperability with some Windows NT machines, as they use the Domain Name System (DNS) instead for naming hosts and name resolution on a network.

See Also: *Domain Name System (DNS), Nbtstat, NetBIOS, NetBIOS name resolution, Windows NT*

NetBIOS name resolution

Resolving a computer's NetBIOS name into its corresponding Internet Protocol (IP) address.

Overview

NetBIOS over TCP/IP (NetBT) enables hosts on a Microsoft Windows NT–based network to communicate with each other. This is accomplished by resolving the NetBIOS name of a target host into its associated IP address, a process called NetBIOS name resolution. Once the host's name has been resolved, address resolution protocol (ARP) is then used to further resolve the host's IP address into its corresponding physical layer address (MAC address). Then once the host's physical address is known, frames can be placed on the wire and directed to this address.

The following describes the main NetBIOS over TCP/IP (NetBT) naming functions in detail:

- **NetBIOS name discovery:** NetBT hosts that want to communicate with similar hosts must issue a NetBIOS name query request to resolve the NetBIOS name of the target server into its IP address.
- **NetBIOS name registration:** NetBT hosts must register their NetBIOS name when they are initialized on a network to ensure that no duplicate names are on the network. NetBIOS name registration can be done either by broadcasts or by directed packets sent to a WINS server. Either or both methods can be used in either order, depending on the NetBT node type of the host.
- **NetBIOS name release:** NetBT hosts must release their NetBIOS names when they are shut down or when a particular NetBIOS-enabled service is stopped on the server. This enables another host to use the released name. NetBIOS name release can be done by broadcasts or by directed packets sent to a WINS server. Either or both methods can be used in either order, depending on the NetBT node type of the host.

Implementation

A number of different methods are used to perform NetBIOS name resolution. The following table shows the order in which these are attempted when the Windows NT machines on the network are configured as H-node machines (see the article called "NetBIOS over TCP/IP node types" elsewhere in this book). In a typical scenario where one Windows NT machine tries to establish communication with another, each name resolution method in the table is successively tried until either the target NetBIOS name is resolved into its associated IP address or the name resolution process fails. Note that some methods may not be available—for example, if there is no NetBIOS Name Server (NBNS) or DNS server on the network then these name resolution methods cannot be employed.

NetBIOS Name Resolution Methods in Order Attempted on Windows NT–Based Networks

Method	*Comments*
Check local NetBIOS name cache	The cache contains recently resolved NetBIOS names.
Contact NBNS	This method works only if NBNS is configured. The name server is usually a Windows Internet Name Service (WINS) server on a Microsoft network. The requestor tries three times to contact the name server and then tries to contact a secondary WINS server three times (if configured with secondary servers).
Perform local broadcast	The requestor broadcasts a NetBIOS name query request packet. The requestor tries three times before giving an error.
Check local Lmhosts file (Unique to Microsoft networks. If all methods fail, an error message states that the computer could not be found on the network.)	The requestor checks if an Lmhosts file exists.
Check local Hosts file (Unique to Microsoft networks. If all methods fail, an error message states that the computer could not be found on the network.)	On Windows NT the requestor checks the Hosts file if Enable DNS For Windows Resolution is selected on the WINS Address tab of the Transmission Control Protocol/Internet Protocol (TCP/IP) property sheet. This option is not available for Windows 2000 and later versions.
Contact DNS server (Unique to Microsoft networks. If all methods fail, an error message states that the computer could not be found on the network.)	The requestor contacts the DNS server if Enable DNS For Windows Resolution is selected on the WINS Address tab of the TCP/IP property sheet and the DNS tab has a DNS server specified on it. The requestor also tries 5, 10, 20, and 40 seconds later.

Examples

An example of when NetBIOS name resolution is used is when you go to the command prompt of a Windows machine and type **net use** followed by the NetBIOS name of the remote host in order to map a drive to a network share, for example, **net use x: \\server7\pub**. In order for this command to be fulfilled, the NetBIOS name of the remote host must first be resolved into its IP address so that it can be contacted on the network, and this is done using NetBIOS name resolution.

Notes

Note that NetBIOS name resolution is not confined only to TCP/IP networks—on Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX) networks, NetBIOS over IPX (NBIPX) resolves NetBIOS names to IPX addresses.

NetBIOS names are also supported by Windows 2000, Windows XP, and Windows .NET Server, but only for interoperability with some Windows NT machines. Windows 2000, Windows XP, and Windows .NET Server use the Domain Name System (DNS) instead for naming hosts and name resolution on a network. Note that a different series of steps is used to resolve host names on a network that uses the Domain Name System (DNS)—this process is usually called host name resolution.

See Also: *Domain Name System (DNS), host name resolution, MAC address, Nbtstat, NetBIOS, NetBIOS name, NetBIOS Name Server (NBNS), NetBIOS over TCP/IP (NetBT), NetBIOS over TCP/IP node types, Net commands*

NetBIOS Name Server (NBNS)

A server responsible for maintaining a list of mappings between NetBIOS computer names and network addresses for a network that uses NetBIOS as its naming service.

Overview

On networks that support NetBIOS (such as Microsoft Windows NT–based networks), NetBIOS name servers (NBNSs) are employed to register NetBIOS names and perform NetBIOS name resolution. Normally, when computers boot up on such a network, they register themselves with the NBNS by providing it with their computer names and network addresses. Then, when one computer needs to communicate with another, the first computer queries the NBNS for the network address of the remote computer.

NBNSs operate in a NetBIOS over TCP/IP (NetBT) mode called p-node, which is defined in RFCs 1001 and 1002. On a Windows NT–based network, you can configure a Windows NT server to assume the role of an NBNS by installing and configuring the Windows Internet Naming Service (WINS) on the machine. WINS servers can also be used on Windows 2000–based networks, but only for communication with some Windows NT computers—the main naming scheme for Windows 2000 networks is the Domain Name System (DNS).

Notes

On networks too small to justify using an NBNS, NetBIOS names can also be resolved by using broadcasts, but this wastes more network bandwidth than using a dedicated NBNS. On such small networks, using Lmhosts files may be preferable to deploying an NBNS.

See Also: *Domain Name System (DNS), NetBIOS, NetBIOS name, NetBIOS name resolution, NetBIOS over TCP/IP (NetBT), NetBIOS over TCP/IP node types, Windows Internet Name Service (WINS)*

NetBIOS over TCP/IP (NetBT)

NetBIOS session-layer protocol running over Transmission Control Protocol/Internet Protocol (TCP/IP).

Overview

NetBIOS over TCP/IP (NetBT) provides NetBIOS session management and naming functions such as NetBIOS name discovery, resolution, renewal, and release. In order to utilize NetBT effectively, a

NetBIOS name server (NBNS) is required to centrally manage name processes, such as NetBIOS name registration. Using the Windows Internet Naming Service (WINS), a Windows NT server can fill the role of such an NBNS and facilitate network communications on a routed TCP/IP internetwork. WINS servers are essential on such internetworks to enable the NetBIOS client/server interface to function since broadcast-based name registrations are not normally forwarded by routers to remote subnets.

Notes

In Windows NT, the Server, Workstation, NetLogon, Browser, and Messenger services interact with NetBT using the Transport Driver Interface (TDI).

See Also: *NetBIOS, NetBIOS name, NetBIOS name resolution, NetBIOS Name Server (NBNS), NetBIOS over TCP/IP node types, Windows Internet Name Service (WINS)*

NetBIOS over TCP/IP node types

Different ways of configuring NetBIOS-enabled nodes to perform naming functions.

Overview

The NetBIOS node type of a computer supporting NetBIOS (such as a Microsoft Windows NT machine) determines exactly how NetBIOS naming functions such as name discovery, registration, and release are implemented by that machine. In particular, such naming functions can be performed by broadcast, by a NetBIOS Name Server (NBNS), or by both methods attempted in either order. The NetBIOS node type thus specifies both which methods are used and the order in which they are used.

The common NetBIOS over TCP/IP node types are listed in the following table.

NetBIOS over TCP/IP Node Types

Node Type	*Method (in the Order Applied)*	*Comments*
B-node (broadcast)	Broadcast only	Uses NetBIOS name queries for name registration and name resolution. Typically not forwarded by routers, so limited to local subnet. Can create excessive traffic in large networks.
P-node (peer-to-peer)	NBNS only	Uses NBNS, which is a single point of failure for NetBIOS naming functions.
M-node (mixed)	Broadcast NBNS	A combination of B-node and P-node. Uses broadcast by default. If unable to resolve, uses NBNS.
H-node (hybrid)	NBNS Broadcast	A combination of P-node and B-node. Uses NBNS by default. Default node type for Microsoft clients if an NBNS is configured on the network.
Microsoft enhanced B-node	NetBIOS name cache Broadcast Lmhosts file	An enhanced broadcast that utilizes the Lmhosts file. Default node type for Microsoft clients if no NBNS is configured on the network.

See Also: *NetBIOS, NetBIOS name, NetBIOS name resolution, NetBIOS Name Server (NBNS), NetBIOS over TCP/IP (NetBT), Windows Internet Name Service (WINS)*

NetBIOS scope ID

A character string appended to a NetBIOS name of a host that identifies the host as belonging to a specific group.

Overview

On Microsoft Windows NT–based networks you can use NetBIOS scope IDs to segment the flat NetBIOS namespace into a series of smaller subspaces. Two hosts can then communicate only if they have the same NetBIOS scope ID and thus belong to the same subspace. The total length of a NetBIOS name plus scope ID cannot exceed 256 characters. Note that the topology of NetBIOS subspaces does not have to match the physical topology of the network or the logical topology of subnets on a Transmission Control Protocol/Internet Protocol (TCP/IP) internetwork.

Uses

You might configure NetBIOS scope IDs if you wanted to isolate a particular subset of computers on your network from the rest of the network and allow them to communicate only among themselves. To configure a NetBIOS scope ID on a computer running Windows NT, use the WINS Address tab of the TCP/IP property sheet. In Windows 2000, you must manually modify an entry in the registry to accomplish this.

Notes

Actually using NetBIOS scope IDs is not recommended. For example, if trust relationships are configured between several Windows NT domains, using NetBIOS scope IDs can break the effect of these trust relationships by preventing pass-through authentication between trusted domain controllers that have different scope IDs. Furthermore, in a single-domain environment, if the scope ID of a workstation is different from that of the domain controllers, users will not be able to log on to the network at that workstation.

See Also: *domain (DNS), NetBIOS, NetBIOS name*

NetBT

Stands for NetBIOS over TCP/IP, the NetBIOS session-layer protocol running over Transmission Control Protocol/Internet Protocol (TCP/IP).

See: *NetBIOS over TCP/IP (NetBT)*

Net commands

A family of commands that can be utilized at the Microsoft Windows command prompt for managing certain aspects of networking.

Overview

These commands are summarized in the following tables. For more information about a specific command (such as net accounts), type **net accounts /?** or **net help accounts** at the command prompt. For additional information on the Net commands for Windows NT, Windows 2000, Windows XP, and Windows .NET Server, refer to Windows Help.

Net Commands for Windows NT, Windows 2000, Windows XP, and Windows .NET Server Platforms

Command	*Description*
Net Accounts	Update the accounts database, modify account and password settings, or display account information
Net Computer	Add or remove computers from the domain
Net Config	Display or change the setting for the Server or Workstation service
Net Continue	Restart a paused Windows service
Net File	Display a list of open shared files and file locks; this command can be used to close a shared file and remove a file lock
Net Group	Add, modify, delete, or display global group account information in the domain directory database
Net Help	Obtain a list of net commands or get help for a specific net command
Net Helpmsg	Obtain further information about Windows network messages
Net Localgroup	Add, modify, delete, or display local group account information in the local or domain directory database
Net Name	Add, delete, or display the names or aliases that the Messenger service recognizes as representing your computer
Net Pause	Pause a Windows service to allow users to disconnect before stopping it

(continued)

Net Commands for Windows NT, Windows 2000, Windows XP, and Windows .NET Server Platforms *continued*

Command	*Description*
Net Print	Display and manage jobs in a print queue
Net Send	Send a message to a user or computer over the network
Net Session	Display the list of currently connected sessions on the local computer
Net Share	Create, delete, or display shared resources
Net Start	Display a list of running services or start a specific stopped service
Net Statistics	Display statistics about the Server and Workstation services
Net Stop	Stop a specified Windows service that is currently running
Net Time	Synchronize the computer's clock with that of another computer or domain or display the time for a computer or domain
Net Use	Connect or disconnect to shared resources or display information about connections
Net User	Add, modify, delete, or display user account information in the local or domain directory database
Net View	Display a list of computers in the domain or display the shared resources available on a specific computer

Net Commands for Windows 95, Windows 98, and Windows Millennium Edition (Me) Platforms

Command	*Description*
Net Config	Display current computer settings
Net Diag	Run the Microsoft Network Diagnostic program to display diagnostic information about a computer
Net Help	Obtain a list of net commands or get help for a specific net command or error message
Net Init	Load protocol and network-adapter drivers without binding them to Protocol Manager
Net Logoff	Break connections to network resources
Net Logon	Log on to a domain
Net Password	Change logon password
Net Print	Display and manage jobs in a print queue
Net Start	Start services
Net Stop	Stop services
Net Time	Synchronize the computer's clock with that of another computer or workgroup or display the time for a computer or workgroup
Net Use	Connect or disconnect to shared resources or display information about connections
Net Ver	Display information about workgroup redirector
Net View	Display a list of computers in the workgroup or display the shared resources available on a specific computer

Notes

Some of these commands produce more than one screen of output at the command prompt. To prevent information from scrolling off the screen, pipe the output through More—for example, type **net help accounts | more.**

See Also: *command prompt*

.NET Enterprise Servers

A set of servers that facilitate the deployment, implementation, and management of the Web services foundational to the Microsoft .NET platform.

Overview

The .NET Enterprise Servers include

- **Application Center 2000:** Used for deploying and managing Web services and applications across the enterprise
- **BizTalk Server 2000:** Uses Extensible Markup Language (XML) and Simple Object Access Protocol (SOAP) to enable the exchange of information between business partners

- **Commerce Server 2000:** Facilitates the development of Web applications for e-commerce
- **Content Management Server 2001:** Facilitates simplified management, rapid deployment, and personalization of Web content on intranets or extranets
- **Exchange Server 2000:** Provides the underlying support for messaging and for building collaborative Web-based workflow applications
- **Host Integration Server 2000:** Enables access to data stores on mainframe computing platforms
- **Internet Security and Acceleration Server 2000:** Enhances enterprise security through firewall and Web caching services
- **Mobile Information Server 2001:** Enables wireless access to enterprise data from mobile clients
- **SharePoint Portal Server:** Provides the ability to create intranet portals which facilitate the sharing of information stored in a variety of formats across the enterprise
- **SQL Server 2000:** Standard platform for relational data storage that supports XML-based access to data

For More Information

Find out more about Microsoft's .NET Enterprise Servers at *www.microsoft.com/servers*.

See Also: *Application Center, BizTalk Server 2000, Commerce Server 2000, Exchange Server, Host Integration Server, Internet Security and Acceleration Server (ISA Server), Mobile Information Server, .NET platform, SQL Server*

.NET experience

A term representing a user's interaction with Web services based upon the Microsoft .NET platform.

Overview

The term *experience* is often used in modern-day programming parlance to describe the interaction between the user and the user interface for an application. A .NET experience is similar to user interaction with traditional client/server applications, but with several enhancements. Specifically, .NET experiences are

- **Location-independent:** .NET experiences can be accessed both offline (for example, at home from a PC) or online (for example, from a cell phone or wireless Personal Digital Assistant [PDA]).
- **Personalized:** .NET experiences store user profile information that simplifies user interaction regardless of the device being used or services being accessed.
- **Targeted:** A single .NET experience can manifest itself differently to the user depending on whether the user is employing a PC, cell phone, Pocket PC, Tablet PC, game console, or some other smart device.

See Also: *.NET platform*

.NET Framework

A developer environment for building, deploying, and running Web services and applications. The .NET Framework is a key piece of Microsoft's .NET platform.

Overview

The .NET Framework comprises three pieces:

- **Common Language Runtime (CLR):** Supports the execution of code written in any programming language (the .NET Framework is language-neutral).
- **Framework Classes:** Self-contained classes that do not require separate type libraries.
- **ASP.NET and ADO.NET:** The .NET versions of ASP+ and ADO+. ASP.NET provides programming models for building Web Forms and Web Services. ADO.NET provides classes for accessing Extensible Markup Language (XML) documents in relational data stores.

The .NET Framework is designed to run on a variety of platforms, including Microsoft Windows 95, Windows 98, Windows NT 4, Windows Millennium Edition (Me), Windows 2000, Windows XP, and Windows .NET Server. There is also a version called the .NET

Compact Framework that is designed to run on Windows CE, and embedded Windows to support key .NET functionality on cell phones, Personal Digital Assistants (PDAs), Tablet PCs, and other smart devices.

Notes

Developers can use the .NET Framework to create and deploy not only XML-based .NET Web services but also traditional COM+ applications. The .NET Framework resembles Windows Distributed interNet Applications Architecture (Windows DNA) in some ways, but it employs a more loosely coupled distributed component architecture.

See Also: *ADO.NET, ASP.NET, .NET platform*

NetLogon Share

An administrative share used by Microsoft Windows NT domain controllers.

Overview

The NetLogon share maps to the %SystemRoot%\system32\repl\import\scripts directory and is used for the following purposes:

- Storing logon scripts (for example, Logon.bat).
- Storing system policies (Ntconfig.pol or Config.pol files).
- Storing a default user profile for users (which must be stored in a subdirectory called Default User). If a user without a local profile on his or her workstation or a server-based roaming profile logs on, the default user profile is used instead.

When a client is authenticated on a Windows NT domain, the final step in the logon process involves connecting to the NetLogon share and downloading or applying any of the items in the preceding list.

See Also: *domain controller, Windows NT*

.NET platform

Microsoft Corporation's new Extensible Markup Language (XML) Web services platform for building integrated service-oriented applications to meet the needs of today's Internet businesses.

Overview

Microsoft .NET aims to leverage several important technology shifts in today's economy:

- The increasing availability of low-cost broadband Internet access for home and business, which makes delivery of fat content such as streaming video a practical reality.
- The proliferation of new computing platforms such as handheld Personal Digital Assistants (PDAs), Tablet PCs, portable MPEG (Moving Pictures Experts Group) players, and Web-enabled cell phones, which are making the computing experience ever more pervasive in today's society.

The .NET platform is designed to help developers build distributed applications that leverage the power of Web for a wide variety of end-user devices. To facilitate this, the .NET platform consists of five components:

- **Tools for developers:** Microsoft Visual Studio .NET, the latest incarnation of Microsoft's popular developer platform, provides language-independent tools and an integrated development environment for programmers to create both.NET experiences for end-user devices and the underlying Web services that provide the foundation for the realization of these experiences. Also key to developers is the .NET Framework, which provides the programming interfaces used for developing the Web services that are at the heart of the .NET vision. The foundation of these new tools is XML, an open standard created and managed by the World Wide Web Consortium (W3C) that is used to facilitate sharing of data and integration of software across different platforms. Other standards supported by .NET include Simple Object Access Protocol (SOAP) and Universal Description, Discovery, and Integration (UDDI) protocols.
- **.NET Enterprise Servers:** The essential underpinning for the .NET platform. These servers, including the Microsoft Windows .NET Server, are designed to aggregate, integrate, and deliver .NET Web services, providing a consistent and compelling user experience across all levels of devices. The .NET Enterprise Servers include familiar ones such as Exchange Server

2000 and SQL Server 2000, which have been partially XML-enabled and provide the underlying "plumbing" for Web services to function. Other .NET servers, such as Application Center 2000 and BizTalk Server 2000, carry this aggregation and integration of Web services to a higher level using special languages such as XLANG and SOAP.

- **Building block services:** These services are designed to ensure that the .NET end-user experience is simple, consistent, and compelling. Building block services perform functions such as managing identities, providing notifications, and providing schematized storage that are necessary to enable the user experience to be consistent across different services, applications, devices, and platforms. Microsoft Corporation is developing a core set of building block services, but many more will be developed by third-party partners for corporate use.
- **Devices:** An important part of the .NET vision is that Microsoft is developing client and device software that can bring the rich .NET experience to users through a variety of smart devices such as Web-enabled cell phones, Pocket PCs, Tablet PCs, and other devices. Microsoft is developing .NET device software for a number of platforms, including Windows XP, Windows 2000, Windows Millennium Edition (Me), Windows CE, and embedded Windows.
- **User Experiences:** Microsoft aims to provide a powerful and compelling user experience through .NET. These experiences will leverage the flexibility of XML Web services together with the power of broadband business, residential, and wireless Internet access to provide a user experience that is secure, simple, consistent, and personalized.

For More Information

Microsoft expresses the heart of its .NET vision at *www.microsoft.com/net*.

See Also: *ASP.NET, building-block services, .NET Enterprise Servers, .NET experience, .NET Framework, XML*

netstat

A Transmission Control Protocol/Internet Protocol (TCP/IP) command that displays current TCP/IP connectivity status and statistics.

Overview

Netstat can be run from the Microsoft Windows 2000 command prompt to view current TCP/IP protocol statistics and connections for the local computer. You can also use it to view statistics on a per-protocol basis for Transmission Control Protocol (TCP), User Datagram Protocol (UDP), Internet Protocol (IP), and Internet Control Message Protocol (ICMP).

In particular, netstat provides information on

- IP addresses and port numbers of TCP/IP connections, including client and server connections. Either host names or IP addresses can be displayed.
- Ethernet statistics, including bytes sent and received, directed and broadcast frames sent and received, discards, and errors.
- The routing table for the local machine.

Examples

To display all connections and listening ports for both TCP and UDP, type **netstat –a** at the command prompt.

See Also: *Transmission Control Protocol/Internet Protocol (TCP/IP)*

NetWare

The popular network operating system from Novell Networks.

Overview

Novell NetWare is a network operating system developed in the early 1980s that has been widely used in local area networks (LANs). It began as a platform for LAN-based file and print services and has evolved into a platform suitable for enterprise networking and e-commerce. The current version of NetWare is 6.

History

NetWare initially became popular in its NetWare 2.*x* and 3.*x* versions, which proved remarkably stable and easy to administer using text-based menu-driven MS-DOS–based utilities such as Syscon, Filer, Fconsole, Pconsole, and Monitor. Security on these platforms was based on the NetWare bindery, and networking was supported by a proprietary suite of protocols based on Internetwork Packet Exchange/ Sequential Packet Exchange (IPX/SPX) developed by Novell.

NetWare 4 provided a more scalable solution for the enterprise by introducing Novell Directory Services (NDS), a hierarchical directory service that replaced the bindery of earlier versions. NDS enabled users and applications to easily locate and access shared resources anywhere on a Novell network regardless of their location. NetWare 4 supported single-network logon, in which users log on once to the NDS tree, are authenticated, and can then find and access all resources on the network for which they have appropriate permissions. NetWare 4 also supported industry-standard Internet Protocol (IP) by encapsulating IP datagrams within IPX packets. The Windows-based administration tool Nwadmin also replaced most of the menu-driven MS-DOS–based administration tools and enabled managing a NetWare 4-based network from a single console.

NetWare 5 included support for native IP, replacing the legacy IPX/SPX used in earlier versions, plus related Internet protocols such as Dynamic Host Configuration Protocol (DHCP) and Domain Name System (DNS). NetWare 5 also included a new multiprocessing kernel with support for virtual memory.

The latest version, NetWare 6, includes a number of enhancements, including Internet file and printing services, 32-way symmetric multiprocessing (SMP), and 32-way clustering support.

Notes

Microsoft Windows 2000 includes a number of protocols and services that support interoperability between Microsoft Windows and Novell NetWare platforms, and migration from NetWare to Windows 2000. These tools include

- NWLink IPX/SPX-Compatible Transport
- Gateway Service for NetWare (GSNW)
- Client Services for NetWare (CSNW)
- File and Print Services for NetWare (FPNW)
- Migration Tool for NetWare

For More Information

Visit Novell online at *www.novell.com.*

See Also: *Client Services for NetWare (CSNW), File and Print Services for NetWare (FPNW), Gateway Service for NetWare (GSNW), Internet Protocol (IP), NetWare protocols, Novell Directory Services (NDS)*

NetWare Core Protocol (NCP)

A legacy NetWare protocol.

Overview

NetWare Core Protocol (NCP) operates at the presentation layer protocol of the Open Systems Interconnection (OSI) reference model. NCP enables sharing of file and print services on legacy NetWare 2.*x* and 3.*x* platforms and performs various other accounting and security functions.

NCP functions by using information learned through Service Advertising Protocol (SAP) broadcasts. It employs Internetwork Packet Exchange (IPX) as its underlying transport and requires acknowledgment of every packet transmitted.

NCP is the analog of Server Message Block (SMB), a protocol used for similar purposes in Microsoft Windows platforms.

See Also: *Internetwork Packet Exchange (IPX), NetWare protocols, Open Systems Interconnection (OSI) reference model, Server Message Block (SMB)*

NetWare Directory Services (NDS)

Old name for Novell Directory Services, the directory services platform from Novell Networks.

See: *Novell Directory Services (NDS)*

NetWare protocols

A suite of protocols developed for legacy versions of Novell NetWare.

Overview

The networking architecture of NetWare evolved from the earlier Xerox Network System (XNS) created in the late 1970s. NetWare 2.*x* and 3.*x* used a proprietary suite of networking protocols that mapped to the upper five layers of the Open Systems Interconnection (OSI) reference model. The more important NetWare protocols included

- **Internetwork Packet Exchange (IPX):** A network layer protocol used to route packets across a network. IPX is a connectionless protocol that identifies nodes on a network using a two-part address. The host portion of an IPX address is just the MAC address of the network interface on the host, and the network portion of the address is arbitrarily assigned by the administrator to uniquely identify each portion of the network. IPX also performs encapsulation for the data-link layer using one of four schemes: 802.2 (Novell proprietary), 802.3 (IEEE), Ethernet II, and Subnetwork Access Protocol (SNAP). IPX is the analog of Internet Protocol (IP), part of the Transmission Control Protocol/Internet Protocol (TCP/IP) suite.
- **Sequenced Packet Exchange (SPX):** A transport layer protocol that ensures reliable delivery of data. SPX performs functions such as delivering acknowledgments of successful delivery and performing error checking. SPX is the analog of Transmission Control Protocol (TCP/IP), also part of TCP/IP.
- **NetBIOS:** A session layer protocol that performs name registration and discovery functions and supports interoperability with other NetBIOS-enabled operating systems, such as Microsoft Windows NT.
- **NetWare Core Protocol (NCP):** A presentation layer protocol that enables sharing of file and print services and performs accounting and security functions. NCP uses information learned through SAP broadcasts and employs IPX as its underlying transport. NCP is the analog of Server Message Block (SMB), a protocol used in Microsoft Windows platforms.
- **Service Advertising Protocol (SAP):** Enables NetWare servers to advertise themselves and their shared resources as present on the network in a fashion similar to the Computer Browser services of the Windows platform. This enables NetWare clients to find and access resources on these servers. SAP employs broadcasts issued every 60 seconds. In versions 4 and higher of NetWare, SAP is no longer required and is replaced by Novell Directory Services (NDS).
- **Get Nearest Server (GNS):** A protocol used when a NetWare client boots to locate NetWare servers on the local network.

There are also several routing protocols specific to legacy versions of NetWare. These routing protocols are used for communication between routers, in contrast to the above protocols, which are used for communication between hosts. Examples of NetWare routing protocols include

- **Novell Routing Information Protocol (IPX RIP):** This is a distance vector routing protocol that is a close analog of Internet Protocol Routing Information Protocol (IP RIP), usually just called Routing Information Protocol (RIP).
- **NetWare Link Services Protocol (NLSP):** This is a link state routing protocol derived from the Intermediate System to Intermediate System (IS-IS) routing protocol, and was developed in response to the lack of scalability of IPX RIP to large internetworks.
- **Enhanced Interior Gateway Routing Protocol (EIGRP):** This protocol supports both IPX and IP.

Notes

In addition to these original NetWare protocols, NetWare version 4 also supports Internet Protocol (IP) encapsulation of IPX/SPX packets, which means that IPX datagrams can be encapsulated within User Datagram Protocol (UDP) packets for transmission over TCP/IP internetworks. NetWare 5 and later now have native support for IP, and SAP has been replaced by Service Location Protocol (SLP), which uses IP as its underlying transport.

See Also: *Enhanced Interior Gateway Routing Protocol (EIGRP), Internetwork Packet Exchange (IPX), MAC address, NetBIOS, NetWare, NetWare Core Protocol (NCP), Open Systems Interconnection (OSI) refer-*

ence model, routing, Routing Information Protocol (RIP), Service Advertising Protocol (SAP), Transmission Control Protocol/Internet Protocol (TCP/IP), User Datagram Protocol (UDP)

network

A group of computers that can communicate with one another.

Overview

Networks harness the power of computers by allowing them to work together. By creating a network, users can share resources with one another and send messages to one another. Networks also allow applications to be distributed across multiple computers. Networks provide applications and users with many benefits over standalone (independent) computers, including

- Distributed processing capability
- Enhanced storage capability
- Centralized management of security and access to resources
- Greater scalability, robustness, and redundancy

For computers to be connected into a network, they require three things:

- **Network client:** Software running on the computer that makes the computer network-aware (able to be networked to other computers and to communicate with them). Operating systems such as Microsoft Windows are sometimes called network operating systems because they have built-in network client software and are thus intrinsically network-aware. Older operating systems such as Microsoft Disk Operating System (MS-DOS) were not networkable by themselves and required additional software such as the Microsoft Network Client 3 for MS-DOS in order to communicate on a network.
- **Network interface card (NIC):** A card inserted into a slot on the computer's motherboard. The card provides a physical connection and the necessary electronics in order for a network cable to be connected to the computer. Other forms of NICs include Personal Computer Memory Card International Association (PCMCIA) cards for laptop computers and wireless access cards for wireless networking.
- **Network protocol suite:** A collection of protocols that control the exact steps which computers use when communicating over a network. An example is the Transmission Control Protocol/Internet Protocol (TCP/IP) suite, which includes Internet Protocol (IP), Transmission Control Protocol (TCP), Address Resolution Protocol (ARP), and Hypertext Transfer Protocol (HTTP). Each protocol within a network protocol suite has a specific function to support communication between computers on a network.

In addition to cables, NICs, and computers, most modern networks also require some kind of dedicated networking device in order to concentrate (join together) the cabling into an actual network. These devices fall into two general categories:

- **LAN devices:** Used to build local area networks (LANs) and include hubs, bridges, routers, and switches.
- **WAN devices:** Used to connect LANs using wide area network (WAN) services from a telecommunications service provider. Examples include routers, access servers, channel service unit/data service units (CSU/DSUs), multiplexers, Frame Relay Access Devices (FRADs), analog modems, Integrated Services Digital Network (ISDN) terminal adapters, and a host of other devices depending on the telecom service employed.

Together with the cabling, these LAN and WAN devices constitute the infrastructure of a company's network.

Types

Networks can be classified in many ways. For example, they can be distinguished according to

- **Administration:** Networks can be private networks (owned and operated by a company or organization) or public networks (shared or leased to companies by a service provider). The Internet is a collection of public networks connected together and running the TCP/IP protocol suite. Not all public networks are part of the Internet, however—for example, AT&T's Frame Relay network is a telecommunications network that companies can lease and use to connect networks located in geographically separated regions.

- **Architecture:** This describes the way signals are transmitted across the network. Examples of common network architectures include Ethernet (including Fast Ethernet and Gigabit Ethernet), Token Ring, Fiber Distributed Data Interface (FDDI), Asynchronous Transfer Mode (ATM), and even serial transmission using RS-232, V.35, and other interfaces.
- **Physical size:** Depending on the number of computers involved and the location of these machines, networks can be variously labeled as local area networks (LANs), campus area networks (CANs), metropolitan area networks (MANs), or wide area networks (WANs). LANs and CANs are usually owned and managed by a single company or organization, MANs are typically owned and managed by telcos and other service providers and leased to companies to connect their LANs, and WANs typically consist of LANs owned and operated by one or more organizations and connected using leased services owned by another organization.
- **Protocol:** Networks use a variety of different protocols, that is, methods for packaging information into frames, packets, or cells for transmission across a network. Common examples of networking protocols include TCP/IP, Internetwork Packet Exchange/Sequential Packet Exchange (IPX/SPX), and Systems Network Architecture (SNA).
- **Security:** Networks vary depending on how clients are authenticated and how resources are secured. Two common ways of implementing this include the workgroup, where every computer controls its own security, and the domain, where a special server called a domain controller manages security for the entire network. Both the workgroup and the domain model are supported by Windows 2000, Windows XP, and Windows .NET Server.
- **Topology:** The term *topology* refers to the manner and complexity of interconnections between computers on a network. Possible network topologies include the bus topology, star topology, ring topology, and mesh topology. Networks can also be described as either flat (using one of the topologies listed previously) or hierarchical (using combinations of different topologies or multiple levels of a single topology).
- **Media:** Computers can be physically connected together in various ways including using coaxial cabling, twisted-pair cabling, and fiber-optic cabling. Computers can also be networked without wires, an approach called wireless networking.

N

Notes

In TCP/IP networking, the term *network* is sometimes used to refer specifically to a group of hosts having the same network ID. Several such networks can then be connected using routers to form a larger network called an internetwork. Individual networks within an internetwork are usually referred to as subnets or subnetworks.

See Also: *analog modem, Asynchronous Transfer Mode (ATM), backbone, bridge, bus topology, cabling, campus area network (CAN), coaxial cabling, domain controller, domain (DNS), Ethernet, Ethernet switch, Fast Ethernet, Fiber Distributed Data Interface (FDDI), fiber-optic cabling, Gigabit Ethernet (GbE), hub, infrastructure, Internet, internetwork, ISDN terminal adapter, local area network (LAN), mesh topology, metropolitan area network (MAN), multiplexer (MUX), network architecture, network client, network design, network ID, network management, network operating system (NOS), network troubleshooting, ring topology, router, serial transmission, star topology, subnet, Systems Network Architecture (SNA), Token Ring, Transmission Control Protocol/Internet Protocol (TCP/IP), twisted-pair cabling, wide area network (WAN), wireless networking, workgroup*

Network Access Point (NAP)

A point where Internet traffic is exchanged between Internet service providers (ISPs).

Overview

Network Access Points (NAPs) are points where sections of the Internet's high-speed backbone are connected together in order to exchange traffic between ISPs—typically, this means connections between Tier 1 ISPs (large backbone providers) and Tier 2 ISPs (regional providers). Since the global portion of the Internet's backbone consists of long-haul fiber-optic cabling and high-speed Asynchronous Transfer Mode (ATM) switching equipment owned and is operated by inter-exchange carriers (IXCs) such as AT&T, Sprint Corporation, and MCI WorldCom, such NAPs are usually located where these carriers interconnect their long-haul lines together, and they contain high-speed switching facilities for transferring traffic from one carrier's lines to another's.

In the Internet's early days, the National Science Foundation established four different NAPs in Chicago, New York, San Francisco, and Washington, D.C. With the growth of the Internet and the changing landscape of telecommunication companies, many more NAPs have been created. These include the well-known "MAE West" in San Jose, California, and "MAE East" in Washington, D.C., both of which are operated by MCI WorldCom.

To lessen the traffic burden on the Internet's backbone, major ISPs can connect their services directly to a NAP in the form of a "peering arrangement," whereby traffic that needs to move between two ISPs connected to the same NAP can move directly from one ISP to the other instead of having to traverse the Internet's backbone.

See Also: *inter-exchange carrier (IXC), Internet service provider (ISP)*

network access server (NAS)

The server at the Internet service provider (ISP) end of a dial-up connection.

Overview

The term *network access server (NAS)* is a general name for the server at an ISP that supports Point-to-Point Protocol (PPP) connections for dial-up clients. The NAS is typically responsible for authenticating the dial-up client's credentials and negotiating flow control and error correction. The NAS is often a general-purpose server running special software such as Microsoft Windows 2000's Internet Connection Services. Alternatively, a NAS may be a standard router that supports PPP.

The NAS can sometimes also be used to establish tunnels through the Internet for virtual private networking (VPN), for example, by using Point-to-Point Tunneling Protocol (PPTP).



Network access server (NAS). *How a NAS works.*

Another name for a NAS is a point of presence (POP) server.

See Also: *Internet service provider (ISP), Point-to-Point Protocol (PPP), Point-to-Point Tunneling Protocol (PPTP), router, virtual private network (VPN)*

network adapter card

Usually called network interface card, a device that allows a computer to communicate on a network.

See: *network interface card (NIC)*

network address translation (NAT)

A method of substituting one Internet Protocol (IP) address for another.

Overview

Network address translation (NAT) is a mechanism for translating the IP addresses of hosts on one network into IP addresses belonging to a different network. NAT is usually used at the boundary of two networks, especially where a private network such as a corporate network meets a public network such as the Internet.

The motivation behind the creation of NAT is that the number of available global (public) registered IP addresses on the Internet is rapidly being depleted. NAT works around this problem by

- **Address reuse:** NAT allows multiple private networks to use the same network IDs (same range of IP addresses). Private networks (networks not directly connected to the Internet) can use any range of IP addresses but usually employ those addresses specially reserved by the Internet Assigned Numbers Authority (IANA) for private network usage, such as 10.0.0.0 through 10.255.255.255 (or 10/8 in classless interdomain routing [CDIR] notation), 172.16.0.0 through 172.32.255.255 (or 172.16/12), and 192.168.0.0 through 192.168.255.255 (or 192.168/16). Addresses in this range are designated by IANA as nonroutable addresses, and networks using these addresses cannot directly connect to the Internet using a router. Instead, they need a router or access device that supports NAT so that these nonroutable addresses can be translated into public addresses for routing over the Internet.
- **Address multiplexing:** NAT allows IP addresses of multiple hosts on a private network to be exposed to the Internet as a single public IP address. This allows the addresses of hosts on a private network to be hidden from the outside world, improving security on the network. Address multiplexing is sometimes referred to as network address port translation (NAPT).

NAT is defined in RFC 1631, and the IP addresses reserved by IANA for use on private networks is defined in RFC 1918.

Uses

NAT has several uses in enterprise networks:

- NAT allows corporate networks using RFC 1918 private network addresses to access the Internet through NAT-enabled routers and access servers. NAT also enables older enterprises that deployed addresses noncompliant with RFC 1918 to connect to the Internet.
- NAT allows corporate networks to hide the address topology of their networks from the Internet. NAT is not a replacement for firewalls, though, as in itself it performs no address or port filtering, just translation. In fact, NAT is usually available as an additional feature on most firewall products today.
- Often two private networks need to join together as a result of a merger. If both networks are using the same RFC 1918 addresses, NAT enables the networks to be united without the needed of readdressing one of them.

Implementation

In a typical NAT scenario, a NAT-enabled router connects an internal corporate network with the Internet. The internal network has multiple IP hosts using private network IP addresses, while the router has a similar private IP address on its near-side (internal) interface and a public (global) address on its far-side (internal) interface. NAT operates by examining traffic that passes through the router and building a table that maps the connections between hosts inside the network and hosts outside on the Internet. For each connection the table contains

- Original IP address and port number of source address
- Original IP address and port number of destination address
- Translated IP address and port number of source address
- Translated IP address and port number of destination address
- Transmission Control Protocol (TCP) and Internet Control Message Protocol (ICMP) sequence numbers

All packets that enter the network through the router have their addresses translated, and all packets leaving the network have their addresses translated back again.

Implementing NAT on a router or firewall thus involves creating and configuring a NAT table containing these private/public IP address mappings. These address mappings can either be

- **Manually created:** A static NAT table essentially consists of a series of manually created NAT rules that specify how IP addresses will be translated. Static NAT mappings are always one-to-one mappings between actual and translated addresses. For example, a typical static NAT rule might be equivalent to the statement, “Translate all IP addresses belonging to the network 176.43.8.*z* to IP addresses in the form 145.5.133.*z* with the subnet mask 255.255.255.0 used for both networks.” This rule results in the address 176.43.8.1 being mapped to 145.5.133.1, 176.43.8.2 being mapped to 145.5.133.2, and so on. This approach can be used, for example, when corporate networks with conflicting addresses need to be merged into one network. Static mappings are not very useful, however, for connections between private networks and the Internet due to the large number of possible connections to Internet hosts, which can make the NAT table grow excessively large thus degrading router performance.

or

- **Dynamically assigned:** NAT-enabled routers can often dynamically allocate IP addresses to hosts on the private network by selecting addresses drawn from a specified pool. Dynamic NAT mappings are also one-to-one mappings between actual and translated addresses. This process is similar to Dynamic Host Configuration Protocol (DHCP) and can be done either randomly or, more usually, on a round-robin basis. Each time a connection is formed between the external and internal networks, NAT assigns a different IP address from the pool to the internal host being connected to and address information in packets is modified accordingly.

Another popular form of dynamic NAT is called address overloading, masquerading, port address translation (PAT), or network address port translation (NAPT). In this situation all the IP addresses of the internal private network are hidden to outsiders, who can access only the single IP address of the interface exposed to the public network. Address overloading thus employs many-to-one mappings of IP addresses and is used when the number of internal addresses is greater than the available number of global addresses. Address overloading differs from standard NAT in that port numbers are also translated, not just IP addresses. For example, it is possible to multiplex many TCP connections through a single global IP address by assigning each connection a different port number. These numbers might be chosen, for example, from the range 61,000 through 65,096, which would allow up to 4096 simultaneous TCP connections through a single overloaded IP address. Address overloading is often used by firewalls and sometimes for load balancing Web servers.

Advantages and Disadvantages

NAT provides corporate networks with portability by eliminating the need for an organization to obtain globally unique IP addresses from its Internet service provider (ISP). Should an organization using global addresses need to change providers, this usually means obtaining new global addresses from the new provider and reconfiguring the network accordingly. With NAT, a company can use RFC 1918 private addresses for hosts on its corporate network, regardless of which ISP it is connected to the Internet through. And when changing ISPs, the only reconfiguration that would be required would be on the external interface of the company's router or firewall, which would need a new global address obtained from the new provider.

NAT also reduces cost for large corporate networks that need to connect to the Internet. This is because without NAT you would need to purchase a large block of unique IP addresses from your ISP in order to connect your network with the Internet, and such address blocks are sometimes scarce and therefore costly. Using NAT, however, only the far side (public interface) of your router or firewall needs a unique global IP address obtained from your ISP—within your network you can use RFC 1918 addresses because your private network is securely hidden from the outside world behind your NAT-enabled router firewall. And RFC 1918 addressing provides companies with access to address blocks as large as Class A (the 10/8 block) that can support millions of different hosts. Try obtaining a Class A from an ISP today if you think you need one—all Class A addresses have been assigned years ago, and only a few Class B addresses are still available.

NAT also helps to conserve the available pool of IPv4 addresses for the Internet, thus postponing the day when networks will need to be migrated to IPv6, a process that may be costly for large enterprises and will require considerable training of network professionals in use of the new protocol.

NAT's main disadvantage is that some protocols (and hence the applications that use them) simply do not work when IP addresses are translated. This particularly applies to protocols that involve

- **Encryption:** NAT does not work with protocols that use encryption schemes, and it can interfere with authentication systems that employ encryption as well. The main way of working around this issue with IPsec, a popular IP encryption protocol, is to use a router that supports both NAT and virtual private networking (VPN) to tunnel IPsec-encrypted packets through unencrypted IP packets that can be translated using NAT, but this is a complicated workaround that increases the router's processing load (and therefore the cost).
- **Embedded addresses:** NAT does not work with protocols that embed address and port information within the data portion of packets in a nonpredictable fashion.

The following table lists some of the protocols that have no trouble working with NAT, that can work with NAT as long as NAT devices are specially configured to support them, and that cannot easily work with NAT.

Support for NAT by Popular Internet Protocols

Work with NAT by Default	*Can Be Configured To Work with NAT*	*Cannot Easily Work with NAT*
Hyptertext Transfer Protocol (HTTP)	Domain Name System (DNS) name resolution	Boot Protocol (BOOTP)
Network File System (NFS)	File Transfer Protocol (FTP)	IPsec
Network Time Protocol (NTP)	H.323	Kerberos
Rlogin	Internet Control Message Protobol (ICMP)	Novell Directory Services (NDS) zone transfers
Telnet	IP multicast	Routing table updates
Trivial File Transfer Protocol (TFTP)	NetBIOS over TCP/IP (NetBT)	Simple Network Management Protocol (SNMP)

Another disadvantage of NAT is that end-to-end connectivity is effectively lost, which makes it more difficult to troubleshoot routing issues. Also, more costly routers may be required due to the additional processing overhead incurred by NAT. This processing overhead can introduce additional latency into internetworks using NAT-enabled routers, which can degrade time-sensitive applications such as Voice over IP (VoIP) and streaming multimedia presentations.

Marketplace

Many routers and access servers support NAT. In particular, Cisco System routers running Cisco's Internetwork Operating System (IOS) versions 11.2 and higher support NAT.

Microsoft Windows 2000 supports two ways of translating IP addresses for connecting a private network with the Internet:

- **Internet Connection Sharing (ICS):** Intended for small office/home office (SOHO) environments to provide access to the Internet through a designated Windows 2000, Windows XP, or Windows .NET Server computer. ICS automatically allocates addresses for internal hosts and only supports one interface to the internal network.
- **Routing and Remote Access Service (RRAS):** Provides a robust solution for larger corporate networks to access the Internet through multiple interfaces and using an addressing scheme chosen by the administrator. Windows 2000 or Windows .NET Server computers using the NAT feature of RRAS also function as DNS and Windows Internet Name Service (WINS) proxies for their connected subnets.

Prospects

NAT is essentially a workaround to extend the viability of the current IPv4 system by reducing the number of unique IP addresses required for connectivity to the Internet. NAT is viewed as a temporary solution until existing IPv4 networks can be fully migrated to the new IPv6 standard. However, the security advantages of using NAT-enabled firewalls has actually revitalized IPv4 to an extent and hence made migration to IPv6 seem less urgent to many network architects. Thus, while the Internet community presses for migration to IPv6, most large enterprises are content to use NAT and avoid the costs associated with a mass upgrade to the newer IPv6 protocol.

On the other hand, the proliferation of small mobile networked devices such as Web-enabled cell phones and Personal Digital Assistants (PDAs) may provide the impetus needed to push the wider networking community toward IPv6. The current IPv4 system lacks sufficient available addresses to support the millions of Internet-enabled mobile devices just over the horizon, and some countries such as Japan are already starting to roll out IPv6 on these devices. Workarounds such as NAT may still be in use for years, however, and gateways can be deployed for converting IPv6 to IPv4 addresses within the mixed IPv6/4 environment that is likely to characterize the global Internet of the next decade.

See Also: *classless interdomain routing (CIDR), Dynamic Host Configuration Protocol (DHCP), firewall, Internet, IP address, IPsec, routing, virtual private network (VPN)*

network architecture

Method used for packaging information for transmission over a network.

Overview

The term *network architecture* is used to describe the signaling, media access control method, and types of cabling for a particular type of computer network. Network architectures are different for local area networks (LANs), wide area networks (WANs), and networks that use terminals to connect to mainframes. Some common examples of LAN network architectures include

- **Ethernet:** This is by far the most popular LAN network architecture in use today. Ethernet, together with Fast Ethernet and Gigabit Ethernet (GbE), forms the basis of all types of business networks from the small office/home office (SOHO) to the enterprise.
- **Token Ring:** This architecture was developed by IBM and can support speeds of 4 and 16 megabits per second (Mbps). In the mid-1990s work was going on to push Token Ring to speeds up of 100 Mbps and higher, but these have been largely abandoned as Fast Ethernet and GbE have displaced Token Ring in most enterprises.
- **Fiber Distributed Data Interface (FDDI):** This architecture runs over fiber-optic cabling and was widely used in the late 1980s and early 1990s for backbones in campus area networks (CANs). It has largely been replaced by Fast Ethernet and GbE.

- **Asynchronous Transfer Mode (ATM):** This technology was envisioned as the successor to both Ethernet and FDDI, but its complexity and high cost have resulted in it being restricted to backbones in large enterprises. If current trends continue, GbE and the emerging 10G Ethernet standard are likely to displace ATM. ATM still retains a strong hold in the telcom market, however, where it is widely implemented in telco switching centers and for long-haul communications between inter-exchange carriers (IXCs).

Examples of LAN architectures that were once popular but are now rarely used include

- **ARCNET:** A legacy LAN architecture that was developed by Datapoint Corporation for small bus topology networks. It has almost disappeared, having been replaced by Ethernet.
- **100VG-AnyLAN:** A legacy architecture that was developed by AT&T and Hewlett-Packard and which has been largely replaced by Fast Ethernet and GbE.

The following are also sometimes considered LAN architectures, but they are really protocol suites that run on top of architectures such as Ethernet and Token Ring:

- **AppleTalk:** A legacy architecture developed by Apple Computer for its Macintosh platform that is essentially a protocol suite that can run on top of Ethernet, Token Ring, or FDDI networks. AppleTalk has largely been replaced by Transmission Control Protocol/Internet Protocol (TCP/IP) running on Ethernet.
- **Banyan VINES:** A legacy set of network protocols and applications developed by Banyan (now called ePresence) that runs on top of Ethernet and Token Ring.

See Also: *10G Ethernet, 100VG-AnyLAN, AppleTalk, ARCNET, Asynchronous Transfer Mode (ATM), backbone, cabling, campus area network (CAN), Ethernet, Fast Ethernet, Fiber Distributed Data Interface (FDDI), Gigabit Ethernet (GbE), inter-exchange carrier (IXC), local area network (LAN), media access control method, network, protocol, signaling, telco, Token Ring, topology, Transmission Control Protocol/ Internet Protocol (TCP/IP), wide area network (WAN)*

network attached storage (NAS)

A storage appliance that attaches directly to the network.

Overview

Traditional file servers use bus-attached disk storage and tend to be processor-bound machines unless unnecessary services and applications are disabled on the machine. Network attached storage (NAS) devices are essentially dedicated file servers that do nothing else. They are generally rack-mounted boxes containing a processor, memory, a Fast Ethernet or Gigabit Ethernet (GbE) network interface card (NIC), and disk drives either in the form of “just a bunch of disks” (JBOD) or a RAID 5 array for fault tolerance. NAS devices usually run an embedded operating system that is optimized for the sole task of rapid serving of files to clients on an Internet Protocol (IP) network.

Using a NAS device is typically as simple as plugging it in and connecting it to the network. Client machines on the network see the NAS device as just another file server. Management of NAS devices may be through a Web interface or from a management console that supports Simple Network Management Protocol (SNMP).

Storage capacity for NAS devices range from hundreds of gigabytes (GB) for those designed for the small to mid-sized business market to large boxes supporting multiterabyte (TB) storage for the large corporation.

Advantages and Disadvantages

NAS devices are generally more efficient file servers than traditional network file servers that use bus-attached storage. They are usually cheap, easy to set up, reliable, and they may sometimes be expandable to meet your growing storage demands. NAS devices typically support a wide range of clients including Microsoft Windows, Apple Macintosh, UNIX, and Linux. They are not as flexible as their larger cousin, storage area networks (SANs), which can be repartitioned when necessary, but they are much easier to manage. Some NAS devices also support advanced features such as load balancing, clustering, remote mirroring, and snapshot fault tolerance.

Marketplace

Vendors of NAS devices for the small office/home office (SOHO) and mid-sized businesses include Compaq Computer Corporation, Dell Computer, Hewlett-Packard, Maxtor Corporation, Network Appliance, Quantum Corporation, Snap Appliances, and Sun Microsystems. In the enterprise arena, EMC Corporation, Network Appliance, and Procom Enterprises are popular enterprise NAS vendors.

See Also: *Fast Ethernet, Gigabit Ethernet (GbE), network interface card (NIC), RAID, Simple Network Management Protocol (SNMP), storage, storage area network (SAN)*

network client

Software that makes a computer network-aware.

Overview

Network client software typically runs on a client computer, a desktop computer (workstation) used by one or more users. The purpose of network client software is to enable the client computer to communicate with other computers called servers in order to access network resources (applications, files, or services) located on these servers.

Without the appropriate client software, a workstation cannot access resources on a network server. For example, a Microsoft Windows client can access resources on a Windows-based server easily, but in order for the Windows client to access resources on a Novell NetWare server the client computer needs special NetWare-aware network client software installed on it.

Windows 2000, Windows XP, and Windows .NET Server include the following network clients:

- **Client for Microsoft Networks:** Enables the computer to participate in a Windows-based network and access resources on servers running different versions of Windows
- **Client Service for NetWare (CSNW):** Enables the computer to directly access resources on Novell NetWare servers

Note that in some Windows operating systems such as Windows 95, Windows 98, and Windows Millennium Edition (Me), the NetWare client is called Client for NetWare Networks instead of Client Service for NetWare. Some versions of Windows also include clients for legacy networks such as Banyan VINES.

See Also: *Client for Microsoft Networks, Client for NetWare Networks, Client Services for NetWare (CSNW), Microsoft Windows, NetWare, network, network operating system (NOS)*

Network Client 3 for MS-DOS

An add-on for Microsoft Disk Operating System (MS-DOS) that makes it a network-aware operating system.

Overview

Network Client enables MS-DOS–based workstations to access resources (such as shared folders, printers, and applications) on a Microsoft network using text-based Net commands. Using Network Client, an MS-DOS–based workstation can participate in either workgroups or domains.

Network Client must be installed on a machine that already has MS-DOS installed on it (you can create installation disks for Network Client using the Windows NT administrative tool called Network Client Administrator). Network Client has only limited support for Transmission Control Protocol/Internet Protocol (TCP/IP), but it does support the Dynamic Host Configuration Protocol (DHCP), Windows Internet Name Service (WINS), and Domain Name System (DNS).

Notes

If you cannot remember the syntax for Network Client commands when you use the MS-DOS command prompt, type **net** to load and open the Network Client pop-up command interface.

See Also: *Domain Name System (DNS), Dynamic Host Configuration Protocol (DHCP), Microsoft Disk Operating System (MS-DOS), Net commands, network, network client, Transmission Control Protocol/Internet Protocol (TCP/IP), Windows Internet Name Service (WINS)*

Network Control Protocol (NCP)

The portion of Point-to-Point Protocol (PPP) responsible for encapsulating network layer protocols.

Overview

Establishing communications between a PPP client and a PPP server involves several stages. The first step in establishing a PPP session is negotiating the actual connection. This is performed using Link Control Protocol (LCP), a PPP data-link layer protocol that is used for authenticating the client and performing callback, compression, and establishing a multilink connection if required. Once LCP has done its job, Network Control Protocol (NCP), another PPP data-link protocol that is actually a family of protocols, takes over to perform two functions:

- **Negotiating network layer attributes:** This involves selecting a network layer protocol understood by both the PPP client and server.
- **Encapsulating the network layer protocol:** This involves selecting the appropriate NCP protocol to encapsulate network layer packets for transmission over the connection. The table shows some of the common NCP protocols used for different network-layer protocols.

NCP Protocols for PPP

Network Layer Protocol	*NCP Protocol*	*Request For Comments (RFC)*
Internet Protocol (IP)	Internet Protocol Control Protocol (IPCP)	1332
Internetwork Packet Exchange (IPX)	Internetwork Packet Exchange Control Protocol (IPXCP)	1552
AppleTalk	AppleTalk Control Protocol (ATCP)	1378
IPv6	IPv6 Control Protocol (IPV6CP)	2023

See Also: *Link Control Protocol (LCP), Point-to-Point Protocol (PPP)*

network design

The science (or art) of designing a properly functioning network.

Overview

Designing networks that can efficiently transport traffic in expected ways can be a challenge. The performance, reliability, scalability, and manageability of a network depend on a variety of factors, including

- **Bandwidth:** Dealing with traffic congestion on a network is important to ensure that applications function smoothly and that users are happy. Solutions include simply throwing bandwidth at the problem (for example, replacing Ethernet with Fast Ethernet), replacing shared media devices (hubs) with switches (local area network [LAN] or Ethernet switches), and implementing Quality of Service (QoS) to better manage existing bandwidth. An issue related to bandwidth is how that bandwidth is distributed across a network. In the 1980s most enterprise networks were designed with the 80/20 rule in mind, which said that you could expect 80 percent of network traffic to be local (within a workgroup or department) but 20 percent of the traffic would need to be carried over the backbone to remote locations. With the rapid growth of the Internet, however, and the fact that it has become an essential element of enterprise networks, the 80/20 rule has shifted to more like a 20/80 rule, especially for networks that need to support multimedia applications such as streaming audio and video presentations or Voice over IP (VoIP).
- **Fault tolerance:** Networks that run mission-critical business applications need some degree of fault tolerance so they can continue operation in the event of a problem. Solutions can include using routed networks with mesh topologies that provide alternate routes, multihoming a corporate network by connecting it to several Internet service providers (ISPs), and using a dual-ring architecture as in Fiber Distributed Data Interface (FDDI).
- **Geography:** Networks that span a continent are designed and built differently from those that occupy only a single office. Wide area networks (WANs) not

only use different technologies than LANs but also involve leasing telecommunications services from telcos and other service providers, distributing network administration among regional offices, and dealing with legal and political issues.

- **Simplicity:** Managing a heterogeneous network consisting of multiple network architectures and protocols can be a headache, but it is also a reality that most large enterprises grow their network in an organic fashion over a period of years. As new networking technologies are added, existing ones are maintained as legacy services to reduce the up-front cost of migrating architectures, services, and data. The result is anything but simple, so anything a network manager can do to reduce the complexity of an enterprise network should be done. The most important thing to do, of course, is to plan each modification of the network carefully.


Layer 3
switch
or router
Layer 2
switch
Layer 4
switch
Layer 3
switch
or router
Server
farm
Stackable
hubs
Layer 3
switch
or router
LAN
LAN
Workgroup
switch
LAN
Departmental
LANs
Workstations
Core level
Distribution level
Access level

Network design. *Typical hierarchical design of an enterprise network.*

- **Size:** Flat networks may suffice for small businesses, but in enterprises where thousands of machines need to be networked, a hierarchical network is more scalable and manageable.
- **Standards:** Using protocols and equipment that conform to internationally recognized standards can be a lifesaver in network design. Although networking devices can initially be purchased from a single vendor to eliminate interoperability issues, the vendor you purchased from might not be around several years later when you want to expand your network. Purchasing standards-based networking equipment ensures (usually) that when you later add devices from a different (but also standards-based) vendor to your existing network, no interoperability issues will arise to haunt you.

Architecture

A typical enterprise network today uses a hierarchical design having three levels:

- **Core level:** This is the network's backbone, and it carries the greatest load of traffic. The network's core can be located in a single equipment room (collapsed backbone) or spread throughout a building or campus (distributed backbone). The core connects the switches and routers that form the basis of the next level of the network, the distribution level.
- **Distribution level:** This is the portion of the network responsible for moving traffic from one site (or department or workgroup or floor or building) to another. Traffic control features are typically implemented at this level as well. Different blocks of the distribution level are connected by the core, and the distribution level delivers traffic to end users through the access level. Each block of the distribution level (called switch block) defines a separate broadcast domain, typically serving no more than 2000 hosts to ensure good performance.
- **Access level:** This portion of the network provides users' client machines with direct access to the network.

The specific networking technologies and infrastructure used within each level of an enterprise network vary as well. The main function of the core is to transport traffic quickly, and, as a result, large Layer 2 backbone switches are typically used at this level. Many enterprises employ a dual core with redundant switches to ensure that critical backbone traffic is carried uninterrupted. The distribution level of older enterprise networks employed routers for routing traffic to and from the core, but modern networks tend to use Layer 3 switches instead. The access level uses hubs or Layer 2 workgroup switches if greater carrying capacity is required for multimedia desktop applications. The switches for the access and distribution layers are often combined in the form of switch blocks as mentioned above.

Notes

To get an idea of how the science of network design has evolved over the last decade, consider the following table, which describes a typical network problem and how to solve it based on late 1980s and late 1990s network design principles.

Network Design: Old and New

Issue	*Old Approach*	*New Approach*
LAN traffic is becoming congested	Segment the network	Replace hubs with switches
Real-time applications perform poorly	Throw bandwidth at the problem	Implement Quality of Service (QoS)
Network is complex, heterogeneous, and multiprotocol	Use a combination of routers, switches, and load balancers	Use multilayer switches
Remote users need access to the network	Use expensive leased lines for branch offices and slow dial-up for mobile users	Use virtual private networking (VPN) over the Internet
WAN traffic is becoming congested	Lease a bigger WAN pipe	Use a content delivery network (CDN) or redirect traffic to local caching devices

See Also: *80/20 rule, backbone, Ethernet, Ethernet switch, Fast Ethernet, hub, infrastructure, Layer 2 switch, Layer 3 switch, local area network (LAN), multihoming, Multilayer Switching (MLS), network, network architecture, quality of service (QoS), router, routing, wide area network (WAN)*

network driver interface specification (NDIS)

A specification for network driver architecture.

Overview

Network driver interface specification (NDIS) simplifies the process of writing drivers for network interface cards (NICs) by enabling them to interact transparently with different transport protocols such as Transmission Control Protocol/Internet Protocol (TCP/IP), Internetwork Packet Exchange/Sequential Packet Exchange (IPX/SPX), and NetBIOS Extended User Interface (NetBEUI). NDIS is also a library of routines (a "wrapper") that is implemented in Microsoft Windows 2000, Windows XP, and Windows .NET Server as the driver Ndis.sys, which provides a uniform programming interface between NIC drivers and network protocols.

NDIS Versions

Version	*Platform*	*16- or 32-bit*	*Features*
2	Windows for Workgroups and OS/2	16	Real mode; each NIC must have its own driver.
3	Windows NT 3.5*x*	32	Unlimited number of NICs can be bound to an unlimited number of protocols.
3.1	Windows 95	32	A superset of NDIS 3 with plug and play functionality and support for minidrivers. Windows 95 supports up to four NICs in a computer.
4	Windows NT 4	32	Unlimited number of NICs can be bound to an unlimited number of protocols. Also allows capturing of all frames on local network segment without the need to switch the NIC to promiscuous mode.
5	Windows 98, Windows Me, Windows 2000, Windows XP, Windows .NET Server	32	Adds support for connection-oriented networks such as Integrated Services Digital Network (ISDN) or Asynchronous Transfer Mode (ATM), including support for multiple virtual circuits on one network adapter.

NDIS was developed jointly by Microsoft Corporation and 3Com Corporation in 1989 and has gone through a series of revisions, as shown in the above table. The most recent versions allow one NIC to be bound to many protocols (which is ideal for heterogeneous networks) and one protocol to run on a system with multiple NICs (which helps increase network bandwidth for heavily used servers).

See Also: *NetBIOS Extended User Interface (NetBEUI), network interface card (NIC), Transmission Control Protocol/Internet Protocol (TCP/IP)*

Network File System (NFS)

A suite of protocols for accessing file systems across a network.

Overview

Network File System (NFS) is a distributed file system developed by Sun Microsystems in the early 1980s that has become the de facto standard in distributing file systems. NFS was designed to enable the exporting of files system across heterogeneous networks comprising multiple operating systems and platforms. NFS technology has been licensed to over 200 vendors and implementations have been made available for a wide variety of platforms including UNIX, Linux, Microsoft Windows, and mainframe environments.

NFS allows clients to locate and access files stored on remote servers. The original NFS specification was designed for local area network (LAN) use and was not optimized for wide area network (WAN) connections, but the current version NFS 3 performs well in the WAN as well as the LAN. The features of NFS 3 include

- Support for terabyte-size files using 64-bit file size indicators (previous versions supported files up to 4 gigabytes in size).
- Maximum packet size of 64 kilobytes (earlier versions supported only 8 KB packet size).
- Choice of User Datagram Protocol (UDP) or Transmission Control Protocol (TCP) for NFS network transport (earlier versions supported only UDP, which performed poorly over a WAN).
- Support for caching of client requests by the server.

The original NFS specification is defined in RFC 1094 and the current NFS 3 version is defined in RFC 1813.

Implementation

NFS uses a layered protocol architecture that maps to the seven layers of the Open Systems Interconnection (OSI) reference model as shown in the following table.

NFS Protocol Suite

OSI Layer	*NFS Protocol*
Physical	Any (Ethernet common)
Data link	Same as Physical
Network	Internet Protocol (IP)
Transport	User Datagram Protocol (UDP) and Transmission Control Protocol (TCP)
Session	Remote Procedure Call (RPC) protocol
Presentation	External Data Representation (XDR) protocol
Application	Network File System (NFS) and Network Information System (NIS)

NFS is implemented as a client/server system that uses special NFS servers and NFS client software running on workstations. These servers use NFS to export (make available) their file system to machines running NFS clients—to the client machine the exported file system appears as part of its own local file system. NFS typically uses remote procedure calls (RPCs) running over User Datagram Protocol (UDP) on server port 2049 for stateless communication between clients and file servers on the network. NFS clients (client machines running NFS client software) import remote file systems from NFS servers, while the NFS servers export local file systems to clients. Machines running the NFS client can connect to NFS servers and read, modify, copy, move, or delete files on the server using RPC requests such as READ, WRITE, CREATE, and MKDIR. To the user accessing the remote file system from the client, the files appear to be stored locally on his or her system. Before a user can access files within the directory structure on the local UNIX file system of the NFS server, the administrator must generally mount the portions of the local UNIX file system that will be made accessible to clients and assign appropriate user privileges.

Marketplace

Although NFS is widely used on UNIX platforms, another file sharing protocol called Server Message Block (SMB) is common on Windows platforms. Windows 2000 and Windows .NET Server support NFS in Services For Unix (SFU) version 2, and products such as Samba implement SMB on UNIX platforms. Interoperability between SMB and NFS is thus available both ways for integrating Windows and UNIX platforms for common file sharing purposes. A wide variety of third-party products are also available that implement NFS on the Windows platform, including ChameleonNFS from NetManage, NFS Maestro from Hummingbird International, and many others.

See Also: *Internet Protocol (IP), Linux, Microsoft Windows, Network Information System (NIS), remote procedure call (RPC), Server Message Block (SMB), Transmission Control Protocol (TCP), UNIX, User Datagram Protocol (UDP)*

network ID

The portion of an Internet Protocol (IP) address that identifies the subnet on which the host resides.

Overview

The IP address of a host consists of two parts: the network ID and the host ID. The network ID portion of an

IP address uniquely identifies the host's local subnet. By contrast, the host ID portion of the IP address identifies the host within its local subnet. Together, the host ID and network ID uniquely identify the host on an internetwork.

Examples

The network ID is found by logically ANDing the binary form of the IP address with the binary form of the subnet mask for the network. For example, if a host has an IP address of 172.16.8.55 on a network with a subnet mask of 255.255.0.0 (the default subnet mask), the network ID of the host is 172.16.0.0, or simply 172.16, as it comprises the first 16 bits of the 32-bit address.

See Also: *host ID, Internet Protocol (IP), IP address, subnet*

Network Information System (NIS)

A protocol used for naming and directory services on UNIX platforms.

Overview

Network Information System (NIS) functions as a kind of telephone book for locating resources on a Transmission Control Protocol/Internet Protocol (TCP/IP) network. In fact, the original name for NIS was "Yellow Pages (YP)." NIS enables users and applications distributed across a network to locate and access files and applications anywhere in the network by accessing a central NIS server. The kinds of information typically provided by NIS servers include password files, host tables, and e-mail aliases.

NIS operates using broadcasts, and on most UNIX platforms, NIS clients communicate with NIS servers using remote procedure calls (RPCs) running over User Datagram Protocol (UDP).

The original NIS was not secure and NIS servers were often targeted in attacks on UNIX networks. A newer version developed by Sun Microsystems called NIS+ includes additional security features, but it has gained only limited popularity in the marketplace.

See Also: *remote procedure call (RPC), UNIX, User Datagram Protocol (UDP)*

network interface card (NIC)

Also called network adapter card or network card, a device that allows a computer to communicate on a network.

Overview

Network interface cards (NICs) are typically adapter cards that plug into a slot on the a computer's motherboard, but they also come in Personal Computer Memory Card International Association (PCMCIA) card format for laptop computers and as cards or external devices for wireless networking. A wide variety of devices for home networking also perform the same general function of a NIC, including devices that plug into Universal Serial Bus (USB), parallel, or serial ports and transmit network signals over twisted pair wiring, telephone lines, or even electrical lines in a home. This article focuses, however, on the use of NICs in servers in enterprise environments, particularly in Gigabit Ethernet (GbE) networking.

Types

NICs are typically

- **Media-specific:** UTP and fiber-optic cabling are the two most common options. Some older combo cards support both thinnet and UTP.
- **Network architecture-specific:** Ethernet, Token Ring, and Fiber Distributed Data Interface (FDDI) each use their own distinctive type of NIC.

NICs for Ethernet networks are available in various speeds including 10 megabits per second (Mbps) for Ethernet, autosensing 10/100 Mbps for Fast Ethernet, and autosensing 10/100/1000 Mbps for GbE. These autosensing NICs determine the highest network speed supported by hubs and switches on the network and configure themselves accordingly.

Implementation

NICs are available for all common system bus types, including Industry Standard Architecture (ISA), Extended Industry Standard Architecture (EISA), Micro Channel Architecture, and Peripheral Component Interconnect (PCI). PCI cards are available in 32-bit and 64-bit form and give the best performance. In addition, PCI NICs are plug and play and hence easy to install and configure, in comparison to legacy NICs that require manual configuration of interrupt request (IRQ) and base I/O port settings.

A NIC's role is to convert the parallel stream of data on a computer's bus to serial form for transmission over the medium joining computers together on the network. This medium is typically either Category 5 (Cat 5) or enhanced Category 5 (Cat 5e) unshielded twisted-pair (UTP) cabling, fiber-optic cabling, or in the case of wireless networking, free space. The computer can communicate with the NIC using several methods, including memory-mapped I/O, direct memory access (DMA), or shared memory. A parallel stream of data is sent to the card and buffered in on-card memory before being packaged into discrete frames for transmission over the network. Framing adds headers and trailers to the data, which contains addressing, clocking, and error-checking information. The frames are then converted to electrical voltage pulses that drive an electrical signal over the wire (for copper wiring), modulated light pulses (for fiber-optic cabling), or microwaves (for wireless networking). The NIC on the receiving computer processes the signal in the reverse order, converting the signal first into a bit stream of frames and then into a parallel data stream for the receiving computer's bus. Some of the above functions are built into the NIC's firmware, and the remainder are implemented by the NIC driver software installed on the computer.

Marketplace

The largest producer of enterprise NICs overall is 3Com Corporation, while the top producer of GbE NICs is Intel Corporation, which has almost half of the enterprise market in this arena. 3Com is in second place in the GbE NIC market after its recent acquisition of Alteon Web Systems' GbE adapter technology. Asanté Technologies rocked the market in 2000 with its introduction of a copper-based 1000BaseT NIC that sold for around $150—half the price of other vendors at the time. The copper GbE NIC market has steadily grown against the fiber GbE NIC market, and by the end of 2000, half of all GbE NICs shipped were copper 1000BaseT NICs.

Choosing the right NIC for a high-performance server is a crucial consideration in enterprise computing and e-commerce, as an inferior NIC can easily become a bottleneck for accessing network services. Some GbE NICs support advanced features such as onboard Internet Protocol Security (IPsec) processing to offload workload from the server. Certain NICs from 3Com fall into this category. Other smaller vendors have produced high-performance NICs with specialized features, such as Akamba Corporation's technology that allows for NICs used in Web servers to process Hypertext Transfer Protocol (HTTP) traffic, and Alacritech's technology for implementing a server's TCP stack in hardware on the NIC.

See Also: *Category 5 (Cat5) cabling, enhanced Category 5 (Cat5e) cabling, Ethernet, Fast Ethernet, Fiber Distributed Data Interface (FDDI), fiber-optic cabling, frame, Gigabit Ethernet (GbE), serial transmission, Token Ring, universal serial bus (USB), unshielded twisted-pair (UTP) cabling, wireless networking*

network layer

Layer 3 of the Open Systems Interconnection (OSI) reference model.

Overview

When two hosts on a network need to communicate, the network layer is responsible for determining a suitable path across the network, usually through some form of route calculation. The network layer thus enables hosts on a network to establish communications with each other. The network layer is also responsible for

- Logical addressing of packets so they can be routed over the network to their intended destination
- Fragmenting packets that are too large to be forwarded by router interfaces into sequences of smaller packets
- Reassembly of sequences of packets into their original order
- Performing congestion control

Types

Network layer protocols may be either connectionless or connection-oriented in operation. Examples of connectionless network-layer protocols include

- **Internet Protocol (IP):** The network layer protocol used on the Internet
- **Internetwork Packet Exchange (IPX):** A legacy NetWare protocol

The above protocols employ the transport layer protocols Transmission Control Protocol (TCP) and Sequential Packet Exchange (SPX), respectively, to ensure reliable communications by fragmenting and reassembling packets and requesting retransmissions when required.

Examples of connection-oriented network layer protocols include X.25 and Logical Link Control Type 2 (LLC-Type 2).

Protocols that enable routers to exchange information to create network topology maps also work at the network layer. Examples of such network layer routing protocols include Routing Information Protocol (RIP), Open Shortest Path First (OSPF), Interior Gateway Routing Protocol (IGRP), Enhanced Interior Gateway Routing Protocol (EIGRP), and Border Gateway Protocol (BGP).

See Also: *Border Gateway Protocol (BGP), Enhanced Interior Gateway Routing Protocol (EIGRP), Interior Gateway Routing Protocol (IGRP), Internet Protocol (IP), Internetwork Packet Exchange (IPX), NetWare protocols, Open Shortest Path First (OSPF), Open Systems Interconnection (OSI) reference model, Routing Information Protocol (RIP), transport layer, X.25*

network management

Managing a network's hardware, applications, and performance.

Overview

Network management is a broad term describing platforms and applications that can manage the various devices and software that constitute a network. This includes such general tasks as

- Monitoring, measuring, and optimizing the performance of routers, switches, access servers, multiplexers, Web servers, mail servers, and other network devices and hardware.
- Detecting, diagnosing, repairing, working around, and predicting the likelihood of failures and other problems.
- Installing, upgrading, patching, distributing, configuring, managing, monitoring, and troubleshooting operating systems and applications on servers, desktop workstations, routers, and other hardware. This is often called desktop or systems management.

Network management may also involve

- Mapping the topology of a network in real time through autodiscovery and graphically displaying this information in useful form to administrators.
- Maintaining a central inventory database describing all devices, operating systems, and software on the network and how they are configured. When a change is made to the configuration of a device or application, the database is updated with the information automatically.
- Setting alarms and establishing automated responses to various alert conditions when they arise. These alerts may relate to device failure, traffic bottlenecks, server overload, and other problems.
- Remotely adding, removing, or rearranging local area network (LAN) and wide area network (WAN) links, a process called configuration management.
- Monitoring a network against intrusion by hackers and other attacks.
- Taking remote control of systems to manage, repair, or troubleshoot them.
- Monitoring service level agreements with vendors and service providers.
- Using artificial intelligence to determine the root cause of network failure and perform needed fixes automatically.
- Generating real-time and cumulative logs and reports of network performance, traffic flow, server load, and other information. These can be for auditing, management, planning, troubleshooting, or provisioning purposes.

- Managing different aspects of a network from workstations, using standard Web browsers, and even using wireless Personal Digital Assistants (PDAs).
- Perform policy-based management of network resources and traffic prioritization, a rapidly emerging new area in network management.

Implementation

Most network management platforms employ a combination of proprietary solutions and standards-based usage of Simple Network Management Protocol (SNMP) and its cousin Remote Monitoring (RMON). Other standards from the Distributed Management Task Force (DMTF) and Internet Engineering Task Force (IETF) are important also, particularly Web-Based Enterprise Management (WBEM) and the emerging Policy Framework and SNMPConf initiatives. Network management platforms support these existing and emerging standards to various degrees.

Network management can be accomplished in several ways:

- **Using prepackaged tools included with network operating systems such as Microsoft Windows and UNIX:** For example, Windows 2000 includes administrative tools such as Performance Monitor, Network Monitor, Computer Management, and other utilities that can be used to remotely monitor, manage, and troubleshoot server and network problems. Command-line tools such as Ping, Ipconfig, Tracert/Traceroute, Netstat, Nslookup, and others are also available on both Microsoft and UNIX platforms for configuring and troubleshooting Transmission Control Protocol/Internet Protocol (TCP/IP) networks. Trivial File Transfer Protocol (TFTP) and Telnet are often used for remote management of Cisco routers and other networking equipment from a command-line interface.
- **Using enterprise network management frameworks:** These are suites of tools integrated to various degrees that enable (or promise to enable) administrators to remotely manage all aspects of a diverse, heterogeneous network from a central administrator console. Many of these systems began in the 1980s as organic collections of tools united by a common user interface (admin console) and back-end database (for storing network configuration information). They were large, complex, expensive, and difficult to implement, often requiring a great deal of customization to work properly and never quite living up to their marketed goals. Such systems were targeted mainly to large enterprises having deep pockets and have found wide acceptance in such environments to this day. This failure to fulfill customer expectations was partly a result of the rapid pace of technological evolution in operating system and networking technologies, with the result that vendors of such network management systems had difficulty keeping up with the pace of change in these technologies. Many of these systems have now evolved into one-size-fits-all packaged management systems that are easier to deploy and use but which are more limited in their goals. Some framework vendors have also made their systems extensible to allow third-party point products to fill gaps in their framework products. Popular examples of these types of frameworks are listed below in the section entitled “Marketplace.”
- **Using loose collections of freeware and open source network management tools:** Network administrators of small to mid-sized companies often create their own custom toolkit of useful management tools and utilities developed in-house or downloaded from the Internet and used for monitoring, configuring, and troubleshooting networks and servers. Using such diverse collections of tools, however, requires a high level of understanding of how networks actually work and how they ought to work and requires the discipline of implementing proper procedures and processes for maximum benefit.
- **Outsourcing network management needs:** Small companies often benefit from outsourcing all of their network management needs to a network/systems integrator, who often can remotely manage network performance and troubleshoot server problems by means of the Internet using browser-based tools. Larger companies may outsource only specific portions of their management needs, such as allowing telcos to remotely monitor the channel service unit/data

service units (CSU/DSUs) and T1 multiplexers that they lease to the customers. Outsourcing is a viable option for companies that do not have the resources to hire their own qualified network personnel.

Whatever the approach used for managing networks, most companies do not make this a high enough priority or allocate sufficient resources (in terms of both staff and money) to this aspect of their business as they do for their deployments of enterprise resource planning (ERP) and customer relationship management (CRM) software. If a company's customer and product data and communication/collaboration abilities are important and must be safeguarded and maintained at all costs, then safeguarding and maintaining the network on which information is stored and over which it travels should be an equally high priority, whatever the cost.

Marketplace

Network management frameworks for enterprise use are available from both traditional vendors and newer startups. Traditional vendors include Tivoli/IBM, Hewlett-Packard, Computer Associates, BMC Software, and several others. Tivoli Enterprise is a suite of platforms and tools providing desktop, network, storage, security, service, Web, and performance management. Tivoli products are available for a wide range of network operating systems, including Microsoft Windows, UNIX, and IBM's OS/390 mainframe platform. Tivoli even has a product line supporting end-to-end management of retail solutions that include point-of-sale terminals and automated teller machines (ATMs). They also have one for managing Personal Digital Assistants (PDAs), a rapidly growing concern in the enterprise environment. Tivoli software is used by 96 percent of Fortune 500 companies and is probably the most widely used management framework in enterprise environments. IBM's earlier NetView management platform is also integrated into the Tivoli line of products.

Another popular framework product is HP OpenView from Hewlett-Packard. Sun Microsystems also offers a management platform called Sun NetManager for their SunOS and Solaris machines. VERITAS Software Corporation is another contender in the enterprise arena with their Veritas NerveCenter—other vendors include Aprisma, NextPoint Networks, Lucent Technologies, and others. Finally, Microsoft has Microsoft Operations Manager (MOM) that provides enterprise-class event and application monitoring for the Windows 2000 and Windows .NET Server operating systems, and .NET Server application platforms.

Microsoft Systems Management Server is popular in the enterprise as a server, desktop, and applications management system. So is LANDesk Management Suite from Intel Corporation and Unicenter TNG from Computer Associates. Windows 2000 also supports a number of networking application programming interfaces (APIs) that allow information about network resources to be programmatically accessed, and some Active Directory Services Interface (ADSI) interfaces also provide similar functionality for script access.

Some vendors of point products that fill specific gaps in the management functionality of framework platforms include Concord Communications, Micromuse, RiverSoft Technologies, Tavve Software, and many others. A good example is CiscoWorks, which can be installed as an add-in for popular management frameworks such as HP OpenView and Sun NetManager. A number of startups provide point products providing root-cause analysis, automated event correlation, and other features previously lacking in big-name framework products. These startups include Evidian, Oxydian, Magnum Technologies, and many others.

Policy-based management tools include Cisco QoS Policy Manager from Cisco Systems and Orchestream Enterprise Edition from Orchestream. Application monitoring and performance tools include EcoSCOPE from Compuware Corporation, NextPoint S^3 from NextPoint Networks, eHealth from Concord Communications, VitalSuite from Lucent Technologies, and many others. The most popular remote control software used in enterprise systems management is undoubtedly PCAnywhere from Symantec Corporation. The Terminal Services component of Windows 2000, Windows XP, and Windows .NET Server offers out-of-the-box remote control functionality for these operating systems. Citrix RMS from Citrix Systems is another network management tool that includes remote control.

Network probes are growing in popularity as weapons in the network manager's arsenal. These probes are small SNMP-enabled devices that can be plugged into a WAN demarcation point or LAN segment to monitor network traffic and collect statistics for network management stations.

Management of Linux systems can be easily performed using Volution, a platform from Caldera International designed for large enterprises, application service providers (ASPs), Internet service providers (ISPs), and similar companies that may use large numbers of Linux machines. Volution is based on Red Hat Package Manager (RPM) technology and supports a number of major Linux distributions. Also in the open source arena, an initiative called OpenNMS was acquired by Atipa Technologies and rebranded as the Bluebird network management platform. Bluebird is available under the open-source license.

For More Information

A good overview on network management standards and free software can be found at *www.simpleweb.org.*

See Also: *Distributed Management Task Force (DMTF), Internet Engineering Task Force (IETF), network, network probe, network troubleshooting, Remote Network Monitoring (RMON), Simple Network Management Protocol (SNMP), Telnet, topology, Transmission Control Protocol/Internet Protocol (TCP/IP), Web-Based Enterprise Management (WBEM)*

Network Monitor

A software-based protocol analyzer included with Microsoft Windows 2000 and Windows .NET Server.

Overview

Network Monitor is a useful tool for troubleshooting network problems at the data-link, network, transport, and higher layers of the Open Systems Interconnection (OSI) reference model. You can use Network Monitor to

- Capture data frames from a connected network
- Display, filter, edit, and retransmit frames on the network
- Monitor and display protocol statistics
- Examine individual captured frames in detail



Network Address 1	1-->2	1<--2	Network Address 2
48543300CD6A	7	9	PICASSO
48543300CD6A	23		*BROADCAST
ADDTRN2216ED	24		*BROADCAST
PICASSO	8	6	R.P.T.D1296C

Time Elapsed: 00:01:37.152

Network Statistics
Frames: 245
Broadcasts: 136
Multicasts: 0
Bytes: 36092
Frames Dropped: 0
Network Status: Normal

Captured Statistics
Frames: 245
Frames in Buffer: 245

Network Address	Frames Sent	Frames Rcvd	Bytes Sent	Bytes Rcvd	Directed Frames Sent	Multicasts Sent	Broadcasts Sent
*BROADCAST	0	136	0	17669	0	0	0
48543300CD6A	31	10	3488	1182	8	0	23
ADDTRN2216ED	31	9	3431	993	7	0	24
PICASSO	47	47	10691	4968	44	0	3

Network Monitor. *Example of a trace in Network Monitor.*

Notes

The version of Network Monitor included with Windows NT, Windows 2000, and Windows .NET Server is a simplified version that lacks some of the features in the full version included with Microsoft Systems Management Server (SMS). In particular, the simplified version can perform only local capturing of data to and from the computer running Network Monitor.

See Also: *network troubleshooting, Open Systems Interconnection (OSI) reference model, Systems Management Server (SMS)*

Network News Transfer Protocol (NNTP)

The Internet protocol for Usenet newsgroups.

Overview

Network News Transfer Protocol (NNTP) is an Internet standard protocol that governs the interaction between NNTP servers (news servers) and NNTP clients (news readers). NNTP is the underlying protocol on which the Usenet news system popular on the Internet. NNTP connections between clients and servers and between servers and servers use Transmission Control Protocol (TCP) for reliable, guaranteed packet delivery.

NNTP is defined in RFC 977.

Implementation

NNTP is both a client/server protocol and a server/server protocol. NNTP supports a set of simple text commands that:

- Enable NNTP clients such as Microsoft Outlook Express to connect to NNTP servers on TCP port 119 and download a list of newsgroups, read the messages in a newsgroup, and post a reply or a new message to a newsgroup.
- Enable NNTP servers to replicate newsgroups and their content among each other. This replication process between NNTP servers (or NNTP hosts, as they are often called) forms the basis of the worldwide news system called Usenet.

NNTP client commands include the following:

- **LIST:** To obtain a list of newsgroups available on the server
- **GROUP:** To select a specific newsgroup
- **ARTICLE:** To display a selected message
- **POST:** To post a new message or reply to an existing one

NNTP clients connecting to NNTP servers sometimes require authentication before their NNTP commands are accepted.

See Also: *Internet, newsfeed, newsgroup, Transmission Control Protocol (TCP)*

network numbers

Numbers assigned to subnets on a legacy Internetwork Packet Exchange/Sequential Packet Exchange (IPX/SPX) internetwork.

Overview

Network numbers uniquely identify portions of the network on an IPX/SPX internetwork. Network numbers must typically be manually assigned to hosts by the administrator to ensure proper network communication.

When using the NWLink IPX/SPX-Compatible Transport protocol on Microsoft Windows 2000, Windows XP, or Windows .NET Server networks, you must configure two different network numbers to ensure proper network communication:

- The IPX network number (also known as the external network number), a unique number assigned to all computers on the same network segment that are using the same NWLink frame type. In Windows 2000, Windows XP, and Windows .NET Server, you configure this number by accessing the NWLink IPX/SPX/NetBIOS Compatible Transport Protocol property sheet, selecting Manual Frame Type Detection, clicking Add, and entering the number.
- The virtual network number (also known as the internal network number), a unique number assigned to a machine that enables it to be used in a multiple network environment. This number is hexadecimal 0 by default; in Windows 2000, Windows XP, and Windows .NET Server, you can configure it by specifying it on the NWLink IPX/SPX/NetBIOS Compatible Transport Protocol property sheet.

To view the network number of a computer running Windows 2000, type **ipxroute config** at the command prompt.

Notes

When using the Transmission Control Protocol/Internet Protocol (TCP/IP), network numbers are instead called network IDs.

See Also: *internetwork, network ID, NWLink IPX/SPX-Compatible Transport (NWLink)*

network operating system (NOS)

An operating system that is network-aware.

Overview

Network operating systems (NOSs) are used to build local area networks (LANs) that can be used for

- Authenticating users who want to access the network for greater security
- Enabling users to share files and printers and exchange messages for performing collaborative work

- Centralizing administration of multiple computers to a single management console
- Running distributed applications that share processing on multiple computers

Marketplace

Examples of popular NOSs include

- Microsoft Windows 2000
- Novell NetWare
- Various flavors of UNIX
- Linux

Internetwork Operating System (IOS) from Cisco Systems is an example of a NOS that runs not on computers but on internetworking devices such as routers.

See Also: *Internetwork Operating System (IOS), Linux, local area network (LAN), NetWare, UNIX, Windows 2000*

network probe

A device for collecting network statistics.

Overview

Network probes are generally small devices that can be plugged into various points of a network to collect statistics and forward them to a network management station. These statistics then allow you to perform traffic analysis and identify trends so you can plan proper upgrades and identify problems.

Implementation

Network probes are a complement to existing network monitoring functionality based on Simple Network Management Protocol (SNMP) and Remote Monitoring (RMON) and are built in to today's intelligent network hubs, switches, and routers. Different probes are available that collect different kinds of information in various levels of detail, store this information in memory, and forward it to troubleshooting tools and management systems. Probes are available for different kinds of network architectures ranging from Ethernet to Asynchronous Transfer Mode (ATM) and from local area network (LAN) to wide area network (WAN) usage. LAN probes can usually be attached anywhere in a network or plugged into a port on an Ethernet switch. WAN probes are usually best located at the demarc point, the location where the physical circuit for the WAN link first enters the network—in other words, before the channel service unit/data service unit (CSU/DSU) when using leased lines such as T-carrier circuits.

See Also: *Asynchronous Transfer Mode (ATM), Channel Service Unit/Data Service Unit (CSU/DSU), Ethernet, Ethernet switch, local area network (LAN), network, network troubleshooting, Remote Network Monitoring (RMON), Simple Network Management Protocol (SNMP), T-carrier, wide area network (WAN)*

network protocol

A Layer 3 (network layer) of the Open Systems Interconnection (OSI) reference model for networking.

Overview

Common network protocols include the following:

- **Internet Protocol (IP):** Part of the Transmission Control Protocol/Internet Protocol (TCP/IP) protocol suite for connectivity with the Internet
- **Internetwork Packet Exchange (IPX):** A legacy Novell NetWare protocol.
- **NetBEUI:** A protocol developed from NetBIOS that functions at both the network and transport layers

Microsoft Corporation's 32-bit Windows operating systems are implemented in a layered fashion that allows multiple network protocols to be bound to multiple network interface cards (NICs) and allows multiple network clients and services to access these protocols. Windows computers can thus establish connectivity and interoperability with non-Microsoft operating system platforms such as UNIX and Novell NetWare.

See Also: *Internet Protocol (IP), Internetwork Packet Exchange (IPX), NetBEUI, network layer, Open Systems Interconnection (OSI) reference model*

network security

The methods used to protect a network from hostile attack.

Overview

Network security is not only a broad topic but also an essential one for today's network administrator. Attempts to intrude, disrupt, and deface business and corporate networks has never been higher, facilitated in part by the ubiquitous presence of the Internet and broadband Internet access. The vulnerability of today's networks to security attacks is compounded by lack of awareness by corporate management, overworked IT (information technology) staff, rapid software upgrade cycles that encourage the release of buggy software, widespread availability on the Internet of easy-to-use hacking and cracking tools, and vulnerabilities in the underlying Transmission Control Protocol/Internet Protocol (TCP/IP) itself, the networking protocol used by the Internet.

Some of the risks faced by networks today include

- Denial of service (DoS) attacks that tie up a network's resources so that legitimate users cannot gain access to them
- Trojan horse programs that install back doors to allow valuable network credentials to be stolen and misused or that install remote control programs that provide intruders with full access to network resources
- Viruses that invade networks through e-mail attachments and wreak havoc with important files
- Network operating systems and applications whose default configurations are insecure and permit a wide range of attacks to be performed
- Public Web sites that expose credit card information stored in databases through buffer overflows and script issues
- Wireless networks with weak or no encryption that can be accessed easily by anyone driving by with a wireless-enabled laptop

Some of the tools and techniques network administrators can use to secure their networks include

- **Physical security:** Simply locking the server room is a step that should not be overlooked. Users should also be taught not to write down their passwords on slips of paper taped under their keyboards and to be alert for malicious social engineering and persons calling and posing as network administrators and asking for passwords to fix alleged network problems.
- **Virus protection:** Subscribing to a virus protection service is essential for hosts connected to the Internet.
- **Authentication:** Properly configuring authentication methods are a necessary step to ensure against unauthorized logons. For high-security environments users can be provided with smart cards and other authentication tokens. Biometrics can also be employed if required, enabling users to be authenticated using fingerprint or retina scanners.
- **Access control:** Properly securing resources with suitable permissions is a necessary step to ensure against unauthorized resource access. Periodic auditing of access controls is also important.
- **Auditing:** Periodic auditing of security logs is essential, as even intelligent risk-analysis systems may miss certain kinds of attacks.
- **Encryption:** Using a protocol such as Internet Protocol Security (IPsec) can ensure the integrity and privacy of data transmitted over the network, and other protocols such as Pretty Good Privacy (PGP) can be used to secure e-mail.
- **Firewalls:** This is an essential tool for securing the perimeter of a network connected to the Internet, but firewalls must be properly configured and maintained and their logs should be periodically reviewed.
- **Remote access:** Remote access systems can be made more secure by implementing callback and other features. If the Internet is used for remote access, virtual private networks (VPNs) can employ IPsec for greater security.
- **Intrusion detection:** Installing an intrusion detection system (IDS) is becoming an essential part of corporate network security. Usually, the more intelligence these systems have the better, but they cannot replace the intelligence of the network administrator.

- **Patches:** Operating systems and applications are frequently found to be buggy or insecure, and vendors issue fixes to address these problems. Keeping up to date regarding available patches and applying them in timely fashion is essential for today's network administrators. Web servers are especially viewed as targets by attackers, and they require considerable attention to maintain security and protect against newly discovered vulnerabilities.
- **Backups and fault tolerance:** Every system is liable to be breached at some point, so having redundant hot standby systems is important in mission-critical e-commerce systems, and regular backups that are periodically restored for testing purposes are often the last line of defense against attackers damaging corporate databases.
- **Security policy:** Developing, internally publishing, monitoring, and enforcing a corporate security policy is a vital step in securing your network.
- **Training:** Making sure that IT staff are trained in using security tools is essential unless network operations are outsourced to other companies.

For More Information

Visit the SANS Institute at *www.sans.org.* Visit the CERT Coordination Center at *www.cert.org.*

See Also: *access control, auditing, authentication protocol, backup, biometric authentication, denial of service (DoS), disaster recovery, encryption, fault tolerance, firewall, hacking, Internet Protocol Security (IPsec), intrusion detection system (IDS), remote access, virtual private network (VPN), virus*

network service type

The way that a network appears to end nodes communicating over it.

Overview

There are two different ways to consider the service method employed for host-host communications on a network: connection method and delivery method. These methods are provided through the operation of the lower three layers of the Open Systems Interconnection (OSI) reference model; namely, the network, data link, and physical layers. Delivery methods may be either

- **Reliable:** Packets are delivered in the correct order without loss or duplication.

or

- **Best effort:** Also called the datagram method, packets (datagrams) may be delivered out of order with possible duplication or lost packets. With best effort delivery, the transport layer (Layer 4 of the OSI model) is usually responsible to ensure out of sequence packets are reordered, duplicate packets are ignored, and lost packets are retransmitted.

From the point of view of network connectivity, there are also two kinds of network services:

- **Connectionless:** Each packet is transmitted independently and contains the full source and destination address of the hosts communicating. No session establishment is required before communications can begin—the transmitting host simply starts sending packets to the destination, hoping higher layer protocols will ensure that delivery is achieved.
- **Connection-oriented:** Also called the virtual circuit (VC) method, this method involves first establishing a communication session between two hosts before transmitting data. Once a session has been established, it is usually assigned some kind of session identifier in place of full source/destination addressing, and all data packets transmitted include this identifier and are routed or switched similarly.

See Also: *connectionless protocol, connection-oriented protocol, Open Systems Interconnection (OSI) reference model, virtual circuit*

Networks file

A text file that provides a local method of resolving network names into their network IDs on a Transmission Control Protocol/Internet Protocol (TCP/IP) network.

Overview

The entries in the networks file are friendly names for TCP/IP networks; they can be used in TCP/IP commands such as the route command and for TCP/IP network management.

The networks file is at the following location on computers running Microsoft Windows:

- **Windows NT, Windows 2000, Windows XP, and Windows .NET Server:** %SystemRoot%\system32\drivers\etc
- **Windows 95 and Windows 98:** \Windows

Examples

Each line in the networks file contains a friendly network name for the network, followed by the IP address of the network and an optional comment prefixed with a pound sign (#). The following example is from the sample networks file included with Windows 95 and Windows 98:

```
loopback       127
campus         284.122.107
london         284.122.108
```

See Also: *hosts file, lmhosts file, protocol file, services file*

Network Termination Unit (NTU)

A telecommunications device used in Integrated Services Digital Network (ISDN) networking.

Overview

The Network Termination Unit (NTU) allows customer premises equipment to be connected to the switching equipment at the telco's central office (CO). ISDN customer premises equipment, such as routers and ISDN phones, usually have an ISDN S/T interface, while the ISDN termination at the customer end of the local loop usually has a U interface using an RJ-45 connector. The NTU converts the U termination of the ISDN line to one or more standard coding S/T interfaces that are suitable for connecting digital ISDN-ready phones, routers, and other devices to an ISDN line.

NTUs work differently from ISDN terminal adapters, which allow you to connect analog telephones, faxes, and similar equipment to your ISDN line. NTUs typically support either point-to-point or multipoint connections over distances of up to 3.4 miles (5.4 kilometers) on 26 AWG copper twisted-pair cabling. Some newer ISDN-enabled devices have a built-in U interface, making an NTU unnecessary.

The following table shows the differences between the Basic Rate ISDN U and S/T interfaces.

Basic Rate ISDN U Interfaces vs. Basic Rate ISDN S/T Interfaces

Property	*U Interface*	*S/T Interface*
Number of wires	2	4
Connector	RJ-45	RJ-45
Zero-to-peak voltage	2.5 V	0.75 V
Line coding	2B1Q (or 4B3T in Europe)	ASI (Alternate Space Inversion)

See Also: *Integrated Services Digital Network (ISDN), ISDN terminal adapter*

Network Time Protocol (NTP)

An Internet protocol for synchronizing computer clocks to an accurate reference clock.

Overview

Network Time Protocol (NTP) is used to synchronize computers with a remote reference system such as a cesium atomic clock. Synchronization of computers on a network is important for distributed applications, directory services, mail services, and other network services to work reliably. NTP solves this problem by providing a hierarchical series of time servers from which other computers can obtain the exact time, typically within an accuracy of several milliseconds. NTP time servers use Universal Time Coordinated (UTC), a global standard time that is independent of time zones.

NTP is defined in RFC 1305 and is supported by most UNIX platforms. A simplified version of NTP called Simple Network Time Protocol (SNTP) is also widely used and is supported by Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Architecture

Master clocks are located at the U.S. Naval Observatories in Washington, D.C., and Colorado Springs, Colorado. These clocks are highly accurate atomic clocks that lose less than a second in a thousand years. Stratum 1 NTP servers obtain their time from direct connections to these master clocks. Stratum 2 servers obtain their time from stratum 1 servers and can provide time synchronization for computers on a network.

See Also: *UNIX, Windows 2000*

network transmission method

The way in which information transmitted over a network is received.

Overview

There are three basic types or models of how network transmissions are performed:

- **Unicasting:** One host transmits to another host. An example is Transmission Control Protocol (TCP), part of the Transmission Control Protocol/Internet Protocol (TCP/IP) suite. Unicasting is the main transmission method used for sending data over a network.
- **Broadcasting:** One host transmits to all hosts. An example is Address Resolution Protocol (ARP), used by TCP/IP networks running on Ethernet to resolve Layer 3 (network layer) Internet Protocol (IP) addresses into their associated Layer 2 (data link layer) MAC addresses. Broadcasts are often employed on networks for advertisements, announcements, name registrations, and other purposes.
- **Multicasting:** One host transmits to a select group of hosts. Multicasting is often used for delivery of streaming audio or video across an IP network.

Notes

A broadcast's scope depends on the aspect of the network under consideration. For example, on IP networks a broadcast is delivered to all hosts on the local subnet, but on Ethernet networks a broadcast is sent to all hosts within a given broadcast domain.

See Also: *Address Resolution Protocol (ARP), broadcast domain, broadcasting, data-link layer, Ethernet, MAC address, multicasting, subnet, Transmission Control Protocol (TCP), Transmission Control Protocol/Internet Protocol (TCP/IP), unicasting*

network troubleshooting

The process of identifying and fixing network communication problems.

Overview

Computer networks are complex entities, and problems can arise on many levels that can prevent network communications from working. Network troubleshooting involves tools and procedures for identifying, locating, repairing, and maintaining networks so they can perform as expected.

Network administrators have a variety of weapons in their arsenal for troubleshooting different types of network problems, including

- **Physical-layer tools:** The physical layer (Layer 1) of the Open Systems Interconnection (OSI) reference model is the layer responsible for signaling, that is, for placing voltages on the wire or light pulses within fiber-optic cabling. Cable testers and time domain reflectometers (TDRs) are the main tools used for diagnosing and locating cable breaks, fractures, and loose connections.
- **Higher-layer tools:** For troubleshooting at the data link, network, transport, and higher layers of the OSI model, protocol analyzers are the primary tool. Protocol analyzers sniff (capture) network traffic and use various degrees of intelligence to interpret the nature of this traffic and any underlying problems that may be present. They range from software that can be installed on standard PCs that have network interface cards (NICs) that support promiscuous mode, to stand-alone devices ranging from handheld to briefcase size.
- **Integrated analyzers:** These tools package cable testers and TDRs with protocol analyzers to provide an integrated platform for troubleshooting a wide range of network problems.
- **Network probes:** Also called Remote Network Monitoring (RMON) probes, these are generally small devices that can be plugged into a network or into switch ports to capture and buffer traffic statistics for forwarding to a network analyzer or network management system. Network probes

facilitate troubleshooting of switched networks, an area in which traditional network analyzers designed for shared networks are less effective.

Marketplace

The market leader in network test equipment is Fluke Corporation, whose LANMeter line of protocol analyzers are widely used in enterprise environments. Fluke's new OptiView Integrated Network Analyzer takes this a step forward by providing an integrated network test device for troubleshooting cabling issues, performing protocol analysis, and capturing RMON statistics at speeds up to the gigabit per second range and using intelligence to present information to users in an understandable format.

Other vendors of network test equipment include 3Com Corporation, Agilent Technologies, Datacom Textron, Microtest, NetScout Systems, Network Associates/ Sniffer Technologies, Network Instruments, Nortel Networks, and WildPackets.

Notes

Some general tips on diagnosing and resolving network problems include

- Determining whether the problem affects a single user, group of users, or all users on the network
- Establishing whether the problem is continuous, periodic, or intermittent
- Checking for loose, sharply bent, or damaged cabling
- Swapping hardware such as cabling, network interface cards (NICs), hubs, and switches to see the effect
- Using Transmission Control Protocol/Internet Protocol (TCP/IP) troubleshooting commands such as ping and tracert

See Also: *cable tester, network, network interface card (NIC), network probe, Open Systems Interconnection (OSI) reference model, ping, Remote Network Monitoring (RMON), time domain reflectometry (TDR), tracert*

network utilization

The percentage of available bandwidth being used in a network.

Overview

For Ethernet networks, a network utilization of 40 to 60 percent is normally the maximum. Higher utilization than this typically results in excessive collisions and retransmissions. Another word that describes network utilization is *throughput*, which is typically measured in megabits per second (Mbps) or megabytes per second (MBps).

See Also: *Ethernet, network*

newsfeed

Replication of Network News Transfer Protocol (NNTP) newsgroup listings and content.

Overview

Newsfeeds are an essential part of the architecture of NNTP. Newsfeeds enable news servers belonging to the Internet's Usenet system to exchange lists of newsgroups and messages with one another.

Newsfeeds come in two types:

- **Push feed:** Initiated by the remote host. This type is usually used when the newsfeed is very large.
- **Pull feed:** Initiated by the local host. This type gives the local host more control over what to download.

The host that provides the newsfeed is called the inbound host; the host that receives the newsfeed is called the outbound host.

See Also: *Internet, Network News Transfer Protocol (NNTP)*

newsgroup

A group of related messages on a Network News Transfer Protocol (NNTP) host.

Overview

Newsgroups generally contain postings on a particular topic, although they are often a prime target for spammers who post unsolicited advertisements. Newsgroups are defined hierarchically using a dotted notation. An example of a newsgroup is alt.books.computing, which is an "alternative" group that discusses books about computing. The dotted notation of the newsgroup name emphasizes the hierarchical structure of the Usenet system of newsgroups. For example,

- alt is the root of the hierarchy of alternative newsgroups.
- alt.books refers to either a newsgroup on alternative books or a collection of such newsgroups.
- alt.books.cooking refers to either a newsgroup on alternative cookbooks or to a collection of such newsgroups.

Newsgroups can be either moderated or unmoderated. In moderated newsgroups, all messages posted to the newsgroup are first sent to the newsgroup moderator, who accepts or rejects messages depending on their relevance to the group's focus. Unmoderated groups are generally a free-for-all, although politeness dictates that users post only messages related to the newsgroup's focus.

Notes

When you first join a newsgroup, it's a good idea to "lurk" in the background for a while and read the postings to understand the focus and tone of the group. Posting off the topic or at too low a level in an advanced group can cause a "newbie" to get "flamed" (bombarded with offensive mail).

See Also: *Internet, Network News Transfer Protocol (NNTP)*

NEXT

Stands for near-end crosstalk, a measurement of the ability of network cabling to reject crosstalk.

See: *near-end crosstalk (NEXT)*

Next Generation I/O (NGIO)

A specification designed to replace the Peripheral Component Interconnect (PCI) system bus.

Overview

With today's Pentium III processors and high-speed hard disks, the PCI bus is rapidly becoming the bottleneck that limits the performance of high-speed data center servers. The PCI bus is limited to about 500 megabits per second (Mbps) of shared throughput. It lacks an error-detection mechanism and has relatively high latency. Next Generation I/O (NGIO) is intended to overcome these limitations. It uses a channel-based architecture that supports full-duplex transmission speeds of up to 2.5 gigabits per second (Gbps).

The NGIO Forum recently combined its efforts with a group called Future I/O, which was promoting a different standard. The combined standard will be called System I/O; its development group is headed by Intel Corporation and IBM and includes Microsoft Corporation, Sun Microsystems, Hewlett-Packard, and Dell Computer Corporation. System I/O will use a channel-based I/O architecture instead of a bus architecture and will use from 1 to 12 wires, each having a throughput of 2.5 Gbps. The channel-based architecture will allow different channels to carry different information to different components simultaneously, which will be a great improvement over parallel-transmission bus technologies. System I/O will also fully support hot-swapping of components.

For More Information

Visit the NGIO Forum at *www.ngioforum.org.*

NFS

Stands for Network File System, a suite of protocols for accessing file systems across a network.

See: *Network File System (NFS)*

NGIO

Stands for Next Generation I/O, a specification designed to replace the Peripheral Component Interconnect (PCI) system bus.

See: *Next Generation I/O (NGIO)*

NIC

Stands for network interface card, a device that allows a computer to communicate on a network.

See: *network interface card (NIC)*

NIS

Stands for Network Information System, a protocol used for naming and directory services on UNIX platforms.

See: *Network Information System (NIS)*

NIST

Stands for National Institute of Standards and Technology, a U.S. government organization that provides services and programs to help U.S. industries commercialize new technologies and compete internationally.

See: *National Institute of Standards and Technology (NIST)*

NNTP

Stands for Network News Transfer Protocol, the Internet protocol for Usenet newsgroups.

See: *Network News Transfer Protocol (NNTP)*

node

A general term for a device on a network that has a specific physical or logical address.

Overview

Nodes on a network can be computers, repeaters, bridges, or other devices on a network that can transmit, receive, or process signals. Another name for a node, especially on Ethernet networks, is a *station*.

Other common meanings of the term *node* include

- A domain or subdomain in the namespace of the Domain Name System (DNS)
- An object in the console hierarchy of Microsoft Management Console (MMC)
- In clustering terminology, a machine that is a member of a cluster

See Also: *clustering, Ethernet, network*

noise

Random disturbances in a transmission.

Overview

In computer networking, noise is undesirable random electrical transmission that is generated by networking components such as network interface cards (NICs) or induced in cabling by proximity to electrical equipment that generates electromagnetic interference (EMI). Noise is generated by all electrical and electronic devices, including motors, fluorescent lamps, power lines, and office equipment, and it can interfere with the transmission of signals on a network. The better the signal-to-noise ratio of an electrical transmission system, the greater the throughput of information on the system.

Noise can usually be reduced (but never entirely eliminated) by using higher-quality components, lowering the temperature of components, or using shielded cabling. Be sure to locate sensitive networking components and cabling away from heavy machinery, generators, motors, and other equipment that can generate a lot of EMI. Also be sure to terminate cables properly at patch panels and wall plates to minimize noise due to crosstalk.

See Also: *cabling, crosstalk, electromagnetic interference (EMI), network interface card (NIC), signal*

normal backup

A type of backup in which all the selected files and folders are backed up.

Overview

Also known as full backup, normal backups are the most secure way of backing up files and folders to tape. In a normal backup, the archive attribute is marked for each file and folder that is backed up. If the file is later modified, the archive attribute is cleared, indicating that the file needs to be backed up again. Normal backups are the safest form of backup but take the longest and use the most tape. They are also the easiest form of backup to perform a restore from, because you generally need only one tape to perform the restore (unless the amount of information to be backed up exceeds the capacity of the tape).

Notes

A good backup plan consists of at least one normal backup each week, with either incremental or differential backups during the rest of the week.

See Also: *backup, backup type*

NOS

Stands for network operating system, an operating system that is network-aware.

See: *network operating system (NOS)*

Novell Directory Services (NDS)

The directory services platform from Novell Networks.

Overview

Novell Directory Services (NDS) is a distributed network directory service platform for managing network resources such as users, groups, servers, shares, printers, and applications. NDS was introduced in 1993 with version 4 of the Novell NetWare operating system. Eventually, NDS was ported to other platforms, ranging from Sun Microsystems' Solaris platform to IBM S/390 mainframes. NDS is widely used in enterprise environments and is the main competitor for the Active Directory directory service of Microsoft Windows 2000 and Windows .NET Server.

Implementation

NDS is loosely modeled after the X.500 specification from the International Telecommunication Union (ITU). The foundation of NDS is the directory tree, which provides a hierarchical view of all network resources. Resources in the network can be grouped logically according to their location, function, or the structure of the company. Objects in the tree can be either containers or leaf objects, with the root container being the name of the company or organization. Containers can be considered branches and can hold leaf objects or other containers. When a user is assigned access rights to a container, these rights flow down into any subcontainers within the container. Trees, subtrees, and containers can also be renamed and merged.

You can implement NDS directories as a distributed database that is partitioned among multiple NDS servers on the network to provide fault tolerance and load balancing. As a result, no single server contains or is responsible for the entire directory. The NDS servers replicate with each other to ensure that each server contains an up-to-date version of the directory for the portion of the directory that the server is responsible for. To locate an object such as a user, a group, a shared directory, or a printer on the network, an NDS client can access the directory on any NDS server.

Notes

NDS was originally called NetWare Directory Services, since it was tightly coupled to the Novell NetWare operating system. The latest version of NDS is now called Novell eDirectory.

See Also: *Active Directory, directory, eDirectory, X.500*

Nslookup

A utility for diagnosing problems with name servers.

Overview

Nslookup is a Transmission Control Protocol/Internet Protocol (TCP/IP) command-line utility for troubleshooting name servers that are part of the Domain Name System (DNS). Nslookup can be used to manually display resource records contained in the zone files of name servers. Nslookup is supported by the Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server operating systems.

Examples

Nslookup can operate in either interactive or noninteractive (batch) mode. You enter interactive mode by typing **nslookup** at the command prompt. Once in the interactive running state, you could type **ls -d microsoft.com,** for example, to list all the resource records for the microsoft.com domain that are stored in the DNS database of the name server being queried.

See Also: *Domain Name System (DNS), name server, Transmission Control Protocol/Internet Protocol (TCP/IP)*

NS record

A Domain Name System (DNS) record that identifies a secondary name server for a zone.

Overview

For each zone in the DNS namespace there are typically one or more name servers that can be used to resolve the names of hosts in that zone into their associated Internet Protocol (IP) addresses. The master name server for a zone (the name server that is authoritative for that zone) is listed in the SOA record that defines the zone's characteristics. Secondary name servers for the zone are identified by one or more NS records, one for each secondary name server in the zone. Each NS record also requires a matching A record that resolves the fully qualified domain name (FQDN) of the secondary name server into its associated IP address.

NS records are also used to specify primary name servers for delegated zones. The full syntax for the NS record is found in RFC 1035.

Examples

Here is a typical example of an NS record:

```
microsoft.com.   IN   NS   ns2.microsoft.com.
```

In this example, hosts within the microsoft.com domain can be resolved using the name server called ns2. In this example IN stands for Internet and NS stands for name server.

See Also: *A record, Domain Name System (DNS), fully qualified domain name (FQDN), name server, SOA record*

NTFS

Stands for NTFS file system, the file system of Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server.

See: *NTFS file system (NTFS)*

NTFS file system (NTFS)

The file system of Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server.

Overview

NTFS file system (NTFS) is an advanced, high-performance file system designed for use with the Windows NT and supported by Windows 2000 and later. NTFS provides better performance and reliability than the file allocation table (FAT) file system first developed for the Microsoft Disk Operating System (MS-DOS) and used in earlier versions of Windows. NTFS also supports security features for data access control and ownership privileges that make it suitable for corporate file and application servers. The following table shows a comparison between the features of NTFS and FAT.

NTFS Compared with FAT

Feature	*NTFS*	*FAT*
Local security	x	
File-level access permissions	x	
Automatic recoverability using lazy writes and transaction logging	x	Lazy writes only
File-level compression	x	
POSIX-compliant	x	
Supports Services for Macintosh	x	
Dual boot with Windows 95 and Windows 98		x
Maximum volume size	2^{64} = 32 exabytes (theoretical) 2^{41} = 2 terabytes (practical)	2^{32} = 4 gigabytes (GB)
Optimal volume size	Less efficient for volumes under ~50 megabytes (MB)	Less efficient for volumes over ~500 MB

Windows 2000, Windows XP, and Windows .NET Server support a new version of NTFS called NTFS5 that includes additional features not supported by the earlier NTFS4 of Windows NT. These features provide greater manageability and enhanced security and include

- **Multiple data streams:** Allow libraries of files to be defined as alternate streams.
- **Reparse points:** Alter the way in which NTFS resolves path names.
- **Change journal:** Provides a persistent log of all changes made to files on the volume.

- **Encryption:** Allows data to be stored in encrypted form using the Encrypting File System (EFS).
- **Sparse file support:** Allows programs to create very large files while consuming disk space only as needed.
- **Disk quotas:** Allow administrators to control how much disk space users have access to.
- **FAT32:** Supports an enhanced version of FAT first included with the OSR2 version of Windows 95. FAT32 supports larger disk partitions than FAT.
- **Universal Disk Format (UDF):** The replacement for the earlier Compact Disk File System (CDFS). UDF is an international standard (ISO-13346) that supports both CD-ROM and DVD-ROM drives.

Architecture

Like FAT, NTFS uses the cluster as the fundamental unit of disk space allocation. The default size of the clusters for an NTFS volume depends on the size of the volume, as shown in the table. When you create a new NTFS volume by formatting a disk partition with NTFS, the master file table (MFT), which contains information concerning all the files and folders stored on the volume, is created. The MFT is located on the disk immediately after the partition boot sector, which contains the BIOS parameter block and the code that enables the operating system to find and load the startup files. After the MFT comes NTFS system files, which help implement NTFS by storing information such as the contents of the volume, volume name and version, table of attribute names and numbers, a list of transaction steps used for NTFS recoverability, and the root folder. After the NTFS system files is the file area where user data can be stored. The total overhead of the MFT and NTFS system files is about 1 MB.



NTFS file system (NTFS). *Structure of an NTFS volume.*

Default Cluster Sizes for NTFS

Volume Size	*Sectors/ Cluster*	*Cluster Size*
512 MB or less	1	512 bytes
513 KB–1024 MB	2	1 kilobyte (KB)
1025 MB–2048 MB	4	2 KB
2049 MB–4096 MB	8	4 KB
4097 MB–8192 MB	16	8 KB
8193 MB–16384 MB	32	16 KB
16385 MB–32768 MB	64	32 KB
32769 MB or more	128	64 KB

Notes

Note that Windows NT 4 systems must be running Service Pack 4 or later to read basic volumes formatted using the Windows 2000 version of NTFS. Also, because of the different disk structures, Windows NT 4 disk utilities such as Autochk and Chkdsk will not work on Windows 2000, Windows XP, or Windows .NET Server NTFS volumes. Because of these incompatibilities, Microsoft Corporation does not recommend dual booting between Windows NT 4 and Windows 2000.

See Also: *file allocation table (FAT), file system*

NTFS permissions (Windows 2000, Windows XP, and Windows .NET Server)

A set of permissions used in Microsoft Windows 2000, Windows XP, and Windows .NET Server to secure folders and files located on an NTFS file system (NTFS) partition or volume.

Overview

NTFS permissions provide security for both local and network access to the file system. They are different from shared folder permissions, which can be applied only to folders and which secure the file system for network access only, not for local access.

NTFS permissions in Windows 2000 differ depending on whether they are applied to files or to folders. The five standard file permissions and six standard folder permissions are listed in the following tables. These standard file and folder permissions are actually composed of various groupings of the 18 different special permissions—for more information, see the "NTFS special permissions (Windows 2000, Windows XP, and Windows .NET Server)" article elsewhere in this book. These groupings simplify the job of securing files and folders on NTFS file system partitions and volumes.

Standard NTFS File Permissions in Windows 2000, Windows XP, and Windows .NET Server

File Permission	*User Access Granted*
Read	Open the file and view its permissions, attributes, and ownership
Write	Modify the file, modify its attributes, and view its permissions, attributes, and ownership
Read & Execute	Delete the file and do everything Read permission allows
Modify	Delete the file and do everything Read & Execute and Write permissions allow
Full Control	Take ownership, modify permissions, and do everything Modify permission allows

Standard NTFS Folder Permissions in Windows 2000, Windows XP, and Windows .NET Server

Folder Permission	*User Access Granted*
Read	View contents of folder and view its permissions, attributes, and ownership
Write	Create new files and folders in the folder, modify its attributes, and view its permissions, attributes, and ownership
List Folder Contents	View contents of folder
Read & Execute	View subfolders within the folder and do everything Read and List Folder Contents permissions allow
Modify	Delete the folder and do everything Read & Execute and Write permissions allow
Full Control	Take ownership, modify permissions, and do everything Modify permission allows

To use these standard permissions to secure a file or folder, you must be the object's owner, have full control of the object, or be a member of the Administrators system group. You must explicitly assign a permission to a file or folder for the permission to be granted. If no permission is specified for a given user or group, the user or group has no access to the file or folder. When you explicitly assign a permission, you can choose to either allow or deny that permission.

When you create a file or folder on an NTFS file system volume, it inherits the permissions of its parent folder or volume. When you assign a permission to a parent folder or volume, you have the option of propagating that permission to all of its child folders and files.

The following rules apply to assigning permissions for files and folders on NTFS file system volumes:

- If a user belongs to two or more groups and the groups have different permissions on a given folder, the user's effective permission is the least restrictive of the permissions. For example, if a user has Read permission on a file and a group the user belongs to has Modify permission, the user's effective permission is Modify, which is the least restrictive of the two.
- A permission explicitly denied overrides a similar permission explicitly allowed. For example, if a user has Read permission on a file and a group the user belongs to has been denied Read permission, the user cannot open and read the file.
- A permission for a file overrides a similar permission for the folder containing the file. For example, if a user has Modify permission on a file and Read permission on the folder containing the file, the user can open, read, edit, and save changes to the file.

Notes

The differences between NTFS standard permissions for the Windows 2000, Windows XP, and Windows .NET Server operating systems and those for Windows NT include the following:

- Windows 2000, Windows XP, and Windows .NET Server have six folder permissions; Windows NT has seven.

- Windows 2000, Windows XP, and Windows .NET Server have five file permissions; Windows NT has four.
- In Windows 2000, Windows XP, and Windows .NET Server, you can explicitly grant or explicitly deny any standard file or folder permission. In Windows NT, you can only explicitly grant a permission (but you can explicitly grant no access as a permission).

When you format a partition or volume using NTFS, the Everyone system group is automatically assigned full control permission for the root of the volume. Any new files or folders you create on the volume inherit this permission. Be aware that leaving full control for everyone might create a security risk; you should replace it with more suitable permissions such as full control for the Authenticated Users special identity.

See Also: *NTFS permissions (Windows NT), NTFS special permissions (Windows 2000, Windows XP, and Windows .NET Server), NTFS special permissions (Windows NT)*

N

NTFS permissions (Windows NT)

A set of permissions used in Microsoft Windows NT to secure folders and files on an NTFS file system (NTFS) partition.

Overview

NTFS permissions provide security for both local and network access to the file system. They are different from shared folder permissions, which can be applied only to folders and which secure the file system for network access only, not for local access.

NTFS permissions in Windows NT differ depending on whether they are applied to files or to folders. The four standard file permissions and seven standard folder permissions are listed in the following tables. These standard file and folder permissions are actually composed of various groupings of six NTFS special permissions:

- Read (R)
- Write (W)
- Execute (X)
- Delete (D)
- Change Permission (P)
- Take Ownership (O)

For more information on these special permissions, see the "NTFS special permissions (Windows NT)" article elsewhere in this book.

Standard NTFS File Permissions in Windows NT

File Permission	*Special Permissions*
Full Control	RWXDPO
Change	RWXD
Read	RX
No Access	None

Standard NTFS Folder Permissions in Windows NT

Folder Permission	*Special Permissions for Folders*	*Special Permissions for Files in a Folder*
Full Control	RWXDPO	RWXDPO
Change	RWXD	RWXD
Add & Read	RWX	RX
Add	WX	Unspecified
Read	RX	RX
List	RX	Unspecified
No Access	None	None

To use these standard permissions to secure a file or folder, you must be the object's owner, have full control of the object, or be a member of the Administrators system group. You must explicitly assign a permission to a file or folder for the permission to be granted. If no permission is specified for a given user or group, the user or group has no access to the file or folder.

When you create a file or folder on an NTFS file system partition, it inherits the permissions of its parent folder or partition. When you assign a permission to a parent folder or partition, you have the option of propagating that permission to all of its child folders and files.

The following rules apply to assigning permissions for files and folders on NTFS file system volumes:

- If a user belongs to two or more groups and the groups have different permissions in a given folder, the user's effective permission is the least restrictive of the permissions. For example, if a user has Read permission on a file and a group the user belongs to has Change permission, the user's effective permission is Change, which is the less restrictive of the two.

- The No Access permission overrides all other permissions. For example, if a user has Read permission on a file and a group the user belongs to has No Access permission, the user cannot open and read the file.
- A permission for a file overrides a similar permission for the folder containing the file. For example, if a user has Change permission on a file and Read permission on the folder containing the file, the user can open, read, edit, and save changes to the file.

Notes

For a description of the differences between NTFS standard permissions for Windows 2000 and for Windows NT, see the "NTFS permissions (Windows 2000)" article elsewhere in this book.

In most cases NTFS standard permissions are sufficient for controlling access to a file or folder. If standard permissions are not sufficiently granular for your purposes, you can use NTFS special permissions.

See Also: *NTFS permissions (Windows 2000, Windows XP, and Windows .NET Server), NTFS special permissions (Windows 2000, Windows XP, and Windows .NET Server), NTFS special permissions (Windows NT)*

NTFS special permissions (Windows 2000, Windows XP, and Windows .NET Server)

Individual permissions granted or denied when NTFS file system (NTFS) standard permissions are not sufficiently granular for specific security purposes.

Overview

NTFS special permissions available depend on whether you are securing files or folders. In both cases, 14 special permissions are available; 10 of these are common to the two scenarios. The following tables list the various NTFS special permissions available in Microsoft Windows 2000, Windows XP, and Windows .NET Server.

NTFS Special Permissions for Both Files and Folders in Windows 2000, Windows XP, and Windows .NET Server

Special Permission	*User Access Granted*
Read Attributes	View the attributes (including read-only, hidden, system, and archive) of the file or folder
Read Extended Attributes	View custom attributes that can be defined by certain applications for the file or folder
Write Attributes	Modify the attributes of the file or folder
Write Extended Attributes	Modify custom attributes that can be defined by certain applications for the file or folder
Delete Subfolders And Files	Delete subfolders or files
Delete	Delete the file or folder; however, even if this permission is denied on a file, you can delete it if its parent folder has been granted Delete Subfolders And Files permission
Read Permissions	View the permissions on the file or folder
Change Permissions	Modify the permissions on the file or folder
Take Ownership	Take ownership of the file or folder
Synchronize	Lets threads in multithreaded programs wait on the file or folder handle and synchronize with another thread that signals it

NTFS Special Permissions Only for Files in Windows 2000, Windows XP, and Windows .NET Server

Special Permission	*User Access Granted*
Execute File	Execute the file
Read Data	Read the file
Write Data	Modify the file
Append Data	Append to the file (but not modify existing data)

NTFS Special Permissions for Folders in Windows 2000, Windows XP, and Windows .NET Server

Special Permission	*User Access Granted*
Traverse Folder	Drill down to other files and folders in the folder even if you have no permissions on intermediate subfolders
List Folder	View the names of subfolders and files in the folder
Create Files	Create files in the folder
Create Folders	Create subfolders within the folder

You can grant or deny special permissions by using the Advanced button on the Security tab of a file's or folder's property sheet. You can select different combinations of special permissions to create custom sets of permissions for special purposes. In most cases, however, it is simplest to use NTFS standard permissions for securing files and folders. If you use special permissions, there is a lot of flexibility in how you can apply them, especially if you are applying them to a folder. For example, you can apply a custom set of special permissions to

- The selected folder only
- The selected folder, its subfolders, and files
- The selected folder and its subfolders only
- The selected folder and its files only
- Subfolders and files of the selected folder but not the folder itself
- Subfolders of the selected folder but not the folder itself
- Files in the selected folder but not the folder itself

To use special permissions you must be the object's owner, have full control of the object, or be a member of the Administrators group.

Notes

In Windows XP and Windows .NET Server, the Full Control permission is listed in the Special Permissions screen. When selected, Full Control gives the user all special permissions that apply to the file or folder.

There are significant differences between NTFS special permissions for Windows 2000, Windows XP, and Windows .NET Server and those for Windows NT. The most obvious difference is that in Windows 2000, Windows XP, and Windows .NET Server, you can assign any of 14 special permissions, but in Windows NT you have 6 special permissions to choose from: Read (R), Write (W), Execute (X), Delete (D), Change Permission (P), and Take Ownership (O). The reason for this difference is that in Windows NT much of the machinery of NTFS is hidden from the user interface, but in Windows 2000, Windows XP, and Windows .NET Server, this machinery is exposed in the user interface.

See Also: *NTFS permissions (Windows 2000, Windows XP, and Windows .NET Server), NTFS permissions (Windows NT), NTFS special permissions (Windows NT)*

NTFS special permissions (Windows NT)

Individual permissions granted or denied when NTFS file system (NTFS) standard permissions are not sufficiently granular for specific security purposes.

Overview

The special permissions available are the same whether you are securing files or folders, with the exception that when you secure a directory you have the additional option of leaving access unspecified instead of assigning a specific set of special permissions. In both cases, six special permissions are available; these are listed in the following table.

NTFS Special Permissions in Windows NT

Special Permission	*Symbol*	*User Access When Applied to Files*	*User Access When Applied to Folders*
Read	R	View file owner and permissions Read the file	View contents of the folder View folder attributes View folder owner and permissions

(continued)

NTFS Special Permissions in Windows NT *continued*

Special Permission	*Symbol*	*User Access When Applied to Files*	*User Access When Applied to Folders*
Write	W	View file owner and permissions Modify file attributes Edit the file	Add files to the folder Add sub-folders Modify folder attributes View folder owner and permissions
Execute	X	View file owner and permissions Modify file attributes Run the executable file	View folder attributes Browse folder hierarchy View folder owner and permissions
Delete	D	Delete the file	Delete the folder
Change Permission	P	Change file permissions	Change folder permissions
Take Ownership	O	Take ownership of the file	Take ownership of the folder

By selecting different combinations of special permissions, you can create custom sets of permissions for special purposes. In most cases, however, NTFS standard permissions are sufficient for securing files and folders. To use special permissions, you must be the object's owner, have full control of the object, or be a member of the Administrators system group. For information on which sets of special permissions comprise the various standard permissions, see the "NTFS permissions (Windows NT)" article elsewhere in this book.

Notes

For a description of the differences between NTFS special permissions for Microsoft Windows NT and for Microsoft Windows 2000, see the "NTFS special permissions (Windows 2000, Windows XP, and Windows .NET Server)" article elsewhere in this book.

See Also: *NTFS permissions (Windows 2000, Windows XP, and Windows .NET Server), NTFS permissions (Windows NT), NTFS special permissions (Windows 2000, Windows XP, and Windows .NET Server)*

NTLM protocol

Another name for Windows NT Challenge/Response Authentication, an authentication scheme used in Microsoft Windows NT–based networks.

See: *Windows NT Challenge/Response Authentication*

NTP

Stands for Network Time Protocol, an Internet protocol for synchronizing computer clocks to an accurate reference clock.

See: *Network Time Protocol (NTP)*

NTU

Stands for Network Termination Unit, a telecommunications device used in Integrated Services Digital Network (ISDN) networking.

See: *Network Termination Unit (NTU)*

NTVDM

Stands for NT Virtual DOS Machine, an MS-DOS environment simulator in Windows NT.

See: *NT Virtual DOS Machine (NTVDM)*

NT Virtual DOS Machine (NTVDM)

An MS-DOS environment simulator in Microsoft Windows NT.

Overview

NT Virtual DOS Machine (NTVDM) is a single-threaded Win32 application that simulates an MS-DOS environment on Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server. The

NTVDM enables the system to properly run MS-DOS and Windows 3.*x* applications. Each MS-DOS–based application running on Windows NT requires its own NT Virtual DOS Machine (NTVDM). As a result, if an MS-DOS–based application fails while running on Windows NT, it does not affect other MS-DOS-based applications.

You can customize the NTVDM for an MS-DOS–based application by right-clicking on the application's executable file and choosing Properties. The settings you can configure are similar to those available in the Windows 3.*x* tool PIF Editor.

See Also: *Microsoft Disk Operating System (MS-DOS), Windows NT*

null modem cable

A serial cable with cross-pinning that is used for file transfers and for other specialized communication between computers.

Overview

Null modem cables, also known as file transfer cables, are used to directly connect two computers for transferring files between them—for example, by using the Direct Cable Connection accessory of Microsoft Windows 95 and Windows 98. Note that parallel data-transfer cables achieve faster data transfer rates for file transfer than serial null modem cables.

N

The most common form of null modem cable is based on the RS-232 serial transmission interface specifications. Pins 2 and 3 are crossed in a null modem cable to allow you to directly link two RS-232 serial ports on different computers. Other pins can also be crossed depending on the intended purpose of the cable. The most common forms of termination for these cables are DB9 and DB25 connectors.

Serial RS-232 null modem cables support distances of up to about 50 feet (15 meters) and can be used for any communication for which a direct DTE-to-DTE connection or DCE-to-DCE connection is required. If longer distances are needed in serial communication, you can use a line driver to amplify the signal up to several kilometers. A cable connecting two pieces of data terminal equipment (DTE) is specifically called a null modem cable, but a cable connecting two pieces of data communications equipment (DCE) is usually called a tail-circuit cable and has a different cross-pinning. You can obtain null modem cables for other serial interfaces such as V.35 and those with special types of pinning.

Notes

Use a shielded null modem cable to extend distances up to 98 feet (30 meters) without using line drivers.

See Also: *data communications equipment (DCE), data terminal equipment (DTE), RS-232, serial transmission*

NWLink

Stands for NWLink IPX/SPX-Compatible Transport, Microsoft Corporation's version of Novell's legacy Internetwork Packet Exchange/Sequential Packet Exchange (IPX/SPX).

See: *NWLink IPX/SPX-Compatible Transport (NWLink)*

NWLink IPX/SPX-Compatible Transport (NWLink)

Microsoft Corporation's version of Novell's legacy Internetwork Packet Exchange/Sequential Packet Exchange (IPX/SPX).

Overview

IPX/SPX is a legacy networking protocol used in Novell NetWare 2.*x* and 3.*x*. NWLink IPX/SPX-Compatible Transport (NWLink) is Microsoft's 32-bit version of this protocol for the Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server platforms.

NWLink supports the following features:

- Compliance with network driver interface specification (NDIS) 4 on Windows NT and NDIS 5 on Windows 2000, Windows XP, and Windows .NET Server.
- Support for NetBIOS over NWLink (NWLink NetBIOS)

- Support for the following interprocess communications (IPC) mechanisms: Windows Sockets, named pipes, and remote procedure calls (RPCs)

Uses

NWLink can be used on Microsoft platforms when

- Microsoft clients such as Windows NT Workstation, Windows 2000 Professional and Windows XP Professional require access to NetWare file, print, and application servers. These clients can access NetWare servers either directly using Client Services for NetWare (CSNW) or through a gateway server running Gateway Service for NetWare (GSNW).
- NetWare clients need access to servers running Windows NT, Windows 2000, and Windows .NET Server. NetWare clients can access file and print services directly on Windows servers using File and Print Services for NetWare (FPNW).

Notes

If a Windows NT, Windows 2000, Windows XP, or Windows .NET server or client with NWLink installed is unable to communicate with NetWare clients or servers, check the properties of NWLink to make sure you are using the same frame type as the machines running NetWare. Note that you must also specify IPX/SPX network numbers when configuring NWLink.

See Also: *Client Services for NetWare (CSNW), File and Print Services for NetWare (FPNW), Gateway Service for NetWare (GSNW), NetBIOS, NetWare, network driver interface specification (NDIS)*

OASIS

Stands for Organization for the Advancement of Structured Information Systems, a nonprofit consortium that promotes Extensible Markup Language (XML) standards.

See: *Organization for the Advancement of Structured Information Systems (OASIS)*

object (Active Directory)

An element of Active Directory directory service that represents a network resource.

Overview

Some common types of objects in Active Directory include

- **Users:** Required for users to log on to the network.
- **Groups:** Collections of user accounts, computers, or other groups created for organizational purposes or for assigning permissions to shared resources.
- **Computers:** Represent machines that belong to the domain.
- **Shared folders:** Pointers to shared folders on a server on the network. If you create a shared folder on a computer running Microsoft Windows 2000, an associated shared folder object is automatically created in Active Directory.
- **Printers:** Pointers to printers on the network. If you create a network printer on a machine running Windows 2000, an associated printer object is automatically created in Active Directory.

Objects have attributes that define and describe them. For example, the attributes of a user object might include the user's name, e-mail address, and phone number. All objects of the same type or class have the same set of attributes, but they are distinguished from each other by having different values for at least one of these attributes. Some attributes are required to have values (such as the First Name attribute of a user object), but other attributes can be optional (such as Telephone Number).

You can group objects by placing them into container objects (containers) such as the following:

- **Domains:** The fundamental units of Active Directory that share common administration, security, and replication requirements. Domains can also be grouped into domain trees and forests to reflect an enterprise's administrative structure.
- **Organizational units (OUs):** Container objects that are used to organize other directory objects. OUs are part of the hierarchical structure of Active Directory, and allow objects are grouped according to common functions and purposes to simplify network administration. The hierarchical grouping of objects and OUs also simplifies the process of searching Active Directory for information about network resources.

Access to an object in Active Directory is based on the object's discretionary access control lists (DACLs), which list the users and groups authorized to access the object and their access levels. You can group objects with similar security requirements into OUs to simplify assignment of permissions to the objects and to facilitate administration and control of network resources. You can assign permissions to objects by using Active Directory Users and Computers, a snap-in for Microsoft Management Console (MMC).

Objects can be referenced by name by using

- **Distinguished names:** Analogous to absolute paths of objects within a file system. The distinguished name of an object specifies complete information about the object's location within Active Directory and includes the domain name, names of OUs that it belongs to, and the name of the object itself. Each object in Active Directory must have a unique distinguished name.

- **Relative distinguished names:** Analogous to relative paths of objects in the current directory of a file system. The relative distinguished name of an object is the portion of the distinguished name that is unique to the object. Any two objects in the same OU need to have unique, differing relative distinguished names.

Notes

When you use Active Directory Users and Computers to view the property sheet for an object, the Security tab, which displays the Active Directory permissions assigned to that object, is usually not visible. Choose Advanced Features from the View menu to make this tab visible.

If you have resources such as shared folders or printers on computers that are not running Windows 2000 or Windows .NET Server, you must manually publish information about these resources in Active Directory if you want users to be able to locate and access them through Active Directory. You do this by adding the appropriate type of object for that resource to Active Directory and having it point to where the resource is located on the network.

When you create a new Active Directory object, you usually use a wizard to specify values for the important attributes of the object. You can specify other attributes after the object is created by opening the property sheet for that object.

See Also: *Active Directory, organizational unit (OU)*

object identifier (OID)

A numeric value that universally identifies data and syntax elements for certain distributed systems.

Overview

Object identifiers (OIDs) are employed in distributed systems such as X.500 and Lightweight Directory Access Protocol (LDAP) directories, Simple Network Management Protocol (SNMP) management systems, Open Systems Interconnection (OSI) applications, and so on. In the directory arena, for example, OIDs are used to identify the various classes and attributes used by Microsoft Active Directory for Windows 2000 and by Novell Directory Services (NDS).

OIDs are assigned by organizations that are recognized as issuing authorities, such as the International Organization for Standardization (ISO), which also maintains a complete list of the world's various issuing authorities. In the United States, for example, the issuing authority is the American National Standards Institute (ANSI).

Examples

In Microsoft's Active Directory directory service, for example, OIDs are used as globally unique identifiers for object classes and attributes. OIDs ensure that when Active Directory is integrated with other directory systems, no conflicts occur, as each attribute and class in Active Directory has an OID that is globally unique. The OID for a class or attribute remains unchanged even when the distinguished name of a directory object is modified because of system configuration changes.

OIDs are expressed in dotted numeric form using an explicitly defined hierarchy of possible values. For example, the OID 1.2.840.113556.1.5.4 represents the Builtin-Domain class of objects within Active Directory. You can determine this by parsing the OID tree as follows:

`1`	`ISO`
`2`	`ANSI`
`840`	`United States`
`113556`	`Microsoft`
`1`	`Active Directory Service`
`5`	`Classes`
`4`	`Builtin-Domain`

An example of an object identifier for a different U.S. company might be 1.2.840.105670, where 1.2.840 is assigned to U.S. companies and 105670 is the number assigned to the specific company. Once your company has an object identifier, you can extend it by appending dotted decimal portions. So if 1.2.840.105670 represents Northwind Traders, 1.2.840.105670.27 might represent the Sales division, 1.2.840.105670.33 might represent the Support division, and so on. Further levels of subdivision are also possible.

Notes

If you want to use Active Directory Schema Manager to create a new class of objects or a new attribute in Active Directory, you should first obtain an object identifier for your organization from ANSI, ISO, or some other issuing authority.

See Also: *Active Directory, American National Standards Institute (ANSI), directory, International Organization for Standardization (ISO), Lightweight Directory Access Protocol (LDAP), Management Information Base (MIB), Novell Directory Services (NDS), Simple Network Management Protocol (SNMP), X.500*

object linking and embedding (OLE)

A low-level object-oriented technology that was the precursor of the Component Object Model (COM).

Overview

Object linking and embedding (OLE) was an early Microsoft technology for programmatically providing services to applications to support the creation of compound documents. For example, using OLE, you could insert bitmap images, sound clips, spreadsheet files, and other objects into Microsoft Word documents.

The term *object linking and embedding* comes from the two possible ways in which OLE enabled the creation of compound documents, specifically:

- Linking adds a link in a document that points to source data stored somewhere else. Linked objects are stored in the document as a path to the original linked data, usually a separate file from the container document.
- Embedding, on the other hand, adds one document directly to the other. Embedded objects are stored with the document that contains them.

History

The meaning of the term *OLE* has shifted somewhat since Microsoft Corporation first introduced it in 1991. Version 1 of OLE, referred to as OLE 1, was Microsoft's first mechanism for creating compound documents. OLE 2, the second version of OLE, improved on OLE 1 and expanded the support for creating more complex compound documents. OLE 2 was based on a new model known as the Component Object Model (COM). Microsoft began to recognize that OLE 2 could be used to solve other software problems and that it could be applied to other areas of software development. Microsoft saw OLE 2 as an expandable architecture to create software and, as such, decided to drop the version number. Microsoft also reduced the name from *object linking and embedding (OLE)* to just *OLE*, with no spell-out. At that time, OLE referred to any technology based on COM. In 1996, Microsoft introduced the term *ActiveX* which initially referred using to COM-based technologies on the Internet, but ActiveX also overlapped with OLE. Soon, OLE technologies were being referred to as *ActiveX technologies*. At that time, Microsoft decided to change the name *OLE* back to its original name, *object linking and embedding (OLE)*, and once again use it to refer to technologies for creating compound documents and the linking and embedding of objects.

Architecture

An OLE application can be one or both of the following:

- **OLE server application:** Used to create objects that will be contained in compound documents. A server application can create OLE components that can be placed in documents created by OLE container applications.
- **OLE container application:** Used to create the actual compound documents. A container application can create documents that can contain and display OLE components using OLE.

OLE container documents support in-place activation, which allows users to activate an embedded OLE component from within the container document. Activating the component changes the container application’s user interface to include features that allow users to directly edit the component from within the container document.

See Also: *ActiveX, Component Object Model (COM)*

object (programming)

A construct containing data as well as methods (functions for manipulating the construct’s data).

Overview

Object-oriented programming (OOP) focuses on objects instead of functions for manipulating separate data entities. The “blueprint” for an object is a class; a specific object is an “instance” of a class that you access using its associated methods. New classes can be derived from more general classes through a procedure called inheritance. The derived class contains all the methods and data of the original class, which can simplify programming.

See Also: *C++*

OBM

Stands for out-of-band management, remotely managing networking and telecommunications equipment using out-of-band (OOB) signaling.

See: *out-of-band management (OBM)*

OCSP

Stands for online certificate status protocol, an emerging specification for validating digital certificates.

See: *Online Certificate Status Protocol (OCSP)*

OC-x

Stands for optical carrier level, a measure of Synchronous Optical Network (SONET) capacity.

See: *optical carrier (OC-x) level*

ODBC

Stands for open database connectivity, a standard method of accessing data stored in relational databases and other structured data sources.

See: *open database connectivity (ODBC)*

ODI

Stands for Open Data-link Interface, a legacy network protocol software interface used by early versions of Novell NetWare.

See: *Open Data-link Interface (ODI)*

OFDM

Stands for orthogonal frequency division multiplexing, an emerging technology for achieving higher data rates in wireless communications.

See: *Orthogonal Frequency Division Multiplexing (OFDM)*

offline browsing

A feature of Microsoft Internet Explorer that allows users to browse cached or subscribed Web content when they are not connected to the Internet.

Overview

Offline browsing is an easy way to browse Web content on a laptop when an Internet connection is not available. Users can surf their history folder to view recently accessed Uniform Resource Locators (URLs). If users click on an unsaved link, they are notified that they are working offline and are asked whether they would like to connect to the Internet to access the resource.

When you add a Web page to your Favorites list, you can specify that the page be available for offline browsing, indicate how deep you want to be able to browse the page’s links offline, and specify how you want to keep the offline content up to date. To view the site offline later, you can

- Choose Synchronize from the Favorites menu to manually synchronize offline content

- Choose Work Offline from the File menu to switch to offline browsing mode
- Select the item from your Favorites list

To leave Work Offline mode, choose Work Offline from the File menu.

See Also: *Internet Explorer*

Offline Files

A feature of Windows 2000, Windows XP, and Windows .NET Server that lets you continue working with shared network resources after you disconnect from the network.

Overview

Shared files and folders from any computer that supports Server Message Block (SMB)–based file and print sharing, such as those running Windows .NET Server, Windows XP, Windows 2000, Windows NT 4, Windows 98, or Windows Millennium Edition (Me), can be made available for offline use by Windows 2000 or Windows XP clients. These clients that are configured to use offline folders can cache the network resources in a local folder. When disconnected from the network, the client can continue working normally on the cached files. The client can then synchronize the contents of the cache with the network share when the connection is restored.



Synchronizing \\leonardo\screendumps
FILE PERMS RFT.RTF
0 of 1 items are complete

Name	Status	Additional information
\\leonardo\screend...	Synchronizing	FILE PERMS RFT.RTF

To skip an item, select it and choose Skip.

Offline Files in Windows 2000. *Synchronizing with a network share using Offline Files in Windows 2000.*

To enable offline file support on a computer running Windows 2000 or Windows XP, open My Computer and choose Folder Options from the Tools menu. Select the Offline Files tab and check Enable Offline Files. Specify synchronization options, a cache size, and additional advanced options. To make a share on the network available for offline use, select the share in My Computer (where it might appear as a mapped network drive) or My Network Places (where it will appear as a network share) and choose Make Available Offline from the File menu. The contents of the network share will be copied to the local computer's cache in a process known as synchronizing. You can specify additional synchronization settings by selecting Settings in the Synchronizing dialog box.

OID

Stands for object identifier, a numeric value that universally identifies data and syntax elements for certain distributed systems.

See: *object identifier (OID)*

OLAP

Stands for online analytical processing, a technology that allows users to perform sophisticated data analysis on typically large amounts of enterprise data to gain insight on the information it contains.

See: *online analytical processing (OLAP)*

OLE

Stands for object linking and embedding, a low-level object-oriented technology that was the precursor of the Component Object Model (COM).

See: *object linking and embedding (OLE)*

OLE DB

A Microsoft technology for universal data access.

Overview

Based on Component Object Model (COM) technologies, OLE DB represents a specification for developing extensible COM interfaces designed to provide applications with uniform methods of accessing data from diverse data sources that can include

- Mainframe databases, including IBM's Information Management System (IMS) and DB2
- Relational databases, including Microsoft SQL Server and Oracle
- Desktop databases, including Microsoft Access, Microsoft FoxPro, and Paradox
- Other data sources, including file systems, spreadsheets, text files, and e-mail message repositories

OLE DB is a key element in Microsoft Corporation's Universal Data Access (UDA) initiative and facilitates the development of applications that combine various types of queries from diverse data sources. OLE DB is the successor to Microsoft's earlier data access technology, Open Database Connectivity (ODBC), which was limited mainly to relational databases and was based on C/C++ application programming interfaces (APIs) instead of COM.

A related technology called ActiveX Data Objects (ADO) provides a simplified front-end for OLE DB that enables access to diverse data sources through OLE DB using scripting languages such as VBScript and JScript.

Architecture

OLE DB works by enabling COM interfaces to be defined that can encapsulate various types of database functionality such as record containers, query processors, and transaction coordinators. The architecture of OLE DB has three parts:

- **Data source:** This can be any structured or unstructured source of data, including ODBC-compliant databases, legacy mainframe systems, file systems, or other data source for which an OLE DB provider can be constructed.
- **OLE DB provider:** A set of COM components designed to extract data requested by an OLE DB consumer from the data source associated with the provider and to return it to the client in tabular format. Each type of data source requires its own special provider in order for clients to be able to access the data using OLE DB. OLE DB providers are available for the full range of data sources, including SQL Server, Microsoft Jet databases, Oracle, and many other common types of data sources. There is also a generic OLE DB provider for standard ODBC-compliant databases.
- **OLE DB consumer:** Represents the client application that needs to access data from the data source. Because of the standard set of interfaces used in OLE DB providers, any consumer is able to access data from any provider. Furthermore, because providers are COM objects, consumers can access them using any programming language, including C++, Microsoft Visual Basic, and Java.



OLE DB. *The architecture of an OLE DB system.*

Examples

As an example of an OLE DB provider, the OLE DB Provider for AS/400 and VSAM enables record-level access to mainframe Virtual Storage Access Method (VSAM) files and to the AS/400 native file system. The OLE DB Provider for AS/400 and VSAM is included with Microsoft Host Integration Server. You use the OLE DB Provider for AS/400 and VSAM to develop applications for discrete data access and for record-level access to physical and logical files on AS/400 systems, in Partitioned Data Sets (PDS) and Partitioned Data Set Extended (PDSE) files, and in most versions of VSAM on mainframes. Using the OLE DB Provider for AS/400 and VSAM, programmers can access mainframe VSAM or AS/400 data using Microsoft's object-based OLE DB data access technology. Programmers can thus access source data from host systems without having to learn about Systems Network Architecture (SNA) or host applications programming. The OLE DB Provider for AS/400 and VSAM facilitates a broad range of data access, from individual records to complete files. Using ActiveX Data Objects (ADO), you can develop web-to-host integration solutions using programming languages such as Microsoft Visual Basic or scripting languages such as Microsoft Visual Basic, Scripting Edition (VBScript), and Microsoft JScript.

Marketplace

OLE DB is the dominant data access technology on the Microsoft Windows platform and is widely used in Online Analytical Processing (OLAP) systems that employ a variety of popular database platforms, including Oracle, DB2, and SQL Server. A competitor to OLE DB is the Java OLAP (JOLAP) initiative, developed by Sun Microsystems, Oracle Corporation, IBM, and Hyperion Solutions Corporation. JOLAP is a specification for creating Java-based interfaces for universal data access, and JOLAP parallels OLE DB in the same way that Java Database Connectivity (JDBC) parallels ODBC.

Notes

The name OLE DB for this technology can be confusing for two reasons:

- OLE stands for “object linking and embedding,” a legacy technology that was the precursor to COM.
- DB suggests “database,” but OLE DB works with any kind of data source and is not limited to relational database systems.

See Also: *ActiveX Data Objects (ADO), Component Object Model (COM), database, Java Database Connectivity (JDBC), Java Online Analytical Processing (JOLAP), online analytical processing (OLAP), open database connectivity (ODBC)*

OLE DB for OLAP

A set of Component Object Model (COM) interfaces and objects that extends OLE DB to allow access to information stored in multidimensional information sources.

Overview

OLE DB for OLAP is included in OLE DB 2 and leverages the OLE DB architecture to enable online analytical processing (OLAP) functions for COM-based applications.

See Also: *Component Object Model (COM), OLE DB*

online analytical processing (OLAP)

A technology that allows users to perform sophisticated data analysis on typically large amounts of enterprise data to gain insight on the information it contains.

Overview

Examples of OLAP analysis include financial modeling, budget forecasting, production planning, and determining broad sales and distribution trends. A query issued in an online analytical processing (OLAP) system could be, “What would be the effect on sales over the next three quarters if the cost of widgets went up 5 percent while sales dropped 15 percent?” OLAP systems primarily focus on queries that ask “What if . . . ?” In other words, OLAP systems are designed for making predictions, modeling scenarios, and supporting decision-making.

The database for an OLAP system is typically structured to allow for efficient retrieval of information. The database can be a data warehouse. A data warehouse is a database that contains static data on a particular subject, drawn from various sources. Queries issued against data warehouses tend to focus on queries that ask “What was . . . ?” or “Who did . . . ?” and are useful for analyzing past sales and growth figures. For example, “What were the total sales for the five largest subsidiaries in the first two quarters of last year?” OLAP systems and data warehouses thus constitute two complementary tools for analyzing and interpreting business data in order to make intelligent decisions.

An OLAP system is typically based on a multidimensional model, which allows users to select, explore, and view the data easily. An OLAP system generally provides the technology for creating and managing the databases. An OLAP system can have tools to discover relationships between data items by comparing the results of various OLAP queries.

Microsoft SQL Server includes tools for data warehousing and online analytical processing, including Data Transformation Services (DTS) Designer and SQL Server OLAP Services (now called Analysis Services). You can use DTS Designer to specify the workflow steps and transactions for combining multiple heterogeneous data sources into a data warehouse. You can then use OLAP Services to analyze the data, preaggregate data into multidimensional cubes for frequently asked queries, model data, create new views, and perform ad hoc sets of calculations.

For More Information

Visit the OLAP Council at *www.olapcouncil.org.*

See Also: *database*

Online Certificate Status Protocol (OCSP)

An emerging specification for validating digital certificates.

Overview

Traditional public key infrastructure (PKI) systems allow recipients of digitally signed documents to check the validity of digital certificates through comparison with a certificate revocation list (CRL), a list of invalid or expired certificates. This has several disadvantages:

- It places the burden of processing on the client, and for large CRLs, this can consume a lot of time.
- CRLs are typically updated every few days, so a client could receive a document with a compromised certificate and not be able to know it.

As a result of these problems, widespread adoption of digital signatures and certificates in business-to-business (B2B) e-commerce transactions has been slow. To overcome this, the Internet Engineering Task Force (IETF) has developed the Online Certificate Status Protocol (OCSP) specification to speed the process of validating certificates and shift the burden of processing away from the client.

Implementation

OCSP is implemented using strategically placed special servers called responders that maintain up-to-date CRL information. These responders are linked together using OCSP to ensure that they all share common CRL information. When a B2B trading partner sends a client a digitally signed document over the Internet, the client verifies the validity of the certificate by formatting a special request and submitting it to a responder. The responder either issues an authoritative reply such as GOOD, REVOKED, or UNKNOWN, or forwards the request to the trading partner's responder or to a third-party responder for validation.

See Also: *B2B, digital certificate, digital signature, public key infrastructure (PKI)*

OnNow

A power-management design initiative from Microsoft Corporation.

Overview

OnNow combines innovations in PC hardware and software to produce a computer that is always on but appears to be off and that responds immediately when a user or application makes a request. For example, an incoming telephone call could wake the computer and start a Telephony Application Programming Interface (TAPI)–enabled application. OnNow is designed to make personal computers function like appliances in the sense that they respond instantly to user action instead of requiring a warm-up period or boot process. OnNow is based on the Advanced Configuration and Power Interface (ACPI) specification developed by Intel Corporation, Microsoft, and Toshiba Corporation.

The power management functions of Microsoft Windows 2000, Windows XP, and Windows .NET Server, as well as those of Windows 98 and Windows Millennium Edition (Me), conform to the OnNow specifications. Instead of having the system basic input/output system (BIOS) control the power state of the system devices and peripherals, OnNow lets the operating system control it. The operating system can place various devices in a sleep state to conserve power and wake them to full power instantly when a user or application issues a request. For OnNow to function as designed, the system must have peripherals and applications that support OnNow power-management functions and the system BIOS must support ACPI.

For More Information

Find out more at *www.microsoft.com/hwdev/onnow.*

See Also: *Advanced Configuration and Power Interface (ACPI)*

OOB

Stands for out-of-band signaling, any transmission technology in which signaling is separate from the data being transmitted.

See: *out-of-band (OOB) signaling*

OpenBSD

A free version of UNIX.

Overview

OpenBSD is based on the BSD 4.4 operating system and is maintained and supported by a large community of developers. Theo de Raadt, a computer science graduate of the University of Calgary in Alberta, Canada, heads the OpenBSD project. OpenBSD is viewed as one of the most secure UNIX platforms available; even its default installation is fairly hacker-proof. OpenBSD includes support for the Kerberos IV security protocol and Internet Protocol Security (IPsec). OpenBSD also supports binary emulation of most software written for other popular UNIX flavors, such as HP-UX, SunOS, Solaris (SVR4), Linux, and FreeBSD. The current release of the OpenBSD software is version 2.5.

For More Information

Find out more about OpenBSD at *www.openbsd.org.*

See Also: *UNIX*

open database connectivity (ODBC)

A standard method of accessing data stored in relational databases and other structured data sources.

Overview

Microsoft open database connectivity (ODBC) is a database access technology that specifies a series of C/C++ application programming interfaces (APIs) that enable Microsoft Windows–based applications to access data stored in ODBC-compliant databases. ODBC thus defines a call-level interface that lets applications access data in any data source by using a suitable ODBC driver. Therefore, the ODBC APIs allow applications to be written independently of the specific database management systems (DBMSs) that contain their source data.

ODBC was originally a specification developed by an industry consortium called X/Open, which is now known as the Open Group. ODBC defines a call-level interface for implementing queries using structured query language (SQL).

Implementation

The main components of ODBC are

- **ODBC API:** A set of function calls, error codes, and SQL syntax that defines how data in a DBMS is accessed.
- **ODBC database drivers:** Dynamic-link libraries (DLLs) that can process ODBC function calls for specific DBMSs. ODBC drivers translate application calls to ODBC into calls that the specific DBMS can respond to.
- **ODBC Driver Manager:** Loads the ODBC drivers that an application needs.

ODBC uses database drivers to link applications to any ODBC-compliant DBMS. ODBC database drivers are available for more than 50 popular DBMSs, including Microsoft SQL Server, Microsoft Access, Microsoft FoxPro, Microsoft Excel, Paradox, dBASE, and delimited text files. With ODBC, applications are not tied to proprietary vendor APIs and can run independently of the underlying data communication protocols. Data can be sent and received in a format suitable for the application instead of being tailored for a vendor-specific DBMS.

Prospects

Microsoft ODBC was designed for the Windows platform. ODBC is implemented as a set of C/C++ function calls and is thus not easily accessed by other languages, such as Microsoft Visual Basic or Sun Microsystems'

Java language. ODBC is considered a legacy technology and has been superseded largely by OLE DB, Microsoft's COM-based specification for enabling universal data access using any programming language. The parallel to ODBC on the Java platform is Java Database Connectivity (JDBC).

See Also: *Component Object Model (COM), dynamic-link library (DLL), OLE DB, Java Database Connectivity (JDBC), Structured Query Language (SQL)*

Open Data-link Interface (ODI)

A legacy network protocol software interface used by early versions of Novell NetWare.

Overview

Novell and Apple Computer developed the ODI specification for defining the communication mechanism between network interface card (NIC) drivers and network protocols. Open Data-link Interface (ODI) is a legacy standard that was defined primarily for the Internetwork Packet Exchange (IPX) protocol on Novell NetWare 2.*x* and 3.*x* networks. ODI allows multiple NICs to be bound to multiple protocols.

Microsoft's NWLink IPX/SPX-Compatible Transport supports ODI for backward compatibility, but ODI has been superseded on Microsoft platforms by the network driver interface specification (NDIS).

See Also: *Internetwork Packet Exchange (IPX), NetWare, network driver interface specification (NDIS), network interface card (NIC)*

Open Shortest Path First (OSPF)

A popular link state dynamic routing protocol for large Internet Protocol (IP) networks.

Overview

Open Shortest Path First (OSPF) is a routing protocol that enables routers on an IP internetwork to dynamically share their routing table information with each other. The Internet Engineering Task Force (IETF) designed OSPF in the 1980s as a replacement for the earlier Routing Information Protocol (RIP), which scaled poorly for large internetworks.

OSPF is an interior gateway protocol (IGP) used for routing traffic within an autonomous system (AS), which is a large IP network managed by a single authority. Since IGPs such as OSPF are used within (not between) autonomous systems, they are sometimes called intra-AS routing protocols (as opposed to inter-AS routing protocols). OSPF is an open standard developed by the IETF, in contrast to Interior Gateway Routing Protocol (IGRP) and Enhanced Interior Gateway Routing Protocol (EIGRP), which are both vendor-specific IGPs developed by Cisco Systems.

OSPF was originally defined in RFC 1131, but this version of the protocol was experimental and not widely deployed. OSPFv2 is defined in RFC 2328 and is the most widely deployed version of OSPF in use today. The IETF has recently developed OSPFv3, which improves on earlier versions by supporting any network layer protocol (not just IP), streamlines link state advertisements, enhances security, and supports Internet Protocol version 6 (IPv6).

Uses

OSPF is widely used in two areas of networking:

- Enterprise-level private IP internetworks, including networks that span several countries, regions, or even continents. OSPF works well in a wide area network (WAN) environment because it updates routing tables only when necessary. Although RIP is still used for some small and mid-sized networks, OSPF has become the de facto IGP for large IP networks and is generally used wherever an internetwork contains about 50 or more routers.
- The Internet, the collection of publicly accessible IP internetworks and backbones connecting them.

OSPF is supported by the Internetwork Operating System (IOS) used by Cisco routers, and by the Routing and Remote Access Service (RRAS) of Microsoft Windows 2000 and Windows .NET Server.

Architecture

Dynamic routing protocols work by enabling routers to exchange routing table information with each other automatically without administrative intervention. OSPF excels in both the way it stores routing table information and in how it keeps this information current. OSPF is a link state routing protocol, which means that OSPF routers store information about the “state of the link” between the local router and other routers. OSPF stores this information in a link state database, which essentially stores a topological map of all routers in the same administrative portion of the internetwork. This may either be all routers within the autonomous system, or, if the AS is subdivided into different areas, all routers within the local area. Each OSPF router stores this link state database information in the form of a tree whose root is centered on the local router itself.

To construct the link state database, each interface of every OSPF router is assigned a cost value. This cost is generally inversely proportional to the bandwidth of the link the interface is connected to, although different cost values can be assigned as desired to shape the flow of traffic through the network. These cost values are then used to create the metrics for different routes within routing tables, with the route having the least cost being the preferred one.

Once the link state database has been constructed, OSPF routers can then use the Shortest Path First (SPF) algorithm (also called Dijkstra’s algorithm) to compute the shortest path between any two subnets in the AS or area. Thus, when traffic needs to be routed from one point of the internetwork to another, the router calculates the optimal path from the link state database and forwards packets accordingly. The SPF algorithm enables routing information to be quickly recalculated if routers go down, a feature called Fast Convergence. The algorithm also ensures that routing loops do not occur.

OSPF routers communicate with each other using HELLO packets, which are sent periodically every 10 to 15 seconds and basically tell other OSPF routers that the sending router is still alive. If an OSPF router does not receive a HELLO packet from another router within an expected time, it assumes that the other router is down and that the link state database is no longer accurate. The router then floods the network with link state advertisements (LSAs) that are picked up by other OSPF routers, and a recalculation of the link state database for all routers is initiated. This recalculation process generally converges quickly, depending on the size of the internetwork and the number of routers used. LSAs contain information about incremental changes to network topology and therefore are efficient in terms of bandwidth usage. LSAs can be secured by either password protection or MD5 checksums.

Implementation

The reason OSPF scales well for large internetworks is because it is hierarchical in design. OSPF allows large autonomous systems to be further subdivided into multiple areas. OSPF routers within an area only need to know about other routers within their own area, not outside their area, and all OSPF routers within a given area share the same link state database. This keeps the routing tables small enough to prevent processing bottlenecks from occurring. OSPF areas within an AS are designated by unique 32-bit identifiers and typically have no more than about 30 or 40 routers within them.



Open Shortest Path First (OSPF). *An example of an internetwork using OSPF, showing different types of OSPF routers.*

If an AS is subdivided into multiple OSPF areas, one of these areas must be a specially designated area called the backbone area, which has the identifier 0 (zero). Every other area within an AS must be directly connected to the backbone area in hub-and-spoke fashion, and adjacent areas communicate with each other directly between their backbones.

To support this hierarchical router topology, OSPF routers can be designated to operate in one of four different roles:

- **Internal router (I):** A router whose interfaces are all within the same area (the area where the router resides). Internal routers are used for routing traffic within the area, and their routing tables contain information only about all other internal routers in that area.
- **Backbone router (B):** A router that has at least one interface connected to the backbone area. Backbone routers are used for routing traffic within the backbone area.
- **Area border router (ABR):** A router that has multiple interfaces, one of which must be connected to the backbone area. ABRs are used for routing traffic between the backbone area and other areas.
- **Autonomous system boundary router (ASBR):** A router used to connect an autonomous system running OSPF to an autonomous system running a different interior gateway protocol.

Advantages and Disadvantages

OSPF has a number of advantages over earlier dynamic routing protocols such as RIP and over other interior gateway protocols such as IGRP and EIGRP, namely:

- It converges quickly and minimizes the risk of routing loops occurring.
- It allows routes to be summarized, reducing the size of routing tables and the processing power needed for routers to use it. This is what makes OSPF highly scalable and suitable for very large internetworks.
- It utilizes very little bandwidth unless a change in network topology has occurred. This is different from RIP routers, which periodically broadcast their entire routing table to neighbors. By contrast, OSPF transmits only incremental changes to network topology.
- It optimizes use of network bandwidth through multicasting instead of broadcasting.
- It supports variable-length subnet masking (VLSM) for classless routing.
- It is flexible and allows administrators to configure routers so that specific routes are preferred over others. This makes OSPF networks fault-tolerant because they can automatically reroute traffic when a link goes down.

Notes

When you design an OSPF-based internetwork, you should work from the top down—that is, you should first plan your autonomous system and how it will interact with other autonomous systems, and then you should subdivide the autonomous system into areas and then into individual networks. Try to map your IP address space and subnets to this hierarchy of areas and networks and assign each area a small set of network IDs that can be summarized as a small series of routes. Be sure that areas connect to each other through your high-speed backbone area and not directly to each other. (In other words, avoid back doors.) Specify cost values that relate to the amount of traffic and each router's hardware characteristics.

See Also: *autonomous system (AS), distance vector routing algorithm, dynamic routing protocol, Enhanced Interior Gateway Routing Protocol (EIGRP), interior gateway protocol (IGP), Interior Gateway Routing Protocol (IGRP), IPv6, Internetwork Operating System (IOS), link state routing algorithm, Routing Information Protocol (RIP), routing protocol, variable-length subnet mask (VLSM)*

open source

A philosophy of software development that makes application code freely available.

Overview

Open source is a philosophy of application development that allows code to be read, redistributed, and modified based on the GNU Public License (GPL) formula. The term *open source* also refers to a loosely organized community of developers dedicated to producing quality software and making it available free or at minimal cost.

Although the open-source operating system called Linux has recently garnered the majority of media attention for this movement, the underlying ideas of open-source software development go back more than 20 years to the early days of the Internet. The development of the BSD UNIX variants FreeBSD, OpenBSD, and NetBSD was a pioneering effort in opening up the UNIX platform for development. From this effort emerged the "hacker" culture of the 1980s (the term *hacker* originally meant someone who tinkered with software to make it better, not someone who maliciously tried to break into systems). The overriding philosophy of software development within the hacker community was originally that software must be free (without cost to its users), but this sharply ideological attitude alienated many in the corporate world and slowed their acceptance of software developed by the hacker community.

In 1998 the term *open source* was coined to replace the confrontational *free software* label and promote acceptance of this philosophy in the corporate arena. The result has been an acceleration of interest in open-source applications and development by enterprises over the last few years, pushed along by large investments in Linux and other open-source technologies by companies such as IBM, Sun Microsystems, Compaq Computer Corporation, and others. The result is that today many open-source applications are packaged and sold by commercial software vendors. These vendors also provide technical support and customization services for their open-source packages, a critical factor in helping open-source software gain acceptance in the corporate world.

Marketplace

Some of the more popular open-source applications and platforms include

- **Linux:** UNIX-like operating system gaining popularity in enterprise networks, especially at the server end in niche applications such as Web servers, mail servers, and storage appliances. A popular form of Linux is available from Red Hat.
- **Apache:** Popular Web server software that runs on UNIX and Linux platforms.
- **Sendmail:** Simple Mail Transport Protocol (SMTP) server software popular on the Internet.
- **PHP:** Programming language for developing Web applications for the Apache/Linux platform.
- **Samba:** Popular application that enables Linux file servers to run Server Message Block (SMB) protocol so they can interoperate with Microsoft Windows-based servers and clients.
- **MySQL:** Structured query language (SQL) database application available from AbriaSoft Company and Nusphere Corporation.
- **Bluebird:** Open-source network management platform project originally called OpenNMS and acquired by Atipa Technologies.

For More Information

Visit the Open Source Initiative (OSI) at *www.opensource.org.*

See Also: *Apache, GNU General Public License (GPL), Linux, UNIX*

Open Systems Interconnection (OSI) reference model

An architectural model for computer networking developed by the International Organization for Standardization (ISO).

Overview

The ISO began work on the Open Systems Interconnection (OSI) model in 1974 to address the problem that the various networking systems being developed at that time could not communicate with each other. The OSI model was intended as a reference model to which vendor-specific networking systems could be compared so that interoperability solutions could be developed. The OSI model was thus intended to allow heterogeneous systems to communicate easily with each other in an open, standardized fashion and to provide a basis for developing standardized network protocols.

Uses

The primary use for the OSI model is as a starting point for understanding how real-world networking protocols work. In other words, the OSI model is a "reference model" to which such protocols as Transmission Control Protocol/Internet Protocol (TCP/IP), DECnet, and Systems Network Architecture (SNA) can be compared. These real world-protocols generally map only loosely to the OSI reference model, however, and usually omit some of the functions, or even levels, of the OSI model. TCP/IP, for example, maps to only four levels of the OSI model—namely, the physical, network, transport, and application layers.

Another popular use of the OSI model is to simplify the process of troubleshooting networking problems. The basic idea is that upper layer protocol functions cannot work unless all lower layer functions first work properly. This means that when you troubleshoot a network problem, you should generally begin with lower-layer issues (addressing such questions as "Is the cable connected?" and "Does the network card have an IP address configured?") before progressing to testing upper layer issues ("Is the httpd daemon running on the Web server?" or "Are the routing tables up to date?"). As such, the OSI model can probably be said to be the networking professional's fundamental troubleshooting tool, as it guides the whole troubleshooting process.

Architecture

The premise behind the OSI model is that communication between hosts on a computer network is too complex a phenomena to be understood as a unity and that it can best be understood by breaking it down into simpler components. The ISO adopted a layered approach in which the OSI model was divided into seven logical layers. Each layer deals with a certain aspect of communications, and upper layers utilize the functions of lower layers to make network communications possible.

You can think of each layer as being logically connected to the same layer on a different computer on the network. For example, the application layer on one machine communicates with the application layer on another machine. But this communication is logical only; physical communication occurs when packets of data are sent down from the application layer of the transmitting computer, encapsulated with header information by each lower layer, and then put on the wire at the transmitting computer's physical layer. After traveling along the wire, the packets are picked up by the receiving computer's physical layer, passed up the seven layers while each layer strips off its associated header information, and then passed to the receiving computer's application layer, where the receiving application can process the data.

The first table lists the seven layers of the OSI model, starting with the lowest layers and working upward, and provides a brief description of the communications functions that operate at each level. The second table provides examples of networking protocols that operate at each layer of the OSI model.

(continued)

Description of Layers of OSI Model

Layer	*Description*
Physical	Defines network transmission media, signaling methods, bit synchronization, architecture (such as Ethernet or Token Ring), and cabling topologies. Defines how network interface cards (NICs) interact with the media (cabling).
Data-link	Specifies how data bits are grouped into frames, and specifies frame formats. Responsible for error correction, flow control, hardware addressing (such as MAC addresses), and how devices such as hubs, bridges, repeaters, and Layer 2 switches operate. The Project 802 specifications divide this layer into two sublayers, the logical link control (LLC) layer and the media access control (MAC) layer.
Network	Defines logical host addresses such as IP addresses, creates packet headers, and routes packets across an internetwork using routers and Layer 3 switches. Strips the headers from the packets at the receiving end.
Transport	Sequences packets so that they can be reassembled at the destination in the proper order. Generates acknowledgments and retransmits packets. Assembles packets after they are received.
Session	Defines how connections can be established, maintained, and terminated. Also performs name resolution functions.
Presentation	Translates data to be transmitted by applications into a format suitable for transport over the network. Redirector software, such as the Workstation service for Microsoft Windows NT, is located at this level. Network shells are also defined at this layer.
Application	Connects user applications with network functionality, controls how applications access the network, and generates error messages. Protocols at this level include HTTP, FTP, SMTP, and NFS.

Examples of Network Protocols Operating at Each Layer of OSI Model

Layer	*Protocols*
Physical	802.3, 802.5, 10BaseX, 100baseX, 1000BaseX, RS-232, V.35, HSSI, FDDI, PPP, DSL, ISDN, Frame Relay, ATM
Data-link	HDLC, SDLC, LAP, LAPB, AAL, SLIP, PPTP, L2F, L2TP, ARP, RARP
Network	IP, ICMP, IGMP, BOOTP, DHCP, IPX, NetBIOS, NetBEUI, APPN, IS-IS, IGRP, EIGRP, BGP, OSPF
Transport	TCP, UDP, SPX, RAS, ATP, NBP, ASP, DVMRP, RTP
Session	LDAP, DNS, RPC, PAP, SSL, TLS
Presentation	ASN.1, LU6.2, Postscript, 3270 Data Stream
Application	HTTP, SMTP, FTP, POP3, IMAP4, Telnet, SNMP, TFTP, RLOGIN, SMB, NLP, NDS, SAP, NCP, X-Windows

Implementation

Although some vendors attempted to develop networking protocols fully compliant with the OSI model, these attempts by and large failed for several reasons:

- **Complexity:** The OSI model was overly complex and its use of seven layers created unnecessary overhead in processing information for transmission on a network. Also, some communications functions, such as connectionless communication, were relatively neglected by the OSI model, while others, such as error correction and flow control, were repeated at several layers in redundant fashion.
- **Closed standards process:** The ISO standards process was relatively closed compared with the open standards process that the Internet Engineering Task Force (IETF) used to develop the TCP/IP suite of protocols. As a result, development of TCP/IP was fast while development of OSI protocols was slow, with the result that TCP/IP established itself long before OSI protocols could gain significant market foothold.

The U.S. government originally tried to require compliance with the OSI reference model for U.S. government networking solutions in the late 1980s by implementing standards called Government Open Systems Interconnection Profiles (GOSIPs). This effort was abandoned in 1995, however, and today virtually no real-world implementations of OSI model protocols exist outside of Europe, and only a few European governments still use OSI model protocols in specialized systems. Instead, the TCP/IP protocol suite has become the de facto world standard for computer networking.

See Also: *application layer, data-link layer, International Organization for Standardization (ISO), Internet Engineering Task Force (IETF), network layer, physical layer, presentation layer, session layer, Transmission Control Protocol/Internet Protocol (TCP/IP), transport layer*

optical carrier (OC-x) level

A measure of Synchronous Optical Network (SONET) capacity.

Overview

The optical carrier (OC-x) levels represent a set of signaling rates for SONET transmission over fiber-optic cabling. The basic unit is OC-1, which represents an aggregation of 810 DS-0 circuits, each having a capacity of 64 kilobits per second (Kbps), resulting in a total OC-1 capacity of 51.84 megabits per second (Mbps). In SONET transmission, however, 30 of these DS-0 circuits are required for protocol overhead, making the actual data throughput of OC-1 only 50.112 Mbps. A single OC-1 circuit is roughly equivalent to a T3 circuit in the telco T-carrier system. Higher data transmission rates (such as OC-3 and OC-12) are simply multiplexed OC-1 circuits—for instance, OC-3 is three times faster than OC-1. The table shows the common OC-x transmission rates used in carrier-class SONET circuits.

Much of the SONET fiber used in the backbone of the Internet still runs at OC-48, although inter-exchange carriers (IXCs) and other carriers are upgrading to higher speeds. AT&T was the first IXC to deploy an OC-192 trunk from coast to coast across the United States, and UUNET, Genuity, and Cable and Wireless also have OC-192 links deployed.

Common Optical Carrier Levels

Level	*Line Rate*	*Payload Rate*
OC-1	51.840 Mbps	50.112 Mbps
OC-3	155.520 Mbps	150.336 Mbps
OC-12	622.080 Mbps	601.344 Mbps
OC-24	1.244160 Gbps	1.202688 Gbps
OC-48	2.488320 Gbps	2.405376 Gbps
OC-96	4.976640 Gbps	4.810752 Gbps
OC-192	9.953280 Gbps	9.621504 Gbps

Notes

OC-x levels also apply to Asynchronous Transfer Mode (ATM) networks. For wireline communications, electrical levels called Synchronous Transport Signal (STS) correspond directly to SONET optical carrier levels. For example, the OC-3 rate for SONET corresponds to the STS-3 rate for electrical transmission.

See Also: *inter-exchange carrier (IXC), Internet, Synchronous Optical Network (SONET), T-carrier*

optical Ethernet

More commonly called metropolitan Ethernet, the process of using Gigabit Ethernet to provision metropolitan areas with high-speed data services.

See: *metropolitan Ethernet*

optical networking

End-to end networking without conversion of electrical signals into optical and back again.

Overview

Traditional optical networks use fiber-optic backbones in local area networks (LANs) or long-haul fiber in wide area networks (WANs). Such networks are not “optical,” however, as only a portion of the network (backbone or WAN link) employs light signals traveling over fiber-optic cabling, while the remainder of these networks involves electrical signals traveling over copper cabling. The main reason that all-optical networks have not yet become commonplace is that routing and switching functions have traditionally been implemented at the electrical level, as there has been no easy way to switch light signals themselves. As a result, traditional networks employ devices that transform electrical signals into optical ones and back again.

This situation, however, is just beginning to change as new technologies are being developed to create all-optical switches and routers. Companies in the forefront of research in this area include Cisco Systems, Nortel Networks, Lucent Technologies, and several startups. Some of the technologies being developed include switches that route light signals of a given wavelength using

- **Tiny adjustable mirrors:** An example of a product using this technology is the Lambda router from Lucent Technologies. Because this technology employs mechanical parts, however, industry analysts do not view it as especially promising.
- **Tiny bubbles in a heated liquid:** These bubbles can be used to divert light signals in response to changing temperature conditions. Agilent Technologies is one company that has worked on this approach, which can form the switching fabric of all-optical mesh networks.
- **Thermo-optic gateways:** This uses narrow silica waveguides whose transmission properties change with temperature to allow light paths to be switched on and off in milliseconds. A start-up called Lynx Photonic Networks is using this approach to develop all-optical switches.

Uses

Initial uses for optical switches and routers are likely to be in carrier-class switching equipment used by service providers and telcos. Some analysts expect such equipment to become widely available about 2005. Enterprise networks may also want to deploy such equipment in their high-speed switched backbones, but this will not likely become popular until several years later due to initial costs of such equipment. Eventually all-optical mesh networks may displace traditional Synchronous Optical Network (SONET) ring architectures in the metropolitan area network (MAN) arena and in cross-connects for long-haul circuits. SONET was originally designed to support time-sensitive voice traffic and is not efficient for carrying packetized data. About half of the capacity of SONET rings in the MAN environment is currently used for data, but the proportion of data to voice traffic is rising rapidly, a critical factor in driving research and development into new optical switching technologies.

Notes

The term *optical networking* is sometimes incorrectly used to refer to either metropolitan Ethernet (also called optical Ethernet) or lambda switching technologies.

See Also: *fiber-optic cabling, lambda switching, metropolitan Ethernet, Synchronous Optical Network (SONET)*

opto isolator

A device for electrically isolating networking components that are joined by long runs of copper cabling.

Overview

Opto isolators are commonly used in RS-232 serial connections between mainframe hosts and terminals connected by long cables. Opto isolation is typically built into line drivers for serial communication, so separate opto isolators are not required. Opto isolators also prevent ground loops from damaging networking components.

Implementation

When a network component or cable transmitting a signal is connected to one port on an opto isolator, the signal is converted briefly into light and then back into an electrical signal before exiting through the other port on the opto isolator. This brief metamorphosis from electric current into light and back again breaks the electrical connection between the two ports of the device, allowing the signal (alternating current) to flow but preventing direct current from flowing along the cable.





Opto isolator. *Using an opto isolator to eliminate ground loops.*

See Also: *ground loop, RS-232, serial transmission*

Orange Book

Another name for the publication Trusted Computer Systems Evaluation Criteria (TCSEC), published by the National Computer Security Center (NCSC) of the U.S. Department of Defense (DoD).

Overview

Orange Book standards are used to evaluate the security of both stand-alone and network operating systems (NOSs). The current version of this publication dates from 1985. The Orange Book, which was named for its orange cover, is actually a part of a series of computer system security guidelines and standards that are collectively known as the Rainbow Series.

The Orange Book provides methods of assessing the security of a specific computer system, and it offers hardware and software manufacturers guidance on how to create products that can be certified as secure by the U.S. government and military.

For example, Microsoft Windows NT Server in certain configurations complies with the C2 (Controlled Access Protection) security standards outlined in the Orange Book. C2 is applied not to operating systems but to specifically tested physical computers running those operating systems. C2 is one of a family of security designations that the Orange Book applies to computer systems, which include the following:

- **D (Minimal Protection):** For systems that were evaluated but failed.
- **C1 (Discretionary Security Protection):** Provides separation between users and data by using access controls.
- **C2 (Controlled Access Protection):** Adds user accountability to C1 in the form of logons, auditing, and other features.
- **B1 (Labeled Security Protection):** Builds on C2 by including informal written security policies, data labeling, and mandatory access control.
- **B2 (Structured Protection):** Builds on B1 by including formal written security policies, separation of critical and noncritical elements, and protection against covert entry.
- **B3 (Security Domains):** Builds on B2 by including reference monitoring of all object access to ensure security, a designated security administrator, and system recovery procedures.
- **A1 (Verified Design):** The same as B3, except security is verified by both testing and analysis of formal design. An A1 system is considered impenetrable to hostile attack.

organizational unit (OU)

A container object used in Microsoft Active Directory directory service to group together other objects within a domain.

Overview

Organizational units (OUs) are logical groupings of resources within a domain. An OU can contain a variety of objects, including users, groups, computers, printers, or even other OUs. OUs are essential to the scalability of Active Directory as they allow objects in a domain to be hierarchically organized in tree-like structures for easier administration. OUs thus simplify the management of Active Directory domains by allowing different administrative tasks to be delegated to different people.

OUs are often used to duplicate the organizational structure of the company within Active Directory. For example, a company might have OUs named Dev, Marketing, and Sales that represent the network resources of these three departments. OUs can also be assigned according to geographical criteria (New York, Los Angeles, and Detroit, for example) or by administrative function (Accounts, Shares, and Printers).

If several domains are connected into a domain tree, each domain can have its own specifically designed hierarchy of OUs. The structures of domains within a domain tree are independent of one another. However, an OU can contain objects only from its own domain, not from any other domain within a domain tree.

Implementation

When you run the Active Directory Installation Wizard to install Active Directory on a member server running Windows 2000 (thus turning the member server into a domain controller), a hierarchy of default OUs is created. This default hierarchy helps you begin administering Active Directory. It consists of the following default OUs, which you can display by using Active Directory Users and Computers, a snap-in for Microsoft Management Console (MMC):

- **Builtin:** Includes built-in security groups such as Administrators and Account Operators
- **Computers:** Includes other computers in the domain
- **Users:** Includes domain user objects
- **Domain Controllers:** Includes the domain controllers in the domain



Name	Type
Builtin	builtinDomain
Computers	Container
Users	Container
Domain Controllers	Organizational Unit

Organizational unit (OU). *The Domain Controllers OU in a domain.*

OUs are displayed in Windows 2000 administrative consoles as folders, much like the folders in a file system that store individual files. You can create OUs for groups of users who will be assigned similar permissions to network resources. You can also create separate OUs for permanent and temporary employees. You can group shared folders and printers with similar security requirements into OUs.

You should create OUs that are stable and will not change frequently, and you should avoid making the hierarchy of OUs too complicated. In a multidomain scenario with a domain tree, it is usually a good idea to make first-level OUs the same for all domains to provide consistency for the company's network resources. First-level OUs typically represent the following:

- Different geographical locations, such as countries, regions, or continents, or different functional locations, such as headquarters and branch offices. This is usually the best way to define first-level OUs.
- Different types of network resources, such as users, printers, and computers. This simplifies resource administration but might lead to too many first-level OUs.
- Different business units, such as Sales, Support, and Management. Keep it flexible and broad enough so

that if your company reorganizes, you will not have to re-create everything.

- Projects and cost centers.
- When creating a hierarchy of OUs, you should generally keep the entire structure of OUs fairly shallow—no more than two or three levels—to ensure good performance when users query Active Directory. A maximum of 10 levels of OUs is recommended.

When migrating from Windows NT to Windows 2000, you can also create OUs to replace resource domains, which are used in Windows NT to simplify and centralize administration of network resources. You can also create domain trees with separate domains for resources. You should create new domains instead of OUs if you want to implement different security policies in different locations or branches of your company or in an extremely large enterprise. Otherwise, it is simpler to create only one domain and organize resources and administrative tasks using OUs within that domain.

OUs are useful in facilitating the administration of Active Directory and therefore the administration of resources on the network itself. Administrators use OUs to organize users and resources on the network and to delegate administrative and other rights and permissions to users and groups. The administrator has full access rights on all objects in the directory and can assign permissions to various subtrees of OUs for appropriate users and groups. For any OU, the administrator can delegate either of the following rights to specific users and groups:

- **Complete administrative control:** Full control over all objects in the OU
- **Limited administrative control:** The ability to modify only certain aspects of objects contained in the OU

Access to objects in Active Directory is based on discretionary access control lists (DACLs), which offer a security model similar to that used in the NTFS file system. Because objects with similar security requirements are grouped into an OU, permissions assigned to the OU are inherited by all objects in the OU. You assign permissions to OUs and other objects by using Active Directory Users and Computers.

Notes

OUs are not part of the namespace of a company, which in Windows 2000 is based on the Domain Name System (DNS). In other words, you can identify a Windows 2000 domain by using a DNS name such as northwind.microsoft.com, but you cannot identify OUs within the domain by using DNS names. However, you can specify OUs by using Lightweight Directory Access Protocol (LDAP) names.

See Also: *Active Directory, Active Directory Users and Computers, domain (DNS), Domain Name System (DNS), domain tree, Lightweight Directory Access Protocol (LDAP), object (Active Directory)*

Organization for the Advancement of Structured Information Systems (OASIS)

A nonprofit consortium that promotes Extensible Markup Language (XML) standards.

Overview

The Organization for the Advancement of Structured Information Systems (OASIS) is a vendor-neutral international organization that strives to develop and promote standards for structured information systems. OASIS was originally formed in 1993 as SGML Open and initially focused on the Standardized Generalized Markup Language (SGML). The name was changed to OASIS in 1998 to reflect the changed focus on XML-based standards and solutions. OASIS acts as a clearinghouse for standards and information concerning structured information systems and helps vendors design products that comply with open XML-based standards.

Together with the United Nations/CEFACT body, OASIS has been active in the development of the Electronic Business Extensible Markup Language (ebXML) standard, a new XML standard for simplifying the exchange of information between business partners to promote e-commerce. OASIS also sponsors the XML.ORG site as a reliable source of information regarding XML standards.

For More Information

Visit OASIS at *www.oasis-open.org.*

See Also: *Electronic Business Extensible Markup Language (ebXML), XML*

Orthogonal Frequency Division Multiplexing (OFDM)

An emerging technology for achieving higher data rates in wireless communications.

Overview

Orthogonal Frequency Division Multiplexing (OFDM) is an emerging signal modulation technology for high-speed communications. While OFDM can be employed in both wireless and wireline communication systems, the technology is mainly being developed to enhance transmission speeds of cellular communications systems beyond the range of emerging third-generation (3G) systems. Other improvements that OFDM provides include overcoming line-of-site (LOS) communications problems, extending the range and subscriber coverage areas of cellular communication systems, and overcoming antenna size issues relating to fixed wireless communications.

Prospects

Current work on OFDM involves harmonizing competing standards developed by the Institute of Electrical and Electronic Engineers (IEEE) and the European Telecommunications Standards Institute-Broadband Radio Access Networks (ETSI-BRAN) standards bodies. Practical OFDM systems are under development by AT&T and others for future fourth-generation (4G) cellular communication systems. Another example is Flarion Technologies, a spin-off from Lucent Technologies, which is developing an OFDM signal-processing scheme called Flash OFDM.

See Also: *3G, cellular communications, wireless networking*

OS/2

A network operating system from IBM.

Overview

OS/2 is a 32-bit operating system that was originally developed by IBM and Microsoft Corporation as a replacement for the 16-bit text-based Microsoft Disk Operating System (MS-DOS). After Microsoft left the project to focus on its own Microsoft Windows operating system, IBM continued to develop OS/2, which is now called OS/2 Warp and includes both server and desktop versions.

IBM's current line of OS/2 software includes the OS/2 Warp Server, the OS/2 Advanced Warp Server, and the OS/2 Warp 4 client. OS/2 Warp in its various forms is a 32-bit preemptive multitasking operating system that supports application, file and print, groupware, and Web server configurations as well as desktop workstations. OS/2 Warp Server includes symmetric multiprocessing support and clustering technologies for high-availability server environments. OS/2 Warp Server supports most common networking protocols and all types of clients, including Microsoft Windows, Apple Macintosh, and AIX clients.

For More Information

Visit OS/2 Warp online at *www.software.ibm.com/os/warp.*

See Also: *Microsoft Windows, network operating system (NOS)*

OSI model

Stands for Open Systems Interconnection model, a reference model for computer networking developed by the International Organization for Standardization (ISO).

See: *Open Systems Interconnection (OSI) reference model*

OSPF

Stands for Open Shortest Path First, a popular link state dynamic routing protocol for large Internet Protocol (IP) networks.

See: *Open Shortest Path First (OSPF)*

OS X

A new operating system for the Apple Macintosh computing platform.

Overview

Mac OS X represents a radical departure from earlier versions of the Mac OS. Unlike earlier versions, the OS X kernel called Mach is based on a version of the UNIX operating system called BSD 4.4. This radical departure allows the Macintosh platform to marry its advanced graphical user interface and multimedia features with the stability and reliability of the well-tested UNIX platform.

Other enhancements in Mac OS X include

- Apple Computer's new Quartz 2-D imaging technology
- 3-D imaging based on the OpenGL standard
- Integrated QuickTime technology
- Adobe Portable Document Format (PDF) printing technology
- A powerful new graphical user interface called Aqua

See Also: *Macintosh, UNIX*

OU

Stands for organizational unit, a container object used in Active Directory directory service to group together other objects within a domain.

See: *organizational unit (OU)*

Outlook

Microsoft Corporation's premier mail client and full-featured desktop information-management application.

Overview

Microsoft Outlook, which is part of the Microsoft Office suite, enables users to manage their messages, appointments, contacts, tasks, and activities. It also integrates with other Office applications at the front end and with Microsoft Exchange at the back end to enable users to collaborate using e-mail, calendar, contact lists, task lists, journals, and notes. Outlook is a full Messaging Application Programming Interface (MAPI) client and interoperates with all e-mail systems that support MAPI.

Outlook can be run as a stand-alone application or as part of the Office suite. Outlook's advanced features include the following:

- Support for MAPI, Post Office Protocol version 3 (POP3), Internet Mail Access Protocol version 4 (IMAP4), and Hypertext Transfer Protocol (HTTP)
- A common user interface with other Office components
- AutoNameCheck, message tracking, message recall, embedded hyperlinks, and other e-mail enhancements
- Enhancements to calendar and scheduling functions to facilitate processing of meeting requests, tracking attendees, and configuring the duration of appointments
- Simplified tracking of "to do" lists using task requests, task tracking, status reports, and task categorizations
- Custom Outlook forms for creating custom collaboration applications

For More Information

You can find out more about Microsoft Outlook at *www.microsoft.com/outlook.*

See Also: *e-mail*

Outlook Express

A basic Internet mail and news client included with Microsoft Internet Explorer version 4 and later.

Overview

Microsoft Outlook Express replaces the older Microsoft Internet Mail and News client included with Internet Explorer 3 and includes the following features:

- Customizable three-pane view that shows folders, messages, and message content
- WYSIWYG editing of Hypertext Markup Language (HTML) messages
- Support for Internet standard protocols, including Simple Mail Transfer Protocol (SMTP), Post Office Protocol version 3 (POP3), Internet Mail Access Protocol version 4 (IMAP4), Lightweight Directory Access Protocol (LDAP), and Network News Transfer Protocol (NNTP)
- Support for multiple Internet service provider (ISP) accounts so that users can receive mail from multiple e-mail accounts and download all messages into the same Inbox
- Integration with Internet Explorer security zones
- Automatic name resolution (matching address book entries to a typed username)
- Stationery templates for adding a personal touch to messages
- Enhanced Inbox rules for filtering incoming mail

out-of-band management (OBM)

Remotely managing telecommunications equipment using out-of-band (OOB) signaling.

Overview

Out-of-band management (OBM) is a popular method of remotely managing the wide area network (WAN) telecommunications components. OBM manages devices “outside of the normally used bandwidth,” in other words, using a separate communications link than the one being used for data transmission. These out-of-band (OOB) links are typically secondary serial communication links. WAN devices typically managed using OOB include routers, switches, access servers, multiplexers, and Channel Service Unit/Data Service Units (CSU/DSUs). Devices that can be managed out of band usually have an RS-232 port or some other kind of serial interface for remote control of their functions.

OBM offers several advantages over in-band management systems such as Simple Network Management Protocol (SNMP) management systems. For one thing, OBM is more secure than in-band management since it typically uses a dedicated serial link for management purposes, Also, SNMP employs the network itself for communication, so if the WAN link goes down, the remote station cannot use SNMP to determine the problem because SNMP functions only if the WAN link is working. OBM is often used as a backup system for in-band SNMP management, when the devices have limited SNMP support, or when the cost of an SNMP management system cannot be justified. You can often manage a device in-band by using a remote Telnet client for entering the same commands that are used in OBM.

Implementation

In a typical OBM setup, a remote PC is connected by a modem through a phone line to a code-operated switch located at the office local area network (LAN). This switch controls networking and telecommunication devices such as routers, bridges, switches, CSUs, and even power supplies through their RS-232 serial connections. Alternatively, the modem might be connected directly to a remote modem connected to the device being managed. In either case, the result is a separate low-cost dial-up circuit connecting the administrator and the network devices that is independent of the main network connection, which is usually a more expensive T1 or other leased line. The administrator can thus access the WAN device from a remote location even when the WAN link itself is down, and can troubleshoot the problem from off-site. OBM also allows administrators to access and configure WAN devices without disturbing the WAN link itself.

You could use OBM functions on a power supply to remotely reboot or reset your network devices when they go down. You can use out-of-band switches to select different serial interfaces remotely over a modem by issuing simple ASCII commands to different devices. You can even use OBM to remotely configure and control devices on your network. OBM devices are a useful part of a network disaster recovery plan.



Out-of-band management (OBM). *Managing WAN hardware out-of-band.*

For networking devices that you can configure and troubleshoot using out-of-band connections, you usually perform management tasks by connecting to a serial port (also called the setup port or configuration port) either locally with a cable or remotely through a modem. You usually use text-based commands from a terminal emulator program such as Windows HyperTerminal, which can emulate a VT100 terminal. You can often control access using passwords for extra security.

You can often use out-of-band transmission so that a device that enters a problem state calls an administrator's pager through a modem. The administrator can then dial in to the device remotely and correct the problem. Some network devices include built-in modems and data switches for remote OBM.

OBM is also used in other areas—for example, servers are often built with OBM capabilities and when they enter a problem state can also take advantage of an OOB connection to deliver an alert.

See Also: *out-of-band (OOB) signaling, Simple Network Management Protocol (SNMP), wide area network (WAN)*

out-of-band (OOB) signaling

Any transmission technology in which signaling is separate from the data being transmitted.

Overview

Out-of-band (OOB) signaling uses one or more channels for transmitting data or voice information and one special out-of-band channel for performing signaling functions such as establishing and terminating the communication link, controlling flow, or transmitting error information. The out-of-band channel can be

- A physically separate set of wires (such as pins 4 and 5 of an RS-232 cable, which perform flow control functions and do not carry data)
- A multiplexed system in which bandwidth is divided into two or more channels within the same set of wires such as Integrated Services Digital Network (ISDN), in which the two B channels and one D channel are multiplexed onto the same set of wires)

The opposite of out-of-band is in-band, in which signaling information is sent over the same channel as the data transmission. Out-of-band transmission is usually considered a better choice than in-band transmission for the following reasons:

- None of the valuable data bandwidth is used for signaling.
- The data stream is not interrupted with signaling information.
- The signaling information cannot be disrupted by the noise created by the data transmission.
- Data transmission characters cannot accidentally (or purposefully) initiate control actions.

Notes

Out-of-band circuits are often used for out-of-band management (OBM) of wide area network (WAN) devices. These are usually physically separate dial-up lines.

See Also: *in-band signaling, out-of-band management (OBM)*

outsourcing

Contracting business functions to external companies.

Overview

Outsourcing of IT (information technology) needs has been an increasing trend in recent years, but such outsourcing is not new. Broadly speaking, for the first few decades of the computing era outsourcing reigned supreme as companies either leased mainframe technology and staff or bought time-sharing services from mainframe computing centers. The client/server revolution of the 1980s then saw the rise of in-house IT departments as large companies sought to gain strategic control of their own IT services and smaller companies tended to rely more on outsourcing deployment and troubleshooting services to consultants and system integrators. In the late 1990s, however, the pendulum began to swing back toward outsourcing a larger share of IT functions. This happened for several reasons:

- Time-to-market has become critical in the accelerating Internet economy, and startup companies often gain a significant edge in this respect by outsourcing their system management and application needs to a new breed of Application Service Providers (ASPs) and Management Service Providers (MSPs).
- The Internet itself has become a key enabler for outsourcing network, desktop, and application management through new browser-based management platforms. The Internet has also realized the virtual enterprise in which companies can manage contract IT staff in remote locations in order to fulfill application development, technical training, and help desk needs that are difficult or expensive to achieve locally.
- The difficulty of recruiting and hiring experienced IT professionals and the cost of retaining them has made outsourcing of many IT functions an attractive solution for many companies.

Today, common outsourced IT functions and services include application hosting, messaging, disaster recovery, enterprise resources planning (ERP), customer relationship management (CRM), supply-chain logistics management, and help desk functions.

Marketplace

The big three companies in the enterprise IT outsourcing arena are EDS, Computer Sciences Corporation, and IBM Global Services. These companies together service the largest share of the corporate outsourcing market, but dozens of ASPs and other service providers have arisen in the last few years to compete in this arena. In 2000, the total IT outsourcing market was estimated at over $100 billion and was growing at over 10 percent a year.

See Also: *application service provider (ASP), Customer Relationship Management (CRM), enterprise resource planning (ERP), Management Service Provider (MSP)*

owner

The user ultimately responsible for the permissions assigned to a file, usually the creator of the file.

Overview

In the NTFS file system, for example, a file stored on an NTFS volume always has an owner. Ownership creates a trail of accountability for actions performed on the file. By default, a file's owner has permission to modify the object's discretionary access control list (DACL) by granting users and groups permissions for various objects.

The ownership of a file on an NTFS volume can be changed in two ways:

- The user who owns the file, or any user who has full control permission on the file, can grant the NTFS take ownership permission to another user, thus allowing that user to take ownership of the file by using the file's Security property sheet. Users can be allowed to take ownership of a file they do not own, but ownership cannot be assigned to them by other users (even the original owner or an administrator).

- Members of the Administrators group can always take ownership of any file by using the Security property sheet. When an administrator takes ownership of a file, the Administrators group, and not the individual administrator, becomes the file's owner.

Notes

In the Microsoft Windows 2000 and Microsoft .NET Server operating systems, objects in Active Directory directory service also have owners. The user who creates an object in Active Directory becomes the object's owner. The owner controls the permissions for the object and its attributes. Ownership of an object in Active Directory can be changed in ways similar to those for a file on an NTFS volume.

See Also: *NTFS file system (NTFS)*

P

P2P

Applications that enable computers to function as both clients and servers.

Overview

Although the acronym *P2P* officially stands for “peer-to-peer,” the acronym has taken on a somewhat different meaning than the earlier concept of peer-to-peer networking that evolved in the 1980s. The original idea referred to networks that were too small to warrant having dedicated servers, hence client machines could share files with one another to facilitate collaboration between users. Such peer-to-peer networks became popular with the release of Microsoft Windows for Workgroups (WFW). A key characteristic of such networks was that security was distributed—that is, there was no central authentication server to manage logon security and access control. As such, peer networking is suitable only for low security environments. Microsoft Corporation developed Windows NT to provide centralized security for such networks, turning them into domain-based networks instead of peer-to-peer ones.

The concept of peer networking has evolved in the last few years, however, to include a whole range of powerful applications that allow client computers to share resources while bypassing servers. This new concept is today called P2P and was popularized by the music sharing service called Napster, which at its peak had over 20 million users worldwide. An essential ingredient in the popularity of the P2P model is the ubiquity of the Internet. However, P2P is also making inroads into traditional enterprise corporate networks as well.

Uses

Some of the emerging uses for P2P applications and platforms include

- **File sharing:** P2P allows clients to share files with one another without using network servers. Napster is the classic example here, but today’s P2P platforms can share any kind of file, including text files and documents, multimedia files, virus definition files, and software patches and updates.
- **Shared processing:** This enables multiple client machines to share the processing load for certain tasks, reducing pressure on network servers. A good example here is the Search for Extra-Terrestrial Intelligence (SETI) at Home Project developed by the University of California at Berkeley. SETI at Home has more than 2 million registered users who have downloaded P2P software and use it to help search radio telescope signal archives for messages that extraterrestrials might be sending from other star systems. Another classic example in this category is Intel Corporation, which has saved $500 million over 10 years by using a P2P program called Netbatch to harness the processing power of thousands of workstations for the job of chip design.
- **Automatic software distribution:** Many enterprises have expressed interest in P2P as a vehicle for distributing software such as virus updates and system patches across the network. One company that pioneered in this direction is myCIO.com (now McAfee AsaP), which developed antivirus definition distribution software that employs token-based authentication to ensure secure distribution of updates.
- **B2B collaboration:** P2P provides new mechanisms for businesses to interact online to integrate supply-chain processes and foster a collaborative business environment. An example of such an application is Mangomind from Mangosoft, which provides a secure real-time Internet-based file-sharing service along the P2P model. Consilient is another company with P2P platforms for B2B linkage.

Marketplace

P2P file sharing services are popular on the Internet. Napster was the pioneer here, and newer alternatives include BearShare, Gnutella, LimeWire, and ToadNode. In the enterprise arena, secure P2P file sharing platforms are also appearing from such vendors as NextPage, Tacit Knowledge Systems, OpenCola, 3Path, and Groove Networks. Many of these platforms can not only share files but also deliver messages, distribute Web content, locate content of interest automatically using rules-based procedures, and perform other functions.

In the area of distributed processing, a P2P application called WebProc from Datasynapse securely allows unused cycles of client machines to be used for complex processing tasks, offloading some of the processing burden from network servers. Porivo Technologies has a similar product called Peer, implemented as a Java-based application, and Entropia has a similar product.

Other emerging P2P vendors include AgentWare, with its P2P platform for managing web sites, portals, and B2B e-commerce; WorldStreet Corporation with P2P software for online brokerages and investment institutions; and Porivo Technologies with Web performance testing software.

Prospects

Early use of Napster and similar P2P file sharing applications by users on corporate networks caused headaches for IT (information technology) managers, as these applications tended to eat up available bandwidth and thus deny access to legitimate network services. This initially created a bias against P2P platforms in the enterprise that still remains in some measure today. Other reasons network administrators have been reluctant to utilize P2P in the enterprise are the lack of standards and because P2P applications bypass centralized server-based network security. Nevertheless, interest in P2P continues to grow in the enterprise.

Major industry players Intel Corporation, Hewlett-Packard, and others have established the P2P Working Group to steer the development of P2P standards, especially in the area of security. The Working Group's efforts are directed toward making P2P a more secure platform for use in the enterprise. Microsoft's .NET platform and Sun Microsystems' JXTA also represent exciting initiatives that will enable secure, enterprise-class P2P applications to be developed for enterprise use.

See Also: *B2B, JXTA, .NET platform, peer-to-peer network*

P3P

Stands for Platform for Privacy Preferences, a standard specifying how Web sites communicate their privacy policy to visitors.

See: *Platform for Privacy Preferences (P3P)*

package

In Microsoft Systems Management Server (SMS), an object that defines software to the SMS system.

Overview

Packages store information about software so that various components of the software can be identified as a group. You use SMS to install a package on client computers, share the package so that it can be run from network servers, and maintain inventory information about the package. You can create packages for all types of software, including Microsoft, third-party, and in-house applications; data files; batch files; and scripts.

A package contains a definition of the files that make up the software, plus other configuration and identification information. You create packages using the Systems Management Server Administrator program. Packages are stored in the SMS database at your site and at all subsites. After you create a package, you must also create a job that can be used to install the package on clients or share the package on servers.

You use a package server—a type of server in an SMS implementation—to install and maintain packages. There are two kinds of package servers:

- **Source servers:** These contain the original source files for software to be distributed.
- **Distribution servers:** These store and distribute the package files.

Notes

If you want to perform software inventory, you need not explicitly create a job for this purpose. When you define the inventory properties for a package, SMS automatically creates a system job to update the SMS inventory components. This allows SMS to maintain inventory information on the package.

See Also: *Systems Management Server (SMS)*

packet

The fundamental unit of information transmitted over a packet-switched network or digital communication link.

Overview

A packet is essentially a chunk of information sent over a network. For example, to transfer a file from one host to another on the Internet using the File Transfer Protocol (FTP), the file is first broken down into a series of chunks of data that are packaged into units called "packets." These packets have a header added to the beginning of the packet that contains control information concerning the packet type, the source address, and the packet's destination address. They may also contain error-checking information, often as a trailer (footer) added to the end of the packet. Packets have a logical structure based on the particular type of protocol used, but the general structure of a packet always includes a header followed by a payload (data) and an optional trailer. Packets can also have different sizes and structures depending on the underlying network architecture.

A packet might also be called a datagram, a frame, or a cell, depending on the type of networking under consideration. However, from the perspective of the Open Systems Interconnection (OSI) reference model, the terms *packet* and *frame* have precise definitions and are considered different entities. From the OSI perspective, a packet is an electronic envelope containing information formed in one of the layers from Layer 3 through Layer 7 of the OSI model, but a frame is an electronic envelope of information that includes the packet as well as other information from all seven layers of the OSI model.

See Also: *frame, Open Systems Interconnection (OSI) reference model, packet switching, packet-switching services*

packet assembler/ disassembler (PAD)

A device that connects computers and other networking equipment to an X.25 packet-switched network.

Overview

Packet assembler/disassemblers (PADs) are telecommunications devices that break down binary data streams into individual packets suitable for asynchronous transmission over X.25 networks. PADs also format packets by adding suitable headers to enable the packets to reach their destination. When receiving data, a PAD also accepts packets from the network and translates (reassembles) them into a data stream that the computer can understand. The PAD's function is thus to assemble data such as strings of characters into packets to transmit over the X.25 network to the remote host and to disassemble packets that are received.

PADs were originally developed to enable remote dumb terminals to communicate over X.25 networks with mainframe computers. They were needed because such terminals lacked the processing capability to implement the X.25 protocol on them directly. The PAD thus acted as an intermediary between the terminal and the mainframe and buffered data received from the terminal and assembled or disassembled it into X.25 packets depending on whether it was transmitting or receiving.

Although early PADs required external data communications equipment (DCE), most PADs now have integrated DCE to allow them to be directly connected to asynchronous data terminal equipment (DTE) such as terminals, computers, routers, and access servers.

Implementation

When one computer on an X.25 network wants to communicate with another computer in a remote location, the first computer sends a signal to its attached PAD requesting a connection to the remote computer. The remote computer responds by either accepting the request and initiating full-duplex communication or rejecting the request. Either computer can then terminate the link at any time. Note that this communication link is for data only—X.25 does not support voice transmission. Note also that PADs are DCEs, and even though they are located at the customer premises, they are actually considered nodes on the X.25 network and are therefore drawn within the cloud in the diagram.

When PADs are used for providing remote access through dumb terminals over X.25 to mainframe or minicomputer hosts, the terminals require PADs but the mainframe hosts do not—they are directly connected to the X.25 network. To configure the PAD, the administrator must specify a number of PAD parameters such as echo control, data forwarding, break signals, line folding, and binary speed. The PAD parameters (usually 22 for each terminal that the PAD services) are defined by an International Telecommunication Union (ITU) protocol called X.3. Communication between terminals and PADs is governed by the protocol X.28, and communication between the PAD and the remote host is governed by X.29.



Packet assembler/disassembler (PAD). *Using PADs to connect dumb terminals to a mainframe host.*

PADs come in different configurations. Some PADs support eight or more asynchronous DTE connections and have multiple DCE interfaces for maximum configurability. Typically, you connect your asynchronous hosts (computers) to the PAD using RJ-45 connectors on twisted-pair cabling. The PAD then connects to a Channel Service Unit/Data Service Unit (CSU/DSU), which interfaces with the X.25 connection using a serial interface such as RS-232 or V.35. Some PADs now have integrated CSU/DSU functionality to allow them to be directly connected to the X.25 networks using serial interfaces. Some PADs even support both X.25 and frame relay and can thus be used to ease the migration path from older X.25 to newer frame relay services.

Notes

The Routing and Remote Access Service (RRAS) on Microsoft Windows 2000 and Windows .NET Server support PADs and other ways of connecting to X.25 networks, such as X.25 smart cards and special modems for dialing up X.25 carriers such as SprintNet and Infonet.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), data communications equipment (DCE), data terminal equipment (DTE), frame relay, International Telecommunication Union (ITU), packet switching, packet-switching services, RS-232, serial transmission, terminal, V.35, X.25*

packet filtering

Controlling a flow of packets based on information contained within the packets.

Overview

Packet filtering is simply a way of controlling traffic on a packet-switched network such as the Internet. Filtering can be performed on packet attributes such as source address, destination address, packet type, packet length, and source and destination port numbers.

Most routers support some degree of packet filtering capability that enables these routers to provide firewall capabilities for protecting a network from unauthorized traffic. Such routers are often called packet-filtering routers or screening routers. Note, however, that implementing packet filtering on a traditional hardware router can cause a performance degradation of about 30 percent on the router's ability to handle network traffic.

Administrators can create rules or policies on screening routers for filtering out unwanted packets and can arrange these rules in the most efficient order. Using these rules, different actions can then be performed on each individual packet that arrives at the router. For example, a packet arriving at the router may be forwarded to its destination, dropped (ignored), or rejected (an error message is returned to the sender). Also, the router may log the event or send an alert to notify the administrator if configured. More sophisticated routers can also

- Modify the contents of the packet—for example, to perform Network Address Translation (NAT).
- Route the packet to a different destination than intended—for example, in load balancing a connection.

Some routers and firewalls can actually ping the source address of each packet to ensure that addresses local to the company network are coming from inside the network and are not being spoofed by a hacker outside the network.

Implementation

Packet filtering can be implemented on screening routers and firewall appliances in two basic ways: static filtering and dynamic filtering.

- **Static packet filtering:** This provides limited security by configuring selected ports as either permanently open or permanently closed. For example, to deny outside packets access to a company intranet server on port 80 (the standard port number for the Hypertext Transfer Protocol, or HTTP) you could configure the router or firewall to block all incoming packets directed toward port 80.
- **Dynamic packet filtering:** Also called stateful packet filtering, this provides enhanced security by allowing selected ports to be opened at the start of a legitimate session and then closed at the end of the session to secure the port against attempts at unauthorized access.

Static filtering



Ports 20, 21, and 1024–65,535 permanently open

Dynamic filtering



Port 21 permanently open

Packets from FTP server cause port 20, and two randomly assigned port numbers, to be temporarily opened.

Packet filtering. *Two forms of packet filtering.*

Dynamic packet filtering is particularly useful for protocols that allocate ports dynamically—for example, with the File Transfer Protocol (FTP). If you want to grant outside users secure access to an FTP server behind the firewall (within the corporate network), you need to consider the following:

- Port 21 (the FTP control port) needs to be left permanently open so that the FTP server can “listen” for connection attempts from outside clients. A static filtering rule can accomplish this.

- Port 20 (the FTP data port) needs to be opened only when data will be uploaded to or downloaded from the FTP server. With static filtering this port would have to be configured as permanently open, which could provide a door for hacking attempts. Dynamic filtering allows this port to be opened at the start of an FTP session and then closed at the end of the session.

Then, in order to establish an FTP connection with the client, the FTP server randomly assigns two port numbers in the range 1024 through 65,535 to the client, one for the control connection and one to transfer data. Because these ports are assigned randomly, there is no way to predict which ports above 1024 must be able to be opened by the firewall. With static filtering, you would therefore have to leave all ports above 1024 permanently open if you wanted to allow FTP access through the firewall, which would be a real security risk. With dynamic filtering, however, you can configure rules on the firewall that will read the packets issued by the server, dynamically open the two randomly assigned ports to allow a session to be opened, monitor the flow of packets to ensure that no unauthorized users attempt to hijack the session, and close the randomly assigned ports when the FTP session ends.

Marketplace

Most traditional hardware routers today support various degrees of packet filtering functions. Packet filtering can be configured on Cisco routers using Cisco Internetwork Operating System (IOS) commands.

An alternative to using screening routers is using a dedicated server with Microsoft Internet Security and Acceleration (ISA) Server installed. ISA Server includes dynamic packet filtering among its various other security features. If packet filtering is enabled, all incoming and outgoing packets are rejected unless an exception is explicitly created that allows them to pass. Packet filters can be enabled on ISA Server only if the machine has an external network interface, such as one connected to a distrusted network such as the Internet. ISA Server includes a number of predefined filters that you can use to quickly configure exceptions for common protocols when securing your network to the Internet. ISA Server also supports domain filters for allowing or denying access to Hypertext Transfer Protocol (HTTP) or File Transfer Protocol (FTP) services based on the source Internet Protocol (IP) address or Domain Name System (DNS) domain name. ISA Server can issue alerts to inform you when packets are rejected or illegal packets are detected. It will also keep a log of alerts that occur for analysis and record keeping.

See Also: *Domain Name System (DNS), File Transfer Protocol (FTP), firewall, Hypertext Transfer Protocol (HTTP), Internet Security and Acceleration Server (ISA Server), Internetwork Operating System (IOS), IP address, packet, port, router*

packet forwarding

Accepting a packet and transmitting it to its destination.

Overview

A router receives packets from hosts on one attached network and either forwards them to hosts on another attached network or forwards them to another router for further forwarding to a more distant network.

The exact way in which a packet is forwarded is typically based on a comparison of the packet's destination address with the routing table stored in the router. Each act of forwarding performed by a router is called a hop across the internetwork.

See Also: *hop count, packet, router*

packet switching

A form of communication in which data is broken into small packets that are forwarded individually across a network to their destination.

Overview

Packet switching allows data to be broken down and sent over computer networks and telecommunications services in short bursts called packets that contain sequence numbers so that they can be reassembled at the destination. These packets typically travel over a network or telecom "cloud" that contains routers or switches that examine and route packets from one such device to another, causing the packets to “hop” from switch to switch or router to router. Individual packets belonging to the same communication session might be switched over several different paths, depending on factors such as traffic congestion and switch availability at any given moment. Once the packets reach their destination, they are reassembled into a bit-stream to enable reliable communications to occur.

Types

Packet switching is the transmission method used for most computer networks because the data transported by these networks is fundamentally bursty in character and can tolerate latency (due to lost or dropped packets). In other words, the transmission bandwidth needed varies greatly in time, from relatively low traffic due to background services such as name resolution services, to periods of high bandwidth usage during activities such as file transfer. This contrasts with voice or video communication, in which a steady stream of information must be transmitted in order to maintain transmission quality and in which latency must remain minimized to preserve intelligibility.

The Internet is the prime example of a packet-switched network based on the Transmission Control Protocol/ Internet Protocol (TCP/IP). A series of routers located at various points on the Internet’s backbone forwards each packet received on the basis of destination address until the packet reaches its ultimate destination. TCP/IP is considered a connectionless packet-switching service because TCP connections are not kept open after data transmission is complete.

X.25 public data networks are another form of packet-switching service, in which packets (or more properly, frames) formatted with the High-level Data Link Control (HDLC) protocol are routed between different X.25 end stations using packet switches maintained by X.25 service providers. Unlike TCP/IP, X.25 is considered a connection-oriented packet-switching protocol because it is possible to establish permanent virtual circuits (PVCs) that keep the logical connection open even when no data is being sent. However, X.25 can be configured for connectionless communication by using switched virtual circuits (SVCs). An X.25 packet-switched network typically has a higher and more predictable latency (about 0.6 seconds between end stations) than a TCP/IP internetwork. This is primarily because X.25 packet switches use a store-and-forward mechanism to buffer data for transmission bursts, which introduces additional latency in communication. In addition, X.25 uses error checking between each node on the transmission path, while TCP/IP uses only end-to-end error checking.

Frame relay (formerly called “fast packet switching”) is another connection-oriented packet-switching service that gives better performance than X.25. It does this by switching packets immediately instead of using the store-and-forward mechanism of X.25 networks. Frame relay also eliminates flow control and error checking to speed up transmission. This is possible because frame relay networks use modern digital telephone lines, which are intrinsically much more reliable than the older analog phone lines on which much of the X.25 public network still depends. Frame relay supports only connection-oriented PVCs for its underlying switching architecture.

Finally, Asynchronous Transfer Mode (ATM) is yet another packet-switching service in which small fixed-length packets called cells are switched between points on a network.

Comparison

Packet switching is different from circuit switching, in which switches are configured in a fixed state for the duration of the session so that the route the data takes is fixed. A network that is circuit-switched requires a dedicated switched communication path for each communication even if its full bandwidth is not being used. In packet switching, bandwidth can be used when available for more efficient transmission. Circuit switching is generally used in telephone systems, and packet switching is used for computer networks. Digital cellular phone services were originally circuit-switched as well, but most cellular systems are now packet-switched networks to achieve greater efficiency in data transmission.

Another difference between packet switching and circuit switching is that circuits must first be established before any data is sent, and this generally involves a certain amount of setup time. During this process, the request for a circuit connection must pass through the circuit-switched network, resources must be reserved for the connection, and a signal must be returned to the initiating station when the circuit is established and data transmission can begin. Circuit-switched networks are thus useful only when the duration of the data transmission is much longer than the setup time involved in establishing the circuit. With packet switching, data can be sent at the start of transmission, which is better suited to the bursty, irregular nature of short network transmissions over a computer network or WAN link. Packet switching is thus a connectionless service in which it is unnecessary to establish a communications line (circuit) before sending a transmission.

See Also: *Asynchronous Transfer Mode (ATM), circuit-switched services, connectionless protocol, connection-oriented protocol, frame relay, Internet, latency, packet, packet-switching services, permanent virtual circuit (PVC), routing, switched virtual circuit (SVC), Transmission Control Protocol/Internet Protocol (TCP/IP), X.25*

packet-switching services

Telecommunications services provided by telcos for building wide area networks (WANs).

Overview

Packet-switching services are services that route customer traffic over telco packet-switching networks. Such services may include frame relay, X.25, Asynchronous Transfer Mode (ATM), or Switched Multimegabit Data Services (SMDS).

Packet-switching services are only one form of WAN service offered by telcos to enable enterprises to connect remote offices. The main alternative to packet-switched services are circuit-switched services such as T-carrier leased lines, which tend to be much more costly because they require dedicated telco switches instead of routing traffic over a public packet-switching network.

Implementation

In a typical scenario, the customer’s local network is typically connected through routers, bridges, Frame Relay Access Devices (FRADs), or other devices to a telco’s central office (CO). These customer premises equipment (CPE) either have built-in technology for connecting directly to packet-switching services or use intermediary devices such as Channel Service Unit/Data Service Unit (CSU/DSU) devices. The packet-switching CPE then takes network frames and “packages” them into packets suitable for the specific type of packet-switching service being used. The packaging process varies with the particular service used, but it basically consists of breaking down network frames into relatively small individual packets of data and tagging the packets with the destination address of the remote node to which the packet is directed. Each end node (local network access device) connected to the cloud has a Layer 2, or data-link layer, address that is known to every other end node. These addresses are used to route packet data between individual nodes on the WAN or to broadcast packets to all nodes when needed. Other information is also tagged onto the packets for error correction and other purposes, depending on the service used. The packets are usually small to lessen the load on the switching devices and to enable quick retransmission when transmission errors occur.

Packets are individually placed onto the carrier’s packet-switched network and switched from circuit to circuit until they reach their destination. Two packets forming part of the same network message might take entirely different routes to reach their destination node—it depends on the best route available at any given moment, as determined by the packet-switching services themselves. This is different from circuit-switched networks, in which all packets are sent over the same switched circuits for the duration of the connection. At the destination, the packets are reassembled into network frames and delivered to the remote network, where they are routed to their destination.



Packet-switching services. *How packet-switching services connect LANs into a WAN.*

In networking diagrams, a public packet-switched network is typically depicted as a cloud because the details of the switches and connections are not of interest to the customer—they are the responsibility of the carrier or carriers providing the services.

Advantages and Disadvantages

Advantages of packet-switching services include the following:

- Customers are not restricted to a single destination, as with point-to-point connections using leased lines.
- Packets can be routed to any destination that supports similar services, so businesses are not tied to a particular carrier or telco.
- Packet-switched networks have low latency and are suitable for hosting dedicated services such as company Web servers if the connection has sufficient bandwidth.
- Customers usually pay monthly rates plus additional charges based on bandwidth use, which means that the primary charges are on a per-transaction basis. The less you use the service, the less you pay.

The main disadvantage of packet-switching services is that they are shared services rather than dedicated ones, although today's telco services offer service level agreements (SLAs) and quality of service (QoS) to guarantee minimum bandwidth for greater reliability.

Notes

If virtual private network (VPN) technologies are employed, the public Internet can also be used as a packet-switching service for multipoint WAN connections, something that is rapidly growing in popularity due to the ubiquity and low cost of Internet access.

See Also: *Asynchronous Transfer Mode (ATM), bridge, Channel Service Unit/Data Service Unit (CSU/DSU), circuit-switched services, customer premises equipment (CPE), frame relay, Frame Relay Access Device (FRAD), leased line, packet, packet switching, quality of service (QoS), router, Switched Multimegabit Data Services (SMDS), T-carrier, telco, virtual private network (VPN), wide area network (WAN), X.25*

PAD

Stands for packet assembler/disassembler, a device that connects computers and other networking equipment to an X.25 packet-switched network.

See: *packet assembler/ disassembler (PAD)*

PAN

Stands for Personal Area Network, a network that surrounds and travels with an individual.

See: *Personal Area Network (PAN)*

PAP

Stands for Password Authentication Protocol, an authentication protocol supported by Point-to-Point Protocol (PPP).

See: *Password Authentication Protocol (PAP)*

parallel transmission

A form of signal transmission that sends multiple bits simultaneously over a cable.

Overview

Although a serial interface such as RS-232 transfers only 1 bit of data at a time, parallel interfaces typically transfer 8 bits (1 byte) of data at a time. Parallel interfaces are used mainly to connect printers, hard disks, and other peripherals to computers. A typical parallel interface for a computer uses a port that accepts a female DB25 connector. The parallel interface for a printer often uses a 36-pin Centronics connector.

For the DB25 connector, all 25 of the leads must be working for parallel transmission to function. In contrast, serial interfaces, which sometimes also use DB25 connectors, require only three active leads to transmit data. The parallel 25-pin connector has 17 leads for carrying signals and 8 leads for grounding. Of the 17 leads, 8 are used for data bit signals, 5 for status signals, and 4 for handshaking. Typical throughput of a parallel interface is 16 kilobits per second (Kbps) or 128 Kbps. Parallel communication is usually limited to cables of up to 20 feet (6 meters), but devices can be used to boost signals for longer distances.

Notes

A new type of parallel interface, conforming to the IEEE 1284 standard, supports bidirectional parallel communication at speeds of up to 1 megabit per second (MBps) over distances of up to 33 feet (10 meters). Parallel ports that support this standard are referred to as Enhanced Parallel Ports (EPPs) or Extended Capabilities Ports (ECPs).

See Also: *connector (device), IEEE 1284, RS-232, serial transmission*

parent domain

A domain that contains other subdomains.

Overview

A parent domain is a domain that has subdomains (or child domains) under it within a domain tree. The Domain Name System (DNS) name of the parent domain forms the basis of the names for the subdomains. For example, the parent domain named microsoft.com could include three child domains named dev.microsoft.com, marketing.microsoft.com, and support.microsoft.com. A two-way transitive trust exists between a parent domain and its associated child domains.

See Also: *Active Directory, domain (Microsoft Windows), domain tree*

parity information

Redundant information associated with any block of information that provides fault tolerance.

Overview

Parity information for a block of data is typically calculated from the data itself and can be used to reconstruct the data in the event of data loss or link failure. One place that parity information is used is in RAID-5 volumes. These volumes stripe data and parity information across a set of physical disks in such a way that for each stripe one disk contains the parity information while the other disks contain the data being stored. Each stripe uses a different (rotating) disk for storing its parity data.

The parity information for the stripe is created using an exclusive OR (Boolean XOR) operation on the data in the stripe. As a simple example, suppose that the block of binary data 10011 is to be written to a stripe on a RAID-5 volume that comprises six physical disks. Bit “1” is written to the first disk, bit “0” to the second disk, bit “0” to the third disk, and so on. The sixth, or parity, disk in the stripe contains the parity bit:

```
1 XOR 0 XOR 0 XOR 1 XOR 1 = 1
```

If the first disk fails so that the "1" bit stored on it is lost, the missing bit can be mathematically reconstructed using the remaining data bits and the parity bit for the stripe as follows:

```
? XOR (0 XOR 0 XOR 1 XOR 1) = 1
? XOR 0 = 1
Therefore ? = 1
```

See Also: *fault tolerance, redundant array of independent disks (RAID)*

partition (Active Directory)

A logical divider for organization information in Active Directory directory service in Microsoft Windows 2000.

Overview

Partitions divide Active Directory into separate sections and enable it to store large numbers of objects in a distributed directory over the network. They also allow Active Directory to scale to millions of objects. A partition functions as a physical storage container for a portion of the directory data for an organization. Each domain's directory information is stored in a separate partition and is identified using the distinguished name of the domain. The global catalog server can find an object in Active Directory by using the object's distinguished name (DN), which can be used to identify a replica of a partition that contains the object.

See Also: *Active Directory, distinguished name (DN), global catalog server*

partition (disk)

A portion of a physical disk that functions like a completely separate physical disk.

Overview

Partitions allow physical disks to function as multiple separate storage units for isolating operating systems from applications data on a single-boot system or for isolating operating systems from one another on a multiboot system.

Disks can have two types of partitions:

- **Primary partitions:** You can install a bootable operating system along with its associated file system on primary partitions. A physical disk can have up to four primary partitions.
- **Extended partitions:** A series of logical drives can be created on extended partitions. You can create an extended partition on a disk to overcome the limitation of four primary partitions per disk.

Notes

You can create partitions by using the Fdisk command in MS-DOS and all versions of Microsoft Windows, by using Disk Administrator in Windows NT, or by using the Disk Management tool in Windows 2000, Windows XP, and Windows .NET Server. Using the Fdisk command, you can create one primary partition and one extended partition. Disk Administrator can create up to four primary partitions or three primary and one extended partition. In Disk Management on Windows 2000, Windows XP, and Windows .NET Server, you can create partitions only on basic disks, not on dynamic disks (volumes are created on dynamic disks instead of partitions).

See Also: *basic disk, dynamic disk*

passive hub

Another name for a patch panel, a rack-mounted panel with a series of connectors that provides a branching-out point for network cabling to leave the wiring closet and make horizontal runs to wall plates in the work areas.

See: *patch panel*

passive optical network (PON)

A technology for bypassing the bottleneck of the local loop.

Overview

Traditional telco data services have been limited by the technology of the local loop, the "last mile" of copper wiring connecting businesses to the Public Switched Telephone Network (PSTN). This copper wiring means that data rates delivered to customers are far below the speeds at which data is transported in the core of telco networks. A passive optical network (PON) provides a way of working around this bottleneck that analysts estimate affects three-quarters of all businesses in the United States.

Implementation

Instead of deploying a full "fiber-to-the-curb" buildout with its high cost and complexity, a PON connects an optical access switch (OAS) or optical line terminal (OLT) located at the telco central office (CO) using a single strand of fiber-optic cabling to a passive optical splitter or coupler located in the neighborhood of a group of customers. The fiber connecting the CO to the splitter is passive—that is, it has no active components such as repeaters or optical amplifiers. Instead, a high-power laser is used to ensure that signals maintain strength over the trunk length, which is typically limited to 12 miles (19 kilometers). Multiple splitters can be deployed on a single fiber, up to a maximum of 32 splitters, and these may be configured in various ways to create star or ring networks as needed and support both permanent virtual circuits (PVCs) and switched virtual circuits (SVCs).



Passive optical network. *Provisioning business customers with high-speed data services using a PON.*

Customers can then be connected to splitters in their neighborhood either by deploying intelligent optical terminals (IOTs) or optical network units (ONUs) located at the customer premises and connecting them to the splitters using fiber-optic cabling (if it has been deployed to the customer premises) or by using existing copper local loop cabling running high-speed Digital Subscriber Line (DSL) technologies. The result is that high-speed data services can be more easily and efficiently provisioned to customers without the need to lay a lot of fiber.

PONs multiplex data at the splitters using either time-division multiplexing (TDM) for downstream traffic or time division multiple access (TDMA) for upstream. Two speed configurations are common: 155 megabits per second (Mbps) in both directions or asymmetric 622 Mbps downstream and 155 Mbps upstream. Some faster speeds have been achieved in test bed environments, such as OC-48 PONS running at 2.48 gigabits per second (Gbps).

Advantages and Disadvantages

PONs help telcos offer high-speed services to more customers without the cost of building out excessive amounts of neighborhood fiber structure. The downside is that they are shared, rather than dedicated, services, but by overlaying dense wavelength division multiplexing (DWDM) on PONs, telcos can provide users with individual lambdas simulating dedicated links. Such services, however, are likely to be several years away.

Marketplace

Several startups have reached market with PON switches, including Quantum Bridge and Terawave Communications. This market is likely to explode in the next few years as real-life PON rollouts accelerate.

For More Information

Visit the Full Service Access Network coalition at *www.fsanet.net.*

See Also: *central office (CO), Digital Subscriber Line (DSL), fiber-optic cabling, fiber to the curb (FTTC), permanent virtual circuit (PVC), Public Switched Telephone Network (PSTN), switched virtual circuit (SVC), telco, Time Division Multiple Access (TDMA), time-division multiplexing (TDM)*

passive termination

A terminator such as a resistor that absorbs signal energy and prevents signal bounce.

Overview

Passive termination is generally used in bus topology networks such as legacy 10Base2 and 10Base5 Ethernet networks. Termination is not required in star topology networks because the central concentrator (hub) provides the termination for each signal path. Ring topology networks such as Token Ring also do not require termination points because the signal path has no beginning or end.

Passive termination is also used in some forms of Small Computer System Interface (SCSI) systems for terminating a chain of SCSI devices. Active termination, which involves electronically canceling the signal incident on the end of a transmission system, is generally more expensive than passive termination but more efficient.

See Also: *10Base2, 10Base5, bus topology, Ethernet, hub, Small Computer System Interface (SCSI), star topology, Token Ring*

pass-through authentication

In Microsoft Windows NT–based networks, a method of performing authentication to a domain controller that resides in a trusted domain.

Overview

Pass-through authentication enables users to log on to computers in domains in which they do not have a valid user account. Users in a multidomain Windows NT–based network can thus access resources anywhere in the enterprise for which they have suitable permissions.

Consider the example of an enterprise consisting of three domains—two resource domains (the trusting domains) in which network resources such as shared folders or printers reside, and a master domain (the trusted domain) in which all user accounts are defined. The resource domains trust the master domain using Windows NT one-way nontransitive trusts. When a user attempts to log on to a computer in a resource domain, pass-through authentication takes place in one of two ways:

- When the user first logs on to the computer, the domain controller in the resource domain passes the user's credentials to the domain controller in the master domain. The user is authenticated, and the user's security identifier (SID) and group membership are returned to the domain controller in the resource domain.
- If the user tries to access a shared folder or printer in the other resource domain, the user's credentials are passed to the domain controller in the master domain in order to be authenticated for resource access.

Notes

Windows 2000 and Windows .NET Server networks employing Active Directory directory service and running in native mode use the Kerberos authentication protocol to authenticate across domain boundaries.

See Also: *Active Directory, domain (Microsoft Windows), Kerberos, trust*

password

A secure identifier that enables a user to access a secured resource.

Overview

Passwords are a part of a user's credentials, which include, at a minimum, the username and password. In a multidomain Microsoft Windows 2000–based enterprise, these credentials also include the user's domain. Passwords are generally known only to users themselves and possibly to members of the Administrators or Account Operators group on Windows 2000–based networks. Users can use their password to log on to the network and access resources for which they have permission. If a user forgets his or her password, the user cannot log on to the network unless the user contacts the administrator and requests that the password be reset.

Notes

When establishing a password policy for your company, you should determine

- Who will control passwords—the administrators or the users. Giving users control over their own passwords makes them completely responsible for their systems and personal data. You can configure Windows NT, Windows 2000, Windows XP, and

Windows .NET Server so that the first time users log on to the network they must change their initial password to one that only they know. This is usually the best solution.

- How complex passwords should be and how often they should be changed. If you make passwords too complex, such as random scrambles of letters, numbers, and symbols, the network might be less secure instead of more secure because users are likely to write down a difficult-to-remember password and tape it under their keyboard or in some other handy location. Also, if passwords must be changed frequently, users will typically make simple changes such as adding an incremental number to the end of each new password. The best policy is usually to require a password of six to eight characters that does not change and to teach users to select passwords that do not include family names, addresses, postal codes, or other easily obtainable personal information. Passwords should usually be simple combinations of letters and numbers, such as "blue144" or "max13one."

See Also: *username*

Password Authentication Protocol (PAP)

An authentication protocol supported by Point-to-Point Protocol (PPP).

Overview

Password Authentication Protocol (PAP) is a clear-text authentication scheme employed in PPP wide area network (WAN) links. PAP is not a secure form of authentication because the user's credentials are passed over the link in unencrypted form. For this reason, Challenge Handshake Authentication Protocol (CHAP) or some other authentication protocol is preferable if the remote PPP client supports it. If the password of a remote client using PAP has been compromised, the authentication server can be attacked using replay attacks or remote client impersonation.

PAP is outlined in RFC 1334.

Implementation

PAP uses a two-way handshake to perform authentication. Once the PPP link is established using the Link Control Protocol (LCP), the PPP client sends a username and password to the PPP server. The server uses its own authentication scheme and user database to authenticate the user, and if the authentication is successful, the server sends an acknowledgment to the client.

PAP is typically used only if the remote access server and the remote client cannot negotiate any higher form of authentication. The remote client initiates the PAP session when it attempts to connect to the PPP server or router. PAP merely identifies the client to the PPP server; the server then authenticates the client based on whatever authentication scheme and user database are implemented on the server.

See Also: *Challenge Handshake Authentication Protocol (CHAP), Link Control Protocol (LCP), Point-to-Point Protocol (PPP), wide area network (WAN)*

PASTE

Stands for Provider Architecture for Differentiated Services and Traffic Engineering, an emerging standard for Internet service billing and traffic delivery.

See: *Provider Architecture for Differentiated Services and Traffic Engineering (PASTE)*

PAT

Stands for port address translation, another name for network address port translation, a form of network address translation (NAT) in which both Internet Protocol (IP) addresses and port numbers are translated.

See: *network address translation (NAT)*

patch cable

A short cable for connecting networking devices.

Overview

Patch cables are usually unshielded twisted-pair (UTP) cabling terminated at both ends with RJ-45 connectors. Cable vendors usually supply patch cables in fixed lengths such as 1, 3, 6, 10, 25, 50, and 100 feet, and also in custom lengths. Patch cables usually come in various colors, which can be helpful in organizing the cabling joining devices on your equipment racks and avoiding "spaghetti." A common use for patch cables is to connect a port on a patch panel to a port on a hub or a switch.



Patch cable. *An example of a patch cable.*

Types

Always use patch cables that meet the requirements of your networking equipment and wiring infrastructure. Category 5 (Cat5) patch cables, which are certified to 100 megahertz (MHz), or enhanced Category 5 (Cat5e) patch cables, which are certified to 350 MHz and higher, are generally recommended for most modern structured wiring installations. Cat5 UTP patch cables should generally be no longer than 33 feet (10 meters).

Using patch cables with molded boots can help prevent kinks from forming and thus prevent pins from becoming bent through rough handling. Molded boots can also reduce the amount of crosstalk in the cable and allow it to perform at higher frequencies.

Be sure to purchase the correct type of patch cable according to its usage. For example:

- The wiring type (pinning) of the cable should match that of your installed premise cabling. Pinning types include TSB 568A, TSB 568B, and USOC, which are described in the table.
- Use straight-pinning or crossover cabling depending on the types of devices you are connecting. Crossover cabling, which has the send and receive wire pairs switched, is used primarily for connecting legacy hubs.

Color Codes by Cable Type

UTP Pinning Type	*Pinning for Each Wire Pair*
568A	Blue 4 and 5 Orange 3 and 6 Green 1 and 2 Brown 7 and 8
568B	Blue 4 and 5 Orange 1 and 2 Green 3 and 6 Brown 7 and 8
USOC	Blue 4 and 5 Orange 3 and 6 Green 2 and 7 Brown 1 and 8

See Also: *Category 5 (Cat5) cabling, crossover cable, crosstalk, enhanced Category 5 (Cat5e) cabling, infrastructure, premise cabling, RJ connectors, structured wiring, unshielded twisted-pair (UTP) cabling*

patch panel

A panel for connecting cabling in a structured wiring infrastructure.

Overview

Patch panels are usually standard 19-inch-wide panels for mounting in equipment racks in wiring closets. A typical patch panel is a rack-mounted panel with a series of RJ-45 jacks that provides a branching-out point for network cabling to leave the wiring closet and make horizontal runs to wall plates in the work areas. They typically contain between 16 and 96 ports for connecting to hubs and switches using patch cables.

Patch panels are mainly used to organize wiring and to avoid "spaghetti." The horizontal cables running from the wiring closet to the wall plates are usually connected to the back of the patch panel, and the patch cords connecting to the hubs and switches plug into the front of the patch panel. The back of the patch panel is a form of punchdown block—wires are not soldered but punched down using a sharp tool called a punchdown block tool. Although an older name for a patch panel is “passive hub,” a patch panel is a “hub” only in the sense that it is a physical device in which wires are concentrated—patch panels themselves cannot be used to network computers. All true hubs used in networking are active hubs, which are powered devices that regenerate signals coming into one port for transmission through other ports on the hub.



Patch panel. *Example of a patch panel.*

Types

Modular patch panels allow the greatest flexibility of configuration by allowing different kinds of jacks (RJ-45 or fiber-optic connectors) to be installed as needed.

Although front-access patch panels are the easiest to install in cramped conditions, you can use hinged or folding patch panels as a convenient alternative to full-size, rack-mounted patch panels.

There are a few things you should be aware of when selecting patch panels:

- Be sure that your patch panels are Category 5 (Cat5)–approved if you plan to upgrade your network.
- Do not remove excessive amounts of cable jacket when you terminate Cat5 cables to terminal blocks.
- Purchase patch panels with built-in surge protection to protect expensive Ethernet switches.

Use cable managers to organize and support cables connected to patch panels.

Notes

In telephony applications, the termination point for twisted-pair wiring is usually called a punchdown block instead of a patch panel.

See Also: *cabling, hub, infrastructure, premise cabling, rack, RJ connectors, structured wiring, switch, wall plate, wiring closet*

path

The route that a user or application follows to locate a file in a file system, an object in a directory, a server on a network, or some other kind of resource in a hierarchical system.

Overview

A path to an object can be one of the following:

- **Absolute path:** This starts from the root of the file system or directory.
- **Relative path:** This starts from the user’s current directory or location.

Examples

On a system running Microsoft Windows, the absolute path to a file is expressed using backslashes, as follows:

```
C:\Windows\Profiles\Administrator\User.dat
```

If the current directory is C:\Windows\Profiles, the relative path to the same file is as follows:

```
\Administrator\User.dat
```

To access files in shared folders on a Windows network, you can use the Universal Naming Convention (UNC) path:

```
\\server16\pub\readme.txt
```

On UNIX platforms, forward slashes are used instead of backslashes, as in this example:

```
/user/bin/blah.gz
```

To request a Web page on the Internet, you specify the page's Uniform Resource Locator (URL), which is essentially the path to the page in the hierarchical Domain Name System (DNS), as follows: *http://www.microsoft.com/support/FAQ.htm*

See Also: *Domain Name System (DNS), Uniform Resource Locator (URL), Universal Naming Convention (UNC)*

pathping

A utility that combines features of ping and tracert.

Overview

Pathping is a Transmission Control Protocol/Internet Protocol (TCP/IP) troubleshooting tool that was introduced in Microsoft Windows 2000 and is included in both Windows XP and Windows .NET Server. You can use pathping to discover the route to a remote host such as tracert (or the UNIX traceroute). It then pings the remote host for a period of time and collects statistics and reports them.

Examples

The following example pathpings a router on the Internet from a remote location:

```
C:\>pathping core2-toronto12-pos10-1.in.
bellnexxia.net

Tracing route to
core2-toronto12-pos10-1.in.bellnexxia.net
[206.108.97.29] over a maximum of 30 hops:

  0  mtit44 [216.130.91.131]

  1  wnpgas06.mts.net [216.130.90.1]

  2  216.130.90.7

  3  wnpgbr01-g11-102.mts.net [205.200.28.82]

  4  dis4-winnipeg32-pos11-0.in.bellnexxia.net
[206.108.110.5]

  5  core2-winnipeg32-pos6-2.in.bellnexxia.net
[206.108.102.129]

  6  core2-toronto12-pos10-1.in.bellnexxia.net
[206.108.97.29]

Computing statistics for 150 seconds...

       Source to Here  This Node/Link
Hop  RTT Lost/Sent=Pct  Lost/Sent=Pct  Address

  0                    babel33 [216.129.43.88]

                        0/ 100 = 0%

  1  191ms 0/ 100=0%    0/ 100 = 0%
wnpgas06.mts.net [216.130.90.1]

                        0/ 100 = 0%

  2  190ms 0/ 100=0%  0/100=0%  216.130.90.7

                        0/ 100 = 0%

  3  204ms 0/ 100=0%  0/
100=0%  wnpgbr01-g11-102.mts.net
[205.200.28.82]

                        0/ 100 = 0%

  4  225ms 0/ 100=0%  0/
100=0%  dis4-winnipeg32-pos11-0.in.bellnexxia.
net [206.108.110.5]

                        0/ 100 = 0%

  5  225ms 0/ 100=0%  0/
100=0%  core2-winnipeg32-pos6-2.in.bellnexxia.
net [206.108.102.129]

                        0/ 100 = 0%

  6  230ms 0/ 100=0%  0/
100=0%  core2-toronto12-pos10-1.in.bellnexxia.
net [206.108.97.29]

Trace complete.
```

See Also: *ping, tracert, Transmission Control Protocol/Internet Protocol (TCP/IP)*

P

PBX

Stands for Private Branch Exchange, a telephone switch at the customer premises that supports multiple independent telephone extensions.

See: *Private Branch Exchange (PBX)*

PCM

Stands for pulse code modulation. a common method used by telcos for converting analog signals into digital.

See: *pulse code modulation (PCM)*

PCS

Stands for Personal Communications Services, a general term for digital cellular phone technologies.

See: *Personal Communications Services (PCS)*

PCT

Stands for Private Communication Technology, an encryption protocol similar to Secure Sockets Layer (SSL).

See: *Private Communication Technology (PCT)*

PDA

Stands for Personal Digital Assistant, a handheld computer used mainly as a personal information manager (PIM) and messaging device.

See: *Personal Digital Assistant (PDA)*

PDC

Stands for primary domain controller, a Microsoft Windows NT domain controller that contains the master copy of the Security Accounts Manager (SAM) database.

See: *primary domain controller (PDC)*

peer server

A computer that functions as a server for a group of users in a peer-to-peer network.

Overview

For example, in a small office with only five users running Microsoft Windows XP, you can set aside an additional machine running Windows XP as a peer server for storing company files. You should use peer servers only in small networks with no great need for security. Security on peer servers is limited to share-level security, which allows only three kinds of access:

- Read-only access based on a password
- Full-control access based on a password
- A combination of the above, based on two separate passwords

If security is an issue, consider using a dedicated server running Windows 2000 or Windows .NET Server.

See Also: *peer-to-peer network*

peer-to-peer network

A network in which the computers are managed independently of one another and have equal rights for initiating communication with each other, sharing resources, and validating users.

Overview

A peer-to-peer network usually has no special server for authenticating users. Each computer manages its own security, so a separate user account might need to be created for each computer that a user needs to access. Users usually store files on their own computers and are responsible for ensuring that those files are appropriately backed up. In a peer-to-peer network, each computer typically runs both client and server software and can be used to make resources available to other users or to access shared resources on the network.

Peer-to-peer networks are simple to set up and are often ideal for small businesses that have fewer than 10 computers and that cannot afford a server-based solution. The disadvantages of peer-to-peer networks are poor security and lack of centralized file storage and backup facilities.

See Also: *server-based network*

PEM

Stands for Privacy Enhanced Mail, a specification for encrypting and securing e-mail.

See: *Privacy Enhanced Mail (PEM)*

perimeter network

A security network at the boundary between a corporate local area network (LAN) and the Internet.

Overview

The perimeter network is an important part of the security framework of any corporate enterprise. The perimeter network is designed to protect servers on the corporate network from attack by malicious users on the Internet. Formerly known as a demilitarized zone (DMZ), the term *perimeter network* emphasizes the location of this security network as standing between the corporate LAN and the Internet.

Implementation

The perimeter network is implemented using a corporate firewall at the border of the corporate LAN. In a typical configuration, such a firewall has three network interfaces:

- **Internet:** The interface exposed to the external, unsecure public network called the Internet.
- **Intranet:** The interface connected to the corporate LAN where vulnerable servers reside.
- **Perimeter network:** The interface connected to the separate network called the perimeter network or demilitarized zone (DMZ). This interface is on the same side of the firewall as the Internet interface, making servers on the perimeter network available to users on the Internet.

The perimeter network typically contains the following kinds of servers:

- **Proxy servers:** These provide secure access for external users to information stored on intranet servers on the corporate LAN.
- **Web servers:** These are public web servers accessible to everyone on the Internet.



Perimeter network. *How a perimeter network is implemented.*

- **Virtual private network (VPN) servers:** These are remote access and authentication servers that allow company employees to securely access servers on their corporate LAN from outside the LAN over the Internet.

In addition, the perimeter network may contain routers, switches, and other devices to enable it to function as desired.

See Also: *firewall, network security, proxy server, virtual private network (VPN)*

Perl

Stands for Practical Extraction and Reporting Language, an interpreted scripting language used for Web applications.

See: *Practical Extraction and Reporting Language (Perl)*

permanent virtual circuit (PVC)

A dedicated circuit between two nodes in a circuit-switched network.



Permanent virtual circuit (PVC). *How a PVC can be established between two LANs to form a WAN.*

Overview

Permanent virtual circuits (PVCs) are typically used in frame relay networking to establish permanent, dedicated links between remote stations or networks. The effect is similar to that of a leased line, but it has added flexibility because fault tolerance can be built into the circuit. For example, BellSouth Corporation offers a frame relay service called Intelligent PVCs that are continually monitored so that should a PVC fail, the switches in the frame relay cloud automatically reconfigure to reroute the customer's traffic over a different circuit.

PVCs are best for wide area network (WAN) links that carry steady, high volumes of network traffic. PVCs offer guaranteed bandwidth and extremely low latency for establishing a connection. Also, because the switching pathway is permanent, the quality of the connection does not vary with time. The result is more reliable service than switched virtual circuits (SVCs). However, PVCs are more expensive than SVCs because telco resources are dedicated to the customer and cannot be used for other purposes. Furthermore, with a PVC you pay for the bandwidth whether or not you use it; with SVCs, the amount you pay depends on how much bandwidth you use.

Implementation

To provision a PVC for a customer, switches are first set up and configured by the telco or carrier to provide a permanent, point-to-point connection between the two nodes. These circuits are called permanent because the telco dedicates specific resources (switches) to your company—they cannot be used by anyone else as long as you lease the service. The switches are called "virtual" because the customer does not have a physical wire connecting two networks but rather a logical connection between switches configured by the telco's management software. In fact, the customer does not even need to know how the circuit is set up.

See Also: *frame relay, frame relay cloud, switched virtual circuit (SVC), virtual circuit*

permissions

Authorization to access or perform an operation on a specific object.

Overview

Permissions are settings that you establish for a network resource to control which users and groups can access the resource and what degree of access they have. Permissions are implemented at several levels in Microsoft

Windows by using discretionary access control lists (DACLs), which are attached to the object they control.

Permissions can be granted to objects by their owners and by anyone to whom owners delegate this ability. Permissions can be used to both grant and deny access to objects—permissions that are not explicitly granted are implicitly denied.

Examples

Examples of permission types on the Windows platform include the following:

- **Shared folder permissions:** Can be applied to shared folders on Windows systems to control access to network shares by users
- **NTFS permissions:** Can be applied to files and folders on NTFS volumes for both local and network control of access to the resources
- **Print permissions:** Can be assigned to printers to control who can manage printers, manage documents, or print documents
- **Active Directory permissions:** Can be assigned to objects within Active Directory directory service of Windows 2000 or Windows .NET Server using Active Directory Users and Computers
- **Public folder permissions:** Can be assigned using Microsoft Outlook to files in public folders to control who can read, edit, or delete those files

See Also: *access control, Active Directory, discretionary access control list (DACL), NTFS permissions (Windows 2000, Windows XP, and Windows .NET Server), NTFS permissions (Windows NT), print permissions, shared folder permissions*

persistent connection

A network connection that is opened for communications to take place and then kept open in case it is needed again.

Overview

One place persistent connections are employed is with the Windows Internet Name Service (WINS) on the Microsoft Windows 2000 platform. Windows 2000 WINS replication partners maintain persistent connections among themselves so that replication can be initiated at any time without the network traffic overhead associated with establishing new connections. This means that WINS databases are updated immediately and shared network resources are always available.

On the other hand, in the earlier version of WINS for Windows NT Server replication partners had to open a new connection between each other every time WINS replication was initiated. As a result, most administrators of large networks configured WINS replication to occur at certain time intervals or after a certain number of updates to the WINS database had accumulated. Because of delays in updating WINS databases on WINS servers, clients sometimes could not access shared network resources.

See Also: *Windows Internet Name Service (WINS)*

Personal Area Network (PAN)

A network that surrounds and travels with an individual.

Overview

The idea of a Personal Area Network (PAN) sounds a lot like science fiction, but with the proliferation of mobile devices such as cell phones, laptops, pagers, and Personal Digital Assistants (PDAs) carried by many knowledge workers today, the day of the PAN may at last be at hand. The enabling technology for PANs may be Bluetooth, a wireless communication technology for small, ad-hoc networks. Using Bluetooth, a "PAN-wired" individual could walk to the front door of an office building and the door would open automatically as the building security network detects and communicates with information stored in the user's PDA. As this person walks up to the soft drink machine, his or her PAN could notify the machine to issue a favorite drink and automatically debit the cost from his or her account. PAN enthusiasts have envisioned other futuristic scenarios, but they are probably still light years away for most of us!

See Also: *Bluetooth*

Personal Communications Services (PCS)

A general term for digital cellular phone technologies.

Overview

Personal Communications Services (PCS) technologies were first developed in the early 1990s because the existing Advanced Mobile Phone Service (AMPS) technologies were running out of available bandwidth in the electromagnetic frequency spectrum. PCS systems are end-to-end digital in nature and are more secure than analog cellular systems. PCS networks can be used for voice, fax, and data applications such as e-mail and file transfers. PCS systems were originally circuit-switched, although most are now being migrated to packet-switched networks.

Some of the standards and technologies that developed from the PCS initiatives include the following:

- **Time Division Multiple Access (TDMA):** These digital cellular systems are based on the TDMA IS-136 standard. TDMA divides frequency bands into time slots and then multiplexes user conversations within these slots. TDMA operates in both the 800-megahertz (MHz) and 1900-MHz frequency bands, but only frequencies at 1900 MHz are specifically referred to as PCS, and those in the 800-MHz range are referred to as cellular.
- **Code Division Multiple Access (CDMA):** These digital cellular systems are based on the CDMA IS-95 standard, which was developed by QUALCOMM. CDMA uses spread-spectrum transmission technologies and assigns codes to individual users transmitting within the same broad frequency spectrum. CDMA operates at both the 800-MHz and 1900-MHz frequencies, but only frequencies at 1900 MHz are specifically referred to as PCS, while those in the 800-MHz range are referred to as cellular.
- **Global System for Mobile Communications (GSM):** These digital cellular systems are based on the GSM 1900 standard. GSM is based on TDMA technologies and divides frequency bands into time slots. GSM has the advantage of supporting roaming between Europe and North America. GSM operates in the 1900-MHz frequency range (or the 1800-MHz range in Europe).

Types

PCS systems and services can also be classified as follows:

- **Narrowband PCS:** Uses the 900-MHz portion of the electromagnetic spectrum, specifically the frequency bands 901–902, 930–931, and 940–941 MHz. Narrowband PCS is used for wireless telephony, wireless data transmission, voice message paging and text-based paging, and other services.
- **Broadband PCS:** A newer technology that uses the 2-gigahertz (GHz) portion of the electromagnetic spectrum, specifically the frequency band from 1850 to 1990 MHz, with the exception of a 20-MHz band reserved for unlicensed voice and data services. Broadband PCS with its greater bandwidth allocation is used or intended for wireless telephony, high-speed wireless data transmission, portable facsimile transmission, wireless Personal Digital Assistants (PDAs), and wireless video telephony services.

See Also: *Advanced Mobile Phone Service (AMPS), broadband transmission, cellular communications, circuit-switched services, Code Division Multiple Access (CDMA), Global System for Mobile Communications (GSM), packet-switching services, Time Division Multiple Access (TDMA)*

Personal Digital Assistant (PDA)

A handheld computer used mainly as a personal information manager (PIM) and messaging device.

Overview

Personal Digital Assistants (PDAs) are generally used for personal and business functions such as keeping track of appointments, sending and receiving e-mail, browsing the Internet, composing memos, performing spreadsheet calculations, managing contact lists, online banking, and viewing stock quotes. A typical PDA has a small grayscale or color liquid crystal display (LCD) with either a small keyboard or a pen-based user interface for entering data. Information can be exchanged with a desktop or laptop PC by using a docking cradle connected to the computer using a serial port, Universal Serial Bus (USB) port, or infrared (IR) communication port, depending on the make and model. The processing power of a typical PDA is similar to that of a 386 processor, and its memory is typically limited to about 16 megabytes. Many PDAs also support standard or even wireless modems for sending and receiving e-mail or accessing specialized Internet content.

Marketplace

One of the earliest PDAs was the Apple Newton, a device whose reach was beyond the technology of its time (it was too large and heavy). Most PDAs today run one of two operating systems:

- **Palm OS:** This is used by the Palm Pilot and Handspring Visor line of PDAs. Palm OS is the most widely-used PDA platform with about 70 percent of the market share, with particular focus on the business executive and consumer markets. The current version of this platform is Palm OS 4.
- **Pocket PC:** This is a version of Microsoft Windows CE used by the Compaq iPaq and Hewlett-Packard Jornada series of PDAs. The Pocket PC platform is rapidly growing in popularity, especially in the large corporation, where it integrates well with Windows-based networks since the Pocket PC includes scaled-down versions of many popular Microsoft software products. The current version of this platform is Pocket PC 2002.

Because PDA management is becoming an increasingly important job for network administrators, a number of vendors have introduced platforms for managing large numbers of PDAs in the enterprise. Examples include two products from TRG (now called HandEra):

- InstallPro Application Guard, which lets administrators deploy applications to Palm OS PDAs.
- ImagePro Deployment Manager, which lets you create an image of a PDA's contents for backup or deployment purposes.

The eventual success of PDAs in the enterprise depends largely upon these new management platforms.

See Also: *universal serial bus (USB)*

PGP

Stands for Pretty Good Privacy, a popular scheme for encrypting e-mail for secure messaging.

See: *Pretty Good Privacy (PGP)*

PHP

A popular server-side scripting language.

Overview

PHP is a scripting language used to create dynamic Web applications. It is an open-source platform and is available for a wide range of operating systems including Linux, versions of UNIX, and Microsoft Windows.

PHP is similar to C language in syntax and to Perl in its support for regular expressions. PHP has capabilities similar to other popular Web scripting languages, including Microsoft Corporation's Active Server Pages (ASP), Sun Microsystems' Java Server Pages (JSP), and Allaire Corporation's ColdFusion. When used on the Apache web server platform, PHP can be built as a binary module and run as a Common Gateway Interface (CGI) application. PHP includes support for Open Database Connectivity (ODBC) databases and can be interfaced with external libraries to extend its functionality.

Notes

The acronym *PHP* originally meant "personal home pages," but the product quickly outgrew this name. The acronym now officially means "PHP: Hypertext Preprocessor," a recursive definition in the style of GNU's not UNIX (GNU).

See Also: *Active Server Pages (ASP), Common Gateway Interface (CGI), Java Server Pages (JSP), open database connectivity (ODBC), Practical Extraction and Reporting Language (Perl), scripting*

physical address

Another name for MAC address, a Layer 2 address for a network node.

See: *MAC address*

physical layer

Layer 1 (or the PHY layer) of the Open Systems Interconnection (OSI) reference model.

Overview

The physical layer is the bottom layer of the seven-layer OSI networking architecture model. It establishes the physical interface and mechanisms for placing a raw stream of bits onto the wire. It defines the voltage, current, modulation, bit synchronization, connection activation and deactivation, and various electrical characteristics for the transmission media (such as unshielded or shielded twisted-pair cabling, coaxial cabling, and fiber-optic cabling). Protocols at the PHY layer include IEEE 802.3, RS-232C, and X.21. Repeaters, transceivers, network interface cards (NICs), and cabling all operate at the PHY level.

See Also: *cabling, Open Systems Interconnection (OSI) reference model, network interface card (NIC), protocol, repeater*

piconet

The basic building block of Bluetooth wireless networks.

Overview

A piconet is a small network running Bluetooth that has eight or fewer devices on it. Piconets can also be connected to form larger networks called scatternets, but it is unlikely that individual users will often carry more than eight Bluetooth-enabled devices on their person at any given time!

Piconets are not the same as Personal Area Networks (PANs). A PAN may be constructed from one or more separate piconets, but generally devices that need to communicate frequently with each other (such as a cell phone and a head set) should be on the same piconet.

See Also: *Bluetooth, Personal Area Network (PAN)*

PIM-DM

Stands for Protocol Independent Multicast-Dense Mode, a dense mode multicast routing protocol.

See: *Protocol Independent Multicast-Dense Mode (PIM-DM)*

PIM-SM

Stands for Protocol Independent Multicast-Sparse Mode, a sparse mode multicast routing protocol.

See: *Protocol Independent Multicast-Sparse Mode (PIM-SM)*

ping

A utility that verifies the integrity of a network connection.

Overview

The Ping command is one of the first commands to use when troubleshooting communication problems on a Transmission Control Protocol/Internet Protocol (TCP/IP) network. To use ping, you open a command line window and type **ping** followed by either the IP address or the fully qualified domain name (FQDN) of the host for which you want to test network connectivity. Internet Control Message Protocol (ICMP) echo packets are then transmitted to the host, and if connectivity is working, an equal number of echo replies are received. The replies show the packet size in bytes, response time in milliseconds, and Time to Live (TTL) of the echo reply. The TTL is decremented for each hop along the way and indicates the number of routers (hops) passed through along the network path.

The usual procedure for using ping to troubleshoot communications on a TCP/IP network is as follows:

1. Verify that TCP/IP is installed and running by pinging the local loopback address using **ping 127.0.0.1**.
2. Ping your own IP address and host name.
3. Ping the IP address of the default gateway for your local network.
4. Ping the IP address of a host on a remote network.

If all of these steps produce the expected results, TCP/IP is installed and running properly on your network. If you can ping a host's IP address but not its fully qualified domain name (FQDN), you probably have a name resolution problem. Check your Domain Name System (DNS) configuration and make sure that the DNS server is running, or check your Hosts file if it is implemented.

Notes

Although ping stands for Packet Internet Groper, it is almost never referred to by that name anymore.

See Also: *default gateway, Domain Name System (DNS), fully qualified domain name (FQDN), host, Internet Control Message Protocol (ICMP), loopback address, pathping, tracert, Transmission Control Protocol/Internet Protocol (TCP/IP)*

PKCS

Stands for Public Key Cryptography Standards, a set of standards for cryptography.

See: *Public Key Cryptography Standards (PKCS)*

PKCS #7

Also called the Cryptographic Message Syntax Standard, a cryptographic standard from RSA Security for the exchange of digital certificates in public key cryptography.

Overview

PKCS #7 specifies the syntax of digital certificates and other encrypted information—specifically, the method by which data is encrypted and digitally signed, as well as the algorithms involved. When you use PKCS #7 to digitally sign data, the result includes the signing certificates, a list of relevant certificate revocation lists, and any other certificates in the certification path. If you use PKCS #7 to encrypt data, it usually includes references to the issuer and the serial number of the certificate that is associated with the public key that can be used to decrypt the encrypted data.

PKCS #7 also supports additional features such as

- Recursion, in which a digital envelope is enclosed in a digital envelope, which is enclosed in another digital envelope, and so on
- Time-stamping of encrypted messages and digital signatures
- Counter-signatures and user-defined attributes

Implementation

PKCS #7 can be used to encrypt two types of data:

- **Base data:** Data that has not been encrypted and contains no cryptographic enhancements such as hashes or digital signatures.
- **Enhanced data:** Data that is encrypted or contains cryptographic enhancements or both. Enhanced content encapsulates one form of content within another.

A variety of content types are defined by the PKCS #7 standard, including the following:

- **Data:** String of bytes or octets.
- **Signed data:** Data along with an encrypted message digest. A message digest is the value produced when a hashing algorithm is applied to data. (The terms *digest* and *hash* are synonymous.) The recipient uses the message digest to confirm that the original message was not tampered with during transit and to validate the identity of the sender.
- **Enveloped data:** Encrypted data plus the public key that can decrypt the data. You use this method to keep the contents of the message secret from all but trusted recipients.
- **Signed-and-enveloped data:** Encrypted content with its public key and doubly encrypted message digest.
- **Digested data:** Data plus a message digest.
- **Encrypted data alone:** The public key for decrypting the data must be transmitted by some other mechanism in this case.

See Also: *digital certificate, encryption, Public Key Cryptography Standards (PKCS)*

PKCS #12

A cryptographic standard for the exchange of digital certificates.

Overview

PKCS #12 is an industry-standard format for the transfer, backup, and restoration of digital certificates and their associated public or private keys used in public key cryptography. PKCS #12 is the export format that is usually used to export a digital certificate with its private key, because exposing a user's private key using a less secure method of export poses a security risk. PKCS #12 is used to export certificates to other computers, to removable media for backup purposes, or to smart cards to enable smart card authentication schemes.

See Also: *digital certificate, encryption, public key cryptography, Public Key Cryptography Standards (PKCS)*

PKI

Stands for public key infrastructure, an infrastructure to enable the use of public key cryptography in a corporate or public setting.

See: *public key infrastructure (PKI)*

Plain Old Telephone Service (POTS)

The basic analog telecommunications service provided by a local telco.

Overview

Plain Old Telephone Service (POTS) is an inexpensive circuit-switched service originally designed for voice communications and supporting data transfer speeds up to 56 kilobits per second (Kbps). POTS was originally the only type of telephone service available, and most residential customers still use it today. Since 1972, however, the old analog POTS is gradually migrating toward an all-digital Integrated Services Digital Network (ISDN) infrastructure, starting mainly with trunk lines and business connections. The combination of the old analog POTS with the newer ISDN infrastructure is commonly called the Public Switched Telephone Network (PSTN).

Architecture

Starting from your home or customer premises, POTS uses a copper twisted-pair cable that eventually terminates at your local telco's central office (CO). Send and receive functions are shared over both wires of the two-wire cable. The connection between the customer premises and the CO forms what is known as the local loop. The CO is a facility with switches that can connect you to another local subscriber, to another CO, or to a long-distance provider, depending on whether your call is local or long distance.

Although POTS is basically an analog service in the local loop and is thus designed for voice traffic, it can also transport data traffic by using a modem to convert analog signals into digital and back again.

See Also: *central office (CO), Integrated Services Digital Network (ISDN), modem, Public Switched Telephone Network (PSTN), telco*

Platform for Privacy Preferences (P3P)

A standard specifying how Web sites communicate their privacy policy to visitors.

Overview

Platform for Privacy Preferences (P3P) is a project of the World Wide Web Consortium (W3C), whose goal is to give Internet users greater control over the privacy of their personal and financial information. Major industry players such as Microsoft Corporation, IBM, America Online, and AT&T have committed to implementing P3P on their sites. Internet Explorer 6, which comes with Windows XP and Windows .NET Server, is P3P-enabled.

P3P is an ongoing initiative to develop standards to ensure the privacy of e-commerce and other transactions over the Internet. The initial version 1 of P3P ensures that users who visit P3P-compliant Web sites will be presented with the site's privacy policy so they can decide whether to give their personal information to the site when doing business or shopping on the Internet. P3P is designed to make corporate privacy policies more accessible to users, instead of requiring users to dig through complex Web sites to find them buried somewhere.

Implementation

P3P specifies a standard format for companies to create machine-readable versions of their privacy policies. When P3P is implemented on a Web site, a user visiting the site will automatically download the company's policy the first time he or she visits the site. Using client-side P3P software, the policy is then displayed on the user's machine along with options about what kind of privacy level the user wants to establish with the site. Once user has selected the privacy level, the next time the user visits the site the policy is automatically downloaded, compared to user settings, and the required degree of privacy is enforced.

Server-side P3P software translates document-based privacy policies into a standardized Extensible Markup Language (XML) format. Client-side P3P software may be integrated into Web browsers, downloaded as a plug in, or built into various applications such as financial applications.

Issues

P3P is an evolving standard. The initial version, P3P 1, has several weaknesses, namely:

- There is no provision to ensure that personal information collected by companies will not be used against the user's wishes. In other words, companies may falsify their privacy policies in order to trick users into submitting their personal data. P3P 1 is thus essentially an "honor system" that still requires users to trust the companies they transact with, but it does make the company's privacy policy more visible so the user can take legal action if the policy has been misrepresented.
- There is no restriction on any interorganizational transfer of user data that may occur during or after an online transaction. For example, the policy does not restrict what the company does with regard to interaction with credit institutions during payment of a transaction.

For More Information

Visit the W3C's P3P site at *www.w3c.org/p3p.*

See Also: *Internet, World Wide Web Consortium (W3C), XML*

plenum cabling

Cabling used for long cable runs within a building.

Overview

Also known as CMP cabling, plenum cabling is a grade of cabling that is resistant to combustion and is used for horizontal cable runs in building plenums and vertical rises such as elevator shafts. A plenum is a horizontal space within a building that houses building components and allows the movement of air. False ceilings are not considered plenums.

Plenum cabling is less flexible and costlier than polyvinyl chloride (PVC) cabling. The external insulating jacket of plenum cabling is usually a fluoropolymer such as Teflon FEP.

See Also: *cabling, polyvinyl chloride (PVC) cabling, premise cabling*

Plug and Play (PnP)

A design philosophy and set of specifications for PC architectures that enables computer hardware, peripherals, device drivers, and operating systems to be easily reconfigured with minimal user understanding and intervention.

Overview

Plug and Play (PnP) frees users from having to manually configure devices and device drivers when they add or remove peripherals from computer systems. For example, to configure a non-PnP sound card, a user typically has to manually change jumpers or dual inline package (DIP) switches on the sound card itself, a task that is often difficult for the inexperienced user. With PnP, you simply plug in the device and follow a series of prompts (if any are necessary) to configure the appropriate drivers for your device.

Implementation

A true PnP system consists of the following three elements:

- A PnP operating system such as Microsoft Windows 2000 or Windows XP.
- A PnP system basic input/output system (BIOS) that supports Advanced Power Management (APM)

or Advanced Configuration for Power Interface (ACPI), automatic configuration of boot and motherboard devices, hot docking, and other features.

- PnP system buses such as Peripheral Component Interconnect (PCI) or universal serial bus (USB) and PnP peripheral devices (internal or external) and their associated drivers. PnP peripheral devices include universal serial bus (USB), Institute of Electrical and Electronics Engineers (IEEE) 1394, Small Computer System Interface (SCSI), Personal Computer Memory Card International Association (PCMCIA), and PCI devices. Industry Standard Architecture (ISA), Extended Industry Standard Architecture (EISA), and Video Electronics Standards Association (VESA) devices are not fully PnP. Other PnP devices include Integrated Device Electronics (IDE) controllers, Enhanced Capabilities Port (ECP) parallel ports, and video adapters.

If a system does not support all three of these features, it is not truly PnP, although it might have some limited PnP support. In a completely PnP system, these features work together to automatically enumerate (identify) new devices installed in or connected to the system, determine their resource requirements, establish a system configuration that can support these requirements without device conflicts, program the devices as necessary and load their device drivers, and notify the user of the changes to the system's configuration.

When you add a new hardware device to a PnP system, the Add New Hardware Wizard starts and installs the necessary drivers for the hardware. The wizard selects suitable hardware resources for the device, which might include an interrupt request (IRQ) line, input/output (I/O) address, direct memory access (DMA) channel, and memory range. If the system cannot properly detect the hardware, you can manually run the Add New Hardware Wizard to configure the hardware.

Notes

When using PnP to install new devices on Microsoft Windows platforms, be sure that the new device is attached to the computer and is turned on before you run the Add New Hardware Wizard.

See Also: *Advanced Configuration and Power Interface (ACPI), Advanced Power Management (APM)*

P-node

A NetBIOS name resolution method used for name registration and resolution.

Overview

P-node is a type of NetBIOS over Transmission Control Protocol/Internet Protocol (TCP/IP) node and is defined in RFCs 1001 and 1002. P-node is supported by computers running Microsoft Windows and is one of four basic methods supported by Windows NT for resolving NetBIOS host names (that is, computer names) into IP addresses. Name resolution is the process of converting the name of a host on the network into a network address (such as an IP address).

Implementation

If a computer running Windows is configured as a P-node machine, it does not use broadcasts to resolve the names of the hosts. Instead, it tries to query a NetBIOS name server to resolve names of other hosts on the network. The advantage of doing this is that name resolution can function across large internetworks consisting of IP subnets connected with routers since routers normally block broadcasts but will forward packets directed toward a specific name server. An example of a NetBIOS name server on a Microsoft Windows network is a Windows NT, Windows 2000, or Windows .NET Server machine running the Windows Internet Name Service (WINS). If the WINS server is unavailable to the client issuing the query, the requested name cannot be resolved into its associated IP address. Furthermore, each client must be configured with the IP address of the WINS server in order for P-node name resolution to work. For this reason, M-node or H-node methods are usually preferred; they can use both broadcasts and directed traffic to resolve NetBIOS names of hosts.

See Also: *B-node, H-node, M-node, NetBIOS name resolution*

PnP

Stands for Plug and Play, a design philosophy and set of specifications for PC architectures that enables computer hardware, peripherals, device drivers, and operating systems to be easily reconfigured with minimal user understanding and intervention.

See: *Plug and Play (PnP)*

pointer (PTR) record

A resource record for reverse name resolution.

Overview

Pointer (PTR) records associate an Internet Protocol (IP) address with a host name in the in-addr.arpa domain. They are used for reverse name lookups to provide host name to IP address mappings.

Examples

Here is an example of a PTR record:

```
1.141.205.202.in-addr.arpa    IN    PTR
server9.microsoft.com.
```

In this PTR record, the IP address 202.205.141.1 is mapped to the host Server9 within the microsoft.com domain. Note that the host's IP address appears in the reverse order in the in-addr.arpa domain.

See Also: *Domain Name System (DNS), resource record (RR)*

point of presence (POP)

A carrier facility that provides an access point for telecommunication services.

Overview

The term *point of presence (POP)* generally refers to a data center to which users can connect in order to access dial-up, leased line, and other telecommunication services. The following can all be considered POPs:

- The central office (CO) for a telco
- The modem bank or switching facility at an Internet service provider (ISP)
- A metropolitan area exchange (MAE) or network access point (NAP) where several ISP backbones connect
- A base station for a cellular communication system

An ISP's POP, for example, would be a facility that housed call aggregators, modem banks, routers, and high-speed Asynchronous Transfer Mode (ATM) switches. Such a POP generally has one or more unique IP addresses plus a pool of assignable IP addresses for its permanent and dial-up clients. The actual POP for an ISP might be colocated within the telecommunications facility of a telco or a long-distance carrier. The ISP rents or leases space in the facility to install the routers and access servers that provide Internet connectivity for clients and for the equipment that provides the ISP with a high-speed T1 or T3 connection to the Internet's backbone.

See Also: *Asynchronous Transfer Mode (ATM), central office (CO), Internet, Internet service provider (ISP), Network Access Point (NAP)*

point-to-multipoint

Communication from a single sending station to multiple receiving stations.

Overview

A point-to-multipoint (or multipoint) wide area network (WAN) consists of three or more end nodes interconnected using a packet-switching telecommunications service. A number of Layer 2, or data-link layer, protocols support multipoint WANs, including frame relay, Switched Multimegabit Data Services (SMDS), Asynchronous Transfer Mode (ATM), and X.25 packet-switched networks.

The opposite of point-to-multipoint is point-to-point communications.



Point-to-multipoint. *Connecting LANs using a multipoint frame relay service.*

A public or private frame relay network can be used to connect multiple networks into a multipoint WAN configuration, as shown in the diagram. Each end node is configured with a unique data-link address, which allows any node on the WAN to communicate with any other node.

See Also: *Asynchronous Transfer Mode (ATM), frame relay, point-to-point, Switched Multimegabit Data Services (SMDS), wide area network (WAN), X.25*

point-to-point

Communication from a single sending station to a single receiving station.

Overview

A point-to-point connection may be a serial link, a dial-up modem connection, a leased line such as a T1 line, or an Integrated Services Digital Network (ISDN) connection. Consider a leased line, for example, which can be used to create a wide area network (WAN) by linking together two end nodes on different local area networks (LANs). In a typical configuration, a router is connected using a serial transmission interface such as V.35 to a Channel Service Unit (CSU) at the customer premises. The CSU provides the interface between the router and the telco's leased line. An identical setup is configured at the remote customer premises.



Point-to-point. *Implementing a point-to-point WAN connection.*

Such point-to-point WAN links typically use either High-level Data Link Control (HDLC) for synchronous connections using Cisco routers or Point-to-Point Protocol (PPP) for asynchronous or synchronous communications linking equipment from different vendors. PPP is usually used in heterogeneous networking environments in which the routing and access equipment comes from different vendors, and HDLC tends to be used in homogeneous networking environments in which the routers and access equipment run only Cisco Systems' Internetwork Operating System (IOS) software. One of the derivatives of these protocols, such as Point-to-Point Tunneling Protocol (PPTP), may also be used as the data-link layer protocol for encapsulating local network traffic into frames for transmission over the WAN link.

Note that because there are only two end nodes in a point-to-point WAN link, addressing need not be provided for the end nodes at the data-link layer.

The opposite of point-to-point is point-to-multipoint communications.

Notes

The term *point-to-point* is also used more generally. For example, the configuration of a terminal connected to a minicomputer using two short-haul asynchronous modems is referred to as a point-to-point connection.

See Also: *Channel Service Unit (CSU), data-link layer, High-level Data Link Control (HDLC), Integrated Services Digital Network (ISDN), Internetwork Operating System (IOS), leased line, point-to-multipoint, Point-to-Point Protocol (PPP), Point-to-Point Tunneling Protocol (PPTP), T-carrier, V.35*

Point-to-Point Protocol (PPP)

A popular wide area network (WAN) encapsulation protocol.

Overview

Point-to-Point Protocol (PPP) is an industry standard data-link layer protocol developed in the early 1990s in response to problems associated with Serial Line Internet Protocol (SLIP), which supported only static Internet Protocol (IP) addressing for clients. PPP is superior to the older SLIP in that it is much faster, it offers error correction and dynamic negotiation of sessions without user intervention, and it can support multiple network protocols simultaneously.

PPP provides reliable delivery of packets over both asynchronous and synchronous serial communications links. PPP works with a wide variety of network protocols by encapsulating and compressing them for efficient delivery over WAN connections. Because of its flexibility, PPP allows WAN devices from different vendors to interoperate.

PPP is also the basis of Point-to-Point Tunneling Protocol (PPTP) and Layer 2 Tunneling Protocol (L2TP), which can be used to create virtual private networks (VPNs). All versions of Microsoft Windows support PPP.

PPP is defined in RFCs 1661 and 1662.

Architecture

PPP encapsulation is based on the High-level Data Link Control (HDLC) derived from the mainframe environment. It supports a wide variety of network layer protocols, including IP, Internetwork Packet Exchange (IPX), NetBEUI, and AppleTalk. Once encapsulated, PPP frames can then be transmitted over serial transmission lines such as Public Switched Telephone Network (PSTN), Integrated Services Digital Network (ISDN), or over packet-switched networks such as X.25.

PPP includes two additional subprotocols:

- **Link Control Protocol (LCP):** This is an extensible protocol for establishing, tearing down, and testing data-link WAN connections.
- **Network Control Protocol (NCP):** This is a family of protocols used for establishing and configuring PPP communication using the different network protocols listed above.

PPP supports a wide range of authentication protocols, including

- Password Authentication Protocol (PAP)
- Challenge/Handshake Authentication Protocol (CHAP)
- Microsoft Challenge/Handshake Authentication Protocol (MS-CHAP)
- Shiva Password Authentication Protocol (SPAP)

Implementation

A typical dial-up session using PPP is completely automated and requires no real-time user input. It has four stages:

- **Link establishment:** PPP uses LCP to establish and maintain a PPP link over a serial transmission line. LCP frames are sent over the data link to test its integrity and establish the link.
- **User authentication:** PPP uses one of several authentication protocols, including PAP, CHAP, and Microsoft Challenge Handshake Authentication Protocol (MS-CHAP).
- **Callback:** PPP Callback Control (Microsoft's implementation of PPP) uses Callback Control Protocol (CBCP) if it is configured.
- **Configuration:** NCPs are used to establish network connections, perform compression and encryption, and lease IP addresses using Dynamic Host Configuration Protocol (DHCP), among other functions. NCP frames are sent over the link to establish a network connection between the PPP server and the remote PPP client.

Notes

If you can connect to a remote PPP server but you cannot ping the remote server, try turning off IP header compression. If that does not work, try logging all PPP communication and examining it later for troubleshooting purposes.

See Also: *asynchronous transmission, Challenge Handshake Authentication Protocol (CHAP), data-link layer, High-level Data Link Control (HDLC), Integrated Services Digital Network (ISDN), Internet Protocol (IP), Layer 2 Tunneling Protocol (L2TP), Link Control Protocol (LCP), Microsoft Challenge Handshake Authentication Protocol (MS-CHAP), Multilink Point-to-Point Protocol (MPPP), Network Control Protocol (NCP), Password Authentication Protocol (PAP), Point-to-Point Tunneling Protocol (PPTP), Public Switched Telephone Network (PSTN), Serial Line Internet Protocol (SLIP), serial transmission, synchronous transmission, wide area network (WAN), X.25*

Point-to-Point Tunneling Protocol (PPTP)

An encapsulation protocol for virtual private networking (VPN).

Overview

Point-to-Point Tunneling Protocol (PPTP) is a data-link layer protocol based on the Internet standard Point-to-Point Protocol (PPP). PPTP was developed by Microsoft Corporation to enable network traffic to be encapsulated and sent over an unsecured public Internet Protocol (IP) network such as the Internet. PPTP does this through the creation of virtual private networks (VPNs), which securely tunnel network traffic through the Internet. Remote users can use PPTP to securely access resources on their corporate network over the Internet instead of having to use direct modem connections or costly leased lines.

PPTP is defined in RFC 2637.

Architecture

PPTP is an extension of PPP that is based on standard PPP negotiation, authentication, and encryption schemes. PPTP can encapsulate any form of network traffic including IP, Internetwork Packet Exchange (IPX), or NetBIOS Enhanced User Interface (NetBEUI) packets, and then create a "tunnel" for secure communication across a wide area network (WAN) link. This tunnel is responsible for authentication and data encryption and makes it safe to transmit data over unsecured networks.

PPTP supports two types of tunneling:

- **Voluntary tunneling:** Initiated by the PPTP client, which includes all versions of Microsoft Windows. This type of tunneling does not require support from an Internet service provider (ISP) or network devices such as bridges.
- **Compulsory tunneling:** Initiated by the PPTP server on the corporate network or at the ISP. This type of tunneling must be supported by network access servers (NASs) or routers.

Notes

Because PPTP supports multiple network protocols, including IP, IPX, and NetBEUI, two computers can establish a tunnel over the Internet only if they are running the same network protocol. To troubleshoot PPTP over a TCP/IP connection, use ping to determine whether you are connected to your PPTP server. Also be sure that you have trusted credentials in the domain of the PPTP server, and be sure that you do not have an active Winsock Proxy client that might be redirecting PPTP packets to a proxy server instead of to your VPN.

See Also: *data-link layer, Internet Protocol (IP), Internetwork Packet Exchange (IPX), NetBIOS Extended User Interface (NetBEUI), Point-to-Point Protocol (PPP), tunneling, virtual private network (VPN), wide area network (WAN)*

polyvinyl chloride (PVC) cabling

A grade of network cabling that uses polyvinyl chloride (PVC) plastic for its outer protective insulating jacket.

Overview

PVC cabling is cheap and flexible but gives off dangerous gases during combustion. PVC cabling is usually used to connect wall plates to computers. Building codes usually require that plenum cabling be used instead of PVC cabling for horizontal runs from wiring closets to wall plates.

Both coaxial and twisted-pair cabling are generally available in either PVC or plenum-grade jackets.

See Also: *cabling, plenum cabling, premise cabling*

PON

Stands for passive optical network, a technology for bypassing the bottleneck of the local loop.

See: *passive optical network (PON)*

POP

Stands for point of presence, a carrier facility that provides an access point for telecommunications services.

See: *point of presence (POP)*

POP3

Stands for Post Office Protocol version 3, an Internet standard protocol for storing and retrieving e-mail.

See: *Post Office Protocol version 3 (POP3)*

port

An endpoint of a connection between two Internet Protocol (IP) hosts.

Overview

Ports identify the applications and services that use connections in Transmission Control Protocol/Internet Protocol (TCP/IP) networks. A port thus identifies a unique process for which a server can provide a service or by which a client can access a service. Ports are identified by two-byte numbers called port numbers and are classified as either TCP ports or User Datagram Protocol (UDP) ports, depending on the type of service being supported.

Notes

In computer terminology, the term *port* represents a connector for attaching cables or peripherals to the computer—for example, a parallel port for connecting a printer to a computer or a serial port for connecting a serial mouse or modem to a computer. Connectors on networking components, such hubs or routers, are also sometimes called ports, although a better term for such a connector on a router would be an *interface*.

See Also: *port number, Transmission Control Protocol (TCP), Transmission Control Protocol/Internet Protocol (TCP/IP), User Datagram Protocol (UDP)*

portal

A general name for a wide range of platforms and services ranging from Internet search engines to systems for managing corporate data.

Overview

The term *portal* means doorway and refers to any application or service that provides easy access to useful information or data. The term was first applied to public Web sites such as Yahoo! that provided visitors with a directory of useful and interesting sites on the Internet along with an associated search engine. Today such

Internet portals offer a much wider range of services, including instant messaging, managing personal contacts and calendars, online shopping and bill payment, customized information about your local news, sports, and weather, and customized personal pages. A number of Internet portals exist, but the "big three" are MSN, Yahoo!, and America Online (AOL).

In the enterprise arena, the portal concept evolved from the earlier concept of intranets, or internal corporate Web sites. Enterprise portals focus more on knowledge management (KM), which deals with making readily available all the various sources of knowledge in an enterprise. Several kinds of enterprise portals have evolved in the last few years, including

- **Enterprise Information Portal (EIP):** Provides front-end access to business data stored in different applications and repositories
- **Enterprise Knowledge Portal (EKP):** Includes functionality of EIPs and provides virtual workspaces for collaboration and file sharing

Marketplace

Some examples of popular portal products for the enterprise include Brio.Portal from Brio Technology, Corporate Portal from Plumtree Software, DataChannel Server from DataChannel, Epicentric Portal Server from Epicentric, Decision Portal from InfoImage, iPlanet Portal Server from Sun-Netscape Alliance, Oracle9iAS from Oracle Corporation, SharePoint Portal Server from Microsoft Corporation, and many others.

See Also: *Enterprise Information Portal (EIP), Enterprise Knowledge Portal (EKP), intranet, knowledge management (KM)*

port number

A 16-bit (2-byte) positive integer used to identify a port on a Transmission Control Protocol/Internet Protocol (TCP/IP) network.

Overview

Ports can be assigned numbers ranging from 0 to 65,536. The number assigned to a port identifies the network service or process supported by the port. For example, the File Transfer Protocol (FTP) uses TCP port 20 for transferring data and port 21 for sending control messages. Transmission Control Protocol (TCP) and User Datagram Protocol (UDP) ports are considered distinct.

There are three main types of ports according to their numbering:

- **Well-known ports:** These originally ranged from 0 to 255 but were later expanded to cover 0 through 1023. Well-known port numbers always represent the same network services and are assigned by the Internet Assigned Numbers Authority (IANA). Some of these numbers are currently unassigned and are reserved for future use. For example, FTP uses the well-known port numbers 20 and 21 as discussed above. For a list of well-known port numbers see the article "well-known port numbers" elsewhere in this book.
- **Registered ports:** These are ports used by different vendors to support their operating systems and applications. Registered ports are acknowledged and listed by IANA but are not considered permanently allocated, so other vendors may use the same port numbers provided they anticipate no interoperability issues. Registered ports range from 1024 through 49,151 and overlap with the numbers of dynamically assigned ports below. Examples of registered ports on the Microsoft Windows platform include TCP/UDP port 1512 for the Windows Internet Name Service (WINS) and UDP port 2504 for the Network Load Balancing service.
- **Dynamically assigned ports:** These are ports that an operating system or application assigns to service client requests as needed. Dynamic ports are allocated from the range 1024 through 65,536 and can be released and reassigned as needed.

See Also: *Internet Assigned Numbers Authority (IANA), port, Transmission Control Protocol (TCP), Transmission Control Protocol/Internet Protocol (TCP/IP), User Datagram Protocol (UDP), well-known port numbers*

POSIX

A set of standards for cross-platform implementations of UNIX.

Overview

POSIX is a standard UNIX operating system interface and environment developed by the Institute of Electrical and Electronics Engineers (IEEE) that supports portability of applications at the source code level. POSIX arose because different vendors were producing different "flavors" of UNIX and code written for one flavor would not run on another unless it was modified appropriately. The solution was to develop a standard in which code could be portable between all UNIX flavors, so that a POSIX call in one program would work on any other POSIX-compliant system.

Because of vendor-specific enhancements most UNIX systems are not 100 percent POSIX-compliant. The POSIX.1 standard defines the portability of C language code by specifying a standard application programming interface (API). Microsoft Windows NT, Windows 2000, and the 32-bit versions of Windows XP and Windows .NET Server are fully compliant with the POSIX.1 standard, which means that their POSIX subsystem can run native C language code written to the POSIX.1 standard. Windows NT does not support other POSIX standards.

POSIX Standards

Standard	*Description*
POSIX.1	Specifies the base system interfaces for C language programming
POSIX.2	Specifies standards for shells and system utilities plus additional C language interfaces
POSIX.3	Specifies methods for testing conformance to POSIX
POSIX.4	Adds real-time extensions to POSIX.1
POSIX.5	Extends POSIX.1 to the Ada programming language
POSIX.9	Extends POSIX.1 to the FORTRAN77 language

Notes

Note that POSIX originally stood for Portable Operating System Interface for UNIX, but no one actually refers to it this way anymore.

See Also: *UNIX*

POST

Stands for power-on self test, a special set of initialization routines stored in read-only memory (ROM) that run whenever a PC is booted.

See: *power-on self test (POST)*

postoffice

The central message store in a legacy Microsoft Mail messaging system.

Overview

The postoffice consists of a series of message storage directories on the Microsoft Mail file server. The postoffice stores information such as user ID, password, user preferences, message folders, mail messages, and attachments. The postoffice is a passive file system; no active software runs on it. The International Telecommunication Union (ITU) refers to this component of a mail system as the "message store."

See Also: *e-mail, International Telecommunication Union (ITU)*

Post Office Protocol version 3 (POP3)

An Internet standard protocol for storing and retrieving e-mail.

Overview

Simple Mail Transfer Protocol (SMTP) provides the underlying transport mechanism for sending e-mail messages over the Internet, but it does not provide any facility for storing and retrieving messages. SMTP hosts must be continuously connected to one another, but most users do not have a dedicated connection to the Internet.

Post Office Protocol version 3 (POP3) solves this problem by providing mechanisms for storing messages sent to each user and received from SMTP hosts in a receptacle called a mailbox. A POP3 server such as Microsoft Exchange Server stores messages for each user until the user connects to download and read them using a POP3 client such as Microsoft Outlook. After a POP3 client reads a message in the user's mailbox on a POP3 server, the message is deleted from the mailbox on the server. Primarily for this reason, POP3 is slowly giving way to a newer protocol called Internet Mail Access Protocol version 4 (IMAP4), which can retain read mail on the server and thus offers better support for mobile users.

Implementation

To retrieve a message from a POP3 server, a POP3 client establishes a Transmission Control Protocol (TCP) session using TCP port 110, identifies itself to the server, and then issues a series of POP3 commands:

- **Stat:** Asks the server for the number of messages waiting to be retrieved
- **List:** Determines the size of each message to be retrieved
- **Retr:** Retrieves individual messages
- **Quit:** Ends the POP3 session

To troubleshoot problems with remote POP3 servers, use Telnet to connect to port 110 and examine the results as you try issuing various POP3 commands such as the ones just described.

See Also: *e-mail, Internet Mail Access Protocol version 4 (IMAP4), port number, Simple Mail Transfer Protocol (SMTP), Telnet, Transmission Control Protocol (TCP)*

POTS

Stands for Plain Old Telephone Service, the basic analog telecommunications service provided by a local telco.

See: *Plain Old Telephone Service (POTS)*

power-on self test (POST)

A special set of initialization routines stored in read-only memory (ROM) that run whenever a PC is booted.

Overview

The power-on self test (POST) is designed to test whether system components are functioning properly before attempting to boot the operating system, and checks such things as the RAM, keyboard, and disk drives. If a problem is detected during the POST, the system typically emits a series of beeps and displays a corresponding error message giving some indication of the problem. Specific problems are indicated by different numbers of beeps, but the interpretation of these varies depending on the BIOS used.

On Pentium III systems that use the popular AMI WinBIOS, use the following table to interpret the number of beeps in order to troubleshoot the problem.

POST Beep Codes for AMI WinBIOS

Number of Beeps	*Problem*	*Resolution*
1, 2, or 3	Memory error	Check speed and voltage of dual inline memory modules (DIMMs), try reseating DIMMs, or replace DIMMs
4	Timer error	Replace motherboard
5	CPU error	Try replacing CPU, or replace motherboard
6	Gate A20 error	Try reseating keyboard controller chip, try replacing keyboard controller chip, or replace motherboard
7	Interrupt error	Replace motherboard
8	Video memory error	Try reseating the video RAM (VRAM), try replacing the VRAM, or replace video card
9	BIOS ROM error	Replace BIOS ROM chip

Power Users group

A built-in group in Microsoft Windows 2000, Windows NT 4, Windows XP, and Windows .NET Server.

Overview

The Power Users group is a local group that exists only on stand-alone servers and client machines. The initial membership of this group is empty. Generally speaking, a power user is a person who is familiar with the advanced features of a program's user interface.

The Power Users group has preassigned rights including the following:

- Log on locally
- Access this computer from the network
- Change the system time
- Shut down the system

Power users also have the right to share and manage local disk resources and printers and to create and modify local user accounts on the local machine.

See Also: *built-in group*

PPP

Stands for Point-to-Point Protocol, a popular wide area networking (WAN) encapsulation protocol.

See: *Point-to-Point Protocol (PPP)*

PPP Multilink

Another name for Multilink Point-to-Point Protocol, a wide area network (WAN) protocol for aggregating multiple Point-to-Point Protocol (PPP) connections.

See: *Multilink Point-to-Point Protocol (MPPP)*

PPTP

Stands for Point-to-Point Tunneling Protocol, an encapsulation protocol for virtual private networking (VPN).

See: *Point-to-Point Tunneling Protocol (PPTP)*

Practical Extraction and Reporting Language (Perl)

An interpreted scripting language used for Web applications.

Overview

Practical Extraction and Reporting Language (Perl) is often used on UNIX platforms to develop Common Gateway Interface (CGI) programs to add dynamic functionality to Web sites—for example, input handlers for Hypertext Markup Language (HTML) forms on Web sites running on Apache web servers. Perl's unique capabilities revolve mainly around its powerful string manipulation capabilities. However, because Perl is an interpreted scripting language, applications that are written in Perl are easy to develop and test but tend to run more slowly than if they were compiled programs written in C or some other high-level programming language.

The current version of Perl is version 6.

Notes

You can use Microsoft Corporation's Windows Script Host (WSH) to run administrative scripts written in Perl by installing a third-party ActiveX scripting engine for Perl. Administrators from UNIX backgrounds can do this to leverage their knowledge of Perl to administer Microsoft Windows 2000.

For More Information

Find out more about Perl at *www.perl.com.*

See Also: *Apache, Common Gateway Interface (CGI), Hypertext Markup Language (HTML), scripting, UNIX, Windows Script Host (WSH)*

premise cabling

The entire wiring system in a building.

Overview

Premise wiring for a building includes the cabling, power lines, wiring closets, distribution centers, wall plates, and fixtures needed to build out a wiring infrastructure. Premise cabling should be installed according to the Electronic Industries Alliance and Telecommunications Industry Association (EIA/TIA) wiring standards and must comply with all state and municipal building codes and requirements.

Implementation

In most computer networking installations today, the premise wiring system is a hierarchical system based on the star topology, starting with the equipment room (main cross-connect) that houses the main telecommunications equipment for the particular building, including servers, Private Branch Exchanges (PBXs), and routers. The equipment room contains the facilities for telecommunications signals to enter and leave the building. It can be one room or several rooms on different floors, depending on the building layout and administrative considerations.

From the equipment room, a vertical backbone cable runs up the building riser or elevator shaft, connecting the equipment room with wiring closets (intermediate cross-connects) on each floor. Additional backbone cabling runs horizontally to secondary wiring closets (horizontal cross-connects) if necessary. No further cross-connects should be used; in other words, the hierarchy should be no more than three cross-connects deep.

The wiring closets contain cabinets or racks with patch panels and a variety of networking equipment such as hubs, switches, and routers. Horizontal wiring runs from the patch panels through wall and ceiling spaces to wall plates and distribution boxes to form local area network (LAN) drops in the work areas where computers are set up. Patch cables or drop cables then connect computers in the work area to the wall plates or other distribution boxes.

See Also: *cabinet, cabling, infrastructure, patch cable, patch panel, rack, star topology, structured wiring, wall plate, wiring closet*

presentation layer

Layer 6 of the seven-layer Open Systems Interconnection (OSI) reference model.

Overview

The presentation layer structures data that is passed down from the application layer into a format suitable for network transmission. This layer is responsible for data encryption, data compression, character set conversion, interpretation of graphics commands, and other functions. The network redirector also functions at this layer.

Transmission Control Protocol/Internet Protocol (TCP/IP) and other common network protocols do not use a separate presentation layer protocol. The presentation layer is thus an abstraction in real-world networking.

See Also: *Open Systems Interconnection (OSI) reference model*

Pretty Good Privacy (PGP)

A popular scheme for encrypting e-mail for secure messaging.

Overview

Pretty Good Privacy (PGP) is a digital signature and encryption scheme developed by Phil Zimmermann in 1991 for secure exchange of e-mail and attached documents. You can use Pretty Good Privacy (PGP) to encrypt e-mail messages so that no one but the intended recipient can read them and to digitally sign messages so that the recipient can be sure of the identity of the sender and that the message has not been tampered with during transit.

Implementation

PGP generally uses the Rivest-Shamir-Adleman (RSA) or Diffie-Hellman public key cryptography algorithm and supports 128-bit keys. When you send a digital signature, a hashing algorithm generates a hash from the username and other information, which is then encrypted using the sender's private key. The hashing algorithm is MD5 when you use RSA and SHA-1 when you use Diffie-Hellman. As in a typical public key cryptography system, the recipient uses the sender's public key to decrypt the signature and verify the sender's identity. The sender's public key is retrieved by the recipient from a public PGP key management server such as the one maintained by certificate servers at Network Associates Technology.

Prospects

PGP is popular in the Internet community but does not scale well for corporate enterprise applications because its key management facilities are implemented as a distributed “web of trust” rather than the usual hierarchical certificate authority (CA) scheme of a traditional public key infrastructure (PKI) needed for Privacy Enhanced Mail (PEM). However, the complexity and cost of rolling out a large-scale PKI has turned many enterprises away from this technology in search of simpler and cheaper schemes such as PGP, so the outlook for PGP in the enterprise still remains to be seen.

In 1997, Zimmermann sold the rights to PGP technology to NAI, which currently offers both a commercial version and a freeware version to customers. NAI also provides the necessary PKI infrastructure and CA for free PGP users, which currently number more than a million. Zimmerman, meanwhile, has joined Hush Communications in developing encryption software based on the Open PGP standard from the Internet Engineering Task Force (IETF). In contrast to traditional PGP that requires special software to be installed on each client, the new version from Hush delivers the private key for authenticated user using a Java applet running in the user’s Web browser. This allows PGP to be used on machines without dedicated PGP client software installed, an advantage for mobile users.

For More Information

You can get PGP at *www.nai.com*.

See Also: *certificate authority (CA), e-mail, encryption, Privacy Enhanced Mail (PEM), public key infrastructure (PKI)*

PRI-ISDN

Stands for Primary Rate Interface ISDN, a high-speed version of Integrated Services Digital Network (ISDN).

See: *Primary Rate Interface ISDN (PRI-ISDN)*

primary domain controller (PDC)

A Microsoft Windows NT domain controller that contains the master copy of the SAM database.

Overview

A Windows NT domain has one primary domain controller (PDC), which periodically undergoes directory synchronization to copy its directory database to back up domain controllers in the domain. The primary domain controller (PDC) must be the first computer installed in a domain and defines the domain. The PDC contains the master copy of the SAM database, but backup domain controllers (BDCs) contain read-only versions of this database.

If a PDC needs to be taken offline for maintenance or repair or if it unexpectedly goes down, a BDC can be promoted to the role of PDC. This is necessary because BDCs contain read-only copies of the domain directory database, so user accounts cannot be modified and passwords cannot be changed unless there is a PDC on the network.

See Also: *backup domain controller (BDC), domain controller, SAM database*

primary name server

A name server that maintains its own local database of resource records.

Overview

A primary name server has a master copy of resource records for each zone over which it has authority. In the Berkeley Internet Name Domain (BIND) implementation of DNS, these resource records are stored locally on the name server in the form of a text file called the zone file. All changes to the resource records for a zone must be made on the primary name server.

Secondary name servers obtain their resource records from master name servers, which can be either primary name servers or other secondary name servers. The usual configuration when name servers are used within a Transmission Control Protocol/Internet Protocol (TCP/IP) internetwork for name resolution is one primary and one secondary name server, with the primary configured as the master name server for the secondary, which is sometimes called the slave name server.

See Also: *Domain Name System (DNS), master name server, name server, secondary name server, zone*

primary partition

A disk partition on which a bootable operating system can be installed.

Overview

Primary partitions cannot be subdivided into further segments, as extended partitions can. The partition table on a drive's master boot record can contain entries for up to four primary partitions or three primary and one extended partition. Only one primary partition at a time can be the active partition (contain the currently running operating system files). In Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server, the active partition is sometimes known as the system partition.

Primary partitions can also be used in multiboot systems to isolate the files of each operating system from one another.

See Also: *extended partition*

Primary Rate Interface ISDN (PRI-ISDN)

A high-speed version of Integrated Services Digital Network (ISDN).

Overview

In the United States and Japan, a Primary Rate Interface ISDN (PRI-ISDN) connection consists of 24 digital channels that are divided between 23 B channels and a single D channel. This flavor of PRI-ISDN is often referred to as 23B+D because of the types and numbers of channels that it uses. The B channels carry the voice or data between the customer premises and the telco's central office (CO), while the D channel is used for establishing and tearing down connections and for signaling. The bandwidth of each B channel and of the single D channel is 64 kilobits per second (Kbps), so the total bandwidth of PRI-ISDN is 1.544 megabits per second (Mbps), which is identical to that of a T1 circuit. By using the BONDING protocol, the 23 B channels can be combined to form a single 1.472-Mbps data channel.

The other flavor of PRI-ISDN, the European version, employs 30 B channels and one D channel, in other words 30B+D. The bandwidth of an E1 circuit is greater at 2.048 Mbps.

See Also: *Basic Rate Interface ISDN (BRI-ISDN), Integrated Services Digital Network (ISDN), T-carrier*

primary ring

The main ring used in the dual ring topology of a Fiber Distributed Data Interface (FDDI) network.

Overview

The primary ring is the only ring used unless it has a fault, in which case the network reconfigures itself to use the secondary ring with the data traveling in the opposite direction. This dual ring configuration provides FDDI with fault tolerance. It is usually a good idea to run the primary and secondary rings along different physical paths to make the FDDI network more fault-tolerant. An accident or disaster affecting one of the rings will thus not affect the other.

See Also: *fault tolerance, Fiber Distributed Data Interface (FDDI), secondary ring*

printing pool

A technique used to connect one printer to multiple print devices.

Overview

In Microsoft Windows printing terminology, a print device is the physical hardware that does the printing, but a printer is a software interface on a computer that enables jobs to be sent to a print device. Normally, a separate printer is configured for each individual print device. Using a printing pool, however, you can identify several print devices as a single printer to the operating system. Then, when a client sends a print job to the pool, the printer sends the job to the first available print device managed by the printer. Clients can thus print jobs without having to check to see which print device is actually free.

Printing pools are typically used in networks with high printing volume and are also used to provide a form of fault tolerance. Printing pools also simplify the administration of large numbers of print devices. Print devices that are pooled can, however, be a mix of local and network interface print devices. Note that the print devices in a printing pool must be the same make and model or at least be similar devices that use the same printer driver. If you do not have identical print devices and thus cannot create a printing pool, you can take other measures to meet the needs of increased printing volume:

- Share an existing printer that is currently not shared for network use
- Configure priorities between printers to enable critical documents to be printed before noncritical ones
- Institute company policies on how to use printers properly and audit printer usage

Be sure to place pooled print devices in close physical proximity to one another so that users do not have to search for the device that printed their job.

See Also: *printing terminology*

printing terminology

Terminology used to describe different aspects of printing.

Overview

In Microsoft Windows networking, the following are some important printing-related terms that administrators should know:

- **Print device:** A hardware device that produces printed output, such as a LaserJet, ink-jet, or dot-matrix print device. Most people loosely refer to these devices as printers, but the term *printer* has a specific meaning in the Windows operating system, as described below.
- **Printer:** A software interface on a Windows computer that allows users and applications to print to a print device. Microsoft uses the term *print device* to refer to the actual hardware device; *printer* refers to the software interface that controls that device. To create a printer, you use the Add Printer Wizard in the Printers folder.
- **Print server:** A computer with which a print device is associated. A print server receives print jobs from clients and sends them to the print device.
- **Printer driver:** A series of files that convert printing commands into machine-specific language for sending them to a print device. Each model and make of print device has its own specific printer driver.

In Microsoft Windows, print devices can be further subdivided into two types:

- **Local print device:** A print device that is locally attached to the parallel or serial port on the print server. If a local print device is being used only on the local machine, its software interface is called a local printer. If a local print device is shared, clients can access it over the network and its software interface is called a network printer from the clients’ perspective.
- **Network-interface print device:** A print device that has its own built-in network interface card (NIC) and can be plugged into the network anywhere that a local area network (LAN) drop is free. A network-interface print device is not connected directly to the print server; it is managed remotely by the print server.

Notes

Keep network-interface print devices on the same network or subnet as their print server to minimize the extra network traffic. Be sure that your print server has sufficient RAM (random access memory) for processing documents and sufficient disk space for spooling print jobs. Dedicating a computer to the role of print server is usually recommended, especially if that computer will manage several print devices.

Print Operators group

A built-in group in Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Overview

Print operators are users who can administer network printers. The Print Operators group is a domain local group whose initial membership is empty. This group has the following preassigned rights:

- Log on locally
- Shut down the system

Print operators also have the right to set up and configure network printers.

See Also: *built-in group*

print permissions

A set of permissions assigned to users and groups to control access to the printers on a Microsoft Windows print server.

Overview

Suitable print permissions are an important part of network administration, especially in enterprise-level networks with different administrative levels. There are four levels of print permissions in Windows, as described in the following table. You can permit or deny any of these permissions, and by clicking the Advanced button on the Printer Properties property page you can configure more granular customized sets of printer permissions if you like.

Print Permissions

Permission	***What It Allows Users To Do***
print	Connect to a printer Print a document Manage your own documents only
manage documents	Print permissions plus: Pause and restart any document Delete any document Manage job settings for all documents
manage printers	Manage documents permissions plus: Share a printer Change printer properties Delete a printer Change printer permissions

Notes

In Windows 2000, you can remotely administer printers over the Internet using a Web browser by accessing the following Uniform Resource Locator (URL):

```
http://Print_Server_Name/printers
```

Administrators can use this feature to configure printer permissions and settings, check the status of printers, and create real-time reports on printer usage.

See Also: *printing terminology, print server, Uniform Resource Locator (URL)*

print server

A server that manages a printer on a network.

Overview

A printer can either be directly connected to a port on the print server (called a local printer), or it can have its own built-in network interface card (NIC) and be connected directly to the network (called a network printer). Clients that want to print jobs send them to the print server, which queues or spools the jobs and then sends them to the printer.

Implementation

To deploy a print server on your network, you can use a Microsoft Windows 2000 or Windows .NET Server machine and configure it to be your print server. Alternatively, instead of dedicating a computer to managing a printer on a network, you can use a stand-alone print server device. These devices generally have a small footprint—some are even pocket-sized—and can be used to attach a printer anywhere in the network. Typically, an RJ-45 port on the device can be plugged directly into an Ethernet hub or into a wall plate in a work area, while an IEEE 1284 port on the device is connected to the printer. Stand-alone print server devices generally have built-in support for a variety of protocols (such as Transmission Control Protocol/ Internet Protocol [TCP/IP], Internetwork Packet Exchange/Sequenced Packet Exchange [IPX/SPX], NetBIOS Enhanced User Interface [NetBEUI], and Data Link Control) and platforms (such as Windows 2000, Windows XP, Novell NetWare, and UNIX) and support a wide variety of makes and models of printers. Other features of stand-alone print server devices can include the following:

- Support for two or four parallel printer connections
- Support for Line Printer Daemon/Line Printer Remote (LPD/LPR) or Dynamic Host Configuration Protocol (DHCP)
- Support for Token Ring or AppleTalk networking architectures

See Also: *network interface card (NIC), printing terminology*

print sharer

Any hardware device that enables two or more computers to directly share one or more attached printers without using a network.

Overview

Print sharers are basically just switches and include the following types:

- **Manual switch boxes:** Here the user turns a rotary switch to select which computer controls the printer. The manual switch boxes are usually in a 2-to-1, 4-to-1, or 6-to-1 configuration. A special switch called an X-switch can allow either of two computers to print to either of two printers. Do not use manual switch boxes with laser printers, as the switching mechanism can cause voltage spikes that can seriously damage the printer.
- **Electronic print-sharing switches:** Here the user uses knobs or toggle switches to select a computer or printer. These switches have solid-state circuitry inside that performs the switching, unlike manual switch boxes, which have simple metallic contacts.
- **Port-contention or FIFO (first in, first out) switches:** These switches automatically monitor all input ports. When a signal enters an input port from a computer, the switch automatically assigns that port to the output printer port.
- **Code-operated switches:** These switches examine the input (computer) data ports for an ASCII string indicating which output (printer) port to switch the incoming printer data to.
- **Scanning switches:** These switches function like port-contention switches except that they sequentially scan the input ports instead of monitoring them all continuously.

Notes

If more than two computers need to share a printer, the best solution is to connect the computers to a local area network (LAN) and use a print server to set up a shared network printer. The print sharing devices listed previously are intended primarily for nonnetworked computers that must be directly connected to printers. In a small peer-to-peer networking setting, you can use a machine running Microsoft Windows XP. In larger networks, Windows 2000 or Windows .NET Server is a better choice.

See Also: *printing terminology, print server*

privacy

The concept that personal or business information should not be shared or accessed without authorization.

Overview

With the emergence of online shopping and business-to-business (B2B) e-commerce in the last few years, privacy has become a critical concern for both consumers and businesses. Privacy involves both ethical and legal issues, and building and maintaining trust is fundamental to its success.

Privacy in the United States generally uses the honor system, although the Federal Trade Commission (FTC) is beginning to establish itself as the privacy defender in the consumer arena. By contrast, the issue of employee privacy in corporations is basically an issue dealt with by state law. Corporations generally issue privacy policies to employees and customers, and many companies practice some form of online monitoring to ensure that employees are not misusing company resources. Examples of such monitoring including logging Web traffic and keeping copies of all e-mails sent and received. In the consumer arena, e-commerce companies sometimes sell customer information to other companies or use it for marketing purposes. Ideally, the privacy policy on the site should explain what the site does with your information and help you decide whether you will do business with the site.

The privacy situation in Europe is generally much stricter, and generally business cannot share a customer's personal information with a third party without the customer's explicit consent. This difference in privacy law can have a significant effect for large enterprises spanning the globe—solutions either involve adopting a strictest common denominator or partitioning company information.

Several independent organizations issue privacy compliance certifications, a popular one being eTrust. Another important development in the area of ensuring online privacy is the emergence of the Platform for Privacy Preferences (P3P), a standard specifying how Web sites communicate their privacy policy to visitors that is being developed by the World Wide Web Consortium (W3C) and is supported by major companies such as Microsoft Corporation, IBM, and America Online (AOL).

Notes

Before you shop online at an e-commerce Web site, be sure to read the privacy policy posted on the site (if you can find it!). Look for a seal from a privacy organization such as eTrust, and be sure not to use things such as your mother's birth name for privacy questions, such as those asked by your credit cards and bank. You should also make sure when making a purchase that the site is secure by looking for https:// in your browser's address field. You might also want to disable cookies on your browser if you are concerned about sites tracking your visits and spending habits, but be aware that this can affect your ability to access certain kinds of sites, such as e-commerce sites.

See Also: *B2B, cookie, e-business, network security, Platform for Privacy Preferences (P3P), World Wide Web Consortium (W3C)*

Privacy Enhanced Mail (PEM)

A specification for encrypting and securing e-mail.

Overview

Privacy Enhanced Mail (PEM) was developed by the Internet Engineering Task Force (IETF) as a standard method for encrypting e-mail messages and protecting their authenticity and integrity. PEM needs to be implemented only on the sending and receiving hosts and does not require any modification of the Internet's Simple Mail Transfer Protocol (SMTP) mail forwarding hosts.

PEM can work with a variety of encryption algorithms including

- MD2 and MD5 for message digests
- Data Encryption Standard (DES) for secret keys
- Rivest-Shamir-Adleman (RSA) for public keys

PEM is documented in RFCs 1421 through 1424.

Implementation

PEM modifies plain text SMTP e-mail messages by converting portions of the message to unintelligible blocks of ASCII code. Three different types of PEM blocks can be included in a message:

- **MIC-CLEAR:** PEM adds an integrity check block to the message but does not encrypt the message.
- **MIC-ONLY:** PEM first encrypts the message and then adds an integrity check.
- **ENCRYPTED:** PEM adds an integrity check to the message and then encrypts the message and the added block.

Issues

Although PEM can be used with either symmetric (secret) key cryptography or public key cryptography, it is mainly intended for use with public key cryptography and therefore requires a public key infrastructure (PKI) to be established before it can effectively be used. This has been the major stumbling block hindering the widespread adoption of PEM, since PKIs have been slow to emerge in the public arena. It has also given room for other schemes such as Pretty Good Privacy (PGP) to emerge and become popular in the market.

See Also: *cryptography, encryption, hashing algorithm, Internet Engineering Task Force (IETF), Pretty Good Privacy (PGP), public key cryptography, public key infrastructure (PKI), Simple Mail Transfer Protocol (SMTP)*

Private Branch Exchange (PBX)

A telephone switch at the customer premises that supports multiple independent telephone extensions.

Overview

Private Branch Exchanges (PBXs) can save businesses the cost of supplying an individual local loop connection for each employee because employees can share external trunk line connections. The PBX provides connectivity between the client's private telephone system that it supports and the telco's public trunk lines. In Europe a PBX is known as a Private Automatic Branch Exchange (PABX).

PBXs were originally switch consoles controlled by human operators, who would plug and unplug patch cords to establish connections for customers. The modern electronic PBX (also known simply as a switch) is a solid-state device that essentially establishes a private switching system that mimics the functions of a telco's much larger central office (CO) switching facility. PBXs allow businesses to have better control of their own telecommunications equipment, and they reduce costs by more effectively routing local telephone traffic.

PBXs support a number of features, including the following:

- **Direct Inward Dialing (DID):** A form of call routing that allows outside users to dial directly to any of the extensions
- **Direct Outward Dialing (DOD):** A form of call routing that allows extensions to dial directly to any outside phone number
- **Station-to-Station Dialing (SSD):** Allows any extension to call any other extension without using a business line

Most modern PBXs support digital phone extensions and T1 or multirate Integrated Services Digital Network (ISDN) for their telco connection and can handle data, fax, and other forms of traffic in addition to voice traffic. PBX boards can also be installed in servers to support computer-telephony integration (CTI). Many products and configurations are available.

Implementation

Typically, a telco or other service provider leases and installs a PBX in the main equipment room of a building or campus. The PBX handles all calls initiated and received in the building. If an outgoing call is directed to another line on the PBX, the PBX routes the call directly to its destination instead of forwarding it to the local CO. Outgoing calls directed to destinations outside the PBX are routed to the CO for handling.



Private Branch Exchange (PBX). *Connecting customer premises equipment to a PBX.*

Telephones and other devices are connected by individual circuits directly to the PBX unit, and trunk lines coming in from the outside terminate at a multitrunk channel band (MCB) unit. The MCB interfaces with the main distribution frame (MDF), which provides the individual circuits that connect the outside world to the PBX unit. The more circuits that the MDF creates from the trunk lines, the more simultaneous outgoing calls can be initiated and received by users of the PBX system. Add-ons for the PBX unit can include call management systems (CMSs), which provide call notification and control services; call accounting services; and modem pools for remote dial-up access.

PBX switches come in various sizes. The smallest is a 3-by-8 switch that supports three business lines and eight extension lines. This configuration permits eight phones to be connected, but only three of them can make or receive calls at a time.

Prospects

The traditional PBX is generally expensive and proprietary. An alternative that is rapidly growing in popularity is the IP PBX, a PBX that uses a packet-switched Internet Protocol (IP) network as its transport instead of traditional circuit-switched telephone lines. IP PBXs are particularly useful for companies that need to support mobile knowledge workers or telecommuters, as they are more flexible and manageable than traditional PBXs. Some analysts predict the IP PBX market will pass the traditional PBX market in 2005.

Notes

An alternative to installing a PBX at the customer premises is to lease a Centrex service from the telco’s CO. This service offers similar features to a PBX but from a remote location, and it is managed remotely by the telco.

See Also: *central office (CO), telco*

Private Communication Technology (PCT)

An encryption protocol similar to Secure Sockets Layer (SSL).

Overview

Private Communication Technology (PCT) is a security technology that was developed by Microsoft Corporation in response to certain weaknesses in version 2 of the SSL protocol. These issues were solved in version 3 of SSL and in its cousin, Transport Layer Security (TLS). As a result, PCT is now considered a legacy protocol and should generally not be used for securing transmissions over the Internet.

See Also: *encryption, Secure Sockets Layer (SSL), Transport Layer Security (TLS)*

private IP address

An Internet Protocol (IP) network ID that can be reused for different networks.

Overview

Because the pool of available IP addresses began to become exhausted in the 1990s, the Internet Engineering Task Force (IETF) came up with a way of reusing certain addresses. They designated three blocks of IP addresses for private use. In other words, any company can use any of these addresses for internal networking purposes. The caveat is that these addresses are not routable to the Internet and networks using them need to use network address translation (NAT) to establish connectivity with the Internet.

The three blocks of private IP addresses specified in FRC 1918 include

- 16,777,216 unique Class A addresses in the range 10.0.0.0 through 10.255.255.255
- 1,1048,576 unique Class B addresses in the range 172.16.0.0 through 172.31.255.255
- 65,536 unique Class C addresses in the range 192.168.0.0 through 192.168.255.255

See Also: *Class A, Class B, Class C, Internet Engineering Task Force (IETF), Internet Protocol (IP), IP address, network address translation (NAT)*

Project 802

An ongoing project of the Institute of Electrical and Electronics Engineers (IEEE) for defining local area network (LAN) and wide area network (WAN) standards and technologies.

Overview

The 802 specifications define the operation of the physical network components—cabling, network adapters, and connectivity devices such as hubs and switches. The Project 802 standards are constantly evolving, and new subcategories are being created to standardize new networking technologies.

Project 802 has a number of subsections, including the following:

- **802.1:** Internetworking standards
- **802.2:** The logical link control (LLC) layer of the Open Systems Interconnection (OSI) reference model data-link layer
- **802.3:** Ethernet (Carrier Sense Multiple Access with Collision Detection)
- **802.4:** Token Bus LAN
- **802.5:** Token Ring LAN
- **802.6:** Metropolitan area network (MAN)
- **802.7:** Broadband technologies
- **802.8:** Fiber-optic technologies
- **802.9:** Integrated voice/data networks
- **802.10:** Network security standards and technologies
- **802.11:** Wireless networking technologies and standards
- **802.12:** Demand priority access technologies
- **802.14:** Cable television access
- **802.15**: Wireless Personal Area Network (WPAN)
- **802.16**: Fixed broadband wireless networking
- **802.17**: Resilient Packet Ring (RPR)

See Also: *802.1, 802.2, 802.3, 802.4, 802.5, 802.6, 802.7, 802.8, 802.9, 802.10, 802.11, 802.12, 802.14, 802.15, 802.16, 802.17, Institute of Electrical and Electronics Engineers (IEEE), local area network (LAN), wide area network (WAN)*

promiscuous mode

A mode in which a network device listens to all traffic present on the local segment.

Overview

Devices such as network interface cards (NICs) typically listen only to traffic that is specifically addressed to the card and to broadcast traffic directed to every host. This is done to improve the card's performance, for if it had to process every frame or packet that arrived, the overhead could be great enough to cause errors or saturate the NIC.

Some NICs can be configured to operate in promiscuous mode, a mode of operation in which the NIC accepts all frames on the wire, including those not specifically directed to it. A NIC operating in promiscuous mode reads every frame it receives, whether the frames are broadcast, multicast, or unicast. In some networks, this can be a security problem because nodes that act "promiscuously" can be configured not only to read frames but also to store them and even retransmit them. Sensitive information can thus be intercepted on the network and retransmitted to remote stations. This problem can occur in both Ethernet and Token Ring networks when NICs are configured to act promiscuously.

Sometimes, however, a network device should act promiscuously. Examples include bridges, which must listen to all traffic in order to build their media access control (MAC) address tables; protocol analyzers; and other network troubleshooting devices that need to capture and analyze all traffic on a particular local area network (LAN) segment.

See Also: *bridge, MAC address, network interface card (NIC), network troubleshooting*

protocol

A set of rules or procedures for sending information over a network.

Overview

Protocols perform such functions as initializing and terminating communication sessions, addressing and routing packets, sending and broadcasting data, performing authentication or encryption, compressing data, and performing error correction. Some protocols have been developed by specific vendors and then accepted as de facto standards by the industry, but others were initially formulated by independent standards bodies and then accepted and implemented by vendors. The most widely implemented protocols are those relating to Transmission Control Protocol/Internet Protocol (TCP/IP) and the Internet.

Types

Protocols are usually classified according to the layer they correspond to in the Open Systems Interconnection (OSI) reference model for networking. Types of protocols include the following:

- **Data-link protocols:** Govern the framing of data, physical addressing of network nodes, and media access control methods. For local area networks (LANs), these primarily include Ethernet, Token Ring, and Fiber Distributed Data Interface (FDDI). For wide area networks (WANs), they include Point-to-Point Protocol (PPP), High-level Data Link Control (HDLC), frame relay, Asynchronous Transfer Mode (ATM), and X.25.
- **Network protocols:** Handle link services and are responsible for addressing, routing, and error checking. Examples include NetBEUI, Internetwork Packet Exchange (IPX), NWLink, and Internet Protocol (IP).
- **Transport protocols:** Enable the establishment of sessions and ensure reliable flow of data. Examples include NetBEUI, Sequenced Packet Exchange (SPX), NWLink, and Transmission Control Protocol (TCP).
- **Application layer protocols:** Enable applications to access network services. Examples include Hypertext Transfer Protocol (HTTP), File Transfer Protocol (FTP), Telnet, Simple Mail Transfer Protocol (SMTP), Simple Network Management Protocol (SNMP), Network News Transfer Protocol (NNTP), X.400, X.500, Server Message Block (SMB), and Network File System (NFS).

For More Information

Visit *www.protocols.com*.

See Also: *Open Systems Interconnection (OSI) reference model*

protocol converter

A device that emulates the behavior of another device.

Overview

Protocol converters are often used in mainframe computing environments where they enable one device to emulate the communication functions of another device. For this reason, a protocol converter is sometimes known as an "emulator," and such emulators can be either hardware-based or software-based. One common type of protocol converter lets you communicate asynchronously with a mainframe host from a PC over a synchronous communication link. This enables you to use the PC as the front end to the host instead of using expensive synchronous terminals. To support this synchronous/asynchronous conversion, the emulation hardware/software must perform several conversions:

- Connect the twinax or coax synchronous connection from the host to an asynchronous RS-232 connection for the PC. For a remote connection, the converter might include X.21 or V.35 serial interfaces as well.
- Take the Synchronous Data Link Control (SDLC) data stream from the host and convert it to an asynchronous format.
- Perform synchronous Extended Binary Coded Decimal Interchange Code (EBCDIC) to asynchronous ASCII conversion and translate standard input/output into appropriate screen/keyboard mappings.



Protocol converter. *Two scenarios where you might use a protocol converter.*

For example, you can turn a PC into a 5250 terminal by installing a 5250 emulator card (a PC typically emulates a 3270 terminal for remote connections or a 5250 terminal for local connections). Here you might use twinax cabling to connect the port on the card directly to an AS/400 or System 390 mainframe. The 5250 emulator software running on the PC typically supports multiple concurrent 5250 sessions.

You can also use protocol converters to connect ASCII printers to AS/400 or System/3x mainframe hosts. A protocol converter for this purpose is sometimes called a printer emulation card.

See Also: *3270, 5250, mainframe, terminal emulator*

protocol file

A text file that provides resolution of protocol names into their respective RFC-defined protocol numbers on a Transmission Control Protocol/Internet Protocol (TCP/IP) network.

Overview

The entries in a protocol file include friendly names for TCP/IP protocol numbers and can be used for well-known service (WKS) records in Domain Name System (DNS) servers and other Windows Sockets applications.

The protocol file is in the following location on computers running Microsoft Windows:

- **Windows 2000, Windows XP, and Windows .NET Server:** %SystemRoot%\system32\drivers\etc\protocol
- **Windows Millennium Edition (Me):** \Windows\protocol

Each line in the protocol file contains the standard name for a protocol followed by the assigned number as defined in RFC 1060, an alias, and an optional comment prefixed with a pound sign (#). The following example comes from the sample protocol file included with Windows 95 and Windows 98:

```
ip     0  IP    # Internet protocol
icmp   1  ICMP  # Internet control message
                  protocol
ggp    3  GGP   # Gateway-gateway protocol
tcp    6  TCP   # Transmission control protocol
```

See Also: *hosts file, lmhosts file, Networks file, services file*

Protocol Independent Multicast-Dense Mode (PIM-DM)

A dense mode multicast routing protocol.

Overview

Protocol Independent Multicast-Dense Mode (PIM-DM) is a multicast routing protocol similar to Distance Vector Multicast Routing Protocol (DVMRP). PIM-DM shares the following similarities with DVMRP:

- Builds source-based trees using reverse-path forwarding
- Operates in dense mode to forward multicast traffic everywhere

The main difference between PIM-DM and DVMRP is that although DVMRP uses its own routing protocol for building its multicast routing tables, PIM-DM can utilize any underlying unicast routing protocol for this purpose, including Interior Gateway Routing Protocol (IGRP), Enhanced Interior Gateway Routing Protocol (EIGRP), Routing Information Protocol (RIP), or Open Shortest Path First (OSPF). This makes PIM-DM considerably more powerful and flexible than DVMRP, particularly for large internetworks.

See Also: *dense mode, Distance Vector Multicast Routing Protocol (DVMRP), Enhanced Interior Gateway Routing Protocol (EIGRP), Interior Gateway Routing Protocol (IGRP), multicasting, Open Shortest Path First (OSPF), Protocol Independent Multicast-Sparse Mode (PIM-SM), Routing Information Protocol (RIP), routing protocol, sparse mode, unicasting*

Protocol Independent Multicast-Sparse Mode (PIM-SM)

A sparse mode multicast routing protocol.

Overview

Protocol Independent Multicast-Sparse Mode (PIM-SM) is closely related to its dense mode cousin, Protocol Independent Multicast-Dense Mode (PIM-DM). Like PIM-DM, PIM-SM can also use a variety of underlying unicast routing protocols for building its routing tables. The differences are that PIM-SM is optimized for wide area network (WAN) usage where the distance between multicast source and receivers is assumed to be great and that there may be limited amounts of bandwidth available for communications between them. To optimize performance in a WAN environment, PIM-SM uses explicit join messages and builds a single shared tree for the entire multicast group instead of using source-based trees as in PIM-DM.

See Also: *dense mode, Protocol Independent Multicast-Dense Mode (PIM-DM), routing protocol, sparse mode, wide area network (WAN)*

protocol suite

A collection of protocols that work together as a group.

Overview

Most networking protocols are actually collections or suites of protocols that work together to perform various complementary functions. Examples of protocol suites include the following:

- NetWare’s Internetwork Packet Exchange (IPX) and Sequenced Packet Exchange (SPX) and related protocols, such as NetWare Core Protocol (NCP) and Service Advertising Protocol (SAP)
- The Internet’s TCP/IP protocol suite, which consists of Internet Protocol (IP), Transmission Control Protocol (TCP), and related protocols such as Address Resolution Protocol (ARP), Internet Control Message Protocol (ICMP), and Hypertext Transfer Protocol (HTTP)
- AppleTalk and its related protocols, such as AppleShare, EtherTalk, and LocalTalk

See Also: *protocol*

Provider Architecture for Differentiated Services and Traffic Engineering (PASTE)

An emerging standard for Internet service billing and traffic delivery.

Overview

The Internet Engineering Task Force (IETF) is developing Provider Architecture for Differentiated Services and Traffic Engineering (PASTE) as a way of defining how Internet service providers (ISPs) can deliver different traffic types to their clients and bill them accordingly. PASTE uses the Multiprotocol Label Switching (MPLS) protocol and the Resource Reservation Protocol (RSVP) to provide these differentiated services.

Existing traffic management technologies such as Cisco Systems' tag switching require that routers maintain state information for every virtual circuit they detect. PASTE eases this requirement by aggregating traffic flows that share a common path into a trunk. Routers need only maintain tables of trunks instead of tables for virtual circuits, which greatly reduces router overhead. Packets can then join or leave a trunk at any router. PASTE can thus be implemented without adding overhead to an ISP's routers, whose tables are often burdened by the rapidly expanding address space of the Internet.

See Also: *Internet Engineering Task Force (IETF), Internet service provider (ISP), Multiprotocol Label Switching (MPLS), Resource Reservation Protocol (RSVP), router*

provisioning

Delivering telecommunications services to the customer premises.

Overview

In enterprise networking, provisioning commonly refers to the process of requesting, obtaining, deploying, and configuring various telco services, mainly in order to build wide area networks (WANs) or to provide high-speed Internet access. For example, one could say "The provisioning of our T1 line took several weeks to complete."

Provisioning also has a more limited usage in terms of configuring various options for telco services. For example, an analog telephone line can be provisioned with only a few options, such as caller ID and call waiting. An Integrated Services Digital Network (ISDN) line can be provisioned with many more options, and the configuration of the ISDN equipment at the customer premises must match that at the telco's central office (CO) for communication to function properly. For example, the service profile identifier (SPID), which is a phone number with additional digits prefixed and appended to it, must be configured properly on the customer's ISDN equipment for the telco's ISDN switching equipment to recognize the type of equipment that is attached, recognize whether one or more devices is attached, and enable calls to be routed appropriately to the equipment.

See Also: *central office (CO), Integrated Services Digital Network (ISDN), T-carrier, telco, wide area network (WAN)*

proxy cache server

A type of proxy server that caches Web pages that users request on the Internet.

Overview

A proxy cache server can be used like a regular proxy server at the border of a private corporate network in order to cache the Web pages returned from the Internet when users in the private network request them. When users request these pages again, the pages are returned instantly from the cache; a new request need not be sent over the Internet. This speeds up browsing for frequently accessed Web sites and reduces the amount of bandwidth used on the corporate Internet link. Proxy cache servers can also be used at Internet service providers (ISPs) and at strategic locations on the Internet's high-speed backbone to provide relief to heavily accessed Web servers and to reduce overall backbone traffic. Another name for this kind of server is *caching proxy*.

Basically, proxy cache servers can perform two kinds of caching:

- **Passive caching:** Web pages that clients request are cached for later retrieval if requested.
- **Active caching:** The proxy server tries to anticipate which Web pages clients will request, and when the server has idle time and the network is sufficiently quiet, the proxy server requests the pages and stores them in the cache.

See Also: *caching, proxy server*

proxy server

An application that acts as an intermediary between a private network and the Internet.

Overview

Proxy servers act as secure gateways to the Internet for client computers, and are usually components of firewalls. They are transparent to client computers—a user interacting with the Internet through a proxy server is not aware that a proxy server is handling the requests unless the user tries to access a resource that the proxy server is configured to disallow. Similarly, the Web server receiving the requests from the proxy server interprets these requests as though they came directly from client computers.

Types

Two basic types of proxy servers are used in network firewall environments:

- **Circuit-level gateways:** These are used to establish virtual circuits (VCs) between machines on the internal private network and the proxy server on the border of the private network. The proxy server controls all connections between the internal private network and the external public network. If a client on the private network wants to access the Internet, for example, the Hypertext Transfer Protocol (HTTP) request packet generated by the client's Web browser traverses the virtual circuit to the proxy server; the proxy server then changes the source IP address of the packet to that of the external (public) network interface of the proxy server and forwards the packet onto the Internet. When a remote HTTP server on the Internet sends a response, the proxy server routes this response back through the virtual circuit to the client that made the request.
- **Application-level gateways:** These operate at Layer 7 (the application layer) and can be used to implement security policies for analyzing packets that reach the external (public) interface of the proxy server from distrusted public networks. These security policies can examine packet addresses and other header information, permit or deny packets on the basis of their contents, and modify the address, header, or contents of packets that they monitor in order to hide key information about the internal network's applications and services. Application-level gateways provide proxy services only for specifically configured applications and protocols such as HTTP, File Transfer Protocol (FTP), Simple Mail Transfer Protocol (SMTP), and Telnet. For each type of application for which you want to regulate access through the firewall, you must install and configure a related proxy service on the proxy server. Applications and protocols for which a proxy service is not installed cannot be accessed through the firewall.

Uses

Proxy servers are generally used to secure private networks connected to unsecured public networks such as the Internet. They have greater functionality than packet filtering routers because they operate at a higher level of the protocol stack and afford greater control over monitoring and managing network access. A proxy server functioning as a security agent for a private network is an essential part of a firewall.

Advantages and Disadvantages

The advantages of using a proxy server include the following:

- It provides a single, secure gateway to manage between your private corporate network and the public Internet.
- It can provide different types of access to the Internet for different groups of users as appropriate.
- It can monitor and track Internet usage for each user.
- It can enable multiple users to share a single high-speed Internet connection.

Instead of using a proxy server, you could provide modems for, and run telephone lines directly to, each user who needs Internet access, but this option is costly. You can also configure a physically separate network with several computers that have shared Internet access, but this is cumbersome for users.

See Also: *firewall, packet filtering, proxy cache server, virtual circuit*

P-series protocols

A group of protocols that are part of the X.400 messaging standards.

Overview

Five P-series protocols relate to messaging systems that support X.400, such as Microsoft Exchange Server:

- **P1:** Specifies the layout of messages transferred from one Message Transfer Agent (MTA) to another. This protocol specifies that X.400 messages consist of two parts: a P1 header, which acts as an envelope and must contain a globally unique recipient address for message routing and control purposes, and a P2 message, which is the actual content of the message.
- **P2:** Defines the format for transmitting the content of an X.400 message. This format includes a P2 header (which is not used because the P1 header provides the necessary routing information for the message) and a P2 body, which is the actual content of the message and consists of one or more body parts of various types (such as text, images, voice, or telex).
- **P3:** Specifies how a user agent (UA) communicates directly with an MTA for sending or receiving a message. This protocol is not used as often as the P7 Protocol for the same reason that Post Office Protocol version 3 (POP3) is used instead of Simple Mail Transfer Protocol (SMTP) to receive Internet mail.
- **P7:** Specifies how a UA communicates with a message store (MS) in order to selectively retrieve messages from the store and delete unwanted messages without downloading them.
- **P22:** A 1988 revision of the P2 Protocol that clarifies and extends certain features of P2.

See Also: *Post Office Protocol version 3 (POP3), Simple Mail Transfer Protocol (SMTP), X.400*

PSTN

Stands for Public Switched Telephone Network, the public telephone network managed by the local telco and long-distance carriers.

See: *Public Switched Telephone Network (PSTN)*

PTR

Stands for pointer record, a resource record for reverse name resolution.

See: *pointer (PTR) record*

public key cryptography

A popular method for encrypting data for transmission over a network.

Overview

Also known as asymmetric cryptography, public key cryptography is an encryption method developed by Martin Hellman and Whitfield Diffie in 1976 that is used for securing transmission of data over unsecure networks such as the Internet. Earliest forms of cryptography involve a private or secret key that was shared by the individuals involved in the transmission. The key is a mathematical entity that the sender can use to encrypt a message and the receiver can use to decrypt it. This form of cryptography is known as secret key cryptography or symmetric cryptography. The main problem with this form of cryptography is the question of how the owner of the key can securely transmit the key. In other words, the main problem is one of key management—how to create, store, and transmit the key to those who will need it to decrypt messages sent to them.

Public key cryptography solves this problem by creating a set of two different keys for anyone needing to transmit encrypted information. A precise mathematical relationship exists between the two keys, which together are called a key pair. Both keys are produced at the same time using a mathematical algorithm such as Rivest-Shamir-Adleman (RSA). As a result, when either one of the two keys is used to encrypt a message, the other can be used to decrypt it.

The two keys in a key pair are as follows:

- **Private key:** Held privately by the owner of the key pair and kept secret from anyone else. The responsibility for safe storage of the private key rests entirely with the key pair owner, who has no need to transmit the private key to others.

- **Public key:** Made available by the key pair owner to anyone who requests it. Because the public and private keys are related mathematically, in principle someone could take another person's public key, perform complex mathematical calculations on it, and extract the corresponding private key. The solution is to use keys sufficiently long and with a sufficiently complex mathematical relationship so that it is all but impossible to extract the private key from the public one.

Once a key pair is generated for someone, that person can use it to encrypt messages and to digitally sign messages so that the recipient can be sure of the sender's identity.

The entire public key cryptography system is ultimately founded on trust. All persons who are issued key pairs must trust the third-party authority who provided the key pairs. This trusted authority is called a certificate authority (CA). Someone who wants to obtain a key pair from a CA must contact the CA and present proof of identity. This could involve a face-to-face meeting, examination of a driver's license with photograph, or some other method of establishing a user's identity.

See Also: *cryptography, digital certificate, digital signature, encryption, public key infrastructure (PKI), Secure Sockets Layer (SSL)*

P

Public Key Cryptography Standards (PKCS)

A set of standards for cryptography.

Overview

The Public Key Cryptography Standards (PKCS) were developed by an industry consortium headed by RSA Laboratories and including Microsoft Corporation. PKCS specifies how a public key cryptography system should be implemented and operated. The following table shows the standards that are important to public key cryptography.

Public Key Cryptography Standards

Standard	*Description*
PKCS #1	Specifies how to encrypt and sign data using RSA encryption
PKCS #2	Now included in PKCS #1
PKCS #3	Describes the Diffie-Hellman key exchange protocol
PKCS #4	Now included in PKCS #1
PKCS #5	Specifies how to encrypt data using a secret key derived from a user's password
PKCS #6	Specifies the syntax standard for extended certificates
PKCS #7	Specifies the general syntax of messages that include cryptographic enhancements such as encryption and digital signatures
PKCS #8	Specifies the format for private key information
PKCS #9	Specifies various attribute types that are used in other PKCS standards
PKCS #10	Specifies the syntax for requesting digital certificates
PKCS #11	Specification for the Cryptoki application programming interface (API), which is used in smart cards
PKCS #12	Specifies a portable format for storing and transporting certificates, private keys, and so forth
PKCS #13	Specifies standards for elliptic curve cryptography (under development at the time of this writing)
PKCS #14	Specifies standards for generating pseudo-random numbers (under development at the time of this writing)
PKCS #15	Specifies the standard format for cryptographic token information (under development at the time of this writing)

See Also: *cryptography, PKCS #7, PKCS #12*

public key infrastructure (PKI)

An infrastructure to enable the use of public key cryptography in a corporate or public setting.

Overview

In order to implement public key cryptography, a public key infrastructure (PKI) must first be deployed. A PKI is essentially a group of services that enables key pairs to be generated, securely stored, and securely transmitted to users so that users can securely send encrypted transmissions and digital signatures over public networks such as the Internet. A PKI can be used to secure e-mail messages and World Wide Web (WWW) transactions, e-commerce and business-to-business (B2B) linkages, and corporate virtual private networks (VPNs).

Architecture

A public key infrastructure consists of a framework of coordinated services that are standardized to a degree by the Public Key Infrastructure X.509 (PKIX) working group of the Internet Engineering Task Force (IETF), although some work in this area still needs to be done. These coordinated services generally include

- A trusted certificate authority (CA) that can obtain a digital certificate and key pair that maps to their identity. This CA may be the enterprise itself, a trusted business party, or a trusted third party such as a government agency or vendor of public PKI services.
- A registration authority (RA) that can accept requests for digital certificates and cache them while the user's alleged identify is verified. Sometimes the verification of user identities is performed by a separate RA, but this service can also be integrated with the functions of the CA.
- A certificate store in which users can access the public keys of other users for encrypting messages or validating digital signatures. This store is usually based on the X.500 directory recommendations and must include a certificate revocation list (CRL) mechanism for identifying certificates that are compromised, expired, or otherwise no longer valid.
- A digital certificate and key management system for generating, storing, and securely transmitting certificates and key pairs to users who request them.

Implementation

Although companies can implement their own in-house PKI systems using software such as Microsoft Windows 2000's Certificate Services and other products, many enterprises employ the services of PKI vendors such as those discussed below to outsource their PKI needs. These vendors provide client software, plug-ins, and CA/RA/CRL services to help enterprises implement public key cryptography as their underlying security mechanism. Unfortunately, implementing PKI is usually easier said than done, and it can be time-consuming and costly (most PKI vendors charge on a per user basis, which adds up quickly for large enterprises). The net result is that PKI often suffers from the perception that it is difficult to implement and use, which has resulted in few large-scale PKI deployments being done so far.

Actually, the most difficult part of implementing PKI in the enterprise arena is usually application integration—getting all the various existing client software packages to recognize and utilize public key cryptography as the basis of their security. Many enterprises have backed away from PKI after an initial trial because of the difficulty of integrating PKI throughout their applications platforms. As an example of the kind of situation you want to avoid, consider the case of an employee who is leaving your company. You delete that person's information from your human resources database—but does your PKI system automatically revoke the employee's digital certificate? This is the sort of automated task that requires careful application integration to ensure your enterprise's security, and it can be difficult to achieve in enterprises with many legacy application packages. Rivest-Shamir-Adleman (RSA) has an innovative solution in this regard with its Web Passport, which uses a small downloadable plug-in module to bridge legacy applications to digital certificates without the need to build support for PKI into these applications.

Marketplace

Major vendors of PKI software and services include Baltimore Technologies, Entrust, RSA Security, and VeriSign. Products from these vendors vary greatly in manageability, application integration, and cost, so before settling on one solution, you should exercise due diligence in testing and piloting popular systems.

Before deciding to implement PKI in your enterprise, it is a good idea to consider first whether it is really needed. E-commerce and messaging are currently being successfully transacted in a relatively secure fashion without the need of PKI—for example, using the Secure Sockets Layer (SSL) protocol. Some startup companies are also developing products that sidestep some of the difficulties of implementing a PKI and provide innovative ways of securing corporate e-mail and Web transactions. Examples include SafeLoop, which sends encrypted electronic messages using Hypertext Transfer Protocol (HTTP) instead of Simple Mail Transport Protocol (SMTP), and Hilgraeve, which enables secure online document collaboration using online storage services instead of sending documents as e-mail attachments. P2P (peer-to-peer) technologies are also emerging as an alternative to traditional Internet messaging and collaboration protocols and may provide an additional option for enterprises seeking innovative solutions to secure electronic communications.

Prospects

Many industry analysts consider PKI's prospects of succeeding in the enterprise and in the larger public arena uncertain. The complexity and cost of implementing PKI has caused many enterprises to balk at the process, especially when funds are more urgently needed for putting out other security-related fires. Many IT (information technology) managers see e-mail filtering, antivirus software, firewalls, and intrusion detection systems as more of a priority than rolling out a complex PKI system. A few spectacular failures of large-scale PKI rollouts have also had a discouraging effect on the market. Another serious issue has been interoperability issues between software and platforms from different PKI vendors, a result of the effect of vendor politics on the standards process.

On the other hand, there have been many successful PKI implementations, even in the public arena. The U.S. Patent and Trademark Office has a PKI system that allows patent applications to be securely filed online, and the result has been considerable cost savings. But by and large the world is still years away from a time when digitally signed documents can be used as easily as paper ones for legal, medical, financial, and contractual transactions between individuals and companies. One positive step occurred in October 2000 with the passing into U.S. law of the Electronic Signatures in Global and National Commerce (E-Sign) Act. However, this law recognizes the legal validity of digital certificates, but it also hedges bets by avoiding the task of defining exactly what a "digital certificate" is.

For More Information

Visit the PKI Forum at *www.pkiforum.org.*

See Also: *certificate authority (CA), cryptography, digital certificate, encryption, key pair, public key cryptography, Secure Sockets Layer (SSL)*

Public Switched Telephone Network (PSTN)

The public telephone network managed by the local telco and long-distance carriers.

Overview

The Public Switched Telephone Network (PSTN) consists of a digital Integrated Services Digital Network (ISDN) backbone of switched circuits together with the analog local loop wiring still found in many residences. The PSTN is sometimes referred to as the Plain Old Telephone Service (POTS), but this term actually refers to the older analog portion of the PSTN.

The PSTN provides the most popular basis for creating wide area networks (WANs) either through dial-up or leased lines. The PSTN is often used in wide area networking because of its ubiquitous nature since local loop connections to the service exist almost everywhere in the world. However, with the advent of alternative services such as high-speed cable modem services and passive optical networking (PON), the days of the slow, analog local loop connection may be approaching their end.

See Also: *analog, cable modem, digital, Integrated Services Digital Network (ISDN), local loop, passive optical network (PON), Plain Old Telephone Service (POTS), wide area network (WAN)*

publishing

In Active Directory directory service, the process of making directory objects accessible to users on the network.

Overview

Many objects created in Active Directory are automatically published or made available to users on the network. For example, when you create a new user object containing information about that user, such as the user's phone number and e-mail address, other users on the network can look up this information in Active Directory.

If an object that does not reside in Active Directory is published, Active Directory points to the object's location on the network. Most objects are automatically published in Active Directory if they reside on computers running Windows 2000, Windows XP, or Windows .NET Server, but you might have to manually publish the location of other objects, such as shared folders and printers on downlevel computers running Windows NT.

When you consider whether to publish an object in Active Directory, consider whether the information will be changed frequently. Published information should be relatively static. Information should be published when it will be useful to a large segment of the enterprise community. Structured information is more useful to publish than individual items such as files, which should be published instead in file systems accessed through share points. Applications can publish their connection points and application data in Active Directory.

See Also: *Active Directory*

pulse code modulation (PCM)

A common method for converting analog signals into digital ones used by telcos.

Overview

Pulse code modulation (PCM) is the standard method used by telephone companies and telecommunications providers for converting analog signals into digital ones that can be transmitted over the Integrated Services Digital Network (ISDN) and Asynchronous Transfer Mode (ATM) backbones of the Public Switched Telephone System (PSTN). Digital signaling has replaced analog in the PSTN backbone because digital signals can be transmitted long distances with little degradation in signal quality.

Implementation

The basis of PCM is the Nyquist Theorem from Information Theory, a branch of mathematics concerned with information and signaling. The Nyquist Theorem states that in order to accurately represent an analog signal as a digital one, the signal must be sampled at twice the maximum analog signal frequency. Since the maximum frequency used in analog voice communications in the local loop is 4 kilohertz (4000 hertz or 4000 cycles/second), the theorem indicates that analog signals must be sampled at twice that or 8 kHz. PCM does just this by taking analog signals with continually varying voltages and quantizing these signals into discrete voltages using an 8-bit (1 byte) representation for each sample. The voltage levels correspond to powers of 2 and represent a series of binary numbers so that the output of a PCM device is essentially a binary number. This sampling and quantization process results in a data transmission rate of 8 bits x 8 KHz = 64 Kbps, which explains why 64 Kbps DS-0 trunk lines form the basis of the PSTN's backbone.

A typical PCM converter consists of a sample-and-hold circuit that samples the analog voltage signal and holds it long enough so that an analog-to-digital converter can convert it into digital (binary) format. A single device plus its associated software that can perform both the analog-to-digital conversion and its reverse is known as a codec or coder/decoder.

See Also: *Asynchronous Transfer Mode (ATM), DS-0, Integrated Services Digital Network (ISDN), local loop, Public Switched Telephone Network (PSTN), telco*

PVC

Stands for permanent virtual circuit, a dedicated circuit between two nodes in a circuit-switched network.

See: *permanent virtual circuit (PVC)*

PVC cabling

Stands for polyvinyl chloride cabling, a grade of network cabling that uses polyvinyl chloride (PVC) plastic for its outer protective insulating jacket.

See: *polyvinyl chloride (PVC) cabling*

Q

QIC

Stands for Quarter Inch Cartridge, the original tape format for tape backups.

See: *Quarter Inch Cartridge (QIC)*

QoS

Stands for quality of service, any network mechanism for ensuring that applications or services are able to operate as expected.

See: *quality of service (QoS)*

QoS ACS

Stands for QoS Admission Control Service, a feature of Microsoft Windows 2000 for implementing quality of service (QoS) on an Internet Protocol (IP) network.

See: *QoS Admission Control Service (QoS ACS)*

QoS Admission Control Service (QoS ACS)

A feature of Microsoft Windows 2000 for implementing quality of service (QoS) on an Internet Protocol (IP) network.

Overview

QoS Admission Control Service (QoS ACS) is a Windows 2000 service that can be used to centrally designate when, how, and by whom shared network segment resources will be used. QoS ACS is based on the Subnet Bandwidth Management (SBM) specification defined by the Internet Engineering Task Force (IETF). QoS ACS operates at the network layer and can service all transport protocols in the TCP/IP protocol suite, including Remote Display Protocol (RDP), User Datagram Protocol (UDP), and Transmission Control Protocol (TCP). A QoS ACS host (a server running Windows 2000 with the QoS ACS service installed and configured) uses the Resource Reservation Protocol (RSVP) as a message service for sending and receiving priority bandwidth requests.

Implementation

A QoS ACS host controls the bandwidth for the subnet to which it is connected. The QoS ACS host uses multicasting to send out messages called beacons to inform clients on the subnet that it is ready to receive bandwidth allocation requests. Clients on the subnet that desire access to shared network resources (such as multimedia servers) first submit their bandwidth request to the QoS ACS server so that it can determine whether sufficient bandwidth is available to allocate to the clients. Bandwidth is then allocated based on the current state of resource and bandwidth availability on the subnet and the requesting user's QoS ACS policy rights. These policy rights are defined in Active Directory directory service.

A client's request for bandwidth will be rejected if the QoS ACS host determines that the user does not have the right to reserve bandwidth on the subnetwork or if the subnetwork does not have sufficient resources to support the request at that time. If the client's request is rejected, the client must decide whether to try accessing the resource using a best-effort service level or wait until later, when priority bandwidth becomes available and can be allocated to the client. If the request is approved, the QoS ACS host logically allocates the requested bandwidth and forwards the client's resource request to the appropriate server on the network. No configuration is required for Windows clients, and non-Windows clients can request bandwidth, provided they are running suitable SBM client software.

See Also: *quality of service (QoS), Resource Reservation Protocol (RSVP)*

Q-series protocols

Also called Series Q protocols, a set of protocols developed by the International Telecommunication Union (ITU) that govern the operation of Integrated Services Digital Network (ISDN).

Overview

Some of the more important Q-series protocols include the following:

- **Q.920/921:** Specifies the User-Network Interface (UNI) data-link layer for ISDN, including the ISDN D channel's Link Access Protocol, D-channel (LAP-D) data-link layer protocol.
- **Q.922A:** Specifies the ITU encapsulation method for frame relay networks.
- **Q.931:** Specifies mechanisms for establishing, maintaining, and tearing down ISDN connections. This includes working with connections in the LAP-D data-link protocol, which runs on the ISDN D channel.
- **Q.93B:** The Asynchronous Transfer Mode (ATM) signaling protocol, which specifies mechanisms for establishing, maintaining, and tearing down broadband ISDN (B-ISDN) connections.

See Also: *Asynchronous Transfer Mode (ATM), Integrated Services Digital Network (ISDN), International Telecommunication Union (ITU), Link Access Protocol, D-channel (LAPD)*

quality of service (QoS)

Any network mechanism for ensuring that applications or services are able to operate as expected.

Overview

Network performance characteristics such as bandwidth, latency, and jitter (variation in delay) can have bad effects on some applications. For example, voice communications and streaming video can be frustrating when delivered over a network with insufficient bandwidth, unpredictable latency, or excessive jitter. Anyone who has used a cell phone has experienced the frustrating "dropouts" that occur from time to time, causing conversation to be difficult. Quality of service (QoS) is all about making sure that a network's bandwidth, latency, and jitter are predictable and suited to the needs of applications that use that network.

History

The general concept of network QoS originated in the telco market, where it represented a set of technologies and methods for ensuring that services provided to customers were above designated minimum levels of quality. For telephone service, this means, for example, reducing the latency of telephone line communications to less than 200 milliseconds even on long distance or overseas calls, as delays above this value result in frequent interruptions or awkward pauses in communications as callers wait for a response from the other end. It also meant reliable calls that were not accidentally disconnected, low levels of static and background noise, and minimal signal distortion as callers voices are modulated from analog to digital and back to analog again over the Public Switched Telephone Network (PSTN).

When enterprises began using telco services such as Integrated Services Digital Network (ISDN) and leased lines for connecting their geographically remote offices into a wide area network (WAN), QoS referred to the reliability of the carrier's WAN services for carrying network traffic, which was especially important for synchronous links between mainframes and remote terminals. However, QoS in its modern sense is associated with the emergence of Asynchronous Transfer Mode (ATM) networking, a technology that allows QoS parameters such as delay, jitter, and loss to be enforced for traffic traveling over the network. In essence, ATM allows "traffic contracts" to be established for different types of applications running on the network to ensure that applications that are sensitive to delay or hungry for bandwidth perform as users want them to. The fact that ATM employs fixed-size 53-byte cells is an advantage in implementing QoS on this technology, as ATM switches can generally process fixed-size cells faster than variable length ones. QoS as it refers to ATM networking basically means two things:

- **Prioritization:** Every cell is assigned a service class, and cells belonging to a specific service class are all handled the same way by switches on the ATM network. Prioritization allows different kinds of traffic to be treated differently on an ATM network. For example, voice traffic can be given higher priority than data to ensure that voice communications are always reliable. Different kinds of data traffic can be treated similarly. For example, traffic for an accounting application can be given high priority, while Web traffic can be assigned a lower priority.
- **Resource reservation:** An ATM connection can request and be assigned a given amount of bandwidth along the entire path between the two end nodes involved. This ensures that the application making the request will perform its function during the connection. Because ATM represents a homogeneous, tightly managed cell-switched system, resource reservation is achievable.

Although ATM remains the winner in the arena of network technologies that support QoS, the greatest interest today is in bringing QoS to Internet Protocol (IP) networks such as the Internet. IP was originally designed as a “best effort” delivery service with no guarantees of reliability, delay, or performance. As a result of the underlying operation of the Transmission Control Protocol (TCP) used to establish IP sessions, and because IP employs variable-length packets that are more complex for routers and local area network (LAN) switches to process than fixed-size ATM cells, it has been difficult to bring QoS to IP networks. Efforts have been underway in this regard for years and have resulted in complex protocols such as DiffServ, Resource Reservation Protocol (RSVP), and Multiprotocol Label Switching (MPLS). These efforts are not complete, and IP QoS generally remains a technology that is complex to implement and whose promises are not quite realized. Simple packet-based IP QoS prioritization schemes work well but are difficult to scale to the enterprise level, and more complex resource reservation-based IP QoS is difficult to achieve over networks with multiple subnets and combinations of hubs, switches, and routers. This is discussed further below.

Implementation

This section will cover the details of ATM QoS and examine the efforts underway to make IP QoS a reality. Beginning with ATM, the basic QoS parameters (or traffic parameters) that can be negotiated on an ATM network include the following:

- **Cell Transfer Delay (CTD):** The latency in seconds for a connection
- **Cell Delay Variation (CDV):** The tolerance per second for cells that should not exceed the peak cell rate
- **Cell Loss Ratio (CLR):** The acceptable ratio of cells delivered to cells lost in a transmission
- **Maximum Burst Size (MBS):** The maximum number of cells per burst
- **Peak Cell Rate (PCR):** The maximum number of cells that can be transmitted per second based on the specified peak bandwidth per second
- **Sustainable Cell Rate (SCR):** The maximum number of cells that can be transmitted per second based on the specified sustainable bandwidth per second

To implement QoS in an ATM network, the sending node signals the network using User to Network Interface (UNI) version 4 signaling to reserve bandwidth, restrict cell loss or delay, or similar QoS parameters. The ATM switches configure themselves accordingly to ensure that the requested QoS is achieved. ATM QoS is “hard state” QoS in that connections may be denied if they violate established QoS settings for the network. Some of the kinds of QoS behaviors that can be enforced on an ATM network include

- **Traffic contracts:** Each ATM end node in an ATM network negotiates a traffic contract with that network to specify data stream parameters such as peak bandwidth, average bandwidth, and maximum burst size. These parameters can be defined for the end node to control the type and amount of traffic that the host can send over an ATM circuit. If an ATM switch in the circuit cannot meet these requirements, it sends a message to the transmitting host indicating that the connection is refused. Each virtual channel or virtual path that is established by an ATM end node in an ATM network has its own traffic contract.

- **Traffic shaping:** This involves ATM devices using data queues to smooth out traffic bursts and limit the peak data rate so that the conditions of the negotiated traffic contracts are met. ATM switches can use several kinds of queuing, including first-in/first-out (FIFO) queuing, prioritized queuing, and weighted fair queuing.
- **Traffic policing:** ATM switches enforce traffic contracts so that the agreed-upon QoS conditions of each data stream are met. If these conditions are violated, ATM switches set the cell-loss priority (CLP) bit of each offending cell, which indicates that the offending cells may be dropped should congestion occur at the switch.

These mechanisms enable ATM QoS to support several different classes of QoS, such as

- **Constant Bit Rate (CBR):** The type of traffic under consideration requires a guaranteed rate of transport and does not tolerate cell loss. To implement CBR, an ATM end station informs the ATM network of the required QoS parameters during call setup. The network then performs admission control by reserving the necessary bandwidth or refusing the connection. The end station is responsible for complying with the agreed-upon peak data rate—if it exceeds this rate, the network drops the offending cells.
- **Variable Bit Rate (VBR):** Similar to CBR, except that maximum burst size and maximum sustainable rate are negotiated in addition to peak data rate.
- **Unspecified Bit Rate (UBR):** Used mainly for LAN emulation (LANE) mode—that is, running IP traffic over ATM backbones. In UBR, if a cell is dropped due to congestion, the entire IP packet to which the cell belongs is retransmitted. UBR does not reserve bandwidth or establish a cell-loss ratio.
- **Available Bit Rate (ABR):** Also used in LAN emulation mode, ABR implements periodic polling of the ATM network to adjust the data transmission rate as needed.

In the realm of IP networks, QoS can be implemented using the same basic approaches used in ATM, namely, prioritization and resource reservation. Prioritization means that the way a particular IP packet will be handled by QoS-enabled devices such as suitable routers and switches on the network is embedded within the packet itself. In other words, IP QoS prioritization works on a packet-by-packet basis, and as a packet traverses the network the various switches and routers handle the packet independently of one another (stateless QoS). Priority-based QoS is configured by setting packet-forwarding rules on the routers and switches on the network, so all such devices on the network must support this feature in order for it to work properly. Priority-based IP QoS schemes generally employ multiple queues on suitable routers and switches so that different types of traffic (packets having different priorities) are delivered to different queues on the device. The device then processes these queues in a way that ensures that traffic with high priority is processed first. Priority-based IP QoS is the basis of the IEEE 802.1p standard and is implemented at Layer 2 (the data link layer) of the Open Systems Interconnection (OSI) reference model, but there is also a Layer 3 approach to IP QoS prioritization called DiffServ, which is discussed later in this article.

By contrast, IP QoS resource reservation uses a stateful approach in which the receiving node (not the sending node) uses RSVP to contact all the various switches and routers along the path to be used, telling each device to reserve the required bandwidth for the traffic. This is complicated by the fact that the switches and routers must be able to adjust to changes in network performance should they occur. The network interface cards (NICs) of the sending and receiving hosts must also support QoS—in other words, the resource reservation type of QoS requires end-to-end support in order to work. The resource reservation approach to IP QoS using RSVP is the method utilized by the QoS Admission Control Service of Microsoft Windows 2000 to implement IP QoS on this platform.

RSVP is the basis of the integrated services (IntServ) approach to IP QoS because this feature must be "integrated" across all packet-forwarding devices on the network in order to work, including routers, switches, and NICs. The IntServ approach enables IP networks to be used as the backbone for applications ranging from voice, video, and real-time data to classical data traffic. By contrast, IP QoS prioritization employs differentiated services (DiffServ), which classifies traffic into different priority classes using the DS field in the IPv4 packet header to define how the packet will be forwarded. The DiffServ approach can be implemented on an IP network with only minor changes to routers but leaves the complexity of implementing QoS to the edges of the network. DiffServ provides only a statistically based QoS to IP networks with no firm guarantee of bandwidth or traffic handling—in contrast to IntServ, which provides guaranteed QoS, albeit in a much more complicated fashion. So it is a trade-off—DiffServ, with its statistical QoS capabilities but ease of configuration and use of existing routing and switching devices, or IntServ, with its guaranteed QoS capabilities but complex configuration and requirement of routing and switching devices that fully support RSVP.

Another approach to IP QoS is Multiprotocol Label Switching (MPLS), which was derived from Cisco's proprietary label switching technology. MPLS is designed to bring some of the advantages of circuit-switched networks to switched IP networks, including predictable delay and latency, the ability to reserve bandwidth, and QoS. All of the various approaches to IP QoS, including IntServ/RSVP, DiffServ, MPLS, and 802.1p are implemented to various degrees on routers and switches from Cisco Systems and other infrastructure vendors.

Prospects

IP QoS remains an elusive target and, in the opinion of some analysts, even an unnecessary one, considering the cost and complexity of implementing it in the enterprise. On the LAN side, the increasing availability and decreasing cost of Gigabit Ethernet (GbE) has made "throwing bandwidth at the problem" a cheaper and easier solution to network congestion than implementing IP QoS. In the WAN environment, where bandwidth is still scarce, IP
QoS makes more sense. On the other hand, prices for high-end WAN services such as T3 and OC-48 are likely to drop in the near future, since the speed at which Synchronous Optical Network (SONET) can run over fiber and the number of channels that can be carried by a single strand are doubling every year. Although the emergence of Voice over IP (VoIP) as a viable enterprise technology may seem to be a driving force for the implementation of IP QoS, some network architects contend that occasional dropouts or garbled transmissions are a small price to pay compared to overhauling their whole infrastructure to support IP QoS. The best solution may be to implement basic two-level traffic prioritization (high priority for voice and video, low for data), upgrade to GbE, and leave it at that for now until IP QoS technology matures and becomes cheaper and easier to manage.

See Also: *802.1p, Asynchronous Transfer Mode (ATM), bandwidth, cell (ATM), Gigabit Ethernet (GbE), Integrated Services Digital Network (ISDN), Internet Protocol (IP), jitter, latency, Multiprotocol Label Switching (MPLS), Public Switched Telephone Network (PSTN), Resource Reservation Protocol (RSVP), Transmission Control Protocol (TCP), wide area network (WAN)*

Quarter Inch Cartridge (QIC)

The original tape format for tape backups.

Overview

Quarter Inch Cartridge (QIC) is a cartridge-based tape format that was developed in the 1970s and became widely popular in the enterprise—in fact, it is still in use in many places. QIC employs serpentine recording to record several parallel tracks on the tape, switching directions at the end of each track. QIC tape cartridges come in two basic formats:

- **Data cartridge (DC):** A large 4 by 6 inch cassette 5/8 inch thick.

- **Mini cartridge (MC):** A smaller 3 ¼ by 2 ½ by 3/5 inch cassette.

There are dozens of different QIC formats based on tape capacity, transfer speed, and interface. Most QIC drives today employ Travan technology originally developed by 3M Corporation and now licensed by Imation Corporation.

For More Information

Get more information about QIC at *www.qic.org.*

See Also: *backup, tape format*

quartet signaling

A signaling method used by 100VG-AnyLAN.

Overview

Quartet signaling makes possible the transmission of data at a speed of 100 megabits per second (Mbps) while using the same transmission frequencies that are used on standard 10BaseT networks. Quartet signaling enables 100VG-AnyLan to leverage existing installations of Category 3, 4, and 5 unshielded twisted-pair (UTP) cabling for 100-Mbps transmission.

Implementation

100VG-AnyLan employs the demand priority method for controlling access to the media, which prevents collisions from occurring. Although 10BaseT Ethernet networks use only two pairs of wires in a four-pair UTP cabling—one pair for transmitting data and the other pair for receiving data and for detecting collisions on the network—100VG-AnyLAN transmits signals over all four pairs of wire in voice-grade UTP cabling, hence the term *quartet signaling*. In addition, quartet signaling uses a different line coding technique than the traditional Manchester coding method used in Ethernet networks. Quartet signaling uses the 5B/6B NRZ line coding method, but Manchester coding uses a 1B/2B scheme whereby 1 bit of data is encoded using two binary symbols. The 1B/2B algorithm is reliable and simple to implement but inefficient. The 5B/6B method encodes 5 bits using six binary symbols, which allows two and a half times as much information to be transmitted per wire compared to 10BaseT Ethernet (as shown in the following table).

Calculations for Line Coding Data Rates

	Manchester Coding	***Quartet Signaling***
Line coding	1B/2B	5B/6B
Line frequency	20 MHz	30 MHz
Data rate per pair	($^1/_2$) x 20 = 10 Mbps	($^5/_6$) x 30 = 25 Mbps
Number of pairs used	1	4
Total data rate	1 x 10 = 10 Mbps	4 x 25 = 100 Mbps

Notes

The 100BaseT4 form of Fast Ethernet also uses all four pairs of wire in twisted-pair cabling.

See Also: *10BaseT, 100VG-AnyLAN, demand priority, Ethernet, line coding, Manchester coding, unshielded twisted-pair (UTP) cabling*

queue

A collection of items waiting to be processed in a specific order.

Overview

Examples of queues in computer and networking technology are numerous and include the following:

- A print queue, which consists of print jobs waiting to be sent to a print device
- A messaging queue (on a mail server such as Microsoft Exchange Server), which consists of messages waiting to be sent
- A backlog of packets waiting to be forwarded over a specific interface by a router
- Information, function calls, or transactions sent by one application and forwarded to another by Microsoft Message Queuing (MSMQ)
- A collection of fax messages waiting to be processed and sent by a fax server
- A series of system messages, such as key presses and mouse clicks, sent by applications to an operating system for processing

queuing methods

Methods used by routers and local area network (LAN) switches for queuing incoming traffic.

Overview

Most LAN switches and routers implement some form of queuing to ensure that packets are not lost in times of heavy traffic. Certain forms of queuing also enable these devices to implement quality of service (QoS) through prioritizing different types of traffic by using different queues for each type. The most common queuing methods used in such devices include

- **First-in/first-out (FIFO) queuing:** Here, incoming packets are stored in the queue and forwarded in the order in which they arrived. FIFO queuing requires no configuration and helps routers handle traffic congestion, but they do not support QoS. On Cisco routers, FIFO queuing is the default queuing method for all interfaces unless configured otherwise.
- **Priority queuing:** Routers using this form of queuing employ multiple queues for different types of traffic, typically four queues for high, medium, normal, and low priority traffic. These traffic types can be distinguished according to incoming interface, packet size, source address, destination address, or network protocol. Queues are emptied in a fashion that ensures that higher priority traffic is given first attention, which enables these devices to support Internet Protocol (IP) QoS prioritization. Priority queuing is used by Asynchronous Transfer Mode (ATM) switches and is often used on wide area network (WAN) links to ensure that high-priority traffic such as Voice over IP (VoIP) and Enterprise Resource Planning (ERP) applications perform as expected.
- **Weighted fair queuing:** This is a flow-based form of queuing that allows interactive traffic to be moved ahead in the queue to ensure good performance. Weighted fair queuing implements QoS by ensuring that applications that require bandwidth get enough of it to function satisfactorily. Weighted fair queuing was introduced with release 11 of the Cisco Internetwork Operating System (IOS).

Queuing methods other than FIFO generally do not need to be configured for wide area network (WAN) access routers if the utilization rate of the WAN link is low. The interfaces that generally benefit most from queuing are subrate interfaces, that is, speeds slower than T1 (fractional T1 being the typical example).

See Also: *Asynchronous Transfer Mode (ATM), Ethernet switch, Internetwork Operating System (IOS), quality of service (QoS), router*

quota management

Managing disk storage for network users.

Overview

Quota management involves setting storage limits for individual users on file servers and other forms of network storage. Although disk space has become an inexpensive commodity over the last few years, managing large amounts of user files can become a nightmare from a management perspective. Setting quotas for users prevents them from accumulating unnecessary files and encourages them to manage their network workspace wisely. Quota management tools generally alert users when volumes are nearly full, which also frees administrators from the chore of intervening by locating and deleting unnecessary files or adding more disk space. Quotas also prevent volumes from becoming full, which can cause storage systems to crash under certain circumstances.

Marketplace

In addition to the disk quota management tools bundled with Microsoft Windows 2000, Windows XP, and Windows .NET Server, and, a number of third-party tools from different vendors are helpful for managing storage in an enterprise environment. Some popular examples include QuotaAdvisor from WQuinn, Quota Server from NORTHERN, Quota Sentinel from NTP Software, and SpaceGuard from Tools4ever.

See Also: *storage*

R

RA

Stands for registration authority, a company or organization that is responsible for receiving and validating requests for digital certificates and public/private key pairs.

See: *registration authority (RA)*

rack

Also called an equipment rack, a metal frame for holding and organizing networking devices.

Overview

Racks offer a way to organize equipment in a wiring closet. Racks can be either wall-mounted or freestanding and come in various heights and standard widths, with 19 inches being by far the most common width. This width is measured between the mounting holes on the rack where equipment is mounted—the actual width of the rack itself is usually several inches wider. The two most common heights for racks are 48 and 83 inches. On industry-standard racks, the holes on the frame are spaced 1.75 inches apart vertically, a distance symbolized as a "U" or "unit" of rack space. If a piece of networking equipment is described as 3U, it therefore occupies 3 x 1.75 = 5.25 inches of vertical space once it is mounted in the rack. A 48-inch rack is 21U in height, meaning it can hold a total of 21 1U devices (or some other combination of devices). An 83-inch rack is 42U in height.

Racks usually come with a variety of accessories. Cable organizers, for example, allow you to run bundled cabling down the side or back of the rack to avoid "spaghetti." You can use sliding shelves or drawers to incorporate odd-sized equipment in racks for easy access for configuration and wiring. Vented sides and fan trays help circulate air to keep equipment from overheating. By attaching a locking plastic or glass door, you can convert some racks into cabinets for more secure storage.

Wall-mounted racks allow you to organize equipment in areas with limited floor space. If your area is prone to earthquakes, it is a good idea to bolt the base of the rack to the floor to protect your equipment.



Rack. *Example of a typical equipment rack.*

Uses

A rack-mountable unit is a device designed to be mounted in a rack. Such rack-mountable devices include servers, hubs, routers, Ethernet switches, patch panels, and uninterruptible power supply (UPS) devices. Rack-mountable servers deserve special attention, as use of these devices in enterprise environments and Internet data centers has grown exponentially in recent years. Numerous manufacturers produce a variety of 1U and 2U rack-mount servers, including Compaq Computer Corporation, Dell Computer Corporation, Hewlett-Packard, and IBM. These servers often support hot-pluggable drives, dual 10/100 or 100/1000 network interface cards (NICs) with automatic failover, embedded hardware redundant array of independent disks (RAID), and other advanced features designed to enhance their reliability and ease of use. Storage appliances from many vendors also come in rack-mount format for easy interfacing with rack-mount servers. Another popular approach is to provide a complete Web server in a 1U appliance format, something widely used by Web hosting companies.

A novel approach is ClearCube Technology's C3 architecture, which provides a rack-mountable chassis into which up to eight fully functional CPU (central processing unit) blades (fully functional PCs in the form of a blade) can be inserted. C3 is essentially a desktop management solution where desktop PCs are replaced by C3 cage units that are centrally located in a server room or wiring closet. Instead of PCs residing on users' desks, they have a mouse, keyboard, monitor, and a small C/Port box that is connected to the cage using Category 5 (Cat5) network cabling. The C3 architecture allows these C/Port boxes to be located up to 600 feet (183 meters) from the cage. The advantage is that when a problem occurs with a user's computer, you can repair it in the server room instead of walking over to the user's work area. The C3 architecture also simplifies the process of operating system and application installations and upgrades, and it minimizes the potential of users damaging their workstations.

Notes

A ladder rack is a modular rack system for supporting cable runs in walls, false floors, and false ceilings, not a rack for mounting servers and other networking devices.

See Also: *cabinet, cabling*

RADIUS

Stands for Remote Authentication Dial-In User Service, an industry-standard security protocol for dial-up data networking services.

See: *Remote Authentication Dial-In User Service (RADIUS)*

RADSL

Stands for Rate-Adjusted Digital Subscriber Line, a Digital Subscriber Line (DSL) technology.

See: *Rate-Adjusted Digital Subscriber Line (RADSL)*

RAID

Stands for redundant array of independent disks, a group of technologies that enhance the performance and/or fault tolerance of disk storage systems.

See: *redundant array of independent disks (RAID)*

RAIT

Stands for redundant array of independent tapes, a technology that enhances the fault tolerance of tape backup systems.

See: *redundant array of independent tapes (RAIT)*

Rate-Adjusted Digital Subscriber Line (RADSL)

A Digital Subscriber Line (DSL) technology.

Overview

Rate-Adjusted Digital Subscriber Line (RADSL) is similar to Asymmetric Digital Subscriber Line (ADSL) but it also includes support for real-time allocation of bandwidth based on line quality. This makes RADSL more flexible and reliable than traditional ADSL, as it can accommodate changing line conditions to ensure that traffic is efficiently transported. Like ADSL, RADSL is an asymmetric technology that typically supports speeds up to 7 megabits per second (Mbps) in the downstream direction and up to 1.5 Mbps upstream.

See Also: *Asymmetric Digital Subscriber Line (ADSL), Digital Subscriber Line (DSL)*

RBOC

Stands for Regional Bell Operating Company, a large incumbent telco.

See: *Regional Bell Operating Company (RBOC)*

Rcp

A UNIX command for copying files to or from remote hosts.

Overview

Rcp is one of the popular r-commands available on all UNIX platforms. Rcp uses Transmission Control Protocol (TCP) to ensure reliable delivery of data between the client and the host. Rcp can be scripted in a batch file and does not require a password. The remote host must be running the rshd service, and the user's username must be configured in the remote host's .rhosts file.

Rcp is implemented on the Microsoft Windows 2000, Windows XP, and Windows .NET Server platforms, but this version includes only rcp client software and not rshd services.

See Also: *Transmission Control Protocol (TCP), UNIX*

RDP

Stands for Remote Desktop Protocol, a protocol for terminal-based computing.

See: *Remote Desktop Protocol (RDP)*

Recreational Software Advisory Council (RSAC)

A nonprofit organization with a content advisory system for Web sites on the Internet.

Overview

The system, known as RSACi (Recreational Software Advisory Council on the Internet), allows Web site administrators to rate their sites according to degrees of potentially objectionable content. There are four basic types of content, each with five levels, rated from 0 to 4. The content areas are Sex, Nudity, Violence, and Offensive Language.

By rating their Web sites according to the RSACi system, Web site administrators can help adults protect children from content that might be objectionable. Microsoft Internet Explorer has built-in client support for the RSACi system, which is administered using a password-protection scheme. Popular Internet portals such as America Online (AOL), Microsoft Network (MSN), and Yahoo! employ the RSACi system.

For More Information

Visit RSAC at *www.rsac.org.*

recursive query

A type of Domain Name System (DNS) query.

Overview

In a recursive query, the resolver contacts a name server to perform a name lookup, and the name server either returns a result or an error. The name server cannot refer the client to a different name server, but it can forward the query directly to another name server if it has a forwarder configured.

When a name lookup is performed on a name server, the resolver sends a recursive query to a nearby name server. If the name is outside the name server's zone of authority, the name server cannot resolve the name and returns an error unless it is also configured as a forwarder. If this is the case, the nearby name server performs an iterative query on a root name server, which then responds with the Internet Protocol (IP) address of a name server whose zone of authority includes the desired top-level domain. Further iterative queries are performed until the name is resolved into its IP address or an error is produced.

See Also: *inverse query, iterative query*

redirection

A process whereby a Web server forwards a request for a file to a different directory, Web site, or application.

Overview

Redirection enables client requests to always be fulfilled, even when content in a site is being updated or if the name of a virtual directory has been changed. For example, if you want to replace an old version of a page named old.htm with a newer version named new.htm, but you do not want to alter the navigational structure of your site or bother users with a notice of the change, you can enter a <META> tag in the <HEAD> section of the old.htm file to redirect browsers to the new page.

Examples

For example, the following tag in the <HEAD> section of the old page causes a browser accessing that page to be redirected to the new page after viewing the old page for 3 seconds:

```
<META HTTP-EQUIV="REFRESH"
CONTENT="3;URL=NEW.HTM">
```

You can place a notice on the old page such as, “This page will be redirected to its newer version after 3 seconds.”

Notes

The term *redirection* is also used in printing. For example, if you are trying to print some documents but a print device has failed, Microsoft Windows 2000, Windows XP, and Windows .NET Server let you redirect all outstanding jobs for the print device to another print device that uses the same printer driver as the failed device. To redirect your pending documents, follow these steps:

1. Open the property sheet for the failed print device and select the Ports tab.
2. Click the Add Port button, select Local Port, select New Port, and enter the Universal Naming Convention (UNC) path for the second print device.
3. Click OK, and then click Apply.

See Also: *Web server*

redirector

A networking component on a client machine enabling the client to access shared network resources.

Overview

The function of a redirector is to make it appear to the client that shared network resources are located on the local machine instead of elsewhere on the network. On a machine running Microsoft Windows 2000, the Workstation service is the default redirector. However, you can install multiple redirectors in Windows 2000 if you need to provide users with connectivity to different file systems.

The Windows 2000 redirector is implemented in the form of a file system driver. When a client program requests a network resource, the request is handed to the I/O Manager, which calls the redirector. The redirector translates the request into Server Message Block (SMB) requests for transmission over the network to the Server service on the remote computer.

See Also: *Server Message Block (SMB)*

redundant array of independent disks (RAID)

A group of technologies that enhance the performance or fault tolerance, or both, of disk storage systems.

Overview

Redundant array of independent disks (RAID) technologies were conceived in the late 1980s as a way of preventing input/output (I/O) and disk storage from becoming the bottleneck in the emerging PC architecture. This was because at the time, processor and memory technologies were growing exponentially while capabilities and costs of disk storage were changing only incrementally. The original meaning of RAID was “redundant array of inexpensive disks,” which highlighted the original purpose of RAID technologies as a means of utilizing the relatively low cost of commodity PC disk drives to provide storage solutions comparable to much more expensive mainframe disk storage platforms. By utilizing such technologies as mirroring, striping, and parity, RAID solutions soon emerged as the storage platform of choice for the PC server platform, a place which it still holds today, since RAID technologies have become integrated into network attached storage (NAS) and storage area network (SAN) technologies as well.

Types

The various levels of RAID that are currently defined include the following:

- **RAID 0:** Also called disk striping, this approach sees data written across the group of drives in stripes. Such “stripe sets” do not support any fault tolerance, but they do provide fast read/write performance. RAID 0 is most frequently employed in an environment where very large files (such as video or medical imaging files) need to be saved and read.
- **RAID 1:** Also called disk mirroring, this method has data written simultaneously to two (or more) disks, making one disk drive a mirror image of the other. Using mirror sets improves read performance slightly but has no effect on a single disk system for write performance. RAID 1 is frequently used for mission-critical servers such as authentication servers and e-commerce servers.
- **RAID 2:** Sometimes referred to as disk striping with error checking and correcting (ECC) or Hamming Code ECC, in this method information is striped (written across) bitwise across several disks and error checking information is calculated and written to a specially designated disk. RAID 2 has slow I/O and is rarely used.
- **RAID 3:** Sometimes known as disk striping with parity or parallel transfer with parity, in this approach data is striped to a disk set and parity information is written to a single disk for error recovery. I/O performance is not good and this method is rarely used nowadays.
- **RAID 4:** Sometimes referred to as disk striping with large stripes, here entire records are written to single drives, and parity information is stored on a single disk for error recovery. Write contention makes this method undesirable in most situations, and it is rarely used.
- **RAID 5:** Also known as disk striping with parity, here both the data and parity information are striped across all disks in stripes to provide full data recoverability in case any single drive fails. Disk striping with parity is an excellent way to protect data from the downtime caused by disk failures and is widely used in enterprises of all sizes. RAID 5 requires a minimum of three disks in order to work.
- **RAID 6:** Sometimes called disk striping with two parity schemes, this is an extension of RAID 5 that has additional fault tolerance built in and is designed to protect data against multiple simultaneous failed disk drives. Interest in this technology is growing in the enterprise networking arena, especially for high-availability e-commerce sites.
- **RAID 10:** Sometimes known as disk striping with disk mirroring, this is an expensive solution that has the same level of fault tolerance as RAID 1 together with the rapid I/O support of RAID 0. It is not commonly used due to the high cost of implementing it (every disk in the stripe set must be mirrored with a second disk). The “10” in RAID 10 is really 1+0 and the technology is sometimes called RAID 1+0 or RAID 0+1 to indicate more clearly what it is about.
- **RAID 53:** Sometimes called disk striping of stripe sets, this approach uses a stripe set (RAID 0) of individual RAID 3 disk arrays. RAID 53 has the same level of fault tolerance as RAID 3 and is very expensive and therefore not commonly used. The name RAID 53 is something of a misnomer, since one might more likely guess the designation to be RAID 30 = RAID 3+0.

Implementation

The two basic approaches to implementing RAID are

- **Software RAID:** This involves adding multiple Small Computer System Interface (SCSI) drives to the motherboard of a PC server and managing these drives as a RAID system using specialized software such as the built-in RAID support of Disk Management in Microsoft Windows 2000 Server, Windows XP, and Windows .NET Server.
- **Hardware RAID:** This utilizes separate storage units with dedicated I/O and integrated processing to provide better performance than software RAID but at a higher price. Popular hardware RAID 5 units often have hot-rebuild, hot-swap, and hot-spare capabilities to protect business-critical data and ensure high availability.



RAID. *The three common RAID technologies.*

Prospects

Different vendors have proposed a number of other RAID levels, including RAID 6, which employs high-speed caching and a real-time embedded operating system to support asynchronous transfers, and RAID 1+5, which combines the features of both mirroring and striping with parity. Land-5's RAIDn technology is one example of RAID 1+5, and this technology is expected to make inroads in the enterprise over the next few years. The most popular RAID levels, however, are still RAID 0, 1, and 5, and Windows 2000 Server supports all three of these storage technologies.

Another emerging approach is to integrate hardware RAID directly onto the motherboards of servers. This approach is expected to yield commodity PC servers costing less than $1,000 with built-in hardware RAID levels 0, 1, and 5 support.

For More Information

Visit the RAID Advisory Board at *www.raid-advisory.com.*

See Also: *fault tolerance, storage*

redundant array of independent tapes (RAIT)

A technology that enhances the fault tolerance of tape backup systems.

Overview

What redundant array of independent disks (RAID) is for disk storage technology, redundant array of independent tapes (RAIT) is for tape drives. RAIT employs multiple tape drives working together in synchronization to stripe incoming data across multiple backup tapes simultaneously. This provides a speed advantage for writing data to tape but poses some issues in the area of reading or modifying information stored on tapes. For example, the archived data is not accessible unless all of the tapes are available to be read. Furthermore, if even one byte of a large archived file needed to be modified, the entire file would need to be rewritten. However, data archived to tape rarely needs to be modified, but rather read for restore purposes.

To overcome this reading limitation, RAIT 5 was developed, the counterpart of RAID 5 stripe set with parity disk storage technology. RAIT 5 distributes parity information across multiple tapes in a RAIT system. Then, when data needs to be restored from tape, this can be done even if one tape is corrupt or missing. The restore process will be slow, but the fault-tolerant aspect of RAIT 5 is appealing to large enterprises that need to archive large amounts of data to tape.

See Also: *backup, redundant array of independent disks (RAID), tape drive*

Regional Bell Operating Company (RBOC)

A large incumbent telco.

Overview

Regional Bell Operating Companies (RBOCs) are regional telcos that were created as a result of the 1983 divestiture of the American Telephone and Telegraph (AT&T) telephone system, also known at the time as the "Bell System" or "Ma Bell." The divestiture divided the telephone company landscape into two parts:

- **Incumbent Local Exchange Carriers (ILECs):** These carriers owned the local loop in their particular coverage areas and provided local telephone services to their subscribers. The divestiture was done to end AT&T's monopoly over the U.S. telephone system. The company was broken up into several dozen smaller Bell Operating Companies (BOCs), each of which was to supply telephone services to local loop subscribers in a given geographical area. Seven larger Regional Bell Operating Companies (RBOCs) were also created, each consisting of two or more BOCs. In addition to the BOCs and RBOCs, dozens of small independent LECs also serviced different areas of the country. The seven original RBOCs were Ameritech, Bell Atlantic, BellSouth Corporation, Nynex, Pacific Bell Telephone Company (PacBell), Southwestern Bell Telephone Company, and US West.
- **Inter-exchange carriers (IXCs):** These companies provided long-distance services for subscribers through the ILECs' local loop. AT&T was left to function as the first IXC, and is joined today by Sprint Corporation and Worldcom to form the "big three" long-distance carriers.

The telephone systems landscape began to change with the passage of the Telecommunications Act of 1996. The act allowed RBOCs and independent LECs to compete with existing IXCs for long-distance carrier business, allowed mergers between telephone companies depending on FCC approval, and essentially opened up the telecommunications market to all kinds of companies, including cable television companies.

Of the seven original RBOCs, only four remain today:

- **SBC Communications:** This company merged with Ameritech and PacBell and is the largest RBOC.
- **Verizon Communications:** Formerly called Bell Atlantic, this company merged with Nynex and GTE and then renamed itself Verizon, and is the second largest RBOC.
- **Qwest Communications:** This company bought US West.
- **BellSouth:** This is the only remaining original RBOC.

Prospects

Some RBOCs—Verizon and SBC, in particular—are beginning to compete in the long-distance market long controlled by the IXCs, at least in their home states. Alignments between RBOCs are also occurring, such as the Cingular venture between BellSouth and SBC, which created the second largest wireless network in the United States. (Verizon, which bought Vodafone, has the largest such network, and AT&T is in third place).

Some industry analysts see the consolidation in the RBOC market as an indication of the failure of the Telecommunications Act of 1996, since the legislation was intended to foster competition and diversify the telecom landscape rather than lead to greater consolidation and fewer choices for consumers. However, the "Big Four" RBOCs are now large enough to be in a position to compete with the “Big Three” IXCs, and the eventual result will hopefully be a wider variety of services and lower prices for business and residential consumers.

The Competitive Local Exchange Carrier (CLEC) “bubble” of the late 1990s has largely burst, and many CLECs have been acquired by RBOCs, IXCs, or other communication companies. CLECs, which were mostly startups reselling Digital Subscriber Line (DSL) services obtained from RBOCs, depended upon the goodwill of RBOCs for obtaining access to telco central offices (COs) to colocate their switching equipment, and some RBOCs were frequently uncooperative in this regard, putting many CLECs in an untenable business position. The result is that the DSL market is now dominated by the RBOCs, with SBC, Verizon, and Qwest being the top three in this market. SBC partnered with CLEC Covad Communications to gain top position in the DSL market, and Verizon acquired NorthPoint Communications for similar purposes. Qwest (through US West) and SBC are also extending DSL services beyond their own home regions.

From an enterprise networking perspective, most large businesses have a kind of love-hate relationship with their RBOC. They love the reliability of RBOC telecommunication services that have matured over many years but hate the high prices and being locked into a single vendor. RBOCs are often slow to provision new high-speed data services, and offer services such as T1 (1.5 megabits per second [Mbps]) and T3 (45 Mbps) but provide few intermediate options between these services. Although the RBOCs will undoubtedly reign supreme in the residential consumer market for years to come, they face stiff competition to their control of the local loop from the new metropolitan Ethernet providers such as Yipes Communications, which has rolled out fiber-based Gigabit Ethernet (GbE) metropolitan area networks (MANs) in large urban areas around the United States.

See Also: *central office (CO), Competitive Local Exchange Carrier (CLEC), Incumbent Local Exchange Carrier (ILEC), inter-exchange carrier (IXC), metropolitan Ethernet, T-carrier, telco*

registration authority (RA)

A company or organization that is responsible for receiving and validating requests for digital certificates and public/private key pairs.

Overview

A registration authority is part of a public key infrastructure (PKI) for implementing public key cryptography. The RA receives a certificate request and verifies the identity of the requestor using acceptable forms of identification, which can be communicated face to face, over the telephone, by mail or courier, or in another secure fashion that is acceptable to the RA. Identification can include a driver’s license, Social Security number, or another unique identifier for the requestor. If the RA approves the request, it contacts the certificate authority (CA) in the PKI and asks it to issue the requestor the desired digital certificate and key pair. The RA and CA are often different entities within the same company or organization.

See Also: *public key cryptography, public key infrastructure (PKI)*

registry

The database containing configuration information on Microsoft Windows platforms.

Overview

The registry is a hierarchical database in which Windows stores information such as configuration information for installed hardware and software, registered document types, user profiles, property settings for icons, and ports being used. The registry in 32-bit versions of Windows replaces the INI files, such as Win.ini and System.ini, that were used in the 16-bit versions Windows 3.1 and Windows for Workgroups 3.11.

Implementation

The registry in Windows 2000, Windows XP, and Windows .NET Server is logically divided into five subtrees, each containing a hierarchical collection of keys and subkeys (analogous to folders and subfolders in a file system) that themselves contain values (analogous to files). Physically, the registry consists of a series of hives and their associated transaction files located in %SystemRoot%\system32\config.

In Windows 98 and Windows Millennium Edition (Me), the logical structure is similar to that of Windows 2000, Windows XP, and Windows .NET Server, but the physical format is incompatible. A sixth subtree called HKEY_DYN_DATA is created dynamically and is used for performance measuring and Plug and Play configuration. The registry consists of dynamic information stored in RAM (random access memory) and two files in the %Win_Root% directory: system.dat, which stores computer-specific information, and user.dat, which stores user-specific information.

Notes

The main tool you should use to modify the registry is Control Panel, which provides a number of utilities for safely configuring different aspects of the system's hardware and installed software. If you want (or need) to dig deeper into the registry, use the registry editor. You can use the regedit or regedt32 tools instead, but do so carefully—a single wrong value can render your operating system unbootable!

relative path

The hierarchical path that locates a file or folder on a file system starting from the current directory.

Overview

The relative path is different from the absolute path, which locates the file or folder starting from the root of the file system. For example, if the current directory is C:\Windows, the relative path to the executable for the game of Solitaire, which is located in the current directory, is simply the name of the executable—sol.exe. If the current directory is C:\Windows\System, the relative path to Solitaire is ..\sol.exe.

In a UNIX file system, the syntax for relative paths is similar, except that it uses forward slashes instead of backslashes to separate levels in the file system hierarchy.

Notes

The idea of a relative path is also used in other naming contexts. For example, in Active Directory directory service of Microsoft Windows 2000 and Windows .NET Server, you can uniquely and globally specify directory objects using the object's distinguished name, which provides a kind of absolute path within the directory starting at the root and terminating at the desired object. For example, the object representing the user Mitch Tulloch in the domain northwind.expedia.com has this distinguished name:

```
DC=com,DC=expedia,DC=northwind,
OU=Users,CN=Mitch Tulloch
```

If a search context is established as the Users container within the northwind.expedia.com domain, the relative distinguished name of the Mitch Tulloch object is simply

```
CN=Mitch Tulloch
```

This relative distinguished name uniquely identifies the desired object within the Users container in Active Directory.

See Also: *absolute path*

remailer

A Web site that lets you forward e-mail messages anonymously.

Overview

Remailers can be used to ensure the privacy of your e-mail address when you send someone e-mail. This is because when a remailer is used to forward a message, all the original message header information is stripped away. The result is that the recipient has no way of determining who originally sent the message. You could use a remailer, for example, to keep recipients from adding your address to a mailing list. You can also use remailers to prevent yourself from being spammed when you voice an unpopular opinion on a mailing list or some other forum.

Another name for this kind of site is anonymous remailer. Yahoo! has a list of Web-based anonymous remailers.

See Also: *e-mail*

remote access

Technology that enables access to network resources from remote locations.



Remote access. *The two kinds of remote access.*

Overview

Remote access is an umbrella term for a group of technologies that enables

- administrators to manage servers, routers, and resources on a network from a remote location
- off-site and mobile users to securely access resources on their corporate networks

Types

There are two basic approaches to remote access:

- **Remote control:** Allows administrators to take control of remote computers and enter keystrokes, issue mouse clicks, and view display output as if they were sitting at the computer's local console. A popular software platform from Symantec Corporation called pcAnywhere is the leader in this category of the enterprise market; it enables administrators to remotely troubleshoot server problems, make configuration changes, and even demonstrate procedures to remote users—in other words, to perform all aspects of remote administration. Provided there is enough bandwidth in the connection, remote control technology usually works well, but when bandwidth is scarce, access to the remote console may be slow and jerky. Remote control access has high security, saves on hardware and licensing costs, and is relatively easy to implement on a network. Microsoft Windows 2000 Server, Windows XP, and Windows .NET Server have their own built-in remote control technology called Terminal Services (TS), which allows up to two concurrent connections for remote control.
- **Remote node:** This is the classic form of remote access and is usually simply referred to as "remote access." In this scenario, a remote access device, such as a router or remote access server (RAS), is used to provide a gateway for remote users to access file, print, and other services on a corporate network—for example, using a laptop and modem. Another remote node scenario is the situation in which a remote branch office accesses resources at company headquarters using a RAS over a leased line or dial-up Integrated Services Digital Line (ISDN) connection. Remote node devices are often computers running specialized remote access software such as the Routing and Remote Access

Service (RRAS) component of Microsoft Windows 2000 and Windows .NET Server. For supporting multiple remote dial-up users, servers can be fitted with a multiport serial board with 4, 8, 12, or more asynchronous communication ports that are connected to an analog modem bank or an ISDN terminal adapter. These machines are sometimes called RAS routers because they have at least one local area network (LAN) and one wide area network (WAN) interface and therefore function essentially as a router. Traditional software routers and LAN switches with ISDN or T1 capability are also frequently used as remote access devices, and these are also sometimes known as access servers. For additional security and ease of use, remote node devices can also include features such as network address translation (NAT), Dynamic Host Configuration Protocol (DHCP) server functionality, password-based authentication, callback, and basic firewall functionality.

Notes

A relatively new solution to the issue of remote access to corporate networks is the concept of the virtual private network (VPN). A VPN is generally a dial-up connection that is tunneled over the Internet to allow remote users to access resources on the corporate network or to allow administrators to remotely administer servers, routers, and other devices. The VPN solution has largely displaced traditional remote node services for mobile users because it allows users to dial in to a local Internet service provider (ISP) and save the long-distance costs associated with dialing in directly to a modem bank connected to a corporate RAS server from a remote location.

See Also: *Integrated Services Digital Network (ISDN), leased line, modem, remote administration, remote control, virtual private network (VPN)*

remote administration

Administering servers, routers, and other network resources from a remote location.

Overview

Remote administration technologies are widely used in today's 24x7 enterprise networks. The capability for administrators to connect to and remotely administer servers while off site when problems arise is essential. Also important is being able to step in and assist remote branch offices in administering their resources over wide area network (WAN) connections.

Types

There are two main approaches to remotely administering enterprise servers: software-based and hardware-based remote administration.

The software-based approach can employ a variety of tools and technologies that enable administrators to do everything from managing permissions on shared folders to actually taking control of a remote machine to configure applications or perform a reboot. Some of the popular platforms and products in this area include

- **Remote node software:** This software provides remote access capability to allow administrators to access shared resources on the remote network. An example here is the Routing and Remote Access Service (RRAS) component of Microsoft Windows 2000 or Windows .NET Server.
- **Remote control software:** This software allows users to actually take control of a remote machine and issue keystrokes or utilize the mouse pointer to do anything a user could do using the machine's local console. The most popular example in this category is Symantec Corporation's pcAnywhere platform, which is widely used in the enterprise for remote control and file transfer. Other popular choices include the Terminal Service (TS) component of Windows 2000 Server, Windows XP, Windows .NET Server, and Citrix Systems' MetaFrame platform. Even some platforms that were originally developed for hacking purposes, such as Back Orifice from Cult of the Dead Cow, have come to be considered legitimate and powerful tools for remote control and administration of servers.
- **Built-in tools:** Widely available tools such as Telnet and Secure Shell (SSH) enable administrators to log in and remotely configure servers, routers, and

local area network (LAN) switches from a command prompt window. Routers and switches, in particular, frequently support another form of remote administration called out-of-band management (OBM), which allows administrators to dial into these devices using a modem connected to an RS-232 serial port on the device and then configure the device using a terminal program such as Microsoft HyperTerminal.

- **Web-based administration:** Some software platforms include support for secure remote administration over the Internet using a standard Web browser. For example, Internet Information Services on Windows 2000 includes an Active Server Pages (ASP) application that allows administrators to remotely configure Internet Information Server (IIS) Web servers using a Web browser such as Microsoft Internet Explorer.

The other variety of remote administration technologies includes various hardware-based solutions such as

- **Access servers:** These are generally routers that provide remote access functionality to allow administrators to access resources on a remote network and manage them.
- **Vendor cards:** These are vendor-specific Peripheral Component Interconnect (PCI) cards that can be installed in the vendor's servers to provide remote control management capability. These cards are proprietary for the platform they are designed for and can be accessed even when the server is down or its operating system crashes. Such cards typically include keyboard and mouse ports that can be connected to the server's keyboard and mouse ports and an Ethernet port for connecting to the network. Examples include Hewlett-Packard's TopTools card and Compaq Computer Corporation's Remote Insight, Lights-Out Edition.
- **External keyboard video mouse (KVM) devices:** These range from stand-alone KVM switches to KVM cards that can be inserted into a separate server. This approach has the advantage over vendor cards in that a single KVM device can be used to control multiple servers.
- **Code-operated matrix switches:** These are useful if remote servers simply need to be rebooted. A switch is connected to a device's power supply and can be controlled from a remote location by means of a computer and a modem.

See Also: *Keyboard Video Mouse (KVM) switch, out-of-band management (OBM), remote access, remote control*

Remote Authentication Dial-In User Service (RADIUS)

An industry-standard security protocol for dial-up data networking services.

Overview

The Remote Authentication Dial-In User Service (RADIUS) is a client/server protocol used to securely authenticate dial-up users. RADIUS supports authentication, authorization, and accounting (AAA), a security infrastructure supported by Cisco Systems' Internetwork Operating System (IOS) and by other platforms, including Microsoft Windows 2000 and Windows .NET Server. RADIUS is defined in RFCs 2138 and 2139.

Uses

Internet service providers (ISPs) commonly use RADIUS to provide business customers with secure dial-up connections. RADIUS can also be used to enhance security for virtual private networking (VPN), typically using Point-to-Point Tunneling Protocol (PPTP).

Implementation

RADIUS is a client/server protocol that involves three components:

- **RADIUS client:** Software installed on the network access server (NAS) that allows the client to make a dial-up connection to the remote network.
- **RADIUS server:** Software installed on a separate server that is used to store the profile information of dial-up users in a central database.
- **Dial-up client:** Software used by remote users to dial in and be authenticated by a RADIUS-enabled network.



Remote Authentication Dial-In User Service (RADIUS). *A typical implementation of RADIUS for an ISP.*

In a typical scenario, a user dials in to a NAS at an Internet service provider (ISP). The NAS server is the RADIUS client, and it takes the user's credentials and reformats them as RADIUS packets, which it then forwards to the RADIUS server, also located at the ISP. The RADIUS server can then either authenticate the user directly from its user profile database or act as a proxy client to forward the authentication request to some other type of service or security device.

Once the RADIUS server has authenticated the client, it sends a RADIUS Access-Accept message to the NAS to inform it that the user connection attempt should be allowed. RADIUS messages are sent as user datagram protocol (UDP) packets using port 1812 for authentication and 1813 for accounting messages. All messages sent between the RADIUS client and the RADIUS server are unencrypted, except for user passwords, which are encrypted. Note that from the dial-up user's perspective, the RADIUS client is the user's dial-in server.

An RFC-compliant RADIUS server stores all user profile information in a flat-file ASCII database that is accessible to any NAS that needs it to authenticate users. Some RADIUS servers can also employ UNIX password files, Password Authentication Protocol (PAP), Challenge Handshake Authentication Protocol (CHAP), Microsoft Challenge Handshake Authentication Protocol (MS-CHAP), third-party security systems, or Network Information Services (NIS) for authenticating users. RADIUS servers are often used as well to provide connection statistics for billing purposes.

Marketplace

RADIUS is supported by access servers from Cisco and other router vendors. RADIUS is also supported by Windows 2000 and Windows .NET Server, where the Internet Authentication Service (IAS) supports RADIUS server functionality and the Routing and Remote Access Service (RRAS) operates as the RADIUS client.

Note that RADIUS implementations from different vendors are often incompatible. Despite the fact that RADIUS is an industry-standard security protocol, many vendors have added features to their implementation that are non-RFC compliant. As a result, when implementing RADIUS in your enterprise it is usually best to stick with solutions from a single vendor.

Notes

Cisco has a proprietary protocol called Terminal Access Controller Access Control System (TACACS) that is similar to RADIUS in operation but includes additional security features. Besides RADIUS and TACACS, the third commonly used security protocol on Cisco access servers is Kerberos.

See Also: *AAA, Challenge Handshake Authentication Protocol (CHAP), Internet service provider (ISP), Internetwork Operating System (IOS), Kerberos, Microsoft Challenge Handshake Authentication Protocol (MS-CHAP), network access server (NAS), Password Authentication Protocol (PAP), Point-to-Point Tunneling Protocol (PPTP), Terminal Access Controller Access Control System (TACACS), security protocols, User Datagram Protocol (UDP), virtual private network (VPN)*

remote bridge

A bridge that connects two geographically separated networks.

Overview

Remote bridges can be used to connect networks using a variety of means, including telephone lines, leased lines, or a circuit-switched service such as X.25. A remote bridge generally has at least one

- Local area network (LAN) port, typically an RJ-45 jack to support an unshielded twisted-pair (UTP) connection to an Ethernet switch or a hub.
- Serial port, such as an RS-232 port or V.35 interface, for connection to the telco service used to link the networks.

A synchronous serial port is employed for connections to digital leased lines, and an asynchronous serial port is used for modems. Some remote bridges even have synchronous and asynchronous serial ports. Remote bridges also commonly support Simple Network Management Protocol (SNMP) and have various other diagnostic and support features, including out-of-band management (OBM).



Remote bridge. *Using remote bridges to connect two distant LANs together.*

To use remote bridges to connect remote LANs, connect a bridge to the main hub or switch in each LAN, and then connect the serial port on each bridge to the modem, Integrated Services Digital Network (ISDN) terminal adapter, or Channel Service Unit/Data Service Unit (CSU/DSU), depending on the type of wide area network (WAN) link used.

See Also: *asynchronous transmission, bridge, leased line, RS-232, serial transmission, synchronous transmission, V.35*

remote client impersonation

A technique for attacking or gaining improper access to a network.

Overview

Remote client impersonation takes place when a third party monitors traffic on a network by using a packet sniffer, captures network traffic during the user authentication process, extracts the authentication parameters (such as username, password, and domain) from the captured frames, and then takes control of the authenticated connection. Authentication schemes in which the user's password is transmitted in clear text, such as the Password Authentication Protocol (PAP) supported by Point-to-Point Protocol (PPP), are most susceptible to remote client impersonation and replay attacks. More secure PPP authentication schemes, such as the Challenge Handshake Authentication Protocol (CHAP) or the Microsoft version of that protocol (MS-CHAP), are preferable. CHAP guards against remote client impersonation by using the user's password to create an encrypted hash of a challenge string instead of passing the actual password during the authentication process. It protects against replay attacks by using a different, arbitrarily selected challenge string for each authentication attempt.

Notes

A similar hacking technique called a replay attack takes place when a third party monitors network traffic, captures a connection during the authentication process, and then plays back the client's captured response to obtain a new authenticated connection.

See Also: *Challenge Handshake Authentication Protocol (CHAP), hacking, Microsoft Challenge Handshake Authentication Protocol (MS-CHAP), network security, network troubleshooting, Password Authentication Protocol (PAP), Point-to-Point Protocol (PPP)*

remote control

Controlling a remote server as if from a local console.

Overview

Remote control platforms allow you to control computers as if you were actually sitting at the local console and typing in keystrokes or clicking the mouse. Such platforms are widely used in the enterprise to

- Enable help desk personnel to step in and take control of a user's machine to fix a problem or demonstrate a procedure
- Allow training personnel to walk students through a procedure without having to sit beside the student
- Enable administrators who are offsite to respond to emergencies by configuring or troubleshooting servers using their laptop or even a Personal Digital Assistant (PDA)

Implementation

The most popular forms of remote control technology are software platforms such as pcAnywhere from Symantec Corporation or ReachOut from Previo Software. To utilize such platforms, a small-footprint remote control client must first be installed on the server that is to be controlled. Other software in this category include the Terminal Services (TS) component of Microsoft Windows 2000 Server, Windows XP, or Windows .NET Server, the Citrix Metaframe platform from Citrix Systems, and the open source Virtual Network Computing (VNC) platform from AT&T Laboratories Cambridge.

There are also a number of hardware-based remote control platforms, including proprietary Peripheral Component Interconnect (PCI) cards such as TopTools from Hewlett-Packard and keyboard video mouse (KVM) solutions such as Key-View from Cybex Computer Products Corporation. These solutions are generally more expensive than software-based tools, but they provide better performance and can also reboot servers when they crash.

See Also: *remote access, remote administration*

Remote Desktop Protocol (RDP)

A protocol for terminal-based computing.

Overview

Remote Desktop Protocol (RDP) is a terminal communications protocol based on the industry-standard T.120 multichannel conferencing protocol from the International Telecommunication Union (ITU). RDP is a proprietary protocol developed by Microsoft Corporation and is sometimes referred to as the Remote Display Protocol. It was formerly known as the T.SHARE protocol.

RDP forms the basis of Terminal Services (TS), a component of Microsoft Windows 2000 Server that supports terminal-based computing. RDP controls the transmission of keystrokes, mouse actions, and display information between Windows 2000 terminal clients and terminal servers. The version of RDP used in Windows 2000 and Windows XP is RDP 5.

Implementation

RDP is a multichannel-capable protocol that supports up to 64,000 separate channels. RDP supports multipoint transmission and employs separate virtual channels for transporting different information over serial transmission links, specifically:

- Mouse and keyboard signals sent from client to server
- Presentation data sent from server to client

RDP supports encryption of data using the RC4 encryption algorithm, and can use 40-bit, 56-bit, and 128-bit key sizes for varying degrees of security. Higher key sizes provide greater security but require greater processing overhead.

See Also: *remote control, T.120, terminal server*

Remote Network Monitoring (RMON)

An extension to Simple Network Management Protocol (SNMP).

Overview

Remote Network Monitoring (RMON) lets you monitor network traffic on a remote Ethernet segment from a central location on the network to detect problem conditions such as traffic congestion, dropped packets, and excessive collisions. You can also use RMON to set network traffic thresholds that trigger alarms so that you can correct network problems before they happen. Embedded RMON in Ethernet switches lets network administrators monitor switched Ethernet networks that cannot easily be monitored using traditional packet-sniffing network analyzers.

RMON was developed in 1992 and defined in RFC 1271. This was later superseded by RFC 1513 for Token Ring networks and RFC 1757 for Ethernet networks. The RMON Management Information Base (MIB) defined in RFC 1757 specifies nine groups of manageable objects (RMON monitoring elements) for various aspects of network traffic monitoring, totaling 204 objects and 2 events. These groups of objects, usually referred to as the RMON 1 groups, are as follows:

- **Statistics (1):** Records statistics for Ethernet network interfaces (ports), including packets sent and received, bytes sent and received, the number of each type of packet, packets dropped, errors, and collisions
- **History (2):** Specifies the types of data being sampled and the frequency at which data is sampled and records the sampled data for later analysis
- **Alarm (3):** Lets you set thresholds and sampling periods to trigger alarms when specified network conditions arise
- **Host (4):** Records MAC addresses; the number of packets sent and received for broadcast, unicast, and multicast packets; the number of bytes sent and received; and the number of error packets for all hosts on the subnet
- **HostTopN (5):** Lets you list hosts according to ranking parameters, such as amount of traffic generated or number of errors generated
- **Matrix (6):** Records statistics for communication between pairs of hosts, such as their source and destination addresses and the number of bytes and packets sent and received
- **Filter (7):** Controls which kinds of packets the agent should capture, such as all packets larger than a certain size, all packets that match a specific bit mask, or logical combinations of individual expressions
- **Capture (8):** Lets you capture packets for collecting network statistics and configure capture buffer sizes
- **Events (9):** Lets you generate SNMP traps and log entries

It is a good idea to ensure that your RMON-enabled device or probe supports at least groups 1, 2, 3, and 9 from the previous list. Probes that support only these four groups are said to support mini-RMON. Many network hardware vendors provide RMON-enabled devices that support only mini-RMON because these are generally considered the most useful RMON groups.

The original RMON specification (now called RMON 1) collected data only from the physical (Layer 1) and data-link (Layer 2) layers of the Open Systems Interconnection (OSI) reference model. To overcome this limitation, which hinders RMON from being useful in switched networks (the original RMON was designed for shared media networks), a newer version called RMON 2 was developed in 1997 and defined in RFC 2021. RMON 2 extends the original RMON specification with nine more Management Information Base (MIB) groups that specify the collection of statistics from the network layer (Layer 3) through the application layer (Layer 7). Using RMON 2, network administrators can remotely collect information about the flow of data in a switched enterprise networking environment. For example, using RMON 2–enabled routers or switches, you could determine which workstations were accessing a specific client/server application on a specific server. RMON 2 is a superset of the original RMON MIB groups and extends them with an additional 268 manageable objects.

Comparison

RMON is similar in many ways to SNMP, for example:

- It employs the MIB format.
- It collects and reports network conditions to a network management station.

RMON differs from SNMP, however, in several significant ways, specifically:

- It supports caching of information gathered from supporting network devices.
- It provides much greater detail about the operation of network devices and the flow of traffic in and out of the device.
- It is more responsive to events occurring on the network. This is because RMON proactively sends the data it has collected instead of waiting to be polled by the network management station as SNMP generally does.
- It is an instrument-based network management protocol that utilizes specialized hardware, which can either be built into network devices or in stand-alone form as RMON probes.

Implementation

Like SNMP, RMON is implemented utilizing a MIB on RMON-enabled devices. These RMON-enabled devices may include

- Stand-alone devices called RMON probes that can be temporarily or permanently installed where desired on the network to study the flow of traffic on a local area network (LAN) segment. Such probes act much like traditional network protocol analyzers, except that they send the information they collect to a central location for analysis and display.
- Existing network devices such as repeaters, bridges, hubs, routers, or Ethernet switches that have RMON functionality embedded into their port circuitry in the form of RMON agent software.
- A stand-alone computer operating as an RMON probe.

An RMON probe consists of an SNMP agent for collecting information and communicating it to an SNMP management application, and one or more RMON MIBs defining the network objects to be managed. Typically, an SNMP-manageable device such as a hub or router only needs additional software installed on it to enable it to support RMON and turn it into a probe. Other devices called hosted probes are implemented as add-on hardware modules with built-in processing power and memory.

RMON is usually implemented on only one device or interface per network segment. For example, in a switched Ethernet environment, RMON agent software runs on each switch port to monitor and collect Ethernet network statistics for the attached segment. For RMON 1 these statistics relate only to the physical layer (Layer 1) and the data-link layer (Layer 2), but for RMON 2 they cover all layers of the OSI model.

When an SNMP management station wants to collect statistics to analyze and present them, the station contacts the RMON agents on the network. Alternatively (and more commonly), RMON agents are configured to send this information automatically when network traffic conditions on the device trigger the agent using SNMP traps.

Marketplace

The leading vendors of RMON probes and software include 3Com Corporation, Agilent Technologies, NetScout Systems, and Nortel Networks. Most vendors of Ethernet switch equipment also add RMON agent capability to the ports of their switches.

See Also: *Ethernet switch, Management Information Base (MIB), network management, Open Systems Interconnection (OSI) reference model, Simple Network Management Protocol (SNMP)*

remote procedure call (RPC)

A protocol that enables one computer to make a function call to another computer on the network.

Overview

Remote procedure call (RPC) is a message-passing programming technology developed by Sun Microsystems and later extended by the Open Software Foundation (OSF). RPC allows an application on one computer to execute procedures and interact with services on a remote computer over a network. RPCs are a common method of enabling client/server processing on the Microsoft Windows and on IBM AIX, HP-UX, Sun Solaris, and other UNIX platforms.

Although local procedure calls (LPCs) provide a mechanism for enabling the different components of an application located on a single computer to communicate with each other, RPCs enable message passing between the components of a distributed application that are located on different computers throughout a network. RPCs use a variety of other interprocess communication (IPC) mechanisms such as named pipes, mailslots, Windows Sockets, and NetBIOS to establish connections between the RPC client and RPC server components on different machines.

Notes

The remote procedure call service (RPC service), a component of the Windows 2000, Windows XP, and Windows .NET Server executive running in kernel mode, is responsible for message-passing between the client and server components of a distributed application—for example, between a client/server application such as Microsoft Outlook (client part) with Microsoft Exchange Server (server part). On a Windows 2000–based network, the server part of a distributed application first registers itself with the RPC Locator service. The client part of the application, which is on the local computer, can then query the RPC Locator service to determine the location of the required server part. A process called the remote procedure stub then packages the client’s function call into a suitable RPC message and sends it to the remote computer using the RPC Run Time process. At the remote machine, a process called the application stub receives the RPC message, unpackages it into a function call, and executes it, returning any resulting values to the client part in a similar fashion. From the viewpoint of the client portion of the application, the server portion appears to be on the same computer.

repeater

A device that extends a network by boosting a signal so it can travel farther.

Overview

Digital signals traveling on cables weaken with distance—a phenomenon known as attenuation. A repeater is a kind of digital amplifier that works at the physical layer (Layer 1) of the Open Systems Interconnection (OSI) reference model to regenerate (amplify) a signal so that it can travel farther. Repeaters come in various types for different network architectures and data communication technologies. Repeaters can also perform other functions, such as filtering out noise caused by electromagnetic interference (EMI), reshaping the signal, and correcting timing to remove jitter so that the signal can travel farther.

Uses

Repeaters are used in Ethernet and Token Ring networking to extend signal transmission over long runs of fiber-optic cabling in order to connect remote local area networks (LANs). Repeaters are also be used in mainframe environments to boost signals for serial transmission to remote terminals. Repeaters can also be used to join dissimilar media such as unshielded twisted-pair (UTP) cabling and thinnet, but they cannot be used to join dissimilar network architectures such as Ethernet and Token Ring.

Repeaters are an inexpensive way to extend a network. Some specific examples of how repeaters could be used include

- Joining two 16-megabits per second (Mbps) Token Ring networks in different buildings over distances up to 1.85 miles (3 kilometers) over multimode fiber-optic cabling or up to 12.5 miles (20 kilometers) over single-mode fiber

- Increasing the lobe length between a Token Ring main ring and a remote node
- Joining dissimilar 10Base2 and 10Base5 segments to form a single Ethernet LAN
- Boosting signals from mainframe controllers to 3270 terminals over coaxial or UTP cabling to support distances up to 1.55 miles (2.5 kilometers)
- Extending the operating distance of T1 lines by placing G.703 repeaters at 1.35-mile (2.2-kilometer) intervals
- Extending backbone fiber-optic cable runs in campus-wide LANs or metropolitan area networks (MANs)

Repeaters are also used in fiber-optic networks to amplify and regenerate light signals for long-distance cable runs. Repeaters do not block broadcasts, so if you connect two Ethernet segments using a repeater, you increase the size of the collision domain, which degrades overall network performance. For this reason, bridges and routers are often preferable to repeaters.

Notes

Up to two Class II Ethernet repeaters can be cascaded together to connect remote nodes that are up to 670 feet (205 meters) apart.

See Also: *electromagnetic interference (EMI), hub, jitter, Open Systems Interconnection (OSI) reference model, physical layer, signal*

replay attack

Also known as remote client impersonation, a hacking technique for attacking or gaining improper access to a network.

See: *remote client impersonation*

Request for Comments (RFC)

A document that describes Internet standards, protocols, and technologies developed by the Internet Engineering Task Force (IETF).

Overview

Any interested party can submit an RFC to the IETF for consideration as an Internet standard. The process for ratifying such proposals as standards is based on consensus rather than by committee. Once proposed, an RFC is reviewed by various technical groups and given one of five classifications:

- Required
- Recommended
- Elective
- Limited Use
- Not Recommended

Once an RFC is classified, it is discussed and tested by research and technical groups and individuals. To become an accepted standard it must pass through three stages:

- **Proposed standard:** Stable, well understood, and generally considered useful
- **Draft standard:** Stable enough to develop implementations of the standard in applications and networking technology
- **Internet standard:** Technically mature, widely implemented, and significantly beneficial to the Internet community

RFCs are sequentially numbered and published by the RFC Editor at the Information Sciences Institute at the University of Southern California. Since 1969, over 3000 RFCs have been proposed and published on various networking protocols, procedures, applications, and concepts.

Note that old RFCs are not updated, so several RFCs might relate to the same Internet protocol or technology, and some of them might be obsolete. To find the current RFC for a protocol or technology, see the Internet Architecture Board (IAB) Official Protocol Standard published quarterly by the IAB.

Examples

The table shows some of the more important RFCs for commonly used Internet protocols.

Some Important RFCs for Internet Protocols

Protocol	*RFC(s)*
ARP	826
DHCP	2131, 2132
DNS	1034, 1035
FTP	959
HTTP-1.1	2068
ICMP	792
IGMP	1112
IMAP4	2060
IP	791, 919, 922, 950
IPv6	1883
Kerberos	1510
LDAPv3	2251
MIME	2045, 2046, 2047, 2049
NetBIOS	1001, 1002
NNTP	977
OSPFv2	2328
POP3	1939
PPP	1661, 1662
PPP-CHAP	1994
PPP-MP	1990
RADIUS	2138
RMON	1757
RSVP	2205
SMTP	821, 822, 974, 1869, 1870
SNMP	1157
SNMPv2	1441
TCP	793
Telnet	854, 855
UDP	768

For More Information

Visit the RFC Editor at *www.rfc-editor.org.*

See Also: *Internet, Internet Engineering Task Force (IETF)*

reservation

An Internet Protocol (IP) address that is reserved for a specific computer by a Dynamic Host Configuration Protocol (DHCP) server.

Overview

A DHCP reservation contains the IP address to be leased and the MAC address of the computer it will be leased to. Reservations are often used for servers on a network, which normally should all have the same IP address. An alternative procedure is to manually assign these servers a static IP address. The advantage of using a reservation is that the IP address of the server is centrally managed in the database of the DHCP server, which means there is less chance of an address conflict.

On Microsoft Windows networks, reservations (or static IP addresses) are always recommended for

- Domain controllers
- Domain Name System (DNS) and Windows Internet Name Service (WINS) servers
- Non-DHCP clients
- Router interfaces

Notes

To create a reservation for a computer, you must know the MAC address of its interface. On computers running Windows NT, Windows 2000, Windows XP, or Windows .NET Server, you can enter **ipconfig** at the command prompt to determine this value; on computers running Windows 95 or Windows 98, you can enter **winipcfg** in the Run dialog box (which you access from the Start menu).

See Also: *Dynamic Host Configuration Protocol (DHCP), IP address, MAC address*

residential gateway

A broadband device that acts as a front end for a home network.

Overview

The rapid growth of the broadband Internet market, together with the increase of teleworking, has provided a fertile market for the emergence of a new breed of broadband access device: the residential gateway. This device either connects to or replaces your Digital Subscriber Line (DSL) modem and enables you to network together PCs and peripherals (sometimes even telephones and fax machines) using a variety of technologies including Ethernet, home phone line networking, or 802.11b wireless networking. Connectivity to the network varies with the type of architecture used and may be standard RJ-45 jacks, universal serial bus (USB) connections, PC adapter cards, or Personal Computer Memory Card International Association (PCMCIA) cards. Features of residential gateways include ease of use, integrated firewall, and virtual private network (VPN) pass-through to support secure teleworking.

Marketplace

Emerging players in the residential gateway market include 2Wire, Cayman Systems, 3Com Corporation, and even the consumer electronics company Panasonic. Some analysts expect the residential gateway market to exceed $5 billion by 2005.

See Also: *Digital Subscriber Line (DSL), RJ connectors, universal serial bus (USB), virtual private network (VPN)*

resilient packet ring (RPR)

An emerging technology for Synchronous Optical Networking (SONET).

Overview

Resilient packet ring (RPR) is a new SONET technology designed for implementation by metropolitan Ethernet service providers. It is designed to make more efficient use of the underlying ring-based fiber-optic cabling infrastructure of existing SONET networks used by carriers.

RPR is based on earlier proprietary technologies developed by Cisco Systems, Nortel Networks, and other high-end infrastructure vendors. The Institute of Electrical and Electronics Engineers (IEEE) is working with the new Resilient Packet Ring Alliance to standardize this new technology and ensure interoperability between equipment from different vendors.

Implementation

Traditional SONET in the metropolitan marketplace employs a dual-ring architecture. One ring is active and carries traffic in one direction only, while the other ring is inactive and is used for redundancy purposes. Should the first ring fail, traffic is routed almost instantaneously to the second ring and then travels in the opposite direction to the first ring. This rapid failover makes SONET an ideal technology for delay-sensitive traffic such as voice and video, but it is not especially critical in transport of data, which is rapidly approaching becoming the dominant form of traffic carried by SONET networks.

RPR employs both rings of the SONET infrastructure to carry traffic simultaneously. Should one ring fail, its portion of traffic is automatically switched to the second ring. Since this switchover could result in sudden congestion of traffic, RPR employs quality of service (QoS) in order to differentiate between voice traffic, which needs high priority due to its sensitivity to delay, and Internet Protocol (IP) packet traffic, which can be assigned low priority since it is less sensitive to delay.

Marketplace

RPR technologies have been around for several years but have been based on proprietary implementations by SONET equipment vendors. The efforts of the Resilient Packet Ring Alliance, however, are guiding these vendors toward developing interoperable standards. Some of the significant vendors involved in producing RPR equipment include Cisco Systems, Dynarc, Lantern Communications, and Nortel Networks.

See Also: *Institute of Electrical and Electronics Engineers (IEEE), metropolitan Ethernet, quality of service (QoS), Synchronous Optical Network (SONET)*

resolver

A Domain Name System (DNS) client.

Overview

A resolver is software running on an Internet Protocol (IP) host that enables the host to query a DNS name server in order to resolve a host name into its associated IP address. The resolver software enables the host to formulate and send a query to the name server, interpret the response from the name server, and pass this information to the application on the client that initially called the resolver software (for example, a Web browser).

On UNIX platforms using Berkeley Internet Name Domain (BIND), a resolver is a set of library routines that are linked to the client programs that need to use them. On Microsoft Windows platforms the resolver is a component of Transmission Control Protocol/Internet Protocol (TCP/IP) software installed on the machine.

See Also: *Berkeley Internet Name Domain (BIND), Domain Name System (DNS), host name resolution, name server*

resource

Also called network resource, any volumes, folders, applications, or devices that users need access to.

Overview

Examples of network resources include the following:

- **Shared folders and volumes:** Contain files that users need to access. Users can be granted different levels of permissions on these shares. For example, users might be given read-only permission for shares that contain administrative documents, modify permission for shares that contain workgroup documents, and full control permission for their own personal shared folders.
- **Shared printers:** Allow many users to print to a single print device. You can control access to the printer by using print permissions and by setting priorities and times for accessing printers.
- **Applications:** Allow users to access back-end applications (such as databases) using front-end clients. These applications can be standard .exe executables or scripted Web server applications such as those developed using Microsoft Active Server Pages (ASP) technology.
- **Web servers:** Allow Hypertext Markup Language (HTML)–based documents and applications to be shared and accessed from any platform by using a standard Web browser such as Microsoft Internet Explorer.
- **File Transfer Protocol (FTP) servers:** Allow files to be shared between different operating system platforms such as UNIX and Microsoft Windows.

See Also: *shared folder*

resource domain

In Microsoft Windows NT, a domain containing network resources.

Overview

Resource domains are part of a master domain model or multiple master domain model enterprise-level implementation of Windows NT. Resource domains simplify resource administration by separating the administration of resources from the administration of user accounts.

In a master domain model implementation of Windows NT, an account domain—or master domain—contains user accounts for every user in the enterprise and is usually located at corporate headquarters. Servers and workstations at branch offices belong to other domains called resource domains. A trust relationship is established so that each resource domain in the enterprise trusts the account domain. Users at branch offices who want to log on to the network simply log on to the account domain even though their workstations are located within resource domains. Administrators at branch offices are responsible for managing only the resources (file and print shares, Web servers, database servers, and so forth) for their own domain and are usually not involved in centralized account management from a domain perspective.

See Also: *account domain, master domain, trust*

resource record (RR)

An entry in a Domain Name System (DNS) zone file.

Overview

Resource records (RRs) are individual records (lines) in a DNS database or zone file on a DNS name server. RRs provide information about hosts on a Transmission Control Protocol/Internet Protocol (TCP/IP) network—for example, the DNS domain name, IP address, and particular function of the host. Depending on the platform used, you may be able to edit the zone file using a simple text editor or a graphical user interface (GUI)–based name server administration tool.

A typical RR consists of a series of fields separated by spaces. The most common type of RR is the address record, or A record, which maps the IP address of an IP host to its domain name. Other common types of RRs include CNAME, NS, PTR, SOA, and SRV records. The following table describes some important types of RRs.

Commonly Used DNS Resource Records

Record Type	*Description*
A (address)	Maps the IP address to the host name
CNAME (canonical name)	Creates an alias for a host name
HINFO (host information)	Specifies information about the host, such as operating system and central processing unit (CPU) type
MX (mail exchanger)	Indicates a Simple Mail Transfer Protocol (SMTP) host (mail forwarder)
NS (name server)	Indicates a DNS name server that is authoritative for the domain
PTR (pointer)	Points to another location in the DNS namespace
SOA (start of authority)	Indicates the name server that is authoritative for the domain
SRV (server)	Locates a host that can provide a specific network service

See Also: *Domain Name System (DNS), IP address, name server, Transmission Control Protocol/Internet Protocol (TCP/IP)*

Resource Reservation Protocol (RSVP)

A signaling protocol used for conveying quality of service (QoS) requests.

Overview

Resource Reservation Protocol (RSVP) is part of the IntServ architecture developed by the Internet Engineering Task Force (IETF) to enable QoS on best-effort networks such as Internet Protocol (IP) networks. RSVP allows hosts to reserve bandwidth between two endpoints along a routed network. RSVP does this by sending special messages to RSVP-enabled routers along the path, which then give traffic sent between these endpoints the requested priority to ensure performance and reduce delay. Note that all routers on a network must be RSVP-enabled in order for the protocol to achieve its goals.

RSVP operates at Layer 3 (network layer) of the Open Systems Interconnection (OSI) reference model and is therefore independent of the type of networking media and network protocols used. RSVP is designed to operate in large heterogeneous routed internetworks such as the Internet to provide QoS for high-priority traffic.

RSVP supports both multicast and unicast transmissions and is a soft-state protocol that requires periodic refreshing to maintain its configured service levels. RSVP is defined in RFC 2205.

See Also: *bandwidth, heterogeneous network, Internet Engineering Task Force (IETF), network layer, Open Systems Interconnection (OSI) reference model, quality of service (QoS), routing*

reverse hosting

An extension to reverse proxying that is supported by Microsoft Internet and Acceleration (ISA) Server.

Overview

Using reverse hosting, a proxy server can simulate the virtual roots on a number of Web servers and redirect requests for a particular domain and root combination to a single Web server. This approach means that only a single hole needs to be opened through the proxy server to allow Hypertext Transfer Protocol (HTTP) requests to enter. Reverse proxying works as an application layer proxy service and supports HTTP only.

See Also: *Hypertext Transfer Protocol (HTTP), Internet Security and Acceleration Server (ISA Server), proxy server, reverse proxy*

reverse name lookup

The process of using a host's Internet Protocol (IP) address to look up its Domain Name System (DNS) name.

Overview

Reverse lookup occurs when a resolver queries a name server to resolve another host's IP address into its associated fully qualified domain name (FQDN). This is the reverse of the usual host name resolution process, in which a resolver queries a name server to resolve a host name into its associated IP address. Reverse name lookups use a special domain called in-addr.arpa.

Uses

Reverse name lookups are used in a variety of circumstances. For example, when a Web browser contacts a Web server, the Web server obtains the IP address of the computer the browser is running on. The Web server software often uses a reverse lookup to try to resolve the client's IP address into its associated FQDN, usually for purposes of logging the Hypertext Transfer Protocol (HTTP) session.

See Also: *Domain Name System (DNS), fully qualified domain name (FQDN), host name resolution, Hypertext Transfer Protocol (HTTP), in-addr.arpa, IP address, name lookup, name server*

reverse proxy

A form of proxying where the proxy server impersonates the Web server.

Overview

In reverse proxying, a proxy server is used to impersonate a Web server to the outside world. The proxy server receives client requests for Web content and fulfills these requests from its cache. It forwards Hypertext Transfer Protocol (HTTP) requests from clients to the actual Web server only if it cannot serve the requests from its own cache.

Reverse proxying offloads Web publishing responsibilities from Web servers and allows you to securely connect a company's internal Web servers to the Internet or to the rest of the company intranet. Microsoft Internet and Acceleration (ISA) Server supports reverse proxying so that you can publish to the Internet without compromising your internal network's security. ISA Server uses reverse proxying to send client requests downstream to a Web server or group of Web servers that are located behind the proxy server. This configuration results in improved Web server capacity planning, protects the security of data while allowing access to the Internet, and allows Web servers to access other servers on the internal network for publishing purposes.

See Also: *Hypertext Transfer Protocol (HTTP), Internet Security and Acceleration Server (ISA Server), proxy server, Web server*

Rexec

A UNIX command for running commands on remote hosts.

Overview

Rexec is one of the r-commands available on all UNIX systems. In order for the remote execution of the command to work, the remote host must be running the Rexec daemon (service). Rexec authenticates the username on the remote host before executing the command and prompts the client to enter a password.

Microsoft Windows 2000, Windows XP, and Windows .NET Server include a Rexec client but no Rexec service. Rexec provides functionality similar to that of Rsh, except Rexec uses clear-text password authentication.

Notes

You cannot use Rexec to run interactive commands such as Vi or Emacs. Instead, use Telnet or Secure Shell to run interactive commands on a remote host. Note also that Rexec forwards the user's password as clear text, which can pose a security risk in some environments.

See Also: *daemon, Rsh, Telnet, UNIX*

RFC

Stands for Request for Comments, a document that describes Internet standards, protocols, and technologies developed by the Internet Engineering Task Force (IETF).

See: *Request for Comments (RFC)*

RG

Stands for Radio Guide, a U.S. Army specification for grades of transmission lines.

Overview

The RG specifications refer to forms of coaxial cable used, many of which were popular in computer networking in the 1970s and 1980s. Examples of RG specifications for coax include

- **RG-8:** Also known as N series cable, which is a coaxial cable with an impedance of 50 ohms. RG-8 looks like thicknet Ethernet cabling but is actually a lower grade and does not perform as well. True thicknet cabling is labeled as IEEE 802.3 cabling, has a diameter of 3/8 inches, and is yellow or orange.
- **RG-58:** Often called thinnet, which is a form of coaxial cabling with an impedance of 50 ohms and a diameter of 3/16 inches used in 10Base2 Ethernet networking. Subdesignations of this standard include RG-58 /U, which has a solid copper core, and RG-58 A/U, which has a stranded copper core.
- **RG-59:** Another name for CATV or cable television cabling, which is a form of coaxial cabling with an impedance of 75 ohms.
- **RG-62:** A form of coaxial cabling with an impedance of 93 ohms that is used in Attached Resource Computer Network (ARCNET) networks.

See Also: *coaxial cabling*

Rijndael

The underlying cryptographic algorithm used in the Advanced Encryption Standard (AES).

Overview

The National Institute of Standards and Technology (NIST) selected Rijndael as the encryption algorithm to be used for the U.S. government encryption standard called AES, which replaces the Data Encryption Standard (DES). Rijndael was developed by Belgian computer scientists Vincent Rijmen and Joan Daemen, and it can employ 128-bit, 192-bit, or 256-bit key lengths, making it considerably stronger and more secure than the 56-bit DES. Rijndael also has a very small footprint (52 bytes), making it portable for cell phones, Personal Digital Assistants (PDAs), and other small devices.

Rijndael will likely take several years to completely displace DES in government use. Triple DES, a much stronger variant of DES, is likely to coexist alongside Rijndael for an even longer period of time where it has been deployed.

See Also: *Advanced Encryption Standard (AES), Data Encryption Standard (DES), encryption*

ring topology

A networking topology in which network stations are connected along a single path whose ends are joined to form a circle.

Overview

Ring topology is employed only in specialized networking technologies, as opposed to the star topology employed in basic structured wiring systems of enterprise Ethernet networks. Common examples of where ring topology is used include

- **Token Ring networks:** The ring of a Token Ring network is concentrated inside a device called a Multistation Access Unit (MAU).
- **Fiber Distributed Data Interface (FDDI) networks:** The ring in this case is both a physical and logical ring and usually runs around a campus or collection of buildings to form a high-speed backbone network. Usually a dual-ring approach is used to provide redundancy.
- **Synchronous Optical Network (SONET):** Used primarily by telcos for metropolitan area network (MAN) trunk rings, this technology also typically employs a dual-ring structure for redundancy.

In some ring topology networks such as Token Ring networks the circle is sometimes only logical—the actual physical arrangement of the cabling might be starlike, with a hub or concentrator at the center. A network based on ring topology is sometimes called a ring network.



Ring topology. *Simple example of a ring network.*

See Also: *bus topology, mesh topology, star bus topology, star topology*

RIP

Stands for Routing Information Protocol, a popular distance vector routing protocol.

See: *Routing Information Protocol (RIP)*

RIPE

Stands for Réseaux IP Européens NCC, a nonprofit organization that administers the registration and allocation of numbers relating to the operation of the Internet in Europe, the Middle East, and parts of Africa.

See: *American Registry for Internet Numbers (ARIN)*

Rivest-Shamir-Adelman (RSA) algorithm

A popular algorithm for public key cryptography.

Overview

Rivest-Shamir-Adelman (RSA) is one of the most popular cryptographic algorithms in use today. Ron Rivest, Adi Shamir, and Leonard Adelman developed RSA in 1977 and RSA Security patented it in 1983. RSA is employed in many popular encryption technologies, such as Pretty Good Privacy (PGP), Transport Layer Security (TLS), Internet Protocol Security (IPsec), and for the Encrypting File System (EFS) in Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Implementation

RSA employs a variable-length key, with typical key size being 512 bits. A longer key can be used to enhance security, or a shorter one can be used to increase the efficiency of the encryption process. RSA also employs a variable-length block size. Block size represents the chunk of plaintext that is encrypted in one application of the algorithm, and this block size must be smaller than the key's bit length. Encryption of a block of plaintext results in a corresponding block of ciphertext whose length is equal to the size of the key.

Marketplace

Until recently, RSA has been a patented technology owned by RSA Security. As of January 2000, however, RSA is now in the public domain. Some analysts suggest that the general growth and acceptance of public key infrastructure (PKI) systems has been hindered by the need for companies to license RSA technologies from RSA Security—if so, this obstacle has now been removed.

Issues

RSA is a relatively slow algorithm compared to other popular encryption algorithms such as the Data Encryption Standard (DES) used by the U.S. government (now replaced by Advanced Encryption Standard, or AES). As a result, RSA is usually not used for encrypting messages. Instead, it is typically used to encrypt a secret key, and the secret key is then used to encrypt the message.

Another issue is that while 512-bit keys are commonly used in e-commerce sites employing RSA encryption, in late 2000 a Swedish team of computer scientists cracked 512-bit RSA encryption using only a single workstation running a number field sieve algorithm. As a result, RSA with 512-bit encryption is no longer considered secure; however, 1024-bit length keys are probably secure for the foreseeable future.

See Also: *Advanced Encryption Standard (AES), Data Encryption Standard (DES), Encrypting File System (EFS), Internet Protocol Security (IPsec), Pretty Good Privacy (PGP), public key cryptography, public key infrastructure (PKI), Transport Layer Security (TLS)*

RJ connectors

A family of push-and-click connectors for twisted-pair wiring in telephone and computer network environments.

Overview

RJ stands for Registered Jack, and the RJ standards define both jacks or receptacles (female) and plugs (male) connectors for different purposes. Some common types of RJ connectors include

- **RJ-11:** A 4-wire or 6-wire telephone-type connector that connects telephones to wall plates. RJ-11 supports up to six wires, but usually only four are used with the two-pair twisted-pair cabling commonly found in telephone cabling.
- **RJ-45:** An 8-wire telephone-type connector used with twisted-pair cabling for connecting computers, wall plates, patch panels, and other networking components. RJ-45 is the standard type of connector for both unshielded twisted-pair (UTP) and shielded twisted-pair (STP) cabling in star-topology Ethernet networks such as 10BaseT and 100BaseT4. RJ-45 is defined in International Organization for Standardization (ISO) standard 8877.
- **RJ-48:** An 8-wire telephone-type connector used with twisted-pair cabling for connecting T1 and 56-kilobyte (KB) digital data service (DDS) lines. RJ-48 uses the same jack as RJ-45 but uses a different pinning, with one pair of wires to transmit signals, one pair to receive signals, one pair for drain, and one unused pair (reserved for future use). RJ-48 connectors come in three varieties: RJ-48C and RJ-48X for connecting T1 lines and RJ-48S for connecting 56-KB DDS lines.

Implementation

The diagram shows RJ-11 and RJ-45/48 connectors, which are used to terminate both ends of UTP cabling. Pins are labeled 1 through 4 or 1 through 6 for 4-wire and 6-wire RJ-11, and 1 through 8 for 8-wire (four-pair) RJ-45/48. Cables can be either straight-pinned or cross-pinned, depending on their use. For example, a straight-pinned RJ-45-terminated UTP cable is used to connect a computer to a 10BaseT hub, while a cross-pinned cable or crossover cable is used to connect two computers directly or to connect two hubs.



RJ connectors. *Two common types of RJ connectors.*

The following table shows the pinning for these various cables, with the colored wires coded as follows:

Y = yellow

G = green

R = red

W = white

S = silver

OR = orange

BL = blue

BK = black

BN = brown

If these colors are combined in striped cables, the coloring is coded OR/W for orange/white or orange with white striping, and so on. RJ-11 and RJ-45 cables generally use solid-color wires, and RJ-48 cables are usually striped. Note that RJ-45 has two types of cross-pinning: 568A/B and Universal Service Order Code (USOC). If the pinning of a wire is listed as Y (1–4), it means that the yellow wire is connected to pin 1 at one end and to pin 4 at the other.

Types of Cable Pinning

Connector/Cable	*Pinning*
RJ-11 straight (4-wire)	Y (1-1), G (2-2), R (3-3), BL (4-4)
RJ-11 crossed (4-wire)	Y (1-4), G (2-3), R (3-2), BL (4-1)
RJ-11 straight (6-wire)	BL (1-1), Y (2-2), G (3-3), R (4-4), BK (5-5), W (6-6)
RJ-11 crossed (6-wire)	BL (1-6), Y (2-5), G (3-4), R (4-3), BK (5-2), W (6-1)
RJ-45 straight (8-wire)	BL (1-1), OR (2-2), BK (3-3), R (4-4), G (5-5), Y (6-6), BN (7-7), S (8-8)
RJ-45 USOC crossed (8-wire)	BL (1-8), OR (2-7), BK (3-6), R (4-5), G (5-4), Y (6-3), BN (7-2), S (8-1)
RJ-45 568A/B crossed (8-wire)	BL (1-3), OR (2-6), BK (3-1), R (4-5), G (5-4), Y (6-2), BN (7-8), S (8-7)
RJ-48C straight (8-wire)	OR/W (1-1), W/OR (2-2), (3-3) unused, BL/W (4-4), W/BL (5-5), (6-6) unused, BL drain (7-7), OR drain (8-8)
RJ-48C crossed (8-wire)	OR/W (1-4), W/OR (2-5), (3-3) unused, BL/W (4-1), W/BL (5-2), (6-6) unused, BL drain (7-7), OR drain (8-8)

See Also: *connector (device), International Organization for Standardization (ISO), shielded twisted-pair (STP) cabling, unshielded twisted-pair (UTP) cabling*

RMON

Stands for Remote Network Monitoring, an extension to Simple Network Management Protocol (SNMP).

See: *Remote Network Monitoring (RMON)*

roaming user profile

A user profile stored on a network server so the user can access her desktop from any computer on the network.

Overview

Roaming user profiles are a feature of Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server that allow users to roam about the network and access their desktop settings and folders from any machine. This is done by storing such roaming profiles in a centralized location on the network, such as a file server or domain controller. If the server on which the profile is stored is unavailable when the user logs on to the network, the locally cached copy of the profile stored on his or her workstation will be used instead.

The system administrator enables roaming profiles for users. A roaming profile that cannot be modified by the user is known as a mandatory user profile. Windows 98 and Windows Millennium Edition (Me) also support roaming profiles, but these are not compatible with Windows 2000, Windows XP, and Windows .NET Server profiles.

See Also: *local user profile, mandatory user profile, user profile*

root

The base of a hierarchical file system.

Overview

The root is the first element in the absolute path of a file or directory on the file system. In other words, the root directory of a file system is the starting point for the tree of directories and files that comprise the file system. The symbol used to represent this directory depends on whether the file system is on a Microsoft Windows or UNIX platform: Windows designates the root directory with a backslash (\), but UNIX employs a forward slash (/).

The term *root* is also used to refer to the highest-level entity in a directory. For example, the root of Active Directory directory service in Windows 2000 is the RootDSE object.

Notes

The term *root* can also refer to the user with the highest level of administrative rights, particularly on UNIX platforms. Other names for this user are SuperUser (also UNIX platforms), Supervisor (NetWare platforms), and Administrator (Windows platforms).

See Also: *Active Directory, file system*

root certificate

A digital certificate that attests to the identity of a certificate authority (CA).

Overview

Every CA requires a root certificate so that it can be "trusted" by entities that request digital certificates from it. If a client trusts the root certificate of a CA, it automatically trusts any other certificates that are issued by that CA. Root certificates thus form one of the foundations of public key cryptography. The root certificate is either signed by the CA itself (self-signed) or by a higher authority in a hierarchy of CAs in a public key infrastructure (PKI).

See Also: *certificate authority (CA), public key infrastructure (PKI)*

root domain

The highest-level parent domain in a domain tree.

Overview

Root domains form the basis of domain trees in an Active Directory directory service implementation of Microsoft Windows 2000 and Windows .NET Server. All other domains in the tree derive their Domain Name System (DNS) name from the root domain and form a contiguous namespace with the root domain. An example of a root domain name for a company called Adventure Works might be adventure-works.com. The root domain is the first domain you create when you implement Active Directory in an enterprise. All other domains you create derive their DNS name from the root domain.

Notes

If you plan to connect your network directly to the Internet, you should register your root domain name with a domain name registration authority. You can use separate external and internal root domain names in your enterprise network if you want to separate network resources that will be accessible to outside users on the Internet from network resources intended for internal company use only. You should register both the internal and external root domain names to prevent future naming conflicts. You should also use a firewall to protect the private domain from the Internet.


Root domain
adventure-works.com
Two-way trust
Two-way trust
alpineskihouse.adventure-works.com
northwindtraders.adventure-works.com

Root domain. *The root domain of a domain tree.*

You should select a root domain name before you implement Active Directory on your Windows 2000– or Windows .NET Server–based network. The name should be easily recognized by users in the outside world, and you should make sure that it is legally acceptable and does not violate existing trademarks or duplicate registered company names. Root domain names should be static and not subject to change.

See Also: *Active Directory, Domain Name System (DNS), domain tree*

root name server

A name server at the top of the Domain Name System (DNS).

Overview

Root name servers are those that can locate name servers that are authoritative for top-level domains such as .com, .org, and .net. Root name servers are the backbone of the DNS naming system and act as an ultimate authority when a local name server cannot resolve a name query. In fact, if all 13 root name servers on the Internet simultaneously failed, users would only be able to reach Web sites registered with local name servers. In other words, the Internet would no longer work and would essentially operate as thousands of small isolated islands. As a result, root name servers are spread out across the Internet for greater protection and are zealously guarded. Examples of root name servers include two belonging to the Military Network (MILNET), one to the National Aeronautics and Space Administration (NASA), several in Europe, one in Japan, and the remainder in the United States. More are likely to be deployed as the Internet grows in size and international reach.

See Also: *Domain Name System (DNS), name server*

routable protocol

A network protocol that can be routed.

Overview

Routable protocols are network protocols that use Layer 3 (network layer) addresses for forwarding packets to their destination. The most commonly used routable protocol today is the Transmission Control Protocol/Internet Protocol (TCP/IP), which is the protocol used on the Internet and in most enterprise networking environments.

Other routable protocols, now considered legacy protocols, include

- Internetwork Packet Exchange/Sequential Packet Exchange (IPX/SPX)
- Xerox Network Systems (XNS)
- DECnet
- AppleTalk
- Banyan VINES

Seldom-used network protocols that are not routable include

- NetBEUI
- Data Link Control (DLC)

Notes

A routable protocol is a network layer protocol that can be routed. A routing protocol, however, is something different: a protocol by which routers can communicate routing table information with one another. Do not get them confused!

See Also: *AppleTalk, Banyan VINES, Data Link Control (DLC), DECnet, NetBEUI, Transmission Control Protocol/Internet Protocol (TCP/IP), Xerox Network Systems (XNS)*

route

A path a packet travels across an internetwork and a command for displaying and configuring routing tables on routers.

Overview

The route a packet takes as it crosses an internetwork is the path, starting from the sending host to a neighboring router and then hopping from router to router until the packet reaches its destination host on some remote network. The process by which the best route to forward a packet is identified is known as routing.

Route is also a command that allows viewing and modification of entries in the internal routing table on an Internet Protocol (IP) host such as a Microsoft Windows 2000, Windows XP, or Windows .NET Server computer. This internal routing table contains routing information that determines how the computer delivers packets to local and remote hosts on the network.

Examples

Typing **route print** at the Windows command prompt displays the routing table of the local computer.

Typing **route add 172.16.25.0 mask 255.255.255.0 172.16.10.1 metric 2** adds a new route to the routing table, specifies that any packets destined for the network with network ID 172.16.25.0 should be forwarded to the router interface 172.16.10.1 in the local network, and specifies that packets sent along this route will traverse two hops on the network.

See Also: *hop count, router, routing, routing table*

router

A device used to connect or segment networks.

Overview

Routers are most often used in Transmission Control Protocol/Internet Protocol (TCP/IP) networks, the Internet being the prime example of a large routed network. Routers can be used either to connect many smaller networks into a larger network called an internetwork or to segment a large network into smaller subnetworks in order to improve performance or manageability. Routers are also sometimes used to join dissimilar media, such as unshielded twisted-pair (UTP) cabling and fiber-optic cabling, and different network architectures, such as Token Ring and Ethernet.

Routers can also be used to connect local area networks (LANs) to telecommunication services such as leased lines or Digital Subscriber Line (DSL). A router used to connect a LAN to a leased line such as a T1 line is often called an access server, and a router used to access DSL servers is known as a DSL router. These routers often support basic firewall functionality to filter out packets based on their source or destination network address. Such a device is sometimes called a packet-filtering router.

Routers generally block broadcast traffic and can thus prevent broadcast storms from slowing down the flow of traffic in a network. Routers are so complex that Cisco Systems, the major vendor of enterprise-level routers, has developed an operating system called Internetwork Operating System (IOS) that is devoted solely to managing routers.

Types

Routers can be either

- **Static routers:** These must have their routing tables configured manually with all network addresses and paths within the internetwork.

or

- **Dynamic routers:** These automatically create their routing tables by listening to network traffic and communicating with other routers.

Comparison

Routers are similar to bridges in that they both forward packets and can be used to either segment or join networks. However, routers use Layer 3 (network layer) addresses such as IP addresses to forward packets, but bridges employ Layer 2 addresses (MAC addresses) for this purpose. When should you use a bridge and when should you use a router? Use bridges to connect network segments that run the same network protocol—for example, to connect an IP segment to an IP segment. Also use bridges when you run legacy nonroutable network protocols such as NetBEUI on your network. On the other hand, use routers to connect network segments that run different network protocols—for example, to connect an IP segment to an Internetwork Packet Exchange (IPX) segment. Generally speaking, routers are more intelligent than bridges and improve network bandwidth by not forwarding broadcast packets to other networks. Finally, use routers when you want to connect your network to the Internet.


100BaseT4
switch
Fast
Ethernet
routers
Server
farm
Branch
office
T1 link
CSU/DSU
Corporate
headquarters
Stackable
100-Mbps
hubs
CSU/DSU
ISP
56-Kbps digital
data service
(DDS) line
Access
router
LAN
LAN
Sync
router
T1 CSU
Primary
T1 link
T1 CSU
ISDN
T/A
ISDN
T/A
Backup
ISDN link
(dialup)
LAN
Dual sync
router
Token Ring
LAN
Router
Ethernet
LAN

Router. *Some examples of typical uses for routers.*

Implementation

Routers work at the network layer (Layer 3) of the Open Systems Interconnection (OSI) reference model. They forward packets between networks on the basis of their destination logical addresses (IP addresses in the case of TCP/IP). Routers also route packets based on the available paths and their costs, thus taking advantage of redundant paths that can exist in a mesh topology network. To do this, routers contain internal tables called routing tables that keep track of the paths that packets can take as they move across the internetwork, along with the cost of reaching each remote network.

Because routers operate at a higher OSI level than bridges do, they have more powerful switching and filtering capabilities. They also generally require greater processing power, which results in routers usually costing more than bridges. Also, because routers use network addresses for routing packets, they can only work if the network protocol is a "routable protocol" such as TCP/IP or Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX). This is different from bridges, which are basically protocol-independent Layer 2 devices.

Marketplace

Cisco holds the dominant place in the high-end router marketplace, with over 88 percent of the market share. Cisco produces a wide variety of routers with varying capabilities for small, medium, and large enterprises. They also produce routers that are used to form the backbone of the Internet. Some common models of Cisco routers include

- **1600 and 1700 Series:** These are used primarily for small businesses to provide wide area network (WAN) access.
- **2600 Series:** These are standard routers for branch office access to corporate headquarters over WAN links.
- **3600 Series:** These are multifunction routers that can be used in branch/enterprise environments and are more powerful and flexible than the 2600 series.
- **7200 and 7500 Series:** These are high-end multiprotocol routers that support a wide variety of media and are used to build both collapsed backbones and WANs.
- **12000 Series:** These are heavy-duty router/switch combinations used in collapsed backbones and carrier networks.

Other popular router manufacturers include Nortel Networks, Juniper Networks, Ericsson, and 3Com Corporation.

Prospects

A few years ago it was thought that Layer 3 Ethernet switches (also simply called Layer 3 switches) would drive the router market out of existence. This has not entirely happened, despite the fact that such switches, being hardware-based, perform much better than traditional software routers. In the enterprise LAN arena, Layer 3 switches do indeed dominate now in collapsed backbones where routers once ruled in distributed backbones. But in the WAN access arena, routers are still going strong and it looks like they will be around for a long time, driven mainly by Internet service providers needing more routers to handle increased traffic.

Appearing on the horizon are terabit routers capable of forwarding 10^{12} bits per second (bps). These routers are intended mainly for use by telecommunications carriers in their backbone networks, and leading vendors include Cisco, Lucent Technologies, and Avici Systems. A startup called Hyperchip is even developing a petabit router capable of switching packets at 10^{15} bits per second, a speed equivalent to a million Gigabit Ethernet (GbE) ports! Such high-end routers are intended for the next generation of all-optical networks that are expected to emerge around 2005.

See Also: *dynamic routing, Ethernet switch, Internetwork Operating System (IOS), Layer 3 switch, Open Systems Interconnection (OSI) reference model, routable protocol, route, routing, routing algorithm, routing interface, routing metric, routing protocol, routing table, static routing*

router routing

Routing that occurs at the routers.

Overview

Routers are generally used to connect different networks together. Router routing is the process by which a router examines an incoming packet and determines which interface on the router to forward the packet to. This is different from host routing, which is routing that occurs at the host itself.

Usually the term *router routing* is simply abbreviated as *routing*. Whether this actually refers to host routing or router routing can usually be determined from the context of the discussion.

See Also: *host routing, router, routing*

routing

Forwarding packets from one network to another across an internetwork.

Overview

Routing is a method of joining multiple networks in a way that allows packets to travel from one network to the next. To do this, devices called routers are used to connect different networks. These routers accept packets destined to remote networks and forward them to the next step along the way.

Routing is only possible with network protocols that are "routable." Examples of routable protocols include

- **Transmission Control Protocol/Internet Protocol (TCP/IP):** The standard network protocol used on the Internet and in most enterprise networking environments today.
- **Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX):** A legacy protocol used in Novell Netware 2.x and 3.x platforms.

The rest of this article focuses on TCP/IP routing, which is the most common type.

Types

Routing can be classified in different ways depending on what is under consideration. For example, there is

- **Host routing:** This is routing that occurs at the host itself. Each host on an IP network normally maintains its own internal routing table. This table is used to determine whether to send a packet to the local network, to a specific router interface, or to the default gateway address.
- **Router routing:** This is routing that occurs at the routers that connect the various networks. Networks connected by routers are generally called subnets, although this term has a more precise meaning in the context of IP addressing. Most of the discussion below focuses on router routing, which is usually simply called routing.

Routing can also be classified according to how routers are configured to forward packets, specifically:

- **Static routing:** Administrators manually enter entries in router tables.
- **Dynamic routing:** Routing tables can be updated automatically when different routers communicate with one another using routing protocols.

Implementation

Routing takes place at the network layer (Layer 3) of the Open Systems Interconnection (OSI) reference model. In TCP/IP networking, this means that routing of packets is based on their destination IP addresses.

Routing takes place on a packet-by-packet basis and involves two steps:

- Determining the best route (path) over which the packet should travel to reach its destination host.
- Forwarding the packet to the appropriate remote network according to its destination IP address.

Forwarding of packets is handled independently by each router along the path the packet has to travel. In other words, the packet is forwarded across each successive "hop" until it arrives at its destination. Routers perform this forwarding using internal tables called routing tables, which contain information describing the potential paths that data can take to travel to remote networks. Between any two subnets on an internetwork there may be more than one route by which the packet can reach its destination. The information in the routing table, therefore, includes the metric (cost value) for each possible route to the destination, and the packet is usually sent along the path with the lowest cost. If two paths to the same destination have the same cost, the stream of packets can be load-balanced between the two routes. Each network traversed on a routed internetwork is called a subnet.

The value of the metric for a specific path depends on several factors. For example, the metric might be proportional to the number of routers that the packet stream must be switched through (the number of hops traversed), the delay or latency of packets when they are processed by each router, the amount of traffic congestion (load) at the router, the available bandwidth along a route, and even the relative reliability of the routers. For static routers, network administrators manually specify metrics for each path and enter them into routing tables, but for dynamic routers routing algorithms are used to automatically calculate metrics for each possible path. Dynamic routers do this by communicating with each other using special protocols called routing protocols. Examples of common routing protocols include the Routing Information Protocol (RIP) and the Open Shortest Path First (OSPF) protocol. Once the routing table for a static router has been properly configured (or once the tables of all dynamic routers have "converged" and stabilized), the router carries out its packet-forwarding function. The entire routing process works like this: if a local host wants to send a packet to a host on a remote network, the local host first checks its own internal routing table (host routing) to determine which nearby router to forward the packet to. The host then uses Address Resolution Protocol (ARP) to obtain the MAC address of the near-side interface of this router and sends the packet directly to this interface. This packet's header contains the destination host's logical network layer address (IP address). When the router receives the packet, it inspects this destination address and compares it to the information stored in its internal routing table to determine what to do with the packet. If the router cannot determine what to do with the packet, it simply drops the packet. Otherwise, it forwards the packet (router routing) to the destination host (if it is on a network connected to the router) or to a more distant router, which forwards the packet again until finally the packet reaches the network where its destination host resides. As the packet is forwarded from router to router across the internetwork, its network layer destination address remains the same, but its MAC address keeps changing to that of the next router interface along the path.

Issues

Routing in a network can suffer from a number of problems. One problem is the existence of routing loops, which occur when a packet passes through the same router more than once on a given trip. The result is that the packet loops until its lifetime decreases to zero and a router discards it. The originating host usually never knows that the packet was dropped and did not reach its destination. Routing loops occur most often in networks that use incorrectly configured static routers. Routing algorithms for dynamic routers can usually detect loops and reconfigure routing tables to eliminate them. Another problem is convergence. In a large internetwork using dynamic routers, it might take some time for a change in one router's tables to propagate to all other routers in the internetwork. In the meantime, temporary routing loops can occur and less efficient network paths might be chosen, resulting in more traffic congestion. Properly designed routing protocols and routers help avoid such issues and make routing a reliable process for building large internetworks from smaller networks.

See Also: *black hole, bridge, convergence, default gateway, dynamic routing, flooding, hop count, host routing, internetwork, Open Systems Interconnection (OSI) reference model, routable protocol, route, router, router routing, routing algorithm, routing interface, routing metric, routing protocol, routing table, static routing, subnet*

routing algorithm

A mathematical procedure that a dynamic router uses to calculate entries for its routing table.

Overview

Routing algorithms underlie the routing protocols that enable dynamic routers to exchange information with one another in order to calculate the metrics of various paths or routes throughout an internetwork. These algorithms generally operate using a combination of variables obtained either by inspecting header information in packets received by the router or manually specified by administrators. The routing algorithm processes the values of these variables to generate the internal routing table for the router. These variables are known as routing metrics and can include the following:

- **Hops:** The number of intermediate routers between a given network and the local router
- **Latency:** The time delay in processing a packet through the router or over a given route
- **Congestion:** The length of the packet queue at the incoming port of the router
- **Load:** The processor use at the router or the number of packets per second that it is currently processing
- **Bandwidth:** The available capacity of a route to support network traffic; decreases as network traffic increases
- **Reliability:** The relative amount of downtime that a particular router might experience because of malfunctions
- **Maximum Transmission Unit (MTU):** The largest packet size that the router can forward without needing to fragment the packet

Routing algorithms are usually implemented as a combination of dynamic (real-time calculated) and static (specified by the network administrator) factors, usually in a distributed fashion where each router independently calculates its own routing tables. In the case of dynamic routers, the exchange of routing information between routers is also part of this process. This provides a degree of fault tolerance for the routing network, for if one router goes down, the remaining routers can recalculate their routing tables to ensure they are able to route traffic around the failed router. Then, when the failed router is restored, the routing tables are recalculated a second time. Some routing algorithms support forwarding packets over several paths to a given destination (when such multiple paths exist) and thus better manage network traffic by load balancing packets accordingly.

Types

An important distinction between routing algorithms involves the space within which they operate. In a flat routing space, all routers are peers, but in a hierarchical routing space, different routing domains, areas, or autonomous systems are connected using a backbone routing network. The advantage of a hierarchical routing space is that it reduces the amount of intercommunication traffic that must take place between routers in order for them to calculate their routing tables. For example, routers that forward traffic only within their own routing table do not need to exchange routing information with routers in other domains. The downside, of course, is that a hierarchical system is much more difficult to implement and maintain than a flat routing space.

Based on this distinction, routing algorithms come in two basic types:

- **Distance vector routing algorithms:** These use a flat routing space, and an example of a routing protocol of this type is the Routing Information Protocol (RIP). Distance-vector routing is sometimes called Bellman-Ford routing or even “old ARPANET routing” by those who are familiar with this algorithm’s origins.
- **Link state routing algorithms:** These employ a hierarchical routing space, and an example of a routing protocol of this type is the Open Shortest Path First (OSPF) protocol. Link state algorithms were developed later than distance-vector ones and have largely displaced them in enterprise networking.

From a network administrator’s perspective, the differences between these algorithms are as follows:

A routing protocol based on the distance vector routing algorithm is simpler to implement than one based on the link state routing algorithm. Routing loops are less likely to occur when the link state algorithm is used, but link state algorithms require more processing power and routers that implement it are generally more costly. The two algorithms offer a trade-off with respect to network traffic between routers. Specifically, routers using the distance vector algorithm periodically send their entire routing table to other routers, but only to routers one hop away, while the link state algorithm floods the entire internetwork with information from each router, but only updated information is sent when needed.

See Also: *distance vector routing algorithm, dynamic routing, link state routing algorithm, Open Shortest Path First (OSPF), router, routing, Routing Information Protocol (RIP), routing protocol, routing table, static routing*

Routing Information Protocol (RIP)

A popular distance vector routing protocol.

Overview

Routing Information Protocol (RIP) is a dynamic routing protocol that is used to exchange routing table information between routers. Depending on the underlying network protocol being supported, this might be

- **RIP for IP:** Used on Internet Protocol (IP) networks
- **RIP for IPX:** Used on Internetwork Packet Exchange (IPX) networks

Both of these routing protocols are generally referred to simply as RIP. RIP was also adapted for the AppleTalk networking system to form the basis of the Routing Table Maintenance Protocol (RTMP).

History

RIP evolved from the Xerox Network Systems (XNS) protocol suite developed in the late 1970s and was designed in1980 as the first interior routing protocol, a protocol used to allow routers to communicate within an internetwork under a single administrative authority. RIP is implemented as a flat intradomain routing protocol, that is, an interior routing protocol with a flat routing space or routing domain. RIP first became popular as a result of its inclusion in release 4.2 of the Berkeley Software Distribution UNIX (BSD UNIX) platform. RIP was commonly used throughout the enterprise in the 1980s, but it was supplanted in the 1990s in large enterprises by Open Shortest Path First (OSPF), a link-state interior routing protocol. Today RIP is viewed as a legacy protocol suitable mainly for small internetworks of fewer than 50 routers or so.

Types

There are two versions of RIP:

- **RIPv1:** This is the original version of RIP that was defined in RFC 1058.
- **RIPv2:** This is a newer version of RIP defined in RFC 1723. RIPv2 is fully backward compatible with the earlier RIPv1 but is enhanced to support optional multicasting of routing table information to the multicast address of 224.0.0.9, the inclusion of subnet mask values in RIP announcements, and simple password protection to prevent rogue RIP routers from hijacking network traffic.

Implementation

The metric used by RIP-enabled routers for calculated routing table entries is based on the number of hops it takes for packets to reach their destination networks. RIP routers do not employ other routing metrics used in link state routing protocols such as load, bandwidth, latency, or Maximum Transmission Unit (MTU) in calculating these routing costs. The routing table of a RIP router contains the cost in hops of every path to every destination network in the internetwork.

When a RIP router is first turned on, it broadcasts its presence using a General RIP Request message. This is done so that neighboring RIP routers can be alerted to send the original router advertisements of their routing tables. These RIP advertisements from neighboring RIP routers allow the original router to dynamically build its own routing tables. In addition, the original RIP router broadcasts to its neighbors all network IDs of locally attached networks so that they can update their own routing tables with this information.

RIP-enabled routers broadcast their complete routing tables every 30 seconds over User Datagram Protocol

(UDP) port 520. This adds some overhead to network traffic, but this information is information is propagated only throughout the local subnet and thus received only by routers that have a routing interface adjacent to this subnet. RIP does not support multipath routing. If a routing table has multiple routes for a single network ID, RIP stores the route with the lowest metric (number of hops to destination).

RIP supports a maximum metric of 15, in other words, networks that are more than 15 hops away from the local network are unreachable when using RIP. The RIP metric is also independent of the packet's Time to Live (TTL) value, so if two networks are separated by more than 15 routers, the packet is dropped even if the TTL value has not decremented to zero. When you try to send a packet to a network more than 15 hops away, a RIP router returns an Internet Control Message Protocol (ICMP) Destination Unreachable message.

Advantages and Disadvantages

RIP is a well-supported industry standard routing protocol, but its maximum of 15 hops, together with the use of broadcast announcements, limits the use of RIP to small internetworks. Another disadvantage is that the routing table of a RIP-enabled router can become quite large since it must contain information about all possible routes to all possible subnets on the internetwork.

Another weakness of RIP is that the routing table announcements are not synchronized over the internetwork and are sent without expectation of acknowledgments. In addition, routing entries in a RIP routing table time out 3 minutes after the last RIP announcement is received, so if a RIP router goes down, it takes time for this information to propagate throughout the internetwork, a problem known as slow convergence. This 3-minute timeout value exists so that information about routers that unexpectedly fail or go down can be propagated throughout the internetwork. If neighboring routers do not hear from a RIP router within 3 minutes, networks that are locally attached to the missing router are assigned a hop count of 16, making them unreachable. These factors can result in convergence problems and routing loops on large RIP-enabled internetworks.

Another factor is that RIP advertisement packets are only 512 bytes in length and can contain a maximum of 25 different routing table entries, so a large routing table with hundreds of entries means that dozens of RIP packets are broadcast every 30 seconds. This can result in a lot of extra broadcast traffic on the local subnet, making RIP unsuitable for large internetworks or for networks having slow wide area network (WAN) links.

Finally, RIP cannot take into account real-time network parameters such as congestion, latency, or router load when the RIP router determines whether to forward a packet along a specific route. An alternative to RIP is to use the Open Shortest Path First (OSPF) protocol, which can dynamically take into account such real-time network parameters, but implementing OSPF is fairly complex and may require you to upgrade existing routers.

Notes

RIP routers should be turned off properly so that they can advertise the fact that they are being turned off to their neighboring routers. This notification, called a triggered update, declares all locally attached networks to the router as having a hop count of 16, making them unreachable. These triggered changes then propagate throughout the internetwork.

If your RIP-enabled internetwork includes slower WAN links as well as fast local area network (LAN) links between networks, you can assign the WAN links hop values that are greater than 1 to compensate for their slower speed. For example, you can assign a T1 link between two networks a hop count of 3 or 4. However, the total hop count between any two networks must still be less than or equal to 15, and such a configuration makes sense only if the topology of the network is a complex mesh involving both fast LAN and slow WAN links.

A RIP-enabled router that can receive RIP broadcasts but cannot send them is called a "silent RIP router."

See Also: *AppleTalk, broadcasting, convergence, dynamic routing, interior gateway protocol (IGP), Internet Control Message Protocol (ICMP), Internet Protocol (IP), internetwork, Internetwork Packet Exchange (IPX), Open Shortest Path First (OSPF), router, routing, routing algorithm, subnet, User Datagram Protocol (UDP), Xerox Network Systems (XNS)*

routing interface

A port where a router connects to a network.

Overview

For any particular network, the port on the router that is directly connected to the local network is called the local interface, and any port on the router that is connected to a different network is called a remote interface. Each router interface has a unique MAC address burned into it, just like a network interface card (NIC) in a computer.

If only one router is connected to the local network, the local interface is the default gateway for all hosts on that network.

See Also: *default gateway, MAC address, router, routing*

routing metric

A variable used by a dynamic router to calculate its routing table entries.

Overview

Dynamic routers employ metrics to determine which routing interface the router should forward a packet to in order to route it to its destination. Routing metrics enable routers to make intelligent decisions about how to forward packets to ensure that

- Packets are delivered efficiently and quickly
- Congestion does not occur over links between networks
- Packets are not lost by being dropped by overloaded or dead routers

Implementation

The simplest metric used by routers to calculate routing table entries is the number of hops to a given destination network. This kind of metric is used by the Routing Information Protocol (RIP), an older routing protocol that enables dynamic routers to communicate with each other to share their routing information and synchronize the entries of their routing tables. On the other hand, if you need a more complicated metric that provides you with more control over the various paths that packets take across your network, you can use a routing protocol such as Open Shortest Path First (OSPF) instead. This protocol employs several variables in calculating its metric, including

- **Load:** Generally, the number of packets being processed per second by the router or its central processing unit (CPU) utilization. If the load on a router becomes high, the router can advise other routers to recalculate routing tables in order to divert traffic around it.
- **Latency:** The time interval needed to route a packet through the router or over a specific path through the internetwork. Latency can be increased by delays due to such factors as port congestion on the router, heavy router load, bandwidth utilization of links between networks, and physical distance between networks.

Some routing metrics are manually entered into a router's configuration by administrators who have a knowledge of the network's physical layout and performance. Such metrics can include

- **Bandwidth:** The total capacity of each network link to carry traffic between different networks in the internetwork.
- **Reliability:** The relative amount of anticipated downtime for a given link between two networks.
- **Cost:** A parameter roughly proportional to the actual cost in dollars of using each network link. Some wide area network (WAN) links might have more latency but cost much less.
- **Maximum Transmission Unit (MTU):** The largest size of packet that the router can forward without segmenting the packet into subpackets. Segmentation of network traffic by routers adds additional latency to network communication.

See Also: *dynamic routing, Open Shortest Path First (OSPF), routing, Routing Information Protocol (RIP), routing table, static routing*

routing protocol

A protocol that enables routers to communicate with each other.

Overview

Routing protocols are the software implementation of routing algorithms, mathematical procedures for determining the cost of various paths or routes through an internetwork so that traffic can be efficiently routed. Routing algorithms are used by dynamic routers, which exchange information with each other that enables them to build routing tables that accurately represent the possible paths on which packets may be routed through the network.

A good routing protocol should have the following characteristics:

- It should allow rapid convergence (recalculation) of routing table information when the network changes—for example, when a router goes down.
- It should prevent routing loops from occurring.
- It should select the optimal route for packets to be forwarded to reach their destination, based on routing metric information.

Types

Routing protocols can be classified in different ways. For example, you can classify them according to how they are affected by administrative boundaries in networks, which results in the following:

- **Interior Gateway Protocols (IGPs):** These routing protocols are used to exchange information between routers within a given administrative area or autonomous system (AS). Other names for this kind of routing protocol are interior routing protocol or intradomain routing protocol.
- **Exterior Gateway Protocols (EGPs):** These protocols are used to exchange information between routers in different administrative areas or autonomous systems (ASs). Other names for this kind of routing protocol are exterior routing protocol and interdomain routing protocol.

Routing protocols can also be classified according to the type of routing algorithm they use, specifically:

- **Distance-vector routing protocols:** These protocols employ the distance-vector routing algorithm to calculate their routing tables and send their entire routing table (or most of it) to other routers when updates are required. Because of their high overhead in communications, distance-vector routing protocols are useful only on relatively small networks with few routers.
- **Link-state routing protocols:** These protocols use the link-state routing algorithm for routing table calculation and send only the state of their own interfaces to other routers, minimizing communications overhead and making these protocols suitable for large networks with many routers.

Finally, routing protocols can be classified as either

- **Classful routing protocols:** These use Internet Protocol (IP) address class distinctions to derive subnet masks. They are essentially simple protocols that are limited in their scalability to large networks.

or

- **Classless routing protocols:** These protocols propagate subnet masks and do not consider IP address classes when routing packets. In other words, they employ classless interdomain routing (CIDR) in their operation.

Examples

Common examples of routing protocols include

- **Routing Information Protocol (RIP):** Based on the distance vector routing algorithm and used in small to medium-sized internetworks, RIP is an intradomain routing protocol that can function only within a given routing domain. Microsoft Windows NT Server, Windows 2000 Server, and Windows .NET Server support RIP; a multihomed machine running Windows NT, Windows 2000, or Windows .NET Server can be used as a RIP router.
- **Interior Gateway Routing Protocol (IGRP):** Based on the distance vector routing algorithm and used in medium-sized to large-sized internetworks, IGRP is an intradomain routing protocol that can function only within a given routing domain. IGRP uses a number of metrics to determine routing cost, including load, bandwidth, latency, reliability, and

Maximum Transmission Unit (MTU). The router determines some of these factors dynamically as it inspects incoming traffic, but others are specified by the network administrator. IGRP supports multipath routing for load balancing and fault tolerance.

- **Open Shortest Path First (OSPF):** Based on the link state routing algorithm and used in medium-sized to large-sized internetworks, OSPF is a hierarchical, intradomain routing protocol that is used within an autonomous system (AS). OSPF evolved from an earlier Open Systems Interconnection (OSI) routing protocol called intermediate-system-to-intermediate-system (IS-IS). OSPF supports multipath routing and uses one or more routing metrics, including bandwidth, reliability, load, latency, and MTU. If OSPF is configured to use more than one metric, it can also support type-of-service (TOS) requests for differentiating traffic.
- **Exterior Gateway Protocol (EGP):** An interdomain routing protocol for routing between different routing domains that are connected by a routing backbone such as the Internet. EGP was the first interdomain routing protocol and was designed in 1984 to enable communication between the core routers of the Internet. EGP does not use routing metrics—it simply keeps track of which networks are currently reachable through a given router.
- **Border Gateway Protocol (BGP):** Another interdomain routing protocol created specifically to enable the core or backbone routers of the Internet to communicate with each other. BGP is superior to EGP because it can detect routing loops and use routing metrics, and it has displaced EGP as the interdomain protocol of choice for the Internet.

Some less commonly used routing protocols include

- **NetWare Link Services Protocol (NLSP):** Used in Novell NetWare 4.*x* as part of its Multi-Protocol Router (MPR). NLSP is based on a combination of OSPF routing and Novell's Service Advertising Protocol (SAP) functions and is also based on the link state routing algorithm.
- **Routing Table Maintenance Protocol (RTMP):** Used in AppleTalk networks and based on the distance vector routing algorithm. RTMP is derived from RIP.

Notes

Remember that a routing protocol is different from a routable protocol. A routing protocol is used by routers to communicate with each other. A routable protocol, on the other hand, is a network protocol, such as Transmission Control Protocol/Internet Protocol (TCP/IP) or Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX), that allows packets to be routed across an internetwork.

See Also: *autonomous system (AS), Border Gateway Protocol (BGP), classful routing protocol, classless interdomain routing (CIDR), classless routing protocol, convergence, distance vector routing protocol, dynamic routing, Exterior Gateway Protocol (EGP), interior gateway protocol (IGP), Interior Gateway Routing Protocol (IGRP), link state routing algorithm, Open Shortest Path First (OSPF), Open Systems Interconnection (OSI) reference model, routable protocol, router, routing, routing algorithm, Routing Information Protocol (RIP), routing metric, routing table, static routing*

routing table

An internal table that determines which interface to send a packet to, based on its destination network addresses.

Overview

Routing tables enable both computers and routers to forward packets to their destinations. On Microsoft Windows platforms these routing tables are built automatically and are used to determine whether to forward specific packets to

- The local network for destination hosts on the local network segment
- A near-side router interface for destination hosts on a specific remote network segment
- The default gateway for hosts in unknown locations

Examples

To view the internal Transmission Control Protocol/Internet Protocol (TCP/IP) routing table on a computer running Windows, type **route print** at the command prompt. The result is a typical routing table that looks something like the following:

```
Active Routes:
                                Gateway
Network Address Netmask         Address     Interface   Metric
127.0.0.0       255.0.0.0       127.0.0.1   127.0.0.1        1
172.16.8.0      255.255.255.0   172.16.8.50 172.16.8.50      1
172.16.8.50     255.255.255.255 127.0.0.1   127.0.0.1        1
172.16.255.255  255.255.255.255 172.16.8.50 172.16.8.50      1
224.0.0.0       224.0.0.0       172.16.8.50 172.16.8.50      1
255.255.255.255 255.255.255.255 172.16.8.50 172.16.8.50      1
```

This particular computer has a single network interface card (NIC) with the address 172.16.8.50. The columns of this table are interpreted as follows:

- **Network Address:** A destination network address on the network
- **Netmask:** The portion of the network address that must match in order for that route to be used
- **Gateway Address:** Where the packet needs to be forwarded (a local NIC or a local router interface)
- **Interface:** The address of the NIC through which the packet should be sent
- **Metric:** The number of hops to the destination network

See Also: *default gateway, routable protocol, route, router, routing, routing interface, routing metric, routing table*

RPC

Stands for remote procedure call, a protocol that enables one computer to make a function call to another computer on the network.

See: *remote procedure call (RPC)*

RPC Ping

A utility for testing for remote procedure call (RPC) connectivity over a network.

Overview

RPC Ping is included with Microsoft Exchange Server for testing RPC connectivity essential for the operation of an Exchange/Outlook messaging system. The server portion of RPC Ping runs on an Exchange server and responds to requests from the RPC Ping client on another station.

If an RPC-based mail client such as Microsoft Outlook cannot connect to an Exchange server in its site, perform the following tests:

- Check network connectivity between the client and the server to try to map a network drive to a shared folder on the server by typing the Net Use command at the command prompt on the client. If this fails, you might have a hardware failure such as a failed network interface card (NIC), a loose cable, or a configuration problem with your networking protocol (such as an erroneous Internet Protocol [IP] address).
- If network connectivity is successful, you might have a problem with the RPC binding order on the client. Try modifying this binding order in the registry.
- If the client still cannot connect to the server, run the server-side component of RPC Ping on the server to test which protocols RPC can bind with and which protocols can be accepted by the client. This server-side component of RPC Ping is called Rpings. Run the client-side component of RPC Ping called Rpingc32 to test RPC connectivity with the Exchange server. If Rpingc32 works for a specific protocol, rearrange the RPC binding order on the client so that this protocol is first.

See Also: *Exchange Server*

RPR

Stands for resilient packet ring, an emerging technology for Synchronous Optical Networking (SONET).

See: *resilient packet ring (RPR)*

RSA

Stands for Rivest-Shamir-Adelman, a popular algorithm for public key cryptography.

See: *Rivest-Shamir-Adelman (RSA) algorithm*

RS-232

A popular serial interface.

Overview

More properly known as RS-232C, RS-232 is a widely implemented serial transmission interface developed by the Electronic Industries Alliance (EIA) that is used for connecting data terminal equipment (DTE) such as computers or terminals to data communications equipment (DCE) such as modems, packet assembler/disassemblers (PADs), or serial printers.

RS-232 specifies the types of wires and connectors, the pinning of the connectors and the function of each wire, the voltage levels and their meanings, and control procedures such as handshaking. RS-232 is compatible with the V.24 and V.28 standards from the International Telecommunication Union (ITU).

Uses

On a PC, RS-232 is typically implemented in a universal asynchronous receiver-transmitter (UART) chip, which converts the internal parallel bus signal to a serial bit stream and vice versa, enabling communication between your system bus and serial devices. Even though the maximum speed of RS-232 is 115.2 kilobits per second (Kbps), older PCs support rates of up to only 56 or 64 Kbps. Newer PCs have a 16550 UART chip that supports serial throughput rates of up to 460.8 Kbps.

You can also use RS-232 with a null modem cable to connect two pieces of DTE (for example, to transfer files). If you are having trouble with an RS-232 connection, be sure that you are using a regular cable for DTE-DCE communication or a null modem cable for DTE-DTE communication—they look the same, but they are incompatible.

Architecture

The RS-232 specification uses unbalanced lines to provide full-duplex serial communication using baseband transmission. RS-232 provides a typical data rate of 19.2 Kbps over a maximum distance of 15 meters (49 feet), but the maximum data transfer rate is 115.2 Kbps. Up to two devices can be connected using RS-232. Devices cannot be daisy-chained together using RS-232. (Use RS-422/423 instead.)

RS-232 cables (cables designed to use the RS-232 serial interface specification) are typically 25-wire unshielded twisted-pair (UTP) cables with DB25 type connectors or 9-wire cables with DB9 connectors. The pin assignments are shown in the following table. Note that only pins 1 through 8 and pin 20 are required for most basic RS-232 functions, which means that 9-pin DB9 connectors can be used on RS-232 serial cables for most applications.

Pin Assignments for RS-232

Pin Number	*Function*
1	Equipment ground (for protection)
2	DTE transmit data
3	DTE receive data
4	Request-to-send (RTS), controlled by the DTE
5	Clear-to-send (CTS), controlled by the DCE
6	Data-set-ready (DSR), controlled by the DTE
7	Signal ground (common return path)
8	Carrier-detect (CD)
9	+ Voltage
10	- Voltage
11	Not used
12	Secondary received line signal indicator
13	Secondary CTS
14	Secondary DTE transmit data
15	DCE transmitter signal timing
16	Secondary DTE receive data
17	Receiver signal timing
18	Local loopback
19	Secondary RTS
20	Data-terminal-ready (DTR), controlled by the DTE
21	Signal quality detector
22	Ring indicator
23	Data signal rate selector
24	DTE transmitter signal timing
25	Test mode

See Also: *connector (device), data communications equipment (DCE), data terminal equipment (DTE),* *full-duplex, RS-422, serial transmission, unbalanced line*

RS-422

A high-speed serial interface.

Overview

RS-422 is a full-duplex serial interface that uses balanced lines and has more immunity from noise than the RS-232 interface. RS-422 was originally designed to supersede the earlier RS-232 standard, but they now coexist in networking environments. RS-422 transmits data at rates between 230 kilobits per second (Kbps) and 1 megabit per second (Mbps). RS-422 cables typically have 25 wires and use DB37 or DB9 connectors, and the maximum distance for an RS-422 link is typically 300 meters (985 feet).

An unbalanced version of RS-422 called RS-423 is defined but is less frequently implemented. RS-422 and RS-423 are compatible with the International Telecommunication Union (ITU) standards V.11 and V.10, respectively.

Uses

RS-422 is used in industrial environments with a lot of electromagnetic interference (EMI) or where more than two serial devices need to be chained together. It is typically used for high-speed synchronous communication between data terminal equipment (DTE) and multiple daisy-chained data communications equipment (DCE).

Notes

Some other related Electronic Industries Alliance (EIA) standards for serial transmission include

- **RS-449:** Specifies the pinning for RS-422 when DB37 connectors are used.
- **RS-485:** Expands RS-422 to include balanced multipoint serial communication using tristate drivers.
- **RS-530:** Specifies the pinning for RS-422 when DB25 connectors are used. Note that RS-530 cables look like RS-232 cables but are not compatible with them.

See Also: *connector (device), data communications equipment (DCE), data terminal equipment (DTE), full-duplex, RS-422, serial transmission, unbalanced line*

RSAC

Stands for Recreational Software Advisory Council, a nonprofit organization with a content advisory system for Web sites on the Internet.

See: *Recreational Software Advisory Council (RSAC)*

Rsh

A UNIX command that enables clients to run commands directly on remote hosts without having to log on to the remote host.

Overview

Rsh is one of the UNIX r-commands that are available on all UNIX systems. In order to use Rsh on a client machine,

- The remote host must be running the Rsh service or daemon.
- The Rsh user and client must have their computer name and username configured in the remote host's .rhosts file.

Rsh provides functionality similar to that of Rexec, another UNIX command that enables clients to run commands directly on remote hosts. The difference is that Rexec uses clear-text password authentication and does not prompt the client to enter a password upon connecting.

Notes

Microsoft Corporation's implementation of Rsh is client software only. If a user on a computer running Microsoft Windows 2000, Windows XP, or Windows .NET Server is logged on to a domain and tries to use Rsh to run a command on a remote UNIX server that is running the Rsh daemon, the domain controller must be available in order to authenticate the user, which is required by the Rsh client.

See Also: *Rexec*

RSVP

Stands for Resource Reservation Protocol, a signaling protocol used for conveying quality of service (QoS) requests.

See: *Resource Reservation Protocol (RSVP)*

runt

An undersized Ethernet frame.

Overview

A runt is an Ethernet frame that is smaller than the minimum 64-byte size. Runts are generally caused by malfunctioning interfaces on routers or malfunctioning network interface cards (NICs) in computers. Runts utilize network bandwidth in a hidden fashion when they are present and are therefore undesirable, but they are a less serious condition than jabbering, which occurs when an interface starts broadcasting frames without ceasing. Runts can slow down a network, but a jabbering card can bring everything to a standstill. To eliminate runts, identify the malfunctioning card or interface and replace it.

See Also: *Ethernet, jabber, network interface card (NIC), router*

S

SACL

Stands for system access control list, a form of access control list (ACL) used by Microsoft Windows 2000 for security control purposes.

See: *system access control list (SACL)*

safe mode

A mode of starting some versions of Microsoft Windows for troubleshooting purposes.

Overview

Safe mode bypasses startup files and runs a basic set of files and drivers including mouse, keyboard, video, mass storage, and basic system services. Safe mode is used for troubleshooting Windows when your system fails to boot properly—for example, when a device driver is corrupt or after you make an erroneous change to the registry. Safe mode bypasses the system startup files to allow you to start with a "clean" configuration.

To access safe mode when booting Windows 98 and Windows Millennium Edition (Me), press the F5 key when the screen shows the message "Starting Windows 98..." or "Starting Windows Me..." You can also start safe mode from the command prompt by typing **win/d:m**. You can also press F6 to access safe mode with networking support. When you are in safe mode, you are informed of this by text displayed in all four corners of the screen.

To access safe mode while booting Windows 2000, Windows XP, or Windows .NET Server, press the F8 key when you see the message "Please select the operating system to start." You will then be presented with a list of options that includes three safe mode options: standard, networking-enabled, and safe mode with command prompt. Use the arrow keys to navigate the list. Press the Enter key to make your selection.



Windows is running in safe mode.

This special diagnostic mode of Windows enables you to fix the problem that is keeping you from starting Windows normally. The problem could be caused by your network or hardware settings. Make sure these settings are correct in Control Panel, and then try starting Windows again. For more information, see the Troubleshooting section in Help. While in safe mode, some of your devices may not be available.

Safe mode. *Entering safe mode in Windows 2000.*

SAM database

Stands for Security Account Manager (SAM) database, which contains user and group account information on a Microsoft Windows NT domain controller.

See: *Security Account Manager (SAM) database*

SAN

Stands for storage area network, a dedicated storage network separate from the network where servers reside.

See: *storage area network (SAN)*

SAP

Stands for Service Advertising Protocol, a Novell NetWare protocol for advertising network resources.

See: *Service Advertising Protocol (SAP)*

SAS

Stands for secure attention sequence, the Ctrl+Alt+Delete keystroke combination in Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server that displays the Windows Security dialog box.

See: *secure attention sequence (SAS)*

SATAN

Stands for Security Administrator Tool for Analyzing Networks, a popular network security analysis tool.

See: *Security Administrator Tool for Analyzing Networks (SATAN)*

Satellite Internet Backbone (SIBone)

A satellite-based network exchange point.

Overview

The Satellite Internet Backbone (SIBone) is the first network exchange point on the Internet that is located in outer space. SIBone uses a satellite deployed by eSAT, and Internet service providers (ISPs) can connect to this exchange point by colocating routers at eSAT's data centers (called teleports), where satellite links using radio telescopes connect the ground station with the satellite. eSAT's satellite employs a proprietary technology called Virtual Onboard Switching (VOS) to simulate a mesh-based technology.

SIBone provides Tier-2 ISPs with an alternative to buying transit services from larger Tier-1 ISPs. VOS allows Tier-2 ISPs to exchange Internet traffic with each other directly, potentially saving costs. SIBone's downside, however, is that the satellite's geosynchronous orbit means that it is 22,236 miles (35,785 kilometers) above the Earth's surface, which can increase the latency of connections by as much as 500 milliseconds (msec). This latency might be acceptable for general purpose Internet traffic but is too large for Voice over IP (VoIP) applications to work well.

See Also: *Internet, Internet service provider (ISP), latency, Voice over IP (VoIP)*

schema

A set of rules defining the structure of a directory.

Overview

In the Active Directory directory service of Microsoft Windows 2000 and Windows .NET Server, the schema defines which objects can be contained in the directory and what attributes those objects can have. The schema can also be considered a formal definition of Active Directory.

Active Directory comes with a default schema that is sufficient in most instances and that defines common network objects in the directory such as users, groups, domains, and computers. You can modify the schema by using the Active Directory Schema, a snap-in for the Microsoft Management Console (MMC). The schema is extensible in that new object classes and attribute types can be added to it. Members of the Schema Admins group have the necessary rights for modifying and extending the schema. The built-in Administrator account is included in this group. You can make the following types of modifications to the schema:

- Create new classes and attributes
- Modify existing classes and attributes
- Deactivate existing classes and attributes

Notes

The schema is actually stored in Active Directory itself in a container under the RootDSE object. Key attributes within the Active Directory schema that are prefixed with "System-" cannot be modified. This ensures consistency of the schema.

If you modify the schema, you should wait five minutes for the modifications to be written to the system, whereupon the changes are updated in Active Directory and replicated to all domain controllers. Therefore, if you modify the schema, you should wait until the changes have replicated throughout your entire enterprise before you create new objects that use these modifications.

As a safety measure, domain controllers by default have read-only permissions on the schema. If you want to write changes to the schema, you must first modify a registry setting on the domain controller on which you plan to make modifications. (Make modifications to the schema from only one domain controller at a time.) The Schema Manager MMC snap-in offers a check box that you can use to set or clear the key. To modify the registry manually, you add the parameter "Schema Update Allowed" with data type REG_DWORD and a nonzero value to the following registry key:

```
HKEY_LOCAL_MACHINE
      \System
          \CurrentControlSet
              \Services
                   \NTDS
                        \Parameters
```

See Also: *Active Directory*

scope

Short for Dynamic Host Configuration Protocol (DHCP) scope, a range of Internet Protocol (IP) addresses that a DHCP server can lease out to DHCP clients.

See: *DHCP scope*

scripting

Writing scripts for performing administration, building dynamic Web sites, and other tasks.

Overview

Scripting involves using scripting languages to write short programs called scripts. These scripts are then executed with the help of a scripting engine, an interpreter that is usually built in to the client or server where the script is executed.

Some uses for scripting in enterprise and e-business environments include

- Automating administrative tasks such as performing backups and unlocking user accounts
- Adding dynamic functionality to static Hypertext Markup Language (HTML) pages to create forms, shopping carts, and other features

Types

There are a wide variety of scripting languages used in enterprise and e-business environments today. Some of the more popular languages include

- **Batch file languages:** A batch file is a collection of Microsoft Windows or UNIX commands saved in a text file. On the Windows platform, for example, batch files are files that have the extension .bat. Batch files can be either manually executed by administrators or can be scheduled to run at specific times. In UNIX environments writing batch files is often called shell scripting.
- **Practical Extraction and Reporting Language (Perl):** This is a popular scripting language used in UNIX environments for writing common gateway interface (CGI) scripts that add dynamic functionality to static Web pages. There are also versions of Perl for the Windows platform.
- **Rexx:** This language originated in IBM's OS/2 computing environment, and is a scripting language that has powerful string manipulation features comparable to those found in Perl.
- **Python:** This is another scripting language that is popular in the UNIX environment. It includes support for object-oriented programming.
- **Visual Basic Scripting Edition (VBScript):** This is a subset of Visual Basic for Applications (VBA) and is a popular tool on Windows platforms for building dynamic Web sites.
- **JScript:** This is Microsoft Corporation's implementation of JavaScript and confirms to the European Computer Manufacturers Association (ECMA) 262 standard. JScript is a powerful tool for writing scripts that perform administrative tasks on the Windows platform.

Implementation

Looking specifically at Web scripting on the Windows platform, two basic approaches can be used:

- **Server-side scripting:** Here the script is executed on the Web server side of a Hypertext Transfer Protocol (HTTP) session. The client requests a page from the server, and the server processes the script and generates HTML, which is then sent to the client. Server-side scripting is popular and forms the basis of Microsoft Active Server Pages (ASP), a platform for building dynamic Web applications based on Microsoft Internet Information Services (IIS). Similar platforms include ColdFusion from Allaire Corporation, Java Server Pages (JSP) from Sun Microsystems, and PHP from the Apache Software Foundation.

- **Client-side scripting:** Here the script is embedded in the Web page downloaded by the client and is executed within the client browser to add dynamic functionality to the page.

Notes

The Windows Script Host (WSH) is a component of Windows that first appeared in Windows NT 4. The WSH enables scripts of various types to be run without the need of a separate container application, and it supports a wide range of ActiveX scripting engines.

See Also: *Active Server Pages (ASP), batch file, Hypertext Markup Language (HTML), Hypertext Transfer Protocol (HTTP), Internet Information Services (IIS), JScript, Practical Extraction and Reporting Language (Perl), VBScript, Windows commands, Windows Script Host (WSH)*

SCSI

Stands for Small Computer System Interface, a popular general-purpose input/output (I/O) bus.

See: *Small Computer System Interface (SCSI)*

SC/ST connectors

Connectors commonly used in fiber-optic networking.

Overview

The SC and ST connectors are the most widely used type of connectors for fiber-optic cabling. They are defined in the Electronic Industries Alliance/Telecommunications Industry Association (EIA/TIA) 568A cabling standard. Details of these connector types are as follows:

- **SC:** This stands for subscriber connector and is a duplex (two strand) fiber-optic connector having a square molded plastic body about twice the size of a standard RJ-45 copper wire connector and a push-pull locking interface. SC connectors are typically used in data communication, cable television (CATV), and telephony environments.
- **ST:** This stands for straight tip and is a simplex (one strand) fiber-optic connector with round ceramic ferrules and bayonet locking features. ST connectors are generally more common than SC connectors in fiber-optic networking environments.

Both SC and ST connectors can be used with either single-mode or multimode fiber-optic cabling. Coupling receptacles for these connectors come in either panel-mount or free-handing designs. For narrow space installations, you can even get 90-degree boot versions instead of straight versions.



SC and ST connectors. *Fiber-optic SC and ST connectors.*

Issues

The main problem with SC and ST connectors is that they are expensive. To terminate a fiber-optic cable with one of these connectors you must splice the cable, polish the end of the fiber, and glue the connector onto the cable. The cost of these connectors plus installation labor means that about 35 percent of the cost of a fiber-optic patch cord is due to the connectors. As a result, fiber-optic cabling manufacturers have been developing new connector types that are easier to install and more compatible with writing panels for existing Category 5 (Cat5) cabling infrastructures. An early development in this regard was the SMA connector, a snap-in connector that features threaded-nut locking. Subtypes of this connector include SMA905 and SMA906.

A recent development has been the emergence of new fiber-optic connectors compatible with RJ-45 connectors. These new connectors allow existing Cat5 wiring panels to be used for optical interconnects instead of having to install special SC/ST/SMA patch panels in wiring closets. Some of the more popular versions of these new connectors include

- **MT-RJ:** Developed by Alcoa, AMP, and Siecor (now Corning Cable Systems)
- **LC:** Developed by Lucent Technologies
- **VF-45:** Developed by 3M Corporation
- **Opti-Jack:** Developed by Panduit Corporation

These different standards are inoperable with one another, and the TIA is essentially letting the market decide which will become the new market standard. The move to these smaller-footprint optical connectors means that SC/ST connectors are beginning to be viewed as legacy technology and might soon be on their way out.

Notes

For harsh environments, a good choice is the military-grade connector. These connectors satisfy the MIL-C-83522 (ST) specifications and are corrosion-proof; have isolated relief boots to reduce cable strain; and are heat, shock, vibration, fungus, and salt-spray resistant.

See Also: *Category 5 (Cat5) cabling, fiber-optic cabling, RJ connectors*

SDLC

Stands for Synchronous Data Link Control, a data-link layer protocol developed in the 1970s by IBM for its Systems Network Architecture (SNA) networking environment.

See: *Synchronous Data Link Control (SDLC)*

SDSL

Stands for Symmetric Digital Subscriber Line, a form of business-grade Digital Subscriber Line (DSL) service.

See: *Symmetric Digital Subscriber Line (SDSL)*

secondary name server

A type of name server in the Domain Name System (DNS).

Overview

A secondary name server is one that downloads its file of resource records from a master name server. The master name server can be either a primary name server or another secondary name server. Primary name servers get their resource records from local files called zone files. Secondary name servers do not maintain local zone files—they obtain their files from master name servers by means of a zone transfer, which occurs when a secondary name server polls a master name server and determines that there are updates to the DNS database that need to be downloaded. This primary/secondary (master/slave) architecture means that a DNS administrator has to maintain only a single set of DNS resource records (on the primary name server), which simplifies DNS administration.

A name server can be a primary name server for one zone and a secondary name server for a different zone. In other words, name servers are defined as primary or secondary on a per-zone basis. On Berkeley Internet Naming Domain (BIND) implementations of DNS, secondary name servers are often referred to as slave name servers.

Notes

Secondary name servers can be used to provide redundancy and load balancing for name resolution. On a corporate Internet Protocol (IP) network that uses DNS as its name resolution method, it is a good idea to have at least two name servers—a primary master name server, and a secondary name server for backup. Otherwise, if the primary goes down, users will not be able to resolve server names on the network and therefore will not be able to find and access any network resources.

BIND makes it possible for slave name servers to keep backup copies of zone files in case the master name server goes down. It is generally a good practice to keep such backup copies. You can also implement a list of up to 10 master name servers that can be tried successively by each slave name server in a very large DNS implementation. BIND v8 includes a feature whereby the primary notifies the slave when changes have been made to the primary's DNS database. This notification process causes BIND v8 name servers to be more up to date with each other than with the polling procedure of earlier BIND implementations.

See Also: *Berkeley Internet Name Domain (BIND), name server, zone, zone file*

secondary ring

The backup ring in Fiber Distributed Data Interface (FDDI) networking.

Overview

FDDI is a dual-ring topology networking architecture based on a token-passing access method. The secondary ring usually sits dark (unused), except when a fault occurs on the primary ring, in which case the network reconfigures itself to make use of the secondary ring to wrap around the fault. Because the data travels on the secondary ring in the opposite direction than it was traveling on the primary ring, when it's put to use, the secondary ring reroutes data back the way it came, thus avoiding the problem spot.

The dual-ring configuration provides FDDI with a degree of fault tolerance—if a computer or cable on the primary ring goes down, the secondary ring is put to use, working in conjunction with the portion of the primary ring that is not broken. This feature is known as a self-healing capability and is performed when the stations on both sides of the link concentrator reconfigure themselves when a failure occurs in the link (due to a cable break, a loose connector, or some device failure).

The FDDI specification allows the length of the two rings to reach up to 125 miles (200 kilometers), with up to 1000 attached stations. However, since the secondary ring is usually used for redundancy purposes, a maximum of 500 stations is allowed on an FDDI network. Repeaters are needed every 1.25 miles (2 kilometers) around the rings.

Notes

You can run the FDDI primary ring and secondary ring along different physical paths to make your FDDI network even more redundant. If an accident or disaster affects one of the rings, it might not affect the other.

See Also: *Fiber Distributed Data Interface (FDDI), primary ring*

secure attention sequence (SAS)

The Ctrl+Alt+Delete keystroke combination in Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server that displays the Windows Security dialog box.

Overview

Users can use the secure attention sequence keystroke combination to do the following:

- Log on to or log off of a Windows workstation
- Lock the console or unlock a locked workstation
- Change their passwords
- Invoke Task Manager
- Shut down, log off, or restart their systems

Notes

The secure attention sequence (SAS) offers protection against Trojan horse programs that masquerade as common system applications. For example, it is impossible to write a Trojan horse program that presents the user with a phony Windows Security dialog box in order to steal a user's credentials, because this program cannot be activated by the SAS. The most that a hacker can do is write a Trojan horse program that displays a Windows Security dialog box at random times while the user is already logged on. To guard against such an event, you should educate users to always use the SAS keystroke sequence even if the computer they are using already displays what appears to be the Windows Security dialog box.

The SAS also kills any logon scripts that are running and can be used to terminate scripts that have stopped responding.

Secure Hypertext Transfer Protocol (S-HTTP)

An Internet protocol for encryption of Hypertext Transfer Protocol (HTTP) traffic.

Overview

Secure Hypertext Transfer Protocol (S-HTTP) is an application-level protocol that extends the HTTP protocol by adding encryption to Web pages. It also provides mechanisms for authentication and signatures of messages. S-HTTP provides broad support for implementing different types of cryptographic algorithms and key management systems. Although S-HTTP systems can make use of digital certificates and public keys, messages can also be encrypted on a per-transaction basis using symmetric session keys.

S-HTTP was proposed as a draft standard in 1996 and is still under development. S-HTTP is not as widely implemented as Secure Sockets Layer (SSL), which is the most popular protocol for encrypting information sent over the Internet.

Notes

S-HTTP is also the name given to World Wide Web (WWW) server software that implements the S-HTTP protocol. This software was developed by Enterprise Integrations Technologies (EIT), the National Center for Supercomputing Applications (NCSA), and RSA Security.

See Also: *cryptography, Hypertext Transfer Protocol (HTTP), Secure Sockets Layer (SSL), security, security protocols, World Wide Web (WWW)*

Secure/Multipurpose Internet Mail Extensions (S/MIME)

A scheme for secure e-mail messaging.

Overview

RSA Security developed Secure/Multipurpose Internet Mail Extensions (S/MIME) as a mechanism for adding security to the Simple Mail Transfer Protocol (SMTP) e-mail messaging protocol. S/MIME adds support for digital signatures and encryption to SMTP to enable authentication of the sender and protect the privacy of the communication. S/MIME is defined in RFCs 2311 through 2315.

Implementation

S/MIME is basically an extension of the widely implemented Multipurpose Internet Mail Extensions (MIME) encoding standard, which defines how the body portion of an SMTP message is structured and formatted. S/MIME uses the RSA public key cryptography algorithm along with the Data Encryption Standard (DES) or Rivest-Shamir-Adleman (RSA) encryption algorithm. In an S/MIME message, the MIME body section consists of a message in PKCS #7 format that contains an encrypted form of the MIME body parts. The MIME content type for the encrypted data is application/pkcs7-mime.

Prospects

S/MIME has gained some popularity in the enterprise but its deployment has been hindered by the complexity and cost of implementing public key infrastructure (PKI) schemes. S/MIME is simpler to implement than the earlier Privacy Enhanced Mail (PEM) specification, but it has not achieved the same widespread use as the Pretty Good Privacy (PGP) scheme developed by Phil Zimmermann.

Notes

Note that since Hypertext Transfer Protocol (HTTP) messages can also transport MIME data, HTTP can also employ S/MIME for secure communications, although this is rarely implemented.

See Also: *Data Encryption Standard (DES), e-mail, encryption, Hypertext Transfer Protocol (HTTP), Multipurpose Internet Mail Extensions (MIME), PKCS #7, Privacy Enhanced Mail (PEM), public key infrastructure (PKI), Rivest-Shamir-Adelman (RSA) algorithm, Simple Mail Transfer Protocol (SMTP)*

Secure Sockets Layer (SSL)

A transport layer security protocol used on the Internet.

Overview

Secure Sockets Layer (SSL) is a security protocol used for securing communications performed over the Internet. SSL provides three things:

- **Authentication:** Ensures that the message received is from the individual it says it is from
- **Confidentiality:** Protects the message from being read by unintended recipients along the way
- **Integrity:** Ensures that the message has not been modified along the way

Netscape Communications developed SSL in 1996 to enable secure transmission of information over the Internet.

Implementation

SSL operates between the application and transport layers of the Open Systems Interconnection (OSI) reference model. SSL supports only those applications and application-layer protocols for which it has been explicitly implemented. In other words, SSL is not a transparent security protocol that can work automatically with any application-layer protocol. SSL commonly operates with the Hypertext Transfer Protocol (HTTP) and sometimes with the Simple Mail Transfer Protocol (SMTP) and Network News Transfer Protocol (NNTP). SSL has been implemented in a wide variety of applications including Web servers, Web browsers, and other Internet applications. Both the client and the server applications must support SSL in order for it to work.

SSL employs public-key encryption for secure authentication and symmetric key encryption for encryption of transmitted information. For public key encryption SSL employs the Rivest-Shamir-Adleman (RSA) encryption algorithm and therefore depends on the implementation of a supporting public key infrastructure (PKI). Message integrity is guaranteed by incorporating a message integrity check mechanism called a message authentication code (MAC).

An SSL session begins when an SSL-enabled client requests a connection with an SSL-enabled server over Transmission Control Protocol (TCP) port 443, the SSL port. This initiates the SSL handshake between the client and server. A Web page that uses SSL has a Uniform Resource Locator (URL) that begins with https instead of the standard http prefix. The server then sends the client its digital certificate and public key. The client and server then negotiate a mutually acceptable level of encryption, which is usually 40-bit, 56-bit, or 128-bit strength, depending on legal restrictions and availability. The client then generates a secret session key, encrypts it with the server's public key, and sends the encrypted session key to the server, which decrypts the session key using its private key. From that point on, the secret key cryptography is employed, and the session key is used to encrypt all data exchanged between the client and server, providing secure, private communication.

Issues

The main problems with SSL are

- Using SSL to secure Web transactions adds significant processing overhead to Web servers, sometimes as much as two orders of magnitude. In other words, a Web server that can support thousands of simultaneous unencrypted HTTP sessions might only be able to support a few dozen SSL sessions based on the same hardware configuration.
- SSL is difficult to implement in e-commerce environments that use Web server farms and server load balancers. This is because SSL is designed to use persistence, which means that the client must maintain the same Internet Protocol (IP) address during the entire session.

To address these issues, you can use specialized network devices called SSL Accelerators to offload SSL processing and session caching to other servers for enhanced performance and greater persistence.

Prospects

The Internet Engineering Task Force (IETF) has standardized a variant of SSL. This variant is known as Transport Layer Security (TLS), and it is similar to SSL 3 but is not interoperable with that protocol. Microsoft Windows 2000, Windows XP, and Windows .NET Server support both SSL and TLS security. As TLS becomes more widely implemented, use of the proprietary SSL protocol might fade, but this is likely to take place over many years due to wide industry support for SSL.

See Also: *Hypertext Transfer Protocol (HTTP), Internet, Internet Engineering Task Force (IETF), port, public key cryptography, Rivest-Shamir-Adelman (RSA) algorithm, Transmission Control Protocol (TCP), Transport Layer Security (TLS), Uniform Resource Locator (URL)*

security

Protection of computer, network, and business assets.

Overview

Security is an important concern in the field of IT (information technology), particularly since the Internet provided a ubiquitous method for connecting networks and systems all over the world. The rise in business on the Internet (e-business) in the 1990s resulted in an exponential increase in attacks on corporate networks, with an accompanying increasing awareness of the fundamental importance of security for protection of business assets such as financial data and confidential personnel information.

Security in general is difficult to achieve in any open system—that is, a system connected to other systems. E-businesses are by definition open systems, whether they involve business-to-client or business-to-consumer (B2C) relationships, as in e-commerce sites and online stores, or business-to-business (B2B) relationships, as in supply-chain and financial transaction systems. Some of the difficulties in securing open systems include

- Recognizing the importance of security and allocating staff and financial resources to implement it properly
- Finding and protecting the weakest point in your system
- Maintaining high security while keeping the system friendly and usable for those involved

In addition, even closed systems must consider the necessity of securing their assets from misuse by those working within the company or organization. In fact, many security analysts consider the "threat from within" to be the more serious one, despite the large amount of attention given to hackers in the mass media in the last few years.

Security encompasses a broad range of subjects that also includes:

- **Privacy:** Ensuring the confidentiality of information, usually through encryption
- **Integrity:** Ensuring the protection of information from being modified or deleted, again usually through encryption

Implementation

Fundamental to securing assets that are accessible through IT systems such as corporate networks and e-commerce sites are the three basic principles of security: authentication, authorization, and auditing. These three are often referred to as "golden rules" because Au is the chemical symbol for gold. These three principles are

- **Authentication:** The process by which a principal (a trusted, identified entity) identifies a user, consumer, or client. Authentication can employ passwords, signatures, smart cards, biometric identification, and other tools. The basis of authentication from an IT perspective is security protocols, which are protocols that enable users to be securely authenticated by network security principals. Examples of such security protocols include NTLM and Kerberos.
- **Authorization:** Once a user is authenticated, the next step is to ensure that the user can access only those resources for which the user is properly authorized. This is done through implementing access controls, permissions, privileges, and other elements, depending on the systems involved. The securest form of authorization is the mandatory or nondiscretionary access control, which enforces strict rules concerning resource access that affect even the resource's owners.
- **Auditing:** The third step is to ensure that access to resources and privileges is logged for purposes of later review. Audit logs help administrators determine when systems have been compromised and take steps to further secure them.

In addition to these golden rules, a number of other strategies are crucial for ensuring the security of business resources accessible through IT systems. These include

- **Murphy's Law:** If something can go wrong, it will. Therefore no system is completely secure and every system will fail at some point. Accept this fact and be prepared.

- **Do not trust technology:** Security is more about people than it is about technology. Systems will not be secure if administrators fail in their responsibilities to implement patches in a timely manner as new vulnerabilities are discovered for applications and operating systems. Likewise, a firewall is no help if the administrator has not taken the time to configure it properly. Similarly, users must be educated to be "security-conscious" and to avoid such mistakes as taping their passwords under their keyboards or opening executable attachments.
- **Least privilege:** Never give users more privileges than they need.
- **Multiple mechanisms:** Never trust a single security system such as a firewall—have multiple systems in place that redundantly protect your assets, including firewalls, virus scanners, intrusion detection devices, hostile content blockers, and virtual private networking (VPN). On the other hand, try to keep security systems as simple as possible, so you do not get overwhelmed with the job of managing security.
- **Comprehensiveness:** It is no use securing one part of a corporate network if another part is left unsecured. Any security solution must be a comprehensive one that hardens every aspect of the system from outside (or inside) attack.
- **Weakest link:** Identify the weakest point in your system and monitor it regularly. The weakest link of a system is different from the choke point, the narrowest part of the system through which an attacker must enter. However, you should also monitor choke points continuously, even if they are hardened.
- **Security policy:** Take the time to write and internally publish a comprehensive security policy that covers the management, use, and implementation of IT systems in a secure fashion. A security policy outlines your environment's basic security architecture, rules for accessing resources, and how these rules are enforced.
- **Security audit:** Having an independent organization check your network's security is a good idea to ensure that your security policy is comprehensive and implemented properly.
- **Standard deployment:** Have a standard process in place for deploying new IT resources such as Web servers on your network. For example, you should first create a standard "hardened" operating system image, then install additional applications needed, add a binary checksum to facilitate detection of modifications to your system, perform vulnerability analysis for your applications, and finally deploy your server on the network. Never deploy a server that is not properly hardened or that still has its default accounts and passwords in place unchanged.
- **Do not forget the obvious:** Most security breaches are caused by well-known vulnerabilities that have not been secured even though patches are readily available.
- **Know your enemy:** The best defense is a good knowledge about likely attackers. Familiarity with the procedures and tools used by hackers will help you identify, harden, and maintain your system's security. Good network security specialists usually have a collection of popular hacker tools in their arsenal, as many of these tools can be used for identifying vulnerabilities.
- **Regular assessment:** Periodically review your company's compliance with its security policy and ensure that your goals are being met.
- **Consider outsourcing:** Managed security providers (MSPs) are a new breed of company that has arisen in recent years to help small and medium-sized businesses secure their IT systems. You can save costs using these companies' services, but carefully evaluate their offerings first and remember that ultimately security is your own company's responsibility. Appointing a Chief Security Officer (CSO) is an important step in determining how best to implement your company's security requirements.

Finally, here are some tips on how to make your IT environment more secure:

- Use strong passwords and change them every 90 days. Be careful about telephone requests to change an employee's password in case someone is impersonating the employee.
- Teach employees how to choose and protect their passwords.
- Immediately disable the accounts of departing employees.
- Pay special attention to security for telecommuters (employees working from home) as you do not have direct management over their working environment. Ensure that they are using personal firewalls and remind them of the consequences of not complying with the company security policy.
- Disable all unnecessary services on servers.
- Apply new security patches released by vendors as soon as possible, but ensure that your systems are fully backed up first in case the patch causes unexpected problems.
- Ensure that your virus protection software has its signature updated regularly.
- Pay special attention to the security of your wireless networks. Most wireless networks are implemented with default security and the result is that anyone driving near your building with a laptop in their car can often access your network.

See Also: *access control, auditing, authentication protocol, business-to-business, encryption, firewall, hacking, intrusion detection system (IDS), Kerberos, network security, password, permissions, privacy, virtual private network (VPN)*

Security Account Manager (SAM) database

Contains user and group account information on a Microsoft Windows NT domain controller.

Overview

All user accounts, group accounts, and resource definitions such as shares and printers on a Windows NT–based network have their security principals defined in the Security Account Manager (SAM) database. The SAM database is also known as the domain directory database, or sometimes simply the directory database.

The master copy of the SAM database is stored on the primary domain controller (PDC) and occupies a portion of the Windows NT registry. Periodic directory synchronization ensures that backup domain controllers (BDCs) have an accurate replica of this master database, so BDCs can also be used for logons and for pass-through authentication of users attempting to access network resources.

Because the entire SAM database must reside in a domain controller's RAM, it cannot exceed about 40 megabytes (MB) in Windows NT, which works out to about 40,000 user accounts, or 26,000 users and Windows NT workstations combined. The following table lists the size of common objects in a SAM database.

Object Sizes in a SAM Database

Object	*Size in SAM Database*
User account	1 kilobyte (KB)
Computer account	0.5 KB
Global group account	0.5 KB plus 12 bytes per user
Local group account	0.5 KB plus 36 bytes per user

Notes

In Windows 2000 and Windows .NET Server, the functions of the SAM database have been migrated to the more powerful and scalable Active Directory directory service.

See Also: *Active Directory, backup domain controller (BDC), primary domain controller (PDC), registry*

Security Administrator Tool for Analyzing Networks (SATAN)

A popular network security analysis tool.

Overview

Security Administrator Tool for Analyzing Networks (SATAN) is a free tool developed by Dan Farmer and Wietse Venema in 1995 for remotely analyzing the security of networks. SATAN consists of a variety of routines that probe a network for security holes in ways that are similar to the ones hackers use. The tool tests the vulnerabilities of Transmission Control Protocol/Internet Protocol (TCP/IP) hosts using common TCP/IP protocols, such as File Transfer Protocol (FTP), Network File System (NFS), and Network Information System (NIS), and analyzes how the host responds to requests based on these protocols. The results are stored in a database and can be displayed using a Web browser.

SATAN runs on machines running UNIX and needs the Perl interpreter to operate. Typically, SATAN identifies weaknesses in the setup and configuration of network software; network administrators can use it to check the configuration of their network software. SATAN can also identify the network services that are running and provide information about the types of hardware and software and the topology of the network.

Issues

Because SATAN is free and can be downloaded from numerous places on the Internet, both network administrators and hackers can use it. If you are concerned about the possible misuse of SATAN against your network, you can obtain various types of free anti-SATAN software on the Internet that alert you to a SATAN attack so that you can take remedial action.

See Also: *File Transfer Protocol (FTP), Network File System (NFS), Network Information System (NIS), network security*

security descriptor

A unique header for an object stored in the Active Directory directory service of Microsoft Windows 2000 and Windows .NET Server.

Overview

Security descriptors contain security identifiers (SIDs), which are discretionary access control lists (DACLs) or system access control lists (SACLs) that specify the access permissions for the object. Specifically, the security descriptor for an object contains the following:

- **Owner SID:** Identifies the security principal (the owner of the object)
- **Group SID:** Used only by Services for Macintosh and the POSIX subsystem
- **DACL:** Contains the access permissions and rights for the object and its attributes, along with the SIDs of the security principals who can access the object
- **SACL:** Contains system-wide security policies such as the auditing policy

See Also: *Active Directory, discretionary access control list (DACL), security identifier (SID), system access control list (SACL)*

security group

A type of group in Microsoft Windows 2000 and Windows .NET Server.

Overview

Security groups are security principals that can contain other security principals such as user, group, and computer objects from the Active Directory directory service. They are one of two types of groups used in Windows 2000, the other being distribution groups. Security groups are used for grouping accounts and for controlling access to resources, much in the same way that global groups and local groups are used in Windows NT–based networks. (In other words, all groups in Windows NT are security groups.)

Types

Security groups come in three types:

- **Domain local groups:** Provide users with permissions to access resources; used only within the specific domain in which they are created
- **Global groups:** Logically group users for administrative purposes and have visibility in the current domain and trusted domains

- **Universal groups:** Similar to global groups but reduce global catalog replication traffic when they are used

See Also: *distribution group, group*

security identifier (SID)

An internal number used in Microsoft Windows 2000 and Windows .NET Server that uniquely identifies a user, group, or other object.

Overview

Security identifiers (SIDs) are used internally by Windows 2000 to provide user accounts with access to network resources. SIDs are guaranteed to be unique because they are created using a combination of user information, domain information, and time and date of account creation. The general format of a SID is a series of decimal numbers separated by dashes in the following form:

```
S-1-X-Y1-Y2-....
```

X is the value of the identifier authority, and Y1, Y2, and so on are values of subauthorities. The prefix S-1 means “SID revision 1.”

Changing the name of a user, computer, or domain does not change the underlying SID for that account. Administrators cannot modify the SID for an account in Windows NT, and there is generally no need to know the SID assigned to a particular account. SIDs are primarily intended to be used internally by the operating system to ensure that accounts are uniquely identified to the system.

security log

A log in Microsoft Windows 2000, Windows XP, and Windows .NET Server that records auditing events.

Overview

Entries in the security log are either success entries, which are identified by a key symbol, or failure entries, which are identified by a padlock symbol. You can view and manage the security log by using the administrative tool Event Viewer, where you can view additional details by opening the property sheet for the particular event. You can also select events by filtering the security log. You can export the security log as a .csv file and import it into a spreadsheet or database program for further analysis.

Notes

In a high-security environment, you can enable a registry parameter named CrashOnAuditFail, which causes the system to display a Stop screen when the security log is full. This prevents unaudited system access on your server. When you restart the system, you must archive the current contents of the security log before continuing. See the *Microsoft Windows 2000 Server Resource Kit* from Microsoft Press for more information.

See Also: *application log, system log*

security principal

An object in the Active Directory directory service of Microsoft Windows 2000 and Windows .NET Server that can be assigned permissions and rights.

Overview

Three types of security principals are used in Windows 2000 networks:

- **User objects:** Represent individual user accounts
- **Group objects:** Can be used to group other security principals for assigning permissions and to ease administration
- **Computer objects:** Represent individual computers running Windows 2000 on the network

Security principals are uniquely identified by security identifiers (SIDs), which provide a unique, internal, alphanumeric identifier for the security principal.

See Also: *Active Directory, security identifier (SID)*

security protocols

Protocols used for authentication clients.

Overview

Security protocols are protocols that allow networks and systems to authenticate users, computers, and applications for purposes of accessing resources on these networks and systems. Security protocols use various forms of encryption to ensure the privacy, authenticity, and integrity of a user's credentials and of network communications.

Types

Some of the popular security protocols in use today include

- **NTLM:** Stands for Windows NT Lan Manager, the native security protocol on Microsoft Windows NT domain-based networks. NTLM is also known as Windows NT Challenge/Response Authentication protocol.
- **Kerberos:** Developed at the Massachusetts Institute of Technology (MIT) and used as the native security protocol by the Active Directory directory service on Windows 2000– and Windows .NET Server–based networks.
- **Remote Authentication Dial-In User Services (RADIUS):** A client/server protocol used to securely authenticate dial-up users for authentication, authorization, and accounting (AAA).
- **Terminal access controller access control system (TACACS):** A proprietary protocol developed by Cisco Systems and similar to RADIUS.
- **Secure Sockets Layer (SSL):** A protocol that secures Hypertext Transfer Protocol (HTTP) communications between users and Web servers.

See Also: *authentication protocol, Hypertext Transfer Protocol (HTTP), Kerberos, protocol, Remote Authentication Dial-In User Service (RADIUS), Secure Sockets Layer (SSL), Terminal Access Controller Access Control System (TACACS), Windows NT Challenge/Response Authentication*

S

security provider

A server or device on a network that authenticates users trying to log on or access network resources.

Overview

In a Microsoft Windows 2000– or Windows .NET Server–based network, special servers called domain controllers act as security providers and handle tasks such as user logons and control of resource access. If all domain controllers are temporarily offline, users can still log on to their local computers and use local computer resources but cannot be authenticated for accessing resources elsewhere on the network.

Notes

Windows 98 and Windows Millennium Edition (Me) can operate as stand-alone computing environments or as part of a Windows 2000 domain. If files on a computer running Windows 98 or Windows Me will be shared by users on a Windows 2000– or Windows .NET Server–based network, be sure that you have configured Windows 98 or Windows Me networking to use user-level security instead of the more common share-level security used in workgroup environments.

See Also: *domain controller*

segmentation

The process of dividing a large network into smaller connected networks.

Overview

Segmentation improves the performance of Ethernet networks by reducing the size of collision domains. Because stations on an Ethernet network use contention to try to use the networking media, fewer stations in a given network segment means less contention and better network performance. Bridges or routers are generally used to segment an Ethernet network into smaller collision domains.

Notes

The term *segmentation* is also used to refer to the process by which routers break down oversized frames into smaller portions that are sequenced, forwarded, and then reassembled at the receiving station. Segmentation is usually a sign that the network is misconfigured because segmentation eats valuable CPU cycles on routers and produces greater latency in network communication.

See Also: *collision domain, Ethernet, frame*

separator page

A page that is printed between print jobs.

Overview

In the old days, separator pages indicated when one print job finished and the next one began. In Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server, separator pages can have two functions:

- Separating printed output in a multiuser environment so that users can more easily retrieve their print jobs
- Switching a print device between different print modes (if the device has this capability)—for example, switching between Printer Control Language (PCL) mode and PostScript mode

Windows 2000 includes several separator pages, which are located in the \Winnt\System32 directory:

- **Pcl.sep:** Switches the printing mode to PCL printing, typically for printers made by Hewlett-Packard. A separator page is also printed.
- **Pscript.sep:** Switches the printing mode to PostScript for supported printers. No separator page is printed.
- **Sysprint.sep:** Functions much as pscript.sep does but also prints a separator page.

Notes

You can use Notepad to edit any default separator page file to create a custom separator file. You can add new lines by using printer escape codes such as those shown in the following table.

Escape Codes for Custom Separator Pages

Code	*Function*
@D	Prints the date that the job was submitted. (Use Regional Settings in Control Panel to specify the format.)
@E	Ejects the page. (Use at the end of a separator page.)
@Fpathname	Prints the contents of the file specified by “pathname” without performing any processing of the file.
@Hnn	Sends escape code nn to the printer (device-specific functionality).
@I	Prints the job number.
@L	Prints the following characters as is until the next escape code is encountered.
@N	Prints the name of the user who submitted the job.
@T	Prints the time that the job was submitted.
@n	Skips n lines.
@0	Skips to the next line.

If a printer can auto-switch between printing modes (by identifying the type of the rendered file sent to it), you do not need to specify a separator page.

serial encapsulation protocols

Protocols used to encapsulate local area network (LAN) traffic for sending over a wide area network (WAN).

Overview

LAN traffic such as Ethernet frames cannot normally be sent over a WAN link without first encapsulating them in a format suitable for WAN serial transmission. This is accomplished through the use of special encapsulation protocols, with different protocols generally being used for different WAN technologies.

Types

Serial encapsulation protocols fall into two basic types:

- **Synchronous:** These protocols are used for synchronous serial links such as leased lines and packet-switching services, and include High-level Data-Link Control (HDLC), Link Access Control, B-channel (LAPB) used in X.25 networking, and Point-to-Point Protocol (PPP). HDLC is the default protocol used for synchronous serial connections on Cisco routers.
- **Asynchronous:** These protocols are used for asynchronous (dialup) serial links and include Serial Line Internet Protocol (SLIP) and Point-to-Point Protocol (PPP).

Notes

With the emergence of metropolitan Ethernet, the days of serial encapsulation might soon be over. Carriers such as Yipes Communications can now provision Gigabit Ethernet (GbE) directly to your demarc point, allowing you to connect your WAN as easily as you build your LAN.

See Also: *Gigabit Ethernet (GbE), High-level Data Link Control (HDLC), metropolitan Ethernet, Point-to-Point Protocol (PPP), Serial Line Internet Protocol (SLIP), serial transmission*

serial interface

An interface on a device that is used for serial transmission.

See: *serial transmission*

Serial Line Internet Protocol (SLIP)

A serial encapsulation protocol.

Overview

Serial Line Internet Protocol (SLIP) is a packet-framing protocol developed for sending Internet Protocol (IP) datagrams over point-to-point wide area networking (WAN) links. SLIP was developed in 1984 for UNIX environments as a simple protocol that provides only frame delimitation and has limited error recovery mechanisms. Later, a variant of SLIP called C-SLIP was developed that included support for data compression.

SLIP was used mainly in UNIX platforms to provide access to the Internet using low-speed dial-up links. SLIP is defined in RFC 1055 and C-SLIP in RFC 1144.

Comparison

SLIP is a legacy protocol that has now been replaced by the Point-to-Point Protocol (PPP) for the following reasons:

- Although SLIP supports only the Transmission Control Protocol/Internet Protocol (TCP/IP) network protocol, PPP is a multiprotocol encapsulation protocol that can also support Internetwork Packet Exchange (IPX) and AppleTalk. This is not really an issue if you are connecting to the Internet, however, since the Internet is strictly TCP/IP-based.
- SLIP generally requires that the host's TCP/IP parameters be configured manually, but PPP can negotiate the parameters during session establishment. These parameters include the host's IP address, the window size, and compression.
- SLIP might require the user to write a script for automating the logon process, but PPP supports both the Password Authentication Protocol (PAP) and the Challenge Handshake Authentication Protocol (CHAP), which let you automatically forward your credentials to the PPP server for authentication.

See Also: *Point-to-Point Protocol (PPP), wide area network (WAN)*

serial transmission

A form of signal transmission that sends information one bit at a time over a single data channel.

Overview

Serial transmission is performed over different kinds of electrical interfaces called serial interfaces. These serial interfaces are generally used to connect data communications equipment (DCE) such as modems to data terminal equipment (DTE) such as computers and terminals. The term *interface* indicates that these specifications describe how to establish an electrical (pinning) and mechanical (connector) shared boundary between devices. An interface specifies a series of protocols, an arrangement of pins, special control signals, and other functions that enable devices to communicate with each other.

Types

The common serial interfaces used in computer networking and telecommunications include the following:

- **RS-232:** The most commonly used serial interface in ordinary network communication, which supports transmission over a range of 0 to 20 kilobits per second (Kbps) at distances of up to 50 feet (15.24 meters). RS-232 can use either DB9 or DB25 connectors.
- **RS-422:** Specifies a balanced electrical interface but no specific mechanical interface for point-to-point serial communication. RS-422 typically uses either DB9 or DB37 connectors.

- **RS-423:** Similar to RS-422, except that unbalanced lines are used instead of balanced ones.
- **RS-449:** Specifies the mechanical interface for RS-422 and RS-423 and is used with these interfaces for high-speed serial communication with Channel Service Unit/Data Service Units (CSU/DSUs) and routers.
- **RS-485:** Defines a balanced, multipoint interface using tristate drivers to reduce noise. The combined interface RS-422/485 allows you to daisy-chain up to 31 serial devices to a single serial port and is typically used for interfacing industrial sensors and measuring equipment to a computer.
- **RS-530:** A successor to RS-232 and RS-449 that provides high-speed synchronous and asynchronous serial communication of up to 2 megabits per second (Mbps).
- **V.35:** An International Telecommunication Union (ITU) standard for data transmission at 48 Kbps that is typically used for connecting CSU/DSUs and routers for wide area network (WAN) communication over digital data service (DDS) lines. V.35 uses a block-shaped 34-pin connector.
- **X.21:** An ITU standard for synchronous communication between DTEs and DCEs on public X.25 packet-switched networks. X.21 typically uses a DB15 connector.

Notes

Serial interfaces such as RS-232 are the most commonly used protocol for devices called line drivers, which enable terminals and hosts to be connected over phone lines and extend the distance over which the serial interface can function by regenerating the signal.

Related terminology includes

- **Serial cable:** A cable used to connect pieces of DCE to pieces of DTE by using a serial interface
- **Serial port:** A plug or connector on pieces of DTE that can use serial transmission to send and receive data

See Also: *data communications equipment (DCE), data terminal equipment (DTE), line driver, parallel transmission, RS-232, V.35*

server

A computer whose role in a network is to provide services and resources to users.

Overview

Servers usually have one or more specific roles in a network, including:

- **Application servers:** These are used as the back end in a client/server environment. Examples include mail servers and database servers.
- **File and print servers:** These provide users with centralized locations for storing files and accessing print devices.
- **Authentication servers:** These servers validate users for logging on and accessing network resources. An example might be a Microsoft Windows 2000 domain controller.
- **Web servers:** These can be used to serve Web content ranging from static Hypertext Markup Language (HTML) pages to e-commerce sites.

See Also: *Web server*

server-based network

A network in which one or more servers centrally manage network security and storage.

Overview

In a server-based network, special computers called servers handle network tasks such as authenticating users, storing files, managing printers, and running applications such as database and e-mail programs. Security is generally centralized in a security provider, which allows users to have one user account for logging on to any computer in the network. Because files are stored centrally, they can be easily secured and backed up.

Server-based networks are more costly and complex to set up and administer than peer-to-peer networks, and they often require the services of a full-time network administrator. They are ideal for businesses that are concerned about security and file integrity and have more than 10 computers.

Examples

Microsoft Windows 2000 is a robust platform for server-based networking that offers centralized network administration, networking that is easy to set up and configure, NTFS file system (NTFS) security, file and print sharing, user profiles that allow multiple users to share one computer or allow one user to log on to many computers, Routing and Remote Access for supporting mobile users, and Internet Information Services (IIS) for establishing an intranet or Internet presence.

See Also: *peer-to-peer network*

server farm

A group of servers managed as a whole.

Overview

Server farms are typically used in large enterprises and e-commerce sites to group Web servers together for handling loads that would exceed the capacity of individual servers. Server farms are generally switched networks running Gigabit Ethernet (GbE) that are separate from the regular corporate network. They often employ load balancing and caching appliances at the front end to give users who are accessing the servers the illusion that they are accessing a single mega-server instead of many smaller servers grouped together. Server farms generally employ 1U or 2U rack-mounted servers that can be deployed by the hundreds or thousands in relatively small rooms.

Server farms come in all shapes and sizes and are often interconnected with storage area networks (SANs) to provide enterprise-level storage capacity and manageability that complements the farm's processing power.

See Also: *Gigabit Ethernet (GbE), rack, storage area network (SAN)*

serverless backup

A backup technology sometimes used in storage area networks (SANs).

Overview

Serverless backup is a new backup technology in which volumes are imaged and their images are stored for archival purposes. Serverless backup generally employs agents that create a "snapshot" of a database or file system and copies this snapshot to tape. Examples of vendors in this emerging market include Legato Systems, Computer Associates, VERITAS Software Corporation, and others. With the growing importance of SANs in enterprise environments, serverless backup is one technology enterprise networking architects might want to watch in the next few years.

See Also: *backup, storage area network (SAN)*

Server Message Block (SMB)

A general-purposes information-sharing protocol.

Overview

Server Message Block (SMB) is a client/server protocol developed jointly by Microsoft Corporation, IBM, and Intel Corporation for passing information between computers on a network. SMB employs NetBIOS for its transport protocol, and is widely used on Microsoft Windows networks and IBM's OS/2 platform for file and print sharing purposes. SMB can also be used on Transmission Control Protocol/Internet Protocol (TCP/IP) networks, in which case it uses NetBIOS over TCP/IP (NetBT) as its transport.

A popular open-source version of SMB called Samba is available for most UNIX platforms. Samba provides full-featured SMB servers which allow Windows clients access to file and print resources on UNIX networks and is a popular platform for Windows/UNIX interoperability.

Uses

SMB supports functions such as:

- Opening and closing connections between SMB clients (redirectors) and SMB servers (file and print servers) to allow clients to access shared network resources
- Locating, reading, and writing to files on a file server
- Locating and printing to shared print queues

SMB can also be used as a general message-passing protocol for performing remote transactions in a distributed applications environment. Remote procedure calls (RPCs) can be performed over SMB, and SMB also supports other interprocess communication (IPC) mechanisms, including named pipes and mailslots.

Implementation

SMB employs four basic types of messages:

- **Session control messages:** Open or close a redirector connection to a shared resource on the server. The SMB redirector packages the requests sent to remote servers in an SMB-enabled network.
- **File messages:** Used by the redirector to gain access to files on the server.
- **Printer messages:** Used by the redirector to send data to a print queue and get status information about the queue.
- **Message messages:** Let applications exchange messages with another computer.

SMB supports both share-level and user-level authentication, with user-level being preferred for greater security.

Notes

Common Internet File System (CIFS) is a standards-based version of the proprietary SMB protocol and runs directly on top of TCP/IP.

For More Information

You can find Samba at *www.samba.org.*

See Also: *Common Internet File System (CIFS), NetBIOS, NetBIOS over TCP/IP (NetBT), redirector, UNIX*

Server Operators

A built-in group in Microsoft Windows 2000 whose members have the rights to administer servers on the network.

Overview

Server Operators is a domain local group whose initial membership is empty. The Server Operators group has the following pre-assigned rights:

- Log on locally to the server console
- Change the system time
- Back up files and directories
- Restore files and directories
- Shut down the system
- Force shutdown from a remote system

Server Operators can also share and manage disk resources and printers on the network and lock the server.

See Also: *built-in group*

service

An operating system background process that provides some specific functionality for the network.

Overview

Services are processes that run in the background and provide functionality for other computers on the network. For example, the Server service enables a Microsoft Windows 2000 machine to act as a server and offer shared resources to other machines on the network. Similarly, the Workstation service enables machines to act as clients and access shared resources on servers. What are called services on Windows networks are referred to as daemons on UNIX networks.

In Windows NT, Windows 2000, Windows XP, and Windows .NET Server, services are remote procedure call (RPC)–enabled so that they can be called from remote computers over the network. Most services can be added and removed by using the Add/Remove Windows Components option in Add/Remove Programs and can be controlled and configured using the Services snap-in, which is accessible from Administrative Tools.

The following tables list the default services available for typical Windows 2000 Server and Windows NT 4 Server installations and indicates which services are normally installed and started automatically.

Common Windows 2000 Services

Service	*Normally Installed*	*Automatically Started*
Alerter	x	x
Application Management	x	
Boot Information Negotiation Layer		
Certificate Services		x
ClipBook	x	
COM+ Event System	x	
Computer Browser	x	x
DHCP Client		x
DHCP Server		x
Distributed File System	x	x
Distributed Link Tracking Client	x	x
Distributed Link Tracking Server	x	
Distributed Transaction Coordinator	x	x
DNS Client	x	x
DNS Server		x
Event Log	x	x
Fax Service	x	
File Replication	x	
File Server for Macintosh		x
FTP Publishing Service		x
IIS Admin Service	x	x
Indexing Service		x
Internet Authentication Service		x
Internet Connection Sharing	x	
Intersite Messaging	x	
IPsec Policy Agent	x	x
Kerberos Key Distribution Center	x	
License Logging Service	x	x
Logical Disk Manager	x	x
Logical Disk Manager Administrative Service	x	
Message Queuing		x
Messenger	x	x
Net Logon	x	x
NetMeeting Remote Desktop Sharing	x	
Network Connections	x	
Network DDE	x	

(continued)

Common Windows 2000 Services *continued*

Service	*Normally Installed*	*Automatically Started*
Network DDE DSDM	x	
Network News Transport Protocol (NNTP)		x
NT LM Security Support Provider	x	
On-line Presentation Broadcast		
Performance Logs and Alerts	x	
Plug and Play	x	x
Print Server for Macintosh		x
Print Spooler	x	x
Protected Storage	x	x
QoS Admission Control (RSVP)		x
QoS RSVP	x	
Remote Access Auto Connection Manager	x	
Remote Access Connection Manager	x	
Remote Procedure Call (RPC)	x	x
Remote Procedure Call (RPC) Locator	x	
Remote Registry Service	x	x
Remote Storage Engine		x
Remote Storage File		x
Remote Storage Media		x
Remote Storage Notification		
Removable Storage	x	x
Routing and Remote Access	x	
RunAs Service	x	x
Security Accounts Manager	x	x
Server	x	x
Simple Mail Transport Protocol (SMTP)	x	x
Simple TCP/IP Services		x
Single Instance Storage Groveler		
SiteServer ILS Service		x
Smart Card	x	
Smart Card Helper	x	
SNMP Service		x
SNMP Trap Service		
System Event Notification	x	x
Task Scheduler	x	x
TCP/IP NetBIOS Helper Service	x	x
TCP/IP Print Server		x

(continued)

Common Windows 2000 Services *continued*

Service	***Normally Installed***	***Automatically Started***
Telephony	x	
Telnet		
Terminal Services	x	
Terminal Services Licensing		x
Trivial FTP Daemon		
Uninterruptible Power Supply	x	
Utility Manager	x	
Windows Installer	x	
Windows Internet Name Service (WINS)		x
Windows Management Instrumentation	x	
Windows Management Instrumentation Driver Extensions	x	
Windows Media Monitor Service		x
Windows Media Program Service		x
Windows Media Station Service		x
Windows Media Unicast Service		x
Windows Time	x	x
Workstation	x	x
World Wide Web Publishing Service	x	x

Common Windows NT 4 Services

Service	***Normally Installed***	***Automatically Started***
Alerter	x	x
ClipBook Server	x	
Computer Browser	x	x
DHCP Client		x
Directory Replicator	x	
EventLog	x	x
File Server for Macintosh		x
FTP Publishing Service		x

(continued)

Common Windows NT 4 Services *continued*

Service	***Normally Installed***	***Automatically Started***
Gateway Service for NetWare		x
Gopher Publishing Service		x
License Logging Service	x	x
Messenger	x	x
Microsoft DHCP Server		x
Microsoft DNS Server		x
Net Logon	x	x
Network DDE	x	
Network DDE DSDM	x	
Network Monitor Agent		
NT LM Security Support Provider	x	x
Plug and Play	x	x
Print Server for Macintosh		x
Protected Storage	x	x
Remote Access Autodial Manager		
Remote Access Connection Manager		
Remote Access Server		x
Remoteboot Service		
RIP for Internet Protocol		x
Remote Procedure Call (RPC) Locator	x	
Remote Procedure Call (RPC) Service	x	x
SAP Agent		x
Schedule	x	
Server	x	x
Simple TCP/IP Services		x
SNMP		x
SNMP Trap Service		
Spooler	x	x
TCP/IP NetBIOS Helper		
TCP/IP Print Server		
Telephony Service	x	
UPS	x	
Windows Internet Name Service (WINS)		x
Workstation	x	x
World Wide Web Publishing		x

See Also: *daemon*

Service Advertising Protocol (SAP)

A Novell NetWare protocol for advertising network resources.

Overview

Service Advertising Protocol (SAP) is used with Internetwork Packet Exchange (IPX) to enable file and print servers to advertise their availability to clients on a network. SAP periodically advertises the address of the server and the types of services it can provide to clients. It sends its advertisements by making frequent broadcasts to all machines on the local network. Routers generally forward the advertisements so that network services can be made available to machines throughout an IPX internetwork.

Issues

The use of SAP broadcasts on IPX internetworks creates effective limits on the size of a usable IPX internetwork. However, you can configure routers to reduce unnecessary SAP traffic by

- Filtering unnecessary SAP broadcasts using access lists on routers
- Using Cisco Systems IPX routers that allow SAP broadcasts to contain update information only, instead of the entire SAP table, and to forward SAP updates only when a change to the SAP table has occurred

See Also: *Internetwork Packet Exchange (IPX), NetWare protocols*

service-level agreement (SLA)

An agreement to provide services above a specified minimum level.

Overview

A service-level agreement (SLA) is a contractual agreement between a customer and a service provider that outlines what services will be provided and defines the acceptable range of performance and availability of those services. SLAs also generally indicate the costs and penalties that will be incurred when performance and availability fall below acceptable levels. SLAs are typically used in contracts with telecommunications service providers (telcos) that provision wide area networking (WAN) connections.

service pack

A collection of patches, fixes, and minor upgrades for a Microsoft product.

Overview

Service packs are typically identified with a number, such as Service Pack 2. Occasionally, interim releases of service packs are also issued, such as Service Pack 2a (SP2a) for Microsoft Transaction Server (MTS). Service packs for each product are generally cumulative. For example, if you apply Service Pack 3 to a product, you normally do not have to apply Service Packs 1 and 2 first, because Service Pack 3 includes the fixes and upgrades in Service Packs 1 and 2. Microsoft Office service packs are known as service releases and are numbered SR-n instead.

Service packs are usually included in Microsoft Developer Network (MSDN) and TechNet subscriptions and are also available for download from the Microsoft Web site. Check MSDN and TechNet for a list of current service packs and what they do for each product. Before you apply a service pack, read its documentation to determine whether you need to apply it. Occasionally, you must apply service packs in a specific order on a system that is running more than one BackOffice product. Check MSDN, TechNet, or the Microsoft Knowledge Base for information on this kind of situation.

Notes

A service pack is not the same as a decimal release, such as an upgrade from version 4 to version 4.01.

services file

A text file that assigns Transmission Control Protocol (TCP) and User Datagram Protocol (UDP) port numbers to Transmission Control Protocol/Internet Protocol (TCP/IP) protocols and services.

Overview

The entries in the services file are used for well-known service (WKS) records in Domain Name System (DNS) servers and other Windows Sockets applications. In addition, you can use the file to quickly determine which well-known TCP or UDP port number is assigned to a specific network service or protocol.

You will find the services file at the following location on a computer running Microsoft Windows:

- **Windows XP and Windows 2000:** %SystemRoot%\System32\drivers\etc\services
- **Windows 95 and Windows 98:** %WinDir%\Services

Each line in the services file contains the standard name for the service followed by the well-known port number as defined in RFC 1060, an alias, and an optional comment prefixed with a pound sign (#). The following example is part of the sample services file included with Windows:

```
# Format:
# <service name>  <port number>/<protocol>
[aliases...]  [#<comment>]
   ...
ftp-data  20/tcp         # FTP, data
ftp       21/tcp         # FTP. control
telnet    23/tcp
smtp      25/tcp  mail   # Simple Mail
                         Transfer Protocol
time      37/tcp  timeserver
time      37/udp  timeserver
```

Notes

You can change the default port number for a TCP/IP service by editing the services file—for example, if you need to run multiple Simple Network Management Protocol (SNMP) agents or if you want to change the default File Transfer Protocol (FTP) control port to make access more private.

See Also: *hosts file, lmhosts file, Networks file, protocol file*

Services for Macintosh

An optional set of services and protocols in Microsoft Windows 2000 and Windows .NET Server that enables file and print resources to be shared between Macintosh computers and computers running Windows 2000 or Windows .NET Server.

Overview

Services for Macintosh simplifies the administration of resources on heterogeneous networks containing a mix of Macintosh and Windows servers and clients. On the Windows 2000 and Windows .NET Server platforms, these services and protocols are sometimes known under the umbrella name AppleTalk network integration.

Services for Macintosh consists of three optional components:

- **AppleTalk protocol:** Apple's proprietary network protocol for Macintosh computers.
- **File Server for Macintosh (MacFile):** Lets you specify which volumes on your Windows 2000– or Windows .NET Server–based server you want to make available to Macintosh clients as Macintosh-accessible volumes, manages differences in permissions between the two platforms, and makes sure that Macintosh file names are legal NTFS file system (NTFS) names.
- **Print Server for Macintosh (MacPrint):** Enables Macintosh clients to spool their print jobs to a Windows 2000 or Windows .NET Server print server.

Macintosh client machines can access Windows 2000 or Windows .NET Server machines running Services for Macintosh in the same way that they access file and print resources on an AppleShare server. Services for Macintosh supports an unlimited number of client connections using the AppleTalk Filing Protocol (AFP), Apple's presentation-layer protocol for sharing files and applications over an AppleTalk network.

Implementation

On servers running Windows 2000 or Windows .NET Server, you can install File Server for Macintosh or Print Server for Macintosh by using the Windows Components Wizard from Add/Remove Programs in Control Panel, which automatically installs the AppleTalk protocol as well. You can also separately install the AppleTalk protocol by using Network and Dial-Up Connections. Services for Macintosh requires an NTFS-formatted volume in order to operate. When

Services for Macintosh is first installed, a Macintosh-accessible volume called Public Files is created on the server running Windows 2000 or Windows .NET Server. You can create other Macintosh-accessible volumes later using My Computer.

See Also: *AppleTalk*

session initiation protocol (SIP)

A signaling protocol used in Voice over IP (VoIP).

Overview

Session initiation protocol (SIP) is an Internet Engineering Task Force (IETF) initiative to replace part of the older H.323 conferencing protocol developed by the International Telecommunication Union (ITU). Using SIP, a VoIP client can initiate and terminate call sessions, invite members into a conferencing session, and perform other telephony tasks. SIP also enables Private Branch Exchanges (PBXs), VoIP gateways, and other communications devices to communicate with one another in a standardized way.

SIP is designed with simplicity in mind in order to avoid the heavy overhead of H.323. SIP employs ASCII text messages similar in format to Hypertext Transfer Protocol (HTTP) and Simple Mail Transfer Protocol (SMTP) messages. SIP operates at the application level of the Open Systems Interconnection (OSI) reference model.

SIP is defined in RFC 2543. 3Com Corporation has been the driving force behind the development of SIP.

See Also: *H.323, Hypertext Transfer Protocol (HTTP), Open Systems Interconnection (OSI) reference model, Private Branch Exchange (PBX), Simple Mail Transfer Protocol (SMTP), Voice over IP (VoIP)*

session layer

Layer 5 of the Open Systems Interconnection (OSI) reference model.

Overview

The session layer enables sessions to be established and terminated between computers on a network. The session layer does not concern itself with issues such as the reliability and efficiency of data transfer between stations because these functions are provided by the first four layers of the OSI reference model. The session layer is responsible for synchronizing data exchange between computers, structuring communication sessions, and other issues directly related to conversations between networked computers. The session layer is also responsible for name recognition functions at the level of logical network names and for assigning communication ports. For example, the NetBIOS protocol is considered to run at the session level.

The session layer of the OSI reference model is not widely implemented in common local area network (LAN) protocol suites such as Transmission Control Protocol/Internet Protocol (TCP/IP) and Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX). Instead, the top three layers of the OSI model—the application layer, presentation layer, and session layer—are often thought of best as a homogeneous whole subsumed within a generalized application layer.

See Also: *NetBIOS, Open Systems Interconnection (OSI) reference model*

share

Shared (or sharing of) network resources.

Overview

As a verb, the word *share* means to make resources on a computer available to other users on the network who have suitable permissions. Resources that can be shared include disk volumes, directories, and printers.

As a noun, the word *share* is typically another name for a folder or directory that allows users on the network who have suitable permissions to access its contents. The name of a share does not have to be the same as the local name of the object. A share usually contains such items as public data, network applications, and users' home folders.

In Microsoft Windows 98 and Windows Millennium Edition (Me), share access can take two forms:

- **Share-level security:** Controls access to a share using a password that is the same for all users. For example, a user who wants to connect to a share on a peer server running Windows 98 or Windows Me that uses share-level security must know only the password for the share in order to access it. Share-level security is commonly used in small workgroups.

- **User-level security:** Controls access to a share through user credentials and group membership. For example, one group of users can be assigned read-only access to the share, another group can be assigned full access, and a third group can be assigned custom access. In order for user-level security to work, the network must have a security provider (such as a Windows 2000 or Windows .NET Server domain controller).

In Windows 2000, shares are always based on user-level security. A network user's access to a shared folder on an NTFS file system (NTFS) volume is governed by a combination of NTFS permissions and shared folder permissions.

Notes

Share names that do not conform to the MS-DOS 8.3 naming convention cannot be accessed by MS-DOS–based workstations.

See Also: *NTFS permissions (Windows 2000, Windows XP, and Windows .NET Server)*

shared folder

A folder that has been shared to allow its contents to be accessed by users on the network (provided they have suitable permissions).

See: *share*

shared folder permissions

In Microsoft Windows, a set of permissions that can be assigned to a shared folder to control access by users and groups on the network.

Overview

Shared folder permissions can be applied only to the entire shared folder, not to its files and subfolders. If you want to control access to individual files and subfolders within a network share, you can use the more granular NTFS file system (NTFS) permissions on Windows NT, Windows 2000, Windows XP, and Windows .NET Server. In addition, shared folder permissions are effective only when a user accesses the folder over the network. If a user can log on locally to the console of the computer where the share is located, that user can always access the contents of the shared folder regardless of the shared folder permissions set (unless the folder is on an NTFS volume and the NTFS permissions restrict the user from accessing the resource). Finally, shared folder permissions are the only way to secure network resources that are stored on file allocation table (FAT) volumes.



○ Not Shared
● Shared As:

Share Name: TOOLS98

Comment: Windows 98 share

Name:	Access Rights:
Domain admins	Custom [RWCDTFA]
Domain users	Read-Only
Mitch	Full Access
The World	Read-Only

Name: Domain admins

○ Read-Only Access Rights
○ Full Access Rights
● Custom Access Rights:
☑ [R]ead Files
☑ [W]rite to Files
☑ [C]reate Files and Folders
☑ [D]elete Files
☑ Change File A[t]tributes
☑ List [F]iles
☑ Change [A]ccess Control

Shared folder permissions. *The Change Access Rights dialog box in Windows 98.*

If a user belongs to two or more groups, and these groups have different permissions on a given share, the user's ability to access the folder over the network can be calculated by two rules:

- The effective permission is the least restrictive (most permissive) permission, as in this example:

```
read + change = change permission
```

- No access or deny access overrides all other permissions, as in this example:

```
read + no access = no access
```

Different versions of Windows employ different mechanisms for assigning shared folder permissions to users and groups. The following tables show the permissions for each of these operating systems and lists what the permissions allow users to perform.

Windows 98 and Windows Me Shared Folder Permissions

Permission	*What It Allows Users to Do*
Read-Only Access Rights	List names of folders and files Browse hierarchies of folders Display the contents of folders and files Run executable files
Full Access Rights	Create and delete folders Add files to folders Create, modify, and delete files Change file attributes (Includes read permissions)
Custom Access Rights	Depending on the options specified, allows users to perform the following actions: Read files Write to files Create files and folders Delete files Change file attributes List files Change access control

Windows NT 4 Shared Folder Permissions

Permission	*What It Allows Users to Do*
No Access	Connect to a share without viewing its contents
Read	List names of folders and files Browse hierarchies of folders Display the contents of folders and files Run executable files
Change	Create and delete folders Create, modify, and delete files Change file attributes Includes read permissions
Full Control	Take ownership of files on NTFS volumes Change file permissions on NTFS volumes Includes read and change permissions



● Shared As:

Share Name: ToolsNT

Comment: Windows NT 4.0 share

User Limit:

○ Maximum Allowed

● Allow 10 Users

Access Through Share: ToolsNT

Owner:

Name:

Domain Admins	Change
Domain Users	Read
Everyone	Read
Mitch	Full Control

Type of Access: Change

Shared folder permissions. *The Access Through Share Permissions dialog box in Windows NT 4.*

Windows 2000, Windows XP, and Windows .NET Server Shared Folder Permissions

Permission	*What It Allows Users to Do*
Read	List names of folders and files Browse hierarchies of folders Display the contents of folders and files Run executable files
Change	Create and delete folders Add files to folders Create, modify, and delete files Change file attributes Includes read permissions
Full Control	Take ownership of files on NTFS volumes Change file permissions Includes read and change permissions

Notes

When you first share a folder in Windows 2000, Windows XP, and Windows .NET Server, the default permissions are Full Control for the Everyone group. You should remove this default permission and assign more appropriate permissions to the share, such as change permission for Domain Users and full control for Administrators.



Tools2000 Properties

You can share this folder among other users on your network. To enable sharing for this folder, click Share this folder.

○ Do not share this folder
● Share this folder
Share name: Tools2000
Comment: Windows 2000 share
User limit: ○ Maximum allowed ● Allow 10 Users

To set permissions for how users access this folder over the network, click Permissions.

To configure settings for Offline access to this shared folder, click Caching.

Permissions for Tools2000

Name
Domain Admins (RDOMAIN\Domain Adm...
Domain Users (RDOMAIN\Domain Users)
Everyone
Mitch (RDOMAIN\mitch)

Permissions:	Allow	Deny
Full Control	☑	☐
Change	☑	☐
Read	☑	☐

Shared folder permissions. *The Permissions dialog box in Windows 2000.*

When you assign permissions to shared folders, use group accounts instead of user accounts in order to simplify administration. Give users the most restrictive permissions that still enable them to perform the necessary tasks on the files in the share.

See Also: *NTFS permissions (Windows 2000, Windows XP, and Windows .NET Server), NTFS permissions (Windows NT), share*

shared SCSI bus

A Small Computer System Interface (SCSI) disk system shared between two nodes in a cluster.

Overview

Shared SCSI buses are used in clustering to allow multiple nodes in a cluster to access the same disk system. The shared SCSI bus logically represents the total interconnection between the cluster and the shared storage devices, but in practice this consists of a number of electrically separate SCSI bus segments. Each disk on a shared SCSI bus is owned by only one of the cluster's nodes. If the disk group fails over, ownership of the disk switches from the failed node to the other node.

Notes

When using a shared SCSI bus with Windows Clustering on Microsoft Windows 2000, you can remove the internal termination of the SCSI bus and use Y-cables or trilink connectors for terminating the external bus. In this way, you can remove the device if maintenance is required without affecting other devices on the bus.

See Also: *clustering, Small Computer System Interface (SCSI)*

share-level security

A mode of security on computers running Microsoft Windows 98 and Windows Millennium Edition (Me) that protects shared folders and printers using a password.

Overview

When using share-level security, all users use the same password to access the resource and any user who knows the password has permission to use the resource. The security options for protecting a shared folder using share-level security include

- Allowing read-only access, with or without a password
- Allowing full access, with or without a password
- Specifying one password for read-only access and another for full access



pub Properties

○ Not Shared
● Shared As:
Share Name: PUB
Comment:
Access Type:
○ Read-Only
○ Full
● Depends on Password
Passwords:
Read-Only Password: *****
Full Access Password: ********

Share-level security. *The Sharing tab of a folder's Properties dialog box.*

Share-level security is often used in small peer-to-peer networks with computers running Windows 98 or Windows Me. Use the Network utility in Control Panel to enable share-level security.

See Also: *peer-to-peer network, user-level security*

shell

The user interface for an operating system.

Overview

The term *shell* refers to the external user-accessible portion of an operating system, and the term *kernel* refers to the part that is normally hidden from the user. On UNIX platforms *shell* usually refers to the command-line interface (also called the command interpreter), but on Microsoft Windows platforms the desktop graphical user interface (GUI) element can also be considered a type of shell.

In a UNIX command-line shell, when a user types a command such as ls (list directory contents), the shell executes the associated program called ls. When the shell executes the command, it typically starts a new process for the command and goes into a sleep state until the command finishes executing, at which time the shell wakes up and issues a prompt to indicate that it is ready to receive another command. The output of shell commands is directed by default to Standard Output, which is the screen, but you can redirect command outputs to files and other applications. One advantage of using a command-line shell is that shell scripts can be written for batch execution of a series of shell commands.

Various shells are available for different UNIX platforms, each tailored to a different administration and programming environment. One commonly used shell is the Bourne Shell, which functions as both a command interpreter and a high-level programming language in which shell scripts can be used to automate groups of processes. Other UNIX shells include the C Shell of System V UNIX, which includes job control and command history mechanisms, and the Korn shell, which supports command-line editing.

S

Notes

The command prompt in Windows provides similar functionality to UNIX shells, although scripting capabilities are more limited because they are based on the MS-DOS command language. The Windows Script Host (WSH) overcomes these limitations by supporting higher-level scripting languages such as Microsoft Visual Basic, Scripting Edition (VBScript), and JScript.

UNIX shell scripts are called batch files in Windows programming environments. In an IBM mainframe environment, they are called EXECs.

See Also: *kernel, UNIX, Windows Script Host (WSH)*

shielded twisted-pair (STP) cabling

Twisted-pair cabling that contains internal shielding.

Overview

The shielding in shielded twisted-pair (STP) cabling is designed to reduce crosstalk and other forms of electromagnetic interference (EMI). The outer insulating jacket contains an inner braided copper mesh to shield the pairs of twisted cables, which themselves are wrapped in foil.

STP cabling is more expensive than unshielded twisted-pair (UTP) cabling. It has an impedance of 150 ohms, has a maximum length of 295 feet (90 meters), and is used primarily in networking environments with a high amount of EMI due to motors, air conditioners, power lines, or other noisy electrical components. STP cabling is the default type of cabling for IBM Token Ring networks.

STP cabling comes in various grades or categories defined by the Electronic Industries Association/Telecommunications Industry Associaiton (EIA/TIA) wiring standards, as shown in the following table.

STP Cabling Categories

Category	*Description*
IBM Type 1	Token Ring transmissions on AWG #22 wire up to 20 megabits per second (Mbps)
IBM Type 1A	Fiber Distributed Data Interface (FDDI), Copper Distributed Data Interface (CDDI), and Asynchronous Transfer Mode (ATM) transmission up to 300 Mbps
IBM Type 2A	Hybrid combination of STP data cable and Category 3 (Cat3) voice cable in one jacket
IBM Type 6A	AWG #26 patch cables

See Also: *crosstalk, electromagnetic interference (EMI), shielding, unshielded twisted-pair (UTP) cabling*

shielding

Metallic material added to cabling to reduce susceptibility to noise due to electromagnetic interference (EMI).

Overview

Shielding usually takes one of two forms:

- A braided copper or aluminum mesh enclosing the signal-carrying wires. This type of shielding offers superior performance and should be used in industrial areas where heavy machinery generates a lot of EMI.
- An aluminum foil sleeve that encloses individual wires or the entire wire bundle. This kind of shielding is more suitable for office environments to shield against noise due to air conditioners, fans, and other motors.

For best performance, you can combine both kinds of shielding. An additional uninsulated drain wire is sometimes used to terminate the shield; it runs the length of the wire in contact with the foil sleeve or mesh.

Shielded cabling is generally more expensive than unshielded cabling.

See Also: *coaxial cabling, shielded twisted-pair (STP) cabling*

short

A condition that occurs when signal-carrying conductors make contact.

Overview

The effect of a short is similar to having a break in the cable—network communication ceases. To find or isolate a short, use a cable tester or time domain reflectometer. Cable shorts can occur only in copper cables, not fiber-optic cables, although breaks can occur in fiber-optic cables.

See Also: *network troubleshooting*

Shortest Path First (SPF)

A routing algorithm used by the Open Shortest Path First (OSPF) protocol.

Overview

Also called the Dijkstra algorithm, Shortest Path First (SPF) is a routing algorithm in which a router computes the shortest path between each pair of nodes in the network. When an OSPF router is initialized, it sends a Hello message to determine whether it has any neighbors (routers that have an interface on the same network). Neighbors respond to the initiating router by using the same Hello packets. In fact, these Hello packets also serve to tell other routers that the transmitting router is still alive (keep-alive function). If more than two OSPF routers are on the internetwork, the Hello protocol causes one of the routers to be designated as the one to send out link state advertisements (LSAs) to all other routers on the network.

Neighbors then synchronize their topological databases with each other to become "adjacent" routers. Each router periodically floods the network with cost information for its adjacent nodes in the form of LSAs, allowing them to compile complete tables of network connections and calculate the path of least cost between any two nodes. Finally, each router analyzes its own database of network topology information and uses it to determine a shortest-path tree using itself as the root; from this tree, it derives a routing table for itself.

See Also: *Open Shortest Path First (OSPF)*

Short Message Service (SMS)

A protocol for sending short text messages over cellular communications systems.

Overview

Short Message Service (SMS) is a two-way text-based messaging service originally developed for the Global System for Mobile Communications (GSM) cellular telephone systems deployed across Europe. SMS allows messages to be sent or received simultaneously with voice, fax, or data transmission over GSM systems because it uses a separate signaling path instead of a dedicated channel. SMS thus works reliably even during peak usage periods of cellular systems. SMS offers an advantage over paging systems in that it notifies the sender using an alert when the recipient has received the message.

SMS can send short messages of up to 160 alphanumeric characters between two cellular users. SMS messages are typically charged to the senders, which encourages users to leave their cell phones on at all times in order to receive SMS messages and alerts.

Implementation

SMS works as a store-and-forward service in which messages that are sent are stored at an SMS messaging center until the recipient can connect and receive them. To use SMS, the user needs a subscription to a GSM bearer that supports SMS and a cell phone that supports SMS. The SMS function must be enabled for that user, typically through a subscription charge together with a per-message fee. Some SMS systems support compression to increase the amount of information that can be included in a message, and support concatenation of messages to create a single message from several message fragments.

Prospects

SMS has proven so popular in Europe that many non-GSM cellular systems around the world have also been implementing it in various degrees. Examples include Digital Advanced Mobile Phone System (D-AMPS) in the United States and Personal Digital Cellular (PDC) in Japan. The worldwide cdmaOne (IS-95b) system supports larger 256-byte two-way messages, but the analog Advanced Mobile Phone System (AMPS) still deployed in much of the United States supports 14-byte receive-only messaging.

SMS has also helped energize the drive toward deploying wireless application protocol (WAP) by creating consumer readiness for broadband wireless e-business.

See Also: *2G, 2.5G, cellular communications, Global System for Mobile Communications (GSM), Wireless Application Protocol (WAP)*

S-HTTP

Stands for Secure Hypertext Transfer Protocol, an Internet protocol for encryption of Hypertext Transfer Protocol (HTTP) traffic.

See: *Secure Hypertext Transfer Protocol (S-HTTP)*

SIBone

Stands for Satellite Internet Backbone, a satellite-based network exchange point.

See: *Satellite Internet Backbone (SIBone)*

SID

Stands for security identifier, an internal number that is used in Microsoft Windows 2000, Windows XP, and Windows .NET Server that uniquely identifies a user, group, or other object.

See: *security identifier (SID)*

signal

An electrical transmission that carries information.

Overview

In its simplest form, a signal is a form of alternating current (AC) running on network cabling that is generated by a networking component such as a network interface card (NIC). Signals are usually purposeful transmissions, as opposed to noise, which is an undesirable transmission generated randomly by networking components and the surrounding environment. Signals can be classified as:

- **Electrical:** Travel over copper wire as a medium
- **Optical:** Travel through fiber-optic cabling
- **Electromagnetic:** Travel through free space, as in wireless networking and cellular communications

In the computer networking environment, signals are generally square waves and thus digital in nature, carrying information in binary format. To accomplish this, information must be encoded into the signal using a line coding mechanism, a technique for representing binary information using a series of discrete voltages. The earliest digital signaling method to be used in computer networking is the unipolar nonreturn to zero (NRZ) mechanism, in which a binary 1 is represented by a positive voltage and a zero by no voltage. Ethernet uses a different method called Manchester coding, and other networking technologies employ other kinds of signaling methods.

See Also: *line coding, Manchester coding, network interface card (NIC), signaling*

signaling

The process in which control information is exchanged during establishment of a communication session.

Overview

In wide area network (WAN) technologies, signaling is the process by which the devices at either end of a WAN link communicate with each other to establish common timing and signal-flow settings. Signaling must occur before a communication session is established and before data is actually sent over the link. Session-establishment signaling between telecommunications devices generally has a certain degree of latency. That is, it takes time for sessions to be negotiated and established before data can be sent. For example, analog modems typically take 15 to 30 seconds from dial-up until the connection is established, and Integrated Services Digital Network (ISDN) dial-up services sometimes take only 1 to 2 seconds to establish a connection.

Implementation

Signaling between telecommunications devices generally takes place by one of two methods:

- **In-band signaling:** The signaling information is sent in the same communication channel as the data itself.
- **Out-of-band signaling:** The signaling happens on a separate channel, usually a separate pair of wires.

See Also: *analog modem, in-band signaling, Integrated Services Digital Network (ISDN), latency, out-of-band (OOB) signaling, wide area network (WAN)*

signal loss

The loss of strength of a signal as it propagates over a medium.

Overview

Signal loss generally refers to loss of signal strength in guided media such as copper cabling and fiber-optic cabling. Unguided media such as wireless networking technologies have signals that decrease in power per unit area primarily because of the inverse square law.

A number of mechanisms can cause signal loss in a wire or cable:

- **Attenuation:** Caused by resistive losses in the cable and affects only copper cabling
- **Absorption:** Causes signal loss in fiber cabling because the glass core material is not perfectly transparent
- **Fractures:** Can result in both attenuation and absorption of signal strength
- **Splices, connectors, and couplings:** Involve dissimilar materials joined together and generally produce some loss

Signal loss is usually expressed in units of decibels (dB) per source of the loss. The following table shows typical signal loss values for fiber-optic cabling. These rough values are useful for estimating total signal loss, which you can calculate by simply adding the loss for each element in the light path.

Signal Loss Values for Fiber-Optic Cabling

Source of Loss	*Approximate Signal Loss*
Connector loss	3 dB/termination
Coupling loss	2 dB/coupler
Intrinsic loss	6 dB/1000 meters
Microbending loss	Increases with decreasing bend radius
Splice loss	4 dB/splice

Notes

The total end-to-end signal loss of a light path through a fiber-optic cabling system is known as the optical power budget. If this value is greater than the power launch rating of your line driver, your system will not work.

Simple Mail Transfer Protocol (SMTP)

An application-layer protocol for delivery of e-mail over the Internet.

Overview

Simple Mail Transfer Protocol (SMTP) defines a message format and forwarding procedure to enable messages to be sent between hosts on the Internet. As such, SMTP is one of the most important protocols in use on the Internet. The basics of SMTP are defined in RFCs 821 and 822.

Implementation

To forward a message, an SMTP host first establishes a connection with a second SMTP host using Transmission Control Protocol (TCP) port 25. An SMTP session is then initiated by sending a HELO command and receiving an OK response. The first host then uses the following commands to forward messages to the second host:

- **MAIL FR:** Identifies the sending host to the receiving host
- **RCPT TO:** Identifies the targeted message recipient to the receiving host by using the Domain Name System (DNS) format user@DNSdomain
- **DATA:** Initiates the sending of the message body as a series of lines of ASCII text, ending with a single period (.) alone on a line
- **QUIT:** Closes the SMTP connection

SMTP uses plain 7-bit ASCII text to send e-mail messages and to issue SMTP commands to receiving hosts. Multipurpose Internet Mail Extensions (MIME) is typically used to encode multipart binary files including attachments into a form that SMTP can handle.

Notes

Note that SMTP only provides message transport only from one SMTP host to another. Support for storing messages in mailboxes is provided by Post Office Protocol version 3 (POP3) and Internet Mail Access Protocol version 4 (IMAP4).

See Also: *ASCII, Internet Mail Access Protocol version 4 (IMAP4), Multipurpose Internet Mail Extensions (MIME), Post Office Protocol version 3 (POP3), Transmission Control Protocol (TCP)*

Simple Network Management Protocol (SNMP)

A popular protocol for network management.

Overview

Simple Network Management Protocol (SNMP) is an Internet-standard Layer-7 (application layer) protocol for collecting information from and configuring network devices such as servers, printers, hubs, switches, and routers on an Internet Protocol (IP) network. SNMP can be used to collect information about network statistics from these devices and to relay this information to a central management console to monitor network health, trap errors, perform diagnostics, and generate reports. Typical statistical information might include the number of packets or frames sent or received per second and the number of errors per second. SNMP can also be used for reading and sometimes modifying device configuration information such as the IP address of an interface, or the version of the operating system running on the device.



Simple Network Management Protocol (SNMP). *How SNMP can be used to manage devices on a network.*

SNMP was developed in the late 1980s and is still the most popular network management protocol in use. There are two versions of SNMP:

- **SNMPv1:** This is the original version of SNMP, which lacked security for ensuring the authenticity and integrity of SNMP messages.
- **SNMPv2:** This version has increased security that supports a simple authentication scheme based on SNMP communities.

SNMPv2 is defined in RFCs 1901 through 1908 and 2089.

Implementation

SNMP is a client/server protocol that consists of two components that work together:

- **SNMP agents:** These are programs that run on the network devices to be managed (called managed devices) and that collect Transmission Control Protocol/Internet Protocol (TCP/IP)–related configuration information and statistics about the operation of the device. Agents do not require heavy CPU usage to run. The types of information that an agent can collect are defined in a local database called a Management Information Base (MIB). MIB databases are hierarchical and contain managed objects that have uniquely assigned identifiers issued by the International Organization for Standardization (ISO). SNMP variables are specific instances of managed objects in MIBs. Agents running on managed devices monitor specific sets of SNMP variables and temporarily store this information until the agent is polled by a management system, whereupon the agent reports the values of the stored information to the management system. Most network devices have built-in SNMP agent software and associated MIBs.
- **SNMP management system:** Also called Network Management System (NMS), this is software that runs on an administrative console and can display data gathered from managed devices in a user-friendly form through a graphical user interface (GUI). SNMP Management Systems software can notify the administrator when certain conditions (such as errors) occur. Most SNMP management systems can also automatically determine the topology and components of a network with SNMP-enabled computers, routers, hubs, and switches and can display network topology, traffic, and conditions in graphical format. SNMP management systems regularly poll managed devices using SNMP messages for statistical and configuration information and then store this information in a central database, which can be used to present the information in a friendly way to users.

SNMP is a simple protocol that is message-based in operation. SNMP messages are sent between management consoles and managed devices over User Datagram Protocol (UDP) port 161. These messages contain a header and a payload called the Protocol Data Unit (PDU). The header contains information about the community being referenced. A community is a subset of agents that will be monitored using a specific management system and institutes a primitive level of security, acting as a primitive means of authentication. SNMP messages come in four types, three of which are issued by management stations and one by agents:

- **Get:** Issued by the management system to an agent on a managed device to read the value of a specific variable on the device.
- **Getnext:** Issued by the management system to determine which SNMP variables are supported by an agent running on a managed device and to traverse a series of variables to read their values sequentially.
- **Set:** Issued by the management system to an agent on a managed device to write a value for a specific variable on the device.
- **Trap:** Issued by an agent running on a managed device when an error or alert condition occurs. The trap message is sent to the management system to alert administrators of the situation.

SNMP version 2 adds additional security features, can be applied to network architectures other than TCP/IP, and supports additional data types. It is only partially backward compatible with SNMP 1. SNMP 2 also defines two additional types of messages:

- **Getbulk:** Similar to getnext but allows the retrieval of greater amounts of information in one data block
- **Inform:** Allows management systems to send information to other management systems using a trap-like message

The management station regularly sends get, getnext, and set messages to the SNMP agent on the managed device, in effect periodically polling the agent for the status of the device. The agent verifies the community name in the message, verifies the IP address or host name of the SNMP management system, processes the request, and sends the results to the management system.

Notes

A new version of SNMP called SNMPv3 is currently being developed to enhance the security of earlier versions.

See Also: *application layer, International Organization for Standardization (ISO), Internet Protocol (IP), Management Information Base (MIB), network management, port, User Datagram Protocol (UDP)*

Simple Object Access Protocol (SOAP)

A message-passing protocol used to enable distributed Web services.

Overview

Simple Object Access Protocol (SOAP) is a protocol developed by Microsoft Corporation, IBM, and other vendors to enable Web applications and services to communicate with one another over the Internet. SOAP enables these services to communicate regardless of the platform they are running on or the programming languages with which they were developed. SOAP is a cross-platform, standards-based solution that is easy to implement and that has broad industry support. SOAP has been proposed as a World Wide Web Consortium (W3C) standard.

Implementation

SOAP connects components of distributed applications using an XML–based RPC mechanism based on Extensible Markup Language (XML) and the Remote Procedure Call (RPC) architecture. Using SOAP, an application on one host can invoke object methods and functions on a remote host running a SOAP application. To perform this, the first application creates a block of XML text that contains the location of the remote object on the network and the data needed by the object to invoke the method. The application then passes the XML block to a SOAP server that encapsulates and transports the message block to the remote application using Hypertext Transfer Protocol (HTTP) or some other common Internet application layer protocol. Once the method has been invoked and execution is complete, the remote application returns a similar XML–based message to the initiating application.

SOAP is intended to complement existing distributed application platforms such as Microsoft's Distributed Component Object Model (DCOM) and the Open Group's Common Object Request Broker Architecture (CORBA). SOAP also forms the underlying transport mechanism for the Electronic Business Extensible Markup Language (ebXML) developed by the Organization for the Advancement of Structured Information Standards (OASIS).

See Also: *Common Object Request Broker Architecture (CORBA), Distributed Component Object Model (DCOM), Electronic Business Extensible Markup Language (ebXML), Hypertext Transfer Protocol (HTTP), remote procedure call (RPC), World Wide Web Consortium (W3C), XML*

simple volume

A type of disk volume in Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Overview

In Windows 2000, Windows XP, and Windows .NET Server, a simple volume is one made up of one or more contiguous blocks of free disk space on a single physical disk. You can extend simple volumes to include additional free disk space from the initial drive or from other drives, forming a spanned volume. You can create simple volumes only on dynamic volumes created using Disk Management. Simple volumes have no fault tolerance but can be mirrored to form mirrored volumes.

See Also: *volume*

simplex

A form of communication in which signals are sent in only one direction.

Overview

Simplex is different from duplex, in which signals can simultaneously be sent and received by a station, and from half-duplex transmission, in which signals can be sent or received but not both at the same time. Simplex transmission occurs in many common communication applications, the most obvious being broadcast and cable television. It is not used in true network communication because stations on a network generally need to communicate both ways. Some forms of network communication might seem to be simplex in nature, such as streaming audio or video, but the communication actually takes place using bidirectional network traffic, usually Transmission Control Protocol (TCP) traffic. Simplex communication is not included in the V series recommendations of the International Telecommunication Union (ITU).

See Also: *duplex, half-duplex*

single domain model

A type of Microsoft Windows NT domain model used for small networks.

Overview

In the single domain model, all global users and group accounts reside in a single domain and all network resources reside in the same domain. The single domain model is simple to implement and offers centralized administration of accounts and resources. Although the model can theoretically work for as many as 40,000 accounts, it performs poorly with large numbers of accounts. The single domain model is, therefore, generally used only in small to mid-sized Windows NT–based networks.

When you upgrade a Windows NT–based network based on the single domain model to a Windows 2000–based network, you usually end up with a single domain in Active Directory directory service. You can then use Active Directory to create organizational units (OUs) to organize your network and assign administrative rights and permissions.

See Also: *complete trust model, master domain, multiple master domain model*

single master domain model

A type of Microsoft Windows NT domain model used for large networks.



Single master domain model. *The structure of the single master domain model.*

Overview

In the single master domain model, all global users and group accounts reside in a single Windows NT domain called the accounts domain. Network resources reside in other domains are called resource domains. Each resource domain needs to have a trust relationship with the accounts domain. Users who log on to their accounts in the accounts domain can access shared network resources in any resource domain if they have the appropriate permissions. The advantages and disadvantages of using this model are shown in the following table.

Pros and Cons of the Single Master Domain Model

Pros	*Cons*
Not difficult to implement—one trust per resource domain	Poor performance when the number of accounts is large
Centralized administration of accounts	Local groups must be created in each resource domain
Resource domains manage their own resources	
Works for up to 40,000 accounts	

When you upgrade a Windows NT–based network based on the single master domain model to a Windows 2000–based network, you usually perform the upgrade from the top down. You first upgrade the master domain to a Windows 2000 domain based on Active Directory directory service. Then you upgrade resource domains to child domains within a directory tree whose root domain is the former master domain. You can move user accounts from the master domain to the domains where users actually work, because two-way transitive trusts enable users in any domain within the domain tree to access resources in any other domain.

Alternatively, companies with a centralized IT (information technology) department can upgrade both the master domain and the resource domains to a single Windows 2000 domain. Organizational units (OUs) can then be created within Active Directory to mirror the administrative structure of the former master domain model. Administrative rights and permissions can be assigned to users and groups based on the new OUs. Here are the advantages of using this approach:

- One domain to manage
- No trust relationships to create or manage
- Faster searching because all directory objects reside in a single domain

See Also: *complete trust model, multiple master domain model, single domain model*

single-mode fiber-optic cabling

A type of fiber-optic cabling that can carry only one signal at a time.

Overview

Single-mode fiber-optic cabling typically has a core that is only 5 or 10 micrometers in diameter—much smaller than the core of multimode fiber, which needs room to carry many different light signals simultaneously. Single-mode fiber uses light generated by a laser-emitting diode to carry signals. Such laser light is extremely stable and uniform and can be accurately focused, making it perfect for long-distance transmission. Single-mode fiber has extremely low signal attenuation and is typically used for long cable runs because it can generally carry signals up to 50 times farther than multimode fiber, which can carry many different signals simultaneously.

Uses

Use single-mode fiber-optic cabling for long cable runs or where extra bandwidth is required. The bandwidth of single-mode fiber is typically double that of multimode fiber. Be aware, however, that installing single-mode fiber requires more care and expertise to avoid signal loss, especially if you terminate the cable with connectors. Single-mode fiber is also more expensive than multimode because multimode systems use transmitters that have cheaper light-emitting diodes, but single-mode systems use more expensive laser-emitting diodes in their transmitters. Also, when you use single-mode fiber-optic cabling, the ancillary devices such as line drivers cost more.

See Also: *fiber-optic cabling, multimode fiber-optic cabling*

Single Sign On (SSO)

Any technology that requires users to have only one set of credentials to access network resources.

Overview

Single Sign On (SSO) has been an elusive goal in enterprise networking for many years. Enterprise networks are generally heterogeneous systems comprised of operating systems and applications from many vendors, and users on these networks often require different sets of credentials for each platform they need to access. As a result, different vendors have pursued the concept of SSO, whereby users employ only one set of credentials to log on to the network and access any applications or resources they might need.

SSO can be viewed as either a benefit or a hazard. From the benefit point of view, some analysts estimate that password maintenance costs the average enterprise hundreds of dollars per user each year—a cost that can be reduced through implementing SSO technologies. On the other hand, the complexity of implementing true SSO in a heterogeneous networking environment can be so great that many network administrators are loath to attempt it.

Marketplace

The foundation for Microsoft Windows 2000's SSO solution is the Kerberos authentication protocol, which can enable SSO to be implemented in a mixed Windows/UNIX environment. Novell has its own SSO solution called Novell Single Sign On (NSSO) that can be used in a mixed Novell/Windows environment. Security companies such as Entrust Technologies and RSA Security have offered SSO solutions based on public key cryptography systems. Third-party companies such as Axent Technologies also offer their own SSO systems for cross-platform authentication.

See Also: *authentication protocol, Kerberos, public key cryptography*

SIP

Stands for session initiation protocol, a signaling protocol used in Voice over IP (VoIP).

See: *session initiation protocol (SIP)*

SLA

Stands for service-level agreement, an agreement to provide services above a specified minimum level.

See: *service-level agreement (SLA)*

SLIP

Stands for Serial Line Internet Protocol, a serial encapsulation protocol.

See: *Serial Line Internet Protocol (SLIP)*

Small Business Server

A complete, integrated server solution from Microsoft Corporation for businesses with 25 or fewer PCs.

Overview

Microsoft BackOffice Small Business Server includes file, print, and application services; communication services; and Internet connection services.

Small Business Server integrates these applications from the BackOffice family of products:

- Microsoft Windows NT
- Microsoft Exchange Server
- Microsoft SQL Server
- Internet Information Services
- Microsoft Proxy Server

Small Business Server also extends this BackOffice functionality by including the following:

- Microsoft Fax Service
- Microsoft Modem Sharing Server
- Internet connectivity for small businesses

Small Business Server is easy to set up and manage, and it can grow with a business's needs. It includes the following features:

- Unified, integrated administration through the Small Business Server Console
- Simple, wizard-based installation and configuration (from creating users to installing printers and establishing Internet connectivity)
- Easy setup and configuration of client computers using the Set Up Computer Wizard
- Extensive online help and troubleshooting tips for the administrator and users
- An easy upgrade path to BackOffice Server when a business grows beyond 25 computers
- Support for e-mail, the Internet, and fax
- Scheduling and collaboration features through the Microsoft Outlook desktop information manager and Exchange Server

For More Information

Visit *www.microsoft.com/sbserver.*

Small Computer System Interface (SCSI)

A popular general-purpose input/output (I/O) bus.

Overview

Small Computer System Interface (SCSI) is a hardware bus specification for connecting storage devices and peripherals to a computer using a parallel transmission interface. SCSI was developed by Apple Computer and is widely used in the enterprise environment for servers and high-end workstations. Although SCSI is mainly used as a hard disk interface, it can also be used for connecting peripherals such as printers and scanners. The main competitor to SCSI is the Integrated Drive Electronics (IDE) interface, which is widely used in commodity PCs.

SCSI is defined by a number of American National Standards Institute (ANSI) standards that include the SCSI-1, SCSI-2, SCSI-3, and SCSI-5 specifications.

Advantages and Disadvantages

SCSI has two main advantages over IDE:

- SCSI supports daisy-chaining of multiple devices, making SCSI drives a more scalable solution for internal PC storage systems.
- SCSI drives generally have faster transfer speeds and better performance than IDE drives.

On the negative side, this extra performance comes at a significantly higher cost, and IDE drives have been closing in on SCSI speeds for the last few years. SCSI also has multiple versions that are incompatible with one another.

Types

SCSI standards and implementations can be classified in several ways. For example, SCSI devices differ depending on the width of the data path used, giving two categories:

- **Narrow SCSI:** One byte (8 bits) of data are transferred for each clock cycle. Narrow SCSI devices typically use the 50-pin Centronics SCSI interface.
- **Wide SCSI:** Two bytes (16 bits) are transferred each cycle. Wide SCSI devices usually employ a 68-pin parallel SCSI interface.

SCSI devices can also be classified according to their use of grounding:

- **Single-ended:** These use unbalanced transmission in which one data lead and one ground lead establish single-ended signal transmission over the bus. This type of device is more prone to the effects of noise and is less forgiving of cable lengths beyond specifications. Single-ended (SE) SCSI is generally considered obsolete.
- **Differential:** These use balanced transmission in which there are two data leads, neither of which are at ground potential. These devices are generally more expensive but are resistant to the effects of noise and can often function over distances that exceed the SCSI specifications. Differential SCSI is used in two common forms: high-voltage differential (HVD) and low-voltage differential (LVD) SCSI.

Finally, forms of SCSI are differentiated by the clock speed used:

- **SCSI:** This is the original 1986 SCSI-1 standard and supports transmission rates of 5 megabytes per second (MBps) over an 8-bit bus and supports up to seven daisy-chained devices. SCSI cables typically use Centronics 50 or Telco 50 connectors, and the chained bus length must not exceed 20 feet (6 meters).
- **Fast SCSI:** Sometimes referred to as Plain SCSI, the SCSI-2 standard supports transmission rates of 10 MBps over an 8-bit bus (called Fast Narrow SCSI) using Micro DB50 connectors or 20 MBps over a 16-bit bus (called Fast Wide SCSI). Fast SCSI supports up to seven daisy-chained devices and the bus length must not exceed 20 feet (6 meters) for Fast Narrow SCSI and 10 feet (3 meters) for Fast Wide SCSI.
- **Ultra SCSI:** Sometimes called Fast-20 SCSI, the SCSI-3 standard supports transmission rates of 20 MBps over an 8-bit bus (Narrow Ultra SCSI) or 40 MBps over a 16-bit bus (Wide Ultra SCSI). Ultra SCSI can support up to 15 daisy-chained devices and its cables typically use MicroD 68-pin or Mini 68 connectors. There are also variants of Ultra SCSI called Ultra2 SCSI, which supports 40 MBps (Narrow) or 80 MBps (Wide), and Ultra3 SCSI, which supports 80 MBps (Narrow) or 160 MBps (Wide).
- **SCSI-5:** Also called Very High Density Connector Interface (VHDCI), this form of SCSI is similar to SCSI-3 but uses a smaller 0.8 millimeter connector.

All these various forms of SCSI are incompatible with one another.



Small Computer System Interface (SCSI). *Four varieties of SCSI interface.*

Implementation

To implement SCSI on a system, use a SCSI adapter to interface with the system bus, suitable SCSI devices such as SCSI hard drives, SCSI cables to daisy-chain the devices, and SCSI terminators for the ends of the bus. Each device on a SCSI bus must have a SCSI device ID number assigned to it, allowing SCSI to be used for daisy-chaining a number of devices together on a single parallel bus. You can change SCSI IDs by using dip switches or jumpers or by using special SCSI configuration software.

SCSI cables must always be properly terminated in order for devices to be properly recognized; they should also use high-quality active terminators. Diagnostic terminators that help identify problems in signal quality are also available.

Always use the shortest cable possible for SCSI connections, because longer cables cause signals to weaken and are more affected by noise due to electromagnetic interference (EMI). When you calculate the total length of the SCSI bus, add the lengths of all the SCSI cable segments plus any internal SCSI cabling.

Be sure that all devices on a SCSI bus are configured for either single-ended or differential transmission—do not mix these methods on a single bus. You can connect single-ended devices to differential transmission devices only by using a signal converter. If you do not use a signal converter, your SCSI devices might be damaged by unexpected voltages.

See Also: *Fibre Channel, storage*

smart card

A plastic card with an embedded microchip used to authenticate the owner.

Overview

Smart cards have been around a long time, at least in concept. The first patent on "chip cards" was issued in 1974, but the technology of that day did not support implementation of the concept. By 1978, however, smart cards began to make their appearance, and their use spread rapidly, particularly in France and several other European countries.

Smart card technology was initially proprietary vendor-based technology that required cards, card readers, and software drivers to be used from a single vendor to ensure interoperability. To overcome this issue, the International Organization for Standards (ISO) developed the ISO 7816 standard that defined the operation of the physical and data-link layer of smart cards and readers. This standard was quickly adopted by financial credit institutions such as Visa International and MasterCard International and by the Global System for Mobile Communications (GSM) cellular phone system. In the last few years smart card readers have even become a built-in feature of high-end laptops from Acer America Corporation, Compaq Computer Corporation, and other PC vendors. Microsoft Windows 2000, Windows XP, and Windows .NET Server also have built-in support for smart card authentication, making the technology easy to implement in the enterprise desktop arena.

See Also: *authentication protocol, Global System for Mobile Communications (GSM)*

SMB

Stands for Server Message Block, a general-purposes information-sharing protocol.

See: *Server Message Block (SMB)*

SMDS

Stands for Switched Multimegabit Data Services, a high-speed metropolitan area network (MAN) data service offered by some telcos.

See: *Switched Multimegabit Data Services (SMDS)*

S/MIME

Stands for Secure/Multipurpose Internet Mail Extensions, a scheme for secure e-mail messaging.

See: *Secure/Multipurpose Internet Mail Extensions (S/MIME)*

SMS (Short Message Service)

Stands for Short Message Service, a protocol for sending short text messages over cellular communications systems.

See: *Short Message Service (SMS)*

SMS (System Management Server)

Stands for Systems Management Server, a server application from Microsoft Corporation for managing an organization's networked computers.

See: *Systems Management Server (SMS)*

SMTP

Stands for Simple Mail Transfer Protocol, an application-layer protocol for delivery of e-mail over the Internet.

See: *Simple Mail Transfer Protocol (SMTP)*

SNA

Stands for Systems Network Architecture, a set of IBM mainframe networking standards and protocols introduced in 1974.

See: *Systems Network Architecture (SNA)*

SNADS

Stands for SNA Distribution Services, the e-mail messaging transport protocol for IBM's Systems Network Architecture (SNA).

Overview

SNADS is a mainframe host-based messaging system that is commonly used in SNA networking environments. Microsoft Exchange Server includes a connector for enabling messaging connectivity between SNADS mail systems and Exchange servers. You can use Microsoft SNA Server to provide the underlying network connectivity for this connector to function. The SNADS connector allows Exchange Server to leverage the functionality of existing host-based messaging systems such as AS/400 and System 3x during migration to a distributed client/server-based environment.

See Also: *Exchange Server, SNA Server*

snap-in

A component that can be loaded into the Microsoft Management Console (MMC).

Overview

Snap-ins provide a specific management capability in Microsoft Windows 2000, Windows XP, Windows .NET Server, or Microsoft server applications. Numerous snap-ins are available for administering Windows 2000–based networks, including third-party snap-ins for managing installable third-party applications and services.

Snap-ins come in two types:

- Stand-alone snap-ins (or simply "snap-ins"), which provide an associated set of administrative functions
- Extensions, which provide additional functionality to stand-alone snap-ins

The following table shows some of the snap-ins that come with Windows 2000. Not all of them appear in the administrative tools program group accessed from the Start menu.

Windows 2000 Snap-Ins

Snap-In	*Function*
Active Directory Users and Computers	Configuring Active Directory, organizing a domain, creating user and group accounts, and configuring security for networking components
Active Directory Schema	Modifying the schema
Active Directory Sites and Services	Creating and managing sites
Active Directory Domains and Trusts	Administering a domain within a domain tree
Admission Control Services Manager	Configuring Admission Control Services

(continued)

Windows 2000 Snap-Ins *continued*

Snap-In	*Function*
Certificate Manager	Managing digital certificates and keys
Component Services	Manages COM+
Computer Management	Managing a computer and creating access to other useful snap-ins such as Disk Management and Event Viewer
Device Manager	Managing resources used by system devices
DHCP Manager	Creating and configuring Dynamic Host Configuration Protocol (DHCP) servers
Disk Defragmenter	Defragmenting disks
Disk Management	Configuring disks and volumes
DFS Manager	Configuring the Distributed file system (Dfs) for centralized management of network resources
DNS Manager	Creating and configuring Domain Name System (DNS) servers
Event Viewer	Viewing system, application, security, and other logs on local and remote computers
File Service Management	Creating shares on local and remote computers and monitoring and configuring network connections
Group Policy Editor	Creating group policy objects (GPOs) for configuring groups of computers centrally
Index Manager	Configuring indexing of directories
Internet Authentication Service	Configuring Internet Authentication Service (IAS) service and clients
Internet Information Services (IIS)	Creating and configuring World Wide Web (WWW) and File Transfer Protocol (FTP) sites
IP Security Policy Management	Configuring Internet Protocol Security (IPsec)
Local User Manager	Managing user accounts in a workgroup
Microsoft System Information	Viewing system component details
Network Management	Managing network services and policies
Removable Storage Management	Managing removable storage devices
Routing and Remote Access Management	Configuring Routing and Remote Access Service (RRAS)
Security Configuration Editor	Creating and modifying security policies
Security Configuration Manager	Managing security policies
System Monitor Log Manager	Managing System Monitor logs
System Service Management	Monitoring, starting, and stopping services
Telephony Manager	Managing Telephony API (TAPI) applications

See Also: *Microsoft Management Console (MMC)*

SNA Server

A Microsoft Corporation server application for local area network (LAN)–host integration, now replaced by Microsoft Host Integration Server.

See: *Host Integration Server*

sniffing

Passively monitoring network traffic.

Overview

Sniffing is a term used to describe the process of nonintrusively capturing network traffic. Sniffing can be used for good or bad reasons. For example, network administrators might connect a packet analyzer (“sniffer”) to a local area network (LAN) segment or Ethernet switch port to troubleshoot network problems. Hackers also employ sniffers to unobtrusively examine network traffic and look for weaknesses that might be exploited.

Sniffing makes use of network interfaces running in something called “promiscuous mode.” In this mode the interface reads and examines every frame or packet on

(continued)

the segment. This is in contrast to an interface working in normal mode, where only those frames addressed to the interface (or broadcast to every interface) are processed.

See Also: *hacking, interface, network troubleshooting*

SNMP

Stands for Simple Network Management Protocol, a popular protocol for network management.

See: *Simple Network Management Protocol (SNMP)*

SOAP

Stands for Simple Object Access Protocol, a message-passing protocol used to enable distributed Web services.

See: *Simple Object Access Protocol (SOAP)*

SOA record

Stands for start of authority record, the first record in a Domain Name System (DNS) zone file.

See: *start of authority (SOA) record*

socket

A logical endpoint for communication between two hosts on a Transmission Control Protocol/Internet Protocol (TCP/IP) network.

Overview

A socket is also an application programming interface (API) for establishing, maintaining, and tearing down communication between TCP/IP hosts. Sockets were first developed for the Berkeley UNIX platform as a way of providing support for creating virtual connections between different processes.

Sockets provide a mechanism for building distributed network applications such as client/server applications. Two sockets form a complete bidirectional communication path between processes on two different TCP/IP hosts. Network-aware applications and services can create and destroy sockets as needed.

Architecture

As an endpoint for network communication between hosts, a socket is uniquely identified by three attributes:

- The host's IP address
- The type of service needed—for example, a connectionless protocol such as User Datagram Protocol (UDP) or a connection-oriented protocol such as Transmission Control Protocol (TCP)
- The port number used by the application or service running on the host

For example, the following identifier would represent a socket for the Simple Mail Transfer Protocol (SMTP) mail service running on a host with the specified IP address. (Port 25 is the well-known port number for the SMTP service on a TCP/IP host.)

```
172.16.8.55 (TCP port 25)
```

Notes

In the Win32 programming environment, sockets are implemented using a programming interface called Windows Sockets. Windows Sockets on Microsoft Windows platforms supports most Internet protocols and services, such as Hypertext Transfer Protocol (HTTP), File Transfer Protocol (FTP), and Telnet.

See Also: *Windows Sockets*

SOCKS

A circuit-layer proxy used to securely send data over distrusted networks.

Overview

SOCKS is a protocol that can be used to establish a secure connection between two computers over the Internet. SOCKS was first developed in 1990, and its current version, SOCKSv5, originated in 1995. SOCKS is widely implemented in firewall, proxy server, and virtual private network (VPN) hardware and software. SOCKS is defined in RFCs 1928, 1929, and 1961.

Implementation

To use SOCKS, you must have SOCKS-enabled client software installed on the hosts that will be communicating over the proxy server. SOCKS lets hosts on each side of a proxy server communicate with each other by establishing a relay connection between the internal and external networks. Using SOCKS, these virtual circuits are set up and torn down between the two hosts on a session-by-session basis. When a SOCKS client wants to connect to a host on the other side of a firewall or proxy server to access network resources, SOCKS server software running on the proxy server authenticates the host's request, creates a circuit-level proxy connection to the target host, requests the necessary data, and relays the information back to the requesting host.



SOCKS. *How the SOCKS v5 protocol works.*

The SOCKS client on the requesting host must first negotiate an authentication method with the SOCKS server before it sends the user's credentials to the SOCKS server for authentication. SOCKS v5 supports a number of authentication methods, including Challenge Handshake Authentication Protocol (CHAP), and digital certificates based on a public key infrastructure (PKI). Once the user is authenticated, the SOCKS client sends a request message using the SOCKS protocol to the SOCKS server (the daemon or SOCKS service running on the firewall or proxy server). This request message contains the address of the target host, such as a Web server on a corporate intranet. The SOCKS server then establishes a Transmission Control Protocol (TCP) connection with the target host that functions as a proxy circuit between the requesting and target hosts. Once this "virtual circuit" is established, the SOCKS server notifies the SOCKS client and communication can begin between the two hosts, with the SOCKS server relaying each packet sent between them.

SOCKS servers usually include comprehensive logging functionality to analyze the flow of traffic between the trusted and distrusted networks.

Notes

The previous version of the protocol, SOCKS v4, was more difficult to configure on the client side and had no support for authentication of users or encryption of data. It also did not support User Datagram Protocol (UDP) traffic. SOCKS v5 is easier to configure, supports various authentication methods and encryption algorithms, and supports connectionless UDP traffic.

See Also: *Challenge Handshake Authentication Protocol (CHAP), firewall, proxy server, public key infrastructure (PKI), Transmission Control Protocol (TCP), virtual private network (VPN)*

softswitch

A media gateway controller for Voice over IP (VoIP).

Overview

Softswitches are part of the infrastructure that links VoIP implementations to the Public Switched Telephone Network (PSTN). They are used to set up telephone calls and coordinate the actions of other telephony devices such as media gateways and signaling gateways. Media gateways are used to translate traffic between Internet Protocol (IP) networks and a carrier's Asynchronous Transfer Mode (ATM) backbone network, and signaling gateways perform services similar to the Signaling System 7 (SS7) protocol used in the PSTN for call establishment, routing, and termination.

Softswitches are less expensive than traditional voice telephony switches. Many telcos are beginning to implement softswitches in their central office (CO) switching fabric to prepare for an eventual move to VoIP technologies, which will enable voice and data networks to converge.

See Also: *Asynchronous Transfer Mode (ATM), central office (CO), Public Switched Telephone Network (PSTN), telco, Voice over IP (VoIP)*

solid conductor wire

Wire that has a single solid copper core surrounded by insulation, as opposed to stranded conductor wire, which consists of many fine strands of wire woven into a conducting bundle.

Overview

Unshielded twisted-pair (UTP) cabling commonly comes in both solid and stranded forms. The solid conductor form is generally used for vertical backbone cabling between wiring closets on different floors and for horizontal runs from wiring closets to wall plates in work areas on each floor. Solid cabling is also used for permanently installed long cable runs inside and between buildings because it has less attenuation than stranded conductor wire and signals can travel farther without losing strength.

The following table compares the advantages of these two types of wire.

Solid Conductor Wire vs. Stranded Conductor Wire

Solid Conductor	*Stranded Conductor*
Less attenuation	More flexible
Better conductivity	Less likely to break or fracture
Easier to terminate	
Cheaper	Longer lasting

See Also: *stranded conductor wire, unshielded twisted-pair (UTP) cabling*

SONET

Stands for Synchronous Optical Network, a physical layer specification for broadband synchronous transmission used by telecommunications carriers.

See: *Synchronous Optical Network (SONET)*

source address

The address from which a frame or packet of data originates on a network.

Overview

The source address identifies the sending host to the receiving host and is used by the receiving host as a destination address for a response packet (such as an acknowledgment). Bridges also use the source address in building their internal routing tables of media access control (MAC) addresses for determining which packets should be forwarded to other network segments.

The source address refers to one of the following:

- The physical address, such as the MAC address of an Ethernet frame
- The logical address, such as the Internet Protocol (IP) address of an IP packet

Source addresses always identify the specific host that transmitted the packet or frame onto the network. This is in contrast to destination addresses, which sometimes direct packets to all hosts or to a specific group of hosts on the network.

Notes

You can see the source address of a packet or frame by using a network sniffer such as Network Monitor, a tool included with Microsoft Systems Management Server (SMS). Network Monitor displays source addresses in both ASCII and hexadecimal form.

See Also: *destination address*

spam

Unsolicited e-mail such as chain letters and advertising for services or products.

Overview

Spam is sometimes politely referred to as unsolicited commercial e-mail (UCE). To avoid getting spam, you can do the following:

- Avoid posting messages to Usenet newsgroups.
- Never reply to junk mail.
- Configure filters on your mail client to filter out mail containing certain keywords.
- Ask your Internet service provider (ISP) to configure its mail servers to reject spam.

If your e-mail address somehow gets on the mailing lists of spammers, you can usually configure rules on your e-mail program's Inbox to discard mail that comes from a specific address, uses words such as *sale* or *buy* in the subject header, or has specific words or phrases in the body of the message, but this is usually a tedious and losing game. A better solution is to use the Delete key. If the situation gets really bad, see whether your mail administrator or ISP can filter out spam.

See Also: *e-mail*

spanned volume

A type of disk volume in Microsoft Windows 2000 and Windows .NET Server.

Overview

A spanned volume is one made up of free space from more than one physical disk. You can extend spanned volumes by adding additional free space from other physical disks. Spanned volumes must be created on dynamic disks. They are not fault tolerant and cannot be mirrored.

S

Notes

In Windows NT, the equivalent to a spanned volume is a volume set.

See Also: *volume*

spanning tree algorithm (STA)

An algorithm that eliminates loops in a bridged or switched network.

Overview

The spanning tree algorithm (STA) has two main purposes:

- To establish a loop-free (tree-like) topology in a network containing bridges and switches. The elimination of loops in bridged (switched) networks is essential in order for communications to be reliable and to prevent traffic from endlessly looping around the network.
- To ensure that there is a path between each pair of network segments in a bridged network. In other words, to ensure that this loop-free tree actually "spans" the entire network.

The STA was created by Radia Perlman.

Implementation

To collect the network topology information needed to use the STA, bridges and switches periodically send to each other special data-link layer messages called bridge protocol data unit (BPDU) messages, which are based on the IEEE 802.1 specification. These messages allow a bridged/switched network to elect a root bridge for the entire network and designated bridges for each network segment, which form the basis of the spanning tree created by the algorithm. The STA determines which ports are redundant and form loops on the network and issues messages that cause those ports to be shut down (blocked) to eliminate the loops. Ports that are blocked are still active (receiving BPDU messages), however, so that if the network topology changes (for example, by a bridge going down or being moved) the port can be unblocked if required to ensure that the network is still fully spanned.

Issues

Implementing the STA on Ethernet switches can sometimes prevent Dynamic Host Configuration Protocol (DHCP) clients from renewing their leases with the DHCP server. For example, it could take a few seconds for the STA to check the ports on a switch for loops, and if a DHCP client tried to obtain a DHCP lease during this time, the DHCPREQUEST packet could be lost. Should this problem arise, you can work around it either by disabling the algorithm on switches or by manually releasing and renewing the computer's Internet Protocol (IP) address using ipconfig.

See Also: *802.1, bridge, Ethernet switch*

sparse mode

One of two forms of the spanning tree algorithm (STA) used in multicasting.

Overview

Whereas dense mode routing is designed for large-scale multicasting where hosts are spread out across every corner of the network, sparse mode is intended to be efficient in routing multicast packets to clusters of hosts across a network. Sparse mode thus assumes that hosts are sparsely concentrated in small clusters or pockets scattered around a few areas of the network. An example of a situation where sparse mode multicasting might be required would be a corporate webcast originating at headquarters and targeted at a limited number of branch offices. Sparse mode is also more effective at dealing with heavy traffic congestion than dense mode when the number of intended recipients is small.

Implementation

Sparse mode multicasting creates a single multicast routing tree for all recipients. Unlike dense mode, where every corner of the network is first flooded with multicast packets and branches that are then pruned back, sparse mode relies on the recipient hosts to initiate the connection by sending a request to a nearby router.

Sparse mode multicasting can employ several different routing protocols to handle the flow:

- Core-Based Trees (CBT)
- Protocol Independent Multicast-Sparse Mode (PIM-SM)

See Also: *Core-Based Trees (CBT), dense mode, multicasting, Protocol Independent Multicast-Sparse Mode (PIM-SM), routing protocol, spanning tree algorithm (STA)*

special identity

Also known as a system group, a special group account in Microsoft Windows 2000 whose membership is controlled by the operating system itself, not by administrators or individual users.

Overview

User accounts become "members" of these special groups based on the type of system activity they participate in; you cannot modify the "membership" of these groups directly. Special identities on Windows 2000 systems include the following:

- **Creator Owner:** Consists of users who will create files or subdirectories within the current directory on an NTFS file system (NTFS) volume.
- **Everyone:** Consists of all network users, including guests and users from distrusted domains. Granting NTFS permissions to Everyone allows anyone to access the file or directory.
- **Interactive:** Consists of all users who log on interactively to the console of the machine or who access the NTFS file system on the machine from a local console.
- **Network:** Consists of all users who log on to the machine from over the network or who access the NTFS file system on the machine from over the network.
- **System:** Consists of the local operating system. System is not normally used when assigning permissions to files and directories on NTFS volumes.
- **Authenticated Users:** Consists of all users with a valid user account in the local directory database or in Active Directory directory service.
- **Anonymous Logon:** Consists of any user accounts that Windows 2000 did not authenticate.
- **Dialup:** Consists of any users who currently have a dial-up connection.

SPF

Stands for Shortest Path First, a routing algorithm used by the Open Shortest Path First (OSPF) protocol.

See: *Shortest Path First (SPF)*

SPM

Stands for statistical packet multiplexing, another name for statistical multiplexing (STM), a multiplexing technique used in frame relay and Asynchronous Transfer Mode (ATM) networking.

See: *statistical multiplexing (STM)*

spoofing

A tactic used by hackers that involves forging the identity of a packet source.

Overview

Spoofing is generally used to attempt to breach a network's security in order to compromise its systems. Spoofing is performed by altering packets' source addresses, making them appear as though they came from a trusted user within the network rather than from a distrusted outside user. Spoofing is one of the common methods used by hackers and is of particular concern when a network is connected to the Internet.

Because of limitations in the design of the current Internet Protocol (IP) standard, IPv4, spoofing of IP packets cannot be prevented, only protected against. One way to protect your network against IP address spoofing is to use the packet-filtering features of a router or firewall. Configure your packet-filtering router so that the input filter on the external router interface discards any packet coming from the external network whose source address makes it look as though it originated from your own internal network. Similarly, configure the output filter on your internal router interface to discard any outgoing packets that have a source address different from that of your internal network to protect against spoofing attacks from within your own network.

See Also: *hacking, Internet Protocol (IP), packet filtering*

spooling

The process of temporarily storing documents sent for printing on a hard disk and then sending them to the print device when it is ready (or when some other criterion has been met).

Overview

The application software that performs spooling is called a spooler. The spooler accepts and temporarily stores documents to be printed and then sends them to the printer according to predefined conditions such as print priority and schedule. Spooling of print jobs allows control to be returned more quickly to the application that generated the job. Spooling also allows jobs to be queued when the printer is unavailable so that the application does not have to generate the jobs again.

Notes

The term *spool* is actually an acronym for Simultaneous Peripheral Operation On Line.

See Also: *printing terminology*

spread spectrum

A wireless networking technology originally developed by the U.S. military for secure wireless communication.

Overview

Unlike other forms of wireless communication, spread spectrum technologies take advantage of a large portion of the electromagnetic spectrum, making it difficult for distrusted users to "listen in" on private conversations. Spread spectrum networking systems generally use very low power signals in the high radio or low microwave portion of the electromagnetic spectrum.

In the United States, spread spectrum communication can utilize three portions of the electromagnetic spectrum that have been allocated by the Federal Communications Commission (FCC) for wireless devices without special licensing:

- **Industrial band:** 902 to 928 megahertz (MHz)
- **Scientific band:** 2400 to 2483.5 MHz
- **Medical band:** 5725 to 5850 MHz

Types

Two basic mechanisms can be used to implement spread spectrum wireless communication: direct sequencing and frequency-hopping.

- **Direct sequencing:** This mechanism takes an individual binary bit from the transmission signal and converts it to a binary string. This string is then transmitted as a single wideband signal over an adjacent set of frequencies, with each bit in the string transmitted at a different frequency. The receiving station examines the bit pattern of the binary string and determines which single bit was originally transmitted by the sending station. This technology has built-in fault tolerance because electromagnetic interference (EMI) might degrade a portion of the binary string, but if the receiving station can recognize a different portion of the string, communication is assured. A typical example of direct sequencing technology might be to assign the string 10011011 to bit 1 and its inverse 01100100 to bit 0. Transmission of the bit sequence 110 would then consist of three transmitted strings: 10011011, 10011011, and 01100100.

- **Frequency-hopping:** This uses a continually changing carrier frequency. The pattern by which the carrier frequency is changed is programmed according to an algorithm known to both the sending and receiving stations. For communication to take place, the two stations must remain synchronized throughout the session. One station is designated the master station and the other the slave station. If particular frequencies within the spread spectrum communication band contain interference from other radio sources, frequency-hopping technology can avoid these frequencies by using adaptive techniques. To further enhance security, either station can also dynamically change the pattern of frequency hopping.

Uses

Spread spectrum technologies can have a variety of uses in networking, including point-to-point links between networks, wireless local area networks (LANs), and cellular-based roving network communication. One common use in networking environments is for connecting stations to a LAN when it is impractical or impossible to lay cabling. You can also use spread spectrum wireless bridge technologies to establish point-to-point or multipoint communication between buildings on a campus. These devices usually support line-of-sight connections that function to distances of 18.5 miles (30 kilometers) or more, with speed decreasing as the distance increases. Spread spectrum devices for wireless LAN stations generally have a much shorter range, usually no more than about 655 feet (200 meters).

See Also: *Direct Sequence Spread Spectrum (DSSS), direct sequencing, frequency hopping, Frequency Hopping Spread Spectrum (FHSS), wireless networking*

SQL

Stands for Structured Query Language, a standards-based language used by relational database management programs primarily for constructing queries.

See: *Structured Query Language (SQL)*

SQL Server

A high-performance client/server relational database management system (RDBMS) for the Microsoft Windows 2000 and Windows .NET Server operating systems.

Overview

A RDBMS is used in high-volume transaction-processing environments such as online order entry systems, data warehousing, decision-support applications, and e-commerce. Microsoft SQL Server includes the following advanced features:

- A distributed management framework for centrally managing all servers running SQL Server in an organization
- Built-in data replication to copy information throughout an enterprise—not only to SQL Server databases but also to Oracle, IBM DB2, Sybase, and other databases
- The Web Assistant for populating a Web server with structured query language (SQL) data for Internet or private intranet use
- Microsoft Distributed Transaction Coordinator for creating distributed transaction-based applications across multiple servers

- Integration with the security features of the Windows NT platform
- A high-performance, scalable, multithreaded parallel architecture
- Scalable dynamic locking architecture for page-level and row-level locking
- Data warehousing and online analytical processing (OLAP) enhancements
- Support for OLE Automation stored procedures
- Integration with Microsoft Exchange through the SQL Mail utility
- Support for Windows .NET Server, Windows 2000, Windows NT, Windows 98, and Windows 95
- A query processor that supports the complex queries used in decision support, data warehousing, and OLAP applications
- Wizards that ease tasks for administrators and programmers
- Support for Microsoft Management Console (MMC)
- Assorted tools for profiling and tuning a server's performance
- Integration with Microsoft Proxy Server and Microsoft Office 2000

SQL Server is a client/server database system. The server runs the SQL Server database software, which processes requests submitted by the database client software and sends the results back to the client. The SQL Executive and the SQL Server Database Engine service are examples of database services performed by SQL Server.

The SQL Server software is arranged in multiple layers. The Net-Library layer, which accepts connections from clients, hides the network connectivity details when a client communicates with a server running SQL Server. Net-Libraries use interprocess communication (IPC) mechanisms such as named pipes, remote procedure calls (RPCs), and Windows Sockets. Several Net-Libraries are included with SQL Server for both the server and the client. Net-Libraries on the server listen for client connection attempts.

A client computer runs the database client software, which is used to connect to the server running SQL Server, make requests, receive results, and display the results on the user's screen. Examples of database client software that can connect to SQL Server include SQL Server Enterprise Manager, ISQL/w, and Microsoft Access. The database client software is also made up of multiple layers. Users interact directly with the client application, which might present a form such as an order entry form. When the user submits the form, the client software interacts with the server running SQL Server using open database connectivity (ODBC) or DB-Library application programming interfaces (APIs). The server processes the request and returns information to the client.

For More Information

Visit *www.microsoft.com/sql.*

See Also: *database, Structured Query Language (SQL)*

SSL

Stands for Secure Sockets Layer, a transport layer security protocol used on the Internet.

See: *Secure Sockets Layer (SSL)*

SSO

Stands for Single Sign On, any technology that requires users to have only one set of credentials to access network resources.

See: *Single Sign On (SSO)*

SSP

Stands for storage service provider, a company offering outsourced storage services.

See: *storage service provider (SSP)*

STA

Stands for spanning tree algorithm, an algorithm that eliminates loops in a bridged or switched network.

See: *spanning tree algorithm (STA)*

stackable hubs

Hubs that can be connected to operate as a single hub.

Overview

Stackable hubs can be placed one above another on an equipment rack and connected using specialized short cables, generally ribbon cables. The reason for using stackable hubs is that the stacked hubs effectively create a single hub with a large number of ports and a single collision domain. This is generally superior to the older way of cascading hubs together by using uplink ports, a method which tends to generate crosstalk. Note that when you stack several hubs, the top and bottom hubs usually have a free connection that must be properly terminated in order for the stacked array to function properly.



Stackable hubs. *How to connect stackable hubs.*

Besides hubs, Ethernet switches are often stackable as well. Switches are stacked mainly to provide greater scalability and increased manageability. Popular stackable Fast Ethernet switches for workgroup environments include 3Com Corporation's SuperStackII line of switches, Cisco Systems' Catalyst 2500 series, and Nortel Networks' BayStack 450 series.

See Also: *crosstalk, Ethernet switch, hub, rack*

stand-alone server

A server that does not perform logon authentication and is not part of a domain.

See: *member server*

standard Ethernet

The original Institute of Electrical and Electronics Engineers (IEEE) standard for implementing 10 megabits per second (Mbps) Ethernet over thick coaxial cabling.

See: *10Base5*

standards organizations

Organizations that help standardize technologies and practices.

Overview

Many standards organizations have contributed specifications and standards to the computer networking industry. Without these agencies, the networking world would be a nightmare of noninteroperable proprietary vendor-developed technologies. Some of the larger and more important standards bodies related to computer networking and Internet standards include

- American National Standards Institute (ANSI)
- European Computer Manufacturers Association (ECMA)
- Institute of Electrical and Electronics Engineers (IEEE)
- Internet Engineering Task Force (IETF)

- International Organization for Standards (ISO)
- International Telecommunication Union (ITU)
- Object Management Group (OMG)
- World Wide Web Consortium (W3C)

Many standards bodies are also devoted to specific technology areas, such as the ATM Forum and the Fibre Channel Alliance. The work of all these standards bodies is important to the long-term viability of the IT (information technology) sector and marketplace.

See Also: *American National Standards Institute (ANSI), Institute of Electrical and Electronics Engineers (IEEE), International Organization for Standardization (ISO), International Telecommunication Union (ITU), Internet Engineering Task Force (IETF), World Wide Web Consortium (W3C)*

star bus topology

A combination of star topology superimposed on a backbone bus topology.



Star bus topology. *Example of a star bus topology.*

Overview

Star bus topology is a networking topology in which hubs for workgroups or departmental local area networks (LANs) are connected by using a network bus to form a single network. You can connect these hubs by using one of the following:

- Regular 10Base2 or 10BaseT cables with uplink ports on the hubs
- Crossover cables for regular (host) ports on the hub
- Special cables for stackable hubs

Notes

When you use this topology with standard Ethernet hubs, do not create an excessively large collision domain by adding too many stations. This will degrade network performance unless you segment the network by using bridges or routers.

See Also: *bus topology, star topology*

StarLAN

The popular name of 1Base5, an obsolete 1 megabit per second (Mbps) local area network (LAN) networking technology.

See: *1Base5*

start of authority (SOA) record

The first record in a Domain Name System (DNS) zone file.

Overview

The start of authority (SOA) record defines the general properties of the zone for a name server, such as the name server on which the zone file resides, the zone of authority, and the administrative contact for the domain.

Examples

Here is an example of a start of authority (SOA) record:

```
@   IN   SOA   nameserver.place.dom.
               postmaster.place.dom. (
1         ; serial number
3600      ; refresh   [1h]
600       ; retry     [10m]
86400     ; expire    [1d]
3600 )    ; min TTL   [1h]
```

This SOA record contains the following information:

- The name of the subdomain over which a particular name server has authority (nameserver.place.dom)
- The name of the host on which this zone file resides
- The e-mail address of the person who is responsible for administering the subdomain (postmaster@place.dom)
- A serial number, which increases when the zone data is updated and which is used in zone transfers to determine whether the secondary name server needs a new version of the zone file
- A refresh interval, in seconds, that informs the secondary name server how frequently it should check with the master name server to see whether its zone information is current
- A retry interval, in seconds, that tells the secondary name server how often to contact the master name server if the initial contact is unsuccessful
- An expire interval, in seconds, that informs the secondary name server how long to keep trying to contact the master name server for a refresh of the zone data before the data expires and the secondary name server no longer responds to name queries
- The Time to Live (TTL), which is a value returned by the name server to resolvers when a name is resolved, informing the resolver how long it can cache the resolved name and Internet Protocol (IP) address

See Also: *Domain Name System (DNS), resource record (RR)*

star topology

A networking topology in which the components are connected by individual cables to a central unit, usually a hub.

Overview

Star topology is the most popular way to connect computers in a workgroup or departmental local area network (LAN), but it is slightly more expensive than using bus topology. When a computer or other networking component transmits a signal to the network, the signal travels to the hub, which forwards the signal simultaneously to all other components connected to the hub. One advantage of star topology is that the failure of a single computer or cable does not bring down the entire LAN. Another advantage is that topology centralizes networking equipment, which can reduce costs in the long run by making network management much easier.

Star topology is used mainly to

- Connect computers in a workgroup or departmental LAN using a hub.
- Connect workgroup or departmental hubs using a master hub or switch. This is a special star topology called either cascading hubs or star-wired topology.



Star topology. *Example of a star topology network.*

Notes

If no one on a star network can access network resources, the hub might be down or overloaded. Try resetting the hub by using the reset switch, or try powering it off and then on. If a hub frequently needs to be reset, you might have a hardware malfunction or network bandwidth might be reaching capacity (which means that you should upgrade your components).

See Also: *bus topology, mesh topology, ring topology, star bus topology*

static address

An Internet Protocol (IP) address that is manually assigned to a host on a Transmission Control Protocol/Internet Protocol (TCP/IP) network.

Overview

Static IP addresses are usually used for

- Small workgroups whose machine configurations will not change often. Peer-to-peer networks that use either Microsoft Windows 95 or Windows 98 do not have a Dynamic Host Configuration Protocol (DHCP) server to assign IP addresses to stations on the network.
- Servers on a network, which should have an IP address that does not change. An alternative is to assign a DHCP reservation to these servers so that they receive their IP addresses automatically from a DHCP server but always receive the same reserved address.
- Windows NT–, Windows 2000–, and Windows .NET Server–based servers that are running certain services, such as DHCP, Windows Internet Name Service (WINS), or Domain Name System (DNS). Servers running these services normally require static IP addresses.

Computers running Windows support both static IP addressing and dynamic IP addressing through the DHCP.

See Also: *Dynamic Host Configuration Protocol (DHCP), IP address*

static mapping

On a Windows Internet Name Service (WINS) server, a manually entered NetBIOS name to Internet Protocol (IP) address mapping stored in the WINS database.

Overview

WINS servers normally create mappings dynamically when a WINS client performs NetBIOS name registration upon client initialization. Non-WINS clients do not register their names, so administrators must manually create WINS database entries. Once they do this, other hosts on the network can perform NetBIOS name discovery queries to resolve the NetBIOS name of non-WINS clients into their IP addresses.

See Also: *Windows Internet Name Service (WINS)*

static routing

A routing mechanism that depends on manually configured routing tables.

Overview

Static routing is generally used in smaller networks that contain only a couple of routers or when security is an issue. Routers that use static routing are sometimes called static routers. Each static router must be configured and maintained separately because static routers do not exchange routing information with each other.

For a static router to function properly, the routing table must contain a route for every network in the internetwork. Hosts on a network are configured so that their default gateway address matches the Internet Protocol (IP) address of the local router interface. When a host needs to send a packet to another network, it forwards the packet to the local router, which checks its routing table and determines which route to use to forward the packet.

Advantages and Disadvantages

Static routers are more difficult to administer than dynamic routers, but they can be more secure because the administrator controls the configuration of the router. They are therefore immune from attempts by hackers to spoof dynamic routing protocol packets in order to reconfigure the router and try to hijack network traffic.

Notes

You can configure a multihomed server as a static router in Microsoft Windows 2000 by first clicking the Advanced button on the Transmission Control Protocol/Internet Protocol (TCP/IP) property sheet. Select the Options tab, select TCP/IP Filtering and click Properties, then select Enable TCP/IP Filtering. You can then add static routes for each remote network by using the Route command.

See Also: *dynamic routing, routing table*

statistical multiplexing (STM)

A multiplexing technique used in frame relay and Asynchronous Transfer Mode (ATM) networking.

Overview

Statistical multiplexing (STM) enables information from a number of channels to be combined for transmission over a single channel. STM dynamically allocates bandwidth only to channels that are currently transmitting on an as-needed basis, without any bandwidth being allocated to quiet (non-transmitting) channels. This is in contrast to time-division multiplexing (TDM), where quiet devices still use up a portion of the multiplexed data stream, filling it with empty packets. STM usually packages the data from the active channels into packets and dynamically feeds them into the output channel on a first in, first out (FIFO) basis, but it can also allocate extra bandwidth to specific input channels on demand.

Switches and other devices that support statistical multiplexing usually include support for other features, such as:

- **Store-and-forward error detection and correction:** Identifies which channel sent each packet of data and corrects errors that occur
- **Data compression:** Increases the amount of data that can be sent per packet

A multiplexer that is capable of statistically multiplexing several data streams together is sometimes called a statmux. If you have a statmux at each end of a digital line, the receiving statmux can identify the channel of each packet sent by the sending statmux and demultiplex the data stream into its original data channels.

Notes

STM is sometimes referred to as statistical time-division multiplexing (STDM) or statistical packet multiplexing (SPM), but the shorter term is used more often.

See Also: *Asynchronous Transfer Mode (ATM), frame relay, multiplexer (MUX), multiplexing, time-division multiplexing (TDM)*

STDM

Stands for statistical time-division multiplexing, another name for statistical multiplexing, a multiplexing technique used in frame relay and Asynchronous Transfer Mode (ATM) networking.

See: *statistical multiplexing (STM)*

STM

Stands for statistical multiplexing, a multiplexing technique used in frame relay and Asynchronous Transfer Mode (ATM) networking.

See: *statistical multiplexing (STM)*

stop screen

A blue screen that appears whenever the Microsoft Windows NT, Windows 2000, Windows XP, or Windows .NET Server operating system experiences a fatal problem and terminates itself.

Overview

A stop screen includes the following information:

- The top of the screen shows the bugcheck information—the error code and a list of up to four developer-defined parameters.
- The middle portion of the screen lists all modules that have been successfully loaded and initialized by the operating system. This information is listed in three columns: preferred memory location, link time stamp, and driver name.
- The bottom portion shows the build number of the kernel and a stack dump that indicates the address range in which the driver might have failed.

The most important part of a stop screen is the bugcheck information in the first few lines, which gives a stop code and parameters that can help identify the source of the problem to Microsoft Corporation support technicians.

The table on the next page shows some common bugcheck codes and how to interpret them.

Common Bugcheck Codes

Code	*Description*
0x9	IRQL_NOT_GREATER_OR_EQUAL: An attempt was made to touch pageable memory at a process interrupt request level (IRQL) that was too high. This usually indicates that a driver is using improper addresses. A stack trace is usually helpful in debugging the problem.
0xA	IRQL_NOT_LESS_OR_EQUAL: Usually indicates a bad or corrupt pointer.
0x1E	KMODE_EXCEPTION_NOT_HANDLED: An exception (error) occurred with a driver or function. This is one of the most common bugcheck codes; you can often use the exception address to identify the driver or function involved.
0x20	KERNEL_APC_PENDING_DURING_EXIT: This usually indicates a problem with a third-party file system driver, such as a third-party redirector. Check with the manufacturer for an updated redirector.
0x2E	DATA_BUS_ERROR: This usually indicates a parity error in system memory. Try installing new RAM. It can also be caused by a driver accessing an address that does not exist; if swapping memory does not solve the problem, try swapping other hardware cards or install updated drivers for them.
0x3E	MULTIPROCESSOR_CONFIGURATION_NOT_SUPPORTED: This indicates mismatched CPUs in a symmetric multiprocessing (SMP) system.
0x4C	FATAL_UNHANDLED_HARD_ERROR: An error prevented the Windows NT operating system from booting properly. Common causes are missing or corrupt registry hives, a corrupt system dynamic-link library (DLL), a corrupt device driver, or an I/O problem with the disk subsystem.
0x51	REGISTRY_ERROR: This could mean corruption in the registry or an input/output (I/O) problem with the disk subsystem that prevents it from properly reading registry information. This error might also occur on a domain controller in which no more allocated space is available for storing the registry files.
0x69	IO1_INITIALIZATION_FAILED: This indicates a failure in initializing the disk subsystem and usually means that you made an incorrect configuration decision during setup or have reconfigured the disk system incorrectly.
0x73	CONFIG_LIST_FAILED: This indicates corruption in the SAM, SOFTWARE, or SECURITY hive.
0x74	BAD_SYSTEM_CONFIG_INFO: This might indicate a corrupt SYSTEM hive in the registry, or it might mean that some critical registry keys in the hive are not present. Try LastKnownGood; if that fails, try the emergency repair disk (ERD).
0x75	CANNOT_WRITE_CONFIGURATION: This usually indicates that there are 0 bytes of free space on the system drive, so the SYSTEM hive of the registry cannot grow in size.
0x77	KERNEL_STACK_INPAGE_ERROR: This is usually caused by a bad block in the paging file or a disk controller error. If the paging file is on a Small Computer System Interface (SCSI) drive, check the cabling and termination.
0x7B	INACCESSIBLE_BOOT_DEVICE: If this occurs right after setup, it might mean that your disk controller is not supported by Windows NT. You might have to check the Windows Driver Library for a new device driver and do a custom installation. This error can also occur when you repartition the disk that contains the system partition. The solution is to edit the ARC paths in the boot.ini file. Another reason for this error is a Master Boot Record (MBR) or boot sector virus.
0x8B	MBR_CHECKSUM_MISMATCH: This usually indicates the presence of a Master Boot Record virus.
0x98	END_OF_NT_EVALUATION_PERIOD: Your evaluation copy of Windows NT has expired.

(continued)

Notes

Sometimes you can compare the addresses of the parameters in the top portion of the stop screen with the addresses of drivers in the stack dump at the bottom and identify which driver might have caused the crash, but this will not always work. For more information on bugcheck codes and how to interpret them, check Microsoft TechNet.

See Also: *TechNet*

storage

Various technologies used to store information.

Overview

Advances in storage technologies and an explosion of enterprise storage needs have made the storage segment the hottest segment of the IT (information technology) market in the last few years. For example, demand for redundant array of independent disks (RAID) systems is doubling every year, and the overall storage utility market is expected to grow to $7 billion by 2003. New technologies such as solid state disks are eliminating the input/output (I/O) bottleneck in high-end servers, and the emergence of 10 Gigabit Ethernet (10GbE) makes storage over IP a promising technology that challenges the supremacy of Fibre Channel in the enterprise storage arena.

Types

Storage in the enterprise environment generally follows a hierarchical three-tier system:

- **Online storage:** This is the primary form of storage used by servers and is used to store data that needs to be easily accessible. The simplest form of online storage is disk storage—that is, disk drives housed within a PC server box. For additional storage other solutions might be used, including RAID 5 arrays, network attached storage (NAS) appliances, and storage area networks (SANs).
- **Nearline storage:** Also called secondary storage, this form is used to store data that infrequently needs to be accessed. Common forms of nearline storage include optical storage technologies such as CD-RW and DVD-RW drives, magneto-optical disks, and Write-Once Read-Many (WORM) disks.
- **Offline storage:** Also called tertiary storage, this form is used to store data that is archived and rarely needs to be accessed. Various forms of tape backup technologies are used for this type of storage.

The main problem with traditional disk drives, whose capacity has risen and footprint has fallen dramatically in recent years, is that the architecture of PC servers limits the amount of disk storage possible. Another issue is that free storage space inside one server cannot easily be allocated to another server. To get around these limitations, enhanced storage technologies have been developed in the last decade. The most popular of these storage technologies in the enterprise arena are currently

- **RAID-5 arrays:** These are external units that can be attached using Small Computer System Interface (SCSI) to servers to provide greater capacity than internal disk storage systems can provide. SCSI arrays are still the most popular form of storage in the enterprise arena, are easy to deploy and use, and can support many terabytes of storage.
- **Network attached storage (NAS):** These are generally stand-alone appliances that can be connected to your Ethernet network to quickly add storage capacity as needed. The main problem with NAS appliances is that they must be managed individually, so deploying a lot of them can become a management headache for administrators.
- **Storage area network (SAN):** This is a separate Fibre Channel or SCSI network containing storage appliances networked together and managed using an integrated set of tools. SANs are easier to manage than NASs but are also more expensive and complex to deploy.
- **Storage service provider (SSP):** These are companies that you can outsource your enterprise storage needs to, and they provide a managed storage environment for a wide range of business needs.

Marketplace

In the real world, different storage technologies generally overlap. Thus, an enterprise storage array such as IBM's Shark uses a combination of SAN and RAID technologies to provide up to 11 terabytes of storage. Shark connects to host servers through either UltraSCSI or Fibre Channel Enterprise Systems Connection (ESCON) links, can be deployed up to 60 miles (96 kilometers) away, supports snapshot backups, and can be used with Microsoft Windows, UNIX, and OS/390 mainframe systems. Besides IBM, the other heavyweight in the high-end storage market is EMC Corporation.

A popular vendor of NAS appliances is Snap Appliances, whose Snap Server line of storage devices can add up to 240 gigabytes (GB) of storage in minutes, support remote management through Simple Network Management Protocol (SNMP), and integrate with network management systems such as Hewlett-Packard Company's OpenView and Computer Associates' Unicentre/TNG. In addition to IBM and EMC, other popular SAN vendors include Connex and MTI Technology Corporation. Vendors of tertiary (offline) storage include VERITAS Software Corporation, EMC, and many others.

Prospects

Solid state disks are the hottest thing in storage nowadays. These disks are essentially multiple boards of synchronous dynamic random access memory (SDRAM) that are implemented in high-end servers to store most frequently used data such as pagefiles and swapfiles, temp files, log files, database tables and indexes, and logon credentials. These categories of data generally represent only about 5 percent of all stored data, but account for around 50 percent of all I/O generated by servers. Using solid state disks can eliminate the storage bottleneck from which enterprise servers have traditionally suffered.

See Also: *10G Ethernet, Fibre Channel, network attached storage (NAS), redundant array of independent disks (RAID), Small Computer System Interface (SCSI), storage area network (SAN), storage over IP, storage service provider (SSP), tape drive*

storage area network (SAN)

A dedicated storage network separate from the network where servers reside.

Overview

Storage area networks (SANs) currently represent the pinnacle of enterprise network storage. SANs are architectures rather than devices, and they provide a highly scalable and manageable storage solution for the needs of the largest enterprises. The idea of SANs originated in mainframe computing environments, but SANs have gained a significant foothold in distributed client/server environments in the last few years.

Typical applications that use a SAN include enterprise resource planning (ERP), Customer Relationship Management (CRM), enterprise data warehousing, and other high-availability applications that require significant amounts of storage. SANs can also be used as remote storage and archival facilities connected to corporate networks by Asynchronous Transfer Mode (ATM) or Synchronous Optical Network (SONET) connections.

Implementation

SANs use dedicated networks that contain a variety of storage technologies, including redundant array of independent disks (RAID) technologies such as disk mirroring and disk striping, magnetic and optical disk storage, and even tape libraries for archival purposes. SANs generally use high-speed Fibre Channel, a high-speed direct connection technology supporting data transfer rates of up to 1 gigabit per second (Gbps), for interconnections between SAN storage devices and server farms. The essence of the SAN idea is to have two separate networks connected: the corporate network with its servers and the storage network with its storage devices. In addition to Fibre Channel, other SAN interconnection technologies include Enterprise System Connection (ESCON) and variants of Small Computer System Interface (SCSI).

SANs can be implemented in three basic topologies:

- **Point-to-point:** Early SANs were direct physical connections between mainframe hosts and storage arrays, but this configuration is rarely used in a distributed client/server networking environment.

- **Arbitrated loop:** This approach employs Fibre Channel hubs to provide shared bandwidth with round-robin forwarding to enable multiple storage devices and servers to communicate with one another. Arbitrated loop SANs are best used in workgroup or departmental environments.
- **Fabric:** This is the most popular approach today, and it employs Fibre Channel switches to create a high-bandwidth any-to-any connection between storage devices and servers that use them. Fabric-based SANs are suitable for the largest enterprise environments.



Storage area network (SAN). *Basic network architecture of a SAN.*

Marketplace

Some of the enterprise-level SAN vendors include Brocade Communications Systems, Compaq Computer Corporation, EMC Corporation, Hewlett-Packard, IBM, StorageTek, Sun Microsystems, and TrueSAN Networks. Less costly SAN solutions for mid-sized businesses are available from DotHill Systems, LSI Logic Corporation, MTI Corporation, nStor Technologies, and other vendors.

Issues

Despite the efforts of organizations such as the Storage Networking Industry Association (SNIA) and the Fibre Channel Alliance, SAN solutions from different vendors still suffer from some degree of interoperability problems, particularly in the area of Fibre Channel fabric switches. As a result, enterprise network architects who are thinking about implementing a SAN for their company are probably best off implementing a solution from a single SAN vendor.

Prospects

An emerging approach called storage over IP connects SANs to server farms using Internet Protocol (IP) running on Gigabit Ethernet (GbE). Other names for this technology are Storage over SAN (SoSAN) and Gigabit Ethernet SAN. Some analysts predict that storage over IP will eventually replace Fibre Channel as the dominant SAN technology in the enterprise, but this is likely to take a decade or so.

SAN management has traditionally used proprietary management tools, but an initiative of the FibreAlliance, which has the support of over 40 different storage vendors, is intended to change this situation. The FibreAlliance is working toward implementing a Fibre Channel Management Integration (FCMGMT-INT) Management Information Base (MIB) to allow Fibre Channel SANs to be managed using the open standard Simple Network Management Protocol (SNMP).

Notes

It is easy to get confused by the various buzzwords relating to external enterprise-level storage devices because standards in this area have not been developed and ratified by standards bodies. Here are two other related storage system concepts:

- **Direct-attached storage (DAS):** Involves a storage system connected to only a single computer using either Small Computer System Interface (SCSI) or Fibre Channel technology. DAS is usually the only solution if your servers are at different geographical locations around your enterprise or if the application that uses them can support only this form of storage—for example, Windows Clustering, which can use a shared SCSI bus.
- **Network-attached storage (NAS):** Involves data storage devices connected to computers using a standard network connection such as Ethernet. This is in contrast to SAN, in which a group of computers uses multipoint Fibre Channel technology. Another difference between NAS and SAN is that NAS involves the use of file servers similar to the Network File System (NFS) used in UNIX environments (from which the concept of NAS evolved), but SAN uses block-mode input/output (I/O) for applications such as clustering and database access. Use a SAN if your data can be centrally located within your enterprise and if your application needs to access data directly using block transfers instead of using shared files. Use NAS if your data needs to be shared between different operating system platforms or for file-based applications such as Web servers.

See Also: *Asynchronous Transfer Mode (ATM), Customer Relationship Management (CRM), enterprise resource planning (ERP), Fibre Channel, Gigabit Ethernet (GbE), redundant array of independent disks (RAID), Simple Network Management Protocol (SNMP), storage, storage over IP, Synchronous Optical Network (SONET)*

storage over IP

Various technologies used to transport storage data across Internet Protocol (IP) networks.

Overview

Storage over IP is an umbrella term for a group of emerging technologies intended mainly for connecting storage area networks (SANs) with server farms using IP networks. Storage over IP promises to simplify enterprise storage management by utilizing familiar networking technologies such as Fast Ethernet and Gigabit Ethernet (GbE) instead of Fibre Channel, the technology currently favored to connect SANs to server networks. Storage over IP also promises to allow SANs to grow beyond the current 6.2-mile (10-kilometer) limit imposed by Fibre Channel architecture.

Types

Some of the proposed standards for storage over IP include

- **ISCSI:** This specification allows Small Computer System Interface (SCSI) commands to be transported over Transmission Control Protocol (TCP). To implement iSCSI, you do not need to make changes to your network—the addition of Fibre Channel-to-Gigabit Ethernet switching gear is all that is required. Backers of the iSCSI specification include Adaptec, Cisco Systems, Hewlett-Packard, IBM, Quantum Corporation, and SANgate Systems.
- **EtherStorage:** A solution developed by Adaptec primarily for the lower end of the storage over IP market, EtherStorage employs Ultra-3 SCSI drives and standard GbE switches together with a proprietary IP-to-SCSI bridge.
- **Fibre Channel over IP:** This technology encapsulates Fibre Channel frames in IP packets that can be transported over GbE, Asynchronous Transfer Mode (ATM), or Synchronous Optical Network (SONET) networks. Fibre Channel over IP is supported by Brocade Communications Systems, Gadzoox Networks, Lucent Technologies, McData Corporation, and QLogic Corporation.
- **Fibre Channel Backbone:** This is similar to Fibre Channel over IP but is especially designed for the wide area network (WAN) environment and is supported by Brocade Communications Systems and Gadzoox Networks.
- **Service Specific Connection Oriented Protocol (SSCOP):** A specification developed by the International Telecommunication Union (ITU), which

employs a data-link Asynchronous Transfer Mode (ATM) protocol for sending storage data over IP.

- **Storage over IP (SOIP):** A specification developed Nishan Systems, which has patented the name "storage over IP" or "SOIP" for a technology that combines features of iSCSI and Fibre Channel over IP. SOIP is supported by Dell Computer Corporation, Quantum, Siemens, and Sun Microsystems.

See Also: *Fast Ethernet, Fibre Channel, Gigabit Ethernet (GbE), Small Computer System Interface (SCSI), storage area network (SAN), Transmission Control Protocol (TCP)*

storage service provider (SSP)

A company offering outsourced storage services.

Overview

Storage service providers (SSPs) are service providers modeled on the Application Service Provider (ASP) model that help companies manage their storage requirements. SSPs generally offer services in three areas:

- **Primary data storage:** Online storage residing either locally on your network or at a remote data center—in either case the SSP manages these devices.
- **Backup and restore:** Off-site archiving for greater security.
- **High availability:** Data is replicated off-site and is made available from anywhere.

Marketplace

Some of the popular players in the rapidly evolving SSP market include Arsenal Digital Solutions, Articulent, CreekPath Systems, ManagedStorage International, NaviSite, Nuclio Corporation, sanrise, Storability, StorageNetworks (a pioneer in this field), StorageProvider, StorageWay, and WorldStor.

See Also: *storage*

stored procedure

A precompiled set of Structured Query Language (SQL) statements that can be executed on demand as a single entity.

Overview

Stored procedures are generally stored in a database. They support features such as user-declared variables and conditional execution and can be run with a single call. They can accept parameters, and they can return parameters and status values. They can also call other stored procedures. You can create permanent stored procedures for global administrative tasks or temporary ones for a specific task.

In Microsoft SQL Server you create a stored procedure by creating a series of SQL statements. SQL Server parses and analyzes the stored procedure and stores it in various system tables. When you execute it for the first time, it is loaded into memory and compiled, storing the execution plan in the procedure cache. By preparsing and prenormalizing a stored procedure, you can achieve significant performance gains compared to using a simple SQL query.

You can use stored procedures with Microsoft SQL Server to

- Create devices and databases
- Access or update information in database tables
- Perform other administrative or user actions

A trigger is a special type of stored procedure that you can use to enforce referential integrity in a database. Other types of stored procedures supported by SQL Server include the following:

- **Extended stored procedures:** Dynamic-link libraries (DLLs) that can be loaded and run like stored procedures
- **Remote stored procedures:** Run from a remote client
- **System stored procedures:** Included with SQL Server to simplify common administrative tasks and to obtain information from system tables
- **User-defined stored procedures:** Created by users for a specific database
- **User-defined system stored procedures:** Created by users and runnable in any database

See Also: *Structured Query Language (SQL)*

STP cabling

Stands for shielded twisted-pair cabling, twisted-pair cabling that contains internal shielding.

See: *shielded twisted-pair (STP) cabling*

stranded conductor wire

Wire that has a core composed of many thin copper strands woven together and surrounded by insulation.

Overview

Stranded conductor wire is generally used for drop cables between computers and wall plates and for patch cables connecting patch panels with hubs and switches. Stranded conductor wire has more attenuation than solid conductor wire and should be used only for short cable runs. Stranded conductor wire is more durable and reliable than solid conductor wire because it can be bent numerous times without fracturing or breaking, and because damage to the wire has less impact on the surface area of the wire and hence on its capacity to carry alternating current.

Types

Stranded wire comes in two basic configuration types:

- **Bunch-stranded wire:** Uses a number of thin wires with the same diameter and twists them together in one direction.
- **Concentric-stranded wire:** Uses several layers of thin wires wrapped in alternating directions. These wires are generally easier to splice and terminate than bunch-stranded wires.

See Also: *solid conductor wire*

striped volume

A type of disk volume in Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Overview

A striped volume is one that stores its data across two or more physical disks in stripes. Striping allocates data alternately and evenly across multiple physical disks. Striped volumes must be created on dynamic disks. They are not fault-tolerant and cannot be mirrored or extended. Striped volumes in Windows 2000, Windows XP, and Windows .NET Server are the equivalent of striped sets in Windows NT.

See Also: *volume*

stripe set

A type of disk volume in Microsoft Windows NT.

Overview

A stripe set is a single volume created using discontiguous free areas on two or more hard disks. Stripe sets are similar to volume sets but can give much faster read/write performance if segments reside on separately controlled drives. Use the Windows NT administrative tool Disk Administrator to create stripe sets by combining 2–32 free areas on two or more disk drives.

Notes

The Windows NT system partition and boot partition cannot be volume sets. Stripe sets also cannot be extended the way volume sets can.

stripe set with parity

A type of fault-tolerant disk volume in Microsoft Windows NT.

Overview

Stripe sets with parity are a fault tolerance technology whereby data is written simultaneously to two or more different disks. Parity information is distributed across the various disks so that if one disk drive fails, the lost data can be regenerated from the parity information. You can use the Windows NT administrative tool Disk Administrator to create, delete, and regenerate stripe sets with parity. Stripe sets with parity are often used to provide fault tolerance for application and data volumes in Windows NT. In Microsoft Windows 2000, Windows XP, and Windows .NET Server, a stripe set with parity is known as a RAID 5 volume.

See Also: *redundant array of independent disks (RAID)*

Structured Query Language (SQL)

A standards-based language used by relational database management programs primarily for constructing queries.

Overview

Structured Query Language (SQL) was originally developed by IBM for mainframe computing environments and is widely used in relational database management systems. The standard version of SQL is defined by the American National Standards Institute (ANSI), but many vendors have made enhancements to its syntax and command functions. The latest SQL standard is called SQL-92 but is more properly known as ANSI standard SQL X3.135-1992 or International Organization for Standardization (ISO) standard ISO/IEC 9075:1992. Microsoft SQL Server conforms to the ANSI SQL-92 standard and enhances this standard with additional statements for certain types of applications, such as data warehousing and Internet/intranet applications.

SQL includes a number of statements that you can use to perform different types of relational operations on the contents of a database, including creating databases and database objects, modifying these objects, and querying databases for information. The most basic SQL statement is the SELECT statement, which you can use to retrieve rows and columns of data from database tables and format the results set.

Examples

The typical format of a SELECT statement is

```
SELECT <columns> FROM <tables> WHERE <rows>
```

where a group of columns are retrieved from a table or tables in which data values are restricted to a particular row or rows. To return all the columns from a table, you can use a wildcard (but this is generally inefficient and should be avoided):

```
SELECT * FROM <tables>
```

Notes

If possible, include a WHERE clause in a SELECT statement to restrict the scope of your query and avoid unnecessary expenditure of system resources. The WHERE clause can include various comparison and logical operators, such as =, >, LIKE, BETWEEN, AND, and IS NULL.

See Also: *database, SQL Server*

structured wiring

Another name for the hierarchical system of unshielded twisted-pair (UTP) cabling used in the typical corporate network.

See: *cabling, infrastructure, premise cabling, unshielded twisted-pair (UTP) cabling*

subnet

A portion of a network that has been subnetted.

See Also: *subnetting*

subnet mask

A 32-bit number that is used to partition Internet Protocol (IP) addresses into a network ID and a host ID.

Overview

Subnet masks are used by Transmission Control Protocol/Internet Protocol (TCP/IP) services and applications to determine whether a given IP address on an internetwork is a local network address or a remote network address. Two types of subnet masks are used in TCP/IP networking:

- **Default subnet mask:** Partitions IP addresses into their network ID and host ID portions
- **Custom subnet mask:** Further partitions the network ID into a number of separate subnets by using a process called subnetting

The default subnet masks for IP address classes A, B, and C are shown in the following table. The table also shows how these subnet masks would partition an IP address such as *w.x.y.z* into a network ID and a host ID portion.

Default Subnet Masks for IP Addresses

Class	*Default Subnet Mask*	*Network ID*	*Host ID*
A	255.0.0.0	*w*	*x.y.z*
B	255.255.0.0	*w.x*	*y.z*
C	255.255.255.0	*w.x.y*	*z*

Implementation

Subnet masks are represented as four-octet dotted-decimal numbers, just as IP addresses are, except that the most common values for an octet in a subnet mask are 0 and 255. In binary notation, decimal 0 represents the octet 00000000, and decimal 255 represents 11111111. A subnet mask thus consists of 32 binary digits, the first n of which are 1s and the remaining of which are 0s.

When the subnet mask is logically ANDed with a 32-bit IP address of a TCP/IP host, the result is the network ID of the host—the portion of the host's IP address that identifies which network the host is on. When the inverse of the subnet mask (for example, the NOT mask) is logically ANDed with the IP address of the host, the result is the host ID of the host—the portion of the host's IP address that uniquely identifies the host on its network.

Examples

For example, consider the IP address 207.61.16.119 and the subnet mask 255.255.255.0. Converting these two numbers to binary and ANDing them gives the host's Network ID:

```
Host = 11001111 00111101 00010000 01110111
Mask = 11111111 11111111 11111111 00000000
AND  = 11001111 00111101 00010000 00000000
     = 207.61.16.0 = network ID
```

Taking the logical NOT of the subnet mask and ANDing it with the host's IP address gives the host's Host ID:

```
    Host = 11001111 00111101 00010000 01110111
NOT Mask = 00000000 00000000 00000000 11111111
     AND = 00000000 00000000 00000000 01110111
         = 0.0.0.119 = host ID
```

S

See Also: *IP address, subnetting*

subnetting

Partitioning a single Internet Protocol (IP) network into multiple subnets.

Overview

To subnet an IP network, you take the assigned network ID and borrow bits from the host ID to establish a group of subnet IDs (subnetted network IDs), one for each subnet. The more bits you borrow, the more subnets you produce, but the fewer the number of possible hosts for each subnet. The borrowing process also defines a unique custom subnet mask for the network. Subnets are then typically joined together using routers.

The advantages of subnetting include

- Reducing network congestion by limiting the range of broadcasts using routers
- Enabling different networking architectures to be joined

Implementation

To subnet your network, you first determine how many subnets you need and the maximum number of possible hosts on each subnet. Then use one of the three tables below, depending on whether you have a Class A, B, or C network ID assigned to your network.

Class A Subnetting Table

Subnet Mask	*Number of Subnets*	*Number of Hosts per Subnet*
255.0.0.0	1	16,777,214
255.128.0.0	2	8,388,608
255.192.0.0	4	4,194,302
255.224.0.0	8	2,097,150
255.240.0.0	16	1,048,574
255.248.0.0	32	524,286
255.252.0.0	64	262,142
255.254.0.0	128	131,070
255.255.0.0	256	65,534
255.255.128.0	512	32,766
255.255.192.0	1024	16,382
255.255.224.0	2048	8190
255.255.240.0	4096	4094
255.255.248.0	8192	2046
255.255.252.0	16,384	1022
255.255.254.0	32,768	510
255.255.255.0	65,536	254
255.255.255.128	131,072	126
255.255.255.192	262,144	62
255.255.255.224	524,288	30
255.255.255.240	1,048,576	14
255.255.255.248	2,097,152	6
255.255.255.252	4,194,304	2

Class B Subnetting Table

Subnet Mask	*Number of Subnets*	*Number of Hosts per Subnet*
255.255.0.0	1	65,534
255.255.128.0	2	32,766
255.255.192.0	4	16,382
255.255.224.0	8	8190
255.255.240.0	16	4094
255.255.248.0	32	2046
255.255.252.0	64	1022
255.255.254.0	128	510
255.255.255.0	256	254
255.255.255.128	512	126
255.255.255.192	1024	62
255.255.255.224	2048	30
255.255.255.240	4096	14
255.255.255.248	8192	6
255.255.255.252	16,384	2

Class C Subnetting Table

Subnet Mask	*Number of Subnets*	*Number of Hosts per Subnet*
255.255.255.0	1	254
255.255.255.128	2	126
255.255.255.192	4	62
255.255.255.224	8	30
255.255.255.240	16	14
255.255.255.248	32	6
255.255.255.252	64	2

Examples

For example, consider a class B network that uses the network ID 172.16.0.0. If this network needs to be subnetted into six subnets, you can accomplish this using a custom subnet mask of 255.255.224.0. Each subnet can be shown to support a maximum of 8190 hosts. The IP address blocks for these six subnets can be selected from the eight possible subnets:

- 172.16.0.1 to 172.16.31.254
- 172.16.32.1 to 172.16.63.254
- 172.16.64.1 to 172.16.95.254
- 172.16.96.1 to 172.16.127.254
- 172.16.128.1 to 172.16.159.254
- 172.16.160.1 to 172.16.191.254
- 172.16.192.1 to 172.16.223.254
- 172.16.224.1 to 172.16.255.254

See Also: *IP address, subnet mask, supernetting*

subtree

A major logical section of the Microsoft Windows 2000, Windows XP, and Windows .NET Server registries.

Overview

Subtrees are the root keys of the registry, and all other registry keys are subkeys of these root keys. The following table summarizes the functions of the five subtrees of the registry.

Subtrees of the Windows NT, Windows 2000, Windows XP, and Windows .NET Server Registries

Subtree	*Function*
HKEY_LOCAL_MACHINE	Contains configuration information for the local machine, including all hardware and software settings
HKEY_CLASSES_ROOT	Provides compatibility with Windows 3.*x* and points to the Classes subkey of HKEY_LOCAL_MACHINE
HKEY_CURRENT_CONFIG	Provides information about the active hardware profile
HKEY_CURRENT_USER	Contains the settings of the user who is currently logged on interactively and points to the SID_# of HKEY_USERS, in which SID_# is the security ID string of the current user

(continued)

Subtrees of the Windows NT, Windows 2000, Windows XP, and Windows .NET Server Registries *continued*

Subtree	*Function*
HKEY_USERS	Contains default system settings and the settings of the user who is currently logged on interactively, plus all previously logged on users

Notes

In Windows 98 and Windows Millennium Edition (Me), a sixth subtree called HKEY_DYN_DATA is generated dynamically and is used for performance measuring by means of System Monitor and plug and play configuration of devices. This subtree is also called the hardware tree.

Most registry troubleshooting takes place in the HKEY_LOCAL_MACHINE\System\Current ControlSet subkey.

See Also: *registry*

supernetting

The opposite of subnetting.

Overview

Subnetting involves creating a subnet mask that causes an Internet Protocol (IP) address to have more network ID bits than its default (classful) subnet mask. For example, the default subnet mask for a Class B address is 255.255.0.0, which identifies addresses for this network as having 16 network ID bits and 16 host ID bits. Subnetting is used to divide the default network into smaller networks. For example, a subnetted subnet mask of 255.255.128.0 identifies each Class B address as having 17 network ID bits and only 15 host ID bits.

Supernetting is the opposite procedure—instead of borrowing bits from the host ID to increase the bits for the network ID (thus increasing the number of networks), supernetting borrows bits from the network ID to increase bits for the host ID, thus combining smaller networks to create larger networks. For example, a supernetted subnet mask of 255.254.0.0 identifies each class B address as having 15 network ID bits and 17 host ID bits, thus creating fewer networks, each with more hosts, than when using the default subnet mask.

Implementation

Supernetting is needed because the number of available class B addresses is small. By using supernetting, contiguous blocks of class C addresses can be combined and used for networks larger than a single class C block can satisfy. For example, if a company needs to deploy 2000 hosts as an IP network that is directly connected to the Internet, it can assign IP addresses for these hosts by

- Using a single class B network ID. This approach is wasteful, as each class B network can support up to 65,534 different hosts, so most of these addresses would end up not being used. Also, it might be difficult or impossible to obtain a class B network ID from your Internet service provider (ISP), as they might have none available to assign.
- Using eight separate class C network IDs, each of which can support up to 254 different hosts, making a total of 8 x 254 = 2032 hosts. This method would work, but it would lead to poorer routing performance because each router would require eight entries in its routing table, one for each of the eight networks to which frames could be forwarded.
- Using supernetting to collapse the above block of eight class C network IDs into a single supernetted network ID. This is the best solution, as only one routing table entry will be required. The router must support classless interdomain routing (CIDR) for this procedure to work (most routers on the Internet support CIDR).

See Also: *classless interdomain routing (CIDR), IP address, subnet mask, subnetting*

surge protector

Also known as a surge suppressor, a device that protects sensitive data communications equipment (DCE) and data terminal equipment (DTE) from sudden rises in power line voltages called surges or spikes.

Overview

Surges occur only with copper cabling such as twisted-pair cabling or coaxial cabling—they do not occur with fiber-optic cabling, which is one advantage of using this more expensive type of cabling for networking applications. Surge protectors use various technologies for absorbing or deflecting unwanted electrical current, including avalanche diodes, metal oxide varistors, and chokes or filters. One of the best electrical protection methods, especially for copper wiring runs between different buildings, is to use opto isolators, which convert electrical signals to light and then back again, thus providing true electrical isolation between the connected buildings. However, opto isolation in itself does not provide surge protection; this is the responsibility of the other components described, the most common component being one of the various types of diodes.

Surge protectors for computer networking come in two main types:

- **Data-line surge protectors:** Connected to network cabling to prevent power surges from damaging networking components.
- **Alternating current (AC) outlet surge protectors:** Connected to AC outlets that provide power for networking components. These surge protectors prevent AC power spikes from damaging networking components.

See Also: *data communications equipment (DCE), data terminal equipment (DTE)*

SVC

Stands for switched virtual circuit, circuit-switching where switches are dynamically set up and torn down as needed.

See: *switched virtual circuit (SVC)*

switch

Any device that can control the flow of electrical signals.

Overview

A number of types of switches are used in computer networking for different purposes. For example, to control access by computers to printers, keyboards, and monitors you can use

- **Matrix switches:** Have a keypad for mapping input ports to output ports and are typically used to connect several printers to several workstations
- **Code-operated switches:** Use a data string sent by the PC to select the printer port to be used
- **Port-contention or scanning switches:** Use several input ports but only one output port and monitor the input ports continually for data to route to the output port
- **Keyboard Video Mouse (KVM) switches:** Allow one keyboard/video-monitor/mouse to be used for several servers

In the context of high-speed Ethernet networks, the term *switch* refers to an Ethernet switch, also called a local area network (LAN) switch or simply a switch. Thus, the phrase “routers and switches” is understood to mean “routers and Ethernet switches.” In general, when referring to controlling data flow within a network, the term *switch* describes any data-link layer device that transfers frames between connected networks. Besides Ethernet, another popular networking technology that employs switches is Asynchronous Transfer Mode (ATM) networking.

Finally, the term *switch* is also used to refer to a device used at a telco central office (CO) for establishing connections in circuit-switched services or for forwarding packets in packet-switched services.

See Also: *Asynchronous Transfer Mode (ATM), central office (CO), circuit-switched services, data-link layer, Ethernet, Ethernet switch, Keyboard Video Mouse (KVM) switch, packet-switching services*

Switched 56

A digital switched-data communication technology that provides full-duplex dial-up connections at a speed of 56 kilobits per second (Kbps).



Switched 56. *Using the Switched 56 service.*

Overview

Switched 56 is essentially the dial-up version of digital data service (DDS) and is generally cheaper than leased-line services. A device called a data set, which is a type of Data Service Unit (DSU), provides Switched 56 services to customer premises. For a typical local area network (LAN) connection, a router on the LAN is attached to the data set by using a V.35 serial interface. The data set is then connected over the customer's local loop twisted-pair wiring to access equipment located at the telco's central office (CO).

Switched 56 uses the same communication channels as DS0. You can establish circuits by manually entering the destination number on a numeric keypad or (more typically) by using in-band signaling when connecting bridges or routers to the service. Depending on the wiring at the customer premises and the equipment at the CO, you can use one of three configurations for this service:

- **Type I service:** Uses a two-pair (4-wire) connection and is supported up to 3.5 miles (5.5 kilometers) from the CO over standard 26-gauge copper twisted-pair wiring.
- **Type II service:** Uses a one-pair (2-wire) connection with in-band signaling. This type is not widely implemented.
- **Type III service:** Uses a one-pair (2-wire) connection with out-of-band signaling and is supported to up to 3.5 miles (5.5 kilometers) from the CO on 22-gauge or 24-gauge copper twisted-pair wiring and includes forward error correction for enhanced data transmission. Although Type III service appears to be full-duplex, in reality time-compression multiplexing (TCM) rapidly switches half-duplex communication at 160 Kbps to simulate full-duplex at 56 Kbps.

Notes

Some carriers offer other higher speed versions of Switched 56. For example, some carriers offer Switched 56 as a 64-Kbps service under the name Switched 64. Other higher dial-up services include Switched 384 and Switched 1536, although these are not widely offered anymore.

Switched 56 is a data-only service that is often available where Integrated Services Digital Network (ISDN) is not available. However, Switched 56 does not support advanced ISDN features such as caller ID and has greater latency for establishing a connection. The cost is typically billed in the same way that ordinary telephone calls are—that is, local calls are free and long distance is billed by the minute.

Dial-up Switched 56 was originally used as a backup wide area network (WAN) link between two networks connected by expensive T1 lines, but it has been phased out by most carriers in favor of ISDN.

See Also: *telecommunications services*

Switched Multimegabit Data Services (SMDS)

A high-speed metropolitan area network (MAN) data service offered by some telcos.

Overview

Switched Multimegabit Data Services (SMDS) is a connectionless, shared-medium telecommunications service that can support data transfer speeds ranging from 56 kilobits per second (Kbps) to 34 megabits per second (Mbps). SMDS was developed by Bellcore in the late 1980s and was first deployed in 1992. SMDS was the first high-speed broadband networking technology offered to subscribers for high-speed wide area network

(WAN) communications and was a precursor to Asynchronous Transfer Mode (ATM) networking. SMDS never really caught on, however, and most carriers are now phasing it out, offering ATM and Synchronous Optical Networking (SONET) services instead. About the only place where SMDS is still provisioned in preference to ATM is Great Britain, where British Telecom (BT) continues to offer this service to customers.



Switched Multimegabit Data Services (SMDS). *Connecting a LAN to an SMDS service.*

Implementation

SMDS is a packet-switching technology similar to Frame Relay and cell-switched ATM. SMDS cells are, in fact, almost identical to ATM cells but use an 8-bit access control field instead of a 4-bit generic flow control field as in ATM. In contrast to the connection-oriented switched-fabric of ATM, however, SMDS is a connectionless service that operates over a shared medium. SMDS and ATM are thus very different in operation and architecture.

The subscriber typically connects to the carrier's SMDS service through a switch or router using an integrated Channel Service Unit/Data Service Unit (CSU/DSU). The CSU/DSU demark point connects to the carrier's SMDS switches over a copper DS-1 connection (1.544 Mbps) for low-speed access or a fiber DS-3 connection (44.736 Mbps) to achieve the highest possible transmission speeds. This point of connection between the subscriber's LAN and the telco's central office (CO) is called the Subscriber Network Interface (SNI). The CO provides a gateway to the SMDS packet-switching network, which consists of high-speed switches joined by trunk lines connecting different telco COs.

An SMDS packet consists of a header with the source address, destination address, and a payload of up to 9188 bytes. The SMDS payload is large so that SMDS can easily encapsulate Ethernet, Token Ring, and Fiber Distributed Data Interface (FDDI) frames for WAN transmission. The E.164 addressing scheme uses decimal numbers up to 15 digits long and includes a country code, area code, and subscriber ID number (similar to ordinary telephone numbers). Different address classes support different data transfer speeds. The serial protocol used for communication between the customer premises equipment and SMDS equipment at the telco's CO is called the SMDS Interface Protocol (SIP), which is based on the IEEE 802.6 standard for MANs. The primary function of SIP is to provide encapsulation of the LAN protocol. (Internet Protocol, Internetwork Packet Exchange, AppleTalk, and just about anything else is supported.) Higher-layer protocols support processes such as address resolution and source address screening.

See Also: *802.6, Asynchronous Transfer Mode (ATM), Channel Service Unit/Data Service Unit (CSU/DSU), Ethernet, Fiber Distributed Data Interface (FDDI), frame relay, metropolitan area network (MAN), router, Synchronous Optical Network (SONET), telco, Token Ring, wide area network (WAN)*

switched virtual circuit (SVC)

Circuit-switching where switches are dynamically set up and torn down as needed.

Overview

Switched virtual circuits (SVCs) are used in circuit-switched services such as the Public Switched Telephone Network (PSTN) and Integrated Services Digital Network (ISDN). The PSTN employs a separate signaling network called Signaling System 7 (SS7) for establishing a communications session between two end nodes. The SS7 is used to configure switches in the telco switching fabric in order to establish a temporary path between the two end nodes. Once the call is finished, SS7 is used to tear down the connection, freeing up these switches to be used for other connections.

SVCs are also employed in certain wide area network (WAN) services such as Asynchronous Transfer Mode (ATM) and frame relay networking. Here different signaling methods are used to set up a temporary switched path through the ATM or frame relay cloud. For example, ATM can use the Interim Interswitch Signaling Protocol (IISP) or the Private Network-to-Network Interface (PNNI) signaling protocols to set up and tear down SVCs, and it can also use Multiprotocol Label Switching (MPLS) to route cells over ATM wide area network (WAN) links.

Comparison

SVCs might be contrasted with permanent virtual circuits (PVCs), which are more commonly used in ATM and frame relay WAN environments. PVCs are point-to-point connections between two end nodes that are permanently configured by the service provider and that utilize dedicated switches in the provider's switching fabric. PVCs are more expensive than SVCs because they need dedicated switching resources. In contrast, SVCs are temporary links in which the actual path over which frames are routed between the two end nodes varies from session to session. Each new session thus requires a new switching path to be established, with the result that SVCs are more flexible and cheaper than PVCs but often suffer from inconsistent connection quality between different sessions.

Notes

Most telcos still offer only PVCs for their wide-area ATM service offerings, mainly because SVCs are more difficult to implement due to the extra signaling protocols involved.

See Also: *Asynchronous Transfer Mode (ATM), circuit-switched services, frame relay, Integrated Services Digital Network (ISDN), Multiprotocol Label Switching (MPLS), permanent virtual circuit (PVC), Public Switched Telephone Network (PSTN), telco, wide area network (WAN)*

Symmetric Digital Subscriber Line (SDSL)

A form of business-grade Digital Subscriber Line (DSL) service.

Overview

Symmetric Digital Subscriber Line (SDSL) is used to provide business subscribers with permanent, high-speed data connections at speeds similar to dedicated T1 lines but at much lower prices. SDSL is based on High-bit-rate Digital Subscriber Line (HDSL) and provides data transfer speeds of 1.5 megabits per second (Mbps) in North America and 2.048 Mbps in Europe. Unlike its cousin Asymmetric Digital Subscriber Line (ADSL), which is popular in the residential broadband Internet access market, HDSL is a symmetric technology in which upstream and downstream speeds are equal.

SDSL employs the 2 Binary 1 Quaternary (2B1Q) line coding scheme used by the Basic Rate Services (BRI) form of Integrated Services Digital Network (ISDN). Although its cousin HDSL needs two pairs of copper wires (four wires), SDSL requires only one pair of wires (two wires) to work. Unlike ADSL, however, which allows a single phone line to carry both voice and data by using a splitter to "split off" frequencies above 26 kilohertz (KHz) for DSL signaling, SDSL takes complete control of the frequency spectrum of the wires, uses no splitter, and provides a data-only service.

SDSL maximum data rates vary with distance from the telco central office (CO). For distances up to 10,000 feet (3 kilometers), speeds of 1.5 Mbps are supported, which is equivalent to T1 speed. At farther distances speeds drop, until at 18,000 feet (5.5 kilometers) SDSL can only carry data at 416 kilobits per second (Kbps).

In the last few years, SDSL has became an attractive offering from competitive local exchange carriers (CLECs) who wanted to compete with high-priced T1 lines offered by incumbent local exchange carriers (ILECs), who generally used HDSL for provisioning these services.

Notes

SDSL is sometimes interpreted to stand for single-line DSL instead of symmetric DSL because it uses a single twisted-pair copper wire.

See Also: *Asymmetric Digital Subscriber Line (ADSL), Basic Rate Interface ISDN (BRI-ISDN), central office (CO), Competitive Local Exchange Carrier (CLEC), High-bit-rate Digital Subscriber Line (HDSL), Incumbent Local Exchange Carrier (ILEC), Integrated Services Digital Network (ISDN), line coding, T1, telco*

SYN attack

A popular form of denial of service (DoS) attack.

Overview

Also called SYN flooding, the SYN attack is a form of DoS attack directed at Transmission Control Protocol/Internet Protocol (TCP/IP) networks connected to the Internet. A SYN attack is a protocol-level attack that can make a computer's network services unavailable to other users. SYN flooding is a DoS methodology specific that exploits the session establishment mechanism of the TCP. Using SYN flooding, an attacker can usurp control of all possible TCP/IP connections to a Web server or other Internet resource, making it impossible for legitimate users to access the resource. The *SYN* refers to the "**sy**nchronize sequence **n**umber" message that is used to initialize a TCP connection.

Implementation

A malicious user initiates a SYN attack by sending a Transmission Control Protocol (TCP) connection request (SYN packet) to a targeted server in a network, usually a Web server. The attacker uses spoofing to alter the source IP address in the SYN packet. When the server receives the connection request, it allocates resources for handling and tracking the new connection and responds by sending a SYN-ACK packet to the nonexistent source address. Because there is no response to the SYN-ACK packet, the server continues to retransmit SYN-ACK several times (five times in Microsoft Windows NT) at increasingly longer time intervals. Finally, after the last retransmission, the server gives up and deallocates the resources previously allocated for the connection. For servers running Windows NT, the default time for this entire process is 189 seconds. The attacker configures software to automatically send large numbers of TCP SYNs in an attempt to tie up the server's TCP resources and prevent other users from connecting to the server.

Notes

SYN attacks against private networks are simple to prevent: you configure a firewall with access lists to accept only incoming IP addresses with known addresses. However, if you are running a Web server that needs to be accessible to anyone on the Internet, it is usually more difficult to defend the server against a SYN attack because if you configure an input filter, the attacker can simply modify the source IP address in the SYN packets. Ways to defend Web servers against SYN attacks include decreasing the time-out period for the TCP three-way handshake mechanism, increasing the size of the SYN-ACK queue, and applying various vendor-supplied patches to your Web server. For more information on configuring Internet Information Services (IIS) servers to withstand SYN attacks, consult the *Microsoft Internet Information Server Resource Kit* from Microsoft Press.

If you are running a Web server and your Web clients are receiving messages such as "The connection has been reset by the remote host," you might be the target of a SYN attack. If you are running IIS as your Web server, type **netstat –n –p tcp** at the command prompt to examine the number of TCP connections in a SYN_RECEIVED state. A large number of SYN_RECEIVED connections might indicate that your server is under attack.

See Also: *denial of service (DoS), hacking, TCP three-way handshake, Transmission Control Protocol (TCP)*

sync

Stands for synchronous transmission, serial transmission in which the sending and receiving nodes are synchronized together by a timing signal.

See: *synchronous transmission*

Synchronous Data Link Control (SDLC)

A data-link layer protocol developed in the 1970s by IBM for its Systems Network Architecture (SNA) networking environment.

Overview

Synchronous Data Link Control (SDLC) is primarily used in wide area networks (WANs) that use leased lines to connect mainframe SNA hosts and remote terminals. SDLC was the first bit-oriented synchronous transmission protocol developed by IBM. It quickly displaced the older, less efficient, character-oriented synchronous protocols such as Bisync and DDCMP. In a serial SDLC link, data is sent as a synchronous bit stream divided into frames that contain addressing and control information in addition to the payload of data.


Mainframe host
Controller
56-Kbps leased line using SDLC
56-Kbps leased line using SDLC
Remote terminals
Front-end processor

Synchronous Data Link Control (SDLC). *Connecting remote terminals to a mainframe host using SDLC.*

Implementation

SDLC uses a master/slave architecture in which one station is designated as primary (master) and the remaining stations are secondary (slaves). The primary station establishes and tears down SDLC connections, manages these connections, and polls each secondary station in a specific order to determine whether any secondary station wants to transmit data. You can use SDLC in a variety of connection topologies, including direct point-to-point connections between a primary and a secondary station and multipoint connections between a primary and a group of secondary stations. Ring topologies are also possible in which a primary controls a ring of secondary stations and is itself part of the ring.

Notes

A number of popular protocols have been derived from the SDLC protocol and standardized by various standards bodies. These include the following:

- **High-level Data Link Control (HDLC):** Developed by the International Organization for Standardization (ISO) and used by Cisco Systems routers for serial communication over leased lines as an alternative to the Point-to-Point Protocol (PPP)
- **Link Access Procedure Balanced (LAPB):** Part of the X.25 protocol stack
- **Logical Link Control (LLC) or IEEE 802.2:** The most popular data link protocol for local area networks (LANs)

See Also: *High-level Data Link Control (HDLC), Systems Network Architecture (SNA)*

Synchronous Optical Network (SONET)

A physical layer specification for broadband synchronous transmission used by telecommunications carriers.

Overview

Synchronous Optical Network (SONET) can simultaneously carry voice, video, and data over long distances of fiber-optic cabling at speeds in excess of 1 gigabit per second (Gbps). SONET was developed by Bellcore in the mid-1980s to carry high-volume voice traffic on the Public Switched Telephone System (PSTN). SONET was standardized by the American National Standards Institute (ANSI). A European version called Synchronous Digital Hierarchy (SDH), standardized by the International Telecommunication Union (ITU), is almost identical to the SONET specification.

Uses

SONET is primarily used by telecommunications carriers (telcos) as the underlying transport mechanism for Asynchronous Transfer Mode (ATM) networking. As such, SONET is widely deployed in both the internal telco switching networks and the trunk networks owned by long-distance carriers. SONET is used in the enterprise environment mainly as the underlying transport for high-speed ATM wide area network (WAN) connections. SONET is a reliable WAN technology that typically provides better than five-nines (99.999 percent) uptime.

Implementation

SONET transmission is generally built from multiplexed DS-0, DS-1, or DS-3 digital signal channels. SONET employs optical time-division multiplexing (TDM) technologies to form a single Synchronous Transport Signal (STS) link that is demultiplexed at the receiving end. The basic SONET transmission rate is 87 bytes transmitted every 125 microseconds, and these SONET frames are transmitted whether or not payload (data) is present. As a result, SONET tends to be somewhat wasteful of bandwidth, with utilizations in access networks often below 5 percent and in ATM backbones below 30 percent. SONET frames expand in size as the speed increases, with 16,704-byte frames being employed for OC-192 circuits. SONET transports local area network (LAN) traffic such as Gigabit Ethernet (GbE) frames by encapsulating them within SONET frames.

SONET capacity is measured in optical carrier (OC) units. A standard Synchronous Transport Signal (STS) SONET channel is equivalent to one OC unit and consists of 810 multiplexed 64 kilobit-per-second (Kbps) DS0 circuits forming a total capacity of 51.84 megabits per second (Mbps). Of these 810 circuits, 783 are used for payload and 27 are used for framing, error correction, format identification, and other forms of protocol overhead. The table below shows some of the currently defined SONET speeds.

SONET is usually implemented in telco networks as a dual-ring topology in order to provide redundancy and fault tolerance. One ring is the active ring and carries traffic in one direction only. The backup ring remains inactive unless a break in the primary ring occurs, in which case the backup ring takes over and carries traffic in the opposite direction. SONET rings utilize a self-healing technology called Automatic Protection Switching (APS) that can detect when the active ring is broken and switch traffic to the backup ring within 50 milliseconds.

SONET Speeds

Electrical Signal	*Optical Carrier*	*Speed*
STS-1	OC-1	51.48 Mbps
STS-3	OC-3	155.52 Mbps
STS-12	OC-12	622.08 Mbps
STS-24	OC-24	1.24 Gbps
STS-48	OC-48	2.48 Gbps
STS-192	OC-192	9.95 Gbps

Issues

Because SONET was originally designed as a circuit-switched TDM communications technology, it is ill-suited to carrying packet data and wasteful of bandwidth when used for this purpose. SONET was designed for carrying voice, a form of traffic that is highly sensitive to latency and jitter, and not packet data, which can tolerate high degrees of variation and delay.

SONET is also complex and expensive to deploy, which is why its implementation has been limited to telco networks. Due to the large installed base of telco SONET equipment, SONET is likely to remain around for many years despite the emergence of optical Ethernet in the metropolitan area network (MAN) as a viable alternative. SONET's main advantage over Gigabit Ethernet (GbE) and emerging 10 Gigabit Ethernet (10GbE) technologies is that it can transport data over much longer distances than these newer technologies can. Even if local exchange carriers (LECs) eventually migrate their systems entirely to 10GbE, SONET is likely to remain the technology of choice for inter-exchange carriers (IXCs) to carry data on their long-haul trunk lines.

Prospects

The trend with many carriers is to abandon SONET entirely except for use as a common communications interface passing traffic off to other carriers. Some newer carriers such as Yipes Communications are pursuing this route, using GbE instead of SONET within the remaining portion of their MANs.

A new SONET technology called resilient packet ring (RPR) enables SONET to simultaneously utilize both rings in a standard dual-ring system. If one ring fails, all traffic is routed to the remaining ring.

See Also: *American National Standards Institute (ANSI), Asynchronous Transfer Mode (ATM), DS-0, Gigabit Ethernet (GbE), inter-exchange carrier (IXC), local exchange carrier (LEC), multiplexing, optical carrier (OC-x) level, Public Switched Telephone Network (PSTN), resilient packet ring (RPR), telco, wide area network (WAN)*

synchronous transmission

Serial transmission in which the sending and receiving nodes are synchronized together by a timing signal.

Overview

Synchronous transmission is a form of serial transmission that uses clocking circuitry at both the transmitting station and the receiving station to ensure that communication is synchronized. This is in contrast to asynchronous transmission, in which start and stop bits are added to the beginning and end of each frame. Synchronous transmission is used in digital modems such as Integrated Services Digital Network (ISDN) terminal adapters, Channel Service Unit/Data Service Units (CSU/DSUs) for T-carrier services, and similar telecommunications services. Synchronous transmission interfaces are generally about 20 percent faster and somewhat more reliable than comparable asynchronous interfaces.

Implementation

Devices that communicate with each other synchronously use either separate clocking channels to ensure synchronization between them or some kind of special signal code embedded in the signal for self-clocking purposes. Separate clocking lines are generally used when the distance between the data terminal equipment (DTE) and data communications equipment (DCE) is fairly short. Typically, the receiving station (such as a modem, a common form of DCE) provides the clocking signal to the transmitting station (usually a computer or a terminal).

The alternative is to use signal preamble, a special group of bytes (usually 8 bytes) called a SYNC signal that alerts the receiver that data is coming, synchronizes the clocks at the two devices, and starts the transmission. Special predefined voltage transition patterns familiar to both the transmitting and receiving stations are contained within the signal and are used to maintain synchronization between the devices. The receiver must extract this embedded information from the signal and use it to maintain synchronization between it and the transmitting station.

See Also: *asynchronous transmission, serial transmission*

SYN flooding

Also known as SYN attack, a popular form of denial of service (DoS) attack.

See: *SYN attack*

system access control list (SACL)

A form of access control list (ACL) used by Microsoft Windows 2000 and Windows .NET Server for security control.

Overview

System access control lists (SACLs) are used for establishing systemwide security policies for actions such as logging or auditing resource access. SACLs should not be confused with the more familiar discretionary access control lists (DACLs) used by Windows 2000 and Windows .NET Server to control access to Active Directory directory service and NTFS file system (NTFS) objects by users and groups.

The SACL attached to a system, directory, or file object specifies

- Which security principals (users, groups, computers) should be audited when accessing the object
- Which access events should be audited for these principals

- Whether a Success or Failure attribute is generated for an access event, depending on the permissions granted in the DACL for the object

See Also: *access control, access control list (ACL), discretionary access control list (DACL)*

system group

Another name for special identity, a special group account in Microsoft Windows 2000 whose membership is controlled by the operating system itself, not by administrators or individual users.

See: *special identity*

system log

A log in Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server that records events generated by the operating system.

Overview

Events logged in the system log mainly consist of information about services starting, stopping, or failing and about system device drivers that fail. Administrators cannot alter the type of information logged in the system log. You can view and manage the system log by using the administrative tool Event Viewer.

The following are three types of events that can be logged to the system log:

- **Errors:** Identified by a white *X* in a red circle; indicates a significant problem that might have caused data loss or the loss of some aspect of system functionality (for example, a service failing to start properly)
- **Warnings:** Identified by an exclamation mark in a yellow triangle; indicates a problem that might not be critical but might have an impact later (such as low disk space)
- **Information:** Identified by a blue letter *i* in a speech balloon; indicates a significant but harmless event such as a service starting or device driver initializing

See Also: *application log, security log*

system partition

The partition on which Microsoft Windows 2000 and Windows .NET Server install hardware-specific files that are needed to start the operating system.

Overview

The files installed on the system partition include the boot loader file (ntldr), the hardware detector file (Ntdetect.com), and the Boot.ini file. The system partition is different from the boot partition, which contains the actual Windows 2000 operating system files and supporting files. During the boot process, the code in the Master Boot Record (MBR) locates the system partition by scanning the partition table.

The system partition must be on the first physical hard disk of the machine and must be an active partition (and hence a primary partition). In a default Windows 2000 installation, both the system partition and boot partition are on the C: drive.

See Also: *boot partition*

system policy

A file that applies a set of rules to a Microsoft Windows NT computer or set of computers to restrict what users or groups of users can see and do on their workstations.

Overview

System policies are included as an administrative feature on the Windows NT operating system platform for helping administrators lock down the desktop configuration of Microsoft Windows NT Workstation, Windows 98, and Windows 95 clients. On the Windows 2000 and Windows .NET Server platforms, a more advanced feature called Group Policy is implemented, which is integrated with Active Directory directory service.

System policies work by overwriting specific registry keys on the computers they are applied to. To apply a system policy to computers in a Windows NT domain, put the Ntconfig.pol file in the NetLogon Share on the primary domain controller (PDC) and use the Directory Replicator Service to replicate the file to other domain controllers. When users log on to the network, the system policy file is downloaded and applied to their Windows NT workstations.

You can create system policy files for Windows NT Workstation clients by using the administrative tool System Policy Editor. A system policy file created this way is usually named Ntconfig.pol.

Notes

If users have Windows 95 or Windows 98 clients, use Poledit.exe to create a Config.pol file and place this in the NetLogon Share, as just described. System policy files created for Windows 95 and Windows 98 clients are usually named Config.pol. If you have a mix of Windows NT, Windows 95, and Windows 98 clients on the network, you must create both an Ntconfig.pol file and a Config.pol file and store them in the NetLogon Share on the PDC.

See Also: *Group Policy*

Systems Management Server (SMS)

A server application from Microsoft Corporation for managing an organization's networked computers.

Overview

Microsoft Systems Management Server (SMS) lets network administrators

- Manage their hardware and software assets
- Distribute new software from a central location
- Manage shared applications loaded from network servers
- Perform network protocol analysis for planning and troubleshooting purposes
- Perform remote troubleshooting and remotely control individual PCs

For example, you can use SMS to determine which computers need updated drivers, which have sufficient free disk space to run new applications, or how many copies of Microsoft Office are installed in your organization. This simplifies maintenance and upgrading tasks for network administrators.

Using SMS, you can also manage, install, and control server-based applications from a central location. You can perform network protocol analysis to locate and resolve bottlenecks on your network. Using the administrative tools of the Microsoft Windows NT operating system, administrators have a single, consistent administrative environment for managing their network assets.

SMS organizes a company's network assets into hierarchical logical groupings of computers and domains called sites. Using the top site, an administrator can centrally manage the entire network. Sites can be designed so that sites without administrators can be managed by sites with administrators. This logical structure is scalable—as your company grows and your needs change, you can add sites and structure.

A typical SMS enterprise deployment might consist of the following tiers:

- A central SMS machine linked to a computer running Microsoft SQL Server that hosts the corporate inventory database, which includes centralized hardware and software inventory information on all your networked computers.
- Primary SMS servers for sharing the load of distribution to the logon servers. These are located so that the majority of network traffic generated by SMS is on local segments.
- Local area network (LAN) servers such as Windows NT and Windows 2000 domain controllers, file and print servers, and application servers.
- Clients such as Windows NT, Windows 2000, Windows 98, or Windows 95.

Software is distributed down the hierarchy, and inventory information is passed up the hierarchy. At each SMS site, inventory information is collected and forwarded to the site above it. Thus, the SMS database at the top site has complete inventory information for the entire network. From this top site, you can use the Systems Management Server Administrator program to query and view the inventory database for hardware, software, and configuration information about any computer on your network. Queries can be specific—for example, you can determine which computers in your network have Pentium processors or which systems have Office installed.

You can also use SMS to distribute and install software on clients and servers on your network, and you can schedule software distribution to minimize the impact on your system. The Systems Management Server Administrator program can

- Send software from one site to another.
- Move software to selected servers called distribution servers. Users can then access and install the software on their clients from these servers.
- Set up and configure network applications on servers for shared use by groups of users. SMS automatically creates a program item for the network application on users' computers.
- Install and configure software on clients and servers.

The following additional features of SMS 2 make it easy to use:

- Integrated setup with SQL Server
- Enhanced administration using wizards, taskpads, and Microsoft Management Console (MMC)
- Context-sensitive Hypertext Markup Language (HTML)–based help
- A nonintrusive 32-bit agent client that is invisible to the user except when distribution packages are available
- A status system that provides a common reporting mechanism for all components
- Support for the Common Information Model (CIM) specification
- Dynamic, discovery-based software inventory mechanisms
- The Network Topology Tracing Tool, which provides a graphical display of the network routes between servers within a site, including infrastructure devices such as routers and hubs
- Dynamic distribution lists for sending software to users automatically when they join a group

For More Information

Visit *www.microsoft.com/smsmgmt.*

Systems Network Architecture (SNA)

A set of IBM mainframe networking standards and protocols introduced in 1974.

Overview

Systems Network Architecture (SNA) includes services for configuring and managing system resources within an IBM mainframe networking environment. SNA originally defined a centralized architecture with mainframe hosts controlling terminals, but it has also been adapted for peer-to-peer communication and distributed client/server computing environments.

Architecture

SNA has seven protocol layers and is similar but not identical to the Open Systems Interconnection (OSI) reference model, whose development it influenced. The SNA protocol suite includes the following:

- **Synchronous Data Link Control (SDLC) protocol:** For data-link layer control of the flow of frames within an SNA network. SNA also supports IEEE 802.5 and 802.2 token passing with Logical Link Control (LLC).
- **Network Control Program (NCP):** For routing, segmentation, and framing functions. NCP usually runs on the host or on the front-end processor.
- **Virtual Telecommunications Access Method (VTAM):** For sequencing, flow control, error recovery, and session management functions. You use VTAM to implement Network Accessible Units (NAUs), which control the flow of data, in an SNA network.
- **Advanced Peer-to-Peer Networking (APPN):** Enables SNA connections between two hosts, such as a PC host accessing an application running on a mainframe host using Advanced Program-to-Program Communications (APPC) sessions. You use APPN to implement Physical Units (PUs) and Logical Units (LUs), which are forms of NAUs that control communication processes for hosts and terminals. LUs represent SNA end nodes such as connections by users or applications, and two LUs communicate by using associated PUs, which are

hardware devices or terminals. A number of types of LUs and PUs are used in an SNA networking environment.

- **NetView:** A network management program for configuring, controlling, troubleshooting, and usage accounting of SNA networks.

Before data can be transferred over SNA, a session must be established between an LU on the client and an LU on the host. For example, a Microsoft Windows NT– or Windows 2000–based server running Microsoft Host Integration Server can connect to a mainframe host by using SNA. Host Integration Server provides connectivity between Windows and SNA environments by providing an SNA gateway running on a Windows NT–, Windows 2000–, or Windows .NET–based server. Windows clients can then connect to the SNA mainframe host by going through the Host Integration Server gateway. By using LU 6.2, which is a peer-to-peer protocol, the Windows NT–based server running Host Integration Server or the mainframe host can initiate the user session. Clients on a Windows NT– or Windows 2000–based network can then access data stored on the host, including data stored in structured or unstructured AS/400 or Virtual Storage Access Method (VSAM) files, DB2 database tables, and transaction processing monitors.

Notes

Non-SNA architectures such as Token Ring networks can interface with SNA networks using Service Points (SPs).

See Also: *Advanced Peer-to-Peer Networking (APPN), Open Systems Interconnection (OSI) reference model, Synchronous Data Link Control (SDLC)*

SYSVOL share

An administrative share on Active Directory directory service–based installations of Microsoft Windows 2000 and Windows .NET Server.

Overview

The SYSVOL share is a shared directory on a domain controller on Windows 2000– and Windows .NET Server–based networks that contains the server's copy of the domain public files, such as group policy objects and scripts for the current domain and the entire enterprise. The contents of this share are replicated to all domain controllers in the Windows 2000 domain. The default path for the SYSVOL share is \%System_Root%\Sysvol\SYSVOL.

Notes

The SYSVOL share must be on an NTFS file system (NTFS) 5 volume because Active Directory uses the journaling function of NTFS 5 to track replication updates.

T

T1

The lowest level of the T-carrier hierarchy.

Overview

T1 is part of the T-carrier digital transmission architecture developed for the Public Switched Telephone Network (PSTN) in the 1960s. A T1 circuit (also called a T1 line) is formed from a combination of 24 DS-0 (Digital Signal Zero) channels, each having a bandwidth of 64 kilobits per second (Kbps), for a total bandwidth of 1.544 megabits per second (Mbps). These 24 DS-0 channels can either be used separately for carrying 24 separate voice circuits (called channelized T1) or aggregated into a single data stream (called unchannelized T1) for high-speed wide area network (WAN) connections.

T1 (sometimes called T-1) actually stands for T-carrier Level 1, but it is almost never referred to in this way.

Uses

T1 is the preferred technology used by enterprises for combining voice, fax, and data transmissions. This is because T1 is "trunking" technology that enables a single physical circuit to support as many as 24 separate virtual circuits, a process which is generally cheaper than provisioning 24 separate physical links. T1 lines are also typically used

- To provide enterprises with dedicated leased-line WAN links among remote locations—for example, to connect a branch office to corporate headquarters.
- To provide corporate users with high-speed access to the Internet.

Architecture

Like other members of the T-carrier family, T1 uses time-division multiplexing (TDM) to interleave multiple DS-0 channels into a single bit stream (called a DS-1 circuit). DS-0 generates 8 bits (1 byte) every 125 microseconds, or 8000 DS-0 frames per second. The bandwidth of a DS-0 channel is therefore

```
DS-0 = 8 bits x 8000 per second
     = 64,000 bits per second (bps)
     = 64 kilobits per second (Kbps)
```

Because T1 multiplexes 24 DS-0 channels together, a single T1 frame (or DS-1 frame) should equal 24 x 8 = 192 bps. The T1 specification, however, adds an extra bit to each frame to ensure that transceivers at each end of the line maintain their synchronization. This extra bit is added at the start of each DS-1 frame, which makes the length of a DS-1 frame equal to 192 + 1 = 193 bits. Using the same transmission rate of 8000 frames per second, this means that the total bandwidth of a T1 circuit is

```
T1 = 193 bits/frame x 8000 frames/sec
   = 1544000 bits/sec
   = 1.544 Mbps
```

TDM is applied to the individual DS-0 channels in such a way that each DS-0 channel is located at the same position of each DS-1 frame generated.

To package binary information into electrical signals, T1 originally used the Alternate Mark Inversion (AMI) line coding mechanism in which a voltage represents a binary 1 and no voltage represents zero. The problem with this mechanism was that it was hard to maintain synchronization between transceivers at opposite ends of the T1 circuit when a large number of successive 0s or 1s were transmitted. A scheme was therefore devised whereby bits were "robbed" from certain parts of each frame to ensure that synchronization could be maintained and to allow for control and signal maintenance information to be carried in-band within the circuit. The net result of this bit robbing was to reduce the data-carrying capacity of each DS-0 channel within DS-1 from 64 Kbps to only 56 Kbps. However, this bit-robbing scheme has no discernable effect on voice transmission.

You can work around the capacity-robbing effect of this bit robbing by replacing AMI line coding with Bipolar with 8-bit Zero Substitution (B8ZS) line coding. B8ZS substitutes a special byte if eight consecutive zero bits are detected to maintain a specific ones density to help maintain synchronization. This approach is called "ones density" and allows a T1 channel service unit/data service unit (CSU/DSU) at the customer premises to recover the data clock reliably when synchronization is lost with the T1 multiplexer at the telco central office (CO). The result of using B8ZS is that each DS-0 channel can carry the full 64 Kbps of data. An alternative scheme to B8ZS that is also commonly used is Zero Byte Time Slot Interface (ZBTSI) line coding.

Bellcore also developed an alternate scheme whereby a 2 Binary 1 Quaternary (2B1Q) line coding scheme was employed. 2B1Q is the same signal encoding mechanism employed by Integrated Services Digital Network (ISDN) and encodes 2 bits/baud instead of the 1 bit/baud supported by AMI. This new technology was called "repeaterless T1" because it eliminated the necessity of regenerating T1 signals every 6000 feet (1830 meters) using repeaters, a process that made original T1 deployments complex and expensive. Repeaterless T1 needed repeaters only every 12,000 feet (3660 meters) and transmitted data at only 784 Kbps over each twisted pair. Because two pairs of wires are used for T1, this new technology also carries data at T1 speed of 1.544 Mbps. This new technology is now commonly referred to as High bit-rate Digital Subscriber Line (HDSL). A telco will often provision customers with HDSL and call it T1 instead, because it is functionally equivalent in speed and framing to T1.

Implementation

T1 cannot operate over analog Plain Old Telephone Service (POTS) telephone lines. Instead, it must be deployed using specially conditioned copper twisted-pair lines, with two pairs of wires (four wires) being used for a single T1 circuit. To support full-duplex communication, two of these four wires are used for transmission (TX interface) and the other two for receiving (RX interface). T1 lines typically terminate at the customer premises with an RJ-48 connector, which looks like an RJ-45 connector but is pinned differently. T1 lines are generally unshielded twisted-pair (UTP) cabling but other media can be used, including coaxial cabling or fiber-optic cabling.

T1 usually cannot run over existing local loop wiring because:

- Bridge taps installed by telcos to trunk telephone traffic in neighborhood wiring causes distortion of T1 signals, so these must be removed to allow the circuit to carry T1 signals.
- Loading coils, which are used to reduce signal distortion for analog phone lines, have the opposite effect of increasing distortion of digital signals, and these also must be removed.

To deploy T1 as a solution for multiplexing voice traffic, a T1 channel bank is generally installed at the customer premises. This channel bank can be connected to a Private Branch Exchange (PBX), which then connects to digital telephone and fax equipment. For WAN data links the scenario is usually somewhat different, using customer premises equipment (CPE) such as

- A T1 CSU/DSU for connecting bridges or routers to T1 circuits
- T1 bridges and routers with integrated T1 CSU/DSUs
- A T1 multiplexer (MUX), a multiplexer for aggregating several T1 circuits for even higher-speed communication
- T1 access routers, which support multiple remote access links over a single T1 line

To test T1 equipment such as channel banks and CSU/DSUs, use a cable simulator, which is a passive device that simulates a standard 22-gauge twisted-pair T1 line that is 1310 feet (400 meters) long (the alternative is to use 1310 feet of actual 22-gauge twisted-pair wiring). Connect two cable simulators between your CPE and your T1 test equipment using the TX and RX interfaces to analyze your device's performance. A "wet" T1 line carries a small DC current of about 140 mA (milliamperes) at several hundred volts for powering the CSU/DSU at the customer premises. "Dry" lines carry no current, so CSU/DSUs must be powered from the customer premises. Do not touch a T1 line—a wet line can give you a serious shock!

Marketplace

The cost of provisioning T1 is complex and depends on whether you are using it for high-speed Internet access (T1 local loop connections between the customer premises and the telco CO) or for building a high-speed WAN (long-haul T1 lines crossing large geographical distances). A good rule of thumb for T1 WAN links is that the long-haul cost is about $2.50 per mile, which means a 2000-mile T1 leased line would cost about $5,000. These figures were for the year 2000, and the good news is that T1 prices have been falling about 10 percent per year for the last couple of years.

The cost for a T1 local loop connection to provide your company with dedicated high-speed Internet access is generally between $1,000 and $1,500 per month. These prices seem not to be changing much, despite forecasts that Digital Subscriber Line (DSL) technologies will cut into the T1 market, the main reason being the greater reliability of T1 compared to newcomer DSL.

The primary reason T1 lines are so expensive is that they are always "on" regardless of whether they are being used. This is characteristic of leased lines and provides both the benefit of availability and the cost of underutilization. A cheaper solution for many companies that do not require full T1 capacity is to lease a fractional T1 service such as 4 x DS0 = 256 Kbps from their carrier and then have them upgrade it to higher speeds as their WAN traffic grows. Fractional T1 is usually cheaper than using individual DS0 circuits multiplexed together.


① Point-to-point WAN link
LAN
Router with CSU/DSU
T1 circuit
T1 circuit
LAN
Router with CSU/DSU
② Multipoint WAN
Router with CSU/DSU
LAN
LAN
T1
Frame relay network
Router with CSU/DSU
T1
T1
Router with CSU/DSU
LAN
T1
LAN
Router with CSU/DSU
③ Remote access
PSTN
T1 circuit
Access router with CSU/DSU
Modems
Mobile computers
LAN

T1. Some different WAN scenarios using T1 lines.

Notes

T1 and PRI-ISDN both carry data at around 1.5 Mbps, but they are incompatible so far as their framing formats are concerned. For example:

- T1 multiplexes 24 DS-0 channels using TDM for carrying data and adds a control bit to each T1 frame (and may use bit robbing to gain additional bandwidth for control purposes)
- PRI-ISDN multiplexes 23 DS-0 channels for carrying data and adds a 24th DS-0 channel dedicated to carrying control information.

The European E1 specification avoids the bit robbing used in American T1 by adding a 16-bit control header to each E1 frame instead of the single bit added to T1 frames.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), Digital Subscriber Line (DSL), DS-0, DS-1, High-bit-rate Digital Subscriber Line (HDSL), Integrated Services Digital Network (ISDN), leased line, line coding, PRI-ISDN, Private Branch Exchange (PBX), Public Switched Telephone Network (PSTN), T1 channel bank, T3, T-carrier, time-division multiplexing (TDM), trunking*

T1 channel bank

Customer premises equipment (CPE) used to terminate a T1 line and make it available across an organization.

Overview

T1 channel banks are typically used to enable T1 lines to connect to

- Data terminal equipment (DTE) such as routers and access servers
- Private Branch Exchange (PBX) units that provide integrated phone/fax services

A typical T1 channel bank consists of a modular chassis unit to which you can add various expansion cards to provide digital communication services for CPE. The modular chassis allows customers to add channels and upgrade fractional T1 services to full T1 or higher. It also allows customers to multiplex several channels to provide higher bandwidth for high-speed data connections to routers, Web servers, and other DTEs. The chassis typically includes a built-in T1 Channel Service Unit (CSU) for terminating the T1 circuit at the customer premises, plus a number of slots capable of holding expansion cards for various uses.



T1 channel bank. *Using a T1 channel bank to connect a router and PBX to a T1 line.*

Each expansion card in a T1 channel bank typically handles either one or two DS-0 channels, which means that different channels can supply different services (such as voice, fax, or data connections). Typical types of expansion cards include the following:

- **Data service cards:** These usually have a dual channel format that supports two DS-0 channels and employ a serial interface such as RS-232, RS-530, or V.35. These interfaces are then used for directly connecting the unit to bridges and routers having integrated Channel Service Unit/Data Service Units (CSU/DSUs).
- **High-speed data cards:** These support up to 1.544 megabits per second (Mbps) in 64-kilobits per

second (Kbps) or 56-Kbps increments (the speed depends on how DS-0 is provisioned by the carrier) by multiplexing DS-0 channels.

- **Voice cards:** These are used to connect the unit to a PBX or directly to a telephone using standard 4-wire connections.
- **Modem cards:** These convert the channel bank into a modem pool to support corporate remote access needs.

Some T1 channel banks can support as many as four T1 lines, which can be configured for both active and backup purposes to provide redundant wide area network (WAN) connections.

See Also: *Channel Service Unit (CSU), Channel Service Unit/Data Service Unit (CSU/DSU), customer premises equipment (CPE), data terminal equipment (DTE), Private Branch Exchange (PBX), T1, T-carrier*

T3

Part of the T-carrier hierarchy.

Overview

T3 represents the "next step up" for enterprises that want to build their wide area network (WAN) connections using dedicated leased lines. Although the commonly used and relatively inexpensive T1 lines used in enterprises carry traffic at 1.544 megabits per second (Mbps), T3 lines support a much faster speed of 44.736 Mbps, well above standard 10Base2 Ethernet speeds and almost comparable to Fast Ethernet. This huge jump in speed, however, comes at a significant cost and with some associated issues:

- T3 requires fiber-optic cabling to be provisioned from the telco central office (CO) to the customer premises, because T3 cannot run over existing copper local loop wiring even if it is properly conditioned. This up-front cost of laying fiber must be factored into the cost of deploying T3 in the enterprise.
- The cost of a dedicated T3 line is generally between $25,000 and $35,000 per month, a hefty price tag compared to the $1,000 to $1,500 cost of individual T1 lines. Many companies have a difficult time justifying the cost of upgrading from T1 to T3.
- Although T3 operates over fiber-optic cabling, there is no universal specification for how physical layer signaling occurs with this system. As a result, different telcos and telecommunications equipment vendors have developed many proprietary T3 signaling schemes, and most of these schemes cannot interoperate. This means that if you want to deploy T3 you must "buy in" to equipment from a single vendor (or lease equipment from your telco).

Despite these issues, T3 has grown in popularity in the last few years, particularly for large enterprises to connect their data centers to the Internet. The main problem faces companies whose WAN or Internet access needs are too great for a T1 line to satisfy yet do not require the capacity (or cannot afford the cost) of a full T3 line. The emerging solution to this problem is for telcos to provision services that bundle multiple T1 links for greater throughput. Cable and Wireless is one provider that offers a dedicated Internet access service called NxT1 that can aggregate from two to seven T1 lines into a single fat data pipe carrying up to 10 Mbps. This system employs Cisco 7500 routers running Multilink Point-to-Point Protocol (MPPP) for link aggregation. The disadvantage of this scheme is that customers must order additional T1 port connections to the provider's network, which adds to the cost. Nevertheless, the cost of this scheme is generally less than using fractional T3, which requires a full T3 interface at the customer premises.

See Also: *Multilink Point-to-Point Protocol (MPPP), T1, T-carrier*

T.120

A family of standards for multiuser conferencing and collaboration over a data network.

Overview

T.120 represents a series of eight International Telecommunication Union (ITU) standards that define real-time multipoint communication over a network such as the Internet. T.120 can be used for such tasks as video conferencing, data exchange, or interactive gaming. The T.120 standards define such things as

- Multipoint services for conferencing
- Standard network services
- Guidelines for defining data channels
- Whiteboard methodologies
- Application-sharing protocols
- File transfer methodologies

A related standard from the ITU is the H.323 standard for video and audio conferencing.

Architecture

The architecture of the T.120 standard follows that defined by the Open Systems Interconnection (OSI) reference model for networking. The T.120 architecture can be divided into two parts:

- **Network-layer and transport-layer standards (T.122 through T.125):** Allow data to be transmitted and received among conferencing nodes over a variety of supported network connections. These standards also provide platform independence and the capacity for simultaneously managing multiple participants running on different operating system platforms and conferencing software.
- **Application-layer standards (T.126 through T.128):** Support multiuser conferencing functions such as whiteboarding, file transfer, and application sharing across different platforms and networks.

The following table shows the details of the various standards included under the T.120 umbrella.

T.120 Suite of Conferencing Standards

Standard	*Description*
T.121	A required standard for T.120 applications that defines how conference nodes register themselves with a T.120 node controller. Also defines the generic application template (GAT) for building T.120 application protocols and management facilities.
T.122	Defines multipoint communication services (MCS) over various topologies to enable multiple participants to send data as part of a conference. The MCS defined by T.122 are implemented by T.125.
T.123	Defines flow control, error control, and sequencing mechanisms for connect, disconnect, send, and receive functions over different network connections.
T.124	Defines how multipoint conferences are initiated and administered and defines the generic conference control (GCC) that manages and monitors users, address lists, data flow, and MCS resources.
T.125	Defines how data is transmitted during a conference, specifying the private and broadcast channels that transport conference data. T.125 implements the MCS defined by T.122.
T.126	Defines mechanisms for transmitting and receiving whiteboard information among conference nodes and managing the multiuser whiteboard workspace.
T.127	Defines mechanisms for file transfer among conference nodes in either broadcast or directed mode.
T.128	Defines mechanisms for application sharing among conference nodes so that users can share their local programs with others for collaborative purposes.

Notes

T.120 also forms the basis of the Remote Desktop Protocol (RDP), which is used by the Terminal Services of Microsoft Windows 2000, Windows XP, and Windows .NET Server.

See Also: *H.323, International Telecommunication Union (ITU), Open Systems Interconnection (OSI) reference model, Remote Desktop Protocol (RDP), Terminal Services*

TACACS

Stands for Terminal Access Controller Access Control System, a security protocol supported by Cisco routers.

See: *Terminal Access Controller Access Control System (TACACS)*

taking ownership

Assuming the role of an object's creator, thus having the associated rights and privileges that this role incurs.

Overview

Ownership describes the highest level of permissions that can be granted to objects. On the Microsoft Windows 2000, Windows XP, and Windows .NET Server platforms, these objects can include files and folders, Active Directory directory service objects, and so on. For example, assuming ownership of an object such as a file on an NTFS file system (NTFS) volume gives one the right to share the object and assign permissions to it. Normally, the user who creates a file on an NTFS volume is the owner. Other users can take ownership of the file provided the user is either a member of the Administrators domain local group, has NTFS full control permission on the object, or has explicit permission to take ownership of the object.

Notes

Ownership can only be taken; it cannot be assigned.

See Also: *NTFS permissions (Windows 2000, Windows XP, and Windows .NET Server), NTFS permissions (Windows NT), NTFS special permissions (Windows 2000, Windows XP, and Windows .NET Server), NTFS special permissions (Windows NT)*

tape drive

A device used to back up data to magnetic tape.

Overview

Tape drives and their larger cousins, tape libraries, form the backbone of the disaster recovery plan for most enterprises. Tape drives are distinguished from one another by a variety of factors:

- **Recording technology:** There are several different ways in which data can be written to magnetic tape, including linear-scan, helical-scan, or hybrids of these two basic technologies. For more information about these various recording technologies and the tape formats from different vendors that support them, see the following article, "tape format."
- **Capacity:** The capacity of a tape drive is the amount of data it can store on a single tape cartridge. This capacity is usually measured in gigabytes (GB) and can be expressed as either native capacity for uncompressed data or compressed capacity. Tape drives for large enterprise networks may have capacities exceeding 50 GB, but drives for departmental or workgroup use may have capacities of only a few GB. Compressed capacity is usually specified as twice the native capacity—in other words, a tape drive with 50 GB native capacity would be rated as having a compressed capacity of 100 GB. The actual capacity when compression is used, however, depends on the type of data being backed up.
- **Transfer speed:** This is the speed at which data can be buffered by the tape drive and written to tape. For enterprise-class tape drives, transfer speeds exceeding 25 megabytes per second (MBps) are possible, but for workgroup or small business use the capacity is often measured in megabytes per minute (MB/min) instead and is considerably less.
- **Cost of media:** If you are backing up large amounts of data frequently, the cost of individual tape cartridges can be a significant expense that needs to be budgeted for accordingly. Cost for tapes range from about $10 to $100, depending on the tape format used.
- **Input/output (I/O) interface:** Most enterprise tape drives use Small Computer Systems Interface (SCSI) as their data interface, but some cheaper drives for small business use have ATAPI/IDE, parallel, or Universal Serial Bus (USB) interfaces.
- **Interoperability:** Usually a tape cartridge produced by one vendor will not work in a tape drive from a different vendor. The only difference is for tapes and drives that adhere to the new Linear Tape Open (LTO) standard developed by

Hewlett-Packard, IBM, and Seagate Technology. LTO drives and cartridges have only recently appeared on the market, but they are likely to become a dominant format in the years to come.

- **Software driver:** Before buying a tape drive for your servers, make sure that your backup software has a suitable driver for this hardware.

Marketplace

The tape drive market is basically divided into three categories:

- **Enterprise:** These drives have the largest capacities and best performance to meet the demanding backup needs of large companies. Some popular drives in this market include DLT 8000 drives from Quantum Corporation, which cost about $5,000 and have a native capacity of 40 GB; Exabyte Mammoth-2 and Sony AIT-2 drives, which are comparable in cost and capacity to the DLT 8000; and the new SuperDLT drives from Quantum and LTO Ultrium drives from IBM, which have higher capacity and cost.
- **Departmental:** These medium-capacity drives include the Tandberg SLR100, Benchmark DLT1, Ecrix VXA-1, and drives from other vendors. The cost for departmental drives is usually $1,000 or slightly higher, and capacity is measured in tens of GB.
- **Workgroup:** For small business settings, these are a wide range of popular drives, including digital audio tape (DAT) drives from a number of vendors, OnStream's ADR50 drives, and Ultrium 3580 from IBM. Drives for workgroup or desktop use typically have capacities of a few GB and cost several hundred dollars.

Notes

Here are some tips on getting the most from your tape drive:

- Make sure you clean your drive's read/write heads regularly, usually every 10 hours or so. Some newer drives automatically clean themselves as needed, while others display a light-emitting diode (LED) indicator when cleaning needs to be done.
- Avoid exposing both the tape drive and the tapes to stray magnetic fields such as those from computer monitors. When some tape formats are exposed to such fields, data can be lost—for others, the entire tape can be rendered unusable.
- Replace your tapes regularly according to the mean lifetime of the particular tape format you use. Most tapes can be used about 50 times before they wear out and become unreliable.

See Also: *backup, disaster recovery, tape format, tape library*

tape format

Techniques for storing digital data on magnetic tape for backup purposes.

Overview

Magnetic tape is the medium used by most companies for archiving valuable business information. No single standard exists, however, for how information is stored on tape. As a result, different vendors have developed a variety of tape formats for use by small, medium, and large businesses. These formats differ in capacity, format, and ease of use, and you need to weigh these factors when deciding which format is appropriate for your organization's needs.

The two main technologies used for storing data on magnetic tape are as follows:

- **Helical-scan:** This method pulls the magnetic tape out of the cartridge that houses it, tensions the exposed tape using capstans and rollers, and wraps the tape around a rotating drum that contains multiple read/write heads. Data is then written in diagonal stripes across the width of the tape, and the entire tape is filled in one pass. This technology is essentially the same used by common VCRs and was developed in the late 1980s. One problem with this technology is that the high speed of the drum rotation (7000 rpm or higher), coupled with the tensioning of the tape, can stretch the tape over time or even cause it to break, but most modern helical tape technologies are designed to minimize these effects.

- **Linear-scan:** This method leaves the tape in the cartridge while passing the small exposed portion of tape over stationary read/write heads. Data is written on one track until the end of the tape is reached, and then the tape reverses direction and the next track is written. This "serpentine" writing action continues until the entire tape is filled. Many linear tape formats use multiple heads to write several tracks simultaneously for greater throughput. The stationary heads and minimal tape tensioning make this approach more reliable than helical-scan technology, but helical-scan generally provides greater performance and supports higher capacity. Linear-scan is also an older technology than helical-scan and is better established, especially in the enterprise arena.

Marketplace

A number of vendors have developed both linear-scan and helical-scan tape technologies, with the result that numerous linear and several helical tape formats are on the market. The following are some of the popular linear-scan tape formats offered by different vendors:

- **Quarter-inch cartridge (QIC):** This is the oldest linear tape format, developed in the early 1980s by Tandberg Data. QIC cartridges have capacities up to 40 gigabytes (GB) with transfer speeds up to 10 megabytes per second (MBps). QIC cartridges originally had a large 4-by-6-by-$^5/_8$-inch form factor, but this is now considered obsolete and has been largely replaced by smaller minicartridges, especially those from Travan using technology developed by 3M Corporation/Imation Corporation.
- **Digital linear tape (DLT):** This linear tape technology was first developed by Conner in 1991 and acquired by Quantum Corporation in 1994. DLT has been the dominant tape format used in enterprise backup solutions for many years. DLT cartridges generally have a form factor of 5.25 inches and come in various types. For example, the Quantum DLT 8000 tape format is popular in the enterprise environment and has a native capacity of 40 GB per cartridge, supports transfer rates of 6 MBps, and costs about $100 each. The DLT 8000 format achieves its high transfer rate by writing four tracks of data simultaneously across the tape. Other popular DLT formats include DLT 7000 and DLT 4000.
- **Super DLT (S-DLT):** This format was recently developed by Quantum and uses a combination of magnetic-head and laser-guided technologies to improve on the earlier DLT architecture. Super DLT cartridges have a native capacity of 100 GB and support transfer speeds from 10 to 40 MBps.
- **9840:** This linear format uses half-inch tape and was developed by StorageTek for their tape automation market. The 9840 format is widely used in mainframe computing environments and has a native capacity of 20 GB and a transfer rate of 10 MBps.
- **Mammoth-2:** This linear tape format from Exabyte Corporation is a competitor of Quantum's DLT format and has a native capacity of 60 GB and a transfer rate of 12 MBps and costs about the same as comparable DLT tape.
- **SLR100:** This format from Tandberg Data has a native capacity of 50 GB and transfer speed of 5 MBps. SLR100 tapes cost about $100 each and are popular in the departmental backup arena.

The following are some of the popular helical-scan tape formats offered by different vendors:

- **Advanced Intelligent Tape (AIT):** This technology from Sony Corporation was the first helical-scan tape technology developed for tape backup. AIT has become a popular alternative to DLT in the enterprise and comes in several versions. AIT-2, for example, has a native capacity of 50 GB and a transfer speed of 6 MBps and costs about $100 per cartridge. The newer AIT-3 has a native capacity of 100 GB and a transfer speed of 11 MBps.
- **8-millimeter:** This helical tape format has the same width as standard videotape and supports native of 20 GB and higher, with transfer speeds of 3 MBps and higher. Sony and Exabyte are two popular manufacturers of 8-millimeter tapes.

- **Digital data storage (DDS):** Often wrongly called digital audio tape (DAT), this is a helical tape format based on technology originally developed for the professional audio market. DDS comes in several popular versions, including DDS-1 (2 GB native capacity) DDS-2 (4 GB), DDS-3 (12 GB), and DDS-4 (20 GB). Transfer rates range from 1.5 to 2.4 MBps. DAT cartridges use 4-millimeter tape in a 3.5-inch form factor and typically cost about $50 each.

Some other tape formats include

- **Advanced Digital Recording (ADR):** This is a technology originally developed by Phillips and now available from OnStream that combines aspects of both linear-scan (stationary heads) and helical-scan (multiple tracks written simultaneously). For example, the ADR50 format has a native capacity of 25 GB and a transfer rate of 2 MBps and is well-suited to the workgroup arena.
- **VXA:** This new format developed by Ecrix Corporation writes data to tape in packet form instead of the streaming method used by both linear-scan and helical-scan tape formats. It uses a variable tape speed in contrast to the fixed speed of the standard formats. VXA also employs a parity striping format called discrete packet format (DPF) to optimize data integrity. VXA-1 tapes have a capacity of 33 GB and a transfer speed of 3 MBps and cost less than $100.

Prospects

A new development in this field has been the emergence of an open standard for linear-scan tape media called Linear Tape Open (LTO). This standard was developed jointly by Hewlett-Packard, IBM, and Seagate Technology and is intended to bridge the interoperability gap that exists because of each tape vendor developing its own proprietary technology. The aim is that LTO tape from one vendor would work equally well on an LTO tape drive from a different vendor. There are actually two different LTO standards:

- **Accelis:** A fast data-access linear tape technology for small and mid-sized businesses.
- **Ultrium:** A high-capacity tape technology for large enterprises.

The Ultrium tape format has a native capacity of 100 GB and a transfer speed of 15 MBps and is likely to emerge as the main competitor to market leader DLT and its successor, Super DLT.

See Also: *backup, storage, tape drive*

tape library

A tape backup device that can retrieve and load tapes automatically.

Overview

When enterprises have hundreds of gigabytes (GB) to several terabytes of data that need to be regularly backed up, simple tape drives, even enterprise-class ones that have capacities of 100 GB or more, simply cannot do the job efficiently. That is where a tape library comes in. A tape library, also called a tape autoloader, is essentially a box with a robotic arm or other device that can store a number of tapes, select and load them, and unload and store them as needed. Tape libraries range from small boxes that can sit on a desk or be mounted in an equipment rack to large room-sized enclosures containing multiple tape drives and thousands of tapes.

Marketplace

One of the more popular vendors in the tape library market is Exabyte Corporation, whose tapes use a proprietary format called Mammoth (now Mammoth-2 or M2). IBM is another major player with its standards-based linear tape open (LTO) 3584 UltraScalable Tape Library, which can store as much as 240 TB of data. Other popular vendors of tape libraries include ADIC, Grau Data Storage, Spectra Logic Corporation, StorageTek, and several others.

See Also: *backup, disaster recovery, tape format, tape library*

TAPI

Stands for Telephony Application Programming Interface, a set of standard application programming interfaces (APIs) developed by Microsoft Corporation and Intel Corporation for accessing telephony services.

See: *Telephony Application Programming Interface (TAPI)*

T-carrier

A family of telco specifications for digital trunking, also used for high-speed wide area network (WAN) connections.

Overview

The original trunking (long-haul communications) architecture of the Plain Old Telephone System (POTS) was analog in nature. This L-carrier system allowed multiple analog local loop connections to be aggregated into trunk lines using frequency-division multiplexing (FDM). The main advantage of trunking was that it saved carriers the cost of having to deploy multiple long-haul lines between different geographical locations.

L-carrier services, however, suffered from distance limitations due to noise and signal distortion. As a result, Bell Laboratories developed T-carrier technology in the early 1960s to replace long-haul analog trunking lines with digital lines. This improved performance and made digital data services available to companies that needed to connect remote branch offices with mainframe computing centers. The first level of T-carrier, the T1 service, was first commercially deployed in the mid-1980s.

Uses

T-carrier services such as T1 and T3 lines have a variety of uses in the enterprise:

- To connect Private Branch Exchange (PBX) equipment at the customer premises with the telco central office (CO)
- To economically provide enterprises with integrated voice/fax/data services
- For building dedicated, high-speed WANs
- For providing users on corporate networks with reliable high-speed Internet access
- For connecting corporate Web servers to the Internet

Architecture

The T-carrier family of specifications basically outlines two considerations: physical media and signaling. As a physical media specification, various levels of the T-carrier hierarchy run over copper twisted-pair wiring, coaxial cabling, fiber-optic cabling, or wireless microwave transmission. For example, T1 lines employ two twisted pairs (four wires) to ensure efficient signaling (this is in contrast to traditional analog POTS lines, which employ only one pair of wires). By contrast, T3 uses fiber-optic cabling as its transmission medium. The table shows the various combinations allowed for physical media. Note that the exact specifications for T3 to run over fiber have never been standardized—as a result, different telcos have developed their own proprietary optical transmission schemes for T3.

T-Carrier Physical Media Combinations

T-Level	*Media*
T1	copper
T1C	copper
T2	copper/microwave
T3	fiber/microwave
T3C	fiber/microwave
T4	fiber/microwave

As far as signaling is concerned, the T-carrier system is based on the DS-0 signaling standard defined by AT&T for digital voice transmission. A single digitized voice channel (DS-0 or Digital Signal Zero channel) carries binary data at 64 kilobits per second (Kbps) and forms the building block of the T-carrier service hierarchy. For example, the T1 service consists of 24 DS-0 channels multiplexed to provide a total data rate of 1.55 megabits per second (Mbps). Note that no carrier is defined for DS-0 itself—that is, you cannot use a single DS-0 channel for digital data transmission, only multiple DS-0 channels aggregated together.

In T-carrier services, these DS-0 channels are multiplexed using time-division multiplexing (TDM) instead of the FDM scheme used in the older L-carrier services. For more details of the T-carrier multiplexing process, see the article “T1” earlier in this chapter. T-carrier services form a hierarchy of standard digital transmission speeds, as shown in the table below. In real life, however, only T1 and T3 services are implemented; T2 is rarely used and no real standard exists for T4 transmission. For digital transmission speeds faster than T-carrier services offer, a newer technology called Synchronous Optical Network (SONET) was developed. SONET now forms the basis of most long-haul and backbone transmission networks for telcos, with T1 and T3 used mainly for provisioning high-speed data services to the customer premises.

The following table shows the different T-carrier services that have been defined (there are no levels defined beyond T4, as SONET has taken over in this domain). Note that in common parlance T1 and DS-1 mean the same thing, but in fact T1 defines the physical specification and DS-1 defines the signaling method. Note also that T1C and T3C refer to “concatenating” (joining together) two T1 or T3 circuits to double aggregate bandwidth. Despite the number of different T-carrier levels defined, only T1 and T3 are commonly used, and T4 has never been implemented, as SONET covers that range. There is also a variant service called fractional T1 offered by most telcos, which essentially means a full T1 circuit is provisioned to the customer but transmission is limited (and charged) for only a portion of the circuit—for example, 4, 8, or 12 DS-0 channels instead of the full 24 channels.

T-Carrier Levels Currently Defined

T-Level	*DS-Level*	*Number of DS-0 Channels*	*Bandwidth*
T1	DS-1	24	1.544 Mbps
T1C	DS-1C	48	3.152
T2	DS-2	96	6.312
T3	DS-3	672	44.736
T3C	DS-3C	1344	91.053
T4	DS-4	4032	274.176

Implementation

T-carrier is usually provisioned as a leased line service from Incumbent Local Exchange Carriers (ILECs). Costs for these services are high, but their high level of reliability makes them a staple of enterprise telecommunications networks. T-carrier can be provisioned in two basic formats for customers:

- **Channelized:** Individual DS-0 channels can carry their own traffic. Channelized T1, for example, allows a single T1 line to carry 24 separate voice channels multiplexed together, which is cheaper for customers than ordering 24 separate local loop connections. Channelized T1 is often used to connect corporate Private Branch Exchanges (PBXs) to ILECs. A channelized T1 line is essentially a single line that is logically equivalent to 24 separate “virtual” telephone lines.
- **Unchannelized:** The DS-0 channels are essentially merged into a single fat pipe, primarily for carrying data for high-speed WAN links. Note the difference: channelized T1 is used for voice, unchannelized for data.

Often what is referred to as T-carrier is really a different service running over the T-carrier physical interface. For example, a 1.544 Mbps frame relay link is really a frame relay running over two-pair twisted wiring using the T1 physical layer specification.

Notes

In Europe a different digital carrier hierarchy called the E-carrier system evolved. For example, the European equivalent of the T1 line is the E1 line, which carries data at 2.048 Mbps. T-carrier and E-carrier systems are incompatible but can interface with each other by using special multiplexing equipment.

Japan calls its digital hierarchy the J-carrier system, but it is essentially the same as the American T-carrier system.

See Also: *DS-0, DS-1, DS-3, frame relay, Incumbent Local Exchange Carrier (ILEC), Plain Old Telephone Service (POTS), Synchronous Optical Network (SONET), T1, T1 channel bank, T3, telco, time-division multiplexing (TDM), wide area network (WAN)*

TCP

Stands for Transmission Control Protocol, a transport layer protocol of the Transmission Control Protocol/Internet Protocol (TCP/IP) suite.

See: *Transmission Control Protocol (TCP)*

TCP/IP

Stands for Transmission Control Protocol/Internet Protocol, an industry-standard protocol suite forming the basis of the Internet.

See: *Transmission Control Protocol/Internet Protocol (TCP/IP)*

TCP three-way handshake

The procedure used for establishing and terminating Transmission Control Protocol (TCP) sessions.

Overview

All TCP communications are connection-oriented in nature. In other words, a TCP session must be established before the hosts involved can engage in the exchange of data between them. The TCP three-way handshake does this by establishing a logical connection between the hosts to ensure reliable transmission can be achieved.


Initiating host
Target host
① Initial sequence number and other data
② Target sequence number + ACK of initiating host's sequence number
③ ACK of target sequence number

TCP three-way handshake. *How the TCP three-way handshake procedure operates.*

The three stages of a TCP three-way handshake are the following:

1. The initiating host sends a TCP packet requesting a new session. This packet contains the initiating host's sequence number for the connection. The packet includes information such as a set SYN (synchronization) flag and data about the size of the window buffer on the initiating host.
2. The target host sends a TCP packet with its own sequence number and an ACK (acknowledgment) of the initiating host's sequence number.
3. The initiating host sends an ACK containing the target sequence number that it received.

A similar three-way process is used to terminate a TCP session between two hosts. Using the same type of handshake to end the connection ensures that the hosts have completed their transactions and that all data is accounted for.

See Also: *ACK, connection-oriented protocol, Transmission Control Protocol (TCP)*

TDM

Stands for time-division multiplexing, a method for sending several data streams over a single communication path.

See: *time-division multiplexing (TDM)*

TDMA

Stands for Time Division Multiple Access, a cellular communications technology based on time-division multiplexing (TDM).

See: *Time Division Multiple Access (TDMA)*

TDR

Stands for time domain reflectometry, a cable testing technique for finding breaks or shorts in a cable.

See: *time domain reflectometry (TDR)*

TechNet

An information resource program developed by Microsoft Corporation for IT (information technology) professionals who work with Microsoft products.

Overview

Microsoft TechNet is important to those who plan, deploy, maintain, support, and evaluate Microsoft business products, such as Microsoft Windows 2000 and members of the Microsoft BackOffice suite. The TechNet program includes a monthly CD subscription, a Web site, electronic newsletters, regular technical briefings at locations around the world, and special offers. Each month a collection of CDs updates your TechNet binder to ensure that you have the latest and most accurate information on all Microsoft products and services. The subscription includes four categories of CDs:

- Monthly issues of up-to-date technical information, which include the Technical Information, Supplementary Drivers and Patches, and full Microsoft Knowledge Base CDs. The Technical Information CD includes a large collection of manuals, resource kits, and other documentation on current versions of Microsoft products; you can either browse or search this CD to find the information you need. The Knowledge Base CD is a collection of thousands of articles written by Microsoft support professionals that answer technical questions, provide detailed how-to information, resolve bugs, list fixes, and document changes and corrections to Microsoft products.
- The Server Utilities, Client Utilities, and Software Library Archive CDs, as well as CDs that contain utilities from various Microsoft product resource kits.
- Service Pack CDs for all Microsoft products for which service packs are available. These service packs provide cumulative fixes and patches for bugs and known problems with Microsoft products and can include additional enhancements to the original product version.
- Extras, such as CDs for Microsoft Seminars Online and time-limited evaluation versions of Microsoft software.

T

An enhanced version of TechNet, called TechNet Plus, includes beta evaluation software for various upcoming Microsoft products.

For More Information

Visit Microsoft TechNet online at *www.microsoft.com/technet.*

telco

A local telephone company.

Overview

The term *telco* is generally used to refer to the local telephone company that owns the local loop connection between your customer premises and the telco central office (CO). The term is also sometimes used to mean any carrier or service provider that can provision voice or data services over your local loop, regardless of whether they actually own that loop.

In its strictest sense, your telco is your Incumbent Local Exchange Carrier (ILEC), typically one of the four Regional Bell Operating Companies (RBOCs), but sometimes an independent phone company, especially in rural areas. Other companies sometimes referred to as telcos include Competitive Local Exchange Carriers (CLECs), inter-exchange carriers (IXCs), and even metropolitan area network (MAN) service providers such as metropolitan Ethernet providers.

Architecture

From the point of view of business customers, who are usually located in dense urban areas, the most important aspect of a telco is how it implements and provides access to its MAN for provisioning high-speed data services. In a typical scenario, the MAN is a dual high-speed Synchronous Optical Network (SONET) ring running on fiber owned by the telco. OC-48 rings running at 2.5 gigabits per second (Gbps) are still common, but most telcos are upgrading to faster services such as OC-96 or OC-192. Business customers who need the highest performance can usually connect an Ethernet switch or router at their customer premises through a T3 line or trunked T1 lines to an Asynchronous Transfer Mode (ATM) switch residing at the periphery of the telco's network. The ATM switch then connects to the SONET ring to allow customers to establish wide area network (WAN) connections among different branch offices.

See Also: *Asynchronous Transfer Mode (ATM), central office (CO), Competitive Local Exchange Carrier (CLEC), Ethernet switch, Incumbent Local Exchange Carrier (ILEC), inter-exchange carrier*

(IXC), metropolitan Ethernet, optical carrier (OC-x) level, Regional Bell Operating Company (RBOC), router, Synchronous Optical Network (SONET), T1, T3, trunking

Telecommunications Industry Association (TIA)

A national trade organization representing all aspects of the telecommunications industry in the United States.

Overview

Working in conjunction with its subsidiary, the Multi-Media Telecommunications Association (MMTA), and its industry peer organization, the Electronic Industries Alliance (EIA), the Telecommunications Industry Association (TIA) represents its members in activities such as establishing public policies and government regulatory issues, developing standards for communication and networking, and organizing trade shows and other events. The TIA's goal is to provide member companies, which are drawn mostly from service providers and hardware vendors in the communication industry, with a forum for discussing industry issues and a voice for representing members' interests on the national and international level.

Active in telecommunications standards development, the TIA is endorsed and accredited by the American National Standards Institute (ANSI). The Standards and Technology Department consists of five divisions organized in more than 70 groups responsible for formulating new standards. These five divisions are

- Fiber Optics
- User Premises Equipment
- Network Equipment
- Wireless Communications
- Satellite Communications

For More Information

Visit the TIA at *www.tiaonline.org.*

See Also: *American National Standards Institute (ANSI), EIA/TIA wiring standards, Electronic Industries Alliance (EIA), standards organizations*

telecommunications services

Various services provided to customers by telcos.

Overview

In addition to standard voice services, telcos offer a wide variety of data transmission services. These services are provisioned to business customers by connecting switching and multiplexing devices located at the telco central office (CO) to customer premises equipment (CPE) such as access servers, routers, and Ethernet switches. These services may be provisioned over the ubiquitous copper local loop wiring, specially conditioned twisted-pair wiring, fiber-optic cabling, or even wirelessly, using microwave transmission or satellites. Using telco data services companies can deploy

- Dedicated leased lines for permanent, dedicated point-to-point wide area network (WAN) connections
- Packet-switched services such as frame relay and X.25 for building multipoint WANs
- Dial-up remote access solutions for mobile users using either analog modems over the circuit-switched Public Switched Telephone Network (PSTN) or using Integrated Services Digital Network (ISDN) services
- High-speed Internet access for corporate users using digital subscriber line (DSL) technologies such as Asymmetric Digital Subscriber Line (ADSL) and High-bit-rate Digital Subscriber Line (HDSL)

Other data communication technologies that telcos sometimes provide include

- Asynchronous Transfer Mode (ATM)
- digital data service (DDS)
- Switched 56
- Switched Multimegabit Data Services (SMDS)
- T-carrier services such as T1, T3, and fractional T1

See Also: *analog modem, Asynchronous Transfer Mode (ATM), central office (CO), digital data service (DDS), Digital Subscriber Line (DSL), frame relay,* *Integrated Services Digital Network (ISDN), Public Switched Telephone Network (PSTN), Switched 56, Switched Multimegabit Data Services (SMDS), T1, T3, T-carrier, telco, wide area network (WAN), X.25*

telecommuting

Working from a location other than the office, usually from home.

Overview

Telecommuting has emerged as a phenomenon of the late 1990s as a new way of working. A knowledge worker who works from home may be called either a telecommuter or a teleworker. The empowering technology behind telecommuting is the Internet, a ubiquitous public network that provides cheap and easy network connectivity between home workers and the office. The negative side of this new technology is security—the Internet is a notoriously unsafe place with hackers, viruses, Trojan horses, and other threats to both home computers and office networks.

Some of the different ways companies can connect their teleworkers to their corporate networks include

- **Dial-up using 56K modems:** This method is more secure than a bare dedicated connection because a new Internet Protocol (IP) address is typically assigned to the home user for each session initiated with the user’s Internet service provider (ISP). Speed is slow but cost is low also—typically $50 per month, including both an ISP account and a second phone line. Dial-up users should connect to their corporate local area network (LAN) using an encrypted virtual private network (VPN).
- **Digital Subscriber Line (DSL):** This is emerging as the technology of choice for teleworkers due to its high speed (at least 20 times that of dial-up), low cost (typically $50 per month over existing phone lines), and security (DSL is a dedicated point-to-point connection). Nevertheless, teleworkers using DSL need a firewall for full protection, and a VPN is required as well. The main problem with DSL is that it is usually available only in urban areas.
- **Cable modem:** This is usually not recommended for teleworkers due to the security issues concerning having your home computer on a LAN segment with other cable modem subscribers in your neighborhood. A firewall and VPN are definitely needed in this scenario.

Other less common teleworking scenarios include

- **Fixed wireless:** Availability is limited, coverage is usually in dense urban areas, and the service is costly.
- **Satellite:** The main issue here is the latency introduced by the long distances the signal must traverse between the subscriber and the service provider. Initial equipment is expensive and monthly costs are moderate.

See Also: *cable modem, Digital Subscriber Line (DSL), Internet, Internet service provider (ISP), modem, wireless networking*

Telephony Application Programming Interface (TAPI)

A set of standard application programming interfaces (APIs) developed by Microsoft Corporation and Intel Corporation for accessing telephony services.

Overview

Telephony Application Programming Interface (TAPI) receives programmatic telephony requests from applications and then forwards them to drivers for telephony devices such as telephones, modems, Integrated Services Digital Network (ISDN) equipment, and Private Branch Exchanges (PBXs). TAPI manages various telephony functions for these devices including

- Signaling
- Call hold and transfer
- Call conferencing and call parking
- Specialized PBX functions

See Also: *application programming interface (API), modem, Integrated Services Digital Network (ISDN), Private Branch Exchange (PBX)*

Telnet

An Internet standard protocol for executing commands on remote hosts.

Overview

Telnet is an application-layer protocol that is part of the Transmission Control Protocol/Internet Protocol (TCP/IP) suite of protocols. Using Telnet, a user on one IP host can connect to and run text-based commands on a different IP host, provided the user can be authenticated and has suitable privileges. The term *telnet* is also commonly used to refer to software that implements this protocol on a particular platform or system. The Telnet protocol is defined in RFC 854.

Uses

Telnet is widely used for remote administration of routers, Ethernet switches, and UNIX mail and Web servers. For example, you can use Telnet to connect to a Web server on port 80 to issue Hypertext Transfer Protocol (HTTP) commands to troubleshoot the server or to an Internet mail forwarding host on port 25 to issue Simple Mail Transfer Protocol (SMTP) commands to do the same.

Telnet is one of five common methods for remotely administering Cisco routers and access servers, the other four methods being

- Direct serial connection from a local terminal to the RS-232 console port
- Remote serial connection through a modem to the RS-343 auxiliary port
- Remote IP connection using HTTP from a Web browser
- Remote IP connection using Simple Network Management Protocol (SNMP) from an SNMP management console

Implementation

Telnet is a client/server protocol in which a Telnet client on the user's machine issues commands to a Telnet server (for example, a UNIX machine running the telnet daemon or a Microsoft Windows 2000 Server running the Telnet Server service). The Telnet client runs within a command-line window on the client machine; in other words, the user opens a command prompt and types **telnet** to start the Telnet client service. The user specifies the remote host's name or IP address, enters her credentials for authentication, and then issues commands. Any application that can be run from the command line on the remote Telnet server can also be remotely executed from the Telnet client machine. When the program or command is executed, its output (if any) is returned to the client and displayed within the command-prompt window.

Windows 2000 includes both a Telnet client implemented as a command-line utility and Telnet server software that supports as many as 63 simultaneous client connections but is licensed to provide only up to two simultaneous client connections. If you require support for additional client connections, you should obtain the Microsoft Windows Services for UNIX 2 add-on pack for Windows 2000 Server.

See Also: *Hypertext Transfer Protocol (HTTP), router, Simple Mail Transfer Protocol (SMTP), Transmission Control Protocol/Internet Protocol (TCP/IP), UNIX*

terminal

Traditionally, a device that provides user access to a mainframe computer.

Overview

Terminals originated in the mainframe computing environment, where they were used as front-end devices to allow users to access the processing power of these mainframes in an interactive way. Users would type commands and data into a terminal, and the information they typed would be sent over serial links to the mainframe for processing. Once the mainframe had completed the processing, it would return the results to the user's terminal and display it in the appropriate format.

The earliest terminals were called teletypes (abbreviated TTY) and were essentially electric typewriters through which users would send commands and data to a mainframe and the mainframe would then type the output returned to the user. A terminal that supports only text output is sometimes called an ASCII terminal.

Over the years a number of standards called terminal protocols have been developed that govern their use. The VT-100 terminal developed by Digital Equipment Corporation was a popular ASCII text-based terminal standard that is still used in some places, such as library online catalog systems, which remote users typically access by running a Telnet client over a dial-up connection. IBM's TN3270 terminal protocol is still widely used in IBM mainframe environments, and their TN5250 terminal protocol is popular with their AS/400 midrange computing environments. Other common terminal protocol standards include ANSI (American National Standards Institute), VT52, and VT220.

Implementation

Terminals generally have little or no inherent data-processing power and rely entirely on the back-end system to do the processing. The terminal is responsible only for processing and queuing input from the keyboard (and other additional input devices, such as a mouse), transmitting this information in a format recognized by the back-end host (typically a mainframe, midframe, or PC-based terminal server). The information the user enters on the keyboard is typically transmitted to the mainframe over an RS-232 or RS-423 asynchronous serial connection, but sometimes it is transmitted instead over an Ethernet or a Token Ring local area network (LAN) connection. Once the processing is completed, the output is sent back to the terminal and typically presented on a "green screen" monitor, which is usually in ASCII format on older systems, or by providing a graphical desktop environment in newer terminal server computing platforms. In other words, the application runs in one location (the mainframe) and the user interface is in a different location (the terminal).

That the mainframe traditionally does all the processing explains the origin of the term *dumb terminal*, which means that a terminal by itself is generally useless unless it is connected to a back-end processing system. However, there are also "smart" or "intelligent" terminals that have various degrees of inherent processing capability.

Terminals can be either local terminals, which are directly connected to their back-end mainframe host through a dedicated serial or shared/switched LAN connection; or remote terminals, which are typically connected over a telephone line using modems at both ends of the connection.

Prospects

The popularity of terminals declined in the late 1980s and early 1990s with the advent of distributed client/server environments and the eclipse of mainframe computing environments. In a client/server environment, data processing is shared between the front-end client computer, usually a full-featured PC with a graphical user interface (GUI) such as Microsoft Windows, and the back-end server, which can be a Windows NT–based server, a Novell NetWare server, an AS/400, or some other system. In the late 1990s, however, the pendulum started to swing back toward terminals with the rising popularity of terminal emulators and PC-based terminal servers. A terminal emulator is hardware or software, or both, that runs on a stripped-down PC with no operating system and causes the PC to function as a terminal, and a terminal server is a back-end server that generates and delivers the user desktop environment to the terminals and performs all the processing. This arrangement permits low-cost "thin clients" to be used and centralizes system administration at the back end, reducing deployment and management costs associated with a distributed client/server systems environment.

See Also: *RS-232, Telnet, terminal emulator, terminal server, Terminal Services, thin client*

Terminal Access Controller Access Control System (TACACS)

A security protocol supported by Cisco routers.

Overview

Terminal Access Controller Access Control System (TACACS) is a family of security protocols used for Authentication, Authorization, and Accounting (AAA). TACACS is similar to the industry standard Remote Authentication Dial-in User Services (RADIUS) security protocol but is more flexible and powerful. In particular, TACACS separates the AAA components and allows them to be used independently of one another.

For example, a common scenario employed by Internet service providers (ISPs) is to use RADIUS for authentication and TACACS for authorization and accounting.

The original version of TACACS was developed in the 1980s by the Defense Data Network for MILNET, the U.S. military portion of the Internet. A variation of this protocol called Extended TACACS (XTACACS) was developed in 1990 and standardized in RFC 1492. Cisco Systems then developed a third version called TACACS+ that is not compatible with earlier versions and has enhanced security features that make the earlier versions obsolete. The remainder of this article focuses on the Cisco version TACACS+ because it is the one in general use.

TACACS+ supports up to 16 different privilege levels and a variety of authentication methods, including standard logon, shell logon, Point-to-Point Protocol (PPP), Novell Asynchronous Services Interface (NASI), and AppleTalk Remote Access Protocol (ARAP).

Comparison

Although TACACS+ is similar to RADIUS, there are architectural differences in how the two protocols work. For example, RADIUS is a connectionless protocol that runs over User Datagram Protocol (UDP). In RADIUS the authentication and authorization features are integrated, and only passwords are encrypted. RADIUS also supports only Internet Protocol (IP) as a network transport and has no method for controlling access to which commands can be executed on a RADIUS-enabled router.

By contrast, TACACS+ is a connection-oriented protocol that runs over Transmission Control Protocol (TCP), separates the three components of AAA functionality, supports a wide variety of network transports, and uses packet encryption and router access lists for greater security. TACACS+ also includes more than 50 attribute/value pairs and supports secure virtual private networking (VPN). Despite these advantages, RADIUS is still the more widely deployed of the two protocols due to its being a vendor-independent industry standard, and TACACS+ is more commonly used in Cisco-only shops.

Implementation

In a typical ISP scenario using TACACS+, a dial-in user connects through the Public Switched Telephone Network (PSTN) to a Cisco access server (router) located at the ISP. The connection between the dial-in user and the router uses an authentication protocol such as Password Authentication Protocol (PAP), Challenge Handshake Authentication Protocol (CHAP), or Microsoft CHAP (MS-CHAP) for securely transmitting the user's credentials to the router.

During the authentication process, the access server forwards the user's credentials to a Cisco AAA server, which is also located at the ISP. The communication between the access server and the AAA server employs TACACS+ as its security protocol. Once the AAA server has authenticated the user, it informs the access server to allow the client connection attempt to be accepted and the user then accesses the Internet.



Terminal Access Controller Access Control System (TACACS). *How a TACACS+-enabled AAA server is used to authenticate dial-in users by an ISP.*

See Also: *AAA, Challenge Handshake Authentication Protocol (CHAP), Internet Protocol (IP), Internet* *service provider (ISP), Microsoft Challenge Handshake Authentication Protocol (MS-CHAP), Password Authentication Protocol (PAP), Point-to-Point Protocol (PPP), Public Switched Telephone Network (PSTN), Remote Authentication Dial-In User Service (RADIUS), Transmission Control Protocol (TCP), User Datagram Protocol (UDP), virtual private network (VPN)*

terminal emulator

Hardware or software, or both, that enables a PC to operate as a terminal.

Overview

Terminal emulators let you use a standard PC to connect to a back-end mainframe or terminal server. The rising popularity of terminal emulators led to the demise of older terminals with their chattery keyboards and green screens. Terminal emulators are typically software packages that run on standard PCs and may include accompanying interface cards to support different kinds of connections such as serial, Ethernet, or Token Ring.

Terminal emulators are often designed to emulate several terminal modes including American National Standards Institute (ANSI), VT52, VT100, VT220, TN3270, and TN5250. Terminal emulators also offer productivity features not supported by older terminals, such as keyboard remapping, support for using scripts and macros to automate tasks, hot-linking of emulator data with desktop applications such as Microsoft Excel, multiple session windows, and a Web browser interface.

Marketplace

Microsoft HyperTerminal is one popular terminal emulator that supports common terminal emulation modes and is included with 32-bit Microsoft Windows operating systems. Many other vendors offer terminal emulation products, including E-Term32 from DCSi, CRT from Van Dyke Technologies, HotVT from Datamission, and Softerm Modular TE from Softronics.

Notes

When running a terminal emulator, the emulation mode on the clients must match the terminal mode running on the back-end system for communication to work. If you are trying to connect to an unknown mainframe or other back-end system and your emulator cannot automatically detect the terminal mode needed, try using ANSI mode first. If that fails, try VT100 and other popular terminal modes.

See Also: *terminal, TN3270, TN5250*

terminal server

Generally, a server that provides the back-end support needed for terminals to function.

Overview

A terminal server can be a mainframe system, a UNIX host running X Windows, or a PC-based server running software such as the Terminal Services included with Microsoft Windows 2000 Server, Windows XP, and Windows .NET Server. The function of a terminal server is to generate the desktop environment that is presented to the user of the terminal and to perform all the processing of data submitted by the user.

The main advantages of terminal-based computing over a traditional client/server PC network are

- **Lower hardware costs:** “Thin clients” (special devices or stripped-down PCs) can be used instead of full-featured desktop PCs. For example, Terminal Services of Windows 2000 Server can present a 32-bit Windows user environment on older PCs that lack the hardware requirements for running a local copy of the latest versions of Windows operating systems.
- **Lower management costs:** Operating systems and applications are installed and run only on the back-end terminal servers, which simplifies deployment and troubleshooting and makes administration more centralized. For example, Terminal Services for Windows 2000 Server supports running applications such as Microsoft Office from centralized terminal servers instead of installing them on every desktop computer in the enterprise.
- **Multiplatform support:** Allows the same applications and desktop environments to be presented on a variety of client platforms, including Windows-based PCs, Macintosh computers, UNIX workstations, and other devices.

Notes

Single-port terminal servers are sometimes used in mainframe environments to allow users connected to different controllers to communicate over the corporate local area network (LAN) without needing a dedicated point-to-point communication link. In a typical configuration, the controller is connected to a terminal server by an RS-232 serial connection, and the terminal server is linked to the LAN by an Ethernet interface.

Some vendors produce rack-mountable terminal server devices with 8 or 16 RJ-45 ports that can be used to connect asynchronous terminals to an Ethernet local area network (LAN) running Transmission Control Protocol/Internet Protocol (TCP/IP) or some other network protocol. Such devices can be used to provide terminals (or PCs running terminal emulation software) with access to network file servers or dial-up access to the Internet. Windows-based management software allows these devices to be remotely managed from a PC for viewing and configuring port information. Built-in support for Password Authentication Protocol (PAP), Challenge Handshake Authentication Protocol (CHAP), and Remote Authentication Dial-In User Service (RADIUS) are often included to control user access. Users can dial in to the device, be authenticated, and select a desired host on the LAN they want to communicate with.

See Also: *terminal, terminal emulator, thin client*

Terminal Services

A component of Microsoft Windows 2000 Server, Windows XP, and Windows .NET Server that supports terminal-based computing.

Overview

Terminal Services enables users to access the Windows 2000, Windows XP, and Windows .NET Server desktop and run Microsoft Windows applications on remote computers and other terminal devices. Terminal Services enables each of these operating systems to function as a terminal server and provide terminal emulation for a wide range of client computers. By moving all processing to the server, Terminal Services reduces total cost of ownership by

- Simplifying system administration by centralizing the installation and management of all applications on the server and supporting full remote administration from a single desktop
- Extending the life of legacy hardware by enabling client computers with minimal processing power and memory to run standard Windows applications
- Extending the life of legacy operating systems by allowing applications designed for Windows 2000, Windows XP, or Windows .NET Server to run on legacy versions of Windows
- Increasing security by using encrypted sessions between clients and servers, by enabling administrators to fully monitor and control user operations by shadowing client sessions from another client computer, and by enabling administrators to input keyboard and mouse actions during client sessions for remote control purposes


Remote Desktop Protocol over TCP/IP
Display information
Keystroke and mouse information
Windows 2000–based server running Terminal Services
Terminal Services client

Terminal Services. *Underlying architecture of how Windows 2000 Terminal Services works.*

Implementation

Three components are required for Terminal Services to work:

- **Terminal server:** A Windows 2000, Windows XP, or Windows .NET Server running Terminal Services that provides each client computer with its own Windows desktop.
- **Terminal Services client:** A “thin client” application that displays the Windows 2000, Windows XP, or Windows .NET Server desktop and running applications within a window on the client computer. Terminal Services clients are provided for all versions of Windows, including 32-bit clients that can run on computers running Windows .NET Server, Windows XP, Windows 2000, Windows NT 4, Windows NT 3.51, Windows 98, or Windows 95 on either Intel or Alpha platforms, and a 16-bit client for Windows for Workgroups 3.11. Special client software can also be embedded in devices such as Windows-based terminals and handheld PCs.
- **Remote Desktop Protocol (RDP):** A protocol suite based on the T.120 standard from the International Telecommunication Union (ITU), which provides the basis for communication between the client and the terminal server. RDP takes all keystroke and mouse actions performed by the terminal client, transports them to the terminal server for processing, and returns the display output to the terminal client. RDP employs Transmission Control Protocol/Internet Protocol (TCP/IP) as its underlying network transport.

Notes

To use Terminal Services you must install both Terminal Services and Terminal Services Licensing, and you must specify the directory location of the licensing server database. You can install Terminal Services during setup or afterward using Add/Remove Programs in Control Panel (you should typically install Terminal Services on a member server instead of a domain controller because installation on a domain controller can affect the domain controller’s performance as a result of the additional load that Terminal Services places on server processor, memory, and network interface). Once these services are installed, you can configure the terminal server’s security to allow users to remotely run multiuser applications, configure user accounts to allow them to log on to the terminal server, create user profiles and home directories if desired, and install Terminal Services client software on client computers. You can install client software either by downloading it across the network or by creating client installation disks for manual installation.

By installing the Citrix MetaFrame add-on, non-Windows clients such as UNIX, Macintosh, and OS/2 Warp can also access a Windows 2000–, Windows XP–, or Windows .NET–based system running Terminal Services to run Windows 2000, Windows XP, or Windows .NET Server applications.

A good rule of thumb is that a terminal server needs an additional 4 to 8 MB of RAM for each additional client it supports. Also, do not run legacy MS-DOS or 16-bit Windows on the terminal server, because this can significantly reduce the number of concurrent users that the server can support and increase the memory requirements for each connected client.

See Also: *Remote Desktop Protocol (RDP), terminal, terminal server, thin client*

terminator

A device connected to one end of a bus or cable that absorbs signals.

Overview

In a bus-based system, a single wire or series of wire segments connects network components in a chain formation. If the ends of the cable are not terminated, a signal placed on the wire by one component will bounce back and forth between the ends of the cable, hogging the cable and preventing other components from signaling. Terminators eliminate this signal bounce by absorbing the signal after each component has seen it once, allowing other components to place their signals on the cable. By supplying a load equal to the impedance of the cable, the terminator prevents reflections or standing waves from developing on the cable. Terminators also prevent interference caused by signal reflection, which can lead to signal loss. Most communication systems such as networks and computer buses require some form of termination at the ends of the data path, although this is often provided internally by the devices at the ends of the data path.

Types

Terminators can be passive (simple resistors) or active (more complex electronics), depending on the type of bus being terminated. Passive terminators use resistors to provide this impedance matching, while active terminators generally use voltage regulators.

Examples of different types of terminators include the following:

- **Coaxial cabling terminators:** Passive terminators that come in various sizes and use Bayonet-Neill-Concelman (BNC) threading to terminate
    - RG-58 thinnet cabling for 10Base2 Ethernet networks with termination resistance of 50 ohms
    - RG-59 cable television terminators with resistance of 75 ohms
    - RG-62 ARCNET cabling terminators with resistance of 93 ohms
- **Small Computer System Interface (SCSI) terminators:** The ends of a SCSI cable must always be terminated in a chain of SCSI devices. The internal termination is usually supplied by the SCSI adapter card, and the external termination is supplied by the last device in the chain. SCSI terminators can be passive, active, differential, or forced-perfect. Forced-perfect terminators compensate for the differences in impedance along the length of a SCSI bus. Diagnostic terminators analyze and display the condition of the data paths within a SCSI bus and are useful for high-availability uses such as clustering.
- **Free connectors:** Connectors on the hubs at both ends of a series of stackable hubs. These terminators are specific to the type of hub sold by a vendor.



Terminator. *Using an ohmmeter to test if thinnet cabling is properly terminated.*

Notes

You can test the termination of a long 10Base2 network without having to hunt for the ends of the cable. Simply use an ohmmeter and test the resistance between the central conductor and the shield of any BNC T-connectors (after removing the cable from the network card to which it is attached). If the reading is about 25 ohms, the cable is properly terminated; if the reading is about 50 ohms, one of the terminators is loose or missing. If the cable appears to be properly terminated but network problems persist, remove one of the terminators and use the ohmmeter to test the connection to the T-connector that you exposed. If the result is less than 50 ohms, you probably have a short in the cable; if it is more than 56 ohms, there is probably a loose T-connector somewhere on the network.

See Also: *10Base2, coaxial cabling, Small Computer System Interface (SCSI), thinnet*

Terrestrial Trunked Radio (Tetra)

A European standard for digital mobile radio services.

Overview

Terrestrial Trunked Radio (Tetra) is an initiative from the European Telecommunications Standards Institute (ETSI) for a single standardized form of digital mobile communications. Tetra is defined in a memorandum of understanding among equipment vendors, service providers, testing bodies, and regulatory agencies that was laid out in 1994. Tetra consists of two complementary standards:

- A standard Time Division Multiple Access (TDMA) cellular communication system for voice and data communication on 25-kilohertz (kHz) channels
- A Packet Data Optimized (PDO) protocol for packet-switched data-only transmission at 36 kilobits per second (Kbps) on 25-kHz channels

Tetra includes support for security features such as multilevel authentication and encryption, allows voice and data communication to be combined using the same equipment, and supports multiplexing of up to four channels to provide data rates of up to 144 Kbps. Tetra complements the Global System for Mobile Communications (GSM) cellular communication standard: GSM itself can be considered an extension of the Integrated Services Digital Network (ISDN) to the wireless domain, and Tetra is an extension of ISDN Private Branch Exchange (PBX) systems to the same domain. Tetra thus provides additional communication functionality not built into GSM, such as direct mobile-to-mobile communication that bypasses the communication infrastructure, support for broadcast and group call features, fast call setup, and priority call.

Notes

Because of the recent growth of the Internet and wide demand for high-speed wireless mobile data services, a new high-speed wireless mobile packet-switching system called the Digital Advanced Wireless System (DAWS) is currently being developed by the ETSI to supercede the Tetra PDO standard.

For More Information

Visit the Tetra home page at *www.tetramou.com.*

See Also: *cellular communications, Digital Advanced Wireless System (DAWS), Global System for Mobile Communications (GSM), Integrated Services Digital Network (ISDN), Private Branch Exchange (PBX), standards organizations, Time Division Multiple Access (TDMA)*

test equipment

A general name for equipment used to configure, diagnose, and troubleshoot networking and telecommunications systems.

Overview

Test equipment is invaluable to busy network administrators for troubleshooting local area network (LAN) or wide area network (WAN) connections, to system integrators who install networks and communication services at customer premises, and to wiring and cabling installation service people. You can buy test equipment for dedicated, single-use testing purposes, but multifunction test equipment is more cost effective.

Test equipment comes in all shapes and sizes, from rack-mounted equipment for enterprise troubleshooting, to handheld scanners and packet sniffers, to laptops that run special software and use special Personal Computer Memory Card International Association (PCMCIA)–attached probes. Here are some examples:

- **Copper cable testers:** Typically handheld devices that can test installed copper cabling for compliance with Electronic Industries Association/Telecommunications Industry Association (EIA/TIA) standards for cabling system performance. These are usually multifunction devices that support both coaxial cabling and twisted-pair cabling. Two-way testers enable you to test a cable from both ends.
- **Fiber-optic cable testers:** Usually a separate category from coax/twisted-pair cable testers. These devices might support testing of single-mode fiber-optic cabling, multimode fiber-optic cabling, or both, and provide detailed measurements in decibels for optical link budget (OLB) calculations to ensure that a fiber installation will support the intended equipment layout. A typical fiber tester consists of two modules: a light source for injecting signals into the system at 850 or 1300 nanometers (depending on the type of fiber) and a power meter to measure what comes out the other end. Some devices include both functions and can be used to test fiber that is still on the spool.
- **Token Ring testers:** Test for shorts, opens, and grounds on shielded twisted-pair (STP) cabling in Token Ring installations.
- **LAN analyzers (sniffers):** For troubleshooting problems with LAN protocols at all levels of the Open Systems Interconnection (OSI) reference model protocol stack, from lower-level protocols such as Data Link Control (DLC), Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX), NetBIOS Enhanced User Interface (NetBEUI), and Transmission Control Protocol/Internet Protocol (TCP/IP) to higher-level protocols such as File Transfer Protocol (FTP), Hypertext Transfer Protocol (HTTP), NetBIOS, Server Message Block (SMB), and Simple Mail Transfer Protocol (SMTP). These devices basically capture LAN traffic and allow you to analyze and filter packets that use specific protocols, that are transmitted and received from specific computers, that are portions of a specific communication session between two computers, and so on. Microsoft Network Monitor, which is included with Microsoft Systems Management Server (SMS), Microsoft Windows 2000, Windows .NET Server, and Windows NT, is a software-based sniffer that runs on any PC with a network card and can capture and analyze most forms of LAN traffic.
- **SCSI testers:** Test Small Computer Systems Interface (SCSI) buses for shorts, opens, or improper termination. These are usually dedicated to a specific type of SCSI interface.
- **ISDN and T1 test equipment:** Includes continuity testers, channel testers, and line-quality analyzers for testing Integrated Services Digital Network (ISDN) and T-carrier circuits. They can sample frames to check for jitter and lack of synchronization.
- **WAN analyzers:** Test serial transmission protocols such as RS-232 and V.35, which are used to connect WAN devices such as routers and bridges to Channel Service Unit/Data Service Units (CSU/DSUs). They are typically used to troubleshoot frame relay, High-level Data Link Control (HDLC), Point-to-Point Protocol (PPP), Synchronous Data Link Control (SDLC), Serial Line Internet Protocol (SLIP), Systems Network Architecture (SNA), and X.25 connections. You can connect a WAN analyzer to a serial connection by using a Y-shaped connector called a data tap, which lets you monitor communication without interfering with the data being transmitted.

Notes

Cable testers can trace cables through walls, ceilings, and floors by measuring a cable's length and telling you whether the cable is terminated, has an open end, is connected to a port on a hub, and other data. You can plug two-way cable testers into a wall plate and test the patch panel to determine which cable connects to the wall plate.

Use a cable tester on a new enhanced Category 5 (Cat5e) cabling installation before you install and configure your Fast Ethernet network equipment. Good-quality cable testers typically test all four pairs of wires in unshielded twisted-pair (UTP) cabling over frequencies of up to 100 megahertz (MHz) or higher, checking cable integrity for shorts and opens, measuring cable segment lengths using time domain reflectometry (TDR), and allowing measurement of attenuation, near-end crosstalk (NEXT), and PowerSum NEXT to an accuracy of 0.1 decibels or better.

See Also: *cabling, Channel Service Unit/Data Service Unit (CSU/DSU), crosstalk, enhanced Category 5 (Cat5e) cabling, fiber-optic cabling, Integrated Services Digital Network (ISDN), network troubleshooting, Open Systems Interconnection (OSI) reference model, RS-232, shielded twisted-pair (STP) cabling, Small Computer System Interface (SCSI), T-carrier, time domain reflectometry (TDR), Token Ring, unshielded twisted-pair (UTP) cabling, V.35*

Tetra

Stands for Terrestrial Trunked Radio, a European standard for digital mobile radio services.

See: *Terrestrial Trunked Radio (Tetra)*

text file

Another name for an ASCII file, a file that contains unformatted ASCII text.

See: *ASCII file*

TFTP

Stands for Trivial File Transfer Protocol, a simple file transfer protocol for Transmission Control Protocol/Internet Protocol (TCP/IP).

See: *Trivial File Transfer Protocol (TFTP)*

thick coax

Another name for thicknet, the thick coaxial cabling used in Standard Ethernet (10Base5) networks.

See: *thicknet*

thicknet

The thick coaxial cabling used in Standard Ethernet (10Base5) networks.

Overview

Thicknet coaxial cabling is usually 3/8 inch in diameter, is fairly rigid, and has an impedance of 50 ohms. It can carry signals up to 500 meters (1640 feet)—hence the designation 10Base5 for "**10** megabits per second **Base**band transmission over **5** hundred meters." Thicknet was commonly used in the 1980s, mainly for Ethernet cabling, but it has been superceded by unshielded twisted-pair (UTP) cabling and fiber-optic cabling.

To connect a computer to a thicknet cable, you attach a vampire tap to the cable. The tap pierces the cable's insulation layers and makes contact with the signal-carrying copper core. The tap is connected to a transceiver, and a drop cable connects the transceiver to an attachment unit interface (AUI) connector on the computer's network interface card (NIC).

See Also: *10Base5, coaxial cabling, Ethernet, fiber-optic cabling, unshielded twisted-pair (UTP) cabling*

thin client

A client used for terminal-based computing.

Overview

A thin client is a device or stripped-down PC that has only the hardware necessary to support terminal client software. In terminal-based computing, the terminal client sends keystrokes and mouse movements over the network to a terminal server where actual applications reside. The server processes the client input and returns display data to the client, which displays the results for the user. In true terminal-based computing the server does the processing—the client is basically a "dumb" terminal that supports keyboard/mouse input and video output only. The thin clients used in terminal-based computing contrast with traditional "fat clients" in the form of standard PCs, which have greater hardware requirements, consume more network bandwidth, are more complex to manage, and cost more than thin clients.

The main difference between the newer generation of thin clients and the older mainframe-based dumb terminals is that today's thin clients can use an Ethernet network running Internet Protocol (IP) as their underlying network transport, but legacy dumb terminals ran over dedicated serial connections instead. The main advantage of thin clients over traditional fat clients is manageability—applications and user profiles can be securely and centrally managed on terminal servers locked away in back rooms, and practically nothing can go wrong with the machines on users' desktops other than a loose network connection.

History

The first thin client developed for the Microsoft Windows platform was WinFrame from Citrix Systems, a multiuser client/server terminal application developed in 1995 for the Windows NT 3.51 Server platform. To distinguish Citrix WinFrame clients from legacy dumb terminals, the term *Windows-Based Terminal (WBT)* was coined. Microsoft Corporation included its own terminal server platform in an edition of its next version of Windows NT, namely Terminal Server Edition for Windows NT 4 Server. Citrix then developed an enhanced version of its own product called MetaFrame. Citrix and Microsoft continue to be the two market leaders in thin-client computing platforms, with Microsoft including its Terminal Services as part of its Windows 2000, Windows XP, and Windows .NET Server platforms and Citrix MetaFrame supporting the Windows, Macintosh, UNIX, and Linux platforms.

Architecture

Despite the similar approach of the Citrix and Microsoft platforms, there are some underlying architectural differences between them. Most significantly, although Microsoft uses its proprietary Remote Desktop Protocol (RDP) for transporting keyboard, mouse, and video information over the network, Citrix uses its own Independent Computing Architecture (ICA) protocol for this purpose. Both of these protocols can operate over any IP network, including local area network (LAN) and dial-up or dedicated wide area network (WAN) connections. Both platforms also include ActiveX controls that allow the client to be any machine running the Microsoft Internet Explorer Web browser (Citrix also includes a plug-in for the Netscape Navigator browser), enabling Windows-based computing within a Web browser interface.

Marketplace

WBTs for enterprise markets come in a variety of formats, including compact desktop units, handheld devices, and even mobile devices such as wireless Personal Digital Assistants (PDAs). A wide variety of vendors produce WBTs that are compatible with Microsoft's RDP and Citrix's ICA architectures, including Wyse Technology, IBM, and many others. Boundless Technologies offers its Capio II terminal, which runs Windows CE, supports Super Video Graphics Array (SVGA) graphics, and has two universal serial bus (USB) ports and built-in 10/100BaseT Ethernet. Network Computing Devices has a similar entry called ThinSTAR. Wyse, which was the first to market with a WBT product, offers the Winterm 3200LE and many other models.

Web-based WBTs are increasingly popular as well, because they allow thin clients to run within standard Web browsers. Popular products in this category include Nfuse from Citrix, HobLink from Hob Software, and Microsoft's Windows 2000 Terminal Services Advanced Client (TSAC).

Prospects

Although thin clients reduce the management costs associated with managing desktop PCs, thin clients themselves require licensing and hence have only a small impact on software costs. Some vendors are trying to work around these licensing costs by providing innovative forms of terminal-based access to Windows 2000, Windows XP, and Windows .NET Server terminal servers. For example, Tarantella has a terminal server product called Tarantella that runs on UNIX platforms, emulates multiple WBT clients to a Windows 2000 terminal server, and supports both native 32-bit Windows applications and Java-based clients running within Web browsers.

Notes

Although the term *thin client* is usually used nowadays in the context of Windows terminal-based computing, other platforms have at times fallen under the banner of thin client, specifically:

- **Legacy-free PC:** Formerly known as the NetPC, this is a revised initiative from Microsoft and PC manufacturers whose aim is to simplify the PC architecture by removal of legacy features such as the Industry Standard Architecture (ISA) bus and to make systems more secure by removing expansion capabilities. Examples of legacy-free PCs in the marketplace include the Compaq iPaq, the IBM NetVista, and the Hewlett-Packard e-pc. Legacy-free PCs tend to be easier to manage than traditional PCs but cost about the same. Legacy-free PCs are not thin clients, however, because they run applications locally and hence need processor, memory, and storage to accomplish this.
- **Network computer (NC):** The NC architecture was created by IBM, Oracle Corporation, and Sun Microsystems as a terminal-based computing platform using a Java-based thin client. The NC architecture has recently re-emerged and scored some success with its new SunRay platform. The NC is a true “thin client” architecture, but it lags in popularity compared to the Windows-based Citrix and Windows 2000 Terminal Services platforms.

Note that the term *thin server* refers to a rack-mount server having a 1U or 2U format, not a terminal server for a thin client. See the article “rack,” elsewhere in this book, for more information about thin servers.

See Also: *Independent Computing Architecture (ICA), Internet Protocol (IP), rack, Remote Desktop Protocol (RDP), terminal, terminal server, Terminal Services*

thin coax

Also called thinnet, the thin coaxial cabling used for 10Base2 Ethernet networks.

See: *thinnet*

thinnet

The thin coaxial cabling used for 10Base2 Ethernet networks.

Overview

Thinnet cabling is RG-58 coaxial cabling that is 3/16 inch in diameter, is relatively flexible, and has an impedance of 50 ohms. Thinnet uses Bayonet-Neill-Concelman (BNC) connectors to connect cable segments, computers, and concentrators (hubs) together in bus-style networks. Many older hubs, bridges, routers, and other networking devices still have at least one thinnet port for connecting to 10Base2 networks.

Thinnet was often used in the 1980s for workgroup or departmental local area networks (LANs). Thinnet has been superceded by the more popular unshielded twisted-pair (UTP) cabling used in structured wiring deployments for premise cabling. One place where thinnet is still used occasionally, however, is in electrically noisy environments such as shop floors in factories, where electromagnetic interference (EMI) caused by motors, generators, and other heavy equipment can disrupt communication over UTP. Coaxial cabling, with its internal shielding, can easily withstand this kind of noise.

Notes

Thinnet cables must be terminated at both ends. If communication on a thinnet network is down, check the termination points first, then check for loose BNC T-connectors attached to the computers on the network. Note that thinnet cabling can become damaged if it is sharply bent or twisted, so handle it carefully. (It is not nearly as fragile as fiber-optic cabling, however.)

See Also: *10Base2, BNC connector, bus topology, coaxial cabling, electromagnetic interference (EMI), terminator, unshielded twisted-pair (UTP) cabling*

TIA

Stands for Telecommunications Industry Association, a national trade organization representing all aspects of the telecommunications industry in the United States.

See: *Telecommunications Industry Association (TIA)*

Time Division Multiple Access (TDMA)

A cellular communications technology based on time-division multiplexing (TDM).

Overview

Time Division Multiple Access (TDMA) is used to refer to two systems:

- Any digital cellular communications system that employs TDM to enable a single channel to carry multiple conversations simultaneously.
- A specific cellular phone system in the United States that is operated by AT&T and is commonly called North American TDMA. More properly speaking, TDMA is the air interface for AT&T Wireless Services.

The first definition is the engineer's, and the second is the popular one from a consumer's point of view. This article will take the broader view of TDMA as a technology and consider the various popular implementations it has achieved.

History

The original analog cellular phone system developed by Bell Laboratories in the late 1970s and widely deployed in the United States was called Advanced Mobile Phone System (AMPS). This technology was based on Frequency Division Multiple Access (FDMA), which assigned one conversation to each channel. The main problems with this system were that FDMA systems supported only a limited number of concurrent users, and, because the channels were narrowly spaced with respect to each other, interference sometimes occurred. To overcome these problems, TDMA was used as the underlying technology for the first all-digital U.S. cellular communications system, called Digital Advanced Mobile Phone System (D-AMPS). The D-AMPS system operated in the same 800 megahertz (MHz) band of the frequency spectrum as AMPS but was able to handle greater numbers of simultaneous conversations and was more immune to interference between channels. D-AMPS is based on the IS-54 standard and is still used in parts of the United States, but newer Code Division Multiple Access (CDMA) cellular systems have become more widely deployed.

Other TDMA-based cellular systems eventually followed, including

- **Global System for Mobile Communications (GSM):** This is the world's most popular cellular communications system, but although it is prevalent in Europe and parts of Asia, it is still behind CDMA systems in the United States. GSM operates at 900 and 1800 MHz in Europe and at 1900 MHz in the United States.
- **Personal Digital Cellular (PDC):** This is the world's second most popular cellular system and is used exclusively in Japan.
- **Personal Communications Services (PCS):** This is an umbrella term for a variety of cellular communication systems that operate at 1900 MHz in the United States. One of the technologies used by PCS is TDMA.
- **Integrated Digital Enhanced Network (IDEN):** This TDMA-based system was developed by Motorola and is used in some parts of the United States.

Implementation

TDMA works by dividing a radio channel in time to create a series of short slots or time intervals, each a small fraction of a second. Signals from different subscribers are then assigned to specific slots, and the whole series of slots is repeated many times per second. The result is that small delays are introduced into conversations, but this happens so quickly that it cannot be noticed by the unaided ear.

Different TDMA-based cellular systems use different slot and cycle times. For example, North American TDMA (that is, D-AMPS) uses 30 kilohertz (KHz)–wide channels segmented into three time slots each 6.67 microseconds long and capable of carrying 320 bits of data per slot. The whole eight-slot frame repeats itself 50 times per second. By contrast, GSM uses eight slots each 0.577 microseconds long and carrying 156 bits of data, cycled at 217 times per second. The result is that a single D-AMPS channel can carry three simultaneous conversations and a GSM channel can carry eight conversations, and the quality of GSM communications is smoother than D-AMPS.

Prospects

Although TDMA systems based on the IS-54 are considered second generation (2G) cellular communication systems, a newer standard IS-136 has been developed as a 2.5G system capable of higher data transfer rates of 43.2 kilobits per second (Kbps).

See Also: *2G, 2.5G, Advanced Mobile Phone Service (AMPS), cellular communications, Code Division Multiple Access (CDMA), Digital Advanced Mobile Phone Service (D-AMPS), Frequency Division Multiple Access (FDMA), Global System for Mobile Communications (GSM), Personal Communications Services (PCS), time-division multiplexing (TDM)*

time-division multiplexing (TDM)

A method for sending several data streams over a single communication path.

Overview

In time-division multiplexing (TDM), data from different input channels is apportioned into fixed-length segments and then multiplexed in round-robin fashion into a single output data stream, which can then be transmitted over a single channel transmission system and then demultiplexed at the destination location. TDM segments can be created by the multiplexer itself or can be inherent in the input channel signals, such as fixed-length frames. For example, if input streams A, B, and C are divided into segments as shown here

```
A = A1, A2, A3,...
B = B1, B2, B3,...
C = C1, C2, C3,...
```

the time-division multiplexed output stream will look like this:

```
MUX(ABC) = A1, B1, C1, A2, B2, C2, A3, B3,
C3,...
```

One weakness in the TDM approach is that if an input channel does not have anything important to carry for a time, empty segments are inserted into the output stream regardless. For example, if channel A is not transmitting data, one-third of the output channel contains null data and is not being used. You can overcome this weakness by using a more sophisticated multiplexing technique called statistical multiplexing.

Uses

TDM is used in a variety of different networking and telecommunications technologies. In T-carrier transmission, for example, TDM enables a single T1 line to simultaneously carry 24 data channels by interleaving data into portions of a single 193-bit frame. For example, bits 1 through 8 represent channel 1, bits 9 through 16 represent channel 2, and so on to bits 185 through 192 for channel 24, plus one final bit number 193, which is used for link synchronization. This TDM-based framing process occurs 8000 times per second, producing a total throughput for T1 of 1.544 megabits per second (Mbps).

See Also: *multiplexing, statistical multiplexing (STM), T1, T-carrier*

time domain reflectometry (TDR)

A cable testing technique for finding breaks or shorts in a cable.

Overview

A time domain reflectometer is a device that sends a pulse onto a cable and measures the time that it takes for the reflection to return from a short or break in the cable. (This is analogous to the use of sonar to determine ocean depth.) The time interval between transmission and reception of the signal is called the signal delay; this delay can be used to determine the location of the short or break, typically within a few centimeters, even though the break might be hidden within the cable’s jacket and not be visible. You can also use the reflectometer to determine the length of an undamaged cable and identify cables running through walls and false ceilings in a cabling installation.

Most high-quality cable testers can perform time domain reflectometry (TDR) tests in addition to their other functions. Time domain reflectometers are available for testing both copper cabling and fiber-optic cabling.

See Also: *cabling, network troubleshooting*

TLD

Stands for top-level domain, a domain that is directly beneath the root domain in the hierarchical Domain Name System (DNS).

See: *top-level domain (TLD)*

TLS

Stands for Transport Layer Security, a security protocol based on Secure Sockets Layer (SSL).

See: *Transport Layer Security (TLS)*

TN3270

A form of Telnet used for accessing mainframe hosts over an Internet Protocol (IP) network.

Overview

TN3270 was developed as an alternate to the regular Telnet service for accessing mainframe computers. TN3270 provides a better look and feel than standard Telnet, but its numeric field handling and keyboard interface are somewhat clumsy. TN3270 provides keyboard emulation and block-mode service at the client level, thus freeing the mainframe from translation functions. TN3270 supports workstation emulation only and does not include file-transfer or printer-emulation services. TN3270 originally stood for Telnet 3270 but is never referred to this way anymore.

By using Microsoft Host Integration Server, users running a TN3270 client can connect to mainframe computers using the TN3270 service included with Host Integration Server. TN3270 can also be used to connect clients to AS/400 systems, but the AS/400 systems must translate the 3270 data stream into 5250 format and provide keyboard mapping between the 3270 and 5250 key sequences, a process that consumes additional CPU resources on the AS/400.

See Also: *Telnet, TN5250*

TN5250

A form of Telnet used for accessing AS/400 systems over an Internet Protocol (IP) network.

Overview

TN5250 is to the AS/400 computing environment what TN3270 is to the mainframe world. TN5250 offers full 5250 terminal emulation, including hot backup and security features similar to those included with the TN3270 service. TN5250 provides workstation emulation only and does not include file-transfer or printer-emulation services. TN5250 originally stood for Telnet 5250 but is never referred to this way anymore.

A TN5250 service included with Microsoft Host Integration Server lets TN5250 clients connect to AS/400 systems without installing Transmission Control Protocol/Internet Protocol (TCP/IP) on the AS/400. Using Host Integration Server, TN5250 provides workstation emulation that supports almost all the field attributes and keyboard sequences of a “real” SNA 5250 except text assist.

See Also: *Telnet, TN3270*

Token Ring

A local area network (LAN) technology developed by IBM.

Overview

Token Ring was first developed by IBM in 1984 as an alternative to Ethernet. Token Ring originally operated at 4 megabits per second (Mbps). This speed was later extended to 16 Mbps, which enabled Token Ring to compete favorably for a while with the 10 Mbps speed of standard Ethernet. Over the years, the evolution of Token Ring, however, has not matched that of Ethernet. Fast Ethernet brought speeds of 100 Mbps, and an initiative called High-Speed Token Ring (HSTR) was undertaken jointly by Token Ring vendors IBM, Madge Networks, and Olicom to do the same. But in 1998, in the face of emerging Gigabit Ethernet (GbE) standards, IBM abandoned its HSTR efforts, which spelled the death knell for Token Ring and relegated it to the realm of a legacy technology. Despite this occurrence, there is still a large installed base in some shops, but it seems inevitable that they will have to consider migrating to Ethernet technologies in the near future.



Token Ring. *The physical and logical topologies of a Token Ring network.*

Token Ring was standardized in the Institute of Electrical and Electronics Engineers (IEEE) 802.5 specifications, which describe a token-passing ring network configured as a physical star topology using structured wiring implemented with twisted-pair cabling and active hubs.

Implementation

In a Token Ring network, stations (computers) are wired in a star formation to a central wiring concentrating unit called a Multistation Access Unit (MAU). Note that the term *Multistation Access Unit* is sometimes abbreviated as MSAU instead of MAU to distinguish it from *media attachment unit*, a term used in older Ethernet networking technologies.

The MAU unit concentrates wiring in a star topology but internally forms a logical ring topology over which network traffic can travel. Lobes connect the individual stations to the MAU. The maximum cable length for a lobe is 74 feet (22.5 meters) or 328 feet (100 meters), depending on the cable type, but you can extend this distance up to 1.5 miles (2.4 kilometers) using repeaters designed for Token Ring networks. Note that distances between MAUs and attached stations are usually specified as lobe lengths, which refer to round-trip signal paths. Thus, a station with a lobe length of 655 feet (200 meters) actually uses a cable 328 feet (100 meters) long.

MAUs typically support 8 or 16 connections for attaching lobes. You can extend a Token Ring network by connecting the ring-out port of one MAU to the ring-in port of another MAU to form larger rings that can support larger numbers of stations (stackable MAUs simplify this interconnection process). The maximum number of MAUs that can be interconnected in this way is 33. Some MAUs also support interconnection using fiber-optic cabling to create networks that span a building or even a campus. Most MAUs also support in-band management by using Simple Network Management Protocol (SNMP) plus out-of-band management by using a serial interface.

Token Ring networks come in two types, both of which can operate at 4 or 16 Mbps:

- **Type 1 Token Ring:** Generally uses shielded twisted-pair (STP) cabling with a special data connector developed by IBM for Token Ring installations. However, 16-Mbps MAUs generally have ports for RJ-45 or DB9 connectors.

- **Type 3 Token Ring:** This type uses standard unshielded twisted-pair (UTP) cabling with RJ-45 connectors.

Type 1 Token Ring is often considered more reliable than Type 3, but the larger installed base of UTP cabling made Type 3 an attractive option for many Token Ring installations. Type 1 configurations support as many as 260 stations per ring, while Type 3 can support up to 72 stations per ring. Most MAUs and NICs are dual-speed and can run at either 4 or 16 Mbps, but not both. However, you can use bridges or routers to connect 4-Mbps Token Ring networks to 16-Mbps Token Ring networks.

STP cabling for Type 1 Token Ring comes in nine types, only two of which are common now:

- **Type 1 cable:** Uses two-pair 22-gauge shielded, grounded solid copper wire. Use this type for longer cable runs such as those between wiring closets and work areas. The maximum lobe length is 655 feet (200 meters).
- **Type 6 cable:** Uses two-pair 26-gauge stranded, shielded copper wire and is more flexible (and looks nicer!) than Type 1 cable. Use this type for work areas in which cables will be visible or where equipment will be moved frequently and especially for patch cables. The maximum lobe length is 148 feet (45 meters).

Token Ring stations pass a single data packet called a token from one computer to the next rather than let each node transmit independently, as in a contention-based network such as Ethernet. Only one token can be on the network at a time, so collisions do not occur in Token Ring networks as they do in Ethernet networks. This process is analogous to sending messages to a group of people by passing a hat. In order to pass a token in a Token Ring network, each station must know who its neighbors are and must perform a check to make sure that the circuit is unbroken. Messages containing this information are continually sent around the ring. The token circulates so long as this message is received. To generate the required information, the first station online in the ring assumes the role of Active Monitor Station. It creates the token and is responsible for taking action if the token is lost or damaged. The Active Monitor Station sends out an Active Monitor Present frame every seven seconds to the next node down the line. Each node in turn informs its downstream neighbor that it is its Nearest Active Upstream Neighbor. An error-detection process called beaconing occurs if the ring breaks and the token fails to circulate. If the Active Monitor Station fails, another station assumes its role of monitoring the status of the network and generating a new token if the existing one is lost.

If a station wants to transmit data over the network, it waits until the token comes by; if the token has not been claimed by another station, it claims the token and inverts the monitor setting bit to mark it "busy" so that no other station can claim the token for a predefined but variable amount of time. The originating station then removes the last byte from the token (called the delimiter byte), appends data to the token, and appends the delimiter byte to the end to form a frame of variable length (up to 8000 bytes). The token with data circulates around the ring in one direction from station to station. (Each station acts as a repeater to regenerate and forward the token.) When it returns to the originating station, the token and the data are removed and a new token is generated and placed onto the network.

Notes

You can get both types of cable in an adapter cable version (terminated at one end with an IBM data connector and at the other end with a DB9 male connector) or a patch-panel version (terminated at both ends with data connectors). Use patch panel cables to connect MAUs, and use adapter cables to connect stations to MAUs. You can also get baluns, which can convert Type 1 IBM cabling to UTP cabling to connect different Token Ring types, and you can get special adapters that allow data connectors to be connected to RJ-45 ports so that you can use installed UTP cabling with Type 1 MAUs.

Some network interface cards (NICs) for Token Ring networking support software-configurable physical layer addressing, but note that all Token Ring NICs must have unique MAC addresses for communications to work properly on a Token Ring network.

The following table provides suggestions for troubleshooting common Token Ring network problems.

Troubleshooting Tips for Token Ring Networks

Problem	*Suggestion*
Mismatched ring speed	Be sure that all connected stations use 4 Mbps or that all use 16 Mbps. Do not mix stations of different speeds.
Stations cannot receive	Check cables and reset the MAU.
Conflicting MAC addresses	Use NIC configuration software to change the MAC address on one of the conflicting computers.
Traffic congestion on the network	Segment the network by using a bridge or a router.

See Also: *Ethernet, Fast Ethernet, Gigabit Ethernet (GbE), local area network (LAN), MAC address, Multistation Access Unit (MAU or MSAU), network interface card (NIC), shielded twisted-pair (STP) cabling, unshielded twisted-pair (UTP) cabling*

top-level domain (TLD)

A domain that is directly beneath the root domain in the hierarchical Domain Name System (DNS).

Overview

Top-level domains (TLDs) are relatively few in number and are used to identify broad classes of Internet services. The number of TLDs is controlled by the Internet Corporation for Assigned Names and Numbers (ICANN), which keeps this number small to maintain the efficiency of the hierarchical DNS naming system. Name resolution for TLDs is provided by the Internet's 13 root name servers and 10 top-level domain servers.

The various TLDs are listed in the following table. Several additional TLDs, such as .name, .pro, .museum, .aero, and .coop, have been approved by ICANN. The first three TLDs are managed commercially by domain name registrars, and their use varies widely. For example, although .net was originally intended for networking companies only, even some personal home pages use this domain.

Top-Level Domains

Domain	*Description*
.com	Commercial businesses and miscellaneous other uses
.net	Networking and telecommunications companies
.org	Nonprofit organizations
.edu	Four-year degree-granting universities and colleges in North America
.gov	U.S. federal government
.mil	U.S. military use only
.int	Organizations established by international treaty
.biz	Businesses
.info	General purpose

In addition to the domains listed in the table, countries as well as states and provinces within countries are identified by two-letter country codes. For example, .uk is the top-level domain for the United Kingdom, .ca is the top-level domain for Canada, and mb.ca is the top-level domain for the province of Manitoba in Canada. Although the .com domain is by far the most popular one today due to the way it is marketed, many businesses are forced to use other domains such as .net, .biz, or their country domain because of the shortage of commercial top-level domains.

Notes

A special domain called in-addr.arpa is used for reverse DNS name lookups (resolving a host name given the host's Internet Protocol [IP] address).

See Also: *country code, Domain Name System (DNS), in-addr.arpa, Internet, Internet Corporation for Assigned Names and Numbers (ICANN), root name server*

topology

The physical layout of computers, cables, switches, routers, and other components of a network.

Overview

The term *topology* can refer to either a network's physical topology, which is the actual physical layout or pattern of the cabling, or its logical topology, which is the path that signals actually take around the network. This difference is most evident in Token Ring networks, whose cabling is physically arranged in a star but whose signal flows in a ring from one component to the next. The term *topology* without any further description is usually assumed to mean the physical layout. The term comes from topos, the Greek word for "place."

When you design a network, your choice of topology will be determined by the network's size, architecture, cost, and management. Basic network topologies include the following:

- **Bus topology:** The stations are connected in a linear fashion. An example is the 10Base2 form of Ethernet.
- **Star topology:** The stations are connected to a single concentrating device called a hub (Ethernet) or a Multistation Access Unit, or MAU (Token Ring physical topology).
- **Ring topology:** The stations are connected in a ring. Examples are Fiber Distributed Data Interface, or FDDI (logical and physical ring), and Token Ring (logical ring and physical star).
- **Mesh topology:** The stations are connected in a complex, redundant pattern. This topology is generally used only in wide area networks (WANs) in which different networks are connected using routers.

Variations of these basic topologies include the following:

- **Star bus topology:** Consists of many star networks whose concentrators (hubs) are connected in a linear bus fashion
- **Star-wired topology or cascaded-star topology:** Consists of star networks whose hubs are joined in star formation to other hubs, forming a kind of tree-shaped network with the main hub at the top

See Also: *bus topology, mesh topology, ring topology, star topology*

tracert

On Microsoft Windows platforms, a utility used for troubleshooting communication on routed Internet Protocol (IP) networks such as the Internet. The corresponding utility on UNIX platforms is known as traceroute.

Overview

Tracert (or traceroute) is used to "trace the route" across an IP internetwork from a local host to a remote one. Tracert uses Internet Control Message Protocol (ICMP) echo packets similar to the way ping operates. When an attempt is made to use tracert to trace the route to a remote IP host, a series of ICMP echo packets are assigned a steadily increasing Time to Live (TTL) to test network connectivity with routers and IP hosts that are farther away along the route. This continues until either connectivity fails or the target host is finally contacted and successfully responds.

Examples

If you run

```
tracert research.microsoft.com
```

from Winnipeg through your local Internet service provider (ISP), you might get a display similar to the following, depending on the route the packets take at that moment:

```
Tracing route to research.microsoft.com
[131.107.65.14] over a maximum of 30 hops:

  1   100 ms   100 ms   110 ms
wnpgas04.mts.net [205.200.55.1]

  2   100 ms    90 ms   100 ms  205.200.55.6

  3    90 ms   100 ms   110 ms
wnpgbr01-g11-102.mts.net [205.200.28.82]

  4   110 ms   100 ms   100 ms
dis4-winnipeg32-pos11-0.in.bellnexxia.net
[206.108.110.5]

  5   120 ms   100 ms   100 ms
core2-winnipeg32-pos6-2.in.bellnexxia.net
[206.108.102.129]
```

T

```
  6   120 ms   130 ms   120 ms
core2-toronto12-pos10-1.in.bellnexxia.net
[206.108.97.29]

  7   120 ms   130 ms   120 ms
core3-toronto12-pos6-0.in.bellnexxia.net
[64.230.242.201]

  8   180 ms   180 ms   181 ms
core2-vancouver-pos10-2.in.bellnexxia.net
[206.108.101.182]

  9   191 ms   180 ms   190 ms
core2-seattle-pos12-0.in.bellnexxia.net
[206.108.102.209]

 10   180 ms   190 ms   190 ms
bx3-seattle-pos5-0.in.bellnexxia.net
[206.108.102.202]

 11   180 ms   190 ms   190 ms
microsoft-gw.core1-seattle-pos6-2.in.
bellnexxia.net [206.108.108.134]

 12   180 ms   190 ms   190 ms  207.46.190.161

 13   180 ms  1042 ms   180 ms
iuscixtukc1202-ge-5-0.msft.net [207.46.129.48]

 14   191 ms   190 ms   190 ms  207.46.168.122

 15   181 ms   190 ms   190 ms  131.107.33.50

 16  1142 ms   1021 ms   191 ms
iusdinetdc7507-fe-0-1-0.msft.net
[131.107.34.135]

 17   190 ms   181 ms   190 ms  131.107.40.70

 18   190 ms   191 ms   190 ms
research.microsoft.com [131.107.65.14]

Trace complete.
```

Note that the destination host was finally reached after a distance of 18 hops, and note the gradually increasing response times.

See Also: *network troubleshooting, ping*

transaction

A method of coordinating a series of changes to a set of resources distributed over the network.

Overview

Transactions are units of work that must succeed or fail as a whole—a transaction can never partially succeed. If a transaction fails while only partially completed, the transaction is rolled back to the beginning. An example is a credit card purchase: The store requests the purchase amount from the credit card company, the company distributes the funds to the store, and the company bills the purchaser. If any part of the transaction fails, the entire transaction must fail to prevent money from being lost.

Component Services on Microsoft Windows 2000 (or Microsoft Transaction Server on Windows NT), a tool that provides the underlying support, or “plumbing,” for creating scalable, distributed, transactional Web applications, provides failure isolations and mechanisms for recovering failed transactions and can run components of transactions as isolated processes for greater crash protection. Component Services uses the Distributed Component Object Model (DCOM) programming architecture for communication between components on Microsoft Windows networks.

See Also: *Distributed Component Object Model (DCOM)*

transaction log

A technology that provides fault tolerance and crash recovery for critical database files.

Overview

Transaction logs are used in products such as the Microsoft Exchange Server directory services database and information store and Microsoft SQL Server. Using Exchange Server as an example, data is written to transaction log files before it is applied to the directory or information store databases. This improves the performance of write operations to the Exchange databases. In Exchange, you might have several transaction logs in your database directory. When a database is backed up, the transaction logs are then purged.

Transaction logs also play an important role in providing fault tolerance and recoverability for databases. If a system crash corrupts the database files, you can use the transaction logs (if they are intact) to restore all changes to the database since the last backup. Transaction logs make online incremental and differential backups possible. Without transaction logs, you would be able to perform full backups only when backing up databases online.

Transact-SQL

Microsoft Corporation's version of Structured Query Language (SQL) used by Microsoft SQL Server.

Overview

Transact-SQL (sometimes called T-SQL) is a superset of the SQL-92 standard developed by the American National Standards Institute (ANSI) and the International Organization for Standards (ISO). Transact-SQL includes all the features of standard SQL plus several enhancements, including

- Conditional programming constructs such as IF and WHILE
- System stored procedures

Transact-SQL has continued to evolve with each new version of SQL Server released by Microsoft and is a powerful data manipulation language for relational database management systems (RDBMS).

See Also: *American National Standards Institute (ANSI), database, International Organization for Standardization (ISO), SQL Server, Structured Query Language (SQL)*

transceiver

An electronic device for connecting a computer to a baseband transmission network so that the computer can transmit and receive signals on the network.

Overview

In the 1980s transceivers were often separate devices attached to thicknet cabling using vampire taps, but today most network interface cards (NICs) have onboard transceivers built into them. Some Fast Ethernet NICs also have a media independent interface (MII) to which an external transceiver can be connected to provide different kinds of 100-megabits per second (Mbps) networking. This allows greater flexibility in your networking options. For example, 100BaseTX transceivers have an RJ-45 port for connecting unshielded twisted-pair (UTP) cabling, and 100BaseFX transceivers have an SC-type port for connecting fiber-optic cabling.

See Also: *baseband transmission, network interface card (NIC), thicknet*

transceiver cable

Also called a drop cable, a cable connecting a computer's network interface card (NIC) to a transceiver attached to a thicknet cable in Standard Ethernet.

See: *drop cable*

Transmission Control Protocol (TCP)

A transport layer protocol of the Transmission Control Protocol/Internet Protocol (TCP/IP) suite.

Overview

Transmission Control Protocol (TCP) is one of two transport layer protocols used by TCP/IP, the other being User Datagram Protocol (UDP). Although UDP supports only unreliable, connectionless network communications, TCP provides support for reliable, connection-oriented delivery of Internet Protocol (IP) packets. TCP supports only point-to-point communications between two hosts and does not support multipoint communications as UDP does.

Some of the features of TCP communications include

- **Byte stream:** TCP accepts a stream of bytes from application level protocols and apportions it into TCP packets without regard to application-level message boundaries within the stream.
- **Connection-oriented:** Before transferring packets, TCP negotiates a connection between sending and receiving hosts using a process called a TCP Three-Way Handshake. TCP connections are also closed using the same process, and connections are maintained using a keep-alive process to ensure that they do not unnecessarily time out. These procedures

enable TCP to guarantee that transmitted data will be delivered to its targeted destination.

- **Full-duplex:** A TCP connection consists of two logical pipes for transmitting packets in opposite directions.
- **Reliable:** All TCP packets within a particular byte stream (part of a specific communication session) are sequenced to ensure that the byte stream can be properly reconstructed at the destination. Packets that successfully arrive at their destination cause acknowledgements (ACKs) to be generated so the sending host will know that delivery has been successful. Packets that arrive out of order are buffered, and missing packets are retransmitted after a period of time when the sending host determines that no acknowledgements have been received for these packets. Sender-side and receiver-side flow control are implemented to prevent loss of packets when buffers are full and to eliminate subsequent unnecessary retransmissions. In addition, TCP checksums are included to enable the receiving host to verify the bit-level integrity of the transmission.

Notes

Microsoft Corporation's implementation of TCP on its Microsoft Windows 2000, Windows XP, and Windows .NET Server platforms include support for advanced features such as self-tuning to ensure that data is sent at a speed optimal for the receiving host, dead gateway detection to ensure that inoperative gateways do not hinder packet delivery, and checksums for ensuring error-free delivery.

See Also: *ACK, connectionless protocol, connection-oriented protocol, Internet Protocol (IP), Transmission Control Protocol/Internet Protocol (TCP/IP), User Datagram Protocol (UDP)*

Transmission Control Protocol/ Internet Protocol (TCP/IP)

An industry-standard protocol suite forming the basis of the Internet.

Overview

Transmission Control Protocol/Internet Protocol (TCP/IP) was developed in the 1970s and 1980s as a standard protocol for linking hosts and networks into wide area networks (WANs). TCP/IP is an open networking standard that is independent from underlying physical network transport mechanisms. It uses a simple addressing scheme called IP addresses that allow billions of individual hosts to communicate with one another on the Internet. TCP/IP is also a routable protocol that is suitable for connecting dissimilar systems (such as Microsoft Windows and UNIX hosts) in heterogeneous networks and is the most common network transport in use today.

TCP/IP is a constantly evolving protocol suite whose development is steered by such bodies as the Internet Society (ISOC), the Internet Architecture Board (IAB), and the Internet Engineering Task Force (IETF). The various protocols, addressing schemes, and concepts of TCP/IP are defined in a series of documents called Requests for Comments (RFCs) issued by the IETF under an open standards process.

The foundation of the TCP/IP protocol suite is the Internet Protocol (IP), which provides the addressing scheme and supports routing of traffic between networks. The current version of IP is called IPv4 (Internet Protocol version 4) and uses a 32-bit addressing scheme. Due to the explosion of popularity of the Internet in recent years, this addressing scheme is viewed as inadequate to handle the Internet's future growth. As a result, a new version called IPv6 is likely to be widely implemented over the next several years.

Architecture

As shown in the diagram, TCP/IP has a layered architecture consisting of four distinct operational layers. These four layers map loosely to the seven layers of the Open Systems Interconnection (OSI) reference model. The four-layer TCP/IP architecture is sometimes referred to as the DoD Model because TCP/IP was developed in connection with the ARPANET project of the U.S. Department of Defense (DoD). Each layer of the TCP/IP protocol suite has its associated component protocols, the most important of which are listed here:

- **Application layer protocols:** These are responsible for application-level access to TCP/IP networking services. These include Dynamic Host

Configuration Protocol (DHCP), Domain Name System (DNS), Hypertext Transfer Protocol (HTTP), File Transfer Protocol (FTP), Telnet, Simple Mail Transfer Protocol (SMTP), Simple Network Management Protocol (SNMP), and numerous others. In the Microsoft implementation of TCP/IP, application layer protocols interact with transport layer protocols by using either Windows Sockets or NetBIOS over TCP/IP (NetBT).

- **Transport layer protocols:** These establish communication through connection-oriented sessions and connectionless broadcasts. Protocols at this layer include Transmission Control Protocol (TCP) and User Datagram Protocol (UDP).
- **Internet layer protocols:** These are responsible for routing and encapsulation into IP packets. Protocols at this layer include Internet Protocol (IP), Address Resolution Protocol (ARP), Internet Control Message Protocol (ICMP), and Internet Group Management Protocol (IGMP).
- **Network layer protocols:** These place frames on the network. TCP/IP can operate over a wide variety of network transports include the various local area network (LAN) architectures (such as Ethernet and Token Ring) and WAN telecommunication service technologies, including dial-up modem connections over the Public Switched Telephone Network (PSTN), Integrated Services Digital Network (ISDN), and Asynchronous Transfer Mode (ATM) networks.

TCP/IP employs two naming schemes to identify hosts and networks on an internetwork:

- **IP addresses:** These are logical 32-bit (4-byte) numeric addresses usually written in the form *w.x.y.z*. Using an associated subnet mask, IP addresses are split into two portions, a network ID that uniquely identifies the local network on the internetwork and a host ID that uniquely identifies the host on the local network. For example, the IP address 205.116.8.44 is partitioned using the subnet mask 255.255.255.0 into the network ID 25.116.8.0 and the host ID 44. IP addresses are the basic or primary way of identifying hosts and networks on an internetwork; they can either be assigned to hosts manually as static addresses or automatically using DHCP as dynamic addresses.
- **Fully qualified domain names (FQDNs):** These are alphanumeric names generally expressed in the form <host_name>.<domain_name> where <domain_name> identifies the particular network to which the host belongs and <host_name> uniquely identifies the host on the specific network. FQDNs are based on a hierarchical worldwide naming system called the Domain Name System (DNS). As an example, the FQDN server12.microsoft.com represents a host named server12 that belongs to a network whose domain name is microsoft.com. This microsoft.com domain is a second-level domain that belongs to the top-level domain named .com, which itself belongs to the root DNS domain named "." (dot). FQDNs are essentially "friendly" names that are easier to remember than IP addresses. For TCP/IP communications to take place, however, FQDNs must first be resolved into their associated IP addresses by using either a DNS server called a name server or using a hosts file stored on the local machine.



Transmission Control Protocol/Internet Protocol (TCP/IP). *How the four layers of the DoD TCP/IP model map to the seven-layer OSI reference model.*

See Also: *Address Resolution Protocol (ARP), Asynchronous Transfer Mode (ATM), Domain Name System (DNS), Dynamic Host Configuration Protocol (DHCP), Ethernet, File Transfer Protocol (FTP), fully qualified* *domain name (FQDN), hosts file, Hypertext Transfer Protocol (HTTP), Integrated Services Digital Network (ISDN), Internet, Internet Architecture Board (IAB), Internet Control Message Protocol (ICMP), Internet Engineering Task Force (IETF), Internet Group Management Protocol (IGMP), Internet Protocol (IP), Internet Society (ISOC), IP address, NetBIOS over TCP/IP (NetBT), Open Systems Interconnection (OSI) reference model, Public Switched Telephone Network (PSTN), Request for Comments (RFC), Simple Mail Transfer Protocol (SMTP), Simple Network Management Protocol (SNMP), subnet mask, Telnet, Token Ring, Transmission Control Protocol (TCP), User Datagram Protocol (UDP), Windows Sockets*

transport layer

Layer 4 of the Open Systems Interconnection (OSI) reference model.

Overview

The transport layer is responsible for providing reliable transport services to the upper-layer protocols. These services include:

- Flow control to ensure that the transmitting device does not send more data than the receiving device can handle
- Packet sequencing for segmentation of data packets and remote reassembly
- Error handling and acknowledgments to ensure that data is retransmitted when required
- Multiplexing for combining data from several sources for transmission over one data path
- Virtual circuits for establishing sessions between communicating stations

Notes

Transmission Control Protocol (TCP) resides at the equivalent of the OSI transport layer in the Transmission Control Protocol/Internet Protocol (TCP/IP) suite of protocols.

See Also: *Open Systems Interconnection (OSI) reference model, Transmission Control Protocol (TCP), Transmission Control Protocol/Internet Protocol (TCP/IP)*

Transport Layer Security (TLS)

A security protocol based on Secure Sockets Layer (SSL).

Overview

Transport Layer Security (TLS) is based on SSL 3 and is very similar in architecture and operation to that protocol. Netscape Communications originally developed SSL in 1993 to provide secure communications over the Internet for Hypertext Transfer Protocol (HTTP) traffic. SSL included support for public and symmetric key cryptography, two-way encrypted authentication, support for anonymous connections, client/server negotiation of the encryption algorithm to be used, and message integrity using digital certificates.

TLS supports all these features of SSL and provides services for secure authentication, data integrity, and confidentiality. TLS is used to secure HTTP, Simple Mail Transfer Protocol (SMTP), and other forms of Internet traffic.

TLS is defined in RFC 2246. A variant of TLS called EAP-TLS that uses the Extensible Authentication Protocol (EAP) extension to Point-to-Point Protocol (PPP) is defined in RFC 2716.

See Also: *Extensible Authentication Protocol (EAP), Hypertext Transfer Protocol (HTTP), Point-to-Point Protocol (PPP), public key cryptography, Secure Sockets Layer (SSL), Simple Mail Transfer Protocol (SMTP)*

tree

Also called a domain tree, a hierarchical grouping of Microsoft Windows 2000 or Windows .NET Server domains.

See: *domain tree*

Trivial File Transfer Protocol (TFTP)

A simple file transfer protocol for Transmission Control Protocol/Internet Protocol (TCP/IP).

Overview
Trivial File Transfer Protocol (TFTP) is a simple file transfer protocol that differs from the more popular File Transfer Protocol (FTP) mainly in that it does not support any form of authentication. TFTP copies files to and from remote hosts by using the User Datagram Protocol (UDP). The remote host must be running the TFTP service or daemon for the TFTP client to be able to communicate with it. TFTP is defined in RFC 1350.

Uses
One place where TFTP is sometimes used is in UNIX environments where the bootstrap protocol (BOOTP) is used for booting diskless workstations. In this scenario, TFTP is used to download the boot disk image from the BOOTP server to the workstation. Another use for TFTP is in Cisco router networking where TFTP can be used to upload or download router configuration information or even perform a flash install of a new version of Cisco Systems' Internetwork Operating System (IOS).

Notes
The Microsoft Windows 2000 and Windows .NET Server platforms include both a command-line TFTP client and an optional TFTP service called the Trivial File Transfer Protocol Daemon (TFTPD) that is installed when the Remote Installation Services component is enabled.

See Also: *bootstrap protocol (BOOTP), File Transfer Protocol (FTP), Internetwork Operating System (IOS), router, User Datagram Protocol (UDP)*

trunking
Any method for aggregating multiple physical network links into a single logical link.

Overview
Trunking provides a way of overcoming the bandwidth limitations of a single physical network link. Trunking is generally employed in three contexts:

- In switched Ethernet networking, trunking can be used in either switch-switch or switch-server connections to relieve traffic congestion by providing increased bandwidth.
- In remote access and wide area networking, trunking is often used to aggregate multiple wide area network (WAN) links into a single fat pipe.
- In telecommunications, telcos sometimes use trunking to aggregate multiple Digital Subscriber Line (DSL) connections for transmission over T1 lines using Asynchronous Transfer Mode (ATM).

The Institute of Electrical and Electronics Engineers (IEEE) 802.3ad standard ensures interoperability among Fast Ethernet and Gigabit Ethernet (GbE) switches that support trunking.

Implementation
Looking specifically at trunking in switched Ethernet networks, trunking is essentially a form of inverse multiplexing that can be either hardware-based or software-based in its implementation. Trunking was originally developed to reduce congestion in switch-switch connections in switched local area network (LAN) environments. By aggregating several 100-megabit-per-second (Mbps) links between Fast Ethernet switches, for example, you can achieve data rates of 300 or 400 Mbps between the switches to accommodate network backbone traffic. In a full-duplex configuration, this means rates of 600 or 800 Mbps, which rivals the more expensive GbE technology and gives new life to old switches. Not only is it often more economical to trunk Fast Ethernet lines than to upgrade to GbE, but trunked Fast Ethernet cable runs can go farther than GbE cable runs. However, in certain situations trunking does not improve matters. For example, trunking cannot speed up server-to-server backups. GbE switches can be similarly joined for increased backbone capacity in congested enterprise networks. Note, however, that although the theoretical speed for quadruple-trunked full-duplex Fast Ethernet connections is 800 Mbps, in practice the maximum achievable rate is about 560 Mbps because of traffic overhead. Note that switches must be intelligent if they are to support trunked connections properly, so check your switch documentation before you attempt to implement trunking on your network.

Trunking can also be implemented in switch-server connections so that multiple connections to a single server can be aggregated. This form of trunking can be purely software based or can be implemented as a combination of both hardware and software. For example, trunking software installed on multiple network interface cards (NICs) in the server automatically handles load balancing across the various server interfaces and can remove an interface from the trunking group if the interface goes down. This provides increased bandwidth between the server and the switch and ensures fault-tolerant operation. Note that software-based trunking adds an overhead of up to 5 percent to the server's CPU, depending on the software and the NIC used. Look for special NICs from trunking software vendors with on-board processors that can run the trunking software and thus reduce the load on the CPU. Also, do not mix and match trunking software or hardware from different vendors in a single trunking group.



Trunking. *Two forms of trunking used in switched Ethernet networks.*

There are two basic approaches to how trunking can be implemented:

- **Symmetrical trunking:** Allows any port in a trunking group to transmit packets to any other port. Full-duplex connections are thus supported over all links in the group. For example, a server can both transmit and receive data at 400 Mbps in a trunked group of four interfaces and one switch.
- **Asymmetrical trunking:** Allows any port in a trunking group to transmit packets but allows only one port (the port on the switch) to receive packets. The server can transmit data at 400 Mbps but can receive data at only 100 Mbps.

Notes

Trunking by itself is limited to point-to-point connections between two switches or between a switch and a server. However, you can use the Multipoint Link Aggregation (MPLA) technology developed by 3Com Corporation to aggregate physical links connected to different switches into a single logical link. MPLA thus supports multipath trunking between multiple switches and servers, giving network administrators flexibility in configuring their hardware for optimal traffic servicing. Other vendors are working on similar multipath trunking technologies, but standards are still developing in this arena.

See Also: *802.3ad, Digital Subscriber Line (DSL), Ethernet, Ethernet switch, Fast Ethernet, Gigabit Ethernet (GbE), network interface card (NIC), T1*

trust

A secure communication channel between two domains in Microsoft Windows NT, Windows 2000, or Windows .NET Server.

Overview

Trust relationships allow users in one domain to access resources in another domain. Trusts work by having one domain trust the authority of the other domain to authenticate its user accounts.

Windows NT trusts, which are based on Windows NT Challenge/Response Authentication, are managed by the Windows NT Directory Services (NTDS). In Windows NT, trusts are one-way—the trusting domain (or resource domain) trusts the trusted domain (or accounts domain). This means that global users in the trusted domain can be authenticated for accessing resources in the trusting domain. Global users from the trusted domain can log on to any computer in either domain and can access resources in either domain if they have the appropriate permissions. Windows NT trusts are also nontransitive. In other words, if domain A trusts domain B and domain B trusts domain C, it is not true that domain A trusts domain C. If you want to establish a two-way trust between two Windows NT domains, you must create two trusts, one in each direction.

Administrators can set up trust relationships between domains by using the Policies menu in User Manager for Domains. The administrator on the accounts domain should permit the trust first, and then the administrator on the resource domain should complete the trust. Only global accounts (global users and global groups) can cross trusts. By using trusts, you can join Windows NT domains into a variety of domain models, including the complete trust model, the master domain model, and the multiple master domain model. You can join domains to support 100,000 or more users for enterprise-level networks.


Windows NT
Trusting domain
One-way trust
Trusted domain
A
B
C
does not mean
A
C
Windows 2000
Domain
Two-way
transitive trust
Domain
A
B
C
means
A
C

Trust. *How trust relationships work in Windows NT and Windows 2000.*

In Windows 2000 and Windows .NET Server, trusts are managed by Active Directory directory service and are based on the Kerberos v5 security protocol. These trusts are always two-way—in other words, if domain A trusts domain B, users in either domain can access resources in the other domain if they have the appropriate permissions. These trusts are also transitive—in other words, if domain A trusts domain B and domain B trusts domain C, domain A also trusts domain C. Trusts are much easier to manage on these platforms than earlier Windows NT trusts, primarily because there are far fewer trusts to manage. This is because Windows 2000 and Windows .NET Server domains are combined into hierarchical structures called domain trees. All users in a domain tree can access resources in any domain of the tree if they have suitable permissions. In Windows 2000 and Windows .NET Server, you can also use another type of trust called an explicit trust, which is a one-way trust similar to that implemented in Windows NT, to form a trust relationship between two domain forests.

See Also: *Active Directory, domain (DNS), domain tree, Kerberos, two-way transitive trust*

T-SHARE

The original name for Remote Desktop Protocol, a protocol for terminal-based computing.

See: *Remote Desktop Protocol (RDP)*

tunneling

A method for transporting packets of one network protocol over a different network protocol.

Overview

Tunneling is a way of using one network infrastructure (called the transit network) for carrying traffic for a different network. This is done by encapsulating the packets of the sending node in frames of the transit network and adding a suitable header to route the frame across the transit network to the receiving node. When the encapsulated frame arrives at the receiving node, it is de-encapsulated so the node can read it. The two nodes (sending and receiving) are called the tunnel endpoints, and the path over which encapsulated frames are routed across the transit network is called the tunnel. In addition to encapsulating traffic, most tunneling technologies also encrypt traffic for greater security as it travels over the transit network, usually an intermediate public network such as the Internet.

Types

Tunneling is widely used as a wide-area networking (WAN) technology for connecting networks using an intermediate public network such as the Internet. Some common examples of tunneling technologies include the following:

- **IPX over IP:** Here Internetwork Packet Exchange (IPX) packets are encapsulated in Internet Protocol (IP) datagrams to enable them to be routed over an IP internetwork such as the Internet. This process allows legacy NetWare 3.x networks to communicate over IP.
- **SNA over IP:** Here Systems Network Architecture (SNA) traffic is encapsulated in IP using User Datagram Protocol (UDP) headers, a process described in RFC 1795 and also known as Data Link Switching (DLSw).
- **Point-to-Point Tunneling Protocol (PPTP):** This is a Microsoft Corporation protocol for tunneling IP, IPX, and NetBIOS Enhanced User Interface (NetBEUI) traffic over the Internet.
- **Layer-2 Tunneling Protocol (L2TP):** This protocol supports tunneling of IP, IPX, and NetBEUI traffic over any point-to-point datagram delivery service including X.25, frame relay, Asynchronous Transfer Mode (ATM), and IP.
- **IP Security (IPsec):** This protocol has a tunnel mode that allows IP traffic to be encapsulated and encrypted for transmission over a public IP network such as the Internet.

See Also: *Internet, Internet Protocol (IP), Internet Protocol Security (IPsec), Internetwork Packet Exchange (IPX), Layer 2 Tunneling Protocol (L2TP), Point-to-Point Tunneling Protocol (PPTP), Systems Network Architecture (SNA), wide area network (WAN)*

twinax cabling

A form of coaxial cabling with twin central conducting cores.

Overview

Twinax cabling typically uses 20 AWG stranded copper conductors, has an outside diameter of 1/3 inch, and comes with a polyvinyl chloride or plenum jacket. Twinax cabling typically has an impedance of 80 to 100 ohms. Twinax cabling is used primarily for connecting IBM System 3X or AS/400 systems to 5250 terminals.

Notes

To extend a twinax connection over long distances, use a repeater. Twinax repeaters can typically transmit signals up to 1 mile (1.6 kilometers) over unshielded twisted-pair (UTP) cabling and over longer distances using duplex fiber-optic cabling. One repeater is required at both ends of the connection.

Use a multiport repeater (hub) to connect several terminals over a single connection to an AS/400 or System 3X host. You can use twinax-to-RJ-45 baluns to connect the terminals and mainframe host to the hub by using UTP cabling. Some repeaters have RJ-11 ports for extending twinax connections over standard telephone cabling. Twinax cabling is traditionally used in a daisy-chained topology, but if you use a multiport repeater, you can also use a star topology configuration.

See Also: *cabling, coaxial cabling, repeater, unshielded twisted-pair (UTP) cabling*

twisted-pair cabling

Copper wire cabling consisting of multiple wires twisted together.

Overview

In computer networking and telecommunications, twisted-pair cabling may consist of from one to four pairs of color-coded insulated stranded copper wires that are twisted together in pairs and enclosed in a protective outer sheath. The twists in twisted-pair cabling help reduce frequency loss and improve signal transmission by reducing the effects of crosstalk. This is because twisting the wires together makes the cabling more resistant to electromagnetic interference (EMI), which helps maintain a high signal-to-noise ratio for reliable network communication to take place.

The earliest uses for twisted-pair cabling was for the Plain Old Telephone System (POTS), where the cabling was used for local loop wiring and was terminated with RJ-11 connectors. Twisted-pair cabling was developed in both shielded and unshielded configurations, with shielded cabling having better performance but costing more. Twisted-pair cabling is today the cabling medium of choice for building computer networks of all sizes from departmental local area networks (LANs) to structured wiring systems for office towers and campuses. Such twisted-pair cabling used for networking purposes employs RJ-45 connectors instead of the RJ-11 connectors used for telephony applications.

Twisted-pair cabling used in Ethernet networking is usually unshielded twisted-pair (UTP) cabling, but shielded twisted-pair (STP) cabling is typically used in Token Ring networks. UTP cabling comes in different grades for different purposes, the most common of which is Category 5 (Cat5) cabling.

Notes

In a telephone environment, one pair of wires is sufficient for ordinary telephone communication to take place. Most customer premises wiring established by telcos uses two-pair wiring in case a second line is later needed for fax or modem use.

See Also: *Category 5 (Cat5) cabling, crosstalk, electromagnetic interference (EMI), Ethernet, Plain Old Telephone Service (POTS), RJ connectors, shielded twisted-pair (STP) cabling, Token Ring, unshielded twisted-pair (UTP) cabling*

two-way transitive trust

A trust relationship between two domains in Microsoft Windows 2000 and Windows .NET Server.

Overview

By default, all Windows 2000 and Windows .NET Server trusts are two-way, meaning that each domain trusts the authority of the other domain for authentication. A Windows 2000 trust is also transitive—if domain A trusts domain B and domain B trusts domain C, domain A trusts domain C. Windows 2000 two-way transitive trusts are based on the Kerberos v5 security protocol.

Because of the two-way transitive nature of Windows 2000 and Windows .NET Server trusts, all domains in a domain tree implicitly trust one another. This means that resources of one domain are available to users in all other domains in the domain tree if they have suitable permissions.

Notes

You can also create one-way nontransitive trusts for Windows 2000– and Windows .NET Server–based networks. These one-way trusts are similar to the trust relationships formed by Windows NT domain controllers. A one-way trust between a domain and a domain tree provides users of the domain with access only to the domain in the tree to which it is joined. One-way trusts can be useful when domains require a less permanent relationship—for example, when two companies take part in a joint venture. Only the resources needed by the other company are made available to the trusted domain; the entire domain tree is not exposed.

See Also: *Active Directory, domain (DNS), Kerberos, trust*

U

UART

Stands for Universal Asynchronous Receiver/Transmitter, hardware used to translate between serial and parallel transmission.

See: *Universal Asynchronous Receiver/Transmitter (UART)*

UDA

Stands for Universal Data Access, a Microsoft Corporation technology for enabling access to any kind of data source.

See: *Universal Data Access (UDA)*

UDDI

Stands for Universal Description, Discovery, and Integration, a platform-independent framework for businesses to advertise and discover each other.

See: *Universal Description, Discovery, and Integration (UDDI)*

UDF (Uniqueness Database File)

Stands for Uniqueness Database File, a text file used to supplement answer files during unattended installations of Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server.

See: *Uniqueness Database File (UDF)*

UDF (Universal Disk Format)

Stands for Universal Disk Format, the successor to the CD-ROM File System (CDFS).

See: *Universal Disk Format (UDF)*

UDFS

Stands for Universal Disk File System, an older name for Universal Disk Format, the successor to the CD-ROM File System (CDFS).

See: *Universal Disk Format (UDF)*

UDP

Stands for User Datagram Protocol, a transport layer protocol of the Transmission Control Protocol/Internet Protocol (TCP/IP) suite.

See: *User Datagram Protocol (UDP)*

ULS

Stands for User Locator Service, an older name for Internet Locator Service, a Lightweight Directory Access Protocol (LDAP) directory service that enables Microsoft NetMeeting users to locate and contact other users for conferencing and collaboration over the Internet.

See: *Internet Locator Service (ILS)*

UM

Stands for Unified Messaging, technology that allows users to access their e-mail, telephone, and fax messages from a single mailbox.

See: *Unified Messaging (UM)*

UMTS

Stands for Universal Mobile Telecommunications System, another name for Wideband Code Division Multiple Access (W-CDMA), a third-generation (3G) cellular communications system deployed in Europe.

See: *Wideband Code Division Multiple Access (W-CDMA)*

unattended installation

Deploying software without administrative intervention.

Overview

Many Microsoft Corporation products, such as Microsoft Windows 2000, Windows XP, Windows .NET Server, BackOffice products, and .NET Server products, support various forms of automatic deployment methods in which direct involvement of the administrator at the target machine is not required. Unattended installation also enables administrators to perform mass deployments of operating system and application software on networked computers. For example, an administrator can install Windows 2000 Professional on multiple desktop client computers without having to remain at each desktop during the installation process and answer the prompts displayed during a normal CD-based installation.

One way of performing an unattended installation is to make use of a distribution server, a network file server that stores the shared source files for the software you want to install. To perform an installation, the Setup program is started on the target computer, which then automatically connects to the share point on the distribution server, downloads the necessary installation files, and installs the software. With Windows 2000 and Windows XP, for example, unattended installation makes use of a special file called an answer file (Unattend.txt) that provides a fixed set of responses to the prompts for information usually generated by the Setup program, thus freeing the administrator from having to remain at the target machine during installation answering prompts. These prompts include information about the computer name, the network protocol to employ, what optional components to install, and other data. You use the answer file by appending the filename to the /u switch when you run Setup from the command prompt. The answer file is a plaintext file that can be customized using either a simple text editor such as Notepad or using the wizard-based tool Setup Manager provided by Windows 2000 and Windows XP.

Another way of performing unattended installations is to use disk-image duplication (or disk cloning) software such as Symantec Corporation's Ghost or PowerQuest Corporation's DriveImage software. In order to use disk cloning as an installation method, however, the master and target systems must have identical hardware configurations. To create a clone, you install and configure the operating system and applications on the master machine and then use the disk imaging software to capture an exact bit-image of the master machine's hard drive, which you then duplicate to the hard drives on the other computers, producing exact clones of the master machine. When you use disk-image duplication software, you must be careful that incompatibilities do not result. For example, if you clone a computer running Windows 2000, the cloned version will have the same security identifier (SID) as the original, which means that the two computers cannot coexist on the same network. Makers of disk-image duplication software can provide utilities for modifying SIDs to work around this problem. Note also that the master and target computers must be stand-alone member servers and not part of a Windows 2000 domain.

Another tool used for unattended installations included with Windows 2000 Server is Remote Installation Services (RIS), which you can use to install Windows 2000 Professional or Windows XP on client computers from a distribution server share point. An image of the fully configured operating system with any locally installed applications that will be required is created and stored on the network share, and the RIS boot disk is used to boot the client computers, connect to the RIS server, download the image, and install the operating system on the client computers. If the client computers have ROM (read-only memory) that supports Pre-Boot Execution Environment (PXE) architecture and have remote boot–enabled network adapter cards, a remote boot disk is not required for each client.

Finally, if you need to perform mass installations of software on large numbers of networked computers, you might consider using desktop systems management software such as Microsoft Systems Management Server (SMS).

See Also: *answer file, disk imaging, Systems Management Server (SMS)*

Unattend.txt

Filename for an answer file, a text file that can be used to perform an unattended installation of Microsoft Windows 2000, Windows XP, and Windows .NET Server.

See: *answer file*

unbalanced line

An electrical cable in which the potential of the signal-carrying conductor is above ground while the return-path conductor is at ground potential.

Overview

An unbalanced line can be contrasted with a balanced line, in which both conductors carry a signal and have potentials that are equal in magnitude but 180 degrees out of phase. In computer networking, an example of an unbalanced line is coaxial cabling, in which the electrical signal is carried solely by the central conductor while the ground path (the internal wire-braid or mesh shielding inside the cable jacket, which is connected to the earth at one termination point of the cable) provides the unbalanced signal return path.



Unbalanced line. *The return-path conductor of the unbalanced line is at ground potential. The return-path conductor of the balanced line carries a signal.*

In contrast, an example of a balanced line is twisted-pair cabling, which comes in the shielded twisted-pair (STP) and the unshielded twisted-pair (UTP) varieties. Because of its electrical characteristics, unbalanced coaxial cabling is more susceptible to electromagnetic interference (EMI) than balanced STP cabling, but coaxial cabling is capable of higher transmission rates over longer distances.

See Also: *balanced line, coaxial cabling, electromagnetic interference (EMI), shielded twisted-pair (STP) cabling, unshielded twisted-pair (UTP) cabling*

UNC

Stands for Universal Naming Convention, a convention for naming shared network resources.

See: *Universal Naming Convention (UNC)*

unicasting

One-to-one communication between stations on a network.

Overview

Unicasting represents full-duplex, point-to-point communication using directed traffic sent between two hosts on a network. Unicasting is contrasted with broadcasting, which is point-to-multipoint in nature and directs information to all accessible hosts on the network, and multicasting, another form of multipoint communication in which information is directed only to hosts that request it. Most user-initiated network traffic is unicast or directed traffic, but broadcast traffic is mostly for clients and services to announce themselves on the network and multicast traffic is for streaming multimedia communication. In the Transmission Control Protocol/Internet Protocol (TCP/IP) protocol suite, the connection-oriented TCP supports unicasting of IP packets, and the connectionless User Datagram Protocol (UDP) provides broadcasting and multicasting of IP packets.

For a unicast packet to reach its destination host on the network, the packet header must contain the address of the destination host. In TCP/IP networking, this destination address is in the form of a logical address called an IP address. On an IP internetwork, routers (network devices that can forward packets to other networks) are usually configured to forward unicast packets (packets directed to a specific host on a destination network) and broadcast packets (packets directed to all users on a subnet, network, or internetwork).



Unicasting. *Comparison of unicasting, multicasting, and broadcasting.*

See Also: *broadcasting, connectionless protocol, connection-oriented protocol, Internet Protocol (IP), multicasting, point-to-multipoint, point-to-point, routing, Transmission Control Protocol (TCP), Transmission Control Protocol/Internet Protocol (TCP/IP), User Datagram Protocol (UDP)*

Unicode

An international character set standard that is capable of representing characters in all written languages.

Overview

The American National Standards Institute (ANSI) character set, which employs a single byte (8 bits) to represent each character, can represent up to $2^8 = 256$ characters only. This is sufficient for most Western languages, but it is insufficient for languages such as Chinese or Arabic. In contrast, the Unicode character set employs two bytes (16 bits) per character and can thus represent a total of $2^{16} = 65,536$ characters—enough for every language in the world, plus punctuation and standard mathematical symbols.

Unicode is the native character encoding for file and object names in Microsoft Windows 2000, Windows XP, and Windows .NET Server. Filenames are also represented in the NTFS file system (NTFS) using Unicode characters. Before any operations are performed on strings, the Win32 subsystem converts all ANSI strings to Unicode. Many Win32 applications have entry points for both 8-bit ANSI and 16-bit Unicode string functions to ensure backward compatibility for running on older platforms such as Windows 95 and Windows 98.

For More Information

Visit the Unicode Consortium at *www.unicode.org.*

See Also: *ASCII*

Unified Messaging (UM)

Technology that allows users to access their e-mail, telephone, fax, and other forms of messages all from a single mailbox.

Overview

Unified Messaging (UM) has been a Holy Grail pursued by system and application vendors for years and which may finally be becoming a reality. The goal of UM is to make it easier for users to manage the various forms of personal communication they use in today's enterprise. For example, the typical knowledge worker might receive dozens of telephone calls, several faxes, a hundred or so e-mails, and numerous pager alerts and instant messaging (IM) communications in a single day. UM aims to simplify things by allowing users to access all these various forms of communication from a single interface, usually an Inbox of an e-mail program but also a telephone or even a Web browser.

Implementation

There are two basic approaches to implementing UM: unified and integrated. The unified solution stores all of a user's messages, regardless of their format, in a single message repository, usually the message store of a mail server. This approach best benefits companies that have not yet heavily invested in alternate messaging architectures such as voice mail and Private Branch Exchange (PBX) systems or network fax servers. Unified UM is typically implemented using third-party vendor add-on products for popular messaging and collaboration servers such as Microsoft Exchange Server or Lotus Notes. A new approach gaining some popularity is to replace traditional PBXs with PC-based PBXs—standard PCs configured with phone-line cards and specialized software to enable them to provide the functions of a traditional PBX together with advanced UM capabilities. Many of these PC-PBX systems are built on top of an Exchange architecture.

For companies that have already acquired voice mail systems and other legacy messaging systems, a better approach might be integrated UM, which makes use of existing messaging systems and ties them together using UM middleware. Integrated UM generally employs a peer-to-peer architecture that connects and synchronizes together various messaging systems such as e-mail, network fax, and voice mail. Integrated UM keeps each type of message stored in its own kind of repository and leverages the use of existing messaging hardware and software. The negative side is that the integrated UM solution generally requires some software customization to be performed to ensure that these various repositories replicate their message header information to one another to enable users to reliably access any form of message from any message interface, such as telephone, cell phone, or e-mail inbox.

Besides these above two solutions, which involve deploying hardware or software at the customer premises, a third approach to UM is gaining popularity, especially among small and mid-sized businesses. This third solution involves outsourcing UM needs to a third party or service provider. These subscription services are typically offered for a low monthly fee from telcos, cellular communication providers, Internet service providers (ISPs), or even portals such as Yahoo!. The user is typically assigned a telephone number, and others can telephone or send faxes to them using this number. Voice messages received are converted to .wav files and forwarded to the user's e-mail inbox, and faxes are converted to .tif files and similarly forwarded. Users then access their voice, fax, and e-mail messages either using their e-mail client or a standard Web browser.

Marketplace

Customer premises equipment (CPE) for implementing unified UM solutions are available from a number of infrastructure vendors including Avaya, Cisco Systems, Lucent Technologies, Mitel Networks, NEC Corporation, Nortel Networks, Siemens, and several others. In addition, many niche vendors specialize in unified and integrated UM solutions, including Active Voice and Captaris. Examples of some popular in-house UM systems include Unified Messenger from Avaya, OnePoint Messenger from Mitel, InternetPBX from COM2001.com (now Alexis), Telephony e-LinX from Esnatech, VoiXX from Intersis, MESSAGEmanager from System Solutions, and TOPCALL Communication Server ONE from TOPCALL International.

Examples of UM service providers include large carriers such as Bell Canada, Verizon Communications, MCI Worldcom, and many others. A number of companies also offer various forms of free UM services in exchange for advertising, including eFax.com, Hello Direct, JFAX.com, Verso Technologies, OneBox, ThinkLink, and uReach Technologies.

Prospects

The driving force behind the current wave of UM solutions is the proliferation of mobile workers using cell phones. Whether traditional UM infrastructure vendors will thrive in the face of the growing number of companies offering subscription-based UM solutions will be the big question to watch over the next few years.

For More Information

Visit the Unified Communications Consortium at *www.unified-msg.com.*

See Also: *e-mail, Internet service provider (ISP), portal, Private Branch Exchange (PBX), telco*

Uniform Resource Locator (URL)

An addressing scheme for locating resources on the Internet.

Overview

A Uniform Resource Locator (URL) is essentially an "address" of a file stored somewhere on the Internet. URLs enable Internet client software such as Hypertext Transfer Protocol (HTTP) clients (most commonly Web browsers) and File Transfer Protocol (FTP) clients to locate and access resources stored on Web servers, FTP servers, and other kinds of Internet hosts. URLs are to the Internet what absolute paths are to network file systems and what Universal Naming Convention (UNC) paths are to shared file and print resources on a Microsoft Windows network.

Architecture

A URL is a hierarchical, structured address based on the Domain Name System (DNS), although a URL can also use an Internet Protocol (IP) address to locate its targets. A URL adheres to the following standard form:

```
[protocol:]//[domain or IP address][:port]/
[path to target file]
```

The components of this syntax are:

- **Protocol:** This is an optional address element that describes the application layer Internet protocol on the server that must be used in order for the client to access the resource. Examples include HTTP:, FTP:, and Telnet:.
- **Domain name or IP address:** This represents the logical address of the server on which the resource resides and is a required element.
- **Port number:** This is required only if the port on the server to which the client must connect to access the resource differs from the default port for that type of protocol. In other words, if no port number is specified, the request is assumed to use the well-known port number for the protocol being used. For example, the well-known port number for HTTP is port 80.
- **Path:** This is required if the resource is not in the root of the server's directory that is mapped to the specified domain name or IP address. This path is usually a virtual path that is mapped to a hierarchical series of directories on the server or on the server's network.

Examples

The following are a few examples of URLs:

- *http://www.microsoft.com/train_cert/default.asp*
- *ftp://172.16.8.99:3355/usr/bin/frag.Z*
- *http://b12.sales.contoso.com/ Sales%20Department/Wigs/Colors/red.html*

The string *%20* in the third URL is an example of character encoding. Because some ASCII characters (such as spaces) are not allowed in URLs, they must be encoded using the form %*xx*, in which *xx* is the hexadecimal code for the character using the International Organization for Standardization (ISO) Latin-1 character set. The string *%20* represents a space character.

See Also: *absolute path, Domain Name System (DNS), File Transfer Protocol (FTP), Hypertext Transfer Protocol (HTTP), IP address, port number, Universal Naming Convention (UNC), Web browser*

uninterruptible power supply (UPS)

A device that can temporarily provide power to network components.

Overview

Downtime of computer networks and systems are the bane of today's 24x7 e-businesses, so guarding against such a condition is essential to the enterprise network architect. One of the key weapons in an administrator's arsenal is the uninterruptible power supply (UPS), which provides:

- Temporary power against brief power outages to prevent mission-critical data from being lost and against extended power failures to enable servers and other key networking components to be shut down in an orderly manner
- Power conditioning to eliminate harmful surges and brownouts that can corrupt data and damage equipment

The standard UPS is typically a device with rechargeable batteries and software drivers that can perform operations such as:

- Notifying users that a shutdown is imminent and that they should save their work
- Pausing services on servers to prevent new connections from being established
- Providing enough power to perform a soft shutdown of servers and other key network components
- Performing other actions as specified in a batch file that runs automatically
- Providing power line conditioning and smoothing out spikes and dips in the power flow

UPS devices range from small stand-alone boxes to rack-mountable units to room-sized devices having integrated diesel generators for extended power generation. UPS devices are generally rated according to two values:

- **Volt-amp (VA) or kilovolt-amp (kVA) rating:** This determines how much connected computer and networking equipment the UPS is capable of supporting. The larger the VA or kVA value, the greater the number and higher the power requirements of connected devices it can support. UPS devices range from small 1000 VA (1 kVA) units costing $100 or so and designed for Small Office/Home Office (SOHO) computer networks and servers to huge high-end 500-kVA units costing thousands of dollars and designed for mission-critical needs such as those of banks and hospitals. Note that UPS devices can also be rated in watts (W) since 1 VA is equal to 1 W and 1 kVA equals 1 kilowatt (kW), but for some reason general usage is to rate them in VA and kVA instead.
- **Time@100%(min):** This is the amount of time that the unit can sustain maximum power generation. Small and mid-sized UPS devices can typically provide 100 percent power to network components and computers for between 5 and 15 minutes after a power failure. You can use additional battery packs with some UPS devices to extend uptime further.

Marketplace

Some of the larger vendors of UPS devices include American Power Conversion Corporation, Best Power, Clary Corporation, Exide Technologies, Falcon Electric, Liebert Corporation, ONEAC Corporation, OPTI-UPS, Powerware, Toshiba Corporation, Tripp Lite, and Tsi Power Corporation. An example of a high-end UPS is the Silcon DP300E from American Power Conversion, which comes in various models rated up to 1.6 megawatts (MW). Such high-end UPS devices are designed for the largest data centers.

Notes

Always test your UPS after installing it. Otherwise, you might be sorry when a power failure happens in your neighborhood! A good way of testing a UPS is simply to unplug a computer on your system and watch what happens. Some UPS units support Simple Network Management Protocol (SNMP), which lets you test the condition of the UPS at regular intervals and report the results to an SNMP management console.

Note also that the larger the load attached to a UPS unit, the shorter the time interval the unit can continue powering attached devices during a power outage. Be sure that your UPS unit can support your power needs for the time needed to properly shut down your system.

To determine what size UPS you need for your network, add the wattages of all the devices you want to connect and ensure that you buy a UPS unit whose VA rating exceeds this value by a good margin.

See Also: *disaster recovery*

Uniqueness Database File (UDF)

A text file used to supplement answer files during unattended installations of Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server.

Overview

Uniqueness Database Files (UDFs) are used to override the answer to prompts provided by answer files during unattended setup. These UDFs replace the general answers in the answer file with information that is specific to a given computer or small group of computers. UDFs typically supply information customized for individual computers such as computer name or username. By contrast, answer files specify more general setup options such as setup mode or time zone, which are the same for all computers on the network. Thus, although you might need only one answer file to deploy a number of Windows 2000 computers on your network, you would need a separate UDF for each computer to be deployed.

The way it works is that the UDF is merged into the answer file at the start of the graphical user interface (GUI) portion of setup. As a result, you can only use UDFs to define setup parameters for the GUI portion of setup, not the text portion. During the text portion of setup, only the answer file can specify parameters to use in response to setup prompts.

Notes

Windows XP and Windows .NET Server use Setup Manager to prepare unattended installation files for system deployment.

See Also: *answer file, unattended installation*

Universal Asynchronous Receiver/Transmitter (UART)

Hardware used to translate between serial and parallel transmission.

Overview

Universal Asynchronous Receiver/Transmitter (UART) chips are employed in the PC architecture to translate signals between a computer's internal bus and its COM ports. This is because although COM ports use serial transmission, which sends bits one at a time, a computer's internal bus is parallel and carries multiple bits of data simultaneously. Another function of the UART is to add start and stop bits when translating from parallel to serial transmission in order to ensure synchronization between the COM ports and connected remote serial devices and to strip off these bits when translating from serial back to parallel for incoming serial transmission.

UARTs employ their own internal clocking system that runs separately from the computer's internal clock, so the UART must be fast enough to handle data transferred to it from the internal bus or bits may be overwritten and communications may become garbled. Internal modems have their own UART chips because they bypass the computer's COM ports for their transmission.

See Also: *bus, modem, serial transmission*

Universal Data Access (UDA)

A Microsoft technology for enabling access to any kind of data source.

Overview

Universal Data Access (UDA) is part of Microsoft Corporation's Windows Distributed Network Architecture (Windows DNA) framework and enables applications to access data from all kinds of sources, including Structured Query Language (SQL) databases, Lightweight Directory Access Protocol (LDAP) directory services, e-mail repositories, spreadsheets, text files, and mainframe and other legacy data sources. UDA relies on three components to connect applications and data browsers with back-end data sources:

- **Open Database Connectivity (ODBC):** Used primarily to access SQL-compliant relational databases such as Microsoft SQL Server databases, Microsoft Jet databases, and Oracle databases.

- **OLE DB:** Specifies a series of extensible Component Object Model (COM) interfaces for accessing various kinds of data sources, including SQL databases (through ODBC), non-SQL structured data sources, and unstructured data such as text files.
- **ActiveX Data Objects (ADO):** Language-independent framework that enables applications to use OLE DB directly.

See Also: *ActiveX Data Objects (ADO), Component Object Model (COM), Joint Engine Technology (Jet), Lightweight Directory Access Protocol (LDAP), OLE DB, open database connectivity (ODBC), SQL Server, Structured Query Language (SQL), Windows Distributed interNet Applications Architecture (Windows DNA)*

Universal Description, Discovery, and Integration (UDDI)

A platform-independent framework for businesses to advertise and to discover one another.

Overview

Universal Description, Discovery, and Integration (UDDI) is an emerging platform used to simplify the process of companies locating and doing business-to-business (B2B) transactions with one another over the Internet. UDDI provides a standard way for businesses to code what they do and store this information in a directory that is publicly accessible to other businesses. The UDDI project is spearheaded by Ariba, IBM, and Microsoft Corporation and is in beta testing by more than 130 companies who have joined on to the initiative.

UDDI is built on a framework of other open standards, including Extensible Markup Language (XML), Hypertext Transfer Protocol (HTTP), and Simple Object Access Protocol (SOAP).

Implementation

UDDI uses a series of specialized servers called registries. Ariba, IBM, and Microsoft maintain beta versions of these registries, but the intention is to eventually turn UDDI over to an open standards body once testing is completed. UDDI registries store directory information about businesses in a centralized location in three formats:

- **White pages:** General information about businesses such as name, address, and description of business services.
- **Yellow pages:** Businesses organized by categories according to tags defined by government standards.
- **Green pages:** Information on the technical aspect of services which individual business systems expose for data exchange purposes using XML.

For More Information

Find out more about UDDI at *www.uddi.org.*

See Also: *B2B, directory, e-business, Hypertext Transfer Protocol (HTTP), Simple Object Access Protocol (SOAP), XML*

Universal Disk Format (UDF)

The successor to the CD-ROM File System (CDFS).

Overview

CDFS was a file system used in Microsoft Windows NT 4 and earlier versions for accessing information stored on CD-ROM disks. Universal Disk Format (UDF) is the successor to CDFS and is capable of both reading from and writing to removable media such as CD, CD-R, CD-RW, DVD, write-once read-many (WORM), and magneto-optical (MO) media. UDFS is an open industry standard based on the following standards:

- ISO 13346 from the International Organization for Standardization (ISO)
- ECMA 167 from the European Computer Manufacturers Organization (ECMA)
- OSTA UDF from the Optical Storage Technology Association (OSTA)

UDF supports a number of advanced features, including

- Access control lists (ACLs)
- Deep directory trees
- Large file sizes up to 64 gigabytes (GB) in size

- Long file names up to 255 characters long with a maximum path length of 1023 characters
- Named streams
- Sparse files
- Unicode file names

UDF is implemented on the Windows 2000, Windows XP, and Windows .NET Server platforms. Some versions of these platforms require special drivers in order to write to certain media.

See Also: *CD-ROM File System (CDFS), file system*

Universal DSL

Another name for G.Lite, a splitterless version of Asymmetric Digital Subscriber Line (ADSL).

See: *G.Lite*

universal group

A type of group in Microsoft Windows 2000 and Windows .NET Server.

Overview

Universal groups are one of three types of groups in Windows 2000 and Windows .NET Server, the other types being domain local groups and global groups. Universal groups differ from these other types in that they can include members from any domain in the forest and can be granted permissions for resources in any domain in the forest. Universal groups can contain user accounts, global groups, and even other universal groups, but they cannot contain domain local groups. Like global groups, all trusted domains have access to universal groups to grant them permission to access resources on the network.

Some typical uses for universal groups include

- You can use global groups nested inside universal groups to dramatically reduce network traffic due to global catalog replication in a Windows 2000–based network. Use universal groups only when their membership changes infrequently, because excessive replication traffic can occur in a domain tree if their membership changes frequently.
- You can also use universal groups to grant users access to resources that are located in multiple domains. Simply add global groups from each domain to a universal group and assign permissions for the resource to the universal group. This use of universal groups is similar to that of domain local groups, except that you can use domain local groups only to assign permissions for resources in a single domain.

Notes

You can create universal groups only when your Windows 2000 or Windows .NET Server domain is running in native mode, not when it is in mixed mode. In other words, you cannot use universal groups in a network that still has downlevel Microsoft Windows NT domain controllers. You can use them only in a network whose domain controllers are all running Windows 2000 or Windows .NET Server.

See Also: *domain local group, forest, global group, group, mixed mode, native mode*

Universal Mobile Telecommunications System (UMTS)

Another name for Wideband Code Division Multiple Access (W-CDMA), a third-generation (3G) cellular communications system being deployed in Europe.

See: *Wideband Code Division Multiple Access (W-CDMA)*

Universal Naming Convention (UNC)

A convention for naming shared network resources.

Overview

The syntax for a Universal Naming Convention (UNC) path to a network resource is as follows:

```
\\server_name\share_name[\path]
```

where “share_name” is a shared folder, and “path” is the (optional) path to the file within the shared folder.

The UNC path \\max\sales\1998\report.doc indicates that the document report.doc is located within the shared folder called sales on the file server called max. The document is in the 1998 subfolder of the sales shared folder.

See Also: *shared folder*

universal serial bus (USB)

A high-speed serial interface for connecting peripherals to computers.

Overview

Connecting peripherals to computer systems has traditionally suffered from two problems:

- Installing internal peripherals such as Peripheral Component Interconnect (PCI) modem cards involved opening the case, plugging the card into an available slot, screwing the card tight, and closing the case—a time-consuming and complicated process for the average user.
- Transmission speeds supported by standard RS-232 serial and Centronics parallel interfaces have been too slow for some external peripherals such as scanners and digital cameras to operate at an acceptable speed.

Universal serial bus (USB) was created to address these issues by providing a low-cost industry-standard high-speed serial interface for external peripherals and supporting Plug and Play (PnP). Installing a USB peripheral is as simple as connecting it to a USB port on the computer using a standard USB cable. Provided the computer is running an operating system that supports PnP and USB, such as Microsoft Windows 2000 or Windows XP, simply plugging in the peripheral causes it to be automatically recognized and configured for use. Since USB provides “hot plug-able” support, no rebooting of the computer is necessary when connecting or disconnecting USB devices. USB makes it easy to connect peripherals to computers and eliminates the need to configure interrupt request (IRQ) settings or dual inline package (DIP) switches since configuration of devices is automatic. USB ports are included on most computer systems sold today, and USB peripherals are becoming popular, especially in the consumer market where USB-capable monitors, mice, keyboards, joysticks, scanners, digital cameras, printers, and other devices are now proliferating. Besides ease of use, another advantage of USB over legacy serial and parallel port communications is that USB carries up to 500 milliamps (mA) of power to connected peripherals, eliminating the need for bulky power supplies for many types of peripherals.



Universal serial bus (USB). *A typical example of using USB to connect peripherals to a computer system.*

Implementation

USB uses a master/slave architecture in which the computer (master) controls all communications between itself and attached peripherals (slave devices). There are several types of USB peripherals:

- **Input/output (I/O) device:** This is simply any peripheral that supports USB connectivity. Examples include USB keyboards, mice, scanners, and speakers.
- **Hub:** This is a device with multiple USB ports that allows several peripherals to share a single USB

port on the computer. USB hubs can be cascaded in a tiered star topology up to five levels deep to support greater numbers of peripherals.

- **Compound device:** This is a USB peripheral that acts as both an I/O device and a hub. An example is a USB monitor, which allows a keyboard or mouse to be connected through it to the computer.

The USB controller on the host system (a computer having a built-in USB port on the motherboard or an installed USB serial card) manages communication between the host and the connected USB devices using a packet-based token-passing mechanism called transfer queuing. Two kinds of communication take place:

- **Initialization:** The host controller continually polls the network to detect new USB devices and to ensure that connected devices are still attached and functioning.
- **Run time:** USB devices make various kinds of requests to the host controller, which queues the requests and respond to them according to a first-in, first-out (FIFO) manner. Requests made by USB devices include requests for or reports of status information, and requests for reading data to or writing data from another device on the bus. All USB requests are handled by the host controller, which obtains and sends the necessary control information or data to the device.

USB theoretically supports up to 126 peripherals connected together, but in practice it is best to keep the number to about a dozen for best performance and to simplify troubleshooting should incompatibilities arise. USB devices can be no more than 16.4 feet (5 meters) apart or the same distance from a hub or computer. The entire cabling arrangement of a computer and multiple USB peripherals is collectively referred to as the USB bus, even if the actual topology is star-like instead of bus-like in appearance.

USB cables are terminated differently at each end, depending on whether they connect to a computer (upstream connection) or I/O device (downstream connection). This is mainly done to prevent loops in the USB bus. The Type A (flat) connector plugs into the USB port on the computer or into the device ports on the hub, and the Type B (square) connector generally connects to the device.

USB supports two speeds, which depend basically on the type of media used to connect peripherals:

- 1.5-megabits per second (Mbps) transmission over unshielded USB cabling
- 12-Mbps transmission over shielded USB cabling

It is usually possible to combine these two types of media into a single arrangement, because USB hubs and host controllers are generally autosensing and can determine which transmission speed to use depending upon the attached cabling. USB cabling is typically 4-wire cabling and uses a 28-gauge twisted pair for data transmission and a 20-gauge untwisted pair for carrying power to the devices. The table shows the pinning types for USB cabling.

Pinning Types for USB Cabling

Pin	*Color*	*Function*
1	Red	+5 V power
2	White	Data -
3	Green	Data +
4	Black	Ground

Marketplace

For Small Office/Home Office (SOHO) users who want to network two computers, USB offers a simple way of doing this using USB direct cable networking. In this scenario, a USB port on one computer is connected directly to a USB port on another to provide Ethernet-like networking capability. Alternatively, more than two computers can be networked using a USB hub. Several companies offer the special USB cabling and software needed to implement USB direct cable networking, including ActionLink from ActionTec Electronics, EZLink USB from Anchor Chips, and USB Direct Connect from Belkin Components.

Prospects

USB is rapidly replacing serial and parallel interfaces as the most popular way of connecting peripherals to computer systems. A new specification called USB 2, or “high-speed USB,” has been developed that is 40 times faster than USB 1.1, and USB 2–capable systems and software started becoming available toward the end of 2001 with support included in hardware from Intel Corporation, systems from Dell Computer Corporation, and in the Microsoft Windows XP operating system platform.

Notes

When you use shielded USB cabling, connect the shield to ground only at the USB host (computer), not at the USB devices (peripherals).

You can connect an Institute of Electrical and Electronics Engineers (IEEE) 1284–compliant printer that has a standard Centronics interface to a USB system by using a Centronics/USB adapter or patch cable.

See Also: *IEEE 1284, IEEE 1394, parallel transmission, Plug and Play (PnP), RS-232, serial transmission*

Universal Wireless Communications (UWC-136)

A standard for third-generation (3G) wireless cellular systems.

Overview

Universal Wireless Communications (UWC-136) is a standard developed by the Universal Wireless Communication Consortium (UWCC), a consortium of more than 85 telecommunications carriers and wireless product vendors.UWC-136 is part of the International Mobile Telecommunications-2000 (IMT-2000) initiative from the International Telecommunication Union (ITU), which promotes UWC-136 as a competing IMT-2000 standard.

UWC-136 is a pure Time Division Multiple Access (TDMA) cellular communication technology that is designed to be backward compatible with the existing IS-136 TDMA digital cellular phone system defined by the ANSI-136 and IS-41 standards and still widely used throughout North America. Implementation of UWC-136 is planned in phases by first upgrading existing IS-136 TDMA systems to IS-136+ to provide data rates of 43.2 kilobits per second (Kbps) over standard 30-kilohertz (kHz) channels. Then IS-136+ will be upgraded to IS-136HS, which is the high-speed component of UWC-136. Eventually, UWC-136 will provide packet-data services at speeds of up to 384 Kbps for wide-area coverage and up to 2 megabits per second (Mbps) for in-building coverage. Voice communication on this system will be high-fidelity wireline quality, comparable to that of Integrated Services Digital Network (ISDN).

For More Information

Visit the UWCC at *www.uwcc.org.*

See Also: *3G, cellular communications, IMT-2000, Integrated Services Digital Network (ISDN), International Telecommunication Union (ITU), Time Division Multiple Access (TDMA)*

UNIX

A popular operating system widely deployed in today's enterprise networking environments.

Overview

UNIX is a multiprocessing, multitasking, multiuser operating system developed at AT&T Bell Laboratories in 1969. UNIX was the first operating system written entirely in the C programming language and consequently has close ties to C. Writing UNIX in C made UNIX a portable operating system—that is, by changing the source code slightly, UNIX could be "ported" (made to work on) any computer hardware platform including PowerPC, MIPS, Intel, Sparc, and various mainframe and midframe computing architectures.

UNIX has the stability and robustness of an operating system that has evolved over 25 years, but it has a reputation for being difficult to learn and administer, mainly due to its high degree of dependence on the command line. On the other hand, this emphasis makes UNIX easier to administer for those familiar with the platform, because it allows administrative tasks to be scripted, scheduled, and executed to make complex and repetitive tasks simple to perform. In fact, much of the original drive toward developing scripting languages came from the UNIX administration environment.

UNIX was designed as a time-sharing environment, in contrast to the batch environment of most computing systems of the time. Using UNIX, multiple users could simultaneously access the system and run their programs, communicating interactively with the system using remote terminals. UNIX users could thus collaborate in real time on computing projects by sharing files and resources.

UNIX has established strong roots for itself in academic computing environments, where it is still frequently used and taught today. UNIX also has its roots in the Internet environment where UNIX and Transmission Control Protocol/Internet Protocol (TCP/IP) evolved hand-in-hand in the 1980s. TCP/IP is the underlying network transport used by all UNIX systems.

Types

There are actually two main “branches” in the UNIX “family tree”:

- **BSD:** Stands for Berkeley Software Distribution, an early variant of UNIX developed in the 1970s by students at the University of California at Berkeley, who licensed AT&T’s version and added such new features as the C shell and vi editor to enhance the AT&T platform. BSD UNIX forms the basis of SunOS, a lightweight version of UNIX developed by Sun Microsystems that supports only a single processor. Another popular flavor of BSD is iXsystems (formerly BSDi) from Wind River Systems. There are also several free versions of BSD UNIX, including FreeBSD, OpenBSD, and NetBSD.
- **System V:** Developed by AT&T Bell Laboratories with UNIX Systems Laboratories, this version incorporates some features of BSD UNIX. The source code for System V UNIX was owned by Santa Cruz Operation (SCO), which is now called Tarantella and is part of Caldera International. System V forms the basis of Solaris, a popular version of UNIX from Sun Microsystems (Solaris also includes some features of BSD), and several other versions.

Based on evolution from these two branches, UNIX has evolved into a number of different “flavors” as vendors have adapted it to their own proprietary hardware platforms. These flavors include the following:

- **Solaris:** This version was developed by Sun Microsystems for its proprietary SPARC computing architecture and is the most popular version of UNIX in use today in the enterprise. Sun Enterprise Servers and Ultra Workstations running Solaris provide a powerful and reliable platform for high-performance computing. Solaris is based on SunOS 5.x, which itself was based on BSD with some features from System V R4 included. The current release of this product is Solaris 8, and it is compliant with the UNIX 98 standard.
- **AIX:** This version by IBM is for its midrange RS/6000 and PowerPC computing platforms. AIX is currently in distant second place in the commercial UNIX marketplace behind Sun’s Solaris operating system. Efforts are underway to port AIX to Intel Corporation’s new 64-bit Itanium processor architecture, which, when complete, should make AIX a viable competitor to Solaris in the high-end server market. The current release of this product is AIX 5L, and it is compliant with the UNIX 98 standard.
- **HP-UX:** This version was developed by Hewlett-Packard Company for its HP 9000 server line and is a close third-place finisher in the commercial UNIX market, behind Sun’s Solaris and IBM’s AIX platforms. HP-UX is based on System V but has some BSD features included. The current release of this product is HP-UX 11i, and it is compliant with the UNIX 95 standard.
- **Tru64 Unix:** This version was originally called Digital Unix and was developed by Digital Equipment Corporation (DEC) for its Alpha processor platform. It was renamed Tru64 when DEC was acquired by Compaq Computer Corporation. Tru64 runs only on the Alpha platform, which is now discontinued but still widely used in high-end computing environments by many companies. Tru64 Unix is compliant with System V R3.2 and R4. The current release of this product is Tru64 Unix 5.1, and it is compliant with the UNIX 95 standard.

- **UnixWare:** This version was developed by SCO (now Caldera) to port UNIX to the Intel PC platform. The current release is UnixWare 7, and it is compliant with the UNIX 95 standard.
- **IRIX:** This version was developed by Silicon Graphics, Inc. (SGI) for its high-end SGI MIPS servers and graphic workstations. IRIX is based on System V R3.2 and R4. The current release is IRIX 6.5, and it is compliant with the UNIX 95 standard.
- **Linux:** A UNIX-like operating system developed by Linus Torvalds which is rapidly growing in popularity for niche deployments in the enterprise.

Several attempts have been made to standardize the UNIX operating system. AT&T created a written standard called the System V Interface Definition (SVID) for its UNIX System V Release 4 (SVR4). In addition, an industry consortium created a standard called Portable Operating System Interface for UNIX (POSIX). The actual trademark *UNIX* is now owned by The Open Group, a consortium of software and hardware manufacturers.

Notes

Microsoft Windows 2000 and Windows .NET Server support interoperability with UNIX to support real-world heterogeneous enterprise networking environments. This interoperability is provided through built-in protocols, services, and tools in the Windows 2000 operating system and also through Microsoft Services for UNIX 2, an add-on product from Microsoft Corporation. Built-in Windows/UNIX interoperability on the Windows 2000 platform includes such features as:

- Common support for industry-standard protocols such as TCP/IP, Dynamic Host Configuration Protocol (DHCP), Domain Name System (DNS), and remote procedure call (RPC) functionality
- Support for File Transfer Protocol (FTP) and Hypertext Transfer Protocol (HTTP) for cross-platform file sharing
- Support for UNIX printing through Line Printer Daemon (LPD), Line Printer Queue (LPQ), and Line Printer Remote (LPR) utilities
- Support for remote terminal emulation using Telnet
- Support for cross-platform database access through open database connectivity (ODBC)
- Support for industry-standard network management through Simple Network Management Protocol (SNMP) and Remote Network Monitoring (RMON)

Services for UNIX 2 provides additional interoperability features with the following UNIX platforms: Solaris, HP-UX, Digital UNIX, IRIX, and Linux. Several third-party companies also offer Windows-compatible interoperability solutions such as:

- X Windows clients specifically designed for Windows-based PCs to support connectivity with UNIX servers
- X Windows servers for Windows such as that from Hummingbird International
- Server Message Block (SMB) to Network File System (NFS) protocol conversion for file sharing between platforms using products such as Samba

See Also: *AIX, Alpha platform, BSD, C++, HP-UX, Intel-based platform, Linux, POSIX, shell, Transmission Control Protocol/Internet Protocol (TCP/IP), UNIX commands*

UNIX commands

Commands for administering various aspects of the UNIX operating system.

Overview

UNIX commands are text-based commands executed from the command line to perform a wide variety of administrative tasks. Most of these commands can also be used in batch files to perform complex administrative tasks from a single command. You can create batch files with a text editor such as ed or vi and schedule their execution by using the Cron command.

The table shows some commonly used UNIX commands, listed in alphabetical order with brief descriptions. Some commands have a simple syntax, such as the cd command for changing the current directory.

Others are more complex and include scripting engines and even programming compilers, such as cc, the UNIX C compiler. Most versions of UNIX support most of these commands, but there are sometimes subtle differences from system to system. To see the exact syntax for any UNIX command, use the man command, which provides access to the UNIX online command reference. For example, to see the syntax for the cd command, type **man cd** at the UNIX command prompt. Note that that there are many UNIX commands not listed in this table—it would take many pages to list all the commands available on the various UNIX platforms.

Some of the commands below are asterisked (*), which indicates that they are specifically available on the Microsoft Windows 2000 platform when Microsoft Services for UNIX 2 is installed.

Some Common UNIX Commands

Command	*Description*
alias	Displays or sets aliases for long command strings
awk	Searches a file for a pattern and performs an action on the lines containing that pattern
basename*	Removes the path leaving only the file name
bg	Moves a stopped process into the background and restarts it
cal	Displays a calendar
cat*	Concatenates or displays files
cc	C language compiler
cd	Changes the current directory
chgrp	Changes group ownership of a file
chmod*	Changes access permissions for a file
chown*	Changes individual ownership of a file
chsh	Changes the default shell in a password file
clear	Clears the screen
cmp	Compares two files and returns the line numbers that differ
cp*	Copies a file
csh	C shell command interpreter
date	Displays the date and time
df	Displays the amount of free disk space in a file system
diff	Displays differences between two files
dirname*	Delivers all but the last level of the path in string
du	Displays file system usage
echo	Echoes the text typed following the command to the screen
ed	Text editor
elm	Text-based e-mail
emacs	Text editor
f77	FORTRAN77 compiler
fg	Moves a stopped process to the foreground and restarts it
find*	Finds a file with specified characteristics
ftp	File Transfer Protocol (FTP) client
grep*	Searches a file for a text pattern
head*	Displays the beginning of a file (by default, displays the first 10 lines)
help	Displays help
hostname	Displays the name of the current host system
kill	Ends a running process
ksh	Korn shell command interpreter
ln*	Links files
lpq	Displays the print queue
lpr	Sends a print job to the spooler
ls*	Lists files in a directory and displays the file statistics
mail	Sends e-mail
man	Accesses the online manual
mkdir*	Creates a new directory
more*	Displays a file one screen at a time
mv*	Moves or renames a file
passwd	Changes your password
perl*	Interpretive scripting language
pico	Text editor
pine	Text-based e-mail program
ps	Displays the status of a process
pwd	Displays the name of the current directory
rm*	Deletes a file
rmdir*	Deletes a directory

(continued)

Some Common UNIX Commands *continued*

Command	*Description*
sed*	Stream line editor
sh*	Invokes the Korn shell command interpreter
sleep	Pauses a process
sort*	Sorts or merges files
split	Splits a file into multiple files
tail*	Copies name file to standard output starting at designated place
talk	Text-based chat
tee*	Transcribes standard input to standard output
telnet	Terminal emulator
touch*	Creates a new file of designated name
uniq*	Reports repeated lines in file
uucp	UNIX-to-UNIX system file copies
uudecode	Decodes a uuencoded file
uuencode	Encodes a binary file
vi*	Text editor
wc*	Displays line, word, or character count in file
who	Displays who else is logged on
whoami	Displays the name of the user currently logged on
whois	Finds remote users and sites
write	Sends a message to a user

See Also: *command, command interpreter, command line, UNIX*

UNIX-to-UNIX Copy (UUCP)

A command for transferring files between two UNIX hosts on a network.

Overview

UNIX-to-UNIX Copy (UUCP) is an early form of electronic messaging developed for UNIX platforms in the 1970s. UUCP was originally designed for transferring files over an asynchronous serial transmission interface such as RS-232. With UUCP, you can transfer files through a direct cable connection between serial ports on two computers by using a null modem cable or over telephone lines by using modems connected to the serial ports of each computer. A version of UUCP has been developed for transferring files over Ethernet as well. UUCP was also used for transferring electronic mail messages (e-mail) between hosts in the early days of the Internet. UNIX hosts used UUCP to transfer mail to a remote host simply by executing the MAIL program on the remote UNIX host and having it run on the local message file to be delivered.

UUCP uses the well-known port number 117 for its path service and number 540 for the UUCP daemon called UUCPD. UUCP has been eclipsed by File Transfer Protocol (FTP) as a general protocol for moving files between hosts and by Simple Mail Transfer Protocol (SMTP) for transferring e-mail messages.

Notes

Third-party vendors have created UUCP gateway connectors for Microsoft Exchange Server to enable Exchange to send and receive UUCP mail over the Internet.

See Also: *Ethernet, RS-232, serial transmission, Simple Mail Transfer Protocol (SMTP), UNIX, UNIX commands*

unshielded twisted-pair (UTP) cabling

Twisted-pair cabling with no internal shielding.

Overview

Unshielded twisted-pair (UTP) cabling is the most common form of network cabling for workgroups and departmental local area networks (LANs) because of its low cost, flexibility, and good performance. In UTP cabling the outer insulating jacket protects the cable from physical stress or damage but does not shield the cable from electromagnetic interference (EMI).

UTP cabling has an impedance of approximately 100 ohms and is available in various grades or categories based on data transmission capabilities, as shown in the table. Category 5 (Cat5) cabling and enhanced Category 5 (Cat5e) cabling are the most popular forms of UTP cabling in Ethernet networking. No agreed standards exist above Cat5e, but there is a proposed standard for Category 6 (Cat6) cabling and some manufacturers even offer UTP cabling they call Category 7 (Cat7) cabling.

UTP Cabling Categories

Category	*Use*
Category 1 (Cat1)	Analog voice grade
Category 2 (Cat2)	Digital voice transmissions up to 4 megabits per second (Mbps)
Category 3 (Cat3)	Digital transmissions up to 10 Mbps
Category 4 (Cat4)	Digital transmissions up to 16 Mbps
Category 5 (Cat5)	Digital transmissions up to 100 Mbps
enhanced Category 5 (Cat5e)	Digital transmission up to 250 Mbps

Notes

To ensure that Cat5e UTP cabling performs effectively, you should also use certified Cat5e wall plates, connectors, and patch panels. The patch panel or wall plate connections should be untwisted no more than 0.5 inch (1.3 cm); also try to keep cabling away from fluorescent lights, motors, and other sources of EMI. Do not bend the cable sharply—the radius of a bend should not be less than 10 times the diameter of the cable. Finally, avoid pulling cable wraps too tightly or crushing the cables in any way.

See Also: *Category 1 (Cat1) cabling, Category 2 (Cat2) cabling, Category 3 (Cat3) cabling, Category 4 (Cat4) cabling, Category 5 (Cat5) cabling, Category 6 (Cat6) cabling, Category 7 (Cat7) cabling, electromagnetic interference (EMI), enhanced Category 5 (Cat5e) cabling, Ethernet, shielded twisted-pair (STP) cabling, structured wiring*

update sequence number (USN)

A type of identifier used in directory replication in Microsoft Windows 2000 and Windows .NET Server.

Overview

Update sequence numbers (USNs) are used for controlling directory replication between domain controllers. When an object is changed in Active Directory directory service, that change must be replicated to all other domain controllers. To do this, Active Directory assigns a USN to each changed object, incrementing the values with time. Each domain controller uses a table to keep track of its own current USN and the highest USN it has received from each of the other domain controllers on the network.



Update sequence number (USN). *How Active Directory uses USNs during directory replication between domain controllers.*

For example, if a domain controller called ABLE notifies a domain controller called BAKER of the updates it has for Active Directory, ABLE sends its own current USN number to BAKER, which compares the USN with the USN it recorded for ABLE in its internal table after the last directory update it received from ABLE. If the received USN is higher than the recorded USN, BAKER requests that ABLE send its updates for the directory. If the received USN is equal to or lower than the recorded one, BAKER knows that it has an up-to-date copy of ABLE's directory and does not request any updates.

USNs are more accurate than time stamps in controlling replication between domain controllers because time stamps depend on the clocks of domain controllers being exactly synchronized. However, time stamps are also employed if a tie-breaking mechanism is required for replication purposes. USNs also speed the recovery of Active Directory if a domain controller experiences a failure.

See Also: *Active Directory, domain controller*

uplink port

A port on an Ethernet hub used to connect the hub to another hub.

Overview

Uplink ports allow Ethernet hubs to be cascaded to form larger networks using standard unshielded twisted-pair (UTP) patch cables. This method of connecting hubs does not use up any of the hub's station ports, which are used to connect computers to the hub. An arrangement of hubs connected together is typically known as a cascaded star topology.

When cascading hubs together, be sure that the root or main hub of your cascaded star arrangement of hubs is a high-quality hub. Do not create collision domains larger than about 150 computers—network performance can degrade seriously due to too many collisions on the network. If hubs cannot meet your bandwidth requirements, consider replacing the main hub with an Ethernet switch.

Notes

If you do not have an uplink port on your hub, you can still connect a station port on the hub to a station port on another hub by using a crossover cable.

See Also: *crossover cable, Ethernet, hub, topology, unshielded twisted-pair (UTP) cabling*

UPN

Stands for User Principal Name, the logon name of a user on a Microsoft Windows 2000 or Windows .NET Server network.

See: *user principal name (UPN)*

UPS

Stands for uninterruptible power supply, a device that can temporarily provide power to network components.

See: *uninterruptible power supply (UPS)*

URL

Stands for Uniform Resource Locator, an addressing scheme for locating resources on the Internet.

See: *Uniform Resource Locator (URL)*

URL switching

A technology for load-balancing Hypertext Transfer Protocol (HTTP) traffic.

Overview

URL switching enables you to flexibly manage access to content stored on Web servers by load-balancing incoming HTTP requests. URL switching does this by directing these incoming requests to Web servers and caching servers based on the value of various substrings within the HTTP headers. For example, requests for static Web pages might be switched to a caching server, while requests for dynamic content are switched to a Web application server. Other criteria that can be used to switch requests include the size of the file requested and whether the content is multimedia in form. Once the switch determines the best server to service the request, it binds the request to that server for the duration of the session. Cookies can also be used with Uniform Resource Locators (URLs) to switch requests to specific Web servers in a server farm.

Other names sometimes used to describe URL switching include Web content switching and Layer-7 switching.

Marketplace

A leading vendor in URL switching devices arena is Alteon WebSystems (acquired by Nortel Networks). Other vendors of Web content switches include Cisco Systems, F5 Networks, Foundry Networks, and Intel Corporation.

See Also: *caching, Hypertext Transfer Protocol (HTTP), Layer 2 switch, Uniform Resource Locator (URL), Web server*

USB

Stands for universal serial bus, a high-speed serial interface for connecting peripherals to computers.

See: *universal serial bus (USB)*

Usenet

A global network of Internet hosts that supports tens of thousands of discussion groups covering every imaginable topic.



Usenet. *How the Usenet system works on the Internet.*

Overview

Usenet is part of the Internet's family of protocols and services and is typically used by individuals for such purposes as

- Asking questions or requesting assistance on a particular issue
- Distributing free information, including binary files such as images, sound clips, and multimedia files
- Advertising products and services
- Discussing issues of general, regional, local, or topical interest

Usenet currently consists of more than 60,000 newsgroups worldwide, and new groups are constantly being created as old ones disband. Most news servers do not carry the complete range of Usenet newsgroups because of the multigigabyte size of a full newsfeed. Other news servers exclude certain categories of groups, such as adult newsgroups. Some newsgroups are moderated, which means that new postings to the group must be approved by a moderator before they can appear in the newsgroup. This minimizes the "noise" or extraneous messages (mostly advertising).

Users typically gain access to the Usenet system by accessing a Usenet server running at their Internet service provider (ISP). Users typically must have an account and a password to connect to their ISP's news server to prevent unauthorized use, although free Usenet servers are also available across the Internet. Users employ Network News Transfer Protocol (NNTP) client software such as Microsoft Outlook Express to access newsgroups on the ISP's server and post new messages to them. Periodically, the ISP's news server replicates its newsgroup messages by pushing or pulling newsfeeds together with nearby Usenet servers on the Internet. As a result, within about 24 hours the messages posted by users are available on virtually every Usenet server in the world. A message typically remains on a news server for a few weeks or until enough new messages have been posted to the newsgroup to bump the old messages off the list.

Implementation

The Usenet system is based on NNTP, a standard Internet protocol defined in RFC 977. The architecture that supports Usenet has two components:

- **Client/server:** This component allows user desktop machines running NNTP client software such as Outlook Express to interact with Usenet servers (NNTP hosts) to perform actions such as downloading a list of available Usenet newsgroups on the server, reading existing messages in the newsgroups, replying to existing messages, or posting new messages.
- **Server/server:** This component allows NNTP hosts to communicate with each other, primarily for the purpose of replicating newsgroup messages between each other to ensure that each NNTP host has up-to-date messages in the newsgroups they host. An example of software that can function as an NNTP host is Microsoft Exchange Server, which fully supports NNTP and can be used to host newsgroup discussions.

The Usenet system of newsgroups is hierarchical in nature, similar to the Domain Name System (DNS). At the top level, Usenet consists of a number of top-level news hierarchies that identify either a range of topics (such as .rec for recreational topics) or a geographic location (such as .mn for Minnesota). Newsgroups are created hierarchically under these top-level categories, as in these examples:

- forsale.mn
- computers.forsale.mn
- macintosh.computers.forsale.mn

The following table shows some of the popular top-level categories.

Top-Level Usenet Categories

Category	*Description*
alt	Alternative, which is a collection of various topics
comp	Information on computer hardware, software, algorithms, and other topics
misc	Miscellaneous information
news	Information about Usenet itself
rec	Recreational topics such as hobbies and travel
sci	Scientific issues
soc	Social issues
talk	General discussion topics such as politics and religion

Notes

If you do not have an NNTP client program or if your company firewall will not allow you to access Usenet services using the well-known port number for NNTP (port 119), you can still access Usenet (if you can browse the Internet using a standard Web browser such as Microsoft Internet Explorer). Web sites such as Google (*www.google.com*) offer a Web interface for reading and posting to Usenet newsgroups. Before doing this at work, however, make sure that your company does not have any policies forbidding employees to access Usenet.

See Also: *Exchange Server, Internet, Internet service provider (ISP), Network News Transfer Protocol (NNTP)*

user account

Credentials assigned to a user to enable secure access to network resources.

Overview

User accounts allow users to log on to desktop computers to access network resources such as shared folders, shared printers, e-mail services, and databases. An administrator generally grants a user access to these resources by assigning the user a set of credentials (user name and password) called a user account. In Microsoft Windows 2000 and Windows .NET Server networks, there are two basic types of user accounts:

- **Domain user accounts:** These are created in Active Directory directory service and stored on domain controllers. You can log on to any computer on the network if you have a domain user account. Domain user accounts are usually referred to simply as user accounts.
- **Local user accounts:** These are stored within the local directory database of a stand-alone server or desktop workstation that belongs to a workgroup instead a domain. A user who has a local user account can log on only to the computer on which the account was actually created.

Notes

A group account (or simply group) essentially acts as a container for holding user accounts. Group accounts simplify network administration by allowing multiple users to be granted or denied access to network resources in a single step—by granting or denying access for the group account to the resource.

See Also: *account, domain user account, group, local user account*

User Datagram Protocol (UDP)

A transport layer protocol of the Transmission Control Protocol/Internet Protocol (TCP/IP) suite.

Overview

User Datagram Protocol (UDP) is one of two transport layer protocols within the TCP/IP protocol suite, the other being Transmission Control Protocol (TCP). Unlike TCP, which is intended for reliable, connection-oriented sessions between two hosts, UDP is a connectionless protocol in which packets are sent without first negotiating a connection between the sending and receiving hosts. UDP also does not include the segmentation, sequencing, flow control, acknowledgement, and retransmission features of TCP and is therefore an “unreliable” or “best-effort delivery” protocol in the same sense that ordinary mail (“snail mail”) is unreliable—that is, there is no guarantee that a packet (or letter) sent will reach its intended recipient (think of TCP as the equivalent of "registered mail" in this analogy). Reliable delivery of UDP packets is the responsibility of application layer protocols above it that use UDP as their underlying network transport. UDP packets do include a checksum header, however, to ensure the integrity of packets that reach their destination.

Because of these characteristics UDP is considered the more "lightweight" of the two TCP/IP transport layer protocols. Although TCP is used for one-to-one communication between two hosts—in other words, for unicasting—UDP is used for one-to-many communication, which includes both broadcasting and multicasting. The following table summarizes the various differences between UDP and TCP—as you can see, UDP is a much simpler protocol than TCP, mainly because it does not need to include mechanisms relating to establishing, maintaining, and tearing down sessions between hosts. Note that neither UDP nor TCP includes fields for source and destination address in their headers—this is because the underlying network layer protocol called Internet Protocol (IP) is responsible for such addressing.

Comparison of Features of UDP and TCP

Feature	*UDP*	*TCP*
Connection method	Connectionless	Connection-oriented
Communication model	One-to-one	One-to-many
Reliability	Best effort	Guaranteed
Header length	8 bytes	20 bytes
Header fields	Source and destination port, length, checksum	Source and destination port, sequence number, acknowledgement number, data offset, reserved, flags, window, checksum, urgent pointer, options, and padding

Uses

Some examples of where UDP is employed include applications and services where name queries are performed, such as

- Domain Name System (DNS)
- NetBIOS name resolution (but if Windows Internet Name Service [WINS] is employed, then TCP is used instead)

Other examples include protocols and services where reliability is provided by

- The application layer protocol itself—for example, Network File System (NFS) and Trivial File Transfer Protocol (TFTP)
- Periodic advertisements—for example, Routing Information Protocol (RIP)

Notes

UDP is defined by RFC 768.

See Also: *connectionless protocol, connection-oriented protocol, Domain Name System (DNS), Internet Protocol (IP), NetBIOS name resolution, Network File System (NFS), Routing Information Protocol (RIP), Transmission Control Protocol (TCP), Transmission Control Protocol/Internet Protocol (TCP/IP), Trivial File Transfer Protocol (TFTP), Windows Internet Name Service (WINS)*

user-level security

A mode of security on computers running Microsoft Windows 98 and Windows Me that protects shared folders and printers by requiring that users be authenticated by the network's security provider.

Overview

User-level security is more flexible and granular than share-level security, which protects shared resources using a password only. The security provider for enabling user-level security to be used on a Windows network can be a Windows 2000 or Windows .NET domain controller or a Novell NetWare server, depending on which network client the computer running Windows 98 or Windows Me has installed.

Windows 98 and Windows Me employ pass-through authentication for granting client requests for shared resources on the computer:

1. A remote client attempts to access a share on the computer running Windows 95 or Windows 98, passing it the user's credentials.

U

2. The computer forwards the user's credentials to the network security provider.
3. The security provider verifies the credentials and informs the computer.
4. The computer grants the user the specified level of access to the share, depending on the user's account and group memberships.

Notes

Use the Network utility in Control Panel to enable user-level security on a computer running Windows 98 or Windows Me.

See Also: *domain controller, share-level security*

User Locator Service (ULS)

Former name for Internet Locator Service, a Lightweight Directory Access Protocol (LDAP) directory service that enables Microsoft NetMeeting users to locate and contact other users for conferencing and collaboration over the Internet.

See: *Internet Locator Service (ILS)*

user mode

A restricted mode of operation for processes in Microsoft Windows NT, Windows 2000, Windows XP, and Windows .NET Server.

Overview

User mode processes include components of the operating system that directly support user applications and the applications that use those subsystems. User mode processes have lower priority and fewer privileges than kernel mode processes, and they cannot access hardware directly.


DOS/Win16 application
POSIX application
Win32 application
NTVDM
OS/2 application
Logon process
User mode
POSIX subsystem
Win32 subsystem
OS/2 subsystem
Security subsystem
Windows NT Executive
Executive services
System services
I/O Manager
Object Manager
Security Reference Monitor
Process Manager
Local Procedure Call Facility
Virtual Memory Manager
Win32 Window Manager & GDI
Kernel mode
Hardware device drivers
Microkernel
Hardware abstraction layer (HAL)
Graphic device drivers
Hardware

User mode. *Architecture of Windows 2000 user mode.*

User mode subsystems include

- Win32 subsystem, which supports Windows applications
- OS/2 subsystem, which supports OS/2 applications
- POSIX subsystem, which supports POSIX-compliant applications
- Security subsystem, which handles logon validation

See Also: *kernel mode*

username

A unique identifier that enables a user to log on to a computer or network.

Overview

Usernames are part of a user's credentials, which include the username, password, and domain name. Each user on the network must have a unique username so that his or her personal folders can be protected against unauthorized access and for administrative purposes such as auditing. A typical example of a username might be "jsmith" or "jeffs" for a user named Jeff Smith. On a network running Microsoft Windows 2000 or Windows .NET Server, an administrator or an account operator can employ the Active Directory Users and Computers console to create and manage user accounts, and account restrictions can be created and managed using group policies.

See Also: *naming convention, user account*

user principal name (UPN)

The logon name of a user on a Microsoft Windows 2000 or Windows .NET Server network.

Overview

User principal names (UPNs) are one of three types of names by which objects in Active Directory directory service can be known, the others being distinguished names (DNs) and relative distinguished names (RDNs). The UPN for a user consists of the name of the User object in Active Directory that is associated with that user's account, followed by the @ sign and then typically by the Domain Name System (DNS) name of the container in Active Directory in which the User object resides. The UPN must be unique for every User object stored in Active Directory.

Examples

If the User object in Active Directory for user Jeff Smith has the name jsmith and if this User object resides in the container with a DNS name of sales.microsoft.com, the default form of Jeff Smith's user principal name is as follows:

```
jsmith@sales.microsoft.com
```

An alternative form of the user principal name for Jeff Smith is

```
jsmith@microsoft.com
```

In other words, the suffix for the user principal name of a user can be either the name of the tree or the name of the domain that resides above the object named in the tree. Note the similarity between the user principal name for Jeff Smith and what you might expect his Simple Mail Transfer Protocol (SMTP) e-mail address to be. The difference is that the user principal name is merely a property that is assigned to the user and can be set to any value.

See Also: *Active Directory, distinguished name (DN), Domain Name System (DNS), Simple Mail Transfer Protocol (SMTP)*

user profile

On Microsoft Windows platforms, user-definable information about a user's work environment, including desktop settings, network connections, printer connections, and Start menu items.

Overview

A user's profile is stored in a folder named after the username and consists of a registry hive and a series of subfolders whose functions are listed in the following table. If additional software is installed on the computer (such as Microsoft Internet Explorer), additional subfolders might exist within the user's profile folder.

Typical User Profile Subfolders and Registry Hives

Subfolder or Hive	*Contents*
Application Data folder	Vendors' application-specific data
Desktop folder	Files and shortcuts on the Windows desktop
Favorites folder	Favorite locations
NetHood folder	Shortcuts to Network Neighborhood items
Personal folder	Users' personal documents
PrintHood folder	Shortcuts to Printer Folder items
Recent folder	Shortcuts to recently opened documents
SendTo folder	Shortcuts for the SendTo menu
Start Menu folder	Start menu shortcuts
Templates folder	Shortcuts to templates
ntuser.dat	Copy of the HKEY_CURRENT_USER hive
ntuser.dat.log	Transaction log for error recovery

Users group

A built-in group in Microsoft Windows 2000 and Windows .NET Server.

Overview

The Users group is a domain local group on domain controllers and a local group on stand-alone servers and computers running Windows 2000 or Windows XP. The initial membership of the Users group is the domain users global group, which consists of all ordinary users on the network. The Users group has no preassigned rights or permissions and should be assigned permissions to network resources that ordinary users will normally require.

See Also: *built-in group*

USN

Stands for update sequence number, a type of identifier used in directory replication in Microsoft Windows 2000 and Windows .NET Server.

See: *update sequence number (USN)*

UTP cabling

Stands for unshielded twisted-pair cabling, twisted-pair cabling with no internal shielding.

See: *unshielded twisted-pair (UTP) cabling*

UUCP

Stands for UNIX-to-UNIX Copy, a command for transferring files between two UNIX hosts on a network.

See: *UNIX-to-UNIX Copy (UUCP)*

uuencoding

A method of encoding binary files into 7-bit ASCII text.

Overview

Uuencoding was originally developed for UNIX platforms to enable binary files to be attached to e-mail messages and transmitted over the Internet using Simple Mail Transfer Protocol (SMTP). The sending program first "uuencodes" the attachments and sends them with the e-mail message, which the receiving program "uudecodes" into its original binary format.

Although still popular on some platforms, uuencoding has been largely superseded by Multipurpose Internet Mail Extensions (MIME), a more sophisticated scheme for encoding multipart e-mail messages. Uuencoding is still used in one context in Microsoft Windows, namely for Basic Authentication on Internet Information Services (IIS). Basic Authentication transmits the user's credentials between the Web browser client and the IIS computer in uuencoded form. This method is commonly referred to as cleartext transmission, although if you were to capture authentication traffic by using a network sniffer such as Microsoft Network Monitor, you would be unable to read the user's credentials without uudecoding the information. Uuencoding is not considered a cryptographic algorithm because it is extremely simple to crack.

An encoding method similar to uuencoding that is implemented on Apple Macintosh systems is called BinHex.

U

Notes

You can tell that a binary file has been uuencoded into an ASCII text file if the text of the file starts with “begin 644...”

See Also: *Basic authentication, Internet Information Services (IIS), Multipurpose Internet Mail Extensions (MIME), Simple Mail Transfer Protocol (SMTP), UNIX*

UWC-136

A standard for third-generation (3G) wireless cellular communication systems.

See: *Universal Wireless Communications (UWC-136)*

V

V.35

A popular serial transmission interface found on routers.

Overview

V.35 defines a high-speed physical interface for synchronous serial communication between data terminal equipment (DTE) and data communications equipment (DCE). V.35 is part of the V-series standards developed by the International Telecommunication Union (ITU) and is widely used in the networking industry.

V.35 uses balanced lines for signaling and unbalanced lines for sending control information. The standard supports transmission rates of up to 1.544 megabits per second (Mbps) over distances of up to 4000 feet (1200 meters). The V.35 interface is typically used to connect routers and other wide area network (WAN) access devices to Channel Service Unit/Data Service Units (CSU/DSUs) to build WANs using T1 lines.



V.35. *Typical V.35 connector format.*

V.35 uses a block-shaped 34-pin block connector for implementing these DTE-to-DCE connections, but you can also use V.35-to-RS-232 gender changers to connect V.35 equipment using 25-pin (DB25) serial cables.

Notes

Although the V.35 standard was replaced by the V.10 and V.11 standards in 1988, it remains one of the more popular DTE/DCE interfaces for local area network/ wide area network (LAN/WAN) connectivity.

Notes

Although the V.35 specification tops out at speeds of 1.544 Mbps, routers from most vendors support higher speeds in their implementation of the V.35 interface, with some as high as 10 Mbps. Nevertheless, if you need WAN links faster than T1 speeds, you will probably need to use a router with a high-speed serial interface (HSSI) port instead of V.35.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), data communications equipment (DCE), data terminal equipment (DTE), High-Speed Serial Interface (HSSI), International Telecommunication Union (ITU), router, serial transmission, T1, V-series, wide area network (WAN)*

V.90

A popular high-speed modem standard.

Overview

V.90 is part of the V-series standards developed by the International Telecommunication Union (ITU). V.90 evolved from two earlier modem standards: the x2 modem technology developed by U.S. Robotics (later bought by 3Com Corporation) and the K56flex modem technology developed by Rockwell. V.90 modems theoretically support downstream communication at 56 kilobits per second (Kbps) and upstream at 33.6 Kbps (upstream transmission is implemented using the same method as the older 33.6 Kbps V.34bis modem standard). V.90 downstream transmission is limited by several factors:


Earlier Modems
Digital PSTN
Client
V.34
modem
Switched
circuit
ADC/DAC
V.34
modem bank
NAS
(network
access server)
Digital
Analog
ADC/DAC
Digital
Analog
Digital
V.90 Modem
Digital PSTN
Client
V.90
modem
Switched circuit
V.90
modem bank
NAS
Digital
Analog
ADC/DAC
Digital
Digital

V.90. *Comparison between V.90 and earlier modem standards.*

- The downstream speed of 56 Kbps is achievable only when there is a digital phone line on one end of the connection, typically on the side of the telco or Internet service provider (ISP). In other words, V.90 is possible only on telephone networks that have only one analog segment in the communication path (the local loop at the subscriber end) instead of two analog segments (at both the subscriber and ISP/central office [CO] ends). The benefit of this scenario is that using a digital phone line on one end of the connection eliminates the quantization error that occurs during analog-to-digital conversion (ADC) that normally takes place with a modem. The digital connection at the telco is actually 64 Kbps, but due to digital-to-analog conversion (DAC) that takes place at the telco CO when the digital connection is switched to the analog local loop, some information loss results that reduces the possible downstream speed to 56 Kbps.
- Despite the fact that V.90 can support 56 Kbps downloads, the actual top downstream speed is only 53 Kbps. This is because Federal Communications Commission (FCC) regulations governing signaling over telephone lines restricts the maximum signal power that can be transmitted over the Public Switched Telephone Network (PSTN) to levels that prevent crosstalk from degrading signal quality. The result of these regulations reduces the possible downstream speed of V.90 from 56 Kbps to 53 Kbps.

- Furthermore, in real life the achievable downstream speed is less than 53 Kbps if line distances between the customer premises and the telco CO exceed 3.5 miles (5.5 kilometers) or if line conditions are poor. In practice, typical downstream speeds for V.90 are usually between 40 to 50 Kbps and the speed is negotiated during call setup. The way this happens is that V.90 employs mechanisms whereby the client modem issues a request for a test tone during negotiation, which is then used to gauge the line quality to determine the optimal downstream transmission speed.

V.90 modems have proved enormously popular for dial-up Internet access. Some industry analysts estimate that there are almost 100 million V.90 modems in use around the world. Although use of broadband Internet using Digital Subscriber Line (DSL) and cable modems is increasing, analysts estimate that V.90 modems will continue to remain the dominant solution until around 2004.

See Also: *cable modem, crosstalk, Digital Subscriber Line (DSL), Internet access, modem, Public Switched Telephone Network (PSTN), serial transmission, V.92, V-series*

V.92

The latest high-speed modem standard from the International Telecommunication Union (ITU).

Overview

V.92 is an emerging standard that provides the same 56 kilobits per second (Kbps) theoretical downstream speeds as the earlier V.90 modem standard. V.92, however, offers some significant enhancements over V.90 modem technology, specifically:

- Upstream speed of 48 Kbps compared to only 33.6 Kbps for V.90 modems. This is accomplished by using the same transmission algorithm for upstream that is used for V.90 downstream communication—in contrast to V.90, which uses the older V.34bis standard for upstream communication.
- Faster call setup and handshaking, typically only 10 seconds compared to 30 seconds for V.90 modems.
- Support for call waiting, so that a user can interrupt a modem session to take a telephone call and then resume the modem session. This means that home users will need only one telephone line instead of two if they use V.92 modems for Internet access.

Marketplace

V.92 modems are being developed by a number of modem manufacturers, including U.S. Robotics, Lucent Technologies, Motorola, PCTEL, and several others.

Issues

Because of these features, V.92 appeals to enterprises using modem pools for remote access to corporate networks. Faster call setup and faster upstream speeds mean shorter remote access sessions and hence lower costs. This can be particularly significant when remote access is performed over long-distance telephone lines.

On the other hand, some Internet service providers (ISPs) may be reluctant to implement V.92, because users may leave their modems connected to the Internet all the time. This may mean greater costs for ISPs, who may have to add additional modem pools to handle the longer connection times (the average dial-up Internet access session is estimated by some analysts at 30 minutes).

See Also: *International Telecommunication Union (ITU), modem, remote access, V.90, V-series*

value entry

A data entry in the Microsoft Windows registry.

Overview

Value entries are contained in keys and are analogous to variables. They consist of three parts:

- **Name:** The name of the value entry (for example, MaintainServerList)

- **Data type:** The type of data stored in the value entry (for example, REG_SZ represents human-readable text)
- **Value:** The actual data contained in the value entry (for example, the string "Auto")

Some of the various data types supported by Windows 2000,Windows XP, and Windows .NET Server are shown in the table. Applications can also define other data types when required.

Examples of Value Entry Data Types

Data Type	*Description*
REG_BINARY	Raw binary data, usually displayed in the registry editor in hexadecimal format
REG_DWORD	Data represented by a number that is 4 bytes long and is displayed in the registry editor in binary, hexadecimal, or decimal format
REG_EXPAND_SZ	An expandable data string (text that contains a variable that is replaced when called by an application)
REG_MULTI_SZ	A multiple string, typically used for lists that are in human-readable text with entries separated by NULL characters
REG_SZ	A sequence of characters in human-readable text, typically used for descriptive information

See Also: *key (registry), registry*

variable-length subnet mask (VLSM)

A technique for conserving Internet Protocol (IP) addresses.

Overview

Variable-length subnet mask (VLSM) was developed in response to shortages in the available pool of IP addresses. Large IP internetworks consisting of multiple subnets typically use assigned IP address blocks inefficiently. This is because although different subnets often have different numbers of hosts, network architects usually design IP internetworks using a single "one size fits all" subnet mask.

For example, consider an enterprise assigned the class B network ID 181.63.0.0 that has hosts among four networks. The number of nodes on each network is 600 on network A, 400 on network B, 200 on network C, and 2 for network D (network D is a dedicated leased line, and because this is a form of point-to-point connection, only two nodes are on the network). The simplest scheme for subnetting the network into four parts would be to use the same subnet mask for each network, namely 255.255.252.0, which can support 1022 hosts per subnet. Because there are four subnets, this subnet mask means we are using 4088 IP addresses from the available pool of 65,534 associated with the class B address. But in fact we are only using 600+400+200+2=1202 of these 4088 addresses, and so 2886 addresses are essentially wasted.

VLSM reduces the amount of wasted addresses by selecting a subnet mask closest to the needs of each network. In the above scenario, this means:

- Network A will use subnet mask 255.255.252.0, which provides 1022 possible addresses of which only 600 are being used (therefore 422 are being wasted).
- Network B will use subnet mask 255.255.254.0, which provides 510 possible addresses of which only 400 are being used (therefore 110 are being wasted).
- Network C will use subnet mask 255.255.255.0, which provides 254 possible addresses of which only 200 are being used (therefore 54 are being wasted).
- Network D will use subnet mask 255.255.255.252, which provides two possible addresses of which both are being used and none are being wasted.

Using VLSM, we have reduced the number of wasted addresses from 2886 (when using a fixed subnet mask scheme) to only 522+110+54=686 addresses, a savings of 2200 addresses.

To use VLSM in the enterprise, a routing protocol supporting VLSM must be employed for communication between routers. Although some routing protocols exchange only network addresses with each other, routing protocols supporting VLSM also exchange subnet masks together with these network addresses. The routing protocols that support VLSM are:

- Enhanced Interior Gateway Routing Protocol (EIGRP)
- Open Shortest Path First (OSPF)
- Routing Information Protocol version 2 (RIPv2)

Issues

VSLM is most often used when OSPF is used to join pre-existing routing domains that use RIP within their domain boundaries. OSPF thus provides the backbone routing service to connect these “RIP islands,” and each RIP island is defined as an OSPF area. The main problem with using VLSM, however, is that it requires careful planning to implement properly—you need to know all your subnets and the maximum possible hosts on each subnet before you start the process of subnetting your network using VLSM. For older networks, implementing VLSM basically means renumbering the network from the ground up, a time-consuming process.

A better alternative to resubnetting your internetwork using VLSM is simply resubnetting it using the private class A network ID 10.0.0.0 and a fixed subnet mask that provides enough addresses for your largest network. In this approach, you simply do not worry about wasting IP addresses because you have 16,777,214 to work with using this network ID. Of course, you can only use this approach if your IP internetwork is connected to the Internet using network address translation (NAT), but this is the standard approach anyway.

See Also: *Class A, Class B, Enhanced Interior Gateway Routing Protocol (EIGRP), IP address, Open Shortest Path First (OSPF), Routing Information Protocol (RIP), subnet mask, subnetting*

VBScript

Stands for Visual Basic Scripting Edition, a scripting language developed by Microsoft Corporation.

Overview

VBScript was designed primarily for use in Web applications running on the Internet Information Services (IIS) and Internet Explorer platforms. VBScript is a lightweight subset of the more powerful Visual Basic for Applications (VBA) programming language used in Microsoft Office and other Microsoft development platforms. VBScript omits features such as file input/output (I/O) and direct access to the operating system to provide a secure scripting platform for developing Web-based applications using server-side scripting technologies such as Active Server Pages (ASP). Internet Explorer includes a scripting engine for interpreting and running client-side scripts written in VBScript. VBScript can run on all versions of Microsoft Windows as well as on certain UNIX platforms.

Note that you cannot use VBScript to write stand-alone programs. Instead, you must embed script into standard Hypertext Markup Language (HTML) files. The script is executed when a Web browser opens the HTML file. Alternatively, ASP can use VBScript to generate HTML on the fly.

Examples

Script within an HTML page is enclosed within <SCRIPT> ... </SCRIPT> tags. For example, the following HTML segment displays a button that, when pressed, displays a message box that reads “Hello World!”:

```
<INPUT TYPE=BUTTON VALUE="Click me"
NAME="BtnHello">
<SCRIPT LANGUAGE="VBScript">
   Sub BtnHello_OnClick
        MsgBox "Hello World!", 0, "An active
        document"
   End Sub
</SCRIPT>
```

In this code, the <INPUT> tag creates the command button and the <SCRIPT> tag contains the script for the event handler that handles the button click.

For More Information

Visit the Microsoft Windows Script Technologies site at *msdn.microsoft.com/scripting.*

See Also: *Active Server Pages (ASP), Hypertext Markup Language (HTML), Internet Information Services (IIS), JavaScript, JScript, scripting*

vCalendar

An Internet protocol for interoperability between scheduling programs running on different platforms.

Overview

vCalendar allows Personal Data Interchange (PDI) programs to exchange scheduling information over the Internet to book meetings, schedule events, and plan other activities. The vCalendar standards define the for mat by which scheduling information can be exchanged over the Internet. The basic units of scheduling information are the event, which consists of a scheduled activity and its time, date, and duration, and the to-do, a work item or assignment that is delegated to an individual.

vCalendar is defined in RFCs 2445 to 2447 and is broadly supported in the e-mail and groupware industry. The current version is vCalendar 1. Microsoft Outlook 98 and later can import and export information in vCalendar format.

For More Information

Visit the Internet Mail Consortium's PDI page at *www.imc.org/pdi.*

See Also: *vCard*

vCard

An Internet protocol for exchanging business information.

Overview

vCard enables users to exchange the kind of information found on business cards by using standard Internet applications such as e-mail clients and Web browsers. It can also be integrated into fax, cellular phone, pager, smart card, and other communication technologies. You can use vCard to electronically communicate information such as a user's name, title, business, address, telephone numbers, e-mail addresses, URLs (Uniform Resource Locators), company logo, photographic likeness, audio clip, and just about anything else. vCard specifies the format for encoding information for transmission over the Internet.

vCard is defined in RFCs 2425 and 2426. The current version is vCard 3. Microsoft Outlook 98 and later and Microsoft Outlook Express 5 support the vCard protocol.

See Also: *vCalendar*

VDSL

Stands for Very-high-rate Digital Subscriber Line, a high-speed flavor of Digital Subscriber Line (DSL).

See: *Very-high-rate Digital Subscriber Line (VDSL)*

Very-high-rate Digital Subscriber Line (VDSL)

A high-speed flavor of Digital Subscriber Line (DSL).

Overview

Very-high-rate Digital Subscriber Line (VDSL) was developed in the early 1990s as a high-speed version of Asymmetric Digital Subscriber Line (ADSL). Most existing VDSL implementations support speeds to 52 megabits per second (Mbps) in the upstream direction and 2.3 Mbps downstream over existing local loop copper wiring. A limiting factor is that VDSL operates over very short distances, typically only 1000 feet (300 meters) from the telco central office (CO). At longer distances, VDLS speeds drop sharply, and the service is difficult to provision beyond about 4500 feet (1400 meters).

VDSL is undergoing standardization by the International Telecommunication Union (ITU), so current VDSL services are vendor-specific. The plan is to standardize two different versions of VDSL:

- **Asymmetric:** This will support 52 Mbps upstream and 6.4 Mbps downstream.
- **Symmetric:** This will support 26 Mbps in both directions.

Marketplace

The VDSL marketplace is still growing, and not many carriers offer the technology to customers. VDSL Systems provides 16-port and 32-port VDSL multiplexers for the carrier market that can handle 26 Mbps traffic at distances up to 5000 feet (1500 meters). The company also provides VDSL customer premises equipment (CPE) in various form factors including access routers, PCI cards, and set-top boxes for the hotel industry.

Telco Systems has an innovative switching called CopperMax, which allows companies to use VDSL to link buildings together using existing telephone lines, provided they are less than 0.75 miles (0.5 kilometers) apart.

See Also: *Asymmetric Digital Subscriber Line (ADSL), Digital Subscriber Line (DSL), International Telecommunication Union (ITU), local loop*

virtual circuit

A logical path or connection between nodes in a network.

Overview

The path of a virtual circuit is composed of discrete segments of the network that are interconnected using switches. Before a transmission can be sent over the circuit, both end stations must agree on the path and its signaling characteristics, a process called establishing the circuit. Once the circuit has been established, the end stations communicate as if they were directly connected using physical wires, but it is the switches that actually establish the communication path throughout the network. To change the logical path the virtual circuit takes across the network, you simply reconfigure the switches—you do not need to reconnect any wires. This is called a virtual circuit because, like a real (physical) circuit, it connects two points for transmission purposes, but instead of being hard-wired it is configurable and therefore “virtual” in nature.

Virtual circuits are generally used in packet-switching networks such as Asynchronous Transfer Mode (ATM), frame relay, and X.25 networks. Virtual circuits are used in wide area networks (WANs) to increase efficiency by forwarding packets using circuit identifiers rather than routing packets using physical or logical addresses. The basic procedure is that once a circuit has been established between two stations, the circuit is assigned a circuit identifier (a number) that is then included in the header of every packet sent by the stations. All packets having this identifier are automatically forwarded by switches over the predefined circuit path without the need to add source or destination addresses to the packets (virtual circuits are point-to-point links and as a result do not need addressing). Using small circuit identifiers means less protocol overhead in packet headers and faster forwarding of packets.

Types

There are two basic types of virtual circuits:

- **Permanent virtual circuit (PVC):** Here the communication management station (the telco’s central office) sets up the switches manually ahead of time and the circuit is always on. This type of virtual circuit provides performance comparable to dedicated (leased) telco lines, but it is generally a costly solution for building WANs because PVCs require carrier resources (switches) to be dedicated to a circuit, whether or not that particular circuit is being used.
- **Switched virtual circuit (SVC):** Here the switches are set up automatically when either end station attempts to establish a communication with the other. Once the session is finished, the circuit is torn down and the carrier switches are freed for other uses. Ordinary telephone communication on the circuit-switching Public Switched Telephone Network (PSTN) essentially functions in this fashion.

ATM networks can be implemented using either permanent or switched virtual circuits, as can older X.25 packet-switching networks. Frame relay generally supports only PVCs, although a few providers have begun to offer SVCs. Because an SVC does not require dedicated carrier resources, they can be billed according to usage, which can save companies money.

See Also: *Asynchronous Transfer Mode (ATM), circuit-switched services, frame relay, packet switching, Public Switched Telephone Network (PSTN), wide area network (WAN), X.25*

virtual directory

A directory that appears to Web browser users to be a subdirectory of a Web site's home directory.

Overview

Although a virtual directory behaves as if it were a subdirectory of the home directory, in fact it might be located in a different folder, drive, or server. The advantage of using virtual directories is that content does not need to be stored only on the Web server—it can be distributed on other servers throughout the Web provider's network. These servers can be located at secure, strategic locations for easy access by Web content developers. The disadvantage is a slight degradation in performance due to data being transmitted over the network.

Virtual directories are supported by Internet Information Services (IIS) on Microsoft Windows 2000, Windows XP, and Windows .NET Server.

Examples

For example, consider a user accessing a Web site by using the following Uniform Resource Locator (URL): *www.microsoft.com/otherstuff/file.htm*.

The directory *otherstuff* appears to the user to be a real subdirectory of the home directory *www.microsoft.com*, while in fact it could be a virtual directory that is mapped to a share on a different server on the Web provider's network.

See Also: *Internet Information Services (IIS), Web server*

virtual hosting

Also called reverse hosting, an extension to reverse proxying that is supported by Microsoft Internet and Acceleration (ISA) Server.

See: *reverse hosting*

V

virtual LAN (VLAN)

A group of ports on an Ethernet switch that behaves like a separate network segment.

Overview

The simplest form of a large Ethernet network is one built using only hubs arranged in a cascaded star topology. For example, in a building there might be one workgroup hub for each work area connected to a root hub in the wiring closet. Such a network has two drawbacks:

- The entire network is one collision domain, which causes the network to scale poorly as the number of hosts increases. Once a certain number of hosts are present on the network, collisions start to occur frequently and network bandwidth is wasted.
- The entire network is also one broadcast domain, which increases the probability of broadcast storms occurring and bringing down the network.

The first problem, that of collisions, is usually dealt with by replacing the main or root hub with an Ethernet switch, specifically a Layer 2 switch. This has the effect of partitioning the network into multiple smaller collision domains, which in this example means that each work area will be a separate collision domain. This reduces the overall effect of collisions on the network and isolates problems arising from too many collisions occurring in one area from other parts of the network.

Unfortunately, this simple solution does not solve the second problem, that of broadcasts. In a cascaded star topology where workgroup hubs are connected to a Layer 2 switch, the entire network is still one large broadcast domain, which increases the risk of broadcast storms. Furthermore, if network services are running that advertise themselves using broadcasts, then a significant amount of overall bandwidth might be consumed by these broadcasts, reducing the amount of available bandwidth for other forms of network communications.

The traditional solution to this problem has been to use routers to partition the network into multiple smaller broadcast domains, insofar as routers generally do not forward broadcasts between their interfaces. This works well, but as the network increases in size, the number of network devices (hubs, routers, and switches) increases also, which leads to greater infrastructure costs. Another problem with this traditional style of network is that when a user moves to a different work area and takes his or her computer along to the new area, then some recabling is usually necessary. For example, when the user connects the computer to the local area network (LAN) drop in the new work area, the administrator usually has to go to the wiring room and switch the ends of the old and new LAN drop plugs to make sure the user is connected to the right hub or switch. Because cabling is typically somewhat disorganized in wiring rooms, this task can be a nightmare and is prone to error.

Virtual LAN (VLAN) technologies were developed to solve all these problems. VLANs allow networks to be segmented logically without having to be physically rewired. Instead of having all ports on a switch be equal and belong to the same network, ports can be segregated into groups, each belonging to a separate logical network. For example, on a 3-port switch you could configure ports 1 and 2 as belonging to network 10 and port 3 as belonging to network 20 (see the illustration on the following page). Physically, all three ports seem to be on the same network, but in reality they are not—broadcasts sent to port 1 can only reach port 2 and not port 3. Administrators can easily make these port assignments indicating which VLANs are mapped to which ports by accessing the software for the switch. Note that VLAN ports do not have to be contiguous—for example, ports 1 and 3 could be on the same VLAN and port 2 on a different VLAN.

The benefits of using VLAN-enabled switches include

- The ability to segment networks into multiple smaller broadcast domains without needing additional network devices such as routers to do this. VLANs make switched Ethernet networks more bandwidth-efficient through this segmentation of broadcast domains.
- The ability to reconfigure ports logically without needing to unplug wires and move them around. If a user takes his or her computer to a new work area, no cables need to be swapped on the switch—just access the switch software and issue commands to change the VLAN assignments for the old and new ports. VLANs thus simplify the process of adding, moving, and deleting users on the network. They also improve network security by avoiding cabling mishaps that can arise when users are moved in traditional Ethernet networks.
- The ability to group users together according to function rather than physical location. In a traditional Ethernet network, all users in a given work area are on the same network segment regardless of their job description or department. Using VLANs, however, you could have one salesperson in each work area of the building sitting next to engineers in their work area, yet on a separate logical network segment.

Implementation

VLANs have the following characteristics:

- One switch may have several VLANs defined on it. A VLAN is identified using a special identification number called a VLAN ID. Stations attached to switch ports having the same VLAN ID act and function as though they are all on the same physical network segment. In other words, broadcasts sent by one host are received only by hosts connected to ports having the same VLAN ID as the sending host. Administrators typically assign VLAN IDs manually at the port level, although port assignments can also be managed dynamically for some switches (the switch does this by maintaining an internal table mapping the media access control [MAC] addresses of connected stations to their VLAN ID). When a host is moved to another department, the only change needed is the assignment of a different VLAN ID to the port to which the host is connected—no switching of patch cables is required.


VLAN IDs
30
20
10
(Shaded nodes constitute VLAN 10)
Servers
Switch
Switch
30
20
20
Workstations
Switch
30
30
10
Workstations
Switch
20
10
10
Workstations

Virtual LAN (VLAN). *A simple example of a network designed using VLAN-enabled switches.*

- A single VLAN can span multiple switches connected together. By using a method called trunking, VLAN-enabled switches can be connected to form large VLANs spanning switches right across the enterprise. To do this, a port on the switch must be designated a trunk port, and trunk ports on different switches are connected using trunk lines. For example, when Fast Ethernet ports are used as trunk ports, trunking can be accomplished by connecting such ports on different switches using enhanced Category 5 (Cat5e) crossover cables.

Switch vendors have traditionally developed their own proprietary VLAN technologies, so implementing a VLAN typically means buying all your switching gear from a single vendor. Cisco Systems is the market leader in VLAN-enabled switches, and many of their Catalyst line of switches support VLANs. Cisco Catalyst switches employ several types of technologies in order to implement enterprise VLANs, namely:

- **Frame tagging:** When an Ethernet frame enters a port on a VLAN-enabled switch, the switch encapsulates the frame by adding a special header or tag that contains the VLAN ID of the port at which the frame arrived. The switch uses the frame tag to determine which ports it can be forwarded to (ports having the same VLAN ID). The tag is then stripped off at the destination ports on the switch, or in the case of traffic moving across multiple switches using trunked connections, it is stripped off when it reaches the destination ports on other connected switches.

- **Inter-switch link (ISL):** This is a proprietary Cisco technology that enables a single port to belong to multiple VLANs—that is, to have multiple VLAN IDs assigned to it. ISL is used for trunking and is also available on special network interface cards (NICs) for servers. When a server has an ISL-supporting NIC installed, it behaves as if it had multiple physical NICs, one for each VLAN. This enables workstations on different VLANs to access the same server, eliminating the need to have separate servers for each VLAN.
- **VLAN Trunking Protocol (VTP):** This is a proprietary Cisco technology that simplifies the task of configuring VLANs across a network. By making any necessary configuration changes to settings on a VTP server, these changes are then propagated across the network to all VLAN-enabled switches that are defined as belonging to the same VTP management domain.

Issues

Three main issues have slowed the acceptance of VLANs in the enterprise: standards, Dynamic Host Configuration Protocol (DHCP), and Layer 3 switches. The problem of standards arises from the proprietary nature of VLAN implementations from different switch vendors. This has resulted in interoperability issues where equipment from one vendor fails to work with that from another vendor. There has been some progress toward standardizing VLAN technologies, however. One important step was the development of the 802.1Q standard from the Institute of Electrical and Electronics Engineers (IEEE), which replaces Cisco's proprietary ISL technology with a standards-based solution. Another development has been the adoption of RFC 2878 by the Internet Engineering Task Force (IETF), which standardizes VLAN frame tagging using the new VLAN Tagged Frame format. RFC 2878 also provides guidelines for switch vendors to improve interoperability with regard to signaling, link aggregation, and Layer 2 traffic prioritization.

The second issue is that of address management of stations on the network. VLANs were originally designed to simplify the management of hosts on the network by using their Layer 2 MAC addresses to identify them to switches. When a computer is unplugged from a LAN drop and moved to a different physical location and plugged in to a different drop, VLAN switches can automatically detect the computer's new location by its MAC address and reconfigure themselves dynamically. The problem is that DHCP was designed for the very same job of dynamic address management but uses Layer 3 (IP) addresses instead. Being a much simpler system, most network managers have chosen DHCP instead of VLANs to ensure that computers can be physically moved around the network if needed. As a result, most VLAN administration is performed manually by assigning VLAN IDs to ports using a command-line interface, a difficult chore in a large enterprise.

The third issue that has slowed the adoption of VLANs has been the emergence of Layer 3 switches, which can perform both bridging (Layer 2) and routing (Layer 3) functions in one box. Layer 3 switches have almost eliminated the need for VLANs in most enterprises. Instead of creating multiple VLANs to segment the network into smaller broadcast domains, the same thing can be accomplished by replacing the root Layer 2 switch with a Layer 3 switch. Each port on the Layer 3 switch represents a separate routed subnet, and the network is thus automatically partitioned into separate broadcast domains.

Prospects

Because of the above issues, the future of VLANs is cloudy. Most enterprise network architects see little point in deploying VLANs when Layer 3 switches can accomplish the same result with less effort. And DHCP manages addresses at Layer 3 more easily than VLANs do it at Layer 2, making it simple to move users around the network. Nevertheless, there has been something of a resurgence of interest in VLANs recently, mainly in the service provider market where companies such as Yipes Communications that offer metropolitan Ethernet use VLAN-enabled switches from Extreme Networks to provision metropolitan area VLANs for their customers. Another growing use of VLANs is in the Web hosting arena, where these companies are using VLANs to help isolate traffic between different subscribers.

See Also: *802.1Q, broadcast domain, collision domain, Dynamic Host Configuration Protocol (DHCP), Ethernet switch, hub, Institute of Electrical and Electronics Engineers (IEEE), Internet Engineering Task Force (IETF), IP address, Layer 2 switch, Layer 3 switch, MAC address, router*

virtual memory

A mechanism by which applications function as though the system has more random access memory (RAM) than it actually does.

Overview

Virtual memory is designed to improve the performance of applications by providing them with greater effective memory than physical RAM provides. Virtual memory works by paging unneeded code from running applications to a file on the hard drive called the page file. In Microsoft Windows 2000, Windows XP, and Windows .NET Server, the Virtual Memory Manager maps the virtual addresses belonging to the address space of a running process to physical pages of memory in the computer. This ensures that each process has sufficient virtual memory to run efficiently and does not trespass on the memory of other processes. The Virtual Memory Manager handles paging between RAM and the page file, swapping pages by using a process called demand paging. The result is that each application has access to up to 4 gigabytes (GB) of memory. A similar process in Windows 98 and Windows Millennium Edition (Me) uses a comparable structure called the swap file.

Virtual memory is also supported by UNIX platforms and the Mac OS X platform.

virtual private network (VPN)

A technology for securely connecting a computer or network to a remote network over an intermediate network such as the Internet.

Overview

The term *virtual private network (VPN)* is used in various senses in the industry to describe a variety of technologies, but in essence it can have one of two meanings:

- Using an insecure public network such as the Internet to connect two networks (or to connect a network and a remote computer)
- Making this connection secure by employing technologies such as tunneling, authentication, and encryption

The two main types of VPNs are

- **Network-network:** A branch office network of an enterprise is connected by a VPN to corporate headquarters. Network-network VPNs offer a low-cost alternative to deploying expensive dedicated leased lines such as T1 lines at all branch offices (corporate headquarters still requires a leased line for its VPN gateway, however, to provide enough bandwidth for its branch office VPN connections). In spite of the cost advantage, however, network-network VPNs have been slow to gain a foothold in the enterprise due to the proven reliability of leased lines and the relative unreliability of the Internet in comparison.
- **Host-network:** A mobile knowledge worker uses his or her laptop or Personal Digital Assistant (PDA) and modem to dial in to a local Internet service provider (ISP) to connect securely to a company intranet or portal using an encrypted VPN connection. Using VPNs this way has proliferated in the enterprise as it is more cost-effective than traditional remote access solutions involving modem pools, dedicated phone lines, and toll-free numbers.

Architecture

VPNs are based on a client/server architecture:

- **VPN client:** This system initiates the VPN connection with the VPN server. For a typical host-network VPN scenario, the remote user first establishes a dial-up connection with a local ISP to connect to the Internet, and then once online, the client contacts the VPN server to connect to the corporate intranet.
- **VPN server:** This system authenticates the VPN client, negotiates which tunneling and encryption protocols to use, and establishes the secure VPN connection. The result is the formation of a secure encrypted tunnel that connects the VPN client to the VPN server. The effect is transparent—that is, as if both client and server were on the same local area network (LAN). For the connection to work, however, the VPN client must be assigned an Internet Protocol (IP) address that makes it appear to the VPN server as if it is on the same LAN as the server. VPN clients thus generally have two IP addresses, one for the VPN connection and one for the intermediate or transit network (the Internet).

Two VPN tunneling protocols are in use today: Microsoft Corporation's Point-to-Point Tunneling Protocol (PPTP) and Cisco Systems' Layer 2 Tunneling Protocol (L2TP). Both protocols are essentially extensions of the industry standard Point-to-Point Protocol (PPP) and are used to encapsulate PPP frames within IP datagrams for transmission over the Internet. In other words, VPNs employ two layers of encapsulation:

- First the IP datagrams from the client and server are encapsulated with PPP headers to form PPP frames for transmission through the serial interface to the modem or leased line.
- Then the PPP frames are encapsulated again with IP headers (and PPTP or L2TP headers) to form IP packets for routing over the Internet.

The result of using PPTP or L2TP is to create a virtual PPP connection between the VPN client and server. In short, the VPN connection behaves as if it were a dedicated point-to-point serial link but packets are actually routed across the Internet.



Virtual Private Network (VPN). *How a VPN connection works between a network and a remote host.*

Note that L2TP does not include a mechanism for encrypting VPN communications, so it must be combined with Internet Protocol Security (IPsec) when used to create a VPN connection.

Implementation

VPNs are typically implemented in one of two ways:

- **Customer premises equipment (CPE):** Here the VPN server is owned and operated by the private company and is located at the periphery of their corporate LAN. Such VPN servers may be routers, access servers, firewall appliances, or standard PC servers running VPN-enabled software such as Microsoft Windows 2000 Server.
- **Service provider:** Corporate VPN needs can also be outsourced to VPN service providers, typically telcos, ISPs, or application service providers (ASPs). The service provider maintains the VPN server at the edge of its own network and parcels out VPN services to companies on a monthly leased basis. In this scenario the customer only requires a standard "dumb" router for Internet access at its end, not a VPN-enabled router.

A third kind of VPN implementation involves using permanent virtual circuits (PVCs) carrying IP over public frame relay networks. This method is employed mainly for enterprise network-network VPNs.

Marketplace

A popular Linux-based VPN/firewall appliance is VelociRaptor from Cobalt Networks, which employs Cobalt's hardware and Raptor's firewall software to provide a secure VPN solution for the small business and remote office markets. Another popular VPN appliance is the Alcatel 7137 Secure VPN Gateway, originally developed by TimeStep (now part of Alcatel). Cisco Systems offers many different VPN-enabled routers and access servers, including the Cisco VPN 3005 Concentrator, which supports up to 100 concurrent users. For the Small Office/Home Office (SOHO) business environment, the Cisco PIX Firewall 506 is a small unit the size of a pocketbook that can support 10 simultaneous VPN connections. Another market contender is the VPN-1 Appliance from Check Point Software Technologies, which includes their widely used Firewall-1 product bundled in a Nokia appliance. Check Point also offers a VPN-1 Gateway for high-end corporate VPN connectivity. 3Com Corporation, Avaya, CoSine Communications, Data Fellows Corporation, Indus River Networks, Intel Corporation, Lucent Technologies, RadGuard, RedCreek Communications, and many other companies offer VPN solutions ranging from VPN gateways and appliances to software products.

Examples of service providers offering standard IP VPN services include Aventail Corporation, Genuity, UUNET, Qwest Communications International, and others. Providers of frame relay-based VPN services include AT&T, Equant, Infonet, MCI/Worldcom, Sprint Corporation, and others. Telera offers a nationwide Voice over IP (VOIP)-enabled managed VPN that employs VPN gateways stationed at colocation centers around the United States.

Prospects

The future of network-network VPNs and corporate host-network VPN gateways may be Digital Subscriber Line (DSL), a technology that provides high-speed Internet access at costs vastly lower than leased lines such as T1 lines. The main issue with most enterprises is that DSL has yet to prove itself as reliable a technology as the more costly leased lines, which are a mature technology that has been around for many years. Nevertheless, the combination of a DSL connection with VPN software to provide security is a tantalizing one for IT departments in times of shrinking budgets.

Notes

Although VPNs typically use the Internet as their transit network, it is also possible to run a VPN over a corporate IP LAN to create a "LAN within a LAN" for secure communications across the network.

For More Information

Visit the VPN Consortium at *www.vpnc.org.*

See Also: *application service provider (ASP), Digital Subscriber Line (DSL), firewall, frame relay, Internet, Internet Protocol Security (IPsec), Internet service provider (ISP), Layer 2 Tunneling Protocol (L2TP), permanent virtual circuit (PVC), Point-to-Point Protocol (PPP), Point-to-Point Tunneling Protocol (PPTP), T1, wide area network (WAN)*

virtual server

A technology that allows multiple independent Web sites to be hosted on a single Web server.

Overview

The term *virtual server* is another name for Web site. Internet Information Services (IIS) on Microsoft Windows 2000 and Windows .NET Server supports virtual servers to enable a single machine to host multiple Web sites. Virtual servers can be implemented three different ways in Windows 2000:

- By binding Internet Protocol (IP) addresses to the server's network interface card (NIC). Each virtual server can be assigned its own unique IP address. DNS servers can then resolve domain names into their respective IP addresses, allowing multiple companies to host their Web sites on a single IIS server. This is the preferred method if a large pool of available IP addresses exists for the server.

- By using a single IP address but assigning a unique port number to each virtual server. Clients must know the exact port number to connect to the server instead of using the default Hypertext Transfer Protocol (HTTP) port number 80.
- By enabling host headers on the IIS server. The server has only one IP address and uses the default HTTP port number 80. The client Web browser attempting to access a Web site on the IIS server must be HTTP 1.1–compliant to seamlessly access the site.

Notes

The term *virtual server* is also used in the Windows Clustering component of Microsoft Windows 2000 Server. In this context a virtual server is usually a resource group that contains all the resources necessary for running an application, including the network name and IP address resources.

See Also: *bindings, Hypertext Transfer Protocol (HTTP), Internet Information Services (IIS), IP address, virtual directory, Web server*

virus

A program designed to infect computer systems.

Overview

Viruses are generally malicious programs created to cause damage or annoyance to computer users. The effects of viruses range from harmless but annoying messages announcing the presence of an “infection” to malicious corruption or deletion of crucial operating system and data files.

Although the term *virus* is generally used to refer to any form of malicious code, technically viruses that infect computer systems do so by attaching themselves to executable files, and when these files are executed the virus spreads to other files or causes various forms of damage such as lost or corrupted data. Some other related forms of “malware” (malicious software) include

- **Worm:** Code that infects a machine and then spreads itself to other machines on the network. Worms do not need a host application to attach themselves to as viruses do. Some worms also multiply on host machines and cause various forms of damage to operating system or user files similar to that which viruses cause.
- **Logic bomb:** Code that executes when certain conditions occur—for example, on a specific date of the month or year. Logic bombs are really a form of virus or worm, depending on what actions they perform when the trigger.
- **Trojan:** Code that masquerades as a legitimate application, usually to trick users into divulging their credentials or other sensitive information.
- **Hoaxes:** These are not viruses at all but simply threats of viruses. This might seem innocuous, but many industry analysts say that enterprise administrators often spend more time dealing with these hoaxes than in eradicating actual viruses, and in a business environment any time wasted is money wasted.

Viruses have many entry points in today’s enterprise networks, including Internet connections, remote access connections, electronic mail, and users downloading and saving software from the Internet onto floppy disks and taking these disks to work to install the software on their office machines.

History

The first recorded PC virus was the Pakistani Brain virus detected in 1987. Since then tens of thousands of different “strains” of viruses have been detected over the years, and the rate at which new viruses are appearing is accelerating, mainly as a result of the widespread availability over the Internet of scripts that can be easily assembled to form new types of viruses. Some of the better-known viruses in the history of malware include

- **Jerusalem virus:** This virus, which appeared in 1990, was an .exe file that trashed the boot sector of machines it infected. It was widespread for almost five years before being eradicated and is estimated to have caused more than $50 million in damage during its lifetime.

- **Concept virus:** This macro virus for Microsoft Word caused about $50 million in damage before it was eradicated about four months after its appearance in 1995.
- **Melissa virus:** This Word macro virus appeared in 1999, was spread by e-mail, and caused an estimated $300 million in damage worldwide.
- **"I Love You" virus:** This VBScript virus appeared in 2000 and was also propagated by e-mail and caused an estimated $700 million in damage in less than a week.

Types

Common categories of viruses include the following:

- **File virus:** These are standard viruses that reproduce by attaching themselves to executable files such as .exe, .cmd, and .bat files. When the executable file is run, the virus code is executed, causing the virus to reproduce itself and inflict whatever form of damage the virus developer intends.
- **Boot-sector virus:** These are viruses that infect the boot sector of a floppy or hard disk and execute when the operating system is booted. They can cause various types of damage, including the total disabling of computer systems. Notorious boot viruses have included the Michelangelo virus and the Stoned virus. A related type of virus is the Master Boot Record (MBR) virus, which infects the system's MBR.
- **Polymorphic virus:** This type of virus modifies itself as it reproduces, causing its signature to change and making it difficult to detect by standard virus protection software unless the specific evolution algorithm is known.
- **Macro virus:** This is an increasingly popular form of virus consisting of a macro writing in Visual Basic for Applications (VBA) or some other scripting language and designed to execute within a word processing or spreadsheet applications such as those included in Microsoft Office. The malicious macro is inserted into a harmless document, the document is sent as an e-mail attachment to a user, and when the user opens the document the macro is executed and the virus infects the system, typically with the result that data is lost or corrupted.

Implementation

Viruses generally consist of two components:

- **Propagation mechanism:** This is code that, when executed, causes the virus to copy itself to other files on the system.
- **Payload:** This code generates the virus's effect, which may range from harmless messages appearing on the system to the entire operating system being wiped out.

Virus protection software guards enterprise computer systems from the danger of viruses by scanning potential virus-bearing files and prompting the deletion of these files. Virus protection software consists of two components:

- **Virus signature:** This is a file containing small portions of every known virus, and is used as a template for comparison with files for detection of virus infection. Virus signature files for virus protection software must be updated frequently, otherwise new types of viruses will not be detected and will cause damage to the system.
- **Search engine:** This software compares the signature file with other files on the computer to determine which files might be infected with a virus.

Marketplace

The market leaders in virus protection software include Computer Associates, McAfee, Sophos, Symantec Corporation, and Trend Micro. Popular products include Norton AntiVirus from Symantec and VirusScan from McAfee.

Prospects

Viruses seem to be an inevitable fact of life for computer users, and protecting against them is essential for any enterprise connected to the Internet. The earliest viruses were spread from user to user by swapping floppy disks. In the mid-1990s, Word and Microsoft Excel macro viruses became the bane of the office productivity worker, and many enterprises disable macros for these applications to prevent users who open e-mail attachments containing macro viruses from infecting the network. The trend at the beginning of the new millennium seems to be that e-mail viruses are the ones to fear most—many companies have had their messaging systems brought to their knees for days as a results of infections by the Melissa and I Love You viruses, and some have even shut down their in-house mail systems and begun outsourcing their messaging needs from application service providers (ASPs) or Internet service providers (ISPs) who have dedicated resources for combating such viruses when they appear. Some of the more popular ASPs offering virus-protected messaging services include Critical Path and MessageClick.

Some of the newer developments in the virus realm include

- Viruses spread by nonstandard means, such as through multimedia files. By simply visiting a Web site that automatically starts a media player application to play the file, it is possible to infect your machine with a virus. Be sure to download the latest patches from your media application vendor to reduce the chance of infection through this method.
- Viruses that target wireless devices such as cell phones and wireless Personal Digital Assistants (PDAs). The first known example was a Trojan called Liberty Crack, which infected wireless Palm Pilot systems, causing applications to be deleted on the systems. A number of vendors are working to address this critical area, including F-Secure, Finjan Software, McAfee, Symantec, and Trend Micro.

Notes

To keep viruses from proliferating on your network, you can take the following measures:

- Install virus protection software on each computer in your network and keep their virus signature files up to date at all times. This applies especially to desktop computers, file servers, and mail servers, as these types of machines are the most vulnerable. Enterprise virus protection software usually includes mechanisms for automatically updating signature files on machines across a network.
- If you have Internet connectivity, be sure that your virus protection software scans for viruses in Web content downloaded from the Internet and in attachments to Simple Mail Transfer Protocol (SMTP) e-mail messages. Many newer viruses can be downloaded from Web sites or received as attachments to e-mail messages. When the attachments are opened, the machine is infected and the virus begins to spread.
- Regularly perform backups of all-important servers and include periodic archives in your backup schedule, because many viruses do not activate for weeks or months after infection.
- Scan new computers for infection before bringing them onto the network.
- Issue a company policy prohibiting users from installing any personal programs on their desktop computers. You might even disable their floppy drives, because infection by means of a floppy is a common route to virus infection. Some companies go so far as to prevent or prohibit users from sending or receiving attachments to their e-mail, a draconian but effective measure in curbing the spread of viruses.

For More Information

You can visit the McAfee Virus Information Center at *www.mcafee.com/centers/anti-virus.*

See Also: *application service provider (ASP), e-mail, hacking, Internet service provider (ISP), network security, Personal Digital Assistant (PDA), security, Simple Mail Transfer Protocol (SMTP)*

VLAN

Stands for virtual LAN, a group of ports on an Ethernet switch that behaves like a separate network segment.

See: *virtual LAN (VLAN)*

VLSM

Stands for variable-length subnet mask, a technique for conserving Internet Protocol (IP) addresses.

See: *variable-length subnet mask (VLSM)*

Voice over IP (VoIP)

An umbrella term for a set of technologies that allow voice traffic to be carried over Internet Protocol (IP) networks such as the Internet.

Overview

Voice over IP (VoIP) is one of the driving forces behind convergence in the networking and telecommunications industry. The term *convergence* refers to the goal of combining all forms of enterprise communications (voice telephony, fax, and data) into a single IP data stream and managing this through a single integrated system. The goal of convergence is twofold:

- To reduce costs by eliminating redundant infrastructures. For example, the typical corporate office building has two separate wiring infrastructures: voice telephony wiring and Category 5 (Cat5) or enhanced Category 5 (Cat5e) twisted-pair network wiring. Similarly, large enterprises spanning several geographical locations often have two communication infrastructures as well: Private Branch Exchanges (PBXs) linked by dedicated tie lines and leased lines for wide area networking (WAN). VoIP enables an enterprise to consolidate these two systems into a single communications infrastructure running on an IP data network, with resultant cost savings.
- To simplify management of all forms of business communication (such as e-mail, voice mail, and faxes) by consolidating all messages into a single user interface, typically in the user's e-mail Inbox.

To achieve these two goals of convergence, VoIP addresses the first issue and unified messaging (UM) addresses the second. These systems may be deployed separately or together in the enterprise, depending on business needs and goals.

Advantages and Disadvantages

Although VoIP promises to save enterprises money by avoiding costly long-distance toll charges, the expertise needed to implement VoIP and the cost of new equipment is often seen as a barrier to embracing this new technology. Other concerns often voiced by network managers include

- **Latency:** Because of the best effort nature of IP communications, voice communications sometimes sound garbled and contain undesirable pauses due to high jitter and latency. This is probably the number one issue that companies consider when choosing a VoIP solution. The problem is especially bad when IP traffic is routed over the public Internet, where VoIP conversations can sound like old CB radio sessions in quality. Improvements in IP quality of service (QoS) discussed below are reducing the importance of this issue, but these IP QoS solutions are complex and difficult to implement.
- **Interoperability:** Because there are competing VoIP standards and vendors have developed their own proprietary solutions, when a company adopts a VoIP plan it must essentially use equipment from only one vendor. Even simple IP phones with RJ-45 Ethernet jacks from one vendor usually do not work with VoIP systems from another vendor. In contrast, traditional PBXs and digital telephones from different vendors interoperate seamlessly. If a dominant VoIP standard emerges over the next few years, however, this interoperability problem might finally be resolved.
- **Cost:** Companies that have already invested heavily in legacy PBXs, digital phone systems, and "dumb" routers might be reluctant to abandon them to deploy all-new VoIP switching, routing, telephones, and call control equipment. The cost of the expertise needed to implement and maintain VoIP solutions must also be considered.

Despite these concerns, VoIP is encroaching steadily into large companies and will probably overtake the legacy PBX market in the next five years if trends continue.

Architecture

Most VoIP solutions developed by different vendors are still proprietary solutions that require all customer premises equipment (CPE) to be purchased or leased from a single vendor, but recently there have been moves toward standards-based VoIP solutions that should eventually allow equipment from different vendors to interoperate in a plug and play (PnP) fashion.

The main problem at this point is that competing standards have evolved in the VoIP arena, and it is still unclear which standards will dominate in the emerging VoIP industry. The main standards and protocols of relevance to VoIP are:

- **H.323:** The earliest VoIP systems were based on the H.323 and T.120 of protocols developed by the International Telecommunication Union (ITU) for audio, video, and data communication and conferencing over IP networks. H.323 works well but is complex to implement—a typical H.323 VoIP system includes end-user stations known as VoIP terminals, gateways for translating between IP networks and telephony networks, gatekeepers for handling calling functions, and multipoint control units (MCUs) for handling multipoint conferencing. In addition to its complexity, H.323 also suffers from considerable protocol overhead because it was originally designed to support video communications. Nevertheless, most VoIP vendors have built their systems around H.323, and it is still considered the primary standard for interoperability between different VoIP systems.
- **Session Initiation Protocol (SIP):** This is an application-layer control protocol defined in RFC 2543 that is designed to allow different telephony, data networking, and VoIP equipment to communicate with one another. SIP is a lightweight protocol with much less overhead than H.323 and is seen by some industry analysts as the logical successor to H.323.
- **Media Gateway Control Protocol (MGCP):** This protocol is defined in RFC 2705 and is designed to translate between the voice traffic carried on the Public Switched Telephone Network (PSTN) and IP traffic carried on the Internet. MGCP is a master/slave protocol that enables media gateway controllers and media gateways to communicate with each other and to control IP telephony terminal equipment. MGCP has been implemented in some VoIP systems but is being phased out in favor of the newer Megaco/H.248 standard.
- **Megaco/H.248:** This protocol is a joint effort of the Megaco working group of the Internet Engineering Task Force (IETF) and the ITU-T Study Group 16. Megaco/H.248 is the successor to MGCP and includes additional features that support peer-to-peer communication and simplified implementation of media gateways and controllers.

For more information on the different VoIP protocols, see the individual entries about them elsewhere in this book.

Implementation

VoIP is all about saving cost for companies, and there are a variety of ways in which it can be implemented using the various architectures outlined previously. One important scenario is for linking offices to eliminate long-distance calling costs. The traditional way for companies to do this has been to connect the PBXs in two offices using tie lines. A tie line is a dedicated connection used for both signaling and call transfer between PBXs. This approach is called a “toll bypass” solution because it bypasses the tolls levied for traditional long-distance traffic, in effect emulating a “toll-free” solution.

Tie lines are usually implemented over T1 lines. For offices relatively near each other, the monthly cost of leasing T1 lines for this purpose can be less than the accumulated cost of a month’s long-distance calls between the offices, but when the distance between offices is great, the T1 line costs become excessive as they are billed by the mile for most U.S. telcos. Another problem is that a separate tie line must be deployed between each pair of offices—calls cannot be routed across multiple call lines.



① Using VoIP for toll bypass between branch offices

② General VoIP solution using Cisco AVVID

Analog phones
LAN
PBX
Router
T1
T1
Router
LAN
PBX
Analog phones
PBX
Analog phones
Router
LAN
Windows 2000 server running Cisco Call Manager
Cisco Catalyst 6009 with voice T1 modules
IP phones
LAN
Computers
PSTN

Voice over IP (VoIP). *Two common types of VoIP solutions.*

VoIP can save costs in this situation by routing voice traffic over existing data lines between offices, also typically T1 lines for large companies. This means instead of needing two T1 lines between offices (one for data and one for tying PBXs together) companies need only one line (voice and data combined). In addition, companies do not need T1 lines between every pair of offices (full mesh topology), as IP packets can be routed across the enterprise provided there is at least one path between each pair of offices (partial mesh).

A more general VoIP solution is to replace existing PBXs with VoIP-enabled routers that perform gateway and gatekeeper functions to handle call setup and routing. One hidden cost in this "all-IP" approach is that traditional digital phones costing about $50 must be replaced by special IP phones often costing hundreds of dollars. This approach to VoIP, championed by Cisco Systems, is sometimes called an IP PBX approach since it completely replaces existing legacy PBX systems. Companies that have invested heavily in legacy PBX equipment may be reluctant to follow this route also and may instead prefer to use VoIP for replacing PBX tie lines to continue leveraging their investment in legacy equipment. Alternatively, some VoIP vendors such as Nortel Networks offer a VoIP gateway approach that let the legacy PBXs continue to handle call processing while line-provisioning is performed by specialized VoIP routers and servers.

Marketplace

Cisco has been the dominant player in the high-end enterprise VoIP market for some time. In fact, Cisco itself uses VoIP across its company, and with more than 10,000 IP phones deployed around the organization, this is still probably one of the largest and most successful VoIP implementations around. Cisco has developed a special architecture for VoIP solutions called Architecture for Voice, Video, and Integrated Data (AVVID) that consisting of three layers: switching and routing infrastructure for routing IP traffic, applications such as Cisco Call Manager running Microsoft Windows 2000 servers for implementing call control, and wired or wireless IP telephones. In the infrastructure area, for example, Cisco 2600, 3600, and AS5300 routers and Cisco Catalyst 6009 switches all support the H.323 standards and can function as H.323 gateways and gatekeepers for building highly scalable VoIP solutions. Cisco's AVVID architecture is straightforward in concept and can effectively scale to more than 100,000 users to meet the needs of the largest enterprise.

The approach taken by Avaya, which, together with Nortel, represents the two dominant players in the legacy PBX market in the United States, is adapted specifically to its own proprietary line of PBX equipment, and scales to 10,000 users for large VoIP deployments. The advantage here is that Avaya offers a clear upgrade path from using its legacy PBXs to move to an all-IP telephony solution. Nortel's Call Pilot solution also supports up to 10,000 users and is popular in Europe but just emerging in the U.S. market. Another large player is Alcatel, whose VoIP solution supports legacy PBX connections and whose call control applications run on UNIX platforms. Alcatel even offers an IP Telephony Starter Kit to enable small companies to quickly and painlessly roll out a VoIP solution. This kit includes an Alcatel OmniStack 6024 Ethernet switch, an OmniPXC 4400 IP PBX, and 10 IP Reflex telephones.

Some larger telecommunication carriers such as AT&T and WorldCom are now offering their own VoIP solutions using Cisco 2600 and 3600 routers deployed at the customer premises in a VoIP gateway approach. AT&T integrates its VoIP solution with Internet access and virtual private network (VPN) support to provide an all-in-one communications infrastructure solution for its customers.

Notes

Despite the great attention garnered by VoIP in the press, other technologies also can serve well for various needs in the enterprise, namely:

- **Voice over frame relay (VoFR):** Standards for this technology are more mature than for VoIP, and VoFR is a good option to consider for replacing tie lines between PBXs in branch offices. Instead of connecting branch offices in pairs using dedicated point-to-point T1 lines, frame relay assembler/disassemblers (FRADs) are used to connect all the offices using the carrier's frame relay cloud. VoFR then multiplexes voice traffic and compresses them into packets and routes them between each pair of offices using permanent virtual circuits (PVCs) preconfigured by the carrier to simulate point-to-point links.

- **Voice over High-level Data Link Control (VoHDLC):** This is another good solution for point-to-point connections, and, like VoFR, it supports multiplexing and compression of voice traffic. The downside here is that HDLC is a Cisco proprietary Layer 2 protocol, so implementing it means you have to go with only one vendor.

The main advantage VoIP has over both of these alternative technologies is scalability—both VoFR and VoHDLC require that voice traffic be encoded and decoded multiple times in transit, and this adds overhead that limits the scalability of these technologies. In contrast, VoIP can be used on IP networks of any size, including the largest of networks, the Internet. The downside of VoIP, of course, is that IP is a best effort packet delivery service with no intrinsic quality of service (QoS). As a result, the quality of voice communications can be poor when using VoIP, especially over a large network such as the Internet, and can result in unacceptable levels of latency, jitter, and dropouts. However, by employing special standards and protocols such as 802.1p, 802.1Q, Resource Reservation Protocol (RSVP), and Multiprotocol Label Switching (MPLS), QoS can be added to IP to the point where voice quality approaches that offered by VoFR, VoHDSL, or even the PSTN.

Another alternative that is used by only a few large companies is Voice over Asynchronous Transfer Mode (VoATM), which provides excellent voice quality since ATM technology has built-in support for QoS. The problem is that to implement VoATM you already need an underlying ATM network connecting branch offices, and only a limited number of large enterprises have implemented ATM across the WAN due to the high cost and complexity of this solution.

An emerging technology gaining a lot of attention is Voice over Digital Subscriber Line (VoDSL), which enables carriers to provision multichannel voice and data communications over Symmetric Digital Subscriber Line (SDSL). Since SDSL is relatively cheap compared to T1 lines, this is an attractive option for certain IP telephony solutions. A typical VoDSL solution involves placing an integrated access device (IAD) at the customer premises, which is connected to both telephone equipment and the computer network. Most VoDSL IADs currently support only 16 voice channels, so this solution is currently marketed mainly toward small and mid-sized businesses. One difficulty is that VoDSL works only with SDSL and does not support the more commonly available Asymmetric Digital Subscriber Line (ADSL) technology. This limits its availability in some areas, but this will still be a technology to watch in the next few years. Vendors of first-generation VoDSL equipment include Copper Mountain Networks, Jetstream Communications, and Tollbridge Technologies.

See Also: *802.1p, 802.1Q, Asynchronous Transfer Mode (ATM), Digital Subscriber Line (DSL), frame relay, Frame Relay Access Device (FRAD), H.323, High-level Data Link Control (HDLC), Internet Protocol (IP), IP PBX, IP telephony, jitter, latency, Megaco, Multiprotocol Label Switching (MPLS), permanent virtual circuit (PVC), Private Branch Exchange (PBX), Public Switched Telephone Network (PSTN), Resource Reservation Protocol (RSVP), session initiation protocol (SIP), Unified Messaging (UM)*

voice profile for Internet mail (VPIM)

An Internet Engineering Task Force (IETF) specification that defines a unified way of transmitting voice mail and fax messages over the Internet.

Overview

Voice profile for Internet mail (VPIM) uses e-mail systems that support Multipurpose Internet Mail Extensions (MIME) and Simple Mail Transfer Protocol Service Extensions (ESMTP) standards for Internet messaging. VPIM can also be deployed over corporate intranets for integrated business messaging solutions. VPIM includes a proposed directory service that enables lookup of routable addresses and includes a mapping specification to support interoperability with other voice messaging systems.

VPIM defines the mechanisms by which voice mail and fax messages can be exchanged between Simple Mail Transfer Protocol (SMTP) mail servers on a Transmission Control Protocol/Internet Protocol (TCP/IP) internetwork. However, VPIM leaves open the way in which specific mail clients interface with these SMTP servers to send and receive voice and fax messages, which will initially be accomplished by implementing VPIM helper applications. VPIM is implemented as a MIME profile, which allows voice and fax information to be encoded using any SMTP mail server that supports MIME. You can implement VPIM by running additional VPIM software on existing SMTP mail servers or by installing VPIM-SMTP gateways on the TCP/IP internetwork. VPIM gateways support messaging between telephones, cell phones, fax machines, pagers, and computers. VPIM will be able to use Lightweight Directory Access Protocol (LDAP) or X.500-based directories for white pages lookup to address messages to users.

Notes

VPIM is supported by the popular UNIX mail forwarder software called Sendmail; other vendors are also implementing VPIM. The current standard, VPIM v2, can be found in RFC 2421, and VPIM v3 is under development.

For More information

Find our more about VPIM at *www.ema.org/vpimdir.*

See Also: *ESMTP, Internet Engineering Task Force (IETF), Lightweight Directory Access Protocol (LDAP), Multipurpose Internet Mail Extensions (MIME), Simple Mail Transfer Protocol (SMTP), X.500*

VoIP

Stands for Voice over IP, an umbrella term for a set of technologies that allow voice traffic to be carried over Internet Protocol (IP) networks such as the Internet.

See: *Voice over IP (VoIP)*

VoIP gateway

A device used in Voice over IP (VoIP) systems.

Overview

A VoIP gateway is a device that allows telephone calls to be transmitted over Internet Protocol (IP) backbone networks by converting voice signals into IP packets and transmitting them over the network. The reverse process then takes place at the other end of the call.

Most VoIP gateways are chassis-based units that have either digital or analog built-in Private Branch Exchange (PBX) interfaces. A device called a gatekeeper keeps track of IP address to phone number mappings for routing calls between different gateways. Built-in local area network (LAN) or wide area network (WAN) interfaces, or both, are included for connecting the gateway to the IP backbone. Some gateways also have built-in routing capabilities. The LAN interface is usually Ethernet, but some gateways support Token Ring. The WAN interface is typically T1 or E1, but smaller gateways designed for Small Office/Home Office (SOHO) environments support Integrated Services Digital Network (ISDN) interfaces. The number of voice interfaces per chassis typically ranges from 72 to 960, depending on the vendor. Voice interfaces are typically the digital signal cross-connect level (DSX-1) type, but some gateways also support the foreign exchange station (FXS) type interfaces for direct attachment of analog telephones.

Notes

When shopping for a VoIP gateway, consider the following points:

- Audio quality should be your primary consideration. The audio quality with low traffic congestion should be close to that of a digital PBX. With heavy traffic congestion, latency and jitter should remain low enough that voice quality is acceptable to average users. A packet loss of 15 percent or more results in transmission with borderline intelligibility; delays of over 700 milliseconds are unacceptable to most users.


Telephones
Digital
PBX
VoIP
gateway
Router
CSU/DSU
T1 line
Telephones
Digital
PBX
VoIP
gateway
Telephones
Digital
PBX
VoIP
gateway
Router
T1 line
WAN
CSU/DSU
Router
IP backbone
LAN

VoIP gateway. *Using a VoIP gateway to implement Voice over IP.*

- Find out what extra features are supported by the gateway, such as dialed number identification service (DNIS) for call routing, automatic number identification (ANI) and caller ID for identifying the incoming caller, and interactive voice response (IVR) for creating telephone menus.
- VoIP gateway technologies are still evolving, so equipment from different vendors might not interoperate, even if the vendors claim to support the H.323 standards of the International Telecommunication Union (ITU). You should therefore buy VoIP from a single vendor, especially if you have an enterprise implementation with many gateways.
- If you are concerned about eavesdropping on voice conversations on IP networks such as the Internet, be sure that your gateways support the H.245 encryption standard. The alternative practice of using a virtual private network (VPN) gateway to encrypt VoIP traffic usually results in additional incompatibility problems. Also be aware that it is difficult to configure a VoIP gateway to operate across a firewall that hides network IP addresses using network address translation (NAT), especially if the traffic is encrypted.

See Also: *Integrated Services Digital Network (ISDN), Internet Protocol (IP), Private Branch Exchange (PBX), Voice over IP (VoIP)*

volume

A bounded amount of disk storage.

Overview

In MS-DOS and early Microsoft Windows platforms, a volume is a portion of a hard disk that can be formatted with a file system and can have a unique drive letter assigned to it. In Windows 2000, Windows XP, and Windows .NET Server, a volume is a logical storage entity composed of portions of one or more physical disks. Volumes can be formatted using the NTFS file system (NTFS) or file allocation table (FAT) and can be assigned a drive letter.

Windows 2000, Windows XP, and Windows .NET Server support two different types of disk storage:

- **Basic storage:** Supported for backwards compatibility with Windows NT version 4 or earlier and can include primary partitions, extended partitions, logical drives, volume sets, mirror sets, stripe sets, or stripe sets with parity
- **Dynamic storage:** Volumes created using the Computer Management snap-in for the Microsoft Management Console (MMC) that can include simple volumes, spanned volumes, striped volumes, mirrored volumes, or RAID 5 volumes

See Also: *basic volume, dynamic volume, storage*

volume set

A single volume created using discontiguous free areas on hard disks.

Overview

Volume sets can be created in Microsoft Windows NT by combining between 2 and 32 free areas on your disk drives. You can extend a volume set formatted with the NTFS file system (NTFS) without having to reformat the entire volume. In Windows 2000, Windows XP, and Windows .NET Server, volume sets are instead called spanned volumes and are created using the Computer Management snap-in for the Microsoft Management Console (MMC).

Notes

Note that in Windows NT the system and boot partitions cannot be on volume sets.

See Also: *stripe set, volume*

VPIM

Stands for voice profile for Internet mail, an Internet Engineering Task Force (IETF) specification that defines a unified way of transmitting voice mail and fax messages over the Internet.

See: *voice profile for Internet mail (VPIM)*

VPN

Stands for virtual private network, a technology for securely connecting a computer or network to a remote network over an intermediate network such as the Internet.

See: *virtual private network (VPN)*

V-series

A series of communication standards developed by the International Telecommunication Union (ITU).

Overview

V-series protocols define methodologies for exchanging data over digital telephone networks. Standards below V.100 define:

- Signaling methods used by serial communication interfaces used in telephony.
- Techniques such as flow control and error control used in communication between data terminal equipment (DTE) such as computers and data communications equipment (DCE) such as modems and multiplexers.

Standards V.100 and higher deal with issues relating to internetworking the telephone system with other types of networks such as packet-switching networks such as X.25.

The following table describes some of the more popular V-series standards relating to modems and other serial interface standards.

Popular Serial Transmission Standards

V Standard	*Description*
V.22	Early standard for full-duplex serial transmission over one pair of wires at 1200 bits per second (bps).
V.22bis	Same as V.22 but supports 2400 bps.
V.24	The ITU equivalent of the RS-232 serial interface.
V.32	Industry standard for 9600-bps serial transmission.
V.32bis	Same as V.32 but supports 14.4 kilobits per second (Kbps).
V.32ter	Same as V.32 but supports 19.2 Kbps.
V.33	Protocol for full-duplex synchronous serial communication over leased lines with two pairs of wires; supports speeds of up to 14.4 Kbps and is used primarily in IBM mainframe environments.
V.34	Supports 28.8-Kbps serial transmission over dial-up (one wire pair) or leased (one or two wire pairs) lines.
V.34bis	Same as V.34 but supports 33.6 Kbps.
V.35	Protocol for synchronous serial communication at speeds of up to 48 Kbps; typically used for DTE/DCE communication between Channel Service Unit/Data Service Units (CSU/DSUs) and bridges/routers. V.35 has technically been replaced by V.10/11 but is still widely implemented in equipment such as routers, switches, and other wide area network (WAN) access devices.
V.42	Same as V.32 but enhances error correction mechanisms using LAPM (link access procedures for modems) and MNP (Microcom Networking Protocol).
V.42bis	Adds 4-to-1 data compression to V.42 and V.90.
V.44	Adds 6-to-1 data compression to V.42, V.90, and V.92.
V.90	High-speed modem standard that supports asymmetric communication with a maximum downstream data rate of 56 Kbps and an upstream rate of 33.6 Kbps.
V.92	High-speed modem standard that supports asymmetric communication with a maximum downstream data rate of 56 Kbps and an upstream rate of 48 Kbps.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), International Telecommunication Union (ITU), modem, RS-232, serial transmission, V.35, V.90, V.92*

W

W3C

Stands for World Wide Web Consortium, a vendor-neutral organization created in 1994 that develops common, interoperable standards and protocols for the World Wide Web (WWW).

See: *World Wide Web Consortium (W3C)*

wall plate

Also called a faceplate, a cabling fixture attached to a wall in a work area for connecting computers to the network.

Overview

Wall plates are generally used in work areas to enable desktop computers to be connected to the network. The wall plates connect to the building's structured wiring system, and the computers connect to the wall plate by a short unshielded twisted-pair (UTP) cable called a drop cable.

Wall plates come in mono-port, dual-port, and quad-port configurations, generally with RJ-45 jacks, which resemble household RJ-11 telephone wall jacks but are larger and have more wires. These RJ-45 jacks are typically used when networks are running Ethernet or Fast Ethernet. Other less common types of jacks include SC jacks for networks that use fiber-optic cabling, and BNC jacks for legacy 10Base2 networks.

The back end of the jacks in a wall plate typically connect to a horizontal cable that runs inside the wall or through a false ceiling or floor. This horizontal table terminates at a patch panel in the wiring closet on that floor, and vertical cabling running through elevator shafts or vertical rises connects wiring on different floors to switches in the main equipment room in the basement.

Implementation

Wall plates are an important feature of a permanent networking installation because they enable stations to be easily disconnected and reconnected to the network and protect network cables from damage caused by physical handling. The most common type are flush wall plates, which are flat like AC outlets, but angled wall plates are often a better choice because they offer better protection from excessive cable bending and protect drop cables from damage by contact with heavy or sharp-edged furniture.

Be sure to label or number wall plates so that you can easily identify the port on the patch panel to which they connect. If you cannot run cabling inside walls and must instead tack cabling directly onto the interior wall surface, use surface-mount boxes instead of wall plates. These are box-shaped adapters that screw onto the wall and have side or face jacks for connecting cables.



Wall plate. *Examples of flush and angled wall plates.*

Notes

You can also get special wall plates for serial interfaces that use DB connectors such as DB9 or DB25. These wall plates are used in mainframe computing environments in which dumb terminals are connected to mainframe hosts by using RS-232 serial lines.

See Also: *cabling, drop cable, premise cabling, RJ connectors, structured wiring, wiring closet*

WAN

Stands for wide area network, a geographically distributed network composed of multiple local area networks (LANs) joined into a single large network using services provided by telecommunication carriers.

See: *wide area network (WAN)*

WAN services

Services offered by telecommunication carriers to enable companies to build wide area networks (WANs).

Overview

WAN services are generally provided to enterprises by telcos, usually either by Regional Bell Operating Companies (RBOCs) or inter-exchange carriers (IXCs). The range of different types of WAN services that telcos can offer includes

- **Dedicated or leased lines:** These services establish a permanent point-to-point connection between two locations. They are always “on” and ready to carry network traffic. Leased lines are typically expensive because telco switches must be dedicated to the customer even when they are not being used. Examples of leased line services include T-carrier services such as T1, fractional T1, and T3. Leased lines are most popular with large enterprises that need reliable, high-bandwidth WAN links between branch offices.
- **Circuit-switched services:** These services establish a temporary path through the carrier’s network, usually only lasting as long as the call. When the session is terminated, the carrier’s switches are then freed up for other customers to use. Examples of circuit-switched services include Integrated Services Digital Network (ISDN) and dial-up modem connections using the Public Switched Telephone Network (PSTN). One problem with using circuit-switched services is that the quality of transmission depends on the switches and trunk lines used and therefore varies from call to call. For this reason, circuit-switched services are typically used for backup in case a leased line goes down. Because circuit-switched services also cost much less than leased lines, they are frequently used in low-traffic WAN networking environments.
- **Packet-switched services:** These services use virtual circuits instead of end-to-end physical connections. Data is transmitted in packets across a public data network (PDN) owned by the carrier (which is really a misnomer, as the network is owned privately). Examples of packet-switching services include frame relay and X.25.
- **Cell-switched services:** This is similar to packet-switching but employs small fixed-size cells instead of variable-size packets. Asynchronous Transfer Mode (ATM) is a popular cell-switching technology used in high-end enterprise WAN services. Connectivity at the customer premises is usually provided using an integrated access device (IAD) or router.

The WAN environment has been changing radically in recent years. Although enterprises have traditionally relied on T1 or frame relay for most branch-office connectivity solutions, several new solutions have emerged that can offer considerable cost savings and ease of use over standard WAN solutions. These new technologies include

- **Digital Subscriber Line (DSL):** A family of different technologies for transmitting data over existing copper local loop wiring at T1 speeds or higher. DSL circumvents the cost of deploying expensive conditioned T1 lines and is a much cheaper solution than T1, but it has not yet achieved the same degree of reliability. Nevertheless, many enterprises are eying this new technology carefully in consideration of future WAN deployments.
- **Virtual private network (VPN):** Using the public Internet for securely carrying private Internet Protocol (IP) traffic between different locations. Any kind of Internet connection can be used for a VPN, including dial-up, DSL, and T1. The advantage here is that data can be carried long distances without any added cost since a public network carries the traffic instead of a carrier’s private network.

- **IP over ATM over SONET:** This technology transports Internet Protocol (IP) traffic using ATM as the Layer 2 (data link layer) protocol and Synchronous Optical Network (SONET) as the underlying Layer 1 (physical layer) transport. The main problem with this solution is the "cell tax," the intrinsic overhead involved in translating IP packets into ATM cells, which can be as high as 13 percent of the throughput—or even higher.
- **Packet over SONET:** Also known as IP over SONET or IP over PPP over SONET, this technology replaces Layer-2 ATM with Point-to-Point Protocol (PPP) encapsulation.
- **Metropolitan Ethernet:** Here carriers run Gigabit Ethernet (GbE) connections right to the customer premises using fiber-optic cabling, which are then typically connected to a metropolitan area network (MAN) dual SONET ring.
- **Fixed wireless:** Buildings too far from a telco central office (CO) to deploy fiber for high-speed WAN links can find an alternative in fixed wireless networking technologies such as Local Multipoint Distribution System (LMDS), Multichannel Multipoint Distribution System (MMDS), microwave systems, or even point-to-point infrared laser transmission. Satellite networking is another emerging option, but its use is limited due to the high latencies involved.

See Also: *Asynchronous Transfer Mode (ATM), circuit-switched services, Digital Subscriber Line (DSL), frame relay, Gigabit Ethernet (GbE), Integrated Access Device (IAD), Integrated Services Digital Network (ISDN), inter-exchange carrier (IXC), Internet Protocol (IP), leased line, Local Multipoint Distribution Service (LMDS), metropolitan Ethernet, Multipoint Multichannel Distribution Service (MMDS), packet-switching services, Point-to-Point Protocol (PPP), Public Switched Telephone Network (PSTN), Regional Bell Operating Company (RBOC), Synchronous Optical Network (SONET), T-carrier, telco, virtual private network (VPN), wide area network (WAN), X.25*

WAP

Stands for Wireless Application Protocol, a technology for implementing mobile devices with the Web.

See: *Wireless Application Protocol (WAP)*

wavelength division multiplexing (WDM)

Transmitting multiple bitstreams down a single strand of fiber-optic cabling using different colors (wavelengths) for each stream.

Overview

Wavelength division multiplexing (WDM) was developed in the late 1980s as a way of increasing the carrying capacity of fiber-optic cabling. Inter-exchange carriers (IXCs) such as AT&T, Sprint Corporation, and Worldcom began implementing WDM in the mid-1990s when it became apparent that the rapid growth of the Internet would soon stress the carrying capacity of long-haul trunk lines. Telcos now turn to WDM as a standard solution when traffic congestion grows on backbone carrier networks.

WDM allows two or more separate bitstreams to be beamed down a strand of fiber using lasers of different frequencies, usually 10 nanometers or more apart in frequency. Each data stream itself can carry multiple data sessions by dividing the stream into different time slots using time-division multiplexing (TDM). WDM thus employs two forms of multiplexing: frequency-division multiplexing (FDM) to create different light paths and TDM to enable each light path to carry multiple data streams.

WDM supports common physical layer technologies used by telcos, including Synchronous Optical Network (SONET) and Asynchronous Transfer Mode (ATM). Although early WDM systems only supported 2 light channels, versions have been developed that support 4, 8, 16, and even 32 or more separate channels. WDM can operate over distances up to about 30 miles (50 kilometers), and this can be extended to hundreds of miles using optical repeaters.

Notes

A newer version of this technology called dense wavelength division multiplexing (DWDM) is essentially WDM on steroids and is basically WDM where the wavelength separation between adjacent channels is 2 nanometers or less, potentially resulting in hundreds of channels being carried over a single strand of fiber and throughput in excess of 1 terabit per second.

See Also: *Asynchronous Transfer Mode (ATM), dense wavelength division multiplexing (DWDM), fiber-optic cabling, frequency-division multiplexing (FDM), inter-exchange carrier (IXC), Synchronous Optical Network (SONET), time-division multiplexing (TDM)*

WBEM

Stands for Web-Based Enterprise Management, a set of technologies for developing standards-based network management platforms.

See: *Web-Based Enterprise Management (WBEM)*

W-CDMA

Stands for Wideband Code Division Multiple Access and known as Universal Mobile Telecommunications System (UMTS) in Europe, a worldwide standard for a third-generation (3G) cellular communications system.

See: *Wideband Code Division Multiple Access (W-CDMA)*

WDM

Stands for wavelength division multiplexing, transmitting multiple data streams down a single strand of fiber-optic cabling using different colors (wavelengths) for each stream.

See: *wavelength division multiplexing (WDM)*

Web

Short for World Wide Web, the popular Internet service that is rapidly changing the way we live and work.

See: *World Wide Web (WWW)*

Web application

A collection of elements on a Web site that performs a task programmatically.

Overview

Web applications are applications that are designed to run on Web servers and are accessed through Web browsers. Web applications may be implemented as client/server, multi-tier, or peer-to-peer applications. A common example of a Web application is the ordering mechanism or “shopping cart” on an e-commerce site such as Amazon.com.

Web applications can be developed by using a variety of technologies, including the following:

- Active Server Pages (ASP)
- ActiveX components or Java applets
- Internet Server API (ISAPI)
- Perl scripting using Common Gateway Interface (CGI)

See Also: *Active Server Pages (ASP), ActiveX, Common Gateway Interface (CGI), Internet Server API (ISAPI), Java, Web page*

Web-Based Enterprise Management (WBEM)

A set of technologies for developing standards-based network management platforms.

Overview

Web-Based Enterprise Management (WBEM) was developed by the Distributed Management Task Force (DMTF), which originated in 1996 as a joint initiative of companies headed by Microsoft Corporation, Intel Corporation, Cisco Systems, Compaq Computer Corporation, and BMC Software. WBEM was designed to help bring order to the chaos of the enterprise network management marketplace with its proprietary solutions and platforms. WBEM provides a framework of application programming interfaces (APIs), an object model, and a syntax for developing network management solutions that are interoperable between vendors.


Network management application
WBEM/CIM
DMI
SNMP
Registry
. . .
Infrastructure (systems, routers, etc.)

Web-Based Enterprise Management. *The architecture of the WBEM framework.*

WBEM is designed to work in heterogeneous enterprise networking environments to collect diagnostic and management data relating to hardware from multiple vendors, different operating systems, different network protocols, and distributed applications. WBEM enables information such as the amount of RAM in a computer, the capacity of a hard disk, the type of process, and the version of the operating system or firmware to be extracted from computers, routers, switches, and other network devices. This information can be used to detect potential problems before they occur, for remote management purposes, and for planning and other decision-making purposes.

WBEM simplifies management by providing a common model and data source that can be extended to function with existing protocols, networking components, and applications. An important part of the WBEM framework for WBEM is the Common Information Model (CIM), a set of schemas for cross-platform network management also developed by the DMTF. Once network management information is collected and stored in the CIM repository, it can be shared across an enterprise and displayed using WBEM management systems. Using CIM, a WBEM management application can access network information using Simple Network Management Protocol (SNMP), Desktop Management Interface (DMI), and other sources such as the Windows registry.

Microsoft has built the WBEM architecture into its Windows 2000, Windows XP, and Windows .NET Server platforms in the form of Windows Management Instrumentation (WMI), Microsoft's implementation of WBEM for 32-bit Microsoft Windows platforms.

For More Information

Find out more about WBEM at *www.dmtf.org/wbem.*

See Also: *Common Information Model (CIM), Desktop Management Interface (DMI), Distributed Management Task Force (DMTF), Simple Network Management Protocol (SNMP), Windows Management Instrumentation (WMI)*

Web browser

A client-side Hypertext Transfer Protocol (HTTP) application.

Overview

Web browsers enable users to access content published on Web servers that reside on the Internet or corporate intranets. Web browsers request and receive content hosted on Web servers using HTTP, the standard application layer protocol for the World Wide Web (WWW). Such content can be static, meaning it consists of text files formatted using Hypertext Markup Language (HTML), or the content can be dynamic, meaning it is generated on demand using server-side or client-side scripting technologies such as Microsoft Active Server Pages (ASP) and JavaScript.

Web browsers typically include features that make "browsing" (locating and accessing resources on) the Web simple, such as

- Toolbar buttons for navigating forward and backward through the tree of previously displayed pages, for stopping the download process, and for manually refreshing a page that loaded incompletely.
- Lists of favorites or bookmarks that store Uniform Resource Locators (URLs) of frequently accessed sites as well as tools for organizing and accessing those URLs.
- Options for specifying a default home page from which to begin browsing, a default search engine for searching the Web, and other default browsing options.

- Security options for handling such concerns as whether to allow scripts, ActiveX components, or Java applets to run on the browser.
- Facilities for displaying a page's underlying source code or HTML and even for editing and publishing Web content.
- Integration with other Internet software such as mail, news, or chat applications. Some Web browsers are packaged as stand-alone applications, while others are part of an overall suite of Internet tools that are integrated at various levels.

History

The first graphical Web browser was developed in 1993 by a group of students headed by Marc Andreessen at the National Center for Supercomputing Applications (NCSA). This browser was known as Mosaic and was distributed free. In 1994, Andreessen left NCSA to help found Netscape Communications, which developed the Netscape Navigator browser. The popularity of this browser helped foster the explosive growth of the Internet in the mid-1990s.

Microsoft quickly entered the arena with its Internet Explorer browser, which has since become the most widely used browser in the marketplace. Starting with Microsoft Windows 95, Microsoft began integrating Internet Explorer into its Windows operating systems, with the result that users running Windows can access Internet resources as easily as files on their own hard drives.

Web browsers have now become a standard interface for a wide range of platforms and services, including messaging, network management, mainframe access, and many other enterprise applications. The Web browser can be thought of a kind of "universal client" that is simple to learn and use, yet powerful enough to handle the most complex programming environments.

See Also: *Active Server Pages (ASP), ActiveX, Hypertext Markup Language (HTML), Hypertext Transfer Protocol (HTTP), Internet Explorer, Java, JavaScript, Web server, World Wide Web (WWW)*

Web content switch

Also called a Layer 7 switch or URL switch, an Ethernet switch that forwards frames according to Layer 4 or higher header information and used primarily for directing and load-balancing Web traffic.

See: *Layer 7 switch*

Web hosting

Hosting of Web content by service providers.

Overview

Companies offering Web hosting services range from local Internet service providers (ISPs) who provide businesses with a few dozen megabytes of server space and access to Perl scripting engines to global companies with server farms that offer dedicated servers, e-mail accounts, domain name holding, Microsoft FrontPage support, open database connectivity (ODBC) support, domain name hosting and holding services, and other services. Some industry analysts estimate that about two-thirds of all corporate Web sites are hosted by Web hosting service providers.

Web hosting started to become big business around 1998 and service providers offering Web hosting services reached their heyday in early 2000. Since then Web hosting providers have been rapidly supplanted by "content hosting" providers that offer an even greater range of services, which can include back-end system integration, custom programming, security management, and site mirroring. However, the distinction between the terms *Web hosting* and *content hosting* is often blurred in this rapidly evolving market.

Web hosting providers generally offer three different kinds of hosting services:

- **Shared hosting:** Your site is running on a Web server owned by the hosting provider, but the server hosts other people's sites as well.
- **Dedicated hosting:** Your site is running on a Web server owned by the hosting provider and your company has exclusive use of that server.

- **Colocated hosting:** You configure your Web server and then bring it in to the hosting provider's data center and they connect it to their high-speed Internet backbone.

When shopping for a Web hosting or content hosting service provider, it is a good idea to find out what degree of availability they guarantee. Many providers offer 99.99 percent availability with no downtime and give clients a refund if any downtime occurs, even if it is only a few minutes. They ensure such levels of availability by hosting sites on multiple redundant servers and scheduling maintenance so that one server is always online. It is also a good idea to make sure that the provider offers the full range of services that you require (or might soon require), such as database access and site mirroring. Find out the size of the pipe that connects the provider with the Internet backbone and at which point of presence (POP) the provider is connected to the Internet. For business hosting purposes, a minimum dual OC3 connection with guaranteed 155-megabits per second (Mbps) throughput is recommended. Decide whether you want dedicated or shared hosting—that is, whether you are willing to share a server and its network bandwidth with other companies or whether you require the stability, reliability, and throughput of your own dedicated Web server.

See Also: *Internet service provider (ISP), Web server*

Web page

A file of text information formatted using Hypertext Markup Language (HTML).

Overview

Web pages are sent by Web servers in response to requests from Web browsers and can contain formatted text, images, scripts, and various forms of active content. Web pages are generally of two types:

- **Static:** Stored as files on the server in the same form that they are delivered to the client. These files usually have the extension .htm or .html.
- **Dynamic:** Pages that include scripts, ActiveX components, Java applets, Dynamic HTML (DHTML), and other forms of active content to make static pages more interesting or useful. Dynamic pages often do not actually exist on the server until the client requests them, whereupon they are generated by the server using Active Server Pages (ASP) or some other server-side scripting technology.

See Also: *Active Server Pages (ASP), ActiveX, Dynamic HTML (DHTML), Hypertext Markup Language (HTML), Internet, Java, scripting, Web browser, Web server*

Web server

A server-side Hypertext Transfer Protocol (HTTP) application.

Overview

Web servers enable the publishing content on the Internet or on corporate intranets. Web servers host Web pages and other content that can be delivered using HTTP to Web browsers and other clients.

The first Web servers were originally developed for the UNIX platform and were used for publishing static Web content consisting of text files formatted using Hypertext Markup Language (HTML). To enhance static Web pages, dynamic features such as forms were later added using scripts written in interpretive languages such as Perl that ran within the UNIX Common Gateway Interface (CGI) execution environment. Other technologies developed later for delivering dynamic Web content include Java applets, ActiveX controls, Microsoft Active Server Pages (ASP) server-side scripting, and many others.

Marketplace

Some of the big players in the Web server arena include

- **Microsoft Internet Information Server (IIS):** A component of the Windows 2000 and Windows .NET Server platforms, IIS is a popular development platform for Internet applications that supports HTTP, File Transfer Protocol (FTP), Simple Mail Transfer Protocol (SMTP), Network News Transfer Protocol (NNTP), Secure Sockets Layer (SSL), Secure/Multipurpose Internet Mail

Extensions (S/MIME), and other Internet standard protocols. IIS also supports Microsoft FrontPage, a popular Web site development tool.

- **iPlanet Web Server:** Formerly Netscape Enterprise Server, iPlanet is a robust Web platform that runs on a variety of platforms and is widely used in enterprise environments.
- **Apache:** An open source application developed originally for the UNIX platform, Apache is popular with the Internet service provider (ISP) community that originated within the academic environment where the Internet originated.
- **Lotus Domino:** The Web server component of IBM's Lotus Notes messaging and collaboration platform.

Industry surveys have indicated that Apache is the predominant player when it comes to hosting public Internet sites, but an industry survey in 2001 indicated that IIS was the most popular Web server platform in Fortune 1000 companies, with 48 percent of respondents using IIS, 24 percent using iPlanet, 18 percent using Apache, and the rest using Domino or other platforms. The iPlanet platform is also used by 7 of the top 10 Fortune 1000 companies.

See Also: *Active Server Pages (ASP), ActiveX, Apache, Common Gateway Interface (CGI), Hypertext Transfer Protocol (HTTP), Internet, Internet Information Services (IIS), Java, Web browser, World Wide Web (WWW)*

Web-to-host

Providing access to legacy mainframe and midframe host systems to client systems using a standard Web browser interface.

Overview

Web-to-host technologies enable large companies to leverage their existing investment in IBM S/390 mainframe and AS/400 midframe host systems to gain advantage in the e-business and e-commerce arena. Host systems are widely used in enterprises for database hosting and transactional processing, and providing easy access to resources on host systems can give companies a competitive edge in the Internet economy. In the client/server computing era, special host client software displaced legacy "dumb terminals" by providing 3270 and 5250 terminal emulation on standard PCs. Web-to-host takes this process a step further by providing ActiveX or Java applets that allow terminal emulation sessions to run within a standard Web browser interface, making it as easy to access host resources as it is to browse the Web.



Web-to-host. *Example of how Web-to-host integration can be implemented.*

Implementation

Web-to-host platforms work in two basic ways:

- **Direct connection:** These platforms provide a direct connection between resources on the host and client Web browsers. Session security is usually provided by the host itself. This security is needed as traditional 3270 and 5250 terminal emulation clients communicate with hosts in clear-text data streams, and this is unacceptable when using the public Internet as the transmission medium.
- **Web server:** Here a Web server acts as a gateway between the host and browser client. The gateway typically provides security by encrypting the data stream, usually using Secure Sockets Layer (SSL) encryption.

In the second approach, the Web-to-host product, such as Microsoft Host Integration Server, communicates with the host system using Systems Network Architecture (SNA) and with the Web server using a programmatic technology such as Microsoft Corporation's Internet Server API (ISAPI) or various scripting technologies. The Web server then communicates with the browser client using standard Hypertext Transfer Protocol (HTTP), which is typically augmented with ActiveX controls or Java applets for greater display functionality.

Marketplace

Besides Microsoft's own Host Integration Server platform, a number of popular Web-to-host integration products are available in the marketplace. A popular solution is WebSphere Host OnDemand from IBM, which provides advanced display and printer emulation, integrated security, and enhanced database support. Some other popular products include WEB-ifier by Anota, e-Vantage Host Access Server by Attachmate Corporation, HostExplorer by Hummingbird International, HostFront by Farabi Technology Corporation, Novation by GT Software, WebConnect by OpenConnect Systems, Rumba by NetManage, WinSurf Mainframe Access by ICOM Infomatics, and Reflection by WRQ.

Notes

When shopping for a Web-to-host solution, look for the following features:

- Enhanced input and display features such as resizable terminal windows, custom screen colors, keyboard mapping, and macros
- 3270 and 5250 printer emulation to enable jobs run on hosts to print to local printers instead of remote host-connected ones
- Centralized deployment and management of host-client connections
- SSL encryption for data stream security

See Also: *3270, 5250, ActiveX, AS/400, Host Integration Server, Hypertext Transfer Protocol (HTTP), Internet Server API (ISAPI), Java, mainframe, scripting, Secure Sockets Layer (SSL), Systems Network Architecture (SNA), terminal emulator, Web browser, Web server*

well-known port numbers

Transmission Control Protocol (TCP) or User Datagram Protocol (UDP) port numbers that have been assigned to specific Transmission Control Protocol/Internet Protocol (TCP/IP) applications or services by the Internet Assigned Numbers Authority (IANA).

Overview

Well-known port numbers are assigned from the range 0 through 1023 from a total possible range of port numbers 0 through 65535. The following table lists many of the well-known port numbers.

Well-Known Port Numbers

Port Number	*Keyword*	*Description*
0/tcp, udp		Reserved
1/tcp, udp	tcpmux	TCP Port Service Multiplexer
2/tcp, udp	compressnet	Management Utility
3/tcp, udp	compressnet	Compression Process
4/tcp, udp		Unassigned
5/tcp, udp	rje	Remote Job Entry
6/tcp, udp		Unassigned
7/tcp, udp	echo	Echo
8/tcp, udp		Unassigned
9/tcp, udp	discard	Discard; alias = sink null
10/tcp, udp		Unassigned
11/tcp, udp	systat	Active Users; alias = users
12/tcp, udp		Unassigned
13/tcp, udp	daytime	Daytime
14/tcp, udp		Unassigned
15/tcp, udp		Unassigned (was netstat)
16/tcp, udp		Unassigned
17/tcp, udp	qotd	Quote of the Day; alias = quote
18/tcp, udp	msp	Message Send Protocol
19/tcp, udp	chargen	Character Generator; alias = ttytst source
20/tcp, udp	ftp-data	File Transfer (default data)
21/tcp, udp	ftp	File Transfer (control), connection dialog
22/tcp, udp		Unassigned
23/tcp, udp	telnet	Telnet
24/tcp, udp		Any private mail system
25/tcp, udp	smtp	Simple Mail Transfer; alias = mail
26/tcp, udp		Unassigned
27/tcp, udp	nsw-fe	NSW User System FE
28/tcp, udp		Unassigned
29/tcp, udp	msg-icp	MSG ICP
30/tcp, udp		Unassigned
31/tcp, udp	msg-auth	MSG Authentication
32/tcp, udp		Unassigned

(continued)

Well-Known Port Numbers *continued*

Port Number	*Keyword*	*Description*
33/tcp, udp	dsp	Display Support Protocol
34/tcp, udp		Unassigned
35/tcp, udp		Any private printer server
36/tcp, udp		Unassigned
37/tcp, udp	time	Time; alias = timeserver
38/tcp, udp		Unassigned
39/tcp, udp	rlp	Resource Location Protocol; alias = resource
40/tcp, udp		Unassigned
41/tcp, udp	graphics	Graphics
42/tcp, udp	nameserver	Host Name Server; alias = nameserver
43/tcp, udp	nicname	Who Is; alias = nicname
44/tcp, udp	mpm-flags	MPM FLAGS Protocol
45/tcp, udp	mpm	Message Processing Module
46/tcp, udp	mpm-snd	MPM (default send)
47/tcp, udp	ni-ftp	NI FTP
48/tcp, udp		Unassigned
49/tcp, udp	login	Login Host Protocol
50/tcp, udp	re-mail-ck	Remote Mail Checking Protocol
51/tcp, udp	la-maint	IMP Logical Address Maintenance
52/tcp, udp	xns-time	XNS Time Protocol
53/tcp, udp	domain	Domain Name Server
54/tcp, udp	xns-ch	XNS Clearinghouse
55/tcp, udp	isi-gl	ISI Graphics Language
56/tcp, udp	xns-auth	XNS Authentication
57/tcp, udp		Any private terminal access
58/tcp, udp	xns-mail	XNS Mail
59/tcp, udp		Any private file service
60/tcp, udp		Unassigned
61/tcp, udp	ni-mail	NI MAIL
62/tcp, udp	acas	ACA Services
63/tcp, udp	via-ftp	VIA Systems – FTP
64/tcp, udp	covia	Communications Integrator (CI)
65/tcp, udp	tacacs-ds	TACACS-Database Service
66/tcp, udp	sql*net	Oracle SQL*NET
67/tcp, udp	bootpc	DHCP/BOOTP Protocol Server
68/tcp, udp	bootpc	DHCP/BOOTP Protocol Server

(continued)

Well-Known Port Numbers *continued*

Port Number	*Keyword*	*Description*
69/tcp, udp	tftp	Trivial File Transfer
70/tcp, udp	gopher	Gopher
71/tcp, udp	netrjs-1	Remote Job Service
72/tcp, udp	netrjs-2	Remote Job Service
73/tcp, udp	netrjs-3	Remote Job Service
74/tcp, udp	netrjs-4	Remote Job Service
75/udp		Any private dial-out service
76/tcp, udp		Unassigned
77/tcp, udp		Any private RJE service
78/tcp, udp	vettcp	Vettcp
79/tcp, udp	finger	Finger
80/tcp, udp	www	World Wide Web HTTP
81/tcp, udp	hosts2-ns	HOSTS2 Name Server
82/tcp, udp	xfer	XFER Utility
83/tcp, udp	mit-ml-dev	MIT ML Device
84/tcp, udp	ctf	Common Trace Facility
85/tcp, udp	mit-ml-dev	MIT ML Device
86/tcp, udp	mfcobol	Micro Focus Cobol
87/tcp, udp		Any private terminal link; alias = ttylink
88/tcp, udp	kerberos	Kerberos
89/tcp, udp	su-mit-tg	SU/MIT Telnet Gateway
90/tcp, udp		DNSIX Security Attribute Token Map
91/tcp, udp	mit-dov	MIT Dover Spooler
92/tcp, udp	npp	Network Printing Protocol
93/tcp, udp	dcp	Device Control Protocol
94/tcp, udp	objcall	Tivoli Object Dispatcher
95/tcp, udp	supdup	SUPDUP
96/tcp, udp	dixie	DIXIE Protocol Specification
97/tcp, udp	swift-rvf	Swift Remote Virtual File Protocol
98/tcp, udp	tacnews	TAC News
99/tcp, udp	metagram	Metagram Relay
100/tcp	newacct	(unauthorized use)
101/tcp, udp	hostname	NIC Host Name Server; alias = hostname
102/tcp, udp	iso-tsap	ISO-TSAP
103/tcp, udp	gppitnp	Genesis Point-to-Point Trans Net; alias = webster
104/tcp, udp	acr-nema	ACR-NEMA Digital Imag. & Comm. 300

(continued)

Well-Known Port Numbers *continued*

Port Number	*Keyword*	*Description*
105/tcp, udp	csnet-ns	Mailbox Name Nameserver
106/tcp, udp	3com-tsmux	3COM-TSMUX
107/tcp, udp	rtelnet	Remote Telnet Service
108/tcp, udp	snagas	SNA Gateway Access Server
109/tcp, udp	pop2	Post Office Protocol version 2 (POP2); alias = postoffice
110/tcp, udp	pop3	Post Office Protocol version 3 (POP3); alias = postoffice
111/tcp, udp	sunrpc	SUN Remote Procedure Call
112/tcp, udp	mcidas	McIDAS Data Transmission Protocol
113/tcp, udp	auth	Authentication Service; alias = authentication
114/tcp, udp	audionews	Audio News Multicast
115/tcp, udp	sftp	Simple File Transfer Protocol
116/tcp, udp	ansanotify	ANSA REX Notify
117/tcp, udp	uucp-path	UUCP Path Service
118/tcp, udp	sqlserv	SQL Services
119/tcp, udp	nntp	Network News Transfer Protocol (NNTP); alias = usenet
120/tcp, udp	cfdptkt	CFDPTKT
121/tcp, udp	erpc	Encore Expedited Remote Pro. Call
122/tcp, udp	smakynet	SMAKYNET
123/tcp, udp	ntp	Network Time Protocol; alias = ntpd ntp
124/tcp, udp	ansatrader	ANSA REX Trader
125/tcp, udp	locus-map	Locus PC-Interface Net Map Server
126/tcp, udp	unitary	Unisys Unitary Login
127/tcp, udp	locus-con	Locus PC-Interface Conn Server
128/tcp, udp	gss-xlicen	GSS X License Verification
129/tcp, udp	pwdgen	Password Generator Protocol
130/tcp, udp	cisco-fna	Cisco FNATIVE
131/tcp, udp	cisco-tna	Cisco TNATIVE
132/tcp, udp	cisco-sys	Cisco SYSMAINT
133/tcp, udp	statsrv	Statistics Service
134/tcp, udp	ingres-net	INGRES-NET Service
135/tcp, udp	loc-srv	Location Service
136/tcp, udp	profile	PROFILE Naming System
137/tcp, udp	netbios-ns	NetBIOS Name Service
138/tcp, udp	netbios-dgm	NetBIOS Datagram Service
139/tcp, udp	netbios-ssn	NetBIOS Session Service
140/tcp, udp	emfis-data	EMFIS Data Service
141/tcp, udp	emfis-cntl	EMFIS Control Service
142/tcp, udp	bl-idm	Britton-Lee IDM
143/tcp, udp	imap2	Interim Mail Access Protocol v2
144/tcp, udp	news	NewS; alias = news
145/tcp, udp	uaac	UAAC Protocol
146/tcp, udp	iso-ip0	ISO-IP0
147/tcp, udp	iso-ip	ISO-IP
148/tcp, udp	cronus	CRONUS-SUPPORT
149/tcp, udp	aed-512	AED 512 Emulation Service
150/tcp, udp	sql-net	SQL-NET
151/tcp, udp	hems	HEMS
152/tcp, udp	bftp	Background File Transfer Program
153/tcp, udp	sgmp	SGMP; alias = sgmp
154/tcp, udp	netsc-prod	Netscape
155/tcp, udp	netsc-dev	Netscape
156/tcp, udp	sqlsrv	SQL Service
157/tcp, udp	knet-cmp	KNET/VM Command/ Message Protocol
158/tcp, udp	pcmail-srv	PCMail Server; alias = repository
159/tcp, udp	nss-routing	NSS-Routing
160/tcp, udp	sgmp-traps	SGMP-TRAPS
161/tcp, udp	snmp	SNMP; alias = snmp
162/tcp, udp	snmptrap	SNMPTRAP
163/tcp, udp	cmip-man	CMIP/TCP Manager
164/tcp, udp	cmip-agent	CMIP/TCP Agent
165/tcp, udp	xns-courier	Xerox
166/tcp, udp	s-net	Sirius Systems
167/tcp, udp	namp	NAMP

(continued)

Well-Known Port Numbers *continued*

Port Number	*Keyword*	*Description*
168/tcp, udp	rsvd	RSVD
169/tcp, udp	send	SEND
170/tcp, udp	print-srv	Network PostScript
171/tcp, udp	multiplex	Network Innovations Multiplex
172/tcp, udp	cl/1	Network Innovations CL/1
173/tcp, udp	xyplex-mux	Xyplex
174/tcp, udp	mailq	MAILQ
175/tcp, udp	vmnet	VMNET
176/tcp, udp	genrad-mux	GENRAD-MUX
177/tcp, udp	xdmcp	X Display Manager Control Protocol
178/tcp, udp	nextstep	NextStep Window Server
179/tcp, udp	bgp	Border Gateway Protocol (BGP)
180/tcp, udp	ris	Intergraph
181/tcp, udp	unify	Unify
182/tcp, udp	audit	Unisys Audit SITP
183/tcp, udp	ocbinder	OCBinder
184/tcp, udp	ocserver	OCServer
185/tcp, udp	remote-kis	Remote-KIS
186/tcp, udp	kis	KIS Protocol
187/tcp, udp	aci	Application Communication Interface
188/tcp, udp	mumps	Plus Five’s MUMPS
189/tcp, udp	qft	Queued File Transport
190/tcp, udp	gacp	Gateway Access Control Protocol
191/tcp, udp	prospero	Prospero
192/tcp, udp	osu-nms	OSU Network Monitoring System
193/tcp, udp	srmp	Spider Remote Monitoring Protocol
194/tcp, udp	irc	Internet Relay Chat (IRC) Protocol
195/tcp, udp	dn6-nlm-aud	DNSIX Network Level Module Audit
196/tcp, udp	dn6-smm-red	DNSIX Session Mgt Module Audit Redir
197/tcp, udp	dls	Directory Location Service

(continued)

Well-Known Port Numbers *continued*

Port Number	*Keyword*	*Description*
198/tcp, udp	dls-mon	Directory Location Service Monitor
199/tcp, udp	smux	SMUX
200/tcp, udp	src	IBM System Resource Controller
201/tcp, udp	at-rtmp	AppleTalk Routing Maintenance
202/tcp, udp	at-nbp	AppleTalk Name Binding
203/tcp, udp	at-3	AppleTalk Unused
204/tcp, udp	at-echo	AppleTalk Echo
205/tcp, udp	at-5	AppleTalk Unused
206/tcp, udp	at-zis	AppleTalk Zone Information
207/tcp, udp	at-7	AppleTalk Unused
208/tcp, udp	at-8	AppleTalk Unused
209/tcp, udp	tam	Trivial Authenticated Mail Protocol
210/tcp, udp	z39.50	ANSI Z39.50
211/tcp, udp	914c/g	Texas Instruments 914C/G Terminal
212/tcp, udp	anet	ATEXSSTR
213/tcp, udp	ipx	Internetwork Packet Exchange (IPX)
214/tcp, udp	vmpwscs	VM PWSCS
215/tcp, udp	softpc	Insignia Solutions
216/tcp, udp	atls	Access Technology License Server
217/tcp, udp	dbase	dBASE UNIX
218/tcp, udp	mpp	Netix Message Posting Protocol
219/tcp, udp	uarps	Unisys ARPs
220/tcp, udp	imap3	Interactive Mail Access Protocol v3
221/tcp, udp	fln-spx	Berkeley rlogind with SPX auth
222/tcp, udp	fsh-spx	Berkeley rshd with SPX auth
223/tcp, udp	cdc	Certificate Distribution Center
224–241		Reserved
243/tcp, udp	sur-meas	Survey Measurement
245/tcp, udp	link	LINK
246/tcp, udp	dsp3270	Display Systems Protocol

(continued)

Well-Known Port Numbers *continued*

Port Number	*Keyword*	*Description*
247–255		Reserved
345/tcp, udp	pawserv	Perf Analysis Workbench
346/tcp, udp	zserv	Zebra server
347/tcp, udp	fatserv	Fatmen Server
371/tcp, udp	clearcase	Clearcase
372/tcp, udp	ulistserv	UNIX Listserv
373/tcp, udp	legent-1	Legent Corporation
374/tcp, udp	legent-2	Legent Corporation
512/tcp	print	Microsoft Windows NT Server and Windows NT Workstation 4 can send LPD client print jobs from any available reserved port between 512 and 1023; see also the description for ports 721 to 731
512/udp	biff	Used by the mail system to notify users of new mail received; currently receives messages only from processes on the same computer; alias = comsat
513/tcp	login	Remote logon such as Telnet; automatic authentication performed based on privileged port numbers and distributed databases that identify “authentication domains"
513/udp	who	Maintains databases showing who’s logged on to the computers on a local net and the load average of the computer; alias = whod
514/tcp	cmd	Like exec, but automatic authentication is performed as for logon server
514/udp	syslog	

(continued)

Well-Known Port Numbers *continued*

Port Number	*Keyword*	*Description*
515/tcp, udp	printer	Spooler; the print server LPD service listens on tcp port 515 for incoming connections; alias = spooler
517/tcp, udp	talk	Like tenex link, but across computers; unfortunately, does not use link protocol (actually just a rendezvous port from which a TCP connection is established)
518/tcp, udp	ntalk	
519/tcp, udp	utime	Unixtime
520/tcp	efs	Extended filename server
520/udp	router	Local routing process (on site); uses variant of Xerox NS routing information protocol; alias = router routed
525/tcp, udp	timed	Timeserver
526/tcp, udp	tempo	Newdate
530/tcp, udp	courier	RPC
531/tcp	conference	Chat
531/udp	rvd-control	MIT disk
532/tcp, udp	netnews	Readnews
533/tcp, udp	netwall	For emergency broadcasts
540/tcp, udp	uucp	Uucpd
543/tcp, udp	klogin	
544/tcp, udp	kshell	Krcmd; alias = cmd
550/tcp, udp	new-rwho	New-who
555/tcp, udp	dsf	
556/tcp, udp	remotefs	Rfs server; alias = rfs_server rfs
560/tcp, udp	rmonitor	Rmonitord
561/tcp, udp	monitor	
562/tcp, udp	chshell	Chcmd
564/tcp, udp	9pfs	Plan 9 file service
565/tcp, udp	whoami	Whoami
570/tcp, udp	meter	Demon

(continued)

Well-Known Port Numbers *continued*

Port Number	*Keyword*	*Description*
571/tcp, udp	meter	Udemon
600/tcp, udp	ipcserver	Sun IPC server
607/tcp, udp	nqs	Nqs
666/tcp, udp	doom	Reserved for Id software
704/tcp, udp	elcsd	Errlog copy/server daemon
721–731/tcp	printer	In Windows NT 3.5, all TCP/IP print jobs sent from a computer running Windows NT were sourced from TCP ports 721 through 731; Windows NT 4 and Windows 2000 source LPD client print jobs from any available reserved port between 512 and 1023
740/tcp, udp	netcp	NETscout Control Protocol
741/tcp, udp	netgw	NetGW
742/tcp, udp	netrcs	Network-based Rev. Cont. Sys.
744/tcp, udp	flexlm	Flexible License Manager
747/tcp, udp	fujitsu-dev	Fujitsu Device Control
748/tcp, udp	ris-cm	Russell Info Sci Calendar Manager
749/tcp, udp	kerberos-adm	Kerberos administration
750/tcp	rfile	Kerberos authentication; alias = kdc
750/udp	loadav	
751/tcp, udp	pump	Kerberos authentication
752/tcp, udp	qrh	Kerberos password server
753/tcp, udp	rrh	Kerberos userreg server
754/tcp, udp	tell	Send; Kerberos slave propagation
758/tcp, udp	nlogin	
759/tcp, udp	con	
760/tcp, udp	ns	

(continued)

Well-Known Port Numbers *continued*

Port Number	*Keyword*	*Description*
761/tcp, udp	rxe	
762/tcp, udp	quotad	
763/tcp, udp	cycleserv	
764/tcp, udp	omserv	
765/tcp, udp	webster	
767/tcp, udp	phonebook	Phone
769/tcp, udp	vid	
770/tcp, udp	cadlock	
771/tcp, udp	rtip	
772/tcp, udp	cycleserv2	
773/tcp	submit	
773/udp	notify	
774/tcp	rpasswd	
774/udp	acmaint_dbd	
775/tcp	entomb	
775/udp	acmaint_transd	
776/tcp, udp	wpages	
780/tcp, udp	wpgs	
781/tcp, udp	hp-collector	HP performance data collector
782/tcp, udp	hp-managed-node	HP performance data managed node
783/tcp, udp	hp-alarm-mgr	HP performance data alarm manager
800/tcp, udp	mdbs_daemon	
801/tcp, udp	device	
888/tcp	erlogin	Logon and environment passing
996/tcp, udp	xtreelic	XTREE License Server
997/tcp, udp	maitrd	
998/tcp	busboy	
998/udp	puparp	
999/tcp	garcon	
999/udp	applix	Applix ac
999/tcp, udp	puprouter	
1000/tcp	cadlock	
1000/udp	ock	

Notes

Registered ports are port numbers that are not controlled by IANA but that IANA registers to indicate to the Internet community which vendor applications use them. Registered ports range from 1024 through 65535 and can be used by any process or program requesting it if the operating system has not already allocated it for a specific use. Programs and processes that communicate using remote procedure calls (RPCs) often randomly select a registered port for each RPC communication session.

See Also: *Internet Assigned Numbers Authority (IANA), port, port number, Transmission Control Protocol (TCP), User Datagram Protocol (UDP)*

WEP

Stands for Wired Equivalent Privacy, a data encryption scheme for securing 802.11b wireless local area networks (WLANs).

See: *Wired Equivalent Privacy (WEP)*

wide area network (WAN)

A geographically distributed network composed of multiple local area networks (LANs) joined into a single large network using services provided by telecommunication carriers.

Overview

Wide area networks (WANs) are commonly deployed in enterprise networking environments having company offices locating in different cities, states, regions, countries, or continents. A WAN is needed wherever offices are too far apart to be connected by local area network (LAN) technologies such as Ethernet, Fast Ethernet, and Gigabit Ethernet.

A company can build a WAN in two basic ways:

- Leasing WAN services such as T1 lines or frame relay from telecommunication carriers such as local exchange carriers (LECs) or inter-exchange carriers (IXCs). This is the typical approach used by most enterprises, and it usually incurs installation plus monthly usage costs paid to the carrier.
- Purchase or lay their own long-haul fiber to connect remote locations. This solution is expensive to deploy but can save money in the long run by eliminating monthly leasing costs for carrier services.



Wide area network (WAN). *Example of how a typical WAN is built.*

Implementation

In a typical carrier-based WAN, company LANs are connected to the carrier's services using special customer services equipment (CPE) deployed at the demarc point, the point where the company's LAN ends the and the carrier's network begins. The boundary of each LAN might be a router, bridge, access server, or other form of data terminal equipment (DTE), which connects through data communication equipment (DCE) such as a modem or channel service unit/data service unit (CSU/DSU) to the termination point of the carrier's line. From the point of view of the company LANs, the carrier's network appears as a "cloud" whose structure is unimportant and whose job is simply to get data from one LAN to another. Configuration of DCE at the customer premises is typically the responsibility of the carrier, who must ensure that these devices are configured properly to be able to access carrier services.

Routers and access servers typically support several types of WAN service connections including

- Circuit-switched services such as Integrated Services Digital Network (ISDN) and dial-up modem connections
- Packet-switched services such as frame relay and X.25
- Mainframe connections, typically using Synchronous Data Link Control (SDLC) protocol
- Peer connections using Point-to-Point Protocol (PPP) and High-level Data Link Control (HDLC) protocol

When planning a WAN, companies should consider the following:

- The average and peak amount of bandwidth usage anticipated
- The types of traffic that will travel over WAN links
- The availability of each type of WAN services from different carriers

See Also: *bridge, Channel Service Unit/Data Service Unit (CSU/DSU), data communications equipment (DCE), data terminal equipment (DTE), demarc, frame relay, High-level Data Link Control (HDLC), Integrated Services Digital Network (ISDN), inter-exchange carrier (IXC), local area network (LAN), local exchange carrier (LEC), modem, Point-to-Point Protocol (PPP), router, Synchronous Data Link Control (SDLC), T1, WAN services, X.25*

Wideband Code Division Multiple Access (W-CDMA)

Known as Universal Mobile Telecommunications System (UMTS) in Europe, a worldwide standard for a third-generation (3G) cellular communications system.

Overview

Wideband Code Division Multiple Access (W-CDMA) is a cellular communication technology that is based on existing second generation (2G) Code Division Multiple Access (CDMA) technology but offering much higher speeds. The term *Wideband* in W-CDMA is used because it uses wider frequency bands than regular CDMA, allowing higher throughput and enabling downward compatibility with existing Global System for Mobile Communication (GSM) systems widely used in Europe and many other parts of the world.

The UMTS standard was proposed by the European Telecommunications Standards Institute (ETSI) and has been incorporated into the International Mobile Telecommunications-2000 (IMT-2000) initiative, a 3G roadmap from the International Telecommunication Union (ITU). W-CDMA is currently being deployed in dense urban areas in Europe as an upgrade to GSM and in Japan by NTT DoCoMo and J-Phone.

Architecture

W-CDMA uses a newly licensed part of the 2-gigahertz (GHz) band of the electromagnetic spectrum, which causes some problems because this frequency band is already used in the United States for other purposes. As a result, W-CDMA may not take hold in the United States, where a competing standard called CDMA2000, based upon QUALCOMM's cdmaOne technology, is the emerging candidate for a 3G standard. W-CDMA is not fully compatible with air and network interfaces of CDMA2000 standards, as CDMA2000 uses synchronous base station transmissions with 20-millisecond frames and W-CDMA uses asynchronous base station transmissions with 10-millisecond frames. This probably means that cellular phone manufacturers will need to build phones that support both the W-CDMA and CDMA2000 standards in order to provide customers with true worldwide roaming service.

W-CDMA chipsets run at 4.096 megahertz (MHz), which provides a maximum transmission speed of 4 megabits per second (Mbps). Because of protocol overhead and other operational considerations, however, W-CDMA is likely to support a real capacity of only 1.1 Mbps and this only with stationary users. The channel bandwidth for W-CDMA is 5 MHz, much wider than the 1.25 MHz channels of CDMA2000.

For More Information

Visit the UMTS Forum at *www.umts-forum.org.*

See Also: *2G, 3G, CDMA2000, Code Division Multiple Access (CDMA), International Mobile Telecommunications-2000 (IMT-2000)*

WiFi

A seal of approval from the Wireless Ethernet Compatibility Alliance (WECA) certifying that wireless networking devices such as access points and network cards are fully compliant with the 802.11b wireless networking standard.

Overview

The WiFi seal of approval guarantees 802.11b wireless devices from one vendor will interoperate with similar devices from any other wireless vendor. WECA is composed of major wireless networking vendors and software developers and its goal is to promote the 802.11 standards by ensuring interoperability between equipment from different vendors.

For More Information

Find out more about WiFi at *www.wirelessethernet.org.*

See Also: *wireless networking*

Windows 3.1

The original 16-bit version of Microsoft Windows that made personal computers easier to use and more productive.

Overview

This original version of Windows went through several earlier versions, but the first widely used version was Windows 3.0, which was released in 1990 and provided users with a graphical user interface (GUI) environment that was easier to learn and use than the command-line environment of Microsoft's earlier MS-DOS operating system. In 1992, Microsoft Corporation released Windows 3.1, which included additional enhancements and utilities and became widely popular with both consumers and business. Windows 3.1 is now considered a legacy operating system and has largely been replaced by Windows 98, Windows Millennium Edition (Me), and Windows XP in the consumer market and by Windows NT and Windows 2000 in the business arena.

Some of the unique features of Windows 3.1 that distinguished it from the earlier MS-DOS operating system include

- A GUI that displays applications in separate windows that can be resized and arranged in any fashion
- Virtual memory, a technique for swapping between RAM and disk space that increases the number of applications that can be run simultaneously
- Customizable user interface elements, including the color scheme, fonts, arrangement of windows, and mouse settings
- Data sharing by applications using Dynamic Data Exchange (DDE) and object linking and embedding (OLE)
- TrueType fonts, which are displayed in What You See Is What You Get (WYSIWYG) fashion and can be scaled to any size
- Device independence, which makes it easier for manufacturers to write device drivers for their hardware
- Network-aware File Manager and Print Manager utilities, which enable access to shared network drives and printers



```
C:\WINDOWS>dir so*

 Volume in drive C is MS-DOS_6
 Volume Serial
 Directory of C
```

Windows 3.1. *The graphical user interface of Windows 3.1.*

Architecture

Windows 3.1 was a 16-bit cooperative multitasking graphical operating system that ran on top of MS-DOS and shared some architectural similarities with MS-DOS. Windows 3.1 used a layered architecture (see the figure) consisting of three main components:

- A top-layer Windows application programming interface (API) that allows software developers to write 16-bit Windows programs without needing to understand the details of how the operating system routines work internally or how device drivers are implemented and communicate with underlying hardware.
- A middle layer consisting of Windows core components and extensions. The core components make up the kernel of the operating system and consist of three subcomponents:
  - **Krnl386.exe:** Handles basic operating system tasks such as memory management, process and thread scheduling, and file input/output (I/O)
  - **User.exe:** Manages user I/O devices such as the keyboard and mouse, manages communication ports, and keeps track of Windows user interface elements such as windows, dialog boxes, icons, and menus
  - **Gdi.exe:** Manages drawing screen graphics and printing

  The middle layer also includes extensions to the core operating system components that are supplied in the form of dynamic-link libraries (DLLs) that add extra functionality to the Windows environment, such as multimedia support and DDE. Windows DLLs make the Windows operating system environment extensible, allowing software manufacturers to add basic functionality to Windows by creating their own custom DLLs. Windows optimizes memory usage by dynamically loading only the DLLs that it needs at a given time.
- A bottom layer, consisting of Windows drivers, that provides device drivers for different hardware devices managed by Windows, such as the keyboard, mouse, video display, and communication ports.



Windows 3.1. *The architecture of Windows 3.1.*

Windows 3.1 had two modes of operation:

- **Standard Mode:** Does not use virtual memory and cannot multitask with MS-DOS applications. In Standard Mode, MS-DOS applications can run only full-screen.
- **386 Enhanced Mode:** Requires an Intel 386 or higher processor, uses virtual memory, and supports multitasking of MS-DOS applications in separate windows. (See the diagram.) This mode includes the Virtual Machine Manager (VMM), which creates and manages separate virtual machines (VMs) running on a single CPU. Each VM functions as though it has access to and control over the entire system's resources. Windows 3.1 and all 16-bit Windows applications run in a single system VM, while each additional MS-DOS application runs in its own separate DOS VM. Virtual device drivers (VxDs) are 32-bit protected-mode DLLs that allow more than one process to share a system resource simultaneously in order to support multitasking. Windows applications are multitasked cooperatively—that is, they must be written to properly relinquish control to other applications to allow them to share system resources. Running Win.com at the MS-DOS prompt invokes the 386 Enhanced Mode system loader (Win386.exe).

Windows 3.1 stored its system and operating system configuration information in a series of text files accessed during the boot process. These included the following:

- Config.sys and Autoexec.bat, which have the same function as in MS-DOS
- Win.ini, which configures the Windows desktop and working environment
- System.ini, which stores the Windows system configuration, including device drivers and mode settings
- Other INI files such as Progman.ini, Protocol.ini, Control.ini, and Lanman.ini

See Also: *Microsoft Windows, Windows for Workgroups*

Windows 3.11

Also called Windows for Workgroups, a version of Microsoft Windows 3.1 released in 1994 that included integrated networking components.

See: *Windows for Workgroups*

Windows 95

Microsoft Corporation's popular desktop operating system and successor to the earlier Microsoft Windows 3.1 and Windows for Workgroups platforms.


LEONARDO
Current Work Documents
Network Neighborhood
Inbox
Recycle Bin
The Interne
McAfee VirusSc...
My Documen
Exploring - C:\WINDOWS\Profiles\administrator\Desktop\Current Work Documents
File Edit View Tools Help
Current Work Documents
All Folders
Contents of 'C:\WINDOWS\Profiles\administrator\Desktop\Current Work Doc
Desktop
LEONARDO
3½ Floppy (A:)
Ms-dos_6 (C:)
Datavol (D:)
(E:)
Control Panel
Printers
Dial-Up Networking
Scheduled Tasks
Network Neighborhood
Recycle Bin
Current Work Documents
Database of Customer Support Incidents for 1999.mdb
Presentation for shareholders meeting.ppt
Proposal for MTIT Enterprises.doc
Receipts for December 1999.xls
Entire Network
File Edit View Help
Headoffice
Manitoba
Mtit
Contains commands for working wi
System Monitor
File Edit View Options Help
Kernel: Processor Usage (%)
100
75
50
25
Kernel: Processor Usage (%) Last value: 24
Windows Help
Help Topics
Back
Options
Related Topics
Start
Exploring - C:\...
Entire Network
Windows Help
System Monitor
3:49 PM

To back up your files to a NetWare or Windows NT server

You can have files on your hard disk automatically backed up to a network server by using a network service called a backup agent. You need to use the backup agent that your network administrator has set up on the server: either ARCserve or Backup Exec.

Your network administrator specifies how often backups are done. You specify which files should be backed up.

For more information about setting up a backup agent service or changing settings such as which folders are backed up, click Related Topics below.

Windows 95. *The Windows 95 desktop.*

Overview

Windows 95 was designed as a desktop operating system for home, office, and business use that preserves full backward compatibility with applications for legacy operating systems such as MS-DOS, Windows 3.1, and Windows for Workgroups. Windows 95 proved wildly popular with both consumers and businesses. It has since been succeeded by several later generations of consumer Windows, including Windows 98, Windows Millennium Edition (Me), and Windows XP.

Windows 95 includes the following enhanced and new features over earlier versions of Microsoft Windows:

- A completely redesigned graphical user interface (GUI) with advanced features such as a configurable desktop, taskbar, Start button, and context menus
- Compatibility with legacy hardware and with MS-DOS and 16-bit Windows applications
- 32-bit virtual device drivers (VxDs) for protected-mode management of devices and services
- Preemptive multitasking kernel that multitasks Win32 and MS-DOS-based applications, replacing the cooperative multitasking approach used by Windows 3.1
- Fully integrated 32-bit disk, network, and print subsystems
- Integrated built-in networking software for Microsoft Networks, Novell NetWare, and Banyan Vines
- Support for long filenames
- Support for plug and play automatic hardware installation and configuration
- Advanced Power Management (APM) support for mobile users
- Integrated Windows Messaging for e-mail
- Integrated dial-up networking for Internet connectivity and for Remote Access Service (RAS) connectivity


Ring 3 of CPU
System VM
Kernel User GDI
Extension DLLs
Win32 app
Win32 app
Win32 app
Win16 app
Win16 app
Win16 app
MS-DOS VM
MS-DOS app
MS-DOS VM
MS-DOS app
...
VxD
VxD
VxD
Virtual Machine Manager (VMM)
Ring 0 of CPU
IFS Manager
VFAT file system
Virtual CD File System (VCDFS)
Redirectors
I/O subsystem

Windows 95. *The Windows 95 architecture.*

- Integrated support for multimedia sound and video applications
- Microsoft Internet Explorer, an integrated Web browser
- Support for advanced features for network administrators, including hardware profiles, user profiles, and system policies

Architecture

The Windows 95 architecture evolved from Windows 3.1 and Windows for Workgroups, but in contrast to these 16-bit versions of Windows, which ran on top of MS-DOS, Windows 95 is a 32-bit operating system with a 32-bit kernel, VxDs, and an Installable File System (IFS) manager, and it does not require that MS-DOS be loaded on the computer. However, Windows 95 includes some 16-bit code and 16-bit components to ensure backward compatibility with MS-DOS, Windows 3.1, and Windows for Workgroups. Windows 95 also supports multithreaded operation and preemptive multitasking operation and manages system resources more effectively than earlier versions of Windows, allowing more and larger applications to be multitasked.

For added protection against application crashes, Windows 95 supports virtual machines (VMs). VMs in Windows 95 are similar to those implemented in Windows 3.1 except for two differences: in Windows 95, 32-bit Windows applications (Win32 apps) can run within their own protected memory address space within the system VM, and 16-bit Windows applications (Win16 apps) also run in the system VM but share their own address space (since they must be cooperatively multitasked). MS-DOS applications run in individual VMs of their own.

Another change in Windows 95 is that system configuration information that was formerly stored in boot files (Config.sys and Autoexec.bat) and INI files is stored in a database structure called the registry. The registry is the central repository for all hardware and software configuration information. Boot and INI files are still supported for backward compatibility with legacy hardware and software.

Notes

Windows 95 went through several incremental releases, each with additional features and enhancements. To determine which version of Windows 95 you are using, run the System utility in Control Panel and look at the version number on the General tab. The incremental versions are described in the table on the following page.

Windows 95 Incremental Releases

Version Number	*Release*
4.00.950	Original full retail version and upgrade from Windows 3.1.
4.00.950A	Windows 95 with Service Pack 1, also called OEM Service Release 1 (OSR1).
4.00.950B	OEM Service Release 2 (OSR2) or OEM Service Release 2.1 (OSR2.1). If “USB Supplement to OSR2” shows up as an installed program when you use the Add/Remove Programs utility in Control Panel, you have OSR2.1 installed.
4.00.950C	OEM Service Release 2.5 (OSR2.5).

If your 20-digit product ID number has *OEM* in it, you have an original equipment manufacturer (OEM) version of Windows 95 that was probably preinstalled on your computer.

See Also: *Microsoft Windows, Windows 3.1, Windows 98, Windows Me (Windows Millennium Edition), Windows XP*

Windows 98

An upgrade for Microsoft Windows 95 and earlier versions of Windows operating systems.

Overview

Windows 98 includes the following features and enhancements over Windows 95:

- A Web-aware user interface that allows Web-like views of local resources and a single tool for browsing local, network, and Internet resources
- Integrated Internet software including Microsoft Internet Explorer, Outlook Express, NetMeeting, Personal Web Server, FrontPad, and NetShow
- Windows Update Manager for accessing the Internet to download enhancements and fixes to Windows 98
- Improved networking support, including a faster Transmission Control Protocol/Internet Protocol (TCP/IP) protocol stack, improved dial-up networking, and support for virtual private networking
- Support for FAT32 drives and a FAT32 conversion utility
- Maintenance Wizard for scheduling system maintenance utilities and other new utilities that simplify administration of computers running Windows 98, including the Microsoft System Information utility, System File Checker, Registry Checker, and Windows Scripting Host (for running administrative scripts from the desktop)
- Support for DVD drives and for multiple monitors on a single computer
- Support for universal serial bus (USB), FireWire (IEEE 1394), and infrared wireless connectivity based on Infrared Data Association (IrDA) standards
- Support for DirectX 5 and OnNow instant-on technology
- Built-in Remote Access Service (RAS) for remote dial-up clients
- Hypertext Markup Language (HTML)-based online help
- Improved versions of many Windows 95 tools and utilities

See Also: *Windows 95, Windows Me (Windows Millennium Edition), Windows XP*

Windows 2000

A powerful 32-bit operating system family from Microsoft Corporation and the successor to the earlier Microsoft Windows NT platform.

Overview

The Windows 2000 operating system is designed as a secure, robust, and highly scalable platform for both desktop and server business applications. There are four members of the Windows 2000 family—the Professional, Server, Advanced Server, and Datacenter Server versions—and each has a place in the corporate enterprise.

- **Windows 2000 Professional** is a powerful desktop operating system that replaces Windows NT Workstation 4. It builds on both the ease-of-use of Windows 98 and the power and reliability of Windows NT. Windows 2000 Professional includes the following features:
  - Wizards for simplifying system configuration and common system maintenance tasks, and time-saving improvements for the user interface, including Microsoft Internet Explorer 5, an integrated Web browser
  - Features for mobile users, including Advanced Configuration and Power Interface (ACPI) support for laptop power management and offline files, and Synchronization Manager for remote use of network resources
  - Support for 4-gigabyte (GB) RAM, two-way symmetric multiprocessing (SMP), universal serial bus (USB) and IEEE 1394 interfaces, Microsoft DirectX 7, OpenGL 1.2, video port extensions, DVD and smart card technologies
  - IntelliMirror client for deployment and maintenance in conjunction with Windows 2000 Server
  - Local data protection using the Encrypting File System (EFS)
  - Support for Transmission Control Protocol/Internet Protocol (TCP/IP) virtual private networking using Point-to-Point Tunneling Protocol (PPTP), Layer 2 Tunneling Protocol (L2TP), and Internet Protocol Security (IPsec)
  - Add-on Windows Services for UNIX components for interoperability with UNIX networking environments, including a Network File System (NFS) client and server, Telnet client and server, scripting tools, and password synchronization features
- **Windows 2000 Server, Standard Edition**, is a comprehensive application, file, print, and Internet services platform that replaces Windows NT Server 4 and provides increased reliability, scalability, management, and applications support. Its features include the following:
  - Active Directory directory service, a directory service based on the X.500 directory specifications that simplifies centralized, one-point management of distributed network resources.
  - Windows Management Tools, which are snap-ins for the Microsoft Management Console (MMC). MMC provides a unified interface for managing enterprise-level network resources.
  - Enhanced Internet services, including Hypertext Transfer Protocol (HTTP), File Transfer Protocol (FTP), Simple Mail Transfer Protocol (SMTP), and Network News Transfer Protocol (NNTP) server support through Internet Information Services (IIS).
  - Windows Terminal Services for running terminal emulation on thin clients, replacing Windows NT Server, Terminal Server Edition.
  - Four-way SMP support.
  - Enhanced COM+ component services.
  - Support for Kerberos and public key infrastructure (PKI) security services.
- **Windows 2000 Advanced Server** is a powerful server operating system that replaces Windows NT Server 4, Enterprise Edition. Windows 2000 Advanced Server is designed for enterprise-level networking environments that require high availability and scalability. Its features include all the ones in Windows 2000 Server, Standard Edition, plus the following:
  - Support for up to 64-GB RAM (through Intel Corporation's Physical Address Extensions) and eight-way SMP
  - Network-based and component-based load balancing with failover clustering
- **Windows 2000 Datacenter Server** is the high end of the Windows 2000 Server family. It supports all the features of Windows 2000 Advanced Server plus advanced clustering and 16-way SMP, with 32-way SMP available through original equipment manufacturers (OEMs).



Windows 2000. *The Windows 2000 desktop.*

Architecture

The architecture of Windows 2000 is similar to that of Windows NT with a few exceptions:

- The kernel is modified to include support for Terminal Services.
- Kernel Mode includes two new modules: Plug and Play Manager and Power Manager.
- I/O Manager includes additional drivers for Asynchronous Transfer Mode (ATM), quality of service (QoS), and other functions.

Notes

If you are a Windows NT system administrator who is moving to the more powerful and scalable Windows 2000 operating system platform, you might be confused at first by the differences between the administrative tools on the two platforms. The following table can help you get up to speed quickly on Windows 2000 system administration by highlighting some of the differences between the basic administrative tools on the Windows NT and Windows 2000 platforms. Note that there is usually no one-to-one correspondence between tools on the two platforms; what can be done with one tool on Windows NT might require several on Windows 2000, and vice versa. The tools listed in the second column are therefore not exact equivalents of those in the first column. Unless otherwise indicated, all Windows 2000 tools referred to are in the Administrative Tools program group, which can be accessed either from the Start menu or from Control Panel.

Comparison of Administrative Tools in Windows 2000 and Windows NT

Windows NT Administrative Tool	*Windows 2000 Equivalent(s)*
Administrative Wizards	Configure Your Server (Various consoles also have integrated wizards.)
Backup	Backup (in System Tools in Accessories)
Disk Administrator	Computer Management
Event Viewer	Event Viewer
License Manager	Licensing
Network Client Administrator	No equivalent
Performance Monitor	Performance
Remote Access Admin	Routing and Remote Access
Server Manager	Computer Management
System Policy Editor	Active Directory Users and Computers Group Policy
User Manager for Domains	Active Directory Users and Computers Active Directory Domains and Trusts Local Security Policy
Windows NT Diagnostics	Computer Management

See Also: *Microsoft Windows, Windows .NET Server, Windows NT, Windows XP*

Windows CE

A version of Microsoft Windows designed for a broad range of handheld and mobile products, including handheld computers, Personal Digital Assistants (PDAs), Windows terminals, smart phones, digital pagers, and industrial controllers.

Overview

Windows CE is primarily intended for handheld PCs that provide portable messaging and Internet capability and for embedded systems in which the operating system is hard-coded by a vendor into a device's ROM. Windows CE is based on a subset of the standard Win32 application programming interface (API), which means that original equipment manufacturer (OEM) developers can use all of the standard Win32 development tools to create custom-based Windows CE solutions for their Windows CE–based products. Windows CE is a component-based operating system that you can use to create "mix-and-match" operating systems that provide only the functionality needed for an embedded system, thus minimizing the memory requirements of such a system. For example, a Windows CE–based industrial sensor might contain the Windows CE kernel and communication modules but not the graphical user interface (GUI). Modules include the following:

- Operating system kernel (32-bit, multitasking, multithreaded, executes in ROM), graphical device interface (GDI), and USER components
- Device drivers, including keyboard, touch panel, notification light-emitting diode (LED), display, audio, battery, Personal Computer Memory Card International Association (PCMCIA), serial devices, and file allocation table (FAT)/FAT32 volumes
- Communication components, including support for both wired and wireless local area network (LAN) connectivity, Transmission Control Protocol/Internet Protocol (TCP/IP) with Windows Sockets, Point-to-Point Protocol (PPP), Serial Line Internet Protocol (SLIP), Infrared Data Association (IrDA) standards, and Telephony Application Programming Interface (TAPI)
- Windows CE Embedded Shell support, which allows developers to create custom shells for providing a user interface for their CE devices
- Win32-like registry for storing configuration information

Windows CE is implemented on a specific hardware platform using a thin layer of code between the kernel and the hardware called the OEM adaptation layer (OAL), which isolates device-specific features of hardware from the operating system kernel, enabling developers to ignore specific hardware functionality.

The current version of Windows CE, version 3, is the basis of the popular PocketPC handheld computing platform.

See Also: *Microsoft Windows, Personal Digital Assistant (PDA)*

Windows commands

Text-based commands that can be issued at the command prompt of Microsoft Windows NT, Windows 2000, Windows XP, or Windows .NET Server for performing administrative and housekeeping tasks.

Overview

Most Windows services are managed using graphical user interface (GUI)–based administrative tools, but you can also perform many administrative tasks at the command prompt either by issuing Windows commands interactively in real time or by saving a series of commands in a text file and running them as a batch file. Windows commands are grouped into several categories:

- **Common Windows commands:** Include commands for performing routing administration tasks. Some of the more frequently used commands are listed in the first table below.
- **Net commands:** For starting, stopping, and configuring networking services.
- **TCP/IP commands:** Commands associated with managing Transmission Control Protocol/Internet Protocol (TCP/IP) networking. These frequently used commands are listed in the second table in this article.
- **MS-DOS configuration commands:** For configuring an MS-DOS environment to run MS-DOS applications. These commands include buffers, country, device, devichigh, dos, dosonly, driveparm, echoconfig, fcbs, files, install, lastdrive, ntcmdprompt, shell, stacks, and switches.

- **MS-DOS subsystem commands:** For backward compatibility with MS-DOS applications. These commands include append, backup, debug, edit, edlin, exe2bin, expand, fastopen, graphics, loadfix, loadhigh, mem, nlsfunc, qbasic, setver, and share.
- **Batch commands:** Used only within batch files for automating system tasks. These commands include call, echo, endlocal, for, goto, if, pause, rem, setlocal, and shift.
- **Filter commands:** For sorting, viewing, and selecting portions of a command's output. These commands include find, more, and sort.
- **Redirection symbols:** For redirecting the input or output of a command to something other than standard input or output. These symbols include >, <, >>, and |.
- **Conditional processing symbols:** Allow you to issue multiple commands from the same command prompt and to act based on the results of the commands' execution. These symbols include &, &&, ||, ( ), and ^.
- **OS/2 configuration commands:** For configuring the operating system environment for applications that run using the OS/2 subsystem of Windows NT. These commands include codepage, devinfo, libpath, and protshell.

The following table lists some of the most frequently used Windows and TCP/IP commands and provides a brief description of what they do.

Common Windows Commands for Windows NT, Windows 2000, Windows XP, and Windows .NET Server

Command	*Description*
Assoc	Displays or modifies file extension associations
At	Schedules commands and programs to run on a system at a specified time and date
Attrib	Displays or changes file attributes
Cacls	Displays or modifies the access control lists (ACLs) of files
Chdir (Cd)	Displays the name of the current directory or changes the current directory
Chkdsk	Displays a disk status report and corrects errors on the disk
Cls	Clears the screen
Cmd	Starts a new instance of the Windows command interpreter
Compact	Displays and alters the compression of files or directories
Convert	Converts file allocation table (FAT) volumes to NTFS file system (NTFS)
Copy	Copies one or more files to another location
Date	Displays the date or allows you to change the date
Del (Erase)	Deletes specified files
Dir	Displays a list of a directory's files and subdirectories
Diskcopy	Copies a floppy disk
Diskperf	Starts and stops system disk performance counters
Doskey	Calls the doskey program, which recalls Windows commands, edits command lines, and creates macros
Exit	Quits the command interpreter and returns to the program that started it
Format	Formats a disk to accept Windows NT files
Help	Provides online information about Windows NT commands
Mkdir (Md)	Creates a directory or subdirectory
Move	Moves one or more files to a specified directory
Ntbooks	Accesses online Windows NT manuals
Prompt	Changes the Windows NT command prompt
Rename (Ren)	Changes the name of a file or files
Rmdir (Rd)	Deletes (removes) a directory
Start	Opens a separate window to run a program or a command

(continued)

Common Windows Commands for Windows NT, Windows 2000, Windows XP, and Windows .NET Server *continued*

Command	*Description*
Time	Displays the system time or sets the computer's internal clock
Tree	Displays the directory structure of a path or disk
Type	Displays the contents of a text file
Ver	Displays the Windows NT version number
Vol	Displays the disk volume label and serial number
Winnt	Performs an installation or upgrade of Windows NT 4
Winnt32	Performs an installation or upgrade of Windows NT 4
Xcopy	Copies files and directories, including subdirectories

TCP/IP Commands

Command	*Description*
Arp	Displays or modifies the IP–to–MAC address translation tables
Finger	Displays user information on a system running the finger service
Ftp	Transfers files to or from a File Transfer Protocol (FTP) server
Hostname	Prints the name of the current computer (host)
Ipconfig	Displays current TCP/IP network configuration values
Lpq	Obtains status of a print queue of a Line Printer Daemon (LPD) server
Lpr	Prints a file to an LPD server
Nbtstat	Displays protocol statistics and current NetBIOS over TCP/IP (NBT) connections
Netstat	Displays TCP/IP protocol statistics and connections
Nslookup	Displays information from Domain Name System (DNS) name servers
Ping	Verifies connections to a remote computer
Rcp	Copies files to or from a system running rshd
Rexec	Runs commands on remote computers running rexec
Route	Displays or modifies network routing tables
Rsh	Runs commands on remote computers running rsh
Tftp	Transfers files to or from a system running tftp
Tracert	Displays the route taken to a remote host on an internetwork

See Also: *command, command interpreter, command line, command prompt, Net commands*

Windows Distributed interNet Applications Architecture (Windows DNA)

An application development framework from Microsoft Corporation.

Overview

Windows Distributed interNet Applications Architecture (Windows DNA) is a programming architecture for rapidly and easily developing highly scalable networked applications that can be accessed from a wide variety of clients including traditional desktop "fat" clients, standard Web browsers, and Internet appliances. Windows DNA is based on Microsoft's "digital nervous system" paradigm for connecting applications, data sources, Web services, and users in new and dynamic ways. Windows DNA leverages the integrated services of Microsoft Windows platforms using an enhanced version of the Component Object Model (COM) framework called COM+.

Microsoft first introduced its Windows DNA strategy in September 1997 as a framework that would both embrace the existing Win32 application programming interface (API) client/server model for application development and also extend this model to include Web services and Internet-based clients. Windows DNA is being superseded by Microsoft's newer .NET Framework.

Architecture

Windows DNA services is based on a tiered architecture as follows:

- **Presentation services:** This is the level at which applications interact with users. Presentation services in Windows DNA include support for Hypertext Markup Language (HTML), Dynamic HTML (DHTML) scripting, and the Win32 API. The key enabler for Windows DNA at the presentation level is Internet Explorer, Microsoft's universal Web client application.
- **Application services:** Handles the core logic of distributed applications. Services at this level include Web services running on Microsoft Internet Information Services (IIS), Microsoft Message Queuing (MSMQ) services, transaction services, and component services provided by the COM+ object model.
- **Data services:** Provides access to data sources using ActiveX Data Objects (ADO) and OLE DB for implementing Microsoft's Universal Data Access (UDA) strategy.
- **System services:** Include services for security, management, directory, networking, and communication provided by the Microsoft Windows 2000 operating system and other Microsoft products such as SQL Server 2000 and Exchange Server 2000.

Implementation

To use the Windows DNA paradigm for distributed application development, you can take the following approach:

1. Separate your application into three logical tiers—presentation, business logic, and data.
2. Select the Windows components and technologies for your presentation level that provide your client with a suitable interface.
3. Write COM components to implement your business logic using the application services of Windows 2000 or Windows NT.
4. Use ADO to access data and use OLE DB to expose data for your third tier.

See Also: *ActiveX Data Objects (ADO), application programming interface (API), COM+, Dynamic HTML (DHTML), Hypertext Markup Language (HTML), Internet Information Services (IIS), .NET Framework, OLE DB, scripting, Universal Data Access (UDA)*

Windows DNA

Stands for Windows Distributed interNet Applications Architecture, an application development framework based on the Microsoft Windows 2000 operating system platform.

See: *Windows Distributed interNet Applications Architecture (Windows DNA)*

Windows Explorer

The primary tool for accessing file systems in 32-bit Microsoft Windows platforms.

Overview

You can use Windows Explorer to perform tasks such as

- Create, move, copy, open, edit, and delete files or folders
- Search for files using complex queries
- Map and disconnect network drives to shared folders on network servers
- View and manipulate properties of files and other file system objects
- Share folders and printers for use on the network
- Configure NTFS file system (NTFS) permissions, auditing, and ownership (only in Windows NT, Windows 2000, Windows XP, and Windows .NET Server)

Windows Explorer displays a hierarchical window-based view of file system and network resources in two panes. The left pane shows a hierarchical view of all available file system resources, including the desktop, local drives, mapped network drives, printers, and

My Network Places. In Windows 2000, the left pane can also show search tools or a history of recently accessed resources. The right pane shows the files and folders or other objects within the currently selected drive or folder in the left pane.


My Computer
File
Edit
View
Favorites
Tools
Help
Back
Search
Folders
History
Address
My Computer
Folders
Desktop
My Documents
My Computer
3½ Floppy (A:)
Thermopod (C:)
Data (D:)
Images (E:)
Audio CD (F:)
Control Panel
My Network Places
Recycle Bin
Internet Explorer
3½ Floppy (A:)
Thermopod (C:)
Data (D:)
Images (E:)
Audio CD (F:)
Control Panel
7 object(s)
My Computer

Windows Explorer. *The graphical user interface (GUI) of Windows Explorer.*

See Also: *file system, My Computer, My Network Places*

Windows for Workgroups

A version of Microsoft Windows 3.1 released in 1994 that included integrated networking components.

Overview

Windows for Workgroups used the same graphical user interface (GUI) as Windows 3.1 but included the following enhancements and new features:

- Integrated networking including support for the NetBIOS Enhanced User Interface (NetBEUI) and Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX) network protocols
- Add-on support for Transmission Control Protocol/Internet Protocol (TCP/IP) including Dynamic Host Configuration Protocol (DHCP), Telnet, and File Transfer Protocol (FTP) through the Microsoft TCP/IP-32 for Windows for Workgroups add-on
- Improved performance with 32-bit networking software that provides support for the Network Driver Interface Specification (NDIS) 3 standard, plus backward compatibility with the NDIS 2 standard of the 16-bit Windows 3.1 operating system
- Password-protected logon
- Low 4-kilobyte (KB) footprint in conventional memory for use with 32-bit network drivers, enabling large MS-DOS applications to be multitasked in a Windows environment
- Compatibility with Microsoft Windows NT Advanced Server, Novell NetWare, and Banyan VINES
- Autodetection of many network interface cards (NICs)
- Integrated mail and fax software
- Workgroup version of Microsoft Mail for e-mail connectivity, and the Schedule+ utility for keeping track of appointments and tasks
- Additional network utilities such as Chat, Net Watcher, WinPopup, and WinMeter

The first version of Windows for Workgroups was version 3.10, but version 3.11 soon followed, adding high-performance 32-bit networking access. Windows for Workgroups quickly became the default desktop operating system for many companies until it was superseded by Windows 95.

Architecture

The architecture of Windows for Workgroups is essentially the same as that of Windows 3.1 except for the networking subsystem, which supports the newer NDIS 3 standard. Windows for Workgroups also includes enhancements to 32-bit disk access, which is implemented as two Windows virtual device drivers (VxDs): Virtual File Allocation Table (VFAT), which is a 32-bit, protected-mode replacement for the MS-DOS file allocation table (FAT) file system; and VCACHE, which replaces the MS-DOS SmartDrive disk-caching utility and improves disk input/output (I/O). The network redirector (VREDIR) is implemented as a file system driver as well. The Installable File System (IFS) manager maintains a table that identifies which type of file system device is associated with each disk volume and forwards all I/O calls to the appropriate device.


File I/O Path for 32-bit File Access

32-bit NDIS 3.0 Networking Stack

Windows for Workgroups 3.11. *The architecture of Windows for Workgroups 3.11.*

See Also: *Microsoft Windows, Windows 3.1*

Windows Internet Name Service (WINS)

A service in Microsoft Windows NT, Windows 2000, and Windows .NET Server dynamically registering, managing, and resolving NetBIOS names.

Overview

Windows Internet Name Service (WINS) was a popular name resolution service on Windows NT networks because it provided a dynamic means of managing NetBIOS name resolution on networks. WINS provided a central location for registering and resolving the NetBIOS names of computers into their associated Internet Protocol (IP) addresses, simplifying the task of finding and accessing resources on a network.

WINS worked by requiring each NetBIOS host (computer) to register its NetBIOS name and IP address with a WINS server using a procedure called NetBIOS name registration. These NetBIOS name-to-IP address mappings were stored in a database called the WINS database and needed to be renewed periodically through NetBIOS name registration renewal messages. If the computer's IP address changed, the WINS database was automatically updated to reflect this, making WINS a totally automatic procedure for managing these mappings. And when a computer shut down, a name release occurred, removing the computer's mapping from the WINS database.

When a WINS client (that is, a computer running Windows) wanted to connect to a shared network resource, it first queried the designated WINS server by issuing a NetBIOS name query message, providing the WINS server with the NetBIOS name of the computer it wanted to connect to. The WINS server responded by checking its WINS database and returning the IP address of the desired computer to the client, enabling the client to locate and connect to the resource.

WINS replaced an earlier form of NetBIOS name resolution based on network broadcasts and had several advantages over this previous approach:

- Traffic directed to WINS servers consumes less network bandwidth than broadcasts.
- WINS enables the browsing of network resources across multiple domains and subnets.
- The WINS database of NetBIOS name-to-IP address mappings is dynamically maintained, eliminating the need for maintaining lmhosts files on clients.

On the newer Windows 2000 and Windows .NET Server platforms, WINS has been replaced by the Domain Name System (DNS) as the primary method for name resolution and resource location. WINS is still available as an option, however, for supporting downlevel

(Windows NT, Windows 98, Windows 95, and Windows for Workgroups) servers and clients on the network.

Notes

A single WINS server can support up to about 5000 clients. However, it is a good idea to always use at least two WINS servers in order to provide fault tolerance for NetBIOS name resolution. WINS servers maintain their own separate WINS databases, but they can be configured to replicate their NetBIOS name to IP address mappings by way of a process called WINS database replication.

See Also: *Domain Name System (DNS), lmhosts file, NetBIOS, NetBIOS name resolution*

Windows Management Instrumentation (WMI)

Microsoft Corporation's implementation of the Web-Based Enterprise Management (WBEM) architecture for enterprise-level network management.



Windows Management Instrumentation (WMI). *The WMI architecture.*

Overview

Windows Management Instrumentation (WMI) is a layer of services in 32-bit Microsoft Windows platforms that lets network management applications track, monitor, and control computers, networking devices, and applications. WMI is based on the WBEM framework developed by the Desktop Management Task Force (DMTF) and uses the Common Information Model (CIM) for describing manageable network objects. Support for WMI is built into Windows 98, Windows 2000, Windows XP, and Windows .NET Server and is available as an add-on for Windows NT 4.

Architecture

WMI has two main components:

- **Windows Management Service (WinMgmt.exe):** This component brokers communication between WMI consumers and providers. A WMI consumer is a management application that can interact with or query managed network objects. The Windows Management Service itself consists of
  - **CIM repository:** An object repository that is used for storing information collected from WMI-manageable hardware and software. This repository is compliant with the CIM standard.
  - **CIM Object Manager:** This component collects information from WMI providers and stores it in the repository.
- **WMI providers:** These function as intermediaries between the network object being managed and WMI. There are WMI providers for Simple Network Management Protocol (SNMP), Win32 objects, the Registry, and Service objects. For example, the Registry provider allows information to be collected from the registries of remote computers and stored in the repository. Similarly, if SNMP information needs to be collected from SNMP-manageable devices, the SNMP provider translates this information into a format suitable for WMI. WMI is also used by Microsoft Systems Management Server (SMS), and the SMS client includes WMI providers that interact with hardware on computers.

See Also: *Common Information Model (CIM), network management, Simple Network Management Protocol (SNMP), Systems Management Server (SMS), Web-Based Enterprise Management (WBEM)*

Windows Me (Windows Millennium Edition)

An upgrade to the Microsoft Windows 98 operating system.

Overview

Windows Me (Windows Millennium Edition) offers many new features and enhancements to the popular Windows 98 operating system, including

- Better ways to manage digital photos, movies, and music
- Protection of critical system files and System Restore for rolling back your system back to a previous working state
- Improved Help and Support areas
- Support for existing and upcoming universal serial bus (USB) devices
- Easier ways of networking your computers together
- Enhancements in networking, messaging, and Internet connectivity

See Also: *Windows 98, Windows XP*

Windows Millennium Edition (Windows Me)

An upgrade to the Microsoft Windows 98 operating system.

See: *Windows Me (Windows Millennium Edition)*

Windows .NET Server

The upcoming version of Microsoft Windows server operating systems that forms the basis of Microsoft Corporation's .NET Framework.

Overview

Microsoft's Windows .NET Server family will be the foundation of the next generation of Internet-enabled businesses. It includes all the features customers expect from a Windows operating system platform, including reliability, scalability, and security, plus additional features that enable businesses to experience the full functionality of the .NET Framework. Currently, Microsoft plans to release four different editions of Windows .NET Server:

- **Windows .NET Standard Server:** A reliable network operating system for building business solutions quickly and easily. Standard Server supports two-way symmetric multiprocessing (SMP) and up to 4 gigabytes (GB) of memory.
- **Windows .NET Enterprise Server:** An enhanced server platform for building hosting applications, infrastructure, and Web services. Enterprise Server supports four-way SMP and up to 32 GB of memory and will also be available for Intel Corporation's 64-bit Itanium processor platform.
- **Windows .NET Datacenter Server:** A platform for building mission-critical enterprise solutions. Datacenter Server supports 32-way SMP and up to 64 GB of memory on the Intel x86 platform and 128 GB of memory on the 64-bit Itanium platform.
- **Windows .NET Web Server:** Optimized for the job of Web applications hosting, Web Server is easy to deploy and manage and can be used in conjunction with Microsoft's ASP.NET Web application technology and managed from a browser-based interface.

At the time of writing, Windows .NET Server is in beta 3. As a result, the information in this article is subject to change.

See Also: *.NET platform*

Windows NT

Microsoft Corporation's original 32-bit business operating system family.

Overview

Microsoft Windows NT is the basis of Microsoft's BackOffice suite of server applications and provides a secure, scalable, and reliable platform for running enterprise line-of-business (LOB) applications. Windows NT was first released in 1993 in two editions, Windows NT Advanced Server (formerly called LAN Manager for Windows NT) and a client edition, Windows NT 3.1. In 1994 the platform was enhanced and released as Windows NT Server 3.5 and Windows NT

Workstation 3.5, which were both soon upgraded to Windows NT 3.51. Windows NT 3.51 included innovative networking and security features such as

- NTFS file system for advanced local and remote file system security
- Windows NT domains, which are implemented using domain controllers for secure logons in a networking environment
- Trust relationships for building enterprise-level multidomain networks
- Centralized storage of user profiles to support roaming users on the network
- Remote Access Service (RAS) for supporting remote users
- Support for both the server and client sides of Dynamic Host Configuration Protocol (DHCP) and Windows Internet Name Service (WINS)
- Support for the software implementation of redundant array of independent disks (RAID) levels 0, 1, and 5
- Integrated support for the Transmission Control Protocol/Internet Protocol (TCP/IP) protocol suite and associated utilities
- Support for Portable Operating System Interface for UNIX (POSIX) and Operating System/2 (OS/2) text-based applications
- Services for Apple Macintosh
- Support for Novell NetWare migration

In 1996 the Windows NT platform was upgraded to version 4, its final version, and included new features and enhancements such as

- An easy-to-use Windows 95–style desktop interface
- Administrative wizards
- Integrated Internet services and tools, including Internet Information Server (IIS)
- Administrative tools such as System Policy Editor, Network Monitor, and Task Manager
- Support for both the server and client sides of the Domain Name System (DNS) protocol
- Support for the Distributed Component Object Model (DCOM)
- Improvements to the core operating system services and components


My Computer
Network Neighborhood
Inbox
Internet Explorer
Services
Startup Parameters:
Exploring - C:\
File Edit View Tools Help
(C:)
All Folders
Desktop
My Computer
3½ Floppy (A:)
(C:)
Program Files
Public
Recycled
Contents of 'C:\'
Program Files
Public
Temp
Winnt
Autoexec.bat
boot.ini
Bootsect.dos
pagefile.sys
Recycled
User Manager - \\RUMPUS11
User View Policies Options Help
Groups
Administrators
Backup Operators
Guests
Power Users
Event Viewer - System Log on \\RUMPUS11
Log View Options Help
Windows NT Server
Programs
Documents
Settings
Find
Help
Run...
Shut Down...
Start
Exploring - C:\
User Manager - \\RUMPU...
Event Viewer - System Log...
9:11 PM

Service	Status
Alerter	Started
ClipBook Server	
Computer Browser	Started
DHCP Client	Started
Directory Replicator	
EventLog	Started
License Logging Service	Started
Messenger	Started
Net Logon	Started
Network DDE	

Username	Full Name	Description
Administrator		Built-in account for administ
Guest		Built-in account for guest ac
mitch1		
mitch2		

Date	Time	Source	Category
2/28/00	1:19:25 PM	Rdr	None
2/28/00	1:11:03 PM	Rdr	None
2/28/00	11:27:40 AM	EventLog	None
2/22/00	12:46:14 AM	Service Control Mar	None
2/22/00	12:43:14 AM	Print	None
2/22/00	12:43:12 AM	Print	None
2/22/00	12:42:58 AM	Print	None
2/22/00	12:42:47 AM	Print	None
2/22/00	12:33:23 AM	EventLog	None
2/22/00	12:33:50 AM	NETLOGON	None
2/22/00	12:22:33 AM	EventLog	None

Windows NT. *The Windows NT 4 user interface.*

The Windows NT 4 family included four editions:

- **Windows NT Server 4:** A fast 32-bit multitasking server operating system for networking environments. It can run as a file and print server, an application server, or an authentication and access control server (domain controller), and it can support as many concurrent connections as licenses purchased and up to 256 concurrent RAS sessions.
- **Windows NT Workstation 4:** A fast 32-bit multitasking desktop operating system that supported 10 incoming concurrent sessions and one RAS session.
- **Windows NT Server 4, Enterprise Edition:** Included Microsoft Cluster Server (MSCS) for two-node clustering, Windows NT Load Balancing Service (WLBS) for load balancing up to 32 servers, eight-way symmetric multiprocessing (and support for up to 32 processors from selected vendors), 4-GB Memory Tuning (4GT), and additional tools and enhancements.


DOS/Win16 application
POSIX application
Win32 application
NTVDM
OS/2 application
Logon process
User mode
POSIX subsystem
Win32 subsystem
OS/2 subsystem
Security subsystem
Windows NT executive
Executive services
System services
I/O Manager
Object Manager
Security Reference Monitor
Process Manager
Local Procedure Call Facility
Virtual Memory Manager
Win32 Window Manager & GDI
Kernel mode
Hardware device drivers
Microkernel
Hardware abstraction layer (HAL)
Graphic device drivers
Hardware

Windows NT. *Windows NT 4 architecture.*

- **Windows NT Server 4, Terminal Server Edition:** Included Terminal Services to present the familiar 32-bit Windows user interface on Windows terminal devices and on earlier versions of Windows desktop operating systems, including those running on legacy hardware.

Microsoft's Windows NT platform is still widely used in business and industry, but it has been superseded by Microsoft's newer and more powerful Windows 2000 platform.

Architecture

Windows NT processes run in one of two modes: user mode and kernel mode. User mode provides an execution environment for user applications as well as the various Windows NT subsystems that support them, which included:

- **Win32 subsystem:** Supports Win32 applications. (All other subsystems depend on this subsystem.)
- **Security subsystem:** Responsible for authentication, access control, and implementing security and audit policies.
- **OS/2 subsystem:** Responsible for running text-based OS/2 1.x applications.
- **POSIX subsystem:** Responsible for running POSIX-compliant UNIX applications.

Windows NT processes that run in user mode are limited to an assigned portion of the system's overall address space but can use virtual memory as needed. User mode processes run at a lower priority than kernel mode processes and have no direct access to system hardware functions. User mode processes must issue all hardware access requests to the Windows NT executive for fulfillment.

The other mode of Windows NT operation is kernel mode, used for running underlying operating system processes, which run at a higher priority than those in user mode. Kernel mode processes include

- **Windows NT executive services:** Implemented in various modules specific to operating system functions. All managers and device drivers are implemented at this level.
- **Microkernel:** Handles core operating system functions such as thread scheduling and interrupt handling.
- **Hardware abstraction layer (HAL):** Makes Windows NT more portable between platforms by isolating hardware-specific differences.

See Also: *Microsoft Windows, Windows 2000*

Windows NT Challenge/ Response Authentication

The authentication scheme used by Microsoft Windows NT–based networks.

Overview

Windows NT Challenge/Response Authentication, also commonly known as NTLM (which stands for Windows NT LAN Manager) authentication, enables user on Windows NT networks to be securely authenticated without the transmission of actual passwords across the network.

When a client attempts to log on to a Windows NT network, the domain controller challenges the client to perform a complex mathematical calculation on the user's password. The domain controller also performs the same calculation on the user's password, obtaining the password from its Security Account Manager (SAM) database. If the two calculations agree, the client is authenticated and allowed to log on to the network and access resources.

Notes

Windows 2000 uses a different authentication scheme based on the Kerberos security protocol, but NTLM authentication is still supported for backward compatibility with Windows NT domain controllers. On Windows 2000, however, NTLM is known instead as Integrated Windows Authentication.

See Also: *authentication protocol, network security, security protocols*

Windows NT Directory Services (NTDS)

The directory services used by Microsoft Windows NT to locate, manage, and organize network resources.

Overview

Windows NT Directory Services (NTDS) utilizes domains, trusts, and directory synchronization to provide users of enterprise-level Windows NT networks with the following capabilities:

- **Single-logon capability:** Users can log on anywhere in the enterprise using only one account.
- **Centralized administration:** Administrators can manage the entire network from a single location.
- **Universal resource access:** Users can access resources anywhere in the enterprise if they have the appropriate permissions.

To build effective enterprise-level directory services using Windows NT domains, you should consider the following factors:

- The number of domains needed (the domain model used)
- The number of domain controllers needed to support the number of users
- The placement of backup domain controllers (BDCs) to assure efficient directory synchronization of directory services
- The placement of BDCs to assure effective logon and resource authentication over slow wide area network (WAN) links

See Also: *domain controller, domain (DNS), trust, Windows NT*

Windows NT LAN Manager Authentication

Also called Windows NT Challenge/Response Authentication, the authentication scheme used by Microsoft Windows NT–based networks.

See: *Windows NT Challenge/Response Authentication*

Windows Script Host (WSH)

A language-independent scripting environment supported by recent versions of Microsoft Windows.

Overview

Scripting is a powerful tool that administrators can use to automate the execution of complex tasks such as performing system administration, installing software components, and managing files and network resources. The original MS-DOS and Windows 3.1 platforms from Microsoft Corporation supported only limited scripting ability using the DOS batch file language. Microsoft developed the Windows Script Host (WSH) to provide the Windows platform with a more powerful scripting environment based on the Component Object Model (COM).

WSH supports any scripting language that can be implemented using COM. Although Visual Basic, Scripting Edition (VBScript) is the most popular language for writing WSH scripts, other languages that can be used include JScript, Perl, TCL, REXX, Python, and even the legacy DOS batch file language. WSH provides two separate execution environments within which scripts can run:

- **Wscript.exe:** Runs scripts from the Windows desktop environment—for example, by double-clicking on a desktop shortcut for the script.
- **Cscript.exe:** Runs scripts from the command-line console.

The manner in which scripts are run is configured using .wsh files, which act somewhat like the legacy INI files from the Windows 3.1 environment and enable administrators to configure settings such as how long a script should be allowed to run before being terminated. To execute the script associated with a particular .wsh file, simply double-click on the file in the Windows desktop environment or use Cscript.exe at the command-line. You can even create several different .wsh files for a single script and use these in different situations.

The original version of WSH was included in the Windows NT 4 Option Pack and was supported by Windows 98 through an optional download. WSH version 2 is included with Windows 2000 and later.

See Also: *batch file, Component Object Model (COM), scripting*

Windows Sockets

Also called Winsock, an application programming interface (API) for interprocess communication (IPC) on Microsoft Windows platforms.

Overview

Windows Sockets provides an IPC mechanism for implementing both reliable, connection-oriented two-way communication and unreliable connectionless communication between processes running on two different computers. Windows Sockets is Microsoft Corporation's implementation of the Berkeley Sockets interface developed on UNIX platforms for Transmission Control Protocol/Internet Protocol (TCP/IP) networks.

Windows Sockets is implemented as a dynamic-link library (DLL) for Windows operating systems. The current implementation of Windows Sockets on Windows platforms is version 2, which supports multicasting, multiple network protocols (including TCP/IP, NWLink, and AppleTalk), and offers better performance than the previous version 1.1. Examples of applications that use Windows Sockets include File Transfer Protocol (FTP), Telnet, Microsoft Internet Explorer, and many others.

See Also: *application programming interface (API), dynamic-link library (DLL), interprocess communication (IPC), Transmission Control Protocol/Internet Protocol (TCP/IP)*

Windows Update

A Web site for updating Microsoft Windows platforms with new features and enhancements.

Overview

Windows Update can be thought of as an online extension of Windows that helps you keep your version of Windows up-to-date with the latest features and security enhancements. To use Windows Update, select its shortcut from the Start menu (Windows Update requires Internet connectivity to work). This action opens Microsoft Internet Explorer and takes you to the site *www.windowsupdate.microsoft.com*. Once you have connected to the site, ActiveX controls scan your system for outdated system files and determine which new versions of these files should be installed. These system files can include drivers, patches, help files, or new Windows components you can download to keep your computer up-to-date. Note that you must be an administrator or a member of the Administrators group to access the Product Updates section of the Windows Update Web site.

Notes

You also have the option of restoring previous versions of system files that have been changed by Windows Update.

Windows XP

The current desktop version of the Microsoft Windows platform.

Overview

Windows XP is the most recent Windows desktop operating system platform and is intended to be the successor to Windows 2000 Professional. Windows XP comes in two editions:

- Windows XP Home Edition for consumers
- Windows XP Professional for business and professional users

Windows XP is built upon an enhanced version of the Windows 2000 code base and integrates the strengths of the Windows 2000 platform (standards-based security, reliability, and manageability) with the flexibility and ease of use of the Windows 98 and Windows Millennium Edition (Me) line of products, which provide full Plug and Play (PnP) support and have an easy-to-use interface). Windows XP offers dramatically improved application response times and faster boot and resume times compared to previous versions, and it is tuned to provide users with a powerful and compelling "experience" of the Windows paradigm.

Windows XP is also the associated desktop client operating system for the upcoming Windows .NET Family of server operating systems. There is also a version of Windows XP called Windows XP Embedded that is designed for handheld and mobile devices having limited processing, memory, storage, and display capacities.

See Also: *Windows 2000, Windows .NET Server*

WINS

Stands for Windows Internet Name Service, a service in Microsoft Windows NT, Windows 2000, and Windows .NET Server for dynamically registering, managing, and resolving NetBIOS names.

See: *Windows Internet Name Service (WINS)*

Winsock

Properly called Windows Sockets, an application programming interface (API) for interprocess communication (IPC) on Microsoft Windows platforms.

See: *Windows Sockets*

WINS proxy agent

A computer that enables non-WINS clients to perform NetBIOS name resolution using the Windows Internet Name Service (WINS).

Overview

A WINS client is an operating system that can register its NetBIOS name with a WINS server. All Microsoft operating systems that are network-capable are (or can be configured to be) WINS clients. An example of a non-WINS client would be a Macintosh computer or a UNIX host.

A WINS proxy agent is a proxy for (acts on behalf of) non-WINS clients to allow them to communicate with WINS servers. WINS proxy agents work by listening for NetBIOS name registration broadcasts from non-WINS clients and then forwarding these broadcasts directly to a WINS server. The WINS server then checks its WINS database to see whether the NetBIOS name received is already being used on the network. If the name is in use, the WINS server returns a negative registration response to the proxy agent, and the proxy server then forwards this response back to the non-WINS client indicating that the name is already in use on the network. If the name is still available, the WINS server registers the NetBIOS name of the non-WINS client and informs the proxy agent to tell the client that registration was successful.

Non-WINS clients typically use broadcasts to perform NetBIOS name registration and resolution and are sometimes called B-node clients. A similar process to the above occurs when a B-node client tries to perform NetBIOS name discovery.

For example, if a non-WINS or B-node client wants to register its name on the network, it broadcasts a NetBIOS name registration request. The proxy agent detects this broadcast request and forwards it directly to the WINS server, which checks its WINS database to see whether the NetBIOS name is already being used on the network. If the name is in use, the WINS server responds to the proxy agent with a negative registration response, and the proxy server forwards this response back to the B-node client indicating that the name is already in use on the network.

Notes

WINS proxy agents are needed only on those subnets that have no WINS server and have non-WINS clients that need to be able to resolve the names of NetBIOS computers on other subnets. WINS proxy agents must be WINS clients but cannot be WINS servers.

See Also: *B-node, NetBIOS, NetBIOS name resolution, Windows Internet Name Service (WINS)*

WINS record

A Domain Name System (DNS) resource record that identifies a host as a Windows Internet Name Service (WINS) server.

Overview

WINS records are used in Microsoft Windows NT–based networks to enable Domain Name System (DNS) servers to refer name lookups to WINS servers. On Windows NT–based networks, WINS uses a dynamically updated database, while the DNS database is static and needs to be manually configured. DNS is thus harder to manage than WINS on Windows NT. So by configuring DNS to use WINS wherever possible, you simplify administration of name resolution on the network.

WINS records are specific to Microsoft Corporation's implementation of DNS on Windows NT and are not used with the new dynamic update of Windows 2000 or in non–Microsoft Windows networks such as those using Berkeley Internet Name Domain (BIND) running on UNIX servers.

See Also: *Domain Name System (DNS), resource record (RR)*

WINS server

A Microsoft Windows NT, Windows 2000, or Windows .NET Server machine running the Windows Internet Name Service (WINS).

Overview

WINS servers accept NetBIOS name registrations and queries from WINS clients and WINS proxy agents and then automatically create and maintain a database of NetBIOS name-to-Internet Protocol (IP) address mappings for clients on the network to speed up NetBIOS name resolution. Client computers periodically renew their name registrations for all its NetBIOS-enabled services to keep the WINS database fresh, and when a client is shut down properly or when a NetBIOS-related service is stopped on the host, the registered NetBIOS names for the client are released from the WINS database. In addition, WINS servers maintain their database through replication with other WINS servers. To do this, you can configure WINS servers in one of two roles:

- **Push partners:** These WINS servers send notices to their pull partners, notifying them of a certain threshold number of changes to their WINS database. You can configure this number on the push partners by using the Windows NT administrative tool WINS Manager or the WINS console in both Windows 2000 and Windows .NET Server. The pull partners respond by requesting the changes, which the push partners then send.
- **Pull partners:** These periodically send requests to their push partners, asking if any changes have been made to their WINS databases. You can configure the time interval for sending these requests on the pull partner. The push partners respond by sending the changes.

WINS servers play a crucial role in supporting efficient NetBIOS name resolution on a network by eliminating NetBIOS broadcasts. When one computer tries to contact another using NetBIOS over Transmission Control/Internet Protocol (TCP/IP), a NetBIOS name query request is first sent directly to a WINS server, which then returns the IP address of the target host and thus enables network communication to take place.

Notes

For fault tolerance on large networks, you should consider using a second WINS server, with WINS replication configured between the primary WINS server and secondary WINS server. One primary and one secondary WINS server are recommended for every 10,000 WINS clients on the network.

WINS servers must have static IP addresses assigned. To enable non-WINS clients to be resolved, create static mappings for them in the WINS database. To enable non-WINS clients to perform NetBIOS name resolution, use WINS proxy agents.

When you configure WINS replication, you should consider the following:

- You can configure WINS servers to be both push and pull partners with other WINS servers.
- WINS servers replicate only changes, not the full WINS database.
- On Windows NT WINS servers, you can manually force WINS replication by clicking the Replicate Now button in WINS Manager. On Windows 2000 WINS servers, you use the Action menu in the WINS console.

Over local area network (LAN) or high-speed wide area network (WAN) links, you should configure all WINS servers as both push and pull partners to keep the WINS database up-to-date on all WINS servers. Over slow WAN links, however, you should configure WINS servers as pull partners only so that you can schedule replication when WAN traffic is light.

See Also: *NetBIOS name resolution, Windows Internet Name Service (WINS)*

Wired Equivalent Privacy (WEP)

A data encryption scheme for securing 802.11b wireless local area networks (WLANs).

Overview

Wired Equivalent Privacy (WEP) provides Layer-2 (data-link layer) security for WLANs based on the popular 802.11b standard. To perform encryption, WEP uses a shared-key algorithm from RSA Security called RC4 Pseudo Random Number Generator (PRNG), which encrypts all data being sent and received between a wireless client and an access point (AP). Key strength for WEP encryption can be configured as either 40-bit or 128-bit, with 40-bit encryption adding approximately 10 percent overhead to 802.11b transmission.

Issues

WEP has recently been shown to be a flawed protocol that can be cracked using inexpensive off-the-shelf WLAN equipment. The problem lies in the fact that WEP integrates encryption and authentication functions so that a group of users share a common key. The

Institute of Electrical and Electronics Engineers (IEEE) 802.11b working group is working on a new version of WEP that will provide stronger security.

Meanwhile, many wireless vendors are offering additional layers of security to their products, which render WEP superfluous to a degree. For example, Cisco Systems' Aironet 350 Series of products include a proprietary encryption scheme that is separated from authentication and adds support for Remote Access Dial-In User Service (RADIUS). Other vendors offer their own similar proprietary schemes for enhancing WLAN security. The problem is that WEP was intended as an industry standard, while proprietary schemes do not work with each other. For now, enterprises concerned about WLAN security are probably best off buying all their equipment from a single vendor and implementing extra layers of security on top of WEP.

See Also: *802.11b, encryption, Institute of Electrical and Electronics Engineers (IEEE), wireless networking*

Wireless Application Protocol (WAP)

A technology for implementing mobile devices with the Web.

Overview

Wireless Application Protocol (WAP) is a set of standards, protocols, and technologies designed to bring Web content to mobile handheld communication devices such as cellular phones and Personal Digital Assistants (PDAs). Such devices generally have limited data input and display features, making it difficult for users to access regular Web content written in Hypertext Markup Language (HTML). To overcome this, the WAP standards include Wireless Markup Language (WML) and WMLScript, offshoots of HTML that can be used to create content custom designed for mobile devices that have small displays and limited bandwidth.

WAP was developed by Ericsson, Motorola, Nokia, and Phone.com (acquired by Openwave Systems) based on technology originally developed in 1995 by Unwired Planet (which became Phone.com). Together these four companies formed the WAP Forum in 1997 to steer the development of WAP standards and technologies. Typical uses for WAP include accessing stock market information, performing online banking, and accessing corporate inventory and sales information.

WAP enables Web content to be delivered over cellular communication systems, which are characterized by a number of issues that make then unsuitable for accessing traditional HTML Web content over Transmission Control Protocol/Internet Protocol (TCP/IP). These issues include

- **Low speed:** WAP is designed to deliver useful content at second-generation (2G) cellular speeds of 9.6 kilobits per second (Kbps) or less. Such limited bandwidth would make it difficult to use TCP/IP with its high protocol overhead.
- **High latency:** Cellular communications can experience latency as high as several seconds on occasion, which could lead to time-outs if TCP/IP were used.
- **Unreliability:** Because cell phone users sometimes go through tunnels or otherwise have their transmissions drop out, using TCP/IP would lead to excessive retransmissions.

The current WAP standard is version 1.2. Version 2 of WAP will include support for animation, color graphics, location-specific content, music downloads, streaming media, and synchronization with content stored on desktop computers.

Architecture

WAP uses a layered protocol stack loosely based on the Open Systems Interconnection (OSI) reference model. The layers of the WAP stack, starting from the bottom, are

- **Bearer layer:** This represents the underlying cellular communications physical and data-link layers, which govern how signals are transmitted and received. WAP is designed to operate with any cellular bearer system, including Time-Division

Multiple Access (TDMA), Code-Division Multiple Access (CDMA), and Global System for Mobile Communication (GSM).

- **Transport layer:** The Wireless Datagram Protocol (WDP) operates at this level. WDP provides a consistent interface between upper layers and the various cellular bearer systems.
- **Security layer:** The Wireless Transport Layer Security (WTLS) protocol operates at this level, providing authentication, privacy, and data integrity functions. WTLS is based on the Internet standard Transport Layer Security (TLS) protocol, which itself is based on Secure Sockets Layer (SSL).
- **Transaction layer:** The Wireless Transaction Protocol (WTP) operates at this level, providing three types of datagram delivery services: unreliable one-way requests, reliable two-way requests, and reliable two-way request-reply transactions.
- **Session layer:** The Wireless Session Protocol (WSP) operates at this level, providing connectionless (using WDP) and connection-oriented (using WDP and WTP) communication services. WSP also functions in a similar role to Hypertext Transfer Protocol (HTTP) in traditional Web systems.
- **Application layer:** The Wireless Application Environment (WAE) resides at this level and includes a microbrowser that interprets and displays WML and WMLScript content for the user.

Implementation

A WAP system consists of three basic components:

- **WAP client:** This is a WAP-enabled mobile device such as a cell phone or wireless PDA. Display on such devices may range from two lines of text to a small graphical display.
- **Web server:** This is a standard Web server on which content that WAP clients can access resides. This content is typically formatted in WML.
- **WAP gateway:** This acts as an intermediary between WAP clients and Web servers and fulfills three roles:
  - Translates requests from WAP clients into a form understandable by Web servers hosting WML content.
  - Translates WML content served up by Web servers into a binary format for transmission to the WAP client, which then displays the content (binary transmission is used instead of text to minimize bandwidth usage)
  - Performs authentication of WAP clients and encryption of WAP transmissions to ensure privacy


Wireless PDA running WAP
Web server on the Internet
① WTP request (UDP packet)
② HTTP request (TCP packet)
③ HTML page (TCP)
④ WML page (UDP)
WAP gateway

Wireless Application Protocol (WAP). *How WAP works.*

A disadvantage of WAP's gateway approach is that content providers must develop redundant versions of their Web content in WML and HTML. The emerging WAP 2 standard may solve this problem by storing content as XHTML instead, since standard PC Web browsers can translate XHTML into HTML while WAP 2 gateways can convert XHTML into WML.

Prospects

WAP has provided widely popular in Europe, thanks to its implementation by such major cellular communication companies as Ericsson and Nokia, who were involved in the development of WAP. WAP usage in Western Europe topped 7 million users in 2000, and that almost doubled in 2001. Critics have disparaged WAP as being painfully slow—in one test it took users almost two minutes just to find out what was on a certain TV channel using a WAP TV guide. In reality, WAP's limitations are really the limitations of cell phones and PDAs, with their small displays and slow wireless connections. It may be that when true third-generation (3G) cellular finally arrives with its megabit speeds, vendors will increase the display sizes on mobile devices to the point where delivering standard HTML Web pages to cell phones might succeed. If this happens, WAP will clearly be an interim technology, but one that more and more people are finding uses for every day.

Notes

The earlier Handheld Device Markup Language (HDML) was a precursor to WAP and formed the initial foundation from which WML was developed.

For More Information

Visit the WAP Forum at *www.wapforum.org.*

See Also: *2G, 3G, bandwidth, cellular communications, Handheld Device Markup Language (HDML), Hypertext Markup Language (HTML), Hypertext Transfer Protocol (HTTP), latency, Open Systems Interconnection (OSI) reference model, Web browser, Web server, Wireless Markup Language (WML), XHTML*

wireless local area network (WLAN)

A set of technologies used to replace traditional wired Ethernet local area networks (LANs) with wireless ones.

Overview

WLAN technologies can be used to replace or enhance traditional wired Ethernet LANs and are increasing in popularity in networking environments at many large companies. Popular WLAN technologies include

- **802.11b.** This operates in the unlicensed 2.4 gigahertz (GHz) band and provides speeds up to 11 megabits per second (Mbps).
- **802.11a.** This is a high-speed version of 802.11b that offers speeds up to 54 Mbps.
- **HiperLAN.** This is a high-speed wireless technology developed by the European Telecommunications Standards Institute (ETSI) that offers speeds up to 25 Mbps (a newer version, HiperLAN/2, provides speeds up to 54 Mbps).
- **HomeRF.** This is a low-speed frequency-hopping wireless technology (most wireless technologies now use direct sequencing instead) that offers speeds of only 1 Mbps.

See Also: *802.11a, 802.11b, HiperLAN/2, HomeRF, WiFi, wireless networking*

Wireless Markup Language (WML)

A language used to create content for the Wireless Application Protocol (WAP) platform.

Overview

Wireless Markup Language (WML) is a formatting language similar to Hypertext Markup Language (HTML) used on the Web. WML is implemented as an Extensible Markup Language (XML) application and is designed to produce content readable from WAP-enabled cell phones and Personal Digital Assistants (PDAs).

WML is both more and less powerful than HTML. WML lacks many of the formatting features of HTML, since these features are hard to implement on the small displays offered by mobile devices. In fact, the only styles supported by WML are emphasis, strong emphasis, boldface, italics, and underlining. WML also has limited support for tables, images, and other advanced HTML features. On the other hand, WML supports features not found in HTML, including tags for:

- Organizing content into decks of cards. WAP phones display only one WML card of information at a time. Cards are organized into decks, and when a card is accessed the entire deck is downloaded and cached for speedier access.
- Linking cards together to facilitate navigating through a deck.
- Providing dynamic interaction between user and content based on events, input forms, and selection lines.

Examples

A simple WML "Hello World" application might look like this:

```
<?xml version="1.0">
<!DOCTYPE wml PUBLIC "-//WAPFORUM//DTD WML
1.1//EN" "http://www.wapforum.org/DTD/
wml_1.1.xml">
<wml>
   <card title="WML Sample">
      <p>Hello World</p>
   </card>
</wml>
```

The first three lines are the XML Prolog and must appear at the start of all WML files. The <wml>…</wml> tags define the deck, and each card is defined by <card>…
</card> delimiters. The output of this application on a WAP phone would be to display the title "WML Sample" at the top of the screen with "Hello World" underneath.

WML is displayed on a WAP phone using a microbrowser, which is similar to a Web browser but adapted to devices with small displays and minimal processing power. The most popular microbrowser is that from Phone.com (acquired by Openwave Systems), who originally developed their browser for the earlier Handheld Device Markup Language (HDML). Nokia has developed its own microbrowser and has made the source code available for developers to use.

Marketplace

Some vendors have produced platforms that can transcode (translate) existing HTML content into WML for delivery to WAP devices. An example is IBM, whose WebSphere Everyplace Suite, Service Provider Edition, functions as middleware between cellular providers and Web content providers.

See Also: *Hypertext Markup Language (HTML), Wireless Application Protocol (WAP), XML*

wireless networking

Networking that uses electromagnetic waves traveling through free space to connect stations on a network.

Overview

In the broadest sense, wireless networking is composed of all forms of network communication that use electromagnetic waves of any wavelength or frequency, which includes the following portions of the electromagnetic spectrum:

- **Infrared (IR) laser:** Also called optical wireless, this point-to-point wireless technology ranges in frequency from about 300 gigahertz (GHz) to 200 terahertz (THz) and is used primarily in confined areas where line-of-sight communication is possible. IR cannot penetrate buildings or structures, but it can reflect off light-colored surfaces. Unfortunately, IR is absorbed by water vapor, so fog or rain can disrupt network communications.
- **Microwave:** Ranging from 2 GHz to 40 GHz, this point-to-point wireless technology is widely used for both terrestrial and satellite communication. Microwave also suffers from signal degradation when weather conditions are poor, but not as much as IR.
- **Broadcast radio:** Ranging from 30 megahertz (MHz) to 1 GHz, this technology can be used in both point-to-point and multipoint topologies and can travel through most buildings and structures, but it suffers from multipath interference when traveling over long distances.

When most people talk about wireless networking, they are talking about one of three things:

- **Fixed wireless:** These are services used to connect two fixed stations, typically an office building with a service provider's access point. Fixed wireless is mainly used for metropolitan area network (MAN) communications between different locations within an urban area. Examples of fixed wireless services include Local Multipoint Distribution System (LMDS) and Multichannel Multipoint Distribution System (MMDS).

- **Wireless local area network (WLAN):** WLAN technologies are used to replace or enhance traditional wired Ethernet local area networks (LANs) and are extremely popular in the enterprise. The most popular WLAN technology is 802.11b, which operates in the unlicensed 2.4 GHz band and provides speeds up to 11 megabits per second (Mbps). Other WLAN technologies include
  - HomeRF, a slower frequency-hopping wireless technology (most wireless technologies now use direct sequencing instead) offering speeds of only 1 Mbps. A wideband version of HomeRF offers speeds up to 10 Mbps, but it looks as though 802.11b has eclipsed HomeRF on the low-speed WLAN front.
  - 802.11a, a high-speed version of 802.11b that offers speeds up to 54 Mbps. 802.11a has the most momentum at present to be the high-speed successor of 802.11b, but unfortunately it is not backward compatible with 802.11b.
  - HiperLAN, a high-speed wireless technology developed by the European Telecommunications Standards Institute (ETSI) and offering speeds up to 25 Mbps. HiperLAN/2 can provide speeds up to 54 Mbps. HiperLAN is a compelling alternative to 802.11a with its built-in support for quality of service (QoS) and robust performance in dispersive environments due to its implementation of orthogonal frequency division multiplexing (OFDM).
- **Wireless personal area network (WPAN):** This is a wireless network used to connect devices that are worn or carried by users over short distances. Bluetooth is an emerging standard for WPANs that bi-directional data communications at 432.6 Kbps over distances up to 33 feet (10 meters).

The rest of this article focuses on WLAN technologies, as these are the most popular form of wireless networks used in enterprise environments.

History

Wireless networking first came to the attention of enterprise users in the mid-1990s when early proprietary products appeared offering speeds under 1 Mbps. In 1997 the Institute of Electrical and Electronics Engineers (IEEE) ratified the first WLAN standard, the 802.11 specification, which supported speeds up to 2 Mbps. In 1999 the IEEE ratified a new standard, the 802.11b High Rate specification, which brought wireless speeds up to 11 Mbps, making them comparable to Ethernet and, for the first time, an attractive alternative to traditional wired Ethernet LANs. Early 802.11b equipment from different vendors proved incompatible due to implementation differences, so the Wireless Ethernet Compatibility Alliance (WECA) was formed to promote interoperability between different vendors. WECA provides a certification called WiFi, which, if it appears on an 802.11b wireless device, virtually guarantees interoperability with devices from any other wireless vendor.

In 2000 the IEEE ratified a standard called 802.11a, which provides even faster speeds of up to 54 Mbps, and access points and PC cards for this technology are now beginning to appear in the marketplace. WECA has also developed a certification for 802.11a interoperability called WiFi5 (802.11a is five times faster than 802.11b). Currently, the IEEE is developing another standard called 802.11g, which runs at 22 Mbps and is backward compatible with 802.11b. It is uncertain at present whether this new technology will succeed in the marketplace.

802.11b currently rules the market in the WLAN arena, but enterprise network architects are beginning to look at 802.11a as an option when higher speed is required. Another recent development is the move toward integrating 802.11b WLAN technology with General Packet Radio Service (GPRS), a 2.5G cellular communication technology. This integration will enable cell phones and similar devices connect to corporate WLANs to send and retrieve data, taking us one step further into a wired world.

Uses

Wireless networks are typically used for

- Communication with mobile stations, which precludes the use of fixed cabling, or for mobile users such as workers moving about in large warehouses or knowledge workers at convention centers for conferences

- Work areas in which it is impractical or expensive to run cabling, such as older buildings that are costly to renovate
- Rapid deployment and reconfiguration of networks in companies that evolve quickly
- Networking buildings together on a campus using wireless bridges or fixed wireless services from a telco
- Sitting in a rubber tire in your swimming pool working on your laptop while sipping margaritas (do not try this if you value your laptop!)

Implementation

Wireless LANs (WLANs) are the simplest and most popular forms of wireless networking technology. To connect wireless stations to a traditional wired LAN, you need just two components:

- **Access point (AP):** This is basically a bridge that has an Ethernet port and a wireless transceiver. The Ethernet port connects to the wired LAN, and the transceiver transmits signals to and receives signals from the wireless stations. The effective reception range from an access point is defined by a circular area called a cell or Basic Service Set. A typical access point might provide up to 32,290 square feet (3000 square meters) of coverage in open areas (or less when obstacles are present) and support data transmission rates of 1 to 10 Mbps. However, the number of wireless stations that an access point can effectively handle is inversely proportional to the average traffic generated by each station. In other words, wireless networks are shared networks not switched ones. When multiple access point have overlapping cells, the access points hand off communication as stations roam from one cell to another.
- **PC card:** This is typically a card having an integrated antenna that connects the computer to the access point. There are also external devices that plug into an RJ-45 port of an Ethernet card or RS-232 serial port to provide similar connectivity. Some PC cards have an external or detachable antenna for greater distance reception. The card turns the computer in which it is installed into a wireless station on the network. The typical power output of a PC card is around 100 milliwatts (mW), which provides a coverage range of about 1000 feet (305 meters) in open areas, or less when obstacles such as walls or buildings are present.



Wireless networking. *A simple wireless LAN (WLAN) in operation.*

Most wireless systems use the Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA) media access method, in contrast to the Carrier Sense Multiple Access with Collision Detection (CSMA/CD) method used in wired Ethernet networks. The primary reason for this is that it is difficult to detect collisions between unguided electromagnetic waves.

Marketplace

Dozens of vendors offer WLAN access points and PC cards, some of the more popular being 3Com Corporation with its AirConnect series of products, Apple Computer with its AirPort line, Enterasys Networks with its RoamAbout AP and PC card, Cisco Systems with its Aironet 340 Series Wireless products, and Agere

Systems with its ORiNOCO line. Prices have fallen rapidly in the last year, and access points are now typically less than $1000 and PC cards may cost less than $200.

Issues

The biggest issue relating to wireless networking is security. Initiatives such as Wired Equivalent Privacy (WEP) from the IEEE have proven insufficient to guarantee the security of wireless networks. In addition, many products from wireless vendors are provided with security turned off by default, and if users do not enable security features their precious data will be broadcast to the world for anyone to intercept. Simply by driving around a downtown area with an 802.11b-enabled laptop, a user can often establish connections with numerous corporate wireless networks and view shared resources on these networks. As a result some wireless vendors are introducing their own proprietary solutions to ensure security for their wireless networking products.

Another issue is the susceptibility of WLANs to electromagnetic interference (EMI). For example, a microwave oven can degrade or sometimes disrupt 802.11b communication since it operates in the same microwave portion of the electromagnetic spectrum. Wireless networks also can have their speed limited by obstacles such as iron girders in buildings, concrete walls, and other signal-absorbing obstacles.

See Also: *802.11, 802.11a, 802.11b, access point (AP), Bluetooth, Carrier Sense Multiple Access with Collision Avoidance (CSMA/CA), Carrier Sense Multiple Access with Collision Detection (CSMA/CD), electromagnetic interference (EMI), General Packet Radio Service (GPRS), HiperLAN/2, HomeRF, Institute of Electrical and Electronics Engineers (IEEE), Local Multipoint Distribution Service (LMDS), Multipoint Multichannel Distribution Service (MMDS), Orthogonal Frequency Division Multiplexing (OFDM), quality of service (QoS), Wired Equivalent Privacy (WEP)*

wiring closet

A room on the floor of a building that contains hubs, switches, and other network components for that floor.

Overview

Also called an equipment room or server room (and various other names), wiring closets generally serve networks on individual floors of a building and are connected using vertical backbone cabling running down the elevator shaft to the main equipment room, which is usually in the basement. The wiring closet on each floor is the termination point for horizontal cabling running from wall plates in work areas on the floor. This horizontal wiring typically terminates in a series of patch panels in the wiring closet. Patch cables are used to connect jacks on the patch panels to ports on hubs and switches to establish network connectivity between computers on the floor and with other floors. In a single-floor building, the wiring closet and the main equipment room are the same and are sometimes called the telecommunications closet because telecommunications services typically terminate in that room as well.

Notes

The standards of the Electronic Industries Association/Telecommunications Industry Association (EIA/TIA) recommend one wiring closet per floor, with a minimum size of 9.8 feet by 6.6 feet (3 meters by 2 meters) per 4898 square feet (455 square meters) of floor space. When stations must be located more than 300 feet (91 meters) from the wiring closet, additional wiring closets are recommended. Wiring closets should be well lit and have an adequate power supply. Equipment should be mounted on racks for greater security and efficiency. “Spaghetti” should be minimized—keep everything accurately labeled to save yourself hours of troubleshooting time when things go wrong. Keep access to the wiring closet clear and secure, and include fire protection devices.

See Also: *infrastructure, premise cabling, structured wiring, wall plate*

WLAN

Stands for wireless local area network, a set of technologies used to replace traditional wired Ethernet local area networks (LANs) with wireless ones.

See: *wireless local area network (WLAN)*

WMI

Stands for Windows Management Instrumentation, Microsoft Corporation's implementation of the Web-Based Enterprise Management (WBEM) architecture for enterprise-level network management.

See: *Windows Management Instrumentation (WMI)*

WML

Stands for Wireless Markup Language, a language used to create content for the Wireless Application Protocol (WAP) platform.

See: *Wireless Markup Language (WML)*

workgroup

A logical grouping of networked peer computers that can share resources with one another.

Overview

Workgroups are usually established to share resources, including files, printers, and other devices. A workgroup is sometimes called a peer-to-peer network because all computers in a workgroup are equally important. In other words, no single computer "runs the network," as in a domain-based model.

Each computer in a workgroup handles security separately using its own local security database, which tracks who can log on to the computer and what rights or permissions users have to resources on the computer. A user who wants to log on to a computer must have an account in that computer's local security database. A user with an account on one computer does not necessarily have any permissions or rights to resources on other computers.

If a computer in a workgroup is used to provide file, print, or other resources to other computers in the workgroup, that computer is generally called a peer server or a stand-alone server. Because security is local to each computer in a workgroup, a peer server can share resources using share-level security only, which uses passwords to protect access to each resource. Users who know this password can access the resources at the level of access with which it is shared (such as read-only access or full access).

Workgroups are simple to implement but hard to maintain. Administrators must create accounts on each computer for the users who need access to them. As a result, workgroups are generally used for small networks of 10 or fewer computers in which security and centralized administration are not an issue.

See Also: *domain (DNS), server-based network*

World Wide Web (WWW)

The popular Internet service that is rapidly changing the way we live and work.

Overview

The World Wide Web Consortium (W3C) defines the World Wide Web (WWW, or Web) as "the universe of network-accessible information, the embodiment of human knowledge." The WWW began as a project for sharing hypertext information over a network that was developed by Tim Berners-Lee at CERN (Conseil Européen pour la Recherche Nucleaire), a physics research center in Geneva, Switzerland.

The Web consists of Web sites hosted on Web servers around the world and connected to the Internet. Users access the Web using Web browsers and similar client applications that use the Web's client/server protocol called Hypertext Transfer Protocol (HTTP). Web sites range from collections of text files formatted with Hypertext Markup Language (HTML) and their associated image, sound, multimedia, and script files to dynamic Web applications that can perform virtually every function imaginable. Individual HTML files within a Web site are called Web pages, and pages can be linked to other pages in the same or different sites, which explains why the word "web" is used, since this conjures up pictures of spider webs.

The Web contains a vast amount of information that is growing exponentially. Of all the interesting things that one could say about the Web (it would take a million books to exhaust the subject), we will focus on one interesting study done by IBM in 2000 that showed that "hyperspace" (another name for the Web) is actually divided into four different "regions" roughly equal in size, as follows:

- **Core:** This comprises 30 percent of the Web and consists of highly visible public Web sites such as Yahoo! and MSN. It is possible to browse from one point in the core to any other point in the core simply by following enough hyperlinks.
- **Origination node:** This comprises 24 percent of the Web and consists of sites that contain links that enable you to reach sites in the Core, but which cannot be traversed in the opposite direction. An example might be a personal home page with a link to MSN on it.
- **Termination node:** This comprises another 24 percent of the Web and consists of sites that you can reach from the Core but which do not link back to the Core. In other words, these are dead-end sites and pages containing various kinds of content but usually with no hyperlinks on them.
- **Disconnected pages:** This comprises 22 percent of the Web and consists of a number of "islands" of Web content that are completely disconnected from the Core. Broken links are often the cause of this condition.

As a result of this fascinating study, one might deduce that if you chose two Web pages at random, you have about one chance in four of being able to browse from one to the other by following links, perhaps hundreds of them! The average "link distance" between two randomly selected pages, however, was determined to be only about 16 clicks.

See Also: *Hypertext Markup Language (HTML), Hypertext Transfer Protocol (HTTP), World Wide Web Consortium (W3C)*

World Wide Web Consortium (W3C)

A vendor-neutral organization created in 1994 that develops common, interoperable standards and protocols for the World Wide Web (WWW).

Overview

Represented by the Massachusetts Institute of Technology (MIT) in the United States and a number of international research centers, the World Wide Web Consortium (W3C) provides a variety of services to its member organizations, including the following:

- Discussion groups and meetings on issues relating to the evolution of the WWW
- Repositories of information, reference documents, and code relating to WWW protocols, services, and applications
- The creation and testing of applications that demonstrate new types of WWW technologies

The process by which the W3C develops new standards and protocols involves four steps:

1. **Note:** An initial idea or comment is submitted as a document for discussion.
2. **Working draft:** Presents work in progress toward a possible standard by the W3C working group involved.
3. **Proposed recommendation:** Issued when a consensus has been reached within the working group.
4. **Recommendation:** Receives the director's stamp of approval as a W3C recommendation.

The director of the W3C is Tim Berners-Lee, the creator of the WWW. Membership in the W3C is tailored to organizations, but private individuals can also join as affiliate members.

For More Information

Visit the W3C at *www.w3c.org.*

See Also: *Internet, standards organizations, World Wide Web (WWW)*

WOW

Stands for "Win16 on Win32," a component of the Microsoft Windows NT operating system that enables 16-bit Windows applications (such as those designed to run on Windows 3.1 and Windows for Workgroups 3.11) to run properly on Windows NT's 32-bit operating system.

Overview

Like MS-DOS applications, 16-bit Windows applications (Win16 applications) also run on Windows NT within the context of a Windows NT Virtual DOS Machine (NTVDM), which simulates the 16-bit environment necessary for these applications to run. However, although MS-DOS applications each require their own separate NTVDMs in which to run, Win16 applications run within a single NTVDM called WOW, which corresponds to the system process Wowexec.exe. And although NTVDMs hosting MS-DOS applications are single-threaded, WOW is a multithreaded NTVDM in which each Win16 application runs as a separate thread using the same shared address space. WOW also simulates the cooperative multitasking environment for which applications written for Windows 3.1 and Windows for Workgroups 3.11 are designed. WOW allows only one Win16 application to run at a time, blocking the threads of all other Win16 applications until the running application relinquishes control. If the Windows NT kernel needs to preempt the Win16 application (by preempting WOW), it always resumes with the same Win16 application.

WOW also handles the translation of 16-bit Windows application programming interfaces (APIs) and messages to their corresponding 32-bit APIs and messages, enabling interoperability and data sharing between 16-bit and 32-bit Windows applications operating on the Windows NT platform.

Windows NT also includes an option for running Win16 applications in their own separate NTVDMs, which enables Win16 applications to function as a process within Windows NT's preemptive, multitasking environment. You can run a Win16 application in a separate NTVDM by opening the Run box from the Start menu, typing the path to the Win16 executable, and selecting the Run In Separate Memory Space check box. Note that doing this can have negative effects on Win16 applications that need to share data with each other by using legacy data-sharing mechanisms such as Dynamic Data Exchange (DDE).

WSH

Stands for Windows Script Host, a language-independent scripting environment supported by recent versions of Microsoft Windows.

See: *Windows Script Host (WSH)*

WWW

Stands for World Wide Web, the popular Internet service that is rapidly changing the way we live and work.

See: *World Wide Web (WWW)*

X

X.25

A legacy packet-switching protocol.

Overview

X.25 is the earliest example of a packet-switching protocol designed to provide wide area network (WAN) connectivity. It was developed in the early 1970s and standardized in 1976 by the Comité Consultatif International Télégraphique et Téléphonique (CCITT), the precursor of the International Telecommunication Union (ITU). X.25 is a synchronous, connection-oriented, bidirectional, full-duplex packet-switching protocol originally designed for connecting "dumb terminals" (character-based terminals) to remote mainframe hosts.

X.25 was designed to be a reliable WAN service that compensated for the fact that dumb terminals lacked the processing power to include an X.25 protocol stack. To ensure this reliability of communication, X.25 includes extra protocol overhead in packet headers. In addition, because X.25 was designed when analog transmission over noisy copper telephone wire was the norm, X.25 packets have additional overhead for error correction. The result of these two factors is the comparatively low overall bandwidth of X.25, which originally operated at only 19.2 kilobits per second (Kbps) (although this was generally sufficient for character-based communication between mainframes and terminals). The current X.25 standard supports speeds up to 2 megabits per second (Mbps) over two pairs of wires, but most implementations are 64-Kbps connections through a standard DS-0 link. The X.25 standard is updated every four years, and versions after 1984 are backward compatible with the 1984 version.

Architecture

The X.25 standard roughly corresponds in its functionality to the first three layers of the Open Systems Interconnection (OSI) reference model. The reason this correspondence is only rough is that X.25 was actually developed before the OSI model was created. Specifically, X.25 defines the following:

- **Physical layer:** Also called the physical layer in X.25 terminology, this layer defines the physical interface for connecting routers or terminals at the customer premises with X.25 switches at the carrier's facilities. The physical layer interface of X.25 is defined by the X.21 standard, which was originally derived from the RS-232 interface for serial transmission. The original X.21 connector was a 15-pin connector, but a newer standard called X.21bis uses a more common 25-pin connector. In general, RS-232 and V.35 serial interfaces have largely replaced X.21 interfaces on X.25 equipment.
- **Data-link layer:** Called the link access layer in X.25 terminology, this layer defines the encapsulation (framing) and error-correction methods used by X.25 and also enables X.25 equipment to initiate or terminate a communication session or initiate data transfer using the Link Access Procedure, Balanced (LAPB), which was derived from the earlier High-level Data Link Control (HDLC) protocol.
- **Network layer:** Called the packet layer in X.25 terminology, this layer defines the way to deliver X.25 packets reliably between end nodes on an X.25 network using the Packet Layer Protocol (PLP) and is also responsible for call setup and termination and for X.25 addressing using the X.121 standard.

Implementation

An X.25 network consists of four elements:

- **Data terminal equipment (DTE):** These include routers and computers at the customer premises that need to communicate using X.25.

- **Data communications equipment (DCE):** These include modems and Channel Service Unit/Data Service Units (CSU/DSUs) that connect the customer's DTE to the X.25 network. You can also connect multiple DTEs to a single DCE by using the multiplexing methods inherent in the X.25 protocol. Similarly, a single X.25 end node can establish several virtual circuits simultaneously with remote nodes.
- **Packet assembler/disassembler (PAD)**: This is a device that you can use to connect a dumb terminal to an X.25 network. The dumb terminal is DTE, and the PAD resides between the DTE and the DCE. Note that a PAD is not required for a router having built-in X.25 support—PADs are only required to connect dumb terminals that have no processing power to implement X.25 directly. The X.3 standard defines the various parameters used for configuring a PAD, the X.28 standard defines the data transmission interface between the DTE and the PAD, and the X.29 standard defines the control protocol between the DTE and the PAD.
- **Public data network (PDN):** This is the X.25 "cloud" of circuits and packet-switching exchanges (PSEs) (switches) at the carrier facility that you can use to connect DTE at different locations together and carry the X.25 packets from one DTE to another. These PDNs typically run parallel to the carrier's Public Switched Telephone Network (PSTN) voice network, and each carrier typically operates its own PDN. Different carriers' PDNs can be interconnected to form larger X.25 networks using the X.75 standard.

X.25 supports two different types of connection-oriented communications:

- **Permanent virtual circuit (PVC):** Here the carrier sets up the switches for the connection ahead of time, emulating a dedicated point-to-point communications link for the connected nodes. PVCs are used when large amounts of data regularly need to be transferred over PDNs, such as for connections between banks and credit agencies.
- **Switched virtual circuit (SVC):** The switches are set up when the call is initiated and are torn down afterward. SVCs are used when only small amounts of information need to be occasionally sent over PDNs.

In typical SVC communications, a DTE initiates a communication session with another DTE by dialing its X.121 address and establishing a virtual circuit. Packets are then forwarded through the PDN by using the ID number of the virtual circuit established for that particular communication session. This ID number is called the logical channel identifier (LCI) and is a 12-bit address that identifies the virtual circuit. X.25 packets are generally 128, 256, or 512 bytes in size, although actual size can range from 64 to 4096 bytes depending on the implementation.



X.25. *Anatomy of a simple X.25 network.*

Issues

X.25 is efficient for batch file transfer but not for interactive communication such as Telnet sessions, in which Transmission Control Protocol/Internet Protocol (TCP/IP) is run over X.25. If you often use Telnet from your X.25 terminal, you can improve efficiency by employing VanJacobsen TCP/IP Header Compression to reduce the overhead of the TCP/IP packet header from 40 bytes to 5 bytes (if your TCP/IP stack supports this feature). Another cause of X.25's inefficiency for interactive communication is the typical half-second latency in communication due to the store-and-forward nature of the packet-switching network. Frame relay does not use store-and-forward packet switching and hence has much less latency. In general, X.25 is not a good communication medium for applications that use TCP/IP because the high latency and low speed can sometimes cause TCP/IP applications to time out.

Prospects

Newer WAN technologies such as frame relay, Integrated Services Digital Network (ISDN), and T-carrier services are now generally preferred to X.25. However, X.25 networks still have applications in areas such as credit card verification, automatic teller machine transactions, and other dedicated business and financial uses. A striking example of how X.25 is still used is offered by the U.S. federal government's Automated Clearing House (ACH) network, a 30-year-old nationwide X.25 network used for collections payments between U.S. banks. Businesses use ACH to perform direct deposit of employee payroll, to credit and debit bank and credit institution funds transfers, and many other tasks. The U.S. Department of the Treasury has created a Web-based front end called *www.pay.gov* to this legacy X.25 system to allow ordinary citizens to pay taxes and other government fees such as those for National Parks permits.

See Also: *Channel Service Unit/Data Service Unit (CSU/DSU), connection-oriented protocol, data communications equipment (DCE), data terminal equipment (DTE), DS-0, frame relay, High-level Data Link Control (HDLC), Integrated Services Digital Network (ISDN), International Telecommunication Union (ITU), Open Systems Interconnection (OSI) reference model, packet assembler/ disassembler (PAD), packet-switching services, permanent virtual circuit (PVC), Public Switched Telephone Network (PSTN), router, RS-232, switched virtual circuit (SVC), T-carrier, Telnet, terminal, Transmission Control Protocol/Internet Protocol (TCP/IP), V.35, wide area network (WAN), X-series*

x86 platform

A PC hardware platform whose processor is based on the Intel 386 architecture microprocessor.

Overview

The x86, or Intel, platform is one of the two processor platforms supported by Microsoft Windows NT (the other being the Alpha platform) and the only processor platform supported by Microsoft Windows 2000. Intel-based systems have essentially caught up with Alpha in terms of speed and functionality and are used for everything from mobile laptop computers to desktop workstations to high-performance symmetric multiprocessing (SMP) servers.

The x86 family is based on the 386 processor and includes the 486, Pentium, Pentium Pro, Pentium II, Pentium III, and Pentium IV processors. Intel processors are based on the complex instruction set computing (CISC) architecture, which uses a large set of basic processor instructions to simplify code compilation. The CISC architecture differs from the reduced instruction set computing (RISC) architecture of the Alpha platform, which uses fewer processor instructions and offers better performance.

Notes

The Windows .NET Server platform also supports the new Itanium 64-bit architecture from Intel Corporation.

See Also: *64-bit architecture, Alpha platform*

X.121 address

An address of an end node connected to an X.25 public data network.

Overview

Also called international data numbers (IDNs), X.121 addresses are similar to long-distance telephone numbers and are used by X.25 end nodes to call each other to set up communication sessions. X.121 addresses are used during the call setup phase of X.25 communication and are used to establish a switched virtual circuit (SVC) between the source node and destination node on the network.

X.121 addresses are typically 14 decimal digits in length, unless fewer can suffice to uniquely determine the address of the destination node being called. The first four digits form the data network identification code (DNIC), with the first three digits indicating the country or region and the fourth digit indicating the carrier that owns the common packet-switching network being used to make the call. The remaining digits form the national terminal number (NTN) and identify the end node being called. An additional 1-byte header indicates the number of digits of both the source and destination nodes.

Once an X.25 communication session is established, a 12-bit logical channel identifier (LCI) is assigned to the two hosts as the identification number of the virtual circuit that is established between them. The X.25 network uses the LCI in the headers of the X.25 packets for routing data between the nodes. The X.121 address is used only at call setup to establish the virtual circuit.

See Also: *X.25, X-series*

X.400

A set of electronic messaging standards defined in 1984 and 1988 by the International Telecommunication Union (ITU).

Overview

The X.400 standards are based on the Open Systems Interconnection (OSI) reference model developed by the International Organization for Standardization (ISO). X.400 defines global standards to enable users to send e-mail between X.400-compliant messaging systems.

X.400 was originally intended to be the uniform, worldwide standard for global messaging, but the Internet's Simple Mail Transfer Protocol (SMTP) has far eclipsed it in popularity. X.400 is still used, however, in some parts of Europe by post, telephone, and telegraph (PTT) authorities.

Implementation

X.400 defines a global Message Handling System (MHS) that consists of a number of messaging components. From an administrative point of view, the primary building blocks of the MHS are management domains (MDs). Note that these management domains are not the same as DNS domains—the Domain Name System (DNS) is used by SMTP messaging services, not X.400. A management domain is a collection of X.400 messaging systems having at least one Message Transfer Agent (MTA) managed by a specific organization. X.400 management domains come in two varieties:

- **Administrative Management Domains (ADMDs):** Messaging systems managed by an administrator or a registered private agency. These are the top-level management domains that handle third-party messaging traffic. An example is a telephone carrier service company such as AT&T.
- **Private Management Domains (PRMDs):** Unique subscriptions to an ADMD, such as telephone numbers of users. PRMDs can send or receive messages from an ADMD, but PRMDs cannot communicate directly with each other.

An X.400 MHS consists of the following five kinds of messaging components:

- **Message Transfer Systems (MTSs):** Collections of one or more MTAs that function together to provide message-forwarding services for a particular X.400 domain.
- **Message Transfer Agents (MTAs):** Route and deliver transport messages to and from User Agents (UAs) and with other MTAs. An MTA corresponds to a mail server in a typical local area network (LAN)–based messaging system. MTAs maintain a database of all UAs registered in their domain and routing tables that indicate how messages should be forwarded to other domains.
- **Message Stores (MSs):** Temporarily store messages that an MTA has received until they can be processed and forwarded for delivery. X.400 thus uses a store-and-forward method of message delivery.



X.400. *Architecture of an X.400 Message Handling System (MHS).*

- **User Agents (UAs):** Provide messaging functionality directly to users. From a practical point of view, a UA can be identified as the e-mail client software that a user is running; from an abstract point of view, a UA is a domain belonging to a user and consisting of additional subcomponents. The goal of an X.400 MHS is to facilitate exchange of messages between different UAs.
- **Access Units (AUs):** Gateways between an X.400 MHS and another messaging system such as a telex or fax system.

Each UA in an X.400 MTS is identified by a special X.400 address called an Originator/Recipient (O/R) address. The O/R address is the e-mail address of the X.400 user and can be quite complex compared to an SMTP e-mail address, which is one reason that SMTP has overtaken X.400 in popularity as a global messaging standard. An O/R address consists of a series of VALUE=ATTRIBUTE pairs separated by semicolons. Not all fields need to be complete—only those that uniquely identify the recipient are required. Here is an example of an X.400 address:

```
C=US;A=MCI;P=MICROSOFT;O=SALES;S=SMITH;G=JEFF;
```

The individual address fields are as follows:

- Country (C) is United States
- ADMD (A) is MCI
- PRMD (P) is Microsoft (company name)
- Organization (O) is Sales Department of Microsoft
- Surname (S) is Smith
- Given name (G) is Jeff

An X.400 message consists of a P1 envelope and its P2/22 message contents. The envelope contains the e-mail address information needed for routing the message to its destination. The X.400 protocol for a message envelope includes support for message tracking and delivery priority features. The X.400 protocol for the message content includes a header and body part for the message.

What typically happens in the message transfer process is that a UA sends a message addressed to another UA in the MHS. The message is forwarded to an MTA in the local MTS, which either delivers the message locally or forwards it to a remote MTA for handling, depending on where the destination UA is located. The message is passed from MTA to MTA until it reaches the MTS of the destination UA, whereupon it is either delivered if the destination UA is connected or stored in an MS until the UA can retrieve it.

See Also: *e-mail, P-series protocols, Simple Mail Transfer Protocol (SMTP), X-series*

X.500

An International Telecommunication Union (ITU) recommendation for a global directory.

Overview

A directory is a tool designed to provide a single source for locating, organizing, and managing a network's resources within a business or enterprise. The X.500 recommendations define a global, hierarchical directory that includes the following features:

- A vendor-neutral standards-based directory based on ITU recommendations
- A single, global, hierarchical namespace of objects and their attributes
- Data management functions for viewing, adding, modifying, and deleting directory objects
- Search capabilities for customizing complete data queries



X.500. *Architecture of an X.500 directory.*

Implementation

From an administrative point of view, the building blocks of the X.500 directory service are Directory Management Domains (DMDs). An X.500 DMD is a collection of X.500 components that includes at least one Directory System Agent (DSA) and is managed by a Domain Management Organization (DMO). There are two types of DMDs:

- **Administrative Directory Management Domains (ADDMDs):** Directory services managed by a registered private agency that provide public directory services. Examples of ADDMDs are Four11 and Bigfoot, which provide public X.500 directory services over the Internet.
- **Private Directory Management Domains (PRDMDs):** Directory services that provide private directory access. An example is a domain controller hosting Active Directory directory service on a network running Microsoft Windows 2000.

The three main components of an X.500 directory are

- **Directory Information Base (DIB):** The actual hierarchical database that contains all the information in the directory. X.500 uses a distributed directory hierarchy in which different subsets of the DIB are found on different servers at different locations. From the user's point of view, however, the entire global X.500 directory appears to be accessible from the local directory server that the Directory User Agent (DUA) connects to. A schema is used to define the various classes of objects and their attributes, which can be stored in the directory. The Directory Information Tree (DIT) is the naming hierarchy that describes the hierarchical structure of the DIB.
- **Directory System Agent (DSA):** A particular server that maintains a subset of the DIB and provides an access point to the directory for DUAs to connect. Each DSA is responsible for a subset of the DIB and includes a set of naming contexts that define objects that are near each other in the DIT. DSAs also communicate with each other for directory replication purposes. This ensures that each DSA's subset of the DIB is current and complete and helps maintain the integrity of the whole X.500 directory system.

- **Directory User Agents (DUAs):** The client software that accesses the X.500 directory on behalf of the user. DUAs can perform such actions as searching, reading, updating, and deleting information in the directory, depending on the level of functionality of the client and the level of access granted to the user. The functionality of a DUA can be built into any type of software, including e-mail clients, Web browsers, or even the operating system itself.

To access information in the directory, a DUA connects to a local DSA and queries the directory by using the Directory Access Protocol (DAP), the standard X.500 protocol for locating, accessing, and modifying information in an X.500 directory. Various attribute-based search methods are possible using X.500-based directory services, including the following:

- White pages searches, for name-to-address lookups
- Yellow pages searches, for looking up a category
- Browsing, for listings related to a given attribute

When a DUA issues a query, the query travels through a chain of DSAs and a result set travels back along the same chain. These queries use DAP, while DSAs communicate with each other using the Directory System Protocol (DSP).

Marketplace

X.500 forms the architectural basis of Active Directory in Windows 2000 and Windows .NET Server, Novell Networks' Novell Directory Services (NDS) eDirectory, Oracle Corporation's Internet Directory (OID), and other popular directory services. Neither Active Directory nor NDS are full X.500 directories, however, although full X.500 directories are offered by a few vendors, including Global Directory Server from Critical Path, eTrust from Computer Associates, and DirX from Siemens.

Prospects

Despite the compelling features of X.500, it is not widely used for several reasons:

- It is a complex directory that was originally based on network protocols used by the Open Systems Interconnection (OSI) reference model and incurs considerable protocol overhead on Transmission Control Protocol/Internet Protocol (TCP/IP) networks.
- It has no native global name registration facility such as the Internet's Domain Name System (DNS), which makes it difficult to implement it as a truly global standard.

The feature-heavy Directory Access Protocol (DAP) used by X.500 is particularly complex and has been widely replaced by the Lightweight Directory Access Protocol (LDAP) developed by the University of Michigan and standardized by the Internet Engineering Task Force (IETF). LDAP directories such as iPlanet's Directory Server and InnoSoft's IDDS are generally more popular than full X.500 ones and much easier to manage, though offering fewer features.

See Also: *Active Directory, directory, Directory Access Protocol (DAP), Lightweight Directory Access Protocol (LDAP), Novell Directory Services (NDS), X-series*

xDSL

Refers to different "flavors" of Digital Subscriber Line (DSL), a group of broadband telecommunications technologies supported over copper local loop connections.

See Also: *Digital Subscriber Line (DSL)*

Xerox Network Systems (XNS)

A suite of networking protocols developed by Xerox Corporation's Palo Alto Research Center (PARC) in the early 1980s.

Overview

Xerox Network Systems (XNS) is based on a five-layer model, in contrast to the seven-layer Open Systems Interconnection (OSI) reference model for networking. The layers of the XNS protocol stack are as follows:

- **Level 0 (media access layer):** Maps to the OSI physical layer and data-link layer and performs similar functions. XNS does not tie into any one media access protocol and supports the Ethernet, High-level Data Link Control (HDLC), Token Ring, and X.25 protocols, among others.

- **Level 1 (network layer):** Maps to the OSI network layer and defines the Internet Datagram Protocol (IDP). IDP functions similarly to the Internet Protocol (IP) of Transmission Control Protocol/Internet Protocol (TCP/IP) and uses a logical addressing scheme that requires four-byte network numbers, four-byte host numbers, and two-byte socket numbers for both source and destination addresses. IDP is responsible for delivering datagrams by using unicast, multicast, and broadcast methods. Level 1 also defines the Routing Information Protocol (RIP), which handles dynamic routing and has evolved into later versions for use in Internetwork Packet Exchange/Sequenced Packet Exchange (IPX/SPX) and TCP/IP networks.
- **Level 2 (transport layer):** Maps to the OSI transport layer and defines the Sequenced Packet Protocol (SPP). SPP functions similarly to the Transmission Control Protocol (TCP) of TCP/IP and is responsible for providing reliable transmission of IDP packets, including sequence numbers and acknowledgments. Level 2 also defines the Packet Exchange Protocol (PEP), which functions similarly to the User Datagram Protocol (UDP) of TCP/IP. For troubleshooting purposes, the Echo Protocol (EP) functions similarly to the ping utility of TCP/IP.
- **Level 3:** Maps to the OSI presentation layer and includes the Filing Protocol (FP), Clearinghouse Protocol (CP), Printing Protocol (PP), and others.
- **Level 4:** Maps to the OSI application layer (XNS has no level that maps to the OSI session layer).

XNS is little used today, but it was important in the evolution of other networking protocols, such as IPX/SPX and TCP/IP.

See Also: *IPX/SPX-Compatible Protocol, protocol, Transmission Control Protocol/Internet Protocol (TCP/IP)*

XHTML

An enhanced version of Hypertext Markup Language (HTML) developed by the World Wide Web Consortium (W3C).

Overview

XHTML is basically a reformulation of HTML 4.01 in Extensible Markup Language (XML) using an XML document type definition (DTD). In other words, XHTML is HTML defined in terms of XML. XHTML thus includes all the functionality of HTML while being fully compliant with XML and including the extensibility and portability of XML.

XHTML is expected to smooth the migration from HTML to XML by allowing developers to create HTML documents that contain XML functionality and are compliant with XML applications. Some of the advantages of using XHTML instead of HTML for Web content development include

- Easier portability to nonstandard user interfaces
- The ability to create new DTDs

Web sites can be developed in or migrated to XHTML without worry of browser incompatibility because XHTML conforms to the operation of existing HTTP user agents. Migrating HTML sites to XHTML ensures that site content is XML-conforming, which is advantageous because it is likely that XML will eventually become the paradigm for developing all Web content.

The current standard is XHTML 1, which was released in January 2000.

For More Information

Find out more about XHTML at *www.w3.org/TR/xhtml1*.

See Also: *Hypertext Markup Language (HTML), World Wide Web Consortium (W3C), XML*

XML

A meta-language used as a universal standard for electronic data exchange. The acronym stands for Extensible Markup Language.

Overview

XML is a derivative of Standardized Generalized Markup Language (SGML), an International Organization for Standardization (ISO) standard developed in 1986. SGML allows you to programmatically describe the structure and content of an electronic document. XML is basically a subset of SGML and is a language that can be used for creating other languages. Numerous XML "dialects" have been developed in the last few years for different sectors of industry. These dialects allow companies within each sector to exchange business information electronically and perform such business transactions as ordering, invoicing, and payment.

The goals of the designers of XML were to create a meta-language for developing business dialects that

- Supports a wide range of applications and processing schemes including client/server, distributed, and multi-tier
- Is easy to implement and use over the Internet
- Creates documents that are human-readable
- Is formal, concise, easy to understand, and has few optional features

History

Electronic business communication emerged in the 1970s when companies such as Kmart and Sears developed proprietary electronic processes for simplifying communication between stores and suppliers. Using these processes, large companies were able to reduce the amount of paperwork involved in their business transactions and save costs because of the reduced amount of labor involved in processing electronic communications over paper ones. Toward the end of the 1970s the U.S. government and companies from the transportation and manufacturing sectors worked with the American National Standards Institute (ANSI) to develop uniform standards for the electronic exchange of business information. The result of this effort was the ANSI X12 standard, which formed the basis of electronic data interchange (EDI). EDI basically defines the format and protocols for electronic exchange of invoices, purchase orders, receipts, and other documents.

EDI has been widely used by business, industry, and government, but its complexity and high cost have tended to limit its implementation in large enterprises. The high cost of EDI is mainly because it uses dedicated leased lines for exchange of business information between companies. To overcome the limitations of EDI, the World Wide Web Consortium (W3C) began developing XML in 1996 as an alternative to EDI, leveraging the popularity of Hypertext Markup Language (HTML) and the ubiquity of the Internet as a communication medium. Although EDI is intrinsically secure because it uses dedicated leased lines, XML requires an additional mechanism for ensuring secure transmission of electronic documents over the unsecure public Internet—for example, by employing a virtual private network (VPN).

The initial XML standard called XML 1 was published in 1998, and the XML Working Group of the W3C steers further development of the language. XML standards continue to evolve, and the most important ones are outlined in the "Architecture" section later in this article.

Uses

One of the earliest implementations of XML was by Microsoft Corporation in their Channel Definition Format (CDF) push technology for the Web. Since then XML has been embraced by all sectors of industry and is supported by software from major vendors such as Microsoft, Oracle Corporation, SAP, and PeopleSoft and by application service providers such as Ariba and Commerce One. Hundreds of different dialects (schemas) have been developed for different industry sectors—for example, to name a few:

- **ACORD XML:** An XML schema developed by the insurance industry for electronic exchange of life insurance information
- **ADPr:** Stands for Active Digital Profile; used for exchanging provisioning information for IT (information technology) products and services
- **AgXML:** Schema for the agricultural products sector developed by Monsanto, Archer Daniels Midland, and other members of this sector and managed by an independent nonprofit organization called AgXML LLC

- **BizTalk:** An XML framework from Microsoft for general e-commerce
- **BPML:** Stands for Business Process Modeling Language, a schema developed by a consortium of 80 companies to standardize how business processes are modeled
- **CDA:** Stands for Clinical Document Architecture, a schema for health care companies to share clinical and patient information electronically
- **CXML:** An XML schema developed by Commerce One for e-commerce
- **MathML:** Used by the academic sector for formatting documents containing mathematical expressions
- **RosettaNet:** XML schema for the high-tech manufacturing industry that has been embraced by over 300 different vendors
- **XKMS:** Stands for XML Key Management Specification, an XML specification developed by the financial and credit sector for secure electronic banking and credit transactions

Comparison

XML resembles HTML in many ways—for example, both languages use plain text files that are marked up using tags. But there are significant differences between XML and HTML, namely the following:

- XML markup describes the data itself, but HTML markup determines how the data is displayed in a Web browser. In other words, although HTML is a markup language, XML is a language for creating new markup languages. Note that unlike HTML, XML itself does not control how data is displayed. Instead, this feature is supported in XML through an associated standard called Extensible Stylesheet Language (XSL).
- HTML uses a fixed set of tags, but XML allows users to create their own tags to describe any kind of data.
- XML documents are easier to search than HTML ones because each kind of data has its own unique type of tags associated with it.
- HTML documents are basically designed for display in Web browsers, but XML can be used as a general language that allows all types of applications to communicate with one another.

Architecture

XML actually embraces a whole series of standards for different language and protocols, and it is still evolving as new pieces are developed and come into play. Some of the important parts of the XML specification include

- **Extensible Stylesheet Language (XSL):** Specifies how XML documents are displayed in a Web browser or other standard interface and allows XML documents to be translated into other types of documents such as HTML Web pages. Although XML documents contain the content (data) used by an application, XSL style sheets format the content of these documents to make them visually understandable. For example, an XSL style sheet could specify how an electronic invoice is displayed in HTML. Microsoft Internet Explorer includes a default XSL style sheet that can be used to display the contents of XML documents in the browser window.
- **Extensible Stylesheet Language Transformations (XSLT):** Allows XML documents to be translated into other types of documents regardless of whether they ever need to be human-readable. XSLT is essentially one-half of XSL, the “translation” part, without any consideration of the “display” part.
- **XPath:** Provides a programmatic syntax for querying XML documents to locate and select specific types of data within them. For example, an XML-enabled application could use XPath to extract pricing information from invoice documents.
- **Xpointer:** Complements XPath by allowing you to identify a portion within an XML document for further processing.
- **XML Query:** Like XPath, XML Query also lets you search for and extract specific kinds of information from an XML document, but XML Query offers a more database-like approach to this process. XML Query is currently still under development by the W3C.

- **XLink:** Provides a standard way of representing hyperlinks within XML documents.
- **Xinclude:** Copies a portion of an XML document into the current document. Compared to Microsoft's Object Linking and Embedding (OLE) technology, XLink is like Linking and XInclude is like Embedding. XInclude is also currently under development by the W3C.
- **Xbase:** Provides a method of coding relative hyperlinks within XML documents.
- **Document type definition (DTD):** A language that allows you to define an XML dialect. Each dialect requires an associated DTD that specifies the structure and syntax of valid and well-formed documents for that dialect. DTD is a complex language that is different from XML and much harder to read and is expected to be superceded by XML Schema, which is described next.
- **XML Schema:** A newer method for defining XML dialects than the older DTD specification. XML Schema uses XML itself to create special documents called schemas that describe the structure and syntax of a particular XML dialect. Hundreds of XML schemas have been developed (see the Implementation section below).
- **Resource Description Framework (RDF):** Specifies how document metadata such as copyright and search keywords can be embedded in XML documents. RDF makes it easier to manage large numbers of XML documents in a collection or repository.
- **Document Object Model (DOM):** Allows XML documents to be parsed into the native object format of a standard programming language. DOM makes it easier for developers to XML-enable their applications.
- **SAX:** Similar to DOM, but instead of reading the entire XML document into memory to process it (as DOM does), SAX allows applications to read through XML documents in real time and trigger events when certain conditions arise. Unlike the other XML standards described above, which are standardized by the W3C, SAX is an open-source project.
- **Simple Object Access Protocol (SOAP):** Enables applications to access remote objects using XML. SOAP is a specification developed by IBM and Microsoft.
- **Uniform Description, Discovery, and Integration (UDDI):** Enables vendors to expose their proprietary XML schemas to each other through a distributed directory service.
- **XAML:** Developed by IBM, Oracle, Hewlett-Packard, and Sun Microsystems, this emerging XML standard is designed to simplify the process of coordinating complex business transactions between multiple parties.

Implementation

XML requires much stricter adherence to formatting rules than HTML does. Specifically, XML documents must be

- **Well-formed:** Complies with the general rules and syntax of XML. For example, in an XML document every opening tag requires a corresponding closing tag. In HTML you can get away with omitting closing tags (omitting the </p> in a <p>…</p> expression, for example), but not so in XML—the rules must be strictly followed. Another example is that all attributes within tags must be enclosed in quotes. For example, in HTML you could have either <font size=4> or <font size="4">, and both would be interpreted correctly by most browsers. In XML only the second of these statements would be considered acceptable in a well-formed document. Other essential aspects of XML formatting include case sensitivity (HTML is not case sensitive) and proper nesting of elements (HTML lets you get away with coding <p>…</p> instead of <p>…</p>).
- **Valid:** Complies with the rules specified in the documents corresponding DTD or schema. In other words, the vocabulary of a particular XML dialect is limited to what is defined in that dialect's "dictionary."

Examples

A simple example of an XML document is the following, which contains the name and phone number for a sales contact person:

```
<?xml version "1.0"?>
<contact_book>
    <contact type="sales">
       <name>
          <first_name>Jeff</first_name>
          <last_name>Smith</last_name>
       </name>
       <phone>555-1212</phone>
    </contact>
</contact_book>
```

The first line of this document (required) is called the prolog, and it informs the XML parser within an application that it is parsing an XML document and other relevant information. The rest of the document is called the document element and contains the data to be used by the application. Note how you can use XML to define tags that are used to describe what the data is about. The "extensible" nature of XML lies in the fact that you can create custom tags to describe different kinds of data as needed. For example, you could create an <im> tag to include the Instant Messaging (IM) identifier for the contact above.

Prospects

Although XML has captured the minds of industry and software vendors alike as a way to simplify and reduce the cost of doing business electronically, few businesses have actually implemented full XML-based business-to-business (B2B) solutions. The reasons for this include

- XML standards have evolved considerably in the few years since XML originated, and they are still evolving. As a result, before implementing XML solutions, many businesses are adopting a "wait-and-see" approach until XML becomes a mature standard.
- Although EDI is expensive and complex, those who have implemented EDI solutions often see little incentive to change, taking an "if it ain't broke, don't fix it" approach.

Despite these issues, it seems almost inevitable that XML will eventually succeed in dominating the electronic business marketplace due to its flexibility, power, and ease of use. A number of vendors are developing workaround approaches to help companies migrate from EDI to XML. For example, Vitria Technology, PaperFree Corporation, and several other companies have created Web-based applications that allow businesses to access EDI documents using a standard Web browser interface and to translate EDI messages into XML.

For More Information

Visit the W3C's XML site at *www.w3.org/xml.* Other useful sites to visit include *www.xml.org* and *www.xml.com.*

See Also: *B2B, Electronic Business Extensible Markup Language (ebXML), electronic data interchange (EDI), Hypertext Markup Language (HTML), Simple Object Access Protocol (SOAP), Universal Description, Discovery, and Integration (UDDI), virtual private network (VPN), World Wide Web Consortium (W3C)*

XNS

Stands for Xerox Network Systems, a suite of networking protocols developed by Xerox Corporation's Palo Alto Research Center (PARC) in the early 1980s.

See: *Xerox Network Systems (XNS)*

X-series

A series of standards and recommendations from the International Telecommunication Union (ITU) dealing with data communication over computer networks and telecommunication services.

Overview

Some of the more important X-series standards and recommendations include the following:

- **X.25:** Defines a protocol for a global packet-switching network for wide area network (WAN) connectivity. Related X-series protocols include X.3, X.28, X.29, X.92, X.96, X.110, and X.121.

- **X.400:** Defines a standard for a global message handling system for e-mail. Related protocols include X.402, X.403, X.407 (ANS.1), X.408, X.411, X.413, X.420, and the P-series protocols.
- **X.500:** Defines a recommendation for a global directory service. Related protocols include X.501, X.509, X.511, and X.518 through X.521.

See Also: *X.25, X.121 address, X.400, X.500*

xSP

Represents the various “flavors” of service providers that emerged in the late 1990s.

Overview

The earliest of the new breed of service providers that emerged in the 1990s was the Internet service provider (ISP), which originally meant a company that provided connectivity with the Internet, usually dial-up for home users and T1 or fractional T1 lines for businesses. As the number of ISPs on the market exploded in the late 1990s, many of the larger ones began to offer additional services to customers including Web hosting, custom Web application development, and e-commerce storefronts. Soon many players in the Internet marketplace began to refer to themselves as different types of service providers in an effort to differentiate themselves from one another according to the services they specialized in offering. Today a growing number of service providers have emerged, often overlapping in the services they offer and changing their focus to adjust to the market. Currently the list includes

- **Application service provider (ASP):** A company that offers software services to business customers across the Internet, particularly services involving outsourcing of Web and e-business applications. ASPs were the next to occur after ISPs, and the late 1990s saw hundreds of them appear—and most of them disappear a year or two later.
- **Business service provider (BSP):** Basically an ASP that provides a wide range of online business services that include not just Web hosting and e-commerce services typical of ASPs but also customer relations management, desktop maintenance support, system integration and consulting services, and other value-added business services.
- **Caching service provider (CSP):** A company that maintains caching servers that speed the transfer of information across the Internet’s infrastructure and offers managed access to these servers for a fee.
- **Commercial service provider (also CSP):** This broad term typically includes ISPs, online service providers, telephone and cable network operators, and similar companies.
- **Content service provider (again CSP):** Helps organizations maintain fresh content on their portals without the need or cost of creating their own internal publishing house.
- **Full-service provider (FSP):** Really just another name for BSP.
- **Hosting service provider (HSP):** Basically an ISP that concentrates on Web hosting.
- **Management service provider (MSP):** A company that manages the (IT) information technology infrastructure for other businesses.
- **Storage service provider (SSP):** A company offering outsourced storage services to businesses.
- **Security service provider (also SSP):** A company offering outsourced security services to businesses.
- **Wireless application service provider (WASP):** An ASP that supports wireless business applications.

Together, all these different types of service providers are generally grouped under the acronym *xSP*, where *x* represents a variable that can be replaced by other letters, such as *I* for Internet or *A* for Application.

See Also: *application service provider (ASP), caching service provider (CSP), commercial service provider (CSP), Management Service Provider (MSP), outsourcing, storage service provider (SSP)*

X Window System

A multiuser client/server graphical user interface (GUI) for UNIX environments.

Overview

The X Window System, also known simply as X, provides a multitasking GUI windowing environment for network-attached UNIX workstations and terminals. The Massachusetts Institute of Technology (MIT), Stanford, and IBM jointly developed X starting in 1984. The first popular release of the platform was X version 11, which came out in 1987. In 1988 the X Consortium was formed to steer development of the system, and Release Six of X, usually called X11R6, appeared in 1996 and remains the most popular version of X. In 1997 the X Consortium turned over responsibility for overseeing further development of X to The Open Group.

Elements of X include the following:

- **X servers:** These form the server portion of the X Window System and are typically UNIX servers but can also be mainframe computers running UNIX.
- **X clients:** These are typically UNIX desktop workstations running the X Window System client software. The client software enables the workstations to display a windowed GUI in the X Window System environment. An alternative to using workstations is using X terminals, which are dumb terminals that have no operating system and use a ROM routine to implement X client software. X terminal machines always must be connected to X servers by using local area network (LAN) connections, in contrast to character-based dumb terminals, which usually use serial connections such as RS-232 or X.21.
- **X protocol:** This is the protocol used for communication between X clients and X servers, and it enables the client to send keyboard and mouse data to the server and display the GUI on the client.
- **X window manager:** Examples include OSF/Motif and K Desktop Environment (KDE), which implement windowing features such as menus, toolbars, and gadgets that provide the look and feel of a windowing GUI environment that allows X applications to run.

X is available on all UNIX platforms and on Linux distributions, and there are even versions for Microsoft Windows, OS/2, and the Macintosh platform.

For More Information

Visit X.Org at *www.x.org.*

See Also: *K Desktop Environment (KDE), UNIX*

Y

Y2K

Also called the year 2000 problem or the millennium bug (even though it is not actually a bug), a computer problem that was expected to affect older hardware and software on January 1, 2000. Similar problems were expected to arise on other dates, particularly September 9, 1999, and February 28, 2000.

Overview

The Y2K problem represented a family of problems that were anticipated at the turn of the millennium. These problems were expected to arise from three primary sources: internal representation of dates, incorrect programming of leap years, and specialized use of certain key dates.

The issue of internal representation of dates in computer software was expected to be the most critical Y2K-related issue. This is because until recently, most software had been written to store date information in a format that used only the last two digits of a year to represent the year. For example, the year 1960 was internally represented as 60. In the early days of programming, system and disk memory were expensive and had to be carefully optimized, and saving 2 bytes by representing the date 1954 internally as the two-digit number 54 yielded significant savings on a system with limited RAM. This type of “good programming practice” continued even into the mid-1990s. And even though some programmers were aware of potential Y2K problems early on, no one expected programs developed in the 1970s and 1980s to continue being used into the next millennium. This date representation issue was the most commonly identified version of the year 2000 problem because the year 2000 would have been represented internally as 00, which is the same representation for the date 1900. In fact, most older software did interpret the internal date 00 as 1900 instead of 2000, which was expected to lead to problems when calculations were performed using dates. For example, many analysts predicted that financial software might calculate that an employee born in 1954 was actually 00 - 54 = -54 years old in the year 2000, and that such negative ages could lead to such problems as missed paychecks or pension contributions—which on a large scale could have had disastrous social consequences.

This date-representation issue was not just a software application problem but also involved PC hardware, specifically in relation to the real-time clock (RTC) chip, which in most PCs uses only two digits to represent a year, and the basic input/output system (BIOS) routing, which is stored in flash ROM. If the BIOS did not contain code to roll over the century from 19xx to 20xx on January 1, 2000, the operating system would see the date 1900 when the user first turned on his or her PC in the year 2000. In some systems this problem could be fixed with a BIOS upgrade, but other systems had to be replaced with Y2K-compliant hardware.

Another Y2K-related issue was that the year 2000 was a leap year because it was divisible by 4, but some older software applications and hardware BIOS programs were expected to not recognize this fact and would therefore produce dates that were off by one day after February 28, 2000.

Finally, many older software applications used special dates to represent special situations. For example, many older COBOL applications gave the date 9/9/99 a special meaning such as “this item is to be saved forever” or “this item is to be deleted after 30 days.” Such applications, therefore, had the potential to produce unpredictable results after September 9, 1999.

Fortunately, the IT (information technology) industry was well aware of these problems years in advance and publicized the potential loss of business that could arise should these issues not be fixed in time. Hardware vendors released new versions of BIOS and other system code to ensure Y2K compliance, and software vendors issued new versions of applications or fixed Y2K issues using service packs and hotfixes. Similarly, IT departments around the world addressed Y2K concerns by allocating resources to upgrading legacy hardware such as PCs built before 1996, upgrading software and applying service packs to eliminate Y2K-related issues, and debugging and rewriting custom software to eliminate other possible date-related bugs. This turned out to be an enormous task—for example, an estimated 180 billion lines of COBOL code had been written for mainframe environments in business, industry, and government, and much, if not most, of this code had the potential to be affected. Y2K problems were not limited to the mainframe arena but also affected server and desktop operating systems and applications on UNIX, Macintosh, and Microsoft Windows platforms, which in turn affected hardware BIOS programming, operating systems, application software, custom code, macros, and data files. The problem was enormous and well publicized, but government and public agencies, enterprise-level businesses, and software and hardware vendors had devoted extensive resources to ensure that systems functioned properly on and after January 1, 2000. The result of these efforts was that instead of the end of the electronic world occurring at the beginning of the new millennium, virtually all government agencies and businesses around the world experienced little more than hiccups in their operation. The Y2K problem, which threatened to be one of humanity's greatest disasters, turned out to be one of IT's greatest triumphs.

Y-connector

A type of connector that can be used to connect a single device or cable to two devices or cables.

Overview

Y-connectors are used in several places in computer networking and systems interconnection. Some examples of different types of Y-connectors include the following:

- **RJ-11 Y-connector:** Allows two or more telephone devices to be plugged into a single RJ-11 wall plate. Some vendors call these adapters modular coupler splitters. This arrangement allows only one of the devices to work at any given time.



Y-connector. *A typical SCSI Y-connector.*

- **SCSI Y-connector:** Allows a Small Computer Systems Interface (SCSI) device to be added to the middle of a chain of SCSI devices. A typical SCSI Y-connector has one 50-pin Centronics male connector and two 50-pin Centronics female connectors. One use for a SCSI Y-connector is the connection of a single RAID 5 SCSI array to two nodes of a Microsoft Windows 2000 server cluster.

See Also: *RJ connectors, Small Computer System Interface (SCSI), Y-splitter*

Y-splitter

Also called a Y-cable, a type of cable adapter that is arranged in a Y-shaped formation and is used to connect one device to a pair of other devices.

Overview

Y-splitters are used in a number of scenarios in computer networking and systems interconnection. Some examples of where Y-splitters may be used include the following:

- **PS/2 Y-splitter:** Typically used to connect an external keyboard and mouse to a single PS/2 port on a laptop such as the IBM ThinkPad. This type of splitter typically has cables that are about 1 foot (30 centimeters) long. PS/2 Y-splitters should use shielded cabling for best operation in noisy electrical environments.
- **Internal power Y-splitter:** An adapter used inside a PC to connect additional internal drives to the internal power supply of the PC. This type of splitter comes in various arrangements for connecting different combinations of hard disk, CD-ROM, and floppy disk.

- **External power Y-splitter:** An adapter commonly used with high-end Ethernet switches to connect them to two redundant external power supplies. If one power supply fails, the other immediately takes over the load, and the failed power supply can be hot-swapped with a replacement.
- **RS-366 Y-splitter:** Used for some videoconferencing systems running in dual port mode over Integrated Services Digital Network (ISDN) connections.

PS/2 Y-splitter



Internal power Y-splitter



Y-splitter. *Examples of two kinds of Y-splitters.*

See Also: *Integrated Services Digital Network (ISDN), Y-connector*

ZAK

Stands for Zero Administration Kit, a collection of tools, methodologies, and guidelines developed for Microsoft Windows 95, Windows 98, and Windows NT 4 that network administrators can use to implement policy-based management of Windows NT–based networks.

See: *Zero Administration Kit (ZAK)*

Zero Administration Kit (ZAK)

A collection of tools, methodologies, and guidelines developed for Microsoft Windows 95, Windows 98, and Windows NT 4 that network administrators can use to implement policy-based management of Windows NT–based networks.

Overview

Microsoft Corporation developed the Zero Administration Kit (ZAK) as part of their Zero Administration Initiative for Microsoft Windows (ZAW), a multifaceted approach designed to reduce the cost and effort of installing, configuring, and managing desktop workstations. ZAW was intended to provide tools and procedures that would simplify the administration of logons, security, applications, and other functions. The ZAK was the first result of the ZAW initiative, and it enabled administrators of Windows 95–, Windows 98–, and Windows NT 4–based networks to

- Manage the configuration of users' desktops from a central location without having to visit each computer. For example, you can specify exactly which applications the user can run, the appearance of the desktop, and where user data might be saved.
- Restrict local access to users' desktops. For example, you could lock down the desktops to prevent users from performing actions that might result in costly help desk calls, such as installing unapproved applications or modifying critical system files.
- Configure applications and data to be stored on network servers. This facilitated upgrading of applications, enabled centralized backup, and provided improved security by enabling administrators to download applications from the network and use local hard drives for caching.

Implementation

The ZAK employed the security of the NTFS file system (NTFS) along with Windows NT system policies and user profiles. Administrators could use the predefined set of system policies to override default local settings and use standard user profiles to configure and manage users' desktops from a central location. The ZAK included two preconfigured modes of operation, though advanced administrators could also create their own custom network configurations. The default modes were:

- **TaskStation Mode:** A desktop configuration that is designed for a "task-oriented" user such as a bank teller or a data entry person. This mode was ideal for users who required access to only one line-of-business application. TaskStation Mode completely locked down users' desktops and booted directly into Microsoft Internet Explorer or some other specified application. The user had no access to the Microsoft Windows Start button, taskbar, Task Manager, Control Panel, file system, or context menus in this mode of operation.
- **AppStation Mode:** A desktop configuration that is designed for typical "knowledge workers" who might use three or four business applications every day but may lack the knowledge and experience to configure or troubleshoot the system or install other applications. This mode provided users with a constrained Windows interface that allowed them access to only those applications they needed in order to perform their jobs. The user had no access to Task Manager, Control Panel, the file system, or context menus in this mode.

Notes

The Windows NT 4 ZAK has now been superseded by Intellimirror and Group Policy features in Windows 2000, Windows XP, and Windows .NET Server. These features provide greater management and control of user desktops and applications than ZAK provided.

For More Information

You can find ZAK at *www.microsoft.com/windows/zak.*

See Also: *Group Policy, IntelliMirror*

zone

In AppleTalk networking, a logical grouping of computers on a network.

Overview

A zone is to legacy AppleTalk networks of Apple Macintosh computers what a virtual LAN (VLAN) is to Ethernet networks. In other words, a zone is a logical way of grouping computers on a network regardless of the physical network segment they each reside upon. For example, a single zone may span several network segments, and multiple zones can be assigned to the same physical network.

Information concerning which zone a particular computer is on is propagated throughout an AppleTalk network using a protocol called the Zone Information Protocol (ZIP). Each computer maintains information about the zones other machines reside in using a local zone information table (ZIT). Administrators can configure which zone a computer belongs to by using the Choose utility on that machine.

Computers that belong to the same zone have access to the same set of shared resources on the network. If a user moves to a different physical network, the user can still belong to the same zone provided the router interface in the user's new location belongs to that zone.

Notes

The term *zone* is also used to refer to a zone of authority, a portion of the Domain Name System (DNS) namespace that is managed by a particular name server.

See Also: *AppleTalk, zone of authority*

zone file

A file on a name server that contains information about a zone in which the name server is authoritative.

Overview

A zone file is a text file consisting of a series of resource records that form the Domain Name System (DNS) database of the name server. These records identify the domain and subdomains that the name server is responsible for managing, Internet Protocol (IP) address to host name mappings for hosts within these domains and subdomains, timing parameters for zone transfers between primary and secondary name servers, and other data.

A name server typically has at least three zone files:

- **<root_domain>.dns:** The forward lookup zone file that is used to resolve host names into IP addresses for Transmission Control Protocol/Internet Protocol (TCP/IP) hosts over which the name server has authority. In the example that follows, the root domain is microsoft.com, and therefore the zone file is microsoft.com.dns.
- **z.y.x.w.in-addr.arpa:** The reverse lookup zone file for the forward lookup zone, which is used to resolve IP addresses into host names for TCP/IP hosts over which the name server has authority. In the example that follows, the network ID is 192.250.100.0, so the reverse lookup zone file is 100.250.192.in-addr.arpa.dns.
- **cache.dns:** A standard file that exists on all name servers and that contains the host names and IP addresses of name servers on the Internet that maintain the root domain of the entire DNS namespace.

Examples

A typical zone file might look like this:

```
; Database file microsoft.com.dns for
microsoft.com. zone.
@             IN      SOA
dns1.microsoft.com.   admin.microsoft.com.
              12      ; serial number
              3600    ; refresh
              600     ; retry
              86400   ; expire
              3600    ; minimum TTL
```

```
; Zone NS records
@            IN    NS    dns1
@            IN    NS    dns2
; Zone A records
dns1         IN    A     192.250.100.10
dns2         IN    A     192.250.100.11
proxy1       IN    A     192.250.100.101
fred         IN    A     192.250.100.102
wilma        IN    A     192.250.100.103
localhost    IN    A     127.0.0.1
www          IN    CNAME fred
ftp          IN    CNAME wilma
```

Notes

Microsoft Windows 2000 gives you the option of integrating DNS with Active Directory directory service. This results in zone information being stored in Active Directory, which has several advantages over traditional implementations of DNS such as Berkeley Internet Name Domain (BIND), in which zone data is stored in text files:

- It provides a more efficient mechanism for zone transfers through the domain replication process of Active Directory. This eliminates the chore of manually configuring zone transfers between primary and secondary DNS servers.
- It provides additional fault tolerance for the DNS information because all Active Directory integrated zones are primary zones and therefore contain a copy of the zone data.

See Also: *Active Directory, Berkeley Internet Name Domain (BIND), Domain Name System (DNS), IP address, name server, resource record (RR), zone of authority, zone transfer*

zone of authority

A portion of the Domain Name System (DNS) namespace that is managed by a particular name server.

Overview

A zone of authority (often simply called a zone) is an administrative unit of DNS namespace and can consist of a single DNS domain or a domain combined with some of its subdomains. An example of a domain might be microsoft.com, which might contain the subdomains sales.microsoft.com, support.microsoft.com, and tech.microsoft.com. The name server that administers the microsoft.com domain is said to be authoritative for that domain. The zone of authority for such a name server might be, for example:

- **Microsoft.com and all three of its subdomains:** The name server contains information about all the hosts in Microsoft.com and in each of its three subdomains. This is not a particularly efficient approach, as it concentrates name resolution within a single name server and may place an undue burden upon the DNS administrator of the zone.
- **Microsoft.com and the two subdomains sales.microsoft.com and support.microsoft.com:** Authority for the subdomain tech.microsoft.com would be delegated to a different name server. This approach is useful if the tech.microsoft.com subdomain needs to be managed as a separate entity from the rest of microsoft.com.
- **Microsoft.com only, with none of its subdomains:** Authority for the subdomains is delegated to one or more name servers, and the name server for microsoft.com contains only delegation information about the other name servers and about hosts in the microsoft.com domain. This approach reduces the burden of administering hosts in the microsoft.com domain by distributing it to administrators in one or more delegated zones.

Note that the concepts of a zone and a domain are related: each zone is anchored in a specific domain known as the zone's root domain. However, not all of the subdomains of the domain necessarily belong to that same zone; those that have been delegated belong to different zones. Another way of saying this is to say that zones are bounded from one another by delegation—that is, each act of delegation creates a new zone.

Each name server must either

- Have its own local zone file, which contains the mappings between Internet Protocol (IP) addresses and host names for hosts found in that zone. A primary name server is one that has its own locally stored zone file called a primary zone file, which is implemented on Berkeley Internet Name Domain (BIND) name servers as a text file called a zone file.



Zone of authority. *Examples of zones delegated on the domain name system (DNS) namespace.*

or

- Download its zone file from another name server using a process known as zone transfer. A secondary name server has no local zone file but downloads it from the primary name server authoritative over the particular zone. This secondary zone file is a read-only file that can only be modified in its original version on the primary name server from which it has been downloaded. Secondary name servers are used in the DNS system mainly to provide redundancy.

A single name server can manage one or more zones, depending on how it is configured. For example, a name server might have one zone for the domain microsoft.com and another zone for the domain adventure.expedia.com.

In networks that use Microsoft Windows 2000 and Windows .NET Server, a zone can take yet a third form, called an Active Directory directory–integrated zone. In this type of zone, the zone information is stored in Active Directory directory service instead of in a text file, and it is replicated across the network using the standard directory replication method employed by domain controllers. Windows 2000 DNS also supports dynamic DNS (DDNS) to ease the administrative burden of manually maintaining zone files.

Notes

Do not confuse DNS zones with AppleTalk zones, discussed in the article “zone” elsewhere in this chapter.

See Also: *Active Directory, Berkeley Internet Name Domain (BIND), domain (DNS), Domain Name System (DNS), dynamic DNS (DDNS), IP address, name server, zone file, zone transfer*

zone transfer

The process of transferring zone information from a primary name server to a secondary name server.

Overview

Zone transfers are an essential part of the operation of the Domain Name System (DNS). Primary name servers maintain the master copy of the zone information for a particular DNS zone of authority, usually in the form of a text file called a zone file. Secondary name servers then download this information from the primary name server authoritative over their zone using the method of zone transfer. The advantages of this approach are that:

- If the primary name server goes down, the secondary name server has a complete, up-to-date copy of the zone file and can handle name resolution requests by DNS clients on the network.
- If a large number of DNS clients on the local network are making name resolution requests from a particular zone, these requests can be load balanced between the primary and secondary name servers for that zone.
- If the primary name server is located on the remote side of a slow wide area network (WAN) link, placing a secondary name server on the local side reduces bandwidth usage for the WAN link by allowing name resolution requests to be handled locally. In this scenario the only network traffic created by DNS is the occasional zone transfers that take place over the link.

Implementation

Zone transfers generally occur in three circumstances:

- When a secondary name server is rebooted.
- When the refresh interval for a secondary name server expires. This interval is defined in the start of authority (SOA) record at the beginning of the zone file on the primary name server.
- When changes have been made to the zone file on the primary name server and a notify list has been configured on the primary name server. A notify list is a list of Internet Protocol (IP) addresses that specify which secondary name servers are allowed to access zone information on the primary name server for purposes of zone transfer. The primary name server immediately notifies the secondary name server that the zone file has been modified and instructs it to initiate a zone transfer without waiting for the refresh interval to expire.

The secondary name server always initiates a zone transfer. Typically, the secondary name server periodically contacts the primary name server to determine whether any changes have been made to the primary name server's zone file. If so, it initiates a request for a zone transfer. Specifically, when the refresh interval expires on the secondary name server, the following occurs:

1. The secondary name server requests and receives the SOA record from the primary name server.
2. The secondary name server compares the version number in the primary name server's SOA record with its own current version number. If they differ, the secondary name server requests a zone transfer from the primary name server.
3. In standard DNS operation, the entire zone file is then transferred during this process.



Zone transfer. *How a typical zone transfer works.*

Notes

DNS as implemented on the Microsoft Windows 2000 and Windows .NET Server platforms allows zone information to be transferred incrementally using updates. In other words, the entire contents of the zone file are not sent when a small change is made to a resource record in the zone file. This method is called incremental zone transfer and is defined in RFC 1995.

An advantage of using directory-integrated DNS zones on Windows 2000 and Windows .NET Server is that the dnsZone object container in Active Directory can be secured using Windows 2000 access control lists (ACLs) for greater security.

See Also: *Domain Name System (DNS), incremental zone transfer, name server, zone file, zone of authority*

About the Authors

Mitch Tulloch is the author of 10 books, including the *Microsoft Encyclopedia of Networking, 1st Edition* (Microsoft Press); *Windows 2000 Administration in a Nutshell* (O'Reilly and Associates); and *Administering IIS4* (Osborne/McGraw-Hill). Mitch also has written articles for such industry magazines as *NetworkWorld* and is a regular contributor to myITforum.com and Swynk.com.

Mitch holds B.Sc. and Cert.Ed. degrees from the University of Manitoba and is a Microsoft Certified Systems Engineer (MCSE). He has more than 20 years of experience teaching and training in technical subjects and currently works as an independent consultant and writer. Mitch is also an accomplished keyboardist and is currently working on several CD projects. You can find out more about Mitch at his Web site, *www.mtit.com*.

Ingrid Tulloch is an experienced researcher who has contributed her skill and expertise to both the first and second editions of the *Microsoft Encyclopedia of Networking*. She is also a professional artist who has exhibited in several North American cities and holds B.A. and Cert.Ed. degrees from the University of Manitoba. You can find out more about Ingrid and view her art online at *www.mtit.com*.

Newnes Dictionary of Electronics


PC74HCT374P
607760T
HSS8823 B Y
IC232
74ACT151 PC
8820 X

S W Amos
R S Amos

Newnes

Newnes
Dictionary of Electronics

This page intentionally left blank

Newnes
Dictionary of Electronics
Fourth Edition

S. W. Amos, CEng, BSc, MIEE
R. S. Amos, BD, BSc, MISTC
Appendix by
G. W. A. Dummer, MBE, CEng, FIEE

Newnes

OXFORD AMSTERDAM BOSTON LONDON NEW YORK PARIS
SAN DIEGO SAN FRANCISCO SINGAPORE SYDNEY TOKYO

Newnes
An imprint of Elsevier Science
Linacre House, Jordan Hill, Oxford OX2 8DP
225 Wildwood Avenue, Woburn, MA 01801-2041

First published 1981
Reprinted 1982, 1986
Second edition 1987
Third edition 1996
Reprinted 1997, 1998
Fourth edition 1999
Reprinted 2000
Paperback edition 2002

Copyright © 1999 Elsevier Science Ltd. except Appendix (pp. 359–389)
Copyright © 1999 G. W. A. Dummer. All rights reserved

No part of this publication may be reproduced in any material form (including photocopying or storing in any medium by electronic means and whether or not transiently or incidentall to some other use of this publication) without the written permission of the copyright holder except in accordance with the provisions of the Copyright, Designs and Patents Act 1988 or under the terms of a licence issued by the Copyright Licensing Agency Ltd, 90 Tottenham Court Road, London, England W1T 4LP. Applications for the copyright holder's written permission to reproduce any part of this publication should be addressed to the publisher

British Library Cataloguing in Publication Data
A catalogue record for this book is available from the British Library

Library of Congress Cataloguing in Publication Data
A catalogue record for this book is available from the Library of Congress

ISBN 0 7506 4331 5

Printed and bound by Antony Rowe Ltd, Eastbourne

For more information on all Newnes publications
please visit our website at www.newnespress.com

Preface to First Edition

The British Standards Institution and the International Electrotechnical Commission have issued a number of publications containing definitions of the terms used in electronics.

The definitions in these published standards are, however, written by experts and intended, chiefly, for use by experts: they are therefore authoritative and brief. Such definitions are not ideally suited to the needs of engineers and technicians who are working in electronics, students who are studying the subject or amateurs interested in it: this dictionary is intended primarily for their benefit.

In this dictionary definitions are supplemented by explanatory material whenever this would seem helpful. Some entries are therefore short essays including diagrams: typical examples are the entries on 'camera tube', 'digital computer' and 'thyristor'. There are also short definitions where a single sentence gives all the information likely to be required: the definition of 'B battery' is an example.

The standard circuit arrangements used in electronic equipment, such as the Hartley oscillator, are defined in words but are more readily understood from circuit diagrams. A large number of such diagrams are therefore included in this dictionary and the graphical symbols used in them conform with BS 3939.

In the form of presentation adopted definitions are arranged in alphabetical order of the initial letter of the first word. Thus 'characteristic impedance' appears under C and not under I. Cross references are provided to draw the reader's attention to related terms and definitions which should assist understanding and attention is drawn to the most helpful of these by printing them in bold italics. Technical terms used in a definition are normally defined elsewhere in the book. An appendix giving many of the abbreviations and acronyms used in the literature has been added and should serve to guide a reader to the definition of a term known only by its abbreviation.

This dictionary is associated with the *'Dictionary of Telecommunications'* by S. J. Aries and the *'Dictionary of Audio, Radio and Video'* by R. S. Roberts. These subjects are closely related with electronics and share many technical terms. For this reason the authors of the dictionaries collaborated during their preparation to prepare a list of technical terms to be defined, to decide in which dictionary each term should appear and what depth of treatment each should receive. North American terminology was fully represented in this list to ensure that the dictionaries have the widest-possible English-speaking readership. It was agreed that some terms for common concepts should appear in all the dictionaries to make them largely self-contained but that detailed explanations of fundamental terms should be confined to the *Dictionary of Electronics*.

Thanks are due to ITT Semiconductors and Motorola Semi-conductor Products for providing information on short-channel MOS transistors.

S.W. Amos
1981

Preface to Second Edition

In this second edition a number of new definitions have been included and some which appeared in the first edition have been revised or expanded. Most of these changes were adopted to keep the dictionary *au fait* with recent developments in semiconductor devices, digital techniques, computers and microprocessors.

I gratefully acknowledge the willing help given by my son Roger and my neighbour Pat Thwaites in the preparation of the new edition.

S.W. Amos
Broadway, 1986

Preface to Fourth Edition

In an effort to keep up-to-date with the continuous flow of developments in electronics, the publishers decided to produce this new edition of the dictionary to incorporate the new terminology introduced since the third edition was published in 1996.

Because this new material is confined chiefly to the field of computing and data-processing equipment and consists largely of acronyms, the Appendix which lists abbreviations and acronyms has been completely rewritten. My son, Roger, and I record our thanks to G. W. A. Dummer, MBE, CEng, FIEE, who supplied most of the text of the new Appendix. As for the previous edition of the dictionary, Roger prepared the camera-ready copy of the new edition for the publishers.

S. W. Amos
Broadway, 1998

A

A battery (US) A battery used to provide the low-tension supply for ***electron-tube*** heaters or filaments.

abend Short for *abnormal end*. In computing ***fatal error*** conditions that require immediate termination of the user's session.

aberration In ***cathode ray tubes***, distortion of the image caused by failure of the electron beam to focus all points in the image accurately on the screen.

absolute permeability Of a material, the ratio of the magnetic flux density to the magnetising force which gives rise to it.

absolute permittivity Of an insulator, the ratio of the electric flux density to the electric field strength which gives rise to it.

absolute power level The magnitude of the power level of a signal at a point in a transmission system, usually expressed in ***decibels***, relative to a power of 1 mW, known as zero power level. For example, a signal power level of 1 μW is known as −30 dB.

absolute value device A device of which the output signal has an amplitude equal to that of the input signal but always has the same polarity irrespective of the polarity of the input signal.

absolute voltage level The magnitude of the voltage level of a signal at a point in a transmission system, usually expressed in ***decibels***, relative to a voltage of 0.775 V, known as zero voltage level. 0.775 V RMS is the voltage corresponding to a power of 1 mW in 600 Ω. A reference voltage level of 1 V is sometimes used in expressing the voltage level of the output of a microphone.

absorber circuit In a transmitter, a circuit, usually employing an ***electron tube***, which absorbs power from the transmitter when a break occurs in an ***oscillatory circuit*** so preventing the formation of an arc across the break which could cause damage.

absorption frequency meter (also known as ***wavemeter***) An instrument for measuring the frequency (or wavelength) of an RF signal, in which a calibrated resonant circuit is coupled to the RF source, maximum energy being absorbed from it when the circuit is resonant at the frequency of the signal.

absorption modulation A method of producing ***amplitude modulation*** in which the amplitude of the carrier is varied according to the power absorbed from it in a resistance the value of which is made to vary in accordance with the instantaneous amplitude of the modulating wave.

A-B test A subjective comparison of the quality of two audio or video signals by switching alternately between the two. Two items of equipment, e.g. hi-fi amplifiers, may be compared in this way. A three-head tape recorder may be tested by switching alternately between the source and playback output while recording a suitable high-quality source.

accelerated life test A form of life test so designed that the time taken to determine the probable life of a component or device is appreciably shorter than the probable life. For example, in an accelerated life test on a switch it may be operated far more frequently than would occur under normal working conditions.

accelerating voltage In an ***electron tube*** the voltage applied between the ***accelerator*** and the ***cathode***.

accelerator or **accelerating electrode** An ***electrode*** in an ***electron tube*** used to increase the velocity of electrons emitted from the cathode. It is usually in the form of a cylinder or a plate with an aperture so as not to intercept electrons but to direct them towards the anode or target electrode.

accentuation In audio-frequency engineering the emphasis of a particular band of frequencies, for example emphasis of the lower end of the audio spectrum, alternatively known as ***bass boost***.

acceptance test A test carried out on a device or equipment to demonstrate that it meets all the requirements of the buyer.

acceptor circuit A ***resonant circuit*** designed to present a low ***impedance*** at a particular frequency. When connected across a high-impedance circuit it acts as a ***notch filter*** which attenuates signals at the chosen frequency. The commonest form of acceptor circuit is a series *LC* combination. See ***rejector circuit, series resonance***.

acceptor impurity In semiconductor technology, a trivalent element such as boron, atoms of which can replace the tetravalent atoms in the lattice of a silicon or germanium crystal so making ***holes*** available as ***charge carriers***. See ***p-type semiconductor***.

acceptor level In the ***energy-level diagram*** of a ***p-type semiconductor*** an intermediate level slightly above the ***valence band*** which is empty at absolute zero temperature and to which electrons can be thermally transferred at other temperatures.

access time Of a ***store*** the time taken to obtain desired information. More specifically the interval between the instant at which the data is called for and the instant at which it is available at a specified location.

accumulator (1) A battery composed of ***secondary cells***. The most widely used forms of accumulator are the lead-acid battery employed in cars, and the nickel-iron battery. (2) In a computer or electronic calculator, a small-capacity ***store*** (or ***memory***) in which the results of an arithmetical calculation are kept until required for a further stage of the calculation.

acoustical impedance The complex ratio of the alternating sound pressure applied to an acoustic system to the resulting alternating volume velocity imparted to it. By analogy with electrical impedance, acoustical impedance is made up of acoustical resistance and acoustical reactance, and the latter can arise from ***inertance*** (acoustical analogue of inductance) and ***compliance*** (acoustical analogue of capacitance). Volume velocity is the product of linear velocity and the cross-sectional area of the system.

acoustic coupler A device enabling a normal telephone handset to be used for ***data transmission***. The handset is placed in a cradle forming part of the terminal equipment and is thus acoustically coupled to a microphone and loudspeaker within the terminal. The ***digital signals*** are converted into audio signals for transmission over the telephone circuit and at the receiving end are reconverted to digital form. The system is suitable only for low-speed transmission.

acoustic delay line A *delay line* which makes use of the time of propagation of sound waves in a solid or liquid medium.

acoustic feedback In general, *feedback* of sound from a loudspeaker to an early stage in the preceding amplifier. In the most familiar example, the sound is picked up by a microphone in a public address system but the effect can also arise when the sound is picked up by a microphonic electron tube or even a transformer. If the feedback exceeds a certain degree, sustained oscillation known as 'howlback' or 'howlround' occurs.

acoustic filter A *network* of acoustic elements designed to pass sound waves within certain frequency bands with little attenuation but greatly attenuating sound waves at other frequencies. Acoustic reactances can take the form of pipes, slots and boxes and these may be connected in series or in shunt so making possible a wide variety of types of filter as in electrical technology.

acoustics In general, the study of the production, propagation and effects of sound waves in solid, liquid and gaseous media. The term is also used to describe the properties of an environment which determine the distribution and absorption of sounds generated within it, i.e. a concert hall may be said to have good acoustics if the sound quality is good within it.

acoustic store A store utilising the properties of an *acoustic delay line*.

activation The treatment applied to *electron-tube* cathodes during manufacture to maximise electron emission. See *reactivation*.

active area Of a rectifier that area of the rectifying junction which effectively conducts current in the forward direction.

active circuit element Same as *active device*.

active current That component of the current in an alternating-current circuit which is in phase with the applied alternating voltage. The power dissipated in the circuit is the product of the RMS values of this component and of the applied voltage. See *reactive current*.

active device or **active element** A component in an electrical or electronic circuit which is capable of amplifying signals. The chief forms of active device are the *electron tube* and the *transistor*. Both require a source of power for their operation. See *amplification*.

active network See *network*.

active power In an alternating-current circuit the arithmetical mean of the product of the instantaneous voltage and instantaneous current over one period.

active transducer A *transducer* which requires a source of power for its operation other than that provided by the input signal. An example is an electrostatic microphone which requires a high-voltage source to charge the capacitor to enable the microphone to operate.

adaptive control Control which varies automatically so as to give optimum results from the controlling process. *Automatic gain control* is an example of adaptive control in which the gain of an amplifier or receiver varies automatically to give a constant level of output signal.

adder In general any device or circuit of which the output represents the sum of the inputs. In particular a combination of *logic elements* which accepts as inputs the signals to be added and the *carry* from any previous stage of addition and gives two outputs, one representing the sum of the inputs and the other the carry for a subsequent stage of addition. An adder can be composed of two ***half adders***.

address In a ***computer*** or ***data-processing equipment***, information, usually in the form of a ***binary word***, which identifies a particular location in a ***store***.

address register In a ***digital computer*** a ***register*** used to store ***addresses***.

admittance (*Y*) A measure of the ease with which an alternating current flows through a circuit. More specifically, admittance is the complex ratio of the current in an alternating-current circuit to the EMF which gives rise to it. It is the reciprocal of ***impedance*** and therefore has real and imaginary components as shown by the expression

$$Y = G + jB$$

where Y is the admittance, G is the conductance and B the susceptance. The numerical value of the admittance is given by

$$Y = \sqrt{(G^2 + B^2)}$$

The admittance concept is useful in solving problems where components are connected in parallel because conductances are added, and susceptances added or subtracted according to their sign to give the net admittance. The unit of admittance is the mho. See ***conductance***, ***susceptance***.

aerial Same as ***antenna***.

afterglow Same as ***persistence***.

after-image In a ***cathode ray tube*** a visual display which lasts after the stimulus causing it has ceased. See ***persistence***.

air cooling The cooling of components and active devices dissipating considerable power by transfer of heat to the ambient air by radiation and/or convection. See ***conduction cooling***, ***convection cooling***, ***forced-air cooling***.

air gap Of an ***inductor*** or ***transformer***, a small gap in the ***magnetic circuit*** deliberately introduced to increase the ***reluctance*** of the circuit and so prevent ***magnetic saturation*** of the core by the direct component of the current in the winding.

airtime The actual time spent by a subscriber using a ***cellular radio system*** such as a mobile telephone. The airtime is normally the basis of the charges levied by the service provider.

Algol See ***computer language***.

algorithm A commonly used sequence of arithmetical or logical operations that is applied to data.

alias In computing, an assumed name for a file or an application or a user.

aliasing The chunky appearance of an oblique or curved edge as displayed on a ***VDU*** or in a ***bitmap*** (*Figure A.1*). See ***anti-aliasing***.



Figure A.1 Bitmapped text from a VDU display, magnified by 4, showing aliasing

aligned-grid tube A ***tetrode*** or ***pentode*** tube in which the wires forming the screen grid are arranged to be in the electron shadow of the wires forming the control grid. Such construction ensures that the screen grid intercepts very few electrons (in spite of its positive potential) and screen-grid current is thus minimised.

alignment In general the adjustment of all the ***preset controls*** of an equipment to give the required performance. In particular, the adjustment of the ***tuning circuits*** of a radio receiver to ensure that they resonate at the required frequencies as the tuning is varied over the received ***waveband(s)***. In a ***superheterodyne receiver*** alignment is necessary to ensure the maintenance of the correct difference in frequency between the oscillator and signal-frequency tuned circuits as the tuning is varied over the waveband(s). Ideally the difference frequency should equal the ***intermediate frequency*** at all tuning settings, but in practice this ideal can be achieved at only two or three tuning points in each waveband.

allowed band In an ***energy-level diagram*** the energy range which electrons may possess. The ***conduction band*** and the ***valence band*** are examples of allowed bands. See ***forbidden band***.

alloy diode A pn ***diode*** manufactured by fusing a pellet of a trivalent or pentavalent element to the face of a wafer of ***semiconductor material***. The wafer is heated until the element dissolves some of the semiconductor. After cooling the dissolved semiconductor crystallises out but sufficient of the element remains to give the required pn structure.

alloy transistor A ***transistor*** manufactured by fusing pellets of trivalent or pentavalent elements to the opposite faces of a thin wafer of semiconductor material. The combination is heated until the elements dissolve some of the ***semiconductor***. After cooling the dissoved semiconductor crystallises out but sufficient of the elements remains to give the pnp or npn structure required, illustrated in *Figure A.2*.

all-pass network A four-terminal ***network*** of which the loss is independent of frequency. A symmetrical lattice network such as that shown in *Figure A.3* is an example of an all-pass network. The ***phase shift*** of the network varies considerably with frequency and such networks are often used as ***phase equalisers*** because they can reduce ***phase distortion*** without affecting frequency response.



Figure A.2 Structure of a pnp alloy-junction bipolar transistor



Figure A.3 A symmetrical lattice network is an example of an all-pass network

alpha cut-off frequency Of a ***bipolar transistor***, the frequency at which the ***current amplification factor*** of the ***common-base circuit*** has fallen to 0.71 $(1/\sqrt{2})$ of its low-frequency value, i.e. is 3 dB down.

alphanumeric code A code using combinations of letters, numerals and other symbols to represent data.

alphanumeric display The display of information by means of letters and numbers. Such displays, usually on the screen of a ***cathode ray tube***, are employed in computers and in information systems such as ***teletext***.

alpha particle A positively-charged particle emitted from an atomic nucleus and consisting of two protons and two neutrons. An alpha particle is identical with a helium nucleus.

alternate display In an ***oscilloscope*** a means of displaying two or more signals by selecting the signals in sequence.

alternating current (AC or a.c.) or **alternating voltage** A current (or voltage) which periodically reverses its direction, varying sinusoidally with time about a mean value of zero. Domestic electricity supplies are usually in the form of alternating current, the frequency being 50 or 60 Hz. Alternating supplies have the advantage that they can be transformed to high voltage for long-distance distribution: high voltage implies low current and therefore low losses.

alternative denial gate Same as ***NAND gate***.

aluminised screen Of a ***cathode ray tube***, a form of construction in which the light-emitting phosphor of the screen is backed by a very thin coating of aluminium. This has the following advantages: (*a*) it protects the screen from bombardment by heavy negative ions so minimising ion burn, (*b*) it stabilises the potential of the screen so avoiding accumulations of charge which could produce shading effects on displays, (*c*) it increases the brightness of the display by reflecting forwards any light transmitted backwards from the phosphor.

ambient noise The noise present in the absence of a signal.

American Standard Code for Information Interchange (ASCII) A standard widely used in computers and data processing equipment to represent alphanumeric characters, punctuation marks and a selection of machine operations (such as line feed) by numbers. Originally ASCII was a 7-bit code, allowing a total of 128 characters and control codes, an eighth bit being used sometimes for ***parity checking***. Many computers now use the eighth bit as part of the code; the extended character set made possible by the additional 128 characters often includes, e.g. the accented letters for most European languages and several currency symbols.

ammeter An instrument for indicating or recording the magnitude of an electric current in ampères (A). For large currents the measurement may be more conveniently expressed in kiloampères (kA) and for small currents in milliampères (mA) or microampères (μA). Current meters must be of low resistance so that, when inserted into a circuit, they have negligible effect on the current being measured.

Ampere's law Same as ***Biot-Savart law***.

ampere-turn The practical unit of ***magnetomotive force***. For a magnetising coil it is equal to the product of the number of turns of wire on the coil and the current (in amperes) flowing in it.

amplification The process by which an electronic device or equipment increases the amplitude of a signal. In linear amplification, the output signal is a magnified but undistorted copy of the input signal but there are circumstances, e.g. in ***class-C operation***, where the output signal, although related to the input, does not have a similar waveform. Some amplifiers are designed to magnify the signal current, others the signal voltage and power amplifiers are required to give substantial current and voltage output. A wide variety of active devices and circuit arrangements are used for amplification in electronic equipment and information on these is given under appropriate headings in this dictionary.

amplification factor (µ) Of an ***electron tube*** the ratio of the change in anode voltage to the change in ***control-grid*** voltage required to maintain the anode current constant. It is usually stated for particular values of electrode voltages.

amplifier A device or assembly of devices through which the current flow is controlled by an input signal so as to give at the output a magnified signal bearing some relationship to the input.

In some applications there is in fact little relationship between input and output, the amplifier operating as a switch controlled by the input signal. In other applications strict proportionality is required between input and output to give linear amplification.

See ***current amplifier***, ***power amplifier***, ***voltage amplifier***.

ampliphase system A modification of the ***Chireix system*** in which the efficiency is improved by ***amplitude modulation*** of the drive signals.

amplitron A microwave amplifying ***electron tube*** used for high-power pulsed operation, e.g. in radar transmitters. The basic form of construction of the tube is shown in *Figure A.4*. The input and output ports are connected to a slow-wave structure surrounding a cylindrical cathode. There is a strong magnetic field parallel to the axis of the cathode.



Figure A.4 Simplified sectional view through an amplitron

amplitude In general the magnitude of a signal. In particular, of a sinusoidally-varying quantity, the peak value, i.e. the maximum departure from the average value. For example, if a voltage is given by $V = V_0 \sin \omega t$, the amplitude is V_0. The value of a sinusoidally-varying quantity at any instant is termed the instantaneous amplitude.

amplitude discriminator In general, a circuit the output of which is a function of the amplitude of two input signals. In particular, the term is used to define a device which gives an output when the two input signals have equal amplitude.

amplitude distortion In a circuit, component or amplifier, distortion arising from variation of gain or attenuation with the amplitude of the input signal. It arises from non-linearity of the input-output characteristic and is produced by hard limiters when the input signal amplitude exceeds the extent of the linear characteristic. See ***amplitude limiter***, ***characteristic curve***.

amplitude gate Device or circuit capable of ***slicing***.

amplitude limiter A four-terminal device which maintains a constant amplitude of output signal for amplitudes of input signal exceeding a certain value. There are two basic types of limiter. In one, which may be termed a hard limiter, a constant-amplitude output is ensured by chopping the peaks of large-amplitude signals, the characteristic having the form shown in *Figure A.5* (a). The resulting waveform mutilation is unimportant, for example, in the hard driven limiter often included before the detector in an FM receiver. This ensures that the signal delivered to the detector is free of amplitude variations (which could cause noise) and contains only frequency variations. A second type of limiter is required in broadcasting and recording to ensure that transmitters or the recording medium are not overloaded by signals of too great an amplitude. Limiters for such applications must maintain linearity of the input-output characteristic and the limiting action is achieved by automatic reduction of the gain of the limiter for large-amplitude input signals so as to maintain the output signal at the limiting level. The characteristics for this type of limiter are shown at *Figure A.5* (b): no distortion occurs except at the instants when the gain is changed. See ***characteristic curve***.



Figure A.5 (a) Non-linear characteristic of a hard limiter and (b) characteristics of a non-distorting limiter for two values of gain

amplitude modulation (AM) A method of ***modulation*** in which the amplitude of the ***carrier wave*** is made to vary in accordance with the instantaneous value of the modulating signal. In radio transmission, considerable use is made of amplitude modulation of a carrier wave and *Figure A.6* illustrates the effect of modulating a radio-frequency wave by a low-frequency sinusoidal signal. Such a modulation system is used, for example, in long-, medium-, and short-wave broadcasting and for the vision



Figure A.6 (a) An unmodulated carrier wave and (b) an amplitude-modulated carrier wave

signal in television broadcasting. In these practical applications the difference between the carrier-wave frequency and the modulating-wave frequency is much greater than suggested in this diagram. It is also possible to amplitude modulate a pulse carrier. See ***double-sideband transmission***, ***pulse amplitude modulation***, ***single-sideband transmission***, ***suppressed-carrier transmission***, ***vestigial-sideband transmission***.

analogue comparator A device used to check the output of an ***analogue-to-digital converter***.

analogue computer A computer that operates on ***analogue signals***, i.e. signals of which the significant property can have any value. These values are represented by corresponding values of voltage or current within the computer circuits which then carry out the required mathematical operations on the signals.

Analogue computers employ ***operational amplifiers*** with ***negative feedback*** for such operations as multiplication, addition, integration and differentiation. Potential dividers are used for division. Function generators are also needed, e.g. to give trigonometrical ratios. The final result from the computer is displayed on a cathode ray tube or on a chart.

Because of the large degree of negative feedback used with operational amplifiers, their outputs are reasonably accurate but there is inevitably some error (e.g. due to drift) and hence there is a limit to the accuracy of the results from the computer. This is normally of little significance because the inputs fed into the computer are normally from measurements which are themselves subject to error. Where precise accuracy is essential a ***digital computer*** is used.

analogue device A device which operates on ***analogue signals***, e.g. an ***analogue computer*** or an audio amplifier.

analogue signal A signal, the significant property of which can have any value. The significant property may be the ***amplitude***, ***phase*** or ***frequency*** of an electrical signal, the angular position of a shaft or the pressure of a fluid. An audio signal is an example of an analogue signal. Signals are often termed analogue where it is necessary to contrast them with digital signals. See ***analogue computer***, ***digital signal***.

analogue switch A switch with characteristics which make it suitable for use with ***analogue signals***. Such signals can have a wide range of voltage and current, and switches for use with them must have values of resistance in the 'on' and 'off' states which are independent of the applied voltage and current. For solid-state analogue switches ***field-effect transistors*** are often used.

analogue-to-digital conversion (ADC) The process of converting an ***analogue signal*** to digital form. See ***digital signal***.

analogue-to-frequency converter A device which accepts an ***analogue signal*** as input and gives an output with a frequency proportional to the input signal.

ancillary store Same as ***backing store***.



Figure A.7 Anderson bridge

Anderson bridge A modified form of ***Maxwell bridge*** used for measuring inductance in terms of capacitance and resistance. As shown in *Figure A.7* the bridge has an additional resistor R_5. The balance conditions (which are independent of frequency) are:

$$L = R_4C\left[R_5\left(1 + \frac{R_2}{R_3}\right) + R_2\right]$$

$$R_2R_4 = R_1R_3$$

and the Anderson bridge has the advantage that the two balance conditions are independent.

AND gate A ***logic gate*** which gives a logic-1 output when, and only when, all the input signals are at logic 1. The graphical symbol for an AND gate is shown in *Figure A.8*. See ***logic level***.



Figure A.8 Graphical symbol for an AND gate

AND-NOT gate Same as ***NAND gate***.

anechoic chamber A room used for testing loudspeakers and microphones in which all sound reflections have been eliminated by lining all the surfaces, including floor and ceiling, with sound-absorbing material.

angle modulation General term for ***modulation*** in which the ***phase angle*** of one signal is varied in accordance with the instantanteous value of another. ***Frequency modulation*** and ***phase modulation*** are two examples of angle modulation.

angle of current flow or **angle of flow** For an amplifier with a sinusoidal input signal the fraction of each cycle, expressed as an angle, during which current flows in the amplifier. For a ***class-A amplifier*** the angle of flow is 360° (2π radians), for a ***class-B amplifier*** it is 180° (π radians) and for a ***class-C amplifier*** it is less than 180°.

angle of lag See ***phase angle***.

angle of lead See ***phase angle***.

angular frequency (ω) The frequency of an alternating quantity expressed in radians per second. Because there are 2π radians in each cycle the angular frequency is equal to $2\pi f$, where f is the frequency in cycles per second (Hertz). Thus

$$\omega = 2\pi f$$

anion Negatively-charged ***ion*** formed in a gas by ***ionisation*** or in an electrolyte by ***dissociation*** and which moves towards the positively-charged electrode (***anode***) under the influence of the potential gradient. See ***cation***.

anisotropic material A material which has different physical properties in different directions. Certain crystals are anisotropic in that their optical properties depend on the direction of incident light relative to the crystal axis. Certain magnetic materials, too, are anisotropic. See ***isotropic***.

annunciator Any device, such as a lamp or a buzzer, used by equipment to attract the attention of its user.

anode Of an ***electron tube*** the positively-charged electrode at which the principal electron stream from the ***cathode*** leaves the tube as an external current. The anode is therefore the output electrode of the tube.

anode AC resistance See ***electrode AC resistance***.

anode-bend detector An AM detector which relies for its action on the curvature of the ***I_a–V_g characteristic*** of an ***electron tube***.

This curvature causes the tube to respond unequally to increase and decrease in the amplitude of the modulated input signal and thus there is a modulation-frequency component in the anode current. This is illustrated in *Figure A.9*. A ***pentode*** is generally used as an anode-bend detector and it is



Figure A.9 Operation of an anode-bend detector

biased near anode-current cut off where characteristic curvature is most marked and detection, therefore, most efficient.

anode characteristic The graphical relationship between the anode voltage and anode current of an ***electron tube*** usually expressed for given values of ***control-grid*** and ***screen-grid voltage***. The shapes of the characteristics for a triode and a pentode are given in *Figure A.10*.



Figure A.10 Typical anode characteristics for a triode and a pentode

anode (collector or drain) dissipation That part of the power supplied to the anode (collector or drain) circuit of an electron tube or transistor which is converted into heat at that electrode. The power thus dissipated is the difference between the DC power input to the electrode and the AC power delivered to the output load.

anode (collector or drain) efficiency The ratio, usually expressed as a percentage, of the AC power delivered to the output load of an active device to the DC power input to the anode (collector or drain) circuit. For a theoretically perfect active device with straight, parallel and equidistant characteristics the maximum efficiency for a sinusoidal signal is 50%. ***Pentodes*** and ***transistors*** can give efficiencies almost equal to this but the efficiency of triodes is much less because of the limited anode voltage swing available before the onset of grid current.

anode (collector or drain) load The impedance of the external circuit between the anode (collector or drain) and the cathode (emitter or source) of an active device. The current variations in the load, the voltage variations across it or the power dissipated in it constitute the output of the active device.

anode modulation Same as ***Heising modulation***.

anode stopper See ***parasitic stopper***.

antenna The system of conductors used at a radio installation to radiate or receive ***electromagnetic waves***. To be effective as a radiator the antenna must have dimensions comparable with the ***wavelength*** and thus medium- and long-wave transmitters must have very large antennas, hundreds of feet in height or length. VHF and UHF transmitting antennas can be very much smaller but must usually be mounted at the top of a hill, a tower or a high building to give adequate service area. Receiving antennas can be small because the low pickup can be compensated by high gain in the receiver circuits. There are many different types of antennas and these are defined in the *Dictionary of Audio, Radio and Video* (Butterworths, 1980).



Figure A.11 Bitmapped text that has been anti-aliased, magnified by 4

anti-aliasing The use of ***pixels*** in intermediate colours to smooth the jagged appearance (***aliasing***) of oblique or curved edges in ***bitmaps*** and ***VDU*** displays (see *Figure A.11*). Anti-aliased text is more readable than text displayed without anti-aliasing. The term is also applied to an analogous process used in converting digitised sound to analogue.

anti-cathode Target of ***electron tube***, particularly an ***X-ray*** tube, on which the electron beam is focused and at which the X-rays are generated.

anti-hunting circuit A circuit incorporated in a feedback system to prevent self-oscillation. The circuit often consists of an *RC* combination designed to absorb energy at frequencies at which the system is likely to ring or oscillate.

antinode Of a ***standing wave***, a point or plane at which a particular variable has a maximum value. Thus antinodes on a transmission line are points at which current or voltage is at a maximum. For a bowed string, antinodes are points at which the amplitude of vibration is at maximum.

antiresonance (US) Same as ***parallel resonance***.

aperiodic circuit A circuit without natural ***resonance***. The term is commonly applied to an ***LC circuit*** which is so heavily damped that the ***impedance*** is substantially constant over a wide band of frequencies centred on the resonance value. It is also applied to an *LC* circuit for which the resonance frequency is so remote from the frequency band in use that there is little change in the impedance over the working frequency range.

aperture (1) Of an optical lens the opening in the diaphragm (entrance pupil) which controls the amount of light passing through the lens. The size of the aperture is usually quoted as a fraction of the focal length of the lens, e.g. an aperture of *f*/8 signifies that the diameter of the aperture is equal to one eighth of the focal length. The aperture control is used, for example, to adjust the amount of light entering a television camera to ensure that the tonal range of the scene to be televised is correctly located on the characteristic(s) of the camera tube(s). (2) In television the term is used to mean the size of the spot where the scanning beam meets the target in a camera tube, flying-spot telecine or picture tube. See ***aperture distortion***. (3) The term has a third meaning when applied to antennas. See the *Dictionary of Audio, Radio and Video* (Butterworths, 1980).

aperture corrector An ***equaliser*** designed specifically to offset ***aperture distortion***.

aperture distortion In television, distortion arising from the finite size of the ***scanning spot***. Such distortion can arise at the transmitting end where the spot is effectively the cross-sectional area of the electron beam where it meets the target in camera tubes or in flying-spot telecines, or at the receiving end where the spot is the cross-sectional area of the scanning beam at the picture tube screen. Because of the finite spot size an instantaneous change in tonal value occurring along a scanning line is reproduced as a pulse with a finite rise or fall time. Thus the spot size determines the degree of detail which can be transmitted and reproduced. It is possible to compensate to some extent for the loss of definition arising from aperture distortion. See ***aperture***, ***aperture corrector***, ***rise time***.

Applegate diagram A diagram used to illustrate the principle of electron bunching in ***velocity-modulated*** tubes. *Figure A.12* is a typical diagram. It is a graph in which the distance travelled by electrons from the buncher gap is plotted vertically and time is plotted horizontally. OA represents the path of a typical electron and the slope of OA measures its velocity. In a velocity-modulated tube the electrons leaving the buncher gap are accelerated by a positive voltage on which is superposed the RF signal it is required to amplify. This imparts a sinusoidal variation to the electron velocities. Suppose OA represents the velocity when the RF voltage is passing through zero and that the RF voltage executes its negative half-cycle immediately afterwards as suggested in *Figure A.12*. Then electrons leaving the gap after those represented by OA have lower velocities as suggested by BC and DE until point P is reached after which the velocities increase. The diagram shows that at a particular distance *d* from the gap the lines meet at a point showing that the electrons gather in bunches at such a distance. By repeating the construction for further cycles of RF the diagram shows that bunches occur at this same spacing from the gap at intervals of 1/*f*, where *f* is the frequency of the RF signal. See ***bunching***, ***klystron***, ***travelling-wave tube***, ***velocity modulation***.



Figure A.12 The bunching of an electron beam velocity-modulated by an RF signal

application A task performed on a computer, such as desktop publishing or databasing, or a suite of software that forms an integrated package to perform that task. For example, several programs may be included together with various kinds of data file used by the programs. Often the various files that make up an application are stored together in one ***directory***.

application(s) software Software that provides an ***application***, in contrast with ***operating systems***, ***utilities*** and ***data***.

Application Specific Integrated Circuit (ASIC) Sometimes known as a gate array, this is a generic ***integrated circuit*** that has been tailored for a specific application. A single ASIC might replace several conventional ***logic*** integrated circuits, allowing a reduction in both circuit board size and power consumption. The term is also sometimes applied to a ***microprocessor*** dedicated to a single purpose.

arc Conduction of an electric current through an ionised gas usually at high current density and accompanied by emission of light. See ***ionisation***, ***spark***.

arcback In a ***gas-filled tube***, conduction between ***anode*** and ***cathode*** resulting in current flow in the reverse direction to normal.

arc conduction See ***arc***.

arc discharge In a ***gas-filled tube***, conduction between ***anode*** and ***cathode*** as a result of electronic emission from the cathode. See ***glow discharge***.

arc drop The voltage between the ***anode*** and ***cathode*** of a ***gas-filled tube*** when it is conducting normally.

architecture The overall design of a computer or data-processing system with special reference to the performance and interaction of its components, its connection to ***peripherals*** and other systems and facilities for future extension.

archive Any ***file*** in a non-volatile storage medium. More specifically, one or more files that have been subjected to a ***compression*** process so that they occupy less space in the storage medium.

arc-over An ***arc*** between two conductors or between a conductor and earth.

arc through In a ***gas-filled tube***, conduction between ***anode*** and ***cathode*** in the normal direction but at a time when the anode should be non-conductive.

arc voltage Same as ***arc drop***.

argument In computing additional data which is entered immediately following a ***command*** to specify the way in which the command is to be executed. For example, in the MS-DOS command

```
COPY A:*.*
```

the character string 'A:*.*' forms the argument, specifying that all files on drive A are to be copied to the currently selected drive and directory.

arithmetic logic unit (ALU) That part of a ***central processing unit*** that performs arithmetical and logical operations.

array (1) A series of similar devices arranged in a meaningful pattern. In computers ***gates*** and ***memory cells*** are usually arranged in a rectangular pattern of columns and rows, known as an array or ***matrix***. Arrays of ***antennas*** are used at short-wave transmitters. (2) In ***computing*** a cluster of similar ***variables*** sharing the same name but distinguished by numeric suffixes enclosed in parentheses.

artificial antenna Same as ***dummy antenna***.

artificial earth A system of conductors mounted a few feet above the ground under an **antenna** and used in place of an earth connection. Such a system is likely to be used where the earth conductivity is poor.

artificial intelligence Computers and computer-controlled machines so organised that they behave, to some extent, like human beings, but without the propensity for mistakes. Perhaps the closest approach has been in so-called ***expert systems.***

artificial language A language based on a set of rules established prior to the use of the language.

artificial line A network of inductors and capacitors designed to simulate the electrical properties of a transmission line over a desired frequency range. See ***capacitance, inductance.***

artificial load A substitute for the normal load of an equipment which has the correct ***impedance*** and can safely dissipate the power generated in it. The artificial load for a transmitter simulates the impedance of the transmission line and antenna but does not radiate.

aspect ratio The ratio of the width to the height of a television picture. This is now standardised at 4:3 to agree with cinema-film practice, but see ***high definition television.***

assembler, assembly language See computer language

astable circuit A circuit with two possible states, both unstable, so that it alternates between the two without need of external triggering signals. Astable circuits can, however, readily be synchronised at the frequency of any regular signal applied to them. An example of an astable circuit is a multivibrator in which both inter-transistor couplings are via capacitors as shown in *Figure A.13*. The two possible states of this circuit are: TR1 on and TR2 off; TR1 off and TR2 on.



Figure A.13 An astable multivibrator circuit

astigmatism A defect in an optical or electron lens which causes focusing in different axial planes to occur at different points along the lens axis. As a result of astigmatism, a point object gives rise to an image in the form of a vertical line at one point on the axis and in the form of a horizontal line at another point as shown in *Figure A.14*. Normally the best compromise is



Figure A.14 Astigmatism in an electron beam

between these two points where the image has the form of a circle, known as the circle of least confusion, which represents equal vertical and horizontal resolution.

asymmetrical circuit A circuit the two sides of which have different electrical properties with respect to a reference potential, usually earth. The term is often applied to circuits in which one side is earthed. See ***symmetrical operation***.

asymmetrical deflection Electrostatic deflection in a ***cathode ray tube*** where the deflecting potentials applied to the plates are not symmetrical about a reference potential (usually the final-anode potential). In particular the term is applied to electrostatic deflection where one plate of a pair is effectively earthed and the deflecting potential is applied to the other.

asynchronous logic In a ***computer*** or ***data-processing equipment***, ***logic*** in which operation is started by a signal generated at the completion of the previous operation. The term is used to distinguish this form of operation from that in which operations are controlled by an internal ***clock***. See ***synchronous logic***.

asynchronous transmission A method of ***data transmission*** in which characters are sent at irregular intervals, each being preceded by a start bit and followed by a stop bit. It is the most widely used method of data transmission between microcomputers.

atomic number Of an element, the total number of unit positive charges carried by the nucleus of an atom. For a neutral atom this is the number of protons in the nucleus and also the number of orbiting electrons. See ***atomic structure***.

atomic structure The atom is regarded as a dense nucleus containing ***protons*** and ***neutrons*** and with a net positive charge, around which revolve a number of electrons neutralising the positive charge of the nucleus. The total number of protons is equal to the atomic number of the element. The innermost electron orbit can contain at most two electrons, the second 8 and the third 18: the number needed for completion is given by $2n^2$, where n is the number of the orbit. The number of electrons in the outermost orbit determines the properties of the element. For example, it is difficult to remove an electron from or to insert an electron into an outermost orbit which has a complete complement of electrons. Thus atoms with completed outermost orbits are chemically inert: such atoms are those of the gases helium, argon, krypton etc. If the outermost shell has only one or two electrons these can be removed with little effort, making elements with such atoms good electrical conductors. Typical of such elements are copper and silver. If the outermost orbit has four electrons, ***covalent bonds*** can be formed between neighbouring atoms in a crystal lattice and the element has ***semiconductor properties***. The obvious examples are ***germanium*** and ***silicon***.

attack time The time that elapses between the instant that a signal at the input of a component or circuit exceeds the ***threshold*** needed to activate the component or circuit and the instant that the component or circuit begins to respond to the input.

attenuation coefficient (or **constant**) See ***propagation coefficient***.

attenuation/frequency distortion or **attenuation distortion** In a system, equipment or component, variation of the gain or attenuation with the frequency of the input signal. Attenuation distortion is illustrated by the ***frequency response curve*** and the most commonly-encountered forms are shown in *Figure A.15*. An important feature of attenuation distortion is that it can be corrected: for example, the effects of an equipment suffering from 'top cut' can be offset by use of an equaliser with a complementary 'top lift' response.



Figure A.15 Common forms of attenuation distortion

attenuator A ***network*** used to reduce the ***amplitude*** of a signal without distorting it. The reduction factor (attenuation) may be fixed or variable. A fixed attenuator is often called a pad. Attenuators may be inserted in lines or between equipments and are then designed not to introduce any impedance change, i.e. they are designed to have a particular value of ***iterative impedance***. Alternatively attenuators can be designed on an ***image-impedance*** basis to match unequal impedances. Networks often used in attenuators are ***T-networks*** and ***π-networks*** and their balanced equivalents ***H-networks*** and ***O-networks***. *Figure A.16* gives an example of an O network with 10-dB attenuation and with an iterative impedance of 300 Ω.



Figure A.16 An O-network 10-dB attenuator with an iterative impedance of 300 Ω

audio frequency (AF) Any frequency of sound wave which is normally audible to the human ear. The lower limit is usually quoted as 15 Hz but it is difficult at such low frequencies to differentiate between the sensations of hearing and feeling. The upper limit is often given as 20 kHz but this limit is dependent on age and falls below 10 kHz for very old people. In electronics, audio signals which are intended for reproduction by loudspeakers are regarded as high quality if the frequency range from 30 Hz to 15 kHz is covered with minimal distortion.

auto-coincidence gate Same as ***exclusive-OR gate***.

autodyne or auto-heterodyne A system of ***heterodyne*** reception in which the same ***active*** and ***passive*** components are used for oscillation and mixing (as in a self-oscillating mixer). See ***mixer***, ***self-oscillating mixer***.

automatic brightness control In a television receiver, a circuit which automatically adjusts the brightness of the display in accordance with the level of ambient light near the receiver. A ***photocell*** may be used to measure the ambient light, its output, after amplification, being used to control the grid bias of the picture tube.

automatic cathode bias Use of a ***resistor*** in the ***cathode*** circuit of an ***electron tube*** to provide ***grid*** bias. A typical circuit is given in *Figure A.17*. The cathode current in R_k sets up a voltage across this resistor which biases the cathode positively with respect to the negative HT supply. The control grid is connected to HT negative by the grid resistor R_g. Thus the grid is biased negatively with respect to the cathode as required.



Figure A.17 Automatic cathode bias

The circuit can be used only when the mean cathode current is constant as in ***class-A operation*** and the value of cathode resistance required is, from Ohm's law, given by V_g/I_k where V_g is the bias voltage and I_k the mean cathode current. Thus if the grid bias is –8 V and the mean cathode current 40 mA, the cathode resistance required is 200 Ω.

For a ***triode*** tube the mean cathode current is equal to the mean anode current but for more complex tubes such as ***pentodes***, the cathode current includes also the screen-grid current.

In addition to providing grid bias a resistor in the cathode circuit also gives ***negative feedback*** which reduces the gain of the tube. If this reduction is undesirable the feedback can be minimised by by-passing the resistor by a ***capacitor*** as shown in *Figure A.17*. The capacitance should be such that the ***reactance*** at the lowest signal frequency is small compared with R_k.

automatic check In ***computers*** and ***data-processing equipment*** the use of ***hardware*** or ***software*** to verify the accuracy of processes carried out by the equipment.

automatic chrominance control (ACC) In a colour television receiver, an (AGC) circuit incorporated in the ***chrominance amplifier*** to ensure that the relative amplitudes of the ***chrominance*** and ***luminance*** signals are maintained. This is necessary to ensure correct colour rendering in spite of variations in signal level at the receiver input.

automatic contrast control See ***automatic gain control.***

automatic frequency control (AFC) A circuit in a receiver which ensures that errors in the frequency of the oscillator or the tuning of a circuit are kept within certain limits. Before 1939 some amplitude modulation receivers had such a control (known as automatic tuning) and a ***discriminator*** was incorporated in the intermediate frequency amplifier to derive an error voltage which was applied to a reactance tube connected across the oscillator tuned circuit. In frequency modulated receivers the detector can be designed to provide the required error signal in addition to the audio frequency output. AFC is desirable in any receiver with preset (e.g. push-button) tuning to compensate for the inevitable slight drift in oscillator frequency.

automatic gain control (AGC) The maintenance of a substantially-constant input signal amplitude at the detector of a radio or television receiver (in spite of variations in amplitude of the input signal to the receiver) by automatic adjustment of the gain of the intermediate frequency and/or radio frequency stages. This adjustment is carried out by a control signal derived from the detector or from a post-detector stage. The purpose of AGC is to minimise the effects of signal fading on audio frequency output or picture contrast and to ensure that all received signals, no matter what their amplitude, give substantially the same output. When applied to radio receivers, AGC was originally known as automatic volume control and when applied to television receivers is sometimes termed automatic contrast control or automatic picture control. See ***forward automatic gain control, reverse automatic gain control, variable-mu tube.***

automatic grid bias Use of a resistor in the ***grid*** (or ***cathode***) circuit of an ***electron tube*** to produce grid-bias voltage as a result of grid (or cathode) current flow. Grid-current bias is commonly used in electron-tube oscillators and cathode-current bias in electron-tube amplifiers. See ***cathode bias.***

automatic picture control Same as ***automatic gain control.***

automatic tuning Same as ***automatic frequency control.***

automatic volume control (AVC) Same as ***automatic gain control.***

automation (1) The theory or technique of making a process automatic. (2) The control of processes by automatic means.

auto-transformer See ***transformer.***

avalanche breakdown In a reverse-biased ***pn junction***, a rapid increase in current which occurs at a particular reverse voltage as a result of cumulative multiplication of charge carriers. The effect is caused by the strong electric field across the junction which gives the few charge carriers so much energy that they liberate other ***hole-electron*** pairs by impact ionisation. The new carriers so created liberate further hole-electron pairs and thus the process becomes regenerative, leading to a very rapid increase in reverse current. See ***charge carriers***, ***ionisation***.

avalanche photo-diode (APD) A ***photo-diode*** in which the electrical output is considerably increased by ***avalanche breakdown***. Such diodes are operated with a reverse bias close to the breakdown voltage so that liberated photo-electrons have sufficient energy to create ***hole-electron*** pairs by impact ionisation.

average detector A detector of which the output approximates to the mean value of the envelope of the input signal. See ***detection***.

azimuth The alignment of a directional antenna or of a recording or playback head in a tape recorder.

B

background noise The sound, typically a faint hiss, heard from an audio system or radio receiver in the absence of a signal.

background processing or task In a ***multitasking*** computer system, the execution of a low-priority task in the intervals when the processor can be spared from current high-priority tasks. Tasks such as printing and disk ***formatting*** are often executed as background tasks.

backing store Same as ***bulk storage***.

backplane A flat panel usually incorporating an earthed plate which is located at the rear of a multiboard equipment and supports the wiring and the receptacles which locate with the ***edge connectors*** on the ***printed-circuit*** or ***printed-wiring boards***.

back porch In a television signal the period of ***blanking level*** immediately following the ***line sync signal***. In colour television this period is largely occupied by the ***colour burst***. See *Figure L.8*.

back-up Of equipment, to duplicate vital hardware so that, in the event of a failure, the normal service can be resumed with minimal delay. Of data, to make a copy of one or more files or a whole disk so that, if the original should be destroyed or corrupted, valuable data or applications remain available on the back-up copy. Hard disk drives are commonly backed up using ***tape streamers*** and sometimes using ***optical disks***.

backward diode A ***Zener diode*** in which the ***doping*** is arranged during manufacture to give a ***breakdown voltage*** of zero. By contrast with normal diodes, such a diode has a reverse resistance lower than the forward resistance as shown in *Figure B.1*. Backward diodes of low capacitance are used as microwave detectors. The graphical symbol for a backward diode is given in *Figure B.2*.



Figure B.1 Characteristics of a backward diode (solid) and a normal diode (dashed)



Figure B.2 Graphical symbol for a backward diode



Figure B.3 Graphical symbol for a backward-wave oscillator: this example is an O-carcinotron

backward-wave oscillator or **carcinotron** A ***travelling-wave tube*** in which the wave propagation is in the opposite direction to the movement of the electron stream. The travelling-wave tube has a ***slow-wave structure*** with a matching termination at the collector end to absorb energy at the output. A backward wave set up in the tube gains energy from the electron beam and the tube can sustain oscillation when the electron-beam velocity equals the wave velocity along the tube. The frequency of oscillation can be adjusted by varying the electron-gun anode voltage and this gives a wider range of control than is possible with the ***klystron*** or a conventional travelling-wave tube. Power outputs of 900 mW are obtainable over a frequency range of 2500 to 5000 MHz. The graphical symbol for a backward-wave oscillator is given in *Figure B.3*: this represents in fact an O-type carcinotron.

baffle (1) In a gas-filled ***electron tube***, a structure with no external connection and placed in the arc path. A baffle may help to control the distribution of current in the path of the arc or may help to de-ionise the gas after the conduction period. (2) In ***acoustics***, a rigid structure such as a sheet of sound-insulating material used to improve the distribution of sound waves. In particular a structure in the centre of which a loudspeaker is mounted. The baffle increases the acoustic path length between the front and rear of the loudspeaker. By bringing the waves radiated from the rear of the loudspeaker into phase with those radiated from the front, the sound at low frequencies can be reinforced, effectively extending the low-frequency response of the loudspeaker.

balance In general the state in which the correct relationship between two quantities has been achieved. For example the signal levels in the two channels of a ***stereophonic system*** are said to be balanced when the correct spacial distribution of sound is achieved.

balanced modulator A circuit which accepts a carrier signal and a modulating signal as inputs and gives a ***suppressed-carrier amplitude-modulated output***. *Figure B.4* gives the circuit diagram of one form of balanced modulator which consists of two matched ***active devices***, the inputs of which are driven in push pull by the modulating signal but in phase by the carrier signal. The carrier input may be regarded as a signal which switches the active devices between conduction and non-conduction at carrier frequency. Thus the output of the circuit consists of a succession of half-cycles of carrier, the envelope of which has the waveform of the modulating signal. This is illustrated in *Figure B.5*: it is the waveform of a



Figure B.4 Simplified circuit for a balanced modulator using two transistors in push-pull



Figure B.5 Waveform of a suppressed-carrier amplitude-modulated signal for sinusoidal modulation

suppressed-carrier amplitude-modulated signal. See ***amplitude modulation suppressed-carrier modulation.***

balanced operation Same as ***push-pull operation.***

balanced-wire circuit A circuit comprising two conductors, electrically alike, and symmetrically arranged with respect to a common reference point, usually ground.

ballast resistor A resistor with a pronounced positive temperature coefficient so designed that when connected in series with a given load it ensures constancy in current for limited variations in supply voltage. Such resistors were used in AC/DC radio receivers where they were connected in series with the electron-tube heaters to ensure constancy in heater current. The graphical symbol for a ballast resistor is given in *Figure B.6.*



Figure B.6 Graphical symbol for a ballast resistor

ballast tube A ballast resistor enclosed in a gas-filled envelope. See ***ballast resistor.***

banana tube A picture tube in which the electron beam scans a single phosphor strip in the horizontal direction, vertical scanning being achieved mechanically by a system of cylindrical lenses mounted inside a drum which rotates around the tube. In the colour version of the tube the single phosphor strip is replaced by three parallel strips of red, green and blue phosphors and the beam is deflected vertically to scan the colour strips as necessary. The tube is not at present in commercial use.

band (1) A range of frequencies between defined limits, e.g. the audio-frequency band which may be taken as the range between 30 Hz and 20 kHz. (2) In an ***energy-level diagram*** a closely-spaced range of electron energy levels, e.g. the ***conduction band***. (3) In ***computers*** or ***data-processing equipment*** a group of recording tracks on a ***magnetic storage*** device such as a drum or disk.

band gap Same as ***energy gap***.



Figure B.7 General form of the response curve for a bandpass filter

bandpass filter A filter designed to pass signals with frequencies between two specified cut-off frequencies. The ***frequency response*** has the general form illustrated in *Figure B.7* and such a response may be obtained at radio frequencies by coupling two identical ***tuned circuits***, both resonant at the same (mid-band) frequency. The block symbol for a bandpass filter is given in *Figure B.8*.



Figure B.8 Block symbol for a bandpass filter

bandstop filter A filter designed to pass signals with all frequencies except those between two specified ***cut-off frequencies***. The frequency response has the general form shown in *Figure B.9* and the block symbol for a bandstop filter is given in *Figure B.10*.

bandwidth (1) The range of frequencies over which the ***gain*** of a ***network***, amplifier or receiver falls within prescribed limits. For example the bandwidth of an amplifier is often taken as the range between the frequencies at which the response is 3 dB down compared with the response at midband. (2) The range of frequencies between the outermost side frequencies of a modulated wave. Thus if the modulating frequencies extend to 10 kHz the bandwidth of an amplitude-modulated signal is 20 kHz.



Figure B.9 General form of the response curve for a bandstop filter



Figure B.10 Block symbol for a bandstop filter

bar code An array of vertical parallel bars of varying thickness printed on packaging, publications and other products. At the checkout in a supermarket, the bar code is read by an ***optoelectronic*** reading device connected to the ***electronic point of sale*** system in order to establish the identity of the item and, from this, its price. The ***host*** computer can in this way make a continuous audit of how each type of merchandise is selling; this is valuable management information. See ***electronic point of sale***.

Barkhausen-Kurz oscillator An early form of triode oscillator in which the grid is biased positively and the anode negatively, oscillation (usually at hundreds of MHz) depending on the ***transit time*** of electrons between cathode and anode. Unwanted oscillations of this type can occur in electron-tube circuits under particular biasing conditions.

barrel distortion Distortion of a television picture in which the sides of a reproduced square bulge outwards. The distortion, illustrated in *Figure B.11*, is caused by ***non-linearity*** of the field produced by the scanning coils. It is the opposite of ***pin-cushion distortion***.



Figure B.11 Reproduction of a square by a picture tube suffering from barrel distortion

barretter Same as ***ballast tube***.

barrier capacitance See ***depletion layer***.

barrier diode Same as ***Schottky diode***.

barrier grid (US) Same as ***stabilising mesh***.

barrier layer Same as ***depletion layer***.

base (region) In a ***bipolar transistor***, that region between the emitter region and the collector region into which minority carriers are injected from the emitter region. It is the controlling electrode of a ***bipolar transistor*** and can be compared with the control grid of an electron tube and the gate of a ***field-effect transistor***. See ***collector***, ***emitter***, ***minority carriers***, ***semiconductor***.

base bias The steady current applied to the base of a ***bipolar transistor*** to ensure that signal excursions operate over the desired region of the transistor characteristic. See ***dc stabilisation***, ***operating point***.

base resistance See ***electrode dc resistance*** and ***electrode ac resistance***.

base station A transmitting and receiving station used for radio communication with mobile stations within a restricted area. For example, in ***cellular*** telephone systems each cell contains a base station. A domestic cordless telephone has radio links to a dedicated base station which is connected to the telephone system.

BASIC See ***computer language***.

bass The lower frequencies of the audible range extending from say 200 Hz to 20 Hz.

bass boost or **lift** ***Accentuation*** in which the lower frequencies of the audio range are emphasised.

bass cut ***Attenuation distortion*** in which the lower frequencies of the audio range are attenuated.

batch file A ***text*** file containing a list of commands or files for processing by a computer.

batch processing A form of data processing in which the computer is given a list of tasks and left to complete them without operator intervention. It is most often used for time consuming operations that involve, for instance, searches through large databases. Batch processing is sometimes undertaken at night or at weekends when the computer is not needed for more urgent, interactive operations.

battery A series and/or parallel arrangement of ***primary cells*** or ***secondary cells*** for supplying power. In common speech a single cell is often called a battery. See ***accumulator***, ***storage battery***, ***voltaic cell***.

battery eliminator A unit providing power from the mains for a radio receiver originally designed for operation from batteries.

Baud In ***data transmission*** a unit of signalling speed equal to the number of code elements transmitted per second. It is commonly regarded as equivalent to the ***bit rate***. The term is derived from the Baudot code used for over a century for the transmission of telegraph signals.

Baxandall circuit A ***negative-feedback*** circuit giving adjustable degrees of ***bass lift***, ***bass cut***, ***top lift*** and ***top cut*** and used in high quality audio amplifiers. A number of variants of the circuit are possible and one example is shown in *Figure B.12*. See ***attenuation distortion***.

B battery (US) A battery used to supply the high tension for the ***anodes*** and ***screen grids*** of electron tubes.

beacon (1) A term sometimes used for an indicator, such as the stereo-subcarrier-detected indicator in a stereo radio receiver. The beacon is often a ***light emitting diode***. (2) A fixed radio transmitter providing mobile stations with guidance signals. See ***radio beacon***.

bead store A magnetic ***store*** in which the storage elements are formed by fusing ***ferrite*** powder directly on to the conductors forming the ***matrix***. See ***magnetic storage***, ***storage element***.



Figure B.12 An example of a Baxandall tone-control circuit

bead thermometer A thermometer using a ***thermistor*** as the temperature-sensing element.

beam current Of a ***cathode ray tube*** the current of the electron stream from the ***cathode*** which strikes the ***screen*** and is primarily responsible for the brightness of the display.

beam deflection tube A colour picture tube with a single ***electron gun*** and in which the ***screen*** is composed of horizontal stripes of red, green and blue phosphors arranged in sequence. A grid of horizontal wires is mounted close to the screen and, by applying suitable potentials to these wires the ***electron beam*** can be deflected so as to strike the phosphor stripe giving the required colour.

beam-indexing tube A colour picture tube with a single ***electron gun*** and in which the ***screen*** is composed of vertical stripes of red, green and blue phosphors arranged in sequence. A beam-indexing system operated, for example, by signals from vertical stripes interleaved with the red, green and blue groups ensures that at any instant the electron gun is always switched to the colour signal corresponding to the phosphor stripe on which the beam is incident.

beam parametric amplifier A ***parametric amplifier*** in which the variable reactance is provided by a modulated electron beam.

beam splitting A technique used in a ***double-beam oscilloscope*** to divide the beam from the ***electron gun*** into two parts which can be deflected independently to permit two different ***traces*** to be simultaneously displayed on the screen.

beam-switching tube Same as ***beam deflection tube.***

beam tetrode A ***tetrode*** incorporating electrodes to direct the electron stream from the ***cathode*** to the ***anode***. As shown in *Figure B.13* the beam-forming electrodes usually consist of two plates connected to the cathode. Beam tetrodes usually have ***aligned grids*** and the resulting high-density electron stream prevents ***secondary emission*** from the anode from reaching the screen grid so preventing the ***tetrode kink*** which would impair efficiency.

beanstalk A circuit consisting of a number of ***transistors*** connected in series across a power supply, their inter-connections being brought out as tapping points. Such a circuit is used at the input to the tetrode modulator of a



Figure B.13 Construction of a beam tetrode

sound radio transmitter, adjustable resistors connected across suitable tapping points being used to set the audio input level, the base bias and the limiter level.

beat frequency The frequency of the periodic pulsations produced by ***beating***. The term is also extended to other examples where two sinusoidal inputs are combined to produce an output at the difference frequency, e.g. in ***frequency changers*** and ***mixers***.

beat frequency oscillator (BFO) In general a variable-frequency oscillator used to interact with a fixed-frequency oscillator to produce the beat or difference frequency.

More specifically, an oscillator used in radio receivers to render audible transmissions of ***continuous-wave telegraphy***. In a superheterodyne receiver the BFO beats with the signal in the ***IF amplifier*** to produce an audible note.

See ***communications receiver, continuous wave***.

beating The combining of two sinusoidal signals to give periodic pulsations. Simple addition of the two signals, if they are of equal amplitude, gives the result shown in *Figure B.5*. The envelope consists of two overlapping sine waves with a frequency equal to half the difference between the frequencies of the original signals as shown by the identity

$$\sin \omega_1 t + \sin \omega_2 t = 2 \sin \left[\left(\frac{\omega_1 - \omega_2}{2}\right) t\right] \cos \left[\left(\frac{\omega_1 + \omega_2}{2}\right) t\right]$$

There are, however, two maxima, i.e. two beats per envelope cycle. Thus the number of beats per second is equal to the difference frequency.

If the two sinusoidal signals are combined in a non-linear device, such as an AM detector, then a multiplicity of output signals with new frequencies is generated: these are ***combination frequencies*** and the first two in the series are the sum and difference frequencies. The difference or beat frequency is the output from an additive ***mixer*** which is selected for amplification in the IF amplifier of a super-heterodyne receiver. It is significant that non-linearity is essential to generate the beat frequency in an additive mixer. This is clear from *Figure B.5*: if the wave shown here is rectified the result has a pronounced component at the difference frequency.

If the original two sinusoidal signals are combined in a device which multiplies them, e.g. a multiplicative mixer, then only two new frequencies are generated. These are the difference term—the beat frequency—and the sum frequency. This is shown by the identity

$$\sin \omega_1 t \sin \omega_2 t = \tfrac{1}{2}[\sin(\omega_1 - \omega_2)t + \sin(\omega_1 + \omega_2)t]$$

In this type of ***mixer*** the beat frequency is generated without need for non-linearity.

beep Onomatopoeic name for the hooting sound issued by computers and other data processing equipment encountering ***error*** conditions or in other circumstances where the operator's attention is required.

bel The basic unit of a logarithmic scale used for expressing ratios of powers. The bel was invented by American telephone engineers in the 1920s and was named after Sir Alexander Graham Bell, the inventor of the telephone. Two powers P_1 and P_2 are related by N bels when

$$\log_{10}(P_1/P_2) = N.$$

The number of bels is thus the common logarithm of the power ratio. It follows that an amplifier with a power gain of 100000 can be said to have a gain of 5 bels. The unit is inconveniently large and its tenth part, the decibel, is always used in practice. See ***decibel***.

benchmark An industry standard test of the performance of an equipment, used for comparison purposes.

beta particles The stream of electrons emitted from certain radioactive substances.

betatron An ***electron tube*** capable of producing an electron beam of very high energy suitable for ***X-ray*** generation. A magnetic field is used to confine the beam to a circular path and its energy is continuously increased by a rapidly-changing electric field.

bias In electronics a steady current or voltage which determines the position of the ***operating point*** on the input-output characteristic of an ***active device***. In magnetic recording a magnetic field superimposed on that due to the signal to be recorded in order to improve the linearity of the relationship between signal and remanent flux density. The bias field in an audio recorder is usually produced by an ultrasonic oscillator.

bias current Of a ***differential amplifier*** the current flowing into each of the two input terminals.

bidirectional thyristor A ***thyristor*** which can be switched to the on-state whether the anode is positive or negative with respect to the cathode. Diode



Figure B.14 Graphical symbol for bidirectional thyristors (a) diode and (b) triode (triac)

and triode types exist and the graphical symbols for both are given in *Figure B.14*. The triode type is triggered into conduction by a signal applied to the gate and this type of thyristor is alternatively known as a triac.

bidirectional transistor A ***bipolar transistor*** in which the connections to emitter and collector terminals can be interchanged without significant change in characteristics. Normally the emitter and collector regions are of different sizes and conductivities. Thus the terminals must be used as the manufacturer prescribes if the intended properties of the transistor are to be realised. If, however, the construction of the transistor is symmetrical, the emitter and collector terminals may be interchanged without effect on characteristics.

bifilar winding A method of winding in which two conductors are wound in close proximity on a former. This is done, for example, to give close coupling between the windings in a ***ratio detector*** transformer. It is also used in the construction of non-inductive resistors by arranging that the current flows in opposite directions in the two conductors so that any magnetic field set up by the current in one conductor is cancelled by that in the other. This is illustrated in *Figure B.15*. A similar technique is used in the construction of the heater of some electron tubes to minimise mains-frequency hum.



Figure B.15 Bifilar winding

bilateral impedance A mutual impedance through which power can be transmitted equally in both directions. Components such as ***resistors***, ***inductors***, ***capacitors*** and combinations of these which are used to couple circuits are examples of bilateral impedances. Any change in one circuit is reflected back to affect the current in the other circuit. See ***mutual impedance***.

bimetal element or **bimetal strip** An assembly of two strips of metal with different coefficients of thermal expansion welded together so that the assembly bends into an arc when heated. Bimetal strips are used in ***thermostats*** and ***thermal relays*** to operate electrical contacts.

bimorph An assembly of two strips of piezo-electric material cemented together. Depending on the way in which the strips are cut from the original crystal the bimorph may bend when a voltage is applied between foil electrodes in contact with the outside surfaces, or it may twist. Bender and twister bimorphs are used in ***piezo-electric loudspeakers*** and disk cutter heads. If a bimorph is subjected to mechanical stress it develops EMFs between electrodes on the outside surfaces. Thus bimorphs are also used in piezo-electric microphones and disk-reproducing heads. See ***piezo-electric crystal, piezo-electric effect, piezo-electric pickup.***

binary cell Same as ***memory cell.***

binary-coded decimal (BCD) A method of translating decimal numbers into the ***binary scale*** by coding the individual figures of the number separately. For example the number 354 in binary-coded decimal is 11 101 100 whereas, if expressed in full binary form, it is 101100010. The advantage of the binary-coded decimal system is that large decimal numbers can be recognised immediately from their BCD coding once the binary equivalent of the decimal numbers from 0 to 9 are known.

binary coding A method of coding information in which the coded information consists of characters which can have only one of two possible values, e.g. in numerical coding the two possible values may be 0 and 1, the digits of the ***binary scale.***

binary counter A circuit which gives one output pulse for every two input pulses. If the input pulses are irregular the circuit is usually regarded as a counter but if they are regular the circuit is generally regarded as a ***frequency divider.*** A ***bistable circuit*** such as a ***multivibrator*** is probably the best-known example of binary counter or divider.

binary digit One of the two digits of the ***binary scale***, i.e. 0 or 1.

binary divider See ***binary counter.***

binary scale A counting scale which has only two digits, 0 and 1. The digits in a binary number thus correspond to powers of 2. For example the binary number 110110 corresponds to

$$\begin{aligned} & 1\times 2^5 + 1\times 2^4 + 0\times 2^3 + 1\times 2^2 + 1\times 2^1 + 0\times 2^0 \\ = {} & 32 + 16 + 0 + 4 + 2 + 0 \\ = {} & 54 \end{aligned}$$

binary word A sequence of consecutive ***binary digits*** which is treated as a unit of information in the storage, transmission and processing in a ***computer*** or ***data-processing equipment.***

binaural (1) In general, hearing by use of both ears. The significant feature of binaural listening is that the listener can locate the position of a source of sound. This can be done from the difference in the time of arrival of the sound at both ears or by detecting the difference in phase. (2) In particular a form of stereo sound transmission in which the two channels originate from microphones located at the positions of the ears in a dummy head. To obtain the full benefit of binaural transmission the two signals must be heard via ***headphones*** so that the left ear hears only the signal from the microphone in the dummy left ear and vice versa. The two channels must be kept separate right up to the listener's ears.

Biot-Savart law The law relating the magnetic field strength due to an electric current with the strength of the current. It can be stated thus: the summation of the magnetic force around a closed path is proportional to the total current flowing across the surface bounded by the path.

bipolar transistor A ***transistor*** which depends for its action on two types of ***charge carrier.*** It consists essentially of three layers of semiconductor material, the centre layer having conductivity complementary to that of the two outer layers. The central layer is very thin and is known as the base, the other two layers being the emitter and collector. The structure is illustrated in *Figure B.16* which also shows that there can be two basic types of bipolar transistor, namely pnp and npn.



Figure B.16 Structure of (a) pnp and (b) npn bipolar transistors

Essentially the device behaves as two pn ***junctions*** in series and in normal usage the layers are so biased that the base-emitter junction is forward biased (and therefore of low resistance) and the collector-base junction is reverse-biased (and therefore of high resistance). Typical working voltages are shown in *Figure B.16.* In the npn transistor (b) the current crossing the base-emitter junction is carried by electrons from the emitter and holes from the base as explained under ***junction,*** but the impurity concentration in the emitter region is considerably greater than that of the base. Thus the electrons greatly outnumber the holes. On entering the base region a few electrons leave it via the external base connection to give a small external base current. Most of the electrons cross the very thin base region and are swept into the collector region, attracted by its positive bias, to give a considerable external collector current—despite the fact that the collector-base junction is reverse-biased. The collector (output) current can be as much as 100 times the base (input) current. This amplification is the essence of transistor action.

In the pnp transistor of *Figure B.16* (a) the holes crossing the base-emitter junction outnumber the electrons but again the external collector current is many times the external base current.

In both types of transistor electrons and holes play a part in the amplifying action, this justifying the description bipolar. Because of their low input resistance and high output resistance bipolar transistors are best regarded as current amplifiers.



Figure B.17 Graphical symbols for (a) pnp and (b) npn bipolar transistors

The graphical symbols for pnp and npn bipolar transistors are given in *Figure B.17*.

bistable also known as **bistable circuit, flip flop** (US) or **toggle** (US) A circuit with only two possible states, both stable. When the circuit is placed in one of the states, it remains in it indefinitely unless compelled to leave it by the application of an external signal. When thus triggered the circuit enters the other possible state and here too it remains unless a further triggering signal is received and this returns the circuit to its original state. Two external signals are thus necessary to restore the circuit to its original state and this illustrates one of the applications of bistable circuits—as ***pulse counters*** or frequency dividers.

Because of their ability to remain in a given state, bistable circuits are extensively employed in digital switching applications, e.g. as the basic elements of ***stores*** and ***registers*** in computers. Basically a bistable circuit may consist of a ***multivibrator*** with two direct inter-transistor couplings but there are many possible types. See ***D bistable***, ***JK bistable***, ***RS bistable***, ***T bistable***.

bit Abbreviated form of ***binary digit***.

bitmap A two-dimensional array of ***pixels*** forming an image or part of an image. See ***graphics***, ***painting software***.

bi-threshold device Same as ***Schmitt trigger***.

bit rate The speed at which binary digits are transmitted. It is usually expressed in bits (kilobits or megabits) per second.

black body Same as ***full radiator***.

black compression or **black crushing** In television, reduction of the gain at signal levels corresponding to black compared with the gain at white and mid-grey levels. Black compression reduces the visibility of detail in the low-light regions of reproduced pictures.

black level In television the minimum permissible level of the ***picture signal*** (*Figure B.18* (a)). In a properly-adjusted system the black-level voltage at the input to a picture tube gives cut-off of the electron beam as indicated in *Figure B.18* (b).

blanking (1) In general the suppression of the signals in a channel or device for a desired period. (2) In television the suppression of the electron beam in a picture tube during line and field flyback periods. (3) In television transmission the suppression of the ***picture signal*** component of a ***video signal***, leaving the ***blanking level*** which may or may not contain sync signals.


white level
picture signal
black level
blanking level
sync. signal
sync. level
time
(a)

Figure B.18 (a) Waveform of a black-and-white video signal


characteristic of picture tube
black level
brightness
grid voltage
picture signal
time

Figure B.18 (b) Application of a video signal to the characteristic of a picture tube

blanking level In a ***video signal*** the boundary level separating the ***picture signal*** from the ***sync signals***, see *Figure B.18* (a).

bleeder or **bleeder resistor** A fixed resistor connected permanently across the output of a power source. It may be included to limit the rise in voltage when the load is disconnected. It may be used to discharge ***capacitors*** when the power supply is switched off or it may be included to improve the regulation of the supply.

blocking In electron tubes the suppression of anode current by applying a large negative voltage to the grid. This may occur either fortuitously, for example, when the grid resistor is open-circuited or it may occur deliberately, e.g. when the tube is used in a ***gate circuit***.

blocking capacitor A ***capacitor*** used between stages in an equipment to prevent the transfer of direct voltages but to provide a low-reactance path to alternating signals. The capacitor of an *RC*-coupled amplifier (see *Figure C.26* (a)) is an example of a blocking capacitor.

blocking oscillator An oscillator in which ***positive feedback*** produces so large an oscillation amplitude that the active device is cut off, usually in the first half-cycle, the circuit then relaxing until conditions again permit oscillation. The circuit thus produces regular bursts of current and is used as a pulse generator in, for example, the sawtooth generators in TV receivers.

The circuit diagram of a transistor blocking oscillator is given in *Figure B.19*. When the tuned circuit oscillates C_1 is charged by base current to a high negative voltage which cuts the transistor off. When C_1 has discharged sufficiently through R_1 oscillation commences again and C_1 is again charged. The transistor thus takes regular bursts of collector current and generates negative-going pulses across R_2 at a frequency determined by the ***time constant*** R_1C_1.



Figure B.19 A transistor blocking oscillator

Bode diagram A diagram in which the gain (and/or phase angle) of a device is plotted against frequency. Such diagrams can be used to determine the stability of the device and to show what degree of negative feedback can safely be applied.

Bode equaliser An ***equaliser*** used to correct the ***frequency response*** of TV sound circuits in which the amount of equalisation can be adjusted, without change in the shape of the equaliser characteristic, by operation of a single control.

bolometer In general a device for measuring electric current or power. The detecting device is a small resistive element, the resistance of which is strongly dependent on temperature. This is included in a bridge circuit which measures the power by the change in resistance resulting from the rise in temperature caused by the power absorbed. The temperature-sensitive element is usually a ***thermistor*** or a filament in an evacuated bulb.

Such instruments are useful for measuring small amounts of RF power, e.g. in a waveguide.

bombardment-induced conductivity Conductivity in an insulator or semiconductor caused by ***charge carriers*** arising from bombardment by ionising particles.

bonding A low-resistance connection between conductors which ensures that they have the same voltage.

Boolean algebra An algebra in which logic relationships and operations are indicated by operators such as AND, OR, NOT etc, which are analogous to mathematical signs. It is named after its inventor George Boole (1815–64) and is used in the design of digital circuits.

booster Same as ***repeater***.

booster diode A diode in the line output stage of a TV receiver which recovers much of the energy stored in the line deflection coils and makes it available as an additional source of supply. This can be added to the normal supply to provide a high-voltage (boost) supply for the line output stage and other stages in the receiver.

booting The process of starting a microprocessor or a computer. Typically, when a microprocessor is started 'from cold' it executes the set of instructions starting at a certain memory location. Clearly this location must be held in ***ROM***. In a computer having a floppy-disk-based ***operating system***, the ROM-based instructions may display a message to the user to insert the floppy disk containing the operating system and then to execute a ***batch file*** on that disk which configures the system.

bootstrap circuit A circuit in which the input signal is connected in series with the output signal and is thus 'pulled' to an extent equal to the output-signal amplitude. A simple example is shown in *Figure B.20*. The output of the amplifier is developed across R_e in the emitter circuit and the input is applied between base and emitter so that the potential of terminal *b* of the input moves in sympathy with the output signal. The circuit is described as 'pulling itself up by hauling on its own bootstrap'.



Figure B.20 Simple example of a bootstrap circuit

bottom bend Non-linear region of the I_a–V_g characteristic of an ***electron tube*** near anode-current cut off.

bottoming Condition in an ***active device*** driven heavily into conduction in which there is very little voltage drop across the output terminals of the



Figure B.21 Conditions in a bottomed active device

device. The device is in fact operated below the knee of the output-current/output-voltage characteristic as illustrated by the operating point P in *Figure B.21*. The output voltage is independent of the magnitude of the input signal provided this is sufficient to cause saturation of the device. When an active device is used as a switch the bottomed condition is known as the on state. See ***operating point***.

bounce In television the damped oscillatory variations in signal level resulting from an abrupt change in the DC component of a ***video signal***. These cause changes in brightness or vertical positioning in reproduced pictures lasting longer than a field period. See ***ringing***.

boxcar circuit (US) or **boxcar lengthener** (US) A circuit for the production of ***pulses*** of predetermined duration, the leading edges of which are triggered by the leading or trailing edges of input pulses.

branch A single path along which current can flow between two ***nodes*** of a network. For example ac, ab and bd are three branches of the network of *Figure B.22*. See ***node***.



Figure B.22 Part of a network: ac, ab and bd are branches

breadboard A collection of components and/or devices interconnected as required in a new design of an equipment. The connections are temporary to facilitate changes of components and/or layout. A breadboard enables the performance of a new equipment to be checked.

breakdown voltage (1) Of an insulator the voltage at which the insulation



Figure B.23 A bridged-T network



Figure B.24 A bridge network

fails and current flows through or across the surface of the insulator as a discharge. (2) Of a gas, same as ***ionisation voltage***. (3) Of a semiconductor device, same as ***avalanche breakdown*** or ***Zener effect***.

bridged-T network A ***T-network*** in which a fourth element is connected in parallel with the two series elements as shown in *Figure B.23*.



Figure B.25 A bridge rectifier with reservoir capacitor

bridge network A network of four elements connected to form a square, the input being applied to two opposite corners, the output being taken from the remaining two corners. The network is shown in *Figure B.24* and is also known as a lattice network.

bridge rectifier Four rectifiers connected to form a bridge network. The combination is extensively used for ***full-wave rectification***. The rectified output has an open-circuit voltage across the reservoir capacitor approximately equal to the peak alternating input to the ***bridge circuit***, *Figure B.25*. For some applications, e.g. battery charging, the reservoir capacitor is not necessary.

brightness The subjective assessment of the amount of light received from a source. The objective measured brightness is more properly called ***luminance***. The brightness control of an oscilloscope or TV receiver determines the grid bias applied to the ***cathode ray tube*** or picture tube and hence the light output from the screen.

broadcasting The transmission of sound or TV programmes by radio or by a wire distribution system for reception by the general public.

bubble See ***magnetic bubble***.

bubble-jet printer See ***printer***.

bucket-brigade device (BBD) A semiconductor device consisting essentially of a series of capacitors linked by switches. In practice the switches are ***bipolar*** or ***field-effect transistors*** and by closing them appropriately by clocked or timed pulses, charge can be transferred from one capacitor to another and so move along the line of capacitors.

buffer memory In a ***digital computer*** an intermediate store used to compensate for the different speeds at which units can handle data.

buffer stage An ***active device*** included between two stages which permits signal transfer from one to the other but isolates the stages so that, for example, changes in impedance in one stage have no effect on the performance of the other.

It is common practice to use ***emitter followers*** as buffer stages.

bug (1) A hidden microphone or other device used for surveillance purposes. (2) A fault in hardware or software that results in a computer malfunction.

building-out network A network inserted in a circuit to modify the input impedance to a desired value. Such networks are used in ***telephony*** to permit accurate matching to a line which is incorrectly terminated at its receiving end.

build-up time or **building-up time** Same as ***rise time***.

bulk storage A facility for storing very large quantities of data. At one time this would have involved banks of tape readers, but today is more likely to be an array of ***hard disk drives***.

bulletin board system (BBS) A form of ***electronic publishing*** in which data and applications software is accessed over telephone lines by subscribers having a computer and suitable modem. Subscribers may also leave messages on the bulletin board for other subscribers to read. It is indeed the electronic equivalent of an office notice board.

bunching In a velocity-modulated tube the process whereby the density of the electron stream is modulated by the applied signal so as to gather the electrons into clusters at particular points along the drift space. See ***Applegate diagram***, ***drift space***, ***velocity modulation***.

burn-in A test in which prototype equipment is operated at full load, usually in a high-temperature environment, continuously for an extended period such as 30 days. The theory is that, if the equipment survives the burn-in test, it will survive the less arduous conditions it is likely to encounter in normal service.

burst signal Same as ***colour burst***.

bus In electronic equipment such as a computer, a conductor or set of conductors used as a path for conveying information or power from one or more sources to one or more destinations. A bus is required to carry a number of different types of information, e.g. for data transference, for control and for addressing. Some success has been achieved in designing standard buses for inter-board connections within a computer system, and for interconnections between various manufacturers' equipment.

bus-bar A conductor used to distribute power to or receive power from several branches.

bypass capacitor A capacitor used to provide a low-reactance path to signals within a particular frequency range.

An example is the capacitor which is connected across the resistor in a cathode bias circuit which is included to provide a low-reactance path for all signal-frequency components in the cathode current. The resistor then carries only the DC component and a steady voltage is therefore set up across the cathode resistor. See ***automatic cathode bias***.

byte A sequence of consecutive ***binary digits***, shorter than a word, which is treated as a unit in ***computers*** and ***data-processing equipment***.

It is generally used for a specific purpose such as synchronising or addressing. It commonly contains 8 bits and is the smallest unit of data that can be put into or removed from an 8-bit store. There are 2^8, i.e. 256, different combinations of binary digits in an 8-bit byte and they can be used, as in the *ASCII* code, to represent the upper and lower-case letters of the alphabet, numerals, punctuation marks, arithmetical and other symbols. See ***binary word***, ***address***.

C

C and C++ See ***computer language***.

cabled distribution system Same as ***wire broadcasting***.

cache An area of high-speed ***memory*** used to speed up computer processing. Caches are used in disk read and write operations, in storing character bitmaps and, above all, in central processing unit operations.

calibrate To adjust test equipment against a standard to ensure that it is working accurately.

camcorder A television camera and video cassette recorder combined in one portable unit. Camcorders are widely used by broadcasting professionals for newsgathering and location work and by hobbyists for creating 'home movies'. It replaces the cine camera formerly used for these purposes and has the advantages over them that no film processing is required so that instant playback is available and that the medium is reusable.

camera tube An ***electron tube*** used in a TV system to produce picture signals by scanning a charge image derived from an optical image of the scene to be televised. The various types of tube that are used in black-and-white or colour TV can be classified according to the type of target used (i.e. whether photo-emissive or photo-conductive) and according to the velocity of the scanning beam (i.e. whether high or low).

The earliest tubes such as the ***iconoscope*** and ***image iconoscope*** had photo-emissive targets and high-velocity scanning beams. The optical image and the scanning beam were projected on the same face of the target and the beam was arranged to scan the target obliquely so that the electron gun did not impede the light path. The chief disadvantages of these tubes (low sensitivity and the presence of strong shading signals in the tube output) stemmed from secondary electrons released from the target as a result of bombardment by the high-velocity scanning beam.

To avoid these difficulties the beam velocity was reduced to a value at which no ***secondary emission*** occurred and in this way the ***orthicon*** and ***image-orthicon*** tubes were developed. The low-velocity scanning beam lands on the target and drives its potential negative until it reaches electron-gun cathode potential. When the target potential has been thus stabilised, the scanning beam is slowed to zero velocity as it approaches the target. One of the chief problems with low-velocity tubes is that of focusing and deflecting such a beam. This was solved by use of ***orthogonal scanning*** and a long magnetic lens: these ensured that the beam always approached the target at normal incidence so that the optical image could not be focused on the scanned face. A combined transparent signal plate and target electrode was developed which enabled the optical image to be projected on one face whilst the rear face was scanned by the beam. Orthicon tubes were first used in TV in 1946. They were free of ***shading signals*** but lacked sensitivity and the target stabilisation could be lost on receipt of a large light input.

Both disadvantages were overcome in the ***image-orthicon*** tube which included an ***image section***, a ***stabilising mesh*** to prevent loss of target stabilisation and an ***electron multiplier*** into which the return scanning beam was directed. This is a highly-sensitive tube and was extensively used in black-and-white TV services for many years. It is, however, too bulky for use in colour cameras where three or four tubes are necessary. Instead, therefore, attention was directed towards photoconductive tubes (***vidicons***) which could be made very simple and compact.

In vidicon tubes, the target consists of a transparent signal plate on which is deposited a layer of photo-conductive material. The scanned face of the target is stabilised at electron-gun cathode potential as in any low-velocity tube and the signal plate is given a small positive bias. Current thus flows longitudinally through the target thickness and the magnitude of this current at any point on the target depends on the target resistance which in turn depends on the illumination of the target at that point. Early vidicon tubes suffered from lag, i.e. there was an appreciable delay between a change of light input and the corresponding change in target resistance but intensive work on photoconductive materials has resulted in satisfactory sensitivity and lag. Most modern colour television cameras incorporate three or four vidicon tubes.

cannibalise To strip serviceable components from one or more (usually non-functioning) equipments in order to build one that works.

capacitance *(C)* A property of two conductors, electrically insulated from each other, which enables them to store charge when a potential difference exists between them. The capacitance is defined as the quotient of the charge and the potential difference thus

$$\text{capacitance } (C) = \frac{\text{charge stored } (q)}{\text{potential difference } (V)}$$

The unit of capacitance is the Farad (F), this being the capacitance when the charge stored is one coulomb and the potential difference is one volt. For many purposes this unit is too large and the submultiples the microfarad (μF) equal to 10^{-6} F and the picofarad (pF) equal to 10^{-12} F are used instead.

capacitance diode Same as ***varactor***.

capacitance potentiometer A number of capacitors connected in series across a source of alternating voltage, the interconnections acting as



Figure C.1 A capacitance potentiometer using two capacitors

tapping points from which a desired value of voltage can be taken. In the simplest example there are only two capacitors as shown in *Figure C.1* and the step-down ratio is given by

$$\frac{v_{out}}{v_{in}} = \frac{1/j\omega C_2}{1/j\omega C_1 + 1/j\omega C_2} = \frac{C_1}{C_1 + C_2}$$

capacitive coupling Coupling between two circuits by virtue of mutual capacitance. The coupling capacitor may be a component connected in series with the circuits as in *Figure C.2* (a) or it may be a shunt component as in *Figure C.2* (b). In *Figure C.2* (a) the ***coupling coefficient*** is given approximately by C/C_1 where C is assumed small compared with C_1 and C_2. In *Figure C.2* (b) the coupling coefficient is given approximately by C_1/C, where C is assumed large compared with C_1 and C_2. In both circuits C_1 is assumed equal to C_2.



Figure C.2 Capacitive coupling by (a) series capacitance and (b) shunt capacitance

capacitor A component consisting essentially of two plates or ***electrodes*** separated by a ***dielectric*** and used because of its ***capacitance***. The capacitance is proportional to the area of the plates and to the ***dielectric constant*** of the insulator and is inversely proportional to the thickness of the dielectric. There are many different types of capacitor varying in capacitance between a few pF and thousands of μF and varying in voltage rating from a few volts to several kilovolts. The plates are often of aluminium and the most commonly-used dielectrics are impregnated paper, mica, plastics, ceramics, air and vacuum. The graphical symbol for a capacitor is given in *Figure C.3* and the component reference is C. See ***electrolytic capacitor***.



Figure C.3 Graphical symbol for a capacitor

capacitor loudspeaker Same as ***electrostatic loudspeaker***.

capacitor microphone Same as ***electrostatic microphone.***

capacitor store A store in which each bit of data is held as a charge on a ***capacitor. Dynamic RAMs*** are of this type.

capture ratio The ability of a radio receiver to select the stronger of two signals at the same frequency. It is measured in ***decibels***, the figure representing the ratio of the closest signal strengths that can be resolved.

carcinotron Same as ***backward-wave oscillator.***



Figure C.4 Derivation of cardioid from circular and figure-of-eight diagrams

cardioid response Type of response represented by a heart-shaped ***polar diagram***. Such a diagram is obtained by combining a circular diagram with a figure-of-eight diagram as shown in *Figure C.4*. A cardioid polar diagram is useful in radio direction finding and is obtained by combining the omnidirectional response of a vertical antenna with the figure-of-eight reponse of a loop antenna.

A cardioid response is also useful in a ***microphone*** because it gives a 180° live area, i.e. it makes the microphone effectively single-sided—ideal for positioning in stage footlights with the dead side towards the audience. This type of response can be obtained from a microphone which combines the omnidirectional (pressure) mode of operation with the figure-of-eight (pressure-gradient) mode of operation. See ***pressure-gradient microphone, pressure microphone.***

card reader In early data processing equipment a device which reads the data on a punched card. Reading was by electromagnetic feelers or photoelectric scanning.

caret An I-shaped ***cursor*** used especially in computer displays that have proportionally spaced characters. The caret is positioned between characters, unlike a conventional rectangular cursor which is positioned directly over fixed-pitch characters.

carrier Same as ***carrier wave.***

carrier storage An effect in pn ***junctions*** which have been driven hard into conduction whereby the current continues to flow for a brief period after the applied voltage has been removed. More ***majority carriers*** move towards the junction than are needed to supply the external current: these are stored and are able to continue the current briefly when the applied voltage is reduced to zero.

carrier suppression A system of AM radio transmission in which the ***carrier wave*** is not transmitted or is transmitted at very low level. This is permissible because the information to be transmitted is carried in the ***sidebands***. At the receiving end the carrier must be re-introduced to make detection possible and a suitable signal is generated locally for this purpose.

carrier wave A continuous wave, usually sinusoidal, of constant amplitude and frequency and intended for angle or amplitude modulation. The term is also used to describe the carrier-frequency component of a modulated wave. See ***amplitude modulation***, ***angle modulation***.

carry In ***computers*** and ***data-processing equipment*** the digit added to the next highest digit position when the sum of the digits in the lower position exceeds the base number.

cascade A circuit arrangement in which the output of one stage of amplification or section of a ***filter***, etc, forms the input of the next stage.

cascode An amplifier consisting of a common-emitter stage feeding into a common-base stage. The arrangement avoids instability by feedback via the collector-base capacitance in the common-emitter stage and can thus be used for stable VHF and UHF amplification. The two transistors are often connected in series across the supply as shown in *Figure C.5*. The circuit arrangement can be used with ***electron tubes*** and with ***field-effect transistors***: in fact a tetrode FET is equivalent to two triode FETs in series.



Figure C.5 A cascode circuit of two bipolar transistors

cassette A container holding sensitive storage media such as tape or film. The container protects the media against light, grease and dust and also makes it easier to handle. Audio compact cassettes and video cassettes in various formats are probably the best known examples.

catalogue A display of the contents of a ***directory***.

catcher The electrodes and associated ***cavity resonator*** in a velocity-modulated tube which extracts energy from the bunched beam. See ***velocity modulation***.

catcher diode A diode used to prevent the voltage at a particular point in a circuit from rising above or falling below a predetermined value.

cathode In general the electrode in any electron tube which is connected to the negative terminal of the supply. In ***electron tubes*** the source of electrons for the principal electron stream. In a glow-discharge tube the cathode may be cold and electrons are then liberated by bombardment of the cathode by heavy positive ions. In ***photocells*** electrons are liberated from the cathode under the stimulus of incident light. In most ***electron tubes***, however, the cathode is heated to liberate electrons and it may take the form of a filament directly heated by the passage of an electric current through it or the cathode may be indirectly heated. See ***cold cathode***, ***glow discharge***, ***indirectly-heated cathode***.

cathode AC resistance See ***electrode AC resistance***.

cathode bias Same as ***automatic cathode bias***.



Figure C.6 A cathode follower circuit

cathode follower An ***electron tube*** in which the load is connected in the cathode circuit, see *Figure C.6*. This gives 100% negative feedback which reduces the voltage gain to just less than unity. Signals applied to the grid thus emerge with little loss from the cathode; in fact, the cathode voltage 'follows' that of the grid. The advantage of the circuit lies in its high input resistance and low output resistance which make it suitable as a ***buffer stage***. There are corresponding ***emitter follower*** and ***source follower*** circuits.

cathode ray oscillograph An instrument for producing permanent records of the waveform of varying electrical quantities. The records are generally obtained by photographing the screen of a ***cathode ray oscilloscope*** and the provision for attaching a camera to the ***cathode ray tube*** is the only distinction between an oscillograph and an oscilloscope.

cathode ray oscilloscope (CRO) Instrument containing a ***cathode ray tube*** used for examining variable electrical quantities, periodic or transient, by displaying the waveform on the screen. For examining periodic waveforms the electron beam is deflected horizontally (i.e. in the X direction) by a sawtooth generator acting as a time base. The signal to be examined is applied to the vertical deflection system (Y direction) usually after amplification. By adjusting the time-base frequency to an exact sub-multiple of the fundamental frequency of the ***waveform*** a stationary pattern can be produced on the screen and detailed observation of the shape of the waveform is possible. To help in obtaining a stationary pattern there is provision for synchronising the time-base generator to the ***waveform***.

The oscilloscope is one of the most widely used tools in electronics. In addition to its obvious application in examining waveforms to detect harmonics or the presence of spurious signals it can be used in conjunction with a ***wobbulator*** for the alignment of receivers. Oscilloscopes are also widely used as indicators in ***radars***. They are also extensively employed in the examination of any physical quantity (e.g. mechanical stress) which can be converted into a corresponding ***electrical signal***. See ***double-beam oscilloscope***, ***oscillograph***.

cathode ray tube (CRT) An ***electron tube*** in which an electron beam is focused on a phosphor screen and is deflected to give a visible display. Such tubes are extensively used in oscilloscopes, in radars, and as picture tubes in TV receivers. Essentially the tubes comprise an ***electron gun*** for generating the beam, a system (either electrostatic or magnetic) for focusing the beam on the screen, a system (also either electrostatic or magnetic) for deflecting the beam, and finally a screen coated with a phosphor which emits light when struck by the beam. *Figure C.7* illustrates the construction of a cathode ray tube with ***electrostatic focusing*** and ***electrostatic deflection***, the type commonly used in oscilloscopes.



Figure C.7 Construction of cathode ray tube with electrostatic focusing and deflection: K, thermionic cathode; G, control grid; A_1, focusing anode; A_2, accelerating or final anode; V_1, V_2, plates for vertical deflection of the beam; H_1, H_2, plates for horizontal deflection of the beam; S, luminescent screen

cathode ray tuning indicator (also known as ***electron ray tube*** (US)). A small ***electron tube*** incorporating a triode amplifier and a simple cathode ray tube in which the area of ***luminescence*** on the screen can be controlled by the signal applied to the triode control grid. It was chiefly used as a tuning indicator in radio receivers the area of the display being controlled from the AGC line. The graphical symbol for the device is given in *Figure C.8*.

cation Positively-charged ***ion*** formed in a gas by ionisation or in an electrolyte by ***dissociation*** and which moves towards the negatively-



Figure C.8 Graphical symbol for a cathode ray tuning indicator

charged electrode (cathode) under the influence of the potential gradient. See ***anion***.

cat's whisker A pointed length of wire, usually copper, which was lightly pressed against a sensitive part of a crystal, e.g. galena, to form a rudimentary form of ***point-contact diode***. This was used for AM detection in the early days of broadcasting in the 1920s.

cavity magnetron A ***magnetron*** in which the anode contains a number of ***cavity resonators*** facing inwards towards the cathode. The electron stream can be made to circulate around the cathode within the space between cathode and anode, and can thus become velocity modulated as a result of passing close to the mouths of the resonators. The resultant bunching of the beam can, by suitable choice of electric and magnetic field strengths give rise to ***oscillation*** at the resonance frequency of the cavities. The resultant energy can be directed into a ***waveguide*** by means of a coupling loop in one of the resonators. In this way microwave oscillations of considerable power can be generated. See ***cavity resonator***, ***velocity modulation***.

cavity resonator A cavity contained by a conducting surface the size and shape being chosen to give resonance at a particular frequency of electromagnetic waves. At microwave frequencies such resonators replace the lumped ***inductance*** and ***capacitance*** used in tuned circuits at lower frequencies.

C battery (US) A battery used to supply the grid bias voltage for ***electron tubes***.

C core A ***magnetic core*** for a ***choke*** or ***transformer*** consisting of two C-shaped sections butted together to form a closed magnetic circuit. The C sections are made by winding magnetic alloy tape into a spiral and then cutting the resultant ring into two. C cores have better magnetic properties than laminated cores because the magnetic grain is parallel to the length of the tape. C cores are also easier to assemble with choke or transformer windings.

Ceefax The ***teletext*** service of the BBC.

cell (1) A device containing two electrodes and capable of generating an EMF between them. The electrodes may be immersed in a electrolyte and generate the EMF as a result of chemical action (see ***voltaic cell***). Alternatively one of the electrodes may be light-sensitive and produce the EMF as a result of illumination by light (see ***photocell***). (2) An elementary unit of a store, e.g. a ***memory cell*** (see ***store***). (3) The area served by a ***base station*** in a ***cellular radio*** system.

cellular radio A radio-based mobile communications system in which numerous low-power ***base stations*** each cover a small area or *cell*, all under the control of a central computer. As a mobile user leaves the area served by one base station, the computer determines which of the surrounding base stations now offers the best transmission path and switches the user over to that base station in a ***transparent*** process.

central processing unit (CPU) or **central processor** In a ***digital computer*** or ***data-processing equipment*** the unit containing the arithmetic, logic and control circuits which direct and co-ordinate operation of the computer and the ***peripheral*** devices.

centre frequency In frequency modulation, the carrier frequency.

Centronics printer standard The most widely used method of transferring data from a computer to a printer. The system uses 36-pin plugs and connectors with eight parallel conductors carrying data, making it faster than alternative serial transmission systems.

ceramic A class of material of very high resistivity and sometimes of high ***permittivity*** or ***permeability*** or with ***piezo-electric*** properties. Thus ceramic materials are extensively used in electronics in magnetic cores (as ferrite), as ***dielectrics*** and as piezo-electric elements. Ceramics cannot usually be machined and are cast into shapes suitable for their application.

chain code A ***binary code*** in which each word is derived from the previous word by shifting the bits one place to the left or the right, dropping the leading bit and inserting a bit at the end. This cyclic sequence ensures that a word cannot recur until the cycle is repeated.

channel (1) In telecommunications generally, a unidirectional signal path. (2) In particular a limited band of frequencies allocated to the transmission of a signal. The channel must be wide enough to accommodate all the significant components of the signal, e.g. ***side frequencies*** of a modulated signal. When channels are closely packed in a ***waveband***, the spacing is made greater than the channel width to give a guard band between adjacent channels. Television channels are identified by numbers in the UK, e.g. channels 21 to 68 are in Bands IV and V. (3) Of a ***field-effect transistor*** the semiconductor layer along which majority carriers flow from the ***source*** to the ***drain*** terminals. The effective width of the channel and hence its electrical resistance is controlled by the voltage applied to the ***gate***.

channel multiplier A type of electron multiplier of tubular construction in which the secondary-electron-emitting material is in the form of a continuous internal surface.

characteristic curve In general a curve representing the relationship between two quantities which illustrates the behaviour of a device or equipment. The term is, however, usually reserved for the curves which show how the current at an electron-tube electrode depends on its voltage or the voltage at another electrode, e.g. the I_a–V_a or the I_a–V_g curves of an ***electron tube***.

characteristic impedance The value approached by the input impedance of an open-circuited ***transmission line*** as its length is increased. This is also the value of ***impedance*** which, if used to terminate the line, gives an input impedance of the same value. Two types of transmission line commonly used for RF transmission are the twin-wire and coaxial cable. At RF the ***reactance*** of the distributed ***inductance*** and ***capacitance*** of the conductors has more effect than the resistance and the characteristic impedance is

given by

$Z_0 = \sqrt{(L/C)}$

where L and C are the inductance and capacitance per unit length of line. For twin-wire and coaxial cables the characteristic impedance can be calculated from the dimensions of the cross-section as indicated in *Figure C.9.*


d
r
$Z_0 = 277 \log_{10} \frac{d}{r}$
(a)
r
R
$Z_0 = 138 \log_{10} \frac{R}{r}$
(b)

Figure C.9 Characteristic impedance of (a) twin-wire and (b) coaxial transmission lines

A significant point about the characteristic impedance is that if a finite length of line is terminated by an impedance equal to the characteristic impedance then the line behaves as if it were of infinite length and no standing waves are set up on it. RF energy can thus be transmitted along it without reflection.

character recognition See ***optical character recognition.***

charge carrier A charged particle which, in moving under the stimulus of an electric field in a conductor, constitutes an electric current. Examples of charge carriers are the positively- or negatively-charged ions in an ***electrolyte*** and the ***electrons*** and ***holes*** in a ***semiconductor.***

charge-coupled device (CCD) A device in which charges on a ***semiconductor*** surface and under ***gate*** electrodes can be transferred as a packet to an adjacent area of the surface by voltage pulses applied to the gates. Such a device can be used for data storage. If the gate electrodes are thin, parallel and equidistant conducting strips then, by applying suitably-phased clock pulses to the strips, any charges placed on the semiconductor surface under the first gate are transferred along the surface of the device as in a ***shift register.***

The method of manufacture of such devices has much in common with that of IGFETs but is simpler in that no contacts or diffusions are required. The devices can be manufactured with very small dimensions so that great packing density is possible. They can thus be used as serial stores and can compete with magnetic disks and tape: indeed they are smaller than disk or tape for a given storage capacity but CCD ***stores*** are, of course, volatile. See ***volatile store.***

charge image In TV the pattern of electric charges on the target surface of a ***camera tube*** which results from the optical-image input and which, when scanned, gives rise to the picture-signal output from the tube.

charge-storage tube An electron tube in which information is retained on its active surface in the form of a ***charge image***. In most television ***camera tubes*** the image is stored on the target electrode in this form and is 'read off' by the scanning beam. ***Storage tubes*** used in VDUs also use similar principles.

charge transfer device (CTD) A ***semiconductor device*** which enables discrete packets of charge to be moved from one position to another. There are two main types: ***bucket-brigade devices*** and ***charge-coupled devices***.

Chebyshev response A ***response curve*** in which the deviations from the ideal curve are made as small as possible and approximately equal to each other over the frequency band of interest. The parameters of ***filters*** are often chosen to give a Chebyshev response.

chip Popular name for an ***integrated circuit***.

chip carrier A plastic or ceramic container for a ***monolithic integrated circuit***, the connections to which are brought out to contacts on all four sides of the package and are designed for ***surface mounting*** on a ***printed wiring board***. The chip carrier is an alternative to the DIP for a large number of contact pins and gives considerable saving in space because of its smaller contact spacing. It also gives a better thermal performance and higher speed of operation because the contacts are shorter than the pins of a DIP.

Chireix system An amplifying system used in AM transmitters in which two constant-voltage phase-modulated signals drive two saturated amplifiers feeding a common load. The power output is a function of the ***phase difference*** between the two signals and this is controlled by the modulating signal. The system was developed in France by H Chireix in the 1930s. See ***ampliphase system***.

choke An ***inductor***, the ***reactance*** of which over a particular band of frequencies is large compared with a given ***impedance***. For example an RF choke may be used at the input of an audio-frequency amplifier to prevent RF signals entering the amplifier. In such an application the choke is likely to be followed by a shunt ***capacitance*** and for successful results the reactance of the choke must be large compared with that of the capacitance so as to give great attenuation at RF.

chopping Periodic interruption of an electrical signal or a beam of light. This can be achieved by electrical or mechanical means and is used to transform a direct-current signal into an alternating signal. ***DC amplification*** is often achieved in this manner, the chopped signal being amplified in conventional capacitance-coupled amplifiers and then reconverted into DC form.

chromatic aberration Defect in an optical lens due to variation of the refractive index of the material with the wavelength and causing coloured fringes in images. The defect is usually eliminated by constructing lenses of two different materials, e.g. crown and flint glass, which give refraction without dispersion. Such combinations are known as achromatic pairs.

chrominance Those attributes of a colour which can be defined by stating the ***hue*** and ***saturation***.

chrominance amplifier The circuits which amplify the ***chrominance signal***.

chrominance signal In colour television the signal which is added to the

luminance signal to give colour information. In the ***NTSC*** and the ***PAL systems*** the chrominance signal is generated by so modulating the chrominance subcarrier that its instantaneous phase relative to that of the ***colour burst*** represents ***hue*** and its amplitude represents ***saturation***.

circle diagram A set of graphs for the solution of ***transmission-line*** problems. Normalised ***resistance*** (R/Z_0) and normalised ***reactance*** (X/Z_0) are plotted on Cartesian or polar co-ordinates and the diagram can be used to calculate, for example, the impedance of a given length of line when terminated in any value of impedance. Z_0 is the ***characteristic impedance*** of the ***transmission line***.

circuit (1) A path consisting of a conductor or a system of conductors through which an electric current can flow. (2) A ***network*** which may contain ***active*** and ***passive devices*** and may have one or more closed paths and which is intended to carry out a particular function. For example an amplifier may be said to have a circuit. (3) In telecommunications a means of bidirectional communication between two points.

circular polarisation ***Elliptical polarisation*** in which the amplitude of an electromagnetic wave remains constant whilst the plane of polarisation rotates. Vertically- or horizontally-polarised radio waves can become circularly-polarised after refraction in the ionosphere. Circular polarisation is used at some FM broadcasting stations to ensure that the signal can be received equally well on vertical and horizontal ***antennas***.

circulating register (1) A ***register*** which retains data by inserting it into a delay device, by regenerating the data and re-inserting it into the register. (2) A ***shift register*** in which data removed from one end is put into the other end in a cyclic sequence.

clamp A circuit for ensuring constancy of the potential of a particular section of a recurrent ***waveform***. Clamps are used in television transmission to ensure that the parts of the waveform which represent black in displayed pictures are maintained at a constant potential. To enable a clamp to operate at the desired instants it is driven by clamping pulses which are synchronised with the waveform to be clamped.

Clapp oscillator A ***Colpitts oscillator*** in which frequency stability is improved by using separate capacitors for tuning and for providing capacitive feedback. A circuit is shown in *Figure C.10* where C_1 is the tuning capacitor and C_2 and C_3 are high-value capacitors which provide the connections to the ***active device*** and swamp any variations in the input capacitance of the device.



Figure C.10 Circuit diagram of one form of Clapp oscillator



Figure C.11 I_d–V_{gs} characteristics of a junction-gate FET with input and output signals for class-A operation

class-A operation Operation of an ***active device*** in which the bias and signal amplitude are so chosen that output current flows throughout each cycle of input signal (assumed sinusoidal), i.e. the ***angle of flow*** is 360°.

This mode of operation is used in most small-signal stages of analogue equipment such as amplifiers and receivers, a linear part of the input-output characteristic being chosen to minimise waveform distortion as shown in Figure *C.11*. It is an inefficient mode of operation because the mean current of the ***active device*** is independent of the ***amplitude*** of the input signal. By utilising the maximum current and voltage swings possible the theoretical efficiency of a class-A output stage (measured by the ratio of the output power to the power taken from the supply) is 50% for a constant-amplitude signal. In AF amplification where signal amplitudes are constantly varying the practical efficiency is unlikely to exceed half this figure.

class-AB operation Operation of an ***active device*** which is biased to give class-A operation for small-amplitude input signals and class-B operation for large-amplitude signals, i.e. the ***angle of flow*** is between 180° and 360°. For ***electron tube*** amplifiers the suffix I is added after the letters AB to indicate that grid current does not flow at any period during the input-signal cycle and the suffix 2 is added if grid current is allowed to flow.

class-B operation Operation of an ***active device*** which is biased almost to output-current cut-off so that current flows only during one half of each cycle of sinusoidal input signal, i.e. the angle of flow is 180° This mode of operation, illustrated in *Figure C.12* is very efficient because the mean current of the active device is directly proportional to the signal amplitude and is almost zero for zero input signal. The output signal is, of course, a reproduction of only one half of each cycle of input signal but linear amplification is possible by using two class-B stages in push-pull operation and most of the output stages in transistor amplifiers and receivers are of this type.



Figure C.12 I_c–I_b characteristic of a bipolar transistor with input and output signals for class-B operation

The theoretical efficiency of a class-B stage (measured by the ratio of the output power to the power taken from the supply) is 78% and efficiencies approaching this value can be obtained in practice. The chief source of inefficiency is the no-signal or quiescent current which must be great enough to minimise ***crossover distortion***. For ***electron tube*** amplifiers the suffix 1 is added after the letter B to indicate that grid current does not flow at any time during the cycle and the suffix 2 is added if grid current is allowed to flow.

class-C operation Operation of an ***active device*** which is biased beyond cut-off of output current so that current flows for less than one half-cycle of sinusoidal input signal, i.e. the ***angle of flow*** is less than 180°. This mode of operation, illustrated in *Figure C.13*, cannot be used for linear amplification but is extensively used for RF amplification, e.g. in transmitters where a tuned output-load circuit rejects harmonics and gives a sinsoidal output signal. Efficiency (measured by the ratio of the output power to the power taken from the supply), can be very high indeed—approaching 90%. For electron-tube amplifiers the suffix 1 is added after the letter C to indicate that grid current does not flow at any period during the input-signal cycle and the suffix 2 is added if grid current is allowed to flow.

class-D operation Operation of an ***active device*** with a pulse-width-modulated input signal. Very high efficiency (measured by the ratio of output power to the power taken from the supply) is possible from a class-D stage because the input is of constant amplitude so permitting maximum use to be made of the current and voltage swings available in the output circuit. See ***pulse-width modulation***.

clear input In ***computers*** and ***data-processing equipment*** a signal applied to a ***store*** to put it into a prescribed state, usually the state of zero stored information.



Figure C.13 I_a–V_g characteristic of an electron tube with input and output signals for class-C operation

click A ***transient signal*** of very short duration. The term describes the sound of the signal when reproduced by an acoustic ***transducer***.

client In a computer network, a user or the user's computer or terminal or the code used at the user's end of the network.

client server In a computer network, a computer from which users (***clients***) can request stored data and applications.

clip art Computer ***graphics***, usually copyright-free, supplied for the express purpose of illustrating ***documents*** produced using computer systems.

clipboard In computing, an area of memory reserved for the exchange of data between applications or between ***documents*** in a single application or within one document.

clipping The process of suppressing that part of a signal waveform which lies to one side of an amplitude boundary. In the example illustrated in *Figure C.14* the parts of the waveform which are more positive than the boundary are suppressed.



Figure C.14 Input and output waveforms illustrating clipping: positive peak clipping is illustrated

clock In ***computers*** and ***data-processing equipment*** the generator of periodic signals, known as clock pulses, which govern the timing of the ***logic*** and other operations carried out by the equipment.

clock speed The frequency of the ***quartz crystal*** that regulates the operation of a central processing unit. Although this is a widely quoted criterion when comparing the performance of computers, it is not the only factor affecting the speed at which computers execute tasks. In some applications memory access time or hard disk access time may be the limiting factor.

closed circuit A circuit which is not broken and therefore in which a current can flow. In broadcasting the term is used to describe a circuit used for rehearsal or recording of a programme which is not radiated at that time to listeners or viewers.

closed-loop control A servo system in which the controlled quantity is measured and compared with the desired value and any difference is fed back into the control system so as to minimise the difference.

clustered dither See ***dithering***.

CMYK colour model See ***colour model***.

C-network A network containing a single shunt element and two series elements, one in each leg as shown in *Figure C.15*. It can be regarded as a balanced form of the ***L-network***.



Figure C.15 A C-network

coaxial cable; coaxial line; concentric line A ***transmission line*** formed from two conductors, one a wire and the other a cylinder concentric with the wire, the space between them being filled with a ***dielectric***. Cables of this type are extensively used for carrying RF signals at frequencies above approximately 10 MHz. Because the fields are confined within the outer conductor there is negligible loss by ***radiation*** from a coaxial cable. See ***characteristic impedance***.

COBOL See ***computer language***.

coding In general a method of representing information by means of characters suitable for the intended equipment or transmission system. For example in the Morse Code information can be expressed in normal language which can be spelled out, each letter of the alphabet being represented by a unique combination of dots and dashes. Thus A is ·– and B is –···. Such a code is suitable for signalling by flashing a light, sounding a buzzer or interrupting an RF carrier. For digital computers a binary coding system is generally used.

coercive field strength or **coercive force** The minimum reverse ***magnetic field strength*** which must be applied to a material to reduce the ***magnetic flux density*** to zero. It is represented by OC in *Figure C.16* and its value depends on the value of the magnetic flux density initially induced in the material.

coercivity The ***coercive field strength*** for a material which has been magnetically saturated.



Figure C.16 A B–H hysteresis curve: CO represents the coercive field strength or coercive force

coherence The maintenance of a fixed frequency. For example a ***laser*** is regarded as a coherent oscillator. In interrupted ***oscillations***, coherence implies the maintenance of phase continuity so that, at the beginning of each packet of oscillations the phase has precisely the value it would have had if the interruption had not taken place.

coincidence circuit or **coincidence gate** A ***gate*** which produces an output ***pulse*** when, and only when, all the inputs receive pulses simultaneously or within a prescribed time interval. See ***logic gate***.

cold cathode A ***cathode*** which emits ***electrons*** without being heated. This definition strictly embraces photo-emissive cathodes but the term is usually reserved for the type of cathode used in some ***gas-filled tubes***. Electron emission from the cathode arises as a result of bombardment by heavy positive ***ions*** released by ***ionisation*** of the gas and can be improved by coating the cathode with materials of low ***work function***.

collector (1) In a ***bipolar transistor***, that region into which ***charge carriers*** are swept from the base region. The carriers are ***minority carriers*** in the base region but ***majority carriers*** in the collector region. The collector-base junction is reverse-biased in normal transistor operation and hence the majority carriers are swept away from the junction and towards the collector terminal. (2) The term is also used to imply a collector of electrons, i.e. the anode in certain types of ***electron tube***.

collector AC resistance See ***electrode AC resistance***.

collimator A device for deflecting the paths of electrons or light rays in a non-parallel beam so as to produce a parallel beam.

colour See ***hue*** and ***saturation***.

colour burst In colour television a ***synchronising signal*** consisting of a few cycles of chrominance subcarrier transmitted within the ***back porch*** of each line period and used to lock the frequency and phase of the ***reference oscillator*** in receivers.

colour cell Of a ***colour picture tube*** the smallest area of the screen which includes a complete set of primary colours. For example in a delta-array tube the triangle which includes one red, one green and one blue phosphor dot.

colour code A system of colours for indicating the values, tolerances and ratings of components or the connections to them. The most familiar colour code is that used on resistors. As shown in *Figure C.17* four bands of colour are used. The first (nearest the end of the resistor) indicates the first figure of the resistance value, the next band gives the second figure and the third indicates the multiplier, i.e. the number of noughts which follow the second figure. The fourth band indicates the tolerance. The code used is as shown in Tables C.1 and C.2. As an example a resistor in which the bands are coloured yellow, violet, orange and silver is of 47 kΩ resistance, tolerance ±10%. In an older system (also indicated in *Figure C.17*) the first figure of the resistance value was indicated by the body colour, the second figure by the end colour and the multiplier by a dot colour. A similar code is used for capacitors to indicate the ***capacitance*** in pF.



Figure C.17 Two methods of indicating the value of a resistor by means of a colour code

Table C.1
Resistance
0 black
1 brown
2 red
3 orange
4 yellow
5 green
6 blue
7 purple
8 grey
9 white

Table C.2
Tolerance
± 1% brown
± 2% red
± 5% gold
± 10% silver
± 20% no fourth band

colour-difference signal In ***compatible colour television*** systems the signal obtained by subtracting the ***luminance signal*** from one of the three primary colour signals. Two colour-difference signals are used to modulate the colour ***subcarrier***, ***quadrature modulation*** being used in the ***NTSC*** and ***PAL*** systems and ***frequency modulation*** in the ***SECAM*** system. At the receiver, after detection, the colour difference signals are added to the luminance signal to yield the red, green and blue colour signals required as inputs to the picture tube.

colour model A means of defining a colour mathematically. Colour models are used in television and in computer ***graphics*** and ***desktop publishing***. The three colour models most regularly used are as follows.

The *RGB* (red/green/blue) model regards all colours as made up from the sum of the values of the three primary colours detected in human eyesight and used in the phosphor dots in a colour ***cathode ray tube***. The values of the individual primaries are sometimes expressed as percentages and sometimes as numbers between 0 and 255 (see ***true colour***). Thus white is 255,255,255 (all primaries turned fully on) and magenta is 255,0,255 (full red and full blue but no green).

The *HSV* (hue/saturation/value) model is based on the way in which the human brain interprets colour information. ***Hue*** represents the wavelength or perceived colour (such as green or violet). ***Saturation*** represents the concentration of the colour; if saturation is low the colour is pale, i.e. mixed with white. ***Value*** represents the overall level of the colour. All three figures are most commonly expressed as percentages, although hue is sometimes expressed as an angle (between 0 and 359°). Note that if value is 0, the colour is black irrespective of the hue or saturation figures and if value is 100 and saturation is 0, the colour is white irrespective of the hue.

The *CMYK* (cyan/magenta/yellow/key) model is based on the behaviour of the inks used in colour printing. Cyan, magenta and yellow allow a wide range of colours to be simulated by overprinting. The inks are assumed to be printed on a white background and the colours are subtracted. Thus cyan and yellow make green while magenta and yellow make the crimson sometimes called 'warm red'. Key is black and is used both to print truly black areas and to produce darker shades of other colours. Values are expressed either as pecentages or as numbers between 0 and 255.

colour television Television in which the pictures are reproduced in colours simulating those of the original scene. At the transmitting end an image of the original scene is analysed into its red, green and blue components and information about these components is contained in the ***chrominance signal***. Modern colour TV systems are compatible and the transmitted signal is basically that of a black-and-white system to which the chrominance signal is added to give information about the ***hue*** and ***saturation*** of the colours in the scene. The chrominance information is conveyed by a colour subcarrier which, with its ***sidebands***, is interleaved with the sidebands of the black-and-white (luminance) signal. A number of different subcarrier modulation systems are in current use. See ***compatibility***, ***chrominance***, ***NTSC***, ***PAL***, ***SECAM***.

colour temperature Of a light source the absolute temperature of a ***full radiator*** (black body) which gives the same colour.

colour video signal or **composite colour signal** (US) In colour television the signal which gives complete colour-picture information and includes ***synchronising signals*** and ***colour burst***.

Colpitts oscillator A sinusoidal oscillator in which the frequency-determining element is a parallel *LC* circuit connected between input and output terminals of an ***active device***, ***positive feedback*** being obtained by connecting a tapping on the capacitive branch of the *LC* circuit to the common terminal (***cathode***, ***emitter*** or ***source***) of the active device. The



Figure C.18 A transistor Colpitts oscillator

effective tuning ***capacitance*** is that of the two capacitors connected in series, the common connection being used as tapping point. ***Figure C.18*** gives the circuit diagram of a transistor Colpitts oscillator. In VHF oscillators the inter-electrode capacitances of the active device can be used as the series-connected capacitors providing the positive feedback.

coma A defect in optical and electron lenses which causes the image of a round dot to develop a comet tail and so appear pear-shaped.

comb An assembly of discrete frequencies spaced at regular intervals within a given frequency band.

combination frequencies The frequencies generated when two sinusoidal signals at different frequencies are applied to a device with a non-linear characteristic. The combination frequencies are given by

$$mf_1 \pm nf_2$$

where f_1 and f_2 are the frequencies of the two input signals, m and n being the integers 1, 2, 3 etc.

combinational logic element Same as ***logic gate***.

command An instruction given to a computer, either by typing it on the keyboard or by choosing it from a ***menu***. A command normally consists of a ***keyword*** which may be followed by one or more ***arguments*** which specify how the command is to be executed. The command is interpreted and executed by the operating system or by an interactive language such as BASIC or by an application program.

command and control The process of controlling mobile personnel and equipment engaged in some project or mission, e.g. in the emergency services. Command and control equipment may integrate radio and telephone communications with computer-controlled displays to show, e.g. the present location and deployment of mobile units superimposed over maps.

command mode In ***interactive computer languages*** the state when no ***program*** is being executed and the computer will respond immediately to commands typed at the keyboard.

common-base circuit (also known as **grounded-base circuit** (US)) A ***bipolar transistor*** circuit in which the input signal is applied between ***base*** and ***emitter***, and the output signal is derived from ***collector*** and base, the base terminal thus being common to input and output circuits. This arrangement gives a very low input resistance and a very high output



Figure C.19 Essential features of the common-base circuit



Figure C.20 Essential features of the common-collector circuit

resistance. Current gain is less than unity but voltage gain can be considerable. The output signal is in phase with the input signal. The basic form of the circuit is shown in *Figure C.19*. It is often used for VHF and UHF amplification as part of a ***cascode*** circuit.

common-collector circuit A ***bipolar transistor*** circuit in which the input signal is applied between ***base*** and ***collector***, and the output signal is derived from ***emitter*** and collector, the collector terminal thus being common to input and output circuits.

This circuit arrangement has a high input resistance and a low output resistance. Voltage gain is approximately unity but current gain can be considerable. The output signal is in phase with the input signal. Because of the unity voltage gain signals applied to the base emerge with negligible loss from the emitter. For this reason the circuit is often known as an ***emitter follower***. The base form of the circuit is shown in *Figure C.20*. It is used where equipment requires a high input resistance or low output resistance and as a buffer stage.

common-emitter circuit (also known as **grounded-emitter circuit** (US)) A bipolar transistor circuit in which the input signal is applied between base and emitter, and the output signal is derived from the collector and emitter, the emitter terminal being thus common to input and output circuits. This form of connection gives a low input resistance and a high output resistance (although the ratio is not so high as for the ***common-base circuit***). Current gain and voltage gain can be considerable. The output signal is in antiphase with the input signal. This is the most widely used of the three basic transistor circuits in analogue equipment probably because it is capable of greater output power than the others. The basic form of the circuit is shown in *Figure C.21*.



Figure C.21 Essential features of the common-emitter circuit

common-mode rejection ratio For a differential amplifier a figure of merit which assesses its ability to reject the same signal applied to both input terminals. An ideal differential amplifier responds only to the difference between the input signals so that there should be zero output for equal input signals. The ratio is best measured by use of alternating input signals to avoid difficulties caused by ***dc offset voltage***.

common-mode signal The algebraic average of the two signals applied to the inputs of a ***differential amplifier***. If the two inputs are of equal amplitude and are accurately in antiphase, the common-mode signal amplitude is zero. If, on the other hand, the two inputs are in phase, then their common amplitude is also that of the common-mode signal. A perfect differential amplifier does not respond to common-mode signals but see ***common-mode rejection ratio***.

common return A return ***path*** that is common to two or more components or circuits; in electronic circuitry one of the supply lines often provides a common return.

communications receiver A radio receiver designed to cope with difficult transmission conditions. Such receivers usually have several wavebands, facilities for controlling the bandwidth of the ***IF amplifier***, a ***BFO***, an efficient ***a.g.c.*** system and, most importantly, a good ***signal-to-noise ratio***.

compact disc (CD and CD-ROM) A disk, most often 5 inches in diameter, carrying a digital recording in the form of a series of minute bumps on a spiral path. The bumps are of the order of 1 μm in diameter and the face of the disc accommodates about 20000 tracks. The disc is replayed by a low-power laser beam which is reflected back along its incident path in the absence of a bump but is scattered if it strikes a bump. Servos are used to enable the laser beam to follow the tracks accurately, to keep the beam in focus on the disc surface and to maintain constant linear speed of the disk as it passes the beam (a master oscillator being used to provide a reference standard). As a consequence of the constant track speed, the rotational speed of the disc decreases from about 500 rpm to 200 rpm as the laser beam moves from its innermost to its outermost position.

Compact discs are used to record mono and stereo sound and the single recorded side gives a maximum playing time of about 75 minutes of stereo sound. A system of PCM is used to record the two sound signals and other signals associated with the servo systems. Sound reproduction from compact discs is greatly superior to that from conventional long-playing disks in freedom from distortion, signal-to-noise ratio, dynamic range and stereo separation.

A further advantage of CDs over other recording media such as long-playing records and tape is that there is no physical contact between the rotating disk surface and the reading head. There is therefore no wear on the disk. Consequently, unless it meets with some catastrophic accident, a CD should sound the same after thousands of playings as when it was new.

Compact discs are also widely used for the mass distribution of computer ***software***. Known as CD-ROMs, these discs have a capacity of over 600 megabytes, much larger than that of ***floppy disks***, facilitating the distribution of very large collections of software. For major software houses it is considerably cheaper to mass produce their software on CD-

ROM than on floppy disks and this is sometimes reflected in software prices.

Other uses for compact disc include the storage of photographs (see ***Photo-CD***) and video (see ***video disk***).

companding The process of compressing a signal at one point in a communications system and of expanding at a later point to restore the original volume range. The process is used to improve the ***signal-to-noise*** ratio of the system and to be effective, the compression must take place before the point at which noise is introduced and expansion after that point. For example in a radio system the compressor is at the transmitter and the expander at the receiver, noise being introduced in the radio link. See ***compression***, ***expansion***.

comparator A circuit which compares two signals and gives an output indicating the result of the comparison.

comparator element Same as ***equivalence element***.

compatibility (1) Of a colour television system that property which permits the colour signal to be reproduced by a normal black-and-white television receiver as a satisfactory black-and-white picture. (2) Of a stereophonic FM broadcasting system that property which permits the stereo signal to be reproduced by a normal monophonic receiver as a satisfactory monophonic signal.

compensation theorem If a ***linear network*** is modified by introducing an increment ΔZ in the impedance of one of the branches, the resulting current increment at any point in the network is equal to the current that would be produced at that point by a compensating voltage of $-I\Delta Z$ acting in series with the modified branch. I is the current in this branch before modification.

compilation See ***computer language***.

complementary metal-oxide-semiconductor (CMOS or COSMOS) A form of construction of ***logic monolithic integrated circuits*** using complementary ***insulated-gate field-effect transistors*** in pairs. The logic inverter stage illustrated in *Figure C.22* is an example of a CMOS circuit.



Figure C.22 A CMOS logic inverter stage

complementary transistor logic (CTL) Logic circuits which make use of pnp and npn ***transistors***.

complementary transistors pnp and npn ***transistors*** with similar characteristics. A positive signal applied to the base of an npn transistor increases the collector current but the same signal applied to the base of a pnp transistor decreases the collector current. Thus if the same signal is applied to the bases of a complementary pair of transistors, the transistors operate in ***push-pull*** without need for a phase-splitting circuit.

complex instruction set computer (CISC) A ***microprocessor*** having traditional ***architecture***, capable of executing a wide repertoire of commands. The processors used in IBM PC-compatible computers are of this type. The alternative is a ***reduced instruction set computer*** (RISC), which has a limited repertoire of commands, but is faster.

compliance In a mechanical or acoustical oscillating system a property of a spring or similar component which enables it to oppose a change in applied force and is measured by the displacement caused by unit force. It is thus the reciprocal of stiffness. Compliance is analogous to ***capacitance*** in electrical oscillating circuits. A spring can store mechanical energy when it is compressed just as a ***capacitor*** can store electrical energy when it is charged.

composite colour signal (US) See ***synchronising signal.***

composite signal (US) Same as ***video signal.***

compound connection Same as ***Darlington pair.***

compression (1) Reduction of the volume range of a signal by varying the ***gain*** to which it is subjected according to the mean volume level, the gain being greater for low signal volumes than for high signal volumes. Compression permits the transmission of higher mean volume levels thus improving ***signal-to-noise ratio.*** (2) In computing and data processing, the reduction of the size of ***files*** and therefore of their storage space requirement or transmission ***bandwidth***. Various compression ***algorithms*** are used, according to the type of data in the file. ***Real-time*** compression and decompression processing is sometimes built into filing systems, greatly enhancing their effective capacity.

compression ratio The ratio, usually stated in decibels, of the gain at a reference signal level to the gain at a higher stated level. See ***compression***.

computer An equipment which accepts information, carries out specified mathematical and/or logical operations upon it and supplies the required answer. Computers are sometimes called data-processing equipment. The information input must be in a form which the computer can accept and there are two principal types of computer, the analogue and the digital. See ***analogue computer, digital computer.***

computer-aided design (CAD) The use of a computer, particularly with ***graphics***, to assist in the design of engineering, structural or architectural projects. As an example of the ***interactive*** design possible by this means, three-dimensional representations of car bodies, building frameworks or printed-wiring-board layouts can be created and modified by the use of ***lightpens*** and ***mice***.

computer-aided engineering (CAE) Generic term embracing ***computer-aided design*** and ***computer-aided manufacture***.

computer-aided manufacture (CAM) Production of goods with the assistance of a computer or numerically-controlled machinery.

computer-aided software engineering (CASE) A technique used in some branches of computing, especially ***databasing*** and business modelling, in which the ***program*** is generated by a computer. The problem to be solved by the new program is defined using CASE tools which may employ a ***graphical user interface*** to indicate relationships between ***repository*** members and outside events. CASE is a much faster and more powerful technique than conventional programming for certain kinds of ***application***.

computer control Operation in which the variables controlling a process are applied to a computer which carries out the required mathematical and/or logical operations on the inputs, the output of the computer being used to control the process.

computer language A combination of symbols, words and statements governed by a syntax and used to construct a ***computer program***. Ultimately the central processing unit only understands a limited range of instructions—*machine code* or *machine language*—which it reads in binary form. The earliest method of programming involved writing machine code directly. This was a cumbersome task since it required an intimate knowledge of the processor and provided no assistance in error finding.

Today some ***applications*** and ***subroutines***, especially those that involve intensive arithmetic, are still programmed in machine code because of its speed of execution. Instead of writing the program directly in machine code, however, a programming language called an *assembler* is used. This uses as source code a sequence of ***mnemonics*** which represent the processor instructions; these are easier to understand than the binary numeric codes themselves. The source code is written in a word processor or text editor and when finished is converted to executable machine code in a process called *assembly*. Because assembler source code inevitably is closely related to the machine code to which it is converted, an assembler is regarded as a *low-level* computer language.

For many applications computer programs are written in *high-level languages* such as C and BASIC in which the source code bears no direct relationship to the machine code that is ultimately executed. High-level languages use ***keywords*** to represent common operations such as displaying output on the VDU or searching text for a certain character sequence. They also allow the programmer to define *subroutines* or procedures for frequently used sequences of operations and these can be called as required from any point in the program. In most high-level languages the completed source code must be converted to executable machine code in a process called *compilation* before it can be executed. Some high-level languages, however, do not require compilation. Instead the source code itself is executed in ***real time*** by a program called an *interpreter*. Inevitably execution is slower than in a compiled language, but interpreted languages are interactive and easy to use; moreover run-time errors usually generate informative error messages such as 'Variable not found at line 360'.

Some of the computer languages in common use are:

C and C++ A general-purpose compiled language using a rigid syntax and structure. One benefit is the comparative ease with which one set of source code can be differently compiled for use on computers having widely differing central processing units and operating systems.

BASIC (Beginner's All-purpose Symbolic Instruction Code). English keywords and simple syntax make this one of the most widely-used languages, especially in microcomputers where it is generally interpreted rather than compiled.

Algol in which the instructions are presented in the form of algorithms.

FORTRAN (FORmula TRANslation) which is mainly used for instructions designed to solve mathematical or logic problems.

COBOL (COmmon Business-Oriented Language) intended for business and commercial use.

Forth used primarily for process control and scientific applications, is unusual in being a compiling language that is interactive. Forth consists of a dictionary of keywords and a compiler; applications are implemented by repeatedly defining new keywords in terms of the original or previously-defined keywords until one keyword is defined which embraces the entire application.

Pascal uses BASIC-like keywords in a very rigid and logical syntax. Because its use fosters an orderly and systematic approach to programming it is much used in education although originally developed for scientific applications.

Occam has been specially developed for use with ***transputers***.

computer terminal An item of equipment at which data can be fed into a (possibly-remote) computer or can be received from it. The data may be fed in via a keyboard and may be received in alphanumeric or graphical form.

concentric line Same as ***coaxial cable***.

concertina phase-splitter Circuit in which an active device is located at the midpoint of the load resistor so that equal and opposite signal voltages are developed at the ***anode*** (collector or drain) and ***cathode*** (emitter or source). *Figure C.22* shows a pnp transistor used in such a circuit.



Figure C.23 Simplified concertina phase-splitter using a pnp transistor

condenser An obsolete term for ***capacitor***.

condenser microphone See ***electrostatic microphone***.

conditional implication gate Same as ***IF-THEN gate***.

conductance (G) The reciprocal of resistance and the real component of admittance. For a purely-resistive AC circuit, the voltage and current are in phase and the conductance is the ratio of current to voltage.

conduction band In an ***energy-level diagram*** the energy range of electrons which have broken free of the parent atom and can thus act as ***charge carriers***, i.e. they can move freely under the influence of an electric field.

conduction cooling Of a device or equipment dissipating considerable power a method of removing heat by use of a ***heat sink*** in good thermal contact with the device. The heat sink may be a finned radiator or a prepared surface on a panel.

conductivity In general a term expressing the ability of a material to carry an electric current. More specifically conductivity is the reciprocal of ***resistivity***. The conductivity of metals, for example, is better, i.e. lower than that of non-metals.

conductor Any element in a component or a ***circuit*** providing a path for the passage of electric current, e.g. the strips of copper on a ***printed circuit*** board.

conjugate impedances Two ***impedances*** with equal values of resistive component and in which the reactive components are equal but of opposite sign.

constant-amplitude recording In disk recording a characteristic for which constant-amplitude sinusoidal signals applied to the recording head give constant recorded amplitudes. See ***constant-velocity recording***.

constant-current characteristics Graphical relationship between the voltages at two electrodes of an ***electron tube*** necessary to maintain the current at one of them constant. The term is generally applied to the V_a–V_g characteristics of an ***electron tube*** for constant I_a which are used in assessing the performance of ***high-power triodes*** as output stages in transmitters.

constant-current modulation Same as ***Heising modulation***.

constant-*k* filter A ladder network composed of ***reactances***, the series reactances being of opposite sign to the shunt reactances. Because positive (i.e. inductive) reactance is directly proportional to frequency and negative (i.e. capacitive) reactance is inversely proportional to frequency, the product of the series and shunt reactances is independent of frequency. The constancy of this product has given this type of filter its name.

Constant-*k* filters may be low-pass, high-pass, band-pass, etc. types but the steepness of fall-off in response at the edges of the passbands is not good and the ***characteristic impedance*** is not constant over the passband so that a purely-resistive termination is not satisfactory. Both disadvantages can be overcome by the inclusion of m-derived sections or half-sections. See ***m-derivation***.

constant luminance system A colour TV system in which the brightness of the reproduced picture depends solely on the transmitted ***luminance signal*** and is unaffected by the ***chrominance signal*** transmitted with it. This is an ideal which is not perfectly achieved in the ***NTSC***, ***PAL*** and ***SECAM*** colour television systems currently in use.

constant-resistance network A network which, when terminated in a pure ***resistance*** of value *R*, gives an input resistance of *R* which is independent of frequency. Attenuators and equalisers are usually designed as constant-resistance networks so that they can be inserted in circuits without affecting resistance terminations. An example of a constant-resistance network is the



Figure C.24 A lattice network in which $Z_1Z_2 = R^2$ is an example of a constant-resistance network

lattice network of *Figure C.24* in which Z_1Z_2 must equal R^2. Z_1 and Z_2 must hence be inverse impedances to give the desired constant-resistance property.

constant-velocity recording In disk recording a characteristic for which constant-amplitude sinusoidal signals applied to the recording head give constant recorded velocities, i.e. the recorded amplitude is inversely proportional to frequency. In practice such a characteristic cannot be used over the whole of the audio spectrum because of the possibility of exceeding the groove spacing at low frequencies and giving inadequate ***signal-to-noise ratio*** at high frequencies. Moreover the chosen characteristic must take into account the fact that sound amplitudes are smaller at high frequencies than at low. Practical recording characteristics tend therefore to be a compromise between constant amplitude and constant velocity. See ***constant-amplitude recording***.

contact The conductive areas which touch to establish ***continuity*** in a switch or a relay.

continuity A continuous low-resistance electrical path between two points.

continuous wave (CW) Radio waves of constant amplitude and frequency. The transmission and reception of such a wave establishes a link between transmitter and receiver but to enable information to be sent over the link the continuous wave (carrier wave) must be keyed on and off in accordance with a code (e.g. Morse) or must be modified in amplitude, phase or frequency, i.e. must he modulated. See ***interrupted continuous wave***, ***modulation***.

contrast (1) In sound transmission the ***dynamic range***, i.e. the ratio of the loudness of the loudest to the quietest passages in a programme. This range must be compressed before a sound programme can be recorded or transmitted. Methods of expansion are available to re-establish the original dynamic range. (2) In TV, the ratio of the brightness levels of two parts of a displayed picture. It is determined by the amplitude of the ***video*** signal input to the picture tube and hence by the gain of the preceding amplifiers.

contrast gradient Same as ***gamma***.

control code An ***ASCII*** character in the range 0 to 31. Such characters represent instructions to perform some operation on the output device rather than printable characters. For example code 7 ('BEL') emits a beep and code 9 ('TAB') moves the insertion point to the next tab stop. From a keyboard these codes may be issued by using the **Ctrl** key in conjunction with alphabetic and other keys.

control grid An ***electrode*** situated between the ***cathode*** and the other electrodes of an ***electron tube***, the potential of which determines the magnitude of the electron current flowing from the cathode to the other electrodes. The control grid is usually situated very close to the cathode and is constructed in the form of a wire spiral the pitch of which can be adjusted during manufacture to give the required degree of control over the density of the electron stream. Thus the pitch of the grid determines the ***mutual conductance*** of the tube. In a ***cathode ray tube*** the control grid (sometimes known as the modulator) is often in the form of a disk containing a small aperture through which the electron beam passes.

control impedance Same as ***unilateral impedance***.

controller In ***computers*** and ***data-processing equipment*** an item of ***hardware*** which controls the operations of ***peripheral units*** according to instructions from the central processor.

controlled-carrier modulation Same as ***floating-carrier modulation***.

controlled silicon rectifier (CSR) Same as ***thyristor***.

control ratio In a ***thyratron*** the slope of the characteristic relating the anode voltage with the critical grid voltage. *Figure C.25* shows that the characteristic has a long linear section showing that the control ratio is constant over a wide range of operating voltages.



Figure C.25 Variation of critical grid voltage with anode voltage for a thyratron

control unit Of a ***digital computer*** that section which is responsible for interpreting and acting upon the input instructions and for applying signals to the ***arithmetic unit*** and other sections of the computer to enable it to carry out the allotted task.

convection cooling Of a device or equipment dissipating considerable power a method of removing heat which relies on natural convection and radiation from the device. An adequate clear space must be provided around the device for this method to be successful.

convergence In a colour picture tube the adjustments which ensure that the three primary colour images are correctly superposed.

conversion conductance (g_c) or **conversion transconductance** (US) The ratio of a small change in the wanted-signal component in the output current of a ***frequency changer*** to the small change in signal-frequency input voltage which gives rise to it under specified operating conditions.

converter General term for an equipment which changes: (1) The nature of a current, e.g. an AC to DC converter (a device changing DC to AC is usually known as an ***inverter***). (2) The voltage of a power supply, e.g. one converting a 12 V DC supply into 240V DC. (3) The frequency of a signal, e.g. the ***frequency changer*** in a ***superheterodyne receiver***. (4) The form in which information is coded, e.g. a television standards converter which converts a 525-line signal into a 625-line version of the same picture.

coprocessor An additional ***processor*** in a ***computer*** designed to carry out specific functions, such as mathematical operations or handling graphical output, relieving the burden on the main processor.

cordless telephone A telephone in which the link between the handset and the base is by ***radio***, both containing ***transceivers***. The advantage is that the user may roam freely within the unit's range during a telephone conversation. The handset is powered by an internal rechargeable battery which is recharged when it is plugged into the base unit; this requires a mains supply.

corona discharge Visible discharge of electricity surrounding a charged conductor when its potential exceeds the critical value at which the surrounding air is ionised. The discharge is often accompanied by a hissing noise and becomes more marked as the radius of curvature of the conductor is reduced. Sharp points, therefore, give pronounced corona discharge and to minimise the effect the surface of the conductor must be smooth.

counterpoise Same as ***artificial earth***.

counting The process of deriving one output pulse for every *n* input pulses. If $n = 2$ the device is a ***binary counter*** and if $n = 10$ it is a ***decade*** counter. If the input pulses are at regular intervals the device is more properly known a ***frequency divider***. Usually a counter is a circuit which can take up a number of different states and which changes from one state to another in a particular sequence each time an input pulse is received.

coupling Any means whereby power can be transferred from one circuit to another. The circuits may be physically separated, power being



(a) (b)

Figure C.26 Examples of coupling by (a) series capacitance and (b) shunt inductance

transferred between them by magnetic or capacitive means, or they may be connected, power being transferred via components common to both circuits. The common component can be in series as C_1 in *Figure C.26* (a) or in shunt as L_3 in *Figure C.26* (b).

coupling coefficient (k) A quantitative measure of the degree of coupling between two circuits. It is equal to the ratio of the ***mutual impedance*** (resistive, inductive or capacitive) between the circuits to the geometric mean of the two impedances of like kind in the two circuits. The maximum possible value of k is unity and values used in practice are often as low as 0.01.



(a) (b) (c)

Figure C.27 Examples of coupling by (a) mutual inductance, (b) shunt capacitance and (c) series capacitance. The coupling coefficient for each circuit is given in the text

If two tuned circuits L_1C_1 and L_2C_2 are coupled by mutual inductance M as shown in *Figure C.27* (a) the coefficient of coupling is given by

$$k = \frac{M}{\sqrt{(L_1L_2)}}$$

and if the two circuits are identical $L_1 = L_2 = L$, so that

$$k = \frac{M}{L}$$

For shunt-capacitance coupling shown in *Figure C.27* (b) the coefficient of coupling is given by

$$k = \frac{\sqrt{(C_1C_2)}}{C_3}$$

in which C_1 and C_2 are assumed small compared with C_3. If $C_1 = C_2 = C$

$$k = \frac{C}{C_3}$$

For series-capacitance coupling shown in *Figure C.27* (c) provided C_1 and C_2 are large compared with C_3, the coefficient of coupling is given by

$$k = \frac{C_3}{\sqrt{(C_1C_2)}}$$

approximately and if $C_1 = C_2 = C$

$$k = \frac{C_3}{C}$$

The examples given are of intentional power transfer, but coupling is sometimes unwanted because it can give rise to *instability* or *oscillation*. To avoid such coupling it may be necessary to employ ***electric*** or ***magnetic screening*** or ***decoupling***.

covalent bonds The bonds between two similar atoms which share two ***electrons***, one from each atom. This occurs in the tetravalent atoms of ***germanium*** and ***silicon*** which therefore behave in some respects as though they had eight electrons in the outermost shell. This is sufficient to fill the shell which accounts for the very low electrical conductivity of pure germanium and silicon.

CPS emitron tube Same as ***orthicon***.

crash In computers and data processing equipment, an ***error*** which results in total loss of control of the system. A common cause is that the processor begins executing an endless loop of instructions to which the user has no input. To the user, the system often appears to 'freeze'. His only recourse is to reset and restart the system. Any processed data that had not been stored at the time of the crash is usually lost irretrievably.

critical coupling The degree of coupling between two circuits tuned to the same frequency which permits maximum transfer of energy from one to the other at the ***resonance frequency***. For degrees of coupling smaller than the critical value the combination has a single-peaked response curve and for degrees of coupling greater than critical the ***frequency response*** has two peaks equidistant from the resonance frequency, the peak separation increasing with increase in coupling as shown in *Figure C.28*. Coupled circuits giving a two-peaked response, with the peaks near to the resonance frequency, are often employed as bandpass filters in RF and IF amplifiers in a receiver. The critical value of the coupling coefficient is given by



Figure C.28 Response curves for two identical tuned circuits showing the effect of varying the degree of coupling

$$k = \frac{1}{\sqrt{(Q_1 Q_2)}}$$

where Q_1 and Q_2 are the Q values of the two tuned circuits. If the circuits are identical and $Q_1 = Q_2 = Q$

$$k = \frac{1}{Q}$$

Thus if $Q = 100$, a common value, the critical value of k is 0.01.

critical damping The condition where the rate of loss of energy is just sufficient to prevent free oscillation of an oscillating system. For a resonant electrical circuit the value of series resistance which gives critical damping is equal to $2\sqrt{(L/C)}$. As an example of a mechanical system the friction in the moving parts of a measuring instrument is commonly adjusted to give critical damping so that the pointer takes up its final reading very quickly and without overshoot (which is the start of ***oscillation***).

critical grid current In a ***thyratron*** the value of the grid current corresponding to the ***critical grid voltage***.

critical grid voltage In a ***thyratron*** with a particular value of anode voltage the minimum value of grid voltage at which anode current begins to flow. The value of the critical grid voltage depends on the anode voltage, becoming less negative as the anode voltage is reduced as shown in *Figure C.25*.

critical-space tetrode A ***tetrode*** in which the spacing between ***screen grid*** and ***anode*** is large so that the negative charge of the electron stream in it at any instant is sufficient to act as a ***suppressor grid*** and so prevent secondary electrons released from the anode from reaching the screen grid. In this way the ***tetrode kink*** can be eliminated so improving the ability of the tube to handle large output voltage swings.

cross coupling Unwanted ***coupling*** between two signal paths which can result in ***crosstalk***.

cross modulation Transfer of the ***modulation*** of one signal to another. In AM reception this can be caused by non-linearity in RF stages. As a result the carrier of a wanted signal becomes modulated by the unwanted modulation of another signal.

crossover distortion In a class-B amplifier, waveform distortion caused by too low a value of standing current. It takes the form of a discontinuity at the datum level of a sinusoidal signal as shown in *Figure C.29* caused by the slight delay which occurs whilst each half of the output stage takes over from the other. See ***class-B operation***.



Figure C.29 Crossover distortion

crossover frequency (1) In ***dividing networks*** the frequency at which equal power is delivered to each of the adjacent frequency channels (assumed correctly terminated). It is the frequency, in fact, at which the signal crosses over from one channel to the other. In two-unit ***loudspeakers*** the crossover frequency is usually between 500 Hz and 2 kHz. (2) See ***turnover frequency***.

crossover network Same as ***dividing network***.

crossover voltage In ***cathode ray tubes*** the voltage of a secondary-emitting surface at which the ***secondary emission ratio*** is unity.



Figure C.30 Variation of secondary emission ratio with surface voltage

There are generally two such voltages as shown at V_1 and V_2 in *Figure C.30*. From *Figure C.30* it is possible to predict the voltage at which the target of a TV camera tube or the screen of a CRT will stabilise. For example if the initial target potential is below V_1 the secondary emission ratio is less than unity and the number of ***electrons*** striking the target exceeds those lost from it. Thus the target potential is driven negative until it stabilises at a potential near that of the ***electron-gun cathode***. This is the type of target stabilisation used in all low-velocity camera tubes.

If, however, the initial target potential is between V_1 and V_2 and if the final anode potential of the electron gun is also between these two voltages then the secondary emission ratio is greater than one and the target releases more electrons than it gains from the ***electron beam***. If the target potential is initially below that of the final anode all the secondary electrons released are collected by the final anode and the target potential rises until it is approximately equal to that of the final anode. If the target potential is initially above that of the final anode the retarding field between target and anode returns the secondary electrons to the target and the target potential falls until again it is approximately equal to the final anode potential. This is the type of stabilisation which occurs in high-velocity TV camera tubes and in ***cathode ray tubes***.

crosstalk Unwanted signals appearing in one signal path as a result of ***coupling*** with other signal paths. An example is the ***induction*** of unwanted speech signals into one pair of conductors from neighbouring pairs in a telephone cable.

crowbar circuit Protective circuit which, in the event of a fault that could damage equipment by excessive voltage or excessive current, applies a short circuit across the supply to the equipment, causing the ***fuses*** to blow or a cut-out to operate thus isolating the equipment from the supply. The short-circuiting device must have very low resistance when triggered into conduction by the fault-detecting circuit and may be, for example, a ***thyratron*** or a ***thyristor***.

cryogenics The study of the properties of devices at temperatures near absolute zero (–273°C or 0°K). See ***superconductivity***.

cryotron (cryogenic store) A ***store*** which makes use of the ability of a magnetic field to control the transition from the normal to the superconductive state of resistive elements.

crystal See ***piezo-electric crystal***.

crystal bimorph See ***bimorph***.

crystal-controlled oscillator See ***crystal oscillator***.

crystal diode A ***semiconductor*** crystal in contact with a metal probe (see ***point-contact diode***) or two different types of semiconductor crystal in contact (which may be regarded as a crude form of ***junction diode***). These were used for detection in the early days of broadcasting and successful results depended on finding and retaining sensitive points on the crystal surfaces. See ***cat's whisker***, ***crystal receiver***.

crystal filter A filter network containing one or more ***piezo-electric crystals*** as frequency-determining elements. The resonant properties of the crystals are used when the filter is required to accept or reject a narrow band of frequencies.

crystal growing See ***crystal pulling***.

crystal loudspeaker A ***loudspeaker*** which relies for its action on the ***piezo-electric effect***. The AF signal is applied to a crystal ***bimorph*** and the resulting vibrations of the bimorph are mechanically coupled to the diaphragm. Such loudspeakers generally operate over a limited frequency range at the upper end of the AF spectrum and form one unit (the tweeter) of a multi-unit loudspeaker. The graphical symbol for a crystal loudspeaker is given in *Figure C.31* (a).



(a) (b)

Figure C.31 Graphical symbols for (a) crystal loudspeaker and (b) crystal microphone

crystal microphone A microphone which relies for its action on the ***piezo-electric effect***. In one type the sound waves strike a diaphragm and the resulting mechanical vibrations are coupled to a crystal ***bimorph***. The voltages developed across the faces of the bimorph constitute the microphone output. In another type of crystal microphone there is no diaphragm and the sound waves impinge directly on a ***sound cell*** which consists of two crystal bimorphs mounted back-to-back. The graphical symbol for a crystal microphone is given in *Figure C.31* (b).

crystal oscillator An ***oscillator*** the frequency of which is controlled by a ***piezo-electric crystal*** usually of quartz. Such oscillators have great stability and are used as frequency standards, in signal generators and as master oscillators in radio transmitters.

crystal oven A thermostatically-controlled oven containing a ***crystal-controlled oscillator***. By maintaining it at a constant temperature, a crystal oscillator can give very high ***frequency stability***. Such ovens have been used in broadcasting transmitting stations to achieve the required stability of ***carrier*** frequency.

crystal pickup A disk-reproducing head which relies for its action on the ***piezo-electric effect***. The movement of the stylus point caused by the groove modulation is coupled to a crystal ***bimorph*** and the voltage developed between its opposite faces constitutes the pickup output. A stereo pickup includes a mechanical device for resolving the movement of the stylus into two directions at right angles to each other, each movement driving a separate bimorph. The symbol for a crystal pickup is given in *Figure C.32*.

crystal pulling A method of producing large single crystals such as are required in the manufacture of ***semiconductor*** devices by slowly withdrawing a developing crystal from the molten semiconductor material.



Figure C.32 Graphical symbol for a crystal pickup

crystal receiver (1) A radio receiver comprising a ***tuned circuit***, a crystal detector and a pair of ***headphones***. A typical circuit diagram for such a simple receiver is given in *Figure C.33*. Receivers of this type were commonly used in the 1920s, before ***electron tubes*** were available, for the reception of broadcast programmes. They required no batteries or mains supply, the AF output depending on the magnitude of the signal picked up by the receiving antenna. A high outdoor ***antenna*** was therefore desirable for good results. (2) A ***waveguide*** incorporating a ***crystal diode*** and used for the detection of received radio signals.



Figure C.33 Circuit diagram of crystal receiver of the 1920s

crystal set Same as ***crystal receiver*** (1).

crystal triode Early name for ***transistor***.

cumulative grid detector Same as ***grid-leak detector***.

current A unidirectional movement of ***charge carriers***. In a conductor the current is a drift of ***electrons*** towards the positive pole of the applied electric field. In a semiconductor, in addition to the electrons moving to the positive pole, current is also carried by ***holes*** moving in the opposite direction. In vacuum electron tubes current is again carried by electrons attracted to the anode: such currents are sometimes called *convection currents*. In a gas-filled tube ***ionisation*** causes the medium to divide into positive and negative ***ions*** which move towards the cathode and anode respectively. A similar process occurs in electrolytes as a result of ***dissociation***. There is, however, no division into charged particles in the ***displacement current***, a hypothetical concept introduced to explain the passage of ***alternating current*** through the dielectric of a capacitor.

current amplification factor Of a ***bipolar transistor*** the ratio of a small change in output current to the change in input current which gives rise to it. In a ***common-base circuit*** the current amplification factor relates changes in collector current with changes in emitter current: this is represented by α or h_{fb} and is necessarily less than unity. In a ***common-emitter circuit*** the current amplification factor relates changes in collector current with changes in base current. This is represented by β or h_{fe} and practical values may lie between 10 and 500. α and β are related thus

$$\beta = \frac{\alpha}{1 - \alpha}$$

current amplifier A circuit incorporating one or more ***active devices*** and designed to amplify current waveforms. The term distinguishes such amplifiers from those designed to amplify voltage waveforms or to deliver power to a load. It is the ratio of source ***impedance*** to input impedance and of output impedance to load impedance which determines whether a device or amplifier is best regarded as a current amplifier, ***voltage amplifier*** or ***power amplifier***. If both ratios are large compared with unity the signal transferred from source to input and output to load is best regarded as a current waveform. The associated signal voltage waveform in a current amplifier is of minor interest and is usually of small amplitude. Because bipolar transistors have a low input impedance and a high output impedance they are usually regarded as current amplifiers.

current dumping An amplifying technique in which a ***class-A stage*** feeds the output load at low signal levels, a ***class-B stage*** taking over progressively as signal level increases, an overall negative feedback system ensuring linearity. The class-B stage is regarded as a current dumper.

current feedback A ***negative feedback*** system in which the feedback signal is directly proportional to the current in the load. The feedback signal may be derived from a ***resistor*** in series with the load as shown in *Figure C.34*, the resistor being small compared with the value of the load. A simple way of applying current feedback to an ***active device*** is to omit the decoupling capacitor which is normally connected across the cathode or emitter bias resistor. The effect of current feedback is to improve linearity, decrease ***gain*** and to increase the effective output resistance of the active device



Figure C.34 Basic principle of current feedback

driving the load, i.e. it tends to make this device a constant-current source. See ***voltage feedback***.

current mirror A circuit arrangement in which a current in one of a pair of matched active devices causes an equal current in the other. In the basic form of the circuit shown in *Figure C.35* the current I_{c1} in TR_1 is determined chiefly by the supply voltage and the value of R_1. This sets up a particular value of base-emitter voltage in TR_1 (dependent on the type of transistor and its temperature) which is directly communicated to the matching transistor TR_2 causing an equal collector current I_{c2} in R_2. If TR_2 is replaced by a number of transistors in parallel their total collector current is equal to I_{c1}. This technique is used in integrated circuits to adjust and stabilise the currents in the individual transistors.



Figure C.35 Basic current-mirror circuit

current mode logic (CML) A form of logic giving high switching speed and good immunity from noise, particularly from disturbances on the supply line. It employs ***bipolar transistors*** arranged in balanced pairs and fed with complementary input signals. The supply to each pair is via a series transistor arranged to maintain a constant current.

cursor The symbol, often a flashing character-sized block, that shows where on a VDU the next character to be typed will appear.



Figure C.36 Response curve for a low-pass filter

cut-off attenuator A length of ***waveguide*** used at a frequency below its ***cut-off frequency*** to introduce non-dissipative attenuation which can be controlled by adjusting the length of the waveguide.

cut-off frequency (1) Of a filter the upper or lower limit of a passband. Outside the passband the attenuation should ideally increase rapidly and the cut-off frequency is sometimes defined as the frequency at which the attenuation is 3 dB as shown for a lowpass filter in *Figure C.36*. (2) Of a ***waveguide*** for a given mode of transmission the frequency below which transmission of RF signals along the guide is not possible. The cut-off frequency depends on the mode and on the cross-sectional dimensions of the waveguide.

cycle An interval of space or time in which a periodically varying quantity completes one set of changes of the variable. For a ***sinusoid*** a cycle contains one complete set of positive values followed by an equal set of negative values.

cyclic code Same as ***Gray code***.

cyclic store A ***store*** to which access is available only at fixed intervals during a cycle, e.g. a ***magnetic drum***.

cylinder The position of one track on a ***floppy*** or ***hard disk***. The term originates from its use on hard drives consisting of a number of disks on a common spindle. Each disk contains two tracks at that position, one on each side. Consequently that position, repeated for each disk on the spindle, could be considered as constituting a hypothetical cylinder. A cylinder-shaped symbol, as shown in *Figure C.37*, is widely used in the computer industry to represent ***mass storage***.



Figure C.37 The cylinder symbol used widely in the computer industry to represent mass storage

D

D-type connector A standard for nine-, 15- and 25-pin connectors that support RS-232-C, RS-432 and RS-422 communications. The connector is so named because of its shape.

daisy chaining A method of linking ***peripheral*** devices in series so that only one communications ***port*** is used on the host computer. A ***SCSI*** port, for example, can support up to seven daisy-chained devices, signals being passed from device to device until they reach their destination. See ***Small Computer Systems Interface (SCSI)***.

daisy wheel ***See printer.***

damping That property of an electrical, mechanical or acoustical resonant circuit which causes a progressive fall in the amplitude of free ***oscillations***. Damping is caused by resistance in electrical circuits and by friction and viscosity in mechanical systems. In electronic circuitry resonant circuits are often deliberately damped to increase the ***bandwidth*** by the addition of ***resistance***.

damping coefficient (or **factor**) (1) A measure of the rate of decrease of ***amplitude*** in a damped ***oscillation***. It is equal to the ratio of one amplitude to the next in the same direction. It is also equal to the ***logarithmic decrement*** divided by the periodic time of the oscillation. In an electrical resonant circuit the damping coefficient is related to the circuit constants, being given by $R/2L$ where R is the series resistance in the circuit and L is the inductance. (2) Of an AF ***power amplifier*** the ratio of the load resistance to the output resistance of the amplifier.

dark current The current which flows in a ***photocell***, ***photo-transistor*** or TV ***camera tube*** when there is no light incident on the photo-sensitive surface. Ideally this current should be zero but in practice there is usually a finite current.

dark-trace tube A ***cathode ray tube*** with a screen composed of potassium chloride which darkens when struck by the electron beam. It is used in ***radars***.

Darlington pair An amplifier stage using two ***bipolar transistors*** in which the base of the second transistor is directly connected to the emitter of the



Figure D.1 A Darlington pair

first, the two collectors being commoned as shown in *Figure D.1*. The combination can be regarded as a single transistor with a gain equal to the product of the gains of the individual transistors.

data In electronics and computing, a ***signal***, often in ***digital*** format, that relates to something in the outside world. The information technology revolution that has blossomed since the early 1980s has been based on the fact that electronic equipment can perform all manner of useful operations on data that represent entities in the real world, quickly and accurately. The word *data* is, strictly speaking, a plural noun, the singular being *datum*, from the Latin for 'a given thing'.

databank Same as ***database***.

database A computer application that sorts, stores and retrieves data, sometimes in very large quantities. For example, a doctor might use a database to store the personal details and medical histories of thousands of patients. A bank might use a database to store details of the accounts of millions of customers. For retrieval data may be selected using combinations of specific factors. The doctor could request a list of all his female patients between certain age limits who are due for a certain medical check-up. The bank could retrieve details of all its customers in a certain region whose accounts exceed a certain sum. The information retrieved could be fed into a ***mailmerge*** application for incorporation into a special mailing to each person selected.

data compression See ***compression***.

data dictionary See ***repository***.

data processing equipment Automatic machines which carry out operations on items of data in order to obtain wanted information. The operations may include sorting, arranging, relating and interpreting the data, and the carrying out of calculations, and is generally achieved today by a ***digital computer***.

data transmission The automatic transfer of data between two points, usually a computer and a data terminal or between two computers. The transfer is usually by a telegraph, telephone or radio link.

data warehouse A computer application that provides access to data in several different ***databases*** in an integrated manner.

D bistable A ***bistable*** circuit with an input (*D*), the logic state of which is faithfully copied at the output on the application of a clock pulse to a separate input. However the output can be forced to logic 1 or 0 by the clear and reset inputs. The graphical symbol for a D bistable is given in *Figure D.2*.



Figure D.2 Logic symbol for a D bistable

DC amplifier An amplifier using direct coupling between stages and thus capable of amplifying a direct current or a signal with a very slow rate of variation.

DC component The mean value of a ***signal***. A signal which has equal areas above and below the time axis, such as one composed solely of sine waves, has a mean value of zero, i.e. has no DC component. An asymmetrical signal has a mean value and this is one of the components (the zero-frequency component) of a complex signal obtained on ***Fourier analysis*** of the signal.

DC coupling Inter-stage coupling via a path which permits DC (***zero-frequency***) signals to be transferred from the output of one stage to the input of the next. The coupling may simply be a physical connection between the output and input electrodes of the ***active devices*** or may consist of a resistive ***potential divider***.

DC restoration A technique for re-inserting the ***zero-frequency*** or low-frequency components of a ***waveform*** after these have been lost or attenuated, e.g. as a result of passing the signal through capacitance-coupled circuits. A repetitive feature is necessary in the waveform such as the negative-going sync signals in television and a diode can then be used to effect restoration as indicated in *Figure D.3*.



Figure D.3 DC restoration of a television waveform by a simple diode circuit

DC stabilisation Of the operating point of an active device the process of ensuring that the mean current through the device is substantially unaffected by variations in the characteristics of the device such as may occur with changes in temperature or when the device is replaced by another of the same type. Stabilisation is necessary particularly when equipment is mass-produced to ensure that the device can always give the planned performance and to prevent ***thermal runaway***.

A typical circuit for DC stabilisation of a ***bipolar transistor*** circuit is given in *Figure D.4*. The potential divider R_1R_2 stabilises the base voltage of the transistor and hence the emitter voltage; the resistor R_3 then determines the mean current through the device.



Figure D.4 Circuit often used for DC stabilisation of the operating point of a bipolar transistor

dead room Same as ***anechoic chamber***.

debug (US) To detect errors or faults (bugs) in a procedure or an equipment and to correct them.

decade In electrical circuit theory the interval between two frequencies with a ratio of 10:1.

decade box An item of test equipment which enables a specific value of ***resistance***, ***capacitance*** or ***inductance*** to be introduced into a circuit. The box has a number of sections, each with ten switched positions, each section having ten times the value of the previous section. Thus any value of resistance, capacitance or inductance within the range of the box can be set up.

decay coefficient (or **factor**) Same as ***damping coefficient*** (or ***factor***).

decay time (1) Of a charge storage tube the time taken for the stored information to fall to a stated fraction of its original value. (2) Of a ***pulse*** same as ***fall time***.

decelerating electrode or **decelerator** An electrode in a ***cathode ray tube*** biased so as to slow down the electron beam. It is usually in the form of a mesh or a short cylinder. Such an electrode is used in low-velocity TV ***camera tubes*** such as the ***image orthicon*** in which the electron beam is required to approach the target at a very low velocity. See ***image orthicon***, ***orthicon***, ***orthogonal scanning***.

decibel One tenth of a ***bel***, the unit used for comparing power levels and voltage levels in electronics and for expressing transmission gains and losses. Two powers P_1 and P_2 are said to differ by n decibels when

$$n = 10 \log_{10}\frac{P_1}{P_2}$$

n being positive when P_1 exceeds P_2 and negative when P_1 is less than P_2. Similarly two voltages V_1 and V_2 are said to differ by n decibels when

$$n = 20 \log_{10}\frac{V_1}{V_2}$$

n being positive when V_1 exceeds V_2 and negative when V_1 is less than V_2.

The decibel is a logarithmic unit and therefore gains and losses expressed in decibels can be added and subtracted arithmetically.

decineper A transmission unit equal to one tenth of a ***neper***.

decoder Any device that converts data from one format to another, especially if the input data is encoded. In logic circuitry a decoder may convert binary coded decimal signals (on four lines) to binary (that is, selecting one of 10 or 16 lines). See ***decoding***.

decoding In general the recovery of the original signal from a coded form of the signal. In particular in ***stereophonic*** radio reception the recovery of the left and right signals from the multiplex received signal and in colour TV reception the recovery of the three primary colour signals from the colour ***video signal***.

decoupling The process of confining signals to the paths where they are required and thus preventing them from entering other areas of a circuit.



Figure D.5 R_1C_1 are collector-decoupling components and C_e is an emitter decoupling capacitor

In multi-stage electronic equipment this is necessary to minimise the ***coupling*** which otherwise might exist between stages by virtue of the finite ***impedance*** of the common power supply, and the usual method of decoupling is by the inclusion of *RC* or *LC* circuits. For example, R_1, C_1 are ***collector***-decoupling components (see *Figure D.5*); the reactance of C_1 is made small compared with R_1 at all operating frequencies and thus the signal-frequency components of the collector current of the transistor are confined to the path which includes R_c, C_1 and C_e and do not enter the power-supply circuits where they could cause ***feedback*** problems, possibly resulting in instability, if the power supply also serves other stages.

C_e provides a low-reactance path for signal-frequency components of the emitter current and thus C_e may be described as a capacitor decoupling R_e.

dedicated Reserved for a special purpose and therefore unavailable for other uses. For example, a fax machine contains a microcomputer which has many of the features of a general-purpose microcomputer, but is dedicated to the communication operations of the fax machine.

de-emphasis The use of a network with a falling high-frequency response to reduce the subjective effect of noise introduced by a transmission system or a record/reproduce system. The upper frequencies are accentuated on recording or at the transmitting end (see ***pre-emphasis***) to ensure an overall level frequency response and the two curves must be complementary. In FM broadcasting the curves are governed by a ***time constant*** of 75 µs.

default In hardware or software, the selection of settings made by the manufacturer. They determine how the system behaves if you choose not to over-ride the settings with others that you prefer.

definition In television in general a statement of the degree of detail in reproduced images. The ability of a TV system to reproduce abrupt changes in tonal value occurring along the scanning lines is known as the horizontal definition, i.e. horizontal definition measures the sharpness of reproduction of vertical edges or lines in the image. Similarly the vertical definition is the ability of the system to reproduce abrupt changes of tonal value occurring along a line at right angles to the scanning lines. The vertical definition measures the sharpness of reproduction of horizontal edges or lines in the image.

deflection sensitivity The linear displacement of the spot on the screen of a ***cathode ray tube*** for a given deflecting field. For ***electrostatic deflection*** it is stated in millimetres for 1 V applied between the deflector plates. Because the deflection sensitivity depends on the final-anode potential of the tube, this must be quoted in any numerical statement of deflection sensitivity.

deflector coils Coils carrying currents to generate the magnetic deflecting field for a ***cathode ray tube***. Two coils are used to give horizontal deflection of the beam and are commonly of rectangular section which are then moulded around the neck of the tube in the form of a saddle. For a TV picture tube or camera tube two further coils are required to give vertical deflection and these are also moulded around the neck overlapping the horizontal deflector coils. All four coils are mounted on an assembly known as a ***yoke***. To concentrate the magnetic field within the ***cathode ray tube*** the yoke is often constructed of magnetic material such as ***ferrite***.

deflector plates In general, electrodes carrying the voltages to generate an electric deflecting field in a ***cathode ray tube***. For horizontal and vertical deflection of the beam in a cathode ray tube the plates are mounted within the neck of the tube, one pair being used for horizontal deflection (*x* direction) of the beam and a second pair for vertical (*y*) deflection. The two sets of plates are arranged in tandem as shown in ***Figure C.7***.

degassing Of an ***electron tube*** the removal of any traces of remanent or occluded gases after the normal evacuation process. These last traces are removed by heating the electrodes by eddy currents induced in them by a coil carrying RF and surrounding the tube whilst pumping proceeds. An extremely good vacuum can be obtained in this way but a ***getter*** is also used to further improve the vacuum.

degaussing Of a colour picture tube the process of minimising residual magnetisation of the structure of the tube and nearby metalwork. This is necessary to avoid possible deflecting effects on the scanning beams which could cause misregistration and colour fringing of reproduced images. Degaussing can be achieved by use of a coil surrounding the face of the tube and which is energised by an alternating current, the amplitude of which is reduced to zero at the beginning of each period of use of the tube.

de-ionisation The return of an ionised gas to the neutral or un-ionised state by recombination of positively- and negatively-charged ***ions*** after the ionising source has been removed.

de-ionisation time Of a ***gas-filled tube***, the time taken for the ***grid*** to regain control after interruption of the anode current. De-ionisation takes a significant time and must be complete before the grid is effective again.

dekatron A cold-cathode gas-filled tube used for ***counting***. It has a central anode and ten cathodes disposed at regular intervals around it with transfer electrodes between the cathodes. In operation a ***glow discharge*** surrounding one cathode is transferred to the next cathode each time a ***pulse*** is applied to the transfer electrodes. After ten pulses the discharge is back at the original cathode and every tenth pulse can be applied to another dekatron thus making a complete counter registering visibly in the decimal system.

delay In general, the time taken for a signal to pass through a system or equipment. In particular for a receiver or amplifier with a step-signal input, it is the time taken for the output signal to reach one half of its final amplitude.

delay distortion or **delay/frequency distortion** Distortion arising from the lack of constancy of the ***phase delay*** of a system over the frequency range required for transmission. To avoid distortion of a complex wave, phase delay should be independent of frequency, i.e. ***phase shift*** should be directly proportional to frequency over the frequency range occupied by the signal. Even small departures from linearity of the phase-frequency curve can cause serious waveform distortion if they occur over a limited frequency range. Thus deficiencies in phase response are better indicated by variations in the slope of the ϕ/ω curve than by variations in the value of ϕ/ω itself. See **group delay, phase distortion.**

delayed automatic gain control An AGC system so designed that it does not come into operation until input signals reach a predetermined (threshold) amplitude. AGC is therefore inoperative for weak signals which therefore receive the full gain of the amplifier or receiver. Such a system does not therefore limit the sensitivity of the receiver.

delay generator An active circuit with a controllable delay between input and output signals. Monostable pulse generators such as ***multivibrators*** can be used as delay generators, the input signal being used to trigger the leading edge of the generated pulse, the trailing edge acting as the output signal. The circuit constants are chosen to give a duration of generated pulse equal to the required value of delay.

delay line or **delay network** A length of transmission line or an ***equivalent network*** of lumped inductance and capacitance designed to introduce a desired value of delay in the transmission of a signal through it. The lumped-constant network is sometimes termed a delay network.

delta-array colour picture tube A shadow-mask picture tube the screen of



Figure D.6 Delta-array colour television tube: basic arrangement of electron gun, shadow mask and screen

which is composed of a very large number of colour cells, each consisting of a dot of red, green and blue phosphor arranged in a delta (triangular) formation as shown in *Figure D.6*. See ***shadow-mask picture tube***.

delta network A network of three branches connected in series to form a closed loop or ***mesh***, the three external ***nodes*** providing the three connections to the network as shown in *Figure D.7*. A three-phase circuit may be delta connected. A delta network is the same as a π network. See ***branch***, ***star connection***, ***star-delta transformation***.



Figure D.7 Three circuit elements connected in delta formation

demagnetisation The reduction of the ***magnetic flux density*** to zero by taking the material through ***hysteresis loops*** of gradually-diminishing amplitude.

demodulation The process of abstracting from a modulated wave a replica of the original modulating signal. It is the converse of ***modulation***.

de Morgan's theorem In ***Boolean algebra*** a principle of duality which states that the values 0 and 1 may be interchanged with AND and OR operations.

demountable Designed to be easily removed from its host equipment. For example, a demountable ***hard disk*** can be easily removed from one computer and installed in another having a suitable drive. This contrasts with conventional hard disks which are permanently installed.

depletion layer A region in a ***semiconductor*** material which is free of charge carriers. Such a region occurs in a reverse-biased pn junction, the charge carriers being attracted towards the terminals by the positive or negative charge due to the applied EMF. The depletion layer bounded by the conductive zones of the massed ***charge carriers*** resembles the structure of a charged capacitor and in fact this capacitance is made use of in ***variable-capacitance diodes***.

depletion mode A mode of operation of a ***field-effect transistor*** which is designed to take a considerable drain current at zero gate bias, a reverse bias being necessary to reduce the current to a normal working value.

depolarisation Of a ***primary cell*** the removal of the gas which collects on the electrodes during discharge and limits the maximum current that may be drawn from it. In the ***Leclanché cell***, for example, manganese dioxide is used as a depolarising agent, being packed around the carbon (positive) electrode to oxidise to water the hydrogen liberated from this electrode during discharge of the cell.

derivative equaliser An ***equaliser*** which operates by adding to the signal to be equalised controllable amounts of the time derivatives of the signal. Such equalisers are used in TV transmission for correcting waveform distortion in video circuits and normally only the first and second derivatives are used.

desktop In computing, the operating environment of a *GUI*. Effectively it is the layout of the *VDU* display when no applications are active and includes the built-in utilities such as a calculator, calendar/clock, text editor and file management system.

desktop computer A self-contained microcomputer which is small enough to be used on a desktop. See also ***laptop computer*** and ***personal computer***.

Desktop Publishing (DTP) A computer application which allows the user to create and edit on screen any type of ***document*** from a simple letter to a full-colour illustrated magazine. Through the use of ***outline fonts*** DTP allows a virtually unlimited range of typefaces, type styles and type sizes in almost any preferred page layout. Documents can also include ***bitmap graphics***, such as ***scanned*** photographs, and ***vector graphics*** such as line drawings, schematics and maps. DTP is strictly *WYSIWYG* ('what you see is what you get') in that the screen display accurately reflects the appearance of the printed document. A *GUI* is a prerequisite of serious DTP applications. The finished document may be printed on a desktop ***printer*** such as a laser printer or the output may be in the form of a ***PostScript*** file which can be read by professional photo-typesetting equipment. Many publications are now prepared using DTP in this way.

destructive reading A ***reading*** process which also erases the data.

detection The process of abstracting information from a ***carrier wave***. In the AM signal detector of a radio receiver the information abstracted is that of the original modulating signal (see ***demodulation***) but an AGC detector abstracts an output proportional to the unmodulated carrier amplitude. There are many different types of detector. See ***anode-bend detector***, ***grid-leak detector***, ***infinite-impedance detector***, ***ratio detector***.

deviation Same as ***frequency deviation***.

deviation ratio In ***frequency modulation*** the ratio of the ***rated frequency deviation*** to the maximum value of the modulating frequency. In FM broadcasting the rated frequency deviation is ±75 kHz and the upper AF limit is 15 kHz giving a deviation ratio of 5.

diamagnetism A property of certain materials subjected to a magnetising field which causes induced magnetisation which opposes the applied field. Such materials are repelled by a magnetic pole and have an effective permeability of less than unity. This effect is typical of elements with an atomic structure containing completed electron shells such as bismuth. See ***ferromagnetism***, ***paramagnetism***.

diaphragm (1) In an electrolytic cell, a porous membrane which separates two electrolytes but permits the passage of ***ions*** between them. (2) In a ***microphone*** a thin resiliently-mounted metal disk or ribbon which vibrates when exposed to sound waves and communicates its motion to the ***transducer*** of the microphone. (3) In a ***loudspeaker*** a thin resiliently-mounted paper structure, usually in the shape of a shallow cone, which radiates sound waves when driven by the ***transducer***. The diaphragm needs to be fairly large, particularly for radiation at low audio frequencies, but there are now ingenious designs of small cabinet loudspeakers which give good bass response.

dichroic mirror A form of optical filter which transmits part of the light spectrum and reflects the remainder. It consists essentially of a plain sheet of optically-flat glass on one face of which a structure of very thin alternate layers of high and low refractive index are deposited by vacuum evaporation. It relies on interference for its operation. Such filters are used in colour TV cameras to split the light from the optical image input into its red, green and blue components. One arrangement which can be used for this purpose is illustrated in *Figure D.8*.



Figure D.8 Simplified diagram showing the use of dichroic mirrors in a colour television camera

dielectric An insulator in which an electric ***field*** persists after the inducing field has been removed. When an insulator is subjected to an electric field there is a redistribution of electric charges within it, the molecules becoming polarised and aligning themselves in the direction of the field. Dielectrics are used as the medium separating the plates of a ***capacitor***.

dielectric constant Same as ***permittivity***.

dielectric dispersion The variation with frequency of the dielectric constant (***permittivity***) of a material.

dielectric hysteresis That property of a ***dielectric*** which causes the electric flux density to be dependent on the previous state of the material in addition to the present value of the electric field strength. For example a dielectric takes a finite time to recover from the effects of an electric strain.

dielectric loss The energy dissipated as heat in an insulator subjected to a varying electric field. In an ideal insulator there is no dielectric loss but in practice changes in the polarisation of the molecules generate some heat.

dielectric strength The ability of an insulator to withstand electric stress without breakdown. Quantitatively it is the ***voltage gradient*** (in volts per centimetre) at which breakdown occurs under standardised conditions.

difference signal In stereo broadcasting the signal formed by subtracting the B signal (in the right channel) from the A signal (in the left channel). In the pilot-tone system of transmission this difference signal is used to modulate the subcarrier. See ***pilot-tone stereo, stereophonic system.***

differential amplifier A ***DC amplifier*** with two independent inputs and one output, the output signal being proportional to the difference between the two input signals. There is hence no output if the two input signals are equal. ***Long-tailed pairs*** are often used in differential amplifiers.

differential electrode resistance Same as ***electrode AC resistance.***

differential gain In a video transmission system the difference in the gain of a small high-frequency signal at two stated levels of a low-frequency signal on which it is superposed. In colour TV the colour subcarrier is used as the high-frequency test signal. Differential gain may be expressed as a percentage or in ***decibels.***

differential permeability Of a material the ***permeability*** as measured by the slope of the curve of ***flux density*** plotted against magnetising force. This value of permeability applies to very small excursions in magnetising force about a steady value and it varies over a wide range depending on the steady value of magnetising force. See ***magnetic field strength.***

differential phase In a video transmission system the difference in phase of the output of a small high-frequency signal at two stated levels of a low-frequency signal on which it is superposed. In colour TV the colour ***subcarrier*** is used as the high-frequency test signal.

differential resistance Of a ***diode*** the ratio of a small change in the voltage drop across the diode to the associated small change in forward current.

differentiating circuit A circuit the output of which is approximately proportional to the rate of change of the input signal. A common example is a circuit comprising a series capacitor followed by a shunt resistor, often used to select the leading or trailing edges of a pulse as shown in *Figure D.9*. The time constant RC must be small compared with the period of the pulses.



Figure D.9 (a) A simple differentiating circuit (b) Input and output waveforms

diffraction The bending of the path of an ***electron beam*** or an ***electromagnetic wave*** when it passes the edge of an obstacle.

diffusion In semiconductor-device manufacture, a technique by which a required amount of an impurity can be introduced into a ***semiconductor*** by exposing it to the vapour of the impurity in a furnace. The depth of penetration of the impurity can be controlled by the duration of the exposure and the graded impurity concentration which results is often helpful in transistor performance. See ***graded-base transistor***.

digital audio broadcasting (DAB) A broadcasting system in which a number of digitally-coded audio signals are used to modulate a closely spaced multiplicity (a *comb*) of carriers. The system was developed by a consortium of European Broadcasting Authorities to overcome the drop-outs and *multipath distortion* experienced in conventional FM reception on mobile and portable receivers. DAB transmissions can be from terrestrial or satellite stations.

The system uses approximately 1500 carriers spaced at 1-kHz intervals in Band III (217.5–230 MHz). The audio signals are digitised and the bit rate is reduced to about one sixth of that used on compact disks by a technique which makes use of the fact that a quiet sound is masked by a loud one and therefore need not be broadcast. The signals so processed are then interleaved in time and the total bit rate is spread over the comb of carriers in a precisely controlled manner. Thus the interval between successive bits on any particular carrier is greatly increased. The comparatively small time delays caused by reflected signals are of no account and are absorbed in a guard period inserted between transmitted bits. The advantage of using a large number of carriers is that heavy interference on individual carriers does not interrupt or affect reception.

digital audio tape (DAT) A standard for the digital recording of audio on cassette tape. Theoretically this results in a high-quality recording, free from background noise and distortion, as on ***compact disc***. DAT is also sometimes used in computing for making ***backups*** of ***hard disks***.

digital computer Equipment for performing calculations and/or logical operations on input data in digital form under the control of a stored program.

Computers play an important role in science and engineering where use is made of the high speed at which they can perform complex calculations. They are extensively used in industry and commerce where their ability to store and process large quantities of information is valuable. They also control and monitor industrial processes. The graphics displays which computers can give are invaluable in design work (CAD) and in providing information and entertainment in the home and in education. Finally mention must be made of the important role played by computers in manufacture (CAM).

The principles of the modern computer can be traced to the work of Babbage who started work on a mechanical machine in 1822. The development of the electronic computer is deemed to have occurred in four distinct steps termed generations as follows:

(a) First generation. The first electronic computer, constructed immediately after the Second World War, employed 18000 electronic tubes as switching elements and used delay lines for storage. It was very large, occupying several rooms and consumed vast quantities of power. Input and output were by teleprinter and punched cards.

(b) Second generation. These computers, developed during the 1950s, used discrete transistors as switching elements and storage was by magnetic cores, drums and tapes. Line printers were used for output. These machines were much smaller and more reliable than the first generation but were still very large compared with modern computers. For the first time a programming language was used.

(c) Third generation. Integrated circuits were used in these computers giving greatly reduced size, higher operating speeds and improved reliability. There were enormous increases in storage capacity. Languages such as FORTRAN, COBOL and BASIC were in common use. The individual minicomputer operated by a few or even one man gained favour over the large centrally-managed machine.

(d) Fourth generation. Large-scale integration has permitted yet further reductions in size and complete processors can now be formed on a single monolithic integrated circuit known as a ***microprocessor***. Semiconductor storage has virtually replaced core stores so making possible the microcomputer.



Figure D.10 Essential features of a digital computer

All computers have the five basic sections shown in *Figure D.10*. The main store consists chiefly of random-access memory (RAM) but there is also some read-only memory. The RAM section is used for holding the current program and transient data being processed by the program. The ROM section may hold only the routines used at start-up, but in some machines also holds the ***operating system*** which contains frequently-used routines that do not require alteration. The capacity of the main store is sometimes inadequate and the permanent store (such as a hard disk) may be used to hold additional data which can be transferred to the main store if and when required. The permanent store also stores programs and data between operating sessions.

The arithmetic and logic unit performs such operations as addition, subtraction, left and right shifts, AND, OR and NOT.

The control unit determines which command in the program is next executed. Usually commands are executed sequentially, but sometimes instructions require a jump to some other section of the program or to a routine in the operating system.

The input device is a means of feeding data into the computer in the digital form which it can accept: this could be a punched-card reader, a keyboard or a mouse.

The output device displays the final result of the program in an intelligible form: this could be a printer or a VDU.

There is a vast range of different types of computer but all belong in one of the following categories:

A microcomputer consists of a microprocessor, main and permanent storage facilities, a keyboard and a visual display unit or, occasionally, circuitry for displaying output on the screen of a domestic television receiver. Usually a BASIC interpreter is included in permanent storage, or even in ROM, allowing users to program the machine in an easily learned programming language.

The minicomputers and midicomputers at one time extensively used in offices, laboratories and industry were multi-user machines having several terminals served in rotation. They have now been largely replaced by networks of microcomputers which offer greater computing power, speed and versatility.

Mainframe computers are used by large organisations such as national banks and public utilities for processing vast quantities of data, such as millions of accounts. Usually they support a large number of time-sharing users. The central processing unit is usually situated in a room with a temperature- and humidity-controlled environment.

digital signal In general a signal of which the significant property can have only a limited number of discrete values. The term is widely used in binary transmission where there are only two discrete values. The signal can then take the form of the presence or absence of a voltage, the closing or opening of a contact, the presence or absence of a hole in a punched card, etc. See ***analogue signal.***

digital-to-analogue converter (DAC) Circuitry for converting a ***digital signal*** to analogue form.

digitise (US) Same as ***analogue-to-digital conversion.***

diode See ***diode electron tube, junction diode, point-contact diode.***

diode detector An AM detector which makes use of the unidirectional conductivity of a diode. Two typical circuit diagrams for diode detectors are given in *Figure D.11*. At (a) the diode is in parallel with the load resistor R_l and at (b) it is in series. Both circuits operate in the same way. On one half-cycle of the carrier-wave input from the tuned circuit *LC* the diode conducts and charges C_l to the peak value of the carrier voltage. During the following half-cycle the diode is reverse-biased and cut off and C_l begins to discharge through the diode load resistor R_l (and L in (a)). However the time constant R_lC_l is such that little of the charge is lost before the charge is restored to peak value again when the diode conducts



Figure D.11 Diode detectors (a) shunt-connected and (h) series-connected

during the next half-cycle. Thus the voltage across C_1 is maintained at the peak value of the carrier input.

When the carrier amplitude varies during modulation, the voltage across C_1 varies correspondingly and is thus a copy of the modulation envelope. The voltage across C_1 is therefore the detector output (in *Figure D.11* (a), *L* has negligible impedance at modulating frequencies).

The time constant R_1C_1 must not be too long otherwise the voltage across C_1 cannot accurately follow downward swings of carrier amplitude. This problem is most acute at high modulating frequencies and at great modulation depths; in fact these factors set an upper limit to the value of time constant which should be equal approximately to the period of the highest modulating frequency.

Figure D.11 (b) represents a sound radio detector and R_2C_2 is an RF ripple filter, C_3 being a blocking capacitor to remove the direct component of the detector output.

diode electron tube An ***electron tube*** with two electrodes, a ***cathode*** and an ***anode***. Such a tube cannot amplify and its significant property is that it can conduct only when the anode is made positive with respect to the cathode. It is therefore used as a rectifier of alternating voltages in power supply units, as a detector of radio signals and as a switching device in analogue and digital equipment. ***Diodes*** often form part of multiple electron tubes, e.g. a double-diode-triode includes two diodes. Typical I_a–V_a characteristics for a diode are given in *Figure D.12* (a) and the graphical symbol for an indirectly-heated diode is given in *Figure D.12* (b). See ***diode detector***.

diode-transistor logic (DTL) A system in which use is made of ***logic elements*** comprising diodes and transistors. See ***logic***, ***logic gate***, ***logic level***.

direct access storage Same as ***random access memory***.



(a) (b)

Figure D.12 I_a–V_a characteristic of a diode (a) and graphical symbol for an indirectly-heated diode (b)

direct component Same as ***DC component.***

direct coupling Same as ***DC coupling.***

direct current (DC or d.c.) A current which flows only in one direction, such as the current drawn from a battery. See also ***alternating current.***

directly-heated cathode Same as ***filament.***

directory In computers and data processing equipment, data is stored in ***files***. Essential information about each file such as its name, type, length, date of creation and physical location in the storage medium is stored in a special file called a *directory*. Besides details of files a directory may contain details of other directories, allowing the organisation of stored files in a logical, hierarchical manner. Each storage medium has a *root directory* in a fixed location; this must be accessed before any data can be read from or written to the medium.

direct voltage A voltage which does not change in polarity, e.g. the voltage available from a battery. Such supplies are used in electronic equipment, e.g. for the ***collectors*** and ***drains*** of transistors. Direct supplies can be obtained from the a.c. mains by using a ***transformer*** to give the required voltage, by ***rectification*** and ***smoothing*** the output.

disassembler A computer program which analyses ***machine code*** and converts it to the mnemonics used in an ***assembler***. Disassemblers are used mainly for diagnostic purposes.

discharge In general the removal of all or some of a stored electric charge. In particular: (1) Of a ***primary*** or ***secondary cell***, the conversion of the chemical energy into electrical energy; (2) Of a ***gas-filled tube*** the passage of an electrical current through the device; (3) Of a charged ***capacitor*** the release of some or all of the stored charge through an external circuit.

discriminator In a frequency- or phase-modulated ***receiver*** the stage in which a voltage (derived from the received signal) is substantially proportional to the deviation of the frequency or the phase from the unmodulated value. There are a number of circuits which can be used for this purpose. See ***Foster-Seeley discriminator***, ***ratio detector***, ***Round-Travis discriminator***.

disk See ***compact disk***, ***floppy disk***, ***floptical disk***, ***hard disk***, ***magneto-optical disk***, ***video disk***.

Disk Operating System (DOS) An ***operating system*** that resides on a ***hard*** or ***floppy disk***, in contrast with one that resides in ***ROM***. Probably the best known is Microsoft DOS (MS-DOS) which is the most commonly used operating system in IBM *PC*-compatible microcomputers.

disk-seal tube An ***electron tube*** made suitable for operation at UHF in which the closely-spaced ***electrodes*** are extended as annular disks which project through the glass envelope to locate with the ends of the coaxial lines used as tuning elements. The fine spacing of the electrodes is necessary to minimise ***transit time*** and so raise the upper frequency limit. *Figure D.13* shows the form of construction used in one type of disk-seal triode.



Figure D.13 Construction of a disk-seal triode

dismount In computing to terminate the use of a ***drive***. This involves closing all open ***files*** and any ***directory*** displays that relate to that drive. There are many possible reasons for dismounting. When an application has been saving data byte by byte on a demountable medium such as ***floppy disk***, the data is written first to a ***buffer*** which is copied to the disk later. If the disk is removed from the drive before the buffer is copied, some of the data is lost. Dismounting forces the completion of such data transfer and therefore ensures an orderly updating and shutdown of open files. See ***mount***.

dispersed dithering See ***dithering***.

dispersion Of any kind of radiation the spreading of a beam according to the value of some property. For example, the spectrum obtained by passing a beam of white light through a prism is caused by dispersion, the beam being deflected in the prism to an extent dependent on frequency.

dispersion gate Same as ***NAND gate***.

displacement current A concept introduced to explain the flow of current through the ***dielectric*** of a ***capacitor*** subjected to a varying voltage. This hypothetical current is equal to the rate of change of the electric flux in the dielectric but there is, of course, no conduction current, i.e. no movement of charge carriers through the dielectric.

display The visual presentation of data in alphanumeric or graphical form or as a drawing, usually on the screen of a cathode ray tube.

dissipation Energy wasted in the resistive component of an electric circuit. The resistance may be that of resistors forming an essential part of the circuit, e.g. the collector load of a transistor. Alternatively the resistance may be incidental, e.g. that of the windings of a transformer. However energy can be dissipated by a circuit even though there is apparently no resistance present, intentional or incidental. A capacitor with poor-quality dielectric or a circuit radiating RF power are two examples. It is common practice to represent the losses in such circuits as due to a resistor which is shown as a discrete component in equivalent circuits. The lost energy is manifested as heat and, for a resistance R carrying a current I, is given by I^2R, V^2/R or VI, where V is the voltage across the resistance.

dissociation The division of a metallic salt into charged ions on solution. Copper sulphate, for example, divides into positively-charged copper ions and negatively-charged sulphate radical ions. If the solution contains electrodes connected to a DC supply, the ions act as ***charge carriers*** and a current passes through the solution. The copper ions move towards and are deposited on the cathode and the sulphate ions migrate to the anode with which they form a new salt which goes into solution. If the electrodes are of copper, the effect of passing a current through the solution is that the cathode increases in size, the anode decreases in size and the concentration of the solution remains constant. If the cathode is of iron, for example, it becomes copper plated when a current is passed and this is the basis of the electroplating process.

distortion (1) Of an electrical signal any unwanted change in the ***waveform***. There are, in general, three causes of waveform distortion:

(a) Variations with frequency of the ***gain*** or ***attenuation*** of the signal path. See ***aperture distortion***, ***attenuation distortion***.

(b) Variation with signal amplitude of the gain or attenuation in the signal path. See ***amplitude distortion***, ***harmonic distortion***, ***intermodulation distortion***, ***non-linear distortion***.

(c) Lack of proportionality between ***phase shift*** and frequency in the signal path. See ***delay distortion***, ***phase distortion***.

(2) Of a displayed image any unwanted change in the tonal ***value***, ***hue*** or ***saturation*** or the introduction of spurious picture details. This can arise, for example, from waveform distortion as detailed under (1) (see ***overshoot***, ***preshoot***, ***ringing***, ***streaking***, ***undershoot***). Distortion can also arise from any errors in the relative positioning of reproduced picture elements arising from shortcomings in the scanning system. See ***barrel distortion***, ***pincushion distortion***, ***trapezium distortion***.

distributed amplifier A wide-band amplifier in which the input ***capacitances*** of a number of ***active devices*** form a ***delay line*** with a number of inductors, the device inputs being excited in sequence by a signal applied to the input of the line. The output capacitances similarly form a delay line with a number of inductors, the output signals from the active devices arriving at the end of the output line in phase.

The advantage of such an amplifier is that its gain can be increased indefinitely by adding more active devices; there is no upper limit to the gain-frequency product as in conventional cascaded amplifiers.

distributed connection In logic circuitry a method of paralleling the outputs of a number of logic elements which gives the effect of an AND or OR operation so avoiding the necessity for including a gate specifically for the purpose. The output terminals of logic elements intended for this form of connection are free transistor ***collectors*** or ***emitters*** destined for connection, with a number of similar elements, to a common external load. The graphical symbols for distributed AND or OR connection are given in *Figure D.14*.



Figure D.14 (a) A distributed AND connection shown with three OR gates and (b) a distributed OR connection shown with three AND gates

distributed constants The inherent ***capacitance*** (***inductance*** or ***resistance***) of an electrical circuit which has a significant length or area, as opposed to the lumped capacitance (inductance or resistance) of a component specifically included in a circuit to provide that property.

For example, a ***transmission line*** has distributed capacitance and inductance and these, in fact, determine the ***characteristic impedance*** of the line.

disturbance See ***interference***.

dithering In computer ***graphics*** the simulation of colours not available in the current ***palette*** using patterns of discrete ***pixels*** in the palette colours. With a careful choice of palette colours (optimising procedures are available) most ***true-colour bitmaps*** can be rendered satisfactorily on the screen in 256-colour video modes. An algorithm known as *Floyd and Steinberg error diffusion* allows the overall colour content of areas of an image to be matched with very high accuracy. In *VGA* and higher-resolution displays dithering with discrete pixels (known as *dispersed dithering*) is not obvious and a casual observer might imagine that he was viewing a true-colour display. Such dithered bitmaps, however, are not amenable to many ***image processing*** operations (such as sharpening) and they may also yield unsatisfactory printouts on some colour ***printers***.

Colour printers also use dithering to simulate most colours since they can only print in eight colours (the ink colours cyan, magenta, yellow and black; the three colours obtained by overprinting pairs of inks: red, green and blue; and the option of leaving the paper, assumed to be white, unprinted). Colour printers may use *clustered* dithering which organises the output into clusters of, say, 36 pixels which may be in any combination of the eight printable colours. This offers a wide range of simulated colours, but reduces the effective resolution of the printout (to 60 'lines per inch' in a 360 dots-per-inch printer). Some high-resolution colour printers, however, use dispersed dithers with Floyd and Steinberg error diffusion, resulting in sharp printouts sometimes described as 'near photographic quality'.

diversity Method of radio reception in which the effects of fading are minimised by combining or selecting from two or more signals carrying the same programme, the signals being obtained via receivers from (*a*) spaced ***antennas***, (*b*) differently-polarised antennas or (*c*) channels on different frequencies. A common technique is to common the AGC lines of the receivers so that weak signals are suppressed and only the strongest is received.

dividing network In multi-unit ***loudspeakers*** a frequency-selective network which divides the frequency range to be radiated into two or more adjacent bands each of which is fed to the appropriate unit.

document A term often used in computing to describe the set of data being processed, whether or not it is destined to be printed and therefore to form a conventional paper document.



Figure D.15 Block diagram of Doherty circuit

Doherty amplifier A linear amplitude-modulated RF amplifying circuit giving high efficiency and used in sound transmitters. It consists of a carrier tube and a peaking tube with inputs and outputs coupled by quarter-wave ***networks*** as shown in *Figure D.15*. Matching and operating conditions are so adjusted that for inputs up to half the maximum the carrier tube delivers power to the ***antenna***, the peaking tube being inoperative. For these low inputs the load presented to the carrier tube is twice the optimum. For inputs exceeding half the maximum the peaking tube comes progressively into operation, so reducing the carrier-tube load to the optimum value, at peak modulation the two tubes contributing equally to the output.

Dolby system A system for improving the ***signal-to-noise ratio*** of audio recordings. The system is based on the principle of compressing the signal before recording and using complementary expansion on reproduction but the audio spectrum is divided into four bands each with its own compressor and expander. Complementary operation is ensured by using the same non-linear ***network*** for compression and expansion, its output being added to the direct signal before recording and subtracted on reproduction.

The system is capable of excellent results and has had wide acceptance in professional sound recording. It is, however, too complex for general use with domestic tape recorders and for these simpler systems have been designed. These are single-band systems intended chiefly to minimise the effects of tape hiss.

domain In a magnetic material a microscopic region regarded as an elementary magnet. When the material is unmagnetised the directions of the ***magnetisation*** of the domains are randomly distributed so that their effects cancel. When a magnetising force is applied the domains rearrange themselves so that their magnetic axes align with the applied field.

dongle See ***hardware key***.

donor impurity In ***semiconductor*** technology a pentavalent element such as arsenic, atoms of which can replace the tetravalent atoms in the lattice of a germanium or silicon crystal so making ***electrons*** available as ***charge carriers***. See ***n-type semiconductor***.

dopant The impurity used for ***doping***.

doping The addition of an impurity to a ***semiconductor*** material to obtain a particular value of p-type or n-type conductivity. Only a very small addition is needed to produce material suitable for use in the manufacture of semiconductor devices. An impurity content of 1 part in 10^8 increases the conductivity of pure germanium and silicon sixteen times and impurity concentrations of a few parts in 10^8 are common in semiconductor-device manufacture. The initial semiconductor material must hence be very pure indeed and the purification of germanium and silicon is one of the most difficult processes in the manufacture of semiconductor devices. See ***n-type semiconductor***, ***p-type semiconductor***.

Doppler effect The apparent change in frequency of a sound or radio wave when there is relative motion between the source and the observer. The frequency increases as the source approaches the observer and decreases as it recedes from him. The effect is used in radio navigation aids, in intruder alarms and various speed measuring instruments.

dot Same as ***picture element***.

dot-matrix printer See ***printer***.

dot pitch A measure of the resolution of a ***monitor*** screen. It indicates the size of the phosphor dots that make up the display. The smaller these are, the sharper the image.

dot-sequential colour television system A system in which signals from the primary colour sources (e.g. the three tubes of a colour camera) are transmitted in sequence so rapidly that each signal persists for only the duration of scanning one picture element. Thus neighbouring elements are reproduced in different primary colours but the elements are so small and so closely spaced that at normal viewing distances the eye cannot resolve them and sees the colour formed by the addition of the primary components.

double-base diode Same as ***unijunction transistor.***

double-heam oscilloscope An oscilloscope in which the ***electron beam*** of the ***cathode ray tube*** is split into two parts which can be deflected independently to permit two different traces to be simultaneously displayed on the ***screen***. This facility is useful, for example, for indicating the phase relationship between two signals or for comparing the input and output waveforms of an amplifier. See ***oscilloscope.***

double-diffused metal-oxide-semiconductor transistor (DMOS) An enhancement ***planar insulated-gate field-effect transistor*** in which successive diffusions by opposite types of impurity through the same opening in the silicon dioxide layer is used to produce a very short channel, the length of which can be closely controlled by the diffusion process. A simplified diagram showing the structure of a double-diffused transistor is given in *Figure D.16*. It has a very small p-region and the channel formed on the upper part of this region under the gate contact is much shorter than in earlier types of insulated-gate transistor.



Figure D.16 Simplified structure of DMOS transistor

In *Figure 1.7*, for example, the channel occupies all the lateral distance between the two n-regions. The channel length determines the drain-source resistance in the on-condition and the speed with which the drain current can be switched on and off, and to achieve low resistance and high speed a short channel is needed. Current flow in the double-diffused transistor is lateral as in earlier field-effect transistors but in other short-channel transistors such as ***TMOS*** and ***VMOS*** current flows through the thickness of the wafer as in planar bipolar transistors.

double-sideband transmission (DSB) A system of amplitude modulation in which both ***sidebands*** are fully transmitted. This is the system used in sound broadcasting on the long, medium and short ***wavebands***.

double superheterodyne reception A method of reception in which two intermediate frequencies are employed, a high one to minimise second channel interference and a low one to give high adjacent-channel selectivity. See ***superheterodyne receiver.***

download To receive data from another computer or other data source.

downtime The period for which equipment is out of action as a result of faults. For equipment providing a public service such as broadcast transmitters downtime must be as low as possible and such equipment is designed to permit very rapid diagnosis of faults and speedy remedy.

downward modulation (US) Same as ***negative modulation.***

Dow oscillator Same as ***electron-coupled oscillator.***

drain In a ***field-effect transistor*** the connection to the ***channel*** which ***majority carriers*** enter on leaving the channel. It corresponds with the collector in ***bipolar transistors*** and the anode in ***electron tubes.***

drain AC resistance See ***electrode AC resistance.***

drawing software Software for creating or editing ***vector graphics*** images.

drift space In a velocity-modulated tube the region between the buncher and the ***catcher*** which is free from alternating fields and in which the velocity-modulated beam gathers into bunches. See ***Applegate diagram, bunching, velocity modulation.***

drift transistor Same as ***graded-base transistor.***

drive (1) In general the input signal for an ***active device*** or equipment. In particular the source of carrier signal for a transmitter. (2) In computing usually used of the mechanical receptacle for a ***storage*** device such as a ***floppy disk drive***, a ***hard disk drive***, a ***tape streamer drive*** or a ***CD-ROM drive***. All of these are electromechanical devices in which a motor physically drives the storage media past the read/write head, but the term is also used in media which are purely electronic. RAMdisks are sometimes called RAMdrives and ***PCMCIA*** card interfaces are also called drives although there are no moving parts to 'drive' mechanically.

driver In computing, software that controls a ***peripheral***, such as a printer or a ***scanner***, and that converts the data being sent to it or received from it into the required format. A driver usually provides control functions such as choice of resolution in a printer or scanner driver.

driver stage Stage providing the input signal for the following stage, usually the output stage of an amplifier or transmitter.

driving-point impedance At any pair of terminals in a ***network*** or point on a transmission line the ratio of the applied voltage to the resulting input current. It is usually measured with all other pairs of terminals correctly terminated. The concept is useful in the design of ***feeders*** to ***antennas.***

drop-out In a tape recording system momentary loss of output signal on replay caused by a temporary loss of contact between the recording head and the magnetic coating of the tape or of the replay head and tape. Drop-outs are also caused by imperfections in the magnetic coating or by excessive wear removing the magnetic coating from the tape. In radio reception, loss of signal caused when waves reaching the receiving antenna via two or more paths are out of phase causing a net cancellation. See ***multipath distortion.***

dry joint An imperfectly soldered joint in which the solder does not adhere properly to the metals to be joined. Such a joint is weak mechanically and may come apart. It can also have a high electrical resistance.

dry reed Same as ***reed relay.***

dual-in-line (DIL) A concept for the standardisation of the arrangement and spacing of the connections to components intended for mounting on ***printed-wiring boards.*** It requires two rows of pins at 0.1-inch spacing. See ***dual-in-line package.***

dual-in-line package (DIP) A plastic or ceramic container for a ***monolithic integrated circuit***, the connections to which are brought out in a DIL format.

As the complexity of ICs has increased, the number of pins required on the DIP has risen to 64 (32 each side). At the standard spacing of 0.1 inch such an IC requires a package over 3 inches long. These considerations have led to the introduction of chip carriers which are much smaller.

dumb terminal A purpose-designed computer ***terminal*** having only limited data processing and storage capability and therefore not able to run any other applications or serve any other purpose. It is therefore a slave to the ***host*** computer which offers full data storage and processing functions. In contrast, an ***intelligent terminal*** offers some local data processing capability.

dummy antenna A network of ***resistance*** and ***reactance*** used to simulate the impedance of an ***antenna***. For transmitter testing the dummy antenna must, in addition to simulating the antenna impedance, be capable of safely dissipating the maximum power output of the transmitter but must not radiate.

For receiver alignment a dummy antenna is connected between the ***signal generator*** and the antenna input terminals of the receiver. A dummy antenna for this purpose need not, of course, be capable of dissipating great power.

dummy load Same as ***artifical load.***

duplex operation A method of operation in which communication between two stations can take place in both directions simultaneously. In a radio system, for example, a receiver at A can receive signals transmitted from B on a carrier frequency f_1 at the same time as a receiver at B is picking up signals radiated from A on a carrier frequency f_2. See ***simplex operation***.

duty cycle Of a system in which there are regular variations in load or in switching, one complete cycle of variations.

duty factor or **duty ratio** Of a regular pulse ***waveform*** the ratio of the pulse duration to the pulse period. Thus for a square wave the duty ratio is 0.5. Duty ratio may also be defined as the ratio of the average pulse power to the peak pulse power.

dynamic characteristics Of an ***active device***, characteristics representing the relationship between electrode current and voltage under specified operating conditions, in particular with a given load. For example a ***resistor*** included in the anode circuit of a ***triode*** causes the anode voltage to fall as anode current increases. The dynamic I_a–V_g characteristic thus crosses the static characteristics for a number of different anode voltages as shown in *Figure D.17*. A significant point is that the slope of the dynamic characteristic is less than that of the static characteristics. For a ***pentode*** the anode voltage has little effect on the anode current and thus the dynamic characteristics are coincident with the static characteristics.

For transistors (bipolar and field-effect) the output voltage also has little effect on the output current. This is shown by the near-horizontal nature of the output characteristic (*Figure B.21*). Thus the dynamic characteristics for transistors differ little from the static characteristics.

dynamic error In a signal varying with time, an error caused by an



Figure D.17 Dynamic and static characteristics of a triode

inadequate high-frequency response. Such errors can arise in ***analogue computers*** from shortcomings in ***transducers***. See ***static error***.

dynamic impedance The ***impedance*** of a parallel *LC* circuit at its resonance frequency. At this frequency the impedance is purely resistive and the term dynamic resistance is often used instead. For a circuit of inductance *L*, capacitance *C* and series resistance *R* the dynamic impedance is given by L/CR, $QL\omega$ or $Q/\omega C$.

dynamic limiter A limiter circuit capable of adjusting its limiting level automatically to compensate for variations in input-signal level. The basic circuit for a dynamic limiter is given in *Figure D.18*. It is assumed that this is fed from an amplifying stage, e.g. the final IF stage in an FM receiver, *LC* being resonant at the intermediate frequency. R_1 is chosen to give heavy damping of *LC* and C_1 is made large so that the time constant R_1C_1 is an appreciable fraction of a second.



Figure D.18 Circuit diagram of a simple dynamic limiter

In operation, C_1 is charged to the peak value of the carrier input from *LC* which is effectively damped by a parallel resistance of $R_2/2$. Now suppose there is a momentary increase in the input to the preceding stage caused, for example, by a spike of noise. This is so fleeting that the voltage across C_1 does not have time to rise to equal it. As a result the diode conducts heavily during this instant and applies very heavy damping across *LC* so reducing the gain of the previous stage and maintaining the voltage across *LC* constant.

If, on the other hand, there is a momentary negative voltage spike in the input to the previous stage, again the voltage across R_1C_1 cannot change quickly enough to register it and this time the diode is cut off for the duration of the spike. *LC* is thus momentarily relieved of the damping due to R_1 and the gain of the previous stage rises, maintaining constant the voltage across *LC*. Thus instantaneous upwards and downwards changes in the input to the previous stage do not affect the voltage across *LC*. The circuit is an effective limiter for upward and downward changes in input amplitude.

If the input to the previous stage alters permanently due to a change in received signal strength then the voltage across R_1C_1 alters slowly to the same extent and the limiting action still applies as before: the circuit is self-adjusting. A dynamic limiter of this type is incorporated in the ***ratio detector***.

dynamic loudspeaker (US) Same as ***moving-coil loudspeaker***.

dynamic microphone (US) Same as ***moving-coil microphone***.

dynamic pickup (US) Same as ***moving-coil pickup***.

dynamic random access memory (DRAM) A ***volatile store*** in which the fundamental storage devices are capacitors arranged in ***matrix*** formation. Associated with each capacitor are ***field-effect transistors*** which act as switches when data is put into the store or withdrawn from it. To prevent loss of data as the capacitors discharge through the inevitable leakage paths, their charges are regularly 'topped up'—a process known as ***refreshing***. Despite the need for refreshing the dynamic RAM is simpler, more compact and cheaper than a ***static RAM*** and, although its speed is lower, is more widely used.

dynamic range (1) Of a sound programme the ratio, usually expressed in ***decibels***, of the loudest to the quietest passage.

(2) Of a transmission or recording system, the ratio, usually expressed in decibels of the overload level of the system to the minimum acceptable signal level and the latter must exceed the ***noise level*** of the system sufficiently to give the required ***signal-to-noise*** ratio.

dynamic resistance See ***slope resistance***, ***dynamic impedance***.



Figure D.19 A typical dynatron I_a–V_a characteristic

dynamic store A ***store*** from which data can be retrieved only at fixed time intervals, e.g. a rotating magnetic disk or drum.

dynatron A ***tetrode*** in which the ***anode*** is at a lower voltage than the screen grid so producing a region of negative slope in the I_a–V_a characteristic as shown in *Figure D.19*.

The effect arises as a result of secondary emission at the anode, the ***secondary electrons*** collected by the screen grid exceeding the primary electrons received from the cathode. The effect is useful in ***dynatron oscillators*** but is a disadvantage when the tube is used as an amplifier where large anode voltage swings are required. The negative-resistance kink can be eliminated by the inclusion of an earthed (or negatively-biased) suppressor grid between anode and screen grid (so giving rise to the ***pentode***) or by using beam-forming plates and aligned grids. See ***beam tetrode***.

dynatron oscillator An oscillator which utilises the region of negative slope of the I_a–V_a characteristic of a tetrode which occurs when the anode voltage is below that of the screen grid. The frequency-determining circuit is connected to the anode as shown in *Figure D.20*. Oscillation then occurs if the dynamic resistance of the tuned circuit has a suitable value, the voltage swing being limited to the extent of the negative-resistance kink. See ***dynatron***.



Figure D.20 Circuit diagram of a dynatron oscillator

dynode An electrode included in an ***electron tube*** to increase the electron stream by ***secondary emission***. See ***electron multiplier***.

E

earphone A small electro-acoustic ***transducer*** designed to fit into or onto the ear.

earth (also known as **ground** (US)) A low-resistance connection, intentional or accidental, to the mass of the earth or to a large conducting body serving as the earth such as a ship's hull or the chassis of a vehicle or of electronic equipment. To make low-resistance contact with the earth a conductor, for example a system of copper wires, may be buried in the ground; this system is commonly used at radio transmitters. For low-power equipment such as receivers an earth connection may be provided either by a copper spike driven into the ground or a connection to a metal cold-water pipe.

The potential of the earth or chassis is taken as a reference level of zero and the potential at any point in the equipment is measured with respect to it. Thus a 180-V supply line means that the voltage is 180 V with respect to earth or chassis potential. A point such as a supply line which is at a constant potential above or below earth potential is often termed 'earthy' because it is usually decoupled to earth by a capacitor giving low reactance to earth. At signal frequencies such a point may be regarded as at earth potential.

earthed-base, -emitter, -grid, etc circuit Literally a circuit in which the base, emitter, grid, etc is connected to earth but the term is generally used to mean a ***common-base, -emitter, -grid*** etc ***amplifier***.

earth loop A loop of conductors formed accidentally when the various components of a system are earthed in different places. If mains conductors pass through the loop, the loop can act as a pick-up coil, introducing undesirable levels of noise into the system. Earth loops are a common cause of mains hum in ***hi-fi*** systems.

earth return or **ground return** (US) Use of the conducting surface of the earth as one leg of an electric circuit, the other leg being provided by a conductor.

Eccles-Jordan circuit A bistable ***multivibrator*** comprising two ***triodes***, the anode of each being coupled to the grid of the other. It was used for generating pulses, the circuit being switched between its two stable states by external triggering signals.

echo An acoustic or electromagnetic wave which is so delayed as a result of ***reflection*** or ***refraction*** that it is received as a signal distinct from that directly transmitted.

economy diode Same as ***booster diode***.

eddy current A circulating current flowing in a conductor as a result of a voltage induced in it by a moving or varying magnetic field. Such currents generate heat in the conductor and this is put to useful purpose in such applications as the eddy-current brake (see also ***degassing***). In transformer cores, however, these currents represent a loss of power and to minimise such losses the cores of low-frequency transformers are constructed of stacked laminations, each electrically insulated from its neighbours.

At radio frequencies, eddy-current losses are so serious that magnetic core materials, if conductive, must be reduced to powder, the individual grains being insulated from each other to minimise losses. Alternatively non-conductive materials such as *ferrites* can be employed in the cores of RF inductors and transformers.

edge connector A linear multi-contact plug or socket designed to mate with the contacts at the edge of a printed-circuit or printed-wiring board.

Edison effect Electrical conduction between a heated filament and an independent cold electrode in the same envelope. In experiments on the blackening of the inside walls of lamps with carbon filaments Edison put a metal plate inside a lamp and found that a current flowed between filament and plate when the latter was made positive with respect to the filament. This was the first observation of ***thermionic emission.***

effective capacitance Same as ***equivalent capacitance.***

effective inductance Same as ***equivalent inductance.***

effective resistance (also known as **radio-frequency resistance**) (1) Same as ***equivalent resistance.*** (2) The total resistance of a conductor to alternating current including the ohmic resistance and the resistance due to skin and ***proximity effects.*** At RF the effective resistance can be many times the ohmic resistance. Also known as ***RF resistance.*** See ***skin effect.***

efficiency In general of an electrical device the ratio expressed as a percentage of the output power to the input power. For example the efficiency of a power transformer approaches 100%. The efficiency of an electronic device such as an amplifier is the ratio of the useful output power to the power taken from the supply. For example the efficiency of a class-A output stage reaches a maximum of 50%.

efficiency diode Same as ***booster diode.***

eigentones Standing sound waves set up between opposite surfaces of a rectangular enclosure such as a room. These waves can occur at the frequency for which the wall spacing is half a ***wavelength***, one wavelength, one and a half wavelengths, etc so that there is a series of frequencies at which eigentones can occur. Standing waves can occur across the length, width and height of a room so that the eigentone structure can be complex. The frequencies of the eigentones largely dictate the room acoustics and it is best if there is no simple relationship between these dimensions so that the eigentones are spaced evenly over the audio spectrum.

EITHER-OR gate Same as ***OR gate.***

elastance The reciprocal of ***capacitance.***

electret A dielectric solid in which the voltage applied to induce an electric field persists after the supply has been removed, leaving the dielectric with separated electric poles of opposite sign. It is the electrostatic analogue of a permanent magnet. Electrets have obvious applications in electrostatic ***microphones*** where they avoid the need for a polarising supply.

electrically-alterable read-only memory (EAROM) Same as ***electrically-erasable programmable read-only memory.***

electrically-erasable programmable read-only memory (EEPROM) A ***non-volatile read-only memory*** of ***MOSFET*** structure in which the stored data can be repeatedly altered in whole or in part by the user.

Data can be erased and reprogramming achieved with the EEPROM in situ (c.f. EPROM) by using Fowler-Nordheim tunnelling—a principle whereby certain electrons subjected to an electric field can cross the forbidden gap of an insulator to enter the conduction band and thus flow freely for a short distance to a positively-charged area.


source
nitride
gate
silicon dioxide
drain
p
p
n- silicon (Si) substrate

Figure E.1 Cross section of MNOS structure

The earliest EEPROMs used the metal-nitride-oxide-semiconductor (MNOS) structure shown in *Figure E.1*. By applying a voltage of around 20 V to the gate, charge can tunnel through to the silicon-dioxide-nitride interface. Here the charge remains trapped because of the high insulation of these regions and renders the transistor insensitive to normal operating voltages of say 5 V.


Source
Control gate
Floating-gate electrode
Drain
n+
n+
p-substrate

Figure E.2 Cross section of an EEPROM

As shown in *Figure E.2* more recent EEPROMs have, in addition to the normal input gate, a floating gate which can be charged and discharged by tunnelling. For an explanation of the behaviour of the floating gate see ***EPROM***. A ***memory cell*** usually consists of such a (storage) transistor together with a second (select) transistor. The two transistors are connected in series in a ***cascode*** arrangement and, depending on the voltage applied to their gates and to the drain terminal of the select transistor, the memory cell can be put into one of four states: unselected, erased, written and read.

electric deflection Same as ***electrostatic deflection***.

electric displacement Same as ***electric flux density***.

electric field A region near a charged body in which an electric charge experiences a mechanical force caused by the charged body. In particular there is a field between two charged bodies of opposite sign, e.g. between the plates of a charged capacitor.

electric field strength At a point in an electric field a vector representing the magnitude and direction of the mechanical force on a unit positive charge at that point. It is normally expressed in terms of the potential gradient, i.e. in volts per centimetre.

electric flux The lines of force constituting an ***electric field***.

electric flux density The electric flux per unit area normal to the direction of the ***lines of force***.

electric force Deprecated term for ***electric field strength***.

electric intensity Same as ***electric field strength***.

electric screen A screen of conducting material used to reduce the penetration of electric fields into a particular region.

electric shield (US) Same as ***electric screen***.

electric strength Same as ***dielectric strength***.

electrode Of an ***active device***: an element which emits, collects or controls the movement of electrons or holes. Electrodes have a variety of terms such as ***anode***, ***base***, ***cathode***, ***collector***, ***dynode***, ***emitter***, ***gate***, ***sink*** and ***source***.

electrode AC resistance Of an ***active device*** the ratio of a small change in electrode voltage to the resulting change in electrode current. Its value is usually quoted for a specific operating point. Thus for the electrode characteristic shown in *Figure E.3* the electrode AC resistance is given by the reciprocal of the slope of the tangent to the characteristic at the point P, i.e. it is given by RS/RQ.



Figure E.3 The electrode AC resistance is given by the reciprocal of the slope of the tangent SO to the curve at the operating point P



Figure E.4 The electrode DC resistance is given by the reciprocal of the slope of the chord OP from the origin to the operating point P

electrode DC resistance Of an ***active device*** the ratio of the direct voltage applied to an ***electrode*** to the resulting direct current through the electrode terminal. Its value is usually quoted for a specific operating point. Thus for the electrode characteristic shown in *Figure E.4* the electrode DC resistance is given by the reciprocal of the slope of the line OP, i.e. it is given by PS/PR.

electrode differential resistance Same as ***electrode AC resistance***.

electrode impedance The ratio of the voltage applied to an ***electrode*** to the resultant current through the electrode terminal of an ***active device***. Its value is usually quoted for a particular set of operating conditions. This is a general definition and the electrical characteristics of electrodes are generally given in more specific definitions such as ***electrode AC resistance*** and ***electrode DC resistance***.

electrode slope resistance Same as ***electrode AC resistance***.

electrodynamic instrument An instrument which relies for its operation on the interaction between two magnetic fields, one due to a current in one or more movable coils and the other due to current in one or more fixed coils. Some power factor meters operate on this principle.

electroluminescence Emission of light from certain materials when stimulated by an electric potential. One material used consists of a phosphor powder embedded in an insulating material. If a layer of such construction is sandwiched between transparent conducting sheets, light is produced when an alternating voltage is applied between the conducting sheets. Electroluminescent panels can be made of almost any size and to emit a wide variety of colours depending on the phosphor used.

electrolyte A conductor in the form of a liquid or paste in which the ***charge carriers*** are positively- and negatively-charged ions which migrate to the electrodes under the action of an applied EMF. Two obvious examples of electrolytes are those in electroplating baths and in ***voltaic cells***. Sometimes the term is applied to the chemical which, when dissolved in a liquid (usually water), gives rise to the ***ions*** by ***dissociation*** and thus promotes electrical conductivity.

electrolytic capacitor A fixed capacitor in which the ***dielectric*** is a thin film of oxide formed by electrolytic action on aluminium foil which acts as the positive plate, the ***electrolyte*** acting as negative plate. Because of the minute thickness of the dielectric this form of construction gives high ***capacitance*** in a component of small dimensions and the dimensions can be further reduced by etching the foil to increase its surface area. In the so-called 'dry' electrolytic capacitors the liquid electrolyte is replaced by a layer of paper saturated with electrolyte. Electrolytic capacitors differ from other types in that they are polarised, i.e. one particular terminal must always be biased positively with respect to the other. This is not a serious disadvantage; because of their high capacitance such capacitors tend to be used in ***smoothing*** and ***decoupling*** circuits where a polarising voltage is present. The irreversible nature of the electrolytic capacitor is indicated in the graphical symbol by representing the positive plate as an open rectangle as shown in *Figure E.5*.



Figure E.5 Graphical symbol for an electrolytic capacitor. The positive sign is not always necessary

electromagnet A device comprising a ferromagnetic core within a winding which displays magnetic properties only when a current flows in the winding.

electromagnetic deflection In a ***cathode ray tube***, deflection of the ***electron beam*** by the magnetic field set up within the tube by current-carrying coils clamped to the outside of the tube. This is the method of deflection favoured in TV camera tubes and picture tubes. Two sets of coils are used, one fed with a line-frequency ***sawtooth*** current to deflect the beam horizontally and the other fed with a field-frequency sawtooth current to give vertical deflection.

electromagnetic induction In a ***conductor*** linked with a magnetic field, the generation of a voltage in the conductor as a result of a change in the magnitude of the field or of relative movement between conductor and field.

The ***transformer*** is an application of electromagnetic induction: the voltage induced in the secondary winding is a result of the continually-changing magnetic field produced by the current in the primary winding. The ***moving-coil microphone*** or pickup is an application in which voltages are induced in a conductor which moves in a static magnetic field. Reference is sometimes made to 'induced currents' but electromagnetic induction causes voltages to be set up in conductors and these can give rise to currents only if the conductors form closed circuits.

electromagnetic lens A lens in which an ***electron beam*** can be brought to a focus at a desired point by means of a ***magnetic field***. There are two basic types; in one type, used with TV camera tubes, the entire tube is included within a coil carrying DC which produces a magnetic field parallel to the tube axis. This field has no effect on ***electrons*** travelling along the tube axis but those moving at angles to the axis are rotated about the axis and return to it at regular intervals along the axis as shown in *Figure E.6*. Thus there


focusing coil
electron gun
electron beam
target
focus points

Figure E.6 A long magnetic lens

are a number of points at which the electron beam is in focus and by adjustment of the accelerating electric field or of the magnetic field one of these focus points can be made to coincide with the target.

The second type of magnetic lens employs a very short magnetic field which can be produced by a permanent ring magnet. The field from such a magnet has pronounced radial components and the interaction of these with the electron beam causes the beam to rotate about the tube axis. The axial component of the field causes the beam to be deflected towards the tube axis so that an image, usually rotated, can be produced on the target.

electromagnetic screen A screen of conducting and possibly magnetically-permeable material used to reduce the penetration of electric and magnetic fields into a particular region.

electromagnetic shield Same as ***electromagnetic screen.***

electromagnetic waves Waves consisting of linked magnetic and electric fields in which each field is at right angles to the other and to the direction of propagation of the waves. Such waves travel in free space at a velocity of 3×10^{10} cm/s and are known as light, radio, gamma, etc waves according to the frequency as indicated in *Figure E.7*.


Wavelength λ metres
10^4
10^2
1
10^{-2}
10^{-4}
10^{-6}
10^{-8}
10^{-10}
10^{-12}
10^{-14}
$3 \cdot 10^{-16}$
10^4
10^6
10^8
10^{10}
10^{12}
10^{14}
10^{16}
10^{18}
10^{20}
10^{22}
10^{24}
Frequency f (Hz)
Long
Med
Short
Ultra short
Radio waves
Infra red
Visible spectrum
Ultra violet
γ-rays
X-rays
Cosmic rays

Figure E.7 Spectrum of electromagnetic waves

electrometer Originally an instrument in which the mechanical force between electrically-charged bodies was used to measure potential difference. Thus an ***electrostatic voltmeter*** is an example of an electrometer. The unique feature of the electrometer is that it takes no current from the source of voltage being measured, i.e. the input resistance of the device is infinite. The term is now used for instruments in which the input signal is applied between the grid and cathode of an ***electron tube***. This also has a high input resistance provided that the grid is negatively biased. The amplified output from the tube can be measured by a conventional measuring instrument such as a moving-coil milliammeter.

electrometer tube An ***electron tube*** specifically designed to have a very low value of grid current for negative grid voltages so as to be suitable for the measurement of small direct currents or voltages in an ***electrometer***.

electromotive force (EMF) The property of a physical or chemical device which enables it to drive an electric current around a circuit. Most of the devices are energy converters and the energy manifested as an EMF results from an input in another energy form. For example in an alternator the EMF is generated by ***electromagnetic induction*** arising from mechanical movement of the rotor. In a transformer secondary winding the EMF is generated by electromagnetic induction due to the changes in ***magnetic flux*** produced by the signal in the primary winding. In a ***thermocouple*** the EMF results from heat applied to the junction and in a photovoltaic cell it is generated by incident light. In a ***voltaic cell*** the energy providing the EMF arises from chemical action within the cell. The unit of EMF is the volt, symbol V.

electron One of the two basic charged particles of which the atoms of chemical elements are assumed to be composed. The other charged constituent is the ***proton*** and an atom is regarded as a central nucleus composed of positively-charged protons and uncharged neutrons. The net positive charge of the nucleus is offset by the negative charge of an equal number of electrons which are assumed to orbit the nucleus in a series of shells or rings as indicated in *Figure E.8*. In this diagram, for simplicity, the shells are shown as coplanar. Electrons in the outermost orbit of certain elements can be removed with little effort. Such electrons are known as free. By movement of these electrons it is possible to achieve a transfer of negative charge through a material: this constitutes an electric current and



Figure E.8 Simplified diagram showing the construction of the atom

is the mechanism of conduction in metals and other good electrical conductors. It is sometimes known as ohmic conduction. Free electrons are also available in ***n-type semiconductors*** and here too current can flow through the material under the stimulus of an EMF, the electrons acting as negative ***charge carriers***. A somewhat different conduction process occurs in ***p-type semiconductors***.

Another way in which a unidirectional flow of electrons can be obtained is by heating a material rich in free electrons such as tungsten in a vacuum and by collecting the electrons by a positively-charged electrode. In this way a stream of electrons, i.e. an electric current, can be made to cross an empty space, a phenomenon known as ***thermionic emission*** which is extensively exploited in ***electron tubes***.

electron beam A stream of ***electrons***, all moving with approximately the same velocity, and confined to a particular value of cross-sectional area. In TV camera tubes and picture tubes such a beam originates in an ***electron gun*** and is focused by an electron lens on the target or screen.

electron-coupled oscillator (ECO) A ***tetrode*** or ***pentode*** circuit in which the cathode, control grid and screen grid operate as an earthed-screen-grid oscillator, so eliminating any capacitive coupling between the output (anode) circuit and the oscillator circuit. A typical circuit diagram utilising a ***Hartley oscillator*** is given in *Figure E.9*. The only link between the oscillator circuit and the output circuit is provided by the electron stream from the cathode. Thus the frequency of oscillation is unaffected by changes in loading on the anode circuit and can also be made substantially independent of HT supply variations by making the screen-grid voltage a particular fraction of the anode voltage.



Figure E.9 Circuit diagram of an electron-coupled oscillator using a Hartley circuit

electron device A device which operates by virtue of electrons moving through a vacuum, a gas or a ***semiconductor***.

electron gun An assembly of ***electrodes*** which generates the ***electron beam*** in a ***cathode ray tube***. As shown in *Figure E.10* the gun consists typically of an indirectly-heated cathode, a ***control grid*** and an ***anode***. The negative



Figure E.10 One possible form of electron-gun structure



Figure E.11 Graphical symbols for an electron gun. (a) detailed; (b) simplified

voltage on the control grid determines the density of the beam leaving the gun (and hence the brightness of the display). The anode is normally a cylinder containing a number of apertures which limit the cross section of the beam leaving the gun. *Figure E.11* gives detailed and simplified graphical symbols for an electron gun.

electronic calculator Digital equipment usually with a keypad input and a numerical display output capable of carrying out arithmetical operations.

The design of calculators has greatly benefitted from the developments in ***monolithic integrated circuits*** since 1960 and they use many of the techniques employed in computers. Early machines were bulky desk-top models using ***seven-segment light-emitting diode*** displays. These were superseded by portable personal machines, battery-driven, still with LED displays. Modern calculators can be as small as a visiting card, have a ***liquid-crystal display***, and require so little power that they operate from built-in photocells in normal room lighting.

They are capable of addition, subtraction, multiplication, division, square roots, trigonometrical and other functions. They even have an internal memory to hold intermediate results in complex calculations. They deliver answers correct to ten significant figures!

electronic mail A system whereby messages are sent from one computer terminal to another. The message is not normally routed directly to the recipient's terminal, because it may be switched off or in use for other purposes. Instead the received message is stored in the ***host*** computer providing the recipient's mail service. The recipient may be informed that there is a message for him when he next logs on to the host or the onus may be on him to check his 'electronic mailbox' regularly for incoming messages.

Electronic Point of Sale (EPOS) An intelligent electronic cash register which offers other functions besides those normally expected of a cash register. For example, it may automatically establish the identity of an item of merchandise by reading a ***bar code*** on it and then retrieve its price from a ***host*** computer which monitors the transactions at several such EPOS terminals.

electronic publishing In general any system using electronic equipment to make quantities of data available on demand to a wide public. More specifically the term is often applied to ***bulletin board systems*** and to the posting of information on large computer networks such as the ***Internet.***

electronics The study of the conduction of electricity in a vacuum, in gases and in ***semiconductors***. Electronics is therefore concerned with methods of generating and controlling ***charge carriers*** such as ***electrons***, ***holes*** and ***ions*** in, for example, ***electron tubes*** and ***transistors***, and with applications of such devices.

electronic switching Use of ***active devices*** to perform switching operations. A ***transistor*** is a good approximation to a switch because it has nearly infinite ***impedance*** when non-conductive, and a very low impedance when conductive. Moreover it can be switched from one state to the other by a signal applied to the ***base*** (or ***gate***). Two transistors with a common emitter or collector connection can perform a changeover operation by suitable signals applied to the bases. Such circuits are better than mechanical switches because they have no moving parts and can operate more quickly. Electronic switching is extensively employed in logic circuitry, for example in ***digital computers***.

electron image Same as ***charge image***.

electron lens An assembly of ***electrodes*** or of permanent or ***electromagnets*** which can be used to focus an electron beam at a given point, e.g. on the target of a cathode ray tube or a camera tube. See ***electrostatic lens***, ***magnetic lens***.

electron microscope An electron-optical instrument which gives a greatly-enlarged image of an object and with magnification and resolution superior to those of an optical microscope. The image may be formed by an ***electron beam*** which passes through a slice of the object or is reflected from it and is magnified by electron lenses for projection on to a screen or photographic film. Sometimes the image is formed from ***electrons*** emitted by the subject itself.

electron multiplier An ***electron tube*** in which the signal current is amplified by means of secondary emission. The tube contains a ***cathode***, a series of ***dynodes***, and an ***anode*** arranged as shown in *Figure E.12*. ***Electrons*** released from the cathode (e.g. as a result of light falling on it) are attracted to dynode 1 by its positive potential and, on striking it, release secondary electrons from it. These are, in turn, attracted to dynode 2 and release further secondary electrons from this. Thus the process continues, the



Figure E.12 The principle of the electron multiplier

number of secondary electrons growing at each stage until the anode is reached. In this way current amplification factors of several thousand can be obtained. Such multipliers are used in photocells (see ***photo-multiplier***) and in the ***image-orthicon tube***.

electron optics The study of the behaviour of ***electron beams*** subjected to electric and magnetic fields, particularly the use of such fields to deflect and focus electron beams. By applying suitable potentials to a system of electrodes it is possible to produce an electric field with ***equipotential surfaces*** shaped like convex or concave lenses. The behaviour of an electron beam entering such a system is similar to that of a light beam entering an optical lens system and this analogy has prompted the adoption of the term electron optics. See ***electron lens***.

electron ray tube (US) Same as ***cathode ray tuning indicator***.

electron tube General term for an evacuated or gas-filled envelope containing electrodes and in which conduction occurs by virtue of ***electrons*** or ***ions*** which move in a controlled manner according to the voltages or currents applied to the ***electrodes***. The US term 'tube' has a wider meaning than the English 'valve' because it embraces cathode ray tubes, camera tubes, picture tubes and photocells which are not usually regarded as valves. See ***gas-filled tube***, ***vacuum tube***.

electrostatic coupling Same as ***capacitive coupling***.

electrostatic deflection Deflection of the ***electron beam*** in a ***cathode ray tube*** by the electric field between two charged deflector plates. The beam is deflected towards the positively-charged plate. See ***deflection sensitivity***.

electrostatic field Same as ***electric field***.

electrostatic flux Same as ***electric flux***.

electrostatic focusing Focusing of the ***electron beam*** in a ***cathode ray tube*** by the use of an ***electrostatic lens***.

electrostatic induction The process by which an electrically uncharged body acquires a charge when placed near (but not touching) a charged body. The process is a manifestation of the repulsion between 'like' charges. If the charged body is negative it has a surfeit of electrons and these repel electrons on the uncharged body to its tar side, leaving the nearside deficient of electrons, i.e. positively charged—a charge arising from electrostatic induction.

electrostatic lens A lens in which an ***electron beam*** is brought to a focus at a desired point by means of an electric field. In general an electrostatic lens consists of an assembly of ***electrodes*** usually of cylindrical form and concentric with the beam. By suitably biasing these electrodes an electric field is produced which has an effect on the electron beam similar to that of a convex lens on a beam of light and by adjustment of the cylinder potentials the electron beam can be brought to a focus at the desired point.

electrostatic loudspeaker A ***loudspeaker*** in the form of a charged parallel-plate ***capacitor*** with a very small air gap, one plate being fixed and the other free to vibrate under the action of the AF signal applied between the plates. This simple form of loudspeaker is illustrated in *Figure E.13* and gives considerable ***harmonic distortion*** unless the amplitude of vibration is kept very small. Its use is therefore limited to the upper end of the AF spectrum where signal amplitudes are small. If, however, the vibrating plate is mounted between two perforated fixed plates, the AF signal being applied in push-pull to the outer plates, the distortion can be so reduced that successful loudspeakers operating on this principle over the whole audio range have been developed.



Figure E.13 A simple electrostatic loudspeaker

electrostatic memory A device in which data are stored in the form of electric charges, e.g. on the screen of a ***storage tube***.

electrostatic microphone A ***microphone*** in the form of a small charged parallel-plate ***capacitor*** with a very small air gap, one plate being fixed and the other free to vibrate under the influence of any incident sound wave. When the moving plate (the diaphragm) vibrates, the capacitance of the microphone changes in sympathy with the pressure of the incident sound wave. Because the charge on the plates is maintained constant, the voltage between the plates varies similarly and this is the output of the microphone.

If such a microphone is connected to a long length of cable, the capacitance of the cable is in parallel with the microphone capacitance and effectively reduces the microphone output. To avoid this effect a common technique is to incorporate a head amplifier in the microphone casing to isolate the microphone from the cable and, of course, to provide amplification of the low microphone output.

electrostatic screen Same as ***electric screen***.

electrostatic shield (US) Same as *electric screen*.

electrostatic voltmeter An instrument for measuring high direct voltages which relies for its action on the attraction between the opposite charges on the plates of a *capacitor*. One form of the instrument resembles a multiplate variable capacitor, one set of plates being fixed and the other free to move against the pull of a spring. The extent of the movement is an indication of the magnitude of the applied voltage. The instrument, being capacitive, takes no current from the source of voltage after the initial charging current and is therefore useful for measuring voltages with a very high source resistance such as the EHT supply in TV receivers.

elliptical polarisation Property of an *electromagnetic wave* of which the plane of *polarisation* is rotating and for which the *amplitude* varies according to the direction of the plane of polarisation. Vertically- and horizonally-polarised radio waves can become elliptically polarised after reflection in the ionosphere. If the amplitude of the wave is constant whilst the plane of polarisation rotates the wave is said to be circularly polarised.

emission General term for the release of electrons from a surface when suitably stimulated. See *cold cathode*, *field emission*, *photo-electric emission*, *secondary emission*, *thermionic emission*.

emitron tube Same as *iconoscope*.

emitter That region of a bipolar transistor from which *charge carriers* flow into the base region. The carriers are *majority carriers* in the emitter region but *minority carriers* in the base region.

emitter AC resistance See *electrode AC resistance*.

emitter-coupled logic (ECL) A form of logic using *bipolar transistors* in which the output signals are derived from the emitters. The low output impedance thus obtained permits rapid charging and discharging of output circuits. Moreover by using *Schottky diodes* connected between collectors and base the transistors can be prevented from becoming saturated. A saturated transistor takes appreciable time to turn off because of *carrier storage*. Thus very low rise and fall times are possible with ECL making this one of the fastest logic systems.

emitter follower Same as *common-collector circuit*.

emulation The use of one device or system to play the part of another. More specifically, the *programming* of a *computer* or *processor* to behave as though it were a computer or processor of a different type. In computing this is useful when a user wishes to access data stored in a format peculiar to a machine which is now obsolete and has been discarded. It is common practice for *printers* to offer a range of emulations of other popular printer types. This ensures that the user will have suitable *driver* software.

enabling signal A signal which prepares a circuit for some subsequent action. For example the signal may open a normally-closed gate.

Encapsulated PostScript (EPS) A *subset* of *PostScript* which is widely used for transferring *vector graphics* images between different applications and different computer types.

encapsulation The process of encasing and sealing a component or an assembly of components in moulded insulating material such as resin. The process is usually carried out in a vacuum and under pressure to prevent the formation of voids and air bubbles.

encoding Same as ***coding***.

endurance test A test on a component to see if it can withstand the changes in stress it is likely to encounter during its life. Depending on the nature of the component the test consists of repeated changes in mechanical or electrical stress, the number of changes being comparable with that likely to occur during the life of the component.

energy gap In an ***energy-level diagram*** the difference in electron energy between the upper boundary of the ***valence band*** and the lower boundary of the ***conduction band***. This is equal to the energy of the ***forbidden band*** and may be defined as the minimum amount of energy required to raise an electron from the valence band to the conduction band.

energy-level diagram A diagram in which electron energy is plotted on a vertical axis.

Electrons have different energies depending on the orbit they occupy. Thus the energies occupy vertical bands such as the conduction band and the valence band as shown in *Figure E.14*. See ***conduction band, forbidden band, valence band***.



Figure E.14 Typical energy-level diagram

enhancement mode A mode of operation of a ***field-effect transistor*** which is designed to take zero drain current at zero gate bias, a forward bias being necessary to increase the current to a normal working value.

entity In computing an item of data stored in a ***database*** or a ***repository*** member or a relationship between repository members.

envelope delay The time taken for a particular point in a ***waveform*** to pass though a system or equipment. It is equal to the first derivative of the phase shift ϕ with respect to the angular frequency ω. Thus

$$\text{group delay} = \text{envelope delay} = \frac{\delta\phi}{\delta\omega}$$

See ***delay, delay distortion, phase distortion***.

envelope detector A detector of which the output waveform is substantially that of the ***modulation envelope*** of the input signal.

envelope velocity The velocity of propagation of the envelope of a wave occupying a frequency band over which the ***envelope delay*** is approximately constant.

epitaxy A method of depositing a thin layer of ***semiconductor*** material on a crystal of the same material so that the layer takes up the same crystal orientation as the crystal. The method is used in transistor manufacture so that the bulk of the emitter and collector regions can be of low ***resistivity*** (and hence low-loss) material, the epitaxial layer being of resistivity suitable to form the pn junctions with the base layer.

equaliser A ***network*** designed to offset the effects of attenuation distortion or phase distortion occurring in ***lines***, equipment or ***transducers***. Thus an equaliser intended to compensate for a loss in high-frequency response of a line requires a complementary 'top-lift' frequency characteristic. Equalisers are often made variable so that they can be adjusted to suit individual line requirements.

equality gate Same as ***equivalence element***.

equipotential surface In an electric field an imaginary surface all points on which have the same electric potential. Lines of electric force always cross equipotential surfaces at right angles. In the electric field surrounding a point charge the equipotential surfaces are spherical and concentric with the point charge. In a charged parallel-plate ***capacitor*** the equipotential surfaces are planes parallel to the plates.

equivalence element In digital circuitry an element with two inputs which gives a logic-1 output when and only when both inputs are at logic 1 or at logic 0. The output of an equivalence element is therefore the complement of that of an ***exclusive-OR gate***. See ***logic gate, logic level***.

equivalent capacitance That value of ***capacitance*** which can replace a given ***two-terminal network*** without affecting the voltage or current at the terminals. For a simple network of capacitances C_1, C_2, C_3, etc in parallel the equivalent capacitance C_{eq} is equal to the sum of the individual capacitances thus

$$C_{eq} = C_1 + C_2 + C_3 + \text{etc}$$

For a simple network of capacitances C_1, C_2, C_3, etc in series the reciprocal of the equivalent capacitance C_{eq} is equal to the sum of the reciprocals of the individual capacitances thus

$$\frac{1}{C_{eq}} = \frac{1}{C_1} + \frac{1}{C_2} + \frac{1}{C_3} + \text{etc.}$$

equivalent circuit A simple theoretical circuit of ***resistance, inductance, capacitance***, voltage or current sources which has approximately the same electrical characteristics as a practical circuit or ***active device*** over a particular amplitude or frequency range. Such equivalent circuits are convenient for analysis of circuit behaviour or circuit design. *Figure E.15* is an example of one form of equivalent circuit for a ***bipolar transistor***.

equivalent inductance That value of ***inductance*** which can replace a given ***two-terminal network*** without affecting the voltage or current at the terminals. For a simple network of inductances L_1, L_2, L_3, etc in series (and without mutual coupling) the equivalent inductance L_{eq} is equal to the sum of the individual inductances thus

$$L_{eq} = L_1 + L_2 + L_3 + \text{etc}$$



Figure E.15 Example of an equivalent circuit for a bipolar transistor which may be used at radio frequencies

For a simple network of inductances L_1, L_2, L_3, etc in parallel (and without mutual coupling) the reciprocal of the equivalent inductance L_{eq} is equal to the sum of the reciprocals of the individual inductances thus

$$\frac{1}{L_{eq}} = \frac{1}{L_1} + \frac{1}{L_2} + \frac{1}{L_3} + \text{etc.}$$

equivalent network A ***network*** which, under certain conditions, can replace another network without effect on the electrical performance of the system of which it forms part. For example a ***pi-network*** can replace a ***T-network*** at a particular frequency provided the elements have suitable values. See ***star-delta transformation***.

equivalent noise resistance Of a circuit or equipment the value of a fictitious resistor included at the input of the circuit (assumed noise-free) which at 290°K gives the same noise output as the circuit. For an ***electron tube*** the resistor is assumed connected in the control grid circuit. Thus the ***shot noise*** and ***partition noise*** of the tube are regarded as thermal noise generated in the equivalent noise resistance.

equivalent resistance That value of resistance which can replace a given ***two-terminal network*** without affecting the voltage or current at the terminals. For a simple network of resistances R_1, R_2, R_3, etc, in the series the equivalent resistance R_{eq} is equal to the sum of the individual resistances thus

$$R_{eq} = R_1 + R_2 + R_3 + \text{etc}$$

For a simple network of resistances R_1, R_2, R_3, etc, in parallel the reciprocal of the equivalent resistance R_{eq} is equal to the sum of the reciprocals of the individual resistances thus

$$\frac{1}{R_{eq}} = \frac{1}{R_1} + \frac{1}{R_2} + \frac{1}{R_3} + \text{etc.}$$

erasable, programmable, read-only memory (EPROM) A ***non-volatile read-only memory*** in which the stored data can be repeatedly changed by the user.

Most EPROMs are based in the floating-gate structure illustrated in *Figure E.2*. Programming is achieved by applying a high voltage (e.g. 20 V) to the drain terminal. This injects high-energy electrons from the substrate through the silicon dioxide layer to the floating gate, where the charge is stored, the gate being surrounded by insulating silicon dioxide.

Because of the presence of the stored charge a high voltage must now be applied to the select gate to turn the transistor on; normal operating voltages (e.g. 3 V) have no effect. In the absence of a stored charge the normal low voltage would, of course suffice to turn the transistor on.

To erase the cell requires internal emission of photo-electrons from the floating gate to the select gate and the substrate. This is achieved by exposing the cell to ultra-violet light for several minutes. The light must be applied via a window in the package and this requires the EPROM to be removed from the equipment for erasure. This disadvantage is overcome in the ***EEPROM***.

erasing (1) In ***magnetic recording*** the obliteration of an existing recording to make the medium available for a new recording. (2) In ***digital computers*** the removal of information from the store leaving the space available for new information.

error In ***computers*** and ***data-processing equipment***, circumstances which prevent normal execution of a ***program*** through the introduction of conditions which the ***central processing unit*** cannot handle. Examples are an instruction to divide a number by zero or to perform an operation on a file that does not exist. In such conditions an error message is often given.

error-correcting code A data code in which the signals conform to specific rules of construction to enable departures from the standard form to be automatically detected and corrected. Such codes require more signal elements than are necessary to convey the information. See ***error-detecting code, parity check.***

error-detecting code A data code in which the signals conform to specific rules of construction to enable departures from the standard form to be detected. Such codes require more signal elements than are necessary to convey the information. As an example in a digital code it may be arranged that all words contain an even number of pulses. Thus any word with an odd number can be detected by a parity check. See ***error-correcting code, parity check.***

Esaki diode Same as ***tunnel diode.***

ethernet Form of ***Local Area Network*** for connecting computers, printers and other equipment within one building. The connection is via twisted wires or coaxial cable and can transmit data at up to 10 M bits/second.

exalted-carrier reception Reception of amplitude-modulated single-, vestigial or double-sideband signals in which the carrier is amplified more than the sidebands with the object of reducing distortion. This method is often used to receive reduced-carrier single-sideband transmissions. See ***amplitude modulation, double-sideband transmission, single-sideband transmission, vestigial-sideband transmission.***

except element Same as ***exclusive-OR element.***

excitation In general the application of an input signal or of the power supply to an item of equipment or to a stage. For example, the current which energises the field magnets of a DC generator is called the excitation. The input signal applied to the control grid of an ***electron tube*** is also known as the exciting voltage.

excitron A grid-controlled gas-discharge rectifier with a mercury-pool cathode and a single anode capable of a large current output. The arc is initiated by an igniter electrode and is maintained by a keep-alive electrode fed from an auxiliary DC source.

exclusive-NOR gate A gate with two inputs which gives a logic-0 output when one and only one of the inputs stands at logic-1. It is therefore the complement of an exclusive-OR gate and its performance is identical with that of an ***equivalence element***.

exclusive-OR gate A gate with two inputs which gives a logic-1 output when one and only one of the inputs is at logic 1. The graphical symbol for an exclusive-OR gate is given in *Figure E.16*.



Figure E.16 Logic symbol for an exclusive-OR gate

executable code Same as ***machine code***.

exit In mainframe computers a point in the ***program*** at which control can be transferred to a user-defined ***subroutine***. It allows users to tailor standard software to meet their precise needs.

expansion Increase in the volume range of a signal by varying the gain to which it is subjected according to the mean volume level, gain being greater for high volume levels than for low volume levels. This is the converse of ***compression*** and it is used to restore the original volume range of a compressed signal. To achieve exact compensation for compression the laws of the compressor and expander must be the same.

expansion card An electronic circuit board which plugs into the ***backplane*** in a computer. It might contain an interface for some peripheral, additional memory, a video digitiser, an extra disk drive or some other storage medium.

expert system A computer application that simulates the behaviour of a human expert in some subject. The application stores large quantities of information in a logically organised structure. It has precise rules about the circumstances in which the information is presented to the user. For example, a medical expert system might begin with a menu listing types of symptoms. Each menu item might lead to a further sub-menu of more specific symptoms. These in turn might lead to a set of questions which the user must answer concerning his condition. When this is completed, the application describes possible causes of the condition and methods of treatment. The application has, in fact, followed much the same course that a consultation with a live doctor might have taken.

exploring coil Same as ***search coil***.

exponential horn An acoustic horn the cross-sectional area of which increases exponentially with distance from the throat. Such horns were used in acoustic record players and sometimes with loudspeakers, the best example of which is the Voigt corner horn loudspeaker.

export In computing, to extract data from an application in a format that is foreign to that application or to that computer type. For example, most ***vector graphics*** packages allow users to export the current document in ***EPS*** (***Encapsulated PostScript***) format. This is useful because this format can also be ***imported*** by a wide variety of applications on many computer types. Exporting facilitates the transfer of data between applications and ***platforms***.

Extended Binary Coded Decimal Interexchange Code (EBCDIC) The code used to represent alphanumeric and other printable characters and control characters in some mainframe and mini-computers, in contrast with the ***ASCII*** code used in microcomputers. The two codes are not compatible and applications which transfer textual data between, e.g. mainframe computers and microcomputers, are required to convert the data from one code to the other.

extended character set An ***ASCII*** character set that includes characters having codes above 127. The additional characters usually included accented letters for most European languages, a selection of currency symbols and a wide range of punctuation marks.

extinction current Of a ***gas-filled tube*** the minimum current at which the discharge can be maintained.

extinction frequency In ***magnetic recording*** the frequency at which the output from the ***reproducing head*** falls to zero as a result of the recorded wavelength becoming comparable with the effective width of the gap in the reproducing head.

extinction voltage Of a ***gas-filled tube*** with decreasing anode voltage the value of the voltage at which the discharge ceases.

extrinsic semiconductor A ***semiconductor***, the conductivity of which is dependent on the presence of an impurity. Most semiconductor materials in their pure state are almost non-conductive but by the introduction of a controlled amount of a suitable impurity the conductivity can be increased to a value at which the material can be used in the manufacture of semiconductor devices such as ***diodes*** and ***transistors***. The proportion of impurity needed for this purpose is very small, typically a few parts in 10^8 so that the initial semiconductor material must be in a very high state of purity. See ***intrinsic semiconductor***.

F

facsimile (1) The process of ***scanning*** a still picture to obtain corresponding electrical signals which can be used locally or remotely to produce a recorded likeness of the picture.

The process is extensively used by news media for the radio transmission of photographs and documents over telephone circuits. The original is clamped to a cylinder which rotates, causing a spot of light to scan the material in a spiral path. The light transmitted through the original falls on a ***photocell***, the output of which is sent to the reproducing machine. The image is reproduced on photo-sensitive material clamped to a rotating cylinder and scanned by a light beam the density of which is controlled in effect by the output of the photocell. ***Synchronising signals*** are used to keep the scanning process at the transmitting and receiving ends in step.

(2) A form of paper-based ***electronic mail*** using standard telephone lines. A 'fax machine' consists of a ***scanner***, a ***printer***, a ***modem*** and a dedicated microcomputer. In the sending instrument the document is scanned and the resulting ***bitmap*** is ***compressed*** before transmission over the telephone lines. In the receiving instrument the bitmap is reconstructed and printed. Computer software is available which allows computers connected to suitable modems to send fax messages based on software ***documents*** which may never have been printed on paper and to receive and display fax messages on screen without any need to print them.

(3) The term is also used to mean an image reproduced by either of the above processes.

fading Accidental or deliberate variation of signal ***amplitude***. Random amplitude variations occur in the signal input to a radio receiver as a result of the vagaries of radio-wave propagation and AGC systems are used in ***receivers*** to minimise the effects of such variations.

Deliberate variations of signal amplitude are employed in sound and vision mixing equipment where programme material is introduced by bringing the signals up to standard amplitude (known as fading up or fading in). Similarly programme material is removed by reducing the signal amplitude to zero (known as fading out).

fader Control used for fade-in and fade-out effects. See ***fading***.

failure Cessation of the ability of a component or equipment to carry out the required function.

failure rate The number of failures per unit time.

fall time A measure of the steepness of the trailing edge of a pulse waveform. More specifically it is the time taken for the instantaneous ***amplitude*** to change from 90% to 10% of the peak value as illustrated in *Figure F.1*.

The ability of a circuit to bring about changes in voltage or current as required in the reproduction of pulses is determined by the high-frequency response of the circuit and the following simple relationship exists between



Figure F.1 Fall time of a pulse

fall time and upper frequency limit f_{max}:

$$f_{max} = \frac{1}{2\,(\text{fall time})}$$

Thus to reproduce a pulse with a 0.1-µs fall time an amplifier requires an upper frequency limit of at least 5 MHz.

In a simple *RC* or *RL* circuit, decreases in voltage or current are exponential in form and for such a change the fall time is simply related to the time constant according to the approximate relationship

fall time = 2.2 × time constant.

fan in In logic circuitry the maximum number of outputs that may be connected in parallel at the input to a logic element whilst still permitting normal operation of that element.

fan out In logic circuitry the maximum number of inputs which can be connected in parallel at the output of a logic element whilst still permitting normal operation of that element.

Farad The unit of capacitance, symbol F. A capacitor is said to have a capacitance of 1 F when 1 coulomb of charge on each plate sets up a potential difference between them of 1 Volt. The farad is an inconveniently large unit and the microfarad (µF) and the picofarad (pF) are more commonly used.

Faraday cage An earthed ***electric screen*** of wire mesh or parallel conductors which shields equipment within it from the effects of ***electric fields*** but is transparent to ***magnetic fields***.

Faraday's law Of electromagnetic induction states that the EMF induced in a circuit is directly proportional to the rate of change of the magnetic flux linked with the circuit.

fatal error An ***error*** which necessitates the immediate termination of the current application, but does not necessarily affect other tasks in the computer.

fax Same as ***facsimile*** (2).

feed Of an ***active device*** the mean current taken by the device from the DC power supply.

feedback The return of a portion of the signal at any stage in an amplifier to an earlier stage so as to augment or reduce the signal at that stage. If the returned signal is in phase with the signal at the earlier point the feedback is said to be positive and its effect is to increase gain. If the returned signal is in phase opposition to the signal at the earlier point the feedback is said to be negative and its effect is to reduce gain. See ***negative feedback***, ***positive feedback***.

feeder In general any ***transmission line*** carrying electrical power. In particular the type of line used to connect an ***antenna*** to a transmitter or a receiver.

ferrite A homogeneous non-metallic material with high permeability and high electrical resistance with the general formula MFe_2O_4 where M is a divalent metal such as nickel, cobalt or zinc. Ferrite cores have very low eddy-current losses making them suitable for use in RF inductors and transformers and in the yokes of deflection coils. Ferrites are of ceramic nature and cannot be sawn or drilled. They are produced in the form of cups, rods and rings from which magnetic circuits can be constructed.

ferrite bead store Same as ***bead store***.

ferromagnetism A property of certain materials subjected to a magnetising field which causes induced magnetism which greatly aids the applied field. Such materials are strongly attracted to a magnetic pole and have high effective permeabilities which are greatly dependent on the applied magnetising field. Iron, cobalt, nickel and certain alloys are typical examples of ferromagnetic materials. See ***diamagnetism***, ***paramagnetism***.

fibre optics The study of the transmission of light along thin fibres of transparent material. Light can be transmitted along such a fibre by a succession of internal reflections and transmission is improved if the fibre material is clad in a material of lower refractive index. Transmission is unaffected if the fibre is bent and thus optical fibres provide a method of conveying light from one point to another and around bends if necessary.

By using an assembly of a very large number of very fine fibres it is possible to convey optical images from one point to another and around bends. This is useful in surgery for internal examinations of the body and there are also television applications.

Because of the enormous ***bandwidth*** obtainable with optical fibres they are also used as a means of communication over long distances.

fidelity The degree to which a transmission system or part of a system reproduces at its output the essential characteristics of the signal applied to its input. The term is often applied to audio equipment such as amplifiers and loudspeakers.

field In TV the part-picture composed by the lines described in one downward sweep of the scanning agent. In ***twin-interlaced scanning***, as used in most TV systems, two vertical sweeps are needed to cover all the lines of the picture and each field is thus a half-picture. If the lines are numbered in sequence from the top to the bottom of the picture, the scanning agent first covers lines 1, 3, 5, etc (this being known as the odd field) and then returns to the top of the picture to cover lines 2, 4, 6, etc (this being known as the even field). The field was formerly known as a ***frame***.

field blanking In TV the suppression of the picture signal during the interval between successive fields.

field-effect transistor (FET) A ***transistor*** consisting essentially of a channel of ***semiconductor*** material, the resistance of which can be controlled by the voltage applied to one or more input terminals (gates).

A feature of the FET is that the input resistance of the gate is very high so that input current is negligible. FETs are therefore voltage-operated devices, a property they share with the ***electron tube***. FETs differ from ***bipolar transistors*** in that the output current is carried by only one type of charge carrier, e.g. electrons in n-channel devices. See ***insulated-gate field-effect transistor, junction-gate field-effect transistor***.

field emission The release of electrons from an unheated surface under the action of a strong magnetic field.

field frequency In TV the number of vertical sweeps made by the scanning beam in one second. For ***interlaced scanning*** it is equal to the product of the picture frequency and the number of fields per picture. In most TV systems the field frequency is approximately equal to the frequency of the supply mains. In Europe this is 50 Hz.

field sync signal In TV the signal transmitted at the end of each field to initiate vertical ***flyback*** of the scanning beam in receivers so keeping field scanning at the receiver in step with that at the transmitter.

In most TV systems the field sync signal consists of one or more pulses (each longer than the line sync pulse) and so arranged that the continuity of the line sync pulses is not interrupted. See *Figure F.2*.



Figure F.2 Waveform of a field sync signal

field time base In TV the circuits responsible for generating the signals causing vertical deflection of the scanning beam.

filament The cathode of an ***electron tube*** which is heated to give the required electron emission by passing an electric current directly through it.

For low-power tubes such as those used in battery-operated equipment, such cathodes consisted of a fine wire consuming say 0.1 A at 1.4 V or 2 V and coated with metallic oxides to yield copious electron emission at a low temperature.

For tubes of higher power such as mains rectifiers the filament was often in the form of a tape consuming say 2 A at 5 V. For high-power transmitting tubes the filament is of pure tungsten or thoriated tungsten consuming up to several hundred amps at say 30 V.

file In *computers* and *data-processing equipment* a series of *bytes* given a unique identity (*filename*) for storage in a *filing system*.

fileserver A computer in a *Local Area Network* which incorporates a high-capacity *hard disk* on which storage space is provided for the users of the network. In practice some storage space may be declared 'public'; this contains files which any network user may access. Other storage space is dedicated to individual users of the network, access to these being protected by a password system. The fileserver may also control other shared resources such as a network *printer*.

filing system In computers and data processing equipment a system which stores *programs* and *data* as *files* in an orderly manner which permits their rapid location for retrieval. The storage media most commonly used are magnetic disks.

filter A *network* which passes signals with frequencies within certain bands (*passbands*) with little attenuation but greatly attenuates signals within other bands (stopbands). The block symbol for a filter is given at *Figure F.3*.



Figure F.3 Block symbol for filter

firing voltage The minimum direct voltage applied to a gas-discharge tube which will initiate the discharge.

firmware Software resident in *read-only memory* in a computer system.

first generation computer See *digital computer*.

fixed-point arithmetic, computation or representation In computers a form of presentation in which a number is displayed as a single set of digits, the decimal (binary or other) point being fixed in position with respect to the set.

fixed disk Same as *hard disk*.

fixed storage Same as *read-only memory*.

flag In computers and data-processing equipment a *bit* or *byte* used to signal the occurrence of a particular condition or event, e.g. an *error*.

flare In an optical or TV image, spurious areas caused by scattering of light in the camera or picture tube.

flash arc In an *electron tube* an arc between the *electrodes* causing a violent increase in cathode emission which, if maintained, can destroy the tube. The effect is thought to be caused by irregularities on electrode surfaces which cause local concentrations of electric field sufficient to ionise the residual gas.

flash EPROM A type of EPROM which can be erased and re-used. Unlike EEPROM, however, the whole memory chip must be erased at once. See *erasable, programmable, read-only memory*.

flashing Same as *reactivation*.

flashover *Arc discharge* between two conductors or between a conductor and earth caused by excessive voltage or a breakdown of the insulation. It may occur between the *electrodes* of an *electron tube*.

flash test Application for a brief period of a voltage considerably greater than the working voltage of a component or equipment to test its insulation resistance.

flat random noise A noise signal in which the components have approximately equal amplitudes over the frequency range of interest.



Figure F.4 Fletcher-Munson equal-loudness curves

Fletcher-Munson curves Equal-loudness curves plotted in terms of sound intensity and frequency (*Figure F.4*).

Each curve is an equal-loudness contour, i.e. it shows how the sound intensity necessary to give a particular value of loudness level varies over the audio band. The lower contours show that at low loudness levels considerably more power is needed to make very low frequency signals and very high-frequency signals as loud as signals around 1 and 2 kHz. This is another way of saying that the human ear is most sensitive at frequencies around 1 and 2 kHz.

As loudness level is increased, however, the contours become flatter showing that the sound intensity needed to give constant loudness does not vary greatly with frequency. In some audio amplifiers the volume control is made frequency discriminating to allow for the change in shape of the contours with change in loudness level.

The number of ***phons*** for each contour is numerically equal to the intensity level at the point where the contour crosses the 1-kHz ordinate; this stems from the definition of the phon.

flicker In TV, unwanted regular variation in the brightness of the reproduced picture. Flicker can be annoying when the ***field frequency*** is low and, in fact, this consideration sets a lower limit to the field frequency which can be used. It was for this reason that ***interlaced scanning*** was adopted because this permits a high field frequency (minimising flicker) whilst allowing a low picture frequency (minimising bandwidth).

flicker effect In *electron tubes*, random variations of the output current causing noise which is inversely proportional to frequency.

flip-flop (US) Same as *bistable circuit*.

floating Not connected to any source of potential. For example the potential of the open-circuited grid of an *electron tube* could be described as floating.

floating-carrier modulation A system of *amplitude modulation* in which the carrier is modulated in the normal manner and is simultaneously controlled by the envelope of the *modulating signal* so that the carrier amplitude is at all times just large enough to accommodate the modulation envelope.

Thus the *modulation depth* remains constant at nearly 100% no matter what the amplitude of the modulating signal. Such a system gives more efficient transmitter operation than if the carrier amplitude is kept constant as in conventional amplitude modulation.

floating-point arithmetic, computation or representation In computing a form of presentation in which a number x is displayed as two numbers y and z such that $x = yb^z$ where b is usually 2 or 10. y is known as the fixed-point part, z as the exponent and b is the base. As an example the number 12500000 could be written 125, 5 (representing 125×10^5).

floppy disk (diskette) A *demountable* data storage and distribution medium used in *microcomputers* and *word processors*. The magnetic disk is enclosed in a rectangular plastic sleeve which, on the earlier 8-inch and 5¼-inch disks, was flexible, hence the term *floppy*. The 3½-inch disks now most widely used are housed in rigid plastic cases which are more robust and incorporate a metal shutter over the aperture for the *read/write* heads, affording better protection against grease and dust. Each side of the disk carries 80 tracks spaced at 135 tracks per inch, giving a storage capacity, depending on the operating system and disk quality, of 720 kbytes, 800 kbytes, 1.44 Mbytes, 1.6 Mbytes or 2.88 Mbytes.

floptical disk and drive A magnetic *data storage* system using media which resemble 3½-inch *floppy disks*, but which use an optical track to allow more accurate tracking of the *read/write* heads. Storage capacity is 21 Mbytes per disk. The drive can also read and write to standard 3½-inch floppy disks.

flow angle Same as *angle of current flow*.

Floyd and Steinberg error diffusion See *dithering*.

fluctuation noise Same as *random noise*.

fluorescence The emission of light from materials irradiated by energy of a higher frequency or bombarded by *electrons*. The effect differs from *phosphorescence* in that the light emission lasts only for the duration of the stimulus.

flutter Distortion in sound reproduced from disk, film or tape and caused by undesired rhythmic speed variations on recording or reproduction. It is usually caused by eccentric or unbalanced driving of the film, tape or turntable. The variations occur at a rate exceeding approximately 20 Hz and cause a roughness in the sound quality. See *wow*.

flux A term used to describe a flow of particles, *photons* or the lines of force of an electric or magnetic field.

flux density The number of particles, ***photons*** or ***lines of force*** of an electric or magnetic field which pass through unit area of a surface normal to the direction of the beam or field.

flyback In ***cathode ray tubes*** the rapid return of the ***electron beam*** to its starting point at the end of each ***trace***. In TV there is a horizontal flyback at the end of each ***scanning line*** and a vertical flyback at the end of each field.

focusing In ***electron optics*** the process of converging the beam to minimum cross section (ideally to a small spot) on the target of the tube.

foldback A protective system for power suppliers which ensures, in the event of a sustained overload, that the output current is automatically reduced to zero thus reducing the possibility of damage to the supplier and/or to the load.

forbidden band In an ***energy-level diagram*** a range of electron energies lying between the permitted bands such as the ***conduction band*** and ***the valence band***.

No electron can have an energy corresponding to that of a forbidden band; it must have lower energy and be, for example, in the valence band or higher energy and be in the conduction band. Electron energy is therefore in steps and if sufficient energy can be given to electrons in the valence band to lift them into the conduction band, the element can be made conductive. See *Figure E.12*.

forced-air cooling A method of removing heat from a component or equipment by blowing air against it or against finned radiators in good thermal contact with it.

forced oscillation See ***oscillation***.

format (1) In data transmission the way in which the code characters are grouped into blocks. (2) A process known as *formatting* must be applied to magnetic storage media such as ***floppy*** and ***hard disks*** before they can be used to store data and programs. The process lays down the pattern of tracks (sometimes called ***cylinders***) divided into ***sectors*** which the ***operating system*** uses to locate files and to check for errors and also creates the ***root directory***.

form factor Of an alternating quantity the ratio of the root mean square value to the mean value of the positive or negative half cycle. For a sinusoidal ***waveform*** the RMS value is 0.71 ($1/\sqrt{2}$) and the mean value 0.63 of the peak value. The form factor is hence $0.71/0.63 = 1.11$.

Forth See ***computer language***.

FORTRAN See ***computer language***.

forward automatic gain control An AGC system in which the gain of ***transistors*** is reduced by use of forward control bias. An essential feature of the circuit is a resistor in the collector circuit (R_1 in *Figure F.5*) which causes the collector voltage to fall as the forward bias increases. The transistors used for this application are so designed that their collector characteristics become more crowded at low collector voltages thus decreasing gain.

forward current In a rectifier or ***semiconductor diode*** the current which flows through it in the forward direction.



Figure F.5 Essential features of a stage of amplification using forward automatic gain control

forward power dissipation In a ***semiconductor diode*** the power dissipated within the diode by the ***forward current***.

forward recovery time Of a ***semiconductor diode*** in a specified circuit the time taken for the ***forward current*** to reach a specified value after the application of forward voltage.

Foster-Seeley discriminator A detector for phase- or frequency-modulated signals in which the centre tap of the tuned secondary winding of a transformer is coupled to the primary winding and in which two ***diodes*** in series opposition are connected across the secondary winding, their net output giving the modulation-frequency output.

A typical circuit diagram of a Foster-Seeley discriminator is given in



Figure F.6 A typical Foster-Seeley discriminator circuit

Figure F.6. The effect of the two types of ***coupling*** between the primary and the secondary windings is that an increase in input-signal frequency from its unmodulated value causes the voltage at one end of the secondary winding to increase whilst that at the other end decreases. One diode therefore yields a larger output than the other. When the frequency of the input decreases from the unmodulated value this process is reversed and the second diode now gives the larger output and it is of opposite polarity to that of the first diode. Thus a modulation-frequency output is obtained from the detector.

A disadvantage of this form of discriminator is that it responds to amplitude modulation of the input signal. In a receiver therefore it must be preceded by one or more limiter stages to give protection against unwanted noise signals. See **amplitude limiter**.

Foucault current Same as ***eddy current***.

Fourier analysis A mathematical method of determining the number, ***amplitude***, ***frequency*** and ***phase*** of the components of a given repetitive complex waveform.

The French mathematician Fourier showed that any repetitive waveform could be synthesised by adding together a number of sinusoidal waves of suitable frequency, amplitude and phase. The frequencies of the waves are simple multiples of the repetition frequency (i.e. the fundamental frequency) of the original waveform.

four-quadrant multiplier A multiplier which operates normally irrespective of the sign of the input signal. See ***two-quadrant multiplier***.

fourth generation computer See ***digital computer***.

Fowler-Norheim tunnelling See ***EEPROM***.

fractal An image, usually mathematically generated, in which the detail appears similar at any level of magnification. A fern leaf provides an example from Nature of a fractal pattern. Fractal-based techniques offer exciting possibilities for data ***compression***.

frame (US) In TV and cinema film practice, one complete picture.

frame frequency (US) Same as ***field frequency***.

frame grabber Same as ***video digitiser***.

frame-grid tube An ***electron tube*** with a ***control grid*** of fine pitch, wound with fine wire and situated very close to the ***cathode*** so giving higher values of ***mutual conductance*** than is possible with grids of more conventional construction. Mutual conductances as high as 15 mA/V can be obtained in a small receiving tube by using frame-grid construction.

framing In digital data transmission systems a procedure used to ensure that the ***receiver*** can identify the subchannel to which each set of data belongs.

Franklin oscillator An ***oscillator*** in which the frequency-determining circuit is coupled via very small ***capacitances*** to the input and output of a two-stage ***electron tube*** amplifier. Because of the double phase inversion in the amplifier, the output is in phase with its input so giving the positive ***feedback*** necessary for oscillation. By making the coupling capacitances to the tuned circuit only just large enough to sustain oscillation the effect of the amplifier on the LC circuit can be minimised so giving good frequency stability. A circuit diagram of a Franklin oscillator is given in *Figure F.7*.

free oscillation See ***oscillation***.



Figure F.7 Circuit diagram of a Franklin oscillator

freeware ***Software*** which may be freely copied, distributed and used subject to conditions described in a text file that forms part of it. Unlike ***public domain software***, its originator retains the copyright and may demand payment if, for instance, a software distributor wishes to incorporate it or a part of it into a commercial package.

freeze frame (1) On a ***video tape recorder***, the facility to stop the tape temporarily during playback while the head continues scanning, thus producing a still picture. In practice this facility often has a time limit after which normal playback is resumed; this is to prevent excessive wear of the tape surface. (2) In computing, a system of primitive animation in which successive frames appear too infrequently to give the illusion of true movement.

frequency band In general the range of frequencies between specified upper and lower limits. In particular one of the following frequency ranges which are agreed internationally.

VLF	very low frequency	3–30 kHz
LF	low frequency	30–300 kHz
MF	medium frequency	300 kHz–3 MHz
HF	high frequency	3–30 MHz
VHF	very high frequency	30–300 MHz
UHF	ultra high frequency	300 MHz–3 GHz
SHF	super high frequency	3–30 GHz
EHF	extra high frequency	30–300 GHz

frequency changer A circuit which accepts a modulated signal at a particular carrier frequency and transfers the modulation to a different, usually lower, carrier frequency. Such circuits are used in ***superheterodyne receivers*** to transfer the modulation of all received signals to the intermediate frequency. Most frequency changers consist of an ***oscillator*** (at a frequency f_1), the output of which is fed, together with the input signal (frequency f_2), to a mixer stage the output of which contains the



Figure F.8 Block sumbol for a frequency changer

required difference frequency (f_1-f_2). Many practical frequency changers use separate ***active devices*** for oscillation and mixing although it is possible to make one device serve both purposes as in the ***self-oscillating mixer***. The block symbol for a frequency changer is given in *Figure F.8*.

frequency converter (US) Same as ***frequency changer***.

frequency deviation In angle modulation the peak difference between the instantaneous frequency of the modulated wave and the carrier frequency.

frequency discriminator Same as ***discriminator***.

frequency divider A circuit which accepts a signal with a frequency f and gives an output at a frequency f/n, where n is an integer. See ***counter***.

frequency division multiplex (FDM) The process of transmitting two or more signals along a common path by using different frequency bands for each of them. Each signal modulates a separate carrier and the carrier frequencies are spaced to avoid mutual interference between ***sidebands***.

frequency modulation (FM) Methods of modulation in which the frequency of the carrier wave is made to vary in accordance with the instantaneous value of the modulating signal.


(a) (b)

Figure F.9 (a) An unmodulated carrier wave and (b) the effect of frequency modulation

Figure F.9 (a) illustrates a carrier wave of constant amplitude and constant frequency and *Figure F.9* (b) shows the effect of frequency modulation. The amplitude of the modulating signal determines the extent of the change in carrier frequency and the frequency of the modulating signal determines the number of times per second the carrier frequency is swept above and below its nominal value.

Frequency modulation is used in sound broadcasting in the VHF bands and in most TV broadcasting services for the associated sound channel. An important feature of frequency modulation is that the carrier amplitude is unaffected by modulation: thus by making frequency modulation receivers immune to amplitude changes in the received signal much interference can be eliminated so making frequency-modulated reception noise-free.

frequency multiplier A circuit which accepts a signal with a frequency f and gives an output at a frequency nf, where n is an integer. The commonest examples of frequency multipliers are frequency doublers and frequency triplers.

One form of frequency multiplier is a device with a markedly non-linear input-output characteristic (e.g. an ***active device*** operating in class C). This generates an output rich in harmonics of the input frequency and the desired component can be selected by a circuit resonant at the required frequency.

frequency pulling The displacement of the frequency of an oscillator towards the frequency of an external applied signal. The effect becomes more marked as the frequency of the applied signal approaches that of the oscillator.

frequency range The range of frequencies over which a component or equipment operates satisfactorily. For example an AF amplifier may have a frequency range of 30 Hz to 15 kHz.

frequency response The variation in output amplitude of a component or equipment as the frequency of a constant-amplitude input is varied over the working frequency range of the equipment. The response is usually displayed as an amplitude/frequency curve and shows up any ***attenuation distortion*** of the equipment.

frequency shift keying (FSK) A form of ***frequency modulation*** in which, without interrupting the carrier, its frequency is switched between two predetermined values termed the mark and space frequencies.

frequency stability A measure of the constancy of the frequency of an oscillation. The frequency stability of an oscillator is important in many applications, e.g. when it is used as the carrier source in a ***transmitter*** which must stay on its assigned carrier frequency within very close tolerance.

frequency standard A highly stable ***crystal-controlled oscillator*** the output of which can be calibrated against National Standard Frequency radio transmissions.

frequency swing In ***angle modulation*** the difference between the maximum and minimum values of the instantaneous frequency of the modulated wave.

fringing Distortion of the ***electric field*** at the edges of a parallel-plate capacitor. The ***lines of force*** are normal to the plates over most of the area of the plates but at the edges they tend to bulge outwards, a feature that may be important in the design of electrostatic deflecting plates in a ***cathode ray tube***.

front end (1) Of an equipment, that section of it which handles the ***input*** signal(s). (2) Of a computer ***application***, the user interface, i.e. the screen display and input facilities with which the user interacts.

front porch In a TV signal the period of ***blanking level*** immediately preceding the ***line sync signal***. See *Figure F.10*.

full adder Same as ***adder***.

full motion video Smooth animation in a full-colour picture occupying the whole screen. This contrasts with the jerky ***freeze-frame*** animation or fractional-screen pictures offered in some computer animation systems.

full radiator An ideal radiator and absorber of radiation. Its radiation in any part of the spectrum is the maximum obtainable from any radiator at the same temperature. The nearest practical form of full radiator is a cavity with opaque walls maintained at a constant temperature and with a small opening for observation. It was formerly known as a black-body radiator.

full-wave rectification Rectification in which power for the load is taken



Figure F.10 Front porch of a television signal

from the AC supply during both half-cycles of the supply. One circuit for a full-wave rectifier is given in *Figure F.11*. Diode D_1 conducts during positive half-cycles of the secondary voltage and diode D_2 during negative half-cycles, the diodes being so connected that current flows through the load in the same direction during both half-cycles. As shown in *Figure F.12* a bridge arrangement of rectifiers is often used for full-wave rectification, this circuit avoiding the need for a centre tap on the transformer secondary winding.



Figure F.11 A full-wave rectifier using a centre-tapped transformer



Figure F.12 A full-wave rectifier using a bridge rectifier

function In computing, a ***subroutine*** which is named and which returns either a numeric value or a character string. The usefulness of functions lies in that, once defined, they can be treated in much the same way as ***variables***; for example, an instruction to display a function executes the code in the function and then displays the value it has returned.

function keys On a ***computer keyboard*** the keys normally numbered F1 to F12 (and sometimes to F24). They have no fixed function, but ***operating systems*** and ***programs*** may assign temporary functions to them. For example, F1 is often used to call up an ***on-line help*** system.

fundamental frequency Of a regular complex ***waveform*** the repetition frequency of the wave.

Fourier analysis of a complex wave yields a series of components the frequencies of which are multiples of the repetition or fundamental frequency of the wave. It is possible for the fundamental frequency component to be missing but in a complex sound signal it is the fundamental frequency, whether present as a discrete component or not, which determines the pitch of the sound.



Figure F.13 Graphical symbol for a fuse

fuse A protective device which heats and melts so interrupting a circuit when the current exceeds a certain value which depends on the material and the cross-sectional area of the fuse. The graphical symbol for a fuse is given in *Figure F.13*.

G

gain In general an indication of the extent to which the amplitude of a signal is increased by its passage through an electronic system or part of it. More specifically the ratio of the output-signal power, voltage or current to the input-signal power, voltage or current. The ratio is usually expressed in decibels as

$$10 \log_{10}\frac{P_{out}}{P_{in}};\ 20 \log_{10}\frac{V_{out}}{V_{in}};\ \text{or } 20 \log_{10}\frac{I_{out}}{I_{in}}$$

gain-bandwidth product Of an ***active device*** a figure of merit assessing its usefulness as a wideband amplifier. A given active device can give a particular value of ***gain*** over a particular value of bandwidth and if the bandwidth is changed the gain is changed in the inverse ratio so that the product remains constant. For an ***electron tube*** the gain-bandwidth product is proportional to $g_m/(C_{in} + C_{out})$, where g_m is the mutual conductance, C_{in} the input capacitance and C_{out} the output capacitance. Thus for wideband applications, tubes with high mutual conductance and low input and output capacitances should be chosen.

gallium arsenide (GaAs) A ***semiconductor*** material in which the electron mobility is better than that of silicon. This makes the material suitable for use in microwave transistors (MESFETs) and for high-speed operations in computers. GaAs also has the property that the electrons can exist in two states as described under ***Gunn effect***. GaAs is also used in LEDs.

galvanometer An instrument for the detection and measurement of very small electric currents. In one type the current passes through a rotatable coil situated in the field of a permanent magnet. The resultant magnetic interaction causes the coil to rotate against the restoring force of a spring, so moving a pointer or a small mirror which reflects a narrow beam of light across a scale.

gamma (γ) In TV a factor expressing the relationship between the contrast in the reproduced image and that in the original scene. Quantitatively it is the slope of the curve of output ***luminance*** plotted against input luminance, both being plotted on logarithmic scales. As shown in *Figure G.1* the overall gamma is given by the slope of the chord connecting two points P and Q which define the length of the characteristic used in the system. Thus overall gamma is given by

$$\gamma = \frac{\log R_2 - \log R_1}{\log S_2 - \log S_1}$$

where R_1 and R_2 are the luminances of the two points in the reproduced image and S_1 and S_2 are the luminances of the corresponding points in the original scene.



Figure G.1 Distinction between overall gamma and point gamma

For a colour TV system the overall gamma should be unity but for black-and-white television where the contrast due to colours is absent an overall gamma of slightly greater than unity, say, 1.2, is recommended.

Because of the curvature of the characteristic the gamma as measured by the slope of the curve can differ appreciably from the overall value. Thus point gamma or contrast gradient at a given point in the characteristic is measured by the slope of the tangent to the point and it is useful to know its value because it measures the visibility of detail in tonal values in the image corresponding to the point. For example in *Figure G.1* the tangent AB measures the point gamma in low-light areas of the image and clearly this gamma is less than the overall gamma, suggested that perhaps some 'black stretching' may be desirable.

gamma rays ***Electromagnetic waves*** similar to ***X-rays*** and of approximately the same frequency emitted from radioactive atoms during disintegration.

ganging Simultaneous adjustment of two or more circuits by a common mechanical control. In a stereo amplifier, for example, operation of the gain control simultaneously adjusts the gain in both channels. In a ***superheterodyne receiver*** tuning of the oscillator and RF circuits is simultaneously adjusted by a single control.

gas amplification factor Of a gas-filled photocell the ratio of the sensitivity with and without ***ionisation*** of the gas.

gas current In a ***vacuum tube*** the flow of positively-charged ***ions*** to a negatively-charged electrode. The ions are produced by ionisation of residual gas by the electron current of the valve.

gas discharge The conduction of a current between two cold electrodes in an ionised gas tube when the potential difference between them is made sufficiently high.

gas-filled rectifier A ***gas-filled tube*** used as a rectifier. The term is a general one which embraces tubes with a mercury-pool cathode or an indirectly-heated cathode; the anode current may or may not be controlled by a third electrode.

gas-filled tube A tube of which the electrical properties are dependent upon the ***ionisation*** of gas deliberately included in the envelope.

gas-filled valve Same as ***gas-filled tube.***

gas focusing In a ***cathode ray tube*** focusing of the electron beam by allowing a trace of gas to remain in the envelope. The electron beam ionises the gas and the positive ***ions*** so released set up a field which counteracts the mutual repulsion between the beam electrons and concentrates the beam into a convergent form.

gas tube Same as ***gas-filled tube.***

gate (logic) See ***logic gate.***

gate (semiconductor) In a ***field-effect transistor*** the ***electrode*** to which the signal voltage is applied to control the effective width and thus the resistance of the ***channel.*** In a ***thyristor*** the electrode to which the control signal is applied to switch the device to the on-state (and in some devices to the off-state).

gate array See ***Application Specific Integrated Circuit.***

gated-beam tube A ***pentode*** designed to operate as a self-limiting phase-difference discriminator in FM receivers, the input signals from the primary and secondary windings of the IF transformer being applied to the control grid and suppressor grid. The tube operates in the same manner as a ***nonode*** and the electrodes are laid out in a manner quite dissimilar to those of a conventional pentode in order to achieve the type of limiting action required at the ***grids.***

gate turn-off switch A ***semiconductor*** device combining the voltage- and current-carrying capacities of the ***thyristor*** with the control of the transistor. It is a four-layer device which can be switched on and off by signals applied to the gate.

Gaussian distribution For a quantity which varies statistically about a mean value the shape of the curve which shows, for any chosen value, the probability of a sample having that value. If a very large number of observations of the quantity are taken and if, for a number of discrete values, the number of observations having each value are plotted, a curve of the shape of *Figure G.2* is obtained.

This is often known as a probability curve and it shows that the number of observations having a value markedly different from the mean value is very small but that the number increases as the value selected approaches the mean value.

Geiger-Muller tube ***Electron tube*** used for the detection of alpha or beta particles or ***gamma rays.*** The tube consists of a fine wire anode surrounded by a co-axial cold-cathode cylinder, the intervening space being filled by gas at a low pressure. The voltage between anode and cathode is adjusted to just below the ionising potential of the gas. When any of the radiations to



Figure G.2 Gaussian distribution curve

be detected enters the tube it causes momentary ionisation of the gas so that a pulse of current flows through the tube. These pulses are usually transferred to a counter circuit to form a Geiger counter equipment.

geometric distortion In television any displacement of picture elements in a reproduced image from the correct positions, i.e. those of the corresponding elements in the original scene.

Germanium (Ge) A tetravalent crystalline element (atomic number 32) widely used in the manufacture of ***semiconductor*** devices. In its pure state the element is an insulator but by suitable doping p- or n-type conductivity of a value suitable for semiconductor devices can be obtained. Germanium devices have a significant ***leakage current*** at normal temperatures making them liable to ***thermal runaway*** and have to a large extent been superseded by ***silicon*** devices.

getter A material included in a ***vacuum tube*** to remove traces of gas remaining after pumping and sealing or which may be released when the tube is put into use. The most commonly-used getter is barium and after the tube is sealed a pellet of the material is vapourised by eddy-current heating and condenses on the walls, combining with the remaining gas as it does so.

glitch Distortion of a pulse waveform in the form of a short-duration disturbance. A typical example is shown in *Figure G.3*.



Figure G.3 An example of glitch

glow discharge In a *gas-filled tube* with a cold cathode, conduction as a result of electronic emission caused by bombardment of the *cathode* by positive *ions*. There is usually weak emission of light.

Gouriet oscillator Same as *Clapp oscillator*.

graded-base transistor A *bipolar transistor* in which the impurity concentration in the base region increases smoothly between the *collector* and *emitter* junctions.

Such a graded concentration, which can be produced by *diffusion*, gives an electric field which speeds up the passage of charge carriers across the base region, so reducing *transit time* and improving high-frequency performance.

gramophone Dated term for a disk player.

graphic equaliser An audio *equaliser* in which the audio *spectrum* is divided up into a number of contiguous bands which are individually amplified, adjustment of the gain controls permitting any desired shape of *frequency response* to be obtained. The frequency bands may be one octave or one third octave in *bandwidth* and the gain controls are usually slider types so arranged that a level frequency response is obtained when the controls are in line. When the sliders are moved, their positions give an indication of the shape of the frequency response of the equaliser.

graphical user interface (GUI) A user interface for a computer system in which most routine operations are performed graphically, i.e. using a *mouse* or other *pointing device* to move a *pointer* on to *icons* on the screen instead of typing textual commands. For example, to copy a file from one directory to another typically involves displaying *windows* representing the source and destination directories, selecting the *icon* in the source directory that represents the file to be copied and dragging this into the destination directory.

graphics In computing, matter appearing on a *VDU* or in a *printout* apart from text in the computer's or printer's regular typeface (font). Usually such graphics consist of pictures, diagrams or rules, boxes, borders or other embellishments. There are two principal systems for creating and editing graphics using a computer.

In *bitmap* graphics (also called *raster graphics*) images are stored as a two-dimensional array of *pixels*. Examples include the output from *scanners* and *video digitisers*. *Applications* for creating and editing bitmaps are sometimes called *painting* software, since ultimately they are concerned only with the colours of areas of pixels. Such applications often feature sophisticated tools for creating lines and shapes in a selected colour and for *image processing*, that is, subjecting the whole or part of the image to some change of colours or dimensions.

The alternative system is *vector graphics*, in which the image is stored effectively as a sequence of co-ordinate-based data describing the lines and shapes of which the image is composed. Applications for creating and editing vector graphics are sometimes called *drawing* software, since it is essentially line-based. Advantages of vector graphics are that the stored image is independent of the output device, it is easy to edit and scale and it may have more than two dimensions. Three-dimensional drawing packages are widely used, for example to create the mathematical models that form the basis of ***virtual reality***. Even two-dimensional packages may divide a drawing into a number of superimposed layers which can be turned on and off individually to show different aspects of the subject, such as the various utilities in a map of a city. ***Computer-aided design*** packages are usually vector-based.

In computers that use a ***graphical user interface***, however, it is common practice for ***text*** to be reproduced on the screen or in printouts in industry-standard typefaces (fonts) that have been stored in the computer as vector graphic images (see ***outline fonts***) and are subsequently rendered using graphical routines rather than textual routines.

graphics accelerator An ***expansion card*** that accelerates a computer's handling of ***graphics*** on the screen. Some accelerators provide a separate ***microprocessor*** dedicated to handling screen output, freeing the main processor for the application task. Others use a variety of techniques to circumvent the more processor-intensive aspects of writing to the screen.

Graphics Interface Format (GIF) A ***bitmap file*** standard originally developed for use in ***bulletin board systems***. It incorporates ***LZW*** compression, substantially reducing most file sizes and therefore also the time taken to transmit the image over costly leased lines. Its disadvantage is its limitation of 8 bits per pixel and it is now being superseded to some extent by ***JPEG*** which offers 24 bits per pixel and even higher compression factors.

Gray code A binary code in which the codes for any two consecutive numbers differ by only one binary digit.

grid An ***electrode*** located between the cathode and the anode of an ***electron tube*** and through the interstices of which the main electron stream of the tube passes.

A tube may have a number of grids (e.g. a ***pentode*** has three) and each usually has the form of a wire spiral surrounding the ***cathode***, the electron stream passing through the meshes of the spiral. The pitch of the spiral is chosen to give the required degree of control over the density of the electron stream.

grid base Of an ***electron tube*** the range of grid voltage between zero and that which gives cut off of anode current. This is illustrated in *Figure G.4*. The grid base depends on the value of anode and screen-grid voltages and these should be stated when values of grid base are quoted. The value of the grid base gives an indication of the maximum peak-to-peak signal input voltage the tube can accept under ***class-A*** conditions.

grid bias (GB) Of an ***electron tube*** the steady voltage applied to the control grid to ensure that signal excursions operate over the required region of the characteristic. The value of the grid bias depends on the anode and screen-grid voltages and these should be stated when values of grid bias are quoted. In ***class-A*** operation the grid bias voltage is chosen to give an operating point near the centre of the most linear part of the characteristic.

grid characteristic Of an ***electron tube*** the relationship between grid voltage and grid current exhibited graphically.

grid emission Of an ***electron tube*** the emission of ***electrons*** or ***ions*** from the grid. This can arise as a result of heating of the grid (primary grid emission) or of bombarding it by electrons or ions (secondary grid emission).



Figure G.4 The grid base of an electron tube

grid leak Dated term for a ***resistor***, usually of high value, connected to the control grid of an ***electron tube*** and used to apply ***grid bias***.

grid-leak detector An AM detector in which the control grid and cathode of a triode or multi-grid ***electron tube*** operate as a ***diode detector***, the AF output being amplified by the tube.



Figure G.5 The circuit diagram of a grid-leak detector

One possible circuit for a grid-leak detector is given in *Figure G.5*. The output of the ***diode detector*** is the voltage generated across C_1 and this provides the tube with ***grid bias*** and also with the AF input signal. Clearly only for one particular value of input signal will the direct component across C_1 be the optimum value of grid bias. In general, therefore, the detector gives considerable ***harmonic distortion*** but with the aid of ***reaction*** it can be made very sensitive and it was very popular in the early days of radio.

grid stopper See ***parasitic stopper***.

ground (US) Same as ***earth***.

grounded-anode, -base, -emitter, -grid, etc circuit Literally a circuit in which the anode, base, emitter grid, etc is earthed but the term is generally used to mean a common-anode, common-base, common-emitter, common-grid circuit, etc.

ground loop Same as ***earth loop.***

ground return Same as ***earth return.***

group code An ***error-detecting code*** used to verify correct transmission of a group of characters.

group delay Same as ***envelope delay.***

group velocity Same as ***envelope velocity.***

grown transistor An early method of manufacturing ***bipolar transistors*** by 'pulling' a ***crystal*** from the molten ***semiconductor*** material, the required p- and n-regions being formed in the crystal by introducing pellets of appropriate impurity into the molten material as the crystal is withdrawn.

guard band A ***frequency band*** between neighbouring ***channels*** which is left vacant to give a margin of safety against mutual interference.

Gunn effect The splitting of ***charge carriers*** into domains by a steady electric field. In certain ***semiconductors,*** typically ***gallium arsenide,*** electrons can exist in a high-mass low-velocity state as well as their normal low-mass high-velocity state and they can be forced into the high-mass state by a steady electric field of sufficient strength. In this state they form clusters or domains which cross the field at a constant rate so that current flows in a series of pulses. This can be made the basis of a microwave oscillator. See ***Gunn-effect diode.***

Gunn-effect diode A semiconductor device used as a microwave oscillator. It is not, strictly speaking, a diode, consisting of an ***epitaxial*** layer of n-type ***gallium arsenide*** grown on a GaAs ***substrate.*** Ohmic contacts are made to the substrate (anode) and the n-layer (cathode). A potential of a few volts between anode and cathode produces an electric field causing electrons to cross the device in clusters or domains (see ***Gunn effect***). Thus the current is in the form of pulses with a frequency dependent on the transit time and hence on the thickness of the n-layer. In use the device is mounted in a ***cavity resonator*** and powers up to 1 W at frequencies between 10 and 30 GHz are possible. Certain other semiconductor materials can also be used in Gunn-effect diodes.

H

hacking Colloquial term for the deliberate gaining of unauthorised access to private computer systems over the telecommunications network. For some hackers this is simply an intellectual challenge; others cause serious problems by tampering with confidential stored data or by making fraudulent use of the data accessed.

halation In a ***cathode ray tube***, degradation of the image caused by an area of light surrounding the spot where the ***electron beam*** strikes the screen. This unwanted area is caused by light from the spot reaching the screen by reflection at the front and rear surface of the faceplate of the tube.

half-adder In logic circuitry a combination of logic elements with two inputs and two outputs so related that one output is the sum of the two inputs and the other is an exclusive-OR function of the two inputs. Two such circuits can be combined to form a ***full adder*** which can perform binary addition. See ***exclusive-OR gate***.

half-duplex operation Of a telegraph system, a ***duplex*** system permitting operation in either direction, but not in both directions simultaneously.

half-section Of a filter. See ***ladder network***.

half-wave rectification Rectification in which power for the load is taken from the AC supply only during alternate half-cycles of the supply. A typical circuit for a half-wave rectifier is given in *Figure H.1*.



Figure H.1 A simple circuit for half-wave rectification

Hall constant (or **coefficient**) Factor relating the voltage generated as a result of the ***Hall effect*** with the product of the current and the magnetic field.

Hall effect The production of a transverse EMF in a current-carrying conductor or semiconductor subjected to a ***magnetic field***. When a conductor or a semiconductor carrying a current is subjected to a magnetic field perpendicular to the direction of current flow a voltage proportional to the current and to the magnetic field is generated across the faces of the conductor perpendicular to the direction of current flow and to the direction of the magnetic field.

Hamming code In digital transmission a code so designed that errors in signals can be detected and corrected. See ***parity check***.

Hamming distance Same as ***signal distance***.

handset An instrument containing a ***microphone*** and an ***earphone*** designed to be hand held, as in the familiar telephone instrument.

hard copy In data processing a copy of a document on paper or similar material, in contrast with a copy on magnetic media such as a floppy disk or in some electronic format. Hard copy is so called because, once committed to paper, it cannot be easily changed; in contrast, a file in a data storage medium, such as a hard or floppy disk, can be readily edited.

hard disk (or hard drive) A data storage system consisting usually of several magnetic disks on a common spindle and sealed with their ***read/write*** heads in a container. The disks are rigid and double-sided, each surface having its own read/write head. To minimise wear, the heads do not contact the disk surface, but are suspended very close to it, the sealed container preventing the ingress of dust which would have a catastrophic effect on the drive's reliability. Physical drive sizes vary widely. Storage capacities range from 20 Mbytes to 10 Gbytes and data transfer is significantly faster than that available from ***floppy disks*** or ***CD-ROMs***. Hard disks are sometimes called *fixed disks* because, in contrast with floppy disks, they are usually fixed permanently in computers where they are used for the storage of commonly used ***software***, such as ***operating systems*** and ***applications***. This software is transferred on to the hard disk from floppy disks, CD-ROMs, tape streamers or over a network. There are, however, some ***demountable*** hard disks. In these the sealed container housing the disks and heads slides out of the drive assembly containing the motor and control electronics. These are used not only for software storage, but also for the distribution of large collections of software.

hard valve Same as ***vacuum tube***.

hardware Term used particularly in computer technology to describe the electronic equipment, its circuits and components. See ***software***.

hardware key A device used to protect a ***software*** package against unauthorised copying. Also known as a *dongle*, the device is plugged into a computer ***port***, often the parallel printer port; the printer is connected to a printer port on the hardware key itself. At start-up the protected software checks for the presence of coded data in the hardware key; if it is absent, the application is terminated. Since the software cannot be used without a suitable hardware key, unauthorised copies of it are useless. The hardware key itself is far more difficult to copy than the software it protects.

harmonic analyser Equipment for measuring the amplitude and phase of the ***harmonic components*** of a complex waveform. It is usually mechanical in nature.

harmonic component Of a complex waveform, one of the components with a frequency equal to a multiple of the fundamental frequency. The analysis of a complex waveform into its harmonic components can be carried out mathematically by ***Fourier analysis*** or practically by use of a ***harmonic analyser***.

harmonic distortion Distortion arising from the non-linearity of the input-output characteristic of a system, equipment or component and resulting in the production of new signals at harmonics of the frequency of a sinusoidal input signal.

harmonic generator Same as ***frequency multiplier***.

Harries tetrode Same as ***critical-space tetrode***.

Hartley oscillator A sinusoidal oscillator in which the frequency-determining element is a parallel-tuned LC circuit connected between the input and output terminals of a ***active device***, ***positive feedback*** being obtained by connecting a tapping on the inductor to the common terminal (***cathode***, ***emitter***, ***source***) of the active device. *Figure H.2* gives the circuit diagram of a transistor Hartley oscillator.



Figure H.2 A transistor Hartley oscillator



Figure H.3 Hay bridge

Hay bridge A bridge circuit generally used for the measurement of inductance in terms of capacitance, resistance and frequency. It differs from the Maxwell bridge in that the capacitor is in series with its associated resistor as shown in Figure H.3. The conditions for balance are:

$$L = R_2R_3\frac{C}{1+\omega^2C^2R_4^2}$$

$$R_1 = R_2R_3\frac{\omega^2C^2R_4}{1+\omega^2C^2R_4^2}$$

head A device which records information on a storage medium, reproduces the information or erases it. The storage medium may be tape, film or disk and the information may be in digital form as in ***data-processing*** equipment or may be in analogue form as in audio and TV ***recording***.

head amplifier An audio or video amplifier incorporated in a ***microphone***, ***television camera*** or motion picture projector to raise the level of the output signal before it is sent along a cable. This technique is used as a means of improving the ***signal-to-noise ratio***.

headphones An electro-acoustic ***transducer*** designed to feed sound directly into the ear and mounted on a headband. Some headbands carry only one transducer so as to leave one ear free. Others carry two transducers which are connected in series or in parallel for monophonic reproduction or can be connected to the two channels of stereo equipment for stereophonic reproduction.

headset A combination of headphone and microphone mounted on a headband and used for two-way communications by, for example, telephone operators and aircraft pilots.

hearing aid An equipment consisting of a ***microphone***, an ***audio amplifier*** and an ***earphone*** and powered by an internal battery which allow persons suffering hearing deficiency to take part in normal conversations and to enjoy radio and television broadcasts. Modern hearing aids are extremely small and can be hidden behind or within the ear. Many also feature a pick-up coil which may be selected instead of the microphone for use in a theatre, church or other auditorium fitted with an ***induction loop***.

heater In general any ***resistor*** carrying current and used to supply heat. In particular the resistor which supplies the heat necessary for ***thermionic emission*** from an indirectly-heated ***cathode***. The heater is usually a tungsten wire contained within the cathode cylinder but electrically insulated from it.

heat sink A metal structure arranged to be in intimate thermal contact with a heat-generating component such as a power transistor to aid heat dissipation and so limit temperature rise in the component. To be efficient a heat sink requires adequate thermal capacity (mass × specific heat). It should also be a good conductor of heat and have large surface area. Often heat sinks are finned to increase surface area.

Heising modulation A circuit for ***amplitude modulation*** in which the ***anodes*** of a modulation-frequency amplifier and a carrier-frequency amplifier are coupled and fed via a common inductor with a high reactance at modulation frequencies.

If the carrier-frequency amplifier operates in ***class C*** its output is proportional to its HT supply voltage. If, therefore, the HT voltage is varied by the modulation-frequency amplifier, amplitude modulation can be achieved. When the anode current of one tube is instantaneously high, that of the other is low and in fact the sum of the two currents is constant. The circuit is sometimes called constant-current modulation.

The basic circuit described here is, in practice, modified to enable very deep modulation to be achieved without excessive distortion, e.g. by the use of a transformer in place of a choke.

Helmholtz resonator A cavity open to the external environment via a small aperture in the cavity wall. Such an arrangement resonates at a frequency dependent on the dimensions of the cavity. Helmholtz resonators are used extensively as tuned elements for electromagnetic waves in microwave tubes such as ***klystrons***. The vented enclosures used in loudspeaker designs and the tuned absorbers used in acoustic treatment of sound studio walls are also examples of Helmholtz resonators.

Henry The unit of self-inductance or mutual inductance, symbol H. An inductor is said to have an inductance of 1 H when a current in it, changing at the rate of 1 A per second, generates a voltage across it of 1 V. Practical inductors have inductances ranging from many H to fractions of a μH.

heptode An ***electron tube*** with five grids situated between cathode and anode. It was usually used as a ***frequency changer***, the first two grids acting together as the grid and anode of the oscillator. Grids 4 and 5, together with the anode, constitute an RF ***tetrode*** acting as an RF mixer. Grid 3 is a screen to minimise capacitive interaction between oscillator and mixer sections. Mixing occurs by virtue of the oscillator-frequency component impressed on the electron stream by grids 1 and 2. However the signals on these grids are usually in antiphase and their effects on the electron stream are therefore mutually destructive. To minimise this effect grid 2 is not of conventional construction but may take the form, for example, of a number of rods which can carry sufficient current to sustain ***oscillation*** but have little modulating effect on the electron stream. Because grids 3 and 5 both function as ***electrostatic screens*** they are often connected together inside or outside the tube.

The graphical symbol for a heptode is given in *Figure H.4* which also indicates the function of each grid.



Figure H.4 Graphical symbol for a heptode indicating the function of each grid

heterodyne The process of combining two signals of different frequencies so as to produce an output at the sum or difference frequency. The process is thus equivalent to non-linear additive mixing or multiplicative mixing. The process is extensively used in sound and TV receivers where the received signal is combined with the output of the local oscillator to produce a difference term at the intermediate frequency. Because the difference frequency is above audibility this type of receiver is known as a supersonic heterodyne, abbreviated to ***superheterodyne*** or superhet.

Hertz The unit of frequency and equal to 1 cycle per second, symbol Hz. The multiple units of kilohertz (kHz), megahertz (MHz) and gigahertz (GHz) are commonly used in electronics.

hexadecimal (hex) A counting scale containing sixteen digits, each digit in a number representing a power of sixteen. Conventionally the digits of the hexadecimal scale are represented by the decimal numbers from 0 to 9 followed by the letters A to F. Thus the decimal equivalent of the hexadecimal number 5A6 can be evaluated in the following manner:

$$\begin{aligned}5A6 &= 5\times 16^2 + 10\times 16^1 + 6\times 16^0\\ &= 5\times 256 + 10\times 16 + 6\times 1\\ &= 1280 + 160 + 6\\ &= 1446\end{aligned}$$

Hexadecimal numbers are often used as a shorthand method of writing binary numbers. The base 16 of the hexadecimal scale is 2^4 and this facilitates conversion between the hexadecimal and the binary scales. Each four digits of a binary number can be uniquely represented by one digit of a hexadecimal number. For example an 8-bit byte such as 01101100 can be represented by the two-digit hexadecimal number 6C, both having a decimal equivalent of 108. Similarly a 16-bit binary word can be represented by a four-digit hexadecimal number.

hexode An *electron tube* with four grids between cathode and anode. The tube may be regarded as an RF *tetrode* (grid 4 being the screen grid) with two *control grids* (1 and 3) separated by a *screen grid* (2) to minimise *capacitive coupling* between the two inputs. Grids 2 and 4 may be connected together inside or outside the tube.

The tube was designed for use as an RF mixer, the oscillator and signal-frequency inputs being applied to grids 1 and 3. The tube is often combined with a triode oscillator in a single envelope to form a triode-hexode frequency changer.

The graphical symbol for a hexode is given in *Figure H.5* which also indicates the function of each grid.



Figure H.5 Graphical symbol for a hexode indicating the function of each grid

hi-fi, high-fidelity A vague term used to describe audio equipment in whose design some effort has been made to ensure that sound is reproduced with minimal distortion.

high-definition television (HDTV) A colour television system providing wide-screen flicker-free pictures with a resolution comparable to that of 35-mm cinematograph film. Considerable research has been invested in the development of such systems using a 16:9 *aspect ratio* and 1125 lines, but there are difficulties in establishing standards that are acceptable worldwide.

high frequency resistance Same as *effective resistance* (2).

high level modulation Same as *high-power modulation*.

high-noise-immunity logic (HNIL) A form of logic similar to *diode-transistor logic* but including a zener diode to increase voltage levels. It is largely obsolete.



Figure H.6 Block symbol for a high-pass filter

high-pass filter A ***filter*** designed to pass signals at frequencies above a specified ***cut-off frequency***. Thus the passband extends from the cut-off frequency to an infinitely-high frequency. In general such filters comprise series capacitors and shunt inductors. The block symbol for a high-pass filter is given in *Figure H.6*.

high-power modulation In an AM transmitter ***amplitude modulation*** of the carrier by introducing the ***modulating signal*** into the anode circuit of the final amplifying stage. The power of the modulating signal thus approximates to that at the transmitter output. See ***low-power modulation***.

high tension (HT) The high-voltage supply required for the ***anodes*** and ***screen grids*** of ***electron tubes***. In battery-operated equipment the HT supply was commonly between 45 V and 90 V but in mains-operated equipment supplies for early stages were often about 200 V and for output stages up to 500 V.

high threshold logic (HTL) Same as ***high-noise-immunity logic***.

highway Same as ***bus***.

H-network A five-element network in which both legs contain two elements in series, a shunt element bridging their junctions as shown in *Figure H.7*. It can be regarded as a balanced form of ***T-network***.



Figure H.7 An H-network

hold control In early TV receivers the controls which determined the free-running frequency of the line and field ***time bases***. The controls were adjusted to bring the time-base frequencies into the range at which the time bases lock at the frequencies of the line and field synchronising signals. Hence receivers had two hold controls: line or horizontal hold; field or vertical hold. Modern receivers do not have hold controls.

hole A deficiency of one ***electron*** in the atomic structure of an atom in an ***extrinsic semiconductor***. As a result of this deficiency the atom has a net positive charge equal to that of an electron and neutralisation of such charges by electrons can give rise to a current in the form of a unidirectional movement of holes as described under ***p-type semiconductor***.

hole conduction The process by which current flows through a ***p-type semiconductor***.

hole injection The basic process underlying the action of ***pnp transistors***. The base-emitter junction is forward-biased and the current which flows between these regions is largely carried by holes moving from emitter to base. These enter the very thin ***base region*** and are swept into the ***collector region*** by the collector-base voltage so giving rise to a considerable collector current. It is the holes injected into the base region from the emitter region which are responsible for the collector current.

hole storage The process which causes the collector current of a ***pnp transistor*** (which has been driven hard into conduction) to continue for a brief period after the emitter current has been cut off. When the transistor has been driven hard on, the emitter injects into the base region more holes than are required to give the collector current and the excess holes are stored ready to be swept into the collector region to prolong the collector current when the emitter current has been cut off. See ***carrier storage***.

homodyne A system of ***heterodyne*** reception in which the received signal is mixed with another at the carrier frequency of the signal and derived from the received signal. Thus there is no local oscillator as in normal heterodyne reception.

horizontal amplifier In oscilloscopes the circuits which amplify the signals responsible for horizontal deflection of the beam. Also known as an *X* amplifier.

horizontal blanking Same as ***line blanking***.

horizontal hold See ***hold control***.

horizontal polarisation Property of an electromagnetic wave in which the plane of polarisation of the electric field is horizontal.

horizontal time base In a ***cathode ray tube*** the circuits generating the signals which give horizontal deflection of the beam. In TV this is usually termed the line time base.

host The computer controlling a ***network***. More specifically, the ***mainframe*** or other large computer served by a network of ***terminals*** or the computer running a ***bulletin board*** or other communications system to which other computers are temporarily connected for data exchange purposes.

hot carrier diode Same as ***Schottky diode***.

hot-electron diode Same as ***Schottky diode***.

hot spot (1) In tubes with a ***mercury-pool cathode*** a small heated area formed on the mercury surface by the ignition electrode and which initiates the discharge. (2) In a high-power ***electron tube*** a small heated area on the ***anode***.

H-parameters Same as ***hybrid parameters***.

HSV colour model See ***colour model***.

hue That quality of a colour which enables it to be classified as red, green, blue, etc. For colours appearing in the ***spectrum***, hue can be quantitatively defined by quoting the wavelength of the colour.

hum An unwanted low-frequency noise originating from mains-driven equipment and comprising harmonics of the mains frequency. The sound may be radiated directly from components such as mains transformers or may be caused by ripple on the DC supply to an amplifier or receiver and heard in the output of ***loudspeakers*** or ***headphones***.

hunting In a controlled system an undesired oscillation, usually at a low frequency, resulting from over-correction in which the controlled quantity fluctuates about the required value.

hybrid coil A ***transformer*** with three windings and four pairs of terminals,



Figure H.8 An application of the hybrid coil. Signals from the microphone can enter the line but do not appear at the earphone. Signals from the line can enter the earphone, but do not enter the microphone

two of the windings being designed for use in a bridge circuit which isolates one pair of terminals from another pair provided the remaining two pairs are correctly terminated. The circuit diagram of one application of a hybrid coil is given in *Figure H.8*.

hybrid computer A computer in which ***analogue*** and ***digital techniques*** are used.

hybrid integrated circuit An integrated circuit using ***monolithic*** and ***thin-film*** techniques.

hybrid network A network with four pairs of terminals which, when two pairs are correctly terminated, transmits power from the third pair into the terminated pairs but not into the fourth pair.

hybrid parameters Of a ***transistor*** a method of expressing the electrical characteristics by representing it as a four-terminal ***equivalent network***, for which the input voltage and output current are expressed in terms of input current and output voltage. The fundamental equations are:

$$v_{in} = h_i i_{in} + h_r v_{out}$$

$$i_{out} = h_f i_{in} + h_o v_{out}$$

from which h_i has the dimensions of an impedance, h_o of an admittance, whilst h_r and h_f are both pure numbers. The parameters are thus mixed or hybrid in nature. In fact h_f is the current gain of the transistor and h_i is the input impedance (both with the output terminals short-circuited), h_o is the output admittance and h_r the voltage feedback ratio (ratio of input voltage to output voltage) both for open-circuited input terminals. See ***Y parameters, Z parameters***.

hypermedia ***Interactive multimedia***, that is, a computer ***application*** in which the user can steer his way through presentations consisting of ***hypertext***, still images, video and sound.

hypertext A form of ***interactive*** text display used in computer ***applications*** and often forming part of ***on-line help*** and ***hypermedia*** systems. Unlike a plain text file through which the user must navigate using scroll bars or other means to control the portion of the document displayed, hypertext uses an active cross-reference system. Certain words in the text are highlighted (often using a different colour). When the user moves the ***pointer*** over one of these and clicks the mouse button, the screen displays an entry giving further information on that topic. Facilities are usually provided to allow the user to retrace his steps and to jump to an interactive index to the whole document.

hysteresis In general a relationship between a force and its effect in which the effect lags on the force so that the magnitude of the effect depends not only on the present value of the force but also on its previous value.

As a result the magnitude of the effect for a given value of force depends on whether the force is increasing or decreasing and any particular value of effect can be produced by two values of force. If the force is varied cyclically the relationship between force and effect, if shown graphically, is a closed loop, the most familiar example of which is the *B–H* curve for a magnetic material.

hysteresis loop Of a magnetic material, the closed figure obtained by plotting the ***magnetic flux density B*** against the ***magnetising force H*** as the magnetising force is varied throughout a complete cycle. An example of this closed loop is shown in *Figure H.9.*



Figure H.9 B–H hysteresis loop for a magnetic material

hysteresis losses In a magnetic material the energy loss whenever varying flux is produced in the material. The loss is proportional to the area of the ***hysteresis loop.***

icon Small graphical representation displayed on the screen to illustrate a computer function. For example, a representation of a file folder to indicate a ***directory***.

iconoscope The earliest form of TV camera tube in which the optical image of the scene to be televised is focused on a photo-emissive target ***mosaic*** which is obliquely scanned by a high-velocity ***electron beam***.

The mosaic is deposited on one face of a mica sheet which is backed by a conductive signal plate from which the output of the tube is taken. When the optical image is focused on the mosaic, photo-electrons are released from each element in proportion to the light falling on it. Thus a positive charge image is built up on the mosaic surface and this grows with time as the capacitance between element and signal plate is charged. The charge image is discharged by the scanning beam and the resulting voltage change is transferred to the signal plate via the capacitive coupling to the mosaic.



Figure I.1 The standard emitron television camera tube: an example of an iconoscope

In spite of the charge storage thus achieved the tube is not very sensitive and required high scene illumination for a satisfactory ***signal-to-noise ratio***. Moreover secondary emission from the target as a result of bombardment by the high-velocity scanning beam results in spurious signals in the tube output which produce undesirable shading effects in reproduced images. These effects were minimised by mixing with the tube output, sawtooth and parabolic waveforms at line and field frequencies.

One example of an iconoscope is the standard emitron tube, the construction of which is illustrated in *Figure I.1*; this is the type of tube used when Britain started the world's first regular high-definition TV service from Alexandra Palace in North London towards the end of 1936.

ideal radiator Same as ***full radiator***.

identity gate Same as ***AND gate***.

IF-THEN gate A gate with two inputs and one output such that the relationship between inputs and outputs is given in the following ***truth table***:

input 1	input 2	output
1	1	1
1	0	0
0	1	1
0	0	1

igniter (also known as **ignition electrode**) In a mercury-pool discharge tube a stationary electrode which is in contact with the mercury pool and, when suitably biased, causes a local hot spot on the surface so initiating the main discharge.

ignition voltage Same as ***firing voltage***.

ignitron A gas-discharge rectifier tube with a ***mercury-pool cathode*** and a single ***anode*** capable of a large current output. The arc is initiated by an ignition electrode which dips into the mercury pool. A positive voltage is applied to the igniter once per cycle of the applied alternating voltage and this causes a small arc at the mercury surface which precipitates the main discharge.

image attenuation coefficient (or **factor**) See ***image transfer coefficient***.

image converter An ***electron tube*** in which an image of a scene focused on a ***photo-cathode*** gives rise to a corresponding visible image on a fluorescent screen. One advantage of such a tube is that the photo-cathode may be made sensitive to infra-red radiation and can thus give a visible image of a scene invisible to the human eye.

image dissector An early form of TV camera tube in which an optical image of the scene to be televised is focused on a ***photo-cathode***, the released ***photo-electrons*** forming an electron image which is focused on the plane of a defining aperture and is swept over the aperture to effect ***scanning***.

The defining aperture was a hole in an ***anode*** and ***electrons*** passing through it were either intercepted by a collector electrode or were directed into an ***electron multiplier***. The tube lacked sensitivity because of the absence of any form of charge storage but it was used for transmitting cinema film where a large light input could be achieved.

image frequency In superheterodyne reception a frequency as much above (or below) the oscillator frequency as the wanted signal frequency is below (or above) it and which is therefore accepted with the wanted signal by the IF amplifier so causing ***interference***.

image iconoscope An early form of TV camera tube consisting of an ***iconoscope*** with an ***image section***.

image impedances Two parameters of a two-terminal-pair ***network*** such that if the output is terminated with an impedance Z_2 the input impedance is Z_1 and if the input is terminated with a impedance Z_1 the output impedance is Z_2.

Networks are used on an image-impedance basis for matching purposes. For example if an amplifier requires a load of impedance Z_1 in order to perform properly and if the load to be fed has an impedance Z_2, then a network with image impedances Z_1 and Z_2 can be used to connect the amplifier to its load. In this way the equipment has an effective load impedance of Z_1 and the load is effectively supplied from a generator of impedance Z_2: in other words correct matching is achieved at the input and the output of the network.

If the network contains inductance and capacitance then it is possible that the image impedances will be correct at only one frequency. A ***transformer*** can achieve matching over a wide frequency range.

image interference In superheterodyne reception interference from signals on the ***image frequency***. The frequency of such interfering signals differs from that of the wanted signal by twice the intermediate frequency and, to minimise image interference, the signal-frequency circuits of a ***superheterodyne receiver*** are designed to give great attenuation at the image frequency.

image isocon An ***image orthicon*** in which the output is obtained from an ***electron multiplier*** into which the electron beam scattered from the ***target*** is directed. When the scanning beam strikes the target some electrons are absorbed to neutralise the charge image, others return to the electron gun and the remainder are scattered. It is the scattered, not returned, electrons which are captured and directed into the electron multiplier in the image isocon.

image orthicon An ***orthicon*** TV camera tube with an ***image section*** and in which the output signal is obtained from an ***electron multiplier*** into which the return scanning beam is directed.


target
horizontal & vertical deflecting coils
focussing coil
alignment coil
accelerator grid no 6
decelerator grid no 5
grid no 4
grid no 3
grid no 2 & dynode no 1
electron gun
televised scene
scanning beam
return beam
camera lens
photocathode
mesh
five-stage multiplier
image section
scanning section
multiplier section

Figure I.2 Simplified diagram of an image orthicon tube

The essential features of the tube are illustrated in *Figure I.2*. An optical image of the scene to be televised is focused on the ***photo-cathode*** and the ***photo-electrons*** so released are focused by a combination of electrostatic and magnetic ***electron lenses*** on the image-section face of the target where they give rise to secondary emission which is collected by the nearby positively-charged mesh.

Thus a positive charge image is established on the face of the target. If the tube is directed at a very bright light causing the target potential to exceed that of the mesh, the excess secondary electrons are returned to the target: in this way the mesh keeps the tube stable for all light inputs.

The target is very thin and the charge image is rapidly transferred to the opposite face which is scanned by the low-velocity beam. The beam lands on the target to neutralise the positive charge image and thus the return scanning beam is amplitude modulated by the required picture signal. The return beam is directed into the input of a multi-stage ***electron multiplier*** which surrounds the ***electron gun***.

The tube is extremely sensitive and is capable of high-quality pictures. It is, however, complex and too bulky (typically 15 in long and 3 or 4½ in diameter) to be used in colour cameras where three or four tubes are necessary.

image phase-change coefficient (or **constant**) See ***image transfer coefficient***.

image processing The application of digital processing to ***bitmapped*** images, such as ***scanned*** photographs or ***digitised*** video, to change their appearance. Often the processing is to improve the appearance, e.g. by improving the contrast in an underexposed photograph, but sometimes the intention is the reverse, e.g. to reduce the number of colours in the image in order to achieve some special effect.

image section An electron-optical stage included in some television camera tubes to increase sensitivity. As shown in *Figure I.3* the optical image is focused on the ***photo-cathode*** in the image stage and the liberated ***photo-electrons*** are focused on the target to form a charge image by secondary emission from the target. The use of an image section thus separates the functions of photo-emission (now carried out by the photo-cathode) and secondary emission (carried out by the ***target***). In the ***iconoscope*** the target is required to carry out both functions.



Figure I.3 Essential features of one type of image section for a camera tube

image transfer coefficient (or **constant**) For a ***network*** terminated in its image impedances at both ends, one half the natural logarithm of the complex ratio of the steady-state volt-amps entering the network to the volt-amps leaving the network.

The real part of the image transfer coefficient is known as the image attenuation coefficient and the imaginary part as the image phase-change coefficient or, more simply, the image phase coefficient.

When networks are connected in ***cascade*** on an image basis the image attenuation coefficient of the group is equal to the sum of the image attenuation coefficients of the individual networks and the image phase coefficient of the group is equal to the sum of the sum of the individual phase coefficients.

For a symmetrical network the real and imaginary parts of the image transfer coefficient are equal to the real and imaginary parts of the ***propagation coefficient.***

immersion lens In a ***cathode ray tube***, an electrostatic electron lens designed to concentrate the ***electrons*** liberated from the ***cathode*** into a beam. Because these electrons have very low velocities the lens is situated very close to the cathode, so close in fact that the cathode may be regarded as immersed in the lens. The lens usually consists of two plates containing apertures and which may have cylindrical extensions.

immitance A term which can mean ***impedance*** or ***admittance***. It is used in network theory where the distinction between impedance and admittance is irrelevant.

impact dot-matrix printer See ***printer.***

impact ionisation The liberation of orbital electrons from an atom in a crystal lattice as a result of a high-energy collision.

impatt diode A four-layer semiconductor device of pnin construction used as a microwave oscillator. A reverse bias causes ***avalanche breakdown*** at the pn junction. Electrons cross the i-region which acts as a ***drift space*** and the ***transit time*** is arranged to be one half the period of the required oscillation. The device then has a ***negative resistance*** and, given a suitable resonant load, can give up to 50 W output at 10 GHz.

impedance (Z) In general an indication of the opposition offered by a circuit to a flow of alternating current in it. More specifically it is the ratio of the alternating EMF applied to the circuit to the resultant current flowing in it. As there is normally a phase difference between the voltage and the current, the impedance Z is complex and can be written

$$Z = R + jX$$

where R, the real component of the impedance is the ***resistance*** of the circuit and X, the imaginary component is the ***reactance*** of the circuit. The numerical value of the impedance is given by

$$|Z| = \sqrt{(R^2 + X^2)}$$

and can be calculated by dividing the RMS applied voltage by the resulting RMS current. The impedance concept is useful in solving problems where components are connected in series because in such circuits resistances can simply be added to give the total or effective resistance and reactances are added or subtracted depending on their sign.

impedance matching The process of ensuring that two ***impedances*** are equal. This is important for two reasons: (1) To ensure that maximum power is transferred from a generator to a load, the generator and load impedances must be matched. To do this over a wide *frequency range* the resistive and reactive components of the load impedance must in effect be made to equal those of the generator, e.g. by the use of a *transformer*. If, however, *matching* is necessary at only one frequency then maximum power transfer occurs when the load impedance is in effect made to equal the conjugate of the generator impedance, i.e. the resistive components are equal, the reactive components are equal in magnitude but opposite in sign. (2) To ensure that there is no reflection at the termination of a *transmission line* or *filter* network the termination must in effect be equal to the characteristic impedance of the line or the iterative impedance of the network.

imperfection Of a crystal, any difference in its structure from that of the ideal crystal. As an example an atom may be missing from a site or a site may be occupied by a foreign atom. Imperfections are responsible for hole and electron conduction.

import In computing to introduce data into an application in a format that is foreign to that application. For example, to introduce a *bitmap* into a *vector graphics* application.

impulse Same as *pulse*.

impurity In *semiconductor* technology a foreign element added in minute but controlled quantities to a semiconductor element to give it the required *p-type* or *n-type* conductivity. In semiconductor compounds an excess or deficiency of an element belonging to the compound.

impurity diffusion See *diffusion*.

inclusion gate Same as *IF-THEN gate*.

inclusive-OR gate Same as *OR gate*.

incremental permeability The ratio of the change in *magnetic flux density* to the small change in *magnetising force* which gives rise to it when this is superimposed on a steady magnetising force.

independent sideband transmission (ISB) A system of *amplitude modulation* in which one *sideband* is produced by modulation by one signal and the other sideband is produced by modulation by a different signal. The system is not greatly used largely because of the difficulty of separating the two signals at the *receiver*.

indirectly-heated cathode A *cathode* of an *electron tube* for which the heat necessary for the thermionic emission is supplied by an independent heater contained within the cathode but insulated from it. The cathode is usually a nickel cylinder coated with electron-emitting material and the heater is a tungsten spiral or hairpin within it but insulated from the cylinder by, for example, aluminium oxide.

induced current A current flowing in a circuit as a result of an *induced EMF*.

induced EMF The EMF generated in a circuit as a result of *electromagnetic induction*.

inductance (L) In general that property of a current-carrying circuit which enables it to generate an EMF in itself (or in a nearby circuit) as a result of changes in the current and therefore in the associated magnetic field. The direction of the induced EMF is such as to oppose the change in current which gave rise to it and thus inductance may be regarded as the electrical analogue of inertia. The EMF induced in the circuit itself is more properly ascribed to self-inductance and that induced in a nearby circuit to ***mutual inductance***. Clearly the inductance of a conductor can be increased by coiling it so as to increase linkage with the magnetic field and the introduction of a ***magnetic core*** increases it further. The practical unit of inductance is the Henry (H) and a circuit is said to have an inductance of one Henry if a current, changing at the rate of one ampere per second, induces an EMF of one volt in it.

induction See ***electromagnetic induction, magnetic flux density***.

induction loop In general any looped conductor used to transfer energy to another by ***mutual inductance***. More particularly, a form of localised wireless broadcasting used in churches, theatres, museums and other public buildings to assist those hard of hearing or to provide a commentary. They are also sometimes installed in the homes of partially deaf people to help them to hear radio and television programmes. The induction loop surrounds the area to be served and is connected to the output of an ***audio amplifier*** reproducing the required audio programme. Receivers are either ***hearing aids*** fitted with suitable pick-up coils (selected on the so-called 'T'-switch) or dedicated receivers usually fitted with an ***earphone*** that the user holds against his ear.

inductive coupling Coupling of two circuits by virtue of a common inductor or by ***mutual inductance***. The common inductor may be a series-connected component as in *Figure I.4* (a) or a shunt component as in (b). *Figure I.5* shows coupling by mutual inductance *M*.



Figure I.4 Coupling by series inductances is shown at (a) and by shunt inductance at (b)



Figure I.5 Coupling between two circuits by mutual inductance M

inductor A component used because of its ***inductance***. A wide variety of types of inductor are used in electronics. At low and audio frequencies inductors of many Henries consists of windings with laminated ferromagnetic cores. At higher frequencies ***eddy-current*** losses become important and non-conductive ferrite cores are used in RF conductors and ***transformers***.

inertance That property of an acoustical vibrating system which enables it to resist changes in velocity. It is a function of the mass of the medium in the system, being given by m/A^2, where m is the mass and A is the cross-sectional area over which the driving pressure acts. Inertance is the acoustical analogue of ***inductance***.

infinite baffle A loudspeaker cabinet which is totally enclosed at the rear so that sound radiated from the rear of the diaphragm cannot interfere with forward-radiated sound. The cabinet therefore behaves as a baffle of infinite dimensions. In a practical design provision must be made to absorb the rear radiation from the diaphragm and allowance must be made for the inevitable raising of the fundamental resonance frequency of the ***loudspeaker*** caused by the stiffness of the air trapped in the cabinet. Nevertheless some very successful designs have been produced, some so small that the cabinet can be readily accommodated on a bookshelf or a mantlepiece.

infinite-impedance detector An ***anode-bend*** detector in which the load is connected in the ***cathode*** circuit. A typical circuit diagram for the detector is shown in *Figure I.6*. The load R_1 and associated capacitor C_1 behave as in a diode detector circuit, i.e. C_1 is charged on positive-going half-cycles of carrier input and discharges through R_1 during negative-going half-cycles, so developing the AF waveform across the combination. The reactance of C_1 is very high at AF and thus the tube has 100% negative feedback. No grid current flows and the input of the tube is very high, imposing negligible ***damping*** on the ***tuned circuit***.



Figure I.6 Circuit diagram of an infinite-impedance detector

information superhighway A vague term denoting any ***network*** over which information in a variety of formats is accessible to a wide public. It is sometimes used to refer to the ***Internet*** although equally applicable to many other networks including interactive ***video on demand*** systems.

Information Technology (IT) A vague term embracing all electronic equipment that is used in the processing and presentation of ***data***.

infra red ***Electromagnetic waves*** with frequencies extending from the red end of the visible ***spectrum*** to the microwave region (see *Figure E.7*). The radiation is invisible but gives a sensation of heat and is used in cooking and industrial heating applications as well as in remote control systems.

inhibiting signal A signal which prevents a particular action occurring. For example it may close a gate to prevent any output which might otherwise occur. An inhibiting signal is a negated ***enabling signal***.

ink-jet printer See ***printer***.

in-line colour picture tube See ***precision-in-line colour picture tube***.

input (1) Of a device or equipment, the signal applied to it and upon which it performs some function, e.g. amplification. (2) The terminals to which the input signal is applied.

input impedance Of a device or equipment, the ***impedance*** it presents to the source of input signal.

insertion gain (or **loss**) The gain resulting from the insertion of a ***network*** between a generator and its load. It is given by the ratio (usually expressed in ***decibels***) of the power (voltage or current) delivered to the load before insertion to the power (voltage or current) delivered after insertion.

insertion signal In TV a signal inserted into one of the line periods during the ***field blanking*** period. The signal is not seen on the screens of viewers' receivers and is used by the transmitting authority to transmit information such as the source of programme or control data. The signal is also used for test purposes to give information on the performance of the television links. Of a television waveform, a signal introduced during flyback periods to carry information for engineering purposes or for display on receiver screens, e.g. ***teletext***.

instability Generation of unwanted and sustained ***oscillations***.

instrument transformer A transformer giving at its secondary winding a voltage or current which is precisely related in magnitude and phase with that at the primary winding and is therefore suitable for application to a measuring instrument or a control or protective device.

insulated-gate field-effect transistor (IGFET) A ***field-effect transistor*** in which the input electrode is capacitively coupled to the channel. A cross section of an IGFET is given in *Figure I.7*. It consists of a base layer of p-type silicon with diffused n-regions at each end to which source and drain connections are made. During manufacture by the ***planar process***, the device is sealed by a layer of silicon dioxide obtained by heating it to 1200°



Figure I.7 Simplified diagram showing the structure of an n-channel insulated-gate field-effect transistor

in an atmosphere of water vapour or oxygen. A thin layer of aluminium is then deposited on the device to provide a gate connection, the aluminium, silicon dioxide and the p-layer forming a capacitor.

With no voltage applied to the gate the only current which flows between source and drain connections is the negligibly-small leakage current of the pn junctions. If, however, the gate is biased positively (with respect to the source) electrons are attracted to the surface either from thermal breakdown of the p-layer or from the n-region and these provide a n-type conducting channel between source and drain permitting a longitudinal current flow. Increase in the positive bias increases channel conductivity and drain current. Because current is zero for zero gate bias and increases with increase in forward bias this device is said to operate in the enhancement mode.

It is however possible in the manufacture of IGFETs to provide an n-layer on the p-base so that there is conductivity in the channel and drain current can flow even with zero gate bias. For such IGFETs negative bias on the gate cuts off the channel as in JUGFETs and for such values of bias the device operates in the depletion mode. Positive gate bias will still increase drain current giving enhancement mode operation as before. IGFETs may have more than one gate and dual-gate IGFETs are sometimes termed ***tetrode*** FETs.

The distinction between enhancement and depletion types of FET is indicated in the graphical symbols by showing the channel of an enhancement device as a broken line. This is illustrated in *Figure I.8* which gives the graphical symbols for a dual-gate depletion-type IGFET and a single-gate enhancement-type IGFET, both with n-type channels.



Figure I.8 Graphical symbols for (a) a dual-gate depletion-mode IGFET and (b) a single-gate enhancement-mode IGFET, both with n-channels

insulation-displacement connector A form of connector for terminating ***ribbon cables*** which clamps on the cable causing contacts in the connector to pierce the insulation of the cable to make connection with the conductors. It makes a quick and effective method of termination which avoids the need for soldering and cable stripping. A typical application for an insulation-displacement connector is for interconnecting printed-circuit or printed-wiring boards.

integrated circuit (IC) See ***hybrid integrated circuit*** or ***monolithic integrated circuit***.

integrating amplifier An ***operational amplifier*** the output of which is equal to the time integral of the input waveform.



Figure I.9 A simple integrating circuit (a) and typical input and output waveforms (b)

integrating circuit A circuit the output of which is approximately proportional to the time integral of the input signal. A common example is a circuit comprising a series resistor followed by a shunt capacitor as shown in *Figure I.9*. The ***time constant RC*** must be long compared with the period of the input pulses.

integrator Any circuit, network or transducer yielding an output waveform substantially similar to the time integral of the input waveform.

intelligent terminal A computer ***terminal*** which, in contrast with a ***dumb terminal***, allows some local data processing and storage facilities. It may run an application which accesses the ***host*** in a more efficient or ***user-friendly*** manner. Often an intelligent terminal is a general-purpose microcomputer running terminal emulation software. See ***programmable workstation***.

intensifier electrode An electrode used to increase the electron-beam velocity in a ***cathode ray tube*** after the beam has been deflected.

intensity modulation Variation of the density of an ***electron beam*** in accordance with the instantaneous value of the ***modulating signal***. An obvious example of intensity modulation occurs in the reproduction of TV images by a picture tube in which the electron-beam density is controlled by the ***video signal*** so as to produce the variations of light intensity on the screen necessary to make up the picture.

interactive Responding instantly to signals from the user. Many computer ***applications***, e.g. word processing, are interactive in that the user provides input to the system via the ***keyboard***, ***mouse*** or other device and this affects the execution of the program. Conventional television and radio broadcasting, in contrast, are not interactive since the viewer or listener has no immediate control over the material being transmitted.

inter-carrier reception In a TV receiver a method of sound reception in which the FM sound signal is derived from the vision detector or a post-detector stage as an FM signal on a carrier frequency equal to the difference between the vision and sound carrier frequencies. The method has the advantage that the centre frequency of the sound signal is unaffected by drift of the local oscillator.

interface A boundary between two pieces of equipment with different functions or between systems in which data are expressed in different forms.

interference (1) In radio or TV reception any unwanted signal, natural or man-made, which adversely affects reception of the wanted signal.

Natural interference signals can arise from lightning flashes, and man-made interference from signals on nearby frequency channels or image channels, from electrical equipment and from car ignition systems.

Interference signals can be picked up on the receiving *antenna* or can reach the receiver via the supply mains. Some reduction in interference may be possible by using a directional antenna, by siting the antenna in an 'electrically-quiet' spot, or by the use of RF filters in the receiver mains supply. The best method is to prevent the radiation of interfering signals by fitting suppressors to the offending equipment. (2) In optics the effects observed when two sources of light of the same frequency are superimposed. Areas where the two waves are in phase are illuminated more brightly than those where the waves are in phase opposition and thus one of the most familiar effects is the formation of interference bands or rings.

interlaced scanning In TV a system in which the scanning agent, during each of its vertical sweeps, scans the image in a series of equidistantly-spaced lines, the lines of each sweep being slightly displaced vertically from those of the previous sweep, so that two or more sweeps are necessary to scan the whole of the picture area. In ***twin-interlaced scanning*** the lines of each vertical sweep fall midway between those of the previous sweep.

intermediate frequency (IF) In a ***superheterodyne receiver*** the carrier frequency to which the modulation of all received signals is transferred by the frequency changer. The signal from the frequency changer is accepted by the IF amplifier which is responsible for most of the gain and the selectivity of a superheterodyne receiver.

intermodulation Interaction between the components of two or more complex signals in a non-linear system leading to the production of new components with frequencies equal to the sums and differences of those of the components of the waves (***combination frequencies***).

intermodulation distortion Distortion arising from the non-linearity of the input-output characteristics of a system, equipment or component and resulting in the generation of new signals at ***combination frequencies*** of the two or more sinusoidal input signals. It is the generation of these new signals some of which are not harmonically related to the frequencies of the input signals which is responsible for the harsh sound of an overloaded audio amplifier.

Internet An autonomous global computer ***network*** originally set up in 1969 to allow academic and governmental bodies to exchange data. Interest in the Internet became fashionable in the early 1990s when it began to be used by a diversity of individuals and organisations for the exchange of scientific, cultural, religious, commercial and other information.

interpretation See ***computer language***.

interrogator A combination of radio transmitter and receiver designed to radiate signals to a ***transponder*** and to display the response received.

interrupted continuous wave (ICW) Type of wave used for radio telegraphy in which an audio-frequency modulating wave or the audio-frequency modulated wave is keyed on and off.

interval In ***acoustics*** the difference in frequency or ***pitch*** between two sounds.

intrinsic diode Same as ***pin diode***.

intrinsic semiconductor A semiconductor material in which the concentration of donor and acceptor impurities is equal so that there is no resultant excess of ***holes*** or ***electrons*** to act as ***charge carriers***. Such material is known as i-type to distinguish it from n-type and p-type material.

inverse amplifier Same as ***inverter***.

inverse feedback Same as ***negative feedback***.

inverse impedances Two impedances the product of which is independent of frequency. Two simple examples of inverse impedances are a purely-inductive and a purely-capacitive impedance. The series and shunt elements in a ***constant-k filter*** are inverse impedances.

inverse networks Two two-terminal networks the impedance of which are inverse, i.e. their product is independent of frequency.

inverse voltage Of a diode in a rectifying circuit, the voltage appearing across the diode when it is non-conductive. See ***peak inverse voltage***.

inverter (1) Equipment for converting DC into AC. (2) In logic circuitry an amplifier the output of which is equal in amplitude but opposite in polarity to the input signal. Such an amplifier can be used as a negator to convert a logic-1 signal to a logic-0 and vice versa.

ion A charged particle formed from an atom or a molecule by the loss or gain of ***valence electrons***. If electrons have been lost, the resultant ion has a positive charge and if electrons have been gained, the ion has a negative charge. As matter is normally uncharged, ions are formed in pairs, one with a positive and the other with a negative charge. In gases the negatively-charged ions may be electrons and the positively-charged ions comprise the remaining parts of the atom or molecule where most of the mass resides.

ion burn An area of reduced luminosity on the screen of a ***cathode ray tube*** caused by partial destruction of the phosphor by bombardment by heavy negative ***ions*** which are liberated from the cathode or are formed by ***ionisation*** of the residual gas. The area is usually at the centre of the screen because the heavy ions are not deflected to the same extent as electrons by the deflecting fields. See ***aluminised screen, ion trap***.

ion gun A device similar to an ***electron gun*** but in which the charged particles are ***ions***.

ion implantation In semiconductor-device manufacture a technique whereby a required amount of an ***impurity*** can be introduced into the semiconductor material by bombarding it with ions of the impurity (usually boron or phosphorus). The ions can be released by an RF discharge or by use of a heated filament and are focused and accelerated by electrostatic means, using voltages up to 500 kV. The process has the advantage over ***diffusion*** of giving more precise control over the concentration and depth of penetration of the impurity.

ionisation The splitting of electrically-neutral matter into positively-charged and negatively-charged ***ions***. Electronics is particularly concerned with ionisation of gases and there are a number of ways in which this can be achieved. For example the gas can be subjected to radiation such as ultra-violet light, ***X-rays*** or ***gamma rays***. This occurs in the upper atmosphere where air is ionised by ultra-violet radiation from the sun to form the ionosphere.

A second method is ionisation by collision: if a voltage is applied between two cold electrodes in a gas tube the few positive and negative ions formed by ultra-violet light are collected at the ***electrodes***. If the voltage is increased sufficiently all such ions will be collected but, in moving rapidly to the electrodes, some ions and electrons collide with gas atoms and split them into further ions. These, too, may liberate ion-pairs and the process results in a rapid build-up of ions. The presence of an electron stream from a heated cathode greatly assists ionisation by collision.

ionisation voltage The minimum voltage applied to a gas-filled tube which will cause ionisation. The ionisation voltage depends on the gas: for example for mercury vapour it is 10.4 V and for helium 24.5 V.

ion trap Method of avoiding ion burn of the screen of a ***cathode ray tube***. In one method the ***electron gun*** is aimed at the neck of the tube and an external permanent magnet is used to deflect the electron beam to the axis of the tube. Heavy negative ions liberated from the cathode or by ionisation of the residual gas which are responsible for ion burn are deflected to a smaller extent than the electrons and continue to bombard the tube neck. The use of an ***aluminised screen*** has now rendered the use of ion traps unnecessary.

isolate (1) To disconnect equipment completely from all sources of power. (2) To provide a degree of physical protection by making an object or circuit inaccessible unless special measures are taken. (3) To use a ***buffer stage*** to prevent interaction between stages in electronic equipment.

isotropic Having the same properties in all directions. See also ***anisotropic***.

iterative impedance That value of impedance which, if used to terminate a ***network***, gives an input impedance of the same value. The virtue of this concept is that networks used on an iterative-impedance basis can be inserted into circuits without affecting impedance levels. For example if the input impedance of an amplifier is 300 Ω (*Figure I.10*(a)) and if a filter with an iterative impedance of 300 Ω is inserted before the amplifier the input to the filter is also 300 Ω as shown in *Figure I.10*(b).



Figure I.10 The use of a two-terminal-pair network on an iterative-impedance basis

J

jack A socket containing a number of spring-loaded contacts which mate with the corresponding contacts of a plug inserted in the jack. The contacts within the jack can be arranged to make or break particular circuits when the plug is inserted as shown in the graphical symbols in *Figure J.1*. Plugs and jacks are extensively used in telephone switchboards and in broadcasting to permit rapid connections to be made to equipment or circuits.



Figure J.1 (a) A three-pole plug and jack connecting two wires and earth and (b) a break-jack. At (b) the contact between a and b and between c and d is broken when the plug is inserted

jamming Deliberate transmission of radio signals to interfere with the reception of other signals.

jitter General term for sudden irregular departures from the ideal value of a parameter such as the ***phase, amplitude*** or ***pulse duration*** of a signal. In TV signals jitter can cause errors in synchronising and these can lead to erratic movements in the displayed picture.

JK bistable A ***bistable circuit*** with two inputs labelled J and K. When the J input is at its logic-1 state, the output (see *Figure J.2*) takes up its logic-1 state. When the J input is at its 0-state it has no effect on the output. When the K input is at its logic-1 state the output takes up its 0-state, but when the K input is at its logic-0 state it has no effect on the output.

The behaviour of the J and K inputs is thus similar to that of the R and S inputs of an ***RS bistable*** but the JK bistable has the advantage that if logic-1 signals are applied simultaneously to the two inputs the output is predictable. In fact every time the simultaneous logic-1 inputs are applied the output of the bistable goes to the complementary state.



Figure J.2 Logic symbol for a JK bistable

Johnson noise Same as ***thermal noise***.

Joint Photographic Experts Group (JPEG) A standard for the storage of ***true-colour bitmaps*** such as those obtained from colour photographs using a *scanner*. The JPEG standard uses Fourier Transform technology to sacrifice fine detail selectively in order to reduce the storage requirements. The degree of ***compression***, however, is controlled by the JPEG file creator who chooses a quality factor expressed as a percentage. At high settings there is little detail loss, although worthwhile space savings may be made; at lower settings deterioration in image quality is more visible and there are greater space savings. Results vary with subject matter, but for many photographs a quality setting of 87 per cent results in a JPEG file about 10 per cent of the size of the original uncompressed bitmap with imperceptible deterioration in image quality at normal magnifications. A purpose-designed ***integrated circuit*** is available which decodes JPEG images considerably faster than a computer can. See also ***MPEG***.

Joule effect The heating effect generated by an electric current in a conductor by virtue of its resistance. Joule's law states that the rate of heat generation is proportional to the square of the current.

joystick A control capable of movement in two mutually-perpendicular directions. Such a control may be used to adjust the position of the cursor of a VDU.

jump In computing, the transfer of control to a different area in memory. This contrasts with the processor's normal sequential execution of the instructions held in memory.

junction In a ***semiconductor*** device a transition region between two regions of different types of conductivity, e.g. a pn junction is the transition region between a p-region and an n-region.

When a pn junction is forward biased as indicated in *Figure J.3*(a), the p-region being positive with respect to the n-region, a considerable current crosses the junction. This current is carried by majority carriers, i.e. holes from the p-region (which move to the right) and electrons from the n-region (which move to the left). This forward current increases rapidly with increase in applied voltage.

If, however, the battery is reversed the majority carriers move away from each other leaving the junction region deficient in carriers: it is then known as a depletion layer. The only current which crosses a reverse-biased junction is a very small one composed of minority carriers, electrons from the p-region (which move to the right) and holes from the n-region (which move to the left). This small leakage current is largely independent of the applied reverse voltage.



Figure J.3 (a) Movements of majority carriers in a forward-biased pn junction and (b) movement of minority carriers in a reverse-biased junction



Figure J.4 Graphical symbol for a diode. The end marked + is that which goes positive when the diode conducts

junction diode A pn junction employed because of its unilateral ***conductivity***. Such diodes are extensively used for rectification, detection and in digital circuitry. The graphical symbol for a junction diode is given in *Figure J.4*.

junction-gate field-effect transistor (JUGFET) A ***field-effect transistor*** in which the gate forms a pn junction with the channel. A simplified structure of an n-channel JUGFET is given in *Figure J.5*. It consists of a crystal of n-type silicon with ohmic contacts provided by highly-doped (n+) regions near the two ends: these provide the source and drain connections to the external circuit. A region of p-type conductivity is formed (e.g. by diffusion) between the ohmic contacts: this provides the gate connection.



Figure J.5 Simplified diagram showing the structure of an n-channel junction-gate field-effect transistor

Current flowing longitudinally between the n+ regions is carried by the free electrons of the n-type channel. The number of electrons available to act as charge carriers is, however, dependent on the gate bias. The more negative (with respect to the source voltage) the gate is made the greater is the area of the depletion layer surrounding the p-region and the smaller the number of electrons available to carry the longitudinal current. In fact the channel can be cut off completely by a sufficiently-great reverse bias on the gate, the depletion layer then occupying the whole of the cross section of the channel.

Because the pn junction is reverse-biased during normal operation of the FET the transistor has a very high input resistance. The channel of a JUGFET may have more than one gate. A connection to the substrate can also provide a second input terminal although it is not usually as sensitive as the normal gate terminal. JUGFETs operate in the depletion mode and the graphical symbol for an n-channel device is given in *Figure J.6*.



Figure J.6 Graphical symbol for an n-channel depletion-mode JUGFET

junction transistor A ***transistor*** containing a ***pn junction*** in its structure. This definition includes a ***junction-gate field-effect transistor*** but the term is generally used to mean a ***bipolar transistor*** as opposed to a ***field-effect transistor***.

K

keep-alive electrode An ***electrode*** in a mercury-arc rectifier which maintains the vapour in a partially-ionised state.

Kell factor In TV a factor expressing the ratio of horizontal to vertical definition. Suppose each of the n lines of a TV picture is made up of alternate black and white elements. If these elements are assumed to be square-which is equivalent to regarding horizontal definition as equal to vertical definition-then there are $4n/3$ elements in each line, the aspect ratio being 4:3. The lowest video frequency which will enable such a row of elements to be resolved is one in which one half-cycle represents a white element and the other half-cycle a black element. This is the upper video-frequency limit for the system and it gives values appreciably higher than are used in practice. The lower practical values are justified by the assumption that the horizontal definition need only be, say, 0.7 times the vertical definition: in other words they are based on a Kell factor of 0.7.

Kelvin bridge A modification of the ***Wheatstone bridge*** used for comparing very low values of resistance. As shown in *Figure K.1* the Kelvin bridge has an additional pair of ratio arms R_3 R_4 which have the same ratio as R_1 and R_2. R_5 and R_6 are the two low-value resistances to be compared and R_7 is an unknown resistance. At balance the following relationship applies:



Figure K.1 Kelvin bridge

$$R_5 = R_6 . \left(\frac{R_1}{R_2}\right)$$

kenotron A hot-cathode high-vacuum diode used for high-voltage low-current rectification in industrial applications, e.g. X-ray equipment.

Kerr cell A light modulator consisting of a liquid cell containing two parallel plane electrodes and situated between crossed polariods. Normally no light emerges because the polariods are crossed. Signals applied between the electrodes cause the plane of ***polarisation*** of the light to rotate (Kerr effect) so allowing light to pass.

key (1) Type of manually-operated switch used in telephone and broadcasting equipment. One example is a Morse key, a single-pole two-way switch designed for rapid operation to generate Morse telegraph signals. A telephone key is a multi-pole single-way or two-way switch operated by a lever or push button. (2) In a ***database*** the criterion against which data are retrieved. For example, if a doctor wishes to retrieve the names of all patients aged 70 or over, the age criterion is said to be the *key*.

keyboard An arrangement of buttons or keys by which the user enters data manually into equipment. More specifically, the alphanumeric keyboards used with ***computers*** or the musical keyboards used with ***synthesisers***.

keypad A small ***keyboard*** often containing only numeric keys and a few others for special functions. Keypads are used in telephones and electronic calculators.

keystone distortion In TV, geometric distortion of the image causing a rectangle to be reproduced as a trapezium or keystone. The effect can be caused by interaction between line-scanning and field-scanning circuits but occurred in the early days of television as a result of oblique scanning of the target by the electron beam in ***iconoscope*** tubes. It was necessary to introduce correction to obtain an accurately rectangular reproduced image.

keyword In computing a string of characters that is recognised by the ***operating system*** or by a ***computer language*** or by ***applications software*** and which initiates an activity.

kinescope (US) Same as ***cathode ray tube***.

Kirchoff's laws (1) In any ***network*** the sum of the currents which meet at a point is zero. (2) In any closed path in a network the algebraic sum of the products of resistance and current in the branches is equal to the sum of the EMFs acting in the path.

These two fundamental laws apply to instantaneous currents and are of great value in theoretical analyses of the behaviour of electronic circuits.

klystron An ***electron tube*** in which the ***electron beam*** is velocity modulated to generate or amplify microwaves. A simplified diagram showing the construction of a typical klystron is given in *Figure K.2*. The electron beam



Figure K.2 Essential features of a two-cavity klystron

from the cathode passes between the grids of a ***cavity resonator*** known as a buncher. The input signal is applied to this resonator and the resulting potentials between the grids causes velocity modulation of the beam. Bunching occurs in the drift space and the bunches, in passing through the catcher grids, induce an amplified output signal in the catcher resonator. The beam is finally collected at the ***anode*** (or collector).

This is in essence the theory of the two-cavity klystron amplifier. The graphical symbol for the tube is given in *Figure K.3*. By coupling the buncher and catcher resonators, the tube can be made to generate microwaves. An alternative form of klystron oscillator is the ***reflex klystron***.



Figure K.3 Graphical symbol for a two-cavity klystron. The symbol shows an indirectly-heated cathode, intensity-modulating electrode, two focusing electrodes and collector. The tunable input resonator is fed via a coaxial line and the tunable output resonator is window-coupled to a waveguide. An external coil is shown to produce the axial magnetic field.

k rating In TV a factor derived from objective measurements of the distortion of a test waveform which expresses the subjective effect of the distortion on reproduced images. The measurement is made on an ***oscilloscope*** fitted with a graticule using a ***pulse and bar test signal***.

L

ladder network A four-terminal ***network*** consisting of alternate series and shunt elements as shown in *Figure L.1*. As shown in the diagram, if each shunt element is replaced by two elements in parallel and if each series element is replaced by two elements in series, the ladder network can be regarded as a succession of ***L-networks*** (*Figure L.2*). Networks 1 and 2, 3 and 4, etc can be combined to form ***pi-networks***. Alternatively networks 2 and 3, 4 and 5, etc could be combined to form ***T-networks***. Thus a ladder network can be regarded as a succession of T-networks or pi-networks. These constituent networks are known as sections and the L-networks of which they are composed, as half-sections. See ***constant-k filter, filter, m-derivation***.



Figure L.1 A ladder network



Figure L.2 The ladder network of *Figure L.1* redrawn as a succession of L-networks

lag (1) See ***phase angle***. (2) In ***photocells*** and ***camera tubes*** the time which elapses between a change in light input and the corresponding change in electrical output. Lag in camera tubes tends to produce blurred images of objects which move rapidly across the field of view. Keeping lag to an acceptable level is one of the difficulties in the design of photoconductive targets.

landline In a communications system a link between two points that uses hard cables, e.g. telephone lines, rather than a radio link.

laptop computer A self-contained ***microcomputer*** which can be operated from internal batteries and is small enough to be carried in a briefcase and used anywhere, e.g. while travelling.

large-scale integration (LSI) See ***monolithic integrated circuit***.

laser (light amplification by stimulated emission of radiation) A device for light amplification which relies for its action on the ***radiation*** emitted by certain atoms when transitions occur between discrete energy levels. In practice positive feedback is usually applied to the amplifiers (by use of mirrors at the input and the output) to make them oscillate. They then become generators of coherent light in the form of a narrow and sharply-defined beam of good spectral purity and frequency stability.

Certain atoms emit radiation as they change from one energy level to a lower energy level and they can be stimulated into emission by placing them in a radiation field with the same frequency as they would normally emit (a technique known as pumping). Amplification is possible if more atoms leave the higher level than absorb energy at the lower level. Suitable materials are therefore those in which atoms at the upper energy level have a longer lifetime than those at the lower level. A number of materials have this property including some gases, liquids, solids and semiconductors. Thus a number of different types of laser have been developed and these are capable of oscillation at a large number of frequencies between ultra-violet and infra-red.

Gas lasers normally employ a helium-neon mixture, argon or carbon dioxide contained in a tube between 1 and 2 mm in diameter and 20 to 100 cm long. Pumping is achieved by passing a discharge through the gas and the carbon-dioxide laser can give several kW of output, adequate for machining operations.

Liquid lasers use solutions of fluorescent materials and are pumped by light from an argon laser or an electronic flash tube. Ruby is the solid most often used in lasers although neodymium glass or yttrium aluminium garnet are also employed. These are optically pumped using light from a flash tube, a krypton arc or a tungsten iodine lamp. Outputs up to 1 kW are possible using a number of cascaded rods of the solid.

Semiconductor lasers are different in nature from the types just described. In pn junctions using certain semiconductors such as gallium arsenide and indium arsenide, radiation is emitted when electrons and holes recombine and by using very high doping it is possible to achieve the condition where the higher-level charge carriers have a longer lifetime than those at the lower level. A high-density forward current across the junction can then lead to laser action and oscillation is possible by using a structure in which the crystal is cleaved at right angles to the plane of the junction, the cleaved surfaces acting as the mirrors which give positive feedback. In early semiconductor lasers of this type, intermittent operation was necessary to avoid overheating but continuous operation is possible in modern multi-layer structures.

Because of the small dimensions possible, semiconductor lasers can be designed to feed light into optical fibres. They are also used to replay *compact disks*. The block symbol for a laser is given in *Figure L.3*.



Figure L.3 General block symbol for a laser

laser printer See *printer*.

latch In general a two-state device which changes state on receipt of an input signal and then remains in that state, ignoring all subsequent input signals, until reset. Latching may be mechanical or electronic.

latch up In ***computers*** or ***data-processing equipment*** a phenomenon in which, as a result of a fault, a particular section of the equipment is prevented from operating normally.

lattice network A two-terminal-pair ***network*** consisting of two series elements, one in each leg, and two shunt elements each bridging an input and output terminal. The lattice network is shown in its usual form in *Figure L.4* but it can be redrawn in the form shown in *Figure L.5* which is generally known as a bridge network.



Figure L.4 A lattice network



Figure L.5 The lattice network of *Figure L.4* redrawn in the form of a bridge network

lead-acid cell (accumulator) A ***secondary cell*** in which the positive plate is of lead dioxide, the negative plate is of lead (in sponge form) and the electrolyte is dilute sulphuric acid. During discharge the acid reacts with both plates to form lead sulphate and thus becomes more dilute. On recharging these reactions are reversed and the acid regains its strength. The cell has an EMF of about 2 V on load and can supply currents up to 100 A. The cells are extensively used for power supply and are most tolerant of variations in charging current. Their chief disadvantage is that the EMF and capacity both fall as temperature is lowered.

leakage current In general any current which flows via an undesired, usually high-resistance path. For example a leakage current may flow across the surface of an insulator. In particular in a ***bipolar transistor*** a component of the collector current which is not controlled by the input current. It is generated by thermal breakdown of covalent bonds in the collector-base junction and increases rapidly with increase in temperature. In germanium transistors leakage current can be large enough to seriously limit the performance of the transistor and it sets a limit to the temperature at which such transistors may be used. In silicon transistors leakage current is negligible at normal temperatures.

leakage flux Of a magnetic circuit that part of the ***flux*** which does not flow in the main (intended) path. For example the leakage flux in a transformer is that which does not link with the secondary winding and does not therefore contribute to the secondary voltage.

leaky-grid detector Same as ***grid-leak detector***.

Leclanché cell A primary voltaic cell consisting of a carbon electrode (positive) and a zinc electrode (negative) immersed in an electrolyte of ammonium chloride solution. In its dry form this is the most widely used of primary cells. The carbon electrode is a rod surrounded by a paste of ammonium chloride and manganese dioxide (depolarising agent) within a zinc container acting as the negative electrode. See ***depolarisation***.

leddicon A ***camera tube*** with a photoconductive target of lead oxide.

Lempel-Ziv-Welsh (LZW) compression A form of data ***compression*** widely used in computing, especially for the storage of ***bitmaps***.

level The amplitude of a signal particularly when compared with a reference amplitude. The level may be expressed in decibels relative to the reference level which is taken as 0 dB. For example if zero level is taken as 1 V, a voltage level of 10 mV can be expressed as −40 dB.

life test A test carried out on a component or device to determine its probable life under normal working conditions.

lifetime In ***semiconductor*** theory the average time between the formation of a ***minority carrier*** and its recombination.

lift In TV a ***pedestal*** of adjustable height.

light-emitting diode (LED) A pn ***junction*** which emits visible radiation when forward biased. When a pn junction is forward biased electrons are driven into the p-region and holes into the n-region as shown in *Figure J.3*(a). Some of these ***charge carriers*** combine in the junction area and with suitable choice of semiconductor material this is accompanied by the emission of visible light. It is possible to obtain light of a number of different colours but maximum electrical-optical efficiency is obtained when the light is red. LEDs are widely used as indicator lamps in electronic equipment and as seven-segment arrays in numerical displays. The graphical symbol for a LED is given in *Figure L.6*.



Figure L.6 Graphical symbol for a light-emitting diode

lighthouse tube An electron tube made suitable for operating at UHF in which the closely-spaced electrodes are extended as annular disks which project through the glass envelope to locate with the ends of the coaxial



Figure L.7 Sectional view of a lighthouse tube

lines used as tuning elements. The stepped sizes of the disks gave the tube the appearance of a lighthouse as shown in *Figure L.7*. The close spacing of the electrodes is necessary to minimise transit time and so raise the limiting frequency of oscillation and amplification. This is an American version of the British *disk-seal tube*.

light pen A device used to produce a visible image on the screen of a ***visual display unit***. By passing the pen over the surface of the unit the operator can communicate with a stored programme and can thus modify the display. Light pens are extensively used in ***computer-aided design***.

light valve A device which enables light transmission to be varied in accordance with the instantaneous value of the applied electrical signal. An example of a light valve is the ***Kerr cell*** used with polarised light.

limiter Same as ***amplitude limiter***.

line (1) Abbreviation for ***transmission line***. (2) Abbreviation for ***scanning line***.

linear distortion Any form of ***distortion*** which is independent of the amplitude of the signal. Thus distortion which results from variation of a parameter with frequency, e.g. attenuation distortion is an example of linear distortion. See ***non-linear distortion***.

linearity control In early TV receivers a control which varied the scanning speed of the ***electron beam*** during the forward trace so as to correct geometric distortion of the image. Such control might be applied to the horizontal and vertical movement of the beam so that there were two linearity controls: line linearity and field linearity.

linear network See ***network***.

line blanking In TV the suppression of the picture signal during the interval between two successive ***scanning lines***.

line frequency In TV the number of horizontal sweeps made by the scanning beam in one second. It is equal to the product of the number of lines per picture and the picture frequency. In a twin-interlaced system such as used by most TV services the picture frequency is one half the field frequency. For example in the British 625-line system there are 50 fields per second and thus the line frequency is 625 x 50/2 = 15.625 kHz.

line microphone A directional microphone in which the ***transducer*** is fed with sound via a long tube with spaced or distributed acoustic elements so designed that only sound waves travelling along the tube axis or at small angles to it are accepted.

lines of force Lines representing the direction of an electric or magnetic field. The direction of the line at any point in it indicates the direction of the force of attraction or repulsion on a small positive charge or small north pole placed at that point, and the number of lines crossing a unit area at right angles to the line is a measure of the field strength.

line printer See ***printer***.

line sync signal In TV the signal transmitted at the end of each ***scanning line*** to initiate horizontal flyback of the scanning beam in receivers, so keeping the scanning at the receiver in step with that at the transmitter. In most TV systems the signal consists of a single pulse from blanking level to sync level as shown in *Figure L.8*, the leading edge of which locks the receiver ***line time base***.



Figure L.8 Waveform of television line sync signal

line time base In TV the circuits responsible for generating the signals causing horizontal deflection of the ***scanning beam***. In modern TV receivers the line output stage generates, in addition to the line scanning current, a direct voltage to boost the supply to the output stage, the heater supply for the picture tube, the EHT supply for the picture tube and possibly a low-voltage supply for early stages in the receiver.

liquid crystal display (LCD) A display system consisting essentially of a very thin layer of liquid sandwiched between two conducting glass plates between which the control voltage is applied. One way in which the applied voltage controls the light transmission of the device is by varying the light scattering in the liquid which is specially chosen because of its long-molecule construction. The conducting areas of the plates are such that, by applying voltages to certain of the leads, specified areas of the display can be illuminated by light transmitted through the device or reflected at the rear glass plate. Thus a seven-segment pattern can be used to give a numerical display.

Liquid crystal displays consume very little electrical power compared with ***light-emitting diode*** displays and have superseded LEDS in battery-operated calculators and digital watches.

Lissajous figures Patterns generated on the screen of a ***cathode ray tube*** when the ***electron beam*** is defected horizontally and vertically by sinusoidal signals with a simple relationship between their frequencies. Some typical patterns are shown in *Figure L.9*.



Figure L.9 Some typical Lissajous figures

Litz wire See ***skin effect***.

L-network A network consisting of one series and one shunt element. See *Figure L.10*.

load (1) Of any signal source the circuit connected across its terminals and into which it delivers power. See ***anode load***. (2) In computers and data



Figure L.10 An L-network

processing to transfer ***data*** or ***programs*** into the system's ***memory*** from a ***storage*** medium.

load line A line drawn on a family of characteristics of an active device to illustrate the relationship between the voltage across and the current in the load when an input signal is applied to the device. *Figure L.11* shows an example of a load line on a set of I_c–V_c characteristics for a ***bipolar transistor***. AB is the load line and its slope is equal to the reciprocal of the load impedance. P is the operating point where the load line meets the characteristic for the chosen value of base bias: P therefore represents the quiescent or no-signal values of voltage (V_o) and current (I_o) for the load. When a signal is applied to the base the operating point oscillates about P along the load line to an extent dependent on the input-signal amplitude.



Figure L.11 A load line on a set of I_c–V_c characteristics

Local Area Network (LAN) A ***network*** of microcomputers within a limited area such as one building or even one office within a building. LANs allow several microcomputer users to share ***peripherals*** that may be too expensive to be allocated to each individual user. Usually one computer is set aside as a ***fileserver***; its ***hard drive*** provides ***storage*** space for individual network users and may also include a 'public' area in which all network users may store and access files and may use this facility to transfer files amongst themselves. Other peripherals, such as laser printers, modems or CD-ROM drives connected to the fileserver will also be accessible to all users of the network. Facilities are usually provided for network users to send messages to other network users.

local oscillator In a ***superheterodyne receiver*** the oscillator the output of which is mixed with the received signal to give an output at the ***intermediate frequency***.

locking The process by which an oscillator can be synchronised at the frequency of a signal applied to it.

lock out See ***latch up***.

logarithmic decrement A measure of the rate of decrease of amplitude in a damped oscillation. It is equal to the natural logarithm of the ratio of one amplitude to the next in the same direction.

It is the natural logarithm of the ***damping coefficient*** or factor. In an electrical resonant circuit the logarithmic decrement is related to the circuit constants, being given by $R/2f_0L$, where R is the series resistance in the circuit, L is the inductance and f_0 the resonance frequency. This is equal to $\pi R\sqrt{(C/L)}$, where C is the capacitance in the circuit.

logic In a ***computer*** or ***data-processing equipment*** the operations chosen to carry out the functions required of the equipment. Also the physical form of the ***logic elements*** chosen for the equipment.

logical In computer ***hardware*** or ***software*** the *logical* appearance of a system or an operation is the way in which it is perceived by the user. This may contrast with the actual configuration or method of operation. See ***physical***.

logic element In ***computers*** and ***data-processing equipment*** a device used to perform a specific logic function. There are two main types: combinational elements usually called ***logic gates*** and sequential elements of which the ***bistable*** is the best-known example.

logic gate A device with a number of input terminals and one output terminal in which the state of the output signal depends in a particular manner on the states of all the input signals. For example the output may take up the 1-state only when all the inputs stand at their 1-state: this is true of an ***AND gate***.

In an electronic gate the 1-state may be the more positive or the more negative of the two voltage values selected as ***logic levels***. The choice is important because the behaviour of the gate depends on it. A gate which functions as an ***AND gate*** for ***positive logic*** behaves as an ***OR gate*** for ***negative logic***. Thus the behaviour of a particular gate cannot be predicted until the logic convention has been decided.

logic level In ***digital computers*** and ***data-processing equipment*** one of the two values of voltage or current which represent the only two possible significant states permissible on the signal lines in the equipment. One value is designated the 0 state and the other the 1 state.

log in or **log on** In computing, to establish contact with a ***host*** computer, which may be a mainframe machine serving many terminals or the ***fileserver*** of a ***local area network***. Logging on (or in) usually involves giving a user identity and a password. The identity determines which personal storage areas the user will be able to access. The password reduces the risk of unauthorised access to confidential data. A user must successfully log on (or in) before he is allowed access to the host.

log off or **log out** In computing, to terminate a session on the ***host*** computer. See ***log in***.

long-persistence tube A ***cathode ray tube*** of which the screen is coated with



Figure L.12 A long-tailed pair using two bipolar transistors

phosphorescent material as well as ***fluorescent*** so that the visible trace persists for several seconds.

long-tailed pair A phase-splitting circuit in which push-pull signals are obtained from the output circuits of two similar ***active devices*** with a common resistance in their emitter (cathode or source) circuits. The circuit (an example is shown in *Figure L.12*) has applications other than phase-splitting: for example if two equal steady signals are applied to the bases, no resulting output appears between a and b. As another example if two equal alternating signals are applied to the bases there is no output provided that the inputs are in phase. Any phase difference results in an output. Thus the circuit can be used as the basis of an FM or PM discriminator.

loss In general an indication of the extent to which the amplitude of a signal is decreased by its passage through an electronic system. More specifically the ratio of the output-signal power, voltage or current to the input-signal power, voltage or current. The ratio is usually expressed in decibels as $10 \log_{10}P_{out}/P_{in}$, $20 \log_{10}V_{out}/V_{in}$ or $20 \log_{10}I_{out}/I_{in}$.

loudness The subjective assessment of the power of a sound.

loudness level A numerical assessment of loudness. The loudness level of a sound in ***phons*** is equal to the intensity level in decibels of a 1-kHz tone which sounds, to the human ear, equally as loud as the sound, zero intensity level being taken as a sound pressure of 2×10^{-5}N/m^2. This is a subjective method of measuring loudness level. It can also he measured objectively by the use of a ***microphone***, amplifier and level meter, the circuit including a weighting network to simulate the frequency response of the ear.

loudspeaker A ***transducer*** for converting electrical audio-frequency signals into corresponding sound signals and capable of radiating enough audio-frequency power for domestic and auditorium purposes.

There is a very wide range of types of loudspeaker varying from the miniature single-unit transducers used in portable radio receivers to the large multi-unit transducer capable of high-fidelity reproduction. Loudspeakers utilise a number of different principles. See ***crystal loudspeaker, electrostatic loudspeaker, moving-coil loudspeaker.***

low-level modulation Same as ***low-power modulation.***

low-pass filter A ***filter*** designed to pass signals at frequencies below a specified cut-off frequency. Thus the passband begins at zero frequency



Figure L.13 Block symbol for a low-pass filter

and extends to the cut-off frequency. In general such filters comprise series inductors and shunt capacitors. The block symbol for a low-pass filter is given in *Figure L.13*.

low-power modulation In an AM transmitter modulation of an RF stage prior to the final high-power stage. This system has the advantage that the modulator need only be of low power but the stage following the modulated amplifier must be linear to avoid distortion of the modulation envelope. See ***high-power modulation***.

low tension (LT) The low voltage used to supply power for the heaters or filaments of electron tubes. For tubes intended for operation from batteries the low tension was usually 1.4 V or 2 V. For indirectly-heated tubes normally operated from an AC supply the low tension was usually 6.3 V.

luminance In general a measure of the light flux emitted or reflected by unit area of a source. More specifically the luminance in a given direction of a surface emitting or reflecting light is the quotient of the light flux measured in that direction and the area of the surface projected on a plane perpendicular to the direction. The subjective assessment of luminance is ***brightness***.

luminance signal (Y) In colour TV the signal which conveys information about the ***luminance*** of the elements constituting the picture. Information about the colours of the elements is contained in the ***chrominance signal***. It is the luminance signal to which a black-and-white receiver responds and which enables it to reproduce a black-and-white version of the colour picture transmitted.

luminescence General term for the emission of light from a phosphor when suitably excited. See ***fluorescence*** and ***phosphorescence***.

luminophore A luminescent material. See ***luminescence***.

lumped circuit constant ***Capacitance*** (***inductance*** or ***resistance***) of a circuit which can be treated for circuit analysis as though it were a single capacitor (inductor or resistor) connected at a point in the circuit. See ***distributed constants***.

M

machine code or **machine language** See ***computer language***.

magic-eye tuning indicator Same as ***cathode-ray tuning indicator***.

magnetic amplifier A device consisting of one or more ferromagnetic cores with windings so arranged that alternating current in one winding can be amplified by virtue of the non-linearity arising from ***magnetic saturation*** of the core. See ***saturable reactor***.

magnetic axis Of a coil carrying current, the line of symmetry of the ***magnetic flux*** pattern.

magnetic bubble In a thin layer of permeable material magnetised across its thickness. a domain in which the magnetism is in the opposite direction. A bubble can be produced by passing a current pulse through a looped conductor. The diameter of a bubble depends on the thickness and properties of the layer and the externally-applied field and can be made very small as required in ***magnetic bubble stores***.

magnetic bubble store A ***non-volatile random-access memory*** in which data can be stored in binary form, the two states being the presence or absence of a magnetic bubble. By forming the bubbles in a epitaxial layer of magnetic material on a semiconductor substrate the bubble diameter can be reduced to a few μm so that very great packing density is possible and such stores offer great possibilities for the future. The bubble store is similar to the CCD store in that it is basically a serial-in/serial-out device which can replace magnetic tape or disk but the magnetic-bubble store has the advantage over CCD that it is non-volatile.

magnetic circuit The closed path of the ***magnetic flux*** set up by a permanent magnet or a winding carrying a current. The path is usually confined to permeable material with possibly a small air gap. It is termed a circuit because the flux is determined by the quotient of the magnetomotive force and the reluctance of the magnetic circuit just as the current in an electric circuit is given by the quotient of EMF and resistance. The reluctance of a magnetic circuit is determined by the dimensions and the permeability of the material forming the closed path.

magnetic core In an ***inductor, transformer*** or similar device the ferromagnetic circuit which is provided to concentrate the ***magnetic flux*** within the region where it is required. In magnetic storage devices the core is a device of magnetic material which is required to retain two or more levels of magnetisation. In other magnetic devices, such as ***magnetic amplifiers*** and ***saturable reactors***, the core is needed to provide the non-linear relationship between magnetising force and flux essential to their action.

magnetic deflection Same as ***electromagnetic deflection***.

magnetic dipole An elementary radiator of electromagnetic waves consisting of a single infinitesimally-small loop.

magnetic drum In ***computers*** and ***data-processing equipment*** a rotating cylinder the surface of which is coated with magnetic material on which data can be stored by selective magnetisation of the surface. Normally the data is in binary form and the recording is by the orientation or the polarity of the local magnetisation of the surface.

magnetic field A region near a permanent magnet or a conductor carrying an electric current in which a magnetic pole experiences a mechanical force caused by the magnet or current.

magnetic field strength (H) At a point in a ***magnetic field*** a vector representing the magnitude and direction of the mechanical force on a unit north pole at that point. It is equal to the magnetomotive force per unit length measured along a closed path in the magnetic field.

magnetic flux The lines of force constituting a ***magnetic field.***

magnetic flux density (B) The magnetic flux per unit area normal to the direction of the lines of force.

magnetic flux leakage Same as ***leakage flux.***

magnetic focusing Focusing of the electron beam in a ***cathode ray tube*** by the use of an ***electromagnetic lens.***

magnetic hysteresis Same as ***hysteresis*** and ***hysteresis loop.***

magnetic induction Same as ***magnetic flux density.***

magnetic intensity Same as ***magnetic field strength.***

magnetic lens Same as ***electromagnetic lens.***

magnetic memory Same as ***magnetic store.***

magnetic moment (1) Of a magnet the product of the pole strength and the distance between the poles. (2) Of a ***magnetic dipole*** a vector equal to the product of the current in the loop and its area. The direction is perpendicular to the plane of the loop.

magnetic recording In general the process of impressing the characteristics of a ***signal*** on a moving magnetic medium. In particular the impressing of an audio or video signal on a magnetic tape or disk as it moves under a recording head. The recording is made by varying the intensity of magnetisation of the medium in accordance with the instantaneous amplitude of the signal.

magnetic saturation The state of a ferromagnetic material subjected to a large magnetising force in which increase in the force gives no increase in ***magnetic flux.***

magnetic screen A screen of magnetically-permeable material used to reduce the penetration of a magnetic field into a particular region.

magnetic shield (US) Same as ***magnetic screen.***

magnetic shunt A piece of magnetic material connected across a magnetic circuit to reduce the flux in that circuit.

magnetic storage A method of data storage using the magnetic properties of materials in the form of cores, films or plates, or as coatings on tapes, disks or drums. See ***floppy disk, hard disk, magnetic bubble, magnetic bubble store, magnetic core, magnetic drum, magnetic tape.***

magnetic susceptibility See ***susceptibility.***

magnetic tape A tape used for the storage of data or the recording of audio or video signals and consisting of magnetic material or coated with such material.

magnetisation In general the process of producing a temporary or permanent magnetic field in a material. More specifically the magnetisation or intensity of magnetisation of a material is the magnetic moment per unit volume or the pole strength per unit area.

magnetising force Same as ***magnetic field strength.***

magnetism The name given to a number of phenomena arising from the special properties of magnetic materials. For example these materials can be magnetised and then always come to rest in the same position when freely suspended. They can magnetise other materials. Two magnetised materials can attract or repel each other.

magnetomotive force (MMF) The force which gives rise to a ***magnetic field***. It is equal to the line integral of the magnetising force around a closed path in a magnetic field and it determines the magnetic flux according to the relationship

$$\text{magnetic flux} = \frac{\text{magnetomotive force}}{\text{reluctance of the magnetic circuit}}$$

which compares with Ohm's law for electrical current. Thus magnetomotive force is the magnetic analogue of electromotive force.

magneto-optical disk and **drive** A ***demountable*** data ***storage*** system which offers many of the advantages of ***Compact Disc*** while also erasable and recordable. To record, the appropriate spot on the disk surface is heated by a laser while a localised magnetic field changes its crystal structure, affecting its reflective properties. The disk is read using a laser as in Compact Disc; indeed many 5-inch magneto-optical drives can also read Compact Discs. The Sony *Mini-Disc*, intended as a ***digital audio*** recording system for portable and automotive equipment, uses 2.5-inch disks holding 125 Mbytes which, with real-time ***companding***, allows about 75 minutes of stereo audio. 5-inch disks for computer use hold a nominal 650 Mbytes.

magnetostriction The change in dimensions of a piece of magnetic material when it is magnetised. The effect is most marked in nickel and is exploited in magnetostriction loudspeakers and oscillators.

magnetron A diode tube in which the electron stream is subjected to a ***magnetic field*** at right angles to the electric field. In its simplest form the magnetron consists of a diode with a cylindrical ***anode***, the ***cathode*** lying along the axis of the cylinder. The anode is split into two or more segments. A strong magnetic field is set up, parallel to the axis of the cylinder, by an external magnet. The anode is positively charged to attract electrons liberated from the cathode but the magnetic field causes the electrons to pursue curved paths around the cathode and, depending on the relative strengths of the electric and magnetic fields, they may not meet the anode at all and return to the cathode. If tuned circuits are connected between neighbouring segments of the anode, the electron stream becomes velocity modulated as it moves around the cathode and in this way bunching and oscillation can occur.

magnification factor (1) See ***amplification factor***. (2) See ***Q-factor***.

mailmerge The process of merging data from a ***database*** repeatedly into copies of a generic ***document*** for printing. Often the document is a standard letter; the data being merged consists of the necessary personal details for the individual recipients. Each letter printed will therefore carry the appropriate details for its intended recipient.

mainframe computer See *digital computer*.

mains hum See *hum*.

main storage Of a ***digital computer*** the internal store associated with the ***central processor***.

mains unit An assembly of components designed to derive from a mains input outputs suitable for operating electronic equipment. For example a mains unit for transistor equipment requires basically a mains transformer, rectifier and smoothing capacitor suitable for the required direct voltage. For electron-tube equipment in addition to the HT (direct) supply, a low-voltage AC supply was required for the tube heaters and this was obtained from a winding on the mains transformer.

maintaining voltage Of a ***gas-filled tube*** the voltage between the ***electrodes*** when the tube is operating normally. The maintaining voltage is independent of the current taken by the tube over a considerable range of current.

maintenance test A test carried out regularly during the life of an equipment or component to check that its performance is still within tolerance.

majority carriers In an ***extrinsic semiconductor*** the type of charge carrier which outnumbers the other type. For example in ***n-type semiconductors*** the majority carriers are electrons and in ***p-type semiconductors*** they are holes.

majority gate A ***logic gate*** with several inputs and one output which gives a logic-1 output only when more than half the inputs stand at logic-1.

Mallory cell Same as ***mercury cell***.

marginal relay A relay which operates when a predetermined change in the coil current or voltage occurs.

maser (microwave amplification by stimulated emission of radiation). A microwave amplifier which makes use of the radiation emitted by certain atoms or molecules when transitions occur from a higher to a lower energy state. A feature of the amplifier is direct interaction between electromagnetic waves and atoms: if the waves are of the right frequency they can stimulate high-energy electrons to release their energy in the form of electromagnetic waves thus amplifying the stimulating signal. Amplification can be almost noise-free particularly if the device is operated at a very low temperature. The block symbol for a maser is shown in *Figure M.1*.



Figure M.1 General block symbol for a maser

masking (1) In acoustics the apparent suppression of a weak sound by a strong one. More specifically it is the amount (in dB) by which the threshold of audibility of a sound is raised by the presence of the other (masking) sound. (2) In colour TV, alteration of the colour rendering by deliberate ***cross-coupling*** between the three primary colour channels. Masking is used to improve the colour rendering of cinema film when transmitted by colour television.

mass In a mechanical oscillating system a property of a body in motion which enables it to resist changes in velocity and is measured by the ratio of force to rate of change of velocity, i.e. the ratio of force to acceleration. Mass is analogous to inductance in an electrical oscillating system. A moving mass possesses kinetic energy just as an inductor carrying current stores energy in the associated magnetic field.

mass storage Same as ***bulk storage***.

master clock Same as ***clock***.

master oscillator In a radio transmitter an oscillator used to determine the frequency of the ***carrier wave***. Such an oscillator requires great frequency stability to maintain the carrier wave on its allotted frequency.

master-slave operation In general a system of two or more devices in which one (the master) controls the operation of the others (the slaves).

match gate Same as equivalence element.

matching (1) The process of ensuring that maximum power is transferred from a generator to its load. As an example an ***L-network*** can be used to match the generator impedance to the load impedance at a particular frequency. Where matching is necessary over a wide frequency band a transformer can be used to couple generator to load. Such matching is used to connect an electron tube to a ***loudspeaker***. (2) The selection of two devices with approximately-equal characteristics. For example two matched transistors are essential in a ***class-B*** stage to minimise distortion.

matrix Mathematically a two-dimensional ***array*** of quantities manipulated in accordance with the rules of matrix algebra. In electronics the term is loosely used to mean any coder or decoder. More specifically in computers a rectangular logic array of intersections between a number of input leads (arranged as rows) and a number of output leads (arranged as columns). ***Logic elements*** are situated at some of the intersections to enable a single input to produce a number of outputs (decoder use) or a number of inputs to give a single output (coder use).

Maxwell bridge An AC bridge network in which one arm consists of ***inductance*** and resistance in series, the opposite arm consists of ***capacitance*** and resistance in parallel, the remaining two arms being resistive.

The bridge is illustrated in *Figure M.2* and is used for the measurement



Figure M.2 A Maxwell bridge

of inductance (in terms of a known capacitance) or capacitance (in terms of a known inductance), the relationship at balance being

$$\frac{L}{C} = R_2R_4 = R_1R_3$$

m-derivation A method of modifying the prototype L half section of a ***filter*** so as to give a sharper cut-off at the edges of the passbands and a better impedance characteristic. The reactance of the series arm (S) of the L section is reduced to mS (m being less than unity) and that of the shunt arm (P) is increased to P/m; in addition a new reactance is added to the half section to give infinite attenuation at a frequency beyond the ***cut-off frequency***.

In series m-derivation the new reactance has a value of $S(1-m^2)/m$ and is connected in series with the shunt element P/m to form an acceptor tuned circuit across the network. In shunt m-derivation the new reactance has a value of $Pm/(1-m^2)$ and is connected in parallel with the series reactance mS to form a rejector tuned circuit. These modifications to the prototype half section (illustrated in *Figure M.3*) do not affect the cut-off frequency of the filter or its characteristic impedance. The frequency of infinite attenuation can be placed anywhere within the stopband by suitable choice of the value of m: the smaller m is made, the nearer is this frequency to the cut-off frequency.



Figure M.3 A prototype L-network (a) and the modifications for series m-derivation (b) and shunt m-derivation (c)

It is common practice in filter design to employ m-derivation in the final half-section of a constant-k filter, which can then be satisfactorily terminated in a pure resistance. The m-derived half-section provides a satisfactory termination for the constant-k sections over most of the passband if m is made equal to 0.6. The m-derived half section also improves the steepness of attenuation outside the passband.

mean time between failures (MTBF) In general a measure of the reliability of an equipment. More specifically it is the time to the first failure or, if the equipment can be repaired, the average time between failures. The MTBF of equipment is a statistical estimate based on the MTBFs of the components in it.

mechanical impedance The complex ratio of the alternating force applied to a vibrating system to the resulting alternating velocity in the direction of the force. By analogy with electrical impedance, mechanical impedance is made up of mechanical resistance (e.g. friction) and mechanical reactance, and the latter can arise from mass (mechanical analogue of inductance) or from compliance (mechanical analogue of capacitance).

medium-scale integration (MSI) See ***monolithic integrated circuit.***

megatron Same as ***lighthouse tube.***

Meissner oscillator An oscillator in which the *LC* circuit which determines the frequency of oscillation is coupled to the input and output circuits of the ***active device*** by separate coupling coils. There is therefore no physical connection between the frequency-determining circuit and the active device. The circuit diagram of a Meissner oscillator is given in *Figure M.4.*



Figure M.4 Circuit diagram of a Meissner oscillator

melt-back transistor A method of manufacturing ***bipolar transistors*** in which the junctions are formed by allowing molten ***semiconductor*** material containing donor and acceptor impurities to solidify. The distribution of the impurities changes on solidification and it is thus possible to form the required npn or pnp structure.

memory A deprecated term for ***store*** but one which is likely to persist in such phrases as ***random-access memory*** and ***read-only memory.***

memory cell The basic unit of a ***store.*** In a binary system the cell has two states representing the two binary digits. In a semiconductor ***dynamic RAM*** the cell may consist of a single capacitor which represents logic 1 when charged and logic 0 when discharged but in a practical cell there are other active components which provide external connections to the capacitor for writing and reading purposes. Alternatively a ***bistable circuit*** consisting of two bipolar or two field-effect transistors can provide the basic storage unit as in a ***static RAM.*** Again additional components are required to provide loads for the transistors and to provide external connections so that the total number of transistors may be six per cell.

menu In computers and microprocessor-controlled equipment, a list of options or commands that appears in the display. Using ***keyboard*** buttons or a ***pointing device*** such as a ***mouse,*** the user positions a pointer over or adjacent to the required menu option to select it and then presses a button to initiate the selected action.

mercury arc rectifier (MAR) A rectifier in which the rectification occurs via an arc between an ***anode*** and a mercury pool acting as ***cathode***. The discharge occurs in ionised mercury vapour and the means adopted to initiate the discharge depends on the type of rectifier. See ***ignitron*** and ***excitron***. Very little voltage drop occurs across a mercury arc rectifier which is therefore very efficient.

mercury cell A primary voltaic cell in which the ***cathode*** is a mixture of mercuric oxide and graphite (usually deposited on a metal base), the anode is of zinc and the electrolyte is a solution of potassium hydroxide.

The cell has an EMF of 1.25 V which remains remarkably constant throughout its life. For a given volume the cell has much greater capacity than the ***Leclanché cell***: expressed differently the mercury cell can be made very small whilst giving a useful life. This makes it useful in applications where small size is important, e.g. in cameras and watches. Such cells are also used to power portable electronic equipment.

mercury-pool cathode A cathode in the form of a pool of mercury in an arc discharge tube such as a mercury arc rectifier. Emission from such a ***cathode*** occurs as a result of bombardment of the mercury surface by positive ions resulting from ionisation of the mercury vapour within the tube and from thermionic emission from hot spots on the surface caused by this bombardment.

mesa transistor A diffused ***bipolar transistor*** in which unwanted regions of semiconductor are etched away leaving the base and emitter regions as plateaux above the collector region. *Figure M.5* gives a typical cross section of a mesa transistor.



Figure M.5 Simplified diagram illustrating the structure of a mesa transistor

mesh In a ***network*** those elements which form a simple closed loop. For example in the network shown in *Figure M.6* there are two meshes as indicated by the arrows.

meta-data ***Data*** which describes data. See ***repository***.

metal-film resistor A resistor made by screening a paste containing metals in a pattern on a ceramic base and firing it at a high temperature. See ***thick-film circuit, thin-film circuit***.



Figure M.6 An example of a two-mesh network

metal-oxide-semiconductor transistor (MOST or MOSFET) Same as ***insulated-gate field-effect transistor.***

metal rectifier A rectifier in which ***unilateral conductivity*** occurs between the inner surface of a coating on a metal and the metal itself. Such a junction constitutes a single rectifier cell and in practical rectifiers the cells are stacked in series to provide the required voltage rating.

Examples of metal rectifiers are the copper-oxide rectifier in which the coating is of copper oxide on copper and the selenium rectifier in which the coating is a selenium alloy on iron. Both have now been superseded by silicon semiconductor rectifiers which are much smaller and more efficient.

metal-semiconductor field-effect transistor (MESFET) A microwave ***field-effect transistor*** with ***gallium arsenide*** as the semiconductor and with a reverse-biased ***Schottky*** junction as the gate. The high mobility of electrons in gallium arsenide and the use of the ***unipolar*** principle gives such transistors a better performance at microwave frequencies than silicon bipolar or field-effect transistors.

micro-alloy diffused transistor (MADT) A ***micro-alloy bipolar transistor*** in which the base wafer is initially given a graded impurity concentration by diffusion.

micro-alloy transistor A ***bipolar transistor*** manufactured by electrolytically etching a wafer of semiconductor material to produce the required thickness of base region and then electrodepositing and subsequently alloying a trivalent or pentavalent element on opposite faces to form the emitter and collector regions.

microcircuit Same as ***monolithic integrated circuit.***

microcomputer A ***computer*** in which the ***central processing unit*** is a ***microprocessor.***

micro-electronics A branch of electronics concerned with the design, manufacture and applications of devices of very small dimensions such as integrated circuits.

microphone An electro-acoustic ***transducer*** for converting sound waves into corresponding electrical signals. Microphones can respond to the pressure of the sound wave or the particle velocity. See ***pressure operation, pressure-gradient operation.***

In general the electro-acoustic energy conversion does not occur in one step. Usually the sound waves strike a diaphragm causing it to vibrate (so creating mechanical energy), the vibrations being communicated to some form of generator which delivers the electrical output. A number of different types of generator are used in microphones. See ***crystal microphone, electrostatic microphone, moving-coil microphone.***

microphonics (US) Same as ***microphony.***

microphony Undesired modulation of the output current of an ***electron tube*** caused by vibration of the ***electrodes*** as a result of mechanical shock. The most familiar example is the 'pong' heard from a ***loudspeaker*** when a microphonic tube in the amplifier is struck. In an extreme form the tube may respond to sound waves from the loudspeaker so giving rise to acoustic feedback and possibly sustained oscillation.

microprocessor A small ***digital computer*** consisting essentially of a ***central processing unit*** with a limited amount of storage and some interface connectors. Microprocessors are now extensively used wherever mathematical and/or logic operations are required to be carried out in sequence and/or under the control of one or more input signals, e.g. in controlling automatic washing machines or machine tools.

It is now possible to include all the components necessary in a microprocessor in a single ***monolithic integrated circuit.***

microwaves Electromagnetic waves with a wavelength smaller than approximately 30 cm, i.e. with a frequency above approximately 1000 MHz.

midicomputer See ***digital computer.***

Miller effect Increase in the effective input capacitance of an ***electron tube*** caused by ***feedback*** from the anode circuit via the internal capacitance between ***anode*** and ***grid***. Such feedback can make the input capacitance many times greater than the physical grid-cathode capacitance.

Miller integrator A circuit in which an external capacitor is connected between ***grid*** and ***anode*** of a ***pentode*** to increase ***Miller effect***. The ***feedback*** introduced by this capacitor has the effect of generating a linear fall of anode potential when anode current is started, e.g. by a positive pulse applied to the suppressor grid. A rectangular pulse applied to the suppressor grid thus generates a sawtooth wave at the anode. Mathematically a ***sawtooth*** is the time integral of a rectangular wave and this accounts for the name of the circuit.

Miller time base See ***Miller transitron.***

Miller transitron A ***Miller integrator*** circuit made astable by capacitively coupling the screen grid to the suppressor grid. With suitable potentials applied to the electrodes the circuit (*Figure M.7*) generates a linear



Figure M.7 Basic circuit for a Miller transitron

sawtooth at the ***anode*** and a rectangular pulse at the screen grid. Thus the circuit is suitable as an oscilloscope time base, the sawtooth providing horizontal deflection voltages and the screen grid giving flyback blanking pulses. The circuit can readily be synchronised at the frequency of a regular signal applied to the suppressor grid.

minicomputer See ***digital computer.***

Mini-Disc See ***magneto-optical disk.***

minimum phase-frequency characteristic Of the infinite number of phase-frequency characteristics which can be associated with a given attenuation-frequency characteristic, the particular characteristic for which the phase shift at each frequency is the minimum value possible.

minimum phase network A ***network*** for which the attenuation-frequency characteristic is associated with its ***minimum phase-frequency characteristic.***

minority carriers In an ***extrinsic semiconductor*** the type of ***charge carrier*** which is outnumbered by the other type. For example in an n-type semiconductor the minority carriers are holes and in a p-type semiconductor they are ***electrons.***

mismatch factor (or ratio) At the junction of a source of power and a load, and at a particular frequency, the ratio of the current delivered to the load to the current which would be delivered to the load if it were perfectly matched to the generator. The ratio is given by

$$k = \frac{2\sqrt{(Z_1 Z_2)}}{Z_1 + Z_2}$$

where Z_1 is the generator impedance and Z_2 is the load impedance. See ***reflection loss.***

mixer (1) In radio or TV equipment which can combine two or more ***signals*** and permits their relative levels to be adjusted to form a composite signal giving the desired sound or visual effect. The term is also used to mean the operator of the mixing equipment.

(2) A device which accepts two inputs at different frequencies and generates an output at the combination frequencies. In particular the RF mixer in a ***superheterodyne receiver*** accepts an input from the antenna (or an RF amplifier) and from the local oscillator and generates an output at the sum or difference frequency which is equal to the intermediate frequency.

mnemonic In general anything that is deliberately made easy to remember. In computing, abbreviations for the various operations which a ***central processing unit*** can execute. They often consist of just three letters, such as ADC for 'Add with carry' and JMP for 'Jump'. These mnemonics and their ***arguments*** are used to build up machine-code programs in assembly language. See ***computer language.***

modem (contracted form of **modulator/demodulator**) An item of electronic equipment used to enable ***digital*** signals to be transmitted over ***analogue*** voice-frequency circuits. A modem operating as a ***modulator*** is required at the transmitting end and a second, acting as demodulator, at the receiving end. See ***modulation, demodulation.***

modulated amplifier In a transmitter a carrier-wave amplifier in which the modulation is introduced. In Heising modulation the amplifier is an *electron tube*, the *carrier wave* being applied to the grid and the modulating wave to the anode.

modulating signal The signal which causes a characteristic of the *carrier wave* to be varied so effecting modulation of the carrier.

modulation The process by which a characteristic of one signal is varied in accordance with another signal. In radio transmission the amplitude or frequency of the *carrier wave* is varied in accordance with the signal it is required to transmit (the *modulating signal*).

modulation depth Extent to which the amplitude of a *carrier wave* is modulated. If expressed quantitatively the modulation depth is equal to the *modulation factor*.

modulation envelope Of an amplitude-modulated wave the curve formed by joining up the peak values of the modulated wave. In *Figure M.8* the dashed line gives the shape of the envelope for a sinusoidal modulating signal.



Figure M.8 An amplitude-modulated wave: the dashed line indicates the modulation envelope

modulation factor For an amplitude-modulated wave the ratio of the departure from the unmodulated carrier amplitude to the carrier amplitude. Thus in *Figure M.9* the modulation factor is a/A. When $a = A$, the carrier amplitude swings between twice its unmodulated value and zero. Attempts to increase the *modulation depth* beyond this value cause the carrier to be reduced to zero for appreciable periods. This leads to distortion of the *modulation envelope* and hence of the received signal. Thus the maximum practical value of the modulation factor is unity and smaller values are usually expressed as percentages.



Figure M.9 The modulation envelope of an amplitude-modulated wave: the modulation factor is given by a/A



Figure M.10 Spectrum diagram for a frequency-modulated wave with a modulation index of 5

modulation index In ***angle modulation*** the ratio of the frequency deviation to the modulating frequency. The modulation index determines the side-frequency structure of the modulated wave. As an example for a modulation index of 5 the structure is as shown in *Figure M.10.* This applies, for example, when the frequency deviation is 75 kHz (the rated maximum in most sound-broadcasting frequency-modulated services) and the modulating frequency is 15 kHz (the upper limit in high-quality broadcasting).

modulation percentage The ***modulation factor*** expressed as a percentage. 100% modulation is equivalent to a modulation factor of unity.

modulator In general any device for achieving ***modulation***. The term has two different specific meanings:

(1) In a transmitter it is the amplifier which applies the modulating signal to the modulated amplifier. (See *Figure M.11*).



Figure M.11 Block diagram illustrating the terminology used in radio transmitters

(2) In telephony it is a device which accepts two input signals and produces an output consisting of one signal modulated by the other. See ***balanced modulator, ring modulator.***

modulo 2 Same as ***OR gate***.

moiré In TV an effect caused by interference between two regular patterned structures. For example a moiré effect can be caused by beats between a pattern in the original scene (say a check suit) and the line structure of the reproduced picture.

monaural Listening with one ear only. Monaural should not be confused with ***monophonic***. See ***binaural.***

monitor Any device or routine used to observe, supervise, control or check the operation of equipment.

monitoring In general the checking of a signal whilst it is being transmitted or recorded to observe some characteristic of the signal, e.g. its information content, times of start or finish, its level (signal strength), technical quality. For quality checking, high-grade monitoring equipment (amplifiers, receivers, loudspeakers, picture-display tubes etc) is essential. Monitoring can be carried out by human observers or by equipment designed to give warnings or take action if the monitored characteristic necessitates it.

monochrome In TV a system in which the transmitted information is confined to the ***luminance*** of the scene. No colour information is transmitted. A monochrome system is therefore a black-and-white system. The term is unfortunate because monochrome means literally light of a single wavelength whereas white light contains a range of wavelengths. In this dictionary therefore the term 'black-and-white' is preferred.

monolithic Term applied to an ***integrated circuit*** in which all the elements are formed *in situ* within a single semiconductor chip.

monolithic integrated circuit A combination of interconnected active and passive devices fabricated on a continuous substrate, usually of silicon. As an example, an integrated circuit may contain several transistors and resistors interconnected to form an amplifier (linear IC) or a collection of logic gates (digital IC). Integrated circuits are manufactured by the ***planar process*** and there is little limit to the degree of complexity and miniaturisation possible by the process.

Although attempts were made to produce integrated circuits in the 1950s it was not until the planar process was developed in 1960 that monolithic structures became possible. These early ICs were digital circuits (RTL, TFL, ECL, etc) composed largely of bipolar transistors and resistors. The number of components per chip was less than 100—a density known as small-scale integration (SSI).

In 1966 MOS transistors were introduced. These had the advantage of requiring fewer diffusions in manufacture and occupied less area on the chip. On the other hand they were slower in operation than bipolar transistors. It was now possible to increase the component density to a few hundreds per chip—a level called medium-scale integration (MSI).

The demand from the computer industry was for still greater component density and by 1969 a single IC containing more than 10000 MOS transistors was available. This stage of development became known as large-scale integration (LSI) and by 1975 component densities were approaching 100000 per chip.

Since 1980 still further miniaturisation has been achieved and component densities of over a million components per chip are possible. This is termed very large scale integration (VLSI). The point has now been reached where integrated circuits require more input and output leads than can be accommodated on a reasonably-sized ***dual-in-line package***. Alternative methods of packaging such as the ***chip carrier*** are being introduced.

There is no doubt that the small space occupied by the modern computer and its inherent reliability are attributable to the use of monolithic integrated circuits.

So far only digital ICs have been mentioned but there have also been significant developments in ICs for linear equipments. The first linear ICs were *operational amplifiers* and towards the end of 1960 ICs were developed for use in radio and television receivers. There is little limit to the complexity of ICs which can therefore be designed to perform many of the functions in receivers, high-fidelity equipment and video cassette recorders to improve their performance, reliability and ease of operation.

monophonic Single-channel sound signal. This is the system used in long-, medium- and short-wave broadcasting. The term is also used to describe the single-channel audio signal derived by a monophonic receiver from a stereo transmission. In the pilot-tone system used for stereo transmission the monophonic signal is the sum of the left and right channels.

monoscope An electron tube containing a target on which a pattern or photograph is printed and which, when scanned by an *electron beam*, generates a picture signal corresponding to the printed image. The tube is generally a high-velocity type and the pattern is printed in a pigment which modifies the *secondary-emission ratio* of the target. Such tubes are useful in TV services because they can replace a complete camera channel when a stationary pattern is to be transmitted.

monostable circuit A circuit with two possible states, one stable and the other unstable. The circuit is normally in its stable state but can be switched to the unstable state by an external signal. It cannot remain in the unstable state, however, and automatically reverts to the stable state, where it remains unless triggered by another external signal.

The circuit takes an appreciable time to return to the stable state and this period is equal to the duration to the unstable state. It can be given any desired value by suitable choice of component values. For this reason monostable circuits are used as delay generators, i.e. generators of pulses of a predetermined duration, the leading edge of which is coincident with that of the trigger pulse. See *multivibrator*.

mosaic Of a *camera tube*, an *electrode* consisting of a very large number of individually-insulated photo-emissive globules on which the optical image is focused. *Photo-electrons* released from the globules in accordance with the amount of light falling on them leave a *charge image* on the mosaic surface.

motherboard The main circuit board in a *computer* on which the *central processing unit* is mounted; most other boards containing *memory* and essential *interface* circuitry plug into edge connectors on the motherboard.

Motion Picture Experts Group (MPEG) A standard for the *storage* and transmission of digitised *full motion video* in a highly *compressed* format. The compressed video is transmitted over telephone lines or read from a storage medium such as compact disk and expanded to full screen size in real time. Individual frames are compressed using the JPEG process (see *Joint Photographic Experts Group*); in frame sequences only the differences between successive frames are stored.

motional impedance Of a *transducer*, the complex impedance obtained by subtracting its impedance when the moving parts are held still from its impedance when the parts are free to move.

motorboating In an audio amplifier self-oscillation at a very low frequency caused by *instability*. The sound of such an oscillation is similar to that of a motorboat engine.

mount In computing, to initialise a ***drive*** or the storage medium e.g. floppy disk, installed in it. This usually involves ***cataloguing*** the ***root directory***.

mouse A small device moved over a desk top which causes a pointer to move across the screen of a visual display unit in the corresponding direction. The mouse may be connected to the computer by a flexible lead (tail) or via an infra-red link. The mouse greatly simplifies and speeds up computer operations and is much favoured in CAD.

moving-coil loudspeaker A loudspeaker in which the diaphragm is attached to a coil flexibly mounted within the magnetic field of a permanent or electromagnet and which moves in sympathy with the audio signal applied to it.

This is the most popular type of loudspeaker and its construction is illustrated in *Figure M.12*. The magnet system is arranged to give a radial field within a small annular gap in which the speech coil is situated.



Figure M.12 Construction of a moving coil loudspeaker

moving-coil microphone A microphone in which the diaphragm is attached to a coil flexibly mounted within the magnetic field of a permanent magnet and which moves when sound waves strike it so inducing corresponding EMFs in the coil. The basic form of the microphone is thus similar to that of a ***moving-coil loudspeaker*** but the diaphragm is made very small so that the microphone has negligible effect on the sound field to which it responds.

moving-coil pickup A ***pickup*** in which the movements of the reproducing stylus are communicated to a coil flexibly mounted within the field of a small permanent magnet so giving rise to corresponding EMFs in the coil.

moving-iron loudspeaker An early form of loudspeaker in which the diaphragm is attached to a soft-iron armature flexibly mounted between the pole pieces of a permanent magnet and within the field of a stationary winding carrying the audio signal to be reproduced. The magnetic poles induced in the armature by the current in the coil react with those of the



Figure M.13 Construction of a moving-iron loudspeaker

pole pieces to cause vibration of the armature and corresponding movement of the diaphragm. See *Figure M.13*.

moving-iron pickup A ***pickup*** in which the movements of the reproducing stylus are communicated to a small armature flexibly mounted below the pole pieces of a small permanent magnet and within a stationary coil. The construction is similar in principle to that of the ***moving-iron loudspeaker***. Movement of the armature causes induced magnetism which links with the coil to give corresponding induced EMFs.

moving-magnet pickup A ***pickup*** in which the movements of the reproducing stylus are communicated to a small permanent magnet situated within a stationary coil. The field of the magnet embraces the coil and movement of the field causes corresponding EMFs to be induced in the coil.

m signal In stereophonic sound broadcasting one half of the ***sum signal***.

multi-cavity klystron A ***klystron*** in which the bunched ***electron beam*** excites a number of catcher resonators. By stagger-tuning the ***catchers***, i.e. tuning them to different frequencies it is possible to give the klystron a wide bandwidth such as, for example, that required in a television transmitter. Four or five resonators are commonly used and such klystrons can deliver 50 kW output for 1 W input power over a bandwidth of 5 MHz between frequencies of 500 and 1000 MHz.

multi-cavity magnetron See ***cavity magnetron***.

multimedia A programme in which information or entertainment is presented through several media such as video, still pictures, text and sound.

multimedia PC An IBM ***PC-compatible*** computer equipped for multimedia applications. In practice this means that it is fitted with a ***soundblaster*** or similar sound generation system and suitable speakers and a ***CD-ROM*** drive. It also requires certain minimum requirements for memory, hard disk capacity and microprocessor.

multipath distortion In FM radio reception distortion of the detector output caused by simultaneous pickup of the wanted signal via two or more paths.

The wavelength used for conventional VHF broadcasting is approximately 3 metres (10 feet). Any object with dimensions comparable to or larger than this, such as a hill, a building or even a car, can reflect such waves. Consequently a mobile FM receiver such as a car radio or a portable radio fitted with an omnidirectional antenna may pick up the required transmission from a number of paths—one directly from the transmitter and the others after one or more reflections. Moreover, the pattern of reflection changes as the receiver moves. Because of their longer path length, the reflected signals are delayed with respect to the direct signal and interference between the direct and delayed signals can cause serious harmonic distortion in the demodulated audio signal.

multiple electron tube A tube in which a number of electrode systems are contained within a single envelope. The systems may share a common ***cathode*** or may have separate cathodes. Examples of such tubes are double-diode-triodes, double-triodes and triode-hexodes.

multiplexing (MUX) The simultaneous transmission of two or more ***signals*** along a common path. The signals may share the path on a time-division basis or on a frequency-division basis. See ***frequency-division multiplex, time-division multiplex.***

multiplier A device with two inputs, the output of which is substantially equal to the product of the input signals. See also ***electron multiplier, frequency multiplier.***

multitasking Of a computer, capable apparently of performing several tasks simultaneously. Such an ability is apparent rather than real since most ***central processing units*** are capable of executing only one instruction at a time. In a multitasking operating environment either the processor divides its time between tasks on a rota basis or, more commonly, one task is given priority, the others being serviced as ***background tasks*** when the processor can be spared.

multivibrator A circuit comprising two ***active devices***, the output of each being coupled to the input of the other. As a result of the large degree of ***positive feedback*** thus caused the circuit has only two possible states. If the active devices are electron tubes or transistors of the same type, then in one state device 1 is driven hard into conduction whilst device 2 is cut off and in the alternative state device 1 is cut off whilst device 2 is conductive. If complementary transistors are used, then both are cut off in one state of the circuit and both are conductive in the other. If the inter-device couplings are direct, as in *Figure M.14*, both states are stable and the resulting circuit is bistable. Triggering signals are thus needed to switch the states making the circuit useful as a binary counter or as an element in a store.

If one inter-device coupling is direct and the other capacitive, then one state is stable and the other unstable. The circuit is now ***monostable*** and will always revert to the stable state having been put into the unstable state



Figure M.14 A bistable multivibrator circuit

by a triggering signal. Such a circuit can be used as a delay generator.

Finally if both inter-device couplings are capacitive both states are unstable and the circuit is ***astable***, generating pulses continuously without the need of triggering pulses. It can, however, readily be synchronised at the frequency of any recurrent signal applied to it.

mu-metal A nickel alloy of high ***permeability*** and low ***hysteresis*** loss used for the construction of ***magnetic screens***.

Musical Instrument Digital Interface (MIDI) A standard that allows electronic musical instruments (such as ***synthesisers***) to be connected to each other or to a computer. Via MIDI one instrument may control another or a computer may control one or more instruments or may record what is being played for subsequent editing or playback.

muting The suppression of the audio channel of a device. FM receivers are sometimes equipped with a muting facility which suppresses the audio output unless received signals exceed a certain strength. Thus signals emerge from a silent background when the tuning is adjusted.

mutual conductance (g_m) Of an ***active device*** the ratio of a small change in the current in one electrode to the small change in voltage at another electrode which gives rise to it. Its value is usually quoted for a specific operating point. *Figure M.15* gives an example of the drain current-gate voltage characteristic for a ***field-effect transistor***. The mutual conductance at the operating point P is given by the slope of the tangent to the curve at that point, i.e. by SQ/QR. It is usually quoted in milliamps per volt and is taken as a figure of merit for the transistor.



Figure M.15 The mutual conductance of an FET is given by the slope of the tangent to the I_d–V_{gs} characteristic curve at the operating point

mutual impedance Between any two pairs of terminals in a ***network*** the ratio of the open-circuit voltage between either pair to the current at the other pair, all other terminals being open-circuited.

mutual inductance A property of two circuits such that a change of current in either of them causes an EMF to be induced in the other. The induced EMF is given by $M\mathrm{d}i/\mathrm{d}t$, where M is the mutual inductance and i is the current in one of the circuits. The most common application of mutual inductance is in the transformer in which two windings are wound on a common magnetic core to maximise mutual inductance.

N

NAND gate (NOT-AND gate) A ***logic gate*** which gives a logic-0 output when, and only when, all the input signals are at logic 1. It may be regarded as an ***AND gate*** followed by a NOT or logic negating stage as suggested by the graphical symbol shown in *Figure N.1*. See ***logic level***.



Figure N.1 Graphical symbol for a NAND gate

natural air cooling Same as ***convection cooling***.

natural frequency Of an oscillatory system, the frequency of free oscillations. Thus it is the frequency at which the system oscillates when shock-excited. A system can have more than one natural frequency and the natural frequency of an antenna is the lowest frequency at which it resonates without the addition of inductance or capacitance.

natural period The reciprocal of the ***natural frequency***.

n-channel metal-oxide-semiconductor (NMOS) A form of construction for ***logic monolithic integrated circuits*** using ***n-channel field-effect transistors***. These have the advantage over PMOS of higher speed of operation (the charge carriers, being ***electrons***, have higher mobility than ***holes***) and have largely replaced PMOS.

Near Instantaneous Compression and Audio Multiplex (NICAM) A digital coding system for the inclusion of sound or data signals within a television broadcast transmission. The signal, typically two-channel stereo, is ***quantised*** to 14 bits and ***compressed*** to 10 bits. Left- and right-channel data is sent alternately in blocks of 32 11-bit (10 data bits plus one parity bit) words, each lasting 1 ms and containing, with control and framing codes, 728 bits. The NICAM carrier is ***quadrature modulated*** by the interleaved and scrambled binary data and transmitted at low level adjacent to the normal f.m. sound carrier.

negate In logic to perform the NOT operation. Thus an AND gate followed by a negating operation becomes a NOT-AND or ***NAND gate***. The symbol for negation is shown in *Figure N.2*.



Figure N.2 Graphical symbol for negation

negative AND gate Same as ***NAND gate***.

negative feedback (NFB) ***Feedback*** in which the signal returned to the earlier stage in the amplifier opposes the input signal at that point. Negative feedback has the effect of reducing the gain of that portion of the amplifier included within the feedback loop. It also improves the linearity and makes the frequency response more level.

Negative feedback has an effect on the output impedance of that stage of the amplifier from which the signal is derived and on the input impedance of the stage at which it is re-introduced. The effect on output impedance depends on whether the feedback signal is proportional to the output voltage (see ***voltage feedback***) or to the output current (see ***current feedback***). The effect on input impedance depends on the way in which feedback signal is re-introduced into the amplifier: if it is connected in series with the input signal it increases input impedance; if it is connected in parallel with the input signal it reduces the input impedance.

Negative feedback is extensively used in the design of electronic equipment. It can be used to give an amplifier a required value of gain, a required value of linearity, a required shape of frequency response (by making the feedback path frequency-discriminating) and required values of input and output impedance. These properties are obtained by suitable choice of ***passive components*** in the feedback circuit and they are therefore independent of the properties of the active devices contained within the feedback loop—a very useful feature in the mass production of electronic equipment.

negative image An image in which white areas are reproduced as black and black areas as white as in a negative photographic film. The effect can occur in TV images, when, for example, the picture tube has low emission.

negative logic A ***computer*** or ***data processing*** system in which the more negative of the two voltages selected as the logic levels is designated the 1 state.

negative modulation In TV transmission ***amplitude modulation*** in which increased picture brightness results in decreased carrier amplitude. This is the system of modulation used in the British 625-line and in most of the world's television systems.

negative OR gate Same as ***NOR gate***.

negative resistance Property of a device in which an increase in applied voltage brings about a decrease in the current through it. The current-voltage characteristic for such a device has a negative slope as shown in *Figure N.3*. Electron tubes can be operated so as to produce a region of negative resistance (see ***dynatron***). A semiconductor example with a similar region is the ***tunnel diode***. A most useful property of a negative-resistance device is that a simple oscillator can be made by connecting a parallel resonant circuit across it.



Figure N.3 A current-voltage characteristic with a negative slope

negator Same as ***NOT gate***.

NEITHER-NOR gate Same as ***NOR gate***.


Figure N.4 Graphical symbol for a neon tube

neon tube A gas discharge tube containing two ***electrodes*** and filled with neon at low pressure. When a voltage exceeding the ***ionisation voltage*** is applied between the electrodes a discharge occurs giving a characteristic red glow. Such tubes are used in neon signs and as indicators in electronic equipment. When the discharge occurs the voltage across the electrodes remains constant and the tube can therefore be used as a voltage reference. The graphical symbol for a neon tube is given in *Figure N.4*.

neper The basic unit of a logarithmic scale used to express ratios of voltages, currents and analogous quantities. The neper is based on the use of natural logarithms and is named after their inventor, John Napier. Two voltages V_1 and V_2 are related by n nepers when $\log_e(V_1/V_2) = n$. The number of nepers is simply the natural logarithm of the voltage ratio.

In conditions of equal impedance (as is usual for input and output quantities in telecommunications) a voltage or current ratio is equal to the square root of the corresponding power ratio. Hence

$$n = \log_e \left(\frac{P_1}{P_2}\right)^{½} = ½ \log_e \frac{P_1}{P_2}$$

By extension, this formula may be applied when the power ratio is not the square of the ratio of the corresponding voltages or currents. It is then important to specify the convention adopted and to indicate the sphere of validity of the usage. The neper may by used to express levels of quantities such as voltage and current in the same way as the ***decibel***.

network (1) A system of inter-connected components chosen and arranged to give specific electrical characteristics. A network containing no source of power is termed passive and one containing one or more sources is known as an ***active network***. If the values of the components forming the network are dependent on the current in them the network is termed non-linear but if the values are independent of current the network is linear.

(2) In ***computing*** two or more computers connected together to facilitate the exchange of data. Computer networks are generally classified as ***local area networks*** if the computers concerned are located on the same premises or as ***wide area networks*** if they are on separate premises and the connection requires the use of telecommunications lines. See ***local area network***, ***wide area network***.

network transfer constant Same as ***image transfer constant***.

neutralisation Use of a balancing network to counteract the ***feedback*** between the input and output terminals of an ***active device*** which occurs via the internal capacitance. The internal feedback causes instability when input and output circuits are tuned to the same frequency and neutralisation is used to enable, for example, transistors in radio receivers to give stable IF amplification. A typical circuit is given in *Figure N.5*: the neutralising capacitor C_n is adjusted to cancel the effect of the collector-base capacitance.

neutrodyne A method of neutralisation developed by Hazeltine in the USA.



Figure N.5 Simplified diagram illustrating one method of neutralising a transistor IF amplifier

neutron An elementary atomic particle with no charge and similar mass to the ***proton***. It is a constituent of all atomic nuclei except that of hydrogen.

n-gate thyristor A thyristor which is switched to the on-state by a negative signal applied between ***gate*** and ***anode***, the gate being a connection to the n-region nearest the anode. It is normally a reverse-blocking thyristor, i.e. one which cannot be switched to the on-state when the anode is negative with respect to the cathode. The graphical symbol for the n-gate thyristor is given in *Figure N.6*.



Figure N.6 Graphical symbol for an n-gate thyristor

nickel-cadmium cell A secondary cell in which the anode consists of a mixture of nickel oxide and hydroxide, the ***cathode*** is of cadmium and the electrolyte is of potassium hydroxide. Its properties are similar to those of the ***nickel-iron cell***. It is widely used in portable electronic equipments.

nickel hydride cell A type of dry battery used in some portable equipment, which offers approximately twice the capacity of ***nickel cadmium*** cells.

nickel-iron cell A secondary cell in which the anode consists of a mixture of nickel oxide and hydroxide, the ***cathode*** is of iron and the electrolyte is of potassium hydroxide. This is an alternative to the ***lead-acid cell*** and has the advantage that the nickel-iron cell will operate satisfactorily at temperatures as low as −30°C. On the other hand it is more expensive than the lead-acid cell and its EMF is only 1.2 V.

Nipkow disk Mechanical scanning device used in early experiments in TV. It consists of a disk containing a number of apertures arranged on a spiral path. The scene to be televised is illuminated by light which passes through these apertures so that, as the disk revolves, the scene is scanned. Light reflected from the scene is picked up by ***photocells*** the output of which is the required picture signal. The system was used in the BBC 30-line television experiments in the late 1920s.



Figure N.7 A C-network has six nodes, numbers 1, 3, 4 and 6 being external, 2 and 5 internal

node (1) In a network a point where three or more elements are connected (internal node) or where signals are applied to or withdrawn from an element (external node). For example the network shown in *Figure N.7* has six nodes, two internal and four external. External nodes are alternatively known as ***terminals***.

(2) Of a ***standing wave***, a point or plane at which a specified variable has a minimum value. Thus nodes on a ***transmission line*** are points at which voltage or current is a minimum. For a bowed string nodes are points at which the amplitude of vibration is a minimum. See ***antinode***.

noise In general any unwanted signals within the useful frequency band of a communications system which tend to obscure the wanted signal. This is a wide definition and embraces a variety of man-made noises such as mains hum, signals from other channels arising from inadequate selectivity or poor image rejection, cross modulation, etc; it also includes naturally-generated signals arising from lightning flashes. Signals from such causes are better termed ***interference*** so that the term noise is reserved for signals which arise in components and ***active devices*** and are known as random noise. Such signals are termed noise because they are heard as undesired sound when reproduced by an acoustic transducer but the term is retained for signals which cause spurious detail on the screen of a ***cathode ray tube***.

Random noise from components is known as ***thermal noise*** or Johnson noise and from active devices is known as ***shot noise*** and ***partition noise***. Even if all sources of man-made noise can be eliminated there still remains random noise and the level of this noise determines the amplitude of the weakest signal which can be successfully transmitted through a communications system. Wanted signals must exceed the noise level by a margin which ensures that the noise does not impair the intelligibility of the signal unduly or the enjoyment of the programme. Thus the noise level and the ***signal-to-noise ratio*** are two important properties of a communications system.

noise factor (or **noise figure**) Of a device, a measure of the noise it introduces. More specifically it is the ratio of the ***signal-to-noise ratio*** at the output of the device to the signal-to-noise ratio at the input and is usually expressed in dB. An ideal, i.e. noise-free, device thus has a noise factor of unity (0 dB).

noise generator A device for generating a standard noise signal which can be used for the measurement of ***noise factor***. In such generators the ***shot noise*** in a saturated diode is often employed as the primary source of noise.

noise limiter In a radio or TV receiver a circuit used to reduce the effect of impulsive noise signals on the sound or picture output. Typically the circuit includes a series diode which is situated at the output of the detector and is so biased that it remains conductive for all normal amplitudes of sound or video signals but becomes non-conductive, so interrupting the wanted signal, for the duration of any noise pulse exceeding a pre-determined amplitude. The resulting interruptions are normally so brief that their subjective effect is negligible.

noise temperature At a given pair of terminals and at a given frequency the temperature of a resistance which gives the same noise power per unit bandwidth as the noise to be measured. The standard reference temperature for noise measurement is 290°K.

non-composite colour-picture signal (US) In TV the signal which comprises full colour-picture information including the colour burst but excluding the synchronising signals.

non-composite signal (US) Same as ***picture signal.***

non-conjunction gate Same as ***NAND gate.***

non-equivalence gate Same as ***exclusive-OR gate.***

non-linear circuit element A circuit element for which the significant property is dependent on the current flowing through it or the voltage across it. An example is a ***non-linear resistance.***

non-linearity distortion General term embracing all the forms of distortion which result from non-linearity of the input-output characteristics of a system, equipment or component, e.g. ***amplitude distortion, harmonic distortion*** and ***intermodulation distortion.*** The significant feature of non-linearity distortion is that it is dependent on signal amplitude.

non-linear network See ***network.***

non-linear resistance A resistance for which the current is not directly proportional to the applied voltage. Such a resistance may have a current-voltage characteristic of the form shown in *Figure N.8*. For comparison the characteristic for a linear resistor (i.e. one which obeys Ohm's law) is shown as a dashed line.



Figure N.8 Current-voltage characteristic for linear and non-linear resistances

nonode An electron tube with seven grids between ***cathode*** and ***anode.*** The first grid (nearest the cathode) is a control grid, grids 2, 4 and 6 are screen



Figure N.9 Graphical symbol for a nonode

grids 3, 5 and 7 are suppressor grids. The arrangement is shown in *Figure N.9*. The tube was used in FM receivers as a self-limiting phase-difference ***discriminator*** and grids 3 and 5 are fed with FM signals from the primary and secondary windings of an IF transformer. The control grid is given a steady bias and suppressor grid 7 is connected to cathode to suppress ***tetrode kink***. The three screen grids are commoned and connected to a low voltage such as 30 V. The limiting action stems from the use of suppressor grids as input electrodes. The signals swing the anode current between zero and the value set by the control-grid bias. Increase in the amplitude of the input signals can produce no corresponding increase in anode-current swing.

non-volatile A term used to describe any form of memory which retains the data it is storing when the equipment is switched off or loses its power supply for some other reason. Under these circumstances the contents of normal RAM is lost. Examples of non-volatile memory include battery-backed RAM and various forms of ***EPROM***.

NOR gate (NOT-OR gate) A ***logic gate*** which gives a logic-0 output when one or more of the input signals is at logic 1. It may be regarded as an OR gate followed by a negating stage as shown by the graphical symbol in *Figure N.10*. See ***logic level***.



Figure N.10 Graphical symbol for a NOR gate

Norton's theorem If an admittance Y' is connected between any two points of a linear network the voltage across it is given by $I/(Y + Y')$, where I is the short-circuit current and Y is the admittance measured between the points before Y' was connected.

NOT-AND gate Same as ***NAND gate***.

NOT-BOTH gate Same as ***NAND gate***.

notch filter A bandstop filter for which the stop band is extremely narrow. Such filters are used for reducing interference which is confined to a single frequency (e.g. heterodyne interference) or to a narrow band of frequencies. The frequency response for a notch filter is illustrated in *Figure N.11*.

NOT gate A ***logic gate*** with a single input and a single output, which gives a logic-0 output when the input is at logic 1, and a logic-1 output when the input is at logic 0. It is often termed a logic negator or ***inverter***.



Figure N.11 Frequency response of a notch filter

npin transistor A type of ***bipolar transistor*** in which the base and collector regions are separated by a region of intrinsic material.

npn transistor See ***bipolar transistor.***

NTSC colour television system A compatible colour TV system pioneered by the National Television Systems Committee in USA in which the ***luminance signal*** is transmitted by ***amplitude modulation*** of the ***vision carrier*** and two ***chrominance signals*** are transmitted simultaneously by ***quadrature modulation*** of a subcarrier, the total ***bandwidth*** being the same as that of a black-and-white system using the same line standards. A ***colour burst*** is included in the ***back porch*** to facilitate decoding of the colour subcarrier.

This is the system used in USA and a number of other countries. The PAL system used in UK and a number of other countries is a development of the NTSC system. See ***PAL*** and ***SECAM*** systems.

n-type semiconductor An ***extrinsic semiconductor*** in which the free-electron density exceeds that of the hole density. Thus the negative charge carriers outnumber the positive charge carriers and current flowing through such materials is due to movement of negative charge carriers.

nuvistor Miniature ***electron tube*** of rigid construction with small ***electrodes*** and electrode clearances designed for high reliability.

Nyquist diagram Of a feedback amplifier a graph in rectangular co-ordinates showing the real and imaginary components of the ratio μ/β, where μ is the gain of the amplifier and β is the fraction of the output voltage fed back. Such a diagram, if plotted for a very wide frequency range, can be used to predict whether the amplifier will be stable.

O

object In computing, any self-contained set of data. For example, in a ***filing system*** the objects are ***files*** and ***directories***, in a ***database*** the objects are the various items of data that are stored and in ***DTP*** or ***vector graphics*** the objects are the various textual items (commonly called *stories*) and individual graphics of which the ***document*** is composed.

object code The form taken by a ***computer program*** after it has been translated from the source code by compilation or assembly. See ***computer language***.

object linking and embedding (OLE) In ***computing***, the practice of storing pointers to ***files*** instead of the file contents themselves. For example, in a ***Desktop Publishing document*** which includes a half-tone illustration as a ***bitmap*** the conventional approach would be to copy the entire bitmap into the document file. This would occupy appreciable memory and in some circumstances its presence might affect the computer's performance. Using OLE, however, only the name and address of the bitmap file is stored in the document. The bitmap itself is loaded into memory only when it is displayed on the ***VDU*** or printed. OLE makes it possible for a computer to handle longer and more complex documents. It does, however, increase the time taken to display or print the document and it introduces complications if the document is transmitted elsewhere, e.g. for phototypesetting.

object-oriented programming A philosophy of computer programming that divides data into separate units called ***objects*** which may be of various types, each handled independently.

Occam See ***computer language***.

occlusion Property of certain solids, particularly some metals, which enables them to absorb gases without chemically combining with them. The final stage in the evacuation of ***electron tubes*** is the removal of the last traces of gases occluded within the electrodes. See ***degassing***.

octal scale A counting scale containing eight digits, each digit in a number representing a power of eight. Thus the decimal equivalent of the octal number 352 can be evaluated as follows:

$$\begin{aligned}352 &= 3 \times 8^2 + 5 \times 8^1 + 2 \times 8^0\\ &= 3 \times 64 + 5 \times 8 \;\; + 2 \times 1\\ &= 192 \quad + 40 \quad +2\\ &= 234\end{aligned}$$

Octal numbers are often used as a shorthand method of writing binary numbers. Because 8 is 2^3 it is easy to convert between the two counting scales. Each three digits of a binary number can be uniquely represented by one of the octal digits, e.g. the binary number 101010110 can be represented by the octal number 526, each having a decimal equivalent of 342.

octave The interval between two frequencies with a ratio of 2:1. Two sound waves with such frequencies blend harmoniously because one is precisely one octave higher than the other.

octode An electron tube with six grids between ***cathode*** and ***anode***. It is normally used as a frequency changer and may be regarded as a ***heptode*** to which a suppressor grid has been added to eliminated the ***tetrode kink***. As in the heptode, grids 3 and 5 may be connected together either inside or outside the envelope. The graphical symbol for an octode is given in *Figure O.1* which also indicates the functions of each grid.



Figure O.1 Graphical symbol for an octode indicating the function of each grid

off-line In computers and data-processing equipment, a term used to describe the peripheral equipment which is not currently under the direct control of the ***central processor***.

off-line storage A storage device or medium not under the direct control of a ***central processor***.

offset current For a ***differential amplifier*** the difference between the two bias currents. It is necessary to minimise offset current and this can be achieved by arranging for the source impedances of the two input signals to be equal.

offset voltage For a ***differential amplifier*** the output voltage arising from inherent DC unbalance of the amplifier. Usually offset voltage can be reduced to zero by adjustment of an external potentiometer but it is often temperature-dependent necessitating a compromise adjustment giving best results over the temperature range to be expected.

ohmic contact A purely-resistive contact between two surfaces such that the voltage drop across the contact is directly proportional to the current through it.

Ohm The unit of electrical resistance, symbol Ω although some standards use R. Practical values of resistance range from fractions of an ohm, through kilohms (KΩ or simply K) to several megohms (MΩ or simply M).

Ohm's law The current (I) in a conductor is directly proportional to the EMF (E) applied to it and is inversely proportional to its resistance (R) provided the temperature remains constant. This may be expressed mathematically as

$$I = \frac{E}{R} \qquad R = \frac{E}{I} \qquad E = IR$$

which enable the third quantity to be calculated when the other two are known. This law is probably the most fundamental in electronics.

one-shot circuit (US) Same as ***monostable circuit***.



Figure O.2 An O-network

O network A ***network*** consisting of four elements connected to form a square, the input being applied across one element, and the output being taken from across the opposite element. The network is illustrated in *Figure O.2* and can be regarded as a balanced form of the *pi-network.*

on line In ***computers*** and ***data-processing equipment***, a term used to describe peripheral equipment which is directly under the control of the ***central processor***. It is also used to describe operation in which a user can interact directly with a computer, i.e. in which the results of a particular operation can be made immediately available to the user.

on-line help In a computer ***application*** a series of screens containing text (and possibly also graphics) designed to help the user to understand the application. It is usually invoked by selecting an option from a Help menu or by pressing a ***function key***.

open circuit A circuit which is broken and in which current cannot therefore flow.

open-circuit impedance Of a two-terminal-pair ***network*** the impedance measured at one pair of terminals when the other pair is open-circuited.

open-collector (drain) output An integrated-circuit logic element in which the collector (drain) circuit of a transistor is completed externally to the integrated circuit. By parallelling such outputs for a number of elements it is possible to achieve a logic operation at the common output point without need for a specific logic element at that point. See ***distributed connection***.

open system A system that conforms to accepted standards so that it can be extended readily using compatible components.

operating point In general a point on the current-voltage characteristic of an ***active device*** which represents the direct voltage and current in the output circuit. The term is used with a number of distinct meanings:

(1) To represent the output current and voltage in the absence of an input signal: this is perhaps better termed the *quiescent point.*

(2) To represent the average current and voltage when an input is applied to the active device. For a symmetrical input signal and for a device with ideal characteristics this point coincides with the quiescent point but for an asymmetrical signal and for practical characteristics the two points do not coincide.

(3) To represent the instantaneous current and voltage in the output circuit. Thus for a purely-resistive load and a sinusoidal input signal the operating point moves up and down the load line making one complete oscillation about the mean position for each cycle of input signal as shown in *Figure O.3.*

operating system The resident ***software*** routines used by a computer to control access to the ***hardware*** features such as the keyboard, VDU and disk drives. In most computers these routines are stored on disk and loaded



Figure O.3 When a sinusoidal input signal is applied to an active device, the operating point P oscillates about its mean position between the limits of Q and R so generating the output-current and output-voltage waveforms indicated

into RAM as required; in some computers the operating system is permanently resident in ROM.

operational amplifier A high-gain direct-coupled integrated-circuit amplifier with external circuitry designed to perform a specific arithmetical or mathematical operation. The external circuitry usually provides overall ***feedback*** suitable for the intended function. For example in *Figure O.4* in which all resistors are equal the output of the amplifier is equal to the sum of the two input signals. The operational amplifier is used here as a summing amplifier.

Operational amplifiers are extensively used in ***analogue computers***.



Figure O.4 An operational amplifier used as a summing amplifier

optical amplifier A device which amplifies an optical signal without converting it to an electronic signal, e.g. a ***semiconductor laser***.

optical character recognition (OCR) A computer ***application*** which recognises the shapes of alphanumeric characters and punctuation marks in a ***bitmap***, for example that obtained by ***scanning*** a printed document, and converts these to a ***text*** file.

optical disk Any disk-based data storage system using optical technology. See ***compact disk, magneto-optical disk, phase-change disk, video disk.***

optical fibre See ***fibre optics.***

opto coupler or **isolator** A photo-emissive source such as a ***light-emitting diode*** encapsulated with a photo-sensitive device such as a ***photo-transistor*** designed to respond well to the radiation (often infra-red) from the source. Such a combination gives an electrical output dependent on the electrical input and can thus be used to couple two circuits. There is, however, no electrical connection between the input and the output of the opto coupler making this a useful device where electrical isolation is required between the coupled circuits. The graphical symbol for an opto coupler is given in *Figure O.5.*



Figure O.5 Graphical symbol for opto coupler or opto isolator

optoelectronics The study and application of electronic devices that emit light (such as ***lasers*** and ***light-emitting diodes***), amplify light (such as ***optical amplifiers***), detect light (such as ***photodiodes*** and ***phototransistors***) and control light (such as ***Kerr cells***).

Oracle The ***teletext*** service of the Independent Broadcasting Authority.

OR-gate A ***logic gate*** which gives a logic-1 output when one or more of the input signals are at logic 1. The graphical symbol for an OR-gate is given in *Figure O.6.*



Figure O.6 Graphical symbol for an OR gate

orthicon An early form of TV camera tube in which the optical image of the scene to be televised is focused on one face of a photo-emissive target, the reverse face of which is orthogonally scanned by a low-velocity ***electron beam.***

The use of a low-velocity scanning beam avoids secondary emission and thus the generation of shading signals as in the ***iconoscope***: it also ensures that the target remains stabilised near the electron-gun cathode potential (hence its British name cathode-potential stabilised emitron). The essential features of the tube are illustrated in *Figure O.7.* The target consists of a layer of mica carrying a transparent signal plate on one face and a mosaic of individually-insulated photo-emissive elements on the other.

When an optical image is focused on the target the elements lose electrons in proportion to the amount of light falling on them and so build up a charge image over the field period. This image is neutralised by the scanning beam which restores to the elements the electrons lost by ***photo-emission.*** Control of the low-velocity beam is obtained by use of an axial



Figure O.7 Essential features of the orthicon tube

magnetic field from the solenoid entirely surrounding the tube. The output of the tube is taken from the signal plate but it could also be taken from the return scanning beam as in the ***image orthicon***. See *orthogonal scanning*.

orthogonal scanning Scanning in which the ***electron beam*** always approaches the target at normal incidence. This is necessary in low-velocity camera tubes such as ***orthicons*** to achieve cathode-potential stabilisation of the whole area of the scanned face of the target. If conventional electrostatic or magnetic methods of deflection are used with a low-velocity beam, the beam approaches the centre of the target at normal incidence but all other points at an angle to the normal. As a result the whole area of the target is not cathode-potential stabilised and shading signals are present in the tube output. This can be avoided and the whole area of the target stabilised by arranging that the beam approaches all points of the target at normal incidence. This can be achieved by use of an axial magnetic field in conjunction with magnetic deflection of the scanning beam. The axial field can also be used as a long magnetic lens to focus the beam on the target.

oscillation In electronics the generation of alternating signals in a circuit containing ***inductance*** or ***resistance*** and ***capacitance***. As an example if a closed *LC* circuit is shock excited, oscillations are set up at the resonance frequency of the circuit. The energy which keeps the alternating current going is stored at one moment in the charged capacitor and at another in the magnetic field of the inductor. As this energy is dissipated in the inevitable resistance of the circuit the oscillation amplitude falls exponentially with time. Such oscillations are termed free and their frequency is determined solely by the constants of the circuit.

If the lost energy can be restored by connecting an ***active device*** to the LC circuit, then sustained oscillation at constant amplitude can be produced: this is the basis of all *LC* oscillators. If an alternating EMF is applied to an LC circuit, then oscillation occurs in the circuit but at the frequency of the applied EMF: this is an example of forced oscillation.

Oscillation can also occur in a circuit containing resistance, capacitance and some active devices and here the frequency of oscillation is governed by the ***time constants*** of the *RC* combinations: an astable multivibrator is an example of such an oscillator.

Oscillation can also occur in a mechanical system and is manifested by the rhythmic motion of part of it. The quantities analogous to inductance and capacitance in a mechanical system are the mass of the moving parts and the elasticity which returns them to the equilibrium position. The energy which keeps oscillation going alternates between the kinetic energy of the moving parts and the potential energy stored in the elastic element.

oscillatory circuit A circuit which consists primarily of ***inductance*** and ***capacitance*** and is capable of producing a current which reverses at least once in direction when the circuit is shock excited, e.g. by the momentary application of a voltage. Practical oscillatory circuits inevitably contain resistance and this, if large enough, can damp the circuit to such an extent that it is rendered non-oscillatory. See ***critical damping***.

oscillograph Same as ***cathode ray oscillograph***.

oscilloscope Same as ***cathode ray oscilloscope***.

outline font A typeface stored in a ***computer*** as a series of line drawings (***vector graphics***). Outline fonts are used in ***Desktop Publishing*** and graphic design applications where they have the advantage over ***bitmapped*** fonts that one set of drawings can be scaled to any required size by multiplying the co-ordinate data by the appropriate constant. Text in outline fonts can also be converted readily to vector graphics for more complex manipulations. Such text is usually printed as graphics; a printer intended solely for use with a computer system using outline fonts strictly needs no resident fonts at all and such cut-down ***laser printers*** are available very cheaply.

outphasing system Same as ***Chireix system***.

output (1) Of a device or equipment, the signal power it produces. (2) The terminals from which the output power is delivered.

output impedance Of a device or equipment, the ***impedance*** presented by the output terminals to the load.

overcoupled circuits Two circuits resonant at the same frequency and between which the degree of coupling is intentionally greater than the critical value. The effect of overcoupling is to give a double-humped frequency response symmetrically disposed about the resonance frequency.

overloading (1) Condition of a source of electrical power when more power is drawn from it than the source can supply continuously without overheating or damage. For example if ***voltaic cells*** are short-circuited the resulting overload current can do irreparable damage to them. (2) Of an equipment, ***active device*** or component the application of an input signal with an excessive amplitude. In analogue equipment such an input exceeds the extent of the linear part of the input-output characteristic and leads to non-linearity distortion.

overshoot Form of transient distortion of a step or pulse signal in which the response temporarily exceeds the final value. This is illustrated in *Figure*



Figure O.8 Overshoot on the leading edge of a pulse

O.8 and the magnitude of the distortion is usually given as the ratio of the overshoot to the step amplitude expressed as a percentage. Overshoot can also occur, of course, on the trailing edge of a pulse.

overtone See ***harmonic component.***

P

packet In ***data*** communications a set of data in digital format accompanied by control information (such as destination and origin) and ***error*** correction bits.

pad Same as ***attenuator.***

padder or **padding capacitor** A capacitor connected in series with the oscillator tuning capacitor in a ***superheterodyne receiver*** to maintain the correct frequency difference between the oscillator and signal-frequency tuned circuits. If the oscillator inductor is fixed, the padding capacitor is a preset component which is adjusted for optimum tracking. Normally, however, the padding capacitor is a fixed component and the oscillator inductance is adjusted for optimum tracking. See ***tracking, trimming.***

page printer A ***printer*** which prints a whole page at a time, such as a laser printer.

pager A compact portable radio receiver carried by personnel and used to contact them within a limited area surrounding the ***base station.*** A pager may reproduce speech communication, may give a visual display of a message or may simply emit an audible tone. Pagers are used mostly in large buildings such as hospitals and airports.

painting software Software for creating or editing ***bitmaps.***

PAL colour television system (Phase Alternation, Line) A compatible colour television system similar to the ***NTSC system*** but in which one of the two ***chrominance signals*** is reversed in phase for the duration of alternate scanning lines. The phase reversal enables more consistent colour rendering to be achieved in receivers by averaging the chrominance signals for two successive lines before displaying them on the picture tube. This technique minimises the effect of any hue errors due to phase shift of the chrominance signals. This is the colour television system used in UK and many other countries.

palette A list of the colours available in a ***VDU*** screen or in a ***bitmap*** with their composition in terms of primaries.

panoramic potentiometer (pan pot) In stereo sound equipment a ***potentiometer*** which can be used to divide a signal in any desired ratio between the



Figure P.1 One possible circuit arrangement for a panoramic potentiometer

left and right channels. Thus the signal can be panned or steered to any desired area between the extreme left and extreme right. *Figure P.1* gives a circuit diagram of one possible way in which a panoramic potentiometer can be connected.

panotrope (US) Disc-reproducing equipment in which the sound is reproduced by loudspeakers driven by amplifiers fed from an electrical pickup.

parafeed Same as ***parallel feed.***

parallel connection A method of connecting components or circuits so that they share the same voltage, the current dividing between the circuits depending on their impedance. See *Figure P.2*. The equivalent impedance Z_{eq} of a number of impedances Z_1, Z_2, Z_3, etc is given by

$$\frac{1}{Z_{eq}} = \frac{1}{Z_1} + \frac{1}{Z_2} + \frac{1}{Z_3} + \text{etc.}$$

but problems on impedances in parallel are probably best solved by use of the admittance concept, the equivalent admittance being the sum of the individual admittances thus:

$$Y_{eq} = Y_1 + Y_2 + Y_3 + \text{etc.}$$

See ***series connection.***



Figure P.2 Components connected in parallel have a common signal voltage *V*

parallel feed Circuit in which the signal output from an ***active device*** is taken via a series capacitor, so separating the alternating and direct components of the output current. The direct circuit is completed by a resistor or inductor. The circuit is sometimes used to feed transformers as shown in *Figure P.3* and has the advantage of avoiding ***polarisation*** of the



Figure P.3 A parallel-fed transformer

transformer core by the direct component of the preceding device, thus enabling a smaller and cheaper transformer to be used.

parallel processing In a computer with multiple microprocessors the simultaneous carrying out of two or more sequences of instructions.

parallel resonance Resonance in which the applied signal is connected to an inductor and capacitor in parallel as shown in *Figure P.4*. Resonance is indicated by the impedance of the *LC* circuit which is a maximum at the resonance frequency given by

$$f = \frac{1}{2\pi\sqrt{(LC)}}$$

as for **series resonance**.



Figure P.4 A parallel resonant circuit

parallel storage (access) A device in which all the bits of a binary word can be stored simultaneously. Cf ***serial storage***.

parallel T-network A circuit comprising two ***T-networks*** in parallel as shown in *Figure P.5*. It is often used as an *RC* filter, as in the diagram, and is capable of giving infinite attenuation at a particular frequency depending on the values of *R* and *C*.



Figure P.5 A parallel-T network used as an *RC* filter

parallel transmission Simultaneous transmission of the elements of a signal over separate channels. See ***serial transmission***.

paralysis Effect of applying a large input signal to an electron-tube amplifier causing the tube to be cut off and the amplifier rendered ineffective for a short period. The signal causes grid current in the tube and this charges the inter-tube coupling capacitor to a voltage (the negative plate being connected to the grid) large enough to bias the tube beyond anode-current cut off. The state of paralysis lasts until the charge on the capacitor has leaked away through the grid resistor sufficiently for the tube to begin taking anode current again. This effect is exploited in the ***blocking oscillator***.

paramagnetism A property of certain materials subjected to a magnetising field which causes induced magnetism which slightly aids the magnetising field. Such materials are attracted very feebly by a magnetic pole and the effective permeability is slightly greater than unity, being almost independent of the magnetising field. See ***diamagnetism, ferromagnetism***.

parameter Strictly one of a number of variables used to express the behaviour of an ***active device*** or ***network*** and which is maintained constant whilst the relationship between other variables is being investigated. For example the I_c–V_c characteristics of a ***bipolar transistor*** are normally displayed as a family of curves, each plotted for a different constant value of base current, which is therefore a parameter. The term is also loosely employed to mean any of the variables used to express electrical behaviour. For example the iterative impedance and cut-off frequency are termed parameters of a network.

parametric amplifier (or **converter**) An amplifier (or converter) which depends for its action on a device, a parameter of which is varied sinusoidally (pumped) at a suitable frequency. The parameter is often the reactance of a semiconductor device such as a ***varactor*** and parametric amplifiers are used for RF amplification at microwave frequencies where they can give a good ***signal-to-noise ratio***.

paraphase Same as ***push-pull***.

parasitic oscillation Unwanted sustained oscillation in an ***active device*** or equipment usually at a frequency well above the passband. It is generated by coupling between stages of the equipment or between the electrodes of an active device. For example if the input and output leads of a ***transistor*** are not screened from each other, the capacitance between them, even though very small, can provide the positive feedback necessary for oscillation. The leads act as the conductors of a transmission line and their dimensions determine the frequency of oscillation which can be very high indeed when the leads are very short. Such oscillation impairs the performance of equipment by introducing noise and reducing power output. ***Parasitic stoppers*** are used to suppress such oscillation.

parasitic stopper Component employed in electronic equipment to suppress ***parasitic oscillation***. Low-value resistors (e.g. 47 Ω), small inductors and ferrite beads are commonly used for this purpose, the components being included in the leads to active devices as close to the device as possible.

parity bit In digital transmission a binary digit added to each binary code group to make the sum of all the binary digits, including the parity bit, always odd or always even. The technique is used to detect errors in binary code groups.

parity check In digital transmission a technique for detecting that an error has occurred in code groups by use of a parity bit. The binary digits in each code group (including the parity bit) are added to check if the sum is odd or even.

partial A component of a complex sound wave the frequency of which is not necessarily an integral multiple of the fundamental frequency. The sound of a struck bell contains a number of partials. See ***harmonic component***.

partition A division introduced in a ***hard disk drive*** so that it behaves as though it were several separate ***logical*** drives. There are many reasons for introducing partitions: (1) Separate ***operating systems*** may reside in different partitions. (2) Some operating systems cannot access hard drives having capacities over a certain threshold, but by introducing partitions such an otherwise unacceptable drive can be used. (3) Some disc formats use a small drive more efficiently than a large one, because the ***sectors*** are smaller; by partitioning a large drive, its effective storage capacity may be increased.

partition noise Noise arising from random variations in the division of the current from the cathode of an ***electron tube*** among the various electrodes. Although the division ratios are constant when measured over an appreciable period there are momentary surfeits and deficits at any given electrode and their variation with time constitutes partition noise.

Such noise arises in ***tetrodes*** and more complex tubes where the cathode current is shared between the anode and the screen grids and makes such tubes about three to five times as noisy as a ***triode*** which has no partition noise. This was the reason for the choice of triodes for the first stage of amplifiers with very small inputs such as microphone and TV-camera head amplifiers.

Pascal See ***computer language***.

passband See ***filter***.

passive component A component which does not contain a source of energy. The chief types of passive component in electronics are inductors, capacitors and resistors. See ***active device***.

passive network See ***network***.

patch (1) A temporary lash-up of equipment typically using jumper leads in order to provide a service at short notice or in other adverse circumstances. (2) An additional file in a ***software*** package which modifies the main files in order to overcome some ***bug*** that was found shortly before release.

path (1) The route taken by a stream of electrons through a component or a ***signal*** through an equipment. (2) The route taken by radio waves between the transmitting antenna and the receiving antenna. (3) In ***computing*** the complete address of a file in a storage medium, starting with the drive identity and including all intermediate directories. (4) In ***vector graphics*** the course followed in plotting a line or the outline of a shape.

pattern generator A ***signal generator*** which produces on the screen of a TV receiver a regular geometric pattern which can be used to facilitate the adjustment of linearity and convergence.

PC-compatible Of a computer, capable of running software intended for the IBM ***PC*** and its successors. Of ***software***, capable of running on the IBM PC, its successors and compatible machines.

p-channel metal-oxide-semiconductor (PMOS) A form of construction for ***logic monolithic integrated circuits*** using p-channel ***field-effect transistors***. See ***NMOS***.

peak clipper See clipping.

peaking circuit (or **network**) A coupling circuit in a pulse or video amplifier including a series or shunt inductor which resonates with the stray capacitance to improve the frequency response at the upper end of the passband. *Figure P.6* gives an example of a shunt-inductance peaking circuit.

peak inverse voltage (PIV) Of a ***diode*** in a rectifying circuit, the maximum instantaneous voltage across the input terminals when the diode is non-



Figure P.6 A peaking circuit incorporating a shunt inductance

conductive. This voltage is made up of the alternating input to the diode plus the voltage across the load circuit and the latter can equal the peak value of the alternating input if a reservoir capacitor is included. Thus the peak inverse voltage can be twice the peak value of the alternating input to the diode, e.g. nearly 700 V if the input voltage is 240 V RMS. The diode must be capable of safely withstanding such a voltage.

peak programme meter (PPM) An instrument for measuring the amplitude of audio signals in terms of the peaks occurring within a predetermined period. The instrument responds very rapidly to increases in signal amplitude to permit accuracy in peak measurement but it takes an appreciable period (of the order of seconds) to return to zero after a peak has been indicated. This avoids the very rapid changes in reading which would otherwise occur and make peak reading difficult. The instrument incorporates a logarithmic amplifier so that the scale can have linear decibel calibrations. The instrument is used for AF measurements in sound broadcasting and recording where accurate knowledge of peak amplitudes is essential.

peak white In black-and-white television the peak excursion of the picture or video signal towards white level. In a dark scene with no highlights peak white may be considerably below ***white level***.

pedestal In general a pulse with a level top which is used as a base for another pulse. In TV the difference between ***black level*** and ***blanking level***. This is usually expressed as a percentage of the difference between ***white level*** and blanking level. See *Figure B.18*(a).

peek In computing, to read the contents of a ***byte*** of memory. See also ***poke***.

Peltier effect When an electric current is maintained through the junction of two dissimilar metals the junction temperature increases or decreases depending on the direction of the current. The heat generated at the junction or lost from it is proportional to the current.

penetration Extent to which an alternating current occupies the cross section of a solid conductor. As frequency is raised alternating currents tend to confine themselves to the outer areas of the cross section (see ***skin effect***). At high radio frequencies so little current is carried by the central region of the conductor that it is practicable to use tubing for RF inductors in place of solid conductors. The depth of penetration is the wall thickness of such a tube which has the same outer diameter and the same RF resistance as a given solid conductor.

pentagrid tube (US) Same as ***heptode***.

Pentium™ Trade name for the Intel 80586 ***microprocessor***.



Figure P.7 Shape of I_a–V_a characteristic of a pentode

pentode An electron tube with a ***cathode***, ***control grid***, ***screen grid***, ***suppressor grid*** and ***anode***. The tube is in effect a tetrode in which the ***tetrode kink*** has been eliminated by the inclusion of the suppressor grid. Thus the characteristics of the tube are a good approximation to the ideal as shown in the typical example shown in *Figure P.7*. Such tubes were extensively used for amplification at RF, IF and AF and in the output stages of amplifiers. The graphical symbol for a pentode is given in *Figure P.8*.



Figure P.8 Graphical symbol for an indirectly-heated pentode

percentage modulation Same as ***modulation percentage***.

Percival system A system of compatible stereo sound transmission pioneered by Electric and Musical Industries in which the sound signal is transmitted as in a monophonic system and the directive information is transmitted as a narrow-band (100 Hz) signal on a subcarrier of about 22 kHz.

performance testing Testing of equipment to determine its characteristics or to determine whether it complies with the specified performance.

periodic permanent magnet (PPM) A structure of alternate permanent ring magnets and salient soft-iron pole pieces used to provide the axial magnetic field in travelling-wave and similar tubes. As shown in *Figure P.9* the annular magnets are so arranged that neighbouring salient pole pieces have opposite polarity. Such a structure avoids the need for a focusing solenoid and requires only small amounts of magnetic material.



Figure P.9 A periodic permanent magnet structure

peripheral Any equipment that is commonly connected to a central control unit. For example, to a computer user a ***printer***, a ***scanner*** and a ***modem*** would be peripherals in that they must be connected to the computer for use. A programmer, however, might think of the computer's internal ***disk drives*** and ***memory*** as peripherals because they are controlled by the ***central processing unit***.

permanent storage Same as ***read-only memory***.

permeability Of a magnetic material, the ratio of its ***absolute permeability*** to the absolute permeability of a vacuum.

permeability tuning A method of adjusting the resonance frequency of a tuned circuit by varying the effective ***reluctance*** of the magnetic circuit of the ***inductor***. Usually such tuning is effected by adjusting the position of a ferromagnetic core in the inductor.

permeance Of a magnetic circuit the ratio of the ***magnetic flux density*** to the ***magnetomotive force*** which gives rise to it. It is the reciprocal of *reluctance* and magnetic analogue of *conductance*.

permitted band Same as ***allowed band***.

permittivity Of an insulator a characteristic constant equal to the ratio of the electric flux density produced in the insulator by a given electric field strength to the flux density produced by the same field strength in a vacuum. More practically it is the ratio of the ***capacitance*** of a capacitor with the insulator as dielectric to that of the same capacitor with air (strictly a vacuum) as dielectric. Values of permittivity for commonly-used insulators range between 2 and 10 but values as high as several thousand are possible.

persistence Emission of light from the screen of a ***cathode ray tube*** after removal of excitation by the electron beam. The period of persistence may be between a fraction of a second to several minutes depending on the ***phosphor*** used in the screen coating.

Personal Computer (PC) Strictly, any ***computer*** designed for use by a single user, in contrast with ***mainframe*** and ***mini-computers*** which may be used simultaneously by several users at separate ***terminals***. In practice this generally means a ***desktop*** or ***laptop microcomputer*** which is self contained, although capable of being connected to a ***network*** for access to shared resources. More specifically, the term Personal Computer (capitalised) or PC is commonly used to designate the IBM PC, introduced in 1981, and its successors and compatible machines.

Personal Computer Memory Card International Association (PCMCIA) A standard originally developed for ***demountable*** memory cards intended primarily for use with portable computers and other data processing equipment. The cards are about the same size as credit cards but slightly thicker and may contain ***ROM***, ***EPROM*** or battery-backed ***RAM*** with storage capacities up to 80 Mbytes. They locate in a slot in the ***host*** device in much the same way as a ***floppy disk***. They are used for the storage and transmission of software, especially in environments where the use of electromechanical storage devices such as floppy and ***hard drives*** is impractical because of, e.g. electromagnetic interference or extremes of temperature. The PCMCIA standard is also used for connecting other peripherals, such as modems and hard disk drives, to portable computers.

persuader An electrode in an ***image orthicon*** tube biased so as to direct the return scanning beam into the ***electron multiplier*** which surrounds the ***electron gun***. The persuader is in the form of a short cylinder and is given a positive bias (with respect to the electron-gun-cathode potential) which is adjusted to give the best uniformity of illumination over the area of the reproduced image: the adjustment is usually labelled 'multiplier focus'.

perveance A factor expressing the ability of a ***diode*** or ***electron gun*** to provide an electron stream under the stimulus of a given accelerating voltage. It is equal to the ***space-charge-limited*** electron current divided by the three-halves power of the accelerating voltage.

p-gate thyristor A ***thyristor*** which is switched to the on-state by a positive signal applied between ***gate*** and ***cathode***, the gate being a connection to the p-region nearest the cathode. It is normally a reverse-blocking thyristor, i.e. one which cannot be switched to the on-state when the anode is negative with respect to the cathode. The graphical symbol for the p-gate thyristor is given in *Figure P.10*.



Figure P.10 Graphical symbol for a p-gate thyristor

phantastron A monostable ***transitron***, i.e. a pentode in which the anode is capacitively coupled to the control grid and the screen grid is directly coupled to the suppressor grid. The circuit is equivalent to a ***monostable multivibrator*** and, when triggered by positive signals on the control grid, generates rectangular pulses at the screen grid and linear sawtooths at the anode. The duration of the output signals can be controlled by adjustment of the standing bias on the control grid. A typical circuit diagram for a phantastron is given in *Figure P.11*.

phantom In telephony an additional independent circuit obtained from two physical balanced two-wire circuits by effectively connecting each pair of conductors in parallel. Signals in the phantom circuit travel in the same direction in the conductors of each physical circuit, as shown in *Figure P.12*, and thus do not interfere with the signals in them.



Figure P.11 A phantastron circuit



Figure P.12 Derivation of a phantom circuit from two physical circuits

phase Of a periodically-varying quantity, that part of a period (in degrees or radians) through which the quantity has advanced since some arbitrary time origin. Usually the origin is taken as the time when the quantity last passed through zero value in changing from negative to positive values.

phase-change disk and **drive** Same as ***magneto-optical disk*** and ***drive***.

phase coefficient (or **constant**) See ***propagation coefficient***.

phase comparator A circuit which compares the phases of two input signals and gives an output dependent on the phase difference. See ***long-tailed*** pair.

phase corrector Same as ***phase equaliser***.

phase delay The time obtained by dividing the ***phase shift*** introduced by a circuit or equipment by the frequency. The phase angle is expressed in radians and the angular frequency in radians per second. Thus

$$\text{phase delay} = \frac{\phi}{\omega}$$

Phase delay can be regarded as the time interval between a crossing of the time axis in the sinusoidal input signal and the corresponding crossing of the time axis in the output signal. Admittedly it would not be easy to measure phase delay in this way because of the difficulty of identifying corresponding time-axis crossings at input and output. This is why delay is usually measured with a complex signal having an easily-identifiable feature such as a steep leading edge which can be timed through the equipment.

phase difference Angle which represents the extent to which one sinusoidal quantity differs in time from another of the same frequency, i.e. it is the angle between the two vectors representing the sinusoidal quantities. If the two vectors coincide the two quantities are in phase and the phase angle is zero. If the two vectors are at right angles the two quantities are in quadrature and the phase angle is 90°.

In electronics we are often concerned with the phase angle between the current in a circuit and the applied alternating voltage. If, as in an inductive circuit, the voltage reaches a given point in its cycle before the current reaches the corresponding point in its cycle, the current is described as lagging on the voltage and the phase angle may be termed the angle of lag.

In a capacitive circuit the current reaches a given point in its cycle before the voltage reaches the corresponding point in its cycle: here the current leads the voltage and the phase angle may be termed an angle of lead.

phase discriminator See ***discriminator***.

phase distortion Distortion which arises when the ***phase shift*** introduced by a system or equipment is not directly proportional to the frequency. If the phase shift is strictly proportional to frequency, as shown in *Figure P.13*, then the ***phase delay*** through the system is constant and independent of frequency. All components of a complex input signal therefore arrive at the output correctly related to each other in time and there is no distortion of the output waveform. *Figure P.13* is a typical practical phase-frequency characteristic and this would cause waveform distortion, in particular an increase in the ***rise time*** of a pulse.



Figure P.13 Phase-frequency characteristics

phase equaliser A ***network*** designed to correct phase distortion occurring within a specified frequency band. If the phase equaliser is not also required to correct for amplitude-frequency distortion, a simple ***all-pass network*** may be used as a phase equaliser.

phase-frequency distortion Same as ***phase distortion***.

phase inverter A circuit of which the output signal is an inverted replica of the input signal. Such stages are required where two signals of identical waveform, one inverted with respect to the other, are needed for application to a push-pull amplifier. 'Signal inverter' is a better term.

phase-locked loop (PLL) A combination of a voltage-controlled oscillator and a phase comparator so connected that the oscillator frequency (or phase) accurately tracks that of an applied frequency- or phase-modulated signal.



frequency- or phase-modulated RF input
phase comparator
low-pass filter
modulation-frequency output
voltage-controlled oscillator

Figure P.14 Block diagram of a phase-locked loop

The arrangement is illustrated in the block diagram of *Figure P.14*. The output of the phase comparator depends on any difference in frequency (or phase) between the two input signals and contains zero-frequency and RF components. The latter are removed by the low-pass filter but, provided the ***cut-off frequency*** of the filter is suitable, the voltage-controlled oscillator will track any frequency or phase modulation of the input signal and the control signal for the oscillator is therefore a replica of the modulating signal.

phase modulation (PM) Method of modulation in which the phase angle of a carrier wave is made to vary in accordance with the instantaneous value of the ***modulating signal***. Phase modulation is similar to frequency modulation. The difference between them is that in frequency modulation, for a constant-amplitude modulating signal, the phase shift is swept between limits inversely proportional to the modulating frequency: in phase modulation the limits are fixed. Similarly in phase modulation for a constant-amplitude modulating signal the frequency is swept between limits directly proportional to the modulating frequency: in frequency modulation the limits are fixed. In practice this means that one form of modulation can be converted to the other by including a 6dB-per-octave filter in the modulating-signal path.

phase quadrature See ***phase difference***.

phase reversal Term applied, somewhat loosely, to the inversion of a signal.

phase shift Of a sinusoidal signal a change of phase angle as a result of, for example, transmission of the signal through a ***network***. Also an alteration in the difference in phase between two or more sinusoidal signals at the same frequency.

Phase Shift Key (PSK) A method of ***phase modulation*** used to transmit digital data over telecommunications links.



Figure P.15 Essential features of a phase-shift oscillator using a bipolar transistor

phase-shift oscillator A sinusoidal oscillator the frequency of which is determined by the phase shift in an *RC* network. In one type, illustrated in *Figure P.15*, a three-section RC network is used to give 180° phase shift at the operating frequency, signal inversion in the active device providing the positive feedback essential for oscillation. In another type of phase-shift oscillator a ***Wien-bridge*** network gives zero phase shift at the operating frequency, a non-signal-inverting amplifier being used to give positive feedback. This is the bias of a number of AF test oscillators.

phase splitter A circuit which provides two output signals of identical waveform, one inverted with respect to the other, for application to a pushpull amplifier. A number of circuits can be used for this purpose. See ***concertina phase splitter, long-tailed pair, see-saw phase splitter.***

phase velocity Of a sinusoidal plane wave the velocity of propagation of an equiphase front in the direction of the normal. It is equal to the product of the wavelength and the frequency. If the phase velocity is independent of frequency it is equal to the envelope and ***group velocity.***

phasing In general the adjustment of an oscillating system to establish a desired phase relationship with another system with the same frequency. In colour TV the process of ensuring that the time of arrival of video or synchronising signals at a particular point are within the tolerances for the system.

In sound reproduction so connecting a (***monophonic***) audio signal to the terminals of the individual units of a multi-unit loudspeaker or of the reproducers of a stereo system that all the diaphragms move in phase.

phon The unit of loudness level. See ***Fletcher-Munson curves, loudness level.***

phonograph pickup (US) Same as ***pickup.***

phosphor A material capable of ***luminescence*** and therefore used as a coating for the screens of ***cathode ray tubes.*** A number of different materials are used depending on the colour and the ***persistence*** required.

phosphorescence Emission of light from a material after it has been irradiated by energy of a higher frequency or has been bombarded by electrons. The emission may continue for a considerable period after the stimulus has been removed. See ***fluorescence.***

photicon Type of ***image iconoscope.***

photo-cathode Electrode in a ***photocell*** or a ***camera tube*** which emits ***photo-electrons*** when irradiated by light. In general the light falling on a photocell is in the form of a spot or stripe and the tube is required to respond to variations in the intensity of the light.

In a camera tube, however, an optical image of the scene to be televised is focused on one face of the photo-cathode which is transparent so that photo-electrons are liberated from the opposite face. The number of photo-electrons emitted from any point on the photo-cathode surface depends on the illumination of that point and thus varies over the area of the photo-cathode depending on the detail in the optical image. The liberated photo-electrons are focused by an ***electron lens*** to form a corresponding charge image on the target of the camera tube. See ***image section***.

Photo-CD A system developed by Kodak for the digital storage of photographic images on a ***compact disc***. The original intention was that users purchase a dedicated Photo-CD player (which would also play audio CDs) and connect it to a domestic television receiver for viewing. Films were processed by Kodak who supplied conventional prints as well as a Photo-CD disk containing *scanned* images of the photographs. Essentially a recordable CD, this was *multi-sessional* in that more images could be added to it in a later session. Each image is stored in five resolutions allowing the user to ***zoom in*** on points of interest. At first the system was not popular because the hardware was expensive, access to the higher-resolution images was slow and it was sometimes inconvenient to view photographs on a domestic television receiver. Photo-CD's renaissance came with the advent of CD-ROM. With suitable software any computer having a CD-ROM drive and a high-resolution ***VDU*** can read a Photo-CD, display the images stored on it and copy them to graphics applications for editing or to DTP applications for incorporation into documents. Photo-CD is now an established source of high-quality ***bitmaps***.

photocell A device which gives an electrical output dependent on the light falling on the input electrode. There are a number of different types of photocell depending on the nature of the light-sensitive material used in them. For example a photocell may be photo-emissive, photoconductive or photovoltaic. Cells using photo-emissive materials may be vacuum or gas-filled.

photoconductive camera tube A camera tube in which the photo-sensitive electrode is photoconductive. Such tubes are known as ***vidicons*** and are extensively used in colour television cameras.

photoconductive cell A photocell in which the photo-sensitive electrode is photoconductive.

photoconductivity Variation of the electrical conductivity of a material when it is irradiated by electromagnetic waves within a particular frequency range. Examples of materials which exhibit photoconductivity are selenium, antimony trisulphide and copper oxide, all of which have been used in the targets of ***vidicon*** camera tubes.

photo-coupler or **isolator** Same as ***opto-coupler*** or ***isolator***.

photo-diode A pn diode the reverse current of which is dependent on the amount of light falling on the junction. The reverse current is carried by minority carriers and is greatly dependent on temperature because heat can



Figure P.16 Graphical symbol for (a) a photo-diode and (b) a photo-transistor

liberate more covalent bonds. Light can also do this and thus a pn diode in a transparent container can be used as a light cell. The graphical symbol for a photodiode is given in *Figure P.16* (a).

photo-electric cell (PEC) Same as ***photocell.***

photo-electric emission (photo-emission) The liberation of ***electrons*** from a material when this is irradiated by electromagnetic waves. The elements sodium, potassium, lithium, rubidium and caesium are notable for their photo-emissive effect and for each element there is a certain threshold frequency of incident light below which no emission occurs.

photo-electron An ***electron*** liberated from a photo-emissive surface by incident light.

photo-multiplier A photo-emissive tube in which the liberated ***photo-electrons*** are directed into an ***electron multiplier*** to give a greatly enhanced current output.

photon An elementary quantity of radiant energy which may be regarded as a fundamental particle or a train of electromagnetic waves. A photon is emitted when an ***electron***, which has been transferred to an orbital of higher energy level, suddenly returns to its former orbital. See ***energy level diagram.***

photo relay Same as ***opto coupler.***

photo-resist An organic substance sensitive to ultra-violet light which is used in the manufacture of transistors and integrated circuits. See ***planar process.***

photo-sensitivity Ability of a material to change its chemical or electrical state when irradiated by electromagnetic waves. Such materials can absorb ***photons*** of light and liberate ***electrons*** which can effect the properties of the material in three ways:

(a) the electrons may be released as photo-electric emission, i.e. as photo-electrons.
(b) the electrons, acting as charge carriers, may increase the electrical conductivity of the material.
(c) the electrons may set up an EMF proportional to the light falling on the material.

These three effects are known as the photo-emissive, photoconductive and photovoltaic effects. Thus photo-sensitivity is a generic term embracing all three effects.

photo-transistor A ***bipolar transistor*** in which the output current is determined primarily by the amount of light falling on the base region. Absorption of ***photons*** in the base region liberates charge carriers so giving rise to a collector current. In circuits using photo-transistors the base may be left disconnected or may be returned to the emitter via a high impedance. The graphical symbol for a photo-transistor is given in *Figure P.16* (b).

photo-tube A vacuum or gas-filled tube containing a ***photocathode*** and an ***anode***. The ***photo-electrons*** liberated from the cathode when light falls on it are collected by the positively-charged anode to give an anode current. The sensitivity of the gas-filled tube is greater than that of the vacuum tube because of the increased anode current caused by ***ionisation***. See ***gas-amplification factor***.

photovoltaic effect The generation of a voltage between two dissimilar materials when their junction is irradiated by electromagnetic waves.

physical In computing, relating to the actual structure of a system or an operation or a block of data. This contrasts with its ***logical*** form which is presented to the user, which is not necessarily the same. For example, if a ***hard disk*** is ***partitioned*** so that it appears to the user as several separate drives, it may be described as one *physical* drive which appears as several *logical* drives.

pickup In general a ***transducer*** which converts signals in a non-electrical form of energy into corresponding electrical signals. Thus a TV camera tube was, at one time, termed a vision pickup tube but this term is now deprecated. The term pickup now tends to be confined to disk reproducing heads which convert the mechanical movements imparted to the stylus by the groove walls of the disk into corresponding electrical output signals.

picture element In TV the smallest area of a picture which can be reproduced. The picture is regarded as composed of a large number of elements arranged in horizontal lines or rows, the length of each element being equal to the vertical distance between neighbouring lines, i.e. the elements are regarded as squares. During transmission the elements are explored in turn by the scanning beam but the system cannot resolve detail finer than that of an element. Thus the picture signal corresponding to a row of alternate black and white elements is a sine wave, as shown in *Figure P.17*, and its frequency is equal to the upper frequency limit of the video bandwidth of the system; but see ***Kell factor***.



Figure P.17 Form of picture signal for a row of alternate black and white elements

In computing, the American term *pixel* is used for the smallest part of a ***VDU*** display or a ***bitmap*** that can be addressed. Pixels are most often square and, in a ***VGA*** screen, have a nominal size of 1/96 inch per side. Each pixel is represented in ***video memory*** by a number of bits, the number being the logarithm (base 2) of the number of colours in the display (or bitmap). Thus a two-colour (monochrome) display requires only 1 bit per pixel (since $2^1 = 2$), a 256-colour display requires 8 bits per pixel ($2^8 = 256$) and a 16,777,216-colour (*true-colour*) display requires 24 bits per pixel ($2^{24} = 16,777,216$).

picture frequency In TV the number of times the whole picture is scanned in a second. In the British television system the picture frequency is 25 Hz and in the USA it is 30 Hz.

picture signal In TV or facsimile the signal which results from the scanning process and which, when combined with the synchronising signal, forms the video signal. See *Figure B.18* (a).

picture/sync ratio In TV the ratio of the maximum picture signal amplitude to the amplitude of the synchronising signals. In *Figure B.18* (a) it is given by: (***white level–blanking level***) : (***blanking level–sync level***). The ratio must be chosen with care for if it is too large the sync signals will be too small to hold pictures steady at the receiver and if it is too small the pictures may be too noisy to view even though synchronisation may be perfect. In the compromise adopted in the UK the picture/sync ratio is 7 : 3.

picture tube A ***cathode ray tube*** used to display pictures in a TV receiver or monitor. They usually have electrostatic focusing and are designed for wide-angle magnetic deflection to give a short tube suitable for mounting in a cabinet. Tubes for displaying black-and-white pictures have a single electron gun and a screen made of a continuous layer of phosphor giving an approximation to white light. For displaying colour television pictures three guns are necessary (or a single gun firing three beams) and the screen is made up of dots or stripes of phosphors giving red, green and blue light. See ***delta-array picture tube***, ***precision-in-line picture tube***.

Pierce oscillator A ***Colpitts oscillator*** in which ***positive feedback*** is provided by the input and output capacitances of a three-terminal ***active device***, a ***piezo-electric crystal*** connected between input and output terminals determining the frequency of oscillation.

piezo-electric ceramic A ceramic material which, after processing, exhibits the ***piezo-electric*** effect.

piezo-electric crystal A crystal with piezo-electric properties. The most frequently-used piezo-electric crystals are those of quartz, tourmaline and Rochelle salt.

piezo-electric effect The development of voltages between the faces of certain crystals when they are subjected to mechanical stress and the converse mechanical deformation of the crystal when voltages are applied between the faces. These properties are exploited in crystal loudspeakers, microphones and pickups. See ***bimorph***.

Slices of piezo-electric crystal suitably oriented with respect to the crystallographic axis also exhibit resonance. For example if a voltage is suddenly applied to or removed from the faces of such a slice, the crystal oscillates with diminishing amplitude at a frequency characteristic of the crystal. A voltage at this frequency applied to the crystal keeps it in continuous oscillation. The crystal behaves in fact as an *LC* circuit of very high *Q* and very high stability. Such crystal slices are used to control the frequency of oscillators where high stability is required. See ***crystal oscillator***.

piezo-electric element A piezo-electric crystal or piezo-electric ceramic material cut to a required size and shape, correctly oriented with respect to the crystallographic axis of the material and provided with electrodes. Such elements are used in ***microphones***, ***loudspeakers*** and ***pickups***.

piezo-electric loudspeaker Same as ***crystal loudspeaker***.

piezo-electric microphone Same as ***crystal microphone***.

piezo-electric oscillator Same as ***crystal oscillator***.

piezo-electric pickup Same as ***crystal pickup***.

pilot or **pilot carrier** A signal, usually a single sinusoidal wave, transmitted over a telecommunications system to indicate the transmission characteristic or to control it. The pilot may be used, for example, for automatic control of the received level of signals transmitted over the system or for synchronisation of the oscillator used for demodulation.

pilot lamp A lamp used to indicate the condition of an associated circuit. A pilot lamp is commonly used, for example, to indicate that an item of equipment is switched on, has reached its correct operating temperature, is faulty, etc, distinctive colours being used to identify the function.

pilot-tone stereo Compatible FM system of stereo sound transmission in which the sum of the left and right signals is transmitted as in monophonic FM systems and the difference signal is transmitted as double-sideband suppressed-carrier amplitude modulation of a subcarrier. A pilot tone at half the subcarrier frequency is also transmitted at low level and is used at receivers to synchronise the demodulator which recovers the difference signal.

pinch Part of the envelope of an ***electron tube*** (or electric lamp) carrying the wires which support the ***electrodes*** and provide the electrical connections to them.

pinch effect In disk reproduction, vertical motion of the tip of the pickup stylus caused by variations in the angle between the groove walls. On recording the angle is less when the cutter is between the peaks of its swings than at the peaks themselves and thus the reproducing stylus makes two vertical movements per recorded cycle and these can result in second harmonic distortion.

pinch off In a ***field-effect transistor***, cut off of the drain current. For example, the negative gate voltage which reduces the drain current to zero in an n-channel device is known as the pinch-off voltage.

pin-cushion distortion Distortion of a TV picture in which the sides of a reproduced square bulge inwards. The distortion, illustrated in *Figure P.18* is caused by non-uniformity of the field produced by the scanning coils. It is the opposite of ***barrel distortion***.



Figure P.18 Reproduction of a square by a picture tube suffering from pin-cushion distortion

pin diode A semiconductor diode containing a region of ***intrinsic semiconductor*** between the p- and n-regions. The transit time across the intrinsic region limits the operating frequency when the diode is used as a detector to below 100 MHz and at microwave frequencies the diode behaves as a linear resistance. However, if a forward bias is applied, carriers are injected into the intrinsic region and the diode resistance falls to a low value, possibly only one thousandth of the reverse resistance. Thus the pin diode is extensively used as a modulator and switch in microwave systems.

pi-network (**π-network**) A ***network*** consisting of two shunt elements with a series element between them. The form of the network is illustrated in *Figure P.19*.



Figure P.19 A π-network

pink noise The noise signal obtained by passing a ***white noise*** signal through a filter with a response which falls at the rate of 3 dB per octave over the frequency range of interest.

pinout A diagram showing the arrangement of the pins of a ***transistor*** or an ***integrated circuit*** with the function of each.

pitch The position of a sound in the musical scale. For a sound with a complex waveform the pitch is determined by the fundamental frequency whether this is present as a discrete component or not. For orchestral performances the fundamental frequency for A in the treble clef is internationally agreed as 440 Hz.

pixel (US) Same as ***picture element***.

planar process The formation of n-type and p-type regions in a semiconductor crystal by introducing impurities via apertures in a mask on the surface. The introduction of this process in 1960 revolutionised the manufacture of silicon transistors, making mass production possible for the first time. A very thin layer of silicon dioxide is grown on the surface of a slice of n-type monocrystalline silicon by heating it to 1100°C in a stream of oxygen. This surface is then coated with a layer of ***photo-resist***. A mask defining the base areas of the transistors is placed over the surface and exposed to ultra-violet light. The photo-resist polymerises where exposed to the light and is then resistant to attack by acids and solvents. On development the unexposed areas of the photo-resist are removed, exposing the silicon dioxide. An etch removes the silicon dioxide, exposing the base area, into which a controlled amount of boron is introduced by diffusion, ion-plantation or other means. By repeating this process with another mask the emitter areas can be defined and the required amount of phosphorus is introduced. Finally a third mask is used to define the positions for connections to the base and emitter areas, the original slice acting as the collector. By this process tens of thousands of transistors can be manufactured simultaneously on a single crystal slice.

Although the above description applies only to the manufacture of bipolar silicon transistors it can obviously be used for making a wide variety of semiconductor devices, including diodes and field-effect transistors. Because the process can also be used for making interconnections between devices, monolithic integrated circuits can also be manufactured in this way. So can RAMs, ROMs and many other devices.

planar transistor A ***bipolar*** or ***field-effect transistor*** manufactured by the ***planar process***.

plane of polarisation Of an ***electromagnetic wave***, the plane containing the direction of the electric field and the direction of propagation.

plasma A region in an ionised gas where the number of positive ***ions*** equals the number of ***electrons*** so that there is no net charge.

plasmatron A gas discharge tube in which the conducting path between the ***anode*** and the main ***cathode*** is provided by ***plasma*** generated by a subsidiary cathode.

plastic effect In TV an effect of relief in reproduced images caused by exaggeration of the tonal transitions. The effect can be caused by a poor low-frequency response in the video amplifier. It can also be caused in images reproduced from an ***image orthicon*** tube because this type of tube tends to provide black borders around image highlights.

plate (US) Same as ***anode***.

plate detector Same as ***anode-bend detector***.

plated-through holes Holes drilled through the conducting tracks of a ***printed-wiring board*** to accept the connecting leads of components mounted on the board. The holes are plated with metal to give good electrical contact between the leads and the tracks when the components are soldered into position. See ***chip carrier***, ***dual-in-line package***, ***surface mounting***.

platform A term sometimes used to refer to the make or type of computer. Thus an ***application*** is said to be available for *cross-platform* if it is available for different types of computer.

platter One of the disks present in a ***hard disk drive***.

playback The process of reproducing a programme that has been ***recorded***.

plotter A computer ***peripheral*** used for producing hard copies of drawings such as those generated in ***computer aided design*** software. A plotter consists of one or more pens which can move backwards and forwards (the X-axis) and lift off the paper. The paper can be wound backwards and forwards through the plotter, providing the Y axis. Any line drawing can be reproduced by the appropriate sequence of movements of the pen and the paper under computer control. A plotter is the only computer output device that can reproduce genuine curves and oblique lines; all other devices print dots on a rectangular matrix that can only simulate oblique lines and curves.

plumbicon A low-velocity TV ***camera tube*** with a photoconductive target containing lead. Modern plumbicon targets are of multi-layer construction and their lag and sensitivity are such that the plumbicon is now the standard tube used in colour TV cameras. See ***vidicon***.

pn boundary Same as ***junction***.

pnip transistor See ***npin transistor***.

pn junction Same as ***junction***.

pnp transistor Type of ***bipolar transistor***.

point-contact diode Early form of semiconductor diode which consisted of a whisker of a metal alloy pressed against a crystal of semiconductor material. Point-contact diodes have now been superseded by ***junction diodes*** which are more robust and easier to manufacture.

point-contact transistor Obsolete type of transistor in which the emitter and collector connections to the base wafer were made by whiskers of a metal alloy. Manufacture of these devices was abandoned years ago in favour of ***bipolar (junction) transistors*** which are easier to mass produce and are more robust.

pointer In computing an ***icon***, often shaped like an arrow, that the user moves around the screen by means of a ***mouse***, ***trackerball*** or other ***pointing device***. The pointer forms part of a ***graphical user interface***. Operations are initiated by moving the pointer over fixed icons on the screen or over options in menus and clicking, that is pressing, a button on the pointing device.

point gamma In TV the slope of the curve relating the logarithm of the output of a device, equipment or system to the logarithm of the input. The input or output may be light or an electrical signal and thus there can be a point gamma for a camera tube, a picture tube or the overall system. See gamma.

pointing device In computing, the ***hardware*** used to move the ***pointer*** around the screen in a ***graphical user interface***. The most commonly used pointing device is the ***mouse***; others include ***joysticks*** and ***trackerballs***.

poke In computing, to set the value contained in a ***byte*** of memory. See also ***peek***.

polar diagram In general, of a quantity which varies with direction, the closed figure generated by the tip of the radius vector as it rotates through 360°, its length representing the magnitude of the quantity and its angle the direction.

Such diagrams are used in electronics to indicate the directivity, e.g. of ***antennas*** and ***microphones***. An omnidirectional response such as that of a vertical radiator in the horizontal plane is represented by a circular polar diagram and a double-sided response such as that of a ribbon microphone (with ribbon vertical) in the horizontal plane is represented by a figure-of-eight polar diagram.

polarisation (1) Of a ***primary cell*** the liberation of gas at the electrodes during discharge. This limits the current that may be drawn from the cell. See ***depolarisation***. (2) Of an electromagnetic wave the direction of the plane containing the electric vector and the direction of propagation. This is, in general, also the direction of the plane of the conductors forming the radiating antenna. Thus a vertical antenna radiates a vertically-polarised wave.

polarity Originally the distinction between the North and South poles of a magnet or the positive and negative terminals of a cell. The term is now more generally applied, e.g. to the potentials of any two terminals of a circuit and to the connections to the loudspeakers in a stereo system which can be said to be correctly polarised when the diaphragms move in phase.

pole (1) A terminal of a ***network*** or a ***cell***. (2) In ***magnetism*** that region of a magnet from which the lines of force of the external magnetic field appear to diverge or converge. In a bar magnet these regions are normally near the ends and if the magnet is freely suspended at its centre it comes to rest with its axis aligned with the earth's magnetic field. The poles are therefore known as the north-seeking or more simply the north pole and the south-seeking or south pole. Magnets can, however, be made with the poles at any desired point in them. (3) For a network of pure reactances, any frequency at which the input reactance is infinite. As shown in *Figure Z.2* the reactance-frequency relationship for a ***network*** of pure reactances is a succession of curves, all with positive slope, which swing between minus infinity and plus infinity, passing through zero, in a manner similar to that of a tangent curve. The poles are the frequencies at which the curves approach infinity, i.e. antiresonant frequencies at which the network presents at its input terminals the equivalent of an inductance and capacitance in parallel.

pool cathode See ***mercury pool cathode.***

port In a ***network*** a pair of terminals at which signals may be fed into the network or withdrawn from it. A two-terminal-pair network such as the simple filter shown in *Figure P.20* may thus be described alternatively as a two-port network.



Figure P.20 An example of a two-port network

porting The process of converting an ***application*** for use on a computer of a different type. Porting is easier if the program is written in C which was specifically designed for use on widely differing machines.

positive feedback ***Feedback*** in which the signal returned to the earlier stage of the amplifier is in phase with and therefore augments the input signal at that point. Positive feedback has the effect of increasing the gain of the amplifier and was used for this purpose in early ***electron tube*** receivers where the feedback was called ***reaction.*** If, however, the amplitude of the feedback signal equals that of the normal input signal, it can take the place of the normal input and the amplifier becomes a generator. This is the basis of a large number of oscillator circuits which are distinguished from each other only in the way in which the positive feedback is obtained.

positive logic A ***computer*** or ***data-processing system*** in which the more positive of the two voltages selected as the logic levels is designated the 1-state.

positive modulation In TV transmission, ***amplitude modulation*** in which increased picture brightness results in increased carrier amplitude. This is the system used in the original British 405-line television system.

post-alloy diffused transistor (PADT) Same as ***mesa transistor.***

post-deflector accelerator Same as ***intensifier electrode.***

post emphasis (US) Same as ***de-emphasis.***

post equalisation (US) Same as ***de-emphasis.***

PostScript A page description language devised by Adobe. It allows pages of ***text*** and ***graphics*** to be described in a plain text file. It is widely used in

laser printers and phototypesetting equipment. A subset, ***Encapsulated PostScript***, is also sometimes used as a common language for transferring ***vector graphics*** images between computers of different types.

potential At a point the work done in bringing a unit electric charge from infinity to that point. It is measured in volts and is often termed the ***voltage***.

potential difference (PD) The difference in electrical states at two points which causes an electric current to flow between them when they are connected by a conductive path. The PD is measured by the work done in moving a unit electric charge from one point to the other. It is measured in volts and is often termed the ***voltage***.



Figure P.21 A simple potential divider composed of two resistors

potential divider A circuit consisting of a number of similar elements in series connected across a voltage source, voltages being taken from the inter-element connections. Frequently the potential divider consists of two resistors as shown in *Figure P.21* and the division ratio, i.e. the ratio of v_{out} to v_{in} is given by

$$\frac{v_{out}}{v_{in}} = \frac{R_2}{R_1 + R_2}$$

See ***capacitance potentiometer***.

potentiometer (1) An instrument for measuring an unknown voltage by balancing it in a bridge circuit against a known voltage. (2) A resistive two-element potential divider in which the division ratio is adjustable. Such devices are extensively used in electronic equipment for adjustable controls, e.g. to control ***gain*** and are constructed in the form of a resistive element carrying a sliding contact which is adjusted by a rotary or linear movement of the control knob. The graphical symbol for a potentiometer is given in *Figure P.22*.



Figure P.22 Graphical symbol for a potentiometer

power amplifier An amplifier designed to deliver substantial output power. The term is used to distinguish such amplifiers from voltage or current amplifiers which are often used to drive power amplifiers. Examples of power amplifiers are those used to drive ***loudspeakers*** or transmitting ***antennas***.

power down The sequence of operations that must be performed when an equipment is switched off. In ***computers*** and ***data processing equipment*** all open files should be closed or valuable data may be lost.

power factor In an AC circuit the ratio of the real power to the apparent power, i.e. the ratio of the dissipation to the product of applied RMS voltage and resulting RMS current.

In a resistive circuit, voltage and current are in phase and the dissipation is equal to their product so that the power factor is unity. In general, however, there is a phase difference between voltage and current and the dissipation is then the product of the active (in-phase) current and applied voltage which is less than the product of external current and applied voltage. The ratio of the two, i.e. the power factor is in fact given by the cosine of the phase angle (cos ϕ). In a simple series circuit the power factor is given by the ratio of resistance to impedance and is thus the reciprocal of the Q factor.

power grid detection ***Grid-leak detection*** employing an ***electron tube*** with a large grid base and a high-voltage anode supply which can accept large input signals without introducing the distortion which arises from the curvature of the I_a–V_g characteristic near anode-current cut off. The time constant of the grid capacitor-grid resistor combination is made smaller than that normally used in grid-leak detection.

power pack (US) Same as ***mains unit.***

power up The sequence of operations that must be performed when an equipment is switched on.

pre-amplifier An amplifier designed to raise the level from a signal source to a value suitable for driving a main amplifier. Where the signal source has a very low output, as for some high-grade microphones, the pre-amplifier may be located very close to it as a means of preserving a good ***signal-to-noise ratio.*** See ***head amplifier.*** In hi-fi equipment the pre-amplifier often incorporates facilities for disk and tape equalisation, audio mixing and tone control.

precision-in-line picture tube (PIL) Same as a ***shadow-mask picture tube*** in which three electron guns (or the three beams from a single gun) are arranged in a horizontal plane and the screen consists of vertical stripes of red, green and blue phosphors. As shown in ***Figure P.23***, the mask has vertical slits, one for each group of three phosphor strips, so arranged that each strip is masked from two of the beams. The ***convergence*** for such tubes is considerably simpler than for ***delta-array picture tubes.***

pre-emphasis The use of a ***network*** which accentuates the response at high frequencies before an audio signal is recorded or transmitted. A corresponding de-emphasis network is used at the reproducing or receiving end to ensure an overall level frequency response. The falling high-frequency response reduces the subjective effect of noise introduced during the transmission or recording process so improving the ***signal-to-noise ratio.***

preferred value Series of values in which each differs from the preceding by a constant multiple and used by international agreement for the values of resistors and capacitors. The system was adopted as a means of reducing to a minimum the number of values required to cover a given range. The value of the constant multiple depends on the tolerance of the component



Figure P.23 Precision-in-line colour picture tube: basic arrangement of electron gun, shadow mask and screen.

value. For example the values for a 20% tolerance are

10 15 22 33 47 68 100

and for 10% tolerance the following intermediate values are added

12 18 27 39 56 82.

presence In reproduced sound the illusion of closeness to the performer or instrument. Presence can be improved by applying a lift to frequencies in the range of 3 to 5 kHz and this is commonly done in hi-fi reproduction.

preset control A variable control intended for infrequent adjustment. An example is provided by the ***trimming*** capacitors in a ***superheterodyne receiver*** which are adjusted when the receiver is aligned after manufacture and are unlikely to require subsequent attention. Such controls are often designed for operation by a screwdriver and are not normally accessible to the receiver owner.

preshoot Form of transient distortion of a step or pulse signal in which the reproduced step is preceded by oscillation. A typical example of preshoot is given in *Figure P.24*.



Figure P.24 An example of preshoot

pressure-gradient microphone A microphone of which the electrical output is proportional to the instantaneous particle velocity of the sound wave to which it responds. In such microphones both faces of the diaphragm are exposed to the incident sound wave so that movement of the diaphragm depends on the difference of the acoustic pressure exerted on the two faces and this difference is proportional to the particle velocity.

A ***ribbon microphone*** in which both faces of the ribbon are exposed to the sound input is an example of a pressure-gradient microphone and one of its most useful properties is that, with the ribbon vertical, it is effectively double-sided, having a figure-of-eight polar diagram in the horizontal plane.

pressure microphone A microphone of which the electrical output is proportional to the instantaneous pressure of the sound wave to which it responds. In such microphones only one face of the diaphragm is exposed to the incident sound wave, the other face being totally enclosed.

A ***moving-coil microphone*** is an example of a pressure microphone and one of its most useful properties is that, if the plane of the diaphragm is horizontal, it is effectively omnidirectional in the horizontal plane, the polar diagram being circular.

Prestel The ***videotex*** system of British Telecom.

preventive maintenance Maintenance designed to detect ageing or failing components which can thus be replaced before they cause failure of the equipment. Typically preventive maintenance consists of a regular application of performance tests.

primary cell A ***voltaic cell*** in which the chemical energy of its constituents gives rise to a current in an external circuit but in which the action is not normally reversible as in a ***secondary cell***. There are many different types of primary cell. See ***Leclanché cell***, ***mercury cell***.

primary electron An electron liberated from a heated cathode by thermionic emission or from a photocathode irradiated by light or from a cold cathode by an intense electric field. See ***secondary electron***.

primary storage Same as ***main storage***.

printed circuit Printed wiring designed to perform a function other than interconnections between components. For example a conducting path can be given a helical form so as to have sufficient inductance for UHF tuning.

printed wiring A pattern of conductors formed on an insulating base and extensively used for the interconnection of components in electronic equipment.

The insulating base is initially given a uniform coating of copper and the required conductor pattern is then printed photographically on the surface in a material which protects the copper. The unwanted copper and the protective material are then removed by immersion in baths of suitable solvents, leaving the printed wiring as a layer of copper. Connections between the printed wiring and components can be achieved by soldering the wire leads of resistors, capacitors, transistors, etc, to the copper where they project through holes drilled in the copper. There are automatic methods of making such soldered connections. An alternative method is ***surface mounting***. See ***chip carrier***, ***dual-in-line***, ***dual-in-line package***, ***plated through holes***.

printer A device which converts suitably coded output from a computer into hard copy printed on paper or other material. All printers reproduce ***text*** and most also handle ***graphics***. The connection to the ***host*** computer is often by a parallel link, e.g. ***Centronics standard***, but sometimes a serial connection is used.

The printer types in most common use are:

Daisy wheel printers A spin-off of typewriter technology, these use a printhead having a detachable *daisy wheel*, so called because the radial platens bearing the reverse impressions of the characters superficially resemble the petals of a daisy. As the printhead scans the paper the daisy wheel is rotated until the required platen is opposite the print position and then the platen is pressed against the paper through an inked ribbon, usually a plastic one-trip ribbon. The system has the advantages of excellent print quality; moreover the typeface may be changed easily by swapping daisy wheels. But the machines are noisy and incapable of reproducing graphics. They are no longer widely used.

Impact dot matrix printers These employ a print head consisting of a vertical row of closely spaced pins, usually 9 or 27 in number, each controlled by a ***solenoid***. As the head scans across the paper, the solenoids are momentarily energised at intervals forcing the pins to strike the paper through an ink-impregnated fabric or plastic ribbon. These printers are suitable for draft documents and internal memos, but not for high-quality document mastering. Graphics can be printed, but inaccuracies of the print head mechanism often result in vertical lines being crooked while the inking of solid areas is often inconsistent because of uneven ribbon wear.

Line printers are specialised dot matrix printers used for long print jobs. They employ a number, sometimes 33, of print heads spaced evenly across the page. Each has a single pin. The heads are moved from side to side to allow the pins to reach every position across the page. The paper is advanced one dot position at a time. Line printers can print over 400 lines of text per minute with high reliability and low operating costs. They are used mainly by medium to large businesses for printing invoices and form letters.

Ink jet and bubble jet printers A development of dot matrix printers in which the pins and inked ribbons are replaced by tiny nozzles through which minute droplets of ink are fired at the paper. The positional accuracy and consistency of inking are greatly superior to those of impact dot matrix machines and high-quality output is obtainable. Many machines offer a resolution of 360 × 360 dots per inch and some offer 720 × 720 dots per inch. Colour ink jet machines use cyan, magenta, yellow and black inks to simulate a wide range of colours, as in commercial printing.

Laser printers These use technology developed for the xerographic photocopying process. A ***laser*** or other light source is used to write a reverse image of the document on an electrostatically charged drum. As the light hits the drum it neutralises the charge. The drum is then dusted with powdered ink called *toner* which is attracted into those areas of the drum surface that still bear a charge. The drum is then rolled over the paper transferring the image in toner on to it. Finally the paper is momentarily heated to melt the toner so that it adheres firmly to the paper, forming a permanent image. Output is fast and print quality excellent. Resolution varies from 300 x 300 dots per inch to 1200 x 1200 dots per inch. Colour laser printers are available, but at the time of writing this technology is still in its infancy. The only disadvantage is that the entire bitmapped image of the document has to be built up at once, usually in the printer's memory. An A4 printer at 300 x 300 dots per inch requires approximately 1 Mbyte. For this reason laser printers are sometimes called *page printers*.

Other printer types currently available use wax thermal and dye sublimation technology. These are used mainly for specialised colour work. They offer the advantage that the dot structure is invisible because the dyes diffuse into each other.

printout The ***hard copy document*** produced by a ***printer***.

print-through In magnetic tape recording the undesired transfer of a recorded signal from one part of a tape to another part when the two parts are brought into contact. This can occur when tape carrying strong signals is wound on spools. On reproduction the transferred signals give weak and usually distorted versions of the strong signals.

probe (1) A unit containing the input stage of an electronic voltmeter or oscilloscope and connected to the main part of the instrument via a multi-core cable so permitting the unit to be positioned very close to the circuit under investigation. A probe permits very short connections to be made to the signal source being measured or examined so minimising capacitive loading of the source.

(2) A conductor of resonant length projecting into a ***waveguide*** or ***cavity resonator*** to inject or abstract RF energy.

processor See ***central processing unit***, ***microprocessor***.

product detector A circuit with two inputs which gives an output proportional to the product of the inputs. Such detectors are used for reception of CW and suppressed-carrier signals. These signals constitute one of the inputs and the other is from a carrier-insertion oscillator the frequency of which is adjusted to give a suitable audio note in CW reception and is adjusted to the (missing) carrier frequency in suppressed-carrier reception. See ***continuous wave***, ***suppressed carrier modulation***.

program For a ***digital computer*** a set of instructions arranged in the correct sequence to achieve the desired result. The result may be the solution of a problem or the preparation of a required set of data.

programmable logic controller (PLC) A specialised ***microcomputer*** intended for controlling industrial equipment and processes.

programmable read-only-memory (PROM) A ***non-volatile read-only memory*** which can be programmed by the user. For a memory using ***bipolar transistors*** this can be done by applying voltages greater than the normal operating voltages. The device has fusible links in series with one of the eletrodes in each ***memory cell*** and the abnormal voltages destroy the links to the chosen cells, thus programming the memory. Once this is done the device is permanently programmed and there is no means of changing the program, but see ***EPROM*** and ***EEPROM***.

programmable terminal A ***terminal*** with a store capable of operating under the control of a stored program.

programmable workstation (PWS) A suitably equipped microcomputer running ***terminal emulation*** software to allow access to a mainframe computer. An advantage of programmable workstations over ***dumb terminals*** is that, in a multitasking environment, an application may be run simultaneously which performs all accesses to the ***host*** mainframe computer automatically, providing a user-friendly interface to the mainframe.

programme meter An instrument for indicating the volume of an audio signal. Two types of programme meter in common use are the ***peak programme meter*** and the ***volume indicator.***

programme volume In sound broadcasting the amplitude of an audio signal as indicated by a ***programme meter.***

projection television System for reproducing TV pictures in which the image formed on the screen of a small picture tube is optically projected on to a larger viewing screen. In domestic projection receivers the screen is of ground glass and the optical image is focused on the rear by an optical system incorporating a concave mirror, a plane mirror and a correcting lens designed to minimise optical distortion. The system is folded, as shown in *Figure P.25*, so as to occupy minimum space and is a version of the system originated by Schmidt for use in astronomical telescopes. For larger installations, e.g. in cinemas the optical image is projected on to the front surface of a reflecting screen.



Figure P.25 Folded optical system used in projecction television receivers

propagation coefficient or **constant** For a wave at a specified frequency and transmitted along a ***transmission line***, the natural logarithm of the vector ratio of the steady-state amplitudes of the wave at points unit distance apart.

For a ***network*** terminated in its iterative impedances at both ends, the natural logarithm of the complex ratio of the input current to the output current. The real part of propagation coefficient is known as the attenuation coefficient or constant and is a logarithmic measure of the ratio of the signal amplitudes. The imaginary part of the propagation coefficient is the phase coefficient and measures the phase difference between the two signals.

For symmetrical networks the real and imaginary parts of the propagation coefficient are equal to the real and imaginary parts of the ***image transfer coefficient***.

protective gap Two ***electrodes***, separated by a small air gap, and connected between the conductors of a ***transmission line*** or between a live conductor and earth to limit the voltage which can be developed. When the voltage exceeds a critical value which depends on the dimensions of the gap, a discharge occurs between the electrodes so removing the high voltage.

protocol An agreed set of rules and procedures for data transmission between two devices.

proton An elementary atomic particle with a positive charge equal to that of the electron but with much greater mass. It is one of the constituents of the atomic nucleus. See ***atomic structure***, ***electron***, ***neutron***.

proximity effect In a conductor carrying an alternating current a concentration of the current towards the edges of the cross section caused by interaction between the conductor and the electromagnetic field set up by neighbouring conductors carrying the same current. This effect is analogous to and additional to ***skin effect*** and becomes more marked as frequency is raised, causing the effective resistance of the conductor to increase steeply with increase in frequency. Proximity effect is particularly marked where a number of conductors carrying the same current are in close proximity as in RF inductors and transformers.

p-type semiconductor An ***extrinsic semiconductor*** material in which the hole density exceeds the free-electron density. Thus the positive charge carriers outnumber the negative charge carriers. The positive charge of a hole can be neutralised by injecting an ***electron*** into it from a neighbouring atom in the crystal lattice. This ***atom*** is then left with an electron deficiency (a ***hole***) which in turn can be neutralised by an electron injected from a third atom. In this way a current can be driven through the crystal under the stimulus of an applied EMF and this current can be regarded as a movement of holes (positive charge carriers) in one direction or of electrons (negative charge carriers) in the opposite direction. See ***n-type semiconductor***.

public address (PA) System of sound reproduction used for diffusing speech or music to large audiences. The system includes loudspeakers and amplifiers and a source of signal such as ***microphone***, ***disk-player*** or tape reproducer. Mixing facilities may also be incorporated. Such systems are widely used in public halls, factories, railway stations, airports, etc, for announcements or entertainment.

public domain software ***Software*** which may be copied, distributed, used or modified without any restrictions except that no one may claim copyright on it. See also ***freeware***, ***shareware***.

Puckle time base An early time base circuit in which the sawtooth voltage was generated across a capacitor charged via a ***pentode*** and discharged by a ***multivibrator***.

pulling Same as ***frequency pulling***.

pulsatance Same as ***angular frequency***.

pulse A sudden departure of short duration of a voltage or current from a steady value. Often pulses approximate to rectangular form and are then



Figure P.26 A pulse waveform with appreciable rise and fall times

characterised by steep leading and trailing edges as shown in *Figure P.26*. Pulses can, however, be of sawtooth or other form. See *fall time*, *rise time*.

pulse amplitude modulation (PAM) Modulation in which the amplitude of the pulses in a *pulse carrier* is made to vary in accordance with the instantaneous value of the modulating signal. See *Figure P.27*.



Figure P.27 Pulse amplitude modulation

pulse and bar signal In TV a test signal used for *k-rating* measurements. The signal has a duration of one line and and includes, in addition to a line sync signal, a *sine-squared pulse* and a rectangular pulse.

pulse carrier A regular train of identical pulses intended for *modulation*.

pulse code A code in which groups of pulses are used to represent information. One example is provided by the Morse code. In another example the pulses represent the quantised values of the amplitude of an *analogue signal*.

pulse code modulation (PCM) A modulation system in which the pulses constituting a *pulse carrier* are divided into groups, each group being modulated so as to represent the quantised values of the amplitude of the analogue signal to be transmitted. For example the pulses in each group can be modulated so as to represent the quantised values in binary code.

pulse counter detector A detector of frequency-modulated waves which operates by counting the number of cycles of RF in a given time interval, the variation in the totals constituting the required replica of the *modulating signal*.

pulse duration The time taken for the instantaneous value of a pulse signal to rise from and fall to a specified fraction of the peak value.

pulse duration modulation (PDM) *Modulation* in which the duration of the pulses in a pulse carrier is made to vary in accordance with the instantaneous value of the modulating signal. See *Figure P.28*.

pulse frequency See *pulse repetition frequency*, *pulse repetition rate*.

pulse frequency modulation (PFM) See *pulse repetition rate modulation*.

pulse interval See *pulse spacing*.



Figure P.28 Pulse duration modulation

pulse interval modulation (PIM) ***Modulation*** in which the spacing of the pulses in a pulse carrier is made to vary in accordance with the instantaneous value of the ***modulating signal.***

pulse modulation ***Modulation*** of a continuous-wave carrier by pulses or modulation of a pulse carrier by another signal.

pulse position modulation (PPM) ***Modulation*** in which the displacement in time of the pulses in a ***pulse carrier*** relative to the unmodulated value is made to vary in accordance with the instantaneous value of the ***modulating signal.***

pulse repetition frequency (PRF) The number of pulses per unit time. The term is used when the number of pulses per unit time is constant as in a regular train of pulses.

pulse repetition rate The average number of pulses per unit time. The term is used when the rate varies as in ***pulse repetition rate modulation.***

pulse repetition rate modulation ***Modulation*** in which the ***pulse repetition rate*** of the pulses in a pulse carrier is made to vary in accordance with the instantaneous value of the ***modulating signal.*** See *Figure P.29.*



Figure P.29 Pulse repetition rate modulation

pulse shaping The process of modifying the shape of a pulse to a desired form.

pulse spacing The interval between corresponding points on two consecutive pulses.

pulse spectrum The distribution with frequency of the Fourier components of a pulse.

pulse time modulation General term for ***modulation*** in which the time of occurrence of some characteristic of the pulses in a ***pulse carrier*** is made to vary in accordance with the instantaneous value of the ***modulating signal.*** Thus ***pulse duration modulation, pulse repetition rate modulation, pulse interval modulation*** and ***pulse position modulation*** are all examples of pulse time modulation.

pulse width modulation Same as ***pulse duration modulation***.

pumping (1) The process of evacuating the envelope of a vacuum tube. (2) In a parametric amplifier the supply of RF oscillation which energises the ***varactor***. In a laser or maser the provision of energy in the form of light or RF which excites the atoms which then emit ***radiation***.

punched card A card in which a pattern of holes is punched to represent data. A standard type of card has 80 columns, each with 12 positions at which a hole may be punched. Each column can represent a character (letter, numeral or symbol) according to the position of one, two or three holes in the 12 positions for that column. Such cards can provide the input for a ***digital computer***, a punched-card reader being necessary to provide the electrical input signal for the computer.

punched tape A tape, usually paper, in which a pattern of holes is used to represent data. Each character (letter, numeral or symbol) is represented by a unique pattern of holes across the width of the tape. Commonly there are eight tracks across the width, seven used for coding the information and the eighth used for ***parity checking***.

purity In colour TV the degree to which a display in one of the primary colours is free from contamination by the other primary colours.

push-pull operation A form of operation of electronic equipment in which two matched signal chains are used to carry signals in phase opposition. A phase-splitting device is used to derive the signals for the two chains and the two signals are recombined at the output. The system has the advantage of minimising even-harmonic distortion, avoids the need for polarising transformer cores and gives economy of current by permitting ***class-B operation*** of ***active devices***.

The principles are illustrated in the circuit diagram of a typical stage of push-pull amplification shown in *Figure P.30*. The two transistors must be accurately matched in characteristics, the antiphase input signals are derived from the centre-tapped secondary winding of the input transformer and the output signals are combined in the centre-tapped primary winding of the output transformer.



Figure P.30 Simple example of a push-pull stage of amplification

Q

Q* factor** Of an inductor or capacitor the ratio of its ***reactance to its effective series resistance. An ideal inductor or capacitor has no series resistance and the *Q* factor is therefore infinite. Practical components inevitably have resistance and thus *Q* factors are finite: they are, in fact, a figure of merit indicating the extent to which the component approximates to a pure reactance. For inductors *Q* values of 100 to 300 are possible and for capacitors much higher values are common. For an inductor *Q* is given by $L\omega/R$ and for the capacitor $1/\omega CR$.

quadraphony In sound reproduction an extension of the stereo principle, in which two further channels are used to originate stereo sound behind the listener to give the illusion that he is surrounded by sound. Quadraphony is, in fact, sometimes called surround sound. The four channels are identified as front left, front right, back left and back right.

A number of systems for broadcasting quadraphonic sound (compatible with existing stereo and monophonic FM broadcasting) and of recording it on disk (compatible with existing stereo and monophonic disks) have been proposed and used but so far there has been no international agreement. There is, of course, no difficulty in recording the four quadraphonic channels as separate tracks on magnetic tape and such tapes are available.

quadrature The relationship between two sinusoidal signals at the same frequency when there is a 90° (π/2 radians) phase difference between them. As an example the current in a loss-less inductor or a loss-less capacitor is in quadrature with the applied EMF, the current in the inductor lagging the EMF and the current in the capacitor leading the EMF.

quadrature detector A detector used to demodulate a ***quadrature modulated*** signal, i.e. to abstract from a quadrature-modulated carrier replicas of the two original modulating signals. Such a detector is an example of a ***synchronous detector*** and is used in an NTSC or PAL television receiver to derive the two ***colour-difference signals*** which together constitute the ***chrominance signal***.

quadrature modulation Method of transmitting two ***modulating signals*** independently on one carrier by splitting the carrier into two components in quadrature and using each signal to modulate one of the components. This method is used in the ***NTSC*** and ***PAL*** colour TV systems to transmit the two colour-difference signals. They are transmitted by suppressed-carrier amplitude modulation of the two quadrature components of the colour sub-carrier.

quadripole A ***network*** with two input terminals and two output terminals. It is sometimes termed a 4-terminal, 2-terminal-pair or 2-port network.

quality factor Same as ***Q factor***.

quantising For a quantity which can have any value between certain limits the division of the range between the limits into a number of sub-ranges, any value within a sub-range being represented by an assigned value within the sub-range. The sub-ranges need not necessarily be equal. Thus when an analogue signal is quantised, the instantaneous amplitude of the resulting signals can have only a limited number of values—equal, in fact, to the number of sub-ranges originally decided. These values can be expressed, for example, in binary code and can thus be transmitted by a ***pulse modulation system***.

quantising distortion (or **noise**) The distortion (or ***noise***) introduced by quantising. An ***analogue signal*** after quantising jumps in amplitude from one quantising level to another and these jumps give rise to distortion the magnitude of which depends on the number of quantising levels employed. The greater the number of levels chosen the less is the quantising distortion but to reduce distortion to the level needed in high-quality sound reproduction requires at least 1000 levels and in practice 2^{12} (4096) are employed.

quarter-wave line (or **transformer**) A length of ***transmission line*** with an electrical length of a quarter of a ***wavelength*** at the operating frequency, used for impedance matching and for isolating at radio frequencies. Such lines are used, for example, to match the characteristic impedance Z_o of a feeder to the driving-point impedance Z_a of an ***antenna***, correct matching being achieved when the characteristic impedance of the quarter-wave section is the geometric mean of Z_o, and Z_a. If a quarter-wave line is short-circuited at one end, the other end presents an infinite impedance at the operating frequency. This isolating property enables short-circuited quarter-wave lines to be used for supporting transmission lines and antenna elements without effect on their performance.

quartz crystal Natural crystal of silicon dioxide with pronounced piezo-electric properties. Such crystals are used for controlling the frequency of oscillators where great stability is required.

quench frequency The frequency at which an ***oscillation*** is quenched. In a ***super-regenerative receiver***, for example, the quench frequency must be ultrasonic to avoid audible interference with the received signal.

quenching The periodic suppression of an ***oscillation***. The term was applied to the suppression of the primary wavetrain in the obsolete quenched-spark transmitting system and is now used to describe the process of terminating the discharge in a ***Geiger-Muller tube***. It is also applied to the suppression of oscillation in a ***super-regenerative receiver***.

quiescent-carrier modulation In telephony, ***modulation*** in which the carrier is suppressed when there is no ***modulating signal*** to be transmitted.

quiescent current The current taken by the ***anode*** (***collector*** or ***drain***) of an ***active device*** or by an equipment from the DC supply in the absence of an input signal. It is the current at the ***quiescent point***.

quiescent point Of an ***active device***, the position of the ***operating point*** when no input signal is applied. The quiescent point indicates the mean current and the mean voltage in the output circuit and so measures the dissipation within the active devices in the absence of an input signal.

quiescent push-pull operation (QPP) A push-pull circuit using two ***pentodes*** biased near anode-current cut off once popular in battery-operated equipment. The circuit is an example of a class B1 amplifier and its economy of HT consumption was its principal attraction.

quiet automatic gain control (QAGC) A combination of ***delayed AGC*** and signal suppression so designed that the audio output of the receiver is suppressed for input signals too weak to operate the AGC system. Quiet AGC has the advantage that only signals capable of operating the AGC system are received and these stand out from a quiet background. In particular the inter-station noise normally heard when the tuning control is operated is absent from a receiver with quiet AGC.

R

radar (radio direction and ranging) Equipment originally designed for measuring the range and bearing of any object by means of radio waves reflected or retransmitted from the object.

In this system a pulse of RF energy was radiated from the radar and this pulse together with the reflected pulse were displayed as blips on the screen of an oscilloscope, the distance between them indicating the range. A later development used a rotating antenna synchronised with a radial time base in the oscilloscope. By using the reflected signals to intensity modulate the oscilloscope beam it was possible to give a display in the form of a map of the surrounding area with moving objects indicated on it: a long-persistence tube was generally used for such displays so that the map persisted for the duration of the sweep. Radars of this type are particularly useful as navigational aids in ships and aircraft.

Radars are nowadays very sophisticated. In addition to the above-mentioned applications these equipments are now used for fire control of guns and for tracking the trajectory of missiles to mention only two examples.

radar beacon Same as ***radio beacon***

radial-beam tube An ***electron tube*** in which the electron beam from a ***cathode*** is rotated by a magnetic field so as to contact a set of anodes arranged circumferentially around the cathode.

radiation The emission of energy in the form of electromagnetic waves or particles.

radiation counter or **radiation detector** See ***Geiger-Muller tube.***

radio The use of electromagnetic waves to transmit and receive electrical signals over a distance without connecting wires. Thus radio, quite properly, embraces TV. However the term radio is often restricted to the transmission and reception of sound signals. For example receiver manufacturers commonly divide their catalogues into two parts, one describing radio (i.e. sound) receivers and the other TV receivers.

radio beacon or **radar beacon** A radio transmitter from which the signals enable a ship or aircraft to determine its position or direction of movement by use of its own receiving equipment.

radio data services (RDS) or **radio broadcast data system** (US) A system of communication in which data is transmitted in digital code by phase modulation of a subcarrier on the normal VHF FM sound broadcast transmission.

This data is ignored by conventional FM receivers but can be decoded by an RDS receiver to perform a number of functions particularly useful to users of car radios. These can include automatic tuning (to find the strongest signal for the chosen channel), instant switching to receive traffic messages on other channels and automatic switch on to a preselected programme. A visual read-out display can give the name of the received station, the time and date, and even details of music being broadcast. RDS is the sound broadcasting equivalent of ***teletext***.

radio-frequency resistance Same as ***effective resistance*** (2).

radio microphone A ***microphone*** the audio output from which is used to modulate a low-power transmitter, the output of which is picked up by a nearby ***receiver***. A lapel microphone is often used as a radio microphone, the miniature transmitter being carried in a pocket. This arrangement is often used where it would be inconvenient to use a cable to carry the microphone output, e.g. in TV production where an actor has a part requiring great mobility. The use of a boom microphone or a trailing microphone lead would restrict his movements but a radio microphone gives the required freedom.

raised-cosine pulse See ***sine-squared pulse***. Because the square of a quantity is always positive irrespective of the sign of the quantity, a sine-squared pulse is positive for both half-cycles of the sine wave. Each sine wave thus gives rise to two sine-squared pulses and these pulses are positive, i.e. they stand above the zero axis and are thus raised. The identity

$$\sin^2\theta = (1 - \cos 2\theta)/2$$

shows that the sine-squared pulse is of cosine form and that its frequency is double that of the sine wave.

ramp generator Same as ***sawtooth generator***.

random access memory (RAM) A storage device in which access to any item of data is independent of the location of the item in the store. Sometimes called direct access store. The term is used to distinguish such storage from that in which data retrieval is serial as in magnetic tape storage.

The use of a RAM is described under ***digital computer***. An alternative name for the RAM is read/write memory. See also ***dynamic RAM*** and ***static RAM***.

random noise ***Noise*** arising from the movements of a large number of ***electrons*** in a conductor (***thermal noise***) or released from a cathode (***shot noise***). Such noise has no periodicity and, if reproduced by an acoustic transducer, has the sound of a smooth hiss.

raster Display on the screen of a picture tube made up by unmodulated ***scanning lines***.

raster graphic Same as ***bitmap***.

rated frequency deviation The maximum value of the frequency deviation permitted in a frequency-modulated system. For FM broadcasting in Band II the rated frequency deviation is ± 75kHz and for the sound channel in 625-line TV system it is ± 50kHz.

ratio arms See ***Wheatstone bridge***.

ratio detector A detector for frequency- or phase-modulated signals capable of a degree of amplitude limitation.

The circuit, a typical example of which is given in *Figure R.1*, incorporates a transformer with a tuned secondary winding, the centre tap of which is coupled to the primary winding as in the ***Foster-Seeley discriminator***. However the two diodes in the ratio detector are series



Figure R.1 Typical ratio detector circuit

aiding and feed an *RC* circuit with a low-value resistor and a long time constant. This combination imposes heavy damping on the tuned secondary circuit and acts, in fact, as a ***dynamic limiter***, thus giving the detector a measure of protection against amplitude-modulated signals. The voltage across C_3 is independent of the frequency modulation and proportional to input-signal amplitude: it is often used to operate a tuning meter or for AGC purposes. Thus the sum of the voltage across C_1 and C_2 is constant but the individual voltages across C_1 and C_2 vary with the frequency of the input signal in the same way as in a Foster-Seeley discriminator and the audio output can be taken from across either of them. The circuit has a performance similar to that of the Foster-Seeley discriminator but has the additional advantage of a measure of amplitude limitation. It is not surprising, therefore, that this detector is widely used in FM receivers.

ray tracing A computer ***application*** which produces photographic-quality ***bitmap*** images of imaginary objects or scenes. A prerequisite is a mathematical model of the object or scene to be depicted. Details of the lighting and 'camera position' are also required. The application then builds up the image pixel by pixel by tracing a hypothetical ray of light back from each pixel to its source, taking into account the colours and other surface characteristics of the objects off which the light has been reflected. The process can be time-consuming. See also ***visualisation***.

reactance (***X***) That component of the impedance of an alternating-current circuit which is due to its ***inductance*** and/or ***capacitance***. It is the imaginary component of impedance and, for a purely-reactive circuit, the voltage and current are in quadrature. The reactance in ohms of an inductance *L* is given by

$$X_L = \omega L$$

and for a capacitance *C*

$$X_C = \frac{1}{\omega C}$$

where ω is the angular frequency.

In a purely-inductive circuit the current lags the applied voltage by 90° and for purely-capacitive circuit the current leads the voltage by 90°. For a given voltage, therefore, the currents are in antiphase and this is indicated by giving reactance a sign, inductive reactance being conventionally positive and capacitive reactance negative. The net reactance of a circuit containing inductance and capacitance in series is thus ($\omega L - 1/\omega C$).

reactance modulation ***Angle modulation*** brought about by the use of a ***reactance*** which is varied in accordance with the instantaneous amplitude of the modulating signal applied to it. A ***transistor*** can be made to behave as a reactance and is often used to give angle modulation, the modulating signal being applied to the base. The carrier signal is applied to the collector and, by means of an RC circuit, a signal advanced or retarded by 90° with respect to the carrier is applied to the base. The collector current is thus in quadrature with the collector voltage and the collector circuit behaves as a reactance, the magnitude of which depends on the mutual conductance of the transistor. By applying the modulating signal to the base the mutual conductance can be varied, thus varying the reactance and giving angular modulation of the carrier. In a practical reactance modulator linearity of modulation is achieved by using two transistors in push-pull with a system of ***negative feedback***.

reaction ***Positive feedback*** used to increase the sensitivity of any form of amplifying a.m. ***detector***. A typical circuit for applying such feedback is given in *Figure R.2*. The amplified modulated RF signal at the tube anode gives rise to a corresponding current in the circuit L_2C_2, the magnitude of which can be controlled by adjustment of C_2, the reaction capacitor. L_2 is coupled to L_1 and so transfers modulated RF signals to the grid circuit and, if the senses of L_1 and L_2 are correctly chosen, this increases the signal at the tube grid. If C_1 is advanced too far the circuit bursts into oscillation but if reaction is set at just below the oscillation point the gain and selectivity of the detector can be enormously increased.

reactivation Process of reviving the ***thermionic emission*** of the cathode of an ***electron tube*** or cathode ray tube. One method is to apply an



Figure R.2 A grid-leak detector with reaction applied via L_2 and C_2

abnormally-high voltage to the heater for a few minutes, a process known as flashing. An alternative approach is to increase the heater voltage permanently by say 10%. Both methods have the effect of 'boiling off' the original emitting surface of the cathode to expose a new surface.

reactive current That component of the current in an alternating-current circuit which is in quadrature with the applied alternating voltage.

read head In ***computers*** the electromagnetic head which reads the information from a magnetic disk or tape.

reading In ***computers*** and ***data-processing equipment*** the process of obtaining or interpreting information from a store.

read-only memory (ROM) In ***computers*** a ***non-volatile store*** the contents of which cannot be altered by instructions to the computer. Such stores are used to hold the routines needed when the computer is started up and sometimes other frequently-required programs such as those required for character generation. There are three types of semiconductor ROM:

(a) those in which the program is implanted by masking operations during manufacture and cannot be altered by the user. See ***planar process***.

(b) those in which the program can be put in by the user in a once-and-for-all operation. See ***PROM***.

(c) those in which the program can be put in by the user and can be altered as often as required. Erasure sometimes requires an inconvenient operation using ultra-violet light (see ***PROM***) but in more recent designs can be achieved electrically (see ***EEPROM***).

Also known as ***fixed storage*** or ***permanent storage***.

real-time operation The operation of a ***computer*** during the time in which related physical processes occur so that the results can be used to guide the physical processes.

receiver In general a device which reproduces a signal in an intelligible form. Thus a telephone receiver reproduces an audio input signal as a sound wave. A radio receiver reproduces signals conveyed by electromagnetic waves as sound waves and a television receiver as a visual display. In hi-fi parlance a receiver is a unit containing both a ***tuner*** and an ***amplifier***.

reciprocity theorem If an EMF introduced at one point in a linear passive ***network*** gives rise to a current at a second point in the network, then the same EMF transferred to the second point will give the same current at the first point.

recombination (1) In an ionised gas the loss of an ***electron*** by negative ions or the gain of an electron by positive ions, thus causing the gas to return to the neutral or un-ionised state. (2) In a ***semiconductor*** the neutralisation of holes by electrons.

reconditioned-carrier reception (US) Same as ***exalted-carrier reception***.

recording Process of impressing an audio or video signal on a medium in such a way that it can be reproduced whenever required. The impression can take the form of mechanical deformation of the medium as in the lateral sound recording of records, it can be magnetic as in the audio and video recording on magnetic tape or it can be photographic on film. In all examples there is relative movement between the medium and the recording or reproducing head. To achieve such movement the medium may be in the form of a disk which is rotated beneath the heads or in the form of a tape or film which is pulled linearly past the heads.

recovery time Same as ***de-ionisation time***.

rectification The process of converting electrical power in the form of alternating current into unidirectional current by use of a device with ***unilateral conductivity***. A number of types of rectifiers and diodes are used for the purpose and the type chosen depends on the current and voltage required. See ***full-wave rectification***, ***half-wave rectification***.

reduced instruction set computer (RISC) A microprocessor having a limited set of instructions but capable of operating at very high speeds (in contrast with a ***Complex Instruction Set Computer***). RISC processors are best suited to mathematics-intensive operations such as handling ***graphics*** and are used in ***laser printers*** and some graphical workstations. The first commercial microcomputer to use a RISC processor was the Acorn Archimedes introduced in 1987.

redundancy In information transmission that fraction of the gross information content of a message that can be eliminated without loss of essential information.

redundancy check An automatic or programmed check using extra digits inserted in the signal to help detect mistakes in the operation of ***computers***.

reed relay A switch consisting of two magnetic reeds carrying electrical contacts and sealed in a glass tube containing an inert gas. The contacts can be closed by passing a current through a coil surrounding the tube or by movement of a permanent magnet near the tube. The main application of reed relays is in controlling low-level signals, e.g. in telephone exchanges.

reference level The signal amplitude chosen as a standard of reference for the measurement of signal amplitudes. Signal amplitudes are commonly expressed in decibels relative to the reference level which is taken as 0 dB. For example if the reference level for signal power is 1 mW then a power of 1 μW could be expressed as a power level of −30 dB. A reference level commonly used for signal voltage measurements in audio work is 0.775 V (which corresponds to a power of 1 mW in 600 Ω).

reference oscillator In a colour TV receiver an oscillator which is synchronised in frequency and in phase with the ***colour burst*** and is used to operate the synchronous detectors which decode the ***chrominance signal***.

reference volume That volume which gives a reading of zero on a ***volume indicator*** calibrated to read zero on a steady 1-kHz tone with a voltage level of 0.775 V.

reference white level (US) Same as ***white level***.

reflected binary code Same as ***Gray code***.

reflection coefficient (1) Of a surface illuminated by light, the ratio of the reflected to the incident light energy. Freshly-fallen snow is a very good reflector of light, having a reflection coefficient of 0.93, whereas grass has a reflection coefficient of only 0.25.

(2) Of electromagnetic waves at the termination of a ***transmission line***, the complex ratio of the reflected signal current to the incident signal current. If the line is terminated in an ***impedance*** equal to its characteristic impedance, signals transmitted along the line are completely absorbed at

the termination and there is no reflected wave. The reflection coefficient is therefore zero. If, however, the line has a characteristic impedance of Z_o and is terminated in an impedance of Z_r there is a reflected current and the reflection coefficient is given by $(Z_o - Z_r)/(Z_o + Z_r)$.

reflection loss (or **gain**) At the junction of a source of power and a load, and at a given frequency, the ratio of the power delivered to a load which is not matched to the generator, to the power which would be delivered to a perfectly-matched load. Generally , the ratio is expressed in ***decibels*** and is given by the formula $10 \log_{10} (Z_1 + Z_2)^2/4Z_1Z_2$, where Z_1 is the generator impedance and Z_2 the load impedance. See ***mismatch factor***.

reflex amplification System in which an amplifier amplifies the same signal twice, e.g. before and after detection or frequency changing. The system was used in the early days of radio, one ***electron tube*** acting simultaneously as RF and AF amplifier.

reflex baffle Same as ***vented enclosure***.

reflex detector Same as ***infinite-impedance detector***.

reflex klystron A ***klystron*** oscillator in which the electron beam is velocity-modulated by a resonator, is reflected back so as to pass through the resonator again, so setting up oscillations the frequency of which can be controlled by the negative voltage applied to the reflector electrode.

Such klystrons can give a frequency-modulated output by applying the modulating signal to the reflector electrode (known as the repeller). Reflex klystrons are used as output stages in microwave transmitters and as local oscillators in microwave receivers. A simplified cross section of a reflex klystron is given in *Figure R.3* and the graphical symbol in *Figure R.4*.



Figure R.3 Simplified cross section of a reflex klystron



Figure R.4 Graphical symbol for a reflex klystron with indirectly-heated cathode, focusing electrode, grid, repeller and tunable cavity resonator loop-coupled to coaxial line output

refraction The deflection of the path of a beam of light, radio waves or stream of electrons caused by the change in propagation velocity when the beam crosses the boundary between two different media. A familiar example of refraction is the apparent bending of the straight edge of an object when part of it is immersed in water. Refraction in this example is caused by the difference between the refractive indexes of air and water.

Radio waves suffer refraction in the upper atmosphere as they encounter regions of different electron density and as a result of such refraction waves can return to the earth's surface making long-distance radio propagation possible. Electron beams are deflected when they cross the boundary between two electric fields of different potential and this effect is exploited in ***electron lenses*** and ***electrostatic deflection***.

refreshing In ***dynamic RAMs*** the automatic process of rewriting the information in each ***memory cell*** at regular intervals. The fundamental storage element in each cell is a capacitor which is charged to represent 1 and discharged to represent 0. The charge leaks away in time through the inevitable resistance but is regularly compared with the charge on a standard cell and is brought up to equal it if necessary.

regeneration (1) Same as ***positive feedback***. (2) Of ***pulses*** the process of restoring them to their original amplitude, shape and timing.

register In a ***central processor*** a temporary ***store*** usually with a capacity of one word length. Processors contain a number of registers for various purposes, e.g. arithmetical functions, indexing and memory addressing.

regulation Of a power supply the variation of output voltage with variation of the current drawn from it. Regulation may also be expressed as the variation of output voltage as a result of changes in alternating voltage input or as a result of changes in temperature.

Regulation can be improved by including in series with the supply a resistance the value of which is adjusted automatically so as to give a constant output voltage in spite of variations in the current drawn from the supply or of input voltage. Many series-regulated supplies of this type exist, the series resistance taking the form of a transistor which is controlled, sometimes via a DC amplifier, by a sample of the output voltage of the unit.

Alternatively the supply may include a fixed series resistance, voltage control being achieved by an ***active device*** connected in parallel with the output. The current drawn by this shunt element varies automatically in such a manner that the voltage across the load circuit remains constant. Again the shunt element, normally a transistor, is fed with a sample of the output voltage.

Reinartz oscillator An oscillator in which the frequency-determining *LC* circuit is connected to the input of an ***active device***, ***positive feedback*** being



Figure R.5 A Reinartz oscillator

obtained via a coil connected in the output circuit of the device and coupled to the *LC* circuit. A typical circuit diagram using an npn transistor is given in *Figure R.5*.

rejection band Of a ***filter***, the stop band.

rejector circuit A resonant circuit designed to present a high impedance at a particular frequency. It is connected in series with a low-impedance circuit and acts as a notch filter which attenuates signals at or near the chosen frequency. The commonest form of rejector circuit is a parallel *LC* combination. See ***parallel resonance***.

relational database A ***database*** comprising data objects of various types which relate to each other, that is refer to each other by having common fields or clauses. Objects can be sorted on the basis of these relationships as well as types. Perhaps the best known example is IBM's DB2.

relative level See ***level***, ***reference level***.

relative permeability See ***permeability***.

relative permittivity See ***permittivity***.

relaxation oscillator A waveform generator the action of which is governed by one or more RC circuits, an output being delivered when the capacitors are rapidly discharged, the circuit 'relaxing' whilst the capacitors are recharged. ***Blocking oscillators*** and ***multivibrators*** are examples of relaxation oscillators.

relay In general a device which enables an input power to control a local source of power and in which there is no proportionality between controlling and controlled power. Thus ***thyristors*** and ***thyratrons*** can both be used as relays but probably the most familiar form of relay is the electromagnetic type which takes the form of a mechanical switch operated by the armature of an electromagnet. The switch may be a multi-contact type so enabling many circuits to be controlled simultaneously by energising or de-energising the electromagnet.

reluctance Of a magnetic circuit, the ratio of the magnetomotive force to the resulting magnetic flux density. It is the reciprocal of ***permeance***. Reluctance is analogous to the resistance of an electrical circuit and is directly proportional to the length l of the magnetic circuit and inversely proportional to the cross-sectional area A. In fact the reluctance is given by

$$R = \frac{l}{A\mu}$$

where μ, the permeability of the magnetic material, is analogous to the conductivity of an electrical circuit.

remanence The flux density which remains in a magnetic material which has been brought to ***saturation***, when the magnetising field is removed. See *Figure R.6*.

remote control Means of controlling equipment from a distance. The link between the remote-control unit and the equipment may be a cable, an ultrasonic wave or an electromagnetic wave. Many TV receivers have facilities for changing channel, adjustment of brightness, contrast, saturation and volume by remote control using an infra-red beam.

remote cut-off tube (US) Same as ***variable-mu electron tube***.

repeater Equipment installed at intervals on a long communications circuit



Figure R.6 A *B-H* loop illustrating remanence

to amplify and/or reshape signals to offset the effects of attenuation and distortion occurring on the circuit.

repeller See ***reflex klystron.***

replay head or **reproducing head** Device for converting a sound or vision track recorded on disk, tape or film into a corresponding electrical signal.

repository In computing a specialised ***database,*** together with supporting ***applications,*** containing definitions and descriptions of the various data resources and processes in use in an organisation. Such data describing data is called *meta-data.* A repository handles not only definitions of data items, but also of the relationships between data items. Repositories evolved from *data dictionaries* and differ from them principally in their broader application; for example, they can also store diagrams of data systems and of business organisations and business processes.

Repositories are used in data administration to provide a consistent and authoritative source of definitions and to enforce standards on data types. They are widely used in software development for integrating the output of applications such as ***computer-aided software engineering*** tools. Increasingly they are used in business administration for such processes as business modelling and business process re-engineering. The value of a repository for such purposes lies in its comprehensive internal cross referencing, which causes any update made to one member to be reflected instantly in all other members which refer to it. Moreover, tools are usually provided which show immediately which other members would be affected by a change to one member, a process called *impact analysis.*

reservoir capacitor ***Capacitor*** connected in parallel with the output of a rectifier. When the rectifier conducts, the reservoir capacitor (*Figure R.7*) is charged to the peak value of the alternating input voltage to the rectifier and when the input voltage falls below the peak value, the reservoir capacitor supplies the load. In so doing the capacitor voltage falls but it is restored to the peak value the next time the rectifier conducts.

residual magnetism Magnetism which persists after the magnetising force has been removed. Residual magnetism varies enormously depending on the magnetic material. In soft iron, for example, residual magnetism is negligible whereas in steel it is so high that a single application of a magnetising field can give permanent magnetism.



Figure R.7 A half-wave rectifying circuit with reservoir capacitor C_1 and smoothing capacitor C_2

resistance That property of a circuit which enables it to dissipate electricity as heat. It is the real component of ***impedance***. For a purely-resistive circuit the voltage and current are in phase and the resistance is given by the ratio of voltage to current. The unit is the ohm; symbol Ω.

resistance-capacitance coupling In general any coupling between circuits by means of a combination of ***resistance*** and ***capacitance***. The term is frequently applied to coupling between active devices, the resistance being the load of the first device. The capacitance couples the output of the first device to the input of the second as shown in *Figure R.8*.



Figure R.8 Resistance-capacitance coupling between cascaded transistor stages

resistance-capacitance filter A filter circuit composed only of ***resistance*** and ***capacitance***. Simple low-pass filters composed of series resistance and shunt capacitance are often used for smoothing the output of a rectifier. Another example of an *RC* filter is provided by the ***parallel-T network*** of *Figure P.5* which is a ***notch filter***.

resistance-capacitance oscillator An oscillator the frequency of which is determined by a network of ***resistance*** and ***capacitance***. One example is the ***phase-shift oscillator*** of *Figure P.15*; another is the ***Wien-bridge oscillator***.

resistivity Same as ***specific resistance***.

resistor Component used in a circuit primarily because of its electrical resistance. There are many different types of resistor. Low-power resistors consist of carbon compounds imbedded in an insulating medium (the resistance value being indicated by a ***colour code***) or may be thick or thin metal films on an insulating base. For high-power dissipation resistors are usually wire wound. The graphical symbol for a resistor is shown in *Figure R.9*.



Figure R.9 Graphical symbol for a fixed resistor

resistor-transistor logic (RTL) A system in which use is made of logic elements comprising ***resistors*** and ***transistors***.

resolution See ***definition***.

resonance The condition in which an oscillating or vibrating system responds with maximum amplitude to an applied force. In an *LC* circuit resonance occurs at the frequency for which the inductive reactance is equal to the capacitive reactance. Thus

$$L\omega = \frac{1}{\omega C}$$

giving

$$\omega = \frac{1}{\sqrt{(LC)}}$$

Thus the resonance frequency is given by

$$f = \frac{1}{2\pi\sqrt{(LC)}}$$

resonant cavity Same as ***cavity resonator***.

resonant circuit A circuit containing inductance and capacitance and which is therefore capable of resonance.

response curve See ***frequency response***.

response time The time taken by a system to respond to an input.

results In computing, the output, usually in text form, generated by data processing operations, especially those involving a mainframe computer.

retentivity Same as ***remanence***.

retrace Same as ***flyback***.

retrieval In ***computers*** and ***data-processing equipment*** the process of selecting and extracting data records from a ***file***.

return current (or **voltage**) In a ***transmission line*** the current (or voltage) wave which is set up at any impedance discontinuity and travels back to the source. The return wave combines with the forward wave to form standing or stationary waves along the transmission line.

return-current coefficient Same as ***reflection coefficient*** (2).

return loss The value of the reflection coefficient expressed in ***decibels*** or ***nepers***.

reverberation time Of a room, hall or studio, the time taken for the intensity of a sound to fall by 60 dB. It is an important parameter because if speech is to be clear in a small room the reverberation time should be about 0.3 s over the audible spectrum. Similarly good acoustics in an orchestral hall require a reverberation time of about 2 s and independent of frequency.

reverse automatic gain control An AGC system in which the gain of ***active devices*** is reduced by use of reverse control bias. This system was extensively used with ***electron tubes*** which were specially designed for the purpose, having variable-mu characteristics which enabled the tubes to accept large-amplitude signals when biased back without introducing serious distortion. ***Transistors*** do not have such characteristics and give distortion when handling large signals in the biased-back condition. ***Forward AGC*** is better suited to transistors.

reverse-blocking thyristor A ***thyristor*** which cannot be switched to the on-state when the anode is negative with respect to the cathode. The graphical symbol for the diode type is given in *Figure R.10* and definitions of the triode types are given under ***n-gate thyristor*** and ***p-gate thyristor***.



Figure R.10 Graphical symbol for a reverse-blocking diode thyristor

reverse-breakdown voltage Of a pn junction or a ***thyristor***, that value of reverse voltage at which any increase in the voltage causes the dynamic resistance of the device to change from a high to a low value. In a pn junction this effect can result from ***avalanche*** or ***Zener breakdown***.

reverse compatibility Of a colour TV system that property which permits a colour television receiver to reproduce a normal black-and-white television signal as a normal black-and-white picture.

reverse-conducting thyristor A ***thyristor*** which is inherently conductive when the anode is negative with respect to the ***cathode***. Diode and triode types exist and the triode may have an n-gate or a p-gate as indicated in the graphical symbols of *Figure R.11*.



Figure R.11 Graphical symbol for reverse-conducting thyristors (a) diode, (b) triode n-gate and (c) triode p-gate

reverse recovery time Of a pn ***junction*** or a ***reverse-blocking thyristor*** the time taken for the reverse current or voltage to reach a specified value after the device has been instantaneously switched from a steady forward current by a reverse bias.

RGB colour model See ***colour model***.

rheostat Old term for a ***variable resistor***.

rhumbatron Same as ***cavity resonator***.

ribbon cable A cable composed of insulated conductors laid side by side and moulded together to form a flat structure in which the conductors have a precise spacing (typically 0.05 in) to facilitate use of the cable with ***insulation-displacement connectors***.

ribbon loudspeaker ***Loudspeaker*** in which the input signal is applied to the ends of a thin metal ribbon which is suspended in a strong magnetic field and acts as diaphragm, the acoustic output being increased by use of a horn. Such loudspeakers are used to radiate at frequencies above approximately 3 kHz.

ribbon microphone ***Microphone*** in which the electrical output is developed between the ends of a thin corrugated metal ribbon which is suspended under light tension in a strong magnetic field and acts as diaphragm. If both faces of the ribbon are exposed to the incident sound wave the microphone acts as a pressure-gradient type but if one face is screened from the sound wave then the microphone behaves as a pressure type. Ribbon microphones are widely used in radio, television and recording. See ***pressure microphone***, ***pressure-gradient microphone***.

rifle microphone Same as ***line microphone***.

ring counter A number of *bistable circuits* connected in a closed loop and so arranged that only one can be in a particular state at any given time. On receipt of each input signal this particular state is passed on to the next bistable circuit in the ring. Thus if there are *n* bistable circuits, the chosen state makes one complete circuit of the loop for every *n* input signals and each bistable circuit gives one output signal for every *n* input signals.

ringing At the output of an electronic circuit the generation of a damped oscillation following any sudden change in input signal. In a TV picture display ringing in the video amplifier gives rise to regularly-spaced vertical stripes to the right of each vertical line in the picture.

ring modulator A ***balanced modulator*** consisting essentially of four diodes connected in a ring or bridge arrangement and two centre-tapped transformers. As shown in *Figure R.12* the carrier input is applied between the centre taps on the input and output transformers and, in the absence of a modulating signal, the circuit between the transformers is completed by diodes D_1 and D_2 or alternatively diodes D_3 and D_4 depending on the polarity of the carrier. The carrier signal flows in opposite directions in the tapped transformer windings and, provided the circuit is accurately balanced, there is no carrier-frequency output.



Figure R.12 Circuit diagram of a ring modulator

A ***modulating signal*** is, however, transmitted through the circuit in an upright form during one half-cycle of carrier (when D_1 and D_2 conduct) and in an inverted form on the alternate half-cycles (when D_3 and D_4 conduct). A sinusoidal modulating signal thus emerges in the form shown in *Figure R.13*; this represents suppressed-carrier amplitude modulation. Because the carrier input acts as a switching signal its amplitude must be greater than that of the modulating signal. See ***suppressed-carrier modulation***.

ring seal tube Same as ***disk-seal tube***.



Figure R.13 Waveform of a suppressed-carrier amplitude-modulated signal for a sinusoidal modulating signal

ripple The alternating component in the output from a rectifier. The ripple frequency is equal to that of the alternating input to the rectifier if this is a half-wave type but is double the input frequency for a full-wave rectifier.

ripple filter A ***low-pass filter*** used to attenuate the ripple component in the output from a rectifier.

rise time A measure of the steepness of the leading edge of a ***pulse***. More specifically it is the time taken for the instantaneous amplitude to change from 10% to 90% of the peak value as shown in *Figure R.14*.



Figure R.14 Rise time of a pulse

The ability of a circuit to reproduce abrupt changes in voltage or current as required in pulses is determined by the high-frequency response of the circuit and the following simple relationship exists between rise time and upper frequency limit f_{max}:

$$\text{rise time} = \frac{1}{2f_{max}}$$

Thus to reproduce a pulse with a 0.1-μs rise time an amplifier requires an upper frequency limit of at least 5 MHz.

In a simple *RC* or *RL* circuit any increases in voltage or current are exponential in form and, for such a change, the rise time is simply related to the ***time constant*** by the approximate relationship:

rise time = 2.2 × time constant.

robot In general any machine which performs physical tasks automatically which would otherwise have been undertaken by a human operative. Robots are used widely in manufacturing industry for repetitive routine tasks such as spray painting components on a production line. They are also used in the nuclear industries and in space exploration for tasks in hazardous environments. Robots are usually remotely controlled by a computer, but some robots have built-in computers giving them limited local intelligence.

roll off Of a system or equipment the shape of the ***frequency response*** curve immediately outside the ***passband***. For example equipment may be said to have a 12dB-per-octave roll off at the high-frequency end of the passband. High-quality audio equipment sometimes provides a choice of roll off rates, e.g. sharp or gradual at both ends of the spectrum. The shape of the roll off of an amplifier is important because it has a bearing on the degree of ***negative feedback*** that can be applied without instability.

root directory The top-level ***directory*** on a ***floppy disk*** or ***hard disk*** or other storage medium. It is created when the disk is ***formatted*** and must be accessed before any read or write operation relating to that storage device is possible.

Round-Travis discriminator A circuit for the detection of phase- or frequency-modulated signals containing two *LC* circuits of which the resonance frequencies are symmetrically disposed about the centre frequency and which feed diode detectors the outputs of which are



Figure R.15 A Round-Travis discriminator

connected in series opposition. The AF output is the net output of the diodes as shown in the circuit diagram of *Figure R.15*. The circuit is not in common use because others, notably the ***ratio detector***, are easier to align and provide a measure of amplitude limitation.

routine A set of instructions implementing one operation in a ***computer program***. The same routine may be used at many points in the program.

RS bistable A ***bistable circuit*** with an S (set) and R (reset) inputs. See *Figure R.16*. When the S input is at its 1-state, the output takes up its 1-state but when the S input is at its 0-state it has no effect on the output. When the R input is at its 1-state, the output takes up its 0-state but when the R input is at its 0-state it has no effect on the output. A disadvantage of the RS bistable is that if 1-state signals are applied simultaneously to the two inputs the effect on the output cannot be predicted. Bistables of this type are not used in applications where simultaneous inputs are possible. The ambiguity can be eliminated by use of a ***JK bistable***.



Figure R.16 Logic symbol for an RS bistable

RS 232, etc An Electronics Industries Association standard for the hardware and protocols of serial data transmission.

rumble In disk reproduction an unwanted low-frequency component usually of mechanical origin. High-quality audio equipment often includes means of attenuating such components, e.g. a bass cut facility.

S

saddle coils Coils for magnetic deflection, usually of rectangular form and shaped so as to fit the neck of a ***cathode ray tube***.

safe operating area An area on the collector voltage-collector current characteristics of a power transistor within which the ***operating point*** should be located to avoid any possibility of overstressing the device. For safe operation of the ***transistor***, the collector current and the collector voltage must not exceed certain values. Moreover the collector dissipation must be kept below a certain limit to avoid overheating. A fourth limit is set by the need to avoid second breakdown (caused by the emitter current concentrating in a particular small area of the junction). To avoid all these limits the values of I_c and V_c must be kept within a safe operating area such as that shown hatched in *Figure S.1*.



Figure S.1 Safe operating area of a transistor



Figure S.2 Sag in the reproduction of a square wave

sag Form of ***distortion*** of a pulse signal in which the instantaneous amplitude falls during the period of the pulse. The extent of the fall is usually quoted as a percentage of the maximum amplitude. *Figure S.2* illustrates 10% sag. An inadequate low-frequency response is the most likely cause of sag.

sample and hold circuit A ***sampling*** circuit in which the instantaneous values of a sampled signal are held for a time by storing them in a capacitor. Such circuits are extensively used in ***analogue-to-digital converters***.

sampling The process of obtaining a sequence of instantaneous values of an ***analogue signal*** at regular or irregular intervals. If the sampled signal is to represent the original at all closely, the sampling frequency must be at least twice that of the highest-frequency component in the original signal.

sanatron A circuit using two ***pentodes*** for producing pulses with a duration linearly related to the amplitude of a control voltage.

saturable reactor An ***inductor*** of which the magnetic core is operated in the region of ***saturation***. If the core material is brought near to saturation by DC magnetisation, a superimposed AC can bring about large changes in inductance and hence reactance. Such devices are used in ***magnetic amplifiers***.

saturation (1) In general, a condition in which further increase in input signal to a device gives no increase in output. Thus a magnetically-saturated material gives no increase in flux for an increase in magnetising force and a saturated transistor gives no increase in collector current for an increase in input signal.

(2) In colour perception the degree to which the light energy is confined to a narrow frequency band. It is thus the converse of the extent to which the colour is diluted with white light. The difference between pink and red is one of saturation.

save In data processing to store a ***file*** in a storage medium such as a ***floppy*** or ***hard disk***.

sawtooth A periodic signal in which each cycle consists of a linear change followed by a rapid return to the value at the beginning of the linear change. The form of the ideal sawtooth is illustrated in *Figure S.3*. A feature of it is that it is composed entirely of odd-order harmonics. Such signals are used extensively for feeding the deflecting systems in oscilloscopes, picture tubes and camera tubes, and also in the conversion between analogue and digital signals. The linear rise is known as the working stroke and the rapid collapse as the ***flyback*** or retrace.



Figure S.3 A sawtooth or ramp waveform (idealised)

In most generators a sawtooth voltage is developed across a capacitor by passing a constant current through it, flyback being achieved by discharging the capacitor. Such circuits may be free-running, in which case they are usually synchronised by external signals or they may be driven types, in which case external ***triggering*** signals are essential to drive them.

scale factor In ***computers*** the factor by which quantities must be multiplied to bring them within the range acceptable to the computer.

scale of ten A counting scale containing ten digits. This is the decimal scale normally used in counting. The digits in a decimal number are multiples of the power of ten. As an example the number 4062 is, if written out in full:

$$4 \times 10^3 + 0 \times 10^2 + 6 \times 10^1 + 2 \times 10^0$$

scale of two Same as ***binary scale***.

scanner (1) The rotating or oscillating directional ***antenna*** used in ***radar*** systems. (2) A computer-controlled radio receiver used in communications systems that monitors each of a range of channels in rotation. (3) In computing, a ***peripheral*** which converts the contents of a paper document, such as a photograph or a printed page, to a ***bitmap***. It contains an array of photo-sensitive cells, usually charge-coupled devices, which pass over the suitably illuminated document at a controlled speed. The output from each cell is sampled at regular intervals and assembled into the bitmap. The finished bitmap is ***uploaded*** to the ***host*** computer for viewing or editing. Text in the document may be converted to ***ASCII*** code using an ***OCR*** application.

scanning In TV the process of analysing or synthesising the light content of the elements constituting the scene. In practice this is achieved by an electron beam which moves over the target of the camera tube or the screen of the picture tube in a series of lines which embrace every element of the image.

scanning lines In TV one of the horizontal rows of elements of which the image is assumed to be composed and which is explored by the scanning beam during transmission and reception. The elements in each line are scanned in order from left to right with a rapid return to the left to start the next line below, and a rapid return to the top of the image when the bottom line has been completed. The motion of the scanning beam is, in fact, similar to that of the eye in reading. The definition of a television system is primarily determined by the number of scanning lines chosen and most modern systems use 525 or 625. Not all the lines are reproduced on receivers because a number are lost during the vertical flyback.

scanning spot In television the small area of the ***target*** of a ***camera tube*** or ***screen*** of a ***picture tube*** which is affected by the scanning beam at any instant during the scanning process.

schema The model defining the structure and organisation of a ***database***.

Schmitt trigger A ***bistable*** device of which the input has two threshold values. The device takes up one of its two stable states when the input signal reaches a threshold value V_1 and remains in this state when the input returns through V_1 and until it reaches a second threshold V_2, at which the device switches to its alternative stable state. The input must now return through V_2 and reach V_1 again before the next change of state occurs.



Figure S.4 Logic symbol for a Schmitt trigger

The switching operations clearly lag behind the changes in input signal and the device is sometimes described as having ***hysteresis***. This is indicated in the block symbol for the Schmitt trigger shown in *Figure S.4*.

Schottky barrier diode Same as ***Schottky diode***.

Schottky diode A diode using a metal/semiconductor junction. The semiconductor is usually highly-doped silicon or gallium arsenide with a thin n-type ***epitaxial*** layer. Conduction is entirely by ***majority carriers*** and there are no ***minority carriers*** to give reverse recovery effects. The diode thus makes an efficient mixer and detector at microwave frequencies.

Schottky diodes start conduction at a low forward voltage (between 0.1 and 0.2 V compared with 0.6 V for a silicon pn diode).

Schottky effect The increase in current from a ***cathode*** beyond the saturation value resulting from an increase in anode voltage. The increase is caused by the lowering of the ***work function*** of the cathode by the increased electric field at its surface.

Schottky noise Same as ***shot noise***.

scintillation (1) Small random variations of the amplitude, phase or angle of arrival of a received radio wave caused by its passage through the ionosphere. The term is analogous to the twinkling of light from a star. (2) In an amplitude-modulated transmitter unwanted frequency modulation of the carrier. Such modulation can occur when the amplitude modulation depth is great. (3) The flash of light produced in a layer of material, notably a ***phosphor***, when a charged particle strikes it at high speed.

scintillation counter Alpha particle and gamma ray counter in which the incident radiation strikes a ***phosphor*** to produce light which is detected by a ***photocell***, the output of which is amplified to operate the counter circuit.

Scophony system System of ***projection television*** in which a beam of light is modulated by a ***Kerr cell*** and then projected on to a screen after reflection at a rotating system of mirrors (known as a mirror screw) which gives the required scanning pattern.

scrambler A device which takes an incoming signal and applies an encryption algorithm to it. The resulting scrambled signal is transmitted to the receiver which contains an *unscrambler*. This applies the reverse of the encrypting algorithm so as to reconstitute the original signal. Scramblers are used to provide security in communications systems to which the public have access.

scratch filter ***Filter*** giving attenuation of the higher audio frequencies and used with an AF amplifier to reduce surface noise in the reproduction of early or worn records. The noise of the reproducing stylus in the groove is negligible in modern discs but the abrasive powder formerly included in the material of records intended for reproduction by steel needles causes a hiss or scratching noise which can be reduced by use of a ***low-pass filter***. If the cut-off frequency and/or the rate of fall of response are controllable it is usually possible to find a compromise setting of the controls where the hiss is not objectionable and the musical fidelity not unduly impaired.

scratch pad In ***computers*** and ***data-processing equipment*** a storage area reserved for intermediate results.

screen Of a ***cathode ray tube*** the layer of ***phosphor*** which fluoresces under the impact of the ***electron beam*** so as to form the required visible display.

screening The use of materials to reduce the penetration of a field into a particular region.



Figure S.5 (a) The capacitance between two parts A and B of a circuit and (b) interposing an earthed screen between A and B eliminates the direct capacitance between them

The principle of electric screening can be understood from *Figure S.5*(a) in which A and B represent two parts of a device or circuit. A is a generator of impedance Z_1 and B has an impedance of Z_2 to chassis. There is a capacitance C_1 between A and B determined primarily by the dimensions of A and B and their distance apart and this can convey energy from A to B. As C_1 is a small capacitance its reactance is likely to be large compared with Z_1 and Z_2, but the energy transfer increases with increase in frequency and at RF may be sufficient to cause instability if B is an early stage in an amplifier.

To prevent such unwanted feedback an earthed screen may be interposed between A and B as shown in *Figure S.5*(b). This eliminates C_1 and replaces it by two capacitances C_2 and C_3 which cannot give ***feedback*** provided the screen is of low-resistance material and is connected to chassis via a very low impedance. The screen need not be solid; a mesh is equally effective.

This principle was used in the ***screen-grid electron tube***. The screen grid is located between anode and control grid to prevent feedback from anode to control grid. The screen must not interrupt the electron stream from cathode to anode so it is made of mesh construction and biased positively with respect to the cathode. To provide the low-impedance connection to earth the screen is decoupled by a low-reactance capacitor.

Unwanted coupling can also occur via ***magnetic fields*** which can induce EMFs in conductors so leading to instability. At low frequencies this can be avoided by totally enclosing the source of magnetic field in a box of high-permeability material. The stray field will then be confined to the low-reluctance path offered by the screening box. At low frequencies, such as mains and audio frequencies, magnetic screening is not often required because inductors and transformers which are likely to generate magnetic fields usually have magnetic cores which, with proper design, confine the field to the component itself so minimising stray field.

However, at higher frequencies, notably radio frequencies, unwanted coupling via magnetic fields is easily possible and the RF and IF inductors of radio receivers require screening to minimise it. The principle used here is to mount the inductors in a conducting can so that eddy currents are induced on the inner surface of the can by the magnetic field due to the current in the inductor. These currents also set up a magnetic field which opposes that due to the inductors so that, outside the can, the two fields cancel thus eliminating the possibility of instability via coupling to external components. Inside the can the two fields do not cancel. In fact the can behaves as a short-circuited turn on a transformer which reduces the effective inductance and Q factor of the inductor. To minimise this effect the can must not be placed too near the inductor: nevertheless the effect of the screening can must be allowed for in designing the inductors. There is no need, of course, for a can, acting as a magnetic screen, to be earthed but it is usual to do this so that the can acts as an electric screen also. The can should be of low-resistance material such as copper or aluminium and the thickness should be greater than the depth of penetration for the frequency used. In general the thickness required to give adequate mechanical strength is more than sufficient.

screen AC resistance See ***electrode AC resistance***.

screen grid An ***electrode*** situated between the control grid and the anode of an ***electron tube*** with the object of minimising the anode-control-grid capacitance. It is effectively earthed, i.e. connected to the cathode at the operating frequency so as to screen the control grid from the anode and prevent ***feedback*** from output to input circuit. In practical circuits the screen grid is maintained at a positive voltage with respect to the cathode to ensure a useful value of anode current. It is decoupled at signal frequencies to the cathode by a low-reactance capacitor.

screen-grid electron tube A tube containing a ***cathode***, ***control grid***, ***screen grid*** and ***anode***. The tube was developed from the triode which proved unsuitable for use as an RF amplifier because of ***feedback*** from output to input via the internal anode-control-grid capacitance. A screen grid was therefore inserted between these electrodes to minimise this capacitance. The screen-grid tube so developed permitted stable RF amplification but unfortunately introduced a ***tetrode kink*** in the I_a-V_a characteristic which prevented large undistorted anode-voltage swings. The introduction of the suppressor grid (to make the pentode) eliminated the tetrode kink.

Tetrodes can be made suitable for large output signals by critical screen-grid-anode spacing (see ***beam tetrode***). The graphical symbol for a tetrode is given in *Figure S.6*.

screen mode Same as ***video mode***.

scrolling Effect used in ***computer applications*** and in TV in which text or graphics appear to move smoothly past the screen. In word processing,



Figure S.6 Graphical symbol for an indirectly heated tetrode

desktop publishing and graphics, user-controlled scrolling is one means of navigating through the ***document*** until the required portion is visible on the screen. In a ***graphical user interface*** scrolling is usually controlled by scroll bars along the right and bottom edges of the window; their positions also give some indication of the location of the portion of the document currently visible.

search coil A small coil used for the measurement of magnetic fields. The coil is inserted in the field so as to give maximum ***coupling*** and is then rapidly withdrawn or the field is abruptly reduced to zero. From the EMF induced in the coil it is possible to calculate the ***flux density***.

SECAM colour television system (Système En Couleurs À Mémoire). A compatible colour TV system originated in France in which the ***luminance signal*** is transmitted by amplitude modulation of the vision carrier and colour information is transmitted by frequency modulation of the vision subcarrier, the two chrominance signals being sent separately on alternate lines. The total bandwidth is the same as that of a black-and-white system using the same line standards. A line-period delay line and an electronic switch are needed at the receiver to ensure use of both chrominance signals on each displayed line. The system is used in France and a number of other countries. See ***NTSC*** and ***PAL colour television systems***.

secondary cell A voltaic cell the chemical state of which, after discharge, can be restored to its original state by passing direct current through the cell in the opposite direction to the discharge current. The cell effectively stores electricity in chemical form and can be recharged as often as necessary without permanent effect on the cell. See ***primary cell***.

secondary electron An ***electron*** liberated from a surface as a result of bombardment by fast-moving primary electrons or ***ions***.

secondary emission ratio The average number of secondary ***electrons*** released from a surface for each primary electron striking it. Depending on the nature and treatment of the surface, secondary emission ratios up to 10 can be achieved. See ***dynode***, ***electron multiplier***.

second channel In ***superheterodyne receivers*** unwanted signals at the ***image frequency*** which are accepted together with the wanted signal by the IF amplifier. Such signals can cause interference with the wanted signals in the form of unwanted modulation or whistles. The signal-frequency circuits of receivers are therefore designed to introduce attenuation at the image frequency so as to minimise second-channel interference.

second detector In ***superheterodyne receivers*** the detector which demodulates the IF signal. The term arose in the early days of radio when the mixer was known as the first detector.

second generation computer See ***digital computer***.

section (of a filter) See ***ladder network***.

sector The smallest area on a ***floppy disk*** or ***hard disk*** that can be accessed. Whole sectors are copied into a buffer for reading and copied from a buffer for writing, even if only one byte requires changing. The size of sectors varies depending on the type and format of the disk, 1 Kilobyte being a typical size.

Seebeck effect Same as ***thermo-electric effect.***

Seeley-Foster discriminator Same as ***Foster-Seeley discriminator.***

see-saw phase splitter A circuit in which a push-pull output is obtained from the outputs of two active devices from an input applied to one of them, the input to the other being obtained from a tapping on a resistor connected between the two output terminals. The circuit is shown in essence in *Figure S.7* using bipolar transistors.



Figure S.7 Basic features of the see-saw phase-splitter circuit

If R_1 is equal to R_2 then the outputs of TR1 and TR2 cannot be of equal amplitude otherwise there would be no input for TR2; in such circumstances the output of TR2 automatically adjusts itself to less than that of TR1 so that the input for TR2 is generated at the junction of R_1 and R_2. However, if the ratio of R_1 to R_2 is made equal to A:(A + 1), where A is the voltage gain of TR1 (and TR2) then equal-amplitude signals can be obtained from the two collectors.

selectance A measure of the fall in response of a resonant circuit as frequency departs from the resonance value. See selectivity.

selectivity That property of a ***tuned circuit***, a tuned amplifier or a receiver which enables it to accept a wanted signal on a particular frequency and to reject signals on nearby frequencies. The phenomenon of ***resonance*** implies selectivity and the selectivity of an *LC* circuit is measured by its ***Q factor***. The selectivity of an amplifier or receiver depends primarily on the number of tuned circuits employed and on their *Q* factors. The superior selectivity of the superheterodyne receiver compared with that of the tuned radio-frequency receiver is due to the fact that a large number of tuned circuits can be used without making tuning difficult.



Figure S.8 The self-capacitance of an inductor shown in dashed lines

self-capacitance The capacitance between parts of the same conductor, resistor or inductor. It is usually represented as being in parallel with the component as shown in *Figure S.8* in which the self-capacitance of an inductor is shown in dashed lines. The self-capacitance of an inductor sets an upper limit on the frequency to which the inductor can be tuned.

self-demagnetisation In a material in which the magnetic circuit is not closed, the reduction of the magnetic field strength by the poles produced at the ends of the magnetic circuit. The self-induced field due to the poles opposes the magnetising field and reduces the magnetisation it is possible to induce in the material.

self-inductance See ***inductance***.

self-oscillating mixer In a ***superheterodyne receiver*** an ***active device*** used as a mixer which is designed to oscillate also thus obviating the need for a separate oscillator.

A typical circuit diagram of a transistor self-oscillating mixer used in a medium-wave receiver is given in *Figure S.9*. The ***coupling*** between L_1, L_2 and L_3 causes the transistor to oscillate. The RF input is applied to the base so that it is, in effect, connected in series with the oscillation injected into the emitter circuit. Mixing occurs by virtue of the non-linearity of the transistor characteristic and the mean emitter current must be chosen with care, being low enough to give adequate non-linearity yet high enough to sustain oscillation over the whole of the ***waveband***.



Figure S.9 Simplified circuit diagram of a self-oscillating mixer

self-oscillation The production of sustained oscillations in an electronic circuit caused by ***positive feedback***.

self-quenching oscillator Same as ***squegging oscillator***.

semiconductor Generally any material with an electrical conductivity between that of an ***insulator*** and a ***conductor***. Specifically a crystalline material the conductivity of which increases on addition of certain impurities, the conductivity increasing with rising temperature over a particular temperature range as shown in *Figure S.10*. The semiconductor materials most used in the manufacture of junction diodes and transistors are germanium and silicon but others such as gallium arsenide are used also notably in light-emitting diodes. The term is also loosely used to mean semiconductor devices such as diodes and transistors. See ***extrinsic semiconductor***, ***intrinsic semiconductor***, ***n-type semiconductor***, ***p-type semiconductor***.



Figure S.10 Resistance-temperature characteristics for a metallic conductor and a semiconductor

semiconductor diode A two-electrode semiconductor device with unilateral conductivity.

There are two basic types described under ***junction diode*** and ***point-contact diode***.

sensitivity In general of equipment, the smallest input signal which gives a specified output or ***signal-to-noise ratio***. For example, the sensitivity of a radio receiver is the smallest RF input which gives a specified signal-to-noise ratio at the output, the modulation frequency and depth of modulation being specified. As another example the sensitivity of a television camera tube is the quotient of the output current and light input at a specified wavelength. The sensitivity of a measuring instrument is the ratio of the deflection to the input causing it.

sensor A ***transducer*** whose output, usually electrical, is used as the input to measuring or monitoring equipment.

separation In twin-channel stereo the degree to which the signal in one channel is free from interference from the signal in the other channel. More specifically when a signal is applied to one channel, the level of that signal which appears in the other channel, the separation being the difference in the two levels expressed in dB. In stereo pickups it is difficult to design a mechanism which can separate the two components of the stylus movement without mutual interference and it is therefore useful to know what degree of separation is possible.

sequencer In electronic music a machine, often a computer running a suitable ***program***, which plays a series of ***sampled*** sounds in a previously defined order, thus providing a musical part or even a whole performance.

sequential scanning Scanning system in which all the lines composing the image are scanned in succession during each vertical downward sweep of the scanning agent. It is therefore non-interlaced scanning. In all practical TV systems *interlaced scanning* is used because of the economy in bandwidth that it gives.

serial storage (access) Storage in which the data are arranged in sequence in the storage medium so that the access time for a particular item depends on its position. See ***parallel storage***.

serial transmission In data transmission a system in which the elements of a signal are sent in sequence over a single channel. See ***parallel transmission***.

series connection A method of connecting components or circuits so that they share the same current, the voltage dividing between them depending on their impedance. See *Figure S.11*. The equivalent impedance Z_{eq} of a number of impedances Z_1, Z_2, Z_3, etc connected in series is given by

$$Z_{eq} = Z_1 + Z_2 + Z_3 + \text{etc.}$$



Figure S.11 A simple series circuit

series modulation Circuit for ***amplitude modulation*** in which the ***modulator*** and ***modulated-amplifier*** electron tubes are connected in series across the HT supply. The modulated amplifier acts as load for the modulator and the modulation frequency voltage generated across it effects modulation. The circuit (shown simplified in *Figure S.12*) has the advantage of requiring no modulation choke or transformer but a disadvantage is that the filament of the modulator, and the circuit which feeds it, are at high tension.

series-parallel connection Form of connection in which branches formed by series-connected elements are connected in parallel or in which groups


+ HT
class A
modulator
A.F
input
G.B
−
+
R_1
R_2
modulated
R.F. output
C_n
class C
modulated
amplifier
unmodulated
R.F. input
R_1
R_2
− HT
G.B −

Figure S.12 Essential features of the series modulation circuit

formed by parallel-connected elements are connected in series. Two simple examples are given in *Figure S.13*.



Figure S.13 Simple examples of series-parallel connection

series regulator See ***regulation***.

series resonance Resonance in which the applied signal is connected to an inductor and capacitor in series. See *Figure S.14*. Resonance is indicated by



Figure S.14 Series resonant circuit

the impedance of the *LC* circuit which is a minimum at the resonance frequency given by

$$f = \frac{1}{2\pi\sqrt{(LC)}}$$

as for parallel resonance. See ***acceptor circuit***.

series stabilisation See ***regulation, stabilisation***.

service area Of a broadcast transmitter the area in which the field strength exceeds a specified value.

servo A system which provides automatic help with an operation or adjustment. For example, the playback head of a video tape recorder is guided along the magnetically recorded tracks by a servo which automatically corrects any deviation from the track.

set-up (US) Same as ***pedestal***.

seven-segment display A method of displaying the numerals from 0 to 9 by illuminating two or more elements out of seven arranged in the form shown in *Figure S.15*. If all the elements are illuminated the display resembles 8; if elements 1, 2, 7, 5 and 4 are illuminated a 5 is displayed. This form of display using ***light-emitting diodes*** or ***liquid-crystal*** elements is extensively used in electronic equipment, e.g. video cassette recorders, calculators, digital watches.



Figure S.15 Arrangement of elements in seven-segment display

shading signals In TV, components in the output of a camera tube which give rise to undesired shading effects in reproduced images. High-velocity camera tubes generate such signals and, in the early days of TV, these signals were neutralised by adding to the camera output specially-generated waveforms at line and field frequencies (known as tilt and bend waveforms).

shadow-mask picture tube A colour picture tube with three ***electron guns*** (or a single gun firing three beams) in which the screen is composed of dots or stripes of red, green and blue phosphors, a shadow mask near the screen ensuring that each beam always strikes the same colour phosphor. In some tubes the phosphor dots are arranged in groups of three in a triangular pattern known as a triad (see ***delta-array colour tube***) and in others as vertical stripes (see ***precision-in-line colour tube***).

shaft encoder A ***transducer*** for indicating the rotational position of a shaft.

Shannon A unit of information in a binary scale.

shape factor In receiver design a measure of the extent to which the shape of the selectivity curve approximates to the ideal rectangular shape. More specifically it is the ratio of the attenuation band to the pass-band, i.e. the ratio of the bandwidth between the 60-dB attenuation points to that between the 3-dB attenuation points (see *Figure S.16*). The ideal selectivity curve has a shape factor of unity and a communications receiver is likely to have a value between 1 and 1.5, a normal domestic receiver having a value between 2.5 and 4.0.



Figure S.16 Ideal and practical receiver selectivity curves

shaping network A ***network*** designed to modify the ***waveform*** of a ***signal***. The simplest and most common forms of shaping network are ***differentiating*** and ***integrating circuits***.

shareware ***Software*** which may be copied and distributed subject to the conditions stated in a text file which forms part of it. Usually these stipulate that the software must not be modified in any way or incorporated into any other package. The user may freely use the software for a while, but if he wishes to continue using it he is urged to send a payment to the originator.

This payment often results in a more complete or more recent version being sent to the user. See also ***freeware***, ***public domain software***.

sharp cut-off tube An ***electron tube*** in which the I_a-V_g characteristic is straight so that anode current is sharply cut off as negative grid bias is increased. Cf ***variable-mu electron tube***.

shielding (US) Same as ***screening***.

shift register In digital equipment a ***store*** in which an ordered set of characters can be moved to the left or right. In particular a row of bistable elements into which a binary word can be fed by serial input to the first bistable and then proceed to the next and so on, at a speed determined by the clock.

shock excitation In a resonant circuit the generation of ***oscillations*** at its natural frequency by the sudden application of an external signal or the sudden release of energy stored in the system.

For example an *LC* circuit can be shock excited into oscillation by the momentary application of an external EMF. Alternatively, if the capacitor is initially charged, shock-excited oscillation occurs if an inductor is suddenly connected across the capacitor.

short circuit An intentional or accidental connection between two points in a circuit by a conducting path of low resistance. If there is normally a difference in potential at the two points, a short circuit can result in an abnormally-large current flow.

short-circuit impedance Of a two-terminal-pair ***network*** the ***impedance*** measured at one pair of terminals when the other pair is short circuited.

shot noise ***Noise*** arising from random variations in the emission of ***electrons*** from a ***cathode***. The number of electrons liberated from a cathode may be constant when they are measured over appreciable periods but there are momentary surfeits or deficits in the number measured over short periods and their variation with time constitutes shot noise. The magnitude of the shot-noise current I_n is given by

$$I_n^2 = 2eI_o\Delta f$$

where e is the charge on the electron

I_o is the current from the cathode

Δf is the bandwidth over which the noise is measured.

Substituting the value for e gives

$$I_n = 5.45 \times 10^{-4}\sqrt{(I_o\Delta f)}\ \mu\text{A}$$

This is the noise component in the total emission from the cathode, i.e. it would be the value if every emitted electron were collected by say the anode of an ***electron tube***. In practice the anode current is limited by the space charge surrounding the cathode to about two thirds of this value. Thus, as an example, if I_o is 10 mA and Δf is 5.5 MHz the noise current is given by

$$\begin{aligned} I_n &= 0.67 \times 5.45 \times 10^{-4}\sqrt{(10^{-2} \times 5.5 \times 10^6)} \\ &= 0.086\ \mu\text{A} \end{aligned}$$

and, if the anode load of the tube is 2 kΩ the noise voltage generated across it is 171.2 μV.

shunt connection The connection of a circuit element in parallel with another so diverting (shunting) some current from it. The term shunt is thus synonymous with parallel but often it is reserved for applications in which one end of the shunt element is connected to earth as in filter circuits.

shunt feed Same as ***parallel feed.***

shunt regulator See ***regulation.***

sideband A band of frequencies containing the new components introduced by modulation of a carrier wave. The term is also used to denote one particular component within a ***sideband***: strictly such a component should be termed a ***side frequency***. Amplitude modulation and angle modulation of a carrier wave result in the generation of numerous pairs of side frequencies symmetrically disposed about the carrier frequency. These components occupy two frequency bands, one above and the other below the carrier frequency as shown in *Figure S.17*. These are the upper sideband and the lower sideband respectively.



Figure S.17 Spectrum diagram showing the side frequencies constituting the two sidebands

side frequency One of the new components generated by the process of ***modulation***. When a sinusoidal carrier of frequency f_1 is amplitude modulated by a signal of lower frequency f_2, two new components with frequencies $(f_1 + f_2)$ and $(f_1 - f_2)$ are generated. Thus the two side frequencies are situated symmetrically above and below the carrier frequency and are spaced from it by an interval equal to the modulating frequency as shown in *Figure S.18*. This shows the amplitude of the two side-frequency components as equal to one half that of the carrier: this is true for 100% modulation.



Figure S.18 Spectrum diagram illustrating the pair of side frequencies generated by 100% amplitude modulation by a sinusoidal signal

When the modulating signal is complex, as in sound broadcasting, each component in it gives rise to a pair of side frequencies so that two patterns of side frequencies are produced symmetrically disposed about the carrier. The spacing between the adjacent side frequencies is equal to the fundamental frequency of the ***modulating signal***.

Side frequencies are also generated in ***frequency modulation and phase modulation*** but here a sinusoidal modulating signal produces several side-frequency pairs some of which can have an amplitude greater than that of the carrier as shown in *Figure M.10*. The side frequencies are symmetrically disposed about the carrier frequency and have a spacing equal to the modulation frequency. A complex modulating signal thus gives rise to a very large number of side frequencies theoretically extending to an infinite frequency. In practice, however, the amplitude of the outer side frequency components is small compared with that of the others and these extreme components can be filtered out without introducing appreciable distortion. Even so a frequency-modulated signal occupies a considerably greater bandwidth than the comparable amplitude-modulated signal.

signal In electronics an electrical quantity varying with time so as to convey information. In equipment, signals are usually in the form of varying voltages or currents but in the link between a radio transmitter and receiver signals have the form of modulated electromagnetic waves.

signal distance The number of digit positions in which the corresponding digits of two equal-length binary words differ. For example the signal distance between the two words 11100101 and 00100011 is 4.

signal generator Equipment for producing voltages or currents of controllable waveform, amplitude and frequency and used for the testing and alignment of electronic equipment. For receiver testing, signal generators are available giving modulated RF outputs.

signal processing or **signal conditioning** (US) The operations it is necessary to carry out on a ***signal*** to achieve the desired result. Typical operations are amplification, frequency changing, waveform shaping, mixing and gating.

signal-to-noise ratio In general the ratio of the power in the wanted signal to that of the noise which tends to interfere with it or mask it. It is usually expressed in dB. The precise way in which the ***signal*** and the ***noise*** are measured depends on the nature of the signal and the noise. For example RMS measurements are used for sound signals and random noise, peak-to-peak measurements for TV signals and impulsive noise.

Signal-to-noise ratio is a most important parameter of a communications system because system efficiency depends, in the final analysis, on the signal-to-noise ratio obtainable. Systems differ considerably in signal-to-noise ratio. For example amplitude limiting in FM systems permits a better signal-to-noise ratio than AM systems. In systems using ***pulse code modulation*** the ability to regenerate clean pulses from received pulses which are only marginally above the noise level makes possible very good signal-to-noise ratios.

silicon A tetravalent element (atomic number 14) widely used in the manufacture of semiconductor devices. In its pure state it is an insulator but by suitable doping, p-type or n-type conductivity of a value suitable for semiconductor device manufacture can be obtained. At normal temperatures leakage current is negligible in silicon devices. For this reason and also because silicon is more readily obtainable (in the form of its oxide it forms about 25% of the earth's crust) it has virtually displaced ***germanium*** as the basic material used for semiconductor devices.

silicon alloy transistor An ***alloy transistor*** in which the base wafer is of silicon. The usual alloying element was aluminium but the transistors were not very successful primarily because of the difficulties caused by the different coefficients of expansion of silicon and aluminium.

silicon chip Popular name for silicon ***integrated circuit.***

silicon controlled rectifier (SCR) Same as ***thyristor.***

silicon controlled switch Same as ***tetrode thyristor.***

silicon disk A bank of ***random access memory*** configured to simulate a ***floppy*** or ***hard disk*** and used for temporary storage of programs and data.

silicon epitaxial planar transistor A ***transistor*** manufactured by the ***planar process*** and making use of ***epitaxy.***

silicon on sapphire (SOS) An example of a technology in which ***monolithic integrated circuit*** elements are fabricated in silicon on an insulating (sapphire) ***substrate.*** In this way the leakages and parasitic capacitances can be minimised so that the operating speed of a store fabricated in this way using ***field-effect transistors*** can approach that of a bipolar store.

silicon target vidicon A ***vidicon*** in which the ***target*** is principally composed of ***silicon.*** Silicon has high photoconductivity but its low resistance is an embarrassment. It is used in the form of a mosaic of individually-insulated pn diodes (with boron as the impurity) which are reverse-biased in normal use.

simplex operation A method of operation in which communication between two stations can take place only in one direction at a time. To effect two-way communication the direction of the link must be reversed. This can be achieved, in a radio system for example, by simultaneously switching the antennas at both ends from receiver to transmitter or vice versa. The same carrier frequency can be used for both directions. See ***duplex operation.***

simulation In general, representation of one device by another. The second device must have characteristics similar to those of the first and is used in preference to the first because it is more convenient to use or easier to understand. For example an *LCR* network may be used to simulate the impedance of an antenna.

sinad ratio In mobile communications the ratio of the wanted signal, together with any distortion terms and noise to the distortion terms and noise. It is usually expressed in dB thus:

$$\text{sinad ratio} = 20 \log_{10} \frac{s + n + d}{n + d}$$

where s = wanted signal voltage

d = distortion terms voltage

n = noise voltage.

sine-squared pulse A single unidirectional pulse equal to the square of a sine wave and used for testing in TV. Such a pulse has a limited spectrum and the pulse duration can be so chosen that it is well suited for testing TV circuits. It is used in ***k-rating*** determinations. See ***raised cosine pulse.***

singing In a ***transmission system*** unwanted sustained oscillation caused by ***positive feedback***. The term is mainly used in telephony. In electronics the effect is usually termed ***instability***.

singing point Of a system with ***positive feedback*** the point at which the gain of the system is just sufficient to cause sustained oscillation. The term has a more precise meaning in telephony. See *Dictionary of Telecommunications* (Butterworths).

single-ended push-pull A circuit in which a pair of ***active devices*** operating in push-pull are connected in series across the supply, the output being taken from their common point. The essential features of the circuit are illustrated in *Figure S.19*. If the two ***transistors*** are of the same type, as shown in (a), then the input signals applied to their bases must be in push-pull and a phase-splitting stage is necessary. If, however, the transistors are complementary, as shown in (b) they can both be driven by the same input signal and a separate phase-splitting stage is unnecessary.



Figure S.19 Essential features of single-ended push-pull stage using (a) similar transistors and (b) complementary transistors

single in-line memory module (SIMM) An ***integrated circuit*** containing, usually, dynamic RAM. SIMMs are widely used in microcomputers where they make memory upgrades simple. To upgrade from 4 Mbytes to 16 Mbytes, e.g. might require the removal of four 1-Mbyte SIMMs and their replacement by four 4-Mbyte SIMMs.

single-shot circuit (US) Same as ***monostable circuit***.

single-sideband transmission (SSB) A system of ***amplitude modulation*** in which only one ***sideband*** is transmitted, the carrier and other sideband being suppressed. The system has the advantage that it occupies only half the bandwidth of the corresponding double-sideband system. Reception is more difficult, however, because the missing carrier must be reintroduced at the receiver to permit detection.

sink A device which drains energy from a system. For example a heat sink is attached to electronic components with considerable dissipation to remove heat from them.

sinusoidal waveform A waveform in which the variable quantity is a sine or cosine function of time. For example a sinusoidal voltage waveform can be represented by the expression

$v = V_0 \sin \omega t$

where v is the voltage at a time t, V_0 is the amplitude of the signal and ω is the ***angular frequency***.

skiatron Same as ***dark-trace tube***.

skin effect In a ***conductor*** carrying an alternating current a concentration of the current towards the edges of the cross section caused by interaction between the conductor and the electromagnetic field set up by it. The effect becomes more marked as the frequency of the current is raised and causes the effective resistance of the conductor to increase sharply with increase in frequency. At high radio frequencies so little of the current is carried by central areas of the cross section that a tube is as good as a solid conductor of the same diameter. It is common practice, in fact, to use copper tubing for the tuning inductors of radio transmitters. Skin effect can also be minimised by using a conductor consisting of a number of individually-insulated strands such as Litzendraht. See ***penetration***.

skirt Of the amplitude-frequency response curve of a resonant circuit, those parts of it away from the peak where the two halves of the curve diverge.

slant polarisation See ***elliptical polarisation***.

slew rate (1) Of a power supplier a measure of the speed with which the output voltage compensates for changes in the current drawn. It measures the maximum rate of change of voltage across the output terminals. (2) Of a differential amplifier the rate of change of the output voltage when a step signal is applied to the input terminals.

slicing The process of suppressing those parts of a signal waveform which lie outside two amplitude boundaries, allowing only those parts which lie between the boundaries to pass on. The process is illustrated in *Figure S.20*.



Figure S.20 Input and output waveform illustrating slicing

slope Same as ***mutual conductance***.

slope detector A detector for ***phase-*** or ***frequency-modulated signals*** which depends for its operation on the slope of the skirts of the amplitude-frequency response curve of a resonant circuit.

If the difference between the resonance frequency and the centre frequency is suitably chosen the frequency variations are converted to amplitude variations (*Figure S.21*) which can be demodulated by an AM detector. Unfortunately the amplitude-frequency relationship of the skirts is not linear and the slope detector inevitably gives considerable distortion. This can, however, be minimised by using the skirts of two resonant circuits in a push-pull arrangement as in the ***Round-Travis discriminator***.



Figure S.21 Operation of a slope detector

slope resistance Of a non-linear resistance the ratio of a small change in applied voltage to the resulting change in current. It is measured by the reciprocal of the slope of the current-voltage characteristic at the operating point and in general depends on the position of that point. For example in *Figure S.22* the slope resistance is high at A, and low at B and infinite at C.



Figure S.22 Characteristic for a non-linear resistor showing variation of slope resistance with the position of the operating point

slow-wave circuit (US) Same as ***slow-wave structure***.

slow-wave structure In ***travelling-wave tubes*** a structure used to reduce the axial velocity of electromagnetic waves to a value equal to the electron-beam velocity to permit the interaction which leads to amplification. The usual form of slow-wave structure is a helix, the ratio of the pitch to circumference being chosen to give the required axial wave velocity.

slug (1) A small cylindrical plug of permeable or conducting material introduced into a coil to adjust the ***inductance***. A permeable slug increases inductance whereas a conducting slug (acting as a short-circuited turn) reduces it. If the slug and coil former are threaded, inductance can be adjusted by screwing the slug in or out, so making slug tuning possible.

(2) A short-circuited winding placed on the core of a relay to introduce a time lag in its operation.

small-scale integration (SSI) See ***monolithic integrated circuit***.

Small Computer Systems Interface (SCSI) A standard for linking computers to ***peripherals*** such as printers and scanners. The advantage of SCSI over other standards is that a number of peripherals can be ***daisy-chained*** together so that they share the same ***port*** on the computer. This reduces the requirements for ports on the computer and can also save cabling costs.

smart A vague term used to describe almost any kind of device which, with the aid of electronics, has acquired some facility for automatic control.

smart card A device which looks like a credit card, but in fact contains electronic circuitry. When this is connected to a suitable host device, it may provide a variety of services. It may, e.g. carry confidential information about the card's owner, such as a full medical record. Alternatively it may contain details of the owner's bank account, which are automatically updated as transactions take place.

smearing In TV, blurring of the verticals in a reproduced image.

Smith chart or **Smith diagram** Same as ***circle diagram***.

smoothing The attenuation of the ripple component in the output of a rectifier.

smoothing circuit Same as ***ripple filter***.

sneak current An unwanted current that flows in a circuit, usually as a consequence of poor circuit design rather than of defective components.

soak testing Of a component or equipment, a prolonged period of operation under normal conditions. The test is often used as a means of detecting intermittent faults, diagnostic instruments being connected to the equipment to call attention to the faulty condition.

soft keys Same as ***function keys***.

soft tube See ***gas-filled tube***.

software For ***computers*** and ***data-processing equipment*** the programs, routines, data and on-line documentation required for their operation. See also ***hardware***.

solar battery or **solar cell** Device for the direct conversion of solar energy to electrical energy. Such devices commonly use the photovoltaic effect of silicon diodes and a single cell gives an EMF of about 0.5 V. A series-parallel arrangement of cells is necessary to provide a battery with a useful output voltage and current. Solar batteries are used to power telephone repeaters in isolated situations and to power space vehicles.

solder An alloy of tin and lead used for making permanent low-resistance joints between metal surfaces. The solder must 'wet' the surface for a satisfactory joint and a flux is used as a cleaning agent.

solenoid An electromagnetic device consisting of an inductor with a hollow core in which a bolt of ferromagnetic material, the *armature*, is free to move. The magnetic field set up by an electric current in the inductor attracts the armature deeper into the core of the inductor. When the current stops flowing and the magnetic field disappears, the armature may return by spring action or may remain in its present position until another inductor in line with the first is energised and draws it away. Solenoids form part of electromagnetic ***relays*** and are widely used in the electrical and electronic control of machinery and industrial processes.

solid state Adjective used to describe a device, the operation of which depends on the structure and properties of a solid, particularly a ***semiconductor***.

sound Subjectively, the sensation produced when the ear responds to vibrations within a certain frequency range. Objectively, the vibrations themselves which are propagated as longitudinal waves in gases, liquids and solids. See ***audio frequency***.

soundblaster The popular name applied to the sound synthesis cards fitted in some IBM ***PC-compatible*** computers to provide the sound effects used in games and ***multimedia*** presentations.

sound cell A piezo-electric element used in ***microphones*** and consisting of two crystal ***bimorphs*** (bender types) mounted back-to-back with a small air space between them. The construction of a sound cell is illustrated in *Figure S.23*. A number of such elements may be connected in parallel to increase microphone sensitivity.



Figure S.23 Construction of a sound cell

source Of a ***field-effect transistor*** the connection to the channel from which majority carriers enter the channel. It corresponds with the ***emitter*** of a ***bipolar transistor*** and the cathode of an ***electron tube***.

source AC resistance See ***electrode AC resistance***.

source code A ***computer program*** in the form from which it is ***compiled*** or ***assembled*** into machine language (the ***object code***). See ***computer language***.

source follower The ***field-effect-transistor*** equivalent of the ***emitter follower*** and the ***cathode follower***.

space charge In general the net electric charge due to a collection of ***ions*** or ***electrons*** in space. In an ***electron tube*** the accumulation of electrons in the region between the cathode and the control grid. The electrons leave the heated cathode with an initial velocity which is soon reduced to zero by the negative charge on the grid and the positive charge on the cathode caused by the loss of electrons. Some electrons return to the cathode but others are being constantly liberated so that a cloud of them gathers in the grid-cathode space. A similar space charge occurs in a pentode between the screen grid and the suppressor grid. See ***virtual cathode***.

spark Conduction of an electric current of high density and of short duration through an ionised gas. See ***arc***.

specific inductive capacity (SIC) Same as ***permittivity***.

specific resistance Of a material, the ***resistance*** between opposite faces of a cube of the material of 1-cm side. The unit is the ohm-cm but for most good conductors the specific resistance expressed in this unit is very small and it is more convenient to use the micro-ohm-cm. For example the specific resistance of copper is 1.66 µΩ-cm.

spectrum (1) A continuous range of frequencies for which the waves have a specified common characteristic. For example the audio spectrum occupies the range between 20 Hz and 20 kHz approximately, the common characteristic being that the human ear can respond to waves of such frequencies. See ***electromagnetic waves***. (2) Of a complex signal, the distribution of the components with frequency. For example a rectangular wave has a spectrum consisting of uniformly-spaced components, the amplitudes of which decrease with increasing frequency.

spectrum analyser An instrument which resolves complex waveforms into their components and displays the result on the screen of a cathode ray tube, the horizontal axis representing ***frequency*** and the vertical axis the ***amplitude***.

speech coil Of a ***moving-coil loudspeaker*** or ***microphone***, the coil which is attached to the diaphragm and to which the audio-frequency input is applied or from which the audio-frequency output is taken.

speed-up capacitor Capacitor bridging the coupling resistor in a multivibrator circuit to improve the rise time of the output pulses. In a ***bistable*** circuit as shown in *Figure S.24* the edges of the output waveforms are not as steep as they could be because the inter-transistor couplings consist of the resistors R_3 and R_4 which, in conjunction with the input capacitances of the transistors, introduce a high-frequency loss. This can be offset by bridging R_3 and R_4 by capacitors C_1 and C_2 which, if of a suitable capacitance, can make the coupling circuit aperiodic.



Figure S.24 Speed-up capacitors C_1 and C_2 in a bistable multivibrator circuit

spherical aberration In an optical lens or mirror, lack of definition in the image caused by rays emanating from a point in the object failing to meet at a point in the image area. The defect is caused by use of spherical surfaces in the lens or mirror: it could be eliminated by use of parabolic surfaces.

spherical wave A wave of which the front is a spherical surface. A wave originating from a point source has such a front, the source being the centre of the spherical surface.

spike A transient of short-duration which occurs during the reproduction of a ***pulse***.

spiral scanning A form of ***scanning*** in which the spot on the screen of a ***cathode ray tube*** moves around the centre of the screen at constant angular velocity gradually moving inwards or outwards in a spiral path, with a rapid return to the edge or centre at the end of the scanning stroke.

split-beam oscilloscope Same as ***double-beam oscilloscope***.

spot In ***cathode ray tubes*** the small area of ***luminescence*** on the screen where the ***electron beams*** strike it. Efforts are made in the design of cathode ray tubes and the associated circuitry to keep the spot area as small as possible in order to improve the definition of the display.

spot wobble A technique used in black-and-white TV receivers to make the line structure of the displayed image less obvious by superimposing a vertical oscillation of very small amplitude on the scanning spot by use of an oscillator working at a frequency well above the video band.

spread Of characteristics the limits between which the properties of a manufactured component may vary from the published nominal value.

sprite Same as ***bitmap***.

spurious emission or radiation From a radio transmitter any radiation at a frequency other than the intended frequency, e.g. at a harmonic of the carrier frequency.

spurious oscillation See ***parasitic oscillation***.

spurious response Any response from a device or equipment other than the wanted response. For example second-channel response in a ***superheterodyne receiver*** is a spurious response.

square-law detector A detector for which the output signal is directly proportional to the square of the input signal over the useful range of the device. The ***anode-bend detector*** can be regarded as an example because the I_a-V_g characteristic of an ***electron tube*** near anode-current cut off is an approximation to a square-law curve.

square wave A wave which regularly alternates between two fixed values of amplitude, spending equal time at each, the times of transition between the values being negligible compared with the period of wave. The waveform of an ideal square wave is shown in *Figure S.25*. It contains a wealth of odd



Figure S.25 Idealised square waveform

harmonics and is extensively used for testing and for timing purposes in electronics.

squegging The generation of an oscillation, amplitude modulated by a relaxation oscillation. Squegging can occur in an oscillator in which there is very tight ***coupling*** between input and output circuits, resulting in a very rapid build-up of oscillation amplitude which is sufficient to cut off the active device. Oscillation therefore ceases until the active device is able to conduct again, whereupon the process repeats itself. A ***blocking oscillator*** is an example of a squegging oscillator in which the periods of conduction are sufficient for only half a cycle of oscillation.

squelch Same as ***quiet automatic gain control.***

s-signal In stereophonic sound broadcasting one half the ***difference signal.***

stabilisation (1) Of a power supply the process of ensuring that the output voltage is always at the intended value. Stabilisation implies regulation and some information on the circuits used for the purpose are given under ***regulation***.

(2) Of the working point of an ***active device*** the process of ensuring that the mean current through the device is always at the intended value. A number of circuit techniques are available for stabilising the working point. An example is shown in the transistor circuit of *Figure S.26*. R_1 and R_2 form a potential divider across the supply and impress a particular value of voltage on the base. By emitter-follower action this voltage appears at the emitter (less 0.7 V approximately in silicon transistors) so fixing the emitter voltage. R_3 is now chosen so that the desired mean emitter current is obtained. Thus if the base voltage is 3.0 V, the emitter voltage is 2.3 V and if R_3 is made, say 1 kΩ, the emitter current is stabilised at 2.3 mA.



Figure S.26 One circuit for stabilising the mean emitter current of a transistor

stabilising mesh The mesh situated near the target of a low-velocity TV camera tube and biased positively with respect to it to prevent instability of the target potential by effectively limiting the maximum potential which it can develop. For small light inputs to the camera, the mesh collects the secondary electrons emitted from the target with the result that the target develops a positive charge image. If, however, any area of the target tends to become more positive than the mesh potential then the electric field between mesh and target returns the secondary electrons to the target until the target potential equals the mesh potential. Thus no area of the target can develop a potential exceeding that of the mesh. See ***camera tube***, ***image orthicon***, ***orthicon***.

stability In general, of equipment, the extent to which a specified feature of its performance can be maintained in spite of variations in supply voltage, temperature or other factors which can affect performance. For example the stability of an oscillator is measured by the deviations in frequency from the nominal value.

stagger tuning The process of obtaining a level response over a desired bandwidth by tuning the resonant circuits to particular frequencies within the passband. This technique is used, for example, in the IF amplifiers of TV receivers and in the multi-cavity ***klystrons*** used in TV transmitters.

standard cell A primary cell the EMF of which remains constant with time and is used as a reference standard. To maintain the constancy of the EMF very little current must be taken from the cell which is not therefore used as a source of power. The best-known example of a standard cell is the Weston cell.

standard radiator Same as **full radiator**.

standby mode The state in which an equipment is not fully operational, but can be brought into operation instantly if required.

standing current Same as **quiescent current**.

standing wave On a ***transmission line*** a stationary pattern of voltage or current produced by interaction between a sinusoidal electromagnetic forwards-travelling wave and the wave travelling in the opposite direction after reflection at an impedance discontinuity. The interaction gives rise to alternate ***nodes*** and ***antinodes*** of voltage and current along the line, the distance between neighbouring voltage nodes (or antinodes) being equal to the wavelength. Acoustic standing waves can also occur, e.g. in an enclosure such as a room, by interference between a wave before and after reflection at a wall. Such standing waves are responsible for the acoustics of a hall.

star-delta transformation A method of simplifying network problems by replacing a star (or delta) network by a delta (or star) network which at a particular frequency has the same properties. The transformation is the same as that between T- and π-networks and for equivalence the following relationships apply (see *Figure S.27*):



Figure S.27 Star and delta networks

$$Z_1 = Z_a + Z_b + \frac{Z_aZ_b}{Z_c}$$

$$Z_2 = Z_b + Z_c + \frac{Z_bZ_c}{Z_a}$$

$$Z_3 = Z_c + Z_a + \frac{Z_cZ_a}{Z_b}$$

$$Z_a = \frac{Z_1Z_3}{Z_1 + Z_2 + Z_3}$$

$$Z_b = \frac{Z_1Z_2}{Z_1 + Z_2 + Z_3}$$

$$Z_c = \frac{Z_2Z_3}{Z_1 + Z_2 + Z_3}$$

star network A ***network*** with three or more branches, one terminal of each being connected to a common point. *Figure S.28* shows a star network. When there are three branches the network may alternatively be termed a ***T-network*** or ***Y-network***.



Figure S.28 A star network

starting anode or **starting electrode** In a gas-filled tube an ***electrode*** used to initiate the ***ionisation*** which causes the main discharge.

static characteristics Of an ***active device***, characteristics representing the relationship between the current at one electrode and the voltage at the same or other electrode, with all other voltages constant and with no load connected to the device. By superimposing a ***load line*** on the static characteristics it is possible to deduce the ***dynamic characteristics*** representing working conditions.

static error An error which is independent of a time-dependent variable. C.f. ***dynamic error***.

staticise In computers to store serial or time-dependent data.

static random-access memory (SRAM) A ***volatile store*** in the form of a matrix of cells, each consisting essentially of a ***bistable*** of ***bipolar*** or ***insulated-gate field-effect transistors***. Within each cell additional transistors provide inputs and outputs for reading and writing purposes, giving a total of 4 or 6 transistors per cell. Such a store retains inserted data provided the power supply is not interrupted. There is no need for ***refreshing*** as in a ***DRAM***.

static sensitive device A transistor or integrated circuit which may be damaged or even destroyed by the static charges generated by handling it if special discharging procedures are not adopted. CMOS devices are often of this type.

static store Same as ***static RAM***.

stationary wave Same as ***standing wave***.

steady state Of a system or equipment the condition when all transient phenomena have ceased and the voltages and currents are steady or varying sinusoidally between constant peak values.

steering diodes In a bistable circuit, ***diodes*** which direct incoming trigger signals alternately to the two elements of the circuit so that it is successively switched between its two possible states. Thus if the triggering signals are regular the steering diodes ensure that the bistable circuit generates square waves at half the trigger frequency.

step function A function which has a value of zero until a particular time at which it instantaneously assumes and maintains a constant finite value.

step recovery diode A semiconductor diode notable for the speed with which it ceases conduction when reverse-biased. It consists of a ***substrate*** of n-type silicon carrying a thin region of lightly-doped n-type silicon and an upper region of p-type silicon. When the diode is forward-biased, charge is stored in the centre region. When the diode is reverse-biased this charge falls and, when it is fully depleted, current through the diode cuts off very suddenly. If such a diode is regularly pulsed into conduction, the current contains a train of regularly-spaced steep edges which can be used to excite a resonant circuit into oscillation, so enabling an input at one frequency to give an output at a different frequency. See ***frequency multiplier***.

step response Of a system or equipment, its response to a signal in the form of a step function.

stereocasting (US) Stereophonic broadcasting.

stereophonic system A system of sound broadcasting or recording and reproduction which gives listeners an impression of directionality and spatial distribution of sound which greatly enhances the realism of reproduction. The system may use a number of spaced ***microphones***, an equal number of channels and the same number of spaced ***loudspeakers*** but, in broadcasting and recording, only two channels are normally employed and the system is compatible so that satisfactory monophonic reproduction of the stereo signal is possible.

sticking An effect in a TV camera tube which has been subjected to a stationary optical image for a long period whereby the tube continues to give a picture signal of the image after the image has been removed. In ***image orthicon*** tubes the effect occurs immediately after switching on because the target resistance is too high and the charge image persists longer than in normal operation.

stopband See ***filter***.

stopper See ***parasitic stopper***.

storage battery or **storage cell** Same as ***secondary cell***.

storage camera tube A camera tube in which a charge image corresponding to the optical image input grows in magnitude on the target until neutralised by the scanning beam. This occurs in all the camera tubes such as the

iconoscope, ***image iconoscope***, ***orthicon***, ***image orthicon*** and ***vidicon*** which have been successfully used in television services. Storage occurs by virtue of the capacitance of the target and it brings about a considerable increase in the sensitivity of the tube. In fact it was not until the advantage of the storage principle was appreciated that tubes sensitive enough for use in television services became possible.

storage element Of a computer ***store***, the smallest element of storage, e.g. a ***memory cell.***

storage tube An electron tube into which information can be fed for later reading. The stored signal can be displayed as a visible image on the screen or can be retrieved as an electrical signal.



Figure S.29 Basic features of storage tube

A simplified diagram of a storage tube is given in *Figure S.29*. The phosphor target is backed (on the viewed face) by a transparent conductive layer. The writing gun is maintained negative with respect to the target to attract electrons which are focused to a fine spot on the target, causing it to luminesce. By applying potentials to the deflecting plates the beam can be deflected so as to write on the screen.

Part of the writing beam is intercepted by the storage mesh and strikes it with sufficient velocity to release secondary electrons. For each beam electron striking the mesh, several secondaries are released (i.e. the ***secondary emission ratio*** is greater than unity). The secondaries are attracted to the nearby collector mesh, causing the storage mesh to go positive in the areas struck by the beam. Thus the display is written on the storage mesh as a positive ***charge image***. The cathodes of the flood guns are only slightly negative with respect to the target potential but electrons are attracted by the positive areas of the storage mesh and pass through it to enhance the display on the phosphor.

Once a charge image has been established on the storage mesh the trace continues to be displayed on the screen for a considerable period—under favourable conditions for up to an hour. In fact if the tube is switched off, a charge image can last for a week.

To erase the display a positive pulse can be applied to the target. This attracts electrons from the flood guns which are designed to flood the entire area of the screen with electrons so 'writing' the entire screen area. As the target potential falls at the end of the pulse the screen is erased.

By restricting the intensity of the beam from the writing gun it is possible to write on the phosphor screen without building up a charge image on the storage mesh—a technique known as 'writing through'.

Such tubes have very high resolution and give a flicker-free display.

store Of a ***computer***, the device into which information can be fed for retention until required. There are a number of different types of storage device, some using magnetic disks or tape, some using capacitors or bistable electronic elements. See ***bistable circuit***, ***magnetic core***, ***magnetic drum***, ***memory cell***, ***RAM***, ***ROM***.

'straight' receiver Same as ***tuned-radio-frequency receiver***.

stray capacitance In electronic circuits the ***capacitance*** arising from all sources other than from capacitors. Thus stray capacitance can arise from within active and passive components and from the proximity of components, conductors and chassis. Stray capacitance is undesirable because it limits gain at high frequencies by shunting loads but it is sometimes put to good effect as part or whole of the tuning capacitance of a resonant circuit. See ***distributed constants***.

streaking In TV an effect in which areas of incorrect tonal rendering appear to the right of vertical lines in the image. In black-and-white television the streaks may be black or white following black or white lines and can occupy any fraction up to the whole of the picture width. The effect is caused by anomalies in the amplitude and/or phase response in the video chain at frequencies around the line frequency.

string In computing, a sequence of ***bytes***, often representing ***text***.

strip (US) Same as ***scanning line***.

strobe To select a particular fraction of the period of a recurrent event. This is often necessary in detailed examinations of a regular ***waveform*** using an ***oscilloscope***. A strobe pulse which coincides in time with the wanted part of the waveform is used to gate the waveform and then to display it.

Structured Query Language (SQL) A language devised by IBM for creating, maintaining and viewing data in a ***database***. It is now becoming an industry standard and may provide a means for different computer types running different databases to extract data from each other.

stub An open-circuited or short-circuited length of ***transmission line***, usually less than a quarter wave, connected across a transmission line to facilitate matching of the line to a load.

subaudio A frequency below the normal audio range. The lower audio limit cannot be accurately defined but a subaudio frequency can be taken as one below 15 Hz.

subcarrier A carrier, usually with modulation, which is used to modulate another (main) carrier. Subcarriers are used extensively in telephony. They are also used in stereo sound broadcasting (to carry the difference signal) and in colour television (to carry the colour information). The subcarriers are ignored when compatible monophonic or black-and-white reproduction is required.

subdirectory Any ***directory*** other than the ***root directory***.

subharmonic Of a complex wave a sinusoidal component with a frequency that is an exact submultiple of that of the fundamental component. For example the second subharmonic has a frequency equal to one half that of the fundamental component.

subjective grading Of the performance of an equipment or system a method of grading in which a panel of observers record their assessments according to a scale. For example interference to a sound or TV programme can be classified as negligible, slightly distracting, distracting, very distracting or completely distracting.

submodulator Of a ***transmitter***, the penultimate stage of the ***modulator***.

subroutine In computers part of a program generally used more than once in the program and dedicated to the carrying out of particular operations. A typical example is the display of text characters.

subschema The user's view of data in a ***database***.

subset A piece of ***software*** which is a shortened and therefore incomplete version of some other software. Subsets of computer languages, for instance, may contain only the principal keywords.

substrate In general, the supporting material on which or in which a ***monolithic integrated ciruit*** is fabricated. In many semiconductor devices the substrate is a layer of monocrystalline silicon. In a ***field-effect transistor*** the substrate supports the channel, the source and the drain. In some types the substrate forms a pn junction with the channel: a connection to the substrate can then be used as a second gate terminal. In other types of FET, however, the substrate is insulated from all parts of the transistor.

summing amplifier An ***operational amplifier*** with a ***negative feedback*** network so designed that the output is equal to the sum of the input signals. Such amplifiers are used in ***analogue computers***.

sum signal In stereo broadcasting the signal formed by adding the signals in the left and right channels. In the pilot-tone system of transmission the sum signal is used to frequency modulate the main carrier and it is this signal which is reproduced by a ***monophonic*** receiver.

super-alpha pair Same as ***Darlington pair***.

superconductivity The virtual disappearance of electrical resistance in certain metals at temperatures approaching absolute zero. The effect is pronounced in copper and zinc around 5°K and currents induced in a ring of these metals by movement of a magnetic field continue to flow for some hours afterwards.

super Emitron Same as ***image iconoscope***.

superheterodyne receiver A radio receiver in which the modulation of all incoming signals is transferred to a new fixed carrier frequency (the intermediate frequency), most of the gain and selectivity of the receiver being achieved in the IF amplifier.

Frequency changing is achieved by mixing the incoming signals, possibly after amplification, with the output of an oscillator, the tuning of which is ganged with that of the signal-frequency circuits so that the mixer output remains at the intermediate frequency for all settings of the tuning control. The IF amplifier is followed by a detector or discriminator and subsequent modulation-frequency amplifiers as required.

The block diagram of a superheterodyne receiver is shown in *Figure S.30* and this applies to AM and FM sound receivers and to the basic structure of



Figure S.30 Block diagram of a superheterodyne receiver

TV receivers. Practically all modern receivers utilise the superheterodyne principle. The term is a telescoped form of supersonic heterodyne, a reference to the fact that the IF is above the audible range.

superposition theorem The current flowing at a point in a linear passive ***network***, as a result of the simultaneous application of a number of voltages distributed in any manner throughout the network, is the sum of the component currents at that point which would be caused by the individual voltages acting separately. Similarly the potential difference existing between any two points in the network as a result of the several applied voltages is the sum of the component potential differences between the points which would be caused by the individual voltages acting separately.

super-regenerative receiver An AM receiver incorporating a detector which is taken in and out of oscillation at an ultrasonic rate, so achieving higher gain than is normally possible without instability. A ***grid-leak detector*** with ***reaction*** is capable of high gain but the gain is limited by the onset of oscillation. The super-regenerative principle avoids this limitation by allowing oscillation to build up and then quenching it at an ultrasonic frequency. It is possible to achieve RF and ultrasonic oscillation in a single active device but better results are possible with a separate ultrasonic oscillator.

suppressed-carrier modulation A system of ***amplitude modulation*** in which both sidebands are transmitted, the carrier being suppressed. Because the carrier component remains constant, whether there is amplitude modulation or not, it is clear that the carrier can be suppressed, all the information being contained in the sidebands. It is necessary, however, to re-insert the carrier at the receiving end to permit detection.

suppressor grid An ***electrode*** situated between the screen grid and anode of an ***electron tube*** to prevent secondary emission from the anode from reaching the screen grid. The suppressor grid is normally connected to the cathode to form a decelerating field near the anode which returns secondary electrons to the anode. In this way the ***tetrode kink*** can be eliminated so improving the ability of the tube to handle large output-voltage swings.

surface acoustic wave device (SAW) A device which makes use of radio waves in the form of surface deformations on piezo-electric materials. Such waves can be excited by suitable ***transducers*** and they have wavelengths about 10^5 times smaller than those in free space. Thus the wavelength of a 35-MHz wave is less than a millimetre and it is possible by suitably shaping the piezo-electric surface to produce an extremely-small filter by techniques similar to those used in microwave filters. ***Bandpass filters*** of this type are used in the IF amplifiers in TV receivers and there is likely to be considerable development in this type of structure in the future.

surface-barrier transistor A ***bipolar transistor*** in which the ***emitter*** and ***collector*** regions are formed by electrodeposition of a trivalent or pentavalent element on opposite faces of a thin base wafer.

surface mounting A method of mounting specially-designed components and integrated circuits on a ***printed wiring*** board by soldering the contacts of the components directly to the tracks, so eliminating the need for holes in the board. The method permits greater component packing density, gives higher speeds of operation and much improved thermal performance.

surface noise In record reproduction the noise produced by the stylus passing through the groove. There is very little surface noise from modern records but earlier types were of shellac incorporating an abrasive material and the minute irregularities in the groove walls caused a pronounced hiss on reproduction. See ***scratch filter***.

surfing Jargon for browsing on the ***Internet***, which some computer users find an absorbing pastime.

surge impedance Same as ***characteristic impedance***.

surround sound Same as ***quadraphony***.

susceptance (*B*) That component of the ***admittance*** of an alternating-current circuit which is due to its ***inductance*** and/or ***capacitance***. It is the imaginary component of admittance and, for a circuit containing only susceptance, the voltage and current are in quadrature. Susceptance is the reciprocal of ***reactance***. For an inductance L the susceptance (in mhos) is given by

$$B_L = 1/\omega L$$

and for a capacitance C

$$B_C = -\omega C$$

where ω is the angular frequency. The signs follow the same convention as for reactance.

susceptibility Of a magnetic material the ratio of the intensity of magnetisation to the magnetising force. For an ***isotropic*** material the susceptibility is equal (in rationalised units) to the relative permeability less one.

sweep The regular movement of the spot across the screen in a ***cathode ray tube*** or the change in frequency across the band in a wobbulator output.

sweep oscillator (US) Same as ***wobbulator***.

swept-frequency generator Same as ***wobbulator***.

swing The difference between the extreme values of current, voltage or frequency of a signal.

swinging choke A series inductor used for smoothing and located immediately following the output of a rectifier. To improve regulation the choke is designed so that its effective inductance decreases with increase in the current through it.

switch A device for breaking (opening) or making (closing) an electric circuit. Switches can be mechanical, e.g. those controlling electric lights, or they can be electronic (consisting of transistor or thyristor circuits) such as those used in electronic telephone exchanges.

switch-mode power supplier A DC power supplier with an AC input and in which the smoothed output from the rectifier is chopped into pulses which are then rectified and smoothed to provide the output, the mark/space ratio of the pulses being automatically adjusted to regulate the output voltage. The chopping device may be self-oscillating or may be driven from a pulse generator, such as an astable multivibrator, within the power supplier. Such power suppliers can be made highly efficient and much more compact than conventional types. One reason for this is that by using a high pulse frequency only small smoothing components are needed. (In power suppliers for television receivers the pulse generator is often synchronised at line frequency.) Another reason is that the active device acting as chopper operates as a switch and (except for the instants of switching) has zero current in it or zero voltage across it; dissipation in the device is thus minimal. See ***regulation***.

syllabic companding ***Companding*** in which the changes of gain are fast enough to follow the syllables in speech but not the individual cycles of the speech waves.

symmetrical deflection Of a ***cathode ray tube***, ***electrostatic deflection*** in which the deflecting voltages applied to the plates are symmetrical about a reference potential (usually the final-anode potential). Such a system gives less geometric distortion of the image than asymmetric deflection.

symmetrical operation Same as ***push-pull operation***.

synchrodyne A system of ***heterodyne*** reception in which the oscillator operates at the carrier frequency of the received signal and is synchronised by the received signal. It is an example of heterodyne reception in which the intermediate frequency is zero, the output from the frequency changer being at modulation frequency.

synchronising signal In TV the ***signals*** which ensure that the horizontal and vertical scanning circuits in picture-display equipment are synchronised with the picture-generating equipment. In colour TV the synchronising signal includes the colour burst which synchronises the chrominance decoder. The synchronising signal is added to the picture signal to form the video signal.

synchronous detector A detector sensitive to phase and amplitude variations in the modulated signal applied to it. Such detectors are used for independently recovering the two components of the chrominance signal from the quadrature-modulated subcarrier in the ***NTSC*** and ***PAL colour TV systems***. For successful operation the detector must be synchronised with the reference signal (colour burst) contained in the TV colour signal.

synchronous logic In ***data-processing*** logic in which all operations start on receipt of a signal from a clock. C.f. ***asynchronous logic***.

synchronous tuning Tuning in which all the resonant circuits are adjusted to the same frequency.

sync level In TV the level reached by the peaks of the synchronising signals. See *Figure B.18* (a).

synthesiser An electronic musical instrument which produces a wide repertoire of sounds using digital techniques to construct the required output waveform.

system A complex of conductors, components and equipments interconnected so as to perform a particular function. For example, a radio receiver can be said to have an ***a.g.c.*** system and a collection of antennas can form a ***diversity*** system.

T

tachogenerator A generator mechanically coupled to a rotating shaft to give an electrical output proportional to the rotational speed of the shaft. This output may be used to indicate the shaft speed or may form an input to a speed-regulator circuit.

Tagged Image File Format (TIFF) A ***bitmap file*** standard widely used for storing images and transferring them, especially between computers of different types. A very versatile format, it can handle images having up to 32 bits per pixel and various compression algorithms. It is, perhaps, the closest approach to an industry-standard bitmap file format.

tandem connection Same as ***cascade***.

tank circuit In general an oscillatory circuit. In particular a parallel *LC* circuit forming the load of a tuned amplifier (e.g. in a transmitter) or forming the frequency-determining element of an oscillator.

tantalum bead capacitor A type of polarised capacitor offering high capacitance with low losses and leakage in a compact package.

tape See ***magnetic recording***.

tape streamer A device for recording data at high speed on tape in a data cartridge. The most common use for tape streamers is for backing up ***hard disk drives***, but they are also used for distributing large collections of software.

target The electrode in an ***electron tube*** on which the ***electron beam*** is focused. Thus the target of a cathode ray tube or a picture tube is the luminescent screen. In a simple camera tube such as an ***iconoscope***, ***orthicon*** or ***vidicon*** the target is photosensitive and an optical image of the scene to be televised is focused on it. As a result the target develops a charge image which is discharged by the scanning beam to generate the tube output.

In camera tubes with an image section the target is of secondary-electron emitting material and the charge image is generated by bombardment of the target by photo electrons from the ***photo-cathode***.

target language (US) Same as ***object code***.

T bistable A ***bistable circuit*** with an input such that every time the input takes on its 1-state the output of the bistable goes to the complementary state. When the T input takes up its 0-state it has no effect on the output.



Figure T.1 Logic symbol for a T bistable

tearing In TV, erratic breaking up of part of a reproduced image by lateral displacement of some of the scanning lines caused by faulty line synchronisation.

tecnetron An early form of ***field-effect transistor*** pioneered by the French.

telecommunication The process of sending information from one point to another by electromagnetic means. The information can be of any kind, e.g. sound or picture signals, and the link between the two points may also be of any kind, e.g. by wire, radio, optical means or a combination of any of them.

telegraphy A system of telecommunication for the transmission of information consisting of graphic symbols, usually letters and figures, by use of a signal code. The system is used primarily where permanent records are required of the messages sent. The link may be of any kind, e.g. line or radio, and the code is often that used by ***teleprinters***.

telemetry A system of telecommunication for the transmission of information on measurements, e.g. the water level in a reservoir is represented by an electrical signal suitable for transmission over the link which may be a line or radio or a mixture or both.

telephony A system of telecommunication for the transmission of speech or other audio signals. The link may be by line or radio or a mixture of both and is normally such as to provide two-way speech communication.

telepresence A computer technique similar to ***virtual reality*** in that the user dons a body suit or headset and gloves to provide an input. In telepresence, however, there is no virtual world. The computer controls a ***robot*** which mimics the user's actions. Telepresence has applications in industry, exploration and military operations where some task must be performed in a hazardous environment. The robot enters the hazardous area and takes the risks, while the human operator remains safe.

teleprinter A machine capable of converting a written message containing letters and figures into a coded form suitable for transmission over a telegraph link to a similar machine which recreates the original message. The teleprinter has a keyboard similar to that of a typewriter and messages typed on it appear on a paper roll at the transmitting and receiving machines so that there are identical records of the message at both ends of the link.

teletext In TV a system of transmitting information in the form of letters, figures and simple diagrams, by signals incorporated in the television waveform. The information can be displayed on the screen of a suitably-equipped television receiver in place of or superimposed on the normal programme.

In this service, termed ***Ceefax*** by the BBC and ***Oracle*** by the IBA, the teletext information is transmitted as a pulse-coded signal occupying one of the normally-empty forward scanning-line periods in the field blanking interval. Several hundred different pages of teletext information can be transmitted using this system giving, for example, details of news items, weather reports, sports results etc. A receiver equipped with a teletext decoder enables the user to select any desired page.

teletypewriter (US) Same as ***teleprinter***.

television The process of creating instantaneously at a distance a black-and-white or coloured image of a real or recorded scene and the movement occurring in it by means of an electrical system of communication. The term recorded scene includes pictures from cinema film, videotape, videodisc or transparency.

television camera Equipment containing the optical and electronic components required to generate a ***picture signal*** from the optical image of a scene. In a black-and-white camera the principal components are an optical lens system and a camera tube. The camera tube requires facilities for deflecting and focusing the electron beam and the camera may include a head amplifier for the camera tube output. A colour television camera incorporates at least three camera tubes and an optical device for splitting the optical image into its red, green and blue components. In addition some colour cameras have a fourth camera tube to generate the luminance signal.

Most television cameras include a viewfinder which may be optical or may be a picture tube fed from the camera output.

television camera tube See ***camera tube.***

television system The particular combination of television signal waveform, method of transmitting vision and sound, channel width, channel spacing etc. chosen. There are a number of different systems and they have been classified by the CCIR. The system used in the United Kingdom is system I.

television waveform See ***video signal.***

temperature coefficient In general a factor expressing the degree to which a quantity is affected by changes in temperature. More specifically it is equal to the relative change in the quantity per degree Celsius. Some electronic components are marked with their temperature coefficient. For example a capacitor marked N750 has a temperature coefficient of capacitance of -750 parts in 10^6.

temporary storage In computers ***storage*** reserved for intermediate results.

terminal A point where a signal is applied to or withdrawn from a ***network*** circuit or equipment. It is also known as an external node. See also ***computer terminal.***

termination The external ***impedance*** connected to the two terminals of a ***transmission line.*** If this impedance is equal to the characteristic impedance of the line, the termination is described as matched and the wave is not reflected at the termination. For any other value of termination there is a reflected wave.

testing The carrying out of operations on a component, equipment or system to determine if it is functioning correctly or, for a new component etc, to determine if it is likely to function correctly when put into service. There are a number of different types of test. See ***accelerated life test, acceptance test, life test, maintenance test.***

tetrode An electron tube with two grids between cathode and anode, that nearest the cathode being the control grid and the other carrying a fixed positive bias. There are two main types of tetrode:

(a) The screen-grid tetrode in which the positively-biased grid is designed as an electrostatic screen between control grid and anode virtually eliminating the grid-anode capacitance and so enabling the tube to be used as a stable RF amplifier. The I_a–V_a characteristic contains the

tetrode kink but if the tube is used only as a small-signal amplifier this is not a serious disadvantage.

(b) The kinkless tetrode in which the positively-biased grid is used, not to eliminate anode-grid capacitance but to eliminate the tetrode kink in the I_a–V_a characteristic. Thus the tube is capable of large output-voltage swings and is used in power output stages, e.g. in AF amplifiers. See ***beam tetrode***, ***critical-space tetrode***, ***screen-grid electron tube***.

tetrode kink See ***dynatron***.

tetrode thyristor A ***thyristor*** with two gate terminals, one connected to the inner n-region (anode gate) and the other to the inner p-region (cathode gate) and which can be switched to the on-state and to the off-state by signals applied to one of these gates. It is sometimes known as a silicon controlled switch. The graphical symbol is given in *Figure T.2*.



Figure T.2 Graphical symbol for a tetrode thyristor (silicon controlled switch)

tetrode transistor See ***insulated-gate field-effect transistor***.

text Data consisting of printable characters such as alphanumerics and punctuation marks. Such data uses a code such as ***ASCII*** or ***EBCDIC***.

text file A ***file*** representing a string of printable characters such as alphanumeric characters and punctuation marks, perhaps in ***ASCII*** format.

thermal breakdown See ***thermal runaway***.

thermal noise ***Noise*** arising from the thermal agitation of the ***electrons*** in a ***conductor***. Although in a conductor with no applied voltage, the number of electrons passing a given point in one direction equals the number passing it in the opposite direction when the measurement is made over an appreciable period, there are momentary surfeits or deficits of electrons and their variation with time constitutes thermal noise. The magnitude of the noise voltage V_n is given by

$$V_n^2 = 4kTR\Delta f$$

where k = Boltzmann's constant,
T = absolute temperature,
R = resistance,
and Δf = bandwidth over which the noise is measured.

Substituting the value for k and putting T = 290°K for normal room temperature we have

$$V_n = 1.25 \times 10^{-4}\sqrt{(R\Delta f)}\,\mu\text{V}.$$

For example the voltage generated across a 2-kΩ resistor over a bandwidth of 5.5 MHz is 131 μV.

thermal relay A ***relay*** which depends for its operation on the heating effect of an electric current.

thermal resistance The difference in the temperature at two points divided by the power flow between them when thermal equilibrium has been established. It is thus the temperature difference per unit dissipation and can be measured in degrees C per watt. The concept is useful in the design of ***heat sinks*** which must have a minimum thermal resistance to be able to dissipate the power transmitted through them satisfactorily. The thermal resistance depends chiefly on the mass and the surface area of the heat sink.

thermal runaway Cumulative effect which occurs in ***semiconductors*** in which the heat generated in the device by the current through it increases the current, so raising the temperature further. This results in a rapid rise in device temperature which can damage or even destroy the device. Where there is danger of thermal runaway, transistor circuits are designed to stabilise the mean current, a process known as DC stabilisation or ***stabilisation*** of the operating point.

thermionic emission The emission of ***electrons*** from a heated conductor. At normal temperatures the free electrons in a conductor have a certain mobility but their energy is not normally sufficient to enable them to escape from the surface of the conductor. If, however, the conductor is heated the electron energy is increased and some can escape into the surrounding space. The more the conductor is heated the greater is the number of electrons which escape. Thus the electrons liberated from the cathode of an ***electron tube*** are released as a result of thermionic emission.

thermionic tube An ***electron tube*** containing an electrode, normally the cathode, which must be heated to release the electrons or ions necessary to give conduction through the tube. See ***gas-filled tube***.

thermistor A ***resistor*** with a large negative temperature coefficient of resistance. The temperature-sensitive materials used in thermistors are oxides of manganese or nickel formed into rods and fired at high temperature. The resistance of a thermistor decreases with increase in temperature and thus with increase in the current through it. Its behaviour, therefore, is the opposite of that of most metallic conductors. Small thermistors are heated by passing the current directly through the temperature-sensitive element but there are also indirectly-heated types where the current is passed through a winding electrically-insulated from the element.

Thermistors are used for surge suppression, e.g. a directly-heated type may be connected in series with the tube heaters in a radio receiver so as to limit the surge of current when the circuit is switched on and the heaters are cold and therefore of low resistance. Thermistors are also used for temperature measurement.

thermocouple Junction of two different metals which, when heated, generates an EMF which depends on the temperature of the junction. Thermocouples are used for measuring radio-frequency currents (by their heating effect) and for measuring high temperatures.

thermo-electric effect The generation of an EMF at the junction of two dissimilar metals when the junction is heated. The effect is sometimes described as the Seeback effect. See also ***Peltier effect***.

thermostat A switch which operates automatically at a predetermined temperature and which is used, in conjunction with a heating or cooling device, to maintain a constant temperature in an enclosure. The switch is often operated by a bimetallic strip. Such an arrangement is used at radio transmitters to maintain a constant temperature for the piezo-electric crystal which determines the carrier frequency.

Thevenin's theorem If an impedance Z' is connected between any two points of a linear network the current which flows in it is given by $V/(Z + Z')$, where V is the voltage and Z is the impedance measured between the points before Z' was connected.

thick-film circuit A circuit in which resistors and their interconnections are formed on a ***substrate*** by applying special inks via a stencil screen or metal mask and firing them in a furnace. Resistance accuracy of ±15% can be achieved. Where necessary the resistors can be adjusted by abrasive trimming or by a laser beam to an accuracy of 0.1%. Discrete components (resistors, capacitors, inductors, transformers, semiconductor diodes and transistors) can be mounted on a thick-film circuit.

thin-film circuit A circuit in which components and their interconnections are formed on a ***substrate*** by evaporation or sputtering of resistive, conductive or dielectric material. The components can be resistors, capacitors or inductors and the substrate can be glass, alumina or silicon. Discrete components (resistors, capacitors, inductors, transformers, semiconductor diodes or transistors) can be mounted on a thin-film circuit.

third-generation computer See ***digital computer***.

three-state output In logic circuitry a device output which in addition to the usual states representing the two logic levels has a third possible state (usually open-circuited) which has no logic significance. It is represented in diagrams as shown in *Figure T.3*. The importance of the open-circuit condition is that it enables an output to be effectively disconnected from its external circuit. Thus a number of outputs may be connected in parallel, e.g. on a bus without interference provided no more than one is enabled at a time.



Figure T.3 Representation of three-state output

threshold The minimum amplitude at which a signal will activate a device, e.g. in logic circuits, the minimum input voltage that will be recognised as a logic-1 rather than a logic-0.

threshold frequency See ***photoelectric-emission***.

throat Of a horn-loaded ***loudspeaker*** that end of the horn where the cross section is a minimum.

thumbnail A reduced-size reproduction of a computer ***graphic***. Some applications create illustrated ***catalogues*** of directories containing graphics files with a thumbnail of each for ease of identification and selection.

thyratron A hot-cathode gas-filled ***triode*** or ***tetrode*** in which the ***control grid*** initiates anode current but does not control it. Provided that the anode voltage is high enough a grid voltage exceeding a critical value initiates anode current which is then limited only by the HT supply voltage and the resistance of the external anode circuit. To cut off the anode current both anode and grid voltages must be below certain values.



Figure T.4 Graphical symbol for a triode thyratron

Thyratrons were extensively used as electronic switches in control circuits, e.g. for controlling the power fed to a load from the mains. The thyratron was connected in series with the load and acted as a half-wave rectifier, the angle of conduction of which could be controlled by the bias applied to the control grid. ***Thyristors*** have now replaced thyratrons in most applications. The graphical symbol for a thyratron is given in *Figure T.4*.

thyristor A bistable ***semiconductor*** device which can be switched to the on-state (and in some types to the off-state also) by a signal applied to the gate terminal.



Figure T.5 Basic construction of a 2-terminal thyristor



Figure T.6 Basic construction of a 3-terminal thyristor

Thyristors are of four-layer pnpn construction and the outer layers are known as the anode and cathode as indicated in *Figure T.5*. If the anode is made positive with respect to the cathode, pn junctions a and c become forward-biased and therefore of low resistance but junction b is reverse-biased thus limiting the current through the device to the leakage current of this junction. If, however, the anode voltage is increased sufficiently avalanche breakdown occurs in the centre junction and a large current flows through the device, limited only by the voltage and resistance in the external circuit: this is the on-state. The anode voltage can now be reduced to a low value but the on-state will persist until the current through the device falls below a critical value when the device becomes non-conductive again (the off-state). If the anode is made negative with respect to the cathode, junction b becomes conductive but junctions a and c are reverse-biased and prevent significant current flow: for such voltages the device remains in the off-state. Such a device is known as a ***reverse-blocking***

diode thyristor. Two such devices connected in reversed parallel form a bidirectional diode thyristor. A variant of the diode thyristor which remains in the on-state for negative anode voltages is known as a reverse-conducting diode thyristor.

By applying a signal to one of the inner layers the pnpn structure can be triggered into the on-state even at low anode voltages and again will remain in the on-state until the current has fallen below the critical value. The inner region is termed the gate as indicated in *Figure T.6* and the three-terminal device is termed a reverse-blocking triode thyristor or, more simply, a thyristor.



Figure T.7 Two-transistor analogue of the thyristor

The mechanism of the triggering process is best understood by reference to the two-transistor analogue of the thyristor. As shown in *Figure T.7* a thyristor can be regarded as a combination of an npn and a pnp transistor with the collector of each connected to the base of the other (see *multivibrator*). Suppose such a device has a small positive anode voltage but is in the off-state. As explained, junctions a and c will be forward-biased and junction b reverse-biased: these are the normal conditions for the two constituent transistors to operate as amplifiers. When a positive voltage is applied between gate and cathode it increases the forward bias of the npn transistor with the result that current crosses junction c and this, by normal transistor action, gives rise to a collector current in the inner n-region which is also the base region of the pnp transistor. By normal amplifying action in the pnp transistor this gives rise to a collector current in the inner p-region which is also the base region of the npn transistor. In this way positive feedback occurs and, if the combined current gain of the two transistors exceeds unity the feedback is regenerative causing a very rapid build-up of current which puts the device into the on-state. The gate voltage can now be removed but the thyristor will remain conductive until the current in it falls below the critical value—behaviour typical of a bistable multivibrator. From the symmetry of the device structure it is clear that the thyristor could alternatively be triggered by a negative signal applied to the inner n-region. Thus there are two types of reverse-blocking triode thyristor one with a p-gate (cathode gate) and the other with an n-gate (anode gate).

There are corresponding reverse-conducting triode thyristors and a type which can be triggered into the off-state known as a turn-off thyristor. A very useful thyristor can be constructed of two triode thyristors in reverse parallel with a common gate connection: this is known as a triac and can be triggered into conduction by a positive or negative signal applied to the gate. If external connections are made to both inner layers of the pnpn structure the thyristor so obtained can be triggered into the on-state and into the off-state by appropriate signals applied to one of the two gates. This is a tetrode thyristor alternatively known as a silicon controlled switch which is used, amongst other applications, as a field oscillator in television receivers.

The chief application for thyristors is as rectifiers in mains-operated power-control systems where the conduction angle is controlled by signals applied to the gate. For this reason thyristors are often known as silicon controlled rectifiers.

The general graphical symbol for a thyristor is given in *Figure T.8*. The symbols for individual types of thyristor are given in the particular definitions.



Figure T.8 General graphical symbol for a thyristor

tilt Same as ***sag***.

time base In cathode ray oscilloscopes that deflection of the electron beam which is defined with respect to time. Usually this is the horizontal deflection, the waveform to be displayed providing vertical deflection.

time-base generator Equipment for generating the ***signals*** providing the ***time base*** for an oscilloscope. For ***electrostatic deflection*** the time base generator must provide a sawtooth voltage and, for flexibility in the applications of the oscilloscope, a wide range of sawtooth frequencies is required.

time constant Of a quantity varying exponentially with time, the time taken for the quantity to vary by 63% (i.e. 1 − 1/e) of the full extent of the change. When a capacitor C charges from a DC supply via a resistor R the voltage across the capacitor reaches 63% of its final value after RC seconds, where R is in ohms and C in Farads. When the capacitor is discharged its voltage reaches 37% of its initial value in RC seconds as shown in *Figure T.9*. RC is thus the time constant of the circuit. If an inductor L is connected across a DC supply via a resistor R the current grows exponentially with time and reaches 63% of its final value (E/R) in L/R seconds where L is in Henries and R in ohms.

time division multiplex (TDM) A multiplex system in which each ***signal*** is allowed use of the communications path for a short time interval. Usually there are a number of signals and they use the path in turn.



Figure T.9 The time constant for an RC combination when charging and discharging

time slot A recurrent interval of time which can be uniquely defined. For example a particular forward line-scanning period during the field blanking interval is the time slot occupied by the ***teletext*** signal.

timing The process of ensuring that all the ***signals*** necessary to make up a complex waveform or to carry out an operation arrive in the correct sequence and at the correct intervals.

T metal-oxide semiconductor transistor (TMOS) An ***insulated-gate field-effect transistor*** so constructed that the current flow is for the most part perpendicular to the plane of the layers as in ***planar*** bipolar transistors; the source consisting of a large number of sites each associated with a short channel, the parallel connection of which yields low switching times and low source-drain resistance in the on condition. Large source and drain areas permit the transistor to give substantial output power.

T-network A ***network*** consisting of two series elements with a shunt element connected to their ***junction***. *Figure T.10* illustrates a T-network: it may be regarded as an example of a star network with three branches.



Figure T.10 A T-network

toggle (US) Same as ***bistable circuit***.

tone (1) In audio a sinusoidal signal of constant frequency used for test purposes or to identify circuits. (2) In popular speech the term is used to describe the quality of a musical sound. For example a cello may be described as having a mellow tone. (3) In photography and TV the degree of light or shade of an image or an element of an image.

tone control A circuit for adjusting the ***frequency response*** of an audio amplifier. The chief ways in which the response may be modified are indicated in *Figure A.12* and high-quality equipment is usually capable of all such responses but in simple receivers with a single tone control this usually introduces top cut only.

tone wedge In TV a test image consisting of a series of areas of which the tone varies in steps between black and white. Most TV test cards incorporate a tone wedge which can be used for the adjustment of receivers.

top cut ***Attenuation distortion*** in which the upper frequencies of the audio range are attenuated.

top lift Accentuation in which the upper frequencies of the audio range are emphasised.

totem-pole output Same as ***single-ended push-pull.***

touch sensor or **switch** A switch which operates when a finger comes into direct connection with two closely-spaced contacts or when the finger provides a capacitive link between the contacts. The direct-connection type of switch is fed from a DC supply and the presence of the finger causes a small direct voltage to be injected into a ***monostable*** or ***bistable*** circuit which performs the required switching action. The capacitive type of switch is fed from an AC supply and the presence of the finger on an insulating cover over the contacts causes a small alternating voltage to be injected into the following circuit which brings about the required switching action. Touch switches are extensively employed, e.g. in controlling lifts and in channel switching on television receivers.

trace Of a ***cathode ray tube*** the pattern generated on the screen by the movement of the ***electron beam***.

track A channel containing stored data in a storage medium such as a tape or ***floppy disk*** or ***hard disk***.

trackball or **trackerball** In computing a ***pointing device*** used as an alternative to a ***mouse***. The trackerball is a fixed unit containing a captive ball whose uppermost portion is exposed. The user manipulates the ball with his thumb or the palm of his hand to guide the pointer around the screen. Trackerballs are also used in closed-circuit television systems, especially for security surveillance, to pan and tilt remotely mounted surveillance cameras.

tracking (1) In a ***superheterodyne receiver*** maintenance of the correct difference between signal frequency and oscillator frequency as the tuning is altered. When similar sections of a ganged tuning capacitor are used for signal-frequency and oscillator circuits, ***trimming*** and ***padding capacitors*** are included in the oscillator circuit to help maintain this frequency difference. In fact even with such aids the difference frequency can be made correct (i.e. equal to the ***intermediate frequency***) only at three settings of the capacitor. These are therefore positioned one near each end of the tuning range and the third at the centre: this is known as three-point tracking.

(2) In record reproducing equipment the accuracy with which the plane of vibration of the reproducing stylus is maintained at right angles to the direction of the groove at the stylus point as the reproducing head moves across the disk. By offsetting the head on the arm (or curving the arm) and

by arranging for the stylus to overshoot the disk centre to a critical extent the tracking error can be minimised.

(3) The formation of carbon conducting paths across the surface of insulating materials by electric stress. Certain insulating materials, notably those made of fibrous material such as paper and paxolin, are very subject to tracking.

transceiver A device, usually portable, which can be used as a ***transmitter*** or a ***receiver***. Much of the circuitry of a transceiver is common to the transmitter and the receiver.

transconductance (US) Same as ***mutual conductance***.

transducer A device which responds to an input signal in one form of energy and gives an output signal bearing a relationship to the input signal but in a different form of energy. The forms of energy are usually acoustic, mechanical and electrical. For example a ***microphone*** is a transducer which converts acoustic into electrical energy. This is an interesting example because there are, in fact, two energy conversions in a microphone. The original acoustic energy (oscillations of air) is first converted into mechanical energy (vibrations of a diaphragm) which is then converted into electrical energy (changes in voltage) at the output terminals.

transductor A ferromagnetic device in which the degree of saturation of the core (and hence the effective inductance) can be controlled by the current flowing in one of the windings. It is sometimes known as a ***saturable reactor***.

transfer characteristic (1) Of an ***active device***, the curve obtained by plotting the output current against the input voltage or current. For an ***electron tube*** or ***field-effect transistor*** the input is taken as a voltage and for a ***bipolar transistor*** as a current. (2) Of a ***camera tube***, the curve obtained by plotting the output current against the light input. (3) Of a magnetic recording system, the curve obtained by plotting the magnetic flux density against the magnetising force.

transfer coefficient (or **constant**) Same as ***image transfer coefficient***.

transfer impedance Between any two pairs of ***terminals*** in a ***network***, the complex ratio of the voltage applied to one pair to the resultant current at the other pair, all other terminals being terminated in a specified manner, e.g. if there are other generators these should be replaced by their internal impedances. The term is defined in the same manner as ***mutual impedance*** but the terminating conditions differ.

transformer A device consisting of two or more inductively-coupled windings. Transformers are widely used in electronics and the following are typical applications:

(*a*) For changing the voltage of an alternating supply.
Where equipment requires a supply voltage which differs from that of the mains, a transformer can be used to give a suitable alternating voltage and at the low mains frequency a laminated ferromagnetic core can be used.

(*b*) For isolation.
Where it is undesirable to have physical connection to the mains, a 1:1 transformer can be used to supply the power. Such transformers are often used with musical instruments such as electric guitars.

(*c*) For impedance matching.
When the ***impedance*** of a load is necessarily different from the optimum value required by the generator, a matching transformer can be included between the two impedances to achieve maximum power transfer. If the impedance ratio is n:1 the transformer turns ratio should be $\sqrt{n}$:1.

(*d*) For coupling.
Step-up transformers are used between stages in electron-tube amplifiers to give voltage gain and step-down transformers between ***bipolar-transistor*** stages to give current gain. At low frequencies such transformers use laminated ferromagnetic cores but at radio frequencies ferrite cores or even air cores can be used. In RF transformers one or both of the windings may be tuned (and the degree of coupling adjusted) to give the required passband. In oscillators a transformer may be used to provide coupling between input and output circuits of an active device so providing the positive feedback essential for oscillation.

(*e*) To convert between balanced and unbalanced operation.
Transformers with centre-tapped windings are used extensively in circuits where balanced operation is required e.g. in ***push-pull amplifiers***, ***ring modulators***.

Where there is no objection to a physical connection between primary and secondary circuits, a transformer need have only one winding with tapping points, the primary or secondary circuit being connected between suitable tapping points. This is known as an autotransformer and line output transformers in television receivers often have a number of tapping points to feed the scanning coils and the various auxiliary circuits which rely on the line output stage for their power.

The graphical symbols for (a) an air-cored transformer and (b) an autotransformer with a ferromagnetic core are shown in *Figure T.11*.



Figure T.11 The graphical symbol for (a) air-cored transformer and (b) an auto-transformer with a ferromagnetic core

transient In an acoustic or electrical system, the ***signal*** which persists for a brief period following a sudden disturbance to the steady-state conditions. Transients have an irregular and non-repetitive waveform. The term is applied particularly to the damped oscillations which follow shock excitation of a resonant system.

transient response The ability of a circuit or device to reproduce transients without ***distortion***.

transistor A semiconductor device of which the output current can be controlled by the signal(s) applied to one or more input terminals. See ***bipolar transistor***, ***field-effect transistor***.

transistor-transistor logic (TTL) A system in which use is made of logic elements comprising chiefly bipolar ***transistors***. In one TTL circuit the output stage is ***single-ended push-pull*** in which one transistor is conductive at a time. Speed of operation is high but is limited by the fact that the bipolar transistors are driven into saturation and, because of ***carrier storage***, switch off more slowly than they switch on. This limitation has been overcome in a recent modification to the TT system in which ***Schottky diodes*** are connected between the collector and the base of the transistors to prevent them from saturating. This has resulted in a significant improvement in speed of operation.

transit angle The transit time expressed as an angle. Transit angle is thus the product of the transit time and the angular frequency.

transition In a waveform an instantaneous change from one value of amplitude to another. An ideal pulse thus contains two transitions. The term 'edge' is sometimes used instead, e.g. the trailing edge of a pulse.

transition frequency (1) Of a bipolar transistor the frequency (f_T) at which the modulus of the common-emitter current amplification factor has fallen to unity. It thus measures the highest frequency at which the transistor can be used as an amplifier; it is, in fact, the gain-bandwidth product for the transistor. (2) See ***turnover frequency***.

transitron A ***pentode*** in which use is made of the virtual cathode set up between the ***screen grid*** and the negatively-charged ***suppressor grid***. The virtual cathode, suppressor grid and anode can be treated as electrodes of a triode, the real cathode, control grid and screen grid being the electrodes of a second triode. Thus the pentode can be used as the equivalent of some two-triode circuits notably multivibrators. The equivalent of a ***monostable multivibrator*** is known as a ***phantastron***.

The negative-resistance characteristic between suppressor grid and screen grid which gives the circuit its name can be used as the basis of an oscillator.

transitron oscillator An oscillator which utilises the negative-resistance kink in the screen-grid characteristic of a pentode with a negatively-biased suppressor grid. See ***dynatron oscillator***, ***transitron***.

transit time In general the time taken for a charge carrier to cross a given gap. In ***electron tubes*** the time taken by ***electrons*** to travel from the ***cathode*** to other electrodes is of great importance and, in fact, limits the upper frequency at which the tubes can be used successfully. Thus tubes for high-frequency applications are constructed with very small inter-electrode spacings to minimise transit time. See ***disk-seal tube***. On the other hand microwave tubes such as ***travelling-wave tubes*** make use of transit time in their operation.

transmission line A system of conductors connecting one point to another along which electric or electromagnetic energy can be sent. Thus telephone lines and power-distribution lines are examples of transmission lines but in electronics the term usually implies a line used for the transmission of RF energy, e.g. from a radio transmitter to the antenna.

An essential feature of such a transmission line is that it should guide energy from the sending end to the receiving end without loss by radiation. One form of construction commonly used consists of two similar conductors mounted close together but maintained at a constant separation. These two conductors form the two sides of a balanced circuit and any radiation from one of them is neutralised by that from the other. Such twin-wire lines are used for carrying high RF power, e.g. at transmitters.

For low-power use the coaxial form of construction is often employed, one conductor being in the form of a cylinder which surrounds the other at its centre and thus acts as a screen. Cables so constructed are extensively used to couple FM and television receivers to their antennas.

At frequencies above approximately 1000 MHz transmission lines are usually in the form of ***waveguides*** which may be regarded as coaxial lines without the centre conductor, the energy being launched into the guide or abstracted from it by probes or loops projecting into the guide.

See ***characteristic impedance***, ***coaxial cable***.

transmitter In general a device which sends a signal. A telephone transmitter converts sound waves to a.f. signals for transmission over telephone circuits. A radio transmitter sends electromagnetic waves conveying sound or television programmes or other forms of data.

transparent In computing and telecommunications a term used to describe a vital process which occurs automatically and without affecting the user; ideally the user should be unaware that it is happening. An example is the handing over of a mobile user from one base station to another in ***cellular radio***.

transponder A combination of radio receiver and transmitter designed to radiate an acknowledging signal automatically when a correct interrogating signal is received.

transputer A combination of microcomputer-type devices designed to achieve higher operating speeds than a conventional microprocessor.

In a normal microprocessor the various operations needed to obtain the desired end result are carried out sequentially as the program indicates. However, in the transputer a higher operating speed is achieved by sharing the operations between a number of microprocessors which operate simultaneously. This parallel mode of working is not easy to achieve technically. Moreover conventional computer languages cannot be used and a new language OCCAM has been designed for use with the transputer.

transverse magnetisation In ***magnetic recording***, magnetisation of the tape across its width, i.e. at an angle to the direction of tape movement. This method is used in video tape recorders as a means of achieving the high tape-to-head speed necessary to record the high video frequencies whilst still keeping a low speed of tape movement. The high transverse scanning speed is achieved by using a number of heads around the circumference of a drum which rotates so sweeping the heads across the tape.

trapezium distortion Same as ***keystone distortion***.

trapezium modulation A system of ***amplitude modulation*** used at sound broadcast transmitters to permit a higher average modulation depth and so give improved intelligibility in areas of low field strength. To achieve this result the AF signal is clipped at an adjustable amplitude level and passed through a low-pass filter to suppress the harmonics introduced by the clipper. Thus peak signals become trapezoidal in waveform.

trap valve amplifier Amplifier with a number of outputs with a high degree of isolation between them used for distributing a broadcast programme to a number of destinations.

travelling-wave tube (TWT) An ***electron tube*** used at VHF and UHF in which the input wave travels along a ***slow-wave structure*** so that its axial velocity equals that of an electron beam fired along the axis, the resulting velocity modulation and consequent bunching providing the required amplification.



Figure T.12 (a) Simplified construction of a travelling-wave tube and (b) graphical symbol for an O-type travelling-wave tube with indirectly-heated cathode, intensity-modulating electrode, focusing electrode, slow-wave structure with connection, collector, focusing coil and window couplers to input and output waveguides

As shown in *Figure T.12*(a) the tube contains an electron gun at one end and a collector at the other, the intervening space being occupied by a helix or other form of slow-wave structure. The input signal is fed into one end of the slow-wave structure and the amplified output is abstracted from the other. The slow-wave structure is designed to reduce the velocity of electromagnetic waves which thread the structure so that the axial velocity is equal to that of the electron beam. Interaction between the wave and electron beam produces amplification. For a helix the factor by which the wave velocity is reduced is the ratio of the circumference to the pitch. Travelling-wave tubes are extensively used as microwave amplifiers and can be designed to have very wide bandwidths. The graphical symbol for one type of travelling-wave is shown in *Figure T.12*(b).

triac See ***bidirectional thyristor, thyristor.***

trigatron Same as ***trigger tube.***

trigger circuit A two-state circuit which can switch from one state to the other automatically or by external signals. See ***astable circuit, bistable circuit, multivibrator.***

triggering The initiation of a change of state in a device by means of an external signal. The significant feature of triggering action is that the change of state continues automatically and independently of the external signal once it has been started. See ***bistable circuit, monostable circuit.***

trigger tube A ***gas-filled tube*** containing a spark gap in which the main



Figure T.13 Graphical symbol for a trigatron or trigger tube



Figure T.14 Graphical symbol for an indirectly-heated triode

discharge can be initiated or terminated by a signal applied to an auxiliary electrode. If the external signal causes conduction in the tube, the state of conduction persists after the triggering signal has ceased. The graphical symbol for a trigger tube is given in *Figure T.13*.

trimming In general the process of fine adjustment of a variable resistor, capacitor or inductor. In particular a trimming capacitor is a small preset component connected in parallel with each section of a ganged tuning capacitor and which is adjusted to compensate for small differences in capacitance between the sections or to achieve three-point ***tracking*** in ***superheterodyne receivers***.

trinitron A precision-in-line television picture tube pioneered by the Japanese.

triode An ***electron tube*** with three electrodes namely a ***cathode***, control grid and ***anode***. This was the first amplifying tube and was invented by Lee de Forest in 1905 when he inserted a grid in a diode. By suitably biasing the grid with respect to the cathode it is possible to control the density of the electron stream from the cathode which reaches the anode. Thus the grid voltage controls the anode current and by including a load in the anode circuit, the anode voltage becomes an amplified copy of the signal applied to the control grid. For linear amplification the grid must be suitably biased.

Such tubes have been widely used in electronic equipment since their invention, their use being confined to audio and subaudio frequencies. The internal anode-to-control grid capacitance makes triodes unsuitable for RF amplification. The graphical symbol for an indirectly-heated triode is given in *Figure T.14*. For most applications triodes have now been superseded by ***transistors***.

triple detection See ***double superheterodyne reception***.

tri-state output Same as ***three-state output***.

trochotron A multi-electrode tube used for ***counting***. It has a single ***cathode*** surrounded by a number of target electrodes and a magnetic field is employed to ensure that the electron beam moves around the cathode to strike the targets in sequence.

tropicalising The practice of ***encapsulating*** whole equipments or circuit boards in materials designed to survive harsh environments, such as high humidity, temperature extremes or the presence of corrosive chemicals.

true colour Colour stored digitally as 24 bits per ***pixel***, that is 8 bits to represent the levels of each of the red, green and blue primaries. This gives a ***palette*** of 2^{24} = 16,777,216 colours, more than the human eye can distinguish. See ***colour model***.

trunk Same as ***bus***.

truth table For a logic function a table showing all the possible combinations of input signals and, for each, the output signal. As a simple example the following is the truth table for an AND function showing that a logic-1 output is obtained only when both inputs stand at the 1-state.

input 1	input 2	output
0	0	0
0	1	0
1	0	0
1	1	1

If the logic convention is reversed so that logic-1 becomes logic-0 and vice versa the truth table takes the form shown below

input 1	input 2	output
1	1	1
1	0	1
0	1	1
0	0	0

which shows that a logic-1 output is obtained when either input is at logic 1. This is the truth table for an OR gate and it shows that whether a given gate acts as an AND gate or an OR gate depends on the logic convention adopted.

tube See ***electron tube***.

tuned circuit A resonant circuit of which the resonance frequency has been adjusted to the desired value.

tuned radio-frequency receiver (TRF) A radio receiver incorporating one or more stages of radio-frequency amplification before the detector and one or more audio-frequency stages after it. A block diagram of a TRF receiver is given in *Figure T.15*. Such receivers were used in the 1920s but the number of tuned circuits it was possible to include in them was limited by the difficulty of ganging the tuning controls. The selectivity was therefore poor and TRF receivers were superseded by ***superheterodyne*** types in the early 1930s.



Figure T.15 Block diagram of a tuned radio-frequency receiver

tuner (1) Short for ***tuning capacitor***. (2) A radio or television receiver containing little or no amplification after the detector and no internal means of monitoring reception. It is normally used in conjunction with an external amplifier, monitor or tape recorder, e.g. in a hi-fi system.

tuning (1) Of a ***tuned circuit*** the process of adjusting the resonance frequency to a desired value. For an LC circuit this can be done by adjusting the capacitance, the inductance or both. (2) Of a ***receiver*** the process of adjusting it to respond to a wanted signal.

tuning capacitor A variable capacitor forming part of a tuned circuit and used to adjust the resonant frequency.

tuning indicator Of a ***receiver*** a device giving visual indication of correct tuning. A number of devices are in common use. The correct tuning point may be indicated by a simple meter movement, by the area of ***luminescence*** on the screen of a small ***cathode ray tube*** or, for TV receivers, by the width of a line of ***luminescence*** on the screen.

tunnel diode A ***pn diode*** which makes use of the ***tunnel effect***. The forward characteristic of a tunnel diode exhibits a region of negative resistance as shown in *Figure T.16* (a) which can be exploited in an oscillator, an electronic switch or for low-noise amplification at frequencies up to 1000 MHz. The graphical symbol for a tunnel diode is shown in *Figure T.16* (b).



Figure T.16 (a) Characteristics for a tunnel diode (solid) and a normal diode (dashed) and (b) graphical symbol for a tunnel diode

tunnel effect Penetration of the potential barrier at the junction between highly-doped p- and n-regions by ***electrons*** which have insufficient energy to surmount the barrier. This effect is impossible to explain in terms of classical physics but is in agreement with quantum mechanics. Because of the tunnel effect the forward characteristics of a tunnel diode differs from that of a normal pn diode. For example current begins to flow across the junction at a very low value of forward bias and it increases with increase in bias up to a maximum (known as the peak point) at about 0.1 V for a germanium diode and then falls reaching a minimum (known as the valley point) at about 0.3 V where the characteristic joins that for a normal pn diode as shown in *Figure T.16* (a). Thus the tunnel effect gives the characteristic a region of negative slope between the peak and valley points. The reverse characteristic for a ***tunnel diode*** also differs from that of a normal pn diode in that breakdown occurs almost at zero bias as for a ***backward diode***.

turn-off thyristor A ***thyristor*** which can be switched from the on-state to the off-state by a signal applied to the gate. n-gate and p-gate types exist and their graphical symbols are given in *Figure T.17*.



Figure T.17 Graphical symbol for turn-off thyristor (a) with n-gate and (b) with p-gate

turnover frequency (US) In disk recording the frequency at which the recording characteristic changes from a ***constant-amplitude*** to ***constant-velocity*** type.

tweeter A small loudspeaker unit designed to operate at audio frequencies above approximately 2 kHz. Tweeters are often piezo-electric types and are used in combination with other units and crossover networks in high-quality wide-range loudspeakers.

twin-interlaced scanning See ***interlaced scanning***.

twin-T network Same as ***parallel-T network***.

twisted pair A cable consisting of two individually insulated wires twisted tightly together. The twisting brings the two conductors in close proximity so that they respond equally to any interfering fields. The induced voltages therefore cancel, minimising the effects of the interference.

two-quadrant multiplier A multiplier the operation of which is restricted to one sign only of the input signals.

two-terminal-pair network A ***network*** of which the characteristics are specified at four particular terminals, two acting as input and the other two as output. The network may have other terminals. Alternatively known as a two-port network.

U

ultra-linear amplification An audio-frequency push-pull output stage using ***tetrodes*** or ***pentodes*** in which the screen grids are fed from tappings on the primary winding of the output transformer. This arrangement feeds a fraction of the output voltage to the screen grids thus giving ***negative feedback*** and by suitable choice of the position of the tapping points odd harmonic distortion can be reduced to a minimum. Even harmonics are, of course, eliminated by the use of push-pull and thus an output stage of this type is capable of excellent linearity.

ultrasonics The study of acoustic waves in material media, the frequency being above that of the audible range. Such waves can be generated by ***magnetostriction*** and ***piezo-electric*** devices and have many practical applications. For example they are used to assist machining operations on brittle materials, to assist soldering, for echo-sounding purposes and in remote control of television receivers. The term is preferred to 'supersonic' which is now reserved for speeds greater than that of sound: supersonic persists, however, in the word superheterodyne.

ultraudion Early form of triode detector using ***positive feedback***.

ultra-violet radiation Electromagnetic waves with a wavelength between approximately 10 and 380 nanometres, i.e. immediately adjacent to the visible spectrum. Although invisible to the human eye, such radiation can affect photographic plates and can produce ionisation.

unbalanced circuit See ***asymmetrical circuit***.

uncommitted logic array (ULA) An ***array*** of logic elements fabricated without interconnections on a substrate. Such arrays can be mass produced by the ***planar*** process and can be used for a number of different purposes depending on the interconnections between the elements. Customers specify the interconnections they require and these are made in a subsequent metallising operation.

undercoupled circuits Two circuits resonant at the same frequency and between which the degree of ***coupling*** is intentionally less than the critical value. The effect of such coupling is to give a response with a single peak at the common resonance frequency and with an amplitude proportional to the degree of coupling but less than that for critical coupling.

undershoot Form of transient distortion of a step or pulse signal in which the response makes a temporary excursion before the main transition and in the opposite direction. See *Figure U.1*.

unijunction transistor A ***transistor*** consisting essentially of a filament of say n-type semiconductor with a p-junction near its centre, connections being brought out from the ends of the filament and from the p-region. The device is well suited for use in simple pulse-generating circuits. The graphical symbol for a unijunction transistor is given in *Figure U.2*.

unilateral conductivity Property of certain devices, notably ***electron tubes*** and semiconductor pn junctions, of conducting electricity easily in one



Figure U.1 Reproduction of the leading edge of a pulse showing undershoot



Figure U.2 Graphical symbol for a unijunction transistor

direction and not at all or only slightly in the opposite direction. Such devices have obvious applications as ***rectifiers***, ***detectors*** and ***switches***.

unilateral impedance A mutual impedance through which power can be transmitted in one direction only. ***Active devices*** such as ***electron tubes*** and ***transistors*** are examples of unilateral impedances because they enable the current in one circuit to be controlled by the current in another circuit but the receiving-circuit current does not affect the sending-circuit current. Alternatively known as control impedances.

unilateralisation Neutralisation circuit used with ***bipolar transistors*** and in which the ***internal feedback*** is counteracted by an external series *RC* circuit, the constants of which are chosen to neutralise the internal collector-base resistance and capacitance. Such neutralisation, if properly adjusted, makes the input and output circuits of the transistor independent of each other so making stable RF amplification possible.

unipolar transistor A transistor which operates by virtue of only one type of charge carrier. An n-channel ***field-effect transistor*** is an example in which the charge carriers are ***electrons***.

unit step See ***step function***.

unitunnel diode A ***tunnel diode*** in which the current at the valley point is approximately equal to that at the peak point. See *Figure T.16*(a).

universal asynchronous receiver/transmitter (UART) In ***computers*** and ***data-processing equipment*** an interface unit between the central processor and a peripheral device.

universal receiver A receiver which operates from AC or DC mains. Such receivers were common when many parts of the country still had DC mains. The receivers had series-connected electron-tube heaters operating via a dropper resistor from the mains supply and HT was obtained via a half-wave rectifier which acted as a series resistor on DC mains. Also termed AC-DC receiver.

univoltage lens An ***electrostatic lens*** consisting of three apertured electrodes, the outer two with a fixed common bias relative to electron-gun cathode potential, focus being affected by variation of the voltage of the inner electrode. Such a lens has a very short focal length and is often used in ***electron microscopes***.

UNIX A *multitasking operating system* available on a wide variety of computers. It allows multiple users to use the same computer and multiple applications may be run simultaneously.

unscrambler See *scrambler*.

unstable state Of a circuit a state which cannot persist, the circuit automatically reverting to an alternative state. When a circuit is placed in an unstable state, changes occur within it which automatically terminate the state after a certain time. Usually the change is the discharge of a capacitor through a resistor which, when the discharge has reached a certain point, precipitates the return to the alternative state. Thus the duration of the unstable state depends on the time constant of an *RC* combination and can be controlled by suitable choice of value for *R* or *C*. ***Monostable circuits*** have one unstable state, ***astable circuits*** have two.

upload To transmit data to another computer.

upward modulation Same as ***positive modulation***.

user-friendly Simple and convenient to operate, needing no specialised skills or knowledge.

utility A piece of ***software*** that performs a useful function but which would normally be used in conjunction with other ***applications***. It is not sufficiently comprehensive to be regarded as an ***application*** in its own right. For example, a program to ***load*** various ***bitmap*** formats would be regarded as a utility. It might be used in conjunction with graphics or desktop publishing software needing to display the bitmap.

V

vacuum tube A tube which has been exhausted to a high degree of vacuum so that the amount of gas present in the envelope is too small to have any effect on the electrical characteristics. The tube may be sealed or continuously pumped. Currents in a vacuum tube are carried by ***electrons*** not ***ions***.

valence The force which binds atoms together to form a molecule.

valence band In an ***energy-level diagram*** the range of energies corresponding to states which can be occupied by the valence electrons binding the atoms together.

valence electrons ***Electrons*** occupying the outermost orbits of an atom and which are shared when atoms combine to form molecules. See ***covalent bonds***.

value (1) The numerical level of the primary property of a passive component, for instance, the number of Ohms of resistance offered by a resistor. (2) In computing, the contents of a ***variable***. (3) In the HSV ***colour model*** the overall level of the light emitted by the colour.

valve Term originally applied to a device which allowed current to pass through it in one direction only (i.e. a ***diode***) but later extended to include vacuum devices with grids which could amplify and oscillate, and gas-filled devices such as ***thyratrons***. The term has been replaced by ***electron tube*** which is used throughout this dictionary.

vapour cooling Of a high-power ***electron tube*** a method of removing heat which utilises the latent heat of vaporisation of water. The external anode has thick copper walls containing vertical passages and is immersed in distilled water which boils in the passages, the latent heat required to turn the water into steam being taken from the tube.

varactor A reverse-biased ***junction diode*** the ***capacitance*** of which can be controlled by adjustment of the bias voltage. Such diodes are used in ***parametric amplifiers***, for automatic frequency control and for tuning in radio and TV receivers.

variable In computing, a block of data held in a reserved area of memory and identified by an unique name. The data held may be numeric or may consist of a text ***string*** and may be accessed by ***programs***; instructions to output the variable yield its current contents, not its name. See also ***array***.

variable-capacitance diode See ***varactor***.

variable-carrier modulation Same as ***floating-carrier modulation***.

variable-mu tube An ***electron tube*** in which the ***control grid*** is wound with a pitch which varies along its length so permitting the mutual conductance to be controlled by choice of grid-bias value. A typical I_a–V_g characteristic for a variable-mu tube is shown in *Figure V.1*: for a small value of grid bias as at A the slope (and gain) is high whereas for a point such as B the slope (and gain) is low. An advantage of these tubes is that they can accept a larger input signal at B than at A for comparable distortion levels. Such



Figure V.1 I_a–V_g characteristic of a variable-mu electron tube showing high mutual conductance at A and low at B

tubes were used in situations where it is required to control gain by choice of bias value as in ***automatic gain control*** systems.

variable-reluctance pickup A ***pickup*** in which the movements of the reproducing stylus vary the reluctance of a magnetic circuit and generate corresponding EMFs in a stationary coil. The moving-iron pickup is an example of a variable-reluctance pickup.

varicap diode Same as ***varactor diode***.

variocoupler A mechanical arrangement permitting control of the degree of magnetic coupling between two coils. For example one coil may be fixed and the other brought up to it to increase the mutual inductance between them.

variometer A variable inductor consisting of two coils, one of which can be rotated within the other so as to vary the mutual inductance between them. The coils are connected in series and the mutual inductance can add or subtract from the series inductance depending on the position and sense of the rotatable coil.

varistor A resistor of semiconductor material with a non-linear current-voltage characteristic.

vector graphics A system of computer graphics in which lines and shapes are stored as co-ordinate-based data. See ***graphics***.

velocity factor Of a ***transmission line*** the ratio of the velocity of an electromagnetic wave along the line to its velocity in free space. Depending on the construction of the line, values of velocity factor lie between 0.6 and 0.97.

velocity modulation The process of periodically altering the velocity of an electron stream by subjecting it to a high-frequency electric field which alternately accelerates and decelerates the beam. If the period of the variation is comparable with the ***transit time*** of the electrons in the space concerned, the electrons subsequently gather into bunches. ***Bunching*** makes possible microwave amplification and oscillation in ***klystrons*** and ***travelling-wave tubes***. See ***Applegate diagram***.

velocity microphone (US) Same as ***pressure-gradient microphone***.

vented enclosure A cabinet housing a loudspeaker unit, closed except for a forward-facing vent, cabinet and vent forming a ***Helmholtz resonator*** tuned, by choice of dimensions, to a low audio frequency. Radiation through the vent reinforces that from the diaphragm at low frequencies so extending the effective frequency response of the loudspeaker.

vertex Same as ***node*** (1).

vertical amplifier In oscilloscopes the circuits which amplify the signals responsible for vertical deflection of the beam. Also known as a Y amplifier.

vertical blanking Same as ***field blanking***.

vertical-groove metal-oxide-semiconductor transistor (VMOS) An ***insulated-gate field-effect transistor*** so constructed that the current flow is nearly perpendicular to the plane of the layers as in planar ***bipolar transistors***, a groove-shaped gate giving very short channel lengths. Such transistors thus have very high switching speeds and low drain-source resistance in the on-condition. Large source and drain areas permit the transistors to give substantial output power. A simplified diagram of the structure of a VMOS transistor is given in *Figure V.2*.



Figure V.2 Simplified construction of VMOS transistor

vertical hold See ***hold control***.

vertical polarisation Property of an electromagnetic wave in which the plane of polarisation of the electric field is vertical.

vertical timebase In a ***cathode ray tube*** the circuits generating the signals which give vertical deflection of the beam. In TV this is usually termed the field timebase.

very-large-scale integration (VLSI) See ***monolithic integrated circuit***.

vestigial sideband transmission (VSB) A system of ***amplitude modulation*** in which one sideband is transmitted in full, only part of the other sideband being transmitted (usually that corresponding to the lower modulating frequencies).

The system is used for transmitting the vision component of a TV signal and has the advantage that it occupies less bandwidth than if both sidebands were transmitted in full.

vibrator converter An equipment in which a tuned reed, maintained in vibration by a low-voltage DC supply, is used to generate DC at a higher voltage. The equipment is, in effect, a ***vibrator inverter*** in which the alternating output voltage is rectified to give the required DC supply often by contacts on the vibrating reed itself so avoiding the need for a separate rectifier.

vibrator inverter A device in which a tuned reed, maintained in vibration by a low-voltage DC supply, is used to generate alternating current usually at higher voltage. The interrupted current from the low-voltage supply is applied to a transformer which generates the required alternating voltage. Such equipments are used, for example, for powering mobile equipment normally designed for operation from mains supplies.

video cassette recorder (VCR) A ***video tape recorder*** which uses cassette tapes. In practice domestic VCRs also incorporate a UHF or VHF television ***tuner***, allowing television broadcasts to be recorded off air without the need for a separate television receiver. A VCR usually incorporates a ***dedicated microcomputer*** which can be programmed to record future television broadcasts automatically.

video digitiser An equipment, often contained in an ***expansion card***, which converts video frames to ***bitmaps***. It is also sometimes called a *frame grabber*.

video disk A disk containing video data, usually in a digital format. The first video disks used a recording technique similar to that in ***Compact Disc***, but were 12 inches in diameter and could accommodate a 1½-hour feature film. With advances in compression and storage technology, such as ***MPEG***, it is now possible to store a feature film on a 5 inch compact disk.

Video Graphics Array (VGA) A VDU display standard introduced by IBM on its PS/2 computer in 1987 and since adopted as an industry standard. The highest resolution in the original VGA standard was 640 × 480 pixels with 16 colours.

video memory The RAM which stores the image on a VDU. The video memory requirement depends on the ***video mode*** since it is proportional to the number of pixels in the display and to the logarithm (base 2) of the number of colours to be displayed. The original VGA standard (640 × 480 × 16 colours) required 640 × 480 × 4 = 1,228,800 bits = 150 kilobytes. A computer fitted with 1 Mbyte of video memory can support a display of 640 × 480 pixels in true colour (24 bits per pixel) which requires 900 kilobytes or a display of 800 × 600 pixels at 16 bits per pixel (65,536 colours) which requires 937.5 kilobytes.

video mode or **screen mode** The specification of a ***VDU*** display. The data include: the number of ***pixels*** across the screen, the number of pixels down the screen, the nominal width and height of a single pixel, the maximum number of colours that may appear on the screen without a change of ***palette*** and the refresh rate, that is the number of frames per second. Most computers allow a choice of screen modes to suit various purposes.

video on demand A proposed system in which subscribers may demand any of a wide range of video, audio or computer material from a remote service provider. The requested material is then transmitted in compressed format over a landline, assumed to be a fibre-optic cable, to the subscriber's terminal. At the time of writing pilot schemes are in operation.

video signal In TV the signal obtained by combining the picture signal with the synchronising signal. The way in which the signals are combined is illustrated in *Figure B.18* (a). See ***picture signal, sync signal.***

video still camera An electronic camera which takes individual frames and stores them as ***bitmaps***. These are subsequently ***uploaded*** to a computer for processing and printing as computer graphics.

video tape recorder (VTR) An equipment which records video and audio, usually in analogue format, on tape. See also ***video cassette recorder.***

videotex A system whereby ***signals*** sent over telephones lines can be displayed as letters, figures or diagrams on the screen of a TV receiver. The system uses the same symbols and techniques as ***teletext*** and British Telecom is now using such a system under the name Prestel to make available to telephone users some hundreds of thousands of pages of information, e.g. on stock exchange prices, railway timetables, sports results.

videotron Same as ***monoscope.***

vidicon A low-velocity TV ***camera tube*** with a photoconductive target. The construction of a vidicon tube is illustrated in *Figure V.3*. The target consists of a transparent signal plate on which is deposited a layer of photoconductive material. The scanned face of the target is stabilised at electron-gun cathode potential as in any low-velocity tube and the signal plate is given a small positive bias. Current thus flows longitudinally through the target thickness and the magnitude of this current at any point on the target depends on the target resistance which in turn depends on the amount of light in the optical image at that point on the target. These longitudinal currents set up a charge image on the scanned face of the target and this is



Figure V.3 Vidicon tube

neutralised by the scanning beam once per picture period. The target has a significant capacitance between front and rear faces and this is charged by the longitudinal currents in the interval between successive scans by the beam so that the charge image grows during the picture period: in other words the tube has the charge storage which is essential to achieve adequate sensitivity.

Early vidicon tubes suffered from lag, i.e. there was an appreciable delay between a change of light input and the corresponding change in target resistance but intensive work on photo-conductive materials has resulted in satisfactory sensitivity and lag. Modern tubes (plumbicons) have multilayer targets of lead oxide.

The vidicon is a particularly simple and compact tube and it is not surprising that it is the standard tube for inclusion in colour TV cameras.

viewdata Same as ***videotex***.

virtual cathode A region between the electrodes of an ***electron tube*** which contains an accumulation of ***electrons*** and can be used as a source of electrons for nearby electrodes. Such regions occur when the electron stream through the tube encounters a retarding field, e.g. between the screen grid and suppressor grid of a pentode. See ***phantastron***, ***space charge***, ***transitron***.

virtual memory Memory which appears to be available to a computer, although it does not exist as physical RAM. Usually virtual memory is a file on a ***hard disk*** accessed via a buffer. Using virtual memory a computer can process files that are larger than the physical RAM fitted in the machine.

virtual reality (VR) An ***interactive*** computer simulation of a three-dimensional environment, such as a building, a town, a ship or a region of outer space, stored as a mathematical model. Using ***vector graphics*** techniques the computer repeatedly generates in ***real time*** the instantaneous view of the environment as seen by a hypothetical observer moving around within it. In the most sophisticated form of VR users wear special headsets containing stereoscopic LCD displays, a binaural sound system and sensors which detect movements of the head. Movement and interactive functions are controlled through further sensors in gloves, or even a whole body suit, worn by the user. These give him the illusion of being inside the virtual world, able to explore it and to interact with it in various lifelike ways. Simpler versions of VR use a conventional monitor and pointing device. VR has many serious applications in such fields as medicine, architecture, town and country planning and training (such as flight simulators). Its leisure uses, however, have attracted much publicity, especially the fantasy games in which several players interact with each other within the virtual environment. See also ***telepresence***.

virus A portion of ***computer program*** devised by a malevolent programmer. Usually viruses are embedded in applications software and they replicate themselves, by embedding themselves in other applications, when the host application is run or even when its icon appears in a directory display. They spread from one system to another when the applications harbouring them are copied and transmitted to other systems. Some viruses are comparatively harmless, perhaps displaying a humorous message on a certain day, but others cause serious damage, overwriting or corrupting valuable data and programs.

vision carrier In TV transmission the carrier wave which is modulated by the *video signal.*

vision frequency In TV transmission the frequency of the *vision carrier.*

vision pickup tube Same as *camera tube.*

vision signal In TV transmission the carrier wave modulated by the *video signal.*

visual display unit (VDU) In *computers* or *data-processing equipment* a *cathode ray tube* used for displaying characters or graphical information under program control. Often a keyboard is associated with visual display unit for displaying the input data.

visualisation The use of computers to create high-quality images of objects that do not exist except as mathematical models. In industry such techniques are used to create photographic-quality images of proposed products (such as automobiles) from engineering drawings. Sometimes *ray tracing* is used, but sophisticated *vector graphics* applications also yield acceptable images, depending on the nature of the subject.

voice coil (US) Same as *speech coil.*

voice recognition Computer technology that recognises and is able to respond to spoken words picked up using a microphone and converted to digital format. It has many applications in security systems and in providing facilities for the handicapped who cannot use a keyboard or pointing device.

volatile Liable to disappear. Data stored in normal RAM is volatile in that it will disappear if the equipment is switched off or its power supply is interrupted. Data stored in battery-backed RAM or on magnetic media such as a floppy or hard disk is non-volatile and is not lost at power-off.

voltage The value of an electromotive force or potential difference expressed in volts.

voltage amplifier A circuit incorporating one or more *active devices* and designed to amplify voltage waveforms. The term distinguishes such amplifiers from those designed to amplify current waveforms or to deliver power to a load. It is the ratio of source impedance to input impedance and of output impedance to load impedance which determines whether a device or amplifier is best regarded as a current amplifier, power amplifier or voltage amplifier. If both ratios are small compared with unity the signals transferred from source to input and output to load are best regarded as voltage waveforms. The associated signal current waveform is of minor interest in a voltage amplifier and is usually of small amplitude. Because *electron tubes* and *field-effect transistors* have a high input impedance and a lower output impedance they are usually regarded as voltage amplifiers.

voltage-controlled oscillator (VCO) An oscillator of which the frequency can be controlled by adjustment of an input voltage. Such an oscillator forms part of *phase-locked-loop* systems. The oscillator may be an *LC* type generating a sinusoidal waveform, the frequency being controlled by a varactor connected across the oscillatory circuit. Alternatively it may be an astable *multivibrator* the duration of the unstable state (and hence the free-running frequency) being controlled by the base bias voltage.

voltage-dependent resistor (VDR) A non-linear resistor the resistance of which decreases markedly with increase in applied voltage. The current-voltage relationship for a voltage-dependent resistor is of the form $I = kV^n$ where k is a constant and n lies between 3 and 7. Such resistors are usually of silicon carbide pressed with a ceramic binder into disks or rods and fired at about 1200°C.

voltage divider Same as ***potential divider***.

voltage dropper A ***resistor*** connected in series with a power supply to drop the voltage applied to the load to a desired value. An example occurs in radio and TV receivers where the electron-tube heaters are connected in series. Where the total heater voltage is less than the mains voltage a resistor is inserted in the circuit to act as a voltage dropper. From Ohm's law the required resistor value is given by (volts to be dropped)/current.

voltage feedback A system in which the negative feedback signal is directly proportional to the voltage across the load. Frequently the feedback signal is derived from a potential divider connected across the load as shown in *Figure V.4*, the potential divider having a total resistance large compared with the load value. The effect of voltage negative feedback is to improve linearity, decrease gain and to decrease the effective output resistance of the ***active device*** driving the load, i.e. it tends to make this device a constant-voltage source.



Figure V.4 Basic principle of voltage feedback

voltage gain Of an ***active device*** or amplifier the ratio of the output voltage to the input voltage. Where the voltage gain depends on the value of the load resistance it is necessary to specify the load value when the voltage gain is quoted. The gain may be expressed as a ratio or in decibels as $20 \log_{10} V_{out}/V_{in}$.

voltage gradient In a ***conductor*** the difference in potential per unit length. In an electric field the difference in potential per unit distance along the normal to the lines of force at the point in question.

voltage level See ***level***.

voltage-multiplier rectifier A combination of ***rectifiers*** and ***capacitors*** which produces an output voltage approximately equal to an exact multiple



Figure V.5 A voltage-doubler rectifier

of the peak value of the alternating input voltage. As an example *Figure V.5* gives the circuit diagram for a voltage doubler. When D_1 conducts C_1 is charged to the peak value of the alternating input. On the next half cycle D_2 conducts and C_2 is also charged to the peak value of the input. C_1 and C_2 are connected in series and their voltages add so yielding an output voltage equal to twice the peak value of the alternating input.



Figure V.6 A voltage-multiplier rectifier

By using a circuit of the type shown in *Figure V.6* it is possible to obtain an output of n times the peak value of the input voltage where *n* is the number of rectifiers (and the number of capacitors) employed. The particular example illustrated is, of course, a voltage tripler.

voltage-reference diode A semiconductor device which when carrying a current within a specified range develops across its terminals a particular voltage of specified accuracy which can be used for reference purposes.

The device consists of two ***Zener diodes*** connected in series back-to-back as indicated in the graphical symbol shown in *Figure V.7.* If the applied voltage has the polarity shown here and is increased sufficiently, diode D_1 is reverse biased and breaks down at its Zener voltage, D_2 being forward biased and so acting as a low-value series resistor. D_1 has a positive temperature coefficient and D_2 is designed to have an equal



Figure V.7 Graphical symbol for a voltage-reference diode

negative coefficient so that the device as a whole has a breakdown voltage independent of temperature provided the bias current through the device is maintained constant.

voltage-reference tube A cold-cathode gas-filled tube which when carrying a current within a specified range develops across its terminals a particular voltage of specified accuracy which can be used for reference purposes.

voltage-regulator circuit See ***regulation***.

voltage-regulator diode A ***Zener diode*** used for voltage regulation. A simple circuit is shown in *Figure V.8*. The supply voltage must exceed the ***Zener breakdown*** voltage so that the voltage across the diode is at breakdown value. The series resistor R_S is so chosen that even when the load takes its maximum current there is still some current through the diode so maintaining the voltage across it at the Zener value.



Figure V.8 Simple voltage-regulator circuit using a Zener diode

voltage-stabiliser circuit See ***stabilisation***.

voltaic cell A cell in which chemical action takes place between two electrodes of different materials immersed in an electrolyte and gives rise to an EMF between the electrodes.

voltmeter An instrument for indicating or recording the magnitude of a voltage in volts. For high voltages the measurement may be in kilovolts (kV) and for small voltages in millivolts (mV) or microvolts (µV). The resistance of a voltmeter must be high so that, when connected across a circuit, it takes negligible current and so has little effect on the voltage being measured.

volume (1) See ***programme volume***. (2) In some computers ***volume*** refers to a storage medium. This might be a ***floppy disk*** or a whole ***hard disk*** or a ***partitioned*** area on a ***hard disk***.

volume compression See ***compression***.

volume expansion See ***expansion***.

volume indicator or **volume meter** See ***programme meter***, ***VU meter***.

volume unit A transmission unit for measuring programme volume. For a sinusoidal signal one volume unit equals one decibel. The VU meter is calibrated in volume units.

von Neumann's principle John von Neumann can be regarded as the father of the modern computer because it was he who in 1944 suggested that the program should be stored electronically within the computer itself so that it could be executed at a speed limited only by that of the logic circuits of the computer. Internal storage also meant that the program could be modified as a result of processing. Hitherto the program had been stored externally on cards or tape and was fed into the computer at low speed. 'Stored program control' is thus the essence of von Neumann's principle.

VU meter A ***voltmeter*** for measuring programme volume. It consists of a moving-coil instrument of a specified type fed from a bridge rectifier which is, in turn, fed from the programme line via a series resistor. Unlike the ***peak programme meter*** the VU meter needs no source of power for its operation other than the signal input. The VU meter measures the total energy of the input signal and not the peak value and its scale is markedly non-linear. It is, however, less expensive than the peak programme meter and is extensively used for measuring programme volume particularly in audio tape recording.

W

wafer (1) A thin layer of insulating material carrying switch contacts. Complex switches often consist of several wafers operated by a common control. (2) A thin slice of semiconductor material which, after treatment, becomes a multiplicity of ***planar transistors*** or of ***integrated circuits***.

wafer loudspeaker (1) A ***moving-coil loudspeaker*** with very little depth designed for use in portable receivers or cars. The small depth is achieved by mounting the magnet within the conical diaphragm. (2) A piezo-electric ***tweeter*** with very little depth.

walkie-talkie A colloquial term for a portable ***transceiver***.

water cooling Of a high-power ***electron tube*** a method of removing heat by pumping water through a jacket or tubing in direct contact with the external anode or collector, the water giving up the acquired heat in an air-cooled heat exchanger outside the equipment.

Watt The unit of electrical power, symbol W or VA. Practical power values in electronics range from many kilowatts (kW or kVA) through milliwatts (mW) to microwatts (μW).

wave A disturbance propagated through a medium or through space. The disturbance can be, for example, the longitudinal mechanical displacement of a material medium constituting a sound wave or the variations in the transverse magnetic and electric fields constituting a radio wave. The graphical representation of such a disturbance is also termed a wave.

wave analyser Same as ***harmonic analyser***.

waveband A frequency range in the electromagnetic spectrum allocated to a specific radio service. For example the range 525 kHz to 1.6 MHz approximately, known as the medium waveband, is devoted to amplitude-modulated broadcasting.

waveform The shape obtained by plotting the instantaneous amplitude of a varying quantity against time in rectangular coordinates. The waveform of a signal can also be displayed on an oscilloscope by applying the signal to the Y plates and a time base to the X plates.

waveguide In general a system of boundaries between materials or media of different refractive index capable of guiding electromagnetic waves. Thus a length of solid dielectric can act as a waveguide, the wave being propagated along it by successive reflections at the walls. The most familiar type of waveguide is, however, the hollow conducting tube, usually of rectangular cross section. There are various modes of propagation within waveguides and the wave may be launched in it or abstracted from it by a probe or a loop projecting into the waveguide. For efficient propagation the cross-sectional dimensions must not be less than half a wavelength and thus to keep the cross section to a reasonable size the frequency of the elctromagnetic waves must be high: it is usually in the microwave region.

wavelength (λ) Of a periodic wave the distance between points of equal phase in consecutive cycles measured at any instant in the direction of propagation of the wave. It is equal to the distance travelled by the wave in one period of oscillation. For electromagnetic waves the wavelength λ is related to the frequency f by the expression

$$\lambda = \frac{v}{f}$$

where v is the velocity of propagation. Thus a frequency of 1 MHz corresponds to a wavelength of 300 m, the velocity of propagation being 3×10^8 m/s.

wavemeter Instrument for measuring the wavelength of an electromagnetic wave either directly or, more usually, indirectly by measuring the frequency. See ***absorption frequency meter***.

wavetrap Same as ***rejector circuit***.

weighting The modification of objective measurements for example to obtain better correlation with subjective assessments. As an example audio noise measurements may be made via a frequency-discriminating (weighting) network which allows for the way in which the annoyance value of noise varies with frequency over the audio band.

Weston cadmium cell A standard ***primary cell*** with electrodes of mercury (positive) and cadmium-mercury amalgam (negative), electrolyte of cadmium sulphate and depolariser of mercurous sulphate. The EMF is 1.108 V at 20°C and the variation of EMF with temperature is known to a high degree of accuracy. See ***standard cell***.

What You See Is What You Get (WYSIWYG) A term sometimes used to describe computer graphics and DTP applications in which the VDU display accurately (within its capabilities) represents the printed output.

Wheatstone's bridge A ***network*** of four ***resistors*** in bridge formation used for the measurement of unknown resistances. The circuit is shown in *Figure W.1*. If the ratio of R_1 to R_2 is the same as that of R_3 to R_4 the PD across R_2 is equal to that across R_4 and the galvanometer gives zero deflection. At balance the following relationship applies



Figure W.1 Wheatstone's bridge circuit



Figure W.2 Wien bridge circuit

$$\frac{R_1}{R_2} = \frac{R_3}{R_4}$$

Thus, if R_1, R_2 and R_3 are known, R_4 can be calculated. R_1 and R_2 are known as the ratio arms.

white compression or **white crushing** In TV, reduction of the gain at signal levels corresponding to white compared with the gain at black and mid-grey levels. The effect of white compression is to reduce the visibility of detail in highlight areas of the reproduced image.

white level In black-and-white TV the maximum permitted level of the picture signal (or, in colour TV, of the ***luminance*** component).

white noise A random noise signal with a level frequency response over a wide frequency range embracing the audible spectrum. Such a noise is used in audio-frequency testing, e.g. of loudspeakers where the noise, which sounds like escaping steam, acquires a coloration if the loudspeaker has resonances. The term is analogous to white light which has components spread over the whole of the visible spectrum.

white peak (US) Same as ***peak white***.

wide area network (WAN) A ***network*** of computers on various premises and requiring the use of telecommunications lines to facilitate the exchange of data. Typically WANs connect ***local area networks*** rather than individual computers, the connection between the LAN and the telecommunications line being by a device called a *bridge* (or *router*).

width control (1) In TV receivers the control which determines the amplitude of horizontal deflection and hence the width of the displayed picture. The control is often a variable inductor connected in series with the line deflection coils. (2) In stereo sound reproduction a control which determines the apparent width of the sound source. It is often a variable resistor bridging the two channels and, in the zero-resistance position, parallels them so that the sound appears to originate from a point source located midway between the two loudspeakers.

Wien bridge An AC bridge circuit in which one arm consists of resistance and capacitance in series, an adjoining arm consists of resistance and capacitance in parallel, the remaining arms being purely resistive. The bridge, shown in *Figure W.2*, is used for measuring capacitance in terms of resistance and frequency. At balance the following relationships apply:

$$\frac{C_1}{C_2} = \frac{R_4}{R_3} - \frac{R_2}{R_1} \qquad C_1C_2 = \frac{1}{\omega^2 R_1 R_2}$$

which give the following expressions for C_1 and C_2

$$C_1^2 = \frac{R_1R_4 - R_2R_3}{\omega^2 R_1^2 R_2 R_3}$$

$$C_2^2 = \frac{R_3}{\omega^2 R_2 (R_1R_4 - R_2R_3)}$$

There is a corresponding Wien inductance bridge.

Wien-bridge oscillator A phase-shift oscillator of which the frequency is determined by the resistance and capacitance values of a Wien-bridge circuit. The network shown in *Figure W.3* consists of two equal resistors and two equal capacitors in a Wien-bridge arrangement. This network gives zero phase shift at the frequency for which



Figure W.3 Frequency-determining network used in Wien-bridge oscillator

$$\omega = \frac{1}{2\pi RC}$$

and at this frequency

$$\frac{v_{out}}{v_{in}} = \frac{1}{3}$$

If therefore an amplifier with zero phase shift and a voltage gain of 3 is connected between the output and input terminals of the network oscillation will result. This is the basis of a number of AF test oscillators. The amplifier gain is stabilised at 3 by negative feedback which can also serve to keep the output level constant. The frequency can be varied by using a two-gang variable capacitor for *C*, *R* being adjusted in steps to give different frequency ranges.

Winchester disk One sort of ***hard disk***. See ***hard disk***.

window An area in a ***VDU display*** dedicated to one application. In a multitasking computer system, several windows may be present simultaneously, which may belong to more than one application. Only one window at a time may be active (it is said to have the *input focus*) and this window will be at the front of the display, hiding areas of other windows which it overlaps.

Windows™ The Microsoft Windows operating environment which provides a ***user-friendly multitasking*** interface with MS-***DOS*** and compatible operating systems.

wire broadcasting The distribution of sound and/or TV programmes to a number of receivers over a wired distribution system using audio frequencies or modulated carrier frequencies.

wired AND Same as ***distributed connection***.

wired OR Same as ***distributed connection***.

wobbulator An RF ***signal generator*** the instantaneous frequency of which can be varied continuously in a known periodic manner over a known fixed or adjustable range without change in amplitude. It is used in conjunction with an oscilloscope to display the shape of the passband of a receiver to facilitate alignment of the tuned circuits.

woofer A loudspeaker unit designed to radiate audio frequencies below approximately 200 Hz. Woofers are usually moving-coil units and are used in conjunction with other units and crossover networks in high-quality wide-range loudspeakers.

word See ***binary word***.

word processor A system for writing, editing, printing and storage of documents. Most word processors are general-purpose ***microcomputers*** or ***minicomputers*** executing word-processing ***programs***. Text typed at the keyboard appears on the screen of a VDU and is also stored in memory. ***Software*** routines allow such facilities as the insertion and deletion of matter, the movement of blocks of text, searches for the occurrence of a particular string of characters (with the option of replacing it by an alternative string) and word counts. A ***hard copy*** of the document may be produced on a printer, formatting routines permitting such features as the centring of titles and justification (straightening) of the right-hand margin.

work function The energy required to emit a single ***electron*** from a ***cathode*** into a field-free space. Its value depends on the material of the cathode.

working point Same as ***operating point***.

working storage Same as ***temporary storage***.

workstation A vague term used in various ways to indicate the data processing or communications equipment needed by one employee at his or her desk. In computing the term is sometimes reserved for specialised high-speed hardware for complex graphics work such as CAD, but the term programmable workstation (PWS) may be applied to any microcomputer being used as an ***intelligent terminal*** to access a mainframe computer. In telecommunications the term is sometimes used to refer to a computer and a telephone on the same desk and sharing the same access to the telecommunications network.

worldwide web A network of linked ***documents*** residing on the ***Internet***.

WORM (Write Once Read Many times) Any ***storage*** system in which data can be written (recorded), but not erased. Consequently the stored data cannot be amended, although an amended version may be stored subsequently elsewhere on the media. The best known WORM system is *CD-recordable* which stores data on ***Compact Disc***. This is used for backing up ***hard drives*** and archiving records of various kinds.

wow Distortion in sound reproduced from disk, film or tape and caused by undesired rhythmic speed variations on recording or reproduction. It is usually caused by eccentric or unbalanced driving of the film, tape or turntable. The variations occur at a rate of less than 20 Hz and cause unpleasant variations in pitch which are particularly noticeable in the reproduction of the piano and of sustained notes.

wrapped connection A method of securing low-resistance contact between a wire and a post by wrapping the wire around a sharp-cornered post under controlled tension using a hand- or power-operated tool. Wrapped connections have been used for twenty-five years and have proved a satisfactory alternative to the soldered connection.

writing In ***computers*** and ***data-processing equipment*** the process of recording information in a storage device or on a data medium. See ***reading***.

writing speed Of a ***cathode ray tube*** the maximum speed at which the spot can travel on the screen whilst still maintaining a required degree of resolution. The more rapidly the spot moves the fainter is the trace generated. Thus there is an upper limit to the speed which can usefully be employed.

X

X amplifier Same as ***horizontal amplifier***.

X-cut crystal A slice of quartz crystal cut at right angles to an *X* axis and parallel to the optic axis. A quartz crystal has the shape of a hexagonal prism and the electric axes (along which the piezo-electric effect is a maximum) pass through the centre and opposite corners of the hexagon as shown in *Figure X.1*. The line through O perpendicular to the plane of the paper is the optic axis of the crystal. The shaded area on the diagram represents an *X* cut. Such slices are used to control the frequency of oscillators, e.g. those used to generate the carrier frequency of radio transmitters, but a disadvantage is that the natural resonance frequency of the slice (determined by its thickness) is temperature dependent so that, for high frequency stability, the temperature of the slice must be controlled within narrow limits.



Figure X.1 Cross section of quartz crystal showing the electric axes by dashed lines: the shaded area represents an *X* cut

X plates See ***deflector plates***.

X rays Electromagnetic radiation of wavelength shorter than approximately 10^{-6} cm. The rays can be generated by directing a stream of high-velocity electrons on to a target of a suitable metal. X rays can affect photographic plates and can ionise gases but probably most applications make use of the fact that X rays can penetrate many substances which are opaque to visible light.

Y

Y amplifier Same as ***vertical amplifier***.

Y-cut crystal A slice of quartz crystal cut at right angles to a *Y* axis and parallel to the optic axis. A quartz crystal has the shape of a hexagonal prism and the *Y* axes (mechanical axes) pass through the centre and the midpoints of opposite sides of the hexagon as shown in *Figure Y.1*. The line through O perpendicular to the plane of the paper is the optic axis of the crystal. The shaded area on the diagram represents a *Y* cut. Such slices are used to control the frequency of oscillators, e.g. those used to generate the carrier frequency of radio transmitters but a disadvantage is that the natural resonance frequency of the slice (determined by its thickness) is temperature dependent so that, for high frequency stability, the temperature of the slice must be controlled within narrow limits.



Figure Y.1 Cross section of a quartz crystal showing the mechanical axes by dashed lines: the shaded area represents a *Y* cut

yoke A piece of magnetic material used to complete a magnetic circuit. The yoke is not itself surrounded by windings but it often acts as a mechanical support for windings as in the deflection coil assembly of a TV ***picture tube***.

y parameters Of a ***transistor***, a method of expressing the electrical characteristics in which the input and output currents are given in terms of the input and output voltages. The two fundamental equations are:

$$i_{in} = y_i v_{in} + y_r v_{out}$$

$$i_{out} = y_f v_{in} + y_o v_{out}$$

where y_i is the input admittance (for short-circuited output terminals); y_o is the output admittance (for short-circuited input terminals); y_r is the reverse transfer admittance and y_f is the forward transfer admittance.

Y plates See ***deflector plates***.

Y signal Same as ***luminance signal***.

Z

Zener breakdown In a reverse-biased pn junction a rapid increase in current which occurs at a particular reverse voltage as a result of the Zener effect. Zener breakdown occurs at a lower reverse bias than ***avalanche breakdown***.

Zener diode A pn diode which exhibits ***Zener breakdown*** or ***avalanche breakdown*** at a specified value of reverse bias and which is therefore used for voltage reference purposes or for voltage stabilisation. The graphical symbol for a Zener diode is given in *Figure Z.1*.



Figure Z.1 Graphical symbol for a Zener diode

Zener effect Conduction through a reverse-biased pn junction caused by spontaneous generation of hole-electron pairs within the inner electron shells of atoms in the junction region. The hole-electron pairs are liberated, not as a result of ionisation by collision (as in avalanche breakdown) but by the intense electric field established across the junction by the reverse bias.

zener voltage The reverse voltage at which ***Zener breakdown*** occurs.

Zenith-G.E. pilot-tone system See ***pilot-tone stereo***.

zero For a ***network*** of pure reactances, any frequency at which the input reactance is zero. As shown in *Figure Z.2* the reactance-frequency relationship for a network of pure reactances is a succession of curves, all with a positive slope, which swing between minus infinity and plus infinity, passing through zero, in a manner similar to that of a tangent curve. The zeros are the frequencies at which the curves pass through zero, i.e. those at



Figure Z.2 Typical reactance-frequency relationship for a network of pure reactances. A, C and E are zeros and B, D and F are poles

which the network presents at its input terminals the equivalent of an inductance and capacitance of equal reactance in series. See ***pole***.

zero frequency (ZF) Synonym for direct current.

Zero Insertion Force (ZIF) socket An ***integrated circuit*** socket especially designed to allow integrated circuits to be inserted and removed quickly and easily and with minimal risk of damage to the pins. A clamping mechanism ensures that the i.c. is held securely in place, its pins making proper electrical connection with their respective sockets. A lever must be operated to release the clamp and allow the i.c. to be changed. ZIF sockets are used in equipment in which i.c.s are changed frequently, e.g. i.c. test equipment and EPROM writing equipment.

zero level See ***reference level***.

zone refining Method of purifying semiconductor material which depends on the fact that impurities are more soluble in the molten material than in the solid material. An ingot of the material is moved slowly through the coils of an RF induction heater so that, in effect, a molten zone travels the length of the ingot. By repeatedly passing the ingot through the coils in the same direction in an inert atmosphere the impurities can be concentrated at one end of the ingot and the other end can be made pure enough for use in semiconductor device manufacture.

zooming In computing, especially ***graphics*** and ***desktop publishing applications***, changing the magnification factor of the ***VDU*** display. Zooming in gives an enlarged display of a small area, revealing fine detail in graphics or making small print more legible. Zooming out allows the whole of a large page to be visible on screen at once; although detail is lost, the overall composition of the page can be assessed. Most applications offer a useful range of zoom settings.

z parameters Of a ***transistor***, a method of expressing the electrical characteristics in which the input and output voltages are given in terms of the input and output currents. The two fundamental equations are:

$$v_{in} = z_i i_{in} + z_r i_{out}$$

$$v_{out} = z_f i_{in} + z_o i_{out}$$

in which z_i is the input impedance, z_o the output impedance, z_f the forward transfer impedance and z_r the reverse transfer impedance. These parameters are not greatly favoured largely because of the difficulty of measuring them and the ***hybrid parameters*** or ***y parameters*** are preferred.

APPENDIX: ELECTRONICS ABBREVIATIONS AND ACRONYMS

© G. W. A. Dummer

The abbreviations and acronyms in this book have been selected from many current sources—books, technical articles, papers and theses—and also from knowledgeable colleagues. Obviously it is not possible to list every acronym from specialised categories, but those in this book have been selected on the basis of their application to present-day electronics.

In the following list acronyms are usually shown in capitals and abbreviations in lower case, except where established usage directs otherwise. Full stops are not shown. Please note that individual writers, publishers and organisations may follow different conventions regarding the use of capitals and full stops in acronyms and abbreviations. For the purposes of alphabetical order Greek letters are regarded as variants of their Latin equivalents.

AC	alternating current
AAL	ATM adaptation layer
AALA	American Association for Laboratory Accreditation
ABR	auxiliary bus resonator
ABR	available bit rate
ACAST	Advisory Committee on the Application of Science and Technology to Development
ACC	automatic chrominance control
acc	accumulator
ACIA	asynchronous communication interface adapter
ACK	acknowledge
ACR	attenuator to crosstalk ratio
ACU	automatic clearing unit
A-D	analogue to digital
ADA	computer language (named after Ada Augusta)
ADC	analogue-to-digital converter
ADCCP	advanced data communication control procedure
ADDER	automatic digital data error recorder
ADF	automatic direction finder
ADP	automatic data processing
ADPCM	adaptive differential pulse code modulation

ADPCU	adaptive differential pulse conditioning unit
ADS	address data strobe
ADSL	asychronous digital subscriber line
ae	aerial
AEA	American Electronics Association
AES (USA)	Audio Engineering Society
AES	auger electron spectroscopy
AES	auto-electronic separator
AEW	airborne early warning
AF	audio frequency
AFC	automatic frequency control
AFM	atomic force microscopy
AFIPS	American Federation of Information Processing Societies
A/G	air to ground
AGC	automatic gain control
AHDL	analog hardware descriptive language
AHS	after-hours sync
AI	artificial intelligence
AIA (USA)	Automated Imaging Association
AIM	avalanche-induced migration
AIRCOMNET	Air Force Command and Administrative Network
ALC	automatic level control
ALD	automatic location device
ALGOL	ALG-orithmic computer language
ALT	radio altimeter
ALU	arithmetic/logic unit
AM	amplitude modulation
AMLCD	active-matrix liquid crystal display
AMPS	advanced mobile phone system
AND	automatic network dialling
ANI	automatic number identification
ANSI	American National Standards Institute
ant	antenna
AOI	AND/OR invert
AOI	automated optical inspection
APA	all points addressable
APC	aperiodic choke
APCM	adaptive pulse code modulation
APD	avalanche photo-diode
API	application programming interface
APL	a programming language developed by Iverson
APPC	advanced program-to-program communications
APPS	automatic parts programming system
APU	arithmetic processor unit

AQL	acceptable quality level
ARB	all routes busy
ARC	adaptive response control
ARINC	Aeronautical Radio, Inc.
ARL	acceptable reliability level
ARP	address resolution protocol
ARPA	Advanced Research Project Agency (Department of Defense)
ARQ	automatic repeat request
ARPANET	Advanced Research Project Agency Network
ARRL	American Radio Relay League
ARU	acoustical resistance unit
ASA	American Standards Association
ASA	Army Security Agency
ASCII	American Standard Code for Information Interchange
ASD	adaptive signal discriminator
ASET	Association of Super-Advanced Electronic Technologies
a-Si	amorphous silicon
ASIC	application specific integrated circuits
ASM	assembler
ASNT	American Society for Non-destructive Testing
ASR	automatic send/receive
ASSOC	application-specific optical chip
ASPR	automatic satellite position reporting system
ASQC	American Society of Quality Control
ASTE	American Society of Test Engineers
ASTM	American Society for Testing and Materials
AT	advanced technology
ATAB	area-array tape automated bonding
ATAPI	advanced technology attachment packet interface
ATC	address translation cache
ATDM	asynchronous time-division multiplexing
ATE	automatic test equipment
ATLAS	abbreviated test language for avionic systems
ATM	asynchronous transfer mode
ATPG	automatic test program generator
ATS	automatic test system
AT & T	American Telephone and Telegraph Company
ATU	aerial (or antenna) tuning unit
ATX	automatic telex exchange
aux	Auxiliary
AV	audio-visual
AVC	automatic volume control
AWACS	Airborne Warning and Control System

AWG	American Wire Gauge
BABS	beacon approach, beacon systems
BABT	British Approvals Board Telecommunications
BALUN	balanced-to-unbalanced transformer
BARRITT	barrier controlled injection and transit time (diode)
BASIC	beginners all-purpose symbolic instruction code
BBC	British Broadcasting Corporation
BBD	bucket-brigade device
BBS	bulletin board system
BCCD	buried-channel charge-coupled device
BCD	binary-coded decimal
BCD	bipolar C-MOS D-MOS
BCH	an FEC parity coding scheme
BCI	bit count integrity
BCS	binary synchronous communication
BCS	British Computer Society
BDOS	basic disk operation system
BDPSK	binary differential phase shift keying
BER	bit error rate
BFO	beat frequency oscillator
BGA	ball grid array
BICMOS	bipolar complementary metal oxide semiconductor
BIFET	bipolar field effect transistor
BIOS	basic input/output system
BIPM	International Bureau of Weights and Measures
BIST	built-in self-test
BIT	built-in test
bit	binary digit
BITE	built-in test equipment
BJT	bipolar junction transistor
BLAISE	British Library Automated Information Service
B-LD	bi-stable laser diode
BMEWS	Ballistic Missile Early Warning System
BMFT	Bundes Ministerium für Forschung und Technologie
BNC	type of co-axial connector
BORAM	block-oriented random-access memory
BP	band pass
BPS	bits per second
BPSK	binary phase-shift keying
BS	backing store
b/s	bits per second
BSB	British Satellite Broadcasting Ltd
BSC	bisynchronous or (binary synchronous) communications

BSDL	boundary scan descriptive language
BSI	British Standards Institute
BTAB	bumped tape automated bonding
BW	bandwidth
byte	8 bits
C	type of co-axial connector
CAAP	co-processor architecture and protocols
CAD	computer-aided design
CAE	computer assisted engineering
CAI	computer aided instruction
CAL	computer assisted learning
CAM	computer aided manufacturing
CAM	content-addressable memory
CAMAC	computer automated measurement and control
CAMEL	Chalmers Advanced Microelectronics Lab., Sweden
CAP	carrier amplitude phase
CAS	column address select
CAS	cordless access service
CASE	computer-aided software engineering
CAT	computer aided testing
CATT	controlled avalanche transit time (diode)
CATV	community antenna television
CAW	common aerial working
CB	cellular broadcast
CB	citizens band (radio)
CBIC	complimentary bipolar integrated circuit
CBR	constant bit rate
CBT	computer based training
CBT	computer-based terminal
CCD	charge-coupled device
CCE	computer controlled equalisation
CCIA	Computer and Communications Industries Association
CCIF	International Telephone Consultative Committee
CCIR	International Radio Consultative Committee
CCITT	International Telegraph and Telephone Consultative Committee
CCTS	Co-ordinating Committee on Satellite Communications
CCTT	cold-cathode trigger tube
CCTV	closed-circuit television
CD	compact disc
CDC	compiler object code
CDI	collector-diffusion isolation
CD-I	compact disc interactive

CDMA	code-division multiple access
CDM	charged-device model
CDU	central display unit
CD-R	compact disc recordable
CD-ROM	compact disc read-only memory
CD-RW	compact disc rewritable
CEEFAX	BBC teletext service
CEMA	Canadian Electrical Manufacture Association
CEN	European Committee on the Co-ordination of Standards
CENEL	European Electrical Standard Co-ordinating Committee
CERDIP	ceramic dual-in-line package
CERN	European Particle Physics Laboratory, Geneva
CESA	Canadian Engineering Standards Association
CFC	chlorofluorocarbon
CFD	computational fluid dynamics
CFR	constant failure rate
CGA	Colour/Graphics Adapter
CGI	common-gateway interface
CH	chain home (radar)
CHL	chain home low (radar)
CIRM	International Marine Radio Association
CISC	complex-instruction-set computer
CISPR	International Special Committee on Radio Interference
CIRC	cross-interleaved Reed-Soloman code (for CDs)
CLCC	ceramic leaded chip carrier
CLOS	common LISP object system
CLS	clear screen display
CML	current-mode logic
CMM	compatibility maturity model
CMO	common-mode operation
CMOS	complementary metal-oxide-semiconductor
CMP	chemical mechanical polishing
CMR	common-mode rejection
CMRR	common-mode rejection ratio
CMV	common-mode voltage
CMVR	common-mode voltage ratio
CNRS	Centre Nationale de la Recherche Scientifique (the French National Science Foundation)
COB	chip on board
COBOL	common business-oriented language
codec	coder-decoder
COFDM	common orthogonal frequency-division multiplexing
COMP	compiler
COMSAT	communications satellite corporation

CORBA	common object-request-broker architecture
COTS	commercial off-the-shelf
CPC	crucially permutable code
CPI	characters per inch
CPM	continuous phase modulation
CPM	control program for microcomputers
CPP	Consultative Panel on Public Information (United Nations)
CPS	characters per second
CPU	central processing unit
CPW	co-planar waveguide
CQ	call to all stations
CR	carriage return
CRC	cyclic redundancy check
CRM	cyclic redundancy model
CROM	control read-only memory
CRO	cathode-ray oscilloscope
CRT	cathode-ray tube
CSA	carrier service area
CSMA/CD	carrier-sense multiple access collision detector
CSN	common services network
CSP	chip scale packaging
CT	cordless telecommunications
CTD	charge transfer device
CTE	coefficient of thermal expansion
CTL	complementary transistor logic
CTS	clear to send
CU	control unit
CVBS	composite video blanking and sync
CVD	chemical vapour deposition
CW	continuous wave

D-A	digital to analogue
DAB	digital audio broadcasting
DAC	digital-to-analogue converter
DACS	Data and Analysis Centre Software
DAL	data access line
DAP	distribute array processor
DAQ	data acquisition
DARPA	Defense Advanced Research Project Agency
DART	dual asynchronous receiver/transmitter
DAS	data acquisition system
DASM	direct access storage medium
DAT	digital audio tape
DAVIC	Digital Audio-Visual Council

DAVID	digital audio-video interactive decoder
dB	decibel
dBi	decibels related to an isotropic antenna
dBm	decibels related to 1 mW
dBw	decibels related to 1V into 600 Ohm
DBMS	database management system
DBPSK	differential-binary phase-shift keying
DBS	direct-broadcasting satellite
DC	direct current
DC	don't care
DCA	Defense Communications Agency
DCA	direct chip attach
DCE	data communications equipment
DCS	digital cellular service
DCS	digital communication system
DCTE	data circuit termination equipment
DCTL	direct-coupled transistor logic
DD	disk drive
DDD	direct distance dialling
DDL	data description language
DECT	digital enhanced cordless communications
DECT	digital European cordless communications
DES	data encryption standard
DEW	distant early warning
DF	direction finding
DFA	digital fault analysis
DFM	design for manufacturability
DFT	design for test
DFT	discrete Fourier transform
DGAC	data generation and acquisition circuit
DI	dielectric isolation
DIANE	Direct Information Access Network for Europe
DIN	Deutsches Industrie Normale (German Standards Institute)
DIL	dual-in-line
DIP	dual-in-line package
DIP	dual-in-line plastic
DMA	direct memory access
DMAC	direct memory access control
DMD	depletion-mode device
DMM	digital multimeter
D-MOS	double-diffused metal-oxide semiconductor
DMS	dynamic mapping system
DMUX	demultiplexer
DNA	digital network architecture

DNS	domain name service
DOA	direction of arrival (signal)
DOS	disc operating system
DP	data processing
DPCM	differential pulse-code modulation
DPDT	double-pole double-throw (switch)
DPE	data processing equipment
DPEK	differential phase-exchange keying
DPM	digital panel meter
DPSK	differential phase-shift keying
DPU	display processing unit
DQA	design quality assurance
DQPSK	differential quadrature phase-shift keying
DR	data rate
DRAM	dynamic random access memory
DS	direct sequence (in spread spectrum systems)
DSB	double sideband (transmission)
DSBSC	double-sideband suppressed carrier
DSBTC	double sideband transmitted carrier
DSDD	double-sided double-density
DSC	direct satellite communication
DSCC	double silk-covered copper
DSIR	Department of Scientific and Industrial Research (UK)
DSL	digital subscriber line
ΔΣM	delta sigma modulation
DSN	deep space network
DSP	digital signal processing
DSP	data signal processor
DSSC	double-sideband suppressed carrier
DSSD	double-sided single-density
DSTC	double-sideband transmitted carrier
DTE	data terminal equipment
DTF	dynamic track following
DTL	diode/transistor logic
DTMF	dual-tone multiple-frequency
DTP	desktop publishing
DTT	digital terrestrial television
DTV	digital television
DUT	device under test
DVB	digital video broadcasting
DVD	digital versatile disc
DVD	digital video disc
DVD-RAM	digital versatile disc random-access memory
DVM	digital voltmeter

DWDM	dense wave division multiplexing
DX	duplex
EAN	European Article Number
EAROM	electrically alterable read-only memory
EBCDIC	extended binary code decimal interchange code
EBIM	electron beam induced current
EBL	electron beam lithography
ECCM	electronic counter-counter measures
ECL	emitter-coupled logic
ECM	electronic counter measures
ECMA	European Computer Manufacturers Association
ECO	electron-coupled oscillator
EDA	electronic design automation
EDC	error detecting code
EDCC	error detection/correction code
EDP	electronic data processing (or processor)
EEPROM	electrically erasable and programmable read-only memory
EEROM	electrically erasable read-only memory
EFL	emitter follower logic
EFM	eight-to-fourteen modulation
EFT	electrical fast transient
EGA	enhanced graphics adaptor
EHF	extremely high frequency
EIA	Electronic Industries Association
EIAJ	Electronic Industries Association of Japan
EIDE	enhanced integrated drive electronics
EIRP	effective isotropic radiated power
ELF	extremely low frequency (< 3 kHz)
ELN	extra-low noise
ELS	electrostatic loudspeaker
EMC	electromagnetic capability
EMD	enhancement-mode device
EMF	electromagnetic field (or force)
EMI	electromagnetic interference
EMP	electromagnetic pulse
EMR	electromagnetic radiation
EMS	energy management system
EMT	electrical module test
EMU	electromagnetic unit
ENG	electronic news gathering
EO	erasable optical
EOC	end of conversion
EOD	end of data

EOF	end of file
EOM	end of message
EOS	electrical overstress
EOT	end of text
EOT	end of transmission
EPLD	erasable programmable logic device
EPOS	electronic point of sale
EPS	encapsulated PostScript
EPG	electronic programme guide
EPM	equipment performance monitoring
EPROM	erasable programmable read-only memory
EPSRC	Engineering and Physical Sciences Research Council
ERCIM	European Research Consortium for Information and Mathematics
ERDA	Elastic Recoil Detection Analysis
EROM	erasable read-only memory
ESA	European Space Agency
Esc	escape
ESD	electrostatic discharge
ESDA	electronic system design automation
ESL	essential service line
ESPRIT	European Strategic Programme for Research and Development in Information Technology
ESR	equivalent series resistance
ESREF	European Symposium on Reliability of Electronic Devices, Failure Physics and Analysis
ESS	electronic switching system
EST	echo suppressor terminal
ESTEC	European Space Research and Technology Centre
ETA	estimated time of arrival
ETD	estimated time of departure
ETS	European Telecommunications Standards
ETS	equivalent time sampling
ETSI	European Telecommunications Standards Institute
EUREKA	European Research and Co-ordination Agency
EUT	equipment under test
eV	electron Volt
EXTND	extended data transfer

F	Farad
FA	failure analysis
FAA	Federal Aviation Authority
FAB	fabrication automation bay
FAMOS	floating-gate avalanche metal-oxide semiconductor

FAMOX	floating-gate avalanche-rejection semiconductor
FAT	file allocation table
fax	facsimile
FC-AL	fibre channel-automated loop
FCD	file control block
FCC	Federal Communication Commission
FCFS	first come first served
FD	fully depeleted (Silicon)
FDC	floppy disc controller
FDD	floppy disc drive
FDDI	fibre-distributed data interface
FDM	frequency-division multiplex
FDMA	frequency-division multiple access
FDTD	finite difference time domain
FEC	forward error correction
FED	field emission display
FEK	frequency exchange keying
FEN	far end noise
FET	field effect transistor
FEXT	far end cross talk
FFT	fast Fourier transform
FG	frame ground
FH	frequency hopping (in spread-spectrum systems)
FIB	focussed ion beam
FIFO	first in, first out
FIMBE	focussed ion beam molecular beam epitaxy
fit	failure rate, one in 10^9 hours
FIT	failure in time
FKE	Institute for Solid-State Electronics (Austria)
FM	frequency modulation
FMEA	failure mode effects analysis
FO	fibre optic
FOC	fibre optic communications
FORTRAN	formula translator (programming language)
FOT	fibre optic transmission
FP	flat pack
FP	floating point
FPGA	field-programmable gate array
FPLA	field-programmable logic array
FPMCM	field-programmable multi-chip module
F-PROM	field-programmable read-only memory
FRAM	high-density, sub-micrometer ferroelectric memory
FSK	frequency shift keying
FSM	frequency shift modulation

FTMIS	floating-gate tunnel-metal-insulator semiconductor
FTP	file transfer protocol (Internet)
FTTH	fibres to the home
FX	effects
FX	foreign exchange
GaAs	gallium arsenide
GaAlAs	gallium aluminium arsenide
GATT	General Agreement on Tariffs and Trade
GB	grid bias
Gbyte	gigabyte (= 1024 Mbytes)
GCC	Global Climate Coalition (Washington, D.C.)
GCI	ground-controlled interception
GDI	graphics device interface
GDP	graphic display processor
GDS	graphic data system
GEE	grid navigation system (radar)
GF	ground fixed
GIGO	garbage in, garbage out
GIF	graphic image file
GIF	graphics interchange format
GL	gun laying (radar)
GM	ground mobile
GMPCS	global mobile positioning communications by satellite
GOP	group of pictures (motion comprehension)
GP	general purpose
GPIB	general-purpose interface bus
GHz	gigaHertz
GP	general purpose
GPIS	general-purpose interface bus
GPS	global positioning system (satellite)
GSM	global system for mobile communications
GUI	graphical user interface
HASS	highly accelerated stress testing
HAST	highly accelerated stress test
HALT	highly accelerated life testing
HBT	heterojunction bipolar transistor
HCMOS	highly scaled high-speed MOS
HCP	hard copy printer
HD	hard disc
HDI	high-density interconnect
HDL	hardware description language
HDLC	high-level data link control

HDMOS	high-density metal oxide semiconductor
HDSL	high-bit-rate digital-subscriber line
HDSS	holographic data storage system
HDT	high-density interconnect
HDTV	high-definition television
HEMT	high-electron-mobility transistor
hex	hexadecimal
HF	high frequency
HFC	high-frequency choke
HIC	hybrid integrated circuit
HiNIL	high noise-immunity logic
HIPPA	high-performance parallel interface
HITFET	highly-integrated temperature-protected FET
HLL	high-level language
HLL	high-level logic
H-MOS	high MOS
HSM	hermetically-sealed microcircuit
HTL	high-threshold logic
HTML	hypertext markup language
HTTP	hypertext transfer protocol
HUD	head-up display
HV	high voltage
Hz	Hertz

IAEA	International Atomic Energy Agency
IANA	Internet Assigned Numbers Agency
IARU	International Amateur Radio Union
IATA	International Air Transport Association
IBA	International Broadcasting Authority
IBE	ion beam etching
IBM	International Business Machines
IC	integrated circuit
ICAO	International Civil Aviation Organisation
ICE	in-circuit emulator
ICL	International Computers Limited
ICPO	International Criminal Police Organisation (Interpol)
IDE	integrated drive electronics (interface)
IDL	interface definition language
IDPM	Institute of Data Processing Management
IDS	input-data strobe
IDX	integrated digital exchange
IEC	infused emitter coupling
IEC	International Electrotechnical Commission
IEC	Interzonal Electrotechnical Commission

IEE	Institution of Electrical Engineers (UK)
IEEE	Institute of Electrical and Electronics Engineers (USA)
IEMP	International Electronics Manufacturing Technology (Symposium)
IERE	Institution of Electronic and Radio Engineers
IES	Institute of Environmental Sciences (USA)
IF	intermediate frequency
IFAC	International Federation of Automatic Control
IFF	identification, friend or foe
IFH	Institüt für Hochfrequenztechnik (Darmstadt)
IGBT	insulated-gate bipolar transistor
IGFET	insulated-gate field-effect transistor
ILB	Inner Lead Bonding
I^2L	integrated-injection logic
ILS	instrument landing system
IMAPS	International Microelectronics Assembly and Packaging Society
IMF	infant mortality factor
IMP	interconnected mesh power system
IMPATT	impact avalanche transit time (diode)
InP	indium phosphide
I/O	input/output
IOP	input/output processor
IP	Internet protocol
IPC	Institute for Interconnecting and Packaging Electronics Circuits (USA)
IPs	intermodulation products
IPL	initial program loader
IR	infra-red radiation
IRD	integrated receiver/decoder
IRE	Institute of Radio Engineers (USA) (now IEEE)
IRQ	interrupt request
ISA	industry-standard architecture (PC Bus)
ISA	Instrument Society of America
ISAM	indexed sequential access method
ISB	independent sideband (transmission)
ISCC	international service co-ordination standard
ISD	international subscriber dialling
ISDN	integrated services digital network
ISDT	integrated services digital terminal
ISDX	integrated services digital exchange
ISFET	ion-sensitive field-effect transistor
ISHM	International Society for Hybrid Microelectronics
ISL	integrated Schottky logic

ISMC	International Society for Measurement and Control
ISO	International Standards Organisation
ISOC	International Service Co-ordination Centre
ISP	Internet service provider
ISPBX	Integrated Services Private Branch Exchange
ISV	independent software vendor
IT	information technology
ITE	international telephone exchange
ITU	International Telecommunications Union

JAN	joint army/navy
JCL	job control language
JEDEC	Joint Electron Device Engineering Council
JEMIMA	Japan Electric Measuring Instruments Manufacturers' Association
JESSI	Joint European Submicron Silicon Project
JFET	junction field-effect transistor
JI	junction isolation
JPCA	Japanese Printed Circuit Board Association
JPCD	just-perceptible colour difference
JPEG	Joint Photographic Experts Group
JUGFET	junction-gate field-effect transistor
JVM	Java Virtual Machine

K	kilOhm
KBD	keyboard
kbit	kilobit
kbyte	kilobyte
KGD	known-good die
kHz	kiloHertz
kΩ	kilOhm
kR	kilOhm
KSR	keyboard send/receive
kV	kiloVolt

LAN	local area network
LAP	link access procedure
LAP	line access point
LAPUT	light-activated programmable unijunction transistor
LARAM	line-addressable random-access memory
LASCR	light-activated silicon controlled rectifier
LASER	light amplification by stimulated emission of radiation
LCA	life cycle analysis
LCC	leaded chip carrier

LCD	liquid crystal display
LDM	limited-distance modem
LEC	light energy converter
LED	light-emitting diode
LEED	low-energy electron diffraction
LF	low frequency (30 kHz to 300 kHz)
LFSR	linear-feedback shift register
LGA	lead-grid array
LIC	linear integrated circuit
LIFO	last in, first out
LLCC	leadless chip carrier
LLD	lightly doped drain
LMDS	local multipoint distribution service
LMM	Laboratoire de Microstructures et de Microélectronique
LMWS	licensed millimetre wave service
LNA	low-noise amplifier
LNB	low-noise block
LNR	low-noise receiver
LO	local oscillator
LOCMOS	locally oxidised CMOS
LORAN	long-range air navigation
LOS	line-of-sight
LP	line printer
LP	long play (gramophone record)
LPCVD	low-pressure chemical vapour deposition
LPE	liquid-phase epitaxy
LPM	library of parameterised modules
LPTTL	low-power transistor/transistor logic
LPTV	low-power television
LRL	logical record length
LRU	least replacement unit
LRU	line replacement unit
LS	lower sideband
LSB	least significant bit
LSD	least significant digit
LSI	large-scale integration
LT	low tension
LUF	lowest usable frequency
LUT	look-up table
LZW	Lempel-Ziv-Welsh (compression)

M	megOhm
mA	milliAmp
µA	microAmp

Mac	Macintosh
MAC	multiply-accumulate
MADT	micro-alloy diffused transistor
MAP	manufacturing automatic protocol
MAP	minimum acceptable performance
MAR	memory address register
MAR	mercury arc rectifier
MASER	microwave amplification by stimulated emission of radiation
MASTER	multimedia-aids-teleconferencing
MATV	master antenna TV
MBA	multiple-beam antenna
MBE	molecular beam epitaxy
Mbit	megabit
MBR	master boot record
MBR	memory buffer register
Mbyte	megabyte
MCM	multi-chip module
MCM-C	multi-chip module - ceramic dielectric
MCM-D	multi-chip module - organic dielectric
MCM-L	multi-chip module - laminate
MCM-Si	multi-chip module - silicon substrate
MCR	minimum cell rate
MCT	mobile communications terminal
MCU	microcontroller (unit)
MDS	microprocessor development system
MEDIA	Microelectronics Development for European Applications
MEMS	microelectromechanical systems
MESFET	metallised-semiconductor field-effect transistor
MF	medium frequency (300 kHz to 3 MHz)
µF	microFarad
MFD	microFarad
MFLOPS	millions of floating-point instructions per second
MFP	mini flat pack
MFSK	multi-frequency shift keying
MHL	microprocessor host loader
MHz	megahertz
MIC	microwave integrated circuit
MIDI	musical instrument digital interface
MIMD	multiple instruction, multiple data
MIME	multipurpose Internet mail extensions
MIN	multistage interconnection networks
MIPS	millions of instructions per second
MIS	metal oxide/silicon

MISD	multiple instruction, single data
MLA	microprocessor language assembler
MLB	multilayer board
MLE	microprocessor language editor
MLE	maximum likelihood estimation
MLS	microwave landing system
MMDS	multichannel, multipoint distribution system
MMDS	multipoint microwave distribution system
MMF	magnetomotive force
MMI	man/machine interface
MMIC	monolithic microwave integrated circuit
MMU	memory management unit
MMX	multimedia extensions
MNCS	multipoint network control system
MNOS	metal nitride oxide semiconductor
MΩ	megOhm
modem	modulator/demodulator
MODHIC	modular hybrid integrated circuit
MOS	metal oxide semiconductor
MOSFET	metal oxide semiconductor field-effect transistor
MOST	metal oxide semiconductor transistor
µP	microprocessor
MPEG	Motion Picture Experts Group
MPU	microprocessor unit
MPX	multiplex
MR	magnetorestrictive
MR	megOhm
MSB	most significant bit
MSC	mobile switching centre
MSD	most signicant digit
MS DOS	Microsoft Disk Operating System
MSI	medium-scale integration
MSIN	multistage interconnection network
MSK	medium shift keying
MST	multiservice terminal
MTBF	mean time between failures
MTD	mass tape duplicator/verifier
MTR	magnetic tape recorder
MTTF	mean time to failure
MTTFF	mean time to first failure
MTTR	mean time to repair
MUMPS	Massachussetts General Hospital Utility Multi-Programming System
MUSA	multiple-unit steerable antenna (or array)

MUX	multiplexer
mV	milliVolt
MV	megaVolt
μV	microVolt
nA	nanoAmp
NAND	NOT AND gate
NASA	National Aeronautics and Space Administration
NBS	National Bureau of Standards (USA)
NC	network computer
NCC	National Computing Centre
NDP	numeric data processor
NDRO	non-destructive readout
NEMA	National Electrical Manufacturers Association
NEN	near-end noise
NEP	noise equivalent power
NEXT	near-end cross-talk
nF	nanoFarad
NF	noise figure
NFB	negative feedback
NIC	network information centre
NIC	negative impedance converter
NiCad	nickel/cadmium cell
NICAM	near-instantaneous compression and audio multiplex
NIST	National Institute of Standards and Technology
NIT	network information table
n-MOS	n-channel metal-oxide semiconductor
NMRR	normal mode rejection ratio
NOP	no operation
NOR	inverted OR gate
NORAD	North American Air Defence Command
NPL	National Physical Laboratory (UK)
NRL	Naval Research Laboratory (USA)
NRZ	non-return zero
NRZI	non-return to zero inverted
NSPE	National Society of Professional Engineers (USA)
NTC	negative temperature coefficient
NTIA	National Telecommunications Information Administration
NTSC	National Television Systems Committee (USA)
NTU	network termination unit
nV	nanoVolt
Ω	Ohm
OAM	operation and maintenance

OB	optical buffer
OB	outside broadcast
OBL	one block lookahead
OBW	occupied bandwidth
OCR	optical character reader
OCR	optical character recognition
ODA	open-document architecture
ODI	open datalink interface
ODS	output datalink strobe
OEE	overall equipment effectiveness
OEM	original equipment manufacturer
OFDM	orthogonal frequency division multiplexing
OHS	occupational health system
OLB	outer lead bonding (in tape automated bonding)
OLE	object linking and embedding
OLR	off-line reader
OMR	optical mark reader
OOBE	out-of-box experience
OODMS	object-oriented database management system
OOK	on/off keying
OOP	object-oriented planning
OOP	object-oriented programming
OOPS	object-oriented programming system
OPAL	operational performance analysis language
OP AMP	operational amplifier
ORACLE	ITV teletext service
OS	operating system
OSCAR	Orbiting Satellite Carrying Amateur Radio
OSD	on-screen display
OSI	open systems interconnection
OSPSK	offset phase shift keying
OTA	operational transconductance amplifier
OTDM	optical time-division multiplexing
OTDMA	optical time-division multiple access
OTDR	optical time-domain reflectometer
OWF	optical working frequency
OXC	optical cross connects

PA	power amplifier
PA	public address
PABX	private automatic branch exchange
PACE	plasma-assisted chemical etching
PAD	packet assembly/disassembly
PADT	post-alloy diffused transistor

PAL	phase alternation, line (colour TV system)
PAM	pulse-amplitude modulation
PAR	partial amplitude response
PAR	precision approach radar
PAR	program aid routine
PASCAL	computer language
PAT	portable appliance tester
PAT	program association table (SI)
PAVD	plasma-assisted vapour deposition
PBGA	plastic ball-grid array
PBX	private branch exchange
PC	printed circuit
PC	personal computer
PCA	principal components analysis
PCB	printed circuit board
PCC	plastic chip carrier
PC-DOS	Personal Computer Disk Operating System
PCI	peripheral component interconnect
PCL	printer control language
PCM	pulse code modulation
PCMCIA	Personal Computer Memory Card International Association
PCN	personal communication network
PCS	personal communication system
PD	partially depleted (silicon)
PD	phase-change disc
PD	photodetector
PD	potential difference
PD	public domain
PDC	personal digital cellular
PDM	product data management
PDM	pulse duration modulation
PDN	provate data network
PDP	plasma display panel
PEC	photo-electric cell
PEM	plastic encapsulated microcircuit
PEP	peak envelope power
PERT	program evaluation and review technique
PES	packetised elementary stream
pF	picoFarad
PF	power factor
PFM	pulse frequency modulation
PFR	power failure restart
PGA	pin grid array (package)
PHS	personal headphone system

PI	peripheral interface
PIA	peripheral interface adaptor
PID	packet identity
PIL	precision in-line (colour picture tube)
PIM	pulse interval modulation
PIND	particle impact noise detection
PIPO	parallel in, parallel out
PISO	parallel in, series out
PIV	peak inverse voltage
PLA	programmable logic array
PLC	programmable logic controller
PLCC	plastic leadless chip carrier
PLD	programmable logic device
PLD	programmable logic design
PLL	phase-locked loop
PLMN	public land mobile network
PM	phase modulation
PMG	permanent magnet generator
p-MOS	p-channel metal-oxide semiconductor
PMR	private mobile radio
PMT	program map table
POTS	plain old telephone service
p-p	peak-to-peak
PPI	plan position indicator
PPI	programmable peripheral interface
PPGA	plastic pin gate array
ppm	parts per million
PPM	peak programme meter
PPM	periodic permanent magnet
PPM	pulse position modulation
PPTC	polymer positive temperature co-efficient
PPV	pay-per-view
PQFP	plastic quad flat package
PRACL	page-replacement algorithm and control logic
PRB	pseudo-random binary (sequence)
PRESTEL	commercial teletext service
PRF	pulse repetition frequency
PROM	programmable read-only memory
PRTP	pseudo-random test pattern
PRTPG	pseudo-random test pattern generator
PSD	power spectral density
PSI	program status indicator
PSK	phase-shift key(ing)
PSN	packet switched network

PSP	programme service provider
PSPDN	packet-switched public data network
PSTN	public switched telephone network
PSW	processor status word
PTB	plated-through board
PTFE	polytetrafluoroethylene
PTH	plated-through-holes
PTT	postal, telegraph and telephone (authority)
PUT	programmable unijunction transistor
PVQ	pyramid vector quantisizer
PWB	printed wiring board
PWM	pulse-width modulation
PWS	programmable workstation
QA	quality assurance
QAGC	quiet automatic gain control
QAM	quadrature amplitude modulation
QC	quality control
QFD	quality, function, deployment
QFP	quad flat pack
QISAM	queued indexed sequential access method
QMB	quick make and break (switch)
QML	qualified manufacturers list
QoS-A	quality of service (architecture)
QPL	qualified parts list
QPP	quiescent push-pull
QPSK	quadrature phase-shift keying
QUIP	quad in-line package
R	Ohm
RAC	Reliability Analysis Centre
RACE	Research and Technology Development in Advanced Communication Technologies in Europe
RADAR	radio detection and ranging
RALU	register and arithmetic/logic unit
RAM	random-access memory
RAS	row address select
RASSP	rapid programming of application-specific signal processors
RC	resistance/capacitance
RCTL	resistor-coupled transistor logic
RDB	radio data broadcast
RDF	radio direction finding
RDP	reliable data protocol

RDS	radio data services
RDSR	relative data service request
rec	receiver
RETMA	Radio, Electronic and Television Manufacturers Association
RF	radio frequency
RFC	radio frequency choke
RFI	radio-frequency interference
RFC	request for comments
RGB	red/green/blue
RIGFET	resistive insulated-gate field-effect transistor
RIM	read-in mode
RISC	reduced-instruction-set computer
RJE	remote job entry
RLC	run-length coding
RLL	run-length limited
R&M	reliability and maintenance
RMS	root mean square
ROM	read-only memory
RPROM	reprogrammable read-only memory
RRD	reversed resistance design
RMM	read-mostly mode
RS	Reed-Solomon coding
RSA	real sector access
RSGB	Radio Society of Great Britain
RST	running status table (part of SI)
RTB	return to base
RTB	reverse translation buffer
RTC	real-time clock
RTFL	real-time fault location
RTL	resistor/transistor logic
RTO	regenerative thermal oxidiser
RTS	request to send
R/W	read/write
RV	random vibration
Rx	receiver
RZ	return to zero

SA	spectrum analyser
SA	signature analysis
SAGE	semi-automatic ground environment (radar)
SAM	scanning auger microscopy
SAR	synthetic aperture radar
SAW	surface acoustic wave

SAZ	signature analyser
SBS	silicon bilateral switch
SC	semiconductor
SC	short circuit
SCA	subchannel adapter
SCAT	scanning acoustic tomography
SCM	subcarrier multiplexing
SCR	silicon controlled rectifier
SCSI	small computer system interface
SCTE	Society of Cable Telecommunications Engineers (USA)
SDH	synchronous digital hierarchy
SDLC	synchronous data-link control
SDMA	space-division multiple access
SDT	service description table (part of SI)
SECAM	système en couleurs à memoire (colour TV system)
SEM	scanning electron microscope
seq	sequential
S/H	sample and hold
SIA	Semiconductor Industry Association (USA)
Si	silicon
SI	service information (or housekeeping details added on to the video, audio or multimedia data stream)
SIC	specific inductive capacity
SID	Society for Information Display (USA)
SIL	single in-line
SIMD	single instruction, multiple data
SIMM	single in-line memory module
SIO	serial input/output
SiO_2	silicon dioxide
SIP	single in-line package
SIPO	serial in, parallel out
SISD	single instruction, single data
SISO	serial in, serial out
SLIC	subscriber line interface card
SLR	sideways looking radar
SMA	surface mount assembly
SMA	type of co-axial connector
SMART	stress marginality and accelerated reliability test
SMART	surface modification by atomic resolution terraces
SMATV	satellite master antenna television
SMB	type of co-axial connector
SMC	surface mounting component
SMC	type of co-axial connector
SMD	surface mount device

SME	Society of Manufacturing Engineers
SMP	symmetrical multiprocessor
SMPS	switched-mode power supply
SMS	subscriber management system
SMT	surface-mount technology
SMT	systems management terminal
SMTA	Surface Mount Technology Association (USA)
SMTP	simple message-transfer protocol
SMPTE	Society of Motion Picture and Television Engineers
SN	signal-to-noise
SNOBOL	string-oriented symbolic language
SNR	signal-to-noise ratio
SOHO	small office/home office
SOI	silicon on insulator
SOIC	small-outline integrated-circuit package
SOM	self-organising map
SOP	small outline package
SOP	Swiss outline package
SOS	silicon-on-sapphire
SP	stack printer
SPC	statistical process control
SPCS	satellite personal communication service
SPICE	simulated program with integrated-circuit emphasis
SPURS	spurious responses
SQL	structured query language
SQUID	superconducting quantum interference device
SRAM	stand-alone random-access memory
SRAM	static random-access memory
SRBP	synthetic resin bonded paper
SRC	Science Research Council (UK)
SSB	single sideband (broadcast)
SSBSC	single sideband, suppressed carrier
SSDD	single-sided, double-density
SSI	small-scale integration
SSIN	single-stage interconnection network
SSSD	single-sided single-density
SSM	scanning squid microscope
SSTC	single-sideband transmitted-carrier
SSTV	slow-scan television
ST	stuffing table (part of SI)
STB	set-top box
STD	subscriber trunk dialling
SUS	silicon universal switch
SWR	standing wave ratio

Sx	simplex
SYSOP	system operator

TAB	tape automated bonding
TAT	Transatlantic Telephone Transmission (cable)
TBMT	transmitter buffer empty
TC	temperature coefficient
TCP	transmission control protocol
TCP/IP	transmission control protocol/Internet protocol
TDD	time division duplex
TDM	time division multiplexing
TDMA	time division multiple-access
TDR	time domain reflectometry
TDSR	transmitter data service request
TDT	time domain transmission
TELEX	teletypewriter exchange (service)
TEM	transmission electron microscope
TEM	transversal electromagnetic
TFT	thin-film transistor
THD	total harmonic distortion
TIA	Telecommunications Industry Association (USA)
TIFF	tagged image file format
TIQ	total integrated quality
T^2L	transistor/transistor logic
TLB	translation lookaside buffer
TLM	transmission-line matrix
TMOS	T-metal oxide/semiconductor
TMR	triple modular redundancy
TODL	tunable optical delay line
TOP	technical and office protocol
TOS	top of stack
TOT	time offset table (part of SI)
TP	test point
TPA	transient program area
TQFP	thin quad flat pack
TQM	total quality management
TRAPPATT	trapped-plasma avalanche transit time (diode)
TRF	tuned radio frequency (receiver)
TRL	transistor/resistor logic
TSL	tri-state logic
TSOP	thin small-outline package
TSS	time shared system
TTL	transistor/transistor logic
TTTN	tandem tile trunk network

TTY	teletypewriter
TV	television
TVS	transient voltage suppressor
TWAIN	toolkit without an important name
TWT	travelling wave tube
Tx	transmitter
UART	universal asynchronous receiver/transmitter
UDP	user datagram protocol
UHF	ultra high frequency (300–3000 MHz)
UHP	ultra high purity
UJT	unijunction transistor
ULA	uncommitted logic array
ULSI	ultra large-scale integration
UMTS	universal mobile telecommunication system
UNCOL	universal computer-oriented language
UNESCO	United Nations Educational, Scientific and Cultural Organisation
UNI	user network interface
UPC	universal peripheral controller
URCLK	universal receiver clock
URL	universal resource locator
USART	universal synchronous/asynchronous receiver/transmitter
USRT	universal synchronous receiver/transmitter
UTC	co-ordinated universal time
UTCLK	universal transmitter clock
UTP	ultra-thin package
UUT	unit under test
VAB	voice answer back
VAN	value added network
VBR	variable bit rate
VCO	voltage-controlled oscillator
VCR	video cassette recorder
VCSEL	vertical-channel surface-emitting laser
VCT	voltage-to-current transactor
VCXO	voltage-controlled crystal oscillator
VDG	video display generator
VDI	visual display interface
VDP	vapour deposition polymerisation
VDR	voltage-dependent resistor
VDSL	very-high-speed digital subscriber line
VDU	visual display unit
VE	value engineering

VESA	Video Electronics Standards Association
VFO	variable-frequency oscillator
VGA	video graphics array
VGA	video graphics adaptor
VHDL	VHSIC hardware description language
VHF	very high frequency (30–300 MHz)
VHSIC	very-high-speed integrated circuit
VIC	video interface chip
VIDEOTEX	interactive computer-controlled medium using TV and telephone
VIEWDATA	now PRESTEL
VIL	vertical injection logic
VIP	versatile information processor
VIP	virtual information projection
VLC	variable-length coding
VLF	very low frequency (3–30 kHz)
VLSI	very-large-scale integration
VM	virtual memory
VMA	valid memory address
VMM	virtual machine monitor
VMS	virtual machine system
VMOS	vertical groove MOS
VOM	Volt/Ohm meter
VPA	valid peripheral address
VPN	virtual private network
VPT	vapour-phase technology
VR	virtual reality
VRAM	video random-access memory
VRC	vertical redundancy check
VRML	virtual-reality modelling language
VS	virtual storage
VSAT	very-small-aperture terminal
VSB	vestigial sideband transmission
VSOP	very small outline package
VTR	video tape recorder
WAIS	wide-area information servers
WAN	wide-area network
WARC	World Advisory Radio Conference
WATS	wide-area telephone service
WDM	wavelength-division multiplexing
WIMPS	windows, icons, menus and pointer
WORM	write once, read many times
WP	word processor

WPC	write precompensation
WPM	words per minute
WS	working set
WSTS	world semiconductor trade statistics
WT	wireless telegraphy
WWW	worldwide web
WYSIWYG	what you see is what you get
XML	extensible markup language
XMS	extended memory specification
XNOR	exclusive-NOR gate
XOR	exclusive-OR gate
xtal	crystal
YIG	yttrium/iron garnet
ZF	zero frequency
ZIF	zero-insertion force

This page intentionally left blank

ENCYCLOPEDIA OF MODERN OPTICS

EDITED BY
B.D. GUENTHER
A. MILLER
L. BAYVEL
J.E. MIDWINTER

VOLUME ONE

EDITOR-IN-CHIEF

Robert D. Guenther
Duke University
Durham, NC, USA

EDITORS

Duncan G. Steel
University of Michigan
Ann Arbor, MI, USA

Leopold Bayvel
London, UK

CONSULTING EDITORS

John E. Midwinter
University College London, London, UK

Alan Miller
University of St Andrews, Fife, UK

EDITORIAL ADVISORY BOARD

R Alferness
Lucent Technologies Bell Laboratories
Holmdel, NJ, USA

D J Brady
Duke University
Durham, NC, USA

J Caulfield
Diversified Research Corporation
Cornersville, TN, USA

R L Donofrio
Display Device Consultants LLC
Ann Arbor, MI, USA

J Dudley
Université de Franche-Comté
Besançon, France

J G Eden
University of Illinois
Urbana, IL, USA

H O Everitt
U.S. Army Research Office
Research Triangle Park, NC, USA

E L Hecht
Adelphi University
Garden City, NY, USA

H S Hinton
Utah State University
Logan, UT, USA

T N Hurst
Hewlett-Packard Laboratories
Tucson, AZ, USA

D Killinger
University of South Florida
Tampa, FL, USA

T A King
University of Manchester
UK

E Leith
University of Michigan
Ann Arbor, MI, USA

A Macleod
Thin Film Center, Inc.
Tucson, AZ, USA

P F McManamon
Air Force Research Laboratory
Wright-Paterson AFB, OH, USA

J N Mait
U.S. Army Research Laboratory
Adelphi, MD, USA

D Phillips
Imperial College
London, UK

C R Pidgeon
Heriot-Watt University
Edinburgh, UK

R Pike
King’s College London
UK

E Van Stryland
University of Central Florida
Orlando, FL, USA

Preface

We live in a world powered by light, but much of the understanding of light was developed around the time of the French Revolution. Before the 1950s, optics technology was viewed as well established and there was little expectation of growth either in scientific understanding or in technological exploitation. The end of the Second World War brought about huge growth in scientific exploration, and the field of optics benefited from that growth. The key event was the discovery of methods for producing a source of coherent radiation, with the key milestone being the demonstration of the first laser by Ted Maiman in 1960. Other lasers, nonlinear optical phenomena, and technologies such as holography and optical signal processing, followed in the early 1960s. In the 1970s the foundations of fiber optical communications were laid, with the development of low-loss glass fibers and sources that operated in the wavelength region of low loss. The 1980s saw the most significant technological accomplishment: the development of efficient optical systems and resulting useful devices. Now, some forty years after the demonstration of the first coherent light source, we find that optics has become the enabling technology in areas such as:

- information technology and telecommunications;
- health care and the life sciences;
- sensing, lighting, and energy;
- manufacturing;
- national defense;
- manufacturing of precision optical components and systems; and
- optics research and education.

We find ourselves depending on CDs for data storage, on digital cameras and printers to produce our family photographs, on high speed internet connections based on optical fibers, on optical based DNA sequencing systems; our physicians are making use of new therapies and diagnostic techniques founded on optics.

To contribute to such a wide range of applications requires a truly multidisciplinary effort drawing together knowledge spanning many of the traditional academic boundaries. To exploit the accomplishments of the past forty years and to enable a revolution in world fiber-optic communications, new modalities in the practice of medicine, a more effective national defense, exploration of the frontiers of science, and much more, a resource to provide access to the foundations of this field is needed. The purpose of this Encyclopedia is to provide a resource for introducing optical fundamentals and technologies to the general technical audience for whom optics is a key capability in exploring their field of interest.

Some 25 internationally recognized scientists and engineers served as editors. They helped in selecting the topical coverage and choosing the over 260 authors who prepared the individual articles. The authors form an international group who are expert in their discipline and come from every part of the technological community spanning academia, government and industry. The editors and authors of this Encyclopedia hope that the reader finds in these pages the information needed to provide guidance in exploring and utilizing optics.

As Editor-in-Chief I would like to thank all of the topical editors, authors and the staff of Elsevier for each of their contributions. Special thanks should go Dr Martin Ruck of Elsevier who provided not only organizational skills but also technological knowledge which allowed all of the numerous loose ends to be tied.

B D Guenther
Editor-in-Chief

ALL-OPTICAL SIGNAL REGENERATION

O Leclerc, Alcatel Research & Innovation,
Marcoussis, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The breakthrough of optical amplification, combined with the techniques of wavelength division multiplexing (WDM) and dispersion management, have made it possible to exploit a sizeable fraction of the optical fiber bandwidth (several terahertz). Systems based on 10 Gbit/s per channel bit-rate and showing capacities of several terabit/s, with transmission capabilities of hundreds or even thousands of kilometers, have reached the commercial area.

While greater capacities and spectral efficiencies are likely to be reached with current technologies, there is potential economic interest in reducing the number of wavelength channels by increasing the channel rate (e.g., 40 Gbit/s). However, such fourfold increase in the channel bit-rate clearly results in a significant increase in propagation impairments, stemming from the combined effects of noise accumulation, fiber dispersion, fiber nonlinearities, and inter-channel interactions and contributing to two main forms of signal degradation. The first one is related to the amplitude domain; power levels of marks and spaces can suffer from random deviations arising from interaction between signal and amplified spontaneous emission (ASE) noise or with signals from other channels through cross-phase modulation (XPM) from distortions induced by chromatic dispersion. The second type of signal degradations occurs in the time domain; time position of pulses can also suffer from random deviations arising from interactions between signal and ASE noise through fiber dispersion. Preservation of high power contrast between '1' and '0', and of both amplitude fluctuations and timing jitter below some acceptable levels, are mandatory for high transmission quality, evaluated through bit-error-rate (BER) measurements or estimated by Q-factors. Moreover, in future optical networks, it appears mandatory to ensure similar but high optical signal quality at the output of whatever nodes in the networks, as to enable successful transmission of the data over arbitrary distance.

Among possible solutions to overcome such systems limitations is the implementation of Optical Signal Regeneration, either in-line for long-haul transmission applications or at the output of network nodes. Such Signal Regeneration performs, or should be able to perform, three basic signal-processing functions that are Re-amplifying, Re-shaping, and Re-timing, hence the generic acronym '3R' (Figure 1). When Re-timing is absent, one usually refers to the regenerator as '2R' device, which has only re-amplifying and re-shaping capabilities. Thus, full 3R regeneration with retiming capability requires clock extraction.

Given system impairments after some transmission distance, two solutions remain for extending the actual reach of an optical transmission system or the scalability of an optical network. The first consists in segmenting the system into independent trunks, with full electronic repeater/transceivers at interfaces (we shall refer to this as 'opto-electronic regeneration' or O/E Regeneration forthwith). The second solution, i.e., all-optical Regeneration, is not the optical version of the first which would have higher bandwidth capability but still performs the same signal-restoring functions with far reduced complexity. At this point, it should be noted that Optical 3R techniques are not necessarily void of any electronic functions (e.g., when using electronic clock recovery and O/E modulation), but the main feature is that these electronic functions are narrowband (as opposed to broadband in the case of electronic regeneration).

Some key issues have to be considered when comparing such Signal Regeneration approaches. The first is that today's and future optical transmission systems or/and networks are WDM networks.



Figure 1 Principle of 3R regeneration, as applied to NRZ signals. (a) Re-Amplifying; (b) Re-Shaping; (c) Re-Timing. NB: Such eye diagrams can be either optical or electrical eye diagrams.

Under this condition, the WDM compatibility – or the fact that any Regeneration solution can simultaneously process several WDM channels – represents a key advantage. The maturity of the technology – either purely optical or opto-electronic – also plays an important role in the potential (pre-)development of such solutions. But the main parameter that will decide the actual technology (and also technique) relies on the tradeoff between actual performance of the regeneration solutions and their costs (device and implementation), depending on the targeted applications (long-haul system, medium haul transport, wide area optical network, etc.).

In this article, we review the current alternatives for all-optical Signal Regeneration, considering both theoretical and experimental performance and practical implementation issues. Key advantages and possible drawbacks of each solutions are discussed, to sketch the picture in this field. However, first we must focus on some generalities about Signal Regeneration and the way to define (and qualify) such regenerator performance. In a second part, we will detail the currently-investigated optical solutions for Signal Regeneration with a specific highlight for semiconductor-based solutions using either semiconductor optical amplifiers (SOA) technology or newly-developed saturable absorbers. Optical Regeneration techniques based on synchronous modulation will also be discussed in a third section. The conclusion will summarize the key features of each solution, so as to underline the demanding challenge optical components are facing in this application.



Figure 2 Generic structure of Signal 2R/3R Regenerator based on Decision Element (2R) and Decision Element and Clock Recovery (3R).

Generalities on Signal Regeneration

Principles

In the general case, Signal Regeneration is performed using a decision element exhibiting a nonlinear transfer function. Provided with a threshold level and when associated with an amplifier, such an element then performs the actual Re-shaping of the incoming data (either in the electrical or optical domain) and completes a 2R Signal Regenerator. Figure 2 shows the generic structure of such a Signal Regenerator in the general case as applied to non return to zero (NRZ) data. A clock recovery block can be added (dotted lines) to provide the decision element with time reference and hence perform the third R (Re-timing) of full Signal 3R Regeneration. At this point, it should be mentioned that the decision element can operate either on electrical signals (standard electrical DFF) provided that optical → electrical and electrical → optical signal conversion stages are added or directed onto optical signals using the different techniques described below. The clock signal can be of an electrical nature, as for electrical decision element in O/E regenerator – or either an electrical or a purely optical signal in all-optical regenerators.

Prior to reviewing and describing the various current technology alternatives for such Optical Signal Regeneration, the issue of the actual characterization of regenerator performance needs to be explained and clarified. As previously mentioned, the core element of any Signal Regenerator is the decision element showing a nonlinear transfer function that can be of varying steepness. As will be seen in Figure 3, the actual regenerative performance of the regenerator will indeed depend upon the degree of nonlinearity of the decision element transfer function.

Figure 3 shows the principle of operation of a regenerator incorporating a decision element with two steepnesses of the nonlinear transfer function. In any case, the ‘1’ and ‘0’ symbols amplitude probability densities (PD) are squeezed after passing through the decision element. However, depending upon the addition of a clock reference for triggering the decision element, the symbol arrival time PD will be also squeezed (clocked decision = 3R regeneration) or enlarged (no clock reference = 2R regeneration) resulting in conversion of amplitude fluctuations to time position fluctuations.

As for system performance – expressed through BER – regenerative capabilities of any regenerator simultaneously depend upon both the output amplitude and arrival time PD of the ‘1’ and ‘0’ symbols. In the unusual case of 2R regeneration (no clocked decision), a tradeoff has then to be derived, considering both the reduction of amplitude PD and the enlarged arrival time PD induced by the regenerator, to ensure sufficient signal improvement. In Figure 3a, we consider a step function for the transfer function of the decision element. In this case, amplitude PD are squeezed to Dirac PD after the decision element, and depending upon addition or not of a clock reference, arrival time PD is reduced (3R) or dramatically enlarged (2R). In Figure 3b, the decision element exhibits a moderately nonlinear transfer function. This results in an asymmetric and less-pronounced squeezing of the amplitude PD compared to the previous case, but in turn results in a significantly less enlarged arrival time PD when no clock reference is added (2R regeneration). Comparison of these two decision element of different nonlinear transfer function indicates that for 3R regeneration applications, the more nonlinear the transfer function of the decision element the better performance, the ideal case being the step function. In the case of 2R regeneration applications, a tradeoff between the actual reduction of the amplitude PD and enlargement of timing PD is to be derived and clearly depends upon the actual shape of the nonlinear transfer function of the decision element.

Qualification of Signal Regenerator Performance

To further illustrate the impact of the actual shape of the nonlinear transfer function of the decision



Figure 3 Signal Regeneration process using Nonlinear Gates. (a) Step transfer function (= Electronic DFF); (b) ‘moderately’ nonlinear transfer function. As an illustration of the Regenerator operation ‘1’ and ‘0’ symbols amplitude probability density (PD) and arrival time probability density (PD) are shown in light gray and dark gray, respectively.

element in 3R application, the theoretical evolution of BER with number of concatenated regenerators have been plotted for regenerators having different nonlinear responses. Figure 4 shows the numerically calculated evolution of the BER of a 10 Gbit/s NRZ signal with fixed optical signal-to-noise ratio (OSNR) at the input of the 3R regenerator, as a function of the cascaded regenerator incorporating nonlinear gates with nonlinear transfer function of different depths. From Figure 4, can be seen different behaviors depending on the nonlinear function shape. As previously stated, the best regeneration performance is obtained with an ideal step function (case a), which is actually the case for O/E regenerator using electronic decision flip-flop (DFF). In that case, BER linearly increase (i.e., more errors) in the cascade. Conversely, when nonlinearity is reduced (cases (b) and (c)), both BER and noise accumulate, until the concatenation of nonlinear functions reach some steady-state pattern, from which BER linearly increases. Concatenation of nonlinear devices thus magnifies shape differences in their nonlinear response, and hence their regenerative capabilities.

Moreover, as can be seen in Figure 4, all curves standing for different regeneration efficiencies pass through a common point defined after the first device. This clearly indicates that it is not possible to qualify the regenerative capability of any regenerator when considering the output signal after only one regenerator. Indeed, the BER is the same for either a 3R regenerator or a mere amplifier if only measured after a single element. This originates from the initial overlap between noise distributions associated with marks and spaces, that cannot be suppressed but only minimized by a single decision element through threshold adjustment.

As a general result, the actual characterization of the regenerative performance of any regenerator should *in fine* be conducted considering a cascade of regenerators. In practice this can easily be done with the experimental implementation of the regenerator under study in a recirculating loop. Moreover, such an investigation tool will also enable access to the regenerator performance with respect to the transmission capabilities of the regenerated signal, which should not be overlooked.

Let us now consider the physical implementation of such all-optical Signal Regenerators, along with the key features offered by the different alternatives.

All-Optical 2R/3R Regeneration Using Optical Nonlinear Gates

Prior to describing the different solutions for all-optical in-line Optical Signal Regeneration, it should be mentioned that since the polarization states of the optical data signals cannot be preserved during propagation, it is required that the regenerator exhibits an extremely low polarization sensitivity. This clearly translates to a careful optimization of all the different optical components making up the 2R/3R regenerator. It should be noted that this also applies to the O/E solutions but is of limited impact, since only the photodiode has to be polarization insensitive.

Figure 5 illustrates the generic principle of operation of an all-optical 3R Regenerator using optical nonlinear gates. Contrary to what occurs in O/E, regenerator where the extracted clock signal drives the electrical decision element, the incoming and distorted optical data signal triggers the nonlinear gate, hence generating a switching window which is



Figure 4 Evolution of the BER with concatenated regenerators for nonlinear gates with nonlinear transfer function of decreasing depths from case (a)–(c) (step function).



Figure 5 Principle of operation of an all-Optical Signal 3R Regenerator using nonlinear gates.

applied to a newly generated optical clock signal so as to reproduce the initial data stream on the new optical carrier.

In the case of 2R Optical Signal Regeneration, a continuous wave (CW) signal is substituted for the synchronized optical clock pulses. As previously mentioned, the actual regeneration performance of the 2R/3R devices will mainly depend upon the nonlinearity of the transfer function of the decision element but in 3R applications the quality of the optical clock pulses has also to be considered. In the following, we describe current solutions to explain the two main building blocks of all-optical Signal Regenerators: the decision element (i.e., nonlinear gate) and the clock recovery (CR) elements.

Optical Decision Element

In the physical domain, optical decision elements with ideal step response – as for electrical DFF – do not exist. Different nonlinear optical transfer functions, approaching more or less the ideal case, can be realized in various media such as fiber, SOA, electroabsorption modulators (EAM), and lasers. Generally, as described below, the actual response (hence the regenerative properties of the device) of such optical gates directly depends upon the incoming signal instantaneous power. Under these conditions, it appears essential to add an adaptation stage so as to reduce intensity fluctuations (as caused by propagation or crossing routing/switching node) and provide the decision element with fixed power conditions. In practice, this results in the addition of a control circuitry (either optical or electrical) in the Re-amplification block, whose complexity directly depends on actual system environment (ultra-fast power equalization for packet-switching applications and compensation of slow power fluctuations in transmission applications).

As previously described the decision gate performs Re-shaping (and Re-timing when clock pulses are added) of the incoming distorted optical signal, and represent the regenerator's core element. Ideally, it should also act as a transmitter with characteristics ensuring the actual propagation of the regenerated data stream. In that respect, the chirp possibly induced by the optical decision gate onto the regenerated signal – and the initial quality of the optical clock pulses in 3R applications – should be carefully considered (ideally by means of loop transmission) as to adequately match line transmission requirements.

Different solutions for the actual realization of the optical decision element have been proposed and extensively investigated using, for example, cross gain modulation in semiconductor optical amplifier (SOA) devices but the most promising and flexible devices probably are interferometers, for which, descriptions of the generic principle of operation follows. Consider a CW signal (probe) at λ_2 wavelength injected into an optical interferometer, in which one arm incorporates a nonlinear medium in which an input signal carried by λ_1 wavelength (command) is, in turn, injected. Such a signal, at λ_1 wavelength, induces a phase shift through cross-phase modulation (XPM) in this arm of the interferometer, the amount depending upon power level $P_{\mathrm{in},\lambda 1}$. In turn, such phase modulation (PM) induces amplitude modulation (AM) on the signal at λ_2 wavelength when recombined at the output of the interferometer and translates the information carried by wavelength λ_1 onto λ_2. Under these conditions, such optical gates clearly act as wavelength converters (it should be mentioned that Wavelength Conversion is not necessarily equivalent to Regeneration; i.e., a linear transfer function performs suitable Wavelength Conversion but by no means Signal Regeneration).

Optical interferometers can be classified according to the nature of the nonlinearity exploited to achieve a π phase shift. In the case of fiber-based devices, such as the nonlinear optical loop mirror (NOLM), the phase shift is induced through the Kerr effect in an optical fiber. The key advantage of fiber-based devices such as NOLM lies in the near-instantaneous (fs) response of the Kerr nonlinearity, making them very attractive for ultra-high bit-rate operation ($\geq$160 Gbit/s). Polarization-insensitive NOLMs have been realized, although with the same drawbacks concerning integrability. With recent developments in highly nonlinear (HNL) fibers, however, the required NOLM fiber length could be significantly reduced, hence dramatically reducing environmental instability.

A second type of device is the integrated SOA-based Mach-Zehnder interferometers (MZI). In MZIs, the phase shift is due to the effect of photo-induced carrier depletion in the gain saturation regime of one of the SOAs. The control and probe can be launched in counter- or co-directional ways. In the first case, no optical filter is required at the output of the device for rejecting the signal at λ_1 wavelength but operation of the MZI is limited by its speed. At this point, one should mention that the photo-induced modulation effects in SOAs are intrinsically limited in speed by the gain recovery time, which is a function of the carrier lifetime and the injection current. An approach referred to as differential operation mode (DOM) and illustrated on Figure 6, which takes advantage of the MZI's interferometric properties, makes it possible to artificially increase the operation speed of such 'slow' devices up to 40 Gbit/s.

As discussed earlier, the nonlinear response is a key parameter for regeneration efficiency. Combining two interferometers is a straightforward means to improve the nonlinearity of the decision element transfer function, and hence regeneration efficiency. This approach was validated at 40 Gbit/s using a cascade of two SOA-MZI, (see Figure 7 (**left**)). Such a scheme offers the advantage of restoring data polarity and wavelength, hence making the regenerator inherently transparent. Finally, the second conversion stage can be used as an adaptation interface to the transmission link achieved through chirp tuning in this second device.

Such an Optical 3R Regenerator was upgraded to 40 Gbit/s, using DOM in both SOA-MZIs with validation in a 40 Gbit/s loop RZ transmission. The 40 Gbit/s eye diagram monitored at the regenerator output after 1, 10, and 100 circulations are shown in Figure 7 (**right**) and remain unaltered by distance. With this all-optical regenerator structure, the minimum OSNR tolerated by the regenerator (1 dB sensitivity penalty at 10^{-10} BER) was found to be as low as 25 dB/0.1 nm. Such results clearly illustrate the high performance of this SOA-based regenerator structure for 40 Gbit/s optical data signals.



Figure 6 Schematic and principle of operation of SOA-MZI in differential mode.

Such a complex mode of operation for addressing 40 Git/s bit-rates will probably be discarded when we consider the recent demonstration of standard-mode wavelength conversion at 40 Gbit/s, which uses a newly-designed active-passive SOA-MZI incorporating evanescent-coupling SOAs. The device architecture is flexible in the number of SOAs, thus enabling easier operation optimization and reduced power consumption, leading to simplified architectures and operation for 40 Gbit/s optical 3R regeneration.

Based on the same concept of wavelength conversion for Optical 3R Regeneration, it should be noted many devices have been proposed and experimentally validated as wavelength converters at rates up to 84 Gbit/s, but with cascadability issues still to be demonstrated to assess their actual regenerative properties.

Optical Clock Recovery (CR)

Next to the decision, the CR is a second key function in 3R regenerators. One possible approach for CR uses electronics while another only uses optics. The former goes with OE conversion by means of a photodiode and subsequent EO conversion through a modulator. This conversion becomes more complex and power-hungry as the data-rate increases. It is clear that the maturity of electronics gives a current advantage to this approach. But considering the pros and cons of electronic CR for cost-effective implementation, the all-optical approach seems more promising, since full regenerator integration is potentially possible with reduced power consumption. In this view, we shall focus here on the optical approach and more specifically on the self-pulsating effect in three-sections distributed feedback (DFB) lasers or more recently in distributed Bragg reflector



Figure 7 Optimized structure of a 40 Gbit/s SOA-based 3R regenerator. 40 Gbit/s eye diagram evolution: (a) B-to-B; (b) 1 lap; (c) 10 laps; (d) 100 laps.

(DBR) lasers. Recent experimental results illustrate the potentials of such devices for high bit rates (up to 160 Gbit/s), broad dynamic range, broad frequency tuning, polarization insensitivity, and relatively short locking times (1 ns). This last feature makes these devices good candidates for operation in asynchronous-packet regimes.

Optical Regeneration by Saturable Absorbers

We next consider saturable absorbers (SA) as nonlinear elements for optical regeneration. Figure 8 (**left**) shows a typical SA transfer function and illustrates the principle of operation. When illuminated with an optical signal with peak power below some threshold (P_{sat}), the photonic absorption of the SA is high and the device is opaque to the signal (low transmittance). Above P_{sat}, the SA transmittance rapidly increases and asymptotically saturates to transparency (passive loss being overlooked). Such a nonlinear transfer function only applies to 2R optical regeneration.

Different technologies for implementing SAs are available, but the most promising approach uses semiconductors. In this case, SA relies upon the control of carrier dynamics through the material's recombination centers. Parameters such as on–off contrast (ratio of transmittance at high and low incident powers), recovery time (1/e) and saturation energy, are key to device optimization. In the following, we consider a newly-developed ion-irradiated MQW-based device incorporated in a micro-cavity and shown on Figure 8 (**right**). The device operates as a reflection-mode vertical cavity, providing both a high on/off extinction ratio by canceling reflection at low intensity and a low saturation energy of 2 pJ. It is also intrinsically polarization-insensitive. Heavy ion-irradiation of the SA ensures recovery times (at $1/e$) shorter than 5 ps (hence compatible with bit-rate above 40 Gbit/s), while maintaining a dynamic contrast in excess of 2.5 dB at 40 GHz repetition rate.

The regenerative properties of SA make it possible to reduce cumulated amplified spontaneous emission (ASE) in the '0' bits, resulting in a higher contrast between mark and space, hence increasing system performance. Yet SAs do not suppress intensity noise in the marks, which makes the regenerator incomplete. A solution for this noise suppression is optical filtering with nonlinear (soliton) pulses. The principle is as follows. In absence of chirp, the soliton temporal width scales in the same way as the reciprocal of its spectral width (Fourier-transform limit) times its intensity (fundamental soliton relation). Thus, an increase in pulse intensity corresponds to both time narrowing and spectral broadening. Conversely, a decrease in pulse intensity corresponds to time broadening and spectral narrowing. Thus, the filter causes higher loss when intensity increases, and lower loss when intensity decreases. The filter thus acts as an automatic power control (APC) in feed-forward mode, which causes power stabilization. The resulting 2R regenerator (composed by the SA and the optical filter) is fully passive, which is of high interest for submarine systems where the power consumption must be minimal, but it does not include any control in the time domain (no Re-timing).

System demonstrations of such passive SA-based Optical Regeneration have been reported with a 20 Gbit/s single-channel loop experiment. Implementation of the SA-based 2R Regenerator with 160 km-loop periodicity made it possible to double the error-free distance ($Q = 15.6$ dB or 10^{-9} BER) of a 20 Gbit/s RZ signal. So as to extend the capability of passive 2R regeneration to 40 Gbit/s systems, an improved configuration was derived from numerical optimization and experimentally demonstrated in a 40 Gbit/s WDM-like, dispersion-managed loop transmission, showing more than a fourfold increase in the WDM transmission distance at 10^{-4} BER (1650 km without the SA-based regenerator and 7600 km when implementing the 2R regenerator with 240 km periodicity).



Figure 8 (a) Saturable Absorber (SA) ideal transfer function. (b) Structure of Multi-Quantum Well SA.

Such a result illustrates the potential high interest of such passive optical 2R regeneration in long-haul transmission (typically in noise-limited systems) since the implementation of SA increases the system's robustness to OSNR degradation without any extra power consumption. Reducing both saturation energy and insertion loss along with increasing dynamic contrast represent key future device improvements. Regeneration of WDM signals from the same device, such as one SA chip with multiple fibers implemented between Mux/DMux stages, should also be thoroughly investigated. In this respect, SA wavelength selectivity in quantum dots could possibly be advantageously exploited.

Synchronous Modulation Technique

All-optical 3R regeneration can be also achieved through in-line synchronous modulation (SM) associated with narrowband filtering (NF). Figure 9 shows the basic layout of such an Optical 3R Regenerator. It is composed of an optical filter followed by an Intensity and Phase Modulator (IM/PM) driven by a recovered clock. Periodic insertion of SM-based modulators along the transmission link provides efficient jitter reduction and asymptotically controls ASE noise level, resulting in virtually unlimited transmission distances. Re-shaping and Re-timing provided by IM/PM intrinsically requires nonlinear (soliton) propagation in the trunk fiber following the SM block. Therefore, one can refer to the approach as distributed optical regeneration. This contrasts with lumped regeneration, where 3R is completed within the regenerator (see above with Optical Regeneration using nonlinear gates), and is independent of line transmission characteristics.

However, when using a new approach referred to 'black box' optical regeneration (BBOR), it is possible to make the SM regeneration function and transmission work independently in such a way that any type of RZ signals (soliton or non-soliton) can be transmitted through the system. The BBOR technique includes an adaptation stage for incoming RZ pulses in the SM-based regenerator, which ensures high regeneration efficiency regardless of RZ signal format (linear RZ, DM-soliton, C-RZ, etc.). This is achieved using a local and periodic soliton conversion of RZ pulses by means of launching an adequate power into some length of fiber with anomalous dispersion. The actual experimental demonstration of the BBOR approach and its superiority over the 'classical' SM-based scheme for DM transmission was experimentally investigated in 40 Gbit/s DM loop transmission. Under these conditions, one can then independently exploit dispersion management (DM) techniques for increasing spectral efficiency in long-haul transmission, while ensuring high transmission quality through BBOR.

One of the key properties of the SM-based all-optical Regeneration technique relies on its WDM compatibility. The first (Figure 10, **left**) and straightforward solution to apply Signal Regeneration to WDM channels amounts to allocating a regenerator to each WDM channel. The second consists in sharing a single modulator, thus processing the WDM channels at once in serial fashion. This approach requires WDM synchronicity, meaning that all bits be synchronous with the modulation, that can be achieved either by use of appropriate time-delay lines located within a DMux/Mux apparatus (Figure 10, **upper right**), or by making the WDM channels inherently time-coincident at specific regenerator locations (Figure 10, **bottom right**). Clearly, the serial regeneration scheme is far simpler and cost-effective than the parallel version; however, optimized re-synchronization schemes still remain to be



Figure 9 Basic layout of the all-optical Regenerator by Synchronous Modulation and Narrowband Filtering and illustration of the principle of operation.



Figure 10 Basic implementation schemes for WDM all-Optical Regeneration. (a) parallel asynchronous; (b) serial re-synchronized; (c) serial self-synchronized.

developed for realistic applications. Experimental demonstration of this concept was assessed by means of a 4 × 40 Gbit/s dispersion-managed transmission over 10 000 km (BER $< 5.10^{-8}$) in which a single modulator was used for the simultaneous regeneration of the 4 WDM channels.

Considering next all-optical regeneration schemes with ultra-high speed potential, a compact and loss-free 40 Gbit/s Synchronous Modulator, based on optically-controlled SOA-MZI, was proposed and loop-demonstrated at 40 Gbit/s with an error-free transmission distance in excess of 10 000 km. Moreover, potential ultra-high operation of this improved BBOR scheme was recently experimentally demonstrated by means of a 80 GHz clock conversion with appropriate characteristics through the SOA-MZI. One should finally mention all fiber-based devices such as NOLM and NALM for addressing ultra-high speed SM-based Optical Regeneration, although no successful experimental demonstrations have been reported so far in this field.

Conclusion

In summary, optical solutions for Signal Regeneration present many key advantages. These are the only advantages to date to possibly ensure WDM compatibility of the regeneration function (mostly 2R related). Such optical devices clearly exhibits the best 2R regeneration performance (wrt to O/E solutions) as a result of the moderately nonlinear transfer function (which in turn can be considered as a drawback in 3R applications), but the optimum configuration is still to be clearly derived and identified depending upon the system application. Optics also allow to foresee and possibly target ultrafast applications above 40G, for signal regeneration if needed. Among the current drawbacks, one should mention the relative lack of wavelength/formats flexibility of these solutions (compared to O/E solutions). It is complex or difficult to restore the input wavelength or address any C-band wavelength at the output of the device or to successfully regenerate modulation formats other than RZ. In that respect, investigations should be conducted to derive new optical solutions capable of processing more advanced modulation formats at 40G. Finally, the fact that the nonlinear transfer function of the optical is in general triggered by the input signal instantaneous power also turns out to be a drawback since it requires control circuitry. The issue of cost (footprint, power consumption, etc.) of these solutions, compared to O/E ones, is still open. In this respect, purely optical solutions incorporating all-optical clock recovery, the performance of which is still to be technically assessed, are of high interest for reducing costs. Complete integration of an all-optical 2R/3R regenerator or such parallel regenerators onto a single semiconductor chip should also contribute to make all-optical solutions cost-attractive even though acceptable performance of such fully integrated devices is still to be demonstrated.

From today's status concerning the two alternative approaches for in-line regeneration (O/E or all-optical), it is safe to say that the choice between either solution will be primarily dictated by both engineering and economical considerations. It will result from a tradeoff between overall system performance, system complexity and reliability, availability, time-to-market, and rapid returns from the technology investment.

See also

Interferometry: Overview. **Optical Amplifiers:** Semiconductor Optical Amplifiers. **Optical Communication Systems:** Wavelength Division Multiplexing.

Further Reading

Bigo S, Leclerc O and Desurvire E (1997) All-optical fiber signal processing for solitons communications. *IEEE Journal of Selected Topics on Quantum Electronics* 3(5): 1208–1223.

Dagens B, Labrousse A, Fabre S, *et al.* (2002) New modular SOA-based active–passive integrated Mach–Zehnder interferometer and first standard mode 40 Gb/s all-optical wavelength conversion on the C-band. paper PD 3.1, Proceedings of ECOCOL 02, Copenhague.

Durhuus T, Mikkelsen B, Joergensen C, Danielsen SL and Stubkjaer KE (1996) All-optical wavelength conversion by semiconductor optical amplifiers. *Journal of Lightwave Technology* 14(6): 942–954.

Lavigne B, Guerber P, Brindel P, Balmefrezol E and Dagens B (2001) Cascade of 100 optical 3R regenerators at 40 Gbit/s based on all-active Mach–Zehnder interferometers. paper We.F.2.6, Proceedings of ECOC 2001, Amsterdam.

Leclerc O, Lavigne B, Chiaroni D and Desurvire E (2002) All-optical regeneration: Principles and WDM implementation. In: Kaminow IP and Li T (eds) *Optical Fiber Technologies IVA*, chap. 15, pp. 732–784. San Diego: Academic Press.

Leuthold J, Raybon G, Su Y, *et al.* (2002) 40 Gbit/s transmission and cascaded all-optical wavelength conversion over 1,000,000 km. *Electronic Letters* 38(16): 890–892.

Öhlén P and Berglind E (1997) Noise accumulation and BER estimates in concatenated nonlinear optoelectronic repeaters. *IEEE Photon Technol. Letters* 9(7): 1011–1013.

Otani T, Suzuki M and Yamamoto S (2001) 40 Gbit/s optical 3R regenerator for all-optical networks. We.F.2.1, Proceedings of ECOC 2001, Amsterdam.

Oudar J-L, Aubin G, Mangeney J, *et al.* (2004) Ultra-fast quantum-well saturable absorber devices and their application to all-optical regeneration of telecommunication optical signals. *Annales des Télécommunications* 58(11–12): 1667–1707.

Sartorius B, Mohrle M, Reichenbacher S, *et al.* (1997) Dispersive self-Q-switching in self-pulsating DFB lasers. *IEEE Journal of Quantum Electronics* 33(2): 211–218.

Ueno Y, Nakamura S, Sasaki J, *et al.* (2001) Ultrahigh-speed all-optical data regeneration and wavelength conversion for OTDM systems. Th.F.2.1, Proceedings of ECOC 2001, Amsterdam.

B

BABINET'S PRINCIPLE

B D Guenther, Duke University, Durham, NC, USA

© 2005, Elsevier Ltd. All Rights Reserved.

In the development of the theory of diffraction, the diffraction field is due to a surface integral, the Fresnel integral, but no restrictions are imposed on the choice of the surface over which the integration must be performed. This fact leads to a very useful property called Babinet's principle, first stated by Jacques Babinet (1794–1872) in 1837 for scalar waves. We will discuss only the scalar Babinet's principle; discussion of the rigorous vector formulation can be found in a number of books on electromagnetic theory.

To introduce Babinet's principle, we label a plane, separating the source, S, and observation point, P, as Σ. If no obstructions are present, a surface integration over Σ yields the light distribution at P. If we place an opaque obstruction in this plane with a clear aperture, Σ_1, then the field at P is given by integrating over only Σ_1; contributions from Σ, outside of Σ_1, are zero since the obstruction is opaque.

We may define an aperture, Σ_2, as complementary to Σ_1 if the obstruction is constructed by replacing the transparent regions of Σ, i.e., Σ_1, by opaque surfaces and the opaque regions of Σ by clear apertures. Figure 1 shows two complementary obstructions, where the shaded region indicates an opaque surface.

The surface integral over Σ generates the field, E, in the absence of any obstruction. If obstruction Σ_1 is present then the diffraction field is E_1, obtained by integrating over Σ_1. According to Babinet's principle, the diffraction field due to obstruction Σ_2, must be

$$\tilde{E}_2 = \tilde{E} - \tilde{E}_1$$

We will look at examples of the application of the principle for both Fraunhofer and Fresnel diffraction.

Fraunhofer Diffraction

The electric field due to Fraunhofer diffraction is given by

$$E_{\mathrm{P}}(\omega_x, \omega_y) = \frac{\mathrm{i}\alpha \mathrm{e}^{-\mathrm{i}kR_0}}{\lambda R_0} \iint_{\Sigma} f(x, y)\mathrm{e}^{-\mathrm{i}(\omega_x x + \omega_y y)}\, \mathrm{d}x\, \mathrm{d}y$$

where α is the amplitude of the incident plane wave and R_0 is the distance from the obstruction to the observation point. We have defined the spatial frequencies, ω_x and ω_y by the equations

$$\omega_x = kL = -\frac{2\pi\xi}{\lambda R_0} \qquad \omega_y = kM = -\frac{2\pi\eta}{\lambda R_0}$$

This surface integral is an approximation of the Hygens–Fresnel integral and can be identified as a Fourier transform of the aperture transmission function, $f(x, y)$ in two dimensions. For our discussion we will consider only one dimension and ignore the parameters in front of the integral.

Assume that $a(x)$ is the amplitude transmission of an aperture in an obstruction, $b(x)$ is the amplitude transmission function of the complementary obstruction and g is the amplitude of the wave when no



Figure 1 An aperture Σ_1 shown by the unshaded region and its complement Σ_2. Reproduced with permission from Guenther R (1990) *Modern Optics*. New York: Wiley. Copyright © 1990 John Wiley & Sons.

obstruction is present. The Fourier transforms of the one-dimensional amplitude transmission functions of the two apertures are equal to the Fraunhofer diffraction patterns that will be generated by the two apertures

$$A(k) = \int_{-\infty}^{\infty} a(x)\mathrm{e}^{-ikx}\,\mathrm{d}x$$

$$B(k) = \int_{-\infty}^{\infty} b(x)\mathrm{e}^{-ikx}\,\mathrm{d}x$$

With no aperture present, the far field amplitude is

$$G(k) = g\int_{-\infty}^{\infty} \mathrm{e}^{-ikx}\,\mathrm{d}x$$

Babinet's principle states that

$$B(x) = G - A(x)$$

must be the Fraunhofer diffraction field of the complementary aperture. We may rewrite this equation for the diffraction field as

$$B(k) = G\delta(k) + A(k)\mathrm{e}^{\mathrm{i}\pi} \qquad [1]$$

The first term on the right of the Fraunhofer diffraction field for the complementary obstruction [1] is located at the origin of the observation plane and is proportional to the amplitude of the unobstructed wave. The second term in the equation for the Fraunhofer diffraction pattern [1] is identical to the Fraunhofer diffraction pattern of the original aperture, except for a constant phase. Thus the Fraunhofer diffraction from the two complementary apertures are equal, except for a constant phase and the bias term at the origin. Physically this means that the diffraction intensity distributions of complementary apertures will be identical but their brightness will differ!

Fresnel Diffraction

We can calculate the Fresnel diffraction from an opaque disk by applying Babinet's principle to the diffraction pattern calculated for a circular aperture.

We assume that a circular aperture of radius a is illuminated by a point source a distance Z' from the aperture. We observe the transmitted wave at the point P, located a distance Z from the aperture (see Figure 2).

The Fresnel diffraction integral is

$$\tilde{E}_{\mathrm{P}} = \frac{\mathrm{i}\alpha}{\lambda\rho D}\mathrm{e}^{-\mathrm{i}kD} \times \iint f(x,y)\mathrm{e}^{-\frac{ik}{2\rho}\left[(x-x_0)^2+(y-y_0)^2\right]}\,\mathrm{d}x\,\mathrm{d}y \qquad [2]$$



Figure 2 Geometry for the analysis of Fresnel diffraction of a circular aperture. Reproduced with permission from Guenther R (1990) *Modern Optics*. New York: Wiley. Copyright © 1990 John Wiley & Sons.

where the distance between the source and observation point is

$$D = Z + Z' + \frac{(\xi - x_s)^2 + (\eta - y_s)^2}{2(Z+Z')} \qquad \frac{1}{\rho} = \frac{1}{Z} + \frac{1}{Z'}$$

and the coordinates of the stationary point are

$$x_0 = \frac{Z'\xi + Zx_s}{Z+Z'} \qquad y_0 = \frac{Z'\eta + Zy_s}{Z+Z'}$$

The parameters of the integral are simplified by the geometry selected for Figure 2. Both the observation point and source are located on the axis of symmetry of the aperture which lies along the z-axis of a cylindrical coordinate system thus

$$x_0 = y_0 = \xi = \eta = 0 \qquad \text{and} \qquad D = Z' + Z$$

The approximation for the distance from the source and observation point to the aperture yields

$$R + R' \approx Z + Z' + \frac{r^2}{2\rho} = D + \frac{r^2}{2\rho}$$

where $r^2 = x^2 + y^2$. The cylindrical coordinate version of [2] is then

$$\tilde{E}_{\mathrm{P}} = \frac{\mathrm{i}\alpha}{\lambda\rho D}\mathrm{e}^{-\mathrm{i}kD}\int_0^a \int_0^{2\pi} f(r,\varphi)\mathrm{e}^{-\mathrm{i}\frac{kr^2}{2\rho}}\,r\,\mathrm{d}r\,\mathrm{d}\phi \qquad [3]$$

We assume that the transmission function of the aperture is a constant, $f(r,\phi) = 1$, to make the integral as simple as possible. After performing the integration over the angle ϕ, [3] can be rewritten as

$$\tilde{E}_{\mathrm{Pa}} = \frac{\mathrm{i}\alpha\pi}{D}\mathrm{e}^{-\mathrm{i}kD}\int_0^{\frac{a^2}{\rho\lambda}} \mathrm{e}^{-\mathrm{i}\pi r^2/\rho\lambda}\,\mathrm{d}\left(\frac{r^2}{\rho\lambda}\right) \qquad [4]$$

Performing the integration of [4], results in the Fresnel diffraction amplitude

$$\tilde{E}_{\mathrm{Pa}} = \frac{\alpha}{D}\mathrm{e}^{-\mathrm{i}kD}\left[1 - \mathrm{e}^{-\mathrm{i}\pi a^2/\rho\lambda}\right] \qquad [5]$$

The intensity of the diffraction field is

$$\begin{aligned} I_{\mathrm{Pa}} &= 2I_0\left(1 - \cos\frac{\pi a^2}{\rho\lambda}\right) \\ &= 4I_0 \sin^2\frac{\pi a^2}{2\rho\lambda} \qquad [6] \end{aligned}$$

[6] predicts a sinusoidal variation in intensity as the observation point moves toward the aperture.

Babinet's principle can now be used to evaluate Fresnel diffraction by an opaque disk, the same size as the circular aperture, i.e., of radius a. The field for the disk is obtained by subtracting the field, diffracted by a circular aperture, from the field of an unobstructed spherical wave, E_{P}:

$$\begin{aligned} \tilde{E}_{\mathrm{Pd}} &= \tilde{E}_{\mathrm{P}} - \tilde{E}_{\mathrm{Pa}} \\ \tilde{E}_{\mathrm{Pd}} &= \frac{\alpha}{D}\mathrm{e}^{-\mathrm{i}kD} - \tilde{E}_{\mathrm{Pa}} \\ &= \frac{\alpha}{D}\mathrm{e}^{-\mathrm{i}kD}\mathrm{e}^{-\mathrm{i}\pi a^2/\rho\lambda} \qquad [7] \end{aligned}$$

The intensity is

$$I_{\mathrm{Pd}} = I_0$$

The result of the application of Babinet's principle is the conclusion that, at the center of the geometrical shadow cast by the disk, there is a bright spot with the same intensity as would exist if no disk were present. This is Poisson's spot. The intensity of this spot is independent of the choice of the observation point along the z-axis.

See also

Diffraction: Fraunhofer Diffraction; Fresnel Diffraction.

Further Reading

Abramowitz M and Stegun IA (1964) *Handbook of Mathematical Functions*. NBS Applied Mathematics Series-55 Washington, DC: National Bureau of Standards.

Born M and Wolf E (1959) *Principles of Optics*. New York: Pergamon Press.

Guenther R (1990) *Modern Optics*. New York: Wiley.

Haus HA (1984) *Waves and Fields in Optoelectronics*. Englewood Cliffs, NJ: Prentice-Hall.

Hecht E (1998) *Optics*, 3rd edn. Reading, MA: Addison-Wesley.

Klein MV (1970) *Optics*. New York: Wiley.

Rossi B (1957) *Optics*. Reading, MA: Addison-Wesley.

Sommerfeld A (1964) *Optics*. New York: Academic Press.

C

CHAOS IN NONLINEAR OPTICS

R G Harrison and W Lu, Heriot-Watt University, Edinburgh, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Instabilities in laser emission, notably in the form of spontaneous coherent pulsations, have been observed almost since the first demonstration of laser action. Indeed, the first laser operated in 1960 by Maiman produced noisy spiked output even under conditions of quasi-steady excitation and provided the early impetus for studies of such effects. Subsequent theoretical efforts towards understanding these phenomena occurred up to the 1980s at a modest level, due in part to the wide scope of alternative areas of fertile investigation provided by lasers during this period. However, since the 1990s, there has been a major resurgence of interest in this area. This has been due to profound mathematical discoveries over this period which have revolutionized our understanding of classical dynamical systems. It is now clear that many systems containing some form of nonlinearity are dynamically unstable and even chaotic and that such behavior is deterministic. Further, the discovery that chaos evolves through particular routes with well-defined scenarios and that such routes are universal, has stimulated experimentalists to search for physical systems that exhibit these properties. These phenomena have now been observed in areas as diverse as fluid flow, chemical reactions, population ecology, and superconductor devices. The laser, perhaps the most recent newcomer to the field, is a paradigm for such investigation, owing to its simplicity both in construction and in the mathematics that describe it, and already a wide range of these phenomena have been observed. Along with a proliferation of new observations, many of the instabilities known to occur in these systems are now being reinterpreted in lieu of our new insight in this area. From this, fascinating new concepts of control and synchronization of chaos have emerged and spawned new fields of applications, not least in secure communication. In this article we introduce the general principles of dynamical instabilities, chaos, and control in lasers. For in-depth study, the reader is referred to texts and review articles cited in the Further Reading section at the end of this article.

Laser Physics

Our conventional understanding of laser physics is concerned with how cooperative order evolves from randomness. This transition is explained by first considering the ensemble of lasing atoms in thermal equilibrium. Every atom executes a small motion, giving rise to an oscillating electric dipole, described by linear dynamics. For larger motions, the atomic dipoles interfere with each other's motion and beyond a particular threshold, the motion becomes 'co-operative' or ordered over a long range. The role of the electromagnetic field in the laser cavity in ordering the induced atomic dipoles, is collectively described as giving rise to a macroscopic polarization, the magnitude of which depends on the number of dipoles (excited atoms). The dynamical interplay between the cavity field amplitude (E) as one variable and the atomic material variables of polarization (P) and population (D) of excited atoms, all of which are in general complex quantities, provide a full description of lasing action. For the simplest laser, a single mode two-level system with a homogeneously broadened gain lasing at resonance, these reduce to just three real variables, the Maxwell–Bloch equations:

$$E = -\kappa E + \kappa P \tag{1}$$

$$P = \gamma_{\perp} ED - \gamma_{\perp} P \tag{2}$$

$$D = \gamma_{II}(\lambda + 1) - \gamma_{II} D - \gamma_{II} \lambda EP \tag{3}$$

where κ is the cavity decay rate, $\gamma_\perp$ is the decay rate of atomic polarization, γ_{II} is the decay rate of population inversion, and λ the pumping parameter.

Described in this way the laser acts as a single oscillator in much the same way as a mechanical nonlinear oscillator, where laser output represents damping of the oscillator and excitation of the atoms is the driving mechanism to sustain lasing (oscillation). For ordered or coherent emission, it is necessary for one or both of the material variables (which are responsible for further lasing emission) to respond sufficiently fast to ensure a phase correlation with the existing cavity field. This is readily obtained in many typical lasers with output mirrors of relatively high reflectivity, since the field amplitude within the laser cavity will then vary slowly compared to the fast material variables which may then be considered through their equilibrium values. This situation, commonly referred to as adiabatic elimination of fast variables, reduces the dynamics of lasing action to that of one (or two) variables, the field (and population), all others being forced to adapt constantly to the slowly varying field variable. Our familiar understanding of DC laser action presupposes such conditions to hold. However when, for example, the level of excitation of the atoms is increased to beyond a certain value, i.e., the second laser threshold, all three dynamical variables may have to be considered, which satisfies the minimum requirement of three degrees of freedom (variables) for a system to display chaos. So this simple laser is capable of chaotic motion, for which the emission is aperiodic in time and has a broadband spectrum. Prediction of such behavior was initially made by Haken in 1975 through establishing the mathematical equivalence of the Maxwell–Bloch equations to those derived earlier by Lorentz describing chaotic motion in fluids.

Nonlinear Dynamics and Chaos in Lasers

In general there is no general analytical approach for solving nonlinear systems such as the Maxwell–Bloch equations. Instead solutions are obtained by numerical means and analyzed through geometric methods originally developed by Poincaré as early as 1892. This involves the study of topological structures of the dynamical trajectories in phase space of the variables describing the system. If an initial condition of a dissipative nonlinear dynamical system, such as a laser, is allowed to evolve for a long time, the system, after all the transients have died out, will eventually approach a restricted region of the phase space called an attractor. A dynamical system can have more than one attractor, in which case different initial conditions lead to different types of long-time behavior. The simplest attractor in phase space is a fixed point which is a solution with just one set of values for its dynamical variables; the nonlinear system is attracted towards this point and stays there, giving a DC solution. For other control conditions the system may end up making a periodic motion; the attractor of this motion is called a limit cycle. However, when the operating conditions exceed a certain critical value, the periodic motion of the system breaks down into a more complex dynamical trajectory, which never repeats. This motion represents a third kind of attractor in phase space called a chaotic or strange attractor.

Figure 1 shows a sequence of trajectories of the Lorentz equations in the phase space of (x, y, z) on increasing the value of one of the control parameters; this corresponds to (E, P, D) in the Maxwell–Block equations on increasing the laser pump. For a control setting near zero, all trajectories approach stable equilibrium at the origin, the topological structure of the basin of attraction being hyperbolic about zero (Figure 1a). For the laser equations, this corresponds to operation below lasing threshold for which the magnitude of the control parameter (laser gain) is insufficient to produce lasing. As the control parameter is increased, the basin lifts at its zero point to create an unstable fixed point here but with now two additional fixed points located in the newly formed troughs on either side of the zero point, which is now a saddle point. This is illustrated in Figure 1b where the system eventually settles to one or other of the two new and symmetrical fixed points, depending on the initial conditions. This corresponds to DC or constant lasing as defined by the parameter values of one or other of these points which are indistinguishable. Pictorially, think of a conventional saddle shape comprising a hyperbolic and inverted hyperbolic form in mutually perpendicular planes and connected tangentially at the origin. With the curve of the inverted hyperbola turned up at its extremity and filling in the volume with similar profiles which allow the two hyperbolic curves to merge into a topological volume, one sees that a ball placed at the origin is constrained to move most readily down either side of the inverted hyperbolas into one or other of the troughs formed by this volume. For the Lorentz system, chaotic behavior occurs at larger values of the control parameter when all three fixed points become saddles. Since none of the equilibrium points are now attracting, the behavior of the system cannot be a steady motion. Although perhaps difficult to visualize topologically, it is then possible to find a region in this surface enclosing all three points and



Figure 1 Trajectories in the three-dimensional phase space of the Lorentz attractor on increasing one of the control parameters. (Reproduced with permission from Thompson JMT and Stewart HB (1987) *Nonlinear Dynamics and Chaos*. New York: John Wiley.)

large enough so that no trajectories leave the region. Thus, all initial conditions outside the region evolve into the region and remain inside from then on. A corresponding chaotic trajectory is shown in Figure 1c. A point outwardly spirals from the proximity of one of the new saddle points until the motion brings it under the influence of the symmetrically placed saddle, the trajectory then being towards the center of this region from where outward spiraling again occurs. The spiraling out and switching over continues forever though the trajectory never intersects. In this case, arbitrarily close initial conditions lead to trajectories, which, after a sufficiently long time, diverge widely. Since a truly exact assignment of the initial condition is never possible, even numerically, a solution comprising several such trajectories therefore evolves and, as a consequence, long-term predictability is impossible. This is in marked contrast to that of the fixed point and limit cycle attractors, which settle down to the same solutions. A recording of one of these variables in time, say for a laser the output signal amplitude (in practice recorded as signal intensity, proportional to the square of the field amplitude), then gives oscillatory emission of increasing intensity with sudden discontinuities (resulting from flipping from one saddle to the other in Figure 1c) as expected.

While the Lorentz/Haken model is attractive for its relative simplicity, many practical lasers cannot be reduced to this description. Nevertheless, the



Figure 2 Lorentz-type chaos in the NH_3 laser (emitting at 81 μm optically pumped by a N_2O laser.

underlying topology of the trajectory of solutions in phase space for these systems is often found to be relatively simple and quite similar, as for three-level models descriptive of optically pumped lasers. An experimental example of such behavior for a single mode far infared molecular laser is shown in Figure 2. In other lasers, for which there is adiabatic elimination of one or other of the fast variables, chaotic behavior is precluded if, as a consequence, the number of variables of the system is reduced to less than three. Indeed this is the case for many practical laser systems. For these systems the addition of an independent external control parameter to the system, such as cavity length or loss modulation, have been extensively used as a means to provide the extra degrees of freedom. Examples include gas lasers with saturable absorbers, solid state lasers with loss modulation, and semiconductor lasers with external cavities, to name but a few. In contrast, for multimode rather than single mode lasers, intrinsic modulation of inversion (or photon flux) by multimode parametric interaction ensures the additional degrees of freedom. Furthermore, when the field is detuned from gain center, the dynamical variables E, P, D are complex, providing five equations for single mode systems, which is more than sufficient to yield deterministic chaos for suitable parameter values. Also, of significance is the remarkably low threshold found for the generation of instabilities and chaos in single-mode laser systems in which the gain is inhomogeneously broadened, an example being the familiar He–Ne laser.

Erratic and aperiodic temporal behavior of any of the system's variables implies a corresponding continuous spectrum for its Fourier transform, which is thus a further signature of chaotic motion. Time series, power spectra, and routes to chaos collectively provide evidence of deterministic behavior. Of the wide range of possible routes to chaos, three have emerged as particularly common and are frequently observed in lasers. These are period doubling, intermittency, and two-frequency scenarios. In the first, a solution, which is initially stable is found to oscillate, the period of which successively doubles at distinct values of the control parameter. This continues until the number of fixed points becomes infinite at a finite parameter value, where the variation in time of the solution becomes irregular. For the intermittency route, a signal that behaves regularly in time becomes interrupted by statistically distributed periods of irregular motion, the average number of which increases with the external control parameter until the condition becomes chaotic. The two-frequency route is more readily identified with early concepts of turbulence, considered to be the limit of an infinite sequence of instabilities (Hopf bifurcation) evolving from an initial stable solution each of which creates a new basic frequency. It is now known that only two or three instabilities (frequencies) are sufficient for the subsequent generation of chaotic motion.

Applications of Chaos in Lasers

It has been accepted as axiomatic since the discovery of chaos that chaotic motion is in general neither predictable nor controllable. It is unpredictable because a small disturbance will produce exponentially growing perturbation of the motion. It is uncontrollable because small disturbances lead to other forms of chaotic motion and not to any other stable and predictable alternative. It is, however, this very sensitivity to small perturbations that has been more recently used to stabilize and control chaos, essentially using chaos to control itself. Among the many methods proposed in the late 1980s, a feedback control approach was proposed by Ott, Grebogi, and Yorke (OGY) in which tiny feedback was used to stabilize unstable periodic orbits or fixed points of chaotic attractors. This control strategy can be best understood by a schematic of the OGY control algorithm for stabilizing a saddle point P^*, as shown in Figure 3. Curved trajectories follow a stable (unstable) manifold towards (away from) the saddle point. Without perturbation of a parameter, the starting state, s_1, would evolve to the state s_2.


Stable manifold
Motion of P^* due to parameter perturbation
P^*
Unstable manifold
State, s_2, after one map iterate (unperturbed)
State, s_3, after one map iterate with parameter perturbation
Starting state, s_1

Figure 3 The OGY control strategy for stabilizing an orbit in a chaotic attractor.

The effect of changing a parameter of the system is depicted as shifting states near P^* along the solid black arrows, whereas the combination of the unperturbed trajectory and the effect of the perturbation is to bring the state to a point, s_3, on the stable manifold. Once on the stable manifold, the trajectory naturally tends towards the desired point. This algorithm has been successfully applied in numerous experimental systems without *a priori* modeling of these systems, examples being in cardiology, electronics, and lasers. Based on the concept of feedback control, various other approaches have been developed where emphasis has been given to algorithms which are more readily implemented in practical systems, in particular that utilizing occasional proportional feedback (OPF). These pioneering studies have since inspired prolific activities, both in theory and experiment, of control of chaos across many disciplines, opening up possibilities of utilizing chaos in many diverse systems. In optics, Roy *et al.* first demonstrated dynamical control of an autonomously chaotic and high-dimensional laser system on microsecond time-scales. The laser, a diode pumped solid-state Nd:YAIG system with an intracavity KTP doubling crystal, exhibited chaotic behavior from coupling of the longitudinal modes through nonlinear sum-frequency generation. To control the system, the total laser output was sampled within a window of selected offset and width. A signal proportional the deviation of the sampled intensity from the center of the window was generated and applied to perturb the driving current of the diode laser. The sampling frequency is related to the relaxation oscillation frequency of the system. This control signal repeatedly attempts to bring the system closer to a periodic unstable orbit that is embedded in the chaotic attractor, resulting in a realization of the periodic orbit. By adjusting the frequency of the feedback signal they observed the basic (relaxation oscillation) and many higher-order periodic waveforms of the laser intensity. In a subsequent experiment, Gills *et al.* showed that an unstable steady state of this laser could also be stabilized by the OPF control technique and tracked with excellent stability to higher output power with increase of the pump excitation.

Another area to receive considerable attention in the last few years is that of synchronization of chaos. It may be expected that chaotic systems will defy synchronization because two such identical systems started at nearly the same initial conditions have dynamical trajectories that quickly becomes uncorrelated. However, it has now been widely demonstrated that when these systems are linked, their chaotic trajectories converge to be the same and remain in step with each other. Further, such synchronization is found to be structurally stable and does not require the systems to be precisely identical. Not surprisingly, these findings have attracted interest from the telecommunication community; the natural masking of information by chaotic fluctuations offering a means to a certain degree of security. In this new approach, a chaotic carrier of information can be considered as a generalization of the more traditional sinusoidal carrier. In communication systems that use chaotic waveforms, information can be recovered from the carrier using a receiver synchronized, or tuned, to the dynamics of the transmitter. Optical systems are particularly attractive since they display fast dynamics, offering the possibility of communication at bandwidths of a hundred megahertz or higher. Van Wiggeren and Roy first demonstrated data transmission rates of 10 Mbites per second using erbium-doped fiber ring lasers. These lasers are particularly well-suited for communication purposes since their lasing wavelength is close to the minimum-loss wavelength in optical fiber. Figure 3 shows a schematic of this system. The tiny message, in order of one thousandth of the carrier intensity, is decoded in the transmitter. The receiver tends to synchronize its behavior to the chaotic part of the transmitted wave (but not the message). Subtracting the waveform created in the receiver from the transmitted signal recovers the tiny message. In principle, it is possible to communicate information at ultrahigh data rate with the use of this scheme because the chaotic dynamics in the ring laser has a very large spectral width. In a later experiment they showed that a receiver can recover information at 126 Mbits/sec from the chaotic carrier (Figure 4).


Transmitter
EDFA
Ring laser
Input message
Intensity
0
50
150
200
Transmitted signal
Intensity
0
50
150
200
Communication channel
EDFA
Decoded message
Intensity
0
50
150
200
Time (ns)
Receiver

Figure 4 Schematic of communication with chaotic erbium-doped fiber amplifiers (EDFAs). Injecting a message into the transmitter laser folds the data into the chaotic frequency fluctuations. The receiver reverses this process, thereby recovering a high-fidelity copy of the message. (Reproduced with permission from Gauthier DJ (1998) Chaos has come again. *Nature* 279: 1156–1157.)

See also

Fourier Optics. **Optical Amplifiers:** Erbrium Doped Fiber Amplifiers for Lightwave Systems. **Polarization:** Introduction.

Further Reading

Abraham NB, Lugiato LA and Narducci LM (eds) (1985) Instabilities in active optical media. *Journal of the Optical Society of America B* 2: 1–272.

Arecchi FT and Harrison RG (1987) *Instabilities and Chaos in Quantum Optics*. Synergetics Series 34, 1–253. Berlin: Springer Verlag.

Arecchi FT and Harrison RG (eds) (1994) *Selected Papers on Optical Chaos*. SPIE Milestone Series, vol. MS 75, SPIE Optical Engineering Press.

Gauthier DJ (1998) Chaos has come again. *Nature* 279: 1156–1157.

Gills Z, Iwata C and Roy R (1992) Tracking unstable steady states: extending the stability regime of a multimode laser system. *Physical Review Letters* 69: 3169–3172.

Haken H (1985) Light. In: *Laser Light Dynamics*, vol. 2. Amsterdam: North-Holland.

Harrison RG (1988) Dynamical instabilities and chaos in lasers. *Contemporary Physics* 29: 341–371.

Harrison RG and Biswas DJ (1985) Pulsating instabilities and chaos in lasers. *Progress in Quantum Electronics* 10: 147–228.

Hunt ER (1991) Stabilizing high-period orbits in a chaotic system – the diode resonator. *Physical Review Letters* 67: 1953–1955.

Ott E, Grebogi C and Yorke JA (1990) Controlling chaos. *Physical Review Letters* 64: 1196–1199.

Pecore LM and Carrol TL (1990) Synchronization of chaotic systems. *Physical Review Letters* 64: 821–824.

Roy R, *et al.* (1992) Dynamical control of a chaotic laser: experimental stabilization of a globally coupled system. *Physical Review Letters* 68: 1259–1262.

VanWiggeren GD and Roy R (1998) Communication with chaotic lasers. *Science* 279: 1198–1200.

VanWiggeren GD and Roy R (1998) Optical communication with chaotic waveforms. *Physical Review Letters* 279: 1198–1200.

CHEMICAL APPLICATIONS OF LASERS

Contents

Detection of Single Molecules in Liquids
Diffuse-Reflectance Laser Flash Photolysis
Laser Manipulation in Polymer Science
Nonlinear Spectroscopies
Photodynamic Therapy of Cancer
Pump and Probe Studies of Femtosecond Kinetics
Time-Correlated Single-Photon Counting
Transient Holographic Grating Techniques in Chemical Dynamics

Detection of Single Molecules in Liquids

A J de Mello, J B Edel and E K Hill, Imperial College of Science, Technology and Medicine, London, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

A significant challenge facing experimentalists in the physical and biological sciences is the detection and identification of single molecules. The ability to perform such sensitive and selective measurements is extremely valuable in applications such as DNA analysis, immunoassays, environmental monitoring, and forensics, where small sample volumes and low analyte concentrations are the norm. More generally, most experimental observations of physical systems provide a measurement of ensemble averages, and yield information only on mean properties. In contrast, single molecule measurements permit observation of the interactions and behavior of a heterogeneous population in real time.

Over the past few years a number of techniques with sufficient sensitivity have been developed to detect single molecules. Scanning probe microscopies (most notably scanning tunneling microscopy and atomic force microscopy) have been used to great effect in the analysis of surface bound species, but for the detection of single molecules in liquids, optical methods incorporating the measurement of absorption or emission processes, have proved most successful.

The Absorption–Emission Cycle

The key concept underlying most emissive approaches to single molecule detection is that a single molecule can be cycled repeatedly between its ground state and an excited electronic state to yield multiple photons. The process can be understood by reference to Figure 1. Fluorescence emission in the condensed phase can be described using a four-step cycle. Excitation from a ground electronic state to an excited state is followed by rapid (internal) vibrational relaxation. Subsequently, radiative decay to the ground state is observed as fluorescence emission and is governed by the excited state lifetime. The final stage is internal relaxation back to the original ground state. Under saturating illumination, the rate-limiting step for this cycle is governed by the fluorescence lifetime (τ_f), which is typically of the order of a few nanoseconds. If a single molecule diffuses through an illuminated zone (e.g., the focus of a laser beam) it may reside in that


Energy
2. Vibrational relaxation, ps
Singlet
Triplet
Intersystem crossing
k_a, σ_a
3. Fluorescence emission, ns
k_f, τ_f
Competing processes: phosphorescence, k_t nonradiative decay, photodegradation, k_d
Ground
1. Electronic absorption, fs
4. Vibrational relaxation, ps
Coordinate

Figure 1 Schematic illustration of the molecular absorption–emission cycle and timescales for the component processes. Competing processes that may reduce the ultimate photon yield are also shown.

region for several milliseconds. The rapid photon absorption-emission cycle may therefore be repeated many times during the residence period, resulting in a burst of fluorescence photons as the molecule transits the beam. The burst size is limited theoretically by the ratio of the beam transit time (τ_r) and the fluorescence lifetime:

$$N_{\text{photons}} = \frac{\tau_r}{\tau_f} \qquad [1]$$

For typical values of τ_r (5 ms) and τ_f (5 ns) up to one million photons may be emitted by the single molecule. In practice, photobleaching and photodegradation processes limit this yield to about 10^5 photons. Furthermore, advances in optical collection and detection technologies enable registration of about 1–5% of all photons emitted. This results in a fluorescence burst signature of up to a few thousand photons or photoelectrons.

Successful single molecule detection (SMD) depends critically on the optimization of the fluorescence burst size and the reduction of background interference from the bulk solvent and impurities. Specifically a molecule is well suited for SMD if it is efficiently excited by an optical source (i.e., possesses a large molecular absorption cross-section at the wavelength of interest), has a high fluorescence quantum efficiency (favoring radiative deactivation of the excited state), has a short fluorescence lifetime, and is exceptionally photostable.

Ionic dyes are often well suited to SMD as fluorescence quantum efficiencies can be close to unity and fluorescence lifetimes below 10 nanoseconds. For example, xanthene dyes such as Rhodamine 6G and tetramethyl-rhodamine isothiocyanate are commonly used in SMD studies. However, other highly fluorescent dyes such as fluorescein are unsuitable for such applications due to unacceptably high photodegradation rate coefficients. Furthermore, some solvent systems may enhance nonradiative processes, such as intersystem crossing, and yield significant reduction in the photon output. Structures of three common dyes suitable for SMD are shown in Figure 2.

Signal vs Background

The primary challenge in SMD is to ensure sufficient reduction in background levels to enable discrimination between signal and noise. As an example, in a 1 nM aqueous dye solution each solute molecule occupies a volume of approximately 1 fL. However, this same volume also contains in excess of 10^{10} solvent molecules. Despite the relatively small scattering cross-section for an individual water molecule ($\sim 10^{-28}$ cm^2 at 488 nm), the cumulative scattering



Figure 2 Structures of common dye molecules suitable for SMD in solution: (a) 3,6-diamino-9-(2-carboxyphenyl)-chloride (rhodamine 110); (b) 9-(2-(ethoxycarbonyl)phenyl)-3,6-bis (ethylamino)-2,7-dimethyl chloride (rhodamine 6G); (c) 9-(2-carboxy-isothiocyanatophenyl)-3,6-bis(dimethylamino)-inner salt (tetra methylrhodamine-5-(and-6)-isothiocyanate).

signal from the solvent may swamp the desired fluorescence signal. The principal method of reducing the solvent background is to minimize the optical detection volume: the signal from a single molecule is independent of probe volume dimensions, but the background scales proportionally with the size of the detection region. Although there are several experimental approaches to SMD in solution, several factors hold common:

1. Tiny detection volumes (10^{-12}–10^{-15} L) are used to reduce background signals.
2. A low analyte concentration combined with the small observation volume, ensures that less than one analyte molecule is present in the probe volume on average.
3. High-efficiency photon collection (optics) and detection maximize the proportion of the isotropic fluorescence burst that is registered.
4. Background reduction methods are employed to improve signal-to-noise ratios. These include: optical rejection of Raman and Rayleigh scatter, time-gated discrimination between prompt scatter and delayed emission, and photobleaching of the solvent immediately before detection.

The minute volumes within which single molecules are detected can be generated in a variety of ways. Picoliter volumes can be defined by mutually orthogonal excitation and detection optics focused in a flowing stream. Much smaller, femtoliter probe volumes are generated using confocal microscopes. At this level, background emission is significantly reduced and high signal-to-noise ratios can be achieved. Confocal detection techniques are versatile and have been widely adopted for SMD in freely diffusing systems. Consequently, confocal methods will be discussed in detail in this article. The other general approach to performing SMD in solution involves the physical restriction of single molecules within defined volumes. Of particular note are techniques where single molecules are confined within a stream of levitated microdroplets. Droplet volumes are typically less than 1 fL and imaging of the entire microdroplet enables single molecule fluorescence to be contrasted against droplet 'blanks' with good signal-to-noise. Furthermore, since molecules are confined within discrete volumes, the technique can be utilized for high-efficiency molecular counting applications. More recently, spatial confinement of molecules in capillaries and microfabricated channels (with submicron dimensions) has been used to create probe volumes between 1 fL and 1 pL, and immobilized molecules on surfaces have been individually probed using wide-field microscopy with epi-illumination or evanescent wave excitation.

Single Molecule Detection using Confocal Microscopy

As previously stated, the confocal fluorescence microscope is an adaptable and versatile tool for SMD. In its simplest form, a confocal microscope is one in which a point light source, a point focus in the object plane, and a pinhole detector are all confocal with each other. This optical superposition generates superior imaging properties and permits definition of ultra-small probe volumes. The concepts behind a basic confocal microscope and its use in SMD are schematically illustrated in Figure 3. Coherent light (typically from a laser and tuned to an optical transition of the molecule under investigation) behaves as a point light source and is focused into a sample chamber using a high-numerical aperture objective lens. As a single molecule traverses the laser beam it is continuously cycled between the ground and an excited electronic state, emitting a burst of fluorescence photons. Fluorescence emission is isotropic (spontaneous emission), so photons are emitted in all directions (4π steradians).



Figure 3 Principle of confocal detection. A confocal pinhole only selects light that emanates from the focal region. Dashed lines indicate paths of light sampled above and below the focal plane that are rejected by the pinhole. The solid ray derives from the focal point, and is transmitted through the pinhole to a detector.

Consequently, the high numerical aperture is used to collect as large a fraction of photons emitted from the focal plane as possible. Designing the objective to be used with an immersion medium, such as oil, glycerin, or water, can dramatically increase the objective numerical aperture, and thus the number of collected photons. Light collected by the objective is then transmitted towards a dichroic beam splitter. In the example shown, fluorescence photons (of lower energy) are reflected towards the confocal detector pinhole, whereas scattered radiation (of higher energy) is transmitted through the dichroic towards the light source. Creation of a precise optical probe volume is effected through the definition of the confocal pinhole. The detector is positioned such that only photons that pass through the pinhole are detected. Consequently, light emanating from the focal plane in the sample is transmitted through the pinhole and detected, whereas light not deriving from the focal plane is rejected by the aperture, and therefore not detected (Figure 3).

To ensure that the maximum number of photons are detected by the system, high efficiency detectors must be used. Photomultiplier tubes (the most common detectors for light-sensing applications) are robust and versatile but have poor detection efficiencies (approximately 5% of all photons that fall on the photocathode yield an electrical signal). Consequently, the most useful detectors for SMD (or low light level) applications are single photon-counting avalanche photodiodes (SPADs). A SPAD is essentially a p–n junction reverse biased above the breakdown voltage, that sustains an avalanche current when triggered by a photon-generated carrier. Detection efficiencies for typical SPADs are normally between 60–70% and are thus ideal for SMD in solution. An approximation of the overall detection efficiency of a confocal system for SMD can be made using eqn [2], which incorporates an estimation of photon losses at all stages of the collection/detection process. Typical transmission efficiencies for each step are also shown.

$$\begin{array}{ccccccccc} \begin{array}{c}\text{overall}\\ \text{detection}\\ \text{efficiency}\end{array} & \approx & \begin{array}{c}\text{objective}\\ \text{collection}\\ \text{efficiency}\end{array} & \times & \begin{array}{c}\text{dichroic}\\ \text{transmission}\\ \text{coefficient}\end{array} & \times & \begin{array}{c}\text{additional}\\ \text{optical}\\ \text{losses}\end{array} & \times & \begin{array}{c}\text{detector}\\ \text{efficiency}\end{array} \\ \\ \mathbf{0.06} & & 0.24 & & 0.9 & & 0.5 & & 0.6 \end{array} \qquad [2]$$

Optical Probe Volumes

The precise nature of the probe volume is determined by the image of the pinhole in the sample and the spherical aberration of the microscope objective. Routinely, confocal probe volumes are approximated as resembling a cylinder with a radius defined by the diffraction-limited waist of a Gaussian beam. This approximation is useful when the incident beam is narrow or not tightly focused. However, when the radius of the incident beam is large, the corresponding diffraction limited focus is narrowed, and the probe volume more closely resembles a pair of truncated cones. Figure 4a illustrates the dependence of the curvature of the 1/e^2 intensity contour on the collimated beam radius.

Consequently, it is clear that a simple cylindrical approximation for the probe volume breaks down for wide, tightly focused beams. If a broad incident beam (diameter >1.5 mm) is used, a large noncylindrical contribution to the probe volume is anticipated and a more appropriate model is required. An alternative and more accurate model for the confocal probe volume considers the Gaussian profile of the focused beam. The 1/e^2 intensity contour radius of a Gaussian waveform with wavelength λ, at some distance z from the beam waist radius w_0, is given by eqn [3]:

$$w(z) = w_0\sqrt{1 + \left(\frac{\lambda z}{\pi w_0^2}\right)^2} \qquad [3]$$

In this case, the probe volume V is given by the volume of rotation of $w(z)$ around the z-axis between Z' and $-Z'$. The volume of rotation can therefore be



Figure 4 (a) $1/e^2$ Gaussian intensity contours plotted for a series of laser beam radii ($\lambda = 488$ nm, $f = 1.6$ mm, $n = 1.52$). (b) Cylindrical and curved components of the Gaussian probe volume. The curved contribution is more significant for larger beam radii and correspondingly tight beam waists.

simply defined according to,

$$V = \int_{-Z'}^{Z'} \pi w(z)^2 dz \qquad [4]$$

Solution of eqn [4] yields

$$V = 2\pi w_0^2 Z' + \frac{2\lambda^2}{3\pi w_0^2} Z'^3 \qquad [5]$$

The Gaussian volume expression contains two terms. The first term, $2\pi w_0^2 Z'$, corresponds to a central cylindrical volume; the second term has a more complex form that describes the extra curved volume (Figure 4b). The diffraction-limited beam waist radius w_0 can be defined in terms of the focusing objective focal length f, the refractive index n, and the collimated beam radius R according to

$$w_0 = \frac{\lambda f}{n\pi R} \qquad [6]$$

Substitution in eqn [5] yields,

$$V = 2\pi\left(\frac{\lambda f}{n\pi R}\right)^2 Z' + \frac{2\lambda^2}{3\pi}\left(\frac{n\pi R}{\lambda f}\right)^2 Z'^3$$

$$= \frac{2\lambda^2 f^2}{\pi n^2 R^2} Z' + \frac{2\pi n^2 R^2}{3 f^2} Z'^3 \qquad [7]$$

The volume is now expressed in terms of identifiable experimental variables and constants. Once again, the first term may be correlated with the cylindrical contribution to the volume, and the second term is the additional volume due to the curved contour. It is clear from Figure 4a that, for a given focal length, the noncylindrical contribution to the probe volume increases with incident beam diameter, when the diffraction limited focus is correspondingly sharp and narrow. Furthermore, it can also be seen that the second term in eqn [7] is inversely proportional to f^2, and thus the extent to which the probe volume is underestimated by the cylindrical approximation increases with decreasing focal length. This fact is significant when performing confocal measurements, since high numerical aperture objectives with short focal lengths are typical. Some realistic experimental parameters give an indication of typical dimensions for the probe volume in confocal SMD systems. For example, if $\lambda = 488$ nm, $f = 1.6$ mm, $Z' = 1.0$ µm and $n = 1.52$, a minimum optical probe volume of 1.1 fL is achievable with a collimated beam diameter of 1.1 mm.

Intensity Fluctuations: Photon Burst Statistics

When sampling a small volume within a system that may freely exchange particles with a large surrounding analyte bath, a Poisson distribution of particles is predicted. A Poisson distribution is a discrete series that is defined by a single parameter μ equating to the mean and variance of the distribution:

$$P(n = x) = \frac{\mu^x e^{-\mu}}{x!} \qquad [8]$$

Common Poisson processes include radioactive disintegration, random walks and Brownian motion. Although particle number fluctuations in the excitation volume are Poissonian in nature, the corresponding fluorescence intensity modulation induces a stronger correlation between photon counts. For a single molecular species the model is described by two parameters: an intrinsic molecular brightness and the average occupancy of the observation volume. A super-Poissonian distribution has a width or variance that is greater than its mean; in a Poisson distribution the mean value and the variance are equal. The fractional deviation Q is defined as the scaled difference between the variance and the expectation value of the photon counts, and gives a measure of the broadening of the photon counting histogram (PCH). Q is directly proportional to the molecular brightness factor ε and the shape factor γ of the optical point spread function. (γ is constant for a given experimental geometry.)

$$Q = \frac{\langle \Delta n^2 \rangle - \langle n \rangle}{\langle n \rangle} = \gamma\varepsilon \qquad [9]$$

A pure Poisson distribution has $Q = 0$; for super-Poissonian statistics $Q > 0$. Deviation from the Poisson function is maximized at low number density and high molecular brightness.

In a typical SMD experiment raw data are generally collected with a multichannel scalar and photons are registered in binned intervals. Figure 5 illustrates typical photon burst scans demonstrating the detection of single molecules (R-phycoerythrin) in solution. Fluorescence photon bursts, due to single molecule events, are clearly distinguished above a low background baseline (top panel) of less than 5 counts per channel in the raw data. It is noticeable that bursts vary in both height and size. This is in part due to the range of possible molecular trajectories through the probe volume, photobleaching kinetics, and the nonuniform illumination intensity in the probe region. In addition, it can be seen that the burst frequency decreases as bulk solution concentration is reduced. This effect is expected since the properties of any given single-molecule event are determined by molecular parameters alone (e.g., photophysical and diffusion constants) and concentration merely controls the frequency/number of events.

Although many fluorescence bursts are clearly distinguishable from the background, it is necessary to set a count threshold for peak discrimination in order to correctly identify fluorescence bursts above the background. A photocount distribution can be used as the starting point for determining an appropriate threshold for a given data set. The overlap between signal and background photocount distributions affects the efficiency of molecular detection. Figure 6 shows typical signal and background photocount probability distributions, with a threshold set at approximately 2 photocounts per channel. The probability of spurious (or false)



Figure 5 Photon burst scans originating from 1 nM and 500 pM R-phycoerythrin buffered solutions. Sample is contained within a 50 μm square fused silica capillary. Laser illumination = 5 μW, channel width = 1 ms. The top panel shows a similar burst scan originating from a deionized water sample measured under identical conditions.



Figure 6 Simulated fluorescence and background photocount probability distributions. The vertical dashed line at 2 counts represents an arbitrarily defined threshold value for peak determination.



Figure 7 A photon counting histogram generated from a 16 second photon burst scan originating from a 10 μg/mL solution of 1000 nm fluorescent microbeads. The dotted curve shows a least-squares fit of early channels to a Poisson distribution, and the dashed vertical line marks the peak threshold (defined as $\mu + 3\sqrt{\mu} = 4.47$ counts).

detection resulting from statistical fluctuations in the background can be quantified by the area under the 'background' curve at photocount values above the threshold. Similarly, the probability that 'true' single molecule events are neglected can be estimated by the area under the 'fluorescence' curve at photocount values below the threshold. Choice of a high threshold value will ensure a negligible probability of calling a false positive, but will also exclude a number of true single molecule events that lie below the threshold value. Conversely, a low threshold value will generate an unacceptably high number of false positives. Consequently, choice of an appropriate threshold is key in efficient SMD.

Since the background shot noise is expected to exhibit Poisson statistics, the early part of the photocount distribution (i.e., the portion that is dominated by low, background counts) can be modeled with a Poisson distribution, to set a statistical limit for the threshold. Photon counting events above this threshold can be defined as photon bursts associated with the presence of single molecules. In an analogy with Gaussian systems the selected peak discrimination threshold can be defined as three standard deviations from the mean count rate:

$$n_{\text{threshold}} = \mu + 3\sqrt{\mu} \qquad [10]$$

Adoption of a threshold that lies 3 standard deviations above the mean yields a confidence limit that is typically greater than 99%. Figure 7 illustrates a sample photocount distribution, a least-squares fit to an appropriate Poisson distribution, and the calculated threshold that results. Once the threshold has been calculated, its value is subtracted from all channel counts and a peak search utility used to identify burst peaks in the resulting data set.

Data Filtering

As stated, the primary challenge in detecting single molecules in solution is not the maximization of the detected signal, but the maximization of the signal-to-noise ratio (or the reduction of background interferences). Improving the signal-to-noise ratio in such experiments is important, as background levels can often be extremely high.

Several approaches have been used to smooth SMD data with a view to improving signal-to-noise ratios. However, the efficacy of these methods is highly dependent on the quality of the raw data obtained in experiment. As examples, three common methods are briefly discussed. The first method involves the use of a weighted quadratic sum (WQS) smoothing filter. The WQS function creates a weighted sum of adjacent terms according to

$$\tilde{n}_{k,WQS} = \sum_{j=0}^{m-1} w_j (n_{k+j})^2 \qquad [11]$$

The range of summation m is the same order as the burst width, and the weighting factors w_j are chosen



Figure 8 Effect of various smoothing filters on a 750 ms photon burst scan originating from a 1 nM R-phycoerythrin buffered solution. Raw data are shown in the top panel.

to best discriminate between single-molecule signals and random background fluctuations. This method proves most useful for noisy systems, in which the raw signal is weak. There is a practical drawback, in that peak positions are shifted by the smoothing function, and subsequent burst analysis is therefore hampered.

Another popular smoothing filter is the Lee-filtering algorithm. The Lee filter preferentially smoothes background photon shot noise and is defined according to

$$\tilde{n}_k = \bar{n}_k + (n_k - \bar{n}_k)\frac{\sigma_k^2}{\sigma_k^2 + \sigma_0^2} \qquad [12]$$

where the running mean (n_k) and running variance (σ_k^2) are defined by

$$\bar{n}_k = \frac{1}{(2m+1)}\sum_{j=-m}^{m} n_{k+j} \quad m < k \leq N - m \qquad [13]$$

$$\sigma_k^2 = \frac{1}{(2m+1)}\sum_{j=-m}^{m} (n_{k+j} - \bar{n}_{k+j})^2 \quad 2m < k \leq N - 2m \qquad [14]$$

for a filter $(2m+1)$ channels wide. Here, n_k is the number of detected photons stored in a channel k, σ_0 is a constant filter parameter, and N is the total number of data points.

A final smoothing technique worth mentioning is the Savitsky-Golay smoothing filter. This filter uses a least-squares method to fit an underlying polynomial function (typically a quadratic or quartic function) within a moving window. This approach works well for smooth line profiles of a similar width to the filter window and tends to preserve features such as peak height, width and position, which may be lost by simple adjacent averaging techniques. Figure 8 shows the effects of using each approach to improve signal-to-noise for raw burst data.

Photon Burst Statistics

A valuable quantitative analysis method for analysis of fluorescence bursts utilizes the analysis of Poisson statistics. Burst interval distributions are predicted to follow a Poissonian model, in which peak separation frequencies adopt an exponential form. The probability of a single molecule (or particle) event occurring after an interval Δt is given by eqn [15]:

$$N(\Delta t) = \lambda \exp(-\beta t) \qquad [15]$$

where λ is a proportionality constant and β is a characteristic frequency at which single molecule events occur. The recurrence time τ_R can then be simply defined as

$$\tau_R = \frac{1}{\beta} \qquad [16]$$



Figure 9 Burst interval distribution analysis of photon burst scans. Data originate from 1 μm fluorescent beads moving through 150 μm wide microchannels at flow rates of 200 nL min^{-1} (circles) and 1000 nL min^{-1} (squares). Least squares fits to a single exponential function are shown by the solid lines.

Equation [6] simply states that longer intervals between photon bursts are less probable than shorter intervals. Furthermore, the recurrence time reflects a combination of factors that control mobility, probe volume occupancy, or other parameters in the single molecule regime. Consequently, it is expected that τ_R should be inversely proportional to concentration, flow rate or solvent viscosity in a range of systems. Figure 9 shows an example of frequency $N(\Delta t)$ versus time plots for two identical particle systems moving at different velocities through the probe volume. A least-squares fit to a single exponential function yields values of $\tau_R = 91$ ms for a volumetric flow rate of 200 nL/min and $\tau_R = 58$ ms for a volumetric flow rate of 1000 nL/min.

Temporal Fluctuations: Autocorrelation Analysis

Autocorrelation analysis is an extremely sensitive method for detecting the presence of fluorescence bursts in single molecule experiments. This approach essentially measures the average of a fluctuating signal as opposed to the mean spectral intensity. As previously discussed, the number of molecules contained within a probe volume at any given time is governed by Poisson statistics. Consequently, the root mean square fluctuation can be defined according to eqn [17],

$$\frac{\sqrt{\langle(\delta N)^2\rangle}}{\langle N\rangle} = \frac{\sqrt{\langle(N-\langle N\rangle)^2\rangle}}{\langle N\rangle} = \frac{1}{\sqrt{\langle N\rangle}} \qquad [17]$$

where N is the number of molecules. It is observed that the relative fluctuation diminishes as the number of particles measured is increased. Hence, it is important to minimize the number of molecules present in the probe volume. It should be noted, however, that if there are too few molecules in the solution there will be long dark periods were no single molecule bursts are observed. If the probe volume is bathed in radiation of constant intensity, fluctuation of the resulting fluorescence signal can simply be defined as deviations from the temporal signal average:

$$\langle F(t)\rangle = \frac{1}{T}\int_0^T F(t)\mathrm{d}t \qquad [18]$$

Here, t is defined as the total measurement time, $F(t)$ is the fluorescence signal at time t, and $\langle F(t)\rangle$ is the temporal signal average. Fluctuations in the fluorescence intensity, $\delta F(t)(\delta F(t) = F(t) - \langle F(t)\rangle)$, with time t, about an equilibrium value $\langle F\rangle$, can be statistically investigated by calculating the normalized autocorrelation function, $G(\tau)$, where

$$G(\tau) = \frac{\langle F(t+\tau)F(t)\rangle}{\langle F\rangle^2} = \frac{\langle \delta F(t+\tau)\delta F(t)\rangle}{\langle F\rangle^2} + 1 \qquad [19]$$

In dedicated fluorescence correlation spectroscopy experiments, the autocorrelation curve is usually generated in real time in a high-speed digital correlator. Post data acquisition calculation is also possible using the following expression

$$G(\tau) = \sum_{t=0}^{N-1} g(t)g(t+\tau) \qquad [20]$$

Here $g(t)$ is the total number of counts during the time interval $(t, t+\Delta t)$, $g(t+\tau)$ is the number of counts detected in an interval of Δt at a later time $t+\tau$, and N is the total number of time intervals in the dataset. In a diffusion controlled system with a single fluorescent molecule that is irradiated with a three dimensional Gaussian intensity profile, the autocorrelation curve is governed by the mean probe volume occupancy N and the characteristic diffusion time (τ_D). The laser beam waist radius ω and the probe depth $2z$ describe the Gaussian profile:

$$G(\tau) = 1 + \frac{1}{N}\left(1+\frac{\tau}{\tau_d}\right)^{-1}\left(1+\left(\frac{\omega}{z}\right)^2\frac{\tau}{\tau_d}\right)^{-1/2} \qquad [21]$$

The diffusion time is a characteristic molecular residence time in the probe volume and inversely



Figure 10 Autocorrelation analysis of photon burst scans of 1 μm fluorescent beads moving through 150 μm wide microchannels at flow rates of 500 nL min^{-1} (stars) and 1000 nL min^{-1} (circles). Solid lines represent fits to the data according to eqn [23].

related to the translational diffusion coefficient for the molecule:

$$D = \frac{w^2}{4\tau_D} \qquad [22]$$

In a flowing system, the autocorrelation function depends on the average flow time through the probe volume τ_{flow}. A theoretical fit to the function can be described according to

$$G(\tau) = 1 + \frac{1}{N} A \exp\left\{\left(\frac{\tau}{\tau_{\text{flow}}}\right)^2 A\right\}$$
$$A = \left(1 + \frac{\tau}{\tau_d}\right)^{-1}\left(1 + \left(\frac{\omega}{z}\right)^2 \frac{\tau}{\tau_d}\right) \qquad [23]$$

where N is the mean probe volume occupancy; the flow velocity v can then be extracted from the characteristic flow time according to

$$v = \frac{w}{\tau_{\text{flow}}} \qquad [24]$$

It should be noted that in the case that directed flow is negligible or defined to be zero, the autocorrelation function simplifies to eqn [21].

Figure 10 illustrates experimentally determined autocorrelation curves for two identical particle systems moving at different velocities through the probe volume. As particle flow velocity is increased, the width of the autocorrelation curves is seen to narrow as a result of the reduced residence time in the probe volume. A plot of the reciprocal of the full width half maximum of the autocorrelation curve as a function of volumetric flow rate is linear, and provides a simple way of calculating particle/molecule velocities within flowing systems.

Applications

The basic tools and methods outlined in this chapter have been used to perform SMD in a variety of chemically and biologically relevant systems, and indeed there is a large body of work describing the motion, conformational dynamics and interactions of individual molecules (see Further Reading). A primary application area has been in the field of DNA analysis, where SMD methods have been used in DNA fragment sizing, single-molecule DNA sequencing, high-throughput DNA screening, single-molecule immunoassays, and DNA sequence analysis. SMD methods have also proved highly useful in studying protein structure, protein folding, protein-molecule interactions, and enzyme activity.

More generally, SMD methods may prove to be highly important as a diagnostic tool in systems where an abundance of similar molecules masks the presence of distinct molecular anomalies that are markers in the early stages of disease or cancer.

See also

Microscopy: Confocal Microscopy.

Further Reading

Ambrose WP, Goodwin PM, Jett JH, Van Orden A, Werner JH and Keller RA (1999) Single molecule fluorescence spectroscopy at ambient temperature. *Chem. Rev.* 99: 2929–2956.

Barnes MD, Whitten WB and Ramsey JM (1995) Detecting single molecules in liquids. *Anal. Chem.* 67: 418A–423A.

Basche T, Orrit M and Rigler R (2002) *Single Molecule Spectroscopy in Physics, Chemistry, and Biology.* New York: Springer-Verlag.

Zander CJ, Enderlein J and Keller RA (2002) *Single Molecule Detection in Solution: Methods and Applications*. New York: John Wiley & Sons.

Diffuse-Reflectance Laser Flash Photolysis

D R Worrall and S L Williams, Loughborough University, Loughborough, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Flash photolysis was developed as a technique to study short-lived intermediates in photoinduced reactions by George Porter (later Lord Porter of Luddenham) and Ronald Norrish in 1949, drawing on Porter's wartime experience with radar techniques. Such was the impact of this development that it earned the Nobel prize jointly for Porter, Norrish, and Eigen in 1967. In this article we will describe the application of flash photolysis to opaque, scattering samples, detailing how light propagation in such samples can be treated theoretically, and will discuss methods by which the data obtained from diffuse reflectance flash photolysis experiments may be analyzed.

The technique of flash photolysis was originally based on using an intense flash of light (the photolysis flash) from a xenon tube to excite the sample, followed a certain time delay later by a spectroscopic flash of lower intensity from a second flash tube, the light from the latter being detected using a photographic plate. The photolysis flash is of sufficient intensity to produce a large population of intermediates (radicals, ions, excited states, isomers) in the sample, which then absorb light from the spectroscopic flash depending on the concentration of intermediates according to the Beer–Lambert law:

$$A = \varepsilon c l \qquad [1]$$

where A is the sample absorbance, ε the molar absorption coefficient, c the concentration and l the pathlength. The absorbance is related to the incident and transmitted intensities as

$$A = \log_{10} I_0/I \qquad [2]$$

With I_0 the incident and I the transmitted intensities, there is therefore an exponential fall-off of intensity with pathlength for a homogeneous absorber. Hence, by monitoring the evolution of the absorption spectra, the changes in concentration of the photoproduced intermediates and hence the kinetics of the processes in which they are involved are elucidated.

Flash photolysis has evolved subsequently to make use of laser sources and sophisticated electronic detection apparatus to push the limits of time resolution to the femtosecond regime. Indeed, recently the Nobel prize for chemistry was awarded to Ahmed Zewail for his work with ultrafast pump-probe techniques. However, in its conventional geometry, flash photolysis is limited to transparent samples, since it is necessary to be able to probe the excited species by monitoring the absorption spectra.

Many biological systems and industrially important samples are opaque or highly scattering, and hence the attenuation of light through the sample is no longer described by the Beer–Lambert law. In 1981, Frank Wilkinson and Rudolph Kessler had the idea of using diffusely reflected light to interrogate the changes in concentration within a scattering sample subjected to a high-intensity excitation pulse. When photons enter a sample, they may be absorbed or scattered. Those which are scattered may re-emerge from the irradiated surface as diffusely reflected light. The intensity of diffusely reflected light emerging from the surface at a particular wavelength is a unique function of the ratio of scattering to absorption. The more scattering events occurring before absorption, the more likely the photon is to escape from the sample as diffusely reflected light. Hence the probability of escape decreases as the absorption probability increases, and the diffusely reflected light is deficient in those wavelengths where the absorption is strongest, i.e., the ratio of the incident to absorbed light intensity at a given wavelength is related to the absorption of the sample at that wavelength.

Kubelka–Munk Theory of Reflectance

The theory which describes the relationship between incident and scattered light intensity, absorption and scatter, and concentration which is widely applied in this context, is the Kubelka–Munk theory of reflectance. The theory was originally developed to describe the reflectance characteristics of paint films but it works quite well for many samples containing a homogeneous distribution of scatterers and absorbers. The limiting assumption in this theory is that the scatterers from which the scattering layer is composed are very much smaller than the total layer thickness. Additionally, the layer should be optically thick such that all of the light entering the layer should be either absorbed or reflected, with a negligible fraction transmitted.

For a layer of thickness X diffusely irradiated with monochromatic light, the diagram shown in Figure 1



Figure 1 Schematic of counterpropagating fluxes in a diffusely irradiated scattering medium.

can be constructed, with I the incident flux and J the diffusely reflected flux, and i and j the fluxes traveling upwards and downwards through an infinitesimally small thickness element dx. Two further parameters may be defined which are characteristic of the medium.

K The absorption coefficient. Expresses the attenuation of light due to absorption per unit thickness.
S The scattering coefficient. Expresses the attenuation of light due to scattering per unit thickness.

Both of these parameters can be thought of as arising due to the particle (or chromophore) acting as a sphere of characteristic size, which casts a shadow either due to the prevention of on-axis transmission or due to absorption. The scattering or absorption coefficient then depends on the effective size of this sphere, and the number density of spheres in the medium. In each case, the probability P of a photon being transmitted through a particular thickness X of a medium is related exponentially to the absorption or scattering coefficient:

$$P = \exp(-KX) \tag{3}$$

$$P = \exp(-SX) \tag{4}$$

The scattering coefficient S depends on the refractive index difference between the particle and the dispersion medium. The scattering coefficient is also dependent upon the particle size, and shows an inverse correlation, i.e., the scattering coefficient increases as the particle size decreases. This effect is a function of the size of the particle relative to the wavelength of light impinging on it, with the scattering coefficient increasing as the wavelength decreases. However, this change with wavelength is small provided the particle size is large relative to the wavelength of the light.

The effect of the material in the element dx on the counterpropagating fluxes i and j depends on the absorption and scattering coefficients. Both i and j will be attenuated by both absorption and scattering:

$$i_2 = i_1 - i_1(S + K)\mathrm{d}x \tag{5}$$

$$j_2 = j_1 - j_1(S + K)\mathrm{d}x \tag{6}$$

Both i and j are reinforced by backscattering from the other flux:

$$i_2 = i_1 + j_1 S\mathrm{d}x \tag{7}$$

$$j_2 = j_1 + i_1 S\mathrm{d}x \tag{8}$$

The net effect of this in the attenuation of the flux propagating into the sample (i) and the flux backscattered from the sample (j) can be expressed as the following differential equations:

$$\mathrm{d}i = (S + K)i_1\mathrm{d}x - j_1 S\mathrm{d}x \tag{9}$$

$$\mathrm{d}j = -(S + K)j_1\mathrm{d}x + i_1 S\mathrm{d}x \tag{10}$$

For a sample of infinite thickness, these equations can be solved to give an analytical solution for the observed reflectance of the sample in terms of the absorption and scattering coefficients:

$$\frac{K}{S} = \frac{(1 - R_\infty)^2}{2R_\infty} \tag{11}$$

where R_∞ is the reflectance from a sample of such thickness that an increase in sample thickness has no effect on the observed reflectance. The absorption coefficient K is dependent upon the concentration of absorbers in the sample through

$$K = 2\varepsilon c \tag{12}$$

with ε the naperian absorption coefficient, c the concentration of absorbers and the factor 2 which is the geometrical factor for an isotropic scatterer. For multiple absorbers, K is simply the linear sum of absorption coefficients and concentrations. Hence for a diffusely scattering medium, an expression analogous to the Beer–Lambert law can be derived to relate concentration to a physically measurable parameter, in this case the sample reflectance. The ratio K/S is usually referred to as the Kubelka–Munk remission function, and is the parameter usually quoted in this context. It is important to note that the relationship with concentration is only valid for a homogeneous distribution of absorbers within a sample.

Transient Concentration Profiles

As has been discussed in the previous section, a light flux propagating through a scattering medium is attenuated by both scattering and absorption events, whilst in a nonturbid medium attenuation is by absorption only. Hence even in a sample with a very low concentration of absorbers, the light flux is rapidly attenuated as it penetrates into the sample by scattering events. This leads to a significant flux gradient through the sample, resulting in a reduction in the concentration of photo-induced species as penetration depth into the sample increases. There are three distinct concentration profiles which may be identified within a scattering sample which are dependent on the scattering and absorption coefficients. These concentration profiles are interrogated by a beam of analyzing light, and hence an understanding of the effect of these differing profiles on the diffusely reflected intensity is vital in interpreting transient absorption data. The transient depth profiles are illustrated in Figure 2.

Kubelka–Munk Plug

This occurs when the photolysis flash, i.e., laser fluence is high and the absorption coefficient is low at the laser wavelength. If we assume a simple photophysical model involving simply the ground state S_0, the first excited singlet state S_1 and first excited triplet state T_1, and we assume that either the quantum yield of triplet state production is high or the S_1 lifetime is very much shorter than the laser pulse allowing re-population of the ground state, then it is possible at high enough fluence to completely convert all of the S_0 states to T_1 states within the sample. Provided the fluence is high enough, this complete conversion will penetrate some way into the sample (Figure 2). Under circumstances where the T_1 state absorbs strongly at some wavelength other than the photolysis wavelength, probing at this wavelength will result in the probe beam being attenuated significantly within a short distance of the surface of the sample, and thus will only interrogate regions where there is a homogeneous excited state concentration. Under these circumstances the reflectance of the sample as a function of the concentration of excited states is described by the Kubelka–Munk equation, and the change in remission function can be used to probe the change in excited state concentration.



Figure 2 Transient concentration profiles following pulsed laser excitation of a scattering and absorbing sample.

Exponential Fall-Off of Concentration

This occurs when the laser fluence is low and the absorption coefficient at the laser wavelength high. Again considering the simple photophysical model, most of the laser flux will be absorbed by the ground state in the first few layers of sample, and little will penetrate deeply into the sample. In the limiting case this results in an exponential fall-off of transient concentration with penetration depth into the sample (Figure 2). Here the distribution of absorbers is not random and the limiting Kubelka–Munk equation is no longer applicable since the mean absorption coefficient varies with sample penetration depth. Lin and Kan solved eqs [9] and [10] with the absorption coefficient K varying exponentially with penetration depth and showed that the series solution converges for changes in reflectance of less than 10% such that the reflectance change is a linear function of the number of absorbing species.

Intermediate Case

Between the two extremes described above is a case where significant transient conversion takes place at the front surface, but with little penetration into the sample. This can occur, for example, with high laser fluences and large ground state absorption coefficients at the laser wavelength. Under these circumstances, illustrated in Figure 2, the analyzing light interrogates not only the transient concentration profile, but also a significant amount of the analyzing light may penetrate through the transient layer into the unconverted sample behind, if the transient absorption at the analyzing wavelength is low. This creates a more complex problem for analysis since effectively the sample is irradiated from both front and back faces, with consequent effects on the diffusely reflected intensity. It is possible to numerically model the reflectance change as a function of transient concentration under these circumstances but a precise knowledge of the absorption and scattering coefficients is required. Under most circumstances, this case is avoided and diffuse reflectance flash photolysis experiments are arranged such that one of the two limiting cases above, generally the exponential fall-off (usually achieved by attenuation of the laser beam), prevails in a particular experiment.

Sample Geometry

In the case of conventional nanosecond laser flash photolysis, it is generally the case that right-angled geometry is employed for the photolysis and probe beams (Figure 3a). This geometry has a number of advantages over alternatives. The photolysis beam and analyzing beam are spatially well separated, such that the analyzing beam intensity is largely unaffected by scattered photolysis light. Also, the fluorescence generated by the sample will be emitted in all directions, whilst the analyzing beam is usually collimated allowing spatial separation of fluorescence and analyzing light; sometimes an iris is used to aid this spatial discrimination. This geometry is appropriate for quite large beam diameters and fluences; where smaller beams are used collinear geometry may be more appropriate in order to achieve long interaction pathlengths.



Figure 3 Sample geometries for (a) conventional and (b,c) diffuse reflectance flash photolysis. ⟶, photolysis beam; ⟶, analyzing beam.

In the case of nanosecond diffuse reflectance flash photolysis, the geometry required is quite different (Figure 3b,c). Here, the photolysis beam and analyzing beam must be incident on the same sample surface, and the diffusely reflected analyzing light is collected from the same surface. The geometry is often as shown in Figure 3b, where the analyzing light is incident almost perpendicularly on the sample surface, with the photolysis beam incident at an angle such that the specular reflection of the photolysis beam passes between detector and analyzing beam (not shown). Alternatively, the geometry shown in Figure 3c may be employed, where diffusely reflected light is detected emerging perpendicular to the sample surface. In both cases, the geometry is chosen such that specular (mirror) reflection of either exciting or analyzing light from the sample is not detected, since specular reflection is light which has not penetrated the sample and therefore contains no information regarding the concentrations of species present. A requirement, as in conventional flash photolysis, is that the analyzing beam probes only those areas which are excited by the photolysis beam, requiring the latter to be larger than the former. The nature of the scattering described previously means that the required geometry does not give spatial discrimination at the detector between photolysis and analyzing light, and fluorescence. This is since both analyzing and photolysis light undergo scattering and absorption processes (although with wavelength-dependent absorption and scattering coefficients) and emerge with the same spatial profiles. Fluorescence, principally that stimulated by the photolysis beam since this is of greatest intensity, originates from within the sample but again undergoes absorption and scattering and emerges with the same spatial distribution as the exciting light. In diffuse reflectance flash photolysis, separation of the analyzing light from the excitation or fluorescence must be achieved using spectral (filters and/or monochromators) or temporal, rather than spatial discrimination. Time-gated charge coupled devices

(CCD) or photodiode array detectors can be effectively used in nanosecond laser flash photolysis to exclude excitation light and fluorescence, since these occur on time-scales usually much shorter than the transient absorption of species of interest. The usual analyzing light source used in nanosecond diffuse reflectance flash photolysis is a xenon arc lamp, due to its good spectral coverage and high intensity. High probe intensity is particularly important in diffuse reflectance flash photolysis since the scattered intensities are often low, and the scattered light emerges in a large solid angle, only part of which can be effectively collected and detected. Also, high intensities allow for the light from the analyzing source to dominate over fluorescence if the latter is relatively weak.

In femtosecond diffuse reflectance laser flash photolysis, sample geometry considerations are also important. Such experiments are performed using the pump-probe technique, with the probe often being a femtosecond white-light continuum. The sample geometry employed is illustrated in Figure 4.

Here the pump and probe are almost colinear, and are incident on the same sample area; again, the requirement is for the pumped area to be larger than the probed area. Diffusely reflected light is then collected and analyzed, time resolution being achieved by varying the delay between pump and probe beams. It should be noted that the temporal resolution is worse than in conventional pump-probe techniques. In conventional femtosecond flash photolysis, the time resolution is generally limited by the widths of pump and probe pulses; in diffuse reflectance mode, the pulses undergo numerous refractions, reflections, and diffractions such that the pulse is temporally broadened during its transit through the material. The extent of this broadening is a sensitive function of the optical properties of the individual sample.



Figure 4 Sample geometry for femtosecond diffuse reflectance flash photolysis. $\xrightarrow{}$, photolysis beam; $\longrightarrow$, analyzing beam.

Kinetic Analysis

Kinetic analysis, and of course time-resolved spectroscopic analysis, require a quantitative treatment of the concentration changes within a sample following an excitation pulse as a function of time. When studying transient absorption phenomena in opaque samples, it is usual to define the reflectance change in terms of the sample reflectance before and after excitation, such that in spectrally resolved data a transient difference spectrum rather than an absolute reflectance spectrum of the transient species is obtained. The latter can, however, be reconstructed from a knowledge of the absorption coefficients and concentration of the species involved. It is possible to define the reflectance change as

$$\frac{\Delta J_t}{J_0} = 1 - \frac{R_t}{R_0} \qquad [13]$$

where R_0 and R_t represent the intensity of probe light diffusely reflected from the sample before excitation and at a time t after excitation, respectively. Frequently reflectance change is expressed as '% absorption', which is defined in eqn [14].

$$\%\ \text{absorption} = 100 \times \left(1 - \frac{R_t}{R_0}\right) \qquad [14]$$

These parameters are often used as being proportional to transient concentration, subject to satisfying the criteria for an exponential fall-off of transient concentration with penetration depth as discussed previously, and are used to replace transient concentration in kinetic equations used in data analysis.

It is generally the case that the samples studied using diffuse reflectance laser flash photolysis have either some degree of heterogeneity, for example paper, microcrystalline cellulose, silica gel or alumina, or have well-defined porous structures such as zeolites. Molecules adsorbed to these supports may be present on the surface, within micro- or mesopores, or intimately included within the structure. Hence each molecule may experience its own unique environment, and this will obviously influence its observed photophysics. It is therefore the case that in these systems, even very simple photo-induced reactions such as unimolecular photoisomerizations do not follow first-order kinetics; rather, a distribution of rates is observed which reflect the differing environments experienced by the molecules, and hence the molecules act as probes of this heterogeneity.

There are a number of approaches to kinetic analysis in opaque, often heterogeneous systems, as described below.

Rate Constant Distributions

Here the sample heterogeneity is treated as producing a series of micro-environments, and the reaction studied will have its own unique rate constant in each of these environments. The width of the observed rate constant distribution therefore describes the number of these possible environments, with the distribution amplitude at any particular rate constant, reflecting the probability of the molecule existing in the corresponding environment.

Exponential series lifetime distribution analysis is the simplest approach to distributed lifetime analysis. This analysis has the inherent advantage that there are no presuppositions regarding the kinetic model describing the data. Rather, a large number of exponentials with fixed rate constants and with amplitudes as adjustable parameters are applied to the data, and a least-squares procedure used to optimize the amplitude of each exponential. Generally there is a relationship between the rate constants, they being equally spaced on either a linear or logarithmic scale. Physically this can be interpreted as a large number of first-order or pseudo-first-order (in the case of bimolecular reactions) rates arising from the sample heterogeneity. Hence the rate constant distribution emerges naturally from the fitting procedure, with no preimposed constraints. Since there are a large number of adjustable parameters, these models are applied most successfully to data with good signal-to-noise.

Alternative approaches involve imposing a distribution shape onto a set of exponentials, and optimizing this distribution to the data. This approach has the advantage that by assuming a rate constant distribution, the relative amplitudes of the exponentials are fixed and hence the number of fitting parameters greatly reduced. One of the more successful models applied in this context is that developed by Albery *et al.* In the development of their model it is assumed that, for the reaction in question, the free energy of activation, $\Delta G^{\neq}$, is distributed normally around a mean value $\Delta\bar{G}^{\neq}$ according to eqn [15]:

$$\Delta G^{\neq} = \Delta\bar{G}^{\neq} - \gamma x R T \qquad [15]$$

with γ being the width of the distribution for $\infty \geq x \geq -\infty$. This assumed normal distribution of the free energy of activation leads to a log-normal distribution of the decay rate constants distributed around some average rate constant $\bar{k}$. The dispersion in the first-order rate constant is then

$$\ln(k) = \ln(\bar{k}) + \gamma x \qquad [16]$$

The equation used to describe the data is given as:

$$\frac{c}{c_0} = \frac{\int_{-\infty}^{\infty} \exp(-t^2)\exp\left[-\bar{k}t\exp(\gamma t)\right]\mathrm{d}t}{\int_{-\infty}^{\infty} \exp(-t^2)\mathrm{d}t} \qquad [17]$$

with c and c_0 being concentration at time $t = t$ and $t = 0$ relative to the excitation flash, respectively. Where reflectance change is proportional to transient concentration, reflectances can be used directly in place of concentrations. This equation can be solved by making the following substitutions:

$$\int_{-\infty}^{\infty} \exp(-t^2)\mathrm{d}t = \pi^{1/2} \qquad [18]$$

$$\int_{-\infty}^{\infty} \exp(-t^2)\exp\left[-\bar{k}t\exp(\gamma t)\right]\mathrm{d}t = \int_0^1 \lambda^{-1}\exp\left(-(\ln\lambda^2)\right)\left(\exp(-\bar{k}t\lambda^{\gamma}) + \exp(-\bar{k}t\lambda^{-\gamma})\right)\mathrm{d}\lambda \qquad [19]$$

Hence here there are only two fitting parameters, namely the width of the distribution γ and the distribution center, $\bar{k}$. Note that for $\gamma = 0$, eqn [17] reduces to a single exponential function.

A further model which constrains the rate constant distribution, which has been successfully applied to describe the rates of photo-induced processes on silica gel surfaces, is a Lévy stable distribution of rate constants, described as:

$$\mathrm{P}(\bar{k}, \alpha, \gamma) = \frac{1}{\pi}\int_0^{\infty} \exp(-\gamma q^{\alpha})\cos(\bar{k}\mathrm{q})\mathrm{dq} \qquad [20]$$

where α is the characteristic power law exponent ($0 < \alpha \leq 2$) and γ is the distribution width ($\gamma > 0$). Special cases of the Lévy stable distribution occur for $\alpha = 1$ and $\alpha = 2$, where the distribution shape becomes Lorentzian and Gaussian, respectively. The Lévy distribution gives an increasing weighting to the tails of the distribution as the distribution width decreases, and can be described as a random walk consisting of long jumps followed by several short walks. It has been shown that this type of foraging behavior is more efficient at seeking out randomly distributed targets than a simple random walk. The Lévy stable distribution has three adjustable parameters which allows greater flexibility in the distribution of rate constants than does the Gaussian model, but still constrains the distribution to be symmetrical about some mean value.

Physical Models

A number of these have been applied to very specific data sets, where parameters of the systems are accurately known. These include random walk models in zeolites, and time-dependent fractal-dimensional rate constants to describe kinetics on silica gel surfaces. The advantage of these methods over rate constant distributions is that since they are based on the physical description of the system, they yield physically meaningful parameters such as diffusion coefficients from analysis of kinetic data. However, for many systems the parameters are known in insufficient detail for accurate models to be developed.

Examples

An example of bimolecular quenching data is shown in Figure 5. Here, anthracene at a concentration of 1 μmol g^{-1} is co-adsorbed to silica gel from acetonitrile solution together with azulene at a concentration of 0.8 μmol g^{-1}. Laser excitation at 355 nm from an Nd:YAG laser produces the excited triplet state of the anthracene, which undergoes energy transfer to the co-adsorbed azulene molecule as a result of the rapid diffusion of the latter.

The data shown in Figure 5 are recorded monitoring at 420 nm, and the laser energy (approximately 5 mJ per pulse) is such that an exponential fall-off of transient concentration with penetration depth is expected such that reflectance change is proportional to transient concentration (see section on Transient Concentration Profiles above). The data are shown on a logarithmic time axis for clarity. The fitted line is obtained by applying the model of Albery *et al.* (see section on Rate Constant Distributions above) with fitting parameters $\bar{k} = 1.01 \times 10^4\ \mathrm{s}^{-1}$ and $\gamma = 0.73$.



Figure 5 Transient absorption decay for anthracene (1 μmol g^{-1}) co-adsorbed with azulene (0.8 μmol g^{-1}) to silica gel monitored at 420 nm. Fitted using the model of Albery *et al.*



Figure 6 Transient absorption decay for the naphthalene (1 μmol g^{-1}) radical cation monitored at 680 nm on silica gel. Fitted using a Lévy stable distribution.

Where ion–electron recombination is concerned, the Albery model often fails to adequately describe the data obtained since it does not allow sufficient small rate constants relative to the value of $\bar{k}$, given the constraints of the Gaussian distribution. The Lévy stable distribution is ideal in this application since it allows greater flexibility in the shape of the distribution.

Figure 6 shows example data for naphthalene adsorbed to silica gel (1 μmol g^{-1}). The laser pulse energy at 266 nm (approximately 40 mJ per pulse) is such that photo-ionization of the naphthalene occurs producing the radical cation. The subsequent decay of the radical cation via ion–electron recombination can be monitored at 680 nm. Note that decay is observed on a time-scale of several thousand seconds. The fitted line is according to a Lévy stable distribution with parameters $\bar{k} = 8.2 \times 10^{-4}\ \mathrm{s}^{-1}$, $\gamma = 0.5$ and $\alpha = 1.7$ (see section on Rate Constant Distributions above). This model allows the shape of the distribution to deviate from a Gaussian, and can be more successful than the model of Albery *et al.* in modeling the complex kinetics which arise on surfaces such as silica gel. Note that where the model of Albery *et al.* can successfully model the data, the data can also be described by a Lévy stable distribution with $\alpha = 2$.

List of Units and Nomenclature

A	Sample absorbance
c	Concentration
I	Incident flux
J	Diffusely reflected flux

k	Rate constant
$\bar{k}$	Mean rate constant
K	Absorption coefficient (absorption per unit thickness) [cm^{-1}]
l	Pathlength [cm]
P	Probability of transmission of a photon through a sample of defined thickness
R_∞	Reflectance of an infinitely thick sample
S	Scattering coefficient (scattering per unit thickness) [cm^{-1}]
t	Time
X	Thickness of sample layer [cm]
α	Characteristic Lévy power law exponent
γ	Width of rate constant distribution
$\Delta G^{\neq}$	Free energy of activation [kJ mol^{-1}]
$\Delta\bar{G}^{\neq}$	Mean free energy of activation [kJ mol^{-1}]
ε	Molar decadic or naperian absorption coefficient

See also

Chemical Applications of Lasers: Pump and Probe Studies of Femtosecond Kinetics. **Optical Materials**: Measurement of Optical Properties of Solids. **Scattering**: Scattering from Surfaces and Thin Films; Scattering Theory.

Further Reading

Albery WJ, Bartlett PN, Wilde CP and Darwent JR (1985) A general-model for dispersed kinetics in heterogeneous systems. *Journal of the American Chemical Society* 107: 1854–1858.

Anpo M (ed.) (1996) Surface photochemistry. *Wiley Series in Photoscience and Photoengineering*, vol. 1. Chichester, UK: John Wiley and Sons.

Anpo M and Matsuura T (eds) (1989) Photochemistry on solid surfaces. *Elsevier Series in Studies in Surface Science and Catalysis*, vol. 47. Amsterdam, The Netherlands: Elsevier Science Publishers B.V.

Asahi T, Furube A, Fukumura H, Ichikawa M and Masuhara H (1998) Development of a femtosecond diffuse reflectance spectroscopic system, evaluation of its temporal resolution, and applications to organic powder systems. *Review of Scientific Instruments* 69: 361–371.

Bertoin J (1998) *Lévy Processes*. Cambridge, UK: Cambridge University Press.

Hapke B (1993) *Introduction to the Theory of Reflectance and Emittance Spectroscopy*. Cambridge, UK: Cambridge University Press.

Kamat PV (1993) Photochemistry on nonreactive and reactive (semiconductor) surfaces. *Chemical Reviews* 93: 287–300.

Kan HKA and Lin TP (1970) Calculation of reflectance of a light diffuser with non-uniform absorption. *Journal of the Optical Society of America* 60: 1252–1256.

Kessler RW and Wilkinson F (1981) Diffuse reflectance triplet–triplet absorption spectroscopy of aromatic hydrocarbons chemisorbed on γ-alumina. *Journal of the Chemical Society – Faraday Transactions I* 77: 309–320.

Kortum G (1969) *Reflectance Spectroscopy*. Berlin: Springer-Verlag.

Kubelka P and Munk F (1931) Ein beitrag zur optik der farbanstriche. *zeitschrift fuer Technische Physik* 12: 593–601.

Ramamurthy V (ed.) (1991) *Photochemistry in Organised & Constrained Media*. New York: VCH Publishers.

Thomas JK (1993) Physical aspects of photochemistry and radiation chemistry of molecules adsorbed on SiO_2, γ-Al_2O_3, zeolites and clays. *Chemical Reviews* 93: 301–320.

Thomas JK and Ellison EH (2001) Various aspects of the constraints imposed on the photochemistry of systems in porous silica. *Advances in Colloid and Interface Science* 89–90: 195–238.

Wendlandt WW and Hecht HG (1966) Reflectance Spectroscopy. *Chemical Analysis Series*, vol. 21. New York: Interscience Publishers.

Wilkinson F and Kelly G (1989) Diffuse reflectance flash photolysis. In: Scaiano JC (ed.) *Handbook of Organic Photochemistry*, vol. 1, pp. 293–314. Florida: CRC Press.

Laser Manipulation in Polymer Science

S Ito, Y Hosokawa and H Masuhara, Osaka University, Osaka, Japan

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Laser manipulation is a method for manipulating single particles with a size of less than a few tens of microns in which optical pressure of a focused laser beam is used to trap and control the particles without any mechanical contact. As infrared lasers, as a trapping light source, have become more user-friendly, even operators who are not familiar with lasers and microscopes can perform laser manipulation. Those laser manipulators already on sale have attracted significant attention as a new tool. It is especially interesting to combine this method with nanotechnology and biotechnology, which have progressed rapidly during the 1990s. In this article, the principle and method of laser manipulation is described and then its applications and possibilities in nanotechnology and biotechnology are summarized.

Principle and Method

When light is reflected or refracted at the interface between two media with different refractive indices, the momentum of photons is changed, which leads to the generation of photon force as a reaction to the momentum change. For example, when a laser beam is reflected by a mirror, the momentum of photons is changed by Δp (Figure 1a). As a result, a photon force, $\mathbf{F}_{\text{phot}}$, acts on the mirror to deflect it vertically away from the reflected beam. In refraction, the momentum of photons is also changed, so that the photon force acts on the interface, as shown in Figure 1b. Thus light does not only give its energy to materials via absorption but also applies a mechanical force to them. However, when we are exposed to light, such as from a halogen lamp, we are never aware of the photon force because its magnitude is less than an order of pN. However, the photon force of the pN order acquired from a focused laser beam is sufficient to manipulate nm–μm-sized particles in solution, under an optical microscope.



Figure 1 Optical pressure originating from the momentum change of photons.

Principle of Laser Trapping

If the size of a particle is larger than the wavelength of a trapping laser beam (μm-sized particles), the principle of single-beam gradient force optical trapping can be explained in terms of geometrical optics. When a tightly focused laser beam is irradiated onto a transparent dielectric particle, an incident laser beam is refracted at the interface between the particle and medium, as represented by Figure 2a. The propagation direction of the beam is changed, i.e., the momentum of the photon is changed, and consequently, a photon force is generated. As the laser beam leaves the particle and enters the surrounding medium, this refraction causes a photon force to be exerted again on that interface. Summing up the force contributions of all rays, if the refractive index of the particle is higher than that of the medium, a resultant force exerted on the particle is directed toward the focal point as an attractive force. However, reflection at the surface of the particle is negligible if that particle is transparent and the refractive index ratio of the particle to medium is close to unity. Therefore, the incident beam is reflected at two surfaces by a small amount, and as a result, the particle is directed slightly to the propagation direction of the incident light. Where the particle absorbs the incident beam, the photon force is also generated to push it in the propagation direction. The negligible effects of the



Figure 2 Principle of single-beam gradient force optical trapping explained by ray optics.

reflection and absorption occur in trapping experiment of transparent particles, such as polymer particles, silica microspheres, etc. However, particles with high reflectance and absorption coefficients such as metallic particles, exert a more dominant force at the surface where absorption and reflection occurs. This force is a repulsive force away from the focal point; consequently, metallic microparticles cannot be optically trapped.

If a dielectric particle is much smaller than the wavelength of a trapping light (nm-sized), it can be regarded as a point dipole (Rayleigh approximation) and the photon force ($\mathbf{F}_{\text{phot}}$) acted on it is given by

$$\mathbf{F}_{\text{phot}} = \mathbf{F}_{\text{grad}} + \mathbf{F}_{\text{scat}} \qquad [1]$$

Here, $\mathbf{F}_{\text{grad}}$ and $\mathbf{F}_{\text{scat}}$ are called the gradient force and scattering force, respectively. The scattering force is caused by the scattering of light, and it pushes the particle toward the direction of light propagation. On the other hand, the gradient force is generated when a particle is placed in a heterogeneous electric field of light. If the dielectric constant of the particle is higher than that of the surrounding medium, the gradient force acts on the particle to push it toward the higher intensity region of the beam. In the case of laser trapping of dielectric nanoparticles, the magnitude of gradient force is much larger than the scattering force. Consequently, the particle is trapped at the focal point of the trapping laser beam, where the beam intensity (electric field intensity) is maximum. The photon force can be expressed as follows:

$$\mathbf{F}_{\text{phot}} \cong \mathbf{F}_{\text{grad}} = \frac{1}{2}\varepsilon_{\text{m}}\alpha\nabla|\mathbf{E}|^2 \qquad [2]$$

$$\alpha = 3V\frac{\varepsilon_{\text{p}} - \varepsilon_{\text{m}}}{\varepsilon_{\text{p}} + 2\varepsilon_{\text{m}}} \qquad [3]$$

where, $\mathbf{E}$ is electric field of the light, V is volume of the particle, and ε_{p} and ε_{m} are dielectric constants of the particle and medium. In trapping nanoparticles that absorb the laser beam, such as gold nanoparticles, the complex dielectric constant and attenuation of the electric field in the particle need to be taken into consideration. Although the forces due to light absorption and scattering are both propelling the particle toward the direction of light propagation, the magnitude of gradient force is much larger than these forces. This is in contrast to the μm-sized metallic particle, which cannot be optically trapped.

Laser Manipulation System

An example of a laser micromanipulation system, with a pulsed laser to induce photoreactions, is shown in Figure 3. A linearly polarized laser beam from a CW Nd^{3+}:YAG laser is modulated to the circularly polarized light by a $\lambda/4$ plate and then split into horizontally and vertically polarized beams by a



Figure 3 A block diagram of a dual beam laser manipulation-reaction system.

polarizing beamsplitter (PBS1). Both laser beams are combined by another (PBS2), introduced coaxially into an optical microscope, and then focused onto a sample through a microscope objective. The focal spots of both beams in the sample solution can be scanned independently by two sets of computer-controlled galvano mirrors. Even if the beams are spatially overlapping, interference does not take place because of their orthogonal polarization relation. Pulsed lasers, such as a Q-switched Nd^{3+}:YAG laser, are used to induce photoreactions, such as photopolymerization, photothermal reaction, laser ablation, etc.

Laser Manipulation and Patterning of Nanoparticles

Laser manipulation techniques enable us to capture and mobilize fine particles in solution. Most studies using this technique have been conducted on μm-sized objects such as polymer particles, microcrystals, living cells, etc. Because it is difficult to identify individual nanoparticles with an optical microscope, laser manipulation techniques have rarely been applied to nanotechnology and nanoscience. However, the laser trapping technique can be a powerful tool for manipulation of nanoparticles in solution where individual particles can be observed. This is achieved by detection of fluorescence emission from labeled dyes or scattered light. Now, even single molecule fluorescence spectroscopy has been achieved by the use of a highly sensitive photodetector, and a single metallic nanoparticle can be examined by detecting the light scattered from it. There have been several reports on the application of laser manipulation techniques for patterning of nm-sized particles. Here, fixation methods of nanoparticles, using the laser manipulation technique and local photoreactions, are introduced.

Patterning of Polymer Nanoparticles

Patterning of individual polymer nanoparticles onto a substrate can be achieved by using local photopolymerization. The following example shows the strength of this method. Polystyrene nanoparticles of 220 nm with fluorescent dye were dispersed in ethylene glycol solution containing polymerizable vinyl monomer (acrylamide, 31 wt%), crosslinker (*N*,*N*′-methylenebisacrylamide, 2.2 wt%), and radical photoinitiator (Irgacure2959, Ciba Specialty Chemicals, 1.1 wt%). When the sample was irradiated by blue light from a high-pressure mercury lamp, green fluorescence from dye molecules within each nanoparticle was observed. A nanoparticle that entered the region, irradiated by a near-infrared laser beam (1064 nm), was trapped at the focal point, and moved onto the surface of the glass substrate by handling the 3D stage of the microscope. An additional fixation laser beam (355 nm, 0.03 μJ, pulse duration ~6 ns, repetition rate ~5 Hz) was then focused to the same point for ~10 s, which led to the generation of acrylamide gel around the trapped nanoparticle. By repeating the procedure, patterning of single polymer nanoparticles on a glass substrate was achieved, and a fluorescence image of single nanoparticles as a letter ‘H’, is shown in Figure 4. A magnified atomic force microscope (AFM) image of one of the fixed nanoparticles is also shown, which confirms that only one polymer nanoparticle was contained in the polymerized gel.

Multiple polymer nanoparticles can also be gathered, patterned, and fixed on a glass substrate by scanning both trapping and fixation laser beams with the use of two pairs of galvano mirrors. The optical transmission and fluorescence images of the ‘H’ patterned nanoparticles on a glass substrate are shown in Figure 5a and b, respectively. The letter ‘H’ consists of three straight lines of patterned and fixed nanoparticles. The trapping laser beam (180 mW) was scanned at 30 Hz along each line with a length of ~10 μm on a glass substrate for 300 s. Nanoparticles were gathered and patterned along the locus of the focal point on the substrate. Then the fixation laser beam (0.097 μJ) was scanned for another 35 s. As a result, the straight lines of



Figure 4 (a) A fluorescence image of spatially patterned individual polymer nanoparticles as the letter ‘H’ in distilled water. (b) A magnified AFM image of one of the produced acrylamide gels containing only one polymer nanoparticle on a glass substrate in the air.



Figure 5 Optical transmission (a) and fluorescence (b) images of patterned and fixed polymer nanoparticles on the glass substrate, as the letter 'H'.

patterned nanoparticles were fixed in generated acrylamide gel on the substrate. Combining several simple fixed patterns, a more complex arrangement can be created with use of the present manipulation and fixation techniques.

Fixation of Individual Gold Nanoparticles

Manipulation and fixation of single metallic nanoparticles in solution has been achieved by means of photo-induced transient melting of nanoparticles. As an example, the following method describes this technique. Gold nanoparticles (diameter ~80 nm) were dispersed in ethylene glycol. In order to identify a single gold nanoparticle, extinction of light from the halogen lamp of the optical microscope by the particle was utilized. Thus, the trapped particle was observed as a black spot in transmission image. The optically trapped single gold nanoparticle was then transferred to a precise position on the surface of glass substrate in the sample solution. The focused 355 nm pulse was additionally irradiated onto the pressed nanoparticle, which led to a transient temperature elevation of the gold nanoparticle to enable its fixation. It was confirmed by AFM observation that, at suitable laser fluence (32–64 mJ cm^{-2}), a gold nanoparticle was fixed on the glass substrate without fragmentation. Repeating the same manipulation and fixation procedure, single gold nanoparticles could be patterned on a glass substrate. Figure 6 shows an AFM image of successive spatial patterning of single 80 nm gold particles.



Figure 6 An AFM image of fixed and patterned gold nanoparticles, as the letter I.

The significance of the laser manipulation-fixation technique is that we can trap, manipulate, and fix single and/or many nanoparticles in solution at room temperature. We have already demonstrated assembling entangled polymer chains of 10–20 nm mean radius by laser trapping, and formation of a single μm-sized particle. Thus, these various kinds of nanoscopic materials can be well manipulated using these techniques and it is believed that the present nanomanipulation-fixation method will be useful for future nanoscience and nanotechnology.

Application to Biotechnology

Recent progress in biotechnology, using single cell manipulation by laser and microscope, has been attracting significant attention. In conventional methods, cell manipulation has been performed by mechanical manipulation using microneedles and micropipettes. However, laser manipulation can be applied as microtweezers. In comparison with the former, this form of laser manipulation has the


Computer
CCD camera
Dichroic mirror 1
Polarizing beamsplitter 2
Mouse
Galvano mirror 2 (to control laser beam B)
Microscope
Objective
Microchip
Polarizing beamsplitter 1
Nd:YAG laser
Pump A
Pump B
Pump C
Galvano mirror 1 (to control laser beam A)

Figure 7 An experimental setup of dual-beam laser manipulation and microfluidic devices.

advantage of no contact with cells and can perform some complex and characteristic movement, for example, rotation, separation, accumulation, etc. Furthermore, by combining it with a microcutter using laser ablation, cell fusion and extraction/injection of organs from/into the cells can be achieved. In this section, single-cell manipulation achieved by using the laser manipulation, is introduced.

Noncontact Rotation of Cells Using Dual Beam Laser Manipulation

As a special feature of laser-cell manipulation, it is noticeable that multiple laser tweezers can be operated independently without any contact. Here, noncontact rotation of the fission yeast, *Schizosaccharomyces pombe* (h^-), demonstrates this method. The yeast has the shape of an ellipse of length 8 and 3 μm for major and minor axes, and is shown set on a dual-beam laser manipulation system in Figure 7. One trapping beam A was focused at the end of the cell to anchor it, and another beam, B, was at the other end and scanned circularly around beam A by controlling the Galvano mirrors. The rotation of the yeast cell was realized at a frequency of less than 2 Hz, as shown in Figure 8. Such a cell manipulation is impossible by mechanical manipulation and indicates the superior performance of laser manipulation.



Figure 8 Rotation of fission yeast cells using dual-beam laser manipulation. The bars are 10 μm.

Transfer of Cells in Microchannel

A flow cytometry to physically separate and identify specific types of cells from heterogeneous populations by fluorescence, which is called fluorescence-activated cell sorter (FACS), has attracted significant attention as an important technique in biotechnology. In the separation process, charged single droplets containing single, fluorescence labeled cells are selected by passing them between two high-voltage deflection plates. Since it is a sequential process, which does not use microscopy, flexible and high-purity cell separation is limited. To overcome this problem, a selective cell separation system, combining the laser trapping with the microchannel, is used. The method using microscopy is useful and flexible, because cells are not simply detected by fluorescence but also identified by their shape, size, surface morphology, absorption, etc. However, cell sorting under a microscope is not processed efficiently by laser trapping. A more effective method is described by the following.

The microchannel was prepared with laser microfabrication and photopolymerization, whose top view is shown in Figure 9a, and was then set on the microscope stage. Three syringes were equipped with homemade pumps A, B, and C, and connected with a microchip. There were two wing-like chambers in the microchip, that were connected with pumps A and C. Between chambers, there was a microchannel 100 μm wide, which joined these chambers and crossed a long microchannel connected with the pump B, thus forming a drain. Thickness of these chambers was 100 μm. By controlling these pumps, the left and right chambers were filled by the culture medium including the yeast cells and the neat culture medium, respectively, as shown in Figure 9b.

Individual cells were transferred from left to right chambers by using a single laser beam and handling an electrically movable microscope stage. The trapping laser irradiated a yeast cell in the left chamber and the trapped cell was transferred to the right chamber. A representative demonstration is given in Figure 9c. The position of the trapped yeast cell was controlled by the microscope stage with the velocity of 20 μm/s. The single yeast cells were successfully transferred from left to right chambers at the rate of 26 s. By combining laser trapping with the microchannel, single separation of cells was achieved under a microscope.

Collection and Alignment of Cells

When cell sorting using laser trapping is applied to biotechnology, the time to transfer cells should be short compared to the above-mentioned times. One method is to transfer multiple cells simultaneously by developing dual-beam laser manipulation, which is shown schematically in Figure 10. One trapping beam A was scanned on a line given as an arrow in Figure 10a at a rate faster than motions of cells.



Figure 9 (a) A microchip fabricated by laser polymerization technique and (b) its schematic representation corresponding to dashed area in the microchip. (c) Cell transfer in microchip using laser trapping. The bars are 100 μm. A trapping laser beam is fixed at the center of each picture, by which a particle is trapped and transferred from left to right chambers. The position of each picture is shown in (b).


(a)
Linear scanning of trapping beam A
(b)
Mouse control of trapping beam B
(c)
Transfer using microscope stage

Figure 10 A schematic illustration of efficient collection and transfer of cells based by dual-beam laser manipulation.



Figure 11 Collection and alignment of fission yeast cells using dual-beam laser manipulation.

The other trapping beam B was used to move individual cells to the line sequentially (Figure 10b). Finally, by moving the microscope stage, many particles trapped at the scanning line can be transferred to another chamber (Figure 10c).

An example is shown in Figure 11. The trapping beam A was scanned on a line with the rate of 15 Hz whose length was 30 μm. The trapping beam B was used to trap a yeast cell and move it to the line, which was controlled by a computer mouse pointer. The cells stored on the line were successfully isolated and with this method three cells can be collected within 15 s. Furthermore, the cells could be transferred with the velocity of 20 μm/s by driving the microscope stage. By improving the presented cell-sorting system, it is expected to realize flexible and high-purity cell separation.

List of Units and Nomenclature

Laser fluence (light energy density per pulse)	[mJ cm^{-2}]

See also

Time-Resolved Fluorescence: Measurements in Polymer Science.

Further Reading

Ashkin A, Dziedzic MJ, Bjorkholm JE and Chu S (1986) Observation of a single-beam gradient force optical trap for dielectric particles. *Optical Letters* 11: 288–290.

Ashkin A, Dziedzic MJ and Yamane T (1987) Optical trapping and manipulation of single cells using infrared laser beams. *Nature* 330: 769–771.

Berns WM, Aist J, Edwards J, *et al.* (1981) Laser microsurgery in cell and developmental biology. *Science* 213: 505–513.

Hoffmann F (1996) Laser microbeams for the manipulation of plant cells and subcellular structures. *Plant Science* 113: 1–11.

Hosokawa Y, Masuhara H, Matsumoto Y and Sato S (2002) Dual-beam laser micromanipulation for sorting biological cells and its device application. *Proceedings of SPIE* 4622: 138–142.

Ito S, Yoshikawa H and Masuhara H (2001) Optical patterning and photochemical fixation of polymer nanoparticles on glass substrates. *Applied Physics Letters* 78: 2566–2568.

Ito S, Yoshikawa H and Masuhara H (2002) Laser manipulation and fixation of single gold nanoparticles in solution at room temperature. *Applied Physics Letters* 80: 482–484.

Kamentsky AL, Melamed RM and Derman H (1965) Spectrophotometer: new instrument for ultrarapid cell analysis. *Science* 150: 630–631.

Kim BH, Kogi O and Kitamura N (1999) Single-microparticle measurements: laser trapping-absorption microscopy under solution-flow conditions. *Analytical Chemistry* 71: 4338–4343.

Masuhara H, De Schryver FC, Kitamura N and Tamai N (eds) (1994) *Microchemistry: Spectroscopy and Chemistry in Small Domains*. Amsterdam: Elsevier-Science.

Sasaki K, Koshioka M, Misawa H, Kitamura N and Masuhara H (1991) Laser-scanning micromanipulation and spatial patterning of fine particles. *Japanese Journal of Applied Physics* 30: L907–L909.

Schütze K, Clement-Segelwald A and Ashkin A (1994) Zona drilling and sperm insertion with combined laser microbeam and optical tweezers. *Fertility and Sterility* 61: 783–786.

Shikano S, Horio K, Ohtsuka Y and Eto Y (1999) Separation of a single cell by red-laser manipulation. *Applied Physics Letters* 75: 2671–2673.

Svoboda K and Block SM (1994) Optical trapping of metallic Rayleigh particles. *Optical Letters* 19: 930–932.

Nonlinear Spectroscopies

S R Meech, University of East Anglia, Norwich, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Chemistry is concerned with the induction and observation of changes in matter, where the changes are to be understood at the molecular level. Spectroscopy is the principal experimental tool for connecting the macroscopic world of matter with the microscopic world of the molecule, and is, therefore, of central importance in chemistry. Since its invention, the laser has greatly expanded the capabilities of the spectroscopist. In linear spectroscopy, the monochromaticity, coherence, high intensity, and high degree of polarization of laser radiation are ideally suited to high-resolution spectroscopic investigations of even the weakest transitions. The same properties allowed, for the first time, the investigation of the nonlinear optical response of a medium to intense radiation. Shortly after the foundations of nonlinear optics were laid, it became apparent that these nonlinear optical signals could be exploited in molecular spectroscopy, and since then a considerable number of nonlinear optical spectroscopies have been developed. This short article is not a comprehensive review of all these methods. Rather, it is a discussion of some of the key areas in the development of the subject, and indicates some current directions in this increasingly diverse area.

Nonlinear Optics for Spectroscopy

The foundations of nonlinear optics are described in detail elsewhere in the encyclopedia, and in some of the texts listed in the Further Reading section at the end of this article. The starting point is usually the nonlinearity in the polarization, P_i, induced in the sample when the applied electric field, E, is large:

$$P_i = \varepsilon_0\left[\chi_{ij}^{(1)}E_j + \frac{1}{2}\chi_{ijk}^{(2)}E_jE_k + \frac{1}{4}\chi_{ijkl}^{(3)}E_jE_kE_l + \cdots\right] \quad [1]$$

where ε_0 is the vacuum permittivity, $\chi^{(n)}$ is the nth order nonlinear susceptibility, the indices represent directions in space, and the implied summation over repeated indices convention is used. The signal field, resulting from the nonlinear polarization, is calculated by substituting it as the source polarization in Maxwell's equations and converting the resulting field to the observable, which is the optical intensity.

The nonlinear polarization itself arises from the anharmonic motion of electrons under the influence of the oscillating electric field of the radiation. Thus, there is a microscopic analog of eqn [1] for the induced molecular dipole moment, μ_i:

$$\mu_i = [\varepsilon_0\alpha_{ij}d_j + \varepsilon_0^{-2}\beta_{ijk}d_jd_k + \varepsilon_0^{-3}\gamma_{ijkl}d_jd_kd_l + \cdots] \quad [2]$$

in which α is the polarizability, β the first molecular hyperpolarizability, γ the second, etc. The power series is expressed in terms of the displacement field $\mathbf{d}$ rather than $\mathbf{E}$ to account for local field effects. This somewhat complicates the relationship between the molecular hyperpolarizabilities, for example, γ_{ijkl} and the corresponding macroscopic susceptibility, $\chi^{(3)}_{ijkl}$, but it is nevertheless generally true that a molecule exhibiting a high value of γ_{ijkl} will also yield a large third-order nonlinear polarization. This relationship between the macroscopic and microscopic parameters is the basis for an area of chemistry which has influenced nonlinear optics (rather than the inverse). The synthesis of molecules which have giant molecular hyperpolarizabilities has been an active area, because of their potential applications in lasers and electro-optics technology. Such molecules commonly exhibit a number of properties, including an extended linear π electron conjugation and a large dipole moment, which changes between the ground and excited electronic states. These properties are in accord with the predictions of theory and of quantum chemical calculations of molecular hyperpolarizabilities.

Nonlinear optical spectroscopy in the frequency domain is carried out by measuring the nonlinear signal intensity as a function of the frequency (or frequencies) of the incident radiation. Spectroscopic information is accessible because the molecular hyperpolarizability, and therefore the nonlinear susceptibility, exhibits resonances: the signal is enhanced when one or more of the incident or generated frequencies are resonant with the frequency of a molecular transition. The rich array of nonlinear optical spectroscopies arises in part from the fact that with more input fields there are more accessible resonances than is the case with linear spectroscopy. As an example we consider the third-order susceptibility, $\chi^{(3)}_{ijkl}E_jE_kE_l$, in the practically important case of two incident fields at the same frequency, ω_1, and a third at ω_2. The difference between the two frequencies is close to the frequency of a Raman active vibrational mode, Ω_{rg} (Figure 1). The resulting susceptibility can be calculated to have the form:

$$\chi^{(3)}_{ijkl}(-2\omega_1+\omega_2;\omega_1,\omega_1,-\omega_2) = \frac{N\Delta\rho_{rg}\Omega_{rg}(\alpha^{\mathrm{R}}_{ij}\alpha^{\mathrm{R}}_{kl}+\alpha^{\mathrm{R}}_{ik}\alpha^{\mathrm{R}}_{jl})}{12\hbar[\Omega^2_{rg}-(\omega_1-\omega_2)^2+\Gamma^2-2\mathrm{i}(\omega_1-\omega_2)\Gamma]} \qquad [3]$$

in which the α^{R} are elements of the Raman susceptibility tensor, Γ is the homogeneous linewidth of the Raman transition, $\Delta\rho_{rg}$ a population difference, and N the number density. A diagram illustrating this process is shown in Figure 1, where the signal field is at the anti-Stokes Raman frequency $(2\omega_1 - \omega_2)$. The spectroscopic method which employs this scheme is called coherent anti-Stokes Raman spectroscopy (CARS) and is one of the most widely applied nonlinear optical spectroscopies (see below). Clearly, from eqn [3] we can see that the signal will be enhanced when the difference frequency is resonant with the Raman transition frequency.



Figure 1 An illustration of the resonance enhancement of the CARS signal, $\omega_{\text{sig}} = 2\omega_1 - \omega_2$ when $\omega_1 - \omega_2 = \Omega_{rg}$.

With essentially the same experimental geometry there will also be nonlinear signals generated at both the Stokes frequency $(2\omega_2 - \omega_1)$ and at the lower of the incident frequencies, ω_2. These signals have distinct phase matching conditions (see below), so they can easily be discriminated from one another, both spatially and energetically. Additional resonance enhancements are possible if either of the individual frequencies is resonant with an electronic transition of the molecule, in which case information on Raman active modes in the excited state is also accessible.

It is worthwhile noting here that there is an equivalent representation of the nth order nonlinear susceptibility tensor $\boldsymbol{\chi}^{(n)}(\omega_{\text{sig}} : \omega_1, \ldots, \omega_n)$ as a time domain response function, $\mathrm{R}^{(n)}(\tau_1, \ldots, \tau_n)$. While it is possible to freely transform between them, the frequency domain representation is the more commonly used. However, the response function approach is increasingly applied in time domain nonlinear optical spectroscopy when optical pulses shorter than the homogeneous relaxation time are used. In that case, the time ordering of the incident fields, as well as their frequencies, is of importance in defining an experiment.

An important property of many nonlinear optical spectroscopies is the directional nature of the signal, illustrated in Figure 2. The directional nonlinear



Figure 2 Experimental geometries and corresponding phase matching diagrams for (a) CARS (b) DFWM (c) RIKES. Note that only the RIKES geometry is fully phase matched.

signal arises from the coherent oscillation of induced dipoles in the sample. Constructive interference can lead to a large enhancement of the signal strength. For this to occur the individual induced dipole moments must oscillate in phase – the signal must be phase matched. This requires the incident and the generated frequencies to travel in the sample with the same phase velocity, $k_\omega/\omega = c/n_\omega$ where n_ω is the index of refraction and k_ω is the wave propagation constant at frequency ω. For the simplest case of second-harmonic generation (SHG), in which the incident field oscillates at ω and the generated field at 2ω, phase matching requires $2k_\omega = k_{2\omega}$. The phase-matching condition for the most efficient generation of the second harmonic is when the phase mismatch, $\Delta k = 2k_\omega - k_{2\omega} = 0$, but this is not generally fulfilled due to the dispersion of the medium, $n_\omega < n_{2\omega}$. In the case of SHG, a coherence length L can be defined as the distance traveled before the two waves are 180° out of phase, $L = |\pi/\Delta k|$. For cases in which the input frequencies also have different directions, as is often the case when laser beams at two frequencies are combined (e.g., CARS), the phase-matching condition must be expressed as a vectorial relationship, hence, for CARS, $\Delta\mathbf{k} = \mathbf{k}_{AS} - 2\mathbf{k}_1 + \mathbf{k}_2 \approx 0$, where $\mathbf{k}_{AS}$ is the wavevector of the signal at the anti-Stokes frequency (Figure 2). Thus for known input wavevectors one can easily calculate the expected direction of the output signal, $\mathbf{k}_s$. This is illustrated for a number of important cases in Figure 2.

Nonlinear Optical Spectroscopy in Chemistry

As already noted, there is a vast array of nonlinear optical spectroscopies, so it is clear some means of classification will be required. For coarse graining the order of the nonlinear process is very helpful, and that is the scheme we will follow here.

Second-Order Spectroscopies

Inspection of eqn [1] shows that in gases, isotropic liquids, and solids where the symmetry point group contains a center of inversion, $\boldsymbol{\chi}^{(2)}$ is necessarily zero. This is required to satisfy the symmetry requirement that polarization must change sign when the direction of the field is inverted, yet for a quadratic, or any even order dependence on the field strength, it must remain positive. Thus second-order nonlinearities might not appear very promising for spectroscopy. However, there are two cases in which second-order nonlinear optical phenomena are of very great significance in molecular spectroscopy, harmonic generation and the spectroscopy of interfaces.

Harmonic conversion

Almost every laser spectroscopist will have made use of second-harmonic or sum frequency generation for frequency conversion of laser radiation. Insertion of an oscillating field of frequency ω into eqn [1] yields a second-order polarization oscillating of 2ω. If two different frequencies are input, the second-order polarization oscillates at their sum and difference frequencies. In either case, the second-order polarization acts as a source for the second-harmonic (or sum, or difference frequency) emission, provided $\boldsymbol{\chi}^{(2)}$ is nonzero. The latter can be arranged by selecting a noncentrosymmetric medium for the interaction, the growth of such media being an important area of materials science. Optically robust and transparent materials with large values of $\boldsymbol{\chi}^{(2)}$ are available for the generation of wavelengths shorter than 200 nm to longer than 5 μm. Since such media are birefringent by design, a judicious choice of angle and orientation of the crystal with respect to the input beams allows a degree of control over the refractive indices experienced by each beam. Under the correct phase matching conditions $n_\omega \approx n_{2\omega}$, and very long interaction lengths result, so the efficiency of signal generation is high.

Higher-order harmonic generation in gases is an area of growing importance for spectroscopy in the deep UV and X-ray region. The generation of such short wavelengths depends on the ability of amplified ultrafast solid state lasers to generate extremely high instantaneous intensities. The mechanism is somewhat different to the one outlined above. The intense pulse is injected into a capillary containing an appropriate gas. The high electric field of the laser causes ionization of atoms. The electrons generated begin to oscillate in the applied laser field. The driven recombination of the electrons with the atoms results in the generation of the high harmonic emission. Although the mechanism differs from the SHG case, questions of phase matching are still important. By containing the gas in a corrugated waveguide phase matching is achieved, considerably enhancing the intensity of the high harmonic. Photon energies of hundreds of electronvolts are possible using this technique. The generation of such high energies is not yet routine, but a number of potential applications are already apparent. A powerful coherent source of X-ray and vacuum UV pulses will certainly aid surface analysis techniques such as UV photoemission and X-ray photoelectron spectroscopy. Much excitement is currently being generated by the possibility of using intense ultrashort X-ray pulses to record structural dynamics on an ultrafast timescale.

Surface second-order spectroscopy

At an interface inversion symmetry is absent by definition, so the second-order nonlinear susceptibility is finite. If the two bulk phase media are themselves isotropic, then even a weak second-order signal necessarily arises from the interface. This surface-specific all-optical signal is unique, because it can be used to probe the interface between two condensed phases. This represents a great advantage over every other form of surface spectroscopy. In linear optical spectroscopy, the signal due to species at the interface are usually swamped by contributions from the bulk phase. Other surface-specific signals do exist, but they rely on the scattering of heavy particles (electrons, atoms) and so can only be applied to the solid vacuum interface. For this reason the techniques of surface SHG and SFG are widely applied in interface spectroscopy.

The most widely used method is sum frequency generation (SFG) between temporally overlapped tuneable infrared and fixed frequency visible lasers, to yield a sum frequency signal in the visible region of the spectrum. The principle of the method is shown in Figure 3. The surface nonlinear susceptibility exhibits resonances at vibrational frequencies, which are detected as enhancements in the visible SFG intensity. Although the signal is weak, it is directional and background free, so relatively easily measured by photon counting techniques. Thus, SFG is used to measure the vibrational spectra of essentially any optically accessible interface. There are, however, some limitations on the method. The surface must exhibit a degree of order – if the distribution of adsorbate orientation is isotropic the signal again becomes zero by symmetry. Second, a significant enhancement at the vibrational frequency requires the transition to be both IR and Raman allowed, as suggested by the energy level diagram (Figure 3).



Figure 3 The experimental geometry for SFG, and an illustration of the resonance enhancement of $\omega_{sig} = \omega_{IR} + \omega_{vis}$ at a Raman and IR allowed vibrational transition.

The SHG signal can also be measured as a function of the frequency of the incident laser, to recover the electronic spectrum of the interface. This method has been used, particularly in the study of semiconductor surfaces, but generally the electronic spectra of adsorbates contain less information than their vibrational spectra. However, by measuring the SHG intensity as a function of time, information on adsorbate kinetics is obtained, provided some assumptions connecting the surface susceptibility to the molecular hyperpolarizability are made. Finally, using similar assumptions, it is possible to extract the orientational distribution of the adsorbate, by measuring the SHG intensity as a function of polarization of the input and output beams. For these reasons, SHG has been widely applied to analyze the structure and dynamics of interfaces.

Third-Order Spectroscopies

The third-order coherent Raman spectroscopies were introduced above. One great advantage of these methods over conventional Raman is that the signal is generated in a coherent beam, according to the appropriate phase matching relationship (Figure 2). Thus, the coherent Raman signal can easily be distinguished from background radiation by spatial filtering. This has led to CARS finding widespread application in measuring spectra in (experimentally) hostile environments. CARS spectroscopy has been widely applied to record the vibrational spectra of flames. Such measurements would obviously be very challenging for linear Raman or IR, due to the strong emission from the flame itself. The directional CARS signal in contrast can be spatially filtered, minimizing this problem. CARS has been used both to identify unstable species formed in flames, and to probe the temperature of the flame (e.g., from measured population differences eqn [3]). A second advantage of the technique is that the signal is only generated when the two input beams overlap in space. Thus, small volumes of the sample can be probed. By moving the overlap position around in the sample, spatially resolved information is recovered. Thus, it is possible to map the population of a particular transient species in a flame.

CARS is probably the most widely used of the coherent Raman methods, but it does have some disadvantages, particularly in solution phase studies. In that case the resonant $\boldsymbol{\chi}^{(3)}$ signal (eqn [3]) is accompanied by a nonresonant third-order background. The interference between these two components may result in unusual and difficult to interpret lineshapes. In this case, some other coherent Raman methods are more useful. The phase matching scheme for Raman-induced Kerr effect spectroscopy (RIKES) was shown in Figure 2. The RIKES signal is always phase matched, which leads to a long interaction length. However, the signal is at ω_2 and in the direction of ω_2, which would appear to be a severe disadvantage in terms of detection. Fortunately, if the input polarizations are correctly chosen the signal can be isolated by its polarization. In an important geometry, the signal (ω_2) is isolated by transmission through a polarizer oriented at 45° to a linearly polarized pump (ω_1). The pump is overlapped in the sample with the probe (ω_2) linearly polarized at $-45°$. Thus the probe is blocked by the polarizer, but the signal is transmitted. This geometry may be viewed as pump-induced polarization of the isotropic medium to render it birefringent, thus inducing ellipticity in the transmitted probe, such that the signal leaks through the analyzing polarizer (hence the alternative name optical Kerr effect).

In this geometry, it is possible to greatly enhance signal-to-noise ratios by exploiting interference between the probe beam and the signal. Placing a quarterwave plate in the probe beam with its fast axis aligned with the probe polarization, and reorienting it slightly ($<1°$) yields a slightly elliptically polarized probe before the sample. A fraction of the probe beam, the local oscillator (LO), then also leaks through the analyzing polarizer, temporally and spatially overlapped with the signal. Thus, the signal and LO fields are seen by the detector, which measures the intensity as:

$$\begin{aligned} I(t) &= \frac{nc}{8\pi}|\mathbf{E}_{\mathrm{LO}}(t) + \mathbf{E}_{\mathrm{S}}(t)|^2 \\ &= I_{\mathrm{LO}}(t) + I_{\mathrm{S}}(t) + \frac{nc}{4\pi}\mathrm{Re}[\mathbf{E}_{\mathrm{S}}^*(t)\cdot\mathbf{E}_{\mathrm{LO}}(t)] \end{aligned} \quad [4]$$

where the final term may be very much larger than the original signal, and is linear in $\boldsymbol{\chi}^{(3)}$. This term is usually isolated from the strong I_{LO} by lock-in detection. This method is called optical heterodyne detection (OHD), and generally leads to excellent signal to noise. It can be employed with other coherent signals by artificially adding the LO to the signal, provided great care is taken to ensure a fixed phase relationship between LO and signal. In the RIKES experiment, however, the phase relationship is automatic. The arrangement described yields an out-of-phase LO, and measures the real part of $\boldsymbol{\chi}^{(3)}$, the birefringence. Alternatively, the quarterwave plate is omitted, and the analyzing polarizer is slightly reoriented, to introduce an in-phase LO, which measures the imaginary part of $\boldsymbol{\chi}^{(3)}$, the dichroism. This is particularly useful for absorbing media. The OHD-RIKES method has been applied to measure the spectroscopy of the condensed phase, and has found particularly widespread application in transient studies (below).

Degenerate four wave mixing (DFWM) spectroscopy is a simple and widely used third-order spectroscopic method. As the name implies, only a single frequency is required. The laser beam is split into three, and recombined in the sample, in the geometry shown in Figure 2. The technique is also known as laser-induced grating scattering. The first two beams can be thought of as interfering in the sample to write a spatial grating, with fringe spacing dependent on the angle between them. The signal is then scattered from the third beam in the direction expected for diffraction from that grating. The DFWM experiment has been used to measure electronic spectra in hostile environments, by exploiting resonances with electronic transitions. It has also been popular in the determination of the numerical value of $\boldsymbol{\chi}^{(3)}$, partly because it is an economical technique, requiring only a single laser, but also because different polarization combinations make it possible to access different elements of $\boldsymbol{\chi}^{(3)}$. The technique has also been used in time resolved experiments, where the decay of the grating is monitored by diffraction intensity from a time delayed third pulse.

Two-photon or, more generally, multiphoton excitation has applications in both fundamental spectroscopy and analytical chemistry. Two relevant level



Figure 4 Two cases of resonant two photon absorption. In (a) the excited state is two-photon resonant, and the process is detected by the emission of a photon. In (b) the intermediate state is resonant, and the final energy is above the ionization potential (IP) so that photocurrent or mass detection can be used.

schemes are shown in Figure 4. Some property associated with the final state permits detection of the multiphoton absorption, for example, fluorescence in (a) and photocurrent in (b).

Excitation of two-photon transitions, as in Figure 4a, is useful in spectroscopy because the selection rules are different to those for the corresponding one-photon transition. For example the change in angular momentum quantum number, ΔL, in a two-photon transition is 0, ± 2, so, for example, an atomic S to D transition can be observed. High spectroscopic resolution may be attained using Doppler free two-photon absorption spectroscopy. In this method, the excitation beams are arranged to be counter-propagating, so that the Doppler broadening is cancelled out in transitions where the two excitation photons arise from beams with opposing wavevectors. In this case, the spectroscopic linewidth is governed only by the homogeneous dephasing time.

The level scheme in Figure 4b is also widely used in spectroscopy, but in this case the spectrum of the intermediate state is obtained by monitoring the photocurrent as a function of ω_1. The general technique is known as resonance enhanced multiphoton ionization (REMPI) and yields high-quality spectra of intermediate states which are not detectable by standard methods, such as fluorescence. The sensitivity of the method is high, and it is the basis of a number of analytical applications, often in combination with mass spectrometry.

Ultrafast Time Resolved Spectroscopy

The frequency and linewidth of a Raman transition may be extracted from the CARS measurement, typically by combining two narrow bandwidth pulsed lasers, and tuning one through the resonance while measuring the nonlinear signal intensity. The time resolved analogue requires two pulses, typically of a few picoseconds duration (and therefore a few wavenumbers bandwidth) at ω_1 and ω_2 to be incident on the sample. This pair coherently excites the Raman mode. A third pulse at ω_1 is incident on the sample a time t later, and stimulates the CARS signal at $2\omega_1 - \omega_2$ in the phase-matched direction. The decay rate of the vibrational coherence is measured from the CARS intensity as a function of the delay time. Thus, the frequency of the mode is measured in the frequency domain, but the linewidth is measured in the time domain. If very short pulses are used (such that the pulsewidth is shorter than the inverse frequency of the Raman active mode) the Raman transition is said to be impulsively excited, and the CARS signal scattered by the time delayed pulse reveals an oscillatory response at the frequency of the Raman active mode, superimposed on its decay. Thus, in this case, spectroscopic information is measured exclusively in the time domain. In the case of nonlinear Raman spectroscopy, similar information is available from the frequency and the time domain measurements, and the choice between them is essentially one of experimental convenience. For example, time domain CARS, RIKES, and DFWM spectroscopy have turned out to be particularly powerful routes to extracting low-frequency vibrational and orientational modes of liquids and solutions, thus providing detailed insights into molecular interactions and reaction dynamics in the condensed phase.

Other time domain experiments contain information that is not accessible in the frequency domain. This is particularly true of photon echo methods. The name suggests a close analogy with nuclear magnetic resonance (NMR) spectroscopy, and the (optical) Bloch vector approach may be used to describe both measurements, although the transition frequencies and time-scales involved differ by many orders of magnitude. In the photon echo experiment, two or three ultrafast pulses with carefully controlled interpulse delay times are resonant with an electronic transition of the solute. In the two-pulse echo, the echo signal is emitted in the phase match direction at twice the interpulse delay, and its intensity as a function of time yields the homogeneous dephasing time associated with the transition. In the three-pulse experiment the pulses are separated by two time delays. By measuring the intensity of the stimulated echo as a function of both delay times it is possible to separately determine the dephasing time and the population relaxation time associated with the resonant transition. Such information is not accessible from linear spectroscopy, and can be extracted only with difficulty in the frequency domain. The understanding of photon echo spectroscopy has expanded well beyond the simple description given here, and it now provides unprecedented insights into optical dynamics in solution, and thus informs greatly our understanding of chemistry in the condensed phase. The methods have recently been extended to the infra red, to study vibrational transitions.

Higher-Order and Multidimensional Spectroscopies

The characteristic feature of this family of spectroscopies is the excitation of multiple resonances, which may or may not require measurements at $\chi^{(n)}$ with $n > 3$. Such experiments require multiple frequencies, and may yield weak signals, so they only became experimentally viable upon the availability of stable and reliable solid state lasers and optical parametric generators. Measurements are made in either the time or the frequency domain, but in either case benefit from heterodyne detection.

One of the earliest examples was two-dimensional Raman spectroscopy, where multiple Raman active modes are successively excited by temporally delayed pulse pairs, to yield a fifth-order nonlinear signal. The signal intensity measured as a function of both delay times (corresponding to the two dimensions) allows separation of homogeneous and inhomogeneous contributions to the line shape. This prodigiously difficult $\chi^{(5)}$ experiment has been completed in a few cases, but is plagued by interference from third-order signals.

More widely applicable are multidimensional spectroscopies using infrared pulses or combinations of them with visible pulses. The level scheme for one such experiment is shown in Figure 5 (which is one of many possibilities). From the scheme, one can see that the nonlinear signal in the visible depends on two resonances, so both can be detected. This can be regarded as a multiply resonant nondegenerate four-wave mixing (FWM) experiment. In addition, if the two resonant transitions are coupled, optical excitation of one affects the other. Thus, by measuring the signal as a function of both frequencies, the couplings between transitions are observed. These appear as cross peaks when the intensity is plotted in the two frequency dimensions, very much as with 2D NMR. This technique is already providing novel information on molecular structure and structural dynamics in liquids, solutions, and proteins.



Figure 5 Illustration of multiple resonance enhancements in a FWM geometry, from which 2D spectra may be generated.

Spatially Resolved Spectroscopy

A recent innovation is nonlinear optical microscopy. The nonlinear dependence of signal strength on intensity means that nonlinear processes are localized at the focal point of a lens. When focusing is strong, such as in a microscope objective, spatial localization of the nonlinear signal can be dramatic. This is the basis of the two-photon fluorescence microscopy method, where a high repetition rate source of low-energy ultrafast pulses is focused by a microscope objective into a sample labeled with a fluorescent molecule, which has absorption at half the wavelength of the incident photons (Figure 4). The fluorescence is necessarily localized at the focal point because of its dependence on the square of the incident intensity. By measuring intensity while scanning the position of the focal point in space, a 3D image of the distribution of the fluorophore is constructed. This technique turns out to have a number of advantages over one photon fluorescence microscopy, most notably in terms of ease of implementation, minimization of sample damage, and depth resolution. The technique is widely employed in cell biology.

Stimulated by the success of two-photon microscopy, further nonlinear microscopies have been developed, all relying on the spatial localization of the signal. CARS microscopy has been demonstrated to yield 3D images of the distribution of vibrations in living cells. It would be difficult to recover such data by linear optical microscopy. SHG has been applied in microscopy. In this case, by virtue of the symmetry selection rule referred to above, a 3D image of orientational order is recovered. Both these and other nonlinear signals provide important new information on complex heterogeneous samples, most especially living cells.

See also

Spectroscopy: Nonlinear Laser Spectroscopy; Raman Spectroscopy.

Further Reading

Andrews DL and Allcock P (2002) *Optical Harmonics in Molecular Systems*. Weinheim, Germany: Wiley-VCH.

Andrews DL and Demidov AA (eds) (2002) *An Introduction to Laser Spectroscopy*. New York: Kluwer Academic.

Butcher PN and Cotter D (1990) *The Elements of Nonlinear Optics*. Cambridge, UK: Cambridge University Press.

Cheng JX and Xie XS (2004) Coherent anti-Stokes Raman scattering microscopy: Instrumentation, theory, and applications. *Journal of Physical Chemistry B* 108: 827.

de Boeij WP, Pshenichnikov MS and Wiersma DA (1998) Ultrafast solvation dynamics explored by femtosecond photon echo spectroscopies. *Annual Review of Physical Chemistry* 49: 99.

Eisenthal KB (1992) Equilibrium and dynamic processes at interfaces by 2nd harmonic and sum frequency generation. *Annual Review of Physical Chemistry* 43: 627.

Fleming GR (1986) *Chemical Applications of Ultrafast Spectroscopy*. Oxford, UK: Oxford University Press.

Fleming GR and Cho M (1996) Chromophore-solvent dynamics. *Annual Review of Physical Chemistry* 47: 109.

Fourkas JT (2002) Higher-order optical correlation spectroscopy in liquids. *Annual Review of Physical Chemistry* 53: 17.

Hall G and Whitaker BJ (1994) Laser-induced grating spectroscopy. *Journal of Chemistry Society Faraday Transactions* 90: 1.

Heinz TF (1991) Second order nonlinear optical effects at surfaces and interfaces. In: Ponath H-E and Stegeman GI (eds) *Nonlinear Surface Electromagnetic Phenomena*, pp. 353.

Hesselink WH and Wiersma DA (1983) Theory and experimental aspects of photon echoes in molecular solids. In: Hochstrasser RM and Agranovich VM (eds) *Spectroscopy and Excitation Dynamics of Condensed Molecular Systems*, chap. 6. Amsterdam: North Holland.

Levenson MD and Kano S (1988) *Introduction to Nonlinear Laser Spectroscopy*. San Diego, CA: Academic Press.

Meech SR (1993) Kinetic application of surface nonlinear optical signals. In: Lin SH, Fujimura Y, and Villaeys A (eds) *Advances in Multiphoton Processes and Spectroscopy*, vol. 8, pp. 281. Singapore: World Scientific.

Mukamel S (1995) *Principles of Nonlinear Optical Spectroscopy*. Oxford: Oxford University Press.

Rector KD and Fayer MD (1998) Vibrational echoes: a new approach to condensed-matter vibrational spectroscopy. *International Review of Physical Chemistry* 17: 261.

Richmond GL (2001) Structure and bonding of molecules at aqueous surfaces. *Annual Review of Physical Chemistry* 52: 357.

Shen YR (1984) *The Principles of Nonlinear Optics*. New York: Wiley.

Smith NA and Meech SR (2002) Optically heterodyne detected optical Kerr effect – Applications in condensed phase dynamics. *International Review of Physical Chemistry* 21: 75.

Tolles WM, Nibler JW, McDonald JR and Harvey AB (1977) Review of theory and application of coherent anti-Stokes Raman spectroscopy (CARS). *Applied Spectroscopy* 31: 253.

Wright JC (2002) Coherent multidimensional vibrational spectroscopy. *International Review of Physical Chemistry* 21: 185.

Zipfel WR, Williams RM and Webb WW (2003) Nonlinear magic multiphoton microscopy in the biosciences. *Nature Biotechnology* 21: 1368.

Zyss J (ed.) (1994) *Molecular Nonlinear Optics*. San Diego: Academic Press.

Photodynamic Therapy of Cancer

A J MacRobert and T Theodossiou, University College London, London, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

One of the most active areas of photomedical research, in recent years, has been the exploration of the use of light-activated drugs known as photosensitizers. These compounds may be activated using light, usually provided by a laser via an optical fiber which is placed at the site of the target lesion. This treatment is known as photodynamic therapy (PDT) and is being applied to the local destruction of malignant tumors and certain nonmalignancies. Activation of the photosensitizer results in the generation of reactive oxidizing intermediates which are toxic to cells, and this process ultimately leads to tumor destruction. PDT is a relatively low-power, nonthermal, photochemical technique that uses fluence rates not exceeding 200 mW/cm^2 and total light doses or fluences of typically 100 J/cm^2. Generally red or near-infrared light is used, since tissue is relatively transparent at these wavelengths. It is a promising alternative approach to the local destruction of tumors for several reasons. First, it is a minimally invasive treatment since laser light can be delivered with great accuracy to almost any site in the body via thin flexible optical fibers with minimal damage to overlying normal tissues. Second, the nature of PDT damage to tissues is such that healing is safer and more complete than after most other forms of local tissue destruction (e.g., radiotherapy). PDT is also capable of some degree of selectivity for tumors when the sensitizer levels, light doses, and irradiation geometry are carefully controlled. This selectivity is based on the higher sensitizer retention in tumors after administration relative to the adjacent normal tissues in which the tumor arose (generally 3:1 for extracranial tumors but up to 50:1 for brain tumors).

The photosensitizer is administered intravenously to the patient and time allowed (3–96 hours depending on the sensitizer) for it to equilibrate in the body before the light treatment (Figure 1). This time is called the drug–light interval. PDT may also be useful for treating certain nonmalignant conditions, in particular, psoriasis and dysfunctional menorrhagia (a disorder of the uterus), and local treatment of infections; such as genital papillomas, infections in the mouth and the upper gastrointestinal tract. In certain cases, the photosensitizer may be applied directly to the lesions, particularly for treatment of skin tumors, as discussed later. The main side-effect of PDT is skin photosensitivity, owing to retention of the drug in the skin, so patients must avoid exposure to sunlight in particular for a short period following treatment. Retreatment is then possible once the photosensitizer has cleared from the skin since these drugs have little intrinsic toxicity, unlike many conventional chemotherapy agents.



Figure 1 Photodynamic therapy: from sensitization to treatment.

Photoproperties of Photosensitizers

By definition, there are three fundamental requirements for obtaining a photodynamic effect: (a) light of the appropriate wavelength matched to the photosensitizer absorption; (b) a photosensitizer; and (c) molecular oxygen. The ideal photochemical and biological properties of a photosensitizer may be easily summarized, although the assessment of a sensitizer in these terms is not as straightforward as might be supposed because the heterogeneous nature of biological systems can sometimes profoundly affect these properties. Ideally though, a sensitizer should possess the following attributes: (a) red or near infrared light absorption; (b) nontoxic, and with low skin photosensitizing potency; (c) selective retention in tumors relative to normal adjacent tissue; (d) an efficient generator of cytotoxic species, usually singlet oxygen; (e) fluorescence, for visualization; (f) a defined chemical composition, and (g) preferably water soluble. A list of several photosensitizers possessing the majority of the above-mentioned attributes is given in Table 1.

The reasons for these requirements are partly self-evident, but worth amplifying. Strong absorption is desirable in the red and near-infrared spectral region, where tissue transmittance is optimum enabling penetration of the therapeutic light within the tumor (Figure 2). To minimize skin photosensitization by solar radiation, the sensitizer absorption spectrum should ideally consist of a narrow red wavelength band, with little absorption at other wavelengths down to 400 nm, below which solar irradiation falls off steeply. Another advantage of red wavelength irradiation is that the potential mutagenic effects encountered with UV-excited sensitisers (e.g., psoralens) are avoided. Since the object of the treatment is the selective destruction of tumor tissue, leaving surrounding normal tissue undamaged, some degree of selective retention of the dye in tumor tissue is desirable. Unfortunately, the significance of this aspect has been exaggerated in the literature and in many cases treatment selectivity owes more to careful light irradiation geometry. Nevertheless, many normal tissues have the capacity to heal safely following PDT damage.

The key photochemical property of photosensitizers is to mediate production of some active

Table 1 Properties of several photosensitizers

Compound	*λ/nm (ε/M^{-1} cm^{-1})*	*Drug dose/mg kg^{-1}*	*Light dose/J cm^{-2}*	*Diseases treated*
Hematoporphyrin (HpD–Photofrin–Photosan)	628 (3.0×10^3)	1.5–5	75–250	Early stage esophagus, bladder, lung, cervix, stomach, and mouth cancers. Palliative in later stages
ALA (converted to protoporphyrin IX)	635 (5×10^3)	60	50–150	Skin, stomach, colon, bladder, mouth cancers. Esophageal dysplasia. Various nonmalignant conditions
Benzoporphyrin derivative (BpD)	690 (3.5×10^4)	4	150	Age-related macular degeneration (AMD)
Tin etiopurpurin (SnET2–Purlytin)	665 (3.0×10^4)	1.2	150–200	Breast and skin cancers, AMD
Monoaspartyl chlorin e_6 (MACE)	660 (4.0×10^4)	1.0	25–200	Skin cancers
Lutetium texaphyrin (Lu–Tex)	732 (4.2×10^4)	1.0	150	Metastatic brain tumors, breast cancers, atherosclerotic plaques
Aluminum disulfonated phthalocyanine	675 (2.0×10^5)	1.0	50–200	Brain, colon, bladder, and pancreatic cancers. Head and neck cancers in animal studies only
Metatetrahydroxychlorin (mTHPC–temoporphin–Foscan)	652 (3.5×10^4)	0.15	5–20	Head, neck, prostate, pancreas, lung, brain, biliary tract, and mouth cancers. Superior to HpD and ALA in mouth cancers
Palladium pheophorbide (Tookad)	763 (8.6×10^4)	2.0	–	Prostate cancer
Hypericin	590 (3×10^4)	–	–	Psoriasis



Figure 2 The absorption spectrum of m-THPC. The structure of m-THPC is shown in the inset.

molecule which is cytotoxic, that is, will destroy cells. The first electronically excited state of molecular oxygen, so-called singlet oxygen, fulfills this role very well and may be produced via the interaction of an excited electronic state of the sensitizer with oxygen present in the tissue. Thus, in summary, to achieve effective photosensitization, a sensitizer should exhibit appreciable absorption at red to near-infrared wavelengths and generate cytotoxic species via oxygen-dependent photochemical reactions. The first clinical photosensitizer was hematoporphyrin derivative (HpD), which is derived synthetically from hematoporphyrin by reaction with acetic and sulfuric acids to give a complex mixture of porphyrins. A purified fraction of these (Photofrin) is available commercially, and this has been used most widely in clinical applications to date. Second-generation (photosensitizers are now becoming available, including phthalocyanine and chlorin compounds as shown in Table 1.

A new approach to PDT has recently emerged involving the administration of a natural porphyrin precursor, 5-aminolaevulinic acid (ALA), which is metabolized within cells to produce protoporphyrin IX (see Table 1). This porphyrin is known to be a powerful photosensitizing agent but suffers from the drawback of being a poor tumor localizer when used directly. In contrast, administration of ALA induces protoporphyrin biosynthesis, particularly in rapidly proliferating cells, which may then be destroyed using irradiation at 630 nm. Therefore, this new therapy may offer enhanced treatment selectivity with little risk of skin photosensitivity owing to the rapid clearance after 24 h of the protoporphyrin. Investigation of this new approach has already proved successful in clinical treatment of skin tumors using topical application of ALA in a thick emulsion.

Considerable effort is also being expended on exploiting the retention of sensitizers in tumors for diagnostic purposes, although the results are rather mixed to date. The prospects with ALA-induced protoporphyrin IX are, however, more promising, as illustrated in Figure 3 where the fluorescence is selectively confined to the skin tumor (basal cell carcinoma).



Figure 3 (a) Image of a basal cell carcinoma; (b) fluorescence imaging of the same lesion after ALA sensitization and 405 nm light excitation.

Mechanisms of Photodynamic Therapy

The main principles of the photosensitization mechanism are now well established with the initial step being excitation of the sensitizer from its electronic ground state to the short-lived fluorescent singlet state. The lifetime of the singlet state is generally only a few nanoseconds and the main role of this state in the photosensitization mechanism is to act as a precursor of the metastable triplet state through intersystem crossing. Efficient formation of this metastable state is required because it is the interaction of the triplet state with tissue components that generates cytotoxic species such as singlet oxygen. Thus the triplet state quantum yield (i.e., probability of triplet state formation per photon absorbed) of photosensitizers should ideally approach unity. Interaction of the metastable triplet state (which in de-aerated solutions has a lifetime extending to the millisecond range) with tissue components may proceed via either a type I or II mechanism or a combination (see Figure 4). A type I process can involve hydrogen abstraction from the sensitizer to


$PS \xrightarrow{h\nu} {}^1PS^*$
${}^1PS^* \longrightarrow {}^3PS^*$
Type I mechanism
${}^3PS^* + {}^3PS^* \longrightarrow PS^{+\bullet} + PS^{-\bullet}$
${}^3PS^* + SUB \longrightarrow SUB^{+\bullet} + PS^{-\bullet}$
$PS^{-\bullet} + {}^3O_2 \longrightarrow PS + O_2^{-\bullet}$
$O_2^{-\bullet} + NO^\bullet \longrightarrow ONOO^-$
$SUB^{+\bullet} + {}^3O_2 \longrightarrow$ oxidative damage
$SUB + O_2^{-\bullet} \longrightarrow$ oxidative damage
$SUB + HO^\bullet + HO^- \longrightarrow$ oxidative damage
Type II mechanism
${}^3PS + {}^3O_2 \longrightarrow {}^1PS + {}^1O_2$
${}^1O_2$ + proteins ⟶ functional changes
${}^1O_2$ + cholesterol/PUFA ⟶ lipid peroxidation
${}^1O_2 + NADPH \longrightarrow NADP^+$
${}^1O_2$ + DNA ⟶ base oxidation
${}^1O_2$ + collagen ⟶ denaturation
vascular occlusion ∴ ischemia
ATP
ADP
AMP
Adenosine
Inosine
Hypoxanthene
Xanthene
Xanthene dehydrogenase
Xanthene oxidase
$O_2^{-\bullet}$
SOD
H_2O_2
Fe^{2+}
$HO^\bullet + HO^-$
${}^3O_2$ (reperfusion)

Figure 4 The photophysical and photochemical mechanisms involved in PDT. PS denotes the photosensitizer, SUB denotes the substrate, either biological, a solvent or another photosensitizer; * denotes the excited state and • denotes a radical.

produce free radicals or electron transfer, resulting in ion formation. The type II mechanism, in contrast, exclusively involves interaction between molecular oxygen and the triplet state to form singlet oxygen which is highly reactive in biological systems. The near-resonant energy transfer from the triplet state to O_2 can be highly efficient and the singlet oxygen yield can approach the triplet state yield provided that the triplet state energy exceeds 94 kJ/mol, the singlet oxygen excitation energy. It is widely accepted that the type II mechanism underlies the oxygen-dependent phototoxicity of sensitizers used for photodynamic therapy. Both proteins and lipids (the main constituents of membranes) are susceptible to photooxidative damage induced via a type II mechanism which generally results in the formation of unstable peroxide species. For example, unsaturated lipids may be oxidized by the 'ene' reaction where the singlet oxygen reacts with a double bond. Other targets include such important biomolecules as cholesterol, certain amino acid residues, collagen, and the coenzyme, NADPH. Another synergistic mode of action involves the occlusion of the microcirculation to tumors and reperfusion injury. Reperfusion injury relates to the formation of xanthene oxidase from xanthene dehydrogenase in anoxic conditions which reacts with xanthene or hypoxanthene products of ATP dephosphorylation to convert the restored oxygen into superoxide anion which directly or via the Fenton reaction causes cellular damage.

An important feature of the type II mechanism, which is sometimes overlooked, is that when the sensitizer transfers electronic energy to O_2 it returns to its ground state. Thus the cytotoxic singlet oxygen species is generated without chemical transformation of the sensitizer which may then absorb another photon and repeat the cycle. Effectively, a singlet photosensitizer molecule is capable of generating many times its own concentration of singlet oxygen, which is clearly a very efficient means of photosensitization provided the oxygen supply is adequate.

Lasers in PDT

Lasers are the most popular light source in PDT since they have several key characteristics that differentiate them from conventional light sources, namely coherence, monochromaticity, and collimated output. The two main practical features that make them so useful in PDT are their monochromaticity and their combination with fiber-optic delivery. The monochromaticity is important since the laser can be tuned to a specific absorption peak of a photosensitizer, thus ensuring that all the energy delivered is utilized for the excitation and photodynamic activation of the photosensitizer. This is not true for a conventional light source (as for example a tungsten lamp) where the output power is divided over several hundred nanometers throughout the UV, visible, and IR regions and only a fraction of the power lies within the absorption band of the photosensitizer. To numerically illustrate this, let us simplify things by representing the lamp output as a square profile and also consider a photosensitizer absorption band about 30 nm full width half maximum. If a laser with a frequency span of about 2 nm and a lamp with the same power but with a frequency span of about 600 nm are used, then the useful portion of it is about 0.05 and if we consider a Gaussian profile for the sensitizer absorption band, the above fraction drops even lower, perhaps even to 0.01. That means that the lamp would achieve 100 times less the excitation rate of the laser, or in other words, we would require a lamp with an output power of 100 times that of the laser to achieve the same rate of excitation and consequently the same time of treatment, provided we use a low enough laser power to remain within the linear regime of the photosensitizer excitation. The other major disadvantage of a lamp source is the lack of collimation which results in low efficiency for fiber-optic delivery.

We now review the different lasers that have found application in PDT. Laser technology has significantly advanced in recent years and there are now a range of options in PDT laser sources for closely matching the absorption profiles of the various photosensitizers. Moreover, since PDT is becoming more widely used clinically, practical considerations, such as portability and turn-key operation are increasingly important. In Figure 5 the optical spectrum is shown from about 380 nm (violet–blue) to 800 nm (near-infrared, NIR). We have superimposed on this spectrum, the light penetration depth of tissue to roughly illustrate how deeply light can penetrate (and consequently activate photosensitizer molecules) into lower-lying tissue layers. The term 'penetration depth' is a measure of the light attenuation by the tissue so the figure of 2 mm corresponds to $1/e$ attenuation of the incident intensity at a tissue depth of 2 mm. It is obvious that light at the blue end of the spectrum has only a superficial effect whereas the more we shift further into the red and NIR regions the penetration depth increases. This is due to two main reasons: absorption and scattering of light by various tissue component molecules. For example, in the blue/green region for the absorption of melanin and hemoglobin is relatively high. But there is a noticeable increase in penetration depth beyond about 600 nm leading to an optimal wavelength region, or



Figure 5 Photosensitizers and laser light sources available in the visible and near-infrared spectral regions.

'therapeutic window' for laser therapy of around 600–1100 nm (Figure 5).

The fundamental wavelength of the Nd:YAG laser lies within this therapeutic window at 1064 nm and this laser is now widely used in thermal laser therapy. The Nd:YAG lasers can be operated either in cw (output power ~ 200 W multimode), long-pulse (~ 500 W average power at 50 Hz), or Q-switched

(50 MW peak power at around 10 ns pulse duration) modes. Nd:YAG is a solid-state laser with a yttrium aluminum garnet crystal doped with about 1% of trivalent Nd ions as the active medium of the laser; and with another transition of the Nd ion, this laser (with the choice of different optics) can also operate at 1320 nm. Although dyes are available which absorb from 800–1100 nm, the generation of singlet oxygen via the type II mechanism is energetically unfavorable because the triplet state energies of these dyes are too low. However, the fundamental frequency of the laser can be doubled (second-harmonic generation, SHG) or tripled (third-harmonic generation, THG) with the use of nonlinear crystals, to upconvert the output radiation to the visible range, thus rendering this laser suitable for PDT: i.e., frequency doubling to 532 nm and tripling to 355 nm. Note that the 532 nm output is suitable for activation of the absorption band of hypericin with a maximum at 550 nm even though it is not tuned to the maximum of this absorption.

In the early days of PDT and other laser therapies, ion lasers were widely used. The argon ion laser uses ionized argon plasma as gain medium, and produces two main wavelengths at 488 nm and 514 nm. The second of the two lies exactly at the maximum of the 514 nm m-THPC absorption. Argon ion lasers are operated in cw mode and usually have output powers in the region of 5–10 W at 514 nm (the most powerful argon ion line). Krypton ion lasers, which emit at 568 or 647 nm, are similar to their argon ion counterparts; however, they utilize ionized krypton plasma as gain medium. The 568 nm output can be used to activate the Rose Bengal peak at 559 nm, whereas the 647 nm most powerful line of krypton ion lasers, has been used for activation of m-THPC (652 nm).

Ideally, for optimal excitation, it is best to exactly tune the laser wavelength to the maxima of photosensitizer absorption bands. For this reason tunable organic dye lasers have been widely used for PDT. In these lasers the gain medium is an organic dye with a high quantum yield of fluorescence. Due to the broad nature of their fluorescence gain profile, tuning elements within the laser cavity can be used for selection of the lasing frequency within the gain band. Tunable dye lasers with the currently available dyes can quite easily cover the range from about 350–1000 nm. However, their operation is not of a ‘turn key’ nature since they require frequent replacement of their active material either for tuning to a different spectral region or for a better performance when the dye degrades. Tunable dye lasers also need to be pumped by some other light source like an argon ion laser, an excimer laser, a solid state laser (e.g., Nd:YAG 532 or 355 nm), a copper vapor laser, or lamps. Dye lasers have been used for the excitation of HpD at 630 nm, protoporphyrin IX at 635 nm, photoprotoporphyrin at 670 nm, and phthalocyanines around 675 nm. A further example is hypericin which, apart from the band at 550 nm, has a second absorption band at 590 nm. This is the optimum operation wavelength of dye lasers with rhodamine 590, better known as rhodamine 6G.

Dye lasers can operate in either pulsed or cw mode. However, there is a potential disadvantage in using a pulsed laser for PDT which becomes apparent when using lower repetition rates and higher pulse energies (>1 mJ per pulse) laser excitation. High pulse energies can induce saturation or transient bleaching of the sensitizer during the laser pulse and consequently much of the energy supplied is not efficiently absorbed by the sensitizer. It has been suggested that this effect accounts for the lack of photosensitized damage in tissue sensitized with a phthalocyanine and irradiated by a 5 Hz, 25 mJ-per-pulse flash lamp pumped dye laser. However, using a low pulse energy, high repetition rate copper vapor pumped dye laser (see below), the results were indistinguishable from cw irradiation with an Argon ion dye laser.

Another laser that has found clinical application in PDT is the copper vapor laser. In this laser the active medium is copper vapor at high temperature maintained in the tube by a repetitively pulsed discharge current. The copper vapor lasers are pulsed with typical pulse duration of about 50 ns and repetition rates reaching 20 kHz. Copper vapor lasers have been operated at quite high average powers up to about 40 W. The output radiation is produced at two distinct wavelengths, namely 511 and 578 nm both of which have found clinical use. Copper vapor pumped dye lasers have also been widely used for activating red-absorbing photosensitizers, and the analogous gold vapor lasers operating at 628 nm have been used to activate HpD.

A relatively new class of tunable lasers is the solid state Ti:Sapphire laser. The gain medium in this laser is a $\sim 1\%$Ti doped sapphire (Al_2O_3) crystal and its output may be tuned throughout the 690–1100 nm region, covering many photosensitizer absorption peaks. For example, most of the bacteriochlorin type photosensitizers have their absorption bands in that spectral region, e.g., m-THPBC with an absorption maximum at 740 nm. Also, Texaphyrin sensitizers absorb highly in this spectral region: lutetium texaphyrin has an absorption maximum at 732 nm.

Although tunable dye or solid-state lasers are widely used in laboratory studies for PDT, fixed-wavelength semiconductor diode lasers are gradually supplanting tunable lasers, owing to their practical convenience. It is now generally the case that when a photosensitizer enters clinical trials or enters standard clinical use, laser manufacturers provide dedicated diode lasers with outputs matched to the chosen sensitizer. In this context there are diode lasers available at 630 nm for use with HpD, at 635 nm for use with ALA-induced protoporphyrin IX, 670 nm for ATSX-10 or phthalocyanines, or even in the region of 760 nm, for use with bacteriochlorins. The advantage of these diode lasers is that they are tailormade for use with a particular photosensitizer, they are highly portable, and they have a relatively easy turn-key operation.

So far we have concentrated on red wavelengths but most of the porphyrin and chlorin family of photosensitizers exhibit quite strong absorption bands in the blue region, known as 'Soret' bands. Despite the fact that tissue penetration in this spectral region is minimal, these bands are far more intense than the corresponding red absorption bands of the sensitizer. In this respect it is possible to activate these sensitizers at blue wavelengths, especially in the case of treatment of superficial (e.g., skin) malignant lesions. There are now blue diode lasers (and light-emitting diodes) for the activation of these bands, in particular at 405 nm where the Soret band of protoporphyrin IX lies or at 430 nm for selective excitation of the photoprotoporphyrin species. For very superficial lesions (e.g., in the retina) it may even be possible to use multiphoton excitation provided by femtosecond diode lasers operating at about 800 nm.

Clinical Applications of Lasers in PDT

In the previous section we reviewed the various types of lasers being used for PDT but their combination with fiber-optic delivery is also of key importance for their clinical application. The laser light may be delivered to the target lesion either externally using surface irradiation, or internally within the lesion which is denoted as interstitial irradiation, as depicted in Figure 6. For example, in case of superficial cutaneous lesions the laser irradiation is applied externally (Figure 6a). The area of the lesion is marked prior to treatment to determine the diameter of the laser spot. For a given fluence rate (100–200 W/cm^2) and the area of the spot, the required laser output power is then calculated. A multimode optical fiber, terminated with a microlens to ensure uniform irradiation, is then positioned at a distance from the lesion yielding the desired beam waste, and the surrounding normal tissue is shielded with dark material. However, if the lesion is a deeper-lying solid tumor, interstitial PDT is employed



Figure 6 Clinical application of PDT. (a) Surface treatment. (b) Interstitial treatment.



Figure 7 Balloon applicator and diffuser fiber used for PDT in Barrett's esophagus.



Figure 8 PDT treatment of a nasal basal cell carcinoma with m-THPC (Foscan®): (a) prior to PDT; (b) tissue necrosis a week after treatment; (c) four weeks after treatment; gradual recession of the necrosis and inflammation; (d) healing two months after treatment. Courtesy of Dr Alex Kuebler.

(Figure 6b). Surgical needles are inserted in an equidistant parallel pattern within the tumor, either freehand or under image (MRI/CT) guidance. Bare tip optical fibers are guided through the surgical needles to the lesion and flagged for position. A beamsplitter is used to divide the laser output into 2–4 components so that two to four optical fibers can be simultaneously employed. The laser power is adjusted so that the output fluence of each of the optical fibers is 100–200 mW. Even light distribution in the form of overlapping spheres approximately 1 cm diameter ensures the treatment of an equivalent volume of tissue around each fiber tip. Once each 'station' is likewise treated the fibers are repositioned accordingly, employing a pull-back technique in order for another station to be treated. Once the volume of the tumor is scanned in this manner the treatment is complete. Interstitial light delivery allows PDT to be used in the treatment of large, buried tumors and is particularly suitable for those in which surgery would involve extensive resection.

The treatment of tumors of internal hollow organs is also possible with PDT. The most representative example of this is the treatment of precancerous lesions in the esophagus, known medically as 'Barrett's esophagus'. In this case, a balloon applicator is used to house a special fiber with a light-diffusing tip or 'diffuser' (Figure 7). These diffusers are variable in length and transmit light uniformly along the whole of their length in order to facilitate treatment of circumferential lesions. The balloon applicator is endoscopically inserted into the patient. The balloon is inflated to stretch the esophageal walls and the flagged diffuser fiber is placed in position, central to the balloon optical window. In this way the whole of the lesion may be treated circumferentially at the same time.

Finally, the clinical response to PDT treatment is shown in Figure 8. The treated area becomes necrotic and inflamed within two to four days following PDT. This necrotic tissue usually sloughs off or is mechanically removed. The area eventually heals with minimal scarring (Figure 8).

Future Prospects

A major factor in the future development of PDT will be the application of relatively cheap and portable semiconductor diode lasers. High-power systems consisting of visible diode arrays coupled into multimode fibers with an output of several Watts, have recently become available which will greatly simplify the technical difficulties which have held back PDT. The use of new photosensitizers, in the treatment of certain tumors by PDT, is making steady progress, and although the toxicology testing and clinical evaluation are lengthy and costly processes, the expectation is that these compounds will become more widely available for patient use during the next five years. Regarding the current clinical status of PDT, Photofrin has recently been approved for treatment of lung and esophageal cancers in Europe, USA, and Japan. Clinical trials are in progress for several of the second-generation photosensitizers which offer significant improvements over Photofrin in terms of chemical purity, photoproperties, and skin clearance. With the increasing clinical application of compact visible diode lasers the prospects for photodynamic therapy are therefore encouraging.

See also

Lasers: Dye Lasers; Free Electron Lasers; Metal Vapor Lasers. **Ultrafast Laser Techniques:** Generation of Femtosecond Pulses.

Further Reading

Bonnet R (2000) *Chemical Aspects of Photodynamic Therapy*. Amsterdam: Gordon and Breach Science Publishers.

Dolmans DEJGJ, Fukumura D and Jain RK (2003) Photodynamic therapy for cancer. *Nature Reviews (Cancer)* 3: 380–387.

Hopper C (2000) Photodynamic therapy: a clinical reality in the treatment of cancer. *Lancet Oncology* 1: 212–219.

Milgrom L and MacRobert AJ (1998) Light years ahead. *Chemistry in Britain* 34: 45–50.

Rosen GM, Britigan BE, Halpern HJ and Pou S (1999) *Free Radicals Biology and Detection by Spin Trapping*. New York: Oxford University Press.

Svelto O (1989) *Principles of Lasers*, 3rd edn. New York: Plenum Press.

Vo-Dinh T (2003) *Biomedical Photonics Handbook*. Boca Raton, FL: CRC Press.

Pump and Probe Studies of Femtosecond Kinetics

G D Scholes, University of Toronto, Toronto, ON, Canada

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Pump-probe spectroscopy is a ubiquitous time-resolved optical spectroscopy that has found application to the study of all manner of ultrafast chemical processes that involve excited states. The principle of the measurement is that a ‘pump pulse’ – usually an intense, short laser pulse – impulsively excites a sample, thus defining the start time for the ensuing photophysical dynamics. A probe pulse interrogates the system at later times in order to capture ‘snap shots’ of the state of the system. Many kinds of pump-probe experiments have been devised. The present article will mainly focus on transient absorption measurements.

Femtosecond pump-probe experiments have been employed to reveal the kinetics of excited state chemical processes such as solvation, isomerization reactions, proton transfer, electron transfer, energy transfer, or photochromism. It is becoming more common to use pump-probe techniques to study systems of increasing complexity, such as photosynthetic proteins, photoreceptor proteins, molecular aggregates, nanostructured materials, conjugated polymers, semiconductors, or assemblies for artificial light harvesting. However, the underlying chemical kinetics are not always easily revealed by pump-probe signals.

The principle of the pump-probe measurement is related to the seminal flash-photolysis experiment devised by Norrish and Porter. However, in order to achieve ultrafast time resolution – beyond that attainable by electronic detection – the probe pulse is temporally short and is controlled to arrive at the sample at variable time delays after the pump pulse has excited the sample. The change in intensity of the probe pulse, as it is transmitted through the sample, is monitored at each pump-probe time delay using a ‘slow’ detector that integrates over the probe pulse duration. One possible xprocess that can diminish the probe transmission is transient absorption. After formation of an excited state S_1 by the pump pulse, the probe pulse can monitor a resonance with a higher excited state $S_1 \rightarrow S_n$ absorption. Figure 1 shows transient absorption spectra, corresponding to excited state absorption at various time delays, that has been probed by a white light continuum probe and monitored by a multichannel CCD detector. The transient spectrum is seen to blue-shift with



Figure 1 Excited state absorption spectra of 4′-*n*-pentyl-4-cyanoterphenyl in octanol solvent. The pump wavelength is 277 nm (100 nJ, 150 fs, 40 kHz) and the probe is a white light continuum (500 to 700 nm) generated in a sapphire crystal. The pump-probe delay *T* for each spectrum is indicated on the plot.



Figure 2 TR^3 spectra of 4′-*n*-pentyl-4-cyanoterphenyl in octanol solvent, recorded using the same set-up as summarized in Figure 1. The dashed lines are deconvolutions of the data to show the Raman bands.

pump-probe delay owing to solvation of the S_1 state of the molecule – the dynamic Stokes' shift. The dynamic Stokes' shift is the shift to lower energy of the emission spectrum as the solvent relaxes in response to the change in dipole moment of the excited electronic state compared to the ground state. The overall intensity of the induced absorption decays according to the lifetime of the excited state.

Although they will not be discussed in detail in the present article, various other pump-probe experiments are possible. For example, when in resonance with this transient absorption, the probe pulse can induce resonance Raman scattering, which reveals the evolution of the vibrational spectrum of the excited state. In this kind of pump-probe experiment we do not monitor the change in probe transmission through the sample. Instead, we monitor the difference between probe-induced resonance Raman scatter from the excited and ground states of the system. The resonance Raman (TR^3) scatter, time-resolved as a function of pump-probe delay, can be detected provided that it is not overwhelmed by fluorescence emission. Typical TR^3 data for different pump-probe delays are shown in Figure 2. The dashed lines show a deconvolution of the spectra to reveal the underlying vibrational bands. These bands are rather broad owing to the spectral width of the 1 ps laser pulses used in this experiment. It is clear that the time-resolution of a TR^3 experiment is limited to the picosecond regime, otherwise most of the vibrational band information is lost. TR^3 and complementary pump-probe infrared transient absorption experiments, utilizing an infrared probe beam, have been useful for observing the evolution of structural information, such as geometry changes, subsequent to photoexcitation.

In the present article we will describe the foundation of experiment and theory necessary to understand resonant ultrafast pump-probe spectroscopy applied to chemical processes in the condensed phase. By resonant, it is meant that the pump and probe pulses have frequencies (energies) resonant with electronic transitions of the molecules being studied. The implications of condensed phase are that the experiment interrogates an ensemble of molecules and the electronic transitions of these molecules are coupled to the random motions and environments of a bath, for example the solvent.

Experimental Measurement of Pump-Probe Data

The experimental setup for a one-color pump-probe experiment (i.e. pump and probe of the same color) is shown in Figure 3. The setup is easily adapted for a two-color experiment. Most of the laser intensity (70%) is transmitted through the first beam splitter so that the pump is more intense than the probe. A second beam splitter is used to split off a small amount of probe light for the reference beam. Note that the arrangement of these beam splitters results in both the pump and probe passing through the same amount of dispersive material on their way to the sample. The pump and probe beams each propagate through half-wave plates in order to control polarization. Usually the probe polarization is set to the magic angle (54.7°) relative to the pump in order to remove polarization bias. The beams are sent towards the sample by way of retroreflectors mounted on $x-y-z$ translation stages. The pump retroreflector is mounted on a precision computer-controlled translation stage such that it can be scanned in the x-direction to arrive at variable delays before and after the probe. The pump and probe beams are aligned using the $y-z$ controls on the retroreflector translation stages together with the pick-off mirrors



Figure 3 An experimental layout for femtosecond pump-probe spectroscopy. The reference beam ideally passes through the sample (not shown as such in aid of clarity). See text for a description. HWP, half-wave plate; BS, beamsplitter (% reflection); FL, focusing lens; CL, collimating lens; ND, neutral density filter; PD, photodetectors.

such that they travel in parallel towards the sample. The overall setup of the beams is in a box geometry so that pump and probe arms have the same path length.

The pump and probe beams are focused into the sample using a transmissive (i.e. lens) or reflective optic FL. The focal length is typically 20 to 30 cm, providing a small crossing angle to improve phase matching. The pump beam should have a larger spot size at its focal point in the sample than the probe beam, in order to avoid artifacts arising from the wandering of the pump and probe spatial overlap as a function of delay time – a potential problem, particularly for long delays. Good spatial overlap of the beams in the sample is important. It can be checked using a 50 μm pinhole. Fine adjustment of the pump-probe delay, to establish temporal overlap of the pump and probe pulses, can be dictated by autocorrelating the beams in a second harmonic generating crystal mounted at the sample position. At the same time the pulse compression is tweaked to ensure that the pulse dispersion in the experiment has been pre-compensated.

The sample is usually flowed or mounted in a spinning cell if it is liquid, in order to avoid thermal effects or photochemical bleaching. The path length of the sample is typically ≤1 mm. The transmitted probe beam is spatially isolated from the pump beam using an iris, is collimated, and then directed onto the photodetector.

The reference beam, which provides the relative reference intensity I_0 should preferably pass through the sample (away from the pump spot). This provides the probe-only transmission – that is, the reference beam intensity is attenuated according to sample ground state optical density. The photodetector outputs are used to ratio the pump-probe arm intensity transmitted through the sample with the reference intensity, $I_{\mathrm{pr}}(\omega, T)/I_0$. Since the pump beam is being chopped at the lock-in reference frequency, the lock-in amplifier outputs the pump-induced fractional change in transmission intensity, $\Delta I_{\mathrm{pr}}(\omega, T)/I_0$, usually simply written as $\Delta T/T$. When the pump-induced signal I_{pr} is small compared to the reference intensity I_0, then the detected $\Delta I_{\mathrm{pr}}(\omega, T)/I_0$ signal is approximately equal to the change in optical density, ΔO.D.:

$$\Delta\mathrm{O.D.} = \log\left(\frac{I_0 - \Delta I_{\mathrm{pr}}}{I_0}\right) \approx \frac{-\Delta I_{\mathrm{pr}}}{I_0} \equiv \frac{-\Delta T}{T} \qquad [1]$$

Here we have used a Taylor expansion $\log(1 + x) \approx x$ for small x.

The power dependence of the signal in the $\chi^{(3)}$ limit should be linear in both the pump and probe intensities. It is also possible to pump the sample using two-photon absorption, then probe an excited state absorption. This is a $\chi^{(5)}$ experiment, so that the signal depends quadratically on the pump intensity.

What is Measured in a Pump-Probe Experiment?

Origin of the Signal

The pump-probe measurement is a third-order nonlinear spectroscopy. A complete calculation of the signal requires computation of the third-order polarization induced by the interaction of the pump and probe with the material sample, together with an account for the kinetic evolution of populations (e.g., excited state reactant and product states, etc.).

The pump pulse, wavevector $\mathbf{k}_1$, interacts twice with the sample, thereby creating excited state population density $|e\rangle\langle e|$ and a hole-in-the-ground state population density $|g\rangle\langle g|$. These population densities propagate until the probe pulse, with wavevector $\mathbf{k}_2$, interacts with the system to induce a polarization that depends on the state of the system at time T after the pump. This induced polarization $P_s(t)$ is radiated in the $\mathbf{k}_s = \mathbf{k}_1 - \mathbf{k}_1 + \mathbf{k}_2 = \mathbf{k}_2$ direction. Because the signal is radiated in the probe direction, the probe pulse acts as a local oscillator to heterodyne the signal. The change in probe-pulse spectral intensity after transmission through an



Figure 4 Labeling and time variable for the description of a pump-probe experiment. T defines the pump-probe delay.

optically thin sample of path length l, with concentration of absorbers c and refractive index n, is given by eqn [2]

$$\Delta I_{\mathrm{pr}}(\omega,T)\propto\frac{cl\omega_{\mathrm{pr}}}{n}\mathrm{Im}\left[\int dtE^{*}_{\mathrm{pr}}(t)P^{(3)}(0,T,t)e^{i\omega t}\right]\qquad[2]$$

In eqn [2] $E_{\mathrm{pr}}(t)$ is the probe pulse electric field, ω is the center frequency of the probe, and * indicates complex conjugate. The time variables correspond to those indicated in Figure 4, and the signal is resolved as a function of frequency by Fourier transformation of $t\rightarrow\omega$. Experimentally this is achieved by dispersing the transmitted probe using a spectrograph. The first-time variable, the time interval between the two pump pulse interactions, is set to zero because we are interested here in the limit where the pulse duration is much shorter than T. In this regime – impulsive pump-probe – the measurement is sensitive to formation and decay of excited state species.

The induced polarization is given by eqn [3]

$$\begin{aligned}P^{(3)}(0,T,t)=&\int_0^\infty \mathrm{d}t\int_0^\infty \mathrm{d}T[R^{\mathrm{SE}}-R^{\mathrm{ESA}}+R^{\mathrm{GSR}}]\\&\times E_1^{*}(t-T)E_1(t-T)E_2(t)\qquad[3]\end{aligned}$$

where the response functions that contain information about the lineshape functions and kinetics are given by eqn [4]:

$$\begin{aligned}R^{\mathrm{SE}}(0,T,t)=&|\mu_{eg}|^2|\mu_{eg}|^2\exp(-i\omega_{eg}t)\\&\times\exp[-g^{*}(t)+2ig''(T+t)-2ig''(T)]\\&\times K^{\mathrm{SE}}(T)\qquad[4a]\end{aligned}$$

$$\begin{aligned}R^{\mathrm{ESA}}(0,T,t)=&|\mu_{eg}|^2|\mu_{fe}|^2\exp(-i\omega_{fe}t)\\&\times\exp[-g^{*}(t)-2ig''(T+t)+2ig''(T)]\\&\times K^{\mathrm{ESA}}(T)\qquad[4b]\end{aligned}$$

$$\begin{aligned}R^{\mathrm{GSR}}(0,T,t)=&|\mu_{eg}|^2|\mu_{eg}|^2\exp(-i\omega_{eg}t)\exp[-g(t)]\\&\times K^{\mathrm{GSR}}(T)\qquad[4c]\end{aligned}$$

The overall intensity of each contribution to the signal is scaled by the transition dipole moment that connects the ground and excited state μ_{eg} or excited state and a higher excited state μ_{fe}. The intensity is further influenced by resonance of the probe-pulse spectrum with the transition frequencies ω_{eg} and ω_{fe}. These transition energies have a time-dependence owing to the relaxation of the excited state density in the condensed phase environment – the dynamic Stokes' shift. The details of the dynamic Stokes' shift depend on the bath, and are therefore contained in the imaginary part of the lineshape function $g(t)=g'(t)+ig''(t)$. The evolution of the Stokes' shift with pump-probe delay T is clearly seen in the excited state absorption spectrum shown in Figure 1. The lineshape function contains all the details of the time-scales of fluctuations of the bath and the coupling of the electronic transition of the molecule to these fluctuations. The lineshape function can be cast in the simple form given by eqn [5] using the Brownian oscillator model in the high temperature, high friction limit:

$$\begin{aligned}g(t)\approx&(2\lambda k_B T_B/\hbar\Lambda)[\Lambda t-1+\exp(-\Lambda t)]\\&+i(\lambda/\Lambda)[1-\exp(-\Lambda t)]\qquad[5]\end{aligned}$$

The Brownian oscillator model attributes fluctuations of the transition frequencies to coupling between electronic states and an ensemble of low-frequency bath motions. In eqn [5]; λ is the solvent reorganization energy (half the Stokes' shift) and Λ is the modulation frequency of the solvent oscillator (τ_{L}^{-1} for a Debye solvent, where τ_{L} is the longitudinal dielectric relaxation time); k_{B} is the Boltzmann constant, and T_{B} is the temperature.

Information about the kinetics of the evolution of the system initiated by the pump pulse is contained in the terms K^{SE}, K^{ESA}, and K^{GSR}. These terms will be discussed in the next section.

The evolution of the excited state density is mapped onto the response functions R^{SE} and R^{ESA}. R^{SE} is the contribution arising from the probe pulse stimulating emission from the excited state e in the probe direction, which increases the probe intensity. Thus the spectrum of the signal arising from R^{SE} resembles the fluorescence emission of the sample, as shown in Figure 5. The excited state absorption contribution to the signal R^{ESA} depletes the probe intensity, and corresponds to an e → f electronic resonance, such as that shown in Figure 1. Note that the ESA signal contributes to the overall $\Delta I_{\mathrm{pr}}(\omega,T)$ with an opposite sign to the SE and GSR contributions. The ground-state recovery term R^{GSR} arises from depletion of the ground-state population by the pump pulse, thereby increasing the transparency of the sample over the



Figure 5 (a) shows the absorption and emission spectrum of a dilute solution of oxazine-1 in water. (b) shows the transient absorption spectrum of this system at various delays after pumping at 600 nm using picosecond pulses. The transient spectrum, ground state recovery and stimulated emission resemble the sum of the absorption and emission spectra.

spectrum of the ground-state absorption (see Figure 5). Thus the transmitted probe intensity is increased relative to that without the pump pulse. The GSR contribution to $\Delta I_{\text{pr}}(\omega, T)$ decreases with T according to the excited state lifetime of the photoexcited species.

The Coherent Spike

To calculate the pump-probe signal over delay times that are of the order of the pulse duration, one must calculate all possible ways that a signal can be generated with respect to all possible time orderings of the two pump interactions and the probe interactions (Liouville space pathways). Such a calculation reveals coherent as well as sequential contributions to the response of the system owing to the entanglement of time orderings that arise from the overlap of pulses of finite duration. The nonclassical, coherent, contributions dominate the signal for the time period during which pump and probe pulses overlap, leading to the coherent spike (or coherent 'artifact') (Figure 6).



Figure 6 A schematic depiction of a pump-probe signal. The coherent spike is labeled 1. In region 2 we can see quantum beats as a sum of sinusoidal modulations of the signal. The label 3 denotes the long time decay of the signal, as determined by the population dynamics, K^{SE}, K^{GSR}, and K^{ESA}.

Nuclear Wavepackets

The electronic absorption spectrum represents a sum over all possible vibronic transitions, each weighted by a corresponding nuclear overlap factor according to the Franck–Condon principle. It was recognized by Heller and co-workers that in the time-domain representation of the electronic absorption spectrum, the sum over vibrational overlaps is replaced by the propagation of an initially excited nuclear wavepacket on the excited state according to $|i(t)\rangle = \exp(-Ht/\hbar)\,|i(0)\rangle$. Thus the absorption spectrum is written as

$$\sigma_i(\omega) = \frac{2\pi\omega}{3c}\int_{-\infty}^{\infty} \mathrm{d}t \exp[-i(\omega - \omega_{eg}^{i})t - g(t)] \times \langle i(0)\,|i(t)\rangle \qquad [6]$$

for mode i. The Hamiltonian H is determined by the displacement of mode i, Δ_i. A large displacement results in a strong coupling between the vibration and the electronic transition from state g to e. In the frequency domain this is seen as an intense vibronic progression. In the time domain this translates to an oscillation in the time-dependent overlap $\langle i(0)\,|i(t)\rangle$, with frequency ω_i, thereby modulating the intensity of the linear response as a function of t.

It follows that an impulsively excited coherent superposition of vibrational modes, created by an optical pulse that is much shorter than the vibrational period of each mode, propagates on the excited state as a wavepacket. The oscillations of this wavepacket then modulate the intensity of the transmitted probe pulse as a function of T to introduce features into the pump-probe signal known as quantum beats (see Figure 6). In fact, nuclear wavepackets propagate on both the ground and excited states in a pump-probe experiment. The short probe pulse interrogates the evolution of the nuclear wavepackets by projecting them onto the manifold of vibrational wavefunctions in an excited or ground state.

Femtosecond Kinetics

According to eqn [4] the kinetics of the evolution of the system initiated by the pump pulse are governed by the terms K^{SE}, K^{ESA}, and K^{GSR}. Each of these terms describes the kinetics of decay, production, or recovery of excited state and ground state populations. In the simplest conceivable case, each might be a single exponential function. The stimulated emission term K^{SE} contains information about the depopulation of the initially excited state, which for example, may occur through a chemical reaction involving the excited state species or energy transfer from that state. The excited state absorption term K^{ESA} contains information on the formation and decay of all excited state populations that give a transient absorption signal. The ground-state recovery term K^{GSR} contains information on the time-scales for return of all population to the ground state, which will occur by radiative and nonradiative processes. Usually the kinetics are assumed to follow a multi-exponential law such that

$$K^{m}(T, \lambda_{exc}, \omega) = \sum_{j=1}^{N} A_j(\lambda_{exc}, \omega) \exp(-t/\tau_j) \qquad [7]$$

where the amplitude A_j, but not the decay time coefficient τ_j, of each contribution in the coupled N-component system depends on the excitation wavelength λ_{exc} and the signal frequency ω. The index m denotes SE, ESA, or GSR.

In order to extract meaningful physical parameters from analysis of pump-probe data, a kinetic scheme in the form of eqn [7] needs to be constructed, based on a physical model to connect the decay of initially excited state population to formation of a product excited state and subsequent recovery of the ground-state population. An example of such a model is depicted in Figure 7. Here the stimulated emission contribution to the signal is attenuated according to the rate that state 1 goes to 2. The transient absorption appears at that same rate and decays according to the radiationless process 2 to 3. The rate of ground state recovery depends on 1 to 2 to 3 to 5 and possibly pathways involving the isomer 4.

The kinetic scheme is not easily extracted from pump-probe data because contributions from each of K^{SE}, K^{ESA}, and K^{GSR} contribute additively at each detection wavelength ω, as shown in eqns [2]–[4]. Moreover, additional, wavelength-dependent, decay or rise components may appear in the data on ultrafast time-scales owing to the time-dependent Stokes' shift (the $g''(t)$ terms indicated in eqns [4]). A spectral shift can resemble either a decay or rise component. In addition, the very fastest dynamics may be hidden beneath the coherent spike. For these reasons, simple fitting of pump-probe data usually cannot reveal the underlying kinetic model. Instead the data should be simulated according to eqns [3] and [4].



Figure 7 Free energy curves corresponding to a model for an excited state isomerization reaction, with various contributions to a pump-probe measurement indicated. See text for a description. (Courtesy of Jordanides XJ and Fleming GR.)

Alternative strategies involve global analysis of wavelength-resolved data to extract the kinetic evolution of spectral features, known as 'species associated decay spectra'. Global analysis of data effectively reduces the number of adjustable parameters in the fitting procedure and allows one to obtain physically meaningful information by associating species with their spectra. These methods are described in detail by Holzwarth.

List of Units and Nomenclature

ESA	excited state absorption
GSR	ground state recovery
SE	stimulated emission
S_n	nth singlet excited state
TR^3	time-resolved resonance Raman
$\chi^{(3)}$	nth-order nonlinear optical susceptibility

See also

Coherent Lightwave Systems. **Coherent Transients:** Ultrafast Studies of Semiconductors. **Nonlinear Optics, Applications:** Raman Lasers. **Optical Amplifiers:** Raman, Brillouin and Parametric Amplifiers. **Scattering:** Raman Scattering. **Spectroscopy:** Raman Spectroscopy.

Further Reading

Fleming GR (1986) *Chemical Applications of Ultrafast Spectroscopy*. New York: Oxford University Press.

Heller EJ (1981) The semi-classical way to molecular spectroscopy. *Accounts of Chemical Research* 14: 368–375.

Holzwarth AR (1996) Data analysis of time-resolved measurements. In: Amesz J and Hoff AJ (eds) *Biophysical Techniques in Photosynthesis*, pp. 75–92. Dordrecht, Germany: Kluwer.

Ippen EP, Shank CV, Wiensenfeld JM and Migus A (1980) Subpicosecond pulse techniques. *Philosophical Transactions of the Royal Society of London A* 298: 225–232.

Jonas DM and Fleming GR (1995) Vibrationally abrupt pulses in pump-probe spectroscopy. In: El-Sayed MA, Tanaka I and Molin Y (eds) *Ultrafast Processes in Chemistry and Photobiology*, pp. 225–256. Oxford, UK: Blackwell Scientific.

Klimov VI and McBranch DW (1998) Femtosecond high-sensitivity, chirp-free transient absorption spectroscopy using kilohertz lasers. *Optics Letters* 23: 277–279.

Lee SY (1995) Wave-packet model of dynamic dispersed and integrated pump-probe signals in femtosecond transition-state spectroscopy. In: Manz J and Wöste L (eds) *Femtosecond Chemistry*, vol. 1, pp. 273–298. Weinheim, Germany: VCH.

Lin SH, Alden R, Islampour R, Ma H and Villaeys AA (1991) *Density Matrix Method and Femtosecond Processes*. Singapore: World Scientific.

Mukamel S (1995) *Principles of Nonlinear Optical Spectroscopy*. New York: Oxford University Press.

Norrish RGW and Porter G (1949) Chemical reactions produced by very high light intensities. *Nature* 164: 658.

Towrie M, Parker AW, Shaikh W and Matousek P (1998) Tunable picosecond optical parametric generator-amplifier system for time resolved Raman spectroscopy. *Measurement Science and Technology* 9: 816–823.

Yan YJ and Mukamel S (1990) Femtosecond pump-probe spectroscopy of polyatomic molecules in condensed phases. *Physical Reviews A* 41: 6485–6504.

Time-Correlated Single-Photon Counting

A Beeby, University of Durham, Durham, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Time-correlated single-photon counting, TCSPC, is a well-established technique for the determination of fluorescence lifetimes and related time-resolved fluorescence properties. Since the 1980s, there have been dramatic changes in the laser sources used for this work, which in turn have opened up the technique to a wide user base.

TCSPC: The Basics

In the TCSPC experiment, the sample is repeatedly excited by a high-repetition rate, low-intensity light source. Fluorescence from the sample is collected and may be passed though a cut-off filter or monochromator to remove scattered excitation light and to select the emission wavelength. The fluorescence is then focused onto a detector, typically a photomultiplier (PMT) or single-photon avalanche diode (SPAD) which detects single emitted photons. The 'raw' signal from the detector fluctuates considerably from event to event. In order to remove any timing error that could be induced by this, the signal is processed first by a constant fraction discriminator (CFD) in order to provide a stable and consistent timing pulse. This signal is used as an input for the time-to-amplitude converter (TAC) which determines the time interval between the excitation of the sample and the emission of the photon. The output from the TAC is a relatively slow pulse whose intensity is proportional to the time interval between the start and stop signals. A pulse height analyzer (PHA) is used to process the output from the TAC and increments a channel in its memory corresponding to a time window during which the photon was detected. As the measurement is repeated many times over, a histogram is constructed in the memory of the PHA, showing the number of photons detected as a function of the time interval. This histogram corresponds to the fluorescence decay.

As outlined below, it is desirable to have a light source with a moderately high repetition rate, typically of the order of MHz. Because it is not practical to start the TAC each time the light source 'fires', it is more usual to operate the TAC in the so-called 'reversed mode', whereby the start signal is derived from the detected photon and the stop is derived from the light source. The electronic circuitry is illustrated in Figure 1. In practice, many researchers still use modular components that are wired together manually, although there is increasingly a tendency towards the use of single PC-based cards which contain all the necessary discriminators, timing circuits, and data acquisition electronics. There are a number of commercial PC cards that contain all the timing electronics, etc., required for TCSPC, for example, Becker and Hickl (Germany).

This approach to obtaining the fluorescence decay profile can only work if the detected photons are 'randomly selected' from the total emission from the sample. In practice, this means that the rate of detection of photons should be of the order of 1% of the excitation rate: that is, only one in a hundred excitation pulses gives rise to a detected photon. This histogram mirrors the fluorescence decay of the sample convolved with the instrument response function (IRF). The IRF is itself a convolution of the temporal response of the optical light pulse, the optical path in the collection optics, and the response of the detector and ancillary electronics. Experimentally, the IRF is usually recorded by placing a scattering material in the spectrometer.


Sample
Pulsed light source
L_1
Synchronization pulse
PMT
Time to amplitude converter, TAC
Stop
Start
Out
Pulse height analyzer, PHA
Constant fraction discriminator, CFD

Figure 1 Schematic diagram of a TSCPC spectrometer. Fluorescence from the sample is collected by L_1, which may also include a monochromator/wavelength selection filter. A synchronization pulse is obtained either from the laser driver electronics directly, or via a photodiode and second constant fraction discriminator. The TAC is shown operating in a 'reversed mode' as is normal with a high repetition rate laser source.

In principle, the decay function of the sample can be extracted by deconvolution of the IRF from the decay function, although in practice it is more common to use the method of iterative re-convolution using a model decay function(s). Thus, the experimentally determined IRF is convolved with a model decay function and parameters within the function are systematically varied to obtain the best fit for a specific model. The most commonly used model assumes the decaying species to follow one or more exponential functions (sum of exponentials) or a distribution of exponentials. Further details regarding the mechanics of data analysis and fitting procedures can be found in the literature. A typical fit is illustrated in Figure 2.

The main aim of this review is to illustrate how recent advances in laser technology have changed the face of TCSPC and to discuss the types of laser light sources that are in use. The easiest way of approaching this topic is to define the criteria for an ideal light source for this experiment, and then to discuss the ways in which new technologies are meeting these criteria.

High Repetition Rate

A typical decay data set may contain something of the order of 0.1–5 million 'counts': it is desirable to



Figure 2 The fluorescence decay of Rhodamine B in water. The sample was excited using a 397 nm pulsed laser diode (1 MHz, <200 ps FWHM), and the emission was observed at 575 nm. Deconvolution of the IRF (dark gray trace) and observed decay (light gray trace) with a single exponential function gave a lifetime of 1.50 ns, with a $\chi^2R = 1.07$, Durbin–Watson parameter = 1.78. The fitted curve is shown overlaid in gray, and the weighted residuals are shown offset in black.

acquire such a number of events in order that we can reliably employ statistical parameters to judge the quality of the fitted decay function(s). As stated above, the rate of photon acquisition should be of the order of 1% of the excitation rate in order to obtain reliable, good-quality data. It is clear then that a high repetition rate source is desirable in order to reduce the overall data acquisition time. However, it is important that the repetition rate of the source is not too high, otherwise the data show 'overlap' effects, caused by the fluorescence intensity from one excitation pulse not completely decaying before the next laser pulse arrives at the sample. Under these conditions the observed fluorescence decay is perturbed and extraction of complex kinetic behavior is more difficult. As a general rule of thumb, it is recommended that the inter-pulse separation is greater than five times the lifetime of the longest component of the fluorescence decay. Fluorescence lifetimes can be as long as 100 ns, indicating a maximum repetition rate of 2 MHz, although when investigating fluorophores with a shorter lifetime correspondingly higher frequencies can be selected. Clearly the ability to vary the repetition rate according to the type of sample under investigation is an advantage.

Short Pulse Duration

Typically the minimum lifetime that can be determined by a TCSPC spectrometer is limited by the instrument response function: as a general rule it is possible to extract fluorescence lifetimes of about one tenth of the full width at half maximum (FWHM) of the IRF by reconvolution methods. As discussed above, the IRF is the product of a number of factors, including the optical pulse duration, differences in the optical path traversed by the fluorescence, the response time of the detector, and the temporal response of the associated timing electronics. Ideally the excitation source should be as short as possible, and with modern laser-based TCSPC systems, it is usually the case that the time-response of the detector is the limiting factor. The introduction of high-speed microchannel plate (MCP) photomultipliers have lead to very short IRFs, which can be <50 ps FWHM. When using these detectors is it essential to keep the optical transit-time spread as low as possible: that is, the path taken by light through a monochromator should be independent of wavelength and trajectory taken through the optics. Many research groups advocate the use of a subtractive dispersive double monochromator for this purpose.

Tunability

Early TCSPC experiments were carried out using hydrogen- or nitrogen-filled flashlamps which produced broadband ns-duration pulses with low repetition rates (<100 kHz). Variable wavelength excitation is possible using these sources, but their low intensity and low repetition rates mean that data acquisition periods can be very long. The early 1980s saw the introduction of cavity-dumped ion lasers and synchronously pumped mode-locked cavity-dumped dye lasers, which provided significantly higher repetition rates, typically up to 4 MHz, and greater intensities. However, the TCSPC experiments that could be carried out using these laser-based sources were somewhat limited by the wavelengths that could be generated by the argon ion and synchronously pumped dye lasers, and their second harmonics. The dye lasers were restricted to the use of Rhodamine 6G as the gain medium, which has a limited tuning range (~580–620 nm). It is often desirable to vary the excitation wavelength as part of a photophysical study, either as a systematic study of the effects of excitation energy upon the excited state behavior, or in order to optimize excitation of a particular chromophore in a system. To some extent in the past, the wavelengths available from the laser systems dictated the science that they could be used to address. The mid- to late-1980s saw the introduction of mode-locked continuous wave (CW) Nd:YAG lasers as pump lasers and increased number of dyes that could be synchronously pumped, providing a broader range of excitation wavelengths as well as increased stability. One drawback of these complex and often fickle laser systems was the level of expertise and attention they required to keep their performance at its peak.

Since the 1990s, the introduction of two important new types of laser have had a significant impact on the use of TCSPC as an investigative method. The first is based upon the mode-locked titanium sapphire laser which offers tuneable radiation from the deep UV to the NIR, whilst the second series of laser are based upon (relatively) low-cost, turn-key solid state diode lasers. The developments and merits of these new laser sources, which now dominate the market for TCSPC sources, are discussed below.

Ti-Sapphire

The discovery of the titanium doped sapphire laser has led to a revolution in ultrafast laser sources. Coupled with efficient diode-pumped solid state

Nd:YAG pump lasers, this medium currently dominates the entire ultrafast laser market, from high repetition, low pulse energy systems through to systems generating very high pulse energies at kHz repetition rates.

Ti-sapphire is, in many respects, an ideal laser gain medium: it has a high energy storage capacity, it has a very broad-gain bandwidth, and it has good thermal properties. Following the first demonstration of laser action in a Ti-sapphire crystal, the CW Ti-sapphire laser was quickly commercialized. It proved to be a remarkable new laser medium, providing greater efficiency, with outputs of the order of 1 W. The laser also provided an unprecedented broad tuning range, spanning from just below 700 nm to 1000 nm. The most important breakthrough for time-resolved users came in 1991, when self-mode-locking in the medium was demonstrated. This self-mode-locking, sometimes referred to as Kerr-lens mode-locking, arises from the nonlinear refractive index of the material and is implemented by simply placing an aperture within the cavity at an appropriate point. The broad-gain bandwidth of the medium results in very short pulses: pulse durations of the order of tens of femtoseconds can be routinely achieved with commercial laser systems.

The mode-locked Ti-sapphire laser was quickly seized upon and commercialized. The first generation of systems used multiwatt CW argon ion lasers to pump them, making the systems unwieldy and expensive to run, but in recent years these have been replaced by diode-pumped Nd:YAG lasers, providing an all solid-state, ultrafast laser source. Equally significantly, the current generation of lasers are very efficient and do not require significant electrical power or cooling capacity. There are several commercial suppliers of pulsed Ti-sapphire lasers, including Coherent and Spectra Physics.

A typical mode-locked Ti-sapphire laser provides an 80 MHz train of pulses with a FWHM of ~100 fs, with an average power of up to 1.5 W and are tuneable from 700 nm to almost 1000 nm. The relatively high peak powers associated with these pulses means that second- or even third-harmonic generation is relatively efficient, providing radiation in the ranges 350–480 nm and 240–320 nm. The output powers of the second and third harmonics far exceeds that required for TCSPC experiments, making them an attractive source for the study of fluorescence lifetime measurements. The simple mode-locked Ti-sapphire laser has some drawbacks: the very short pulse duration provides a broad-bandwidth excitation, the repetition rate is often too high with an inter-pulse separation of ~12.5 ns, and the laser does not provide continuous tuning from the deep-UV though to the visible. Incrementally, all of these points have been addressed by the laser manufacturers.

As well as operating as a source of femtosecond pulses, with their associated bandwidths of many tens of nm, some modern commercial Ti-sapphire lasers can, by adjustment of the optical path and components, be operated in a mode that provides picosecond pulses whilst retaining their broad tuning curve. Under these conditions, the bandwidth of the output is greatly reduced, making the laser resemble a synchronously pumped mode-locked dye laser.

As stated above, a very high repetition rate can be undesirable if the system under study has a long fluorescence lifetime due to the fluorescence decay from an earlier pulse not decaying completely before the next excitation pulse. Variation of the repetition of output frequency can be addressed by two means. The first is to use a pulse-picker. This is an opto-accoustic device which is placed outside the laser cavity. An electrical signal is applied to a device, synchronized to the frequency of the mode-locked laser to provide pulses at frequencies from ~4 MHz down to single-shot. The operation of a pulse picker is somewhat inefficient, with less than half of the original pulse energy being obtained in the output, although output power is not usually an issue when using these sources. More importantly, when using pulse-pickers, it is essential to ensure that there is no pre- or post-pulse which can lead to artifacts in the observed fluorescence decays. The second means of reducing the pulse duration is cavity dumping. This is achieved by extending the laser cavity and placing an opto-acoustic device, known as a Bragg cell, at a beam-waist within the cavity. When a signal is applied to the intracavity Bragg cell, synchronized with the passage of a mode-locked pulse though the device, a pulse of light is extracted from the cavity. The great advantage of cavity-dumping is that it builds up energy within the optical cavity and when pulses are extracted these are of a higher pulse energy than the mode-locked laser alone. This in turn leads to more efficient harmonic generation. This addition of the cavity dumper system extends the laser cavity and hence reduces the overall frequency of the mode-locked laser to ~50 MHz, and can provide pulses at 9 MHz down to single shot.

The extension of the tuning range of the Ti-sapphire laser has been facilitated by the introduction of the optical parametric oscillator (OPO). In the OPO, a short wavelength pump beam passes through a nonlinear optical crystal and generates two tuneable



Figure 3 An illustration of the spectral coverage provided by currently available pulsed semiconductor lasers and LEDs, and a modern Ti-sapphire laser and OPO. Note that the OPO's output is frequency doubled, and the wavelengths in the range 525– ~ 440 nm may be obtained by sum frequency mixing of the Ti-sapphire's fundamental output with the output of the OPO. * denotes that there are many long wavelength pulsed laser diodes falling in the range $\lambda > 720$ nm.

beams of longer wavelengths. Synchronous pumping of the OPOs with either a fs or ps Ti-sapphire laser ensures reasonably high efficiencies. The outputs from the OPO may be frequency doubled, with the option of intracavity doubling enhancing the efficiency still further. Using an 800 nm pump wavelength, an OPO provides typical signal and idler tuning ranges of 1050–>1350 nm and 2.1–3.0 μm, respectively. The signal can be doubled to give 525–680 nm, effectively filling the visible spectrum. The average powers obtainable from Ti-sapphire pumped OPOs makes them eminently suitable for TCSPC experiments. A summary of the spectral coverage of the Ti-sapphire laser and OPO, and low-cost solid-state sources are illustrated in Figure 3.

An additional advantage of the Ti-sapphire laser is the possibility of multiphoton excitation. The combination of high average power and very short pulse duration of a mode-locked Ti-sapphire laser means that the peak-powers of the pulses can be very high. Focusing the near-IR output of the laser gives rise to exceedingly high photon densities within a sample which can lead to the simultaneous absorption of two or more photons. This is of particular significance when recording fluorescence lifetimes in conjunction with a microscope, particularly when the microscope is operated in a confocal configuration. Such systems are now being used for a derivative of TCSPC, known as fluorescence lifetime imaging (FLM).

In summary, the Ti-sapphire laser is a very versatile and flexible source that is well suited to the TCSPC experiment. Off-the-shelf systems provide broad spectral coverage and variable repetition rates. Undoubtedly this medium will be the mainstay of TCSPC for some time to come.

Diode Lasers

Low-power diode lasers, with outputs in the range 630–1000 nm, have been commercially available for some time. These devices, which are normally operated as CW sources, can be operated in a pulsed mode, providing a high frequency train of sub-ns pulses. However, the relatively long output wavelengths produced by this first generation of diode lasers severely restricted the range of chromophores that could be excited and this proved to be a limiting factor for their use as TCSPC sources. Attempts to generate shorter wavelengths from these NIR laser diodes by second harmonic generation (SHG), were never realized: the SHG process is extremely inefficient due to the very low peak output power of these lasers. Shorter wavelengths could be obtained by pulsing conventional light-emitting diodes (LEDs), which were commercially available with emission wavelengths covering the visible spectrum down to ~450 nm. However, these had the disadvantage of exhibiting longer pulse durations than those achievable from laser diodes and have much broader emission bandwidths than a laser source.

The introduction of violet and blue diode lasers and UV-LEDs by the Nichia Corporation (Japan) in the late 1990s resulted in a renewed interest in sources utilizing these small, solid-state devices. At least three manufacturers produce ranges of commercial TCSPC light sources based upon pulsed LEDs and laser diodes and can now boast a number of pulsed laser sources in their ranges including 375, 400, 450, 473, 635, 670, and 830 nm. Currently commercial pulsed laser diodes and LEDs are manufactured by Jobin-Yvon IBH (UK), Picoquant (Germany), and Hamamatso (Japan). These small, relatively low-cost devices offer pulse durations of <100 ps and excitation repetition rates of up to tens of MHz making them ideally suited to 'routine' lifetime measurements. Although these diode laser sources are not tunable and do not span the full spectrum, they are complemented by pulsed LEDs which fill the gap in the visible spectrum. Pulsed LEDs generally have a longer pulse duration and broader, lower intensity spectral output, but are useful for some applications. At the time of writing there are no diode laser sources providing wavelengths of <350 nm, although Jobin-Yvon IBH (UK) have recently announced pulsed LEDs operating at 280 nm and 340 nm. As LEDs, and possibly diode lasers, emitting at these shorter wavelengths become more widely available, the prospects of low running costs and ease of use makes these semiconductor devices an extremely attractive option for many TCSPC experiments. Commercial TCSPC spectrometers based around these systems offer a comparatively low-cost, turnkey approach to fluorescence lifetime based experiments, opening up what was a highly specialized field to a much broader range of users.

See also

Lasers: Noble Gas Ion Lasers. **Light Emitting Diodes**. **Ultrafast Laser Techniques:** Pulse Characterization Techniques.

Further Reading

Lakowicz JR (ed.) (2001) *Principles of Fluorescence Spectroscopy*. Plenum Press.

O'Connor DV and Phillips D (1984) *Time-Correlated Single Photon Counting*.

Spence DE, Kean PN and Sibbett W (1991) *Optics Letters* 16: 42–44.

Transient Holographic Grating Techniques in Chemical Dynamics

E Vauthey, University of Geneva, Geneva, Switzerland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Over the past two decades, holographic techniques have proved to be valuable tools for investigating the dynamics of chemical processes. The aim of this chapter is to give an overview of the main applications of these techniques for chemical dynamics. The basic principle underlying the formation and the detection of elementary transient holograms, also called transient gratings, is first presented. This is followed by a brief description of a typical experimental setup. The main applications of these techniques to solve chemical problems are then discussed.

Basic Principle

The basic principle of the transient holographic technique is illustrated in Figure 1. The sample material is excited by two laser pulses at the same wavelength and crossed at an angle $2\theta_{pu}$. If the two pump pulses have the same intensity, I_{pu}, the intensity distribution at the interference region, assuming plane waves, is

$$I(x) = 2I_{pu}\left[1 + \cos\left(\frac{2\pi x}{\Lambda}\right)\right] \qquad [1]$$

where $\Lambda = \lambda_{pu}/(2\sin\theta_{pu})$ is the fringe spacing, λ_{pu} is the pump wavelength, and I_{pu} is the intensity of one pump pulse.

As discussed below, there can be many types of light–matter interactions that lead to a change in the optical properties of the material. For a dielectric material, they result in a spatial modulation of the optical susceptibility and thus of the complex refractive index, $\tilde{n}$. The latter distribution can be described as a Fourier cosine series:

$$\tilde{n}(x) = \tilde{n}_0 + \sum_{m=1}^{\infty} \tilde{n}_m \cos\left(\frac{m2\pi x}{\Lambda}\right) \qquad [2]$$

where $\tilde{n}_0$ is the average value of $\tilde{n}$. In the absence of saturation effects, the spatial modulation of $\tilde{n}$ is harmonic and the Fourier coefficients with $m > 1$ vanish. In this case, the peak to null variation of the complex refractive index, $\Delta\tilde{n}$, is equal to the Fourier coefficient $\tilde{n}_1$. The complex refractive index can be split into its real and imaginary components:

$$\tilde{n} = n + iK \qquad [3]$$

where n is the refractive index and K is the attenuation constant.

The hologram created by the interaction of the crossed pump pulses consists in periodic, one-dimensional spatial modulations of n and K. Such distributions are nothing but phase and amplitude gratings, respectively. A third laser beam at the probe wavelength, λ_{pr}, striking these gratings at Bragg angle, $\theta_B = \arcsin(\lambda_{pr}/2\Lambda)$, will thus be partially diffracted (Figure 1b). The diffraction efficiency, η, depends on the modulation amplitude of the optical properties. In the limit of small diffraction efficiency ($\eta < 0.01$), this relationship is given by

$$\eta = \frac{I_{dif}}{I_{pr}} \cong \left[\left(\frac{\ln 10\Delta A}{4\cos\theta_B}\right)^2 + \left(\frac{\pi d\Delta n}{\lambda_{pr}\cos\theta_B}\right)^2\right] \times \exp\left(-\frac{\ln 10A}{\cos\theta_B}\right) \qquad [4]$$

where I_{dif} and I_{pr} are the diffracted and the probe intensity respectively, d is the sample thickness, and $A = 4\pi dK/(\lambda \ln 10)$ is the average absorbance.

The first and the second terms in the square bracket describe the contribution of the amplitude and phase gratings respectively, and the exponential term accounts for the reabsorption of the diffracted beam by the sample.

The main processes responsible for the variation of the optical properties of an isotropic dielectric material are summarized in Figure 2.

The modulation of the absorbance, ΔA, is essentially due to the photoinduced concentration change,


Pump
pulse1
x
Λ
Fringe
spacing
θ_pu
Pump
pulse 2
Sample
(a)
θ_B
Probe
pulse (I_pr)
Transmitted
pulse
Diffracted
pulse (I_dif)
(b)

Figure 1 Principle of the transient grating technique: (a) grating formation (pumping), (b) grating detection (probing).


Δñ
Δn
Phase grating
ΔA
Amplitude grating
population changes
Δn_K
Optical Kerr effect
Δn_d
Density changes
Δn_p
Population changes
Δn_K^n
Nuclear
Δn_K^e
Electronic
Δn_d^e
Electrostriction
Δn_d^T
Thermal
expansion
Δn_d^v
Volume
changes
Nonresonant interactions

Figure 2 Classification of the possible contributions to a transient grating signal.

ΔC, of the different chemical species i (excited state, photoproduct, …):

$$\Delta A(\lambda_{pr}) = \sum_i \varepsilon_i(\lambda_{pr})\Delta C_i \qquad [5]$$

where ε_i is the absorption coefficient of the species i.

The variation of the refractive index, Δn, has several origins and can be expressed as

$$\Delta n = \Delta n_K + \Delta n_p + \Delta n_d \qquad [6]$$

Δn_K is the variation of refractive index due to the optical Kerr effect (OKE). This nonresonant interaction results in an electronic polarization (electronic OKE) and/or in a nuclear reorientation of the molecules (nuclear OKE) along the direction of the electric field associated with the pump pulses. As a consequence, a transient birefringence is created in the material. This effect is usually discussed within the framework of nonlinear optics in terms of intensity dependent refractive index or third order nonlinear susceptibility. Electronic OKE occurs in any dielectric material under sufficiently high light intensity. On the other hand, nuclear OKE is mostly observed in liquids and gases and depends strongly on the molecular shape.

Δn_p is the change of refractive index related to population changes. Its magnitude and wavelength dependence can be obtained by Kramers–Kronig transformation of $\Delta A(\lambda)$ or $\Delta K(\lambda)$:

$$\Delta n_p(\lambda) = \frac{1}{2\pi^2}\int_0^\infty \frac{\Delta K(\lambda')}{1-(\lambda'/\lambda)^2}\,\mathrm{d}\lambda' \qquad [7]$$

Δn_d is the change of refractive index associated with density changes. Density phase gratings can have essentially three origins:

$$\Delta n_d = \Delta n_d^t + \Delta n_d^v + \Delta n_d^e \qquad [8]$$

Δn_d^t is related to the temperature-induced change of density. If a fraction of the excitation energy is converted into heat, through a nonradiative transition or an exothermic process, the temperature becomes spatially modulated. This results in a variation of density, hence to a modulation of refractive index with amplitude Δn_d^t. Most of the temperature dependence of n originates from the density. The temperature-induced variation of n at constant density is much smaller than Δn_d^t.

Δn_d^v is related to the variation of volume upon population changes. This volume comprises not only the reactant and product molecules but also their environment. For example, in the case of a photodissociation, the volume of the product is larger than that of the reactant and a positive volume change can be expected. This will lead to a decrease of the density and to a negative Δn_d^v.

Finally, Δn_d^e is related to electrostriction in the sample by the electric field of the pump pulses. Like OKE, this is a nonresonant process that also contributes to the intensity dependent refractive index. Electrostriction leads to material compression in the regions of high electric field strength. The periodic compression is accompanied by the generation of two counterpropagating acoustic waves with wave vectors, $\vec{k}_{ac} = \pm(2\pi/\Lambda)\vec{i}$, where $\vec{i}$ is the unit vector along the modulation axis. The interference of these acoustic waves leads to a temporal modulation of Δn_d^e at the acoustic frequency ν_{ac}, with $2\pi\nu_{ac} = k_{ac}\nu_s$, ν_s being the speed of sound. As Δn_d^e oscillates between negative and positive values, the diffracted intensity, which is proportional to $(\Delta n_d^e)^2$, shows at temporal oscillation at twice the acoustic frequency. In most cases, Δn_d^e is weak and can be neglected if the pump pulses are within an absorption band of the sample.

The modulation amplitudes of absorbance and refractive index are not constant in time and their temporal behavior depends on various dynamic processes in the sample. The whole point of the transient grating techniques is precisely the measurement of the diffracted intensity as a function of time after excitation to deduce dynamic information on the system.

In the following, we will show that the various processes shown in Figure 2, that give rise to a diffracted signal, can in principle be separated by choosing appropriate experimental parameters, such as the timescale, the probe wavelength, the polarization of the four beams, or the crossing angle.

Experimental Setup

A typical experimental arrangement for pump–probe transient grating measurements is shown in Figure 3. The laser output pulses are split in three parts. Two parts of equal intensity are used as



Figure 3 Schematic of a transient grating setup with pump–probe detection.



Figure 4 Beam geometry for transient grating: (a) in plane; (b) boxcars.

pump pulses and are crossed in the sample. In order to ensure time coincidence, one pump pulse travels along an adjustable optical delay line. The third part, which is used for probing, can be frequency converted using a dye laser, a nonlinear crystal, a Raman shifter, or white light continuum generation. The probe pulse is sent along a motorized optical delay line before striking the sample at the Bragg angle. There are several possible beam configurations for transient grating and the two most used are illustrated in Figure 4. When the probe and pump pulses are at different wavelengths, they can be in the same plane of incidence as shown in Figure 4a. However, if the pump and probe wavelengths are the same, the folded boxcars geometry shown in Figure 4b has to be used. The transient grating technique is background free and the diffracted signal propagates in a well-defined direction. In a pump–probe experiment, the diffracted signal intensity is measured as a function of the time delay between the pump and probe pulses. Such a setup can be used to probe dynamic processes occurring in timescales going from a few fs to a few ns, the time resolution depending essentially on the duration of the pump and probe pulses. For slower processes, the grating dynamics can be probed in real time with a *cw* laser beam and a fast photodetector.

Applications

The Transient Density Phase Grating Technique

If the grating is probed at a wavelength far from any absorption band, the variation of absorbance, $\Delta A(\lambda_{pr})$, is zero and the corresponding change of refractive index, $\Delta n_p(\lambda_{pr})$, is negligibly small. In this case, eqn [4] simplifies to

$$\eta \cong \left(\frac{\pi d}{\lambda_{pr}\cos\theta_B}\right)^2 \times \Delta n_d^2 \qquad [9]$$

In principle, the diffracted signal may also contain contributions from the optical Kerr effect, Δn_K, but we will assume here that this non-resonant and ultrafast response is negligibly small. The density change can originate from both heat releasing processes and volume differences between the products and reactants, the former contribution usually being much larger than the latter. Even if the heat releasing process is instantaneous, the risetime of the density grating is limited by thermal expansion. This expansion is accompanied by the generation of two counterpropagating acoustic waves with wave vectors, $\vec{k}_{ac} = \pm(2\pi/\Lambda)\vec{i}$. One can distinguish two density gratings: 1) a diffusive density grating, which reproduces the spatial distribution of temperature and which decays by thermal diffusion; and 2) an acoustic density grating originating from the standing acoustic wave and whose amplitude oscillates at the acoustic frequency ν_{ac}.

The amplitudes of these two gratings are equal but of opposite sign. Consequently, the time dependence of the modulation amplitude of the density phase grating is given by

$$\Delta n_d(t) = \left(\frac{\beta Q}{\rho C_v} + \Delta V\right)\rho\left(\frac{\partial n}{\partial \rho}\right)R(t) \qquad [10a]$$

with

$$R(t) = 1 - \cos(2\pi\nu_{ac}t) \times \exp(-\alpha_{ac}\nu_s t) \qquad [10b]$$

where ρ, β, C_v, and α_{ac} are the density, the volume expansion coefficient, the heat capacity, and the acoustic attenuation constant of the medium, respectively, Q is the amount of heat deposited during the photoinduced process, and ΔV is the corresponding volume change. As the standing acoustic wave oscillates, its corresponding density grating interferes with the diffusive density grating. Therefore, the total modulation amplitude of the density and thus Δn_d exhibits the oscillation at ν_{ac}. Figure 5 shows the time profile of the diffracted



Figure 5 Time profile of the diffracted intensity measured with a solution of malachite green after excitation with two pulses with close to counterpropagating geometry.

intensity measured with a solution of malachite green. After excitation to the S_1 state, this dye relaxes nonradiatively to the ground state in a few ps. For this measurement, the sample solution was excited with two 30 ps laser pulses at 532 nm crossed with an angle close to 180°. The continuous line is the best fit of eqns [9] and [10]. The damping of the oscillation is due to acoustic attenuation. After complete damping, the remaining diffracted signal is due to the diffusive density grating only.

$R(t)$ can be considered as the response function of the sample to a prompt heat release and/or volume change. If these processes are not instantaneous compared to an acoustic period ($\tau_{ac} = \nu_{ac}^{-1}$), the acoustic waves are not created impulsively and the time dependence of Δn_d is

$$\Delta n_d(t) = \left(\frac{\beta Q}{\rho C_v} + \Delta V\right)\rho\left(\frac{\partial n}{\partial \rho}\right)F(t) \qquad [11a]$$

with

$$F(t) = \int_{-\infty}^{t} R(t - t')\cdot f(t')\mathrm{d}t' \qquad [11b]$$

where $f(t)$ is a normalized function describing the time evolution of the temperature and/or volume change. In many cases, $f(t) = \exp(-k_r t)$, k_r being the rate constant of the process responsible for the change. Figure 6 shows the time profile of the diffracted intensity calculated with eqns [9] and [11] for different values of k_r.

If several processes take place, the total change of refractive index is the sum of the changes due to the individual processes. In this case, Δn_d should be expressed as

$$\Delta n_d(t) = \sum_i \left(\frac{\beta Q_i}{\rho C_v} + \Delta V_i\right)\rho\left(\frac{\partial n}{\partial \rho}\right)F_i(t) \qquad [12]$$



Figure 6 Time profiles of the diffracted intensity calculated using eqns [9] and [11] with various k_r values.

The separation of the thermal and volume contributions to the diffracted signal is problematic. Several approaches have been proposed, the most used being the measurement in a series of solvents with different expansion coefficient β. This method requires that the other solvent properties like refractive index, dielectric constant, or viscosity, are constant or that the energetics of the system investigated does not depend on them. This separation is easier when working with water because its β value vanishes at 4 °C. At this temperature, the density variations are due to the volume changes only.

The above equations describe the growth of the density phase grating. However, this grating is not permanent and decays through diffusive processes. The phase grating originating from thermal expansion decays via thermal diffusion with a rate constant k_{th} given by

$$k_{th} = D_{th}\left(\frac{2\pi}{\Lambda}\right)^2 \qquad [13]$$

where D_{th} is the thermal diffusivity. Table 1 shows k_{th} values in acetonitrile for different crossing angles.

The decay of the phase grating originating from volume changes depends on the dynamics of the population responsible for ΔV (vide infra).

Time resolved optical calorimetry

A major application of the density phase grating in chemistry is the investigation of the energetics of photo-induced processes. The great advantage of this technique over other optical calorimetric methods, like the thermal lens or the photoacoustic spectroscopy, is its superior time resolution. The time constant of the fastest heat releasing process that can be time resolved with this technique is of the order of the acoustic period. The shortest acoustic period is achieved when forming the grating with two counterpropagating pump pulses ($2\theta_{pu} = 180°$). In this case the fringe spacing is

Table 1 Fringe spacing, Λ, acoustic frequency, ν_{ac}, thermal diffusion rate constant, k_{tr}, for various crossing angles of the pump pulses, 2 θ_{pu}, at 355 nm and in acetonitrile

$2\ \theta_{pu}$	Λ (μm)	$\nu_{ac}(s^{-1})$	$k_{th}\ (s^{-1})$
0.5°	40.7	3.2×10^7	4.7×10^3
50°	0.42	3.1×10^9	4.5×10^7
180°	0.13	9.7×10^9	4.7×10^8

$\Lambda = \lambda_{pu}/2n$ and, with UV pump pulses, an acoustic period of the order of 100 ps can be obtained in a typical organic solvent.

For example, Figure 7a shows the energy diagram for a photoinduced electron transfer (ET) reaction between benzophenone (BP) and an electron donor (D) in a polar solvent. Upon excitation at 355 nm, $^1BP^*$ undergoes intersystem-crossing (ISC) to $^3BP^*$ with a time constant of about 10 ps.



Figure 7 (a) Energy diagram of the states involved in the photoinduced electron transfer reaction between benzophenone (BP) and an electron donor (D) (VR: vibrational relaxation, ISC: intersystem crossing; ET: electron transfer; REC: charge recombination). (b) Time profile of the diffracted intensity measured at 590 nm after excitation at 355 nm of a solution of BP and 0.05 M D. (c) Same as (b) but measured at 1064 nm with a *cw* laser.

After diffusional encounter with the electron donor, ET takes place and a pair of ions is generated. With this system, the whole energy of the 355 nm photon ($E = 3.49$ eV) is converted into heat. The different heat releasing processes can be differentiated according to their timescale. The vibrational relaxation to $^1BP^*$ and the ensuing ISC to $^3BP^*$ induces an ultrafast release of 0.49 eV as heat. With donor concentrations of the order of 0.1 M, the heat deposition process due to the electron transfer is typically in the ns range. Finally, the recombination of the ions produces a heat release in the microsecond timescale. Figure 7b shows the time profile of the diffracted intensity measured after excitation at 355 nm of BP with 0.05 M D in acetonitrile. The 30 ps pump pulses were crossed at 27° ($\tau_{ac} = 565$ ps) and the 10 ps probe pulses were at 590 nm. The oscillatory behavior is due to the ultrafast heat released upon formation of $^3BP^*$, while the slow dc rise is caused by the heat dissipated upon ET. As the amount of energy released in the ultrafast process is known, the energy released upon ET can be determined by comparing the amplitudes of the fast and slow components of the time profile. The energetics as well as the dynamics of the photoinduced ET process can thus be determined. Figure 7c shows the decay of the diffracted intensity due to the washing out of the grating by thermal diffusion. As both the acoustic frequency and the thermal diffusion depends on the grating wavevector, the experimental time window in which a heat releasing process can be measured, depends mainly on the crossing angle of the pump pulses as shown in Table 1.

Determination of material properties

Another important application of the transient density phase grating technique is the investigation of material properties. Acoustics waves of various frequencies, depending on the pump wavelength and crossing angle, can be generated without physical contact with the sample. Therefore, acoustic properties, such as the speed of sound and the acoustic attenuation of the material, can be easily obtained from the frequency and the damping of the oscillation of the transient grating signal.

Similarly, the optoelastic constant of a material, $\rho \partial n/\partial \rho$, can be determined from the amplitude of the signal (see eqn [11]). This is done by comparing the signal amplitude of the material under investigation with that obtained with a known standard.

Finally, the thermal diffusivity, D_{th}, can be easily obtained from the decay of the thermal density phase grating, such as that shown in Figure 7c. This technique can be used with a large variety of bulk materials as well as films, surfaces and interfaces.

Investigation of Population Dynamics

The dynamic properties of a photogenerated species can be investigated by using a probe wavelength within its absorption or dispersion spectrum. As shown by eqn [4], either ΔA or Δn_p has to be different from zero. For this application, Δn_K and Δn_d should ideally be equal to zero. Unless working with ultrashort pulses (< 1 ps) and a weakly absorbing sample, Δn_K can be neglected. Practically, it is almost impossible to find a sample system for which some fraction of the energy absorbed as light is not released as heat. However, by using a sufficiently small crossing angle of the pump pulses, the formation of the density phase grating, which depends on the acoustic period, can take as much as 30 to 40 ns. In this case, Δn_d is negligible during the first few ns after excitation and the diffracted intensity is due to the population grating only:

$$I_{dif}(t) \propto \sum_i \Delta C_i^2(t) \qquad [14]$$

where ΔC_i is the modulation amplitude of the concentration of every species i whose absorption and/or dispersion spectrum overlaps with the probe wavelength.

The temporal variation of ΔC_i can be due either to the dynamics of the species i in the illuminated grating fringes or to processes taking place between the fringes, such as translational diffusion, excitation transport, and charge diffusion. In liquids, the decay of the population grating by translational diffusion is slow and occurs in the microsecond to millisecond timescale, depending on the fringe spacing. As thermal diffusion is typically hundred times faster, eqn [14] is again valid in this long timescale. Therefore if the population dynamics is very slow, the translational diffusion coefficient of a chemical species can be obtained by measuring the decay of the diffracted intensity as a function of the fringe spacing. This procedure has also been used to determine the temperature of flames. In this case however, the decay of the population grating by translational diffusion occurs typically in the sub-ns timescale.

In the condensed phase, these interfringe processes are of minor importance when measuring the diffracted intensity in the short timescale, i.e., before the formation of the density phase grating. In this case, the transient grating technique is similar to transient absorption, and it thus allows the measurement of population dynamics. However, because holographic detection is background free, it is at least a hundred times more sensitive than transient absorption.

The population gratings are usually probed with monochromatic laser pulses. This procedure is well suited for simple photoinduced processes, such as the decay of an excited state population to the ground state. For example, Figure 8 shows the decay of the diffracted intensity at 532 nm measured after excitation of a cyanine dye at the same wavelength. These dynamics correspond to the ground state recovery of the dye by non-radiative deactivation of the first singlet excited state. Because the diffracted intensity is proportional to the square of the concentration changes (see eqn [14]), its decay time is twice as short as the ground state recovery time. If the reaction is more complex, or if several intermediates are involved, the population grating has to be probed at several wavelengths. Instead of repeating many single wavelength experiments, it is preferable to perform multiplex transient grating. In this case, the grating is probed by white light pulses generated by focusing high intensity fs or ps laser pulses in a dispersive medium. If the crossing angle of the pump pulses is small enough ($< 1°$), the Bragg angle for probing is almost independent on the wavelength. A transient grating spectrum is obtained by dispersing the diffracted signal in a spectrograph. This spectrum consists in the sum of the square of the transient absorption and transient dispersion spectra. Practically, it is very similar to a transient absorption spectrum, but with a much superior signal to noise ratio. Figure 9 shows the transient grating spectra measured at various time delays after excitation of a solution of chloranil (CA) and



Figure 8 Time profile of the diffracted intensity at 532 nm measured after excitation at the same wavelength of a cyanine dye (inset) in solution and best fit assuming exponential ground state recovery.



Figure 9 Transient grating spectra obtained at various time delays after excitation at 355 nm of a solution of chloranil and 0.25 M methylnaphthalene (a): from top to bottom: 60, 100, 180, 260, 330 and 600 ps; (b): from top to bottom: 100, 400, 750, 1100, 1500 ps).

methylnaphthalene (MNA) in acetonitrile. The reaction that takes place is

$$^3\mathrm{CA}^* \cdot \mathrm{MNA} \xrightarrow{\text{diffusion}} (^3\mathrm{CA}^* \cdot \mathrm{MNA}) \xrightarrow{\text{ET}}$$

$$^3(\mathrm{CA}^- \cdot \mathrm{MNA}^+) \xrightarrow{\text{MNA}} {}^3(\mathrm{CA}^- \cdot \mathrm{MNA}^+)$$

After its formation upon ultrafast ISC, $^3\mathrm{CA}^*$, which absorbs around 510 nm, decays upon ET with MNA to generate CA^-(450 nm) and MNA^+ (690 nm). The ion pair reacts further with a second MNA molecule to form the dimer cation (580 nm).

The time profile of the diffracted intensity reflects the population dynamics as long as these populations follow first- or pseudo-first order kinetics. Higher order kinetics leads to inharmonic gratings and in this case the time dependence of the diffracted intensity is no longer a direct measure of the population dynamics.

Polarization Selective Transient Grating

In the above applications, the selection between the different contributions to the diffracted signal was essentially made by choosing the probe wavelength and the crossing angle of the pump pulses. However, this approach is not always sufficient. Another important parameter is the polarization of the four waves involved in a transient grating experiment. For example, when measuring population dynamics, the polarization of the probe beam has to be at magic angle (54.7°) relatively to that of the pump pulses. This ensures that the observed time profiles are not distorted by the decay of the orientational anisotropy of the species created by the polarized pump pulses.

The magnitude of ΔA and Δn depends on the pump pulses intensity, and therefore the diffracted intensity can be expressed by using the formalism of nonlinear optics:

$$I_{dif}(t) = C\int_{-\infty}^{+\infty} \mathrm{d}t\, I_{pr}(t - t'') \times \left[\int_{-\infty}^{t} \mathrm{d}t' |R_{ijkl}(t'' - t')| I_{pu}(t') \right]^2 \qquad [15]$$

where C is a constant and R_{ijkl} is an element of the fourth rank tensor $\mathbf{R}$ describing the nonlinear response of the material to the applied optical fields. In isotropic media, this tensor has only 21 nonzero elements, which are related as follows:

$$R_{1111} = R_{1122} + R_{1212} + R_{1221} \qquad [16]$$

where the subscripts are the Cartesian coordinates. Going from right to left, they design the direction of polarization of the pump, probe, and signal pulses. The remaining elements can be obtained by permutation of these indices ($R_{1122} = R_{1133} = R_{2211} = \ldots$). In a conventional transient grating experiment, the two pump pulses are at the same frequency and are time coincident and therefore their indices can be interchanged. In this case, $R_{1212} = R_{1221}$ and the number of independent tensor elements is further reduced:

$$R_{1111} = R_{1122} + 2R_{1212} \qquad [17]$$

The tensor $\mathbf{R}$ can be decomposed into four tensors according to the origin of the sample response: population and density changes, electronic and nuclear optical Kerr effects:

$$\mathbf{R} = \mathbf{R}(p) + \mathbf{R}(d) + \mathbf{R}(K, e) + \mathbf{R}(K, n) \qquad [18]$$

As they describe different phenomena, these tensors do not have the same symmetry properties. Therefore, the various contributions to the diffracted intensity can, in some cases, be measured selectively by choosing the appropriate polarization of the four waves.

Table 2 shows the relative amplitude of the most important elements of these four tensors.

The tensor $\mathbf{R}(p)$ depends on the polarization anisotropy of the sample, r, created by excitation with polarized pump pulses:

$$r(t) = \frac{N_{\parallel}(t) - N_{\perp}(t)}{N_{\parallel}(t) + 2N_{\perp}(t)} = \frac{2}{5}\mathrm{P}_2[\cos(\gamma)]\exp(-k_{re}t) \qquad [19]$$

where $N_{\parallel}$ and $N_{\perp}$ are the number of molecules with the transition dipole oriented parallel and perpendicular to the polarization of the probe pulse, respectively, γ is the angle between the transition dipoles involved in the pump and probe processes, P_2 is the second Legendre polynomial, and k_{re} is the rate constant for the reorientation of the transition dipole, for example, by rotational diffusion of the molecule or by energy hopping.

The table shows that $R_{1212}(d) = 0$, i.e., the contribution of the density grating can be eliminated with the set of polarization $(0°, 90°, 0°, 90°)$, the so-called crossed grating geometry. In this geometry, the two pump pulses have orthogonal polarization, the polarization of the probe pulse is parallel to that of one pump pulse and the polarization component of the signal that is orthogonal to the polarization of the probe pulse is measured. In this geometry, $R_{1212}(p)$ is nonzero as long as there is some polarization anisotropy, ($r \neq 0$). In this case, the diffracted intensity is

$$I_{dif}(t) \propto |R_{1212}(p)|^2 \propto [\Delta C(t) \times r(t)]^2 \qquad [20]$$

The crossed grating technique can thus be used to investigate the reorientational dynamics of molecules, through $r(t)$, especially when the dynamics of r is faster than that of ΔC. For example, Figure 10 shows the time profile of the diffracted intensity measured in the crossed grating geometry with rhodamine 6G in ethanol. The decay is due to the reorientation of the molecule by rotational diffusion, the excited lifetime of rhodamine being about 4 ns.

On the other hand, if the decay of r is slower than that of ΔC, the crossed grating geometry can be used to measure the population dynamics without any interference from the density phase grating. For example, Figure 11 shows the time profile of the diffracted intensity after excitation of a suspension of $\mathrm{TiO_2}$ particles in water. The upper profile was measured with the set of polarization $(0°, 0°, 0°, 0°)$ and thus reflects the time dependence of $R_{1111}(p)$ and $R_{1111}(d)$. $R_{1111}(p)$ is due to the trapped electron population, which decays by charge recombination, and $R_{1111}(d)$ is due to the heat dissipated upon both charge separation and recombination. The lower time profile was measured in the crossed grating geometry and thus reflects the time dependence of R_{1212} and in particular that of $R_{1212}(p)$.

Each contribution to the signal can be selectively eliminated by using the set of geometry $(\zeta, 45°, 0°, 0°)$ where the value of the 'magic angle' ζ for each

Table 2 Relative value of the most important elements of the response tensors $\mathbf{R}(i)$ and polarization angle ζ of the signal beam, where the contribution of the corresponding process vanishes for the set of polarization $(\zeta, 45°, 0°, 0°)$.

Process	R_{1111}	R_{1122}	R_{1212}	ζ
Electronic OKE	1	1/3	1/3	−71.6°
Nuclear OKE	1	−1/2	3/4	63.4°
Density	1	1	0	−45°
Population:				
$\gamma = 0°$	1	1/3	1/3	−71.6°
$\gamma = 90°$	1	2	−1/2	−26.6°
No correlation: $r = 0$	1	1	0	−45°



Figure 10 Time profile of the diffracted intensity measured with a solution of rhodamine 6G with crossed grating geometry.



Figure 11 Time profiles of the diffracted intensity after excitation at 355 nm of a suspension of $\mathrm{TiO_2}$ particles in water and using different set of polarization of the four beams.

contribution is listed in Table 2. This approach allows for example the nuclear and electronic contributions to the optical Kerr effect to be measured separately.

Concluding Remarks

The transient grating techniques offer a large variety of applications for investigating the dynamics of chemical processes. We have only discussed the cases where the pump pulses are time coincident and at the same wavelength. Excitation with pump pulses at different wavelengths results to a moving grating. The well-known CARS spectroscopy is such a moving grating technique. Finally, the three pulse photon echo can be considered as a special case of transient grating where the sample is excited by two pump pulses, which are at the same wavelength but are not time coincident.

List of Units and Nomenclature

C	concentration [mol L^{-1}]
C_{v}	heat capacity [J K^{-1} kg^{-1}]
d	sample thickness [m]
D_{th}	thermal diffusivity [m^2 s^{-1}]
I_{dif}	diffracted intensity [W m^{-2}]
I_{pr}	intensity of the probe pulse [W m^{-2}]
I_{pu}	intensity of a pump pulse [W m^{-2}]
k_{ac}	acoustic wavevector [m^{-1}]
k_r	rate constant of a heat releasing process [s^{-1}]
k_{re}	rate constant of reorientation [s^{-1}]
k_{th}	rate constant of thermal diffusion [s^{-1}]
K	attenuation constant
n	refractive index
$\tilde{n}$	complex refractive index
N	number of molecule per unit volume [m^{-3}]
r	polarization anisotropy
$\mathbf{R}$	fourth rank response tensor [m^2 V^{-2}]
υ_{s}	speed of sound [m s^{-1}]
V	volume [m^3]
α_{ac}	acoustic attenuation constant [m^{-1}]
β	cubic volume expansion coefficient [K^{-1}]
γ	angle between transition dipoles
Λ	fringe spacing [m]
Δn_d	variation of refractive index due to density changes
Δn_d^e	Δn_d due to electrostriction
Δn_K	variation of refractive index due to optical Kerr effect
Δn_d^p	Δn_d due to volume changes
Δn_p	variation of refractive index due to population changes
Δn_d^t	Δn_d due to temperature changes
Δx	peak to null variation of the parameter x
ε	molar decadic absorption coefficient [cm L mol^{-1}]
ζ	angle of polarization of the diffracted signal
η	diffraction efficiency
θ_B	Bragg angle (angle of incidence of the probe pulse)
θ_{pu}	angle of incidence of a pump pulse
λ_{pr}	probe wavelength [m]
λ_{pu}	pump wavelength [m]
ρ	density [kg m^{-3}]
τ_{ac}	acoustic period [s]
υ_{ac}	acoustic frequency [s^{-1}]

See also

Chemical Applications of Lasers: Nonlinear Spectroscopies; Pump and Probe Studies of Femtosecond Kinetics. **Holography, Applications:** Holographic Recording Materials and their Processing. **Holography, Techniques:** Holographic Interferometry. **Materials Characterization Techniques:** $\chi^{(3)}$. **Nonlinear Optics Basics:** Four-Wave Mixing. **Ultrafast Technology:** Femtosecond Chemical Dynamics, Gas Phase; Femtosecond Condensed Phase Spectroscopy – Structural Dynamics.

Further Reading

Bräuchle C and Burland DM (1983) Holographic methods for the investigation of photochemical and photophysical properties of molecules. *Angewandte Chemie International Edition Engl* 22: 582–598.

Eichler HJ, Günter P and Pohl DW (1986) *Laser-Induced Dynamics Gratings*. Berlin: Springer.

Fleming GR (1986) *Chemical Applications of Ultrafast Spectroscopy*. Oxford: Oxford University Press.

Fourkas JT and Fayer MD (1992) The transient grating: a holographic window to dynamic processes. *Accounts of Chemical Research* 25: 227–233.

Hall G and Whitaker BJ (1994) Laser-induced grating spectroscopy. *Journal of the Chemistry Society Faraday Trans* 90: 1–16.

Levenson MD and Kano SS (1987) *Introduction to Nonlinear Laser Spectroscopy*, revised edn. Boston: Academic Press.

Mukamel S (1995) *Nonlinear Optical Spectroscopy*. Oxford: Oxford University Press.

Rullière C (ed.) (1998) *Femtosecond Laser Pulses*. Berlin: Springer.

Terazima M (1998) Photothermal studies of photophysical and photochemical processes by the transient grating method. *Advances in Photochemistry* 24: 255–338.

cross-sectional area 10^4 times and dispersed the beam across it. The CPA technique makes it possible to use conventional laser amplifiers and to stay below the onset of nonlinear effects.

See also

Diffraction: Diffraction Gratings. **Ultrafast Laser Techniques:** Pulse Characterization Techniques.

COHERENCE

Contents

Overview
Coherence and Imaging
Speckle and Coherence

Overview

A Sharma and A K Ghatak, Indian Institute of Technology, New Delhi, India

H C Kandpal, National Physical Laboratory, New Delhi, India

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Coherence refers to the characteristic of a wave that indicates whether different parts of the wave oscillate in tandem, or in a definite phase relationship. In other words, it refers to the degree of confidence by which one can predict the amplitude and phase of a wave at a point, from the knowledge of these at another point at the same or a different instant of time. Emission from a thermal source, such as a light bulb, is a highly disordered process and the emitted light is incoherent. A well-stabilized laser source, on the other hand, generates light in a highly ordered manner and the emitted light is highly coherent. Incoherent and coherent light represent two extreme cases. While describing the phenomena of physical optics and diffraction theory, light is assumed to be perfectly coherent in both spatial as well as temporal senses, whereas in radiometry it is generally assumed to be incoherent. However, practical light sources and the fields generated by them are in between the two extremes and are termed as partially coherent sources and fields. The degree of order that exists in an optical field produced by a source of any kind may be described in terms of various correlation functions. These correlation functions are the basic theoretical tools for the analyses of statistical properties of partially coherent light fields.

Light fields generated from real physical sources fluctuate randomly to some extent. On a microscopic level quantum mechanical fluctuations produce randomness and on macroscopic level the randomness occurs as a consequence of these microscopic fluctuations, even in free space. In real physical sources, spontaneous emission causes random fluctuations and even in the case of lasers, spontaneous emission cannot be suppressed completely. In addition to spontaneous emission, there are many other processes that give rise to random fluctuations of light fields. Optical coherence theory was developed to describe the random nature of light and it deals with the statistical similarity between light fluctuations at two (or more) space–time points.

As mentioned earlier, in developing the theory of interference or diffraction, light is assumed to be perfectly coherent, or, in other words, it is taken to be monochromatic and sinusoidal for all times. This is, however, an idealization since the wave is obviously generated at some point of time by an atomic or molecular transition. Furthermore, a wavetrain generated by such a transition is of a finite duration, which is related to the finite lifetime of the atomic or molecular levels involved in the transition. Thus, any wave emanating from a source is an ensemble of a large number of such wavetrains of finite duration, say τ_c. A simplified visualization of such an ensemble is shown in Figure 1 where a wave is shown as a series of wavetrains of duration τ_c. It is evident from the figure that the fields at time t and $t + \Delta t$ will have a definite phase relationship if $\Delta t \ll \tau_c$ and will have no or negligible phase relationship when $\Delta t \gg \tau_c$. The time τ_c is known as the coherence time of the



Figure 1 Typical variation of the radiation field with time. The coherence time ~ τ_c.

radiation and the field is said to remain coherent for time ~ τ_c. This property of waves is referred to as the time coherence or the temporal coherence and is related to the spectral purity of the radiation. If one obtains the spectrum of the wave shown in Figure 1 by taking the Fourier transform of the time variation, it would have a width of $\Delta\nu$ around ν_0 which is the frequency of the sinusoidal variation of individual wavetrains. The spectral width $\Delta\nu$ is related to the coherence time as

$$\Delta\nu \sim 1/\tau_c \qquad [1]$$

For thermal sources such as a sodium lamp, $\tau_c \sim 100$ ps, whereas for a laser beam it could be as large as a few milliseconds. A related quantity is the coherence length l_c, which is the distance covered by the wave in time τ_c,

$$l_c = c\tau_c \sim \frac{c}{\Delta\nu} = \frac{\lambda_0^2}{\Delta\lambda} \qquad [2]$$

where λ_0 is the central wavelength ($\lambda_0 = c/\nu_0$) and $\Delta\lambda$ is the wavelength spread corresponding to the spectral width $\Delta\nu$. In a two-beam interference experiment (e.g., Michelson interferometer, Figure 2), the interfering beam derived from the same source will produce good interference fringes if the path difference between the two interfering beams is less than the coherence length of the radiation given out by the source.

It must be added here that for the real fields, generated by innumerable atoms or molecules, the individual wavetrains have different lengths around an average value τ_c. Furthermore, several wavetrains in general are propagating simultaneously, overlapping in space and time, to produce an ensemble whose properties are best understood in a statistical sense as we shall see in later sections.

Another type of coherence associated with the fields is the space coherence or the spatial coherence, which is related to the size of the source of radiation. It is evident that when the source is an ideal point source, the field at any two points (within the coherence length) would have definite phase relationship. However, the field from a thermal source of finite area S can be thought as resultant of the fields from each point on the source. Since each point source would usually be independent of the other, the phase relationship between the fields at any two points would depend on their position and size of the source. It can be shown that two points will have a strong phase relationship if they lie within the solid angle $\Delta\Omega$ from the source (Figure 3) such that



Figure 2 Michelson interferometer to study the temporal coherence of radiation from source S; M_1 and M_2 are mirrors and BS is a 50%–50% beamsplitter.

$$\Delta\Omega \sim \frac{\lambda_0^2}{S} \qquad [3]$$

Thus, on a plane R distance away from the source, one can define an area $A_c = R^2\Delta\Omega$ over which the field remains spatially coherent. This area A_c is called the coherence area of the radiation and its square root is sometimes referred to as the transverse coherence length. It is trivial to show that

$$A_c \sim \frac{\lambda_0^2}{\Delta\Omega_S} \qquad [4]$$

where $\Delta\Omega_S$ is the solid angle subtended by the source on the plane at which the coherence area is defined. In Young's double-hole experiment, if the two pinholes lie within the coherence area of the radiation from the primary source, good contrast in fringes would be observed.

Combining the concepts of coherence length and the coherence area, one can define a coherence volume as $V_c = A_c l_c$. For the wavefield from a thermal source, this volume represents that portion of the space in which the field is coherent and any



Figure 3 Spatial coherence and coherence area.

interference produced using the radiation from points within this volume will produce fringes of good contrast.

Mathematical Description of Coherence

Analytical Field Representation

Coherence properties associated with fields are best analyzed in terms of complex representation for optical fields. Let the real function $V^{(r)}(\mathbf{r},t)$ represent the scalar field, which could be one of the transverse Cartesian components of the electric field associated with the electromagnetic wave. One can then define a complex analytical signal $V(\mathbf{r},t)$ such that

$$\begin{aligned} V^{(r)}(\mathbf{r},t) &= \mathrm{Re}[V(\mathbf{r},t)], \\ V(\mathbf{r},t) &= \int_0^\infty \tilde{V}^{(r)}(\mathbf{r},\nu)\mathrm{e}^{-2\pi i\nu t}\,\mathrm{d}\nu \end{aligned} \tag{5}$$

where the spectrum $\tilde{V}^{(r)}(\mathbf{r},\nu)$ is the Fourier transform of the scalar field $V^{(r)}(\mathbf{r},t)$ and the spectrum for negative frequencies has been suppressed as it does not give any new information since $\tilde{V}^{(r)^*}(\mathbf{r},\nu) = \tilde{V}^{(r)}(\mathbf{r},-\nu)$.

In general, the radiation from a quasi-monochromatic thermal source fluctuates randomly as it is made of a large number of mutually independent contributions from individual atoms or molecules in the source. The field from such a source can be regarded as an ensemble of a large number of randomly different analytical signals such as $V(\mathbf{r},t)$. In other words, $V(\mathbf{r},t)$ is a typical member of an ensemble, which is the result of a random process representing the radiation from a quasi-monochromatic source. This process is assumed to be stationary and ergodic so that the ensemble average is equal to the time average of a typical member of the ensemble and that the origin of time is unimportant. Thus, the quantities of interest in the theory of coherence are defined as time averages:

$$\langle f(t)\rangle = \lim_{T\to\infty} \frac{1}{2T}\int_{-T}^{T} f(t)\mathrm{d}t \tag{6}$$

Mutual Coherence

In order to define the mutual coherence, the key concept in the theory of coherence, we consider Young's interference experiment, as shown in Figure 4, where the radiation from a broad source of size S is illuminating a screen with two pinholes P_1 and P_2. The light emerging from the two pinholes produces interference, which is observed on another screen at a distance R from the first screen. The field at point P, due to the pinholes, would be $K_1V(\mathbf{r}_1, t-t_1)$ and $K_2V(\mathbf{r}_2, t-t_2)$ respectively, where $\mathbf{r}_1$ and $\mathbf{r}_2$ define the positions of P_1 and P_2, t_1 and t_2 are the times taken by the light to travel to P from P_1 and P_2, and K_1 and K_2 are imaginary constants that depend on the geometry and size of the respective pinhole and its distance from the point P. Thus, the resultant field at point P would be given by

$$V(\mathbf{r},t) = K_1V(\mathbf{r}_1, t-t_1) + K_2V(\mathbf{r}_2, t-t_2) \tag{7}$$

Since the optical periods are extremely small as compared to the response time of a detector, the detector placed at point P will record only the time-averaged intensity:

$$I(P) = \langle V^*(\mathbf{r},t)V(\mathbf{r},t)\rangle \tag{8}$$



Figure 4 Schematic of Young's double-hole experiment.

where some constants have been ignored. With eqn [7], the intensity at point P would be given by

$$I(P) = I_1 + I_2 + 2\,\mathrm{Re}\left\{K_1 K_2^* \Gamma(\mathbf{r}_1, \mathbf{r}_2, t - t_1, t - t_2)\right\} \qquad [9]$$

where I_1 and I_2 are the intensities at point P, respectively, due to radiations from pinholes P_1 and P_2 independently (defined as $I_i = \langle |K_i V(\mathbf{r}_i, t)|^2 \rangle$) and

$$\begin{aligned}\Gamma(\mathbf{r}_1, \mathbf{r}_2, t - t_1, t - t_2) &\equiv \Gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)\\ &= \left\langle V^*(\mathbf{r}_1, t) V(\mathbf{r}_2, t + \tau)\right\rangle \end{aligned} \qquad [10]$$

is the mutual coherence function of the fields at P_1 and P_2, and it depends on the time difference $\tau = t_2 - t_1$, since the random process is assumed to be stationary. This function is also sometimes denoted by $\Gamma_{12}(\tau)$. The function $\Gamma_{ii}(\tau) \equiv \Gamma(\mathbf{r}_i, \mathbf{r}_i, \tau)$ defines the self-coherence of the light from the pinhole at P_i, and $|K_i|^2 \Gamma_{ii}(0)$ defines the intensity I_i at point P, due to the light from pinhole P_i.

Degree of Coherence and the Visibility of Interference Fringes

One can define a normalized form of the mutual coherence function, namely:

$$\begin{aligned}\gamma_{12}(\tau) \equiv \gamma(\mathbf{r}_1, \mathbf{r}_2, \tau) &= \frac{\Gamma_{12}(\tau)}{\sqrt{\Gamma_{11}(0)}\sqrt{\Gamma_{22}(0)}}\\ &= \frac{\langle V^*(\mathbf{r}_1, t) V(\mathbf{r}_2, t + \tau)\rangle}{\left[\left\langle |V(\mathbf{r}_1, t)|^2\right\rangle \left\langle |V(\mathbf{r}_2, t)|^2\right\rangle\right]^{1/2}}\end{aligned} \qquad [11]$$

which is called the complex degree of coherence. It can be shown that $0 \leq |\gamma_{12}(\tau)| \leq 1$. The intensity at point P, given by eqn [9], can now be written as

$$I(P) = I_1 + I_2 + 2\sqrt{I_1 I_2}\,\mathrm{Re}\left[\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)\right] \qquad [12]$$

Expressing $\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)$ as

$$\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau) = |\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)| \exp\left[\mathrm{i}\alpha(\mathbf{r}_1, \mathbf{r}_2, \tau) - 2\pi \mathrm{i} \nu_0 \tau\right] \qquad [13]$$

where $\alpha(\vec{r}_1, \vec{r}_2, \tau) = \arg[\gamma(\vec{r}_1, \vec{r}_2, \tau)] + 2\pi\nu_0\tau$, and ν_0 is the mean frequency of the light, the intensity in eqn [12] can be written as

$$\begin{aligned}I(P) = {} & I_1 + I_2 + 2\sqrt{I_1 I_2}|\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)|\\ & \times \cos\left[\alpha(\mathbf{r}_1, \mathbf{r}_2, \tau) - 2\pi\nu_0\tau\right]\end{aligned} \qquad [14]$$

Now, if we assume that the source is quasi-monochromatic, i.e., its spectral width $\Delta\nu \ll \nu_0$, the quantities $\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)$ and $\alpha(\mathbf{r}_1, \mathbf{r}_2, \tau)$ vary slowly on the observation screen, and the interference fringes are mainly obtained due to the cosine term. Thus, defining the visibility of fringes as $v = (I_{\max} - I_{\min})/(I_{\max} + I_{\min})$, we obtain

$$v = \frac{2(I_1 I_2)^{1/2}}{I_1 + I_2} |\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)| \qquad [15]$$

which shows that for maximum visibility, the two interfering fields must be completely coherent ($|\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)| = 1$). On the other hand, if the fields are completely incoherent ($|\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)| = 0$), no fringes are observed ($I_{\max} = I_{\min}$). The fields are said to be partially coherent when $0 < |\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)| < 1$. When $I_1 = I_2$, the visibility is the same as $|\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)|$. The relation in eqn [15] shows that in an interference experiment, one can obtain the modulus of the complex degree of coherence by measuring I_1, I_2, and the visibility. Similarly, eqn [14] shows that from the measurement the positions of maxima, one can obtain the phase of the complex degree of coherence, $\alpha(\mathbf{r}_1, \mathbf{r}_2, \tau)$.

Temporal and Spatial Coherence

If the source illuminating the pinholes is a point source of finite spectral width situated at point Q, the fields at point P_1 and P_2 (Figure 4) at any given instant are the same and the mutual coherence function becomes

$$\begin{aligned}\Gamma_{11}(\tau) = \Gamma(\mathbf{r}_1, \mathbf{r}_1, \tau) &= \langle V^*(\mathbf{r}_1, t) V(\mathbf{r}_1, t + \tau)\rangle\\ &= \langle V^*(\mathbf{r}_2, t) V(\mathbf{r}_2, t + \tau)\rangle = \Gamma_{22}(\tau)\end{aligned} \qquad [16]$$

The self-coherence, $\Gamma_{11}(\tau)$, of the light from pinhole P_1, is a direct measure of the temporal coherence of the source. On the other hand, if the source is of finite size and we observe the interference at point O which corresponds to $\tau = 0$, the mutual coherence function would be

$$\Gamma_{12}(0) = \Gamma(\mathbf{r}_1, \mathbf{r}_2, 0) = \langle V^*(\mathbf{r}_1, t) V(\mathbf{r}_2, t)\rangle \equiv J_{12} \qquad [17]$$

which is called the mutual intensity and is a direct measure of the spatial coherence of the source. In general, however, the function $\Gamma_{12}(\tau)$ measures, for a source of finite size and spectral width, a combination of the temporal and spatial coherence, and in only some limiting cases, the two types of coherence can be separated.

Spectral Representation of Mutual Coherence

One can also analyze the correlation between two fields in the spectral domain. In particular, one can define the cross-spectral density function $W(\mathbf{r}_1, \mathbf{r}_2, \nu)$ which defines the correlation between the amplitudes of the spectral components of frequency ν of the light at the points P_1 and P_2. Thus:

$$W(\mathbf{r}_1, \mathbf{r}_2, \nu)\delta(\nu - \nu') = \left\langle V^*(\mathbf{r}_1, \nu)V(\mathbf{r}_2, \nu')\right\rangle \qquad [18]$$

Using the generalized Wiener–Khintchine theorem, the cross-spectral density function can be shown to be the Fourier transform of the mutual coherence function:

$$\Gamma(\mathbf{r}_1, \mathbf{r}_2, \tau) = \int_0^\infty W(\mathbf{r}_1, \mathbf{r}_2, \nu)\mathrm{e}^{-2\pi \mathrm{i}\nu t}\,\mathrm{d}\nu \qquad [19]$$

$$W(\mathbf{r}_1, \mathbf{r}_2, \nu) = \int_{-\infty}^\infty \Gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)\mathrm{e}^{2\pi \mathrm{i}\nu t}\,\mathrm{d}\tau \qquad [20]$$

If the two points P_1 and P_2 coincide (i.e., there is only one pinhole), the cross-spectral density function reduces to the spectral density function of the light, which we denote by $S(\mathbf{r}, \nu)[\equiv W(\mathbf{r}, \mathbf{r}, \nu)]$. Thus, it follows from eqn [20] that the spectral density of light is the inverse Fourier transform of the self-coherence function. This leads to the Fourier transform spectroscopy, as we shall see later. One can also define spectral degree of coherence at frequency ν as

$$\begin{aligned}\mu(\mathbf{r}_1, \mathbf{r}_2, \nu) &= \frac{W(\mathbf{r}_1, \mathbf{r}_2, \nu)}{\sqrt{W(\mathbf{r}_1, \mathbf{r}_1, \nu)W(\mathbf{r}_2, \mathbf{r}_2, \nu)}} \\ &= \frac{W(\mathbf{r}_1, \mathbf{r}_2, \nu)}{\sqrt{S(\mathbf{r}_1, \nu)S(\mathbf{r}_2, \nu)}} \qquad [21]\end{aligned}$$

It is easy to see that $0 \le |\mu(\mathbf{r}_1, \mathbf{r}_2, \nu)| \le 1$. It is also sometimes referred to as the complex degree of coherence at frequency ν. It may be noted here that in the literature the notation $G^{(1,1)}(\nu) \equiv G(\mathbf{r}_1, \mathbf{r}_2, \gamma)$ has also been used for $W(\mathbf{r}_1, \mathbf{r}_2, \nu)$.

Propagation of Coherence

The van Cittert–Zernike Theorem

Perfectly coherent waves propagate through diffraction formulae, which have been discussed in this volume elsewhere. However, incoherent and partially coherent waves would evidently propagate somewhat differently. The earliest treatment of propagation noncoherent light is due to van Cittert, which was later generalized by Zernike to obtain what is now the van Cittert–Zernike theorem. The theorem deals with the correlations developed between fields at two points, which have been generated by a quasi-monochromatic and spatially incoherent planar source. Thus, as shown in Figure 5, we consider a quasi-monochromatic ($\Delta\nu \ll \nu_0$) planar source σ, which has an intensity distribution $I(\mathbf{r}')$ on its plane and is spatially incoherent, i.e., there is no correlation between the fields at any two points on the source.



Figure 5 Geometry for the van Cittert–Zernike theorem.

The field, due to this source, would develop finite correlations after propagation, and the theorem states that

$$\begin{aligned}\gamma(\mathbf{r}_1, \mathbf{r}_2, 0) &= \frac{\Gamma_{12}(0)}{\sqrt{\Gamma_{11}(0)}\sqrt{\Gamma_{12}(0)}} \\ &= \frac{1}{\sqrt{I(\mathbf{r}_1)I(\mathbf{r}_2)}}\iint_\sigma I(\mathbf{r}')\frac{\mathrm{e}^{2\pi \mathrm{i}\nu_0(R_2-R_1)/c}}{R_1R_2}\mathrm{d}^2r'\end{aligned} \qquad [22]$$

where $R_i = |\mathbf{r}_i - \mathbf{r}'|$ and $I(\mathbf{r}_i)$ is the intensity at point P_i. This relation is similar to the diffraction pattern produced at point P_1 due to a wave, with a spherical wavefront converging towards P_2 and with an amplitude distribution $I(\mathbf{r}')$ when it is diffracted by an aperture of the same shape, size, and the intensity distribution as those of the incoherent source σ. Thus, the theorem shows that a radiation, which was incoherent at the source, becomes partially coherent as it propagates.

Generalized Propagation

The expression $\mathrm{e}^{-2\pi \mathrm{i}\nu_0 R_1/c}/R_1$ can be interpreted as the field obtained at P_1 due to a point source located at the point $\mathbf{r}'$ on the planar source. Thus, this expression is simply the point spread function of the homogeneous space between the source and the observation plane containing the points P_1 and P_2. Hopkins generalized this to include any linear optical system characterized by a point spread function $h(\mathbf{r}_j - \mathbf{r}')$ and obtained the formula for the complex degree of coherence of a radiation emerging from an incoherent, quasi-monochromatic planar source after it has propagated through such a linear optical system:

$$\gamma(\mathbf{r}_1,\mathbf{r}_2,0) = \frac{1}{\sqrt{I(\mathbf{r}_1)I(\mathbf{r}_2)}}\iint_\sigma I(\mathbf{r}')h(\mathbf{r}_1 - \mathbf{r}')h^*(\mathbf{r}_2 - \mathbf{r}')\mathrm{d}^2r' \qquad [23]$$

It would thus seem that the correlations propagate in much the same way, as does the field. Indeed, Wolf showed that the mutual correlation function

$\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau)$ satisfies the wave equations:

$$\nabla_1^2\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau)=\frac{1}{c^2}\frac{\partial^2}{\partial\tau^2}\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau)$$
$$\nabla_2^2\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau)=\frac{1}{c^2}\frac{\partial^2}{\partial\tau^2}\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau) \qquad [24]$$

where ∇_j^2 is the Laplacian with respect to the point $\mathbf{r}_i$. Here the first of eqns [24], for instance, gives the variation of the mutual coherence function with respect to $\mathbf{r}_1$ and τ for fixed $\mathbf{r}_2$. Further, the variable τ is the time difference defined through the path difference, since $\tau=(R_2-R_1)/c$, and the actual time does not affect the mutual coherence function (as the fields are assumed to be stationary).

Using the relation in eqn [20], one can also obtain from eqn [24], the propagation equations for the cross-spectral density function $W(\mathbf{r}_1,\mathbf{r}_2,\nu)$:

$$\nabla_1^2 W(\mathbf{r}_1,\mathbf{r}_2,\nu)+k^2W(\mathbf{r}_1,\mathbf{r}_2,\nu)=0$$
$$\nabla_2^2 W(\mathbf{r}_1,\mathbf{r}_2,\nu)+k^2W(\mathbf{r}_1,\mathbf{r}_2,\nu)=0 \qquad [25]$$

where $k=2\pi\nu/c$.

Thompson and Wolf Experiment

One of the most elegant experiments for studying various aspects of coherence theory was carried out by Thompson and Wolf by making slight modifications in the Young's double-hole experiment. The experimental set-up shown in Figure 6 consists of a quasi-monochromatic broad incoherent source S of diameter $2a$. This was obtained by focusing filtered narrow band light from a mercury lamp (not shown in the figure) on to a hole of size $2a$ in an opaque screen A. A mask consisting of two pinholes, each of diameter $2b$ with their axes separated by a distance d, was placed symmetrically about the optical axis of the experimental setup at plane B between two lenses L_1 and L_2, each having focal length f. The source was at the front focal plane of the lens L_1 and the observations were made at the plane C at the back focus of the lens L_2. The separation d was varied to study the spatial coherence function on the mask plane by measuring the visibility and the phase of the fringes formed in plane C.



Figure 6 Schematic of the Thompson and Wolf experiment.

Using the van Cittert–Zernike theorem, the complex degree of coherence at the pinholes P_1 and P_2 on the mask after the lens L_1 is

$$\gamma_{12}=|\gamma_{12}|e^{i\beta_{12}}=\frac{2J_1(v)}{v}\ \text{with}\ v=\left(\frac{2\pi\nu ad}{cf}\right) \qquad [26]$$

for symmetrically placed pinholes about the optical axis. Here β_{12} is the phase of the complex degree of coherence and in this special case where the two holes are equidistant from the axis, β_{12} is either zero or π, respectively, for positive or negative values of $2J_1(v)/v$. Let us assume that the intensities at two pinholes P_1 and P_2 are equal. The interference pattern observed at the back focal plane of lens L_2 is due to the superposition of the light diffracted from the pinholes. The beams are partially coherent with degree of coherence given by eqn [26]. Since the pinholes are symmetrically placed, the intensity due to either of the pinholes at a point P at the back focal plane of the lens L_2 is the same and is given by the Fraunhofer formula for diffraction from circular apertures, i.e.:

$$I_1(P)=I_2(P)=\left|\frac{2J_1(u)}{u}\right|^2,\ \text{with}\ u=\frac{2\pi\nu}{c}b\sin\phi \qquad [27]$$

and ϕ is the angle that the diffracted beam makes from normal to the plane of the pinholes. The intensity of the interference pattern produced at the back focal plane of the lens L_2 is:

$$I(P)=2I_1(P)\left[1+\left|\frac{2J_1(v)}{v}\right|^2\cos(\delta+\beta_{12})\right] \qquad [28]$$

where $\delta=\mathrm{d}\sin\phi$ is the phase difference between the two beams reaching P from P_1 and P_2. For the on-axis point O, the quantity δ is zero.

The maximum and minimum values of $I(P)$ are given by

$$I_{\max}(P)=2I_1(P)\lfloor 1+|2J_1(v)/v|^2\rfloor \qquad [29(a)]$$

$$I_{\max}(P)=2I_1(P)\lfloor 1-|2J_1(v)/v|^2\rfloor \qquad [29(b)]$$

Figure 7 shows an example of the observed fringe patterns obtained by Thompson (1958) in a subsequent experiment.

Types of Fields

As mentioned above, $\gamma_{12}(\tau)$ is a measure of the correlation of the complex field at any two points P_1



Figure 7 Two beam interference patterns obtained by using partially coherent light. The wavelength of light used was 0.579 μm and the separation *d* of the pinholes in the screen at B was 0.5 cm. The figure shows the observed fringe pattern and the calculated intensity variation for three sizes of the secondary source. The dashed lines show the maximum and minimum intensity. The values of the diameter, 2*a*, of the source and the corresponding values of the magnitude, $|\gamma_{12}|$, and the phase, β_{12}, are also shown in each case. Reproduced with permission from Thompson BJ (1958) Illustration of phase change in two-beam interference with partially coherent light. *Journal of the Optical Society of America* 48: 95–97.

and P_2 at specific time delay τ. Extending this definition, an optical field may be coherent or incoherent, if $|\gamma_{12}(\tau)| = 1$ or $|\gamma_{12}(\tau)| = 0$, respectively, for all pairs of points in the field and for all time delays. In the following, we consider some specific cases of fields and their properties.

Perfectly Coherent Fields

A field would be termed as perfectly coherent or self-coherent at a fixed point, if it has the property that $|\gamma(\mathbf{R}, \mathbf{R}, \tau)| = 1$ at some specific point $\mathbf{R}$ in the domain of the field for all values of time delay τ. It can also be shown that $\gamma(\mathbf{R}, \mathbf{R}, \tau)$ is periodic in time, i.e.:

$$\gamma(\mathbf{R}, \mathbf{R}, \tau) = \mathrm{e}^{-2\pi \mathrm{i}\nu_0\tau} \quad \text{for} \quad \nu_0 > 0 \qquad [30]$$

For any other point $\mathbf{r}$ in the domain of the field, $\gamma(\mathbf{R}, \mathbf{r}, \tau)$ and $\gamma(\mathbf{r}, \mathbf{R}, \tau)$ are also unimodular and also periodic in time.

A perfectly coherent optical field at two fixed points has the property that $|\gamma(\mathbf{R}_1, \mathbf{R}_2, \tau)| = 1$ for any two fixed points $\mathbf{R}_1$ and $\mathbf{R}_2$ in the domain of the field for all values of time delay τ. For such a field, it can be shown that $\gamma(\mathbf{R}_1, \mathbf{R}_2, \tau) = \exp[\mathrm{i}(\beta - 2\pi\nu_0\tau)]$ with ν_0 (> 0) and β are real constants. Further, as a corollary, $|\gamma(\mathbf{R}_1, \mathbf{R}_1, \tau)| = 1$ and $|\gamma(\mathbf{R}_2, \mathbf{R}_2, \tau)| = 1$ for all τ, i.e., the field is self-coherent at each of the field points $\mathbf{R}_1$ and $\mathbf{R}_2$, and

$$\gamma(\mathbf{R}_1, \mathbf{R}_1, \tau) = \gamma(\mathbf{R}_2, \mathbf{R}_2, \tau) = \exp(-2\pi \mathrm{i}\nu_0\tau) \text{ for } \nu_0 > 0$$

It can be shown that for any other point $\mathbf{r}'$ within the field

$$\begin{aligned} &\gamma(\mathbf{r}, \mathbf{R}_2, \tau) = \gamma(\mathbf{R}_1, \mathbf{R}_2, 0)\gamma(\mathbf{r}, \mathbf{R}_1, \tau) = \gamma(\mathbf{r}, \mathbf{R}_1, \tau)\mathrm{e}^{\mathrm{i}\beta} \\ &\gamma(\mathbf{R}_1, \mathbf{R}_2, \tau) = \gamma(\mathbf{R}_1, \mathbf{R}_2, 0)\exp[-2\pi \mathrm{i}\nu_0\tau] \end{aligned} \qquad [31]$$

A perfectly coherent optical field for all points in the domain of the field has the property that $|\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)| = 1$ for all pairs of points $\mathbf{r}_1$ and $\mathbf{r}_2$ in the domain of the field, for all values of time delay τ.

It can then be shown that $\gamma(\mathbf{r}_1,\mathbf{r}_2,\tau) = \exp\{i[\alpha(\mathbf{r}_1) - \alpha(\mathbf{r}_2)] - 2\pi i\nu_0\tau\}$, where $\alpha(\mathbf{r}')$ is real function of a single position $\mathbf{r}'$ in the domain of the field. Further, the mutual coherence function $\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau)$ for such a field has a factorized periodic form as

$$\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau) = U(\mathbf{r}_1)U^*(\mathbf{r}_2)\ \exp(-2\pi i\nu_0\tau) \qquad [32]$$

which means the field is monochromatic with frequency ν_0 and $U(\mathbf{r})$ is any solution of the Helmholtz equation:

$$\nabla^2 U(\mathbf{r}) + k_0^2 U(\mathbf{r}) = 0, \quad k_0 = 2\pi\nu_0/c \qquad [33]$$

The spectral and cross-spectral densities of such fields are represented by Dirac δ-functions with their singularities at some positive frequency ν_0. Such fields, however, can never occur in nature.

Quasi-Monochromatic Fields

Optical fields are found in practice for which spectral spread $\Delta\nu$ is much smaller than the mean frequency $\bar{\nu}$. These are termed as quasi-monochromatic fields. The cross-spectral density $W(\mathbf{r}_1,\mathbf{r}_2,\nu)$ of the quasi-monochromatic fields attains an appreciable value only in the small region $\Delta\nu$, and falls to zero outside this region.

$$W(\mathbf{r}_1,\mathbf{r}_2,\nu) = 0,\ \ |\nu - \bar{\nu}| > \Delta\nu \ \text{ and } \ \Delta\nu \ll \bar{\nu} \qquad [34]$$

The mutual coherence function $\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau)$ can be written as the Fourier transform of cross-spectral density function as

$$\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau) = e^{-2\pi i\bar{\nu}\tau}\int_0^\infty W(\mathbf{r}_1,\mathbf{r}_2,\nu)e^{-2\pi i(\nu-\bar{\nu})\tau}d\nu \qquad [35]$$

If we limit our attention to small τ such that $\Delta\nu|\tau| \ll 1$ holds, the exponential factor inside the integral is approximately equal to unity and eqn [35] reduces to

$$\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau) = \exp(-2\pi i\bar{\nu}\tau)\int_0^\infty [W(\mathbf{r}_1,\mathbf{r}_2,\nu)]d\nu \qquad [36]$$

which gives

$$\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau) = \Gamma(\mathbf{r}_1,\mathbf{r}_2,0)\ \exp(-2\pi i\bar{\nu}\tau) \qquad [37]$$

Equation [37] describes the behavior of $\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau)$ for a limited range of τ values for quasi-monochromatic fields and in this range it behaves as a monochromatic field of frequency $\bar{\nu}$. However, due to the factor $\Gamma(\mathbf{r}_1,\mathbf{r}_2,0)$, the quasi-monochromatic field may be coherent, partially coherent, or even incoherent.

Cross-Spectrally Pure Fields

The complex degree of coherence, if it can be factored into a product of a component dependent on spatial coordinates and a component dependent on time delay, is called reducible. In the case of perfectly coherent light, the complex degree of coherence is reducible, as we have seen above, e.g., in eqn [32], and in the case of quasi-monochromatic fields, this is reducible approximately as shown in eqn [37]. There also exists a very special case of a cross-spectrally pure field for which the complex degree of coherence is reducible. A field is called a cross-spectrally pure field if the normalized spectrum of the superimposed light is equal to the normalized spectrum of the component beams, a concept introduced by Mandel. In the space-frequency domain, the intensity interference law is expressed as the so-called spectral interference law:

$$\begin{aligned} S(\mathbf{r},\nu) = {} & S^{(1)}(\mathbf{r},\nu) + S^{(2)}(\mathbf{r},\nu) \\ & + 2\left[\sqrt{S^{(1)}(\mathbf{r},\nu)}\sqrt{S^{(2)}(\mathbf{r},\nu)}\right]\mathrm{Re}[\mu(\mathbf{r}_1,\mathbf{r}_2,\nu)e^{-2\pi i\nu\tau}] \end{aligned} \qquad [38]$$

where $\mu(\mathbf{r}_1,\mathbf{r}_2,\nu)$ is the spectral degree of coherence, defined in eqn [21] and τ is the relative time delay that is needed by the light from the pinholes to reach any point on the screen; $S^{(1)}(\mathbf{r},\nu)$ and $S^{(2)}(\mathbf{r},\nu)$ are the spectral densities of the light reaching P from the pinholes P_1 and P_2, respectively (see Figure 4) and it is assumed that the spectral densities of the field at pinholes P_1 and P_2 are the same $[S(\mathbf{r}_1,\nu) = CS(\mathbf{r}_2,\nu)]$. Now, if we consider a point for which the time delay is τ_0, then it can be seen that the last term in eqn [38] would be independent of frequency, provided that

$$\mu(\mathbf{r}_1,\mathbf{r}_2,\nu)\ \exp(-2\pi i\nu\tau_0) = f(\mathbf{r}_1,\mathbf{r}_2,\tau_0) \qquad [39]$$

where $f(\mathbf{r}_1,\mathbf{r}_2,\tau_0)$ is a function of $\mathbf{r}_1$, $\mathbf{r}_2$ and τ_0 only and the light at this point would have the same spectral density as that at the pinholes. If a region exists around the specified point on the observation plane, such that the spectral distribution of the light in this region is of the same form as the spectral distribution of the light at the pinholes, the light at the pinholes is cross-spectrally pure light.

In terms of the spectral distribution of the light $S(\mathbf{r}_1,\nu)$ at pinhole P_1 and $S(\mathbf{r}_2,\nu)[= CS(\mathbf{r}_1,\nu)]$ at pinhole P_2, the mutual coherence function at the pinholes can be written as

$$\Gamma(\mathbf{r}_1,\mathbf{r}_2,\tau) = \sqrt{C}\int S(\mathbf{r}_1,\nu)\mu(\mathbf{r}_1,\mathbf{r}_2,\nu)\ \exp(-2\pi i\nu\tau)d\nu \qquad [40]$$

and using eqn [39], we get the very important condition for the field to be cross-spectrally pure, i.e.:

$$\gamma(\mathbf{r}_1,\mathbf{r}_2,\tau) = \gamma(\mathbf{r}_1,\mathbf{r}_2,\tau_0)\gamma(\mathbf{r}_1,\mathbf{r}_1,\tau - \tau_0) \qquad [41]$$

The complex degree of coherence $\gamma(\mathbf{r}_1, \mathbf{r}_2, \tau)$ is thus expressible as the product of two factors: one factor characterizes the spatial coherence at the two pinholes at time delay τ_0 and the other characterizes the temporal coherence at one of the pinholes. Equation [41] is known as the reduction formula for cross-spectrally pure light. It can further be shown that

$$\mu(\mathbf{r}_1, \mathbf{r}_2, \nu) = \gamma(\mathbf{r}_1, \mathbf{r}_2, \tau_0)\ \exp(2\pi i \nu \tau_0) \qquad [42]$$

Thus, the absolute value of the spectral degree of coherence is the same for all frequencies and is equal to the absolute value of the degree of coherence for the point specified by τ_0. It has been shown that cross-spectrally pure light can be generated, for example, by linear filtering of light that emerges from the two pinholes in Young's interference experiments.

Types of Sources

Primary Sources

A primary source is a set of radiating atoms or molecules. In a primary source the randomness comes from true source fluctuations, i.e., from the spatial distributions of fluctuating charges and currents. Such a source gives rise to a fluctuating field. Let $Q(\mathbf{r}, t)$ represent the fluctuating source variable at any point $\mathbf{r}$ at time t, then the field generated by the source is represented by fluctuating field variable $V(\mathbf{r}, t)$. The source is assumed to be localized in some finite domain such that $Q(\mathbf{r}, t) = 0$ at any time $t > 0$ outside the domain. Assuming that field variable $V(\mathbf{r}, t)$ and the source variable $Q(\mathbf{r}, t)$ are scalar quantities, they are related by an inhomogeneous equation as

$$\nabla^2 V(\mathbf{r}, t) - \frac{1}{c^2}\frac{\partial^2}{\partial t^2} V(\mathbf{r}, t) = -4\pi Q(\mathbf{r}, t) \qquad [43]$$

The mutual coherence functions of the source $\Gamma_Q(\mathbf{r}_1, \mathbf{r}_2, \tau) = \langle Q^*(\mathbf{r}_1, t) Q(\mathbf{r}_2, t+\tau)\rangle$ and of the field $\Gamma_V(\mathbf{r}_1, \mathbf{r}_2, \tau) = \langle V^*(\mathbf{r}_1, t) V(\mathbf{r}_2, t+\tau)\rangle$ characterize the statistical similarity of the fluctuating quantities at the points $\mathbf{r}_1$ and $\mathbf{r}_2$. Following eqn [20], one can define, respectively, the cross-spectral density function of the source and the field as

$$W_Q(\mathbf{r}_1, \mathbf{r}_2, \nu) = \int_{-\infty}^{\infty} \Gamma_Q(\mathbf{r}_1, \mathbf{r}_2, \tau) e^{-2\pi i \nu t}\, d\tau \qquad [44]$$

$$W_V(\mathbf{r}_1, \mathbf{r}_2, \nu) = \int_{-\infty}^{\infty} \Gamma_V(\mathbf{r}_1, \mathbf{r}_2, \tau) e^{-2\pi i \nu t}\, d\tau$$

The cross-spectral density functions of the source and of the field are related as

$$(\nabla_2^2 + k^2)(\nabla_1^2 + k^2) W_V(\mathbf{r}_1, \mathbf{r}_2, \nu) = 4\pi^2 W_Q(\mathbf{r}_1, \mathbf{r}_2, \nu) \qquad [45]$$

The solution of eqn [45] is represented as

$$W_V(\mathbf{r}_1, \mathbf{r}_2, \nu) = \int_S \int_S W_Q(\mathbf{r}'_1, \mathbf{r}'_2, \nu) \frac{e^{ik(R_2 - R_1)}}{R_1 R_2} d^3 r'_1\, d^3 r'_2 \qquad [46]$$

where $R_1 = |\mathbf{r}_1 - \mathbf{r}'_1|$ and $R_2 = |\mathbf{r}_2 - \mathbf{r}'_2|$ (see Figure 8). Using eqn [46], one can then obtain an expression for the spectrum at a point ($\mathbf{r}_1 = \mathbf{r}_2 = \mathbf{r} = r\mathbf{u}$) in the far field ($r \gg r'_1, r'_2$) of a source as

$$S^{\infty}(r\mathbf{u}, \nu) = \frac{1}{r^2} \int_S \int_S W_Q(\mathbf{r}'_1, \mathbf{r}'_2, \nu) e^{-ik\mathbf{u}\cdot(\mathbf{r}'_1 - \mathbf{r}'_2)} d^3 r'_1\, d^3 r'_2 \qquad [47]$$

where $\mathbf{u}$ is the unit vector along $\mathbf{r}$. The integral in eqn [47], i.e., the quantity defined by $r^2 S^{\infty}(r\mathbf{u}, \nu)$, is also defined as the radiant intensity, which represents the rate of energy radiated at the frequency ν from the source per unit solid angle in the direction of $\mathbf{u}$.

Secondary Sources

Sources used in a laboratory are usually secondary planar sources. A secondary source is a field, which arises from the primary source in the region outside the domain of the primary sources. This kind of source is an aperture on an opaque screen illuminated either directly or via an optical system by primary sources. Let $V(\boldsymbol{\rho}, t)$ represent the fluctuating field in a secondary source plane σ at $z = 0$ (Figure 9) and $W_0(\boldsymbol{\rho}_1, \boldsymbol{\rho}_2, \nu)$ represent its cross-spectral density (the subscript 0 refers to $z = 0$). One can then solve eqn [25] to obtain the propagation of the cross-spectral density from this planar source. For two points P_1 and P_2 located at distances which are large compared to wavelength, the cross-spectral density is



Figure 8 Geometry of a 3-dimensional primary source S and the radiation from it.



Figure 9 Geometry of a planar source σ and the radiation from it.

then given by

$$W(\mathbf{r}_1,\mathbf{r}_2,\nu)=\left(\frac{k}{2\pi}\right)^2\int_\sigma\int_\sigma W_0(\boldsymbol{\rho}_1,\boldsymbol{\rho}_2,\nu)\times\frac{\mathrm{e}^{\mathrm{i}k(R_2-R_1)}}{R_1R_2}\cos\theta'_1\cos\theta'_2\,\mathrm{d}^2\rho_1\,\mathrm{d}^2\rho_2 \qquad [48]$$

where $R_j=|\mathbf{r}_j-\boldsymbol{\rho}_j|$, $(j=1,2)$, θ'_1 and θ'_2 are the angles that R_1 and R_2 directions make with the z-axis (Figure 9). Using eqn [48], one can then obtain an expression for the spectrum at a point ($\mathbf{r}_1=\mathbf{r}_2=\mathbf{r}=r\mathbf{u}$) in the far field ($r\gg\rho_1,\rho_2$) of a planar source as

$$S^\infty(r\mathbf{u},\nu)=\frac{k^2}{2\pi^2}\frac{\cos^2\theta}{r^2}\int_\sigma\int_\sigma W_0(\boldsymbol{\rho}_1,\boldsymbol{\rho}_2,\nu)\times\mathrm{e}^{-\mathrm{i}k\mathbf{u}_\perp\cdot(\boldsymbol{\rho}_1-\boldsymbol{\rho}_2)}\mathrm{d}^2\rho_1\,\mathrm{d}^2\rho_2 \qquad [49]$$

where $\mathbf{u}_\perp$ is the projection of the unit vector $\mathbf{u}$ on the plane σ of the source.

Schell-Model Sources

In the framework of coherence theory in space–time domain, two-dimensional planar model sources of this kind were first discussed by Schell. Later, the model was adopted for formulation of coherence theory in space–frequency domain. Schell-model sources are the sources whose degree of spectral coherence $\mu_A(\mathbf{r}_1,\mathbf{r}_2,\nu)$ (for either primary or secondary source) is stationary in space. It means that $\mu_A(\mathbf{r}_1,\mathbf{r}_2,\nu)$ depends on $\mathbf{r}_1$ and $\mathbf{r}_2$ only through the difference $\mathbf{r}_2-\mathbf{r}_1$, i.e., of the form:

$$\mu_A(\mathbf{r}_1,\mathbf{r}_2,\nu)\equiv\mu_A(\mathbf{r}_2-\mathbf{r}_1,\nu) \qquad [50]$$

for each frequency ν present in the source spectrum. Here A stands for field variables V, in the case of a Schell-model secondary source and for source variables Q, in the case of a Schell-model primary source. The cross-spectral density function of a Schell-model source is of the form:

$$W_A(\mathbf{r}_1,\mathbf{r}_2,\nu)=[S_A(\mathbf{r}_1,\nu)]^{1/2}[S_A(\mathbf{r}_2,\nu)]^{1/2}\mu_A(\mathbf{r}_2-\mathbf{r}_1,\nu) \qquad [51]$$

where $S_A(\mathbf{r},\nu)$ is the spectral density of the light at a typical point in the primary source or on the plane of a secondary source. Schell model sources do not assume low coherence, and therefore, can be applied to spatially stationary light fields of any state of coherence. The Schell-model of the form given in eqn [51] has been used to represent both three-dimensional primary sources and two-dimensional secondary sources.

Quasi-Homogeneous Sources

Useful models of partially coherent sources that are frequently encountered in nature or in the laboratory are the so-called quasi-homogeneous sources. These are an important sub-class of Schell-model sources. A Schell-model source is called quasi-homogeneous if the intensity of a Schell model source is essentially constant over any coherence area. Under these approximations, the cross-spectral density function for a quasi-homogeneous source is given by

$$\begin{aligned}W_A(\mathbf{r}_1,\mathbf{r}_2,\nu)&=S_A\left[\tfrac{1}{2}(\mathbf{r}_1+\mathbf{r}_2),\nu\right]\mu_A(\mathbf{r}_2-\mathbf{r}_1,\nu)\\&=S_A[\mathbf{r},\nu]\mu_A(\mathbf{r}',\nu)\end{aligned} \qquad [52]$$

where $\mathbf{r}=(\mathbf{r}_1+\mathbf{r}_2)/2$, and $\mathbf{r}'=\mathbf{r}_2-\mathbf{r}_1$. The subscript A stands for either V or Q for the field variable or a source variable, respectively. It is clear that for a quasi-homogeneous source the spectral density $S_A(\mathbf{r},\nu)$ varies so slowly with position that it is approximately constant over distances across the sources that are of the order of the correlation length Λ, which is a measure of the effective width of $|\mu_A(\mathbf{r}',\nu)|$. Therefore, $S_A(\mathbf{r},\nu)$ is a slowly varying function of $\mathbf{r}$ (Figure 10b) and $|\mu_A(\mathbf{r}',\nu)|$ is a fast varying function of $\mathbf{r}'$ (Figure 10a). In addition, the linear dimensions of the source are large compared with the wavelength of light and with the correlation length Δ (Figure 10c).

Quasi-homogeneous sources are always spatially incoherent in the ‘global’ sense, because their linear dimensions are large compared with the correlation length. This model is very good for representing two-dimensional secondary sources with sufficiently low coherence such that the intensity does not vary over the coherence area on the input plane. It has also been applied to three-dimensional primary sources,



Figure 10 Concept of quasi-homogeneous sources.

three-dimensional scattering potentials, and two-dimensional primary and secondary sources.

Equivalence Theorems

The study of partially coherent sources led to the formulations of a number of equivalence theorems, which show that sources of any state of coherence can produce the same distribution of the radiant intensity as a fully spatially coherent laser source. These theorems provide conditions under which sources of different spatial distribution of spectral density and of different state of coherence will generate fields, which have the same radiant intensity. It has been shown, by taking examples of Gaussian–Schell model sources, that sources of completely different coherence properties and different spectral distributions across the source generate identical distribution of radiant intensity. Experimental verifications of the results of these theorems have also been carried out. For further details on this subject, the reader is referred to Mandel and Wolf (1995).

Correlation-Induced Spectral Changes

It was assumed that spectrum is an intrinsic property of light that does not change as the radiation propagates in free-space, until studies on partially coherent sources and radiations from them in 1980s, revealed that this was true only for specific type of sources. It was discovered on general grounds that the spectrum of light, which originates in an extended source, either a primary source or a secondary source, depends not only on the source spectrum but also on the spatial coherence properties of the source. It was also predicted theoretically by Wolf that the spectrum of light would, in general, be different from the spectrum of the source, and be different at different points in space on propagation in free space.

For a quasi-homogeneous planar secondary source defined by eqn [52], whose normalized spectrum is the same at each source point, one can write the spectral density as

$$S_0(\boldsymbol{\rho},\nu) = I_0(\boldsymbol{\rho})g_0(\nu) \quad \text{with} \quad \int_0^\infty g_0(\nu)\mathrm{d}\nu = 1 \qquad [53]$$

where $I_0(\boldsymbol{\rho})$ is the intensity of light at point $\boldsymbol{\rho}$ on the plane of the source, $g_0(\nu)$ is the normalized spectrum of the source and the subscript 0 refers to the quantities of the source plane. Using eqn [49], one can obtain an expression for the far-field spectrum due to this source as

$$S^\infty(r\mathbf{u},\nu) = \frac{k^2}{2\pi^2}\frac{\cos^2\theta}{r^2}\int_\sigma\int_\sigma I_0(\boldsymbol{\rho})g_0(\nu)\mu_0(\boldsymbol{\rho}',\nu) \times \mathrm{e}^{-ik\mathbf{u}_\perp\cdot(\boldsymbol{\rho}_1-\boldsymbol{\rho}_2)}\,\mathrm{d}^2\rho_1\,\mathrm{d}^2\rho_2 \qquad [54]$$

Noting that $\boldsymbol{\rho} = (\boldsymbol{\rho}_1 + \boldsymbol{\rho}_2)/2$ and $\boldsymbol{\rho}' = \boldsymbol{\rho}_2 - \boldsymbol{\rho}_1$, one can transform the variables of the integration and obtain after some manipulation:

$$S^{(\infty)}(r\mathbf{u},\nu) = \frac{k^2\cos^2\theta}{(2\pi r)^2}\tilde{I}_0\tilde{\mu}_0(k\mathbf{u}_\perp,\nu)g_0(\nu) \qquad [55]$$

where

$$\tilde{\mu}_0(k\mathbf{u}_\perp,\nu) = \int_\sigma \mu_0(\boldsymbol{\rho}',\nu)\mathrm{e}^{-ik\mathbf{u}_\perp\cdot\boldsymbol{\rho}'}\,\mathrm{d}^2\rho' \qquad [56]$$

and

$$\tilde{I}_0 = \int_\sigma I_0(\boldsymbol{\rho})\mathrm{d}^2\rho \qquad [57]$$

Equation [55] shows that the spectrum of the field in the far-zone depends on the coherence properties of the source through its spectral degree of coherence $\mu_0(\boldsymbol{\rho}',\nu)$ and on the normalized source spectrum $g_0(\nu)$.

Scaling Law

The reason why coherence-induced spectral changes were not observed until recently is that the usual thermal sources employed in laboratories or commonly encountered in nature have special coherence properties and the spectral degree of coherence has the function form:

$$\mu^{(0)}(\boldsymbol{\rho}_2 - \boldsymbol{\rho}_1, \nu) = f[k(\boldsymbol{\rho}_2 - \boldsymbol{\rho}_1)] \quad \text{with} \quad k = \frac{2\pi\nu}{c} \qquad [58]$$

which shows that the spectral degree of coherence depends only on the product of the frequency and space coordinates. This formula expresses the so-called scaling law, which was enunciated by Wolf. Commonly used sources satisfy this property. For example, the spectral degree of coherence of Lambertian sources and black-body sources can be shown to be

$$\mu_0(\boldsymbol{\rho}_2 - \boldsymbol{\rho}_1, \nu) = \frac{\sin(k|\boldsymbol{\rho}_2 - \boldsymbol{\rho}_1|)}{k|\boldsymbol{\rho}_2 - \boldsymbol{\rho}_1|} \qquad [59]$$

This expression evidently satisfies the scaling law. If the spectral degree of coherence does not satisfy the scaling law, the normalized far-field spectrum will, in general, vary in different directions in the far-zone and will differ from the source spectrum.

Spectral Changes in Young's Interference Experiment

Spectral changes in Young's interference experiment with broadband light are not as well understood as in experiments with quasi-monochromatic, probably because in such experiments no interference fringes are formed. However, if one were to analyze the spectrum of the light in the region of superposition, one would observe changes in the spectrum of light in the region of superposition in the form of a shift in the spectrum for narrowband spectrum and spectral modulation for broadband light. One can readily derive an expression for the spectrum of light in the region of superposition. Let $S^{(1)}(P, \nu)$ be the spectral density of the light at P which would be obtained if the small aperture at P_1 alone was open; $S^{(2)}(P, \nu)$ has a similar meaning if only the aperture at P_2 was open (Figure 4).

Let us assume, as is usually the case, that $S^{(2)}(P, \nu) \approx S^{(1)}(P, \nu)$ and let d be the distance between the two pinholes. Consider the spectral density at the point P, at distance x from the axis of symmetry in an observation plane located at distance of R from the plane containing the pinholes. Assuming that $x/R \ll 1$, one can make the approximation $R_2 - R_1 \approx xd/R$. The spectral interference law (eqn [38]) can then be written as

$$S(P, \nu) \approx 2S^{(1)}(P, \nu)\{1 + |\mu(P_1, P_2, \nu)| \times \cos[\beta(P_1, P_2, \nu) + 2\pi\nu x d/cR]\} \qquad [60]$$

where $\beta(P_1, P_2, \nu)$ denotes the phase of the spectral degree of coherence. Equation [60] implies the two results:

(i) at any fixed frequency ν, the spectral density varies sinusoidally with the distance x of the point from the axis, with the amplitude and the phase of the variation depending on the (generally complex) spectral degree of coherence $\mu(P_1, P_2, \nu)$; and

(ii) at any fixed point P in the observation plane the spectrum $S(P, \nu)$ will, in general, differ from the spectrum $S^{(1)}(P, \nu)$, the change also depending on the spectral degree of coherence $\mu(P_1, P_2, \nu)$ of the light at the two pinholes.

Experimental Confirmations

Experimental tests of the theoretical prediction of spectral invariance and noninvariance due to correlation of fluctuations across the source were performed just after the theoretical predictions. Figure 11 shows results of one such experiment in which spectrum changes in the Young's experiment were studied. Several other experiments also reported confirmation of the source correlation-dependent spectral changes. One of the important applications of these observations has been to explain the discrepancies in the maintenance of the spectroradiometric scales by national laboratories in different countries. These studies also have potential application in determining experimentally the spectral degree of coherence of partially coherent fields. The knowledge of spectral degree of coherence is often important in remote sensing, e.g., for determining angular diameters of stars.



Figure 11 Correlation-induced changes in spectrum in Young's interference. Dashed line represents the spectrum when only one of the slits is open, the continuous curve shows the spectrum when both the slits are open and the circles are the measured values in the latter case. Reproduced with permission from Santarsiero M and Gori F (1992) Spectral changes in Young interference pattern. *Physics Letters* 167: 123–128.

Applications of Optical Coherence

Stellar Interferometry

The Michelson stellar interferometer, named after Albert Michelson, was used to determine the angular diameters of stars and also the intensity distribution across the star. The method was devised by Michelson without using any concept of coherence, although subsequently the full theory of the method was developed on the basis of propagation of correlations. A schematic of the experiment is shown in Figure 12. The interferometer is mounted in front of a telescope, a reflecting telescope in this case. The light from a star is reflected from mirrors M_1 and M_2 and is directed towards the primary mirror (or the objective lens) of the telescope. The two beams thus collected superpose in the focal plane F of telescope where an image crossed with fringes is formed. The outer mirrors M_1 and M_2 can be moved along the axis defined as $M_1M_3M_4M_2$ while the inner mirrors M_3 and M_4 remain fixed. The fringe spacing depends on the position of mirrors M_3 and M_4 and hence is fixed, while the visibility of the fringes depends on the separation of the mirrors M_1 and M_2 and hence, can be varied. Michelson showed that from the measurement of the variation of the visibility with the separation of the two mirrors, one could obtain information about the intensity distribution of the stars, which are rotationally symmetric. He also showed that if the stellar disk is circular and uniform, the visibility curve as a function of the separation d of the mirrors M_1 and M_2 will have zeros for certain values of d, and that the smallest of these d values for which zero occurs is given by $d_0 = 0.61\lambda_a/\alpha$, where α is the semi-angular diameter of the star and λ_a is the mean wavelength of the filtered quasi-monochromatic light from the star. Angular diameters of several stars down to 0.02 second of an arc were determined.



Figure 12 Schematic of the Michelson stellar interferometer.

From the standpoint of second-order coherence theory the principles of the method can be readily understood. The star is considered an incoherent source and according to the van Cittert–Zernike theorem, the light reaching the outer mirrors M_1 and M_2 of the interferometer will be partially coherent. This coherence would depend on the size of and the intensity distribution across the star. Let (x_1, y_1) and (x_2, y_2) be the coordinates of the positions of the mirrors M_1 and M_2, respectively, and (ξ, η) the coordinates of a point on the surface plane of the star which is assumed to be at a very large (astronomical) distance R from the mirrors. The complex degree of coherence at the mirrors would then be given by eqn [22] which can now be written as

$$\gamma(\Delta x, \Delta y, 0) = \frac{\int_\sigma I(u, v) e^{-ik_a(u\Delta x + v\Delta y)}\, du\, dv}{\int_\sigma I(u, v) du\, dv} \qquad [61]$$

where $I(u, v)$ is the intensity distribution across the star disk σ as a function of the angular coordinates $u = \xi/R$, $v = \eta/R$, $\Delta x = x_1 - x_2$, $\Delta y = y_1 - y_2$, and $k_a = 2\pi/\lambda_a$, λ_a being the mean wavelength of the light from the star. Equation [61] shows that the equal-time ($\tau = 0$) complex degree of coherence of the light incident at the outer mirrors of the interferometer is the normalized Fourier-transform of the intensity distribution across the stellar disk. Further, eqn [15] shows that the visibility of the interference fringes is the absolute value of γ, if the intensity of the two interfering beams is equal, as in the present case. The phase of γ can be determined by the position of the intensity maxima of the fringe pattern (eqn [14]). If one is interested in determining only the angular size of the star and the star is assumed to be a circularly symmetric disk of angular diameter 2α and of uniform intensity [$I(u, v)$ is constant across the disk], then eqn [61] reduces to

$$\gamma(\Delta x, \Delta y) = \frac{2J_1(v)}{v}, \quad v = \frac{2\pi\alpha}{\lambda_a} d, \quad d = \sqrt{(\Delta x)^2 + (\Delta y)^2} \qquad [62]$$

The smallest separation of the mirrors for which the visibility γ vanishes corresponds to $v = 3.832$, i.e., $d_0 = 0.61\lambda_a/\alpha$, which is in agreement with Michelson's result.

Interference Spectroscopy

Another contribution of Michelson, which was subsequently identified as an application of the coherence theory, was the use of his interferometer (Figure 2) to determine the energy distribution in the spectral lines. The method he developed is capable to resolving spectral lines that are too narrow to be analyzed by the spectrometer. The visibility of the interference fringes depends on the energy distribution in the spectrum of the light and its measurement can give information about the spectral lines. In particular, if the energy distribution in a spectral line is symmetric about some frequency ν_0, its profile is simply the Fourier transform of the visibility variation as a function of the path difference between the two interfering beams. This method is the basis of interference spectroscopy or the Fourier transform spectroscopy.

Within the framework of second-order coherence theory, if the mean intensity of the two beams in a Michelson's interferometer is the same, then the visibility of the interference fringes in the observation plane is related to the complex degree of coherence of light at a point at the beamsplitter where the two beams superimpose (eqn [15]). The two quantities are related as $v(\tau) = |\gamma(\tau)|$ where $\gamma(\tau) \equiv \gamma(\mathbf{r}_1, \mathbf{r}_1, \tau)$ is the complex degree of self-coherence at the point $\mathbf{r}_1$ on the beamsplitter. Following eqn [19], $\gamma(\tau)$ can be represented by a Fourier integral as

$$\gamma(\tau) = \int_0^\infty s(\nu)\exp(-\mathrm{i}2\pi\nu\tau)\mathrm{d}\nu \qquad [63]$$

where $s(\nu)$ is the normalized spectral density of the light defined as $s(\nu) = S(\nu)/\int_0^\infty S(\nu)\mathrm{d}\nu$ and $S(\nu) \equiv S(\mathbf{r}_1, \nu) = W(\mathbf{r}_1, \mathbf{r}_1, \nu)$ is the spectral density of the beam at the point $\mathbf{r}_1$. The method is usually applied to very narrow spectral lines for which one can assume that the peak that occurs at ν_0, and $\gamma(\tau)$ can be represented as

$$\begin{aligned}\gamma(\tau) &= \bar{\gamma}(\tau)\exp(-2\pi\mathrm{i}\nu_0\tau) \quad \text{with}\\ \bar{\gamma}(\tau) &= \int_{-\infty}^{\infty} \bar{s}(\mu)\exp(-\mathrm{i}2\pi\mu\tau)\mathrm{d}\mu\end{aligned} \qquad [64]$$

where $\bar{s}(\mu)$ is the shifted spectrum such that

$$\begin{aligned}\bar{s}(\mu) &= s(\nu_0 + \mu) \quad & \mu \geq -\nu_0\\ &= 0 & \mu < -\nu_0\end{aligned}$$

From the above one readily gets

$$v(\tau) = |\gamma(\tau)| = \left|\int_{-\infty}^{\infty} \bar{s}(\mu)\exp(-\mathrm{i}2\pi\mu\tau)\mathrm{d}\mu\right| \qquad [65]$$

If the spectrum is symmetric about ν_0, then $v(\tau)$ would be an even function of τ and the Fourier inversion would give:

$$\bar{s}(\mu) = s(\nu_0 + \mu) = 2\int_0^\infty v(\tau)\cos(2\pi\mu\tau)\mathrm{d}\tau \qquad [66]$$

which can be used to calculate the spectral energy distribution for a symmetric spectrum about ν_0 from the visibility curve. However, for an asymmetric spectral distribution, the visibility and the phase of the complex degree of coherence must be determined as the Fourier transform of the shifted spectrum is no longer real everywhere.

Higher-Order Coherence

So far we have considered correlations of the fluctuating field variables at two space–time $(\mathbf{r}, t)$ points, as defined in eqn [10]. These are termed as second-order correlations. One can extend the concept of correlations to more than two space–time points, which will involve higher-order correlations. For example, one can define the space–time cross correlation function of order (M, N) of the random field $V(\mathbf{r}, t)$, represented by $\Gamma^{(M,N)}$, as an ensemble average of the product of the field $V(\mathbf{r}, t)$ values at N space–time points and $V^*(\mathbf{r}, t)$ at other M points. In this notation, the mutual coherence function as defined in eqn [10] would now be $\Gamma^{(1,1)}$. Among higher-order correlations, the one with $M = N = 2$, is of practical significance and is called the fourth-order correlation function, $\Gamma^{(2,2)}(\mathbf{r}_1, t_1, \mathbf{r}_2, t_2; \mathbf{r}_3, t_3, \mathbf{r}_4, t_4)$. The theory of Gaussian random variables tells us that any higher correlation can be written in terms of second-order correlations over all permutations of pairs of points. In addition, if we assume that $(\mathbf{r}_3, t_3) = (\mathbf{r}_1, t_1)$ and $(\mathbf{r}_4, t_4) = (\mathbf{r}_2, t_2)$, and that the field is stationary, then $\Gamma^{(2,2)}$ is called the intensity–intensity correlation and is given as

$$\begin{aligned}&\Gamma^{(2,2)}(\mathbf{r}_1,\mathbf{r}_2,t_2 - t_1)\\ &\quad= \langle V(\mathbf{r}_1,t_1)V(\mathbf{r}_2,t_2)V^*(\mathbf{r}_1,t_1)V^*(\mathbf{r}_2,t_2)\rangle\\ &\quad= \langle I(\mathbf{r}_1,t_1)I(\mathbf{r}_2,t_2)\rangle\\ &\quad= \langle I(\mathbf{r}_1,t_1)\rangle\langle I(\mathbf{r}_2,t_2)\rangle(1 + |\gamma^{(1,1)}(\mathbf{r}_1,\mathbf{r}_2,t_2 - t_1)|^2)\end{aligned} \qquad [67]$$

where

$$\gamma^{(1,1)}(\mathbf{r}_1,\mathbf{r}_2,t_2 - t_1) = \frac{\Gamma^{(1,1)}(\mathbf{r}_1,\mathbf{r}_2,t_2 - t_1)}{[\langle I(\mathbf{r}_1,t_1)\rangle]^{1/2}[\langle I(\mathbf{r}_2,t_2)\rangle]^{1/2}} \qquad [68]$$

We now define fluctuations in intensity at $(\mathbf{r}_j, t_j)$ as

$$\Delta I_j = I(\mathbf{r}_j, t_j) - \langle I(\mathbf{r}_j, t_j)\rangle$$

and then the correlation of intensity fluctuations becomes

$$\begin{aligned}\langle \Delta I_1 \Delta I_2 \rangle &= \big\langle I(\mathbf{r}_1,t_1)I(\mathbf{r}_2,t_2)\big\rangle - \big\langle I(\mathbf{r}_1,t_1)\rangle\langle I(\mathbf{r}_2,t_2)\big\rangle \\ &= \big\langle I(\mathbf{r}_1,t_1)\big\rangle\big\langle I(\mathbf{r}_2,t_2)\big\rangle |\gamma^{(1,1)}(\mathbf{r}_1,\mathbf{r}_2,t_2-t_1)|^2\end{aligned} \quad [69]$$

where we have used eqn [67]. Equation [69] forms the basis for intensity interferometry.

Hanbury-Brown and Twiss Experiment

In this landmark experiment conducted both on the laboratory scale and astronomical scale, Hanbury-Brown and Twiss demonstrated the existence of intensity–intensity correlations in terms of the correlations in the photocurrents in the two detectors and thus measured the squared modulus of complex degree of coherence. In the laboratory experiment, the arc of a mercury lamp was focused onto a circular hole to produce a secondary source. The light from this source was then divided equally into two parts through a beamsplitter. Each part was, respectively, detected by two photomultiplier tubes, which had identical square apertures in front. One of the tubes could be translated normally to the direction of propagation of light and was so positioned that its image through the splitter could be made to coincide with the other tube. Thus, by suitable translation a measured separation d between the two square apertures could be introduced. The output currents from the photomultiplier tubes were taken by cables of equal length to a correlator. In the path of each cable a high-pass filter was inserted, so that only the current fluctuations could be transmitted to the correlator. Thus, the normalized correlations between the two current fluctuations:

$$C(d) = \frac{\big\langle \Delta J_1(t)\Delta J_2(t)\big\rangle}{\big\langle [\Delta J_1(t)]^2\big\rangle^{1/2}\big\langle [\Delta J_2(t)]^2\big\rangle^{1/2}} \quad [70]$$

as a function of detector separation d could be measured. Now when the detector response time is much larger than the time-scale of the fluctuations in intensity, then it can be shown that the correlations in the fluctuations of the photocurrent are proportional to the correlations of the fluctuations in intensity of the light being detected. Thus, we would have

$$C(d) \approx \delta |\gamma^{(1,1)}(\mathbf{r}_1,\mathbf{r}_2,0)|^2 \quad [71]$$

where δ is the average number of photocounts of the light of one polarization during the time-scale of the fluctuations (for general thermal sources, this is much less than one). Equation [71] represents the Hanbury-Brown–Twiss effect.

Stellar Intensity Interferometry

Michelson stellar interferometry can resolve stars which have angular sizes of the order of 0.01″, since for smaller stars, the separation between the primary mirrors runs into several meters and maintaining stability of mirrors such that the optical paths do not change, even by fraction of a wavelength, is extremely difficult. The atmospheric turbulence further adds to this problem and obtaining stable fringe pattern becomes next to impossible for very small stars. Hanbury-Brown and Twiss applied the intensity interferometry based on their photoelectric correlation technique for determining the angular sizes of such stars. Two separate parabolic mirrors collected light from the star and the output of the photodetectors placed at the focus of each mirror was sent to a correlator. The cable lengths were made unequal so as to compensate for the time difference of the light arrival at the two mirrors. The normalized correlation of the fluctuations of the photocurrents was determined as described above. This would give the variation of the modulus-squared degree of coherence as a function of the mirror separation d from which the angular size of the stars can be estimated. The advantage of the stellar intensity interferometer over the stellar (amplitude) interferometer is that the light need not interfere as in the latter, since the photodetectors are mounted directly at the focus of the primary mirrors of the telescope. Thus, the constraint on the large path difference between the two beams is removed and large values of d can now be used. Moreover, the atmosphere turbulence and the mirror movements have very small effect. Stellar angular diameters as small as 0.0004″ of arc with resolution of 0.00003″ could be measured by such interferometers.

See also

Coherence: Coherence and Imaging. **Coherent Lightwave Systems**. **Coherent Transients:** Coherent Transient Spectroscopy in Atomic and Molecular Vapours. **Coherent Control:** Applications in Semiconductors; Experimental; Theory. **Interferometry:** Overview. **Information Processing:** Coherent Analogue Optical Processors. **Terahertz Technology:** Coherent Terahertz Sources.

Further Reading

Beran MJ and Parrent GB (1964) *Theory of Partial Coherence*. Englewood Cliffs, NJ: Prentice-Hall.

Born M and Wolf E (1999) *Principles of Optics*. New York: Pergamon Press.

Carter WH (1996) Coherence theory. In: Bass M (ed.) *Hand Book of Optics*. New York: McGraw-Hill.

Davenport WB and Root WL (1960) *An Introduction to the Theory of Random Signals and Noise*. New York: McGraw-Hill.

Goodman JW (1985) *Statistical Optics*. Chichester: Wiley.

Hanbury-Brown R and Twiss RQ (1957) Interferometry of intensity fluctuations in light: I basic theory: the correlation between photons in coherent beams of radiation. *Proceedings of the Royal Society* 242: 300–324.

Hanbury-Brown R and Twiss RQ (1957) Interferometry of intensity fluctuations in light: II an experimental test of the theory for partially coherent light. *Proceedings of the Royal Society* 243: 291–319.

Kandpal HC, Vaishya JS and Joshi KC (1994) Correlation-induced spectral shifts in optical measurements. *Optical Engineering* 33: 1996–2012.

Mandel L and Wolf E (1965) Coherence properties of optical fields. *Review of Modern Physics* 37: 231–287.

Mandel L and Wolf E (1995) *Optical Coherence and Quantum Optics*. Cambridge, UK: Cambridge University Press.

Marathay AS (1982) *Elements of Optical Coherence*. New York: John Wiley.

Perina J (1985) *Coherence of Light*. Boston, MA: M.A. Reidel.

Santarsiero M and Gori F (1992) Spectral changes in Young interference pattern. *Physics Letters* 167: 123–128.

Schell AC (1967) A technique for the determination of the radiation pattern of a partially coherent aperture. *IEEE Transactions on Antennas and Propagation* AP-15: 187.

Thompson BJ (1958) Illustration of phase change in two-beam interference with partially coherent light. *Journal of the Optical Society of America* 48: 95–97.

Thompson BJ and Wolf E (1957) Two beam interference with partially coherent light. *Journal of the Optical Society of America* 47: 895–902.

Wolf E and James DFV (1996) Correlation-induced spectral changes. *Report on Progress in Physics* 59: 771–818.

Coherence and Imaging

J van der Gracht, HoloSpex, Inc., Columbia, MD, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical imaging systems are strongly affected by the coherence of the light that illuminates the object of interest. In many cases, the light is approximately coherent or incoherent. These approximations lead to simple mathematical models for the image formation process and allow straightforward analysis and design of such systems. When the light is partially coherent, the mathematical models are more complicated and system analysis and design is more difficult. Partially coherent illumination is often used in microscopy, machine vision, and optical lithography. The intent of this article is to provide the reader with a basic understanding of the effects of coherence on imaging. The information should enable the reader to recognize when coherence effects are present in an imaging system and give insight into when coherence can be modified to improve imaging performance. The material relies mostly on concepts drawn from the Fourier optics perspective of imaging and a rigorous coherence theory treatment is avoided. We encourage the reader to consult the Further Reading list at the end of this article, for more complete definitions of terms for coherence theory. A number of experimental results highlight the effects of spatial coherence of the illumination on image formation. Discussions of the role of coherence in such key applications are interspersed throughout the article.

Image Formation – Ideal and Optimal

An image is typically defined as the reproduction or likeness of the form of an object. An image that is indistinguishable from the original object is generally considered to be ideal. In a general context, the sound of a voice coming from a loudspeaker can be thought of as the image of the sound coming directly from the original speaker's mouth. In optical imaging, the ideal image replicates the light emanating from the object. Taken to the extreme, the ideal image replicates the light leaving the object in terms of intensity, wavelength, polarization, and even coherence. When the final image is viewed by the eye, the ideal image only needs to replicate the spatial distribution of the light leaving the object in terms of color and relative intensity at each point on the object. (In this article, intensity is defined as optical power per unit area (watts per meter squared).)

A general diagram of a direct view image formation system is shown in Figure 1. The condenser optics gathers light from a primary source and illuminates a transmissive object having a complex wave amplitude transmission of $O(x, y)$. The imaging optics produce an optical image that is viewed directly by the viewer. A growing number of image formation systems now include a solid-state image detector as shown in Figure 2. The raw intensity optical image is converted to an electronic signal that can be digitally processed and then displayed on a monitor. In this system, the spatial intensity distribution emanating from the monitor is the final image. The task of the optical system to the left of the detector is to gather spatial information about the light properties of the object. In fact, the information gathered by the detector includes information about the object, the illumination system, and the image formation optics. If the observer is only interested in the light transmission properties of the object, the effects of the illumination and image formation optics must be well understood. When the light illuminating the object is known to be coherent or incoherent, reasonably simple models for the overall image formation process can be used. More general, partially coherent illumination can produce optically formed images that differ greatly from the intensity pattern leaving the object. Seen from this perspective, partially coherent illumination is an undesirable property that creates nonideal images and complicates the image analysis.



Figure 1 Direct view optical system. Imaging optics conveys the light from an illuminated object directly to the human viewer.



Figure 2 Indirect view optical system. The raw intensity optical image is detected electronically, processed and a final image is presented to the human observer on a display device.

The ideal image as described above is not necessarily the optimum image for a particular task. Consider the case of object recognition when the object has low optical contrast. Using the above definition, an ideal image would mimic the low contrast and render recognition difficult. An image formation system that alters the contrast to improve the recognition task would be better than the so-called ideal image. The image formation system that maximized the appropriate performance metric for a particular recognition task would be considered optimal. In optimizing the indirect imaging system of Figure 2, the designer can adjust the illumination, the imaging optics, and the post-detection processing. In fact, research microscopes often include an adjustment that modifies illumination coherence and often alters the image contrast. Darkfield and phase contrast imaging microscopes usually employ partially coherent illumination combined with pupil modification to view otherwise invisible objects. Seen from this perspective, partially coherent illumination is a desirable property that provides more degrees of freedom to the imaging system designer. Quite often, partially coherent imaging systems provide a compromise between the performance of coherent and incoherent systems.

Elementary Coherence Concepts

Most readers are somewhat familiar with the concept of temporal coherence. In Figure 3, a Michelson interferometer splits light from a point source into two paths and recombines the beams to form interference fringes. The presence of interference fringes indicates that the wave amplitude fluctuations of the two beams are highly correlated so the light adds in wave amplitude. If the optical path difference between the two paths can be made large without reducing the fringe contrast, the light is said to be



Figure 3 The presence of high contrast fringes in a Michelson interferometer indicates high temporal coherence.



Figure 4 A Young's two pinhole interferometer produces: (a) a uniform high contrast fringe pattern for light that is highly spatially and temporally coherent; (b) high contrast fringes only near the axis for low temporal coherence and high spatial coherence light; and (c) no fringe pattern for high temporal coherence, low spatial coherence light.

highly temporally coherent. Light from very narrowband lasers can maintain coherence over very large optical path differences. Light from broadband light sources requires very small optical path differences to add in wave amplitude.

Spatial coherence is a measure of the ability of two separate points in a field to interfere. The Young's two pinhole experiment in Figure 4 measures the coherence between two points sampled by the pinhole mask. Only a one-dimensional pinhole mask is shown for simplicity. Figure 4a shows an expanded laser beam illuminating two spatially separated pinholes and recombining to form an intensity fringe pattern. The high contrast of the fringe indicates that the wave amplitude of the light from the two pinholes is highly correlated. Figure 4b shows a broadband point source expanded in a similar fashion. The fringe contrast is high near the axis because the optical path difference between the two beams is zero on the axis and relatively low near the axis. For points far from the axes, the fringe pattern disappears because the low temporal coherence from the broadband source results in a loss in correlation of the wave amplitudes.

A final Young's experiment example in Figure 4c shows that highly temporally coherent light can be spatially incoherent. In the figure, the light illuminating the two pinholes comes from two separate and highly temporally coherent lasers that are designed to have the same center frequency. Since the light from the lasers is not synchronized in phase, any fringes that might form for an instant will move rapidly and average to a uniform intensity pattern over the integration time of a typical detector. Since the fringe contrast is zero over a practical integration time, the light at the two pinholes is effectively spatially incoherent.

Two-point Imaging

In a typical partially coherent imaging experiment we need to know how light from two pinholes adds at the optical image plane, as shown in Figure 5. Diffraction and system aberrations cause the image of a single point to spread so that the images of two spatially separated object points overlap in the image plane. The wave amplitude image of a single pinhole is called the coherent point spread function (CPSF). Since the CPSF is compact, two CPSFs will only overlap when the corresponding object points are closely spaced. When the two points are sufficiently close, the relevant optical path differences will be small so full temporal coherence can be assumed. Spatial coherence will be the critical factor in determining how to add the responses to pairs of point images. We assume full temporal coherence in the subsequent analyses and the light is said to be *quasimonochromatic*.

Coherent Two-Point Imaging

Consider imaging a two-point object illuminated by a spatially coherent plane wave produced from a point source, as depicted in Figure 6a. In the figure, the imaging system is assumed to be space-invariant. This means that the spatial distribution of the CPSF is the same regardless of position of the input pinhole. The CPSF in the figure is broad enough such that the image plane point responses overlap for this particular pinhole spacing. Since the wave amplitudes from the two pinholes are correlated, the point responses add in wave amplitude, resulting in a two-point image intensity given by

$$I_{2\mathrm{coh}}(x) = I_0|h(x-x_1)|^2 + I_0|h(x-x_2)|^2 \qquad [1]$$

where $h(x)$ is the normalized CPSF and I_0 is a scaling factor that determines the absolute image intensity value. Since the CPSF has units of wave amplitude, the magnitude squaring operation accounts for the square law response of the image plane detector.



Figure 5 Imaging of two points. The object plane illumination coherence determines how the light adds in the region of overlap of the two image plane points.

More generally, the image intensity for an arbitrary object distribution can be found by breaking the object into a number of points and adding the CPSFs due to each point on the object. The resultant image plane intensity is the spatial convolution of the object amplitude transmittance with the CPSF and is given by

$$I_{\mathrm{coh}}(x) = I_0\left|\int O(\xi)h(\xi - x)\mathrm{d}\xi\right|^2 \qquad [2]$$

where $O(x)$ is the object amplitude transmittance.

Incoherent Two-Point Imaging

Two pinhole imaging with spatially incoherent light is shown in Figure 6b, where a spatially extended blackbody radiator is placed directly behind the pinholes. Once again the imaging optics are assumed to be space-invariant and have the same CPSF as the system in Figure 6a. Since the radiation is originating from two completely different physical points on the source, no correlation is expected between the wave amplitude of the light leaving the pinholes and the light is said to be spatially incoherent. The resultant image intensity corresponding to the two pinhole object with equal amplitude transmittance values is calculated by adding the individual intensity responses to give

$$I_{2\mathrm{inc}}(x) = I_0|h(x-x_1)|^2 + I_0|h(x-x_2)|^2 \qquad [3]$$

For more general object distributions, the image intensity is the convolution of the object intensity transmittance with the incoherent PSF, and is given by

$$I_{\mathrm{inc}}(x) = I_0\int |o(\xi)|^2|h(x-\xi)|^2\mathrm{d}\xi \qquad [4]$$



Figure 6 Imaging of two points for (a) spatially coherent illumination and (b) spatially incoherent imaging.

where the intensity transmittance is the squared magnitude of the amplitude transmittance and the incoherent PSF is the squared magnitude of the CPSF.

Partially Coherent Two-Point Imaging

Finally we consider two pinhole imaging illuminated by partially spatially coherent light. Now the two-point responses do not add simply in amplitude or intensity. Rather, the image intensity is given by the more general equation:

$$I_{2\mathrm{pc}}(x) = I_0\big[|h(x - x_1)^2 + |h(x - x_2)|^2 + 2\mathrm{Re}\{\mu(x_1; x_2)h(x - x_1)h^*(x - x_2)\}\big] \quad [5]$$

where the $*$ denotes complex conjugations and $\mu(x_1; x_2)$ is the normalized form of the mutual intensity of the object illumination evaluated at the object points in question. The mutual intensity function is often denoted as $J_0(x_1; x_2)$ and is a measure of the cross correlation of the wave amplitude distributions leaving the two pinholes. Rather than providing a rigorous definition, we note that the magnitude of $J_0(x_1; x_2)$ corresponds to the fringe contrast that would be produced if the two object pinholes were placed at the input of a Young's interference experiment. The phase is related to the relative spatial shift of the fringe pattern. When the light is uncorrelated, $J_0(x_1; x_2) = 0$ and eqn [5] collapses to the incoherent limit of eqn [4]. When the light is coherent, $J_0(x_1; x_2) = 1$ and eqn [5] reduces to the coherent form of eqn [2].

Image formation for a general object distribution is given by the bilinear equation:

$$I_{\mathrm{pc}}(x) = I_0 \int o(\xi_1)o^*(\xi_2)h(x - \xi_1)h^*(x - \xi_2) \times J_{\mathrm{o}}(\xi_1 - \xi_2)\mathrm{d}\xi_1\,\mathrm{d}\xi_2 \quad [6]$$

Note that, in general, $J_0(x_1; x_2)$ must be evaluated for all pairs of object points. Close examination of this equation reveals that just as a linear system can be evaluated by considering all possible single point responses, a bilinear system requires consideration of all possible pairs of points. This behavior is much more complicated and does not allow the application of the well-developed linear system theory.

Source Distribution and Object Illumination Coherence

According to eqn [6], the mutual intensity of all pairs of points at the object plane must be known, to calculate a partially coherent image. Consider the telecentric Kohler illumination imaging system shown in Figure 7. The primary source is considered to be spatially incoherent and illuminates the object after passing through lens L1 located one focal distance away from the source and one focal distance away from the object. Even though the primary source is spatially incoherent, the illumination at the object plane is partially coherent. The explicit mutual intensity function corresponding to the object plane illumination is given by applying the van Cittert Zernike theorem:

$$J_0(\Delta x) = \int S(\xi)\exp[\mathrm{j}2\pi\Delta x\xi/\lambda F]\mathrm{d}\xi \quad [7]$$

where $S(x)$ is the intensity distribution of the spatially incoherent primary source, F is the focal length of the lens, λ is the illumination wavelength, and $\Delta x = x_1 - x_2$. The van Cittert Zernike theorem reflects a Fourier transform relationship between the source image intensity distribution and the mutual intensity at the object plane. When the source plane is effectively spatially incoherent, the object plane mutual intensity is only a function of separation distance. For a two-dimensional object, the mutual intensity needs to be characterized for all pairs of unique spacings in x and y. In Figure 7, the lens arrangement ensures that the object plane is located in the far field of the primary source plane. In fact, the van Cittert Zernike theorem applies more generally, even in the Fresnel propagation regime, as long as the standard paraxial approximation for optics is valid.



Figure 7 A telecentric Kohler illumination system with a spatially incoherent primary source imaged onto the pupil.


Lens
Spatially incoherent source
(a)
F
F
$J_0(\Delta x) = 1$
1.0
Δx
Lens
Infinite extent spatially incoherent source
(b)
F
F
$J_0(\Delta x) = \zeta(\Delta x)$
Δx
Lens
Finite spatially incoherent source
(c)
F
F
$J_0(\Delta x) = \frac{\sin(\alpha\pi\Delta x)}{\alpha\pi\Delta x}$
Δx

Figure 8 Light propages from the source plane to the object plane and produces (a) coherent illumination from a single source point; (b) incoherent illumination from an infinite extent source; and (c) partially coherent illumination from a finite extent primary source.

Figure 8 shows some simple examples of primary source distributions and the corresponding object plane mutual intensity function. Figure 8a assumes an infinitesimal point source and the corresponding mutual intensity is 1.0 for all possible pairs of object points. Figure 8b assumes an infinite extent primary source and results in a dirac delta function for the mutual intensity function. This means that there is no correlation between any two object points having a separation greater than zero so the object plane illumination is spatially incoherent. In Figure 5c, a finite extent uniform source gives a mutual intensity function of the form $\sin(\alpha\pi\Delta x)/(\alpha\Delta x)$. The finite-sized source corresponds to partially coherent imaging and shows that the response to pairs of points is affected by the spatial distribution of the source in a complicated way. Note that a large primary source corresponds to a large range of angular illumination at the object plane.

Varying the size of the source in the imaging system of Figure 8 will affect the spatial coherence of the illumination and hence the optical image intensity. Many textbook treatments discuss the imaging of two points separated by the Rayleigh resolution criterion which corresponds to the case where the first minimum of one point image coincides with the maximum of the adjacent point image. With a large source that provides effectively incoherent light, the two point image has a modest dip in intensity between the two points, as shown in Figure 9a. Fully coherent illumination of two points separated by the Rayleigh resolution produces a single large spot with no dip in intensity, as shown in Figure 9b. Varying the source size and hence the illumination spatial coherence produces a dip that is less than the incoherent intensity dip. This result is often used to suggest that coherent imaging gives poorer resolution than incoherent imaging. In fact, generalizations about two-point resolution can be misleading.

Recent developments in optical lithography have shown that coherence can be used to effectively increase two-point resolution beyond traditional diffraction limits. In Figure 9c, one of the pinholes in a coherent two-point imaging experiment has been modified with a phase shift corresponding to one half of a wavelength of the illuminating light. The two images add in wave amplitude and the phase shift creates a distinct null at the image plane and effectively enhances the two-point resolution. This approach is termed phase screen lithography and has been exploited to produce finer features in lithography by purposely introducing small phase shift masks at the object mask. In practice, the temporal and spatial coherence of the light is engineered to give sufficient coherence to take advantage of the two-point enhancement while maintaining sufficient incoherence to avoid speckle-like artifacts associated with coherent light.

Spatial Frequency Modeling of Imaging

Spatial frequency models of image formation are also useful in understanding how coherence affects image formation. A spatially coherent imaging system has a particularly simple spatial frequency model. In the



Lens L1
Lens L2
Lens L2
Image
Intensity
Distance
(a)
Lens L1
Lens L2
Lens L2
Image
Infite
extent
source
Intensity
Distance
(b)
Lens L1
Lens L2
Lens L2
Image
Phase
shift
Intensity
Distance
(c)

Figure 9 Comparison of coherent and two point imaging of two pinholes separated by the Rayleigh distance. (a) Coherent image cannot resolve the two points. (b) Incoherent image barely resolves the two points. (c) Coherential illumination with a phase shifting plate at one pinhole produces a null between the two image points.



Lens
L1
Object
Lens
L2
Pupil
Lens
L3
Image
F
F
F
F
F
F

Figure 10 The object Fourier transform is filtered by the pupil function in a coherent imaging system.

spatially coherent imaging system shown in Figure 10, the on-axis plane wave illumination projects the spatial Fourier transform of the object, or Fraunhofer pattern, onto the pupil plane of the imaging system. The pupil acts as a frequency domain filter that can be modified to perform spatial frequency filtering. The complex transmittance of the pupil is the wave amplitude spatial frequency transfer function of the imaging system. It follows that the image plane wave amplitude frequency spectrum, $\tilde{U}_c(f_x)$, is given by

$$\tilde{U}_c(f_x) = \tilde{O}(f_x)H(f_x) \qquad [8]$$

where $\tilde{O}(f_x)$ is the spatial Fourier transform of the object amplitude transmittance function and $H(f_x)$ is proportional to the pupil plane amplitude transmittance. Equation [8] is the frequency domain version of the convolution representation given by eqn [2], but does not account for the squared magnitude response of the detector.

In the previous section, we learned that an infinite extent source is necessary to achieve fully incoherent imaging for the imaging system of Figure 7. As a thought experiment, one can start with a single point source on the axis and keep adding mutually incoherent source points to build up from a coherent imaging system to an incoherent imaging system. Since the individual source points are assumed to be incoherent with each other, the images from each point source can be added in intensity. In Figure 11,



Figure 11 A second source point projects a second object Fourier transform onto the pupil plane. The images produced by the two source points add in intensity at the image plane.

only two point sources are shown. Each point source projects an object Fraunhofer pattern onto the pupil plane. The centered point source will result in the familiar coherent image. The off-axis point source projects a displaced object Fraunhofer pattern that is also filtered by the pupil plane before forming an image of the object. The image formed from this second point source can be modeled with the same coherent imaging model with a shifted pupil plane filter. Since the light from the two source points is uncorrelated, the final image is calculated by adding the intensities of the two coherently formed images.

The two source point model of Figure 11 can be generalized to an arbitrary number of source points. The final image is an intensity superposition of a number of coherent images. This suggests that partially coherent imaging systems behave as a number of redundant coherent imaging systems, each having a slightly different amplitude spatial frequency transfer function due to the relative shift of the pupil filter with respect to the object Fraunhofer pattern. As the number of point sources is increased to infinity, the primary source approaches an infinite extent spatially incoherent source. In practice, the source need not be infinite. When the source is large enough to effectively produce linear-in-intensity imaging, the imaging system is effectively spatially incoherent. The corresponding image intensity in the spatial frequency domain, $\tilde{I}_{\text{inc}}(f_x)$, is given by

$$\tilde{I}_{\text{inc}}(f_x) = \tilde{I}_{\text{obj}}(f_x)\text{OTF}(f_x) \qquad [9]$$

where $\tilde{I}_{\text{obj}}(f_x)$ is the spatial Fourier transform of the object intensity transmittance and $\text{OTF}(f_x)$ is the incoherent optical transfer function which is proportional to the spatial autocorrelation of the pupil function.

Many texts include detailed discussions comparing the coherent transfer function and the OTF and attempt to make comparisons about the relative performance of coherent and incoherent systems. These comparisons are often misleading since one transfer function describes the wave amplitude spatial frequency transfer function and the other describes the intensity spatial frequency transfer function. Here we note that incoherent imaging systems do indeed allow higher object amplitude spatial frequencies to participate in the image formation process. This argument is often used to support the claim that incoherent systems have higher resolution. However, both systems have the same image intensity spatial frequency cutoff. Furthermore, the nature of the coherent transfer function tends to produce high contrast images that are typically interpreted as higher-resolution images than their incoherent counterparts. Perhaps the real conclusion is that the term resolution is not well defined and direct comparisons between coherent and incoherent imaging must be treated carefully.

The frequency domain treatment for partially coherent imaging of two-dimensional objects involves a four-dimensional spatial frequency transfer function that is sometimes called the bilinear transfer function or the transmission cross-coefficient model. This model describes how constituent object wave amplitude spatial frequencies interact to form image plane intensity frequencies. The utility of this approach to analysis is limited for someone new to the field, but is often used in numerical simulations of partially coherent imaging systems used in optical lithography.

Experimental Examples of Important Coherence Imaging Phenomena

Perhaps the best way to gain an understanding of coherence phenomena in imaging is to examine experimental results. In the following section we use experimental data to see how coherence affects edge response, noise immunity, and depth of field. Several experimental configurations were used to collect the image data, but all of the systems can be represented generically by the Kohler illumination system shown in Figure 12. Kohler illumination is often employed in many projection illumination systems. In order to obtain Kohler illumination, the primary spatially incoherent source is imaged onto the pupil plane of the imaging portion of the system and the object is placed at the pupil plane of the condenser optics.

Primary Source Generation

Figure 13 shows a highly coherent illumination system produced by focusing a laser beam to a point and imaging the focused spot onto the pupil of the imaging system to produce spatially coherent illumination. The use of a laser produces highly temporally coherent light.

Two methods were used to create an extended spatially incoherent primary source with control over the spatial intensity distribution. Figure 14a shows a collimated laser beam with a 633 nm center wavelength illuminating a rotating diffuser. A photographically produced mask defines the spatial shape of the primary source. The laser provides highly temporally coherent light and the diffuser destroys the spatial coherence of the light. Consider the thought experiment of two pinholes placed immediately to the right of the moving diffuser. Without the diffuser, the two wave amplitudes would be highly correlated. Assuming that the diffuser can be modeled as a spatially random phase plate, a fixed diffuser would only introduce a fixed phase difference between the amplitudes leaving the two pinholes and would not destroy the coherence. When the diffuser is rotated, the light from each pinhole encounters a different phase modulation that is changing over time. This random modulation destroys the effective correlation between the wave amplitude of the light leaving the two pinholes provided that the rotation speed is sufficiently fast.



Figure 12 General representation of the Kohler illumination imaging systems used in the experimental result section. The primary incoherent source is imaged onto the imaging system pupil plane and the object resides in the pupil of the condenser optics.



Figure 13 Highly spatially and temporally coherent illumination produced by imaging a focused laser beam into the imaging system pupil.



Figure 14 Two methods for generating a spatially incoherent primary source. (a) An expanded laser beam passes through a moving diffuser followed by a mask to define the extent and shape of the source. (b) A broadband source exits a multifiber lightguide and propagates to a moving diffuser followed by a source mask.

The moving diffuser method is light inefficient but is a practical way of exploring coherence in imaging in a laboratory environment. The choice of the diffuser is critical. The diffuser should spread light out uniformly over an angular subtense that overfills the object of interest. Many commercially available diffusers tend to pass too much light in the straight through direction. Engineered diffusers can be purchased to produce an optimally diffused beam. When quick and inexpensive results are required, thin plastic sheets used in day-to-day packaging often serve as excellent diffusers. When the diffusion angles are not high enough, a number of these plastic sheets can be layered on top of each other to achieve the appropriate angular spread.

The second method for producing a spatially incoherent source is shown in Figure 14b. Broadband light is delivered through a large multifiber lightguide and illuminates a moving diffuser. The main purpose of the diffuser is to ensure that the entire object is illuminated uniformly. The low temporal coherence of the source and the long propagation distances are usually enough to destroy any spatial coherence at the plane of the diffuser. The rotation further ensures that no residual spatial coherence exists at the primary source plane. A chromatic filter centered around 600 nm, with a spectral width of approximately 100 nm, is shown in the light path. The filter was used to minimize the effects of chromatic aberrations in the system. The wide spectral width certainly qualifies as a broadband source in relation to a laser. High-contrast photographically defined apertures determine the spatial intensity distribution at the plane of the primary source. In the following results, the primary source distributions were restricted to circular sources of varying sizes as well as annular sources. These shapes are representative of most of the sources employed in microscopy, machine vision, and optical lithography.

Noise Immunity

Coherent imaging systems are notorious for introducing speckle-like noise artifacts at the image. Dust and optically rough surfaces within an optical system result in a complicated textured image plane intensity distribution that is often called speckle noise. We refer to such effects as coherent artifact noise. Figure 15a shows the image of a standard binary target as imaged by a benchtop imaging system, with the highly coherent illumination method shown in Figure 13. Some care was taken to clean individual lenses and optical surfaces within the system and no dust was purposely introduced. The image is corrupted by a complicated texture that is due in



Figure 15 High temporal coherence imaging with disk sources corresponding to (a) extremely high spatial coherence ($K = 0.05$) and (b) slightly reduced but high spatial coherence ($K = 0.1$).



Figure 16 High spatial coherence disk illumination ($K = 0.1$) imaging through a dust covered surface with (a) narrowband laser illumination and (b) with broadband illumination.

part to imperfections in the laser beam itself and in part to unwanted dust and optically rough surfaces. Certainly, better imaging performance can be obtained with more attention to surface cleanliness and laser beam filtering, but the result shows that it can be difficult to produce high-quality coherent images in a laboratory setting.

Lower temporal coherence and lower spatial coherence will reduce the effect of speckle noise. The image of Figure 15b was obtained with laser illumination according to Figure 14a with a source mask corresponding to a source to pupil diameter ratio of $K = 0.1$. The object plane illumination is still highly temporally coherent and the spatial coherence has been reduced but is still very high. The artifact noise has been nearly eliminated by the modest reduction of spatial coherence. The presence of diagonal fringes in some regions is a result of multiple reflections produced by the cover glass in front of the CCD detector. The reflections produce a weak secondary image that is slightly displaced from the main image and the high temporal coherence allows the two images to interfere.

The noise performance was intentionally perturbed in the image of Figure 16a by inserting a slide with a modest sprinkling of dust at an optical surface in between the object and the pupil plane. The illumination conditions are the same as for the image of Figure 15b. The introduction of the dust has further degraded the image. The image of Figure 16b maintains the same spatial coherence ($K = 0.1$) but employs the broadband source. The lower temporal coherence eliminates the unwanted diagonal fringes but the speckle noise produced by the dust pattern does not improve significantly relative to the laser illumination $K = 0.1$ system. Figures 17a–c show that increasing the source size (and hence the range of angular illumination) reduces



Figure 17 Low temporal coherence imaging through a dust-covered surface with various source sizes and shapes: (a) disk source with $K = 0.3$; (b) disk source with $K = 0.7$; (c) disk source with $K = 2.0$; and (d) a thin annular source with an outer diameter corresponding to $K = 0.5$ and inner diameter corresponding to $K = 0.45$.



Figure 18 Slices of edge intensity images of high contrast edges taken by a laboratory system with low temporal coherence and (a) high spatial coherence (disk source with $K = 0.1$) and (b) effectively incoherent (disk source with $K = 2$).

the spatial coherence and virtually eliminates the unwanted speckle pattern. Finally, Figure 17d shows that an annular source can also provide some noise immunity. The amount of noise immunity is related to the total area of the source rather than the outer diameter of annular source. Seen from the spatial frequency model, each source point produces a noise-corrupted coherent image. Since the effect of the noise is different for each coherent image, the image plane noise averages out as the images add incoherently. This perspective suggests that an extended source provides redundancy in the transfer of object information to the image plane.

Edge Response

Spatial coherence has a strong impact on the images of edges. The sharp spatial frequency cutoff of spatially coherent imaging systems creates oscillations at the images of an edge. Figure 18 shows slices of experimentally gathered edge imagery as a function of the ratio of source diameter to pupil diameter. Higher coherence systems produce sharper edges, but tend to have overshoots. The sharper edges contribute to the sense that high-coherence systems produce higher-resolution images. One advantage to an incoherent imaging system is that the exact location of the edge corresponds to the 50% intensity location. The exact location of an edge in a partially coherent imaging system is not as easily determined. The presence or lack of edge ringing can be used to assess whether a given imaging system can be modeled as spatially incoherent or partially coherent.

Depth of Field

Coherent imaging systems exhibit an apparent increase in depth-of-field compared to spatially incoherent systems. Figure 19 shows spatially incoherent imagery for four different focus positions. Figure 20 shows imagery with the same amount of defocus produced with highly spatially coherent light. Finally, Figure 21 gives an example of how defocused imagery depends on the illumination coherence. The images of a spoke target were all gathered with a fixed amount of defocus and the source size was varied to control the illumination coherence. The images of Figure 21 differ greatly, even though the CPSF was the same for all the cases.

Digital Post-detection Processing and Partial Coherence

The model of Figure 2 suggests that post-detection image processing can be considered as part of the image formation system. Such a general view can result in imaging that might be otherwise unobtainable by classical means. In fact, microscopists routinely use complicated deblurring methods to reconstruct out-of-focus imagery and build up three-dimensional images from multiple image slices.

The coherence of the illumination should be considered when undertaking such image restoration. Rigorous restoration of partially coherent imagery is computationally intensive and requires precise knowledge of the coherence. In practice, a linear-in-intensity model for the image formation is almost always used in developing image restoration algorithms. Even nonlinear restoration algorithms have built-in linear assumptions about the image formation models which imply spatially incoherent illumination.



Figure 19 Spatially incoherent imaging for (a) best focus, (b) moderate misfocus, and (c) high misfocus.

The images of Figures 22a and b are digitally restored versions of the images of Figure 19b and Figure 20b. The point spread function was directly measured and used to create a linear restoration filter that presumed spatially incoherent illumination. The restored image in Figure 22a is faithful since the assumption of spatially incoherent light was reasonable. The restored image of Figure 22b suffers from a loss in fidelity since the actual illumination coherence was relatively high. The image is visually pleasing and correctly conveys the presence of three bar targets. However, the width of the bars is not faithful to the original target which had spacings equal to the widths of the bars.

As discussed earlier, the ideal image is not always the optimal image for a given task. In general, restoration of partially coherent imaging with an implicit spatially incoherent imaging model will produce visually pleasing images that are not necessarily faithful to the object plane intensity. While they are not faithful, they often preserve and even enhance edge information and the overall image may appear sharper than the incoherent image. When end task performance is improved, the image may be considered to be more optimal than the ideal image. It is important to keep in mind that some of the spatial information may be misleading and a more complete understanding of the coherence may be needed for precise image plane measurements. This warning is relevant in microscopy where the user is often encouraged to increase image contrast by reducing illumination spatial coherence. Annular sources can produce highly complicated spatial coherence functions that will strongly impact the restoration of such images.

Summary and Discussion

The coherence of the illumination at the object plane is important in understanding image formation.



Figure 20 High spatial coherence disk source ($K = 0.2$) imaging for (a) best focus, (b) moderate misfocus, and (c) high misfocus.

Highly coherent imaging systems produce high-contrast images with high depth of field and provide the opportunity for sophisticated manipulation of the image with frequency plane filtering. Darkfield imaging and phase contrast imaging are examples of frequency plane filtering. Unfortunately, coherent systems are sensitive to optical noise and are generally avoided in practical system design. Relaxing the temporal coherence of the illumination can provide some improvement, but reducing the spatial coherence is more powerful in combating noise artifacts. Research microscopes, machine vision systems, and optical lithography systems are the most prominent examples of partially coherent imaging systems. These systems typically employ adjustable spatially incoherent extended sources in the shapes of disks or annuli. The exact shape and size of the primary source, shapes the angular extent of the illumination at the object plane and determines the spatial coherence at the object plane. Spatial coherence effects can be significant, even for broadband light. Control over the object plane spatial coherence allows the designer to find a tradeoff between the various strengths and weaknesses of coherent and incoherent imaging systems.

As more imaging systems employ post-detection processing, there is an opportunity to design fundamentally different systems that effectively split the image formation process into a physical portion and a post-detection portion. The simple example of image deblurring cited in this article shows that object plane coherence can affect the nature of the digitally restored image. The final image can be best understood when the illumination coherence effects are well understood. The spatially incoherent case results in the most straightforward model for image interpretation, but is not always the best choice since the coherence can often be manipulated to increase the contrast and hence the amount of useful information in the raw image. A completely general approach to



Figure 21 Imaging with a fixed amount of misfocus and varying object spatial coherence produced by: (a) highly incoherent disk source illumination ($K = 2$); (b) moderate coherence disk source ($K = 0.5$); (c) high coherence disk source ($K = 0.2$); and (d) annular source with outer diameter corresponding to $K = 0.5$ and inner diameter corresponding to $K = 0.45$.



Figure 22 Digital restoration of blurred imagery with an inherent assumption of linear-in-intensity imaging for (a) highly spatially incoherent imaging ($K = 2$) and (b) high spatial coherence ($K = 0.2$).

imaging would treat the coherence of the source, the imaging optics, and the post-detection restoration all as free variables that can be manipulated to produce the optimal imaging system for a given task.

See also

Coherent Lightwave Systems. **Information Processing:** Coherent Analogue Optical Processors. **Terahertz Technology:** Coherent Terahertz Sources.

Further Reading

Bartelt H, Case SK and Hauck R (1982) Incoherent Optical Processing. In: Stark H (ed.) *Applications of Optical Fourier Transforms*, pp. 499–535. London: Academic Press.

Born M and Wolf E (1985) *Principles of Optics*, 6th edn. (corrected), pp. 491–554. Oxford, UK: Pergamon Press.

Bracewell RN (1978) *The Fourier Transform and its Applications*. New York: McGraw Hill.

Gonzales RC and Woods EW (1992) *Digital Image Processing*, 3rd edn., pp. 253–304. Reading, MA: Addison-Wesley.

Goodman JW (1985) *Statistical Optics*, 1st edn. New York: John Wiley & Sons.

Goodman JW (1996) *Introduction to Fourier Optics*, 2nd edn. New York: McGraw Hill.

Hecht E and Zajac A (1979) *Optics*, 1st edn., pp. 397–435, Reading, MA: Addison-Wesley.

Inoue S and Spring KR (1997) *Video Microscopy*, 2nd edn. New York: Plenum.

Reynolds GO, DeVelis JB, Parrent GB and Thompson JB (1989) *Physical Optics Notebook: Tutorials in Fourier Optics*, 1st edn. New York: SPIE, Bellingham and AIP.

Saleh BEA and Teich MC (1991) *Fundamentals of Photonics*, pp. 343–381. New York: John Wiley & Sons.

Speckle and Coherence

G Häusler, University of Erlangen-Nürnberg,
Erlangen, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Opticists are aware that the amount of coherence plays a significant role in imaging systems: laser speckles are known to add significant noise to the image, as well as parasitic interferences from dusty lenses. Optical systems are often called coherent, if a laser is used (right), and incoherent if other sources come into play (wrong). Many users of optical systems are unaware that it is not the high temporal coherence but the spatial coherence that commonly afflicts the image quality, and that this parasitic spatial coherence is ubiquitous, even though not obvious. Coherent artifacts can occur without the use of lasers, although speckle noise is more prominent with lasers. Even opticists sometimes underestimate the damage that residual coherent noise can cause, and as laser oriented sensor funding programs are 'en vogue', nonexperts are disappointed if some metrology device does not include a laser.

This encyclopedia addresses the many uses of lasers. In this article, we will discuss the costs of coherence. The commonly pretended incoherent approach of everyday optics may lead to significant quantitative measuring errors of illumination or reflectivity, 3d shape, distance or size. Spatial coherence is the dominant source of noise. We will give some rules of thumb to estimate these errors and a few tricks to reduce coherent noise. These rules will help to minimize coherent noise, however, it turns out that as spatial coherence is ubiquitous, there are only limited options available to clear it. One of the options to build good sensors that measure shape, reflectivity, etc. is avoiding the use of lasers!

To become familiar with some basics of the theory of coherence we refer the reader the Further Reading section at the end of this article.

Coherence can be boon or disaster for the opticist, as is explained in other articles of this encyclopedia about interferometry, diffraction, and holography. A specific topic is information acquisition from coherently scattered light. An enlightening example is where speckles in white light interferometry at rough surfaces and in speckle interferometry are exploited. We will briefly discuss white light interferometry at rough surfaces in the section on speckles as carriers of information below.

Practical Coherence Theory

A major issue of this chapter will be corrupting properties of coherence in the daily life of an optical metrologist. We will demonstrate that 'speckle' noise is ever present, and essentially unavoidable, in the images of (diffusively reflecting) objects. Its influence on the quality of optical measurements leads to a lower limit of the physical measuring uncertainty.



Figure 1 Ground glass in sunlight: (a) the image of a ground glass, illuminated by the sun, observed with small aperture (from large distance), displays no visible speckles; (b) a medium observation aperture (smaller distance) displays weak visible speckles; (c) observation with very high aperture displays strong contrast speckles; and (d) the image of the ground glass on a cloudy day does not display speckles, due to the very big aperture of illumination. Reproduced with permission from Häusler G (1999) Optical sensors and algorithms for reverse engineering. In: Donah S (ed.) Proceedings of the 3rd Topical Meeting on Optoelectronic Distance/Displacement Measurements and Applications. IEEE-LEOS.

This ‘coherent noise’ limit is, not surprisingly, identical to Heisenberg’s limit. We will start by summarizing the important results, and will give some simple explanations later.

Some Basic Observations

(i) The major source of noise in optical measurements is spatial coherence, the temporal coherence status, generally, does not play a significant role.
(ii) An optically rough surface displays subjective speckles with contrast $C = 1$, if the observation aperture $\sin u_o$ is larger than the illumination aperture $\sin u_q$.
(iii) The speckle contrast is $C \sim \sin u_q / \sin u_o$, if the observation aperture is smaller than the illumination aperture.

Figure 1 illustrates the situation by a simple experiment.

The results of Figure 1 can be explained simply by summarizing some 80 pages of coherence theory in a nutshell, by useful simplifications and approximations (Figure 2).



Figure 2 Basic experiment for spatial coherence. An extended source, such as the sun or some incandescent lamp illuminates a double slit, from a large distance. On a screen behind the double slit we can observe ‘double slit interference’, if the waves coming from x_1 and x_2 display coherence. The contrast of the interference fringes is given by the magnitude of the coherence function Γ (neglecting some normalization factor). Γ is a function of the two slit locations x_1 and x_2.

If the source is at an infinite distance, the coherence function no longer depends on the two variables but just on the slit distance $d = |x_1 - x_2|$. In this case, the coherence function $\Gamma(d)$ can be easily calculated as the Fourier transform of the spatial intensity distribution of the source (van Cittert-Zernike theorem). Let us assume a one dimensional source with an angular size of $2u_q$, where u_q is commonly called the aperture of the illumination. In this case, the coherence function will be:

$$\Gamma(d) \sim \sin c(2u_q d/\lambda) \qquad [1]$$

The width of the coherence function which gives the size of the coherently illuminated area (coherence area) can be approximated from eqn [1]:

$$d_\Gamma = \lambda / u_q \qquad [2]$$

Equation [1] includes some approximations: for circular sources such as the sun, we get an additional factor 1.22 for the width of the coherence function – the ‘sinc-function’ has to be replaced by the Bessel function $J_1(r)/(r)$. There is another approximation: we should replace the aperture angle u_q by $\sin u_q$, for larger angles. We choose the wavelength of the maximum sensitivity of the eye, at $\lambda = 0.55\ \mu\text{m}$, which is the wavelength of the maximum emission of the sun also.

In conclusion, if two points at the object are closer than d_Γ these points will be illuminated with a high degree of coherence. The light waves, scattered from these object-locations can display interference contrast. Specifically, they may cancel each other out, causing a low signal-to-noise ratio of only 1:1. This does not happen if the points have a distance larger than d_Γ.

From Figure 3 we learn that the width of the spatial coherence function from sunlight illumination at the earth’s surface is ~110 μm. (Stars more distant than the sun appear smaller, and hence have a wider coherence function, at the earth’s surface. Michelson was able to measure the angular size of some close stars, by measuring the width of this coherence function, which was about $d_\Gamma \sim 10$ m.)

Figure 4 again displays an easy to perform experiment. We can see speckles at sunlight illumination. We can observe speckles as well in shops because they often use small halogen spot illumination.

So far we have only discussed the first stage (from the source to the object). We still have to discuss the way from the object to the retina (or CCD-chip of a video camera). This is illustrated by Figure 5.


Two points are illuminated coherently,
as far as their distance is smaller than d_Γ.
$d_\Gamma = \lambda/u_q$
Example: sun ill. at earth $u_q = 0.005$ und $d_\Gamma = 110$ μm
Coherence function
Sun
$2u_q$
$d_\Gamma \sim 110$ μm
Earth

Figure 3 Coherence from sunlight illumination. With the van Cittert–Zernike theorem and an approximate illumination aperture of the sun $u_q^{\text{sun}} \sim 0.005$ (0.25°), we get a width of the coherence function at the Earth’s surface of about $d_\Gamma \sim 110\ \mu\text{m}$.



Figure 4 Finger nail in sunlight, with speckles.


Γ(d)
psf
u_q
u_o
Source
Ground glass
Observer
• Width of coherence function at ground glass: $d_\Gamma = \lambda/u_q$
• Distance, resolvable by observer: $d_o = \lambda/u_o$
Coherence for $u_o > u_q$
Speckle

Figure 5 Coherence in a nutshell: spatial coherence and observer.

As an object, we choose some diffusely reflecting or transmitting surface (such as a ground glass). The coherence function at the ground glass has again a width of d_Γ. What happens if we image this ground glass onto our retina? Let us assume our eye to be diffraction limited (which, in fact, it is at sunlight conditions, where the eye pupil has only a diameter $\Phi_{\text{pupil}} = 2.5$ mm diameter or less). Then a point x_1 at the ground glass will cause a diffraction spot at the retina, with a size of:

$$d'_{\text{diffr}} = \lambda/u'_{\text{o}} = 8\ \mu\text{m} \qquad [3]$$

The image sided aperture of observation u'_0 of the eye is calculated from Φ_{pupil} and from its focal length $f_{\text{eye}} = 18$ mm as $u'_{\text{o}} = \Phi_{\text{pupil}}/2f_{\text{eye}} = 0.07$. If we project the diffraction spot at the retina back onto the object, we get its size d from:

$$d_{\text{diffr}} = \lambda/u_{\text{o}} = \lambda/(\Phi_{\text{pupil}}/2z_{\text{o}}) \qquad [4]$$

with z_{o} = observation distance of the object from the eye. We call $u_{\text{o}} = \Phi_{\text{pupil}}/2z_{\text{o}}$ the object sided observation aperture. Let us calculate the laterally resolvable distance d_{diffr} at the object, with a distance $z_{\text{o}} = 250$ mm, which is called the ‘comfortable viewing distance’:

$$d_{\text{diffr}}(z_{\text{o}} = 250\ \text{mm}) = 110\ \mu\text{m} \qquad [5]$$

After these preparations we come to the crucial issue: how does the image at the retina appear if we cannot resolve distances at an object smaller than d_Γ, and how does it appear if the resolution of the eye is sufficient to resolve distances smaller than d_Γ?

Let us start with the first assumption: $d_{\text{diffr}} \gg d_\Gamma$. Now the images of points at the object, over an area of the diffraction spot are more or less incoherently averaged at the retina, so we will see little interference contrast or ‘speckles’. From eqn [4] we see that at this incoherent averaging starts for distances larger than 250 mm, which is the comfortable viewing distance. Adults cannot see objects from much closer distances. We generally do not see speckles, not just at the limit of maximum accommodation. For larger distances, if we take $z_o = 2500$ mm, the resolvable distance at the object will be 1.1 mm, which is 10 times larger than the diameter of the coherence area. Averaging over such a large area will drop the interference contrast by a factor of 10. Note that such a small interference contrast might not be visible, but it is not at zero!

Coming to the second assumption we can laterally resolve distances smaller than d_Γ. In order to understand this, we first have to learn what is an 'optically rough' object surface. Figure 6 illustrates the problem.

A surface commonly is called 'rough' if the local height variations are larger than λ. However, a surface appears only rough, if the height variation within the distance that can be resolved by the observer, is larger than λ (reflected light will travel the distance twice, hence a roughness of $\lambda/2$ will be sufficient). Then the scattered different phasors, or 'Huygens elementary waves':

$$u_s \sim \exp[i2kz(x, y)] \qquad [6]$$

scattered from the object at x, y may have big phase differences so that destructive interferences (and speckle) can occur in the area of the diffraction image. So the attribute 'rough' depends on the object as well as on the observation aperture. With a high observation aperture (microscope), the diffraction image is small and within that area the phase differences might be small as well. So a ground glass may then look locally like a mirror, while with a small observation aperture it appears 'rough'.

With the 'rough' observation mode assumption, we can summarize what we have assumed: with resolving distances smaller than the coherence width d_Γ we will see high interference contrast; in fact we see a speckle contrast of $C = 1$, if the roughness of the object is smaller than the coherence length of the source. This is the case for most metal surfaces, for ground glasses, or for worked plastic surfaces. The assumption is not true for 'translucent' surfaces, such as skin, paper, or wood. This will be discussed below.

The observation that coherent imaging is achieved, if we can resolve distances smaller than the coherence width d_Γ, is identical to the simple rule that fully coherent imaging occurs if the observation aperture u_o is larger than the illumination aperture u_q.

As mentioned, we will incoherently average in the image plane, over some object area, determined by the size of the diffraction spot. According to the rules of speckle-averaging, the speckle contrast C decreases with the inverse square root of the number N of incoherently averaged speckle patterns. This number N is equal to the ratio of the area A_{diff} of the diffraction spot divided by the coherence area $A_\Gamma = d_\Gamma^2$. So we obtain for the speckle contrast C:

$$C = 1 \quad \text{for } u_q < u_o \qquad [7a]$$

$$C = 1/\sqrt{(N)} = u_o/u_q, \quad \text{for } u_q >= u_o \qquad [7b]$$

We summarize the results in Figure 7.

Equation [7b] has an interesting consequence: we never get rid of speckle noise, even for large illumination apertures and small observation apertures. In many practical instruments, such as a slide projector, the illumination 'aperture stop' cannot be greater than the imaging lens. Fortunately, the observer's eye commonly has a pupil smaller than that of the projector, and/or looks from a distance at the projection screen. Laser projection devices however cause strong and disturbing speckle effects for the user and significant effort is invested to cope with this effect.



Elementary phasors have phase differences bigger than +/– 180°. Destructive interference may occur.

Figure 6 What is a rough surface?



Figure 7 Coherence in a nutshell: what are the conditions for incoherent and coherent imaging?



Figure 8 Microfiche projection. For high observation aperture (a) strong speckles occur, and for small observation aperture (b), the speckle contrast is low.

In Figure 8, an image is depicted from a microfiche reading projector. Figure 8a displays the close-up look (high observation aperture) and Figure 8b depicts a more distant view (small observation aperture). The amount of noise is much less in the second case, as it should be according to the rules of eqn [7].

Let us finish this section with some speculation. How would a fly see the sunny world, with a human type of eye? With high observation aperture and at short distance, the world is full of speckle noise. Fortunately, nature invented the facet-eye, for insects, as depicted in Figure 9.



Figure 9 Facet eye and 'human' eye. The facet eye consists of many low aperture lenses, in contrast to the human eye.

Speckle Limits of Metrology

The consequences of the effects discussed above are often underestimated. We should be suspicious, if some effect in nature that disturbs us – like our coherent noise – is ubiquitous, that there might be some deep underlying principle that does not allow us to know everything about the object under observation. Indeed, it turns out that Heisenberg's uncertainty principle is strongly connected with coherent noise (Figure 10).

We can see this from the following experiment: a laser spot is projected onto a ground glass, and imaged with high magnification by a video camera, with an aperture sin u_o. The ground glass is macroscopically planar. When the ground glass is laterally shifted, we find that the observed spot is 'dancing' at the video target. Its observed position is not constant, although its projected position is. It turns out that the standard deviation of the observed position is equal to the uncertainty calculated from the aperture by Heisenberg's principle.



Figure 10 Coherence makes it impossible to localize objects with very high accuracy. Laser spots projected onto a ground glass cannot be imaged without some uncertainty of the lateral position. The four pictures of the spot images, taken with different lateral positions of the ground glass, display the cross bar (true position) and the apparent position of the spot images. The position uncertainty is equal to the uncertainty calculated from Heisenberg's uncertainty principle.

We can calculate the limit for the distance measuring uncertainty, from speckle theory, as well from Heisenberg's principle (within some factor of order 1):

$$\delta z \cdot \delta p_z \gg h/4\pi \qquad [8]$$

where δp_z is the uncertainty of the photon impulse h/λ in the z-direction (along the optical axis of the measuring system) and h is Planck's constant. For a small measurement uncertainty of the distance, we should allow a big uncertainty δp_z. This can be achieved by a large aperture of the observation system, giving the photons a wide range of possible directions to the lens. We can also allow different wavelengths, and come to white light interferometry, see section on speckles as carriers of information below. The result is – not surprising – the same as Rayleigh scattering found for the depth of field:

$$\delta z = \lambda / \sin^2 u_o \qquad [9]$$

Coherent noise is the source of the fundamental limit of the distance measuring uncertainty δz of triangulation based sensors.

$$\delta z = C \cdot \lambda / (\sin u_o \sin \theta) \qquad [10]$$

where C is the speckle contrast, λ is the wavelength, $\sin u_o$ is the aperture of observation, and θ is the angle of triangulation (between the direction of the projection and the direction of observation). For a commercially available laser triangulation sensor, (see Figure 11), with $\sin u_o \sim 0.01, C = 1$ and $\theta = 30°$, the measuring uncertainty δz will be larger than 100 μm. We may add, that for $\sin u_o = \sin \theta$, which is valid for auto-focus sensors (such as the confocal scanning microscope), eqn [10] degenerates to the well known Rayleigh depth of field (eqn [9]).

The above results are remarkable in that we cannot know the accurate position of the projected spot or about the position of an intrinsic reflectivity feature; we also cannot know the accurate local reflectivity of a coherently illuminated object. A further consequence is that we do not know the accurate shape of an object in 3D-space. We can calculate this ‘physical measuring uncertainty’ from the considerations above.

These consequences hold for optically rough surfaces, and for measuring principles that exploit the local intensity of some image, such as with all triangulation type of sensors. The consequences of these considerations are depressing: triangulation with a strong laser is not better than triangulation with only one single photon. The deep reason is, that all coherent photons stem from the same quantum mechanical phase cell and are indistinguishable. Hence, many photons do not supply more information than one single photon.



Figure 11 Principle of laser triangulation. The distance of the projected spot is calculated from the location of the speckled spot image and from the angle of triangulation. The speckle noise introduces an ultimate limit of the achievable measuring uncertainty. Reproduced with permission from *Physikalische Plätter* (May 1997): 419.

Why Are We Not Aware of Coherence

Generally, coherent noise is not well visible, even in sophisticated technical systems the visibility might be low. There are two main reasons; first, the observation aperture might be much smaller than the aperture of illumination. This is often true, for large distance observation, even with small apertures of illumination. The second reason holds for technical systems, if the observation is implemented via pixelized video targets. If the pixel size is much larger than a single speckle, which is commonly so, then, by averaging over many speckles, the noise is greatly reduced. However, we have to take into account that we pay for this by loss of lateral resolution $1/\delta x$. We can formulate another uncertainty relation:

$$\delta x > \lambda / (C \cdot \sin u_o) \qquad [11]$$

which says that if we want to reduce the speckle contrast C (noise), by lateral averaging, we can do this but lose lateral resolution $1/\delta x$.

Can We Overcome Coherence Limits?

Since the daily interaction of light with matter is coherent scattering, we can overcome the limit of eqn [10] only by looking for measuring principles that are not based on the exploitation of local reflectivity, i.e., on ‘conventional imaging’. Concerning optical 3D-measurements, the principle of triangulation uses the position of some image detail, for the calculation of the shape of objects, and has to cope with coherent noise.

Are there different mechanisms of photon–matter interaction, with noncoherent scattering? Fluorescence and thermal excitation are incoherent mechanisms. It can be shown (see Figure 12) that triangulation utilizing fluorescent light, displays much less noise than given by eqn [10]. This is exploited in fluorescent confocal microscopy.

Thermally excited matter emits perfectly incoherent radiation as well. We use this incoherence to measure the material wear in laser processing (see Figure 13), with, again, much better accuracy than given by eqns [9,10].

The sensor is based on triangulation. Nevertheless, by its virtually zero coherent noise, it allows a measuring uncertainty which is limited only by camera noise and other technical imperfections. The uncertainty of the depth measurement through the narrow aperture of the laser nozzle is only a few



Figure 12 Reduction of speckle noise by triangulation with fluorescent light. A flat metal surface is measured by laser triangulation. Top: surface measured by laser triangulation with full speckle contrast. Bottom: the surface is covered with a very thin fluorescent layer, and illuminated by the same laser, however, the triangulation is done after suppressing the scattered laser light, and utilizing the (incoherent!) fluorescent light. This experiment proves that it is the coherent noise that causes the measuring uncertainty.



Figure 13 A 100 W laser generates a plasma that emits perfectly incoherent radiation at the object surface. The emitted light can be used to measure on-line the distance of the object surface. A triangulation sensor, exploiting the incoherent plasma emission, controls surface ablation with an accuracy of only a few microns. Reproduced with permission from F & M, *Feinwerktechnik Mikrotechnik Masstechnik* (1995) Issue 9.

microns, beating the limitation of eqn [10] by a factor of about 5, even in the presence of a turbulent plasma spot with a temperature of 3000 K.

Broadband Illumination

Speckle noise can hardly be avoided by broadband illumination. The speckle contrast C is related to the surface roughness σ_z and the coherence length l_c by eqn [12]:

$$C^2 \sim l_c/2\sigma_z \quad \text{for} \quad \sigma_z \gg l_c \qquad [12]$$

So, only for very rough surfaces, and white light illumination, C can be reduced. However, the majority of technical objects is smooth, with a roughness of a few micrometers, hence speckles can be observed even with white light illumination ($l_c \sim 3$ µm). This situation is different for 'translucent' objects such as skin, paper, or some plastic material.

Speckles as a Carrier of Information

So far we discussed the problems of speckles when measuring rough surfaces. We can take advantage of speckles, if we do not stick to triangulation as the basic mechanism of distance measurement. We may utilize the fact that although the phase within each speckle has a random value, this phase is constant over some area. This observation can be used to build an interferometer that works even at rough surfaces. So, with proper choice of the illumination aperture and observation aperture, and with a surface roughness less than the coherence length, we can measure distances by the localization of the temporal coherence function. This function can easily be measured by moving the object under test along the optical axis and measuring the interference intensity (correlogram) at each pixel of the camera. The signal generating mechanism of this 'white light interferometer' distance measurement is not triangulation but 'time of flight'. Here we do not suffer from the limitations of eqn [10]. The limits of white light rough surface interferometry are discussed in the Further Reading section at the end of this article.

The 'coherence radar' and the correlograms of different speckles are depicted in Figures 14 and 15.

The physical mechanism of the signal formation in white light interferometry at rough surfaces is different from that of white light interferometry at smooth surfaces. That is why the method is sometimes referred as 'coherence radar'. We will briefly summarize some advantageous, and – probably unexpected – features of the coherence radar.

We call the real shape of the object, or the surface profile, $z(x, y)$, where z is the local distance at the position (x, y). We give the measured data an index 'm^2':

(i) The physical measuring uncertainty of the measured data is independent from the observation aperture. This is quite a remarkable property, as it enables us to take accurate measurements at the bottom of deep boreholes.

(ii) The standard deviation σ_z of the object can be calculated from the measured data z_m: $\sigma_z = <|z_m|>$. According to German standards, σ_z corresponds to the roughness measure R_q.

    This measure R_q was calculated from measurements at different roughness gauges, with different observation apertures. Two measurements are depicted in Figure 16.

The experiments shown in Figure 16 display the correct roughness measure, even if the higher frequencies of the object spectrum $Z(\nu, \mu)$ (Figure 17), are not optically resolved. The solution of this paradox might be explained as follows.

From the coherently illuminated object each point scatters a spherical wave. The waves scattered from different object points have, in general, a different phase. At the image plane, we see the laterally



Figure 14 'Coherence radar', white light interferometry at rough surfaces. The surface under test is illuminated with high spatial coherence and low temporal coherence. We acquire the temporal coherence function (correlogram) within each speckle, by scanning the object under test in depth.



Figure 15 White light speckles in the $x-z$ plane. The left side displays the acquired correlograms, for a couple of speckles, the right side shows the graphs of some of the correlograms. We see that the correlograms are not located at a constant distance, but display some 'distance uncertainty'. This uncertainty does not originate from the instrument, but from the roughness of the object.



Figure 16 Optical measurement of the roughness beyond the Abbe resolution limit. The roughness is measured for 4 roughness standards N1–N4, with different observation apertures. The roughness is measured correctly, although the microtopology is not resolved by the observing optics.


Surface
$z(x, y)$
x
$\sigma_z > \lambda/2$
Diameter d_B of the diffraction psf of the observing optics
Spectrum
$Z(\nu, \mu)$
??
ν
$1/d_B$ Bandlimit of the optical system

Figure 17 Signal generation beyond the Abbe limit. The microtopology of the object $z(x, y)$ is not resolved, due to the large diffraction image with diameter d_B. Yet we get information from beyond the bandlimit $1/d_B$ of the observing optics.

averaged complex amplitude $<u>$, according to eqn [6]. The averaging is due to the diffraction limited resolution.

Equation [6] reveals that the (spatially) averaged field amplitude $<u>$ is a nonmonotonic, nonlinear function of the surface profile $z(x, y)$, if the surface is rough (i.e., $z \gg \lambda$). We do not average over the profile z but over the complex amplitude. As a consequence of this nonlinearity, the limited observation aperture does not only collect the spatial frequencies ν, μ of the spatial Fourier spectrum $Z(\nu, \mu)$ within the bandlimit $1/d_B$, but also acquires information beyond this bandlimit. The reason is the 'down conversion' of higher spatial frequencies by nonlinear mixing. Simulations and experiments confirm the consequences.

Thus we can evaluate the surface roughness, even without laterally resolving the microtopology. However, there is a principal uncertainty on the measured data. We do not see the true surface but a surface with a 'noise' equivalent to the roughness of the real surface.

Nonlinear nonmonotonic nonlinearities in a sequence of operations may cause 'chaotic' behavior, in other words, small parameter changes such as vibrations, humidity on the surface, etc. may cause large differences of the outcome. In fact, we observe a significant variation of the measured data $z_m(x, y)$ within a sequence of repeated measurements. Our conjecture is that the complex signal formation may be involved in this irregular behavior. The hypothesis may be supported by the observation that much better repeatability can be achieved at specular surfaces, where eqn [6] degenerates to a linear averaging over the surface profile:

$$<u> \sim 1 + ik <z(x, y)>, \quad \text{for } z \ll \lambda \qquad [13]$$

Summary

Spatial coherence is ubiquitous and unavoidable. Spatial coherence disturbs most optical measurements, where optically rough surfaces exist. Then, coherence gives the ultimate limit of the achievable measuring uncertainty. There are simple rules to estimate the measuring uncertainty, by calculating the width of the coherence function and the resolution of the observation system. Spatial coherence and Heisenberg's uncertainty principle lead to the same results of measuring uncertainty.

On the other hand – the formation of signals from coherent light that is scattered at rough surfaces is quite complex and a strongly nonlinear process, which sometimes might encode information which is not otherwise available. One example appears to be the measurement of the roughness with white light interferometry – which is possible, even if the microtopology of the surface is not optically resolved.

See also

Coherence: Overview; Coherence and Imaging.

Further Reading

Born M and Wolf E (1999) *Principles of Optics*, 7th edn. Cambridge: Cambridge University Press.

Brooker G (2003) *Modern Classical Optics*. Oxford: Oxford University Press.

Dainty JC (ed.) (1984) *Laser Speckle and Related Phenomena*. Berlin, Heidelberg, New York: Springer Verlag.

Dorsch R, Herrmann J and Häusler G (1994) Laser triangulation: fundamental uncertainty in distance measurement. *Applied Optics* 33: 1306–1314.

Dresel T, Venzke H and Häusler G (1992) 3D-sensing of rough surfaces by coherence radar. *Applied Optics* 31: 919–925.

Ettl P (2002) *Über die Signalenstehung bei Weisslichtinterferometrie*. PhD Dissertation, University of Erlangen-Nürnberg.

Häusler G, Ettl P, Schenk M, Bohn G and Laszlo I (1999) Limits of optical range sensors and how exploit them. In: Asakura T (ed.) *Trends in Optics and Phototonics*. Ico IV, Springer Series in Optical Sciences, vol. 74, pp. 328–342. Berlin, Heidelberg, New York: Springer Verlag.

Häusler G and Herrmann J (1992) Physical limits of 3D-sensing. Proceedings of the SPIE Conf. 1822. In: Svetkov D (ed.) *Optics, Illumination, and Image Sensing for Machine Vision VII*, pp. 150–158. Boston, MA: SPIE.

Klein M and Furtak TE (1986) *Optics*. New York: John Wiley & Sons.

Klinger P, Spellenberg B, Herrmann JM and Häusler G (2001) *In Process 3D-Sensing for Laser Material Processing*. Proceedings of Third Int. Conf. on 3-D Digital Imaging and Modeling, Quebec City, Canada. Los Alamitos: IEEE Computer Society, 38–41.

Pedrotti F and Pedrotti L (1993) *Introduction to Optics*, 2nd edn. New Jersey: Prentice Hall.
Pérez J-Ph (1996) *Optik, Spektrum Akademischer*. Heidelberg: Verlag.
Sharma A, Kandpal HC and Ghatak AK (2004) *Optical Coherence*. See this Encyclopedia.
van de Gracht (2004) *Coherence and Imaging*. See this Encyclopedia.
Young M (1993) *Optics and Lasers, Including Fibers and Optical Wave Guides*, 4th revised edn. Berlin, Heidelberg: Springer Verlag.

COHERENT CONTROL

Contents

Theory
Experimental
Applications in Semiconductors

Theory

H Rabitz, Princeton University, Princeton, NJ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Since the inception of quantum mechanics almost a century ago, a prime activity has been the observation of quantum phenomena in virtually all areas of chemistry and physics. However, the natural evolution of science leads to the desire to go beyond passive observation to active manipulation of quantum mechanical processes. Achieving control over quantum phenomena could be viewed as engineering at the atomic scale guided by the principles of quantum mechanics, for the alteration of system properties or dynamic behavior. From this perspective, the construction of quantum mechanically operating solid-state devices through selective material growth would fall into this category. The focus of this article is principally on the manipulation of quantum phenomena through tailored laser pulses. The suggestion of using coherent radiation for the active alteration of microworld processes may be traced to the early 1960s, almost immediately after the discovery of lasers. Since then, the subject has grown enormously to encompass the manipulation of (1) chemical reactions, (2) quantum electron transport in semiconductors, (3) excitons in solids, (4) quantum information systems, (5) atom lasers, and (6) high harmonic generation, amongst other topics. Perhaps the most significant use of these techniques may be their provision of refined tools to ultimately better understand the basic physical interactions operative at the atomic scale.

Regardless of the particular application of laser control over quantum phenomena, there is one basic operating principle involved: active manipulation of constructive and destructive quantum wave interferences. This process is depicted in Figure 1, showing the evolution of a quantum system from the initial state $|\psi_i\rangle$ to the desired final state $|\psi_f\rangle$ along three of possibly many interfering pathways. In general, there may be many possible final accessible states $|\psi_f\rangle$, and often the goal is to achieve a high amplitude in one of these states and low amplitude in all the others. The target state might actually be a superposition of states, and an analogous picture to



Figure 1 The evolution of a quantum system under laser control from the initial state $|\psi_i\rangle$ to the final state $|\psi_f\rangle$. The latter state is chosen to have desirable physical properties, and three of possibly many pathways between the states are depicted. Successful control of the process $|\psi_i\rangle \rightarrow |\psi_f\rangle$ by a tailored laser pulse generally requires creating constructive quantum wave interferences in the state $|\psi_f\rangle$ from many pathways, and destructive interferences in all other accessible final states $|\psi_{f'}\rangle \neq |\psi_f\rangle$.

that in Figure 1 would also apply to steering about the density matrix. The process depicted in Figure 1 may be thought of as a microscale analog of the classic double-slit experiment for light waves. As the goal is often high-finesse focusing into a particular target quantum state, success may call for the manipulation of many quantum pathways (i.e., the notion of a 'many-slit' experiment). Most applications are concerned with achieving a desirable outcome for the expectation value $\langle\psi_f|O|\psi_f\rangle$ associated with some observable Hermitian operator O.

The practical realization of the task above becomes a control problem when the system is expressed through its Hamiltonian $H = H_0 + V_c$, where H_0 is the free Hamiltonian describing the dynamics without explicit control; it is assumed that the free evolutionary dynamics under H_0 will not satisfactorily achieve the physical objective. Thus, a laboratory-accessible control term V_c is introduced in the Hamiltonian to achieve the desired manipulation. Even just considering radiative interactions, the form of V_c could be quite diverse depending on the nature of the system (e.g., nuclear spins, electrons, atoms, molecules, etc.) and the intensity of the radiation field. Many problems may be treated through an electric dipole interaction $V_c = -\boldsymbol{\mu}\cdot\boldsymbol{\varepsilon}(t)$ where $\boldsymbol{\mu}$ is a system dipole moment and $\boldsymbol{\varepsilon}(t)$ is the laser electric field. Where appropriate, this article will consider the interaction in this form, but other suitable radiative control interactions may be equally well treated. Thus, the laser field $\boldsymbol{\varepsilon}(t)$ as a function of time (or frequency) is at our disposal for attempted manipulation of quantum systems.

Before considering any practical issues associated with the identification of shaped laser control fields, a fundamental question concerns whether it is, in principle, possible to steer about any particular quantum system from an arbitrary initial state $|\psi_i\rangle$ to an arbitrary final state $|\psi_f\rangle$. Questions of this sort are addressed by a controllability analysis of Schrödinger's equation

$$i\hbar\frac{\partial|\psi(t)\rangle}{\partial t} = [H_0 - \boldsymbol{\mu}\cdot\boldsymbol{\varepsilon}(t)]|\psi(t)\rangle, \quad |\psi(0)\rangle = |\psi_i\rangle \qquad [1]$$

Controllability concerns whether, in principle, some field $\boldsymbol{\varepsilon}(t)$ exists, such that the quantum system described by $H_0 = H_0 - \boldsymbol{\mu}\cdot\boldsymbol{\varepsilon}(t)$ permits arbitrary degrees of control. For finite-dimensional quantum systems (i.e., those described by evolution amongst a discrete set of quantum states), the formal tools for such a controllability analysis exist both for evaluating the controllability of the wave function, as well as the more general time evolution operator $U(t)$, which satisfies

$$i\hbar\frac{\partial U}{\partial t} = [H_0 - \boldsymbol{\mu}\cdot\boldsymbol{\varepsilon}(t)]U, \quad U(0) = 1 \qquad [2]$$

Analyses of this type can be quite insightful, but they require detailed knowledge about H_0 and $\boldsymbol{\mu}$. Cases involving quantum information science applications are perhaps the most demanding with regard to achieving total control. Most other physical applications would likely accept much more modest levels of control and still be categorized as excellent achievements.

Theoretical tools and concepts have a number of roles in considering the control of quantum systems, including (1) an exploration of physical/chemical phenomena under active control, (2) the design of viable control fields, (3) the development of algorithms to actively guide laboratory control experiments towards achieving their dynamical objectives, and (4) the introduction of special algorithms to reveal the physical mechanisms operative in the control of quantum phenomena. Activities (1)–(3) have thus far been the primary focus of theoretical studies in this area, and it is anticipated that item (4) will grow in importance in the future.

A few comments on the history of laser control over quantum systems are relevant, as they speak to the special nature of the currently employed successful closed-loop quantum control experiments. Starting in the 1960s and spanning roughly 20 years, it was thought that the design of lasers to manipulate molecular motion could be achieved by the application of simple physical logic and intuition. In particular, the thinking at the time focused on using cw laser fields resonant with one or more local modes of the molecule, as state or energy localization was believed to be the key to successful control. Since quantum dynamics phenomena typically occur on ultrafast time-scales, possibly involving spatially dispersed wave packets, expecting to achieve high quality control with a light source operating at one or two resonant frequencies is generally wishful thinking. Quantum dynamics phenomena occur in a multifrequency domain, and controls with a few frequencies will not suffice. Over approximately the last decade, it became clear that successful control often calls for manipulating multiple interfering quantum pathways (cf., Figure 1). In turn, this recognition led to the need for broad-bandwidth laser sources (i.e., tailored laser pulses). Fortunately, the necessary laser pulse-shaping technologies have become available, and these sources continue to expand into new frequency ranges with enhanced bandwidth capabilities. Many chemical and physical applications of control over quantum phenomena involve performing a significant amount of work (i.e., quantum mechanical action), and sufficient laser field intensity is required. A commonly quoted adage is 'no field, no yield', and at the other extreme, there was much speculation that operating nonlinearly at high field intensities would lead to a loss of control because the quantum system would effectively act as an amplifier of even weak laser field noise. Fortunately, the latter outcome has not occurred, as is evident from a number of successful high field laser control experiments.

Quantum control may be expressed as an inverse problem with a prescribed chemical or physical objective, and the task being the discovery of a suitable control field $\boldsymbol{\varepsilon}(t)$ to meet the objective. Normally, Schrödinger's equation [1] is viewed as linear, and this perspective is valid if the Hamiltonian is known a priori, leaving the equation to be solved for the wave function. However, in the case of quantum control, neither the wave function nor the control field is known a priori, and the two enter bilinearly on the right-hand side of eqn [1]. Thus, quantum control is mathematically a nonlinear inverse problem. As such, one can anticipate possibly diverse behavior in the process of seeking successful controls, as well as in the ensuing quantum dynamical control behavior. The control must take into account the evolving system dynamics, thereby resulting in the control field being a function(al) of the current state of the system $\boldsymbol{\varepsilon}(\psi)$ in the case of quantum control design, or dependent on the system observations $\boldsymbol{\varepsilon}(\langle O\rangle)$ in the case of laboratory closed-loop field discovery efforts where $\langle O\rangle = \langle\psi|O|\psi\rangle$. Furthermore, the control field at the current time t will depend in some implicit fashion on the future state of the evolving system at the final target time T. It is evident that control field design and laboratory discovery present highly nontrivial tasks.

Although the emphasis in this review is on the theoretical aspects of quantum control theory, the subject exists for its laboratory realizations, and those realizations, in turn, intimately depend on the capabilities of theoretical and algorithmic techniques for their successful implementations. Accordingly, theoretical laser control field design techniques will be discussed, along with algorithmic aspects of current laboratory practice. This material respectively will focus on optimal control theory (OCT) and optimal control experiments (OCEs), as seeking optimality provides the best means to achieve any posed objective. Finally, the last part of the article will present some general conclusions on the state of the quantum control field.

Quantum Optimal Control Theory for Designing Laser Fields

When considering control in any domain of application, a reasonable approach is to computationally design the control for subsequent implementation in the laboratory. Quantum mechanical laser field design has taken on a number of realizations. At one limit is the application of simple intuition for design purposes, and in some special cases (e.g., the weak field perturbation theory regime), this approach may be applicable. Physical insights will always play a central role in laser field design, but to be especially useful, they need to be channeled into the proper mathematical framework. Many of the interesting applications operate in the strong-field nonperturbative regime. In this domain, serious questions arise regarding whether sufficient information is available about the Hamiltonian to execute reliable designs. Regardless of whether the Hamiltonian is known accurately or is an acknowledged model, the theoretical study of quantum control can provide physical insight into the phenomena involved, as well as possibly yielding trial laser pulses for further refinement in the laboratory.

Achieving control over quantum mechanical phenomena often involves a balance of competing dynamical processes. For example, in the case of aiming to create a particular excitation in a molecule or material, there will always be the concomitant need to minimize other unwanted excitations. Often, there are also limitations on the form, intensity, or other characteristics of the laser controls that must be adhered to. Another goal is for the control outcome to be as robust as possible to the laser field fluctuations and Hamiltonian uncertainties. Overriding all of these issues is merely the desire to achieve the best possible physical result for the posed quantum mechanical objective. In summary, all of these desired extrema conditions translate over to posing the design of control laser fields as an optimization problem. Thus, optimal control theory forms a basic foundation for quantum control field design.

Control field design starts by specification of the Hamiltonian components H_0 and $\boldsymbol{\mu}$ in eqn [1], with the goal of finding the best control electric field $\boldsymbol{\varepsilon}(t)$ to balance the competing objectives. Schrödinger's equation must be solved as part of this process, but this effort is not merely a forward propagation task, as the control field is not known a priori. As an optimal design is the goal, a cost functional $J = J(\text{objectives, penalties, } \boldsymbol{\varepsilon}(t))$ is prescribed, which contains the information on the physical objectives, competing penalties, and any costs or constraints associated with the structure of the laser field. The functional J could contain many terms if the competing physical goals are highly complex. As a specific simple illustration, consider the common goal of steering the system to achieve an expectation value $\langle\psi(T)|O|\psi(T)\rangle$ as close as possible to the target value O_{target} associated with the observable operator O at time T. An additional cost is imposed to minimize the laser fluence. These criteria may be embodied in a cost functional of the form

$$J = \left(\langle\psi(T)|O|\psi(T)\rangle - O_{\text{target}}\right)^2 + \omega\int_0^T \varepsilon^2(t)\,\mathrm{d}t - 2\Im\int_0^T \mathrm{d}t\left\langle\lambda(t)|\mathrm{i}\hbar\frac{\partial}{\partial t} - H_0 + \boldsymbol{\mu}\cdot\boldsymbol{\varepsilon}(t)|\psi(t)\right\rangle \quad [3]$$

Here, the parameter $\omega \geq 0$ is a weight to balance the significance of the fluence term relative to achieving the target expectation value, and $|\lambda(t)\rangle$ serves as a Lagrange multiplier, assuring that Schrödinger's equation is satisfied during the variational minimization of J with respect to the control field. Carrying out the latter minimization will lead to eqn [1], along with the additional relations

$$\mathrm{i}\hbar\frac{\partial}{\partial t}|\lambda(t)\rangle = [H_0 - \boldsymbol{\mu}\cdot\boldsymbol{\varepsilon}(t)]|\lambda(t)\rangle,\quad |\lambda(T)\rangle = 2\sigma O|\lambda(T)\rangle \quad [4]$$

$$\boldsymbol{\varepsilon}(t) = \frac{1}{\omega}\Im\langle\lambda(t)|\boldsymbol{\mu}|\psi(t)\rangle \quad [5]$$

$$\sigma = \langle\psi(T)|O|\psi(T)\rangle - O_{\text{target}} \quad [6]$$

Equations [1] and [4]–[6] embody the OCT design equations that must be solved to yield the optimal field $\boldsymbol{\varepsilon}(t)$ given in eqn [5]. These design equations have an unusual mathematical structure within quantum mechanics. First, insertion of the field expression in eqn [5] into eqns [1] and [4] produces two cubically nonlinear coupled Schrödinger-like equations. These equations are in the same family as the standard nonlinear Schrödinger equation, and as such, one may expect that unusual dynamical behavior could arise. Although eqn [4] for $|\lambda(t)\rangle$ is identical in form to the Schrödinger equation [1], only $|\psi(t)\rangle$ is the true wavefunction, with $|\lambda(t)\rangle$ serving to guide the controlled quantum evolution towards the physical objective. Importantly, eqn [1] is an initial value problem, while eqn [4] is a final value problem. Thus, the two equations together form a two-point boundary value problem in time, which is an inherent feature of temporal engineering optimal control as well. The boundary value nature of these equations typically leads to the existence of multiple solutions, where σ in eqn [6] plays the role of a discrete eigenvalue, specifying the quality of the particular achieved control field design. The fact that there are generally multiple solutions to the laser design equations can be attractive from a physical perspective, as the designs may be sorted through to identify those being most attractive for laboratory implementation.

The overall mathematical structure of eqns [1] and [4]–[6] can be melded together into a single design equation

$$\mathrm{i}\hbar\frac{\partial}{\partial t}|\psi(t)\rangle = [H_0 - \boldsymbol{\mu}\cdot\boldsymbol{\varepsilon}(\psi, \sigma, t)]|\psi(t)\rangle,\quad |\psi(0)\rangle = |\psi_{\mathrm{i}}\rangle \quad [7]$$

The structure of this equation embodies the comments in the introduction that control field design is inherently a nonlinear process. The main source of complexity arising in eqn [7] is through the control field $\boldsymbol{\varepsilon}(\psi, \sigma, t)$ depending not only on the wave function at the present time t, but also on the future value of the wavefunction at the target time T contained in σ. This structure again reflects the two-point boundary value nature of the control equations.

Given the typical multiplicity of solutions to eqns [1] and [4]–[6], or equivalently, eqn [7], it is attractive to consider approximations to these equations (except perhaps for the inviolate Schrödinger equation [1], and much work continues to be done along these lines. One case involves what is referred to as tracking control, whereby a path is specified for $\langle\psi(t)|O|\psi(t)\rangle$ evolving from $t = 0$ out to $t = T$. Tracking control eliminates σ to produce a field of the form $\boldsymbol{\varepsilon}(\psi,t)$, thereby permitting the design equations to be explicitly integrated as a forward-marching problem toward the target; the tracking equations are still nonlinear with respect to the evolving state. Many variations on these concepts can be envisioned, and other approximations may also be introduced to deal with special circumstances. One technique appropriate for at least few-level systems is stimulated Raman adiabatic passage (STIRAP), which seeks robust adiabatic passage from an initial state to a particular final state, typically with nearly total destructive interference occurring in the intermediate states. This design technique can have special attractive robustness characteristics with respect to field errors. STIRAP, tracking, and various perturbation theory-based control design techniques can be expressed as special cases of OCT, with suitable cost functionals and constraints. Further approximation methods will surely be developed, with the rigorous OCT concepts forming the general foundation for control field design.

As the OCT equations are inherently nonlinear, their solution typically requires numerical iteration, and a variety of procedures may be utilized for this purpose. Almost all of the methods employ local search techniques (e.g., gradient methods), and some also show monotonic convergence with respect to each new iteration step. Local techniques typically evolve to the nearest solution in the space of possible control fields. Such optimizations can be numerically efficient, although the quality of the attained result can depend on the initial trial for the control field and the details of the algorithm involved. In contrast, global search techniques, such as simulated annealing or genetic algorithms, can search more broadly for the best solution in the control field space. These more expansive searches are attractive, but at the price of typically requiring more intensive computations. Effort has also gone into seeking global or semiglobal input → output maps relating the electric field $\boldsymbol{\varepsilon}(t)$ structure to the observable $O[\boldsymbol{\varepsilon}(t)]$. Such maps may be learned, hopefully, from a modest number of computations with a selected set of fields, and then utilized as high-speed interpolators over the control field space to permit the efficient use of global search algorithms to attain the best control solution possible. At the foundation of all OCT design procedures is the need to solve the Schrödinger equation. Thus, computational technology to improve this basic task is of fundamental importance for designing laser fields.

Many computations have been carried out with OCT to attain control field designs for manipulating a host of phenomena, including rotational, vibrational, electronic, and reactive dynamics of molecules, as well as electron motion in semiconductors. Every system has its own rich details, which in turn, are compounded by the fact that multiple control designs will typically exist in many applications producing comparable physical outcomes. Collectively, these control design studies confirm the manipulation of constructive and destructive quantum wave interferences as the general mechanism for achieving successful control over quantum phenomena. This conclusion may be expressed as the following principle:

> **Control field–system cooperativity principle**: Successful quantum control requires that the field must have the proper structure to take full advantage of all of the dynamical opportunities offered by the system, to best satisfy the physical objective.

This simple statement of system–field cooperativity embodies the richness, as well as the complexity, of seeking control over quantum phenomena, and also speaks to why simple intuition alone has not proved to be a generally viable design technique. Quantum systems can often exhibit highly complex dynamical behavior, including broad dispersion of the wave packet over spatial domains or multitudes of quantum states. Handling such complexity can require fields with subtle structure to interact with the quantum system in a global fashion to manage all of the motions involved. Thus, we may expect that successful control pulses will often have broad bandwidth, including amplitude and phase modulation. Until relatively recently, laser sources with these characteristics were not available, but the technology is now in hand and rapidly evolving (see the discussion later).

The cooperativity principle above is of fundamental importance in the control of all quantum phenomena, and a simple illustration of this principle is shown in Figure 2 for the control of wave packet motion on an excited state of the NO molecule. The target for the control is a narrow wave packet located over the well of the excited B state. The optimal control field consists of two coordinated pulses, at early and late times, with both features having internal structure. The figure indicates that the ensuing excited state wave packet has two components, one of which actually passes through the target region during the initial evolution, only to return again and meet the second component at just the right place and time, to achieve the target objective as best as possible. Similar cooperativity interpretations can be found in virtually all implementations with OCT.

The main reason for performing quantum field design is to ultimately implement the designs in the laboratory. The design procedures must face laboratory realities, which include the fact that most Hamiltonians are not known to high accuracy (especially for polyatomic molecules and complex solid-state structures), and secondly, a variety of laboratory field imperfections may unwittingly be present. Notwithstanding these comments, OCT has been fundamental to the development of quantum control, including laying out the logic for how to perform the analogous optimal control experiments. Design implementations and further OCT development will continue to play a basic role in the quantum control field. At present, perhaps the most important contribution of OCT has been to (1) highlight the basic control cooperativity principle above, and (2) provide the basis for developing algorithms to successfully guide optimal control experiments, as discussed below.

Algorithms for Implementing Optimal Control Experiments

The ultimate purpose of considering control theory within quantum mechanics is to take the matter into



Figure 2 Control of wave packet evolution on the electronically excited B state of NO, with the goal of creating a narrow final packet over the excited state well. (a) indicates that the ground-state packet is brought up in two pieces using the coordinated dual pulse in (b). The piece of the packet from the first pulse actually passes through the target region, then bounces off the right side of the potential, to finally meet the second piece of the packet at just the right time over the target location r^* for successful control. This behavior is an illustration of the control field–system cooperativity principle stated in the text.

the laboratory for implementation and exploitation of its capabilities. Ideally, theoretical control field designs may be attained using the techniques discussed above, followed by the achievement of successful control upon execution of the designs in the laboratory. This appealing approach is burdened with three difficulties: (1) Hamiltonians are often imprecisely known, (2) accurately solving the design equations can be a significant task, and (3) realization of any given design will likely be imperfect due to laboratory noise or other unaccounted-for systematic errors. Perhaps the most serious of these difficulties is point (1), especially considering that the best quality control will be achieved by maximally drawing on subtle constructive and destructive quantum wave interference effects. Exploiting such subtleties will generally require high-quality control designs that, in turn, depend on having reliable Hamiltonians. Although various designs have been carried out seeking robustness with respect to Hamiltonian uncertainties, the issue in point (1) should remain of significance in the foreseeable future, especially for the most complex (and often, the most interesting!) chemical/physical applications. Mitigating this serious problem is the ability to create shaped laser pulse controls and apply them to a quantum system, followed by a probe of their effects at an unprecedented rate of thousands or more independent trials per minute. This unique capability led to the suggestion of partially, if not totally, sidestepping the design process by performing closed-loop experiments to let the quantum system teach the laser how to achieve its control in the laboratory. Figure 3 schematically shows this closed loop process, drawing on the following logic:

1. **The molecular view**. Although there may be theoretical uncertainty about the system Hamiltonian, the actual chemical/physical system under study ‘knows’ its own Hamiltonian precisely! This knowledge would also include any unusual exigencies, perhaps associated with structural or other defects in the particular sample. Furthermore, upon exposure to a control field, the system ‘solves’ its own Schrödinger equation impeccably accurately and as fast as possible in real time. Considering these points, the aim is to replace the offline arduous digital computer control field design effort with the actual quantum system under study acting as a precise analog computer, solving the true equations of motion.
2. **Control laser technology**. Pulse shaping under full computer control may be carried out using even hundreds of discrete elements in the frequency domain controlling the phase and amplitude structure of the pulse. This technology is readily available and expanding in terms of pulse center frequency flexibility and bandwidth capabilities.



Figure 3 A schematic of the closed-loop concept for allowing the quantum system to teach the laser how to achieve its control. The actual quantum system under control is in a loop with a laser and pulse shaper all slaved together with a pattern recognition algorithm to guide the excursions around the loop. The success of this concept relies on the ability to perform very large numbers of control experiments in a short period of time. In principle, no knowledge of the system Hamiltonian is required to steer the system to the desired final objective, although a good trial design $\varepsilon_0(t)$ may accelerate the process. The ith cycle around the loop attempts to find a better control field $\varepsilon_i(t)$ such that the system response $\langle O(T)\rangle_i$ for the observable operator O comes closer to the desired value O_{target}.

3. **Quantum mechanical objectives.** Many chemical/physical objectives may be simply expressed as the desire to steer a quantum mechanical flux out one clearly defined channel versus another.
4. **Detection of the control action.** Detection of the control outcome can often be carried out by a second laser pulse or any other suitable high duty cycle detection means, such as laser-induced mass spectrometry. The typical circumstance in point (3) implies that little, if any, time-consuming offline data analysis will be necessary beyond that of simple signal averaging.
5. **Fast learning algorithms.** All of the four points above may be slaved together using pattern recognition learning algorithms to identify those control fields which are producing better results, and bias the next sequence of experiments in their favor for further improvement. Although many algorithms may be employed for this purpose, the global search capabilities of genetic algorithms are quite attractive, as they may take full advantage of the high throughput nature of the experiments.

In linking together all of these components into a closed-loop OCE, it is important that no single operational step significantly lags behind any other, for efficiency reasons. Fortunately, this economy is coincident with all the tasks and technologies involved. For achieving control alone, there is no requirement that the actual laser pulse structure be identified on each cycle of the loop. Rather, the laser control ‘knob’ settings are adequate information for the learning algorithm, as the only criterion is to suitably adjust the knobs to achieve an acceptable value for the chemical/physical objective. The learning algorithm in point (5) operates with a cost functional J, analogous to that used for computational design of fields, but now the cost functional can only depend on those quantities directly observable in the laboratory (i.e., minimally, the current achieved target expectation value). In cases where a physical understanding is sought about the control mechanism, the laser field structure must also be measured. This additional information is typically also not a burden to attain, as it often is only required for the single best control field at the end of the closed-loop learning experiments.

The OCE process in Figure 3 and steps (1)–(5) above constitute the laboratory process for achieving optimal quantum control, and exactly the same reasons put forth for OCT motivate the desire for attaining optimal performance: principally, seeking the best control result that can possibly be obtained. Seeking optimal performance also ensures some degree of inherent robustness to field noise, as fleeting observations would not likely survive the signal averaging carried out in the laboratory. Additionally, robustness as a specific criterion may also be included in the laboratory cost functional in item (5). When a detailed physical interpretation of the controlled dynamics is desired, it is essential to remove any extraneous control field features that have little impact on the system manipulations. Without the latter clean-up carried out during the experiments, the final field may be contaminated by structures that have little physical impact. Although quantum dynamics typically occurs on femtosecond or picosecond time-scales, the loop excursions in Figure 3 need not be carried out on the latter time-scales. Rather, the loop may be traversed as rapidly as convenient, consistent with the capabilities of the apparatus. A new system sample is introduced on each cycle of the loop. This process is referred learning control, to distinguish it from real-time feedback control.

The closed-loop quantum learning control algorithm can be self-starting, requiring no prior control field designs, under favorable circumstances. Virtually all of the current experiments were carried out in this fashion. It remains to be seen if this procedure of 'going in blind' will be generally applicable in highly complex situations where the initial state is far from the target state. Learning control can only proceed if at least a minimal signal is observed in the target state. Presently, this requirement has been met by drawing on the overwhelmingly large number of exploratory experiments that can be carried out, even in a brief few minutes, under full computer control. However, in some situations, the performance of intermediate observations along the way to the target goal may be necessary in order to at least partially guide the quantum dynamics towards the ultimate objective. Beneficial use could also be made from prior theoretical laser control designs $\boldsymbol{\varepsilon}_0(t)$ capable of at least yielding a minimal target signal.

The OCE closed-loop procedure was based on the growing number of successful theoretical OCT design calculations, even with all of their foibles, especially including less than perfect Hamiltonians. The OCT and OCE processes are analogous, with their primary distinction involving precisely what appears in their corresponding cost functionals. Theoretical guidance can aid in identifying the appropriate cost functionals and learning algorithms for OCE, especially for addressing the needs associated with attaining a physical understanding about the mechanisms governing controlled quantum dynamics phenomena.

A central issue is the rate that learning control occurs upon excursions around the loop in Figure 3. A number of factors control this rate of learning, including the nature of the physical system, the choice of objective, the presence of field uncertainties and measurement errors, the number of control variables, and the capabilities of the learning algorithm employed. Achieving control is a matter of discrimination, and some of these factors, whether inherent to the system or introduced by choice, may work against attaining good-quality discrimination. At this juncture, little is known quantitatively about the limitations associated with any of these factors.

The latter issues have not prevented the successful performance of a broad variety of quantum control experiments, and at present the ability to carry out massive numbers of closed-loop excursions has overcome any evident difficulties. The number of examples of successful closed-loop quantum control is rapidly growing, with illustrations involving the manipulation of laser dye fluorescence, chemical reactivity, high harmonic generation, semiconductor optical switching, fiber optic pulse transmission, and dynamical discrimination of similar chemical species, amongst others. Perhaps the most interesting cases are those carried out at high field intensities, where prior speculation suggested that such experiments would fail due to even modest laser field noise being amplified by the quantum dynamics. Fortunately, this outcome did not occur, and theoretical studies have indicated that surprising degrees of robustness to field noise may accompany the manipulation of quantum dynamics phenomena. Although the presence of field noise may diminish the beneficial influence of constructive and destructive interferences, evidence shows that field noise does not appear to kill the actual control process, at least in terms of obtaining reasonable values for the control objectives. One illustration of control in the high-field regime is shown in Figure 4, demonstrating the learning process for the dissociative rearrangement of acetophenone to form toluene. Interestingly, this case involves breaking two bonds, with the formation of a third, indicating that complex dynamics can be managed with suitably tailored laser pulses.

Operating in the strong-field regime, especially for chemical manipulations, also has the important benefit of producing a generic laser tool to control a broad variety of systems by overcoming the long-standing problem of having sufficient bandwidth. For example, the result in Figure 4 uses a Ti:sapphire laser in the near-infrared regime. Starting with a bandwidth-limited pulse of intensity near



Figure 4 An illustration of dissociative rearrangement achieved by closed-loop learning control in Figure 3. The optimally deduced laser pulse broke two bonds in the parent acetophenone molecule and formed a new one to yield the toluene product. The laboratory learning curve is shown for the toluene product signal as a function of the generations in the genetic algorithm guiding the experiments. The fluctuations in the learning curve for optimizing the toluene yield corresponds to the algorithm searching for the optimal yield as the experiments proceed.

$\sim 10^{14}$ W cm^{-2}, in this regime, the dynamic power broadening can easily be on the order of ~ 1 eV or more, thereby effectively converting the otherwise discrete spectrum of the molecule into an effective continuum for ready multiphoton matching by the control laser pulse. Operating under these physical conditions is very attractive, as the apparatus is generic, permitting a single shaped-pulse laser source (e.g., a Ti:sapphire system with phase and amplitude modulation) to be utilized with virtually any chemical system where manipulations are desired. Although every desired physical/chemical goal may not be satisfactorily met (i.e., the goals must be physically attainable!), the means are now available to explore large numbers of systems. Operating under closed loop in the strong-field tailored-pulse regime eliminates the prior serious limitation of first finding a physical system to meet the laser capabilities; now, the structure of the laser pulse can be shaped to meet the molecule's characteristics. Strong field operations may be attractive for these reasons, but other broadband laser sources, possibly working at weaker field intensities, might be essential in some applications (e.g., controlling electron dynamics in semiconductors, where material damage is to be avoided). It is anticipated that additional broadband laser sources will become available for these purposes.

The coming years should be a period of rapid expansion, including a thorough exploration of closed-loop quantum control capabilities. As with the use of any laboratory tool, certain applications may be more amenable than others to attaining successful control. The particular physical/chemical questions need to be well posed, and controls need to have sufficient flexibility to meet the objectives. The experiments ahead should be able to reveal the degree to which drawing on optimality in OCE, combined with the performance of massive numbers of experiments can lead to broad-scale successful control of quantum phenomena. One issue of concern is the richness associated with the large numbers of phase and amplitude control knobs that may be adjusted in the laboratory. Some experiments have already operated with hundreds of knobs, while others have restricted their number in a variety of ways, to simplify the search process. Additional technological and algorithmic advances may be required to manage the high-dimensional control space searches. Fortunately, for typical applications, the search does not reduce to seeking a needle in a haystack, as generally there are multiple control solutions, possibly all of very good quality.

As a final comment on OCE, it is useful to appreciate the subtle distinction of the procedure from closed-loop feedback experiments. This distinction is illustrated in Figure 5, pointing to three types of closed-loop quantum control laboratory experiments. The OCE procedure in Figure 5a produces a generic laser tool capable of controlling a broad variety of systems with an emphasis in the figure placed on the point that each cycle around the loop starts with a new sample for control. The replacement of the sample on each cycle eliminates a number of difficulties, principally including concerns about sample damage, avoidance of operating the loop at the ultrafast speed of the quantum mechanical processes, and elimination of the effect that 'to observe is to disturb' in quantum mechanics. Thus, learning control provides a generic practical procedure, regardless of the nature of the quantum system. Figure 5b has the same structure as that of Figure 5a, except the loop is now closed around the same single quantum system, which is followed throughout its evolution. All of the issues mentioned above that are circumvented by operating through laboratory learning control in Figure 5a must now be directly faced in the setup of Figure 5b. The procedure in Figure 5b will likely only be applicable in special circumstances, at least for the reason that many quantum systems operate on time-scales far too fast for opto-electronics and computers to keep up with. However, there are certain quantum mechanical processes that are sufficiently slow to meet the criteria. Furthermore, a period of free evolutionary



Figure 5 Three possible closed-loop formulations for attaining laser control over quantum phenomena. (a) is a learning control process where a new system is introduced on each excursion around the loop. (b) utilizes feedback control with the loop being traversed with the same sample, generally calling for an accurate model of the system to adjust the controls on each loop excursion. (c) is, at present, a dream machine where the laser and the sample under control are one unit operating without external algorithmic guidance. The closed-loop learning control procedure in (a) appears to form the most practical means to achieve laser control over quantum phenomena, especially for complex systems.

quantum dynamics may be permitted to occur between one control pulse and the next, to make the time issue manageable. While the learning control process in Figures 3 and 5a can be performed model-free, the feedback algorithm in Figure 5b generally must operate with a sufficiently reliable system Hamiltonian to carry out fast design corrections to the control field, based on the previous control outcome. These are very severe demands, but they may be met under certain circumstances. One reason for considering closed-loop feedback control in Figure 5b is to explore the basic physical issue of quantum mechanical limitations inherent in the statement 'to observe is to disturb'. It is suggestive that control over many types of quantum phenomena may fall into the semiclassical regime, lying somewhere between classical engineering behavior and the hard limitations of quantum mechanics. Experiments of the type in Figure 5b will be most interesting for exploring this matter. Finally, Figure 5c introduces a *gedanken* experiment in the sense that the closed-loop process is literally built into the hardware. That is, the laser control and quantum system act as a single functioning unit operating in a stable fashion, so as to automatically steer the system to the desired target. This process may involve engineering the quantum mechanical system prior to control in cases where that freedom exists, as well as engineering the laser components involved. The meaning of such a device in Figure 5c can be understood by considering an analogy with airplane flight, where the aircraft is constructed to have an inherent degree of aerodynamic stability and will essentially fly (glide) on its own accord when pushed forward. It is an open question whether closing the loop in the hardware can be attained for quantum control, and an exploration of this concept may require additional laser technologies.

Conclusions

This article presented an overview of theoretical concepts and algorithmic considerations associated with the control of quantum phenomena. Theory has played a central role in this area by revealing the fundamental principles underlying quantum control, as well as by providing algorithms for designing controls and guiding experiments to discover successful controls in the laboratory. The challenge of controlling quantum phenomena, in one sense, is an old subject, going back at least 40 years. However, roughly the first 30 of these years would best be described as a period of frustration, due to a lack of full understanding of the principles involved and the nature of the lasers needed to achieve success. Thus, from another perspective, the subject is quite young, with perhaps the most notable development being the introduction of closed-loop laboratory learning procedures. At the time of writing this article, these procedures are just beginning to be explored for their full capabilities. To appreciate the young nature of this subject, it is useful to note that the analogous engineering control disciplines presently occupy many thousands of engineers worldwide, both theoreticians and practitioners, and have done so for many years. Yet, engineering control is far from considered a mature subject. Armed now with the basic concepts and proper laboratory tools, one may anticipate a thorough exploration of control over quantum phenomena, including its many possible applications.

Acknowledgments

Support for this work has come from the National Science Foundation and the Department of Defense.

Further Reading

Brixner T, Damrauer NH and Gerber G (2001) Femtosecond quantum control. *Advances in Atomic, Molecular, and Optical Physics* 44: 1–54.

Rabitz H and Zhu W (2000) Optimal control of molecular motion: Design, implementation and inversion. *Accounts of Chemical Research* 33: 572–578.

Rabitz H, de Vivie-Riedle R, Motzkus M and Kompa K (2000) Whither the future of controlling quantum phenomena? *Science* 288: 824–828.

Rice SA and Zhao M (2000) Optical Control of Molecular Processes. NewYork: John Wiley.

Experimental

R J Levis, Temple University, Philadelphia, PA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The experimental control of quantum phenomena in atoms, molecules, and condensed phase materials has been a long-standing challenge in the physical sciences. For example, the idea that a laser beam could be used to selectively cleave a chemical bond has been pursued since the demonstration of the laser in the early 1960s. However, it was not until very recent times that one could realize selective bond cleavage. One key to the rapid acceleration of such experiments is the capability of manipulating the relative phases between two or more paths leading to the same final state. This is done in practice by controlling the phase of two (or two thousand!) laser frequencies coupling the initial state to some desired final state. The present interest in phase-related control stems in part from research focusing on quantum information sciences, controlling chemical reactivity, and developing new optical technologies, such as in biophotonics for imaging cellular materials. Ultimately, one would like to identify coherent control applications having impact similar to linear regime applications like compact disk reading (and writing), integrated circuit fabrication, and photodynamic therapy. Note that in each of these the phase of the electromagnetic field is not an important parameter and only the brightness of the laser at a particular frequency is used. While phase is of negligible importance in any one photon process, for excitations involving two or more photons, phase not only becomes a useful characteristic, it can modulate the yield of a desired process between zero and one hundred percent.

The use of optical phase to manipulate atomic and molecular systems rose to the forefront of laser science in the 1980s. Prior to this there was considerable effort directed toward using the intensity and high spectral resolution features of the laser for various applications. For example, the high spectral resolution character was employed in purifying nuclear isotopes. Highly intense beams were also used in the unsuccessful attempt to pump enough energy into a single vibrational resonance to selectively dissociate a molecule. The current revolution in coherent control has been driven in part by the realization that controlling energy deposition into a single degree of freedom (such as selectively breaking a bond in a polyatomic molecule) can not be accomplished by simply driving a resonance with an ever more intense laser source. In the case of laser-induced photo dissociation, such excitation ultimately results in statistical dissociation throughout the molecule due to vibrational mode coupling. In complex systems, controlling energy deposition into a desired quantum state requires a more sophisticated approach and one scheme involves coherent control.

The two distinct regimes for excitation in coherent control, the time and frequency domain experiments, are formally equivalent. While the experimental approach and level of success for each domain is vastly different, both rely on precisely specifying the phase relations for a series of excitation frequencies. The basic idea behind phase control is simple. One emulates the interference effects that can be easily visualized in a water tank experiment with a wave propagating through two slits. In the coherent control experiment, two or more indistinguishable pathways must be excited that connect one quantum state to another. In either water waves, or coherent control, the probability for observing constructive or destructive interference at a target state depends on the phase difference between the paths connecting the two locations in the water tank, or the initial and final states in the quantum system. In the case of coherent control, the final state may have some technological value, for instance, a desirable chemical reaction product or an intermediate in the implementation of quantum computation.

Frequency domain methods concentrate on interfering two excitation routes in a system by controlling the phase difference between two distinct frequencies coupling an initial state to a final state. Perhaps the first mention of the concept of phase control in the optical regime can be traced to investigations in Russia in the early 1960s, where the interference between a one- and three-photon path was theoretically proposed as a means to modulate a two-photon absorption. This two-path interference idea lay dormant until the reality of controlling the relative phase of two distinct frequencies was achieved in 1990 using gas phase pressure modulation for frequency domain experiments. The idea was theoretically extended to the control of nuclear motion in 1988. The first experimental example of two-color phase control over nuclear motion was demonstrated in 1991. It is interesting that the first demonstrations of coherent control did not, however, originate in the frequency domain approach, but came from time domain investigations in the mid-1980s. This was work that grew directly out of the chemical dynamics community and will be described below.

While frequency domain methods were developed exclusively for the observation of quantum interference, the experimental implementation of time-domain methods was first developed for observing nuclear motion in real time. In the time domain, a superposition of multiple states is prepared in a system using a short duration (~50 fs) laser pulse. The superposition state will subsequently evolve according to the phase relationships of the prepared states and the Hamiltonian of the system. At some later time the evolution must be probed using a second, short-time-duration laser pulse. The time-domain methods for coherent control were first proposed in 1985 and were based on wavepacket propagation methods developed in the 1970s. The first experiments were reported in the mid-1980s.

To determine whether the time or frequency domain implementation is more applicable for a particular control context, one should compare the relevant energy level spacing of the quantum system to the bandwidth of the excitation laser. For instance, control of atomic systems is more suited to frequency domain methods because the characteristic energy level spacing in an atom (several electron volts) is large compared to the bandwidth of femtosecond laser pulses (millielectron volts). In this case, preparation of a superposition of two or more states is impractical with a single laser pulse at the present time, dictating that the control scheme must employ the initial state and a single excited eigenstate. In practice, quasi-CW nanosecond duration laser pulses are employed for such experiments because current ultrafast (fs duration) laser sources cannot typically prepare a superposition of electronic states. One instructive exception involves the excitation of Rydberg states in atoms. Here the electronic energy level spacing can be small enough that the bandwidth of a femtosecond excitation laser may span several electronic states and thus can create a superposition state. One should also note that the next generation of laser sources in the attosecond regime may permit the preparation of a wavepacket from low-lying electronic states in an atom. In the case of molecules, avoiding a superposition state is nearly impossible. Such experiments employ pico- to femtosecond duration laser pulses, having a bandwidth sufficient to excite many vibrational levels, either in the ground or excited electronic state manifold of a molecule. To complete the time-dependent measurement, the propagation of the wavepacket to the final state of interest must be observed (probed) using a second ultrafast laser pulse that can produce fluorescence, ionization, or stimulated emission in a time-resolved manner. The multiple paths that link the initial and final state via the pump and the probe pulses are the key to the equivalence of the time and frequency domain methods.

There is another useful way to classify experiments that have been performed recently in coherent control, that is into either open-loop or closed-loop techniques. Open-loop signifies that a calculation may be performed to specify the required pulse shape for control before the experiment is attempted. All of the frequency-based, and most of the time-based experiments fall into this category. Closed-loop, on the other hand, signifies that the results from experimental measurements must be used to assist in determining the correct parameters for the next experiment, this pioneering approach was suggested in 1992. It is interesting that in the context of control experiments performed to date, closed-loop experiments represent the only route to determining the optimal laser pulse shape for controlling even moderately complex systems. In this approach, no input from theoretical models is required for coherent control of complex systems. This is unlike typical control engineering environments, where closed-loop signifies the use of experiments to refine parameters used in a theoretical model.

There is one additional distinction that is of value for understanding the state of coherent control at the present time. Experiments may be classified into systems having Hamiltonians that allow calculation of frequencies required for the desired interference patterns (thus enabling open-loop experiments) and those having ill-defined Hamiltonians (requiring closed-loop experiments). The open-loop experiments have demonstrated the utility of various control schemes, but are not amenable to systems having even moderate complexity. The closed-loop experiments are capable of controlling systems of moderate complexity but are not amenable to precalculation of the required control fields. Systems requiring closed-loop methods include propagation of short pulses in an optical fiber, control of high harmonic generation for soft X-ray generation, control of chemical reactions and control of biological systems. In the experimental regime, the value of learning control for dealing with complex systems has been well documented.

The remainder of this article represents an overview of the experimental implementation of coherent control. The earliest phase control experiments involved time-dependent probing of molecular wavepackets, and were followed by two-path interference in an atomic system. The most recent, and general, implementation of control involves tailoring a time-dependent electromagnetic field for a desired objective using closed-loop techniques. Since the use of tailored laser pulses appears to be rather general, a more complete description of the experiment is provided.

Time-Dependent Methods

The first experiments demonstrating the possibility of coherent control were performed to detect nuclear motion in molecules in real time. These investigations were the experimental realization of the pump-dump or pulse-timing control methods as originally described in 1985. The experimental applications have expanded to numerous systems including diatomic and triatomic molecules, small clusters, and even biological molecules. For such experiments, a vibrational coherence is prepared by exciting a superposition of states. These measurements implicitly used phase control both in the generation of the ultrashort pulses and in the coherent probing of the superposition state by varying the time delay between the pump and probe pulses, in effect modulating the outcome of a quantum transition. Since the earliest optical experiment in the mid-1980s, there have been many hundreds of such experiments reported in the literature. The motivation for the very first experiments was not explicitly phase control, but rather the observation of nuclear motion of molecules in real time. In such later measurements, oscillations in the superposition states were observable for many cycles, up to many tens of picoseconds in favorable cases, i.e., diatomic molecules in the gas phase. The loss of signal in the coherent oscillations is ultimately due to passage of the superposition state in to surrounding bath states. This may be due to collision with another molecule, dissociation of the system or redistribution of the excitation energy into other modes of the system not originally excited in the superposition. It is notable that coherence can be maintained in solution phase systems for tens of picoseconds and for the case of resonances having weak coupling to other modes, coherence can even be modulated in large biological systems on the picosecond time scale.

Decoherence represents loss of phase information about a system. In this context, phase information represents our detailed knowledge of the electronic and nuclear coordinates of the system. In the case of vibrational coherence, decoherence may be represented by intramolecular vibrational energy transfer to other modes of the molecule. This can be thought of as the propensity of vibrational modes of a molecule to couple together in a manner that randomizes deposited energy throughout the molecule. Decoherence in a condensed phase system includes transfer of energy to the solvent modes surrounding the system of interest. For an electronically excited molecule or atom, decoherence can involve spontaneous emission of radiation (fluorescence), or dissociation in the case of molecules. Certain excited states may have high probability for fluorescence and would represent a significant decoherence pathway and an obstacle for coherent control. These states may be called 'lossy' and are often used in optical pumping schemes as well as for stimulated emission pumping. An interesting question arises as to whether one can employ such states in a pathway leading to a desired final state, or must such lossy states be avoided at all costs in coherent control. This question has been answered to some degree by the method of rapid adiabatic passage. In this experiment, an initial state is coupled to a final state by way of a lossy state. The coupling is a coherent process and the preparation involves dressed states that are eigenstates of the system. In this coherent superposition the lossy state is employed, but no population is allowed to build up and thus decoherence is circumvented.

Two-Path Interference Methods

Interference methods form perhaps the most intuitive example of coherent control. The first experimental demonstration was reported in 1990 and involved the modulation of ionization probability in Hg by interfering a one-photon and three-photon excitation pathway to an excited electronic state (followed by two-photon ionization). The long delay between the introduction of the two-path interference concept in 1960 and the demonstration in 1990 was the difficulty in controlling the relative phase of the one- and three-photon paths. The solution involved generating the third harmonic of the fundamental in a nonlinear crystal, and copropagating the two beams through a low-density gas. Changing the pressure of the gas changes the optical phase retardance at different rates for different frequencies, thus allowing relative phase control between two colors. The ionization yield of Hg was clearly modulated as a function of pressure. Such schemes have been extended to diatomic molecular systems and the concept of determining molecular phase has been investigated. While changing the phase of more than two frequencies has not been demonstrated using pressure tuning (because of experimental difficulties), a more flexible method has been developed to alter relative phase of up to 1000 frequency bands, as will be described next.

Closed-Loop Control Methods

Perhaps the most exciting new aspect of control in recent years concerns the prospect for performing closed-loop experiments. In this approach a more complex level of control in matter is achieved in comparison to the two-path interference and pump-probe control methods. In the closed-loop method, an arbitrarily complex time-dependent electromagnetic field is prepared that may have multiple subpulses and up to thousands of interfering frequency bands. The realization of closed-loop control over complex processes relies on the confluence of three technologies: (i) production of large bandwidth ultrafast laser pulses; (ii) spatial modulation methods for manipulating the relative phases and amplitudes of component frequencies of the ultrafast laser pulse; and (iii) closed-loop learning control methods for sorting through the vast number of pulse shapes available as potential control fields. In the closed-loop method, the result of a laser molecule interaction is used to tailor an optimized pulse.

In almost all of the experimental systems used for closed-loop control today, Kerr lens mode-locking in the Ti:sapphire crystal is used to phase lock the wide bandwidth of available frequencies (750–950 nm) to create the ultrafast pulse. In this phenomenon, the intensity variation in the short laser pulse creates a transient lens in the Ti:sapphire lasing medium that discriminates between free lasing and mode-locked pulses. As a result, all of the population inversion available in the lasing medium may be coerced into enhancing the ultrashort traveling wave in the cavity in this way. The wide bandwidth available may then be amplified and tailored into a shaped electromagnetic field. Spatial light modulation is one such method for modulating the relative phases and amplitudes of the component frequencies in the ultrafast laser pulse to tailor the shaped laser pulse. Pulse shaping first involves dispersing the phase-locked frequencies on an optical grating, the dispersed radiation is then collimated using a cylindrical lens and the individual frequencies are focused to a line forming the Fourier plane. At the Fourier plane, the time-dependent laser pulse is transformed into a series of phase-locked continuous wave (CW) laser frequencies, and thus Fourier transformed from time to frequency space. The relative phases and amplitudes may be modulated in the Fourier plane using an array of liquid crystal pixels. After altering the spectral phase and amplitude profile, the frequencies are recombined on a second grating to form the shaped laser pulse. With one degree of phase control and 10 pixels there are an astronomic number (360^{10}) of pulse shapes that may be generated in this manner. (At the present time, pulse shapers have up to 2000 independent elements.) Evolutionary algorithms are employed to manage the available phase space. Realizing that the pulse shape is nothing more than the summation of a series of sine waves, each having an associated phase and amplitude, we find that a certain pulse shape can be represented by a genome consisting of an array of these frequency-dependent phases and amplitudes. This immediately suggests that the methods of evolutionary search strategies may be useful for determining the optimal pulse shape for a desired photoexcitation process.

The method of closed-loop optimal control for experiments was first proposed in 1992 and the first experiments were reported in 1997 regarding optimization of the efficiency of a laser dye molecule in solution. Since that time a number of experiments have been performed in both the weak and strong field regime. In the weak field regime, the intensity of the laser does not alter the field free structure of the excited states of the system under investigation. In the strong field, the field free states of the system are altered by the electric field of the laser. Whether one is in the weak or strong field regime depends on parameters including the characteristic level spacing of the states of the system to be controlled and the intensity of the laser coupling into those states. Examples of weak field closed-loop control include optimization of laser dye efficiency, compression of an ultrashort laser pulse, dissociation of alkali clusters, optimization of coherent anti-Stokes

Raman excitation, and optical pulse propagation in fibers. In the strong field, the laser field is used to manipulate the excited states of the molecule as well as induce population transfer among these states. In this sense, the laser is both creating and exciting resonances, in effect allowing universal excitation with a limited frequency bandwidth of 750–850 nm. For chemical applications, it is worth noting that most molecules do not absorb in this wavelength region in the weak field. Strong field control has been used for controlling bond dissociation, chemical rearrangement, photonic reagents, X-ray generation, molecular centrifuges and the manipulation of mass spectral fragmentation intensities. In the latter case, a new sensing technology has emerged wherein each individual pulse shape represents an independent sensor for a molecule. Given the fact that thousands of pulse shapes can be tested per minute, this represents a new paradigm for molecular analysis.

At the time of this writing, the closed-loop method for adaptively tailoring control fields, has far outstripped our theoretical understanding of the process (particularly in the strong field regime). Adaptive control is presently an active field of investigation, encompassing the fields of physics, engineering, optics, and chemistry. In the coming years, there will be as much work done on the mechanism of control as in the application of the methods. Due to small energy level spacings and complexity of the systems, we anticipate the majority of applications to be in the chemical sciences.

See also

Coherence: Coherence and Imaging; Overview. **Interferometry:** Overview. **Microscopy:** Interference Microscopy.

Further Reading

Brumer PW and Shapiro M (2003) *Principles of the Quantum Control of Molecular Processes*. New York: Wiley Interscience.

Chen C and Elliott DS (1990) Measurement of optical phase variations using interfering multiphoton ionization processes. *Physics Review Letters* 65: 1737.

Levis RJ and Rabitz H (2002) Closing the loop on bond selective chemistry using tailored strong field laser pulses. *Journal of Physical Chemistry A* 106: 6427–6444.

Levis RJ, Menkir GM and Rabitz H (2001) Selective bond dissociation and rearrangement with optimally tailored, strong-field laser pulses. *Science* 292(5517): 709–713.

Rice SA and Zhao M (2000) *Optical Control of Molecular Dynamics*. New York: Wiley Interscience.

Stolow A (2003) Femtosecond time-resolved photoelectron spectroscopy of polyatomic molecules. *Annual Review of Physical Chemistry* 54: 89–119.

Zewail AH, Casati G, Rice SA, *et al.* (1997) Femtochemistry: Chemical reaction dynamics and their control. *Chemical Reactions and Their Control on the Femtosecond Time Scale, Solvay Conference on Chemistry* 101: 3–45.

Applications in Semiconductors

H M van Driel and J E Sipe, University of Toronto, Toronto, ON, Canada

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Interference phenomena are well-known in classical optics. In the early 19th century, Thomas Young showed conclusively that light has wave properties, with the first interference experiment ever performed. He passed quasi-monochromatic light from a single source through a pair of double slits using the configuration of Figure 1a and observed an interference pattern consisting of a series of bright and dark fringes on a distant screen. The intensity distribution can be explained only if it is assumed that light has wave or phase properties. In modern terminology, if E_1 and E_2 are the complex electric fields of the two light beams arriving at the screen, by the superposition principle of field addition the intensity at a particular point on the screen can be written as

$$I \propto |E_1 + E_2|^2 = |E_1|^2 + |E_2|^2 + |E_1||E_2| \cos(\phi_1 - \phi_2) \qquad [1]$$

where $\phi_1 - \phi_2$ is the phase difference of the beams arriving at the screen. While this simple experiment was used originally to demonstrate the wave properties of light, it has subsequently been used for many other purposes, such as measuring the wavelength of light. However, for our purposes, here the Young's double slit apparatus can also be viewed as a device that redistributes light, or

(a) Optical interferometer



(b) Matter interferometer



(c) Conduction-valence band transitions



Figure 1 (a) Interference effects in the Young's double slit experiment; (b) illustration of the general concept of coherence control via multiple quantum mechanical pathways; (c) interference of single- and two-photon transitions connecting the same valence and conduction band states in a semiconductor.

controls its intensity at a particular location. For example, let's consider one of the slits to be a source, with the other slit taken to be a gate, with both capable of letting through the same amount of light. If the gate is closed, the distant screen is nearly uniformly illuminated. But if the gate is open, at a particular point on the distant screen there might be zero intensity or as much as four times the intensity emerging from one slit because of interference effects, with all the light merely being spatially redistributed. In this sense the double slit system can be viewed as a device to redistribute the incident light intensity. The key to all this is the superposition principle and the properties of optical phase.

The superposition principle and interference effects also lie at the heart of quantum mechanics. For example, let's now consider a system under the influence of a perturbation with an associated Hamiltonian that has phase properties. In general the system can evolve from one quantum state $|i\rangle$ to another $|f\rangle$ via multiple pathways involving intermediate states $|m\rangle$. Because of the phased perturbation, interference between those pathways can influence the system's final state. If a_m is the (complex) amplitude associated with a transition from the initial to the final state, via intermediate virtual state $|m\rangle$, then for all possible intermediate states the overall transition probability, W, can be written as

$$W = \left| \sum_m a_m \right|^2 \qquad [2]$$

In the case of only two pathways, as illustrated in Figure 1b, W becomes

$$\begin{aligned} W &= |a_1 + a_2|^2 \\ &= |a_1|^2 + |a_2|^2 + |a_1||a_2|\cos(\phi_1 - \phi_2) \qquad [3] \end{aligned}$$

where ϕ_1 and ϕ_2 are now the phases of the two transition amplitudes. While this expression strongly resembles that of eqn [1], here ϕ_1 and ϕ_2 are influenced by the phase properties of the perturbation Hamiltonian that governs the transition process; these phase factors arise, for example, if light fields constitute the perturbation. But overall it is clear that the change in the state of the system is affected by both the amplitude and phase properties of the perturbation. Analogous with the classical interferometer, equality of the transition amplitudes leads to maximum contrast in the transition rate. Although it has been known since the early days of quantum mechanics that the phase of a perturbation can influence the evolution of a system, generally phase has only been discussed in a passive role. Only in recent years has phase been used as a control parameter for a system, on the same level as the strength of the perturbation itself.

Coherence Control

Coherence control, or quantum control as it is sometimes called, refers to the active process through which one can use phase-dependent perturbations originating with, for example, coherent light waves, to control one or more properties of a quantum system, such as state population, momentum, or spin. This more general perspective of interference leads to a picture of interference of matter waves, rather than simply light waves, and one can now speak of an effective 'matter interferometer'. Laser beams, in particular, are in a unique position to play a role in such processes, since they offer a macroscopic 'phase handle' with which to create such effects. This was recognized by the community of atomic and molecular scientists who emphasized the active manifestations of quantum interference effects, and proposed that branching ratios in photochemical reactions might be controlled through laser-induced interference processes. The use of phase as a control parameter also represents a novel horizon of applications for the laser since most previous applications had involved only amplitude (intensity).

Of course, just as the 'visibility' of the screen pattern for a classical Young's double slit interferometer is governed by the coherence properties of the two slit source, the evolution of a quantum system reflects the coherence properties of the perturbations, and the degree to which one can exercise phase control via external perturbations is also influenced by the interaction of the system of interest with a reservoir – essentially any other degrees of freedom in the system – which can cause decoherence and reduce the effectiveness of the 'matter interferometer'. Since the influence of a reservoir will generally increase with the complexity of a system, one might think that coherence control can only be effectively achieved in simple atomic and molecular systems. Indeed, some of the earliest suggestions for coherence control of a system involved using interference between single and three photon absorption processes, connecting the same initial and final states with photons of frequency 3ω and ω, respectively, and controlling the population of excited states in atomic or diatomic systems. However, it has been difficult to extend this 'two color' paradigm to more complex molecular systems. Since the reservoir leads to decoherence of the system overall, shorter and shorter pulses must be used to overcome decoherence effects. However, short pulses possess a large bandwidth with the result that, for complex systems, selectivity of the final state can be lost. One must therefore consider using interference between multiple pathways in order to control the system, as dictated by the details of the unperturbed Hamiltonian of the system.

For a polyatomic molecule or a solid, the complete Hamiltonian is virtually impossible to determine exactly and it is therefore equally difficult to prescribe the optimal spectral (amplitude and phase) content of the pulses that should be used for control purposes. An alternative approach has therefore emerged, in which one foregoes knowledge of the eigenstates of the Hamiltonian and details of the different possible interfering transition paths in order to achieve control of the end state of a system. This branch of coherence control has come to be known as optimal control. In optimal control one employs an optical source for which one can (ideally) have complete control over the spectral and phase properties. One then uses a feedback process in which experiments are carried out, the effectiveness of achieving a certain result is determined, and the pulse characteristics are then altered to obtain a new result. A key component is the use of an algorithm to select the new pulse properties as part of the feedback system. In this approach the molecule teaches the external control system what it 'requires' for a certain result to be optimally achieved. While the 'best' pulse properties may not directly reveal details of the multiple interference process required to achieve the optimal result, this technique can nonetheless be used to gain some insight into the properties of the unperturbed Hamiltonian and, regardless of such understanding, achieve a desirable result. It has been used to control chemical reaction rates involving several polyatomic molecules, with considerable enhancement in achieving a certain product relative to what can be done using simple thermodynamics.

Coherence Control in Semiconductors

Since coherence control of chemical reactions involving large molecules has represented a significant challenge, it was generally felt that ultrafast decoherence processes would also make control in solids, in general, and semiconductors, in particular, difficult. Early efforts therefore focused on atomic-like situations in which the electrons are bound and associated with discrete states and long coherence times. In semiconductors, the obvious choice is the excitonic system, defect states, or discrete states offered by quantum wells. Population control of excitons and directional ionization of electrons from quantum wells has been clearly demonstrated, similar to related population control of and directional ionization from atoms. Other manifestations of coherence control of semiconductors include control of electron–phonon interactions and intersub-band transitions in quantum wells.

Among the different types of coherence control in semiconductors is the remarkable result that it is possible to coherently control the properties of free electrons associated with continuum states. Although optimal control might be used for some of these processes, we have achieved clear illustrations of control phenomena based on the use of harmonically related beams and interference of single- and two-photon absorption processes connecting the continuum valence and conduction band states as generically illustrated in Figure 1c. Details of the various processes observed can be found elsewhere. Of course, the momentum relaxation time of electrons or holes in continuum states is typically of the order of 100 fs at room temperature, but this time is sufficiently long that it can permit phase-controlled processes. Indeed, with respect to conventional carrier transport, this 'long time' lapse is responsible for the typically high electrical mobilities in crystalline semiconductors such as Si and GaAs. In essence, a crystalline semiconductor with translational symmetry has crystal momentum as a good quantum number, and selection rules for scattering prevent the momentum relaxation time from being prohibitively small. Since electrons or holes in any continuum state can participate in such control processes, one need not be concerned about pulsewidth or bandwidth, unless the pulses were to be so short that carriers of both positive and negative effective mass were generated within one band.

Coherent Control of Electrical Current Using Two Color Beams

We now illustrate the basic principles that describe how the interference process involving valence and conduction band states can be used to control properties of a bulk semiconductor. We do so in the case of using one or two beams to generate and control carrier population, electrical current, and spin current. In pointing out the underlying ideas behind coherence control of semiconductors, we will skip or suppress many of the mathematical details which are required for a full understanding but which might obscure the essential physics. In particular we consider how phase-related optical beams with frequencies ω and 2ω interact with a direct gap semiconductor such that $\hbar\omega < E_g < 2\hbar\omega$ where E_g is the electronic bandgap. For simplicity we consider exciting electrons from a single valence band via single-photon absorption at 2ω and two-photon absorption at ω. As is well known, within an independent particle approximation, the states of electrons and holes in semiconductors can be labeled by their vector crystal momentum $\mathbf{k}$; the energy of states near the conduction or valence bandedges varies quadratically with $|\mathbf{k}|$. For one-photon absorption the transition amplitude can be derived using a perturbation Hamiltonian of the form $H = e/mc\, \mathbf{A}^{2\omega} \cdot \mathbf{p}$ where $\mathbf{A}^{2\omega}$ is the vector potential associated with the light field and $\mathbf{p}$ is the momentum operator. The transition amplitude is therefore of the form

$$\mathrm{a}^{2\omega} \propto E^{2\omega} e^{i\phi_{2\omega}} p_{cv} \qquad [4]$$

where p_{cv} is the interband matrix element of $\mathbf{p}$ along the field ($E^{2\omega}$) direction; for illustration purposes the field is taken to be linearly polarized. The overall transition rate between two particular states of the same $\mathbf{k}$ can be expressed as $W_1 \propto \mathrm{a}^{2\omega}(\mathrm{a}^{2\omega})^* \propto I^{2\omega}|p_{cv}|^2$ where $I^{2\omega}$ is the intensity of the beam. This rate is independent of the phase of the light beam as well as the sign of $\mathbf{k}$. Hence the absorption of light via single-photon transitions generally populates states of equal and opposite momentum with equal probability or, equivalently, establishes a standing electron wave with zero crystal momentum. This is not surprising since photons possess very little momentum and, in the approximation of a uniform electric field, do not give any momentum to an excited electron. The particular states that are excited depends on the light polarization and crystal orientation. However, the main point is that while single-photon absorption can lead to anisotropic filling of electron states, the distribution in momentum space is not polar (dependent on sign of $\mathbf{k}$). Similar considerations apply to the excited holes, but to avoid repetition we will focus on the electrons only.

For two-photon absorption involving the ω photons and connecting states similar to those connected with single-photon absorption, one must employ the 2nd order perturbation theory using the Hamiltonian $H = e/mc\mathbf{A}^{\omega} \cdot \mathbf{p}$. For two-photon absorption there is a transition from the valence band to an (energy nonallowed) intermediate state followed by a transition from the intermediate state to the final state. To determine the total transition rate one must sum over all possible intermediate states. For semiconductors, by far the dominant intermediate state is the final state itself, so that the associated transition amplitude has the form

$$\mathrm{a}^{\omega} \propto (E^{\omega} e^{i\phi_{\omega}} p_{cv})(E^{2\omega} e^{i\phi_{\omega}} p_{cc}) \propto (E^{\omega})^2 e^{2i\phi_{\omega}} p_{cv} \hbar k \qquad [5]$$

where the matrix element p_{cc} is simply the momentum of the conduction band state ($\hbar k$) along the direction of the field. Note that unlike an atomic system, p_{cc} is nonzero, since Bloch states in a crystalline solid do not possess inversion symmetry. If two-photon absorption acts alone, the overall transition rate between two particular $\mathbf{k}$ states would be $W_2 \propto (I^{\omega})^2 |p_{cv}|^2 k^2$. As with single-photon absorption, because this transition rate is independent of the sign of k, two-photon absorption leads to production of electrons with no net momentum.

When both single- and two-photon transitions are present simultaneously, the transition amplitude is the sum of the transition amplitudes expressed in eqn [3]. The overall transition rate is then found using eqn [1] and yields $W = W_1 + W_2 + Int$ where the interference term Int is given by

$$Int \propto E^{2\omega} E^{\omega} E^{\omega} \sin(\phi_{2\omega} - 2\phi_{\omega}) k \qquad [6]$$

Note, however, that the interference effect depends on the sign of k and hence can be constructive for one part of the conduction band but destructive for other parts of that band, depending on the value of the relative phase, $\Delta\phi = \phi_{2\omega} - 2\phi_{\omega}$. In principle one can largely eliminate transitions with $+\mathbf{k}$ and enhance those with $-\mathbf{k}$. This effectively generates a net momentum for electrons or holes and hence, at least temporarily, leads to an electrical current in the absence of any external bias. The net momentum of the carriers, which is absent in the individual processes, must come from the lattice. Because the carriers are created with net momentum during the pulses one has a form of current injection that can be written as

$$dJ/dt \propto E^{2\omega}E^{\omega}E^{\omega}\sin(\Delta\phi) \qquad [7]$$

where J is the current density. This type of current injection is allowed in both centrosymmetric and noncentrosymmetric materials. The physics and concepts behind the quantum interference leading to this form of current injection are analogous with the Young's double slit experiment. Note as well that if this 'interferometer' is balanced (single- and two-photon transition rates are similar), then it is possible to control the overall transition rate with great contrast. Roughly speaking, one balances the two arms of the 'effective interferometer' involved in the interference process, one 'arm' corresponding to the one-photon process and the other to the two-photon process. As an example, let's consider the excitation of GaAs, which has a room-temperature bandgap of 1.42 eV (equivalent to 870 nm). For excitation of GaAs using 1550 and 775 nm light under balanced conditions, the electron cloud is injected with a speed close to 500 km s^{-1}. Under 'balanced' conditions, nearly all the electrons are moving in the same direction. Assuming that the irradiance of the 1550 nm beam is 100 MW cm^{-2}, while that of the second harmonic beam is only 15 kW cm^{-2} (satisfying the 'balance' condition), with Gaussian pulse widths of 100 fs, one obtains a surprisingly large peak current of about 1 kA cm^{-2} for a carrier density of only 10^{14} cm^{-3} if scattering effects are ignored. When scattering is taken into account, the value of the peak current is reduced and the transient current decays on a time-scale of the momentum relaxation time. Figure 2a shows an experimental setup which can be used to demonstrate coherence control of electrical current using the above parameters. Figure 2a shows the region between a pair of electrodes on GaAs being illuminated by a train of harmonically related pulses. Figure 2b illustrates how the steady-state experimental voltage across the capacitor changes as the phase parameter $\Delta\phi$ is varied. Transient electrical currents, generated though incident femtosecond optical pulses, have also been detected through the emission of the associated Terahertz radiation.



Figure 2 (a) Experimental setup to measure steady-state voltage (V) across a pair of electrodes on GaAs with the intervening region illuminated by phased radiation at ω and 2ω; (b) induced voltage across a pair of electrodes on a GaAs semiconductor as a function of the phase parameter associated with two harmonically related incident beams.

The current injection via coherence control and conventional cases (i.e., under a DC bias) differs with respect to their evolution. The current injected via coherent control has an onset determined by the rise time of the optical pulses. In the case of normal current production, existing carriers are accelerated by an electric field, and the momentum distribution is never far from isotropic. For a carrier density of 10^{14} cm^{-3} a DC field $\sim$80 kV cm^{-1} is required to produce a current density of 1 kA cm^{-2}. In GaAs, with an electron mobility of 8000 cm^2 V^{-1} s^{-1} this current would occur about 1/2 ps after the field is 'instantaneously' turned on. This illustrates that the coherently controlled phenomenon efficiently and quickly produces a larger current than can be achieved with the redirecting of statistically distributed electrons.

A more detailed analysis must take into account the actual light polarization, crystal symmetry, crystal face, and orientation relative to the optical polarization. For given optical intensities of the two beams, the maximum electrical current injection in the case of GaAs occurs for linearly polarized beams both oriented along the (111) or equivalent direction. However, large currents can also be observed with the light beams polarized along other high symmetry directions.

Coherent Control of Carrier Density, Spin Population, and Spin Current Using Two Color Beams

The processes described above do not exhaust the coherent control effects that can be observed in bulk semiconductors using harmonic beams. Indeed, for noncentrosymmetric materials, certain light polarizations and crystal orientations allow one to coherently control the total carrier generation rate with or without generating an electrical current. In the case of the cubic material GaAs, provided the ω beam has electric field components along two of the three principal crystal axes, with the 2ω beam having a component along the third direction, one can coherently control the total carrier density. However, the overall degree of control here is determined by how 'noncentrosymmetric' the material is.

The spin degrees of freedom of a semiconductor can also be controlled using two color beams. Due to the spin–orbit interaction, the upper valence bands of a typical semiconductor have certain spin characteristics. To date, optical manipulation of electron spin has been largely based on the fact that partially spin-polarized carriers can be injected in a semiconductor via one-photon absorption of circularly polarized light from these upper valence bands. In such carrier injection – where in fact two-photon absorption could be used as well – spins with no net velocity are injected, and then are typically dragged by a bias voltage to produce a spin-polarized current. However, given the protocols discussed above it should not come as a surprise that the two color coherence scheme, when used with certain light polarizations, can coherently control the spin polarization, making it dependent on $\Delta\phi$. Furthermore, for certain polarization combinations it is also possible to generate a spin current with or without an electrical current. Given the excitement surrounding the field of spintronics, where the goal is the use of the spin degree of freedom for data storage and processing, the control of quantities involving the intrinsic angular momentum of the electron is of particular interest.

Various polarization and crystal geometries can be examined for generating spin currents with or without electrical current. For example, with reference to Figure 3a, for both beams propagating in the **z** (*normal*) direction of a crystal and possessing the same circular polarization, an electrical current can be injected in the (*xy*) plane, at an angle from the crystallographic **x** direction dependent on the relative phase parameter, $\Delta\phi$; this current is spin-polarized in the **z** direction. As well, the injected carriers have a $\pm$**z** component of their velocity, as many with one component as with the other; but those going in one direction are preferentially spin-polarized in one direction in the (*xy*) plane, while those in the other direction are preferentially spin-polarized in the opposite direction. This is an example of a spin current in the absence of an electrical current.

Such a pure spin current that is perhaps more striking is observable with the two beams cross linearly polarized, for example with the fundamental beam in the **x** direction and the second harmonic beam in the **y** direction as shown in Figure 3b. Then there is no net spin injection; the average spin in any



Figure 3 (a) Excitation of a semiconductor by co-circularly polarized ω and 2ω pulses. Arrows indicate that a spin polarized electrical current is generated in the $x-y$ plane in a direction dependent on $\Delta\phi$ while a pure spin current is generated in the beam propagation (z) direction. (b) Excitation of a semiconductor by orthogonally, linearly polarized ω and 2ω pulses. Arrows indicate that a spin polarized electrical current is generated in the direction of the fundamental beam polarization as well as along the beam propagation (z) direction.

direction is zero. And for a vanishing phase parameter $\Delta\phi$ there is no net electrical current injection. Yet, for example, the electrons injected with a $+\mathbf{x}$ velocity component will have one spin polarization with respect to the $\mathbf{z}$ direction, while those injected with a $-\mathbf{x}$ component to their velocity will have the opposite spin polarization with respect to the $\mathbf{z}$ direction.

The examples given above are the spin current analog of the two-color electrical current injection discussed above. There should also be the possibility of injecting a spin current with a single beam into crystals lacking center-of-inversion symmetry.

The simple analysis presented above relies on simple quantum mechanical ideas and calculations using essentially nothing more than Fermi's Golden Rule. Yet the process involves a mixing of two frequencies, and can therefore be thought of as a nonlinear optical effect. Indeed, one of the key ideas to emerge from the theoretical study of such phenomena is that an interpretation of coherence control effects alternate to that provided by the simple quantum interference picture that is provided by the usual susceptibilities of nonlinear optics. These susceptibilities are, of course, based on quantum mechanics, but the macroscopic viewpoint allows for the identification and classification of the effects in terms of 2nd order nonlinear optical effects, 3rd order optical effects, etc. Indeed, one can generalize many of the processes we have discussed above to a hierarchy of frequency mixing effects or high-order nonlinear processes involving multiple beams with frequency $n\omega, m\omega, p\omega\ldots$ with n, m, p being integers. Many of theses schemes require high intensity of one or more of the beams, but can occur in a simple semiconductor.

Coherent Control of Electrical Current Using Single Color Beams

It is also possible to generate coherence control effects using beams at a single frequency (ω), if one focuses on the two orthogonal components (e.g., x and y) polarization states and uses a noncentrosymmetric semiconductor of reduced symmetry such as a strained cubic semiconductor or a wurtzite material such as CdS or CdSe. In this case, interference between absorption pathways associated with the orthogonal components can lead to electrical current injection given by

$$dJ/dt \propto E^{\omega}E^{\omega}\sin(\phi_{\omega}^{x} - \phi_{\omega}^{y}) \qquad [8]$$

Since in this process current injection is linear in the beam's intensity, the high intensities necessary for two-photon absorption are not necessary. Nonetheless, the efficacy of this process is limited by the fact that it relies on the breaking of center-of-inversion symmetry of the underlying crystal. It is also clear that the maximum current occurs for circularly polarized light and that right and left circularly polarized light lead to a difference in sign of the current injection. Finally, for this particular single beam scheme, when circularly polarized light is used the electrical current is partially spin polarized.

Conclusions

Through the phase of optical pulses it is possible to control electrical and spin currents, as well as carrier density, in bulk semiconductors on a time-scale that is limited only by the rise time of the optical pulse and the intrinsic response of the semiconductor. A few optically based processes that allow one to achieve these types of control have been illustrated here. Although at one level one can understand these processes in terms of quantum mechanical interference effects, at a macroscopic level one can understand these control phenomena as manifestations of nonlinear optical phenomena. For fundamental as well as applied reasons, our discussion has focused on coherence control effects using the continuum states in bulk semiconductors, although related effects can also occur in quantum dot, quantum well, and superlattice semiconductors. Applications of these control effects will undoubtedly exploit the all-optical nature of the process, including the speed at which the effects can be turned on or off. The turn-off effects, although not discussed extensively here, are related to transport phenomena as well as momentum scattering and related dephasing processes.

See also

Semiconductor Physics: Spin Transport and Relaxation in Semiconductors; Spintronics. **Interferometry**: Overview. **Coherent Control:** Experimental; Theory.

Further Reading

Brumer P (1995) Laser control of chemical reactions. *Scientific American* 272: 56.

Rabitz H, de Vivie-Riedle R, Motzkus M and Kompa K (2000) Whither the future of controlling quantum phenomena? *Science* 288: 824.

Shah J (1999) *Ultrafast Spectroscopy of Semiconductors and Semiconductor Nanostructures*. New York: Springer.

van Driel HM and Sipe JE (2001) Coherent control of photocurrents in semiconductors. In: Tsen T (ed.) *Ultrafast Phenomena in Semiconductors*, p. 261. New York: Springer Verlag.

COHERENT LIGHTWAVE SYSTEMS

M J Connelly, University of Limerick, Limerick, Ireland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Conventional optical communication systems are based on the intensity modulation (IM) of an optical carrier by an electrical data signal and direct detection (DD) of the received light. The simplest scheme employs on/off keying (OOK), whereby turning on or off, an optical source transmits a binary 1 or 0. The signal light is transmitted down an optical fiber and at the receiver is detected by a photodetector, as shown in Figure 1. The resulting photocurrent is then processed to determine if a 1 or 0 was received. In the ideal case, where a monochromatic light source is used and where no receiver noise (detector dark current and thermal noise) is present, the probability of error is determined by the quantum nature (shot noise) of the received light. In this case, the number of photons/bit required (sensitivity) at the receiver, to achieve a bit-error-rate (BER) of 10^{-9}, is 10. This is called the quantum-limit. In practical receivers without an optical preamplifier, operating in the 1.3 μm and 1.55 μm optical fiber communication windows, the actual sensitivity is typically 10–30 dB less than the theoretical sensitivity. This is due to receiver noise, in particular thermal noise. This means that the actual sensitivity is between 100 to 10 000 photons/bit. The capacity of IM/DD fiber links can be increased using wavelength division multiplexing (WDM). At the receiver the desired channel is selected using a narrowband optical filter. Some advanced commercial IM/DD systems utilize dense WDM with 50 GHz spacing and single-channel bit rates as high as 40 Gb/s. Indeed, IM/DD systems with terabit (10^{12} bit/s) capacity are now possible.

Compared to IM/DD systems, coherent optical communication systems have greater sensitivity and selectivity. In the context of coherent lightwave systems, the term coherent refers to any technique employing nonlinear mixing between two optical waves on a photodetector, as shown in Figure 2. Typically, one of these is an information-bearing signal and the other is a locally generated wave (local oscillator). The result of this heterodyne process is a modulation of the photodetector photocurrent at a frequency equal to the difference between the signal and local oscillator frequencies. This intermediate frequency (IF) electronic signal contains the information in the form of amplitude, frequency, or phase that was present in the original optical signal. The IF signal is filtered and demodulated to retrieve the transmitted information. An automatic frequency control circuit is required to keep the local-oscillator frequency stable.

It is possible for the information signal to contain a number of subcarriers (typically at microwave frequencies), each of which can be modulated by a separate data channel. It is a simple matter to select the desired channel at the receiver by employing electronic heterodyning and low pass filtering, as shown in Figure 3. In IM/DD systems, channel selection can only be carried out using narrowband optical filters.

Coherent optical communications utilize techniques that were first investigated in radio communications. Most of the basic research work on coherent optical communications was carried out in the 1980s and early 1990s, and was primarily motivated by the need for longer fiber links using no repeaters. Improving receiver sensitivity using coherent techniques made it possible to increase fiber link spans. In the mid-1990s, reliable optical fiber amplifiers became available. This made it possible to construct fiber links using optical amplifiers spaced at appropriate intervals to compensate for fiber and other transmission losses.

The sensitivity of an IM/DD receiver can be greatly improved by the use of an optical preamplifier. Indeed the improvement is so marked that coherent techniques are not a viable alternative to IM/DD in the vast majority of commercial optical communication systems due to their complexity and higher cost. Moreover, because semiconductor lasers with very precise wavelengths and narrowband optical filters can be fabricated, the selectivity advantage of coherent optical communications has become less important. This has meant that the research work currently being carried out on coherent optical communications is very limited, and in particular, very few field trials have been carried out since the early 1990s.

We will review the basic principles underlying coherent optical communications, modulation schemes, detection schemes, and coherent receiver sensitivity. The effects of phase noise and polarization on coherent receiver performance will be outlined. A brief summary of pertinent experimental results will also be presented.


1 0 1
t
Information signal
Photodetector
Filter
Data out
1 0 1
t

Figure 1 IM/DD optical receiver.


Optical combiner
Signal light
E_s
E_{LO}
Photodetector
i_d
IF filter
Demodulator
Data out
Local oscillator
AFC circuit

Figure 2 Basic coherent optical receiver. AFC: automatic frequency control.


Signal light
Photodetector
IF filter
Phase locking
IF oscillator
$\cos(2\pi f_{IF}t)$
Subcarrier oscillator
$\cos(2\pi f_1 t)$
LPF
Demodulator
Channel 1 data out
Local oscillator
Power
Channel 1
f_{IF}
$f_{IF}-f_1$
$f_{IF}+f_1$
f
Channel 1
f_1
f
Channel 1
f_1
f
Channel 1
f_1
f
(a)
(b)
(c)
(d)

Figure 3 Coherent detection and processing of a subcarrier modulated signal lightwave. The power spectrum of the detected signal is shown: (a) after IF filtering; (b) after multiplication by the IF oscillator; (c) after multiplication with the subcarrier oscillator (in this case channel 1's carrier frequency); and (d) after low pass filtering prior to demodulation and data detection. LPF: lowpass filter.

Basic Principles

In coherent detection, a low-level optical signal field E_s is combined with a much larger power optical signal field E_{LO} from a local oscillator laser. E_s and E_{LO} can be written as

$$E_s(t) = \sqrt{2P_s}\cos[2\pi f_s t + \phi_s(t)] \qquad [1]$$

$$E_{LO}(t) = \sqrt{2P_{LO}}\cos[2\pi f_{LO} t + \phi_{LO}(t)] \qquad [2]$$

where P_s, f_s, and ϕ_s are the signal power, optical frequency, and phase (including phase noise), respectively. P_{LO}, f_{LO}, and ϕ_{LO} are the equivalent quantities for the local oscillator. For ideal coherent detection, the polarization states of the signal and local oscillator must be equal. If this is the case, the photocurrent is given by

$$i_d(t) = R[E_s(t) + E_{LO}(t)]^2 \qquad [3]$$

where R is the detector responsivity. Because the detector cannot respond to optical frequencies, we have

$$\begin{aligned} i_d(t) = R\big\{&P_s + P_{LO} + 2\sqrt{P_s P_{LO}} \\ &\times\cos[2\pi f_{IF}t + \phi_s(t) - \phi_{LO}(t)]\big\} \end{aligned} \qquad [4]$$

The IF signal is centered at frequency $f_{IF} = f_s - f_{LO}$. In homodyne detection $f_s = f_{LO}$ and the homodyne signal is centered at baseband. In heterodyne detection $f_s \neq f_{LO}$ and the signal generated by the photodetector is centered around f_{IF} (typically three to six times the bit rate). The IF photocurrent is proportional to $\sqrt{P_s}$, rather than P_s as is the case in direct detection, and is effectively amplified by a factor proportional to $\sqrt{P_{\mathrm{LO}}}$. If P_{LO} is large enough, the signal power can be raised above the receiver noise, thereby leading to a greater sensitivity than possible with conventional IM/DD receivers using p–i–n or avalanche photodiodes. Theoretically it is possible to reach shot noise limited receiver sensitivity although this is not possible in practice. Homodyne optical receivers usually require less bandwidth and are more sensitive than heterodyne receivers but require that the local oscillator is phase locked to the information signal. This requires an optical phase locked loop (OPLL), which is very difficult to design.

Modulation Schemes

The three principal modulation schemes used in coherent optical communications; amplitude shift keying (ASK), frequency shift keying (FSK) and phase shift keying (PSK), are shown in Figure 4. ASK modulation is essentially the same as the OOK scheme used in IM/DD systems. The optical signal is given by

$$E_s(t) = 2a(t)\sqrt{2P_s}\cos[2\pi f_s t + \phi_s(t)] \qquad [5]$$

where $a(t) = 0$ or 1 for transmission of a 0 or 1, respectively. P_s is the average signal power, assuming that it is equally likely that a 0 or 1 is transmitted. ASK modulation can be achieved by modulating the output of a semiconductor laser using an external modulator. The most common type is based on $\mathrm{LiNbO_3}$ waveguides in a Mach–Zehnder interferometer configuration.



Figure 4 Modulation schemes for coherent optical communications: (a) ASK; (b) FSK; and (c) PSK.

In FSK modulation, the optical frequency of the signal lightwave is changed slightly by the digital data stream. In binary FSK, the optical signal is given by

$$E_s(t) = \sqrt{2P_s}\cos[2\pi(f_s + a(t)\Delta f)t + \phi_s(t)] \qquad [6]$$

where $a(t) = -1$ or 1 for transmission of a 0 or 1, respectively. The choice of the frequency deviation Δf depends on the available bandwidth, the bit rate B_T and the demodulation scheme used in the receiver. The modulation index m is given by

$$m = \frac{2\Delta f}{B_T} \qquad [7]$$

The minimum value of m that produces orthogonality (for independent detection of the 0s and 1s) is 0.5. If $m = 0.5$, the signal is referred to as minimum FSK (MFSK). When $m \geq 2$, the signal is referred to as wide-deviation FSK, and when $m < 2$, as narrow-deviation FSK. Wide-deviation FSK receivers are more resilient to phase noise than narrow-deviation FSK receivers. FSK modulation can be achieved using $\mathrm{LiNbO_3}$ external modulators, acoustic optic modulators and distributed feedback semiconductor lasers. The phase of the lightwave does not change between bit transitions.

In PSK modulation, the digital data stream changes the phase of the signal lightwave. In binary PSK the optical signal is given by

$$E_s(t) = \sqrt{2P_s}\cos\left[2\pi f_s t + a(t)\theta + \frac{\pi}{2} + \phi_s(t)\right] \qquad [8]$$

where $a(t) = -1$ or 1 for transmission of a 0 or 1, respectively. The phase shift between a 0 and 1 is $\theta + \pi/2$. Most PSK schemes use $\theta = \pi/2$. PSK modulation can be achieved by using an external phase modulator or a multiple quantum well electroabsorption modulator.

Detection Schemes

There are two classes of demodulation schemes: synchronous and asynchronous. The former exploits the frequency and phase of the carrier signal to perform the detection. The latter only uses the envelope of the carrier to perform the detection. In the following we review the principal demodulation schemes.

PSK Homodyne Detection

In an ideal PSK homodyne receiver, shown in Figure 5, the signal light and local oscillator have identical


Signal light
Photodetector
LPF
Decision circuit
Data out
Local oscillator
Loop filter

Figure 5 PSK homodyne receiver.


Signal light
Photodetector
BPF centered at f_{IF}
x
LPF
Decision circuit
Data out
$\cos(2\pi f_{IF}t)$
Phase locking
Reference oscillator
Local oscillator

Figure 6 PSK synchronous heterodyne receiver. BPF: bandpass filter.


Phase locking
Reference oscillator
$\cos(2\pi f_1 t)$
BPF centered at f_1
x
LPF
+
+
−
Decision circuit
Data out
Signal light
Photodetector
Local oscillator
BPF centered at f_2
x
LPF
$\cos(2\pi f_2 t)$
Phase locking
Reference oscillator

Figure 7 FSK heterodyne synchronous receiver.

optical frequency and phase. If the resulting baseband information signal is positive, then a 1 has been received. If the baseband information signal is negative, then a 0 bit has been received. This scheme has the highest theoretical sensitivity but requires an OPLL and is also highly sensitive to phase noise.

ASK Homodyne Detection

An ideal ASK homodyne receiver is identical to an ideal PSK homodyne receiver. Because the baseband information signal is either zero (0 bit) or nonzero (1 bit), the receiver sensitivity is 3 dB less than the PSK homodyne receiver.

PSK Heterodyne Synchronous Detection

Figure 6 shows an ideal PSK synchronous heterodyne receiver. The IF signal is filtered by a bandpass filter, multiplied by the phase locked reference oscillator to move the signal to baseband, low pass filtered and sent to a decision circuit that decides if the received bit is a 0 or 1. The receiver requires synchronization of the reference oscillator with the IF signal. This is not easy to achieve in practice because of the large amount of semiconductor laser phase noise.

ASK Heterodyne Synchronous Detection

This scheme is basically the same as the PSK heterodyne detection and is similarly difficult to design.

FSK Heterodyne Synchronous Detection

This scheme is shown in Figure 7 for a binary FSK signal consisting of two possible frequencies $f_1 = f_s - \Delta f$ and $f_2 = f_s + \Delta f$. There are two separate branches in which correlation with the two possible IF signals at f_1 and f_2 is performed. The two resulting signals are subtracted from each other and a decision taken on the sign of the difference. Because of the requirement for two electrical phase locked loops, the scheme is not very practical.

ASK Heterodyne Envelope Detection

In this scheme, shown in Figure 8, the IF signal is envelope detected to produce a baseband signal proportional to the original data signal. The output of the envelope detector is relatively insensitive to laser phase noise.

FSK Heterodyne Dual-Filter Detection

In this scheme, shown in Figure 9, two envelope detectors are used to demodulate the two possible IF signals at f_1 and f_2 and a decision taken based on the outputs. The scheme is tolerant to phase noise and can achieve high sensitivity. However, it needs high-bandwidth receiver electronics because a large frequency deviation is required.

FSK Heterodyne Single-Filter Detection

This scheme omits one branch of the FSK heterodyne dual-filter receiver and performs a decision in the same way as for the ASK heterodyne envelope detection. Because half the power of the detected signal is not used, the sensitivity of the scheme is 3 dB worse than the dual-filter scheme.

CPFSK Heterodyne Differential Detection

This scheme, shown in Figure 10, uses the continuous phase (CP) characteristic of an FSK signal, i.e., there is no phase discontinuity at bit transition times. After bandpass filtering, the IF photocurrent is

$$i_{\mathrm{IF}}(t) = A\cos\{2\pi[(f_{\mathrm{IF}} + a(t)\Delta f)]t\} \qquad [9]$$

where $A = R\sqrt{P_{\mathrm{s}}P_{\mathrm{LO}}}$. The output from the delay-line demodulator, after low pass filtering to remove the double IF frequency term, is

$$x(t) = \frac{A^2}{2}\cos\{2\pi[f_{\mathrm{IF}} + a(t)\Delta f]\tau\} \qquad [10]$$

The function of the delay-line demodulator is to act as a frequency discriminator. We require that $x(t)$ is a maximum when $a(t) = 1$ and a minimum when $a(t) = -1$. This is the case if the following relations are satisfied:

$$2\pi(f_{\mathrm{IF}} + \Delta f)\tau = 2\pi k \qquad [11]$$

$$2\pi(f_{\mathrm{IF}} - \Delta f)\tau = (2k-1)\pi, \qquad k \text{ an integer}$$


Signal light
Photodetector
BPF centered at f_{IF}
Envelope detector
LPF
Decision circuit
Data out
Local oscillator

Figure 8 ASK heterodyne envelope receiver.


Signal light
Photodetector
BPF centered at f_1
BPF centered at f_2
Envelope detector
Envelope detector
+
+
−
Decision circuit
Data out
Local oscillator

Figure 9 FSK heterodyne dual-filter receiver.


Signal light
Photodetector
BPF centered at f_{IF}
X
τ
Delay-line demodulator
$x(t)$
LPF
Decision circuit
Data out
Local oscillator

Figure 10 CPFSK heterodyne differential detection receiver.

Hence, we require that

$$\Delta f \tau = \frac{1}{4} \qquad [12]$$

$$f_{\mathrm{IF}}\tau = \left[k - \frac{1}{4}\right], \qquad k \text{ integer}$$

In terms of the modulation index we have

$$\tau = \frac{1}{2mB_{\mathrm{T}}} \qquad [13]$$

The above equation shows that it is possible to decrease the value of τ required by increasing m, thereby reducing the sensitivity of the receiver to phase noise. The minimum value of m possible is 0.5. This scheme can operate with a smaller modulation index compared to the dual-filter and single-filter schemes for a given bit rate, thereby relaxing the bandwidth requirements of the receiver electronics.

DPSK Heterodyne Differential Detection

In differential phase shift key (DPSK) modulation, a 0 is sent by changing the phase of the carrier by π with respect to the previous signal. A 1 is sent by not changing the phase. The receiver configuration is identical to the CPFSK heterodyne differential detection receiver, except that the time delay τ is equal to the inverse of the data rate. Compared to other PSK detection schemes, DPSK differential detection is relatively simple to implement and is relatively immune to phase noise.

Coherent Receiver Sensitivity

The signal-to-noise ratio γ_{c} of an ideal PSK homodyne receiver, in the shot-noise limit, is given by

$$\gamma_{\mathrm{c}} = \frac{2RP_{\mathrm{s}}}{eB_{\mathrm{c}}} \qquad [14]$$

where B_{c} is the receiver bandwidth. The detector responsivity is given by

$$R = \frac{\eta e}{hf_{\mathrm{s}}} \qquad [15]$$

where η is the detector quantum efficiency (≤ 1). The average signal power $P_{\mathrm{s}} = N_{\mathrm{s}} hf_{\mathrm{s}} B_{\mathrm{T}}$, where N_{s} is the average number of photons per bit. If it is assumed that $B_{\mathrm{c}} = B_{\mathrm{T}}$, then

$$\gamma_{\mathrm{c}} = 2\eta N_{\mathrm{s}} \qquad [16]$$

The actual detected number of photons per bit $N_{\mathrm{R}} = \eta N_{\mathrm{s}}$, so

$$\gamma_{\mathrm{c}} = 2N_{\mathrm{R}} \qquad [17]$$

If the noise is assumed to have a Gaussian distribution, then the bit error rate (BER) is given by

$$\mathrm{BER} = \frac{1}{2} erfc\left(\sqrt{2N_{\mathrm{R}}}\right) \qquad [18]$$

where *erfc* is the complementary error function; $erfc(x) \approx \mathrm{e}^{-x^2}/(x\sqrt{\pi})$ for $x > 5$. The receiver sensitivity for a $\mathrm{BER} = 10^{-9}$ is 9 photons/bit.

BER expressions and sensitivity for the demodulation schemes discussed above are listed in Table 1. The sensitivity versus N_{R} is plotted for some of the demodulation schemes in Figure 11. The received signal power required for a given BER is proportional to B_{T}. This dependency is shown in Figure 12 for some of the demodulation schemes.

Table 1 Shot-noise limited BER expressions and sensitivity for coherent demodulation schemes

Modulation scheme	*BER*	*Sensitivity (photons/bit)*
Homodyne		
PSK	$\frac{1}{2} erfc\left(\sqrt{2N_{\mathrm{R}}}\right)$	9
ASK	$\frac{1}{2} erfc\left(\sqrt{N_{\mathrm{R}}}\right)$	18 (peak 36)
Synchronous heterodyne		
PSK	$\frac{1}{2} erfc\left(\sqrt{N_{\mathrm{R}}}\right)$	18
ASK	$\frac{1}{2} erfc\left(\sqrt{\frac{N_{\mathrm{R}}}{2}}\right)$	36 (peak 72)
FSK	$\frac{1}{2} erfc\left(\sqrt{\frac{N_{\mathrm{R}}}{2}}\right)$	36
Asynchronous heterodyne		
ASK (envelope)	$\frac{1}{2}\exp\left(-\frac{N_{\mathrm{R}}}{2}\right)$	40 (peak 80)
FSK (dual-filter)	$\frac{1}{2}\exp\left(-\frac{N_{\mathrm{R}}}{2}\right)$	40
FSK (single-filter)	$\frac{1}{2}\exp\left(-\frac{N_{\mathrm{R}}}{4}\right)$	80
Differential detection		
CPFSK	$\frac{1}{2}\exp(-N_{\mathrm{R}})$	20
DPSK	$\frac{1}{2}\exp(-N_{\mathrm{R}})$	20



Figure 11 Shot-noise limited BER versus number of received photons/bit for various demodulation schemes: (a) PSK homodyne; (b) synchronous PSK; (c) synchronous FSK; (d) ASK envelope; (e) FSK dual-filter; and (f) CPFSK and DPSK.

Phase Noise

A major influence on the sensitivity possible with practical coherent receivers is laser phase noise, which is responsible for laser linewidth (3 dB bandwidth of the laser power spectrum). The effect of phase noise on system performance depends on the modulation and demodulation scheme used. In general, the effects of phase noise are more severe in homodyne and synchronous heterodyne schemes than in asynchronous schemes. If $\Delta\nu_{\mathrm{IF}}$ is the beat linewidth (without modulation present) between the signal and local oscillator lasers, the normalized beat linewidth $\Delta\nu$ is defined as

$$\Delta\nu = \frac{\Delta\nu_{\mathrm{IF}}}{B_{\mathrm{T}}} \qquad [19]$$

where $\Delta\nu_{\mathrm{IF}}$ is the IF phase noise bandwidth. Semiconductor lasers usually have a Lorentzian spectrum in which case $\Delta\nu_{\mathrm{IF}}$ is equal to the sum of the signal and local-oscillator laser linewidths. The requirements placed on $\Delta\nu$ become less severe as the bit rate increases. Table 2 compares the $\Delta\nu$ requirement for a 1 dB power penalty at a BER of 10^{-9} for some of the principal modulation/demodulation schemes.



Figure 12 Required signal power versus bit rate for a BER = 10^{-9} for various shot-noise limited demodulation schemes: (a) PSK homodyne; (b) ASK envelope; and (c) CPFSK. The signal wavelength is 1550 nm and the detector is assumed to have unity quantum efficiency.

Table 2 Required normalized beat linewidth at 1 dB power penalty for a BER = 10^{-9} for various modulation/demodulation schemes

	Modulation scheme	*$\Delta\nu$ (%)*
Homodyne	PSK	6×10^{-4} (balanced loop) 0.01 (decision-driven loop)
Synchronous heterodyne	PSK	0.2–0.5
Asynchronous heterodyne	PSK	0.3–0.7
	ASK (envelope)	3
	FSK (dual-filter)	10–20
Differential detection	CPFSK	0.33 ($m = 0.5$) 0.66 ($m = 1.0$)
	DPSK	0.33

PSK Homodyne Detection – Phase Locked Loop Schemes

Practical homodyne receivers require an OPLL to lock the local-oscillator frequency and phase to that of the signal lightwave. There are a number of OPLL schemes possible for PSK homodyne detection, including the balanced PLL, Costas-type PLL and the decision-driven PLL.

The balanced PLL scheme, shown in Figure 13, requires that the PSK signal uses a phase shift of less than π between a 0 and 1, $E_{\mathrm{s}}(t)$ and $E_{\mathrm{LO}}(t)$ can be written as

$$E_{\mathrm{s}}(t) = \sqrt{2P_{\mathrm{s}}}\cos\left[2\pi f_0 t + a(t)\theta + \phi_{\mathrm{N,s}}(t) + \frac{\pi}{2}\right] \qquad [20]$$

$$E_{\mathrm{LO}}(t) = \sqrt{2P_{\mathrm{LO}}}\cos[2\pi f_0 t + \phi_{\mathrm{N,LO}}(t)] \qquad [21]$$

where f_0 is the common signal and local oscillator optical frequency and $\phi_{\mathrm{N,s}}(t)$ and $\phi_{\mathrm{N,LO}}(t)$ are the signal and local oscillator phase noise, respectively. When $\theta \neq \pi/2$, $E_{\mathrm{s}}(t)$ contains an unmodulated carrier component (residual carrier) in quadrature with the information-bearing signal. $E_{\mathrm{s}}(t)$ and $E_{\mathrm{LO}}(t)$ are combined by an optical 180° hybrid. The output optical signals from the π-hybrid are given by

$$E_1(t) = \frac{1}{\sqrt{2}}[E_{\mathrm{s}}(t) + E_{\mathrm{LO}}(t)] \qquad [22]$$

$$E_2(t) = \frac{1}{\sqrt{2}}[E_{\mathrm{s}}(t) - E_{\mathrm{LO}}(t)] \qquad [23]$$

The voltage at the output of the summing circuit is given by

$$\begin{aligned} v_{\mathrm{L}}(t) = 2RR_{\mathrm{L}}\sqrt{P_{\mathrm{s}}P_{\mathrm{LO}}}\{&a(t)\sin\theta\cos[\phi_{\mathrm{e}}(t)] \\ &+ \cos\theta\sin[\phi_{\mathrm{e}}(t)]\} \end{aligned} \qquad [24]$$

where the photodetectors have the same responsivity and load resistance R_{L}. The phase error is given by

$$\phi_{\mathrm{e}}(t) = \phi_{\mathrm{N,s}}(t) - \phi_{\mathrm{N,LO}}(t) - \phi_{\mathrm{c}}(t) \qquad [25]$$

$\phi_{\mathrm{c}}(t)$ is the controlled phase determined by the control signal $v_{\mathrm{c}}(t)$ at the output of the loop filter. v_{L} contains two terms; an information-bearing signal proportional to $\sin\theta$, which is processed by the data detection circuit, and a phase error signal proportional to $\cos\theta$ used by the PLL for locking. The power penalty, due to the residual carrier transmission, is $10\log_{10}(1/\sin^2\theta)$ dB.

This scheme is not practical because the $\Delta\nu$ needed for a power penalty of <1 dB is typically less than 10^{-5}. This would require that $\Delta\nu_{\mathrm{IF}} < 10$ kHz for


Signal light
E_s
E_1
π-hybrid directional coupler
Photodetector-1
Photodetector-2
E_{LO}
E_N
R_L
R_L
+
−
x
v_L
Data detection
Data out
Local oscillator
v_c
Loop filter

Figure 13 PSK homodyne balanced PLL receiver.


Signal light
π-hybrid directional coupler
Photodetector-1
Photodetector-2
R_L
R_L
LPF
Decision circuit
Data out
x
1-bit delay
Local oscillator
Loop filter

Figure 14 PSK decision-driven PLL.

a data rate of 1 Gb/s. The narrow signal and local-oscillator linewidths required are only achievable with external cavity semiconductor lasers.

The Costas-type and decision-driven PLLs also utilize π-hybrids and two photodetectors but as they have full suppression of the carrier ($\theta = \pi/2$), nonlinear processing of the detected signals is required to produce a phase error signal that can be used by the PLL for locking. In the decision-driven PLL, shown in Figure 14, the signal from one of the photodetector outputs is sent to a decision circuit and the output of the circuit is multiplied by the signal from the second photodetector. The mixer output is sent back to the local oscillator laser for phase locking. The $\Delta\nu$ required for a power penalty of <1 dB is typically less than 2×10^{-4}. This is superior to both the balanced PLL and Costas-type PLL receivers.

Heterodyne Phase Locking

In practical synchronous heterodyne receivers phase locking is performed in the electronic domain utilizing techniques from radio engineering. In the PSK case, electronic analogs of the OPLL schemes used in homodyne detection can be used. Synchronous heterodyne schemes have better immunity to phase noise than the homodyne schemes.

Asynchronous Systems

Asynchronous receivers do not require optical or electronic phase locking. This means that they are less sensitive to phase noise than synchronous receivers. They do have some sensitivity to phase noise because IF filtering leads to phase-to-amplitude noise conversion.

Differential Detection

Differential detection receivers have sensitivities to phase noise between synchronous and asynchronous receivers because, while they do not require phase locking, they use phase information in the received signal.

Phase-Diversity Receivers

Asynchronous heterodyne receivers are relatively insensitive to phase noise but require a much higher receiver bandwidth for a given bit rate. Homodyne receivers only require a receiver bandwidth equal to the detected signal bandwidth but require an OPLL, which is difficult to implement. The phase diversity receiver, shown in Figure 15, is an asynchronous homodyne scheme, which does not require the use of an OPLL and has a bandwidth approximately equal to synchronous homodyne detection. This is at the expense of increased receiver complexity and reduced sensitivity compared to synchronous homodyne detection. The phase-diversity scheme can be used with ASK, DPSK, and CPFSK modulation. ASK modulation uses an squarer circuit for the demodulator component, while DPSK and CPFSK modulation use a delay line and mixer.



Figure 15 Multiport phase-diversity receiver. PD: photodetector.

In the case of ASK modulation, the outputs of the N-port hybrid can be written as

$$E_k(t)=\frac{1}{\sqrt{N}}\left\{a(t)\sqrt{2P_s}\cos\left[2\pi f_s t+\phi_s(t)+\frac{2\pi k}{N}\right]\right. \\ \left.+\sqrt{2P_{LO}}\cos[2\pi f_{LO}t+\phi_{LO}(t)]\right\}, \\ k=1,2,\ldots,N,\ N\geq 3 \qquad [26]$$

For $N=2$, the phase term is $\pi/2$ for $k=2$. The voltage input to the k-th demodulator (squarer), after the dc terms have been removed by the blocking capacitor, is given by

$$v_k(t)=a(t)\frac{RR_L}{N}2\sqrt{P_sP_{LO}}\cos\left[2\pi(f_s-f_{LO})\right. \\ \left.+\phi_s(t)-\phi_{LO}(t)+\frac{2\pi k}{N}\right] \qquad [27]$$

These voltages are then squared and added to give an output voltage

$$v_L(t)=\alpha\left(\frac{RR_L}{N}\right)^2 4P_sP_{LO}a(t)\sum_{k=1}^{N}\left\{1+\cos\left[4\pi\right.\right. \\ \left.\left.\times\left(f_s-f_{LO}\right)t+2\phi_s(t)-2\phi_{LO}(t)+\frac{4\pi k}{N}\right]\right\} \qquad [28]$$

where α is the squarer parameter. The lowpass filter at the summing circuit output effectively integrates $v_L(t)$ over a bit period. If $2(f_s-f_{LO})\ll B_T$ and the difference between the signal and local oscillator phase noise is small within a bit period, then the input voltage to the decision circuit is

$$v_D(t)=\alpha\frac{(RR_L)^2}{N}4P_sP_{LO}a(t) \qquad [29]$$

which is proportional to the original data signal. In shot-noise limited operation, the receiver sensitivity is 3 dB worse than the ASK homodyne case. The scheme is very tolerant of laser phase noise. The $\Delta\nu$ for a power penalty of <1 dB is of the same order as for ASK heterodyne envelope detection.

Polarization

The mixing efficiency between the signal and local-oscillator lightwaves is a maximum when their polarization states are identical. In practice the polarization state of the signal arriving at the receiver is unknown and changes slowly with time. This means that the IF photocurrent can change with time and in the worst case, when the polarization states of the signal and local-oscillator are orthogonal, the IF photocurrent will be zero. There are a number of possible solutions to this problem.

1. Polarization maintaining (PM) fiber can be used in the optical link to keep the signal polarization from changing. It is then a simple matter to adjust the local-oscillator polarization to achieve optimum mixing. However, the losses associated with PM fiber are greater than for conventional single-mode (SM) fiber. In addition most installed fiber is SM fiber.
2. An active polarization controller, such as a fiber coil using bending-induced birefringence, can be used to ensure that the local-oscillator polarization tracks the signal polarization.
3. A polarization scrambler can be used to scramble the polarization of the transmitted signal at a speed greater than the bit rate. The sensitivity degradation due to the polarization scrambling is 3 dB compared to a receiver with perfect polarization matching. However, this technique is only feasible at low bit rates.
4. The most general technique is to use a polarization-diversity receiver, as shown in Figure 16. In this scheme, the signal light and local-oscillator



Figure 16 Polarization-diversity receiver.

Table 3 General comparisons between various modulation/demodulation schemes. The sensitivity penalty is relative to ideal homodyne PSK detection

Modulation/demodulation scheme	*Sensitivity penalty (dB)*	*Immunity to phase noise*	*IF bandwidth/bit rate*	*Complexity*
Homodyne PSK	0	Very poor	1	Requires an OPLL
Synchronous heterodyne PSK	3	Poor	3–6	Requires electronic phase locking
Asynchronous heterodyne FSK (dual-filter)	6.5	Excellent	3–6	High bandwidth IF circuits and two envelope detectors required
Differential detection CPFSK	3.5	Moderate	≈2	Relatively simple
DPSK	3.5	Moderate	≈2	Relatively simple

are split into orthogonally polarized lightwaves by a polarization beamsplitter. The orthogonal components of the signal and local-oscillator are separately demodulated and combined. The resulting decision signal is polarization independent. The demodulator used depends on the modulation format.

Comparisons Between the Principal Demodulation Schemes

General comparisons between the demodulation schemes discussed above are given in Table 3. FSK modulation is relatively simple to achieve. FSK demodulators have good receiver sensitivity and low immunity to phase noise. PSK modulation is also easy to achieve and gives good receiver sensitivity. ASK modulation has no real merit compared to FSK or PSK.

In general, homodyne schemes have the best theoretical sensitivity but require optical phase locking and are very sensitive to phase noise. Phase diversity receivers are a good alternative to homodyne receivers, in that they do not require an OPLL. Asynchronous heterodyne receivers have similar sensitivities to synchronous receivers but are much less complex. However, they require an IF bandwidth much greater than the data rate.

Differential detection schemes have good receiver sensitivity, do not require wide bandwidth IF circuits and have moderate immunity to phase noise. The advantage of CPFSK over DPSK is that the immunity to phase noise can be increased by increasing the FSK modulation index.

Table 4 Coherent systems experiments. The penalty is with respect to the theoretical sensitivity

Receiver	*Bit rate (Mb/s)*	*Sensitivity (dBm)*		*Penalty (dB)*
		dBm	*Photons/bit*	
ASK	400	−47.2	365	9.7
FSK (dual-filter)	680	−39.1	1600	16
CPFSK ($m = 0.5$)	1000	−37	1500	18.6
differential detection	4000	−31.3	1445	18.6
DPSK	400	−53.3	45.1	3.5
	2000	−39.0	480	13.8

Polarization diversity receivers can be used with any modulation/demodulation scheme and offer the most general approach to overcoming polarization effects.

System Experiments

Most coherent communication system experiments date from the 1980s and early 1990s and were based on the technology available at that time. This restricted the bit rates possible to typically <4 Gb/s. Some coherent systems experimental results obtained around this time are listed in Table 4. All of the listed experimental trials used lasers (usually external cavity lasers) with negligible phase noise in the 1550 nm region. It can be seen that the measured sensitivities deteriorate at higher bit rates. This is attributable to the nonuniform response and bandwidth limitations of the modulator, photodetector, and demodulator. There is no doubt that the performance could be improved by the use of current optoelectronic technologies.

Conclusion

Coherent optical communication systems offer the potential for increased sensitivity and selectivity compared to conventional IM/DD systems. However, coherent optical receivers are more complex and have more stringent design parameters compared to IM/DD receivers. Moreover, advances in optoelectronic component design and fabrication along with the advent of reliable optical amplifiers has meant that coherent systems are not a viable alternative to IM/DD systems in the vast majority of optical communication systems.

List of Units and Nomenclature

e	Electronic charge
h	Planck constant

See also

Modulators: Modulation and Demodulation of Optical Signals. **Optical Amplifiers:** Basic Concepts; Erbium Doped Fiber Amplifiers for Lightwave Systems; Optical Amplifiers in Long-Haul Transmission Systems. **Optical Communication Systems:** Architectures of Optical Fiber Communication Systems; Lightwave Transmitters; Wavelength Division Multiplexing. **Polarization:** Introduction.

Further Reading

Barry JR and Lee EA (1990) Performance of coherent optical receivers. *IEEE Proceedings* 78: 1369–1394.

Cvijetic M (1996) *Coherent and Nonlinear Lightwave Communications*. Boston, MA: Artech House.

Kazovsky LG (1989) Phase- and polarization-diversity coherent optical techniques. *Journal of Lightwave Technology* 7: 279–292.

Kazovsky L, Benedetto S and Willner A (1996) *Optical Fiber Communication Systems*. Boston, MA: Artech House.

Linke RA and Gnauck AH (1988) High-capacity coherent lightwave systems. *Journal of Lightwave Technology* 6: 1750–1769.

Ryu S (1995) *Coherent Lightwave Systems*. Boston, MA: Artech House.

COHERENT TRANSIENTS

Contents

Coherent Transient Spectroscopy in Atomic and Molecular Vapors
Foundations of Coherent Transients in Semiconductors
Ultrafast Studies of Semiconductors

Coherent Transient Spectroscopy in Atomic and Molecular Vapors

P R Berman, University of Michigan, Ann Arbor, MI, USA

R G Brewer, Stanford University, Stanford, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical spectroscopy is a method that allows one to determine atomic and molecular transition frequencies, as well as relaxation rates in atomic and molecular vapors. The transition frequencies serve as ‘fingerprints’ that can be used to identify and classify atoms and molecules. Optical spectroscopic methods fall into two broad categories, continuous wave (cw) or stationary spectroscopy and time-dependent or transient spectroscopy. In cw spectroscopy, the absorption or emission line shapes are measured as a function of the frequency of a probe field. On the basis of theoretical line shape formulas, it is then possible to extract the relevant transition frequencies and relaxation rates from the line shapes. In transient optical spectroscopy, pulsed optical fields are used to create atomic state populations or coherences between atomic states. Following the excitation, the time-evolution of the atoms is monitored, from which transition frequencies and relaxation rates can be obtained.

The earliest coherent transient effects were observed with atomic nuclear spins in about 1950 by H C Torrey, who discovered transient spin nutation, and by E L Hahn who detected spin echoes and free induction decay (FID). The optical analogs of these and other nuclear magnetic resonance (NMR) effects have now been detected using either optical pulses or techniques involving Stark or laser frequency switching.

In this brief introduction to coherent optical transients, several illustrative examples of coherent transient phenomena are reviewed. The optical Bloch equations are derived and coupled to Maxwell's Equations. The Maxwell–Bloch formalism is used to analyze free precession decay, photon echoes, stimulated photon echoes, and optical Ramsey fringes. Experimental results are presented along with the relevant theoretical calculations. In addition, coherent transient phenomena involving quantized matter waves are discussed. Although the examples considered in this chapter are fairly simple, it should be appreciated that sophisticated coherent transient techniques are routinely applied as a probe of complex structures such as liquids and solids or as a probe of single atoms and molecules.

Optical Bloch Equations

Many of the important features of coherent optical transients can be illustrated by considering the interaction of a radiation field with a two-level atom. The lower state $|1\rangle$ has energy $-\hbar\omega_0/2$ and upper state $|2\rangle$ has energy $\hbar\omega_0/2$. For the moment, the atom is assumed to be fixed at $\mathbf{R} = 0$ and all relaxation processes are neglected. The incident electric field is

$$\mathbf{E}(\mathbf{R}=0,t) = \frac{1}{2}\boldsymbol{\varepsilon}[E(t)e^{-i\omega t} + E(t)e^{i\omega t}] \qquad [1]$$

where $E(t)$ is the field amplitude, $\boldsymbol{\varepsilon}$ is the field polarization and ω is the carrier frequency. The time dependence of $E(t)$ allows one to consider pulses having arbitrary shape. A time-dependent phase for the field could have been included, allowing one to consider the effect of arbitrary frequency 'chirps,' but such effects are not included in the present discussion. It is convenient to expand the atomic state wave function in a field interaction representation as

$$|\psi(t)\rangle = c_1(t)e^{i\omega t/2}|1\rangle + c_2(t)e^{-i\omega t/2}|2\rangle \qquad [2]$$

The atom-field interaction potential is

$$V(\mathbf{R},t) = -\boldsymbol{\mu}\cdot\mathbf{E}(\mathbf{R},t) \qquad [3]$$

where $\boldsymbol{\mu}$ is a dipole moment operator. When eqn [2] is substituted into Schrödinger's equation and rapidly varying terms are neglected (rotating-wave approximation), one finds that the state amplitudes evolve according to

$$i\hbar\frac{\mathrm{d}\mathbf{c}}{\mathrm{d}t} = \tilde{\mathbf{H}}\mathbf{c}; \qquad \tilde{\mathbf{H}} = (\hbar/2)\begin{pmatrix} -\delta_0 & \Omega_0(t) \\ \Omega_0(t) & \delta_0 \end{pmatrix} \qquad [4]$$

where $\mathbf{c}$ is a vector having components (c_1, c_2)

$$\delta_0 = \omega_0 - \omega \qquad [5]$$

is an atom-field detuning

$$\Omega_0(t) = -\frac{\mu E(t)}{\hbar} = -\frac{\mu}{\hbar}\sqrt{\frac{2S(t)}{\varepsilon_0 c}} \qquad [6]$$

is a Rabi frequency, $\mu = \langle 1|\mu\cdot\varepsilon|2\rangle = \langle 2|\mu\cdot\varepsilon|1\rangle$ is a dipole moment matrix element, ε_0 is the permittivity of free space, and $\mathbf{S}(t)$ is the time-averaged Poynting vector of the field. Equation [4] can be solved numerically for arbitrary pulse envelopes.

Expectation values of physical observables are conveniently expressed in terms of density matrix elements defined by

$$\rho_{ij} = c_i c_j^* \qquad [7]$$

which obey equations of motion

$$\begin{aligned} \dot\rho_{11} &= -i\Omega_0(t)(\rho_{21} - \rho_{12})/2 \\ \dot\rho_{22} &= i\Omega_0(t)(\rho_{21} - \rho_{12})/2 \\ \dot\rho_{12} &= -i\Omega_0(t)(\rho_{22} - \rho_{11})/2 + i\delta_0\rho_{12} \\ \dot\rho_{21} &= i\Omega_0(t)(\rho_{22} - \rho_{11})/2 - i\delta_0\rho_{21} \end{aligned} \qquad [8]$$

An alternative set of equations in terms of real variables can be obtained if one defines new parameters

$$\begin{aligned} u &= \rho_{12} + \rho_{21}; & \rho_{12} &= (u + iv)/2 \\ v &= i(\rho_{21} - \rho_{12}); & \rho_{21} &= (u - iv)/2 \\ w &= \rho_{22} - \rho_{11}; & \rho_{22} &= (m + w)/2 \\ m &= \rho_{11} + \rho_{22}; & \rho_{11} &= (m - w)/2 \end{aligned} \qquad [9]$$

which obey

$$\begin{aligned} \dot u &= -\delta_0 v \\ \dot v &= \delta_0 u - \Omega_0(t) w \\ \dot w &= \Omega_0(t) v \\ \dot m &= 0 \end{aligned} \qquad [10]$$

The last of these equations reflects the fact that $\rho_{11} + \rho_{22} = 1$, while the first three can be rewritten as

$$\dot{\mathbf{U}} = \boldsymbol{\Omega}(t) \times \mathbf{U} \qquad [11]$$

where the *Bloch vector* $\mathbf{U}$ has components (u, v, w) and the *pseudofield vector* $\boldsymbol{\Omega}(t)$ has components $[\Omega_0(t), 0, \delta_0]$.

Equations [8] or [10] constitute the optical Bloch equations without decay. The vector $\mathbf{U}$ has unit magnitude and traces out a path on the Bloch sphere as it precesses about the pseudofield vector. The component w is the population difference of the two atomic states, while u and v are related to the quadrature components of the atomic polarization (see below).

Equations [8] and [10] can be generalized to include relaxation. A simplified relaxation scheme that has a wide range of applicability is one in which state 2 decays spontaneously to state 1 with rate γ_2, while the relaxation of the coherence ρ_{12} is characterized by a complex decay parameter Γ_{12}, resulting from phase-changing collisions with a background gas. When such processes are included in eqn [8], they are modified as

$$\dot{\rho}_{11} = -i\Omega_0(t)(\rho_{21} - \rho_{12})/2 + \gamma_2\rho_{22} \qquad [12a]$$

$$\dot{\rho}_{22} = i\Omega_0(t)(\rho_{21} - \rho_{12})/2 - \gamma_2\rho_{22} \qquad [12b]$$

$$\dot{\rho}_{12} = -i\Omega_0(t)(\rho_{22} - \rho_{11})/2 - \gamma\rho_{12} + i\delta\rho_{12} \qquad [12c]$$

$$\dot{\rho}_{21} = i\Omega_0(t)(\rho_{22} - \rho_{11})/2 - \gamma\rho_{21} - i\delta\rho_{21} \qquad [12d]$$

where $\gamma = \gamma_2/2 + \mathrm{Re}(\Gamma_{12})$ and the detuning $\delta = \delta_0 - \mathrm{Im}(\Gamma_{12})$ is modified to include the collisional shift. With the addition of decay, the length of the Bloch vector is no longer conserved. The quantity γ_2 is referred to as the longitudinal relaxation rate. Moreover, one usually refers to $T_1 = \gamma_2^{-1}$ as the longitudinal relaxation time and $T_2 = \gamma^{-1}$ as the transverse relaxation time. In the case of purely radiative broadening, $\gamma_2 = 2\gamma$ and $T_1 = T_2/2$.

Maxwell–Bloch Equations

As a result of atom-field interactions, it is assumed that a polarization is created in the medium of the form

$$\mathbf{P}(\mathbf{R}, t) = \frac{1}{2}\boldsymbol{\varepsilon}\left[P(Z,t)e^{i[kZ-\omega t]} + P^*(Z,t)e^{-i[kZ-\omega t]}\right] \qquad [13]$$

which gives rise to a signal electric field of the form

$$\mathbf{E}_s(\mathbf{R}, t) = \frac{1}{2}\boldsymbol{\varepsilon}\left[E_s(Z,t)e^{i[kZ-\omega t]} + E_s^*(Z,t)e^{-i[kZ-\omega t]}\right] \qquad [14]$$

The z-axis has been chosen in the direction of $\mathbf{k}$. It follows from Maxwell's equations that the quasi-steady-state field amplitude is related to the polarization by

$$\frac{\partial E_s(Z,t)}{\partial Z} = \frac{ik}{2\varepsilon_0}P(Z,t) \qquad [15]$$

To arrive at eqn [15], it is necessary to assume that transverse field variations can be neglected, that the *phase matching* condition $k = \omega/c$ is met, and that the complex field amplitudes $P(Z,t)$ and $E_s(Z,t)$ vary slowly in space compared with e^{ikZ} and slowly in time compared with $e^{i\omega t}$.

The polarization $\mathbf{P}(\mathbf{R}, t)$, defined as the average dipole moment per unit volume, is given by the expression

$$\mathbf{P}(\mathbf{R}, t) = \mathcal{N}\Big[\boldsymbol{\mu}_{21}\langle\rho_{12}(Z,t)\rangle e^{-i[kZ-\omega t]} + \boldsymbol{\mu}_{12}\langle\rho_{21}(Z,t)\rangle e^{i[kZ-\omega t]}\Big] \qquad [16]$$

where $\mathcal{N}$ is the atomic density and $\rho_{12}(Z,t)$ and $\rho_{21}(Z,t)$ are single-particle density matrix elements that depend on the atomic properties of the medium. As such, eqn [16] provides the link between Maxwell's equations and the optical Bloch equations. The $\langle\ \rangle$ brackets in eqn [16] indicate that there may be additional averages that must be carried out. For example, in a vapor, there is a distribution of atomic velocities that must be summed over, while, in a solid, there may be an inhomogeneous distribution of atomic frequencies owing to local strains in the media. By combining eqns [9], [13], [15] and [16], and using the fact that $\mu = \mu_{12}\cdot\varepsilon = \mu_{21}\cdot\varepsilon$, one arrives at

$$\begin{aligned}\frac{\partial E_s(Z,t)}{\partial Z} &= \frac{ik\mathcal{N}\mu}{\varepsilon_0}\langle\rho_{21}(Z,t)\rangle \\ &= \frac{ik\mathcal{N}\mu}{2\varepsilon_0}\langle u(Z,t) - iv(Z,t)\rangle \end{aligned} \qquad [17]$$

which, together with eqn [12], constitute the Maxwell–Bloch equations. From eqn [17], it is clearly seen that the coherence $\langle\rho_{21}(Z,t)\rangle$ drives the signal field. If $\langle\rho_{21}(Z,t)\rangle$ is independent of Z, the intensity of radiation exiting a sample of length L is proportional to

$$I(L,t) = \frac{k\mathcal{N}\mu L}{\varepsilon_0}{}^2|\langle\rho_{21}(t)\rangle|^2 \qquad [18]$$

Alternatively, the outgoing field can be heterodyned with a reference field to extract the field amplitude rather than the field intensity.

Coherent Transient Signals

The Maxwell–Bloch equations can be used to describe the evolution of coherent transient signals. In a typical experiment, one applies one or more 'short' radiation pulses to an atomic sample and monitors the radiation field emitted by the atoms following the pulses. A 'short' pulse, is one satisfying

$$|\delta|\tau, ku\tau, \gamma\tau, \gamma_2\tau \ll 1 \qquad [19]$$

where τ is the pulse duration. Conditions [19] allow one to neglect any effects of detuning (including Doppler shifts or other types of inhomogeneous broadening) or relaxation during the pulse's action. The evolution of the atomic density matrix during each pulse is determined solely by the pulse area defined by

$$\theta = \int_{-\infty}^{\infty} \Omega_0(t)\mathrm{d}t \qquad [20]$$

In terms of density matrix elements in a standard interaction representation defined by

$$\begin{aligned} \rho_{12}^I &= \rho_{12}e^{-i[kZ+\delta t]}, \quad & \rho_{21}^I &= \rho_{21}e^{i[kZ+\delta t]}, \\ \rho_{22}^I &= \rho_{22}, & \rho_{11}^I &= \rho_{11} \end{aligned}$$

the change in density matrix elements for an interaction occurring at time T_j is given by

$$\begin{pmatrix} \rho_{11}^I \\ \rho_{22}^I \\ \rho_{12}^I \\ \rho_{21}^I \end{pmatrix}^+ = \frac{1}{2}\begin{pmatrix} 1+\cos\theta_j & 1-\cos\theta_j & i\sin\theta_j e^{i\Phi(T_j)} & -i\sin\theta_j e^{-i\Phi(T_j)} \\ 1-\cos\theta_j & 1+\cos\theta_j & -i\sin\theta_j e^{i\Phi(T_j)} & i\sin\theta_j e^{-i\Phi(T_j)} \\ i\sin\theta_j e^{-i\Phi(T_j)} & -i\sin\theta_j e^{-i\Phi(T_j)} & 1+\cos\theta_j & (1-\cos\theta_j)e^{-2i\Phi(T_j)} \\ -i\sin\theta_j e^{i\Phi(T_j)} & i\sin\theta_j e^{i\Phi(T_j)} & (1-\cos\theta_j)e^{2i\Phi(T_j)} & 1+\cos\theta_j \end{pmatrix}\begin{pmatrix} \rho_{11}^I \\ \rho_{22}^I \\ \rho_{12}^I \\ \rho_{21}^I \end{pmatrix}^- \qquad [21]$$

where $\mp$ superscripts refer to times just before and after the pulse

$$\Phi(T_j) = \mathbf{k}\cdot\mathbf{R}(T_j) + \delta T_j$$

$$\mathbf{R}(T_j) = \mathbf{R} - \mathbf{v}(t - T_j)$$

θ_j is the pulse area, and $\mathbf{v}$ is the atomic velocity. Between pulses, or following the last pulse, the atoms evolve freely in the absence of any applied fields. The density matrix elements evolve as

$$\begin{aligned} \dot{\rho}_{11}^I &= \gamma_2\rho_{22}^I; \quad & \dot{\rho}_{22}^I &= -\gamma_2\rho_{22}^I; \\ \dot{\rho}_{12}^I &= -\gamma\rho_{12}^I; & \dot{\rho}_{21}^I &= -\gamma\rho_{21}^I \end{aligned} \qquad [22]$$

A coherent transient signal is constructed by piecing together field interaction zones and free evolution periods. There are many different types of coherent transient signals. A few illustrative examples are given below.

Free Polarization Decay

Free polarization decay (FPD), also referred to as optical FID, is the optical analog of free induction decay (FID) in NMR. This transient follows preparation of the atomic sample by any of three methods: (1) an optical pulse resonant with the atomic transition; (2) a Stark pulse that switches the transition frequency of a molecule (atom) into resonance with an incident *cw* laser beam; or (3) an electronic pulse that switches the frequency of a *cw* laser into coincidence with the molecular (atomic) transition frequency. In methods (2) and (3), the FPD emission propagates coherently in the forward direction along with the *cw* laser beam, automatically generating a heterodyne beat signal at a detector that can be orders of magnitude larger than the FPD signal. The FPD field intensity itself exiting the sample is equal to

$$\begin{aligned} I(L,t) &= \left(\frac{k\mathcal{N}\mu L}{\varepsilon_0}\right)^2 |\langle\rho_{21}(t)\rangle|^2 \\ &= \left(\frac{k\mathcal{N}\mu L}{2\varepsilon_0}\sin\theta\right)^2 \left|\int \mathrm{d}\mathbf{v}\, W_0(\mathbf{v})e^{-[\gamma - i(\delta+\mathbf{k}\cdot\mathbf{v})]t}\right|^2 \end{aligned} \qquad [23]$$

For a Maxwellian velocity distribution

$$W_0(\mathbf{v}) = \frac{1}{(\pi u^2)^{3/2}} e^{-(v/u)^2} \qquad [24]$$

where u is the most probable atomic speed, one finds

$$I(L,t) = \left(\frac{k\mathcal{N}\mu L}{2\varepsilon_0}\sin\theta\right)^2 e^{-2\gamma t}e^{-(kut)^2/2} \qquad [25]$$



Figure 1 Pulse sequence and signal intensity for free precession decay. In this and subsequent figures, time is measured in units of 2/*ku*.

If $ku \gg \gamma$, the signal decays mainly owing to inhomogeneous broadening, as shown in Figure 1. Owing to different Doppler shifts for atoms having different velocities, the optical dipoles created by the pulse lose their relative phase in a time of order $T_2^* = 2/ku$. The FPD signal can be used to measure T_2^*, which can be viewed as an inhomogeneous, transverse relaxation time. At room temperature ku/γ is typically of order of 100.

When FPD signals are observed using laser frequency switching, method 3 above, the *cw* field can modify the molecular velocity distribution, exciting only those atoms having $\mathbf{k} \cdot \mathbf{v} = -\delta \pm \gamma'$, where γ' is a power broadened homogeneous width. In the linear field regime, the FPD signal again decays on a time scale of order $(ku)^{-1}$, since the velocity distribution is unchanged to first order in the field amplitude. When one considers nonlinear interactions with the field, however, the *cw* field excites a narrow velocity subclass that is no longer subject to inhomogeneous broadening. These atoms give rise to a contribution to the FPD signal that decays with rate $T_2^{-1} = (\gamma + \gamma')$. Thus by using nonlinear atom-field interactions, one can extract homogeneous decay rates in situations where there is large inhomogeneous broadening. The price one pays is that only a small percentage of the atoms (those having velocities for which the applied field is resonant) contribute to the signal.



Figure 2 Optical free precession decay in Cs using an excitation pulse having 20 ns duration. Reproduced with permission from Lehmitz H and Harde H (1986) In: Prior Y, Ben-Reuven A and Rosenbluh M (eds) *Methods of Laser Spectroscopy*, pp. 109–112. New York: Plenum.



Figure 3 Optical free precession in NH_2D using the Stark switching technique. Reproduced with permission from Brewer RG and Shoemaker RL (1972) Optical free induction decay. *Physical Review A* 6: 2001. Copyright (1972) by the American Physical Society.

A FPD signal obtained on the D_2 transition in Cs is shown in Figure 2, where $T_2^* = 1.4$ ns. Oscillations in the signal originate from ground state hyperfine splitting. Figure 3 represents a FPD signal obtained in NH_2D at 10.6 μm using the method of Stark switching with *cw* state preparation. The oscillations are the heterodyne beat signal while the slowly varying increase in the signal is the result of optical nutation of molecules switched into resonance by the Stark pulse. The FPD signal manifests itself as a reduction of the amplitude of the oscillation with time. This amplitude decays with the (power-broadened) homogeneous decay rate γ'.

Photon Echo

Although the FPD signal produced by short excitation pulses decays in a time of order $(ku)^{-1}$, the coherence of individual atoms decays in a much longer time, T_2.



Figure 4 Pulse sequence and signal intensity for the photon echo.

The question arises as to whether it is possible to bring all the atomic dipoles back into phase so they can radiate a coherent signal. The photon echo accomplishes this goal, although it has very little to do with either photons or echoes. The pulse sequence and echo signal are shown in Figure 4. The first pulse creates a phased array of dipoles, which begin to dephase owing to inhomogeneous broadening. At time T_{21} the second pulse provides a nonlinear interaction that couples ρ_{12} and ρ_{21}. As a result of the second pulse, the dipoles begin a rephasing process that is completed at time $t = 2T_{21}$. The 'echo' appears at this time. The echo intensity exiting the sample is

$$\begin{aligned} I(L,t) &= \left(\frac{k\mathcal{N}\mu L}{\varepsilon_0}\right)^2 |\langle\rho_{21}(t)\rangle|^2 \\ &= \left(\frac{k\mathcal{N}\mu L}{2\varepsilon_0}\sin\theta_1 \sin^2(\theta_2/2)\right)^2 \\ &\quad \times e^{-4\gamma T_{21}} e^{-k^2u^2(t-2T_{21})^2/2} \end{aligned} \qquad [26]$$

If the echo intensity is measured as a function of T_{21}, one can extract the homogeneous decay rate $\gamma = T_{21}^{-1}$. It is interesting to note that the echo intensity near $t = 2T_{21}$ mirrors the FPD intensity immediately following the first pulse. For experimental reasons, it is often convenient to use a different propagation vector for the second pulse. If $\mathbf{k}_1$ and $\mathbf{k}_2$ are propagation vectors of the first and second pulses, the echo signal is in the direction $\mathbf{k} = 2\mathbf{k}_2 - \mathbf{k}_1$, provided $|\mathbf{k}_2 - \mathbf{k}_1|/k_1 \ll 1$.

The echo signal is sensitive only to $\rho_{21}(t)$ and $\rho_{12}(t)$ in the entire time interval of interest. Any interaction that results in a degradation of the dephasing–rephasing process for these density matrix elements leads to a decrease in the echo intensity. As such, echo signals can serve as a probe of transverse relaxation. Transverse relaxation generally falls into two broad categories. First, there are dephasing processes which produce an exponential damping of the coherences and contribute to γ. Second there is *spectral diffusion*; in a vapor, spectral diffusion is produced by velocity-changing collisions that change the effective field frequency seen by the atoms owing to the Doppler effect. Such terms enter the optical Bloch equations as *integral* terms, transforming the equations into differentio-integral equations. In general, the phase-changing and velocity-changing aspects of collisions are entangled; however, if the collisional interaction is *state-independent*, as it is for some molecular transitions, then collisions are purely velocity-changing in nature, leading to an echo that decays exponentially as T_{21}^3 for early times and T_{21} for later times. For electronic transitions, collisions are mainly phase-changing in nature, but there is a velocity-changing contribution that persists in the forward diffractive scattering cone. Photon echo techniques are sufficiently sensitive to measure the relaxation caused by such diffractive scattering.

The photon echo was first observed by NA Kurnit and co-workers, using a pulsed ruby laser (Figure 5). In Stark switching experiments, the photon echo follows two Stark pulses as shown in Figure 6. The effects of velocity-changing collisions on the photon echo signal in a CH_3F molecular vapor is represented in Figure 7. The signal exhibits exponential decay varying as T_{21}^3 for early times and T_{21} for later times. A theoretical interpretation of the observed echo decay permits a determination of the binary collision parameters for CH_3F, namely, the characteristic velocity jump $\Delta u_{\mathrm{rms}} = 200\ \mathrm{cm\ s^{-1}}$ and the cross section of $\sigma = 580\ \text{Å}^2$.



Figure 5 A photon echo signal from ruby. Time increases to the right with a scale of 100 ns/division. The pulse on the right is the echo signal, while the first two pulses are the (attenuated) input pulses. Reprinted with permission from Kurnit NA, Abella ID and Hartmann SR (1964) Observation of a photon echo. *Physical Review Letters* 13: 567. Copyright (1964) by the American Physical Society.



Figure 6 A photon echo signal in $^{13}CH_3F$ using the Stark switching method. The third pulse in trace (a) is the echo heterodyne beat signal. This signal is preceded by 'nutation' transient signals following each of the two Stark pulses shown in trace (b). Reprinted with permission from Brewer RG and Shoemaker RL (1971) Photo echo and optical nutation in molecules. *Physical Review Letters* 27: 631. Copyright (1971) by the American Physical Society.



Figure 7 Decay of the photon echo signal in $^{13}CH_3F$ as a function of pulse separation. Reprinted with permission from Schmidt J, Berman PR and Brewer RG (1973) Coherent transient study of velocity-changing collisions. *Physical Review Letters* 31: 1103. Copyright (1973) by the American Physical Society.



Figure 8 Pulse sequence and signal intensity for the stimulated photon echo.

Stimulated Photon Echo

In contrast to conventional photon echoes, *stimulated photon echoes* can be used to *simultaneously* measure both transverse and longitudinal relaxation times. Stimulated photon echoes have become an important diagnostic probe of relaxation in condensed matter systems as well as atomic vapors. The pulse sequence is shown in Figure 8 and consists of three pulses, having areas $\theta_1, \theta_2, \theta_3$, and equal propagation vectors $\mathbf{k}$. The time interval between the first two pulses is $T_{21} \gg T_2^*$ and pulse 3 occurs at time $t = T_{21} + T$. The maximum echo amplitude is given by

$$I(L, t_e) = \frac{1}{2}\left(\frac{k\mathcal{N}\mu L}{2\varepsilon_0}\sin\theta_1 \sin\theta_2 \sin\theta_3\right)^2 \times e^{-2\gamma_2 T} e^{-4\gamma T_{21}} \qquad [27]$$

and occurs when $t_e - (T_{21} + T) = T_{21}$. The optimal pulse sequence consists of three $\pi/2$ pulses.

If slightly different $\mathbf{k}$ vectors are chosen such that $\mathbf{k}_1 = \mathbf{k}_3 \approx \mathbf{k}_2$ the echo intensity varies as

$$e^{-2\gamma_2 T} e^{-4\gamma T_{21}} e^{-|\mathbf{k}_1 - \mathbf{k}_2|^2 u^2 (T + 2T_{21})^2/2}$$

By varying the angle between $\mathbf{k}_1$and $\mathbf{k}_2$, one can determine the Doppler width ku. By monitoring the echo signal as a function of $T_{21}(T)$, one obtains information on the transverse (longitudinal) relaxation.

The situation changes dramatically if there is an *additional* ground state level (level 0) to which the excited state can decay. In that case, the system is 'open' since population can leave the 'two-level' subsystem. The total population of the 1–2 state subsystem is no longer conserved, requiring an *additional* decay rate to account for relaxation. Let us suppose that all states decay with rate Γ_t as a result of their finite time in the laser beams. Moreover, let $\Gamma_{2,1}$ and $\Gamma_{2,0}$ be the decay rates of level 2 to levels 1 and 0, respectively. Assuming that $\gamma_2 T \gg 1$, one finds that the factor $e^{-2\gamma_2 T}$ in eqn [27] must be replaced by $(\Gamma_{2,0}/(\Gamma_{2,1} + \Gamma_{2,0}))^2 e^{-2\Gamma_t T}$. If $\Gamma_{2,0} \neq 0$, there is a long-lived component in the ground state population that contributes to the echo signal. One can exploit this feature of open systems to study spectral diffusion or velocity-changing collisions with very high sensitivity. Echoes can occur for time separations T much greater than the excited state lifetime. The creation of such long-lived stimulated photon echoes can be attributed to the fact that, in open systems, a portion of the velocity modulation created by the first two pulses in the ground state remains following spontaneous decay from the excited state.

The stimulated photon echo observed on the D_1 transition in sodium is shown in Figure 9. This is



Figure 9 Stimulated photon echo observed on the D_1 transition in sodium. Reprinted with permission from Mossberg T, Flusberg A, Kachru R and Hartmann SR (1979) Total scattering cross section for Na on He measured by stimulated photon echoes. *Physical Review Letters* 42: 1665. Copyright (1979) by the American Physical Society.

an 'open' system, owing to ground state hyperfine structure. For the data shown, T is 17 times the 16 ns lifetime of the excited state. The first three pulses represent light scattered from the three input pulses and the fourth pulse is the echo. The echo appears at $t = T + 2T_{21}$.

Optical Ramsey Fringes

We have seen that coherent transients can be used to measure relaxation rates. With a slight modification of the stimulated photon echo geometry, it is also possible to use coherent transient signals to measure transition frequencies. If one chooses $\mathbf{k}_3$ in the $-\mathbf{k}_1$ direction instead of the $\mathbf{k}_1$ direction, it is possible to generate a phase matched signal in the

$$\mathbf{k} = \mathbf{k}_1 - \mathbf{k}_2 + \mathbf{k}_3 = -\mathbf{k}_2$$

direction. To simplify matters, it is assumed that $\mathbf{k}_1 \approx \mathbf{k}_2 = -\mathbf{k}$ and terms of order $|\mathbf{k}_1 - \mathbf{k}_2| u \times (T + 2T_{21})$ are neglected.

The averaged density matrix element in the vicinity of the echo is

$$\langle \rho_{21}(t) \rangle = (i/8) \sin \theta_1 \sin \theta_2 \sin \theta_3 e^{-\gamma_2 T} e^{-2\gamma T_{21}} \times e^{i\delta[(t-T_{21}-T)+T_{21}]} e^{-k^2u^2|(t-T_{21}-T)-T_{21}|^2/4} \qquad [28]$$

An echo is formed at time $t_e = T + 2T_{21}$, just as for the stimulated photon echo, but there is an additional phase factor, given by $e^{2i\delta T_{21}}$ when $t = t_e$, that is absent for the nearly collinear geometry. This phase factor is the optical analog of the phase factor that is responsible for the generation of Ramsey fringes in the microwave domain. The phase factor can be measured directly by heterodyning the signal field with a reference field or, indirectly, by converting the off-diagonal density matrix element into a population by the addition of a *fourth* pulse in the $\mathbf{k}_3$ direction at time $t = T + 2T_{21}$. In either case, the signal varies as $\cos(2\delta T_{21})$. The central fringe, corresponding to $\delta = 0$ can be isolated using one of two methods. If the experiment is carried out using an atomic beam rather than atoms in a cell, $T_{21} = L/u_0$, will be different for atoms having different u_0 (L = spatial separation of the first two pulses and u_0 is the longitudinal velocity of the atoms). On averaging over a distribution of u_0, the fringe having $\delta = 0$ will have the maximum amplitude. Experiments of this type allow one to measure optical frequencies with accuracy of order T_{21}^{-1}. For experiments using temporally-separated pulses acting on atoms in a cell, it is necessary to take data as a function of δ for several values of T_{21}, and then average the data over T_{21}. It might seem remarkable that narrow pulses having large bandwidths can be used to measure optical frequencies with arbitrary accuracy as T_{21} is increased. Of course, it is the *total* duration of the pulse sequence rather than the duration of a single pulse that is the relevant time parameter. For the optical coherence, T_{21} is the appropriate time parameter (during the interval T, it is population rather than coherence that contributes to the signal). The price one pays by using large T_{21} is a signal that decays as $e^{-4\gamma T_{21}}$.

Figure 10 illustrates an optical Ramsey fringe signal on the 657 nm intercombination line in Ca. Four-field zones were used. The most probable value of T_{21} was about 10^{-5} s for an effusive beam having a most probable longitudinal speed equal to $800\ \mathrm{ms}^{-1}$, giving a central fringe width of order 60 kHz.



Figure 10 An optical Ramsey fringe signal on the 657 nm intercombination line in Ca. Four field zones were used. The solid and dotted lines represent runs with the directions of the laser field reversed, to investigate phase errors in the signals. Reprinted from Ito N, Ishikawa J and Moringa A (1994) Evaluation of the optical phase shift in a Ca Ramsey fringe stabilized optical frequency standard by means of laser-beam reversal. *Optics Communications* 109: 414, with permission from Elsevier.

Atom Interferometry

Matter wave atom interferometers rely on the wave nature of the center-of-mass motion for their operation. Such interferometers illustrate some interesting features of coherent optical transients not found in NMR. As an example, one can consider the response of a cold atomic ensemble to two, off-resonant standing-wave optical pulses separated in time by T. The electric field amplitude of pulse $j (j = 1, 2)$ is given by $\mathbf{E}_j(\mathbf{Z}, t) = \boldsymbol{\varepsilon} E_j(t)\cos(kZ)\cos(\omega t)$. The net effect of the field is to produce a spatially-modulated, ac Stark or light shift of the ground state energy. As a result, pulse j modifies the ground state amplitude by the phase factor $\exp[i\theta_j \cos(2kZ)]$. In other words, the standing wave field acts as a phase grating for the atoms. The phase factor can be interpreted in terms of momentum exchange between the two traveling wave components of the standing wave field. Owing to the fields' interaction with the atoms, all even integral multiples of $2\hbar k$ can be exchanged by the fields, imparting impulsive momenta of $2n\hbar k$ (n is a positive or negative integer) to the atoms. For an atom having momentum $\mathbf{P}$ and mass M, the frequency change associated with this momentum change is

$$E_{P,\mathbf{P}\pm 2n\hbar k\hat{Z}}/\hbar = \left(\frac{P^2}{2M} - \frac{|\mathbf{P} \pm 2n\hbar k\hat{Z}|^2}{2M}\right)\Big/\hbar$$
$$= \mp\frac{2nP_Z k}{M} - \omega_{2nk} \qquad [29]$$

where

$$\omega_\kappa = \frac{\hbar\kappa^2}{2M}$$

There are two contributions to the frequency eqn [29]. The first part is independent of $\hbar$ and represents a classical Doppler shift, while the second part is proportional to $\hbar$ and represents a quantum, matter-wave effect. The quantum contribution will become important for times of order ω_{2nk}^{-1}. As with the echoes described previously, the Doppler effect results in a dephasing and rephasing of the optical response. However, in contrast to the previous echoes, the ground state density is no longer constant for times $t > \omega_{2nk}^{-1}$, when matter wave effects begin to play a role. At such times the phase grating created by the pulses can be transformed into amplitude gratings of the atomic density.

Long interaction times are possible, limited only by the time the atoms spend in the field. As such, atom interferometers offer exciting new possibilities for precision measurements of rotation rates, fundamental constants such as $\hbar$, gravitational acceleration, and gravitational gradients. Moreover, one can take advantage of the nonlinear atom-field interaction to create atomic density patterns having period $\lambda/2n$ from a standing wave optical field having wavelength λ. In this manner one has the possibility to construct atom interferometers and atom structures that operate on the nano-scale (spacings on the order of tens of nanometers).

Conclusion

Optical coherent transients are now used routinely as probes of atomic vapors, liquids, and condensed matter. Sophisticated techniques have been developed using fast and ultrafast pulses (having duration of 10 to 100 femtoseconds) to probe such systems and obtain the relevant relaxation rates. The manner in which optical coherent transients can be used to extract information on transition frequencies and relaxation rates in atomic and molecular vapors has been reviewed. In atomic vapors, optical coherent transients provide a means for obtaining both longitudinal and transverse relaxation rates. Moreover, echo experiments serve as an extremely sensitive probe of velocity changing collisions. Similar techniques are being rediscovered as an important tool in the analysis of cold atomic vapors and Bose–Einstein condensates. Only the most basic optical coherent transient phenomena have been described in this chapter. More elaborate, multi-pulse excitation schemes are joining established methods in attempts to understand the complex decay dynamics that one encounters in many branches of physics, chemistry and biology.

Acknowledgments

The research of PRB is supported by the National Science Foundation under Grants No. PHY-0098016 and the FOCUS Center Grant, and by the U. S. Army Research Office under Grant No. DAAD19-00-1-0412.

List of Units and Nomenclature

$\mathbf{E}(\mathbf{R}, t)$	Electric field vector
$E(t)$	Electric field amplitude
$E_s(Z, t)$	Complex signal electric field amplitude
$I(L, t)$	Signal intensity exiting the sample
$\mathbf{k}$	Field propagation vector
L	Sample length
$\mathcal{N}$	Atomic density
$\mathbf{P}$	Center-of-mass momentum
$\mathbf{P}(\mathbf{R}, t)$	Polarization vector
$P(Z, t)$	Complex polarization field amplitude
T_{21}, T	Time interval between pulses
u	Most probable atomic speed

(u, v, w)	Elements of Bloch vector
$\mathbf{U}(t)$	Bloch vector
$\mathbf{v}$	Atomic velocity
$W_0(\mathbf{v})$	Atomic velocity distribution
γ	Transverse relaxation rate
γ_2	Excited state decay rate or longitudinal relaxation rate
δ	Atom-field detuning
θ	Pulse area
μ	Dipole moment matrix element
ρ_{ij}^{I}	Density matrix element in 'normal' interaction representation
$\rho_{ij}(Z, t)$	Density matrix element in a field interaction representation
τ	Pulse durations
ω	Field frequency
ω_k	Recoil frequency
ω_0	Atomic transition frequency
$\Omega(t)$	Generalized Rabi frequency
$\boldsymbol{\Omega}(t)$	Pseudofield vector
$\Omega_0(t)$	Rabi frequency

See also

Interferometry: Gravity Wave Detection; Overview.

Further Reading

Allen L and Eberly J (1975) *Optical Resonance and Two-Level Atoms*, Chapters 2,4,9, New York: Wiley.

Berman PR and Steel DG (2001) *Coherent optical transients*. In: Bass M, Enoch JM, Van Stryland E and Wolf WL (eds) Handbook of Optics, vol. IV. chap. 24 New York: McGraw-Hill. (Material presented in this chapter is a condensed version of this reference.).

Brewer RG (1977) Coherent optical spectroscopy. In: Balian R, Haroche S and Liberman S (eds) *Frontiers in Laser Spectroscopy, Les Houches, Session XXVII*, vol. 1, pp. 341–396. Amsterdam: North Holland.

Brewer RG (1977) Coherent optical spectroscopy. In: Bloembergen N (ed.) *Nonlinear Spectroscopy*, Proc. Int. School Phys., Enrico Fermi, Course 64, Amsterdam: North-Holland.

Brewer RG (1977) *Coherent optical transients*. In *Physics Today*, vol. 30(5), 50–59.

Brewer RG and Hahn EL (1984) Atomic memory. In *Scientific American*, vol. 251(6), 50–57.

Journal of Optical Society America (1986) Special issue on coherent optical spectroscopy, Vol. A3(4).

Levenson MD and Kano SS (1988) *Introduction to Nonlinear Laser Spectroscopy*, Chapter 6. Boston: Academic Press.

Meystre P and Sargent M III (1999) *Elements of Quantum Optics*, 3rd edn. Chapter 12. Berlin: Springer-Verlag.

Shen YR (1984) *The Principles of Nonlinear Optics*, Chapter 17. New York: Wiley.

Shoemaker RL (1978) Coherent transient infrared spectroscopy. In: Steinfeld JI (ed.) *Laser and Coherence Spectroscopy*, pp. 197–371. New York: Plenum.

Zinth W and Kaiser W (1988) *Ultrafast Coherent Spectroscopy*. In: Kaiser W (ed.) *Ultrashort Laser Pulses and Applications*, vol. 60, pp. 235–277. Berlin: Springer-Verlag.

Foundations of Coherent Transients in Semiconductors

T Meier and S W Koch, Philipps-University, Marburg, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Electromagnetic irradiation of matter generates a coherent superposition of the excited quantum states. The attribute 'coherent' relates to the fact that the material excitations originally have a well defined phase dependence which is imposed by the phase of the excitation source, often a laser in the optical regime. Macroscopically, the generated superposition state can be described as an optical polarization which is determined by the transition amplitudes between the participating quantum states.

The optical polarization is a typical non-equilibrium quantity that decays to zero when a system relaxes to its equilibrium state. Coherent effects are therefore only observable in a certain time window after pulsed photo-excitation, or in the presence of a continuous-wave (cw) beam. As coherent transients one usually refers to phenomena that can be observed during or shortly after pulsed laser excitation and critically depend on the presence of the induced optical polarization.

Many materials such as atoms, molecules, metals, insulators, semiconductors including bulk crystals, heterostructures, and surfaces, as well as organic and biological structures are studied using coherent optical spectroscopy. Depending on the particular system, the states participating in the optical transitions, the interactions among them, and the resulting time-scale for the decay of the induced polarization may be very different. As a result, the time window during which coherent effects are observable can be as long as seconds for certain atomic transitions, or it may be as short as a few femtoseconds (10^{-15}s), e.g., for metals, surfaces, or highly excited semiconductors.

Coherent spectroscopy and the analysis of coherent transients has provided valuable information on the nature and dynamics of the optical excitations. Often it is possible to learn about the interaction processes among the photoexcitations and to follow the temporal evolution of higher-order transitions which are only accessible if the system is in a non-equilibrium state.

The conceptually simplest experiment which one may use to observe coherent transients is to time resolve the transmission or reflection induced by a single laser pulse. However, much richer information can be obtained if one excites the system with several pulses. A pulse sequence with well-controlled delay times makes it possible to study the dynamical evolution of the photo-excitations, not only by time resolving the signal, but also by varying the delay. Prominent examples of such experiments are pump-probe measurements, which usually are performed with two incident pulses, or four-wave mixing, for which one may use two or three incident pulses.

Besides the microscopic interaction processes, the outcome of an experiment is determined by the quantum mechanical selection rules for the transitions and by the symmetries of the system under investigation. For example, if one wants to investigate coherent optical properties of surface states one often relies on phenomena, such as second-harmonic or sum-frequency generation, which give no signal in perfect systems with inversion symmetry. Due to the broken translational invariance, such experiments are therefore sensitive only to the dynamics of surface and/or interface excitations.

In this article the basic principles of coherent transients are presented and several examples are presented. The basic theoretical description and its generalization for the case of semiconductors are introduced.

Basic Principles

In the absence of free charges and currents, Maxwell's equations show that the electromagnetic field interacts with matter via the optical polarization. This polarization **P**, or more precisely its second derivative with respect to time $(\partial^2/\partial t^2)\mathbf{P}$, appears as a source term in the wave equation for the electric field **E**. Consequently, if the system is optically thin such that propagation effects within the sample can be ignored and if measurements are performed in the far field region, i.e., at distances exceeding the characteristic optical wavelength λ, the emitted electric field resulting from the polarization is proportional to its second time derivative, $\mathbf{E} \propto (\partial^2/\partial t^2)\mathbf{P}$. Thus the measurement of the emitted field dynamics yields information about the temporal evolution of the optical material polarization.

Microscopically the polarization is determined by the transition amplitudes between the different states of the system. These may be the discrete states of atoms or molecules, or the microscopic valence and conduction band states in a dielectric medium, such as a semiconductor. In any case, the macroscopic polarization **P** is computed by summing over all microscopic transitions p_{cv} via $\mathbf{P} = \sum_{c,v} (\boldsymbol{\mu}_{cv} p_{cv} + c.c.)$, where $\boldsymbol{\mu}_{cv}$ is the dipole matrix element which determines the strength of the transitions between the states v and c, and $c.c.$ denotes the complex conjugate. If ε_c and ε_v are the energies of these states, their dynamic quantum mechanical evolution is described by the phase factors $e^{-i\varepsilon_c t/\hbar}$ and $e^{-i\varepsilon_v t/\hbar}$, respectively. Therefore, each p_{cv} is evolving in time according to $e^{-i(\varepsilon_c - \varepsilon_v)t/\hbar}$. Assuming that we start at $t = 0$ with $p_{cv}(t = 0) = p_{cv,0}$, which may be induced by a short optical pulse, we have for the optical polarization $\mathbf{P}(t) = \sum_{c,v} (\boldsymbol{\mu}_{cv} p_{cv,0} e^{-i(\varepsilon_c - \varepsilon_v)t/\hbar} + c.c.)$. Thus $\mathbf{P}(t)$ is given by a summation over microscopic transitions which all oscillate with frequencies proportional to the energy differences between the involved states. Hence, the optical polarization is clearly a coherent quantity which is characterized by amplitude and phase. Furthermore, the microscopic contributions to $\mathbf{P}(t)$ add up coherently. Depending on the phase relationships, one may obtain either constructive superposition, interference phenomena like quantum beats, or destructive interference leading to a decay (dephasing) of the macroscopic polarization.

Optical Bloch Equations

The dynamics of photo-excited systems can be conveniently described by a set of equations, the optical Bloch equations, named after Felix Bloch (1905–1983) who first formulated such equations to analyze the spin dynamics in nuclear magnetic resonance. For the simple case of a two-level model, the Bloch equations can be written as

$$i\hbar \frac{\partial}{\partial t} p = \Delta\varepsilon p + \mathbf{E}\cdot\boldsymbol{\mu} I \qquad [1]$$

$$i\hbar \frac{\partial}{\partial t} I = 2\mathbf{E}\cdot\boldsymbol{\mu}(p - p^*) \qquad [2]$$

Here, $\Delta\varepsilon$ is the energy difference and I the inversion, i.e., the occupation difference between upper and lower state. The field **E** couples the polarization to the product of the Rabi energy $\mathbf{E}\cdot\boldsymbol{\mu}$

and the inversion I. In the absence of the driving field, i.e., $\mathbf{E} \equiv 0$, eqn [1] describes the free oscillation of p discussed above.

The inversion is determined by the combined action of the Rabi energy and the transition p. The total occupation N, i.e., the sum of the occupations of the lower and the upper states, remains unchanged during the optical excitation since light does not create or destroy electrons; it only transfers them between different states. If N is initially normalized to 1, then I can vary between -1 and 1. $I = -1$ corresponds to the ground state of the system, where only the lower state is occupied. In the opposite extreme, i.e., for $I = 1$, the occupation of the upper state is 1 and the lower state is completely depleted.

One can show that eqns [1]–[2] contain another conservation law. Introducing $\mathcal{P} = p + p^* = 2Re[p]$ and $\mathcal{J} = i(p - p^*) = -2Im[p]$, which are real quantities and often named polarization and polarization current, respectively, one finds that the relation

$$\mathcal{P}^2 + \mathcal{J}^2 + I^2 = 1 \qquad [3]$$

is fulfilled. Thus the coupled coherent dynamics of the transition and the inversion can be described on a unit sphere, the so-called Bloch sphere. The three terms $\mathcal{P}, \mathcal{J}$, and I can be used to define a three-dimensional Bloch vector $\mathbf{S} = (\mathcal{P}, \mathcal{J}, I)$. With these definitions, one can reformulate eqns [1]–[2] as

$$\frac{\partial}{\partial t}\mathbf{S} = \mathbf{\Omega} \times \mathbf{S} \qquad [4]$$

with $\mathbf{\Omega} = (-2\boldsymbol{\mu}\cdot\mathbf{E}, 0, \Delta\varepsilon)/\hbar$ and × denoting the vector product.

The structure of eqn [4] is mathematically identical to the equations describing either the angular momentum dynamics in the presence of a torque or the spin dynamics in a magnetic field. Therefore, the vector $\mathbf{S}$ is often called pseudospin. Moreover, many effects which can be observed in magnetic resonance experiments, e.g., free decay, quantum beats, echoes, etc. have their counterparts in photo-excited optical systems.

The vector product on the right-hand side of eqn [4] shows that $\mathbf{S}$ is changed by $\mathbf{\Omega}$ in a direction perpendicular to $\mathbf{S}$ and $\mathbf{\Omega}$. For vanishing field the torque $\mathbf{\Omega}$ has only a z-component. In this case the z-component of $\mathbf{S}$, i.e., the inversion, remains constant, whereas the x- and y-components, i.e., the polarization and the polarization current, oscillate with the frequency $\Delta\varepsilon/\hbar$ on the Bloch sphere around $\mathbf{\Omega}$.

Semiconductor Bloch Equations

If one wants to analyze optical excitations in crystallized solids, i.e., in systems which are characterized by a periodic arrangement of atoms, one has to include the continuous dispersion (bandstructure) into the description. In translationally invariant, i.e., ordered systems, this can be done by including the crystal momentum $\hbar\mathbf{k}$ as an index to the quantities which describe the optical excitation of the material, e.g., p and I in eqns [1]–[2]. Hence, one has to consider a separate two-level system for each crystal momentum $\hbar\mathbf{k}$. As long as all other interactions are disregarded, the bandstructure simply introduces a summation over the uncoupled contributions from the different $\mathbf{k}$ states, leading to inhomogeneous broadening due to the presence of a range of transition frequencies $\Delta\varepsilon(\mathbf{k})/\hbar$.

For any realistic description of optical processes in solids, it is essential to go beyond the simple picture of non-interacting states and to treat the interactions among the elementary material excitations, e.g., the Coulomb interaction between the electrons and the coupling to additional degrees of freedom, such as lattice vibrations (electron–phonon interaction) or other bath-like subsystems. If crystals are not ideally periodic, imperfections, which can often be described as a disorder potential, need to be considered as well.

All these effects can be treated by proper extensions of the optical Bloch equations introduced above. For semiconductors the resulting generalized equations are known as semiconductor Bloch equations, where the microscopic interactions are included at a certain level of approximation. For a two-band model of a semiconductor, these equations can be written schematically as

$$i\hbar\frac{\partial}{\partial t}p_{\mathbf{k}} = \Delta\varepsilon_{\mathbf{k}}p_{\mathbf{k}} + \Omega_{\mathbf{k}}(n^c_{\mathbf{k}} - n^v_{\mathbf{k}}) + i\hbar\frac{\partial}{\partial t}p_{\mathbf{k}}|_{\mathrm{corr}} \qquad [5]$$

$$i\hbar\frac{\partial}{\partial t}n^c_{\mathbf{k}} = (\Omega^*_{\mathbf{k}}p_{\mathbf{k}} - \Omega_{\mathbf{k}}p^*_{\mathbf{k}}) + i\hbar\frac{\partial}{\partial t}n^c_{\mathbf{k}}|_{\mathrm{corr}} \qquad [6]$$

$$i\hbar\frac{\partial}{\partial t}n^v_{\mathbf{k}} = -(\Omega^*_{\mathbf{k}}p_{\mathbf{k}} - \Omega_{\mathbf{k}}p^*_{\mathbf{k}}) + i\hbar\frac{\partial}{\partial t}n^v_{\mathbf{k}}|_{\mathrm{corr}} \qquad [7]$$

Here $p_{\mathbf{k}}$ is the microscopic polarization and $n^c_{\mathbf{k}}$ and $n^v_{\mathbf{k}}$ are the electron populations in the conduction and valence bands (c and v), respectively. Due to the Coulomb interaction and possibly further processes, the transition energy $\Delta\varepsilon_{\mathbf{k}}$ and the Rabi energy $\Omega_{\mathbf{k}}$ both depend on the excitation state of the system, i.e., they are functions of the time-dependent polarizations and populations. This leads, in particular, to a coupling among the excitations for all different values of the crystals momentum $\hbar\mathbf{k}$. Consequently, in the presence of interactions, the optical excitations can no longer be described as independent two-level systems but have to be treated as a coupled many-body system. A prominent and important example in this context is the appearance of strong exciton resonances which, as a consequence of the Coulomb interaction, show up in the absorption spectra of semiconductors energetically below the fundamental bandgap.

The interaction effects lead to significant mathematical complications since they induce couplings between all the different quantum states in a system and introduce an infinite hierarchy of equations for the microscopic correlation functions. The terms given explicitly in eqns [5]–[7] arise in a treatment of the Coulomb interaction on the Hartree-Fock level. Whereas this level is sufficient to describe excitonic resonances, there are many additional effects, e.g., excitation-induced dephasing due to Coulomb scattering and significant contributions from higher-order correlations, like excitonic populations and biexcitonic resonances, which make it necessary to treat many-body correlation effects that are beyond the Hartree-Fock level. These contributions are formally included by the terms denoted as $|_{\mathrm{corr}}$ in eqns [5]–[7]. The systematic truncation of the many-body hierarchy and the analysis of controlled approximations is the basic problem in the microscopic theory of optical processes in condensed matter systems.

Examples

Radiative Decay

The emitted field originating from the non-equilibrium coherent polarization of a photo-excited system can be monitored by measuring the transmission and the reflection as function of time. If only a single isolated transition is excited, the dynamic evolution of the polarization and therefore of the transmission and reflection is governed by radiative decay. This decay is a consequence of the coupling of the optical transition to the light field described by the combination of Maxwell- and Bloch-equations. Radiative decay simply means that the optical polarization is converted into a light field on a characteristic time scale $2T_{\mathrm{rad}}$. Here, T_{rad} is the population decay time, often also denoted as T_1-time. This radiative decay is a fundamental process which limits the time on which coherent effects are observable for any photo-excited system. Due to other mechanisms, however, the non-equilibrium polarization often vanishes considerably faster.

The value of T_{rad} is determined by the dipole matrix element and the frequency of the transition, i.e., $T_{\mathrm{rad}}^{-1} \propto |\boldsymbol{\mu}|^2 \Delta\omega$, with $\Delta\omega = \Delta\varepsilon/\hbar$. The temporal evolution of the polarization and the emitted field are proportional to $e^{-i\Delta\omega t - t/(2T_{\mathrm{rad}})}$. Usually one measures the intensity of a field, i.e., its squared modulus, which evolves as $e^{-t/T_{\mathrm{rad}}}$ and thus simply shows an exponential decay, the so-called *free-induction decay* (see Figure 1). T_{rad} can be very long for transitions with small matrix elements. For semiconductor quantum wells, however, it is in the order of only 10 ps, as the result of the strong light-matter interaction.

The time constant on which the optical polarization decays is often called T_2. In the case where this decay is dominated by radiative processes, we thus have $T_2 = 2T_{\mathrm{rad}}$.

Superradiance

The phenomenon of superradiance can be discussed considering an ensemble of N two-level systems which are localized at certain positions $\mathbf{R}_i$. In this case



Figure 1 A two-level system is excited by a short optical pulse at $t = 0$. Due to radiative decay (inset) and possibly other dephasing mechanisms, the polarization decays exponentially as function of time with the time constant T_2, the dephasing time. The intensity of the optical field which is emitted as a result of this decay is proportional to the squared modulus of the polarization, which falls off with the time constant $T_2/2$. The decay of the squared modulus of the polarization is shown in (a) on a linear scale and in (b) on a logarithmic scale. The dephasing time was chosen to be $T_2 = 10$ ps which models the radiative decay of the exciton transition of a semiconductor quantum well.

Maxwell's equations introduce a coupling among all these resonances since the field emitted from any specific resonance interacts with all other resonances and interferes with their emitted fields. As a result, this system is characterized by N eigenmodes originating from the radiatively coupled optical resonances.

A very spectacular situation arises if one considers N identical two-level systems regularly arranged with a spacing that equals an integer multiple of $\lambda/2$, where λ is the wavelength of the system's resonance, i.e., $\lambda = c/\Delta\omega$, where c is the speed of light in the considered material (see Figure 2a). In this case all emitted fields interfere constructively and the system behaves effectively like a single two-level system with a matrix element increased by $\sqrt{N}$. Consequently, the radiative decay rate is increased by N and the polarization of the coupled system decays N-times faster than that of an isolated system (see Figure 2b). This effect is called superradiance.

It is possible to observe superradiant coupling effects, e.g., in suitably designed semiconductor heterostructures. Figure 2c compares the measured time-resolved reflection from a single quantum well (dashed line) with that of a Bragg structure, i.e., a multiple quantum-well structure which consists of 10 individual wells that are separated by $\lambda/2$ (solid line), where λ is the wavelength of the exciton resonance. For times greater than about 2 ps the direct reflection of the exciting pulse has decayed sufficiently and one is left with the exponential decay of the remaining signal. Figure 2c shows that this decay is much more rapid for the Bragg structure than for the single quantum well, due to superradiance introduced by the radiative coupling among the quantum wells.

Destructive Interference

As the next example we now consider a distribution of two-level systems which have slightly different transition frequencies characterized by the distribution function $g(\Delta\omega - \bar{\omega})$ of the transition frequencies which is peaked at the mean value $\bar{\omega}$ and has a spectral width of $\delta\omega$ (see Figure 3a). Ignoring the radiative coupling among the resonances, the optical polarization of the total system evolves after excitation with a short laser pulse at $t = 0$ proportional to $\int d\omega\, g(\Delta\omega - \bar{\omega})e^{-i\Delta\omega t} \propto \tilde{g}(t)e^{-i\bar{\omega}t}$, where $\tilde{g}(t)$ denotes the Fourier transform of the frequency distribution function. $\tilde{g}(t)$ and thus the optical polarization decays on a time-scale which is inversely proportional to the spectral width of the distribution function $\delta\omega$. Thus the destructive interference of many different transition frequencies results in a rapid decay of the polarization (see Figure 3b).



Figure 2 (a) N identical two-level systems are depicted which are regularly arranged with a spacing that equals an integer multiple of $\lambda/2$, where λ is the wavelength of the system's resonance. Due to their coupling via Maxwell's equations all fields emitted from the two-level systems interfere constructively and the coupled system behaves effectively like a single two-level system with an optical matrix element increased by $\sqrt{N}$. (b) The temporal decay of the squared modulus of the polarization is shown on a logarithmic scale. The radiative decay rate is proportional to N and thus the polarization of the coupled system decays N-times faster than that of an isolated system. This effect is called superradiance. (c) Measured time-resolved reflection of a semiconductor single quantum well (dashed line) and a $N = 10$ Bragg structure, i.e., a multi quantum well where the individual wells are separated by $\lambda/2$ (solid line), on a logarithmic scale. [Part (c) is reproduced with permission from Haas S, Stroucken T, Hübner M, *et al.* (1998) Intensity dependence of superradiant emission from radiatively coupled excitons in multiple-quantum-well Bragg structures. *Physical Review B* 57: 14860. Copyright (1998) by the American Physical Society].



Figure 3 (a) An ensemble of two-level systems is shown where the resonance frequencies are randomly distributed according to a Gaussian distribution function of width $\delta\omega$ around an average value. (b) The temporal dynamics of the squared modulus of the polarization of ensembles of two-level systems after excitation with a short optical pulse at $t = 0$ is shown on a linear scale. Since the dephasing time is set to infinity, i.e., $T_2 \to \infty$, the polarization of an ensemble of identical two-level system ($\delta\omega = 0$) does not decay. However, for a finite width of the distribution, $\delta\omega > 0$, the individual polarizations of the ensemble oscillate with different frequencies and, therefore, due to destructive interference the polarization of the ensemble decays as function of time. Since the Fourier transform of a frequency-domain Gaussian is a Gaussian in the time domain, the dashed, dotted, and dashed dotted line have a Gaussian shape with a temporal width which is inversely proportional to $\delta\omega$.

In the spectral domain this rapid decay shows up as inhomogeneous broadening. Depending on the system under investigation, there are many different sources for such an inhomogeneous broadening. One example is the Doppler broadening in atomic gases or disorder effects such as well-width fluctuations in semiconductor quantum wells or lattice imperfections in crystals.

In the nonlinear optical regime it is, under certain circumstances, possible to reverse the destructive interference of inhomogeneously broadened coherent polarizations. For example, in four-wave mixing, a second pulse may lead to a rephasing of the contributions with different frequencies, which results in the photon echo (see discussion below).

Quantum Beats



Figure 4 (a) Two optical resonances with frequency difference $\Delta\omega_1 - \Delta\omega_2$ may be realized by either a three-level system or by two uncoupled two-level systems. After impulsive excitation with an optical pulse the linear polarization of both types of systems show a modulation of the squared modulus of the polarization with the time period $2\pi/(\Delta\omega_1 - \Delta\omega_2)$. For the intrinsically coupled three-level system these modulations are called quantum beats, whereas for an interference of uncoupled systems they are named polarization interferences. Using nonlinear optical techniques, e.g., four-wave mixing and pump probe, it is possible to distinguish quantum beats and polarization interferences since coupled and uncoupled systems have different optical nonlinearities. (b) The temporal dynamics of the squared modulus of the polarization is shown for systems with two resonances and frequency difference $\Delta\omega_1 - \Delta\omega_2$, neglecting dephasing, i.e., setting $T_2 \to \infty$. After excitation with a short optical pulse at $t = 0$ the squared modulus of the polarization is periodically modulated with a time period $2\pi/(\Delta\omega_1 - \Delta\omega_2)$.

The occurrence of quantum beats can be understood most easily in a system where the total optical polarization can be attributed to a finite number of optical transitions. Let us assume for simplicity that all these transitions have the same matrix element. In this case, after excitation with a short laser pulse at $t = 0$ the optical polarization of the total system evolves proportional to $\sum_i e^{-i\Delta\omega_i t}$. The finite number of frequencies results in a temporal modulation with time periods $2\pi/(\Delta\omega_i - \Delta\omega_j)$ of the squared modulus of the polarization which is proportional to the emitted field intensity. For the case of two frequencies the squared modulus of the polarization is proportional to $[1 + \cos((\Delta\omega_1 - \Delta\omega_2)t)]$, i.e., due to the interference of two contributions the polarization varies between a maximum and zero (see Figure 4b).

In the linear optical regime it is impossible to distinguish whether the optical transitions are uncoupled or coupled. As shown in Figure 4, the two uncoupled two-level systems give the same linear polarization as a three-level systems where the two transitions share a common state. It is, however, possible to decide about the nature of the underlying transitions if one performs nonlinear optical spectroscopy. This is due to the fact that the so-called quantum beats, i.e., the temporal modulations of the polarization of an intrinsically coupled system, show a different temporal evolution as the so-called polarization interferences, i.e., the temporal modulations of the polarization of uncoupled systems. The former ones are also much more stable in the presence of inhomogeneous broadening than the latter ones.



Figure 5 (a) Two Gaussian laser pulses separated by the time delay τ can lead to interferences. As shown by the thick solid line in the inset, the spectral intensity of a single pulse is a Gaussian with a maximum at the central frequency of the pulse. The width of this Gaussian is inversely proportional to the duration of the pulse. The spectral intensity of the field consisting of both pulses shows interference fringes, i.e., is modulated with a spectral period that is inversely proportional to τ. As shown by the thin solid and the dotted lines in the inset, the phase of the interference fringes depends on the phase difference $\Delta\varphi$ between the two pulses. Whereas for $\Delta\varphi = 0$ the spectral intensity has a maximum at the central frequency, it vanishes at this position for $\Delta\varphi = \pi$. (b) The temporal dynamics of the squared modulus of the polarization is shown for a two-level system excited by a pair of short laser pulses neglecting dephasing, i.e., setting $T_2 \to \infty$. The first pulse excites at $t = 0$ an optical polarization with a squared modulus normalized to 1. The second pulse, which has the same intensity as the first one, also excites an optical polarization at $t = 2$ ps. For $t > 2$ ps the total polarization is given by the sum of the polarizations induced by the two pulses. Due to interference, the squared modulus of the total polarization depends sensitively on the phase difference $\Delta\varphi$ between the two pulses. For constructive interference the squared modulus of the total polarization after the second pulse is four times bigger than that after the first pulse, whereas it vanishes for destructive interference. One may achieve all values in between these extremes by using phase differences $\Delta\varphi$ which are no multiples of π. It is thus shown that the second pulse can be used to coherently control the polarization induced by the first pulse.

In semiconductor heterostructures, quantum-beat spectroscopy has been widely used to investigate the temporal dynamics of excitonic resonances. Also the coupling among different optical resonances has been explored in pump-probe and four-wave-mixing measurements.

Coherent Control

In the coherent regime the polarization induced by a first laser pulse can be modified by a second, delayed pulse. For example, the first short laser pulse incident at $t = 0$ induces a polarization proportional to $e^{-i\Delta\omega t}$ and a second pulse arriving at $t = \tau > 0$ induces a polarization proportional to $e^{-i\varphi}e^{-i\Delta\omega(t-\tau)}$. Thus for $t \geq \tau$ the total polarization is given by $e^{-i\Delta\omega t}(1 + e^{-i\Delta\varphi})$ with $\Delta\varphi = \varphi - \Delta\omega\tau$. If $\Delta\varphi$ is an integer multiple of 2π, the polarizations of both pulses interfere constructively and the amplitude of the resulting polarization is doubled as compared to a single pulse. If, on the other hand, $\Delta\varphi$ is an odd multiple of π, the polarizations of both pulses interfere destructively and the resulting polarization vanishes after the action of both pulses. Thus by



Figure 6 Transient optical nonlinearities can be investigated by exciting the system with two time delayed optical pulses. The pump pulse (E_p) puts the system in an excited state and the test (probe) pulse (E_t) is used to measure its dynamics. The dynamic nonlinear optical response may be measured in the transmitted or reflected directions of the pump and test pulses, i.e., $\pm k_p$ and $\pm k_t$, respectively. In a pump-probe experiment one often investigates the change of the test absorption induced by the pump pulse, by measuring the absorption in the direction k_t with and without E_p. One may also measure the dynamic nonlinear optical response in scattering directions like $2k_p - k_t$ and $2k_t - k_p$ as indicated by the dashed lines. This is what is done in a four-wave-mixing or photon-echo experiment.

varying the phase difference of the two pulses it is possible to coherently enhance or destroy the optical polarization (see Figure 5b).

One can easily understand the coherent control in the frequency domain by considering the overlap between the absorption of the system and the pulse spectrum. For excitation with two pulses that are temporally delayed by τ, the spectrum of the excitation shows interference fringes with a spectral oscillation period that is inversely proportional to τ. The positions of the maxima and the minima of the fringes depend on the phase difference between the two pulses. For constructive interference, the excitation spectrum is at a maximum at the resonance of the system, whereas for destructive interference the excitation spectrum vanishes at the resonance of the system (see Figure 5a).

Coherent control techniques have been applied to molecules and solids to control the dynamical evolution of electronic wavepackets and also the coupling to nuclear degrees of freedom. In this context, it is sometimes possible to steer certain chemical reactions into a preferred direction by using sequences of laser pulses which can be chirped, i.e., have a time-dependent frequency. Furthermore, in semiconductors and heterostructures, coherent control has been used to optically inject electronic currents on an ultrafast time-scale.

Transient Absorption Changes

In a typical pump-probe experiment one excites the system with a pump pulse (E_p) and probes its dynamics with a weak test pulse (E_t) (see Figure 6). With such experiments one often measures the differential absorption $\Delta\alpha(\omega)$ which is defined as



Figure 7 (a) Absorption spectra of a two-level system. The solid line shows the linear optical absorption spectrum as measured by a weak test pulse. It corresponds to a Lorentzian line that is centered at the transition frequency $\Delta\omega$, which has been set to zero. The width of the line is inversely proportional to the dephasing time T_2. In the presence of a pump pulse which resonantly excited the two-level system, the absorption monitored by the test pulse is reduced in amplitude, i.e., bleached, since the pump puts the system in an excited state (dashed line). In the optical Stark effect the frequency of the pump is nonresonant with the transition frequency. If the pump is tuned below (above) the transition frequency, the absorption is shifted to higher (lower) frequencies, i.e., shifted to the blue (red) part of the spectrum, see dotted (dashed-dotted) line. (b) The differential absorption obtained by taking the difference between the absorption in the presence of the pump and the absorption without pump. The dashed line shows the purely negative bleaching obtained using a resonant pump. The dotted and the dashed-dotted lines correspond to the dispersive shape of the blue and red shift obtained when pumping below and above the resonance, respectively. (c) Measured differential absorption spectra of a semiconductor quantum well which is pumped off resonantly 4.5 *meV* below the 1s heavy-hole exciton resonance. The four lines correspond to different polarization directions of the pump and probe pulses as indicated. [Part (c) is reproduced with permission from Sieh C, Meier T, Jahnke F, *et al.* (1999) Coulomb memory signatures in the excitonic optical Stark effect. *Physical Review Letters* 82: 3112. Copyright (1999) by the American Physical Society.]

the difference between the probe absorption in the presence of the pump $\alpha_{\text{pump on}}(\omega)$ and the probe absorption without the pump $\alpha_{\text{pump off}}(\omega)$.

For resonant pumping and for a situation where the pump precedes the test (positive time delays $\tau > 0$), the absorption change is usually negative in the vicinity of the resonance frequency $\Delta\omega$, indicating the effect of absorption bleaching (see Figure 7a,b). There may be positive contributions spectrally around the original absorption line due to resonance broadening and, at other spectral positions, due to excited state absorption, i.e., optical transitions to energetically higher states which are only possible if the system is in an excited state. The bleaching and the positive contributions are generally present in coherent, and also in incoherent situations, where the polarization vanishes but occupations in excited states are present.

For detuned pumping, the resonance may be shifted by the light field as for example, in the optical Stark effect. Depending on the excitation configuration and the system, this transient shift may be to higher (blue shift) or lower energies (red shift) (see Figure 7a,b). With increasing pump-probe time delay the system gradually returns to its unexcited state and the absorption changes disappear.

As an illustration we show in Figure 7c experimentally measured differential absorption spectra of a semiconductor quantum well which is pumped spectrally below the exciton resonance. For a two-level system one would expect a blue shift of the absorption, i.e., a dispersive shape of the differential absorption with positive contributions above and negative contributions below the resonance frequency. This is indeed observed for most polarization directions of the pump and probe pulses. However, if both pulses are oppositely circularly polarized, the experiment shows a resonance shift in the reverse direction, i.e., a red shift. For the explanation of this behavior one has to consider the optical selection rules of the quantum well system. One finds that the signal should actually vanish for oppositely circularly



Figure 8 (a) Differential absorption spectra are shown for resonant pumping of a two-level system for various time delays τ between the pump and the test pulse. When the pump precedes the test, i.e., $\tau < 0$, the differential absorption exhibits spectral oscillations with a period which is inversely proportional to the time delay. When τ approaches zero, these spectral oscillations vanish and the differential absorption develops into purely negative bleaching. (b) Measured differential transmission spectra of a multi quantum well for different negative time delays as indicated. [Part (b) is reproduced with permission from Sokoloff JK, Joffre M, Fluegel B, *et al.* (1988) Transient oscillations in the vicinity of excitons and in the band of semiconductors. *Physics Review B* 38: 7615. Copyright (1988) by the American Physical Society.]



Figure 9 (a) The intensity dynamics as measured in a four-wave-mixing experiment on an ensemble of inhomogeneously broadened two-level systems for various time delays τ of the two incident pulses. The first pulse excites the system at $t = 0$. In the time period $0 < t < \tau$ the individual polarizations of the inhomogeneously broadened system oscillate with their respective frequencies and due to destructive interference the total polarization decays, cp. **Figure 3**. The second pulse arriving at $t = \tau$ leads to a partial rephasing of the individual polarizations. Due to phase conjugation all individual polarizations are in phase at $t = 2\tau$ which results in a macroscopic measurable signal, the photon echo. Due to dephasing processes the magnitude of the photon echo decays with increasing τ, see solid, dashed, dotted and dashed-dotted lines. Describing the dephasing via a T_2 time corresponds to an exponential decay as indicated by the thin dotted line. By measuring the decay of the echo with increasing τ, one thus gets experimental information on the dephasing of the optical polarization. (b) Time-resolved four-wave-mixing signal measured on an inhomogeneously broadened exciton resonance of a semiconductor quantum well structure for different time delays as indicated. The origin of the time axis starts at the arrival of the second pulse, i.e., for a non-interacting system the maximum of the echo is expected at $t = \tau$. The insets show the corresponding time-integrated four-wave-mixing signal and the linear absorption. [Part (b) is reproduced with permission from Jahnke F, Koch M, Meier T, *et al.* (1994) Simultaneous influence of disorder and Coulomb interaction on photon echoes in semiconductors. *Physics Review B* 50: 8114. Copyright (1994) by the American Physical Society.]

polarized pulses, as long as many-body correlations are neglected. Thus in this case the entire signal is due to many-body correlations and it is their dynamics which gives rise to the appearance of the red shift.

Spectral Oscillations

For negative time delays $\tau < 0$, i.e., if the test pulse precedes the pump, the absorption change $\Delta\alpha(\omega)$ is characterized by spectral oscillations around $\Delta\omega$ which vanish as τ approaches zero (see Figure 8a). The spectral period of the oscillations decreases with increasing $|\tau|$. Figure 8b shows measured differential transmission spectra of a multiple quantum-well structure for different negative time delays. As with the differential absorption, also the differential transmission spectra are dominated by spectral oscillations around the exciton resonance whose period and amplitude decrease with increasing $|\tau|$.

The physical origin of the coherent oscillations is the pump-induced perturbation of the free-induction decay of the polarization generated by the probe pulse. This perturbation is delayed by the time τ at which the pump arrives. The temporal shift of the induced polarization changes in the time domain leads to oscillations in the spectral domain, since the Fourier transformation translates a delay in one domain into a phase factor in the conjugate domain.

Photon Echo

In the nonlinear optical regime one may (partially) reverse the destructive interference of a coherent, inhomogeneously broadened polarization. For example, in four-wave mixing, which is often performed with two incident pulses, one measures the emitted field in a background-free scattering direction (see Figure 5). The first short laser pulse excites all transitions at $t = 0$. As a result of the inhomogeneous broadening the polarization decays due to destructive interference (see Figure 3). The second pulse arriving at $t = \tau > 0$ is able to conjugate the phases ($e^{i\varphi} \rightarrow e^{-i\varphi}$) of the individual polarizations of the inhomogeneously broadened system. The subsequent unperturbed dynamical evolution of the polarizations leads to a measurable macroscopic signal at $t = 2\tau$. This photon echo occurs since at this point in time all individual polarizations are in phase and add up constructively (see Figure 9a). Since this rephasing process leading to the echo is only possible as long as the individual polarizations remain coherent, one can analyze the loss of coherence (dephasing) by measuring the decay of the photon echo with increasing time delay.

Echo experiments are frequently performed using more complicated geometries, e.g., more than two laser pulses. Further echo phenomena can also be observed as the result of the coupling of the photoexcitation to nuclear degrees of freedom and also due to spatial motion of the electrons, i.e., electronic currents.

Time-resolved four-wave-mixing signal, measured on an inhomogeneously broadened exciton resonance of a semiconductor quantum well structure for different time delays, is presented in Figure 9b. Compared to Figure 9a, the origin of the time axis starts at the arrival of the second pulse, i.e., for a non-interacting system the maximum of the echo is expected at $t = \tau$. Due to the inhomogeneous broadening the maximum of the signal is shifting to longer times with increasing delay. Further details of the experimental results, in particular, the exact position of the maximum and the width of the signal, cannot be explained on the basis of non-interacting two-level systems, but require the analysis of many-body effects in the presence of inhomogeneous broadening.

See also

Coherent Control: Applications in Semiconductors; Experimental; Theory. **Spectroscopy:** Nonlinear Laser Spectroscopy.

Further Reading

Allen L and Eberly JH (1975) *Optical Resonance and Two-Level Atoms*. New York: Wiley.

Baumert T, Helbing J, Gerber G, *et al.* (1997) Coherent control with femtosecond laser pulses. *Advanced Chemical Physics* 101: 47–82.

Bergmann K, Theuer H and Shore BW (1998) Coherent population transfer among quantum states of atoms and molecules. *Review of Modern Physics* 70: 1003–1025.

Bloembergen N (1965) *Nonlinear Optics*. New York: Benjamin.

Brewer RG (1977) *Coherent Optical Spectroscopy*. In: Balian, *et al.* (ed.). Course 4 in Les Houches Session XXVII, *Frontiers in Laser Spectroscopy*, vol. 1. Amsterdam: North-Holland Publ.

Cohen-Tannoudji C, Dupont-Roc J and Grynberg G (1989) *Photons and Atoms*. New York: Wiley.

Haug H and Koch SW (2004) *Quantum Theory of the Optical and Electronic Properties of Semiconductors*, 4th edn. Singapore: World Scientific.

Koch SW, Peyghambarian N and Lindberg M (1988) Transient and steady-state optical nonlinearities in semiconductors. *Journal of Physics* C 21: 5229–5250.

Macomber JD (1976) *The Dynamics of Spectroscopic Transitions*. New York: Wiley.

Mukamel S (1995) *Principles of Nonlinear Optical Spectroscopy*. New York: Oxford.

Peyghambarian N, Koch SW and Mysyrowicz A (1993) *Introduction to Semiconductor Optics*. Englewood Cliffs, NJ: Prentice-Hall.

Pötz W and Schroeder WA (eds) (1999) *Coherent Control in Atoms, Molecules, and Semiconductors*. Dordrecht: Kluwer.

Schäfer W and Wegener M (2002) *Semiconductor Optics and Transport Phenomena*. Berlin: Springer.

Shah J (1999) *Ultrafast Spectroscopy of Semiconductors and Semiconductor Nanostructures*, 2nd edn. Berlin: Springer.

Yeazell JA and Uzer T (eds) (2000) *The Physics and Chemistry of Wave Packets*. New York: Wiley.

Ultrafast Studies of Semiconductors

J Shah, Arlington, VA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Linear optical spectroscopy, using the techniques of absorption, transmission, reflection and light scattering, has provided invaluable information about the electronic and vibrational properties of atoms, molecules, and solids. Optical techniques also possess some additional unique strengths: the ability to

1. generate nonequilibrium distributions functions of electrons, holes, excitons, phonons, etc. in solids;
2. determine the distribution functions by optical spectroscopy;
3. determine the nonequilibrium distribution functions on femtosecond timescales;
4. determine femtosecond dynamics of carrier and exciton transport and tunneling; and
5. investigate interactions between various elementary excitations as well as many-body processes in semiconductors.

Researchers have exploited these unique strengths to gain fundamental new insights into nonequilibrium, nonlinear, and transport physics of semiconductors and their nanostructures over the past four decades.

A major focus of these efforts has been devoted to understanding how a semiconductor in thermodynamic equilibrium, excited by an ultrashort optical pulse, returns to the state of thermodynamic equilibrium. Four distinct regimes can be identified:

(a) the coherent regime in which a well-defined phase relationship exists between the excitation created by the optical pulse and the electromagnetic (optical) field creating it;
(b) the nonthermal regime in which the coherence (well-defined phase relationships) has been destroyed by various collision and interference processes but the distribution function of excitations is nonthermal (i.e., cannot be described by a Maxwell–Boltzmann distribution or its quantum (degenerate) counterparts);
(c) the hot carrier regime in which the distributions for various excitations are thermal, but with different characteristic temperatures for different excitations and thermal bath; and
(d) the isothermal regime in which the excitations and the thermal bath are at the same temperature but there is an excess of excitation (e.g., electron–hole pairs) compared to thermodynamic equilibrium.

Various physical processes take the semiconductor from one regime to the next, and provide information not only about the fundamental physics of semiconductors but also about the physics and ultimate performance limits of electronic, optoelectronic, and photonic devices.

In addition to coherent and relaxation dynamics, ultrafast studies of semiconductors provide new insights into tunneling and transport of carriers, and demonstrate novel quantum mechanical phenomena and coherent control in semiconductors.

The techniques used for such studies have also advanced considerably over the last four decades. Ultrafast lasers with pulse widths corresponding to only a few optical cycles (1 optical cycle ≈ 2.7 fs at 800 nm) have been developed. The response of the semiconductor to an ultrafast pulse, or a multiple of phase-locked pulses, can be investigated by measuring the dynamics of light emitted by the semiconductor using a streak camera (sub-ps time resolution) or a nonlinear technique such as luminescence up-conversion (time resolution determined by the laser pulse width for an appropriate nonlinear crystal). The response of the semiconductor can also be investigated using a number of two or three beam pump-probe techniques such as transmission, reflection, light scattering or four-wave mixing (FWM). Both the amplitude and the phase of the emitted radiation or the probe can be measured by phase-sensitive techniques such as spectral interferometry. The lateral transport of excitation can be investigated by using time-resolved spatial imaging and the vertical transport and tunneling of carriers can be investigated using the technique of ‘optical markers’. Electro-optic sampling can be used for transmission/reflection studies or for measuring THz response of semiconductors. More details on these techniques, and indeed many topics discussed in this brief article, can be found in the Further Reading.

Coherent Dynamics

The coherent response of atoms and molecules is generally analyzed for an ensemble of independent (noninteracting) two-level systems. The statistical properties of the ensemble are described in terms of the density matrix operator whose diagonal components relate to population of the eigenstates and off-diagonal components relate to coherence of the superposition state. The time evolution of the density matrix is governed by the Liouville variant of the Schrödinger equation $i\hbar\dot{\rho} = [H, \rho]$ where the system Hamiltonian $H = H_0 + H_{\text{int}} + H_R$ is the sum of the unperturbed, interaction (between the radiation field and the two-level system), and relaxation Hamiltonians, respectively. Using a number of different assumptions and approximations, this equation of motion is transformed into the optical Bloch equations (OBE), which are then used to predict the coherent response of the system, often using iterative procedures, and analyze experimental results.

Semiconductors are considerably more complex. Coulomb interaction profoundly modifies the response of semiconductors, not only in the linear regime (e.g., strong exciton resonance in the absorption spectrum) but also in the coherent and nonlinear regime. The influence of Coulomb interaction may be introduced by renormalizing the electron and hole energies (i.e., introducing excitons), and by renormalizing the field–matter interaction strength by introducing a renormalized Rabi frequency. These changes and the relaxation time approximation for the relaxation Hamiltonian lead to an analog of the optical Bloch equations, the semiconductor Bloch equations which have been very successful in analyzing the coherent response of semiconductors.

In spite of this success, it must be stressed that the relaxation time approximation, and the Boltzmann kinetic approach on which it is based, are not valid under all conditions. The Boltzmann kinetic approach is based on the assumption that the duration of the collision is much shorter than the interval between the collisions; i.e., the collisions are instantaneous. In the non-Markovian regime where these assumptions are not valid, each collision does not strictly conserve the energy and momentum and the quantum kinetic approach becomes more appropriate. This is true for photo-excited semiconductors as well as for the quantum transport regime in semiconductors. Also, semiconductor Bloch equations have been further extended by including four-particle correlations. Finally, the most general approach to the description of the nonequilibrium and coherent response of semiconductors following excitation by an ultrashort laser pulse is based on nonequilibrium Green's functions.

Experimental studies on the coherent response of semiconductors can be broadly divided into three categories:

1. investigation of novel aspects of coherent response not found in other simpler systems such as atoms;
2. investigation of how the initial coherence is lost, to gain insights into dephasing and decoherence processes; and
3. coherent control of processes in semiconductors using phase-locked pulses.

Numerous elegant studies have been reported. This section presents some observations on the trends in this field.

Historically, the initial experiments focused on the decay of the coherent response (time-integrated FWM as a function of delays between the pulses), analyzed them in terms of the independent two-level model, and obtained very useful information about various collision processes and rates (exciton–exciton, exciton–carrier, carrier–carrier, exciton–phonon, etc.). It was soon realized, however, that the noninteracting two-level model is not appropriate for semiconductors because of the strong influence of Coulomb interactions. Elegant techniques were then developed to explore the nature of coherent response of semiconductors. These included investigation of time- and spectrally resolved coherent response, and of both the amplitude and phase of the response to complement intensity measurements. These studies provided fundamental new insights into the nature of semiconductors and many-body processes and interactions in semiconductors. Many of these observations were well explained by the semiconductor Bloch equations. When lasers with <10 fs pulse widths became laboratory tools, the dynamics was explored on a time-scale much shorter than the characteristic phonon oscillation period (≈115 fs for GaAs longitudinal optical phonons), the plasma frequency (≈150 fs for a carrier density of 5×10^{17} cm^{-3}), and the typical electron–phonon collision interval (≈200 fs in GaAs). Some remarkable features of quantum kinetics, such as reversal of the electron–phonon collision, memory effects, and energy nonconservation, were demonstrated. More recent experiments have demonstrated the influence of four-particle correlations on coherent nonlinear response of semiconductors such as GaAs in the presence of a strong magnetic field.

The ability to generate phase-locked pulses with controllably variable separation between them provides an exciting opportunity to manipulate a variety of excitations and processes within a semiconductor. If the separation between the two phase-locked pulses is adjusted to be less than the dephasing time of the system under investigation, then the amplitudes of the excitations produced by the two phase-locked pulses can interfere either constructively or destructively depending on the relative phase of the carrier waves in the two pulses. The nature of interference changes as the second pulse is delayed over an optical period. A number of elegant experiments have demonstrated coherent control of exciton population, spin orientation, resonant emission, and electrical current. Phase-sensitive detection of the linear or nonlinear emission provides additional insights into different aspects of semiconductor physics.

These experimental and theoretical studies of ultrafast coherent response of semiconductors have led to fundamental new insights into the physics of semiconductors and their coherence properties. Discussion of novel coherent phenomena is given in a subsequent section. Coherent spectroscopy of semiconductors continues to be a vibrant research field.

Incoherent Relaxation Dynamics

The qualitative picture that emerges from investigation of coherent dynamics can be summarized as follows. Consider a direct gap semiconductor excited by an ultrashort laser pulse of duration τ_L (with a spectral width $h\Delta\nu_L$) centered at photon energy $h\nu_L$ larger than the semiconductor bandgap E_g. At the beginning of the pulse the semiconductor does not know the pulse duration so that coherent polarization is created over a spectral region much larger than $h\Delta\nu_L$. If there are no phase-destroying events during the pulse (dephasing rate$1/\tau_D \ll 1/\tau_L$), then a destructive interference destroys the coherent polarization away from $h\nu_L$ with increasing time during the excitation pulse. Thus, the coherent polarization exists only over the spectral region $h\Delta\nu_L$ at the end of the pulse. This coherence will be eventually destroyed by collisions and the semiconductor will be left in an incoherent (off-diagonal elements of the density matrix are 0) nonequilibrium state with peaked electron and hole population distributions whose central energies and energy widths are determined by $h\nu_L$, $h\Delta\nu_L$ and E_g, if the energy and momentum relaxation rates $(1/\tau_E, 1/\tau_M)$ are much smaller than the dephasing rates.

The simplifying assumptions that neatly separate the excitation, dephasing and relaxation regimes are obviously not realistic. A combination of all these (and some other) physical parameters will determine the state of a realistic system at the end of the exciting pulse. However, after times $\sim \tau_D$ following the laser pulse, the semiconductor can be described in terms of electron and hole populations whose distribution functions are not Maxwell–Boltzmann or Fermi–Direct type, but nonthermal in a large majority of cases in which the energy and momentum relaxation rates are much smaller than the dephasing rates. This section discusses the dynamics of this incoherent state.

Extensive theoretical work has been devoted to quantitatively understand these initial athermal distributions and their further temporal evolution. These include Monte Carlo simulations based on the Boltzmann kinetic equation approach (typically appropriate for time-scales longer than ~ 100 fs, the carrier–phonon interaction time) as well as the quantum kinetic approach (for times typically less than ~ 100 fs) discussed above. We present below some observations on this vast field of research.

Nonthermal Regime

A large number of physical processes determines the evolution of the nonthermal electron and hole populations generated by the optical pulse. These include electron–electron, hole–hole, and electron–hole collisions, including plasma effects if the density is high enough, intervalley scattering in the conduction band and intervalence band scattering in valence bands, intersub-band scattering in quantum wells, electron–phonon, and hole–phonon scattering processes. The complexity of the problem is evident when one considers that many of these processes occur on the same time-scale. Of these myriad processes, only carrier–phonon interactions and electron–hole recombinations (generally much slower) can alter the total energy in electronic systems. Under typical experimental conditions, the redistribution of energy takes place before substantial transfer of energy to the phonon system. Thus, the nonthermal distributions first become thermal distributions with the same total energy. Investigation of the dynamics of how the nonthermal distribution evolves into a thermal distribution provides valuable information about the nature of various scattering processes (other than carrier–phonon scattering) described above.

This discussion of separating the processes that conserve energy in the electronic system and those that transfer energy to other systems is obviously too simplistic and depends strongly on the nature of the problem one is considering. The challenge for the experimentalist is to devise experiments that can isolate these phenomena so each can be studied separately. If the laser energy is such that $h\nu_L - E_g < \hbar\omega_{LO}$, the optical phonon energy, then majority of the photo-excited electrons and holes do not have sufficient energy to emit an optical phonon, the fastest of the carrier–phonon interaction processes. The initial nonthermal distribution is then modified primarily by processes other than phonon scattering and can be studied experimentally without the strong influence of the carrier–phonon interactions. Such experiments have indeed been performed both in bulk and quantum well semiconductors. These experiments have exhibited spectral hole burning in the pump-probe transmission spectra and thus demonstrated that the initial carrier distributions are indeed nonthermal and evolve to thermal distributions. Such experiments have provided quantitative information about various carrier–carrier scattering rates as a function of carrier density. In addition, experiments with $h\nu_L - E_g > \hbar\omega_{LO}$ and $h\nu_L - E_g >$ intervalley separation have provided valuable information about intravalley as well as intervalley electron–phonon scattering rates. Experiments have been performed in a variety of different semiconductors, including bulk semiconductors and undoped and modulation-doped quantum wells. The latter provide insights into intersub-band scattering processes and quantitative information about the rates.

These measurements have shown that under typical experimental conditions, the initial nonthermal distribution evolves into a thermal distribution in times $<$ or ~ 1 ps. However, the characteristic temperatures of the thermal distributions can be different for electrons and holes. Furthermore, different phonons may also have different characteristic temperatures, and may even be nonthermal even when the electronic distributions are thermal. This is the hot carrier regime that is discussed in the next subsection.

Hot Carrier Regime

The hot carriers, with characteristic temperatures T_c (T_e and T_h for electrons and holes, respectively), have high energy tails in the distribution functions that extend several kT_c higher than the respective Fermi energies. Some of these carriers have sufficient energy to emit an optical phonon. Since the carrier–optical phonon interaction rates and the phonon energies are rather large, this may be the most effective energy loss mechanism in many cases even though the number of such carriers is rather small. The emitted optical phonons have relatively small wavevectors and nonequilibrium populations larger than expected for the lattice temperature. These optical phonons are often referred to as hot phonons although nonequilibrium phonons may be a better term since they probably have nonthermal distributions. The dynamics of hot phonons will be discussed in the next subsection, but we mention here that in case of a large population of hot phonons, one must consider not only phonon emission but also phonon absorption. Acoustic phonons come into the picture at lower temperatures when the fraction of carriers that can emit optical phonons is extremely small or negligible, and also in the case of quantum wells with sub-band energy separation smaller than optical phonons.

The dynamics of hot carriers have been studied extensively to obtain a deeper understanding of carrier–phonon interactions and to obtain quantitative measures of the carrier–phonon interaction rates. Time resolved luminescence and pump-probe transmission spectroscopy are the primary tools used for such studies. For semiconductors like GaAs, the results indicate that polar optical phonon scattering (longitudinal optical phonons) dominates for electrons whereas polar and nonpolar optical phonon scattering contribute for holes. Electron–hole scattering is sufficiently strong in most cases to maintain a common electron and hole temperature for times $> \sim 1$ ps. Since many of these experiments are performed at relatively high densities, they provide important information about many-body effects such as screening. Comparison of bulk and quasi-two-dimensional semiconductors (quantum wells) has been a subject of considerable interest. The consensus appears to be that, in spite of significant differences in the nature of electronic states and phonons, similar processes with similar scattering rates dominate both types of semiconductors. These studies reveal that the energy loss rates are influenced by many factors such as the Pauli exclusion principle, degenerate (Fermi–Dirac) statistics, hot phonons, and screening and many-body aspects.

Hot carrier distribution can be generated not only by photo-excitation, but also by applying an electric field to a semiconductor. Although the process of creating the hot distributions is different, the processes by which such hot carriers cool to the lattice temperature are the same in two cases. Therefore, understanding obtained through one technique can be applied to the other case. In particular, the physical insights obtained from the optical excitation case can be extremely valuable for many electronic devices that operate at high electric fields, thus in the regime of hot carriers. Another important aspect is that electrons and holes can be investigated separately by using different doping. Furthermore, the energy loss rates can be determined quantitatively because the energy transferred from the electric field to the electrons or holes can be accurately determined by electrical measurements.

Isothermal Regime

Following the processes discussed above, the excitations in the semiconductor reach equilibrium with each other and the thermal bath. Recombination processes then return the semiconductor to its thermodynamic equilibrium. Radiative recombination typically occurs over a longer time-scale but there are some notable exceptions such as radiative recombination of excitons in quantum wells occurring on picosecond time-scales.

Hot Phonons

As discussed above, a large population of nonequilibrium optical phonons is created if a large density of hot carriers has sufficient energy to emit optical phonons. Understanding the dynamics of these nonequilibrium optical phonons is of intrinsic interest.

At low lattice temperatures, the equilibrium population of optical phonons is insignificant. The optical phonons created as a result of photoexcitation occupy a relatively narrow region of wavevector (k) space near $k = 0$ ($\sim 1\%$ of the Brillouin zone). This nonequilibrium phonon distribution can spread over a larger k-space by various processes, or anharmonically decay into multiple large-wavevector acoustic phonons. These acoustic phonons then scatter or decay into small-wavevector, low-energy acoustic phonons that are eventually thermalized.

Pump-probe Raman scattering provides the best means of investigating the dynamics of nonequilibrium optical phonons. Such studies, for bulk and quantum well semiconductors, have provided invaluable information about femtosecond dynamics of phonons. In particular, they have provided the rate at which the nonequilibrium phonons decay. However, this information is for one very small value of the phonon wavevector so the phonon distribution function within the optical phonon branch is not investigated. The large-wavevector acoustic phonons are even less accessible to experimental techniques. Measurements of thermal phonon propagation provide some information on this subject. Finally, the nature of phonons is considerably more complex in quantum wells, and some interesting results have been obtained on the dynamics of these phonons.

Tunneling and Transport Dynamics

Ultrafast studies have also made important contributions to tunneling and transport dynamics in semiconductors. Time-dependent imaging of the luminescing region of a sample excited by an ultrashort pulse provides information about spatial transport of carriers. Such a technique was used, for example, to demonstrate negative absolute mobility of electrons in p-modulation-doped quantum wells. The availability of near-field microscopes enhances the resolution of such techniques to measure lateral transport to the subwavelength case.

A different technique of 'optical markers' has been developed to investigate the dynamics of transport and tunneling in a direction perpendicular to the surface (vertical transport). This technique relies heavily on fabrication of semiconductor nanostructures with desired properties. The basic idea is to fabricate a sample in which different spatial regions have different spectral signatures. Thus if the carriers are created in one spatial region and are transported to another spatial region under the influence of an applied electric field, diffusion, or other processes, the transmission, reflection, and/or luminescence spectra of the sample change dynamically as the carriers are transported.

This technique has provided new insights into the physics of transport and tunneling. Investigation of perpendicular transport in graded-gap superlattices showed remarkable time-dependent changes in the spectra, and analysis of the results provided new insight into transport in a semiconductor of intermediate disorder. Dynamics of carrier capture in quantum wells from the barriers provided information not only about the fundamentals of capture dynamics, but also about how such dynamics affects the performance of semiconductor lasers with quantum well active regions.

The technique of optical markers has been applied successfully to investigate tunneling between the two quantum wells in an a-DQW (asymmetric double quantum well) structure in which two quantum wells of different widths (and hence different energy levels) are separated by a barrier. The separation between the energy levels of the system can be varied by applying an electric field perpendicular to the wells. In the absence of resonance between any energy levels, the wavefunction for a given energy level is localized in one well or the other. In this nonresonant case, it is possible to generate carriers in a selected quantum well by proper optical excitation. Dynamics of transfer of carriers to the other quantum well by tunneling can then be determined by measuring dynamic changes in the spectra. Such measurements have provided much insight into the nature and rates of tunneling, and demonstrated phonon resonances. Resonant tunneling, i.e., tunneling when two electronic levels are in resonance and are split due to strong coupling, has also been investigated extensively for both electrons and holes. One interesting insight obtained from such studies is that tunneling and relaxation must be considered in a unified framework, and not as sequential events, to explain the observations.

Novel Coherent Phenomena

Ultrafast spectroscopy of semiconductors has provided valuable insights into many other areas. We conclude this article by discussing some examples of how such techniques have demonstrated novel physical phenomena.

The first example once again considers an a-DQW biased in such a way that the lowest electron energy level in the wide quantum well is brought into resonance with the first excited electron level in the narrow quantum well. The corresponding hole energy levels are not in resonance. By choosing the optical excitation photon energy appropriately, the hole level is excited only in the wide well and the resonant electronic levels are excited in a linear superposition state such that the electrons at $t = 0$ also occupy only the wide quantum well. Since the two electron eigenstates have slightly different energies, their temporal evolutions are different with the result that the electron wavepacket oscillates back and forth between the two quantum wells in the absence of damping. The period of oscillation is determined by the splitting between the two resonant levels and can be controlled by an external electric field. Coherent oscillations of electronic wavepackets have indeed been experimentally observed by using the coherent nonlinear technique of four-wave mixing. Semiconductor quantum wells provide an excellent flexible system for such investigations.

Another example is the observation of Bloch oscillations in semiconductor superlattices. In 1928 Bloch demonstrated theoretically that an electron wavepacket composed of a superposition of states from a single energy band in a solid undergoes a periodic oscillation in energy and momentum space under certain conditions. An experimental demonstration of Bloch oscillations became possible only recently by applying ultrafast optical techniques to semiconductor superlattices. The large period of a superlattice (compared to the atomic period in a solid) makes it possible to satisfy the assumptions underlying Bloch's prediction. The experimental demonstration of Bloch oscillations was also performed using four-wave mixing techniques. This provides another prime example of the power of ultrafast optical studies.

Summary

Ultrafast spectroscopy of semiconductors and their nanostructures is an exciting field of research that has provided fundamental insights into important physical processes in semiconductors. This article has attempted to convey the breadth of this field and the diversity of physical processes addressed by this field. Many exciting developments in the field have been omitted out of necessity. The author hopes that this brief article inspires the readers to explore some of the Further Reading.

See also

Coherence: Coherence and Imaging. **Coherence Control:** Experimental; Theory. **Coherent Transients:** Ultrafast Studies of Semiconductors. **Nonlinear Optics, Basics:** Four-Wave Mixing. **Scattering:** Scattering Theory.

Further Reading

Allen L and Eberly JH (1975) *Optical Resonance and Two-Level Atoms*. New York: Wiley Interscience.

Chemla DS (1999) Chapter 3. In: Garmire E and Kost AR (eds) *Nonlinear Optics in Semiconductors*, pp. 175–256. New York: Academic Press.

Chemla DS and Shah J (2001) Many-body and correlation effects in semiconductors. *Nature* 411: 549–557.

Haug H (2001) Quantum kinetics for femtosecond spectroscopy in semiconductors. In: Willardson RK and Weber ER (eds) *Semiconductors and Semimetals*, vol. 67, pp. 205–229. London: Academic Press.

Haug H and Jauho AP (1996) *Quantum Kinetics in Transport and Optics of Semiconductors*. Berlin: Springer-Verlag.

Haug H and Koch SW (1993) *Quantum Theory of the Optical and Electronic Properties of Semiconductors*. Singapore: World Scientific.

Kash JA and Tsang JC (1992) Chapter 3. In: Shank CV and Zakharchenya BP (eds) *Spectroscopy of Nonequilibrium Electrons and Phonons*, pp. 113–168. Amsterdam: Elsevier.

Mukamel S (1995) *Principles of Nonlinear Optical Spectroscopy*. New York: Oxford University Press.

Shah J (1992) *Hot Carriers in Semiconductor Nanostructures: Physics and Applications*. Boston, MA: Academic Press.

Shah J (1999) *Ultrafast Spectroscopy of Semiconductors and Semiconductor Nanostructures*. 2nd edn. Heidelberg, Germany: Springer-Verlag.

Steel DG, Wang H, Jiang M, Ferrio KB and Cundiff ST (1994) In: Phillips RT (ed.) *Coherent Optical Interactions in Solids*, pp. 157–180. New York: Plenum Press.

Wegener M and Schaefer W (2002) *Semiconductor Optics and Transport*. Heidelberg, Germany: Springer-Verlag.

Zimmermann R (1988) *Many-Particle Theory of Highly Excited Semiconductors*. Leipzig, Germany: Teubner.

COLOR AND THE WORLD

G N Rao, Adelphi University, Garden City, NY, USA

© 2005, Elsevier Ltd. All Rights Reserved.

The human visual system is capable of detecting a small part of the electromagnetic spectrum which is called light. The visible region has a typical wavelength range of about 380–780 nm. Under optimal conditions the range is 360–830 nm. The most important point is that color is a perception. It is how human beings perceive the visual part of the electromagnetic spectrum. The color of an object perceived depends on the physical characteristics of the radiation illuminating the object, spectral scattering and reflectivity of the object, physiology of the eye, photochemistry of the sensors in the retina, the complex data processing that takes place in the visual system, and the psychology of color perception. In this review, we present an overview of color in nature and the world. Initially, color and wavelength is presented, then the human visual system and color perception. Then we go on to discuss measuring color and colorimetry and then color in nature, followed by a brief account of color in art and holography and the structural colors in nature.

Color and Wavelength (Spectral and Nonspectral Colors)

The ingenious yet simple experiments performed by Isaac Newton in the year 1666 and his ideas presented in his famous treatise 'Opticks', are the foundations of our understanding of color and color perception. Based on his experiments, Newton showed that different regions of the visible spectrum are perceived as different colors and the solar radiation (white light) consists of spectral colors violet, blue, cyan, green, yellow, orange, and red. Thus, natural day light is quite colorful though we perceive it as colorless. Table 1 gives approximate wavelength ranges of the spectral colors. Superposition of all the spectral colors results in a perception of white.

Colors can be produced in a number of ways:

1. *Gas discharges* emit characteristic radiation in the visible region. For example, neon discharge is red in color, argon discharge blue, sodium discharge yellow, helium-neon laser gives red radiation and argon ion laser blue-green radiation. A variety of fluorescent lamps are available and they provide continuous spectral power distribution with characteristic lines of mercury in the blue-green region. Gas-filled sodium and fluorescent lamps offer long life and high efficiency and are popular for indoor and outdoor lighting.
2. *Transition metal* (Cr, Mn, Fe, Co, Ni, Cu) compounds or transition metal impurities are responsible for the colors of the minerals, paints, gems, and pigments. They involve inorganic compounds of transition metal or rare earth ions with unpaired d or f orbitals. About 1% chromium sesquioxide (Cr_2O_3) in colorless aluminum oxide results in beautiful red ruby, a gemstone. The Cr^{3+} impurity in pure beryllium aluminum silicate gives a beautiful emerald green resulting in sapphire, another gemstone. Transition metal impurities are added to glass in the molten state to prepare colored glass. For example, adding Cr^{3+} gives green, Mn^{3+} purple, Fe^{3+} pale yellow, Co^{3+} reddish blue, Ni^{2+} brown, and Cu^{2+} greenish blue color.
3. *Color in Organic Compounds* – Most natural and synthetic dyes and biological (vegetable and animal origin) colorants are complicated organic molecules. They absorb light, exciting molecular orbitals. The dyes are used for food coloration, clothing, photographic, and sensitizer purposes.
4. *Colors of metals, semiconductor materials and color centers* – The colors of these materials are caused by the electronic transitions involving the energy bands.

   Diode lasers emit radiation corresponding to the bandgap of the semiconductor materials used for their fabrication. They are inexpensive, compact, and can be operated using dry cell batteries. They are extensively used in compact disks, barcode readers, and optical communications.

   Light emitting diodes (LED) are also prepared using semiconductor materials and they emit radiation corresponding to the bandgap of the semiconductor materials used for their fabrication. LEDs are available in a variety of colors, red (GaAsP), orange (AlInGaP), yellow (InGaAs), green (CdSSe), blue (CdZnS) and are widely used in clocks, toys, tuners, displays, electronic billboards, and appliances.

   Color centers may be produced by irradiating some alkali halides and glass materials with electromagnetic radiation (gamma rays, X-rays, ultraviolet, and visible radiation) or with charged or uncharged particles (electrons, protons, neutrons). The irradiation produces an electron hole pair and the electron is trapped forming an electron center. The electron or hole, or both, form a color center absorbing part of the visible radiation. The color centers can be reversed by heating to high temperatures.
5. *Optical Phenomenon* lead to spectacular colors in nature and in biological materials. Scattering of light by the atmosphere is responsible for colors of the sky, beautiful sunsets and sunrise, twilight, blue moon, and urban glows. Dispersion and polarization cause rainbows and halos. Interference gives rise to the beautiful colors of thin films on water, foam, bubbles, and some biological colors (butterflies). Diffraction is responsible for the colors of liquid crystals, coronae, color of gems (opal), color of animals (sea mouse), the colors of butterfly (*Morpho rhetenor*), and diffraction gratings.

Table 1 Approximate wavelength ranges of different spectral colors

Color	*Wavelength range (nm)*
Violet	380–435
Blue	435–500
Cyan	500–520
Green	520–565
Yellow	565–597
Orange	597–625
Red	625–780

The Human Visual System and Color Perception

Photoreceptors in the Eye: Rods and Cones

As light enters the eye, the cornea and the eye lens focus the image on the retina. The retina has two kinds of photoreceptors: rods and cones so named because of their shapes. Typically, there are about 7 million cones and 110–125 million rods. Cones are activated during photopic (daylight) conditions and the rods during scotopic (night) conditions. Cones are responsible for color perception whereas rods can perceive only white and gray shades. Cones are predominantly located near the fovea, the central region of the retina. When light falls on the rods and the cones, the photosensitive material in them, namely rhodopsin, is activated, generating an electrical signal which is further processed in the visual system and transmitted to the visual cortex. Considerable data processing takes place within the retina.

Color Perception

Subjective nature of color

Color is a perception and is subjective. There is no way one can define color in an absolute or quantitative means, even though it can be precisely characterized by the spectral power distribution (SPD) of the radiation. For monochromatic light of different wavelengths we see the spectral colors detailed in Table 1. In general, the SPD of light from an object is complex and to predict the exact color of such a spectrum is quite difficult. However, in the following we discuss some simple color schemes.

Additive color mixing

Newton's experiments demonstrated that using the three primary color light sources, blue, green, and red and by varying their relative intensities, one can generate most of the colors by additive color mixing. Additive color mixing is employed in stage lighting, and large screen color television projection systems. If we are concerned only with the hue and ignore saturation and brightness, the superposition of colored light beams of equal brightness on a white screen gives the following simple additive color scheme:

$$\text{Green} + \text{Red} \Rightarrow \text{Yellow}$$

$$\text{Blue} + \text{Red} \Rightarrow \text{Magenta}$$

$$\text{Blue} + \text{Green} \Rightarrow \text{Cyan}$$

$$\text{Blue} + \text{Green} + \text{Red} \Rightarrow \text{White}$$

Subtractive color mixing

When white light passes through, say, a red filter, the radiation corresponding to the red radiation is transmitted and all other parts of the visible spectrum are absorbed. If we insert more red filters the brightness of the light transmitted becomes less though the hue is likely to be more saturated. If you insert red and blue filters together in a white beam, you will see no light transmitted because the red filter blocks the entire spectrum except the radiation corresponding to red color which in turn is blocked by the blue filter.

Subtractive color scheme is also applicable when paints of various colors are mixed together. The subtractive primary colors are magenta, yellow, and cyan. The artists often call them red, yellow, and blue. By appropriately mixing the primary colored paints one can, in principle, generate most of the colors.

How many colors can we differentiate?

If we do a simple experiment beginning from the lowest wavelength of the visible spectrum, say 380 nm, and gradually move to the long wavelength end of the visible spectrum, one can differentiate about 150 spectral colors. For each spectral color there will be a number of colors that vary in brightness and saturation. Additionally, we can have additive mixtures of these spectral colors, which in turn have variations in brightness and saturation. It is estimated that under optimal conditions we can differentiate as many as 7 to10 million different colors and shades.

Temporal Response of the Human Visual System

Positive afterimages

The visual system responds to changes in the stimulation in time. However, the response of the visual system is both delayed and persists for some time after the stimulation is off. Because of the persistence of vision, one would see positive afterimages. The afterimages last about 1/20 s under normal conditions but are shorter at high light conditions. A rapid succession of images show results in a perception of continuous motion which is the basis for movies and TV.

Close your eyes for about five minutes so that any after images of the objects you have seen before are cleared. Open your eyes to see a bright colored object and then close your eyes again; you will see positive afterimages of the object in its original colors. Even though the positive afterimage at the initial stages will be of the same colors as the original, they gradually change color showing that different cones recover at different rates.

Negative afterimages

If you stare at a color picture intensely for about a minute and look at a white background, such as a sheet of white paper, you will see the complementary colors of the picture. The image of the object falls on a particular part of the retina and if we look at a green colored object, the cones that are more sensitive to the mid-wavelength region are activated and are likely to be saturated. If you look at a bright sheet of white paper immediately, the cones that are sensitive to the middle wavelength region are inactivated since they need some time to replenish the active chemical whereas the cones that have maximum sensitivity for the low and high wavelengths are active, therefore you will see the object in complementary colors. Yellow will be seen after looking at blue image, cyan after looking at red image and vice versa.

Spatial Resolution of the Human Visual System

Lateral inhibition (color constancy)

By and large the perceived color of an object is independent of the nature of the illuminating white light source. The color of the object does not change markedly under different white light sources of illumination. For example, we see basically the same color of the object in the daytime in the light of the blue sky or under an incandescent light source even though the spectral power distributions of these sources are different and the intensity of light reaching the eye in both cases is also drastically different. The color constancy is a result of chromatic lateral inhibition. The human visual system has a remarkable way of comparing the signals from the object and manipulating them with the signals generated from the surroundings and picking up the correct color independent of the illuminating source. The color constancy and simultaneous lightness contrast are due to lateral inhibition. Lateral inhibition was exploited by a number of artists to provide certain visual effects that would not have been possible otherwise. For example, Georges Seurat in his famous painting 'La Poseuse en Profil' improved the light intensity contrast in different regions of his painting by employing edge enhancement effects resulting from lateral inhibition. Victor Vasarely's art work 'Arcturus' demonstrates the visual effects of lateral inhibition in different colors.

Spatial assimilation

The color of a region assimilates the color of the neighboring region, thus changing the perception of its color. Closely spaced colors, when viewed from a distance, tend to mix partitively and are not seen as distinct colors but as a uniform color due to additive color mixing. Georges Seurat in his painting 'Sunday Afternoon on the Island of La Grande Jatte', uses thousands of tiny dots of different colors to produce a variety of color sensations, a technique which is known as pointillism. The visual effects of spatial assimilation were clearly demonstrated by Richard Anuszkiewicz in his painting 'All Things Do Live in the Three'.

Color Perception Models

Thomas Young, in 1801, postulated that there are three types of sensors thus proposing trichromacy to explain the three attributes of color perception: hue, saturation, and brightness. Data on microspectrophotometry of excised retinas, reflection densitometry of normal eyes, and psychophysical studies of different observers confirm the existence of three types of cones. As shown in Figure 1, the three types of cones have different responsivities to light. The cones that have maximum responsivity in the short wavelength region are often refereed as S-cones, the cones that have maximum in the intermediate wavelength range as I-cones, and the cones that have maximum in the long wavelength region as L-cones.

The three response curves have considerable overlap. The overlap of the response curves and the complex data processing that takes place in the visual system enable us to differentiate as many as 150 spectral colors and about seven to ten million different colors and shades. An important consequence of the existence of only three types of color sensors is that different spectral power distributions can produce identical stimuli resulting in the perception of the same color. Such spectral power distributions are called metamers.

The neural impulses generated by the cones are processed through a complex cross-linking of bipolar cells, horizontal cells, amacrine cells, and communicated to ganglion cells leading to the optic chiasmas through the optic nerve. Information gathered by about 100 million photoreceptors, after considerable processing, is transmitted by about a million ganglion cells.



Figure 1 Relative spectral absorption of the three types of cones. *S*, *I*, and *L* respectively stand for the cones that have maximum responsivity for the short, intermediate, and long wavelength regions.

The zone theory of color vision assumes two separate zones where the signals are sequentially processed. In the first zone the signals are generated by the cones and in the second zone, the signals are processed to generate one achromatic and two opponent chromatic signals. Possibly other zones exist where the signals generated in the first and the second zones are further processed and communicated to the visual cortex where they are processed and interpreted based on the temporal and spatial response and comparisons with the information already available in the memory.

Measuring Color and Colorimetry

Since color is a human perception, how do we measure color? Colorimetry is based on the human visual system and how different observers perceive color. Though, the spectral power distribution of light is helpful for characterizing spectral hues, it is very difficult to infer the color from the spectral power distribution.

The three attributes of color perception are hue, saturation, and brightness. Hue is the color such as red, green, and blue. Saturation refers to the purity of the color. A color is said to be more saturated if the whiteness in the color is less and vice versa. Brightness is related to the intensity of light. For the sun at sunrise the hue is red, saturated, and low brightness. About half an hour after sunrise, the hue is yellow, less saturated, and higher brightness. Though a variety of color schemes are available in the literature, in the following we discuss the Munsell system and the C.I.E. diagram only.

Munsell Color System

Albert Munsell, a painter and art teacher, devised a color atlas in 1905 by arranging different colors in an ordered three-dimensional space. He used the three color attributes hue, chroma, and value corresponding to hue, saturation, and brightness. In this system there are 10 basic hues, each of which is divided into 10 equal gradations, resulting in 100 equally spaced hues. Each hue has a chart with a number of small chips arranged in rows and columns. Under daylight illumination, the chips in any column are supposed to have colors of equal chroma and the chips in any row are supposed to be of equal brightness. The brightness increases from the bottom of the chart to the top in steps that are perceptually equal. The saturation of the color increases from the inside edge to the outside edge of the chart in steps that are also perceptually equal. Each chip is identified by hue, value/chroma. In the Munsell scale, black is given a value of 0 and white 10, and the nine grays are uniformly placed in between. Though the Munsell system has gone through many revisions, typically it has a total of about 1450 chips. The Munsell color scheme, though subjective in nature, is widely used because of its simplicity and ease.

The Commission Internationale de l'Echlairage (C.I.E.) Diagram

Even though the visible light reaching the eye has a very complex SPD, color perception is mostly dependent on the signals generated by the three different types of cones. However, we do not know precisely the absorption and sensitivity of the cones and therefore are not in a position to calculate the signal strengths generated by the three different cones. Additionally, the response of the cones is specific to the individual. Therefore, the C.I.E. system is based on the average response of a large sample of normal observers. The C.I.E. system employs three color matching functions $\bar{x}(\lambda), \bar{y}(\lambda)$, and $\bar{z}(\lambda)$ (Figure 2), based on the psychological observations of a large number of standard observers to calculate the 'tristimulus values' X, Y, and Z defined as

$$X = c\int S(\lambda)\bar{x}(\lambda)\mathrm{d}\lambda \qquad [1]$$

$$Y = c\int S(\lambda)\bar{y}(\lambda)\mathrm{d}\lambda \qquad [2]$$

$$Z = c\int S(\lambda)\bar{z}(\lambda)\mathrm{d}\lambda \qquad [3]$$

Here, λ is the wavelength, $S(\lambda)$ the spectral power distribution, and c is the normalization constant. The integration is carried out over the visible region, normally 380 to 780 nm. The system is based on the assumption of additivity and linearity. The sum of the tristimulus values $(X + Y + Z)$ is normalized to 1. We choose $y(\lambda)$ so that the Y tristimulus value is proportional to the luminance which is a quantitative measure of the intensity of light leaving the surface. We further calculate x and y which are called chromaticity coordinates:

$$x = \frac{X}{(X + Y + Z)} \qquad [4]$$

$$y = \frac{Y}{(X + Y + Z)} \qquad [5]$$

The psychological color is then specified by the coordinates (Y, x, y). Relationship between colors is usually displayed by plotting the x and y values on



Figure 2 Color-matching functions $\bar{x}$ (λ),$\bar{y}$ (λ), and $\bar{z}$ (λ) of the C.I.E. 1931 standard observer.

a two-dimensional Cartesian Coordinate system with z as an implicit parameter ($z = 1 - x - y$) which is known as the C.I.E. chromaticity diagram (Figure 3). In this plot, the monochromatic hues are on the perimeter of a horseshoe shaped curve and is called spectrum locus. A straight line joining the ends of the spectrum is called the line of purples. Every chromaticity is represented by means of two coordinates (x, y) in the chromaticity diagram. The point corresponding to $x = 1/3$ and $y = 1/3$ (also $z = 1/3$) is the point of 'equal energy' and represents achromatic point. The complementary colors are on the opposite sides of the achromatic point. Complementary wavelength of a color is obtained by drawing a line from the color through the achromatic point to the perimeter on the other side.

Continuum (white) sources

A perfect white source is the one that has constant SPD over the entire visible region. Such a source will not distort the color of the objects they illuminate. A number of sources in general are considered as white sources; they include incandescent lamps, day skylight, a variety of fluorescent lamps, etc. It should be noted that the SPD of these sources is not constant and varies with the source. Typical SPDs of commonly used light sources are given in Figure 4.

Color temperature

The thermal radiation emitted by a black body has a characteristic SPD which depends solely on its temperature. The wavelength λ of the peak of this distribution is inversely proportional to its absolute temperature. As the absolute temperature of the blackbody increases, the peak shifts towards shorter wavelengths (blue region) and also the width of the distribution decreases. Since the peak of the black body radiation is dependent on the absolute temperature, the color of the blackbody can be approximately defined by its temperature.

The color temperature of a body is that temperature at which the SPD of the body best matches with that of the blackbody radiation at that temperature. The concept of color temperature is often used to characterize the sources. Low color temperature sources have a reddish tinge and high color temperature sources tend to be slightly bluish. For example, the color temperature of red looking star Antares is about 5000 K and that of the bluish white looking Sirius is about 11 000 K. One should note that the color temperature of a body is different from its actual temperature. The fluorescent lamps have a



Figure 3 Chromaticity diagram of the C.I.E. 1931 standard observer. The chromaticities of the incandescent sources and their color temperatures are given inside the curve. A, B, and C are the C.I.E. standard illuminants. The chromaticities of the helium-neon laser (red, 633 nm) and the argon-ion laser (green 515 nm, blue 488 nm, and indigo, 458 nm) are also shown.



Figure 4 Relative SPDs of commonly used white light sources.

color temperature range of 5000–7500 K, incandescent lamps about 3000 K, direct sunlight ~4870 K and overcast skylight has a color temperature of ~7000 K.

The C.I.E. chromaticity diagram along with the color temperatures of the commonly employed sources, is shown in Figure 3.

Color in the Nature

As the solar radiation passes through the atmosphere, it is partly absorbed and partly scattered by the atmospheric constituents: air, water vapor, and dust particles. Absorption depends on the molecular properties of the air molecules, water vapor, and the dust particles, and is strongly wavelength dependent. Absorbed energy increases the internal energy of the molecule finally manifesting itself as thermal energy. When the sun is at the zenith, the solar radiation passes through one air mass loosing approximately 32% of its power. The SPD of the solar radiation above the atmosphere and at the Earth's surface at air mass 1 is shown in Figure 5. Scattering and absorption of the solar radiation by the atmosphere are responsible for a variety of interesting colorful views in the nature and they are briefly discussed in this section.

Atmospheric Colors

1. *Colors of the sky.* Scattering occurs over most of the visible part of the electromagnetic spectrum and is a function of the frequency of



Figure 5 Spectral irradiance (kW m^{-2} µm^{-1}) of the solar radiation measured above the atmosphere and at the Earth's surface at sea level on a clear day and the sun at the zenith.

the radiation. According to Lord Raleigh's theory of scattering, the scattering probability varies inversely as a function of the fourth power of the wavelength of the radiation. If we consider the radiation corresponding to blue (400 nm) and the radiation corresponding to say red (700 nm), the photons corresponding to blue radiation are scattered by about 9.4 times that of photons corresponding to the red radiation. During noontime, when we look at the sky, not directly at the sun, the sky looks unsaturated blue because of the predominant scattering experienced by the high frequency radiation corresponding to blue color. However, it should be noted that the daytime skylight contains all the spectral colors of the solar radiation though the spectral power distribution has changed resulting in an increase in the intensity of the high frequency (blue) radiation. During noontime at the horizon, the sky looks close to white in color with a bluish tinge, because the solar radiation has passed through many air masses. As the thickness of the atmosphere increases, the intensity of the blue radiation decreases and ultimately as the radiation reaches the horizon, all the spectral colors are scattered about the same level resulting in white or bluish white sky.

2. *Polarization of the solar radiation by the atmosphere.* Light scattered by a molecule is polarized. The blue skylight is polarized with a maximum polarization of about 75% to 85% at 90° from the sun.
3. *Distant mountains seem bluish in color.* When an artist wishes to paint a distant mountain in perspective, he/she paints it blue; why? This is called airlight. The low wavelength part of the solar radiation is scattered more prominently, giving it a blue perspective when observed from a distance. However, it should be mentioned that the distant mountains may look any color depending on the scattering and absorption of the solar radiation sometimes resulting in 'Purple Mountain's majesty.'
4. *Sun looks red at the sunrise and sunset.* At sunset as the sun approaches the horizon, the sun changes its color from dazzling white to yellow, orange, bright red, and dull red and the order is reversed at sunrise. At the sunsets and sunrise, the solar radiation travels through many airmasses compared to approximately one airmass when the sun is at the zenith. Because of the large mass of air the radiation has to pass through, first the blue part of the spectrum is removed and the transmitted green to red spectral colors give the appearance of yellow. As this spectrum passes through more airmass, green is scattered most, leaving spectral yellow, orange, and red. As the radiation further passes through air, yellow and orange are also scattered, leaving only red.

5. *Twilight*. After sunset (dusk), or before the sunrise (dawn), the sky is illuminated by light which in turn illuminates the landscape. At sunsets and sunrise the solar radiation passes through a large mass of air. At a solar depression of about 0°, most of the blue is lost by scattering, resulting in a yellow arch and bright sky, and as the solar depression increases to about 10°, the arch will be reddish and the brightness of the sky reduced.
6. *Alpenglow*. Snow-covered mountains glow orange yellow from the low sun and after the sunset the same mountains look purple because of the reflection of the twilight.
7. *Twinkling of stars*. The stars twinkle. The local variations in the density of air are responsible for the twinkling of stars. As the density of air changes, so does the index of refraction and the starlight is continually refracted and dispersed. Twinkling is more prominent when the stars are on the horizon or on cold clear and windy nights.
8. *Mirages*. Mirages are refracted images produced because of the existence of refractive index gradients in the atmosphere. This results in the sight of shimmering water on a highway, inverted view of a car, etc.
9. *Aurora Borealis*. Aurorae are diffused slowly moving lights seen at high latitudes. They are often greenish yellow with different shapes. The lights in the northern hemisphere are called 'Aurora Borealis' and the lights in the southern hemisphere 'Aurora Australis.' They are caused primarily by the high-energy electrons deflected by the Earth's magnetic field towards the Earth's magnetic poles interacting with the atmospheric molecules resulting in molecular excitation and ionization. When the molecules de-excite, the characteristic electromagnetic radiation is commonly emitted. The commonly seen yellow-green light is due to the molecular emission of oxygen at 557 nm.
10. *Urban glows*. The scattered light from cities can be observed from space. The metropolitan Los Angeles can be observed from about 250 km in space. Extensively used sodium lamps with strong spectral yellow and blue-green mercury and fluorescent lights have unique color spectra of their own.

Colors due to Water and Water Droplets

1. *What is the color of pure water?* The transmission coefficient of pure water as a function of wavelength for different thicknesses of water column is shown in Figure 6. Our perception of the color of water changes with the thickness of water. For 1 mm thick water column, all the wavelengths are transmitted, resulting in the perception of white; 1 m thick water column looks unsaturated bluish green. As the thickness of water increases, the bluish green color will get more and more saturated. The color of water perceived by us depends on: (i) light reflected from the water surface; (ii) the light refracted at the water surface and diffused and scattered by the water molecules; and (iii) the refracted light reaches the bottom and gets reflected, which is further diffused and scattered and refracted at the water surface again. What we see is an additive sum of all these components.



Figure 6 Transmission coefficient of water as a function of wavelength for different thicknesses of water (1 mm, 1 m, and 10 m).

2. *Refraction through water–air interface*. When light travels from an optically denser medium to an optically lighter medium, the light is deviated away from the normal. This is the reason why the apparent depth of a fish located in a pond is less than the true depth and a pencil struck in water seems to bend. If you are a diver when you look at the horizon from under water, the hemisphere seems to be compressed into a circle of diameter 97.2° instead of 180° which is known as 'Optical Manhole.'
3. *Glitter*. When you look at the reflection of the sun or the moon in wavy water, you notice a bright elongated reflected light known as glitter. It has a brilliant reddish orange color when the sun is above the horizon. Since the water is wavy, light reflected by a certain part of the wave at a certain time has the correct angle of reflection to reach your eye, which is known as glint. An ensemble of a large number of glints

coming from different waves and different parts of the waves results in glitter. Since you are looking at the reflected light, it will be polarized.

4. *Sky pools and landpools*. The light coming from a wavy water surface of a lake consists of oval shaped bright colored patterns that continually change in shape. This results from the reflection of skylight by the wavy water. If the waves are not turbulent the reflected light reaching your eye continually changes resulting in bright colored patterns. Landpools are caused by a nearby sloping landscape and the reflected light pattern from the landscape.
5. *Thin films*. Oil floats on water and spreads into thin films because of its low surface tension. When viewed in reflected natural white light, the light reflected from the top surface of the oil and the light reflected from the interfacial surface of oil and water interfere to produce colorful patterns. Brilliant colored patterns are commonly seen on the roads after rain because of gasoline on water. Foam ordinarily consists of bubbles ranging typically 10^{-4} mm to several mm. Even though each bubble produces colorful light due to the interference effects, the light coming out of the foam adds up to white light.
6. *Wet surfaces look darker*. A water spot on a concrete road looks darker. Since concrete is not porous a thin layer of water sticks to the surface. At the water surface part of the light incident is reflected, and a large part is transmitted. The transmitted light is diffusively scattered, part of which goes through total internal reflection and only a small part reaches the eye, making the surface look darker.

   When a fabric is wet it looks darker because of a slightly different mechanism. The surface of the fabric gets coated with a thin layer of water (refractive index = 1.33) which is smaller than the refractive index of the fabric. When the cloth is wet more light is transmitted, and less gets reflected than before. The transmitted light penetrates the fabric and gets scattered, resulting in a darker appearance.
7. *Rainbows*. Water with a refractive index of 1.33 is a dispersive medium. White light consisting of different wavelengths travel at different speeds in the medium and emerge at different directions. If the dispersion is adequate, different spectral colors can be seen by the naked eye. The dew covered lawn on a sunny day displays the spectral colors. If you stand close to the dew drop without blocking the sun's radiation falling on the drop, at some angle one should see the spectral colors. The primary rainbow is produced by the water droplets in the atmosphere after rain. The radius of the primary rainbow is about 42° with a width of about 2°. The color of the primary rainbow would be blue to red from the center of the rainbow. A rainbow is observed at the antisolar point. The brightness of the rainbow depends on the ambient sunlight, the size of the droplets, and whether the sun is low or high in the sky. The secondary rainbow, which is fainter, is often seen outside the primary rainbow at about 51°. The secondary rainbow will have red to blue from the center of the secondary rainbow. The secondary rainbow is approximately half as bright as the primary rainbow. The secondary rainbow is caused by two total internal reflections within the droplet whereas the primary rainbow is the result of one total internal reflection only. Because of the total internal reflection process, light is about 95% tangentially polarized in the primary rainbow.
8. *Heiligenschein*. Heiligenschein or the 'holy light' can be seen around the shadow of your head on a lawn on a sunny morning when dew drops are present. Usually, the dew drops are held by the tiny hairs of the grass at some distance from the blade of the grass. As light falls on the droplet, the spherical drop converges light at its focus and if the grass blade is located at that point, the light gets retroreflected approximately towards the sun resulting in holy light around your shadow.
9. *Coronae*. Colored concentric patchy rings seen around the moon and the sun are called coronae. They are primarily produced by the water droplets in the thin clouds. Even though the water droplets are randomly located, the diffracted light from the droplets has a defined angle and the superposition of the diffraction patterns from different water droplets results in colored ring structures. Coronae can be easily seen around the full moon viewed through thin clouds.
10. *The Glory*. On a foggy day with the sun at your back, one may see bright colored rings in the form of arches of about 5° to 10° at the solar point. The light in the glory is polarized and the ring structure is produced by reflection of the solar radiation by the fog.
11. *Clouds*. Clouds contain suspended water droplets or ice crystals. The size of the droplets ranges from less than a micrometer to about 100 micrometers (10^{-6} m). When the air is supersaturated with water vapor, the water condenses into water droplets, resulting in a definite shape to the cloud. When the sun's radiation falls on

the cloud, the light is scattered by the water droplets. Even though one would expect that the scattered light may have some color distribution, since we look at the scattered light from a very large number of droplets, the summation of all the colors results in white. Some clouds look dark or gray because, either they are in the shadow of other clouds or they are so thick that most of the light is absorbed. During sunset and sunrise, the clouds look bright orange because of the colored light illuminating them. Even though all the clouds are basically white, they may appear colored because of the selective absorption of certain colors in the atmosphere or due to the colored background radiation. Often, you see a silver lining at the edges of a cloud, because at the edges the density of water is low and when the sun illuminates it from the back, the radiation is scattered in the forward direction quite efficiently, resulting in a bright and shiny 'silver lining' to the cloud.

12. *Lightning*. Lightning is caused by an intense electrical discharge due to the high potential differences developed. On a cloudy and rainy day, as the water droplets grow in size, the falling drops get distorted to ellipsoidal shape and get polarized. The top smaller portion becoming negative and the lower larger part becoming positive. As the deformation increases, the drop ultimately breaks and the smaller drops being negatively charged and the larger ones positively charged. The wind currents easily lift the buoyant small drops to higher altitudes and the heavier positively charged droplets fall towards the Earth. The final result is that the upper region of the cloud is negatively charged whereas the lower region of the cloud is positively charged. The portion of the Earth under the cloud becomes negatively charged due to induction. The localized ions in the positively charged cloud produce a strong electric field which is further augmented by the induced negative charges on the Earth below. The strong electric field ionizes the air molecules setting up a current discharge to the earth. This discharge is called stepped leader. Following the stepped leader, the charges in the upper region of the cloud also discharge resulting in what is called return stroke. The sequence of leader and return strokes occur typically about ten times in a second. Since the clouds are charged and they are closer to each other, lightening is more frequent between the oppositely charged clouds than cloud and Earth. It is estimated that the lightning between the clouds is about five times more frequent compared to the lightening events between a cloud and the Earth. In this process, the nitrogen and oxygen molecules in air are excited and ionized. The flash is produced by the de-excitation of these molecular species. Since the temperatures involved are quite high (30 000 K), the flash has a strong unsaturated bluish hue. Some hydrogen lines are also observed in the flash. Hydrogen is produced as a result of the dissociation of water molecules during the discharge process.
13. *Ice and Halos*. Snow reflects most of the light falling with a reflectivity of about 95%. Snowflakes are crystalline and have hexagonal structure. In nature they occur in assorted sizes and shapes. As white light falls on them, light may be simply reflected from their surfaces making them shining white, which are often called glints. The light may also pass through the crystalline material get dispersed and emerge with different colors, which are known as sparkles.

    The halos appear as thin rings around the sun or the moon. They are produced because of the minimum deviation of light in snow crystals. The 22° halo is most common and is often seen a number of times in a year. The halos are circular and have a faint reddish outer edge and a bluish white diffused spot at the center. They often look white because of the superposition of different colors resulting in a more or less white color.

Color in Art and Holography

Sources of Color

There are two major color sources, dyes and paint pigments. Dyes are usually dissolved in a solvent. The dye molecules have selective absorption resulting in selective transmission. Paint pigments are powdered and suspended in oil or acrylic. The paint particles reflect part of the radiation falling on them, selectively absorb part of the radiation and transmit the balance. Lakes are made of translucent materials such as tiny grains of alumina soaked in a dye of appropriate color.

In the case of water colors and printer's inks, part of the light incident is reflected from the surface and the remaining transmitted which is selectively absorbed by the dye. The transmitted light reflected by the paper, passes through the dye again and emerges. Each transmission produces color by subtractive color scheme and the emerging light is mixed partitively by the observer.

In the case of paints, the color depends on the size and concentration of the pigment particles and the medium in which they are suspended. Part of the light incident on the artwork gets reflected at the surface and the remaining selectively absorbed and transmitted which in turn is further reflected and transmitted by other pigment particles each time following a subtractive color scheme. The light reaching the canvas gets reflected and passes through the medium and emerges. Again, all the emerging beams are partitively mixed by the observer.

Holograms may be broadly categorized as transmission and reflection holograms. Both transmission and reflection (volume) holograms are prepared by producing the interference pattern of the reference and object laser beams. Transmission holograms can be viewed in the presence of the reference laser beam that was employed for its preparation. Spectacular three-dimensional colored images are reconstructed by the reflection holograms depending on the angle of incidence of the white light and the direction of observation. Embossed holograms are popular for advertising, security applications (credit cards), display, and banknotes. Some studios prepare three-dimensional holographic portraits that can be viewed in natural light. In the future, three-dimensional videos and even holographic three-dimensional movies may be a reality.

Structural Colors in Nature

Nanoscale Photonic Lattices

Newton observed that iridescence (change in color with the direction of observation) is caused by optical interference. The colors are produced by the interference or the light diffracting characteristics of the microstructures and not by the selective reflection or absorption of light, as in the case of pigments. Photonic band structures consist of periodic arrangement of dielectric materials even though they are transparent, have a bandgap resulting in inhibition of certain wavelengths. Light with frequencies in the gaps between the bands get reflected resulting in the specific color.

The structural colors of light can be seen in the animal world and minerals. For example, opal, a sedimentary gem does not have crystalline structure, but consists of tiny spheres of silica packed together. The diffraction of light through these structures results in spectacular colors determined by the size of the spheres and their periodicity. The spines of the sea mouse Aphrodite are covered with natural photonic structures that produce iridescence resulting in brilliant colors depending on the direction of the incident light and the direction of observation.

In the case of the butterfly, *Morpho rhetenor*, the metallic blue color is produced by the periodic structure of its wings. Its wings have layers of scales, each of about 200 mm long and 80 mm wide and about 1300 thin parallel structures per mm which form a diffraction grating.

The bird feathers viewed through an optical microscope show the structural components which are responsible for their coloration. The structural details of the peacock's eye pattern employing the scanning electron microscopy show photonic structures on peacock barbules. Barbules are the strap like branches on the peacock feathers. The four principal colors on the peacock feathers blue, green, yellow, and brown were identified wth the specific structures. The interference between the light reflected from the front surface to that reflected from the back was shown to be responsible for the brown color in the peacock's eye. The photonic structure of the green barbule has a periodic structure of melanin cylinders with a spacing of about 150 nm whereas the blue barbule has a periodic structure of 140 nm, and yellow barbules have a periodicity of 165 nm.

See also

Dispersion Management. **Holography, Techniques:** Color Holography. **Photon Picture of Light**. **Polarization:** Introduction. **Scattering:** Scattering Theory.

Further Reading

Blau SK (2004) Light as a feather: structural elements give peacock plumes their color. *Physics Today* 57: 18–21.

Color Science, http://www.physics.sfasu.edu/astro/color.html.

Colourware, Colour FAQ, http://www.colourware.co.uk/cpfaq.htm.

CVRL Color & Vision database, http://www.cvrl.org/.

Hecht E (2002) *Optics*, 4th edn. San Francisco, CA: Addison Wesley.

Lynch DK and Livingston W (2001) *Color and Light in Nature*, 2nd edn. Cambrige, UK: Cambridge University Press.

Minnaert MGJ (1993) *Light and Color in the Outdoors*. Heidelbergh: Springer-Verlag.

Nassau K (2000) *The Physics and Chemistry of Color*. New York: John Wiley and Sons.

Poynton CA, Color technology, http://www.Poynton.com/ColorFAQ.html.

Tayeb G, Gralak B and Enoch S (2003) Structural colors in nature and butterfly-wing modeling. *Optics and Photonics News* 14(2): 38–43.

Wyszecki G and Stiles WS (2000) *Color Science*. New York: John Wiley.

D

DETECTION

Contents

Fiber Sensors
Heterodyning
Image Post-Processing and Electronic Distribution
Smart Pixel Arrays

Fiber Sensors

M J Connelly, University of Limerick, Limerick, Ireland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The growth in the fiber optic communications and optoelectronics industries has led to the development and commercialization of many types of optical components. Fiber sensor devices and systems are a major user of such technologies. This has resulted in the development of commercial fiber sensors that can compete with conventional sensors. Fiber sensors are capable of measuring a wide variety of stimuli including: mechanical (displacement, velocity, acceleration, strain, pressure); temperature; electromagnetic (electric field, magnetic field, current); radiation (X-ray, nuclear); chemical composition; flow and turbulence in liquids; and biomedical. The main advantages of fiber sensors are that they are low cost, compact and lightweight, robust, passive, immune to electromagnetic interference, and highly sensitive.

Fiber sensors can be grouped into two basic classes: intrinsic and extrinsic. In an intrinsic fiber sensor the sensing is carried out by the optical fiber itself. In an extrinsic sensor the fiber is simply used to carry light to and from an external optical device where the sensing takes place. Point fiber sensors are localized to discrete regions; quasi-distributed sensors utilize point sensors at various locations along a fiber and distributed sensors are capable of sensing over the entire length of fiber.

A basic fiber sensor system, as shown in Figure 1, consists of a light source, fiber sensor, optical detector, and signal processing electronics. A measurand causes some change (intensity, phase, polarization, spectrum, etc.) in the light propagating through the sensor. This change is detected and processed to give an output signal proportional to the measurand. A large part of fiber sensor research concerns the development of fiber sensors sensitive to particular measurands and appropriate signal processing techniques. We describe some of the most important fiber sensors and also consider quasi-distributed and distributed sensing, including the use of multiplexing techniques.



Figure 1 Basic fiber sensor system.

Intensity-Based Fiber Sensors

The intensity modulation (IM) of light is a simple method for optical sensing. There are several mechanisms that can produce a measurand-induced change in the optical intensity propagated by an optical fiber. Perhaps the simplest type of IM fiber sensor is the microbend sensor shown in Figure 2. The sensor consists of two grooved plates between which passes an optical fiber. The upper plate can move in response to pressure. When the fiber is bent sufficiently, light escapes into the fiber cladding and is lost. The greater the pressure on the plates the more loss occurs.

Coupling-based fiber sensors are useful for measurement of displacement or dynamic pressure. Transmission and reflective configurations are possible as shown in Figure 3. The transmission coupling-based sensor consists of two fibers with a small gap between them. The amount of light coupled to the second fiber depends on the fiber acceptance angles and the distance between the fibers. One of the fibers can move in response to vibration or pressure thereby changing the distance between the fibers and hence the coupling loss. The reflection-based sensor operates in a similar fashion, where light is reflected from a flexible diaphragm back into a collecting fiber. The reflected light intensity changes as the diaphragm is flexed. Once the coupling relationship between the input fiber, diaphragm and collecting fiber is known, intensity changes can be related to the applied displacement or pressure.



Figure 2 Microbend fiber sensor. The transducer moves in response to pressure and in doing so changes the bending radius of the fiber and thereby the fiber loss.



Figure 3 (a) Transmission and (b) reflective coupling-based fiber sensors.



Figure 4 Evanescent wave fiber chemical sensor.

Evanescent wave fiber sensors exploit the fact that some of the energy in the guided mode of an optical fiber penetrates a short distance from the core into the cladding. The penetration of light energy into the cladding is called the evanescent wave. It is possible to design a sensor where energy is absorbed from the evanescent wave in the presence of certain chemicals as shown in Figure 4. This is achieved by stripping the cladding from a section of the fiber and using a light source having a wavelength that can be absorbed by the chemical that is to be detected. The resulting change in light intensity is a measure of the chemical concentration. Measurements can also be performed in a similar fashion by replacing the cladding with a material such as an organic dye whose optical properties can be changed by the chemical under investigation. Evanescent wave fiber sensors have found many applications in the biomedical field, such as blood component meters for detection of cholesterol and uric acid concentrations in blood.

A linear position sensor based on time division multiplexing is shown in Figure 5. It uses a square-wave modulated light source, optical delay loops and an encoded card. The delay loops separate the return signal from the encoded card by a time that is greater than the pulse duration. The encoded return signal can be decoded to determine the card position and velocity.

Interferometric Sensors

Interferometric fiber sensors operate on the principle of interference between two or more light beams to convert phase differences to intensity changes. Common configurations used include Michelson, Mach–Zehnder, and Sagnac interferometers, polarimetric systems, grating and etalon-based interferometers and ring resonators. Interferometric fiber sensors have extremely high sensitivity and are able to resolve path differences of the order of 10^{-6} of the light


Time delay loops
Encoded card
Light source
Star coupler
Coupler
Detector
Decoder
Position/velocity
Reflective patch

Figure 5 Linear position sensor using time division multiplexing.


Measurand (e.g., axial strain)
Laser diode
Single-mode fiber
Signal arm
Material under test
Mirrored ends
Detector
Reference arm
Coated fiber

Figure 6 Michelson interferometric strain sensor. Part of the signal arm is embedded in a material, such as concrete (in civil engineering structures) or carbon composite (used in the aerospace industry).

source wavelength. To realize high sensitivity, spectrally pure light sources such as semiconductor lasers must be used. In addition, single mode fibers and components are used to maintain the spatial coherence of the light beams. Factors that affect the performance of interferometric sensors include the optical source phase noise and the polarization states of the interfering light beams.

In two-beam interferometric sensors, such as the Michelson interferometric strain sensor shown in Figure 6, one of the light beams travels through a fiber where its phase can be modulated by the measurand. The two reflected beams recombine on a detector, the output of which is of the form $1 + V \cos \phi$ as shown in Figure 7. ϕ is the relative phase shift between the return beams and V the interferometer visibility. Compensating techniques must be used to ensure that the interferometer sensitivity is maximized. Active techniques involve the insertion of an active device, such as a fiber stretcher, in one of the interferometer arms to control the mean phase difference between the beams. Passive schemes have the advantage in that no active components are required, but usually involve complex signal processing schemes such as active homodyne or synthetic heterodyne demodulation. The sensitivity of the fiber to the measurand can be further improved through the use of specialized coatings.



Figure 7 Two-beam interferometer transfer function. The sensitivity is maximized when the mean phase difference between the detected light beams is an odd integer multiple of $\pi/2$. When this is the case the interferometer is said to be operating in quadrature.

Compact interferometric sensors can be constructed using intrinsic or extrinsic Fabry–Perot type configurations, the most common of which are shown in Figure 8. If the Fabry–Perot cavity reflectivities are $\ll 1$, then it can be considered to be a two-beam interferometer.

Polarimetric fiber sensors relate changes induced in the polarization state of light to the measurand.

These sensors usually use high birefringence (Hi-Bi) fiber. The phase difference between the two orthogonally polarized modes of Hi-Bi fiber is given by

$$\phi = \Delta\beta l \qquad [1]$$

where $\Delta\beta$ is the fiber (linear) birefringence and l the fiber length. Both $\Delta\beta$ and l can be changed by the measurand. A polarimetric strain sensor using Hi-Bi fiber embedded in carbon fiber composite, is shown in Figure 9. Light from a linearly polarized He–Ne laser is launched into the Hi-Bi fiber, through a half-waveplate and lens. The waveplate is used to rotate the light plane of polarization so that it is at 45° to the principal axes of the fiber. This ensures that half of the input light power is coupled to each of the fast and slow modes of the Hi-Bi fiber. The output light from the Hi-Bi fiber is passed through a polarization beamsplitter. The beamsplitter separates the light into two orthogonally polarized beams, which are then detected. The output from each of the detectors is given by $V_1 = I_0 \sin^2\phi$ and $V_2 = I_0 \cos^2\phi$, respectively, where I_0 is the input light intensity. The state of polarization (SOP) of the output light from the Hi-Bi fiber is given by

$$\text{SOP} = \frac{V_1 - V_2}{V_1 + V_2} = \cos^2\phi + \sin^2\phi \qquad [2]$$

It is a simple matter to calculate the SOP, from which ϕ can be determined. The form of eqn [2] is very similar to the two-beam interferometer transfer function, shown in Figure 7.

A polarimetric electric current sensor based on the Faraday effect is shown in Figure 10. The Faraday effect provides a rotation of the light's polarization state when a magnetic field is parallel to the optical path in glass. If an optical fiber is closed around a current-carrying conductor, the Faraday rotation is directly proportional to the current. By detecting the polarization rotation of light in the fiber, the current can be measured.

Linearly polarized light is equivalent to a combination of equal intensity right and left circularly polarized components. The linear state of polarization of the polarized laser light rotates in the presence of a magnetic field because the field produces


Fiber reflective splice
Reflective end
Light
(a)
Fiber reflective splices
Light
(b)
Intrinsic Fabry–Perot sensors
Single-mode fiber
Capillary tube
Bond or fusion weld
Light
Multimode fiber
(c)
Hollow core fiber section
Light
(d)
Extrinsic Fabry–Perot sensors

Figure 8 Interferometric fiber Fabry–Perot configurations.


Hi-Bi fiber embedded in carbon fiber composite
Polarization beamsplitter
HeNe laser
Detector
Half-wave plate
Detector
Signal processing

Figure 9 Polarimetric strain sensor system.



Figure 10 Polarimetric electric current sensor system.

circular birefringence in the fiber. This means that right and left circularly polarized light will travel at different speeds and accumulate a relative phase difference given by

$$\phi = VBl \qquad [3]$$

where V is the Verdet constant (rad Tesla^{-1} m^{-1}) of the glass, B the magnetic field flux density (Tesla), and l the length of the fiber exposed to the magnetic field. In the polarimetric current sensor, the polarization rotation is converted to an intensity change by the output polarizer. The output to the detector is proportional to $1 + \sin(2\phi)$, from which ϕ and the current can be determined.

The linear birefringence of conventional silica fiber is much greater than its circular birefringence. To make a practical current sensor, the linear birefringence must be removed from the fiber and this can be achieved by annealing the fiber. Annealing involves raising the temperature of the fiber, during manufacture, to a temperature above the strain point for a short period of time and slowly cooling back to room temperature. This reduces stresses in the glass, which are the principal cause of linear birefringence, and also cause physical and chemical changes to the glass. Waveguide-induced birefringence cannot be removed by annealing, but can be significantly reduced by twisting the fiber.

White light – or more accurately low-coherence – interferometry utilizes broadband sources such as LEDs and multimode lasers in interferometric measurements. Optical path differences (OPDs) are observed through changes in the interferometric fringe pattern. A processing interferometer is required in addition to the sensing interferometer to extract the fringe information.

The processing of white light interferometry signals relies on two principal techniques. The first technique involves scanning the OPD of the processing interferometer to determine regions of optical path balance. The second technique involves determination of the optical spectrum using an optical spectrum analyzer. The resulting fringe pattern fringe spacing is then related to the OPD of the sensing interferometer.

An example of the optical path scanning technique is shown in Figure 11a. The sensing interferometer is designed such that its OPD is much greater than the coherence length of the light source, so at its output no interference fringes are observed. The output of the sensing interferometer is fed to the processing interferometer. The OPD of the processing interferometer is scanned using a piezoelectric fiber stretcher driven by a suitable scanning voltage. As the processing interferometer is scanned, interference fringes are observed at two distinct points as shown in Figure 11b. The first set of fringes occurs when the OPD of the processing interferometer is within the coherence length of the optical source (close to zero). The second set of fringes occurs when the OPDs in the two interferometers are equal. The OPD in the sensing interferometer can be determined by measuring the OPD in the processing interferometer between the two positions of maximum visibility in the output signal from the detector. This, in turn, can be related to OPD changes due to the action of the measurand, in this case strain.

Sagnac interferometric sensors can be used to create highly sensitive gyroscopes that can be used to sense angular velocity (e.g., in aircraft navigation systems). It is based on the principle that the application of force (e.g., centrifugal force) will alter the wavelength of light as it travels around a coil of optical fiber. A basic open-loop fiber gyroscope is shown in Figure 12. The broadband source (e.g., superluminescent diode) is split into two counter propagating light beams traveling in the clockwise and anticlockwise directions. The polarizer is used to ensure the reciprocity of the counter propagating waves. The inherent nonlinear response of the gyroscope can be overcome by using a phase modulator and signal processing techniques. In the ideal case the detector output is proportional to $1 + \cos\phi_s$. The Sagnac phase shift ϕ_s between the two returning beams is given by

$$\phi_s = \frac{8\pi AN\Omega}{c\lambda_0} \qquad [4]$$

A is the area enclosed by a single loop of the fiber, N the number of turns, Ω the component of the angular velocity perpendicular to the plane of the loop, λ_0 the free-space wavelength of the optical source, and c the speed of light in a vacuum. Sensitivities greater than 10^{-8} rad/s and dynamic ranges in excess of 40 dB have been achieved with open-loop fiber gyroscopes. More advanced gyroscopes can greatly improve on this performance.

Fiber Grating Sensors

Many types of fiber gratings can be used in sensing applications including Bragg, long-period, and


Broadband source
Strain
Sensing interferometer
Mirrored end
Piezoelectric fiber stretcher
Processing interferometer
Signal processing
Detector
(a)
Fringes due to finite source coherence length
Path difference between positions of maximum visibility
Fringes due to OPD balance between the sensing and processing interferometers
Intensity
0
Optical path difference
(b)

Figure 11 Low-coherence interferometric sensor. (a) Schematic diagram. (b) Output of the scanned processing interferometer.


Broadband source
Fiber polarizer
Fiber coil
Angular speed (Ω)
Detector
Phase modulator
Signal processing
Angular velocity vector (perpendicular to the plane of the loop) with magnitude Ω
Output signal (proportional to Ω)

Figure 12 Basic open-loop fiber gyroscope.

chirped gratings. Because fiber gratings are small and have a narrow wavelength response, they can be used for both point and quasi-distributed sensing. They can be embedded in composite materials for smart structure monitoring and also in civil engineering structures such as bridges.

Fiber Bragg gratings (FBGs) are the most popular type of grating sensor. A typical FBG consists of a short section (typically a few mm) of single-mode fiber with a periodic modulation (typically 100s of nm) of the core refractive index. The index modulation causes light in the forward propagating core mode to be coupled into the backward core mode. This causes the FBG to act as a highly wavelength-selective rejection filter. The wavelength of peak reflectivity is the Bragg wavelength $\lambda_B = 2n_{\mathrm{eff}}\Lambda$, where n_{eff} is the effective refractive index of the guided mode in the fiber and Λ the index modulation period. Both n_{eff} and Λ can be changed by an external measurand, resulting in a shift in λ_B.

The basic principle of FBG sensors is the measurement of an induced shift in the wavelength of an optical source due to a measurand, such as strain or temperature. A basic reflective FBG sensor system is shown in Figure 13. A broadband light source is used to interrogate the grating, from which a narrowband slice is reflected. The peak wavelength of the reflected spectrum can be compared to λ_B, from which strain or temperature can be inferred. The shift in the Bragg wavelength $\Delta\lambda_B$ with applied microstrain $\Delta(\mu\varepsilon)$ and change in temperature ΔT, for silica fiber is given approximately by

$$\frac{\Delta\lambda_B}{\lambda_B} \approx 0.78\times10^{-6}\Delta(\mu\varepsilon) + 6.67\times10^{-6}\Delta T \qquad [5]$$



Figure 13 Basic reflective FBG sensor system.

A wavelength resolution of ~1 pm is required (at 1.3 μm) to resolve a temperature change of 0.1 °C or a strain change of 1 $\mu\varepsilon$. The response of the grating to strain can be improved through the use of specialized coatings. Polyimide coatings are commonly used as an efficient strain transducer for gratings embedded in composite materials. Because thermal effects in materials are usually very slow, it is relatively easy to measure dynamic strain (>1 Hz). However, in structural monitoring it can be necessary to distinguish between wavelength shifts due to static strain and those due to temperature. One technique is to use two collocated gratings whose response to strain and temperature is significantly different. In addition to strain and temperature measurement, grating sensors have also been used to measure flow, vibration, electromagnetic fields and chemical effects.

An example of quasi-distributed strain sensing, using a wavelength division multiplexed array of FBGs, is shown in Figure 14. Each FBG in the array has a unique Bragg wavelength. The return light from the FBG array is passed through a tunable narrowband Fabry–Perot filter. As the filter is tuned, the wavelengths returned by the individual FBGs can be analyzed and the strain present at each grating determined.

FBGs can be used as narrowband reflectors for creating fiber laser sensors, capable of measuring temperature, static strain, and very high-resolution dynamic strain. The basic form of an FBG laser sensor system shown in Figure 15 consists of a doped fiber section between two identical FBGs. The doped fiber is optically pumped to provide gain and thereby enable lasing to occur. Single-mode or multi-mode lasing is possible depending on the cavity length. In single-mode operation the FBG laser linewidth can be much smaller than the linewidth of diode lasers. This means that FBG laser sensors have greater sensitivities compared to passive FBG sensors.



Figure 14 Quasi-distributed strain sensing using a wavelength division multiplexed array of FBGs.

When the cavity is subject to weak dynamic strain, the laser output is frequency modulated. This frequency modulation can be detected by using interferometric techniques. The main advantage of the FBG laser sensor over direct interferometry is that it is possible to obtain comparable strain sensitivities using a much shorter length of fiber.

Long-period fiber gratings (LPFGs) are attracting much interest for use in sensing applications. They are more sensitive to measurands than FBGs and easier to manufacture. A typical LPFG has a length of tens of mm with a grating period of 100s of μm. Its operation is different to an FBG in that coupling occurs between the forward propagating core mode and co-propagating cladding modes. The high attenuation of the cladding modes results in a series of minima occurring in the transmission spectrum of the fiber. This means that the spectral response is strongly influenced by the optical properties of the cladding and surrounding medium. This can be exploited for chemical sensing as shown in Figure 16, where a broadband source is used to interrogate an LPFG. The wavelength shifts of the output spectrum minima can be used to determine the concentration of particular chemicals in the substance surrounding the grating. The longest wavelength attenuation bands are the most sensitive to the refractive index of the substance surrounding the grating. This is because higher order cladding modes extend a greater distance into the external medium. LPFGs can also be used as strain, temperature, refractive index, bend, and load sensors.

Fiber Laser Doppler Velocimeter

Laser Doppler velocimetry (LDV) is a technique used for measuring velocity, especially of fluid flows. A fiber LDV system and associated scattering geometry is shown in Figure 17. In LDV two coherent laser beams intersect in a small measurement volume where they can interfere. The light reflected by a seed particle passing through the measurement volume is modulated at a frequency proportional to the spatial frequency (Doppler difference frequency Δf) of the interference fringes and the component of its velocity



Figure 15 FBG laser sensor with interferometric detection.



Figure 16 Detail of LPFG sensor.

normal to the interference fringes. Δf is given by

$$\Delta f = \frac{2nV\cos\beta}{\lambda_0}\sin(\theta/2) \qquad [6]$$

where n is the fluid refractive index, V the particle velocity and λ_0 the laser free-space wavelength. The output of the detector is processed to extract Δf and therefore $V\cos\beta$. Δf is independent of the scattered light direction so collection of the scattered light using a lens increases the system sensitivity. The form of eqn [6] indicates that the direction of flow cannot be ascertained. The simplest technique to resolve this ambiguity is to apply a frequency shift Δf_s to one of the input beams. This can be achieved by the use of a piezoelectric frequency shifter. The frequency shift causes a phase shift to appear between the two beams. The phase shift increases linearly with time. This results in a fringe pattern of spacing s, which moves with constant velocity $V_f = s\Delta f_s$. In this case the measured Δf will be less than or greater than Δf_s, depending on whether the particle is moving with or against the fringe motion. There will then be an unambiguous detectable range of velocities from zero to V_f.

Luminescence-Based Fiber Sensors

Luminescence-based fiber sensors are usually based on fluorescence or amplified spontaneous emission occurring in rare earth materials. They can be used in many applications such as chemical, humidity, and temperature sensing. It is possible to connect a fiber to luminescent material or to introduce luminescent dopants into the fiber. An example of the latter, used to detect chemical concentration is shown in Figure 18. A laser pulse causes the doped section of the fiber to luminesce at a longer wavelength than the


PZT frequency shifter
Measurement volume
Fluid flow seeded with small particles
Lens
Laser
Detector
Lens
Scattered light from seed particle
Signal processing
β
Velocity vector
θ/2
Incoming laser beams
θ/2
Detection point
Scattered light
Seed particle

Figure 17 Fiber Doppler velocimeter and scattering geometry.


Pulsed laser
Doped fiber probe
Luminescence intensity
t
Detector
Vessel
Chemical (e.g., gas)
Signal processing for determine luminescence lifetime
Signal proportional to chemical concentration

Figure 18 Chemical sensor based on fluorescence in doped optical fiber.


Pulsed laser
Multimode fiber
Heat source
Signal processing
Detector
Backscattered signal
Stokes line (temperature independent)
Laser frequency (Rayleigh backscatter)
Anti-Stokes line (temperature dependent)
Increasing frequency

Figure 19 Anti-Stokes Raman thermometry system.

laser. The luminescence intensity *I(t)* at the detector has an exponential decay profile given by

$$I(t) = I_0 \exp\big(-(k_1 + k_2 C)t\big) \qquad [7]$$

where I_0 is the initial luminescence intensity, t time, k_1, k_2 constants, and C the chemical concentration. The luminescence time constant $1/(k_1 + k_2 C)$ can be determined by comparing the luminescence intensity at various times after excitation by the laser pulse, from which C can be determined. The use of time division multiplexing allows quasi-distributed measurement of chemical concentration. The use of plastic optical fiber for luminescence-based sensors is attracting much interest.

Distributed Fiber Sensing

We have seen that both point and quasi-distributed sensing are possible using fiber sensors. Distributed sensing can be achieved through the use of linear or nonlinear backscattering or forward scattering techniques. In linear backscattering systems, light backscattered from a pulse propagating in an optical fiber is time resolved and analyzed to obtain the spatial distribution of the measurand field, e.g., polarization optical time domain reflectometry analyzes the polarization state of backscattered light to determine the spatial distribution of electromagnetic fields. Nonlinear backscattering schemes use effects such as Raman or Brillouin scattering. An important example of the former is the anti-Stokes Raman thermometry system shown in Figure 19. A light pulse is transmitted down the sensing fiber. Spontaneous Raman scattering causes Stokes and anti-Stokes photons to be generated along the fiber. Some of these photons travel back along the fiber to a fast detector. The intensity of the Stokes line is temperature independent. The anti-Stokes line intensity is a function of temperature. The ratio of the two intensities provides a very accurate measurement of temperature. The measurement location is determined by timing of the laser pulse.

See also

Environmental Measurements: Laser Detection of Atmospheric Gases. **Fiber Gratings**. **Interferometry:** Overview; Phase Measurement Interferometry; White Light Interferometry. **Optical Materials:** Smart Optical Materials.

Further Reading

Culshaw B and Dakin JP (1988, 1989, 1997) *Optical Fiber Sensors*, vols. I, II, III. Norwood, MA: Artech House.

Grattan KTV and Meggitt BT (1994, 1997, 1999, 1999) *Optical Fiber Sensor Technology*, vols. I, II, III and IV. Boston, CA: Kluwer Academic.

Grattan KTV and Meggitt BT (2000) *Optical Fiber Sensor Technology*. Boston, MA: Kluwer Academic.

Kersey AD, Davis MA, Patrick HJ, *et al.* (1997) Fiber grating sensors. *Journal of Lightwave Technology* 15: 1442–1463.

Krohn DA (1999) *Fiber Optic Sensors: Fundamentals and Applications*, 3rd edn. Research Triangle Park, NC: Instrumentation Society of America.

Lopez-Higuera JM (2001) *Handbook of Optical Fiber Sensing Technology*. New York: Wiley.

Othonos A and Kalli K (1999) *Fiber Bragg Gratings: Fundamentals and Applications in Telecommunications and Sensing*. Norwood, MA: Artech House.

Udd E (1991) *Fiber Optic Sensors: An Introduction for Engineers and Scientists*. New York: Wiley.

Udd E (1995) *Fiber Optic Smart Structures*. New York: Wiley.

Yu FTS and Yin S (2002) *Fiber Optic Sensors*. New York: Marcel Dekker.

Heterodyning

T-C Poon, Virginia Polytechnic Institute and State University, Blacksburg, VA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Heterodyning, also known as frequency mixing, is a frequency translation process. Heterodyning has its root in radio engineering. The principle of heterodyning was discovered in the late 1910s by radio engineers experimenting with radio vacuum tubes. Russian cellist and electronic engineer Leon Theremin invented the so-called Thereminvox, which was one of the earliest electronic musical instruments that generates an audio signal by combining two different radio signals. American electrical engineer Edwin Armstrong invented the so-called super-heterodyne receiver. The receiver shifts the spectrum of the modulated signal, that is, the frequency contents of the modulated signal, so as to demodulate the audio information from it. Commercial amplitude modulation (AM) broadcast receivers nowadays are super-heterodyne type. After illustrating the basic principle of heterodyning by some simple mathematics, we will discuss some examples on how the principle of heterodyning is used in radio and in optics.

For a simple case, when signals of two different frequencies are heterodyned or mixed, the resulting signal produces two new frequencies, the sum and difference of the two original frequencies. Figure 1 illustrates how signals of two frequencies are mixed or heterodyned to produce two new frequencies, $\omega_1 + \omega_2$ and $\omega_1 - \omega_2$, by simply multiplying the two signals $\cos(\omega_1 t + \theta_1)$ and $\cos(\omega_2 t)$, where ω_1 and ω_2 are radian frequencies of the two signals and θ_1 is the phase angle between the two signals. Note that when the frequencies of the two signals to be heterodyned are the same, i.e., $\omega_1 = \omega_2$, the phase information of $\cos(\omega_1 t + \theta_1)$ can be extracted to get $\cos\theta_1$ if we use an electronic lowpass filter (LPF) to filter out the term $\cos(2\omega_1 t + \theta_1)$. This is shown in Figure 2. Heterodyning is often referred to as homodyning for the mixing of two signals of the same frequency.

For a general case of heterodyning, we can have a signal represented by $s(t)$ with its spectrum $S(\omega)$, which is given by the Fourier transform of $s(t)$, and when it is multiplied by $\cos(\omega_2 t)$, the resulting spectrum is frequency-shifted to new locations in the frequency domain as:

$$\mathcal{F}\{s(t)\cos(\omega_2 t)\} = \frac{1}{2}S(\omega - \omega_2) + \frac{1}{2}S(\omega + \omega_2) \quad [1]$$

where $\mathcal{F}\{s(t)\} = S(\omega)$ and $\mathcal{F}\{\cdot\}$ denotes the Fourier transform of the quantity being bracketed. The spectrum of $s(t)\cos(\omega_2 t)$, along with the spectrum of $s(t)$, is illustrated in Figure 3. It is clear that multiplying $s(t)$ with $\cos(\omega_2 t)$ is a process of heterodyning, as we have translated the spectrum of the signal $s(t)$. This process is known as modulation in communication systems.

In order to appreciate the process of heterodyning let us now consider, for example, heterodyning in radio. In particular, we consider AM. While the frequency content of an audio signal (from 0 to around 3.5 kHz) is suitable to be transmitted over a pair of wires or coaxial cables, it is, however, difficult to be transmitted in air. By impressing the audio information onto a higher frequency, say 550 kHz, as one of the broadcast bands in AM radio, i.e., by


$\cos(\omega_1 t + \theta_1)$
$\frac{1}{2}\cos[(\omega_1 - \omega_2)t + \theta_1] + \frac{1}{2}\cos[(\omega_1 + \omega_2)t + \theta_1]$
$\cos(\omega_2 t)$

Figure 1 Heterodyning of two sinusoidal signals.


$\cos(\omega_1 t + \theta_1)$
LPF
$\frac{1}{2}\cos\theta_1$
$\cos(\omega_1 t)$
$\frac{1}{2}\cos\theta_1 + \frac{1}{2}\cos(2\omega_1 t + \theta_1)$

Figure 2 Heterodyning becomes homodyning when the two frequencies to be mixed are the same: homodyning allows the extraction of the phase information of the signal.



Figure 3 Spectrum of $s(t)$ and $s(t)\cos(\omega_2 t)$. It is clear that spectrum of $s(t)$ has been translated to new locations upon multiplying a sinusoidal signal.



Figure 4 Radio link: heterodyning in the demodulation stage is often known as heterodyne detection.

modulating the audio signal, the resulting modulated signal can now be transmitted using antennas of reasonable dimensions. In order to recover (demodulate) the audio signal from the modulated signal, the modulated signal is first received by an antenna in a radio receiver, multiplied by the so-called local oscillator with the same frequency as the signal used to modulate the audio signal, then followed by a lowpass filter to eventually obtain the audio information back. The situation is illustrated in Figure 4. We shall now describe the process mathematically with reference to Figure 4.

We denote $s(t)$ as the audio signal. After multiplying by $\cos(\omega_c t)$, which is usually called a carrier in radio in the modulation stage, where ω_c is the radian frequency of the carrier. The modulated signal $s(t)\cos(\omega_c t)$. is transmitted via an antenna. When the modulated signal is received in the demodulation stage, the modulated signal is then multiplied by the local oscillator of signal waveform $\cos(\omega_c t)$. The output of the multiplier is given by

$$s(t)\cos(\omega_c t)\cos(\omega_c t) = s(t)\tfrac{1}{2}[1 + \cos(2\omega_c t)] \qquad [2]$$

Note that the two signals in the demodulation stage, $s(t)\cos(\omega_c t)$ and $\cos(\omega_c t)$, are heterodyned to produce two new frequencies, the sum $\omega_c + \omega_c = 2\omega_c$ to give the term $\cos(2\omega_c t)$ and the difference $\omega_c - \omega_c = 0$ to give the term $\cos(0) = 1$. Since the two frequencies to be multiplied in the demodulation stage are the same, this is homodyning as explained above. Now by performing lowpass filtering (LPF), we can recover our original audio information $s(t)$. Note that if the frequency of the local oscillator in the demodulation stage within the receiver is higher than the frequency of the carrier used in the modulation stage, heterodyning in the receiver is referred to as superheterodyning, which most receivers nowadays use for amplitude modulation. In general, we have two heterodyning processes in the radio system just described, one in the modulation stage and the other in the demodulation stage. However, it is unusual to speak of heterodyning in the modulation stage, and so we just refer to the process in the demodulation stage as ‘heterodyne detection.’

In summary, heterodyne detection can extract the information from a modulated signal and can also extract the phase information of a signal if homodyning is used. We shall see, in the next section, how optical heterodyne detection is employed.

Optical information is usually carried by coherent light such as a laser. Let $\psi_p(x, y)$ be a complex amplitude of the light field, which may physically represent a component of the electric field. We further assume that the light field is oscillating at temporal frequency ω_0. Therefore, we can write the light field as $\psi_p \exp(i\omega_0 t)$. By taking the real part of $\psi_p \exp(i\omega_0 t)$, i.e., $\mathrm{Re}[\psi_p \exp(i\omega_0 t)]$, we recover the usual physical real quantity. For a simple example, if we let $\psi_p = A\exp(-ik_0 z)$, where A is some constant and k_0 is the wavenumber of the light, $\mathrm{Re}[\psi_p \exp(i\omega_0 t)] = \mathrm{Re}[A\exp(-ik_0 z)\exp(i\omega_0 t)] = A\cos(\omega_0 t - k_0 z)$, which is a plane wave propagating along the positive z direction in free space. To detect light energy, we use a photodetector (PD), as shown in Figure 5. Assuming a plane wave for simplicity, as $\psi_p = A$, we have also taken $z = 0$ at the surface of the photodetector. As the photodetector responds to intensity, i.e., $|\psi_p|^2$, which gives the current, i, as output by spatially integrating the intensity:

$$i \propto \int_S |\psi_p \exp(i\omega_0 t)|^2 \mathrm{d}x\mathrm{d}y = A^2 S \qquad [3]$$

where S is the surface area of the photodetector. We can see that the photodetector current is proportional to the intensity, A^2, of the incident light. Hence the output current varies according to the intensity of the



Figure 5 Optical direction detection or optical incoherent detection.

optical signal intensity. This mode of photodetection is called direct detection or incoherent detection in optics.

Let us now consider the heterodyning of two plane waves on the surface of the photodetector. We assume an information-carrying plane wave, also called the signal plane wave, $A_s \exp\{i[(\omega_0 + \omega_s)t + s(t)] \times \exp(-ik_0 x \sin\phi)\}$, and a reference plane wave, $A_r \exp(i\omega_0 t)$, or called a local oscillator in radio. The situation is shown in Figure 6.

Note that the frequency of the signal plane wave is ω_s higher than that of the reference signal, and it is inclined at an angle ϕ with respect to the reference plane wave, which is normal incident to the photodetector. Also, the information content $s(t)$ is in the phase of the signal wave. In the situation shown in Figure 6, we see that the two plane waves are interfered on the surface of the photodetector, giving the total light field ψ_t, given by

$$\psi_t = A_r \exp(i\omega_0 t) + A_s \exp\{i[(\omega_0 + \omega_s)t + s(t)]\} \times \exp(-ik_0 x \sin\phi) \qquad [4]$$

Again, the photodetector responds to intensity, giving the current

$$\begin{aligned} i &\propto \int_S |\psi_t|^2 \mathrm{d}x\mathrm{d}y \\ &= \int_{-a}^{a}\int_{-a}^{a} [A_r^2 + A_s^2 + 2A_r A_s \cos(\omega_s t + s(t) \\ &\quad - k_0 x \sin\phi)]\mathrm{d}x\mathrm{d}y \end{aligned} \qquad [5]$$

where we have assumed that the photodetector has a $2a \times 2a$ square area. The current can be evaluated to be:

$$i(t) \propto 2a(A_r^2 + A_s^2) + 4A_r A_s \frac{\sin(k_0 a \sin\phi)}{k_0 \sin\phi}\cos(\omega_s t + s(t)) \qquad [6]$$

The current output has two parts: the DC current and the AC current. The AC current at frequency ω_s is commonly known as the heterodyne current.



Figure 6 Optical heterodyne detection.

Note that the information content $s(t)$ originally embedded in the phase of the signal plane wave has now been preserved and transferred to the phase of the heterodyne current. The above process is called optical heterodyning. In optical communications, it is often referred to as optical coherent detection. In contrast, if the reference plane wave has not been used for the detection, we have the incoherent detection. The information content carried by the signal plane wave would be lost, as it is evident that for $A_r = 0$, the above equation gives only a DC current at a value proportional to the intensity of the plane wave, A_s^2.

Let us now consider some of the practical issues encountered in coherent detection. Again, the AC part of the current given by the above equation is the heterodyne current $i_{het}(t)$, given by

$$i_{het}(t) \propto A_r A_s \frac{\sin(k_0 a \sin\phi)}{k_0 \sin\phi}\cos(\omega_s t + s(t)) \qquad [7]$$

We see that since the two plane waves propagate in slightly different directions, the heterodyne current output is degraded by a factor of

$$\frac{\sin(k_0 a \sin\phi)}{k_0 \sin\phi} = a\mathrm{sinc}(k_0 a \sin\phi)$$

where $\mathrm{sinc}(x) = \sin(x)/x$. For small angles, i.e., $\sin\phi \approx \phi$, the current amplitude falls off as $\mathrm{sinc}(k_0 a\phi)$. Hence, the heterodyne current is at a maximum when the angular separation between the signal plane wave and the reference plane wave is zero, i.e., the two plane waves are propagating exactly in the same direction. The current will go to zero when $k_0 a\phi = \pi$, or $\phi = \lambda_0/2a$, where λ_0 is the wavelength of the laser light. To see how critical it is for the angle ϕ to be aligned in order to have any heterodyne output, we assume the size of the photodetector $2a = 1$ cm and the laser used is red, i.e., $\lambda_0 \approx 0.6$ μm; ϕ is calculated to be about 2.3×10^{-3} degrees. Hence to be able to work with coherent detection, we need to have precise optomechanical mounts for angular rotation.

Finally we describe a famous application of heterodyning in optics – holography. As we have seen, the mixing of two light fields with different temporal frequencies will produce heterodyne current at the output of the photodetector. But we can record the two spatial light fields of the same temporal frequency with photographic films instead of using electrical devices. Photographic films respond to light intensity as well. We discuss holographic recording of a point source object as a simple example. Figure 7 shows a collimated laser split into two plane waves and recombined by the use of two mirrors (M) and two beamsplitters (BS). One plane wave is used to illuminate the pinhole aperture (our point source object), and the other



Figure 7 Holographic recording of a point source object.

illuminates the recording film directly. The plane wave that is scattered by the point source object, which is located z_0 away from the film, generates a diverging spherical wave. This diverging wave is known as an object wave in holography. The object wave arising from the point source object on the film is given by, according to Fresnel diffraction:

$$\psi_0 = A_0 \exp(-ik_0z_0)\ \frac{ik_0}{2\pi z_0} \times \exp[-ik_0(x^2+y)^2/2z_0]\exp(i\omega_0 t) \qquad [8]$$

This object wave is a spherical wave, where A_0 is the amplitude of the spherical wave.

The plane wave that directly illuminates the photographic plate is known as a reference wave, ψ_r. For the reference plane wave, we assume that the plane wave has the same phase with the point source object at a distance z_0 away from the film. Its field distribution on the film is, therefore, $\psi_r = A_r \exp(-ik_0z_0)\exp(i\omega_0 t)$, where A_r is the amplitude of the plane wave. The film now records the interference of the reference wave and the object wave, i.e., what is recorded on the film as a 2D pattern is given by $t(x,y) \propto |\psi_r + \psi_0|^2$. The resulting recorded 2D pattern, $t(x,y)$, is called the hologram of the object. This kind of recording is known as holographic recording, distinct from a photographic recording in which the reference wave does not exist and hence only the object wave is recorded. Now:

$$\begin{aligned} t(x,y) &\propto |\psi_r + \psi_0|^2 \\ &= \Big|A_r \exp(-ik_0z_0)\exp(i\omega_0 t) + A_0\exp(-ik_0z_0) \\ &\quad \times \frac{ik_0}{2\pi z_0}\exp[-ik_0(x^2+y)^2/2z_0]\exp(i\omega_0 t)\Big|^2 \\ &= A + B\sin\left\{\frac{k_0}{2z_0}[(x^2+y)^2/2z_0]\right\} \end{aligned} \qquad [9]$$

where A and B are some inessential constants. Note that the result of recording two spatial light fields of the same temporal frequency preserves the phase information (noticeably the depth parameter z_0) of the object wave. This is considered optical homodyning as it is clear from the result shown in Figure 2.

The intensity distribution being recorded on the film, upon being developed, will have transmittance given by the above equation. This expression is called the Fresnel zone plate, which is the hologram of a point source object and we shall call it the point-object hologram. Figure 8 shows the hologram for a particular value of z_0 and k_0. The importance of this phase-preserving recording is that when we illuminate the hologram with a plane wave, called the reconstruction wave, a point object is reconstructed at the same location of the original point source object if we look towards the hologram as shown in Figure 9, that is the point source is reconstructed at a distance z_0 from the hologram as if it were at the same distance away from the recording film. For an arbitrary 3D object, we can imagine the object as a collection of points, and therefore, we can see that we have a collection of Fresnel zone plates on the hologram. Upon reconstruction, such as the illumination of the hologram by a plane wave, the observer would see a 3D virtual object behind a hologram.



Figure 8 Point-object hologram.

As a final example, we discuss a state-of-the-art holographic recording technique called optical scanning holography, which employs the use of optical heterodyning and electronic homodyning to achieve real-time holographic recording without the use of films. We will take the holographic recording of a point object as an example. Suppose we superimpose a plane wave and a spherical wave of different temporal frequencies and use the resulting intensity pattern as an optical scanning beam to raster scan a point object located z_0 away from the point source that generates the spherical wave. The situation is shown in Figure 10. Point C is the point source that generates the spherical wave (shown with dashed lines) on the pinhole object, our point object. This point source, for example, can be generated by a focusing lens. The solid parallel rays represent the plane wave. The interference of the two waves generates a Fresnel zone plate type pattern on the pinhole object:

$$\begin{aligned} &I_s(x, y;\ z_0, t) \\ &= \left| A_r \exp(-ik_0 z_0) \exp(i\omega_0 t) + A_0 \exp(-ik_0 z_0) \frac{ik_0}{2\pi z_0} \right. \\ &\quad \left. \times \exp[-ik_0(x^2 + y)^2/2z_0] \exp[i(\omega_0 + \Omega)t] \right|^2 \\ &= 1 + \left(\frac{1}{\lambda_0 z_0} \right)^2 + \frac{1}{\lambda_0 z_0} \sin\left[\frac{\pi}{\lambda_0 z_0}(x^2 + y^2) - \Omega t \right] \end{aligned} \quad [10]$$

assuming $A_r = A_0 = 1$ for simplicity. Note that the plane wave is at temporal frequency ω_0, and the spherical wave is at temporal frequency $\omega_0 + \Omega$. The expression $I_s(x, y;\ z_0, t)$ is a temporally modulated Fresnel zone plate and is known as the time-dependent Fresnel zone plate (TDFZP). If we freeze time, say at $t = t_0$, we have the Fresnel zone plate pattern on the pinhole object as shown in Figure 10. However, if we let the time run in the above expression, physically we will have running zones that would be moving away from the center of the pattern. These running zones are the result of optical heterodyning of the plane wave and the spherical wave of different temporal frequencies. It is this TDFZP that is used to raster scan a 3D object to obtain holographic information of the scanned object and such technique is called optical scanning holography.

Upon scanning by the TDFZP, the photodetector, captures all the transmitted light and delivers a current, which consists of a heterodyne current at



Figure 9 Reconstruction of a point-object hologram.



Figure 10 Optical scanning holography (use of optical heterodyning and electronic homodyning to record holographic information upon scanning the object in two dimensions).

frequency Ω. After electronic bandpass filtering (BPF) at Ω, the heterodyne current is homodyned electronically by cos(Ωt) and lowpass filtered (LPF) to extract the phase information of the current. When this final scanned and processed current is display in a 2D display, as shown in Figure 10, we have the Fresnel zone plate, which is the hologram of the pinhole object, on the display. We can photograph this 2D display to obtain a transparency and have it illuminated by a plane wave to have the reconstruction as shown in Figure 9, or, since the hologram is now in electronic form, we can store it in a PC and reconstruct it digitally. When holographic reconstruction is performed digitally, we have so-called digital holography.

See also

Diffraction: Fresnel Diffraction. **Holography, Techniques:** Digital Holography.

Further Reading

Banerjee PP and Poon TC (1991) *Principles of Applied Optics*. MA: Irwin.
Palais JC (1988) *Fiber Optic Communications*. New Jersey: Prentice-Hall.
Poon TC and Banerjee PP (2001) *Contemporary Optical Image Processing with MATLAB*. Oxford: Elsevier.
Poon TC and Qi Y (2003) Novel real-time joint-transform correlation using acousto-optic heterodyning. *Applied Optics* 42: 4663–4669.
Poon TC, Wu MH, Shinoda K and Suzuki Y (1996) Optical scanning holography. *Proc. IEEE* 84: 753–764.
Pratt WK (1969) *Laser Communication Systems*. New York: Wiley.
Stremler FG (1990) *Introduction to Communication Systems*. MA: Addison-Wesley.
VanderLugt A (1992) *Optical Signal Processing*. New York: Wiley.

Image Post-Processing and Electronic Distribution

K M Iftekharuddin, The University of Memphis, Memphis, TN, USA

F Ahmed, The Catholic University of America, Washington, DC, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The spectacular development of imaging sensors, communication, and internet infrastructure has immensely facilitated the creation, processing, and distribution of electronic digital images. One nontrivial aspect of the digital image is its complete application dependence. The image may be created using a number of different acquisition methods and sensors. It is then processed in different ways, depending upon myriad of digital imaging applications. Consequently, the effectiveness of a useful electronic image processing engine may involve development of robust pre-processing techniques, different types of goal-directed processing such as detection, recognition, identification, classification, tracking, reconstruction and/or registration, as well as post-processing algorithms for different application areas such as multimedia, biomedical, astronomical, defense, consumer, industrial, etc. A notional schematic of this electronic image processing cycle is shown in Figure 1. Note that while the goal-directed techniques may be different, based on problems at hand, the pre- and post-processing techniques and tools are very similar. Thus, most of the common image pre-processing techniques are also applicable for image post-processing purposes.

Electronic image post-processing techniques involve three broad domains such as: (i) spatial; (ii) frequency; and (iii) time-frequency. Each of these domain techniques may be grouped into different types of processing such as: (i) spatial domain technique to include filtering, spatial processing such as histogram modification, morphological processing, texture processing, etc.; (ii) frequency domain technique to include filter; and (iii) time-frequency domain technique to include short-time Fourier transform, wavelet, and Wigner-ville transforms.

On the other hand, it is useful to identify the typical lifecycle of a digital image from the distribution perspective as shown in Figure 2. The image may be created using a number of different acquisition methods and sensors as mentioned above. The processing block next combines all different types of processing, as mentioned in Figure 1. The image may then be transmitted over the internet or it can leave the digital world to go to the print world. It may then go through wear/tear, subsequently being scanned back to digital domain again. After some processing, it may again be distributed over the internet.

Consequently, the image may be copied legally or fraudulently, processed, and used by a user. Further, the threats and vulnerabilities of the internet have also increased proportionately. The rapid development and availability of high-end computers, printers, and scanners has made the tools of counterfeiting easily accessible and more affordable. With these products, one may counterfeit digital images, which are easy to distribute and modify. As a result, copyright ownership poses a formidable challenge to image post-processing and distribution.

In the subsequent sections, we briefly review relevant background in image post-processing and distribution techniques. We also present a few representative application examples of image post-processing and copyright protection in image distribution.


Electronic image acquisition
Pre-processing
– Spatial
– Frequency
– Time-frequency
Goal-directed processing
– Detection
– Recognition
– Tracking
– Consumer, etc.
Post-processing
– Spatial
– Frequency
– Time-frequency
Target applications
– Biomedical
– Defense
– Industrial
– Aerospace, etc.

Figure 1 Notional schematic of electronic image processing.


Acquisition
Process
Print
Wear/tear
Scan
Process
Internet distribution
Digital copy
Process

Figure 2 Typical lifecycle of a digital image distribution cycle.

Techniques in Image Post-Processing

Image Formation

We begin by describing the image formation technique briefly. Consider that a three-dimensional (3D) object or scene is imaged onto a 2D imaging plane by means of a recording system such as a camera. If the image formation process is linear, the recorded image may be modeled as the output of the system shown in Figure 3, which is given mathematically by

$$g(x,y) = s\left\{\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} h(x,y;s,t)f(s,t)\mathrm{d}s\,\mathrm{d}t\right\} + n(x,y) \quad [1]$$

where $g(x,y)$ denotes the recorded output image, and $f(x,y)$ is the ideal electronic image. The function $h(x,y;s,t)$ is the 2D impulse response or the point-spread function (PSF) of the image formation system. The PSF determines the radiant energy distribution in the image plane due to a point source located in the object plane. Usually the PSF is normalized such that

$$\left\{\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} h(x,y;s,t)\mathrm{d}s\,\mathrm{d}t\right\} = 1 \quad [2]$$

The noise contribution $n(x,y)$ is shown as an additive random process that is statistically uncorrelated with the image. This is a simplification because noises such as film-grain noise and the noise caused by photon statistics, which often corrupt images, are not uncorrelated with the input. This simplification nonetheless leads to reasonable and useful results. One of the primary goals of image pre-processing (and post-processing as well) is to devise techniques that reduce this additive random noise.

The PSF is a function of only the argument differences $x - s$ and $y - t$ for stationary image and object fields. Thus, it is possible to envision an image formation system that is space invariant; hence the PSF is independent of position. In this case, we may rewrite the superposition integral in eqn [1] into a more familiar convolution integral as follows:

$$g(x,y) = \left\{\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} h(x-s,y-t)f(s,t)\mathrm{d}s\,\mathrm{d}t\right\} + n(x,y) \quad [3]$$



Figure 3 Model for image formation and recording.

Equivalently, eqn [3] is written as

$$g(x,y) = \{h(x,y)^{*}f(x,y)\} + n(x,y) \quad [4]$$

where ($*$) is used to denote 2D convolution. Converting from a continuous image $f(x,y)$ to its discrete representation $f(i,j)$ requires the process of sampling. In the ideal sampling system, $f(x,y)$ is multiplied by an ideal 2D impulse train given as

$$f(i,j) = \sum_{m=-\infty}^{+\infty}\sum_{m=-\infty}^{+\infty} f(mX_0,nY_0)\,\delta(x-mX_0,y-Y_0) \quad [5]$$

where X_0 and Y_0 are the sampling distances or intervals, $\delta(^*,^*)$ is the ideal impulse function. Note that the square sampling implies that $X_0 = Y_0$. Sampling with an impulse function corresponds to sampling with an infinitesimally small point. If one is interested in image processing, one should choose a sampling density based upon the classical Nyquist sampling theory. Thus, in discrete domain implementation, eqns [3] and [4] are expressed as

$$g(i,j) = \left\{\sum_{\forall(k,l)} h(i,j;k,l)f(k,l)\right\} + n(i,j),\ 0 \le i,j \le N-1 \quad [6]$$

and,

$$g(i,j) = s\left\{\sum_{\forall(k,l)} h(i-k,j-l)f(k,l)\right\} + n(i,j) \quad [7]$$

Thus, we may rewrite eqn [6] in discrete domain as follows:

$$g(i,j) = h(i,j)^{*}f(i,j) + n(i,j) \quad [8]$$

where ($*$) represents convolution operation. Equation [8] also describes the spatial domain filtering wherein $h(x,y;s,t)$ may be considered as the spatial domain filter mask. The discrete Fourier transform may be used to yield the frequency domain model as follows:

$$G(u,v) = H(u,v)F(u,v) + N(u,v) \quad [9]$$

where G, H, F, and N are corresponding Fourier transforms and u and v are the dummy variables. In eqn [9], $H(u,v)$ is again the frequency domain filter.

We discuss the frequency domain filtering concept further, later in this article.

Spatial Domain Processing

The image pixel domain operations are frequently described as the spatial domain processing. These techniques are important for image pre- as well as post-processing operations. We describe two representative spatial domain processing techniques such as histogram processing and fractal processing for texture analysis below.

Histogram processing

One of the important issues in post-processing is image enhancement. Distortions in image may be introduced due to different noise factors, relative motion between a camera and the object, a camera that is out of focus, or atmospheric turbulence. Noise may be due to thermal measurement errors, recording medium, transmission medium, or digitization process. The histogram processing operation is one of the simplest techniques for enhancing the distorted image for certain type of noises. Histogram equalization is a contrast enhancement technique with the objective to obtain a new enhanced image with a uniform histogram. This can be achieved by using the normalized cumulative histogram as the gray scale mapping function. Histogram modeling is usually introduced using continuous domain functions. Consider that the images of interest contain continuous intensity levels in the interval [0,1] and that the transformation function τ which maps an input image $f(x, y)$ onto an output image $w(x, y)$ is continuous within this interval. We assume that the transfer function, $K_f = \tau(K_w)$, is single-valued and monotonically increasing such that it is possible to define the inverse law $K_w = \tau^{-1}(K_f)$. An example of such a transfer function is illustrated in Figure 4. All pixels in the input image, with densities in the interval D_f to $D_f + dD_f$, are mapped using the transfer function $K_f = \tau(K_w)$, such that they assume an output pixel density value in the interval from D_w to $D_w + dD_w$. Consider that if the histogram h is regarded as a continuous probability density function p, describing the distribution of the intensity levels, then we obtain:

$$p_w(w) = p_f(D_f)/d(D_f) \qquad [10]$$

where

$$D_f = du(f)/df \qquad [11]$$

In the case of histogram equalization, the output probability densities are all an equal fraction of the maximum number of intensity levels in the input image, thus generating a uniform intensity distribution. Sometimes it is desirable to control the shape of the output histogram in order to enhance certain intensity levels in an image. This can be accomplished by the histogram specialization operator which maps a given intensity distribution into a desired distribution using a histogram equalized image as an intermediate stage.



Figure 4 A histogram transformation function.

Fractals for Texture Analysis

The fractal aspect of an image has successfully been exploited for image texture analysis. The fractal concept developed by Mandelbrot, who coined the term fractal from the Latin 'fractus', provides a useful tool to explain a variety of naturally occurring phenomena. A fractal is an irregular geometric object with an infinite nesting of structure at all scales. Fractal objects can be found everywhere in nature such as coastlines, fern trees, snowflakes, clouds, mountains, and bacteria. Some of the most important properties of fractals are self-similarity, chaos, and noninteger fractal dimension (FD). The FD of an object can be correlated with the object properties. Object textures in images are candidates for characterization using fractal analysis because of their highly complex structure. The fractal theory developed by Mandelbrot is based, in part, on the work of mathematicians Hausdorff and Besicovitch. The Hausdorff–Besicovitch dimension, D_H, is defined as:

$$D_H = \lim_{\varepsilon \to 0^+} \frac{\ln N}{\ln 1/r} \qquad [12]$$

where N is the number of elements of box size r required to form a cover of the object. The FD can be defined as the exponent of the number of self-similar pieces (N) with magnification factor ($1/r$) into which a figure may be broken. The FD is a noninteger value in contrast to objects that lie strictly in Euclidean space. The equation for FD is as follows:

$$\mathrm{FD} = \frac{\ln\,(\text{number of self-similar pieces})}{\ln\,(\text{magnification factor})} = \frac{\ln N}{\ln(1/r)} \qquad [13]$$

Frequency Domain Image Filtering

Ignoring noise contribution, we may obtain the basic filtering expression using eqns [7] and [8] as follows:

$$f(i,j) = \Im^{-1}[G(u,v)/H(u,v)] \qquad [14]$$

where $\Im^{-1}$ is the inverse Fourier transform and $[1/H(u,v)]$ is the inverse frequency domain filter. The key importance of this result is that, instead of performing a convolution as shown in eqn [7] to obtain the output of the system, we obtain the inverse of the Fourier transform of the impulse response $h(x,y;s,t)$ and the output image $g(x,y)$, multiply them and then take the inverse Fourier transform of the product to obtain $f(x,y)$. This is the basis for all the filtering as well as other types of image post-processing such as image reconstruction works. The filter function in eqn [9] may have different forms and shapes based on different types of functions such as uniform, Gaussian, lowpass, highpass, etc. While these are all linear filters, there are examples of nonlinear filters such as median, mean, etc. that are equally applicable for image post-processing.

Time-Frequency Domain Processing

One of the fundamental aspects of early image representation is the notion of scale. An inherent property of objects in the world and details in image is that they only exist as meaningful entities over certain ranges of scale. Consequently, a multiscale representation is of crucial importance if one aims at describing the structure of the world, or more specially the structure of projections of the three-dimensional world onto two-dimensional electronic images. The multiscale image post-processing may be facilitated by the wavelet (WT) computation.

A wavelet is, by definition, an amplitude-varying short waveform with a finite bandwidth. Naturally, wavelets are more effective than the sinusoids of Fourier analysis for matching and reconstructing signal features. In wavelet transformation and inversion, all transient or periodic data features can be detected and reconstructed by stretching or contracting a single wavelet to generate the matching building blocks. Consequently, wavelet analysis provides many flexible and effective ways to post-process images that surpass classical techniques – making it very attractive for data analysis, and modeling. The continuous WT is defined as

$$\Phi(a,b) = |a|^{-1/2}\int_{-W}^{W} x(t)\Psi\left[\frac{t-b}{a}\right]\mathrm{d}t \qquad [15]$$

where a and b are scaling and translation factors and $\Psi(t)$ is the mother wavelet. The WT may be viewed as a multiresolution analysis with shifted and scaled versions of the mother wavelet. Corresponding WT coefficients $c_{m,n}$ are

$$c_{m,n} = |a_0|^{-m/2}\int x(t)\Psi([a_0^{-m}t - nb_0])\mathrm{d}t \qquad [16]$$

The reconstruction of the signal is achieved using the admissibility condition, $\int \Psi(t)\mathrm{d}t = 0$, as follows:

$$x(t) = c\int\int_{a>0}\left[\Phi(a,b)\frac{\Psi a, b(t)}{a}\right]\mathrm{d}a\,\mathrm{d}b \qquad [17]$$

where c is a constant. For compact dyadic wavelets, binary scaling and dyadic translation of the mother wavelet form the basis functions. A dyadic translation is a shift by the amount $n/2^m$ that is an integer multiple of the binary scale factor and of the width of the wavelet as well. The discrete WT (DWT) is the natural choice for digital implementation of WT. The DWT basis and 'sub-band coding' process for discretization of a and b are identified. The iterative bandpass filter that finally leads to the wavelet is given as

$$\Psi m, n(x) = 2^{m/2}\Psi(2^{-m}x - n) \qquad [18]$$

The above eqn [18] forms the basis for 'sub-band' implementation for multiresolution analysis (MRA) of wavelet processing.

Image Post-Processing Examples

Some of the important application areas for electronic image post-processing involve the following:

(i) Biomedical image analysis and object detection;
(ii) Image compression for transmission and distribution;
(iii) Satellite image processing and noise removal;
(iv) IR/SAR/detection and clutter removal; and
(v) Image classification and machine vision.

In this article, we provide examples of some of these image-post-processing applications.

Example I: Spatial Domain Processing: Image Post-Processing in Biomedical Image

The mega voltage X-ray images are the X-ray images taken using high voltage X-radiations. These images are often characterized by low resolution, low contrast, and blur. The importance of mega voltage X-ray images arises in the context of radiation therapy for cancer treatment wherein the mega voltage X-radiation is used as a therapeutic agent. Figure 5 shows such mega voltage X-ray images, also known as an electronic portable digital (EPID) image with a very low level of detail. Figure 5a shows poor dynamic range. In order to improve the contrast of this image, without affecting the structure (i.e., geometry) of the information contained therein, we can apply the histogram equalization operation discussed in eqn [10]. Figure 5b presents the result of the histogram image enhancement post-processing process. The low level of detail in the bony anatomy is easily visible in Figure 5b.

Example II: Frequency Domain Processing: Image Post-Processing in Biomedical Tissue Detection

In medical imaging, texture is a fundamental characteristic that can be exploited to analyze tissues and pathologies in a biomedical image. The image texture is often characterized by the random nature of the objects such as tissues and body structures, noise, imaging modality, imaging limitations, and a variety of measurement parameters affecting the image acquisition process. Extensive research suggests that the fractal analysis may be combined with MRA techniques to post-process the texture content of an image in general and tumor detection in particular. In addition, the stochastic fractal Brownian motion (fBm) is well suited to describe texture and tumor characteristics since fBm offers an elegant integration of fractal and multiresolution analysis.

The fBm is a part of the set of $1/f$ processes, corresponding to a generalization of the ordinary Brownian motion $B_{\mathrm{H}}(s)$. It is a nonstationary zero-mean Gaussian random function, defined as

$$\begin{aligned} B_{\mathrm{H}}(t) - B_{\mathrm{H}}(s) = {} & \frac{1}{\Gamma(H+0.5)} \\ & \times \left\{ \int_{-\infty}^{0} [(t-s)^{H-0.5} - s^{H-0.5}] \mathrm{d}B(s) \right. \\ & \left. + \int_{0}^{\infty} (t-s)^{H-0.5} \mathrm{d}B(s) \right\}, \quad B_{\mathrm{H}}(0) = 0 \qquad [19] \end{aligned}$$

where the Hurst coefficient H, restricted to $0 < H < 1$, is the parameter that characterizes fBm; t and s correspond to different observation times of the process B_{H}, and Γ to the Euler's Gamma function. From the frequency domain perspective, it is known that some of the most frequently seen structures in fractal geometry, generally known as $1/f$ processes, show a power spectrum satisfying the power law relationship:

$$S(\omega) \propto \frac{k}{|\omega|^{\gamma}} \qquad [20]$$

where ω corresponds to the spatial frequency, and $\gamma = 2H + 1$. The observations of stationarity and self-similarity of fBm suggest that the use of time-frequency signal decomposition techniques, such as MRA, are well suited for the analysis of fractal signals. Thus, the fBm analysis framework, along with eqn [13], may be successfully exploited to estimate H, and hence, FD as follows:

$$\mathrm{FD} = D_{\mathrm{E}} + 1 - H \qquad [21]$$



Figure 5 (a) Original EPID image; and (b) Histogram enhanced image.

where D_E is the Euclidean dimension that contains the fBm (i.e., the position of each point of the process is described with the vector $x = (x_1, \ldots, x_E)$).

We exploit the wavelet MRA combined with complementary signal processing techniques such as time-frequency descriptions and parameter estimation of stochastic signals in fBm framework for tumor detection in CT images. We demonstrate an example of image post-processing for tumor segmentation. We test our models to estimate FD in brain MR images as shown in Figures 6a and b, respectively. The images are scanned pixel-by-pixel with a sliding window that defines the subimage for analysis. Pre-processing, such as median filtering, is used to remove noise from the original images.

The results for the spectral analyses of CT image are shown in Figure 7. The results suggest that the FD values do not depend on the mother wavelet used. The window size that offers the best results is the 16 × 16 pixels, while better discrimination between low and high H values is obtained using biorthogonal wavelet. To improve tumor detection performance of the spectral technique, we apply post-processing filters on the results in Figures 8a and b, respectively. In Figure 8, for an example, we show the filtered fractal analysis results corresponding to a 16 × 16 pixels window with Daubechies 4. It is possible to obtain an even better description of the location and shape of the tumor after applying a two-dimensional post-processing filter to the matrices derived from the variance estimation algorithms with biorthogonal 1.5 wavelet and an 8 × 8 pixels window, respectively. The results are shown in Figure 9 and are similar for both averaging and Gaussian filters as well.



Figure 6 Biomedical images used to test the proposed algorithms.

Example III: Time-Frequency Domain Filtering: Image Post-Processing in Noise Reduction (De-Noising)

This section discusses an example of image post-processing in image noise removal (or de-noising) using a scale-frequency technique such as wavelets. The wavelet transform has been proved to be very successful in reducing noise (de-noising) in an image. We recently propose a new family of wavelets namely Joint Harmonic Wavelet Transform (JHWT) that offers better speckle noise reduction for image post-processing. Unlike wavelets generated by discrete dilation functions, as shown in eqn [18], whose shape cannot be expressed in functional form, JHWT has a simple structure, which can be written, in the



Figure 7 MR-Fractal analysis using spectral method (a) and (b) correspond to a 16 × 16 analyzing window for Daubechies 4 and biorthogonal 1.5 wavelets, respectively.


Gaussian [5,5], sigma = 1
16 pixel, db4, spectral method
Average [3,3],
16 pixel, db4, spectral method

(a) (b)

Figure 8 Post-processing results using: (a) 5 × 5 Gaussian filtering with $\sigma = 1$ and (b) 3 × 3 averaging filter.


Gaussian [5,5], sigma = 0.5
8 pixel, bior 1.5, variance method
Average [3,3],
8 pixel, bior 1.5, variance method

(a) (b)

Figure 9 Post-processing on the fractal analysis results of Figure 8 for (a) 5 × 5 Gaussian filtering with $\sigma = 1$, and (b) 3 × 3 averaging filtering.

frequency domain:

$$W(\omega) = \int_{-\infty}^{\infty} w(x)\exp(-\mathrm{i}\omega x)\mathrm{d}x,$$
$$= \begin{cases} 1 & \text{for } 2\pi \le \omega < 4\pi \\ 0 & \text{elsewhere} \end{cases} \qquad [22]$$

Now, at level j, we let $g(x) = w(2^j x)$ and shift it by $k/2^j$ to obtain the harmonic wavelet as:

$$g(x - k/2^j) = \{\exp\{\mathrm{i}4\pi(2^j x - k)\} - \exp\{\mathrm{i}2\pi(2^j x - k)\}\}/\mathrm{i}2\pi(2^j x - k) \qquad [23]$$

where integers j and k define the scale and translation of the wavelet $w(x)$, respectively on the x-axis. Now consider a real function $f(t)$ is represented by the sequence f_r of length $(n - 1)$, where $r = 0$ to $2^n - 1$. To obtain JHWT coefficients, we take FFT of f_r such that,

$$|F_{2^j+s}|^2 = (1/n^2)\sum_{k=0}^{n-1} |a_{2^j+k}|^2 \exp(-\mathrm{i}4\pi sk/n), \qquad [24]$$
$$\text{where } r = 0 \text{ to } n-1 \text{ and } s = 0 \text{ to } n-1$$

where j denotes the level of the wavelet, k is the translation, m and n are adjacent levels of wavelets with $n = 2^j$, and $s = m - n$. The JHWT in eqn [24] offers all the properties and advantages of standard discrete wavelet transform. Putting $n = 2^j$ and $m = s + n$, eqn [24] yields all the JHWT coefficients from


(a) (b) (c)

Figure 10 (a) Noisy image; (b) de-noised image with JHWT-filtering; and (c) de-noised image with WP-filtering.

the Fourier coefficients as

$$\sum_{j=0}^{N-1} |F_{2^j+4}|^2 = |a_0|^2 + \sum_{j=0}^{n-2} (1/2^j) \times \sum_{k=0}^{2^j-1} \left(|a_{2^j+k}|^2 + |a_{N-2^j-k}|^2\right) + (a_{N/2})^2 = (1/N) \sum_{r=0}^{N-1} f_r^2 \qquad [25]$$

Unlike conventional correlation techniques, the perfect octave band limited characteristics of JHWT eliminate the necessity of any multiplication. We show an example of image de-noising in Figure 10 using JHWT.

Image Post-processing, Transmission, and Distribution

One of the areas wherein image post-processing plays a vital role is in image transmission. A significant problem for any digital library is the network bandwidth required to transmit large digital images. The bandwidth consumption depends on the number of images used by a single user, and with the number of users requesting the services of the library. The popularity of database browsers such as Gopher and Mosaic has serious implications for image transmission and distribution. There has been active research in innovative new compression schemes and transmission protocols that reduce bandwidth requirements for many users along with software servers and visualization. Further, compression of digital image and video data plays an important role in reducing the transmission and distribution cost for visual communication.

One of the requirements for effective image transmission and distribution is reduced data size for faster speed. Image compression schemes are often used for image data reduction. Most of the successful image compression schemes exploit subdividing the image into blocks for increased compression. However, this subdivision of image renders a blocky effect on the compressed image. There has been intense research in removing the blocky effect on the compressed image. To achieve high bit rate reduction while maintaining the best possible perceptual quality, post-processing techniques provide one attractive solution. There has been a significant amount of work done in post-processing of compressed image/video. Some of them are developed from the image enhancement point of view while others are from image restoration. In the case of image restoration, the post-processing is considered as a reconstruction problem. Image enhancement methods are performed based on the local contents of the decoded image as discussed above.

The image post-processing algorithms are, generally, very effective in removing blocking artifacts. A straightforward approach to remove blocking artifacts is to apply lowpass filtering to the region, where artifacts occur. Consequently, the filter must be adapted to the block boundaries, i.e., the image partition. Further, if high frequency details such as edges and texture are to be preserved, then lowpass filter coefficients should be selected appropriately in regions where such details occur. Therefore, adaptive image post-processing such as spatial filtering methods may be applied to deal with this problem. In low-bit-rate image and video compression and distribution systems, high frequency transformed coefficients are often lost due to aggressive quantization or uneven error protection schemes. However, with the block-based encoding and transmission methods, the amount of high frequency texture loss is uneven between adjacent blocks. Thus, it is possible to exploit this texture-level correlation between adjacent image blocks to reconstruct the lost texture.

A relevant problem of robust transmission and distribution of compressed electronic images involves unreliable networks. The pre- and post-processing of the image data may play a vital role in addressing this problem. With the rapid growth of mobile wireless communication systems, wireless multimedia has recently undergone enormous development. However, to design an efficient multimedia communication system over wireless channels, there still exist many challenges due to severe wireless channel conditions, special characteristics of the compressed multimedia data, and resource limitation, such as power supply. Since multimedia data, such as an image, contain redundancy, to efficiently utilize limited resources, source compression may be necessary. Further, as mentioned above, the ease of image creation, processing, transmission, and distribution has also magnified the associated counterfeiting problems. We discuss the relevant issues of image distribution in the following sections.

Techniques in Image Distribution

The spectacular development of imaging sensors, communication, and internet infrastructure has also made the counterfeiting tools easily accessible and more affordable. In addition, the threats and vulnerabilities of the internet have also increased manyfold. All of these together pose a formidable challenge to the secure distribution and post-processing of images.

Requirements of Secure Digital Image Distribution

In light of the above-mentioned vulnerabilities of image distribution channels and processes, below are a few requirements of secure image distribution:

- *Data Integrity and Authentication*: Digital image is easy to tamper with. Powerful publicly available image processing software packages such as Adobe Photoshop or PaintShop Pro make digital forgeries a reality. Integrity of the image content and authentication of the source and destination of the image distribution are, therefore, of utmost importance.
- *Digital Forensic Analysis*: Consider a litigation involving a medical image that is used for diagnosis and treatment of a disease, as shown in the post-processing example in Figures 7 or 8 above. Integrity of the image again is vital for the proper forensic analysis.
- *Copyright Protection*: Digital copyright protection has become an essential issue to keep the healthy growth of the internet and to protect the rights of on-line content providers. This is something that a textual notice alone cannot do, because it can so easily be forged. An adversary can steal an image, use an image processing program to replace the existing copyright notice with a different notice and then claim to own the copyright himself. This requirement has resulted in a generalized digital rights management initiative that involves copyright protection technologies, policies, and legal issues.
- *Transaction Tracking/Fingerprinting*: In the continuous (re)distribution of digital images through internet and other digital media (CD, camera, etc.), it is important to track the distribution points to track possible illegal distribution of images.

Next, we will discuss how the digital watermarking technology can help enforce these security requirements.

Example of secure image distribution: digital watermarking

Digital watermarking is the process of embedding a digital code (watermark) into a digital content like image, audio, or video. The embedded information, sometimes called a watermark, is dependent on the security requirements mentioned above. For example, if it is copyright application, the embedded information could be the copyright notice. Figure 11 shows a block diagram of the digital watermarking process.

Consider that we want to embed a message M in an image, f_o, also known as the original image. For the sake of brevity, we drop the indices representing the pixel coordinates. The message is first encoded using source coding and optionally with the help of error correction and detection coding, represented in Figure 11 as $e(M)$ such that

$$W_m = e(M) \qquad [26]$$

The encoded message W_m is then combined with the key-based reference pattern W_k, in addition to the scaling factor α, to result in W_a which is the signal that is actually added to the original image, given as

$$W_a = \alpha(f_o)[W_M \otimes W_K] \qquad [27]$$

Note that the scaling coefficient α may be a constant or image dependent or derived from a model of image perceptual quality. When the scaling factor α is dependent on the original image, we can have informed embedding which may result in more perceptually adaptive watermarking. The operation involving W_m and W_k is the modulation part, which is dependent on the actual watermarking algorithm used. As an example, in a typical spread-spectrum based watermarking, this operation is usually an exclusive NOR (XNOR) operation. The final operation is an additive or multiplicative embedding of W_a with the original image. We show a simple additive watermarking process as

$$f_w = f_o + W_a \qquad [28]$$



Figure 11 A simple watermarking process: embedder and detector.



Figure 12 (a) Original image, (b) watermarked image, and (c) the difference image.

The result of this process is the watermarked image f_w which may actually need some clipping and clamping operations to have the image pixel values in the desired range.

The detector, as shown in Figure 11, does the inverse operations of the embedder. If the original image is known, as in the case of nonblind watermarking, it is first subtracted from the watermarked image. Blind watermarking detector, on the other hand, uses some filtering with a goal to estimate and subtract the original image component. The result of filtering is then passed to the decoder, which collects the message bits with the help of the shared key, and finally gets back the decoded message M'.

Figure 12 shows the original image, watermarked image, and the difference image using a spread-spectrum based watermarking algorithm, respectively. The enhanced difference image represents a noise-like image, wherein the scaling coefficient α is clearly dependent on the original image. As evident from Figure 12b, the hidden message is imperceptible as well as the change in the original image. The imperceptibility is one of the primary criteria of digital watermarking.

There are other criteria such as unobtrusiveness, capacity, robustness, security, and detectability. Thus, digital watermarking is a multidimensional problem, which attempts to make a trade-off among a number of different criteria. The inserted watermark should not be obtrusive to the intended use of the original image. Because the watermarking process does not increase the size of the original image, it may be desirable to add as much information as possible. However, generally speaking, the more information one adds, the more severe will be the impact on the perceptual quality of the image. From the detection point of view, watermark should be robust enough to tolerate a range of image post-processing and degradation. In addition, the embedded watermark should also be secure enough so that it may not be removed from the watermarked image. Finally, detectability of the embedded watermark is an important criterion that places some constraints on the embedding algorithm.

In order to fully appreciate the use of watermarking for image distribution, it is instructive to look at different classes of watermark, which is delineated in Figure 13.

For an example, depending on the robustness criterion of watermarking, they can be classified into three categories such as robust, fragile, and semi-fragile. Note that while the robustness of watermark is important, it is not always equally desirable in all applications. Let us take the authentication as an example. If you, as the owner of a digital image, embed some authentication information into the image using watermarking, you might want to see the authentication fail, when some one steals your image. This is an example of nonrobust watermark, where the fragility of the embedded watermark is required to detect any forging done on the digital image.

Now, consider how watermark provides the security requirements for secure image distribution. In particular, we look into the authentication of watermark. Figure 14 shows the use of watermark for image authentication, which has some similarities with the cryptographic authentication using digital signature. However, there are potential benefits to using watermarks in content authentication and verification. Unlike cryptography, watermarking offers both in-storage and in-transit authentication. Watermarking is also faster compared to encryption, which is very important in internet-based image distribution. By comparing a watermark against a known reference, it may be possible to infer not just that an alteration occurred but what, when and where changes have occurred. As shown in Figure 14, first we identify some features from the image and then we compute the digital signature, which is then embedded into the image. The detector takes a test image, computes the signature and extracts the embedded


Visible
Invisible
Blind
Nonblind
Spatial domain
Transform domain
Visibility
Extraction
Readable
Detectable
Recognition
Processing method
Public
Private
Detection
Water marking
Invertible
Noninvertible
Invertibility
Robustness
Robust
Fragile
Semi-fragile
Existence of message
Cover document
Message
Stegano-graphic
Nonstegano-graphic
Noise
Image format
Hardware software
Image
Video
Audio
Text

Figure 13 Watermark classifications.



Figure 14 Image authentication using watermark.

signature, and then compares the two. If they match, the image is authenticated. If they do not match, then the image may have gone through some forging/tampering effects and the algorithm may optionally detect the tamper area as well.

One of the limitations of the watermarking approach in secure image distribution is that the technology is not yet widely deployed, and nor is the protocol satisfactorily standardized. Other major limitation is that the watermarking process cannot be made sufficiently robust to arbitrary types of different attacks. In reality, therefore, the hybrid combination of cryptography and watermarking is expected to improve the secure distribution of images across the unreliable internet.

Concluding Remarks

In this chapter, we discussed the principles of image post-processing and distribution. We showed a few representative examples for post-processing and distribution. We also explained the relevant issues in image distribution and present digital watermarking as one of the solutions for secure image distribution.

Acknowledgment

One of the authors (KMI) wishes to acknowledge the partial support of this work through a grant (RG-01-0125) from the Whitaker Foundation.

See also

Imaging: Information Theory in Imaging.

Further Reading

Ahmed F and Moskowitz IS (2004) A correlation-based watermarking method for image authentication applications, accepted for publication in *Optical Engineering*.
Barlaud M (1994) *Wavelets in Image Communication, Advances in Image Communication 5*. Amsterdam: Elsevier.
Chui A (1992) *An Introduction to Wavelets*. San Diego: Academic Press.
Cox NI, Bloom J and Miller M (2001) *Digital Watermarking: Principles & Practice*. Francis, CO: Morgan Kauffman Publishers.
Daubechies I (1990) The wavelet transform, time-frequency localization and signal analysis. *IEEE Transactions on Information Theory* 36(5): 961–1005.
Gonzalez RC and Woods RE (1993) *Digital Image Processing*. New Jersey: Addison-Wesley Publishing Company.
Iftekharuddin KM and Parra C (2004) Multiresolution-fractal analysis of medical images. Under Review. *Neuroimaging*, vol. 1. New York: Wiley/IEEE Press, Chapter 4.
Jain AK (1989) *Fundamental of Digital Image Processing*. New Jersey: Prentice-Hall.
Lu N (1997) *Fractal Imaging*. San Diego: Academic Press.
Mallat S (1989) A theory for multiresolution signal decomposition: the wavelet representation. *IEEE Transactions on Pattern Analysis and Machine Intelligence* 11(7): 674–693.
Mandelbrot BB (1983) *The Fractal Geometry of Nature*. San Francisco, CA: Freeman.
Schmucker AM and Wolthusen SD (2003) *Techniques and Applications of Digital Watermarking and Content Protection*. Norwood, MA: Artech House.
Serra J (1982) *Image Analysis and Mathematical Morphology*. San Diego: Academic Press.
Stallings W (2003) *Cryptography and Network Security – Principles and Practices*, 3rd edn. New Jersey: Prentice-Hall.
Wu M and Liu B (2002) *Multimedia Data Hiding*. New York: Springer.

Smart Pixel Arrays

P Seitz, Centre Suisse d'Electronique et de Microtechnique SA, Zurich, Switzerland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

For more than 50 years silicon has been the semiconductor on which the enormous progress of microelectronics is based. Since silicon is also an excellent detector for electromagnetic radiation, in particular in the visible spectrum between 400 and 700 nm, the advances in semiconductor technology have directly influenced the progress of solid-state image sensing. Once the relentlessly shrinking dimensions of transistors have reached a critical minimum limit, it has become economically feasible to co-integrate analog and digital circuitry with each light-sensitive pixel. This capability is at the heart of the technological revolution called smart pixel arrays.

The first section relates how the shrinkage of minimum feature size on silicon chips paralleled the reduction of solid-state pixel geometry, as a function of time. This development ceased once the pixel size reached the optical diffraction limit, which marked the birth of the field of smart pixel arrays. In the second section, the basic functionality and the most important physical limitations of conventional pixels and photosensors are given. The third section deals with opto-electronic functionality that is preferred today, of smart pixel arrays; in particular, the capability of spatio-temporal demodulation is very much in demand. In the fourth section, some of the most useful modular building blocks for smart pixel arrays are presented, together with a few key applications. An outlook on photonic systems-on-chip (SoC) is given in the fifth section, with a discussion of single-chip machine vision systems (so-called seeing chips), organic semiconductors for even higher levels of integration of photonic microsystems, and smart pixel arrays that are sensitive to physical parameters other than electromagnetic radiation.

Silicon Technology for Image Sensing

Long before it was realized that silicon would be the material on which modern semiconductor industry and the information technology revolution is based, in 1940 Russell Ohl discovered that silicon is an excellent detector of electromagnetic radiation. In particular, silicon is an excellent detector for light in the visible and near infrared part of the spectrum, for wavelengths between 400 and 1,000 nm. This is very fortunate because it allows designers of image sensors to profit directly from the amazing progress of silicon technology. Since the 1970s, the minimum feature size on silicon chips showed a reliable exponential reduction of about 10% per year, as illustrated in Figure 1. This is a direct consequence of the observation by Intel's Gordon Moore, sometimes called 'Moore's law', that the number of transistors per integrated circuit doubles about every two years. The evolution of minimum feature size is paralleled by the evolution of minimum pixel size of solid-state image sensor, as illustrated in Figure 2. Once the pixel size reached a record low value of 2.4 μm in the year 1996, no further reduction in pixel size seemed desirable, because the optical diffraction limit was essentially reached.

The combination of technological availability of smaller and smaller electronic components and pixel size that demanded no further reduction, inspired researchers to provide each pixel with an increasing amount of electronic functionality, all of which is available simultaneously for massively parallel information processing. This represents the heart of the smart pixel array revolution; pixels that not only sense the incident electromagnetic radiation but that are capable of pre-processing the acquired information in a relevant fashion.


Source: SIA/ITRS Roadmaps and Dataquest

Figure 1 Evolution of minimum feature size (DRAM half-pitch) in state-of-the-art silicon technology, showing an exponential reduction for the past 30 years, which is expected to continue for at least another decade.



Figure 2 Evolution of minimum pixel pitch in CCD image sensors, tracking the exponential reduction of minimum feature size shown in Figure 1, until a lower limit was reached in 1997, imposed by optical diffraction. Since then, no smaller pixel pitches have been described in the literature; this is indicated graphically with the hatched 'diffraction limit' line.

Basic Functionality and Physical Limitations of Conventional Solid-State Photosensors

The prime task of a pixel is the detection of incident electromagnetic radiation. The detection process consists of six basic steps:

1. The incident photon impinges on the surface of the image sensor, and it has to reach the bulk of the semiconductor.
2. In the bulk of the semiconductor the photon has to interact with the semiconductor, converting its energy into a number of electron–hole pairs.
3. The photogenerated charge carriers must be transported to the sensor surface.
4. At the surface, the photogenerated charge needs to be collected and accumulated in the storage part of the pixel.
5. The accumulated photocharge must be transferred to the input of an electronic circuit capable of detecting this charge.
6. The charge detection circuit converts photocharge into a corresponding voltage, exhibiting a monotonous (but not necessarily linear) transfer function.

Since the interaction length of electromagnetic radiation in silicon is in the tens of micrometers for incident photon energies between 1 eV and 10 keV (corresponding to a wavelength range of about 0.1 to 1,000 nm), silicon is an excellent detector for this large spectral range. This is illustrated for the visible and near infrared spectral range in Figure 3, showing the absolute external quantum efficiency of a pixel realized with an industry standard silicon process. In the visible spectral range, absolute external quantum efficiencies close to 100% can be reached, even with standard silicon processes for the microelectronics industry that were not optimized for photosensing applications.



Figure 3 External quantum efficiency of a photosensor realized with an industry standard CMOS process, showing quantum efficiencies above 50% in the whole visible spectral region.

Photocharge transport to the surface of the semiconductor is mainly provided by diffusion, i.e. random thermal motion of the charge carriers that exhibit a velocity of about 10^5 m/s in silicon at room temperature. The mean distance L traveled by a diffusing charge carrier during time t is given by

$$L = \sqrt{Dt} \qquad [1]$$

with the diffusivity D, which has a value of around 40 cm^2/s for electrons in low-doped silicon at room temperature.

Once the photocharge carriers are close to the surface of the semiconductor, they are transported by drift in an electric field E, exhibiting a linear dependence of the transport distance L with time t:

$$L = \mu E t \qquad [2]$$

with the mobility μ which has a value of around 1300 cm^2/Vs for electrons in low-doped silicon at room temperature.

There are two basic principles for creating the electric field with which the photocharge carriers are transported to their storage site within the pixel. A photodiode consists of a semiconductor junction between a p-doped and an n-doped region, as illustrated in Figure 4. Such a photodiode also represents a capacitance on which photocharge can be accumulated and stored. Photodiodes are used as photosensors in one



Figure 4 Cross-section of a photodiode, consisting of an n-doped region in a p-doped substrate. The substrate is contacted using a heavily p-doped diffusion S, and the n-region is contacted using a heavily n-doped diffusion D. The space–charge region is illustrated as hatched area at the pn-junction.



Figure 5 Cross-section of an MOS capacitance, the basic element of a CCD image sensor. On top of a p-substrate a thin transparent insulator O and a transparent electrode E are fabricated. The substrate is contacted with a heavily p-doped diffusion S, and the electrode E is contacted with the gate contact G. The hatched area illustrates the space–charge region under the electrode.

popular type of image sensor, so-called APS (active pixel sensor) or CMOS (complementary metal oxide semiconductor) imagers.

An alternative to a photodiode is an MOS (metal oxide semiconductor) capacitor, consisting of a transparent electrode that covers an insulating layer on top of semiconducting material, as illustrated in Figure 5. An MOS capacitor is the basic element of a charge coupled device (CCD), the other widespread type of image sensor.

The charge transfer between photodiodes and photodetector circuits is based on electrical conduction, occurring essentially with the speed of light. In CCDs, the charge transfer is effectuated with clocks, and excellent charge transfer efficiencies can be observed at clock frequencies of several tens of MHz.

The major limitation in semiconductor photosensors is the last element in the line, i.e. the electronic charge detection circuit. In Figure 6, a so-called source follower is illustrated, which is by far the most frequently used photocharge detection circuit. Its performance is limited by the thermal (Johnson) noise in the channel of the first field effect transistor (FET). This corresponds to a statistical uncertainty with which an amount of photocharge can be measured at the gate of the FET. The input referred charge noise variance s_Q is given approximately by



Figure 6 Schematic diagram of a photosensor's output diffusion OD connected to a reset transistor R and a source follower transistor SF, the most widely used charge detection circuit for image sensors and smart pixel arrays. The photocharge is stored on the effective capacitance C at the gate of transistor SF, which is read out using a row select transistor RS, connecting the source follower to the readout column Col.

$$s_Q \cong C^2 \frac{4kTB}{g} \qquad [3]$$

where C is the effective capacitance seen by the gate of the FET, k is Boltzmann's constant, T is the absolute temperature, B is the effective bandwidth at the FET's channel, and g is the transconductance of the FET.

Desired Optoelectronic Functionality in Smart Pixel Arrays

From the previous section it becomes clear that even conventional pixel and photosensors can be improved in several desirable respects:

- The spectral response can be improved in the ultraviolet (50–400 nm), or it can be expanded significantly into the X-ray region (below 0.1 nm) and into the infrared region (above 1,000 nm).
- The speed of the photosensors can be increased by replacing diffusion based photocharge transfer mechanisms with the directed, more efficient drift in electric fields. This is true for the vertical as well as for the lateral charge transport direction.
- The sensitivity of the electronic charge detection process can be improved in two ways. It can be achieved by decreasing the effective detection capacitance C at the input of the charge detection circuit, as can easily be seen from eqn [3]. An alternative is to make use of a physical charge amplification process (i.e. avalanche multiplication in a high electric field), that has low intrinsic noise.

- A derivative improvement that is desired is the increase of the dynamic range D/R of the complete detection process, as defined, for example, by

  $$D/R = 10^{10} \log \frac{Q_{\max}^2}{s_Q} \qquad [4]$$

  where $Q_{\max}$ denotes the maximum (or saturation) charge and s_Q is the total charge noise variance of the electronic detection circuit.

In addition to the above described improvements of conventional pixel functionality, a huge demand exists for the capability to measure the parameters of modulated electromagnetic signals, i.e. to demodulate such signals. This demand is related to the large number of very powerful electronic and opto-electronic measurement principles, capable of improving the sensitivity of the measurement process significantly by employing modulated signals, either in the temporal or in the spatial domain. For this reason, smart pixel arrays are sought that offer this combination of photodetection and demodulation.

Modular Building Blocks for Smart Pixel Arrays

Towards the end of the last century, a large body of literature has been created, addressing various approaches for the realization of one of the above described desired opto-electronic functionalities. The result is a powerful 'toolbox' of modular building blocks for custom smart pixel arrays, with which optimized solutions for optical measurement problems and practical applications can be constructed.

High-Sensitivity Charge Detection

From the noise formula (eqn [3]) two possibilities for the improvement of the sensitivity of image sensors can be deduced: A first approach is the reduction of the capacitance value. An excellent example for this is the invention of the 'double gate' FET, in which the charge to be measured is not placed on a gate electrode at the surface but resides in the semiconductor bulk. In this way the effective capacitance of the pixel can be reduced by at least one order of magnitude compared to conventional pixels. The resulting capacitance of less than 1 fF leads to a readout noise of about one electron at room temperature and for a readout bandwidth of several MHz. Unfortunately the small capacitance allows the storage of only around ten thousand electrons. For such small charge packets, quantum noise is still relevant, leading to significantly degraded image quality, even when the images are taken under favorable lighting conditions.

A second approach to high-sensitivity photosensing exploits the dependence of the charge detection variance on the measurement bandwidth, as indicated in eqn [3]. One method for exploiting this consists of reading out the image sensor at a significantly reduced bandwidth of a few 10 kHz. At the same time, the image sensor is cooled to temperatures of around −100 °C. This becomes necessary because readout at such slow speeds increases the time, to read one complete image, to many minutes, requiring a substantial reduction of the dark current. Instead of working at low readout bandwidths, it is also possible to read out the same information repeatedly and non-destructively at high speed, and to average many measurements of the same amount of photocharge. Both methods have been shown to lead to readout noise levels of about one electron; on the other hand, both approaches require very long times for the acquisition of complete images.

This problem can be resolved by exploiting the massive parallelism that smart pixel arrays offer: low-bandwidth techniques can be employed without losing effective readout speed. Pixels and columns are read out with low-bandwidth amplifiers that are all active simultaneously, and only the final off-chip readout amplifier needs to operate at a large bandwidth. In practice, this approach has been used successfully in single-chip digital cameras with Megapixel resolution, exhibiting a readout noise of only a very few electrons.

A completely different approach is based on the use of a physical amplification mechanism with low intrinsic noise, before detecting the amplified charge packets with a conventional electronic circuit; the avalanche multiplication effect in high electric fields is very well suited to this approach. Each pixel is supplied with its own combination of stabilized avalanche multiplier and conventional charge detection circuit. This approach has been used for the realization of a fully integrated 2D array of single photon detectors that can be fabricated with industry standard CMOS processes. Similar performance is obtained with the Impactron™ series of high-sensitivity CCD image sensors offered by Texas Instruments Inc., making use of a single multistage avalanche multiplier at the output of the image sensor. For both high-sensitivity smart pixel arrays, single-photoelectron performance is reported at room temperature and at readout frequencies of several MHz, as required for video applications.

Photosensing with Improved Dynamic Range

Conventional solid-state image sensors and cameras usually have a very limited dynamic range, as defined in eqn [4]. Typical values are between 40 and 80 dB, rarely exceeding four orders of magnitude. In natural scenes, however, much higher *D*/*R* values can be encountered. To cope with this, the human eye is capable of spanning a dynamic range of more than 150 dB. This realization has spurred the invention of several methods with which the *D*/*R* of smart pixel arrays can be increased.

One approach consists of acquiring several images of the same scene with different exposure times, with the subsequent combination into one high-dynamic-range composite picture. *D*/*R* values exceeding 120 dB have been obtained with such multi-exposure methods. Fast-moving objects, however, will have relocated from one exposure to the next, resulting in false, blurred representations of these objects in the composite picture.

This can be overcome using nonlinear response characteristics similar to the ones found in natural vision. Impinging light produces a photocurrent that is highly linear with the incident light intensity. Because the voltage across the photodiode is logarithmically dependent on the photocurrent, a logarithmic voltage-illumination response is obtained, with a *D*/*R* exceeding 120 dB. Such logarithmic pixels are well-suited for applications providing high illumination levels but they suffer from excessive noise and slow response speed at low light levels.

This disadvantage led to the development of linear-logarithmic pixels, exhibiting a high-sensitivity linear response at low light levels, and a gradual changeover to logarithmic response once a certain, programmable light level is reached. The design principle is illustrated in Figure 7. An otherwise conventional CMOS/APS pixel is supplied with a device that exhibits logarithmic voltage–current response, such as a diode. As long as the cathode is at a higher voltage than the anode, no current flows across the diode, and the pixel response is linear. Once the photocurrent has lowered the cathode voltage below the anode voltage, the pixel response becomes logarithmic, as described above. The *D*/*R* of such a linear-logarithmic pixel reaches unprecedented high values; almost 200 dB have already been obtained in practice. Because of the simplicity and robustness of this principle, such linear-logarithmic smart pixel arrays have found their way into commercial sensor and camera products that are available commercially, as illustrated in Figure 8. A circuit board and a light bulb are imaged in linear mode (Figure 8a), showing highly saturated areas, and in linear-logarithmic mode (Figure 8b), in which even the light bulb's filament can clearly be seen.



Figure 7 Schematic diagram of a high-dynamic-range pixel, consisting of a conventional APS/CMOS pixel, as illustrated in Figure 6, in combination with a shunt diode SD. The photocurrent lowers the voltage at the gate of transistor SF continuously. Below a certain value of this voltage, the diode starts to become forward biased, leading to a linear-logarithmic illumination response, with a dynamic range that can be as high as 200 dB.

Extension of the Spectral Sensitivity Range

The spectral sensitivity of silicon is essentially restricted to the spectral wavelength range between 0.1 and 1,100 nm. With a suitable choice of materials that cover the silicon sensor's surface, this sensitive wavelength range can be extended. For high-energy radiation, scintillator materials are employed, capable of converting incident high-energy photons into a proportional number of visible photons. Scintillators render smart image sensors particularly sensitive in the UV (300–400 nm), deep UV (below 300 nm), X-ray (0.002–1 nm), and gamma ray (below 0.002 nm) spectral region. Typically, the scintillator materials are fabricated as platelets that are glued on the surface of the produced CMOS/CCD image sensor.

The extension of the sensitive spectral range to the infrared can be achieved with semiconductor materials with smaller energy bandgaps than silicon. Examples include Ge, SiGe, SiC, PtSi, IrSi, InAs, InGaAs, or InGaAsP. Typically, these materials are deposited on the produced CMOS/CCD image sensor in an ultra-high vacuum environment. An alternative is the use of bump-bonding, with which the CMOS/CCD image sensor can be connected to a small-bandgap material chip at each pixel site. With these technologies, silicon-based smart pixel arrays become sensitive to wavelengths of several microns.



Figure 8 Images of a scene with high dynamic range, taken with an image sensor exhibiting linear illumination response (a) and linear-logarithmic illumination response (b). A similar pixel architecture as illustrated in Figure 7 is employed. (Courtesy of Photonfocus AG, Lachen, Switzerland.)

High-Speed Image Sensing

Increasing the speed of the photosensing process necessitates improvements in two key areas. Photocharges need to be collected and transported faster, and the acquired information must be read out faster.

A comparison of eqns [1] and [2] immediately reveals that the replacement of diffusion by drift transport provides the desired speed improvement. In the vertical direction, the electric field of photodiodes or MOS capacitances reaches more deeply into the semiconductor bulk if lower doping levels of the substrate are used or the bias voltage is increased. Improving the lateral transport speed is more difficult. A highly successful approach in so-called drift-field pixels is illustrated in Figure 9. On top of a thin (a few tens of nanometers) transparent insulator, a highly resistive layer – often of polysilicon – is placed. When a voltage difference is applied at the two ends, a small current flows across the resistive layer, inducing a linear potential variation at the semiconductor surface. A simple calculation shows that very small transit times for photocharges can be obtained in this way. Assuming a (quite large) pixel size of 25 μm and a voltage difference of 5 V, the maximum transit time of photoelectrons that have to move from one end of the pixel to the other, is less than 1 ns. This is more than two orders of magnitude faster than can be achieved with diffusion transport.

Smart pixel arrays provide a simple solution to the problem of speeding up the readout of the acquired picture information; a large degree of parallelism. This is illustrated with the architecture of a split-field high-speed image sensor, shown schematically in Figure 10. The photosensitive area is split into two parts, so that the column amplifiers of one half have time to settle to their proper voltages, while the columns of the other half are being read out. No time is lost, therefore, when another row of the image is selected for readout. A large number of output amplifiers are provided for highly parallel readout of the image data, each with a typical readout rate of 40–100 MHz. In this way, sustainable pixel rates of several GHz can be achieved in practice.



Figure 9 Cross-section of a drift field pixel, exploiting the lateral drift field at the semiconductor–oxide interface. The corresponding sloped potential distribution $\Phi(x)$ is created with a highly resistive transparent electrode E on top of a thin transparent insulator O; this conductor has two contacts C1 and C2 at its ends, to which a voltage difference is applied. Depending on the sign of the slope, the photoelectrons are collected either in diffusion D1 or D2. The hatched area indicates the space-charge region.

Static Spatial Demodulation

The spatially varying geometry of the photosensitive part of a pixel can be used for the static spatial



Figure 10 Block diagram of a high-speed image sensor, making use of the large amount of parallelism possible in smart pixel arrays. The light-sensitive area is split into two fields whose rows can be addressed independently with two separate row address generators RG. In this way, one row of one field can be selected and the corresponding column amplifiers CA can reach equilibrium, while the columns of the other field are being read out using several parallel output amplifiers OA.



Figure 11 Illustration of a one-dimensional intensity distribution $p(x)$ of light which is incident on a shaped photodiode with position-dependent width $w(x)$, between the two boundaries a and b.

demodulation of an impinging light field. When a one-dimensional intensity distribution $p(x)$ is incident on a photodiode with spatially varying width $w(x)$ between the limits a and b, as illustrated in Figure 11, an output signal r is produced:

$$r = \int_a^b p(x)w(x)\mathrm{d}x \qquad [5]$$

By shaping the photodiode appropriately, any type of parametrized linear transform can be realized, as illustrated by the photomicrograph in Figure 12. In this practical example, four photodiodes are shaped sinusoidally and cosinusoidally, weighted with a slowly varying windowing function. Their signals are used for determining the Fourier coefficients (the sine and cosine transform) of an incident light distribution for a fixed spatial frequency. This is employed, for example, in cost-effective optical encoders, capable of measuring linear displacement with an accuracy below 50 nm.



Figure 12 Photomicrograph of two photodiode pairs that are shaped as spatial sine and cosine functions, weighted with a slowly varying windowing function. The four photosignals can be employed to determine the phase and amplitude of a one-dimensional intensity signal that has the same spatial frequency as the sine and cosine. In practice, the accuracy of the phase determination is as high as 0.1% of the spatial wavelength. The width of the photomicrograph corresponds to about 1 mm in reality.

Dynamic Spatial Convolution

Many image-processing tasks require the convolution of the pixel data $P_{i,j}$ at the position (i, j) in an image with a two-dimensional convolution kernel $w_{k,l}$:

$$R_{k,l} = \sum_{i=-N}^{N} \sum_{j=-N}^{N} P_{i,j} w_{k-i,l-j} \qquad [6]$$

Instead of employing a purely geometrical solution, as described in the previous section, an alternate approach is found when interpreting the convolution eqn [6] in the following way. The resulting image R is obtained by displacing the original image P laterally by an amount (k,l), by multiplying the shifted pixel values with the corresponding weight $w_{k,l}$, and by adding up all these products.

The lateral displacement is realized with a CCD structure, implementing the 2D lateral movement of the acquired image charge packets, the multiplications with the convolution kernel values are realized by using various exposure times for each lateral shift position, proportional to the corresponding weight value, and the summation is just the natural charge accumulation of CCD structures. The problem of negative weights is solved by separately determining the positive and negative parts of the weight function, each stored separately in the pixel, and by calculating the difference of the two values during readout, either on-chip or off-chip. In this way, such convolution image sensors can be used for the determination of complete, programmable, real-time image convolutions, with arbitrary kernels that are fully under the dynamic control of digital logic or microprocessors. Practical experience with such convolution imagers shows that the convolution results exhibit inaccuracies of less than 1%.

Temporal Demodulation

In many relevant optical measurement techniques, temporally modulated light fields are employed. For this reason, smart pixel arrays are desired, providing synchronous demodulation of these signals. An electromagnetic signal $S(t)$ that is harmonic as a function of time with given frequency ω, having unknown modulation amplitude A, offset B and phase delay φ, is described by

$$S(t) = A\sin(\omega t + \varphi) + B \qquad [7]$$

The three unknowns A, B and φ can be measured if three or more sampling points are sampled synchronously per period in so-called 'lock-in' pixels. An example of a lock-in pixel employing the drift-field transport principle with four accumulation taps, is illustrated in Figure 13. Demodulation frequencies of several tens of MHz have already been demonstrated in practice.

The most important application of such synchronous demodulation pixels is in optical time-of-flight range cameras. Such a camera incorporates a light source, usually an array of infrared or visible LEDs, that is modulated at a few tens of MHz. The modulated light is reflected diffusely by the various objects, and the camera's lens images it onto a lock-in image sensor. Each of its pixels carries out synchronous sampling/accumulation of photocharges. At the end of the exposure time, the accumulated photocharge samples are read out, and the three modulation parameters of the reflected light are determined for each pixel. The phase shift is a direct measure of the local distance. It has been shown that for a wide range of operating conditions, the distance resolution of such optical range cameras is already limited just by the photo shot noise. A typical result of such a depth image is shown in Figure 14.



Figure 13 Schematic top view of a lock-in pixel based on the lateral drift-field approach illustrated in Figure 9. A square electrode is fabricated with a highly resistive transparent material on top of a thin insulator. The electrode contacts C1 to C4 are employed to create a 'reeling' potential distribution that rotates with the modulation frequency of the incident light that requires synchronous demodulation, so that the photocharges are collected at diffusions D1 to D4, respectively, at the appropriate time during each period.

Photonic Systems-on-chip

The microelectronics revolution is based on the key notion of integration. More functionality integrated monolithically on the same chip leads to faster, smaller, better performing, and cheaper products. The same is true for smart pixel arrays, for which progress through integration is attained in several respects.



Figure 14 Example of a distance picture (a person) out of a 3D range image sequence, taken with an optical time-of-flight distance camera making use of lock-in pixels. Depending on the available light level, the background illumination and the modulation frequency, such solid-state range cameras can have a resolution of a few mm.

Seeing Chips

Already, in the mid-1980s, researchers were excited about the possibility of integrating local signal processing capabilities in each pixel, implementing some functions of biological vision systems. It was envisioned that an increasing amount of bio-inspired functionality would lead to smart image sensors, exhibiting a primitive sense of vision. The idea of a 'seeing chip', with the capability to interpret a scene, was born.

Unfortunately, even today, our understanding of the enormously successful biological vision systems has not yet reached a mature enough state allowing us to implement signal processing functions that approximate any 'image understanding'. Published algorithms are still incapable of interpreting a scene and 'perceiving' its contents. Obviously, no set of vision algorithms is yet known with which seeing chips could be realized. Although progress is slower than envisioned, single-chip machine vision systems of growing complexity and increasing functionality are being developed.



Figure 15 Schematic block diagram of a monolithically integrated photonic microsystem, that is expected to be producable in the near future with organic semiconductors. All optoelectronic devices are fabricated on the same planar surface: photovoltaic power supplies (PV); analog and digital signal processing (ASP and DSP); photodetectors (PD); photoemitters (PE) – used for bidirectional communication or as parts of a photonic detector subsystem – a light guiding structure (LG) that can be sensitized for specific sensing applications, and a display subsystem (DS).

Organic Semiconductors for Monolithic Photonic Microsystems

The realization that organic materials with conjugated double bonds, in particular noncrystalline polymers, are direct bandgap semiconductors, has recently led to a flurry of R&D activities in the domain of organic photonics. Organic light-emitting diodes (OLEDs), color displays, lighting panels, photodiodes, image sensors, photovoltaic cells, RF transponders, and tags, and several other organic photonic devices have not only been demonstrated but many are already commercially available. The special appeal of organic semiconductors stems from their potential for monolithic, low-cost integration of complete, large-area photonic microsystems, even on thin, flexible substrates. In Figure 15, such a monolithic photonic microsystem is illustrated schematically, combining a photovoltaic power supply, a photonic detector subsystem, analog and digital signal processing, as well as bidirectional optical communications with the outside world, possibly including also an on-chip display. The photonic detector subsystem typically consists of a light source, a light guiding structure that is sensitized – for example chemically – and a photodetector/image sensor subsection. In such a monolithic photonic microsystem, the term 'smart pixel array' obtains a much broader meaning, opening up a huge number of practical applications in essentially all domains of our daily and professional lives. This domain of organic semiconductors for integrated photonic microsystems is still largely unexplored, and it is offering exciting opportunities for research and product development.

Smart Pixel Arrays Beyond Electromagnetic Field Imaging

The sensing capabilities of smart pixel arrays are not restricted to electromagnetic radiation; this technology can also be used for the acquisition of other two- or three-dimensional physical fields. As an example, electrostatic imaging can be used for the temporally and spatially resolved acquisition of surface potential distributions in living cells. Electrostatic potential values of several hundred mV can be acquired with a precision of 1 mV and a temporal resolution below 1 millisecond. Other acquisition modalities include magnetostatic field imaging, for example by employing the Hall effect, or imaging of local electrostatic charge or current density distributions.

Summary

The relentless advances of semiconductor technology make it possible to integrate an increasing amount of photosensitive, analog, and digital functionality in the same smart pixel and on the same smart pixel array. Unusual photosensor devices can be fabricated with commercially available semiconductor processes, implementing innovative designs and layouts, as well as novel electronic circuits, with which the physical limits of photosensing and photocharge processing may be reached. Novel opto-electronic microsystems can be developed, based on application-specific smart pixel arrays, either by realizing known optical measurement techniques more efficiently or by implementing new techniques, whose realization requires the availability of nonconventional image sensing functionality.

Already, smart pixel arrays are opening up a large number of new opportunities in photonics research and product development. The continuously increasing levels of integration lead to new forms of system-on-chip solutions for a wide range of practical applications. Smart pixel arrays can perform at the basic limits imposed by physics, and they have become indispensable tools in almost any type of research laboratory and any field of science and engineering.

List of Units and Nomenclature

Bandwidth	B	s^{-1}
Boltzmann's constant	k	J/K
Capacitance	C	F
Charge	Q	C
Charge carrier mobility	μ	$m^2/(V\ s)$
Charge noise variance	s_Q	C^2
Diffusivity	D	m^2/s
Distance	L	m
Dynamic range	D/R	dB
Field effect transistor transconductance	g	A/V
Integrated power measured with shaped photodiode	r	W
Intensity of electromagnetic wave	S, A, B	W/m^2
One-dimensional light intensity distribution	$p(x)$	W/m^2
One-dimensional width distribution	$w(x)$	m
Phase delay	φ	–
Pixel value at position (i,j) in an image	$P_{i,j}; R_{i,j}$	–
Temperature	T	K
Temporal frequency	ω	s^{-1}
Time	t	s
Two-dimensional convolution kernel	$w_{k,l}$	–

See also

Electromagnetically Induced Transparency. **Photonic Crystals:** Photonic Crystal Lasers, Cavities and Waveguides. **Semiconductor Materials:** Group IV Semiconductors, Si/SiGe.

Further Reading

Forrest SR (2000) Active optoelectronics using thin-film organic semiconductors. *IEEE Journal on Selected Topics in Quantum Electronics* 6: 1072–1083.

Fossum ER (1997) CMOS image sensors: electronic camera-on-a-chip. *IEEE Transactions on Electron Devices* 44: 1689–1698.

Hosticka BJ, Seitz P and Simoni A (2004) Optical time-of-flight range imaging for solid-state 3D vision. In: Grimes G and Dickey EC (eds) *Encyclopedia of Sensors*. Stevenson Ranch, CA: American Scientific Publishers (in print).

Koch C (1989) Seeing chips: analog VLSI circuits for computer vision. *Neural Computation* 1: 184–200.

Lutz G (1999) *Semiconductor Radiation Detectors*. Berlin: Springer.

Mead C (1989) *Analog VLSI and Neural Systems*. Reading, MA: Addison-Wesley.

Saleh BEA and Teich MC (1991) *Fundamentals of Photonics*. New York: John Wiley and Sons.

Seitz P (1999) Solid-state image sensing. In: Jaehne B (ed.) *Handbook of Computer Vision and Applications*. London: Academic Press.

Seitz P and Blanc N (2003) CCD and APS/CMOS technology for smart pixels and image sensors. *Proceedings of SPIE* 5251 (in print).

Sze SM (1994) *Semiconductor Sensors*. New York: John Wiley and Sons.

Theuwissen AJP (1995) *Solid State Imaging with Charge Coupled Devices*. Dordrecht, Germany: Kluwer.

DIFFRACTION

Contents

Diffraction Gratings
Fraunhofer Diffraction
Fresnel Diffraction

Diffraction Gratings

J Turunen and T Vallius, University of Joensuu, Joensuu, Finland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The classic textbook example of a diffraction grating is a periodic arrangement of parallel opaque wires: if a plane wave is incident upon such a structure, it is divided into a multitude of plane waves propagating in well-defined directions. In particular, the dramatic wavelength-dependence of these directions has attracted great interest ever since the potential of diffraction gratings in spectroscopy was realized in the late 1700s. Today spectroscopy is only one, though important, application of diffraction gratings. Gratings of many different forms belong to the basic building blocks in modern wave-optics-based design of optical elements and systems.

Grating Equations

Some examples of the wide variety of possible grating structures are illustrated in Figure 1, which shows the profiles of some commonly encountered diffraction gratings that are invariant in the y direction. These are known as linear gratings. Each grating may be of reflection type (the refractive index n_{III} is complex) or of transmission type (n_{III} is real). In all cases n_1 and n_2 can both be real or one of them can be complex. Here we assume that the incident field is a plane wave with wave vector $\boldsymbol{k}$ in the $x-z$ plane; more general illumination waves can be represented as superpositions of plane waves.

Figure 1a illustrates a binary grating: in the modulated region $0 < z < H$ the refractive index alternates between n_1 and n_2, changing from one value to another at certain transition points within the period d. The structure in Figure 1b represents a sinusoidal surface-relief grating as an example of smooth grating profiles. Finally, Figure 1c shows a triangular grating profile.

The periodicity of a grating, illuminated by a plane wave, usually leads to the appearance of a set of reflected and transmitted plane waves (diffraction orders of the grating) that propagate in directions determined by the grating period d, the illumination wavelength λ, and the refractive indices n_{I} and n_{III} (see Figure 2a). These directions are obtained from the transmission grating equation:

$$n_{\mathrm{III}} \sin \theta_m = n_{\mathrm{I}} \sin \theta + m\lambda/d \qquad [1]$$

where m is the index of the diffraction order and θ_m is its propagation angle. For reflected orders (superscript r) one simply replaces n_{III} by n_{I} in eqn [1].

Obviously only a limited number of orders satisfy the condition $|\theta_m| < \pi/2$ and thereby represent conventional propagating plane waves. Higher, so-called evanescent orders are inhomogeneous waves that propagate along the grating surface and decay exponentially in the z direction. However, they cannot be ignored in grating analysis, as we shall see.

In the case of a biperiodic grating with a period $d_x \times d_y$ the propagation direction of the incident beam is defined by two angles θ and ϕ illustrated in Figure 2b. The grating equations now read as:

$$n_{\mathrm{III}} \sin \theta_{mn} \cos \phi_{mn} = n_{\mathrm{I}} \sin \theta \cos \phi + m\,\lambda/d_x \qquad [2]$$

$$n_{\mathrm{III}} \sin \theta_{mn} \sin \phi_{mn} = n_{\mathrm{I}} \sin \theta \sin \phi + n\lambda/d_y, \qquad [3]$$

where θ_{mn} and ϕ_{mn} define the propagation directions of the diffraction order with indices m and n. For reflected orders n_{III} is again replaced by n_{I}. These expressions apply also to the special case of linear gratings (limit $d_y \to \infty$) illuminated by a plane



Figure 1 Examples of linear gratings. (a) Binary grating; (b) sinusoidal grating; (c) triangular grating. Here d is the grating period, H is the thickness of the modulated region, θ is the angle of incidence, and n denotes refractive index.



Figure 2 Diffraction by gratings. (a) Linear grating; (b) definitions of direction angles in the case of a biperiodic grating.

wave not propagating in the x–z plane (conical incidence).

Some two-dimensionally periodic gratings are illustrated in Figure 3. The structure illustrated in Figure 3a is an extension of a binary grating to the biperiodic geometry: here a single two-dimensional feature is placed within the grating period but, of course, more features with different outlines could be included as well. Moreover, each period could contain a continuous ‘mountain-range’ or consist of a ‘New-York’-style pixel structure. Figure 3b illustrates a structure consisting of an array of rectangular-shaped holes pierced in a flat screen, while Figure 3c defines an array of isolated particles on a flat substrate. If the grid or the particles are metallic, surrounded by dielectrics from all sides, one speaks of inductive and capacitive structures, respectively: in the former case relatively free-flowing currents are induced in the metallic grid structure, but in the latter case the isolated metal particles become polarized (and therefore capacitive) when illuminated by an electromagnetic field.



Figure 3 Examples of biperiodic gratings. (a) General binary grating; (b) inductive structure; (c) capacitive structure.

Grating Theory

Gratings equations provide exact knowledge of the propagation directions of the diffraction orders, but they give no information about the distribution of light among different orders. To obtain such information, one must in general solve Maxwell's equations exactly (rigorous diffraction theory), but within certain limits simpler methods are available. In all cases, however, the transmitted and reflected fields are represented as superpositions of plane waves that propagate in the directions allowed by the grating equations (these are known as Rayleigh expansions).

The most popular method for rigorous grating analysis is the Fourier Modal Method (FMM), though many alternative analysis methods exist. To understand the principle of FMM, consider first binary gratings. The field inside the modulated region $0 < z < H$ is represented as a superposition of waveguide modes, determined by imagining that the modulated region would extend from $x = -\infty$ to $x = \infty$. With given transition points the electric permittivity, its inverse, and the electric field inside the grating, can be represented in the form of Fourier series and one ends up with a matrix eigenvalue problem with finite dimensions when the matrices are truncated. A numerical solution of this problem provides a set of orthogonal modes that can propagate in the structure with certain propagation constants. The relative weights of the modes are then determined by applying the electromagnetic boundary conditions at the planes $z = 0$ and $z = H$ to match the modal expansions inside the grating with the plane-wave (Rayleigh) expansions of the fields in the homogeneous materials on both sides of the grating. This matching procedure, which is numerically implemented by solving a set of simultaneous linear equations, yields the complex amplitudes of the electric and magnetic field components associated with the reflected and transmitted diffraction orders of the grating.

Of main interest are the diffraction efficiencies, η_m (or η_{mn} for biperiodic gratings) of the orders, which tell the distribution of energy between different propagating orders. In electromagnetic theory the diffraction efficiency is defined as the z-component of the time-averaged Poynting vector associated with the particular order, divided by that of the incident plane wave.

Gratings with z-dependent surface profiles can be handled similarly if they are 'sliced' into a sufficient number of layers, in each of which the grating is modeled as a binary structure. The electromagnetic boundary conditions are applied at each slice boundary and the approach models the real continuous structure with arbitrary degree of accuracy when the number of the slices is increased; in practice it is usually sufficient to use approximately 20–30 slices for sufficiently accurate modeling of any continuous grating profile by FMM.

The main problem with rigorous techniques such as FMM is bad scaling. If, in the case of 1D modulated (or y-invariant) gratings, the period is increased by a factor of two, the computation time required to solve the eigenvalue problem is increased by a factor of around eight. Thus we have a d^3 type scaling law. The situation is much worse for biperiodic gratings, for which the exponent is around six. Thus no foreseeable developments in computer technology will solve the problem, and approximate analysis methods have to be sought. A multitude of such methods are under active development, but in this context we discuss the simplest example only.

If $d \gg \lambda$ and the grating profile does not contain wavelength-scale features, one can describe the effects of a grating on the incident field merely by considering it as a complex-amplitude-modulating object, which imposes a position-dependent phase shift and amplitude transmission (or reflection) coefficient on the incident field. This model is known as the thin-element approximation (TEA).

At normal incidence the plane-wave expansion of any scalar field component U immediately behind the grating (at $z = H$) takes the form:

$$U(x, y, H) = \sum_{m=-\infty}^{\infty} \sum_{n=-\infty}^{\infty} T_{mn} \times \exp[\mathrm{i}2\pi(mx/d_x + ny/d_y)] \qquad [4]$$

where

$$T_{mn} = \frac{1}{d_x d_y} \int_0^{d_x} \int_0^{d_y} U(x, y, H) \times \exp[-\mathrm{i}2\pi(mx/d_x + ny/d_y)]\mathrm{d}x\,\mathrm{d}y \qquad [5]$$

are the complex amplitudes of the transmitted diffraction orders. In TEA the field at $z = H$ may be connected to the field at $z = 0$ (a unit-amplitude plane wave is assumed here) by optical path integration along a straight line though the modulated region of the grating:

$$U(x, y, H) = \int_0^H \exp\left[\mathrm{i}\frac{2\pi}{\lambda}\hat{n}(x, y, z)\right]\mathrm{d}z \qquad [6]$$

where $\hat{n}(x, y, z) = n(x, y, z) + \mathrm{i}\kappa(x, y, z)$ is the complex refractive-index distribution in the region $0 < z < H$. With TEA the diffraction efficiencies can be calculated from a simple formula:

$$\eta_{mn} = |T_{mn}|^2 \qquad [7]$$

which, however, ignores Fresnel reflections.

Equations [5]–[7] allow one to obtain closed-form expressions for the diffraction efficiencies η_{mn} in many grating geometries. For example, a y-invariant triangular profile with $H = \lambda/|n_\mathrm{I} - n_\mathrm{III}|$ gives $\eta_{-1} = 100\%$ if $n_1 = n_\mathrm{III}$, $n_2 = n_\mathrm{I}$, and $\theta = 0$. For a Q-level stair-step-quantized version of this grating we obtain:

$$\eta_m = \sin c^2(1/Q) \qquad [8]$$

where $\sin cx = \sin(\pi x)/(\pi x)$. It should be noted, however, that these results are valid only for gratings with $d \gg \lambda$, even if they are corrected by Fresnel transmission losses at the interface between the two media.

Fabrication of Gratings

Gratings can be manufactured in a number of different ways, perhaps the simplest being to plot an equidistant array of straight black and white lines and to reduce the scale of the pattern photographically. This method can be readily adapted to the generation of more complex grating structures and diffractive elements, but it is not suitable for the production of high-quality gratings required in, for example, spectroscopy.

Ruling engines represent the traditional way of making gratings with periods of the order of the wavelength of light, especially for spectroscopic applications. These are machines equipped with a triangularly shaped diamond ruling edge and an interferometrically controlled two-dimensional mechanical translation stage that moves the substrate with respect to the ruling edge. Triangular-profile gratings of high quality can be produced with such machines, but the fabrication process is slow and the cost of the manufactured gratings is therefore high. In addition, even with real-time interferometric control of the ruling-edge position, it is impossible to avoid small local errors in the grating geometry. Such errors are particularly harmful if they are periodic since, according to the grating equation, these errors will generate spurious spectral lines known as ghosts. Such lines generated by the grating 'super-period' are weak but they may be confused with real spectral lines in the source spectrum. If the ruling errors are random, they result in 'pedestal-type' background noise. While such errors do not introduce ghosts, they nevertheless reduce the visibility of weak original spectral lines.

The introduction of lasers in the early 1960s made it possible to form stable and high-contrast interference patterns over a sufficient time-scale to allow the exposure of photographic films and other photosensitive materials such as polymeric photoresists. This interferometric technique offers a direct method for the fabrication of large diffraction gratings without appreciable periodic errors. With this technique it is possible to make highly regular gratings for spectroscopy, but it does not permit easy generation of arbitrarily shaped grating structures. The two intersecting plane waves can also be generated with a linear grating using diffraction orders $m = +1$ and $m = -1$, suppressing the zero order by appropriate design of the grating profile and choosing the period in such a way that all higher transmitted orders are evanescent. This so-called phase mask technique is suitable, for example, for the exposure of Bragg gratings in fibers.

To generate arbitrary gratings one usually employs lithographic techniques. Some of the possible processes are illustrated in Figure 4. The exposure can be performed with scanning photon, electron, or ion beams, etc. The process starts with substrate preparation, i.e., coating it with a beam-sensitive layer known as resist, and in the case of electron beam exposure with a thin conductive layer to prevent charging. Following the exposure the resist is developed chemically, and in this process either the exposed or nonexposed parts of the resist are dissolved (depending on whether the resist is of positive or negative type), leading to a surface-relief profile. Several alternative fabrication steps may follow the development, depending on the desired grating type. If a high-contrast resist is used, a slightly 'undercut' profile as illustrated in Figure 4c is obtained. This can be coated with a metal layer and the resist can be 'lifted off' chemically. Thus a binary metallic grating is formed. To produce a binary dielectric profile one bombards the substrate with ions either purely mechanically (ion beam milling) or with chemical assistance (reactive ion etching), and finally the residual metal is dissolved.

Alternatively, the particle beam dose can be varied with position to obtain an analog profile in the resist after development. This resist profile can be transformed into the substrate by proportional etching, which leads to an analog dielectric surface-relief structure (see Figure 4f). This profile can be made



Figure 4 Lithographic processes for grating fabrication. (a) Substrate after preparation for electron beam exposure; (b) exposure by a scanning electron beam; (c) slightly undercut profile in hight-contrast resist after development, under metal film evaporation; (d) analog resist profile after variable-dose exposure and resist development; (e) finished binary metallic grating after resist lift-off; (f) transfer of the analog surface-relief profile into the substrate by proportional etching; (g) etching of a binary profile into the substrate with a metal mask; (h) growth of a metal film on an analog surface profile.



Figure 5 Spectral diffraction efficiency curves of spectroscopic gratings in TE polarization. (a) Binary; (b) sinusoidal; and (c) triangular reflection gratings illuminated at Bragg angle. Solid lines: $d = \lambda_0$. Dashed lines: $d = 2\lambda_0$.


Mag = 513 X
20 μm
EHT = 30.00 kV
WD = 15 mm
Signal A = SE2
Photo No. = 337
Date : 18 Nov 1998
Time : 13:34

Figure 6 A scanning electron micrograph of a part of a diffractive lens.

reflective by depositing a thin metal film on top of it. If large-scale fabrication of identical gratings is the goal, a thick (~100 μm) metal layer (for example nickel) can be grown on the surface by electroplating. After separation from the substrate, the electroplated metal film, which is a negative of the original profile, can be used as a stamp in replicating the original profile in plastics using methods such as hot embossing, ultraviolet radiation curing, and injection molding. In particular, the latter method provides the key to high-volume and low-cost production of various types of diffraction gratings and other grating-based diffractive structures in the industrial scale.

Some Grating Applications

We now proceed to describe a collection of representative grating applications. More exhaustive coverage of grating applications can be found in the Further Reading section at the end of this article.

Spectroscopic Gratings

The purpose of a spectroscopic grating is to divide the incident light into a spectrum, i.e., to direct different frequency components of the incident beam into different directions given by the grating (eqn [1]). When the grating period is reduced, the angular dispersion $\partial\theta_m/\partial\lambda$, and therefore the resolution of the spectrograph, increases.

In the numerical examples presented in Figure 5 we assume a reflection grating in a Littrow mount, i.e., $\theta_m^r = -\theta$. This mount is common in spectroscopy; it obviously requires that the grating is rotated when the spectrum is scanned. We see from eqn [1] that in the Littrow mount:

$$\sin\theta = \frac{m\lambda}{2d} \qquad [9]$$

By inserting this result back into eqn [1] and differentiating we obtain a quantitative measure for dispersion in the Littrow mount:

$$\frac{\partial\theta_m}{\partial\lambda} = -\frac{m}{2d\cos\theta} \qquad [10]$$

We consider TE polarization (electric field is linearly polarized in the y-direction) and order $m = -1$, optimize H to give maximum efficiency at $\lambda_0 = 550$ nm, and plot the diffraction efficiency η_{-1} over the visible wavelength range for two values of the grating period, $d = \lambda_0$ and $d = 2\lambda_0$. Rigorous diffraction theory is used with $n_I = n_2 = 1$, and the metal is assumed to be aluminum (n_I and n_{III} are complex-valued).

In Figure 5a binary gratings with one groove (width $d/2$) per period is considered. Parametric optimization gives $H = 422$ nm if $d = 1\lambda$, and $H = 168$ nm if $d = 2\lambda$. Figure 5b illustrates the results for sinusoidal gratings with $H = 345$ nm if $d = 1\lambda$, and



Figure 7 Diffraction efficiency versus wavelength for triangular transmission gratings illuminated at normal incidence. Solid lines: TE polarization. Dashed lines: TM polarization.



Figure 8 Surface-relief profiles of (a) continuous and (b) binary 1 → 8 beamsplitter gratings.

$H = 520$ nm if $d = 2\lambda$. Finally, triangular gratings with $H = 431$ nm if $d = 1\lambda$, and $H = 316$ nm if $d = 2\lambda$, are considered. The triangular grating profile is seen to be the best choice in general.

Diffractive Lenses

Diffractive lenses are gratings with locally varying period and groove orientation. Figure 6 illustrates the central part of a diffractive microlens fabricated by lithographic methods. It is seen to consist of concentric zones with radially decreasing width.

The phase transmission function of an ideal diffractive focusing lens can be obtained by a simple optical path calculation, and is given by

$$\phi(r) = \frac{2\pi}{\lambda_0}\left(f - \sqrt{f^2 + r^2}\right) \approx -\frac{\pi}{\lambda_0 f} r^2 \qquad [11]$$

where f is the focal length, r is the radial distance from the optical axis, and the approximate expression is valid in the paraxial region $r \ll f$. Here λ_0 is the design wavelength, which determines the modulation depth of the locally blazed grating profile:

$$H = \frac{\lambda_0}{n(\lambda_0) - 1} \qquad [12]$$

and $n(\lambda_0)$ is the refractive index of the dielectric material at $\lambda = \lambda_0$.

The zone boundaries r_n are defined by the condition $\phi(r_n) = -2\pi n$, and therefore we obtain from eqn [11]:

$$r_n = \sqrt{2nf\lambda_0 + (n\lambda_0)^2} \approx \sqrt{2nf\lambda_0} \qquad [13]$$

Obviously, when the numerical aperture of the lens is large, the zone width in the outer regions of the lens is reduced to values of the order of λ. Figure 7 illustrates the local diffraction efficiency in different part of a diffractive lens: we use the order $m = -1$ of a locally triangular diffraction grating of the



Figure 9 Diffraction pattern produced by a continuous-profile beamsplitter grating when (a) $d = 200\lambda$ and (b) $d = 50\lambda$.



Figure 10 Diffraction pattern produced by a binary beamsplitter grating grating when (a) $d = 200\lambda$ and (b) $d = 50\lambda$.

type shown in Figure 1c with $\theta = 0$, assuming that $n_{\mathrm{I}} = n_2 = 1.5$ (fused silica) and $n_1 = n_{\mathrm{III}} = 1$. The efficiency η_{-1} is calculated as a function of λ using rigorous diffraction theory for both TE and TM polarization (the electric vector points in the groove direction in the TE case and is perpendicular to it in the TM case). It is seen that the local efficiency of the lens becomes poor in regions where the local grating period is small, and thus diffractive lenses operate best in the paraxial region (it is, however, possible to obtain improved nonparaxial performance by optimizing the local grating profile).

A factor that limits the use of diffractive lenses with polychromatic light is their large chromatic aberration: in the paraxial limit the focal length depends on the wavelength according to the formula:

$$f(\lambda) = \frac{\lambda_0}{\lambda} f \qquad [14]$$

However, since the dispersion of a grating has an opposite sign compared to the diffraction of a prism, a weak positive diffractive lens can be combined with a relatively strong positive refractive lens to form a single-element achromatic lens. Such a hybrid lens is substantially thinner and lighter than a conventional all-refractive achromatic lens made of crown and flint glasses.

Beam Splitter Gratings

Multiple beamsplitters, also known as array illuminators, are gratings with sophisticated periodic structure that are capable of transforming an incident plane wave into a set of diffraction orders with a specified distribution of diffraction efficiencies. Most often one wishes to obtain a one- or two-dimensional array of diffracted plane waves with equal efficiency. This goal can be achieved by appropriate design of the grating profile, which may be of binary, multilevel, or continuous form.

Figure 8 illustrates binary and continuous grating profiles capable of dividing one incident plane wave into eight diffracted plane waves (central odd-numbered orders of the grating) with equal efficiency in view of TEA. Figure 9 shows the distribution of energy among the different diffraction orders in and around the array produced by the continuous profile, evaluated by rigorous theory for two different grating periods, while Figure 10 gives corresponding results for the binary grating.



Figure 11 Scanning electron micrograph of a sophisticated beamsplitter grating.



Figure 12 The far-field diffraction pattern produced by the grating in Figure 11.

The fraction of incident energy that ends up in the desired eight orders is 72% for the binary grating and 96% for the continuous grating according to TEA, making the latter more attractive from a theoretical viewpoint. However, the continuous profile is more difficult to fabricate accurately than the binary one, especially for small values of the ratio d/λ. Moreover, the array uniformity produced by the continuous profile degrades faster than that of the binary profile when the period is reduced.

An example of the structure of a biperiodic grating that is capable of forming a large, shaped array of diffraction orders with equal efficiency is presented in Figure 11. Figure 12 shows the far-field diffraction pattern produced by this element: the shape of Finland with the location of the town of Joensuu highlighted by placing the zero diffraction order on the appropriate position on the map (the apparent nonuniformity in the array is mostly due to the finite resolution of the CCD detector).



Figure 13 Zero order spectral transmission (solid line) and reflection (dashed line) of an aluminium inductive grid filter with 400 nm period.

Inductive Grid Filters

As a final example we consider a scaled-down version of a device well known from the door of a microwave oven: one can see in through the holes pierced in the metallic screen in the oven door, but the microwaves are trapped inside because their wavelengths are large in comparison with the dimensions of the holes. Another example of these inductive grid filters is found in large radio telescope mirrors for centimeter-scale wavelengths, which are wide-grid structures rather than smoothly curved metal surfaces.

Figure 13 illustrates the spectral transmission and reflection curves of an inductive grid filter of the type illustrated in Figure 3b. We assume that $d_x = d_y = d = 400$ nm, $c_x = c_y = c = 310$ nm, $H = 500$ nm, and that the grid is a self-supporting structure ($n_{\mathrm{I}} = n_{\mathrm{III}} = 1$) made of aluminum. Only the zero reflected and transmitted orders propagate when $\lambda > d$, but other orders (with rather low efficiency) appear for smaller wavelengths. We see that the filter reflects infrared radiation effectively, but transmits a substantial part of radiation at visible and shorter wavelength regions.

List of Units and Nomenclature

Complex field amplitude	U
Diffraction angles [rad]	θ, ϕ
Diffraction efficiency	η
Focal length [m]	f, f_0
Grating period [m]	d
Grating thickness [m]	H
Number of quantization levels	Q
Phase function [rad]	$\phi(r)$
Refractive index	n
Wavelength [m]	λ, λ_0
Wave vector [m^{-1}]	$\mathbf{k}$

See also

Fiber Gratings.

Further Reading

Chandezon J, Maystre D and Raoult G (1980) A new theoretical method for diffraction gratings and its numerical application. *Journal of Optics* 11: 235–241.

Gaylord TK and Moharam MG (1985) Analysis and applications of optical diffraction by gratings. *Proceedings of IEEE* 73: 894–937.

Herzig HP (ed.) (1997) *Micro-optics: Elements, Systems and Applications*. London: Taylor & Francis.

Hutley MC (1982) *Diffraction Gratings*. London: Academic Press.

Li L (2001) Mathematical reflections on the fourier modal method in grating theory. In: Bao G, Cowsar L and Masters W (eds) *Mathematical Modelling in Optical Science*, pp. 111–139. Philadelphia: SIAM.

Li L, Chandezon J, Granet G and Plumey J-P (1999) Rigorous and efficient grating-analysis method made easy for optical engineers. *Applied Optics* 38: 304–313.

Petit R (ed.) (1980) *Electromagnetic Theory of Gratings*. Berlin: Springer-Verlag.

Rayleigh JWS (1907) On the dynamical theory of gratings. *Proceeding of the Royal Society A* 79: 399.

Solymar L and Cooke DJ (1981) *Volume Holography and Volume Gratings*. London: Academic Press.

Turunen J, Kuittinen M and Wyrowski F (2000) Diffractive optics: electromagnetic approach. In: Wolf E (ed.) *Progress in Optics XL*. Amsterdam: Elsevier.

Turunen J and Wyrowski F (eds) (1997) *Industrial and Commercial Applications of Diffractive Optics*. Berlin: Akademie Verlag.

van Renesse RL (1993) *Optical Document Security*. Boston, MA: Artech House.

Fraunhofer Diffraction

B D Guenther, Duke University, Durham, NC, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Geometrical optics does a reasonable job of describing the propagation of light in free space unless that light encounters an obstacle. Geometrical optics predicts that the obstacle would cast a sharp shadow. On one side of the shadow's edge would be a bright uniform light distribution, due to the incident light, and on the other side there would be darkness. Close examination of an actual shadow edge reveals, however, dark fringes in the bright region and bright fringes in the dark region. This departure from the predictions of geometrical optics was given the name diffraction by Grimaldi.

There is no substantive difference between diffraction and interference. The separation between the two subjects is historical in origin and is retained for pedagogical reasons. Since diffraction and interference are actually the same physical process, we expect the observation of diffraction to be a strong function of the coherence of the illumination. With incoherent sources, geometrical optics is usually all that is needed to predict the performance of an optical system and diffraction can be ignored except at dimensions on the scale of a wavelength. With light sources having a large degree of spatial coherence, it is impossible to neglect diffraction in any analysis.

Even though diffraction produced by most common light sources and objects is a small effect, it is possible to observe diffraction without special equipment. By viewing a light source through a slit formed by two fingers that are nearly touching, fringes can be observed. Diffraction is used by photographers and television cameramen to provide artistic highlights in an image containing small light sources. They accomplish this by placing a screen in front of the camera lens. Light from point sources in the field of view is diffracted by the screen and produces ‘stars’ in the image. A third place where diffraction effects are easily observed is when a mercury or sodium streetlight, a few hundred meters away, is viewed through a sheer curtain.

Fresnel originally developed an approximate scalar theory based on Huygens’ principle which states that:

> Each point on a wavefront can be treated as a source of a spherical wavelet called a secondary wavelet or a Huygens’ wavelet. The envelope of these wavelets, at some later time, is constructed by finding the tangent to the wavelets. The envelope is assumed to be the new position of the wavefront.

Rather than simply using the wavelets to construct an envelope, Fresnel’s scalar theory assumes that the Huygens’ wavelets interfere to produce a new wavefront (*see* **Diffraction:** Fresnel Diffraction).

A rigorous diffraction theory is based on Maxwell’s equations and uses the boundary conditions associated with the obstacle to calculate a field scattered by the obstacle. The origins of this scattered field are currents induced in the obstacle by the incident field. The scattered field is allowed to interfere with the incident field to produce a resultant diffracted field. The application of the rigorous theory is very difficult and for most problems an approximate scalar theory developed by Kirchhoff and Sommerfeld is used.

Kirchhoff Theory of Diffraction

Kirchhoff’s theory was based on the elastic theory of light but can be reformulated into a vector theory. Here we will limit our discussion to the scalar formulation. Given an incident wave, φ, we wish to calculate the optical wave at point P_0, in Figure 1, located at $\mathbf{r}_0$, in terms of the wave’s value on a surface, S, that we construct about the observation point.

To obtain a solution to the wave equation at the point, P_0, we select as a Green’s function the one proposed by Kirchhoff (Box 1), a unit amplitude spherical wave, expanding about the point at $\mathbf{r}_0$, denoted by Ψ, and then apply Green’s theorem (see Box 2). We will run into boundary condition problems as we proceed with the derivation of the solution. Sommerfeld removed the problems by assuming a slightly more complex Green’s function (see Box 1). We will limit our discussion to the Kirchhoff Green’s function.



Figure 1 Region of integration for solution of Kirchhoff’s diffraction integral. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

Green’s theorem requires that there be no sources (singularities) inside the surface S but our Green’s function [1] is based on a source at r_0. We eliminate the source by constructing a small spherical surface S_ε, of radius ε, about $\mathbf{r}_0$, excluding the singularity at $\mathbf{r}_0$ from the volume of interest, shown in gray in Figure 1. The surface integration that must be performed in Green’s theorem is over the surface $S' = S + S_\varepsilon$.

Within the volume enclosed by S', the Green’s function, Ψ, and the incident wave, φ, satisfy the scalar Helmholtz equation so that the volume integral can be written as

$$\iiint_V (\Psi\nabla^2\varphi - \varphi\nabla^2\Psi)\mathrm{d}v = -\iiint_V (\Psi\varphi k^2 - \varphi\Psi k^2)\mathrm{d}v \qquad [7]$$

The right side of [7] is identically equal to zero. This fact allows us to use [6] to produce a simplified statement of Green’s theorem:

$$\iint_{S'} \left(\Psi\frac{\partial\varphi}{\partial n} - \varphi\frac{\partial\Psi}{\partial n}\right)\mathrm{d}s = 0 \qquad [8]$$

Box 1

Green's Function

1. **Kirchhoff Green's function**: Assume that the wave, Ψ, is due to a single point source at $\mathbf{r}_0$. At an observation point, $\mathbf{r}_1$, the Green's function is given by

$$\Psi(\mathbf{r}_1) = \frac{e^{-ik\cdot\mathbf{r}_{01}}}{r_{01}}, \qquad [1]$$

   where $r_{01} = |\mathbf{r}_{01}| = |\mathbf{r}_1 - \mathbf{r}_0|$ is the distance from the source of the Green's function, at $\mathbf{r}_0$, to the observation position, at $\mathbf{r}_1$.
2. **Sommerfeld Green's function**: Assume that there are two point sources, one at P_0 and one at P_0' (see Figure 2 where the source, P_0', is positioned to be the mirror image of the source at P_0 on the opposite side of the screen, thus

$$r_{01} = r_{01}' \qquad \cos(\hat{\mathbf{n}}, \mathbf{r}_{01}) = -\cos(\hat{\mathbf{n}}, \mathbf{r}_{01}') \qquad [2]$$

   A Green's function that could be used is

$$\Psi' = \frac{e^{-ik\cdot\mathbf{r}_{01}}}{r_{01}} - \frac{e^{-ik\cdot\mathbf{r}_{01}'}}{r_{01}'} \qquad [3a]$$

   or

$$\Psi' = \frac{e^{-ik\cdot\mathbf{r}_{01}}}{r_{01}} + \frac{e^{-ik\cdot\mathbf{r}_{01}'}}{r_{01}'} \qquad [3b]$$

Box 2

Green's Theorem

To calculate the complex amplitude, $\tilde{E}(\mathbf{r})$, of a wave at an observation point defined by the vector $\mathbf{r}$, we need to use a mathematical relation known as Green's Theorem. Green's theorem states that, if φ and Ψ are two scalar functions that are well behaved, then

$$\iint_S (\varphi\nabla\Psi\cdot\hat{\mathbf{n}} - \Psi\nabla\varphi\cdot\hat{\mathbf{n}})\mathrm{d}s = \iiint_V (\varphi\nabla^2\Psi - \Psi\nabla^2\varphi)\mathrm{d}v \qquad [4]$$

The vector identities

$$\nabla\Psi\cdot\hat{\mathbf{n}} = \frac{\partial\Psi}{\partial n} \qquad \nabla\varphi\cdot\hat{\mathbf{n}} = \frac{\partial\varphi}{\partial n} \qquad [5]$$

allow Green's theorem to be written as

$$\iint_S \left[\varphi\frac{\partial\Psi}{\partial n} - \Psi\frac{\partial\varphi}{\partial n}\right]\mathrm{d}s = \iiint_V [\varphi\nabla^2\Psi - \Psi\nabla^2\varphi]\mathrm{d}v \qquad [6]$$

This equation is the prime foundation of scalar diffraction theory but only the proper choice of Ψ, φ and the surface, S, allows direct application to the diffraction problem.



Figure 2 Geometry for the Sommerfeld Green's function. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

Because the integral over the combined surfaces, S and S_ε, is equal to zero, the integral over the surface S must equal the negative of the integral over the surface, S_ε:

$$-\iint_{S_\varepsilon}\left(\Psi\frac{\partial\varphi}{\partial n}-\varphi\frac{\partial\Psi}{\partial n}\right)\mathrm{d}s=\iint_{S}\left(\Psi\frac{\partial\varphi}{\partial n}-\varphi\frac{\partial\Psi}{\partial n}\right)\mathrm{d}s \quad [9]$$

To perform the surface integrals, we must evaluate the Green's function on the surface, S′. We therefore select $\mathbf{r}_1$, the vector defining the observation point, to be on either of the two surfaces that make up S′. The derivative, $\partial\Psi/\partial n$, to be evaluated is

$$\begin{aligned}\frac{\partial\Psi}{\partial n}&=\frac{\partial\Psi}{\partial r}\frac{\partial r}{\partial n}\\&=\left(-ik\frac{e^{-ik\cdot\mathbf{r}_{01}}}{r_{01}}-\frac{e^{-ik\cdot\mathbf{r}_{01}}}{r_{01}^2}\right)\cos(n,\mathbf{r}_{01})\end{aligned} \quad [10]$$

where $\cos(\hat{\mathbf{n}},\mathbf{r}_{01})$ is the cosine of the angle between the outward normal $\hat{\mathbf{n}}$ and the vector $\mathbf{r}_{01}$, the vector between points P_0 and P_1. (Note from Figure 1 that the outward normal on S_ε is inward, toward P_0, while the normal on S is outward, away from P_0.)

For example if $\mathbf{r}_1$ were on S_ε, then

$$\cos(\mathbf{n},\mathbf{r}_{01})=-1, \quad [11]$$

$$\frac{\partial\Psi(\mathbf{r}_1)}{\partial n}=\left[\frac{1}{\varepsilon}+ik\right]\frac{e^{-ik\varepsilon}}{\varepsilon}, \quad [12]$$

where ε is the radius of the small sphere we constructed around the point at P_0.

We now use [10] to rewrite the two integrals in [9]. The integral over the surface S_ε is

$$\begin{aligned}&\iint_{S_\varepsilon}\left(\Psi\frac{\partial\varphi}{\partial n}-\varphi\frac{\partial\Psi}{\partial n}\right)\mathrm{d}s\\&=\iint_{S_\varepsilon}\left[\frac{\partial\varphi}{\partial n}\frac{e^{-ik\varepsilon}}{\varepsilon}-\varphi\frac{e^{-ik\varepsilon}}{\varepsilon}\left(\frac{1}{\varepsilon}+ik\right)\right]\\&\times\varepsilon^2\sin\theta\,\mathrm{d}\theta\,\mathrm{d}\phi\end{aligned} \quad [13]$$

while the integral over the surface S is

$$\iint_{S}\left[\frac{e^{-ik\cdot\mathbf{r}_{01}}}{r_{01}}\frac{\partial\varphi}{\partial n}-\varphi\frac{\partial}{\partial n}\left(\frac{e^{-ik\cdot\mathbf{r}_{01}}}{r_{01}}\right)\right]r^2\sin\theta\,\mathrm{d}\theta\,\mathrm{d}\phi \quad [14]$$

The omitted volume contained within the surface S_ε is allowed to shrink to zero by taking the limit as $\varepsilon\to 0$. Equation [14] will not be affected by taking the limit. The first and last terms of the right side of [13] go to zero as $\varepsilon\to 0$ because they contain $\varepsilon e^{-ik\varepsilon}$. The second term in [13] contains $e^{-ik\varepsilon}$ which goes to 1 as $\varepsilon\to 0$. Therefore, in the limit as $\varepsilon\to 0$, [9] becomes

$$\varphi(\mathbf{r}_0)=\frac{1}{4\pi}\iint_{S}\left[\frac{e^{-ik\cdot\mathbf{r}_{01}}}{r_{01}}\frac{\partial\varphi}{\partial n}-\varphi\frac{\partial}{\partial n}\left(\frac{e^{-ik\cdot\mathbf{r}_{01}}}{r_{01}}\right)\right]\mathrm{d}s \quad [15]$$

which is sometimes called the integral theorem of Kirchhoff. By carefully selecting the surface of integration in [15], we can calculate the diffraction field observed at P_0 produced by an aperture in an infinite opaque screen.

Assume that a source at P_2 in Figure 3 produces a spherical wave that is incident on an infinite, opaque screen from the left. To find the field at P_0 in Figure 3, we apply [15] to the surface $S_1+S_2+\Sigma$, where S_1 is a plane surface adjacent to the screen, Σ is that portion of S_1 in the aperture and S_2 is a large spherical surface, of radius R, centered on P_0, see Figure 3. The first question to address is how to calculate the contribution from S_2 or better yet how do we show we can ignore contributions from S_2. As R increases, Ψ and φ will decrease as $1/R$. However, the area of integration increases as R^2 so the $1/R$ fall-off is not a sufficient reason for neglecting the contribution of the integration over S_2.

On the surface S_2, the Green's function and its derivative are

$$\Psi=\frac{e^{-ikR}}{R} \quad [16]$$



Figure 3 Integration surface for diffraction calculation. P_2 is the source and P_0 is the point where the field is to be calculated. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

$$\frac{\partial\Psi}{\partial n} = \left(-\mathrm{i}k - \frac{1}{R}\right)\frac{\mathrm{e}^{-\mathrm{i}kR}}{R} \approx -\mathrm{i}k\Psi \qquad [17]$$

where the approximate equality is for large R. Thus, the integral over S_2 for large R is

$$\iint_{S_2}\left[\Psi\frac{\partial\varphi}{\partial n} + \varphi(\mathrm{i}k\Psi)\right]\mathrm{d}s$$

$$= \iint_{S_2}\Psi\left(\frac{\partial\varphi}{\partial n} + \mathrm{i}k\varphi\right)R^2 \sin\theta\,\mathrm{d}\theta\,\mathrm{d}\phi \qquad [18]$$

The quantity $R\Psi = \mathrm{e}^{-\mathrm{i}\mathbf{k}\cdot\mathbf{R}}$ is finite as $R \to \infty$ so for the integral to vanish, we must have

$$\lim_{R\to\infty} R\left(\frac{\partial\varphi}{\partial n} + \mathrm{i}k\varphi\right) = 0 \qquad [19]$$

This requirement is called the Sommerfeld radiation condition and is satisfied if $\varphi \to 0$ as fast as $1/R$ (for example, a spherical wave). Since the illumination of the screen will be a spherical wave, or at least a linear combination of spherical waves, we should expect the integral over S_2 to make no contribution (it is exactly zero).

Another way to insure that surface S_2 makes no contribution is to assume that the light turns on at time t_0. At a later time, t, when we desire to know the field at P_0, the radius of S_2 is $R > c\ (t - t_0)$ which physically means that the light has not had time to reach S_2. In this situation, there can be no contribution from S_2. This is not a perfect solution because when the wave is of finite duration it can no longer be considered monochromatic.

We should expect the major contribution in the integral over S_1 to come from the portion of the surface in the aperture, Σ. We make the following assumptions about the incident wave, φ (these assumptions are known as St. Venaut's hypothesis or Kirchhoff's boundary conditions)

1. We assume that, in the aperture, φ and $\partial\varphi/\partial n$ have the values they would have if the screen were not in place.
2. On the portion of S_1 not in the aperture, φ and $\partial\varphi/\partial n$ are identically zero.

The Kirchhoff boundary conditions allow the screen to be neglected, reducing the problem to an integration only over the aperture. It is surprising that the assumptions about the contribution of the surface S_2 and the screen yield very accurate results (as long as polarization is not important, the aperture is large with respect to the wavelength, and we don't get too close to the aperture).

Mathematically the Kirchhoff boundary conditions are incorrect. The two Kirchhoff boundary conditions imply that the field is zero everywhere behind the screen, except in the aperture, which makes Ψ and $\partial\Psi/\partial n$ discontinuous on the boundary of the aperture. Another problem with the boundary conditions is that Ψ and $\partial\Psi/\partial n$ are known only if the problem has already been solved.

The Sommerfeld Green's functions will remove the inconsistencies of the Kirchhoff theory. If we use the Green's function [3a] then Ψ vanishes in the aperture while $\partial\Psi/\partial n$ can assume the value required by Kirchhoff's boundary conditions. If we use the Green's functions [3b] then the converse holds, i.e. $\partial\Psi/\partial n$ is zero in the aperture. This improved Green's function makes the problem harder with little gain in accuracy so we will retain the Kirchhoff formalism.

As a result of the above discussion, the surface integral [15] is only performed over the surface, Σ, in the aperture. The evaluation of the Green's function on this surface can be simplified by noting that normally $r_{01} \gg \lambda$, i.e., $k \gg 1/r_{01}$, thus on Σ,

$$\begin{aligned}\frac{\partial\Psi}{\partial n} &= \cos(\mathbf{n}, \mathbf{r}_{01})\left(-ik - \frac{1}{r_{01}}\right)\frac{e^{-ik\cdot r_{01}}}{r_{01}} \\ &\approx -ik\cos(\hat{\mathbf{n}}, \mathbf{r}_{01})\frac{e^{-ik\cdot r_{01}}}{r_{01}}\end{aligned} \qquad [20]$$

Substituting this approximate evaluation of the derivative into [15] yields

$$\varphi(\mathbf{r}_0) = \frac{1}{4\pi}\iint_{\Sigma}\frac{e^{-ik\cdot r_{01}}}{r_{01}}\left[\frac{\partial\varphi}{\partial n} + ik\varphi\cos(\hat{\mathbf{n}}, \mathbf{r}_{01})\right]ds \qquad [21]$$

The source of the incident wave is a point source located at P_2, with a position vector, $\mathbf{r}_2$, measured with respect to the coordinate system and a distance $|\mathbf{r}_{21}|$ away from P_1, a point in the aperture (see Figure 3). The incident wave is therefore a spherical wave of the form

$$\varphi(\mathbf{r}_{21}) = A\frac{e^{-ik\cdot r_{21}}}{r_{21}} \qquad [22]$$

which fills the aperture. Here also we will assume that $r_{21} \gg \lambda$ so that the derivative of the incident wave assumes the same form as [20]. Then [21] can be written

$$\begin{aligned}\varphi(\mathbf{r}_0) &= \frac{iA}{\lambda}\iint_{\Sigma}\frac{e^{-ik\cdot(r_{21}+r_{01})}}{r_{21}r_{01}} \\ &\quad\times\left[\frac{\cos(\hat{\mathbf{n}}, \mathbf{r}_{01}) - \cos(\hat{\mathbf{n}}, \mathbf{r}_{21})}{2}\right]ds\end{aligned} \qquad [23]$$

This relationship is called the Fresnel–Kirchhoff diffraction formula. It is symmetric with respect to r_{01} and r_{21}, making the problem identical when the source and measurement point are interchanged.

A physical understanding of [23] can be obtained if it is rewritten as

$$\varphi(\mathbf{r}_0) = \iint_{\Sigma}\Phi(\mathbf{r}_{21})\frac{e^{-ik\cdot r_{01}}}{r_{01}}ds \qquad [24]$$

The field at P_0 is due to the sum of an infinite number of secondary Huygens sources in the aperture Σ. The secondary sources are point sources radiating spherical waves of the form

$$\Phi(\mathbf{r}_{21})\frac{e^{-ik\cdot r_{01}}}{r_{01}} \qquad [25]$$

with amplitude $\Phi(r_{21})$, defined by

$$\Phi(\mathbf{r}_{21}) = \frac{i}{\lambda}\left[A\frac{e^{-ik\cdot r_{21}}}{r_{21}}\right]\left[\frac{\cos(\hat{\mathbf{n}}, \mathbf{r}_{01}) - \cos(\hat{\mathbf{n}}, \mathbf{r}_{21})}{2}\right] \qquad [26]$$

The imaginary constant, i, causes the wavelets from each of these secondary sources to be phase shifted with respect to the incident wave. The obliquity factor, in the amplitude [26]

$$\tfrac{1}{2}[\cos(\hat{\mathbf{n}}, \mathbf{r}_{01}) - \cos(\hat{\mathbf{n}}, \mathbf{r}_{21})] \qquad [27]$$

causes the secondary sources to have a forward directed radiation pattern.

If we had used the Sommerfeld Green's function, the only modification to our result would be a change in the obliquity factor to $\cos(\mathbf{n},\mathbf{r}_{01})$. In our discussions below we will assume that the angles are all small, allowing the obliquity factor to be replaced by 1 so that in the remaining discussion the choice of Green's function has no impact.

We will assume the source of light is at infinity, $z_1 = \infty$ in Figure 3, so that the aperture is illuminated by a plane wave, traveling parallel to the z-axis. With this assumption

$$\theta' = \cos(\mathrm{n}, \mathbf{r}_{21}) \approx -1 \qquad [28]$$

We will also make the paraxial approximation which assumes that the viewing position is close to the z-axis, leading to

$$\theta = \cos(\mathbf{n}, \mathbf{r}_{01}) \approx 1 \qquad [29]$$

With these assumptions eqn [24] becomes identical to the Huygens–Fresnel integral discussed in the section on Fresnel diffraction:

$$\tilde{E}(\mathbf{r}_0) = \frac{i}{\lambda}\iint_{\Sigma}\frac{\tilde{E}_i(\mathbf{r})}{R}e^{-ik\cdot R}\,ds \qquad [30]$$

The modern interpretation of the Fresnel–Kirchhoff (or now in the small-angle approximation, the Fresnel–Huygens) integral is to view it as a convolution integral. By considering free space to be a linear system, the result of propagation can be calculated by convolving the incident (input) wave with the impulse response of free space (our Green's function),

$$\frac{\mathrm{i}}{\lambda}\,\frac{\mathrm{e}^{-\mathrm{i}\mathbf{k}\cdot\mathbf{R}}}{R} \qquad [31]$$

The job of calculating diffraction has only begun with the derivation of the Fresnel–Kirchhoff integral. In general, an analytic expression for the integral cannot be found because of the difficulty of performing the integration over R. There are two approximations that will allow us to obtain analytic expressions of the Fresnel–Kirchhoff integral. In both approximations, all dimensions are assumed to be large with respect to the wavelength. In one approximation, the viewing position is assumed to be far from the obstruction; the resulting diffraction is called Fraunhofer diffraction and will be discussed here. The second approximation, which leads to Fresnel diffraction, assumes that the observation point is nearer the obstruction, to be quantified below. This approximation, which is the more difficult mathematically, is discussed in the article on **Diffraction:** Fresnel Diffraction.

Fraunhofer Approximation

In Fraunhofer diffraction, we require that the source of light and the observation point, P_0, be far from the aperture so that the incident and diffracted wave can be approximated by plane waves. A consequence of this requirement is that the entire waveform passing through the aperture contributes to the observed diffraction.

The geometry to be used in this derivation is shown in Figure 4. The wave incident normal to the aperture, Σ, is a plane wave and the objective of the calculation is to find the departure of the transmitted wave from its geometrical optical path. The calculation will provide the light distribution, transmitted by the aperture, as a function of the angle the light is deflected from the incident direction. We assume that diffraction makes only a small perturbation on the predictions of geometrical optics. The deflection angles encountered in this derivation are, therefore, small, as assumed above, and we will be able to use the paraxial approximation.

The distance from a point P, in the aperture, to the observation point P_0, of Figure 4, is

$$R^2 = (x-\xi)^2 + (y-\eta)^2 + Z^2 \qquad [32]$$

From Figure 4 we see R_0 is the distance from the center of the screen to the observation point, P_0,

$$R_0^2 = \xi^2 + \eta^2 + Z^2 \qquad [33]$$

The difference between these two vectors is

$$\begin{aligned} R_0^2 - R^2 &= (R_0 - R)(R_0 + R) \\ &= \xi^2 + \eta^2 + Z^2 - Z^2 - (x^2 - 2x\xi + \xi^2) \\ &\quad - (y^2 - 2y\eta + \eta^2) \\ &= 2(x\xi + y\eta) - (x^2 + y^2) \end{aligned} \qquad [34]$$



Figure 4 Geometry for Fraunhofer diffraction. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

The equation for the position of point P in the aperture can be written in terms of [34]:

$$\begin{aligned} r = R_0 - R &= \frac{R_0^2 - R^2}{R_0 + R}, \\ &= [2(x\xi + y\eta) - (x^2 + y^2)]\frac{1}{R_0 + R} \end{aligned} \quad [35]$$

The reciprocal of $(R_0 + R)$ can be written as

$$\frac{1}{R_0 + R} = \frac{1}{2R_0 + R - R_0} = \frac{1}{2R_0}\left(1 + \frac{R - R_0}{2R_0}\right)^{-1} \quad [36]$$

Now using [36]

$$\begin{aligned} R_0 - R &= \left[\frac{x\xi + y\eta}{R_0} - \frac{x^2 + y^2}{2R_0}\right]\left[1 - \frac{R_0 - R}{2R_0}\right]^{-1} \\ &= \left[\frac{x\xi + y\eta}{R_0} - \frac{x^2 + y^2}{2R_0}\right]\left[1 - \frac{r}{2R_0}\right]^{-1} \end{aligned} \quad [37]$$

If the diffraction integral [30] is to have a finite (nonzero) value, then

$$k|R_0 - R| \ll kR_0 \quad [38]$$

This requirement insures that all the Huygens's wavelets, produced over the aperture from the center out to the position r, will have similar phases and will interfere to produce a nonzero amplitude at P_0. This requirement results in

$$\frac{1}{1 - \frac{r}{2R_0}} \approx 1 \quad [39]$$

From this equation we are tempted to state that the aperture dimension must be small relative to the observation distance. However, for the exponent to provide a finite contribution in the integral, it is kr that is small, not the aperture dimension, r.

Using the approximation for $(R_0 - R)$, we obtain the diffraction integral

$$\tilde{E}_P = \frac{i\alpha\, e^{-i\mathbf{k}\cdot\mathbf{R}_0}}{\lambda R_0} \iint_{\Sigma} f(x, y) e^{+ik\left(\frac{x\xi + y\eta}{R_0} - \frac{x^2 + y^2}{2R_0}\right)}\, dx\, dy \quad [40]$$

The change in the amplitude of the wave due to the change in R, as we move across the aperture, is neglected, allowing R in the denominator of the Huygens–Fresnel integral to be replaced by R_0 and moved outside of the integral. We have introduced the complex transmission function, $f(x, y)$, of the aperture to allow a very general aperture to be treated. If the aperture function described the variation in absorption of the aperture as a function of position, as would be produced by a photographic negative, then $f(x, y)$ would be a real function. If the aperture function described the variation in transmission of a biological sample, it might be entirely imaginary.

The argument of the exponent in [40] is

$$\begin{aligned} &ik\left(\frac{x\xi + y\eta}{R_0} - \frac{x^2 + y^2}{2R_0}\right) \\ &= i2\pi\left(\frac{x\xi + y\eta}{\lambda R_0} - \frac{x^2 + y^2}{2\lambda R_0}\right) \end{aligned} \quad [41]$$

If the observation point, P_0, is far from the screen, we can neglect the second term and treat the phase variation across the aperture as a linear function of position. This is equivalent to assuming that the diffracted wave is a collection of plane waves. Mathematically, the second term in [41] can be neglected if

$$\frac{x^2 + y^2}{2\lambda R_0} \ll 1 \quad [42]$$

This is called the far-field approximation and the theory yields Fraunhofer diffraction. If the quadratic term of [41] is on the order of 2π then the fraction is

$$\frac{x^2 + y^2}{2\lambda R_0} \approx \Theta(1) \quad [43]$$

and we must retain the quadratic term and the theory yields Fresnel diffraction.

We define spatial frequencies in the x and y direction by

$$\begin{aligned} \omega_x &= \frac{2\pi}{\lambda}\sin\theta_x = -\frac{2\pi\xi}{\lambda R_0} \\ \omega_y &= \frac{2\pi}{\lambda}\sin\theta_y = -\frac{2\pi\eta}{\lambda R_0} \end{aligned} \quad [44]$$

We define the spatial frequencies with a negative sign to allow equations involving spatial frequencies to have the same form as those involving temporal frequencies. The negative sign is required because ωt and $\mathbf{k}\cdot\mathbf{r}$ appear in the phase of the wave with opposite signs and we want the Fourier transform in space and in time to have the same form.

With the variables defined in [44], the integral becomes

$$\tilde{E}_P(\omega_x, \omega_y) = \frac{i\alpha\, e^{-i\mathbf{k}\cdot\mathbf{R}_0}}{\lambda R_0} \iint_{\Sigma} f(x, y) e^{-i(\omega_x x + \omega_y y)}\, dx\, dy \quad [45]$$

The result of our derivation is that the Fraunhofer diffraction field, $\tilde{E}_P$, can be calculated by performing the two-dimensional Fourier transform of the aperture's transmission function.

Definition of Fourier Transform

In this discussion the function $F(\omega)$ is defined as the *Fourier transform* of $f(t)$:

$$\mathcal{F}\{f(t)\} \equiv F(\omega) \equiv \int_{-\infty}^{\infty} f(\tau) \mathrm{e}^{-\mathrm{i}\omega\tau}\, \mathrm{d}\tau \qquad [46]$$

The transformation from a temporal to a frequency representation given by [46] does not destroy information; thus, the inverse transform can also be defined

$$\mathcal{F}^{-1}\{F(\omega)\} = f(t) = \frac{1}{2\pi} \int_{-\infty}^{\infty} F(\omega) \mathrm{e}^{\mathrm{i}\omega t}\, \mathrm{d}\omega \qquad [47]$$

By assuming that the illumination of an aperture is a plane wave and that the observation position is in the far field, the diffraction of an aperture is found to be given by the Fourier transform of the function describing the amplitude transmission of the aperture. The amplitude transmission of the aperture, $f(x, y)$, may thus be interpreted as the superposition of mutually coherent plane waves.

Diffraction by a Rectangular Aperture

We will now use Fourier transform theory to calculate the Fraunhofer diffraction pattern from a rectangular slit and point out the reciprocal relationship between the size of the diffraction pattern and the size of the aperture.

Consider a rectangular aperture with a transmission function given by

$$f(x, y) = \begin{cases} 1 & |x| \le x_0, |y| \le y_0 \\ 0 & \text{all other } x \text{ and } y \end{cases} \qquad [48]$$

Because the aperture is two-dimensional, we need to apply a two-dimensional Fourier transform but it is not difficult because the amplitude transmission function is separable, in x and y. The diffraction amplitude distribution from the rectangular slit is simply one-dimensional transforms carried out individually for the x and y dimensions:

$$\tilde{E}_P = \frac{\mathrm{i}\alpha}{\lambda R_0} \mathrm{e}^{-\mathrm{i}k\cdot\mathbf{R}_0} \int_{-x_0}^{x_0} f(x) \mathrm{e}^{-\mathrm{i}\omega_x x}\, \mathrm{d}x \int_{-y_0}^{y_0} f(y) \mathrm{e}^{-\mathrm{i}\omega_y y}\, \mathrm{d}y \qquad [49]$$

Since both $f(x)$ and $f(y)$ are defined as symmetric functions, we need only calculate the cosine transforms to obtain the diffracted field:

To calculate the Fourier transform defined by [46] we can rewrite the transform as

$$F(\omega) = \int_{-\infty}^{\infty} f(\tau) \cos \omega\tau\, \mathrm{d}\tau - \mathrm{i} \int_{-\infty}^{\infty} f(\tau) \sin \omega\tau\, \mathrm{d}\tau \qquad [50]$$

If $f(\tau)$ is a real, even function then the Fourier transform can be obtained by simply calculating the cosine transform:

$$\int_{-\infty}^{\infty} f(\tau) \cos \omega\tau\, \mathrm{d}\tau \qquad [51]$$

$$\tilde{E}_P = \mathrm{i} \frac{4x_0 y_0 \alpha}{\lambda R_0} \mathrm{e}^{-\mathrm{i}k\cdot\mathbf{R}_0} \frac{\sin \omega_x x_0}{\omega_x x_0} \frac{\sin \omega_y y_0}{\omega_y y_0} \qquad [52]$$

The intensity distribution of the Fraunhofer diffraction produced by the rectangular aperture is

$$I_P = I_0 \frac{\sin^2 \omega_x x_0}{(\omega_x x_0)^2} \frac{\sin^2 \omega_y y_0}{(\omega_y y_0)^2} \qquad [53]$$

The maximum intensities in the x and y directions occur at

$$\omega_x x_0 = \omega_y y_0 = 0 \qquad [54]$$

The area of this rectangular aperture is defined as $A = 4x_0 y_0$, resulting in an expression for the maximum intensity of

$$I_0 = \left[\frac{\mathrm{i}4x_0 y_0 \alpha\, \mathrm{e}^{-\mathrm{i}k\cdot\mathbf{R}_0}}{\lambda R_0} \right]^2 = \frac{A^2 \alpha^2}{\lambda^2 R_0^2} \qquad [55]$$

The minima of [53] occur when $\omega_x x_0 = n\pi$ or when $\omega_y y_0 = m\pi$. The location of the zeros can be specified as a dimension in the observation plane or, using the paraxial approximation, in terms of the angle defined by [44]

$$\begin{aligned} \sin \theta_x &\approx \theta_x \approx \frac{\xi}{R_0} = \frac{n\lambda}{2x_0} \\ \sin \theta_y &\approx \theta_y \approx \frac{\eta}{R_0} = \frac{m\lambda}{2y_0} \end{aligned} \qquad [56]$$

The dimensions of the diffraction pattern are characterized by the location of the first zero, i.e., when $n = m = 1$, and are given by the observation plane coordinates, ξ and η. The dimensions of the diffraction pattern are inversely proportional to the dimensions of the aperture. As the aperture dimension expands, the width of the diffraction pattern decreases until, in the limit of an infinitely wide aperture, the diffraction pattern becomes a delta function.



Figure 5 The amplitude of the wave diffracted by a rectangular slit. This sinc function describes the light wave's amplitude that would exist in both the *x* and *y* directions. The coordinate would have to be scaled by the dimension of the slit. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

Figure 5 is a theoretical plot of the amplitude of the diffraction wave from a rectangular slit.

Diffraction from a Circular Aperture

To obtain the diffraction pattern from a circular aperture we first convert from the rectangular coordinate system we have used to a cylindrical coordinate system. The new cylindrical geometry is shown in Figure 6. At the aperture plane

$$\begin{aligned} x &= s\cdot\cos\varphi \qquad & y &= s\cdot\sin\varphi \\ f(x,y) &= f(s,\varphi) \qquad & \mathrm{d}x\,\mathrm{d}y &= s\,\mathrm{d}s\,\mathrm{d}\varphi \end{aligned} \qquad [57]$$

At the observation plane

$$\xi = \rho\cdot\cos\theta \qquad \eta = \rho\cdot\sin\theta \qquad [58]$$

In the new, cylindrical, coordinate system at the observation plane, the spatial frequencies are written as

$$\begin{aligned} \omega_x &= -\frac{k\xi}{R_0} = -\frac{k\rho}{R_0}\cos\theta \\ \omega_y &= -\frac{k\eta}{R_0} = -\frac{k\rho}{R_0}\sin\theta \end{aligned} \qquad [59]$$

From Figure 6 we see that the observation point, P, can be defined in terms of the angle ψ, where

$$\sin\psi = \frac{\rho}{R_0} \qquad [60]$$

This allows an angular representation of the size of the diffraction pattern if it is desired.

Using [57] and [59], we may write

$$\begin{aligned} \omega_x x + \omega_y y &= -\frac{ks\rho}{R_0}(\cos\theta\cos\varphi + \sin\theta\sin\varphi), \\ &= -\frac{ks\rho}{R_0}\cos(\theta-\varphi) \end{aligned} \qquad [61]$$

The Huygens–Fresnel integral for Fraunhofer diffraction can now be written in terms of cylindrical coordinates:

$$\tilde{E}_P = \frac{\mathrm{i}\alpha}{\lambda R_0}\mathrm{e}^{-\mathrm{ik}\cdot\mathrm{R}_0}\int_0^{\frac{a}{2}}\int_0^{2\pi} f(s,\varphi)\mathrm{e}^{-\mathrm{ik}\frac{s\rho}{R_0}\cos(\theta-\varphi)}\,s\,\mathrm{d}s\,\mathrm{d}\varphi \qquad [62]$$

We will use this equation to calculate the diffraction amplitude from a clear aperture of diameter *a*, defined by the equation

$$f(s,\varphi) = \begin{cases} 1 & s \le \frac{a}{2},\ \text{all } \varphi \\ 0 & s > \frac{a}{2} \end{cases} \qquad [63]$$

The symmetry of this problem is such that

$$f(s,\varphi) = f(s)g(\varphi) = f(s) \qquad [64]$$

$$\mathcal{F}\{f(s,\phi)\} = \mathcal{F}\{f(s)\} = F(\rho) \qquad [65]$$



Figure 6 Geometry for calculation of Fraunhofer diffraction from a circular aperture. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

$$F(\rho,\theta) = \int_0^\infty f(s)s\,\mathrm{d}s \int_0^{2\pi} \mathrm{e}^{-\mathrm{i}\rho\cdot s\cos(\varphi-\theta)}\,\mathrm{d}\varphi \qquad [66]$$

$$F(\rho) = \int_0^\infty f(s)\,s\,\mathrm{d}s \int_0^{2\pi} \mathrm{e}^{-\mathrm{i}\rho\cdot s\cos\varphi}\,\mathrm{d}\varphi \qquad [67]$$

The second integral in [67] belongs to a class of functions called the Bessel function defined by the integral

$$\mathrm{J}_n(s\rho) = \frac{1}{2\pi}\int_0^{2\pi} \mathrm{e}^{\mathrm{i}[s\rho\sin\varphi - n\varphi]}\mathrm{d}\varphi \qquad [68]$$

In [67] the integral corresponds to the $n = 0$, zero-order, Bessel function. Using this definition, we can rewrite [67] as

$$F(\rho) = \int_0^\infty f(s)\mathrm{J}_0(s\rho)s\,\mathrm{d}s \qquad [69]$$

This transform is called the Fourier–Bessel transform or the Hankel zero-order transform.

Using these definitions, the transform of the aperture function, $f(s)$, is

$$F(\rho) = \int_0^{\frac{a}{2}} \mathrm{J}_0(s\rho)s\,\mathrm{d}s \qquad [70]$$

We use the identity

$$x\mathrm{J}_1(x) = \int_0^x \chi\mathrm{J}_0(\chi)\,\mathrm{d}\chi \qquad [71]$$

to obtain

$$F(\rho) = \frac{a}{2\rho}\mathrm{J}_1\left(\frac{\rho a}{2}\right) \qquad [72]$$

We can now write the amplitude of the diffracted wave as

$$\tilde{E}_P = \frac{\mathrm{i}\alpha}{\lambda}\mathrm{e}^{-\mathrm{i}\mathbf{k}\cdot\mathbf{R}_0}\left[\frac{\pi a}{k\rho}\mathrm{J}_1\left(\frac{ka\rho}{2R_0}\right)\right] \qquad [73]$$

A plot of the function contained within the bracket of [73] is given in Figure 7. If we define

$$u = \frac{ka\rho}{2R_0} \qquad [74]$$

then the spatial distribution of intensity in the diffraction pattern can be written in a form known as the Airy formula,

$$I = I_0\left[\frac{2\mathrm{J}_1(u)}{u}\right]^2 \qquad [75]$$

where we have defined

$$I_0 = \left(\frac{\alpha A}{\lambda R_0}\right)^2 \qquad [76]$$

with A representing the area of the aperture, $A = \pi(\frac{a}{2})^2$.

The intensity pattern described by [75] is called the Airy pattern. The intensity at $u = 0$ is the same as was obtained for a rectangular aperture of the same area, because, in the limit,

$$\lim_{u\to 0}\left[\frac{2\mathrm{J}_1(u)}{u}\right] = 1 \qquad [77]$$

For the Airy pattern, 84% of the total area is contained in the disk between the first zeros of [75]. Those zeros occur at $u = \pm 1.22\pi$, which corresponds



Figure 7 Amplitude of a wave diffracted by a circular aperture. The observed light distribution is constructed by rotating this Bessel function around the optical axis. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

to a radius in the observation plane of

$$\rho = \frac{1.22(\lambda R_0)}{a} \qquad [78]$$

91% of the light intensity is contained within the circle bounded by the second minimum at $u = 2.233\pi$. The intensities in the secondary maxima of the diffraction pattern of a rectangular aperture [53] are much larger than the intensities in the secondary maxima of the Airy pattern of a circular aperture of equal area. The peak intensities, relative to the central maximum, of the first three secondary maxima of a rectangular aperture are 4.7%, 1.6%, and 0.8%, respectively. For a circular aperture, the same quantities are 1.7%, 0.04%, and 0.02%, respectively.

Array Theorem

There is an elegant mathematical technique for handling diffraction from multiple apertures, called the array theorem. The theorem is based on the fact that Fraunhofer diffraction is given by the Fourier transform of the aperture function and utilizes the convolution integral.

The convolution of the functions $a(t)$ and $b(t)$ is defined as

$$g(t) = a(t) \otimes b(t) = \int_{-\infty}^{\infty} a(t)b(\tau - t)\,\mathrm{d}t \qquad [79]$$

The Fourier transform of a convolution of two functions is the product of the Fourier transforms of



Figure 8 The convolution of an aperture with an array of delta functions will produce an array of identical apertures, each located at the position of one of the delta functions. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

the individual functions:

$$\mathcal{F}\{a(t) \otimes b(t)\} = \mathcal{F}\left\{\int_{-\infty}^{\infty} a(t)b(\tau - t)\,\mathrm{d}t\right\} = A(\omega)B(\omega) \qquad [80]$$

We will demonstrate the array theorem for one dimension, where the functions represent slit apertures. The results can be extended to two dimensions in a straightforward way.

Assume that we have a collection of identical apertures, shown on the right of Figure 8. If one of the apertures is located at the origin of the aperture plane, its transmission function is $\psi(x)$. The transmission function of an aperture located at a point, x_n, can be written in terms of a generalized aperture function, $\psi(x - \alpha)$, by the use of the sifting property of the delta function

$$\psi(x - x_n) = \int \psi(x - \alpha)\delta(\alpha - x_n)\,\mathrm{d}\alpha \qquad [81]$$

The aperture transmission function representing an array of apertures will be the sum of the distributions of the individual apertures, represented graphically in Figure 8 and mathematically by the summation

$$\Psi(x) = \sum_{n=1}^{N} \psi(x - x_n) \qquad [82]$$

The Fraunhofer diffraction from this array is $\Phi(\omega_x)$, the Fourier transform of $\Psi(x)$,

$$\Phi(\omega_x) = \int_{-\infty}^{\infty} \Psi(x) \mathrm{e}^{-\mathrm{i}\omega_x x}\, \mathrm{d}x \qquad [83]$$

which can be rewritten as

$$\Phi(\omega_x) = \sum_{n=1}^{N} \int_{-\infty}^{\infty} \psi(x - x_n) \mathrm{e}^{-\mathrm{i}\omega_x x}\, \mathrm{d}x \qquad [84]$$

We now make use of the fact that $\psi(x - x_n)$ can be expressed in terms of a convolution integral. The Fourier transform of $\psi(x - x_n)$ is, from the convolution theorem [80], the product of the Fourier transforms of the individual functions that make up the convolution:

$$\begin{aligned}\Phi(\omega_x) &= \sum_{n=1}^{N} \mathcal{F}\{\psi(x-\alpha)\}\mathcal{F}\{\delta(\alpha - x_n)\}\\ &= \mathcal{F}\{\psi(x-\alpha)\} \sum_{n=1}^{N} \mathcal{F}\{\delta(\alpha - x_n)\}\\ &= \mathcal{F}\{\psi(x-\alpha)\}\mathcal{F}\left\{\sum_{n=1}^{N} \delta(\alpha - x_n)\right\} \qquad [85]\end{aligned}$$

The first transform in [85] is the diffraction pattern of the generalized aperture function and the second transform is the diffraction pattern produced by a set of point sources with the same spatial distribution as the array of identical apertures. We will call this second transform the array function.

To summarize, the array theorem states that the diffraction pattern of an array of similar apertures is given by the product of the diffraction pattern from a single aperture and the diffraction (or interference) pattern of an identically distributed array of point sources.

N Rectangular Slits

An array of N identical apertures is called a diffraction grating in optics. The Fraunhofer diffraction patterns produced by such an array have two important properties; a number of very narrow beams are produced by the array and the beam positions are a function of the wavelength of illumination of the apertures and the relative phase of the waves radiated by each of the apertures.

Because of these properties, arrays of diffracting apertures have been used in a number of applications.

- At radio frequencies, arrays of dipole antennas are used to both radiate and receive signals in both radar and radio astronomy systems. One advantage offered by diffracting arrays at radio frequencies is that the beam produced by the array can be electrically steered by adjusting the relative phase of the individual dipoles.
- An optical realization of a two-element array of radiators is Young's two-slit experiment and a realization of a two-element array of receivers is Michelson's stellar interferometer. Two optical implementations of arrays, containing more diffracting elements, are diffraction gratings and holograms. In nature, periodic arrays of diffracting elements are the origin of the colors observed on some invertebrates.
- Many solids are naturally arranged in three-dimensional arrays of atoms or molecules that act as diffraction gratings when illuminated by X-ray wavelengths. The resulting Fraunhofer diffraction patterns are used to analyze the ordered structure of the solids.

The array theorem can be used to calculate the diffraction pattern from N rectangular slits, each of width a and separation d. The aperture function of a single slit is equal to

$$\psi(x, y) = \begin{cases} 1 & |x| \le \frac{a}{2}, |y| \le y_0 \\ 0 & \text{all other } x \text{ and } y \end{cases} \qquad [86]$$

The Fraunhofer diffraction pattern of this aperture has already been calculated and is given by [52]:

$$\mathcal{F}\{\psi(x, y)\} = K \frac{\sin \alpha}{\alpha} \qquad [87]$$

where the constant K and the variable α are

$$\begin{aligned} K &= \frac{\mathrm{i}2ay_0\alpha}{\lambda R_0} \mathrm{e}^{-\mathrm{i}\mathbf{k}\cdot\mathbf{R}_0} \frac{\sin \omega_y y_0}{\omega_y y_0}\\ \alpha &= \frac{ka}{2} \sin \theta_x \qquad [88]\end{aligned}$$

The array function is

$$A(x) = \sum_{n=1}^{N} \delta(x - x_n) \quad \text{where } x_n = (n-1)d \qquad [89]$$

and its Fourier transform is given by

$$\mathcal{F}\{A(x)\} = \frac{\sin N\beta}{\sin \beta} \qquad [90]$$

$$\beta = \frac{kd}{2} \sin \theta_x$$

The Fraunhofer diffraction pattern's intensity distribution in the x-direction is thus given by

$$I_\theta = I_0 \underbrace{\frac{\sin^2\alpha}{\alpha^2}}_{\text{shape factor}} \underbrace{\frac{\sin^2 N\beta}{\sin^2\beta}}_{\text{grating factor}} \qquad [91]$$

We have combined the variation in intensity in the y-direction into the constant I_0 because we assume that the intensity variation in the x-direction will be measured at a constant value of y.

A physical interpretation of [91] views the first factor as arising from the diffraction associated with a single slit; it is called the shape factor. The second factor arises from the interference between light from different slits; it is called the grating factor. The fine detail in the spatial light distribution of the diffraction pattern is described by the grating factor and arises from the coarse detail in the diffracting object. The coarse, overall light distribution in the diffraction pattern is described by the shape factor and arises from the fine detail in the diffracting object.

Young's Double Slit

The array theorem makes the analysis of Young's two-slit experiment a trivial exercise. This application of the array theorem will demonstrate that the interference between two slits arises naturally from an application of diffraction theory. The result of this analysis will support a previous assertion that interference describes the same physical process as diffraction and the division of the two subjects is an arbitrary one.

The intensity of the diffraction pattern from two slits is obtained from [91] by setting $N = 2$:

$$I_\theta = I_0 \frac{\sin^2\alpha}{\alpha^2} \cos^2\beta \qquad [92]$$

The sinc function describes the energy distribution of the overall diffraction pattern, while the cosine function describes the energy distribution created by interference between the light waves from the two slits. Physically, α is a measure of the phase difference between points in one slit and β is a measure of the phase difference between similar points in the two slits. Zeros in the diffraction intensity occur whenever $\alpha = n\pi$ or whenever $\beta = \frac{1}{2}(2n+1)\pi$. Figure 9 shows the interference maxima, from the grating factor, under the central diffraction peak, described by the shape factor. The number of interference maxima contained under the central maximum is given by

$$\frac{2d}{a} - 1 \qquad [93]$$

In Figure 9 three different slit spacings are shown with the ratio d/a equal to 3, 6, and 9, respectively.

The Diffraction Grating

In this section we will use the array theorem to derive the diffraction intensity distribution of a large number of identical apertures. We will discover that the positions of the principal maxima are a function of the illuminating wavelength. This functional relationship has led to the application of a diffraction grating to wavelength measurements.

The diffraction grating normally used for wavelength measurements is not a large number of diffracting apertures but rather a large number of reflecting grooves cut in a surface such as gold or aluminum. The theory to be derived also applies to these reflection gratings but a modification must be made to the theory. The shape of the grooves in the reflection grating can be used to control the fraction of light diffracted into a principal maximum and we will examine how to take this into account. A grating whose groove shape has been controlled to enhance the energy contained in a particular principal maximum is called a blazed grating. The use of special groove shapes is equivalent to the modification of the phase of individual elements of an antenna array at radio frequencies.

The construction of a diffraction grating for use in an optical device for measuring wavelength was first suggested by David Rittenhouse, an American astronomer, in 1785, but the idea was ignored until Fraunhofer reinvented the concept in 1819. Fraunhofer's first gratings were fine wires spaced by wrapping the wires in the threads of two parallel screws. He later made gratings by cutting (*ruling*) grooves in gold films deposited on the surface of glass. H.A. Rowland made a number of well designed ruling machines, which made possible the production of large-area gratings. Following a suggestion by Lord Rayleigh, Robert Williams Wood (1868–1955) developed the capability to control the shape of the individual grooves.



Figure 9 The number of interference fringes beneath the main diffraction peak of a Young's two-slit experiment with rectangular apertures. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

If N is allowed to assume values much larger than 2, the appearance of the interference fringes, predicted by the grating factor, changes from a simple sinusoidal variation to a set of narrow maxima, called principal maxima, surrounded by much smaller, secondary maxima. To calculate the diffraction pattern we must evaluate [91] when N is a large number.

Whenever $N\beta = m\pi$, $m = 0, 1, 2, \ldots$, the numerator of the second factor in [91] will be zero, leading to an intensity that is zero, $I_\theta = 0$. The denominator of the second factor in [91] is zero when $\beta = l\pi$, $l = 0, 1, 2, \ldots$ If both conditions occur at the same time, the ratio of m and N is equal to an integer, $m/N = l$, and instead of zero intensity, we have an indeterminate value for the intensity, $I_\theta = 0/0$. To find the actual value for the intensity, we must apply L'Hospital's rule

$$\lim_{\beta\to l\pi} \frac{\sin N\beta}{\sin\beta} = \lim_{\beta\to l\pi} \frac{N\cos N\beta}{\cos\beta} = N \qquad [94]$$

L'Hospital's rule predicts that whenever

$$\beta = l\pi = \frac{m}{N}\pi \qquad [95]$$

where l is an integer, a principal maximum in the intensity will occur with a value given by

$$I_{\theta P} = N^2 I_0 \frac{\sin^2\alpha}{\alpha^2} \qquad [96]$$

Secondary maxima, much weaker than the principal maxima, occur when

$$\beta = \left(\frac{2m+1}{2N}\right)\pi \qquad m = 1, 2, \ldots \qquad [97]$$

(When $m = 0$, m/N is an integer, thus the first value that m can have in [97] is $m = 1$.) The intensity of each secondary maximum is given by

$$\begin{aligned} I_{\theta S} &= I_0 \frac{\sin^2\alpha}{\alpha^2}\frac{\sin^2 N\beta}{\sin^2\beta} \\ &= I_0 \frac{\sin^2\alpha}{\alpha^2}\left[\frac{\sin^2\left(\frac{2m+1}{2}\right)\pi}{\sin^2\left(\frac{2m+1}{2N}\right)\pi}\right] \\ &= I_0 \frac{\sin^2\alpha}{\alpha^2}\left[\frac{1}{\sin\left(\frac{2m+1}{2N}\right)\pi}\right]^2 \end{aligned} \qquad [98]$$

The quantity $(2m+1)/2N$ is a small number for large values of N, allowing the small angle approximation to be made:

$$I_{\theta S} \approx I_0 \frac{\sin^2\alpha}{\alpha^2}\left[\frac{2N}{\pi(2m+1)}\right]^2 \qquad [99]$$

The ratio of the intensity of a secondary maximum and a principal maximum is given by

$$\frac{I_{\theta S}}{I_{\theta P}} = \left[\frac{2}{\pi(2m+1)}\right]^2 \qquad [100]$$

The strongest secondary maximum occurs for $m = 1$ and, for large N, has an intensity that is about 4.5% of the intensity of the neighboring principal maximum.

The positions of principal maxima occur at angles specified by the grating formula.

$$\beta = \frac{kd \sin\theta}{2} = l\pi = \frac{m}{N}\pi \qquad [101]$$

The angular position of the principal maxima (the diffracted angle θ_d) is given by the Bragg equation

$$\sin\theta_d = \frac{l\lambda}{d} \qquad [102]$$

where l is called the grating order. This simple relationship between the angle and the wavelength can be used to construct a device to measure wavelength, the grating spectrometer.

The model we have used to obtain this result is based on a periodic array of identical apertures. The transmission function of this array is a periodic square wave. If, for the moment, we treat the grating as infinite in size, we discover that the principal maxima in the diffraction pattern correspond to the terms of the Fourier series describing a square wave.

The zero order, $m = 0$, corresponds to the temporal average of the periodic square wave and has an intensity proportional to the spatially averaged transmission of the grating. Because of its equivalence to the temporal average of a time-varying signal, the zero-order principal maximum is often called the dc term.

The first-order principal maximum corresponds to the fundamental spatial frequency of the grating and the higher orders correspond to the harmonics of this frequency.

The dc term provides no information about the wavelength of the illumination. Information about the wavelength of the illuminating light can only be obtained by measuring the angular position of the first or higher order principal maxima.

Grating Spectrometer

The curves shown in Figure 10 display the separation of the principal maxima as a function of $\sin\theta_d$. The angular separation of principal maxima can be converted to a linear dimension by assuming a distance, R, from the graing to the observation plane. In the lower right-hand curve of Figure 10, a distance of 2 meters was assumed. Grating spectrometers are classified by the size in meters of R used in their design. The larger R, the easier it is to resolve wavelength differences. For example, a 1 meter spectrometer is a higher-resolution instrument than a 1/4 meter spectrometer.

The fact that the grating is finite in size causes each of the orders to have an angular width that limits the resolution with which the illuminating wavelength can be measured. To calculate the resolving power of the grating, we first determine the angular width of a principal maximum. This is accomplished by measuring the angular change, of the principal maximum's position, when β changes from $\beta = l\pi = m\pi/N$ to $\beta = (m+1)\pi/N$, i.e., $\Delta\beta = \pi/N$. Using the definition of β

$$\beta = \frac{kd \sin\theta_d}{2} \qquad [103]$$

$$\Delta\beta = \frac{\pi d \cos\theta_d \Delta\theta}{\lambda}$$

and the angular width is

$$\Delta\theta = \frac{\lambda}{Nd \cos\theta_d} \qquad [104]$$

The derivative of the grating formula gives

$$\Delta\lambda = \frac{d}{l}\cos\theta_d \Delta\theta \qquad [105]$$

$$\Delta\theta = \frac{l\Delta\lambda}{d \cos\theta_d}$$

Equating this spread in angle to eqn [104] yields

$$\frac{l\Delta\lambda}{d\cos\theta} = \frac{\lambda}{Nd\cos\theta} \qquad [106]$$

The resolving power of a grating is therefore

$$\frac{\lambda}{\Delta\lambda} = Nl \qquad [107]$$

The improvement of resolving power with N can be seen in Figure 10. A grating 2 inches wide and containing 15 000 grooves per inch would have a resolving power in second order ($l = 2$) of 6×10^4. At a wavelength of 600 nm this grating could resolve two waves, differing in wavelength by 0.01 nm.

The diffraction grating is limited by overlapping orders. If two wavelengths, λ and $\lambda + \Delta\lambda$, have successive orders that are coincident, then



Figure 10 Decrease in the width of the principal maxima of a transmission grating with an increasing number of slits. The various principal maxima are called orders, numbering from zero, at the origin, out to as large as seven in this example. Also shown is the effect of different ratios, *d/a*, on the number of visible orders. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

from eqn [102]

$$(l+1)\lambda = l(\lambda + \Delta\lambda) \qquad [108]$$

The minimum wavelength difference for which this occurs is defined as the free spectral range of the diffraction grating

$$(\Delta\lambda)_{\mathrm{SR}} = \frac{\lambda}{l} \qquad [109]$$

Blazed Gratings

We have been discussing amplitude transmission gratings. Amplitude transmission gratings have little practical use because they waste light. The light loss is from a number of sources.

1. Light is diffracted simultaneously into both positive and negative orders (the positive and negative frequencies of the Fourier transform). The negative diffraction orders contain redundant information and waste light.
2. In an amplitude transmission grating, light is thrown away because of the opaque portions of the slit array.
3. The width of an individual aperture leads to a shape factor for a rectangular aperture of $\mathrm{sinc}^2\alpha = (\sin^2\alpha)/\alpha^2$, which modulates the grating factor and causes the amplitude of the orders to rapidly decrease. This can be observed in **Figure 10**, where the second order is very weak. Because of the loss in intensity at higher orders, only the first few orders ($l = 1, 2$ or 3) are useful. The shape factor also causes a decrease in diffracted light intensity with increasing wavelength for higher-order principal maxima.
4. The location of the maximum in the diffracted light, i.e., the angular position for which the shape factor is a maximum, coincides with the location of the principal maximum due to the zero-order interference. This zero-order maximum is independent of wavelength and is not of much use.

One solution to the problems created by transmission gratings would be the use of a grating that modified only the phase of the transmitted wave. Such gratings would operate using the same physical processes as a microwave phased array antenna, where the location of the shape factor's maximum is controlled by adding a constant phase shift to each antenna element. The construction of an optical transmission phase grating with a uniform phase variation across the aperture of the grating is very difficult. For this reason, a second approach, based on the use of reflection gratings, is the practical solution to the problems listed above.

By tilting the reflecting surface of each groove of a reflection grating, Figure 11, the position of the shape factor's maximum can be controlled. Problems 1, 3, and 4 are eliminated because the shape factor maximum is moved from the optical axis out to some angle with respect to the axis. The use of reflection gratings also removes Problem 2 because all of the incident light is reflected by the grating.

Robert Wood, in 1910, developed the technique of producing grooves of a desired shape in a reflective grating by shaping the diamond tool used to cut the grooves. Gratings, with grooves shaped to enhance their performance at a particular wavelength, are said to be blazed for that wavelength. The physical properties on which blazed gratings are based can be understood by using Figure 11. The groove faces can be treated as an array of mirror surfaces. The normal to each of the groove faces makes an angle θ_B with the normal to the grating surface. We can measure the angle of incidence and the angle of diffraction with respect to the grating normal or with respect to the groove normal, as shown in Figure 11. From Figure 11, we can write a relationship between the angles

$$\theta_i = \varphi_i - \theta_B \qquad -\theta_d = -\varphi_d + \theta_B \tag{110}$$

(The sign convention used defines positive angles as those measured in a counterclockwise rotation from the normal to the surface. Therefore, θ_B is a negative angle.) The blaze angle provides an extra degree of freedom that will allow independent adjustment of the angular location of the principal maxima of the grating factor and the zero-order, single-aperture, diffraction maximum. To see how this is accomplished, we must determine, first, the effect of off-axis illumination of a diffraction grating.



Figure 11 Geometry for a blazed reflection grating. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

Off-axis illumination is easy to incorporate into the equation for the diffraction intensity from an array. To include the effect of an off-axis source, the phase of the illuminating wave is modified by changing the incident illumination from a plane wave of amplitude, E, traveling parallel to the optical axis, to a plane wave with the same amplitude, traveling at an angle θ_i to the optical axis: $\tilde{E}\,e^{-ikx\sin\theta_i}$. (Because we are interested only in the effects in a plane normal to the direction of propagation, we ignore the phase associated with propagation along the z-direction, $kz\cos\theta_i$.) The off-axis illumination results in a modification of the parameter for single-aperture diffraction from

$$\alpha = \frac{ka}{2}\sin\theta_d \tag{111}$$

to

$$\alpha = \frac{ka}{2}(\sin\theta_i + \sin\theta_d) \tag{112}$$

and for multiple aperture interference from

$$\beta = \frac{kd}{2}\sin\theta_d \tag{113}$$

to

$$\beta = \frac{kd}{2}(\sin\theta_i + \sin\theta_d) \tag{114}$$

The zero-order, single-aperture, diffraction peak occurs when $\alpha = 0$. If we measure the angles with respect to the groove face, this occurs when

$$\alpha = \frac{ka}{2}(\sin\varphi_i + \sin\varphi_d) = 0 \tag{115}$$

The angles are therefore related by

$$\sin\varphi_i = -\sin\varphi_d \tag{116}$$

$$\varphi_i = -\varphi_d$$

We see that the single-aperture, diffraction maximum (the shape factor's maximum) occurs at the same angle that reflection from the groove faces occurs. We can write this result in terms of the angles measured with respect to the grating normal

$$\theta_i = -(\theta_d + 2\theta_B) \tag{117}$$

The blaze condition requires the single aperture diffraction maximum to occur at the lth principal maximum, for wavelength λ_B. At that position

$$l\pi = \frac{2\pi d}{\lambda_B}(\sin\theta_i + \sin\theta_d) \qquad [118]$$

$$l\lambda_B = 2d\sin\tfrac{1}{2}(\theta_i + \theta_d)\cos\tfrac{1}{2}(\theta_i - \theta_d)$$

For the special geometrical configuration called the Littrow condition, where $\theta_i = \theta_d$, we find that [117] leads to the equation

$$l\lambda_B = 2d\sin\theta_B \qquad [119]$$

By adjusting the blaze angle, the single-aperture diffraction peak can be positioned on any order of the interference pattern. Typical blaze angles are between 15° and 30° but gratings are made with larger blaze angles.

See also

Diffraction: Fresnel Diffraction.

Further Reading

Born M and Wolf E (1970) *Principles of Optics*. New York: Pergamon Press.

Guenther RD (1990) *Modern Optics*. New York: Wiley.

Haus HA (1984) *Waves and Fields in Optoelectronics*. Englewood Cliffs, NJ: Prentice-Hall.

Hecht E (1998) *Optics*. 3rd edn. Reading, MA: Addison-Wesley.

Jackson JD (1962) *Classical Electrodynamics*. New York: Wiley.

Klein MV (1970) *Optics*. New York: Wiley.

O'Neill EL (1963) *Introduction to Statistical Optics*. Reading, MA: Addison-Wesley.

Rossi B (1957) *Optics*. Reading, MA: Addison-Wesley.

Rubinowicz A (1984) Tahe Miyamoto–Wolf diffraction wave. In: Wolf E (ed.) *Progress in Optics*, vol. IV, p. 201. Amsterdam: North-Holland.

Sommerfeld A (1964) *Optics*. New York: Academic Press.

Stone JM (1963) *Radiation and Optics*. New York: McGraw-Hill.

Fresnel Diffraction

B D Guenther, Duke University, Durham, NC, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Fresnel was a civil engineer who pursued optics as a hobby, after a long day of road construction. Based on his own very high-quality observations of diffraction, Fresnel used the wave propagation concept developed by Christiaan Huygens (1629–1695) to develop a theoretical explanation of diffraction. We will use a descriptive approach to obtain the Huygens–Fresnel integral by assuming an aperture can be described by N pinholes which act as sources for Huygens' wavelets. The interference between these sources will lead to the Huygens–Fresnel integral for diffraction.

Huygens' principle views wavefronts as the product of wavelets from various luminous points acting together. To apply Huygens' principle to the propagation of light through an aperture of arbitrary shape, we need to develop a mathematical description of the field from an array of Huygens' sources filling the aperture. We will begin by obtaining the field from a pinhole that is illuminated by a plane wave,

$$\tilde{\mathrm{E}}_i(\mathbf{r}, t) = \tilde{\mathrm{E}}_i(\mathbf{r})e^{i\omega t}$$

Following the lead of Fresnel, we will use theory of interference to combine the fields from two pinholes and then generalize to N pinholes. Finally by letting the areas of each pinhole approach an infinitesimal value, we will construct an arbitrary aperture of infinitesimal pinholes. The result will be the Huygens–Fresnel integral.

We know that the wave obtained after propagation through an aperture must be a solution of the wave equation,

$$\nabla^2\tilde{\mathrm{E}} = \mu\varepsilon\frac{\partial^2\tilde{\mathrm{E}}}{\partial t^2}$$

We will be interested only in the spatial variation of the wave so we need only look for solutions of the Helmholtz equation

$$(\nabla^2 + k^2)\tilde{\mathrm{E}} = 0$$

The problem is further simplified by replacing this vector equation with a scalar equation,

$$(\nabla^2 + k^2)\tilde{E}(x, y, z) = 0$$

This replacement is proper for those cases where $\mathbf{n}E(x,y,z)$ [where $\mathbf{n}$ is a unit vector] is a solution of the vector Helmholtz equation. In general, we cannot substitute $\mathbf{n}E$ for the electric field $\mathbf{E}$ because of Maxwell's equation

$$\nabla\cdot\mathbf{E} = 0$$



Figure 1 Geometry for application of Huygens' principle to two pinholes. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.



Figure 2 The geometry for calculating the field at P_0 using [9]. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

Rather than working with the magnitude of the electric field, we should use the scalar amplitude of the vector potential. We will neglect this complication and assume the scalar, E, is a single component of the vector field, $\mathbf{E}$. A complete solution would involve a scalar solution for each component of $\mathbf{E}$.

The pinhole is illuminated by a plane wave, and the wave that leaves the pinhole will be a spherical wave which is written in complex notation as

$$\tilde{E}(\mathbf{r})e^{i\omega t} = A\frac{e^{-i\delta}e^{-ik\cdot r}}{r}e^{i\omega t}$$

The complex amplitude

$$\tilde{E}(\mathbf{r}) = A\frac{e^{-i\delta}e^{-ik\cdot r}}{r} \qquad [1]$$

is a solution of the Helmholtz equation. The field at P_0, in Figure 1, from two pinholes: one at P_1, located a distance $\mathbf{r}_{01} = |\mathbf{r}_0 - \mathbf{r}_1|$ from P_0, and one at P_2, located a distance $\mathbf{r}_{02} = |\mathbf{r}_0 - \mathbf{r}_2|$ from P_0, is a generalization of Young's interference. The complex amplitude is

$$\tilde{E}(\mathbf{r}_0) = \frac{A_1}{r_{01}}e^{-ik\cdot r_{01}} + \frac{A_2}{r_{02}}e^{-ik\cdot r_{02}} \qquad [2]$$

We have incorporated the phase δ_1 and δ_2 into the constants A_1 and A_2 to simplify the equations.

The light emitted from the pinholes is due to a wave, E_i, incident onto the screen from the left. The units of E_i are per unit area so to obtain the amount of light passing through the pinholes, we must multiply E_i by the areas of the pinholes. If $\Delta\sigma_1$ and $\Delta\sigma_2$ are the areas of the two pinholes, respectively, then

$$A_1 \propto \tilde{E}_i(\mathbf{r}_1)\Delta\sigma_1 \qquad A_2 \propto \tilde{E}_i(\mathbf{r}_2)\Delta\sigma_2$$

$$\tilde{E}(\mathbf{r}_0) = C_1\frac{\tilde{E}_i(\mathbf{r}_1)}{r_{01}}e^{-ik\cdot r_{01}}\Delta\sigma_1 + C_2\frac{\tilde{E}_i(\mathbf{r}_2)}{r_{02}}e^{-ik\cdot r_{02}}\Delta\sigma_2 \qquad [3]$$

where C_i is the constant of proportionality. The constant will depend on the angle that $\mathbf{r}_{0i}$ makes with the normal to $\Delta\sigma_i$. This geometrical dependence arises from the fact that the apparent area of the pinhole decreases as the observation angle approaches 90°.

We can generalize [3] to N pinholes

$$\tilde{E}(\mathbf{r}_0) = \sum_{j=1}^{N} C_j\frac{\tilde{E}_i(\mathbf{r}_j)}{r_{0j}}e^{-ik\cdot r_{0j}}\Delta\sigma_j \qquad [4]$$

The pinhole's diameter is assumed to be small compared to the distances to the viewing position but large compared to a wavelength. In the limit as $\Delta\sigma_j$ goes to zero, the pinhole becomes a Huygens source. By letting N become large, we can fill the aperture with these infinitesimal Huygens' sources and convert the summation to an integral.

It is in this way that we obtain the complex amplitude, at the point P_0, see Figure 2, from a wave exiting an aperture, Σ_0, by integrating over the area of the aperture. We replace $\mathbf{r}_{0j}$, in [4], by $\mathbf{R}$, the position of P_1, the infinitesimal Huygens' source of area, ds, measured with respect to the observation point, P_0. We also replace $\mathbf{r}_j$ by $\mathbf{r}$, the position of the infinitesimal area, ds, with respect to the origin of the coordinate system. The discrete summation [4] becomes the integral

$$\tilde{E}(\mathbf{r}_0) = \iint_A C(\mathbf{r})\frac{\tilde{E}_i(\mathbf{r})}{R}e^{-ik\cdot\mathbf{R}}ds \qquad [5]$$

This is the Fresnel integral. The variable $C(\mathbf{r})$ depends upon θ, the angle between $\mathbf{n}$, the unit vector normal to the aperture, and $\mathbf{R}$, shown in Figure 2. We now need to determine how to treat $C(\mathbf{r})$.

The Obliquity Factor

When using Huygens' principle, a problem arises with the spherical wavelet produced by each

Huygens' source. Part of the spherical wavelet propagates backward and results in an envelope propagating toward the light source, but such a wave is not observed in nature. Huygens neglected this problem. Fresnel required the existence of an obliquity factor to cancel the backward wavelet but was unable to derive its functional form. When Kirchhoff placed the theory of diffraction on a firm mathematical foundation, the obliquity factor was generated quite naturally in the derivation. In this intuitive derivation of the Huygens–Fresnel integral, we will present an argument for treating the obliquity factor as a constant at optical wavelengths. We will then derive the constant value it must be assigned.

The obliquity factor, $C(\mathbf{r})$, in [5], causes the amplitude per unit area of the transmitted light to decrease as the viewing angle increases. This is a result of a decrease in the effective aperture area with viewing angle. When Kirchhoff applied Green's theorem to the scalar diffraction problem, he found the obliquity factor to have an angular dependence given by

$$\frac{\cos(\hat{\mathbf{n}},\mathbf{R}) - \cos(\hat{\mathbf{n}},\mathbf{r}_s)}{2} \qquad [6]$$

which includes the geometrical effect of the incident wave arriving at the aperture, at an angle with respect to the normal to the aperture from a source located at a position $\mathbf{r}_s$, with respect to the aperture. If the source is at infinity, then the incident wave can be treated as a plane wave, incident normal to the aperture, and we may simplify the angular dependence of the obliquity factor to

$$\frac{1+\cos\theta}{2}$$

where $\theta \rightarrow (\hat{\mathbf{n}},\mathbf{R})$ is the angle between the normal to the aperture and the vector $\mathbf{R}$. This is the configuration shown in Figure 2. The obliquity factor provides an explanation of why it is possible to ignore the backward-propagating wave that occurs in application of Huygens' principle. For the backward wave, $\theta = \pi$, and the obliquity factor is zero.

The obliquity factor increases the difficulty of working with the Fresnel integral and it is to our benefit to be able to treat it as a constant. We can neglect the angular contribution of the obliquity factor by making an assumption about the resolving power of an optical system operating at visible wavelengths.

Assume we are attempting to resolve two stars that produce plane waves at the aperture of a telescope with an aperture diameter, a. The wavefronts from the two stars make an angle ψ with respect to each other, Figure 3:

$$\tan\psi \approx \psi = \frac{\Delta x}{a}$$

The smallest angle, ψ, that can be measured is determined by the smallest length, Δx, that can be measured. We know we can measure a fraction of wavelength with an interferometer but, without an interferometer, we can measure a length no smaller than λ, leading to the assumption that $\Delta x \geq \lambda$. This reasoning leads to the assumption that the smallest angle we can measure is

$$\psi \geq \frac{\lambda}{a} \qquad [7]$$

The resolution limit established by the above reasoning places a limit on the minimum separation that can be produced at the back focal plane of the telescope. The minimum distance on the focal plane between the images of star 1 and 2 is given by

$$d = f\psi \qquad [8]$$

From [7]

$$d = \frac{\lambda f}{a}$$

The resolution limit of the telescope can also be expressed in terms of the cone angle produced when the incident plane wave is focused on the back focal plane of the lens. From the geometry of Figure 3, the cone angle is given by

$$\tan\theta = \frac{a}{2f}$$



Figure 3 Telescope resolution. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

The separation between the stars 1 and 2 at the back focal plane of the lens in Figure 3 is thus

$$d = \frac{\lambda}{2 \tan \theta} \qquad [9]$$

If we assume that the minimum d is 3λ (this is four times the resolution of a typical photographic film at visible wavelengths), then the largest obliquity angle that should be encountered in a visible imaging system is

$$\tan \theta = \frac{\lambda}{2d} = \frac{\lambda}{6\lambda} = \tfrac{1}{6} = 0.167$$

$$\theta = 9.5^\circ \approx 10^\circ$$

yielding a value for $\cos \theta = 0.985$ and $(1 + \cos \theta)/2 = 0.992$. The obliquity factor has only changed by 0.8% over the angular variation of 0° to 10°. The obliquity factor as a function of angle is shown in Figure 4 for an incident plane wave. The obliquity factor undergoes a 10% change when θ varies from 0° to about 40°; therefore, the obliquity factor can safely be treated as a constant in any optical system that involves angles less than 40°.

While we have shown that it is safe to ignore the variability of C, we still have not assigned a value to the obliquity factor. To find the proper value for C, we will compare the result obtained using [5] with the result predicted by using geometric optics.

We illuminate the aperture Σ_0 in Figure 5 with a plane wave of amplitude α, traveling parallel to the z-axis. Geometrical optics (equivalently the propagation of an infinite plane wave) predicts a field at P_0, on the z-axis, a distance z_0 from the aperture, given by

$$\tilde{E}_{\text{geom}} = \alpha e^{-ikz_0} \qquad [10]$$

The area of the infinitesimal at P_1 (the Huygens' source) is

$$ds = r \, dr \, d\phi$$



Figure 4 The obliquity factor as a function of the angle defined in eqn [6] for an incident plane wave. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.



Figure 5 Geometry for evaluating the constant in the Fresnel integral. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

Based on our previous argument, the obliquity factor can be treated as a constant, C, that can be removed from under the integral. The incident wave is a plane wave whose value at $z = 0$ is $E(r) = \alpha$. Using these parameters, the Fresnel integral [5] can be written as

$$\tilde{E}(z_0) = C\alpha \iint \frac{e^{-ik \cdot R}}{R} r \, dr \, d\phi \qquad [11]$$

From the geometry in Figure 5, the distance from the Huygens source to the observation point is

$$z_0^2 + r^2 = R^2$$

where z_0 is a constant equal to the distance from the observation plane to the aperture plane. The variable of integration can be written in terms of R:

$$r \, dr = R \, dR$$

The limits of integration over the aperture extend from $R = z_0$ to the maximum value of R, $R = R_M(\phi)$.

$$\tilde{E}(z_0) = C\alpha \int_0^{2\pi} \int_{z_0}^{R_M(\phi)} e^{-ikR} dR \, d\phi \qquad [12]$$

The integration over R can now be carried out to yield

$$\tilde{E}(z_0) = \underbrace{\frac{C\alpha}{ik} e^{-ikz_0} \int_0^{2\pi} d\phi}_{\text{Geometrical Optics}} - \underbrace{\frac{C\alpha}{ik} \int_0^{2\pi} e^{-ikR_M(\phi)} d\phi}_{\text{Diffraction}} \qquad [13]$$

The first integration in [13] is easy to perform and contains the amplitude at the observation point due to geometric optics. The second term may be interpreted as interference of the waves diffracted by the boundary of the aperture. An equivalent statement is that the second term is the interference of the waves scattered from the aperture's boundary, an interpretation of diffraction that was first suggested by Young.

The aperture is irregular in shape, at least on the scale of a wavelength, thus in general, kR_M will vary over many multiples of 2π as we integrate around the aperture. For this reason, we should be able to ignore the second integral in [13] if we confine our attention to the light distribution on the z-axis. After neglecting the second term, we are left with only the geometrical optics component of [13]:

$$\tilde{E}(z_0) = \frac{2\pi C}{\mathrm{i}k}\alpha \mathrm{e}^{-\mathrm{i}kz_0} \qquad [14]$$

For [14] to agree with the prediction of geometric optics [10] the constant C must be equal to

$$C = \frac{\mathrm{i}k}{2\pi} = \frac{\mathrm{i}}{\lambda} \qquad [15]$$

The Huygens–Fresnel integral can be written, using the value for C just derived,

$$\tilde{E}(\mathbf{r}_0) = \frac{\mathrm{i}}{\lambda}\int\int_{\Sigma} \frac{\tilde{E}_{\mathrm{i}}(\mathbf{r})}{R}\mathrm{e}^{-\mathrm{i}\mathbf{k}\cdot\mathbf{R}}\,\mathrm{d}s \qquad [16]$$

The job of calculating diffraction has only begun with the derivation of the Huygens–Fresnel integral [16]. Rigorous solutions exist for only a few idealized obstructions. To allow discussion of the general properties of diffraction, it is necessary to use approximate solutions. To determine what type approximations we can make let's look at the light propagation path shown in Figure 6.

For the second term in [13] to contribute to the field at point P_0, in Figure 6, the phase of the exponent that we neglected in [13] must not vary over 2π when the integration is performed over the aperture, i.e.,

$$\Delta = \mathbf{k}\cdot(\mathbf{R}_1 - \mathbf{R}'_1 + \mathbf{R}_2 - \mathbf{R}'_2) < 2\pi$$



Figure 6 One-dimensional slit used to establish Fresnel approximations. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

From the geometry of Figure 6, the two paths from the source, S, to the observation point, P_0, are

$$R_1 + R_2 = \sqrt{z_1^2 + (x_1 + b)^2} + \sqrt{z_2^2 + (x_2 + b)^2}$$

$$R'_1 + R'_2 = \sqrt{z_1^2 + x_1^2} + \sqrt{z_2^2 + x_2^2}$$

By assuming that the aperture, of width b, is small compared to the distances z_1 and z_2, the difference between these distances, Δ, can be rewritten as a binomial expansion of a square root

$$\sqrt{1+b} = 1 + \frac{b}{2} - \frac{b^2}{8} + \ldots \qquad [17]$$

thus

$$\Delta \approx k\left(\frac{x_1}{z_1} + \frac{x_2}{z_2}\right)b + \frac{k}{2}\left(\frac{1}{z_1} + \frac{1}{z_2}\right)b^2 + \ldots \qquad [18]$$

If we assume that the second term of this expansion is small, i.e.,

$$\frac{k}{2}\left(\frac{1}{z_1} + \frac{1}{z_2}\right)b^2 \ll 2\pi$$

$$\frac{b^2}{2}\frac{1}{z_1} + \frac{1}{z_2} < \lambda$$

we see that the phase of the wavefront in the aperture is assumed to have a quadratic dependence upon aperture coordinates. Diffraction predicted by this assumption is called Fresnel diffraction.

To discover the details of the approximation consider Figure 7. In the geometry of Figure 7, the Fresnel integral [16] becomes

$$\tilde{E}_{\mathrm{P}_0} = \frac{\mathrm{i}\alpha}{\lambda}\int\int_{\Sigma} f(x,y)\frac{\mathrm{e}^{-\mathrm{i}\mathrm{k}\cdot(\mathrm{R}+\mathrm{R}')}}{RR'}\mathrm{d}x\,\mathrm{d}y \qquad [19]$$

As we mentioned in our discussion of [13] the integral that adds diffractive effects to the geometrical optics field is nonzero only when the phase of the integrand is stationary. For Fresnel diffraction, we can insure that the phase is nearly constant if R does not differ appreciably from Z, or R' from Z'. This is equivalent to stating that only the wave in the aperture, around a point in Figure 7 labeled **S**, called the stationary point, will contribute to E_{p}. The stationary point, **S**, is the point in the aperture plane where the line, connecting the source and observation positions, intersects the plane. Physically, only light propagating over paths nearly equal to the path predicted by geometrical optics (obtained from Fermat's principle) will contribute to E_{P_0}.



Figure 7 Geometry for Fresnel diffraction. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

The geometry of Figure 7 allows the distances R and R' to be written as

$$R^2 = (x - \xi)^2 + (y - \eta)^2 + Z^2 \qquad [20]$$

$$R'2 = (x_s - x)^2 + (y_s - y)^2 + Z'2$$

To solve these expressions for R and R', we apply the binomial expansion [17] and retain the first two terms:

$$R + R' \approx Z + Z' + \left[\frac{(x-\xi)^2}{2Z} + \frac{(x_s - x)^2}{2Z'}\right] + \left[\frac{(y-\eta)^2}{2Z} + \frac{(y_s - y)^2}{2Z'}\right] \qquad [21]$$

In the denominator of [19], R is replaced by Z and R' by Z'. (By making this replacement, we are implicitly assuming that the amplitudes of the spherical waves are not modified by the differences in propagation distances over the area of integration. This is a reasonable approximation because the two propagation distances are within a few hundred wavelengths of each other). In the exponent, we must use [21], because the phase changes by a large fraction of a wavelength, as we move from point to point in the aperture.

If the wave, incident on the aperture, were a plane wave we can assume $R' = \infty$ and [19] becomes

$$\tilde{E}_{P_0} = \frac{i\alpha}{\lambda}\,\frac{e^{-ikZ}}{Z}\int\!\!\int_{\Sigma} f(x,y)\,e^{-\frac{ik}{2Z}[(x-\xi)^2+(y-\eta)^2]}\,dx\,dy \qquad [22]$$

The physical interpretation of [22] states that when a plane wave illuminates the obstruction, the field at point P_0 is a spherical wave, originating at the aperture, a distance Z away from P_0:

$$\frac{e^{-ikZ}}{Z}$$

The amplitude and phase of this spherical wave are modified by the integral containing a quadratic phase dependent on the obstruction's spatial coordinates.

By defining three new parameters,

$$\rho = \frac{ZZ'}{Z + Z'} \quad \text{or} \quad \frac{1}{\rho} = \frac{1}{Z} + \frac{1}{Z'} \qquad [23a]$$

$$x_0 = \frac{Z'\xi + Zx_s}{Z + Z'} \qquad [23b]$$

$$y_0 = \frac{Z'\eta + Zy_s}{Z + Z'} \qquad [23c]$$

the more general expression for Fresnel diffraction of a spherical wave can be placed in the same format as [22]. The newly defined parameters x_0 and y_0 are the coordinates, in the aperture plane, of the stationary point, S. The parameters in [23] can be used to express, after some manipulation, the spatial dependence of the phase, in the integrand of [19]

$$R + R' = Z + Z' + \frac{(\xi - x_s)^2 + (\eta - y_s)^2}{2(Z + Z')} + \left[\frac{(x - x_0)^2 + (y - y_0)^2}{2\rho}\right]$$

A further simplification to the Fresnel diffraction integral can be made by obtaining an expression for the distance, D, between the source and the observation point:

$$D = Z + Z' + \frac{(\xi - x_s)^2 + (\eta - y_s)^2}{2(Z + Z')} \qquad [24]$$

We use this definition of D to also write

$$\frac{1}{ZZ'} = \frac{Z+Z'}{ZZ'}\frac{1}{Z+Z'} \approx \frac{1}{\rho D}$$

Using the parameters we have just defined, we may rewrite [19] as

$$\tilde{E}_{\mathrm{P}_0} = \frac{\mathrm{i}\alpha}{\lambda\rho D}\mathrm{e}^{-\mathrm{i}kD}\iint f(x,y)\mathrm{e}^{-\frac{\mathrm{i}k}{2\rho}\left[(x-x_0)^2+(y-y_0)^2\right]}\mathrm{d}x\,\mathrm{d}y \qquad [25]$$

With the use of the variables defined in [23], the physical significance of the general expression of the Huygens–Fresnel integral can be understood in an equivalent fashion as was [22]. At point P_0, a spherical wave

$$\frac{\mathrm{e}^{-\mathrm{i}kD}}{D}$$

originating at the source, a distance D away, is observed, if no obstruction are present. Because of the obstruction, the amplitude and phase of the spherical wave are modified by the integral in [25]. This correction to the predictions of geometrical optics is called Fresnel diffraction.

Mathematically, [25] is an application of the method of stationary phase, a technique developed in 1887 by Lord Kelvin to calculate the form of a boat's wake. The integration is nonzero only in the region of the critical point we have labeled **S**. Physically, the light distribution, at the observation point, is due to wavelets from the region around **S**. The phase variations of light, coming from other regions in the aperture, are so rapid that the value of the integral over those spatial coordinates is zero. The calculation of the integral for Fresnel diffraction is complicated because, if the observation point is moved, a new integration around a different stationary point in the aperture must be performed.

Rectangular Apertures

If the aperture function, $f(x,y)$, is separable in the spatial coordinates of the aperture, then we can rewrite [25] as

$$\tilde{E}_{\mathrm{P}_0} = \frac{\mathrm{i}\alpha}{\lambda\rho D}\mathrm{e}^{-\mathrm{i}kD}\int_{-\infty}^{\infty} f(x)\mathrm{e}^{-\mathrm{i}g(x)}dx\int_{-\infty}^{\infty} f(y)\mathrm{e}^{-\mathrm{i}g(y)}\mathrm{d}y$$

$$\tilde{E}_{\mathrm{P}_0} = A[C(x) - \mathrm{i}S(x)][C(y) - \mathrm{i}S(y)]$$

A represents the spherical wave from the source, a distance D away,

$$A = \frac{\mathrm{i}\alpha}{2D}\mathrm{e}^{-\mathrm{i}kD}$$

If we treat the aperture function as a simple constant, C and S are integrals of the form

$$C(x) = \int_{x_1}^{x_2}\cos[g(x)]\mathrm{d}x \qquad [26a]$$

$$S(x) = \int_{x_1}^{x_2}\sin[g(x)]\mathrm{d}x \qquad [26b]$$

The integrals, $C(x)$ and $S(x)$, have been evaluated numerically and are found in tables of Fresnel integrals. To use the tabulated values for the integrals, [26] must be written in a general form

$$C(w) = \int_0^w \cos\left(\frac{\pi u^2}{2}\right)\mathrm{d}u \qquad [27]$$

$$S(w) = \int_0^w \sin\left(\frac{\pi u^2}{2}\right)\mathrm{d}u \qquad [28]$$

The variable u is an aperture coordinate, measured relative to the stationary point, $\mathbf{S}(x_0,y_0)$, in units of

$$\sqrt{\frac{\lambda\rho}{2}}$$

$$u = \sqrt{\frac{2}{\lambda\rho}}(x - x_0) \text{ or } u = \sqrt{\frac{2}{\lambda\rho}}(y - y_0) \qquad [29]$$

The parameter w in [27] and [28] specifies the location of the aperture edge relative to the stationary point **S**. The parameter w is calculated through the use of [29] with x and y replaced by the coordinates of the aperture edge.

The Cornu Spiral

The plot of $S(w)$ versus $C(w)$, shown in Figure 8, is called the Cornu spiral in honor of M. Alfred Cornu (1841–1902) who was the first to use this plot for graphical evaluation of the Fresnel integrals.

To use the Cornu spiral, the limits w_1 and w_2 of the aperture are located along the arc of the spiral. The length of the straight line segment drawn from w_1 to w_2 gives the magnitude of the integral. For example, if there were no aperture present, then, for the x-dimension, $w_1 = -\infty$ and $w_2 = \infty$. The length of the line segment from the point $(-1/2,1/2)$ to $(1/2,1/2)$ would be the value of E_{P_0}, i.e., $\sqrt{2}$. An identical value is obtained for the y-dimension, so that

$$\tilde{E}_{\mathrm{P}_0} = 2A = \frac{\alpha\mathrm{e}^{-\mathrm{i}kD}}{D}$$



Figure 8 Cornu spiral obtained by plotting the values for *C*(*w*) versus *S*(*w*) from a table of Fresnel integrals. The numbers indicated along the arc of the spiral are values of *w*. The points 1–5 correspond to observation points shown in Figure 9 and are used to calculate the light intensity diffracted by a straight edge. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.



Figure 9 A geometrical construct to determine w_1 for the stationary point S associated with five different observation points. The values of *w* are then used in Figure 8 to calculate the intensity of light diffracted around a straight edge. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

Table 1 Fresnel integrals for straight edge

w_1	$C(w_1)$	$S(w_1)$	I_P/I_0	P_j
∞	0.5	0.5	0	
2.0	0.4882	0.3434	0.01	
1.5	0.4453	0.6975	0.021	P_1
1.0	0.7799	0.4383	0.04	
0.5	0.4923	0.0647	0.09	P_2
0	0	0	0.25	P_3
−0.5	−0.4923	−0.0647	0.65	
−1.0	−0.7799	−0.4383	1.26	P_4
−1.2	−0.7154	−0.6234	1.37	
−1.5	−0.4453	−0.6975	1.16	
−2.0	−0.4882	−0.3434	0.84	P_5
−2.5	−0.4574	−0.6192	1.08	
−∞	−0.5	−0.5	1.0	

This is the spherical wave that is expected when no aperture is present.

As an example of the application of the Fresnel integrals, assume the diffracting aperture is an infinitely long straight edge reducing the problem to one dimension:

$$f(x, y) = \begin{Bmatrix} 1 & x \geq x_1 \\ 0 & x < x_1 \end{Bmatrix}$$

The value of E_{P_0} in the y-dimension is from above $\sqrt{2}$ since $w_1 = -\infty$ and $w_2 = \infty$. In the x-dimension, the value of w at the edge is

$$w_{x_1} = \sqrt{\frac{2}{\lambda\rho}}(x_1 - x_0)$$

We will assume that the straight edge blocks the negative half-plane so that $x_1 = 0$. The straight edge is treated as an infinitely wide slit with one edge located at infinity so that $w_2 = \infty$ in the upper half-plane. When the observation point is moved, the coordinate x_0 of S changes and the origin of the aperture's coordinate system moves. New values for the w's must therefore be calculated for each observation point.

Figure 9 shows the assumed geometry. A set of observation points, P_1–P_5, on the observation screen are selected. The origin of the coordinate system in the aperture plane is relocated to a new position (given by the position of S) when a new observation point is selected. The value of w_1, the position of the edge with respect to S, must be recalculated for each observation point. The distance from the origin to the straight edge, w_1, is positive for P_1 and P_2, zero for P_3, and negative for P_4 and P_5.

Figure 8 shows the geometrical method used to calculate the intensity values at each of the observation points in Figure 9 using the Cornu spiral. The numbers labeling the straight line segments in Figure 8 are associated with the labels of the observation points in Figure 9.

To obtain an accurate calculation of Fresnel diffraction from a straight edge, a table of Fresnel integrals provides the input to the following equation

$$I_P = I_0\left\{\left[\tfrac{1}{2} - C(w_1)\right]^2 + \left[\tfrac{1}{2} - S(w_1)\right]^2\right\}$$

where $I_0 = 2A^2$. Table 1, shows the values extracted from the table of Fresnel integrals to find the relative intensity at various observation points. The result obtained by using either method for calculating the light distribution in the observation plane, due to the straight edge in Figure 9, is plotted in Figure 10. The relative intensities at the observation points



Figure 10 Light diffracted by a straight edge with its edge located at $w = 0$. The points labeled 1–5 were found using the construction in Figure 9 to obtain w. This was then used in Figure 8 to find a position on the Cornu spiral. The length of the lines shown in Figure 8 from the (1/2,1/2) point to the numbered positions led to the intensities shown. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

depicted in Figure 9 are labeled on the diffraction curve of Figure 10.

Fresnel Zones

Fresnel used a geometrical construction of zones to evaluate the Huygens–Fresnel integral. The Fresnel zone is a mathematical construct, serving the role of a Huygens source in the description of wave propagation. Assume that at time t, a spherical wavefront from a source at P_1 has a radius of R'. To determine the field at the observation point, P_0, due to this wavefront, a set of concentric spheres of radii, $Z, Z + (\lambda/2), Z + 2(\lambda/2), \ldots, Z + j(\lambda/2), \ldots$ are constructed, where Z is the distance from the wavefront to the observation point on the line connecting P_1 and P_0 (see Figure 11). These spheres divide the wavefront into a number of zones, $\zeta_1, \zeta_2, \ldots, \zeta_j \ldots$, called Fresnel zones, or half-period zones.

We treat each zone as a circular aperture illuminated from the left by a spherical wave of the form

$$\tilde{E}_j(\mathbf{R}') = \frac{A\mathrm{e}^{-\mathrm{i}\mathbf{k}\cdot\mathbf{R}'}}{R'} = \frac{A\mathrm{e}^{-\mathrm{i}kR'}}{R'}$$

R' is the radius of the spherical wave. The field at P_0 due to the jth zone is obtained by using [5]

$$\tilde{E}_j(\mathrm{P}_0) = \frac{A}{R'}\mathrm{e}^{-\mathrm{i}\mathbf{k}\cdot\mathbf{R}'} \iint_{\zeta_j} C(\varphi)\frac{\mathrm{e}^{-\mathrm{i}\mathbf{k}\cdot\mathbf{R}}}{R}\mathrm{d}s \qquad [30]$$

For the integration over the jth zone, the surface element is

$$\mathrm{d}s = R'2\sin\theta\mathrm{d}\theta\,\mathrm{d}\phi \qquad [31]$$



Figure 11 Construction of Fresnel zones observed from a position P_0 on a spherical wave originating from a source at point P_1. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.



Figure 12 Geometry for finding the relationship between R and R' yielding eqn [32]. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

The limits of integration extend over the range

$$Z + (j-1)\tfrac{\lambda}{2} \le R \le Z + j\tfrac{\lambda}{2}$$

The variable of integration is R; thus, a relationship between R' and R must be found. This is accomplished by using the geometrical construction shown in Figure 12.

A perpendicular is drawn from the point Q on the spherical wave to the line connecting P_1 and P_0, in Figure 12. The distance from the source to the observation point is $x_1 + x_2$ and the distance from the source to the plane of the zone is the radius of the incident spherical wave, R'. The distance from P_1 to P_0 can be written

$$x_1 + x_2 = R' + Z$$

The distance from the observation point to the zone is

$$\begin{aligned} R^2 = x_2^2 + y^2 &= [(R' + Z) - x_1]^2 + (R' \sin\theta)^2 \\ &= R'2 + (R' + Z)^2 - 2R'(R' + Z)\cos\theta \end{aligned}$$

The derivative of this expression yields

$$R\,\mathrm{d}R = R'(R' + Z)\sin\theta\,\mathrm{d}\theta \qquad [32]$$

Substituting [32] into [31] gives

$$\mathrm{d}s = \frac{R'}{R' + Z} R\mathrm{d}R\mathrm{d}\phi \qquad [33]$$

The integration over ϕ is accomplished by rotating the surface element about the P_1P_0 axis. After integrating over ϕ between the limits of 0 and 2π, we obtain

$$\tilde{E}_j(\mathrm{P}_0) = \frac{2\pi A}{R' + Z} \mathrm{e}^{-\mathrm{ik}\cdot\mathrm{R}'} \int_{Z+(j-1)\frac{\lambda}{2}}^{Z+\frac{j\lambda}{2}} \mathrm{e}^{-\mathrm{ik}\cdot\mathrm{R}} C(\varphi)\mathrm{d}R \qquad [34]$$

We assume that $R',\ Z \gg \lambda$ so that the obliquity factor is a constant over a single zone, i.e., $C(\varphi) = C_j$. The obliquity factor is not really a constant as we earlier assumed but rather a very slowly varying parameter of j, changing by less than two parts in 10^4 when 'j' changes by 500 (for $Z = 1$ meter and $\lambda = 500$ nm). In fact it only changes by 2 parts in 10^{-7} across one zone. We are safe in applying the assumption that the obliquity factor is a constant over a zone and this allows the integral in [34] to be calculated:

$$\tilde{E}_j(\mathrm{P}_0) = \frac{2\pi \mathrm{i} C_j A}{k(R' + Z)} \mathrm{e}^{-\mathrm{i}k(R'+Z)} \mathrm{e}^{-\mathrm{i}kj\frac{\lambda}{2}} \left[1 - \mathrm{e}^{-\mathrm{i}k\frac{\lambda}{2}}\right] \qquad [35]$$

Using the identity $k\lambda = 2\pi$ and the definition for the distance between the source and observation point [24] modified for this geometry, $D = R' + Z$ [35] can be simplified to

$$\tilde{E}_j(\mathrm{P}_0) = 2\mathrm{i}\lambda(-1)^j \frac{C_j A}{D} \mathrm{e}^{-\mathrm{i}kD} \qquad [36]$$

The physical reasons for the behavior predicted by [36] are quite easy to understand. The distance from P_0 to a zone changes by only $\lambda/2$ as we move from zone to zone and the area of a zone is almost a constant, independent of the zone number; thus, the amplitudes of the Huygens' wavelets from each zone should be approximately equal. The alternation in sign, from zone to zone, is due to the phase change of the light wave from adjacent zones because the propagation paths for adjacent zones differ by $\lambda/2$.

To find the total field strength at P_0 due to N zones, the collection of Huygens' wavelets is added:

$$E(\mathrm{P}_0) = \sum_{j=1}^{N} \tilde{E}_j(\mathrm{P}_0) = \frac{2\mathrm{i}\lambda A}{D} \mathrm{e}^{-\mathrm{i}kD} \sum_{j=1}^{N} (-1)^j C_j \qquad [37]$$

To evaluate the sum, the elements of the sum are regrouped and rewritten as

$$\begin{aligned} -\sum_{j=1}^{N} (-1)^j C_j = \frac{C_1}{2} + \left(\frac{C_1}{2} - C_2 + \frac{C_3}{2}\right) \\ + \left(\frac{C_3}{2} - C_4 + \frac{C_5}{2}\right) + \ldots \end{aligned}$$

Because the C's are very slowly varying functions of j, even out to 500 zones, we are justified in setting the quantities in parentheses equal to zero. With this approximation, the summation can be set equal to one of two values, depending upon whether there is an even or odd number of terms in the summation

$$-\sum_{j=1}^{N} (-1)^j C_j = \left\{ \begin{array}{ll} \frac{1}{2}(C_1 + C_N) & N \text{ odd} \\ \frac{1}{2}(C_1 - C_N) & N \text{ even} \end{array} \right\}$$

For very large N, the obliquity factor approaches zero, $C_N \to 0$, as was demonstrated in Figure 4. Thus, the theory has led us to the conclusion that the total field produced by an unobstructed wave is equal to one half the contribution from the first Fresnel zone, i.e., $E = E_1/2$. Stating this result in a slightly different way, we obtain a surprising result – the contribution from the first Fresnel zone is twice the amplitude of the unobstructed wave!

The zone construction can be used to analyze the effect of the obstruction of all or part of a zone. For example, by constructing a circular aperture with a diameter equal to the diameter of the first Fresnel zone, we have just demonstrated that it is possible to produce an intensity at the point P_0 equal to four times the intensity that would be observed if no aperture were present. To analyze the effects of a smaller aperture, we subdivide a half-period zone into a number of subzones such that there is a constant phase difference between each subzone. The individual vectors form a curve know as the vibrational curve. Figure 13 shows a vibrational curve produced by the addition of waves from nine subzones of the first Fresnel zone. The vibrational curve in Figure 13 is an arc with the appearance of a half-circle.



Figure 13 Vector addition of waves from nine subzones constructed in the first Fresnel zone. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

If the radius of curvature of the arc were calculated, we would discover that it is a constant, except for the contribution of the obliquity factor,

$$\rho = \frac{\lambda R'}{R' + Z} C(\varphi)$$

Because the obliquity factor for a single zone is a constant to 2 parts in 10^{-7}, the radius of curvature of the vibration curve can be considered a constant over a single zone. If we let the number of subzones approach infinity, the vibrational curve becomes a semicircle whose chord is equal to the wavelet produced by zone one, i.e., E_1. If we subdivide additional zones, and add the subzone contributions, we create other half-circles whose radii decrease at the same rate as the obliquity factor. The vibrational curve for the total wave is a spiral, constructed of semicircles which converges to a point halfway between the first half-circle, see Figure 14. The length of the vector from the start to the end of the spiral is $E = E_1/2$, as we derived above. When this same construction technique is applied to a rectangular aperture, the vibrational curve generated is the Cornu spiral.

Circular Aperture

The vector addition technique, described in Figure 13, can be used to evaluate Fresnel diffraction, at a point P_0, from a circular aperture and yields the intensity distribution along the axis of symmetry of the circular aperture. The zone concept will also allow a qualitative description of the light distribution normal to this axis.

To develop a quantitative estimate of the intensity at an observation point on the axis of symmetry of the circular aperture, we construct a spiral, Figure 14, to represent the Fresnel zones of a spherical wave incident on the aperture. The point B on the spiral shown in Figure 14 corresponds to the portion of the spherical wave unobstructed by the screen. The length of the chord, AB, represents the amplitude of the light wave at the observation point P_0. As the diameter of the aperture increases, B moves along the spiral, in a counterclockwise fashion, away from A. The first maximum occurs when B reaches the point labeled A_1 in Figure 14; the aperture has then uncovered the first Fresnel zone. At this point, the amplitude is twice what it would be with no obstruction. Four times the intensity!



Figure 14 Vibration curve for determining the Fresnel diffraction from a circular aperture. The change of the diameter of the half-circles making up the spiral has been exaggerated for easy visualization. The actual changes are one part in 10^{-5}. The position of point B is determined by the aperture size. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

If the aperture's diameter continues to increase, B reaches the point labeled A_2 in Figure 14 and the amplitude is very nearly zero; two zones are now exposed in the aperture. Further maxima occur when an odd number of zones are in the aperture and further minima when an even number of zones are exposed. Figure 15 shows an aperture containing four exposed Fresnel zones. The amplitude at the observation point would correspond to the chord drawn from A to A_4 in Figure 14.

The aperture diameter can be fixed and the observation point P_0 can move along, or perpendicular to, the axis of symmetry of the circular aperture. As P_0 is moved away from the aperture, along the symmetry axis, i.e., as Z increases, the radius of the Fresnel zones increase without limit. For small values of n, the radius of the nth zone can be approximated by

$$r_n \approx \sqrt{nZ\lambda} \qquad [38]$$



Figure 15 Aperture with four Fresnel zones exposed. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

At $Z_{\max}$, the light intensity is a maximum, given by the chord length from A to A_1 in Figure 14. If $\lambda = 500$ nm and $a = 0.5$ mm then this maximum occurs when $Z = 0.5$ m

$$Z_{\max} = \frac{a^2}{\lambda} \qquad [39]$$

If we start at $Z_{\max}$ and move toward the aperture, along the axis, as Z decreases in value, a point will be reached when the intensity on the axis becomes a minimum. The value of Z where the first minimum in intensity is observed is equal to

$$Z_{\min} = \frac{a^2}{2\lambda}$$

In Figure 14 the chord would extend from A to A_2.

As the observation point, P_0, is moved along the axis toward the aperture, and Z assumes values less than $Z_{\min}$, the point B in Figure 14 spirals inward, toward the center of the spiral and the intensity cycles through maximum and minimum values. The cycling of the intensity, as the observation point moves toward the aperture, will not continue indefinitely. At some point, the field on the axis will approach the field observed without the aperture because the distance between $Z_{\max}$ and $Z_{\min}$ shrinks to the wavelength of light making the intensity variation unobservable.

For values of Z that exceed $Z_{\max}$ of [39], the aperture radius, a, will be smaller than the radius of the first zone, and Fraunhofer diffraction will be observed because the aperture contains only one zone and the phase in the aperture is a constant.

Opaque Screen

If the screen containing a circular aperture, of radius a, is replaced by an opaque disk of radius a, the intensity distribution on the symmetry axis, behind the disk, is found to be equal to the value that would be observed with no disk present. This prediction was first derived by Poisson, to demonstrate that wave theory was incorrect; however, experimental observation supported the prediction and verified the theory.

We construct a spiral, shown in Figure 16, similar to the one for the circular aperture in Figure 14. The point B on the spiral represents the edge of the disk. The shaded portion of the spiral from A to B does not contribute because that portion of the wave is covered by the disk and the zones, associated with that portion of the wave, cannot be seen from the observation point. The amplitude at P_0 is the length of the chord from B to A_∞ shown in Figure 16. If the observation point moves toward the disk, then B moves along the spiral toward A_∞. There is always intensity on the axis for this configuration, though it slowly decreases until it reaches zero when the observation point reaches the disk; this corresponds to point B reaching point A_∞ on the spiral. Physically, zero intensity occurs when the disk blocks the entire light wave. There are no maxima or minima observed as the disk diameter, a, increases or as the observation distance changes. If the observation point is moved perpendicular to the symmetry axis, a set of concentric bright rings are observed. The origin of these bright rings can be explained using Fresnel zones, in a manner similar to the one used to explain the bright rings observed in a Fresnel diffraction pattern from a circular aperture.



Figure 16 Vibration curve for opaque disk. The shaded region makes no contribution because it is associated with the portion of the wave obstructed by the opaque object. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

Zone Plate

In the construction of Fresnel zones, each zone was assumed to produce a Huygens wavelet, out of phase with the wavelets produced by its nearest neighbors. If every other zone were blocked, then there would be no negative contributions to [37]. The intensity on-axis would be equal to the square of the sum of the amplitudes produced by the in-phase zones – exceeding the intensity of the incident wave. An optical component made by the obstruction of either the odd or the even zones could therefore be used to concentrate the energy in a light wave.

The boundaries of the opaque zones, used to block out-of-phase wavelets, are seen from [38] to increase as the square root of the integers. An array of opaque rings, constructed according to this prescription is called a zone plate, see Figure 17.

A zone plate will perform like a lens with focal length

$$f = \pm \frac{r_1^2}{\lambda} \qquad [40]$$

The zone plate, shown in Figure 17, will act as both a positive and negative lens. What we originally called the source can now be labeled the object point, O, and what we called the observation point can now be labeled the image point, I. The light passing through the zone plate is diffracted into two paths, labeled C and D in Figure 17. The light waves, labeled C, converge to a real image point I. For these waves the zone plate performs the role of a positive lens with a focal length given by the positive value of [40]. The light waves, labeled D in Figure 17, appear to originate from the virtual image point labeled 𝕀. For these waves the zone plate performs the role of a negative lens with a focal length given by the negative value of [40].

The zone plate will not have a single focus, as is the case for a refractive optical element, but rather will have multiple foci. As we move toward the zone plate, from the first focus, given by [40], the effective Fresnel zones will decrease in diameter. The zone plate will no longer obstruct out-of-phase Fresnel zones and the light intensity on the axis will decrease. However, additional maxima, of the on-axis intensity, will be observed at values of Z for which the first zone plate opening contains an odd number of zones. These positions can also be labeled as foci of the zone plate; however, the intensity at each of these foci will be less than the intensity at the primary focus.

Lord Rayleigh suggested that an improvement of the zone plate design would result if, instead of blocking every other zone, we shifted the phase of alternate zones by 180°. The resulting zone plate, called a phase-reversal zone plate, would, more efficiently, utilize the incident light. R.W. Wood was the first to make such a zone plate. Holography provides an optical method of constructing the phase-reversal zone plates in the visible region of the spectrum. Semiconductor lithography has been used to produce zone plates in the x-ray region of the spectrum.



Figure 17 A zone plate acts as if it were both a positive and a negative lens. Light from the object, O, is diffracted into waves traveling in both the D and the C directions. The light traveling in the C direction produces a real image of O at I. The light traveling in the D direction appears to originate from a virtual image at I. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.



Figure 18 (a) A set of Fresnel zones has been constructed about the optical path taken by some light ray. If the optical path of the ray is varied over the cross-hatched area shown in the figure, then the optical path length does not change. This cross-hatched area is equal to the first Fresnel zone and is described as the neighborhood of the light ray. (b) The neighborhood defined in (a) is moved so that it surrounds an incorrect optical path for a light ray. We see that this region of space would contribute no wave amplitude at the observation point because of the destructive interference between the large number of partial zones contained in the neighborhood. Reprinted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley & Sons.

The resolving power of a zone plate is a function of the number of zones contained in the plate. When the number of zones exceeds 200, the zone plate's resolution approaches that of a refractive lens.

Fermat's Principle

The Fresnel zone construction provides physical insight into the interpretation of Fermat's principle which states that, if the optical path length of a light ray is varied in a neighborhood about the true path, there is no change in path length. By constructing a set of Fresnel zones about the optical path of a light ray, we can discover the physical meaning of a neighborhood.

The rules for constructing a Fresnel zone require that all rays passing through a given Fresnel zone have the same optical path length. The true path will pass through the center of the first Fresnel zone constructed on the actual wavefront. A neighborhood must be the area of the first Fresnel zone, for it is over this area that the optical path length does not change. Figure 18a shows the neighborhood, about the true optical path, as a cross-hatched region equal to the first Fresnel zone.

Light waves do travel over wrong paths but we do not observe them because the phase differences for those waves that travel over the 'wrong' paths are such that they destructively interfere. By moving the neighborhood, defined in the previous paragraph as the first Fresnel zone, to a region displaced from the true optical path, we can use the zone construction to see that this statement is correct. In Figure 18b the neighborhood is constructed about a ray that is improper according to Fermat's principle. We see that this region of space would contribute no energy at the observation point because of destructive interference between the large number of partial zones contained in the neighborhood.

This leads us to another interpretation of diffraction. If an obstruction is placed in the wavefront so that we block some of the normally interfering wavelets, we see light not predicted by Fermat's principle, i.e., we see diffraction.

Further Reading

Backer BB and Copson EJ (1969) *The Mathematical Theory of Huygens' Principle*. London: Oxford University Press.
Born M and Wolf E (1970) *Principles of Optics*. New York: Pergamon Press.
Guenther RD (1990) *Modern Optics*. New York: Wiley.
Haus HA (1984) *Waves and Fields in Optoelectronics*. Englewood Cliffs, NJ: Prentice-Hall.
Hecht E (1998) *Optics*, 3rd edn. Reading, MA: Addison-Wesley.
Klein MV (1970) *Optics*. New York: Wiley.
Rubinowicz A (1984) *Tahe Miyamoto–Wolf diffraction wave*. In: Wolf E (ed.) Progress in Optics, vol. IV.
Sayanagi I (1967) Pinhole Imagery. *Journal of the Optical Society of America*. 57: 1091–1099.
Sears FW (1949) *Optics*. Reading, MA: Addison-Wesley.
Sommerfeld A (1964) *Optics*. New York: Academic Press.
Stegliani DJ, Mittra R and Semonin RG (1967) Resolving power of a zone plate. *Journal of the Optical Society of America* 57: 610–613.
Stone JM (1963) *Radiation and Optics*. New York: McGraw-Hill.

DIFFRACTIVE SYSTEMS

Contents

Aberration Correction with Diffractive Elements
Applications of Diffractive and Micro-Optics in Lithography
Design and Fabrication of Diffractive Optical Elements
Diffractive Laser Resonators
Diffractives in Animals
Microstructure Fibers
Omnidirectional Surfaces and Fibers
Wave Optical Modeling and Design

Aberration Correction with Diffractive Elements

N Lindlein, University of Erlangen-Nürnberg, Erlangen, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Diffractive optical elements (DOEs) can be used for the correction of aberrations in optical systems because of two fundamental properties:

1. The phase function Φ of a DOE can be chosen quite arbitrarily so that for a given wavelength λ the DOE can act like an aspheric optical element.
2. The dispersion of a DOE due to the local grating equation is very high and its sign is opposite to that of the dispersion of a refractive optical element with normal dispersion of the refractive index.

The first property allows the correction of monochromatic aberrations in an optical system similar to the case of using an aspheric surface in a refractive optical system. The second property allows the construction of hybrid achromatic optical elements that consist of a refractive lens and a diffractive lens whose optical powers have the same sign (e.g., two positive lenses for a positive achromatic element or two negative lenses for a negative achromatic element).

This article will first describe two methods for the simulation of DOEs by ray tracing because ray tracing is the basic simulation tool for aberration correction. Afterwards, the properties of DOEs for the correction of monochromatic and chromatic aberrations and some applications will be discussed. The name DOE will always mean either binary, or multiple-step or blazed surface relief diffractive optical elements which change only the phase of the incident wave and not the amplitude. All examples will be given for transmission elements but in principle reflective elements can also be described with quite similar formulas.

Ray Tracing Simulation of DOEs

First of all it seems straightforward to use a diffractive analysis to simulate a diffractive optical element. However, the global diffractive analysis of a general DOE with perhaps 1000 or more grating structures and locally changing grating period and especially the diffractive analysis of a complete optical system containing DOEs and other elements is so complex that it can be done only for very simple DOEs and systems. Therefore, the diffractive analysis of a DOE is mostly restricted to a local analysis using some periods (e.g., 10–50 periods) to calculate, e.g., the different local diffraction orders, their diffraction efficiencies and possibly local phase shifts. For the global analysis another simulation method has to be used.

The most important simulation method for the correction of aberrations in traditional optical systems is ray tracing. Therefore, ray tracing methods are also used for DOEs. These methods can calculate the path of a ray for a given diffraction order, but they cannot calculate the diffraction efficiency for this ray. For the calculation of the diffraction efficiency local diffractive analysis methods (scalar or rigorous methods depending on the local grating frequency and the angle of the incident ray) have to be used in addition. In particular, for applications with a broad wavelength spectrum (e.g., an achromatic lens) or a broad spectrum of angles of the incident rays, the diffraction efficiency has to be analyzed carefully to obtain the energy distribution in the different diffraction orders. But this is beyond the scope of this article about aberration correction and we assume that we know the local diffraction efficiency for each ray.

Sweatt Model for the Ray Tracing Simulation of DOEs

An aspheric refractive surface with height h as a function of the lateral coordinates x and y and a refractive index n below the surface and air (refractive index 1) above the surface can be approximately replaced by a DOE with the phase function (see Figure 1)

$$\Phi(x, y) = 2\pi \frac{(n-1)h(x, y)}{\lambda} \qquad [1]$$

Here, λ is the wavelength of the light for which the DOE is designed and the phase function is a continuous representation of the structure of the DOE. To encode the phase function of the DOE the wrapped phase function $\Phi \bmod 2\pi$ has to be considered. The encoding itself can be done by building a blazed, a multiple-step or a binary structure (see Figure 1), whereby the first-order diffraction efficiency decreases from the blazed to the binary structure (at maximum 100% diffraction efficiency for the blazed structure and about 40% for the binary structure). The replacement of an aspheric refracting surface by a DOE using eqn [1] is only valid in the paraxial approximation since the phase function of the DOE is encoded in a plane whereas the refracting surface of the aspheric is typically curved. But, the agreement between the aspheric surface and the DOE with a phase function calculated with the help of eqn [1] increases with increasing refractive index n since then the curvature of the aspheric is quite small and the refraction also nearly takes place in a plane. Of course, the refractive index of real materials cannot exceed a value of more than about 3.5 (for silicon used in the near infrared). But, in a numerical simulation the refractive index can be arbitrarily high, e.g., several thousand. This is the reason why the so called Sweatt model for tracing rays through DOEs uses a weakly curved aspheric surface with height h_{sweatt} and a very high refractive index n_{sweatt} to simulate a diffractive phase function Φ:



Figure 1 Transition from an aspheric refracting surface to a blazed diffractive optical element and finally to a binary diffractive optical element.

$$h_{\text{sweatt}}(x, y) = \frac{\lambda}{n_{\text{sweatt}} - 1} \frac{\Phi(x, y)}{2\pi} \qquad [2]$$

To take into account the wavelength dispersion of the DOE the refractive index n_{sweatt} in the Sweatt model has to be proportional to the wavelength λ

$$n_{\text{sweatt}}(\lambda) = n_0 \frac{\lambda}{\lambda_0} \qquad [3]$$

where n_0 is the refractive index at the wavelength λ_0.

The validity of the Sweatt model increases with increasing refractive index and becomes nearly exact for $n_{\text{sweatt}} \rightarrow \infty$ (in practice values of several thousand for the refractive index are normally sufficient and a rule of thumb is to take the numerical value of the utilized wavelength specified either in nanometers for infrared light or angstroms for visible light). The Sweatt model was introduced as a means to simulate DOEs in ray tracing programs unable to implement DOEs directly but capable of simulating aspheric refractive surfaces. However, a disadvantage of this model is the numerical error generated by the finite value of the refractive index.

Modern ray tracing programs therefore use a more appropriate model based on the local grating equation.

Local Grating Model for the Ray Tracing Simulation of DOEs

The basic equation for the simulation of DOEs by the local grating model is that the phase Φ_{out} of a diffracted ray in the plane of the DOE can be calculated from the phase Φ_{in} of the incident ray by adding the phase function Φ of the DOE multiplied by the diffraction order m:

$$\Phi_{\text{out}}(x, y, z_0) = \Phi_{\text{in}}(x, y, z_0) + m\Phi(x, y) \qquad [4]$$

Here, z_0 is the z-coordinate of the DOE plane which is assumed to be perpendicular to the z-axis (see Figure 2). The diffraction order m will be only one for an ideal blazed DOE but it can have an arbitrary integer value for binary DOEs. In practice, the optical designer will calculate the system for one diffraction order and analyze the system for other diffraction orders afterwards if necessary.



Figure 2 Schematic view in two-dimensions of the path of a ray which is diffracted at a DOE.

For the phases Φ_{in} of the incident and Φ_{out} of the diffracted ray the eikonal equation of geometrical optics is valid,

$$|\nabla\Phi_j|^2 = k_j^2 = \left(\frac{2\pi n_j}{\lambda}\right)^2 \qquad [5]$$

where the index j can have the two values $j \in \{\text{in}, \text{out}\}$. n_{in} or n_{out} are the refractive indices of the materials in which the incident or diffracted rays propagate. λ is the wavelength in vacuum. This form of the eikonal equation is obtained from the more common form $|\nabla L_j|^2 = n_j^2$, which is derived in any textbook of optics, by multiplying it with $(2\pi/\lambda)^2$ and using the definition of the optical phase $\Phi_j = 2\pi L_j/\lambda$. Here, L_j is the optical path length which is often called the eikonal. The curves of constant phase $\Phi_j(x, y, z) = \text{constant}$ are the wavefronts and the gradient $\nabla\Phi_j(x, y, z)$ points in the direction of the local ray which is perpendicular to the wavefront at the point (x, y, z) and describes its direction of propagation. Furthermore, the unit vectors $\mathbf{e}_{in}$ and $\mathbf{e}_{out}$ along the ray direction of the incident and diffracted ray, respectively, can be calculated by normalizing the gradient:

$$\mathbf{e}_j = \frac{\nabla\Phi_j}{|\nabla\Phi_j|} = \frac{\lambda}{2\pi n_j}\nabla\Phi_j; \qquad j \in (\text{in}, \text{out}) \qquad [6]$$

Since $\mathbf{e}_j$ is a unit vector, i.e., $e_{x,j}^2 + e_{y,j}^2 + e_{z,j}^2 = 1$, it can be seen from eqn [6] (and also from the original eqn [5]) that the z-component $e_{z,j}$ of the ray direction vector can be calculated (apart from its sign) if the two partial derivatives of the phase with respect to x and y are known. This means that it is sufficient to know the phase in a plane as stated in eqn [4].

By calculating the partial derivatives of eqn [4] with respect to x and y the equations for the ray tracing at a DOE are derived:

$$\begin{aligned}
\frac{\partial\Phi_{out}(x, y)}{\partial x} &= \frac{\partial\Phi_{in}(x, y)}{\partial x} + m\frac{\partial\Phi(x, y)}{\partial x} \\
&\Rightarrow n_{out}e_{x,out}(x, y) \\
&= n_{in}e_{x,in}(x, y) + m\frac{\lambda}{2\pi}\frac{\partial\Phi(x, y)}{\partial x} \\
\frac{\partial\Phi_{out}(x, y)}{\partial y} &= \frac{\partial\Phi_{in}(x, y)}{\partial y} + m\frac{\partial\Phi(x, y)}{\partial y} \\
&\Rightarrow n_{out}e_{y,out}(x, y) \\
&= n_{in}e_{y,in}(x, y) + m\frac{\lambda}{2\pi}\frac{\partial\Phi(x, y)}{\partial y}
\end{aligned} \qquad [7]$$

The local grating frequencies ν_x and ν_y in x and y direction are calculated from the phase function Φ by:

$$\begin{aligned}
\nu_x(x, y) &= \frac{1}{2\pi}\frac{\partial\Phi(x, y)}{\partial x} \\
\nu_y(x, y) &= \frac{1}{2\pi}\frac{\partial\Phi(x, y)}{\partial y}
\end{aligned} \qquad [8]$$

Therefore, given $\mathbf{e}_{in}$ and eqn [6], the ray direction vector $\mathbf{e}_{out}$ of the diffracted ray is

$$n_{out}\mathbf{e}_{out} = n_{out}\begin{pmatrix} e_{x,out} \\ e_{y,out} \\ e_{z,out} \end{pmatrix} = \begin{pmatrix} n_{in}e_{x,in} + m\lambda\nu_x \\ n_{in}e_{y,in} + m\lambda\nu_y \\ \sqrt{n_{out}^2 - (n_{in}e_{x,in} + m\lambda\nu_x)^2 - (n_{in}e_{y,in} + m\lambda\nu_y)^2} \end{pmatrix} \qquad [9]$$

The dependence of the lateral coordinates x and y is left out in eqn [9] to simplify notation. It can be easily checked that this equation fulfills the required condition for the unit vector: $e_{x,out}^2 + e_{y,out}^2 + e_{z,out}^2 = 1$.

As stated above, for a blazed DOE fabricated to the exact depth and illuminated by the design wavelength only the first diffraction order $m = 1$ is generated. But in practice other diffraction orders m are generated due to fabrication errors or illuminating with other wavelengths. In particular, by using binary DOEs there are inherently different diffraction orders. Therefore, it may be necessary to analyze the optical system for several values m one after the other. Each value m defines one wavefront generated by the DOE and the wavefront can be calculated by evaluating the optical path lengths along the rays at different points. In practice, the optical system has to be analyzed for those values m with sufficiently high diffraction efficiency. Then, it can be checked whether undesired diffraction orders of the DOE are blocked in the optical system by aperture stops or whether they will disturb the output of the optical system. The local diffraction efficiency of each ray for a value m can be calculated to a good approximation by using a diffractive analysis of the corresponding local grating, i.e., that of an infinitely extended grating which would have the same grating period and the same structure shape (e.g., depth) as the DOE at the specific point.

If the y component of the incident ray and the local grating frequency ν_y are both zero the ray components in the x direction can be expressed via the sine of the angle of incidence φ_{in} or the angle of the diffracted ray φ_{out} (see Figure 2). In this case the first row of eqn [9] can be written as

$$n_{\text{out}} \sin \varphi_{\text{out}} = n_{\text{in}} \sin \varphi_{\text{in}} + m \frac{\lambda}{p_x} \qquad [10]$$

where the local grating period $p_x = 1/\nu_x$ has been introduced. This is the well-known grating equation.

In this article eqns [4]–[10] assume that the DOE is on a planar substrate and that x and y are the lateral coordinates on the substrate. However, the equations can also be written in a vector formulation which is valid for DOEs on curved substrates (see Further Reading).

So, we have now a powerful simulation method to design and analyze in the following several optical systems containing DOEs to correct monochromatic or chromatic aberrations.

Correction of Monochromatic Aberrations

For practical applications it is important to have an efficient algorithm to calculate the phase function of a DOE to correct the aberrations in a given optical system. Several different cases have to be distinguished. An easy case is the design of a DOE to produce a desired output wavefront Φ_{out} from a known input Φ_{in}. In this case, eqn [4] can be used to calculate the phase function Φ of the DOE directly. Two examples are given in the following. Afterwards, some aspects of a more general numerical optimization procedure are described.

Aberration Correction for Interferometrically Recorded Holograms

Although the following example of the aberration correction of interferometrically recorded holograms by using DOEs seems to be quite special it shows exemplarily several principal steps which are necessary to design a DOE for correcting monochromatic aberrations.

In this article the name DOE is used for diffractive elements with a microstructured surface (binary, multistep or blazed). Such elements have the property that their diffraction efficiency depends only weakly on the wavelength or the angle of incidence of the illuminating light. Another interesting class of diffractive elements are holograms in volume media, which are recorded interferometrically using two coherent recording waves. The refractive index in a volume hologram is modulated periodically and the thickness has to amount to several periods of the interference pattern along the z-direction in order to have a so-called thick hologram with a high diffraction efficiency. If there are only a few periods along the z-direction the quite small modulation of the refractive index (typically about 0.02) will result in a low diffraction efficiency. Therefore, if the angle between the two recording waves is small the resulting interference pattern will have large periods and only a few periods are recorded in the photosensitive layer along the z-direction. But this means that the holographic optical element (HOE) can only have a small diffraction efficiency. From this fact, it is clear that also by using the recorded HOE the deflection angle between the incident and the diffracted wave must not be smaller than a certain value because otherwise the thickness has to be very big or the diffraction efficiency decreases. Therefore, such elements with high diffraction efficiency, which will be named in the following holographic optical elements (HOE), are always off-axis elements because for on-axis elements all rays in the neighborhood of the axis are only deflected by a small angle and then the diffraction efficiency would be low. For the correct wavelength and angle of incidence, so that the Bragg condition of holography is fulfilled, HOEs, like blazed DOEs, exhibit only one dominant diffraction order $m = m_{\text{dom}}$ (normally $m_{\text{dom}} = 1$). But, if the angle of incidence or the wavelength change, the diffraction efficiency in the order m_{dom} decreases rapidly and light passes through the HOE without being deflected, i.e., most of the light is then in the order $m = 0$. For this reason, a HOE can be used for example for a head-up display to fade in some information under the Bragg angle without hindering the normal view onto the environment.

Traditional materials for HOEs like dichromated gelatin (DCG) are sensitive only in the blue–green spectral region (e.g., for light of an argon ion laser with $\lambda = 488$ nm). However, once recorded it will be illuminated in many applications (e.g., optical interconnects) by a wavelength in the red–infrared spectral region. Unfortunately, the wavelength mismatch between recording and reconstruction illumination introduces aberrations.

If the two desired reconstruction waves at the wavelength λ_2 have the phases $\Phi_{\mathrm{r},\lambda 2}$ and $\Phi_{\mathrm{o},\lambda 2}$ in the surface plane of the HOE (the subscripts r and o refer to interferometry reference and object, respectively), the phase function Φ of the HOE which has to be recorded is

$$\Phi(x, y) = \Phi_{\mathrm{o},\lambda 2}(x, y) - \Phi_{\mathrm{r},\lambda 2}(x, y) \qquad [11]$$

If our discussion here is restricted to holographic lenses, the two reconstruction waves will be spherical (or plane) waves (see Figure 3b) with the center of curvature at the points $\mathbf{r}_{\mathrm{r},\lambda 2}$ and $\mathbf{r}_{\mathrm{o},\lambda 2}$ and eqn [11] is:

$$\begin{aligned}\Phi(x,\ y) = {} & \frac{2\pi\sigma_{\mathrm{o},\lambda 2}}{\lambda_2}\sqrt{(x - x_{\mathrm{o},\lambda 2})^2 + (y - y_{\mathrm{o},\lambda 2})^2 + z_{\mathrm{o},\lambda 2}^2} \\ & - \frac{2\pi\sigma_{\mathrm{r},\lambda 2}}{\lambda_2}\sqrt{(x - x_{\mathrm{r},\lambda 2})^2 + (y - y_{\mathrm{r},\lambda 2})^2 + z_{\mathrm{r},\lambda 2}^2}\end{aligned} \qquad [12]$$

The parameters $\sigma_{\mathrm{o},\lambda 2}$ and $\sigma_{\mathrm{r},\lambda 2}$ are either $+1$ for a divergent spherical wave or -1 for a convergent spherical wave. The surface of the HOE itself is in the plane at $z = 0$.



Figure 3 Schematic view of the (a) recording and (b) reconstruction setup for a holographic lens. The recording is made at wavelength λ_1 and the reconstruction at wavelength λ_2.

The task is now to find two recording waves which construct nearly the same three-dimensional interference pattern in the hologram at the recording wavelength λ_1. This means that eqn [12] has to be fulfilled exactly for the difference of the phases of the two recording waves in the plane $z = 0$ and, additionally, the Bragg condition has to be fulfilled at least approximately. So, the next step is to calculate one of the recording waves with phase $\Phi_{\mathrm{r},\lambda 1}$ so that the Bragg condition is fulfilled. This can be done approximately with a third-order theory resulting in a spherical wave or nearly exactly with an iterative numerical procedure resulting generally in an aspheric recording wave. If $\Phi_{\mathrm{r},\lambda 1}$ is known, the other recording wave with phase $\Phi_{\mathrm{o},\lambda 1}$ is calculated by

$$\Phi_{\mathrm{o},\lambda 1}(x, y) = \Phi(x, y) + \Phi_{\mathrm{r},\lambda 1}(x, y) \qquad [13]$$

At least this recording wave will be aspheric. To generate such an aspheric wave it is traced by ray tracing to a plane where the two recording waves are spatially separated. There, either a DOE or a combination of a DOE and a lens are used to generate the aspheric wave. The calculations of the phase function of the DOE are done again by using an equation like [11] whereby one wave is the propagated aspheric wave (possibly propagated also through a lens) and the other is normally a plane off-axis wave with which the DOE will be illuminated in the real recording setup (see Figure 3a). Here, the off-axis angle is necessary to allow spatial filtering of disturbing diffraction orders of the DOE which will be normally fabricated as a binary DOE.

Experiments of our own showed (see the literature) that nearly diffraction-limited holographic lenses with a numerical aperture of NA = 0.4 can be fabricated by correcting the aberrations of about 28 wavelengths peak-to-valley (for the reconstruction at 633 nm wavelength) due to the wavelength mismatch between recording at 488 nm wavelength and reconstruction at 633 nm wavelength by using a DOE in the recording setup.

Testing of Aspheric Surfaces by Using a DOE as Aberration Compensating Element

An important application for DOEs is testing aspheric surfaces and nowadays more and more companies use DOEs to test aspheric surfaces which are used for example in the objectives of lithographic wafer steppers to produce highly integrated microelectronic circuits.

In this testing setup the DOE is illuminated by a wave with phase Φ_{in} to generate a wave with phase Φ_{out} that is incident perpendicular to the aspheric surface (see Figure 4). After reflection at the asphere



Figure 4 Scheme showing the basic elements for testing an aspheric surface.

the wave is retro-reflected and takes the same path if the asphere has no surface deviations and no misalignments. This means that the setup is completely symmetric for a reflection at the aspheric surface. Therefore, the optical path lengths have to be identical for all rays on the asphere. To calculate the phase function of the DOE the following steps are made:

- A grid of N rays starting perpendicularly on the aspheric surface and having all phase zero (due to the fact that the phase has to be identical it can be set to zero) is traced to the plane of the DOE. N depends on the shape and numerical aperture of the asphere and the grid will be in most cases two dimensional and regular or one dimensional (along one radial section of the asphere) and regular if the asphere and the system are completely rotationally symmetric. As a rule of thumb the number N of rays has to be more than twice the number of polynomial coefficients if the asphere is described by a polynomial.
- The phase of these rays is the function $-\Phi_{\text{out}}$ (the negative sign is necessary because the rays take the opposite direction) and is now known at some points (x_i, y_i) with $i \in \{1, 2, \ldots, N\}$.
- The phase Φ_{in} of the incident wave which is in practice either a plane wave or a spherical wave is calculated in the plane of the DOE. If the incident wave is generated by a lens having aberrations it is again calculated by ray tracing, otherwise it can be calculated analytically.
- Now, the phase function Φ of the DOE can in principle be calculated with the help of eqn [4].

However, the phase Φ_{out} (and possibly also Φ_{in}) is known only at some points (x_i, y_i), but it has to be known at all points of the DOE. Therefore in practice an analytical representation of the phase functions of the incident and output wave has to be calculated. This can be done by fitting a polynomial to the phase values using a least squares fit. In this case the coordinates, at which the phase values are known, can be quite arbitrary as long as the sampling is dense enough. For a rotationally symmetric system the polynomial should also be rotationally symmetric, i.e., a polynomial P_{rot} depending only on the radius coordinate r

$$r = \sqrt{x^2 + y^2} \qquad [14]$$

$$P_{\text{rot}}(r) = \sum_{j=0}^{G} a_j r^j \qquad \text{or} \qquad P_{\text{rot}}(r) = \sum_{j=0}^{G/2} a_{2j} r^{2j} \qquad [15]$$

where G is the degree of the polynomial, i.e., the highest power in r. In these two cases the number N of sampling points lying along one radial section of the rotationally symmetric optical system should be larger than $2G$ or G, respectively.

For general non-symmetric systems a Cartesian polynomial P_{cart} can be used, e.g.,

$$P_{\text{cart}}(x, y) = \sum_{j=0}^{G} \sum_{k=0}^{G-j} a_{jk} x^j y^k \qquad [16]$$

Here, the number of coefficients of the polynomial is $(G + 1)(G + 2)/2$ and the number N of sampling points should again be larger than twice the number of coefficients, i.e., $N > (G + 1)(G + 2)$.

For both types of polynomials the coefficients a_j or a_{jk} have to be calculated so that the merit function M

$$M(\mathbf{a}) = \sum_{i=1}^{N} (P(x_i, y_i) - \Phi_j(x_i, y_i))^2; \quad j \in \{\text{in, out}\} \qquad [17]$$

is minimized. The symbol P means either P_{rot} or P_{cart}. The vector $\mathbf{a}$ symbolizes the coefficients $\mathbf{a}_j$ or $\mathbf{a}_{jk}$. By differentiating M with respect to all coefficients and setting the partial derivatives to zero a system of linear equations is obtained which can be solved by standard procedures. As mentioned before, the number N of independent sampling points has to be at least double the size of the number of coefficients of the polynomial. Otherwise, the polynomial can ‘swing’ between the sampling points and the polynomial fits well to the desired phase function only at the sampling points but not at other points in between.

For very irregular aspherics with a fast change of the local curvature it might by necessary not to take a global polynomial fit but a spline fit, i.e., a set of adjacent local polynomials with several continuity conditions at the border area of each local polynomial. In this case the total number of coefficients used to describe the phase functions and Φ_{in} and Φ_{out} of the DOE will be increased compared to the description by a global polynomial. Then, the number N of rays for the calculation has also to be increased accordingly.

So, in this example the DOE acts as a null-compensator for the asphere and at first sight it is not a typical example for aberration correction. However, by regarding the complete system the DOE compensates the aberrations, i.e., deviations from a spherical wave, generated by the asphere which are primary and higher-order spherical aberrations if the asphere is rotationally symmetric and more general aberrations otherwise. This example shows how the phase function of a DOE can be designed straightforwardly for correcting aberrations if there is only one well-defined wavefront propagating through the optical system. This design method can also be used for other optical systems where the input and the output wavefront of the DOE are well defined.

Numerical Optimization of DOEs in Optical Systems

In a general optical system, where a DOE is not only used to compensate the aberrations for one specific incident wave but for different incident waves (optical system with a field), it is not possible to calculate the optimum phase function in such a straightforward way as given above. However, a DOE is in principle similar to an asphere in an optical system, so that the design rules for including aspherics in optical systems can be used in some cases as long as monochromatic aberrations are considered. Nevertheless, one should keep in mind that a DOE is, according to the Sweatt model, an asphere with high refractive index and small height, i.e., the deflection of the light rays occurs in a plane (or on a curved surface if the DOE is situated on a curved substrate). Therefore, the design rules for aspheric surfaces can be used only if the high refractive index of the Sweatt model is used in the design.

In the general case only a numerical optimization can be used. For this, it is very important to select an appropriate mathematical representation of the phase function of the DOE.

For rotationally symmetric optical systems also the phase function of the DOE should be rotationally symmetric. Therefore, in such a case it is useful to write the phase function Φ as a polynomial in the radius coordinate r as given in eqns [14] and [15]. Then, the $(G + 1)$ or $(G/2 + 1)$ coefficients a_j have to be optimized, whereby a_2 is proportional to the focal power of the DOE, whereas the other coefficients represent aspheric terms. Depending on the numerical aperture and on the application the degree G of the polynomial can be increased in order to achieve a better solution. Nevertheless, the degree in the optimization should be as small as necessary in order to avoid 'swinging effects' and numerical instabilities of the polynomial. To determine the smallest adequate degree an iterative method has to be used by starting with a quite small degree (e.g., 4). If the result of the optimization is not good enough the degree has to be increased until the result of the optimization is satisfying.

For non-rotationally symmetric optical systems a Cartesian polynomial like in eqn [16] can be taken and all the $(G + 2)(G + 1)/2$ coefficients a_{jk} have to be optimized. Since the number of free parameters is in this case larger than the number of free parameters in the rotationally symmetric case the convergence of the optimization may take a long time and the risk to break down in a local minimum of the multidimensional parameter space increases.

In principle, the calculation of a DOE used, e.g., for testing an aspheric surface can also be done by optimizing the coefficients of the polynomial representing the phase function of the DOE. Nevertheless, as a general rule it can be said that a direct calculation of the phase function is always more efficient than a numerical optimization, if the direct calculation is possible. In practice, it can be seen that the maximum degree of a polynomial, which is directly calculated by the method described in the last section, is always smaller than the degree which is necessary in a numerical optimization to achieve convergence of the optimization.

Of course, in such cases where several different types of aberrations (on-axis aberrations like spherical aberration, off-axis aberrations like astigmatism and coma or field aberrations like field curvature or distortion) have to be corrected in an optical system a direct calculation of the phase function is not possible so that only the numerical optimization can provide a solution.

Up to now only monochromatic aberrations have been discussed. But as stated at the beginning of this article the strong dispersion of a DOE having opposite sign to the dispersion of a refractive element offers additional applications of DOEs by correcting chromatic aberrations. The principle of doing this is described in the following.

Correction of Chromatic Aberrations

The focal power $1/f$ (f is the focal length of the lens) of a thin refractive lens consisting of two spherical surfaces with radii of curvature R_1 and R_2 and made of a material (glass) with refractive index n is

$$\frac{1}{f(\lambda)} = (n(\lambda) - 1)\left(\frac{1}{R_1} - \frac{1}{R_2}\right) \qquad [18]$$

where λ is the wavelength of the illuminating light.

This equation is valid for all wavelengths and so also for the commonly used wavelength $\lambda_d = 587.6$ nm (yellow d-line of helium) which is near the center of the visible spectrum. Then $1/R_1 - 1/R_2$ can be expressed as $1/((n_\mathrm{d} - 1)f_\mathrm{d})$ and the focal power depends on the wavelength as

$$\frac{1}{f(\lambda)} = \frac{n(\lambda) - 1}{n_\mathrm{d} - 1}\frac{1}{f_\mathrm{d}} \qquad [19]$$

where n_d and f_d are the refractive index and the focal length at $\lambda_\mathrm{d} = 587.6$ nm, respectively. So, by combining two thin lenses made of materials with refractive indices n_1 and n_2 and focal lengths f_1 and f_2 the focal power of the doublet assuming a zero distance between the two lenses is:

$$\begin{aligned}\frac{1}{f_\mathrm{ges}(\lambda)} &= \frac{1}{f_1(\lambda)} + \frac{1}{f_2(\lambda)}\\ &= \frac{n_1(\lambda) - 1}{n_{1,\mathrm{d}} - 1}\frac{1}{f_{1,\mathrm{d}}} + \frac{n_2(\lambda) - 1}{n_{2,\mathrm{d}} - 1}\frac{1}{f_{2,\mathrm{d}}} \qquad [20]\end{aligned}$$

For an achromatic doublet the focal power should be equal for two different wavelengths which are commonly the wavelengths $\lambda_\mathrm{F} = 486.1$ nm (blue F-line of hydrogen) and $\lambda_\mathrm{C} = 656.3$ nm (red C-line of hydrogen) which mark the limits of the well visible spectrum (of course the visible spectrum itself is broader but the sensitivity of the human eye to wavelengths below λ_F or beyond λ_C is quite bad). Therefore, the following equations result:

$$\begin{aligned}\frac{1}{f_\mathrm{ges}(\lambda_\mathrm{F})} = \frac{1}{f_\mathrm{ges}(\lambda_\mathrm{C})} &\Rightarrow \frac{n_1(\lambda_\mathrm{F}) - n_1(\lambda_\mathrm{C})}{n_{1,\mathrm{d}} - 1}\frac{1}{f_{1,\mathrm{d}}}\\ &= -\frac{n_2(\lambda_\mathrm{F}) - n_2(\lambda_\mathrm{C})}{n_{2,\mathrm{d}} - 1}\frac{1}{f_{2,\mathrm{d}}} \qquad [21]\end{aligned}$$

By introducing the Abbe number V_d

$$\begin{aligned}V_\mathrm{d} &= \frac{n_\mathrm{d} - 1}{n_\mathrm{F} - n_\mathrm{C}}\\ &= \frac{n(\lambda_\mathrm{d} = 587.6\ \mathrm{nm}) - 1}{n(\lambda_\mathrm{F} = 486.1\ \mathrm{nm}) - n(\lambda_\mathrm{C} = 656.3\ \mathrm{nm})} \qquad [22]\end{aligned}$$

equation [21] can be simplified to

$$V_{1,\mathrm{d}}f_{1,\mathrm{d}} = -V_{2,\mathrm{d}}f_{2,\mathrm{d}} \qquad [23]$$

Now, the wavelength dispersion of all conventional materials (glasses, polymers, etc.) is such that the refractive index decreases with increasing wavelength, i.e. the material has a so-called normal dispersion. This means that the Abbe number V_d is always positive and ranges from about 20 for high-dispersive glasses (e.g., SF59) to more than about 80 for low-dispersive glasses (e.g. Ultran 20). So, to fabricate a refractive achromatic doublet with a positive focal power it is necessary to take a positive lens with focal length f_1 made of a low-dispersive glass with a large Abbe number $V_{1,\mathrm{d}}$ and a negative lens with focal length f_2 made of a high-dispersive glass with a small Abbe number $V_{2,\mathrm{d}}$ (see Figure 5a). Therefore, the resulting focal power of the achromatic doublet

$$\frac{1}{f_{\mathrm{ges,d}}} = \frac{1}{f_{1,\mathrm{d}}} + \frac{1}{f_{2,\mathrm{d}}} = \frac{1}{f_{1,\mathrm{d}}}\left[1 - \frac{V_{2,\mathrm{d}}}{V_{1,\mathrm{d}}}\right] \qquad [24]$$

is always smaller than the focal power of the positive lens with focal power $1/f_{1,\mathrm{d}}$ alone.

The situation is completely different if a refractive and a diffractive lens are used. From the Sweatt model


n_1, $V_{1,\mathrm{d}}$
n_2, $V_{2,\mathrm{d}}$
(a)
n_1, $V_{1,\mathrm{d}}$
(b)

Figure 5 Structure of achromats: (a) refractive achromatic doublet consisting of a positive lens with low dispersion and a negative lens with high dispersion; (b) hybrid achromatic lens consisting of a positive refractive lens and a positive diffractive lens.

of a DOE (eqn [3]) it is known that the refractive index n_{sweatt} is proportional to the wavelength λ

$$n_{\mathrm{sweatt}}(\lambda) = \frac{n_0}{\lambda_0}\lambda = \frac{n_{\mathrm{d}}}{\lambda_{\mathrm{d}}}\lambda \qquad [25]$$

Therefore, the Abbe number of a DOE is

$$\begin{aligned} V_{\mathrm{d}} &= \frac{n_{\mathrm{d}} - 1}{n_{\mathrm{F}} - n_{\mathrm{C}}} \\ &= \frac{\lambda_{\mathrm{d}}}{\lambda_{\mathrm{F}} - \lambda_{\mathrm{C}}}\left(1 - \frac{1}{n_{\mathrm{d}}}\right) \overset{n_{\mathrm{d}}\to\infty}{=} \frac{\lambda_{\mathrm{d}}}{\lambda_{\mathrm{F}} - \lambda_{\mathrm{C}}} \\ &= -3.452 \end{aligned} \qquad [26]$$

Here, we used the fact that the accuracy of the Sweatt model increases with increasing refractive index so that the Abbe number of a DOE is achieved in the limit of an infinite refractive index. So, it can be seen that the Abbe number of a DOE is a small negative constant. This means that the dispersion of a DOE is high and opposite in sign to that of a refractive element. Therefore, according to eqns [23] and [26] a positive refractive lens with a large focal power (i.e., small focal length) and a positive diffractive lens with a small focal power (i.e., long focal length) can be combined to form an achromatic doublet with a focal power larger than the focal power of one of the two lenses alone (see Figure 5b). By using eqns [19] and [25] the focal power of a diffractive lens can be calculated with the Sweatt model (n very big $\rightarrow n - 1 \approx n$):

$$\frac{1}{f_{\mathrm{DOE}}(\lambda)} = \frac{\lambda}{\lambda_{\mathrm{d}} f_{\mathrm{d}}} \qquad [27]$$

In practice, the lenses are neither thin nor is the distance between them zero. In this case the equations for the design of a hybrid achromatic doublet are more complex (see Further Reading). Nevertheless, the given equations can be used for a first design and to understand the principal behavior.

Another advantage of a hybrid achromatic doublet is that the DOE can in addition behave like an asphere. Therefore, e.g., the spherical aberration can be corrected with the aspheric terms of the DOE provided that the spherical aberration is considerably smaller than the phase term encoded in the DOE to correct the chromatic aberrations. Otherwise, the correction of the monochromatic (spherical) aberration will disturb the correction of the chromatic aberrations. A comparison of a simple hybrid achromat, consisting of a planoconvex lens with the diffractive structure made directly onto the plane surface of the refractive lens and a conventional refractive achromatic doublet shows that the optical performance of the hybrid achromat is a little bit worse than that of the refractive achromatic doublet regarding, for example, off-axis aberrations. A simple explanation of this is that a refractive achromatic doublet has three spherical surfaces and two glasses, i.e., in total five parameters, whereas a hybrid achromat has one spherical surface, one glass and the DOE with a paraxial term and an aspheric term, i.e. in total about four parameters. Of course, the merit of these different types of parameters is not identical so that this assessment is only qualitative.

In the case of hybrid achromatic elements for a broad wavelength range (e.g., for the whole visible wavelength range) the dependence of the diffraction efficiency on the wavelength may be a limiting factor because the other diffraction orders behave like stray light and reduce the maximum contrast of the image. Therefore, special laminated blazed diffractive optical elements made of laminae of two or more different materials are described in the literature which show a nearly achromatic behavior of the diffraction efficiency but the 'normal' dispersion of DOEs. DOEs are in the meantime used in zoom lenses (see the cited patent in Further Reading) to correct chromatic aberrations.

Summary

In this article the possibilities of correcting monochromatic and chromatic aberrations in optical systems by using diffractive optical elements have been discussed. There are several advantages and disadvantages of using DOEs.

Advantages:

- DOEs offer many degrees of freedom in the design. By using modern lithographic fabrication techniques the fabrication of a DOE with a strongly aspheric phase function is just as expensive as fabricating a simple Fresnel zone lens with a quadratic phase function. So, DOEs can be used in some cases instead of aspheric surfaces which are more expensive. In addition, the lithographic fabrication technique guarantees a quite good accuracy concerning the phase function of the DOE compared to the more difficult fabrication of well-defined aspheric surfaces.
- The strong chromatic dispersion with the opposite sign to that of a refractive element allows the correction of chromatic aberrations. DOEs also give in this case an additional degree of freedom in the design because aspheric terms of the phase function can correct in addition monochromatic aberrations of the system as long as these aberrations are considerably smaller than the quadratic term of the phase function which corrects the chromatic aberrations.

Disadvantages:

- DOEs often exhibit not only one diffraction order but several diffraction orders due to fabrication errors, a broad spectrum of application wavelengths or because some DOEs naturally have several diffraction orders like, for example, binary DOEs. This can produce disturbing light in the optical system and limit the application.
- The strong dispersion can restrict the application in monochromatic systems because it requires in some cases (e.g., for testing aspheric surfaces) not only a relative constancy, i.e., constant but the absolute value does not have to be hit exactly, of the illuminating wavelength but an absolute constancy because otherwise systematic aberrations are introduced by the DOE.

So, there are many advantages of DOEs compared to other optical elements but on the other hand a DOE is not a magic bullet in correcting aberrations in optical systems. Depending on the system a careful assessment of the advantages and disadvantages has to be performed in order to find the best solution.

List of Units and Nomenclature

Abbe number	real number	V_d
Angle	[rad]	φ
Cartesian coordinates	[m]	x, y, z
Coefficients of a polynomial	different negative powers of m	a
Components of the ray vector	real numbers	e_x, e_y, e_z
Degree of a polynomial	integer number	G
Diffraction order	integer number	m
Focal length	[m]	f
Grating frequencies in x and y direction	$[\mathrm{m}^{-1}]$	ν_x, ν_y
Height of a lens surface	[m]	h
Local grating periods in x and y direction	[m]	p_x, p_y
Merit function	real valued function	M
Modulus of the wave vector	$[\mathrm{m}^{-1}]$	k
Nabla differential operator $\begin{pmatrix} \partial/\partial x \\ \partial/\partial y \\ \partial/\partial z \end{pmatrix}$	$[\mathrm{m}^{-1}]$	∇
Number of sampling points/rays	integer number	N
Optical phase, phase function	[rad]	Φ
Polynomial	real valued function	P
Radial coordinate	[m]	r
Refractive index	real number	n
Sign variable	either +1 or −1	σ
Symbol for partial differentiation		∂
Unit vector in ray direction	vector with three real components	$\mathbf{e}$
Wavelength	[m]	λ

See also

Geometrical Optics: Aberrations.

Further Reading

Born M and Wolf E (1997) *Principles of Optics*, 6th edn. Cambridge, UK: Cambridge University Press.

Fairchild RC and Fienup JR (1982) Computer-originated aspheric holographic optical elements. *Optical Engineering* 21: 133–140.

Falkenstörfer O, Lindlein N, Keinonen T and Schwider J (1996) Diffraction-limited holographic lenses in dichromated gelatine. *Optical Engineering* 35: 2026–2033.

Herzig HP (1997) *Micro-Optics*. London: Taylor & Francis.

Kogelnik H (1969) Coupled wave theory for thick hologram gratings. *The Bell System Technology Journal* 48: 2909–2947.

Kress B and Meyrueis P (2000) *Digital Diffractive Optics*. Chicester, UK: Wiley.

Latta JN (1971) Computer-based analysis of holography using ray tracing. *Applied Optics* 10: 2698–2710.

Lindlein N, Schwider J, Schrader M, *et al.* (1993) Wavelength mismatch correcting elements for volume holograms written on a laser pattern generator. *Journal of Modern Optics* 40: 647–661.

MacGovern AJ and Wyant JC (1971) Computer generated holograms for testing optical elements. *Applied Optics* 10: 619–624.

Meier RW (1965) Magnification and third-order aberrations in holography. *Journal of the Optical Society of America* 55: 987–992.

Nishio A (1999) Zoom lens with diffractive optical elements. United States Patent 5978153.

Offner A (1966) Ray tracing through a holographic system. *Journal of the Optical Society of America* 56: 1509–1512.

Sinzinger S and Jahns J (1999) *Microoptics*. Weinheim: Wiley-VCH.

Stone Th and George N (1988) Hybrid diffractive-refractive lenses and achromats. *Applied Optics* 27: 2960–2971.

Sweatt WC (1977) Describing holographic optical elements as lenses. *Journal of the Optical Society of America* 67: 803–808.

Upatnieks J, Vander Lugt A and Leith E (1966) Correction of lens aberrations by means of holograms. *Applied Optics* 5: 589–593.

Welford WT (1975) A vector raytracing equation for hologram lenses of arbitrary shape. *Optical Communications* 14: 322–323.

Winick K (1982) Designing efficient aberration-free holographic lenses in the presence of a construction-reconstruction wavelength shift. *Journal of the Optical Society of America* 72: 143–148.

Applications of Diffractive and Micro-Optics in Lithography

V Kettunen, Heptagon, Zurich, Switzerland

H P Herzig, University of Neuchâtel, Neuchâtel, Switzerland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Most aspects of modern life are thoroughly influenced by the micro-electronics industry through microchips, such as microprocessors and memory chips. Optical lithography has been a key factor in the rapid pace of integration that drives the development of the micro-electronics industry. The photolithography process not only facilitates the fabrication of the chips, but also directly influences the limits of the obtainable chip performance in terms of speed or storage capacity, through the minimum feature size that can be created in the lithography steps. The increasing resolution demands of the IC industry, outlined in the International Technology Roadmap for Semiconductors as technology nodes, mean continuing demand for improvements in the photolithography systems.

The challenges to the improvements are encapsulated in the equation for the resolution of an optical lithography system:

$$R = k_1 \lambda / NA \qquad [1]$$

which expresses the resolution R in terms of the smallest resolvable half-pitch as a function of the wavelength λ, the numerical aperture NA of the exposure system and the unit less constant k_1, which is used as a measure of lithographic difficulty, with smaller values indicating a more challenging process. Traditionally, the increase in the resolution has been obtained by decreasing the used wavelength, with the current mark for volume production systems currently standing at 193 nm. Within each wavelength, further reduction has been traditionally obtained by increasing the numerical aperture towards the mathematical limit of 1. Finally, several so-called Resolution Enhancement Techniques (RET) have been introduced to reduce k_1, in order to reach subwavelength technology nodes within each lithography wavelength generation. It is in connection with these techniques that micro-optics has found a role in modern lithography systems.

In this chapter we discuss the ways micro-optics are being utilized in lithography systems. We will start with a brief overview of conventional lithography systems, of the essential parts of such systems as well as the special resolution enhancement techniques utilized in the systems. We will then discuss the utilization of micro-optics within the context of lithography systems, along with the unique challenges in terms of design and fabrication that are associated with such applications. Finally, we will briefly discuss nonconventional lithography applications, especially those based on utilization of micro-optics. It should be noted that the motivation of this article is to describe the issues related to the use of micro-optical elements in a modern lithography system and is not intended as a review of the modern lithography systems, nor is it a review of micro-optics.

Overview of Conventional Lithography Systems

Photolithography is a process whereby a specified pattern or mask is transferred onto a wafer using photons. In the process a photosensitive material, commonly known as a resist, is initially used to record the pattern that is generated when the mask is illuminated. After exposure, the resist is developed. The resist is referred to as positive or negative, depending on whether it is removed or remains, respectively, after the development of the irradiated regions. After its development, the pattern in the resist is then transferred onto the wafer using suitable chemical processes, such as wet chemical etching or dry plasma etching.

Several different lithographical techniques exist. The oldest and simplest is contact printing, where a photomask is brought into contact with a layer of photoresist on the wafer. Although this technique can reproduce high-resolution features, the contact between the wafer and the mask can lead to problems with cross contamination, and can damage either the wafer or the mask. Contact printing is mainly used nowadays in laboratory environments for small series of photolithography steps. A slightly more complicated technique is proximity printing, in which the photomask is held in close proximity to the surface of the wafer without actual contact. This avoids the problems of contamination and damage, but due to diffraction effects, reduces the maximum resolution of the process. Nevertheless, proximity printing remains a valuable technique for lithography applications, that do not require the highest possible resolution.

Modern volume production photolithography systems are based on the use of a projection system to image a mask onto a wafer through a complex system of lenses. There exist several variations of the basic idea. In some systems the entire mask is imaged at once onto the wafer. This approach works only when the feature size on the mask is reasonably large, in the range of a few microns. Reproducing smaller features with this approach is generally not possible, as the demands on the optical quality of the projection system, in the form of allowed aberrations, become extremely difficult to meet, especially when the physical size of the optical components increases with the reducing feature size. Therefore, so-called wafer steppers are used in modern microchip fabrication. The basic idea of a wafer stepper is to image only a small region of the mask onto the wafer, and pattern the entire surface area in consecutive steps.

The centerpiece of a wafer stepper is the exposure system. Its task is to image desired patterns from the photomask to their proper positions on the surface of the wafer. In many systems this process includes a size reduction between the patterns on the photomask and on the wafer. This reduces the dimensional accuracy requirements, such as feature size and positioning for the mask fabrication by whatever is the de-magnification of the lithography system. However, it also increases the complexity of the exposure system, as significance of aberrations is increased. The requirements of microchip production mean that the image of the photomask with submicron features must be reproduced on the wafer with a dimensional accuracy of only a few tens of nanometers and aligned to a specific position within a fraction of the linewidth. Furthermore, these tolerances must be guaranteed over the entire exposure field that is typically several square centimeters. It is not surprising that the resulting complex piece of optics costs several millions dollars.



Figure 1 Schematic illustration of the exposure system.

The exposure system consists of a projection lens, illumination system, and wafer management system, as illustrated schematically in Figure 1.

A typical projection lens is a complicated lens system. As the resolution of a lens system is inversely proportional to the diameter of the lenses, the lenses in photolithographic systems can have diameters up to 250 mm, and the whole system is arranged inside a massive barrel-frame. The aim of the projection lens in the entire exposure system is to image the pattern from the photomask to the wafer. The projection lens is primarily responsible for the resolution and must therefore fulfill the highest optical requirements. To produce the smallest possible image, diffraction effects alone must essentially limit the resolution of the system. This means that the optical aberrations over the exposure field of several square centimeters must be virtually eliminated, by the wavefront deviations being less than a fraction of the wavelength.

The illumination system transfers the illumination source through the photomask to the entrance of the projection system. The main requirements for the illumination system are to collect most of the light into the system and to ensure that the irradiance of the photomask is uniform to within a few percent. In addition, resolution enhancement techniques, based on off-axis illumination, require that the illumination pattern on the photomask has a specific shape. We will discuss these requirements later in more detail. In general terms, the illumination system is less complicated than the projection system, especially with regard to the elimination of aberrations, due to the fact that precise imaging is not required in the illumination system.

Although the wafer management system is outside the scope of this article, we note in passing that it maintains the position, orientation, and movement of the wafers through the exposure system. Again, high precision is required to ensure the successful exposure of the desired pattern to the wafer.

Resolution Enhancement Techniques

In most modern lithography systems the achievable maximum resolution is increased via the use of one or more special resolution enhancement techniques (RET). These are essentially creative refinements of the lithography technology, based on theoretical optics papers published often decades before their first application in the lithography process in the late 1980s and early 1990s. There are essentially three RET approaches: Off-Axis Illumination (OAI), Optical Proximity Correction (OPC), and Phase Shifted Masks (PSM).

In optical proximity correction the basic idea is to predistort the mask pattern in order to overcome the proximity effects caused by the optics and the different processes. This is done either using a set of pre-existing rules describing the connection between a mask pattern and its realization on the wafer, using advanced models to predict the proximity effects during the lithography process, or with some combination of both. The key difficulties with OPC are related to the fabrication of the predistorted mask and to the accuracy of the used distortion rules or proximity effect models. Finally, it should be noted that OPC is strictly speaking not a true resolution enhancement technique, as it only enhances the effective resolution and not the theoretical resolution limit of the process defined by the optics.

In phase shifted masks the improvement in the resolution is obtained by altering the phase of light passing through different portions of the mask, creating regions of destructive interference in the image. This leads to higher contrast, which helps to improve the effective patterning resolution. However, as with OPC, there is no true resolution enhancement in terms of the theoretical resolution limit. There are two main difficulties with application of PSM. First, it is not straightforward to introduce required phase shifts into an arbitrary design layout, because some geometrical shapes, such as junctions are harder to realize than others. Another problem lies with the mask fabrication, which requires careful calibration of the material layers and can be very complicated and costly compared to fabrication of conventional binary masks.

For the purposes of this article, only off-axis illumination is discussed, as both OPC and PSM are essentially mask-based techniques and thus provide no opportunity for micro-optics. Off-axis illumination refers to any illumination scheme that significantly reduces or eliminates the light hitting the mask at near normal incidence, leading to the diffraction pattern of the mask being shifted on the projection lens. The principle behind the resolution enhancement, obtained by introducing such a shift, is schematically illustrated in Figure 2 for periodic pattern.



Figure 2 Schematic illustration of effect of off-axis illumination on image formation.

The mask pattern can be imaged if at least two diffraction orders generated by the mask pass through the pupil of the projection lens. Using on-axis illumination, the minimum feature size of the system is reached when the period of the mask pattern is so short that the ± 1st diffraction orders can no longer pass through the pupil. If the illumination is moved off-axis, the diffraction pattern is shifted and the second diffraction order (in this case +1st) again passes the pupil. Thus the resolution has been increased. A secondary improvement in contrast may be obtained by shaping the diffraction orders falling onto the pupil, such that the filling of the pupil is optimized, i.e., such that less unwanted light contributing to the background illumination passes the pupil. Finally, the depth of focus of the system can be optimized by ensuring that the contributing orders (in this case 0th and +1st) are symmetric with regards to the optical axis.

The conventional way to realize off-axis illumination schemes is to introduce a suitable aperture to the illumination optics between the source and the mask. In order to effectively use off-axis illumination, the shape and size of the aperture, i.e., the illumination pattern, must be optimized for the specific mask shape and pitch. This optimization leads to four basic shapes, as illustrated in Figure 3. In most modern lithography systems these shapes



Figure 3 The four typical illumination patterns: disk, ring or annular, quadrupole, and dipole.

are available with different values of partial coherence factor, governed by the ratio of the numerical aperture of the illumination lens and projection lens, allowing control of proximity effects and edge sharpness.

Overview of Micro-Optics

There exists no generally agreed definition of micro-optics, but it typically means optical systems built to significantly smaller scales than conventional table-top systems, using components such as micro-lenses and microprisms with physical dimensions in the range of a couple of millimeters at most. Micro-optical systems also include so-called diffractive optical elements, which are usually optical components whose operation cannot be explained by Snell's law or the law of reflection. Such elements are usually macroscopically planar microstructures, consisting of features with dimensions from a couple of wavelengths to a few tens of microns, and are designed by advanced numerical algorithms based on diffraction theory.

In the past decade, micro-optics has emerged as a powerful new addition to the field of optics and optical systems, following improvements in micro-optics fabrication techniques, both via adaptation from established microelectronics fabrication processes and development of novel approaches, such as variable dose direct writing using either UV light or an electron beam. Additionally, emergence of replication techniques, such as injection molding or UV casting, allows the low-cost mass production of micro-optical elements, making micro-optics economically feasible for a wide range of consumer applications. Consequently, micro-optical elements, utilizing either refractive or diffractive surfaces, are now found in industrial applications such as material processing, in the optical telecom field, and in consumer electronics such as the digital video camera.

One of the major strengths of micro-optics, as compared to conventional optics, is their ability to realize complex optical functions into a compact form. This is especially true for micro-optics using diffractive optical elements, as diffractive elements may be designed to realize several optical functions such as focusing, filtering, or beam splitting at once allowing integration of several classical optical components into a single diffractive element.

Micro-Optics in Conventional Lithography Systems

The simplicity of contact or proximity printing means that there is little need or opportunity to incorporate additional functionality through inclusion of micro-optical elements. The only exception to this will be discussed in the final section of this article, where we will consider a nonconventional technique, which utilizes micro-optics and can be incorporated into proximity printing systems. However, in this section we will limit the discussion to projection-based lithography systems such as wafer steppers.

Let us consider the possible uses of micro-optics in the three main parts of the exposure system identified in the earlier section. It is obvious that the wafer management system, which is essentially mechanical, cannot be enhanced by inclusion of micro-optics. In principle, micro-optics could be incorporated into the projection system to reduce its weight and, to a lesser degree, complexity. However, it is important to note that using micro-optics to reduce the physical size, i.e., the diameter of the lenses in the projection system is not possible, as such reduction would increase the theoretical minimum feature size the system can resolve which is inversely proportional to the lens diameter. In practical terms, even the most advanced fabrication approaches used to realize micro-optical elements cannot yet produce elements with the precision and quality sufficient to meet the optical requirements associated with a lithographic projection lens. In general, the state of the art in micro-optics is such that it does not make sense to replace refractive lenses with diffractive ones unless the weight of the optics is a critical parameter in determining the merit of the system. This is not the case for wafer steppers.

Even though the optical requirements for the lenses in the illumination system are not as high as in the projections system, they are in practice still far too demanding for micro-optical elements. Therefore, the only area where micro-optics could be used in the illumination system is the generation of various illumination patterns needed for the off-axis illumination schemes used for resolution enhancement, as well as overall homogenization of light. An element meeting these goals is essentially a custom-designed diffuser, where both the generated angular range and the relative intensity of illumination in any given angular direction are controlled to a high degree.

Custom Diffusers for Illumination

As mentioned earlier, one of the strengths of micro-optics lies in its ability to combine different optical functions into a single element. When used in lithographic illumination systems, micro-optical elements can serve a dual purpose. The element can serve as an artificial aperture, effectively distributing the light over some predetermined angular range and at the same time minimizing light outside the range, allowing generation of various illumination patterns needed for the resolution enhancement via off-axis illumination. Unlike conventional solutions based on the use of actual apertures to generate the desired illumination patterns, distribution of light using micro-optical elements can be done with efficiencies up to 95%, with typical target efficiency being in the range of 90%, depending on the pattern complexity. At the same time, the element can be used to smooth the light distribution, improving the uniformity of the illumination. Typically the required uniformity error, i.e., allowed variations from the average illumination, is in the range of 5%, but can be as low as 1%.

In addition to the above-mentioned high-efficiency and -uniformity targets, optical quality requirements of modern lithography systems introduce unique challenges to the micro-optics used in such systems. First, micro-optical elements used in lithography systems must also exhibit low amounts of stray light, especially in formation of hot-spots. Typically, hot-spots are allowed to be only a few percent of the average illumination level. Because of the fact that the size, shape, and profile of the illumination beam can vary, partly due to variations in the source and partly because such variations improve the functionality of the lithography system, by, for example, controlling the partial coherence factor, the micro-optical elements must be virtually space-invariant. The elements must perform the same function regardless of where and how the illumination coming from the source hits the element. Furthermore, the elements themselves must have very low absorption, because the high power used could otherwise lead to destruction of the elements. This means that the materials must be carefully selected. Finally, the optical wavelengths used in advanced lithography systems are 248 nm or less. Because the feature size of a diffractive element scales down with the wavelength, the features in elements used are much smaller than in the case of elements used for applications in the visible region. Consequently the accurate fabrication of such elements becomes a formidable challenge, because most fabrication errors, such as mask misalignment, etch depth error or the way the sharp corners in diffractive elements get rounded during fabrication, increase in significance when the feature size is decreased.

There exist two distinct approaches for obtaining such custom-designed diffusers. We will now discuss the benefits and weaknesses of these two techniques in terms of efficiency, pattern uniformity, stray light, and ease of fabrication, in order to illustrate the trade-off a designer creating micro-optical elements for a lithography system has to consider.

Aperture Modulated Diffusers

One approach to acquire custom diffusers for illumination systems is to use an array of refractive or diffractive micro-lenses. More generally, the lens phase can be replaced by any phase obtained by geometrical considerations, i.e., by a geometrical map transform between the input and output planes of the optical system. The basic principle of an aperture modulated diffuser is to use the phase function to accurately control the angular divergence of the diffuser, while the shape of the desired intensity distribution is created by introducing a properly shaped aperture in which the phase function is contained. This basic principle is shown in Figure 4.



Figure 4 Basic principle of aperture modulated diffuser. The lens f-number determines the angular extend of the far field pattern, while the lens aperture shape determines the shape of the pattern.

The main benefit of using a lens phase lies in the ease of the design process, which essentially consists of selecting the numerical aperture of the lens to meet the angular size of the desired pattern, while more complicated phase profiles can be used to improve some aspects of the performance of the diffuser.

In terms of optical performance, aperture modulated diffusers typically achieve efficiency of up to 95% and low levels of stray light, easily fulfilling the target specifications outlined earlier, especially when refractive surfaces are used. However, since the lens aperture in the element plane controls the shape of the intensity distribution, the range of intensity distribution shapes is limited. This is necessary because it must be possible to tile the required aperture shape in order to realize an array of elements with high fill factor, i.e., to realize a space-invariant diffuser. Furthermore, introducing an aperture into the element plane means that intensity oscillations, due to boundary diffraction at the edge of the apertures, cannot be avoided. Consequently, the uniformity of the generated intensity distributions suffers. This is especially true in cases where the desired intensity pattern has sharp corners, where the intensity oscillations due to boundary diffraction, can easily be up to 50% of the average intensity of the desired intensity pattern. Figure 5 illustrates a typical far field intensity distribution obtainable with aperture modulated diffusers.



Figure 5 Typical intensity distribution obtainable with an aperture modulated diffuser. The overall distribution is smooth apart from the slow intensity oscillations at the edges resulting from diffraction at the aperture boundary.

One needs to consider several issues with regard to the fabrication of aperture modulated diffusers. For refractive aperture modulated diffusers, the main issue is the accurate realization of the required surface profile. The fabrication of large arrays of refractive elements having arbitrary surface profiles is still challenging. Resist reflow techniques, where the micro-lenses are realized by melting small islands of resist, lead to a spherical lens profile. Complicated and hard-to-control profile reshaping techniques are required if dramatic alterations from the spherical lens profiles are needed. Even though fabrication through direct writing techniques, such as laser writing offers more freedom, realization of arbitrary refractive surface remains a challenge. Therefore, use of refractive elements is mainly limited to cases where the lens profile can be close to the spherical shape. The most important of such cases are patterns with uniform circular or rectangular distributions. The former can be realized by proper selection of the numerical aperture of the lens, while the latter can be realized by combining two properly selected cylindrical lenses on opposite sides of the substrate.

For diffractive aperture modulated diffusers there are considerably less limitations in terms of what phase profiles can be attained. As long as the opening angles, i.e., the angular size of the pattern is below 10 degrees, the phase can be realized as a diffractive element. With diffractive elements, the main issue to consider is therefore the effect of typical fabrication errors such as profile depth and shape errors. First, the typical consequence of fabrication errors in the element is loss of efficiency via increase of stray light. Fortunately the errors do not generate sharp stray light peaks, with the obvious exception of the axis hot-spot. This results from the fact that both lens functions and more complicated phase functions designed by geometrical considerations, exhibit locally periodic structures, and the introduction of common fabrication errors then leads to redistribution of light away from the desired signal orders of these local structures to higher or lower orders. On the level of the whole intensity distribution, such redistribution appears as a constant rise in the background noise level, but will not lead to sharp intensity fluctuations.

Another issue related to the fabrication of aperture modulated diffusers appears when diffuser elements are fabricated using a series of photomasks, as it is typically the case with a relatively large size of the element. Although mask misalignment is essentially a random error, i.e., the direction and amount of the error are difficult to predict before hand, it easily leads to systematic and partly symmetric uniformity problems with aperture modulated diffusers.



Figure 6 Effect of mask misalignment on the intensity distribution with aperture modulated diffusers. Essentially random error leads to symmetric and systematic uniformity error due to locally periodic nature of the design.

Again the reason for this lies in the locally periodic nature of the elements. A single mask misalignment along some direction results in an erroneous profile shape in the structures, which are periodic in the direction of the alignment error. Consequently, the relative intensity distribution along that direction is changed. On the other hand, structures, where the period is perpendicular to the misalignment, are realized correctly. Furthermore, the local period of the phase function is often changing from the center of the element to the edge, meaning that the relative magnitude of the mask misalignment is different in different parts of the element. These facts lead to asymmetry in the overall intensity distribution, which is especially harmful with off-axis illumination patterns, as the asymmetry results in loss of the resolution gain obtained with off-axis illumination. Furthermore, as the source of the asymmetry is essentially a random error, compensation in the design is very difficult. Figure 6 illustrates the above-mentioned phenomena.

Fan-Out Based Diffusers

An alternative technique uses specially designed fan-out elements to produce a large number of closely spaced diffraction orders arranged in a desired pattern, as illustrated in Figure 7. Such an approach offers all the flexibility of diffractive elements, allowing generation of nearly arbitrary intensity distributions, especially if the elements can be realized as so-called multilevel elements, i.e., if the surface profile can have more than two distinct levels.



Figure 7 Basic principle of fan-out based diffusers. A grating is used to generate a high number of closely spaced diffraction orders arranged in the shape of the desired pattern.

The flexibility in the design comes at a cost, where specially developed design tools, such as the iterative Fourier transform algorithm, are required. Fortunately such tools are starting to become commercially available as emphasis and interest in wave-optical engineering, an extension of the classical optical engineering approaches, increases.

In terms of optical performance, fan-out based diffusers offer high uniformity as there are no boundary diffraction effects as with aperture modulated diffusers. Furthermore, by choosing the beam separation of the fan-out to be clearly smaller than the divergence of the incidence beam, it is possible to average out any local intensity variations from order to order, leading to a smooth overall intensity distribution. The remaining variations in the intensity distribution generated by a fan-out based diffuser can be as small as 1% of the average intensity.

As a trade-off for the improved performance in terms of uniformity compared to aperture modulated diffusers, fan-out based diffusers typically exhibit lower efficiency and, consequently, higher levels of stray light, even when no fabrication errors are present. This is a result of additional design freedoms being used to remove unwanted intensity oscillations from the far field regions, belonging to the desired intensity distribution, by introducing some noise outside these regions. Typically the efficiency of a fan-out based diffuser is in the range of 85–90%, or 5–10 percentage points lower than the efficiency of a comparable aperture modulated diffuser (should one exist). Furthermore, unlike aperture modulated diffusers, fan-out based diffusers can have stray light that forms hot-spots. If care is not taken during the design, these hot-spots may be up to 10% of the average intensity of the illumination pattern, even in the absence of fabrication errors. Figure 8 illustrates



Figure 8 Typical intensity distribution obtainable with a fan-out based diffuser. Overall distribution is smooth, but stray light appears outside the main pattern.



Figure 9 Effect of mask misalignment on the intensity distribution with fan-out based diffusers. The uniformity error appears randomly, allowing statistical compensation schemes.

a typical far field intensity distribution obtainable with fan-out based diffusers.

Fan-out based diffusers offer several advantages in terms of fabrication compared to mapping based diffusers. First, random errors, such as mask misalignment, do not lead to symmetric or systematic uniformity problems, but instead result in random local oscillations in the intensity pattern as illustrated in Figure 9. This allows special compensation schemes where the element is divided into segments, each of which has different fabrication tolerances but generates the same far field intensity distribution. If the fabrication tolerances of the individual designs are balanced correctly against the typical fabrication errors of the used fabrication methods, the loss of uniformity due to fabrication errors can be eliminated almost entirely. Furthermore, the flexibility of diffractive design allows for fabrication error-tolerant designs. This follows from the ability to combine several optical functions in a single optical element. The typical trade-off with designs with relaxed fabrication tolerances is that the optical performance of the element in terms of efficiency is worse than that of a conventional design if fabrication errors are not present.

Micro-Optics and Non-Conventional Lithography

In the previous section we have considered micro-optics in connection with conventional lithography approaches and shown that micro-optical elements can find a significant role in such systems. We conclude this article by considering briefly nonconventional lithography systems, focusing especially on a technique called micro-lens lithography, which is fundamentally based on the use of micro-optical elements.

The most straightforward way to improve existing lithography approaches is to further reduce the wavelength used in the exposure process. In X-ray lithography, the light source used in conventional lithography approaches is replaced by a cyclotron emitting light with wavelengths deep in the X-ray region. This leads to minimum resolution far lower than achievable by conventional techniques, but with the additional difficulty and cost of maintaining and running such a source.

The techniques that are currently considered as serious alternatives for conventional photolithography approaches are based on the use of particles other than photons in the fundamental exposure process. Techniques such as electron- or ion-beam lithography are routinely used to realize structures with feature size and positioning resolution of some tens of nanometers for use in both micro-electronics and micro-optics. The main drawback of these approaches is the cost involved in patterning large surface areas. Unlike optical lithography techniques, particle beam lithography cannot expose large surface areas at once, instead requiring painstaking scanning of the surface area with a relatively small writing beam. This leads to processing times that scale linearly with the required surface area, and consequently the throughput of such techniques is small. Therefore, particle beam lithography is not yet widely used in commercial fabrication of micro-electronics. However, it is worth noting that especially electron beam lithography is widely used in the origination of micro-optical components, as the relatively high cost of creating the master component can be offset in the final product by the inexpensive replication process. Such an approach allows the replicated end-product to meet the high optical requirements achievable only by high resolution surface control, yet remain affordable for use in, for example, consumer electronics. This has lead some in the micro-optics community to conclude that electrons are better suited for fabrication of components controlling photons, while photons are better suited for fabrication components controlling electrons.

In addition to particle beam lithography, other noteworthy techniques exist. For our purposes, the most interesting technique is the so-called micro-lens array lithography, where one or more micro-lens arrays are used to image the pattern of the photomask to the resist layer on the substrate. Although the resolution of this approach is limited to 3–5 microns, for applications such as with flat panel displays, micromechanics, or multichip module fabrication, this technique is of considerable interest.

It is well known that the geometrical aberrations scale down proportionally with the physical lens size. Thus, large areas can be imaged favorably by use of arrays of micro-lenses, where each lens images only a small section of the whole field. Such a setup is shown in Figure 10.

With this setup it is possible to expose a comparatively large area with a single exposure, thus eliminating the need for costly stepping operations and therefore increasing the throughput of the system. Analysis of the basic system shows that an array based on spherical micro-lenses of 1 mm focal length and 300 micron aperture can produce a nearly diffraction limited resolution on the order of 3–5 micrometers over a 300 micron field.

In terms of conventional lithography systems, the micro-lens array lithography has most in common with proximity printing. Both techniques achieve comparable resolutions, yet avoid damaging the mask or substrate by keeping the two separated by some finite working distance. However, micro-lens array lithography offers two distinct advantages over conventional proximity printing. First, the working distance between the imaging system and the substrate surface can be much larger, which further minimizes the risk of mask or substrate damage. Furthermore, added working distance allows lithography steps on nonflat surfaces, e.g., inside holes or grooves where conventional proximity printing would not be possible. Another advantage of the micro-lens array lithography is the larger depth of focus. With proximity printing, the resolution rapidly decreases with increasing distance. In micro-lens array lithography, the optimum resolution is obtained at the image plane, while a region of reasonable resolution extends forward and backward from this plane (Figure 11). This extension means that in the depth of field, resolution is less sensitive to changes in the working distance, which makes it better suited for practical applications.

In addition to the optical benefits of micro-lens array lithography, there also exist other practical benefits. Many micro-devices have a repetitive and



Figure 10 Basic geometry of micro-lens array lithography.



Figure 11 Depth of focus with micro-lens array lithography and conventional printing. (a) With micro-lens array lithography, the image of the mask is extended both forward and backward from the working plane at distance z. (b) In conventional printing, the resolution is rapidly reduced with increasing working distance z.



Figure 12 Ultra-flat micro-lens projection system (courtesy of R. Völkel, SUSS MicroOptics, Neuchâtel, Switzerland).

discrete nature with respect to some unit element. Such a unit element lends itself well to the imaging properties particular to lens arrays, as each lens of the array can be made to correspond to the unit cell of the particular micro-device making the imaging highly efficient. A photograph of a micro-lens projection system is shown in Figure 12.

One could also imagine that instead of an array of imaging systems, an array of pattern generators is used that generates a specific pattern, such as lines or points. In the ideal case such a system would replace the mask and the imaging system altogether. However, this approach is only possible for simple patterns and large production series.

Outlook

As long as optical lithography stays attractive, micro-optics will be used as beam-homogenizers and sophisticated diffusers to generate optimized illumination patterns. How far micro-optics will be used in the imaging system is difficult to predict. However, it can be assumed that the difference between micro-optics and macro-optics fabrication technology will disappear.

Recent research is also investigating near-field optics to further reduce the resolution limit. Micro-optics technology is well suited to realize such systems. A serious problem of near-field optics is the short distance (10 nm–100 nm) between the optical element and the interface to be patterned. In addition, near-field optics is based on scanning systems, which increases the exposure time considerable. However, there is still room for improvements or as Richard Feynman said ‘there is plenty of room at the bottom’.

Further Reading

Dändliker R, Gray S, Clube F, Herzig HP and Völkel R (1995) Non-conventional techniques for optical lithography. *Microelectronic Engineering* 27: 205–211.

Herzig HP (1998) *Micro-Optics: Elements, Systems and Applications*. London: Taylor & Francis.

Herzig HP and Kipfer P (1999) Aperture modulated diffusers (AMDs). In: Asakura T (ed.) *International Trends in Optics and Photonics*. Berlin: Springer.

Naumann H and Schröder G (1992) *Bauelemente der Optik*. München, Germany: Carl Hanser Verlag.

Sheats JR and Smith BW (eds) (1998) *Microlithography: Science and Technology*. New York: Marcel Decker.

Turunen J and Wyrowski F (eds) (1997) *Diffractive Optics for Industrial And Commercial Applications*. Berlin: Wiley-VCH.

Völkel R, Herzig HP, Nussbaum P, Dändliker R and Hugle WB (1996) Microlens array imaging system for photolithography. *Optical Engineering* 35: 3323–3330.

Design and Fabrication of Diffractive Optical Elements

D W Prather, T Dillon, A Sure and X Gao,
University of Delaware, Newark, DE, USA

J N Mait, US Army Research Laboratory, Adelphi, MD, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Diffractive optical elements (DOEs) are passive devices that redirect and focus light through the division and mutual interference of a propagating electromagnetic wave. This is in contrast to refractive elements, which redirect and focus light through variations in indices of refraction. From a historical perspective, diffraction was traditionally considered a detriment in optics and caused images to blur. However, we now know that it is possible to use diffraction to enhance the performance of optical systems. For example, DOEs can be used to correct chromatic aberrations and to implement optical functions that conventional refractive and reflective optics cannot, such as multiple beamsplitting.

Further, recent advances in computing and fabrication technologies have increased the number of applications in which diffractive elements are used, which has established diffractive optics as yet another tool in an optical designer's kit.

The first modern diffractive element was the hologram. A hologram is a photographic record of the constructive and destructive interference between two coherent beams known as the object and write beams. The object beam contains information about the object recorded. The write beam is necessary to record the hologram but contains no information itself. When the hologram is played back with a third beam, the read beam, the recorded interference pattern diffracts it in such a way that it reconstructs the object beam.

Unfortunately, the functions that a natural hologram can produce are limited to those whose wavefields can be produced in a laboratory. Thus, although it is possible to record a hologram that can focus or deflect a single beam, it is difficult to record a hologram that splits a single beam into multiple foci. However, the advent of computing technology made it possible to design such holograms analytically. The first diffractive element designed with the aid of a computer was demonstrated in 1966. Since then the ability to create elements that respond arbitrarily has had widespread application in imaging systems, telecommunications, and sensing.

The two most basic diffractive elements are the grating and the Fresnel zone plate. The diffractive behavior of a grating is predominately transverse to the optic axis. It causes light to split into discrete beams, referred to as diffraction orders, each with a different angle of propagation relative to the optic axis. The diffractive behavior of a Fresnel zone plate also divides incoming light into discrete orders, however, the orders are produced along the optic axis. This is useful in producing the diffractive equivalent of a refractive lens. Arbitrary transverse and longitudinal behavior is realized by combining characteristics of these basic two diffractive elements. In the remainder of this article, we discuss the design and fabrication of general diffractive elements.

Design

Once an optical system designer determines the functional behavior required for a particular application, for example, focusing or multiple beamsplitting, he or she needs to design a diffractive element that realizes this function. However, unlike refractive and reflective optical elements, whose material properties and surface curvatures determine their functionality, the functionality of a diffractive element is determined by a pattern of wavelength scale features. Determining this pattern is the goal of diffractive design but to do so one must first understand the physical relationship between the DOE and the wavefield it produces.

Scalar diffraction theory is one of the simpler models that relates the effect of a surface relief, or diffractive profile, $d(x, y)$, on an incident wavefield $U_{\text{in}}(x, y)$:

$$U_{\text{out}}(x, y) = \exp[\mathrm{i}\theta(x, y)]U_{\text{in}}(x, y) \qquad [1]$$

where the phase transformation $\theta(x, y)$ is related to the diffractive profile $d(x, y)$ by

$$\theta(x, y) = 2\pi(n-1)d(x, y)/\lambda \qquad [2]$$

The constant n is the refractive index of the optical substrate and λ is the wavelength of illumination in a vacuum.

The effects of the phase change are not apparent until the wavefield $U_{\text{out}}(x, y)$ propagates over some distance z. In scalar diffraction theory the relationship between $U_{\text{out}}(x, y)$ and the wavefield $U_z(x, y)$ at a plane a distance z away, is described by the Rayleigh–Sommerfeld diffraction equation:

$$U_z(x,y) = \int_{-\infty}^{\infty}\int_{-\infty}^{\infty} U_{\text{out}}(\zeta,\eta) \times \frac{\exp\left\{\mathrm{i}(2\pi z/\lambda)\sqrt{1+(x-\zeta/z)^2+(y-\eta/z)^2}\right\}}{\mathrm{i}z\lambda[1+(x-\zeta/z)^2+(y-\eta/z)^2]}\mathrm{d}\zeta\,\mathrm{d}\eta \qquad [3]$$

Huygens' principle is reflected in this formulation by the convolution between the transmitted field $U_{\text{out}}(x,y)$ and a spherical wave $h(x,y)$, which represents free space propagation over the distance z:

$$U_z(x,y) = U_{\text{out}}(x,y)^{**}h(x,y) \qquad [4]$$

where

$$h(x,y) = \frac{\exp\left\{\mathrm{i}(2\pi z/\lambda)\sqrt{1+(x/z)^2+(y/z)^2}\right\}}{\mathrm{i}z\lambda[1+(x/z)^2+(y/z)^2]} \qquad [5]$$

The Rayleigh–Sommerfeld formulation is valid so long as the angles at which energy diffracts from the aperture are small. If the distance z is sufficiently large that the angles stay clustered about the optic axis, one can replace the spherical wave response of freespace with a parabolic wave:

$$h(x,y) \approx \frac{\exp(\mathrm{i}2\pi z/\lambda)}{\mathrm{i}z\lambda}\exp[\mathrm{i}(\pi/\lambda z)(x^2+y^2)] \qquad [6]$$

This simplification is referred to as the paraxial, or Fresnel, approximation. The diffraction integral is now given by:

$$\begin{aligned} U_z(x,y) \approx{}& \frac{\exp(\mathrm{i}2\pi z/\lambda)}{\mathrm{i}z\lambda}\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} U_{\mathrm{out}}(\zeta,\eta) \\ &\times \exp\left\{\mathrm{i}(\pi/\lambda z)[(x-\zeta)^2+(y-\eta)^2]\right\}\mathrm{d}\zeta\,\mathrm{d}\eta \\ ={}& \frac{\exp(\mathrm{i}2\pi z/\lambda)}{\mathrm{i}z\lambda}\exp[\mathrm{i}(\pi/\lambda z)(x^2+y^2)] \\ &\times \int_{-\infty}^{\infty}\int_{-\infty}^{\infty} U_{\mathrm{out}}(\zeta,\eta)\exp[\mathrm{i}(\pi/\lambda z)(\zeta^2+\eta^2)] \\ &\times \exp\left\{-\mathrm{i}2\pi[\zeta(x/\lambda z)+\eta(y/\lambda z)]\right\}\mathrm{d}\zeta\,\mathrm{d}\eta \end{aligned} \qquad [7]$$

The second representation results from an expansion of the exponent and allows the diffraction integral to be written as a Fourier transform. The quadratic phase terms can be removed if a positive lens with focal length z is placed next to the diffractive element and a second positive lens with focal length z is placed in the image plane (see Figure 1). Under these conditions, $U_{\mathrm{out}}(x,y)$ and $U_z(x,y)$ form a Fourier transform pair:

$$\begin{aligned} U_z(x,y) &= \mathrm{FT}[U_{\mathrm{out}}(x,y)]|_{u=x/\lambda z, v=y/\lambda z} \\ &= \mathrm{FT}\{\exp[\mathrm{i}\theta(x,y)]\}^{**}\mathrm{FT}[U_{\mathrm{in}}(x,y)]|_{u=x/\lambda z, v=y/\lambda z} \end{aligned} \qquad [8]$$

The objective of diffractive design is to find a surface relief $d(x,y)$ that generates a desired response $q(x,y)$ somewhere in the response $U_z(x,y)$. However, eqns [3] and [7] neglect the fabrication process, which affects the fields that can actually be realized. A diffractive optic designer can incorporate fabrication constraints into their design either directly or indirectly. In a direct approach, the designer represents the diffractive structure parametrically, for example, a multilevel phase element can be represented by a discrete set of allowed phase values and a binary phase element can be represented by the contours that separate one phase value from the other. A designer defines the diffractive element by specifying and modifying these parameters.



Figure 1 Optical Fourier transform module.

In an indirect approach, the designer first determines an intermediate function without consideration for fabrication and afterward applies the fabrication constraints to this function. For example, if $f(u,v)$ is the desired response one wishes to generate in the z-plane using $U_{\mathrm{in}}(x,y)$ as the input, from eqn [8], the optical function required to do is

$$Q(x,y) = F(x,y)/U_{\mathrm{in}}(x,y) \qquad [9]$$

where $F(x,y)$ is the Fourier transform of $f(u,v)$. The designer must then find a phase $\theta(x,y)$ that satisfies the fabrication constraints and insures that $\exp[\mathrm{i}\theta(x,y)] \approx Q(x,y)$.

For example, fabrication using multiple binary masks yields a phase structure quantized to 2^N levels. An effective design should, therefore, yield a quantized phase structure that minimizes reconstruction error. A naïve approach is to set the magnitude of $Q(x,y)$ in eqn [9] to unity and quantize the phase. However, this introduces considerable error. A direct approach to design searches only over the set of quantized phase structures for the one that, for example, generates the desired response with maximum energy and minimum error. An indirect design seeks first a phase structure whose response produces a minimum amount of error between it and $Q(x,y)$ and then quantizes this structure.

Performance of the element can be improved if one exploits certain freedoms available in design. For example, all systems have a finite-sized detector. It is, therefore, unnecessary to specify the performance of the diffractive element everywhere in the image plane. Its behavior within the detector window is all that is important. If only the intensity of the response is specified, then the phase of the response within the window is also a design freedom. Finally, one can also control the amount of energy contained in the signal window by scaling the amplitude of the response. This allows a designer to balance diffraction efficiency with error in the signal window.

Two general nonlinear optimization algorithms for the design of DOEs are represented in Figure 2. Indicative of the nature of data flow, Figure 2a is



Figure 2 Algorithms used for diffractive design. (a) Unidirectional and (b) bidirectional algorithms.

referred to as a unidirectional algorithm and Figure 2b as bidirectional. In a unidirectional algorithm, changes are made only to the diffractive element. The changes are driven by how well the element performed in a previous iteration. If models exist for both forward and inverse propagation (T and T^{-1}, respectively), a designer can use a bidirectional algorithm, which allows modification of both the diffractive element and its response. This allows bidirectional algorithms to converge to a solution, in general, more rapidly than unidirectional algorithms. In scalar theory, T is a Fourier transform but more rigorous models exist. If the model of the optical system cannot be inverted, a unidirectional algorithm must be used.

Fabrication

Regardless of which design algorithm is used to determine $d(x, y)$, ultimately it needs to be realized physically. Although numerous techniques exist for doing so, by far the most common are based on microlithographic processes. The process requires exposing a layer of photoresist deposited on top of an optical substrate and etching the photoresist to transfer the pattern into the substrate. These methods are especially appealing because they leverage the existing manufacturing infrastructure of the microelectronics industry and, as a consequence, have enabled the efficient and economical mass manufacture of DOEs.

Two basic methods exist for patterning photoresist, direct writing using a modulated beam and indirect patterning using masks. Further, the mask process can be either a single or multistep process. The multistep approach uses N masks and N exposures to fabricate a multilevel diffractive element that has 2^N phase levels (see Figure 2). However, profiles that contain very small features are difficult to fabricate in this manner. As a consequence, alternative processes using single-step grayscale lithography have also been developed.

Although grayscale photolithography is more time-efficient and less prone to mask alignment errors than multistep lithography, the photoresist must respond linearly to illumination. Unfortunately, most photoresists used to fabricate microelectronic circuits are highly nonlinear. However, one can obtain a linear response by adjusting the exposure and development process. In the following, we review fabrication using both multiple binary masks and a single grayscale mask.

Multilevel Fabrication Using Binary Masks

In this fabrication method, one must first generate a sequence of N masks that are related, in a recursive manner, to the quantized phase $\theta(x, y)$:

$$m_k(x, y) = \mathrm{mod}(M_k(x, y), 2), \quad k = [1, N] \qquad [10]$$

where

$$M_{k+1}(x, y) = \frac{M_k(x, y) - m_k(x, y)}{2} \qquad [11]$$

and

$$M_1(x, y) = \theta(x, y)\frac{N}{2\pi} \qquad [12]$$

The masks can be produced using either optical or electron beam (e-beam) pattern generators from integrated circuit fabrication. The pattern generators expose a thin layer of photoresist on the surface of a chrome-covered quartz substrate. Development of the photoresist leaves the desired diffractive pattern in the unexposed areas. The diffractive pattern is transferred to the chrome layer by etching any chrome not covered by photoresist. After the chrome etch process is completed, any remaining photoresist is washed away to yield the finished lithographic mask. This process is repeated for each mask.

The completed mask set is used to fabricate the DOE using techniques similar to those used to generate the mask set. An optical substrate is coated with a thin layer of photoresist, placed in intimate contact with the first lithographic mask $m_1(x, y)$, and illuminated with an ultraviolet (UV) exposure lamp. During photoresist development, exposed resist is washed away, which leaves a binary pattern in the remaining developed photoresist.

When the pattern is transferred into the substrate material via etching, the photoresist acts as an etch stop. For the first mask, the etch depth into the substrate corresponds to a π-phase shift. The process is repeated for each subsequent mask, that is, the substrate is coated with a layer of photoresist, UV illumination exposes the photoresist through the mask, the photoresist is developed, and the substrate etched by the remaining pattern. The etch depth of each mask is half that of the previous mask. Figure 3 illustrates this process.

The substrate can be etched using either wet or dry techniques. In wet etching, one uses reactive chemicals, such as hydrofluoric acid, to etch the substrate. However, wet etching is isotropic, that is, substrate etching occurs equally in all directions. As a result, it is difficult to preserve vertical sidewalls and to achieve high fidelity in etching high-aspect ratio features. As a consequence, dry etching is more commonly used.

A dry etch uses a beam of ions to remove substrate material. The process for removal can be either chemical or kinetic. The process used is determined by the value of the plasma power that creates the source of ions relative to the bias power used to accelerate the ions toward the substrate. If the bias power is large and the plasma power small, a small stream of ions are accelerated rapidly toward the substrate. In this case, the operational mode is similar to a micromilling machine, wherein inert particles chip away at the surface by virtue of their kinetic energy. Alternatively, a small bias power and a large plasma power produce a large population of ions with no preferential directionality. This yields an isotropic process similar to wet etching.

Two methods for performing dry etching are reactive ion etching (RIE) and inductively coupled plasma (ICP) etching. However, in RIE systems the bias and plasma power are not independent due to capacitive coupling. Thus, adjusting one affects the other. ICP, on the other hand provides independent control over the bias and plasma powers. Independent control allows one to control precisely the anisotropic nature of an etch process. As mentioned above, this is achieved by varying the bias power relative to the plasma power, which controls the directionality of the acceleration.

Independent control is important because the ideal process for a given DOE depends on the substrate material and the characteristics of the diffractive profile. Independent control allows one to adjust the respective powers, as well as gas flow rates, and their partial pressures, to determine an optimal etch process. Dry etching allows one to incorporate endpoint detection, which provides precise control


Step 1: Glass spin coated with a thin film of photoresist
Photoresist
Substrate
Step 2: Exposure with the first mask
Mask
Photoresist
Substrate
Step 3: Develop
Developed photoresist
Substrate
Step 4: Dry etching
Substrate
Step 5: Spin coating with photoresist
Substrate
Step 6: Exposure with the second mask
Mask
Photoresist
Substrate
Step 7: Develop
Developed photoresist
Substrate
Final step 8: Dry etching
Substrate

Figure 3 Fabrication of a multilevel quantized phase DOE using binary masks.

over the etch depth. As presented below, achieving the proper etch depth is important to generating responses with high diffraction efficiency.

Care must be used when determining the number of phase levels appropriate for a particular application. The number of phase levels has a direct impact on the portion of input energy one can hope to diffract into the desired response. This is referred to as the diffraction efficiency. According to scalar diffraction theory, the relationship between the maximum diffraction efficiency η and the number of masks N is:

$$\eta = \mathrm{sinc}^2\left(\frac{1}{N}\right) \qquad [13]$$

Thus, using two masks to create a 4-level phase element, as opposed to a single mask to create a binary-phase element, doubles the upper bound on the diffraction efficiency from 41% to 81%. The maximum diffraction efficiency for 8-level and 16-level phase elements is 95 and 99%, respectively.

However, this increase in diffraction efficiency incurs fabrication costs. After the first etch step, each subsequent exposure requires careful mask alignment. Alignment is accomplished using a standard tool from integrated circuit fabrication known as a mask aligner. The quality of a mask aligner is determined by its precision and the majority of commercially available aligners can register a mask and substrate to within less than a micrometer. This degree of alignment accuracy is sufficient to fabricate many useful multilevel diffractive elements.

To summarize, a multilevel surface relief profile uses a set of N masks to generate a surface profile that exhibits 2^N phase levels. The etch depth for the kth mask is $d_k = \lambda/2^k(n-1)$. In the next section, we describe a process for fabricating continuous DOE profiles in a single expose and etch cycle.

Continuous DOE Profiles Using Grayscale Lithography

Grayscale photolithography has become increasingly popular because of its flexibility and convenience in fabricating continuous diffractive profiles. Methods including directly writing partially exposed e-beam resist, resist reflow lithography, and using grayscale masks in a single step exposure. Here we discuss only the latter method because the processes are similar to those used in multiple mask fabrication. Thus, the same facilities can be used to produce both. In particular, we consider the application of high-energy-beam-sensitive (HEBS) glass to grayscale lithography and the fabrication of continuous profile DOEs.

The process for creating a diffractive element using HEBS glass is similar to fabricating a binary-phase element from a single mask. However, mask creation is markedly different. HEBS glass is a white crown glass within which a thin buried layer of silver ions is incorporated. The layer of silver ions is created via ion exchange in an aqueous acidic solution and essentially serves the same function as silver grains in photographic film. When the glass is exposed to a beam of electrons, the silver-containing crystal complexes are chemically reduced and the glass darkens. By controlling the electron dose, one controls the opacity of the glass to produce a grayscale pattern.

Although the attraction of single-step grayscale lithography is reduced costs in fabrication, the process incurs high calibration costs to insure quality pattern transfer through several steps. The parameter that has the greatest impact on the overall process is the desired size of the smallest diffractive feature. The minimum feature size affects the selection of the accelerating potential, beam current, addressing grid, and electron dose of the e-beam used to expose the HEBS glass.

The e-beam accelerating potential sets the resolution limit of the process and affects the sensitivity of the glass to the electron dose, the total charge per area incident upon the glass. For example, for a constant electron dose, increasing the accelerating potential increases the darkening response of the material. The large accelerating potential produces a large flux, which achieves the desired electron dose in a short period using energetic electrons. This, in turn, enhances the sensitivity of the glass. However, increasing the accelerating potential also increases scattering, which limits the minimum feature size achievable. Thus, low beam energies are generally used to write small features. But this, unfortunately, reduces the range of available optical densities because the material is less sensitive at low beam energies. To compensate for the reduced sensitivity, it is possible to increase the electron dose by increasing the exposure time. However, this undermines to some extent using a low energy beam to achieve small features due to broadening that results from long exposure times.

Once the accelerating potential for writing the mask is chosen, the beam current and addressing grid need to be specified. The beam current is related to the spot size and, therefore, affects directly the length of time to write the mask. High current levels produce large spots. Since write times can easily reach into hours for large structures, high current levels are desirable to reduce them.

The addressing grid represents the physical grid that the electron beam is translated over in order to complete the exposure. This grid should be chosen as finely as possible, however, too fine a grid can significantly increase the required dwell time on each grid point. In this respect, a compromise is required. High beam currents produce short dwell times, which may necessitate using a coarse address grid to insure the beam is capable of performing the exposure.

Once the process parameters are set, calibration between the HEBS transmission and the electron dose is necessary. Analyzing the optical density of written test structures by some experimental means and determining its functional dependence on the electron dose completes the calibration. This allows one to specify the electron doses required to achieve the features dictated by the device design.



Figure 4 Fabrication of a continuous phase DOE using a grayscale mask.

If resolution requirements cannot be met through judicious selection of the accelerating potential, then some of the contrast in the mask can be sacrificed for an increase in available resolution. As we have mentioned, reducing the maximum optical density, or contrast, can alleviate scattering-induced broadening. It is possible, however, to compensate to some degree for the reduced contrast during the photolithography process, where UV exposure and develop times provide additional latitude in the pattern transfer process.

Figure 4 represents the fabrication of a continuous profile DOE using a grayscale mask. The substrate is spin-coated with a thin film of photoresist, placed in intimate contact with the grayscale mask, and UV illuminated to expose the resist film. The resist is developed and the pattern transferred into the substrate using either wet or dry etching techniques. Because the solubility of the resist is proportional to exposure, developing the photoresist produces a variable height profile.

Grayscale lithography is challenging because modern photoresists are also designed to be highly nonlinear yet linear response is required. Traditional photoresists are also designed to amplify mask contrast and produce the sharpest resist profile, thus they either dissolve away quickly and completely, or remain impervious to developer. The exposure threshold of traditional resists is, therefore, steep and considerable effort is required to



Figure 5 HEBS glass fabrication. (a) Data map of the optical density cross-section of an exposed HEBS grayscale mask and (b) its corresponding visible image.



Figure 6 Characterization of a continuous phase diffractive lens. (a) Two-dimensional profile. (b) Three-dimensional profile. (c) Line scan of the two-dimensional plot. (d) Image of element from a scanning electron microscope.

insure that resist exposure is on the linear portion of the curve.

Although the resist exposure process is sensitive to all parameters, the behavior of a resist can be characterized using simulation models. The details of the photoresist models can be found elsewhere, but the simulations predict that the greatest utilization of the available resist occurs for short exposure times (seconds), and that these short exposures require long developing times (minutes). Further, the models predict that low mask contrast does not adversely affect the usable resist height. It is, therefore, not unreasonable to use a low contrast mask to achieve small features.

Through simulation it is possible to determine process parameters that maximize the linear response range of the photoresist. However, these parameters must be validated in the laboratory. The results presented in Figures 5 and 6 provide convincing evidence of the efficacy of these techniques.

Final Remarks

Advances in passive photonic devices have been made possible by leveraging fabrication processes from the electronics industry. Modifying standard photolithographic techniques and photoresist processes has produced an industrial capacity for fabricating diffractive elements. This capability will no doubt lead to future advances in telecommunications, signal processing, and imaging.

See also

Diffraction: Fresnel Diffraction. **Diffractive Systems:** Aberration Correction with Diffractive Elements. **Holography, Techniques:** Overview.

Further Reading

Dascher W, Long P, Stein R, Wu C and Lee SH (1997) Cost-effective mass fabrication of multilevel diffractive optical elements by use of a single optical exposure with a gray-scale mask on high-energy beam-sensitive glass. *Applied Optics* 36: 4675–4680.

Dillon T, Balcha A, Murakowski JA and Prather DW (2004) Continuous-tone grayscale mask fabrication using high-energy-beam-sensitive (HEBS) glass. *Journal of Microlithography, Microfabrication, and Microsystems*.

Fienup JR (1980) Iterative method applied to image reconstruction and to computer-generated holograms. *Optical Engineering* 19: 297–306.

Goodman JW (1968) *Introduction to Fourier Optics*. New York: McGraw-Hill.

Kohler M (1998) Etching in microsystem technology. In: Turunen J and Wyrowski F (eds) *Diffractive Optics for Industrial and Commercial Applications*. Berlin: Wiley-VCH.

LeCompte M, Gao X and Prather DW (2001) Photoresist characterization and linearization procedure for the grayscale fabrication of diffractive optical elements. *Applied Optics* 40: 5921–5927.

Leith EN and Upatnieks J (1962) Reconstructed wavefronts and communication theory. *Journal of the Optical Society of America A* 52: 1123–1130.

Lohmann AW and Paris DP (1967) Binary Fraunhofer holograms generated by computer. *Applied Optical* 6: 1739–1748.

Mait JN (1995) Understanding diffractive optical design in the scalar domain. *Journal of the Optical Society of America A* 12: 2145–2158.

Stern MB and Rubico-Jay T (1994) Dry etching for coherent refractive microlens arrays. *Optical Engineering* 33: 3547–3551.

Swanson GJ (1989) Binary optics technology: the theory and design of multi-level diffractive optical elements, Technical Report 854, MIT.

Swanson GJ (1991) Binary optics technology: theoretical limits on the diffraction efficiency of multi-level diffractive optical elements, Technical Report 914, MIT.

Swanson GJ and Veldkamp WB, (1990) High-efficiency, multilevel diffractive optical elements. United States Patent 4,895,790.

Wang MR and Su H (1998) Laser direct-write gray-level mask and one-step etching for diffractive microlens fabrication. *Applied Optics* 37: 7568–7576.

Wu CK (1994) High Energy Beam Sensitive Glasses. U.S. Patent 5,285,517.

Wyrowski F (1991) Digital holography as part of diffractive optics. *Report on Progress in Physics* : 1481–1571.

Diffractive Laser Resonators

U D Zeitner, Fraunhofer Institute of Applied Optics and Precision Engineering, Jena, Germany

F Wyrowski, Friedrich-Schiller University, Jena, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

All lasers consist of three basic functional components: an active medium, an optical arrangement to pump the active medium, and a resonator, which we consider in detail here. The basic function of the resonator is to back-couple a portion of the emitted laser light into the active medium for further amplification. Simultaneously, in steady-state laser operation, the geometry of the resonator defines the spatial field distribution of the generated light field.

In the most simple, and most common, case the laser resonator consists of two planar or spherical mirrors. This configuration was proposed in 1958 and has been treated extensively in the literature. However, these configurations are only special cases of a more general resonator concept in which arbitrary mirror surface profiles are used. Historically, resonators consisting of surface profiled mirrors played only a small role in laser physics. This was due, not only to difficulties in their numerical design and analysis, but also to the lack of suitable fabrication methods for the mirrors.

However, since the 1990s, these difficulties have been overcome and in 1992 it was demonstrated for the first time experimentally a stable CO_2 laser resonator that has a user-defined mode shape generated by surface structured mirrors.

In the following we derive the basic design rules for stable and unstable diffractive laser resonators and discuss the advantages and disadvantages of the technology.

Modes in Laser Resonators

Before presenting the details of diffractive laser resonators we look first at some general properties of the electromagnetic field inside a laser resonator. As is typical in laser resonator theory, we use scalar and paraxial descriptions of the fields.

The complex amplitude $U(x, y, z)$ represents one scalar, monochromatic component of the electromagnetic field. To handle wave propagation inside the resonator, we use a general operator formalism in which the influence of each optical component on the wave $U(x, y, z)$ is represented by an operator. One of the most important operators is the so-called round trip operator $\mathbf{Z}$, which describes the effect of a round trip inside the resonator on the wave $U(x, y, z)$.

If $U(x, y, z)$ denotes the wave at the beginning of a resonator round trip, the resulting wave $\tilde{U}(x, y, z)$ at its end is

$$\tilde{U}(x, y, z) = \mathbf{Z}U(x, y, z) \qquad [1]$$

With reference to Figure 1, the round trip operator can be decomposed into a series of operators that represent the different elements in the resonator. For the common two-mirror resonator a round trip from mirror 1 to mirror 2, reflection at mirror 2, back propagation to mirror 1, and final reflection at



Figure 1 General diffractive laser resonator arrangement.

mirror 1, is represented by

$$\mathbf{Z} = \mathbf{R}_1 \mathbf{P}_{\Delta z} \mathbf{R}_2 \mathbf{P}_{\Delta z} \qquad [2]$$

The operators $\mathbf{R}_1$ and $\mathbf{R}_2$ represent the reflection at mirrors 1 and 2, respectively, and the propagation along the resonator length Δz is represented by the propagation operator $\mathbf{P}_{\Delta z.}$

In steady-state laser operation, the wave circulating inside the resonator reproduces itself, up to a constant factor γ, after a complete round trip:

$$\tilde{U}(x, y, z) = \gamma U(x, y, z) \qquad [3]$$

Together eqns [1] and [3] give the eigenvalue equation:

$$\gamma U(x, y, z) = \mathbf{Z} U(x, y, z) \qquad [4]$$

which, in general, has a set of solutions $U_p(x, y, z)$.

Thus, in steady-state, the waves $U_p(x, y, z)$ circulating inside the resonator are eigenfunctions of the round trip operator $\mathbf{Z}$ with the connected eigenvalue γ_p. The eigenfunctions of the resonator are called modes and the real-valued eigenvalues γ_p are connected with the round trip losses V, according to the equation:

$$V = 1 - |\gamma_p|^2 \qquad [5]$$

As we can see, the spatial properties of the modes are determined by the optical elements in the resonator. In the simple two-mirror resonator, the mirror profiles, which are related to the operators $\mathbf{R}_1$ and $\mathbf{R}_2$, can be used to specify the shape of the modes.

To derive the rules for resonator design we must look closer at the orthogonality of the resonator modes. The normalized eigenfunctions of the round trip operator $\mathbf{Z}$ do not obey the usual power-orthogonality relationship:

$$\iint U_m(x, y, z) U_n^*(x, y, z)\, \mathrm{d}x\, \mathrm{d}y = \delta_{mn} \qquad [6]$$

but instead satisfy the biorthogonality relationship:

$$\iint U_{m;+}(x, y, z) U_{n;-}(x, y, z)\, \mathrm{d}x\, \mathrm{d}y = \delta_{mn} \qquad [7]$$

The δ_{mn} is the so-called Kronecker symbol and $*$ denotes the complex conjugate. In eqn [7], $U_{m;+}(x, y, z)$ is the mode in plane z traveling in the $+z$ direction and $U_{m;-}(x, y, z)$ is the mode in the same plane z propagating in the opposite direction. The physical reason for the difference between eqns [6] and [7] are diffractive mode losses at limiting apertures. However, if a mode $U_{m;+}(x, y, z)$ travels without losses through the whole resonator, a power normalization:

$$\iint U_m(x, y, z) U_m^*(x, y, z)\, \mathrm{d}x\, \mathrm{d}y = 1 \qquad [8]$$

is valid in all planes z. Equations [7] and [8] will be used in the next section to derive the design strategy for resonators with predefined fundamental modes.

If the mirrors, either planar or spherical, are assumed to be infinite in extent, it is possible to derive analytic solutions for the modes. This yields either the Gauss–Hermite or Gauss–Laguerre modes, which are orthogonal in the sense of eqn [6]. For resonators whose mirror shape differs from either a plane or sphere, the analytical calculation of its eigenfunctions or resonator modes is difficult and in most cases even impossible.

However, in such cases the analysis can be performed numerically. One of the most common methods is the Fox-Li-algorithm which uses the physical propagation of the modes through the resonator. The algorithm begins with a random field distribution in some plane of the resonator. This field is then numerically propagated through the resonator until a round trip is completed. The effect of the resonator optical elements must be accounted for in this procedure. At the end of the resonator round trip, the starting field will have changed due to diffraction and serve as a new starting wave for a succeeding round trip calculation. This procedure is repeated until a static field distribution is obtained, which is then an eigenfunction of the resonator.

Design Principles

The condition in eqn [7] on the biorthogonality of resonator modes, together with the eqn [8] valid for lossless modes, can be used to develop principles to design resonators with an arbitrary fundamental mode shape. Consider a stable laser resonator characterized by negligible diffraction loss of the fundamental mode. Following the discussion above, its lossless modes must simultaneously satisfy eqns [7] and [8]. A comparison of both equations yields:

$$U_+(x, y, z) = U_-^*(x, y, z) \qquad [9]$$

For reasons of simplicity we neglect here, and in the following, the subscript m for the mode order if only one mode is considered. Because this equation must hold in all planes z, it is satisfied in the mirror resonator planes z_0 and z_b. Further, by definition of the operators $\mathbf{R}_1$ and $\mathbf{R}_2$:

$$U_+(x, y, z_b) = \mathbf{R}_1 U_-(x, y, z_b) \qquad [10]$$

$$U_-(x, y, z_0) = \mathbf{R}_2 U_+(x, y, z_0) \qquad [11]$$

The combination of eqns [10] and [11] with eqn [9] yields the following expressions for the mirror operators:

$$\mathbf{R}_1 = \frac{U_+(x, y, z_b)}{U_+^*(x, y, z_b)} \qquad [12]$$

$$\mathbf{R}_2 = \frac{U_-(x, y, z_0)}{U_-^*(x, y, z_0)} \qquad [13]$$

Equations [12] and [13] imply that lossless modes are phase-conjugated on reflection at the resonator mirrors. Because we have not made any assumptions on the shape of the mode, these equations represent a general property of lossless resonator modes. Furthermore, they provide a general design rule for the construction of stable laser resonators with predefined fundamental mode shape.

If one considers limiting apertures inside the resonator, an equivalent statement for lossy modes can be made by making assumptions about phase conjugation in a lossy system and showing that they lead to a contradiction. Without loss of generality, we assume an aperture on the outcoupling resonator mirror that clips the mode. We now consider the wave $U_-(x, y, z_0)$ after reflection at this mirror and assume this wave is still phase-conjugated after propagation through the resonator during its reflection at the back resonator mirror according to:

$$U_+(x, y, z_b) = U_-^*(x, y, z_b) \qquad [14]$$

If now the wave $U_+(x, y, z_b)$ is back propagated to the outcoupling mirror, we end up with the wave $U_+(x, y, z_0)$ which must, because of the phase conjugation in z_b, have the same amplitude as the wave $U_-(x, y, z_0)$ we started with. As a result, because both waves are connected to each other via the reflection operator of the outcoupling mirror by eqn [11], $\mathbf{R}_2$ cannot influence the amplitude distribution which, however, is a contradiction to the assumption of a limiting aperture. Thus, we finally can state that lossy modes do not have the property to be phase conjugated during their reflection at both mirrors. As a consequence, the design of diffractive mirrors for unstable laser resonators, in general characterized by energy outcoupling via diffractive losses, is more complex than simply calculating a phase-conjugating mirror structure for stable laser resonators.

Up to now, design methods described in the literature for unstable laser resonators with user-defined output beam shapes have all been based on an iterative calculation of the mirror reflection function. Because a detailed description of these methods is rather complex, we restrict ourselves to a sketch of the principal ideas behind them.

Without loss of generality, we consider an unstable laser resonator from which the light is coupled out by a mirror with spatially varying transmission and reflection. The second mirror is fully reflective within its aperture. The particular application defines only few design constraints which are in most cases the light wavelength, the dimensions of the resonator, and the shape of the outcoupled beam $U_0(x, y, z_0)$. As a consequence of the outcoupling principle, the shape of the mode inside the resonator is not finally defined by the outcoupled beam. In regions where the outcoupling mirror is reflective and not transmissive, the mode amplitude can be chosen freely. Also the amplitude of the mode in the plane of the back resonator mirror is not fixed but influenced by the amplitude and phase of the mode in the plane of the outcoupling mirror.

The general starting situation for an unstable resonator design is sketched in Figure 2. The design procedure must yield the complex amplitudes of four waves: the mode directly in front of the outcoupling mirror $U_-(x, y, z_0)$, the mode after reflection at the outcoupling mirror $U_+(x, y, z_0)$, and the complex amplitudes of the forward and reverse modes in the plane of the back resonator mirror $U_+(x, y, z_b)$ and $U_-(x, y, z_b)$, respectively. Since we assume no losses at



Figure 2 Starting situation for design of an unstable diffractive laser resonator.

this mirror, the amplitudes must satisfy the condition:

$$|U_{+}(x,y,z_b)| = |U_{-}(x,y,z_b)| \quad [15]$$

If we further assume no absorption at the outcoupling mirror, the amplitudes of the three waves in z_0 are related according to:

$$|U_{-}(x,y,z_0)| + |U_0(x,y,z_0)| = |U_{+}(x,y,z_0)| \quad [16]$$

To design the resonator one starts with the choice of initial intensity distributions for the wavefields $U_{-}(x,y,z_0)$ and $U_{+}(x,y,z_b)$. In order to obtain a good filling of the available mode volume, a homogeneous intensity across the mirror apertures is recommendable. To avoid strong diffraction effects at the mirror edges, the corresponding intensity distributions should be smoothed out. Together with the desired outcoupled beam amplitude $|U_0(x,y,z_0)|$ one can calculate the two remaining amplitudes for the wave fields $U_{-}(x,y,z_b)$ and $U_{+}(x,y,z_0)$ according to eqns [15] and [16].

An iterative algorithm, such as the well known Gerchberg–Saxton algorithm, can be used to find the phases of the beams $U_{-}(x,y,z_0)$ and $U_{+}(x,y,z_0)$ that insure the wavefields have almost equal amplitudes once they are propagated or back-propagated, respectively, to the plane z_b. In order to find wavefields that satisfy eqns [15] and [16], two successive iteration runs with different constraints on the complex amplitudes have to be performed. During the first iteration run no change in the initial amplitudes in plane z_0 are allowed. The iteration only look for phases for $U_{-}(x,y,z_0)$ and $U_{+}(x,y,z_0)$ which result in the amplitude $|U_{+}(x,y,z_b)|$ once they are propagated and back-propagated, respectively, to plane z_b. Usually the results of a Gerchberg–Saxton algorithm, with such constraints, are wavefields $U_{+}(x,y,z_b)$ and $U_{-}(x,y,z_b)$ with similar but not equal amplitude. Thus, in order to determine wavefields that satisfy eqn [15], a second iteration run with the Gerchberg–Saxton algorithm has to be added in which slight variations in wavefield amplitudes also in plane z_0 are allowed. Because the application of the constraints to ensure convergence of the iteration is rather complex, we do not go into details here but refer the reader to the Further Reading at the end of this article.

Upon completion of the iterations, the mirror reflectance operators $\mathbf{R}_1$ and $\mathbf{R}_2$ are calculated according to:

$$\mathbf{R}_1 = \frac{U_{+}(x,y,z_b)}{U_{-}(x,y,z_b)} \quad [17]$$

$$\mathbf{R}_2 = \frac{U_{-}(x,y,z_0)}{U_{+}(x,y,z_0)} \quad [18]$$

The design method described so far yields a mathematical expression for the resonator mirror reflection operator. Practical realization of the resonator requires this expression be converted into a description of a physical property of the mirror. In most practical cases this is the surface profile. Since the design method considers only phase-only functions, the physical description of the reflection operators are:

$$\begin{aligned} \mathbf{R}_1 &= \exp[-\mathrm{i}\phi_1(x,y)] \text{ and} \\ \mathbf{R}_2 &= \exp[-i\phi_2(x,y)] \end{aligned} \quad [19]$$

Using the so-called thin-element-approximation, the surface profiles $h_1(x,y)$ and $h_2(x,y)$ of the two mirrors follow directly from the phases $\phi_1(x,y)$ and $\phi_2(x,y)$:

$$\begin{aligned} h_1(x,y) &= -\frac{\lambda}{4\pi}\phi_1(x,y) \text{ and} \\ h_2(x,y) &= -\frac{\lambda}{4\pi}\phi_2(x,y) \end{aligned} \quad [20]$$

with λ being the laser wavelength. The expressions in eqn [20] contain a factor of 1/2 due to reflection. These surface profiles are commonly fabricated by microlithographic techniques. For stable laser resonators, where the mirrors perform a static phase conjugation, the mirror profile is a surface of equal phase of the fundamental mode.

Use of General Resonator Modes

Applications of diffractive laser resonators can be classified into beam shaping for a particular task external to the laser and resonator optimization via modifying the eigen-space of the round trip operator.

Internal beam shaping for external tasks is relevant to applications where it is advantageous to use a fixed beam profile other than a Gaussian, as is the case for instance in materials processing. Shaping the beam internally, avoids the energy losses usually associated with external beam shaping techniques. However, lasers that have a nonGaussian outcoupled beam profile are often less flexible in their general applicability.

However, there is considerable potential for diffractive laser resonators to enhance resonator characteristics and thereby improve the lasing operation itself. The conventional Gaussian-shaped fundamental mode in customary laser resonators varies considerably in intensity from its central maximum to its outer wings. The transfer of energy from the pumped active medium into the propagating mode is dependent upon the local transverse intensity and is optimal for homogeneous illumination. As a result, the efficiency with which energy is transferred into the fundamental mode can be increased by using diffractive resonator mirrors to match the shape of the lateral fundamental mode to that of the cross-section of the active medium.

An important resonator property, especially in high power laser systems, is the difference of round trip losses V between the fundamental mode and the higher, usually undesired, laser modes. This difference is referred to as modal discrimination. With no limiting apertures, the wavefronts of all Gauss–Hermite or Gauss–Laguerre modes of common laser resonators are phase conjugated upon reflection at the spherical mirrors. As we have shown above, there is a tight connection between the phase conjugation property of resonator modes and their property of having no round trip losses. Thus, the phase conjugation property of Gauss–Hermite and Gauss–Laguerre modes directly implies small round trip losses. In fact, in resonators without apertures they all have an eigenvalue $\gamma_p = 1$ and according to eqn [5] the round trip losses are zero. High-order modes, whose diameters are large, can be suppressed by decreasing the size of the mirror aperture, however, because the difference in mode diameter between modes of neighboring order m is small, the achievable discrimination is limited to a maximum ratio $V_{m+1}/V_m \approx 10$. The structured surface profile of the mirrors in a diffractive laser resonator whose fundamental mode is nonGaussian is tightly adapted to the phase of the design mode. The wavefront of the higher-order modes in these resonators often do not fit the mirror profile and it can be observed that their round trip losses are significantly higher. Thus, diffractive laser resonators usually show an improved modal discrimination compared to resonators with spherical mirrors. This effect can be further improved by inserting into the resonator additional phase plates with diffuser-like properties.

Shaping the surface profile of resonator mirrors or insertion of additional phase plates significantly improves the flexibility for the resonator design. As is demonstrated by the examples below, there are resonator configurations in which high modal discrimination or adaptation of the mode volume to the cross-section of the active medium are combined with a Gaussian shape of the outcoupled beam.

In the design procedure described so far, the resonators were treated as passive optical systems. The propagation of the mode through the resonator has not been influenced by the active medium. However, in real laser systems, this simplification is often not applicable. Due to the pumping process and the connected heat insertion, the refractive index distribution inside the active medium is not homogeneous, which affects the propagation of the modes. Furthermore, changes or fluctuations in the pump energy and cooling mechanisms introduce temporal changes in the optical function associated with the refractive index of the active medium. Further, although static or averaged, optical power of the active medium are included in the round trip operator and calculation of the mirror profiles, experiments with lasers that have diffractive resonator mirrors indicate that the temporal fluctuations can strongly influence the shape and round trip losses of the fundamental resonator mode. In general, diffractive laser resonators are more sensitive to deviations from design than conventional resonators.

Examples

We consider as an example the adaptation of fundamental mode shape to the cross-section of the active medium. In solid state lasers, such as Nd:YAG lasers, the active medium is often a crystal rod with a circular cross-section. Instead of using this sharp-edged cross-section shape as intensity distribution for the desired fundamental mode, a smoothed version, which is approximated by a super-Gaussian intensity distribution in the center plane of the rod, is chosen to be the fundamental mode. The super-Gaussian intensity distribution has a more desirable propagation characteristic than a sharp circular one. However, even these modes do not exhibit the advantageous property of propagation-invariant beam shape characteristic of Gaussian beams.

In our first example, we consider the design of a stable diffractive laser resonator with a super-Gaussian fundamental mode shape inside the active medium and a Gaussian beam coupled out from the resonator. The resonator configuration is based upon a beam shaping arrangement for a Gauss to super-Gauss beam transformation. Its optical setup is sketched in Figure 3. In the plane of the outcoupling



Figure 3 Setup for the Gauss-to-super-Gauss resonator.

mirror z_0, the fundamental mode has a Gaussian amplitude $U_g(x, y, z_0)$. A phase element, which is located directly in front of the outcoupling mirror, shapes the mode amplitude into a super-Gaussian one $U_{sg}(x, y, z_m)$ in the center plane z_m of the active medium. For this special beam shaping problem it is possible to calculate a phase plate surface profile that transforms the beams without energy losses. The corresponding calculation procedure is described in the Further Reading section at the end of this article.

The mirror profiles have to be realized to satisfy the previously derived phase conjugation property for the described beam. Since the Gaussian beam has its minimum waist at the outcoupling mirror, its phase is planar in that plane. Thus, to insure phase conjugation a plane mirror is all that is required in front of the beam shaping phase plate. In the plane of the back resonator mirror the beam has a modulated wavefront due to its transformation from a Gaussian to a super-Gaussian amplitude distribution. Thus, a surface modulated mirror profile is required to phase conjugate this beam during reflection. Figures 4a and b represent the phase profile of the beam shaping element and the back resonator mirror, respectively, for the following set of parameters: laser wavelength $\lambda = 1064$ nm, radius of the Gaussian and super-Gaussian beams in the plane z_0 and z_m, respectively, $w_g = 1$ mm and $w_{sg} = 1$ mm, order of the super-Gauss $n = 10$, distance $z_m - z_0 = 200$ mm, and resonator length $z_b - z_0 = 250$ mm. The amplitude distribution for the fundamental mode in this resonator simulated with the Fox–Li-algorithm is shown in Figure 4c for the plane of the outcoupling mirror and in Figure 4d for the center of the active medium.

In our second example, the flexibility of diffractive laser resonators is demonstrated by a resonator with a user-defined far-field intensity distribution. In our case the far-field intensity $|U_f(x, y, z_f)|^2$ is shaped like the Greek letter lambda, λ. Because we are concerned only with the intensity of the wavefield, the phase $\phi_f(x, y, z_f)$ of the far-field $U_f(x, y, z_f)$ can be chosen freely. As shown in the following, this phase freedom can be used to improve the interaction of the mode with the active medium, as was the case in our first design example. Again, the mode shape in the center of the active medium has a super-Gaussian intensity distribution, which insures high extraction efficiency. We used an iterative Fourier-transform algorithm to calculate a far-field phase that yields a nearly super-Gaussian intensity distribution in the outcoupling plane of the resonator. The resulting wave:

$$U_0(x, y, z_0) = a_0(x, y, z_0) \exp[i\varphi_0(x, y, z_0)] \qquad [21]$$

is generated directly as the laser output. The amplitude $a_0(x, y, z_0)$ is generated as a mode inside the cavity using a surface-modulated back resonator mirror. This performs a static phase conjugation of the desired mode in the mirror plane. The phase $\varphi_0(x, y, z_0)$ is provided by an additional element on the outside of the outcoupling mirror. A sketch of the resonator configuration is shown in Figure 5.

For the experimental realization of this example the thermal index gradient of the active medium was included into the resonator design and the two diffractive elements were fabricated on a quartz substrate using electron beam lithography and ion-beam etching. The measured mode shape in the plane of the outcoupling mirror and the far-field



Figure 4 Gauss-to-super-Gauss resonator: (a) phase of beam shaping element; (b) phase of back resonator mirror, simulated amplitude distributions for the fundamental resonator mode; (c) in the plane of the outcoupling mirror; and (d) in the center of the active medium.



Figure 5 Configuration for resonator internal generation of a user defined far-field intensity distribution. (With permission from Zeitner UD, Wyrowski F and Zellmer H (2000) External design freedom for optimization of resonator originated beam shaping. *IEEE Journal of Quantum Electronics* 36: 1105–1109. © 2001 IEEE.)



Figure 6 Measured mode intensities for the resonator of Figure 5. (a) In the plane of the outcoupling mirror; and (b) in the far-field of the resonator. (With permission from Zeitner UD, Wyrowski F and Zellmer H (2000) External design freedom for optimization of resonator originated beam shaping. *IEEE Journal of Quantum Electronics* 36: 1105–1109. © 2000 IEEE.)

intensity distribution are shown in Figures 6a and b, respectively. The mode in the outcoupling plane of the resonator fills an area of about 2 mm diameter with nearly homogeneous intensity. The far-field shows the desired λ-shaped intensity distribution. The variations in intensity are due to the nonlinear response of the active medium. As mentioned above, the response can be improved if these effects are included in the design of the resonator mirrors.

Conclusion

Diffractive laser resonators are a generalization of common spherical mirror resonators. The use of arbitrary resonator mirror profiles and additional internal phase plates offer a huge flexibility for the generation of user defined mode shapes and optimization of resonator properties like extraction efficiency and modal discrimination. The drawback of the use of structured mirrors is an increased adjustment effort, because the diffractive mirrors have more degrees of freedom to be aligned. Furthermore, diffractive resonators tend to be more sensitive against changes of the optical properties of the active medium than spherical mirror resonators. Such changes may occur due to temporal fluctuations in pump power or cooling power.

Most promising applications for diffractive resonators are:

- lasers for materials processing which require a fixed intensity pattern for the sample treatment and a fixed laser power;
- high efficient homogeneous laser illumination, for example, for data projection or sensing applications; and
- suppression of higher order modes and maintaining single-mode operation for high brightness lasers.

Some example applications and solutions have been presented here which cannot be achieved by conventional resonator optics. For stable laser resonators, the phase-conjugation property of the modes is used for a straightforward calculation of the required diffractive mirror profiles. Unstable resonator geometries with diffractive outcoupling require more complex iterative design procedures. However, especially for high-power and high-gain lasers, the latter sometimes have more advantageous properties, such as better discrimination of undesired higher-order modes and more simple mirror cooling options.

See also

Lasers: Carbon Dioxide Lasers. **Phase Control:** Phase Conjugation and Image Correction.

Further Reading

Aagedal H, Wyrowski F and Schmid M (1997) Paraxial beam splitting and shaping. In: Turunen J and Wyrowski F (eds) *Diffractive Optics for Industrial and Commercial Applications*, pp. 165–188. Berlin: Akademie Verlag.

Belanger PA, Lachance RL and Pare C (1992) Super-Gaussian output from a CO_2 laser by using a graded-phase mirror resonator. *Optics Letters* 17: 739–741.

Fox A and Li T (1961) Resonant modes in a maser interferometer. *Bell Systems Technical Journal* 40: 453–488.

Gerchberg R and Saxton W (1972) A practical algorithm for the determination of phase from image and diffraction plane pictures. *Optik* 35: 237–246.

Herzig H (1997) *Micro Optics*. London: Taylor & Francis.

Leger JR (1997) Diffractive laser resonators. In: Turunen J and Wyrowski F (eds) *Diffractive Optics for Industrial and Commercial Applications*, pp. 165–188. Berlin: Akademie Verlag.

Leger JR, Chen D and Dai K (1994) High modal discrimination in a Nd:YAG laser resonator with internal phase gratings. *Optics Letters* 19: 1976–1978.

Makki S and Leger JR (2001) Mode shaping of a graded-reflectivity-mirror unstable resonator with an intra-cavity phase element. *IEEE Journal of Quantum Electronics* 37: 80–86.

Siegman AE (1986) *Lasers*. Mill Valley, CA: Univ. Science Books.

Zeitner UD and Wyrowski F (2001) Design of unstable laser resonators with user-defined mode shape. *IEEE Journal of Quantum Electronics* 37: 1594–1599.

Zeitner UD, Wyrowski F and Zellmer H (2000) External design freedom for optimization of resonator originated beam shaping. *IEEE Journal of Quantum Electronics* 36: 1105–1109.

Diffractives in Animals

A R Parker, University of Oxford, Oxford, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Structural coloration involves the selective reflectance of incident light by the physical nature of a structure. Although the color effects often appear considerably brighter than those of pigments, structural colors often result from completely transparent materials. In addition, animal structures can be designed to provide the opposite effect to a light display: they can be antireflectors, causing ‘all’ of the incident light to penetrate a surface (like glass windows, smooth surfaces cause some degree of reflection).

The study of natural structural colors began in the seventeenth century, when Hooke and Newton correctly explained the structural colors of silverfish (Insecta) and peacock feathers (Figure 1), respectively. Nevertheless, accurate, detailed studies of the mechanisms of structural colors did not begin until the introduction of the electron microscope in 1942.

Structural colors generally may be formed by one of three mechanisms: thin-film reflectors, diffraction gratings, or structures causing scattering of light waves. This is a simplistic characterization resulting from the application of geometric optics to the reflective elements. Some structures, however, rather fall between the above categories, such as photonic crystals (Figure 2) – these become apparent when quantum optics is considered. In some cases, this has led to confusion over the reflector type. For example, the reflectors in some scarab beetles have been categorized by different authors as multilayer reflectors, three-dimensional diffraction gratings, photonic crystals, and liquid crystal displays. Perhaps all are correct! Since the above categories are academic, I place individual cases of structural colors in their most appropriate, not unequivocal, category. Also, in this article I will employ geometric optical treatments only.

The array of structural colors found in animals today results from millions of years of evolution. Structures that produce metallic colors have also been identified in extinct animals. Confirmation of this

Figure 1 Newton's subject.

fact, from ultrastructural examination of exceptionally well-preserved fossils, such as those from the Burgess Shale (Middle Cambrian, British Columbia), 515 million years old, permits the study of the role of light in ecosystems throughout geological time, and consequently its role in evolution. In some cases, such as for ostracod crustaceans, diffraction gratings have been found to increase in their optical sophistication throughout 350 million years of evolution.

Multilayer Reflectors

Light may be strongly reflected by constructive interference between reflections from the different interfaces of a stack of thin films (of actual thickness *d*) of alternately high and low refractive index (*n*). For this to occur, reflections from successive interfaces must emerge with the same phase and this is achieved when the so-called 'Bragg Condition' is fulfilled. The optical path difference between the light reflected from successive interfaces is an integral number of wavelengths and is expressed in the equation:

$$2nd \cos \Theta = (m + 1/2)\lambda \qquad [1]$$

from which it can be seen that the effect varies with angle of incidence (Θ, measured to the surface normal), wavelength (λ), and the optical thickness of the layers (*nd*). There is a phase change of half a wavelength in waves reflected from every low to high refractive index interface only. The optimal narrowband reflection condition is therefore achieved where the optical thickness (*nd*) of every layer in the stack is a quarter of a wavelength. In a multilayer consisting of a large number of layers with a small variation of index the process is more selective than one with a smaller number of layers with a large difference of index. The former therefore gives rise to more saturated colors corresponding to a narrow spectral bandwidth and these colors therefore vary more with a change of angle of incidence. Both conditions can be found in animals – different colored effects are appropriate for different functions under different conditions. For an oblique angle of incidence, the wavelength of light that interferes constructively will be shorter than that for light at normal incidence. Therefore, as the angle of the incident light changes, the observed color also changes (Figure 3).

Single layer reflectors are found in nature, where light is reflected, and interferes, from the upper and lower boundaries (Figure 4). A difference in the thickness of the layer provides a change in the color observed from unidirectional polychromatic light. The wings of some houseflies act as a single thin film and appear different colors as a result of this phenomenon. A single quarter-wavelength film of guanine in cytoplasm, for example, reflects about 8% of the incident light. However, in a multilayer reflector with ten or more high index layers, reflection efficiencies can reach 100%. Thus, animals possessing such reflectors may appear highly metallic.

The reflectance of the multilayer system increases very rapidly with increasing number of layers. If the dimensions of the system deviate from the quarter-wave condition (i.e., *nd* is not equal for all layers), then the reflector is known as 'nonideal' in a theoretical sense (may be 'ideal' for some natural situations). 'Nonideal' reflectors have a reduced proportional reflectance (not always a significant reduction) for a given number of layers and this



Figure 2 Scanning electron micrograph of a cross-section of the wall of a cylindrical spine of the sea mouse *Aphrodita* sp. (Polychaeta). The wall is composed of small cylinders with varying internal diameters (increasing with depth in the stack), arranged in a hexagonal array, that form a photonic crystal fiber. The opal-type photonic crystal – hexagonally packed nano-spheres (250 nm diameter) – are also found in animals (e.g. weevils). Scale bar represents 8 μm.

reflectance has a narrower bandwidth. A narrow bandwidth, less conspicuous reflection is sometimes selected for in animals, this will be discussed later in this article. Multilayer reflectors polarize light incident at Brewster's angles. This is about 54° for a quarter-wave stack of guanine and cytoplasm. At very oblique angles, all wavelengths are strongly reflected.

Multilayer reflectors are common in animals. They are usually extra-cellular, produced by periodic secretion and deposition, but sometimes occur within cells. Guanine ($n = 1.83$) is a common component in invertebrate reflectors because it is one of very few biological materials with a high refractive index and is readily available to most invertebrates as a nitrogenous metabolite. However, arthropods, including insects, crustaceans, and spiders, have largely ignored guanine in favor of pteridines. Also surprising is that the reflector material of closely related species, e.g., the molluscs *Pecten* (scallop) and *Cardium* (cockle), may differ.

Multilayers produce effects in beetle cuticle from highly metallic colors ('ideal' system) to rather dull greens ('nonideal' system in combination with scattering; Figure 5), and colors from the wings of many butterflies. Often in butterflies, layers of chitin ($n =$ about 1.56) are supported by vertical vanes of the scales. Air ($n = 1.0$) fills in the spaces and provides the alternate layers of the system. Under white light at normal incidence, the blue color of the butterfly *Arhopala micale* turns to green when the air is replaced by acetone. This is due to an increase in the refractive index of the low n layer (the actual thickness of this layer remains the same but the optical thickness increases) that effectively makes the system less 'ideal'. If the refractive indices of both layers were made equal, there would be no internal interference. A layer of melanin often underlies the reflector and intensifies the metallic colored effect by absorbing the transmitted portion of incident light. For example, in beetles, the elytra of *Anopognathus parvulus* appears metallic gold, green, or yellow in reflected light, and diffuse brown in transmitted light. Individual butterfly scales have been examined in detail to reveal a number of variations of quarter-wave stacks, sometimes in combination with other optical structures, to provide a range of colored effects.

The crustaceans *Limnadia* (Conchostraca), *Tanais tennicornis* (Tanaidacea), *Ovalipes molleri* (Decapoda), and the males of *Sapphirina* (Copepoda) all bear multilayer reflectors in their cuticles, in different forms (Figure 6). In contrast to the usual continuous thin layers, male sapphirinids have ten to fourteen layers of interconnecting hexagonal platelets within the epidermal cells of the dorsal integument. The reflector of *O. molleri* comprises layers that are corrugated and also slightly out of phase (Figure 7). At close to normal incidence this structure reflects red light, but at an angle of about 45° blue light is reflected. The corrugation, however, functions to broaden the reflectance band, at the expense of reducing the intensity of reflection.



Figure 3 Butterfly (*Parthenos sylvia* (Nymphalidae) from Malaysia), showing the change in color with angle of wings. This animal may have evolved a temporal signal rather than a static one.

A broadband wavelength-independent reflectance, appearing silver or mirror-like to the human eye, can be achieved in a multilayer stack in at least three ways in invertebrates (Figure 8). These are (a) a composite of regular multilayer stacks each tuned to a specific wavelength, (b) a stack with systematically changing optical thicknesses with depth in the structure, termed a 'chirped' stack, and (c) a disordered arrangement of layer thicknesses about a mean value, termed a 'chaotic' stack (Figure 8). The nauplius eye of the copepod *Macrocyclops* (Crustacea) has regularly arranged platelets ~100 nm thick in stacks of 20–60, achieving the first condition. Silver beetles and the silver and gold chrysalis of butterflies in the genera *Euoplea* and *Amauris*, owe their reflection to the second condition. The mirror-like reflectors in the scallop *Pecten* eye comprise alternating layers of cytoplasm ($n = 1.34$) and guanine crystals ($n = 1.83$) and approximate an 'ideal' quarter-wave system in the same manner as within fish skin using the third mechanism. The ommatidia of the superposition compound eyes of *Astacus* (Crustacea) are lined with a multilayer of isoxanthopterin (a pteridine) crystals, which again fall into the third category. Multilayer reflectors can also be found in the eyes of certain spiders, butterflies, and possibly flies, where they assist vision, as discussed further below.

Squid and cuttlefish, for example, possess mirror-like reflectors in photophores (light organs) and



Figure 4 Schematic diagram of thin-film reflection. The direction of wave (straight line) and profile of electric (or magnetic) component are illustrated. Incident waves are indicated by a solid line, reflected waves by broken lines. Refraction occurs at each media interface. The refractive index of the film (n_f) is greater than the refractive index of the surrounding medium (n_a). Constructive interference of the reflected waves is occurring. As the angle of incidence changes, different wavelengths constructively interfere. At normal incidence constructive interference occurs where $n_f \times d_f = \lambda/4$.

iridophores. Iridophores are cells that, in this case, contain groups (iridosomes) of flexible layers of thin lamellae with cytoplasm between, forming a quarter-wave stack. The platelets of both squids and octopods develop from the rough endoplasmic reticulum and are separated by extracellular space. Euphausiid crustaceans possess photophores with very elaborate mirror-like reflectors. Up to 60 dense layers, about 70 nm thick and 75–125 nm apart, are formed from the aggregation of granules (probably a type of chitin) and surround the main photogenic mass. An intricate ring consisting of very flattened cells, forming the dense layers of a multilayer reflector (about 175 nm thick, separated by 90 nm) surrounds the lens of the photophore and reflects blue light at acute angles of incidence.

Dead invertebrates may not display their original colors. Following death, one (or both) of the layers in a multilayer reflector may become gradually reduced. For example, water may be lost from the system. This occurs in beetles of the genus *Coptocycla*; their brassy yellow color quickly changes through green, blue, and violet until the brown of melanin is finally observed. The color progression may subsequently be reversed by water uptake. This is an important consideration when examining fossils for multilayer reflectors. Multilayer reflectors have been identified in the shells of some ammonites, preserved as fossils.



Figure 5 Generalized diagram of a multilayer reflector in the cuticle of the green beetle *Calloodes grayanus* (high refractive index material is shown shaded). Outer layer causes scattering.

Diffraction Gratings

When light interacts with a periodic surface consisting for example of a series of parallel grooves, it may be deviated from the direction of simple transmission or reflection. For this to happen, light which is scattered or diffracted from successive grooves should be out of phase by integral values of 2π. This occurs when, for a given direction of propagation, the optical path difference via successive grooves is $M\lambda$, where M is an integer known as the circle number.



Figure 6 Bivalve shell with outer pigment removed to reveal an incidental multilayer reflector. Layers evolved to provide strength and prevent crack propagation.



Figure 7 Transmission electron micrograph of a multilayer reflector in the cuticle of a swimming paddle of the crab *Ovalipes molleri* (Crustacea: Decapoda). Layers of reflector are slightly sinuous and out of phase; note the unusual side branches of each high refractive index (dark) layer, which provide support for these solid layers within a liquid matrix. Scale bar represents 5 μm.

This may be expressed by the grating equation:

$$2d(\sin \alpha - \sin \beta) = M\lambda \qquad [2]$$



Figure 8 Three ways of achieving a broadband, wavelength-independent reflector in a multilayer stack (high refractive index material is shown shaded). (a) Three quarter-wave stacks, each tuned to a different wavelength. (b) A 'chirped' stack. (c) A 'chaotic' stack.

where α and β are angles of incidence and diffraction, and d is the period.

As with multilayers, the effect gives rise to coloration because different wavelengths are diffracted into different directions. Although the effect changes with angle of incidence, it is less critical than it is with thin films and the visual appearance is different. For a parallel beam of white light incident upon a multilayer, one wavelength will be reflected as determined by the Bragg Condition. The same beam



Figure 9 Reflection-type diffraction grating (w = periodicity, m = order of reflected beam). For white light of fixed angle of incidence (Θ_i), the color observed is dependent on the point of observation (e.g., violet light can be seen at point x, red at point y, within the first order spectrum).

incident upon a grating will be dispersed into spectra (e.g., Figure 9). The complete spectrum reflected nearest to the perpendicular (grating normal) is the first order. The first-order spectrum is reflected over a smaller angle than the second-order spectrum, and the colors are more saturated and appear brighter within the former. Diffraction gratings have polarizing properties, but this is strongly dependent on the grating profile.

Diffraction gratings were believed to be extremely rare in nature, but have recently been revealed to be common among invertebrates. They are particularly common on the seate or setules (hairs) of Crustacea, such as on certain first antennal setules of male Myodocopina ostracods or ‘seed shrimps’ (Crustacea) (Figure 10). Here, the grating is formed by the external surface of juxtaposed rings with walls circular in cross-section (Figure 11). The width of the rings, and consequently the periodicity of the grating, is about 700 nm in *Azygocypridina lowryi*. Different colors are viewed with varying angles of observation under a fixed light source. The ostracod *Euphilomedes carcharodonta*, for example, additionally houses a diffraction grating on the rostrum, a continuous flattened area of the carapace that is corrugated to form periodic ridges. The dark brown beetle *Serica sericea*, bears gratings on its elytra with 800 nm periodicity, which causes a brilliant iridescence in sunlight.

Many polychaetes possess gratings on their setae (hairs). For example, the opheliid *Lobochesis longiseta* bear gratings with periodicities in the order of 500 nm (Figure 12), appearing iridescent. The wings of the neurochaetid fly *Neurotexis primula* bear diffraction gratings only on their dorsal surfaces, and the iridescent effect remains after the insect is gold coated for electron microscopy. These gratings cause iridescence with a higher reflectance than the iridescence of the membranous wings of other insects, which reflect light by interference. Iridescence caused by interference disappears after gold coating because transmission of light through the outer surface is prevented.



Figure 10 Diffraction gratings on the halophores (hairs) on the first antenna of the seed shrimp *Azygocypridina lowryi* (Ostracoda).



Figure 11 Scanning electron micrograph of diffraction grating on a halophore (setule) of *Azygocypridina lowryi* (Ostracoda). Scale bar represents 2 μm.

Very closely spaced, fine setules may also form the ridges of a diffraction grating. Cylindroleberidid



Figure 12 Scanning electron micrograph of diffraction gratings on a hair of *Lobochesis longiseta* (Polychaeta). Scale bar represents 10 μm.



Figure 13 Scanning electron micrograph of *Tetraleberis brevis* (Ostracoda), hairs of comb of maxilla; setules (orientated vertically) form the ridges of a grating. Scale bar represents 2 μm.

ostracods (seed-shrimps) possess a comb on their maxilla bearing numerous setules on each seta (hair), collectively forming a grating with a periodicity of about 500 nm (Figure 13).

The 'helicoidal' arrangement of the microfibrils comprising the outer 5–20 μm of the cuticle (exocuticle) of certain scarabeid beetles, such as *Plusiotis resplendens*, also gives rise to metallic colors. Here, the fibrils are arranged in layers, with the fibril axis in each layer arranged at a small angle to the one above, so that after a number of layers the fibrillar axis comes to lie parallel to the first layer. Thus, going vertically down through the cuticle, two corresponding grating layers will be encountered with every 360° rotation of the fibrils – the 'pitch' of the system. Polarized light encounters an optically reinforcing plane every half turn of the helix. The system can be treated as a three-dimensional diffraction grating, with a peak reflectance at $\lambda = 2nd$, where d is the separation of analogous planes, or half the pitch of the helix. The diffracted light resembles that from a linear grating except for the polarization; the three-dimensional grating reflects light that is circularly or elliptically polarized. It should be noted that the diffracted color does not depend on the total film thickness as it does in interference, but on the layer repeat distance within the film as in the diffraction grating (analogous to 'liquid crystals').

When each groove of a grating is so formed that it independently, by means of geometrical optics, redirects the light in the direction of a chosen diffracted order, it is known as a blazed grating. In a blazed reflection grating, each groove consists of a small mirror (or prism) inclined at an appropriate angle (i.e., the grating has a 'saw-tooth' profile). Blazed gratings have been identified on the wing scales of the moth *Plusia argentifera* (Plusinae).

When the periodicity of a grating reduces much below the wavelength of light, it becomes a zero-order grating and its effect on light waves changes. This difference in optical effect occurs because when the periodicity of the grating is below the wavelength of light the freely propagating diffracted orders are suppressed and only the zero-order is reflected when the illumination is normal to the plane of the grating. To describe accurately the optical properties of a zero-order grating, rigorous electromagnetic theory is required. In contrast to gratings with freely propagating orders, zero-order structures can generate saturated colors even in diffuse illumination. Such structures occur on the setae (hairs) of the first antenna of some isopod crustaceans, such as the giant species of *Bathynomus*. Here, there are diffracted orders and the spectral content of the light within the grating is controlled by the groove profile. In an optical system that only accepts the zero-order, what is seen is white light minus that diffracted into the ±1 orders.

A zero-order grating can cause total transmission (i.e., there is no reflection). Such antireflective structures are found on the corneal surfaces of each ommatidium (visual unit) in the eye of *Zalea minor* (Diptera) (Figure 14). The periodicity of the corneal gratings of this fly is 242 nm. Another form of antireflection grating is formed on the transparent wings of the hawkmoth *Cephonodes hylas* on the corneal surface of each visual unit (ommatidium) of the eyes of moths and butterflies (Figure 15). Here, optical-impedance matching is achieved by means of a hexagonal array of tapered cylindrical protuberances, each of about 250 nm diameter, thus forming a 'tri-grating' with grooves transecting at 120°.



Figure 14 Scanning electron micrograph of the compound eye of *Zalea minor* (Diptera). The corneal surface at the junction of two ommatidia is shown with antireflection gratings (positioned on sloping regions, i.e., at high angles to the normal of the eye) phasing into moth-eye-type protuberances. Scale bar represents 2 μm.



Figure 15 Tri-grating (antireflector) on the corneal surface of a butterfly eye. Scale bar represents 2 μm.

The protuberances provide a graded transition of refractive index between the air and the cornea/wing. Hence the refractive index at any depth is the average of that of air and the corneal/wing material.

The grooves of a grating may also create parallel rows in two directions, forming a bi-grating. Bi-gratings can be found in some crustaceans and flies. In the amphipod crustacean *Waldeckia australiensis*, two effectively superimposed gratings subtend angles of about 60/120° (Figure 16).



Figure 16 Bi-grating on the callynophores (hairs) of the amphipod crustacean *Waldeckia australiensis*. Scale bar represents 2 μm.



Figure 17 Light micrograph of the surface of a hair of *Canadia spinosa* (Middle Cambrian, 515 million years old, British Columbia), isolated by acid maceration of the rock matrix, showing gratings running longitudinally. Periodicity 0.9 μm.

In terms of fossil colors, diffraction gratings are responsible for the nacreous luster of brachiopod shells, such as those from the Devonian, around 360 million years old. Here, tabular aragonite platelets averaging 600 nm in thickness, each comprising a linear diffraction grating, form layers and consequently a three-dimensional diffraction grating. Antireflective, zero-order gratings have been identified on the eye of an Eocene fly, 45 million years old, preserved in Baltic amber. Linear diffraction gratings causing color have been discovered on the sclerites of *Wiwaxia corrugata* from the Burgess Shale (Middle Cambrian, 515 million years old) (Figure 17). This finding has led to the 'light switch theory', in that the evolution of the first eye caused the big bang in animal evolution.

Scattering (Incoherent Reflectors)

Simple, equal scattering of all spectral wavelengths results in the observation of a diffuse white effect. This commonly arises from the effects of a nonperiodic arrangement of colloidally dispersed matter where the different materials involved have different refractive indices (Figure 18), or from solid colorless materials in relatively concentrated, thick layers. In the colloidal system, the particles are larger than the wavelength of light and can be thought of as mirrors oriented in all directions. The reflection is polarized unless the incident light is at normal incidence on the system and, in the colloidal system, spherical or randomly arranged particles are involved.

The colloidal system involves either a gas-in-solid, gas-in-liquid, liquid-in-liquid (emulsions), or solid-in-liquid. For example, the gas-in-liquid system is partly responsible for the white body and/or tentacles of certain anemones. Light is reflected and refracted at the surfaces of the particles of matter or spaces (with dimensions >1 μm), regardless of the color of the materials involved (except opaque brown and black compounds, such as melanin). In insects, the materials involved typically have very low transparencies.



Figure 18 Scattering of white light by small particles (represented by black circles). The reflected light is randomly directed at different angles.



Figure 19 Scanning electron micrograph of a section of a white reflecting patch on the abdomen of the fly *Amenia* sp., showing closely packed, randomly arranged hairs that scatter incident light in all directions (Figure 11). Scale bar represents 20 μm.

An unordered (as opposed to periodic) group of closely spaced setae (hairs), such as those in patches on the fly *Amenia* sp., may form a white reflection via random scattering or reflection (Figure 19). However, if the arrangement becomes periodic to some degree, a diffraction grating may be formed, such as the grating of *Tetraleberis brevis* (Ostracoda) (Figure 13).

From some scales of butterfly wings, light is scattered uniformly and completely in all directions, due to the chaotic disposition of the surfaces. Matt or pearly whites may be observed depending on the complexity of the arrangement of the structures, which affects the relative degree of scattering. The structures may be so small that the molecular topography of the surface has an effect. The chromatic effects of the butterfly scales are greatly intensified if a dark, absorbing pigment screen lies beneath. This screen prevents reflection of white or colored light from the background that would dilute or alter the color. Additionally, if a dark pigment such as melanin is interspersed with the scattering elements, the reflection will appear a shade of gray or brown. The cells of the reflector in the photophore of a beetle ('fire-fly') are packed with sphaerocrystals of urate that cause a diffuse reflection (Figure 20).

Reflection and refraction that occur at the interfaces of strata with different refractive indices may result in the display of white light. The degree of whiteness depends upon the difference in refractive indices. This mechanism is evident in the shells of many lamellibranch molluscs. Between the outer, often pigmented layer and the mantle, is a thick middle layer of crystalline calcium carbonate. The inner surface of this (nacreous) layer is lined with multiple laminations of the same salt. In most species these laminations are sufficiently thick (>1 μm) to render the inner lining white, although in some species they become thin so as to form a multilayer reflector. Calcium carbonate similarly produces whiteness in Foraminifera and in calcareous sponges, corals, echinoderms, and crustacean cuticles. Also, in the class of white solids is silica in diatom tests and skeletons of hexactinellid sponges.

Other forms of scattering also exist and result in a blue colored effect (red when the system is viewed in transmission). Tyndall or Mie scattering occurs in a colloidal system where the particle size approximates the wavelength of light. Here, diffraction is important. Rayleigh scattering occurs in molecules in a two-photon process by which a photon is absorbed and raises the molecule to an excited electronic state from which it re-radiates a photon when it returns to the ground state. Diffraction is not involved here.

Tyndall scattered light is polarized under obliquely incident light. The intensity of the resultant blue is increased when it is viewed against a dark background, such as melanin. The relative sizes of particles determine the shade of blue. If the particles responsible for the scattering coalesce to form particles with a diameter greater than about 1 μm, then white light is observed (see above). A gradation from blue to white scattering ('small' to 'large' particles) occurs on the wings of the dragonfly *Libellula pulchella*.

Scattered blues can also be found in other dragonflies. In the aeschnids and agrionids, the epidermal cells contain minute colorless granules and a dark base. The males of libellulids and agrionids produce a waxy secretion that scatters light similarly over their dark cuticle. The green of the female *Aeschna cyanea* is the combined result of Tyndall scattering and a yellow pigment, both within the epidermal cells (degradation of the yellow pigment turns the dead dragonfly blue).

Scattered blues are also observed from the skin of the cephalopod *Octopus bimaculatus*, where a pair of ocelli are surrounded by a broad blue ring. Blue light is scattered from this region as a result of fine granules of purine material within cells positioned above melanophore cells. The color and conspicuousness of the ring are controlled by the regulation of the melanophores, by varying the distribution of melanin



Figure 20 Sections of photophores (bioluminescent organs), external surface of animals on the right. (a) The 'fire-fly' beetle *Pyrophorus* sp., abdominal photophore of male – reflector is based on a scattering system. (b) The shrimp *Sergestes prehensilis*, showing lens layers and absorptive pigment – reflector is based on a multilayer type.

and consequently the density of the absorbing screen. The squid *Onychia caribbaea* can produce rapidly changing blue colors similarly. The bright blue patterns produced by some nudibranch molluscs result from reflecting cells containing small vesicular bodies, each composed of particles about 10 nm in diameter and therefore appropriate for Rayleigh scattering.

See also

Diffraction: Diffraction Gratings. **Scattering:** Scattering Theory.

Further Reading

Fox DL (1976) *Animal Biochromes and Structural Colours*. Berkeley, CA: University of California Press.

Fox HM and Vevers G (1960) *The Nature of Animal Colours*. London: Sidgwick and Jackson Ltd.

Gale M (1989) Diffraction, beauty and commerce. *Physics World* 2: 24–28.

Harvey EN (1952) *Bioluminescence*. New York: Academic Press Inc.

Herring PJ, Cambell AK, Whitfield M and Maddock L (1990) *Light and Life in the Sea*. Cambridge, UK: Cambridge University Press.

Hutley MC (1982) *Diffraction Gratings*. London: Academic Press.

Land MF and Nilsson D-E (2002) *Animal Eyes*. Oxford, UK: Oxford University Press.

Pain S (1998) Seeing the light. *New Scientist* 2161: 42–46.

Parker AR (1999) Light-reflection strategies. *American Scientist* 87: 248–255.

Parker AR (2003) *In the Blink of an Eye*. London: Simon and Schuster/Cambridge (USA): Perseus Publishing.

Parker AR, Welch VL, Driver D and Martini N (2003) An opal analogue discovered in a weevil. *Nature* 426: 786–787.

Parker AR, McPhedran RC, McKenzie DR, Botten LC and Nicorovici N-AC (2001) Aphrodite's iridescence. *Nature* 409: 36–37.

Microstructure Fibers

R S Windeler, OFS Laboratories, Murray Hill, NJ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Microstructure fibers have unique properties that cannot be obtained from traditional fibers (i.e. all glass, doped silica fibers) and can deliver functionalities superior to many of today's best transmission and specialty fibers. Their unique properties are obtained from an intricate cross-section of high and low index regions that traverse the length of the fiber. The vast majority of fibers consist of silica for the high-index region and air for the low-index region. These fibers are known by several different names including microstructure fiber, holey fiber, and photonic crystal fiber. The term microstructure fiber is used in this chapter because it is the most generic, encompassing all the fiber types.

Microstructure fiber properties vary greatly and are determined by the size and arrangement of air holes in the fiber. For example, fibers have been fabricated such that the numerical aperture of the core or cladding approaches one. They have been fabricated with unique dispersion profiles, such as a zero-group velocity dispersion in the near visible regime or an ultraflat dispersion over hundreds of nanometers wide. They have been fabricated to generate a super continuum over two octaves wide. Some guide light with an air core via bandgap guidance. In addition, the air holes in these microstructure fibers can be filled with highly tunable materials, giving one the capability of controlling the fiber properties for use in energy efficient devices.

Microstructure fibers can have doped regions like traditional fibers. These hybrid fibers combine the benefits of traditional and microstructure fibers. The doped core typically guides most of the light, but its guidance properties can be strongly influenced by the air regions. Applications for hybrid fibers include dispersion compensation, polarization maintaining, and bend insensitive fibers.

Loss is always an important factor when determining whether a microstructure fiber will compete with or replace a traditional optical fiber. The index profiles that make these fibers so special can also lead to fibers that have an inherently high loss at connections or along the length of the fiber. Loss at connections typically occurs due to mode mismatch between the two fibers, undesired hole collapse, or poor alignment. Loss along the fiber length can occur due to impurities, hole surface roughness, or poor confinement.

The dispersion profile (zero dispersion wavelength, dispersion slope, normal or anomalous) of microstructure fibers can be optimized more than a traditional fiber, because the hole size and placement can be arranged to make the cladding index strongly wavelength dependent. Dispersion causes a pulse to spread because the phase velocity is wavelength dependent. Normal dispersion is when longer wavelengths travel faster than shorter wavelengths. Anomalous dispersion is just the opposite – shorter wavelengths travel faster than longer wavelengths. Dispersion determines the amount of interaction between different wavelengths. For applications such as transmission fiber, one wants little interaction and for high nonlinear applications, one wants significant interaction.

This chapter examines the methods for fabricating microstructure fibers and reviews the different types of microstructure fibers and their properties. Fibers that guide by total internal reflection are reviewed separately from bandgap guided fibers because their properties are significantly different. Lastly, a description and example of an active device is presented in which the air regions of a microstructure fiber are filled with controllable material.

Microstructure Fiber Fabrication

At first glance, fabrication of microstructure fibers looks similar to traditional fibers in that the fibers are fabricated in a two-step process. First a preform is fabricated and then it is drawn (stretched) into a fiber. However, when the process is examined in more detail, both the preform fabrication and draw depart significantly from traditional methods. First, a novel preform fabrication method is used to incorporate air holes that run the length of the preform. Second, novel drawing procedures are used to keep the air holes open as the preform diameter is reduced by several orders of magnitude during draw.

Preform Fabrication

Microstructure preforms are cylinders of amorphous material usually less than a few centimeters in diameter that have an index profile running the length of the preform similar to the desired fiber. The most common preform consists of air and a single material such as silica, polymer, or high nonlinear glass. These air-containing preforms are relatively easy to fabricate but are difficult to draw because the structures can deform.

The basic parameters of the fiber are usually determined by the geometry of the holes in the preform. These include hole diameter (d), hole position, pitch (center-to center hole spacing, Λ), core diameter (a), and number of layers. However, changes in the size and shape of the holes in the fiber can be made purposely or accidentally during draw, which will cause deviations between the fiber and preform profiles.

Several methods are used to fabricate microstructure preforms including stacking, casting, extrusion, and drilling. Each process has its advantages and disadvantages. By far, the most common method is stacking in which tubes, rods, and core rods (rods containing doped cores fabricated by traditional optical fiber techniques) are stacked in a close packed pattern such as a triangular or hexagonal lattice (Figure 1). The bundle of tubes and rods is then bound together with a large tube, called an overclad tube. Fibers can be made with complicated or asymmetric index profiles by strategically placing tubes with the same outer diameter (for good stacking) but a different inner diameter to change the index in that location. For example, a fiber with smaller holes on opposite sides of the core produces high birefringence.

The main advantages of stacking are that no special equipment is needed for fabricating microstructure preforms and that doped cores are easily added. However, there are several disadvantages. First, the stacking method is limited to simple geometries of air holes because the tubes are stacked in a close pack arrangement. Second, unless hexagonal tubes are used, interstitial areas are created between the tubes that may not be desired in the final fiber. Third, the method is labor intensive and requires significant glass handling.

A variation of the stacking method is used for fabricating air-clad fibers. Air-clad preforms are created by placing a layer of small tubes around the perimeter of a large core rod. The assembly is then overcladed for strength (Figure 2).

Extrusion and casting of glass powder, polymer, or sol–gel slurry are also used for making single material



Figure 1 (a) Tubes, rods, and core rods are stacked together in a close packed arrangement and held together with an overclad tube. (b) During draw the desired air region stay open forming a microstructure fiber.



Figure 2 (a) An air-clad preform is fabricated by stacking a ring of small, thin walled tubes around a large core rod. (b) Photograph of the resulting fiber.

microstructure preforms. The main advantage of extrusion and casting is that complicated structures can be fabricated in which the position, size, and shape of the air regions are independent of one another. The disadvantage of this method is that preform fabrication is more difficult compared to the other fabricate methods. This method may become more common as complex air structures are needed to make advanced microstructure fibers.

The last method consists of drilling holes in a preform or rod. Drilling is well understood and used for other specialty fibers. The advantage of this method is that it is easy to drill holes of various sizes in any position in a preform, including doped regions. The disadvantages of drilling are that the holes cannot be drilled very deep compared to a traditional preform length; the distance between holes may be limited due to cracking; and the fiber may experience high loss due to surface roughness of the holes and impurities incorporated during drilling.

Fiber Draw

It is significantly more difficult to draw a microstructure preform with air holes than a traditional preform. This is because the air holes tend to close due to surface tension. This force can be overcome or minimized using two different techniques. The first is to draw the preform under very high tension (low temperature). Minimal hole collapse occurs when the draw tension is significantly larger than the surface tension. The problem with this method is that the break rate increases substantially at higher tension.

The second method is to apply an external pressure to the holes to counteract the surface tension. If a single pressure source is used, the holes can be made larger or smaller during draw by changing the pressure as needed. However, the process can become unstable because a large hole needs a lower pressure to maintain its size than a small hole. If holes of different sizes exist, a larger hole will grow at the expense of a smaller one regardless of the pressure used. To minimize the instability, this method is typically performed in conjunction with high-tension drawing.

To alleviate the draw problem, a second solid material can be used in the preform to obtain the desired index profile. With the air regions removed from the preform, the drawing process becomes significantly easier. In addition, when a preform consists of two solid materials, one of the materials does not have to be continuous, as in single material preforms. This allows for simpler designs such as concentric rings, which may be easier to fabricate and model (Figure 13c). The disadvantage of this approach is finding two materials that have compatible physical and chemical properties, have low loss, and have a large index of refraction difference.

Microstructure Fiber Types

Microstructure fibers are categorized by their method of guidance, properties, and function. Index guided microstructure fibers most closely resemble traditional fibers and are described first. These fibers guide light by total internal reflection and have a core index of refraction greater than the cladding. Bandgap fibers are examined next. The unique guidance of bandgap fibers allows the core index to be lower than the cladding index. Tunable microstructure fibers are described last. These microstructure fibers are filled with tunable materials so that the fiber's properties can be actively manipulated.

Index Guided Fibers

Most microstructure fibers guide light by total internal reflection. The size and spacing of air holes determine the guiding properties. For example, a solid silica core surrounded by a cladding consisting of small air holes that are spread apart creates a small core-to-cladding index difference similar to what can be achieved in traditional fibers. At the other extreme, a solid silica core surrounded by a cladding of large holes, which are closely spaced together, forms a large core-to-cladding index difference. This structure creates a large numerical aperture in the core and optically isolated regions within the fiber. The ability to create regions of significantly different indices in various parts of the fiber distinguishes the index guided microstructure fibers from traditional fiber. Different types of microstructure fiber are formed by varying the size, spacing and pattern of the air holes.

Different techniques are used to model these fibers, depending on spacing and size of the air holes relative to the wavelength of the guided light. If the hole diameter and spacing is much smaller than the wavelength of the guided light, the cladding index can be modeled as an average index weighted by the volume fraction of the two materials (typically air and silica). As the hole diameter or spacing approaches the wavelength of the guided light, complicated models are used such as finite difference method, finite element method, beam propagation method, or multipole method.

Endlessly single-mode fiber

The endlessly single-mode fiber consists of a solid core surrounded by a two dimensional array of small air holes in the cladding (Figure 3). The size and position of the air holes are arranged such that only the fundamental mode exists in the core regardless of the wavelength of the guided light.

The prevention of higher order modes can be understood by examining the V number. The V number is a dimensionless parameter that describes the guiding nature of the waveguide. In traditional fiber, when the V number is less than 2.405, the fiber will guide only the fundamental mode. The V number is given by

$$V = \frac{2\pi a}{\lambda}(n_{\text{core}}^2 - n_{\text{clad}}^2)^{1/2} \qquad [1]$$

where a is the core diameter, λ is the wavelength of the guided light, and n_{core} and n_{clad} are the index of refractions of the core and cladding, respectively. In traditional fiber, the core and cladding index (n_{core} and n_{clad}) are for the most part constant, so the V number increases as the wavelength decreases.

However, for the endlessly single mode microstructure fiber, the V number does not increase indefinitely with decreasing wavelength, but approaches a constant value. Obtaining a V number independent of wavelength is understood by examining the distance the light propagates into the cladding as a function of wavelength. As the wavelength becomes shorter, light penetrates a shorter distance into the cladding, interacting with less of the air regions. This causes the effective cladding index (n_{clad}) to increase with decreasing wavelength, such that V approaches a constant value.



Figure 3 Photograph of an endlessly single mode fiber (Reprinted with permission from Birks TA, Knight JC and Russell P (1997) Endlessly single mode photonic crystal fiber. *Optics Letters* 22: 961–963).

Microstructure fibers are made endlessly single-moded over all wavelengths by properly designing the hole diameter-to-pitch ratio (d/Λ). When the d/Λ is low enough, the microstructure fiber guides light only in the single mode regardless of wavelength and core size (Figure 4). However, these large core diameter fibers are limited by long wavelength bend loss in the same way as large core single mode traditional fibers.

High delta core fiber

High delta core microstructure fibers (HDCMF) consist of a small (typically less than 2 microns) solid silica core surrounded by one or more layers of large air holes closely spaced together (Figure 5). This creates a very large index difference between the core and cladding. A core-to-cladding index difference of 0.4 is easily achieved in a HDCMF, which is an order of magnitude larger than can be achieved with traditional fiber.

Even though the core is very small, these fibers are almost always multimoded due to the large index difference between the core and cladding. However, because of its small core, it is difficult to launch anything other than the fundamental mode into the fiber. Once a mode is guided in the fiber it remains in that mode due to the large difference in effective indices between modes (Figure 6). When higher-order modes are purposely generated in the fiber, they also



Figure 4 The effective V number as a function of Λ/λ for various d/Λ (Reprinted with permission from Birks TA, Knight JC and Russell P (1997) Endlessly single mode photonic crystal fiber. *Optics Letters* 22: 961–963).



Figure 5 High delta core fibers consist of a small solid core surrounded by at least one layer of large air holes closely spaced together. Right-hand panel reprinted with permission from Ranka JK, Windeler RS and Stentz AJ (2000) Optical properties of high-delta air-silica microstructure optical fibers. *Optics Letters* 25: 796–798.



$n_{\text{eff}} = 1.425$ $n_{\text{eff}} = 1.390$

Figure 6 Individual modes do not couple well due to large differences in effective indices between modes. The figure shows the mode profile and effective index of the fundamental and the next higher mode for a fiber with a two-micron diameter core with a core-to-cladding index difference of 0.45 (Reprinted with permission from Ranka JK, Windeler RS and Stentz AJ (2000) Optical properties of high-delta air-silica microstructure optical fibers. *Optics Letters* 25: 796–798).

guide over long lengths without coupling to other modes (Figure 7). This strong guidance makes the fiber extremely bend insensitive.

HDCMF can have a unique dispersion profile because it can guide the fundamental mode exclusively in the multimode regime. This allows greater flexibility in controlling the shape of the dispersion profile, especially the ability to move the zero dispersion to shorter wavelengths. The HDCMF is the first silica fiber with anomalous dispersion of single-mode light below 1270 nm (the wavelength at which the material dispersion of silica is zero). These fibers are often made to have a zero-group velocity dispersions around 770 nm for use with Ti-sapphire lasers.

HDCMF is ideal for performing nonlinear experiments in the near-visible regime because the fiber's small, high-index core creates high intensity light, and the fiber's low dispersion creates long interaction times. For example, a broadband continuum can be generated over two octaves using less than a meter of HDCMF fiber (Figures 8 and 9).

Tapered microstructure fiber (TMF)

Coupling light in and out of HDCMF is difficult and results in a large loss due to its small core. When free space optics are used to couple the light, frequent realignment of the beam is required to minimize loss due to drifts in the equipment. Splicing HDCMF fiber to traditional fiber also results in high loss due to a large modal mismatch. These coupling problems are solved with tapered microstructure fibers.

Tapered microstructure fibers (TMF) consist of a traditional germanium single-mode core surrounded by a small silica cladding (Figure 10). The inner



Far-field pattern, 532 nm light
5 meter fiber length

Far-field pattern, 355 nm light
2 meter fiber length

Figure 7 Far-field patterns show that higher order modes propagate long distances in the HDCMF without coupling to other modes (Reprinted with permission from Ranka JK, Windeler RS and Stentz AJ (2000) Optical properties of high-delta air-silica microstructure optical fibers. *Optics Letters* 25: 796–798).



Figure 8 Plot of a supercontinuum spectrum over two octaves wide generated from a 75 cm piece of HDCMF (Reprinted with permission from Ranka JK, Windeler RS and Stentz AJ (2000) Visible continuum generation in air-silica microstructure optical fibers with anomalous dispersion at 800 nm. *Optics Letters* 25: 25–27).



Figure 9 Photograph of fiber generating the supercontinuum. The bottom photo shows the continuum after passing through a prism.


Core
Core
Core
Easy coupling onto standard fiber
132 μm
12 μm
5–10 μm
132 μm
132 μm
Core
Core
10–20 cm waist
0.60 cm taper length

Figure 10 Schematic drawing of the tapered microstructure fiber (Reprinted with permission from Chandalia JK, Eggleton BJ, Windeler RS, Kosinski SG, Liu X and Xu C (2001) Adiabatic coupling in tapered air-silica microstructures optical fiber. *IEEE Photonics Tech. Letters* 13(1) (©2001 IEEE)).

cladding is surrounded by a layer of air holes and then a protective outer silica cladding for strength. Since the core of the TMF is very similar to a traditional single-mode fiber core, the splice loss is low. Splice losses below 0.075 dB are typical.

Properties similar to the HDCMF are obtained by adiabatically tapering the TMF while maintaining the cross-sectional profile of the fiber. In the taper region, the fundamental mode is no longer guided by the germanium core and evolves into the fundamental mode of the silica region, where it is confined by the ring of air holes. The taper waist is typically ten to twenty centimeters long and has properties identical to the HDCMF. When the fiber is adiabatically expanded back to its original size, the light is guided back into the standard diameter germanium core, making it easy to splice to traditional fiber with low loss.

The same effect can be obtained by stretching a traditional fiber from 125 microns down to 2 microns. However, there are several disadvantages compared to the tapered microstructure fiber. The taper region is much longer in the traditional fiber; the optimal diameter of the silica core is harder to maintain; the taper region must remain clean and uncoated; and the taper region is much weaker.

Air-clad fiber

Air-clad fibers consist of a doped core surrounded by a silica inner cladding. The inner cladding is surrounded by a ring of air, which in turn is surrounded by an outer silica cladding for strength (Figure 2). Thin silica webs connect the inner and outer claddings to hold the inner fiber region in place. The region consisting of air and thin silica webs creates an optical barrier, preventing most of the light from escaping the inner cladding. Such fibers are referred to as double clad fiber.

In traditional double-clad fibers, a material of lower index (typically another layer of glass or a layer of polymer) immediately surrounds the inner silica cladding. A key optical parameter describing the light guiding properties of the inner cladding is the numerical aperture (NA). The NA is defined as the sine of the largest (acceptance) angle of light that will be guided in the inner cladding. The upper NA values of traditional double-clad fibers (~0.22 and ~0.45 for glass and polymer outer claddings, respectively) are limited by the refractive indices of the available cladding materials.

For the air-clad fiber, the NA is determined by the ability of light to escape from the inner cladding through the silica webs. The NA of the air-clad fiber can be calculated by modeling the web as an infinitely long slab waveguide. As seen in Figure 11, the NA increases as the webs become thinner or the wavelength of light becomes longer. To obtain NA similar to what is achieved by coating a traditional fiber with a low index polymer (NA ~ 0.45), the web thickness must be about equal to the wavelength of the light. The NA of the air-clad fiber increases dramatically as the web thickness becomes less than half the wavelength of the guided light. Numerical apertures above 0.90 have been experimentally demonstrated.

The large NA values achievable with air-clad fibers are an important advantage for advanced double-clad



Figure 11 Predicted NA as a function of the web thickness divided by the wavelength using an infinite slab model.



Figure 12 Schematic of the mechanism of (a) index guided light and (b) band gap guided light (Reprinted with permission from Cregan RF, Mangan BJ, Knight JC, Birks TA, Russell PJ, Roberts PJ and Allan DC (1999) Single-mode photonic band gap guidance of light in air. *Science* 285. Copyright 1999 American Association for the Advancement of Science).



Figure 13 Photographs and drawing of three types of bandgap fibers: (a) triangular array cladding with an air core (Cregan RF, Mangan BJ, Knight JC, Birks TA, Russell PJ, Roberts PJ and Allan DC (1999) Single-mode photonic band gap guidance of light in air. *Science* vol. 285), (b) tunable with a silica core, (c) concentric rings with an air core (Reprinted with permission from Temelkuran *et al.* *Nature* 420. Copyright 1999 American Association for the Advancement of Science).

amplifiers and lasers. A double-clad amplifier or laser (also known as cladding pumped amplifier or laser) contains a double-clad fiber with a rare earth doped core. High-power pump light, launched into and guided within the inner cladding, excites the rare earth ions as the pump light crosses through the core. The excited ions, which emit light with the same wavelength and phase as the signal, amplify the signal. The fiber's efficiency and the rare earth inversion level increase with the amount of pump light absorbed by the core. The light absorbed by the core, in turn, increases with the core-to-inner cladding area ratio and the pump light intensity in the inner cladding.

Traditional fibers have a practical limit to their core-to-cladding ratio. The maximum core diameter is limited by bend loss. And, while ultimately the minimum fiber diameter is limited by draw capabilities, in practice it is limited by the ability to couple pump light into a fiber having a limited inner-cladding NA. For a pump source of given brightness, the product of beam diameter and NA cannot be increased. Such light can be successfully coupled into a larger inner cladding with smaller NA or a smaller inner cladding with larger NA.



Figure 14 Spectrum of a typical bandgap fiber.

Air-clad fibers have other advantages over traditional double-clad fibers. The outer glass cladding in air-clad fibers is optically inactive. This allows the inner cladding diameter to be decoupled from the physical fiber diameter, eliminating draw-related constraints on minimum inner cladding size. Since only the inner cladding is optically active, its size can be optimized (made smaller) while keeping the total fiber diameter at the standard 125 microns. In addition, the pump light does not interact with the polymer coating, which can be important if the polymer properties are affected by the surroundings.



Figure 15 Holes in the microstructure fibers are filled with controllable materials to affect the fiber properties actively. Photos show (a) original fiber and (b) fiber after polymer is inserted and cured in the microstructure fiber.



Figure 16 Schematic of a tunable device in which low index liquid is positioned over the grating. The plot shows the shift in the spectrum as a function of temperature (Reproduced from Kerbage C, Windeler RS, Eggleton BJ, Dolinskoi M, Mach P and Rogers JA (2002) Tunable devices based on dynamic positioning of micro-fluids in microstructure optical fiber. *Optics Communications* 204: 179–184, with permission from Elsevier).



Figure 17 Schematic of a tunable device in which a high index liquid plug is moved over the grating. The plot shows the intensity of the spectrum as a function of temperature (Reproduced from Kerbage C, Windeler RS, Eggleton BJ, Dolinskoi M, Mach P and Rogers JA (2002) Tunable devices based on dynamic positioning of micro-fluids in microstructure optical fiber *Optics Communications* 204: 179–184, with permission from Elsevier).

Bandgap Guided Fibers

Bandgap fibers guide light in the core (also referred to as a defect) by confining the light through constructive interference due to Bragg scattering (Figure 12). Unlike traditional fibers, this mechanism allows light to propagate in a core that has an index lower than the cladding. Bandgap fibers with an air core could theoretically be very low loss, propagate high powers, have a large effective area core, and exhibit very low nonlinearities. In addition, the fibers can be used in novel devices by filling the core with special gasses or liquids for nonlinear processes.

Bandgap fibers can be generalized into three types (Figure 13). The first type of fiber has an air core surrounded by a cladding that consists of a periodic array of air holes in silica. Fibers of this type have been designed to guide a single mode and hold the greatest promise of guiding light over long distances with very low loss. The second type of bandgap fiber consists of a silica core and a silica cladding with a periodic array of holes which are filled with a high-index, tunable liquid. This design allows the bandgap properties to be tuned and is of interest for use in devices. The third fiber type consists of rings of alternating high- and low-index dielectric material with a center air core. They typically have a large, multimode core which is ideal for sending high powers. In addition, very little light is in the dielectric materials so the fiber can be designed to guide any wavelength with relatively little loss.

The spectrum of a bandgap fiber is quite different than an index guided fiber (Figure 14). Frequencies that lie within the bandgap cannot propagate in the cladding and are confined to the defect in the lattice (the core). Bandgap fibers with ideal geometry are predicted to have losses over an order of magnitude lower than can be obtained in an ideal traditional fiber. Although the loss of bandgap fibers has not been demonstrated to be less than traditional fiber at telecommunication wavelengths, bandgap fibers have been shown to have much lower loss than traditional fibers at other wavelengths.

Tunable Microstructure Fiber Devices

Unique tunable devices are made by filling the air holes of microstructure fibers with materials whose properties can be controlled actively (Figure 15). The materials can be positioned in the core or cladding to affect the corresponding modes. Most commonly, the index of refraction is changed using temperature sensitive liquids or polymers, although



Figure 18 Schematic of a tunable device using both high and low index liquids with two heaters. The plot shows that the position and strength of the spectrum are adjusted independently (Reproduced with permission from Mach P, Dolinski M, Baldwin KW, Rogers JA, Kerbage C, Windeler RS and Eggleton BJ (2002) Tunable microfluidic optical fiber. *Applied Physics Letters* 80(23). Copyright (2002) by the American Physical Society).

materials that respond to electric or magnetic fields enable a quicker response time. These material-filled active fibers can be used to fabricate devices like tunable filters, switches, broadband attenuators, and fibers with tunable birefringence. Below, a few examples of tunable filters are presented in which the device properties depend on the type and position of the liquid inserted in the fiber holes.

A microstructure tunable filter works by controlling the spectral position, shape, or strength of a longitudinal long-period grating written in the fiber. A grating is written in the fiber before filling the holes with tunable liquid. The position of the peak absorption wavelength is controlled by placing a liquid, with an index close to silica and strongly temperature dependent, in air holes in the cladding region over the grating (Figure 16). The cladding index is tuned by varying the temperature of the liquid, using a small thin film heater located over the liquid. The position of the peak absorption wavelength moves as the cladding index is changed.

The strength or depth of the filter is controlled by inserting a moveable plug of high-index fluid in a sealed air section of a microstructure fiber (Figure 17). The strength of the grating is determined by the fraction of the grating surrounded by high index fluid. The position of the liquid plug relative to the grating can be finely adjusted with a thin film heater located over the air region adjacent to the material plug. As heat is applied to the air, the air expands and pushes the liquid plug over the grating, decreasing the coupling of the fundamental mode to higher order cladding modes. Figure 18 shows an example in which the position and strength of a filter are varied independently using two heaters and two adjacent materials.

See also

Photonic Crystals: Photonic Crystal Lasers, Cavities and Waveguide.

Further Reading

Birks TA, Knight JC and Russell P (1997) Endlessly single mode photonic crystal fiber. *Optics Letters* 22(13).

Bjarklev A, Broeng J and Bjarklev AS, *Photonic Crystal Fibers*, Boston: Kluwer Academic Publishers.

Broeng J, Mogilevstev D, Bjarklev A and Barkou SE (1999) Photonic crystal fibers: A new class of optical waveguides. *Optical Fiber Technology*, vol. 5.

Chandalia JK, Eggleton BJ, Windeler RS, Kosinski SG, Liu X and Xu C (2001) Adiabatic coupling in tapered air-silica microstructures optical fiber. *IEEE Photonics Tech. Letters* 13(1).

Cregan RF, Mangan BJ, Knight JC, Birks TA, Russell PJ, Roberts PJ and Allan DC (1999) Single-mode photonic band gap guidance of light in air. *Science* 285.

Eggleton BJ, Westbrook PS, White CA, Kerbage C, Windeler RS and Burdge GL (2000) Cladding-mode resonance in air-silica microstructure optical fiber. *Journal Lightwave Technology* 18(8).

Joannopoulos JD, Meade RD and Winn JN (1995) *Photonic Crystals*. New Jersey: Princeton University Press.

Johnson SG, Ibanesc M, Skorobogatiy M, Weisberg M, Engeness O, Soljacic M, Jacobs SA, Joannopoubs JD and Fink Y (2001) Low-loss asymptotically single-mode propagation in large-core OmniGuide fibers. *Optics Express* 9(13).

Kerbage C, Hale A, Yablon A, Windeler RS and Eggleton BJ (2001) Integrated all fiber variable attenuator based on hybrid microstructure fiber. *Applied Physics Letters* 79(19).

Kerbage C, Windeler RS, Eggleton BJ, Dolinskoi M, Mach P and Rogers JA (2002) Tunable devices based on dynamic positioning of micro-fluids in microstructure optical fiber. *Optics Communications* 204: 179–184.

Knight JC, Birks TA, Russell PJ and Atkin DM (1996) All-silica single-mode optical fiber with photonic crystal cladding. *Optics Letters* 21(19).

Knight JC, Birks TA and Russell PJ (2001) 'Holey' silica fibers. In: Markel VA and George TF (eds). *Optics of nanostructured materials*. New York: John Wiley & Sons.

Mach P, Dolinski M, Baldwin KW, Rogers JA, Kerbage C, Windeler RS and Eggleton BJ (2002) Tunable microfluidic optical fiber. *Applied Physics Letters* vol. 80.

Ranka JK, Windeler RS and Stentz AJ (2000) Visible continuum generation in air-silica microstructure optical fibers with anomalous dispersion at 800 nm. *Optics Letters* 25(1).

Ranka JK, Windeler RS and Stentz AJ (2000) Optical properties of high-delta air-silica microstructure optical fibers. *Optics Letters* 25: 796–798.

Omnidirectional Surfaces and Fibers

S Hart, G Benoit and Y Fink, Massachusetts Institute of Technology, Cambridge, MA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Omnidirectional Reflecting Mirrors

Mirrors are probably the most prevalent of optical devices. Known to the ancients and used by them as objects of worship and beauty, mirrors are currently employed for imaging, solar energy collection, and also in laser cavities. Their intriguing optical properties have captured the imagination of scientists as well as artists and writers.

One can distinguish between two types of mirrors, the age-old metallic, and the more recent multilayer dielectric. Metallic mirrors reflect light over a broad range of frequencies incident from arbitrary angles (i.e., omnidirectional reflectance). However, at infrared and optical frequencies a few percent of the incident power is typically lost due to absorption.

Multilayer dielectric mirrors are used primarily to reflect a narrow range of frequencies incident from a particular angle or particular angular range. Unlike their metallic counterparts, dielectric reflectors can be extremely low loss. The ability to reflect light of arbitrary angle of incidence for all-dielectric structures has been associated with the existence of a complete photonic bandgap, which can exist only in a system with a dielectric function that is periodic along three orthogonal directions. In fact, a sufficient condition for the achievement of omnidirectional reflection in a periodic system with an interface, is the existence of an overlapping bandgap regime in phase space above the light cone of the ambient media.

Consider a system that is constructed of alternating dielectric layers coupled to a homogeneous medium – characterized by n_0 (such as air with $n_0 = 1$), at the interfaces. Electromagnetic waves are incident upon the multilayer film from the homogeneous medium. While such a system was analyzed extensively in the literature the possibility of omnidirectional reflectivity was not recognized until recently.

The generic system is described by the index of refraction profile in Figure 1, where h_1 and h_2 are the layer thickness, and n_1 and n_2 are the indices of refraction of the respective layers. The incident wave has a wavevector $\vec{k} = k_x\hat{e}_x + k_y\hat{e}_y$, and frequency of $\omega = c|k|$. The wavevector together with the normal to the periodic structure defines a mirror plane of symmetry which allows us to distinguish between two independent electromagnetic modes: transverse electric (TE) modes and transverse magnetic (TM) modes. For the TE mode the electric field is perpendicular to the plane, as is the magnetic field for the TM mode.

General features of the transport properties of the finite structure can be understood when the properties of the infinite structure are elucidated. In a structure with an infinite number of layers, translational symmetry along the direction perpendicular to the layers leads to Bloch wave solutions of the form:

$$u_K(x, y) = E_K(y)\,\mathrm{e}^{\mathrm{i}Ky}\,\mathrm{e}^{\mathrm{i}k_x x} \qquad [1]$$



Figure 1 Schematic of the multilayer system showing the layer parameters (n_α, h_α – index of refraction and thickness of layer α), the incident wavevector $\vec{k}$ and the electromagnetic mode convention.

where $E_K(y)$ is periodic, with a period of length a, and K is the Bloch wave number. These waves represent solutions to an eigenvalue problem and are completely and uniquely defined by the specification of K, k_x and ω.

Solutions can be propagating or evanescent, corresponding to real or imaginary Bloch wave numbers, respectively. It is convenient to display the solutions of the infinite structure by projecting the $\omega(K, k_x)$ function onto the $\omega - k_x$ plane; Figure 2a,b are examples of such projected structures.

The gray background areas highlight phase space where K is strictly real, that is, regions of propagating states, while the white areas represent regions containing evanescent states. The shape of the projected bandstructures for the multilayer film can be understood intuitively. At $k_x = 0$, the bandgap for waves traveling normal to the layers is recovered. For $k_x > 0$, the bands curve upward in frequency. As $k_x \to \infty$, the modes become largely confined to the slabs with the high index of refraction and do not couple between layers (and are therefore independent of k_x).





Figure 2 (a) Projected bandstructure of a multilayer film with the light line and Brewster line, exhibiting a reflectivity range of limited angular acceptance with ($n_1 = 2.2$ and $n_2 = 1.7$ and a thickness ratio of $h_2/h_1 = 2.2/1.7$). (b) Projected bandstructure of a multilayer film together with the light line and Brewster line, showing an omnidirectional reflectance range at the first and second harmonic (propagating states – dark gray, evanescent states – white, omnidirectional reflectance range – light grey). The film parameters are $n_1 = 4.6$ and $n_2 = 1.6$ with a thickness ratio of $h_2/h_1 = 1.6/0.8$. These parameters are similar to the actual polymer–tellurium film parameters measured in the experiment. Reproduced with permission from Fink Y, Winn JN, Fan S, *et al.* (1998) A dielectric omnidirectional reflector. *Science* 282: 1679–1682. Copyright 1998 American Association for the Advancement of Science.

In a finite structure, the translational symmetry in the directions parallel to the layers is preserved, hence k_x remains a conserved quantity and can be used to label solutions even though these solutions will no longer be of the Bloch form. The relevance of the band diagram to finite structures is that it allows for the prediction of regions of phase space where waves are evanescently decaying in the multilayer structure.

Since we are primarily interested in waves originating from the homogeneous medium external to the periodic structure, we will focus only on the portion of phase space lying above the light line. Waves originating from the homogeneous medium satisfy the condition $\omega \geq ck_x/n_0$, where n_0 is the refractive index of the homogeneous medium, and therefore they must reside above the light line. States of the homogeneous medium with $k_x = 0$ are normal incident, and those lying on the $\omega = ck_x/n_0$ line with $k_y = 0$ are incident at an angle of 90°.

The states in Figure 2a, that are lying in the restricted phase space defined by the light line and that have a (ω, k_x) corresponding to the propagating solutions (gray areas) of the crystal can propagate in both the homogeneous medium and in the structure. These waves will partially or entirely transmit through the film. Those with (ω, k_x) in the evanescent regions (white areas) can propagate in the homogeneous medium but will decay in the crystal – waves corresponding to this portion of phase space will be reflected off the structure.

The multilayer system leading to Figure 2a represents a structure with a limited reflectivity cone, since for any frequency one can always find a k_x vector for which a wave at that frequency can propagate in the crystal – and hence transmit through the film. The necessary and sufficient criterion for omnidirectional reflectivity at a given frequency is that there exists no transmitting state of the structure inside the light cone – this criterion is satisfied by frequency ranges marked in light gray in Figure 2b. In fact, the system leading to Figure 2b exhibits two omnidirectional reflectivity ranges.

The omnidirectional range is defined from above by the normal incidence bandedge $\omega_h(k_y = \pi/a, k_x = 0)$ (Figure 2b) and below by the intersection of the top of the TM allowed bandedge with the light line $\omega_l(k_y = \pi/a, k_x = \omega_l/c)$ (Figure 2b).

A dimensionless parameter used to quantify the extent of the omnidirectional range is the range to mid-range ratio defined as $(\omega_h - \omega_l)/\frac{1}{2}(\omega_h + \omega_l)$.

Figure 3 is a plot of this ratio as a function of n_2/n_1 and n_1/n_0, where ω_h and ω_l are determined by solutions of eqn [2] with quarter wave layer thickness. The contours in this figure represent various equi-omnidirectional ranges for different material index parameters and could be useful for design purposes.

At normal incidence, there is no distinction between TM and TE modes. At increasingly oblique angles, the gap of the TE mode increases, whereas the gap of the TM mode decreases. In addition, the center of the gap shifts to higher frequencies. Therefore, the criterion for the existence of omnidirectional reflectivity can be restated as the occurrence of a frequency overlap between the gap at normal incidence and the gap of the TM mode at 90°. Analytical expressions for the range to mid-range ratio can be obtained by setting:

$$\omega_h = \frac{2c}{h_2 n_2 + h_1 n_1} \cos^{-1}\left(- \left| \frac{n_1 - n_2}{n_1 + n_2} \right| \right)$$

$$\omega_l = \frac{2c}{h_2\sqrt{n_2^2 - 1} + h_1\sqrt{n_1^2 - 1}} \times \cos^{-1}\left(\left| \frac{n_1^2\sqrt{n_2^2 - 1} - n_2^2\sqrt{n_1^2 - 1}}{n_1^2\sqrt{n_2^2 - 1} + n_2^2\sqrt{n_1^2 - 1}} \right| \right) \qquad [2]$$

Moreover, the maximum range width is attained for thickness values that are not equal to the quarter wave stack though the increase in bandwidth gained by deviating from the quarter wave stack is typically only a few percent.

In general, the TM mode defines the lower frequency edge of the omnidirectional range; an example can be seen in Figure 2b for a particular choice of the indices of refraction. This can be proven by showing that:

$$\left.\frac{\partial \omega}{\partial k_y}\right|_{\mathrm{TM}} \geq \left.\frac{\partial \omega}{\partial k_y}\right|_{\mathrm{TE}} \qquad [3]$$

in the region that resides inside the light line. The physical reason for eqn [3] lies in the vectorial nature of the electric field. In the upper portion of the first band the electric field concentrates its energy in the high dielectric regions. Away from normal incidence, the electric field in the TM mode has a component in the direction of periodicity, this component forces a larger portion of the electric field into the low dielectric regions. The group velocity of the TM mode is therefore enhanced. In contrast, the electric field of the TE mode is always perpendicular to the direction of periodicity and can concentrate its energy primarily in the high dielectric region. While the omnidirectional reflection criteria can be used to confine light in various geometries, it is the cylindrical fiber configuration that appears to present significant application opportunities.



Figure 3 The range to mid-range ratio $(\omega_h - \omega_l)/\frac{1}{2}(\omega_h + \omega_l)$, for the fundamental frequency range of omnidirectional reflection, plotted as contours. Here, the layers were set to quarter wave thickness and $n_1 > n_2$. The ratio for our materials is approximately 45%. ($n_1/n_2 = 2.875$, $n_2/n_0 = 1.6$) is located at the intersection of the dashed lines (black dot). Reproduced with permission from Fink Y, Winn JN, Fan S, *et al.* (1998) A dielectric omnidirectional reflector. *Science* 282: 1679–1682. Copyright 1998 American Association for the Advancement of Science.

Mesostructured Fibers for External Reflection Applications

Polymer fibers are ubiquitous in applications such as textile fabrics, due to their excellent mechanical properties and the availability of low-cost, high-volume processing techniques; however, the control over their optical properties has so far remained relatively limited. Conversely, dielectric mirrors are used to precisely control and manipulate light in high performance optical applications, but the fabrication of these typically fragile mirrors has been mostly restricted to planar geometries and typically involves multiplicity of deposition sequences in a high vacuum thin film deposition system.

Fabrication Approach

The fabrication of extended lengths of omnidirectionally reflecting fibers with large bandgaps and


Centimeters-long macroscopic layered preform
Heating and drawing in furnace
Kilometer-long microscopic layered fiber

Figure 4 Conceptual preform based fabrication process for meso-structured fibers.

high layer counts poses considerable challenges. To illustrate the nature of this formidable task, one needs to consider the necessity of maintaining the uniformity of sub-100 nm layer thicknesses over kilometer-length scales; creating continuous layers with an aspect ratio of $\sim 10^{10}$ in a single process! To meet this and other challenges associated with the fabrication of mesostructured fibers, we have developed a preform-based fabrication approach (Figure 4). A scaled-up version of the final fiber, called a preform, is fabricated which shares the geometry and materials of the final fiber but exhibits macroscopic lateral features. The preform is heated up and drawn under tension into the fiber using a simple cylindrical furnace. The macroscopic layers are reduced in the process to microscopic dimensions while maintaining the overall geometry and symmetry of the original preform. Conservation of mass determines the final length of the fiber – typically this length is equal to the lateral reduction factor squared multiplied by the length of the preform. The nature of the process and requirements on the fiber's optical properties lead to the definition of materials selection rules. First, in order to achieve omnidirectional reflectivity, one needs to identify two solid materials exhibiting an index contrast given by the plot in Figure 3. Second, to enable the codrawing of the two dissimilar materials both will need to have viscosities that are lower than $\sim 10^8$ poise at the drawing temperature. In order to maintain high draw speeds, the majority component needs to be amorphous and the adhesion between these two materials needs to be sufficient to prevent delamination. Finally, their thermal expansion coefficients need to be close or alternatively at least one of the materials needs to be capable of relieving the stress due to CTE mismatch.

Materials Selection Criteria

Pairs of materials that are compatible with the process and fiber property requirements have been identified, including: high glass transition temperature (T_g), thermoplastic polymers such as poly(ether-sulfone) (PES), poly (ether-imide) (PEI) and members of the chalcogenide glass family, such as arsenic triselenide (As_2Se_3) or arsenic trisulfide. Pairs of these materials will have substantially different refractive indices, as shown in Figure 5, which is a measurement of the real and imaginary indices of refraction of PES and As_2Se_3, obtained using a broadband spectroscopic ellipsometer (SOPRA GES5). They nevertheless exhibit similar thermo-mechanical properties within a certain thermal processing window.



Figure 5 (a) Real part (n – light gray) and imaginary part (k – dark gray) of the refractive index of annealed As_2Se_3. The black crosses correspond to literature values. (b) Real part (n – upper) and imaginary part (k – lower) of the refractive index of PES.

Adhesion and extensional viscosity in the fluid state are difficult to measure in general, and the measurement of high-temperature surface tension is quite involved. Thus, limited data on these properties are available and it was necessary to empirically identify materials that could be used to draw out mirror-fibers. Various high-index chalcogenide (S, Se, and Te containing) glasses and low-index polymers were identified as potential candidates based on their optical properties and overlapping thermal softening regimes. Adhesion and viscosity matching were tested by thermal evaporation of a chalcogenide glass layer on top of a polymer film or rod and elongation of the coated substrate at elevated temperatures. The choice of a high-temperature polymer, PES, and a simple chalcogenide glass, As_2Se_3, resulted in excellent thermal co-deformation without film cracking or delamination. Approximate matching of extensional viscosity in this manner was also demonstrated using As_2Se_3 and PEI. The properties, processing, and applications of chalcogenide glasses have been explored extensively elsewhere. One advantage in choosing As_2Se_3 for this application is that not only is it a stable glass, but it is a stoichiometric compound that can be readily deposited in thin films through thermal evaporation or sputtering without dissociation. Additionally, As_2Se_3 is transparent to IR radiation from approximately 0.8 to 17 μm as shown in the ellipsometric data (Figure 5a), and has a refractive index of ~2.8 in the mid-IR. PES is a high-performance, dimensionally stable thermoplastic with a refractive index of ~1.6 and good transparency to EM waves in a range extending from the visible regime into the mid-IR (~5 μm), as shown in Figure 5b.


Step 1:
Stoichiometric thermal evaporation of As_2Se_3 onto free-standing PES film
Step 2:
Rolling of coated film into cladded hollow multilayer cylinder on SiO_2 tube substrate
Step 3:
Vacuum thermal consolidation
Step 4:
Fiber heating and drawing

Figure 6 Multilayer preform fabrication sequence.

Preform Construction Process and Fiber Draw

The selected materials were used to construct a multilayer preform rod, which essentially is a macroscale version of the final fiber. In order to fabricate the dielectric mirror fiber preform, an As_2Se_3 film was deposited through thermal evaporation on either side of a free-standing PES film which was then rolled on top of a PES tube substrate, forming a structure having 21 alternating layers of PES and As_2Se_3, as shown in Figure 6.

The resulting multilayer fiber preform was subsequently drawn down using an optical fiber draw tower into hundreds of meters of multilayer fiber with a precisely controlled submicron layer thickness, creating a photonic bandgap in the mid-IR. Fibers of outer diameters varying from 175–500 μm with a typical standard deviation of 10 μm from target, were drawn from the same preform to demonstrate adjustment of the reflectivity spectra through thermal deformation. The spectral position of the photonic bandgap was controlled by the optical monitoring of the outer diameter (OD) of the fiber during draw, which was later verified by reflectivity measurements on single and multiple fibers of different diameters. Scanning electron micrographs (SEMs) of the cross-section of these fibers are depicted in Figure 7.

Bandstructure for Multilayer Fibers for External Reflection Applications

In theoretically predicting the spectral response of these fibers, it is helpful to calculate the photonic



Figure 7 SEM micrographs of 400 μm OD fiber cross-section. The entire fiber is embedded in epoxy. (a) shows the entire fiber cross-section, with mirror structure surrounding the PES core; (b) demonstrates that the majority of the fiber exterior is free of significant defects and that the mirror structure adheres well to the fiber substrate; and (c) reveals the ordering and adhesion within the alternating layers of As_2Se_3 (bright layers) and PES. Stresses developed during sectioning caused some cracks in the mounting epoxy that are deflected at the fiber interface. Fibers from this batch were used in the reflectivity measurements recorded below in Figure 9a. Reproduced with permission from Hart SD, Maskaly GR, Temelkuran B, Prideaux PH, Joannopoulos JD and Fink Y (2002) External reflection from omnidirectional dielectric mirror fibers. *Science* 296: 510–513. Copyright 2002 American Association for the Advancement of Science.



Figure 8 Photonic band diagram for a one-dimensional photonic crystal having a periodic refractive index alternating between 2.8 and 1.55. Gray regions represent propagating modes within the structure, while white regions represent evanescent modes. Hatched regions represent photonic bandgaps where high reflectivity can be expected for external EM waves over an angular range extending from normal to 35° incidence. The lower dark shaded trapezoid represents a region of external omnidirectional reflection.

bandstructure that corresponds to an infinite one-dimensional photonic crystal. This allows for the analysis of propagating and evanescent modes in the structure, corresponding to real or imaginary Bloch wave number solutions.

The electric or magnetic field vector is parallel to the mirror layer interfaces for the TE and TM polarized modes, respectively. The parallel wavevector (k_y) is the component of the incident electromagnetic (EM) wavevector that is parallel to the layer interfaces. The phase space accessible from an external ambient medium is contained between the light lines (defined by the glancing-angle condition $\omega = ck_y/n_0$), and the modes between the 35° lines correspond to those sampled experimentally. Axes are normalized to the thickness *a* of one mirror bilayer (a period consisting of one high- and one low-index layer). Figure 8 depicts the photonic band diagram for an infinite structure having similar periodicity and refractive indices to the mirror structures fabricated here. Three photonic bandgaps are present where high reflectivity is expected within the 0–35° angular range, and the fundamental gap contains a region of external omnidirectional reflectivity.

Optical Characterization of ‘Mirror Fibers’

Mirror fiber reflectivity was measured from both single fibers and parallel fiber arrays using a Nicolet/SpectraTech NicPlan Infrared Microscope and Fourier Transform Infrared Spectrometer (Magna 860). The microscope objective (SpectraTech 15 ×, Reflachromat) used to focus on the fibers had a numerical aperture (NA) of 0.58. This results in a detected cone where the angle of reflection with respect to the surface normal of the structure could vary from normal incidence to ~35°, which is determined by the NA of the microscope objective. As a background reference for the reflection measurements, we used gold-coated PES fibers of matching diameters. Dielectric mirror fibers, drawn to 400 μm OD, exhibited a very strong reflection band centered at 3.4 μm wavelength (Figure 9a). Measured reflectivity spectra agree well with planar-mirror transfer matrix method (TMM) simulations, where the reflectivity was averaged across the aforementioned angular range for both polarization modes. Fibers drawn down to 200 μm OD show a similar strong fundamental reflection band centered near 1.7 μm (Figure 9b). This shifting of the primary photonic bandgap clearly illustrates the precise tuning of the reflectivity spectra over wide frequency ranges through thermal deformation processing. Strong optical signatures are measurable from single fibers as small as 200 μm OD. Fiber array measurements,



Figure 9 Measured reflectance spectra for 400 μm OD (a) and 200 μm OD (b) dielectric mirror fibers relative to gold-coated fibers of the same diameter. (a) shows a single-fiber reflectivity measurement, while (b) compares single-fiber reflectivity to that measured from a multifiber array. Simulations were performed using the transfer matrix method.

simultaneously sampling reflected light from multiple fibers, agree quite well with single-fiber data (Figure 9b).

These reflectivity results are strongly indicative of uniform layer thickness control, good interlayer adhesion, and low interdiffusion through multiple thermal treatments. This was confirmed by SEM inspection of fiber cross-sections (Figure 7). The layer thicknesses observed ($a = 0.90$ μm for the 400 μm fibers; $a = 0.45$ μm for the 200 μm fibers) correspond well to the measured reflectivity spectra. The fibers have a hole in the center, due to the choice of a hollow rod as the preform substrate, which experienced some nonuniform deformation during draw. The rolled-up mirror structure included a double outer layer of PES for mechanical protection, creating a noticeable absorption peak in the reflectivity spectrum at ~3.2 μm (Figure 9a).

A combination of spectral and direct imaging data demonstrates excellent agreement with the photonic band diagram. The measured gap width (range to mid-range ratio) of the fundamental gap for the 400 μm OD fiber is 27%, compared to 29% in the photonic band diagram.

Tunable 'Fabry–Perot' Fibers

The fabrication of fibers surrounded by or lined with alternating layers of materials with a large disparity in their refractive indices, presents interesting opportunities for passive and active optical devices. While a periodic multilayer structure, such as the one reported above, leads to the formation of photonic bandgaps and an associated range of high reflectivity, it is the incorporation of intentional deviations from periodicity, also called 'defects', which allows for the creation of localized electromagnetic modes in the vicinity of the defect. These structures, sometimes called optical cavities, in turn can provide the basis for a large number of interesting passive and active optical devices such as vertical cavity surface emitting lasers (VCSELs), bi-stable switches, tuneable dispersion compensators, tuneable drop filters, etc. Here we report on the fabrication of a fiber surrounded by a Fabry–Perot cavity structure and demonstrate that by application of axial mechanical stress, the spectral position of the resonant Fabry–Perot mode can be reversibly tuned.

Structure and Optical Properties of the Fabry–Perot Fibers

The fabrication technique described above allows for the accurate placement of optical cavities that can encompass the entire or partial fiber circumference. The fibers discussed above are made of As_2Se_3 and PES and have a low index Fabry–Perot cavity (Figure 10).

This structure was achieved by introducing an extra polymer layer in the middle of the periodic multilayer structure of the preform, thus generating a defect mode in the photonic bandgaps of the drawn fibers. The position of the bandgap center is linearly related to the optical thickness of the layers by the Bragg condition. Through accurate outer diameter control afforded by the laser micrometer mounted on the draw tower we have been able to place gaps (Figure 11) at wavelengths ranging from 11 microns to below 1 micron. Such cost-effective tuneable optical filters could lead to applications such as optical


Multilayer dielectric mirrors
r
z
θ
Applied axial strain ε_{zz}
Fabry–perot cavity
(a)
(b)
(c)
(d)
(e)
(f)

Figure 10 Schematic of the structure of dielectric mirror fibers made of As_2Se_3 (light gray) and PES (dark gray) with low index Fabry–Perot cavity. The local cylindrical coordinate system is represented as well as the applied axial strain ε_{zz}. Typical radii are ~150 μm ± 100 μm. Backscattered SEM micrographs of the cross-sections of a 460 micron diameter fiber (a, b, c) and of a 240 micron diameter fiber (d, e, f) embedded in epoxy and microtomed. (a) and (d) show the entire cross-section of the fibers, (b) and (e) demonstrate long-range layer uniformity, and (c) and (f) reveal the ordering and adhesion of the Fabry–Perot cavity structure. Bar scales have been redrawn for clarity. Reproduced with permission from Benoit G, *et al.* (2003) Static and dynamic properties of optical cavities in photonic bandgap gains. *Advanced Materials* 15: 2053–2056.



Figure 11 Array of parallel fibers with outer diameter ranging from ~420 μm (bottom) to ~100 μm (top). The colors are due to the narrow 4th order photonic bandgap in the visible.

switches for wavelength-division-multiplexing (WDM) systems and sensors.

The cross-sectional structures of a 240 micron and a 460 micron diameter fiber were observed by an SEM using a backscattered electron detector (Figure 10). The structure is composed of a hollow core polymer rod surrounded by six bilayers of As_2Se_3 and PES, separated in the middle by an extra polymer layer, which forms the Fabry–Perot cavity. An extra polymer layer protects the fiber surface. For the 240 micron (460 micron) diameter fiber, the glass layers are ~135 nm (250 nm) thick, except for the first and the last ones which are half as thick due to the fabrication technique; the polymer layers are ~270 nm (540 nm) thick and the defect layer is ~610 nm (1170 nm) thick.

Reflectivity spectra measurements were performed under a microscope using a (Nicolet SpectraTech NicPlan) Infrared Microscope and Fourier Transform Infrared Spectrometer (Magna 860) with a lens numerical aperture (NA) corresponding to 30 degrees of angular spread. They exhibited a single-mode Fabry–Perot resonant mode at 1.74 and 3.2 μm for the 240 and 460 micron diameter fiber, respectively (Figure 12).

Because of the range of incident angles, the measured quality factor (Q-factor, defined as its spectral position divided by the full width half maximum (FWHM)) was equal to 31. Using the different thicknesses and the real and imaginary part of the refractive index (n & k) of As_2Se_3 and PES carefully measured with a broadband (300 nm to 16 microns) spectroscopic ellipsometer (Sopra GES-5), the reflectivity spectra of these fibers were computed with the TMM by approximating them as a one-dimensional planar stacking. By averaging the calculated spectra over the accessible incident angles and polarizations, we obtained a very good agreement between the simulation and the measurements.



Figure 12 Computed (black lines) and measured (grey lines) reflectivity spectra for the 240 micron (a) and of the 460 micron diameter fibers (b) with Fabry–Perot resonant modes at 1.74 and 3.2 μm, respectively. Reproduced with permission from Benoit G, *et al.* (2003) Static and dynamic properties of optical cavities in photonic bandgap gains. *Advanced Materials* 15: 2053–2056.

Simulation of the Opto-Mechanical Behavior of the Fabry–Perot Fibers

We focused our analysis on the elastic regime, which ultimately limits the operational range of these fibers. The fiber's Young's modulus (E) can be approximated by modeling this multilayer structure as independent parallel springs under axial (along the z-axis of the fiber) strain assumed to be equal for all the layers, leading to a Young's modulus of 2.64 GPa (using $E_{\mathrm{PES}} = 2.4$ GPa for bulk PES and $E_{\mathrm{As_2Se_3}} = 15$ GPa reported for 1.5 μm thick films).

Neglecting the possible strain-induced refractive index variation of the materials, the normalized shift of the Fabry–Perot resonant mode can be related to the applied axial strain by calculating the radial stresses σ_{rr} (resulting from the difference between the Poisson ratios of the materials – $\nu_{\mathrm{PES}} = 0.45$ and $\nu_{\mathrm{As_2Se_3}} = 0.289$ – and the adhesion condition between the layers) and displacements u_r in each layer under axial strain. Starting from the equilibrium equations:

$$\frac{\partial \sigma_{zz}}{\partial z} = 0 \qquad [4]$$

$$\frac{\partial \sigma_{rr}}{\partial r} + \frac{\sigma_{rr} - \sigma_{\theta\theta}}{r} = 0 \Leftrightarrow \frac{\mathrm{d}^2 u_r}{\mathrm{d}^2 r} + \frac{1}{r}\frac{\mathrm{d}u_r}{\mathrm{d}r} - \frac{u_r}{r^2} = 0 \qquad [5]$$

and using Hooke's law and Lame's equations, we can derive a general expression for u_r and σ_{rr}, with two unknowns A and B per layer:

$$u_r = \frac{A}{r} + Br \qquad [6]$$

$$\sigma_{rr} = -\frac{2GA}{r^2} + 2(\eta + G)B + \lambda\varepsilon_{zz} \qquad [7]$$

where $G = E/[2(1+\nu)]$ is the shear modulus and $\eta = E\nu/[(1+\nu)(1-2\nu)]$ the Lame modulus. The continuity of the displacement and the radial stress at each interface, plus the boundary conditions (σ_{rr} vanishes at free surfaces) can be expressed as a linear system whose unique solution allows us to relate the radial strain in each layer to the applied axial strain as a linear relation $\varepsilon_{rr} = C\varepsilon_{zz}$, where C can be interpreted as an effective Poisson ratio. Finally, taking into account that the Fabry–Perot resonant mode itself is linearly shifted within the bandgap because of the different effective Poisson ratios of the glass and polymer layers, we obtain a linear relation between the normalized shift of the Fabry–Perot resonant mode and the applied axial strain:

$$\frac{\Delta\lambda}{\lambda} = -0.373\varepsilon_{zz} \qquad [8]$$

All the layers (except the outer protective polymer layer) are under tensile radial stress whose maximum (0.22 MPa under 1% axial strain) is located at the interface between the layers and the polymer core where delamination is most likely to occur.

Mechanical Tuning Experiment and Discussion

Measurements were performed on fibers ~30 cm long, which were fixed at one end with epoxy to a load cell (Transducer Techniques MDB-2.5) while the other end was attached with strong tape to a pole mounted on a stepper rotational stage (Newport PR50) (Figure 13). This end of the fiber was also screwed to the pole to further secure it in place.

The diameter of the pole was equal to 2.1 cm, leading to a normalized shift precision below 0.005%. The uncertainty on the Young's modulus, due to the precision of the load cell, was lower than 30 MPa. All the reflectivity spectra were normalized to a background taken with a flat gold mirror. The measurements were realized as far as possible from the fixed ends of the fiber where edge effects are likely to occur. These edge effects result in a reduction of the length of the fiber that deforms uniformly and consequently increase the real strain far from the edges by a factor of 1.14 and 1.15 for the 240 and the 460 micron diameter fiber, respectively (determined experimentally by measuring the position of two reference points on the fiber) compared to the strain calculated from the rotation of the pole. Moreover, to avoid measuring slight variations in the spectral position of the bandgap resulting from outer diameter variations, typically of the order of 4–5 microns over meters of fibers, the measurements were realized at a fixed reference position on the fiber.

By focusing on the fundamental bandgap of the 240 and the 460 micron diameter fiber, we demonstrated the tuning of the Fabry–Perot resonant mode under increasing axial strain (Figure 14).

A drop in the reflectivity of 13% was observed at 1.71 μm (dash line) for the 240 micron diameter fiber when increasing the applied axial strain from 0.23% (light gray) to 1.07% (dark gray). The normalized-shift versus strain curves (Figure 15) appeared to be linear for both fibers up to approximately 0.9% (dash line) with a slope equal to −0.3859 and −0.3843 for the 240 and the 460 micron diameter fiber, respectively, close to the predicted value (−0.373, eqn [8]).

The normalized shift was equal to −0.347% for 0.9% applied axial strain, which seems to be the limit of the elastic regime and corresponds to small applied


Aperture (30 degrees)
Shift of the photonic bandgap
Incident light
Reflected light normalized by background
Fiber
Rotational stage
Load cell

Figure 13 Experimental setup used for mechanical tuning demonstration. Reproduced with permission from Benoit G, *et al.* (2003) Static and dynamic properties of optical cavities in photonic bandgap gains. *Advanced Materials* 15: 2053–2056.



Figure 14 Reflectivity versus wavelength plot showing the shift of the Fabry–Perot resonant mode of the 240 micron diameter fiber for three increasing values of the applied axial strain. Reproduced with permission from Benoit G, *et al.* (2003) Static and dynamic properties of optical cavities in photonic bandgap gains. *Advanced Materials* 15: 2053–2056.

loads: 76 and 300 g for the 240 and 460 micron diameter fiber, respectively. Under higher strains, the normalized-shift versus strain curves were no longer linear and the measured loads would start decreasing slightly with time, which could be a sign of delamination between the layers and the polymer core, of plastic deformation and/or of relaxation in the layers. The stress–strain curves also exhibit an elastic regime up to approximately 1% strain with a corresponding Young's modulus equal to 2.59 GPa for the 240 μm OD fiber and to 2.39 GPa for the 460 μm OD fiber. These values are slightly lower than the predicted value, possibly due to relaxation effects in the polymer and the glass layers (for As_2Se_3 and PES, $T_g = 175$ and 220 °C, respectively).

Wavelength-Scalable Hollow Optical Fibers with Large Photonic Bandgaps for CO_2 Laser Transmission

Hollow optical transmission fibers offer the potential to circumvent fundamental limitations associated with conventional index guided fibers and thus have been the subject of active research in recent years. Here we report on the materials selection, design, fabrication, and characterization of extended lengths of hollow optical fiber lined with an interior omnidirectional dielectric mirror. These fibers consist of a hollow air core surrounded by multiple alternating submicron-thick layers of a high-refractive-index glass and a low-index polymer, resulting in large infrared photonic bandgaps. These gaps provide strong confinement of optical energy in the hollow fiber core and lead to light guidance in the fundamental and up to fourth-order gaps. We show that the fiber transmission windows can be scaled over a large wavelength range covering at least 0.75 to 10.6 microns. The utility of our approach is further demonstrated by the design and fabrication of tens of meters of hollow photonic bandgap fibers for 10.6 micron radiation transmission. We demonstrate transmission of carbon dioxide (CO_2) laser light with high power-density through more than 4 meters of hollow fiber and measure the losses to be less than 1.0 dB/m at 10.6 microns. This establishes suppression of fiber waveguide losses by orders of magnitude compared to the intrinsic fiber material losses.

Silica optical fibers have been extremely successful in telecommunications applications, and other types of solid-core fibers have been explored at wavelengths where silica is not transparent. However, all fibers that rely on light propagation principally through a solid material have certain fundamental limitations stemming from nonlinear effects, light absorption by electrons or phonons, material dispersion, and Rayleigh scattering that limit maximum optical transmission power and increase attenuation losses. These limitations have, in turn, motivated the study of a fundamentally different light-guiding methodology: the use of hollow waveguides having highly reflecting walls. Light propagation through air in a hollow fiber eliminates or greatly reduces the problems of nonlinearities, thermal lensing, and end-reflections, facilitating high-power laser guidance and other applications which may be impossible using conventional fibers. Hollow metallic or metallo-dielectric waveguides have been studied fairly extensively and found useful practical application, but their performance has been bounded by the notable losses occurring in metallic reflections at visible and infrared (IR) wavelengths, as well as by the limited length and mechanical flexibility of the fabricated waveguides. Hollow all-dielectric fibers, relying on specular or attenuated total reflection, have also been explored, but high transmission losses have prevented their broad application. More recently, all-dielectric fibers,



Figure 15 Normalized shift of the Fabry–Perot resonant mode (defined as $\Delta\lambda/\lambda$) versus applied axial strain for the 240 micron (diamonds) and the 460 micron diameter fiber (dots). The curve obtained for the 240 micron diameter fiber is lower because the experimental 0% strain is likely to correspond to a nonzero positive strain, necessary to keep this thinner fiber straight for the measurement (equivalent to a load less than 10 g). Reproduced with permission from Benoit G, *et al.* (2003) Static and dynamic properties of optical cavities in photonic bandgap gains. *Advanced Materials* 15: 2053–2056.

consisting of a periodic array of air holes in silica, have been used to guide light through air using narrow photonic bandgaps. Solid-core, index-guiding versions of these silica photonic crystal fibers have also been explored for interesting and important applications, such as very large core single-mode fibers, nonlinear enhancement and broadband supercontinuum generation, polarization maintenance, and dispersion management. However, the air-guiding capabilities of such waveguides thus far remain inferior to transmission through solid silica, due to various factors such as the difficulties in fabricating long, uniform fibers which must have a high volume fraction of air and many air–hole periods, as well as by the large electromagnetic (EM) penetration depths associated with the small photonic bandgaps achievable in these air–silica structures. In our fiber, the hollow core is surrounded by a solid high-refractive-index-contrast multilayer structure leading to large photonic bandgaps and omnidirectional reflectivity. The pertinent theoretical background and recent analyses indicate that such fibers may be able to achieve ultralow losses and other unique transmission properties. The large photonic bandgaps result in very short EM penetration depths within the layer structure, significantly reducing radiation and absorption losses while increasing robustness. Omnidirectional reflectivity is expected to reduce intermode coupling losses.

To achieve high index contrast in the layered portion of the fiber, we combined a chalcogenide glass with a refractive index of ~2.8 As_2Se_3, and a high-performance polymer with a refractive index of ~1.55 PES. We recently demonstrated that these materials could be thermally co-drawn into precisely layered structures without cracking or delamination, even under large temperature excursions. The same polymer was used as a cladding material, resulting in fibers composed of ~98% polymer by volume (not including the hollow core) and thus combine high optical performance with polymeric processability and mechanical flexibility. We fabricated a variety of fibers by depositing a 5–10 micron thick As_2Se_3 layer through thermal evaporation onto a 25–50 micron thick PES film and the subsequent ‘rolling’ of that coated film into a hollow multilayer tube called a fiber preform. This hollow macroscopic preform was consolidated by heating under vacuum and cladded with a thick outer layer of PES; the layered preform was then placed in an optical fiber draw tower and drawn down into tens or hundreds of meters of fiber having well-controlled submicron layer thicknesses. The nominal positions of the photonic bandgaps were determined by laser monitoring of the fiber OD during the draw process. Typical standard deviations in the fiber OD were ~1% of the OD. The resulting fibers were designed to have large hollow cores, useful in high-energy transmission.

SEM analysis (Figure 16) reveals that the drawn fibers maintain proportionate layer thickness ratios and that the PES and As_2Se_3 films adhere well during rigorous thermal cycling and elongation. Within the multilayer structure shown in Figure 1, the PES layers (gray) have a thickness of 900 nm, and the As_2Se_3 layers (bright) are 270 nm thick (except for the first and last As_2Se_3 layers, which are 135 nm). Broadband fiber transmission spectra were measured with a Fourier transform infrared (FTIR) spectrometer (Nicolet Magna 860), using a parabolic mirror to couple light into the fiber and an external detector. The results of these measurements are shown in the lower panel of Figure 2 for fibers having two different layer structures. For each spectrum, light is guided at the fundamental and high-order photonic bandgaps. Also shown in the upper panel of Figure 2, is the corresponding photonic band diagram for an infinite periodic multilayer structure calculated using the experimental parameters of our fiber (layer thicknesses and indices). Good agreement is found between the positions of the measured transmission peaks and the calculated bandgaps, corroborated with the SEM-measured layer thicknesses, verifying that transmission is dominated by the photonic bandgap mechanism. In order to demonstrate ‘wavelength scalability’ (i.e., the control of transmission through the fiber’s structural parameters) another fiber was produced, having the same cross-section but with thinner layers. We compared the transmission



Figure 16 Cross-sectional SEM micrographs at various magnifications of hollow cylindrical multilayer fiber mounted in epoxy. The hollow core appears black, the PES layers and cladding gray, and the As_2Se_3 layers bright white. This fiber has a fundamental photonic bandgap at a wavelength of ~3.55 microns. Reproduced with permission from Temelkuran B, Hart SD, Benoit G, Joannopoulos JD and Fink Y (2002) Wavelength-scalable hollow optical fibres with large photonic bandgaps for CO_2 laser transmission. *Nature* 420: 650–653.

spectra for the original 3.55 micron bandgap fibers to the fiber with the scaled-down layer thicknesses.

Figure 17 shows the shifting of the transmission bands, corresponding to fundamental and high-order photonic bandgaps, from one fiber to the next. The two fibers analyzed in Figure 17 were fabricated from the same fiber preform using different draw-down ratios (fibers with a fundamental bandgap centered near 3.55 microns have an OD of 670 microns; those with a gap at 3.1 microns have an OD of 600 microns). The high-order bandgaps are periodically spaced in frequency, as expected for such a photonic crystal structure.

The wavelength scalability of our fibers was further demonstrated in the fabrication of hollow fibers designed for the transmission of 10.6 micron EM radiation. This not only shows that these structures can be made to guide light at extremely disparate wavelengths, but that specific useful bandgap wavelengths can be accurately targeted during fabrication and fiber drawing. Powerful and efficient CO_2 lasers are available that emit at 10.6 microns and are used in such applications as laser surgery and materials processing, but waveguides operating at this wavelength have remained limited in length or loss levels. Using the fabrication techniques outlined above, we produced fibers having hollow core diameters of 700–750 microns and ODs of 1300–1400 microns with a fundamental photonic bandgap spanning the 10–11 micron wavelength regime, centered near 10.6 microns. Figure 5 depicts a typical FTIR transmission spectrum for these fibers, measured using ~30 cm long straight fibers.



Figure 17 Upper panel: Calculated photonic bandstructure associated with the dielectric mirror lining of the hollow fiber. Modes propagating through air and reflected by the fiber walls lie in the bandgaps (white) and within the light cone defined by the glancing-angle condition (black line). The gray regions represent modes radiating through the mirror. The fundamental bandgap has the widest range-to-mid-range ratio, with a region of omnidirectional reflectivity highlighted in black. Lower panel: Comparison of transmission spectra for two different hollow fibers of ~30 cm length having similar structure but scaled photonic crystal (multilayer) period dimensions. The spectrum in gray is from a fiber with a fundamental photonic bandgap at 3.55 microns; the black spectrum is from a fiber where the corresponding bandgap is at 3.1 microns. High-order bandgaps (indicated by arrows) are periodically spaced in frequency. Reproduced with permission from Temelkuran B, Hart SD, Benoit G, Joannopoulos JD and Fink Y (2002) Wavelength-scalable hollow optical fibres with large photonic bandgaps for CO_2 laser transmission. *Nature* 420: 650–653.

In order to quantify the transmission losses in these 10.6 micron bandgap hollow fibers, fiber cut-back measurements were performed. This involved the comparison of transmitted intensity through ~4 meters of straight fiber with the intensity of transmission through the same section of fiber cut to shorter lengths (Figure 18 inset). This test was performed on multiple sections of fiber, and the results found to be nearly identical for the different sections tested. The measurements were performed using a 25 watt CO_2 laser (GEM-25, Coherent-DEOS) and high power detectors (Newport 818T-10). The fiber was held straight, fixed at both ends as well as at multiple points in the middle to prevent variations in the input coupling and propagation conditions during fiber cutting. The laser beam was sent through focusing lenses as well as 500 micron diameter pinhole apertures and the input end face of the fiber was coated with a metal film to prevent accidental



Figure 18 Typical transmission spectrum of hollow fibers designed to transmit CO_2 laser light. The fundamental photonic bandgap is centered near a wavelength of 10.6 microns and the second-order gap is at ~5 microns. Inset: Log of transmitted power (arbitrary units) versus length of fiber (meters). The slope of this graph is the loss in dB/m. The measured fiber has a hollow core diameter of 700 microns. Reproduced with permission from Temelkuran B, Hart SD, Benoit G, Joannopoulos JD and Fink Y (2002) Wavelength-scalable hollow optical fibres with large photonic bandgaps for CO_2 laser transmission. *Nature* 420: 650–653.

laser damage from misalignment. The transmission losses in the fundamental bandgap at 10.6 microns were measured to be 0.95 dB/m, as shown in the inset of Figure 18, with an estimated measurement uncertainty of 0.15 dB/m. These loss measurements are comparable to some of the best reported loss values for other types of waveguides operating at 10.6 microns. A bending analysis for fibers with a bandgap centered at 10.6 microns revealed bending losses below 1.5 dB for 90 degree bends with bending radii from 4–10 cm. We expect that these loss levels could be lowered even further by increasing the number of layers, through optimization of the layer thickness ratios and by creating a cylindrically symmetric multilayer fiber with no inner seam (present here because of the 'rolling' fabrication method). In addition, using a polymer with lower intrinsic losses should greatly improve the transmission characteristics.

One reasonable figure of merit for optical transmission losses through hollow all-dielectric photonic bandgap fibers is to compare the hollow fiber losses to the intrinsic losses of the materials used to make the fiber. As_2Se_3 has been explored as an IR-transmitting material, yet the losses at 10.6 microns reported in the literature are ~10 dB/m for highly purified material, and more typically are greater than 10 dB/m for commercially available materials such as those used in our fabrication. Based on FTIR transmission and spectroscopic ellipsometer measurements that we have performed on PES, the optical losses associated with propagation through solid PES should be greater than 40 000 dB/m at 10.6 microns. This demonstrates that guiding light through air in our hollow bandgap fibers leads to waveguide losses that are orders of magnitude lower than the intrinsic fiber material losses, which has been one of the primary goals of hollow photonic bandgap fiber research. These comparatively low losses are made possible by the very short penetration depths of EM waves in the high refractive index contrast photonic crystal structure, allowing these materials to be used at wavelengths that may have been thought improbable. Another long-standing motivation of infrared fiber research has been the transmission of high-power laser light. As a qualitative demonstration of the potential of these fibers for such applications, both straight and smoothly bent fibers of lengths varying from 0.3–2.5 meters were used to transmit enough CO_2 laser energy to burn holes through paper. The maximum laser power density coupled into our fibers in these trials was approximately 300 W/cm^2, more than sufficient to burn a homogeneous polymer material, including PES. No damage to the fibers was observed when the laser beam was properly coupled into the hollow fiber core. These results indicate the feasibility of using hollow multilayer photonic bandgap fibers as a low-loss wavelength-scalable transmission medium for high-power laser light.

See also

Diffractive Systems: Design and Fabrication of Diffractive Optical Elements. **Fiber and Guided Wave Optics:** Fabrication of Optical Fiber. **Lasers:** Carbon Dioxide Lasers. **Spectroscopy:** Fourier Transform Spectroscopy.

Further Reading

Abeles F (1950) Investigations on the propagation of sinusoidal electromagnetic waves in stratified media. Application to thin films. *Annales de Physique* 5: 706.

Benoit G and Fink Y, Spectroscopic Ellipsometry Database, http://mit-pbg.mit.edu/Pages/Ellipsometry.html

Born M and Wolf E (1980) *Principles of Optics*, 6th edn. New York: Pergamon Press, p. 67.

Engeness TD, Ibanescu M, Johnson SG, *et al.* (2003) Dispersion tailoring and compensation by modal interactions in OmniGuide fibers. *Optics Express* 11: 1175–1198. http://www.opticsexpress.org/abstract.cfm?URI = OPEX-11-10-1175

Fink Y, Winn JN, Fan S, *et al.* (1998) A dielectric omnidirectional reflector. *Science* 282: 1679–1682.

Fink Y, Ripin DJ, Fan S, Chen C, Joannopoulos JD and Thomas EL (1999) Guiding optical light in air using an all-dielectric structure. *Journal of Lightwave Technology* 17: 2039–2041.

Hart SD, Maskaly GR, Temelkuran B, Prideaux PH, Joannopoulos JD and Fink Y (2002) External reflection from omnidirectional dielectric mirror fibers. *Science* 296: 510–513.

Ibanescu M, Johnson SG, Soljacic M, *et al.* (2003) Analysis of mode structure in hollow dielectric waveguide fibers. *Physics Review E* 67: 046608-1–8.

Johnson SG, Ibanescu M, Skorobogatiy M, *et al.* (2001) Low-loss asymptotically single-mode propagation in large-core OmniGuide fibers. *Optics Express* 9: 748–779. http://www.opticsexpress.org/abstract.cfm?URI = OPEX-9-13-748

Kuriki K, Shapira O, Hart SD, *et al.* (2004) Hollow multilayer photonic bandgap fibers for NIR applications. *Optics Express* 12: 8.

Soljacic M, Ibanescu M, Johnson SG, Joannopoulos JD and Fink Y (2003) Optical bistability in axially modulated OmniGuide fibers. *Optics Letters* 28: 516–518.

Temelkuran B, Hart SD, Benoit G, Joannopoulos JD and Fink Y (2002) Wavelength-scalable hollow optical fibres with large photonic bandgaps for CO_2 laser transmission. *Nature* 420: 650–653.

Yeh P, Yariv A and Hong C-H (1977) Electromagnetic propagation in periodic stratified media. 1. General theory. *Journal of the Optical Society of America* 67(4): 423.

Yeh P, Yariv A and Marom E (1978) Theory of Bragg fiber. *Journal of the Optical Society* 68: 1196–1201.

Wave Optical Modeling and Design

F Wyrowski, Friedrich-Schiller University, Jena, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Why do ray optics dominate the literature on optical engineering? The major practical reason may be that historically optical engineering has dealt with systems for image forming. These systems transform divergent spherical waves from points in an object, into spherical waves converging to focal points in the image. Thus, the basic operation of an imaging system performed by a lens is changing the radius of curvature of spherical fields. The propagation of spherical waves is modeled well by geometrical optics, so long as truncation by apertures and other high frequency aberrations are not significant. Moreover, the basic merit function in imaging evaluates the appearance of the image point at its correct location by so-called dot diagrams. Evaluation of this merit function requires only a ray bundle representation of the output field. The combination of a ray representation with geometrical optics propagation is called raytracing, which explains the dominance of raytracing in conventional optical engineering. Because the design of illumination systems is also often based on principles of imaging, raytracing remains a suitable technique in that case too. However, systems that perform general light transformations must apply wave-optical engineering techniques, which constitutes a generalization of conventional optical engineering. In this sense it includes the modeling of image-forming systems as a special case.

Modeling Principles

Modeling in wave-optical engineering addresses the propagation of electromagnetic fields through systems as illustrated in Figure 1. The introduction of operators and operands as mathematical tools simplifies a systematic discussion of the modeling concepts. Formally, an electromagnetic field may be expressed by the operand $\mathbf{f} \in \mathsf{F}$ with the set of fields F. The actual form of $\mathbf{f} \in \mathsf{F}$ depends on the physical approach chosen to model electromagnetic fields. For instance, $\mathbf{f} \in \mathsf{F}$ may stand for a ray bundle, a complex amplitude, or a coherence function. The photon source generates a field which acts as the input field $\mathbf{f}$ into the optical system. The quality of the output field $\mathbf{f}_{\text{out}}$ is evaluated with the help of a merit function $\boldsymbol{\Omega}$. This function may consist of M components which yields:

$$\boldsymbol{\Omega}(\mathbf{f}_{\text{out}}) = \{\Omega_1(\mathbf{f}_{\text{out}}), \ldots, \Omega_\mu(\mathbf{f}_{\text{out}}), \ldots, \Omega_M(\mathbf{f}_{\text{out}})\} \quad [1]$$

with $\Omega_\mu : \mathsf{F} \to \mathsf{R}^+$ and $\mu = 1, \ldots, M$. Each component Ω_μ defines a mathematical way to obtain one positive valued quantity for a given $\mathbf{f}_{\text{out}}$. Examples are the rms-value to evaluate the quality of a wavefront, M^2-value to judge the profile of a laser beam, center of gravity of a light distribution, light transformation efficiency, and the value of an overlap integral to determine the coupling efficiency into a fiber. Any property of the output field can be evaluated by an appropriate definition of a function Ω_μ, as long as the demanded field parameters are accessible for the field model in use. However, it should be mentioned, that it is not clear *a priori*, that all quality criteria Ω_μ can be satisfied simultaneously. How the different Ω_μ are related is dependent on the application.

The propagation of the input field through the system is mathematically summarized by the operator equation:

$$\mathbf{f}_{\text{out}} = S(p_\alpha)\mathbf{f}_{\text{in}} \quad [2]$$

with the operator $S : \mathsf{F} \to \mathsf{F}$. p_α stands for all parameters p_1, p_α, p_A which specify the system, for instance position of elements, refractive index, surface profiles, and layer thickness. Obviously a full electromagnetic model of S does not exist for arbitrary systems. The propagation problem eqn [2] is much too complex for a wave-optical solution. However, for a sequential approach the situation is different. If the propagation through a system is performed sequentially through the elements and the homogenous regions, at least approximate wave-optical methods are available to model the propagation S. In a sequential approach, either the transmitted or reflected field is considered per region



Figure 1 An optical system may include various types of elements to perform the desired optical function. Layered media, free-form surfaces, index-modulated regions, microstructured interfaces, lenses, and other structured media offer the flexibility needed to realize general light transformations. Typically structured media and homogenous regions follow each other.

of the system. Although this is an approximation, it turns out to be very useful in wave-optical engineering. With regard to Figure 2 the sequential approach is mathematically expressed by

$$\mathbf{f}_{\text{out}} = S(p_\alpha)\mathbf{f}_{\text{in}} = \mathcal{P}_J(n_J, \Delta z_J)S_{J-1}(p_{\alpha_{J-1}})\cdots S_2(p_{\alpha_2}) \times \mathcal{P}_1(n_1, \Delta z_1)\mathbf{f}_{\text{in}} \quad [3]$$

$\mathcal{P}_j(n_j, \Delta z_j)$ expresses the propagation through a homogenous dielectric with refractive index n_j and extent Δz_j. This type of propagation is also called free propagation. Sometimes the term free propagation is restricted to propagation in vacuum; Here it is used more generally. $S_j(p_{\alpha_j})$ models the propagation through an optical component which is specified by the parameters p_{α_j}. Optical engineering needs physical models for the field operand $\mathbf{f}$, the free propagation $\mathcal{P}$, and the propagation S_j through elements. The most fundamental demand in wave-optical engineering is a wave-optical model to express the field $\mathbf{f}$ in homogenous regions. It is common to restrict to harmonic fields. The generalization to more general radiation is often possible by suitable superposition of harmonic fields. This approach assumes linear optical systems as typical in optical engineering. From Maxwell's equations it follows that harmonic fields in homogenous regions are completely specified if two independent field components are determined in one plane z_0 within the region. Therefore, the electromagnetic field operand takes the form:

$$\mathbf{f}(x, y, z_0) = [E_x(x, y, z_0), E_y(x, y, z_0)] \quad [4]$$

with the complex amplitudes E_x and E_y of the x and y components of the electric field vector. Because the knowledge of $\mathbf{f}(x, y, z_0)$ allows the direct calculation of the missing complex amplitudes E_z, H_x, H_y, H_z via Maxwell's equations, the entire electromagnetic harmonic field in a homogenous region is specified by eqn [4].

With respect to the two components of the field operand $\mathbf{f}$ propagation operators S are 2×2-matrices of the form:

$$S = \begin{Bmatrix} S_{xx} & S_{xy} \\ S_{yx} & S_{yy} \end{Bmatrix} \quad [5]$$

In the case of a diagonal matrix, that is $S_{xy} = S_{yx} = 0$, E_x and E_y propagate independently and are considered decoupled channels of the system. If in addition $S_{xx} = S_{yy}$, both channels behave identically, and it is sufficient to model only one channel. This is often referred to as the scalar model. Of course, also in the scalar model the electromagnetic field still consists of two independent components and maintains its vectorial nature.

Numerical implementation of eqn [3] for the field operand of eqn [4] constitutes the backbone of modeling in wave-optical engineering.

Free Propagation

The propagation $\mathcal{P}$ of harmonic fields $\mathbf{f}$ through homogenous regions of a system has a rigorous electromagnetic solution in form of the spectrum of plane waves integral which yields:

$$\begin{aligned}\mathbf{f}(x,y,z\geq z_0) &= \mathcal{P}_{\text{SPW}}\mathbf{f}(x,y,z_0) \\ &= \begin{pmatrix} \mathcal{P}_{\text{SPW}} & 0 \\ 0 & \mathcal{P}_{\text{SPW}} \end{pmatrix}\begin{pmatrix} E_x(x,y,z_0) \\ E_y(x,y,z_0) \end{pmatrix} \\ &= \begin{pmatrix} \mathcal{F}^{-1}\left([\mathcal{F}E_x(x,y,z_0)]\mathrm{e}^{\mathrm{i}(k_x x + k_y y + k_z \Delta z)}\right) \\ \mathcal{F}^{-1}\left([\mathcal{F}E_y(x,y,z_0)]\mathrm{e}^{\mathrm{i}(k_x x + k_y y + k_z \Delta z)}\right) \end{pmatrix} \end{aligned} \quad [6]$$

with the Fourier transform $\mathcal{F}$ and $\Delta z = z - z_0$. The term $\mathcal{F}E(x,y,z_0)$ is called spectrum of planewaves (SPW). The operator matrix is diagonal and $\mathcal{P}_{\text{SPW}} = \mathcal{P}_{xx} = \mathcal{P}_{yy}$, that means the x- and y-components propagate independent of each other according to the same formula in homogenous dielectrics.



Figure 2 Formally a system may be subdivided into a sequence of homogenous dielectrics like air and inhomogeneous regions which include the elements. We indicate a region by the letter *j*.

In this sense, free propagation is a scalar problem which allows the convenient use of $U(x,y,z)$ instead of two field components for the sake of simpler mathematical expressions.

Equation [6] allows the derivation of other rigorous versions of the free propagation operator $\mathcal{P}_{\mathrm{SPW}}$, for instance Rayleigh's integral formula, which is well-known from diffraction theory. Moreover, eqn [6] leads to important approximate operators for far-field propagation and the propagation of paraxial fields. Propagation of a field into its far field is given by the operator:

$$\begin{aligned} U(r\mathbf{s}) &= \mathcal{P}_{\mathrm{far}} U(x,y,z_0) \\ &= -\mathrm{i}2\pi k s_z [\mathcal{F}U(x,y,z_0)]|_{(ks_x,ks_y)} \frac{\exp(\mathrm{i}kr)}{r} \end{aligned} \qquad [7]$$

with the wave number $k = 2\pi n/\lambda$, $r = |\mathbf{r}| = (x^2 + y^2 + (\Delta z)^2)^{1/2}$, and the direction vector $\mathbf{s} = (s_x, s_y, s_z) = \mathbf{r}/r$. Here, and in what follows, λ denotes the vacuum wavelength. $|_{(ks_x,ks_y)}$ indicates the variables to be inserted into the Fourier transformed field. Though the far-field formula is derived for $r \to \infty$, it is also of great practical value for the propagation of fields generated by nonparaxially emitting sources like laser diodes. Roughly speaking eqn [7] predicts a spherical wave in the far field which is modulated by the spectrum of planewaves of the field in z_0. $\mathcal{P}_{\mathrm{far}}$ propagates from the plane z_0 to the spherical surface with radius r and not to a plane z.

The paraxial approximation of eqn [6] follows if the spectrum of planewaves $\mathcal{F}U(x,y,z_0)$ possesses significant values only for small k_x and k_y, that is if both electric field components propagate approximately along the z-axis. The resulting propagation operator is known as Fresnel's integral formula. In practice, its formulation with the Fourier transform $\mathcal{F}$ is typically more suitable:

$$\begin{aligned} U(x,y,z \geq z_0) &= \mathcal{P}_{\mathrm{paraxial}} U(x,y,z_0) \\ &= \frac{k \exp[\mathrm{i}k\Delta z]}{\mathrm{i}2\pi\Delta z} \exp\left[\frac{\mathrm{i}k(x^2+y^2)}{2\Delta z}\right] \\ &\times \left| \left\{ \mathcal{F}\left(\exp\left[\frac{\mathrm{i}k(x^2+y^2)}{\Delta z}\right] U(x,y,z_0) \right) \right\} \right|_{(x,y)n/\lambda\Delta z} \end{aligned} \qquad [8]$$

$|_{(x,y)n/\lambda\Delta z}$ indicates the variables to be inserted after Fourier transform. The far-field approximation of eqn [8] leads to the well-known Fraunhofer diffraction formula.

Equations [6]–[8] provide fundamental operators for the propagation of fields in wave-optical engineering. All integrals are based on Fourier transforms which allows the application of the fast Fourier transform (FFT) in practice. Dependent on the propagation technique, one or two FFTs must be performed. In practice, the sampling of fields is of great concern. Naturally the amount of data should be as small as possible. According to the rigorous propagation operator eqn [6] the (x,y)-coordinate system and therefore the sampling period in z_0 and z are identical, that is, scaling does not occur. As illustrated in Figure 3, that can lead to an enormous amount of data for large propagation distances. For demonstration purpose the field amplitude depicted at the top is chosen. The field window has the size 1 mm × 4 mm. The wavelength λ is 632.8 nm, $n = 1$, and the sampling distance 10 µm. That results in 100 × 400 sampling points. Propagation of this field with the spectrum of planewave operator maintains the size of the field window. The resulting field for a propagation distance $\Delta z = 10$ mm is shown in the middle. Because of diffraction, the field widens. As long as the initial window is large enough to encompass the propagated field, the propagation method works well. At the bottom, the resulting field for $\Delta z = 200$ mm is shown. The field exceeds the size of the window and that leads to numerical errors (aliasing). This can be avoided by embedding the initial field into a window which is large enough with respect to the expected size of the propagated field. As a result, one obtains the



Figure 3 Illustration of numerical properties of the spectrum of plane wave propagation technique. The field amplitude depicted at the top is numerically propagated in free space and the distributions in the middle and the bottom are obtained. The simulations in this and all following figures were performed. The simulations in this and all following figures were performed with the wave-optical engineering software VirtualLab™ from LightTrans GmbH.



Figure 4 Starting from the same input field and the same distances as in Figure 3 the propagated fields depicted in the middle and the bottom are obtained using the paraxial propagation operator. Because of the inherent scaling the field window sizes are 632.8 μm × 632.8 μm and 12.656 mm × 12.656 mm, respectively. The number of sampling points remains unchanged. Obviously, the field in the middle is too small to encompass the propagated field and numerical errors occur. For the long distance the field size is perfectly matched to the field size obtained by propagation.

demanded accuracy at cost of increasing data memory requirements and computation time. Thus in practice the SPW propagation operator is particularly suitable for short distances. Fortunately the paraxial propagation operator eqn [6] possesses a complementary behavior. Because of $(x, y)n/\lambda\Delta z$, the (x, y)-coordinate system changes its scaling with the distance. As illustrated in Figure 4, that makes it well suited for large propagation distances but problems occur for small ones. Therefore, all paraxial propagation problems have an efficient numerical solution by a suitable combination of $\mathcal{P}_{\text{paraxial}}$ and $\mathcal{P}_{\text{SPW}}$. In the nonparaxial case the far-field operator eqn [7] often helps to realize a numerically efficient propagation for large distances. However, there are sometimes situations, in which free propagation of nonparaxial fields causes significant numerical problems.

Propagation Through Elements

The propagation of harmonic fields $\mathbf{f}$ through elements is a challenging task. For example, Figure 5 illustrates propagation through smooth or microstructured interfaces between two homogenous media. The field $\mathbf{f}_1(x, y, z_1)$ should be determined if $\mathbf{f}_0(x, y, z_0)$, the shape of the interface, and the refractive indices n_0 and n_1 are known. The reflection mode of operation can be formulated analogously. It is remarkable that this basic problem possesses a rigorous solution only for a few special interface geometries. Of particular importance are the rigorous solutions for plane and periodic interfaces. In the first case, the solution comprizes Snell's law of refraction, the law of reflection, and Fresnel's formulae. Grating theory provides the solution for periodic interfaces. It is possible to use these methods also for nonperiodic interfaces but at the cost of immense computational effort. Thus, they are only practicable for structures with detail no larger than a few wavelengths. For general interfaces, accurate approximate methods are required. One approach is to decompose a general propagation problem into a set of simpler problems that can be solved rigorously. The results are then combined to obtain an approximate solution of the original problem. Two basic concepts for subdividing the general problem are: (i) Decomposition of the incident field into laterally truncated fragments which illuminate elementary fractions of the interface. (ii) Decomposition of the response of the interaction of the incident field with the interface into approximately independent ones related to local interface features. The first technique is referred to as local elementary interface approximation (LEIA) and the second one as local independent response approximation (LIRA). Elementary interfaces of particular importance are plane, periodic, and spherical ones.



Figure 5 A planewave $\mathbf{f}_0$ propagates through an interface between two homogeneous dielectrics with refractive index n_0 and n_1. The interface is of general shape and therefore a rigorous solution of the propagation problem does not exist. The virtual planes in z_0 and z_1 encompass the interface in a way which minimizes the distance $z_1 - z_0$.

The local plane interface approximation (LPIA) is of particular importance in wave-optical engineering. Figure 6 illustrates the basic concept for the example



Figure 6 If a lateral fraction of the input field is propagated towards the interface, it is often possible to laterally restrict the major part of the propagated field to a local plane interface. Because of diffraction it is never possible to do that rigorously. Neglecting diffraction in the region between z_0 and z_1 provides a simple model to propagate a section of the incident plane field through the interface. Fresnel's formulae and Snell's law of refraction can then be applied directly to obtain the transmitted plane field, which is propagated to the plane z_1.

of a plane incident field. It has been proven that the approximation of geometrical optics propagation within the regions of the component, here that means between z_0 and z_1, provides results which are surprisingly accurate in numerous situations of practical interest. A full wave-optical version of LPIA is currently under research and development. In general, however, LPIA is applicable if the characteristic lateral extent of the local modulation of the interface is not close to the wavelength. It should be emphasized that LPIA is, as most other approximate propagation techniques, a 2 × 2 matrix, like eqn [5], with nonvanishing components. That means, for instance, that in general, an E_y-component occurs in z_1 even if $E_y = 0$ in z_0. That is, the two field channels experience crosstalk. A further approximation in geometrical optics LPIA, popular in Fourier optics holography, and diffractive optics is the thin element approximation (TEA). Geometrical optics LPIA leads to TEA if refraction and the local dependence of Fresnel losses at the interface are neglected. Obviously, that is allowed only if all angles involved, including the slope of the interface and the direction of the input field, are small. Therefore, TEA is a paraxial and geometrical optics approximation. Moreover, small local slopes of the interface lead to a restriction to thin elements, which explains the name TEA. It is also referred to as scalar approximation, because the operator matrix becomes diagonal with $S_{\mathrm{TEA}} = S_{xx} = S_{yy}$, that means the two field channels propagate independently according the same formula through the interface. In the thin element only approximation the dependence of the optical path through the element on position (x, y) is considered and mathematically takes the form:

$$\begin{aligned} U(x,y,z_1) &= S_{\mathrm{TEA}}U(x,y,z_0) \\ &= c_{\mathrm{Fresnel}}U(x,y,z_0)\exp\left[\frac{\mathrm{i}2\pi n_1(z_1-z_0)}{\lambda}\right] \\ &\quad\times\exp\left[\frac{\mathrm{i}2\pi h(x,y)(n_0-n_1)}{\lambda}\right] \end{aligned} \qquad [9]$$

with the vacuum wavelength λ. The profile height $h(x, y)$ is expressed as the distance from z_0 to the interface. Propagation through an interface between dielectrics modeled with TEA affects the phase of the incident field proportional to the profile height. The magnitude remains unchanged besides a constant factor c_{Fresnel}, due to Fresnel's equations. If complex valued refractive indices are taken into consideration, absorption results in an amplitude modulation completely analogous to the phase modulation described in eqn [9]. This way it is also possible to address the propagation through apertures and the combination of S_{TEA} with $\mathcal{P}$ leads to the well-known diffraction integrals. In fact, Kirchhoff's boundary conditions of field propagation through a hole in a completely opaque screen can be interpreted as TEA for complex valued refractive indices.

The simple form of the TEA operator allows a straightforward numerical implementation. The field operand and the profile are equidistantly sampled and the resulting field is sampled analogously. That makes the combination of S_{TEA} with numerical implementations of the free propagation operators $\mathcal{P}$ easy. As soon as refraction is considered in geometrical optics LPIA, the equidistant sampling of the output field is destroyed which enforces additional interpolation effort before a free propagation by fast Fourier transforms can be implemented, because fast numerical Fourier transform algorithms require an equidistant sampling.

In wave-optical engineering the combination of geometrical optics LPIA with a wave-optical field model is mandatory. In this context it is instructive to mention, that its combination with a ray-bundle representation of the incident electromagnetic field leads to raytracing through the interface, that is it reduces to the basic technique in conventional optical engineering.

Similar to LPIA it is possible to consider linear gratings as elementary local interface and the local linear grating approximation (LLGA) results. It is of special concern for all types of diffractive elements, for which the interface can locally considered periodically. An important example is given for diffractive lenses in the outer zones of high numerical aperture lenses. In the center and for low numerical aperture TEA is appropriate for propagating through diffractive lenses.

Design Principles

The design problem in wave-optical engineering can be stated as follows: specify system parameters p_α in a way that ensures for a given input field $\mathbf{f}_{\text{in}}$ an output field $\mathbf{f}_{\text{out}}$ which satisfies the quality criteria defined by the merit functions Ω_μ. In addition, one may demand a system which is most simple, particularly cheap, or various other system properties of concern in practice.

Design constitutes an optimization problem. Restrictions to the system parameters and the merit function sets design constraints as well as design freedoms.

System parameters can be restricted, for instance, by the materials available, the maximum size of a system, and types of element profiles. Within these limits the system parameters are chosen freely during optimization to achieve the optical function.

The merit functions determines which parameters of the output field are important and should be emphasized, for instance the intensity distribution. All output fields, whose parameters satisfy the constraints satisfy the design problem. In most applications, not all field parameters are constrained. For instance, in laser materials processing or illumination applications, the merit function is related to energy quantities and then the phase of the output field can be used as a free parameter distribution. Moreover, the output field is typically not constrained in the entire output plane, but only in so-called signal regions, which introduces freedom of amplitude outside the signal regions. Hence, dependent on the application, there exist field parameters that can be chosen partly or completely free during design.

Successful design strategies use the freedoms to improve the matrix function. It is often not clear a priori, if a solution does exist. Then the field constraints are satisfied as good as possible in terms of the merit function.

In imaging systems, typical system parameters include, for instance, distances, refractive indices, curvature of lenses, and parameters to specify aspherical surfaces. For high-end lens systems, the resulting number of parameters can be large, but they are still small enough to utilize parameter optimization algorithms if the designer starts with a reasonable initial guess. In wave-optical engineering, the number of system parameters can become huge due to the generalized nature of the structures, which typically prevents the use of system parameter optimization techniques. For example, the profile of diffractive elements is typically specified by 10^4–10^6 parameters. Thus a direct optimization of the system parameters, which requires the evaluation of $S(p_\alpha)$ (see eqn [3]) after any change of system parameters p_α, is not realistic.

Instead of optimizing the system parameters directly, which is referred to as design in the structural embodiment of the system, a technique wellknown from Fourier optics and diffractive optics can be generalized for wave-optical engineering. It does not start with structure related element parameters but replaces all or at least some of the operators $S_j(p_{\alpha_j})$ of eqn [3] by mathematical operators $\mathcal{T}_j(t_{\tau_j})$. t_τ denotes the parameters of $\mathcal{T}$. The propagation operator through a system expressed in this functional embodiment has the form:

$$\begin{aligned}\mathbf{f}_{\text{out}} &= S_{\text{functional}}\mathbf{f}_{\text{in}} \\ &= \mathcal{P}_J(n_J, \Delta z_J)\mathcal{T}_{J-1}(t_{\tau_{J-1}})\cdots\mathcal{T}_2(t_{\tau_2}) \\ &\quad \times \mathcal{P}_1(n_1, \Delta z_1)\mathbf{f}_{\text{in}} \end{aligned} \tag{10}$$

if all propagations through elements are expressed in functional form. A very important example of a functional operator $\mathcal{T}$ is given by a simple multiplication of both field components with identical or different complex functions $t(x, y)$, that is:

$$\mathcal{T}_t(t_\tau)\mathbf{f}_{\text{in}} = \begin{pmatrix} t_{xx}(x, y) & 0 \\ 0 & t_{yy}(x, y) \end{pmatrix}\mathbf{f}_{\text{in}}(x, y) \tag{11}$$

The values of both $t(x, y)$ form the parameters t_τ of $\mathcal{T}$. The functions $t(x, y)$ are also called ideal transmission functions of elements. Of special interest are phase-only transmission functions $t(x, y) = \exp[i\tau(x, y)]$ (see discussion below). If $t(x, y) = t_{xx}(x, y) = t_{yy}(x, y)$, the design is simplified. Fortunately, in most actual applications this assumption is valid.

Designing in the functional embodiment requires the evaluation of $S_{\text{functional}}$ instead of S of eqn [3], which reduces the numerical complexity enormously. That improves the likelihood for developing efficient design algorithms to optimize the distances Δz_j, the refractive indices n_j, and parameters t_{τ_j}.

The design in the functional embodiment does not deliver the structure parameters of elements but only parameters t_τ of the operator $\mathcal{T}$ which gives information about how a field should be changed at the position z where $\mathcal{T}$ takes effect. Thus, in a next design step, elements must be obtained which cause the required effect. This so-called structure design step is also generally challenging because it requires the solution of an inverse propagation problem through interfaces. For a further discussion the most important $\mathcal{T}$, that is the transmission type operator of eqn [11], is considered. For the sake of simplicity $t(x, y) = t_{xx}(x, y) = t_{yy}(x, y)$ is assumed. Then, a solution which uses geometrical optics LPIA in combination with phase-only transmissions is known in the form of a recursive structure design strategy. In its paraxial approximation, that is TEA, the solution becomes very simple. For a transmission $t(x, y) = \exp[\mathrm{i}\tau(x, y)]$, obtained from a functional design, an element with a surface profile:

$$h(x, y) = \frac{\lambda \tau(x, y)}{2\pi(n_{\text{element}} - n_{\text{free}})} \qquad [12]$$

results from eqn [9]. The refractive index of the element is denoted by n_{element} and the homogenous region behind the element has the index n_{free}, eqn [12] constitutes a direct relationship between the phase values of the transmission function and the profile $h(x, y)$. This structure design technique is accurate for all paraxial situations. However, it is also a reasonable method for nonparaxial structure design since it provides an initial profile for further optimization. Obviously it is applicable for phase-only transmission functions only. That underlines the importance of this type of functional operator for the design in the functional embodiment. Often the fabrication of profiles is done with lithographic techniques which result in surface reliefs with a few discrete height levels, that means the profile $h(x, y)$ is quantized. According to eqn [12] a quantization of $h(x, y)$ directly leads to quantized phase values $\tau(x, y)$. This quantization must be taken into account when designing $\tau(x, y)$. An example should serve to discuss further aspects of structure design according to eqn [9]. A fundamental transmission in various applications is the phase of a spherical wave and its paraxial version, the quadratic phase. An example of a spherical phase $\tau(x, y)$ is shown in Figure 7 where the 2π-modularity of the exponential function is taken into account – as normal for phase data which has been obtained by numerical calculations. Inserting this phase into eqn [9] leads to the profile of a diffractive lens. Because of the use of inverse TEA for structure design it works as demanded for moderate numerical apertures and starts to suffer from aberrations for large numerical apertures because of electromagnetic effects in the very outer zones. It is also possible to unwrap the phase before inserting it into eqn [9]. Then a smooth surface, that is a refractive spherical lens, results. It is well-known that a spherical lens works accurately in the paraxial domain and suffers from aberrations for moderate and large numerical apertures, which are more severe than for the diffractive lens. The use of inverse geometrical optics LPIA as a structure design technique is not restricted to the paraxial domain and therefore it leads to a suitable aspherical surface in order to ensure a spherical phase transmission for larger numerical apertures too. This is illustrated in Figure 8. The lens example shows another advantage of the two-step design method, which consists of the design in the functional embodiment prior to the one in the structural form of the element. In the functional



Figure 7 The phase of a spherical phase in the 2π-modulo representation. This phase can be unwrapped which leads to a smooth spherical phase which varies from 0 to various 2π. The noisy edges are due to the use of a cartesian coordinate system.



Figure 8 Application of the thin lens approximation for structure design leads to a spherical surface for a spherical phase-only transmission. The corresponding surface is depicted by the dotted line. If geometrical optics LPIA is used for structure design, an aspherical surface is obtained as required. The aspherical surface is depicted by the solid line. The height of the surfaces are shown as function of the radius *r*. Naturally the difference between TEA and geometrical optics LPIA occurs for larger *r* only.

form the transmission is obtained. It is not necessary to decide about the use of a diffractive or a refractive element in an early stage of the design. Moreover, it provides the designer with insight into selecting optical elements to achieve the function. If the phase-only transmission can be unwrapped, a refractive as well as a diffractive element can be used. An optical engineer has the freedom to decide about the suitable choice taking fabrication, size, costs, and other additional constraints into account. However, as soon as the phase-only transmission includes so-called vortices, unwrapping is not possible and diffractive optics is mandatory. An example of a vortex is shown in Figure 9. It turns out that vortices are more likely to appear in wave-optical engineering the less image-like the optical function is (see also last section). It is important to note, that functional design assumes a diagonal operator matrix, that is, it excludes crosstalk of the two field channels. Transferring the system into a structural form may violate this assumption because of vectorial effects in the nonparaxial domain. For instance, geometrical optics LPIA in general does not correspond to a diagonal operator. Therefore, it is necessary to analyze the final system for $\mathbf{f}_{\text{in}}$ – even in the case of linear polarized light – using more accurate propagation techniques than S_{TEA} if it is not ensured that the paraxial approximation is accurate enough.



Figure 9 Illustration of a single vortex of charge one. The phase varies from 0 to 2π. Because of the vortex, this phase is not unwrappable, that means a smooth phase function cannot be obtained. The transition in the phase function requires a microstructure in the profile of the element, which generates this phase-only transmission.

The so-called thin lens, or ideal lens, in conventional optical engineering constitutes a special case of the two-step design strategy. In the first design step, distances and lens focal lengths are determined, without taking into account the actual shape of a lens. In the second step lenses, or even lens systems, are inserted according to the position and the focal length specified in the first step. Thus, wave-optical engineering extends our understanding by broadening established methods in optical engineering.

Fundamental Systems

A smart approach to design minimizes the number of elements required to achieve a desired light transformation. Thus, it is logical to try a functional design with a system of the form:

$$\begin{aligned} U_{\text{out}}(x,y) &= S_{\text{functional}} U_{\text{in}}(x,y) \\ &= \mathcal{P}(n_{\text{free}}, \Delta z_{\text{out}}) \exp[i\tau(x,y)] \\ &\quad \times \mathcal{P}(n_{\text{free}}, \Delta z_{\text{in}}) U_{\text{in}}(x,y) \end{aligned} \qquad [13]$$

which is illustrated in Figure 10. One phase-only transmission, properly placed between the input and the output plane, should realize the desired transformation of the function. Scalar terminology is used, because both components are decoupled in the functional embodiment.



Figure 10 A basic system for light transformation can be described functionally by two propagations through homogeneous dielectrics with refractive index n_{free} and one phase-only transmission function. (b) If the second propagation is replaced by an operation in functional form, here the Fourier transform, the setup shown on the right side results.

If the output field is completely specified by the merit function, for instance: if the complex amplitude of a laser beam should be transformed into another one, the so-called amplitude matching strategy is a very powerful technique to solve the design problem stated by eqn [13]. In amplitude matching one determines the Distances Δz_{in} and Δz_{out} such that the inverse propagated U_{out} and the forward propagated U_{in} possess identical magnitudes. If such distances exist, the transformation can be realized using a phase-only transmission in the plane z_t. The phase simply follows from the ratio of the propagated fields. If no distances exist where amplitude matching occurs, the design problem has no solution and at least one more transmission function must be introduced.

As mentioned above, in numerous applications the output field is not specified completely. In particular, phase is often a free parameter. Then, an even simpler system approach than the one suggested by eqn [13], often leads to reasonable solution. Instead of $\mathcal{P}(n_{\text{free}}, \Delta z_{\text{out}})$, a Fourier transform is assumed, then if,

$$\begin{aligned} U_{\text{out}}(k_x, k_y) &= S_{\text{functional}} U_{\text{in}}(x, y) \\ &= \mathcal{F}\{\exp[\mathrm{i}\tau(x, y)]\mathcal{P}(n_{\text{free}}, \Delta z_{\text{in}})U_{\text{in}}(x, y)\} \end{aligned} \qquad [14]$$

The output field is expressed in k-coordinates as long as the system is discussed in functional form. For a functional design the distance Δz_{in} is of no concern, however it must be chosen together with the structure design as discussed below. Thus, in functional design, one concentrates only on the design of the transmission function. The iterative Fourier transform algorithm (IFTA), an extremely powerful algorithm, has been developed to accomplish this design. Its principle is illustrated in Figure 11. The algorithm sequentially applies constraints on the transmission and in the Fourier plane. Properly controlled, the algorithm converges to a Fourier pair for which the transmission plane constraint is satisfied completely and the Fourier domain constraint is satisfied as accurately as required by the merit function. The initial distribution is of enormous importance for a successful transmission design. Typically the initial distribution is defined in the Fourier plane as shown in Figure 11. A field $U_{\text{sig}}(k_x, k_y)$ is chosen, which satisfies the merit function. It is called the signal field. Because of design freedoms such as phase, typically there exists a set of signal fields F_{sig}. If phase freedom is available, any field with the desired amplitude and an arbitrary phase is an element of F_{sig} and can be used as initial distribution of the IFTA. Dependent on the application, the choice of the phase is of fundamental concern. In the following we assume phase freedom is available, but IFTA is also useful if this is not the case.


Initial signal field
Satisfying constraints in Fourier/signal plane
$\mathcal{F}$
$\mathcal{F}^{-1}$
Satisfying constraints in transmission plane
Designed transmission

Figure 11 Illustration of the basic principle of the iterative Fourier transform algorithm (IFTA). By a sequential satisfaction of constraints in the signal and the transmission plane, the design in the functional embodiment can be accomplished. If both constraints are satisfied accurate enough, the IFTA is terminated with a final satisfaction of the transmission plane constraints. The depicted IFTA version can be generalized by replacing $\mathcal{F}$ by $\mathcal{P}$ or any S.

It is helpful to distinguish between two types of signal fields. If amplitudes for only a finite number of discrete k-values, (i.e., angles or directions), need to be determined, the transmission acts as a diffractive beamsplitter. In all other cases more general light transformations are concerned.

The constraints in the transmission plane follow from the structure design. In most cases the structure design is done by TEA according to eqn [12]. Then, phase-only transmissions are required. Typically the fabrication of the corresponding element profile demands a phase quantization in addition. Both constraints have been intensively investigated for the IFTA.

As mentioned above, practically signal fields are always restricted to one or more signal regions of finite extent. For example, a detector has finite extent. Outside of these regions the signal may be unrestricted or only partially restricted. This freedom in amplitude outside the signal regions is fundamental for a successful design of phase-only transmissions. It has been shown, that the only phase-only function whose Fourier transform exists over a finite area is a linear phase. The transform of all other phase-only functions contribute energy outside of the signal regions. In other words, the use of amplitude freedom is mandatory. Energy losses due to stray light outside the signal region cannot be avoided. As a result, it is not possible to generate the desired response with 100% efficiency. For any given signal field U_{sig} an upper bound $\eta_{\mathrm{bound}}(U_{\mathrm{sig}})$ of the achievable efficiency $\eta(U_{\mathrm{sig}})$ of light transformation with a phase-only transmission has been derived, that is $\eta(U_{\mathrm{sig}}) \leq \eta_{\mathrm{bound}}(U_{\mathrm{sig}})$. The equal sign is only valid for the special case of a linear phase transmission, for which the signal field consists of one k-direction only. Then $\eta_{\mathrm{bound}}(U_{\mathrm{sig}}) = \eta(U_{\mathrm{sig}}) = 1$ is obtained. After structure design for a linear phase-only transmission with TEA, a so-called blazed grating results. If TEA is a sufficient approximation one concludes that a blazed grating has a theoretical efficiency of 100%. For all other signals the theoretical efficiency is smaller than 100%. Moreover, the upper bound is a function of U_{sig} and thus also of its phase. Therefore, in a first step of a transmission design it is recommendable to perform a phase synthesis which maximizes the upper bound. This first design step delivers information about achieveable efficiency and a suitable initial signal field for the IFTA.

If fabrication requires phase quantization, amplitude freedom can be used to separate quantization noise from the signal regions. Unfortunately this reduces the achievable efficiency even more. If the phase to be quantized is homogenously distributed, the upper bound for a phase-only transmission quantized to Q equidistant phase levels is given by:

$$\eta_{\mathrm{bound}}(U_{\mathrm{sig}}, Q) = \mathrm{sinc}^2\left[\frac{1}{Q}\right]\eta_{\mathrm{bound}}(U_{\mathrm{sig}}) \qquad [15]$$

For the special case of linear phase, the well-known formula $\eta(Q) = \mathrm{sinc}^2[1/Q]$ follows. The values of $\mathrm{sinc}^2[1/Q]$ and therefore of quantized blazed gratings in the paraxial approximation are 0.405, 0.812, 0.950, 0.987, and 0.997 for $Q = 2$, 4, 8, 16, and 32, respectively. This result does not mean that, for example, a diffractive beamsplitter with a splitting ratio $1 : M_{\mathrm{beams}}$ and 16 height levels will provide ~99% efficiency. According to eqn [15], the theoretical values are smaller and depend on M_{beams} because $\eta_{\mathrm{bound}}(U_{\mathrm{sig}})$ depends via U_{sig} on M_{beams}. If fabrication processes and the inherent imperfections are taken into consideration, the values decrease even more. As a rule of thumb, it is possible to claim that efficiencies larger than 90% are always challenging to obtain. With sophisticated design and fabrication techniques, efficiencies larger than 80% are reasonable.

Up to now, we have discussed only the importance of the signal field phase to efficiency. But the phase of the initial signal field has another extremely important effect on the result of the transmission design. From mapping-type considerations, a smooth initial signal field phase can be constructed in order to realize a light transformation. An example is illustrated in Figure 12. It shows the central part of the phase of the transmission function which transforms a Gaussian input beam into a flat-top line beam. Because of the smooth signal phase also the transmission phase is smooth and therefore unwrappable. This approach is typical for a so-called beam shaping design. It requires a well-defined input beam and high accuracy in adjustment of the beam shaping optics to obtain the output field with good quality. If, instead of a smooth initial phase, a random one is applied, the situation illustrated in Figure 13 (left) is achieved. Here the phase of the transmission looks random, which is typical for beamsplitter and diffuser. Because such phase functions possess numerous vortices, they do not allow an unwrapping. Thus, diffractive elements are the logical result of structure design. An example is shown in Figure 13 (right).

Figure 14 shows how light from a laser diode passes through the diffuser element of Figure 13 (right). The radiation is transformed into an intensity pattern that depicts the ‘skyline’ of Jena. Although globally the intensity possesses the requested shape, a closer look shows that the intensity distribution is speckled. However, in numerous applications this is not a problem so long as the size of the speckles is well adapted to the resolution of the detector.



Figure 12 The input beam on the left propagates through the transmission function the central part of the phase of which is shown in the middle and in the signal plane the amplitude shown on the right results. This Gaussian-to-line transformation is a typical beam shaping design task.



Figure 13 A typical phase distribution of a transmission (left) which results from design with IFTA for a random initial signal field phase. Numerous vortexes prevent its unwrapping. Therefore, structure design leads to diffractive elements. Then, a quantization of the phase is demanded in most cases. An example is shown on the right-handed side. It depicts a portion of a four level diffuser which results in the output field shown in Figure 14. The pixel size is 400 nm and the corresponding element was designed and fabricated in a cooperation of LightTrans GmbH and the Institute of Applied Physics at the University of Jena.



Figure 14 Optical demonstration of the use of a diffuser (see in Figure (right)) transforming a laser diode beam into an intensity displaying the 'skyline' of Jena. No additional optical element is needed! Stray light appears but is laterally separated from the desired signal and thus it is easy to be filtered.

This technique is called diffuser-type light transformation. The appearance of the global intensity distribution is robust against variations in the input beam and thus is well-suited also for partial coherent illumination, for example radiation from an excimer laser and LED. In that case, even the appearance of speckles is reduced or vanishes completely. The mapping-type and the diffuser-type approach to choose the initial signal phase constitute two extreme cases of a great variety to control basic aspects of light transformation using different initial phases.

After choosing a suitable initial signal field $U_{\mathrm{sig}}(k_x, k_y)$ the IFTA typically performs well and a transmission function is obtained, which leads to $|U_{\mathrm{out}}(k_x, k_y)|^2 \propto |U_{\mathrm{sig}}(k_x, k_y)|^2$ in the signal region with minimum error. In the next step the structural design must be performed. The structure of the element is calculated via eqn [12].

Besides designing structure to produce the desired transmission function one needs to realize optically the Fourier transformation. Placing the observation plane in the far field behind the element is the most straightforward way to achieve this. However, field Fourier transformation can also be realized by lenses as shown in Figure 15. From simple geometric considerations using paraxial approximation one obtains:

$$\alpha = \frac{2\pi n_{\mathrm{free}}}{\lambda f_{\mathrm{e}}} \qquad [16]$$

Each system produces a Fourier transform that is scaled specially by α, where the output field is considered in a dielectric with refractive index n_{free}. The effective focal length f_{e} is equal to the focal length of the lens if the element is placed in front of the lens (see top of Figure 15), the distance of the element to the lens is of no concern for the resulting intensity, however it is recommended to minimize the distance between element and lens for elements with deflection angles close to the paraxial limit. That avoids light losses due to truncation by the lens aperture. If the focal length itself is chosen as the distance of the element to the lens, a so-called $2f$-setup results, which generate, in addition to the correct magnitude, the correct phase of the Fourier transformation in the focal plane. If an alternative distance to the lens is used, an additional quadratic phase occurs in the focal plane. If the element is placed behind the lens (see middle row of Figure 15), f_{e} is the distance between element and focal plane. This setup provides some freedom in adjusting the output scaling. On the other hand, it requires an accurate adjustment of position to obtain a specific scaling. This is not required for the first setup. In order to obtain a specific



Figure 15 Three setups to realize a Fourier transformation for a beam shaping or diffuser/splitter element, which deflects the light only in a paraxial way. In all cases the output is obtained in the focal plane of the lens.

scaling of the output field $U_{\mathrm{out}}(\alpha x, \alpha y)$, the effective focal length and the size of $U_{\mathrm{sig}}(k_x, k_y)$ in the k-space must be chosen properly according to eqn [16]. In addition to the size of the output field, its resolution is also of fundamental importance. According to eqn [14] and the convolution theorem the output field is given by

$$U_{\mathrm{out}}(k_x, k_y) = \mathcal{F}\ \exp[\mathrm{i}\tau(x, y)] * \mathcal{F}\mathcal{P}(\Delta z_{\mathrm{in}})U_{\mathrm{in}}(x, y) \qquad [17]$$

where $*$ denotes the convolution. For a constant transmission function one would obtain the focus of the input beam. In functional embodiment that is $\mathcal{F}\mathcal{P}(\Delta z_{\mathrm{in}})U_{\mathrm{in}}(x, y)$ only. In the structural form, the focus of the beam must be calculated by propagating the input field through the system without the transmission function. The Fourier transformed transmission function, that is $\mathcal{F}\ \exp[\mathrm{i}\tau(x, y)]$, is convolved with this beam focus in order to obtain the resulting output field. In beamsplitting that means a replication of the beam. In general the output field can be understood as being composed of numerous replicated beam foci which are overlapping. That makes plausible that the size of the focus of the input beam limits the resolution of the whole output field. The size of the focus is determined by the basic beam focusing lens system and not by the diffractive or refractive element. In conclusion, a highly resolved output field requires a focusing optic with high numerical aperture. For examples, it is not possible to obtain a flat-top beam profile from a Gaussian beam where focus has the same size as the flat-top should have. The steeper the sidewalls of the flat-top profile, the smaller must be the focal spot without the beam shaping element. The choice of a suitable numerical aperture of the lens system must be done before the transmission design is performed because it also determines the extent of the transmission function. The distance Δz_{in} must be chosen in such a way that ensures that the propagated input field illuminates the whole aperture of the system.

If a high numerical aperture on the output side is required to achieve a high resolution, the setup in the middle of Figure 15 should be avoided and the first setup is preferable. Otherwise the element would be illuminated by a highly nonparaxial field which violates the structure design with TEA. With the same argument, but now on the input side, an input field with high divergence should be at least partly collimated to achieve a paraxial illumination of the element. Then, the setup at the bottom of Figure 15 results.

For nonparaxial light transformation, that means the output field is large and hence the transformation requires nonparaxial deflection of the input field; the described transmission and structure design is still useful to obtain an initial design for a further optimization by wave-optical modeling techniques.

Though a Fourier approach to obtain general light transformations seems rather restricted, it covers a broad field of applications. The combination of suitable beam optics with the refractive free-form or diffractive element can be very simple (see optical setup of Figure 14) or very complex. That mainly depends on the resolution and size of the demanded output field as it is well known from imaging systems.

Each design should be finalized with a complete wave-optical analysis, typically including adjustment and fabrication error tolerancing, to achieve a full understanding of the optical properties of the system. After this final investigation it is ready for fabrication and application providing a further innovation through optics and photonics on the base of wave-optical engineering.

See also

Fourier Optics.

Further Reading

Aagedal H, Schmid M, Beth T, Teiwes S and Wyrowski F (1996) Theory of speckles in diffractive optics and its application to beam shaping. *Journal of Modern Optics* 43(7): 1409–1421.

Aagedal H, Schmid M, Egner S, Müller-Quade J, Beth T and Wyrowski F (1997) Analytical beam shaping with application to laser-diode arrays. *Journal of the Optical Society of America A* 14(7): 1549–1553.

Aagedal H, Wyrowski F and Schmid M (1997) Paraxial beamsplitting and shaping. In: Turunen J and Wyrowski F (eds) *Diffractive Optics for Industrial and Commercial Applications*, chapter 6, pp. 165–188. Berlin: Akademie Verlag.

Born M and Wolf E (1980) *Principles of Optics*, 6th edn. New York: Pergamon Press.

Bryngdahl O (1974) Optical map transformations. *Optics Communications* 10(2): 164–168.

Bühling S, Schimmel H and Wyrowski F (2003) Wave-optical engineering with virtuallab. *Proceedings SPIE*, 5182: 24–33.

Bühling S, Schimmel H and Wyrowski F (2003) Challenges in industrial applications of diffractive beam splitting. *Proceedings SPIE* 5182: 123–131.

Collier RJ, Burckhardt CB and Lin LH (1971) *Optical Holography*. London: Academic Press.

Fienup JR (1980) Iterative method applied to image reconstruction and to computer-generated holograms. *Optical Engineering* 19(3): 297–305.

Gerchberg RW and Saxton WO (1972) A practical algorithm for the determination of phase from image and diffraction plane pictures. *Optik* 35(2): 237–246.

Goodmann JW (1968) *Introduction to Fourier Optics*. New York: McGraw-Hill.

Goodman JW and Silvestri AM (1970) Some effects of Fourier-domain phase quantization. *IBM Journal of Reserved Development* 14: 478–484.

Krackhardt U, Mait JN and Streibl N (1992) Upper bound on the diffraction efficiency of phase-only fanout elements. *Applied Optics* 31(1): 27–37.

Lajunen H, Tervo J, Turunen J, Vallius T and Wyrowski F (2003) Simulation of light propagation by local spherical interface approximation. *Applied Optics* 34: 6804–6810.

Mandel L and Wolf E (1995) *Optical Coherence and Quantum Optics*. Cambridge: Cambridge University Press.

Pfeil AV and Wyrowski F (2000) Wave-optical structure design with the local plane-interface approximation. *Journal of Modern Optics* 47(13): 2335–2350.

Pfeil AV, Wyrowski F, Drauschke A and Aagedal H (2000) Analysis of optical elements with the local plane-interface approximation. *Applied Optics* 39(19): 3304–3313.

Schimmel H, Bühling S and Wyrowski F (2003) Use of ray tracing in wave-optical engineering. *Proceedings SPIE* 5182: 6–14.

Schimmel H and Wyrowski F (2000) Amplitude matching strategy for wave-optical design of monofunctional systems. *Journal of Modern Optics* 47(13): 2295–2321.

Sergienko N, Stamnes JJ, Kettunen V, Kuittinen M, Turunen J, Vahimaa P and Friberg AT (1999) Comparison of electromagnetic and scalar methods for evaluation of diffractive lenses. *Journal of Modern Optics* 46(1): 65–82.

Smith WJ (1997) *Practical Optical System Layout*. New York: McGraw-Hill.

Smith WJ (2000) *Modern Optical Engineering*, 3rd edn. Bellingham: SPIE Press.

Turunen J (1997) Diffraction theory of microrelief gratings. In: Herzig HP (ed.) *Micro-Optics Elements, Systems and Applications*, chapter 2, pp. 31–52. London: Taylor & Francis.

Turunen J and Wyrowski F (1997) *Diffractive Optics for Industrial and Commercial Applications*. Berlin: Akademie Verlag.

Vallius T, Jefimovs K, Kettunen V, Kuittinen M, Laakkonen P and Turunen J (2001) Design of non-paraxial array illuminators by step-transition perturbation approach. *Journal of Modern Optics* 48(12): 1869–1879.

Wyrowski F (1990) Diffractive optical elements: Iterative calculation of quantized, blazed phase structures. *Journal of the Optical Society of America A* 7: 961–969.

Wyrowski F (1991) Digital phase encoded inverse filter for optical pattern recognition. *Applied Optics* 30: 4650–4657.

Wyrowski F (1991) Considerations on convolution and phase factors. *Optics Communications* 81(6): 353–358.

Wyrowski F (1991) Upper bound of the diffraction efficiency of diffractive phase elements. *Optics Letters* 16(24): 1915–1917.

Wyrowski F (1993) Design theory of diffraction elements in the paraxial domain. *Journal of the Optical Society of America A* 10: 1553–1561.

Wyrowski F (2003) Comments on wave-optical engineering. *Proceedings SPIE* 5182: 1–5.

Wyrowski F and Turunen J (2002) Wave-optical engineering. In: Guenther AH (ed.) *International Trends in Applied Optics*, chapter 21, pp. 471–496. Bellingham: SPIE Press.

DISPERSION MANAGEMENT

A E Willner, Y-W Song, J Mcgeehan and Z Pan, University of Southern California, Los Angeles, CA, USA

B Hoanca, University of Alaska Anchorage, Anchorage, AK, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical communications systems have grown explosively in terms of the capacity that can be transmitted over a single optical fiber. This trend has been fueled by two complementary techniques, those being the increase in data-rate-per-channel coupled with the increase in the total number of parallel wavelength channels. However, there are many considerations as to the total number of wavelength-division-multiplexed (WDM) channels that can be accommodated in a system, including cost, information spectral efficiency, nonlinear effects, and component wavelength selectivity.

Dispersion is one of the critical roadblocks to increasing the transmission capacity of optical fiber. The dispersive effect in an optical fiber has several ingredients, including intermodal dispersion in a multimode fiber, waveguide dispersion, material dispersion, and chromatic dispersion. In particular, chromatic dispersion is one of the critical effects in a single mode fiber (SMF), resulting in a temporal spreading of an optical bit as it propagates along the fiber. At data rates ≤ 2.5 Gbit/s, the effects of chromatic dispersion are not particularly troublesome. For data rates ≥ 10 Gbit/s, however, transmission can be tricky and the chromatic dispersion-induced degrading effects must be dealt with in some way, perhaps by compensation. Furthermore, the effects of chromatic dispersion rise quite rapidly as the bit rate increases – when the bit rate increases by a factor of four, the effects of chromatic dispersion increase by a factor of 16! This article will only deal with the management of chromatic dispersion in single mode fiber.

One of the critical limitations of optical fiber communications comes from chromatic dispersion, which results in a pulse broadening as it propagates along the fiber. This occurs as photons of different frequencies (created by the spreading effect of data modulation) travel at different speeds, due to the frequency-dependent refractive index of the fiber core. Compounding the problems cause by chromatic dispersion is the fact that as bit rates rise, chromatic dispersion effects rise quadratically with respect to the increase in the bit rate. One can eliminate these effects using fiber with zero chromatic dispersion, known as dispersion shifted fiber (DSF). However, with zero dispersion, all channels in a wavelength-division-multiplexed (WDM) system travel at the same speed, in-phase, and a number of deleterious nonlinear effects such as cross-phase modulation (XPM) and four-wave mixing (FWM) result. Thus, in WDM systems, some amount of chromatic dispersion is necessary to keep channels out-of-phase, and as such chromatic dispersion compensation is required. Any real fiber link may also suffer from 'dispersion slope' effects, in which a slightly different dispersion value is produced in each WDM channel. This means that while one may be able to compensate one channel exactly, other channels may progressively accumulate increasing amounts of dispersion, which can severely limit the ultimate length of the optical link and the wavelength range that can be used in a WDM system. This article will address the concepts of chromatic dispersion and dispersion slope management followed by some examples highlighting the need for tunability to enable robust optical WDM systems in dynamic environments. Some dispersion monitoring techniques are then discussed and examples given.

Chromatic Dispersion in Optical Fiber Communication Systems

In any medium (other than vacuum) and in any waveguide structure (other than ideal infinite free space), different electromagnetic frequencies travel at different speeds. This is the essence of chromatic dispersion. As the real fiber-optic world is rather distant from the ideal concepts of both vacuum and infinite free space, dispersion will always be a concern when one is dealing with the propagation of electromagnetic radiation through fiber. The velocity in fiber of a single monochromatic wavelength is constant. However, data modulation causes a broadening of the spectrum of even the most monochromatic laser pulse. Thus, all modulated data have a nonzero spectral width which spans several wavelengths, and the different spectral components of modulated data travel at different speeds. In particular, for digital data intensity modulated on an optical carrier, chromatic dispersion leads to pulse broadening – which in turn leads to chromatic dispersion limiting the maximum data rate that can be transmitted through optical fiber (see Figure 1).

Considering that the chromatic dispersion in optical fibers is due to the frequency-dependent nature of the propagation characteristics, for both the material (the refractive index of glass) and the waveguide structure, the speed of light of a particular wavelength λ will be expressed as follows, using a Taylor series expansion of the value of the refractive index as a function of the wavelength:

$$v(\lambda) = \frac{c_0}{n(\lambda)} = \frac{c_0}{n_0(\lambda_0) + \dfrac{\partial n}{\partial \lambda}\delta\lambda + \dfrac{\partial^2 n}{\partial \lambda^2}(\delta\lambda)^2} \qquad [1]$$

Here, c_0 is the speed of light in vacuum, λ_0 is a reference wavelength, and the terms in $\partial n/\partial \lambda$ and $\partial^2 n/\partial \lambda^2$ are associated with the chromatic dispersion and the dispersion slope (i.e., the variation of the chromatic dispersion with wavelength), respectively. Transmission fiber has positive dispersion, i.e. longer wavelengths result in longer propagation delays. The units of chromatic dispersion are picoseconds per nanometer per kilometer, meaning that shorter time pulses, wider frequency spread due to data modulation, and longer fiber lengths will each contribute linearly to temporal dispersion. Higher data rates inherently have both shorter pulses and wider frequency spreads. Therefore, as network speed increases, the impact of chromatic dispersion rises precipitously as the square of the increase in data rate. The quadratic increase with the data rate is a result of two effects, each with a linear contribution. On one hand, a doubling of the data rate makes the spectrum twice as wide, doubling the effect of dispersion. On the other hand, the same doubling of the data rate makes the data pulses only half as long (hence twice as sensitive to dispersion). The combination of a wider signal spectrum and a shorter pulse width is what leads to the overall quadratic impact. Moreover, the data modulation format used can significantly affect the sensitivity of a system to chromatic dispersion. For example, the common nonreturn-to-zero (NRZ) data format, in which the optical power stays high throughout the entire time slot of a ‘1’ bit, is more robust to chromatic dispersion than is the return-to-zero (RZ) format, in which the optical power stays high in only part of the time slot of a ‘1’ bit. This difference is due to the fact that RZ data have a much wider channel frequency spectrum compared to NRZ data, thus incurring more chromatic dispersion. However, in a real WDM system, the RZ format increases the maximum allowable transmission distance by virtue of its reduced duty cycle (compared to the NRZ format), making it less susceptible to fiber nonlinearities as can be seen in Figure 2.

A rule for the maximum distance over which data can be transmitted is to consider a broadening of the pulse equal to the bit period. For a bit period B, a dispersion value D and a spectral width $\Delta\lambda$, the dispersion-limited distance is given by

$$L_D = \frac{1}{D \cdot B \cdot \Delta\lambda} = \frac{1}{D \cdot B \cdot (cB)} \propto \frac{1}{B^2} \qquad [2]$$

(see Figure 3). For example, for single mode fiber, $D = 17$ ps/nm/km, so for 10 Gbit/s data the distance is $L_D = 52$ km. In fact, a more exact calculation


(a)
Photon velocity (f)= Speed of light in a vacuum / Index of refraction (f)
Information bandwidth of data
0 1 1 0 1 0
Time
Fourier transform
v_j
v_i
v_k
v = velocity
f_Carrier
freq.
(b)
Temporal pulse spreading → F [distance, (bit rate)^2] → ps/nm / km
Time
(c)

Figure 1 The origin of chromatic dispersion in data transmission. (a) Chromatic dispersion is caused by the frequency-dependent refractive index in fiber. (b) The nonzero spectral width due to data modulation. (c) Dispersion leads to pulse broadening, proportional to the transmission distance and the data rate.



Figure 2 Performances of RZ and NRZ formats in a real fiber transmission link. (Reproduced with permission from Hayee I and Willner AE (1999) NRZ versus RZ in 10–40-Gb/s dispersion-managed WDM transmission systems. *IEEE Photon. Tech. Lett.* 11(8): 991–993.)



Figure 3 Transmission distance limitations due to uncompensated dispersion in SMF as a function of data rate for intensity modulated optical signals. (Reproduced with permission from Garrett LD (2001) Invited Short Course, *Optical Fiber Communication Conference.*)

shows that for 60 km, the dispersion induced power penalty is less than 1 dB (see Figure 4). The power penalty for uncompensated dispersion rises exponentially with transmission distance, and thus to maintain good signal quality, dispersion compensation is required.

Chromatic Dispersion Management

Optical Nonlinearities as Factors to be Considered in Dispersion Compensation

Even though it is possible to manufacture fiber with zero dispersion, it is not practical to use such fiber for WDM transmission, due to large penalties induced by fiber nonlinearities. Most nonlinear effects originate from the nonlinear refractive index of fiber, which is not only dependent on the frequency of light but also on the intensity (optical power), and is related to the optical power as:

$$\bar{n}(f, P) = n(f) + n_2 \frac{P}{A_{\text{eff}}} \qquad [3]$$

where $n(f)$ is the linear part of the refractive index, P is the optical power inside the fiber, and n_2 is the nonlinear-index coefficient for silica fibers. The typical value of n_2 is 2.6×10^{-20} m^2/W. This number takes into account the averaging of the polarization states of the light as it travels in the fiber. The intensity dependence of the refractive index gives rise to three major nonlinear effects.



Figure 4 Power penalties due to uncompensated dispersion in single mode fiber (SMF) as a function of distance and data rate. (Reproduced with permission from Garrett LD (2001) Invited Short Course, *Optical Fiber Communication Conference.*)

Self-phase modulation (SPM)

A million photons ‘see’ a different glass than does a single photon, and a photon traveling along with many other photons will slow down. SPM occurs because of the varying intensity profile of an optical pulse on a single WDM channel. This intensity profile causes a refractive index profile and, thus, a photon speed differential. The resulting phase change for light propagating in an optical fiber is expressed as:

$$\Phi_{\text{NL}} = \gamma P L_{\text{eff}} \qquad [4]$$

where the quantities γ and L_{eff} are defined as:

$$\gamma = \frac{2\pi n_2}{\lambda A_{\text{eff}}} \text{ and } L_{\text{eff}} = \frac{1 - e^{-\alpha L}}{\alpha} \qquad [5]$$

where A_{eff} is the effective mode area of the fiber and α is the fiber attenuation loss. L_{eff} is the effective nonlinear length of the fiber that accounts for fiber loss, and γ is the nonlinear coefficient measured in rad/km/W. A typical range of values for γ is between 10–30 rad/km/W. Although the nonlinear coefficient is small, the long transmission lengths and high optical powers, that have been made possible by the use of optical amplifiers, can cause a large enough nonlinear phase change to play a significant role in state-of-the-art lightwave systems.

Cross-phase modulation (XPM)

When considering many WDM channels co-propagating in a fiber, photons from channels 2 through N can distort the index profile that is experienced by channel 1. The photons from the other channels 'chirp' the signal frequencies on channel 1, which will interact with fiber chromatic dispersion and cause temporal distortion. This effect is called cross-phase modulation. In a two-channel system, the frequency chirp in channel 1, due to power fluctuation within both channels, is given by

$$\Delta B = \frac{\mathrm{d}\Phi_{\mathrm{NL}}}{\mathrm{d}t} = \gamma L_{\mathrm{eff}}\frac{\mathrm{d}P_1}{\mathrm{d}t} + 2\gamma L_{\mathrm{eff}}\frac{\mathrm{d}P_2}{\mathrm{d}t} \qquad [6]$$

where, $\mathrm{d}P_1/\mathrm{d}t$ and $\mathrm{d}P_2/\mathrm{d}t$ are the time derivatives of the pulse powers of channels 1 and 2, respectively. The first term on the right-hand side of the above equation is due to SPM, and the second term is due to XPM. Note that the XPM-induced chirp term is double that of the SPM-induced chirp term. As such, XPM can impose a much greater limitation on WDM systems than can SPM, especially in systems with many WDM channels.

Four-wave-mixing (FWM)

The optical intensity propagating through the fiber is related to the electric field intensity squared. In a WDM system, the total electric field is the sum of the electric fields of each individual channel. When squaring the sum of different fields, products emerge that are beat terms at various sum and difference frequencies to the original signals. Figure 5 depicts that if a WDM channel exists at one of the four-wave-mixing beat-term frequencies, then the beat term will interfere coherently with this other WDM channel and potentially destroy the data.

Dispersion Maps

While zero-dispersion fiber is not a good idea, a large value of the accumulated dispersion at the end of a fiber link is also undesirable. An ideal solution is to have a 'dispersion map,' alternating sections of positive and negative dispersion as can be seen in Figure 6. This is a very powerful concept: at each point along the fiber the dispersion has some nonzero value, eliminating FWM and XPM, but the total dispersion at the end of the fiber link is zero, so that no pulse broadening is induced (Table 1). The most advanced systems require periodic dispersion compensation, as well as pre- and post-compensation (before and after the transmission fiber).

The addition of negative dispersion to a standard fiber link has been traditionally known as 'dispersion compensation,' however, the term 'dispersion management' is more appropriate. SMF has positive dispersion, but some new varieties of nonzero dispersion-shifted fiber (NZDSF) come in both positive and negative dispersion varieties. Some examples are shown in Figure 7. Reverse dispersion fiber is also now available, with a large dispersion



(b) Degradation on optical spectrum (Unequal channel spacing)

(c) Degradation on bit stream (equal channel spacing)



Figure 5 (a) and (b) FWM induces new spectral components via nonlinear mixing of two wavelength signals. (c) The signal degradation due to FWM products falling on a third data channel can be reduced by even small amounts of dispersion. (Reproduced with permission from Tkach RW, Chraplyvy AR, Forghieri F, Gnauck AH and Derosier RM (1995) Four-photon mixing and high-speed WDM systems. *Journal of Photon Technology* 13(5): 841–849.)

comparable to that of SMF, but with the opposite sign. When such flexibility is available in choosing both the magnitude and sign of the dispersion of the fiber in a link, dispersion-managed systems can be fully optimized to the desired dispersion map using a combination of fiber and dispersion compensation devices (see Figure 8).

Dispersion is a linear process, so first-order dispersion maps can be understood as linear systems. However, the effects of nonlinearities cannot be ignored, especially in WDM systems, with many tens of channels, where the launch power may be very high. In particular, in systems deploying dispersion compensating fiber (DCF), the large nonlinear coefficient of the DCF can dramatically affect the dispersion map.

Corrections to Linear Dispersion Maps

Chromatic dispersion is a necessity in WDM systems, to minimize the effects of fiber nonlinearities. A chromatic dispersion value as small as a few ps/nm/km is usually sufficient to make XPM and FWM negligible. To mitigate the effects of nonlinearities but maintain small amounts of chromatic dispersion, NZDSF is commercially available. Due to these nonlinear effects, chromatic dispersion must be managed, rather than eliminated.


Positive dispersion transmission fiber
Negative dispersion element
–D
–D
–D
Accumulated dispersion (ps/nm)
D_total = 0
+D
–D
+D
–D
+D
–D
Distance (km)

Figure 6 Dispersion map of a basic dispersion managed system. Positive dispersion transmission fiber alternates with negative dispersion compensation elements such that the total dispersion is zero end-to-end.

If a dispersion-management system was perfectly linear, it would be irrelevant whether the dispersion along a path is small or large, as long as the overall dispersion is compensated to zero (end to end). Thus, in a linear system the performance should be similar, regardless of whether the transmission fiber is SMF, and dispersion compensation modules are deployed every 60 km, or the transmission fiber is NZDSF (with approximately a quarter of the dispersion value of SMF) and dispersion compensation modules are deployed every 240 km. In real life, optical nonlinearities are very important, and recent results seem to favor the use of large, SMF-like, dispersion values in the transmission path and correspondingly high dispersion compensation devices. A recent study of performance versus channel spacing showed that the capacity of SMF could be more than four times that of NZDSF. This is because the nonlinear coefficients are much higher in NZDSF than in SMF, and for dense WDM the channel interactions become a limiting factor. A critical conclusion is that not all dispersion compensation maps are created equal: a simple calculation of the dispersion compensation, to cancel the overall dispersion value, does not lead to optimal dispersion map designs.



Figure 7 Chromatic dispersion characteristics of various commercially available types of transmission fiber.

Table 1 Commercially available fibers and their characteristics

	Dispersion @ 1,550 nm [ps/nm/km]	*Dispersion slope [ps/nm^2/km]*	*Attenuation [dB]*	*Mode field diameter [μm]*	*PMD [ps/km$^{0.5}$]*
SMF	18	0.08	$\leq$0.25	11	$\leq$0.5
Tera Light	8.0	0.058	$\leq$0.2	9.2	$\leq$0.04
TW-RS	4.4	0.043	$\leq$0.25	8.4	$\leq$0.03
LEAF	4.0	0.085	$\leq$0.25	9.6	$\leq$0.08
Standard DCF	−90	−0.22	$\leq$0.5	5.2	$\leq$0.08


SMF + DCF
+D
0
Distance (km)
100
200
300
1. High local dispersion: (D≥17)
High SPM, Low XPM, Low FWM
2. Short compensation distance
Nonzero DSF + SMF
0
−D
Distance (km)
1,000
2,000
3,000
1. Low local dispersion: (D ~ ±0.2)
Low SPM, Suppressed XPM,
Suppressed FWM
2. Long compensation distance
Dispersion values (in ps/nm/km):
SMF: ~ +17, DCF: ~ −85, Nonzero DSF: ~ ±0.2

Figure 8 Various dispersion maps for SMF-DCF and NZDSF-SMF.

Additionally, several solutions have been shown to be either resistant to dispersion, or have been shown to rely on dispersion itself for transmission. Such solutions include chirped pulses (where prechirping emphasizes the spectrum of the pulses so that dispersion does not broaden them too much), dispersion assisted transmission (where an initial phase modulation tailored to the transmission distance leads to full-scale amplitude modulation at the receiver end due to the dispersion), and various modulation formats robust to chromatic dispersion and nonlinearities.

Dispersion Management Solutions

Fixed Dispersion Compensation

From a systems point of view, there are several requirements for a dispersion compensating module: low loss, low optical nonlinearity, broadband (or multichannel) operation, small footprint, low weight, low power consumption, and clearly low cost. It is unfortunate that the first dispersion compensation modules, based on DCF only, met two of these requirements: broadband operation and low power consumption. On the other hand, several solutions have emerged that can complement or even replace these first-generation compensators.

Dispersion compensating fiber (DCF)

One of the first dispersion compensation techniques was to deploy specially designed sections of fiber with negative chromatic dispersion. The technology for DCF emerged in the 1980s and has developed dramatically since the advent of optical amplifiers in 1990. DCF is the most widely deployed dispersion compensator, providing broadband operation and stable dispersion characteristics, and the lack of a dynamic, tunable DCF solution has not reduced its popularity.

As can be seen in Figure 9, the core of the average dispersion compensating fiber is much smaller than that of standard SMF, and beams with longer wavelengths experience relatively large changes in mode size (due to the waveguide structure) leading to greater propagation through the cladding of the fiber, where the speed of light is greater than that of the core. This leads to a large negative dispersion value. Additional cladding layers can lead to improved DCF designs that can include negative dispersion slope to counteract the positive dispersion slope of standard SMF.

In spite of its many advantages, DCF has a number of drawbacks. First, it is limited to a fixed compensation value. In addition, DCF has a weakly guiding structure and has a much smaller core cross-section, 19 μm^2, compared to the 85 μm^2 of SMF. This leads to higher nonlinearity, higher splice losses, as well as higher bending losses. Last, the length of DCF required to compensate for SMF dispersion is rather long, about one-fifth of the length of the transmission fiber for which it is compensating. Thus DCF modules induce loss, and are relatively bulky and heavy. The bulk is partly due to the mass of fiber, but also due to the resin used to hold the fiber securely in place. One other contribution to the size of the module is the higher bend loss associated with the refractive index profile of DCF; this limits the radius of the DCF loop to 6–8 inches, compared to the minimum bend radius of 2 inches for SMF.

Traditionally, DCF-based dispersion compensation modules are usually located at amplifier sites. This serves several purposes. First, amplifier sites offer relatively easy access to the fiber, without requiring any digging or unbraiding of the cable. Second, DCF has high loss (usually at least double that of standard SMF), so a gain stage is required



Figure 9 Typical DCF (a) refractive index profile and (b) dispersion and loss as a function of wavelength. Δ*n* is defined as refractive index variation relative to the cladding.


Experimental setup
1.5 µm transmatters
1
60 km
Standard fiber lines
L = 0.275 dB/km
D = +17.5 ps/nm km
2
DCF
3
4
DCF
5
Rx
7
DCF
6
Total loss: 100 dB including connectors
Total dispersion: ~6,300 ps/nm
System performance
2 × 10 Gb/s, 2^23-1 PRBS NRZ
× Back-to-back SNR > 40 dB
● 1,558 nm channel SNR > 25.75 dB
▲ 1,552 nm channel SNR > 25.25 dB
Bit error rate
−4
−5
−6
−7
−8
−9
−10
−11
−12
−13
−14
Error-free for 5 days
−14 −13 −12 −11 −10 −9 −8 −7
Received power (dBm)

Figure 10 System demonstration of dispersion compensation using DCF. (Reproduced with permission from Park YK, Yeates PD, Delavaux J-MP, *et al.* (1995) A field demonstration of 20-Gb/s capacity transmission over 360 km of installed standard (non-DSF) fiber. *Photon. Technol. Lett.* 7(7): 816–818.)

before the DCF module to avoid excessively low signal levels. DCF has a cross-section four times smaller then SMF, hence a higher nonlinearity, which limits the maximum launch power into a DCF module. The compromise is to place the DCF in the mid-section of a two-section EDFA. This way, the first stage provides pre-DCF gain, but not to a power level that would generate excessive nonlinear effects in the DCF. The second stage amplifies the dispersion compensated signal to a power level suitable for transmission though the fiber link. This launch power level is typically much higher than could be transmitted through DCF without generating large nonlinear effects. Many newer dispersion compensation devices have better performance than DCF, in particular lower loss and lower nonlinearities. For this reason, they may not have to be deployed at the mid-section of an amplifier. Figure 10 shows the real demonstration results using the DCF.

Chirped fiber Bragg gratings

Fiber Bragg gratings have emerged as major components for dispersion compensation because of their low loss, small footprint, and low optical nonlinearity. Bragg gratings are sections of single-mode fiber in which the refractive index of the core is modulated in a periodic fashion, as a function of the spatial coordinate along the length of the fiber. When the spatial periodicity of the modulation matches what is known as a Bragg condition with respect to the wavelength of light propagating through the grating, the periodic structure acts like a mirror, reflecting the optical radiation that is traveling through the core of the fiber. An optical circulator is traditionally used to separate the reflected output beam from the input beam.

When the periodicity of the grating is varied along its length, the result is a chirped grating which can be used to compensate for chromatic dispersion. The chirp is understood as the rate of change of the spatial frequency as a function of position along the grating. In chirped gratings the Bragg matching condition for different wavelengths occurs at different positions along the grating length. Thus, the roundtrip delay of each wavelength can be tailored by designing the chirp profile appropriately. Figure 11 compares the chirped FBG with uniform FBG. In a data pulse that has been distorted by dispersion, different frequency components arrive with different amounts of relative delay. By tailoring the chirp profile such that the frequency components see a relative delay which is the inverse of the delay of the transmission fiber, the pulse can be compressed back. The dispersion of the grating is the slope of the time delay as a function of wavelength, which is related to the chirp.

The main drawback of Bragg gratings is that the amplitude profile and the phase profile as a function of wavelength have some amount of ripple. Ideally, the amplitude profile of the grating should have a flat (or rounded) top in the passband, and the phase profile should be linear (for linearly chirped gratings) or polynomial (for nonlinearly chirped gratings). The grating ripple is the deviation from the ideal profile shape. Considerable effort has been expended on reducing the ripple. While early gratings were plagued by more than 100 ps of ripple, published results have shown vast improvement to values close to ±3 ps.

Higher order mode dispersion compensation fiber

One of the challenges of designing standard DCF is that high negative dispersion is hard to achieve unless the cross-section of the fiber is small (which leads to high nonlinearity and high loss). One way to reduce both the loss and the nonlinearity is to use a higher-order mode (HOM) fiber (LP_{11} or LP_{02} near cutoff instead of the LP_{01} mode in the transmission fiber).



Figure 11 Uniform and chirped FBGs. (a) A grating with uniform pitch has a narrow reflection spectrum and a flat time delay as a function of wavelength. (b) A chirped FBG has a wider bandwidth, a varying time delay and a longer grating length.

Such a device requires a good-quality mode converter between LP_{01} and LP_{02} to interface between the SMF and HOM fiber. HOM fiber has a dispersion per unit length greater than six times that of DCF. Thus, to compensate for a given transmission length in SMF, the length of HOM fiber required is only one sixth the length of DCF. Thus, even though losses and nonlinearity per unit length are larger for HOM fiber than for DCF, they are smaller overall, because of the shorter HOM fiber length. As an added bonus, the dispersion can be tuned slightly by changing the cutoff wavelength of LP_{02} (via temperature tuning). A soon to be released HOM fiber-based commercial dispersion compensation module is not tunable, but can fully compensate for dispersion slope.

Tunable Dispersion Compensation

The need for tunability

In a perfect world, all fiber links would have a known, discrete, and unchanging value of chromatic dispersion. Network operators would then deploy fixed dispersion compensators periodically along every fiber link to exactly match the fiber dispersion. Unfortunately, several vexing issues may necessitate that dispersion compensators are tunability, that they have the ability to adjust the amount of dispersion to match system requirements.

First, there is the most basic business issue of inventory management. Network operators typically do not know the exact length of a deployed fiber link nor its chromatic dispersion value. Moreover, fiber plants periodically undergo upgrades and maintenance, leaving new and nonexact lengths of fiber behind. Therefore, operators would need to keep in stock a large number of different compensator models, and even then the compensation would only be approximate. Second, we must consider the sheer difficulty of 40 Gbit/s signals. The tolerable threshold for accumulated dispersion for a 40 Gbit/s data channel is 16 times smaller than at 10 Gbit/s. If the compensation value does not exactly match the fiber to within a few percent of the required dispersion value, then the communication link will not work. Tunability is considered a key enabler for this bit rate (see Figures 12 and 13). Third, the accumulated dispersion changes slightly with temperature, which begins to be an issue for 40 Gbit/s systems and 10 Gbit/s ultra long-haul systems. In fiber, the zero-dispersion wavelength changes with temperature at a


Accumulated chromatic dispersion
Partial compensation
SMF
DCF
OC-192 limit
OC-768 limit
Perfect compensation
Distance (km)

Figure 12 The need for tunability. The tolerance of OC-768 systems to chromatic dispersion is 16 times lower than that of OC-192 systems. Approximate compensation by fixed in-line dispersion compensators for a single channel may lead to rapid accumulation of unacceptable levels of residual chromatic dispersion.



Figure 13 Tunable dispersion compensation at OC-768 (40 Gb/s) is essential for achieving a comfortable range of acceptable transmission distances (80 km for tunable, only ~4 km for fixed compensation).

typical rate of 0.03 nm/°C. It can been shown that a not-uncommon 50 °C variation along a 1,000 km 40 Gbit/s link can produce significant degradation (see Figure 14). Fourth, we are experiencing the dawn of reconfigurable optical networking. In such systems, the network path, and therefore the accumulated fiber dispersion, can change. It is important to note that even if the fiber spans are compensated span-by-span, the pervasive use of compensation at the transmitter and receiver suggests that optimization and tunability based on path will still be needed.

Other issues that increase the need for tunability include: (i) laser and (de)mux wavelength drifts for which a data channel no longer resides on the flat-top portion of a filter, thereby producing a chirp on the signal that interacts with the fiber's chromatic dispersion; (ii) changes in signal power that change both the link's nonlinearity and the optimal system dispersion map; and (iii) small differences that exist in transmitter-induced signal chirp.



Figure 14 Accumulated dispersion changes as a function of the link length and temperature fluctuation along the fiber link.


f1
f3
Incident
f1
f2
f3
Chirped FBG
Reflected
External Mechanical Stretcher
No slope change at λ0
Stretch
Relative time delay (ps)
λ0
λ(nm)
Linearly chirped
Slope change at λ0
Stretch
Relative time delay (ps)
λ0
λ(nm)
Nonlinearly chirped

Figure 15 Tuning results for both linearly and nonlinearly chirped FBGs using uniform stretching elements. The slope of the dispersion curve at a given wavelength λ_0 is constant when the linearly chirped grating is stretched, but changes as the nonlinearly chirped grating is stretched.

Approaches to tunable dispersion compensation

A host of techniques for tunable dispersion compensation have been proposed in recent years. Some of these ideas are just interesting research ideas, but several have strong potential to become viable technologies.

Fiber gratings offer the inherent advantages of fiber compatibility, low loss, and low cost. If a FBG has a refractive-index periodicity that varies nonlinearly along the length of the fiber, it will produce a time delay that also varies nonlinearly with wavelength (see Figure 15). Herein lies the key to tunability. When a linearly chirped grating is stretched uniformly by a single mechanical element, the time delay curve is shifted towards longer wavelengths, but the slope of the ps-vs.-nm curve remains constant at all wavelengths within the passband. When a nonlinearly-chirped grating is stretched, the time delay curve is shifted toward longer wavelengths, but the slope of the ps-vs.-nm curve at a specific channel wavelength changes continuously. Ultimately, tunable dispersion compensators should accommodate multichannel operation. Several WDM channels can be accommodated by a single chirped FBG in one of two ways: fabricating a much longer (i.e., meters-length) grating, or using a sampling function when writing the grating, thereby creating many replicas of transfer function of the FBG in the wavelength domain (see Figure 16).

One free-space-based tunable dispersion compensation device is the virtually imaged phased array (VIPA), based on the dispersion of a Fabry–Perot interferometer. The design requires several lenses, a movable mirror (for tunability), and a glass plate with a thin film layer of tapered reflectivity for good mode matching. Light incident on the glass plate undergoes several reflections inside the plate. As a result, the beam is imaged at several virtual locations, with a spatial distribution that is wavelength-dependent.



Figure 16 The concept of 'sampled' FBGs, where a superstructure is written on top of the grating that produces a Fourier transform in the frequency domain, leading to multiple grating passbands.

Several devices used for dispersion compensation can be integrated on a chip, using either an optical chip media (semiconductor-based laser or amplifier medium) or an electronic chip. One such technology is the micro-ring resonator, a device that, when used in a structure similar to that of an all-pass filter (see Figure 17), can be used for dispersion compensation on a chip-scale. Although these technologies are not yet ready for deployment as dispersion compensators, they have been used in other applications and have the potential to offer very high performance at low cost.

As the ultimate optical dispersion compensation devices, photonic bandgap fibers (holey fibers) are an interesting class in themselves (see Figure 18). These are fibers with a hollow structure, with holes engineered to achieve a particular functionality. Instead of being drawn from a solid preform, holey fibers are drawn from a group of capillary tubes fused together. This way, the dispersion, dispersion slope, the nonlinear coefficients could in principle all be precisely designed and controlled, up to very small or very large values, well outside the range of those of the solid fiber.



Figure 17 Architecture of an all-pass filter structure for chromatic dispersion and slope compensation. (Reproduced with permission from Madsen CK, Lenz G, Bruce AJ, *et al.* (1999) Integrated all-pass filters for tunable dispersion and dispersion slope compensation. *Photon. Technol. Lett.* 11(12): 1623–1625.)



Figure 18 (a) SEM image of a photonic crystal fiber (holey fiber), and (b) net dispersion of the fiber at 1550 nm as a function of the core diameter. (Reproduced with permission from Birk TA, Mogihetsev D, Knight JC and Russell PSt.J (1999) Integrated all-pass filters for tunable dispersion and dispersion slope compensation. *Photon. Technol. Lett.* 11(6): 674–676.)

Dispersion Slope Mismatch

Transmission fiber, especially fiber with dispersion compensation built in, may suffer from a dispersion slope in which a slightly different dispersion value is produced for each WDM channel (see Figure 19). Even though the compensator would be able to cancel the dispersion of the fiber at the design wavelength, there will be residual dispersion left at the other wavelength channels unless the compensator can match the slope of the dispersion curve of the fiber as well. Some solutions for dispersion slope compensation are described in this section.

First, DCF, with negative dispersion slope, is a prime candidate for deployment as a dispersion slope compensator even though it cannot easily be made tunable. By designing the DCF with the same ratio of dispersion to dispersion slope as that of a real fiber link, new types of DCF can be used to compensate for both dispersion and dispersion slope, much like DCF is used for dispersion compensation today. DCF's popularity, wideband functionality, and stable dispersion characteristics make this a particularly attractive solution. Designing the DCF to match the dispersion characteristics of the transmission fiber is the critical engineering challenge in this slope compensation scheme. Second, third-order nonlinearly chirped FBG can act as a tunable dispersion slope compensator. A simple modification of the nonlinearly chirped FBG allows tuning of the compensated dispersion slope value via stretching the grating. The grating is prepared such that the time delay as a function of wavelength has a cubic profile that covers several WDM channels over a continuous bandwidth of many nanometers. Since the resulting dispersion curve is quadratic over the grating bandwidth, the dispersion slope experienced by the WDM channels can be tuned by stretching the grating using a single mechanical element (see Figure 20). Third, combining the VIPA, with either a 3D mirror or diffraction grating, can also provide tunable free-space dispersion slope compensation. Slope tuning is achieved by dynamically controlling the MEMS-based 3D mirror or the diffraction grating. Fourthly, using an FBG with many spaced thin-film heater sections can also enable tunable dispersion slope. Each heater can be individually electrically controlled, allowing the time delay profile of the grating to be dynamically tuned via changing the temperature along the length of the grating. Advanced applications of this technique can allow alterations to the entire time delay profile of the grating, providing a truly flexible dispersion and dispersion slope compensation mechanism.



Figure 19 The chromatic dispersion slope mismatch caused by the different slopes of transmission fiber (SMF or NZDSF) and DCF.

Chromatic Dispersion Monitoring

Another important issue related to dispersion management is dispersion monitoring techniques. In a reconfigurable system, it is necessary to reconfigure



Figure 20 Tunable dispersion slope compensation using a third-order nonlinearly chirped FBG. (a) Cubic time delay curves of the grating, and (b) quadratic dispersion curves showing the change in dispersion in each channel before and after tuning. (Reproduced with permission from Song YW, Motoghian SMR, Starodubov D, *et al.* (2002) Tunable dispersion slope compensation for WDM systems using a non-channelized third-order-chirped FBG. *Optical Fiber Communication Conference* 2002. Paper ThAA4.)

any tunable chromatic dispersion compensation modules on the fly as the network changes. An in-line chromatic dispersion monitor can quickly measure the required dispersion compensation value while data are still being transmitted through the optical link. This is very different from the more traditional chromatic dispersion measurement techniques where dark fiber is used and the measurement is done off-line over many hours (or days).

Chromatic dispersion monitoring is most often done at the receiving end, where the Q-factor of the received data or some other means is employed to assess the accumulated dispersion. Existing techniques that can monitor dispersion in-line, fast, and with relatively low cost include: (i) general performance monitoring using the bit-error rate (BER) or eye opening, but this approach cannot differentiate among different degrading effects; (ii) detecting the intensity modulation induced by phase modulation at the transmitter; (iii) extracting the bit-rate frequency component (clock) from photo-detected data and monitoring its RF power (see Figure 21); (iv) inserting a subcarrier at the transmitter and subsequently monitoring the sub-carrier power degradation; (v) extracting several frequency components from the optical data using very narrow-band optical filters and detecting the optical phase; (vi) dithering the optical-carrier frequency at the transmitter and measuring the resultant phase modulation of the clock extracted at receiver with an additional phase-locked loop; and (vii) using an optical filter to select the upper and lower vestigial sideband (VSB) signals in transmitted optical data and determine the relative group delay caused by dispersion (see Figure 22).



Figure 21 Clock regenerating effect due to chromatic dispersion for NRZ data. As the amount of residual dispersion increases, so does the amount of power at the clock frequency. This power can be used to monitor the amount of uncompensated chromatic dispersion. (Reproduced with permission from Pan Z, Yu Q, Xie Y, *et al.* (2001) Chromatic dispersion monitoring and automated compensation for NRZ and RZ data using clock regeneration and fading without adding signalling. *Optical Fiber Communication Conference 2001.* Paper WH5.)

Conclusion

Chromatic dispersion is a phenomenon with profound implications for optical fiber communications systems. It has negative effects, broadening data pulses, but it also helps reduce the effects of fiber nonlinearities. For this reason, managing dispersion, rather than trying to eliminate it altogether, is the key. Fixed dispersion components are suitable for point-to-point OC-192 systems. Tunable dispersion components are essential for dispersion management in reconfigurable and OC-768 systems. These dispersion compensation elements must have low loss, low nonlinearity, and must be cost effective.



Clock phase shift = $2\pi \times R_b \times$ (Time delay) = f(dispersion)

Figure 22 Chromatic dispersion monitoring using the time delay (Δt) between two VSB signals, which is a function of chromatic dispersion. (Reproduced with permission from Yu Q, Yan L-S, Pan Z and Willner AE (2002) Chromatic dispersion monitor for WDM systems using vestigial-sideband optical filtering. *Optical Fiber Communication Conference 2002.* Paper WE3.)

Although several technologies have emerged that meet some or all of the above requirements, no technology is a clear winner. The trend is towards tunable devices, or even actively self-tunable compensators, and such devices will allow system designers to cope with the shrinking system margins and with the emerging rapidly reconfigurable optical networks.

List of Units and Nomenclature

Chromatic dispersion	The time-domain pulse broadening in an optical fiber caused by the frequency dependence of the refractive index. This results in photons at different frequencies traveling at different speeds [ps/nm/km].
Chromatic dispersion slope	Different wavelengths have different amounts of dispersion values in an optical fiber [$\text{ps/nm}^2\text{/km}$].
Conventional single mode fiber (SMF)	Fiber that transmits only a single optical mode by virtue of a very small core diameter relative to the cladding. Provides lowest loss in the 1,550 nm region and has zero dispersion at 1,300 nm.
Cross-phase modulation (XPM)	A nonlinear Kerr effect in which a signal undergoes a nonlinear phase shift induced by a copropagating signal at a different wavelength in a WDM system.
Dispersion compensating fiber (DCF)	Optical fiber that has both a large negative dispersion and dispersion slope around 1,550 nm.
Fiber Bragg gratings (FBGs)	A small section of optical fiber in which there is a periodic change of refractive index along the core of the fiber. An FBG acts as a wavelength-selective mirror, reflecting only specific wavelengths (Bragg wavelengths) and passing others.
Four-wave mixing (FWM)	A nonlinear Kerr effect in which two or more signal wavelengths interact to generate a new wavelength.
Kerr effect	Nonlinear effect in which the refractive index of optical fiber varies as a function of the intensity of light within the fiber core.
Modulation	The process of encoding digital data onto an optical signal so it can be transmitted through an optical network.
Nonlinear effects	Describes the nonlinear responses of a dielectric to intense electromagnetic fields. One such effect is the intensity dependence of the refractive index of an optical fiber (Kerr effect).
Nonzero dispersion-shifted fiber (NZDSF)	Optical fiber that has a small amount of dispersion in the 1,550 nm region in order to reduce deleterious nonlinear effects.
Polarization mode dispersion (PMD)	Dispersion resulting from the fact that different light polarizations within the fiber core will travel at different speeds through the optical fiber [$\text{ps/km}^{0.5}$].
Self-phase modulation (SPM)	A nonlinear Kerr effect in which a signal undergoes a self-induced phase shift during propagation in optical fiber.
Wavelength division multiplexing (WDM)	Transmitting many different wavelengths down the same optical fiber at the same time in order to increase the amount of information that can be carried.

See also

Nonlinear Optics, Basics: Four-Wave Mixing. **Photonic Crystals:** Nonlinear Optics in Photonic Crystal Fibers.

Further Reading

Agrawal GP (1997) *Fiber-Optic Communication Systems*. Rochester, NY: John Wiley & Sons.

Agrawal GP (1997) *Nonlinear Fiber Optics*, 2nd edn. Academic Press.

Gowar J (1993) *Optical Communication Systems*, 2nd edn. Prentice Hall.

Kaminow IP and Koch TL (1997) *Optical Fiber Telecommunications IIIA & IIIB*. Academic Press.

Kashyap R (1999) *Fiber Bragg Gratings*. Academic Press.

Kazovsky L, Benedetto S and Willner A (1996) *Optical Fiber Communication Systems*. Artech House.

Willner AE and Hoanca B (2002) Fixed and tunable management of fiber chromatic dispersion. In: Kaminow IP and Li T (eds) *Optical Fiber Telecommunications IV*. Academic Press.

Yariv A and Yeh P (1984) *Optical Waves in Crystals*. John Wiley & Sons.

DISPLAYS

R L Donofrio, Display Device Consultants LLC, Ann Arbor, MI, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

This article is a brief review of display technology being used today. It emphasizes some of the optical aspects of displays. The details of the basic construction of the display devices are also discussed to aid in understanding. The displays covered are the CRT, VFD, FED, PDP, LED, OLED, LCD-AMLCD, transmissive and transflective LCDs.

Definition of a Display

A display can be defined as an object which transfers information to the viewer and/or an output unit that gives a visual representation of data.

Optical Characteristics of a Display

A display has (in general) the optical characteristics of luminance, reflectivity, contrast ratio, color, surface gloss, resolution, and image sharpness (sometimes called small area contrast). Measurement methods can be obtained from the EIA (Electronics Industries Alliance), JT-31 (Optical Characteristics of Display Devices), SAE (Society of Automotive Engineers and ISO Standards) and VESA Standards, to name a few.

Luminance

The luminance of a display is its light output and is given in units of candela/square meter or cd/m^2 (in the English system fL). Luminance is measured using a photometer, photometer/colorimeter, or spectroradiometer.

Illuminance

The illuminance is the light incident on the surface being measured. Its units are Lumen per m^2 or Lux (and in the English system Ft.cd). This is measured using illuminance meters.

Reflectivity

The reflectivity for CRTs (cathode ray tubes) is measured with incident light at 45 degrees (in some cases for LCDs, a smaller 30 degree angle is used). The reflected light from the surface is measured with a detector normal to (perpendicular to) the surface. Devices such as 'tube face reflectivity' (TFR) can be used to measure this parameter and it is published in the EIA-JT-31 measurement methods. Other similar methods are used for flat panel displays.

Color

Although color perception is different for different individuals, standard responses to color stimuli have been developed and we can measure the color of different objects and display images. Color can be measured with such equipment as a colorimeter or spectroradiometer. The output data are given in various color systems. Color systems, such as the 1931 CIE (Commission International de I'Eclairage) Color System (x, y), the 1960 CIE (u, v) or 1976 CIE (u', v') color coordinates are all used. All these color systems can be converted to each other by simple mathematical relations and these conversions are usually available to the user in the data output. The choice of the color space/system is dependent on application but the system in most general use for displays is the 1976 CIE (u', v'). This color system has become more widely used because equally perceived color differences in this color system are at almost equal distances in this color space. In reality, the quest for a system with equal distances equating to equal color differences can be achieved through a complicated matrix approach in which the constants used in the matrix vary from point to point in the color space.

Gloss

Gloss is a measure of surface reflectivity under Snell's Law criteria (equal incidence and reflection angles). The measurement angles of 20, 45, 60, and 85 degrees are used to measure the gloss of common surfaces. Display glass surface measurements tend to use the 60 degree gloss angle. The surface of a display can be made rougher to scatter incident light away from the viewer or it can be optically coated to reduce the reflected light to achieve improved viewing. Some times both methods are used. Reduced gloss surfaces also are involved with the reduction in surface glare. The level of increased roughness of the surface affects the user's ability to see detail.

Contrast Ratio

When people talk about contrast they generally mean 'contrast ratio'. The contrast ratio (CR) of an area on a display is a unitless parameter and is defined as the excited luminance (L_e) divided by the unexcited luminance (L_u). The excited luminance (L_e) equals the glass transmission (T) times some excited internal luminance (L_{ei}) and for simplicity, L_u equals T times an internal zero ambient unexcited luminance light level of (L_{ui}). Factors, such as internal scattered light in LCDs and scattered electrons and scattered light in CRTs, give a nonzero un-excited luminance L_u.

When dealing with the CR, the effect of ambient illumination A contributes to the numerator and the denominator. Thus, when the ambient illumination is increased, it lowers the contrast ratio. In a simple case where the ambient illumination is reflected from the surface of the display whose reflectivity is ρ, the contrast ratio is given below:

$$\mathrm{CR} = (L_e + A\rho)/(L_u + A\rho) \qquad [1]$$

For the case of the reflectivity of a phosphor screen (reflectance R) coated panel with a glass transmission (T), the reflectivity to first approximation is

$$\rho = cRT^2 \qquad [2]$$

where c is a constant.

So we see that changes in contrast can come about through changing the display's glass panel transmission. For example, if the L_e of the white field of a CRT was 100 fL with a 90% panel glass (along with $R = 0.5$) and had a L_u of 2 fL, then the zero ambient contrast would be 50. However, with an ambient illumination of 50 Ftcd the contrast would be 4.76. Now, when we use a 50% transmission panel glass at the ambient illumination of 50 Ft.cd the CR is increased to approximately 8.39. Equations [1] and [2] show how to calculate the contrast. It should be noted that decreased panel glass transmission or the use of 'dark glass' increases contrast because the reflectivity is a 'T squared' effect and the luminance L is a function 'T'. There are second-order effects involved with the reduction of reflected light and unexcited luminance which make the equations more complicated. These second-order effects will not be covered as they are beyond the basic discussion of this article.

In comparing display CR, one must compare the displays at the same ambient illumination. Additionally, you will find that a number of flat panel display advertising reports will report the CR at zero ambient illumination. As we have shown, these CR values are the highest ones for the display. The CR for emissive displays tends to be constant over a wide range of viewing angles, whereas the contrast ratio for liquid crystal displays (LCDs) is more variable over large-angle viewing. Recent new electrode position developments, such as the 'in-plane switching' technology for active matrix liquid crystal displays (AMLCDs) has gone a long way to reduce this reduced angle-of-view effect in that type of LCD display.

Figure 1 shows how a viewer in a sport utility vehicle (SUV) would see the changes in contrast with viewing angle for two types of twisted nematic LCDs (TN-LCDs). One of the TN LCDs does not



Figure 1 A typical rectangular viewing envelope for a mid-size SUV vehicle superimposed on LCD iso-contrast plots. Left is standard TN LCD. Right, is film-compensated TN LCD. Reproduced from Smith-Gillespie R, *et al.* (2001) Design requirements for automotive entertainment displays. *Proceedings of the 8th Annual Symposium on Vehicle Displays (2001)*. Permission for reprint courtesy of the Society for Information Displays.

have the film compensation and the other does. For relative contrast appraisal, the red areas show the highest contrast regions and the blue the lowest. It is obvious that different technologies can give significant changes in viewed contrast.

Phosphor Aging

The fall off of luminance as the phosphor screen is bombarded with the electron beam is called phosphor aging. This effect is due to two main factors: (i) the thermal quenching of the phosphor luminescence (which is reversible); and (ii) a nonreversible aging due to damage to the screen components (such as phosphor, binder, and aluminum coating). It has been found that the aging (when we are using an electron beam) is a function of the number of electrons bombarding the screen. Aging models help us to understand and predict the amount of aging a tube will show after a fixed amount of time. The first aging model in 1951 was on ion bombardment and showed that:

$$I = I_0/(1 + AN) \qquad [3]$$

where I_0 is the initial luminance before aging, and I is the final luminance.

In 1961 a similar (one parameter) Model $I = I_0/(1 + CN)$ was used by Pfhanl, where C is the aging constant to half luminance and N is the number of coulombs. In 1981, a two-component model for low current aging was presented, where:

$$I = I_0/(1 + N(B/Q^D)) \qquad [4]$$

Here we have two constants B and D, and Q is the cumulated charge in number of coulombs. When $D = 0$ then the equation given above goes to the Pfhanl case.

Later, in 1996 the three-parameter model was described and in 1997 the Gaussian beam aging model was described.

Ambient Illumination and Reflection

To see the information shown on a display, the information must be spatially detected by the human eye over the reflected ambient illumination (such as room and sunlight). The ambient illumination is generally from localized or diffuse sources. As we have seen previously, the effect of diffuse illumination can be reduced through the use of neutral density filters. But, when we are dealing with very high ambient light such as that entering the canopy of a fighter aircraft then, the monochromatic information from the display can be viewed using selective spectral filters. However, for the usual computer monitor, the ‘specular reflection’ (Snell’s Law type of reflection) off the front of the display is due to a localized external light source. This reflection is reduced by methods such as anti-glare (AG) and anti-reflecting (AR) surfaces applied to the front surface of the display. A flat versus curved front surface of the display can also be a glare reduction technique. Surface roughness is used in AG surfaces to scatter a portion of the specular light away from the viewer. Surface roughness can be achieved through surface abrading, surface plastic coating, surface silicate coating, and surface acid etching to name a few methods. AR surfaces use optical interference techniques to reduce the reflected light to the viewer. In some cases, both methods are applied to a display surface. Surface gloss of the display is usually measured with a gloss meter in 60 degree gloss values but 20, 45, and 80 degree angles are also used. Resolution is measured in line pairs/mm or pixels/mm and image sharpness is associated with modulation transfer function (MTF) measurements. We should note here that resolution and image sharpness are not the same thing. High resolution is equated with the high frequency limit of the MTF measurement. Since the reduction in specular reflection through the use of surface roughness can affect the image sharpness, we see that a system of trade-offs can be developed to optimize a display for a given viewing environment. AR coatings improve glare reduction without scattering and thus give higher-resolution capability to the displays but this is usually obtained at a higher price then the AG coatings.

Types of Displays

Displays can be divided into two types; emissive and nonemissive. By emissive we mean that the display surface gives off light. In the nonemissive, the display or a small portion of the display acts as a shutter or spatial filter which also can be reflective in nature. In this nonemissive mode, the display can pass light from a source in back of or in front of the shutter (or both, as we shall see later).

Table of Emissive and Nonemissive Displays

Thus from Table 1 we see that under the title of emissive displays we have the cathode ray tube (CRT), projection CRT, vacuum fluorescent display (VFD), field emissive display (FED), electroluminescent (EL) display, light emitting diode (LED), organic light emitting diode (OLED), and plasma. These devices, which are in the realm of emissive displays, use certain types of emissive materials called

Table 1 Table of emissive and nonemissive displays

Emissive	*Nonemissive*
CRT	LCD and AMLCD
VFD	Bi-Stable LCD
FED	Digital Mirror D
EL – inorganic	LCOS (Liquid Crystal on Si)
LED	Electronic Inks
OLED	
PLASMA	

lumophors (or phosphors). The lumophors are called cathodoluminescent, photoluminescent, and electroluminescent, depending whether the excitation action was due to the interaction of the phosphor with cathode rays, photons, or low-voltage electrons. Cathodoluminescent lumophors are used in cathode ray tubes (CRTs – television tubes, monitor tubes, projection CRTs), (VFDs), and (FEDs).

EL displays can use inorganic lumophors (phosphors) or organic lumophors such as those used in OLEDs. Under photoluminescence displays, we have 'plasma displays' (plasma TV), IR-up conversion, and fluorescent lamps. In plasma displays, the excitation of the plasma in a localized region gives rise to UV photons which strike the phosphor screen in that region. In IR-up conversion, IR photons are absorbed in such a way that two IR photons can excite an electron with twice the energy of one IR photon. This then allows the use of IR lasers to create displays through the excitation of these up-conversion phosphors. In fluorescent lamps, the UV created by the excitation of Hg or Xe, strikes the special lamp phosphors (coated on the inside of the glass envelope), which become luminescent.

Under the heading of shutters we can consider LCDs which consist of AMLCDs, super twisted nematic liquid crystal displays (STN LCDs) and bistable LCDs. Another shutter type is the liquid crystal on silicon (LCOS) display and the movable digital mirror display (DMD), and the digital light processing (DLP) projecting engines. Another spatial display type is both normal and dynamic inks. A dynamic ink can be a 'polarizable' ink display in which a two shade (light/dark) ink sphere element can rotate under the presence of an electric field to show the light or dark side. Although they are very interesting, we will not cover ink displays in this article.

The shutter action is also used in some projection TV sets (or projectors) in which the LCD either transmits or reflects (such as LCOS) the light from an arc lamp. The DMD movable mirrors reflect the digital information to the lens system and the unwanted rays are reflected away from the lens to a black light capture area.

The Cathode Ray Tube (CRT)

The CRT is a display which has been in use for over 100 years (the Braun CRT tube was developed in 1898). The CRT uses a phosphor screen which is bombarded by energetic electrons and emits visible light radiation. The single electron gun CRT was used for years in early monochrome television sets and monochrome computer displays. Monochrome green, amber, and white phosphors have been used in monitor tubes. Some color selectivity can be obtained with the single electron gun using the following three methods; (i) voltage penetration phosphors, (ii) current sensitive phosphors and (iii) beam index methods. In a CRT, the penetration of the electron beam follows Hans Bethe's energy loss equation for electron penetration in solids and thus is a function of the electron energy or CRT voltage.

Hans Bethe's energy loss equation is:

$$\mathrm{d}E/\mathrm{d}x = -2\Pi \mathrm{e}^4 (N_\mathrm{e}/E)\ln(\alpha E/I) \qquad [5]$$

where: E = energy of the incident electron; x = depth of material; N_e = density of atomic electrons; I = mean excitation energy; and α = a constant.

In the voltage penetration tube, a cascaded screen is used to give a color change when the electron voltage is increased. For example, if a cascade screen is made from a green phosphor layer placed on top of the red phosphor layer then the electrons strike the green phosphor first. Then with increased voltage, the electrons pass through the top phosphor and excite the bottom red phosphor. In the current sensitive color tube, the phosphor screen is composed of (for example) red and green phosphor whose luminance versus current curves are different. In these cases, we are referring to the linearity of the change in luminescence from the phosphor as a result of a change in electron beam current. The red phosphor (generally a rare earth oxide) is a linear phosphor, whereas the green is nonlinear. Changing the current thus can change the color of the display. In the beam index tube, a UV (or secondary electron emitters have also been used) emitting index layer is put along side a red, green, or blue triad (for example, between the blue and the red phosphor stripes). The scanning electron beam, through the use of a UV sensor (or secondary electron detector) mounted in the rear portion of the tube and the scanning electronics, can determine the location of the red, green, and blue phosphors. The electron beam can then excite only the individual phosphor areas of interest. With this tube, generally, the electron beam is at a low current to give a small enough cross-section to only excite one color and thus has limited application.

Another application of the monochrome is the projection CRT system. Here, three tubes for red, green, and blue are used to project an image on a viewing screen. The terminology is such that, when the CRTs are in the back of the screen and the viewer in front of the screen, it is called a 'rear' projection set and if the CRTs and the viewer are in front of the screen it is a 'front' projection set. The principle here is that, either using one CRT tube at a time or by a superposition two or three of the CRTs, the color of the displayed image will be within the color gamut defined by the primary colors.

The Color CRT

The more ubiquitous method of obtaining a color display is the device called the shadow mask CRT (and the similar Trinitron CRT). This color CRT is designed in such a manner that through the use of an aperture mask, (seen in Figure 1) the electrons from the red electron gun strike the red phosphor and likewise electrons from the green and blue electron guns strike the green and blue phosphors. The combination allows the viewer to see a color image. This color separation action is seen in Figure 2. Although Figure 2 shows a delta tri-color design, there are also in-line systems in which the mask consists of an array of slots which are somewhat rectangular in nature. In this array, many slots can be on a line, or a mask made can be made of a series of wires as used in the Trinitron design.

The disadvantage of the shadow mask technique is that the mask can capture as much as 80% of the electrons from the electron guns. This yields lower screen luminance and lower contrast due to scattered electrons. As the screen size gets larger from 19 inches to 36 inches or more, additional temperature compensation methods must be used to reduce the effects of mask heating. A number of methods to control the shift of the electron beam on the phosphor as the mask heats up have been developed. Initially, axially positioned bimetal springs were used on masks to compensate for the heating effect. Then lighter masks were used with corner lock suspension systems. Another method is using mask materials with lower coefficients of expansion such as INVAR.

Contrast in color CRTs has been improved by first applying a carbon coating between the panel glass and the phosphor screen. This requires additional process steps which form 'windows' in the carbon coating (matrix) through which the excited phosphor is seen. The use of pigmented phosphors also helped to reduce the reflectivity of the phosphor/matrix screen.

The phosphors used in the shadow mask color CRT are the red Y_2O_2S:Eu or, in some cases, the Y_2O_3:Eu phosphor. The green phosphor is ZnS:Cu and the blue phosphor is ZnS:Ag.

The CRT seen in Figure 3 shows the new high-definition television-type (HDTV) tube with the 16 × 9 aspect ratio as contrasted with the older 4 × 3 aspect ratio (screen width × height).



Figure 2 The action of a shadow mask.

Figure 3 A typical HDTV color CRT. Reproduced from Donofrio RL (2002) The future of direct-view CRTs. *SID Information Display Magazine* 6: 10. Permission for reprint courtesy of the Society for Information Display.

The Vacuum Fluorescent Display (VFD)

The VFD can be thought of as a low-voltage CRT. Just as in the CRT, electrons from a cathode are controlled by a grid which allows them to be accelerated and strike the phosphor screen anode. However, the electrons in a CRT can be accelerated with a voltage of 30 000 V, whereas the VFD accelerates the electrons with voltages of 12 to 40 V.

In the operation of the VFD, electrons are emitted by the filament. The filament is a very thin tungsten wire coated with a tri-carbonate oxide (barium, strontium, and calcium carbonates) which are the same constituents of the CRT oxide cathode. The filament is held between a filament support and an anchor which applies tension to the filament wire. A current is passed through the filament to achieve a temperature to ~600 °C. At that temperature, thermonic emission occurs. Between the filament and the phosphor elements is a stainless steel mesh grid. By the application of a positive or negative voltage on this grid, electrons can either be cut off or accelerated to the phosphor on the anode. The anode can be a conductor such as graphite, coated with a phosphor layer such as ZnO:Zn (zinc oxide). This is a low-voltage cathodoluminescent phosphor which emits a green color with an emission maxima of about 505 nm. Other phosphors are also used to obtain red, orange, and blue (Figure 4).

In addition to the filament, grid and anode, the VFD is a vacuum device (like the CRT) and contains a getter to assist achieving and maintaining a good vacuum and an internal transparent conductive coating to protect the display from external electrostatic fields. The VFD display is used frequently in the auto industry and aging of the phosphor is very small, achieving 100 000 hrs to half of the initial luminance.



Figure 4 The cross-section of a vacuum fluorescent display assembly.

VFD units have been made with phosphor elements on either side of the filament. This gives rise to a 3D effect. Graphic and fixed segment VFDs have been made for multimedia products and 16 × 16 graphics for Kanji and other characters.

Experimentally, 2D VFD arrays have been made similar to the FEDs covered in the next section.

Field Emissive Displays (FEDs)

The FED is similar to the CRT and the VFD in that electrons from a source bombard a phosphor screen. In both the CRT and the VFD thermionic electrons are used. However, in the FED the electrons arise from field emission. Field emission devices create electrons though quantum mechanical tunneling from the emitter surface into the vacuum by the action of a large electrical field. This process is governed by the Fowler–Nordheim equation. This equation takes the form:

$$J = A(\beta V)^2/\Phi \exp(-B\Phi^{3/2}/\beta V) \qquad [6]$$

where, J is the electron current density; V is the applied voltage; Φ is the work function of the emitting tip; A & B are constants; and β is the field enhancement factor.

The emitters can be of the Molybdenum Spindt type and also the polydiamond or diamond-like carbon (DLC) coated emitters. We have the field enhancement with a sharp tip and reduced work function with the DLC. There has been renewed interest in FEDs, with the development of the 'carbon nanotube' as an electron field emitting source. The carbon nanotube is a fullerene material, which is a distinct form of carbon. This 'bucky ball'-like



Figure 5 Field emission display cross-section. Reproduced from Green P and Haven D (1998) Fundamentals of emissive displays. *SID Short Course S-3*. Permission for reprint courtesy of the Society for Information Display.



Figure 6 ACPDP partial cross-section view. Reproduced from Green P and Haven D (1998) Fundamentals of emissive displays. *SID Short Course S-3*. Permission for reprint courtesy of the Society for Information Display.

material is cylindrical instead of spherical in nature, has great strength, and high conductivity.

There are two types of FEDs, a low-voltage (LVFED) and a high-voltage (HVFED). The HVFED uses an aluminum film over the phosphor to protect the phosphor screen from aging. The HVFED can use the high voltage (2–10 KV) electrons to bombard the aluminized screen and it can use the more efficient, somewhat standard CRT phosphors ZnS:Cu green, ZnS:Ag Blue, and Y_2O_3:Eu red. The LVFED (12–200 V) cannot use the standard CRT phosphors but uses the low-voltage phosphor such as the ZnO:Zn green phosphor. This does not use an aluminum layer, since about 2 KV is needed to penetrate the Al layer. The commonly used CRT red phosphor Y_2O_2S:Eu was found unsuitable for HVFED use due to release of the sulfur during electron bombardment.

Figure 5 shows that for this basic FED structure, the electrons from the Spindt emitter are controlled by the voltages of the anode, control electrode and emitter electrode.

Plasma Displays

Earlier plasma displays, made using excited Ne gas with the characteristic amber glow required no phosphor and were used in the printing industry. Present plasma displays used for television and information signs are photoluminescent displays. As shown in Figure 6, the excitation of the plasma gas made of elements such as He, Ne, Ar, and Xe give rise to a glow discharge and the creation of vacuum ultraviolet photons that strike the screen and cause it to luminesce. In construction, the display is similar to the FED in that it is a matrix addressed device. It has been described in literature that the similarity goes even further with the need for anode and cathode surfaces, a means of evacuating and a perimeter seal. There are two types of plasma displays, DC and AC. The AC design appears to be the more successful. Typical PDP phosphors for the triad are $(Y,Gd)BO_3$:Eu for the red, Zn_2SiO_4:Mn for the green, and $BaMgAl_{10}O_{17}$:Eu (called BAM for short) for the blue. Figure 6 below shows the basic structure of an AC plasma display. One phosphor element is shown with barrier ribs and address and scan electrodes. The discharge of the plasma takes place in the region of the phosphor and excites the photoluminescent phosphor, which is shaped (in this example) along the side of the barrier ribs and over the address electrode.

Electroluminescence

Electroluminescence was first seen in the 1930s by Destriau. EL is the generation of (nonthermal) light by use of an electric field. High electric field EL units emit light through the impact of high energy electrons in luminescent centers in a semi-conducting material. The electric field can be alternating current (AC) or direct current (DC). Powder phosphor AC EL displays appear to be one of the successful inorganic EL display methods. Because of their rugged nature, alternating current electroluminescence ACEL displays have been used in trucks, tractors and the M1 Abrams Tank. Thick-film EL panels are also used in some vehicle displays as back lights for LCDs. These light panels are free from mercury and are more environmentally friendly.

Inorganic LED Displays

Light-emitting diodes are being used as backlights for LCD displays, replacing some of the fluorescent light backlighting methods. They are also used in indicator lights. Large displays have been made of LEDs. Using a matrix array row and column connectors, we can digitally select a given color LED and pattern in an LED array and generate a color image. Similar methods were carried out many years ago using incandescent lights. However, now they are bright and fast reacting. LEDs operate by semiconductor P–N junction rules and the flow of electrons and holes under forward bias operation give rise to junction light emission. Materials such as GaP:Zn,O are used to create a red LED with an emission maxima wavelength of 699 nm.

Red, green, and blue-UV/blue LEDs are now available, with an increasing demand for white LEDs. Two methods are used to produce a white LED. One method is to use a blue LED with the front of the LED coated with a green photoluminescent phosphor. If the phosphor is thin enough, the blue light penetrates the screen and excites the green to give a blue/green white. Another method is to use a blue LED and coat it with a white photoluminescent phosphor.

Organic LEDs

The basic process of light generation in OLEDs is the formation of a P–N junction. Electrons injected from the N-type material and holes from the P-type material recombine at the junction and light is generated. There are presently two competing methods to fabricate an OLED. The first developed by Kodak in 1987 is the small molecule molecular weight material approach. In OLED operation, the electron hole pair recombine to form excitons (on the average one singlet and three triplet excitons are formed for every four electron hole pairs). The light for the Kodak OLED is from the recombination of singlet excitons and the energy transferred to the fluorescent dye. The terminology is such that we have small molecule-OLEDs (sm-OLEDs) and polymer-OLED (PLED). In later developments, the sm-OLED device structure was reported to have three layers. The first is the hole transport layer (hole transport) enhancing layer copper phthalocyanine (CuPc), a layer NPB (60 nm), the light emitting aluminum tris-8-hydroxyquinolate Alq layer (75 nm), and electron transport layer. The electron transport layer is in contact with the three layer structure. The top electrode is a low work function material, such as MgAg (75–200 nm thick) called an electron injection layer and topped with a transparent indium tin oxide (ITO) layer for transparent OLEDS. All of these coatings are applied in a vacuum chamber.

In the phosphorescent material method, the light emission is from the triplet excitons through the use of phosphorescent dyes and the polymer-based devices. The common base material is a polyphenylene-vinylene PPV and other polymers such as polyfluorene have been used. The construction of the phosphorescent OLED is similar in that the ITO is also used as a starting substrate but the hole transport layer is applied by spin casting from solution. Spin casting is also used for the electron transfer material. After drying (removal of solvents) a calcium cathode material is applied. A contrast of 3000/1 has been achieved (for a military type application) using a green OLED with an AR coated circular polarizer and at an ambient light level of 500 lux, and a 6/1 contrast ratio has been achieved with an ambient illumination of 50 000 lux and an output of 370 cd/m^2. Additionally, OLEDs can be made on flexible (F) substrates and are called FOLEDs. The use of a transparent (T) cathode gives rise to a top emission OLED or a TOLED.

The first OLED display used in auto products was developed by Pioneer and used in a radio display and the Ford Motor Company has shown a White OLED display in one of their ‘Concept Cars’. This display allows them to have a reconfigurable instrument


Electron transport layer and dopant (Alq3/QA)
Cathode electrode (Mg/Ag)
Hole transport layer (NPB)
ITO anode
Glass substrate
Green light output

Figure 7 OLED partial cross-section – Kodak type. Reproduced from Green P and Haven D (1998) Fundamentals of emissive displays. *SID Short Course S-3*. Permission for reprint courtesy of the Society for Information Display.

Figure 8 Philips poled display in an auto mirror. Reproduced with permission of Philips Mobile Display Systems.

panel (IP) and is made up of a number of 5 inch × 8 inch displays across the instrument panel (Figure 7).

The POLED as seen in Figure 8 is now being used by Philips Mobile Systems in a rear view car mirror, as seen below. It is the display from a video camera looking at the rear of a car to see any obstacles to backing up safely.

Thin Film EL (TFEL) Displays

A simple type of TFEL display is the color by white structure shown below. In this case, the color is generated using a white phosphor and red, green, and blue optical filters. To make this ACEL display function properly, insulators are used on either side of the phosphor. In Figure 9, the ITO conducting stripes (depicted) horizontally on the top and vertically on the bottom, give the means of addressing each color pixel. The white phosphor, for example, is a ZnS:Mn, SrS:Ce blend which gives a white electroluminescence.

Other phosphors such as ZnS:Mn can be used but its yellow luminescence requires the use of a green and red filter and only two metal electrodes on the bottom to give a two-color display. Better red green color separation can be achieved through the use of a $Zn_{1-x}Mg_xS$:Mn and ZnS:Mn phosphor mix. New EL blue phosphor developments have allowed larger color gamuts to be achieved.

One of the important characteristics of the alternating current thin-film electroluminescence (ACTFEL) is that it has an operating temperature range from −40 °C to 85 °C which is key for automotive use. It has a viewing angle of 160 degrees with a life of more than 50 000 hours. Active matrix (active addressed) AMEL structures allow fast



Figure 9 Color thin film electroluminescent display (TFEL) cross-section. Reproduced from Dakkala A (1998) New EL displays for vehicular applications. In: Donofrio RL and Musa S (eds) *Flat Panel and Vehicle Display '98.* Permission for reprint courtesy of the Society for Information Display.



Figure 10 AMLCDs used in automobiles. Reproduced from Donofrio RL (2003) The road show. *SID Information Display Magazine* 7: 26. Permission for reprint courtesy of the Society for Information Display.



Figure 11 The operation of a simple liquid crystal display. Reproduced from Lueder E (1997) Fundamentals of passive and active-addressed liquid crystal displays. *SID Short Course S-1* (1997). Permission for reprint courtesy of the Society for Information Display.

response and moving graphic displays. These have found application in 'heads up displays' (HUD) for the military and medical industries and in consumer goods such as portable computers, pagers, cell phones, and 3D gaming.

The Active Matrix LCD

The active matrix liquid crystal display (AMLCD) device consists of a series of liquid crystal cells or windows whose characteristics can be controlled by an applied voltage to pass or restrict the passage of light through the windows via the external polarizers and the polarizing action of the LCD cells. These displays are used in laptop and tabletop computers, TVs, and for automotive displays (for driving information and entertainment). Figure 10 shows some present applications for AMLCDs in the automobile.

When the simple LCD is used without a transistor matrix, it is termed a passive display rather than an active one. Figure 11 below shows how a simple LCD cell operates.

The action shown in this figure is the twisted alignment nature of the liquid crystal material. When the polarizer on the left has its high transmission axis horizontal and the polarizer on the right of this cell has perpendicular alignment then the light from the backlight (f) is passed through the crossed polarizers. However, when voltage is applied to the cell, the liquid crystal is no longer twisted and the crossed polarizers prevent the light from going though the cell to the viewer. If the polarizers were not crossed but the polarization transmission axis was in the same direction in both polarizers, then the opposite effect would occur.



Figure 12 Typical color LCD filter transmission characteristics. Reproduced from Donofrio RL and Abileah A (1998) LCD backlighting system – phosphors and colors. In: Donofrio RL and Musa S (eds) *Flat Panel and Vehicle Display '98, p. 123*. Permission for reprint courtesy of the Society for Information Display.

In order to show a color image, the LCD is designed to have three or more cells clustered per color pixel. The following (Figure 12) is the transmission profiles of each of these red, green, and blue filters.

The backlight used is a fluorescent lamp with a white phosphor (made up of red, green, and blue photoluminescent phosphors). Figure 13 shows what would happen if only the blue phosphor was used and also shows the superposition of the mercury lines that penetrate the phosphor and contribute to the final spectral energy distribution.

Reflective LCD

For applications where there is suitable external light to view the display, no internal light source is used.



Figure 13 The relative luminance spectrum of the LCD. Backlight blue phosphor showing mercury lines. Reproduced from Donofrio RL and Abileah A (1998) LCD backlighting system – phosphors and colors. In: Donofrio RL and Musa S (eds) *Flat Panel and Vehicle Display '98, p. 123*. Permission for reprint courtesy of the Society for Information Display.



Figure 14 The action and construction of a reflective LCD. Reproduced with permission from Watanabe R and Tomita O (2003) Active-Matrix LCDs for Mobile Telephones in Japan. *SID Information Display Magazine* 7(3): 30–35. Permission for reprint courtesy of the Society for Information Display.



Figure 15 The action and cross-section of a transflective LCD. Reproduced with permission from Watanabe R and Tomita O (2003) Active-Matrix LCDs for Mobile Telephones in Japan. *SID Information Display Magazine* 7(3): 30–35. Permission for reprint courtesy of the Society for Information Display.

This reflective LCD consists of a polarizer and retarder plates stacked on the front side of the cell. The cell with spacers contains the liquid crystal material and on the bottom of the cell is located a reflecting surface. It has been found that a dimpled reflecting surface makes a diffuse reflecting surface (Figure 14).

Transflective LCD

The importance of the transflective device is that it has better contrast under high ambient illumination than the standard transmission back lighted LCD and fair contrast for low ambient illumination.

The construction of this device consists of front and rear circular polarizers, back light, reflective elements, and novel filters. The back light is in the rear of the display. However, like the reflective LCD, internal reflectors are used on each pixel. The filters are designed spatially to be more transmissive for the reflective light than for the back light. Additionally the cell gap for the reflective light is smaller then the transmitted light region because the reflected light passes the cell twice whereas the transmitted light passes the cell once. This type of device seen in Figure 15, is finding uses in the auto industry and where the LCD is needed for both low and high ambient light levels.

Conclusions

In this brief review of displays we have tried to cover many different types of displays. The reader will in time find that there are many other variations on the displays discussed. The object is to give the reader an up-to-date review of the topics involved with displays and the various types of display in use today. By its nature it is a broad approach.

See also

Color and the World. **Instrumentation:** Photometry. **Light Emitting Diodes**. **Materials for Nonlinear Optics:** Liquid Crystals for NLO.

Further Reading

Donofrio RL (1981) Low Current Density Aging. *Proceedings of the Electro-Chemical Society*, Abstract #152, May 11, 1981.

Donofrio RL (2003) The road show. *Information Display* 7(3): 26–29.

Donofrio RL and Abileah A (1998) LCD backlighting. *Flat Panel and Vehicle Displays '98* : 119–124. Metropolitan Detroit Chapter of the SID.

Donofrio RL, Musa S and Wise K (eds) (1999) Vehicle Displays and Microsensors '99. *Proceedings of the 6th Strategic Forum and Technical Symposium*, Sept 22–23, 1999.

Flat Panel Display Measurements Standard, Version 1.0 VESA (Video Electronics Standards Association) May 15, 1998.

Forrest S (2002) *Fundamentals of Organic Light-Emitting Devices*. Short Course S-2 SID.

Green P and Haven D (1998) *Fundamentals of Emissive Displays*, Short Course S-3, SID.

Keller P (1991) *The Cathode-Ray Tube, Technology, History, and Applications*. New York: Palisades Press.

Leverence HW (1968) *An Introduction to Luminescence of Solids*. Dover Publications.

MacDonald W and Lowe A (1997) *Display Systems – Design and Applications*. SID Series in Display Technology, Wiley and Sons Ltd.

Sherr S (1993) *Electronic Displays*, 2nd edn. John Wiley.

Shionoya S and Yen WM (1998) *Phosphor Handbook*. CRC Press.

Stupp EH and Brennesholtz MS (1999) *Projection Displays*. SID Series in Display Technology, Wiley and Sons Ltd.

Watanabe R and Tomita O (2003) Active-Matrix LCDs for Mobile Telephones in Japan. *SID Information Display Magazine* 7(3): 30–35.

Web site atis.org/tg2k/. American National Standard TI.523-2001 'Def of Display Device'.

Wu ST and Yang DK (2001) *Reflective Liquid Crystal Displays*. SID Series in Displays Technology, Wiley and Sons Ltd.

E

ELECTROMAGNETICALLY INDUCED TRANSPARENCY

J P Marangos, Imperial College of Science, Technology and Medicine, London, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In this article we examine how the process of electromagnetically induced transparency (EIT) can be used to increase the efficiency of non-linear optical frequency mixing schemes. We illustrate the basic ideas by concentrating upon the enhancement of resonant four-wave mixing schemes in atomic gases. To start we introduce the quantum interference phenomenon that gives rise to EIT. The calculation of EIT effects in a three-level atomic medium using a density matrix approach is presented. Next we examine the modified susceptibilities that result and that can be used to describe nonlinear mixing, and show how large enhancements in nonlinear conversion efficiency can result. Specific examples are briefly discussed along with a further discussion of the novel aspects of refractive index and pulse propagation modifications that result from EIT. The potential benefits to nonlinear optics of electromagnetically induced transparency are discussed. In an article of this nature it is not possible to credit all of the important contributions to this field, but we include a bibliography for further reading indicating some of the seminal contributions.

Electromagnetically induced transparency is the term applied to the process by which an otherwise opaque medium can be rendered transparent through laser-induced quantum mechanical interference processes. The linear susceptibility is substantially modified by EIT. Absorption is cancelled due to destructive interference between excitation pathways. The dispersion of the medium is likewise modified such that where there is no absorption the refractive index is unity and there can be a large value of normal dispersion leading to low values of group velocity. In contrast to the linear susceptibility the nonlinear susceptibility involving these same resonant laser fields will undergo constructive rather than destructive interference. This leads to a strong enhancement in nonlinear frequency mixing. For a normally transparent medium the nonlinear optical couplings will be small unless large-amplitude fields are applied. The most important consequence of EIT, in contrast to the usual case when a medium is transparent, is that the dispersion is not vanishing and the nonlinear couplings can be very large.

To understand how this comes about we must consider the system illustrated in Figure 1a where because of the resonant condition satisfied for the applied fields the atom can be simplified to just three-levels. The important parameters in this model system are that state |2> is metastable and has a dipole-allowed coupling to state |3>. The coupling between states |1> and |3> is also dipole-allowed



Figure 1 A three-level atomic system coupled to laser fields in the lambda configuration is shown on the left-hand side. In the limit of a strong coupling field this is equivalent to the dressed states |a> and |b> coupled to the ground state by the probe field alone as shown on the right-hand side.

and as a consequence state |3> can decay radiatively to either |1> or |2>. Let a coupling field be applied resonantly to the |2> − |3> transition, which may be cw or pulsed but should in the latter case be transform-limited. We define the Rabi coupling as $\Omega_{23} = \frac{\mu_{23}E}{\hbar}$ where E is the laser electric field amplitude and μ_{23} is the dipole moment of the transition. The Rabi frequency needs to be larger than the inhomogeneous broadening of the sample. A second field, the probe, typically of much lower intensity, is then applied in resonance with the |1> − |3> transition. If the condition $\Omega_{23} \gg \Omega_{13}$ is satisfied then it is convenient to replace the bare atomic states |2> and |3> with the dressed states (see Figure 1b):

$$|a\rangle = \frac{1}{\sqrt{2}}[|2\rangle + |3\rangle] \qquad [1a]$$

$$|b\rangle = \frac{1}{\sqrt{2}}[|2\rangle - |3\rangle] \qquad [1b]$$

Transitions from state |1> induced by the probe field to this pair of near-resonant dressed states are subject to exact cancellation at resonance if |2> is perfectly metastable. This is because the only contribution to the excitation amplitude comes from the matrix elements $\langle 1|\mathbf{r}\cdot\mathbf{E}|3\rangle$ as the |1> − |2> transition is dipole forbidden. The contributions from the equally detuned states |a> and |b> thus enter into the overall amplitude with opposite signs and equal magnitude as can be seen by inspection of eqns [1a] and [1b]. This leads to cancellation of the absorption amplitude. This type of absorption cancellation is well known and closely related to the so-called *dark states*.

Theoretical Treatment of EIT in a Three-Level Medium

It was realized by several workers in the 1970s that laser-induced interference effects could lead to a cancellation of absorption at certain frequencies. To gain a more quantitative understanding of the effects of the coupling field upon the optical properties of a dense ensemble of three-level atoms we require a treatment that computes the optical susceptibility of the medium. A treatment originally carried out by Harris *et al.* for a Λ scheme similar to that illustrated in Figure 1 was the first to derive the modified susceptibilities that will be discussed below. In that treatment the state amplitudes in the three-level atom were solved in the steady-state limit and from these the linear and nonlinear susceptibilities (see below) are then derived. In what follows we adopt a density matrix treatment as employed by various workers. This readily allows the inclusion of dephasing as well as population decay terms. The critical parameters in this system are the strengths of the fields (described in terms of the Rabi couplings), the detuning of the fields from resonance $\Delta\omega_{13} = \omega_{13} - \omega_P$ and $\Delta\omega_{23} = \omega_{23} - \omega_C$ (see Figure 2), the radiative decays from |3> to |1> and |2>, γ_c and γ_d and from |2>−|1> γ_a (although the latter is anticipated to be smaller). Extension to other configurations of the three states, such as a V or ladder scheme is implicit within this general treatment.

Figure 2 illustrates the system considered. This treatment will also address the nonlinear response in a four-wave mixing scheme completed by the two-photon resonant coupling applied between state |1> and |2>.

We write the interaction Hamiltonian as:

$$H = H_0 + V \qquad [2]$$



Figure 2 A four-wave mixing scheme incorporating the three-level lambda system in which electromagnetically induced transparency has been created for the generated field ω_d by the coupling field ω_c. The decay rates γ_i from the three atomic levels are also shown. For a full explanation of this system see text.

where H_0 is the unperturbed Hamiltonian of the system and is written as

$$H_0 = \hbar\omega_1|1\rangle\langle 1| + \hbar\omega_2|2\rangle\langle 2| + \hbar\omega_3|3\rangle\langle 3| \qquad [3]$$

and V is the interaction Hamiltonian and can be expressed

$$\begin{aligned} V = {} & \hbar\Omega_{\mathrm{a}}\mathrm{e}^{-\mathrm{i}\omega_{\mathrm{a}}\mathrm{t}}|2\rangle\langle 1| + \hbar\Omega_{\mathrm{c}}\mathrm{e}^{-\mathrm{i}\omega_{\mathrm{c}}\mathrm{t}}|2\rangle\langle 3| \\ & + \hbar\Omega_{\mathrm{d}}\mathrm{e}^{-\mathrm{i}\omega_{\mathrm{d}}\mathrm{t}}|3\rangle\langle 1| + c.c \end{aligned} \qquad [4]$$

Note that the Rabi frequencies in the equation can be described as $\hbar\Omega_{ij} = \mu_{ij}|E(\omega_{ij})|$, where μ_{ij} is the dipole moment of the transition between states |i> and |j>, the Rabi frequency Ω_{a} is a two-photon Rabi frequency that characterizes the coupling between the laser field a and the atom for this two-photon transition. We have assumed for simplicity that $\omega_{\mathrm{a}} = \omega_{\mathrm{b}} = \omega_{12}/2$.

Assuming all the fields lie close to the resonance, the rotating wave approximation can be applied to the interaction picture and the interaction Hamiltonian V^I is given as

$$\begin{aligned} V^I = {} & \hbar\Omega_{\mathrm{a}}\mathrm{e}^{\mathrm{i}\Delta_{\mathrm{a}}\mathrm{t}}|2\rangle\langle 1| + \hbar\Omega_{\mathrm{c}}\mathrm{e}^{\mathrm{i}\Delta_{\mathrm{c}}\mathrm{t}}|2\rangle\langle 3| \\ & + \hbar\Omega_{\mathrm{d}}\mathrm{e}^{\mathrm{i}\Delta_{\mathrm{d}}\mathrm{t}}|3\rangle\langle 1| + c.c \end{aligned} \qquad [5]$$

where Δ_{a}, Δ_{c} and Δ_{d} refer the detunings of the fields and can be written as:

$$\begin{aligned} \Delta_{\mathrm{a}} &= \omega_{12} = 2\omega_{\mathrm{a}} \\ \Delta_{\mathrm{c}} &= \omega_{32} - \omega_{\mathrm{c}} \\ \Delta_{\mathrm{d}} &= \omega_{13} - \omega_{\mathrm{d}} \end{aligned} \qquad [6]$$

For the evaluation of the density matrix with this interaction V^I, the Schrödinger equation can be restated in terms of the density matrix components. This form is called the Liouville equation and can be written as:

$$\hbar\frac{\partial}{\partial t}\varrho_{ij}(t) = -\mathrm{i}\sum_k H_{ik}(t)\varrho_{ij}(t) + \mathrm{i}\sum_k \varrho_{ij}(t)H_{ik}(t) + \Gamma_{ij} \qquad [7]$$

where Γ_{ij} represents phenomenologically added decay terms (i.e. spontaneous decays, collisional broadening, etc.). This formalism leads to a set of nine differential equations for nine different density matrix elements that describe the three-level system.

To remove the optical frequency oscillations, a coordinate transform is needed and to incorporate the relevant oscillatory detuning terms into the off-diagonal elements we make the substitution:

$$\begin{aligned} \tilde{\varrho}_{12} &= \varrho_{12}\mathrm{e}^{-\mathrm{i}\Delta_{\mathrm{a}}\mathrm{t}} \\ \tilde{\varrho}_{23} &= \varrho_{23}\mathrm{e}^{-\mathrm{i}\Delta_{\mathrm{c}}\mathrm{t}} \\ \tilde{\varrho}_{31} &= \varrho_{31}\mathrm{e}^{-\mathrm{i}\Delta_{\mathrm{d}}\mathrm{t}} \end{aligned} \qquad [8]$$

This operation conveniently eliminates the time dependencies in the rate equations and the equations of motion for the density matrix are given by:

$$\begin{aligned} \frac{\partial}{\partial t}\varrho_{11} = {} & \mathrm{i}\frac{1}{2}\Omega_{\mathrm{a}}\tilde{\varrho}_{12} + \mathrm{i}\frac{1}{2}\Omega_{\mathrm{d}}\tilde{\varrho}_{13} - \mathrm{i}\frac{1}{2}\Omega^*_{\mathrm{a}}\tilde{\varrho}_{21} \\ & - \mathrm{i}\frac{1}{2}\Omega^*_{\mathrm{d}}\tilde{\varrho}_{31} + \Gamma_{11} \\ \frac{\partial}{\partial t}\varrho_{22} = {} & \mathrm{i}\frac{1}{2}\Omega^*_{\mathrm{c}}\tilde{\varrho}_{23} + \mathrm{i}\frac{1}{2}\Omega^*_{\mathrm{a}}\tilde{\varrho}_{21} - \mathrm{i}\frac{1}{2}\Omega_{\mathrm{c}}\tilde{\varrho}_{32} \\ & - \mathrm{i}\frac{1}{2}\Omega_{\mathrm{a}}\tilde{\varrho}_{12} + \Gamma_{22} \\ \frac{\partial}{\partial t}\varrho_{33} = {} & \mathrm{i}\frac{1}{2}\Omega^*_{\mathrm{c}}\tilde{\varrho}_{23} - \mathrm{i}\frac{1}{2}\Omega^*_{\mathrm{d}}\tilde{\varrho}_{31} + \mathrm{i}\frac{1}{2}\Omega_{\mathrm{d}}\tilde{\varrho}_{13} \\ & - \mathrm{i}\frac{1}{2}\Omega_{\mathrm{c}}\tilde{\varrho}_{32} + \Gamma_{33} \\ \frac{\partial}{\partial t}\varrho_{23} = {} & \mathrm{i}\frac{1}{2}\Omega_{\mathrm{c}}\tilde{\varrho}_{22} - \mathrm{i}\frac{1}{2}\Omega_{\mathrm{c}}\tilde{\varrho}_{33} - \mathrm{i}\Delta_{\mathrm{a}}\tilde{\varrho}_{23} \\ & + \mathrm{i}\frac{1}{2}\Omega_{\mathrm{d}}\tilde{\varrho}_{21} - \mathrm{i}\frac{1}{2}\Omega_{\mathrm{a}}\tilde{\varrho}_{13} + \Gamma_{23} \\ \frac{\partial}{\partial t}\varrho_{21} = {} & \mathrm{i}\Omega_{\mathrm{a}}\tilde{\varrho}_{22} + \mathrm{i}\Omega_{\mathrm{a}}\tilde{\varrho}_{33} + \mathrm{i}\Omega_{\mathrm{d}}\tilde{\varrho}_{23} - \mathrm{i}\Delta_{\mathrm{c}}\tilde{\varrho}_{21} \\ & - \mathrm{i}\frac{1}{2}\Omega_{\mathrm{c}}\tilde{\varrho}_{31} - \mathrm{i}\frac{1}{2}\Omega_{\mathrm{a}}\tilde{\varrho}_{31} + \Gamma_{21} \\ \frac{\partial}{\partial t}\varrho_{31} = {} & \mathrm{i}\frac{1}{2}\Omega_{\mathrm{d}}\tilde{\varrho}_{22} + \mathrm{i}\Omega_{\mathrm{d}}\tilde{\varrho}_{33} + \mathrm{i}\Omega_{\mathrm{d}}\tilde{\varrho}_{23} - \mathrm{i}\Delta_{\mathrm{c}}\tilde{\varrho}_{21} \\ & - \mathrm{i}\frac{1}{2}\Omega_{\mathrm{c}}\tilde{\varrho}_{31} - \mathrm{i}\frac{1}{2}\Omega_{a}\tilde{\varrho}_{31} + \Gamma_{31} \end{aligned} \qquad [9]$$

Using the set of equations above and the relation $\tilde{\varrho}_{ij} = \tilde{\varrho}^*_{ij}$ we obtain equations for $\tilde{\varrho}_{12}$, $\tilde{\varrho}_{32}$, and $\tilde{\varrho}_{13}$. For the incoherent population relaxation the decays can be written:

$$\begin{aligned} \Gamma_{11} &= \gamma_{\mathrm{a}}\varrho_{22} + \gamma_{\mathrm{d}}\varrho_{33} \\ \Gamma_{22} &= -\gamma_{\mathrm{a}}\varrho_{22} + \gamma_{\mathrm{c}}\varrho_{33} \\ \Gamma_{33} &= -(\gamma_{\mathrm{c}} + \gamma_{\mathrm{d}})\varrho_{33} \end{aligned} \qquad [10]$$

and for the coherence damping:

$$\begin{aligned} \Gamma_{21} &= -\left\{\frac{1}{2}[\gamma_{\mathrm{a}} + \gamma_{\mathrm{c}}] + \gamma^{\mathrm{col}}_{21}\right\}\varrho_{21} \\ \Gamma_{23} &= -\left\{\frac{1}{2}[\gamma_{\mathrm{a}} + \gamma_{\mathrm{c}} + \gamma_{\mathrm{d}}] + \gamma^{\mathrm{col}}_{23}\right\}\varrho_{23} \\ \Gamma_{31} &= -\left\{\frac{1}{2}[\gamma_{\mathrm{d}} + \gamma_{\mathrm{c}}] + \gamma^{\mathrm{col}}_{31}\right\}\varrho_{31} \end{aligned} \qquad [11]$$

where $\gamma^{\mathrm{col}}_{ij}$ represents collisional dephasing terms which may be present.

This system of equations can be solved by various analytical or numerical methods to give the individual density matrix elements. Analytical solutions are possible if we can assume for instance that $\Omega_c \gg \Omega_a$, Ω_d and that there are continuous-wave fields so a steady-state treatment is valid. For pulsed fields or in the case where the generated field may be significant numerical solutions are in general required.

We are specifically interested in the optical response to a probe field at ω_d (close to resonance with the $|1\rangle - |3\rangle$ transition) that is governed by the magnitude of the coherence ϱ_{13}. We find ϱ_{13} making the assumption that only the coupling field is strong, i.e., that $\Omega_c \gg \Omega_a, \Omega_d$ holds. From this quantity the macroscopic polarization is obtained from which the susceptibility can be computed. The macroscopic polarization P at the transition frequency ω_{13} can be related to the microscopic coherence ϱ_{13} via the expression:

$$P_{13} = N\mu_{13}\varrho_{13} \qquad [12]$$

where N is the number of equivalent atoms in the ground state within the medium, and μ_{13} is the dipole matrix element associated with the transition. In this way real and imaginary parts of the linear susceptibility χ at frequency ω can be directly related to ϱ_{13} via the macroscopic polarization since the latter can be defined as:

$$P_{13}(\omega) = \varepsilon_0\chi(\omega)E \qquad [13]$$

where E is the electric field amplitude at frequency ω_d. The linear susceptibility (real and imaginary parts) is given by the following expressions:

$$\mathrm{Re}\chi_D^{(1)}(-\omega_d,\omega_d) = \frac{|\mu_{13}|^2 N}{\varepsilon_0\hbar} \times\left[\frac{-4\Delta_{21}(|\Omega_2|^2 - 4\Delta_{21}\Delta_{32}) + 4\Delta_{31}\gamma_a^2}{4\Delta_{31}\Delta_{21} - \gamma_d\gamma_a - |\Omega_2|^2)^2 + 4(\gamma_d\Delta_{21} + \gamma_a\Delta_{31})^2}\right] \qquad [14]$$

$$\mathrm{Im}\chi_D^{(1)}(-\omega_d,\omega_d) = \frac{|\mu_{13}|^2 N}{\varepsilon_0\hbar} \times\left[\frac{8\Delta_{21}^2\gamma_d + 2\gamma_a(|\Omega_2|^2 + \gamma_d\gamma_a)}{(4\Delta_{31}\Delta_{21} - \gamma_d\gamma_a - |\Omega_2|^2)^2 + 4(\gamma_d\Delta_{21} + \gamma_a\Delta_{31})^2}\right] \qquad [15]$$

We now consider the additional two-photon resonant field ω_a. This leads to a four-wave mixing process that generates a field at ω_d (i.e., the probe frequency). The nonlinear susceptibility that describes the coupling of the fields in a four-wave mixing process is given by the expression:

$$\chi_D^{(3)}(-\omega_d,\omega_a,\omega_a,\omega_c) = \frac{\mu_{23}\mu_{13}N}{6\varepsilon_0\hbar^3((\Delta_{21} - j\gamma_a/2)(\Delta_{31} - j\gamma_d/2) - (|\Omega_c|^2/4))^*} \times\sum_i \mu_{i1}\mu_{i3}\left(\frac{1}{\omega_i - \omega_a} + \frac{1}{\omega_i - \omega_b}\right)$$

Nonlinear Optical Processes

The dependence of the susceptibilities upon the detuning is plotted in Figure 3. In this plot the effects of inhomogeneous (Doppler) broadening are



Figure 3 Electromagnetically induced transparency is shown in the case of significant Doppler broadening. The Doppler averaged values of the imaginary Im[$\chi^{(1)}$] and real Re[$\chi^{(1)}$] parts of the linear susceptibility and the nonlinear susceptibility $\chi^{(3)}$ are plotted in the three frames. The Doppler width is taken to be $20\gamma_d$, $\Omega_c = 100\gamma_d$ and $\gamma_d = 50\gamma_a$, $\gamma_c = 0$.

also incorporated by computing the susceptibilities over the inhomogeneous profile (see below for more details).

By inspection of eqn [14] we see that the absorptive loss at the minimum of $\mathrm{Im}[\chi^{(1)}]$ varies as γ_a/Ω_c^2. This dependence is a consequence of the interference discussed above. In the absence of interference (i.e., just simply Autler–Townes splitting) the minimum loss would vary as γ_d/Ω_c^2. Since $|3> - |1>$ is an allowed decay channel (in contrast to $|2> - |1>$) it follows that $\gamma_b \gg \gamma_a$ and so the absorption is much less as a consequence of EIT. $\mathrm{Re}[\chi^{(1)}]$ in eqn [15] and Figure 3 is also modified significantly. The resonant value of refractive index is equal to the vacuum value where the absorption is a minimum, the dispersion is normal in this region with a gradient determined by the strength of the coupling laser, a point we will return to shortly. For an unmodified system the refractive index is also unity at resonance but in that case there is high absorption and steep anomalous absorption. Reduced group velocities result from the steep normal dispersion that accompanies EIT. Inspection of the expression [16] and Figure 3 shows that $\chi^{(3)}$ is also modified by the coupling field. The nonlinear susceptibility depends upon $1/\Omega_c^2$ as is expected for a laser dressed system, however in this case there is not destructive but rather constructive interference, between the field-split components. This result is of great importance: it ensures that the absorption can be minimized at frequencies where the nonlinear absorption remains large.

As a consequence of constructive interference the nonlinear susceptibility remains resonantly enhanced whilst the linear susceptibility vanishes or becomes very small at resonance due to destructive interference. Large nonlinearity accompanying vanishing absorption (transparency) of course match conditions for efficient frequency mixing as a large atomic density can then be used. Moreover the dispersion (controlling the refractive index) also vanishes at resonance; this leads to perfect phase matching (i.e., zero wavevector mismatch between the fields) in the limit of a simple three-level system. As a result of these features a large enhancement of the conversion efficiency in this type of scheme can be achieved.

To compute the generated field strength Maxwell's equations must be solved using these expression for the susceptibility to describe the absorption, refraction, and nonlinear coupling in the medium. We will treat this within the slowly varying envelope approximation since the fields are cw or nanosecond pulses. To be specific we assume that the susceptibilities are time independent, i.e., that we are in the steady-state (cw) limit. We make the assumptions also that there is no pump field absorption and that we have plane waves. Under these assumptions the generated field amplitude A_d is given in terms of the other field amplitudes A_i by:

$$\frac{\partial}{\partial z}A_\mathrm{d} = \mathrm{i}\frac{\omega_\mathrm{d}}{4c}\chi^{(3)}A_\mathrm{a}^2A_\mathrm{c}\mathrm{e}^{-\mathrm{i}\Delta k_\mathrm{d}z} - \frac{\omega_\mathrm{d}}{2c}\mathrm{Im}[\chi^{(1)}]A_\mathrm{d} + \mathrm{i}\frac{\omega_\mathrm{d}}{2c}\mathrm{Re}[\chi^{(1)}]A_\mathrm{d} \qquad [16]$$

where the wavevector mismatch is given by:

$$\Delta k_\mathrm{d} = k_\mathrm{d} + k_\mathrm{c} - 2k_\mathrm{a} \qquad [17]$$

The wavevector mismatch will be zero on resonance for the three-level atom considered in this treatment. In fact the contribution to the refraction from all the other atomic levels must be taken into account whilst computing Δk_d and it is implicit that these make a finite contribution to the wavevector mismatch.

We can solve this first-order differential equation with the boundary condition $A_\mathrm{d}(z=0)=0$ to find the generated intensity $I(\omega_\mathrm{d})$ after a length z:

$$I(\omega_\mathrm{d}) = \frac{3n\omega_\mathrm{d}^2}{8Z_0c^2}|\chi^{(3)}|^2|A_\mathrm{a}|^4|A_\mathrm{c}|^2 \times \frac{\left\{1+\mathrm{e}^{-\frac{\omega_\mathrm{d}}{c}\mathrm{Im}[\chi^{(1)}]z} - 2\mathrm{e}^{-\frac{\omega_\mathrm{d}}{c}\mathrm{Im}[\chi^{(1)}]z}\cos\left(\Delta k + \frac{\omega_\mathrm{d}}{2c}\mathrm{Re}[\chi^{(1)}]\right)z\right\}}{\frac{\omega_\mathrm{d}^2}{4c^2}\mathrm{Im}[\chi^{(1)}]^2 + \left\{\Delta k + \frac{\omega_\mathrm{d}}{2c}\mathrm{Re}[\chi^{(1)}]\right\}^2}$$

where Z_0 is the impedance of free space. This expression is quantitatively correct for the case of the assumptions made. More generally the qualitative predictions and general scaling remain valid in the limit where the pulse duration is significantly longer than the time required to traverse the medium. Note that both real and imaginary parts of $\chi^{(1)}$ and $\chi^{(3)}$ play an important role, as we would expect for resonant frequency mixing. The influence of that part of the medium refraction which is due to other levels is contained in the terms with Δk. In the case of a completely transparent medium this becomes a major limit to the conversion efficiency.

Propagation and Wave-Mixing in a Doppler Broadened Medium

Doppler shifts arising from the Maxwellian velocity distribution of the atoms in the medium lead to a corresponding distribution in the detunings for the various members of the atomic ensemble. The response of the medium, as characterized by the susceptibilities, must therefore include the Doppler effect by performing a weighted sum over possible detunings. The weighting is determined by the Gaussian form of the Maxwellian velocity distribution. From this operation the effective values of the susceptibilities at a given frequency are obtained, and these quantities can be used to calculate the generated field. This step is of considerable practical importance as in most up-conversion schemes it is not possible to achieve Doppler-free geometries and the use of laser cooled atoms, although in principle possible, limits the atomic density that can be employed. The interference effects persist in the dressed profiles providing the coupling laser Rabi frequency is comparable to or larger than the inhomogeneous width. This is because the Doppler profile follows a Gaussian distribution which falls off much faster in the wings of the profile than the Lorentzian profile due to the natural broadening.

In the case considered with weak probe field, excited state populations and coherences remain small. The two-photon transition need not be strongly driven (i.e., a small two-photon Rabi frequency can be used) but a strong coupling laser is required. The coupling laser must be intense enough that its Rabi frequency is comparable to or exceeds the inhomogenous widths in the system (i.e., Doppler width), and a laser intensity of above 1 MW cm^{-2} is required for a typical transition. This is trivially achieved even for unfocused pulsed lasers, but does present a serious limit to cw lasers unless a specific Doppler-free configuration is employed. The latter is not normally suitable for a frequency up-conversion scheme if a significant up-conversion factor is required, e.g., to the vacuum ultraviolet (VUV); however recent experiments report significant progress in cw frequency up-conversion using EIT and likewise a number of other possibilities, e.g., laser-cooled atoms and standing-wave fields, have been proposed.

A transform-limited single-mode laser pulse is essential for the coupling laser field since a multimode field will cause an additional dephasing effect on the coherence, resulting in a deterioration of the quality of the interference. In contrast, whilst it is advantageous for the field driving the two-photon transition to be single mode (in order to achieve optimal temporal and spectral overlap with the EIT hole induced by the dressing laser), this is not essential since this field does not need to drive the coherence responsible for interference.

When a pulsed laser field is used additional issues must be considered. The group velocity is modified for pulses propagating in the EIT large reductions, e.g., by factors down to $<c/100$, in the group velocity have been observed. Another consideration beyond that found in the simple steady-state case is that the medium can only become transparent if the pulse contains enough energy to dress all the atoms in the interaction volume. The minimum pulse energy to prepare a transparency is:

$$E_{\mathrm{preparation}} = \frac{f_{13}}{f_{23}} NL\hbar\omega \qquad [18]$$

where f_{ij} are the oscillator strengths of the transitions and NL the product of the density and the length. Essentially the number of photons in the pulse must exceed the number of atoms in the interaction volume to ensure all atoms are in the appropriate dressed state. This puts additional constraints on the laser pulse parameters.

Up-conversion to the UV and vacuum UV has been enhanced by EIT in a number of experiments. Only pulsed fields have so far been up-converted to the VUV with EIT enhancement. The requirements on a minimum value of $\Omega_c > \Delta_{\mathrm{Doppler}}$ constrains the conversion efficiency that can be achieved because the $1/\Omega_c^2$ factor in eqn [17] ultimately leads to diminished values of $\chi^{(3)}$. The use of gases of higher atomic weight at low temperatures is therefore highly desirable in any experiment utilizing EIT for enhancement of four-wave mixing to the VUV. Conversion efficiencies, defined in terms of the pulse energies by E_d/E_a or E_d/E_c of a few percent have been achieved using the EIT enhancement technique. It is typically most beneficial to maximize the conversion efficiency defined by the first ratio since ω_a is normally in the UV and is the lower energy of the two applied pulses.

Nonlinear Optics with a Pair of Strong Coupling Fields in Raman Resonance

An important extension of the EIT concept occurs when two strong fields are applied in Raman resonance between a pair of states in a three-level system. Considering the system illustrated in Figure 1 we can imagine that both applied fields are now strong. Under appropriate adiabatic conditions the system evolves to produce the maximum possible value for the coherence $\varrho_{12} = 0.5$. Adiabatic evolution into the maximally coherent state is achieved by adjusting either the Raman detuning or the pulse sequence (counter to-intuitive order). The pair of fields may also be in single-photon resonance with a third level, in which case the EIT-like elimination of absorption will be important. This situation is equivalent to the formation of a darkstate, since neither of the two strong fields is absorbed by the medium. For sufficiently strong fields the single-photon condition need not be satisfied and a maximum coherence will still be achieved.

An additional field applied to the medium can participate in sum- or difference-frequency mixing with the two Raman resonant fields. The importance of the large value of coherence is that it is the source polarization that drives the new fields generated in the frequency mixing process. Complete conversion can occur over a short distance that greatly alleviates the constraints usually set by phase-matching in nonlinear optics. Recently near unity conversion efficiencies to the far-UV were reported in an atomic lead system where maximum coherence had been created. In a molecular medium large coherence between vibrational or rotational levels has also been achieved using adiabatic pulse pairs. Efficient multi-order Raman sideband generation has been observed to occur. This latter observation may lead the way to synthesizing very short duration light pulses since the broadband Raman sideband spectrum has been proved to be phase-locked.

Pulse Propagation and Nonlinear Optics for Weak CW Fields

In a Doppler-free medium a new regime can be accessed. This is shown in Figure 4 where the possibility now arises of extremely narrow transparency dips since very small values of Ω_c are now sufficient to induce EIT. The widths of these features are typically subnatural and are therefore accompanied by very steep normal dispersion, which corresponds to a much reduced group velocity. The ultraslow propagation of pulses is one of the most dramatic manifestations of EIT in this regime. Nonlinear susceptibilities are now very large as there is constructive interference controlling the value and the splitting of the two states is negligible compared to their natural width. Nonlinear optics at very low light levels, i.e., at the few-photon limit, is possible in this regime.



Figure 4 Electromagnetically induced transparency is shown in the case where there is no significant Doppler broadening. The values of the imaginary Im[$\chi^{(1)}$] and real Re[$\chi^{(1)}$] parts of the linear susceptibility and the nonlinear susceptibility $\chi^{(3)}$ are plotted in the three frames. We take $\Omega_c = \gamma_d/5$ and $\gamma_d = 50\gamma_a$, $\gamma_c = 0$.

Propagation of pulses is significantly modified in the presence of EIT. Figure 4 shows the changes to Re[$\chi^{(1)}$] that arise. Within the transparency dip there exists a region of steep normal dispersion. In the vicinity of resonance this is almost linear and it becomes reasonable to consider the leading term only that describes the group velocity. An analysis of the refractive changes has been provided by Harris who expanded the susceptibilities (both real and imaginary parts) of the dressed atom around the resonance frequency to determine various terms in Re[$\chi^{(1)}$]. The first term of the series (zero order) Re[$\chi^{(1)}$](ω_{13}) = 0 corresponds to the vanishing dispersion at resonance. The next term $\partial[\mathrm{Re}\chi^{(1)}](\omega)/\partial\omega$ gives the slope of the dispersion curve; at ω_{13} this takes the value:

$$\frac{\partial \mathrm{Re}\chi^{(1)}(\omega_{13})}{\partial \omega} = \frac{|\mu_{13}|^2 N4(\Omega_c^2 - \gamma_a^2)}{2\pi\varepsilon_0(\Omega_c^2 + \gamma_a\gamma_d)} \qquad [19]$$

The slope of the dispersion profile leads to a reduced group velocity v_g:

$$\frac{1}{v_g} = \frac{1}{c} + \frac{\pi}{\lambda}\frac{\partial \chi^{(1)}}{\partial \omega} \qquad [20]$$

From the expression for $\partial\chi/\partial\omega$ we see that this slope is steepest (and so v_g mimimum) in the case where $\Omega_c \gg \Gamma_2$ and $\Omega_c^2 \gg \Gamma_2\,\Gamma_3$ but is still small compared to Γ_3 (i.e., $\Omega_C < \Gamma_3$) and hence $\partial\chi/\partial\omega \propto 1/\Omega_c^2$. In the limit of small Ω_c the following expression for v_g therefore holds:

$$v_g = \frac{\hbar c \varepsilon_0 [\Omega_c]^2}{2\omega_d |\mu_{13}|^2 N} \qquad [21]$$

Extremely low group velocities, down to a few meters per second, are achieved in this limit using excitation of the hyperfine split ground states in either laser cooled atomic samples or Doppler-free configurations in finite temperature samples. Recently similar light slowing has been observed in solids. Storage of the optical pulse within the medium has also been achieved by adiabatically switching off the coupling field and thus trapping the optical excitation as an excitation within the hyperfine ground states for which the storage time can be very long (>1 ms) due to very low dephasing rates. Since the storage scenario should be valid even for single photons this process has attracted considerable attention recently as a means to enable quantum information storage.

Extremely low values of Ω_c are sufficient to induce complete transparency (albeit in a very narrow dip) and at this location the nonlinear response is resonantly enhanced. Very high efficiency nonlinear frequency mixing and phase conjugation at low light levels have been reported under these conditions. It is expected that high-efficiency nonlinear optical processes will persist to ultralow intensities (the few photon level) in an EIT medium of this type.

One example of highly enhanced nonlinear interactions is the predicted large values of the Kerr type nonlinearity (nonlinear refractive index). The origin of this can be seen by considering the steep dispersion profile in the region of the transparency dip in Figure 4. Imagine that we apply an additional field ω_f, perhaps a very weak one, at a frequency close to resonance between state |2> and a fourth level |4>. The ac Stark shift caused by this new field to the other three level, although small, will have a dramatic effect upon the value of the refractive index because of the extreme steepness of the dispersion profile. Essentially even a very small shift of the resonant wavelength causes a large change in the refractive index for a field applied close to this frequency. It is predicted that strong cross-phase modulations will be created in this process between the fields ω_f and ω_d, even in the quantum limit for these fields. This is predicted to lead to improved schemes for quantum nondemolition measurements of photons through the measurement of the phase-shifts they induce (through cross-phase modulation) on another quantum field. This type of measurement has direct application in quantum information processing.

See also

Nonlinear Optics, Applications: Phase Matching; Raman Lasers. **Scattering:** Raman Scattering.

Further Reading

Arimondo E (1996) Coherent population trapping in laser spectroscopy. *Progress in Optics* 35: 257–354.

Harris SE (1997) Electromagnetically induced transparency. *Physics Today* 50: 36–42.

Harris SE and Hau LV (1999) Non-linear optics at low light levels. *Physical Review Letters* 82: 4611–4614.

Harris SE, Field JE and Imamoglu A (1990) Nonlinear optical processes using electromagnetically induced transparency. *Physical Review Letters* 64: 1107–1110.

Hau LV, Harris SE, Dutton Z and Behroozi CH (1999) Light speed reduction to 17 metres per second in an ultra-cold atomic gas. *Nature* 397: 594–598.

Marangos JP (2001) Electromagnetically induced transparency. In: Bass M, *et al.* (ed.) *Handbook of Optics*, vol. IV, ch. 23. New York: McGraw-Hill.

Merriam AJ, Sharpe SJ, Xia H, *et al.* (1999) Efficient gas-phase generation of vacuum ultra-violet radiation. *Optics Letters* 24: 625–627.

Schmidt H and Imamoglu A (1996) Giant Kerr nonlinearities obtained by electromagnetically induced transparency. *Optics Letters* 21: 1936–1938.

Scully MO (1991) Enhancement of the index of refraction via quantum coherence. *Physical Review Letters* 67: 1855–1858.

Scully MO and Suhail Zubairy M (1997) Quantum Optics. Cambridge, UK: Cambridge University Press.

Sokolov AV, Walker DR, Yavuz DD, *et al.* (2001) Femtosecond light source for phase-controlled multi-photon ionisation. *Physical Review Letters* 87: 033402-1.

Zhang GZ, Hakuta K and Stoicheff BP (1993) Nonlinear optical generation using electromagnetically induced transparency in hydrogen. *Physical Review Letters* 71: 3099–3102.

ENVIRONMENTAL MEASUREMENTS

Contents

Doppler Lidar
Hyperspectral Remote Sensing of Land and the Atmosphere
Laser Detection of Atmospheric Gases
Optical Transmission and Scatter of the Atmosphere

Doppler Lidar

R M Hardesty, National Oceanic and Atmospheric Administration, Boulder, CO, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Lidars developed for the measurement of atmospheric winds make use of the Doppler effect, in which radiation scattered or emitted from a moving object is shifted in frequency as a result of the movement of the particles. Atmospheric Doppler lidars irradiate a volume of atmosphere with a pulse of very narrowband, laser-produced radiation, then detect the change in frequency of the radiation backscattered from atmospheric aerosol particles or molecules present in the volume. Although Doppler lidars are conceptually similar to Doppler weather radars, lidar wavelengths are 3–4 orders of magnitude shorter than radar wavelengths, producing some important differences in propagation and scattering characteristics. Radiation at wavelengths in the optical region of the spectrum is efficiently scattered by aerosols and molecules, therefore Doppler lidars, unlike commonly used Doppler weather radars, do not require the presence of hydrometeors or insects to obtain useful results. Also, optical radiation can be tightly collimated, virtually eliminating effects of ground clutter and enabling lidar probing of small volumes to within a few meters of terrain or structures.

The primary disadvantage of lidar techniques is the severe attenuation of the optical radiation by cloud water droplets and fog. Doppler lidars do not typically probe beyond the edge of most atmospheric clouds – the one exception being tenuous ice clouds such as cirrus, which often are characterized by low optical extinction and high backscatter, making them excellent lidar targets. Doppler lidars also do not have the extended range, which can exceed 100 km, available from contemporary meteorological radars when scatterers are present.

In clear air, however, the characteristics and capabilities of Doppler lidar are well suited for obtaining detailed wind and turbulence observations for a wide variety of applications. Lidar beams can be easily scanned to characterize motions within very confined three-dimensional spaces such as shallow atmospheric boundary layers, narrow canyons, and turbulent structures. The relative compactness of Doppler lidars makes deployment on aircraft or other moving platforms extremely viable, and a Doppler lidar deployed on a satellite has been proposed as a way to obtain global measurements of atmospheric wind fields. By scanning a lidar beam from an orbiting satellite and analyzing the returns backscattered from clouds, aerosols, and molecules, a satellite-based instrument could provide important wind information for numerical forecast models.

Doppler Lidar Fundamentals

Backscattered Light

As laser light propagates through the atmosphere, some of the incident energy is scattered by the atmospheric molecules and constituents through which the light passes. In lidar applications, the light backscattered (scattered directly back toward the source) is collected and analyzed. The backscattering properties of an atmospheric particle depend on its refractive index, shape, and size. In the special case when the particle is much smaller than the wavelength of the incident radiation, as is the case for laser radiation scattered by atmospheric molecules, the scattering process is characterized as Rayleigh scattering. Because, in the Rayleigh scattering regime the energy backscattered by a particle increases proportionally as the inverse of the fourth power of the wavelength, Doppler lidar systems designed for molecular scatter operate at short wavelengths. Molecular Doppler lidar systems typically operate in the visible or ultraviolet spectral regions.

Aerosol particles, the other component of the atmosphere that scatters laser light, produce Mie scattering, which applies when the diameter of the scatterers is not orders of magnitude smaller than the incident wavelength. Aerosol particles present in the atmosphere include dust, soot, smoke, and pollen, as well as liquid water and ice. Although for Mie scattering the relationship between the power backscattered by an ensemble of aerosol particles and the incident wavelength is not simply characterized, most studies have shown that the energy backscattered increases roughly proportional to the first or second power of the inverse of the incident wavelength, depending on the characteristics of the scattering aerosol particles. In a polluted environment, such as in the vicinity of urban areas, an abundance of large particles often results in a roughly linear relationship between the inverse of the incident wavelength and the backscattered energy, while in more pristine environments, such as the free troposphere, the inverse wavelength/backscatter relationship can approach or exceed a square-law relationship.

The primary objective in Doppler lidar is to measure the Doppler frequency shift of the scattered radiation introduced by the movements of the scattering particles. Figure 1 shows a typical spectrum of the radiation collected at the lidar receiver for a volume of atmosphere irradiated by a monochromatic laser pulse. Molecular scattering produces the broadband distribution in Figure 1, where the broadening results from the Doppler shifts of the radiation backscattered from molecules moving at their thermal velocities. The width of the molecular velocity distribution in the atmosphere ranges from ~320 to 350 m s^{-1}, scaling as the square root of the temperature. In the center of the spectrum is a much narrower peak resulting from scattering of the light by aerosol particles. Because the thermal velocity of the much larger aerosol particles is very low, the width of the distribution of the aerosol return is determined by the range of velocities of particles moved about by small-scale turbulence within the scattering volume. This is typically on the order of a few m s^{-1}. Also shown in Figure 1 is an additional broadband distribution, due to scattered solar radiation collected at the receiver. If the laser source is not monochromatic, the backscattered signal spectrum is additionally broadened, with the resulting spectrum being the convolution of the spectrum shown in Figure 1 with the spectrum of the laser pulse. As seen in the figure, the entire spectrum is Doppler-shifted in frequency, relative to the frequency of the laser pulse. The object for a Doppler lidar system is to measure this shift, given by $\delta f = 2v_{\mathrm{rad}}/\lambda$, where v_{rad} is the component of the mean velocity of the particles in the direction of propagation of the lidar pulse and λ is the laser wavelength.



Figure 1 Distribution of wind velocities in a lidar return, showing Doppler shift resulting from wind-induced translation of the scatterers. The ratio of aerosol to molecular signals increases with increasing wavelength.

Elements of a Doppler Lidar

Doppler lidar systems can be designed primarily to measure winds from aerosol-scattered radiation, molecule-scattered radiation, or both. The type of system places specific requirements on the primary components that comprise a Doppler lidar system. A Doppler lidar consists of a laser transmitter to produce pulses of energy that irradiate the atmospheric volume of interest, a receiver which collects the backscattered photons and estimates the energy and Doppler shift of the return, and a beam pointing mechanism for directing the laser beam and receiver field of view together in various directions to probe different atmospheric volumes. Independent of whether the primary scatterers are molecules or aerosol particles, the system design criteria for a Doppler system are driven by a fundamental relationship between the error in the estimate of mean frequency shift δf_1, the bandwidth of the return f_2 (proportional to the distribution of velocities), and the number of incident backscattered photons detected N as

$$\delta f_1 \propto f_2/N^{1/2} \qquad [1]$$

Thus, the precision of the velocity estimate is improved by increasing the number of detected signal photons and/or decreasing the bandwidth of the backscattered signal. It is obvious from the equation that a significantly greater number of photons are required to achieve the same precision in a Doppler measurement from a molecular backscattered signal, characterized by higher bandwidth f_2, compared to the number required to compute velocities from aerosol returns. The improved measurement precision gained from a narrow bandwidth return also indicates that the laser transmitter in a Doppler lidar system should be characterized by narrow spectral width (considerably narrower than the spectral broadening caused by the distribution of velocities), and to increase the number of photons detected, maximum transmit energy.

Narrowband, single-frequency pulses are obtained by employing a low-power, precisely frequency-stabilized master oscillator laser, whose radiation is either used to seed a stabilized, higher-energy laser cavity (injection seeding) or amplified in one or more optical amplifiers (master-oscillator, power amplifier, (MOPA)) to produce frequency-stabilized pulses.

The lidar receiver gathers the backscattered photons and extracts the wind velocity as a function of the range to the scattering volume. This requires a telescope, to gather and focus the scattered radiation, and a receiver to detect the scattered radiation and determine the Doppler shift. Frequency analysis in a Doppler lidar receiver is carried out using one of two techniques: coherent detection (also known as heterodyne detection) or direct detection (alternately labeled incoherent detection). The techniques differ fundamentally. In a heterodyne receiver, frequency analysis is carried out on a digitized time series created by mixing laser radiation with the backscattered radiation, while in direct detection lidar an interferometer optically analyzes the backscattered radiation to produce a light pattern which contains the information on the frequency content.

Coherent (Heterodyne) Doppler Lidar

Description

Coherent or heterodyne lidar is implemented by optically mixing the backscattered laser light with radiation from a stable, continuous-wave, local oscillator (LO) laser whose frequency is precisely controlled to be a known frequency offset, typically on the order of tens of MHz, from that of the laser transmitter (Figure 2). The mixing process at the face of an optical detector generates, after high pass filtering, an electrical signal with amplitude proportional to amplitude of the backscattered electromagnetic field and frequency equal to the difference between the backscattered field frequency and the LO laser field frequency. This signal is sampled, and then digitally processed to estimate the range-dependent mean frequency shift of the backscattered signal, from which the radial wind component can be derived. A property of coherent lidar is that, because of constructive and destructive interference of the returns from individual scatterers, single pulse returns are characterized by random fluctuations in the amplitude and phase of the detected time series and Fourier spectrum. Consequently, averaging (sometimes referred to as accumulation) over multiple pulses usually is necessary to produce a sufficiently precise estimate of the signal mean frequency estimate. Because the phase of the detected time series is random within each pulse, averaging must be carried out in the power spectrum or autocorrelation function domain, rather than on the detected time series.



Figure 2 Schematic of coherent detection of backscattered radiation.

The optical mixing process in coherent Doppler lidar provides both benefits and design challenges. Because receiver efficiencies (equivalent fraction of incident photons entering the receiver that are converted to electrons) are quite high, wind velocities can be estimated from very weak backscattered signals. Also, signal processing is performed on a time series derived from the mixed signal, enabling the use of electrical filters to produce a narrow receiver bandwidth and effectively eliminating broadband solar background light as a major source of noise. As a result, unlike many lidars coherent Doppler lidar performance is not degraded under daylight conditions.

The primary limitation of coherent detection results from the added photon noise from the local oscillator radiation (which is usually much stronger than the backscattered radiation). The effect of local oscillator photon noise is to define a system noise level below which very weak signals cannot be practically extracted, even with substantial multiple-pulse averaging. In addition, because efficient mixing requires phase coherence of the backscattered signal field across the detector, coherent lidar performance at longer ranges is degraded by strong optical turbulence along the path of the laser pulse. These adverse effects of turbulence increase for shorter wavelength systems.

Although measurements at wavelengths near 1.06 μm have been demonstrated, coherent Doppler lidar systems used for regular atmospheric probing operate in the eye-safe, infrared portion of the spectrum at wavelengths longer than 1.5 μm. Currently, the two most common system wavelengths for coherent lidar wind systems are in atmospheric window spectral regions around 2 and 10.6 μm. Early coherent Doppler lidar measurements, beginning in the 1970s, employed CO_2 laser transmitters and local oscillators operating at wavelengths near 10.6 μm. Pulsed CO_2 laser transmitters with as much as 10 J of energy have since been demonstrated, and systems with 1 J lasers have probed the atmosphere to ranges of 30 km or more. In the late 1980s, solid state laser transmitters operating near 2 μm wavelengths were introduced into coherent lidar wind-measuring systems. The compact size and potential reliability advantages of solid-state transmitters, in which the transmitter laser is optically pumped by an array of laser diodes, provide advantages over larger CO_2 laser technology. Also, because for a given measurement accuracy the range-resolution obtainable is proportional to wavelength, 2 μm instruments have an enhanced capability to probe small-scale features. However, although development of higher energy, single-frequency coherent lidar sources operating at 2 μm region, as well as at 1.5 μm, is currently an active research area, solid state lasers with pulse energies greater than several tens of mJ have yet to be incorporated into lidar systems for atmospheric probing.

Applications of Coherent Doppler Lidar

Coherent lidars have been used to measure winds for a variety of applications, and from an assortment of platforms, such as ships and aircraft. Since these lidars operate in the infrared where aerosol scattering dominates molecular scattering, they require aerosol particles to be present at some level to obtain usable returns. Although clouds also provide excellent lidar targets, most of the more useful applications of coherent lidars involve probing the atmospheric boundary layer or lower troposphere where aerosol content is highest. Because of the capability to scan the narrow lidar beam directly adjacent to terrain, a unique application of lidar probing is the measurement of wind structure and evolution in complex terrain such as mountains and valleys. Over the past two decades, Doppler lidar studies have been used, for example, to study structure of damaging windstorms on the downwind side of mountain ranges, advection of pollution by drainage flows from valleys, and formation of mountain leeside turbulence as a potential hazard to landing aircraft. The interactions of wind flows with complex terrain can produce dangerous conditions for transportation, especially aircraft operations. Figure 3 shows a strong mountain wave measured by a Doppler lidar near Colorado Springs, during an investigation of the effects of downslope winds and turbulence on aircraft operations at the Colorado Springs airport. The mountains are on the right of the figure, where the strong wave with wavelength of about 6 km can be seen. Note the reversal in winds near the location where the wave descends to the surface. The Colorado Springs study was prompted by the crash of a passenger jet while landing at the airport during a period when the winds were down the slope of the Rocky Mountains just to the west of the airport.

A Doppler lidar was recently deployed in an operational mode for wind shear detection at the new Hong Kong International Airport. Because winds flowing over mountainous terrain just south of the



Figure 3 Vertical scan of the winds in a mountain wave measured by a 10.6 μm coherent Doppler lidar near Colorado Springs, Colorado. Courtesy L. Darby, NOAA.

airport can produce mountain waves and channeled flows, wind shear is frequently encountered during landing and takeoff operations. Figure 4 shows a gust front situated just to the west of the airport, characterized by a sharp wind change (which would produce a corresponding change in airspeed) approaching 13 m s^{-1} over a distance of less than one kilometer. Providing a capability to detect such events near the airport and warn pilots during approach or preparation for takeoff was the primary reason for deployment of the lidar. Within the first year of operation the Hong Kong lidar was credited with improving wind shear detection rates and providing more timely warnings for pilots of the potentially hazardous conditions. As of August 2003 this lidar had logged more than 10 000 hours of operation.

Because coherent Doppler lidars are well matched to applications associated with probing small-scale, turbulent phenomena, they have also been deployed at airports to detect and track wing tip vortices generated by arriving or departing aircraft on nearby parallel runways. In the future, a network of ground-based lidars could provide information on vortex location and advection speed as well as wind shear, leading to a potential decrease in congestion at major airports. Also, compact lidar systems looking directly ahead of research aircraft have shown the capability to detect wind changes associated with potentially hazardous clear-air turbulence. In the future, a Doppler lidar installed on the commercial aircraft fleet could potentially look ahead and provide a warning to passengers to fasten seat belts before severe turbulence is encountered.

The high resolution obtainable in a scanning lidar enables visualization of finely structured wind and turbulence layers. Figure 5 shows an image of turbulence associated with a nocturnal low-level jet just 50 m above the surface obtained at night over flat



Figure 4 Horizontal depiction of the radial component of the wind field measured at Hong Kong Airport by a 2.02 μm Doppler lidar during a gust front passage, showing strong horizontal shear just west of the airport. Courtesy C. M. Shun, Hong Kong Observatory.



Figure 5 Turbulence structure within a nocturnal stable layer at a height of 50 m. Note the stretching of the vertical scale. Courtesy R. Banta, NOAA.

terrain in Kansas. Although a low-level jet was present on just about every evening during the experiment, similar images obtained at different times by the Doppler lidar illustrated markedly different characteristics, such as a wide variation in the observed mechanical turbulence along the interface. Such observations enable researchers to improve parameterizations of turbulence in models and better understand the conditions associated with vertical turbulent transport and mixing of atmospheric constituents such as pollutants.

By deploying Doppler lidars on moving platforms such as ships and aircraft, the spatial coverage of the measurements can be greatly increased. Although removal of platform motion and changes in orientation are not trivial, aircraft-mounted lidar can map out such features as the low-level jet and the structure of boundary layer convective plumes. Figure 6 shows horizontal and vertical motions associated with convective plumes measured along an approximately 60 km path over the southern Great Plains of the United States. From such measurements estimates of turbulence intensity, integral scale, and other boundary layer characteristics can be computed.

Direct Detection Doppler Lidar

Description

Direct detection or incoherent Doppler lidar has received significant attention in recent years as an alternative to coherent lidar for atmospheric wind measurements. In contrast to coherent lidar, in which an electrical signal is processed to estimate Doppler shift, an optical interferometer, usually a Fabry–Perot etalon, serves as the principal element in a direct detection lidar receiver for determining the frequency shift of the backscattered radiation.

One implementation of a direct-detection Doppler lidar receiver is the ‘fringe imaging’ technique. In this design, the interferometer acts as a spectrum analyzer. The backscatter radiation is directed through a



Figure 6 Vertical motion in convective plumes measured by a vertically pointing airborne coherent Doppler lidar. Total horizontal extent of the measurements is approximately 60 km, reddish colors correspond to upward motions.



Figure 7 Schematic of Fabry–Perot etalon in a direct detection, fringe-imaging lidar receiver. Courtesy P. Hays, Michigan Aerospace Corporation.

Fabry–Perot interferometer, which produces a ring pattern in the focal plane (Figure 7). The spectral content information of the incident radiation is contained in the radial distribution of the light. Each ring corresponds to an order of the interferometer and is equivalent to a representation of the backscattered signal frequency spectrum. As the mean frequency of the backscattered radiation changes, the rings move inward or outward from the center. To extract a spectrum of the backscattered light, one or more of the rings are imaged onto a two-dimensional detector, and the resulting pattern analyzed. The rings can either be detected using a multi-element ring detector, or can be converted to a linear pattern with a circle-to-line converter optic and then imaged on to a charge-coupled device array device.

An alternate direct detection receiver configuration, generally called the double edge technique, is to employ two interferometers as bandpass filters, with the center wavelength of each filter set above and below the laser transmitter wavelength, as shown in Figure 8. The incoming radiation is split between the two interferometers, and the wavelength shift is computed by examining the ratio of the radiation transmitted by each interferometer. Both the double edge and fringe-imaging techniques have demonstrated wind measurements to heights well into the stratosphere. The major challenge associated with the double edge receiver is optimizing the instrument when both aerosol and molecular scattered radiation are present, since in general the change in transmission as a function of velocity is different for the aerosol and molecular signals. Double edge receivers optimized for both aerosol and molecular returns place the bandpass of the etalon filters at the precise wavelength where the change in transmission with change in Doppler shift is the same for both aerosol and molecular returns.

For both types of direct detection receivers described above, much of the radiation incident on the interferometer is reflected out of the system, reducing the overall efficiency of the receiver. Recently, designs that incorporate fiber optics to collect a portion of the reflected radiation and 'recycle' it back into the etalon have been demonstrated as a method to improve the transmission efficiency of the etalon in a fringe imaging receiver.



Figure 8 Spectrum of molecular lidar return showing placement of bandpass filters for a dual channel (double edge) direct detection receiver. Courtesy B. Gentry, NASA.

Doppler Wind Measurements Based on Molecular Scatter

One of the primary advantages of direct detection Doppler lidar is its capability for measurements based on scatter from atmospheric molecules. Measurement of Doppler shifts from molecular scattered radiation is challenging because of the large Doppler-broadened bandwidth of the return. Because one wants to measure a mean wind velocity with a precision of a few m s^{-1} or better, in the order of 10^5 photons are required. Some combination of multiple pulse averaging, powerful lasers, and large receiver optics is required to obtain these high photon counts from backscattered returns.

Molecular-scatter wind measurements have been demonstrated in the visible spectral region at 532 nm wavelength as well as at 355 nm in the near ultraviolet. The ultraviolet region has the dual advantages of enhanced molecular scatter and less restrictive laser eye-safety restrictions. Figure 9 shows the time series of a wind profile measured in the troposphere from both aerosols and clouds using a molecular-scatter, ground-based 355-nm wavelength Doppler fringe-imaging lidar. The figure shows measurements from receiver channels optimized for the wideband molecular signal and the narrowband aerosol return. For this measurement, backscattered photons were collected by a 0.5 m receiver aperture, averaged for 1 minute, and processed. In the absence of clouds, direct detection Doppler lidars have measured wind profiles continuously from the surface to beyond 15 km height. Figure 10 shows that the estimated wind error for the same 355 nm lidar is less than 1 m s^{-1} to about 10 km, and less than 4 m s^{-1} at 15 km height.

Heterodyne and Direct-Detection Doppler Trade-Offs

Lively debates within the lidar community have occurred over the past decade regarding the relative merits of heterodyne versus direct detection Doppler lidars. To a large extent, the instruments are complementary. Generally, heterodyne instruments are much more sensitive when significant aerosols are present. Coherent lidar processing techniques have been developed that can produce accurate wind measurement rates using only a few lidar pulses with as few as 100 detected photons, such that several wind observations per second can be obtained for nominal pulse rates. This inherent sensitivity has led to numerous applications in which a lidar beam has been scanned rapidly over a large volume to obtain time-varying, three-dimensional wind measurements.



Figure 9 Time series of radial wind speed profiles measured by a 355 nm fringe-imaging direct detection lidar aerosol channel (top) and molecular channel (bottom) at Maura Loa Observatory, HI. Change in wind speed and blocking of the return by clouds is clearly seen. Courtesy C. Nardell, Michigan Aerospace Corp.

The primary advantage of direct detection instruments is their demonstrated capability to measure winds from molecular-backscattered returns in the middle and upper troposphere. In very pristine air, direct detection offers the only method for long-range wind measurements, even though significant averaging may be required. Direct-detection lidars have the additional advantage of being unaffected by atmospheric refractive turbulence. Unlike heterodyne lidars, which require a very pure laser pulse and a diffraction-limited receiver field of view matched to and precisely aligned with the transmitted beam, direct detection systems can have a wider bandwidth transmitter and a receiver field of view several times diffraction-limited. In direct detection lidar design, the field of view is usually constrained by the need to limit background light during daytime operation. A major design challenge for direct detection instruments is holding the Fabry–Perot etalon plate spacing stable over a range of temperatures and in high vibration environments.

Global Wind Measurements

A satellite-based Doppler lidar has frequently been proposed as a way to measure wind fields over most of the Earth. At present, winds are the one major meteorological variable not well-measured from orbiting platforms. Measurement of winds is especially important over regions of the Earth that are not currently well sampled, such as over Northern Hemisphere oceans, as well as over most of the tropics and Southern Hemisphere. Wind profile information is currently obtained from radiosondes and by tracking cloud and water vapor inhomogeneities using satellite imagers. Doppler lidar wind measurements would greatly augment the current data set by providing wind estimates throughout the troposphere under clear conditions, and highly height-resolved observations down to cloud tops when cloud decks are present. Observing system simulation experiments conducted in recent years indicate that satellite-based lidar global wind



Figure 10 Estimated error in the radial velocity estimate versus altitude for a 355 nm direct detection, fringe imaging Doppler lidar system at Mauna Loa observatory on Hawaii. The lidar provides data for assimilation into local mesoscale forecast models. Courtesy C. Nardell, Michigan Aerospace Corp.

measurements could lead to a significant improvement in long-term forecast skill, provided the wind fields can be observed with sufficient accuracy and spatial resolution.

In a Doppler lidar wind mission, a satellite carrying a lidar system would orbit the Earth in a nearly polar orbit. The pulsed laser beam would be scanned conically about the nadir to obtain different components of the wind velocity. The scanning could be either continuous or 'stop and stare'. After sufficient returns are averaged at a given pointing angle to produce an acceptable estimate, the radial component of the velocity would be computed and assimilated directly into numerical analysis and forecast models.

Doppler lidar measurement of winds from space is theoretically feasible but technologically difficult. Depending on the orbital height, the scattering volume is anywhere from 450 to ~850 km from the satellite, which challenges the sensitivity of current system types. Because weight and power consumption are critical parameters for space systems, telescope diameter and laser power cannot be easily increased to obtain the necessary sensitivity. Similarly, the ability to average returns from multiple pulses is also limited by time limitations. Because a satellite moves at about 7 km s^{-1}, in order to obtain measurements over a horizontal distance of 300 km (the resolution of the radiosonde network) only about 45 seconds are available to make enough observations from multiple look angles to obtain a useful measurement. It should also be noted that, as a result of the high orbital velocity of the satellite, precise knowledge of beam pointing is extremely critical for measurements from satellites. For a lidar operating at a nadir angle of 45 degrees, an error in the knowledge of pointing angle of just 1 mrad results in an error of about 5 ms^{-1} in the measured radial component of the wind.

Despite the challenge of employing a satellite-based Doppler lidar, efforts are continuing to develop the appropriate technology and to assess the impact of the observations. The European Space Agency is planning a Doppler wind lidar demonstration mission for the late 2000s that would incorporate a nonscanning, direct-detection instrument with both aerosol and molecular channels. Doppler lidar technology research and numerical simulations aimed at satellite-based wind sensing is ongoing at several research centers within the United States, Europe, and Japan. One option currently being studied is a 'hybrid' lidar system that would combine a direct detection lidar for measurement of winds in the clear free troposphere with a low-energy coherent system that would obtain its observations from clouds and the aerosol-rich boundary. Although a hybrid instrument reduces some requirements on system power and aperture size, combining the two techniques on a single platform will likely require innovative engineering and new approaches to beam combining and scanning.

See also

Environmental Measurements: Optical Transmission and Scatter of the Atmosphere. **Scattering:** Scattering Theory.

Further Reading

Baker WE, Emmitt GD, Robertson F, *et al.* (1998) Lidar-measured wind from space: a key component for weather and climate prediction. *Bulletin of the American Meteorological Society* 79: 581–599.

Banta RM, Olivier LD and Levinson DH (1993) Evolution of the Monterey Bay sea breeze layer as observed by pulsed Doppler lidar. *Journal of Atmospheric Science* 50 (24): 3959–3982.

Banta RM, Olivier LD, Gudiksen PH and Lange R (1996) Implications of small-scale flow features to modeling dispersion over complex terrain. *Journal of Applied Meteorology* 35: 330–342.

Banta RM, Darby LS, Kaufmann P, Levinson DH and Zhu C-J (1999) Wind flow patterns in the Grand Canyon as revealed by Doppler lidar. *Journal of Applied Meteorology* 38: 1069–1083.

Frehlich R (1996) Coherent Doppler lidar measurements of winds in the weak signal regime, 1997. *Applied Optics* 36: 3491–3499.

Gentry B, Chen H and Li SX (2000) Wind measurements with a 355 nm molecular Doppler lidar. *Optics Letters* 25: 1231–1233.

Grund CJ, Banta RM, George JL, *et al.* (2001) High-resolution Doppler lidar for boundary-layer and cloud research. *Journal of Atmosphere and Oceanic Technology* 18: 376–393.

Huffaker RM and Hardesty RM (1996) Remote sensing of atmospheric wind velocities using solid state and CO_2 coherent laser systems. *Proceedings of the IEEE* 84: 181–204.

Menzies RT and Hardesty RM (1989) Coherent Doppler lidar for measurements of wind fields. *Proceedings of the IEEE* 77: 449–462.

Post MJ and Cupp RE (1990) Optimizing a pulsed Doppler lidar. *Applied Optics* 29: 4145–4158.

Rees D and McDermid IS (1990) Doppler lidar atmospheric wind sensor: reevaluation of a 355 nm incoherent Doppler lidar. *Applied Optics* 29: 4133–4144.

Rothermel J, Cutten DR, Hardesty RM, *et al.* (1998) The multi-center airborne coherent lidar atmospheric wind sensor. *Bulletin of the American Meteorological Society* 79: 581–599.

Skinner WR and Hays PB (1994) Incoherent Doppler lidar for measurement of atmospheric winds. *Proceedings of SPIE* 2216: 383–394.

Souprayen C, Garnier A and Hertzog A (1999) Rayleigh–Mie Doppler wind lidar for atmospheric measurements. II: Mie scattering effect, theory, and calibration. *Applied Optics* 38: 2422–2431.

Souprayen C, Garnier A, Hertzog A, Hauchecorne A and Porteneuve J (1999) Rayleigh–Mie Doppler wind lidar for atmospheric measurements. I: Instrumental setup, validation, first climatological results. *Applied Optics* 38: 2410–2421.

Hyperspectral Remote Sensing of Land and the Atmosphere

W H Farrand, Space Science Institute, Boulder, CO, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Hyperspectral remote sensing is a true marriage of imaging technology with spectroscopy. Hyperspectral remote sensing systems (also known as imaging spectrometer systems) fully sample the optical wavelength range of interest, whether it be the reflected solar range (0.35 to 2.5 μm) or the range of thermal emission from the Earth's surface (3.0 to 14 μm). A hyperspectral sensor views the Earth's surface in a series of contiguous and spectrally narrow image bands. Figure 1 presents the concept of hyperspectral remote sensing, wherein each spatial element of an image has an associated full resolution spectrum. The calibrated reflectance or emittance spectra collected by a hyperspectral system are meant to be directly comparable with that of materials measured in the laboratory. With such high spectral resolution, it thus becomes possible to do reflectance or emittance spectroscopy of the Earth's surface from an overhead perspective.

Underlying Principles

Optical remote sensing is done over wavelength intervals, or windows, in which the atmosphere is largely transparent. For the reflective solar portion of the spectrum, the atmosphere is mostly transparent from approximately 0.35 to 2.5 μm. Water, CO_2, and other gases have absorptions of varying strength in this range. This window is subdivided into the range of human vision (the visible) and the region of slightly longer wavelengths known as the near infrared; together they are the visible/near infrared or VNIR and extend from approximately 0.35 to 1.0 μm. The region from approximately 1.0 to 2.5 μm is known as the short wavelength infrared or SWIR. In the range of emitted terrestrial radiation there are two window regions. The first extends from approximately 3 to 5 μm and is known as the medium wavelength infrared or MWIR, and the second, the long wavelength infrared or LWIR, extends from approximately 8 to 14 μm.

The light that is intercepted by the entrance aperture of a sensor is known by the quantity of radiance which is measured in units of microwatts per square centimeter per nanometer per unit of solid angle. Physical quantities related to the material properties of Earth surface materials are reflectance and emittance. Both properties are the result of ratios and so are unitless. One definition of reflectance is that it is the ratio of radiance reflected from a material, divided by the radiance reflected from an identically illuminated perfectly diffuse reflector. Likewise, a definition for emittance is the ratio of radiance emitted from a material, divided by the ratio


Each pixel has an associated continuous spectrum that can be used to identify the surface materials
Images taken simultaneously in 100 – 200 spectrally contiguous and spatially registered spectral bands
Reflectance
0.4
Wavelength (μm)
2.5

Figure 1 Hyperspectral remote sensing concept.

of radiance emitted from a perfectly emitting material of the same temperature.

Materials covering the Earth's surface, or gases in the atmosphere, can be identified in hyperspectral data on the basis of absorption features, or bands, in the spectra recorded by the sensor. Absorption bands result from the preferential absorption of energy in some wavelength interval. The principal types of processes by which light can be absorbed include, in order of decreasing energy of the process, electronic charge transfers, electronic crystal field effects, and molecular vibrations. The former two processes are observed in minerals and manmade materials that contain transition group metal cations, most usually, iron. Charge transfer absorptions are the result of cation-to-anion or cation-to-cation electron transfers. Crystal field absorptions are explainable by the quantum mechanical theory of atomic structure, wherein an atom's electrons are contained in orbital shells. The transition group metals have incompletely filled *d* orbital shells. When a transition metal cation, such as iron, is surrounded by anions, and potentially selects other cations, an electric field, known as the crystal field, exists. Crystal field absorptions occur when radiant energy causes that cation's orbital shell energy levels to be split by interaction with the crystal field. The reflectance spectra of different iron-bearing minerals are unique, because the iron cation has a unique positioning with respect to the anions and other cations that compose the mineral.

A material's component molecules have bonds to other molecules and as a result of interaction with radiant energy, these bonds can stretch or bend. These molecular vibrations, and overtones of those vibrations, are less energetic processes than the electronic absorption processes described above and so the resulting absorption features occur at longer wavelengths. Fundamental vibrational features occur in the MWIR and LWIR. Overtones and combination overtones of these vibrations are manifested as weaker absorption features in the SWIR. These overtone features in the SWIR include absorptions diagnostic of carbonate and certain clay minerals. Absorption features caused by vibrational overtones of C–H, O–H, and N–H stretches are also manifested in the SWIR and these absorption features are characteristic of important vegetative biochemical components such as cellulose, lignin, starch, and glucose. An example of the effect of the changes in reflected energy recorded at a sensor, due to the absorption of incident energy by green vegetation and other surface materials, is provided in Figure 2.

Laboratory spectrometers have been used for many years to analyze the diagnostic absorptions of materials caused by the above effects. More recently, spectrometers were mounted on telescopes to determine the composition of the Moon and the other solid bodies in our solar system. Technology progressed to where profiling spectrometers (instruments that measure a successive line of points on the surface) could be mounted on aircraft. The next logical step was the construction of imaging spectrometers (hyperspectral sensors) that measured spectra in two spatial dimensions. In fact, the data produced by a hyperspectral sensor are often thought of as an image cube (Figure 3) because they consist of three dimensions: two spatial and one spectral.



Figure 2 Portion of a scene from the Airborne Visible/Infrared Imaging Spectrometer (AVIRIS) from Utah that includes a basalt flow, circularly irrigated grasses sparsely vegetated plains, and damp alluvial sediments. AVIRIS channels centered at 0.45, 0.55, 0.81, and 2.41 μm are shown. Green vegetation is brightest in the 0.81 μm band which samples the peak of the near infrared plateau (see **Figure 7**) just beyond the 'red edge'. The green vegetation and damp sediments are darkest in the 2.41 μm band where water has a very low reflectance (note also **Figure 8**). The bright patches in the basalt flow in the 2.41 μm image are occurrences of oxidized red cinders which have a high reflectance in the SWIR.



Figure 3 Visualization of a hyperspectral image cube. A 1.7 μm image band from the Airborne Visible/Infrared Imaging Spectrometer (AVIRIS) over the Lunar Crater Volcanic Field, Nevada is shown with each of the 224 rightmost columns and 224 topmost lines arrayed behind it. In the lower right-hand corner, the low reflectance of ferric oxide-rich cinders in the blue and green show up as dark in the stacking of columns with the high reflectance in the infrared showing up as bright.

Advances in hyperspectral sensor technology have been accompanied by advances in associated technologies, such as computing power and the evolution of data processing algorithms.

Data Processing Approaches

An early impediment to the widespread use of hyperspectral data was the sheer volume of the data sets. For instance, a single scene from NASA's Airborne Visible/Infrared Imaging Spectrometer (AVIRIS) is 614 samples by 512 lines by 224 bands. With its short integer storage format, such a scene takes up 140.8 Mbytes. However, since the dawn of the hyperspectral era, in the 1980s, computing power has expanded immensely and computing tasks, which once seemed prohibitive, are now relatively effortless. Also, numerous processing algorithms have been developed which are especially well suited for use with hyperspectral data.

Spectral Matching

In one class of algorithms, the spectrum associated with each spatial sample is compared against one or a group of model spectra and some similarity metric is applied. The model spectrum can be measured by a laboratory or field portable spectrometer of pure materials or can be a single pixel spectrum, or average of pixel spectra, covering a known occurrence of the material(s) to be mapped. A widely used similarity metric is the Spectral Angle Mapper (SAM). SAM is the angle, θ, obtained from the dot product of the image pixel spectrum, t, and the library spectrum, r, as expressed by

$$\theta = \cos^{-1}\left(\frac{t * r}{\|t\| * \|r\|}\right) \qquad [1]$$

SAM is insensitive to brightness variations and determines similarity based solely on spectral shape. Lower θ values mean more similar spectra.

In a related approach, matching is done, not on the entire spectrum, but rather on characteristic absorption features of the materials of interest. In Figure 4, the geometry of an absorption band is plotted. To map a given mineral, with a specific absorption feature, a high resolution laboratory spectrum is resampled to the spectral resolution of the hyperspectral sensor. The spectrum is subsampled to match the specific absorption feature (i.e., only bands from the short wavelength shoulder of the absorption to the long wavelength shoulder are included). A straight line continuum (calculated, based on a line between the two-band shoulders) is divided out from both the laboratory and the sensor spectra. Contrast between the library and the sensor spectra is mitigated through the use of an additive constant. This constant is incorporated into a set of equations which are solved through the use of standard least squares. The result of such a band-fitting algorithm is two data numbers per spatial sample of the hyperspectral scene. First the band depth (or, alternatively, band area) of the feature is calculated, and second, a goodness-of-fit parameter is calculated. These two parameters are most often combined in a band-depth times goodness-of-fit image. More sophisticated versions of the band-mapping algorithm target multiple absorption features and are, essentially, expert systems.



Figure 4 Parameters that describe an absorption band.

Spectral Mixture Analysis

A fundamentally different methodology for analyzing hyperspectral data sets is to model the measured spectrum of each spatial sample as a linear combination of endmember spectra. This methodology is based on the fact that the ground area corresponding to any given spatial sample likely will be covered by more than one material, with the consequence that the measured reflectance or emittance spectrum is a mixed pixel spectrum. The objective of linear SMA is to try to determine the fractional abundance of the component materials, or endmembers. The basis of linear spectral unmixing is to model the response of each spatial element as a linear combination of endmember spectra. The basis equation for linear SMA is

$$r(x, y) = \alpha \mathbf{M} + \varepsilon \qquad [2]$$

where $r(x, y)$ = the relative reflectance spectrum for the pixel at position (x, y), α = the vector of endmember abundances, $\mathbf{M}$ = the matrix of endmember spectra, and ε = the vector of residuals between the modeled and the measured reflectances. Application of SMA results in a series of fraction images for each endmember wherein the data numbers range, ideally, between 0 and 1. Fraction image pixels with a digital number (DN) of 0 are taken to be devoid of the endmember material. Fraction image pixels with a DN of 1.0 are taken to be completely covered with the endmember material.

Techniques related to SMA have been developed which also map the abundance of a target material on a per pixel basis. These include implementations highly similar to SMA such as Orthogonal Subspace Projection (OSP) wherein, as with SMA, all endmembers must be determined a priori. Other approaches such as Constrained Energy Minimization (sometimes referred to as 'Matched Filter') do not require a priori knowledge of the endmembers. Instead, only the reflectance or emittance spectrum of the target need be known and the undesired spectral background is estimated, and ultimately compensated for, using the principal eigenvectors of the sample correlation or covariance matrix of the hyperspectral scene.

Expert Systems and Artificial Neural Networks

Another means of extracting information from hyperspectral data sets is to use computer approaches that in some way mimic the human thought process. This can take the form of an expert system which applies a set of rules or tests as each pixel spectrum is successively analyzed. For example, if a spectrum has an absorption at 2.2 μm it could tentatively be classified as being caused by a clay mineral. Additionally, if the absorption is a doublet, the specific clay mineral is likely a kaolinite. In practice, expert system codes are lengthy and complex although excellent results can be demonstrated from their use, albeit at the expense of processing time. Another approach in this vein is the use of an artificial neural network (ANN) for data processing. The use of ANNs is motivated by their power in pattern recognition. ANN architectures are well suited for a parallel processing approach and thus have the potential for rapid data processing.

Hyperspectral Remote Sensing of the Land

Geology

Early efforts with airborne hyperspectral sensors focused on geologic remote sensing. This was, at least in part, a consequence of the mineralogic diversity of the Earth's surface and the fact that many minerals have absorption features which are unique and diagnostic of the mineral's identity. The expectation, which was soon borne out by results from these early sensors, was that, given exposure of the surface, mineralogic maps as detailed as the spatial resolution of the sensor could be derived from hyperspectral data. As some of the processing techniques discussed above have become more readily available, it has become possible to produce mineralogic maps from hyperspectral data far more rapidly and cost-effectively than geologic maps produced by standard means (e.g., by walking over the ground and manually noting which lithologies are underfoot).

The propensity for transition metals, most especially iron, to absorb energy through charge transfer and crystal field effects, is noted above. Fe–O and Fe^{2+}–Fe^{3+} charge transfers cause a profound absorption in the reflectance spectrum of Fe-bearing minerals shortwards of 0.4 μm. The wing of this absorption causes the low blue and green reflectance of Fe-bearing minerals. Crystal field bands cause an absorption feature in the 0.9 to 1.0 μm region. The ability to discriminate subtle differences among Fe-bearing minerals in hyperspectral data has proven extremely valuable in applications such as mineral exploration, volcanology, and in the characterization of abandoned mine lands.

In the SWIR, absorptions caused by vibrational overtones of molecular bonds within minerals. These include absorptions in the 2.2 and 2.3 μm region which are characteristic of many Al- and Mg-bearing clay minerals. Absorptions in the SWIR are narrower in width than the Fe-generated crystal field bands discussed previously. In fact, the requirement to efficiently resolve these vibrational overtone absorption bands (which have full width at half maximum (FWHM) bandwidths of 20 to 40 nm) helped to drive the selection of the nominal 10 nm bandwidth of early and most current hyperspectral sensors. Certain clay minerals can be indicators of hydrothermal activity associated with economic mineral deposits; thus, the SWIR is an important spectral region for mineral exploration. Clay minerals, by definition, have planar molecular structures that are prone to failure if subjected to shearing stresses. The ability to uniquely identify and map these minerals, using hyperspectral data, has thus been used to good effect to identify areas on volcanoes and other hydrothermally altered terrains that could be subject to landslides.

Minerals with adsorbed or molecularly bound OH^- and/or water have vibrational overtone absorptions near 1.45 and 1.9 μm, although these features are masked in remotely sensed data by prominent atmospheric water vapor bands at 1.38 and 1.88 μm. The reflectance of water and OH-bearing minerals decrease to near zero at wavelengths longwards of



Figure 5 Reflectance spectra of representative minerals. Kaolinite represents clay minerals with its diagnostic 2.2 μm band caused by an overtone vibration of the Al–OH bond. The 2.335 μm band of calcite is caused by an overtone vibration of the carbonate molecule. The features shortwards of 1.0 μm in the hematite spectrum are caused by crystal field and charge transfer absorptions due to Fe^{3+}. The bands near 1.0 and longwards of 2.0 μm in the augite spectrum are the result of Fe^{2+} crystal field bands.

2.5 μm, due to the presence of water and OH fundamental vibrations near 3.0 μm. Minerals bearing the carbonate (CO_3^{-2}) molecule are abundant on the Earth's surface due to the ubiquitous occurrences of limestone and dolomite. Calcite and dolomite have overtone absorptions centered at 2.335 and 2.315 μm, respectively. A good test for the spectral resolution and spectral calibration of a hyperspectral sensor is its ability to successfully discriminate calcite from dolomite on the basis of the aforementioned absorption features. Figure 5 shows representative spectra of carbonate, clay, and ferric and ferrous iron-bearing minerals.

Absorptions resulting from fundamental molecular absorptions are manifested in the LWIR. These absorptions are of great geologic interest because they include absorptions resulting from vibrations of the Si–O bond and silicate minerals form the bulk of the Earth's crust. The wavelength at which the Si–O stretching feature occurs is dictated by the level of polymerization (or molecule-to-molecule bonding) of the silicate mineral. Highly polymerized framework silicate minerals, such as quartz and feldspar, have a shorter wavelength absorption than do silicate minerals, such as olivine which are composed of disconnected SiO_4 molecules. In Figure 6, laboratory emission spectra of highly and poorly polymerized silicate minerals are shown.

Vegetation and the Environment

While different minerals are, by definition, generally composed of diverse component molecules, different species of vegetation represent variations of the same general biochemical constituents (e.g., chlorophyll, proteins, lignin, cellulose, sugar, starch, etc.). In the thermal IR, vegetation has a generally flat emittance, thus it is in the reflective solar spectrum that most vegetative remote sensing is performed. The major features in the reflectance spectrum of green vegetation are shown in Figure 7. In the visible, the major absorption features are caused by the presence of chlorophyll. Chlorophyll has strong absorptions in the blue and the red, leaving a reflectance maximum (the green peak) at 0.55 μm. In the NIR, scattering in the leaf structure causes high reflectance leaving a profound absorption edge (the red edge) between



Figure 6 Emissivity spectra of SiO_4-bearing minerals showing the shift in band minimum to higher wave number with increasing polymerization.



Figure 7 Major spectral features in the reflectance spectrum of green vegetation.

0.7 and 0.78 μm. Past the red edge and into the SWIR, the spectrum of green vegetation is dominated by water in the leaf, with leaf water absorptions occurring at 0.97, 1.19, 1.45, 1.93, and 2.50 μm. Studies of vegetation, using multispectral systems, have made use of a number of broadband indices. Hyperspectral systems allow for the discrimination of individual absorption features and subtle spectral shape differences in vegetation spectra which are unresolvable using broadband multispectral systems. For example, the absorptions caused by chlorophyll can be used for studies of chlorophyll content in vegetative canopies. The unique interaction of chlorophyll with leaf structures can provide a morphology to the green peak that is unique to a given species and thus is mappable using a spectral feature fitting approach.

A desired goal in the study of vegetation and ecosystem processes is to be able to monitor the chemistry of forest canopies. The foliar biochemical constituents making up forest canopies have associated absorption features in the SWIR, that result from vibrational overtones and combinations of C–O, O–H, C–H, and N–H molecular bonds. However the absorptions from these biochemical components overlap so that the chemical abundance of any one plant component cannot be directly related to any one absorption feature. An even more serious challenge is introduced by the strong influence of water in the SWIR in green vegetation spectra. Water constitutes 40 to 80% of the weight of leaves. However, the unique characteristics of high-quality hyperspectral data (e.g., excellent radiometric and spectral calibration, high signal-to-noise ratio, high spectral resolution) have been used to detect even these subtle features imprinted on the stronger water features.

The amount of water present in plant leaves is, in itself, a valuable piece of information. Hyperspectral data can be used to determine the equivalent water thickness present in vegetative canopies. Conversely, the amount of dry plant litter and/or loose wood can be estimated using spectral mixture analysis and related techniques. Taken together, all these data: vegetation species maps, determinations of leaf water content and the relative fractions of live vegetation versus litter, can be used to characterize woodlands for forest fire potential. The ability to map different species of vegetation has also proved useful in the field of agriculture, for assessing the impact of invasive weed species on farm and ranch land. Being able to assess the health of crops, in terms of leaf water content, is also important for agriculture.

Another subtle vegetative spectral feature, that provides information on plant vitality, is the aforementioned red edge. Shifts in the position of the red edge have been linked to vegetation stress. Studies have shown that vegetation stress and consequent shifts in the position of the red edge can be caused by a number of factors, including insufficient water intake or the intake of pernicious trace metals. Vegetation growing over mineral deposits can display red edge shifts and this can be used to assist in mineral exploration efforts.

Another application area, in which hyperspectral remote sensing has found great utility, is in the analysis of snow-covered areas. Over the reflective solar spectrum, the reflectance of snow varies from values near zero in the SWIR to values near one in the blue. Differences in the grain size of snow result in differences in reflectance as is illustrated in Figure 8. The spectral variability of snow makes it easily distinguishable from other Earth surface materials.



Figure 8 Differences in snow reflectance spectra resulting from differences in snow grain size. Courtesy of Dr Anne Nolin of Oregon State University.

Linear spectral unmixing, using hyperspectral data, has been shown to successfully discriminate between snow, vegetation, rock, and clouds and to accurately map snow cover fraction in mixed pixels. Accurate maps of snow cover, types of snow, and fractions of liquid water admixed with snow grains, are required for forecasting snowmelt runoff and stream discharge in watersheds dominated by snow cover.

Hyperspectral Remote Sensing of the Atmosphere

The physical quantity most often sought in land remote sensing studies is surface reflectance. However, the quantity recorded by a hyperspectral sensor is radiance at the entrance aperture of the sensor. In order to obtain reflectance, the background energy level of the Sun and/or Earth must be removed and the scattering and absorbing effects of the atmosphere must be compensated for. In the VNIR through SWIR, there are seven atmospheric constituents with significant absorption features: water vapor, carbon dioxide, ozone, nitrous oxide, carbon monoxide, methane, and oxygen. Molecular scattering (commonly called Rayleigh scattering) is strong in the blue but decreases rapidly with increasing wavelength. Above 1 μm, its effect is negligible. Scattering caused by atmospheric aerosols, or Mie scattering, also is more prominent at shorter wavelengths and decreases with increasing wavelength, but the dropoff of effects from Mie scattering is not as profound as that for Rayleigh scattering. Consequently, effects from aerosol scattering can persist into the SWIR.

There are three primary categories of methods for removing the effects of atmosphere and solar insolation from hyperspectral imagery, in order to derive surface reflectance. Methods of atmospheric corrections can be considered as being either an image-based, empirical, or model-based approach. An image-based, or 'in-scene' approach uses only data measured by the instrument. Empirical methods make use of the remotely sensed data in combination with field measurements of reflectance, to solve a simplified equation of at-sensor radiance such as eqn [3].

$$L_s = A\rho + B \qquad [3]$$

where L_s is the at-sensor radiance, ρ is the reflectance of the surface, and A and B are quantities that incorporate, respectively, all multiplicative and additive contributions to the at-sensor radiance. All the quantities expressed in eqn [3] can be considered as varying as a function of wavelength, λ. Approximations for A and B from eqn [3] constitute a set of gains and offsets derived from the empirical approach. In some empirical approaches, atmospheric path radiance is ignored and only a multiplicative correction is applied.

Model-based approaches seek to model what the at-sensor radiance should be on a pixel-by-pixel basis, including the contribution of the atmosphere. The at-sensor radiance, L_s, at any wavelength, λ, can be expressed as

$$L_s = \frac{1}{\pi}(E\rho + M_T)\tau_\theta + L_u \qquad [4]$$

where E is the irradiance at the surface of the Earth, ρ is the reflectance of the Earth's surface, M_T is the spectral radiant exitance of the surface at temperature, T, τ_θ is the transmissivity of the atmosphere at zenith angle θ, and L_u is the spectral upwelling path radiance of the atmosphere. The ability to solve eqn [4] and do atmospheric correction on a pixel-by-pixel basis is appealing, in that it negates the shortcomings of an empirical approach where a correction based on calibration targets in one part of a scene might not be appropriate for another part of the scene, due to differences in atmospheric path-length or simple atmospheric heterogeneity. Model-based approaches are also able to take advantage of the greater spectral dimensionality of hyperspectral data sets for the derivation of atmospheric properties (e.g., the amount of column water vapor, CO_2 band depths, etc.) directly from the data.

The main atmospheric component, affecting imagery in the reflective solar portion of the spectrum, is water vapor. Model-based atmospheric correction techniques determine the column water vapor for each pixel in the scene, based on the depth of the 940 and/or 1130 nm atmospheric water bands. Thus for each pixel, an appropriate amount of water can be removed. The maps of atmospheric water vapor distribution are themselves of interest to atmospheric scientists. Absorption features caused by well-mixed gases, such as the 760 nm O_2 band, can be used by model-based programs, to produce images of approximate scene topography. More advanced model-based approaches also solve for the scattering effects of aerosols on the hyperspectral data.

As noted above, atmospheric constituents, including industrial effluents, can be detected and spatially mapped by hyperspectral sensors. The fundamental vibrational absorption of gases of interest occurs in the MWIR and the LWIR. Overtones of these gaseous molecular vibrations occur in the VNIR to SWIR, but are generally too weak to be detected. The ability to detect anthropomorphically produced gases depends on a number of factors, including the temperature difference between the gas cloud and the background atmosphere, the concentration of gas within the cloud, and the size of the cloud (e.g., the path length of light through the cloud).

See also

Imaging: Infrared Imaging. **Instrumentation:** Spectrometers.

Further Reading

Clark RN (1999) Spectroscopy of rocks and minerals, and principles of spectroscopy. In: Rencz AN (ed.) *Remote Sensing for the Earth Sciences*, pp. 3–57. New York: John Wiley and Sons.

Farrand WH and Harsanyi JC (1997) Mapping the distribution of mine tailings in the Coeur d'Alene River Valley, Idaho through the use of a Constrained Energy Minimization technique. *Remote Sensing Environment* 59: 64–76.

Gao B-C and Goetz AFH (1995) Retrieval of equivalent water thickness and information related to biochemical components of vegetation canopies from AVIRIS data. *Remote Sensing Environment* 52: 155–162.

Gao B-C, Heidebrecht KH and Goetz AFH (1993) Derivation of scaled surface reflectances from AVIRIS data. *Remote Sensing Environment* 44: 165–178.

Goetz AFH (1989) Spectral remote sensing in geology. In: Asrar G (ed.) *Theory and Applications of Optical Remote Sensing*, pp. 491–526. New York: John Wiley & Sons.

Goetz AFH, Vane G, Solomon JE and Rock BN (1985) Imaging spectrometry for Earth remote sensing. *Science* 228: 1147–1153.

Hapke B (1993) *Theory of Reflectance and Emittance Spectroscopy*. Cambridge, UK: Cambridge University Press.

Kirkland LE, Herr KC and Salisbury JW (2001) Thermal infrared spectral band detection limits for unidentified surface materials. *Applied Optics* 40: 4852–4862.

Martin ME, Newman SD, Aber JD and Congalton RG (1998) Determining forest species composition using high spectral resolution remote sensing data. *Remote Sensing Environment* 65: 249–254.

Painter TH, Roberts DA, Green RO and Dozier J (1998) The effect of grain size on spectral mixture analysis of snow-covered area with AVIRIS data. *Remote Sensing Environment* 65: 320–332.

Pieters CM and Englert PAJ (eds) *Remote Geochemical Analysis: Elemental and Mineralogical Composition*. Cambridge, UK: Cambridge University Press.

Pinzon JE, Ustin SL, Castaneda CM and Smith MO (1997) Investigation of leaf biochemistry by hierarchical foreground/background analysis. *IEEE Transactions on Geoscience and Remote Sensing* 36: 1–15.

Roberts DA, Green RO and Adams JB (1997) Temporal and spatial patterns in vegetation and atmospheric properties using AVIRIS. *Remote Sensing Environment* 62: 223–240.

Wessman CA, Aber JD and Peterson DL (1989) An evaluation of imaging spectrometry for estimating forest canopy chemistry. *International Journal of Remote Sensing* 10: 1293–1316.

Laser Detection of Atmospheric Gases

E V Browell, W B Grant and S Ismail, NASA Langley Research Center, Hampton, VA, USA

Published by Elsevier Ltd.

Introduction

Lidar (light detection and ranging) systems are able to measure profiles of atmospheric aerosols, clouds, and gases by transmitting a pulsed laser beam into the atmosphere and collecting the backscattered radiation from aerosols and molecules in the atmosphere with a receiver located near the transmitter. The differential absorption lidar (DIAL) approach is the most widely used technique for measuring a variety of gases. In this approach, two closely spaced laser wavelengths are used: one which is absorbed by the gas of interest, and the other which is only weakly, or not at all, absorbed by the gas. A differential with respect to range and wavelength is calculated, to determine the average gas concentration along any segment of the lidar path, using the familiar Beer–Lambert law for an absorbing medium.

The DIAL equation can be expressed in its simple form as

$$N = \left(1/\left(2(R_2 - R_1)(\sigma_{\mathrm{on}} - \sigma_{\mathrm{off}})\right)\right) \times \ln\left(P_{\mathrm{off}}(R_2)P_{\mathrm{on}}(R_1)\right)/\left(P_{\mathrm{off}}(R_1)P_{\mathrm{on}}(R_2)\right) \qquad [1]$$

where N is the average gas concentration, R is the range, σ_{on} and σ_{off} are the absorption cross sections at the on- and off-line wavelengths, and $P_{\mathrm{on}}(R)$ and $P_{\mathrm{off}}(R)$ are the powers received at the on- and off-line wavelengths. However, since it is performed in the atmosphere and not a laboratory, great care must be taken to ensure that the data are analyzed properly to minimize random and systematic errors. Random errors arise from noise in the backscattered signal, the solar background signal, and the inherent detector noise, and this type of error can be reduced by signal averaging. Systematic errors arise from uncompensated instrument and atmospheric effects and must be carefully considered in system design and operation and data processing.

Another approach, the Raman lidar approach, uses inelastic scattering (scattered/emitted light has different wavelength than the illuminating light) from gases where the wavelength shift corresponds to vibrational or rotational energy levels of the molecules. Any illuminating laser wavelength can be used, but since the Raman scattering cross-section varies as λ^{-4}, where λ is the wavelength, the shorter laser wavelengths, such as in the near UV spectral region, are preferred. While even shorter wavelengths in the solar blind region below ~300 nm would permit operation in daytime, the atmospheric attenuation, due to Rayleigh scattering and UV molecular absorption, limits the measurement range. High-power lasers are used due to the low Raman scattering cross-sections. The Raman lidar measurements have to be carefully calibrated against a profile measured using another approach, such as is done for water vapor (H_2O) measurements with the launch of hygrometers on radiosondes, since the lidar system constants and atmospheric extinctions are not usually well known or modeled. In order to obtain mixing ratios of H_2O with respect to atmospheric density, the H_2O signals are ratioed to the nitrogen Raman signals. However, care must be exercised in processing these data due to the spectral dependences of atmospheric extinction.

Surface-Based Lidar Systems

Surface-based lidar systems measure the temporal evolution of atmospheric profiles of aerosols and gases. The first lidar systems used to remotely measure atmospheric gases were Raman lidar systems. The Raman lidar systems were thought to be very promising since one high-power laser could be used to measure a variety of gases. They are easier to develop and operate than DIAL systems, because the laser does not have to be tuned to a particular gas absorption feature. However, the Raman scattering cross-section is low, and the weak, inelastically scattered signal is easily contaminated by daylight background radiation, resulting in greatly reduced performance during daytime. Raman lidar systems have been developed primarily for measuring H_2O and retrieving atmospheric temperature.

Surface-based UV DIAL systems, that are part of the Network for the Detection of Stratospheric Change (NDSC) have made important contributions to the understanding of stratospheric O_3. There are DIAL systems at many locations around the Earth, with sites in Ny-Ålesund, Spitzbergen (78.9°N, 11.9°E), Observatoire Haute Provence, France (43.9°N, 5.7°E), Table Mountain, California (34.4°N, 118.2°W), Mauna Loa, Hawaii (19.5°N, 155.6°W), and Lauder, New Zealand (45.0°S, 169.7°E). First established in the 1980s, these DIAL systems are strategically located so that O_3 in different latitude bands can be monitored for signs of change. In addition, they can provide some profiles for comparison with space-based O_3 measuring instruments. The parameters of a typical ground-based UV DIAL system used in the NDSC are given in Table 1.

Airborne DIAL Systems

Airborne lidar systems expand the range of atmospheric studies beyond those possible by surface-based lidar systems, by virtue of being located in aircraft that can be flown to high altitudes and to remote locations. Thus, they permit measurements at locations inaccessible to surface-based lidar systems. In addition, they can make measurements of large atmospheric regions in times that are short compared with atmospheric motions, so that the large-scale patterns are discernible. Another advantage of airborne lidar operation is that lidar systems perform well in the nadir (down) direction since the atmospheric density and aerosol loading generally increases with decreasing altitude towards the surface, which helps to compensate for the R^{-2} decrease in the lidar

Table 1 Parameters for the Jet Propulsion Laboratory's Mauna Loa DIAL systems for stratospheric O_3 measurements

L [illegible]	XeCl	Nd:YAG (3rd Harmon.)
Wavelength (nm)	308 (on)	355 (off)
Pulse energy (mJ)	300	150
Pulse repetition frequency (Hz)	200	100
R [illegible]		
Area (m^2)	0.79	
Optical efficiency (%)	~40	
Wavelengths–Rayleigh (nm)	308	355
N_2 Raman (nm) (for aerosol correction)	332	387
[illegible]		
Measurement range* (km)	15–55	
Vertical resolution (km)	3 at bottom, 1 at O_3 peak, 8–10 at top	
Measurement averaging time (hours)	1.5	
Measurement accuracy	<5% at peak, 10–15% at 15 km, >40% at 45 km	

*Chopper added to block beam until it reaches 15 km in order to avoid near field signal effects.

signal with range. For the zenith direction, the advantage is that the airborne lidar system is closer to the region being measured.

Field Measurement Programs

Global O_3 Measurements

The first airborne DIAL system, which was developed by the NASA Langley Research Center (LaRC), was flown for O_3 and aerosol investigations in conjunction with the Environmental Protection Agency's Persistent Elevated Pollution Episodes (PEPE) field experiment, conducted over the east coast of the US in the summer of 1980. This initial system has evolved into the advanced UV DIAL system that will be described in the next section. Airborne O_3 DIAL systems have also been developed and used in field measurement programs by several other groups in the United States, Germany, and France.

The parameters of the current NASA LaRC airborne UV DIAL system are given in Table 2. The on-line and off-line UV wavelengths of 288.2 and 299.6 nm are used for DIAL O_3 measurements during tropospheric missions, and 301 and 310 nm are used for stratospheric missions. This system also transmits 1,064 and 600 nm beams for aerosol and cloud measurements. The time delay between the on- and off-wavelength pulses is 400 μs, which is sufficient time for the return at the first set of wavelengths to end, but short enough that the same region of the atmosphere is sampled. This system has a demonstrated absolute accuracy for O_3 measurements of better than 10% or 2 ppbv (parts per billion by volume), whichever is larger, and a measurement precision of 5% or 1 ppbv with a vertical resolution of 300 m and an averaging time of 5 minutes (about 70 km horizontal resolution at typical DC-8 ground speeds).

The NASA LaRC airborne UV DIAL systems have made significant contributions to the understanding of both tropospheric and stratospheric O_3, aerosols, and clouds. These systems have been used in 18 international and 3 national field experiments over the past 24 years, and during these field experiments, measurements were made over, or near, all of the oceans and continents of the world. A few examples of the scientific contributions made by these airborne UV DIAL systems are given in Table 3.

The NASA LaRC airborne UV DIAL system has been used extensively in NASA's Global Tropospheric Experiment (GTE) program which was started in the early 1980s, had as its primary mission the study of tropospheric chemistry in remote regions of the Earth, in part to study and gain a better understanding of atmospheric chemistry in the unperturbed atmosphere. A related goal was to document the Earth's atmosphere in a number of places during seasons when anthropogenic influences are largely absent, then return to these areas later to document the changes. The field missions have included campaigns in Africa, Alaska, the Amazon Basin,

Table 2 Parameters of the NASA LaRC airborne UV DIAL system

L [illegible]: Nd:YAG-pumped dye lasers, frequency doubled into the UV			
Pulse repetition frequency (Hz)	30		
Pulse length (ns)	8–12		
Pulse energy (mJ) at 1.06 μm	250–300		
Pulse energy (mJ) at 600 nm	50–70		
UV pulse energy (mJ)			
For troposphere at 288/300 nm	20		
For stratosphere at 301/310 nm	20		
Dimensions (l × w × h) (cm)	594 × 102 × 109		
Mass (kg)	1735		
Power requirement (kW)	30		
		Wavelength region (nm)	
R[illegible]	289–311	572–622	1064
Area (m^2)	0.086	0.086	0.864
Receiver optical efficiency (%)	30	40	30
Detector quantum efficiency (%)	26 (PMT)	8 (PMT)	40 (APD)
Field-of-view (mrad)	≤1.5	≤1.5	≤1.5
[illegible]			
Measurement range (km)	up to 10–15 (nadir and zenith)		
Vertical resolution (m)	300–1500, depending on range		
Horizontal resolution (km)	≤70		
Measurement accuracy	≤10% or 2 ppbv, whichever is greater		

Table 3 Examples of significant contributions of airborne O_3 DIAL systems to the understanding of tropospheric and stratospheric O_3 (see also Figures 1–5)

[illegible]:
- Air mass characterizations in a number of remote regions
- Continental pollution plume characterizations (see Figures 1 and 2)
- Study of biomass burn plumes and the effect of biomass burning on tropospheric O_3 production (see Figure 3)
- Case study of warm conveyor belt transport from the tropics to the Arctic
- Study of stratospheric intrusions and tropopause fold events (see Figure 4)
- Observation of the decay of a cutoff low
- Power plant plume studies

[illegible]:
- Contributions to the chemical explanation of behavior of Antarctic O_3
- Quantification of O_3 depletion in the Arctic (see Figure 5)
- Polar stratospheric clouds – particle characterizations
- Intercomparison with surface-based, airborne and space-based instruments
- Quantification of O_3 reduction in tropical stratosphere after the June 1991 eruption of Mount Pinatubo and characterization of the tropical stratospheric reservoir edge
- Cross-vortex boundary transport



Figure 1 Latitudinal distribution of ozone over the western Pacific Ocean obtained during the second Pacific Exploratory Mission (PEM West B) in 1994.

Canada, and North America, and over the Pacific Ocean from Antarctica to Alaska, with concentrated measurements off the east coast of Asia and in the tropics. One of the bigger surprises of the two decades of field missions, was the discovery in the mid-1990s, that the tropical and South Pacific Ocean had very high tropospheric O_3 concentrations in plumes from biomass burning in Africa and South America during the austral spring. There were few indications from surface-based or space-based measurements that there were extensive biomass burn plumes in the area, primarily since the plumes were largely devoid of aerosols due to being stripped out during cloud convective lofting. Once over the ocean, horizontal transport appears to proceed relatively unimpeded unless a storm system is encountered.

The NASA LaRC airborne UV DIAL system has also been flown in all the major stratospheric O_3 campaigns starting in 1987 with the Airborne Antarctic Ozone Experiment (AAOE) to determine the cause of the Antarctic ozone hole. The UV DIAL system documented the O_3 loss across the ozone hole region. Later, when attention was turned to the Arctic and the possibility of an ozone hole there, the system was used to produce an estimate of O_3 loss during the winter season as well as to better characterize the polar stratospheric cloud (PSC) particles. The UV DIAL system was also used to study O_3 loss in the tropical stratospheric reservoir following the eruption of Mount Pinatubo in June 1991. The loss was spotted by the Microwave Limb Sounder (MLS) on the Upper Atmospheric Research Satellite (UARS), but the MLS



Figure 2 Pollution outflow from China over the South China Sea (right side of figure) with clean tropical air on south side of a front (left side of figure), observed during PEM West B in 1994.

was unable to study the loss in detail due to its low vertical resolution (5 km) compared to the small-scale (2–3 km) features of the O_3 loss. Other traditional space-based O_3 measuring instruments also had difficulty during this period, due to the high aerosol loading in the stratosphere following the eruption.

Space-Based O_3 DIAL System

In order to obtain nearly continuous, global distributions of O_3 in the troposphere, a space-based O_3 DIAL system is needed. A number of key issues could be addressed by a space-based O_3 DIAL system including: the global distribution of photochemical O_3 production/destruction and transport in the troposphere; location of the tropopause; and stratospheric O_3 depletion and dynamics. High-resolution airborne O_3 DIAL and other aircraft measurements show that to study tropospheric processes associated with biomass burning, transport of anthropogenic pollutants, tropospheric O_3 chemistry and dynamics, and stratosphere–troposphere exchange, a vertical profiling capability from space with a resolution of 2–3 km is needed, and this capability cannot currently be achieved using passive remote sensing satellite instruments. An example of the type of latitudinal O_3 cross-section that could be provided by a space-based O_3 DIAL system is shown in Figure 1. This figure shows many different aspects of O_3 loss and production; vertical and horizontal transport; and stratosphere–troposphere exchange that occurs from the tropics to high latitudes.



Figure 3 Biomass burning plume over the Atlantic Ocean arising from biomass burning in the central part of western Africa, observed during the TRACE-A mission in 1992.

This type of data would be available from just one pass from a space-based O_3 DIAL system. A space-based O_3 DIAL system optimized for tropospheric O_3 measurements (see system description in Table 4a,b) would also permit high-resolution O_3 measurements in the stratosphere (1 km vertical, 100 km horizontal), along with high-resolution aerosol measurements (100 m vertical, 10 km horizontal). In addition, these DIAL measurements will be useful in assisting in the interpretation of passive remote sensing measurements and in helping to improve their data processing algorithms.

Global H_2O Measurements

H_2O and O_3 are important to the formation of OH in the troposphere, and OH is at the center of most of the chemical reactions in the lower atmosphere. In addition H_2O is an excellent tracer of vertical and horizontal transport of air masses in the troposphere, and it can be used as a tracer of stratosphere–troposphere exchange. Increased aerosol sizes, due to high relative humidities, can also affect heterogeneous chemical processes and radiation budgets in the boundary layer and in cloud layers. Knowledge of H_2O is important to weather forecasting and climate



Figure 4 Ozone distribution observed on flight across US during the SASS (Subsonic Assessment) Ozone and Nitrogen Experiment (SONEX) in 1997. A stratospheric intrusion is clearly evident on left side of figure, and low ozone air from tropics transported to mid-latitudes can be seen in the upper troposphere on the right.



Figure 5 Ozone cross-sections in the stratosphere measured in the winter of 1999/2000 during the SOLVE mission. The change in ozone number density in the Arctic polar vortex due to chemical loss during the winter is clearly evident at latitudes north of 72°N.

predictions. Thus, H_2O distributions can be used in several different ways to better understand chemical, transport, radiation and meteorological processes in the global troposphere.

H_2O Raman Lidar Systems

The first Raman lidar measurements of H_2O were made in the late 1960s, but not much progress in using the Raman approach for H_2O was made until a system using an abandoned searchlight mirror was employed by the NASA Goddard Space Flight Center in the mid-1980s, to show that if the signal collector (telescope) was large enough, useful Raman measurements could be made to distances of several kilometers. Until recently, Raman lidar measurements of H_2O were largely limited to night-time, due to the high sunlight background interference. Measurements are now made during daytime, using very narrow telescope fields of view and very narrowband filters in the receiver. A good example of a Raman lidar system used to measure H_2O is that at the Department of Energy's Atmospheric Radiation Measurement – Cloud and Radiation Test Bed (ARM-CART) site in Oklahoma. The site is equipped with a variety of instruments aimed at studying the radiation properties of the atmosphere. The system parameters are given in Table 4a,b.

Raman lidar systems have been used for important measurements of H_2O from a number of ground-based locations. Some of the important early work dealt with the passage of cold and warm fronts. The arrival of the wedge-shaped cold front, pushing the warm air up, was one of these studies. Raman lidar have also been located at the ARM-CART site in Kansas and Oklahoma, where they could both provide a climatology of H_2O as well as provide correlative measurements of H_2O for validation of space-based instruments.

Table 4a Parameters for the US Department of Energy's surface-based Raman lidar system for measurements of H_2O

L[illegible]	Nd:YAG Laser
Wavelength (nm)	355
Pulse energy (mJ)	400
Pulse repetition frequency (Hz)	30
R[illegible]	
Area (m^2)	1.1
Wavelengths (nm)	
Water vapor	407
Nitrogen	387
[illegible]	
Measurement range (km)	
Night-time	near surface to 12
Daytime	near surface to 3
Range resolution (m)	39 at low altitudes, 300 >9 km
Measurement accuracy (%)	
Night-time	<10 <7 km (1 min avg) 10–30 at high altitudes (10–30 min avg)
Daytime	10 <1 km; 5–15 for 1–3 km (10 min avg)

Table 4b Parameters for the NASA Goddard Space Flight Center's Scanning Raman lidar system for measurements of H_2O

	D[illegible]/*N*[illegible]	*N*[illegible]
L[illegible]	Nd:YAG Laser	XeF
Wavelength (nm)	355	351
Pulse energy (mJ)	300	30–60
Pulse repetition frequency (Hz)	30	400
R[illegible]		
Area (m^2)	1.8	1.8
Wavelengths (nm)		
Water vapor	407	403
Nitrogen	387	382
[illegible]		
Measurement range (km)		
Night-time	near surface to 12	
Daytime	near surface to 4	
Range resolution (m)	7.5 at low altitudes, 300 >9 km	
Measurement accuracy (%)		
Night-time	<10 <5 km (10 sec and 7.5 m range resolution) <10 <7 km (1 min avg) 10–30 at high altitudes (10–30 min avg)	
Daytime	<10 <4 km (5 min avg)	

H_2O DIAL Systems

H_2O was first measured with the DIAL approach using a temperature-tuned ruby laser lidar system in the mid-1960s. The first aircraft-based H_2O DIAL system was developed at NASA LaRC, and was flown in 1982, as an initial step towards the development of a space-based H_2O DIAL system. This system was based on Nd:YAG-pumped dye laser technology, and it was used in the first airborne H_2O DIAL atmospheric investigation, which was a study of the marine boundary layer over the Gulf Stream. This laser was later replaced with a flashlamp-pumped solid-state alexandrite laser, which had high spectral purity, i.e., little out-of-band radiation, a requirement since water vapor lines are narrow, and this system was used to make accurate H_2O profile measurements across the lower troposphere.

A third H_2O DIAL system, called LASE (Lidar Atmospheric Sensing Experiment) was developed as a prototype for a space-based H_2O DIAL system, and it was completed in 1995. This was the first fully autonomously operating DIAL system. LASE uses a Ti:sapphire laser that is pumped by a double-pulsed, frequency-doubled Nd:YAG to produce laser pulses in the 815 nm absorption band of H_2O (see Table 5). The wavelength of the Ti:sapphire laser is controlled by injection seeding with a diode laser that is frequency locked to a H_2O line using an

Table 5 Parameters of LASE H_2O DIAL system

Laser	Ti:sapphire
Wavelength (nm)	813–818
Pulse energy (mJ)	100
Pulse-pair repetition frequency	5 (on- and off-line pulses separated by 300 μs)
Linewidth (pm)	<0.25
Stability (pm)	<0.35
Spectral purity (%)	>99
Beam divergence (mrad)	<0.6
Pulse width (ns)	35
Receiver	
Area (m^2)	0.11
Receiver optical efficiency (%)	50 (night), 35 (day)
Avalanch Photodiode (APD) detector quantum efficiency (%)	80
Field-of-view (mrad)	1.0
Noise equivalence power ($W\ Hz^{-0.5}$)	2×10^{-14}
Excess noise factor	3
System performance	
Measurement range (altitude) (km)	15
Range resolution (m)	300–500
Measurement accuracy (%)	5

Table 6 Examples of significant contributions of airborne H_2O DIAL systems to the understanding of H_2O distributions (see also **Figures 6–8**)

NASA Langley H_2O DIAL systems, including LASE
Study of marine boundary layer over Gulf Stream
Observation of H_2O transport at a land/sea edge
Study of large-scale H_2O distributions across troposphere (see **Figure 6**)
Correlative in situ and remote measurements
Observations of boundary layer development (see **Figure 7**)
Cirrus cloud measurements
Hurricane studies (see **Figure 8**)
Relative humidity effects on aerosol sizes
Ice supersaturation in the upper troposphere
Studies of stratospheric intrusions
H_2O distributions over remote Pacific Ocean
Other airborne H_2O DIAL systems
Boundary layer humidity fluxes
Lower-stratospheric H_2O studies

absorption cell. Each pulse pair consists of an on-line and off-line wavelength for the H_2O DIAL measurements. To cover the large dynamic range of H_2O concentrations in the troposphere (over 3 orders of magnitude), up to three line pair combinations are needed. LASE uses a novel approach of operating from more than one position on a strongly absorbing H_2O line. In this approach, the laser is electronically tuned at the line center, side of the line, and near the wing of the line to achieve the required absorption cross-section pairs (on and off). LASE has demonstrated measurements of H_2O concentrations across the entire troposphere using this 'side-line' approach. The accuracy of LASE H_2O profile measurements was determined to be better than 6% or 0.01 g/kg, whichever is larger, over the full dynamic range of H_2O concentrations in the troposphere. LASE has participated in over eight major field experiments since 1995. See Table 6 for a listing of topics studied using airborne H_2O DIAL systems (Figures 6–8).

Space-Based H_2O DIAL System

The technology for a space-based H_2O DIAL system is rapidly maturing in the areas of: high-efficiency, high-energy, high-spectral-purity, long-life lasers with tunability in the 815- and 940-nm regions; low-weight, large-area, high-throughput, high-background-rejection receivers; and high-quantum-efficiency, low-noise, photon-counting detectors. With the expected advancements in lidar technologies leading to a 1-J/pulse capability, a space-based H_2O DIAL system could be flown on a long-duration space mission this decade.

Space-based DIAL measurements can provide a global H_2O profiling capability, which when combined with passive remote sensing with limited vertical resolution, can lead to 3-dimensional measurements of global H_2O distributions. High vertical resolution H_2O ($\leq$1 km), aerosol ($\leq$100 m), and cloud top ($\leq$50 m) measurements from the lidar along the satellite ground-track, can be combined with the horizontally contiguous data from nadir passive sounders to generate more complete high-resolution H_2O, aerosol, and cloud fields for use in the various studies indicated above. In addition, the combination of active and passive measurements can provide significant synergistic benefits leading to improved temperature and relative humidity measurements. There is also strong synergism with aerosol and cloud imaging instruments and with future passive instruments that are being planned or proposed for missions addressing atmospheric chemistry, radiation, hydrology, natural hazards, and meteorology.

Tunable Laser Systems for Point Monitoring

Tunable diode laser (TDL) systems are also used to measure atmospheric gases on a global scale from aircraft and balloons. TDLs are small lasers that emit extremely narrowband radiation and can be tuned in the near IR spectral region using a combination of temperature and current. TDLs can be built into very sensitive and compact systems and located on the surface or flown on aircraft or balloons and used to measure such species as CO, HCl, CH_4, and oxides of nitrogen such as N_2O and NO_2. They derive their



Figure 6 LASE measurements of water vapor (left) and aerosols and clouds (right) across the troposphere on an ER-2 flight from Bermuda to Wallops during the Tropospheric Aerosol Radiative Forcing Experiment (TARFOX) conducted in 1996.



Figure 7 Water vapor and aerosol cross-section obtained on a flight across a cold front during the Southern Great Plains (SGP) field experiment conducted over Oklahoma in 1997.



Figure 8 Measurements of water vapor, aerosols, and clouds in the inflow region of Hurricane Bonnie during 1998 Convection and Moisture Experiment (CAMEX-3). A rain band can be clearly seen at the middle of Leg-AB on the satellite and LASE cross-sections.

high sensitivity to the fact that the laser frequency is modulated at a high frequency, permitting a small spectral region to be scanned rapidly. The second- or fourth-harmonic of the scan frequency is used in the data acquisition, effectively eliminating much of the low-frequency noise due to mechanical vibrations and laser power fluctuations. In addition, multipass cells are employed, thereby generating long paths for the absorption measurements.

TDL systems have been used in a number of surface-based measurement programs. One system was mounted on a ship doing a latitudinal survey in the Atlantic Ocean and monitored NO_2, formaldehyde (HCHO), and H_2O_2. Another TDL system was located at the Mauna Loa Observatory and was used to monitor HCHO and H_2O_2 during a photochemistry experiment, finding much lower concentrations of both gases than models had predicted. The TDL system used to measure HCHO has been used in a number of additional ground-based measurement programs and has also been flown on an aircraft in a couple of tropospheric missions.

One TDL system, called DACOM (Differential Absorption CO Measurement), has been used in a large number of NASA GTE missions. It makes measurements of CO in the 4.7 μm spectral region and CH_4 in the 3.3 or 7.6 μm spectral region. This instrument is able to make measurements at a 1 Hz rate and with a precision of 0.5–2.0%, depending on the CO value, and an accuracy of ±2%. DACOM has been very useful in determining global distributions of CO due to the wide-ranging nature of the GTE missions. It has also contributed to the characterization and understanding of CO in air masses encountered during the GTE missions (Table 7).

A pair of TDL instruments, the Airborne Tunable Laser Absorption Spectrometer (ATLAS) and the Aircraft (ER-2) Laser Infrared Absorption Spectrometer (ALIAS), have been flown on several NASA missions to explore polar O_3 chemistry and atmospheric transport. The ATLAS instrument measures N_2O, and ALIAS is a 4-channel spectrometer that measures a large variety of gases, including HCl, N_2O, CH_4, NO_2, and CO and is currently configured to measure water isotopes across the tropopause.

A new class of lasers, tunable quantum-cascade (QC) lasers, are being added to the list of those available for *in situ* gas measurement systems. Using a cryogenically cooled QC laser during a series of 20 aircraft flights beginning in September 1999 and extending through March 2000, measurements were made of CH_4 and N_2O up to ~20 km in the stratosphere over North America, Scandinavia, and Russia, on the NASA ER-2. Compared with its companion lead salt diode lasers, that were also flown on these flights, the single-mode QC laser, cooled to 82 K, produced higher output power (10 mW), narrower laser linewidth (17 MHz), increased measurement precision (a factor of 3), and better spectral stability (~0.1 cm^{-1} K). The sensitivity of the QC laser channel was estimated to correspond to a minimum-detectable mixing ratio of approximately 2 ppbv of CH_4.

Laser Long-Path Measurements

Laser systems can also be used in long-path measurements of gases. The most important of such programs entailed the measurement of hydroxyl radical (OH) in the Rocky Mountains west of

Table 7 Examples of significant contributions of airborne tunable diode laser systems to the understanding of atmospheric chemistry and transport

- *B [illegible]*
  - The first [illegible] measurements of the suite NO_2, NO, O_3, and the NO_2 photolysis rate to test NO_x (NO_2 + NO) photochemistry
  - The first [illegible] stratospheric measurements of NO_x over a full diurnal cycle to test N_2O_5 chemistry
  - *I* [illegible] measurements of NO_2 and HNO_3 over the 20–35 km region to assess the effect of Mt. Pinatubo aerosol on heterogeneous atmospheric chemistry
  - Measurements of HNO_3 and HCl near 30 km
  - Measurements of CH_4, HNO_3, and N_2O for validation of several satellite instruments
  - Intrusions from midlatitude stratosphere to tropical stratospheric reservoir
- *A [illegible]*
  - *C [illegible]*
    - Measurement of CO from biomass burning from Asia, Africa, Canada, Central America, and South America
    - Detection of thin layers of CO that were transported thousands of miles in the upper troposphere
    - Observed very high levels of urban pollution in plumes off the Asian continent
    - Emission indices for many gases have been calculated with respect to CO
  - *M [illegible]*
    - Determined CH_4 flux over the Arctic tundra, which led to rethinking of the significance of tundra regions as a global source of CH_4
    - Found that biomass burning is a significant source of global CH_4
    - Found strong enhancements of CH_4 associated with urban plumes
- *A [illegible]*
  - *R [illegible]*
    - Extreme denitrification observed in Antarctic winter vortex from NO_y:N_2O correlation study
    - Observed very low N_2O in Antarctic winter vortex, which helped refute the theory that the O_3 hole is caused by dynamics
    - Contributed to the study of transport out of the lower stratospheric Arctic vortex by Rossby wave breaking
    - Measurement of concentrations of gases involved in polar stratospheric O_3 destruction and production
    - Activation of chlorine in the presence of sulfate aerosols
  - *M [illegible]*
    - Measurements in aircraft exhaust plumes in the lower stratosphere, especially of reactive nitrogen species and CO
    - Vertical profiles of CO in the troposphere and lower stratosphere
    - Determination of the hydrochloric acid and the chlorine budget of the lower stratosphere
    - Measurement of NO_2 for testing atmospheric photochemical models
    - Trends in HCl/Cl_y in the stratosphere <21 km, 1992–1998
    - Gas concentration measurements for comparison with a balloon-borne Fourier transform spectrometer observing the Sun
    - Near-IR TDL laser hygrometers (ER-2, WB57, DC-8) for measuring H_2O and total water in the lower stratosphere and upper troposphere
    - Remnants of Arctic winter vortex detected many months after breakup
  - [illegible]
    - Tropical entrainment time scales inferred from stratospheric N_2O and CH_4 observations

Boulder, Colorado. OH was measured using a XeCl excimer laser operating near 308 nm and transmitting a beam to a retroreflector 10.3 km away. The measurements were quite difficult to conduct, primarily since OH abundance is very low (10^5–$10^7\,\mathrm{cm}^{-3}$), yielding very low absorption (~0.02% for an abundance of $10^5\,\mathrm{cm}^{-3}$) over the 20.6 km path. In addition, the excimer laser could generate OH from ambient H_2O and O_3, unless the laser energy density was kept low. To help ensure good measurements, a white light source was also employed during the measurements to monitor H_2O, O_3, and other gases. The measurements were eventually very successful and led to new values for OH abundances in the atmosphere.

Laser-Induced Fluorescence (LIF)

The laser-induced fluorescence approach has been used to measure several molecular and ionic species *in situ*. The LIF approach has been used to measure OH and HO_2 (HO_x) on the ground and on aircraft platforms. One airborne LIF system uses a diode-pumped Nd:YAG-pumped, frequency-doubled dye laser to generate the required energy near 308 nm. The laser beam is sent into a White cell where it can make 32–36 passes through the gas in the cell to increase the LIF signal strength. NO is used to convert HO_2 to OH. The detection limit in 1 minute of about 2–3 ppqv (10^{-15}) above 5 km altitude, which translates into a concentration of about 4×10^4 molec/cm^3 at 5 km and 2×10^4 molec/cm^3 at 10 km altitude. One of the interesting findings from such measurements is that HO_x concentrations are up to 5 times larger than model predictions based on NO_x concentrations, suggesting that NO_x emissions from aircraft could have a greater impact on O_3 production than originally thought.

NO is detected using the LIF technique in a two-photon approach: electrons are pumped from the ground state using 226 nm radiation and from that state to an excited state using 1.06 μm radiation. The 226 nm radiation is generated by frequency doubling a dye laser to 287 nm and then mixing that with 1.1 μm radiation derived from H_2 Raman shifting of frequency-mixed radiation from a dye laser and a Nd:YAG laser. From the excited level, 187–201 nm radiation is emitted. In order to measure NO_2, it is first converted to the photofragment NO via pumping at 353 nm from a XeF excimer laser. One of the interesting findings from airborne measurements in the South Pacific is that there appeared to be a large missing source for NO_x in the upper troposphere.

Summary

DIAL and Raman lidar systems have played important roles in studying the distribution of gases such as O_3 and H_2O on local, regional, and global scales, while TDL systems have played corresponding roles for such gases as CO, HCl, and oxides of nitrogen. It is anticipated that these approaches will continue to yield valuable information on these and other gases, as new and more capable systems are developed. Within the next decade, it is expected that a DIAL system will be placed in orbit to make truly global measurements of O_3, H_2O, and/or carbon dioxide.

See also

Imaging: Lidar. **Scattering:** Raman Scattering.

Further Reading

Browell EV (1994) Remote sensing of trace gases from satellites and aircraft. In: Calvert J (ed.) *Chemistry of the Atmosphere: The Impact on Global Change*, pp. 121–134. Cambridge, MA: Blackwell Scientific Publications.

Browell EV, Ismail S and Grant WB (1998) Differential absorption lidar (DIAL) measurements from air and space. *Applied Physics. B* 67: 399–410.

Dabas A, Loth C and Pelon J (eds) (2001) *Advances in Laser Remote Sensing*. Selected Papers presented at the 20th International Laser Radar Conference (ILRC), Vichy, France, 10–14 July 2000, pp. 357–360. Palaiseau Cedex, France: A. Edition d'Ecole Polytechnique.

Goldsmith JEM, Bisson SE, Ferrare RA, *et al.* (1994) Raman lidar profiling of atmospheric water vapor: simultaneous measurements with two collocated systems. *Bulletin American Meteorological Society* 75: 975–982.

Goldsmith JEM, Blair FH, Bisson SE and Turner DD (1998) Turn-key Raman lidar for profiling atmospheric water vapor, clouds, and aerosols. *Applied Optics* 37: 4979–4990.

Grant WB (1995) Lidar for atmospheric and hydrospheric studies. In: Duarte F (ed.) *Tunable Laser Applications*, pp. 213–305. New York: Marcel Dekker Inc.

Grant WB, Browell EV, Menzies RT, Sassen K and She C-Y (eds) (1997) *Laser Applications in Remote Sensing*. SPIE Milestones series, 690 pp, 86 papers.

Grisar R, Booettner H, Tacke M and Restelli G (1992) *Monitoring of Gaseous Pollutants by Tunable Diode Lasers*. Proceedings of the International Symposium held in Freiburg, Germany, 17–18 October 1991, 372 pp. Dordrecht, The Netherlands: Kluwer Academic Publishers.

McDermid IS, Walsh TD, Deslis A and White M (1995) Optical systems design for a stratospheric lidar system. *Applied Optics* 34: 6201–6210.

Mégie G (1988) Laser measurements of atmospheric trace constituents. In: Measures RM (ed.) *Laser Remote Chemical Analysis*, pp. 333–408. New York: J Wiley & Sons.

Podolske JR and Loewenstein M (1993) Airborne tunable diode laser spectrometer for trace gas measurements in the lower stratosphere. *Applied Optics* 32: 5324–5330.

Pougatchev NS, Sachse GW, Fuelberg HE, *et al.* (1999) Pacific Exploratory Mission-Tropics carbon monoxide measurements in historical context. *Journal of Geophysics Research* 104: 26,195–26,207.

Sachse GW, Collins Jr JE, Hill GF, *et al.* (1991) Airborne tunable diode laser sensor for high precision concentration and flux measurements of carbon dioxide and methane. *Proceedings of the SPIE International Society for Optical Engineering* 1443: 145–156.

Svanberg S (1994) Differential absorption lidar (DIAL). In: Segrist MW (ed.) *Air Monitoring Spectroscopic Techniques*, pp. 85–161. New York: J Wiley & Sons.

Webster CR, *et al.* (1994) Aircraft (ER-2) laser infrared absorption spectrometer (ALIAS) for in situ measurements of HCl, N_2O, CH_4, NO_2, and HNO_3. *Applied Optics* 33: 454–472.

Whiteman DN, Melfi SH and Ferrare RA (1992) Raman lidar system for the measurement of water vapor and aerosols in the Earth's atmosphere. *Applied Optics* 31: 3068–3082.

Zanzottera E (1990) Differential absorption lidar techniques in the determination of trace pollutants and physical parameters of the atmosphere. *Critical Reviews in Analytical Chemistry* 21: 279–319.

Optical Transmission and Scatter of the Atmosphere

S M Adler-Golden and A Berk,
Spectral Sciences, Inc., Burlington, MA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The ability to understand and model radiative transfer (RT) processes in the atmosphere is critical for remote sensing, environmental characterization, and many other areas of scientific and practical interest. At the Earth's surface, the bulk of this radiation, which originates from the sun, is found in the ultraviolet to infrared range between around 0.3 and 4 μm. This article describes the most significant RT processes for these wavelengths, which are absorption (light attenuation along the line of sight LOS) and elastic scattering (redirection of the light). Transmittance, T, is defined as one minus the fractional extinction (absorption plus scattering). At longer wavelengths (in the mid- and long-wave infrared) the major light source is thermal emission.

A few other light sources are mentioned here. The moon is the major source of visible light at night. Forest fires can be a significant source of mid-wave infrared radiation. Manmade light sources include continuum sources such as incandescent lamps and spectrally narrow sources such as fluorescent lamps and lasers. In general, spectrally narrow sources need to have a different RT treatment than continuum sources due to the abundance of narrow spectral absorption lines in the atmosphere, as is discussed below.

The challenge of atmospheric RT modeling is essentially to solve the following equation that describes monochromatic light propagation along the LOS direction:

$$\left(\frac{1}{k}\right)\frac{\mathrm{d}I}{\mathrm{d}u} = -I + J \qquad [1]$$

where I is the LOS radiance (watts per unit area per unit wavelength per steradian), k is the extinction coefficient for the absorbing and scattering species (per unit concentration per unit length), u is the material column density (in units of concentration times length), and J is the radiance source function. I is a sum of direct (i.e., from the sun) and diffusely scattered components. The source function represents the diffuse light scattered into the LOS, and is the angular integral over all directions Ω_i of the product of the incoming radiance, $I(\Omega_\mathrm{i})$, and the scattering phase function, $p(\Omega_\mathrm{o}, \Omega_\mathrm{i})$:

$$J(\Omega_\mathrm{o}) = \int_{\Omega_\mathrm{i}} p(\Omega_\mathrm{o}, \Omega_\mathrm{i}) I(\Omega_\mathrm{i})\mathrm{d}\Omega_\mathrm{i} \qquad [2]$$

The scattering phase function describes the probability density for incoming light from direction Ω_i scattering out at angle Ω_o, and is a function of the difference (scattering) angle θ.

The direct radiance component, I', is described by eqn [1] with the source function omitted. Integrating along the LOS leads to the well-known Beer's Law equation for transmittance:

$$T = I'/I'_0 = \exp(-ku) \qquad [3]$$

where I'_0 is the direct radiance at the boundary of the LOS. The quantity $ku = \ln(1/T)$ is known as the optical depth.

Atmospheric Constituents

The atmosphere has a large number of constituents, including numerous gaseous species and suspended liquid and solid particulates. Their contributions to extinction are depicted in Figure 1. The largest category is gases, of which the most important are water vapor, carbon dioxide, and ozone. Of these, water vapor is the most variable and carbon dioxide the least, although the CO_2 concentration is gradually increasing. In atmospheric RT models, carbon dioxide is frequently taken to have a fixed and altitude-independent concentration, along with other 'uniformly mixed gases' (UMGs). The concentration profiles of the three major gas species are very different. Water vapor is located mainly in the lowest 2 km of the atmosphere. Ozone has a fairly flat profile from the ground through the stratosphere (~30 km). The UMGs decline exponentially with altitude, with a scale height of around 8 km.

Gases

Gas molecules both scatter and absorb light. Rayleigh scattering by gases scales inversely with the fourth power of the wavelength, and is responsible for the sky's blue color. For typical atmospheric conditions, the optical depth for Rayleigh extinction is approximately $0.009/\lambda^4$ per air mass (λ is in μm and air mass is defined by the vertical column from ground to space). The Rayleigh phase function has a $(1 + \cos^2\theta)$ dependence.

Absorption by gases may consist of a smooth spectral continuum (such as the ultraviolet and visible electronic transitions of ozone) or of discrete spectral lines, which are primarily rotation lines of molecular vibrational bands. In the lower atmosphere (below around 25 km altitude), the spectral shape of these lines is determined by collisional broadening and described by the normalized Lorentz line shape formula:

$$f_{\text{Lorentz}}(\nu) = \frac{\alpha_c/\pi}{\alpha_c^2 + (\nu - \nu_0)^2} \qquad [4]$$

Here ν is the wavenumber (in cm^{-1}) [$\nu = (10\,000\ \mu\text{m/cm})/\lambda$], ν_0 is the molecular line transition frequency and α_c is the collision-broadened half-width (in cm^{-1}), which is proportional to pressure. The constant of proportionality, known as the pressure-broadening parameter, has a typical value on the order of $0.06\ \text{cm}^{-1}\ \text{atm}^{-1}$ at ambient temperature. The extinction coefficient $k(\nu)$ is the product of $f_{\text{Lorentz}}(\nu)$ and the integrated line strength S, which is commonly in units of $\text{atm}^{-1}\ \text{cm}^{-2}$.

At higher altitudes in the atmosphere the pressure is reduced sufficiently that Doppler broadening



Figure 1 Spectral absorbance (1 − transmittance) for the primary sources of atmospheric extinction. The 12 nm resolution data were generated by MODTRAN for a vertical path from space with a mid-latitude winter model atmosphere.

becomes competitive with collisional broadening, and the Lorentz formula becomes inaccurate. The general lineshape for combined collisional and Doppler broadening is the Voigt lineshape, which is proportional to the real part of the complex error (probability) function, w:

$$f_{\text{Voigt}}(\nu) = \frac{1}{\alpha_{\text{d}}\sqrt{\pi}}\text{Re}\left[w\left(\frac{\nu - \nu_0}{\alpha_{\text{d}}} + \frac{\alpha_{\text{c}}}{\alpha_{\text{d}}}\text{i}\right)\right] \qquad [5]$$

Here, α_{d} is the Doppler $1/e$ half-width.

Comprehensive spectral databases have been compiled of the transition frequencies, strengths, and pressure-broadened half-widths for atmospherically important molecules throughout the electromagnetic spectrum. Perhaps the most notable of these databases is HITRAN, which was developed by the US Air Force Research Laboratory and is currently maintained at the Harvard-Smithsonian Center for Astrophysics in Cambridge, MA.

Liquids and Solids

The larger particulates in the atmosphere (greater than a few μm in radius) typically belong to clouds. Low-altitude clouds consist of nearly spherical water droplets, while high-altitude cirrus clouds are mainly a collection of ice crystals. Other large particulates include sand dust. Their light scattering is close to the geometric limit at visible and ultraviolet wavelengths. This means that the extinction is nearly wavelength-independent, and the scattering phase function and single-scattering albedo may be reasonably modeled with ray-tracing techniques that account for the detailed size and shape distributions of the particles. However, Mie scattering theory is typically used to calculate cloud optical properties because it is exact for spherical particles of any size.

The smaller particulates in the atmosphere belong to aerosols, which are very fine liquid particles, and dusts, which are solids such as minerals and soot. These particulates are concentrated mainly in the lower 2 km or so of the atmosphere; however, they are also present at higher altitudes in smaller concentrations. Their optical properties are typically modeled using Mie theory. The wavelength dependence of the scattering is approximately inversely proportional to a low power of the wavelength, typically between 1 and 2, as befits particulates intermediate in size between molecular and geometric-limit. The scattering phase functions have a strong forward-scattering peak; values of the asymmetry parameter g (the average value of $\cos\theta$) typically range from 0.6 to 0.8 at solar wavelengths.

Solution Methods

Geometry

Atmospheric properties are primarily a function of altitude, which determines pressure, temperature and species concentration profiles. Accordingly, most RT methods define a stratified atmosphere. The most accurate treatments of transmission and scattering account for the spherical shape of the layers and refraction; however, most RT models use a plane-parallel approximation for at least some computations, such as multiple scattering.

Spectral Resolution

Optical instruments have finite, and frequently broad, wavelength responses. Nevertheless, modeling their signals requires accounting for the variation of absorption on an extremely fine wavelength scale, smaller than the widths of the molecular lines.

‘Exact’ monochromatic methods

The most accurate RT solution method involves explicitly solving the RT problem for a very large number of monochromatic wavelengths. This line-by-line method is used in a number of RT models, such as FASCODE. It allows Beer’s law to be applied to combine transmittances from multiple LOS segments, and provides an unambiguous definition of the optical parameters. It is suitable for use with spectrally structured light sources, such as lasers. The one major drawback of this method is that it is computationally intensive, and therefore may not be practical for problems where large wavelength ranges, multiple LOS views and multiple atmospheric conditions need to be treated.

To alleviate the computational burden of monochromatic calculations, some approximate methods have been developed that model RT in finite spectral intervals, as described below.

Statistical band models

The band model method represents spectral lines in a narrow interval, $\Delta\nu$, statistically using such parameters as the total line strength, the mean pressure-broadening parameter, and the effective number of lines in the interval. An example of a popular band model-based RT algorithm is MODTRAN, which is described below.

A key to the success of band models is the availability of approximate analytical formulas for the integrated absorption for an individual molecular transition of strength S, known as the single-line total equivalent width, W_{sl}:

$$W_{\mathrm{sl}} = \int_{-\infty}^{\infty} [1 - \exp(-Suf_{\nu})]\mathrm{d}\nu \qquad [6]$$

In the optically thin (small absorption) limit, W_{sl} is proportional to the molecular species column density, while in the optically thick (large absorption) limit it scales as the square root of the column density. A further assumption made by MODTRAN is that the line centers are randomly located within the interval, i.e., spectrally uncorrelated. With this assumption, the net transmittance can be expressed as the product of the transmittances for each individual line, whether the line belongs to the same molecular species or a different species.

A particular challenge in band models is treatment of the inhomogeneous path problem – that is, the variations in path properties along a LOS and their effect on the statistical line parameters, which arise primarily from differences in pressure and hence line width. The Curtis–Godson path averaging method provides a reasonable way to define 'equivalent' homogeneous path parameters for the band model. Another challenge is to define an effective extinction optical depth for each layer in order to solve the RT problem with scattering. One option in MODTRAN is to define it by computing the cumulative transmittance through successive layers in a vertical path.

Correlated-*k* model

Another well-known approximate RT algorithm for spectral intervals is the correlated-*k* method. This method starts with an 'exact' line-by-line calculation of extinction coefficients (k's) within the interval on a fine spectral grid, from which a *k*-distribution (vs. cumulative probability) is computed. A database of *k* values and probabilities summing to 1 is built from these *k*-distributions for a grid of atmospheric pressures and temperatures, and for all species contributing to the spectral interval. Inhomogeneous paths are handled by recognizing that the size order of the k's is virtually independent of pressure and typically only weakly dependent on temperature. LOS transmittances, LOS radiances, and fluxes are calculated by interpolating the database over temperature and pressure to define the k's for each LOS segment, solving the monochromatic RT equation at each fixed distribution location, and finally integrating over the distribution. The correlated-*k* method has been found to be quite accurate for atmospheric paths containing a single molecular species; however, corrections must be applied for spectral intervals containing multiple species.

Scattering Methods

When the diffuse light field is of interest, scattering methods are used to calculate the source function *J* of eqns [1] and [2].

Single scattering

If scattering is weak, the approximation may be made that the solar radiation scatters only once. Thus the integral over the scattering phase function, eqn [2], is straightforwardly calculated using the direct radiance component, which is given by eqn [3]. The neglect of multiple scattering (i.e., the diffuse contribution to the source function) means that the diffuse radiance is underestimated; however, single scattering is sufficiently accurate for some atmospheric problems in clear weather and at infrared wavelengths.

Multiple scattering

A number of different methods have been developed to solve the multiple scattering problem. Two-stream methods, which are the simplest and fastest, resolve the radiance into upward and downward directions. These methods generally produce reasonably accurate values of hemispherically averaged radiance, which are also referred to as horizontal fluxes or irradiances.

A much more accurate approach to the multiple scattering problem is the method of discrete ordinates. It involves expansion of the radiation field, the phase function and the surface reflectance as a series of spherical harmonics, leading to a system of linear integral equations. Evaluation of the integrals by Gaussian quadrature leads to a solvable system of linear differential equations. An important approximation called delta-M speeds up convergence of the discrete ordinates method, especially when scattering phase functions are strongly forward peaked, by representing the phase function as the sum of a forward direction δ-function and a remainder term. For most scattering problems, the solution is converged upon with a modest number (~8 to 16) of quadrature points (streams).

A very different type of multiple scattering technique, called the Monte Carlo method, is based on randomly sampling a large number of computer-simulated 'photons' as they travel through the atmosphere and are absorbed and scattered. The basic idea here is that sensor radiance can be expressed as a multiple path integral over the local source terms, and Monte Carlo methods solve integrals by sampling the integrand. The major advantage of this method is that it is flexible enough to allow for all of the complexity of a realistic atmosphere, often neglected by other methods. The major drawback is its computational burden, as a large number of photons is required for reasonable convergence; the Gaussian error in the calculation declines with the square root of the number of photons. The convergence problem is moderated to a large extent by using the physics of the problem being solved to bias the selection of photon paths toward those trajectories which contribute most; mathematically, this is equivalent to requiring that the integrand be sampled most often where its contributions are most significant.

An Example Atmospheric RT Model: MODTRAN

MODTRAN, developed collaboratively by the Air Force Research Laboratory and Spectral Sciences, Inc., is the most widely used atmospheric radiation transport model. It defines the atmosphere using stratified layering and computes transmittances, radiances, and fluxes using a moderate spectral resolution band model with IR through UV coverage. The width of the standard spectral interval, or bin, in MODTRAN is 1 cm^{-1}. At this resolution, spectral correlation among extinction sources is well characterized as random. Thus, the total transmittance from absorption and scattering of atmospheric particulates and molecular gases is computed as the product of the individual components.

Rayleigh, aerosol, and cloud extinction are all spectrally slowly varying and well represented by Beer's Law absorption and scattering coefficients on a 1 cm^{-1} grid. Calculation of molecular absorption is more complex because of the inherent spectral structure and the large number of molecular transitions contributing to individual spectral bins. As illustrated in Figure 2, MODTRAN partitions the spectral bin molecular attenuation into 3 components:



Figure 2 Components of molecular absorption. The line center, line tail and continuum contributions to the total absorption are illustrated for the central 1 cm^{-1} spectral bin.

- *Line center absorption* from molecular transitions centered within the spectral bin;
- *Line tail absorption* from the tails of molecular lines centered outside of the spectral bin but within 25 cm^{-1}; and
- H_2O and CO_2 *continuum absorption* from distant (>25 cm^{-1}) lines.

Within the terrestrial atmosphere, only H_2O and CO_2 have sufficient concentrations and line densities to warrant inclusion of continuum contributions. These absorption features are relatively flat and accurately modeled using 5 cm^{-1} spectral resolution Beer's Law absorption coefficients.

Spectral bin contributions from neighboring line tails drop off, often rapidly, from their spectral bin edge values, but the spectral curves are typically simple, containing at most a single local minimum. For MODTRAN, these spectral contributions are pre-computed for a grid of temperature and pressure values, and fit with Padé approximants, specifically the ratio of quadratic polynomials in wavenumber. These fits are extremely accurate and enable line tail contributions to be computed on an arbitrarily fine grid. MODTRAN generally computes this absorption at a resolution equal to one-quarter the spectral bin width, i.e., 0.25 cm^{-1} for the 1.0 cm^{-1} band model.

The most basic *ansatz* of the MODTRAN band model is the stipulation that molecular line center absorption can be approximated by the absorption of n identical Voigt lines randomly distributed within the band model spectral interval, $\Delta\nu$. Early in the development of RT theory, Plass derived the expression for the transmittance from these n randomly distributed lines:

$$T = \left(1 - \frac{W'_{\mathrm{sl}}}{\Delta\nu}\right)^n \qquad [7]$$

MODTRAN's evolution has resulted in a fine tuning of the methodology used to define both the effective line number n and the in-band single-line equivalent width W'_{sl}. The effective line number is initially estimated from a relationship developed by Goody, in which lines are weighted according the to square root of their strength, but MODTRAN combines nearly degenerate transitions into single lines because these multiplets violate the random distribution assumption. The initial effective line number values are refined to insure a match with higher resolution transmittance predictions degraded to the band model resolution. The in-band equivalent width is computed for an off-centered Voigt line of strength *S*. Lorentz and Doppler half-widths are determined as strength-weighted averages. The off-center distance is fixed to insure that the weak-line Lorentz equivalent width exactly equals the random line center value.

MODTRAN scattering calculations are optimally performed using the DISORT discrete ordinates algorithm developed by Stamnes and co-workers. Methods for computing multiple scattering such as DISORT require additive optical depths, i.e., Beer's Law transmittances. Since the in-band molecular transmittances of MODTRAN do not satisfy Beer's Law, MODTRAN includes a correlated-*k* algorithm option. The basic band model *ansatz* is re-invoked to efficiently determine *k*-distributions; tables of *k*-data are pre-computed as a function of Lorentz and Doppler half-widths and effective line number, assuming spectral intervals contain *n* randomly distributed identical molecular lines. Thus, MODTRAN *k*-distributions are statistical, only dependent on band model parameter values, not on the exact distribution of absorption coefficients in each spectral interval.

Applications

Among the many applications of atmospheric transmission and scattering calculations, we briefly describe two complementary ones in the area of remote sensing, which illustrate many of the RT features discussed earlier as well as current optical technologies and problems of interest.

Earth Surface Viewing

The first example is Earth surface viewing from aircraft or spacecraft with spectral imaging sensors. These include hyperspectral sensors, such as AVIRIS, which have typically a hundred or more contiguous spectral channels, and multispectral sensors, such as Landsat, which typically have between three and a few tens of channels. These instruments are frequently used to characterize the surface terrain, materials and properties for such applications as mineral prospecting, environmental monitoring, precision agriculture, and military uses. In addition, they are sensitive to properties of the atmosphere such as aerosol optical depth and column water vapor. Indeed, in order to characterize the surface spectral reflectance, it is necessary to characterize and remove the extinction and scattering effects of the atmosphere.

Figure 3 also shows an example of data collected by the AVIRIS sensor at ~3 km altitude over thick vegetation. The apparent reflectance spectrum is the observed radiance divided by the Top-of-Atmosphere horizontal solar flux. Atmospheric absorption by water vapor, oxygen, and carbon dioxide is evident, as well as Rayleigh and aerosol scattering. Figure 3 shows the surface reflectance spectrum inferred by modeling and then removing these atmospheric effects (this process is known as atmospheric removal, compensation, or correction). It has the characteristic smooth shape expected of vegetation, with strong chlorophyll absorption in the visible and water bands at longer wavelengths. A detailed analysis of such a spectrum may yield information on the vegetation type and its area coverage and health.



Figure 3 Vegetation spectrum viewed from 3 km altitude before (apparent reflectance) and after (reflectance) removal of atmospheric scatter and absorption.

Sun and Sky Viewing

The second remote sensing example is sun and sky viewing from the Earth's surface with a spectral radiometer, which can yield information on the aerosol content and optical properties as well as estimates of column concentrations of water vapor, ozone, and other gases. Figure 4 shows data from a Yankee Environmental Systems, Inc. multi-filter rotating shadow-band radiometer, which measures both 'direct flux' (the direct solar flux divided by the cosine of the zenith angle) and diffuse (sky) flux in narrow wavelength bands. The plot of ln(direct signal) versus the air mass ratio is called a Langley plot, and is linear for most of the bands, illustrating Beer's Law. The extinction coefficients (slopes) vary with wavelength consistent with a combination of Mie and Rayleigh scattering. The water-absorbing 940 nm band has the lowest values and a curved



Figure 4 Direct solar flux versus air mass at the surface measured by a Yankee Environmental Systems, Inc. multi-filter rotating shadow-band radiometer at different wavelengths.

plot, in accordance with the square-root dependence of the equivalent width for optically thick lines. The diffuse fluxes, which arise from aerosol and Rayleigh scattering, have a very different dependence on air mass than the direct flux. In particular, the diffuse contributions often increase with air mass for high sun conditions.

The ratio of the diffuse and direct fluxes is related to the total single-scattering albedo, which is defined as the ratio of the total scattering coefficient to the extinction coefficient. Results from a number of measurements showing lower than expected diffuse-to-direct ratios have suggested the presence of black carbon or some other continuum absorber in the atmosphere, which would have a significant impact on radiative energy balance at the Earth's surface and in the atmospheric boundary layer.

List of Units and Nomenclature

Line shape function [cm]	f_ν
Lorentz line shape function [cm]	$f_{\text{Lorentz}}(\nu)$
Voigt line shape function [cm]	$f_{\text{Voigt}}(\nu)$
Scattering asymmetry parameter	g
Direct plus diffuse radiance (W cm^{-1} sr^{-1} or W cm^{-2} μm^{-1} sr^{-1})	I
Direct radiance (W cm^{-1} sr^{-1} or W cm^{-2} μm^{-1} sr^{-1})	I'
Direct radiance at the LOS boundary (W cm^{-1} sr^{-1} or W cm^{-2} μm^{-1} sr^{-1})	I'_0
Source function (W cm^{-1} sr^{-1} or W cm^{-2} μm^{-1} sr^{-1})	J
Extinction coefficient (cm^{-1} atm^{-1})	k
Effective number of lines in bin	n
Scattering phase function (sr^{-1})	p
Line strength (cm^{-2} atm^{-1})	S
Transmittance	T
Column density (atm cm)	u
Complex error (probability) function	w
Single-line total equivalent width (cm^{-1})	W_{sl}
Single-line in-band equivalent width (cm^{-1})	W'_{sl}
Collision-broadened half-width at half maximum (cm^{-1})	α_{c}
Doppler half-width at 1/*e* (cm^{-1})	α_{d}
Spectral interval (bin) width (cm^{-1})	$\Delta\nu$
Scattering angle (radian)	θ
Wavelength (μm)	λ
Wavenumber (cm^{-1})	ν
Molecular line transition frequency	ν_0
Direction of incoming light (sr)	Ω_{i}
Direction of outgoing light (sr)	Ω_{o}

See also

Environmental Measurements: Laser Detection of Atmospheric Gases. **Instrumentation:** Spectrometers. **Scattering:** Scattering from Surfaces and Thin Films.

Further Reading

Berk A, Anderson GP, Acharya PK, Bernstein LS, Shettle EP, Adler-Golden SM, Lee J and Muratov L (2004) MODTRANS User's Manual. Airforce Research Laboratory, Hanscom AFB, MA, in press.

Chandrasekhar S (1960) *Radiative Transfer*. New York: Dover Publications, Inc., Originally published by Oxford University Press, London (1950).

Fenn RW, Clough SA, Gallery WO, Good RE, Kneizys FX, Mill JD, Rothman LS, Shettle EP and Volz FE (1985) Optical and infrared properties of the atmosphere. In: Jursa AS (ed.) *Handbook of Geophysics and the Space Environment*, chap. 18, US Air Force Geophysics Laboratory, Hanscom AFB, MA, AFGL-TR-85-0315, available from NTIS ADA 167000.

Goody RM and Yung YL (1989) *Atmospheric Radiation, Theoretical Basis*, 2nd edn. New York: Oxford University Press.

HITRAN Special Issue, J. Quant. Spectrosc. Rad. Transfer, vol. 82, Nos. 1–4, 15 November–15 December (2003).

Houghton J (2001) *The Physics of Atmospheres*, 3rd edn, Cambridge, UK: Cambridge University Press.

Killinger DK, Churnside JH and Rothman LS (1994) Atmospheric optics. In *Handbook of Optics*, 2nd edn, 2-Volume Set, chap. 44. New York: McGraw-Hill.

Liou KN (1997) *An Introduction to Atmospheric Radiation*, 2nd edn. London: Academic Press.

Smith FG (ed.) (1993) *The Infrared and Electro-Optical Systems Handbook*, vol. 2, *Atmospheric Propagation of Radiation*. Ann Arbor: Environmental Research Institute of Michigan.

Thomas GE and Stamnes K (1999) *Radiative Transfer in the Atmosphere and Ocean*. Cambridge, UK: Cambridge University Press.

Van de Hulst HC (1981) *Light Scattering by Small Particles*. New York: Dover Publications, Inc., Originally published in 1957, New York: John Wiley & Sons, Inc.

F

FIBER AND GUIDED WAVE OPTICS

Contents

Overview
Dispersion
Fabrication of Optical Fiber
Light Propagation
Measuring Fiber Characteristics
Nonlinear Effects (Basics)
Nonlinear Optics
Optical Fiber Cables
Passive Optical Components

Overview

A Mickelson, University of Colorado, Boulder, CO, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

It is said that some in ancient Greece knew that light could be guided inside slabs of transparent material. From this purported little-known curiosity in the ancient world, guided wave optics has grown to be the technology of the physical level of the systems which transfer most of the information about the world; the waveguide of the worldwide telecommunications network is the optical fiber. The optical fiber itself is but a passive waveguide, and guided wave optics is the technology which includes all of the passive and active components which are necessary to prepare optical signals for transmission, regenerate optical signals during transmission, route optical signals through systems and code onto optical carriers, and decode the information from optical carriers, to more conventional forms. In this article, some introduction to this rather encompassing topic will be given.

This article will be separated into four parts. In the first section, discussion will be given to fiber optics, that is, the properties of the light guided in optical waveguides which allow the light to be guided in distinctly nonrectilinear paths over terrestrial distances. The second section will then turn to the components which can be used along with the fiber optical waveguides in order to form useful systems. These components include sources and detectors as well as optical amplifiers. In the third section, we will discuss the telecommunications network which has arisen due to the availability of fiber optics and fiber optic compatible components. The closing section will discuss integrated optics, the field of endeavor which has such great promise to form the future of optical technology.

Fiber Optics

Fiber optics is a term which generally refers to a technology in which light (actually infrared, visible, or ultraviolet radiation) is transmitted through the transparent cores of small threads of composite material. These threads, or fibers as they are called, when surrounded by a cladding material and coated with polymer for environmental protection (see Figure 1) can be coiled like conventional wire and



Figure 1 A depiction of the structure of an optical fiber. The innermost cylinder is the core region in which the majority of the light is confined. The next concentric region is the cladding region which is still made of a pure material but one of a lower index of refraction than the innermost core region, such that the light of the lightwave decays exponentially with extension into this region. The outermost region is a coating which protects the fused silica of the core and cladding from environmental contaminants such as water. For telecommunications fibers, the core is comprised of fused silica doped with germanium and typically has an index of refraction of 1.45, whereas the cladding differs from this index by only about 1%. The coating is often a polyimide plastic which has a higher index (perhaps 1.6) but no light guided light should see the cladding-coating interface.

when cabled can resemble (a very lightweight flexible version of) conventional transmission wire. Although most of the optical fiber in use today is fabricated by a process of gas phase chemical deposition of fused silica doped with various other trace chemicals, fiber can be made from a number of different material systems and in a number of different configurations for use with various types of sources. In what follows in this opening section, we will limit discussion to the basic properties of the light guided by the fiber and leave more technological discussion to following sections.

There are two complementary mathematical descriptions of the propagation of light in an optical waveguide. In the ray description, light incident on a fiber endface is considered to be made up of a bundle of rays. In a uniform homogeneous medium, each ray is like an arrow that exhibits rectilinear propagation from its source to its next interface with a dissimilar material. These rays satisfy Snell's laws of reflection and refraction at interfaces between materials with dissimilar optical properties that they encounter along their propagation path. That is, at an interface, a fraction of the light is reflected backwards at an angle equal to the incident angle and a portion of the light is transmitted in a direction which is more directed toward the normal to the interface when the index increases across the



Figure 2 Schematic depiction of the geometrical optics interpretation of the coupling of light into an optical fiber. Here a ray that is incident on the center of the fiber core at an upward angle is first refracted at the fused silica–air interface into the fused silica core. The ray is then totally internally reflected at the core cladding interface such that the ray power remains in the core. The ray picture of light coupling is applicable to single rays coupling to a multimode fiber. When there are multiple rays, interference between these rays must be taken into account which is difficult to do in the ray picture. When there is only one (diffraction limited) mode in the fiber, the interference between a congruence of (spatially coherent) incident rays is necessary to describe the coupling. This description is more easily effected by a quasi-monochromatic mode picture of the propagation.

boundary and is directed more away from the normal when the index decreases. At the input endface of a waveguide, a portion of the energy guided by each ray is refracted due to the change in refractive index at the guide surface and then exhibits a more interesting path within the fiber. In a step index optical fiber, where the index of refraction is uniformly higher in the fiber core than in a surrounding cladding, the rays will propagate along straight paths until encountering the core cladding interface. Guided rays (see Figure 2) are totally internally reflected back into the fiber core to again be totally internally reflected at the next core cladding interface and so on. Radiating rays (see Figure 3) will be only partially reflected at the core cladding interface and will rapidly die out in propagating down the fiber when it is taken into account that typical distances between successive encounters with the boundary may be sub-millimeter and total propagation distances may be many kilometers. In graded index fibers, the refractive index within the fiber core varies continuously from a maximum somewhere within the core to a minimum at which the core ends and attaches continuously to a cladding. The ray paths within such fibers are curved and the guided rays are characterized by the fact that once in the fiber they never encounter the cladding. Radiating rays encounter the cladding and are refracted out of the fiber. This description of fiber propagation is quite simple and pleasing but does not take into account that each ray actually is carrying a clock that remembers how long it has been following its given path. When two rays come together, they can



Figure 3 Schematic depiction of the existence of a cut-off angle for coupling into an optical fiber. A ray incident from air on the center of the fused silica fiber core is refracted at the air fused silica interface and then split when it comes to the core cladding interface within the fiber. Were the refracted angle of this ray zero (along the core cladding interface) we would say the ray is totally internally reflected and no power escapes. As it is, there is refracted power into the cladding and the ray will rapidly attenuate as it propagates along the fiber. Although most telecommunications fiber in this day and age is graded index (the rays will curve rather than travel along straight paths), a typical repeat period in such a fiber is a millimeter, whereas propagation distances may be 100 km. With a loss of even only 0.1% at each reflection form the cladding, the light light at cut-off will be severely attenuated in one meter, no loss, one kilometer.

either add or subtract, depending on the reading on their respective clocks. When the light is nearly monochromatic, the clocks' readings are simply a measure of the phase of the ray when it was radiated from its source and the interference between rays can be quite strong. This interference leads to conditions which only allow certain ray paths to be propagated. When the light has a randomly varying phase in both space and time (and is therefore polychromatic), the interference all but disappears. But the condition that allows coupling to a specific ray path (mode) also is obliterated by the phase randomness, and coupling to a single mode guide, for example, becomes inefficient.

When we need to preserve phase relations in order to preserve information while it propagates along a fiber path, we need to use single modes excited by nearly transform limited sources, that is sources whose time variation exhibits well-defined (nonrandom) phase variation. As a monochromatic wave carries no information, we will require a source which can be modulated. When modulation can be impressed on a carrier without loss of phase information of either information or carrier, information can be propagated at longer distances than when the frequency spectrum of the carrier is broadened by noise generated during the modulation. We refer to such a source that can be modulated without broadening as a coherent or nearly coherent source. We cannot easily adapt the ray picture to the description of propagation of such coherent radiation in an optical fiber. Instead we must resort to using the time harmonic form of Maxwell's equations, the equations which describe electromagnetic phenomena, whereas rays can be described by a simplification of the time-dependent form of these equations. In the time harmonic approach, we assume that the source is monochromatic and then solve for a set of modes of the fiber at the assumed frequency of the source. These modes have a well-defined phase progression as a function of carrier frequency and possess a given shape in the plane transverse to the direction of propagation. Information can be included in the propagation by assuming the quasi-monochromatic variation of the source, that is, one assumes that the source retains the phase relations between the various modulated frequency components even while its amplitude and phase is being varied externally. When one assumes that time harmonically (monochromatic) varying fields are propagating along the fiber axis, one obtains solutions of Maxwell's equations in the form of a summation of modes. These are guided modes, ones that propagate down the fiber axis without attenuation. There are also radiation modes that never couple into a propagating mode in the fiber. These modes are analogous to the types of rays we see in the ray description of fiber propagation. There are also another set of modes which are called evanescent modes which show up at discontinuities in the fiber or at junctions between the fiber and other components. In the modal picture of fiber propagation, each of these modes is given an independent complex coefficient (that is, a coefficient with both amplitude and phase). These coefficients are determined first by any sources in the problem and then must be recalculated at each discontinuity plane along the propagation path in the fiber. When the source(s) in the problem is not transform limited, the phases of the coefficients become smeared out and the coupling problems at discontinuities take on radically different solutions.

In some limit, these randomized solutions must appear as the ray solutions. Optical fibers are generally characterized by their numerical aperture (NA), as well as the number which characterizes its transverse dimension. The numerical aperture is essentially the sine of the maximum angle into which the guide will radiate into free space. When the guide is multimoded, then the transverse dimension is generally given as a diameter. When a guide is single-moded, the transverse dimension is generally given as a spotsize, that is, by a measure of the size of a unity magnification image of the fiber endface. Multimode guides can be excited by even poorly coherent sources so long as they radiate into the NA or capture angle at the input of the guide. Single-mode fibers require an excitation which matches the shape and size of their fundamental mode.

Active Fiber Compatible Components

Our discussion of propagation in fiber optic waveguides would be a rather sterile one if there were not a number of fiber compatible components that can generate, amplify, and detect light streams available to us in order to construct fiber optic systems. In this section, we will try to discuss some of the theory of operation of active optical components in order to help elucidate some of the general characteristics of such components and the conditions that inclusion of such components in a fiber system impose on the form that the system must take.

In a passive component such as an optical fiber, we need only consider the characteristics of the light that is guided. Operation of active components requires that the optical fields interact with a medium in such a manner that energy can be transferred from the field through an excitation of the medium to the controlling electrical stream and/or vice versa. Generally one wants the exchange to go only one way, that is from field to electrical stream or from electrical stream to field. In a detector this is not difficult to achieve, whereas in lasers and amplifiers it is quite hard to eliminate the back reaction of the field on the device. Whereas a guiding medium can be considered as a passive homogeneous continuum, the active medium has internal degrees of freedom of its own as well as a granularity associated with the distribution of the microscopic active elements. At least, we must consider the active medium as having an active index of refraction with a mind (set of differential equations anyway) of its own. If one also wants to consider noise characteristics, one needs to consider the lattice of active elements which convert the energy. The wavelength of operation of that active medium is determined by the energy spacing between the upper and lower levels of a transition which is determined by the microscopic structure of these grains, or quanta, that make up the medium. In a semiconductor, we consider these active elements to be so uniformly distributed and ideally spaced that we can consider the quanta (electron hole pairs) to be delocalized but numerous and labeled by their momentum vectors. In atomic media such as the rare earth doped optical fibers which serve as optical amplifiers, we must consider the individual atoms as the players. In the case of the semiconductor, a current, flowing in an external circuit, controls the population of the upper (electronic) and lower (hole) levels of each given momentum state within the semiconductor. When the momentum states are highly populated with electrons and holes, there is a flow of energy to the field (at the transition wavelength) and when the states are depopulated, the field will tend to be absorbed and populate the momentum states by giving up its energy to the medium. The situation is similar with the atomic medium except that the pump is generally optical (rather than electrical) and at a different wavelength than the wavelength of the field to be amplified. That is to say, one needs to use a minimum of three levels of the localized atoms in the medium in order to carry out an amplification scheme.

The composition of a semiconductor determines its bandgap, that is, the minimum energy difference between the electron and hole states of a given momentum value. A source, be it a light emitting diode (LED) or laser diode (see Figure 4) will emit light at a wavelength which corresponds to an energy slightly above the minimum gap energy (wavelength equals the velocity of light times Planck's constant divided by energy) whereas a detector can detect almost any energy above the bandedge. Only semiconductors with bandgaps which exhibit a minimum energy at a zero momentum transfer can be made to emit light strongly. Silicon does not exhibit a direct gap and although it can be used as a detector, it cannot be used as a source material. The silicon laser is and has been the 'Holy Grail' of electronics because of the ubiquity of silicon electronics. To even believe that a 'Holy Grail' exists requires a leap of faith. Weak luminescence has been



Figure 4 A schematic depiction of the workings of a semiconductor laser light source. The source is fabricated as a diode, and normal operation of this diode is in forward bias, that is, the p-side of the junction is biased positively with respect to ground which is attached to the n-side of the junction. With the p-side positively biased, current should freely flow through the junction. This is not quite true as there is a heterojunction region between the p- and n-regions in which electrons from the n-side may recombine with holes from the p-side. This recombination gives off a photon which is radiated. In light emitting diodes (LEDs), the photon simply leaves the light source as a spontaneously emitted photon. In a laser diode, the heterojunction layer serves as a waveguide and the endfaces of the laser as mirrors to provide feedback and allow laser operation in which the majority of the photons generated are generated in stimulated processes.

observed in certain silicon structures. This luminescence has been used for mid-infrared sources (where thermal effects mask strong luminescence) and in concert with rare earth dopants to make visible light emitting diodes. The silicon laser is still only a vision.

Source materials are, therefore, all made of compound semiconductors. Detectors are in essence the inverse of sources (see Figure 5) but also must detect at wavelengths above their gap energy. For primarily historical reasons, as will be further discussed below, telecommunications employs essentially three windows of wavelengths for different applications, wavelengths centered about 0.85 microns in the first window, wavelengths about 1.3 microns in the second window, and wavelengths about 1.55 microns in the third window. Materials made of layers of different compositions of AlGaAs and mounted on GaAs substrates are used in the first band, while the other bands require the increased degree of freedom allowed by the quaternary alloys of InGaAsP mounted on InP substrates. Other material mixes are possible, these above-mentioned materials are the most common. Rare earth ions exhibit many different transitions. The most useful ones have proven to be the transitions of Er in the third telecommunications window, the one that covers the spectral region to either side of 1.55 microns. Although both Nd and Pr can be made to amplify near the 1.3 micron window, amplifiers made of these materials have not proven to be especially practical.



Figure 5 A schematic depiction of the workings of a semiconductor detector. As with a semiconductor source, the detector is fabricated to operate as a diode, that is a p-n junction, but in the case of the detector this diode is to be operated only in reverse bias, that is, with the n-material being biased positively with respect to the ground which is attached to the p-material's contact. In this mode of operation, no current should flow through the junction as there are no free carriers in the material, they have all been drawn out through the contacts. A photon of sufficiently high energy can change this situation by forming an electron hole pair in the material. The electron and hole are thereafter drawn to the n- and p-contacts, respectively, causing a detectable current to flow in the external circuit.

Telecommunications Technology

The physical transmission layer of the worldwide telecommunications network has come to be dominated by fiber optic technology, in particular, by wavelength division multiplexed or WDM single-mode fiber optics operating in the 1.55 micron telecommunications window. In the following, we will first discuss how this transformation to optical communications took place and then go on to discuss some of the specifics of the technology.

Already by the middle of the 1960s, it was clear that changes were going to have to take place in order that the exponential growth of the telephone system in the United States, as well as in Europe, could continue. The telephone system then, pretty much as now, consisted of a hierarchy of tree structures connected by progressively longer lines. A local office is used to connect a number of lines emanating in a tree structure to local users. The local offices are connected by trunk lines which emanate from a toll office. The lines from there on up the hierarchy are long distance ones which are termed long lines and can be regional and longer. The most pressing problem in the late 1960s was congestion in the so-called trunk lines which connect the local switching offices. The congestion was naturally most severe in urban areas. These trunk lines were generally one kilometer in length at that time. The problem was that there was no more space in the ducts that housed these lines. A solution was to use time division multiplexing or TDM to increase the traffic that could be carried by each of the lines already buried in the conduit. The problem was that the twisted pair lines employed would smear out the edges of the time varying bit streams carrying the information at the higher bitrates (aggregated rates due to the multiplexing) due to the inherent dependence of signal propagation velocity on frequency known as dispersion. After discussion and even development of a number of possible technologies, in 1975 a demonstration of a fiber optic system which employed multimode semiconductor lasers feeding multimode optical fibers all operating at 0.85 micron wavelength, proved to be the most viable model for trunk line replacement. The technology was successful and already in 1980 advances in single-mode laser and single-mode fiber technology operating at the 1.3 micron wavelength had made the inclusion of fiber into the long lines viable as well. For roughly the decade from 1985 onward, single-mode fiber systems dominated long line replacement for terrestrial as well as transoceanic links. The erbium doped fiber amplifier which operated in the 1.55 micron wavelength third telecommunication window had proven itself to be viable for extending repeater periods by around 1990. Development of the InGaAsP quaternary semiconductor system allowed for reliable lasers to be manufactured for this window as development of strained lattice laser technology in the InGaAs system allowed for efficient pump lasers for the fiber amplifiers. As the optical amplifiers could amplify across the wavelength band that could be occupied by many aggregated channels of TDM signals, the move of the long line systems to the third telecommunications window was accompanied by the adoption of wavelength division multiplexing or WDM. That is, electronics becomes more expensive as the analog bandwidth it can handle increases. Cost-effective digital rates are now limited to a few Gb/s, and analog rates to perhaps 20 GHz. Optical center frequencies are in the order of 2×10^{14} Hz and purely optical filters can be made to cleanly separate information signals spaced as closely as 100 GHz apart on optical carriers. An optical carrier can then be made to carry hundreds of channels of 10 Gb/s separated by 100 GHz and this signal can be propagated thousands of kilometers through the terrestrial fiber optics network. Such is today's Worldwide Web.

Integrated Optics as a Future of Guided Wave Optics

As electronics has been pushed to ever greater levels of integration, its power has increased and its price has dropped. A goal implicit in much of the development of planar waveguide technology has been that optics could become an integrated technology in the same sense as electronics. This has not occurred and probably will not occur. This is not to say that integrated optical processing circuits are not being developed and that they will be not employed in the future. They most definitely will.

Integrated optics was coined as a term when it was used in 1969 to name a new program at Bell Laboratories. This program was aimed at investigation of all the technologies that were possible with which to fabricate optical integrated circuits. The original effort was in no way driven by fiber optics as the Bell System only reluctantly moved to a fiber optic network solution in 1975. The original integrated optics efforts were based on such technologies as the inorganic crystal technologies that allowed for large second-order optical nonlinearities, a necessity in order that a crystal also exhibits a large electro-optic coefficient. An electro-optic coefficient allows one to change the index of refraction of a crystal by applying a low frequency or DC electromagnetic field across the crystal.



Figure 6 A schematic depiction of an integrated optical device which is often used as a high speed modulator. The device is an integrated version of a Mach–Zehnder interferometer. The basic idea behind its operation is that spatially and temporally coherent light is input into a single mode optical channel. That channel is then split into two channels by a Y-junction. Although not depicted in the figure, the two arms should not have completely equivalent propagation paths. That is to say, that if the light in one of those paths propagates a slightly longer distance (as measured in terms of phase fronts of the wave) then one cannot recombine the power from the two arms. That is, in the second Y-junction, a certain amount of the light which we are trying to combine from the two arms will be radiated out from the junction. In fact, if the light were temporally incoherent (phase fronts not well defined), exactly half of the light would be radiated form the junction. This is a statement of the brightness theorem which was thought to be a law of propagation before there were coherent sources of light. In a high speed modulator, the substrate is an electro-optic crystal and electrodes are placed over the two arms which apply the electrical signal to be impressed on the optical carrier to the channels.

Lithium niobate technology is a technology that has lasted to the present as an optical modulator technology (see Figure 6) and an optical switch technology (see Figure 7), as well as a technology for parametric wavelength conversion. Unfortunately, although low loss passive waveguide can be fabricated in lithium niobate, the crystal is not amenable to any degree of monolithic integration. Glass was also investigated as an integration technology from the early days of integrated optics, but the lack of second-order nonlinearity in glass strictly limited its applicability. Attention for a period turned to monolithic integration in the semiconductor materials which were well progressing as for use as lasers, detectors, and integrated circuits. Semiconductor crystals, however, are too pure to allow for low loss light propagation which requires the material defects to be so numerous that optical wavelengths cannot sample them. Passive waveguides in semiconductors incur huge losses that can only be mitigated by almost constant optical amplification which, unfortunately, cannot track the rapid optical field variations necessary for information transfer. Early on, attention turned to silicon



Figure 7 A schematic depiction of an integrated optical device which is often used as an optical switch. This device is interferometric but really has no free space optics counterpart as the Mach–Zhender interferometer does. In this interferometer, spatially and temporally coherent light is input into a single mode input channel. The two single optical mode input channels, which are initially so far apart from each other in terms of their mode sizes that they are effectively uncoupled, are then brought ever closer together until they are strongly coupled and their modes are no longer confined to their separate waveguides but are shared between the two channels. As the channels are symmetric, but the initial excitation, if from a single waveguide alone, is not, the pattern must evolve with propagation. Were both input channels excited, symmetry would still require a symmetry of their phases. If the phases were either equal to each other or completely out of phase, then there would be no evolution because we would have excited coupler modes. If the coupled region is the proper length, light input to one channel will emerge from the other after the channels are pulled apart. If the substrate is an electro-optic crystal and electrodes are placed over the channels, application of a voltage can affect the evolution of the interference in such a manner so as to 'decouple' the channels and switch the light back to the original channel.

optical bench technology, a technology which has presently spawned micro-electro-mechanical-system (MEMs) technology and still persists as an expensive vehicle to hybrid electro-optical integration. In silicon bench, individual components are micro-mounted with solder or silicon pop-up pieces on a silicon wafer which serves as a micro-optical bench. The technology is expensive and hybrid but pervasive in the highest end of cost classes of optical systems.

The tremendous success of the fiber optical network spawned a movement in which groups tried to achieve every possible system functionality in fibers themselves. A notable success has been the optical fiber amplifier. Significantly less successful in the fiber optic network has been the fiber Bragg grating. Attempts to carry out WDM functionalities in all fiber configuration leads to unwieldy configurations requiring large amounts of fiber and significant propagation delays, although, Bragg grating sensors have proven to be somewhat useful in sensing applications. WDM functions have been implemented in a large number of different hybrid configurations, involving various types of glasses, fused silica on silicon and simple hybrids of birefringent crystals.

The telecommunications network is not the driver that it once was. That this is so is perhaps the strongest driving force yet for integrated optics. The driver now is new applications that must be implemented in the most efficient manner. The most efficient manner is quite generally the one in which there is a maximum degree of integration. In the long run, polymer has always been the winning technology for optics of any kind, due to the flexibility of the technology and the drop in cost that accompanies mass production. Indeed, polymer integrated optics progresses. There are also a number of researchers involved in investigating strongly guiding optics, so-called photonic crystal optics. That is, in order to achieve low loss as well as low cost, the fiber and integrated optic waveguides up to the present have used small variations in optical properties of material to achieve guidance at the cost of having structures that are many wavelengths in size. In radio frequency (RF) and microwave technology, for example, guides are tiny fractions of a wavelength. This can lead to an impedance matching problem. RF and microwave impedance matching costs (versus circuit impedance matching costs) are generally quite high, precluding mass application. That radio frequency systems, such as cell phone transceivers link to the rest of the world by antenna, allows that the overall circuit dimension can be kept less than a single wavelength and impedance matching can be foregone in this so-called circuit limit. It is usually hard to keep an overall microwave system to less than a wavelength in overall extent except in the cell phone case or in a microwave oven. Optical miniaturization will require high index contrast guides, and will require optical impedance matching. There are few complete optical systems which will comprise less than an optical wavelength in overall extent. But then this so-called photonic crystal technology will likely be polymer compatible and there may be ways to find significant cost reduction. The future of integrated optics is unclear but bright.

See also

Fiber and Guided Wave Optics: Dispersion; Fabrication of Optical Fiber; Light Propagation; Measuring Fiber Characteristics; Nonlinear Effects (Basics); Nonlinear Optics; Optical Fiber Cables; Passive Optical Components. **Optical Communication Systems:** Wavelength Division Multiplexing.

Further Reading

Agrawal GP (1995) *Fiber-Optic Communication Systems*. New York: Wiley.

Bette, DeMarchis G and Iannone (1995) *Coherent Communications*. New York: Wiley.

Haken H (1985) *Light*. New York: Elsevier North-Holland.

Hecht E (1998) *Optics*. Reading, MA: Addison-Wesley.

Klein MV and Furtak TE (1986) *Optics*. New York: Wiley.

Marcuse D (1982) *Light Transmission Optics*. New York: Van Nostrand Reinhold.

Marcuse D (1991) *Theory of the Dielectic Optical Waveguide*. Boston, MA: Academic Press.

Mickelson AR, Lee Y-C and Basavanhally NR (1997) *Optoelectronic Packaging*. New York: Wiley.

Saleh BAA and Teich MC (1991) *Fundamentals of Photonics*. New York: Wiley.

Yariv A (1997) *Optical Electronics in Modern Communications*. New York: Van Nostrand Reinhold.

Dispersion

L Thévenaz, École Polytechnique Fédérale de Lausanne, Lausanne, Switzerland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Dispersion designates the property of a medium to propagate the different spectral components of a wave with a different velocity. It may originate from the natural dependence of the refractive index of a dense material to the wavelength of light, and one of the most evident and magnificent manifestations of dispersion is the appearance of a rainbow in the sky. In this case dispersion gives rise to a different refraction angle for the different spectral components of the white light, resulting in an angular dispersion of the sunlight spectrum and explicating the etymology of the term dispersion. Despite this spectacular effect, dispersion is mostly seen as an impairment in many applications, in particular for optical signal transmission. In this case, dispersion causes a rearrangement of the signal spectral components in the time domain, resulting in temporal spreading of the information and eventually in severe distortion.

There is a trend to designate all phenomena resulting in a temporal spreading of information as a type of dispersion, namely the polarization dispersion in optical fibers that should be properly named as polarization mode delay (PMD). In this article chromatic dispersion will be solely addressed, that designates the dependence of the propagation velocity on wavelength and that corresponds to the strict etymology of the term.

Effect of Dispersion on an Optical Signal

An optical signal may always be considered as a sum of monochromatic waves through a normal Fourier expansion. Each of these Fourier components propagates with a different phase velocity if the optical medium is dispersive, since the refractive index n depends on the optical frequency ν. This phenomenon is linear and causal and gives rise to a signal distortion that may be properly described by a transfer function in the frequency domain.

Let $n(\nu)$ be the frequency-dependent refractive index of the propagation medium. When the optical wave propagates in a waveguiding structure the effective wavenumber is properly described by a propagation constant β, that reads:

$$\beta(\nu) = \frac{2\pi\nu}{c_0} n(\nu) \qquad [1]$$

where c_0 is the vacuum light velocity. The propagation constant corresponds to an eigenvalue of the wave equation in the guiding structure and normally takes a different value for each solution or propagation mode. For free-space propagation this constant is simply equal to the wavenumber of the corresponding plane wave.

The complex electrical field $E(z,t)$ of a signal propagating in the z direction may be properly described by the following expression:

$$\begin{aligned} &E(z,t) = A(z,t)\, \mathrm{e}^{\mathrm{i}(2\pi\nu_0 t - \beta_0 z)} \\ &\quad \text{with} \quad \nu_0\text{: the central optical frequency} \\ &\quad \text{and} \quad \beta_0 = \beta(\nu_0) \end{aligned} \qquad [2]$$

where $A(z,t)$ represents the complex envelope of the signal, supposed to be slowly varying compared to the carrier term oscillating with the frequency ν_0. Consequently, the signal will spread over a narrow band around the central frequency ν_0 and the propagation constant β can be conveniently approximated by a limited expansion to the second order:

$$\beta(\nu) = \beta_0 + \left.\frac{\mathrm{d}\beta}{\mathrm{d}\nu}\right|_{\nu=\nu_0} (\nu - \nu_0) + \left.\frac{\mathrm{d}^2\beta}{\mathrm{d}\nu^2}\right|_{\nu=\nu_0} (\nu - \nu_0)^2 \qquad [3]$$

For a known signal $A(0,t)$ at the input of the propagation medium, the problem consists in determining the signal envelope $A(z,t)$ after propagation over a distance z. The linearity and the causality of the system make possible a description using a transfer function $H_z(\nu)$ such as:

$$\tilde{A}(z,\nu) = H_z(\nu)\,\tilde{A}(0,\nu) \qquad [4]$$

where $\tilde{A}(z,\nu)$ is the Fourier transform of $A(z,t)$.

To make the transfer function $H_z(\nu)$ explicit, let us assume that the signal corresponds to an arbitrary harmonic function:

$$A(0,t) = A_0\,\mathrm{e}^{\mathrm{i}2\pi ft} \qquad [5]$$

Since this function is arbitrary and the signal may always be expanded as a sum of harmonic functions through a Fourier expansion, there is no loss of generality. The envelope identified as a harmonic function actually corresponds to a monochromatic wave of optical frequency $\nu = \nu_0 + f$ as defined by eqn [2]. Such a monochromatic wave will experience the following phase shift through propagation:

$$\begin{aligned} E(z,t) &= A_0\,\mathrm{e}^{\mathrm{i}[2\pi(\nu_0+f)t-\beta(\nu_0+f)z]} \\ &= A_0\,\mathrm{e}^{\mathrm{i}2\pi ft}\mathrm{e}^{\mathrm{i}[2\pi\nu_0 t-\beta(\nu_0+f)z]} \end{aligned} \qquad [6]$$

On the other hand, an equivalent expression may be found using the linear system described by eqns [2] and [4]:

$$\begin{aligned} E(z,t) &= A(z,t)\,\mathrm{e}^{\mathrm{i}(2\pi\nu_0 t-\beta_0 z)} \\ &= A_z\,\mathrm{e}^{\mathrm{i}2\pi ft}\,\mathrm{e}^{\mathrm{i}(2\pi\nu_0 t-\beta_0 z)} \end{aligned} \qquad [7]$$

Since eqns [6] and [7] must represent the same quantities and using the definition in eqn [4], a simple comparison shows that the transfer function must take the following form:

$$H_z(\nu) = \mathrm{e}^{-\,\mathrm{i}[\beta(\nu)z-\beta_0 z]} \qquad [8]$$

The transfer function takes a more analytical form using the approximation in eqn [3]:

$$H_z(\nu) = \mathrm{e}^{-\,\mathrm{i}2\pi(\nu-\nu_0)\tau_\mathrm{D}}\,\mathrm{e}^{-\,\mathrm{i}\pi D_\nu(\nu-\nu_0)^2 z} \qquad [9]$$

In the transfer function interpretation the first term represents a delay term. It means that the signal is delayed after propagation by the quantity:

$$\tau_\mathrm{D} = \frac{1}{2\pi}\frac{\mathrm{d}\beta}{\mathrm{d}\nu_0}z = \frac{z}{V_\mathrm{g}} \qquad [10]$$

where V_g represents the signal group velocity. This term therefore brings no distortion for the signal and thus states that the signal is replicated at the distance z with a delay τ_D.

The second term is the distortion term which is similar in form to a diffusion process and normally results in time spreading of the signal. In the case of a light pulse it will gradually broaden while propagating along the fiber, like a hot spot on a plate gradually spreading as a result of heat diffusion. The effect of this distortion is proportional to the distance z and to the coefficient D_ν, named group velocity dispersion (GVD):

$$D_\nu = \frac{1}{2\pi}\frac{\mathrm{d}^2\beta}{\mathrm{d}\nu^2} = \frac{\mathrm{d}}{\mathrm{d}\nu}\left(\frac{1}{V_\mathrm{g}}\right) \qquad [11]$$

It is important to point out that the GVD may be either positive (normal) or negative (anomalous) and the distortion term in the transfer function in eqn [9] may be exactly cancelled by propagating in a medium with D_ν of opposite sign. It means that the distortion resulting from chromatic dispersion is reversible and this is widely used in optical links through the insertion of dispersion compensators. These are elements made of specially designed fibers or fiber Bragg gratings showing an enhanced GVD coefficient, with a sign opposite to the GVD in the fiber.

From the transfer function in eqn [9] it is possible to calculate the impulse response of the dispersive medium:

$$h_z(t) = \frac{1}{\sqrt{i|D_\nu|z}}\,\mathrm{e}^{\mathrm{i}\pi\frac{(t-\tau_\mathrm{D})^2}{D_\nu z}} \qquad [12]$$

so that the distortion of the signal may be calculated by a simple convolution of the impulse response with the signal envelope in the time domain.

The effect of dispersion on the signal can be more easily interpreted by evaluating the dispersive propagation of a Gaussian pulse. In this particular case the calculation of the resulting envelope can be carried out analytically. If the signal envelope takes the following Gaussian distribution at the origin:

$$A(0,t) = A_0\,\mathrm{e}^{-\frac{t^2}{\tau_0^2}} \qquad [13]$$

with τ_0 the $1/e$ half-width of the pulse, the envelope at distance z is obtained by convoluting the initial envelope with the impulse response $h_z(t)$:

$$\begin{aligned} A(z,t) &= h_z(t) \otimes A(0,t) \\ &= A_0\sqrt{\frac{\mathrm{i}z_0}{z+\mathrm{i}z_0}}\,\mathrm{e}^{\mathrm{i}\pi\frac{(t-\tau_\mathrm{D})^2}{D_\nu(z+\mathrm{i}z_0)}} \end{aligned} \qquad [14]$$

where

$$z_0 = -\frac{\pi\tau_0^2}{D_\nu} \qquad [15]$$

represents the typical dispersion length, that is the distance necessary to make the dispersion effect noticeable.

The actual pulse spreading resulting from dispersion can be evaluated by calculating the intensity of the envelope at distance z:

$$|A(z,t)|^2 = A_0 \frac{\tau_0}{\tau(z)} \mathrm{e}^{-\frac{2(t-\tau_D)^2}{\tau^2(z)}} \qquad [16]$$

that is still a Gaussian distribution centered about the propagation delay time τ_D, with $1/e^2$ half-width:

$$\tau(z) = \tau_0\sqrt{1 + (z/z_0)^2} \qquad [17]$$

The variation of the pulse width $\tau(z)$ is presented in Figure 1 and clearly shows that the pulse spreading starts to be nonnegligible from the distance $z = z_0$. This gives a physical interpretation for the dispersion length z_0. It must be pointed out that there is a direct formal similarity between the pulse broadening of a Gaussian pulse in a dispersive medium and the spreading of a free-space Gaussian beam as a result of diffraction. Asymptotically for distances $z \gg z_0$, the pulsewidth increases linearly:

$$\tau(z) \simeq |D_\nu| \frac{z}{\pi\tau_0} \qquad [18]$$

It must be pointed out that the width increases proportionally to the dispersion D_ν, but also inversely proportionally to the initial width τ_0. This results from the larger spectral width corresponding to a narrower pulsewidth, giving rise to a stronger dispersive effect.



Figure 1 Variation of the $1/e^2$ half-width of a Gaussian pulse, showing the pulse spreading effect of dispersion. The dashed line shows the asymptotic linear spreading for large propagation distance.

The chromatic dispersion does not modify the spectrum of the transmitted light, as any linear effect. This can be straightforwardly demonstrated by evaluating the intensity spectrum of the signal envelope at any distance z, using the eqns [4] and [8]:

$$|\tilde{A}(z,\nu)|^2 = |H_z(\nu)\tilde{A}(0,\nu)|^2 = |\mathrm{e}^{-\mathrm{i}[\beta(\nu)z-\beta_0 z]}|^2|\tilde{A}(0,\nu)|^2 = |\tilde{A}(0,\nu)|^2 \qquad [19]$$

It means that the pulse characteristics in the time and frequency domains are no longer Fourier-transform limited, since after the broadening due to dispersion, the spectrum should normally spread over a narrower spectral width. This feature results from a re-arrangement of the spectral components within the pulse. This can be highlighted by evaluating the distribution of instantaneous frequency through the pulse. The instantaneous frequency ω_i is defined as the time-derivative of the wave phase factor $\phi(t)$ and is uniformly equal to the optical carrier pulsation $\omega_i = 2\pi\nu_0$ for the initial pulse, as can be deduced from the phase factor at $z = 0$ by combining eqns [2] and [13]. This constant instantaneous frequency means that all spectral components are uniformly present within the pulse at the origin.

After propagation through the dispersive medium the phase factor $\phi(t)$ can be evaluated by combining eqns [2] and [14] and evaluating the argument of the resulting expression. The instantaneous frequency ω_i is obtained after a simple time derivative of $\phi(t)$ and reads:

$$\omega_i(t) = \omega_0 + \frac{2\pi z}{D_\nu(z^2 + z_0^2)}(t - \tau_D) \qquad [20]$$

For $z > 0$ the instantaneous frequency varies linearly over the pulse, giving rise to a frequency chirp. The frequency components are re-arranged in the pulse, so that the lower frequency components are in the leading edge of the pulse for a normal dispersion $D_\nu > 0$ and the higher frequencies in the trailing edge. For an anomalous dispersion $D_\nu < 0$, the arrangement is opposite, as can be seen in Figure 2. The effect of this frequency chirp can be visualized in Figure 3, showing that the effect of dispersion is equivalent to a frequency modulation over the pulse. The chirp is maximal at position z_0 and the pulsewidth takes its minimal value τ_0 when the chirp is zero. It is evident with this description that the pulse broadening may be entirely compensated through propagation in a medium of opposite



Figure 2 Distribution of the instantaneous frequency through a Gaussian pulse. At the origin the distribution is uniform (left) and the dispersion induces a frequency chirp that depends on the sign of the GVD coefficient D_ν.



Figure 3 The dispersion results in a pulse broadening together with a frequency chirp, here for a normal GVD, that can be seen like a frequency modulation.

group velocity dispersion; this is equivalent to reversing the time direction in Figure 3. Moreover a pre-chirped pulse can be compressed to its Fourier-transform limited value after propagation in a medium with the proper dispersion sign. This feature is widely used for pulse compression after pre-chirping through propagation in a medium subject to optical Kerr effect.

The above description of the propagation of a Gaussian pulse implicitly states that the light source is perfectly coherent. In the early stages of optical communications it was not at all the case, since most sources were either light emitting diodes or multimode lasers. In this case the spectral extent of the signal was much larger than actually required for the strict need of modulation. Each spectral component may thus be considered as independently propagating the signal and the total optical wave can be identified to light merged from discrete sources emitting simultaneously the same signal at a different optical frequency. The group velocity dispersion will cause a delay $\delta\tau$ between different spectral components separated by a frequency interval $\delta\nu$ that can be simply evaluated by a first-order approximation:

$$\delta\tau = \frac{\mathrm{d}\tau_D}{\mathrm{d}\nu}\delta\nu = \frac{\mathrm{d}}{\mathrm{d}\nu}\left(\frac{z}{V_g}\right)\delta\nu = D_\nu z\delta\nu \qquad [21]$$

where eqns [10] and [11] have been used. The delay $\delta\tau$ is thus proportional to the GVD coefficient D_ν, to the propagation distance z and the frequency separation $\delta\nu$. This description can be extended to a continuous frequency distribution with a spectral width σ_ν, resulting to the following temporal broadening σ_τ:

$$\sigma_\tau = |D_\nu|\sigma_\nu z \qquad [22]$$

Traditionally the spectral characteristics of a source are given in units of wavelength and the GVD coefficient is expressed in optical fibers accordingly. Following the same description as above, the temporal broadening σ_τ, for a spectral width σ_λ in wavelength units, reads:

$$\sigma_\tau = |D_\lambda|\sigma_\lambda z \qquad [23]$$

Since equal spectral widths must give equal broadening the value of the GVD in units of wavelength can be deduced from the natural definition in frequency units:

$$D_\lambda = \frac{\mathrm{d}}{\mathrm{d}\lambda}\left(\frac{1}{V_g}\right) = \frac{\mathrm{d}}{\mathrm{d}\nu}\left(\frac{1}{V_g}\right)\frac{\mathrm{d}\nu}{\mathrm{d}\lambda} = -\frac{c_0}{\lambda^2}D_\nu \qquad [24]$$

It must be pointed out that the coefficient D_λ takes a sign opposite to D_ν; in other words, a normal dispersion corresponds to a negative GVD coefficient D_λ. It is usually expressed in units of picoseconds of temporal broadening, per nanometer of spectral width and per kilometer of propagating distance, or ps/nm km. For example, a pulse showing a spectral width of 1 nm propagating through a 100 km fiber having a dispersion D_λ of $+10$ ps/nm km, will experience, according to eqn [23], a pulse broadening σ_τ of $10 \times 1 \times 100 = 1000$ ps or 1 ns.

Material Group Velocity Dispersion

Any dense material shows a variation of its index of refraction n as a function of the optical frequency ν. This natural property is called material dispersion and is the dominant contribution in weakly guiding structures such as standard optical fibers. This natural dependence results from the noninstantaneous response of the medium to the presence of the electric field of the optical wave. In other words, the polarization field $P(t)$ corresponding to the material response will vary with some delay or inertia to the change of the incident electric field $E(t)$. This delay between cause and effect generates a memory-type response of the medium that may be described using a time-dependent medium susceptibility $\chi(t)$. The relation between medium polarization at time t and incident field results from the weighted superposition of the effects of $E(t')$ at all previous times $t' < t$. This takes the form of the following convolution:

$$P(t) = \varepsilon_0 \int_{-\infty}^{+\infty} \chi(t - t')E(t')\mathrm{d}t' \qquad [25]$$

Through application of a simple Fourier transform this relation reads in the frequency domain as:

$$P(\nu) = \varepsilon_0 \chi(\nu) E(\nu) \qquad [26]$$

showing clearly that the noninstantaneous response of the medium results in a frequency-dependent refractive index using the standard relationship with the susceptibility χ:

$$n(\nu) = \sqrt{1 + \chi(\nu)} \quad \text{where} \quad \chi(\nu) = \mathrm{FT}\{\chi(t)\} \qquad [27]$$

This means that a beautiful natural phenomenon such as a rainbow, originates on a microscopic scale from the sluggishness of the medium molecules to react to the presence of light. For signal propagation, it results in a distortion of the signal and in most cases in a pulse spreading, but the microscopic causes are in essence identical. This noninstantaneous response is tightly related to the molecules' vibrations that also give rise to light absorption. For this reason it is convenient to express the propagation in an absorptive medium by adding an imaginary part to the susceptibility $\chi(\nu)$:

$$\chi(\nu) = \chi'(\nu) + \mathrm{i}\chi''(\nu) \qquad [28]$$

so that the refractive index $n(\nu)$ and the absorption coefficient $\alpha(\nu)$ reads in a weakly absorbing medium:

$$n(\nu) = \sqrt{1 + \chi'(\nu)}$$
$$\alpha(\nu) = -\frac{2\pi\chi''(\nu)}{\lambda n(\nu)} \qquad [29]$$

Since the response of the medium, given by the time-dependent susceptibility $\chi(t)$ in eqn [25], is real and causal, the real and imaginary part of the susceptibility in eqn [28] are not entirely independent and are related by the famous Kramers–Kronig relations:

$$\chi'(\nu) = \frac{2}{\pi}\int_0^{\infty} \frac{s\chi''(\nu)}{s^2 - \nu^2}\mathrm{d}s$$
$$\chi''(\nu) = \frac{2}{\pi}\int_0^{\infty} \frac{\nu\chi'(\nu)}{\nu^2 - s^2}\mathrm{d}s \qquad [30]$$

Absorption and dispersion act in an interdependent way on the propagating optical wave and knowing either the absorption or the dispersion spectrum is theoretically sufficient to determine the entire optical response of the medium. The interdependence between absorption and dispersion is typically illustrated in Figure 4. The natural tendency is to observe a growing refractive index for increasing frequencies in low absorption regions. In this case, the dispersion is called normal and this is the most observed situation in transparency regions of a material, which obviously offer the largest interest for optical propagation. In an absorption line the tendency is opposite, a diminishing index for increasing wavelength, and such a response is called anomalous dispersion. The dispersion considered here is the phase velocity dispersion, represented by the slope of $n(\nu)$, that must not be mistaken with the group velocity dispersion (GVD) that only matters for signal distortion. The difference between these two quantities is clarified below.



Figure 4 Typical optical response of a transparent medium, showing the spectral interdependence between the absorption coefficient α and the index of refraction n.

To demonstrate that a frequency-dependent refractive index $n(\nu)$ gives rise to a group velocity dispersion and thus a signal distortion we use eqns [1] and [10], so the group velocity V_g can be expressed:

$$V_g = \frac{c_0}{N} \quad \text{with} \quad N = n + \nu\frac{\mathrm{d}n}{\mathrm{d}\nu} = n - \lambda\frac{\mathrm{d}n}{\mathrm{d}\lambda} \qquad [31]$$

N is called group velocity index and differs from the phase refractive index n only if n shows a spectral dependence. In a region of normal dispersion $(\mathrm{d}n/\mathrm{d}\nu) > 0$, the group index is larger than the phase index and this is the situation observed in the great majority of transparent materials. From eqn [31] and using eqn [24] the GVD coefficient D_λ can be expressed as a function of the refractive index $n(\lambda)$:

$$D_\lambda = \frac{\mathrm{d}}{\mathrm{d}\lambda}\left(\frac{1}{V_g}\right) = \frac{\mathrm{d}}{\mathrm{d}\lambda}\left(\frac{N}{c_0}\right) = -\frac{\lambda}{c_0}\frac{\mathrm{d}^2 n}{\mathrm{d}\lambda^2} \qquad [32]$$

The GVD coefficient is proportional to the second derivative of the refractive index n with respect to wavelength and is therefore minimal close to a point of inflexion of $n(\lambda)$. As can be seen in Figure 4 such a point of inflexion is always present where absorption is minimal, at the largest spectral distance from two absorption lines. It means that the conditions of low-group velocity dispersion and high transparency are normally fulfilled in the same spectral region of an optical dielectric material. In this region the phase velocity dispersion is normal at any wavelength, but the group velocity is first normal for shorter wavelengths, then is zero at a definite wavelength corresponding to the point of inflexion of $n(\lambda)$, and finally becomes anomalous for longer wavelengths. The situation in which normal phase dispersion and anomalous group dispersion are observed simultaneously is in no way exceptional.

In pure silica the zero GVD wavelength is at 1273 nm, but is subject to be moderately shifted to larger wavelengths in optical fibers, as a result of the presence of doping species to raise the index in the fiber guiding core. This shift normally never exceeds 10 nm using standard dopings; larger shifts are observed resulting from waveguide dispersion and this aspect will be addressed in the next section. The zero GVD wavelength does not strictly correspond to the minimum attenuation in silica fibers, because the dominant source of loss is Rayleigh scattering in this spectral region and not molecular absorption. This scattering results from fluctuations of the medium density as observed in any amorphous materials such as vitreous silica and is therefore a collective effect of many molecules that does not impinge on the microscopic susceptibility $\chi(t)$. It has therefore no influence on the material dispersion characteristics and this explains the reason for the minimal attenuation wavelength at 1550 nm, mismatching and quite distant from the zero material GVD at 1273 nm.

Material GVD in amorphous SiO_2 can be accurately described using a three-term Sellmeier expansion of the refractive index:

$$n(\lambda) = \sqrt{1 + \sum_{j=1}^{3} \frac{C_j \lambda^2}{\lambda^2 - \lambda_j^2}} \qquad [33]$$

and performing twice the wavelength derivative. The coefficients C_j and λ_j are found in most reference handbooks and result in the GVD spectrum shown in Figure 5. Such a spectrum explains the absence of interest for propagation in the visible region through optical fibers, the dispersion being very important in this spectral region. It also explains the large development of optical fibers in the 1300 nm region as a consequence of the minimal material dispersion there. It must be pointed out that it is quite easy to set up propagation in an anomalous GVD regime in optical fibers, since this regime is observed in the lowest attenuation spectral region. Anomalous dispersion makes possible interesting propagation features when combined with a third-order nonlinearity as the optical Kerr effect, namely soliton propagation and efficient spectral broadening through modulation instability.



Figure 5 Material dispersion of pure silica. The visible region (0.4–0.7 µm) shows a strong normal GVD that decreases when moving into the infrared and eventually vanishes at 1273 nm. In the minimum attenuation window (1550 nm) the material GVD is anomalous.

Waveguide Group Velocity Dispersion

Solutions of the wave equation in an optical dielectric waveguide such as an optical fiber are discrete and limited. These solutions, called modes, are characterized by an unchanged field distribution along the waveguides and by a uniform propagation constant β over the wavefront. This last feature is particularly important if one recall that the field extends over regions presenting different refractive indices in a dielectric waveguide. For a given mode, the propagation constant β defines an effective refractive index n_{eff} for the propagation by similarity to eqn [1]:

$$\beta = \frac{2\pi\nu}{c_0} n_{\text{eff}} \qquad [34]$$

The value of this effective refractive index n_{eff} is always bound by the value of the core index n_1 and of the cladding index n_2, so that $n_2 < n_{\text{eff}} < n_1$. For a given mode, the propagation constant β, and so the effective refractive index n_{eff}, only depend on a quantity called normalized frequency V that essentially scales the light frequency to the waveguide optical parameters:

$$V = \frac{2\pi}{\lambda} a \sqrt{n_1^2 - n_2^2} \qquad [35]$$

where a is the core radius. Figure 6 shows the dependence of the propagation constant β of the fundamental mode LP_{01} on the normalized frequency V. The variation is nonnegligible in the single-mode region and gives rise to a chromatic dispersion, since V depends on the wavelength λ, even in the fictitious case of dispersion-free refractive indices in the core and the cladding materials. This type of chromatic dispersion is called waveguide dispersion.

To find an expression for the waveguide dispersion in function of the guiding properties, let us define another normalized parameter, the normalized phase constant b, such as:

$$\beta = \frac{2\pi}{\lambda} \sqrt{n_2^2 + b(n_1^2 - n_2^2)} \qquad [36]$$

The parameter b takes values in the interval $0 < b < 1$, is equal to 0 when $n_{\mathrm{eff}} = n_2$ at the mode cutoff, and is equal to 1 when $n_{\mathrm{eff}} = n_1$. This latter situation is never observed and is only asymptotic for very large normalized frequencies V. Solving the wave equation provides the dispersion relation $b(V)$ and it is important to point out that this relation between normalized quantities depends only on the shape of the refractive index profile. Step-index, triangular or multiple-clad index profiles will result in different $b(V)$ relations, independently of the actual values of the refractive indices n_1 and n_2 and of the core radius a.

From the definitions in eqns [10] and [35] and in the fictitious case of an absence of material dispersion, the propagation delay per unit length reads:

$$\frac{1}{V_g} = \frac{1}{2\pi}\frac{d\beta}{d\nu} = \frac{1}{2\pi}\frac{d\beta}{dV}\frac{dV}{d\nu} = \frac{\lambda}{2\pi} V \frac{d\beta}{dV} \qquad [37]$$



Figure 6 Propagation constant β as a function of the normalized frequency V in a step-index optical fiber. The single mode region is in the range $0 < V < 2.405$.

so that the waveguide group velocity dispersion can be expressed using the relation in eqn [24]:

$$D_\lambda^{\mathrm{w}} = \frac{d}{d\lambda}\left(\frac{1}{V_g}\right) = \frac{d}{d\nu}\left(\frac{1}{V_g}\right)\frac{d\nu}{d\lambda} = -\frac{\nu}{\lambda}\frac{d}{d\nu}\left(\frac{1}{V_g}\right) = -\frac{1}{2\pi c_0} V^2 \frac{d^2\beta}{dV^2} \qquad [38]$$

The calculation of the combined effect of material and waveguide dispersions results in very long expressions in which it is difficult to highlight the relative effect of each contribution. Nevertheless, by making the assumption of weak guidance:

$$\frac{n_1 - n_2}{n_2} \simeq \frac{N_1 - N_2}{N_2} \ll 1 \qquad [39]$$

where N_1 and N_2 are the group indices in the core and the cladding, respectively, defined in eqn [31], the complete expression can be drastically simplified to obtain for the delay per unit length:

$$\frac{1}{V_g} = \frac{1}{c_0}\left[N_2 + (N_1 - N_2)\frac{d(bV)}{dV}\right] \qquad [40]$$

and for the total dispersion:

$$D_\lambda = D_2 + (D_1 - D_2)\frac{d(bV)}{dV} - (N_1 - N_2)\frac{N_2}{n_1}\frac{1}{\lambda c_0} V \frac{d^2(bV)}{dV^2} \qquad [41]$$

where

$$D_1 = -\frac{\lambda}{c_0}\frac{d^2 n_1}{d\lambda^2} \quad \text{and} \quad D_2 = -\frac{\lambda}{c_0}\frac{d^2 n_2}{d\lambda^2} \qquad [42]$$

are the material GVD in the core and the cladding, respectively.

The first two terms in eqn [41] represent the contribution of material dispersion weighted by the relative importance of core and cladding materials for the propagating mode. In optical fibers, the difference between D_1 and D_2 is small, so that this contribution can be often well approximated by D_2, independently of any guiding effects.

The last term represents the waveguide dispersion and is scaled by 2 factors:

- *The core-cladding index difference* $n_1 - n_2 \simeq N_1 - N_2$. The waveguide dispersion will be significantly enhanced by increasing the index difference between core and cladding.
- *The shape factor* $V(d^2(bV)/dV^2)$. This factor uniquely depends on the shape of the refractive index profile and may substantially modify the



Figure 7 Material, waveguide and total group velocity dispersions for: (a) step-index fiber; (b) triangular profile fiber. The waveguide dispersion can be significantly enhanced by changing the shape of the index profile, making possible a shift of the zero GVD to the minimum attenuation window.

spectral dependence of the waveguide dispersion, making possible a great variety of dispersion characteristics.

Due to this degree of freedom brought by waveguide dispersion it is possible to shift the zero GVD wavelength to the region of minimal attenuation at 1550 nm in silica optical fibers. Figure 7a shows the total group velocity dispersion of a step-index core fiber, together with the separate contributions of material and waveguide GVD. In this case, the material GVD is clearly the dominating contribution, while the small waveguide GVD results in a shift of the zero GVD wavelength from 1273 nm to 1310 nm. A larger shift could be obtained by increasing the core-cladding index difference, but this also gives rise to an increased attenuation from the doping and no real benefit can be expected from such a modification. In Figure 7b, the core shows a triangular index profile to enhance the shape factor in eqn [41], so that the contribution of waveguide GVD is significantly increased with no impairing attenuation due to excessive doping. This makes it possible to realize the ideal situation of an optical fiber showing a zero GVD at the wavelength of minimum attenuation. These dispersion-shifted fibers (DSF) have now become successful in modern telecommunication networks.

Nevertheless, the absence of dispersion favors the efficiency of nonlinear effects and several classes of fibers are now proposed, showing a small but nonzero GVD at 1550 nm, with positive or negative sign, nonzero DSF (NZDSF). By interleaving fibers with positive and negative GVDs it is possible to propagate along the optical link in a dispersive medium and thus minimize the impact of nonlinearities, while maintaining the overall GVD of the link close to zero and canceling any pulse spreading accordingly.

List of Units and Nomenclature

Chromatic dispersion [ps nm^{-1} km^{-1}]	D_λ
Electric field [V m^{-1}]	E
Group index	N
Group velocity [m s^{-1}]	V_g
Group Velocity Dispersion GVD [s^2 m^{-1}]	D_ν
Linear attenuation coefficient [m^{-1}]	α
Medium susceptibility	χ
Normalized frequency	V
Optical frequency [s^{-1}]	ν
Propagation constant [m^{-1}]	β
Propagation delay [s]	τ_D
Polarization density field [A s m^{-2}]	P
Refractive index	n
Vacuum light velocity [m s^{-1}]	c_0
Wavelength [m]	λ

See also

Dispersion Management. **Fiber and Guided Wave Optics:** Overview. **Fourier Optics**. **Nonlinear Optics, Basics:** Kramers–Kronig Relations in Nonlinear Optics.

Further Reading

Ainslie BJ and Day CR (1986) A review of single-mode fibers with modified dispersion characteristics. *IEEE Journal of Lightwave Technology* LT-4(8): 967–979.

Bass M (ed.) (1994) *Handbook of Optics*, sponsored by the Optical Society of America, 2nd edn, vol. II, chap. 10 & 33. New York: McGraw-Hill.

Buck JA (1995) In: Goodman JW (ed.) *Fundamentals of Optical Fibers*, chap. 1, 5, 6. New York: Wiley Series in Pure and Applied Optics.

Gloge D (1971) Dispersion in weakly guiding fibers. *Applied Optics* 10: 2442–2445.

Jeunhomme LB (1989) *Single Mode Fiber Optics: Principles and Applications*. Optical Engineering Series, No. 23. New York: Marcel Dekker.

Marcuse D (1974) *Theory of Dielectric Optical Waveguides*. Series on Quantum Electronics – Principles and Applications, chap. 2. New York: Academic Press.

Marcuse D (1980) Pulse distortion in single-mode fibers. *Applied Optics* 19: 1653–1660.

Marcuse D (1981) Pulse distortion in single-mode fibers. *Applied Optics* 20: 2962–2974.

Marcuse D (1981) Pulse distortion in single-mode fibers. *Applied Optics* 20: 3573–3579.

Mazurin OV, Streltsina MV and Shvaiko-Shvaikovskaya TP (1983) *Silica Glass and Binary Silicate Glasses (Handbook of Glass Data; Part A)* Series on Physical Sciences Data. Amsterdam: Elseviervol. 15, pp. 63–75.

Murata H (1988) *Handbook of Optical Fibers and Cables*. Optical Engineering Series, No. 15, chap. 2. New York: Marcel Dekker.

Saleh BEA and Teich MC (1991) In: Goodman JW (ed.) *Fundamentals of Photonics*, chap. 5, 8 & 22. New York: Wiley Series in Pure and Applied Optics.

Fabrication of Optical Fiber

D Hewak, University of Southampton,
Southampton, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The drawing of optical fibers from silica preforms has, over a short period of time, progressed from the laboratory to become a manufacturing process capable of producing millions of kilometers of telecommunications fiber a year. Modern optical fiber fabrication processes produce low-cost fiber of excellent quality, with transmission losses close to their intrinsic loss limit. Today, fiber with transmission losses of 0.2 dB per kilometer of fiber are routinely drawn through a two-stage process that has been refined since the 1970s.

Although fibers of glass have been fabricated and used for hundreds of years, it was not until 1966 that serious interest in the use of optical fibers for communication emerged. At this time, it was estimated that the optical transmission loss in bulk glass could be as low as 20 dB km^{-1} if impurities were sufficiently reduced, a level at which practical applications were possible. At this time, no adequate fabrication techniques were available to synthesize glass of high purity, and fiber-drawing methods were crude.

Over the next five years, efforts worldwide addressed the fabrication of low-loss fiber. In 1970, a fiber with a loss of 20 dB km^{-1} was achieved. The fiber consisted of a titania doped core and pure silica cladding. This result generated much excitement and a number of laboratories worldwide actively began researching optical fiber. New fabrication techniques were introduced, and by 1986, fiber loss had been reduced close to the theoretical limit.

All telecommunications fiber that is fabricated today is made of silica glass, the most suitable material for low-loss fibers. Early fiber research studied multicomponent glasses, which are perhaps more familiar optical materials; however, low-loss fiber, could not be realized, partly due to the lack of a suitable fabrication method. Today other glasses, in particular the fluorides and sulfides, continue to be developed for speciality fiber applications, but silica fiber dominates in most applications.

Silica is a glass of simple chemical structure containing only two elements, silicon and oxygen. It has a softening temperature of about 2,000°C at which it can be stretched, i.e. drawn into fiber. An optical fiber consists of a high purity silica glass core, doped with suitable oxide materials to raise its refractive index (Figure 1). This core, typically on the order of 2–10 microns in diameter, is surrounded by silica glass of lower refractive index. This cladding layer extends the diameter to typically 125 microns. Finally a protective coating covers the entire structure. It is the phenomenon of total internal reflection at the core cladding interface that confines light to the core and allows it to be guided. The basic requirements of an optical fiber are as follows:

1. The material used to form the core of the fiber must have a higher refractive index than the cladding material, to ensure the fiber is a guiding structure.



Figure 1 Structure of an optical fiber.

2. The materials used must be low loss, providing transmission with no absorption or scattering of light.
3. The materials used must have suitable thermal and mechanical properties to allow them to be drawn down in diameter into a fiber.

Silica (SiO_2) can be made into a glass relatively easily. It does not easily crystallize, which means that scattering from unwanted crystalline centers within the glass is negligible. This has been a key factor in the achievement of a low-loss fiber. Silica glass has high transparency in the visible and near-infrared wavelength regions and its refractive index can be easily modified. It is stable and inert, providing excellent chemical and mechanical durability. Moreover, the purification of the raw materials used to synthesize silica glass is quite straightforward.

In the first stage of achieving an optical fiber, silica glass is synthesized by one of three main chemical vapor processes. All use silicon tetrachloride ($SiCl_4$) as the main precursor, with various dopants to modify the properties of the glass. The precursors are reacted with oxygen to form the desired oxides. The end result is a high purity solid glass rod with the internal core and cladding structure of the desired fiber.

In the second stage, the rod, or preform as it is known, is heated to its softening temperature and stretched to diameters of the order of 125 microns. Tens to hundreds of kilometers of fiber are produced from a single preform, which is drawn continuously, with minimal diameter fluctuations. During the drawing process one or more protective coatings are applied, yielding long lengths of strong, low-loss fiber, ready for immediate application.

Preform Fabrication

The key step in preparing a low-loss optical fiber is to develop a technique for completely eliminating transition metal and OH ion contamination during the synthesis of the silica glass. The three methods most commonly used to fabricate a glass optical fiber preform are: the modified chemical vapor deposition process (MCVD); the outside vapor deposition process (OVD); and the vapor-axial deposition process (VAD).

In a typical vapor phase reaction, halide precursors undergo a high temperature oxidation or hydrolysis to form the desired oxides. The completed chemical reaction for the formation of silica glass is, for oxidation:

$$SiCl_4 + O_2 \rightarrow SiO_2 + 2Cl_2 \qquad [1]$$

For hydrolysis, which occurs when the deposition occurs in a hydrogen-containing flame, the reaction is:

$$SiCl_4 + 2H_2O \rightarrow SiO_2 + 4HCl \qquad [2]$$

These processes produce fine glass particles, spherical in shape with a size of the order of 1 nm. These glass particles, known as soot, are then deposited and subsequently sintered into a bulk transparent glass. The key to low-loss fiber is the difference in vapor pressures of the desired halides and the transition metal halides that cause significant absorption loss at the wavelengths of interest. The carrier gas picks up a pure vapor of, for example, $SiCl_4$, and any impurities are left behind.

Part of the process requires the formation of the desired core/cladding structure in the glass. In all cases, silica-based glass is produced with variations in refractive index produced by the incorporation of dopants. Typical dopants used are germania (GeO_2), titania (TiO_2), alumina (Al_2O_3), and phosphorous pentoxide (P_2O_5) for increasing the refractive index, and boron oxide (B_2O_2) and fluorine (F) for decreasing it. These dopants also allow other properties to be controlled, such as the thermal expansion of the glass and its softening temperatures. In addition, other materials, such as the rare earth elements, have also been used to fabricate active fibers that are used to produce optical fiber amplifiers and lasers.

MCVD Process

Optical fibers were first produced by the MCVD method in 1974, a breakthrough that completely solved the technical problems of low-loss fiber fabrication (Figure 2).

As shown schematically in Figure 3, the halide precursors are carried in the vapor phase by oxygen carrier gas into a pure silica substrate tube. An oxy-hydrogen burner traverses the length of the tube, which it heats externally. The tube is heated to temperatures of about 1,400°C which then oxidizes the halide vapor materials. The deposition temperature is sufficiently high to form a soot made of glassy particles which are deposited on the inside wall of the substrate tube but low enough to prevent the softened silica substrate tube from collapsing. The process usually takes place on a horizontal glass-working lathe.

During the deposition process, the repeated traversing of the burner forms multiple layers of soot. Changes to the precursors entering the tube and thus the resulting glass composition are introduced for layers which will form the cladding and then the core. The MCVD method allows germania to be doped into

Figure 2 Fabrication of an optical fiber preform by the MCVD method.



Figure 3 Schematic of preform fabrication by the MCVD method.

the silica glass and the precise control of the refractive index profile of the preform. When deposition is complete, the burner temperature is increased and the hollow, multilayered structure is collapsed to a solid rod. A characteristic of fiber formed by this process is a refractive index dip in the center of the core of the fiber. In addition, the deposition takes place in a closed system, which dramatically reduces contamination by OH^- ions and maintains low levels of other impurities. The high temperature allows high deposition rates compared to traditional chemical vapor deposition (CVD) and large performs, built up from hundreds of layers can be produced.

The MCVD method is still widely used today though it has some limitations, particularly on the preform size that can be achieved and thus the manufacturing cost. Diameter of the final preform is determined by the size of the initial silica substrate tube, which, due to the high purity required, accounts for a significant portion of the cost of the preform. A typical preform fabricated by MCVD yields about 5 km of fiber. Its success has spurred improvements to the process, in particular to address the fiber yield from a single preform.

OVD Process

The outside vapor deposition (OVD) methods, also known as outside vapor phase oxidation (OVPO), synthesize the fine glass particles within a burner flame. The precursors, oxygen, and fuel for the burner, are introduced directly into the flame. The soot is deposited onto a target rod that rotates and traverses in front of the burner. As in MCVD, the preform is built up layer by layer, though now initially by depositing the core glass and then building up the cladding layers over this. After the deposition process is complete, the preform is removed from the target rod and is collapsed and sintered into a transparent glass preform. The center hole remains, but disappears during the fiber drawing process. This technique has advantages in both size of preform which can be obtained and the fact that a high-quality silica substrate tube is no longer required. These two advantages combine to make a more economical process. From a single preform, several hundred kilometers of fiber can be produced.

VAD Process

The most recent refinement to the fabrication process was developed again to aid the mass production of high-quality fibers. In the VAD process, both core and cladding glasses are deposited simultaneously. Like OVD, the soot is synthesized and deposited by flame hydrolysis, as shown in Figure 4, the precursors are blown from a burner, oxidized, and deposited onto a silica target rod.

Burners for the VAD process consist of a series of concentrate nozzles. The first delivers an inert carrier and the main precursors $SiCl_4$, the second delivers an inert carrier glass and the dopants, the third delivers hydrogen fuel, and the fourth delivers oxygen. Gas flows are up to a liter per minute and deposition rates can be very high. With the VAD process, both core and cladding glasses can be deposited simultaneously. The main advantage is that this is a continuous process, as the soot which forms the core and cladding glasses are deposited axially onto the end of the rotating silica rod, it is slowly drawn upwards into a furnace which sinters and consolidates the soot into a transparent glass. The upward motion is such that the end at which deposition is occurring remains in a fixed position and essentially the preform is grown from this base.

The advantages of the VAD process are a preform without a central dip and, most importantly, the mass production associated with a continuous process. The glass quality produced is uniform and the resulting fibers have excellent reproducibility and low loss.



Figure 4 Schematic of preform fabrication by the VAD method.



Figure 5 A commercial scale optical fiber drawing tower.

Other Methods of Preform Fabrication

There are other methods of preform fabrication, though these are not generally used for today's silica glass based fiber. Some methods, such as fabrication of silica through sol–gel chemistry could not provide the large low-loss preforms obtained by chemical vapor deposition techniques. Other methods, such as direct casting of molten glass into rods, or formation of rods and tubes by extrusion, are better suited to and find application in other glass chemistries and speciality fibers.

Fiber Drawing

Once a preform has been made, the second step is to draw the preform down in diameter on a fiber drawing tower. The basic components and configuration of the drawing tower have remained unchanged for many years, although furnace design has become more sophisticated and processes like coating have become automated. In addition, fiber drawing towers have increased in height to allow faster pulling speeds (Figure 5).

Essentially, the fiber drawing process takes place as follows. The preform is held in a chuck which is mounted on a precision feed assembly that lowers the preform into the drawing furnace at a speed which matches the volume of preform entering the furnace to the volume of fiber leaving the bottom of the furnace. Within the furnace, the fiber is drawn from the molten zone of glass down the tower to a capstan, which controls the fiber diameter, and then onto a drum. During the drawing process, immediately below the furnace, is a noncontact device that measures the diameter of the fiber. This information is fed back to the capstan which speeds up to reduce the diameter or slows down to increase the fiber diameter. In this way, a constant diameter fiber is produced. One or more coatings are also applied in-line to maintain the pristine surface quality as the fiber leaves the furnace and thus to maximize the fiber strength.

The schematic drawing in Figure 6 shows a fiber drawing tower and its key components. Draw towers are commercially available, ranging in height from 3 m to greater than 20 m, with the tower height increasing as the draw speed increases.

Typical drawing speeds are on the order of $1\,\mathrm{m\,s^{-1}}$. The increased height is needed to allow the fiber to cool sufficiently before entering the coating applicator, although forced air-cooling of the fiber is commonplace in a manufacturing environment.



Figure 6 Schematic diagram of an optical fiber drawing tower and its components.

Furnaces

A resistance furnace is perhaps the most common and economical heating source used in a fiber drawing tower. A cylindrical furnace, with graphite or tungsten elements, provides heating to the preform by blackbody radiation. These elements must be surrounded by an inert gas, such as nitrogen or argon, to prevent oxidation. Gas flow and control is critical to prevent variations in the diameter of the fiber. In addition, the high temperature of the elements may lead to contamination of the preform surface that can then weaken the fiber.

An induction furnace provides precise clean heating through radio frequency (RF) energy that is inductively coupled to a zirconia susceptor ring. This type of furnace is cleaner than the graphite resistance type and is capable of continuous running for several months. It also has the advantage that it does not require a protective inert atmosphere and consequently the preform is drawn in a turbulence-free environment. These advantages result in high-strength fibers with good diameter control.

Diameter Measurement

A number of noncontact methods of diameter measurement can be applied to measure fiber diameter. These include laser scanning, interferometry, and light scattering techniques. To obtain precise control of the fiber diameter, the deviation between the desired diameter and the measured diameter is fed into the diameter control system. In order to cope with high drawing speeds, sampling rates as high as 1,000 times per second are used. The diameter control is strongly affected by the gas flow in the drawing furnace and is less affected by the furnace temperature variation. The furnace gas flow can be used to achieve suppression of fast diameter fluctuations. This is used in combination with drawing speed control to achieve suppression of both fast and slow diameter fluctuations. Current manufacturing processes are capable of producing several hundreds of kilometers of fiber with diameter variations of ± 1 micron.

There are two major sources of fiber diameter fluctuations: short-term fluctuations caused by temperature fluctuations in the furnace; and long-term fluctuations caused by variations in the outer diameter of the preform. Careful control of the furnace temperature, the length of the hot zone, and the flow of gas minimize the short-term fluctuations. Through optimization of these parameters, diameter errors of less than ± 0.5 microns can be realized. The long-term fluctuations in diameter are controlled by the feedback mechanism between the diameter measurement and the capstan.

Fiber Coating

A fiber coating is primarily used to preserve the strength of a newly drawn fiber and therefore must be applied immediately after the fiber leaves the furnace. The fiber coating apparatus is typically located below the diameter measurement gauge at a distance determined by the speed of fiber drawing, the tower height, and whether there is external cooling of the fiber. Coating is usually one of the limiting factors in the speed of fiber drawing. To minimize any damage or contamination of the pristine fiber leaving the furnace, this portion of the tower, from furnace to the application of the first coating, is enclosed in a clean, filtered-air chamber.

A wide variety of coating materials has been applied; however, conventional, commercial fiber generally relies on a UV curable polymer as the primary coating. Coating thickness is typically 50–100 microns. Subsequent coatings can then be applied for specific purposes. A dual coating is often used with an inner primary coating that is soft and an outer, secondary coating which is hard. This ratio of low to high elastic modulus can minimize stress on the fiber and reduce bending loss.

Alternative coatings include hermetic coatings of a low melting temperature metal, ceramics, or amorphous carbon. These can be applied in-line before the polymeric coating. Metallic coatings are applied by passing the fiber through a molten metal while ceramic or amorphous coatings utilize an in-line chemical vapor deposition reactor.

Types of Fiber

The majority of silica fiber drawn today is single mode. This structure consists of a core whose diameter is chosen such that, with a given refractive index difference between the core and cladding, only a single guide mode propagates at the wavelength of interest. With a discrete index difference between core and cladding, it is often referred to as a step index fiber. In typical telecommunications fiber, single mode operation is obtained with core diameters of 2–10 microns with a standard outer diameter of 125 microns.

Multimode fiber has core diameters considerably larger, typically 50, 62.5, 85, and 110 microns, again with a cladded diameter of 125 microns. Multimode fibers are often graded index, that is the refractive index is a maximum in the center of the fiber and smoothly decreases radially until the lower cladding index is reached. Multimode fibers find use in non-telecommunication applications, for example optical fiber sensing and medicine.

Single mode fibers, which are capable of maintaining a linear polarization input to the fiber, are known as polarization preserving fibers. The structure of these fibers provides a birefringence that removes the degeneracy of the two possible polarization modes. This birefringence is a small difference in the effective refractive index of the two polarization modes that can be guided and it is achieved in one of two ways. Common methods for the realization of this birefringence are an elliptical core in the fiber, or through stress rods, which modify the refractive index in one orientation. These fiber structures are shown in Figure 7.

While the loss minimum of silica-based fiber is near 1.55 microns, step index single-mode fiber offers zero dispersion close to 1.3 micron wavelengths and dispersion at the loss minimum is considerable. A modification of the structure of the fiber, and in particular a segmented refractive index profile in the core, can be used to shift this dispersion minimum to 1.55 microns. This fiber, illustrated in Figure 7 is known as dispersion shifted fiber. Similarly fibers, with a relatively low dispersion over a wide wavelength range, known as dispersion flattened fibers, can be obtained by the use of multiple cladding layers.



(a) Dispersion shifted fiber



(b) Polarization preserving fiber

Figure 7 Structure of (a) dispersion shifted fiber and (b) two methods of achieving polarization preserving fiber.

List of Units and Nomenclature

Dopants	Elements or compounds added, usually in small amounts, to a glass composition to modify its properties.
Fiber drawing	The process of heating and thus softening an optical fiber preform and then drawing out a thin thread of glass.
Fiber loss	The transmission loss of light as it propagates through a fiber, usually measured in dB of loss per unit length of fiber. Loss can occur through the absorption of light in the core or scattering of light out of the core.
Glass	An amorphous solid formed by cooling from the liquid state to a rigid solid with no long range structure.
Modified chemical vapor deposition (MCVD)	A process for the fabrication of an optical preform where gases flow into the inside of a rotating tube, are heated and react

	to form particles of glass which are deposited onto the wall of the glass tube. After deposition, the glass particles are consolidated into a solid preform.
Outside vapor deposition (OVD)	A process for the fabrication of an optical preform where glass soot particles are formed in an oxy-hydrogen flame and deposited on a rotating rod. After deposition, the glass particles are consolidated into a solid preform.
Preform	A fiber blank, a bulk glass rod consisting of a core and cladding glass composite which is drawn into fiber.
Refractive index	A characteristic property of glass, which is defined by the speed of light in the material relative to the speed of light in a vacuum.
Silica	A transparent glass formed from silicon dioxide.
Vapor-axial deposition	A process similar to OVD, where the core and cladding layers are deposited simultaneously.

See also

Detection: Fiber Sensors. **Fiber and Guided Wave Optics:** Dispersion; Light Propagation; Measuring Fiber Characteristics; Nonlinear Effects (Basics); Optical Fiber Cables. **Fiber Gratings**. **Optical Amplifiers:** Erbrium Doped Fiber Amplifiers for Lightwave Systems. **Optical Communication Systems:** Architectures of Optical Fiber Communication Systems; Historical Development; Wavelength Division Multiplexing. **Optical Materials:** Optical Glasses.

Further Reading

Agrawal GP (1992) *Fiber-Optic Communication Systems*. New York: John Wiley & Sons.

Bass M and Van Stryland EV (eds) (2001) *Fiber Optics Handbook: Fiber, Devices, and Systems for Optical Communications*. New York: McGraw-Hill Professional Publishing.

Fujiura K, Kanamori T and Sudo S (1997) Fiber materials and fabrications. In: Sudo S (ed.) *Optical Fiber Amplifiers*, ch. 4, pp. 193–404. Boston, MA: Artech House.

Goff DR and Hansen KS (2002) *Fiber Optic Reference Guide: A Practical Guide to Communications Technology*, 3rd edn. Oxford, UK: Butterworth-Heinemann UK.

Hewak D (ed.) (1998) *Glass and Rare Earth Doped Glasses for Optical Fibres*. EMIS Datareview Series, INSPEC. London: The Institution of the Electrical Engineers.

Keck DB (1981) Optical fibre waveguides. In: Barnoski MK (ed.) *Fundamentals of Optical Fiber Communications*. New York: Academic Press.

Li T (ed.) (1985) *Optical Fiber Communications: Fiber Fabrication*. New York: Academic Press.

Personick SD (1985) *Fiber Optics: Technology and Applications*. New York: Plenum Press.

Schultz PC (1979) In: Bendow B and Mitra SS (eds) *Fiber Optics*. New York: Plenum Press.

Light Propagation

F G Omenetto, Los Alamos National Laboratory,
Los Alamos, NM, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Optical fibers have become a mainstay of our modern way of life. From phone calls to the internet, their presence is ubiquitous. The unmatched ability that optical fibers have to transmit light is an amazing asset that, besides being strongly part of our present, is poised to shape the future.

The foundation of the unique ability of optical fibers to transmit light hinges on the well-known physical concept of total internal reflection. This phenomenon is described by considering the behavior of light traveling from one material (A) to a different material (B). When light traverses the interface of the two materials with a specific angle, its direction of propagation is altered with respect to the normal to the surface, according to the well-known Snell law which relates the incident angle (onto the interface between A and B) to the refracted angle (away from the interface between A and B). This is written as $n_A \sin i = n_B \sin r$, where i is the angle of incidence, r the angle of refraction, and n_A and n_B are the refractive indices of the materials A and B. Under appropriate conditions, a critical value of the incidence angle (i_{CR}) exists for which the light does not propagate into B and is totally reflected back into A. This value is given by $i_{CR} = \arcsin(n_A/n_B)$. It follows that total internal reflection occurs when light is traveling from a medium with a higher index of refraction into a medium with a lower index of refraction. As an approximation, this is the basic idea behind light propagation in fibers.

Optical fibers are glass strands that include a concentric core with a cladding wrapped around it. The index of refraction of the core is slightly higher than the index of refraction of the cladding, thereby creating the necessary conditions for the confinement of light within them. Such index mismatches between the core and the cladding are determined by using different materials for each, by doping the glass matrix before pulling the fiber to create an index gradient, by introducing macroscopic defects such as air-holes in the structure of the fiber cladding (such as in the recently developed photonic crystal fibers), or by using materials other than glass, such as polymers or plastic.

The real physical picture of light guiding in fibers is more complex than the conceptual description stated above. The light traveling in the fiber is, more precisely, an electromagnetic wave with frequencies that lie in the optical range, and the optical fiber itself constitutes an electromagnetic waveguide. As such, the waveguide supports guided electromagnetic modes which can take on a multitude of shapes (i.e., of energy distribution profiles), depending on the core/cladding index of refraction profiles. These profiles are often complex and determine the physical boundary conditions that influence the field distribution within the fiber. The nature of the fiber modes has been treated extensively in the literature where an in-depth description of the physical solutions can be found.

There are many distinguishing features that identify different optical fiber types. Perhaps the most important one, in relation to the electromagnetic modes that the fiber geometry supports, is the distinction that is made between single-mode fibers and multimode fibers. As the name implies, a single-mode fiber is an optical fiber whose index of refraction profile between core and cladding is designed in such a way that there is only one electromagnetic field distribution that the fiber can support and transmit. That is to say, light is propagated very uniformly across the fiber. A very common commercially used fiber of this kind is the Corning SMF-28 fiber, which is employed in a variety of telecommunication applications. Multimode fibers have larger cores and are easier to couple light into, yet the fact that many modes are supported implies that there is less control over the behavior of light during its propagation, since it is more difficult to control each individual mode.

The condition for single-mode propagation in optical fibers is determined during the design and manufacture of the fiber by its geometrical parameters and is specific to a certain operation wavelength. A quantity V is defined as $V = (2\pi/\lambda) \times a(n_{\mathrm{core}}^2 - n_{\mathrm{cladding}}^2)^{1/2}$, where a is the core radius and λ is the wavelength of light. For example, a step-index fiber (i.e., a fiber where the transition from the index of refraction of the core to the index of refraction in the cladding is abrupt), supports a single electromagnetic mode if $V < 2.405$.

Light propagation in optical fibers, however, is affected by numerous other factors besides the electromagnetic modes that the fiber geometry allows.

First, the ability to efficiently transmit light in optical fiber is dependent on the optical transparency of the medium that the fiber is made of. The optical transparency of the medium is a function of the wavelength (λ) of light that needs to be transmitted through the fiber. Optical attenuation is particularly high for shorter wavelengths and the transmission losses for ultraviolet wavelengths become considerably higher than in the near infrared. The latter region, due to this favorable feature, is the preferred region of operation for optical fiber based telecommunication applications. This ultimate physical limit is determined by the process of light being scattered off the atoms that constitute the glass, a process called Rayleigh scattering. The losses due to Rayleigh scattering are inversely proportional to the fourth power of the wavelength (losses $\propto \lambda^{-4}$), and therefore become quite considerable as λ is decreased.

The ability of optical fibers to transmit light over a certain set of wavelengths, is quantified by their optical attenuation. This parameter is defined as the ratio of the output power versus the input power and is usually measured in units of decibels (dB), i.e., attenuation (dB) $= 10 \log_{10}(\mathrm{P}_{\mathrm{out}}/\mathrm{P}_{\mathrm{in}})$.

The values that are found in the literature relate optical attenuation to distance and express the attenuation per unit length (such as dB/km). Single-mode fibers used in telecommunications are usually manufactured with doped silica glasses designed to work in the near infrared, in a wavelength range between 1.3 and 1.6 μm (1 μm $= 10^{-6}$ m) which provides the lowest levels of Rayleigh scattering and is located before the physical infrared absorption of silica (~1.65 μm) kicks in. Such fibers, which have been developed and refined for decades, have attenuation losses of less that 0.2 dB/km at a wavelength of 1.55 μm. Many other materials have been used to meet specific optical transmission needs. While silica remains by far the most popular material used for optical fiber manufacturing, other glasses are better suited for different portions of the spectrum: quartz glass can be particularly transmissive in the ultraviolet whereas plastic is sometimes conveniently used for short distance transmission in the visible.

The ability to collect light at the input of the fiber represents another crucial and defining parameter. Returning to total internal reflection, such an effect can only be achieved by sending light onto an interface at a specific angle. In fibers, the light needs to be coupled into a circular core and reach the core cladding interface at that specific geometrical angle. The measure of the ability to couple light in the fiber is referred to as 'coupling efficiency'. The core dimension defines the geometry of the coupling process which, in turn, determines the efficiency of the propagation of light inside the fiber. In order to be coupled efficiently and therefore guided within the fiber, the light has to be launched within a range of acceptable angles. Such a range is usually defined or derivable from the numerical aperture (NA) of the fiber which is approximately $\mathrm{NA} = (n_{\mathrm{core}}^2 - n_{\mathrm{cladding}}^2)^{1/2}$, or can be alternatively described as a function of the critical angle for total internal reflection within the fiber by $\mathrm{NA} = n_{\mathrm{core}} \sin i_{\mathrm{CR}}$. Also, light has to be focused into the core of the fiber and therefore the interplay between core size, focusability, and NA (i.e., acceptance angle) of the fiber influence the coupling efficiency into the fiber (which in turn affects transmission). Typical telecommunication fibers have a 10 μm core (a NA of ~ 0.2) and have very high coupling efficiencies (of the order of 70–80%). Specialized single mode fibers (such as photonic crystal fibers) can have core diameters down to a few microns, significantly lower coupling efficiencies, and high numerical apertures. Multimode fibers, in contrast, are easy to couple into given their large core size.

Other factors that contribute to losses during propagation are due to the physical path that the actual optical fiber follows. A typical optical fiber strand is rarely laid along a straight line. These types of losses are called bending losses and can be intuitively understood by thinking that when the fiber is straight, the light meets its total reflection condition at the core-cladding interface, but when the fiber bends, the interface is altered and varies the incidence conditions of light at the interface. If the bend is severe, light is no longer totally reflected and escapes from the fiber.

Another important issue that influences propagation arises when the light that travels through the fiber is sent in bursts or in pulses of light. Pulsed light is very important in fiber transmission because the light pulse is the carrier of optical information, most often representing a binary digit of data. The ability to transmit pulses reliably is at the heart of modern day telecommunication systems. The features that affect the transmission of pulses through optical fibers depend, again, largely on the structure and constituents of the fiber. One of the most important effects on pulsed light is dispersion. This phenomenon causes the broadening in time of the light pulses during their travel through the fiber. This can be easily explained by a Fourier analogy by thinking that a short pulse in time (such as the 10–20 picosecond pulse duration that is used for optical communications, $1 \text{ picosecond} = 10^{-12}$ seconds) has a large frequency content (i.e., is composed of a variety of 'colors'). Since the speed of light through bulk media, and therefore through the fiber constituent, depends on wavelength, different 'colors' will travel at different speeds, arriving at the end of the fiber slightly delayed with respect to one another. This causes a net pulse broadening and is dependent on the properties of the fiber that are depicted in the dispersion curve of the fiber. This type of dispersion is called chromatic dispersion and is dependent on the distance the pulse travels in the fiber. A measure of the pulse broadening can be calculated by multiplying the dispersion value for the fiber (measured in ps/km) at the wavelength of operation times and the distance in kilometers that the pulse travels.

There are other types of dispersion that affect pulses traveling through fibers: light with different polarization travels at a different speed, thereby causing an analogous problem to chromatic distortion. In multimode fibers, different modes travel with different properties. Dispersion issues are extremely important in the design of the next-generation telecommunication systems. As a push is made toward higher transmission capacity, pulses become shorter and these issues have to be dealt with carefully. Specifically, transmission of light in optical fibers becomes more complex because the interaction between the light and the fiber material constituents becomes nonlinear. As pulses become shorter, their energy is confined in a smaller temporal interval, making their peak power (which is equal to energy/time) increase. If the peak power becomes sufficiently high, the atoms that form the glass of which the fiber is made are excited in a nonlinear fashion adding effects that need to be addressed with caution. Energetic pulses at a certain wavelength change their shape during propagation and can become severely distorted or change wavelength (i.e., undergo a frequency conversion process), thereby destroying the information that they were meant to carry.

Several physical manifestations of optical nonlinearity affect pulsed light propagation, giving rise to new losses but also providing new avenues for efficient transmission.

Perhaps the most successful example of the positive outcome of nonlinear effects in fibers is the optical soliton. The latter is an extremely stable propagating pulse that is transmitted through the fiber undistorted, since it is a result of a peculiar balance between the linear distortion and nonlinear distortion that cancel each other by operating in a specific region of dispersion of the optical fiber (the anomalous dispersion region).

Nonlinear effects in fibers are an extremely rich area of study which, besides several drawbacks, carries immense opportunities if the nonlinearities can be controlled and exploited.

See also

Dispersion Management. **Nonlinear Optics, Applications:** Pulse Compression via Nonlinear Optics. **Solitons:** Optical Fiber Solitons, Physical Origin and Properties.

Further Reading

Hecht J (2001) *Understanding Fiber Optics*. New York: Prentice Hall.

Snyder AW and Love JD (1983) *Optical Waveguide Theory*. Boston: Kluwer Academic Press.

Agrawal GP (2001) *Nonlinear Fiber Optics*. San Diego: Academic Press.

Measuring Fiber Characteristics

A Girard, EXFO, Quebec, Canada

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The optical fiber is divided in two types: multimode and singlemode. Each type is used in different applications and wavelength ranges and is consequently characterized differently. Furthermore, the corresponding test methods also vary.

The optical fiber characteristics may be divided into four categories:

- The optical characteristics (transmission related);
- The dimensional characteristics;
- The mechanical characteristics; and
- The environmental characteristics.

These categories will be reviewed in the following sections, together with their corresponding test methods.

Fiber Optical Characteristics and Corresponding Tests Methods

The following sections will describe the following optical characteristics:

- attenuation;
- macrobending sensitivity;
- microbending sensitivity;
- cut-off wavelength;
- multimode fiber bandwidth;
- differential mode delay for multimode fibers;
- chromatic dispersion;
- polarization mode dispersion;
- polarization crosstalk; and
- nonlinear effects.

Attenuation

The spectral attenuation of an optical fiber follows exponential power decay from the power level at a cross-section 1 to the power level at cross-section 2, over a fiber length L, as follows:

$$P_2(\lambda) = P_1(\lambda) \cdot e^{-\gamma(\lambda)L} \qquad [1]$$

$P_1(\lambda)$ is the optical power transmitted through the fiber core cross-section 1, expressed in mW; $P_2(\lambda)$ is the optical power transmitted through the fiber core cross-section 2 away from cross-section 1, expressed in mW; $\gamma(\lambda)$ is the spectral attenuation coefficient in linear units, expressed in km^{-1}; and L is the fiber length expressed in km.

Attenuation may be characterized at one or more specific wavelengths or as a function of wavelength. In the later case, attenuation is referred to spectral attenuation. Figure 1 illustrates such power decay.

Equation [1] may be expressed in relative units as follows:

$$\log_{10} P_2 = (\log_{10} P_1) \cdot - \gamma L \cdot \log_{10} e \qquad [2]$$

P is expressed in dBm units using the following definition.



Figure 1 Power decay in an optical fiber due to attenuation.

The power in dBm is equal to 10 times the logarithm in base 10 of the power in mW; or

$$0\ \text{dBm} = 10\log_{10}(1\ \text{mW}) \qquad [3]$$

Then

$$\gamma(\lambda)[\text{km}^{-1}] = [(10\log_{10} P_1) - (10\log_{10} P_2)] \div L\log_{10} e \qquad [4]$$

$$\alpha(\lambda)[\text{dB/km}] = [P_1(\text{dBm}) - P_2(\text{dBm})]/L \qquad [5]$$

A new relative attenuation coefficient $\alpha(\lambda)$ with units of dB/km has been introduced, which is related to the linear coefficient $\gamma(\lambda)$ with units of km^{-1} as follows:

$$\alpha(\lambda) = (\log_{10} e)\cdot\gamma(\lambda) \approx 4{,}343\gamma(\lambda) \qquad [6]$$

$\alpha(\lambda)$ is the spectral attenuation coefficient of a fiber and is illustrated in Figure 2.

Test methods for attenuation

The attenuation may be measured by the following methods:

- cut-back method;
- backscattering method; and
- insertion loss method.

Cut-back method. The cut-back method is a direct application of the definition in which the power levels P_1 and P_2 are measured at two points of the fiber change of input conditions. P_2 is the power emerging from the far end of the fiber and P_1 is the power emerging from a point near the input after cutting the fiber.

The output power P_2 is recorded from the fiber under test (FUT) placed in the measurement setup. Keeping the launching conditions fixed, the FUT is cut to the cut-back length, for example 2 m from the launching point. The FUT attenuation, between the points where P_1 and P_2 have been measured, is calculated using P_1 and P_2, from the definition equations provided above.

Backscattering method. The attenuation coefficient of a singlemode fiber is characterized using bidirectional backscattering measurements. This method is also used for:

- attenuation uniformity;
- optical continuity;
- physical discontinuities;
- splice losses; and
- fiber length.

An optical time domain reflectometer (OTDR) is used for performing such characterization. Adjustment of laser pulsewidth and power is used to obtain a compromise between resolution (a shorter pulsewidth provides a better resolution but at lower power) and dynamic range/fiber length (higher power provides better dynamic range but with longer pulsewidth). An example of such an instrument is shown in Figure 3.

The measurement is applicable to various FUT configurations (e.g., cabled fiber in production or deployed in the field, fiber on a spool, etc.). Two unidirectional backscattering curves are obtained, one from each end of the fiber (Figure 4).

Each backscattering curve is recorded on a logarithmic scale, avoiding the parts at the two ends of the curves, due to parasitic reflections.

The FUT length is found from the time interval between the two ends of the backscattering loss



Figure 2 Typical spectral attenuation of a singlemode fiber.


FUT
Patchcord
OTDR
EXFO
FTB-300
Near-end connector
Far-end connector

Figure 3 The backscattering method (OTDR).


OTDR
dB
Span start
Mechanical splice (reflective event)
Span end
Fiber attenuation
Fusion splice (Nonreflective event)
Noise floor
2
3
4
5
6
7
20.0
15.0
10.0
5.0
0.0
2
4
6
8
10
12
14
16
18
km
Start
Quick Save
Storage
OTDR Report
Setup
Print
About
Exit
EXP
TYPICAL OTDR TRACE
97/08/08, 10:07

Figure 4 Unidirectional OTDR backscattering loss measurement.

curve together with the FUT group index of refraction, n_g, as:

$$L_f = c_{fs} \cdot \frac{\Delta T_f}{n_g} \qquad [7]$$

c_{fs} is the velocity of light in free space.

The bidirectional backscattering curve is obtained using two unidirectional backscattering curves and calculating the average loss between them. The end-to-end FUT attenuation coefficient is obtained from the difference between two losses divided by the difference of their corresponding distances.

Insertion loss method. The insertion loss method consists of the measurement of the power loss due to the FUT insertion between a launching and a receiving system, previously interconnected (reference condition). The powers P_1 and P_2 are evaluated in a less straightforward way than in the cut-back method. Therefore, this method is not intended for use in manufacturing.

The insertion loss technique is less accurate than the cut-back, but has the advantage of being non-destructive for the FUT. Therefore, it is particularly suitable in the field.


Cladding, n_C
$\sin \varphi = n_C/n_c$
Core, n_c
φ

Figure 5 Total internal reflection and macrobending effect on the light rays.

Macrobending Sensitivity

Macrobending sensitivity is the property by which there is a certain amount of light leaking (loss) into the cladding when the fiber is bent and the bending angle is such that the condition of total internal reflection is no longer met at the core-cladding interface. Figure 5 illustrates such a case.

Macrobending sensitivity is a direct function of the wavelength: the longer the wavelength and/or the smaller the bending diameter, the more loss the fiber experiences. It is recognized that 1625 nm is a wavelength that is very sensitive to macrobending (see Figure 6).

The macrobending loss is measured by the power monitoring method (OTDR, especially for field assessment, see Figure 6) or the cut-back method.

Microbending Sensitivity

Microbending is a fiber property by which the core-cladding concentricity randomly changed along


OTDR Advanced
macrobending1550(1550)
macrobending1310(1310)
30.00
29.50
29.00
28.50
28.00
1310 (1310)
1550 (1550)
2
A
B
1000
1500
2000
2500
3000
m
Quick Save
Storage
Report
OTDR Advanced
macrobending1625(1625)
macrobending1550(1550)
30.00
29.50
29.00
28.50
28.00
1625 (1625)
1550 (1550)
A
B
1000
1500
2000
2500
3000
m
Quick Save
Storage
Report

Measurements
4-pt. Splice loss
0.034 dB

Measurements
4-pt. Splice loss
0.083 dB

Figure 6 Macrobending sensitivity as a function of wavelength.

the fiber length. It causes the core to wobble inside the cladding and along the fiber length.

Four methods are available for characterizing microbending sensitivity in optical fibers:

- expandable drum for singlemode fibers and optical fiber ribbons over a wide range of applied linear pressure or loads;
- fixed diameter drum for step-index multimode, singlemode, and ribbon fibers for a fixed linear pressure;
- wire mesh and applied loads for step-index multimode and singlemode fibers over a wide range of applied linear pressure or loads; and
- 'basketweave' wrap on a fixed diameter drum for singlemode fibers.

The results from the four methods can only be compared qualitatively. The test is nonroutine for general evaluation of optical fiber.

Cut-off Wavelength

The cut-off wavelength is the shortest wavelength at which a single mode can propagate in a singlemode fiber. This parameter can be computed from the fiber refractive index profile (RIP). At wavelengths below the cut-off wavelength, several modes propagate and the fiber is no longer singlemode, but multimode.

In optical fibers, the change from multimode to singlemode behavior does not occur at a specific wavelength, but rather over a smooth transition as a function of wavelengths. Consequently, from a fiber-optic network standpoint, the actual threshold wavelength for singlemode performance is more critical. Thus an effective cut-off wavelength is described below.

The cut-off wavelength is defined as the wavelength greater than the ratio between the total power, in the higher-order modes and the fundamental mode, which has decreased to less than 0.1 dB. According to this definition, the second-order mode LP_{11} undergoes 19.3 dB more attenuation than the fundamental LP_{01} mode when the modes are equally excited.

Because the cut-off wavelength depends on the fiber length, bends, and strain, it is defined on the basis of the following three cases:

- fiber cut-off wavelength;
- cable cut-off wavelength; and
- jumper cable cut-off wavelength.

Fiber cut-off wavelength: Fiber cut-off wavelength λ_{fc} is defined for uncabled primary-coated fiber and is measured over 2 m with one loop of 140 mm radius loosely constrained, with the rest of the fiber kept essentially straight. The presence of a primary coating on the fiber usually will not affect λ_{fc}. However, the presence of a secondary coating may result in λ_{fc} being significantly shorter than that of the primary coated fiber.

Cable cut-off wavelength: Cable cut-off wavelength is measured prior to installation on a substantially straight 22 m cable length prepared by exposing 1 m of primary-coated fiber at both ends, the exposed ends each incorporating a 40 mm radius loop. Alternatively, this parameter may be measured on 22 m primary-coated uncabled fiber in the same configuration as for the λ_{fc} measurement.

Jumper cable cut-off wavelength: Jumper cable cut-off wavelength is measured over 2 m with one loop of 76 mm radius, or equivalent (e.g., split mandrel), with the rest of the jumper cable kept essentially straight.

Multimode Fiber Bandwidth for Multimode Fibers

The −3 dB bandwidth of a multimode optical fiber (or modal bandwidth) is defined as the lowest frequency where the magnitude of the baseband frequency response in optical power has decreased by 3 dB relative to the power at zero frequency. Modal bandwidth is also called intermodal dispersion as it takes into account the dispersion between the modes of propagation of the transmitted signal into the multimode fiber.

Various methods of reporting the results are available, but the results are typically expressed in terms of the −3 dB (optical power) frequency. Figure 7 illustrates modal bandwidth.

The bandwidth or pulse broadening may be normalized to a unit length, such as GHz · km, or ns/km.



Figure 7 Determination of modal bandwidth.

Two methods are available for determining transmission capacity of multimode fibers:

- the frequency domain measurement method in which the baseband frequency response is directly measured in the frequency domain by determining the fiber response to a sinusoidally modulated light source; or
- the optical time domain measurement method (pulse distortion) in which the baseband response is measured by observing the broadening of a narrow pulse of light.

Differential Mode Delay for Multimode Fibers

Differential mode delay (DMD) characterizes the modal structure of a graded-index glass-core multimode fiber. DMD is useful for assessing the bandwidth performance of a fiber when used with short-pulse, narrow spectral-width laser sources.

The output from a singlemode probe fiber excites the multimode FUT at the test wavelength. The probe spot is scanned across the FUT endface, and the optical pulse delay is determined at specified radial offset positions between an inner and an outer limit. DMD is the difference in optical pulse delay time between the FUT fastest and slowest modes excited for all radial offset positions between and including the inner and the outer limits.

The related critical issues influencing DMD are the temporal width of the optical pulse, jitter in the timing, the finite bandwidth of the optical detector, and the mode broadening due to the source spectral width and the FUT chromatic dispersion.

The test method is commonly used in production and research facilities, but is not easily accomplished in the field. DMD may be a good predictor of the source launching conditions. DMD may be normalized to a unit length, such as ps/m.

Chromatic Dispersion

Chromatic dispersion in a singlemode fiber is a combination of material dispersion and waveguide dispersion (see Figure 8), and it contributes to pulse broadening and distortion in a digital signal.

Material dispersion is produced by the dopants used in glass and is important in all fiber types. Waveguide dispersion is produced by the wavelength dependence of the index of refraction and is critical in singlemode fibers only.

From the point of view of the transmitter, this is due to two causes:



Figure 8 Contribution of the material and waveguide dispersions to the chromatic dispersion.



Figure 9 Difference between the phase and the group index of refraction.

- The presence of wavelengths in the source optical spectrum. Each wavelength has a different phase delay and group delay (different group velocities) along the fiber, because they travel under different index of refraction (or phase) as the index varies as a function of wavelengths, as shown in Figure 9.
- The other cause is the modulation of the source, which itself has two effects:
  - As bit-rates increase, the spectral width of the modulated signal increases and can become comparable to or exceed the spectral width of the source.
  - Chirp occurs when the source wavelength spectrum varies during the pulse. By convention, positive chirp at the transmitter occurs when the spectrum during the rise/fall of the pulse shifts towards shorter/longer wavelengths respectively. For a positive fiber dispersion coefficient, longer wavelengths are delayed relative to shorter wavelengths. Hence if the sign of the product of chirp and dispersion is positive, the two processes combine to produce pulse broadening. If the product is negative, pulse compression can occur over an initial fiber length until the pulse reaches a minimum width and then broadens again with increasing dispersion.

The electric field propagating into the FUT may be simply described as follows:

$$E(t, z) = E_0 \sin(\omega t - \beta z) \qquad [8]$$

$\omega = 2\pi c/\lambda$ [rad/s] is the angular frequency; $\beta = kn = (\omega/c)n$ is the effective index; as β has units of m^{-1} it is often referred to as wavenumber or even sometimes propagation constant; k is the propagation constant.

The group delay τ_g is then given by:

$$\mathrm{d}\beta/\mathrm{d}\omega = \beta_1 = \tau_g \qquad [9]$$

An example of the group delay spectral distribution is shown in Figure 10. Assuming n is not complex; β_1 is the first-order derivative of β.

The group velocity v_g is given by

$$v_g = (\mathrm{d}\beta/\mathrm{d}\omega)^{-1} = -(\lambda^2/2\pi c)(\mathrm{d}\beta/\mathrm{d}\lambda)^{-1} \qquad [10]$$

The FUT input–output delay is given by

$$\tau_d = L/v_g \qquad [11]$$

L is the FUT length.

The group index of refraction n_g is given by

$$n_g = c/v_g = n - \lambda(\mathrm{d}n/\mathrm{d}\lambda) \qquad [12]$$

The dispersion parameter or dispersion coefficient D (ps/nm · km) is given by

$$D = -(\omega/\lambda)(\mathrm{d}\tau_g/\mathrm{d}\omega) = -(2\pi c/\lambda^2)(\mathrm{d}^2\beta/\mathrm{d}\omega^2)$$
$$= -(\lambda/c)(\mathrm{d}^2 n/\mathrm{d}\lambda^2) \qquad [13]$$

$$\mathrm{d}^2\beta/\mathrm{d}\omega^2 = \beta_2 \qquad [14]$$

An example of the spectral distribution of D obtained from the group delay is shown in Figure 10.

β_2 (ps^2/km) is the group velocity dispersion parameter, so D may be related to β_2, as follows:

$$D = -(\omega/\lambda)\beta_2 \qquad [15]$$

When β_2 is positive then D is negative and vice-versa. The region where β_2 is positive is called normal dispersion while the negative-β_2 region is called anomalous dispersion.

At λ_0, β_1 is minimum, and $\beta_2 = 0$, then $D = 0$.

The dispersion slope S ($\mathrm{ps/nm^2 \cdot km}$), also called the differential dispersion parameter or second-order dispersion, is given by

$$S = \mathrm{d}D/\mathrm{d}\lambda = (\omega/\lambda)\beta_3 + (2\omega/\lambda^2)\beta_2 \qquad [16]$$

$$\beta_3 = \mathrm{d}\beta_2/\mathrm{d}\omega = \mathrm{d}^3\beta/\mathrm{d}\omega^3$$

At λ_0, β_1 is minimum, $\beta_2 = 0$, then $D = 0$; but S is not zero and depends on β_3. An example of the spectral distribution of S and S_0 is illustrated in Figure 10.

Overall, the general expression of β is given by

$$\beta(\omega) = \beta_0 + (\omega - \omega_0)\beta_1 + (1/2)(\omega - \omega_0)^2\beta_2$$
$$+ (1/12)(\omega - \omega_0)^3\beta_3 + \cdots \qquad [17]$$

Figure 11 illustrates the difference between dispersion unshifted fiber (ITU-T Rec. G.652), dispersion shifted fiber (ITU-T Rec. G.653) and nonzero dispersion shifted fiber (ITU-T Rec. G.655).

Test methods for the determination of chromatic dispersion

All methods measure the group delay at a specific wavelength over a range and use agreed fitting functions to evaluate λ_0 and S_0.

In the phase shift method, the group delay is measured in the frequency domain, by detecting, recording, and processing the phase shift of a sinusoidal modulating signal between a reference, a secondary fiber path, and the channel signal.

Setup variances exist and some do not require the secondary reference path. For instance, by using a reference optical filter at the FUT output it is possible to completely decouple the source from the phase-meter. With such an approach, chromatic dispersion may now be measured in the field over very long links using optical amplifiers (see Figure 12).



Figure 10 Relation between the pulse (group) delay and the (chromatic) dispersion.



Figure 11 Chromatic dispersion for various types of fiber.



Figure 12 Test results for field-related chromatic dispersion using the phase-shift technique.

In the differential phase shift method, two detection systems are used together with two wavelength sources at the same time. In this case the chromatic dispersion may be determined directly from the two group delays. This technique usually offers faster and more reliable results but costs much more than the phase-shift technique which is usually preferred.

In the interferometric method, the group delay between the FUT and a reference path is measured by a Mach–Zehnder interferometer. The reference delay line may be an air path or a singlemode fiber standard reference material (SRM). The method can be used to determine the following characteristics:

- longitudinal chromatic dispersion homogeneity; and
- effect of overall or local influences, such as temperature changes and macrobending losses.

In the pulse delay method, the group delay is measured in the time domain, by detecting, recording, and processing the delay experienced by pulses at various wavelengths.

Polarization Mode Dispersion

Polarization mode dispersion (PMD) causes an optical pulse to spread in the time domain and may impair the performance of a telecommunications system. The effect can be related to differential phase and group velocities and corresponding arrival time of different polarization components of the pulse signal. For a sufficiently narrowband source, the effect can be related to a differential group delay (DGD), $\Delta\tau$, between a pair of orthogonally polarized principal states of polarization (PSP) at a given wavelength or optical frequency (see Figure 13a).


Δτ
t
Fast axis
z,t
Δτ
Slow axis
(a)
Δτ
t
Fast axis
z,t
Δτ
Slow axis
(b)
Δτ
t
Fast axis
z,t
Δτ
Slow axis
(c)

Figure 13 PMD effect on the pulse broadening and its possible pulse impairment. (a) The pulse is spread by the DGD $\Delta\tau$ but the bit rate is too low to create an impairment. (b) The pulse is spread by the DGD $\Delta\tau$ but the bit rate is high enough to create an impairment. (c) The DGD $\Delta\tau$ is large enough even at low bit rate to make the pulse spreading and creating impairment.

In an ideal circular symmetric fiber, the two PSPs propagate with the same velocity. However:

- a real fiber is not perfectly circular;
- the core is not perfectly concentric with the cladding;
- the core may be subjected to microbending;
- the core may present localized clusters of dopants; and
- the environmental conditions may stress the deployed cable and affect the fiber.

Each time the fiber undergoes local stresses and consequently birefringence. These asymmetry characteristics vary randomly along the fiber and in time, lead to a statistical behavior of PMD.

For a deployed cabled fiber at a given time and optical frequency, there always exist two PSPs such that the pulse spreading due to PMD vanishes, if only one PSP is excited. On the contrary, the maximum pulse spread due to PMD occurs when both PSPs are equally excited, and is related to the difference in their group delays, the DGD associated with the two PSPs. For broadband transmission, the DGD statistically varies as a function of wavelengths or frequencies and result in an output pulse that is spread out in the time domain (see Figures 13a–c). In this case, the spreading can be related to the RMS (root mean square) of DGD values $\langle \Delta\tau^2 \rangle^{1/2}$. However, if a known distribution such as the Maxwell distribution may be fit to the DGD distribution probability, then a mean (or average) value of the DGD $\langle \Delta\tau \rangle$ may be correlated to the RMS value and used as a system performance predictor in particular with a maximum value of the DGD distribution associated to a low probability of occurrence. This maximum DGD may then be used to define the quality of service that would tolerate values lower than this maximum DGD.

Test methods for polarization mode dispersion

Three methods are generically used for measuring PMD. Other methods or analyses may exist but they are generally not standardized or are limited in their applications.

- Stokes parameter evaluation (SPE)
  - Jones matrix eigenanalysis (JME)
  - Poincaré sphere analysis (PSA)
- Fixed analyzer (FA)
  - Extrema counting (EC)
  - Fourier transform (FT)
- Interferometry (INTY)
  - Traditional analysis (TINTY)
  - General analysis (GINTY).

All methods use a linearly polarized source at the FUT input and are suitable for laboratory measurements of factory lengths of fiber and cable. However, the interferometric method is the only method appropriate for measurements of cabled fiber that may be moving or vibrating such as is found in the field.

Stokes parameter evaluation. SPE determines PMD by measuring a response to a change of narrowband light (from a tuneable light source with broadband detector – JME, or a broadband source with a filtered detector such as an interferometer – PSA) across a wavelength range. The Stokes vector of the output light is measured for each wavelength. The change of these Stokes vectors with angular optical frequency (wavelength), ω and with the change in input SOP (state of polarization), yields the DGD as a function of wavelength.

For both JME and PSA analyses, three distinct and known linear SOPs (orthogonal on the Poincaré sphere) must be launched for each wavelength. Figure 14 illustrates the test setup and examples of test results.

The JME and PSA method are mathematically equivalent.

Fixed analyzer. FA determines PMD by measuring a response to a change of narrowband light across a wavelength range. For each SOP, the change in output power that is filtered through a fixed polarization analyzer, relative to the power detected without the analyzer, is measured as a function of wavelength. Figure 15 illustrates a test setup and examples of test results.

The resulting measured function can be analyzed in one of two ways:

- by counting the number of peaks and valleys (EC) of the curve and application of a formula. This analysis is considered as a frequency domain approach; and
- by taking the Fourier transform (FT) of the measured function. This FT is equivalent to the pulse spreading obtained by TINTY.

Interferometry. INTY uses a broadband light source and an interferometer. The fringe pattern containing the source auto-correlation, together with the PMD related cross-correlation of the emerging electromagnetic field, is determined by the interference pattern of the output light, i.e., the interferogram. The PMD determination for the wavelength range associated with the source spectrum is based on the envelope of the fringe


Broadband source
Tunable laser source
Polarizer (3 SOPs)
FUT
Tunable filter
Polarimeter
Polarimeter
Stokes parameters
DGD$_{max}$
PMD
DGD (ps)
0
0.05
0.1
0.15
0.2
0.25
0.3
1557.36
1549.32
1541.35
192
192.5
193
193.5
194
194.5
195
Optical frequency (THz)
DGD, DGD mean = 0.79821 PMD = 0.91331ps
DGD$_{max}$
PMD
DGD (ps)
0
0.2
0.4
0.6
0.8
1
1.2
1.4
1530.65
1530.49
1530.33
1530.17
195.86
195.87
195.88
195.89
195.9
195.91
195.92
195.93
Optical frequency (THz)
DGD$_{max}$
PMD
DGD (ps)
0
1
2
182
1647.2 nm
195
Optical frequency (THz)
208
1441.3 nm

Figure 14 PMD by Stokes parameter evaluation method.


Broadband source
Tunable laser source
Polarizer (1 SOP)
FUT
Analyzer (0° or 90°)
Optical spectrum analyzer
Optical power meter
1.8
1.6
1.4
1.2
1
0.8
0.6
0.4
0.2
0
0
4
8
12
16
20
Delay [ps]

Figure 15 PMD by fixed analyzer method.

pattern interferogram. Two analyses are available to obtain the PMD:

- TINTY uses a set of specific operating conditions for its successful applications and a basic setup; and
- GINTY uses no limiting operating conditions, but in addition to the same basic setup, also using a modified setup compared to TINTY.

Figure 16 illustrates the test setup for both approaches and examples of test results.

Polarization Crosstalk

Polarization crosstalk is a characteristic of energy mixing/transfer/coupling between the two PSPs in a PMF (polarization maintaining fiber) when their isolation is imperfect. It is the measure of the strength of mode coupling or output power ratio between the PSPs within a PMF.

A PMF is an optical fiber capable of transmitting, under external perturbations, such as bending or lateral pressures, both HE_{11}^{x} and HE_{11}^{y} polarization modes whose electric field vector directions are orthogonally to each other and which have different propagation constants β_x and β_y.

Two methods are available for measuring the polarization crosstalk of PMF:

- *power ratio method*, which uses the maximum and minimum values of output power at a specified wavelength, and is applicable to fibers and connectors jointed to a PMF, and to two or more PMFs joined in series; and
- *in-line method*, which uses an analysis of the Poincaré sphere, and is applicable to single or cascaded sections of PMF, and to PMF interconnected with optical devices.

Nonlinear Effects

When the power of the transmission signal is increased to achieve longer span lengths at high bit



Figure 17 Power output-to-power input relationship for production of nonlinear effects.

expressed as follows:

$$n = n_0 + n_2 I \qquad [18]$$

n is the nonlinearity dependent index; n_0 is the linear part of the index; n_2 is the nonlinear index, also called the Kerr nonlinear index (2.2 to 3.4×10^{-16} cm^2/W); and I is the optical intensity inside the fiber.

The field propagation at a distance L into the fiber is described by the following equation:

$$E_{out}(L) = E_{in}(0)\exp[-a/2 + i\beta + \gamma P(L, t)/2]L \qquad [19]$$

$a/2$ is the attenuation; $i\beta$ is the phase of the wave; and $\gamma P(L, t)/2$ is the nonlinearity term;

$$\gamma = 2\pi n_2/\lambda A_{eff} \qquad [20]$$

γ is the nonlinearity coefficient and may be a complex number; A_{eff} is the fiber core effective area; $P(L, t)$ is the total power; and λ is the signal wavelength and t the time variable.

The nonlinear coefficient is defined as n_2/A_{eff}. This coefficient plays a critical role in the fiber and is closely related to system performance degradation due to nonlinearities when very high power is used.

Methods for measuring the nonlinear coefficient. Two methods are available for measuring the nonlinear coefficient:

- Continuous-wave dual-frequency (CWDF); and
- Pulsed single-frequency (PSF).

In the CWDF method, light from two wavelengths is injected into the fiber. At higher power, the light from the two wavelengths beat due to the nonlinearity and produce an output spectrum that is spread. The relationship of the power level to a particular spreading is used to calculate the nonlinear coefficient.

In the PSF method, the pulsed light from a single wavelength is injected into the fiber. Very short pulses (<1 ns) and their input peak power must be measured and related to the nonlinear spreading of the output spectrum.

Stimulated Brillouin scattering

In an intensity modulated system using a source with a narrow linewidth, significant optical power is transferred from the forward-propagating signal to a backward-propagating signal when the SBS power threshold is exceeded. At that point periodic regions of index of refraction produce a grating traveling at speed of sound away from the source. The grating reflects backward part of the incident light. The reflected sound waves (acoustic phonons) scatter light back to the source. Phase matching (or momentum conservation) dictates that the scattered light preferentially travels in the backward direction. The scattered light will be Doppler-shifted (downshifted or Brillouin-shifted) by approximately 11 GHz (at 1550 nm, for G.652 fiber). The scattered light has a very narrow spectrum (very coherent) and very close to the carrier signal and may be very detrimental.

Stimulated Raman scattering

SRS is an interaction between light and the fiber molecular vibrations as adjacent atoms vibrate in opposite directions (an 'optical phonon'). Some of the energy of the main carrier (optical pump wave) is transferred to the molecules, thereby further increasing the amplitude of their vibrations. If the vibrations become large enough, a threshold is reached at which the local index of refraction changes. These local changes then scatter light in all directions similar to Rayleigh scattering. However, unlike Rayleigh scattering, the wavelength of the Raman scattered light is shifted to longer wavelengths by an amount that corresponds to the molecular vibration frequencies and the Raman signal spreads over a large spectrum.

Self-phase modulation

SPM is the effect that a powerful pulse has on its own phase, considering that in eqn [18], $I(t)$ varies in time:

- $I(t) \rightarrow n(t) = n_0 + n_2 I(t) \rightarrow$ modulates the phase $\beta(t)$ of the pulse; and
- $dI/dt \rightarrow dn/dt \rightarrow d\beta/dt$(chirp) → broadening in the frequency domain → broadening in the time domain.

$I(t)$ peaks at the center of the pulse (peak power) and consequently increases the index of refraction. A higher index causes the wavelengths in the center of the pulse to accumulate phase more quickly than at the wings of the pulse:

- this causes wavelength stretching (shift to longer wavelengths) at pulse leading edge (risetime); and
- this causes wavelength compression (shift to shorter wavelengths) at pulse trailing edge (falltime).

The pulse will then broaden with negative (normal) dispersion and shorten with positive (anomalous) dispersion. SPM may then be used for dispersion compensation considering that self-phase modulation imposes $C > 0$ (positive chirp). It can cancel the dispersion if properly manage as a function of the sign of the dispersion. SPM is one of the most critical nonlinear effects for the propagation of soliton or very short pulses over very long distance.

Cross-phase modulation

XPM is the effect that a powerful pulse has on the phase of an adjacent pulse from another WDM system channel traveling in phase or at slightly the same group velocity. It concerns spectral interference between two WDM channels:

- the increasing $I(t)$ at the leading edge of the interfering pulse shifts the other pulse to longer wavelength; and
- decreasing $I(t)$ at the trailing edge of the interfering pulse shifts the other pulse to shorter wavelengths.

This produces spectral broadening, which dispersion converts to temporal broadening depending on the sign of the dispersion. XPM effect is similar to SPM except it depends on the channel count.

Four-wave (four-photon) mixing

FWM is the by-product production effect from two or more WDM channels. For two channels $I(t)$ modulates the phase of each signal (ω_1 and ω_2). An intensity modulation appears at the beat frequency $\omega_1 - \omega_2$.

Two sideband frequencies are created in a similar way as harmonics generation. New wavelengths are created in a number equal to $N^2(N-1)/2$, where $N =$ number of original wavelengths.

Fiber Dimension Characteristics and Corresponding Tests Methods

Table 1 provides a list of the various fiber dimensional characteristics and their corresponding test methods.

Table 1 Fiber dimensional characteristics

Attribute	*Measured parameter*
Fiber geometry	Core/cladding diameter Core/cladding noncircularity Core-cladding concentricity error
Numerical aperture	
Mode field diameter	
Coating geometry	
Length	

Fiber Geometry Characteristics

The fiber geometry is related to the core and cladding characteristics.

Core

The core center is the center of a circle which best fits the points at a constant level in the near-field intensity profile emitted from the central region of the fiber, using wavelengths above and/or below the cut-off wavelength.

The RIP can be measured by refracted near field (RNF) or transverse interferometry techniques and transmitted near field (TNF).

The core concentricity error is the distance between the core center and the cladding center. This definition applies very well for multimode fibers. The distance between the center of the near field profile and the center of the cladding is also used for singlemode fibers.

The mode field diameter (MFD) represents a measure of the transverse electromagnetic field intensity of the mode in a fiber cross-section and it is defined from the far-field intensity distribution.

The MF is the singlemode field distribution of the LP_{01} mode, giving rise to a spatial intensity distribution in the fiber.

The MF concentricity error is the distance between the MF center and the cladding center.

The core noncircularity is a measure of the core ellipticity. This parameter is one of the causes for creating birefringence in the fiber and consequently PMD.

Cladding

The cladding is the outermost region of constant refractive index in the fiber cross-section.

The cladding center is the center of a circle best fitting the outer limit (boundary) of the cladding.

The cladding diameter is the diameter of the circle defining the cladding center.

The cladding noncircularity is a measure of the difference between the diameters of the two circles defined by the cladding tolerance field divided by the nominal cladding diameter.

Coating

The primary coating is one or more layers of protective material applied to the cladding during or after the drawing process to protect the cladding surface (e.g., a 250 μm protective coating). The secondary coating is one or more layers of protective material applied over the primary coating in order to give additional protection or to provide a particular structure.

Measurement of the fiber geometrical attributes

The fiber geometry is measured by the following methods:

- TNF;
- RNF;
- Side-view technique/transverse interference;
- TNF image technique; and
- Mechanical diameter.

Test instrumentation may incorporate two or more methods such as the one shown in Figure 18.

Transmitted near-field technique. The cladding diameter, core concentricity error, and cladding noncircularity are determined from the near-field intensity distribution. Figure 19 provides a series of examples of test results from TNF measurements.

Refracted near-field technique. The RIP across the entire fiber (core and cladding) can be directly obtained from the RNF measurement, as shown in Figure 20.

The geometrical characteristics of the fiber can be obtained from the refractive index distribution using suitable algorithms:

- core/cladding diameter;
- core/cladding concentricity error;
- core/cladding noncircularity;
- maximum numerical aperture (NA); and
- index and relative index of refraction difference.

Figure 21 illustrates the core geometry.

Side-view technique/transverse interference. The side-view method is applied to singlemode fibers to determine the core concentricity error, cladding diameter and cladding noncircularity by measuring the intensity distribution of light that is refracted inside the fiber. The method is based on an interference microscope focused on the side view of an FUT illuminated perpendicular to the FUT axis. The fringe pattern is used to determine the RIP.


EXFO
EXFO
①
②
③
④
⑤
⑥
⑦
⑧
⑨
⑩
⑪
⑫
⑬
⑭
⑮
⑯
⑰
⑱
⑲
⑳
㉑
(1) Metallic block
(2) Measurement cell
(3) Fiber under test
(4) RNF detector
(5) Microscope objective lens
(6) RNF laser source
(7) Temperature sensor
(8) TNF laser source (1310 nm)
(9) TNF laser source (1550 nm)
(10) LED source (fiber search)
(11) Bare fiber adapter
(12,13,14) Optical fiber pigtails
(15) TNF detector
(16) Multimode optical fiber
(17) Parabolic mirror
(18,19) Beamsplitters
(20) Mirror
(21) CCD camera (fiber search)

Figure 18 RNF/TNF combined instrumentation.



Figure 19 MFD measurement by TNF.



Figure 20 RIP from RNF measurement.

TNF image technique. The TNF image technique, also called near-field light distribution, is used for the measurement of the geometrical characteristics of singlemode fibers. The measurement is based on analysis of magnified images at the FUT output. Two subsets of the method are available:

- grey-scale technique which performs an x–y near-field scan using a video system; and
- Single near-field scanning technique performing a one-dimensional scan.

Mechanical diameter. This is a precision mechanical diameter measurement technique used to accurately determine the cladding diameter of silica fibers. The technique uses an electronic micrometer such as based on a double-pass Michelson interferometer. The technique is used for providing calibrated fibers to the industry as SRM.

Numerical Aperture

The NA is an important attribute for multimode fibers in order to predict their launching efficiency, joint loss at splices and micro/macrobending characteristics.

A method is available for the measurement of the angular radiant intensity distribution (far-field)

```
Units = [µm]
                                            (Mem)      (Mem)
                          Cladding   Core   Cladding   Core
No. of points           :   20        14      20        16
Fitting level           :    0.5       0.5     0.5       0.5

Circular fit
Diameter                :  125.3       6.3   125.3       6.3
Standard deviation      :    0.2       0.0     0.2       0.0
Center distance         :              0.8               0.8
Conc. error (%)         :              0.6               0.6

Elliptical fit
Large axis (yellow)     :  125.8       6.4   125.8       6.4
Small axis (blue)       :  124.9       6.3   124.9       6.3
Standard deviation      :    0.2       0.0     0.2       0.0
Center distance         :              0.8               0.8
Conc. error (%)         :              0.6               0.6
Non-circularity (%)     :    0.7       0.9     0.7       0.9

Orient. ellipse : 7.09°
Diam. X : 125.73 µ
Diam. Y : 124.90 µ
```



Figure 21 Core geometry by RNF measurement.

distribution or the RIP at the output of an FUT. NA can be determined from the analysis of the test results.

Mode Field Diameter

The definition of the MFD is given in the section describing the core center above. Four measurement methods are available:

- direct far-field scan determines MFD from the far-field intensity distribution;
- variable aperture in far field determines MFD from the complementary aperture transmission function $a(x)$, $x = d\tan\theta$ being the aperture radius and d the distance between the aperture and the FUT:

$$\mathrm{MFD} = \frac{\lambda}{\pi d}\left[\int_0^\infty a(x)\frac{x}{(x^2+d^2)^2}\,\mathrm{d}x\right]^{-1/2} \qquad [21]$$

Equation [21] is valid for small-θ approximation.

- near-field scan determines MFD from the near-field intensity distribution I_{NF}, r being the radial coordinate:

$$\mathrm{MFD} = 2\left[2\frac{\int_0^\infty rI_{\mathrm{NF}}(r)\,\mathrm{d}r}{\int_0^\infty r\left[\frac{\mathrm{d}I^{1/2}(r)}{\mathrm{d}r}\right]^2\mathrm{d}r}\right]^{1/2} \qquad [22]$$

Equation [22] is valid for small-θ approximation; and

- bidirectional backscattering uses an OTDR and bidirectional measurements to determine MFD by comparing the FUT results with a reference fiber.

Effective Area

A_{eff} is a critical nonlinearity parameter and is defined as follows:

$$A_{\mathrm{eff}} = \frac{2\pi[\int_0^\infty I(r)r\,\mathrm{d}r\,]^2}{\int_0^\infty I(r)^2 r\,\mathrm{d}r} \qquad [23]$$

$I(r)$ is the field intensity distribution of the fiber fundamental mode at radius r. The integration in the equation is carried out over the entire fiber cross-section. For a Gaussian approximation:

$$I(r) = \exp -2\left(\frac{2r}{\mathrm{MFD}}\right)^2 \qquad [24]$$

which yields:

$$A_{\mathrm{eff}} = \frac{\pi}{4}\mathrm{MFD}^2 \qquad [25]$$

Three methods are available for the measurement of A_{eff}:

- direct far-field;
- variable aperture in far-field; and
- near-field.

Mechanical Measurement and Test Methods

Table 2 describes the various mechanical characteristics and their corresponding test methods.

Proof Stressing

The proof stress level is the value of tensile stress or strain applied to a full fiber length over a short period of time. The method for fiber proof stressing is the longitudinal tension which describes procedures for applying tensile loads to a length of fiber. The fiber stress is calculated from the applied tension. The tensile load is applied over short periods of time but not too short in order for the fiber to experience proof stress.

Residual Stress

Residual stress is the stress built up by the thermal expansion difference between core and cladding during the fiber drawing process or splicing. Methods are available for measuring residual stress based on polarization effects. A light beam produced by a rotating polarizer propagates to the x-axis direction while the beam polarization is in the y–z plane and the fiber longitudinal axis in the z-axis. The light experiences different phase shift in the y- and z-axis due to the FUT birefringence. The photoelastic effect gives the relationship between this phase change and residual stresses.

Stress Corrosion Susceptibility

The stress corrosion susceptibility is related to the dependence of crack growth on applied stress. It depends on the environmental conditions and static and dynamic values may be observed.

Environmental Characteristics

Table 3 lists the fiber characteristics related to the effect of the environment.

Table 2 Fiber mechanical characteristics

Attribute
Proof stress
Residual stress
Stress corrosion susceptibility
Tensile strength
Stripability
Fiber curl

Table 3 Fiber environmental characteristics

Attribute
Hydrogen aging
Nuclear gamma irradiation
Damp heat
Dry heat
Temperature cycling
Water immersion

Hydrogen Aging for Low-Water-Peak Single-Mode Fiber

Hydrogen aging on low-water peak fibers, such as G.652.C, is based on a test performed at 1.0 atmosphere of hydrogen pressure at room temperature over a period of one month. Other proportional combinations are possible.

Nuclear Gamma Irradiation

Nuclear radiation is considered on the basis of a steady state response of optical fibers and cables exposed to gamma radiation and to determine the level of related radiation-induced attenuation produced in singlemode or multimode cabled or uncabled fibers.

The fiber attenuation generally increases when exposed to gamma radiation. This is primarily due to the trapping of radiolytic electrons and holes at defect sites in the glass (i.e., the formation of 'color centers'). Two regimes are considered:

- the low dose rate suitable for estimating the effect of environmental background radiation; and
- the high dose rate suitable for estimating the effect of adverse nuclear environments.

The effects of environmental background radiation are measured by the attenuation (cut-back method). The effects of adverse nuclear environments are tested by power monitoring before, during and after FUT exposure.

See also

Fiber and Guided Wave Optics: Nonlinear Effects (Basics). **Imaging:** Interferometric Imaging. **Interferometry:** Gravity Wave Detection; Overview. **Polarization:** Introduction. **Scattering:** Scattering Phenomena in Optical Fibers.

Further Reading

Agrawal GP (1997) *Fiber-Optic Communication Systems*, 2nd edn. New York: John Wiley & Sons.

Agrawal GP (2001) *Nonlinear Fiber Optics*, 3rd edn. San Diego, CA: Academic Press.
Girard A (2000) *Guide to WDM Technology and Testing*. Quebec: EXFO, pp. 194.
Hecht J (1999) *Understanding Fiber Optics*, 3rd edn. Upper Saddle River, NJ: Prentice Hall.
Masson B and Girard A (2004) *FTTx PON Guide, Testing Passive Optical Networks*. Quebec: EXFO, pp. 56.
Miller JL and Friedman E (2003) *Optical Communications Rules of Thumb*. New York: McGraw-Hill, pp. 428.
Neumann E-G (1988) *Single-Mode Fibers, Fundamentals*. Berlin: Springer-Verlag.

Nonlinear Effects (Basics)

G Millot and P Tchofo-Dinda, Université de Bourgogne, Dijon, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Many physical systems in various areas such as condensed matter or plasma physics, biological sciences, or optics, give rise to localized large-amplitude excitations having a relatively long lifetime. Such excitations lead to a host of phenomena referred to as nonlinear phenomena. Of the many disciplines of physics, the optics field is probably the one in which practical applications of nonlinear phenomena have been the most fruitful, in particular, since the discovery of the laser in 1960. This discovery has thus led to the advent of a new branch in optics, referred to as *nonlinear optics*. The applications of nonlinear phenomena in optics include the design of various kinds of laser sources, optical amplifiers, light converters, light-wave communication systems for data transmission purposes, to name a few.

In this article, we present an overview of some basic principles of nonlinear phenomena that result from the interaction of light waves with dielectric waveguides such as optical fibers. These nonlinear phenomena can be broadly divided into two main categories, namely, parametric effects and scattering phenomena. Parametric interactions arise whenever the state of the dielectric matter is left unchanged by the interaction, whereas scattering phenomena imply transitions between energy levels in the medium. More fundamentally, parametric interactions originate from the electron motion under the electric field of a light wave, whereas scattering phenomena originate from the motion of heavy ions (or molecules).

Linear and Nonlinear Signatures

The macroscopic properties of a physical system can be obtained by analyzing the response of the system under an external excitation. For example, consider at time t the response of a system, such as an amplifier, to an input signal $E_1 = A\sin(\omega t)$. In the low-amplitude limit of the output signal, the response R_1 of the system is proportional to the excitation:

$$R_1 = \alpha_1 E_1 \qquad [1]$$

where α_1 is a constant. This type of behavior corresponds to the so-called linear response. In general, a physical system executes a linear response when the superposition of two (or more) input signals E_1 and E_2 yields a response which is a superposition of the output signals, as schematically represented in Figure 1:

$$R = \alpha_1 R_1 + \alpha_2 R_2 \qquad [2]$$

Now, in almost all real physical systems, if the amplitude of an excitation E_1 becomes sufficiently large, distortions will occur in the output signals. In other words, the response of the system will no longer be proportional to the excitation, and consequently, the law of superposition of states will no longer be observed. In this case, the response of the system may take the following form:

$$R = \alpha_1 E_1 + \alpha_2 E_1^2 + \alpha_3 E_1^3 + \ldots \qquad [3]$$

which involves not only a signal at the input frequency ω, but also signals at frequencies 2ω, 3ω, and so on. Thus, harmonics of the input signal are generated. This behavior, called *nonlinear response*, is at the origin of a host of important phenomena in many



Figure 1 Schematic representation of linear and nonlinear responses of a system, to two input signals.

branches of sciences, such as in condensed matter physics, biological sciences, or in optics.

Physical Origin of Optical Nonlinearity

Optical nonlinearity originates fundamentally from the action of the electric field of a light wave on the charged particles of a dielectric waveguide. In contrast to conductors where charges can move throughout the material, dielectric media consist of *bound* charges (ions, electrons) that can execute only relatively limited displacements around their equilibrium positions. The electric field of an incoming light wave will cause the positive charges to move in the polarization direction of the electric field whereas negative charges will move in the opposite direction. In other words, the electric field will cause the charged particles to become dipoles, as schematically represented in Figure 2.

Then each dipole will vibrate under the influence of the incoming light, thus becoming a source of radiation. The global light radiated by all the dipoles represents the scattered light. When the charge displacements are proportional to the excitation (incoming light), i.e., in the low-amplitude limit of scattered radiation, the output light vibrates at the same frequency as that of the excitation. This process corresponds to Rayleigh scattering. On the other hand, if the intensity of the excitation is sufficiently large to induce displacements that are not negligible with respect to atomic distances, then the charge displacements will no longer be proportional to the excitation. In other words, the response of the medium, which is no longer proportional to the excitation, becomes nonlinear. In this case, the scattered waves will be generated not only at the excitation frequency (the Kerr effect), say ω, but also at frequencies that differ from ω (e.g., 2ω, 3ω). On the other hand, it is worth noting that when all induced dipoles vibrate coherently (that is, their relative phase does not vary randomly), their individual radiation may, under certain conditions, interfere constructively and lead to a global field of high intensity. The condition of constructive interference is the phase-matching condition.



Figure 2 Electric dipoles in a dielectric medium under an external electric field.

In practice, the macroscopic response of a dielectric is given by the polarization, which corresponds to the total amount of dipole moment per unit volume of the dielectric. As the mass of an ion is much larger than that of an electron, the amplitude of the ion motion is generally negligible with respect to that of the electrons. As a consequence, the electron motion generally leads to the dominant contribution in the macroscopic properties of the medium. The behavior of an electron under an optical electric field is similar to that of a particle embedded in an anharmonic potential. A very simple model (called the Lorentz model) that provides a deep insight into the dielectric response consists of an electron of mass m and charge $-e$ connected to an ion by an elastic spring (see Figure 2). Under the electric field $E(t)$, the electron executes a displacement $x(t)$ with respect to its equilibrium position, which is governed by the following equation:

$$\frac{\mathrm{d}^2x}{\mathrm{d}t^2}+2\lambda\frac{\mathrm{d}x}{\mathrm{d}t}+\omega_0^2x+(a^{(2)}x^2+a^{(3)}x^3+\cdots)$$
$$=-\frac{e}{m}E(t) \qquad [4]$$

where $a^{(2)}$, $a^{(3)}$, and so on, are constant parameters, ω_0 is the resonance angular frequency of the electron, and λ is the damping coefficient resulting from the dipolar radiation. When the amplitude of the electric field is sufficiently large, then the restoring force on the electrons becomes a nonlinear function of x; hence the presence of terms such as $a^{(2)}x^2$, $a^{(3)}x^3$, and so on, in eqn [4]. In this situation, the macroscopic response of the dielectric is the polarization

$$P=-\sum ex(\omega,2\omega,3\omega,\ldots) \qquad [5]$$

where $x(\omega,2\omega,3\omega,\ldots)$ is the solution of eqn [4] in the frequency domain, and the summation extends over all the dipole moments per unit volume. In terms of the electric field E the polarization may be written as

$$P=\varepsilon_0(\chi^{(1)}E+\chi^{(2)}E^2+\chi^{(3)}E^3+\cdots) \qquad [6]$$

where $\chi^{(1)}$, $\chi^{(2)}$, $\chi^{(3)}$, and so on, represent the susceptibility coefficients. Figure 3 (top left) illustrates schematically the polarization as a function of the electric field.

In particular, one can clearly observe that when the amplitude of the incoming electric field is sufficiently small (bottom left in Figure 3), the polarization (top right) is proportional to the electric field (bottom left), thus implying that the electric dipole radiates a wave having the same frequency as that of the incoming light (bottom right). On the other hand, Figure 4



Figure 3 Polarization induced by an electric field of small amplitude. Nonlinear dependence of the polarization as a function of field amplitude (top left) and time dependence of the input electric field (bottom left). Time dependence of the induced polarization (top right) and corresponding intensity spectrum (bottom right).



Figure 4 Polarization induced by an incoming electric field of large amplitude.

shows that for an electric field of large amplitude, the polarization is no longer proportional to the electric field, leading to radiation at harmonic frequencies (see Figure 4, bottom right).

This nonlinear behavior leads to a host of important phenomena in optical fibers, which are useful for many optical systems but detrimental for other systems.

Parametric Phenomena in Optical Fibers

In anisotropic materials, the leading nonlinear term in the polarization, i.e., the $\chi^{(2)}$ term, leads to phenomena such as the harmonic generation or optical rectification. This $\chi^{(2)}$ term vanishes in homogeneous isotropic materials such as cylindrical optical fibers, and there the leading nonlinear term becomes the $\chi^{(3)}$ term. Thus, most of outstanding nonlinear phenomena in optical fibers originate from the third-order nonlinear susceptibility $\chi^{(3)}$. Some of those phenomena are described below.

Optical Kerr Effect

The optical Kerr effect is probably the most important nonlinear effect in optical fibers. This effect induces an intensity dependence of the refractive index, which leads to a vast wealth of fascinating phenomena such as self-phase modulation (SPM), cross-phase modulation (CPM), four-wave mixing (FWM), modulational instability (MI) or optical solitons. The Kerr effect can be conveniently described in the frequency domain through a direct analysis of the polarization, which takes the following form:

$$P_{\mathrm{NL}}(\omega) = \frac{3}{4}\varepsilon_0\chi^{(3)}(\omega)|E(\omega)|^2E(\omega) \qquad [7]$$

The constant 3/4 comes from the symmetry properties of the tensor $\chi^{(3)}$. Setting $P_{\mathrm{NL}}(\omega) = \varepsilon_0\varepsilon_{\mathrm{NL}}E(\omega)$, where $\varepsilon_{\mathrm{NL}} = \frac{3}{4}\chi^{(3)}|E|^2$ is the nonlinear contribution to the dielectric constant, the total polarization takes the form

$$P(\omega) = P_{\mathrm{L}} + P_{\mathrm{NL}} = \varepsilon_0[\chi^{(1)}(\omega) + \varepsilon_{\mathrm{NL}}]E(\omega) \qquad [8]$$

As eqn [8] shows, the refractive index n, at a given frequency ω, is given by

$$n^2 = 1 + \chi^{(1)} + \varepsilon_{\mathrm{NL}} = (n_0 + \Delta n_{\mathrm{NL}})^2 \qquad [9]$$

with $n_0^2 = 1 + \chi^{(1)}$. In practice $\Delta n_{\mathrm{NL}} \ll n_0$, and then, the refractive index is given by

$$n(\omega, |E|^2) = n_0(\omega) + n_2^e|E|^2 \qquad [10]$$

where n_2^e is the nonlinear refractive index defined by $n_2^e = 3\chi^{(3)}/(8n_0)$. The linear polarization P_{L} is responsible for the frequency dependence of the refractive index, whereas the nonlinear polarization P_{NL} causes an intensity dependence of the refractive index, which is referred to as the optical Kerr effect. Knowing that the wave intensity I is given by $I = \alpha|E|^2$, with $\alpha = \frac{1}{2}\varepsilon_0 cn_0$, the refractive index can be then rewritten as

$$n(\omega, I) = n_0(\omega) + n_2 I \qquad [11]$$

with $n_2 = n_2^e/\alpha = 2n_2^e/(\varepsilon_0 cn_0)$. For fused silica fibers one has typically: $n_2 = 2.66 \times 10^{-20}\ \mathrm{m^2\ W^{-1}}$. For example, an intensity of $I = 1\ \mathrm{GW\ cm^{-2}}$ leads to $\Delta n_{\mathrm{NL}} = 2.66 \times 10^{-7}$, which is much smaller than $n_0 \approx 1.45$.

Four-Wave Mixing

The four-wave mixing (FWM) process is a third-order nonlinear effect in which four waves interact through an energy exchange process. Let us consider two intense waves, $E_1(\omega_1)$ and $E_2(\omega_2)$, with $\omega_2 > \omega_1$, called pump waves, propagating in an optical fiber. Hereafter we consider the simplest case when waves propagate with the same polarization. In this situation the total electric field is given by

$$\begin{aligned} E_{\mathrm{tot}}(\mathbf{r}, t) &= E_1 + E_2 \\ &= A_1(\omega_1)\exp[\mathrm{i}(\mathbf{k}_1\cdot\mathbf{r} - \omega_1 t)] \\ &\quad + A_2(\omega_2)\exp[\mathrm{i}(\mathbf{k}_2\cdot\mathbf{r} - \omega_2 t)] \end{aligned} \qquad [12]$$

where $\mathbf{k}_1$ and $\mathbf{k}_2$ are the wavevectors of the fields E_1 and E_2, respectively. Equation [7], which gives the nonlinear polarization induced by a single monochromatic wave, remains valid provided that the frequency spacing between the two waves is relatively small, i.e., $|\Delta\omega| = |\omega_2 - \omega_1| \ll \omega_0 = (\omega_1 + \omega_2)/2$. In this context, eqn [7] leads to

$$P_{\mathrm{NL}} \approx \frac{3}{4}\varepsilon_0\chi^{(3)}(\omega_0)|E_{\mathrm{tot}}|^2E_{\mathrm{tot}} \qquad [13]$$

Substituting eqn [12] in eqn [13] yields

$$\begin{aligned} P_{\mathrm{NL}} = 2n_0n_2\varepsilon_0\Big[&\left(|E_1|^2 + 2|E_2|^2\right)E_1 \\ &+ \left(|E_2|^2 + 2|E_1|^2\right)E_2 + E_1^2E_2^* + E_1^*E_2^2\Big] \end{aligned} \qquad [14]$$

The term $|E_1|^2E_1$ in the right-hand side of eqn [14] represents the self-induced Kerr effect on the wave ω_1. The term $|E_2|^2E_1$, which corresponds to a modification of the refractive index seen by the wave ω_1, due to the presence of the wave ω_2, represents the cross-Kerr effect. Thus, the refractive index at frequency ω_1 depends simultaneously on the intensities of the two pumps, i.e., $n = n(\omega_1, |E_1|^2, |E_2|^2)$. Similarly the third and fourth terms in the right-hand side of eqn [14] illustrate the self-induced and cross-Kerr effects on the wave ω_2, respectively. Note that the self-induced Kerr effect is responsible for a self-phase modulation, which induces a spectral broadening of a pulse propagating through the optical fiber, whereas the cross-Kerr effect leads to a cross-phase modulation that induces a spectral broadening of one wave in the presence of a second wave. The two last terms in the right-hand side of eqn [14] correspond to the generation of new waves at frequencies $2\omega_1 - \omega_2$ and $2\omega_2 - \omega_1$, respectively. The wave with the smallest frequency $2\omega_1 - \omega_2 = \omega_{\mathrm{s}}$ is called the Stokes wave, whereas the wave with the highest frequency $2\omega_2 - \omega_1 = \omega_{\mathrm{as}}$ is called the anti-Stokes wave. These two newly generated waves interact



Figure 5 Schematic diagram representing a non-degenerate four-wave mixing process (top) and the corresponding frequency spectrum (bottom).

with the two pumps through an energy exchange process. This interaction is commonly referred to as a four-wave mixing process.

From a quantum mechanical point of view, four-wave mixing corresponds to a process in which two photons with frequencies ω_1 and ω_2 are annihilated with simultaneous creation of two photons at frequencies ω_s and ω_{as}, respectively. The new waves are generated at frequencies ω_s and ω_{as} such that

$$\omega_1 + \omega_2 = \omega_s + \omega_{as} \qquad [15]$$

which states that the total energy is conserved during the interaction. But the condition for this FWM process to occur is that the total momentum is conserved, that is,

$$\Delta\mathbf{k} = \mathbf{k}_s + \mathbf{k}_{as} - \mathbf{k}_1 - \mathbf{k}_2 = 0 \qquad [16]$$

or equivalently,

$$n(\omega_s)\omega_s + n(\omega_{as})\omega_{as} - n(\omega_1)\omega_1 - n(\omega_2)\omega_2 = 0 \quad [17]$$

Equation [16] is known as the phase-matching condition. Figure 5 displays a schematic diagram of a four-wave mixing process with the corresponding frequency spectrum.

FWM with different pump frequencies $\omega_1 \neq \omega_2$ is called ‘nondegenerate FWM’, whereas the case $\omega_1 = \omega_2$ is referred to as ‘degenerate FWM’, or more simply, as three-wave mixing.

Conclusion

Optical fibers constitute a key device for many areas of optical sciences, and in particular for ultrafast optical communications. The nonlinear phenomena that arise through the nonlinear refractive index change (induced mainly by the Kerr effect) have been largely investigated these last two decades for applications such as all-optical wavelength conversion, parametric amplification, generation of new optical frequencies or ultrahigh repetition rate pulse trains. However, in many other optical systems such as optical communication systems, these nonlinear phenomena become harmful effects, and in this case control processes are being developed in order to suppress or at least reduce their impact in the system.

List of Units and Nomenclature

Nonlinear refractive index n_2 [$\mathrm{m^2\,W^{-1}}$]
Optical intensity I [$\mathrm{GW\,cm^{-2} = 10^9\,W\,cm^{-2}}$]

CPM: cross phase modulation
FWM: four wave mixing
MI: modulational instability
SPM: self-phase modulation

See also

Fiber and Guided Wave Optics: Light Propagation; Measuring Fiber Characteristics. **Lasers:** Optical Fiber lasers. **Optical Amplifiers:** Semiconductor Optical Amplifiers. **Optical Communication Systems:** Wavelength Division Multiplexing. **Scattering:** Scattering Theory. **Solitons:** Soliton Communication Systems.

Further Reading

Agrawal GP (2001) *Nonlinear Fiber Optics*. San Diego, CA: Academic Press.

Bloembergen N (1977) *Nonlinear Optics*. Reading, MA: Benjamin.

Boyd RW (1992) *Nonlinear Optics*. San Diego, CA: Academic Press.

Butcher PN and Cotter DN (1990) *The Elements of Nonlinear Optics*. Cambridge, UK: Cambridge University Press.

Dianov EM, Mamyshev PV, Prokhorov AM and Serkin VN (1989) *Nonlinear Effects in Optical Fibres*. Switzerland: Harwood Academic Publishers.

Hellwarth R (1977) Third-order optical susceptibilities of liquids and s\olids. *Progress in Quantum Electronics 5*: 1–68.

Pocholle JP, Papuchon M, Raffy J and Desurvire E (1990) Non linearities and optical amplification in single mode fibres. *Revue Technique Thomson-CSF* 22: 187–268.

Shen YR (1984) *Principles of Nonlinear Optics*. New York: Wiley.

Nonlinear Optics

K Thyagarajan and A K Ghatak, Indian Institute of Technology, New Delhi, India

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The invention of the laser provided us with a light source capable of generating extremely large optical power densities (several MW/m^2). At such large power densities, matter behaves in a nonlinear fashion and we come across new optical phenomena such as second-harmonic generation (SHG), sum and difference frequency generation, intensity dependent refractive index, mixing of various frequencies, etc. In SHG, an incident light beam at frequency ω interacts with the medium and generates a new light wave at frequency 2ω. In sum and difference frequency generation, two incident beams at frequencies ω_1 and ω_2 mix with each other producing sum $(\omega_1 + \omega_2)$ and difference $(\omega_1 - \omega_2)$ frequencies at the output. Higher-order nonlinear effects, such as self-phase modulation, four-wave mixing, etc. can also be routinely observed today. The field of nonlinear optics dealing with such nonlinear interactions is gaining importance due to numerous demonstrated applications in many diverse areas such as optical fiber communications, all-optical signal processing, realization of novel sources of optical radiation, etc.



Figure 1 (a) In bulk media, tighter focusing produces larger intensities, but over shorter interaction lengths. (b) In optical waveguides diffraction effects are balanced by waveguiding and the interaction lengths are much larger.

Nonlinear optical interactions become prominent when the optical power densities are high and interaction takes place over long lengths. The usual method to increase optical intensity is to focus the light beam using a lens system. For a given optical power, the tighter the focusing, the larger will be the intensity for a given optical power; however, greater will be the divergence of the beam. Thus tighter focusing produces larger intensities, but over shorter interaction lengths (see Figure 1a). Optical waveguides, in which the light beam is confined to a small cross-sectional area, are currently being explored for realizing efficient nonlinear devices. In contrast to bulk media, in waveguides, diffraction effects are balanced by waveguiding and the beam can have small cross-sectional areas over much longer interaction lengths (see Figure 1b). A simple optical waveguide consists of a high index dielectric medium surrounded by a lower index dielectric medium so that light waves can be trapped in the high index region by the phenomenon of total internal reflection. Figure 2 shows a planar waveguide, a channel waveguide and an optical fiber. In the planar waveguide a film of refractive index n_f is deposited/diffused on a substrate of refractive index n_s and has a cover of refractive index n_c (with n_s, $n_c < n_f$). The waveguide has typical cross-sectional dimensions of a few micrometers. Unlike planar waveguides, in which guidance takes place only in one dimension, in channel waveguides the diffused region in a substrate is surrounded on all sides by lower index media. Optical fibers are structures with cylindrical symmetry and have a central cylindrical core of doped silica surrounded by a concentric cylindrical cladding of pure silica which has a slightly lower refractive index. Light guidance in all these waveguides takes place through the phenomenon of total internal reflection.

In contrast to bulk interactions requiring beam focusing, in the case of optical waveguides, the beam can be made to have extremely small cross-sectional



Figure 2 A planar waveguide, a channel waveguide and an optical fiber.

areas (~25 μm^2) over very long interaction lengths (~20 mm in integrated optical waveguides and tens of thousands of kilometers in the case of optical fibers). This leads to very much increased nonlinear interaction efficiencies even at moderate powers (approximately a few tens of mW).

In the following sections, we will discuss some of the important nonlinear interactions that are being studied with potential applications to various branches of science and engineering. Obviously it is impossible to cover all aspects of nonlinear optics – several books have been written in this area (see Further Reading section at the end of this article) – what we will do is to discuss the physics of some of the important nonlinear effects.

Apart from intensity and length of interaction, one of the most important requirements for many efficient nonlinear interactions is the requirement of phase matching. The concept of phase matching can be easily understood from the point of view of SHG. In SHG, the incident wave at frequency ω generates a nonlinear polarization at frequency 2ω and this nonlinear polarization is responsible for the generation of the wave at 2ω. Now, the phase velocity of the nonlinear polarization wave at 2ω is the same as the phase velocity of the electromagnetic wave at frequency ω, which is usually different from the phase velocity of the electromagnetic wave at frequency 2ω; this happens due to wavelength dispersion in the medium. When the two phase velocities are unequal, the polarization wave at 2ω (which is the source) and the electromagnetic wave at 2ω pass in and out of phase with each other as they propagate through the medium. Due to this, the energy flowing in from ω to 2ω cannot add constructively and the efficiency of second-harmonic generation is limited. If the phase velocities of the waves at ω and 2ω are matched then the polarization wave and the wave at 2ω remain in phase leading to drastically increased efficiencies. This condition is referred to as phase matching and plays a very important role in most nonlinear interactions.

Nonlinear Polarization

In a linear medium, the electric polarization P is assumed to be a linear function of the electric field E:

$$P = \varepsilon_0 \chi E \qquad [1]$$

where, for simplicity, a scalar relation has been written. The quantity χ is termed as linear dielectric susceptibility. At high optical intensities (which corresponds to high electric fields), all media behave in a nonlinear fashion. Thus eqn [1] is modified to

$$P = \varepsilon_0(\chi E + \chi^{(2)}E^2 + \chi^{(3)}E^3 + \dots) \qquad [2]$$

where $\chi^{(2)}, \chi^{(3)}, \dots$ are higher order susceptibilities giving rise to the nonlinear terms. The second term on the right-hand side is responsible for SHG, sum and difference frequency generation, parametric interactions, etc. while the third term is responsible for third-harmonic generation, intensity dependent refractive index, self-phase modulation, four-wave mixing, etc. For media possessing an inversion symmetry, $\chi^{(2)}$ is zero and there is no second-order nonlinear effect. Thus silica optical fibers, which form the heart of today's communication networks, do not possess the second-order nonlinearity.

We will first discuss second-harmonic generation and parametric amplification which arises due to the second-order nonlinear term and then go on to effects due to third-order nonlinear interaction.

Second-Harmonic Generation in Crystals

The first demonstration of SHG was made in 1961 by focusing a 3 kW ruby laser pulse ($\lambda_0 = 6943$ Å) on a quartz crystal. An incident beam from a ruby laser (red color) after passing through a crystal of KDP, gets partly converted into blue light which is the second harmonic. Ever since, SHG has been one of the most widely studied nonlinear interactions.

We consider a plane wave of frequency ω propagating along the z-direction through a medium and consider the generation of the second-harmonic frequency 2ω as the beam propagates through the medium. Now, the field at ω generates a polarization at 2ω, which acts as a source for the generation of an electromagnetic wave at 2ω. Corresponding to the frequencies ω and 2ω, the electric fields are assumed to be given by

$$E^{(\omega)} = \frac{1}{2}(E_1(z)\mathrm{e}^{\mathrm{i}(\omega t - k_1 z)} + \text{c.c.}) \qquad [3]$$

and

$$E^{(2\omega)} = \frac{1}{2}(E_2(z)\mathrm{e}^{\mathrm{i}(2\omega t - k_2 z)} + \text{c.c.}) \qquad [4]$$

respectively; c.c. stands for the complex conjugate of the preceding quantities. The quantities:

$$k_1 = \omega\sqrt{(\varepsilon_1 \mu_0)} = (\omega/c)n^{\omega} \qquad [5]$$

and

$$k_2 = 2\omega\sqrt{(\varepsilon_2 \mu_0)} = (2\omega/c)n^{2\omega} \qquad [6]$$

represent the propagation vectors at ω and 2ω, respectively; ε_1 and ε_2 represent the dielectric permittivities at ω and 2ω, and n^{ω} and $n^{2\omega}$ represent the corresponding wave refractive indices. It should be noted that the amplitudes E_1 and E_2 are assumed to be z dependent – this is because at $z = 0$ (where the beam is incident on the medium) the amplitude E_2 is zero and this would develop as the beam propagates through the medium. We will now develop an approximate theory for the generation of the second harmonic.

We start with the wave equation:

$$\nabla^2 E - \varepsilon\mu_0 \frac{\partial^2 E}{\partial t^2} = \mu_0 \frac{\partial^2 P_{\mathrm{NL}}}{\partial t^2} \qquad [7]$$

where P_{NL} is the nonlinear polarization. An incident wave at frequency ω generates a polarization at 2ω, which acts as a source for the generation of an electromagnetic wave at 2ω.

In order to consider SHG, we write the wave equation corresponding to 2ω with the nonlinear polarization at 2ω given by

$$P_{\mathrm{NL}}^{(2\omega)} = \frac{1}{2}\left(\tilde{P}_{\mathrm{NL}}^{(2\omega)}\, \mathrm{e}^{2\mathrm{i}(\omega t - k_1 z)} + \mathrm{c.c.}\right) \qquad [8]$$

where

$$\tilde{P}_{\mathrm{NL}}^{(2\omega)} = dE_1E_1 \qquad [9]$$

and

$$d = \frac{\varepsilon_0 \chi^{(2)}}{2} \qquad [10]$$

represents the effective nonlinear coefficient and depends on the nonlinear material, the polarization states of the fundamental and the second harmonic and also on the propagation direction. Simple manipulations give us, for the rate of change of amplitude of the second harmonic wave:

$$\frac{\mathrm{d}E_2}{\mathrm{d}z} = -\frac{i\mu_0\, dc\omega}{n^{2\omega}} E_1^2(z)\mathrm{e}^{\mathrm{i}(\Delta k)z} \qquad [11]$$

where

$$\Delta k = k_2 - 2k_1 = (2\omega/c)(n^{2\omega} - n^{\omega}) \qquad [12]$$

and we have assumed:

$$\mathrm{d}^2E_2/\mathrm{d}z^2 \ll k_2(\mathrm{d}E_2/\mathrm{d}z) \qquad [13]$$

In order to solve eqn [11] we neglect depletion of the fundamental field, i.e., $E_1(z)$ is almost a constant and the quantity E_1^2 on the right-hand side can be assumed to be independent of z. If we now integrate eqn [11], we obtain:

$$E_2(z) = -\frac{i\mu_0\, dc\omega}{n^{2\omega}} zE_1^2\mathrm{e}^{\mathrm{i}\sigma}\frac{\sin\sigma}{\sigma} \qquad [14]$$

where

$$\sigma = \frac{1}{2}(\Delta k)z = (\omega/c)(n^{2\omega} - n^{\omega})z \qquad [15]$$

Now, the powers associated with the beams corresponding to ω and 2ω are given by:

$$P_1 = \frac{n^{\omega}}{2c\mu_0}S|E_1|^2, \qquad P_2 = \frac{n^{2\omega}}{2c\mu_0}S|E_2|^2 \qquad [16]$$

where S represents the cross-sectional area of the beams. Substituting for $|E_2|^2$ from eqn [16], we get after some elementary simplifications:

$$\eta = \frac{P_2}{P_1} = \frac{2c^3\mu_0^3 d^2\omega^2}{(n^{\omega})^2 n^{2\omega}} z^2 \frac{P_1}{S}\left(\frac{\sin\sigma}{\sigma}\right)^2 \qquad [17]$$

when η represents the SHG efficiency. Note that the efficiency of SHG increases if P_1/S, the intensity of the fundamental wave increases. Also η increases if the nonlinear coefficient d increases (obviously) and if the frequency increases. However, for a given power P_1, the conversion efficiency increases if the area of the beam decreases – thus a focused beam will have a greater SHG efficiency. The most important factor is $(\sin\sigma/\sigma)^2$ which is a sharply peaked function around $\sigma = 0$, attaining a maximum value of unity at $\sigma = 0$. Thus for maximum SHG efficiency:

$$\sigma = 0 \Rightarrow n^{2\omega} = n^{\omega} \qquad [18]$$

i.e., the refractive index at 2ω must be equal to the refractive index at ω – this is known as the phase matching condition.

The phase matching condition can be pictorially represented by a vector diagram (see Figure 3). In Figure 3, $\mathbf{k}_1\omega$ and $\mathbf{k}_2\omega$ represent the wave vectors of the fundamental and the second harmonic respectively. To achieve reasonably effective SHG, it is very important to satisfy the phase-matching condition. Efficiencies under nonphase matched operation can be orders of magnitude lower than under phase-matched operation.

We see from eqn [17] that the smallest z for which η is maximum is:

$$z = L_c = \frac{\pi}{\Delta k} = \frac{\pi c}{2\omega(n^{2\omega} - n^{\omega})} \qquad [19]$$



Figure 3 Vector diagram representing the phase matching condition for SHG.

where we have used eqn [15] for Δk. The length L_c is called the phase coherence length and represents the maximum crystal length up to which the second-harmonic power increases. Thus, if the length of the crystal is less than L_c, the second-harmonic power increases almost quadratically with z. For $z > L_c$, the second-harmonic power begins to reduce again.

In general, because of dispersion, it is very difficult to satisfy the phase-matching condition. However, in a birefringent medium, for example with $n_o > n_e$, it may be possible to find a direction along which the refractive index of the *o*-wave for ω equals the refractive index of the *e*-wave for 2ω (see Figure 4). For media with $n_e > n_o$, the direction would correspond to that along which the refractive index of the *e*-wave for ω equals the refractive index for the *o*-wave for 2ω. This can readily be understood by considering a specific example. We consider the SHG in KDP corresponding to the incident ruby laser wavelength ($\lambda_0 = 0.6943\ \mu\text{m}$, $\omega = 2.7150 \times 10^{15}$ Hz). For this frequency:

$$\left\{ \begin{array}{ll} n_o^{\omega} = 1.50502, & n_e^{\omega} = 1.46532 \\ n_o^{2\omega} = 1.53269, & n_e^{2\omega} = 1.48711 \end{array} \right\} \qquad [20]$$

The refractive index variation for the *e*-wave is given by:

$$n_e(\theta) = \left(\frac{\sin^2\theta}{n_e^2} + \frac{\cos^2\theta}{n_o^2} \right)^{-\frac{1}{2}} \qquad [21]$$

where θ is the angle that the wave propagation direction makes with the optic axis. Now, as can be seen from the above equations:

$$n_e < n_e(\theta) < n_o \qquad [22]$$

Since n_o at 0.6943 μm lies between n_e and n_o at 0.34715 μm, there will always exist an angle θ_m along which $n_e^{2\omega}(\theta_m) = n_o^{\omega}$. We can solve for θ_m and obtain:

$$\cos\theta_m = \left[\frac{(n_o^{\omega})^2 - (n_e^{2\omega})^2}{(n_o^{2\omega})^2 - (n_e^{2\omega})^2} \right]^{1/2} \frac{n_o^{2\omega}}{n_o^{\omega}} \qquad [23]$$

For the values given by eqn [20], we find $\theta_m = 50.5°$.

Quasi Phase Matching (QPM)

As mentioned earlier, phase matching is extremely important for any efficient nonlinear interaction. Recently the technique of quasi phase matching (QPM) has become a convenient way to achieve phase matching at any desired wavelength in any material. QPM relies on the fact that the phase mismatch in the two interacting beams can be compensated by periodically readjusting the phase of interaction through periodically modulating the nonlinear characteristics of the medium at a spatial frequency equal to the wavevector mismatch of the two interacting waves. Thus in SHG, when the nonlinear polarization at 2ω and the electromagnetic wave at 2ω have an accumulated phase difference of π, then the sign of the nonlinear coefficient is reversed so that the energy flowing from the polarization to the wave can add constructively with the existing energy (see Figure 5). Thus, by properly choosing the period of the spatial modulation of the nonlinear coefficient, one could achieve phase matching. This scheme, QPM, is being very widely studied for application to nonlinear interactions in bulk and in waveguides.

In a ferroelectric material such as lithium niobate, the signs of the nonlinear coefficients are linked to the direction of the spontaneous polarization. Thus a



Figure 4 In a birefringent medium, for example with $n_o > n_e$, it may be possible to find a direction along which the refractive index of the *o*-wave for ω equals the refractive index of the *e*-wave for 2ω.



Figure 5 By reversing the sign of the nonlinear coefficient after every coherence length, the energy in the second harmonic can be made to grow. (a) Perfect phase matching; (b) Quasi phase matching; (c) Nonphase matched.

periodic reversal of the domains of the crystal can be used for achieving QPM (see Figure 6). This is the currently used technique to obtain high-efficiency SHG and other nonlinear interactions in $LiNbO_3$, $LiTaO_3$, and KTP. The most popular technique today, to achieve periodic domain reversal in $LiNbO_3$, is the technique of electric field poling. In this method, a high electric field pulse is applied to properly oriented lithium niobate crystal using lithographically defined electrode patterns to produce a permanent periodic domain reversed pattern. Such a periodically domain reversed $LiNbO_3$ crystal with the periodically reversed domains going through the entire depth of the crystal is also referred to as PPLN (periodically poled lithium niobate, pronounced 'piplin') and is now commercially available.

In order to analyze SHG in a periodically poled material, let us assume that the nonlinear coefficient d varies sinusoidally with a period Λ. In such a case we have:

$$d = d_0 \sin(Kz) \qquad [24]$$

where d_0 is the amplitude of modulation of the nonlinear coefficient and $K(= 2\pi/\Lambda)$ represents the spatial frequency of the periodic modulation. For easier understanding we are assuming the modulation to be sinusoidal; in general, the modulation will be periodic but not sinusoidal. Any periodic modulation can be written as a superposition of sinusoidal and cosinusoidal variations. Thus our discussion is valid for one of the Fourier components of the variation.

By using eqn [24], eqn [11] for the variation of the amplitude of the second harmonic becomes:

$$\frac{dE_2}{dz} = -\frac{i\mu_0 d_0 c\omega}{n^{2\omega}} E_1^2(z)e^{i(\Delta k)z} \sin(Kz) \qquad [25]$$

which can be written as:

$$\frac{dE_2}{dz} = -\frac{\mu_0 d_0 c\omega}{2n^{2\omega}} E_1^2(z)e^{i(\Delta k)z}[e^{iKz} - e^{-iKz}] \qquad [26]$$

Using similar arguments as earlier, it can be shown that if $\Delta k - K = 0$, then only the second term within the brackets in eqn [26] contributes to the growth of the second harmonic and similarly if $\Delta k + K = 0$, then only the first term within the brackets contributes to the growth of the second harmonic. The first condition implies that:

$$2\frac{2\pi}{\lambda_0}(n^{2\omega} - n^{\omega}) - \frac{2\pi}{\Lambda} = 0 \qquad [27]$$

where $\Lambda = 2\pi/K$ represents the spatial period of the modulation of the nonlinear coefficient, and λ_0 is the wavelength of the fundamental. Thus the modulation period Λ required for QPM SHG is:

$$\Lambda = \frac{\lambda_0}{2(n^{2\omega} - n^{\omega})} = 2\,L_c \qquad [28]$$

Figure 7 shows the vector diagram corresponding to QPM SHG. The phase mismatch between the fundamental and second harmonic is compensated by the spatial frequency vector of the periodic variation of d.

In the case of waveguides, n^{ω} and $n^{2\omega}$ would represent the effective indices of the modes at the fundamental and the second-harmonic frequency. It may be noted that the index difference between the fundamental and the second harmonic is typically 0.1 and thus the required spatial periods for a fundamental wavelength of 800 nm is ~4 μm.

The main advantage of QPM is that it can be used at any wavelength within the transparency window of the material; only the period needs to be correctly chosen for a specific fundamental wavelength. One can also choose appropriate polarization to make use of the largest nonlinear optical coefficients. Another advantage is the possibility of varying the domain reversal period (chirp) to achieve specific interaction characteristics such as increased bandwidth, etc.

In general, the spatial variation of the nonlinear grating is not sinusoidal. In this case the efficiency of interaction would be determined by the Fourier component of the spatial variation at the spatial frequency corresponding to the period given by eqn [28]. Also, since the required periods are very small, it is possible to use a higher spatial period of modulation and use one of the Fourier components for the nonlinear interaction process. Thus, in the case of periodic reversal of the nonlinear coefficient



Figure 6 QPM can be achieved by a periodic reversal of the domains of a ferroelectric material. Arrows represent the direction of the spontaneous polarization of the crystal.



Figure 7 Vector diagram corresponding to QPM-SHG.

with a spatial period given by:

$$\Lambda_g = m\frac{\lambda_0}{2(n^{2\omega} - n^{\omega})}; \qquad m = 1, 3, 5, \ldots \qquad [29]$$

which happens to be the m^{th} harmonic of the fundamental spatial frequency required for QPM, the corresponding nonlinear coefficient that would be responsible for SHG would be the Fourier amplitude at that spatial frequency. This can be taken into account by defining an effective nonlinear coefficient:

$$d_{\text{QPM}} = \frac{2d_0}{m\pi} \qquad [30]$$

Of course the largest effective nonlinear coefficient is achieved by using the fundamental frequency with $m = 1$. Higher spatial periods are easier to fabricate but would lead to reduced nonlinear efficiencies.

As compared to bulk devices, in the case of waveguides, the interacting waves are propagating in the form of modes having specific intensity distributions in the transverse plane. Because of this, the nonlinear interaction also depends on the overlap between the periodically inverted nonlinear medium, the fields of the fundamental and second-harmonic waves. Thus if $E_\omega(x, y)$ and $E_{2\omega}(x, y)$ represent the electric field distributions of the waveguide modes at the fundamental and second-harmonic frequency, then the efficiency of SHG depends on the following overlap integral:

$$I_{\text{ovl}} = \int\int d_0(x, y)E_\omega^2(x, y)E_{2\omega}(x, y)\,\mathrm{d}x\,\mathrm{d}y \qquad [31]$$

where $d_0(x, y)$ represents the transverse variation of the nonlinear coefficient of the waveguide. Thus optimization of SHG efficiency in the case of waveguide interactions has to take account of the overlap integral.

Since QPM relies on periodic phase matching, it is highly wavelength dependent. Thus the required period Λ is different for different fundamental frequencies. Any deviation in the frequency of the fundamental would lead to a reduction in the efficiency due to deviation from QPM condition. Thus the pump laser needs to be highly stabilized at a frequency corresponding to the fabricated period.

Apart from SHG, QPM has been used for other three-wave interaction processes such as difference frequency generation, parametric amplification, etc. Among the many materials that have been studied for SHG using QPM, the important ones are lithium niobate, lithium tantalite, and potassium titanyl phosphate (KTP). Many techniques have been developed for periodic domain reversal to achieve a periodic variation in the nonlinear coefficient. This includes electric field poling, electron bombardment, thermal diffusion treatment, etc.

Third-Order Nonlinear Effects

In the earlier sections, we discussed effects arising out of second-order nonlinearity, i.e., the term proportional to E^2 in the nonlinear polarization. This nonlinear term is found only in media not possessing an inversion symmetry. Thus amorphous materials or crystals possessing inversion symmetry do not exhibit second-order effects. The lowest-order nonlinear effects in such a medium is of an order three wherein the nonlinear polarization is proportional to E^3.

Self-phase modulation (SPM), cross-phase modulation (XPM) and four-wave mixing (FWM) represent some of the very important consequences of third-order nonlinearity. These effects have become all the more important as they play a significant and important role in wavelength division multiplexed optical fiber communication systems.

Self-Phase Modulation (SPM)

Consider the propagation of a plane light wave at frequency ω through a medium having $\chi^{(3)}$ nonlinearity. The polarization generated in the medium is given by

$$P = \varepsilon_0\chi E + \varepsilon_0\chi^{(3)}E^3 \qquad [32]$$

If we consider a single frequency wave with an electric field given by

$$E = E_0\cos(\omega t - kz) \qquad [33]$$

then

$$P = \varepsilon_0\chi E_0\cos(\omega t - kz) + \varepsilon_0\chi^{(3)}E_0^3\cos^3(\omega t - kz) \qquad [34]$$

Expanding $\cos^3\theta$ in terms of $\cos\theta$ and $\cos 3\theta$, we obtain the following expression for the polarization at frequency ω:

$$P = \varepsilon_0\left(\chi + \frac{3}{4}\chi^{(3)}E_0^2\right)E_0\cos(\omega t - kz) \qquad [35]$$

For a plane wave given by eqn [33], the intensity is

$$I = \frac{1}{2}c\varepsilon_0 n_0 E_0^2 \qquad [36]$$

where n_0 is the refractive index of the medium at low intensity. Then

$$P = \varepsilon_0\left(\chi + \frac{3}{2}\frac{\chi^{(3)}}{c\varepsilon_0 n_0}I\right)E \qquad [37]$$

The polarization P and electric field are related through the following equation:

$$P = \varepsilon_0(n^2 - 1)E \qquad [38]$$

where n is the refractive index of the medium. Comparing eqns [37] and [38], we get

$$n^2 = n_0^2 + \frac{3}{2}\frac{\chi^{(3)}}{c\varepsilon_0 n_0} I \qquad [39]$$

where

$$n_0^2 = 1 + \chi \qquad [40]$$

Since the last term in the eqn [39] is usually very small, we get

$$n = n_0 + n_2 I \qquad [41]$$

where

$$n_2 = \frac{3}{4}\frac{\chi^{(3)}}{c\varepsilon_0 n_0^2} \qquad [42]$$

is the nonlinear coefficient.

For fused silica $n_0 \approx 1.47$, $n_2 \approx 3.2 \times 10^{-20}$ m^2/W and if we consider power of 100 mW having a cross-sectional area of 100 μm^2, the resultant intensity is 10^9 W/m^2 and the corresponding change in refractive index is

$$\Delta n \approx n_2 I \approx 3.2 \times 10^{-11} \qquad [43]$$

Although this is very small, when the beam propagates over an optical fiber over long distances (a few hundred to a few thousand kilometers), the accumulated nonlinear effects can be significant.

In the case of an optical fiber, the light beam propagates as a mode having a specific transverse electric field distribution and thus the intensity is not constant across the cross-section. In such a case, it is convenient to express the nonlinear effect in terms of the power carried by the mode (rather than in terms of intensity). If the linear propagation constant of the mode is represented by β, then in the presence of nonlinearity, the effective propagation constant is given by

$$\beta_{\mathrm{NL}} = \beta + \frac{k_0 n_2}{A_{\mathrm{eff}}} P \qquad [44]$$

where $k_0 = 2\pi/\lambda_0$, P is the power carried by the mode. The quantity A_{eff} represents the effective transverse cross-sectional area of the mode and is defined by

$$A_{\mathrm{eff}} = \frac{\left[\int_0^\infty \int_0^{2\pi} \psi^2(r) r \,\mathrm{d}r\,\mathrm{d}\phi\right]^2}{\int_0^\infty \int_0^{2\pi} \psi^4(r) r \,\mathrm{d}r\,\mathrm{d}\phi} \qquad [45]$$

where $\psi(r)$ represents the transverse mode field distribution of the mode. For example, under the Gaussian approximation:

$$\psi(r) = \psi_0\, \mathrm{e}^{-r^2/w_0^2} \qquad [46]$$

where ψ_0 is a constant and $2w_0$ represents the mode field diameter (MFD), we get:

$$A_{\mathrm{eff}} = \pi w_0^2 \qquad [47]$$

It is usual to express the nonlinear characteristic of an optical fiber by the coefficient given by

$$\gamma = \frac{k_0 n_2}{A_{\mathrm{eff}}} \qquad [48]$$

Thus, for the same input power and same wavelength, smaller values of A_{eff} lead to greater nonlinear effects in the fiber. Typically:

$$\begin{aligned} &A_{\mathrm{eff}} \sim 50\text{–}80\ \mu\mathrm{m}^2 \quad \text{and} \\ &\gamma \approx 2.4\ \mathrm{W}^{-1}\,\mathrm{km}^{-1} \ \text{to}\ 1.5\ \mathrm{W}^{-1}\,\mathrm{km}^{-1} \end{aligned} \qquad [49]$$

When a light beam propagates through an optical fiber, the power decreases because of attenuation. Thus, the corresponding nonlinear effects also reduce. Indeed, the phase change suffered by a beam in propagating from 0 to L is given by

$$\phi = \int_0^L \beta_{\mathrm{NL}}\,\mathrm{d}z = \beta L + \gamma \int_0^L P\,\mathrm{d}z \qquad [50]$$

If α represents the attenuation coefficient, then

$$P(z) = P_0\, \mathrm{e}^{-\alpha z} \qquad [51]$$

and we get

$$\phi = \beta L + \gamma P_0 L_{\mathrm{eff}} \qquad [52]$$

where

$$L_{\mathrm{eff}} = \frac{1 - \mathrm{e}^{-\alpha L}}{\alpha} \qquad [53]$$

is referred to as the effective length. For $\alpha L \gg 1$, $L_{\mathrm{eff}} \approx 1/\alpha$ and for $\alpha L \ll 1$, $L_{\mathrm{eff}} \approx L$.

The effective length represents the length of the fiber over which most of the nonlinear effects has accumulated. For a loss coefficient of 0.20 dB/km, $L_{\mathrm{eff}} \approx 21$ km.

If we consider a fiber length much longer than L_{eff}, then to have reduced impact of SPM, we must have

$$\gamma P_0 L_{\mathrm{eff}} \ll 1 \qquad [54]$$

or

$$P_0 \ll \frac{1}{\gamma L_{\mathrm{eff}}} \approx \frac{\alpha}{\gamma} \qquad [55]$$

For $\alpha = 4.6 \times 10^{-2}$ km^{-1} (which corresponds to an attenuation of 0.2 dB/km) and $\gamma = 2.4$ W^{-1} km^{-1}, we get

$$P_0 \ll 19\ \mathrm{mW} \qquad [56]$$

Propagation of a Pulse

When an optical pulse propagates through a medium, it suffers from the following effects:

(i) attenuation;
(ii) dispersion; and
(iii) nonlinearity.

Attenuation refers to the reduction in the pulse energy due to various mechanisms, such as scattering, absorption, etc. Dispersion is caused by the fact that a light pulse consists of various frequency components and each frequency component travels at a different group velocity. Dispersion causes the temporal width of the pulse to change; in most cases it results in an increase in pulse width, however, in some cases the temporal width could also decrease. Dispersion is accompanied by chirping, the variation of the instantaneous frequency of the pulse within the pulse duration. Since both attenuation and dispersion cause a change in the temporal variation of the optical power, they closely interact with nonlinearity in deciding the pulse evolution as it propagates through the medium.

Let $E(x, y, z, t)$ represent the electric field variation of an optical pulse. It is usual to express E in the following way:

$$E(x, y, z, t) = \frac{1}{2}[A(z, t)\psi(x, y)e^{i(\omega_0 t - \beta_0 z)} + \text{c.c.}] \quad [57]$$

where $A(z, t)$ represents the slowly varying complex envelope of the pulse, $\psi(x, y)$ represents the transverse electric field distribution, ω_0 represents center frequency, and β_0 represents the propagation constant at ω_0.

In the presence of attenuation, second-order dispersion and third-order nonlinearity, the complex envelope $A(z, t)$ can be shown to satisfy the following equation:

$$\frac{\partial A}{\partial z} = -\frac{\alpha}{2}A - \beta_1\frac{\partial A}{\partial t} + i\frac{\beta_2}{2}\frac{\partial^2 A}{\partial t^2} - i\gamma|A|^2 A \quad [58]$$

Here

$$\beta_1 = \left|\frac{d\beta}{d\omega}\right|_{\omega=\omega_0} = \frac{1}{v_g} \quad [59]$$

represents the inverse of the group velocity of the pulse, and

$$\beta_2 = \left|\frac{d^2\beta}{d\omega^2}\right|_{\omega=\omega_0} = -\frac{\lambda_0^2}{2\pi c}D \quad [60]$$

where D represents the group velocity dispersion (measured in ps/km nm).

The various terms on the RHS of the eqn [58] represent the following:

I term:	attenuation
II term:	group velocity term
III term:	second-order dispersion
IV term:	nonlinear term

If we change to a moving frame defined by coordinates $T = t - \beta_1 z$, eqn [58] becomes

$$\frac{\partial A}{\partial z} = -\frac{\alpha}{2}A + i\frac{\beta_2}{2}\frac{\partial^2 A}{\partial T^2} - i\gamma|A|^2 A \quad [61]$$

If we neglect the attenuation term, we obtain the following equation which is also referred to as the nonlinear Schrödinger equation:

$$\frac{\partial A}{\partial z} = i\frac{\beta_2}{2}\frac{\partial^2 A}{\partial T^2} - i\gamma|A|^2 A \quad [62]$$

The above equation has a solution given by

$$A(z, t) = A_0 \operatorname{sech} \sigma T\, e^{-igz} \quad [63]$$

with

$$A_0^2 = -\frac{\beta_2}{\gamma}\sigma^2, \qquad g = -\frac{\sigma^2}{2}\beta_2 \quad [64]$$

Equation [63] represents an envelope soliton and has the property that it propagates undispersed through the medium. The full width at half maximum (FWHM) of the pulse envelope will be given by $\tau_f = 2\tau_0$, where

$$\operatorname{sech}^2 \sigma\tau_0 = \frac{1}{2} \quad [65]$$

which gives the FWHM τ_f:

$$\tau_f = 2\tau_0 = \frac{2}{\sigma}\ln(1 + \sqrt{2}) \approx \frac{1.7627}{\sigma} \quad [66]$$

The peak power of the pulse is:

$$P_0 = |A_0|^2 = \frac{|\beta_2|}{\gamma}\sigma^2 \quad [67]$$

Replacing σ by τ_f, we obtain

$$P_0\tau_f^2 \approx \frac{\lambda_0^2}{2c\gamma}D \quad [68]$$

where we have used eqn [60]. The above equation gives the required peak for a given τ_f for the formation of a soliton pulse.

As an example, we have $\tau_f = 10$ ps, $\gamma = 2.4\ \text{W}^{-1}\ \text{km}^{-1}$, $\lambda_0 = 1.55\ \mu\text{m}$, $D = 2$ ps/km nm and the required peak power will be $P_0 = 33$ mW.

Soliton pulses are being extensively studied for application to long distance optical fiber communication. In actual systems, the pulses have to be optically amplified at regular intervals to compensate for the loss suffered by the pulses. The amplification could be carried out using erbium doped fiber amplifiers (EDFAs) or fiber Raman amplifiers.

Spectral Broadening due to SPM

In the presence of only nonlinearity, eqn [61] becomes

$$\frac{\mathrm{d}A}{\mathrm{d}z} = -i\gamma|A|^2A \qquad [69]$$

whose solution is given by

$$A(z,t) = A(z=0,t)\mathrm{e}^{-\mathrm{i}\gamma Pz} \qquad [70]$$

where $P = |A|^2$ is the power in the pulse. If P is a function of time, then time dependent phase term at $z = L$ becomes

$$\mathrm{e}^{\mathrm{i}\phi(t)} = \mathrm{e}^{\mathrm{i}[\omega_0 t - \gamma P(t)L]} \qquad [71]$$

We can define an instantaneous frequency as

$$\omega(t) = \frac{\mathrm{d}\phi}{\mathrm{d}t} = \omega_0 - \gamma L\frac{\mathrm{d}P}{\mathrm{d}t} \qquad [72]$$

for a Gaussian pulse:

$$P = P_0\,\mathrm{e}^{-2T^2/\tau_0^2} \qquad [73]$$

giving

$$\omega(t) = \omega_0 + \frac{4\gamma LTP_0\,\mathrm{e}^{-2T^2/\tau_0^2}}{\tau_0^2} \qquad [74]$$

Thus the instantaneous frequency within the pulse changes with time, leading to chirping of the pulse (see Figure 8). Note that since the pulsewidth has not changed, but the pulse is chirped, the frequency spectrum of the pulse has increased. Thus SPM leads to the generation of new frequencies. By Fourier transform theory, an increased spectral width implies that the pulse can now be compressed in the temporal domain by passing it through a medium with the proper sign of dispersion. This is indeed one of the standard techniques to realize ultrashort femtosecond optical pulses.



Figure 8 Due to self phase modulation, the instantaneous frequency within the pulse changes with time leading to chirping of the pulse.

Cross Phase Modulation (XPM)

Like SPM, cross-phase modulation also arises due to the intensity dependence of refractive index, leading to spectral broadening. Unlike SPM, in the case of XPM, intensity variations of a light beam at a particular frequency modulate the phase of light beam at another frequency. If the signals at both frequencies are pulses, then due to difference in group velocities of the pulses, there is a walk off between the two pulses, i.e., if they start together, they will separate as they propagate through the medium. Nonlinear interaction takes place as long as they physically overlap in the medium. Smaller the dispersion, smaller will be the difference in group velocities (assuming closely spaced wavelengths) and the longer they will overlap. This would lead to stronger XPM effects. At the same time, if two pulses pass through each other, then since one pulse will interact with both the leading and the trailing edge of the other pulse, XPM effects will be nil provided there is no attenuation. In the presence of attenuation in the medium, the pulse will still get modified due to XPM. A similar situation can occur when the two interacting pulses are passing through an optical amplifier.

To study XPM, we assume simultaneous propagation of two waves at two different frequencies through the medium. If ω_1 and ω_2 represent the two frequencies, then one obtains for the variation of the amplitude A_1 of the frequency ω_1:

$$\frac{\mathrm{d}A_1}{\mathrm{d}z} = -i\gamma(\tilde{P}_1 + 2\tilde{P}_2)A_1 \qquad [75]$$

where $\tilde{P}_1$ and $\tilde{P}_2$ represent the powers at frequencies ω_1 and ω_2, respectively. The first term in eqn [75] represents SPM while the second term corresponds to XPM. If the powers are assumed to attenuate at the same rate, i.e.:

$$\tilde{P}_1 = P_1\,\mathrm{e}^{-\alpha z}, \qquad \tilde{P}_2 = P_2\,\mathrm{e}^{-\alpha z} \qquad [76]$$

then the solution of eqn [75] is

$$A_1(L) = A_1(0)\,\mathrm{e}^{-\mathrm{i}\gamma(P_1+2P_2)L_{\text{eff}}} \qquad [77]$$

where, as before, L_{eff} represents the effective length of the medium. When we are studying the effect of power at ω_2 on the light beam at frequency ω_1, we will refer to the wave at frequency ω_2 as pump, and the wave at frequency ω_1 as probe or signal. From eqn [77] it is apparent that the phase of signal at frequency ω_1 is modified by the power at another frequency. This is referred to as XPM. Note also that XPM is twice as effective as SPM.

Similar to the case of SPM, we can now write for the instantaneous frequency in the presence of XPM as eqn [72]:

$$\omega(t) = \omega_0 - 2\gamma L_{\text{eff}} \frac{\mathrm{d}P_2}{\mathrm{d}t} \qquad [78]$$

Hence the part of the signal that is influenced by the leading edge of the pump will be down-shifted in frequency (since in the leading edge $\mathrm{d}P_2/\mathrm{d}t > 0$) and the part overlapping with the trailing edge will be up-shifted in frequency (since $\mathrm{d}P_2/\mathrm{d}t < 0$). This leads to a frequency chirping of the signal pulse just as in the case of SPM.

If the probe and pump beams are pulses, then XPM can lead to induced frequency shifts depending on whether the probe pulse interacts only with the leading edge or trailing edge or both, as they both propagate through the medium. Let us consider a case when the group velocity of pump pulse is greater than that of the probe pulse. Thus, if both pulses enter the medium together, then since the pump pulse travels faster, the probe pulse will interact only with the trailing edge of the pump. Since in this case $\mathrm{d}P_2/\mathrm{d}t$ is negative, the probe pulse suffers a blue-induced frequency shift. Similarly if the pulses enter at different instants but completely overlap at the end of the medium, then $\mathrm{d}P_2/\mathrm{d}t > 0$ and the probe pulse would suffer a red-induced frequency shift. Indeed, if the two pulses start separately and walk through each other, then there is no induced shift due to cancellation of shifts induced by leading and trailing edges of the pump. Figure 9 shows measured induced frequency shift of 532 nm probe pulse as a function of the delay between this pulse and a pump pulse at 1064 nm, when they propagate through a 1 m long optical fiber.

When pulses of light at two different wavelengths propagate through an optical fiber, due to different group velocities of the pulses, they pass through each other, resulting in what could be termed as a collision. In the linear case, the pulses will pass through without affecting each other, but when intensity levels are high, XPM induces phase shifts in both pulses. We can define a parameter termed walk off length L_{wo} which is the length of the fiber required for the interacting pulses to walk off relative to each other. The walk off length is given by

$$L_{\text{wo}} = \frac{\Delta\tau}{D\Delta\lambda} \qquad [79]$$

where D represents the dispersion coefficient, and $\Delta\lambda$ represents the wavelength separation between the interacting pulses. For return to zero (RZ) pulses, $\Delta\tau$ represents the pulse duration while for nonreturn to zero (NRZ) pulses, $\Delta\tau$ represents the rise term or fall time of the pulse. Closely spaced channels will thus interact over longer fiber lengths, thus leading to greater XPM effects. Larger dispersion coefficients will reduce L_{wo} and thus the effects of XPM. Since the medium is attenuating, the power carried by the pulses decreases as they propagate and thus leading to reduced XPM effect. The characteristic length for attenuation is the effective length L_{eff}, defined by eqn [53]. If $L_{\text{wo}} \ll L_{\text{eff}}$, then over the length of interaction of the pulses, the intensity levels do not change appreciably and the magnitude of the XPM-induced effects will be proportional to the wavelength spacing $\Delta\lambda$. For small $\Delta\lambda$'s, $L_{\text{wo}} \gg L_{\text{eff}}$ and the interaction length is now determined by the fiber losses (rather than by walk off) and the XPM-induced effects become almost independent of $\Delta\lambda$. Indeed, if we consider XPM effects between a continuous wave (cw) probe beam and a sinusoidally industry modulated pump beam, then the amplitude of the XPM-induced



Figure 9 Measured induced frequency shift of 532 nm probe pulse as a function of the delay between this pulse and a pump pulse at 1064 nm, when they propagate through a 1 m long optical fiber. (Reproduced from Baldeck PL, Alfano RR and Agrawal GP (1998) Induced frequency shift of copropagating ultrafast optical pulses. *Applied Physics Letters* 52: 1939–1941 with permission from the American Institute of Physics.)

phase shift ($\Delta\Phi_{pr}$) in the probe beam is given by:

$$\begin{aligned} \Delta\Phi_{pr} &\approx 2\gamma P_{2m} L_{eff} \quad \text{for} \quad L_{wo} \gg L_{eff} \\ \Delta\Phi_{pr} &\approx 2\gamma P_{2m} L_{wo} \quad \text{for} \quad L_{wo} \ll L_{eff} \end{aligned} \qquad [80]$$

Here P_{2m} is the amplitude of the sinusoidal power modulation of the pump beam.

XPM-induced intensity interference can be studied by simultaneously propagating an intensity modulated pump signal and a cw probe signal at a different wavelength. The intensity modulated signal will induce phase modulation on the cw probe signal and the dispersion of the medium will convert the phase modulation to intensity modulation of the probe. Thus, the magnitude of the intensity fluctuation of the probe signal serves as an estimate of the XPM induced interference. Figure 10 shows the intensity fluctuations on a probe signal at 1550 nm, induced by a modulated pump for a channel separation of 0.6 nm. Figure 11 shows the variation of the RMS value of probe intensity modulation with the wavelength separation between the intensity modulated signal and the probe. The experiment has been performed over four amplified spans of 80 km of standard single mode fiber (SMF) and nonzero dispersion shifted fiber (NZDSF). The large dispersion in SMF has been compensated using dispersion compensating chirped gratings. The probe modulation, in the case of SMF, decreases approximately linearly with 1/Δλ for all Δλs; the modulation is independent of Δλ. In contrast the NZDSF shows a constant modulation for Δλ ≤ 1 nm.



Figure 10 Intensity fluctuations induced by cross phase modulation on a probe signal at 1550 nm by a modulated pump for a channel separation of 0.6 nm. (Reproduced with permission from Rapp L (1997) Experimental investigation of signal distortions induced by cross phase modulation combined with dispersion. *IEEE Photon Technical Letters* 9: 1592–1595, © 2004 IEEE.)



Figure 11 Variation of the RMS value of probe intensity modulation with the wavelength separation between the intensity modulated signal and the probe. (Reproduced with permission from Shtaif M, Eiselt M and Garret LD (2000) Cross-phase modulation distortion measurements in multispan WDM systems. *IEEE Photon Technical Letters* 12: 88–90, © 2004 IEEE.)

This is consistent with the earlier discussion in terms of L_{wo} and L_{eff}.

Four-Wave Mixing (FWM)

Four-wave mixing (FWM) is a nonlinear interaction that occurs in the presence of multiple wavelengths in a medium, leading to the generation of new frequencies. Thus, if light waves at three different frequencies ω_2, ω_3, ω_4 are launched simultaneously into a medium, the same nonlinear polarization that led to intensity dependent refractive index, leads to nonlinear polarization component at a frequency:

$$\omega_1 = \omega_3 + \omega_4 - \omega_2 \qquad [81]$$

This nonlinear polarization, under certain conditions, leads to the generation of electromagnetic waves at ω_1. This process is referred to as four-wave mixing due to the interaction between four different frequencies. Degenerate four-wave mixing corresponds to the case when two of the input waves have the same frequency. Thus, if $\omega_3 = \omega_4$, then inputting waves at ω_2 and ω_3 leads to the generation of waves at the frequency

$$\omega_1 = 2\omega_3 - \omega_2 \qquad [82]$$

During FWM process, there are four different frequencies present at any point in the medium. If we write the electric field of the waves as

$$E_i = \frac{1}{2}[A_i(z)\psi_i(x,y)e^{i(\omega_i t - \beta_i z)} + \text{c.c.}], \qquad [83]$$
$$i = 1, 2, 3, 4$$

where, as before, $A_i(z)$ represents the amplitude of the wave, $\psi_i(x, y)$ the transverse field distribution, and β_i the propagation constant of the wave. The total electric field is given by

$$E = E_1 + E_2 + E_3 + E_4 \qquad [84]$$

Substituting for the total electric field in the equation for nonlinear polarization, the term with frequency ω_1 comes out as

$$P_{\mathrm{NL}}^{(\omega_1)} = \frac{1}{2}[P_{\mathrm{NL}}^{(\omega_1)}\, \mathrm{e}^{\mathrm{i}(\omega_1 t - \beta_1 z)} + \mathrm{c.c.}] \qquad [85]$$

where

$$P_{\mathrm{NL}}^{(\omega_1)} = \frac{3\varepsilon_0}{2}\chi^{(3)} A_2^* A_3 A_4 \psi_2 \psi_3 \psi_4\, \mathrm{e}^{-\mathrm{i}\Delta\beta z} \qquad [86]$$

and

$$\Delta\beta = \beta_3 + \beta_4 - \beta_2 - \beta_1 \qquad [87]$$

In writing eqn [86], we have only considered the FWM term, neglecting the SPM and XPM terms.

Substituting the expression for $P_{\mathrm{NL}}^{(\omega_1)}$ in the wave equation for ω_1 and making the slowly varying approximation (in a manner similar to that employed in the case of SPM and XPM), we obtain the following equation for $A_1(z)$:

$$\frac{\mathrm{d}A_1}{\mathrm{d}z} = -2i\gamma A_2^* A_3 A_4\, \mathrm{e}^{-\mathrm{i}\Delta\beta z} \qquad [88]$$

where γ is defined by eqn [48] with $k_0 = \omega/c$, ω representing the average frequency of the four interacting waves, and A_{eff} is the average effective area of the modes.

Assuming all waves to have the same attenuation coefficient α and neglecting depletion of waves at frequencies ω_2, ω_3 and ω_4, due to nonlinear conversion we obtain for the power in the frequency ω_1 as

$$P_1(L) = 4\gamma^2 P_2 P_3 P_4 L_{\mathrm{eff}}^2 \eta\, \mathrm{e}^{-\alpha L} \qquad [89]$$

where

$$\eta = \frac{\alpha^2}{\alpha^2 + \Delta\beta^2}\left[1 + \frac{4\mathrm{e}^{-\alpha L}\sin^2\frac{\Delta\beta L}{2}}{(1 - \mathrm{e}^{-\alpha L})^2}\right] \qquad [90]$$

and L_{eff} is the effective length (see eqn [53]). Maximum four-wave mixing takes place when $\Delta\beta = 0$, since in such a case $\eta = 1$. Now:

$$\Delta\beta = \beta(\omega_3) + \beta(\omega_4) - \beta(\omega_2) - \beta(\omega_1) \qquad [91]$$

Since the frequencies are usually close to each other, we can make a Taylor series expansion about any frequency, say ω_2. In such a case, we obtain

$$\Delta\beta = (\omega_3 - \omega_2)(\omega_3 - \omega_1)\left|\frac{\mathrm{d}^2\beta}{\mathrm{d}\omega^2}\right|_{\omega=\omega_2} \qquad [92]$$

In optical fiber communication systems, the channels are usually equally spaced. Thus, we assume the frequencies to be given by

$$\begin{aligned} &\omega_4 = \omega_2 + \Delta\omega, \qquad \omega_3 = \omega_2 - 2\Delta\omega \text{ and} \\ &\omega_1 = \omega_2 - \Delta\omega \end{aligned} \qquad [93]$$

Using these frequencies and eqn [60], eqn [92] gives us:

$$\Delta\beta = -\frac{4\pi D\lambda^2}{c}(\Delta\nu)^2 \qquad [94]$$

where $\Delta\omega = 2\pi\Delta\nu$. Thus maximum FWM takes place when $D = 0$. This is the main problem in using wavelength division multiplexing (WDM) in dispersion shifted fibers which are characterized by zero dispersion at the operating wavelength of 1550 nm, as FWM will then lead to crosstalk among various channels. FWM efficiency can be reduced by using fiber with nonzero dispersion. This has led to the development of nonzero dispersion shifted fiber (NZDSF) which have a finite nonzero dispersion of about ±2 ps/km nm at the operating wavelength.

From eqn [94], we notice that for a given dispersion coefficient D, FWM efficiency will reduce as $\Delta\nu$ increases.

In order to get a numerical appreciation, we consider a case with $D = 0$, i.e., $\Delta\beta = 0$. For such a case $\eta = 1$. If all channels were launched with equal power P_{in} then:

$$P_1(L) = 4\gamma^2 P_{\mathrm{in}}^3 L_{\mathrm{eff}}^2\, \mathrm{e}^{-\alpha L} \qquad [95]$$

Thus the ratio of power generated at ω_1, due to FWM and that existing at the same frequency, is

$$\frac{P_{\mathrm{g}}}{P_{\mathrm{out}}} = \frac{P_1(L)}{P_{\mathrm{in}}\,\mathrm{e}^{-\alpha L}} = 4\gamma^2 P_{\mathrm{in}}^2 L_{\mathrm{eff}}^2 \qquad [96]$$

Typical values are $L_{\mathrm{eff}} = 20$ km, $\gamma = 2.4\ \mathrm{W}^{-1}\ \mathrm{km}^{-1}$. Thus:

$$\frac{P_{\mathrm{g}}}{P_{\mathrm{out}}} \approx 0.01 P_{\mathrm{in}}^2 (\mathrm{mW}^2) \qquad [97]$$

Figure 12 shows the output spectrum measured at the output of a 25 km-long dispersion shifted fiber ($D = -0.2$ ps/km nm) when three 3 mW wavelengths are launched simultaneously. Notice the generation of many new frequencies by FWM. Figure 13 shows the



Figure 12 Generation of new frequencies because of FWM when waves at three frequencies are incident in the fiber. (Reproduced with permission from Tkach RW, Chraplyvy AR, Forghiari F, Gnanck AH and Derosier RM (1995) Four-photon mixing and high speed WDM systems. *Journal of lightwave Technology* 13: 841–849, © 2004 IEEE.)



Figure 13 Ratio of generated power to the output as a function of channel spacing $\Delta\lambda$ for different dispersion coefficients. (Reproduced with permission from Tkach RW, Chraplyvy AR, Forghiari F, Gnanck AH and Derosier RM (1995) Four-photon mixing and high speed WDM systems. *Journal of lightwave Technology* 13: 841–849, © 2004 IEEE.)

ratio of generated power to the output as a function of channel spacing $\Delta\lambda$ for different dispersion coefficients. It can be seen that by choosing a nonzero value of dispersion, the four-wave mixing efficiency can be reduced. Larger the dispersion coefficient, smaller can be the channel spacing for the same crosstalk.

Since dispersion leads to increased bit error rates in fiber optic communication systems, it is important to have low dispersion. On the other hand, lower dispersion leads to crosstalk due to FWM. This problem can be resolved by noting that FWM depends on the local dispersion value in the fiber, while the pulse spreading at the end of a link depends on the overall dispersion in the fiber link. If one chooses a link made up of positive and negative dispersion coefficients, then by an appropriate choice of the lengths of the positive and negative dispersion fibers, it would be possible to achieve a zero total link dispersion while at the same time maintaining a large local dispersion. This is referred to as dispersion management in fiber optic systems.

Although FWM leads to crosstalk among different wavelength channels in an optical fiber communication system, it can be used for various optical processing functions such as wavelength conversion, high-speed time division multiplexing, pulse compression, etc. For such applications, there is a concerted worldwide effort to develop highly nonlinear fibers with much smaller mode areas and higher nonlinear coefficients. Some of the very novel fibers that have been developed recently include holey fibers, photonic bandgap fibers, or photonic crystal fibers which are very interesting since they possess extremely small mode effective areas ($\sim 2.5\ \mu\text{m}^2$ at 1550 nm) and can be designed to have zero dispersion even in the visible region of the spectrum. This is expected to revolutionize nonlinear fiber optics by providing new geometries to achieve highly efficient nonlinear optical processing at lower powers.

Supercontinuum Generation

Supercontinuum (SC) generation is the phenomenon in which a nearly continuous spectrally broadened output is produced through nonlinear effects on high peak power picosecond and subpicosecond pulses. Such broadened spectra find applications in spectroscopy, wavelength characterization of optical components such as a broadband source from which many wavelength channels can be obtained by slicing the spectrum.

Supercontinuum generation in an optical fiber is a very convenient technique since it provides a very broad bandwidth (>200 nm), the intensity levels can be maintained high over long interaction lengths by choosing small mode areas, and the dispersion profile of the fiber can be appropriately designed by varying the transverse refractive index profile of the fiber.

The spectral broadening that takes place in the fiber is attributed to a combination of various third-order effects such as SPM, XPM, FWM, and Raman scattering. Since dispersion plays a significant role in the temporal evolution of the pulse, different dispersion profiles have been used in the literature to achieve broadband SC.



(a) SC spectrum



(b)

Figure 14 Super Continuum spectrum generated by passing 25 GHz optical pulse train at 1544 nm generated by a mode locked laser diode and amplified by an erbium doped fiber. (Reproduced from Yamada E, Takara H, Ohara T, Satc K, Morioka T, Jinguji K, Itoh M and Ishi M (2001) A high SNR, 150 Ch. Supercontinuum CW optical source with high SNR and precise 25 GHz spacing for 10 Gbit/s DWDM systems. *Electronics Letters* 37: 304–306 with permission from IEEE.)

Some studies have used dispersion decreasing fibers, dispersion flattened fibers, while others have used a constant anamolous dispersion fiber followed by a normal dispersion fiber.

Figure 14 shows the SC spectrum generated by passing 25 GHz optical pulse train at 1544 nm generated by a mode locked laser diode and amplified by an erbium doped fiber. The fiber used for SC generation is a polarization maintaining dispersion flattened fiber. The output is a broad spectrum containing more than 150 spectral components at a spacing of 25 GHz with a flat top spectrum over 18 nm. The output optical powers range from −9 dBm to +3 dBm. Such sources are being investigated as attractive solutions for dense WDM (DWDM) optical fiber communication systems.

Conclusions

The advent of lasers provided us with an intense source of light and led to the birth of nonlinear optics. Nonlinear optical phenomena exhibit a rich variety of effects and coupled with optical waveguides and fibers, such effects can be observed even at moderate optical powers. With the realization of compact femtosecond lasers, highly nonlinear holey optical fibers, quasi phase matching techniques, etc, the field of nonlinear optics is expected to grow further and lead to commercial exploitation such as in compact blue lasers, soliton laser sources and multiwavelength sources and for fiber optic communication.

List of Units and Nomenclature

Attenuation	The decrease in optical power of a propagating mode usually expressed in dB/km
Birefringent medium	A medium characterized by two different modes of propagation characterized by two different polarization states of a plane light wave along any direction
Cross-phase modulation (XPM)	The phase modulation of a propagating light wave due to the nonlinear change in refractive index of the medium brought about by another propagating light wave
Effective length (L_{eff})	The length over which most of the nonlinear effect is accumulated in a propagating light beam
Four-wave mixing (FWM)	The mixing of four propagating light waves due to intensity dependent refractive index of the medium. This mixing leads to the generation of new frequencies from a set of two or three input light beams
Mode effective area (A_{eff})	The cross sectional area of the mode which determines the nonlinear effects on the propagating mode. This is different from the core area
Nonlinear polarization (P_{NL})	When the response of the medium to an applied electric field is not proportional to the applied electric field, then this results in a nonlinear polarization
Optical waveguides	Devices which are capable of guiding optical beams by overcoming diffraction effects using

	the phenomenon of total internal reflection
Phase coherence length	The minimum crystal length upto which the second harmonic power generated by the nonlinear interaction increases
Phase matching	Condition under with the nonlinear polarization generating an electromagnetic wave propagates at the same phase velocity as the generated electromagnetic wave
Pulse dispersion	The broadening of a light pulse as it propagates in an optical fiber
Quasi-phase matching (QPM)	Periodic modulation of the nonlinear coefficient to achieve efficient nonlinear interaction
Second-harmonic generation (SHG)	The generation of a wave of frequency 2ω from an incident wave of frequency ω through nonlinear interaction in a medium
Self-phase modulation (SPM)	The modulation of the phase of a propagating light wave due to the nonlinear change in refractive index of the medium brought about by itself
Supercontinuum generation (SC)	The phenomenon in which a nearly contiunuous spectrally broadband output is produced through nonlinear effects on high peak power picosecond and sub-picosecond pulses
Walk off length (L_{wo})	Length of the fiber required for two interacting pulses at different wavelengths to walk off relative to each other

See also

Nonlinear Optics, Applications: Phase Matching. **Nonlinear Optics, Basics:** $\chi^{(2)}$–Harmonic Generation; $\chi^{(3)}$–Third-Harmonic Generation; Four-Wave Mixing. **Spectroscopy:** Second Harmonic Spectroscopy.

Further Reading

Agrawal GP (1989) *Nonlinear Fiber Optics*. Boston, MA: Academic Press.

Armstrong JA, Bloembergen N, Ducuing J and Pershan PS (1962) Interactions between light waves in a nonlinear dielectric. *Physics Review* 127: 1918.

Baldeck PL, Alfano RR and Agrawal GP (1998) Induced frequency shift of copropagating ultrafast optical pulses. *Applied Physics Letters* 52: 1939–1941.

Baldi P (1992) *Generation de fluorescence parametrique guidee sur niobate et tantalite de lithium polarizes periodiquement. Etudes preliminaire d'un oscillateur parmetrique optique integree*. Doctoral Thesis of the University of Nice, France.

Chiang TK, Kagi N, Marhic ME and Kazovsky LG (1996) Cross phase modulation in fiber links with multiple optical amplifiers and dispersion compensators. *Journal of Lightwave Technology* 14: 249–259.

Franken PA, Hill AE, Peter CW and Weinreich G (1961) Generation of optical harmonics. *Physics Review Letters* 7: 118.

Ghatak AK and Thyagarajan K (1987) *Optical Electronics*. Cambridge, UK: Cambridge University Press.

Ghatak AK and Thyagarajan K (1998) *Introduction to Fiber Optics*. Cambridge, UK: Cambridge University Press.

Lim EJ, Fejer MM and Byer RL (1989) Second-harmonic generation green light in periodically poled planar lithium niobate waveguide. *Electronic Letters* 25: 174.

Lim EJ, Fejer MM, Byer RL and Kozovsky WJ (1989) *Electronic Letters* 25: 731–732.

Myers LE and Bosenberg WR (1997) Periodically poled lithium niobate and quasi phase matcher parametric oscillators. *IEEE Journal of Quantum Electronics* 33: 1663–1672.

Newell AC and Moloney JV (1992) *Nonlinear Optics*. Redwood City, CA: Addison Wesley Publishing Co.

Rapp L (1997) Experimental investigation of signal distortions induced by cross phase modulation combined with dispersion. *IEEE Photon Technical Letters* 9: 1592–1595.

Shen YR (1989) *Principles of Nonlinear Optics*. New York: Wiley.

Shtaif M, Eiselt M and Garret LD (2000) Cross-phase modulation distortion measurements in multispan WDM systems. *IEEE Photon Technical Letters* 12: 88–90.

Tkach RW, Chraplyvy AR, Forghiari F, Gnanck AH and Derosier RM (1995) Four-photon mixing and high speed WDM systems. *Journal of Lightwave Technology* 13: 841–849.

Wang QZ, Lim QD, Lim DH and Alfano R (1994) High resolution spectra of self phase modulation in optical fibers. *Journal of Optical Society of America* B-11: 1084.

Webjorn J, Siala S, Nan DW, Waarts RG and Lang RJ (1997) Visible laser sources based frequency doubling in nonlinear waveguides. *IEEE Journal of Quantum Electronics* 33: 1673–1686.

Yamada M, Nada N, Saitoh M and Watanabe K (1993) *Applied Physics Letters* 62: 435–436.

Yamada E, Takara H, Ohara T, Sato K, Morioka T, Jinguji K, Itoh M and Ishi M (2001) A high SNR, 150 Ch. Supercontinuum CW optical source with high SNR and precise 25 GHz spacing for 10 Gbit/s DWDM systems. *Electronics Letters* 37: 304–306.

Yariv A (1997) *Optical Electronics in Modern Communications*, 5th ed. New York: Oxford University Press.

Optical Fiber Cables

G Galliano, Telecom Italia Lab, Torino, Italy

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In order to be put to practical use in the telecommunication network, optical fibers must be protected from environmental and mechanical stresses which can change their transmission characteristics and reliability.

The fibers, during manufacturing, are individually protected with a thin plastic layer (extruded during the drawing) to preserve directly their characteristics from damage due to the environment and handling. This coating surrounding the fiber cladding (with an external diameter of 125 μm) is known as the primary coating, which is obtained with a double layer of UV resin for a maximum external diameter of about 250 μm.

Primary coated fiber, at the end of the manufacturing process, is subjected to a dynamic traction test (proof-test) to monitor its mechanical strength. This test, carried out on all fibers manufactured, consists of the application of a well-defined strain (from 0.5% to 1%) for a fixed time (normally 1 s) and thus permits the exclusion of, from successive cabling, those fibers with poor mechanical characteristics.

At the end of the manufacturing process the optical fibers are not directly usable. It is necessary to surround the single fiber (or groups of fibers) with a structure which provides protection from mechanical and chemical hazards and allows for stresses that may be applied during cable manufacture, installation, and service.

Suitable protection is provided using fiber conditioning within the cable (secondary coating or loose cabling), while entire protection is obtained with some cable elements, such as strength members, core assembling, filling, and outer protections. Moreover, the cable structure and its design is heavily influenced by the application (e.g., number of fibers), installation (laying and splicing), and environmental conditions of service (underground, aerial, or submarine).

In this article, the main characteristics of optical cables (with both multimode or single mode fibers) are described and analyzed, together with suitable solutions.

Secondary Fiber Coating

The fiber, before cabling, can be protected with a secondary coating (a tight jacketing) to preserve it during cable stranding. However, fiber with only a primary coating may be cabled with a suitable cable protection.

In the first case the fiber can be directly stranded to form a cable core; in the second case, a single group of fibers must be inserted into a loose structure (tubes or grooves) with a proper extra-length. These two solutions are not always distinguishable; in fact, tight fibers inserted into loose tubes or grooves are often used.

The implementation of the secondary coating and the choice of proper materials requires particular attention, in order to avoid microbending effects on the fiber, which can cause degradation of the transmission characteristics. Microbending is caused by the pressure of the fiber on a microrough surface, or by the fiber buckling, due to the contraction of the structure (e.g., secondary coating) containing it. Microbending causes an increase in fiber attenuation at long wavelengths (1300 and 1550 nm) for both single and multimode fibers, but is particularly emphasized in multimode fibers.

Tight Jacket

In a tight protection, the primary coating fiber is surrounded by a second plastic jacket in contact with the fiber. This jacket mainly protects the fiber from lateral stresses that can cause the microbending.

The fiber can be individually protected with a single or double layer of plastic material or in a ribbon structure. In Figure 1 four different types of tight jacket are shown. In Figure 1a and b the fibers are singularly protected with a single or double layer up to an external diameter of 0.9 mm. The second type is normally preferred because the external hard plastic gives a good fiber protection and the inner soft plastic avoids microbending effects on the fiber.

In a ribbon structure, from 4 to 16 primary coated fibers are laid close and parallel and covered with plastic. Two types of ribbon are normally classified ‘encapsulated’ (Figure 1c) or ‘edge bonded’ (Figure 1d). In the first case, the fibers are assembled with a common secondary coating (one or two layers), in the second case, an adhesive is used to stick together the fibers with only the primary coating.



Figure 1 Different types of tight coatings.

Care should be taken in applying tight protection, in particular for a ribbon structure, to avoid an attenuation increase due to the action of the jacket on the fiber (in particular for the thermal contraction of the coating materials). The ribbon structure is designed to permit the simultaneous junction of multiple fibers; for this reason the ribbon geometry must be precision controlled.

Loose Jacket

In a loose protection the fiber can be inserted into a cable with only the primary coating. A thin layer of colored plastic may be added onto the primary coating to identify the fiber in the cable. The fibers are arranged in a tube or in a groove on a plastic core (slotted core). The diameter of the tube or the dimension of the core must be far larger than the diameter of the fiber so that the fiber is completely free inside the structure. The fibers can be inserted into a tube or into a slotted core, singularly or in groups. The space inside the tube around the fibers can be empty or filled with a suitable jelly. Some examples of loose structures are shown in Figure 2. In the tube structure, the external diameter of the jacket depends on the number of the fibers: for a single fiber up to 2 mm (Figure 2a), and for a multifiber tube (Figure 2b) up to 3 mm (for 10 fibers).

Examples of slotted core structures are shown in Figure 2c and d, respectively, for one fiber and for a group of fibers, the dimensions of grooves depending on the number of fibers.

Plastic materials with a high Young modulus are normally used for the tube that is extruded on the single or on the group of fibers. Instead, for the slotted core, plastic materials with good extrusion are used to obtain a precise profile of the grooves.

The loose structure guarantees freedom to the fibers in a defined interval of elongation and compression. Out of this interval, microbending effects can arise which increase fiber attenuation. Axial compression generally occurs when the cable is subjected to low temperatures and is generated from the thermal contraction of the cable materials that is different from that of the fibers. Axial elongation normally occurs when the cable is pulled or by the effects of high temperature.

For a correct design of a cable with a loose structure, the extra length of the fiber with respect to the tube or groove dimension and the stranding pitch must be evaluated, starting from the range of axial compression and elongation. In fact, care must be taken to prevent the fiber from being strained or forced against the tube or groove walls in the designed range.

For the tube solution, the extra length of the fibers is controlled during the tube extrusion; for the slotted core solution, the length is controlled during cabling, giving a controlled tension to the slotted core. The loose structure is often used for the cabling of fibers with tight jacketing, joining the advantages of the tight protection and loose cable. This solution is typical for ribbon cables.

Fiber Identification

To identify the fibers in a cable, a proper coloration with defined color codes must be given to the single fibers. In the tight protection, the tight buffer is directly colored during extrusion. In the loose protection, a thin colored layer is added on the primary coating of the fiber; tubes or slotted core may



Figure 2 Different types of loose coatings.

be also colored to identify groups of fibers in high potentiality cables.

Cable Components

The fundamental components of an optical cable are: the cable core with the optical fibers, the strength member (one or more) which provide the mechanical strength of the cable, sheaths which provide the external protection, and filling materials.

Cable Core

The optical fibers with the secondary coating (tight or loose) are rejoined together in a cable core. For tight fibers or loose tubes, the cable core is obtained by stranding the fibers or the tubes around central elements that normally act as strength members too (see below).

The stranding pitch must be long enough to avoid excessive bending of the fibers and short enough to guarantee stress apportionment among the fibers in cable bends and maximum elongation of the cable without fiber strain. Normally, a helical stranding is used, but often SO stranding, that consists in an inversion of stranding direction every three of more turns, is employed. The second stranding type makes the cabling easier but may reduce its performance.

The unit core or the slotted core are made of plastic and normally incorporate a central strength member.

Strength Member

The strength member may be defined as an element that provides the mechanical strength of the cable, to withstand elongation and contraction during the installation and to ensure thermal stability. Fiber elongation, when the cable is pulled or the fiber compressed due to low temperatures, depends greatly on the characteristics of the strength member inserted in the cable.



Figure 3 Different locations of the strength member in an optical cable.

As the maximum elongation values suggested for the fibers are in the range from 20 to 30% of the proof-test value, the maximum elongation allowed for a tight cable is ~0.1% instead of ~0.3% for a loose cable. To warrant these performances, a material with a high Young modulus is normally used as a strength member. Also, the strength member must be light (to avoid excessive cable weight) and flexible: these properties make it easier when laying the cable in ducts.

The strength member may be metallic or non-metallic and may be inserted in the core (Figure 3a) or in the outer part of the cable (Figure 3b), normally under the external sheath. Often two strength members are placed in an optical cable: the first one in the core and the second one under the sheath (Figure 3c).

Metallic strength members, generally one or more wires of steel, are inserted in the center or in the outer part of the cable. The steel, for its low thermal expansion coefficient and high Young modulus, behaves as a good strength member, particularly when it is arranged in the central core. Steel is a nonexpensive material, but needs protection against corrosion and electrical-induced voltages, such as by lightning or current flow in the ground.

If cables with high flexibility are requested, steel is not suitable and aramid fiber yarn or glass-fiber reinforced plastic (G-FRP) are used, particularly when the strength member is placed in the outer part of the cable. Glass fiber elements are generally used as a compressive strength member in the central cable core to avoid contraction at low temperatures, but they may be used as strength elements when the traction strength is low.

Aramid yarns are not active as resisting compression elements but are normally arranged in the outer part of the optical cable. Aramid yarns have a high Young modulus (as with steel) and low specific weight: in commercial form they consist of a large number of filaments gathered into a layer. Normally two layers stranded in opposite directions are used to avoid cable torsion during the installation.

Metal-free cables are protected by G-FRP and aramid yarns. This solution results in optical cables which are insensitive to electrical interferences.

Sheaths

The functions of the sheaths are to protect an optical cable during its life, in particular from mechanical and environmental stresses. During the installation or when the cable is in service, it may be subjected to mechanical stresses, for example, presence of humidity or water and chemical agents. The sheaths act as a barrier to avoid degradations of the fibers in the internal cable core.

The plastic sheaths (one or more, depending on the cable type and structure) are extruded over the core. This extrusion is a delicate operation in cable manufacturing because the cable core may be subjected to tension, while during the cooling the thermal compression of the plastic produces a stress on all the cable elements. Examples of cable sheaths are shown in Figure 4.

Different plastic materials, such as polyvinylchloride (PVC), polyethylene, and polyurethane are normally used. PVC has excellent mechanical properties, flexibility, and is flame retardant but is permeable to humidity. On the other hand, high-density polyethylene has a permeability lower than PVC, with good mechanical properties and low coefficient of friction, but it is more flammable than PVC and less flexible. Finally, polyurethane, for its softness and high flexibility, is often used for inner sheaths. When low toxicity is requested (e.g., in indoor cables), halogen-free materials are employed.



Figure 4 Examples of optical cable sheaths.

Often a metallic barrier is used under the external sheath to prevent moisture entering the cable core. The type most widely used is an aluminum ribbon (of a few tenths of a millimeter) bonded into the external polyethylene sheath, during the sheath extrusion. This structure is normally indicated as a LAP (laminated aluminum polyethylene) sheath.

When the cable is directly buried, a metallic armor (corrugated steel tape or armoring wires) is generally inserted. The metallic armor protects the cable core against radial stresses but it is also used as protection against rodents and insects.

Filling Compounds and Other Components

Fillings are used in optical cables to avoid the presence of moisture and water propagation in the cable core should a failure occur in the cable sheath. Suitable jelly compounds, with constant viscosity at a wide range of temperatures and chemical stabilities, are generally inserted in the cable core and, sometimes, in the outer protection layer. In loose structures, the jelly is in direct contact with the fibers: the compound must be compatible with them and guarantee the fiber freedom. Special compounds may be used to adsorb and permanently fix any hydrogen present in the cable core. The presence of hydrogen gas, that may be generated from the internal materials of the cable (mainly metals), is harmful to the fibers because it causes permanent attenuation increases and thus damage to them.

With the generic terminology ‘other components’, some other components used in the optical cables are included. They are often similar to those used in conventional cables. The most important are: insulated conductors, plastic fillers, and cushion layers and tapes around the fiber core.

Insulated copper conductors may be incorporated in the cable core, for example, to carry power supply or as service channels, or to detect the presence of moisture in the cable (in this case, the insulation is missing or partial). The conductors may cause problems due to the voltages induced by power lines or lighting.

Plastic fillers are often used to complete the cable core geometry. Cushion layers are used to protect the cable core against radial compression. Normally, they are based on plastic materials wound around the core. Tapes are wound around the cable core to hold the assemblies together and secondly to provide a heat barrier during the sheath extrusion. Mylar tapes are usually employed.

Optical Cable Structures, Types, and Applications

Cable Structures

The structure of an optical cable is strictly dependent on the construction method and the application type that determines the design and the grade of external protection. The main core (or inner) structures of an optical cable can be classified as: stranded structures (tight and loose); slotted core cable; or ribbon cable. In this section, a few examples of cable structures are presented. Below, separate sections are devoted to submarine cables and to special application cables, for their particular structures and features.

In the stranded tight structure, a low number of tight or loose fibers is stranded around a strength member to form a cable unit. Some of this cable unit may be joined to constitute a cable with a medium/high number of fibers (Figure 5a). Alternatively the fibers may be arranged in a multilayer structure (Figure 5b).

The main advantages of a tight stranded structure are the small dimensions of the cable core, even when a large number of fibers are involved, and also the facility of handling. Care must be taken in the design of the strength member: in fact, the fibers are immediately subjected to tension when the cable is pulled into the ducts or compressed when subjected to low temperatures.

In the stranded loose structures, two categories of cables are defined, one fiber per tube and a group of fibers (up to 20) per tube (Figure 5c). As already mentioned, in the loose structures, the fibers are free inside the tube and for this reason the cable is less critical than the tight cable. The external dimensions of loose cables are larger than tight cables, but the solution with multiform tubes allows for cables with a high number of fibers in relatively small dimensions.

Slotted core cables (Figure 2c,d) contain fibers with only the primary coating and may be divided, as in the stranded loose structure, into one fiber per groove or into a group of fibers per groove. The cable design and the choice of a suitable plastic material for the slotted core joined to a proper strength member, make it possible to obtain cables with fiber stability at a wide range of temperature. As in the loose stranded solutions, the slotted core solution is adopted to obtain cables with a high number of fibers in small dimensions.

In the ribbon solution, the fibers (from 4 to 16) are placed in a linear ribbon array. Many ribbons are stacked together to constitute the optical unit. The ribbon cable normally has a loose structure (loose tube or slotted core). Three structures are shown in Figure 6. In the first example (classical AT & T cable), 12 ribbons of 12 fibers are directly stacked and stranded in a tube (Figure 6a). In the second and third examples, ribbons are inserted into tubes or grooves (Figure 6b,c). Several tubes or slotted cores can be assembled together to give a cable with very high fiber density. The ribbon approach may be efficient when a large number of fibers must be



Figure 5 Structures of stranded core cables.



Figure 6 Structures of ribbon cables.

simultaneously handled, spliced, and terminated at connectors.

Types and Applications

The choice of an optical cable is heavily established by many factors, but mainly on the type of installation. On this basis, some different typology of cables may be identified: aerial cables, duct cables, direct buried cables, indoor cables, underwater cables, etc.

Aerial cables can be clasped onto a metal strand or can be self supporting. In the first case, the cable is not subjected to a particular tension but requires good thermal and mechanical performances. This solution is chosen when the cable must withstand strong ice and wind and when long distances between the poles are required. All the structures mentioned above may be adopted. In the second case, the cable is normally exposed to high mechanical stresses during its life and high tensile strength must be guaranted to maintain the fiber elongation at a safety level. Generally, loose structures are preferred for their greater fiber freedom. Often, in self-supporting cables, the strength member is external to the cable core. An example is shown in Figure 7.

Cables pulled in ducts must be resistant to pulling and torsion forces, and light and flexible to permit the installation of long sections. The cable must also protect the fibers against water and moisture that may be present in ducts or manholes. Usually the cable is filled with a jelly compound, a metallic barrier is normally used and, often, an armoring is added when protection against rodents is necessary. All the structures described above may be employed in duct cables.

The characteristics of direct buried cables are very similar to those of duct cables, but additional protections, such as metallic armoring, are required to avoid the risk of damages from digging and other earthmoving work.



Figure 7 Self-supporting aerial cable.

Cables for indoor applications normally require a smaller number of fibers. Their main characteristics are: small dimensions, flexibility, small curvature radius, and ease in handling and jointing. For indoor applications, the sheath must not permit flame propagation and must have a low emission of toxic gases and dark smoke. Tight cables are preferably used for indoor applications due to their compactness and small dimensions.

Underwater cables are employed in the crossing of rivers, in lakes and lagoons, and for shallow water applications in general. Such cables must have stringent requirements such as resistance to moisture and water penetration and propagation, pulling resistance (during the installation, and recovery in event of failure), and high resistance to static pressure and core structure compatible with land cables (when it is part of a ground link). In addition, due to the presence of metallic structures, attention should be paid to hydrogen effects.

Submarine Cables

Submarine cable is manufactured for laying in deep-sea conditions. In designing a submarine cable, it is necessary to provide high reliability that the mechanical and transmission characteristics of the optical fibers will be stable over a long period of time. Different cables are used for submarine applications, but generally follow the basic scheme of Figure 8.

The central core (with a few fibers – up to 12 – in a slotted core or in a tight structure) is surrounded by a double layer of steel wires that act as strength members against tensile action and water pressure. Metal pipes at the inner or outer sides of the strength member, act as a water barrier and as power supply conductors (for the supply of the undersea regenerators).

The outer polyethylene insulating sheath is the ultimate protection for the ordinary deep-sea cable. For cables requiring special protection, steel wire armoring (anti-attack from fishes), and further polyethylene are added.

The cable must have stringent mechanical requirements, such as resistance to traction, torsion, crushing, impact, and to shark attack. The cable must be suitable for installation using standard cable-laying ships. Furthermore the cable materials must have low content of hydrogen and emissions. If necessary, a hydrogen absorber may be included in the cable core.

Special Cables

This category comprises cables not specifically used in ordinary telecommunication networks, but cables used for specific applications and according to specified requirements. Cables for military use are normally employed for temporary plant restoration. They must be light but crush resistant and with good mechanical characteristics. Cables for mobile applications (robots, elevators, aircrafts, submarines, etc.) generally require high flexibility and tensile strength. Special cables may be installed in particular environments, where they must be insensitive, for instance, to nuclear radiation, chemical agents, and high temperatures.

Optical cables can be installed in power lines, together with the power conductors, or into the ground wires of high-voltage overhead power lines. In this last type of cable, the central stranded steel wire, making up the ground wire, is replaced with a metal tube containing the optical unit (normally a small groups of optical fibers inserted in a tube or in a slotted core).

Blown Fiber

This technology consists of the installation of a single fiber or of small fiber bundles (or cables) into pre-installed tubes or ducts using a flux of compressed air. Initially, cables with empty tubes are installed and successively, at the time of need, the tubes can be filled by blowing fibers (singly, or in bundles) or cables. The installation time is normally fast; some compressors can blow tens of meters in a minute. The typical maximum blowing distance is about 1 km for horizontal planes, but it is reduced



Figure 8 Basic structure of a submarine cable.

along winding roads. The advantage of this technique is to produce variable and flexible structures, increasing the number of fibers to fit the network need. Besides, substitutions or change of fibers can be quickly carried out without substitution of the cable.

See also

Fiber and Guided Wave Optics: Dispersion. **Light Emitting Diodes**.

Further Reading

Griffioen W (1989) The installation of conventional fiber-optic cables in conduits using the viscous flow of air. *Journal of Lightwave Technology* 7(2): 297–302.

Hughes H (1997) *Telecommunications Cables. Design, Manufacture and Installation.* : John Wiley and Sons.

Keiser G (1986) *Optical Fiber Communications*. McGraw-Hill.

Murata H (1988) *Handbook of Optical Fibers and Cables*. Marcel Dekker.

Technical Staff of CSELT (1990) *Fiber Optic Communications Handbook Second Edition.* : TAB Books.

Passive Optical Components

D Suino, Telecom Italia Lab, Torino, Italy

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Modern telecommunications networks are based on fiber optics as signal transporters. In these networks the signals travel in the form of light confined within the fibers. As light power travels through the fibers from the source apparatus to the receiver, a number of components are employed to manage the optical signal. All other components that are not used to manage the signal are called ‘passive optical components’. They serve several functions, such as to join two different fibers to distribute the signal onto more optical branches to limit the optical power to select particular wavelengths, and so on.

These components can be located anywhere in the network, depending on their function and on the network architecture. However, their main location is near the apparatus in which it is necessary to manage the signal before it is sent through the network or at the junction in the network where it is sent on to the receiver.

The main types of passive components that are found in a network can be grouped as follows:

- Joint devices:
  - Optical connectors;
  - Mechanical splices.
- Branching devices:
  - Nonwavelength-selective branching devices;
  - WDM.
- Attenuators;
- Filters;
- Isolators;
- Circulators.

Optical fibers are also divided into several groups (multimode 50/125, multimode 62.5/125, singlemode, dispersion shifted, NZD, and so on). There are also components of different typology that match up with each particular fiber. However, the general concept in terms of functionality, technology, and characteristic parameters, are the same among passive optical components of the same type (connectors, branching devices, or attenuators) but of different groups (single-mode, multimode, etc.).

Optical Joint Devices

The function of an optical joint is to perform a junction between two fibers, giving optical continuity to the line. Two different classes of joint can be considered: the connectors and the splices. The joints made by using connectors, are flexible points in the network, which means they can be opened and reconnected several times in order, for example, to reconfigure the network plan. However, a splice is a fixed joint and usually cannot be opened and remated. There are two type of splice: mechanical splices, holding joints to fibers by glue or mechanical crimp, and fusion splices fusing the two fiber heads with a suitable fusion splicer.

General Considerations

Considering that fibers can be described as pipes, in the core of which flows light, continuity between two fibers means that the two cores must be aligned in a stable and accurate way. Obviously this alignment must be carried out with minimum power loss in the junction. The main factors that affect the power loss in a joint point between two fibers are:

- x = Lateral offset;
- z = Longitudinal offset;
- θ = Angular misalignment; and
- w_T/w_R = Mode field diameter ratio (in the single mode fiber) or numerical aperture ratio (in the multimode fiber).

These geometrical mismatching between the two fibers is represented in Figure 1.

The function that describes the joint attenuation is different for single-mode and multimode connectors, but the parameters that contribute to it are the same. The general formulation for these functions are complicated and, in particular, for the multimode connector it involves an integral on the shape distribution of the light in the fiber core. These functions become simpler in particular conditions: for example, if we consider a single-mode joint without a gap between the two fibers (that is the more usual condition in the modern connectors) the z parameter is nil, and in this case the function that describes the attenuation of the connector is

$$A(dB) = -10 \log\left\{\left(\frac{2w_T w_R}{w_T^2 + w_R^2}\right)^2 \times \exp\left[-2\,\frac{(x\lambda)^2 + (\pi n w_T w_R \sin(\vartheta))^2}{\lambda^2(w_T^2 + w_R^2)}\right]\right\} \qquad [1]$$

where n is the fiber core refractive index and λ is the wavelength of the light.



Figure 1 Main parameter that affects the joint power loss.

Figure 2 shows the trend of eqn [1], where the parameter ranges in the graphs are typical for the most common products on the market. It is evident that the main contribution to attenuation arises from the lateral offset.

For connectors of good quality, both for single-mode and multimode fibers, the attenuation values are in the range of a few tenths of dB (typically less than 0.3 dB). Another important factor for a joint, in particular for connectors used in networks for high speed or analog signals, is the return loss (RL). This is a parameter that gives a measure of the quantity of light back-reflected onto the optical discontinuity of the connector, due to the Fresnel effect. The RL is defined as the ratio in dB between the incident light power (P_{inc}) and the reflected light power (P_{ref}):

$$\text{RL} = -10 \log\left(\frac{P_{\text{ref}}}{P_{\text{inc}}}\right) \qquad [2]$$

Fresnel reflection arises when the light passes between two media with different refractive indices. In the case of connectors in which the two fibers are not in contact, the light passes from the silica of the fiber



Figure 2 Single mode connector attenuation as a function of the geometrical parameters. Each curve is plotted keeping the other parameter constant.

core to the air in the gap. This causes the reflection of 4% of the incident light that, as RL, is about 14 dB.

To improve the RL performances of an optical joint, it is necessary to reduce the refractive index difference. This can be achieved either by index matching material between the two fibers that reduces the differences between the refractive index of the fiber and the gap, or by performing a physical contact between the fiber heads. The first technique is typically used in mechanical splices but, due to the problem related with the pollution contamination of the index matching, it is not a good solution for connectors that are to be opened and reconnected several times.

The physical contact solution is the most frequently adopted for these connectors. Physical contact is obtained by polishing the ferrule and the fiber end-faces in a convex shape, with the fiber core positioned in the apex (Figure 3). With this technique, the typical values of return loss for a single mode connector are in the range from 35 dB to 55 dB, depending on the polishing grade. The residual back-reflected light is generated in the thin layer of the fiber end surface, because of slight changes in the refractive index due to the polishing process.

Higher return loss values (small quantity of reflected light) are achieved with the angled physical contact (APC) technique. This is obtained by polishing the convex ferrule end face angled with respect to the fiber axis. In this way, the light is not back reflected into the fiber core, but into the cladding, and is thus eliminated (Figure 4). In APC connectors, typical return loss values are greater than 60 dB.



Figure 3 Back reflection effects in PC connectors.



Figure 4 Back reflection effects in APC connectors.

Optical Connectors

On the market are several types of optical connectors. It is possible to divide them into three main groups:

- Connectors with direct alignment of bare fiber;
- Connectors with alignment by means of a ferrule; and
- Multifiber connectors.

Connectors with direct alignment of bare fiber

In this type of connector the bare fibers are aligned on an external structure that is usually a V-groove (Figure 5). Two configurations can be performed: plug and socket or plug–adapter–plug. In the first case, the fiber in the socket is fixed and the one in the plug aligns to it. In the plug–adapter–plug configuration, two identical plugs containing the bare fibers are locked onto an adapter in which the fibers are placed on the aligned structure. These connectors are cheaper than the connectors with a ferrule, (described below), but this is unreliable. In fact, the bare fibers are delicate and brittle and they can be affected by the external mechanical or environmental stresses.

Connectors with alignment by means ferrule

In this type of connector, the fibers are fixed in a secondary alignment structure, usually of cylindrical shape, called a ferrule. The fiber alignment is obtained by inserting the two ferrules containing the fibers into a sleeve. Usually this type of connector is in the plug–adapter–plug configuration (Figure 6). With this technique, the precision of the alignment is moved from the V-groove precision to the dimensional tolerance of the ferrule. Typical tolerance values on the parameters for a cylindrical ferrule with a diameter of 2.5 mm, are in the range of a tenth of a micrometer, and must be verified on the diameter, eccentricity between the hole (through which the fiber is fixed) and cylindricity of the external surface.

Multifiber connectors

In some types of optical cable, the fibers are organized in multiple structures, in which many fibers are glued together to form a ribbon. The ribbon can have



Figure 5 Scheme of the bare fibers alignment on a V-groove.



Figure 6 Scheme of a plug–adapter–plug connector with alignment by ferrules and sleeve.

2, 4, 8, 12, or 16 fibers, for example. When these cables are used, it is convenient to maintain the ribbon fiber structure in the connectors (until the point in which it is necessary to use the fibers singularly). Multifiber connectors are typically based on a secondary alignment on a plastic ferrule of rectangular shape in which the fibers maintain the same geometry that they have in the ribbon. The rectangular ferrules of the two plugs are normally aligned by means of two metallic pins placed in two hole in line with the fiber. In Figure 7, a scheme of a multifiber connector is shown.

Mechanical Splices

Mechanical splices are yet another way to join together two fibers. All the main considerations for the connectors are true for the mechanical splices. The difference is that the mechanical splice is a fixed joint and, normally, it cannot be opened and re-mated. Mechanical splices, both for single fiber and for multifiber structures, are the most usually manufactured. In a mechanical splice, the fibers are aligned directly in a V-groove and fixed by glue or a mechanical holder.

These components are cheaper than fusion splices but their optical, mechanical, and environmental functions are lower than the fusion splices. Figure 8, shows a mechanical splice for multifibers in which the fibers are crimped on a V-groove array. Usually, to avoid high optical reflection in the junction point, this type of joint is filled with index matching material.

Branching Devices

Branching devices are passive components devoted to distributing the optical power from an input fiber to two or more fibers. These components can be classified in two broad classes, on the basis of the wavelength dependence. The nonwavelength-selective branching devices, called also couplers or splitters, share the input power to two or more fibers independently from the light wavelength.



Figure 7 Multifiber connector.



Figure 8 Example of a multifiber mechanical splice.

The components that perform the light distribution on more fibers on the basis of the different wavelengths of the input light are called a WDM (wavelength division (de)multiplexer).

Branching devices have three or more ports, bare fiber or connectors, for the input and/or output of optical power, and share optical power among these ports. A generic branching device can be represented as a multiport device having N input ports and M output ports, as shown in the Figure 9.

The optical characteristics of a branching device can be represented by a square transfer matrix of $n \times n$ coefficients, where n is the total number of the component ports. Each coefficient t_{ij} in the matrix is the fractional optical power transferred among designated ports, that is the ratio of the optical power P_{ij} transferred out of port j with respect to input



Figure 9 Scheme of a generic N × M branching device.

power P_i into port i:

$$T = \begin{bmatrix} t_{11} & t_{12} & \cdots & t_{1n} \\ t_{21} & & & \\ \vdots & & t_{ij} & \vdots \\ & & \ddots & \\ t_{n1} & & & t_{nn} \end{bmatrix} \quad [3]$$

where:

$$t_{ij} = \frac{P_{ij}}{P_i} \quad [4]$$

So, according to the relationship between two ports, the coefficients represent several parameters. For example, if the port i is an input port and j is an output port, t_{ij} is the transferred power signal through the component, while if they exist as two isolated ports the coefficients represent the crosstalk between the two ports.

The three main techniques to obtain this type of component are:

(i) All fiber components;
(ii) Micro-optics; and
(iii) Integrated optics.

Nonwavelength-Selective Branching Devices

A nonwavelength-selective branching device is a component having three or more ports, which shares an input signal among the output ports in a predetermined fashion. Usually these components are completely reversible and so they also work as a combiner of signals from more input ports onto a single output port.

There are several types of couplers for different applications:

- Y-coupler with one input port and two output ports;
- X-coupler with two input ports and two output ports; and
- Star coupler with more than two ports in input and/or in output.



Figure 10 Scheme of a fusion 2 × 2 coupler.

Moreover the couplers can be symmetrical, and in this case they divide the input power light onto n equal output flows, or asymmetrical devices in which the quantity of power light in the output ports is shared in a predefined nonuniform way.

The techniques used to carry out this type of device are mainly the fusion technique or planar technique. The first one is based on the phenomenon of evanescent wave coupling: when the core of two optical guides (as fibers) are located in close proximity, a power exchange from a guide to another is possible. This configuration can be obtained by stretching the fibers under controlled fusion (see Figure 10).

The planar technique, that is the simpler integrated optic application, is based on the optical guides with appropriate shapes being placed directly onto a silicon wafer by means of lithographic processes (Figure 11).

The fusion technique has the advantage of being ‘all in fiber’ so the component is ready to be inserted into the optical networks by means of usual joint techniques. But for a high number of ports, the coupling ratio among the branches cannot be controlled in a precise way and the cost of the fusion device is proportional to the number of the branches. On the contrary, a device obtained with the planar technology must be coupled with fibers normally used and this operation may be difficult due to the different geometry of the planar guide (rectangular) and the fiber (circular). On the other hand, this technology allows a high precision in the optical characteristics of the component and the cost of the device is independent of the branch number.

WDM

A wavelength-selective branching device, usually called WDM (Wavelength Depending Multiplexer),


Doped layer
Silicon wafer
After photolithographic process
Doped optical guide
After cladding layer deposition
Cladding
Example of structures made in planar technique
1 x 8 coupler
8 x 8 star coupler

Figure 11 Scheme of the process to obtain a planar coupler and an example of a device.

is a component having three or more ports which shares an input signal among the output ports in a predetermined fashion, depending on the wavelength, so that at least two different wavelength ranges are nominally transferred between two different couples of ports.

WDM devices may be divided in three categories on the basis of the bandwidth of the channels (the spacing between two adjacent wavelength discriminated by the device):

(i) DWDM (Dense WDM) device operates for channel spacing equal or less than 1000 GHz (about 6–8 nm in the range of typical optical wavelength used in telecommunications systems, 1310 or 1550 nm);
(ii) CWDM (Coarse WDM) device operates for channel spacing less than 50 nm and greater than 1000 GHz; and
(iii) WWDM (Wide WDM) device operates for channel spacing equal or greater than 50 nm.

These components are used to combine, at the input side of an optical link in only one fiber, more optical signals with different wavelengths and separate them at the receiving end. This technology allows to send along a fiber, more communication channels, thus increasing the total bit rate transmitted. These types of components can be obtained using filters to select single a wavelength (as a diffractive grating that resolves the light into its monochromatic components) or using the phenomena of evanescent field coupling occurring between two adjacent fiber cores (as described for coupler devices), controlling in a precise way the coupling zone; this is, in fact, dependent on the wavelength (Figure 12).

Using wavelength filters, as they select a singular wavelength, it is necessary to perform a cascade filter structure for separating more than two wavelengths.


$\lambda_1 \cdots \lambda_n$
λ_1 Filter
$\lambda_2 \cdots \lambda_n$
λ_1
(a)
$\lambda_1 \cdots \lambda_n$
λ_1
λ_2
λ_3
λ_n
Diffractive device
(b)

Figure 12 (a) Scheme of the filter technique and (b) diffractive device technique.


Cladding
Zones with modified refractive index
d
Core
Optical fiber

Figure 13 Scheme of FBG.

Micro-optic technologies are generally used for multimode fiber due to the critical collimation problem. For the single-mode fiber the evanescent field coupling technique is applied directly to fiber or to planar optical guides.

Another efficient technique to create WDM devices is with a fiber Bragg grating (FBG) wavelength filter directly applied to the fiber. FBGs consist in periodic modulation (see Figure 13) of the refractive index along the core of the fiber, and they act as reflection filters.

During the fabrication process (see Figure 14) the core of the optical fiber is exposed to UV radiation, and this exposure increases the refractive index of the core in defined zones, with a periodic shape obtained by the interference fringe created by crossing two coherent beams.



Figure 14 Scheme of FBG production.



Figure 15 Transmission characteristic of FBG.

Figure 15 shows a representative spectral curve of a FBG filter centered at 1625 nm. The central wavelength, the width, and the value of reflection depend on the grating period (*d*) and on the deposited UV energy in the fiber core.

Other Passive Optical Components

In an optical network, besides the devices described above, there are a number of other passive optical components that perform particular functions on the optical signal; the main ones are:

Attenuators These are devices used to attenuate the optical power, for example, in front of a receiver when the optical line is short and the power of the received signal is still too high for the detector, or when it is necessary to equalize the signals arriving from different optical lines. It exists both in tunable and fixed versions. The first ones allow adjustment of the attenuation value, however, the second ones have a fixed and predefined value. The fixed optical attenuators can be obtained by inserting a filter or stressing a fiber in a controlled and permanent way. The tunable attenuators are based on variable optical parameters as, for example, the distance or the lateral offset in an optical connection. They exist both as connect lengths of fiber (attenuated optical jumpers) or as compact components similar to a double connector (plug stile attenuator).



Figure 16 Principle scheme of an optical circulator.

Filters These are components with two ports employed to select or to filter some fixed wavelengths. They can be divided into the following categories:

- short-wave pass (only wavelengths lower than or equal to a specified value are passed);
- long-wave pass (only wavelengths greater than or equal to a specified value are passed);
- band-pass (only an optical window is allowed); and
- notch (only an optical window is inhibited).

It is also possible to have a combination of the above categories. The optical filtering can be obtained by inserting one or more filtering devices (as interferential films) into a fiber or creating a filter directly on the fiber by the FBG described above.

Isolators These are nonreciprocal two-port optical device in which the light flows in the forward direction, and not in the reverse one. The isolators are used to suppress backward reflections along an optical fiber transmission line, while having minimum insertion loss in the forward direction. Fiber optic isolators are commonly used to avoid back reflections into laser diodes and optical amplifiers, which can make the laser and amplifiers oscillate unstably, and cause noise in the fiber optic transmission system.

Circulators These are passive components having three or more ports numbered sequentially $(1, 2, \ldots, n)$ through which optical power is transmitted nonreciprocally from port 1 to port 2,..., from port (i) to port $(i+1), \ldots$ and from port n to port 1 (Figure 16).

See also

Diffraction: Fresnel Diffraction. **Optical Communication Systems:** Wavelength Division Multiplexing.

Further Reading

Adam MJ (1981) *An Introduction to Optical Waveguides*. New York: John Wiley & Sons.

Blonder GE, *et al.* (1989) Glass waveguides on silicon for hybrid optical packaging. *IEEE Journal of Lightwave Technology* 7: 1530.

Digonnet M and Shaw HJ (1983) Wavelength multiplexing in single-mode fiber couplers. *Applied Optics* 22: 484.

Jeunhomme LB (1983) *Single-Mode Fiber Optics – Principles and Applications*. New York: Marcel Dekker.

Kashima N (1995) *Passive Optical Components for Optical Fiber Transmission*. Norwood, MA: Artech House.

Kashima N (1993) *Optical Transmission for the Subscriber Loop*. Norwood, MA: Artech House.

Miller CM (1986) *Optical Fiber Splices and Connectors – Theory and Methods*. New York: Marcel Dekker.

SC86B IEC (1999) *IEC 60874-1: Connectors for Optical Fibres and Cables – Part 1: Generic Specification*, 4th edn. Geneva: International Electrotechnical Commission.

SC86B IEC (1999) *IEC 61073-1: Optical Fibres and Cables – Mechanical Splices and Fusion Splice Protectors – Part 1: Generic Specification*, 3rd edn. Geneva: International Electrotechnical Commission.

SC86B IEC (1999) *IEC 60869-1: Fibre Optic Attenuators – Part 1: Generic Specification*, 3rd edn. Geneva: International Electrotechnical Commission.

SC86B IEC (2000) *IEC 60875-1: Non-wavelength Selective Fibre Optic Branching Devices – Part 1:Generic Specification*, 4th edn. Geneva: International Electrotechnical Commission.

SC86B IEC (2000) *IEC 62077-1: Fibre Optic Circulators – Part 1: Generic Specification*, 1st edn. Geneva: International Electrotechnical Commission.

SC86B IEC (2000) *IEC 61977-1 Ed. 1.0: Fibre Optic Filters – Generic Specification*, 1st edn. Geneva: International Electrotechnical Commission.

SC86B IEC (2000) *IEC 61202-1: Fibre Optic Isolators – Part 1: Generic Specification*, 1st edn. Geneva: International Electrotechnical Commission.

Technical Staff of CSELT (1990) *Fiber Optic Communications Handbook*, 2nd edn, TAB Books. New York: McGraw-Hill.

Yokohama I, *et al.* (1988) Novel mass-fabrication of fiber couplers using arrayed fiber ribbons. *Electronic Letters* 24: 1147.

FIBER GRATINGS

P S Westbrook, OFS Laboratories, Murray Hill, NJ, USA

B J Eggleton, University of Sydney, Sydney, NSW, Australia

© 2005, Elsevier Ltd. All Rights Reserved.

Fiber gratings are periodic index variations inscribed into the core of an optical fiber, and are important devices for manipulating fiber guided light. Since their first fabrication in the late 1970s, fiber grating use and manufacture has increased significantly and they are now employed commercially as optical filters, reflectors and taps in telecommunications systems, and as strain and temperature sensors in various industries. We review optical fibers and the fundamentals of fiber grating characteristics as well as fabrication. Finally we consider several of the major industrial and scientific applications of fiber gratings.

Fiber Modes

A fiber grating couples light between the modes of an optical fiber, and therefore a knowledge of these modes is essential to understanding the characteristics of fiber gratings. In what follows, we emphasize single-mode fibers used near 1550 nm because these are very important in most practical applications that use fiber gratings. A single-mode fiber can be viewed as a thin cylinder of silica with a central raised index region of small enough diameter so that only a single mode is guided through total internal reflection at the core boundary. The electric field (*E*-field) of the fundamental mode propagating in the core is described by a characteristic transverse *E*-field profile and a propagation constant k:

$$\begin{aligned} E &= E(r, \varphi)\mathrm{e}^{-\mathrm{i}(\omega t - kz)} \\ k &= 2\pi n_{\mathrm{eff}}/\lambda \end{aligned} \qquad [1]$$

Here r and φ are the radial and azimuthal directions, z is measured longitudinally along the fiber, ω is the radial frequency, and λ is the vacuum wavelength, and the *E*-field points in the same direction everywhere. As the second equation indicates, the fiber mode propagates in the fiber as though it has an effective refractive index n_{eff}.

The silica cladding acts to isolate the core mode from the outside, hence the core mode penetrates very little into the cladding. However, if the outer cladding surface allows total internal reflection, the cladding may also guide light. Such ‘cladding modes’ are also important in understanding fiber gratings, since the grating couples the core mode with the cladding modes. As shown in Figure 1, the cladding modes extend outside the core into the cladding region, and their effective index is therefore always less than that of the core mode. We also note that in the case when the outer coating of the fiber does not support total internal reflection, ‘leaky’ cladding modes result. In the limit that there is no reflection at the cladding boundary a continuum of ‘radiation modes’ results. Although these modes are not guided, they are exploited in a variety of applications and can be carefully tailored by a suitably designed fiber grating. Note that the radiation and cladding modes exist regardless of the presence of a grating; a grating simply couples power from the core mode to the cladding/radiation modes; the grating is typically only a small perturbation on the index profile of the waveguide and the corresponding mode fields.

Fiber Grating Theory

Fiber gratings are longitudinal periodic variations in the refractive index (or, more generally, the dielectric function) of the core and/or cladding of an optical fiber. The scattering from any grating may be understood simply by considering the scattering off each successive period and adding these contributions while taking the phase of the *E*-field into account. Figure 2 illustrates this analysis in the case of a fiber Bragg reflector. When the reflections from each period of the grating add constructively, a strong back-reflection results. This is known as Bragg reflection. The condition for Bragg reflection is given by:

$$\lambda_{\mathrm{Bragg}} 2 n_{\mathrm{eff}} = \Lambda_{\mathrm{grating}} \qquad [2]$$

Here λ_{Bragg} is the vacuum wavelength of the light (equivalent to its frequency, $\omega = 2\pi c/\lambda$), n_{eff} is the effective index of the mode, and $\Lambda_{\mathrm{grating}}$ is the period of the grating refractive index modulations. This Bragg reflection is evident in a narrow dip in the



Figure 1 Fiber modes. Refractive index profile of a step index, single-mode fiber (dashed line). Radial profiles of mode *E*-fields of the fundamental (LP01) core mode, guided within the raised index region defined by the core, and one of the many higher-order cladding modes guided by the outer, air–silica interface. Also shown is a fiber indicating the ray paths for core, cladding, and radiation modes.

transmission spectrum of the grating (see Figure 3a). The ability of a fiber grating to selectively reflect the core light at one wavelength is one of its most important practical properties since it can be used as a narrowband filter or reflector. As a fiber component, the fiber grating has the advantage of compactness and provides in-line wavelength filtering.



Figure 2 Bragg reflection. Each period of the grating reflects a small fraction of the incident light. When the period of the grating is adjusted so that these reflections add coherently, a strong Bragg reflection results and a narrow dip is observed in the transmission spectrum of the fiber (see **Figure 3a**). As shown in **Figures 3** and **4**, Bragg reflection can also occur into cladding modes.

The condition for Bragg reflection may be expressed more generally as a phase-matching condition. Phase matching refers to the condition when the phases of all the grating-scattered waves are the same and there is constructive interference. More specifically, this condition expresses the relationship between the spatial frequencies of the incident light, the scattered light, and the grating modulation, necessary for constructive interference in the scattered light. For a grating, the phase matching condition may be expressed in terms of the grating wavevector, $K_{\text{grating}} = 2\pi/\Lambda_{\text{grating}}$ and of the two mode propagation constants, k_{incident} and $k_{\text{scattered}}$ (defined in eqn [1])

$$k_{\text{incident}} - K_{\text{grating}} = k_{\text{scattered}} \qquad [3]$$

Using phase matching, we can understand the various transmission spectra that result from fiber



Figure 3 Phase matching. Fiber grating resonances occur when the phase matching condition is satisfied: $k_{\text{inc}} - K_{\text{grating}} = k_{\text{scat}}$. Propagation constants ($k = 2\pi n_{\text{eff}}/\lambda$) of the fiber modes are indicated as hash marks on the vertical line. The region indicates the regime of unguided radiation modes. The fiber grating is represented by its longitudinal spatial frequency (wavevector) $K_{\text{grating}} = 2\pi/\Lambda_{\text{grating}}$, where Λ_{grating} is the period of the grating. Assuming an incident forward-going core mode, the grating wavevector then phase matches to (a) counter-propagating core and cladding modes (fiber Bragg grating, FBG), (b) continuum of radiation modes, or (c) a copropagating cladding mode (long-period grating, LPG).

gratings. Figure 3 shows the transmission characteristic observed for core guided light in a single-mode fiber containing three different types of gratings: Bragg reflector, radiation mode coupler, and copropagating mode coupler. Each grating has a different type of phase matching condition. Figure 3 also depicts the phase matching condition in eqn [3] graphically. The vertical line contains a mark representing the propagation constants, k, of modes of a single mode fiber (both positive and negative for the two propagation directions) and a solid black region representing the radiation mode continuum. Bragg reflection into backward-propagating core and cladding modes occurs for short grating periods ($K_{\text{grating}} \sim 2k_{\text{core}}$). Such gratings are known as fiber Bragg gratings (FBGs) and a typical transmission spectrum with a strong Bragg reflection and several cladding mode resonances is shown in Figure 3a (a typical Bragg reflection spectrum is shown in Figure 8 below; the FBG grating period was ~500 nm). Core-cladding mode reflection results in loss resonances for wavelengths shorter than the core–core Bragg reflection. When the grating period is very long (in general, $K_{\text{grating}} < k_{\text{core}}(n_{\text{cladding}} - 1)/n_{\text{cladding}}$; typically Λ_{grating} is ~1000 times that of an FBG), phase matching to copropagating cladding modes occurs. Such gratings are known as long-period gratings (LPGs). A typical LPG spectrum is shown in Figure 3c. The LPG resonance corresponds to coupling between the core mode and a single copropagating cladding mode. For wavevectors in between these two regimes, coupling to the continuum of radiation modes is possible. An example of such a grating spectrum is shown in Figure 3b. We note that fiber cladding modes can be either well guided (resulting in the sharp grating resonances of Figure 3a) or poorly guided (resulting in a broad continuum of Figure 3b) depending on the fiber surface. The radiation mode approximation is valid in the limit that the cladding mode is very poorly guided (i.e., has high loss) within the grating region.

While phase matching yields the resonance wavelengths of a fiber grating, the strengths of these resonances must be derived from a full solution of Maxwell's equations. The most common approximation used in these calculations is known as coupled mode theory (CMT). In CMT, the longitudinal refractive index variation is assumed to be a small perturbation to the waveguide modes, which results only in a change in the propagation constant of the modes but does not change the transverse dependence of the mode E-fields (see eqn [1]). CMT then assumes that the E-field amplitude of each mode varies slowly (compared to wavelength) along the grating. A pair of coupled equations relating the two mode amplitudes as a function of position along the grating can then be derived, and these allow for computation of the grating reflection and transmission. The coupling between two modes is determined by an overlap integral κ_{12} between the product of the E-fields of the two modes (E_1 and E_2) and the periodic refractive index variation:

$$\kappa_{12} \propto \iint_{\text{Area}} E_1(r,\phi)E_2(r,\phi)\delta n(r,\phi)\,\mathrm{d}A \qquad [4]$$

where $\delta n(r,\phi)$ is derived from the refractive index modulation:

$$\delta n(r,\phi,z) = \delta n(r,\phi)\cos(K_{\text{grating}}z) \qquad [5]$$

This overlap integral is useful because it allows for a rough comparison of the strength of resonances for different modes without the need to obtain a full CMT solution. In the simple case of Bragg reflection of the core mode in a standard single-mode fiber (see Figure 1):

$$\kappa = \frac{\pi \delta n \eta}{\lambda}, \qquad [6]$$

where $\eta \approx 0.8$ is the overlap integral of the core mode intensity with the core.

To understand fiber grating spectra we first discuss a 'uniform' Bragg grating, of length L. Such a grating has uniform index modulation along its length and is shown in Figure 4a. Depending on the length and refractive index modulation of the grating, it may be classified as either weak or strong. The division between these two regimes may be understood by considering the light scattered by each successive period of the grating. The fraction of light scattered from each period can be approximated by $\delta n/2n$ using the Snell's law reflectance formula. The boundary between a strong and a weak grating occurs when the grating is either long enough or strong enough that the sum of the scattering from all periods is of order 1. This division may also be expressed in terms of κ and L: $\kappa L \sim 1$.

In the weak limit, the incident light propagates through the grating with very little scattering. In this case, both the LPG and FBG resonances have transmission spectra that are approximately related to the Fourier transform of the grating index profile. (For LPGs, this may not hold if modal dispersion is large; see the discussion below.) In the case of a uniform grating profile, this results in a $1 - \text{sinc}^2$ wavelength dependence of the transmission spectrum and a spectral width $\delta\lambda/\lambda \sim \Lambda_{\text{grating}}/L = 1/N_{\text{periods}}$ as shown in Figure 4a. An important feature of the uniform grating is the side lobes. The side lobes result from the sudden 'turn on' of the grating. In the FBG,



Figure 4 Fiber Bragg grating refractive index profiles and spectra. (a) A uniform profile with transmission spectra for both strong and weak index modulations. (b) An 'unapodized' Gaussian grating profile showing Fabry–Perot-like structure within the grating resonance. (c) A '100% dc apodized' Gaussian grating profile showing a symmetric transmission spectrum. (d) A superstructure grating exhibiting four resonance peaks.

they can be understood as resonances of the effective Fabry–Perot cavity defined by the sharp grating boundaries.

In the strong limit, a substantial fraction of light is scattered out of the incident mode, and the FBG and LPG transmission spectra become different. As shown in Figure 4a, the FBG spectrum widens to a width determined only by δn: $\delta\lambda/\lambda = \delta n/n$. The incident light penetrates only a short distance ($\sim \lambda/\delta n$) into the grating before being completely reflected. The strong LPG, on the other hand, becomes 'overcoupled' as the second mode is reconverted into the incident mode. The result is a higher transmission for the incident core mode (provided that the scattered mode propagates without loss).

While uniform gratings are easy to model and manufacture, most practical fiber gratings have a nonuniform profile. In a nonuniform grating profile, both the refractive index modulation amplitude, $\delta n_{\text{AC}}(z)$, and the average effective index value, $\delta n_{\text{DC}}(z)$, may vary along the fiber grating length:

$$\delta n(z) = \delta n_{\text{DC}}(z) + \delta n_{\text{AC}}(z)\cos(K_{\text{grating}}z) \qquad [7]$$

By controlling the ac and dc index change, a greatly improved filter may be fabricated. Figure 4b shows the index profile and the grating transmission spectrum of a fiber Bragg grating with an 'unapodized' Gaussian profile. Note that due to the smooth increase in modulation amplitude, the sidebands of the uniform grating have been eliminated. However, because the dc index (and hence Bragg condition) is not constant within the grating, sharp resonant structure is observed within the grating resonance. This structure can be understood as Fabry–Perot resonances in the cavity formed by the nonuniform Bragg condition within the grating. Figure 4c shows a grating with a '100% dc apodized' Gaussian profile. This grating has a constant dc refractive index within the grating and therefore the resonance is smooth and symmetric. Most useful bandpass filters require a profile close to 100% apodization. Although not shown in Figure 4, a smoothly varying index profile also eliminates the sidelobes in LPG resonances.

Other important types of nonuniform fiber gratings include chirped fiber gratings and superstructure fiber gratings. In a chirped fiber grating the grating period slowly changes along the length of the grating. As discussed below, chirped fiber gratings may be used as chromatic dispersion compensators. They may also be used as broadband reflectors. LPGs may also be chirped to produce a broadband response. Superstructure gratings have oscillations in the period and/or amplitude of the refractive index modulations. The resulting grating can have several resonance peaks (see Figure 4d). The properties of nonuniform gratings may be computed using CMT and also understood intuitively using 'band-diagrams' and an effective index model of the fiber grating response.

Grating spectra showing radiation mode coupling are unlike FBGs or LPGs because there is no conversion of the radiation modes back to the incident core mode. The sharp resonances smooth out into a broad continuum. The grating transmission spectrum depends less on the refractive index profile of the grating than on the overlap of the core mode and grating with the radiation modes. Radiation mode coupling is greatly affected by tilting the grating planes with respect to the axis of the fiber. As discussed below, such tilted gratings may be designed as loss filters and optical fiber taps. Grating tilt has also been applied to decrease core mode back-reflection.

LPG resonances (and to some degree FBGs) may also exhibit strong dependence on the modal dispersion (or variation of the propagation constant, k, with wavelength). This wavelength dependence can dominate the wavelength dependence arising from CMT, making the resonance more or less narrow than predicted by CMT without modal dispersion. In an extreme case, very broadband LPG resonances (40 nm) may be produced between the core mode and a specially designed higher-order mode whose propagation constant varies such that it is resonant with the core mode over a large bandwidth.

Fiber Grating Fabrication

Photosensitivity

The key discovery leading to the study and practical application of fiber gratings was the phenomenon of UV-induced photosensitivity in the conventional germanosilicate optical fibers used in telecommunications systems. UV irradiation of the germanosilicate core region can produce refractive index changes in the range 0.01 to 0.0001. Such refractive index changes are large enough to produce useful filters and reflectors. The refractive index change is most efficiently produced by irradiation close to 242 nm or around 193 nm, where germanosilicate glass has strong absorptions. Numerous other dopants have been shown to be photosensitive at wavelengths ranging from 484 nm to 155 nm. These include P, Ce, Pb, Sn, N, Sn-Ge, Sb, and Ge-B. Other dopants, such as Al and F, show very little photosensitivity.

A second major discovery enabling practical manufacture of fiber gratings was the effect of 'hydrogen loading'. The fiber is placed in a pressurized hydrogen atmosphere until molecular hydrogen has diffused into the core region to a level of a few mole percent (a level similar to that of the photosensitive dopants). UV irradiation of the resulting fiber produces index changes an order of magnitude larger than in the unloaded fiber. Hydrogen loading allows gratings to be easily imprinted in conventional single-mode fibers, whose Ge content is too low to allow for strong gratings. The increase in photosensitivity is true for most photosensitive dopants. Index changes in excess of 10^{-2} have been produced with hydrogen loading. In order to avoid increased OH absorption in the telecommunications band (1520–1630 nm), deuterium (D_2) is normally used in place of hydrogen.

The origins of UV photosensitivity are not fully understood; however, at least two mechanisms are agreed to contribute to the index change. Firstly, as is evident from Figure 5, the UV absorption spectrum is modified during UV exposure. This bleaching corresponds to a change in refractive index in the infrared which may be computed using the Kramers–Kronig relations. In particular, the absorption band at



Figure 5 UV absorption spectrum of Ge-doped silica before and after irradiation with 242 nm light, showing bleaching of the Ge-oxygen deficient defect feature at 242 nm.

242 nm resulting from germanium oxygen deficient centers is bleached, indicating that these defects are modified during exposure. The infrared index change results both from this bleaching and from the change in the UV absorption edge at ~190 nm. Secondly, absorption of UV causes the silica matrix to contract. This compaction and the resulting stress distribution also change the refractive index.

Both mechanisms are enhanced by the presence of hydrogen in the silica lattice. The hydrogen reacts with oxygen, thus increasing the number of UV-absorbing germanium oxygen-deficient centers. As a result, in hydrogen loaded fibers, more of the Ge atoms participate in the index change, explaining the large increase in photosensitivity. The number of oxygen-deficient defects may also be increased during fiber manufacture by collapsing the fiber preform in a low-oxygen atmosphere. Such fibers show increased photosensitivity without the need for hydrogen loading. Co-doping a Ge-doped fiber with boron has also been shown to increase the level of photosensitivity of a fiber for a given level of index change in the core.

An important aspect of UV-induced index changes is that they require thermal annealing to ensure long-term stability. Sufficient exposure to elevated temperatures can completely erase the refractive index change in some Ge-doped gratings. Gratings can be completely erased by several hours of heating to greater than 500 °C. Thermal stability has been described by an activation energy model which assumes a distribution of energies for the defects giving rise to the refractive index change. Therefore, at a given anneal temperature a fixed fraction of the index change will quickly decay, leaving only stable defects that easily survive at lower temperatures. By annealing at several temperatures for a fixed time, a relationship between temperature and time required for a given refractive index decay may then be derived and used in accelerated aging tests of fiber gratings. For 20-year grating reliability of ~1% decrease in UV-induced refractive index change, a typical Ge-doped grating requires annealing at 140 °C for 12 hours.

Grating Inscription

The first method used in UV grating inscription is known as 'internal writing'. In this method light propagating in the fiber causes a standing wave to form within the core, and UV photosensitivity from a two-photon process results in permanent grating formation. Both LPG and FBG resonances have been fabricated using this method. The technique is inflexible, however, because the grating parameters are not easily controlled.

Another important advance that made possible the widespread use of fiber gratings is the 'transverse side-writing' technique. In this method, a UV interference pattern is projected through the side of the fiber onto the core region. The first demonstration of this technique employed a free space interferometer to produce the UV fringes. A significant improvement on this technique employs a zero-order nulled phase mask to generate the interference pattern. The phase mask acts to split the incident beam, and these two then form the interference pattern. The method is shown in Figure 6. The advantage of the phase mask



Figure 6 Phase mask fabrication of a fiber grating.

technique is that the fringes are very stable, since the UV beams propagate only a short distance. Another important technique for writing fiber gratings is the 'point-by point' writing method. In a point-by-point technique the UV interference pattern is modulated and translated along a fiber in such a way that a long grating may be formed. Although complex and sensitive, such methods can yield gratings as long as a few meters and also allow for the fabrication of complex grating profiles. Point-by-point methods have been used to fabricate broadband chirped dispersion compensating gratings and Bragg reflectors with very low dispersion.

LPGs may also be fabricated with UV irradiation. An amplitude mask is typically used. Requirements for beam coherence are greatly reduced because of the long period (typically a few hundred microns). Other techniques may also be used to fabricate LPGs. The fiber may be periodically deformed by heating or with periodic microbends. Dynamic LPGs may also be produced by propagating acoustic waves along the fiber.

Applications

Fiber gratings are key enabling technologies in a number of important applications. In this section we review these, highlighting the unique functionalities that can be provided by fiber gratings.

Fiber Grating Strain and Temperature Sensitivity

Fiber gratings are sensitive to both strain and temperature and may therefore be used as sensors. Both LPG and FBG resonances change with strain and temperature. LPGs show greater but more complicated sensitivity and typically FBGs are used in such applications. Strain sensitivity arises from the fact that gratings are extended in length. Because fibers are very thin (diameter ~125 μm), significant extension is possible. A smaller strain sensitivity arises from the stress optic effect. Typical sensitivity at 1550 nm is ~1 pm/1 $\mu\varepsilon$ in FBGs. Temperature sensitivity arises from temperature dependence of the refractive index and gives rise to a change order 0.011 nm/°C of temperature change of the FBG. FBG strain sensors have been applied to map stress distributions and can be employed in a distributed manner with many Bragg reflectors in one fiber being examined with one detector.

These sensitivities may also be used to make fiber grating filters tunable. Temperature changes are more stable but typically give 1–2 nm of change in an FBG resonance. Strain tuning is more difficult to package commercially but can give up to 4 nm in extension and more than 10 nm in compression. Passive thermal stabilization of grating resonances may also be achieved by designing packages in which strain and temperature variations cancel each other.

Fiber Grating Stabilized Diode Lasers and Fiber Lasers

One of the first important commercial applications of fiber gratings was in stabilization of fiber coupled diode lasers. Normally these lasers operate on several cavity modes making the output unstable. If feedback is provided in the form of a narrowband reflection then the laser output will be only in this narrow bandwidth. The fiber grating is implemented in the fiber pigtail of the diode laser and typically provides a few percent reflectivity over a bandwidth of ~1 nm. The application is depicted schematically in Figure 7.

More generally, fiber gratings have been used to realize fiber laser cavities and fiber distributed feedback lasers. One important example is the cascaded Raman resonator fiber laser, in which several FBGs recycle Raman pump light to produce high-power, fiber coupled light at any design wavelength.

Optical Add/Drop Multiplexers

Another important commercial FBG application is the optical add/drop multiplexer (see Figure 8). These are key components in wavelength division multiplexed (WDM) networks. WDM networks transmit large amounts of data through a single fiber by modulating several optical carrier wavelengths and sending all the wavelengths through a single fiber. The optical add/drop multiplexer allows individual wavelengths to be added or dropped from a given fiber.

Fiber Bragg gratings are useful in this application because of the very narrow resonances that are achievable (typically a few tenths of a nm at 1550 nm). For wavelengths close to the Bragg wavelength an FBG strongly reflects. The reflectivity and bandwidth are determined by the depth of the index modulation and grating length, as discussed earlier. These degrees of freedom make fiber gratings ideal filters to be used in wavelength division multiplexed lightwave networks, in which multiple channels are transmitted along long lengths of optical fiber. Figure 8 illustrates schematically the principle of



Figure 7 Fiber Bragg grating stabilized diode laser. The fiber grating reflector in the laser pigtail provides a small level of feedback to stabilize the laser output power and wavelength.



Figure 8 Top: Add/drop node employing fiber grating reflector. Bottom: characteristic reflection and transmission spectrum of an add/drop fiber grating filter.

a fiber grating based add/drop multiplexer. The grating is located between two three-port optical circulators. (A circulator is a bulk optic element that allows transmission only from port n to port $n + 1$.) Different channels are incident upon the grating from the left and only one particular channel undergoes reflection at the grating. Note that by carefully designing the grating properties the reflectivity in the adjacent channel can be made to be negligible. This one channel is reflected and re-routed by the three-port circulator. The remainder of the channels are transmitted through the grating. The grating also enables the 'add' functionality. In this case light originating from a different part of the optical network enters the link again through an optical circulator and is reflected off the fiber grating.

Gain-Flattening Loss Filters

A primary strength of fiber gratings is the diversity of filter shapes that is achievable through modification of the grating profile. Gain-flatteners are an important application requiring such filter design. Gain-flattening filters are important in WDM telecommunications systems in order to smooth the wavelength dependence of fiber amplifiers (such as Er or Raman amplifiers). Both LPGs and FBGs may be employed as gain flattening filters. The desired loss spectrum is translated into a corresponding grating profile. LPGs have the advantage of low return loss, but the LPG resonance wavelengths and strengths are very sensitive to the fiber geometry, making the computation of the grating profile less accurate. FBGs may also be used in both tilted and untilted form; however they typically have back-reflections that require careful fiber grating growth or an isolator to suppress back-reflections. Figure 9 shows an example of a gain equalizing loss filter using LPGs.

Dispersion Compensator

Chromatic dispersion can limit the transmission distances and capacities of long-haul fiber links. Chromatic dispersion arises from the variation in propagation velocity with wavelength. An initially sharp pulse is thus dispersed and begins to overlap with adjacent pulses resulting in degraded signal quality. A key technology for long-haul fiber links is therefore 'dispersion compensation'. The most common solution has been 'dispersion compensating fiber' (DCF), which is simply fiber in which the chromatic dispersion has been engineered to be the exact opposite of the dispersion in the fiber link. Limitations of DCF include nonlinearities, higher-order dispersion, and lack of tunability. Fiber gratings offer an alternative approach that overcomes the problems.

Fiber Bragg gratings can provide strong chromatic dispersion when operated in reflection with a three-port circulator (see Figure 10). In this case the grating period is made to vary along the length of the grating. This means that different wavelengths in a pulse reflect at different positions in the grating. This gives rise to wavelength-dependent group delay and therefore chromatic dispersion. The advantage of the fiber grating compared to DCF is that the device can be made to be very compact, with potentially lower



Figure 9 Long-period grating gain equalizer. Several individual gratings (dashed line) are combined to produce the overall shape (solid line).



Figure 10 Chirped fiber grating dispersion compensator.

insertion loss, reduced optical nonlinearity, and controllable optical characteristics. In particular fiber gratings offer the possibility of engineering the chromatic dispersion to allow for compensation of dispersion slope and other degradations such as polarization mode dispersion.

Optical Monitors

Fiber gratings may also be employed as compact optical taps coupling core guided light to the radiation modes propagating outside the fiber (see Figure 3b). When a conventional Bragg grating is tilted with respect to the fiber axis it can scatter light out of the fiber in a highly directional manner. The angle of scatter is also wavelength dependent because of the phase matching condition discussed above. This wavelength dependence may form the basis of a compact wavelength monitor. The fiber grating is used to simultaneously couple light out of the fiber and separate the wavelengths. A simple



Figure 11 Fiber grating wavelength monitor. The fiber grating acts to scatter light out of fiber and simultaneously disperse the light.

detector array can then measure a spectrum of all the channels in a typical WDM system (see Figure 11).

Fiber grating taps may also scatter light in a polarization sensitive manner. This may be achieved by tilting the fiber grating by 45° with respect to the fiber axis. The resulting broadband taps may be employed in compact polarization monitoring schemes in which detectors are placed on the outside of the fiber to detect light at specific polarizations.

Advanced Topic in Fiber Gratings

Fiber Gratings in Air–Silica Microstructured Optical Fibers

Air–silica microstructure fibers (ASMFs), also known as ‘holey’ fibers, are fibers with air regions running along their length and allow for more complicated modal properties than conventional silica-doped fiber. It has been shown that fiber gratings can be UV written into photosensitive regions of various types of microstructure fibers. ASMF gratings open new possibilities for fiber grating devices. In addition, they are useful in studying the guidance properties of ASMFs, because they can selectively excite higher-order modes of the fiber. The phase matching condition may be used to derive the effective indices of the higher-order modes and mode profiles may be recorded by imaging a cleaved surface. Such measurements agree well with standard beam propagation computations. Figure 12 shows an example of a mode field image generated with a FBG.

One important application of ASMF gratings is a widely tunable LPG filter. Such filters employ a ‘hybrid waveguide’ formed by infusing a polymer into the air regions. Because the polymer index is much more sensitive to temperature than silica, the guidance properties of the cladding modes may be tuned. Thus, widely tunable LPG filters may be formed. Moreover, because the cladding modes are confined within an ‘inner cladding’ such filters are insensitive to external index, allowing for instance, the use of on-fiber, thin film heaters for power-efficient temperature tuning.



Figure 12 Cross-section of an air–silica microstructure fiber along with measured and simulated modes guided by the air regions.

Nonlinear Optics in Fiber Gratings

The linear properties of fiber gratings are well understood and as explained earlier lead to a number of interesting phenomena and applications. When the peak intensity of the optical field is very high a new class of nonlinear effects can occur. These optical nonlinearities arise from the intrinsic nonlinearity of the material system in which the grating is inscribed. In the case of optical fibers, the dominant nonlinearity is third-order nonlinearity which manifests itself in the refractive index of the material depending on the peak intensity of the optical field: $n = n_0 + n_2 I$. This nonlinearity gives rise to a number of dramatic nonlinear effects in fiber gratings, including all-optical switching, bistability, multistability, soliton generation, pulse compression, and wavelength conversion.

To understand these effects we consider an intense optical field incident upon a fiber grating with a central wavelength tuned inside the stopband of the grating where the reflectivity is high. At low intensities the pulse is reflected and only a small amount of light leaks through the grating. As the intensity of the incident optical field is increased the optical nonlinearity becomes significant and results in shifting of the local Bragg wavelength of the grating. This in turn can lead to an increase in transmission of light through the grating and bistable operation.

Theoretical studies of the continuous wave nonlinear properties of periodic media show that such media can exhibit switching as well as bistability and multistability. This prediction has been confirmed experimentally in a variety of geometries, such as in semiconductors, and in colloidal crystals. Experiments studying nonlinear effects in gratings can also be performed in optical fiber gratings. In these experiments short optical pulses are typically used in order to obtain the very high intensities. This has several key advantages. The first of these is that long, high-quality Bragg gratings can be permanently imprinted into the core of optical fibers by side illumination with interfering ultraviolet beams (see above). This allows for very long interaction lengths (compared to picosecond pulse lengths) and enables nonlinear propagation phenomena to be studied in detail. These include a number of propagation phenomena, such as the formation and propagation of Bragg solitons, modulational instability, and pulse compression. The second advantage is that although the nonlinearity is weak, it has a response time of the order of a few femtoseconds, and thus acts essentially instantaneously on the scale of all but the shortest optical pulses. Finally, the ability to engineer the fiber grating offers a number of unique geometries and potential applications of nonlinear fiber gratings.

A key idea in the interpretation of nonlinear optics in fiber Bragg gratings is the Bragg soliton. Briefly, in these solitons the enormous dispersion provided by the fiber Bragg grating is balanced by the fiber nonlinearity. This is analogous to the optical soliton that has been demonstrated in standard single-mode fiber where the dispersion is predominantly associated with the intrinsic material properties of silica. Since the dispersion of a Bragg grating can be five orders of magnitude larger than that of unprocessed fiber, Bragg solitons can be observed in gratings of only a few centimeters in length, thus rivaling the compactness of other soliton geometries, such as spatial solitons. Of course this implies that the required optical intensities to generate Bragg solitons are correspondingly higher than in uniform media.



Figure 13 Pulse compression associated with nonlinear pulse propagation through a fiber Bragg grating. Compression is associated with the formation of a Bragg soliton when the incident pulse is tuned just outside of the photonic bandgap formed by the grating.

Figure 13 shows an example of experimental results when the peak intensity of a pulse incident upon a fiber grating was approximately 10 GW/cm^2 and the incident pulse is tuned to the anomalous dispersion regime of the grating. In particular, Figure 13 shows the transmitted intensity versus time for different values of detuning. By varying the strain on the grating, we can change the detuning of the input pulse, and thus tune to different points on the dispersion curve. Note also from Figure 13 that far from the photonic bandgap edge, where the grating-induced dispersion is negligible, the pulse is unaffected and propagates through the grating at the speed of light. Closer to the edge of the photonic bandgap the pulse is substantially compressed due to the formation of a Bragg soliton. In addition to this compression, the transmitted pulse is substantially delayed in time as a result of the reduced group velocity of the pulse propagating through the grating.

List of Units and Nomenclature

cw	Continuous wave
FBG	Fiber Bragg grating
LPG	Long-period grating

See also

Detection: Fiber Sensors. **Fiber and Guided Wave Optics:** Fabrication of Optical Fiber; Light Propagation; Measuring Fiber Characteristics; Nonlinear Optics; Optical Fiber Cables. **Lasers:** Optical Fiber Lasers. **Optical Amplifiers:** Optical Amplifiers in Long-Haul Transmission Systems. **Optical Communication Systems:** Architectures of Optical Fiber Communication Systems; Basic Concepts. **Optical Materials:** Optical Glasses. **Photon Picture of Light**.

Further Reading

Adams MJ (1981) *An Introduction to Optical Waveguides*. Chichester, UK: Wiley.

Agrawal GP (2001) *Applications of Nonlinear Fiber Optics*. San Diego, CA: Academic Press.

Eggleton BJ, Westbrook PS, Windeler RS, Spalter S and Strasser TA (1999) Grating resonances in air-silica microstructured optical fibers. *Optical Letters* 24: 1460–1462.

Eggleton BJ, Lenz G and Litchinitser NM (2000) Optical pulse compression schemes that use nonlinear Bragg gratings. *Fiber Integrated Optics* 19: 383–421.

Espindola RP, Windeler RS, Abramov AA, *et al.* (1999) External refractive index insensitive air-clad long period fiber grating. *Electronic Letters* 35: 327–328.
Hill KO, Fujii Y, Johnson DC and Kawasaki BS (1978) Photosensitivity in optical fiber waveguides: applications to reflection filter fabrication. *Applied Physics Letters* 32: 647–649.
IEEE Journal of Lightwave Technology (1997) Special issue on fiber gratings, photosensitivity and poling 15(8).
Kashyap R (1999) *Fiber Bragg Gratings*. New York: Academic Press.
Kogelnik H (1990) Theory of optical waveguides. In: Tamir T (ed.) *Guided-Wave Optoelectronics*. Berlin: Springer-Verlag.
Lemaire PJ, Atkins RM, Mizrahi V and Reed WA (1993) High-pressure H_2 loading as a technique for achieving ultrahigh UV photosensitivity and thermal sensitivity in GeO_2 doped optical fibers. *Electronic Letters* 29: 1191–1193.
Marcuse D (1974) *Theory of Dielectric Optical Waveguides*. New York: Academic Press.
Meltz G, Morey WW and Glenn WH (1989) Formation of Bragg gratings in optical fibres by transverse holographic method. *Optical Letters* 14: 823–825.
Othonos A and Kalli K (1999) *Fiber Bragg Gratings: Fundamentals and Applications in Telecommunications and Sensing*. Norwood, MA: Artech House.
Polladian L (1993) Graphical and WKB analysis of nonuniform Bragg gratings. *Physical Review E* 48: 4758–4767.
Westbrook PS, Eggleton BJ, Windeler RS, *et al.* (2001) Cladding mode loss in hybrid polymer-silica microstructured optical fiber gratings. *IEEE Photonic Technology Letters* 12: 495–497.

FOURIER OPTICS

S Jutamulia, University of Northern California, Petaluma, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Coherent optical information processing is almost entirely based on the Fourier-transform property of a lens. A Fourier-transform lens is actually an ordinary lens. If the input transparency is placed in the front focal plane of the lens and illuminated with coherent collimated light (planewave), the amplitude function in the back focal plane of the lens will be the Fourier transform of the input transparency as shown in Figure 1. A coherent optical processor usually consists of two lenses, as shown in Figure 2, thus it performs two Fourier transforms successively. The first lens transforms the input function from space domain into frequency domain, and the second lens transforms back the frequency function from frequency domain to the output function in space domain.

Fourier Transform Property of Lens

Recently, the Fourier-transform property of lenses has been explained, simply using the concept of linear system and geometrical optics. In contrast, the Fourier-transform property of lenses is traditionally analyzed, based on the Fresnel–Kirchhoff diffraction theory involving quadratic phase terms (eqns [2] and [3]). In this article, we adopt the simple geometrical theory based on geometrical optics.

We start our discussion by looking at Figure 1. Consider that a coherent point source is at the center of the front focal plane of the lens, which is denoted by plane (x, y). The point source generates a collimated beam parallel to the optical axis. The amplitude function at the back focal plane of the lens, which is denoted by plane (u, v), can be described as unity. Consequently, we can express mathematically:

$$f(x, y) = \delta(x, y) \qquad [1]$$

$$F(u, v) = 1 \qquad [2]$$

where $f(x, y)$ is the amplitude function in the front focal plane, and $F(u, v)$ is the amplitude function in the back focal plane.

If the point source shifts a distance a along the y-axis, the amplitude function in the front focal plane is

$$f(x, y) = \delta(x, y + a) \qquad [3]$$

The off-axis point source generates a tilted collimated beam. If we place a screen in the plane (u, v), we will see uniform intensity across the screen similar to that which would be seen when the source is centered on the axis. Mathematically, it means:

$$|F(u, v)|^2 = 1 \qquad [4]$$

However, the phase of the amplitude function is not uniform, since the collimated beam is not parallel to


Amplitude function f(x,y)
Amplitude function f(u,v)
y
x
Lens
v
u
f
f

Figure 1 A lens Fourier-transforms amplitude function $f(x, y)$ in the front focal plane to amplitude function $F(u, v)$ in the back focal plane.


Input plane
Fourier-transform plane
Output plane
Lens
Lens
y
x
v
u
ξ
η
Illuminating coherent collimated light
f
f
f
f

Figure 2 A pair of lenses form 4-f coherent optical processor.

the optical axis. In other words, plane (u, v) is not parallel to the wavefront.

If the phase at the center of plane (u, v) is considered zero, the phase at any point at plane (u, v) can be calculated referring to Figure 3. Using simple geometry, we know that

$$d(u, v) = \frac{a}{f} v \qquad [5]$$

where $d(u, v)$ is the optical path difference. Correspondingly, the phase is

$$\phi(u, v) = \frac{2\pi}{\lambda f} av \qquad [6]$$

where λ is the wavelength of light.

In complex representation, the amplitude function is expressed as

$$F(u, v) = A(u, v) \exp[i\phi(u, v)] \qquad [7]$$

where $A(u, v)$ and $\phi(u, v)$ are magnitude and phase of the amplitude function, respectively. From eqn [4], we know that

$$A(u, v) = |F(u, v)| = 1 \qquad [8]$$


Front focal plane (x,y)
Back focal plane (u,v)
Lens
f
d
v
a

Figure 3 Calculation of phase function in the back focal plane (u, v) based on geometrical optics.


y′
y
−p′
x′
a
x
−q′
−a
v′
v
u′
α
u

(a) (b)

Figure 4 (a) Front focal plane coordinate system (x, y) is rotated by α. (b) Similarly, back focal plane coordinate system (u, v) is rotated by α.

Substituting eqns [8] and [6] into [7] yields

$$F(u, v) = \exp\left(i\frac{2\pi}{\lambda f} av\right) \qquad [9]$$

Equation [9] is the amplitude function in the back focal plane of the lens, when the amplitude function in the front focal plane of the lens is given by eqn [3].

Consider now that coordinate (x, y) is rotated by angle α to new coordinates (x', y') as shown in Figure 4a. The amplitude function in the front focal plane now becomes

$$f(x', y') = \delta(x' + p', y' + q') \qquad [10]$$

where

$$p' = a \sin \alpha \qquad [11a]$$

$$q' = a \cos \alpha \qquad [11b]$$

Correspondingly, coordinate (u, v) is also rotated by the same angle α to new coordinates (u', v') as shown in Figure 4b. The old coordinates u and v can be described in terms of new coordinates u' and v' as follow:

$$u = u' \cos \alpha - v' \sin \alpha \qquad [12a]$$

$$v = u' \sin \alpha + v' \cos \alpha \qquad [12b]$$

Substituting eqn [12b] into eqn [6] yields

$$\phi(u', v') = \frac{2\pi}{\lambda f} a(u' \sin \alpha + v' \cos \alpha) \qquad [13]$$

Further, substituting eqns [11a] and [11b] into [13] yields

$$\phi(u', v') = \frac{2\pi}{\lambda f}(p'u' + q'v') \qquad [14]$$

Thus, the amplitude function in the back focal plane of lens is

$$F(u', v') = \exp\left[i\frac{2\pi}{\lambda f}(p'u' + q'v') \right] \qquad [15]$$

For convenience, we now change parameters x' and y' to x and y, u' and v' to u and v, p' and q' to $-p$ and $-q$. Equations [10] and [15] become

$$f(x, y) = \delta(x - p, y - q) \qquad [16]$$

$$F(u, v) = \exp\left[-i\frac{2\pi}{\lambda f}(pu + qv) \right] \qquad [17]$$

We may simply consider that $f(x, y)$ is an input function and $F(u, v)$ is an output function of a system, since they are both physically the same amplitude functions. If there are two mutually coherent point sources at $(0, 0)$ and $(0, -a)$ with different amplitudes k and l in the front focal plane, the input function is

$$f(x, y) = k\delta(x, y) + l\delta(x, y + a) \qquad [18]$$

These two point sources will generate two collimated beams. Since they are mutually coherent, two collimated beams will interfere, and the resultant amplitude function in the back focal plane is simply the superposition of two beams, which is

$$F(u, v) = k + l \exp\left(i\frac{2\pi}{\lambda f} av \right) \qquad [19]$$

Thus, the lens is a linear system when the light is coherent. Furthermore, if input function $f(x, y)$ is a group of mutually coherent point sources with different amplitudes (i.e., an optical transparency illuminated with a planewave), it can be expressed as follows:

$$f(x, y) = \int\int_{-\infty}^{\infty} f(p, q)\delta(x - p, y - q)\mathrm{d}p\, \mathrm{d}q \qquad [20]$$

Since the lens is a linear system, output function will be the same superposition as follows:

$$F(u,v) = \int\int_{-\infty}^{\infty} f(p,q)\exp\left[-i\frac{2\pi}{\lambda f}(pu+qv) \right]\mathrm{d}p\mathrm{d}q \qquad [21]$$

By again changing parameters p and q to x and y, respectively, eqn [21] becomes

$$F(u,v) = \int\int_{-\infty}^{\infty} f(x,y)\exp\left[-i\frac{2\pi}{\lambda f}(xu+yv) \right]\mathrm{d}x\mathrm{d}y \qquad [22]$$

which is the optical Fourier transform of the input function $f(x,y)$.

4-f Coherent Optical Processor

If the amplitude function in the front focal plane of a lens is denoted by $f(x, y)$, then the amplitude function in the back focal plane is simply $F(u, v)$ given in eqn [22], which is the Fourier transform of $f(x, y)$. Mathematically, $f(x, y)$ can also be derived from $F(u, v)$ (eqn [4]). After neglecting the normalization factor, it can be expressed as follows:

$$f(x, y) = \int\int_{-\infty}^{\infty} F(u, v)\exp\left[i\frac{2\pi}{\lambda f}(xu+yv) \right]\mathrm{d}u\, \mathrm{d}v \qquad [23]$$

The normalization factor $(1/\lambda f)^2$ is caused by the coordinate scale factor λf in the Fourier-transform plane (u,v).

Equations [22] and [23] are Fourier transform and inverse Fourier transform, respectively. The operation of Fourier transform is represented by a notation $F\{\cdot\}$, and inverse Fourier transform is $F^{-1}\{\cdot\}$.

Two Fourier transform lenses can be combined into a two-lens processor, which is better known as a 4-f optical processor, as shown in Figure 2. Figure 2 illustrates the principle of a 4-f optical processor, in which $f(x, y)$, $F(u, v)$, and $f(\xi, \eta)$ are amplitude functions in input, Fourier transform, and output planes, respectively. Since $F(u, v)$ is the function of spatial frequency, Fourier-transform plane is also called a frequency plane. Since a lens performs only Fourier transform, to perform inverse Fourier transform, the output plane must be rotated by 180°. Thus, orientations of ξ and η correspond to $-x$ and $-y$.

In practice, $f(x, y)$ is represented by an optical mask, which can be a film transparency or a spatial light modulator. The optical mask with $f(x, y)$ amplitude transmittance is illuminated with collimated coherent light to produce the amplitude function $f(x, y)$. The Fourier transform $F(u, v)$ is physically formed in the frequency plane. The frequency content of the input function $f(x, y)$ can be directly altered by placing an optical mask in the frequency plane. Finally, an image with amplitude function $f(\xi, \eta)$ is formed in the output plane. Notice that all detectors, including our eyes, detect intensity that is the square of amplitude.



Figure 5 Block diagram of 4-f coherent optical processor.

According to eqn [22], $F(u,v)$ can be expressed in terms of $f(x,y)$ as

$$F(u,v) = F\{f(x,y)\} \qquad [24]$$

Similarly, the amplitude function in the output plane must be

$$f(x',y') = F\{F(u,v)\} \qquad [25]$$

where (x',y') is the coordinate of the output plane having the same orientation as (x,y) in the input plane. This function can be expressed in terms of inverse Fourier transform as follows:

$$f(-x',-y') = F^{-1}\{F(u,v)\} \qquad [26]$$

A rotated coordinate (ξ,η), shown in Figure 2, substitutes $(-x',-y')$, such that

$$f(\xi,\eta) = F^{-1}\{F(u,v)\} \qquad [27]$$

Thus, the successive operations can be simply illustrated by the diagram shown in Figure 5.

Spatial Filtering

The origin of optical information processing can be traced as far back as the work of Abbe of 125 years ago. His interest at that time concerned the theory of microscopy in order to establish a scientific approach to microscope design. He found that a larger aperture resulted in higher resolution. An object under the microscope, whose size was of the order of the wavelength of light, diffracted the illuminating light, i.e., the straight light was bent. If the aperture of the objective lens was not large enough to collect all of the diffracted light, the image did not correspond exactly to that object. Rather, it related to a fictitious object whose complete diffracted light pattern matched the one collected by the objective lens. These lost portions are associated with the higher spatial frequency. Their removal will result in a loss in image sharpness and resolution. The basic ideas of Abbe's theory were later clarified in a series of experiments by Porter in the early 1900s.

Since the late 1940s, the possibility of applying coherent optical techniques to image processing had been explored. In 1960, Cutrona *et al.* presented an optical system using lenses to perform Fourier transforms. Thus, every Fourier transformation in the processor can be realized by a lens. The power of this architecture is its capability of forming Fourier spectra and also being cascaded.

Consider an image formed by an optical system such as a camera; because of the error or limitation of the system, the perfect point in the object may smear. If we consider that the original object is the collection of a large number of very fine points, the formed image will be the collection of the same number of blurred spots, instead of fine points. Thus, the image formation can be expressed by convolution. The blurred spot is represented by the impulse response $h(x,y)$, which is the characteristic of the optical system.

When the input is a point (an impulse), its amplitude function is a delta function $\delta(x,y)$, and the output amplitude function is $h(x,y)$. The observed image is the intensity function $|h(x,y)|^2$. Since it indicates the spread of a point, $|h(x,y)|^2$ is called the point spread function.

The output image function $o(x,y)$ is the convolution of input function $f(x,y)$ and the impulse response $h(x,y)$ as follows:

$$o(x,y) = \iint_{-\infty}^{\infty} f(p,q)h(x-p,y-q)\mathrm{d}p\,\mathrm{d}q \qquad [28]$$

Notice that $h(x-p,y-q)$ is the blurred spot centered at (p,q). $H(u,v)$, $F(u,v)$, and $O(u,v)$ are Fourier transforms of $h(x,y)$, $f(x,y)$, and $o(x,y)$, respectively. Substitution of

$$h(x-p,y-q) = \iint_{-\infty}^{\infty} H(u,v) \times\exp\left[i\frac{2\pi}{\lambda f}[(x-p)u+(y-q)v]\right]\mathrm{d}u\,\mathrm{d}v \qquad [29]$$

then

$$F(u,v) = \iint_{-\infty}^{\infty} f(p,q)\exp\left[-i\frac{2\pi}{\lambda f}(pu+qv)\right]\mathrm{d}p\,\mathrm{d}q \qquad [30]$$

yields

$$o(x,y) = \iint_{-\infty}^{\infty} F(u,v)H(u,v)\exp\left[i\frac{2\pi}{\lambda f}(xu+yv)\right]\mathrm{d}u\,\mathrm{d}v \qquad [31]$$

Since

$$o(x,y) = \iint_{-\infty}^{\infty} O(u,v)\exp\left[i\frac{2\pi}{\lambda f}(xu+yv)\right]\mathrm{d}u\,\mathrm{d}v \qquad [32]$$

we obtain

$$O(u,v) = H(u,v)F(u,v) \qquad [33]$$

The function $H(u,v)$, which is the Fourier transform of the impulse response $h(x,y)$, is called transfer function. Actually, $H(u,v)$ changes the spectrum of input function $F(u,v)$ to become $O(u,v)$ and the spectrum of the output function becomes $H(u,v)F(u,v)$.

The first application of spatial filtering may be the restoration of a photograph. The image formed by a camera is a collection of spots. If the image is in focus, the size of the spots is very fine, and thus the image looks sharp. If the image is out of focus, the spot size is fairly large and the image is blurred. Interestingly, an out-of-focus image can be restored using spatial filtering technique.

Consider that the original image is $f(x,y)$. Because it is out of focus, a point in the image becomes a spot expressed by $h(x,y)$. If the image is in focus, $h(x,y)$ is a delta function. If the in-focus image is $f(x,y)$, its frequency function is $F(u,v)$. The defocused image $o(x,y)$ is expressed by eqn [28], and its frequency function is $F(u,v)H(u,v)$. To produce the in-focus image, the frequency function must be $F(u,v)$. Thus $F(u,v)H(u,v)$ must be multiplied by the filter function of $1/H(u,v)$ to produce $F(u,v)$ only. The filter of $1/H(u,v)$ can be made from a photographic plate to provide its magnitude, and a glass plate having two values of thickness to provide +1 and −1 signs. The glass plate is essentially a phase filter. The photographic plate with varying density function is an amplitude filter. By passing frequency function $F(u,v)H(u,v)$ through the combination of amplitude and phase filters, it will result in $F(u,v)$ only. When $F(u,v)$ is again Fourier transformed by a lens, an in-focus image $f(x,y)$ will be produced.

Complex Matched Spatial Filtering

The restoration of a photograph mentioned above, utilizes the filter function $1/H(u,v)$, which has positive and negative real values. We will see an application in which the filter function is a complex function. A complex function filter can be produced by a single hologram, instead of using a combination of a phase filter and an amplitude filter. The complex matched spatial filter can perform a correlation, as first demonstrated by Vander Lugt. The complex filter is actually a Fourier transform hologram proposed by Leith and Upatnieks.

The synthesis of a complex filter is shown in Figure 6. First, a function $g(x,y)$ is displayed in the input plane by a transparency or spatial light modulator and illuminated with a collimated coherent light beam. Its Fourier-transform $G(u,v)$ is generated in the back focal plane of the lens. The hologram is made in the Fourier-transform plane by recording the interference pattern of $G(u,v)$ and the reference beam $R(u,v)$. $R(u,v)$ is an oblique collimated beam, having magnitude of unity, which is expressed mathematically as

$$R(u,v) = \exp(iau) \qquad [34]$$

and

$$a = \frac{2\pi \sin\alpha}{\lambda} \qquad [35]$$

where α is the angle of the reference beam and λ is the wavelength of light.

The transmittance of the recorded hologram will be

$$\begin{aligned} T(u,v) &= |G(u,v) + R(u,v)|^2 \\ &= |G(u,v)|^2 + 1 + G(u,v)\exp(-iau) \\ &\quad + G^*(u,v)\exp(iau) \end{aligned} \qquad [36]$$

where * denotes the complex conjugate. The hologram, which is called a complex matched spatial filter, is then placed back in the Fourier-transform plane, as shown in Figure 7. A new input function $f(x,y)$ is displayed in the input plane. The Fourier-transform of input function, $F(u,v)$ will be generated in the Fourier-transform plane. The amplitude of light,



Figure 6 Synthesis of complex matched spatial filter is the recording of Fourier-transform hologram.



Figure 7 Optical processing using complex matched spatial filter in a 4-f processor.

immediately after the complex matched spatial filter, is

$$F(u,v)T(u,v) = (|G(u,v)|^2+1)F(u,v) + F(u,v)G(u,v)\exp(-iau) + F(u,v)G^*(u,v)\exp(iau) \qquad [37]$$

The second lens then produces the inverse Fourier transform of $F(u,v)T(u,v)$ in the output plane:

$$F^{-1}\{F(u,v)T(u,v)\} = F^{-1}\{(|G(u,v)|^2+1)F(u,v)\} + F^{-1}\{F(u,v)G(u,v)\exp(-iau)\} + F^{-1}\{F(u,v)G^*(u,v)\exp(iau)\} \qquad [38]$$

The first term will be at the center of the output plane. The second and the third terms will appear at $(b,0)$ and $(-b,0)$ in (ξ,η) plane, respectively, where

$$b = f\sin\alpha \qquad [39]$$

and f is the focal length of lens.

We are now in a position to analyze the inverse Fourier transform of $F(u,v)G(u,v)$ and $F(u,v)G^*(u,v)$. Referring to eqns [28]–[33], the inverse Fourier transform of $F(u,v)G(u,v)$ is the convolution of $f(\xi,\eta)$ and $g(\xi,\eta)$. Thus, the complex matched spatial filtering can also be applied to the restoration of photography mentioned previously without using the combination of amplitude and phase filters.

The inverse Fourier transform of $F(u,v)G^*(u,v)$ is derived as follows:

$$o_3(\xi,\eta) = \iint_{-\infty}^{\infty} F(u,v)G^*(u,v) \times \exp\left[i\frac{2\pi}{\lambda f}(\xi u+\eta v)\right]\mathrm{d}u\,\mathrm{d}v \qquad [40]$$

Substitute

$$F(u,v) = \iint_{-\infty}^{\infty} f(\alpha,\beta) \times \exp\left[-i\frac{2\pi}{\lambda f}(\alpha u+\beta v)\right]\mathrm{d}\alpha\,\mathrm{d}\beta \qquad [41]$$

and

$$G^*(u,v) = \iint_{-\infty}^{\infty} g^*(-p,-q) \times \exp\left[-i\frac{2\pi}{\lambda f}(pu+qv)\right]\mathrm{d}p\,\mathrm{d}q \qquad [42]$$

into eqn [40], one obtains

$$o_3(\xi,\eta) = \iint_{-\infty}^{\infty} f(\alpha,\beta)\iint_{-\infty}^{\infty} g^*(-p,-q) \times \iint_{-\infty}^{\infty}\exp\left[i\frac{2\pi}{\lambda f}(\xi-\alpha-p)u + (\eta-\beta-q)v\right]\mathrm{d}u\,\mathrm{d}v\,\mathrm{d}p\,\mathrm{d}q\,\mathrm{d}\alpha\,\mathrm{d}\beta$$

$$o_3(\xi,\eta) = \iint_{-\infty}^{\infty} f(\alpha,\beta)\iint_{-\infty}^{\infty} g^*(-p,-q) \times \delta(\xi-\alpha-p,\eta-\beta-q)\mathrm{d}p\,\mathrm{d}q\,\mathrm{d}\alpha\,\mathrm{d}\beta$$

$$o_3(\xi,\eta) = \iint_{-\infty}^{\infty} f(\alpha,\beta)g^*(\alpha-\xi,\beta-\eta)\mathrm{d}\alpha\,\mathrm{d}\beta \qquad [43]$$

Equation [43] is the correlation of $f(x,y)$ and $g(x,y)$. It is apparent that the correlation output $o_3(\xi,\eta)$ will achieve the maximum when $f(x,y)$ is identical to $g(x,y)$. If $f(x,y)$ and $g(x,y)$ are different, the correlation function will be a flat function with minor random fluctuation. Optical correlators using complex matched spatial filters have been applied to automatic pattern recognition.

Joint Transform Correlator

Alternatively, the joint transform correlator can perform a correlation without recording a complex matched spatial filter in advance. In addition to the correlation, the joint transform correlator can also be used as a general optical processor.

A transparency with amplitude transmittance $f(x,y)$ is centered at $(-a,0)$, and a second transparency with amplitude transmittance $g(x,y)$, is centered at $(a,0)$. The two transparencies are illuminated by a coherent collimated beam and jointly Fourier transformed by a single lens as shown in Figure 8. In the back focal plane of the lens, the amplitude function $S(u,v)$ is

$$S(u,v) = \iint_{-\infty}^{\infty} [f(x+a,y)+g(x-a,y)] \times \exp\left[-i\frac{2\pi}{\lambda f}(xu+yv)\right]\mathrm{d}x\,\mathrm{d}y \qquad [44]$$



Figure 8 Joint Fourier transform of two input functions.



Figure 9 Fourier transform of the joint power spectrum.

$S(u,v)$ is the joint Fourier spectrum of $f(x,y)$ and $g(x,y)$. It can be written as

$$S(u,v) = F(u,v)\exp\left[i\frac{2\pi}{\lambda f}au\right] + G(u,v)\exp\left[-i\frac{2\pi}{\lambda f}au\right] \quad [45]$$

where $F(u,v)$ and $G(u,v)$ are Fourier transforms of $f(x,y)$ and $g(x,y)$, respectively.

If a square-law detector is placed in the back focal plane of the lens, the recorded pattern of joint power spectrum $|S(u,v)|^2$ is

$$\begin{aligned}|S(u,v)|^2 = {} & |F(u,v)|^2 \\ & + F(u,v)G^*(u,v)\exp\left[i\frac{4\pi}{\lambda f}au\right] \\ & + F^*(u,v)G(u,v)\exp\left[-i\frac{4\pi}{\lambda f}au\right] \\ & + |G(u,v)|^2 \end{aligned} \quad [46]$$

where * denotes the complex conjugate. A photographic plate is a square-law detector and can be used to record $|S(u,v)|^2$. When the developed plate is placed in the input plane, as shown in Figure 9, the input transmittance is $|S(u,v)|^2$ as given in eqn [46].

The inverse Fourier transform of the joint power spectrum $|S(u,v)|^2$, in the back focal plane of the lens, is

$$o(\xi,\eta) = \iint_{-\infty}^{\infty} |S(u,v)|^2 \exp\left[i\frac{2\pi}{\lambda f}(\xi u + \eta v)\right]\mathrm{d}u\,\mathrm{d}v \quad [47]$$

which consists of four terms, according to eqn [46]. We now analyze this equation term by term. The first term is

$$o_1(\xi,\eta) = \iint_{-\infty}^{\infty} |F(u,v)|^2 \exp\left[i\frac{2\pi}{\lambda f}(\xi u + \eta v)\right]\mathrm{d}u\,\mathrm{d}v \quad [48]$$

which is the auto-correlation of $f(x,y)$

$$o_1(\xi,\eta) = \iint_{-\infty}^{\infty} f(\alpha,\beta)f^*(\alpha-\xi,\beta-\eta)\mathrm{d}\alpha\,\mathrm{d}\beta \quad [49]$$

The second term is

$$o_2(\xi,\eta) = \iint_{-\infty}^{\infty} F(u,v)G^*(u,v)\exp\left[i\frac{4\pi}{\lambda f}au\right] \times \exp\left[i\frac{2\pi}{\lambda f}(\xi u + \eta v)\right]\mathrm{d}u\,\mathrm{d}v \quad [50]$$

which is

$$o_2(\xi,\eta) = \iint_{-\infty}^{\infty} f(\alpha,\beta)g^*[\alpha-(\xi+2a),\beta-\eta]\mathrm{d}\alpha\,\mathrm{d}\beta \quad [51]$$

Equation [51] is the correlation between $f(x,y)$ and $g(x,y)$, shifted by $-2a$ in the ξ-axis direction.

Similarly, the third term will be the correlation between $g(x,y)$ and $f(x,y)$, shifted by $2a$ in the ξ-axis direction:

$$o_3(\xi,\eta) = \iint_{-\infty}^{\infty} g(\alpha,\beta)f^*[\alpha-(\xi-2a),\beta-\eta]\mathrm{d}\alpha\,\mathrm{d}\beta \quad [52]$$

And the fourth term is

$$o_4(\xi,\eta) = \iint_{-\infty}^{\infty} g(\alpha,\beta)g^*(\alpha-\xi,\beta-\eta)\mathrm{d}\alpha\,\mathrm{d}\beta \quad [53]$$

which is the auto-correlation of $g(x,y)$ and overlaps with the first term at the center of the output plane.

From the analysis given above, it is understood that the correlation of $f(x,y)$ and $g(x,y)$, and the correlation of $g(x,y)$ and $f(x,y)$, are shifted by $-2a$ and $2a$, respectively, along the ξ-axis. The correlation outputs are centered at $(-2a,0)$ and $(2a,0)$ in the back focal plane of the lens. If $f(x,y)$ and $g(x,y)$ are the same, the two correlation outputs are identical. The first and fourth terms are the autocorrelations of $f(x,y)$ and $g(x,y)$, centered at $(0,0)$. Thus the second and third terms, which are correlation signals, can be isolated. A versatile real-time joint transform correlator, using inexpensive liquid crystal televisions, is widely used in laboratory demonstration.

See also

Information Processing: Coherent Analogue Optical Processors. **Spectroscopy:** Fourier Transform Spectroscopy.

Further Reading

Abbe E (1873) Beitrage zur Theorie des Mikroskops und der mikroskopichen Wahrnehmung. *Archiv Mikroskopie Anatomie* 9: 413–468.

Bracewell RN (1965) *The Fourier Transform and Its Applications*. New York: McGraw-Hill.

Cutrona LJ, Leith EN, Palermo CJ and Porcello LJ (1960) Optical data processing and filtering systems. *IRE Transactions on Information Theory* IT-6: 386–400.

Goodman JW (1968) *Introduction to Fourier Optics*. New York: McGraw-Hill.

Jutamulia S (1992) Joint transform correlators and their applications. *Proceedings of the SPIE* 1812: 233–243.

Jutamulia S and Asakura T (2002) Optical Fourier-transform theory based on geometrical optics. *Optical Engineering* 41: 13–16.

Leith EN and Upatnieks J (1962) Reconstructed wavefronts and communication theory. *Journal of the Optical Society of America* 52: 1123–1130.

Porter AB (1906) On the diffraction theory of microscopic vision. *Philosophical Magazine* 11: 154–166.

Rau JE (1966) Detection of differences in real distributions. *Journal of the Optical Society of America* 56: 1490–1494.

Tsujiuchi J (1963) Correction of optical images by compensation of aberrations and by spatial frequency filtering. *Progress in Optics* 2: 133–180.

Vander Lugt A (1964) Signal detection by complex spatial filtering. *IEEE Transactions on Information Theory* IT-10: 139–145.

Weaver CS and Goodman JW (1966) A technique for optically convolving two functions. *Applied Optics* 5: 1248–1249.

Yu FTS (1983) *Optical Information Processing*. New York: Wiley.

Yu FTS and Ludman JE (1988) Joint Fourier transform processor. *Microwave Optical Technology Letters* 1: 374–377.

Yu FTS, Jutamulia S, Lin TW and Gregory DA (1987) Adaptive real-time pattern recognition using a liquid crystal TV based joint transform correlator. *Applied Optics* 26: 1370–1372.

G

GEOMETRICAL OPTICS

Contents

Lenses and Mirrors
Aberrations
Prisms

Lenses and Mirrors

A Nussbaum, University of Minnesota, Minneapolis, MN, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Lenses are carefully shaped pieces of transparent material used to form images. The term 'transparent' does not necessarily mean that the lens is transmitting visible light. The element germanium, well-known in the transistor industry, is a light-gray opaque crystal which forms images with infrared radiation, and provides the optics for night-vision instruments. The lenses used in cameras, telescopes, microscopes, and other well-known applications, are made from special glasses or – more recently – from plastics. Hundreds of different optical glass formulas are listed in the manufacturers' catalogues. Plastics have come into use in recent years because it is now possible to mold them with high precision. The way in which lenses form images has been studied for several hundred years, resulting in an enormous and very complicated literature. In this article, we show how this theory can be simplified by introducing the restriction that lenses are perfect. This limitation provides an easy introduction to the image forming process. A companion article **Geometrical Optics:** Aberrations, will deal with imperfect components, showing how their defects degrade images and how corrections are made.

The Cardinal Points and Planes of an Optical System

The location, size and orientation of an image are items of information which a designer needs to know. The nature of the image can be determined by a simple model of an optical system, based on two experimental observations. The first is well-known and is pictured in Figure 1. Parallel rays of light passing through a double convex lens (a simple magnifying glass, for example) should meet at the focal point or focus, designated as F'. For rays from the right side of the lens, another such point F exists at an equal distance from the lens. The other experiment uses the lens to magnify (Figure 2a). The amount of magnification decreases as the lens is brought closer to 'ISAAC NEWTON' (Figure 2b), and when the lens touches the paper, object and image are approximately the same size. The locations of object and image corresponding to equality in size are called the unit or principal points H and H', respectively, and the set of four points F, F', H, and H' are the cardinal points. Therefore, the planes through these points normal to the axis of the lens are the cardinal planes. Figure 3 shows an object whose image we can now determine. The coordinate orientation in this figure may appear strange at first. It is customary in optics to designate the lens axis as OZ, and the other two axes form a right-handed system. The x-axis then lies in the



Figure 1 Focal points of a double convex lens.



(a) (b)

Figure 2 Magnification by a double convex lens. The magnification in (a) is reduced when the lens is brought closer to the image (b).



Figure 3 Ray tracing using cardinal points and planes.

plane of the figure; the y-axis, coming out of the paper and perpendicular to it, is not shown. The object, of height x, is placed to the left of the focal point F. The cardinal points occur in the order F, H, H', F', since we expect – based on the experiment corresponding to Figure 2 – that the unit points are very close to the lens. Another fact to be demonstrated later is that H and H' are actually inside the lens. Two rays are shown leaving the point P at the top of the object. The ray which is parallel to the axis strikes the unit plane through H and continues to the right, completely missing the lens. The ray then meets the unit plane through H' at a point which must be a distance x from the axis. To understand why, we recognize that if the object were relocated so as to lie on the object-space unit plane, the ray emerging at the other unit plane will be at a distance x from the axis; as required by the definition of these planes. We then assume that the ray is bent or refracted at the unit plane at H' and proceeds to, and beyond, the focal point F'. The second ray, from P through the focal point F, is easily traced since the lens is indifferent to the direction of the light. Assume temporarily that we know the location of the image point P'. Let a parallel ray leave this point and travel to the left. The procedure just given indicates that this ray will strike the unit plane at H', emerge at the other unit plane, be refracted so as to pass through F and reach the object point P. Then reversing the direction of this ray, it will start at P, emerge at the unit plane H' and travel parallel to the axis, intersecting the other ray at P'. The distance between F and H is called the object space focal length f, with f' being the corresponding image space quantity. Simple geometry, making use of the similar triangles and the distances indicated in this diagram, can be used to derive the Newton lens equation or the equivalent Gauss lens equation. Detailed derivations of these two equations will be found in either of the sources listed in the Further Reading at the end of this article. It is not usually made clear in physics texts that these equations apply only to the special case of a single, thin lens, and we shall not apply them here. The image in this figure is real, inverted, and reduced. That is, it is smaller than the object, oriented in the opposite direction, and can be projected onto a screen located at the image position. This result can be verified by using an ordinary magnifier to form the image of a distant light source on a sheet of white paper.

Paraxial Matrices

To consider how light rays behave in optical systems, we introduce the index of refraction n of a material medium, defined as the ratio of the velocity of light c in a vacuum to its velocity v in that medium, or:

$$n = \frac{c}{v} \qquad [1]$$

The velocity of light in air is approximately the same as it is in a vacuum. A light ray crossing the interface between air and a denser medium such as glass will be bent towards the normal to the surface. This is the phenomenon of refraction and the amount of bending is governed by Snell's law, which has the form:

$$n \sin \theta = n' \sin \theta' \qquad [2]$$

where n and n' are the indices of refraction of the two media and θ and θ' are the angles as measured from the normal. Figure 4 shows a ray of light leaving an object point P and striking the first surface of a lens at point P_1. It is refracted there, and proceeds to the second surface. All rays shown lie in the z, x-plane or meridional plane, which passes through the symmetry axis OZ. The amount of refraction is specified by Snell's law, eqn [2], which we shall now simplify. The sine of an angle can be approximated by the value of the angle itself, if this value is small when expressed in radians (less than 0.1 rad), and Snell's law simplifies to

$$n_1 \theta_1 = n'_1 \theta'_1 \qquad [3]$$



Figure 4 Ray passing through a double convex lens.

This is called the paraxial form of Snell's law; the word paraxial means 'close to the axis'. It turns out, however, that the Snell's law angles are not convenient to work with, and we eliminate them with the terms:

$$\theta_1 = \alpha_1 + \phi, \qquad \theta'_1 = \alpha'_1 + \phi \qquad [4]$$

where α_1 is the angle which the incident ray makes with the axis OZ, α'_1 is the corresponding angle for the refracted ray, and ϕ is the angle which the radius r_1 (the line from C to P_1) of the lens surface makes at the center of curvature C. This particular angle can be specified as

$$\sin \phi = \frac{x_1}{r_1} \qquad [5]$$

but using the paraxial approximation simplifies this to

$$\phi = \frac{x_1}{r_1} \qquad [6]$$

Substituting for the angles gives

$$n'_1 \alpha'_1 = \frac{n_1 - n'_1}{r_1} + n_1 \alpha_1 \qquad [7]$$

Notice that the distance from the point P_1 to the axis is labeled as either x_1 or x'_1. This strange notation leads to the trivial relation

$$x_1 = x'_1 \qquad [8]$$

and this can be combined with eqn [7] to obtain the matrix equation:

$$\begin{pmatrix} n'_1 \alpha'_1 \\ x'_1 \end{pmatrix} = \begin{pmatrix} 1 & -k_1 \\ 0 & 1 \end{pmatrix} \begin{pmatrix} n_1 \alpha_1 \\ x_1 \end{pmatrix} \qquad [9]$$

where the constant k_1 is called the refracting power of surface 1 and is defined as

$$k_1 = \frac{n'_1 - n_1}{r_1} \qquad [10]$$

To review the procedure for matrix multiplication, the first element $n'_1 \alpha'_1$ in the one-column product matrix is calculated by multiplying the upper left-hand corner of the 2×2 matrix with the first element of the one-column matrix to its right, obtaining $1(n_1 \alpha_1)$, and to this is added the product $-k_1 x_1$ of the upper right-hand element in the 2×2 matrix and the second member of the one-column matrix. This square matrix is called the refraction matrix R_1 for surface 1, defined as

$$R_1 = \begin{pmatrix} 1 & -k_1 \\ 0 & 1 \end{pmatrix} \qquad [11]$$

Next, we look at what happens to the ray as it travels from surface 1 to surface 2. As it goes from P_1 to P_2, its distance from the axis becomes

$$x_2 = x_1' + t_1' \tan \alpha_1' \qquad [12]$$

or using the paraxial approximation for small angles:

$$x_2 = x_1' + t_1' \alpha_1' \qquad [13]$$

Another approximation we shall use is to regard t_1' as being equal to the distance between the lens vertices V_1 and V_2. Using the identity:

$$\alpha_2 = \alpha_1' \qquad [14]$$

leads to a second matrix equation:

$$\begin{pmatrix} n_2\alpha_2 \\ x_2 \end{pmatrix} = \begin{pmatrix} 1 & 0 \\ t_1'/n_1' & 1 \end{pmatrix} \begin{pmatrix} n_1'\alpha_1' \\ x_1' \end{pmatrix} \qquad [15]$$

where the 2×2 translation matrix T_{21} is defined as

$$T_{21} = \begin{pmatrix} 1 & 0 \\ t_1'/n_1' & 1 \end{pmatrix} \qquad [16]$$

To get an equation which combines a refraction followed by a translation, we take the one-column matrix on the left side of eqn [9] and substitute it into eqn [15] to obtain

$$\begin{pmatrix} n_2\alpha_2 \\ x_2 \end{pmatrix} = T_{21}R_1 \begin{pmatrix} n_1\alpha_1 \\ x_1 \end{pmatrix} \qquad [17]$$

Note that the 2×2 matrices appear in right to left order and that the multiplication of two square matrices is an extension of the rule given above. This equation gives the location and slope of the ray which strikes surface 2 after a refraction and a translation. To continue the ray trace at surface 2, we introduce a second refraction matrix R_2 by expressing k_2 in terms of the two indices at this surface and the radius. Then eqn [17] is extended to give the relation:

$$\begin{pmatrix} n_2'\alpha_2' \\ x_2' \end{pmatrix} = R_2T_{21}R_1 \begin{pmatrix} n_1\alpha_1 \\ x_1 \end{pmatrix} \qquad [18]$$

This process can obviously be applied to any number of components. The product of the three 2×2 matrices in the above equation is known as the system matrix S_{21} and it completely specifies the effect of the lens on the incident ray passing through it. It is also written as

$$S_{21} = R_2T_{21}R_1 = \begin{pmatrix} b & -a \\ -d & c \end{pmatrix} \qquad [19]$$

where the four quantities a, b, c, and d are known as the Gaussian constants. They are used extensively in specifying the behavior of a lens or an optical system. We now state the sign and notation conventions which are necessary for the application of paraxial matrix methods:

1. Light normally travels from left to right.
2. The optical systems we deal with are symmetrical about the z-axis. The intersections of the refracting or reflecting surfaces with this axis are the vertices and are designated in the order encountered as V_1, V_2, etc.
3. Positive directions along the axes are measured from the origin in the usual Cartesian fashion, so that horizontal distances (that is, along the z-axis) are positive if measured from left to right. Angles are positive when measured up from the z-axis.
4. Quantities associated with the incident ray are unprimed; those for the refracted ray are primed.
5. A subscript denotes the associated surface.
6. If the center of curvature of a surface is to its right, the radius is positive, and vice versa.
7. There is a special rule for mirrors to be explained below.

Using the Gaussian Constants

Figure 5 shows the double convex lens of Figure 4 with the assumed locations of the cardinal points indicated. These positions, which we shall now determine accurately, are at distances designated as l_F, l_F', l_H, and l_H' and are measured from the associated vertex. The object position can be called t, a positive quantity which is measured to the right from object to the first vertex, or it can be called t_1 if measured in the opposite direction. For the first choice, the matrix specifying the translation from object to lens will have the quantity t/n_1 in its lower left-hand corner. However, it is both logical and convenient to use the first vertex as the reference point. Hence, we replace t/n_1 in the translation matrix with the quantity $-t_1/n_1$, and remember to specify t_1 as a negative number when calculating the image position. The equation connecting object and image is obtained by starting with this matrix, multiplying it by the system matrix of eqn [19], and finally by a translation matrix



Figure 5 Definitions of cardinal plane locations.

corresponding to the translation t'_2 from lens to image to obtain:

$$\begin{pmatrix} n'_2\alpha'_2 \\ x' \end{pmatrix} = \begin{pmatrix} 1 & 0 \\ t'_2/n'_2 & 1 \end{pmatrix}\begin{pmatrix} b & -a \\ -d & c \end{pmatrix} \times \begin{pmatrix} 1 & 0 \\ -t_1/n_1 & 1 \end{pmatrix}\begin{pmatrix} n_1\alpha_1 \\ x \end{pmatrix} \qquad [20]$$

where α or α_1 is the angle that the ray from the top of the object makes with the z-axis. This equation takes the initial value of the inclination α and of the position x of the ray leaving the object, and determines the final values, α' and x' at the image. The product of the three 2×2 matrices on the right-hand side can be consolidated into a single matrix called the object-image matrix $S_{P'P}$. Then eqn [20] can be written as

$$\begin{pmatrix} n'_2\alpha'_2 \\ x' \end{pmatrix} = S_{P'P}\begin{pmatrix} n_1\alpha_1 \\ x \end{pmatrix} \qquad [21]$$

and this matrix has the complicated form:

$$S_{P'P} = \begin{pmatrix} b + \dfrac{at_1}{n_1} & -a \\ \dfrac{bt'_2}{n'_2} + \dfrac{at_1t'_2}{n_1n'_2} - d - \dfrac{ct_1}{n_1} & c - \dfrac{at'_2}{n'_2} \end{pmatrix} \qquad [22]$$

If we put this matrix into the previous equation, we obtain an unsatisfactory result: the value of x' will depend on the angle α_1 made by the incident ray, as can be seen by multiplying the two matrices on the right side. The ratio of x' to x is called the magnification m; that is

$$m = \frac{x'}{x} \qquad [23]$$

A perfect image can be formed only if the magnification is determined solely by the object distance and the constants of the lens. To eliminate this difficulty, the lower left-hand element in the matrix, eqn [22] is required to be equal to zero, and the magnification is then:

$$m = \frac{x'}{x} = c - \frac{at'_2}{n'_2} \qquad [24]$$

The determinant of this matrix is unity, since it is the product of three matrices whose individual determinants are unity. It follows that

$$\frac{1}{m} = b + \frac{at_1}{n_1} \qquad [25]$$

so that

$$\begin{pmatrix} n'_2\alpha'_2 \\ x' \end{pmatrix} = \begin{pmatrix} 1/m & -a \\ 0 & m \end{pmatrix}\begin{pmatrix} n_1\alpha_1 \\ x \end{pmatrix} \qquad [26]$$

Using the fact that the lower left-hand element of the matrix eqn [22] is zero shows that

$$\frac{t'_2}{n'_2} = \frac{d + ct_1/n_1}{b + at_1/n_1}, \qquad \frac{t_1}{n_1} = \frac{d - bt'_2/n'_2}{-c + at'_2/n'_2} \qquad [27]$$

This equation connects the object distance t_1 with the image distance t'_2, both quantities being measured from the appropriate vertex. This relation is known as the generalized Gauss lens equation. It applies to all lens systems, no matter how complicated.

We can determine the location of the unit planes by letting $m = 1$. This t'_2 in eqn [27] is the location l'_H of the image space unit plane, and it becomes

$$l'_H = \frac{n'_2(c - 1)}{a} \qquad [28]$$

This relation expresses the location of the unit plane on the image side as the distance from V_2 to H'. Similarly, the location of H with respect of V_1 is

$$l_H = \frac{n_1(1 - b)}{a} \qquad [29]$$

To locate the focal planes, consider a set of parallel rays coming from infinity and producing a point image at F'. The terms containing t_1 in eqn [27] are much larger than d or b, and this relation becomes

$$l'_F = \frac{n'_2 c}{a} \qquad [30]$$

Letting t'_2 become infinite in the right-hand half of eqn [27], the location of F is given by the equation

$$l_F = \frac{-n_1 b}{a} \qquad [31]$$

The focal lengths f and f' shown in Figure 5 were defined earlier as the distances between their respective focal and unit planes. Hence

$$f' = l'_F - l'_H = \frac{n'_2}{a} \qquad [32]$$

and

$$f = l_F - l_H = \frac{-n_1}{a} \qquad [33]$$

If we let $n_1 = n'_2 = 1$ for air, these become

$$-f = f' = \frac{1}{a} \qquad [34]$$

The Gaussian constant a is thus the reciprocal of the focal length in air. Even when the lens is not in air, it is still true that $f' = -f$ if the lens is in a single medium. It is also true regardless of whether or not the lens is symmetric.

It is customary in optics to work with a consistent set of units, such as centimeters or millimeters, and the sign conventions used for x and y are the standard Cartesian rules. As mentioned above, curved surfaces which open to the right have a positive radius and vice versa. As an example, let a double convex lens have radii of 2.0 and 1.0, respectively, an index of refraction of 1.5, and a thickness of 0.5. These quantities are then denoted as

$$\begin{aligned} &r_1 = +2.0, \quad r_2 = -1.0, \quad t'_1 = t_2 = +0.5 \\ &n_1 = 1.0, \quad n'_1 = 1.5 = n_2, \quad n'_2 = 1.0 \end{aligned} \qquad [35]$$

By eqn [10]:

$$k_1 = \frac{n'_1 - n_1}{r_1} = \frac{1.5 - 1.0}{2.0} = 0.25 \qquad [36]$$

and

$$k_2 = \frac{1.0 - 1.5}{-1.0} = 0.50 \qquad [37]$$

The system matrix S_{21} is

$$\begin{aligned} S_{21} &= R_2 T_{21} R_1 \\ &= \begin{pmatrix} 1 & -0.50 \\ 0 & 1 \end{pmatrix} \begin{pmatrix} 1 & 0 \\ 0.5/1.5 & 1 \end{pmatrix} \begin{pmatrix} 1 & -0.25 \\ 0 & 1 \end{pmatrix} \\ &= \begin{pmatrix} 0.83 & -0.71 \\ 0.33 & 0.92 \end{pmatrix} \end{aligned} \qquad [38]$$

and we note that the determinant is

$$(0.83)(0.92) - (0.71)(-0.33) = 1.00 \qquad [39]$$

This property of the system matrix provides a very useful check on the accuracy of matrix multiplications. The locations of the four cardinal points can be determined from the formulas given above and their locations are shown in the scale drawing of Figure 6. Since we know how to locate the cardinal points of a lens, we are in a position to ray trace in a precise manner, using the method of Figure 3 and adding a third ray. After locating F, H, H', and F', we no longer need the lens; the cardinal planes with the proper separation are fully equivalent to the lens they replace. This is very much like what electrical engineers do when they replace a complicated circuit with a black box; this equivalent circuit behaves just like the original. Ray tracing becomes more complicated when we deal with diverging lenses (Figure 7), but the procedure gives above still applies. Parallel rays spread apart and do not come to a focus on the right-hand side of the lens. However, if the refracted



Figure 6 Positions of cardinal planes for an asymmetric lens.



Figure 7 Ray tracing for a planar-concave lens.



Figure 9 Formation of a virtual image by a concave lens.



Figure 8 Formation of a virtual image by a convex lens.

rays are extended backwards, these extensions will meet as indicated. This behavior can be verified quantitatively by using the formulas developed above. It will be found that *F* and *F*′ have exchanged places, but *H* and *H*′ retain their original positions inside the lens. If an object is placed between the focal point *F* and the first vertex of a convex lens (Figure 8), then our usual procedure produces two rays which do not intersect in image space. The ray from the object which is parallel to the axis is refracted downward so that it does not intersect the other ray in image space. However, the extensions to the left of these two rays meet to form an image which is erect, magnified, and virtual. This is the normal action of a magnifying lens; the image can be seen but cannot be projected onto a screen, unlike the real, inverted image of Figure 3. This ray tracing diagram confirms what would be seen when a double convex lens is used to magnify an object lying close to the lens. For the double concave lens of Figure 9, a parallel ray leaves an object point *P* and is refracted upward at the unit plane *H*′ in such a way that its extension, rather than the ray itself, passes through *F*′. The ray headed for *F* is refracted at *H* before it can reach the object-space focal plane and becomes parallel to the axis. The third ray, going from *P* to *H*, emerges at *H*′ parallel to its original direction and its extension to the left passes through the image point *P*′ already determined by the intersection of the other two rays. The resulting virtual image is upright and reduced. All three rays in this diagram behave exactly like the corresponding rays in Figure 3; the only change is the use of the extensions to locate the image. The eye receives the diverging rays from *P* and believes that they are coming from *P*′.

Nodal Points and Planes

Let a ray leave a point on the z-axis at an angle α_1, and have an angle α'_2 when it reaches image space.

Since $x = 0$ at the starting point, eqn [26] shows that

$$n'_2\alpha'_2 = n_1\alpha_1/m \qquad [40]$$

The ratio of the final angle to the initial angle in this equation is the angular magnification μ, which is then

$$\mu = n_1/mn'_2 \qquad [41]$$

The locations of object and image for unit angular magnification are called the nodal points, labeled as N and N'. The above definition shows that the linear and angular magnification are reciprocals of one another when object and image are in air or the same medium. The procedure that located the unit points will show that the nodal points have positions given by

$$\frac{l_N}{n_1} = \frac{(n'_2/n_1) - b}{a} \qquad [42]$$

and

$$\frac{l'_N}{n'_2} = \frac{c - (n_1/n'_2)}{a} \qquad [43]$$

When the two indices are identical, these relations are identical to those for the points H and H'. That is why the rays from P to H and H' to P' in Figure 3 are parallel.

Compound Lenses

A great advantage of the paraxial matrix method is the ease of dealing with systems having a large number of lenses. To start simply, consider the cemented doublet of Figure 10: a pair of lenses for which surface 2 of the first element and surface 1 of the second element match perfectly. The parameters of this doublet are given in the manner shown below.



Figure 10 Specification for a cemented doublet.

It is understood that the first entry under r is r_1, the second entry is r_2, and so on. Note that this doublet has only three surfaces; if the two parts were separated by an air space, producing an air-spaced doublet, then there would be four surfaces to specify. The values of the indices n' and the spacings t' are placed between the values of r. The constants of the doublet are then

$$\begin{array}{ccc} r & n' & t' \\ 1.0 & & \\ & 1.500 & 0.5 \\ -2.0 & & \\ & 1.632 & 0.4 \\ \infty & & \end{array} \qquad [44]$$

Note that surface 3, which is flat, has a radius of infinity. Numbering the vertices in the usual manner, the system matrix is

$$S_{31} = R_3T_{32}R_2T_{21}R_1 \qquad [45]$$

where

$$k_2 = (n'_2 - n_2)/r_2 = (1.632 - 1.500)/-2.0 \qquad [46]$$

Approximations for Thin Lenses

An advantage of paraxial matrix optics is the ease of obtaining useful relations. For example, combining the several expressions for the Gaussian constant a, we obtain:

$$a = -\frac{n_1}{f} = \frac{n'_2}{f'} = k_1 + k_2 - \frac{k_1k_2t'_1}{n'_1} \qquad [47]$$

and using the definitions of k_1 and k_2 with the lens in air leads to

$$\frac{1}{f'} = (n'_1 - 1)\left[\frac{1}{r_1} - \frac{1}{r_2} + \frac{(n'_1 - 1)t'_1}{n'_1r_1r_2}\right] \qquad [48]$$

which is the lensmakers' equation. It tells how to find the focal length of a lens from a knowledge of its material and geometry. This derivation is much more direct than what you will usually find. This equation becomes simpler when we are dealing with thin lenses – those for which the third term in brackets can be neglected by assuming that the lens thickness is approximately zero. Then

$$\frac{1}{f'} = (n'_1 - 1)\left[\frac{1}{r_1} - \frac{1}{r_2}\right] \qquad [49]$$

which is the form often seen in texts. We then realize that the original form is valid for lenses of any thickness, but the thin lens form can be used if the spacing is much less than the two radii. It is also seen that when the thickness is approximately zero, then

$$b = c = 1 \qquad [50]$$

and the unit planes have locations

$$l_H = l'_H = 0 \qquad [51]$$

Thus, they are now coincident at the center of the lens. A ray from any point on the object would pass undeviated through the geometrical center of the lens, as is often shown in the elementary books. These new values of the Gaussian constants give a system matrix of the form:

$$S_{21} = \begin{pmatrix} 1 & -1/f' \\ 0 & 1 \end{pmatrix} \qquad [52]$$

This matrix contains a single constant, the focal length of the lens, so that the preliminary design of an optical system is merely a matter of specifying the focal length of the lenses involved and using the resulting matrices to determine the object-image relationship. We also note that this matrix looks like a refraction matrix; the non-zero element is in the upper right-hand corner. This implies that the refraction–translation–refraction procedure that actually occurs can be replaced, for a thin lens, by a single refraction occurring at the coinciding unit planes. Ophthalmologists take advantage of the thin lens approximation by specifying focal lengths in units called diopters. The reciprocal of the focal length in meters determines its refraction power in diopters. For example, a lens with $f' = 10$ cm will be a 10 diopter lens. If two lenses are placed in contact, the combined power is the sum of the individual powers, for multiplying matrices of the above form gives the upper right-hand element as $(-1/f'_1 - 1/f'_2)$.

The Paraxial System for Design or Analysis

The material given in this article can serve as the basis for an organized way of taking the specifications of an optical system and using them to gain a full understanding of this system. We shall demonstrate it with a practical example which has some interesting features. Chemical engineers have long known that the index of refraction of a liquid can be determined by observing the empty bore of a thick glass tube with a telescope having a calibrated eyepiece and then measuring the magnification of the bore when the liquid flows through it. Consider a liquid with an index of 1.333 and a tube with bore radius of 3 cm, outer radius of 4 cm, and glass of index equal to 1.500. The first step is to specify the parameters of the optical system. These are the radii $r_1 = -3$, $r_2 = -4$ and the thickness $t'_1 = 1$, regarding the tube as a concentric lens with an object to its left; the indices $n_1 = 4/3$ (fractions are convenient), $n'_1 = 3/2$, $n'_2 = 1$. Calculating the elements of the two refraction matrices and the translation matrix, the system matrix is

$$S_{21} = \begin{pmatrix} 1 & -1/8 \\ 0 & 1 \end{pmatrix}\begin{pmatrix} 1 & 0 \\ 2/3 & 1 \end{pmatrix}\begin{pmatrix} 1 & 1/18 \\ 0 & 1 \end{pmatrix} \qquad [53]$$

Multiplying, the Gaussian constants are

$$a = 2/27, \quad b = 11/12, \quad c = 28/27, \quad d = -2/3 \qquad [54]$$

An important check is to verify that $bc - ad = 1$, as is the case here. The expressions given previously for the positions of the cardinal points then lead to the values

$$\begin{aligned} &l_H = 3/2, \qquad l'_H = 1/2, \qquad l_F = -16\ 1/2, \\ &l'_F = 14, \qquad l_N = -3, \qquad l'_N = -4 \end{aligned} \qquad [55]$$

These points are shown in Figure 11. Although the same scale has been used for both horizontal and vertical distances, this is usually not necessary; the vertical scale, which merely serves to verify the magnification, can be arbitrary. The entire liquid column is the object in question, but it is simpler to use a vertical radius as the object. Then the image, generated as described in all the previous examples,



Figure 11 Ray tracing diagram for a thick-walled glass tube.

coincides with the object and it is enlarged, erect, and virtual. We confirm the image location shown by using the generalized Gaussian lens equation, giving

$$\begin{aligned} t' &= [(-2/3) + (28/27)(-3)/(4/3)]/[(11/12) \\ &\quad + (2/27)(-3)/(4/3)] \\ &= -4 \end{aligned} \qquad [56]$$

and this agrees with the sketch. The denominator of this expression was shown to be the reciprocal of the magnification $1/m$ with a value of 3/4, and m itself can be calculated from t' as $c - at' = 4/3$; this is another important check on the accuracy of the calculation; the sketch obeys this conclusion, and the purpose of this analysis is confirmed.

Reflectors

To show how reflecting surfaces are handled with matrices, consider a plane mirror located at the origin and normal to the z-axis (Figure 12). The ray which strikes it at an angle α_1 leaves at an equal angle, resulting in specular reflection. Since $k = 0$ for a flat surface, the refraction matrix reduces to the unit matrix and by eqn [9]:

$$n'_1 \alpha'_1 = n_1 \alpha_1 \qquad [57]$$

This contradicts Figure 12, since α_1 and α'_1 are opposite in sign.

If, however, we specify that

$$n'_1 = -n_1 \qquad [58]$$



Figure 12 Specular reflection.

then the difficulty is removed. Hence, reflections involve a reversal of the sign on the index of refraction, and two successive reflections restore the original sign. For a mirror, the refraction power is

$$k_1 = \frac{n'_1 - n_1}{r_1} = \frac{-1-(1)}{r_1} = -\frac{2}{r_1} \qquad [59]$$

The system matrix for a single refracting surface thus becomes

$$S_{11} = R_1 = \begin{pmatrix} 1 & -k_1 \\ 0 & 1 \end{pmatrix} = \begin{pmatrix} 1 & 2/r_1 \\ 0 & 1 \end{pmatrix} \qquad [60]$$

with

$$a = -2/r_1, \qquad b = c = 1, \qquad d = 0 \qquad [61]$$

The connection between object and image can be expressed as

$$\begin{pmatrix} n'_1 \alpha'_1 \\ x'_1 \end{pmatrix} = \begin{pmatrix} 1 & 0 \\ t'/n'_1 & 1 \end{pmatrix} \begin{pmatrix} b & -a \\ -d & c \end{pmatrix} \begin{pmatrix} 1 & 0 \\ -t/n_1 & 1 \end{pmatrix} \begin{pmatrix} n_1 \alpha_1 \\ x_1 \end{pmatrix} \qquad [62]$$

and using the same procedure that was applied to eqns [28]–[31], the locations of the six cardinal points are

$$\begin{gathered} l_F = -n_1 b/a, \quad l'_F = n'_1 c/a \\ l_H = n_1(1-b)/a, \quad l'_H = n'_1(c-1)/a \qquad [63] \\ \frac{l_N}{n_1} = \frac{(n'_1/n_1) - b}{a}, \quad \frac{l'_N}{n'_1} = \frac{c - (n_1/n'_1)}{a} \end{gathered}$$

so that for the spherical mirror:

$$l_F = \frac{(-1)(1)}{-2/r_1} = \frac{r_1}{2} = l'_F \qquad [64]$$

$$l_H = l'_H = 0 \qquad [65]$$

and

$$l_N = \frac{-1-1}{-2/r_1} = r_1 \qquad [66]$$

but

$$\frac{l'_N}{-1} = \frac{1-(-1)}{-2/r_1}, \quad l'_N = r_1 \qquad [67]$$

Since r_1 is negative, these equations show that the unit points lie on the vertex, the foci coincide halfway between the center of curvature and the



Figure 13 Ray tracing for a concave mirror.

vertex, and the nodal points are at this center. The perfect focusing is a consequence of the paraxial approximation. The true situation is presented in **Geometrical Optics:** Aberrations. Ray tracing for this mirror uses the procedure developed for lenses, which applies to optical systems of any complexity. Figure 13 shows an object to the left of the center of curvature. The ray from P parallel to the axis goes to H' and then through F', while the ray through F goes to H and then becomes parallel to the axis. Their intersection at P' produces a real, inverted image. The third set of rays represents something different: it requires a knowledge of the nodal point locations. The ray from P to N should be parallel to the ray from N' to P', by definition; in this example, they meet this requirement by being colinear.

As an example of the power of matrix optics to simplify the design or analysis of an optical system involving lenses and mirrors, consider an object that is 15 units to the left of a converging lens, with focal length $f' = 10$. A concave mirror, of radius $r_1 = 16$, is 20 units to the right of the lens. The refraction power of the mirror is $k_1 = (-1-1)/-16 = 1/8$ and using the thin lens form of the system matrix, the combined matrix is

$$\begin{pmatrix} 1 & -1/8 \\ 0 & 1 \end{pmatrix}\begin{pmatrix} 1 & 0 \\ 20 & 1 \end{pmatrix}\begin{pmatrix} 1 & -1/10 \\ 0 & 1 \end{pmatrix} = \begin{pmatrix} -3/2 & 1/40 \\ 20 & -1 \end{pmatrix} \qquad [68]$$

This gives the constants a, b, c, and d, from which we find that the image is $-4\ 4/9$ units to the left of the mirror, its magnification is $-8/9$, and it is inverted. Compare the simplicity of this procedure with the usual way of doing this calculation, which involves first finding the image in the lens and then using that image as a virtual object.

Conclusion

It has been shown that the use of paraxial matrices provides a simple approach to an understanding of the kind of optical systems that provide perfect images. Further details and derivations of expressions given here will be found in the Further Reading below.

See also

Geometrical Optics: Aberrations.

Further Reading

Brouwer W (1964) *Matrix Methods in Optical Instrument Design*. New York: WA Benjamin.

Nussbaum A (1998) *Optical System Design*. Upper Saddle River, NJ: Prentice-Hall.

Aberrations

A Nussbaum, University of Minnesota, Minneapolis, MN, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The article **Geometrical Optics:** Lenses and Mirrors, describes image formation by components which are optically perfect. The images may be magnified or reduced and they may be erect or inverted, but they are otherwise faithful replicas of the object. This behavior is a consequence of ray tracing based on an approximate or paraxial form of Snell's law which we write as

$$n\theta = n'\theta' \qquad [1]$$

where n and n' are the indices of refraction on either side of an interface and θ and θ' are the angles of incidence and refraction. If, however, the following exact form of Snell's law:

$$n \sin\theta = n' \sin\theta' \qquad [2]$$

governs the ray behavior, as is the case when the rays have large inclinations with respect to the symmetry axis, then it is necessary to devise a more involved ray



Figure 1 Ray tracing in the meridional plane.

tracing procedure. Figure 1, which shows the first surface of a lens, will be used to explain how this procedure works. A ray leaves the object point P and strikes the lens surface at the point P_1. Rays which lie completely in the plane ZOX are said to be meridional; this is the plane which passes through the symmetry axis, just as meridians on the Earth's surface are determined by planes through the geographic axis. By regarding the various distances in the figure as vectors, it is possible to start with the initial coordinates of the ray and with the direction-cosines which specify its slope and find the coordinates of the point P' where the ray strikes the lens surface. A derivation of the equation governing this process will be found in the text of A Nussbaum (see Further Reading). This derivation involves only elementary algebra and vector analysis, and will be found simpler than the usual textbooks treatment of ray tracing procedures. The equation is

$$T_1 = \frac{F}{-E + \sqrt{E^2 - c_1 F}} \qquad [3]$$

where

$$E = Bc_1/2 = c_1[(z - v_1)N + xL] - N \qquad [4]$$

and

$$F = Cc_1 = c_1\left[(z - v_1)^2 + x^2\right] - 2(z - v_1) \qquad [5]$$

Knowing the coordinates z and x of the starting point P of the ray, as well as its starting cosines N and L, plus the curvature c_1 or radius $r_1 = 1/c_1$ of the lens surface and the location v_1 of the surface's vertex, we can readily calculate the length T_1 of the ray. Then its components on the two axes give the coordinates of P'. Next, we need to find the slope of the ray after it is refracted at the lens surface, and this can be calculated from Snell's law combined with the behavior of the incident and refracted rays regarded as vectors. Again we invoke the reference cited above for a derivation of the equations giving the value of the direction-cosines after refraction; these expressions are

$$n_1' N_1' = K_1/c_1 + n_1 N_1 - K_1 z_1 \qquad [6]$$

and

$$n_1 L_1' = n_1 L_1 - K_1 x_1 \qquad [7]$$

where K_1 is known as the refracting power and has the definition

$$K_1 = c_1(n_1' \cos\theta' - n_1 \cos\theta) \qquad [8]$$

The ray can now be traced to the next surface knowing the lens thickness, and then to the image plane. These two sets of equations, when incorporated into a computer program of about two dozen lines, will trace meridional rays to any desired accuracy through an optical system containing an arbitrary number of lenses and spherical reflectors. As an example, consider a symmetric double convex lens with radii of 50 units at surface 1, −50 units at surface 2, a thickness of 15 units, and an index of 1.50. Rays parallel to the axis – one at 0.2 units above the axis, a second one at 2 units above the axis, and a third one at 20 units above the axis – are started well to the left and traced to the paraxial focal plane, which is at 47.368 units from the second surface. The ray that is 0.2 units above the axis will cross the focal plane at the axis; this is a paraxial ray, passing through the paraxial focal point F'. The ray which is 2 units above the axis crosses the focal plane slightly below the focal point, and is therefore not quite paraxial, while the ray which starts at 20 units above the axis falls well short of the focal point, intersecting the axis before it reaches the focal plane. This behavior indicates that the lens possesses a defect known as spherical aberration and these calculations imply that spherical aberration should be defined as the failure of nonparaxial rays to conform to the behavior of paraxial rays. This definition does not appear in optics texts, and the few definitions that are given appear to be incorrect. As clearly indicated in **Geometrical Optics:** Lenses and Mirrors, the focal point of a lens is strictly a paraxial concept and it is a constant, obtainable from the parameters of the lens or lens system. It is meaningless to speak of a focal point as defined by a pair of nonparaxial rays; this infinite set of ray-pairs determines a corresponding number of intersection points, all of which fall short of the true focal point F'. This situation is nicely illustrated by the next figure, which shows a large number of parallel rays, the central ones being paraxial and the others behaving differently. The rays which are very close to the axis will meet as expected at the focal point F'. The rays a little farther out – the intermediate rays – will cross the axis just a little to the left of F', and those near the edge of the lens – the *marginal* rays – will fall very short, as indicated. Rotating this diagram about the axis, we realize that spherical aberration produces a very blurry circular image at the paraxial plane. The three-dimensional envelope of the group of rays produced by this rotation is known as the caustic surface and the narrowest cross-section of this surface, slightly to the left of the paraxial focal plane, is called the circle of least confusion. If this location is chosen as the image plane, then the amount of spherical aberration can be reduced somewhat. Other methods of improving the image will be considered below. Figure 2 was obtained by adding a graphics step to the computer program described above. Figure 3 shows how to define spherical aberration quantitatively. Two kinds of aberration are specified in this figure. The place where the ray crosses the axis, lying to the left of F', is at a distance, measured from the paraxial focus, called the longitudinal spherical aberration (LSA), while the distance below the axis at the focal plane is the transverse spherical aberration (TSA). To reduce this aberration, note in Figure 2 that the amount of refraction at the two surfaces of the lens for marginal rays is not the same. Equalizing the refraction at the two surfaces will improve the situation. Suppose we alter the lens while keeping the index, thickness, and focal length constant; only the radii will change. This can be done if the new radii satisfy the paraxial equation giving the focal length in terms of the lens constants. The process of varying the shape of lens, while holding the other parameters constant, is called *bending the lens*. This can be easily accomplished by a computer program, obtaining what are known as optimal shape lenses, which are commercially available. To study their effect on spherical aberration, define the shape factor σ of a lens as

$$\sigma = \frac{r_2 + r_1}{r_2 - r_1} \qquad [9]$$

from which $\sigma = 0$ for a symmetric lens ($r_1 = -r_2$). Figure 4a shows the monitor screen for a symmetric lens, and Figure 4b illustrates the result of lens bending. This lens has had the curvature of the first surface raised and the second surface has been flattened to keep the focal length constant. Let us now consider what lens designers can do about spherical aberration. Brouwer in his book (see Further Reading) gives the specifications for a cemented doublet consisting of a double convex lens followed by a lens with two concave surfaces. The longitudinal spherical aberration of the front lens alone varies as shown in Figure 5. The way that the designer arranged for the marginal rays to meet at the paraxial focus, rather than falling short, was to recognize that a diverging lens following the front element would refract the rays away from – rather than closer to – the axis. When this second component is added, we would expect the behavior shown in Figure 6. Note that the value of LSA for the doublet has been enormously reduced, as indicated by the horizontal scale change. Spherical aberration can be reduced in more elaborate systems as part of the design process. Telescopes, in particular, make use of corrector plates which are placed in front of the large mirrors.



Figure 2 Spherical aberration for parallel meridional rays.



Figure 3 Definitions of transverse and longitudinal spherical aberration.

Coma

We have seen how to trace nonparaxial, meridional rays and found that spherical aberration appears because the intermediate and marginal rays do not behave like the central rays. We now wish to deal


First radius = 50
Second radius = –58
Shape factor = 8
LSA = –14.84688
Vertical horizontal arrows change first radius by 5/8.5 units
any other key terminates
(a)
First radius = 32
Second radius = –125
Shape factor = .5923567
LSA = –9.112822
Vertical horizontal arrows change first radius by 5/0.5 units
any other key terminates
(b)

Figure 4 Lens bending as performed numerically.



Figure 5 Spherical aberration for a single lens.



Figure 6 Reduction of spherical aberration by a doublet.



Figure 7 Configuration used to illustrate coma.

with rays that do not lie in a meridional plane; these are nonmeridional or skew rays. Calculating the behavior of such a ray would appear to be a complicated problem, but it turns out to be a simple extension of what has already been accomplished. Let a skew ray start at an arbitrary point in space with coordinates x, y, and z and let it have direction cosines L, M, and N with respect to OX, OY, and OZ. The points P and P_1 in Figure 1 are now out of the plane ZOX and when the vectors in this figure are expressed as the sum of three, rather than two, components, the equations given above for meridional rays acquire terms in y and M which have the same form as those for x and L. Now trace a set of skew rays chosen to lie on a cylinder (Figure 7) which is centered about the z-axis of a lens, so that all the rays are meridional. These rays are fairly far from the axis, so that they are also nonparaxial, but they all meet at a common image point, forming a cone whose apex is this image point. Then give this cylinder a downward displacement while holding fixed the intersection point of each ray with the dotted circle on the front of the lens. The tilting of the cylinder changes all its rays – except the top and the bottom rays – from meridional to skew. In addition, the cone on the image side will then tilt upwards; it should not change in any other way if the skew rays continue to meet at a well-defined apex. But this is not what happens in a simple lens, as will now be explained.



Figure 8 Starting a coma plot.



Figure 9 Coma as calculated numerically.


X
X
F′
Z
Y
F′
60°
Paraxial image plane (side view)
Paraxial image plane (plan view)

Figure 10 Customary way of illustrating coma.

Let the top and bottom meridional rays meet at a point *P* in image space (Figure 8) and use this point to determine the location of an image plane. The skew ray just below the uppermost ray in Figure 7 will pass through this plane fairly close to the intersection point. Let us guess (and confirm later) that it will pass through a point slightly to the right of *P* and a little below it, as we observe this plane from the lens position. This is point 1 in Figure 8. The next skew ray on the front of the lens will strike the image plane still farther below and to the right, producing point 2 in the figure. As we continue to trace these rays down the front half of the circle, we realize that a ray almost at the bottom of Figure 7 will have to be very close to the lower meridional ray and that its image point is just below but to the left of *P*; this is the point labeled 'next-to-last' in Figure 8. All of these points join to form a closed curve. The back halves of the dotted circle and of the ray cylinder are not shown in the figure, but since we are again starting at *P* in Figure 8, the pattern will repeat itself. That is, we get a second closed curve which – by symmetry – should be identical to the first curve. This is a most unusual effect; double-valued phenomena are quite rare. To confirm this prediction, we use the skew ray equations, and trace the pattern formed by a set of concentric cylinders of different sizes. The appearance of the coma pattern generated by the computer is shown in Figure 9. Each half-circle on the front side of the lens produces a closed figure (an approximation to a circle) as an image. If coma were the only aberration (when it is called ideal coma), the plots would be the perfect, coinciding circles of Figure 10. The comet-like shape explains where the name comes from. We can picture the generation of these circles in the way shown in this figure. The ray through the geometrical center of the lens produces a point in the paraxial focal plane. The top and bottom rays (the meridional rays) from the circles of increasing size produce points which define image planes that are successively closer to the lens; this is a consequence of spherical aberration. Moving the top ray parallel to itself and along the half-circle generates the image plane pattern. The lines tangential to the coma circles make an angle of 60° with each other, as can be seen by measurement on the computer output. Most optics books look at coma in a way different from that given here. Coma has been defined by WJ Smith (see Further Reading) as the variation of magnification with aperture, analogous to the definition of spherical aberration as the variation of focal length with aperture. And as was previously mentioned, focal length and magnification are purely paraxial concepts, not applicable to the description of aberrations. The definition that comes from the arguments given above is that coma is the failure of skew rays to match the behavior of meridional rays, just as spherical aberration is the failure of meridional rays to match the behavior of paraxial rays. Most texts show coma in its ideal form.

Astigmatism

We have shown that spherical aberration is the failure of meridional rays to obey the paraxial approximation and coma is the failure of skew rays to match the behavior of meridional rays. To see the connection between these two aberrations, consider the object point *P* of Figure 11. This very complicated diagram can actually be very helpful in understanding the third of the five geometrical aberrations. Let *P* be the source of a meridional fan: this is the group of rays with the top ray labeled PA and the bottom ray is PB. If the lens is completely corrected for spherical aberration, this fan will have a sharp image point P'_T lying directly below the z-axis. Now let *P* also be the source of a fan bounded by the rays PC and PD. This fan is at right-angles to the other one; we can think of these rays as having the maximum skewness possible. If the lens has no coma, this fan also will produce a sharp image point P'_s which, for a converging lens, will be farther from the lens than the tangential focal point. In other words, even though the lens has been fully corrected for both aberrations, the two corrections will not necessarily produce a common image. In the figure, the meridional fan is called a tangential fan and the skew fan is called a sagittal fan; these are the terms commonly used by lens designers. The failure of the sagittal and tangential rays to produce a single image in a lens corrected for both spherical aberration and coma is known as astigmatism. Astigmatism, coma, and spherical aberration are the point aberrations that an optical system can have. We have already noted that spherical aberration is the only one that can be associated with a point on the z-axis; the others require an off-axis object. Astigmatism is very common in the human eye; to see how it shows up, look at the sagittal image point P'_s of Figure 11. This point is a distance z_s, from the x,y-plane. A plane through this point will have a line image on it, the sagittal line, due to the tangential fan, which has already come to a focus and is now diverging. The converse effect, producing a tangential line, occurs at the other image plane. If we locate an image plane halfway between the two, then both fans contribute to the image and in the ideal case it will be a circle. As the image plane is moved forwards or backwards, these images become ellipses and eventually reduce to a sagittal or a tangential line, as shown in Figure 12. Because there are two different



Figure 11 Tangential and sagittal fans displaying astigmatism.



Figure 12 Astigmatic image patterns.



Figure 13 Image degraded by astigmatism.

image planes, an object with spokes (Figure 13) will have an image for which the vertical lines are sharp and the others get gradually poorer as they become more horizontal, or vice versa, depending on which image plane is chosen. Eye examinations detect astigmatism if the spokes appear to go from black to gray. This example of the effect of astigmatism was often based on a radial pattern of arrows, which explains the origin of the word sagittal, derived from the Latin 'sagitta' for arrow.

Curvature of Field and Distortion

Having covered the three point aberrations, there are two lens defects associated with extended objects. If we move the object point *P* in Figure 11 closer to or farther from the *z*-axis, we would expect the positions of the tangential and sagittal focal planes to shift, for it is only when the paraxial approximation holds that these image points are independent of *x*. Hence, we obtain the two curves of Figure 14, which shows what astigmatism does to the image of a two-dimensional object. If the astigmatism could be eliminated, the effect would be to make these curved image planes coincide, but we have no guarantee that the common image will be flat, or paraxial. The resulting defect is called Petzval curvature or curvature of field. For a single lens, the Petzval surface can be flattened by a stop in the proper place, and this is usually done in inexpensive cameras. Petzval curvature is associated with the *z*-axis. If we take the object in Figure 11 and move it along the *y*-axis, then all rays leaving it are skew and this introduces distortion, the aberration associated with the coordinates normal to the symmetry axis. Distortion is what causes vertical lines to bulge outward (barrel distortion) or inward (pincushion distortion) at the image plane, as shown in Figure 15. A pinhole camera will have no distortion, since there are no skew rays, and a single thin lens with a small aperture will have very little. Placing a stop near the lens to reduce astigmatism and curvature of field introduces distortion because, as shown in Figure 16a, the rays for object points far from the axis are limited to off-center sections of the lens. The situation in this figure corresponds to barrel distortion; placing the stop on the other side of the lens produces pincushioning. Distortion can be



Figure 14 Petzval of field curvature.



Figure 15 Barrel and pincushion distortion.



Figure 16 (a) Distortion-creating stop. (b) Symmetric-component lens that reduces distortion.



Figure 17 Reduction of astigmatism through design.

therefore reduced by a design which consists of two identical groupings (Figure 16b), with the iris diaphragm placed between them; the distortion of the front half cancels that of the back half. Figure 17 shows the output for a calculation using approximate formulas rather than exact ray tracing. Note that the designer has arranged for astigmatism to vanish at the lens margin. This example indicates the nature of astigmatism in a system for which the coma and the spherical aberration are low but not necessarily zero; it is the failure of the tangential and sagittal image planes to coincide.

Nonspherical Surfaces

So far, we have considered optical systems that use only spherical or plane reflecting and refracting surfaces. However, many astronomical telescopes use parabolic and hyperbolic surfaces. In recent years, nonspherical or aspheric glass lenses have become more common because they can be mass produced by computer-controlled machinery and plastic lenses can be molded with very strict tolerances. Ray tracing procedures given above can easily be extended to the simplest kind of aspheric surfaces: the conic sections. Iterative procedures may be applied to surfaces more complicated than the conic sections. A well-known example is the curved mirror; a spherical reflecting surface will have all the aberrations mentioned here, but a parabolic mirror will bring parallel rays to a perfect focus at the paraxial focal point, thus eliminating the spherical aberration. Headlamp reflectors in automobiles are a well-known example. A plano-convex lens with this defect corrected will be one whose first surface is flat and whose second surface is a hyperbola with its eccentricity equal to the index of refraction of the glass composing the lens. One form of astronomical telescope, which has a large primary concave mirror to collect the light and reflect it back to a smaller secondary convex mirror, is the Ritchey–Chrétien design of 1924. Both mirrors are hyperbolic in shape, completely eliminating spherical aberration. This is the design of the Hubble space telescope. The two-meter diameter primary mirror, formed by starting with a spherical mirror and converted to a hyperbola by computer-controlled polishing, was originally fabricated incorrectly and caused spherical aberration. From a knowledge of the computer calculations, it was possible to design, build, and place in orbit a large correcting optical element which removed all the aberrations from the emerging image.

Conclusion

The three-point aberrations and the two extended object aberrations have been defined and illustrated. Simple ways of reducing them have been mentioned, but the best way of dealing with aberrations is in the process of lens design. In addition, there is a completely separate defect known as chromatic aberration. All the above calculations are based on ray tracing for a single wavelength (or color) of visible light. However, the index of refraction of a transparent material varies with the wavelength of the light passing through it, and a design good for one value of the wavelength will give an out-of-focus image for any other wavelength. It has been known for many years that an optical system composed of two different kinds of glass will provide a complete correction for two colors – usually red and blue – and other colors will be partially corrected. Such lenses are said to be achromatic. For highly demanding applications, such as faithful color reproductions



Figure 18 High-power high-resolution microscope objective.

of works of art, it is possible to design elaborate and expensive lenses which correct for yellow light as well. This kind of optical system is said to be apochromatic. With perfect imaging at the two ends and the middle of the visible spectrum, the color error elsewhere is virtually nonexistent. As an example of a design which is free of all aberrations – geometric and chromatic – Figure 18 shows the ray trace for a high-power aberration-free and apochromatic microscope objective. Note that the trace shows parallel rays brought to a focus inside the cover glass; in use, the light source would be a point on the slide and the light would converge at the eyepiece.

See also

Geometrical Optics: Lenses and Mirrors; Prisms.

Further Reading

Brouwer W (1964) *Matrix Methods in Optical Instrument Design*. New York: WA Benjamin.
Laikin M (1990) *Lens Design*. New York: Marcel Dekker.
Nussbaum A (1998) *Optical System Design*. Upper Saddle River, NJ: Prentice-Hall.
Nussbaum A and Phillips RA (1976) *Contemporary Optics for Scientists and Engineers*. Englewoods Cliffs, NJ: Prentice Hall.
Smith WJ (1990) *Modern Optical Engineering*, 2nd edn. New York: McGraw-Hill Book Co.

Prisms

A Nussbaum, University of Minnesota, Minneapolis, MN, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Prisms are solid structures made from a transparent material (usually glass). Figure 1 shows the simplest type of prism – one that has many uses. The vertical sides are two identical rectangles at right angles to each other and a larger third rectangle is at 45° to the other two. The top and bottom are 45°–45°–90° triangles. The most common applications of prisms are:

1. To bend light in a specified direction
2. To fold an optical system into a smaller space
3. To provide proper image orientation
4. To combine or split optical beams, using partially reflecting surfaces
5. To disperse light in optical instruments such as spectrographs.

Single Prisms as Reflectors

A prism like that of Figure 1 can act as a very effective reflector; it is more efficient than a mirror since there is no metal coating to absorb light. Figure 2 shows a light ray entering the prism at right angles to one of the smaller sides, reflected at the larger side, and emerging at right angles to the other small side. The path shown is determined by Snell's law. This law has the form:

$$n \sin \theta = n' \sin \theta' \qquad [1]$$



Figure 1 A 45–45–90 degree prism.



Figure 2 Total internal reflection by a prism.

This indicates that a ray of light making an angle θ to the normal at the interface between media of indices of refraction n and n', will be refracted and the angle to the normal becomes θ'. Notice that the light ray strikes the surface where the reflection takes place at an angle of 45° to the normal; this angle is too large to permit it to emerge from the prism after refraction. To understand why, we recognize that when the ray is able to leave the glass, Snell's law requires that the emerging angle be larger than the incident angle. The largest possible incident angle – known as the critical angle – will correspond to an emerging angle of 90°; that is, this ray will be parallel to the interface. For an index of 1.50, as an example, the critical angle θ_c satisfies Snell's law in the form:

$$1.5 \sin \theta_c = 1.0 \sin 90° \qquad [2]$$

from which $\theta_c = 41.8°$. The ray shown in the figure will therefore remain in the glass. Furthermore, since the indices appearing on both sides of Snell's law are now those of the glass, then the incident and refracted angles must be identical, and the prism reflects the ray in the same way that a mirror would. This phenomenon is known as total internal reflection.

This prism has an important application as an optical component of a fingerprint machine, whose action depends on modifying the total internal reflection which normally occurs. Figure 3 shows the prism and the reflecting behavior of Figure 2, with a person's finger pressed against the long side. When the ray strikes a place on the surface corresponding to a valley in the fingerprint pattern, the index at this region is that of air, and the ray is reflected in the usual manner. But a ray striking a portion of the prism which lies immediately below a raised section of the skin will make an angle with the normal which is now smaller than the critical angle, since the index is much greater than that of air, so that the ray will cross the interface and be absorbed by the finger. The reflected beam, with the fingerprint pattern sharply reproduced, is sent to a detector and the resulting signal goes to a computer, where it is processed and used to drive a printer. The fingerprint cards generated by this kind of equipment are sharper than those done by the traditional smeared-ink method. It is possible to observe the phenomenon just described by looking at your fingers while holding a glass of water – the fingerprints will show up in an enhanced manner. In addition to the better quality, the manufacturer of one version of this equipment has incorporated a feature in their computer program which can detect attempts by the person being fingerprinted to degrade the image.



Figure 3 Use of a prism to produce a fingerprint.



Figure 4 A pentaprism.

A more elaborate single prism – one with five sides – is the pentaprism of Figure 4, used extensively in single lens reflex cameras. This prism does not take advantage of the total internal reflection process, as described above. Below the bottom face is a mirror at a 45° angle. Light from the camera's lens is reflected upward and emerges from the left-hand face where the scene being photographed is observed by the eye.



Figure 5 Action of coated faces of a pentaprism.



Figure 6 Amici prism.

Since there are two reflections, the reversal caused by a single mirror is eliminated. The camera's mirror is hinged and when the exposure button is pressed, it flies up and the incoming light can reach the film. The two reflecting faces, which lie at an angle of 45° to one another (Figure 5), are coated. To see why this is necessary, note that the two angles in the isosceles triangle formed by the light ray and the face extensions must equal (180° − 45°)/2 or 67.5°. This ray must then lie at an angle of 90° − 67.5° to the normal, or 22.5°, which is much less than the critical angle needed for reflection.

There are at least a dozen other forms of prism which have been designed and used. For example, the Amici prism (Figure 6) is a truncated right-angle prism with a roof section added to the hypotenuse face. It splits the image down the middle and thereby interchanges the right and left portions. These prisms must be very carefully made to avoid producing a double image. One use is in telescopes to correct the reversal of an image.

Double Prism Reflectors

Another extensive application of prisms is their use in pairs as components of telescopes and binoculars. The most widely used is a pair of Porro prisms: two right angle prisms arranged as shown in Figure 7. The double change in direction has two effects; it eliminates image reversal and it shortens the spacing between objective and eyepiece lenses, making the binoculars lighter and more compact. It is possible to calculate how light rays behave in Porro prisms with a ray tracing procedure. This method involves the use of 4×4 matrices and its development is rather complicated. A simple understanding of the way light passes through this optical component can be based on Figure 8, which shows the two prisms separated for clarity. An arbitrary ray (the heavy line) coming from the object will be reflected at a 45° angle at each of the four faces that it strikes. Using two line segments at right angles as an object, the ray from the top of the vertical arrow and the ray from the end of the horizontal arrow will behave as indicated. The image is then identical to the object but rotated by 180°. Since the optics of the binoculars – the combined effect of the objective and the eyepiece – result in an inverted image, the Porro prism corrects this problem.



Figure 7 A pair of Porro prisms.



Figure 8 Action of Porro prisms.

Prisms as Instruments

Prisms are the crucial optical element in many laboratory instruments. To show how they can be used to measure the index of refraction of transparent materials – solids or liquids – consider the prism of Figure 9, with apex angle A. Light comes to the prism at an incident angle i, enters the prism at the angle of refraction r, crosses the prism and is refracted a second time when it emerges, the associated angles being designated as r' and i'. When the ray leaves the prism, it is traveling in a direction which represents an angular deviation δ from its original orientation. This deviation is the sum of the individual changes in direction at each face, or

$$\delta = (i - r) + (r' - i') \qquad [3]$$

For the triangle formed by the projected normals, which meet at the angle A:

$$r = r' + A \qquad [4]$$

Hence

$$\delta = i + i' - A \qquad [5]$$

The minimum value of the deviation is an important property of the prism; we find it by differentiation to obtain:

$$\mathrm{d}\delta = \mathrm{d}i + \mathrm{d}i' = 0 \qquad [6]$$

Differentiation of the form of Snell's law valid at each interface, namely:

$$\sin i = n \sin r, \quad \sin i' = n \sin r' \qquad [7]$$



Figure 9 Calculation of prism deviation.

gives

$$\mathrm{d}i = n \cos r \, \mathrm{d}r / \cos i \qquad [8]$$

$$\begin{aligned} \mathrm{d}i' &= n \cos r' \, \mathrm{d}r' / \cos i' \\ &= n \cos r' \, \mathrm{d}r / \cos i' \end{aligned} \qquad [9]$$

where $\mathrm{d}r'$ can be replaced by $\mathrm{d}r$, as obtained from the equation connecting r, r', and A. It now follows that:

$$\begin{aligned} \mathrm{d}\delta = n\Big[&\left\{\cos r / \sqrt{(1 - n^2 \sin^2 r)}\right\} \\ &- \left\{\cos(A - r) / \sqrt{(1 - n^2 \sin^2(A - r)}\right\}\Big]\mathrm{d}r = 0 \end{aligned} \qquad [10]$$

from which

$$\begin{aligned} &\cos^2 r\left\{1 - n^2 \sin^2(A - r)\right\} \\ &\quad = \cos^2(A - r)\{1 - n^2 \sin^2 r\} \end{aligned} \qquad [11]$$

or:

$$\cos^2 r = \cos^2(A - r) \qquad [12]$$

and finally:

$$r = A/2, \quad r' = A/2, \quad i' = i \qquad [13]$$

The differentiation thus leads to the conclusion that the ray enters and leaves the prism in a symmetrical manner. The amount of deviation is now:

$$\delta = 2i - A \qquad [14]$$

or:

$$i = (\delta + A)/2 \qquad [15]$$

and:

$$n = \sin i / \sin r = \sin\{(\delta + A)/2\} / \sin(A/2) \qquad [16]$$

Using this expression to calculate n as a function of δ, it is found that δ is a minimum, so that a measurement of the minimum deviation produced by a prism gives the value of its index of refraction in a direct and accurate way. This method can also be used for liquids; a triangular glass cell with walls of reasonable thickness is made very accurately and used to measure δ. The refraction due to the walls does not affect the measurement, since the refraction occurring at the entrance wall is equal but opposite to that at the exit wall.

The description of prism behavior given so far assumes that we are dealing with monochromatic light; that is light of a single wavelength or single



Figure 10 A prism spectrometer.

color in the visible spectrum. However, the index *n* of a prism varies with wavelength and white light passing through a prism will undergo dispersion – each component of a beam will emerge at a different angle and can be observed. The prisms that are part of expensive glass chandeliers display such an effect. This property of a prism is used in spectrometers – instruments which can measure the wavelength of light. Figure 10 shows a schematic diagram of this kind of instrument of high quality. Note that the light is brought into and taken out of the spectrometer with doublets. As shown in **Geometrical Optics:** Aberrations, doublets can be designed to be achromatic – that is, they focus light throughout the spectrum in approximately the same way. Various kinds of spectrometers have been put into use, with the ability to resolve closely spaced wavelengths being a crucial factor in the design.

See also

Geometrical Optics: Aberrations; Lenses and Mirrors.

Further Reading

Brouwer W (1964) *Matrix Methods in Optical Instrument Design*. New York: WA Benjamin.

Longhurst RS (1967) *Geometrical and Physical Optics*, 2nd edn. New York: John Wiley & Sons.

MIL-HDBK-141 (1962) *Military Standardization Handbook*. Washington, DC: US Government Printing Office.

H

HOLOGRAPHY, APPLICATIONS

Contents

Art Holography
High-Resolution Holographic Imaging and Subsea Holography
Holographic Recording Materials and Their Processing

Art Holography

A Pepper, Shearwater Foundation, Nottingham, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Holography captures the phase and amplitude of light reflected from, or transmitted through, an object. In visual terms it captures 'true' three-dimensional space and any objects which are placed within that space. This is very different from the various optical illusions, including perspective drawing and painting, which 'trick' the eye into thinking it is seeing a dimensional image on a flat surface. Not surprisingly, artists have been intrigued by display holography since reports about it became more public in the early 1960s.

Since much of the information about the holographic process was originally published in professional scientific and optics journals, which the artistic community rarely read, or had access to, the transfer of practical information from optical scientist to visual artist was slow. As less technical reports about holography began to appear in publications, such as *Scientific American*, and art journals, such as *Leonardo*, more artists became aware of the possibilities holography offered. It is now over 50 years since its invention by Dennis Gabor, and art holography can be found in public and private collections around the world, ranging from major museums, through academic art galleries to large individual collections.

For the purpose of this article, holography can be defined as a section of a broad optical field, encompassing display holograms produced by artists, creative individuals, and groups. These works are often produced through independent or self-driven research, but can also be the result of a commissioned project. Holographic art works tend not to be produced specifically for commercial gain (although some do sell for large amounts and can be editioned in the same way prints or photographs, to increase their salability or make them more accessible to a wider audience). It is incredibly difficult to assess the number of artists working in this field today, as no specific research has been carried out, but it can be estimated as between 50–100 individuals worldwide, which includes those who have shown work in curated group and solo exhibitions. This relatively small number has made an enormous impact and includes artists who have made holography their main medium of expression, as well as those, more established in other media, who have extended their creative vocabulary by embracing the holographic process. Salvador Dali for example, had holograms made of his sculptural compositions in the early 1970s, and Bruce Nauman used the process to capture a series of self-portraits in the 1960s. Apart from these well known and established contemporary artists, much of the pioneering work has been driven by individuals who have concentrated on holography as their medium of choice.

Some artists build their own optical studio in which to experiment in a hands-on environment, some collaborate with scientific and research establishments, where the work, facilities and expertise is shared, and others design and supervise the production of their work which is produced for them by a commercial company. All of them produce a unique contribution to the visual arts.

Early Exploration

Holography offers a unique method of recording and reproducing three dimensions on a flat surface without the need for special glasses (for stereoscopic viewing), lenses (such as lenticular viewing) or linear perspective which, since the Renaissance, has been our main method of tricking the eye into believing that an image recedes into the distance and displays three dimensions.

Many of the very early works produced by artists concentrated on the obvious still life nature of the medium and explored the unusual phenomenon of objects ‘frozen’ in holographic space. Almost all of these early works were recorded using continuous wave helium neon lasers, either in scientific/research facilities, which artists had arranged to use, or in collaboration with established scientists and optical imaging researchers.

As early as 1969, British artist Margaret Benyon was experimenting with this new medium. Her laser transmission hologram ‘Picasso’, is a recording of images taken from Pablo Picasso’s painting ‘Demoiselles D’Avignon’. Here Margaret Benyon took a copy of the painting, cut out the characters, placed them in a three-dimensional spatial arrangement, with real objects, and then made a hologram of this ‘scene’. Picasso attempted to show, through many of his paintings, multiple views of the same subject on a two-dimensional surface, one of the main thrusts of Cubism in the late twentieth century. Benyon achieved this in ‘real space’ by recording a hologram of the flat reproductions. By doing so, she demonstrated that holography automatically achieved what Picasso, and many other key contemporary visual artists, had been trying to do for years.

Holographic Black Holes

It has been known, from the very early days of holographic research that, when using a continuous wave laser to record a hologram, if any object in the scene moves more than half the wavelength of light, no interference pattern will be produced and therefore no recording of the object will take place. Unlike photography, where if an object moves during the exposure, it will become blurred, in holography it will simply not be recorded. Clearly, if no recording can be made, optical researchers working with holography, while noting the phenomenon, would not necessarily feel the need to make holograms which would fail. Several artists, on the other hand, not confined by research deadlines, have acknowledged this strange phenomenon and exploited this limitation of the holographic process. One of the very early examples is ‘Hot Air’ (Figure 1), a laser transmission hologram by Margaret Benyon and now in the Australian National Gallery Collection. Produced in 1970, it shows a three-dimensional composition of a jug, cup, and the artist’s hand. The jug and cup were filled with hot water and during the recording of the holographic plate, with a continuous wave laser, the heat from the hot water disturbed the air above these objects. This tiny amount of movement resulted in the area above the jug and cup not being recorded. Similarly, the artist’s hand moved slightly during the exposure and therefore did not record. Strangely, when viewing the resulting laser transmission hologram, the hand is visible. What is displayed is a holographic hand-shaped black hole, the three-dimensional recording of the space once occupied by the hand; the dimensional recording of the absence of an object.



Figure 1 ‘Hot Air’, Margaret Benyon 1970. Laser transmission hologram. Copyright © 1970 M. Benyon. Reproduced with permission.

> Artists in display holography place continual demands on the technology. Their natural tendency is to break rules. I believe that most successful holographic artists belong to this 'suck it and see' category of experimentalists. On hearing about the 'rules' of holography, they break them, just to see what happens. (Margaret Benyon, PhD Thesis, 1994).

Benyon started by breaking the rules and has continued to develop from these early pioneering laser transmission works, which helped establish a visual 'vocabulary' including many important social and political issues.

Other artists have exploited the 'limitations' of the holographic process to produce visually stunning works which question how we look at the three-dimensional world and question what is 'real'. Rick Silberman (USA) developed a shadowgram technique where the hologram is made of a laser illuminated ground glass screen. Objects are placed in front of this luminous surface and their three-dimensional silhouette is recorded. The viewer of the hologram is looking at the space where the object used to be. A pivotal work in this field is 'The Meeting' 1979 (Figure 2), a white light reflection hologram which had been recorded in such a way as to cause the three-dimensional shadow of a wine glass to protrude out of the holographic plate and be viewable several centimeters in front of it, between the observer and the holographic emulsion. The actual wine glass used in the recording has been broken and what remains (the base, stem, and small part of the bowl of the glass) is placed on a platform attached to the holographic plate. When viewing the work head on, the missing parts of the broken glass are recreated, in three dimensions, by the holographic shadow. When viewed obliquely, from the side for example, only the broken (real), glass is visible. Not only does this piece have an element of performance in the recording, breaking, mounting, and reconstruction of the wine glass, it also explores questions of visual perception and concepts of reality.



Figure 2 'The Meeting', Rick Silberman 1979. White light reflection hologram (shadowgram). Copyright © 1980 ATP. Reproduced with permission.

The recording of the shadow of an object, or objects, has now become commonplace in creative holography, with many artists employing techniques to mix different objects together, change their color and rearrange them in space. One advantage of this technique is that dependence on absolute stability of the objects used is reduced. The objects are 'encouraged' to move during the recording process and so create 'negative' images. Steve Weinstock (USA), Marie-Andrée Cossette (Canada), Michael Wenyon and Susan Gamble (USA/UK) have all contributed to this area in some of their early works.

Public Display

As the technology and optical processes of holography have developed, so greater flexibility, and public accessibility, have emerged. The single most important aspect has been the ability to display holograms in white light.

Emmett Leith and Uris Upatnieks invented laser transmission holography in 1964. They demonstrated the practicalities of Gabor's original invention, by utilizing laser light, to produce three-dimensional images. To display these recorded images, laser light needed to be shone through the holographic plate, at the original angle used by the recording reference beam (off-axis). The results were breathtaking, with full visual parallax in all directions. Although it was the laser light which made the recording and reconstruction of these unusual images possible, the laser was also a limiting factor. Each time a hologram was displayed, a laser was required. This relegated the technique to displays in scientific conferences, laboratories, or other locations with optical equipment. What was needed was a technique allowing holograms to be displayed without the need for this expensive and dangerous laser light. White light holography was the answer.

Although a laser is still required to record the original hologram, by using a copying technique, a restricted aperture or one step process, the resulting holograms can be reconstructed using a small source of white light such as a spotlight or even direct sunlight. As expensive lasers were no longer needed to display holograms, large public exhibitions could be mounted. Gallery and museum spaces could include holography in their exhibitions and individuals could buy and display holography in domestic locations. This technique also benefited the commercial display market, where holograms could now be used for advertising and promotional events.

Stephen Benton (USA) (1942–2003), inventor of white light transmission (rainbow) holography in 1968, made a major contribution to the use of the medium by artists. His technique not only allowed holograms to be viewed in white light, but they were extremely bright and offered the possibility of creating multicolor images. His 'Crystal Beginnings' 1977, (Figure 3), shows just how much space can be created with very simple points of light. Benton even taught master classes for artists so that he could explain how his technique functioned and explain the mathematics involved. He also worked with several artists to help them realize their individual projects.

Harriet Casdin-Silver (USA) was one of the first pioneering artists to work with Benton and produced several key works now seen as integral to the art of holography. Their early collaboration 'Cobweb Space', 1972, sculpted pure light and was one of the very first art holograms to be displayed using Benton's rainbow hologram technique. A later work, 'Equivocal Forks', 1977, exists in different formats; as a laser transmission hologram showing the pseudoscopic display of domestic folks which protrude, inside out, from the holographic plate, and as a number of white light transmission holograms, of the same image, which were shown in an outdoor installation mounted by The Center for Advanced Visual Studies, part of the Massachusetts Institute of Technology. This demonstrated to a wide, nonscientific, audience, that holograms could be accessible, easily illuminated and weatherproof. Casdin-Silver has continued to produce art holography and has, most recently, worked with large-scale portraiture.



Figure 3 'Crystal Beginnings' Stephen Benton 1977, White light transmission (rainbow) hologram. Jonathan Ross Collection, London, UK. One of the best known works by the inventor of the rainbow hologram. Copyright © 2004 J. Ross. Reproduced with permission.

Although Benton's process increased the accessibility of holography, an earlier technique, invented by Yuri Denisyuk (Russia) in 1962, allowed holograms to be recorded in a single step and then displayed using white light. The political situation between the USSR and the rest of the world during the early 1960s meant that information and results from much of this early work was not openly accessible, and communication between Denisyuk and other key researchers in holography was limited. However, as soon as details of the Denisyuk technique became more widely available in the 1970s, artists began to embrace it as a practical alternative.

The work of Nicholas Phillips (UK), whose research improved chemical processing of display holograms during the late 1970s, helped artists and the rest of the holographic field to achieve much better results when making reflection holograms, a technique favored in Europe. He was also heavily involved with the rock band, 'The Who', and their Holoco company which mounted two very successful exhibitions of display holography at the Royal Academy of Art, London, at this time. Artists who might not have come across the holographic phenomenon became aware of its potential due to its presence in one of the UK's more traditional art venues. Other large exhibitions in the late 1970s and early 1980s in USA, Sweden, and Japan also highlighted the immense possibilities holography offered to a nonscientific community of gallery visitors.

As interest in all aspects of holography increased, dedicated spaces opened to sell, display, and archive the output from artists, scientists, and commercial producers. One of the most influential of these was the Museum of Holography, located in the SoHo art district of Lower Manhattan, New York (Figure 4). From 1976 through to 1992, it regularly mounted group and solo exhibitions by artists, giving many of

Figure 4 Dr Dennis Gabor, inventor of holography with, Posy Jackson, Director of the Museum of Holography, during his visit to the Museum in March, 1977. Copyright © 1977 Paul D. Barefoot. Reproduced with permission.

them their first major exposure to a museum-going public. There were displays relating to the scientific, commercial, and industrial usage of the medium, as well as exceptionally popular traveling exhibitions. 'Through the Looking Glass', which traveled worldwide, allowed early display holography to be experienced by thousands of people who would not normally have come into contact with the medium. In the Summer of 1981, over 300,000 visitors saw 'Through the Looking Glass' during the 11 weeks it was on view at the Israel Museum, Jerusalem.

After the Museum of Holography closed in 1992, its entire collection was purchased by the MIT Museum, Boston, USA, and now forms part of the largest museum collection of creative and scientific holography in the world. The New York museum was not an isolated venue. During the late 1970s and early 1980s, museums of holography opened in Chicago, Paris, and Pulheim (near Cologne). Galleries were also founded in many major cities to sell art and commercial holograms.

Stability Solutions

Although being able to display holograms using inexpensive sources of white light allowed the medium to become much more accepted as a display process, there has always been the cost and complexity of the optical laboratories needed to record the holograms in the first place. Few artists were able to equip their studios with 'off the shelf' optical components and precision-built isolation tables most often found in scientific and research labs. The solution was to replace the commercially built isolation table with much less expensive sand tables.

Sand box holography revolutionized the field for independent artists. By building a wood or brick box filled with sand, resting on car inner tubes, artists were able to hand-make their own isolation tables. Inexpensive optics, mounted onto plastic pipes were simply thrust into the sand, allowing complex optical recording setups to be constructed. Surprisingly, many key artworks have been produced using this technique, which opened the field to anyone with basic construction skills and a laser.

The laser has remained an expensive element in the holography studio but, most recently, the prospect of replacing this with laser diodes has offered a much more economic alternative. Not only can light from these diodes provide more compact optical setups to record holograms, they can also be used to display them. Significant progress has been made in both diode recording and display, which is opening up new opportunities for the visual artist. Almost all of the early practitioners in the field were attracted to holography because of the laser transmission holograms they saw. They have a depth and dimensional quality which is extremely different from the white light viewable holograms we tend to see today. Now, with the possibility of displaying holograms illuminated by inexpensive laser diodes, the laser transmission hologram is set, once again, to be a viable medium for artists.

Object Holography

Many artists were attracted to holography because of its unusual three-dimensional properties. However, they did not have the resources to make holograms of large objects or scenes, so scaled these down and constructed small sculptural settings for recording. One of the pioneering artists in this area was Dan Schweitzer (1946–2001). Originally an actor and familiar with theatrical staging, many of his holograms are populated by tiny figures placed in specially built 'theatrical' settings. Holography not only recorded these specially constructed miniature 'rooms', but the resulting images were realistic enough to suggest to the viewer that they were looking at a scaled-down life-size event. We do this regularly when looking at photographs and accept that they are a small-scale version of a larger scene. Traditional holography does not offer this 'scaling down' in the same way as photography. One celebrated example is Schweitzer's 'Thendara', 1978, where a sculpted, miniature figure sits and looks towards a window frame. He also produced a companion piece in which the physical model, used to make the earlier hologram, is on display as a piece of sculpture. Here the miniature window is the frame for a hologram displaying a previously recorded model of a landscape. As Schweitzer's technical skills



Figure 5 'Od Vent', Dan Schweitzer 1980, White light transmission hologram in sculptural mount. Copyright © 1980 ATP. Reproduced with permission.

developed, he began to produce complex multilayered works incorporating still-life models, hologram fragments, and optical animation to construct visual spaces which could not exist in the real world.

In his work 'Od Vent' (1980) (Figure 5), Schweitzer framed an exceptionally complex white light transmission hologram into a theatrical model of a doorway. The miniature stairs lead up to an opening, a portal into another world, in which the hologram is mounted. Illuminated from behind, the hologram displays multiple exposures, optical animation, and several superimpositions of objects as an observer moves from left to right in front of the piece. In this complex holographic world, the silhouette of the figure, standing in the door, casts a bright (negative) shadow down the miniature stairs. Not only are we able to look into an illusionary world through the holographic doorway, where at a certain point Einstein looks back at us, but the peculiarities of this holographic world extend into our own world as seen by the 'real' (negative) shadow cast down onto the stairs.

Another artist, who combined the use of multiple exposed objects displayed in a single space, is John Kaufman (USA). He established a reputation by recording objects (often rocks) collected from around his Californian holography studio. These found objects were captured in three dimensions and were then, through a multiple exposure and emulsion swelling technique, combined into a single still-life composition. He became expert at masking out areas of his objects so that they could appear in different, intense colors, and in many cases used the holographic process and multiple exposures to mix colors directly in the holographic space he was working with. In 'Stone Head' (1982) (Figure 6), for example, this relatively 'normal' stone is transformed by the use of intense color and the three-dimensional volume it occupies.

When considering how the hologram should be framed and displayed, several artists have utilized the mount in which the hologram sits as an integral part of a much more complex work. Frithioff Johansen (Denmark) recorded a hologram of smoke, freezing it in time and space using a pulsed laser (see below). This was then converted into a white light transmission hologram and mounted in a frame of granite. 'Hardware-Software 1' 1987–1988, allows the gallery visitor to not only view the massiveness of the granite structure, but also the delicate sculptural solidity of smoke 'frozen' in space.

Rebecca Deem (USA) recorded what appears to be an extremely simple hologram of a luminous tube, mounted onto a swivel at the end of an elegant metal support. In 'W/Hole Message' viewers can look into the small holographic plate and see the image of the tube extending away from them into the volume behind the plate. By flipping the hologram, on its swivel, to turn it over, the image in the hologram is also flipped and the tube appears in the viewer's space, between them and the plate. This three-dimensional pseudoscopic image, one of the attractive and unusual aspects of holographic display, is inside out, back to front, and upside down. The gallery visitor really does have a chance to view the whole message.



Figure 6 'Stone Head', John Kaufman 1982, White light reflection hologram. Copyright © 1982 John Kaufman. Reproduced with permission.



Figure 7 'Breakfast', Pearl John 2002. Laser etched toast displayed in a white light reflection hologram. Copyright © 2002 Pearl John. Reproduced with permission.

Text has become an important element in holography, as it is often incorporated in, onto, or around holographic displays. Eduardo Kac (Brazil) has produced several holograms, which display poems, words, and letters floating within the holographic space he has created.

Pearl John (UK) most recently produced a series of still-life holograms using a pulsed laser but with the added subtlety of writing onto the surface of her objects. In 'Breakfast' 2002 (Figure 7), for example, the slices of toast, making up the composition, have been laser etched with text which appears 'burnt' into the surface of the bread.

Pulsed Lasers

Continuous wave lasers placed limits on the holographic recording process and dictated that no movement in the recorded object could take place. We have seen that this 'problem' was exploited by artists at an early stage, but there was also a desire to capture living objects, in the form of the human figure. Pulsed laser holography was the solution. Because this type of laser generates a bright flash of coherent laser light, the intensity and duration of the pulse is enough to 'freeze' any physical movement during the recording process, allowing the recording of people, animals, or anything which moves and could be brought into an holography studio. Again, the cost and accessibility of this specialist equipment was prohibitive to artists, but they found ways of persuading scientists with pulsed lasers to help them. Early adopters of this technique were artists such as Ana Maria Nicholson (USA), Melissa Crenshaw and Sydney Dinsmore (Canada), Margaret Benyon (UK), Anait (USA), and Alexander (USA/UK). Recordings could now be made of live figurative compositions and individual portraits. Many of the artists, not content with producing the holographic version of a traditional photographic portrait, began to manipulate these recordings, distorting, multiple exposing and inverting these unusual three-dimensional images of people.



Figure 8 'Awakening', Ana Maria Nicholson, 1993. White light (pulsed) reflection hologram. Copyright © 1993 Ana Maria Nicholson. Reproduced with permission.

Holographic portraits do have an unusual quality, which painters or photographers have found difficult to deal with but art holographers have embraced. Some, like Ana Maria Nicholson (USA), have combined subtle processing techniques, to introduce color 'layers' into the portraits, combined with nonstandard views or compositions (see 'Awakening' 1993 (Figure 8)). Other artists, who emerged in the 1980s, produced complex, highly staged compositions, such as those from Patrick Boyd (UK), or they offered us a different view of the 'self portrait' like those by Martin Richardson (UK). Others, such as Shu-Min Lin (Taiwan), used the combination of multiple views of human figures recorded onto the same holographic plate. By walking past these displays, an animated effect could be experienced.

So much interest was generated in pulsed holography that several studios emerged for use by artists, including independent facilities and those within educational establishments. No longer was this the domain of the well funded scientific research facility. Several of these 'studios' still exist and are offering artists access to equipment through specialized artist-in-residence programs.

Abstraction

Although holography is an exceptional process for recording every detail of an object and the volume it occupies, many artists have wanted to work with the abstract and kinetic possibilities the process offers. Light can be recorded and displayed in three dimensions, it can be animated, inverted, compressed, sculpted, and projected. Douglas Tyler (USA), in his In the 'Dream Point Series' 1983 (Figure 9), recorded small laser transmission holograms but displayed them using normal white light, producing a smearing effect of the three-dimensional object. He then mounted these onto transparent surfaces (Plexiglas) and drew on the surface of the plastic to incorporate etched lines and shapes. Rudie Berkhout (Netherlands/USA) began his holographic exploration with stunning abstract landscapes made of luminous, multicolor, animated objects which took advantage of his mastery of the white light transmission technique. Most recently he has been recording reflection holograms which display undulating colored 'waves' of light as an observer moves past the hologram. These have been included in specially produced paintings for large-scale architectural commissions.

Sam Moree (USA) combines multiple images, exposures, diffraction gratings, and smaller holograms into a single work. The finished holograms display a complex series of image fragments and colors within the depth of the holographic space he has constructed. Ruben Nuñez (Venezuela), originally approached holography from a background in glass production and used the ability of the holographic process to 'capture' light reflecting and passing through his glass objects. The resulting white light transmission holograms display an abstract 'photonic' display of form and color. Fred Unterseher (USA), uses holography to record optical distortions and diffraction gratings which would display abstract patterns of light. Many of these early works were mandala images which displayed an intense kinetic effect as an observer walked past the surface of the holographic plate.



Figure 9 'Dream Passages': 32″ × 138″ (3 panels 32″ × 46″). Douglas E. Tyler 1983, Laser transmission holograms, tape and Plexiglas, illuminated with white light. Detail of center panel. Copyright © 1983 D.E. Tyler. Reproduced with permission.

Pseudo Holograms

In 1973, Lloyd Cross invented the multiplex (integral) hologram technique which used sequential two-dimensional images recorded on movie film combined with white light (rainbow) hologram techniques. The result was a holographic stereogram, which gave viewers the illusion of seeing animated images in three dimensions. The final holographic sheet was displayed either curved or as a complete cylinder, which was often motorized so that viewers could stand in front of the unit and watch the animation take place as the hologram rotated. Such a display does give the impression that an observer can walk all the way round the image, enhancing its perceived three-dimensional effect.

As the original images are recorded photographically, there are several advantages – anything which can be recorded on inexpensive black and white movie film can be converted into a holographic display. Short animated sequences can be presented while accepted film techniques such as zoom, pan, tilt, and transitions can be incorporated into the finished sequence of images. Although very popular for advertizing and promotional campaigns during the 1980s, particularly in the USA, several artists used this technique. They could make the movie film sequences themselves and then send this film to a commercial producer for a hologram to be made for them. This offered an interesting balance in the creative process. The artist could concentrate on the filmic image, using facilities and photographic techniques they were familiar with and not have to learn the holographic process or build a holographic laboratory themselves. Artists such as Anait (USA) produced several experiments in the area, one of which showed her inside the holographic display,



Figure 10 'Woman' Harriet Casdin-Silver 1979. Multiplex hologram (white light transmission). Copyright © 1980 ATP. Reproduced with permission.

writing, with spray cream, seemingly onto the holographic surface. Dieter Jung (Germany), used this technique to display a specially written poem which appeared to spiral around inside of the display.

Harriet Casdin-Silver used the technique to produce an unusual self-portrait. 'Woman', 1979 (Figure 10), is a multiplex hologram of the artist's head. Black and white film images were recorded of Casdin-Silver's head, through 360 degrees, and then each frame of film was converted into a thin white light transmission hologram. The artist chose not to display the resulting image in a normal cylindrical display, but to 'flatten' it out so that the front, sides, and back of her head could be seen, distorted, in a single head-on view.

As video and digital imaging processes have developed over the years they too have been combined with this pseudo holographic technique, opening up a wide avenue of possibilities. Video footage, computer generated modeling, or any process which can produce sequential 2-D images, can now be converted into an animated 3-D hologram. As digital video cameras and computer 3-D modeling software drop in price, and increase in sophistication, a whole new area of display has become available to the digital and video artist.

Multi Media

As in other areas of the visual arts, more than one medium or process are often combined. Doris Vila (USA) has produced complex environments combining large-scale holographic images which, rather than being illuminated with a single source of light, are reconstructed with multiple spotlights or via video projectors. The lighting is activated by sensors in the exhibition space, which are computer controlled and made to trigger certain sequences dependent on the input they receive from the movement of visitors.



Figure 11 'Neuro Hologram', Ikuo Nakamura, 1993. White light transmission hologram with multiple, computer controlled, lighting. Copyright © 1993 Ikuo Nakamura. Reproduced with permission.

Traditional illumination of a hologram involves a single point source of light shining onto, or through, the holographic plate. This will reconstruct a single image. If multiple lights are shone onto the hologram, multiple reconstructions of the single image will result. By using many independently controlled lights on one hologram, Vila has been able to create animation and kinetic effects as the resulting multiple images overlap. Using light from a video projector also allows the artist to combine a reconstructed holographic image with two-dimensional animated footage from the video projector.

Other artists to combine holograms with structures, interactive lighting and environments, sound, and installational displays include: Georges Dyens (Canada), Marie-Christiane Mathieu (Canada), Matthew Schreiber (USA), Philippe Boissonnet (Canada) Ana MacArthur (USA) and Shunsuke Mitamura (Japan).

Ikuo Nakamura (Japan/USA) has used multiple lighting of a single computer generated hologram to produce animated effects controlled by the viewer. In his 'Neuro Hologram' 1993 (Figure 11), brain waves from the viewer, wearing a special set of sensors on their head, are measured and converted into control signals for a number of lights behind the hologram. By relaxing, or becoming agitated, the viewer can change their brain waves and actively control the appearance of the hologram, causing multiple views of the holographic image to fade in and out, giving an impression of abstract animation.

Architectural Scale

One of the great limitations of holography has been the size of the holographic plates on which the light sensitive emulsion is coated. These tend to be in the region of 20 × 23 cm, 30 × 40 cm, or meter-square formats. Generally, the larger the finished hologram, the larger the laboratory needed to produce it. This impacts a great deal on artists who do not have the facilities, or finances, to produce ‘large’ holograms. A solution has been to combine smaller holographic plates together, as a mosaic, to give the size and scale needed. In recent years, several artists have completed public commissions for large-scale interior and exterior holographic installations.

Setsuko Ishii, (Japan) has produced several installations in public spaces where individual holographic plates are mounted together to form a larger composite structure. Many of these pieces use holograms recorded on dichromate gelatin plates which produce an exceptionally bright image, ideal for public spaces, where visibility, from multiple angles, is important.

Michael Bleyenberg (Germany) produced an entire exterior holographic wall (13 × 5 meters) during 2002 (Figure 12), for the extension of a research building in Bonn. The installed graphic wall, ‘EyeFire’ (AugenFeuer), is made up of 26 smaller panels, each constructed from tiny holographic ‘pixels’ (holographic optical elements, HOE) to give an intense color effect. Working in collaboration with the Institute for Light and Building Technology, Cologne, Bleyenberg was able to design his graphic panels on a computer screen and have this information translated into the thousands of tiny holographic pixels which, when seen together, make up the complex and high intensity colour design.



Figure 12 ‘EyeFire/AugenFeuer’, Michael Bleyenberg 2000. White light transmission holograms mounted onto building exterior. Copyright © 2000 M. Bleyenberg. Reproduced with permission.

Dieter Jung (Germany) has produced commissioned art works for large interior architectural spaces. In ‘Perpetuum Mobile’ 2001, located at the European Patent Office, The Hague, holograms are placed on the floor, which can be walked over, and an extensive holographic mobile structure hangs overhead. The light, and color, from the abstract holograms in the mobile sections, can be reflected in the abstract holographic floor and combine to produce an interior lightscape impossible to produce with more traditional media.

Holograms can be mass produced using a mechanical embossing process which transfers the optical contents of the original master hologram onto plastic sheeting for duplication in large runs. One novel use of this material has been the interior of the Canadian pavilion at Expo ‘92 (Figure 13). Melissa Crenshaw (Canada/USA) used huge quantities of embossed holographic material to cover the 3000 square foot interior walls of the specially built pavilion. Lighting was installed to illuminate this optical diffracting wall and the entire structure was covered in glass, over which water flowed. The resulting interior appeared to be a wall of liquid light which changed color and hue depending on where it was viewed from.

Sally Weber (USA) used holographic embossed material for several outdoor commissions. Structures were clad in embossed holographic sheets and made water resistant. Sunlight illuminated the installations to produce surfaces of constantly changing color. In direct (bright) sunlight, intense rainbow colors would be diffracted by the holographic surfaces. On an overcast day, pastel, more muted,



Figure 13 Interior of the Canadian Pavilion Expo ‘92, Spain. Holographic wall water feature by Melissa Crenshaw. White light transmission (embossed) hologram foil mounted into pavilion walls. Copyright © 1992 M. Crenshaw. Reproduced with permission.



Figure 14 Signature of Source, Sally Weber 1997. Site specific window installation at the Karl Ernst Osthaus-Museum, Hagen, Germany. Copyright © 1997 Sally Weber. Reproduced with permission.

colors would appear. Although she is often known for these large-scale outdoor embossed works, one of her permanent commissions is housed in the Karl Ernst Osthaus-Museum, Hagen, Germany, where specially made holographic diffraction gratings are incorporated into an existing building. 'Signature of Source' 1997, (Figure 14), is a permanent, site-specific installation producing a line of light which enters the museum space from the skylight it is built into. This abstract line of pure color becomes a sculptural element within the space of the museum and is generated by the action of light from outside the building being manipulated and 'formed' as it passes through the holographic window.

One of the most celebrated and very early attempts to incorporate large-scale holograms into art works was the installation 'There's No Place Like Home' by Paula Dawson (Australia) in 1979–1980 (Figure 15). A laser transmission hologram of an entire room was recorded. The room was specially constructed, life size, and recorded onto a single holographic plate. The resulting hologram was then built into the window of a small 'house' constructed in the gallery. Visitors were able to approach the house, look into the window and 'see' the interior with its furniture, fixtures, and fittings. They would then enter the house and walk past the space where the room appeared to exist. When viewed from this vantage point there was nothing there except an empty space. Artists have often questioned and researched the concepts of 'inside and outside', voyeurism, reality, normality, and 'existence', but few have had the tenacity to produce an installation with such visual and conceptual impact.



Figure 15 'There's no Place Like Home', Paula Dawson 1979–1980. Laser transmission hologram of an entire room. Copyright © 1980 Paula Dawson. Reproduced with permission.

Twenty-First Century Art

Art holography has developed and matured over the past 50 years to become a viable and significant element in the contemporary visual arts. Critics are still asking 'is it art?' in the same way they used to worry about whether photography was art. While they consider this problem, practitioners in the medium are continuing to find ways to push past its technical and visual boundaries (Figure 16). They continue to collaborate with the scientific and research world and use holography as a medium to comment on life and society in the early twenty-first century.

> ...I hope, that one day I will be able to give you, artists, something really powerful; panoramic holograms,

MANIFESTO

.A code.
.Spatial.
.Didactic.
.Photonic.
.Futuristic.
.A discipline.
.Illumination.
.A photograph.
.Science↔Art.
.A precision tool.
.Illusion concrete.
.Pure chiaroscuro.
.An automatic Eden.
.An indivisible whole.
.Painting↔Sculpture.
.3D on 2D intimating nD.
.Material and immaterial.
.Writing the whole picture.
.The presence of absence.
.Making the invisible visible.
.An artificial 3D imaging system.
.Re-evaluating our visual traditions.
.Part of an innate human grammar.
.A bridge into the future with a past.
.The smile without the Cheshire Cat.
.Neither geometric nor organic in form.
.The reconstruction of light wave-fronts.
.Shattering the illusionist paradigm in art.
.A perceptual screen from the 'real world'.
.A potential mass-communications medium.
.A visible medium and a subvisible principle.
.A model for the complexities of brain function.
.Not art, but a condition in which art can happen.
.Mirrored in the life process, our own physiology.
.A mirror to our evolutionary progress from objects to systems.
.Realizing space time/time reversed/back as front/inside as out.
.A model for non-fragmentary thinking, language and behaviour.
.A diminutive shadow-theatre in which metaphors are strongly lit.
.A possible visual model for quantum theory and relativity theory.
.The most complete form of reproductive imaging that exists to date.
.A means of making statements about the world, or presenting pieces of it.
.The fulfillment of a longstanding cultural vision of what imaging ought to be like.
.Joined with high technology to raise the ceiling on humanity, or record Doomsday.
.The automatic execution of the ultimate cubist notion of a simultaneous view at every given point.
.An expression for mystical aphorisms such as 'the universe in a grain of sand' and 'we are all one'.

HOLOGRAPHY AS ART

Figure 16 'Holography as Art', Margaret Benyon 1980. Manifesto. Copyright © 1980 M. Benyon. Reproduced with permission.

extending to infinity, in natural colors. Dennis Gabor, Inventor of holography in a letter to artist Margaret Benyon 28th February, 1973.

See also

Coherence: Coherence and Imaging. **Diffraction:** Diffraction Gratings. **Holography, Techniques:** Overview. **Imaging:** Multiplex Imaging. **Interferometry:** White Light Interferometry. **Introductory Article:** Early Development of the He–Ne Laser (Title TBC).

Further Reading

Benyon M (1994) *How is Holography Art?* PhD thesis, Royal College of Art, London.

Brill LM (ed.) (1989) Holography as an art medium, Leonardo. *Journal of the International Society of Arts, Sciences and Technology*, 22 (3 and 4).

Coyle R and Hayward P (1995) *Apparition, Holographic Art in Australia*. University of Sydney, NSW, Australia: Power Publications.

Casdin-Silver H (1998) *The Art of Holography Exhibition Catalogue*. Lincoln, MA, USA: DeCordova Museum and Sculpture Park.

Holographische Visionen, Bilder durch Licht zum Leben erweckt (1991) Exhibition Catalogue, Museum für Holographie und neue Visuelle Medien, Pulheim, Germany: Edition Braus.

Holosphere, Formerly published by the Museum of Holography. New York: Boston, USA: Archieved at the MIT Museum.

Jackson R and Burns J (1976) *Holografi: Det 3-Dimensionella Mediet, Exhibition Catalogue*. Museum of Holography, New York: Stockholm Cultural Center.

Jung D (ed.) (2003) *Holographic Network*. Germany: Rasch Verlag, Bramsach.

Orazem V and Schepers J (1992) *Olografia, Holografie, Holography, Exhibition Catalogue*. Rocca, Paolina, Italy: Centro Espositivo.

Lipp A and Zec P (1985) *Mehr Licht/More Light, Exhibition Catalogue*. Kabel-Verlag: Hamburger Kunsthalle.

Pepper AT (ed.) (1992) *The Creative Holography Index: The International Catalogue for Holography*. Germany: Monand Press.

Pepper AT (ed.) (1996) *Art in Holography 2*. International Symposium on Art in Holography. Nottingham, UK: University of Nottingham.

Margaret Benyon M (1989) *Phases: Exhibition Catalogue*. New York, USA: Museum of Holography.

Tyler DE (ed.) (1990) *Report, International Congress on Art in Holography*. Notre Dame, Indiana, USA: Saint Mary's College.

Tyler DE (ed.) (2003) *Leading Lights, Women in Holography, Exhibition Catalogue*. Notre Dame, Indiana, USA: Saint Mary's College.

High-Resolution Holographic Imaging and Subsea Holography

J Watson, University of Aberdeen, Aberdeen, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Holography is well-known to most of us: there can be few who are not familiar with the white-light display hologram seen in exhibitions and shops and on credit cards. The impact of holography, though, spreads far and wide into areas as diverse as vibration analysis, image processing, holographic-optical elements, and optical computers. One aspect often overlooked is its suitability for high-precision imaging and accurate dimensional measurement. It is the unique ability of holography to recreate, from a flat photographic film, a three-dimensional image that is optically indistinguishable from the original which sets it apart from other imaging techniques. In particular, holography comes into its own when recording objects in a hazardous environment or where access is difficult, such as underwater or in nuclear fuel element inspection.

We describe here the use of holography for imaging, identification, and measurement of aquatic organisms. A detailed knowledge of the distribution and dynamics of marine and freshwater organisms and particles, such as plankton, is crucial to our understanding of such systems and how they affect our environment. Traditional methods of gathering *in situ* data on aquatic particles, such as net-collection and electronic counting or photography, are not usually suited to observing precise spatial relationships and can destroy the more delicate organisms. The overriding benefit of holography is that it permits nonintrusive and nondestructive observation and analysis of organisms in their natural environment, while preserving their relative spatial distribution. Holography also offers a permanent archive. The use of a short-duration pulsed laser is essential, in order to reduce the effects of vibration or movement in any of the optical components or objects being recorded. Consequently, the object scene is effectively 'frozen' at the recording instant, thereby allowing fast moving particles to be imaged. Compared to a photograph, a hologram captures vastly more data. Sequential holograms can record changes within the volume over a defined period of time and the wide recording dynamic range afforded by a hologram allows images to be captured that would otherwise be lost in noise.

Methodology of Holographic Recording and Replay

Of the many possible recording methods of holography two in particular, 'in-line' and 'off-axis', find use for high-resolution *in situ* imaging underwater. The concepts and fundamental principles outlined here are generally applicable wherever high-precision measurement is needed from a hologram.

In an in-line reference beam hologram (ILH), a single laser beam (Figure 1) is directed through the


A single collimated laser beam traverses the scene
Optical flats
Holographic emulsion
Hologram formed between undeviated laser beam and light scattered from particles
Collimating lens
Water-filled observation tank
Small particles in water– (e.g., bubbles, plankton, etc.)

Figure 1 Recording an in-line hologram.


Laser light
Beam splitter
Object beam path
Beam expander lens
Glass window
Holographic emulsion
Hologram formed between off-axis laser beam and light reflected from particles
Reference beam path
Small particles in water-filled observation tank
Beam expander lens

Figure 2 Recording an off-axis hologram.

sample volume towards the holographic plate and records the optical interference between light diffracted by the object and the undeviated portion of the illuminating beam. The subject volume is illuminated in transmission and the scene needs an overall transparency of about 80% so that speckle noise does not seriously degrade image quality. Particles down to around 5 μm dimension can be readily recorded and identified. The particular benefits of ILH are its geometric simplicity, minimization of laser coherence and energy requirements, and high resolution over a large depth of field.

For recording an off-axis reference beam hologram (OAH), a two beam geometry is utilized: one beam illuminates the scene and the other directly illuminates the holographic film at an oblique incidence angle (Figure 2). Interference occurs between diffuse light reflected from the scene and the angularly separated reference beam. On replay, the real and virtual images are similarly angularly separated which makes their interrogation easier. OAH is primarily applied to opaque subjects of large volume. Although there is no real upper limit to the size of particles that can be recorded (this is determined by available energy and coherence of the laser) the practical lower limit to the resolution that can be achieved is around 50 to 100 μm. The scene can be front, side or back illuminated (or all three combined) allowing high concentrations of large particles to be recorded, provided that they reflect sufficient light to the film, and allowing subject visibility to be optimized. OAH provides a more complete record than ILH, in the sense that it gives information on the surface structure of the object, while ILH records only a silhouette.

Holograms are replayed or reconstructed in a variety of ways, depending on the recording parameters and subsequent processing of the recording medium. In scientific and engineering applications the requirements of high resolution and image fidelity demand that they are replayed with a laser, and viewed with some auxiliary optical system and (usually) a video camera. Depending on the orientation of the hologram, either the virtual image, which is apparently located behind the hologram and seen through it, or the real image, which is formed in space in front of the hologram, will be visible.

Considering first the off-axis hologram in the virtual image mode, the processed hologram is replaced in the position in which it was recorded and illuminated with an exact duplicate of the original reference wave, in terms of its wavelength, curvature, and beam angle. In this mode, which might be termed 'normal' viewing of an off-axis hologram, a virtual image (Figure 3) is observed as if viewing the scene through a window. Other than the colour, this image is almost optically indistinguishable from the original scene; it retains features such as parallax and three-dimensionality and does not suffer from perspective distortion or defocusing of the image.

For data extraction and measurement from a hologram, creation of the virtual image is not the best method of observation. Here the projected real image (Figure 4) is most useful. If we illuminate an off-axis hologram from behind, with a wave which is the exact conjugate of the original (i.e., one which possesses the same wavelength as the original but with the opposite direction and curvature), we generate an image that appears to float in the real space in front of the observer. Often a collimated reference beam is used in recording, since reconstruction is then a simple case of turning the hologram around. No lens is needed to form this image, and it is optically identical to the original wave that it is reversed left-to-right and back-to-front (pseudoscopic). Planar sections of the real image can be optically interrogated by directly projecting onto a video camera (often with the lens removed) which can be moved throughout the 3D volume. It is this 'optical sectioning' feature of a holographic recording that is so useful when nondestructive (noninvasive) evaluation must be made, at high resolution, of collections of objects which extend over a considerable depth.

A series of images taken from the real image of one hologram and captured on a video camera (Figure 5) illustrates how the viewing plane can be moved sequentially through the reconstruction to show firstly one marine organism and then another. The axial separation of the organisms is about 35 mm.

To replay an in-line hologram, it is also placed in a conjugate of the recording beam (Figure 6). The replayed hologram simultaneously forms two images, one virtual, the other real, which are located on the optic axis on opposite sides of the holographic plate. These images are co-axial, and located (for the typical case of collimated recording and replay beams) at equal distances in front of and behind the hologram plane. Although a true 3D real image is produced it has almost no parallax, and cannot easily be seen by the unaided eye. This image has inverted depth perspective and is seen in darkfield against the out-of-focus virtual image.



Figure 3 Replay of an off-axis hologram in virtual image mode.


Laser light
Reference beam path
Beam splitter
Beam stop
Holographic emulsion
Beam expander lens
Life-size image in front of the holographic plate is inside-out and left-to-right
Collimating lens
Measuring microscope or video camera traverses the real image
Hologram replayed with 'conjugate' of recording beam
Planar sections through image

Figure 4 Replay of an off-axis hologram in real image mode.



Figure 5 A series of images taken from a single hologram showing the concept of moving the viewing plane through the real image.


Holographic emulsion
A collimated laser beam illuminates the recorded hologram
Measuring microscope or video camera traverses the real image
Virtual image
Real image
Two images of the original are seen: one on either side of the holographic emulsion
Planar sections through image

Figure 6 Replay of an in-line hologram.

Holographic Image Quality

In general, the usefulness of holography for accurate inspection and measurement is dependent on its ability to reproduce an image of the object which is low in optical aberrations and high in image resolving power. Regardless of whether or not the hologram is recorded underwater, high resolution, high contrast, and low noise are the dominant requirements, rather than image brightness. In practice, loss of resolution and image degradation can occur at any stage in the recording and replay of a hologram. All the primary monochromatic aberrations to be found in any optical system (spherical aberration, astigmatism, coma, distortion, and field curvature), may be present in the holographic image. The most significant factors affecting this are departure from conjugacy of the reconstruction beam; positional mismatch and misalignment between reference beam and film; degradation of the reconstruction beam due to poor optical quality of the film substrate or optical components; and, distortion of the fringe pattern recorded in the holographic film as a result of chemical processing. For precise and accurate reconstruction of the real image, the reconstruction reference beam should be the exact phase conjugate of that used in recording. Under these conditions, the lateral, longitudinal, and angular magnifications of the real image with all equal unity and aberrations will be reduced to a minimum.

Diffraction-limited resolution of a holographically produced real image, in the absence of all aberrations, is usually defined from the ability to distinguish two points in the image separated by a distance r. The resolution as defined in this way is dependent upon reconstruction wavelength, λ_c, the separation between hologram and reconstructed image, s, and the effective aperture, D, of the hologram:

$$r = 1.22 s \lambda_c / D \qquad [1]$$

This relationship is well-known in imaging optics: it defines the ideal resolving power of a lens and is equally applicable to holography. In holography, though, the presence of speckle effects introduced by the coherence of the light and the finite aperture of the viewing system influence the resolving power. In practice, the minimum resolution is increased by a factor of two to three to take account of speckle. For off-axis holograms the choice of film size (effective aperture) has a considerable bearing on image resolution. Typically, for 100 mm diameter film the theoretical image resolution (neglecting speckle effects) is around 6 μm (150 lp/mm) with a 532 nm laser at a target distance of 1 m. For in-line holograms (with collimated illumination) the film size also defines the transverse dimensions of the volume recorded.

Wavelength matching between recording and reconstruction beams require that, if possible, the same type of laser be used in both replay and recording. Of course, this is not possible in field situations when the use of a pulsed laser is essential to ensure that the fringe pattern is not blurred by any movement in the system. In such applications, laboratory replay of the hologram may require the use of a tuneable laser to match wavelengths precisely, although in practice an argon laser provides a useful selection of wavelengths. A mismatch between record and replay wavelengths will lead to distortion in the image, because longitudinal and lateral magnifications will no longer have the same value.

In contrast to off-axis holograms, the interference patterns on an in-line hologram are localized about the geometric shadow of the objects. The lack of a spatially separate reference beam leads to a requirement that there be a large fraction (>80%) of the beam unobscured. This limits the size of particles that can be recorded and sets an upper limit on the recordable concentration of particles (around 40 particles cm^{-3} for 20 μm diameter particles and a recorded depth of 1 m). There is also a need to balance the size of the particles with the object-to-hologram distance. The range of object size recordable on an in-line hologram has an upper limit set by the requirement to record in the far-field of the object, so that the conditions of Fraunhofer recording are satisfied:

$$z > d^2/\lambda \qquad [2]$$

where z is the object-to-film distance and d is the maximum dimension of the object to be recorded. In-line holograms are relatively easy to replay as the only requirement is to place the hologram normal to the replay beam. Following this criterion, the upper limit for good size measurement is about 2 to 3 mm particle size over a recording distance of a meter. Unlike off-axis holograms which are extremely sensitive to misalignment, the in-line geometry minimizes the effects of film rotation about its axes. A collimated recording beam is by far the easiest to duplicate upon replay. Small deviations from collimation can significantly affect conjugacy and hence resolution, introducing aberrations (mainly spherical) and a depth-dependent magnification (e.g., a cuboid replays as a trapezoidal prism).

In general, the interference field is captured on photographic emulsions; these may be laid on acetate or polyester film bases or on glass plates. If film is used, it is essential that it be held as flat as possible between thin flat glass plates or under vacuum, and should not be stretched or put under any strain during exposure. An in-line hologram does not require an extremely high-resolution recording medium. The fringe spacing is not as fine as the typical carrier fringe frequency used in off-axis holograms, and holograms can be made on conventional slow photographic emulsions. In practice, however, ultra-fine grained holographic film is almost always used since the intensity of the forward scattered light (a function of grain size) is then reduced: this is important in increasing the signal-to-noise ratio, as the replayed image is viewed against a background of the attenuated replay beam. Since the proportion of the illuminating beam that goes into the images is very low, this lack of angular separation requires that the average optical density of the hologram is high. The high optical density attenuates the undiffracted light, thus the image appears bright against a dark background, resulting in contrast reversal.

The exposed film is chemically processed to render the interference field permanent. This process is a crucial step in the holographic procedure, and especially critical for good off-axis holograms. Some of the factors, which have to be considered, include image brightness, image resolution, reconstruction wavelength, emulsion shrinkage, humidity, and noise level. It has been well established that for bright off-axis holograms on silver halide film, bleaching of the emulsion with its consequent conversion into a phase hologram is essential to maximize diffraction efficiency. Some forms of bleaching produce a nonuniform shrinkage of the emulsion which will give rise to astigmatism in the reconstructed image. Bleaching significantly increases the background noise levels of the hologram and introduces a high degree of variability into the result. In practice, the best repeatability will be obtained with amplitude processing if the low brightness can be tolerated.

Underwater Holography

When holography is extended to the inspection of underwater scenes, the hologram is recorded in water but the image is replayed, in the laboratory, in air. Because of the refractive index difference between recording and replay spaces, optical aberrations will be introduced into the reconstructed image, and will seriously impair the potential for precision measurement, unless some method of aberration reduction is incorporated. In ILH, only spherical aberration is significant since both reference and object beam angles are normal to the recording plane. However, in OAH the dominant aberrations are astigmatism and coma, which increase with the field angle of the subject in the reconstructed image. These limit resolution and introduce uncertainty in co-ordinate location, since the focal 'point' is now distributed over a finite region of image space. A key point here is an appreciation that the additional aberrations introduced are entirely due to the refractive index mismatch between object and image spaces and are unconnected with the holographic process itself: they are in essence the same distortions seen when looking into a fish-tank. Furthermore, the water itself may be expected to influence the quality of the images produced. An increase in the overall turbidity of the water will adversely affect both in-line and off-axis techniques and would be expected to create a background noise that will reduce image fidelity.

Techniques, such as immersing the holographic plate in water during recording or direct replay back into water, have been used to minimize underwater aberrations, but such methods are generally impractical in the field. One practical solution, unique to holography, compensates the change of effective wavelength of light as it passes through water, by allowing a deliberate mismatch of recording and replay reference beams to balance the refractive index mismatch.

For holograms recorded and replayed in air, a usual prerequisite is that the reconstruction wavelength should remain unchanged from that used in recording. By noting the dependence of wavelength on the refractive index, we can apply the more general condition that it is the ratio λ/n that must remain constant. This relationship suggests that a hologram, immersed in water, and recorded at a wavelength λ_a will produce an aberration-free image in air when replayed at a reconstruction wavelength, λ_c, which is itself equivalent to the wavelength of light when passing through water, λ_w, i.e.:

$$\lambda_c = \lambda_w = \lambda_a n_a / n_w \qquad [3]$$

where n_a and n_w are the respective refractive indices of air and water. Thus, in principle, the aberrations may be completely eliminated by the introduction of an appropriate wavelength change between recording and replay. If a green (532 nm) laser is used in recording, the ideal replay wavelength is about 400 nm (i.e., 532 nm/1.33). However, no convenient laser lines exist at exactly this wavelength. Furthermore, complete correction assumes that the entire recording system be located in water. Since this is both impractical and undesirable, holograms are usually recorded with the holographic film in air behind a planar glass window. The additional glass and air paths affect the compensation of aberrations. However, third-order aberration theory shows that if the window-to-air path length ratio is appropriately chosen for a specific replay wavelength, then aberration balancing occurs and residual aberrations are reduced to a minimum over a wide range of field angles and object locations. For an air gap of 120 mm and a BK7 window of 30 mm thickness, a blue replay wavelength of 442 nm (HeCd laser) achieves a good performance over a full field angle of about 40°.

In most underwater applications the objects (or the camera) are in motion during the exposure. The effect of this motion is to blur out the finer fringes, and thus reduce resolution and contrast. In-plane motion is the most severe, and adopting the experimentally verified criterion that the maximum allowable motion is less than one-tenth of the minimum required fringe spacing of the smallest object, then for in-line holograms the maximum object motion must be less than one-tenth of the object's dimension. For particles of 10 μm dimension, and a typical Q-switched YAG laser pulse duration of 20 ns, a high transverse velocity of up to 50 m s^{-1} can be tolerated. Off-axis holograms are more demanding in their requirements and the maximum allowed velocity is reduced to about 3 m s^{-1}. This is, however, more than adequate for most field applications of the technique.

Underwater Holographic Cameras

The first-known use of holography for recording living marine plankton was by Knox in 1966, who recorded in-line holograms (ILH), using a short coherence length ruby laser, of a variety of living marine plankton species in a tank. However, to avoid problems with refractive index and wavelength changes, the holographic plate was immersed directly in water, which is completely impractical for field use. It was not until the late 1970s that quantitative data from replayed holograms of marine particles recorded *in situ* were obtained by Carder and his team. Small volumes (10 or 20 cm^3) were recorded using ILH and a low-power HeNe laser, which limited the technique to slowly moving objects. Later, Heflinger used the off-axis geometry with both pulsed argon-ion (514 nm) and pulsed xenon (535 nm) lasers to record plankton on 35 mm film. In order to compensate for the aberrations introduced by replaying the real image in air, the real image was projected back into the water tank using a conjugate beam from a continuous-wave argon laser. The sides of their tank were flexible so that the real image could be placed close to the exit window and viewed via an external microscope. Knox later developed a ship-borne in-line holographic camera which was deployed from the *RV Ellen B Scripps*. A pulsed xenon laser was used to record water volumes of up to 10^5 cm^3 to a water depth of 100 m.

It was not until the late 1990s that significant use of underwater holography for plankton recording came to the fore again. Joseph Katz at Johns Hopkins University, Baltimore, USA developed a camera based around a ruby laser to record in-line holograms on rolls of film, in a 63 mm diameter sample volume that can be varied from 100 to 680 mm in length. The camera housing utilizes a two-tube design with one tube holding the laser and another containing film holder and power units. The recording volume is situated 890 mm above the camera to minimize disturbance to flow. The camera is designed as a 'Lagrangian drifter' to move with the water current and was successfully deployed in Chesapeake Bay, Baltimore, and Solomon's Island, Maryland. Holograms were recorded of various species of phytoplankton and zooplankton and represented a significant advance in the deployment of sub-sea holography.

From the early 1980s, a team led by Aberdeen University, Scotland, investigated the use of underwater holography for offshore applications. Primary interest was in inspection of subsea pipelines for corrosion and damage, and much of the work concentrated on an analysis of the optical aberrations introduced by recording in water and replaying in air and methods of compensating for such aberrations. However, this work was later adapted for holography of plankton and led to the consequent development of the HoloMar system. The HoloMar camera was the first to incorporate simultaneous ILH and OAH recording.

More recent developments have utilized digital or electronic recording of holograms in the in-line mode, and it is to be expected that much more use will be made of 'e-holography' in the future.

For field applications of holography, it is essential to record the holograms using a pulsed laser in order to create stable interference fringes. For subsea purposes, a laser with a wavelength in the blue-green region of the spectrum will match the oft-quoted peak transmission window of seawater. In practice, a frequency-doubled Nd-YAG laser with a wavelength of 532 nm is a good choice, although ruby lasers operating at 694 nm are also acceptable if transmission distance is not an issue. Usually OAH requires more energy and places stricter constraints on coherence properties than ILH. Beam quality is governed by quality of the optical components in the beam path and also by the output beam of the laser itself. Because off-axis holography uses diffuse front/side illumination, energies of up to several hundred millijoules are often required for large (up to a meter in diameter) poorly reflective objects, and coherence lengths of greater than a meter are needed to record large scene depths. To obtain a long coherence length, and thus enable large-volume objects to be recorded, it is necessary that the laser operate in a single longitudinal cavity mode so that the bandwidth of the laser line is kept small. To enable smooth even illumination of both subject and holographic emulsion, good spatial beam quality is needed. This usually dictates laser output beams with either a Gaussian (TEM_{00}) mode profile or a flat profile, and spatial filtering during beam expansion. Compared to off-axis holography, the demands placed upon lasers for ILH are minimal. The only essential requirement is for a good spatial mode structure. Energy requirements are moderate: as little as 10 mJ is enough since little light is lost during the passage of the beam through the recording volume. The laser coherence length can be quite short, and only depends on the



Figure 7 The HoloMar camera configuration showing the separate in-line and off-axis beam paths.

effective hologram area, thus lasers operating on more than one longitudinal mode are usually quite suitable.

The HoloMar System

The HoloMar system (shown diagrammatically in Figure 7) was developed to record simultaneous in-line and off-axis holograms of partially overlapping, but orthogonal, views of the water column. Although the recording views are orthogonal to each other, the arrangement provides an element of cross-correlation between holograms. It is designed around a Q-switched, frequency-doubled Nd-YAG laser with an output energy of 700 mJ in a single pulse of less than 10 ns duration and a coherence length in excess of 2 m. The laser output is split into two beams: one of 100 mJ and the other of 600 mJ energy. The 100 mJ beam is further split into two equal energy beams and expanded and collimated to a diameter of about 90 mm. One path forms the illuminating beam for the in-line mode and the other path forms the reference beam for the off-axis mode. The in-line path records a water column of 470 mm by 90 mm diameter (9,000 cm^3) at 400 mm from the front face of the housing, whereas the off-axis hologram records almost the entire volume (50,000 cm^3) delineated by the front window to the end of the arms that house the in-line system (see Figure 7). Three 'lightrods', encompassing hollow perspex tubes with 10 glass beam-splitter plates distributed equally along the length, positioned at 45° to the main axis, provide roughly even side illumination to the off-axis volume. The front face of the camera is shown in Figure 8; the lightrods are positioned on either side of the recording volume (two on one side, one on the other). The exit window for the in-line beam path and the off-axis window can also be seen.


Off-axis window
Lightrods
In-line window
In-line recording volume delineated by space between in-line windows
Off-axis recording volume delineated by space between lightrods and off-axis window

Figure 8 Front-end of the HoloMar camera showing the 'lightrods' and in-line and off-axis windows.

Two motor-driven plate holders and transport mechanisms hold up to 20 plates for in-line and 24 for off-axis holograms. One pair of plates can be exposed every 10 seconds, or they can be exposed separately. The camera is remotely operated from the surface via a control console (PC). A network of micro-controllers serves as the backbone of the in-camera control system and communication between topside and camera modules is implemented using a Controller Area Network (CAN) bus via an umbilical cable. The entire camera is enclosed in a water-tight stainless steel housing of 1,000 mm diameter by 2,200 mm length. The prototype system is capable of either ship deployment or attachment to a fixed buoy and allows recording down to a water depth of 100 m.

The HoloMar camera is shown, in Figure 9, being lowered into Loch Etive, a sea loch on the west coast of Scotland, on its maiden dive. Figures 10 and 11 show holographic images of plankton recorded on this cruise. The first shows a view from a virtual



Figure 9 The HoloMar camera being lowered into Loch Etive, Scotland.



Figure 10 A photograph taken from a virtual image replay of an off-axis hologram recorded in Loch Etive.



Figure 11 Images of calanoid copepods from (a) an in-line hologram recorded at 70 m depth and (b) an off-axis hologram recorded at 60 m depth, the millimeter scale is added at the replay stage. Each organism is approximately 4 mm long.

replay of an off-axis hologram at a wavelength of 514 nm: this is what a viewer would see when looking from the inside of the holocamera into the laser-illuminated water. Each bright dot signifies an object of interest; two fiducial wires can also be seen fixed diagonally across the arms at the end of the camera, some 300 mm from the off-axis window. In the lower left of the image a long 'string-like' object about 40 mm long is probably 'floc', the dead organic matter that forms the food-stuff of many zooplankton. Objects like this would be destroyed in net-collection. Figure 11 shows images taken from the real image projection of in-line and off-axis holograms. The holograms are replayed using a collimated beam at wavelengths of 514, 488, 457, or 442 nm, depending on location in the image volume. Some of the contrasting features between in-line and off-axis holograms are apparent: the in-line image shows clearly the outline of the organism with detail resolvable down to about 10 μm, whereas the off-axis hologram, although not achieving this resolution, reveals the body structure of the organism.

List of Units and Nomenclature

d	dimension of object to be recorded
D	effective aperture of hologram
n	refractive index
n_a	refractive index of air
n_w	refractive index of water
r	minimum resolvable separation between two points on the hologram
s	distance between hologram and image location
z	distance between hologram and object location
λ	wavelength
λ_a	in-air wavelength of recording beam
λ_c	reconstruction wavelength
λ_w	effective wavelength of recording beam in water

See also

Holography, Applications: Holographic Recording Materials and Their Processing. **Holography, Techniques:** Computer-Generated Holograms. **Phase Control:** Phase Conjugation and Image Correction.

Further Reading

Beers JR, Knox C and Strickland JDH (1970) A permanent record of plankton samples using holography. *Limnology and Oceanography* 15: 967–970.

Carder KL (1979) Holographic microvelocimeter for use in studying ocean particle dynamics. *Optical Engineering* 18: 524–525.

Hariharan P (1984) *Optical Holography*, 2nd edn. Cambridge, UK: Cambridge University Press.

Heflinger LO, Stewart GL and Booth CR (1978) Holographic motion pictures of microscopic plankton. *Applied Optics* 17: 951–954.

Hobson PR and Watson J (2002) The principles and practice of holographic recording of plankton. *Journal of Optics A: Pure and Applied Optics* 4: S34–S49.

Katz J, Donathay PL, Zhang J, King S and Russell K (1999) Submersible holocamera for detection of particle characteristics and motions in the ocean. *Deep-Sea Research* 46: 1455–1481.

Kilpatrick JM and Watson J (1993) Underwater hologrammetry: reduction of aberrations by index compensation. *Journal of Physics D: Applied Physics* 26: 177–182.

Knox C (1966) Holographic microscopy as a technique for recording dynamic microscopic subjects. *Science* 153: 989–990.

Malkiel E, Alquaddoomi O and Katz J (1999) Measurements of plankton distribution in the ocean submersible holography. *Measurement Science and Technology* 10: 1141–1152.

Owen RB and Zozulya AA (2000) In-line digital holographic sensor for monitoring and characterizing marine particulates. *Optical Engineering* 39: 2187–2197.

Stewart GL, Beers JR and Knox C (1970) Application of holographic techniques to the study of marine plankton in the field and the laboratory. *Proceedings of SPIE* 41: 183–188.

Sun H, Dong H, Player MA, *et al.* (2002) In-line digital holography for the study of erosion processes in sediments. *Measurement Science and Technology* 13: L1–L6.

Watson J, Alexander S, Craig G, *et al.* (2001) Simultaneous in-line and off-axis subsea holographic recording of plankton and other marine particles. *Measurement Science and Technology* 12: L9–L15.

Holographic Recording Materials and Their Processing

H I Bjelkhagen, De Montfort University, Leicester, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The first off-axis transmission holograms in the USA were recorded on Kodak 649F spectroscopic silver halide material (now discontinued). For the first reflection holograms, which were recorded in Russia, a very fine-grain emulsion (Lippmann emulsion) had to be prepared to resolve the fine interference pattern associated with such holograms. Since then various types of recording materials for holography have been developed and manufactured, including improved silver halide emulsions.

The following provides a brief description of the holographic recording process. For recording holograms and holographic optical elements (HOEs), dichromated gelatin, photopolymer materials, and photoresist materials are employed, in addition to silver halide materials. Existing holographic recording materials are described, as well as suitable processing methods to obtain high-quality holograms and HOEs.

Holographic Recording Materials

To produce a hologram, a micropattern, caused by interference between the object beam and the reference beam, is recorded in a light-sensitive high-resolution material. The quality of a holographic image depends on a number of factors, such as: the geometry and stability of the recording setup; the coherence of the laser light; the reference and object beam ratio; the type of hologram produced; the size of the object and its distance from the recording material; the recording material and the emulsion substrate used; the processing technique applied as well as the reconstruction conditions. The material must comply with certain requirements to be suitable for this purpose. The most important of these concerns the resolving power of the material. The recording material must be able to resolve the highest spatial frequencies of the interference pattern created by the maximal angle θ between the reference and the object beams in the recording setup (Figure 1).

If λ is the wavelength of the laser light used for the recording of a hologram and n the refractive index of the emulsion, then the closest separation d_e between the fringes in the interference pattern created by the angle θ between the reference and the object beams in the recording setup is

$$d_e = \frac{\lambda}{2n \sin(\theta/2)} \qquad [1]$$


Reference beam (wavelength λ)
Object beam (wavelength λ)
θ
Refractive index n
Emulsion
d_e
Glass

Figure 1 Demand on resolution for recording a hologram.

For high-quality holograms the resolution limit of the material must be higher than the minimum value obtained according to the above formula. For a reflection hologram recorded in blue light ($\lambda = 400\,\text{nm}$) with an angle of 180° between the beams, a minimum resolving power of 7600 lines $(\text{mm})^{-1}$ is required.

In holography, the resolution of the holographic image and the resolving power of the recording material are not directly related to the way in which they are in photography.

Equation [1] gives the minimum resolving power needed to record a hologram. The resolution of the image depends on the area (diameter D) of the recording material, the recording laser wavelength (λ), and the distance (L) between the recording material and the object (Figure 2).

Theoretically, the resolution of the holographic image is the diffraction-limited resolution that can be obtained when the information is collected over an aperture equal to the size of the recording holographic plate. In principle, the larger the holographic plate the better the resolution will be. To obtain high image resolution, it is important that the recorded interference fringes will not change or be distorted during processing. To prevent that from happening, a stable support for the emulsion (like a glass plate) is needed and the processing method applied must not affect the recorded fringe pattern in the emulsion. In coherent imaging systems laser speckles are present which may also have an effect upon image resolution.

There are two main types of holograms: amplitude and phase holograms. In a pure amplitude hologram only the absorption varies with the exposure (after processing), whereas in a pure phase hologram, either the refractive index or the emulsion thickness varies with the exposure. If the hologram is thin, $d \approx 0$, phase variations are then caused by surface relief variations only. If the hologram is thick and has a negligible surface relief ($\Delta d = 0$), phase variations are caused by index variations only. In many cases, the phase modulation in a hologram is a combination of the two different extreme types (a complex hologram).

For amplitude holograms, amplitude transmission T_a against exposure or log exposure is used (Figure 3). For a phase hologram, the corresponding curve is the phase shift against the log exposure relation (Figure 4).

One of the most important hologram characteristics is its diffraction efficiency η. It is defined as the diffracted intensity E_i of the wanted diffraction order of the hologram in relation to the incident



Figure 2 Resolution of a holographic image depends on the area (diameter D) of the recording material, the recording laser wavelength λ, and the distance L between the recording material and the object.



Figure 3 Amplitude transmission T_a versus the logarithm of exposure H used for the characterization of amplitude transmission holograms.



Figure 4 Phase shift $\Delta\phi$ versus the logarithm of exposure H used for the characterization of phase transmission holograms.

intensity of the reconstruction beam E_r : $\eta = E_i/E_r$. In the definition of η, the incidental light losses caused by surface reflection and base absorption should be subtracted, but are often ignored. Other important hologram characteristics are the signal-to-noise ratio (SNR) and the dynamic range of the recording material.

The resolution capability of an image reproduction process is normally described by the Modulation Transfer Function (MTF). Briefly, a test pattern containing a sinusoidal variation in illuminance combined with a continuous variation in spatial frequency along one direction is recorded. The modulation M of the pattern in the test target is

$$M = (H_{\mathrm{MAX}} - H_{\mathrm{MIN}})(\mathrm{H}_{MAX} + \mathrm{H}_{MIN})^{-1} \qquad [2]$$

where **H** is the exposure incident on the photographic material. When this pattern is recorded in the material, light scattering will take place in the emulsion, which will reduce the original contrast of the pattern. Therefore, the modulation of the pattern will be decreased, in particular at high spatial frequencies. The effective exposure modulation M' will then be

$$\mathrm{M}' = (H'_{\mathrm{MAX}} - H'_{\mathrm{MIN}})(H'_{\mathrm{MAX}} + H'_{\mathrm{MIN}})^{-1} \qquad [3]$$

where **H**$'$ is exposure in the emulsion.

The original modulation M is constant and accurately known; it is also independent of the spatial frequency. After the tested emulsion has been processed, the corresponding 'exposed' modulation is obtained from the density variations. The ratio between modulation M' in the emulsion and modulation M of the incident exposure is called the modulation transfer factor, also called response

$$R = M(M')^{-1} \qquad [4]$$

If the response is plotted as the function of spatial frequency, this curve will then be the modulation transfer function of the material. The MTF for both a holographic emulsion and a conventional photographic emulsion are illustrated in Figure 5.

There are many ways of categorizing holograms but here we are mainly interested in definitions related to the recording material and its processing. One of the valid criteria is the thickness of the recording layer (as compared to the interference fringe spacing within the layer), i.e., the layer coated on the material substrate. Holograms can thus be classified into 'thin' or 'thick' (sometimes also called 'plane' or 'volume' holograms, respectively). To distinguish between the two types, the Q-parameter is normally used; it is defined in the following way:



Figure 5 Graphical representation of the modulation transfer function (MTF) curves for both a conventional emulsion and a holographic emulsion are shown.

$$Q = 2\pi\lambda d(n\Lambda^2)^{-1} \qquad [5]$$

where λ is the wavelength of the illuminating light, d is the thickness of the layer, n is the refractive index of the emulsion, and Λ the spacing between the recorded fringes. A hologram is considered thick if $Q \geq 10$, and thin if $Q \leq 1$. Holograms with Q-values between 1 and 10 can be treated as either thin or thick.

Recording Materials

The most common holographic materials used for recording holograms are the following: silver halide emulsions; dichromated gelatin emulsions; photopolymer materials; photoresist materials; thermoplastic materials; bacteriorhodopsin; and photorefractive crystals.

The following materials can also be considered for holographic recordings, but not many practical applications have been reported so far: chalcogenide glasses; ferroelectric-photoconductors; liquid crystals; magneto-optic films; metal and organic dye ablative films; photochromic and photodichroic materials; photothermorefractive glass; and transparent electrophotographic films.

Sensitivity of Photographic and Holographic Materials

The time of exposure for a given material will depend on the sensitivity of the material used, as well as on the intensity of the interference pattern. Some holographic materials must be processed after exposure in a specific way to obtain a hologram. The recorded intensity variations are converted during this processing step to local variations in optical density or refractive index and/or thickness of the recording layer.

Exposure H is defined as the incident intensity E times the time t of exposure of the recording material. If the intensity is constant during the whole exposure time, which is usually the case, then

$$H = Et \qquad [6]$$

Holographic materials are usually characterized using radiometric units. The radiometric equivalent of illuminance is irradiance. The unit of irradiance is $W(m)^{-2}$ and the exposure will then be expressed in $J(m)^{-2}$. The sensitivity of a holographic emulsion is most often expressed in $\mu J(cm)^{-2}$ or $mJ(cm)^{-2}$. Knowing the sensitivity of the material used and having measured the irradiance at the position of the holographic plate, the exposure time can be calculated using the above formula, i.e.,

$$\text{Exposure time} = \text{sensitivity/irradiance}$$

Holographic materials are sensitized in such a way that they are optimized for laser wavelengths commonly used in holography.

Silver Halide Materials

A silver halide recording photographic material is based on one type, or a combination of silver halide crystals embedded in a gelatin layer. The emulsion is coated on a flexible or stable substrate material. Silver-halide grain sizes vary from about 10 nanometers for the ultra-fine-grain holographic emulsions to a few micrometers for highly sensitive photographic emulsions (Table 1).

Silver salts are only sensitive to UV light, violet, and deep blue light. Therefore special sensitizers (dyes) must be added to the emulsion to make it sensitive to other parts of the spectrum. Orthochromatic emulsions are sensitive to green light. If the material has been sensitized to both green and red light, it is said to be panchromatic.

Table 1 Silver halide emulsion grain sizes

Type of emulsion	*Average grain diameter [nm]*
Ultra-fine-grain holographic emulsion	10–30
Fine-grain holographic emulsion	30–50
Fast holographic emulsion	50–100
Chlorobromide paper emulsion	200
Lithographic emulsion	200–350
Fine-grained photographic emulsion	350–700
Fast photographic emulsion	1000–2000
Fast medical X-ray emulsion	2500

In the following, silver halide materials manufactured by photographic and holographic companies are described. The main difference between the new materials and the previous emulsions from Agfa, Ilford, etc., is that for the current silver halide emulsions, the grain sizes are smaller. The present holographic silver halide emulsion manufacturing process is more or less based on the Russian ultrafine-grain emulsion technology.

Substrates for Holographic Emulsions

The material on which the emulsion is coated has a strong bearing on the final quality of the hologram. The best choice is often a glass plate as it is mechanically stable and optically inactive. High resolution imaging, hologram interferometry, holographic optical elements (HOEs) and spatial filters are a few examples where a very stable emulsion support is important. Mass produced holograms are mainly recorded on film substrates. However, the use of film has many advantages as compared to that of glass (breakage, weight, cost, size, etc.). Film substrates are used exclusively in the production of large-format holograms. Film substrates are of mainly two types: a polyester (polyethylene terephthalate); or a cellulose ester, commonly triacetate (cellulose triacetate) or acetate–butyrate. Polyester is mechanically more stable than triacetate film and it is also less sensitive to humidity. Because of the higher tensile strength, the polyester film can be made thinner than the triacetate film. On the other hand, polyester is birefringent, which can cause problems when recording holograms. In Table 2 most current commercial silver halide materials for holography are listed.

Processing of Silver Halide Emulsions

In silver halide emulsions a latent image is formed during exposure, which later is developed to a silver image. Processing (development, fixing, and bleaching) silver halide emulsions requires some expertise to obtain high-quality holograms. With the exception of DCG emulsions, other holographic materials are easier to process and more straightforward. Here it is not possible to describe all techniques employed and recipes used for silver halide processing. The reader is referred to the Further Reading section for more details.

Table 2 Commercial holographic recording materials

Material	*Thickness [μm]*	*Spectral sensitivity [nm]*	*Sensitivity [μJ (cm)$^{-2}$] at*				*Resolv. power [lp (mm)$^{-1}$]*	*Grain size [nm]*
			442	*514*	*663*	*694*		
SILVER HALIDE EMULSIONS:								
Slavich								
Red PFG-01	7	<700	–	–	80	–	>3000	35–40
Red PFG-03M	7	<700	–	–	1500	–	>5000	10–20
Green VRP-M	7	<550	–	80	–	–	>3000	35–40
Pan PFG-03C	9	400–700	1000	2000	1000	–	>5000	10–20
Colourholographic								
Red BB-700	7	<700	–	–	50	150	>2500	50–60
Red BB-640	7	<650	–	–	150	–	>4000	20–25
Green BB-520	7	<540	150	150	–	–	>4000	20–25
Blue BB-450	7	<470	150	–	–	–	>4000	20–25
Kodak								
Red 131PX	9	<650	2	–	0.5	–	>1250	70
Red 131CX	9	<650	2	–	0.5	–	>1250	70
Red 120PX	6	<750	60	–	40	40	>2500	58
Red 120CX	6	<750	60	–	40	40	>2500	50
FilmoTec-ORWO								
Red HF65	10	<650	–	–	1500	–	5000	30
Green HF53	10	<550	–	700	–	–	5000	30
Ultimate								
Ultimate 15	7	<700	–	150	150	150	>5000	15
Ultimate 08	7	<650	120	200	200	–	>7000	8
DICHROMATED GELATIN EMULSIONS								
Slavich								
Blue PFG-04	16	<515	1×10^5	2.5×10^5	–	–	10000	–
FilmoTec-ORWO								
Blue GF 40	6/20	*	*	–	–	–	–	–
* delivered: non-sensitized								
Holotec								
Custom orders only								
THERMOPLASTIC MATERIALS								
Tavex America								
Pan TCC-2	–	<800	1	1	1	1	1500	–
MD Diffusion								
Custom orders only								
PHOTORESIST MATERIALS								
Towne Technologies								
UV-Blue Shipley 1800	1.5–2.4	<450	1.5×10^5	–	–	–	1000	–
Hoya Corporation								
Custom orders only								
BACTERIORHODOPSIN MATERIALS								
MIB GmbH								
BR-WT B-type	30–100	<650	–	80×10^3	–	–	5000	–
BR-D96N M-type	30–100	<650	30×10^3	–	–	–	5000	–

The developing agent is the most important constituent in a holographic developer. In addition to the developing agent, a developer consists of the following components: a preservative (or antioxidant); a weak silver-solvent agent; an accelerator (or activator); a restrainer; and a solvent which is usually water. Employing a developer which contains a silver-solvent agent, solution-physical development or semi-physical development can be performed. Such a developer is particularly suitable for processing the ultrafine-grain emulsions.

Holographic Developers

Silver halide materials for holography are all of the fine-grain type. Such materials require the application of special processing techniques to achieve the best possible results. For the processing of amplitude holograms a high-contrast developer is required, such as Kodak D-19. For holograms which are going to be bleached (phase holograms), developers based on ascorbic acid, hydroquinone, metol, pyrocatechol, or pyrogallol are frequently used. The following developers are recommended for the new silver halide materials: D-19; CW-C2; AAC; MAA-3; PAAP; and for pulsed laser recordings, the SM-6 developer. Colloidal development, employing a highly diluted developer which contains silver solvents, is recommended for the ultrafine-grain emulsions. Colloidal silver grains formed in the emulsion during such development are very small which means that very little absorption occurs. The method produces holograms with high diffraction efficiency combined with very low light scattering noise. The Russian GP-2 developer is recommended for colloidal development. Recipes for common holographic developers are found in Table 3.

Bleach Baths

Bleaching is used to convert a developed hologram (containing a silver image) into a phase hologram, to obtain a higher diffraction efficiency than is possible for amplitude holograms. During bleaching the silver image is converted into a water-soluble or an insoluble silver compound. Holographic bleaching techniques can be divided into three categories:

1. Conventional or direct (rehalogenating) bleaching;
2. Fixation-free rehalogenating bleaching;
3. Reversal (complementary) or solvent bleaching.

In conventional bleaching, the developed silver image is, after fixing, converted into a transparent silver halide compound, i.e., after the unexposed silver halide crystals have been removed. This method is not recommended for ultrafine-grain emulsions. Instead the fixation-free rehalogenating bleaching is preferred. The hologram is bleached directly after development, without fixing, leaving the unexposed silver halide crystals in the emulsion. A rehalogenating bleach bath consists of: an oxidizing agent; an alkali halide (often KBr); and a buffer. Among the rehalogenating bleaches, the following bleach baths work well: PBQ-bleach; Ferric EDTA; and the PBU-bleaches (PBU-amidol or the PBU-metol).

In reversal bleaching, the developed silver image is not fixed. Instead it is converted into a soluble silver complex which is removed from the emulsion during bleaching, leaving only the original unexposed silver halide grains in the emulsion. A reversal bleach bath consists of an oxidizing agent and a buffer. For ultrafine-grain silver halide emulsions, the reversal method is not recommended. The very small unexposed silver halide grains are also affected (partly dissolved) during reversal bleaching, resulting in low diffraction efficiency. For materials with larger grains, a more diluted version of the dichromate Kodak R-9 bleach can be

Table 3 Developers for silver halide emulsions

Constituents	*CWC2*	*GP-2*	*MAA-3*	*PAAP*	*AAC*	*SM6*
Methylphenidone		0.2 g				
Catechol	10 g					
Ascorbic acid	5 g		10 g	18 g	16 g	18 g
Hydroquinone		5 g				
Metol			2.5 g			
Phenidone				0.5 g		6 g
Sodium sulfite	5 g	100 g				
Sodium phosphate (diabasic)				28.4 g		28.4 g
Urea	50 g					
Potassium hydroxide		5 g				
Sodium hydroxide				12 g		12 g
Sodium carbonate	30 g		55.6 g		60 g	
Ammonium thiocyanate		12 g				
Distilled water	1 l	1 l	1 l	1 l	1 l	1 l
Dilution:	no	15 ml dev. + 400 ml water	no	no	no	no

Table 4 Bleach baths for silver halide emulsions

Constituents	*Ferric-EDTA (rehal.)*	*PBQ (rehal.)*	*PBU-(amidol/metol) (rehal.)*	*Copper (rehal.)*	*Chrome (reversal)*	*PSSB (reversal)*
Amidol *or* metol*			1 g			
Cupric bromide			1 g			
Potassium persulfate			10 g			20 g
Potassium dichromate					4 g	
p-Benzoquinone		2 g				
Ferric III sulfate	30 g					30 g
Copper sulfate				35 g		
Disodium EDTA	30 g					
Boric acid		1.5 g				
Citric acid			50 g			
Potassium bromide	30 g	30 g	20 g	30 g		
Sodium hydrogen sulfate	30 g			30 g		30 g
Sulfuric acid					4 ml	
Distilled water	1 l	1 l	1 l	1 l	1 l	1 l

*To be added after all other constituents have been dissolved.

used. Recipes for common holographic bleach baths are found in Table 4.

Commercial Silver Halide Emulsions

In Table 2 most of the current silver halide holographic emulsions are listed. The main manufacturer of holographic silver halide emulsions is the Micron branch of the SLAVICH Joint Stock Company photographic company located outside Moscow (2 pl. Mendeleeva, 152140 Pereslavl-Zalessky, Russia, www.slavich.com). Both film (triacetate) and glass plates are manufactured. Many different sizes are produced, including 115 cm by 10 m film rolls. Recommended holographic developers: CW-C2, SM-6. Many rehalogenating holographic bleach baths work well and, in particular, the PBU-type bleaches are recommended.

Colourholographic Ltd is a new company based in England (Braxted Park, Great Braxted, Witham CM8 3BX, England; www.colourholographic.com). The Colourholographic materials are based on the HRT emulsion, previously manufactured in Germany by Dr Birenheide. At the present time only glass plates are manufactured in England. Recommended processing solutions for the new HRT materials are a sodium-sulfite-free ascorbic acid–metol developer followed by a rehalogenating ferric EDTA or PBU bleaches. For reflection holograms, a pyrogallol developer and the ferric-EDTA bleach can be used.

Eastman Kodak's holographic materials are produced in America (343 State Street, Rochester, New York 14650, USA; www.kodak.com/go/PCB products). These plates are usually made to order only. Materials can be ordered with (marked -01) or without (marked -02) anti-halation layer. The 120 emulsion can be used for recording holograms using a pulsed ruby laser. Kodak recommends the developer Kodak D-19 for the processing.

FilmoTec is located in Germany (Chemie Park Bitterfeld-Wolfen, Röntgenstrasse, D-06766 Wolfen, Germany; www.filmotec.de). The company manufactures ORWO holographic emulsions which are coated only on triacetate film, 104 cm wide in 10 and 30 m lengths.

In France, M. Yves Gentet has started a small-scale emulsion manufacturing company: Atelier de Création d'Art en Holographie Yves Gentet (50, rue Dubourdieu, F-33800 Bordeaux, France; www.perso.wanadoo.fr/holographie) Monochromatic and panchromatic ultrafine-grain emulsions are produced called 'Ultimate'. Plates and film up to 60 cm by 80 cm are produced. An ascorbic acid–metol developer is recommended followed by a Ferric EDTA bleach. In addition, the Russian GP-2 developer can be used. Also a special developer can be ordered from the company.

Konica in Japan is manufacturing a green-sensitive emulsion for the use in the American holographic VOXEL 3D medical imaging system and, in addition, for the Japanese market only.

Dichromated Gelatin Materials

Dichromated gelatin (DCG) is an excellent recording material for volume phase holograms and HOEs. The grainless material has its highest sensitivity in the UV region, but extends into the blue and green parts of the spectrum. There are possibilities to sensitize the emulsion in the red part of the spectrum as well. However, DCG is most often exposed with blue laser wavelengths. Depending on processing parameters, diffraction efficiency and bandwidth can be controlled. It is easy to obtain high diffraction efficiency combined with a large SNR.

During the exposure of a DCG emulsion to UV or blue light, the hexavalent chromium ion (Cr^{6+}) is photo-induced to trivalent chromium ion (Cr^{3+}) which causes cross-linking between neighboring gelatin molecules. The areas exposed to light are hardened and become less soluble than the unexposed areas. Developing consists of a water wash which removes the residual or unreacted chemical compounds. Dehydration of the swollen gelatin follows after the material has been immersed in isopropanol, which causes rapid shrinkage resulting in voids and cracks in the emulsion, thus creating a large refractive index modulation. The underlying mechanism is not completely clear because high modulation can also be caused by the binding of isopropanol molecules to chromium atoms at the cross-linked sites. The DCG material has a rather low sensitivity of about $100\,\mathrm{mJ(cm)^{-2}}$. In many cases DCG plates are prepared by fixing an unexposed silver halide emulsion and then sensitizing it in a dichromate solution. It is also, for example, possible to make a 10 μm thick emulsion on a 8″ by 10″ glass plate using 1 g ammonium dichromate mixed with 3 g photographic grade gelatin in 25 ml deionized water. Then the emulsion is spin-coated on the glass substrate or the emulsion is applied by the doctor blade coating technique. Many HOE manufacturers prefer to produce their own emulsions but there are also commercial DCG emulsions available on the market.

Processing of DCG holograms are performed in graded alcohol (propanol) baths starting with water–propanol solutions of high water content and ending with pure propanol (cold or hot) baths. Depending on the wanted HOE characteristics, one has to carefully control the propanol/water mixtures as well as the temperature of the different baths. Cold baths produce better uniformity and lower noise. Warm baths can yield high index modulation but often with increased noise. The bandwidth can be controlled by the processing temperature and the ratio of propanol/water mixtures.

Commercial DCG Materials

Slavich in Russia is one manufacturer of presensitized dichromated plates for holography. The DCG emulsion is marked PFG-04. Plates up to a size of 30 by 40 cm can be ordered.

The FilmoTec DCG emulsions are only available on 190 μm triacetate film, 104 cm wide in 10 and 30 m lengths; emulsion thickness 6 or 20 μm. Note that the film needs to be sensitized in dichromate solution before recording. This means that the company only supplies large-format gelatin-coated film.

Holotec is a German-based company which offers presensitized DCG coated on both plates and film (Jülicher Strasse 191, D-52070 Aachen, Germany; www.holotec.de). The Holotec emulsion is the high-quality DCG emulsions developed by Professor Stojanoff in Aachen. The company can supply large-format DCG glass plates (m^2 size) or film (PET-Polyethylenterephtalat), pre-sensitized and ready to use.

Photopolymer Materials

Photopolymer materials have become popular for recording phase holograms and HOEs, in particular for mass production of holograms since some photopolymer materials only require dry processing techniques.

A photopolymer recording material, such as the DuPont material, consists of three parts: a photopolymerizable monomer; an initiator system (initiates polymerization upon exposure to light); and a polymer (the binder). First, an exposure is made to the information-carrying interference pattern. This exposure polymerizes a part of the monomer. Monomer concentration gradients, formed by variation in the amount of polymerization due to the variation in exposures, give rise to diffusion of monomer molecules from the regions of high concentration to the regions of lower concentration. The material is then exposed to regular light of uniform intensity until the remaining monomer is polymerized. A difference in the refractive index within the material is obtained. The DuPont material requires only a dry processing technique (exposure to UV light and a heat treatment) to obtain a hologram. The DuPont photopolymer materials have a coated film layer thickness of about 20 μm. The photopolymer film is generally coated in a 12.5″ width on a 14″ wide Mylar® polyester base which is .002″ thick. The film is protected with a .00092″ thick Mylar® polyester cover sheet.

The recording of a hologram on DuPont polymer is rather simple. The film has to be laminated to a piece of clean glass or attached to a glass plate using an index-matching liquid. Holograms can be recorded manually, but in order to produce large quantities of holograms, a special machine is required. For hologram replication a laser line scanning technique can provide the highest production rate.

The photopolymer material needs an exposure of about 10 mJ(cm)$^{-2}$.

After the exposure is finished, the film has to be exposed to strong white or UV light. DuPont recommends about 100 mJ(cm)$^{-2}$ exposure at 350–380 nm. After that, the hologram is put in an oven at a temperature of 120 °C for two hours in order to increase the brightness of the image. The process is simple and very suitable for machine processing using, for example, a baking scroll oven.

Commercial Pholymer Materials

Currently the only manufacturer of holographic photopolymer materials is E.I. du Pont de Nemours & Co. (DuPont Holographics, POB 80352, Wilmington, DE 19880, USA; www.dupont.com/holographics). In the past it was possible to obtain photopolymer materials from DuPont, but in 2002 the company changed its policy and today it is producing materials mainly for DuPont Holographics, but approved customers may still be able to buy material from DuPont. The reason for the restrictions is that many applications of mass-produced holograms are in the field of document security, where DuPont's photopolymers are used to produce optical variable devices (OVDs).

Photoresist Materials

Photoresist materials in holography are used for making masters for display and security holograms. The recorded relief image in the photoresist plate is then used to make the nickel shim needed as the tool for embossing holograms into plastic materials.

The exposure to actinic radiation produces changes in the photoresist layer that result in a solvency differentiation as a function of exposure. Processing is done with a suitable solvent dissolving either the unexposed or exposed regions, depending on whether the resist is of the negative or the positive type. For optical recording, positive photoresist (exposed resist removed during development) is preferred to the negative type because of the higher resolving power and low scatter. On the resulting surface, relief pattern particles of nickel are deposited by electrolysis to make a mold, which can then be used as an embossing tool. The photoresist process can be used for making transmission holograms only. If an embossed hologram is mirror-backed by using, for example, an aluminum coating process, it can be used in the reflection reconstruction mode as well. Photoresists are UV and deep-blue sensitive. The material is spincoated on glass substrates to obtain a thickness of between 0.5 and 2 μm, then it is baked at about 75 °C for 15 minutes. A typical photoresist for holography (e.g., Shipley Microposit 1350) has a sensitivity of about 10 mJ(cm)$^{-2}$. The most common laser wavelengths for recording photoresist holograms are the following wavelengths: 413 nm (Krypton-ion), 442 nm (Helium–Cadmium), and 458 nm (Argon-ion). At higher wavelengths, e.g., 488 nm, the sensitivity is rather low. Development of Shipley resist is performed in Shipley 303A developer, diluted 1 part developer + 5 parts de-ionized water. Normally only a 10 second development time is needed (under agitation). After that the plate has to be rinsed in de-ionized water for 2 minutes. The plate needs to be dried quickly with a high pressure steam of compressed nitrogen or dry, filtered compressed air.

Commercial Resist Materials

The main American manufacturer of photoresist is Shipley Co. (1457 Macarthur Rd., #101, Whitehall, PA 18052, USA). There are a few companies which make plates based on Shipley resist.

Towne Technologies, Inc. (6–10 Bell Ave., Sommerville, NJ 08876, USA; www.townetech.com) produces spin-coated plates using Shipley resist (Shipley S-1800 series). Towne plates have a sublayer of iron oxide which enhances adhesion of the resist during electroplating operations. In addition, the sublayer eliminates unwanted backscatter from the glass substrate. The plates are developed in Shipley 303A developer.

Hoya Corporation (7-5 Naka-Ochiai 2-chome, Shinjuku-ku, Tokyo, Japan; www.hoya.co.jp) is a producer of mask blanks coated with 0.5 μm thick Shipley S-1800 resist (SLW plates). Different types of glass as well as quartz plates are produced. Hoya supply plates for holography, however, custom orders only.

Thermoplastic Materials

The holographic thermoplastic is a multilayer structure coated on glass or film. The substrate is first coated with a conducting layer, e.g., evaporated gold, then a photoconductor, e.g., poly-n-vinyl carbazole, PVK, that has been sensitized with, e.g., 2,4,7-trinitro-9-fluorenone (TNF), and on top of this layer a thermoplastic coating is deposited (usually a styrene-methacrylate material). The recording of a hologram starts with a uniform charging of the surface of the thermoplastic material using a corona charger. The charge is divided between the photoconductor and the thermoplastic layer. Exposure and the consequent photogeneration in the photoconductor cause charges of opposite signs to migrate to the interface with the thermoplastic layer and the substrate. This will not change the charge, but only decrease the surface potential. Before the image can be developed, the material has to be recharged with the uniform corona charger. This step adds additional charges to the exposed areas, in proportion to the reduced potential which is also proportional to the exposure. The material is then heated to a softening temperature of the thermoplastic layer which will be deformed due to the electrostatic forces acting on it. The material is then cooled and the image is fixed as a relief surface pattern in the thermoplastic layer. The processing time after the exposure necessary to obtain the image is between ten seconds and half a minute. If the material is heated to a somewhat higher temperature, the pattern disappears and the image is erased. The thermoplastic material can now be used for the recording of another hologram, repeating the recording procedure. Such a cycling technique can be repeated hundreds of times, without any serious effect on the quality of the image. That, and the fast dry processing made such materials popular for the use in holographic cameras for nondestructive testing. The sensitivity is between 10 and 100 $\mu J(cm)^{-2}$ over the whole visible electromagnetic spectrum.

Commercial Thermoplastic Materials

In the past, several companies produced thermoplastic materials and recording equipment for holography. Since there is very little demand for such materials today, there is only one company which can deliver thermoplastic equipment for holography: Tavex America Inc. (14 Garden Road, Natick, MA 01760, USA; www.tavexamerica.com). Tavex America manufactures a thermoplastic camera, TCC-2 in which 40 mm by 40 mm plates are used. For obsolete systems, thermoplastic film can still be obtained from MD Diffusion in France (93 rue d'Adelshoffen, F67300 Schiltigheim, France).

Bacteriorhodopsin

Photochromic materials, a class to which bacteriorhodopsin (BR) belongs, have not been used much in holography. Photochromics are real-time recyclable materials which need no processing for development. They can easily be erased and reused over and over again. In holography the only successful material has been the BR film which was introduced only a few years ago. BR is a biomolecule with several applications in photonics, comprising a light-driven molecular proton pump with exceptional photoelectric and photochromic properties. BR is a photochromic protein, found in the photosynthetic system of a salt-marsh bacterium, termed purple membrane (PM), of the cell membrane of *Halobacterium salinarum*. BR thin films are made from polymer suspensions of the isolated purple membrane. Some of the desirable properties of BR films are real-time writing and erasing in microsecond time-scales, durability allowing millions of write/erase cycles without degradation, very high spatial resolution of 5000 $lp(mm)^{-1}$, reasonably good light sensitivity of approximately 10 $mJ(cm)^{-2}$, the encoding of both amplitude and phase patterns, and the use of visible laser light for writing and reading. The composition of the films may also be altered by chemical means to control the optical characteristics, and the BR molecules themselves may be mutagenically changed for performance optimization. Particular properties that can be enhanced in these ways are image lifetimes and the diffraction efficiency of holograms recorded in the films. One advantage of this material is that it is reversible. Therefore it has been considered to be used in holographic storage systems and for real-time holographic interferometry applications. BR film can be used for recording polarization holograms because of BR films inherent photo-inducable optical anisotropy. The material is also possible to expose with pulsed lasers, which makes it suitable for fast holographic recording.

The BR film works in the following way. When illuminated with green light, the BR molecule undergoes an absorption resulting in a maximum shift of about 160 nm towards the red and its color changes from purple to yellow. The yellow image can be erased by illuminating the BR material with blue light. The recording–erasing cycle can be repeated about a million times. Suitable BR-films for holography are obtained by embedding purple membranes into inert matrices like polyvinylalcohol or polyacrylamide. For hologram recording and erasure two photochemical conversions $B \rightarrow M$ (B-type holograms) and $M \rightarrow B$ (M-type holograms) can be employed. After excitation by light, BR cycles through a sequence of spectrally distinguishable intermediates and returns to the initial state. The time associated with this thermal relaxation process depends on several aspects, for example, type of BR (wildtype or variant), pH value of film-matrix, film-temperature, etc. For example, the M intermediate is populated from the B state (absorption spectrum peaked at 570 nm) by a green pumping beam and information is recorded with blue light, which initiates the photochemical $M \rightarrow B$ transition. The M state has its absorption peak at 410 nm. In BR variants in which the thermal relaxation of the M state has been prolonged, photocontrolled switching between these two states can be achieved. Only when the pumping beam is incident upon the BR film can information be recorded with blue light. The pumping beam can be used as a readout beam for the recorded hologram.

Commercial BR Materials

A holographic camera based on a BR film is manufactured in Germany. The holographic system, FringeMaker-*plus*, developed at the University of Marburg is marketed by Munich Innovation Biomaterials (MIB) GmbH. (Hans-Meerwein-Str., D-35032 Marburg, Germany; www.mib-biotech.de). MIB is also a manufacturer of both wildtype and genetically modified BR film for holography and other scientific/technical applications. BR-films offered by MIB can be used in two different recording configurations: the transition from the initial B to M-state (induced with yellow light) serves as basis for optical data recording and processing (B-type recording); or the photochemically induced transition from M to B state (M-type recording). In the latter case, yellow light is used to control the population of the M-state and blue light is used to write the information. MIB offers BR-films with normal and slow thermal relaxation characteristics. Typical relaxation time ranges (RTR), after which the photochemically excited BR molecules have returned to the original state, are between 0.3 and 80 s. The BR film is sealed between two windows of high-quality optical glass. The BR film layer has a thickness of 30–100 μm, dependent on the optical density of the film. The diameter of the film device is 25 mm and the clear aperture is 19 mm.

Photorefractive Crystal Materials

Photorefractive crystals are electro-optic materials which are suitable for recording volume phase holograms in real-time. These crystals are important components in holographic storage systems and are seldom used in other holographic image applications. Holograms recorded in crystals, such as: lithium niobate ($LiNbO_3$); barium titanate ($BaTiO_3$); potassium tantalate niobate (KTN); barium sodium neobate (SBN); bismuth silicon oxide (BSO); and bismuth germanium oxide (BGO), consist of bulk space charge patterns. An interference pattern acting upon a crystal will generate a pattern of electronic charge carriers that are free to move. Carriers are moving to areas of low optical illumination where they get trapped. This effect will form patterns of net space charge, creating an electrical field pattern. As these crystals have strong electro-optic properties, the electrical field pattern will create a corresponding refractive index variation pattern, which means a phase hologram. These holograms can be immediately reconstructed with a laser beam differing from the beams creating the hologram. A hologram can also be erased and a new hologram can be recorded in the crystal. Holograms can be fixed by converting the charge patterns to the patterns of ions which are not sensitive to light. In some materials the hologram can be fixed by heating the crystal to above 100 °C based on thermally activated iconic conductivity. The resulting iconic is frozen upon cooling the crystal back to room temperature. More details about these materials and storage applications are found in the Further Reading.

See also

Holography, Techniques: Overview.

Further Reading

Bjelkhagen HI (1993) *Silver Halide Recording Materials for Holography and Their Processing*. Springer Series in Optical Sciences, vol. 66. Heidelberg: Springer-Verlag.

Bjelkhagen HI (ed.) (1996) *Selected Papers on Holographic Recording Materials*. SPIE Milestone Series, vol. MS130. Bellingham, WA, USA.

Lessard RA (ed.) (1995) *Selected Papers on Photopolymers, Physics, Chemistry, and Applications*. SPIE Milestone Series, vol. MS114. Bellingham, WA, USA.

Sincerbox GT (ed.) (1994) *Selected Papers on Holographic Storage*. SPIE Milestone Series, vol. MS95. Bellingham, WA, USA.

Smith HM (ed.) (1977) *Holographic Recording Materials*, Springer Topics in Applied Physics, vol. 20. Berlin: Springer-Verlag.

HOLOGRAPHY, TECHNIQUES

Contents

Overview
Color Holography
Computer-Generated Holograms
Digital Holography
Holographic Interferometry
Sandwich Holography and Light in Flight

Overview

C Shakher and A K Ghatak, Indian Institute of Technology, New Delhi, India

© 2005, Elsevier Ltd. All Rights Reserved.

Major Milestones

1948:	Essential concept for holographic recording by Dennis Gabor.
1960:	The first successful operation of a laser device by Theodore Maiman.
1962:	Off-axis technique of holography by Leith and Upatnieks.
1962:	Yu N Denisyuk suggested the idea of three-dimensional holograms based on thick photoemulsion layers. His holograms can be reconstructed in ordinary sunlight. These holograms are called Lippmann–Bragg holograms.
1964:	Leith and Upatnieks pointed out that a multicolor image can be produced by a hologram recorded with three suitably chosen wavelengths.
1969:	S A Benton invented 'Rainbow Holography' for display of holograms in white light. This was a vital step to make holography suitable for display applications.

Holography is the science of recording an entire optical wavefront, both amplitude and phase information, on appropriate recording material. The record is called a hologram. Unlike conventional photography, which records a three-dimensional scene in a two-dimensional format, holography records true three-dimensional information about the scene.

Holography was invented by Gabor in 1948 and his first paper introduced the essential concept for holographic recording – the reference beam. Holography is based on the interference between waves and, it provides us with a way of storing all the light information arriving at the film in such a way that it can be regenerated later.

The use of the reference beam is utilized because the physical detectors and recorders are sensitive only to light intensity. The phase is not recorded but is manifest only when two coherent waves of the same frequency are simultaneously present at the same location. In that case, the waves combine to form a single wave whose intensity depends not only on intensities of the two individual waves, but also on the phase difference between them. This is key to holography. The film record, or hologram, can be considered as a complicated diffraction grating. Holograms bear no resemblance to conventional photographs in that an image is not actually recorded. In fact, the interferometric fringes which are recorded on the recording material are not visible to an unaided eye because of extremely fine interfringe spacing (~ 0.5 micrometer). The fringes which are visible on the recording material are the result of dust particles in the optical system used to produce the hologram.

Gabor's original technique is now known as in-line holography. In this arrangement, the coherent light source as well as the object, which is a transparency containing small opaque details on a clear background, is located along the axis normal to the photographic plate. With such a system, an observer focusing on one image observes it superposed on the out-of-focus twin image as well as a strong coherent background. This constitutes the most serious problem of Gabor's original technique.

The first successful technique for separating the twin images was developed by Leith and Upatnieks in 1962. This is called the off-axis or side band technique of holography. We shall consider mainly the off-axis technique here.

Basic Holography Principle

Light from a laser or any light beam is characterized by spatial coherence (l_c) and temporal coherence (τ_c), which is discussed in all textbooks on optics. For typical laboratory hologram recording, the required degree of coherence of laser radiation is determined by the type of object and geometrical arrangement being used for the recording. The following condition must hold:

$$L \ll c\tau_c \qquad [1]$$

where τ_c is the coherence time, and L the maximum path length difference between the two waves chosen to record the hologram. To begin recording, two wavefronts are derived from the same laser source. One wavefront is used to illuminate the object and another is used as a reference wavefront. The wavefront derived by illuminating the object is superimposed with the reference wave and the interference pattern is recorded. These object and reference waves must:

- be coherent (derived from the same laser); and
- have a fixed relative phase at each point on the recording medium.

If the above conditions are not met, the fringes will move during the exposure and the holographic record will be smeared. Therefore, to record the hologram one should avoid air currents and vibrations. The recording medium must have sufficient resolution to record the fine details in the fringe pattern. This will be typically of the order of the wavelength. To create a three-dimensional image from the holographic process one then has to record and reconstruct the hologram. The object and reference waves are derived from the same laser.

Holograms record an interference pattern formed by interference of object and reference wavefronts, as explained above. We may mention here that for the two plane waves propagating at an angle θ between them, the spacing of the interference fringes is given by

$$\alpha = \frac{\lambda_0}{2\sin(\theta/2)} \qquad [2]$$

where λ_0 is the free space wavelength.

Processing of the hologram (developing, fixing, and washing of the recording material) yields a plate with alternating transparent and opaque parts, variation of refractive index, or variation of height corresponding to intensity variation in the fringe pattern. Such a plate can be regarded as a complicated diffraction grating. In this process, the hologram is illuminated with monochromatic, coherent light. The hologram diffracts this light into wavefronts which are essentially indistinguishable from the original waves which were diffracted from the object. These diffracted waves produce all the optical phenomena that can be produced by the original waves. They can be collected by a lens and brought into focus, thereby forming an image of the original object, even though the object has since been removed. If the reconstructed waves are intercepted by the eye of an observer, the effect is exactly as if the original waves were being observed; the observer sees what appears to be the original object in true three-dimensional form. As the observer changes his viewing position, the perspective of the image scene changes; parallactic effects are evident and the observer must refocus when the observation point is changed from a near to a distant object in the scene. Assuming that both the construction and reconstruction of the hologram are made with the same monochromatic light source, there is no visual test which can be made to distinguish between the real object and the reconstructed image of the object. It is as if the hologram were a window through which the apparent object is viewed.

Hologram of a Point Object

Consider a hologram recorded with a collimated reference wave normal to the recording plate and a point object inclined at a certain angle. If the hologram is illuminated once again with the same collimated reference wave, it reconstructs two images, one virtual true image and the other real image. However, the two images differ in one very important respect.

While the virtual image is located in the same position as the object and exhibits the same parallax properties, the real image is formed at the same distance from the hologram but in front of it. Corresponding points on the real and virtual images are located at equal distances from the plane of the hologram; the real image has the curious property that its depth is inverted. Such an image is not formed with a normal optical system; it is therefore called a pseudo image as opposed to a normal or orthoscopic image.

This depth inversion results in conflicting visual clues, which make viewing of the real image psychologically unsatisfactory. Thus, if O_1 and O_2 are two elements in the object field, and if O_1 blocks the light scattered by O_2 at a certain angle, the hologram records information only on the element O_1 at this angle and records no information about this part of O_2. An observer viewing the real image from the corresponding direction then cannot see this part of O_2, which, contrary to normal experience, is obscured by O_1, even though O_2 is in front of O_1.

Production of an Orthoscopic Real Image

An orthoscopic real image of an object can be produced by recording two holograms in succession. In the first step, a hologram is recorded of the object with a collimated reference beam. When this hologram is illuminated once again with the collimated reference beam that was used to record it, it reconstructs two images of the object at unit magnification, one of them being an orthoscopic virtual image, while the other is a pseudoscopic real image. A second hologram is then recorded of this real image with a second collimated reference beam.

When the second hologram is illuminated with a collimated beam it reconstructs a pseudoscopic virtual image located in the same position as the real image formed by the second hologram is an orthoscopic image. Since a collimated reference beam is used throughout, the final real image is the same size as the original object and free from aberrations.

In addition to these characteristic linked intensities with the three-dimensional nature of the reconstruction, the holographic recording has several other properties. Each portion of the hologram can reproduce the entire image scene. If a smaller and smaller portion of the hologram is used for reconstruction, there is loss of image intensity and reconstruction. When a hologram is reversed, such as in contact printing processes, it will still reconstruct a positive image indistinguishable from the image produced by the original hologram.

Simple Mathematical Description of Holography

Let the object and reference waves be given by

$$U_o = O(x, y)e^{i\phi(x,y)} \qquad [3]$$

and

$$U_r = R\, e^{iky\sin\theta} \qquad [4]$$

U_r describes the reference (plane wave) propagating at angle θ to the z-axis.

The intensity at the hologram plane is

$$\begin{aligned} I &= |U_r + U_o|^2 \\ &= |U_r|^2 + |U_o|^2 + U_r^* U_o + U_r U_o^* \end{aligned} \qquad [5]$$

As can be seen from the above equation, the amplitude and phase of the wave are encoded as the amplitude and phase modulation of a set of interference fringes. The material used to record the patterns of interference fringes described above is assumed to provide linear mapping of the intensity incident during the reconstruction process into amplitude transmitted by or reflected from the recorded material. Usually both light detection and wavefront modulation are performed by photographic plate/film. We assume the amplitude transmission properties of the plate/film after processing to be described by

$$T = T_o - b(E - E_o) \qquad [6]$$

where the exposure E, at the film is $E = I\tau$; here τ is the exposure time. T_0 is the transmittance of the unexposed plate.

If the hologram is reilluminated by the reference wave, the transmitted wave amplitude will be

$$U_t = U_r(T_o - b\tau(|U_o|^2 + U_r^* U_o + U_r U_o^*)) \qquad [7]$$

The first term is reference wave times a constant. The second term is the reference wave modulated by $|U_o|^2 = O(x, y)^2$; it gives small-angle scattering about the reference wave direction. The third term is proportional to U_o. It is the same as the original object wave (note this is only so if the reconstruction wave is identical to the reference wave). The fourth term is

$$-b\tau U_r^2 U_0^* = -b\tau R^2\, e^{iky2\sin\theta} O(x, y)e^{-i\phi(x,y)} \qquad [8]$$

This is essentially a wave traveling in a direction $\sin^{-1}(2\sin\theta)$ to the z-axis, with the correct object amplitude modulation but its phase reversed in sign, producing a conjugate wave.

Types of Holograms

Primarily, the holograms are classified as thin and thick, based on the thickness of the recording medium. When the thickness of the recording medium is small compared with the average spacing of the interference fringes, the hologram can be treated as a thin hologram. Such holograms are characterized by spatially varying complex amplitude transmittance:

$$\mathbf{t}(x,y) = [\mathbf{t}(x,y)]\exp[-\mathrm{i}\phi(x,y)] \qquad [9]$$

Thin holograms can be further categorized as thin amplitude holograms or thin phase holograms. If amplitude transmittance of the hologram is such that $\phi(x,y)$ is constant while $\mathbf{t}(x,y)$ varies over the hologram, the hologram is termed an amplitude hologram. For a lossless phase hologram, $|\mathbf{t}(x,y)| = 1$, so that the complex amplitude transmittance is caused by variation in phase.

When the thickness of the hologram recording material is large compared to the fringe spacing of the interference fringes, the holograms may be considered as volume holograms. These may be treated as a three-dimensional system of layers corresponding to a periodic variation of absorption coefficient or refractive index, and the diffracted amplitude is at a maximum when Bragg's condition is satisfied. In general, the behavior of thin and thick holograms corresponds to Raman Nath and Bragg diffraction regimes. The distinctions between two regimes is made on the basis of a parameter Q, which is defined by the relation:

$$Q = \frac{2\pi\lambda_o d}{n_o\Lambda^2} \qquad [10]$$

where

Λ = spacing of fringe on hologram, measured normal to the surface;
d = thickness of recording medium;
n_o = mean refractive index of the medium; and
λ_o = wavelength of light.

Small values of Q ($Q < 1$) correspond to thin gratings, while large values of Q ($Q > 10$) correspond to volume gratings. For values of Q between 1 and 10, intermediate properties are exhibited. However, this criterion is not always adequate. The boundaries between the thin and thick holograms are given by the value of

$$P = \frac{\lambda_o^2}{\Lambda^2 n_o n_1} \qquad [11]$$

where P^{-2} is the relative power diffracted into higher orders, and $P < 1$ for thin holograms and $P > 10$ for thick holograms. For P having values between 1 and 10, the hologram may be thin or thick, depending on the other parameters involved.

Holograms can also be classified based on whether they are reconstructed in transmitted light or reflected light. For transmission holograms, during the recording stage, two interfering wavefronts make equal but opposite angles to the surfaces of recording medium and are incident on it from the same side. Reflection holograms reconstruct images in reflected light. They are recorded such that the interfering wavefronts are symmetrical with respect to the surface of the recording medium but are incident on it from opposite sides. When the angle between the interfering wavefronts is maximum (180°), the spacing between the fringe planes of the recording medium is minimum. Under such conditions, reflection holograms may have wavelength sensitivity high enough to be reconstructed, even with white light.

An important development in the field of holography was the invention of rainbow holograms by Benton in 1969. This provides a method for utilizing white light for illumination when viewing the holograms. The technique does so by minimizing the blur introduced by color dispersion in transmission holograms, at the price of giving up parallax information in one dimension.

Recording Materials

An ideal recording medium for holography should have a well matching spectral sensitivity corresponding to available laser wavelengths, linear transfer characteristics, high resolution, and low noise. It should also be either inexpensive or indefinitely recyclable. Toward achieving the above-mentioned properties, several materials have been studied, but none has been found so far that meets all the requirements. Materials investigated include: silver halide photographic emulsion; dichromated gelatin plates/films; silver halide sensitized gelatin plates/films; photo-resists; photo polymer systems; photochromics; photo thermoplastics; and ferro-electric crystals. Recently, the use of storage and processing capabilities of computers, together with CCD cameras, has been used for recording holograms.

Silver halide photographic emulsions are a commonly used recording material for holography, mainly because of relatively high sensitivity and easy availability. Manufacture, use, and processing of these emulsions have been well standardized. The need for wet processing and drying may constitute a major drawback. Dichromated gelatin can be considered an almost ideal recording material for volume phase holograms, as it has a large refractive index modulation capability, high resolution, low absorption and scattering.

Because of these features, dichromated gelatin has been extensively investigated. The most significant disadvantage is its comparatively low sensitivity. Pennington *et al.* developed an alternative technique, which combines the advantage of silver halide emulsions (high sensitivity) with that of dichromated gelatin (low absorption scattering and high stability). It involves exposing silver halide photographic emulsion and then processing it, so as to obtain a volume phase hologram consisting solely of hardened gelatin.

Thin phase holograms can be recorded on photoresists, which are light-sensitive organic films yielding relief image after exposure and development. They offer advantages of easy replication using thermoplastics but are slow in response and undergo nonlinear effects at diffraction efficiency greater than ~0.05. Shipley AZ-1350 is a widely used photoresist, with maximum sensitivity in the ultraviolet, dropping rapidly for longer wavelengths towards the blue.

Photopolymers are being keenly investigated because they offer advantages such as ease of handling, low cost, and real-time recording for the application of holography and nonlinear optics. However, they have low sensitivity and short shelf life.

Thin phase surface relief holograms can be recorded in a thin layer of thermoplastics. These materials have a reasonably high sensitivity over the whole visible spectrum, fairly high diffraction efficiency, and do not require wet processing. Their application in holographic interferometry, optical information processing, and in making compact holographic devices has been widely reported.

Photorefractive crystals such as $Bi_{12}SiO_{20}$, $LiNbO_3$, $Bi_{12}GeO_{20}$, $BaTiO_3$, $LiTaO_3$, etc., as recording materials, offer high-angular sensitivity and provide capability to read and write volume holographic data in real time. Besides the materials discussed here, several other materials have been investigated for recording holograms; these include photocromics, elastomere devices, magneto-optic materials, etc.

Application of Holography

Holography can be constructed not only with the light waves of lasers, but also with sound waves, microwaves, and other waves in the electromagnetic spectrum of radiation. Holograms made with ultraviolet light or X-rays can record images of objects/particles smaller than the wavelength of visible light, e.g., atoms or molecules. Acoustical holography uses sound waves to see through solid objects. Holography has a vast scope of practical applications, which have been classified into two major categories:

1. applications requiring three-dimensional images for visual perception; and
2. applications in which holography is used as a measuring tool.

The unique ability of holography – to record and reconstruct both electromagnetic and sound waves – makes it a valuable tool for education, science, industry, and business. Below are some of the important applications:

1. Holographic interferometry (HI) is one of the most powerful measuring tools. In HI, two states of an object, i.e., initial and deformed state are recorded on the same photographic plate. After reconstruction of the light wave corresponding to two states of an object, interferences and deformations are displayed in terms of the interference pattern. The change of distance of one tenth of a micron, or lower, can be resolved. HI provides scientists/engineers with crucial data for design of critical machine parts of power-generating equipment, in the aircraft industry, automobile industry, and nuclear installations (say, for example, in the design of containers used to transport nuclear materials, improve the design of aircraft wings and turbine blades, etc.). Presently, HI is being widely used in mechanical engineering, acoustics, and aerodynamics, for nondestructive testing, to investigate oscillation in diaphragms and flow around various objects, respectively.
2. Microwave holography can detect objects deep within spaces, by recording the radio waves they emit.
3. Another important application of holography is the design of optical elements, which possess special properties. A holographic recording of a concave mirror behaves in much the same way as the mirror itself, i.e., it can focus the light. In some cases chromatism can be introduced in the design of elements so that a location of the point, where the beams are focused, depends on the wavelength. This can be achieved by accurately choosing the recording arrangement of the focusing elements, these elements are, in fact, diffraction gratings. These can have low noise levels, freedom from astigmatism, and have other useful properties. Holographic optical elements have found applications in supermarket scanners to read barcodes, headup displays in fighter aircraft to observe critical cockpit instruments, etc.
4. A telephone credit card used in Europe and other developed countries has embossed surface holograms which carry a monetary value. When the card is inserted into the telephone, a card reader discerns the amount due and deducts the appropriate amount to cover the cost of the call.

5. Holography is having applications in analog and digital computers, offering remarkable opportunities to realize various logical operators, devices for identifying images based on matched filtering, and in computer memory units. The basic advantage of holographic memory is that a relatively large volume of information can be stored and that there are a limited number of ways to change the record. The arrival of the first prototype of optical computers, which use holograms as storage material for data, could have a dramatic impact on the holographic market. The yet-to-be-unveiled optical computers will be able to deliver trillions of bits of information faster than the current generation of computers.
6. Optical tweezers are going to become an important tool for the study of micro-organisms/bacteria, etc.
7. Holograms can be used to locate and retrieve information without knowing its location in the storage medium, only needing to know some of its content.
8. The links between computer science and holography are now well-established and are developing, with at least two aspects making computer-generated holograms extremely interesting. First, such holograms enable us to obtain visual 3-dimensional reconstructions of imagined objects. For example, one can reconstruct three dimensions of a model of an object still in the design stage. Second, computer-generated holograms can be used to reconstruct lightwaves with specified wave fronts. This means specially computed and manufactured holograms may function as optical elements that transform the incident light wave into desired wavefronts.
9. Another important applications of holography is its utilization to compensate for the distortion that occurs when viewing objects through optically heterogeneous mediums. It can be achieved based on the principle of beam reversal by the hologram.
10. Finally, let us consider the application of holography to art. The development of holography gives very effective ways of creating qualitative three-dimensional images. Thus, a new independent area of holographic creative work representational/artistic holography has appeared. The art of holographic depiction has developed along two major routes. The first is creation of the view hologram, used as holograms of natural objects that are to be displayed in exhibitions and museums; these are also known as artistic holograms. Portrait holography is also classified under this category. The progress in portrait holography is hampered partly because of imperfection of pulsed lasers and partly because of the deterioration of photographic material when exposed to pulsed electromagnetic radiation.

The principle behind the creation of elusion by using composite holograms is also very convincing for the display of objects. To synthesize the composite holograms, the photographs of various aspects of a scene are printed onto the photographic plate. The synthesis techniques for preparing the composite hologram are very complicated, while the images created by holograms are still far from perfect. However, there is no doubt that composite holography opens holography up as an artistic technique. Recently rainbow holography has been very popular to display such objects.

See also

Holography, Applications: Art Holography. **Holography, Techniques:** Color Holography; Computer-Generated Holograms; Digital Holography; Holographic Interferometry. **Phase Control:** Phase Conjugation and Image Correction.

Further Reading

Benton SA (1969) On a method for reducing the information content of holograms. *Journal of the Optical Society of America* 59: 1545.

Denisyuk YuN (1962) Photographic reconstruction of the optical properties of an object in its own scattered radiation field. *Sov. Phys.-Dokl.* 7: 543.

Denisyuk YuN (1963) On the reproduction of the optical properties of an object by the wave field of its scattered radiation, Pt. I. *Optical Spectroscopy* 15: 279.

Denisyuk YuN (1965) On the reproduction of the optical properties of an object by the wave field of its scattered radiation, Pt II. *Optical Spectroscopy* 18: 152.

Gabor SD (1948) A new microscopic principle. *Nature* 161: 777.

Gabor D (1949) Microscopy by reconstructed wavefronts. *Proceedings of the Royal Society* A197: 454.

Gabor D (1951) Microscopy by reconstructed wavefronts: II. *Proceedings of the Physical Society* B64: 449.

Hariharan P (1983) *Optical Holography: Principle, Techniques and Applications*. Cambridge, UK: Cambridge University Press.

Leith EN and Upatnieks J (1962) Reconstructed wavefronts and communication theory. *Journal Optical of the Society of America* 52: 1123.

Leith EN and Upatnieks J (1963) Wavefront reconstruction with continuous-tone objects. *Journal of the Optical Society of America* 53: 1377.

Leith EN and Upatnieks J (1964) Wavefront reconstruction with diffused illumination and three-dimensional objects. *Journal of the Optical Society of America* 54: 1295.

Pennington KS and Lin LH (1965) Multicolor wavefront reconstruction. *Applied Physics Letters* 7: 56.

Stroke GW and Labeyrie AE (1966) White-light reconstruction of holographic images using the Lippmann-Bragg diffraction effect. *Physics Letters* 20: 368.

Color Holography

H I Bjelkhagen, De Montfort University, Leicester, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Since the appearance of the first laser-recorded monochromatic holograms in the 1960s, the possibilities of recording full-color high-quality holograms have now become a reality. Over many years holographic techniques have been created to produce holograms with different colors, referred to as pseudo- or multicolor holograms. For example, in the field of display holography, it is common to make multiple-exposed reflection holograms using a single-wavelength laser and emulsion thickness manipulation to obtain an image with different colors. In this way many beautiful pseudocolor holograms have been made by artists. Applying Benton's rainbow hologram technique (for example, the one used for embossing holograms on credit cards), it has been possible to record transmission holograms as well as mass-produce embossed holograms with 'natural' colors. However, a rainbow hologram has a very limited viewing position from which a correct color image can be seen.

This article will acquaint the reader with the topic of color holography (full-color or true-color holography). This describes a holographic technique to obtain a color 3D image of an object where the color rendition is as close as possible to the color of the real object. A brief review of the development of color holography, the current status and the prospects of this new 3D imaging technique, are presented. Also included are recording techniques using three lasers providing red, green and blue (RGB) laser light as well as computer-generating techniques for producing full parallax 3D color images.

The Development of Color Holography

In theory, the first methods for recording color holograms were established in the early 1960s. Already Leith and Upatnieks (1964) proposed multicolor wavefront reconstruction in one of their first papers on holography. The early methods concerned mainly transmission holograms recorded with three different wavelengths from a laser or lasers, combined with different reference directions to avoid cross-talk. Such a color hologram was then reconstructed (displayed) by using the original laser wavelengths from the corresponding reference directions. However, the complicated and expensive reconstruction setup prevented this technique from becoming popular. More suitable for holographic color recording is reflection holography, which can be reconstructed and viewed in ordinary white light.

Most likely, the three-beam transmission technique might eventually become equally applicable, provided inexpensive multicolor semiconductor lasers become widely available. Such RGB lasers can be used to display a very realistic, deep, and sharp holographic image of, for example, a room.

Relatively few improvements in color holography were made during the 1960s and 1970s. Not until the end of the 1970s did a few examples of color holograms appear. During the 1980s, new and improved techniques were introduced. A review of various transmission and reflection techniques for color holography was published by Hariharan (1983). From 1990 until today, many high-quality color holograms have been recorded, mainly due to the introduction of new and improved panchromatic recording materials. On the market are ultra-fine-grain silver halide emulsions (manufactured by Slavich in Russia) as well as photopolymer materials (manufactured by E. I. du Pont de Nemours & Co. in the USA).

Color reflection holography presents no problems with regard to the geometry of the recording setup, but the final result is highly dependent on the recording material used and the processing techniques applied. There are some problems associated with recording color holograms in general and specifically in silver halide emulsions:

- Scattering occurring in the blue part of the spectrum typical of many holographic coarse-grain silver halide emulsions makes them unsuitable for the recording of color holograms.

- Multiple storage of interference patterns in a single emulsion reduces the diffraction efficiency of each individual recording. The diffraction efficiency of a three-color recording in a single-layer emulsion is lower than a single wavelength recording in the same emulsion.
- During wet processing, emulsion shrinkage frequently occurs, causing a wavelength shift. White-light-illuminated reflection holograms normally show an increased bandwidth upon reconstruction, thus affecting the color rendition.
- The fourth problem, related to some extent to the recording material itself, is the selection of appropriate laser wavelengths and their combination in order to obtain the best possible color rendition of the object.

In the beginning, when no suitable panchromatic emulsion existed, the sandwich technique was used to make color reflection holograms. Two plates were sandwiched together, in which, for example, two different types of recording materials were used. The most successful demonstration of the sandwich recording technique was made by Kubota (1986) in Japan. He used a dichromated gelatin (DCG) plate for the green (515 nm) and the blue (488 nm) components, and an Agfa 8E75 silver halide plate for the red (633 nm) component of the image. Kubota's sandwich color hologram of a Japanese doll recorded in 1986, demonstrated the potential of high-quality color holography for the first time. Color holograms have also been recorded in red-sensitized DCG materials.

Extensive work in the field of reflection color holography was performed by Hubel and Solymar (1991). Primarily they employed Ilford silver halide materials for the recording of color holograms applying the sandwich technique.

Very important is the research on recording materials by Usanov and Shevtsov (1990) in Russia. Their work is based on the formation of a microcavity structure in gelatin, by applying a special processing technique to silver halide emulsions. Such holograms recorded in a silver halide emulsion have a high diffraction efficiency and exhibit a typical DCG hologram quality.

Not until panchromatic ultra-fine-grain silver halide emulsions were introduced in Russia in the early 1990s, was it possible to record high-quality color holograms in a single emulsion layer as demonstrated by the present author. Although it is now possible to produce color holograms, they need to be displayed correctly. An important improvement would be to find an edge-illuminating technique to make color holograms easier to display. The display problem still remains the main obstacle preventing color holograms, as well as monochrome holograms, being more widely used.

Recording of Color Holograms

Currently, most transmission color holograms are of the rainbow type. Large-format holographic stereograms made from color-separated movie or video recordings have been produced. There are also some examples of embossed holograms in which a correct color image is reproduced. In order to generate a true color rainbow hologram, a special setup is required in which the direction of the reference beam can be changed in between the recordings of the color-separated RGB primary images. However, as already mentioned, holographic color images of the rainbow type can reconstruct a correct color image only along a horizontal line in front of the film or plate and, thus, of less interest for serious color holography applications. Reflection holography can offer full parallax, large field of view 3D color images where the colors do not change when observed from different directions.

Silver Halide Materials

To be able to record high-quality color reflection holograms it is necessary to use extremely low light-scattering recording materials. This means, for example, the use of ultra-fine-grain silver halide emulsions (grain size about 10 nm). Currently, the only producer of a commercial holographic panchromatic ultra-fine-grain silver halide material is the Micron branch of the Slavich photographic company located outside Moscow. The PFG-03c emulsion comes in standard sizes from 63 mm × 63 mm format up to 300 mm × 406 mm glass plates and is also available on film. Some characteristics of the Slavich material are presented in Table 1.

By using suitable processing chemistry for the PFG-03c emulsion it has been possible to obtain high-quality color holograms. These holograms are recorded in a single-layer emulsion, which greatly simplifies the recording process as compared with many earlier techniques. The aforesaid single-layer technique is described below.

Table 1 Characteristics of the Slavich panchromatic emulsion

Silver halide material	PFG-03C
Emulsion thickness	7 μm
Grain size	12–20 nm
Resolution	~10,000 $\mathrm{lp(mm)^{-1}}$
Blue sensitivity	~1.0–1.5 × 10^{-3} $\mathrm{J(cm)^{-2}}$
Green sensitivity	~1.2–1.6 × 10^{-3} $\mathrm{J(cm)^{-2}}$
Red sensitivity	~0.8–1.2 × 10^{-3} $\mathrm{J(cm)^{-2}}$
Color sensitivity peaked at	633 nm and 530 nm

Photopolymer Materials

The color holography photopolymer material from DuPont is another alternative recording material for color holograms. In particular, this type of material is suitable for mass production of color holograms. Although, being less sensitive than the ultra-fine-grain silver halide emulsion, it has special advantages of easy handling and dry processing (only UV-curing and baking). The DuPont color photopolymer material has a coated film layer thickness of about 20 μm. The photopolymer film is generally coated in a 12.5-inch width on a 14-inch wide Mylar® polyester base which is 0.002-inch thick. The film is protected with a 0.00092-inch thick Mylar® polyester cover sheet. However, the panchromatic polymer material is only supplied to specially selected and approved hologram producers. The reason for this is that some applications of color holograms are in the field of document security where optically variable devices (OVDs) are produced.

The recording of a color hologram on DuPont polymer is simple. The film has to be laminated to a piece of clean glass or attached to a glass plate using an index-matching liquid. To obtain the right color balance, the RGB sensitivity depends on the particular material, but typically red sensitivity is lower than green and blue sensitivities. It is difficult to obtain high red-sensitivity of photopolymer materials. Simultaneous exposure is the best recording technique for photopolymer materials. Holograms can be recorded manually, but in order to produce large quantities of holograms, a special machine is required. For hologram replication the scanning technique can provide the highest production rate. In this case, three scanning laser lines are needed, which can be adjusted in such a way that all three simultaneously can scan the film. The color photopolymer material needs an overall exposure of about 10 mJ(cm)$^{-2}$.

After the exposure is finished, the film has to be exposed to strong white or UV light. DuPont recommends about 100 mJ(cm)$^{-2}$ exposure at 350–380 nm. After that, the hologram is put in an oven at a temperature of 120 °C for two hours in order to increase the brightness of the image.

Laser Wavelengths for Color Holograms

The problem of choosing optimal primary laser wavelengths for color holography is illustrated in the 1976 CIE chromaticity diagram (Figure 1) which indicates suitable laser wavelengths for color holograms.

It may seem that the main aim of choosing the recording wavelengths for color holograms would be to cover as large an area of the chromaticity diagram as possible. However, there are many other



Figure 1 The 1976 CIE uniform scales chromaticity diagram shows the gamut of surface colors and positions of common laser wavelengths. Optimal color-recording laser wavelengths are also indicated.

considerations that must be taken into account when choosing the wavelengths for color holograms. One of these important considerations is the question of whether three wavelengths are really sufficient for color holography. The wavelength selection problem for color holography has been treated in several papers, for example by Peercy and Hesselink (1994).

Hubel and Solymar (1991) provided a definition of color recording in holography:

> A holographic technique is said to reproduce 'true' colors if the average vector length of a standard set of colored surfaces is less than 0.015 chromaticity coordinate units, and the gamut area obtained by these surfaces is within 40% of the reference gamut. Average vector length and gamut area should both be computed using a suitable white light standard reference illuminant.

An important factor to bear in mind when working with silver halide materials is that a slightly longer blue wavelength than the optimal one might give higher-quality holograms (better signal-to-noise ratio) because of reduced Rayleigh scattering during the recording. Another important factor to consider is the reflectivity of the object at primary spectral wavelengths. It has been shown that the reflectivity of an object at three wavelength bands, peaked at 450, 540, and 610 nm, has an important bearing on color reconstruction. These wavelengths can also be considered optimal for the recording of color holograms even though the laser lines are very narrow-band. A triangle larger than necessary can be considered in order to compensate for color desaturation (color shifting towards white) that takes place when reconstructing color reflection holograms in white light. According to Hubel's color rendering analysis, the optimal wavelengths are 464, 527, and 606 nm for the sandwich silver halide recording technique. If the calculations are performed to maximize the gamut area instead, the following set of wavelengths is obtained: 456, 532, and 624 nm. However, when approached from a different viewpoint, the optimal trio of wavelengths based on the reconstructing light source of 3400 K, a 6 μm thick emulsion with a refractive index of 1.63 and an angle of 30° between the object and the reference beam the following wavelengths were obtained: 466.0, 540.9, and 606.6 nm. Peercy and Hesselink (1994) discussed wavelength selection by investigating the sampling nature of the holographic process. During the recording of a color hologram the chosen wavelengths point-sample the surface-reflectance functions of the object. This sampling on color perception can be investigated by the tristimulus value of points in the reconstructed hologram which is mathematically equivalent to integral approximations for the tristimulus integrals. Peercy and Hesselink used both Gaussian quadrature and Riemann summation for the approximation of the tristimulus integrals. In the first case they found the wavelengths to be 437, 547, and 665 nm. In the second case the wavelengths were 475, 550, and 625 nm. According to Peercy and Hesselink, the sampling approach indicates that three monochromatic sources are almost always insufficient to preserve all of the object's spectral information accurately. They claim that four or five laser wavelengths are required.

Only further experiments will show how many wavelengths are necessary and which combination is the best for practical purposes. Another factor that may influence the choice of the recording wavelengths is the availability of cw lasers currently in use in holographic recording, for example, argon ion, krypton ion, diode-pumped solid state (DPSS) frequency-doubled Nd:YAG, helium neon, and helium cadmium lasers (Table 2).

The recent progress in DPSS laser technology has made available both red and blue DPSS lasers. These lasers are air-cooled, small, and each laser requires less than a hundred watts of electric power to operate. Usually, a set of three DPSS lasers will be the best choice of cw lasers for color holography in the future.

Setup for Recording Color Holograms

A typical reflection hologram recording setup is illustrated in Figure 2.

Table 2 Wavelengths from cw lasers

Wavelength [nm]	*Laser type*	*Single line power [mW]*
442	Helium cadmium	<100
457	DPSS blue	<500
458	Argon ion	<500
468	Krypton ion	<250
476	Krypton ion	<500
477	Argon ion	<500
488	Argon ion	<2000
497	Argon ion	<500
502	Argon ion	<400
514	Argon ion	<5000
521	Krypton ion	<100
529	Argon ion	<600
531	Krypton ion	<250
532	DPSS green	<3000
543	Green neon	<10
568	Krypton ion	<100
633	Helium neon	<80
647	Krypton ion	<2000
656	DPSS red	<1000



Figure 2 The setup for recording color reflection holograms.

The different laser beams necessary for the exposure of the object pass through the same beam expander and spatial filter. A single-beam Denisyuk arrangement is used, i.e., the object is illuminated through a recording holographic plate. The light reflected from the object constitutes the object beam of the hologram. The reference beam is formed by the three expanded laser beams. This 'white' laser beam illuminates both the holographic plate and the object itself through the plate. Each of the three primary laser wavelengths forms its individual interference pattern in the emulsion, all of which are recorded simultaneously during the exposure. In this way, three holographic images (a red, a green, and a blue image) are superimposed upon one another in the emulsion.

Three laser wavelengths are employed for the recording: 476 nm, provided by an argon ion laser, 532 nm, provided by a cw frequency-doubled Nd:YAG laser, and 647 nm, provided by a krypton laser. Two dichroic filters are used for the combining of the three laser beams. The 'white' laser beam goes through a spatial filter, illuminating the object through the holographic plate.

By using the dichroic filter beam combination technique, it is possible to perform simultaneous exposure recording, which makes it possible to control independently the RGB ratio and the overall exposure energy in the emulsion. The RGB ratio can be varied by individually changing the output power of the lasers, while the overall exposure energy is controlled solely by the exposure time. The overall energy density for exposure is about 3 $\mathrm{mJ(cm)^{-2}}$.

In the initial experiments performed by the author in 1993, a specially designed test object consisting of the 1931 CIE chromaticity diagram, a rainbow ribbon cable, pure yellow dots, and a cloisonné elephant, was used for the color balance adjustments and exposure tests. Later, another test target was employed – the Macbeth ColorChecker® chart, which was used for color rendering tests.

Color reflection holograms can also be produced using copying techniques so that projected real images can be obtained, however, normally associated with a restricted field of view. For many display purposes, the very large field of view obtainable in a Denisyuk color hologram is often more attractive.

Processing of Color Holograms

The dry processing of color holograms recorded on photopolymer materials has already been described. The process is simple and very suitable for machine processing using, for example, a baking scroll oven. The processing of silver halide emulsions is more difficult and critical. The Slavich emulsion is rather soft, and it is important to harden the emulsion before the development and bleaching takes place. Emulsion shrinkage and other emulsion distortions caused by the active solutions used for the processing must be avoided. In particular, when recording master color holograms intended for photopolymer replication, shrinkage control is extremely important. The processing steps are summarized in Table 3.

Table 3 Color holography processing steps

1.	Tanning in a formaldehyde solution	6 min
2.	Short rinse	5 s
3.	Development in the CWC2 developer	3 min
4.	Wash	5 min
5.	Bleaching in the PBU-amidol bleach	~5 min
6.	Wash	10 min
7.	Soaking in acetic acid bath (printout prevention)	1 min
8.	Short rinse	1 min
9.	Washing in distilled water with wetting agent added	1 min
10.	Air drying	

It is very important to employ a suitable bleach bath to convert the developed silver hologram into a phase hologram. The bleach must create an almost stain-free clear emulsion so as not to affect the color image. In addition, no emulsion shrinkage can be permitted, as it would change the colors of the image. Washing and drying must also be done so that no shrinkage occurs. Finally, to prevent any potential emulsion thickness variation by humidity variations, the emulsion needs to be protected by a glass plate sealed onto the hologram plate.

Evaluation of Color Holograms

Recorded color holograms of the two test targets are presented here. The illuminating spotlight to reconstruct the recorded color holograms was a 12-Volt 50-Watt halogen lamp. This type of spotlight is suitable for displaying color holograms. The selection of a suitable lamp for the reconstruction of color holograms is much more important than the selection of lamps for monochrome hologram display. The color balance for the recording of a color hologram must be adjusted to the type of spotlight that is going to be used for the display of the finished hologram. Figure 3 shows a typical normalized spectrum obtained from a white area of the color test target hologram.

This means that the diffraction efficiency of each color component is obtained assuming a flat spectrum of the illuminating source. One should note the high diffraction efficiency in blue, needed to compensate for the low blue light emission of the halogen spotlight. The noise level, mainly in the blue part of the spectrum, is visible and low. The three peaks are exactly at the recording wavelengths; i.e., 647, 532, and 476 nm.

In Table 4 some results of the Macbeth ColorChecker® investigation are presented. The 1931 CIE *x* and *y* coordinates are measured at both the actual target and the holographic image of the target. The measured fields are indicated in the table by color and the corresponding field number.



Figure 3 Normalized spectrum from a white area of a color test target hologram.

Color reproductions of two color holograms by the author are presented. A photograph of the 100 mm by 120 mm hologram of the CIE test object is shown in Figure 4. Featured in Figure 5 is a 200 mm by 250 mm hologram of a large Russian egg.

Computer-Generated Color Holograms

Today it is not possible to obtain a computer-generated hologram (CGH) with the same high information content as the laser-recorded ones of real objects. What may become possible in the future is a technique to compute and record the interference pattern that is stored in a Denisyuk color hologram which, upon illumination, can produce an image like the laser-recorded ones of real objects. Therefore, the best compromise is to use holographic stereograms which can provide high-quality computer-generated images. A holographic stereogram is created by using a series of 2D photographic images or 2D images displayed on a LCD screen from which the hologram is recorded. In order to obtain a high-quality holographic image with a large field of view, many 2D images are needed. As mentioned earlier, some color CGHs of the rainbow transmission type have been produced. However, image color changes as a function of viewer position in that type of hologram, making them less attractive than computer-generated reflection holograms. Over the last few years there has been rapid progress in color CGHs of the reflection type. Remarkable results have been achieved by Klug *et al.* (1997) at Zebra Imaging Inc. A new technique, to record very large full-parallax color reflection CGHs, has been developed. Color holograms can be produced, having both vertical and horizontal parallax, with a 100° field of view. The generation of a holographic hardcopy of either digitized images or computer graphics models is based on the following technique. The 'object'

Table 4 Chromaticity coordinates from color hologram recording tests using the Macbeth ColorChecker®

Object	*White #19*	*Blue #13*	*Green #14*	*Red #15*	*Yellow #16*	*Magenta #17*	*Cyan #18*
CIE *x y*	*x*/*y*	*x*/*y*	*x*/*y*	*x*/*y*	*x*/*y*	*x*/*y*	*x*/*y*
Target	0.435/0.405	0.295/0.260	0.389/0.514	0.615/0.335	0.517/0.450	0.524/0.322	0.285/0.380
Image	0.354/0.419	0.335/0.362	0.337/0.449	0.476/0.357	0.416/0.437	0.448/0.338	0.295/0.366



Figure 4 Hologram of the CIE test object recorded with 476, 532, and 647 nm laser wavelengths. Notice the rainbow ribbon cable, the pure yellow dots, the full range of colors, and a balanced white in the center of the CIE color test target.



Figure 5 Color hologram of a large Russian egg, size 100 mm by 120 mm.

sub-beam is directed through a sequence of digital images on a liquid-crystal screen. Each resulting exposure, about two millimeters square, is called a 'hogel'. The full-color hogels are the holographic building blocks of a finished CGH image. In an automated step-and-repeat process, 9×10^4 hogels are formed on a flat square tile of DuPont panchromatic photopolymer film by simultaneous RGB laser exposures. The 60 cm by 60 cm tile itself is the finished hologram, or to obtain larger holograms, the 3D image is made in 60 cm by 60 cm tiled increments. So far, the largest image created was of Ford's P2000 Prodigy concept car in which ten such holograms tiled together made up the large color reflection hologram (1.2 m by 3 m) which is reproduced in Figure 6.

This technique has opened the door to real 3D computer graphics. However, generating such a large hologram is a very time-consuming process. The Ford P2000 hologram took almost two weeks (300 hours) to produce, since each individual panel requires a 24-hour recording time.

The Future of Color Holography

The manufacturing of large-format color reflection holograms is now possible. Mass production of color holograms on photopolymer materials has started in Japan. Although good color rendition can be obtained, some problems remain to be solved, such



Figure 6 Computer-generated color hologram of Ford's P2000 Prodigy concept car. A ten tile full parallax Mosaic hologram produced by Zebra Imaging, Inc., size 1.2 m by 3 m.

as desaturation, image resolution, signal-to-noise ratio and dynamic range. Other limitations concerning holographic color recording include the fact that some colors we see are the result of fluorescence, which cannot be recorded in a hologram. There are some differences in the recorded colors in one of the test charts shown here. However, color rendition is a very subjective matter. Different ways of rendition may be preferable for different applications, and different people may have different color preferences.

At the present time, research on processing color reflection holograms recorded on ultra-fine-grain materials is still in progress. Work is carried out on microcavity structure holograms in order to produce low-noise reflection holograms with high diffraction efficiency. For producing large quantities of color holograms, the holographic photopolymer materials are most suitable and will be further improved in the future.

Another important field of research is the development of a three-wavelength pulsed laser. Employing such a laser, dynamic events, as well as portraits, can be recorded in a holographic form. Currently, research work is in progress at the French German Research Institute ISL, Saint Louis, France, as well as at the Geola company in Lithuania.

The virtual color image behind a color holographic plate represents the most realistic image of an object that can be obtained today. The extensive field of view adds to the illusion of beholding a real object rather than an image of it. The wavefront reconstruction process recreates accurately the three-wavelength light scattered off the object during the recording of the color hologram. This 3D imaging technique has many obvious applications, in particular, in displaying unique and expensive artifacts. There are also many potential commercial applications of this new feature of holographic imaging, provided that the display problem can be solved using some sort of integrated lighting.

Today, it is technologically possible to record and replay acoustical waves with very high fidelity. Hopefully, holographic techniques will be able to offer the same possibility in the field of optical waves, wavefront storage, and reconstruction. Further development of computer-generated holographic images will make it possible to display extremely realistic full-parallax 3D color images of nonexisting objects, which could be applied in various spheres, for example, in product prototyping, as well as in other applications in 3D visualization and three-dimensional art. Eventually it will become possible to generate true-holographic 3D color images in real-time, as computers become faster and possess greater storage capacity. However, the most important issue is the development of extremely high-resolution electronic display devices which are necessary for electronic holographic real-time imaging.

See also

Holography, Techniques: Computer-Generated Holograms.

Further Reading

Bjelkhagen HI (1993) *Silver Halide Recording Materials for Holography and Their Processing*. Springer Series in Optical Sciences, vol. 66. New York: Springer-Verlag.

Bjelkhagen HI, Jeong TH and Vukičević D (1996) Color reflection holograms recorded in a panchromatic ultrahigh-resolution single-layer silver halide emulsion. *Journal of Imaging Science* & *Technology* 40: 134–146.

Bjelkhagen HI, Huang Q and Jeong TH (1998) Progress in color reflection holography. In: Jeong TH (ed.) *Sixth International Symposium on Display Holography*, Proc. SPIE, vol. 3358, pp. 104–113. Bellingham, WA: The International Society for Optical Engineering.

Hariharan P (1983) Colour holography. In: Wolf E (ed.) *Progress in Optics*, vol. 20, pp. 263–324. Amsterdam: North-Holland.

Hubel PM and Solymar L (1991) Color reflection holography: theory and experiment. *Applied Optics* 30: 4190–4203.

Klug MA, Klein A, Plesniak W, Kropp A and Chen B (1997) Optics for full parallax holographic stereograms. In: Benton SA and Trout TJ (eds) *Practical Holography XI and Holographic Materials III*, Proc. SPIE, vol. 3011, pp. 78–88. Bellingham, WA: The International Society for Optical Engineering.

Kubota T (1986) Recording of high quality color holograms. *Applied Optics* 25: 4141–4145.

Leith EN and Upatnieks J (1964) Wavefront reconstruction with diffused illumination and three-dimensional objects. *Journal of the Optical Society of America* 54: 1295–1301.

Peercy MS and Hesselink L (1994) Wavelength selection for true-color holography. *Applied Optics* 33: 6811–6817.

Usanov YuE and Shevtsov MK (1990) Principles of fabricating micropore silver-halide-gelatin holograms. *Optics and Spectroscopy (USSR)* 69: 112–114.

Watanabe M, Matsuyama T, Kodama D and Hotta T (1999) Mass-produced color graphic arts holograms. In: Benton SA (ed.) *Practical Holography XIII*, Proc. SPIE, vol. 3637, pp. 204–212. Bellingham, WA: The International Society for Optical Engineering.

Computer-Generated Holograms

W J Dallas, University of Arizona, Tucson, AZ, USA

A W Lohmann, University of Erlangen-Nürnberg, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

A hologram is a tool for shaping the amplitude and the phase of a light wave. Shaping the amplitude distribution is easy, one way is by a photographic plate, another way is by binary pixels as used in 'half-tone printing'. The phase distribution can be shaped by RE-fraction on a thin film of variable thickness, or by DIF-fraction on a diffraction grating that has been deliberately distorted.

Both kinds of holograms can be manufactured based on a computer design, the refractive version being called a 'kinoform', and the diffractive version being known as a computer-generated hologram (CGH). We will explain the fundamentals of computer holography with emphasis on the 'Fourier–CGH', and will also highlight the large variety of applications.

From the Classical Hologram to the Computer-Generated Hologram: CGH

Holography is a method to form images, consisting of two steps: recording and reconstruction. In the recording step, some interference fringes are recorded on a photographic plate (Figure 1a). The two interfering waves originate from the object and from a reference light source. After being developed by the usual photo-chemical treatment the photographic plate is called a hologram. In the reconstruction step, the hologram acts as a diffracting object that is illuminated by a replica of the reference light. Due to diffraction, the light behind the hologram is split into three parts (Figure 1b). One part proceeds to the observer who perceives a virtual object where the genuine object had been originally during the recording step.



Figure 1 Holographic image formation in two steps: (a) recording the hologram, (b) reconstructing the object wave.

This was a brief description of 'classical-holography'. In 'computer holography' the first step, recording, is synthetic. In other words, the propagation of the light from the object to the photographic plate is simulated digitally. The simulation includes the addition of the object wave to the reference wave and the subsequent modulus square process, which describes the transition from the two complex amplitudes to the hologram irradiance:

$$|u_0(x) + u_R(x)|^2 = I_H(x) \qquad [1]$$

The amplitude transmittance of the hologram is

$$T_H(x) = c_0 + c_1 I_H(x) = c_1 u_0 u_R^* + \cdots \qquad [2]$$

The coefficients c_0 and c_1 represent the photochemical development. In the reconstruction process (Figure 1b) the transmittance T_H is illuminated by the reference beam. Hence, we get

$$u_R(x) T_H(x) = c_1 u_0(x) |u_R(x)|^2 + \cdots \qquad [3]$$

If the reference intensity $|u_R(x)|^2$ is constant, this term represents a reconstruction of the object wave $u_0(x)$. The omitted parts in eqns [2] and [3] describe those beams that are ignored by the observer (Figure 1b). The hologram transmittance $T_H(x)$ is an analog signal:

$$0 \leq T_H \leq 1 \qquad [4]$$

Before the 1960s, when computer holograms were invented, the available plotters could produce only binary transmittance patterns. Hence, it was necessary to replace the analog transmission $T_H(x)$ by a binary transmission $B_H(x)$, which is possible without loss of image quality. In addition, binary computer holograms have better light efficiency and a better signal-to-noise ratio. They are also more robust when being copied or printed.

Another advantage of a CGH is that the object does not have to exist in reality, which is important for some applications. The genuine object may be difficult to manufacture or, if it is three-dimensional, difficult to illuminate. The CGH may be used to implement an algorithm for optical image processing. In that case, the term 'object' becomes somewhat fictitious. We will discuss more about applications, towards the end of this article.

From a Diffraction Grating to a Fourier CGH

Now we will explain, in some detail, the 'Fourier type' CGH. Fourier holograms are more popular than two other types: 'image-plane' CGHs and 'Fresnel-type' CGHs. The Fresnel-type will be treated in the section on 'software' because of some interest in 3-D holograms. Certain hardware issues will also be described.



Figure 2 Grating diffraction, but with an off-axis source.

The explanation of Fourier CGHs begins with grating diffraction (Figure 2). The only uncommon feature in Figure 2 is the off-axis location of the source. It is arranged such that the plus-first diffraction order will hit the center of the output plane.

We will now convert a simple Ronchi grating (Figure 3a) into a Fourier CGH. The Ronchi grating transmittance can be expressed as the Fourier series:

$$G(x) = \sum_{(m)} C_m \exp\left(\frac{2\pi imx}{D}\right); \quad C_0 = \frac{1}{2};$$

$$C_m = \frac{\sin(\pi m/2)}{\pi m} \qquad [5]$$

Now we shift the grating bars by an amount PD. Then we modify the width from $D/2$ to WD, as shown in Figure 3b. The Fourier coefficients are now

$$C_m = \frac{\exp(2\pi imP)\sin(\pi mW)}{\pi m} \qquad [6]$$

The C_{+1} coefficient is responsible for the complex amplitude at the center of the readout plane:

$$C_{+1} = \frac{\exp(2\pi iP)\sin(\pi W)}{\pi} \qquad [7]$$

We are able now to control the beam magnitude, $A = (\frac{1}{\pi})\sin(\pi W)$, by the relative bar width W and the phase $\phi = 2\pi P$ by the relative bar shift P. This particular kind of phase shift is known as 'detour phase'.

So far, the light that ends up at the center of the exit plane, leaves the grating as a plane wave with a wave vector parallel to the optical axis. Now we distort the grating on purpose (Figure 3c):

$$W \rightarrow W(x,y); \qquad P \rightarrow P(x,y) \qquad [8]$$



Figure 3 Modifying a grating into a hologram in 3 steps: (a) Ronchi grating, (b) Modified width and location of the grating bars, (c) Distorted grating bars, (d) as in **Figure 3c**, but now discrete distortions.

These distortions should be mild enough that the plus-first order light behind the distorted grating can be described by the complex amplitude:

$$\left(\frac{1}{\pi}\right)\sin[\pi W(x,y)]\,\exp[2\pi i P(x,y)] = u_{\mathrm{H}}(x,y) \qquad [9]$$

This is a generalization of eqn [7]. The phase $2\pi P(x,y)$ covers the range from $-\pi$ to $+\pi/2$ if the shift is bounded by $|P| \le \frac{1}{2}$. That is enough to cover the range of complex amplitudes within the circle of $|u_{\mathrm{H}}| \le \frac{1}{\pi}$. We will return shortly to the condition 'mild-enough distortions' in the context of Figure 4.



Figure 4 CGH with 64 × 64 cells.

Most plotters move their pens only in the x-direction and y-direction and printers place dots on a grid. Therefore it is convenient to replace the continuous (x,y) variations of W and P by piece-wise constant variations, as in Figure 3d. That restriction turns out to be acceptable, as demonstrated by the first computer holograms. The theoretical proof involves the sampling theorem.

Recall that the light propagation through a 2-f system (Figure 2, between grating and output plane) can be described by a Fourier transformation:

$$\iint u_{\mathrm{H}}(x,y)\exp\left[\frac{-2\pi i(xx'+yy')}{\lambda f}\right]\mathrm{d}x\,\mathrm{d}y = \tilde{u}_{\mathrm{H}}\left(\frac{x'}{\lambda f},\frac{y'}{\lambda f}\right) \qquad [10]$$

Suppose now that we wish to see a particular image: $v(x',y')$. Hence, we request that

$$v(x',y') = \tilde{u}_{\mathrm{H}}\left(\frac{x'}{\lambda f},\frac{y'}{\lambda f}\right)\mathrm{RECT}\left(\frac{x'}{\lambda f}\right) \qquad [11]$$

The RECT function indicates that only the PLUS first diffraction order is of interest. As a consequence we have to select the grating distortions $W(x,y)$ and $P(x,y)$ such that the hologram $u_{\mathrm{H}}(x,y)$ is the



Figure 5 A reconstruction from a 1024 × 1024 CGH. The real image and the symmetrical twin image appear. The zeroth-order is blocked.



Figure 6 Reconstruction setup for a Fourier CGH.

Fourier transform of $v(x', y')$:

$$u_H(x,y) = \iint v(x',y') \exp\left[\frac{2\pi i(xx'+yy')}{\lambda f}\right] \mathrm{d}x'\,\mathrm{d}y' \qquad [12]$$

The condition 'mild enough distortions' has been treated in the literature. There is not enough space here to present that part of the CGH theory. But we show an actual CGH with 64 × 64 cells (Figure 4). This CGH is no longer a grating, but, it shows enough resemblance to our heuristic derivation. Hence, the CGH theory appears to be trustworthy. A CGH looks less regular if the image $v(x', y')$ contains a random phase that simulates a diffuser. The diffuser spreads light across the CGH and so levels out unacceptably large fluctuations in the amplitude.

With 512 × 512 or 1024 × 1024 cells in a CGH one can obtain an image of the quality seen in Figure 5. The reconstruction setup is shown in Figure 6, here with the letter F as the image.

About Some CGH Algorithms

The computational effort for getting the desired hologram amplitude of a Fourier hologram u_H is reasonable due to the powerful FFT algorithm. However, to use it the data must be discrete. In other words, the CGH consists of cells, centered at $x_m = mD$, $y_n = nD$ as shown in Figure 3d. The questions now are: 'What is the proper cell size D?' and 'How many cells are needed?' The answers to those questions depend on the parameters of the image. If the zero order (see Figure 6) should be at the distance Δx_0, then the quasi-grating period D should obey:

$$\frac{\lambda f}{D} \geq \Delta x_0 \qquad [13]$$

And if the size of an image pixel should be as fine as δx_0, the size Δx_H of the hologram should obey:

$$\frac{\lambda f}{\Delta x_H} \leq \delta x_0 \qquad [14]$$

This condition is plausible because the finite size Δx_H of the hologram acts like a resolution-limiting aperture. The combination of eqns [13] and [14] yields

$$\frac{\Delta x_0}{\delta x_0} \leq \frac{\Delta x_H}{D} \qquad [15]$$

This means that the number of image pixels $\Delta x_0/\delta x_0$ is bounded by the number of CGH cells $\Delta x_H/D$. The generalization to two dimensions is straightforward. Again, Fourier CGHs benefit from the fact that the light propagation from the virtual object to the hologram plane can be described by a Fourier transformation. Hence, the FFT can be used.

And now we move to the synthesis of a Fresnel hologram. A Fresnel hologram is recorded at a finite distance z from the object. Hence, we have to simulate the wave propagation in free space from the object (at $z = 0$) to the hologram at a distance z. This free space propagation can be described (in the paraxial approximation) as a convolution of object and quasi-spherical wave:

$$u_0(x) \rightarrow \int_{-\infty}^{\infty} u_0(x') \exp\left[\frac{-i\pi(x - x')^2}{\lambda z}\right] \mathrm{d}x' = u(x,z) \qquad [16]$$

In the Fourier domain the corresponding operation is:

$$\tilde{u}_0(\mu) \rightarrow \tilde{u}_0(\mu) \exp[-i\pi\lambda z\mu^2] = \tilde{u}(\mu, z) \qquad [17]$$

The indirect execution of eqn [16], based on eqn [17], is easy: a Fourier transformation of the object converts $u_0(x)$ into $\tilde{u}_0(\mu)$, which is then multiplied by the quadratic phase factor, yielding $\tilde{u}(\mu, z)$. An inverse Fourier transformation produces $u(x, z)$. The two Fourier transformations consist typically of $4N \log N$ multiply/add operations. N is the number of pixels: image size Δx_0, divided by the pixel size δx_0.

In the case of a rectangular object $u_0(x, y)$, the number of pixels is $\Delta x_0 \Delta y_0 / \delta x_0 \delta y_0$.

Now to describe the algorithmic effort for computing the convolution, the $u_0(x)$ has N pixels, and, the lateral size of the exponential is essentially $M = z/\delta z$, where δz represents 'depth of focus'. M describes the lateral size of the diffraction cone, measured in pixel size units δx_0, and the convolution involves MN multiply/adds. A comparison of these two algorithms is dictated by the ratio

$$\frac{M}{4 \log N} \qquad [18]$$

The direct convolution is preferable if the distance z is fairly small. The integration limits of eqn [16] depend on the oscillating phase $\pi x^2/\lambda z$. Effectively, nothing is contributed to this integral, when this phase varies by more than 2π over the length, δx_0, of an object pixel. Note that the pixel size of $u(x, z)$ does not change with the distance z, because the bandwidth $\Delta\mu(z) = \Delta\mu_0$ is z-independent. This is so because the power spectrum is z-invariant:

$$|\tilde{u}(\mu, z)|^2 = |\tilde{u}_0(\mu)|^2 \qquad [19]$$



Figure 7 Synthesis of a hologram for a three-dimensional object.

It is easy to proceed from here to the CGH synthesis of a 3-D object. One starts with an object detail $u_1(x)$ at z_1, for example, the house as in Figure 7. Then, one propagates to the next object detail at z_2. This second detail may act as a multiplication (transmission) and as addition (source elements). This process is repeated as the wave moves towards the plane of the hologram. There, a reference wave has to be added, as in the Fourier case.

A very powerful algorithm for the CGH synthesis is 'IFTA' (iterative Fourier transform algorithm). Suppose, we want to design a Fourier CGH, which looks like a person and whose reconstructed image shows the signature of that person (Figure 8a,b). In other words, the two intensities

$$|u_H(x, y)|^2 \text{ and } |\tilde{u}_H(\mu, \nu)|^2 \qquad [20]$$

are determined. But, the phase distributions of u_H and $\tilde{u}_H$ are still at our disposal. The IFTA algorithm will yield those phases in many cases at the expense of ten, hundred or more Fourier transformations.

The IFTA algorithm is sometimes called 'Fourier Ping-Pong' because it bounces back and forth between the (x, y) and the (μ, ν) domain. The amplitudes $|u_H|$ and $|u_0|$ are enforced at every opportunity. But the associated phases are free to vary and to converge, eventually. If so, u_H and u_0 are completely known. The IFTA will not always converge, for example not if

$$|u_H(x, y)| = \delta(x, y) \text{ and } |\tilde{u}_H(\mu, \nu)| = \delta(\mu, \nu) \qquad [21]$$

But the chances are fairly good if both amplitudes are often close to one and seldom near zero.



Figure 8 IFTA-CGH: (a) The Fourier CGH. (b) The optical reconstruction thereof. (Courtesy of H.O. Bartelt.)

Finally, an image plane CGH is trivial from an algorithmic point of view. The simulated propagation from object plane to image plane is usually an identity, apart from the finite bandwidth of the image-forming system. Nevertheless, image plane holograms can be quite useful, for example for interferometric testing of a nonspherical mirror of an astronomical telescope. The CGH is laid out to provide a wavefront that is suitable for an interferometric 'null test'. The CGH serves as a 'synthetic prototype'.

A fourth kind of CGH, to be named near-field CGH may emerge. It operates in the near-field and it employs evanescent waves as they occur, if object details are comparable in size with, or even smaller than, the wavelength. Conceivable topics are 'super resolution' and 'sub-lambda lithography'. Fundamentals and history of classical evanescent holography are reported in the Further Reading.

Some Hardware Aspects

We now describe some hardware aspects of the CGHs. Remembering the CGH cell structure in Figure 3d, we saw the amplitude encoded as relative width W (eqn [6]). Instead of the width, one may use the relative height $H \leq 1$ as the amplitude parameter. More efficient, but more difficult to manufacture are saw tooth-shaped hologram cells. The saw tooth prism may be approximated by a phase stair, which is possible with today's lithographic technology. The corresponding theory is called phase quantization.

Some CGH Applications

Some applications had been mentioned already before, e.g., 3-D display (see Figure 7). The data volume can be very high, hence, shortcuts such as eliminating the vertical perspective, are necessary. The largest CGHs for visual light are used for testing astronomical telescopes by means of interferometry. The IFTA algorithm has been used, among other things, for designing a CGH which acts as an optimal diffuser. Speckles and light efficiency are the critical issues in diffuser design. Another project, that also benefits from IFTA, is beam shaping. That is a broad topic with aims at, for example, homogenizing the output of laser, beam structuring for welding, cutting, and scanning.

A CGH can also be used as a spatial filter for image processing. For example, an input image may be Hilbert-transformed in the setup shown in Figure 9a. The filter (Figure 9b) is a grating, of which one sideband is shifted by one-half of the grating period. Such a geometric shift generates the π-phase shift that is needed for the Hilbert transformation. The same setup can also be used to implement Zernike's phase contrast. Now the grating is distorted such that the zero-frequency region at the optical axis is reduced in amplitude by (typically) a factor of 0.2. In addition, the phase is shifted by $\pi/2$ due to a fringe shift of a quarter period (Figure 10a). In the image plane one can see an ordinary image on-axis, and two phase-contrast images in the plus-minus first diffraction orders. One of them has positive phase contrast, the



Figure 9 (a) Hilbert setup. (b) Hilbert filter.



Figure 10 (a) Phase contrast filter. (b) Phase contrast output.



Figure 11 (a) Differentiation filter. (b) Differentiation output.

other one has negative phase contrast (Figure 10b). Another simple spatial filter (Figure 11a) produces a derivative of the input $u(x,y) : \partial u(x,y)/\partial x$ (Figure 11b). Equations [22]–[24] explain this differential filtering experiment.

$$u(x,y) \rightarrow \frac{\partial u(x,y)}{\partial x} = v(x,y) \qquad [22]$$

$$\tilde{u}(\mu,\nu) \rightarrow 2\pi i \mu \cdot \tilde{u}(\mu,\nu) = \tilde{v}(\mu,\nu) \qquad [23]$$

$$\tilde{p}(\mu,\nu) = 2\pi|\mu| \cdot \left\{ \begin{array}{c} +i(\mu > 0) \\ -i(\mu > 0) \end{array} \right\} \qquad [24]$$

The phase portion of the filter (Figure 11a) is the same as for the Hilbert filter, but, the filter amplitude now enhances the higher frequencies. The object used for getting the results of Figure 10b and 11b was a phase-only object: a bleached photograph.

A very famous spatial filtering experiment is 'matched filtering', which can be used for pattern recognition. The original matched filters were classical Fourier holograms of the target pattern. Computer hologram's can do the same job, even with spatially incoherent objects, this work being initiated by Katyl.

Fourier holograms are also attractive for data storage, due to their robustness against local defects. However, a local error in the Fourier domain spreads out all over the image domain. The computed hologram has an advantage over classical holograms because of the freedom to incorporate any error detection and correction codes for reducing the bit error rate even further.

One of the most recent advances is in matched filtering with totally incoherent light. This step allows moving spatial filtering out of the well-guarded laboratory into hostile outdoor environments.

Finally, a word about terminology; several terms are used in place of 'CGH': synthetic hologram, digital hologram, holographic optical element (HOE), diffractive optical element (DOE) or digital optical element.

CGHs have also been made for other waves, such as acoustical waves, ocean waves, and microwaves. Digital antenna steering represents a case of computer holography.

See also

Diffraction: Fraunhofer Diffraction; Fresnel Diffraction. **Fourier Optics**. **Holography, Techniques:** Computer-Generated Holograms; Holographic Interferometry; Overview. **Imaging:** Information Theory in Imaging; Inverse Problems and Computational Imaging; Three-Dimensional Field Transformations. **Information Processing:** Coherent Analogue Optical Processors; Free-Space Optical Computing; Incoherent Analog Optical Processors. **Optical Communication Systems:** Free-Space Optical Communications. **Optical Processing Systems**. **Phase Control:** Wavefront Coding.

Further Reading

Andrés P (1999) *Opt. Lett.* 245: 1331.
Brown BR and Lohmann AW (1966) *Appl. Opt.* 5: 967.
Brown BR and Lohmann AW (1969) *IBM J. R&D* 13: 160.
Bryngdahl O (1973) *Progr. Opt.* 11: 168.
Bryngdahl O and Wyrowski F (1990) *Progr. Opt.* 28: 1–86.
Dallas WJ (1971) *Appl. Opt.* 10: 673.
Dallas WJ (1973) *Appl. Opt.* 12: 1179.
Dallas WJ (1980) *Topics in Appl. Phys.* 40: 291–366.
Dallas WJ (1999–2003) http://www.radiology.arizona.edu/dallas/CGH.htm. University of Arizona, Tucson, AZ.
Dresel T, Beyerlein M and Schwider J (1996) *Appl. Opt.* 35: 4615.
Fienup JR (1981) *Proc. SPIE* 373: 147.
Fienup JR (1982) *Appl. Opt.* 21: 2758.
Gerchberg RW and Saxton WO (1972) *Optik* 35: 237.
Goodman JW and Silvestri AM (1970) *IBM J. R&D* 14: 478.

Hansler RL (1968) *Appl. Opt.* 7: 1863.
Hauk D and Lohmann AW (1958) *Optik* 15: 275.
Ichioka Y and Lohmann AW (1972) *Appl. Opt.* 11: 2597.
Katyl RH (1972) *Appl. Opt.* 11: 1255.
Kozma A and Kelly DL (1965) *Appl. Opt.* 4: 387.
Lee WH (1978) *Progr. Opt.* 16: 219–232.
Lesem LB, Hirsch PM and Jordan JA (1969) *IBM J. R&D* 13: 150.
Lohmann AW and Paris DP (1967) *Appl. Opt.* 6: 1746.
Lohmann AW and Paris DP (1968) *Appl. Opt.* 7: 651.
Lohmann AW and Sinzinger S (1995) *Appl. Opt.* 34: 3172.
Lohmann AW and Werlich HW (1971) *Appl. Opt.* 10: 670.
McGovern AJ and Wyant JC (1971) *Appl. Opt.* 10: 619.
Pe'er A, Wang D, Lohmann AW and Friesem AA (1999) *Opt. Lett.* 24: 1469; (2000) 25: 776.
Sinzinger S and Jahns J (1999) *Micro Optics*. New York: Wiley.
Vander Lugt AB (1964) *IEEE, IT* 10: 139.
Wyrowski F and Bryngdahl O (1991) *Rep. Prog. Phys.* 1481–1571.
Yaroslavskii LP and Merzlyakov NS (1980) *Methods in Digital Holography*. New York: Plenum Press.

Digital Holography

W Osten, University of Stuttgart, Stuggart, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The sinusoidal nature of light, its ability to interfere, and the precise knowledge of its wavelength make it possible to measure several metrological quantities, such as distances and displacements, with high accuracy. However, the high frequency of light results in the difficulty that the primary quantity to be measured, i.e., the phase of the light wave, cannot be observed directly. All quadratic sensors (CCD, CMOS, photo plates) are only able to record intensities. Therefore, one makes use of a trick: the transformation of phase changes into recordable intensity changes as the basic principle of interferometry and holography. Holography provides the possibility to record and to reconstruct the complete information of optical wave fields. Numerous potential applications such as 3D-imaging of natural objects, fabrication of diffractive optical elements, and interferometric investigation of complex technical components become possible. Further progress has been made by recording holograms directly with electronic targets and not in photographic emulsions. In this way the independent numerical reconstruction of phase and intensity can be accomplished by the computer. One important consequence is that interferometric techniques, such as 3D-displacement analysis and 3D-contouring, can be implemented easily and with high flexibility. Furthermore, digitally recorded holograms can be transmitted via telecommunication networks and optically reconstructed at any desired place using an appropriate spatial light modulator. Consequently, the complete optical information of complex objects can be transported between different places with high velocity. This opens the possibility to compare nominal identical but physically different objects (master sample comparison) available at different locations with interferometric sensitivity. We call this remote metrology.

Direct Phase Reconstruction by Digital Holography

In digital speckle pattern interferometry (DSPI), the object is focused onto the target of an electronic sensor. Thus, an image plane hologram is formed as a result of the interference with an inline reference wave. In contrast with DSPI, a digital hologram is recorded without imaging. The target records the superposition of the reference and the object wave in the near-field region – a so-called Fresnel hologram. The basic optical setup in digital holography for recording holograms is the same as in conventional holography (Figure 1a). A laser beam is divided into two coherent beams, one illuminating the object and forming the object wave, the other entering the target directly and forming the reference wave. On this basis, very compact solutions are possible. Figure 1b shows a holographic camera where the interferometer, containing a beamsplitter and some wavefront shaping components, is mounted in front of the camera target.

For a description of the principle of digital Fresnel holography, we use a simplified version of the optical setup (Figure 2a). The object is modeled by a plane rough surface that is located in the (x, y)-plane and illuminated by laser light. The scattered wavefield forms the object wave $u(x, y)$. The target of an electronic sensor (e.g., a CCD or a CMOS) used for recording the hologram is located in the (ξ, η)-plane at the distance d from the object. Following the basic principles of holography, the hologram $h(\xi, \eta)$ originates from the interference of the object wave $u(\xi, \eta)$ and the reference wave $r(\xi, \eta)$





Figure 1 Setup for recording digital holograms. (a) Schematic setup for recording a digital hologram onto a CCD target. (b) Implementation of a holographic camera by mounting a compact holographic interferometer in front of a CCD-target (4 illumination directions are used). Reproduced from Seebacher S, Osten W, Baumbach Th and Jüptner W (2001) The determination of material parameters of microcomponents using digital holography. *Optics and Lasers in Engineering* 36(2): 103–126, copyright © 2001, with permission from Elsevier.

in the (ξ, η)-plane:

$$h(\xi,\eta) = |u(\xi,\eta) + r(\xi,\eta)|^2 = rr^* + ru^* + ur^* + uu^* \quad [1]$$

The transformation of the intensity distribution into a gray value distribution, that is stored in the image memory of the computer, is considered by the characteristic function t of the sensor. This function is generally only approximately linear:

$$T = t[h(\xi,\eta)] \quad [2]$$

Because the sensor has a limited spatial resolution, the spatial frequencies of the interference fringes in the hologram plane – the so-called micro-interferences – have to be considered. The fringe spacing g and the spatial frequency f_x, respectively, are determined by the angle β between the object and the reference wave (Figure 2b):

$$g = \frac{1}{f_x} = \frac{\lambda}{2\sin(\beta/2)} \quad [3]$$

with λ as the wavelength. If we assume that the discrete sensor has a pixel pitch (distance between adjacent pixels) $\Delta\xi$, the sampling theorem requires at least two pixels per fringe for a correct reconstruction of the periodic function:

$$2\Delta\xi < \frac{1}{f_x} \quad [4]$$

Consequently, we obtain for small angles β:

$$\beta < \frac{\lambda}{2\Delta\xi} \quad [5]$$

Modern high-resolution CCD or CMOS chips have a pitch, $\Delta\xi$, of about 4 µm. In this case, a maximum angle between the reference and the



Figure 2 Geometry for recording and reconstruction of digital holograms. (a) Schematic setup for Fresnel holography. (b) Interference between the object and reference wave in the hologram plane.

object wave of only 4° is acceptable. The practical consequence of the restricted angle resolution in digital holography is a limitation of the effective object size that can be stored holographically by an electronic sensor. However, this is only a technical handicap. Larger objects can be placed at a sufficient distance from the hologram, or reduced optically by imaging with a negative lens.

The reconstruction is done by illuminating the hologram with a so-called reconstruction wave $c(\xi, \eta)$:

$$u'(x', y') = t[h(\xi, \eta)]c(\xi, \eta) \qquad [6]$$

The hologram, $t[h(\xi, \eta)]$, diffracts the wave, $c(\xi, \eta)$, in such a way that images of the object wave are reconstructed. Usually four terms are reconstructed if the wave, $u'(x', y')$, propagates in space. An assumed linear characteristic function, $t(h) = \alpha h + t_0$, delivers:

$$u' = Tc = t(h)c \qquad [7]$$

and

$$u' = \alpha\lfloor cu^2 + cr^2 + cur^* + cru^* \rfloor + ct_0 \qquad [8]$$

with two relevant image terms, $[cur^*]$ and $[cru^*]$. The appearance of the image terms depends on the concrete shape of the reconstruction wave. Usually the reference wave, $c = r$, or its conjugated version, $c = r^*$, is applied. In the case of the conjugated reference wave, a direct or real image will be reconstructed due to a converging image wave that can be imaged on a screen at the location of the original object.

However, in digital holography the reconstruction of the object wave in the image plane, $u'(x', y')$, is done by numerical simulation of the physical process, as shown in Figure 3a. The reconstruction wave with a well-known shape equal to the reference wave, $r(\xi, \eta)$, propagates through the hologram, $h(\xi, \eta)$. Following the Huygens principle, each point, $P(\xi, \eta)$, on the hologram, acts as the origin of a spherical elementary wave. The intensity of these elementary waves is modulated by the transparency, $h(\xi, \eta)$. In a given distance, $d' = d$, from the hologram, a sharp real image of the object can be reconstructed as the superposition of all elementary waves. For the reconstruction of a virtual image, $d' = -d$ is used.

Consequently, the calculation of the wavefield, $u'(x', y')$, in the image plane starts with the pointwise multiplication of the stored and transformed intensity values, $t[h(\xi, \eta)]$, with a numerical model of the reference wave, $r(\xi, \eta)$. If the hologram is assumed to be uniformly illuminated by a normally incident, monochromatic plane wave of amplitude 1 the reference wave can be modeled by $r(\xi, \eta) = 1$. After the multiplication the resulting field in the hologram plane is propagated in free space. In the distance, d', the diffracted field, $u'(x', y')$, can be found by solving the well-known Rayleigh–Sommerfeld diffraction formula, that is also known as the



Figure 3 Reconstruction of digital holograms. (a) Principle of wave front reconstruction. (b) Light propagation by diffraction (Huygens–Fresnel principle).

Huygens–Fresnel principle:

$$u'(x', y') = \frac{1}{\mathrm{i}\lambda} \iint_{-\infty\cdots\infty} t[h(\xi, \eta)] r(\xi, \eta) \times \frac{\exp(\mathrm{i}k\rho)}{\rho} \cos\theta \, \mathrm{d}\xi \, \mathrm{d}\eta \qquad [9]$$

with

$$\rho(\xi - x', \eta - y') = \sqrt{d'^2 + (\xi - x')^2 + (\eta - y')^2} \qquad [10]$$

as the distance between a point $O'(x', y', z = d')$ in the image plane and a point $P(\xi, \eta, z = 0)$ in the hologram plane, and

$$k = \frac{2\pi}{\lambda} \qquad [11]$$

as the wave number. The obliquity factor, $\cos\theta$, represents the cosine of the angle between the outward normal and the vector joining P to O′. This term is given as:

$$\cos\theta = \frac{d'}{\rho} \qquad [12]$$

and therefore the Huygens–Fresnel principle can be rewritten:

$$u'(x', y') = \frac{d'}{\mathrm{i}\lambda} \iint_{-\infty\cdots\infty} t[h(\xi, \eta)] r(\xi, \eta) \frac{\exp(\mathrm{i}k\rho)}{\rho^2} \mathrm{d}\xi \mathrm{d}\eta \qquad [13]$$

This numerical reconstruction delivers the complex amplitude of the wavefront. Consequently, the phase distribution, $\phi(x', y')$, and the intensity, $I(x', y')$, can be calculated directly from the reconstructed complex function, $u'(x', y')$:

$$\phi(x', y') = \arctan \frac{\mathrm{Im}|u'(x', y')|}{\mathrm{Re}|u'(x', y')|} \qquad [-\pi, \pi] \qquad [14]$$

$$I(x', y') = u'(x', y') u'^*(x', y') \qquad [15]$$

The direct approach to the phase yields several advantages for imaging and metrology applications that are discussed later.

Reconstruction Principles in Digital Holography

Different numerical reconstruction principles have been investigated: the Fresnel approximation, the convolution approach, the lens-less Fourier approach, the phase shifting approach, and the phase-retrieval approach. In this section the main techniques are briefly described.

The Fresnel Approximation

If the distance, d, between the object and hologram plane, and equivalently, $d' = d$, between the hologram and image plane, is large compared to $(\xi - x')$ and $(\eta - y')$, then the denominator of eqn [13] can be replaced by d'^2 and the parameter ρ in the numerator can be approximated by a binomial expansion for the square root (10) where only the first two terms are considered:

$$\rho \approx d' \left[1 + \frac{(\xi - x')^2}{2d'^2} + \frac{(\eta - x')^2}{2d'^2} \right] \qquad [16]$$

The resulting expression for the field at (x', y') becomes

$$u'(x', y') = \frac{\exp(\mathrm{i}kd')}{\mathrm{i}\lambda d'} \iint_{-\infty\cdots\infty} t[h(\xi, \eta)] r(\xi, \eta) \times \exp\left[\frac{\mathrm{i}k}{2d'} \left\{ (\xi - x')^2 + (\eta - y')^2 \right\} \mathrm{d}\xi \, \mathrm{d}\eta \right] \qquad [17]$$

Equation [17] is a convolution integral that can be expressed as

$$u'(x', y) = \iint_{-\infty\cdots\infty} t[h(\xi, \eta)] r(\xi, \eta) H \times (\xi - x', \eta - y') \mathrm{d}\xi \, \mathrm{d}\eta \qquad [18]$$

with the convolution kernel:

$$H(x', y') = \frac{\exp(\mathrm{i}kd')}{\mathrm{i}\lambda d'} \exp\left[\frac{\mathrm{i}k}{2d'} (x'^2 + y'^2) \right] \qquad [19]$$

Another notation of eqn [17] is found if the term $\exp[(\mathrm{i}k/2d')(x'^2 + y'^2)]$ is taken out of the integral:

$$u'(x', y') = \frac{\exp(\mathrm{i}kd')}{\mathrm{i}\lambda \mathrm{d}'} \exp\left[\mathrm{i}\frac{k}{2d'} (x'^2 + y'^2) \right] \iint_{-\infty\cdots\infty} \times \left\{ t[h(\xi, \eta)] r(\xi, \eta) \exp\left[\mathrm{i}\frac{k}{2d'} (\xi^2 + \eta^2) \right] \right\} \times \exp\left[-\mathrm{i}\frac{2\pi}{\lambda d'} (\xi x' + \eta y') \right] \mathrm{d}\xi \, \mathrm{d}\eta \qquad [20]$$

or

$$u'(x', y') = \frac{\exp(\mathrm{i}kd')}{\mathrm{i}\lambda d'} \exp\left[\mathrm{i}\frac{\mathrm{k}}{2d'} (x'^2 + y'^2) \right] \times \mathrm{FT}_{\lambda d'} \left\{ t[h(\xi, \eta)] r(\xi, \eta) \exp\left[\mathrm{i}\frac{k}{2d'} (\xi^2 + \eta^2) \right] \right\} \qquad [21]$$

where $\mathrm{FT}_{\lambda d'}$ indicates the 2-dimensional Fourier transform that has been modified by a factor $1/(\lambda d')$. Equation [21] makes clear that the diffracted wavefront consists of the Fourier transform (FT) of the digitally stored hologram, $t[h(\xi,\eta)]$, multiplied by the reference wave, $r(\xi,\eta)$, and the chirp function, $\exp\{(i\pi/\lambda d')(\xi^2+\eta^2)\}$. This Fourier transform is scaled by the constant factor, $1/(id'\lambda)$, and a phase factor that is independent of the processed hologram.

The discrete sampling in digital processing requires the transformation of the infinite continuous integral in eqn [20] into a finite discrete sum. This results in the finite Fresnel transform:

$$u'(m,n) = \sum_{j=0}^{M-1}\sum_{l=0}^{N-1} t[h(j\Delta\xi, l\Delta\eta)]r(j\Delta\xi, l\Delta\eta) \times \exp\left[\frac{i\pi}{d'\lambda}(j^2\Delta\xi^2 + l^2\Delta\eta^2)\right] \times \exp\left\{-i2\pi\left(\frac{jm}{M}+\frac{ln}{N}\right)\right\} \quad [22]$$

where constants and pure phase factors preceding the sums have been omitted. The main parameters are the pixel number $M \times N$ and the pixel pitches $\Delta\xi$ and $\Delta\eta$ in the two directions, which are defined by the used sensor chip.

The discrete phase distribution, $\phi(m,n)$, of the wavefront and the discrete intensity distribution, $I(m,n)$, on the rectangular grid of $M \times N$ sample points can be calculated from the reconstructed complex function, $u'(m,n)$, by using eqns [14] and [15], respectively. The wrapped phase distribution is computed directly without the need of additional temporal or spatial phase modulation such as phase shifting or spatial heterodyning.

For interferometric applications with respect to displacement and shape measurement the phase difference, $\delta(m,n)$, of two reconstructed wave fields, $u_1'(m,n)$ and $u_2'(m,n)$, needs to be calculated. The algorithm can be reduced to the following equation:

$$\delta(m,n) = \phi_1(m,n) - \phi_2(m,n) \quad [23]$$

Figure 4 shows the principle of displacement measurement by digital holography. Besides the investigation of surface displacements in the region of the wavelength, digital holography can be applied advantageously for the measurement of the shape of complex objects. In Figure 5, a turbine blade was investigated with the 2-wavelength contouring method. Both, the digitally reconstructed mod 2π-phase and its demodulated version after-phase unwrapping, are presented. Phase unwrapping is necessary in digital holography, since the fringe-counting problem still remains. However, there are some efficient approaches to overcome the difficulties of this process.



Figure 4 The principle of digital holographic interferometry demonstrated on an example of a loaded small beam. The interference phase is the result of the subtraction of the two phases which correspond to the digital holograms of both object states.

Following eqn [22] the pixel spacing in the reconstructed image is

$$\Delta x' = \frac{d'\lambda}{M\Delta\xi} \quad \text{and} \quad \Delta y' = \frac{d'\lambda}{N\Delta\eta} \quad [24]$$

Additional to the real image, a blurred virtual image and a bright dc-term, the zero-order diffracted field, is reconstructed. This term can effectively be eliminated by preprocessing the stored hologram or the different terms can be separated by using the off-axis instead of the in-line technique. However, the spatial separation between the object and the reference field requires a sufficient space-bandwidth product of the used CCD-chip, as discussed in the section on direct phase reconstruction above.

Numerical Reconstruction by the Convolution Approach

In the section above, we have already mentioned that the connection between the image term, $u'(x',y')$, and the product, $t[h(\xi,\eta)]r(\xi,\eta)$, can be described by a linear space-invariant system. The diffraction formula [17] is a superposition integral with the impulse response:

$$H(x'-\xi, y'-\eta) = \frac{\exp(ikd')}{i\lambda d'} \times \exp\left[\frac{ik}{2d'}\{(\xi-x')^2+(\eta-y')^2\}\right] \quad [25]$$

A linear space-invariant system is characterized by a transfer function G, that can be calculated as the



Figure 5 Phase reconstruction by digital holographic interferometry on an example of 2-wavelength contouring of a turbine blade. (a) Image of the turbine blade. (b) Mod-2π phase distribution. (c) Unwrapped phase distribution. (d) CAD reconstruction of the turbine blade.

Fourier-transform of the impulse response:

$$G(f_x, f_y) = \mathrm{FT}\{H(\xi, \eta, x', y')\} \qquad [26]$$

with the spatial frequencies f_x and f_y. Consequently, the convolution theorem can be applied, which states that the Fourier transform of the convolution, $t[h(\xi, \eta)]r(\xi, \eta)$, with H is the product of the individual Fourier transforms, $\mathrm{FT}\{t[h(\xi, \eta)]r(\xi, \eta)\}$ and $\mathrm{FT}\{H\}$. Thus $u'(x', y')$ can be calculated by the inverse Fourier transform of the product of the Fourier-transformed convolution partners:

$$u'(x', y') = \mathrm{FT}^{-1}\{\mathrm{FT}[t(h)r]\mathrm{FT}[H]\} \qquad [27]$$

$$u'(x', y') = [t(h)r] \otimes H \qquad [28]$$

with $\otimes$ as the convolution symbol. The computing effort is comparatively high: two complex multiplications and three Fourier transforms. The main difference to the Fresnel transform is the different pixel size in the reconstructed field:

$$\Delta x' = \Delta\xi \quad \text{and} \quad \Delta y' = \Delta\eta \qquad [29]$$

Numerical Reconstruction by the Lensless Fourier Approach

We have already mentioned that the limited spatial resolution of the sensor restricts the angle resolution of the digital hologram. The sampling theorem requires that the angle between the object beam and the reference beam at any point of the electronic sensor be limited in such a way that the microinterference spacing is larger than double the pixel size. In general, the angle between the reference beam and the object beam varies over the sensor's surface, and so does the maximum spatial frequency. Thus, for most holographic setups, the full spatial bandwidth of the sensor cannot be used. However, it is important to use the entire spatial bandwidth of the sensor because the lateral resolution of the reconstructed image depends on a complete evaluation of the entire information obtained from the sensor.

Even if the speed of digital signal processing is increasing rapidly, algorithms should be as simple and as fast to compute as possible. For the Fresnel approach and the convolution approach, several fast Fourier transforms and complex multiplications are necessary. Therefore, a more effective approach, such as the subsequently described algorithm, seems promising.

The lensless Fourier approach is the fastest and most suitable algorithm for small objects. The corresponding setup is shown in Figure 6. It allows us to choose the lateral resolution in a range from a few microns to hundreds of microns without any additional optics. Each point, (ξ, η), on the hologram is again considered as a source point of a spherical elementary wavefront (Huygen's principle). The intensity of these elementary waves is modulated by $t[h(\xi, \eta)]$ – the amplitude transmission of the hologram. The reconstruction algorithm for lensless Fourier holography is based on the Fresnel reconstruction. Here again, $u(x, y)$ is the object wave in the object plane, $h(\xi, \eta)$ the hologram, $r(\xi, \eta)$ the reference wave in the hologram plane, and $u'(x', y')$ the reconstructed wavefield.

For the specific setup of lensless Fourier holography, a spherical reference wave is used with an origin at the same distance from the sensor as the object itself. In the case that $d' = -d$, $x = x'$, and $y = y'$, both virtual images are reconstructed and the reconstruction algorithm then reads:



Figure 6 Scheme of a setup for digital lensless Fourier holography of diffusely reflecting objects.

$$u'(x', y') = \frac{\exp(\mathrm{i}kd)}{\mathrm{i}\lambda d}\, \mathrm{e}^{-\mathrm{i}\frac{k}{2d}(x^2+y^2)} \times \mathrm{FT}_{\lambda d'}\left\{t[h(\xi,\eta)]\cdot r(\xi,\eta)\cdot \mathrm{e}^{-\mathrm{i}\frac{k}{2d}(\xi^2+\eta^2)}\right\} \quad [30]$$

with $\mathrm{FT}_{\lambda d}$ as the 2-dimensional Fourier transformation which has been scaled by a factor $1/\lambda d$. In this recording configuration, the effect of the spherical phase factor associated with the Fresnel diffraction pattern of the object is eliminated by the use of a spherical reference wave, $r(\xi, \eta)$, with the same average curvature:

$$r(x, y) = \text{const.} \times \exp\left(\mathrm{i}\frac{\pi}{\lambda d}(\xi^2 + \eta^2)\right) \quad [31]$$

This results in a more simple reconstruction algorithm which can be described by

$$u'(x', y') = \text{const.} \times \exp\left(-\mathrm{i}\frac{\pi}{\lambda d}(x^2 + y^2)\right) \times \mathrm{FT}_{\lambda d}\{h(\xi, \eta)\} \quad [32]$$

Besides the simpler and faster reconstruction algorithm (only one Fourier transformation has to be computed), the Fourier algorithm uses the full space-bandwidth product (SBP) of the sensor chip because it adapts the curvature of the reference wave to the curvature of the object wave.

Influences of Discretization

For the estimation of the lateral resolution in digital holography, three different effects related to discretization have to be considered: averaging, sampling, and the limited sensor size. We assume a quadratic sensor with $N \times M$ pixels of the size $\Delta\xi \times \Delta\xi$. Each pixel has a light-sensitive region with a side length $\gamma\Delta\xi = \Delta\xi_{\mathrm{eff}}$. γ^2 is the so-called fill factor $(0 \leq \gamma \leq 1)$, that indicates the active area of the pixel. The sensor averages the incident light which has to be considered because of possible intensity fluctuations over this area. The continuous expression for the intensity $I(\xi, \eta) = t[h(\xi, \eta)]$, registered by the sensor, has to be integrated over the light-sensitive area. This can be expressed mathematically by the convolution of the incident intensity $I(\xi, \eta)$, with a rectangle function:

$$I^1(\xi, \eta) \propto I \otimes \mathrm{rect}_{\Delta\xi_{\mathrm{eff}},\Delta\xi_{\mathrm{eff}}} \quad [33]$$

The discrete sampling of the light field is modeled by the multiplication of the continuous assumed hologram with the 2-dimensional comb-function:

$$I^2(\xi, \eta) \propto I^1(\xi, \eta) \times \mathrm{comb}_{\Delta\xi.\Delta\xi} \qquad [34]$$

Finally, the limited sensor size requires that the comb-function has to be truncated at the borders of the sensor. This is considered by the multiplication with a 2-dimensional rect-function of the size $N \times \Delta\xi$:

$$I^3(\xi, \eta) \propto I^2 \times \mathrm{rect}_{N\Delta\xi N.\Delta\xi} \qquad [35]$$

The consequences are amplitude distortions, aliasing and speckling that have to be considered in the reconstruction procedure.

Advantages of Digital Holography

Besides the electronic processing and the direct access to the phase, some further advantages recommend digital holography for several applications such as metrology and microscopy:

- The availability of the independently reconstructed phase distributions of each individual state of the object and interferometer, respectively, offers the possibility to record a series of digital holograms with increased load amplitude. In the evaluation process, the convenient states can be compared interferometrically. Furthermore, a series of digital holograms with increasing load can be applied to unwrap the mod 2π-phase temporally. In this method, the total object deformation is subdivided into many measurement steps, in which the phase differences are smaller than 2π. By adding up those intermediate results, the total phase change can be obtained without any further unwrapping. This is an important feature, since it is essential to have an unwrapped phase to be able to calculate the real deformation data from the phase map. Figure 7 shows an example of such a measurement. The left image shows the wrapped deformation phase for a clamped coin which was loaded with heat. The right image shows the temporal unwrapped phase which has been obtained by dividing the total deformation into 85 sub-measurements. Thus, the displacement of the object can be observed almost in real time during the loading process.
- The independent recording and reconstruction of all states also gives a new degree of freedom for optical shape measurement. In the case of multiwavelength contouring, each hologram can be stored and reconstructed independently with its corresponding wavelength. This results in a drastic decrease of aberrations and makes it possible to use larger wavelength differences for the generation of shorter synthetic wavelengths.



Figure 7 Temporal unwrapping by digital holography: (a) Wrapped phase of a thermal loaded coin. (b) Temporally unwrapped phase.

- Because all states of the inspected object can be stored and evaluated independently, only seven digital holograms are necessary to measure the 3D-displacement field and shape of an object under test: one hologram for each illumination direction before and after the loading, respectively, and one hologram with a different wavelength (or a different source-point of illumination) which can interfere with one of the other holograms to perform two-wavelength-contouring (or two-source-point-contouring) for shape measurement. If four illumination directions are used, nine holograms are necessary.
- The direct access to all components of the wavefield makes it possible to correct wavefront aberrations effectively by computer.
- The digital hologram containing all information of the wavefront can be transmitted via the internet to any location and can be reconstructed digitally by computer or as an analogue version by a spatial light modulator. Consequently, remote access to wavefronts, that are generated at distant places, is possible.
- Finally, the possibility to miniaturize complex holographic sensor setups and to use this method for remote comparative interferometry, makes digital holography a versatile tool for the solution of numerous inspection and measurement problems.

See also

Diffraction: Fresnel Diffraction. **Fourier Optics**. **Holography, Techniques:** Holographic Interferometry.

Further Reading

Butters JN and Leendertz JA (1971) Holographic and video techniques applied to engineering measurement. *Journal of Measurement Control* 4: 349–354.

Creath K (1993) Temporal phase measurement methods. In: Robinson DW and Reid GT (eds) *Interferogram Analysis*. Bristol and Philadelphia: IOP Publishing Ltd.

Demetrakopoulos T and Mittra T (1974) Digital and optical reconstruction of images from suboptical diffraction patterns. *Applied Optics* 13: 665–670.

Denisyuk YuN (1962) Photographic reconstruction of the optical properties of an object in its own scattered radiation field. *Doklady Akademii Nauk SSSR* 144: 1275–1279.

Gabor D (1949) Microscopy by reconstructed wavefronts. *Proceedings of the Royal Society, A* 197: 454–487.

Goodman JW (1996) *Introduction to Fourier Optics*. New York: McGraw Hill Comp. Inc.

Goodman JW and Lawrence RW (1967) Digital image formation from electronically detected holograms. *Applied Physics Letters* 11: 77–79.

Kolenovic E, Osten W, Klattenhoff R, Lai S, Kopylow C and Jüptner W (2003) Miniaturized digital holography sensor for distal three-dimensional endoscopy. *Applied Optics* 42(25): 5167–5172.

Kreis T (1996) *Holographic Interferometry*. Berlin: Akademie Verlag.

Kreis Th and Jüptner W (1997) Principles of digital holography. In: Jüptner W and Osten W (eds) *Proc. Fringe'97, 3rd International Workshop on Automatic Processing of Fringe Patterns*, pp. 353–363. Berlin: Akademie Verlag.

Kreis Th and Jüptner W (1997) The suppression of the dc-term in digital holography. *Optical Engineering* 36: 2357–2360.

Kujawinska M (1993) Spatial phase measurement methods. In: Robinson DW and Reid GT (eds) *Interferogram Analysis*. Bristol and Philadelphia: IOP Publishing Ltd.

Lee W-H (1978) Computer generated holograms: techniques and applications. In: Wolf E (ed.) *Progress in Optics*, vol. XVI, pp. 121–230. Amsterdam: North Holland.

Leith EN and Upatnieks J (1961) New techniques in wavefront reconstruction. *JOSA* 51: 1469–1473.

Osten W (2000) Holography and virtual 3D-testing. Proc. International Berlin Workshop HoloMet 2000, New Prospects of Holography and 3D-Metrology, *Strahltechnik* 14: 14–17.

Osten W (2003) Active metrology by digital holography. *Proceedings of SPIE* 4933: 96–110.

Osten W and Kujawinska M (2000) Active phase measuring metrology. In: Rastogi PK and Inaudi D (eds) *Trends in Optical Nondestructive Testing and Inspection*, pp. 45–69. Amsterdam: Elsevier Science B.V.

Osten W, Jüptner W and Seebacher S (1998) *The Qualification of Large Scale Approved Measurement Techniques for the Testing of Microcomponents*. Proc. 18th Symposium on Seebacher, Experimental Mechanics of Solids, Jachranka, pp. 43–55.

Osten W, Baumbach T, Seebacher S and Jüptner W (2001) Remote shape control by comparative digital holography. *Proc. Fringe 2001*, Bellingham: Elsevier Science, pp. 373–382.

Osten W, Seebacher S and Jüptner W (2001) The application of digital holography for the inspection of microcomponents. *Proceedings of SPIE* 4400: 1–15.

Osten W, Baumbach T and Jüptner W (2002) Comparative digital holography. *Optics Letters* 27(20): 1764–1766.

Pedrini G, Schedin S and Tiziani HJ (2001) Aberration compensation in digital holographic reconstruction of microscopic objects. *Journal of Modern Optics* 48: 1035–1041.

Powell RL and Stetson K (1965) Interferometric vibration analysis of three-dimensional objects by wavefront reconstruction. *JOSA* 55: 1593–1598.

Schnars U (1994) Direct phase determination in hologram interferometry with use of digitally recorded holograms. *Journal of the Optical Society of America A* 11: 2011–2015.

Schnars U and Jüptner W (1994) Direct recording of holograms by a CCD target and numerical reconstruction. *Applied Optics* 33(2): 179–181.

Seebacher S (2001) Application of digital holography for 3d-shape and deformation measurement of micro components. PhD thesis, University of Bremen.

Seebacher S, Osten W and Jüptner W (1997) 3-D deformation analysis of micro-components using digital holography. *Proceedings of SPIE* 3098: 382–391.

Seebacher S, Osten W, Baumbach Th and Jüptner W (2001) The determination of material parameters of microcomponents using digital holography. *Optics and Lasers in Engineering* 36(2): 103–126.

Takeda M, Taniguchi K, Hirayama T and Kogho H (1996) Single transform Fourier–Hartley fringe analysis for holographic interferometry. In: Füzessy Z, Jüptner W and Osten W (eds) *Simulation and Experiment in Laser Metrology*, pp. 67–73. Berlin: Akademie Verlag.

Wagner C, Seebacher S, Osten W and Jüptner W (1999) Digital recording and numerical reconstruction of lensless Fourier holograms in optical metrology. *Applied Optics* 38(22): 4812–4820.

Wagner C, Osten W and Seebacher S (2000) Direct shape measurement by digital wavefront reconstruction and multi-wavelength contouring. *Optical Engineering* 39(1): 79–85.

Yamaguchi I and Zhang T (1979) Phase-shifting digital holography. *Optical Letters* 22: 1268–1270.

Yaroslavsky LP and Merzlyakov NS (1980) *Methods of Digital Holography*. New York: Consultants Bureau.

Zhang Y, Pedrini G, Osten W and Tiziani H (2003) Image reconstruction for in-line holography with the Yang-Gu algorithm. *Applied Optics* 42(32): 6452–6457.

Holographic Interferometry

P Rastogi, Swiss Federal Institute of Technology, Lausanne, Switzerland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The development of holographic interferometry has redefined our perception of optical interferometry. The unique property of holographic interferometry to bring a wavefront, generated at some earlier time, stored in a hologram and released at a later time, to interfere with a comparison wavefront, has made possible the interferometric comparison of a rough surface, which is subject to stress, with its normal state. Assuming the surface deformations to be very small, the interference of the two speckled wavefronts forms a set of interference fringes that are indicative of the amount of displacement and deformation undergone by the diffuse object.

Holographic interferometry is an important and exciting area of research and development. It has established itself as a highly promising noninvasive technique in the field of optical metrology. Techniques within its folds for the measurement of static and dynamic displacements, topographic contours, and flow fields have been developed and demonstrated with success in a wide range of problems. Significant and extensive contributions to the development of holographic interferometry have been realized both from the theoretical and experimental perspectives. A wide range of procedures have been developed which make it not only possible to measure surface displacements and deformations of engineering structures to an accuracy of a fraction of a micrometer but also to detect material flaws and inhomogeneities having escaped the manufacturing process. The methodology of quantitative analysis of holographic interferograms has undergone extensive development during the last decade. This article provides a brief review of the holographic techniques with emphasis placed on bringing out its relevance in experimental mechanics and nondestructive testing. The series of books given in the Further Reading section at the end of this article treat the field in detail.

Basic Methods in Holographic Interferometry

The ability of holography to store a wavefront and release it for reconstruction at a later time offers access to the possibility to compare wavefronts, which have albeit existed at different times. There are several schemes that have been established to obtain the interferometric comparison of the wavefronts.

Double-Exposure Holographic Interferometry

In frozen form of wavefront comparison, two holograms of the object are recorded on a photographic plate. The first hologram is made with the object in its initial, unstressed state and the second hologram is recorded with the object in its final, stressed state. Upon reconstruction, the hologram releases the two stored wavefronts, one corresponding to the object in its unstressed state and the other corresponding to the object in its stressed state (Figure 1). The virtual image is overlaid by a set of



Figure 1 Layout for observing a double exposure holographic interferogram.

bright and dark interference fringes, which are due to the displacement of the object between the two exposures.

The fringe pattern is permanently stored on the holographic plate. The interference fringes denote the loci of points that have undergone an equal change of optical path between the light source and the observer. The image intensity of the holographic interferogram is

$$I(x, y) = I_0(x, y)\{1 + V(x, y)\cos(\varphi(x, y) - \varphi'(x, y))\} \qquad [1]$$

where $I_0(x, y)$ is the background intensity, $V(x, y)$ is the fringe contrast, and φ and φ' are the phases of the waves from the object in its initial and deformed states, respectively.

A bright fringe is produced whenever

$$\varphi(x, y) - \varphi'(x, y) = 2n\pi \qquad n = 0, 1, 2, \ldots \qquad [2]$$

where n is the fringe number. The wave scattered by a rough surface shows rapid variations of phase, which have little correlation across the wavefront. The phase difference varies randomly over the ray directions contained within the aperture of the viewing system, which would normally prevent the observation of fringes with large aperture optics near such points. However, a surface may exist at a distance from the object at which the value of phase difference is stationary over the cone of ray pairs defined by the viewing aperture. Interference fringes are localized in the region where the variation in phase difference is minimum over the range of viewing directions. This approach has been widely used to compute fringe localization for any object displacement and for any arbitrary illumination and observation geometry.

Real-Time Holographic Interferometry

A hologram is made of an arbitrarily shaped rough surface. After development, the hologram is placed back in exactly the same position. Upon reconstruction, the hologram produces the original wavefront. A person looking through the hologram sees a superposition of the original object and its reconstructed image (Figure 2). The object wave interferes with the reconstructed wave to produce a dark field due to destructive interference. If the object is now slightly deformed, interference fringes are produced which are related to the change in shape of the object. A dark fringe is produced, whenever:

$$\varphi(x, y) - \varphi'(x, y) = 2n\pi \qquad n = 0, 1, 2, \ldots \qquad [3]$$

The method is very useful for determining the direction of the object displacement, and for compensating on the interferogram the influence of the rigid body motion of the object when subjected to a stress field.

The optical setup for real-time holography uses an immersion tank, which is mounted on a universal stage and contains the photographic plate. The holographic plate is followed by a vidicon camera, which visualizes the interferograms directly onto the TV monitor screen connected to a video-recording tape to memorize the information. The use of thermoplastic plates as recording material has gained in importance in recent years for implementing real-time and double exposure holographic interferometry setups, as it can be processed rapidly *in situ* using electrical and thermal processing.



Figure 2 Layout for observing a holographic interferogram in real-time.

The plate is also cost-effective as it is erasable and reusable at least several hundred times. In thermoplastic recording the information is recorded as a thickness variation corresponding to a charge intensity pattern deposited on the thermoplastic layer. Self-developing or photorefractive crystals are other interesting alternatives to the use of film as the recording medium.

Digital Holographic Interferometry

The method consists of recording two holograms corresponding to undeformed and deformed states of an object using a CCD camera. These images are stored in a digital image processing system. The two holograms are then reconstructed separately by numerical methods from the digitaly stored holograms. The advantage of digital holography is that it allows for computing both the intensity and the phase of a holographically stored wavefront during the numerical reconstruction. The contours of constant optical phase change, due to deformation, are obtained by subtracting the reconstructed phases of the undeformed from the deformed object wavefield.

A hologram can be recorded on a CCD as long as the sampling theorem is fulfilled; that is to say, each period of the spatial variation of the hologram intensity is sampled by at least two pixels of the CCD array. The condition imposes a limit on the angle that the object beam can make with the reference beam, which must necessarily be small given that the resolution of CCDs is relatively low. The applications of the method are thus limited mainly by the pixel size in CCD array. The maximum spatial frequency $f_{\max}$ that must be resolved by the recording medium is determined by the maximum angle $\Delta\theta_{\max}$ between the reference and the object wave:

$$f_{\max} = \frac{2}{\lambda}\sin\frac{\Delta\theta_{\max}}{2} \qquad [4]$$

where λ is the wavelength of the laser source. Since the CCD cameras have resolutions of around 100 lines/mm, the maximum angle between the object and reference waves is limited to a few degrees.

Calculation of Phase Change on Object Loading

A diffusely reflecting object is deformed such that a point P on the surface moves to P′ as shown in Figure 3. In double-exposure or real-time holographic interferometry the two wavefronts related to the states of a surface before and after deformation are reconstructed simultaneously and compared. The change of optical path length due to displacement d is



Figure 3 Calculation of the change in optical phase due to surface displacement.

$$\Delta\varphi = \frac{2\pi d}{\lambda}(\cos\psi_1 + \cos\psi_2) \qquad [5]$$

where ψ_1 and ψ_2 are the angles which the illumination and observation waves make with respect to the direction of displacement; eqn [5] can be written in the form:

$$\Delta\varphi = \frac{2\pi d}{\lambda}\cos\eta\cos\psi \qquad [6]$$

where ψ is the angle of bisection between the incident and viewing directions, and η is the angle which the bisector makes with the direction of displacement. The term $d\cos\eta$ being the resolved part of the displacement PP′ in the direction of the bisector, implies that the fringe pattern provides the measure of the displacement component along the bisector of the angle between the incident and viewing directions.

Digital Phase Measurement

The last decade has seen a rapid development of techniques for the automatic and precise reconstruction of phases from fringe patterns. These are based on the concepts of fringe tracking, Fourier transform, carrier frequency, and phase shift interferometry. Quantitative measurement of wavefront phase, for example, can be obtained in a few seconds using phase shift interferometry. With this technique one records a series of holograms by introducing artificially known steps of phase differences in the interference image in eqn [1]:

$$I_i(x,y) = I_0(x,y)\{1 + V(x,y)\cos(\Delta\varphi(x,y) + \Delta\psi_i)\}; \quad i = 0,1,2,\ldots \qquad [7]$$

where $\Delta\psi_i$ is the phase shift which is produced, for example, by shifting the phase of the reference wave. A minimum of three intensity patterns is required to calculate the phase at each point on the object surface. Known phase shifts are commonly introduced using a piezoelectric transducer, which serves to shorten or elongate the reference beam path by a fraction of wavelength; the phase-shifter is placed in one arm of the interferometer. Numerous phase shifting techniques have been developed and which can be incorporated to holographic interferometry to generate a phase map, $\Delta\varphi(x, y)$, corresponding to the object displacement. The calculated phase $\Delta\varphi(x, y)$ is independent of the terms $I_0(x, y)$ and $V(x, y)$, and considerably reduces the dependence of the accuracy of measurements on the fringe quality.

The introduction of phase shift interferometry not only provides accurate phase measurements but also eliminates the problem of phase sign ambiguity of the interference fringes. Dynamic phase shifting techniques allow for producing time sequences of deformation maps for studying objects subjected to time-varying loads. The concept is based on considering the normal phase variations caused by a dynamic phenomenon as equivalent to the phase shifting that is introduced in a holographic interferometer in order to perform the phase evaluation task. This method extends the possibility of applying the method to continuous deformation measurements.

Basic Interferometers for Static Displacement Measurement

Equation [6] shows that observation along a single direction yields information only about the resolved part of the surface displacement in one particular direction. The approach to measuring three-dimensional vector displacement would be to record holograms from three different directions in order to obtain three independent resolved components of displacement. The computation of the resulting system of equations would then allow for determining the complete displacement vector.

Out-of-Plane Displacement Component Measurement

The out-of-plane component of displacement is usually measured by illuminating and viewing the object surface in a near normal direction. The fringe equation corresponding to the line of sight displacement component is given by

$$w = \frac{n\lambda}{2} \qquad [8]$$

where w is the out-of-plane component of displacement. An example of a fringe pattern depicting the out-of-plane displacements in a rectangular aluminum plate, clamped along the edges and drawn out at the center by means of a bolt, subjected to three-point loading, is shown in Figure 4.

In-Plane Displacement Component Measurement

The in-plane component of displacement can be measured by illuminating the object along two directions symmetric to the surface normal and observing along a common direction. This is schematized in Figure 5. The in-plane displacements, in a direction containing the two beams, are mapped as a moiré between the interferograms due to each illumination beam. The moiré appears as a family of fringes:

$$u = \frac{n\lambda}{2\sin\theta_e} \qquad [9]$$



Figure 4 Example of interferogram corresponding to the whole field distribution of out-of-plane component of displacement, *w*, on an aluminum plate subjected to three-point bending.



Figure 5 Schematic of the geometrical configuration for measuring the in-plane component of displacement, *u*.



Figure 6 Fringe contours showing the in-plane displacement response of a disk under diametral compression.

where u is the displacement component in the x-direction and θ_e is the angle which the illumination beams make with the surface normal. Figure 6 shows the u pattern corresponding to a disk under diametral compression. The moiré pattern is obtained after optically filtering the interference image.

Comparative Holographic Interferometry

Another technique of significant interest in non-destructive testing is comparative holography that provides the contours of path variations related to the difference in displacements or shapes of two objects. The method provides information about the resolved part of the difference in displacement vector along the direction bisecting the illumination and observation rays. In the case of illumination and observation normal to the object surface, the fringe equation becomes

$$\Delta w = \frac{n\lambda}{2} \qquad [10]$$

where Δw is the difference in displacement component along z direction. The technique provides a tool to compare the mechanical responses of two nominally identical specimens subjected to the same loading and also the shapes of two nominally identical specimens. These features are useful in detecting anomalies in a test specimen with respect to the flaw-free master specimen. One such example is shown in Figure 7a, which displays the presence of a defect in a test specimen. In this case two plates, one flaw-free and the other with a flaw, are subjected to identical loadings. The fringe map in Figure 7b is related to the difference in displacements of test and master specimens subjected to unequal loadings. The presence of flaws is detected in both interferograms.

Basic Interferometers for Dynamic Displacement Measurement

Another important application of holographic interferometry is in the study of the resonant modes of vibration of an object.



Figure 7 Comparative holography reveals the presence of defects in aluminum plates using (a) identical and (b) unequal loadings.



Figure 8 (a) Schematic of the geometrical configuration of a vibrating cantilever beam; (b) plot of fringe function for time-average holography.

Frozen Time-Average Holographic Interferometry

Consider that a hologram is recorded of an object, which is vibrating sinusoidally in a direction normal to its surface (Figure 8a). The exposure time is supposed to be much longer than the period of vibration. The intensity distribution of the image reconstructed by this hologram is

$$I(x, y) = I_o(x, y) J_o^2\left[\frac{2\pi}{\lambda} d(x, y)(\cos \theta_e + \cos \theta_o)\right] \quad [11]$$

where J_o is the zero-order Bessel function of the first kind. The virtual image is modulated by the $J_o^2(\xi)$ function. The dark fringes correspond to the zeros of the function $J_o^2(\xi)$. A plot of the function, shown in Figure 8b, is characterized by a comparatively brighter zero-order fringe, which corresponds to the nodes, a decreasing intensity, and an unequal spacing between the successive zeros. The interferogram in Figure 9 shows the vibrational modes of a helicopter component. The nodes that represent zero motion are clearly seen as the brightest areas in the time average reconstructed pattern.

Real-Time Time-Average Holographic Interferometry

The possibility of studying the response of vibrating objects in real-time extends the usefulness of the technique to identify the resonance states (resonant vibration mode shapes and resonant frequencies) of the object. A single exposure is made of the object in its state of rest. The plate is processed, returned to its original condition and reconstructed. The observer looking through the hologram at the sinusoidally



Figure 9 Fringe contours showing the mode shape of a vibrating helicopter component.

vibrating object sees the time-averaged intensity:

$$I(x,y) = I_o(x,y)\left[1 - J_o\left\{\frac{2\pi}{\lambda}d(x,y)(\cos\theta_e + \cos\theta_o)\right\}\right] \qquad [12]$$

Stroboscopic Holographic Interferometry

Stroboscopic holography is another interesting variant in the study of vibrations. The hologram is recorded by exposing the photographic plate twice for short time intervals during a vibration cycle. The pulsed exposures are synchronized with the vibrating surface, which is equivalent to making the surface virtually stationary during the recording. Reconstruction of the hologram yields cosinusoidal fringes, which are characteristic of double exposure holography. In real-time stroboscopic holography, a hologram of a nonvibrating object is first recorded. If the vibrating object is illuminated stroboscopically and viewed through the hologram, the reconstructed image from the hologram interferes directly with the light scattered from the object to generate live fringes.

Flow Measurement

Application of holographic interferometry to flow visualization and the measurement of spatial refractive index, density or temperature distributions have led to an advancement of understanding in areas such as aerodynamics, plasma diagnostics, and heat transfer. In the holographic interferometer shown in Figure 10 two consecutive exposures are made, usually the first exposure without flow and the second in the presence of a flow field. Double pulsed holography is used if the flow field is changing rapidly. The optical phase change due to flow between the exposures is



Figure 10 Schematic of a configuration for studying flow.



Figure 11 Fringe contours showing the phase distribution of a test flame.

$$\Delta\varphi(x,y) = \frac{2\pi}{\lambda}\int_0^t \{n'(x,y,z) - n'_o\}\mathrm{d}z \qquad [13]$$

where $n'(x,y,z)$ is the refractive index distribution during the second exposure, n'_o is the uniform refractive index during the first exposure, and t is the length of the test section. Assuming that the properties of the flow are constant in the z direction, the expression for phase change can be expressed as

$$\Delta\tau(x,y) = KL\{\rho(x,y) - \rho_o\} \qquad [14]$$

where K is the Gladstone–Dale constant, ρ is the density of the gas, and ρ_o is the density in a no-flow situation. The interference pattern contours the change in the density field of the flow. The change in density per fringe is given by λ/Kt. An example of application related to temperature measurements in an axisymmetric premixed flame is illustrated in Figure 11.



Figure 12 Schematic diagram of a two-beam method for shape measurement.

Surface Contouring

A practical way to display the shape of an object is to obtain contour maps showing the intersection of the object with a set of equidistant planes orthogonal to the line of sight.

The Dual Refractive Index Method

The method requires placing the model in a glass tank filled with a liquid (or gas) of refractive index n'_1. A hologram of the object is recorded, and the liquid contained in the tank is replaced by one of refractive index n'_2. An observer looking through the hologram sees the object surface modulated by a set of interference fringes arising from the change of optical phase in the light rays traversing the two liquids. The contour interval is given by

$$\Delta z = \frac{\lambda}{2(n'_1 - n'_2)} \qquad [15]$$

The Dual Illumination Method

In this method, the object is illuminated obliquely by collimated beams along two directions symmetric to the surface normal. The scattered waves are recorded on a holographic plate and the object and its reconstructed image are viewed through the hologram. Two sets of parallel equidistant fringes are projected onto the object surface by introducing small tilts, $\Delta\theta_e$, to the illumination beams (Figure 12). The contour sensitivity per fringe is given by

$$\Delta z = \frac{\lambda}{2\sin\theta_e \sin\Delta\theta_e} \qquad [16]$$

The sensitivity of the method can be tuned in a wide range. An example of topographic contour pattern is shown in Figure 13. The distance between two adjacent moiré contour planes is 172 μm.



Figure 13 Example of a moiré topographic contour pattern obtained using the two-beam method.



Figure 14 Examples of (a) shape measurement: the distance between two adjacent contour planes is 208 μm; and, (b) very large out-of-plane deformation measurement on a cantilever beam. The distance between two adjacent contour planes is 19 μm.


X
Illumination beam
Shearing imaging device
Δx
Image reconstruction plane
Hologram
Reference

Figure 15 Schematic diagram of the principle used in holographic shearing interferometry.



Figure 16 Examples of (a) moiré fringe contour, and (b) phase distribution corresponding to slope change produced on a centrally loaded aluminum plate clamped along its boundary.

In another method a collimated beam obliquely illuminates the object and a set of parallel equidistant fringes is projected onto the object surface by introducing a small tilt, $\Delta\theta_e$, to the illumination beam. Providing an appropriate reference beam rotation and a holographic plate translation generates contouring surfaces normal to the line of sight. A typical result using one beam illumination is shown in Figure 14a. The distance between two adjacent moiré contour planes is 208 μm.

This approach has been used to obtain measurement of large out-of-plane deformations undergone by a deformed object. The fringe pattern in Figure 14b corresponds to the out-of-plane displacement of a cantilever beam subjected to load at its free end. The distance between two adjacent contour planes is 19 μm.

Holographic Shearing Interferometry

Holographic shearing interferometry directly provides the patterns of slope change contours by laterally shearing wavefronts diffracted from the object surface. There are numerous ways to achieve shearing, such as, by introducing a Michelson type configuration, an inclined glass plate device, or a split-lens assembly in a holographic interferometer. The role of the shearing device is to enable the observation of a point on the object along two distinct neighboring directions. As a result of lateral wavefront shearing in the interferometer, a point in the image plane receives contributions from two different points on the object (Figure 15). Assuming that the illumination beam lies in the $x-z$ plane and makes an angle θ_e with the z-axis, and the observation is carried along the direction normal to the object surface, the change of optical phase due to deformation is

$$\Delta\varphi = \frac{2\pi}{\lambda}\left[\frac{\partial u}{\partial x}\sin\theta_e + \frac{\partial w}{\partial x}(1+\cos\theta_e)\right]\Delta x \qquad [17]$$

where Δx is the object shear along the x-direction. For $\theta_e = 0$, eqn [11] reduces to

$$\frac{\partial w}{\partial x} = \frac{n\lambda}{2\Delta x} \qquad [18]$$

Equation [18] displays a family of holographic moiré fringes corresponding to the contours of constant slope change. The fringe pattern shown in Figure 16a illustrates a moiré corresponding to contours of constant slope change for a centrally loaded square aluminum plate clamped along its boundary. An example of phase distribution



Figure 17 Example taken from the study of the fracture process zone in concrete: phase distribution corresponds to in-plane displacements on a notched concrete specimen subjected to a wedge splitting test.



Figure 18 Example of application to nondestructive testing on a fingertip-joint wood specimen under tension using an in-plane sensitive holographic moiré setup.



Figure 19 Application to the detection of defects in a tyre. Courtesy of H. Steinbichler, Steinbichler GmbH.


(a) (b)

Figure 20 Fringe contours showing (a) a specific limb movement of a chick embryo during incubation, and (b) the hatching behavior. The point on the shell receiving blows is clearly visible.

corresponding to slope change along x-direction, is shown in Figure 16b.

Examples of Applications

Holographic interferometry has firmly established itself as an attractive and useful class of technique in nondestructive testing. Defects in a specimen are made apparent by the presence of anomalies in the interference fringe distribution of the deformed state of the specimen. The presence of flaws such as voids, disbonds, delaminations, and cracks weakens the strength of the specimen. The resulting strain concentration areas produced by the presence of flaws in the specimen are detected through their effect on the surface deformation map. The flaws in the specimen manifest themselves as distortion of the fringes, pockets of fringe concentrations, or localized discontinuities of the fringes in the full-field display of the deformation field of a test specimen in response to the applied load.

Figure 17 shows phase distribution corresponding to in-plane displacements of a notched fiber-reinforced concrete specimen subjected to a wedge-splitting test. The application is taken from the study of a fracture process zone in fiber-reinforced concrete. Another example of the application of holography in nondestructive testing is shown in Figure 18. The fringe pattern corresponds to in-plane displacements on a fingertip joint wood specimen under tension. Figure 19 shows an example of an application of holography in the tyre industry. The interferogram reveals, through the changes in the fringe pattern, defects in the tyre. The picture in Figure 20a is taken from the study of the embryonic behavior of embryos during incubation. The photograph shows a specific limb movement near the air space. The method also allows for a lively display of the hatching behavior of the chick. The point on the shell receiving blows is clearly visible in Figure 20b.

Conclusions

The aim of this article is to introduce readers to holographic techniques available for the noninvasive and whole-field investigation of the time-evolution and spatial distribution of the displacement and refractive index fields. Diverse techniques to obtain contourgrams of three-dimensional objects are also presented. The method offers strong potential in nondestructive testing applications, such as in the detection of flaws, in the conception of prototypes, in the evaluation of the performances of structural components, and in the verification of the reliability of finite-element computer codes.

See also

Holography, Techniques: Digital Holography; Overview. **Interferometry:** Overview; Phase Measurement Interferometry.

Further Reading

Erf RK (1974) *Holographic Non-Destructive Testing*. New York: Academic.

Ostrovsky YI, Butusov MM and Ostrovskaya GV (1980) *Interferometry by Holography*. Berlin: Springer-Verlag.

Ostrovsky YI, Schepinov VP and Yakovlev VV (1991) *Holographic Interferometry in Experimental Analysis*. Berlin: Springer-Verlag.

Rastogi PK (1994) *Holographic Interferometry – Principles and Methods*. Berlin: Springer-Verlag.

Schumann W and Dubas M (1979) *Holographic Interferometry*. Berlin: Springer-Verlag.

Schumann W, Zürcher JP and Cuche D (1985) *Holography and Deformation Analysis*. Berlin: Springer-Verlag.

Vest CM (1979) *Holographic Interferometry*. New York: Interscience.

Sandwich Holography and Light in Flight

N Abramson, Royal Institute of Technology,
Stockholm, Sweden

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction to Holographic Interferometry

Holography is a photographic principle that produces 3D images that are so real that it is possible to take measurements inside this image with a precision of a fraction of a thousandth of a millimeter. Contours are formed within the holographic image that, like the relief lines of a map, indicate the displacements of every point on the object surface. The method is named holographic interferometry (*see* **Holography, Techniques:** Holographic Interferometry) and it can be used to measure deformation, vibration and also, with slightly lower resolution, dimension.

In real time holography the deformed object is directly compared to the holographic image of its undeformed state. In double exposure holography the comparison is made between two holographic recordings on the same plate, while in sandwich holography the two states are recorded on two different plates that are sandwiched together for comparison.

Sandwich holography is useful in industrial environments, because it can measure much larger deformations and also compensate for unwanted movement of the object or the setup between the two exposures. Further on in the process it will produce any sign of deformation and comparison can be made at any time without referring back to original setup. However, processing of the two plates is needed before the comparison can be made and the plates have to be positioned with high accuracy.

Interferometric Sensitivity

To calculate the interferometric sensitivity let us name (A) the point from which the laser light is emitted, (B) the point behind the hologram plate from which the observation is made, and (C) the displaced point on the object surface to be measured. Draw an ellipsoid through (C) with (A) and (B) as focal points. If (C) is displaced along the surface of the ellipsoid, the path length ACB will remain unchanged and no interference fringes are formed, while a displacement normal to this surface produces maximal interference. A diagram, the holodiagram, is based on these ellipsoids and used for the making and evaluation of holograms.

The bisector to ACB will be the normal to the ellipsoids. If the path length ACB is repeatedly increased by δL a diagram like Figure 1 is formed where the separation (s) of the ellipses, and thus the interferometric sensitivity, varies over the diagram. If δL is the wavelength of the laser light, one interference fringe is formed each time an object point has moved the distance (s) because of a deformation of the object between the two exposures. The displacement (d) can be calculated:

$$d = ns \tag{1}$$

$$s = k0.5\delta L \tag{2}$$

$$k = 1/\cos\alpha \tag{3}$$

where n is number of fringes between fixed and studied point, k is constant along arcs of circles through A and B, and α is half the angle ACB.

When two slightly dissimilar patterns are placed one on top of the other, a moire pattern is formed that shows up the difference. The moire analogy to holographic interferometry is based on the fact that one fringe is formed for every ellipse that is crossed by an object point displaced between the two exposures.

If δL is the wavelength (λ) of the laser light the displacement (d) is

$$d = nk0.5\lambda \tag{4}$$

If two-wavelength holography is used to measure the 3D shape of an undisturbed object, it will be seen intersected by ellipses where the separation (s) is

$$s = k0.5\lambda_1\lambda_2/(\lambda_1 - \lambda_2) \tag{5}$$

If δL is the coherence length or the pulse length of the laser source, the object will be seen intersected by one single bright fringe, the thickness (s) of which is

$$s = k\delta L \tag{6}$$

Everything outside that ellipse will be dark during reconstruction. This phenomenon can be used either to optimize the use of a limited coherence length or to explain the results of 'light-in-flight recordings', as described later.



Figure 1 The holodiagram used for the evaluation of holograms.

The Principle of Sandwich Holography

In the following discussion on sandwich holography, we will only study the simplified example where the directions of illumination and observation are normal to the studied displacement and therefore α is equal to zero. The reflected light from an object point combined with the reference light produces a set of hyperbolas (Young's fringes) on the hologram plate.

When the object point is displaced between exposures on two different hologram plates, the hyperbolas will be positioned differently on the plates. There is a one-to-one relationship between the ellipsoids and the hyperbolas. Thus one point on the hologram plate will be crossed by one hyperbola if the corresponding object point is moved so that it crosses one of the ellipses of the holodiagram. Thus, the moire effect of the displaced hyperbolas at the hologram plate represents the moire effect of the ellipses in the object space. The interference pattern in the reconstructed object image can therefore be manipulated by moving one plate in relation to the other during reconstruction.

We have found that the simplest way to do this is to glue the two plates together separated by the glass thickness of one plate. To make the situation identical during exposure and reconstruction, the plates also have to be recorded in pairs. Thus, the first exposure can be made with one front plate and one back plate in contact in the hologram holder (Figure 2). The second exposure is made in exactly the same position with two new plates. After processing the front plate of the second exposure is glued in front of the back plate of the first exposure.

Then a reconstruction beam similar to the reference beam, is used to reconstruct the sandwich hologram. The interference fringes seen on the image of the object are manipulated by tilting the sandwich hologram, which results in an addition or subtraction of new fringes as in the following examples:

1. If the object is rotated by the small angle ϕ_1, the number of fringes can, during reconstruction, be



Figure 2 The exposures and reconstructions of a sandwich hologram.

eliminated by rotating the sandwich in the same direction by the much larger angle ϕ_2.

$$\phi_1 = \left[\frac{d}{2Ln}\right]\phi_2 \qquad [7]$$

2. If the sandwich during reconstruction is rotated around an axis perpendicular to that of the object rotation, new fringes are introduced at the angle γ, which is analogous to, but much larger than, the object rotation ϕ_1.

$$\phi_1 = \left[\frac{d}{2Ln}\right]\varphi_2 tg\gamma \qquad [8]$$

3. When the sandwich is rotated as described in (2) fringes are formed, the radius of curvature (r_2) of which are much larger than those of the bent object (r_1).

$$r_1 = \left[\frac{2Ln}{d}\right]\left[\frac{1}{\varphi_2}\right]r_2 \qquad [9]$$



Figure 3 The movements of three steel bars in relation to a frame are to be measured by the fringes of sandwich holography. However, the unwanted motion of the total set-up makes the evaluation impossible.

Examples

The object consisted of three vertical steel bars (Figure 3) that were fixed by screws at their lower end to a rigid frame that surrounded all the bars. The middle bar was also supported at the upper end. Forces were applied at the middle of the bars. The right bar is deformed away from the observer while the other two are deformed towards him. After deformation of the three objects the second pair of plates were exposed. Then all four plates were processed.

The back plate of the first exposure (B_1 in Figure 2) was repositioned in the plate holder in front of the plate of the second exposure (F_2). The two plates were bonded together to form a sandwich hologram. O_1 and O_2 represent the two positions of one object, which between the two exposures was bent at angle ϕ_1 toward the hologram. (L) is the distance between the front hologram and the object (~1 m); (L) is also the distance between the point of illumination and the object. (D) is the distance between the point source of the reference beam and the hologram plate ($D = 2L$); (d) is the thickness of one hologram plate (~1.3 mm); (n) is the refractive index of the plates (~1.5 mm).

When the two plates were properly repositioned in the plate holder, fringes were seen everywhere, both on the steel bars and on the supposedly fixed frame which apparently had made an accidental movement (Figure 3). By tilting the plate holder in different directions, the fringes on the frame could be eliminated and the hologram could be evaluated as if the frame had remained fixed (Figure 4).



Figure 4 The unwanted fringes caused by the motion of the total set-up have been eliminated by a tilt of the sandwich hologram.



Figure 5 Another tilt of the sandwich hologram reveals that the left and the right bar have been deformed in opposite directions.

The plate holder was then tilted backwards at angle ϕ_2 and horizontal fringes were found on the frame while the top of the left bar became fringe-free (Figure 5). The number of fringes on the right bar increased, proving that it had been tilted in the opposite direction. If the sandwich were instead rotated around a vertical axis at angle φ_2, a set of vertical fringes were formed on the frame, while the bars became covered by fringes, the inclination and curvature of which represent a magnified view of the deformed bars as seen in profile (Figure 6).



Figure 6 A rotation of the sandwich hologram around a vertical axis produces fringes that reveal direction of tilt and bending radius of all steel bars.

Introduction to Light-in-flight Recording by Holography

Recording of light pulses in flight have been possible since the beginning of the 1990s, using two-photon fluorescence or ultrafast Kerr cells driven by laser pulses. Very fast optical phenomena, such as refractive-index changes in laser-produced plasmas, have been recorded by holography using short illumination pulses.

In 1968, Staselko *et al.* published a method of studying the time coherence pattern of wave trains from pulsed lasers by the use of autocorrelation in which the unknown pulse is compared to itself. The method we name 'light-in-flight recording by holography' (LIF) is based on studying both the temporal and the spatial shape of pulses by correlation, which means that we study the change in shape of a pulse before and after it has passed through the transformation we want to study. For this process, we want to start with as short a pulse (or short coherence length) as possible and then compare the transformed pulse to the original pulse.

In a hologram only those parts of an object will be recorded for which the path length from the laser to the holographic plate via the object does not differ from the path length of the reference beam by more than the pulse length (or coherence length) of the laser light used for the recording. If that length is short, during reconstruction a large object will be seen intersected by an imaginary surface in the form of an ellipsoid, one of its two foci being the point from which the spherical wavefronts of illumination are emitted (spatial filter (A) in Figure 1) and the other being the point of observation (B). A spherical wavefront appears distorted into an ellipsoid if it is divergent, and into a hyperboloid if it is convergent, while a flat wavefront appears distorted into a paraboloid. The general rule is that the apparent wavefront has the shape of a mirror that focuses light from (A) to (B).

By careful planning, it is possible to optimize the geometry of the holographic setup in such a way that the utilized portions of the ellipsoids and hyperboloids can be approximated into flat surfaces. Thus, the object is seen intersected by one flat imaginary interference surface, the depth of which can be altered during reconstruction by changing the point of observation at the hologram plate.

Light of short duration, or short coherence length, can, in this way, be used in a holographic method for finding depth contours. If, however, the 3D shape of the object is known a priori, e.g., if it is a flat surface, this method can just as well be used to study the 3D shape of the illuminating wavefront. As mentioned before, the intersections of the ellipsoids can be approximated by intersections of spherical wave fronts of illumination, if the distance between object and hologram plate is long and if the flat surface is perpendicular to the line of sight.



Exposure of light-in-flight



Reconstruction of light-in-flight

Figure 7 During exposure of the light-in-flight hologram, the short pulse from the laser is used to obliquely illuminate both the object and the hologram plate. Only those parts will be recorded where path length for object light and reference light are equal.

Examples of Wavefront Studies

As an example we will describe an experiment that consists of an opaque white diffusely reflecting flat screen, that is illuminated from the left at an oblique angle, as seen in Figure 7. A mirror is fixed to the screen so that some of the light is reflected upwards. During recording of the hologram, the reference pulse is reflected by the two mirrors (M) so that it arrives at the middle of the hologram plate at the same time as the object pulse, in the form of diffuse light, arrives from the middle of the screen. As the reference pulse passes over the hologram plate from left to right, it works like a curtain shutter (focal-plane shutter) recording early object light to the left and later light to the right. This ‘light shutter’ moves across the plate with a velocity faster than light which is possible as it is just an intersection between pulsefront and plate. The difference in time of the recordings made at the two ends of the hologram plate is the time it takes for the reference pulse to move across the plate, or about 800 picoseconds. During reconstruction with a continuous laser the early arriving object light is seen through the left part of the plate, while the later arriving light is seen through its right part. If the eye, or a TV camera scans from left to right, the pulse is seen moving continuously over the object screen, with some of it reflected upwards by the mirror (Figure 8a–d). The corresponding pulse length is 100 ps (~30 mm), and to minimize pulsefront distortions the screen is perpendicular to the line of sight.

The photo in Figure 9 shows the result of another experiment. A spherical wave expands from a point source at left and moves to the right. The spherical wavefront intersects a flat observation screen consisting of a white-coated aluminum plate of 20 × 30 cm. A cylindrical lens is fixed, with its axis normal to the screen, so that it focuses the arriving light almost parallel to the screen surface. Figure 8 is a composite of several photographs taken through different parts


(a) (b) (c) (d)

Figure 8 Resulting reconstructed images of the light reflected by a mirror at about 45°. These four photos were taken during reconstruction while the camera behind the hologram plate was moved from left to right in between each of the exposures.



Figure 9 Light focused by a lens. A composite of several photos taken from different parts of the hologram plate. An image of the lens is included to make the picture clear.



Figure 10 Spheres intersected by a thin sheet of light.

of the hologram plate. The pulse length was in this case 10 ps (~3 mm).

Measuring the Shape of 3D Objects

The wavefront (pulse front) of a short pulse forms a thin sheet of light. The intersection of this sheet by a 3D body produces on its surface a thin line representing a cross-section. It is advantageous if this cross-section represents a flat surface, which will be approximately the case if the illumination and observation beams are collimated or arrive from points at large distances.

By moving the point of observation along the hologram plate from left to right, the intersecting sheet of light can be moved in depth forward or backward. Determination of fringe order number (by finding the zero fringe) no longer represents any problem because only the zero order fringe exists. Therefore, this way of contouring has great advantages, especially when the observations and calculations are made by computer. Figure 10 shows a set of spheres intersected by a thin light sheet.

The intersecting light sheet can be manipulated in yet another way, i.e., it can be rotated. If the point of observation is moved away from the plate, the right part of an object will be seen through the right part of the plate were the recording made later than at the left part. During the time interval between left and right records, the intersecting light sheet has moved so that it intersects the object further away, resulting in a tilted cross-section of the object. This way it has been possible to rotate the cross-section up to 90 degrees, so that if, for example, a face is illuminated from the front by a flat sheet of light, the reconstructed intersection will show the face in profile.

In a limited way it is also possible to produce results similar to those of LIF by using a CCD camera instead of the holographic plate. The great advantage is its compatibility with a PC, while the main disadvantage is a lower resolution.

Other Uses

Like all methods of 'gated viewing', LIF can be used to look through scattering media, e.g., to look through human tissue. By observing only the first light the influence of the later arriving scattered light is eliminated. Thus, LIF can be used as a diagnostic method based on the idea that the scattering, absorption, or refractive index of cancer is different from that of healthy tissue. Another use of LIF is to image just a thin section of a gas or liquid filled with particles. In this way it is possible to observe the distribution and velocity in a certain localization without influence of the scattering from particles in front of or behind the studied section.

Up to now we have discussed gated viewing by LIF in the laboratory using picosecond light pulses and distances of up to a few meters. Instead we could look at astronomical objects with light pulses of days (e.g., a supernova) and distances of many light years. Even in these cases we will see particles in space illuminated by ellipsoids with (A) being the supernova and (B) a telescope on Earth. While each ellipsoid in the laboratory may represent a pathlength of some nanoseconds, each ellipsoid in space might represent light years.

However, the methods we have shown here are not limited to the study of the apparent shape of spheres of light. They can also be used to study other objects moving at ultrahigh velocities. If an exploding supernova throws out particles in all directions at a rather slow velocity, it can be seen surrounded by an expanding sphere. If, instead, this sphere expanded with the speed of light (which is not possible) it would appear to us just like an ellipsoid of the holodiagram. If, however, it expanded at a very high velocity, but lower than that of light, the sphere would appear to us in the shape of an egg with its pointed end towards the observer. The velocity of expansion could, in this case, appear superluminal (higher than the speed of light). If the velocity is (v), its approaching velocity will to a first approximation appear to be the true velocity divided by $(1 - v/c)$.



Figure 11 A modified Minkowski diagram consisting of one cone of illumination (A) and one cone of observation (B). The separation in time and space between (A) and (B) could either be static as in LIF or caused by a relativistic velocity of the observer from (A) to (B).

Finally, we will show a relationship between LIF and special relativity, by looking at a modification of the 'Minkowski light cones'. Figure 11 shows a diagram where (x) and (y) represent space coordinates, while (z) represents time multiplied by (c). A sphere from a short pulse of light that expands from the point A is represented by a cone with its apex at (A). A sphere from a short observation that converges to (B) is represented by a cone with its apex at (B). Only those object points, that are positioned at the elliptic intersection of the two cones, can be seen illuminated. This ellipse is identical to one of the ellipses of the holodiagram. The distance in time and space separating (A) and (B) could be either caused by the fixed distance between source of laser light and hologram plate in holographic LIF, or by a high velocity of the observer. Thus, the Lorentz contraction in special relativity could be explained as a measuring error because the high velocity of the observer traveling from (A) to (B) causes his sphere of observation to be transformed into an ellipsoid of observation. The tilt of the elliptic intersection indicates which observations that appear to be simultaneous depending on the separation of (A) and (B) along the y-axis, both in LIF and in relativity.

See also

Holography, Techniques: Holographic Interferometry.

Further Reading

Abramson N (1971) Moiré patterns and hologram interferometry. *Nature* 231: 65–67.

Abramson N (1981, 1986) *The Making and Evaluation of Holograms*. London: Academic Press.

Abramson N (1996) *Light in Flight, or, The Holodiagram – The Columbi Egg of Optics*. USA: SPIE Press, vol. PM 27.

An W and Carlsson T (1999) Digital measurement of three-dimensional shapes using light-in-flight speckle interferometry. *Optical Engineering* 38: 1366–1370.

Dugay MA and Mattick AT (1971) Ultrahigh speed photography of picosecond light pulses and echoes. *Applied Optics* 10: 2162–2170.

Garrington S (1992) Invisible jet sheds new light. *Nature* 355: 771–772.

Giordmaine J and Rentzepis P (1967) Two-photon excitation of fluorescence by picosecond light pulses. *Applied Physics Letters* 11: 216.

Hinrichs H and Hinsch KD (1997) Light-in-flight holography for flow visualization and velocimetry in three-dimensional flows. *Optics Letters* 22: 828–830.

Malin D and Allen D (1990) Echoes of the supernova. *Sky and Telescopes* 22–25, January.

Powell R and Stetson K (1965) Interferometric analysis by wavefront reconstruction. *Journal of the Optical Society of America* 55: 1593–1598.

Spears K and Serafin J (1989) Chrono-coherent imaging for medicine. *IEEE Transactions on Medical Engineering* 36: 1210–1220.

Staselko DI, Denisyuk YN and Smirnow AG (1969) Holographic recording of the time-coherence pattern of a wave train from a pulsed laser source. *Optics and Spectroscopy* 26: 413.

IMAGING

Contents

Information Theory in Imaging
Inverse Problems and Computational Imaging
Adaptive Optics
Hyperspectral Imaging
Imaging Through Scattering Media
Infrared Imaging
Interferometric Imaging
Lidar
Multiplex Imaging
Photon Density Wave Imaging
Three-Dimensional Field Transformations
Volume Holographic Imaging
Wavefront Sensors and Control (Imaging Through Turbulence)

Information Theory in Imaging

F O Huck and C L Fales, NASA Langley Research Center, Hampton, VA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Information theory is an intuitively attractive mathematical approach for combining observation with communication, or sensing with processing. So far, however, this approach has remained largely in the realm of signal processing and transmission, as first formalized by Shannon and Wiener over 50 years ago. Recent extensions of this approach to imaging have mostly addressed the interpretation of images, without explicitly accounting for the critical limiting factors that constrain image gathering and restoration. Yet, to be useful in the characterization of imaging, information theory must account for these constraints and lead to a close correlation between predicted and actual performance. The characterization that is outlined here traces the rate of information from the scene to the observer; and it pairs this rate, first, with the theoretical minimum data rate to assess the efficiency with which information can be transmitted, and, second, with the maximum-realizable fidelity to assess the quality with which images can be restored. Further details, especially for the mathematical development of figures of merit and for the design of imaging systems, can be found in the Further Reading.

Model of Imaging

Description

Modern imaging systems usually have the following three stages, as depicted in Figure 1:

1. *Image gathering*, to capture the radiance field that is either reflected or emitted by the scene and transform this field into a digital signal;



Figure 1 Model of digital imaging systems.

2. *Signal coding*, to encode the acquired signal for the efficient transmission and/or storage of data and decode the received signal for the restoration of images. The encoding may be either lossless (without loss of information) or lossy (with some loss of information), if a higher compression is required;
3. *Image restoration*, to produce a digital representation of the scene and transform this representation into a continuous image for the observer.

Human vision may be included in this model as a fourth stage, to characterize imaging systems in terms of the information rate that the eye of the observer conveys from the displayed image to the higher levels of the brain.

These stages are similar to each other in one respect: each contains one or more transfer functions, either continuous or discrete, followed by one or more sources of noise, also either continuous or discrete. The continuous transfer function of the image-gathering device (and of the human eye) is followed by sampling that transforms the captured radiance field into a discrete signal with analog magnitudes. In most devices the photodetection mechanism conveys this signal serially into an analog-to-digital (A/D) converter to produce a digital signal. However, analog signal processing in a parallel structure, akin to that in human vision, has many advantages that are increasingly emulated by neural networks.

This model of imaging differs from the classical model of communication that Shannon and Wiener addressed in two fundamental ways:

1. *The continuous-to-discrete transformation in image gathering*. Whereas communication is constrained critically only by bandwidth and noise, image gathering is constrained also by the compromise between blurring and aliasing, due to limitations in the response of optical apertures and in the sampling density of photodetection mechanisms. This additional constraint requires the rigorous treatment of insufficiently sampled signals throughout the imaging system.
2. *The sequence of image gathering followed by signal coding*. Whereas the characterization of communication addresses the perturbations that occur at the encoder and decoder or during transmission, the characterization of imaging systems must also address the perturbations in the image-gathering process prior to coding. These additional perturbations require a clear distinction between the information rate of the encoded signal and the associated theoretical minimum data rate or, more generally, between information and entropy.

The mathematical model of imaging that is outlined here accounts for the appropriate deterministic and stochastic (random) properties of natural scenes and for the critical limiting factors that constrain the performance of imaging systems. The corresponding formulations of the figures of merit are sufficiently general to account for a wide range of radiance field properties, photodetection mechanisms, and signal processing structures. However, the illustrations emphasize: (a) the salient properties of natural scenes that dominate the captured radiance field in the visible and near-infrared region under normal daylight conditions; and (b) the photodetector arrays that are used most frequently as the photodetection mechanism of image-gathering devices.

Radiance Field

The radiance field $L(x, y; \lambda)$, reflected by natural scenes, may be modeled approximately as

$$L(x, y; \lambda) = \frac{1}{\pi} I(\lambda)\rho(\lambda)\rho(x, y) \quad [1]$$

where $I(\lambda)$ and $\rho(\lambda)$, respectively, represent the spectral irradiance and reflectance properties as a function of the wavelength λ, and $\rho(x, y)$ represents the random reflectance properties as a function of the spatial coordinates (x, y). Figure 2 illustrates a model of $\rho(x, y)$ for which the power spectral density (PSD) $\hat{\Phi}_\rho(\upsilon, \omega)$ corresponds closely to that typical of natural scenes, as given by

$$\hat{\Phi}_\rho(\upsilon, \omega) = \frac{2\pi\mu_\rho^2\sigma_\rho^2}{[1 + (2\pi\mu_\rho\zeta)^2]^{3/2}} \quad [2]$$



Figure 2 Model of reflectance $\rho(x, y)$.



Figure 3 Normalized PSD of the reflectance $\rho(x, y)$.



Figure 4 Optical geometry of image-gathering device.

where $\zeta^2 = \upsilon^2 + \omega^2$ and (υ, ω) are the spatial frequency coordinates of the Fourier-transform domain (see Figure 3). This model consists of random polygons, whose boundaries are distributed according to Poisson probability with a mean separation of μ_ρ, and whose magnitudes are distributed according to independent zero-mean Gaussian statistics of variance σ_ρ^2. The constraints associated with eqn [1] are satisfied by letting the mean reflectance $\bar{\rho} = 0.5$ and the standard deviation $\sigma_\rho \leq 0.2$.

Image Gathering



(a) Geometry (b) Sampling passband

Figure 5 Photodetector-array geometry and sampling passband.

Figure 4 depicts the basic optical geometry of an image-gathering device, in which the objective lens forms an image of the captured radiance field across the photodetector array, and the array transforms this image into a discrete signal. The sampling lattice (X, Y), which determines the resolution of this device, is formed in angular units by the separation (X_p, Y_p) of the photodetector-array apertures and the distance ℓ_p as given for one of the dimensions by

$$X = 2\tan^{-1}\frac{X_p}{2\ell_p} \approx \frac{X_p}{\ell_p}\,\text{rad} = \frac{57.3X_p}{\ell_p}\,\text{deg} \qquad [3]$$

Normally, the sampling lattice is square, as shown in Figure 5, so that $X_p = Y_p$. Then the corresponding area of the photodetector apertures is $A_p = \gamma_p^2$, and the solid angle Ω of the instantaneous field of view (IFOV) is $\Omega \approx A_p/\ell_p^2$ ster.

The sampling lattice projected onto the scene at the distance ℓ_o has the dimensions $(X_o, Y_o) \approx (X\ell_o, Y\ell_o)$. Because these dimensions represent the finest spatial detail that normally can be restored, it is convenient to measure the mean spatial detail of the scene relative to the sampling lattice, as given by $\mu = \mu_\rho(X_o Y_o)^{-1/2}$, which reduces to $\mu = \mu_\rho X_o^{-1}$ for $X = Y$. Hence, $\mu = 1$ indicates that the sampling interval is equal to the mean spatial detail.

The image-gathering process that transforms the continuous radiance field $L(x, y; \lambda)$ into the discrete signal $s(\mathbf{x}, \mathbf{y})$ may be modeled by the expression

$$s(\mathbf{x}, \mathbf{y}) = K\rho(\mathbf{x}, \mathbf{y}) * \tau(\mathbf{x}, \mathbf{y}) + n_p(\mathbf{x}, \mathbf{y}) \qquad [4]$$

where the discrete coordinates $(\mathbf{x}, \mathbf{y}) = (mX, nY)$, and the symbol $*$ denotes continuous spatial convolution. This model accounts, in the simplest form, for the reflectance-to-signal conversion gain K, the reflectance $\rho(x, y)$ of the scene, the spatial response (SR) $\tau(x, y)$ of the image-gathering device, the continuous-to-discrete transformation by the photodetector-array lattice, and the discrete noise $n_p(\mathbf{x}, \mathbf{y})$ of the photodetectors. The discrete coordinates are defined by the sampling function

$$\underline{|||} \equiv \underline{|||}(\mathbf{x}, \mathbf{y}) = XY \sum_{\mathbf{x},\mathbf{y}} \delta(x - \mathbf{x}, y - \mathbf{y}) \qquad [5]$$

where $\delta(x, y)$ is the Dirac delta function; and the gain is given by

$$K = \frac{1}{\pi} A_\ell \Omega \int I(\lambda)\rho(\lambda)r(\lambda)\mathrm{d}\lambda \qquad [6]$$

where $A_\ell = \pi D^2/4$ is the area of the objective lens with diameter D, and $r(\lambda)$ is the responsivity of the photodetectors. This gain relates the magnitude of the signal $s(\mathbf{x}, \mathbf{y})$ directly to that of the reflectance $\rho(x, y)$; and, together with the variances σ_ρ^2 and σ_p^2 of the reflectance and the photodetector noise, respectively, it also determines the rms-signal-to-rms-noise ratio (SNR) $K\sigma_\rho/\sigma_p$.

The DFT of $s(\mathbf{x}, \mathbf{y})$ is the periodic spectrum $\tilde{s}(\upsilon, \omega)$ given by

$$\tilde{s}(\upsilon, \omega) = K\hat{\rho}(\upsilon, \omega)\hat{\tau}(\upsilon, \omega) * \hat{\underline{|||}} + \tilde{n}_p(\upsilon, \omega) \qquad [7]$$

where $\hat{\rho}(\upsilon, \omega)$ is the spectrum of the reflectance, $\hat{\tau}(\upsilon, \omega)$ is the spatial frequency response (SFR) of the image-gathering device, and $\tilde{n}_p(\upsilon, \omega)$ is the spectrum of the photodetector noise. The symbol $\hat{\underline{|||}}$ is the Fourier transform of the sampling function $\underline{|||}$. It accounts for the sidebands generated by the sampling process and is given by

$$\hat{\underline{|||}} \equiv \hat{\underline{|||}}(\upsilon, \omega) = \sum_{\mathbf{v},\mathbf{w}} \delta(\upsilon - \mathbf{v}, \omega - \mathbf{w}) \qquad [8]$$

where $(\mathbf{v}, \mathbf{w}) = (m/X, n/Y)$. The corresponding sampling passband is

$$\hat{B} = \left\{(\upsilon, \omega);\ |\upsilon| < \frac{1}{2X},\ |\omega| < \frac{1}{2Y}\right\} \qquad [9]$$

The above expression for $\tilde{s}(\upsilon, \omega)$ can be rewritten more conveniently as

$$\tilde{s}(\upsilon, \omega) = K\hat{\rho}(\upsilon, \omega)\hat{\tau}(\upsilon, \omega) + \hat{n}(\upsilon, \omega) \qquad [10]$$

where

$$\hat{n}(\upsilon, \omega) = \hat{n}_{\mathrm{a}}(\upsilon, \omega) + \tilde{n}_p(\upsilon, \omega) \qquad [11]$$

is the spectrum of the total noise in the acquired signal. The first term $\hat{n}_{\mathrm{a}}(\upsilon, \omega)$ represents the aliased signal components caused by insufficient sampling, as given by

$$\hat{n}_{\mathrm{a}}(\upsilon, \omega) = K\hat{\rho}(\upsilon, \omega)\hat{\tau}(\upsilon, \omega) * \hat{\underline{|||}}_{\mathrm{s}} \qquad [12]$$

where

$$\hat{\underline{|||}}_{\mathrm{s}} \equiv \hat{\underline{|||}}_{\mathrm{s}}(\upsilon, \omega) = \sum_{\mathbf{v},\mathbf{w} \neq (0,0)} \delta(\upsilon - \mathbf{v}, \omega - \mathbf{w}) \qquad [13]$$

If, for spatial coordinates at either the scene or the photodetector array, the unit of (x, y) is meters, then the unit of (υ, ω) is cycles m^{-1}; and if, for angular coordinates centered at the objective lens, the unit of (x, y) is radians, then the unit of (υ, ω) is cycles rad^{-1}. Either way, it is convenient to normalize the sampling intervals to unity (i.e., $X = Y = 1$). Then the area of the sampling passband is $|\hat{B}| = 1$, the unit of (x, y) is samples, and the unit of (υ, ω) is cycles sample^{-1}.

The SFR $\hat{\tau}(\upsilon, \omega)$ of the image-gathering device is

$$\hat{\tau}(\upsilon, \omega) = \hat{\tau}_\ell(\upsilon, \omega)\hat{\tau}_p(\upsilon, \omega) \qquad [14]$$

where $\hat{\tau}_\ell(\upsilon, \omega)$ and $\hat{\tau}_p(\upsilon, \omega)$ are the SFRs of the objective lens and photodetector apertures, respectively. This SFR may be modeled approximately by the circularly symmetric Gaussian shape

$$\hat{\tau}(\upsilon, \omega) = \exp[-(\zeta/\zeta_{\mathrm{c}})^2] \qquad [15]$$

where, as shown in Figure 6, the optical-response index ζ_{c} controls the trade-off between the blurring that is caused by the decrease of the SFR inside the sampling passband and the aliasing that is caused by the extension of the SFR beyond this passband.

Signal Coding

Signal coding may be divided into two stages, as depicted in Figure 1. The first stage, which is represented by the digital operator $\tau_{\mathrm{e}}(\mathbf{x}, \mathbf{y})$ and the quantization noise $n_q(\mathbf{x}, \mathbf{y}; \kappa)$, accounts for manipulations of the acquired signal that seek to extract those



Figure 6 SFRs $\hat{\tau}(\upsilon, \omega)$ of the image-gathering device relative to the sampling passband $\hat{B}$ for unit sampling intervals (i.e., $X = Y = 1$).

features of the captured radiance field considered to be perceptually most significant, which usually entails some loss of information. The second stage, which is represented by the encoder, accounts for manipulations that seek to reduce redundancies in the acquired signal, without loss of information. The resultant encoded signal $s_{\mathrm{e}}(\mathbf{x}, \mathbf{y}; \kappa)$ may be expressed in the same form as eqn [4] for the acquired signal $s(\mathbf{x}, \mathbf{y})$ as

$$s_{\mathrm{e}}(\mathbf{x}, \mathbf{y}; \kappa) = s(\mathbf{x}, \mathbf{y}) \otimes \tau_{\mathrm{e}}(\mathbf{x}, \mathbf{y}) + n_q(\mathbf{x}, \mathbf{y}; \kappa) \qquad [16]$$

where the symbol $\otimes$ denotes discrete spatial convolution, and $n_q(\mathbf{x}, \mathbf{y}; \kappa)$ is the quantization noise. If the data transmission and/or storage are error-free, as is assumed here, then the signal that leaves the decoder remains identical to the signal that enters the encoder.

The DFT of $s_{\mathrm{e}}(\mathbf{x}, \mathbf{y}; \kappa)$ is the periodic spectrum $\tilde{s}_{\mathrm{e}}(\upsilon, \omega; \kappa)$ given in the same form as eqn [10] by

$$\tilde{s}_{\mathrm{e}}(\upsilon, \omega; \kappa) = K\hat{\rho}(\upsilon, \omega)\hat{\Gamma}_{\mathrm{e}}(\upsilon, \omega) + \hat{n}_{\mathrm{e}}(\upsilon, \omega; \kappa) \qquad [17]$$

where

$$\hat{\Gamma}_{\mathrm{e}}(\upsilon, \omega) = \hat{\tau}(\upsilon, \omega)\tilde{\tau}_{\mathrm{e}}(\upsilon, \omega) \qquad [18]$$

is the throughput SFR from image gathering to transmission, and

$$\hat{n}_{\mathrm{e}}(\upsilon, \omega; \kappa) = \hat{n}(\upsilon, \omega)\tilde{\tau}_{\mathrm{e}}(\upsilon, \omega) + \tilde{n}_q(\upsilon, \omega; \kappa) \qquad [19]$$

is the accumulated noise in the encoded signal. For η-bit quantization, where $\eta = \log \kappa$ and κ is the number of uniformly spaced quantization levels, $\tilde{n}_q(\upsilon, \omega; \kappa)$ may be treated (for $\eta \geq 4$) as independent Gaussian noise with the PSD

$$\tilde{\Phi}_q(\upsilon, \omega; \kappa) = \sigma_q^2 = (\sigma_{s_{\mathrm{e}}}/\kappa)^2 \qquad [20]$$

where $\sigma_{s_{\mathrm{e}}}^2$ is the variance given approximately by

$$\sigma_{s_{\mathrm{e}}}^2 \approx K^2 \int_{\hat{B}}\!\!\int \hat{\Phi}_\rho(\upsilon, \omega)|\hat{\Gamma}_{\mathrm{e}}(\upsilon, \omega)|^2 \mathrm{d}\upsilon \mathrm{d}\omega \qquad [21]$$

Image Restoration

Image restoration, as depicted in Figure 1, transforms the decoded signal $s_{\mathrm{e}}(\mathbf{x}, \mathbf{y}; \kappa)$ into the digital image $r(\bar{\mathbf{x}}, \bar{\mathbf{y}}; \kappa)$, as modeled by the expression

$$r(\bar{\mathbf{x}}, \bar{\mathbf{y}}; \kappa) = \overline{\text{III}} s_{\mathrm{e}}(\mathbf{x}, \mathbf{y}; \kappa) \otimes \Psi(\bar{\mathbf{x}}, \bar{\mathbf{y}}; \kappa) \qquad [22]$$

The operation indicated by $\overline{\text{III}} s_{\mathrm{e}}(\mathbf{x}, \mathbf{y}; \kappa)$ (called zero padding) prepares the decoded signal for image restoration with interpolation, and the operator $\Psi(\bar{\mathbf{x}}, \bar{\mathbf{y}}; \kappa)$ produces the digital image $r(\bar{\mathbf{x}}, \bar{\mathbf{y}}; \kappa)$ on the interpolation lattice $\overline{\text{III}}$ that is Z times denser than the sampling lattice $\underline{\text{III}}$. If the interpolation in the image restoration is sufficiently dense (normally, for $Z \geq 4$), then the blurring and raster effects of the image-display process are suppressed entirely. This condition leads not only to the best realizable image quality but also to the simplest expression for the continuous displayed image, as given in the same form as eqns [10] and [17] by

$$\hat{R}(\upsilon, \omega; \kappa) = \hat{\rho}(\upsilon, \omega)\hat{\Gamma}_r(\upsilon, \omega; \kappa) + \hat{n}_r(\upsilon, \omega; \kappa) \qquad [23]$$

where

$$\hat{\Gamma}_r(\upsilon, \omega; \kappa) = \hat{\tau}(\upsilon, \omega)\tilde{\tau}_{\mathrm{e}}(\upsilon, \omega)\hat{\Psi}(\upsilon, \omega; \kappa) \qquad [24]$$

is the throughput SFR from image gathering to display, and

$$\begin{aligned}\hat{n}_r(\upsilon, \omega; \kappa) &= K^{-1}\hat{n}_{\mathrm{e}}(\upsilon, \omega; \kappa)\hat{\Psi}(\upsilon, \omega; \kappa) \\ &= \hat{n}_{\mathrm{ar}}(\upsilon, \omega; \kappa) + \hat{n}_{pr}(\upsilon, \omega; \kappa) \\ &\quad + \hat{n}_{qr}(\upsilon, \omega; \kappa)\end{aligned} \qquad [25]$$

is the accumulated noise in the restored image. This noise may be expressed explicitly by substituting the noise components given above. The noise due to the granularity in image-display mediums is not accounted for here.

The Wiener filter, that minimizes the mean-square error due to the perturbations in image gathering and coding, is given by

$$\hat{\Psi}(\upsilon, \omega; \kappa) = \frac{\hat{\Phi}'_\rho(\upsilon, \omega)\hat{\Gamma}^*_{\mathrm{e}}(\upsilon, \omega)}{\hat{\Phi}'_\rho(\upsilon, \omega)|\hat{\Gamma}_{\mathrm{e}}(\upsilon, \omega)|^2 + \hat{\Phi}'_{n_{\mathrm{e}}}(\upsilon, \omega; \kappa)} \qquad [26]$$

where $\hat{\Phi}'(\upsilon, \omega) = \sigma_\rho^{-2}\hat{\Phi}_\rho(\upsilon, \omega)$ is the normalized PSD of the radiance field and

$$\begin{aligned}\hat{\Phi}'_{n_{\mathrm{e}}}(\upsilon, \omega; \kappa) = (K\sigma_\rho)^{-2}\Big[&\hat{\Phi}_n(\upsilon, \omega)|\tilde{\tau}_{\mathrm{e}}(\upsilon, \omega)|^2 \\ &+ \tilde{\Phi}_q(\upsilon, \omega; \kappa)\Big]\end{aligned}$$

is the normalized PSD of the accumulated noise in the encoded signal. If the photodetector noise is white so that the PSD $\tilde{\Phi}_p(\upsilon, \omega)$ is equal to its variance σ_p^2 and the PSD $\tilde{\Phi}_q(\upsilon, \omega; \kappa)$ is equal to its variance σ_q^2, then the PSD of the noise simplifies to

$$\hat{\Phi}'_{n_{\mathrm{e}}}(\upsilon, \omega; \kappa) = \hat{\Phi}'_{n_{\mathrm{e}}}(\upsilon, \omega) + \tilde{\Phi}'_q(\upsilon, \omega; \kappa) \qquad [27]$$

where

$$\begin{aligned}\hat{\Phi}'_{n_{\mathrm{e}}}(\upsilon, \omega) = \Big[&\hat{\Phi}'_\rho(\upsilon, \omega)|\hat{\tau}(\upsilon, \omega)|^2 * \hat{\underline{\text{III}}}_{\mathrm{s}} \\ &+ (K\sigma_\rho/\sigma_p)^{-2}\Big]|\tilde{\tau}_{\mathrm{e}}(\upsilon, \omega)|^2\end{aligned} \qquad [28]$$

and

$$\hat{\Phi}'_q(\upsilon, \omega; \kappa) = (K\sigma_\rho/\sigma_{s_{\mathrm{e}}})^{-2}\kappa^{-2} \qquad [29]$$

These simplifying conditions permit the Wiener filter given above and the figures of merit given below to be expressed as a function of the SNR $K\sigma_\rho/\sigma_p$, which can be specified without accounting explicitly for either the gain K or the variances σ_ρ^2 and σ_p^2.

Figures of Merit

Information Rate $\mathcal{H}$

The information rate $\mathcal{H}$ (in bits sample^{-1}) of the encoded signal $s_\mathrm{e}(\mathbf{x}, \mathbf{y}; \kappa)$ is defined by

$$\mathcal{H} = \mathcal{E}[\tilde{s}_\mathrm{e}(v, \omega; \kappa)] - \mathcal{E}[\tilde{s}_\mathrm{e}(v, \omega; \kappa) | \hat{\rho}(v, \omega) : (v, \omega) \in \hat{B}] \quad [30]$$

where the first term, $\mathcal{E}[\cdot]$, represents the entropy of $\tilde{s}_\mathrm{e}(v, \omega; \kappa)$ and the second term, $\mathcal{E}[\cdot|\cdot]$, represents the conditional entropy of this signal when the reflectance spectrum $\hat{\rho}(v, \omega)$ within the sampling passband $\hat{B}$ is known. For the assumptions that have been made about image gathering and coding, the conditional entropy becomes the entropy of the accumulated noise $\hat{n}_\mathrm{e}(v, \omega; \kappa)$, so that $\mathcal{H}$ simplifies to

$$\begin{aligned}\mathcal{H} &= \mathcal{E}[\tilde{s}_\mathrm{e}(v, \omega; \kappa)] - \mathcal{E}[\hat{n}(v, \omega; \kappa) : (v, \omega) \in \hat{B}] \\ &= \frac{1}{2} \int_{\hat{B}} \int \log\left[1 + \frac{\hat{\Phi}'_\rho(v, \omega) |\hat{\Gamma}_\mathrm{e}(v, \omega)|^2}{\hat{\Phi}'_{n_\mathrm{e}}(v, \omega; \kappa)}\right] \mathrm{d}v\,\mathrm{d}\omega \end{aligned} \quad [31]$$

The theoretical upper bound of $\mathcal{H}$ is Shannon's channel capacity $\mathcal{C}$ for a bandwidth-limited system, with white photodetector noise and an average power limitation (here the variance σ_ρ^2), as given by

$$\mathcal{C} = \frac{1}{2} \log\left[1 + (K\sigma_\rho/\sigma_p)^2\right] \quad [32]$$

$\mathcal{H}$ can reach $\mathcal{C}$ only when

$$\hat{\Phi}_\rho(v, \omega) = \begin{cases} \sigma_\rho^2, & (v, \omega) \in \hat{B} \\ 0, & \text{elsewhere} \end{cases}$$

$$\hat{\tau}(v, \omega) = \begin{cases} 1, & (v, \omega) \in \hat{B} \\ 0, & \text{elsewhere} \end{cases} \quad [33]$$

However, neither of these two conditions can occur in practice because both the PSD $\hat{\Phi}_\rho(v, \omega)$ of natural scenes and the SFR $\hat{\tau}(v, \omega)$ of image-gathering devices decrease gradually with increasing spatial frequency, as depicted in Figures 3 and 6, respectively. Hence, $\mathcal{H}$ can never reach $\mathcal{C}$.

Theoretical Minimum Data Rate $\mathcal{E}$

The theoretical minimum data rate $\mathcal{E}$ (also in bits sample^{-1}) that is required to convey the information rate $\mathcal{H}$ is defined by

$$\mathcal{E} = \mathcal{E}[\tilde{s}_\mathrm{e}(v, \omega; \kappa)] - \mathcal{E}[\tilde{s}_\mathrm{e}(v, \omega; \kappa) | \tilde{s}(v, \omega)] \quad [34]$$

where the second term, $\mathcal{E}[\cdot|\cdot]$ is the uncertainty of $\tilde{s}_\mathrm{e}(v, \omega; \kappa)$, when $\tilde{s}(v, \omega)$ is known. For the assumptions that have been made about the coding process, the conditional entropy becomes the entropy $\mathcal{E}[\tilde{n}_q(v, \omega; \kappa)]$ of the quantization noise, so that $\mathcal{E}$ simplifies to

$$\begin{aligned}\mathcal{E} &= \mathcal{E}[\tilde{s}_\mathrm{e}(v, \omega; \kappa)] - \mathcal{E}[\tilde{n}_q(v, \omega; \kappa)] \\ &= \frac{1}{2} \int_{\hat{B}} \int \log\left[1 + \frac{\hat{\Phi}'_\rho(v, \omega) |\hat{\Gamma}_\mathrm{e}(v, \omega)|^2 + \hat{\Phi}'_{n_\mathrm{e}}(v, \omega)}{\tilde{\Phi}'_q(v, \omega; \kappa)}\right] \mathrm{d}v\,\mathrm{d}\omega \end{aligned} \quad [35]$$

This expression for $\mathcal{E}$ represents the entropy of completely decorrelated data.

Information Efficiency $\mathcal{H}/\mathcal{E}$

The information efficiency of completely decorrelated data is defined by the ratio $\mathcal{H}/\mathcal{E}$. This ratio reaches its upper bound $\mathcal{H}/\mathcal{E} = 1$ when $\hat{\Phi}'_{n_\mathrm{e}}(v, \omega) \ll \hat{\Phi}'_\rho(v, \omega) |\hat{\Gamma}_\mathrm{e}(v, \omega)|^2$ and $\hat{\Phi}'_{n_\mathrm{e}}(v, \omega) \ll \tilde{\Phi}'_q(v, \omega; \kappa)$, because then both eqn [31] for $\mathcal{H}$ and eqn [35] for $\mathcal{E}$ reduce to the same expression

$$\mathcal{H} = \mathcal{E} = \frac{1}{2} \int_{\hat{B}} \int \log\left[1 + \frac{\hat{\Phi}'_\rho(v, \omega) |\hat{\Gamma}_\mathrm{e}(v, \omega)|^2}{\tilde{\Phi}'_q(v, \omega; \kappa)}\right] \mathrm{d}v\,\mathrm{d}\omega \quad [36]$$

This upper bound can be approached with a small loss in $\mathcal{H}$ only when the aliasing and photodetector noise are small. Hence, the electro-optical design that optimizes $\mathcal{H}$ also optimizes $\mathcal{H}/\mathcal{E}$. However, a compromise always remains between $\mathcal{H}$ and $\mathcal{H}/\mathcal{E}$ in the selection of the number of quantization levels: $\mathcal{H}$ favors fine quantization, whereas $\mathcal{H}/\mathcal{E}$ favors coarse quantization.

Maximum-Realizable Fidelity $\mathcal{F}$

The maximum-realizable fidelity $\mathcal{F}$ of the images restored with the Wiener filter $\hat{\Psi}(v, \omega; \kappa)$ can be expressed as a function of the throughput SFR $\hat{\Gamma}_r(v, \omega; \kappa)$ given by eqn [24] as

$$\mathcal{F} = \int\int \hat{\Phi}'_\rho(v, \omega) \hat{\Gamma}_r(v, \omega; \kappa)\, \mathrm{d}v\,\mathrm{d}\omega \quad [37]$$

or, equivalently, as a function of the integrand $\hat{\mathcal{H}}(\upsilon, \omega; \kappa)$ of the information rate $\mathcal{H}$ given by eqn [31] as

$$\mathcal{F} = \int\int \hat{\Phi}'_{\rho}(\upsilon, \omega)\left[1 - 2^{-\hat{\mathcal{H}}(\upsilon,\omega;\kappa)}\right] \mathrm{d}\upsilon \mathrm{d}\omega \qquad [38]$$

This relationship between fidelity and information rate can be extended to other goals. For example, the enhancement of spatial features (e.g., edges and boundaries), for robotic vision, can be accommodated by letting $\tilde{\tau}_{\mathrm{e}}(\upsilon, \omega)$ be the desired feature-enhancement filter.

Performance and Design Trade-offs

Electro-optical Design

Figure 7 presents the information rate $\mathcal{H}$ (for lossless encoding) as a function of the optical-response index ζ_{c} and the mean spatial detail μ. The information rate $\mathcal{H}$ versus ζ_{c} is given for several SNRs $K\sigma_{\rho}/\sigma_{p}$ and $\mu = 1$, and $\mathcal{H}$ versus μ is given for the three informationally optimized designs specified in Table 1.

The curves show that $\mathcal{H}$ can reach its highest possible value only when both of the following conditions are met:

1. The relationship between the SFR $\hat{\tau}(\upsilon, \omega)$ and the sampling passband $\hat{B}$ is chosen to optimize $\mathcal{H}$ for the available SNR $K\sigma_{\rho}/\sigma_{p}$. This design is said to be informationally optimized.
2. The relationship between the sampling passband $\hat{B}$ and the PSD $\hat{\Phi}_{\rho}(\upsilon, \omega)$ is chosen to optimize $\mathcal{H}$. For the PSDs $\hat{\Phi}_{\rho}(\upsilon, \omega)$ typical of natural scenes, the best match occurs when the sampling interval is near the mean spatial detail of the scene (i.e., when $\mu \approx 1$).

These conditions are consistent with those for which the information rate $\mathcal{H}$ reaches Shannon's channel capacity $\mathcal{C}$. However, blurring and aliasing constrain $\mathcal{H}$ to values that are smaller than $\mathcal{C}$ by a factor of nearly two (i.e., $\mathcal{H} \lesssim \mathcal{C}/2$). Hence, these conditions replace the role of white and band-limited signals in classical communication theory, to establish an upper bound on the information rate in imaging systems.

The above two conditions appeal intuitively when the problem of image restoration is considered:

1. The result that the SFR $\hat{\tau}(\upsilon, \omega)$ that optimizes $\mathcal{H}$ depends on the available SNR is consistent with the observation that, in one extreme, when the SNR is low, substantial blurring should be avoided because the photodetector noise would constrain the enhancement of fine spatial detail even if aliasing were negligible. In the other extreme, when the SNR is high, substantial aliasing should be avoided so that this enhancement is relieved from any constraints except those that the sampling passband inevitably imposes.

Table 1 Informationally optimized designs

Design	$K\sigma_{\rho}/\sigma_{p}$	ζ_{c}	$\mathcal{H}^{*}$
1	256	0.3	4.4
2	64	0.4	3.3
3	16	0.5	2.2

$^{*}\mu = 1$.



Figure 7 Information rate $\mathcal{H}$ versus the optical-response index ζ_{c} and the mean spatial detail μ (relative to the sampling interval). The designs are specified in Table 1, and the SFRs $\hat{\tau}(\upsilon, \omega)$ for ζ_{c} are shown in Figure 6.

2. The result that $\mathcal{H}$ reaches its highest value when the sampling interval is near the mean spatial detail of the scene is consistent with the observation that, ordinarily, it would not be possible to restore spatial detail that is finer than the sampling interval, whereas it would be possible to restore much coarser detail from fewer samples.

Information Rate and Data Rate

Figure 8 presents an information-entropy $\mathcal{H}(\mathcal{E})$ plot that characterizes the relationship between the information rate $\mathcal{H}$ of the encoded signal and the associated theoretical minimum data rate, or entropy, $\mathcal{E}$ for η-bit quantization. The encoder SFR $\hat{\tau}_e(\upsilon, \omega)$ is assumed to be unity. The plot illustrates the trade-off between $\mathcal{H}$ and $\mathcal{E}$ in the selection of the number of quantization levels for encoding the acquired signal. It shows, in particular, that the design that realizes the highest information rate $\mathcal{H}$ also enables the encoder to realize the highest information efficiency $\mathcal{H}/\mathcal{E}$. This result appeals intuitively, because the perturbations due to aliasing and photodetector noise that interfere with the image restoration can also be expected to do so with the signal decorrelation.



Figure 8 The information-entropy $\mathcal{H}(\mathcal{E})$ plot of the information rate $\mathcal{H}$ versus the associated theoretical minimum data rate $\mathcal{E}$ for η-bit quantization. The designs are specified in Table 1.

Throughput SFR

Figure 9 illustrates the SFRs $\hat{\tau}(\upsilon, \omega)$ and $\hat{\Psi}(\upsilon, \omega; \kappa)$ of the image-gathering device and Wiener filter, respectively, and of their product, the throughput SFR $\hat{\Gamma}_r(\upsilon, \omega; \kappa)$, for the three designs specified in Table 1. As the accumulated noise becomes negligible, $\hat{\Gamma}_r(\upsilon, \omega; \kappa)$ approaches the ideal SFR of the classical communication channel, which is unity inside the sampling passband and zero outside.

Information Rate, Fidelity and Robustness

The PSD $\hat{\Phi}_\rho(\upsilon, \omega)$ of a scene is seldom known when images are restored. Moreover, even if the PSD were known to be the one given by eqn [2], then the mean



(a) Image gathering (b) Wiener filter (c) Throughput

Figure 9 SFRs of image gathering, restoration, and throughput. The designs are specified in Table 1.

spatial detail μ would usually remain uncertain because it depends, not only on the properties of the scene, but also on the angular resolution and viewing distance of the image-gathering device. In practice, therefore, image restorations have to rely on estimates of the statistical properties of scenes. The tolerance of the quality of the restored image to errors in these estimates is referred to as the robustness of the image restoration.



Figure 10 Information rate $\mathcal{H}$ and maximum-realizable fidelity $\mathcal{F}$ versus the optical-response index ζ_c for two SNRs $K\sigma_\rho/\sigma_p$. $\mathcal{F}$ is given for the matched ($\langle\mu\rangle = 1$) and two mismatched Wiener restorations.

Figure 10 presents the information rate $\mathcal{H}$ and the corresponding maximum-realizable fidelity $\mathcal{F}$ for matched and mismatched Wiener restorations. These restorations represent the digital image $R(\bar{x}, \bar{y}; \kappa)$ or, equivalently, the continuous image $R(x, y; \kappa)$ displayed on a noise-free medium. The matched restorations use the correct value of μ, whereas the mismatched restorations use wrong estimates of μ. These curves reveal that the informationally optimized designs produce the highest fidelity and robustness, and that both improve with increasing $\mathcal{H}$. Moreover, these curves reveal that, ordinarily, one cannot go far wrong in Wiener restorations by assuming that the mean spatial detail is equal to the sampling interval (i.e., $\mu = 1$). This observation appeals intuitively because spatial detail that is much smaller cannot be resolved, and detail that is larger is not degraded substantially by blurring and aliasing.

Information Rate and Visual Quality

Figures 11 and 12 present Wiener restorations and their three components, as given by eqn [23], where $\rho(x, y) * \Gamma_r(x, y; \kappa)$ accounts for blurring, $n_{ar}(x, y; \kappa)$ accounts for aliasing, and $n_{pr}(x, y; \kappa)$ accounts for



(a) $R(x,y;\kappa)$
(b) $\rho(x,y) * \Gamma_r(x,y;\kappa)$
(c) $4n_{ar}(x,y;\kappa)$
(d) $4n_{pr}(x,y;\kappa)$

Figure 11 Images restored with the Wiener filter and their three components for designs 1 (top) and 3 (bottom).



(a) $R(x,y;\kappa)$ (b) $\rho(x,y) * \Gamma_r(x,y;\kappa)$ (c) $4n_{ar}(x,y;\kappa)$ (d) $4n_{pr}(x,y;\kappa)$

Figure 12 Images restored with the Wiener filter and their three components for designs 1 (top) and 3 (bottom).

photodetector noise. The contrast of the illustrations of the two noise components has been increased by a factor of four to improve their visibility. The extraneous structure that aliasing produces in the images of the resolution wedges is commonly referred to as Moiré pattern. The corresponding distortion in the images of the random polygons emerges more subtly as jagged (or staircase) edges.

The images are formed from a set of 64 × 64 samples with a $Z = 4$ interpolation and have a 4 × 4 cm format. If these images were displayed in a smaller format, then the jagged edges could not be resolved by the observer and would appear to be the result of blurring or photodetector noise instead of aliasing. Aliasing has, therefore, often been overlooked as a significant source of image degradation.

The Wiener restoration produces images in which fine spatial detail near the limit of resolution normally has a high contrast approaching that in the scene. However, these images also tend to contain visually annoying defects, due to the accumulated noise and the ringing near sharp edges (Gibbs phenomenon). Hence, it is often desirable to combine this restoration with an enhancement filter that gives the user some control over the trade-off among fidelity, sharpness and clarity.

Figure 13 presents images for which the Wiener restorations given in Figures 11 and 12 are enhanced for visual quality by suppressing some of the defects due to aliasing and ringing. This enhancement improves clarity at the cost of a small loss in sharpness. The images are produced again from 64 × 64 pixels, but they are displayed in three different formats. The smallest format, with a density of 64 pixels/cm, corresponds to a display of 256 × 256 pixels in a 4 × 4 cm area, which is typical of the images found in the prevalent digital image-processing literature. As can be observed, this small format leads to images that are indistinguishable from each other because they hide many of the distortions that larger formats clearly reveal.

In general, if the images are displayed in a format that is large enough to reveal the finest spatial detail near the limit of resolution of the imaging system, then distortions due to the perturbations in this system become also visible. When no effort is spared to reduce these distortions without a perceptual loss of resolution and sharpness, then it becomes strongly evident that the best visual quality with which images can be restored improves with increasing information rate, even after the fidelity has essentially reached its upper bound. This improvement continues until it is gradually ended by the unavoidable compromise among sharpness, aliasing, and ringing as well as by the granularity of the image display.



Figure 13 Images restored with the Wiener filter and enhanced for visual quality. The large, medium, and small formats contain 16, 32 and 64 pixels/cm, respectively.

Concluding Remarks

The performance of image-gathering devices and the human eye is constrained by the same critical limiting factors. When these factors are accounted for properly, then it emerges that the design of the image-gathering device that is optimized for the highest realizable information rate corresponds closely, under appropriate conditions, to the design of the human eye that evolution has optimized for viewing the real world. This convergence of information theory and evolution toward the same design clearly supports the extension of information theory to the characterization of imaging systems.

Numerous other information-theoretic characterizations of imaging are now emerging. However, none of these characterizations accounts for the critical limiting factors that constrain image gathering and restoration, as outlined here. Hence, it is not possible for them to address the efficiency and accuracy with which images can be conveyed. Moreover, none of these characterizations combines observation with communication, or sensing with processing, in a general formalization. Instead, each of them still deals with a particular measurement or imaging problem. Hence, the role of information theory in imaging is far from mature. Many challenges remain: to develop general formalizations, to account for physical phenomena, and to correlate predictions with measurements.

See also

Information Processing: Optical Digital Image Processing. **Modulators:** Electro-optics.

Further Reading

Fales CL, Huck FO, Alter-Gartenberg R and Rahman Z (1996) Image gathering and digital restoration. *Philosophical Transactions of the Royal Society of London* A354: 2249–2287.

Huck FO and Fales CL (2001) Characterization of image systems. *Encyclopedia of Imaging Science and Technology.* New York: John Wiley & Sons.

Huck FO, Fales CL and Rahman Z (1996) An information theory of visual communication. *Philosophical Transactions of the Royal Society of London* A354: 2193–2248.

Huck FO, Fales CL and Rahman Z (1997) *Visual Communication: An Information Theory Approach.* Boston, CA: Kluwer Academic Publishers.

Lesurf JCG (1995) *Information and Measurement.* Bristol, UK: Institute of Physics Pub.

O'Sullivan JA, Blahut RE and Snyder DL (1998) Information-theoretic image formation. *IEEE Transactions Information Theory* 44: 2094–2123.

Shannon CE (1948) A mathematical theory of communication. *Bell System Technical Journal* 27: 379–423 and 28: 623–656.

Shannon CE and Weaver W (1964) *The Mathematical Theory of Communication.* Urbana, IL: U. Illinois Press.

Wiener N (1949) *Extrapolation, Interpolation, and Smoothing of Stationary Time Series.* New York: John Wiley & Sons.

Inverse Problems and Computational Imaging

M Bertero and P Boccacci, University of Genova, Genova, Italy

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

A digital image is an array (2D image) or a cube (3D image) of quantized numbers, providing a representation of a physical object or a map of some distributed property of the object (density of matter, energy, etc.). It can be obtained by digitizing the original image (for instance, a photograph) or can be directly formed by the outputs of the imaging system (digital camera, microscope, telescope, etc.). When visualized on a suitable image display device, a digital image must provide a representation of the physical object which can be easily interpreted and analyzed. In many cases, however, this condition is not satisfied. We give two typical examples.

The first is that of an image degraded by blurring which can be introduced by defects of the optical systems (such as aberrations) or by image motion, image defocusing, etc. The representation of the object does not have the quality which should be desirable for its interpretation.

The second case is even more important and arises when the output of the imaging system is not directly related to the physical quantity to be imaged. For instance, in X-ray tomography, the output of a detector is the attenuation of an X-ray pencil crossing the body while the quantity to be imaged is the density of the body.

In the situations described above, the desired image can be obtained by solving a number of mathematical problems. If we denote f as the object, namely the target of the imaging system, and g as the image of f provided by the system, then the problems to be solved can be summarized as follows:

- develop a physical model of the system to obtain a mathematical relationship between the object f and the image g; the computation of g from a given f is usually called the solution of the direct problem;
- solve the problem of obtaining the physical quantity f from given outputs g of the system; this second step is usually called the solution of the inverse problem.

The digital image of f, obtained by solving an inverse problem, is a computed one, generated by the computer where the algorithm for the solution of the inverse problem has been implemented.

It may be convenient to formulate both the direct and the inverse problem in terms of functions rather than arrays, cubes, etc., because such a formulation allows the use of powerful tools of functional analysis for their investigation. Next, the results obtained in the continuous case can be used for understanding the features of the corresponding discrete problem. In most important applications, for instance, the relationship between f and g is linear so that, in the discrete version of the direct problem, one obtains g by applying a suitable matrix A to f while, in the discrete version of the inverse problem, one obtains f from g by solving a linear algebraic system. However, the solution of the inverse problem is not so simple and the difficulties can be understood by looking at the corresponding continuous problem.

The basic reason relies on the fact that inverse problems are ill-posed in the sense of Hadamard: the solution may not exist; even if it exists it may not be unique; and, even if it exists and is unique, it may not depend continuously on the data. The last statement means that a small perturbation of the data, such as that caused by noise or any kind of experimental error, can completely modify the solution.

Inverse problems are ill-posed because imaging systems do not transmit complete information about the physical object. Therefore, the problem is to extract the useful information contained in the data or, in mathematical terms, to look for approximate solutions which are stable against noise. This is the purpose of a mathematical theory introduced in its general form by the Russian mathematician, Tikhonov and known as regularization theory.

We illustrate the general framework outlined above by means of a specific example – image deconvolution, also known as image deblurring, image restoration, etc. The object f is the image which should be recorded in the absence of degradation, while g is the image corrupted by aberrations or other causes of blurring. Both f and g are functions of 2D (or 3D) space variables $\mathbf{x}$ which are the coordinates of a point in the image domain. If the imaging system is isoplanatic, then it is described by a space-invariant point spread function (PSF) $K(\mathbf{x})$, which is the image of a point source located in the center of the image domain. The PSF provides the response of the system to any point source wherever it is located. On the other hand, its Fourier transform, the transfer function $\hat{K}(\omega)$ (the hat denotes Fourier transform and ω, the spatial frequencies associated to the space variables $\mathbf{x}$), tells us how a signal of a fixed frequency is propagated through the linear system, so that the blurring can also be viewed as a sort of frequency filtering.

Under these assumptions the image g is the convolution product of object f and PSF K:

$$g(\mathbf{x}) = \int K(\mathbf{x} - \mathbf{x}')f(\mathbf{x}')\mathrm{d}\mathbf{x}' \qquad [1]$$

and the solution of the direct problem is just the computation of a convolution product.

The image g, as given by eqn [1], is the so-called noise-free image. The actually recorded image g_r is affected by a noise term and, in general, it can be written in the following form:

$$g_r(\mathbf{x}) = g(\mathbf{x}) + n(\mathbf{x}) \qquad [2]$$

where $n(\mathbf{x})$ is a function describing noise contamination. It is a random function and, therefore, it is unknown even if one understands its statistical properties. We point out that eqn [2] does not imply that the noise is additive or signal independent. For instance, in microscopy and astronomy, the contamination of the image is due both to photon noise, which satisfies Poisson statistics, and read-out noise, which is basically Gaussian and white. Therefore the noise term in eqn [2] must only be intended as the difference between the noisy and the noise-free image.

In a first attempt at approaching the inverse problem, it seems quite natural to ignore the noise term $n(\mathbf{x})$ and to solve eqn [1] for $f(\mathbf{x})$ with $g(\mathbf{x})$ replaced by $g_r(\mathbf{x})$. Then, by taking the Fourier transform of both sides of this equation and using the well-known convolution theorem, one finds the following relationship:

$$\hat{g}_r(\omega) = \hat{K}(\omega)\hat{f}(\omega) \qquad [3]$$

which relates the Fourier transform of f and g to the transfer function of the imaging system.

The solution of this equation looks elementary. However, a first problem is due to the fact that an optical system is generally band-limited; its band Ω is the bounded domain of spatial frequencies where the transfer function is different from zero. Since the noise is not band-limited or, at least, has a band much broader than that of the optical system, outside Ω the right-hand side of eqn [3] is zero while the left-hand side is not; in other words, the solution of the deconvolution problem, as formulated above, does not exist because no object f satisfies eqn [3] everywhere. In this particular case, one can circumvent the problem by applying a suitable filter to $g_r(\mathbf{x})$, in order to suppress the out-of-band noise.

The second problem is the nonuniqueness of the solution of the problem with the filtered data. This is due to the so-called invisible objects, namely objects whose Fourier transform is zero on Ω, so that the corresponding images are exactly zero. If we find a solution of the deconvolution problem, by adding an arbitrary invisible object to this solution, we find another solution of the same problem. A well-defined solution can be obtained by requiring its Fourier transform to be zero outside Ω. In other words, we set to zero what is not transmitted by the imaging system.

The standard way for approaching the previous questions is to look for solutions in the least-squares sense, namely for objects which minimize the functional:

$$\varepsilon^2(f) = \|K * f - g_r\|^2 \qquad [4]$$

where $*$ denotes the convolution product, as defined in eqn [1], and the right-hand side is the square of the L^2-norm (which can also be interpreted as energy) of the discrepancy between the recorded image g_r and the computed image $K * f$. If one looks for a least-squares solution with minimal energy then one automatically re-obtains the solution discussed above, namely an object whose Fourier transform in Ω is given by

$$\hat{f}_{\mathrm{inv}}(\omega) = \frac{\hat{g}_r(\omega)}{\hat{K}(\omega)} \qquad [5]$$

and is zero outside Ω. Such a solution is that provided by the so-called inverse filter.

However, there is an additional difficulty in that the transfer function usually tends to zero at the boundary of the band while the Fourier transform of the noise, hence that of g_r, does not, or tends to zero in a different way. It follows that $\hat{f}_{\mathrm{inv}}(\omega)$ is divergent or very large at the boundary of the band. We conclude that its inverse Fourier transform does not exist or, if it exists, is affected by large artifacts due to noise propagation. The latter is the typical situation in the case of digital images. In Figure 1 we give the result of a numerical simulation showing the typical effect produced by the inverse filter. The object is a beautiful picture of a galaxy recorded by the Hubble Space Telescope (HST), while the PSF is a computed one describing the blurring of HST before installation of the optics correction. The blurred image is obtained by convolving the object with the PSF and by adding white noise. The restored image produced by the inverse filter is completely corrupted by noise.



Figure 1 Illustrating the effect of the inverse filter: (a) Image of the Circinus galaxy taken on 10 April 1999, with the Wide Field Planetary Camera 2 of the Hubble Space Telescope; (b) the PSF used for blurring the RGB components of the image (here shown in red); (c) the blurred image obtained by convolving the components of the image in (a) with the corresponding PSFs and adding noise; (d) the restoration obtained by applying the inverse filter to the three components of (c). Part (a) courtesy of NASA/Space Telescope Science Institute.

The inverse filter provides a solution which fits the data in the best possible way and therefore also fits the noise in the frequency domains where the signal is weakly transmitted by the imaging system. This can be achieved at the cost of an energy (L^2-norm) of the solution which is too large. Therefore, such a conclusion suggests that one must search for a reasonable compromise between data fitting and energy of the solution. This is the basic idea of regularization theory, at least in its most simple form. The mathematical formulation is obtained by looking for objects which minimize the functional:

$$\Phi_{\mu}(f) = \|K * f - g_r\|^2 + \mu\|f\|^2 \qquad [6]$$

where μ, the so-called regularization parameter, is a parameter controlling the trade-off between data fitting and energy of the solution: when μ is small, the data fitting is good and the energy is large while, when μ is large, the data fitting is poor and the energy is small.

For a given μ, the function f_{μ}, which minimizes the functional of eqn [6] is called the regularized solution of the problem. It is easy to show that its Fourier transform is given by

$$\hat{f}_{\mu}(\omega) = \frac{\hat{K}^{*}(\omega)}{|\hat{K}(\omega)|^2 + \mu}\hat{g}_r(\omega) \qquad [7]$$

The regularized solutions form a one-parameter family of functions. When μ is small these functions are strongly contaminated by noise whose effect is gradually reduced when μ increases. For too large values of μ, one re-obtains blurred versions of the original object.

Such behavior is illustrated by the sequence of regularized solutions given in Figure 2 and corresponding to the example of Figure 1. The regularization parameter increases starting from left to right and from top to bottom. Its values are $\mu = 0$ (inverse filter), 0.001, 0.01, 0.05, 0.1, and 0.5 (the noise is of the order of a few percent and the PSF is normalized in such a way that the sum of all its value is 1). The sequence makes evident the well-established theoretical result of the existence of an optimal value of the regularization parameter. Such an optimal value can



Figure 2 Illustrating the effect of the regularization parameter. The blurred image is that shown in Figure 1c. The sequence is obtained by increasing the value of the regularization parameter: (a) $\mu = 0$ (inverse filter); (b) $\mu = 0.001$; (c) $\mu = 0.01$; (d) $\mu = 0.05$; (e) $\mu = 0.1$; (f) $\mu = 0.5$. It is evident that the best restoration is that shown in (c).

be determined in the case of numerical simulations as that represented in Figure 2. However, its estimation in the case of real images is more difficult. Several methods for the selection of μ have been proposed. We only mention the so-called discrepancy principle. It consists of determining the value of μ, such that the value of the discrepancy functional at f_μ, $\varepsilon^2(f_\mu)$ coincides with an estimate of the energy of the noise. In other words, the data are fitted with an accuracy comparable with their uncertainty.

As shown by eqn [7], the regularized solution has the same band Ω of the imaging system, because $\hat{K}^*(\omega)$ is zero outside Ω. As is known, a band-limited function can be represented in terms of its samples taken at a rate which is roughly proportional to the size of the band. This is the content of the famous Shannon sampling theorem (more precisely its 2D extension). On the other hand, the sampling distance can be taken as a measure of the resolution provided by the restored image so that one concludes that the restoration method discussed above does not produce an improvement of the resolution of the imaging system. It certainly produces an improvement of the quality of the image which makes possible a visual verification of that resolution.

In many circumstances, the term super-resolution is used for describing methods which allow an improvement of resolution beyond the limit provided by the sampling theorem. Therefore, a super-resolving method must produce a restored image with a band broader than that of the imaging system. Therefore, super-resolution is related to the problem of out-of-band extrapolation.

Such an approach was already proposed in the 1960s, when it was observed that the Fourier transform of an object with a finite spatial extent (all objects have this property) is analytic; then the theorem of unique analytic continuation implies that the Fourier transform of the object can be determined everywhere from its values on the band of the imaging system.

Unfortunately this problem is ill-posed, so that out-of-band extrapolation is not feasible in practice. Only recently it has been recognized that a considerable amount of super-resolution is possible when the spatial extent of the object is not much greater than the resolution distance of the instrument. For example, super-resolving methods could be used for detecting unresolved binary star in astronomical images.

The important point is that a super-resolving method must implement explicitly the finite extent of the object: the domain of the object must be estimated and the method must search for a solution which is zero outside this domain. This introduces an important question in object restoration and, more generally, in the theory of inverse problems, namely the design of regularized solutions satisfying additional conditions (constraints). This question is also important from the theoretical point of view: the problem is ill-posed because of insufficient information on the object as transmitted by the imaging system; the use of additional constraints reduces the class of the solutions which are compatible with the data and therefore can improve the restoration. This is the use of a priori information in the solution of inverse problems.

A constraint which has been widely investigated and used is the positivity of the solution, i.e., all the values of the restored image must be positive or zero. The physical meaning of the constraint is obvious. Its beneficial effect is to reduce ringing artifacts which affect the regularized solutions previously discussed, in cases where the object contains bright spots over a black background or sharp intensity variations from zero to some positive value. The ringing is essentially related to the well-known Gibbs effect in the truncation of the Fourier series.

The requirement of positivity is the requirement of a particular lower bound on the values of the solution. Therefore, one can consider more general constraints in requiring a given lower and/or upper bound on the values of the solution, eventually combined with a constraint on the domain to produce, for instance, a super-resolved positive solution. The most general form of these constraints requires that the solution belongs to a given closed and convex set $\mathcal{C}$ in some functional space. A general method producing regularized solutions in a convex set is an iterative method which is essentially a gradient method for the minimization of the least-squares functional, with a projection on the set $\mathcal{C}$ at each iteration. In the case of object deconvolution, the least-squares functional is that given in eqn [4] and the method has the following form: if f_k is the result of the k-th iteration, then f_{k+1} is given by

$$f_{k+1} = P_{\mathcal{C}}[f_k + \tau K^{\mathrm{T}} * (g_r - K * f_k)] \tag{8}$$

where $P_{\mathcal{C}}$ is the convex projection onto the set $\mathcal{C}$, τ is a relaxation parameter and $K^{\mathrm{T}}(\mathbf{x}) = K(-x)$. In general, the algorithm, known as the projected Landweber method, is initialized with $f_0 = 0$. An important property is that it has a regularization effect, in the sense that iterations must not be pushed to convergence but stopped after a suitable number of iterations to avoid strong noise contamination. In Figure 3 we compare, in a specific example, the result obtained by means of the linear regularization method and that obtained by means of the projected iterative method with a lower and upper bound on the solution. The reduction of ringing is evident.

Among the methods producing positive solutions we must mention the most popular one in astronomy, the so-called Richardson–Lucy method, which is an iterative method for Maximum-Likelihood estimation. If the PSF has been normalized in such a way that the sum of all its values is one, it takes the following form:

$$f_{k+1} = f_k\left(K^{\mathrm{T}} * \frac{g_r}{K * f_k}\right) \tag{9}$$

The method is normally initialized with a uniform image and it must not be pushed to convergence to avoid noise amplification. Another algorithm suggested by statistical arguments and producing positive solution is the so-called Maximum Entropy Method (MEM).

The image restoration methods described above have wide applications both in microscopy and



Figure 3 Illustrating the effect of constraints on image restoration: (a) Image of the Earth taken during the Apollo 11 mission; (b) blurred image of (a) obtained by assuming out-of-focus blur and adding noise; (c) optimal restoration provided by the regularization method; the ringing around the boundary of the Earth is evident; (d) optimal restoration obtained by means of the projected Landweber method with a lower and an upper bound on the solution at each iteration. Part (a) courtesy of NASA.

astronomy. For instance, the minimization of the functional eqn [6], with the additional constraint of positivity, has been used for deconvolving images in microscopy to reduce the effect of the missing cone. On the other hand, the Richardson–Lucy method was widely used for deconvolving the images of HST before installation of corrective optics.

Nowadays, image deconvolution is becoming more important for the ground-based telescopes equipped with adaptive optics. Indeed, even if adaptive optics is able to provide a considerable compensation of the atmospheric blur, a further improvement can be obtained by deconvolving the detected images. The PSF is provided by the image of a suitable guide star.

Finally, it is worth mentioning the Large Binocular Telescope, in construction on the Mount Graham in Arizona, because this instrument requires image restoration methods for a full exploitation of its imaging properties. The telescope (Figure 4) consists of two 8 m mirrors on a common mount: both mirrors are equipped with adaptive optics and are combined interferometrically to reach the resolution



Figure 4 Picture of the Large Binocular Telescope (LBT) in construction on the Mount Graham in Arizona. It consists of two mirrors on the same mount. The images of the two mirrors are combined interferometrically to produce a high-resolution image in the direction of the line joining the centers of the mirrors (baseline).

of a 22.8 m mirror in the direction of the baseline. The telescope can be rotated to record images of the same astronomical target with different orientations of the baseline, i.e., the line joining the centers of the two mirrors. Finally the images must be processed by means of multiple images deconvolution methods to obtain a unique high-resolution image, equivalent to that produced by a 22.8 m mirror.

The applications of inverse problems with major social impact are in the area of medical imaging. The spectacular success of X-ray computerized tomography (CT), invented by GH Hounsfield at the beginning of the 1970s, has stimulated the development of other imaging modalities, based essentially on the same principle, such as positron emission tomography (PET) and single photon emission computerized tomography (SPECT). Computed images are also provided by magnetic resonance imaging (MRI). In such a case, however, the computational problem is rather simple since it consists essentially in Fourier transform inversion.

The basic principle of X-ray CT is described as a finely collimated source S (see Figure 5a) emitting a pencil of X-rays which propagates through the body along a straight line L up to a well collimated receiver R. If we know both the intensity I_0 of the source and the intensity I detected by the receiver, the logarithm of the ratio I_0/I is the integral of the linear attenuation function (roughly proportional to the density function of the body) along the line L. If the source and the receiver are moved along two parallel lines, having direction θ and defining the plane Π (in practice a planar slice of the body under consideration), one obtains the integrals of the linear attenuation function $f(\mathbf{x})$ along all parallel lines orthogonal to θ. The scanning variables in the plane Π are defined in Figure 5b: φ is the angle formed by the unit vector θ with the x-axis and s is the signed distance between the origin and the integration line L. The integrals along all parallel lines orthogonal to θ define a function of s which is called the projection of $f(\mathbf{x})$ in the direction θ:

$$P_\theta(s) = \int_{-\infty}^{+\infty} f(s \cos\varphi - u \sin\varphi, s \sin\varphi + u \cos\varphi)\mathrm{d}u \tag*{[10]}$$

The set of the projections of $f(\mathbf{x})$ for all possible θ is called the Radon transform of $f(\mathbf{x})$, in honor of the mathematician Johann Radon, who first investigated the problem of recovering a function of two variables from its line integrals. Today, such a problem is known as Radon transform inversion or object restoration from projections. Sampled values of the Radon transform, i.e., sampled values of the projections for a number of possible directions between 0 and π, are the outputs of the acquisition system of the medical equipment known as CT-scanners (Figure 6). Their data-processing system contains the implementation of an algorithm for Radon transform inversion and the final result is a set of computed images providing maps of slices of the human body.



Figure 5 (a) Scheme of the scanning procedure in X-ray tomography: the source(S)–receiver(R) pair is moved along a direction θ orthogonal to the line S–R, defining the plane Π to be imaged; when the scanning has been completed the system is rotated by a certain angle, the scanning procedure is repeated, and so on. (Reproduced with permission from Bertero M and Boccacci P (1998) *Introduction to Inverse Problems in Imaging*. Bristol, UK: IOP Publishing.) (b) Definition of the variables used in the representation of the Radon transform; φ is the angle formed by the S–R line with the x_1-axis; s is the signed distance between the origin and the integration line (orthogonal to θ); and u is the coordinate on the integration line.

The plot of the Radon transform of f in the (s, φ)-plane, obtained by representing its values as gray levels, is called the sinogram of f. In Figure 7, we give the image of the sinogram of a brain slice. The horizontal rows provide representations of the projections of the phantom. In the image, the angle φ defining the direction θ takes values between 0 and 2π

while the variable s takes values between $-a$ and a, if a is the radius of a disc containing the phantom. As is evident, the sinogram is symmetric with respect to the point $(0, \pi)$. Each point in the rectangle corresponds to a straight line crossing the phantom and the straight lines through a fixed point of the phantom describe a sinusoidal curve in the (s, φ)-plane. This property has given rise to the name sinogram.

The sinogram is, in a sense, the image of the body slice under investigation, as provided directly by a CT-scanner. However, an inspection of this image does not easily provide information about the body. Therefore, it must be processed to obtain a more significant image. Radon transform inversion is an example of inverse and ill-posed problem and its solution must be treated with extra care.

The crucial point in Radon transform inversion is the Fourier slice theorem, whose content is the following: the Fourier transform of the projection in the direction θ of the function f, is the Fourier transform of f on the straight line passing through the origin and having direction θ:

$$\hat{P}_\theta(\omega) = \hat{f}(\omega\theta) \qquad [11]$$

This theorem clarifies the information content of CT data: each projection provides the Fourier transform of the function f along a well-defined straight line in the plane of the spatial frequencies. It is also the starting point for deriving the basic algorithm of data inversion in tomography, the filtered back-projection (FBP). It is obtained from Fourier transform inversion in polar coordinates and is a two-step algorithm: the first step is a filtering of the projections by means of a ramp-filter; the second is the back-projection of the filtered sinogram. More precisely the two steps are as follows:

- *Filtering*: for each θ the projection $P_\theta(s)$ is replaced by a filtered projection given by

  $$Q_\theta(s) = \int_{-\infty}^{+\infty} |\omega| \hat{P}_\theta(\omega) e^{i\omega s}\, d\omega \qquad [12]$$

  where the multiplication by the ramp filter $|\omega|$ derives from the Jacobian of polar coordinates;
- *Back-projection*: this operation is the dual of the projection operation: indeed the projection assigns to a straight line L with coordinates (s, φ), hence to a point of the domain of definition of the Radon transform, the integral of f along L; on the other hand, the back-projection assigns the value of the Radon transform at (s, φ) to all points of the straight line L with the same coordinates (a pictorial representation of projection and back-projection is given in Figure 8); as a consequence the back-projection operator $R^\#$ assigns to each



Figure 6 Picture of a scanner for X-ray tomography. The annular part contains the acquisition and scanning systems.



(a) (b)

Figure 7 (a) Picture of a brain slice; (b) the corresponding sinogram. As explained in the text, the sinogram is a gray-level representation of the Radon transform in the s, φ plane. Each horizontal line in (b) corresponds to a projection of (a).



Figure 8 (a) The effect of the projection operation is shown by drawing the projections of a circular phantom corresponding to three directions. (b) shows the result obtained by applying the back-projection operation to the three projections given in (a). It is evident that the picture provided by this operation has a maximum on the domain of the circular phantom.

point **x** the sum (integral) of all values of the Radon transform corresponding to straight lines passing through **x**:

$$R^{\#}P_{\theta}(\mathbf{x}) = \int_0^{2\pi} P_{\theta}(x\cos\varphi + y\sin\varphi)\mathrm{d}\varphi \qquad [13]$$

The back-projection operator, when applied directly to the projections as in eqn [13], provides a blurred image of f; in order to get a satisfactory restoration it must be applied to the filtered projections $Q_{\theta}(s)$. This point is illustrated in Figure 9.

We point out that the ramp filter introduced in eqn [12] amplifies the high frequency components of the projections hence the noise corrupting these components. This remark clarifies that Radon transform inversion is an ill-posed problem and requires some kind of regularization. This is obtained by introducing an additional low-pass filter which reduces the effect of the high frequencies. The most frequently used combination of ramp and low-pass filter is the so-called Shepp–Logan filter.

X-ray tomography is also called transmission computerized tomography (TCT) because the image is obtained by detecting the X-rays transmitted by the body. It provides information about anatomical details of human organs because the map of the linear attenuation function is essentially the map of the density of the tissues.

A different type of information is obtained by the so-called emission computerized tomography (ECT) which is based on the administration of radio-nuclide-labeled agents known as radio-pharmaceuticals. Their distribution in the body of the patient depends on factors such as blood flow, metabolic processes, etc. Then a map of this distribution is obtained by detecting the γ-rays produced by the decay of the radio-nuclides. Therefore, ECT yields functional information, in the sense that the images produced by ECT show the function of the tissues of the organs.



Figure 9 Illustrating the effect of the filtered back-projection. Shown here is: a slice of the so-called Shepp–Logan phantom; the corresponding sinogram (indicated by the arrow CT scanner); the filtered sinogram (indicated by the arrow filtering; the restorations obtained by applying the back-projection operation both to the original sinogram and to the filtered sinogram.

Two different modalities of ECT are usually considered:

- single photon emission computerized tomography (SPECT), which makes use of radio-isotopes where a single γ-ray is emitted per nuclear disintegration;
- positron emission tomography (PET), which makes use of β^+-emitters, where the final result of a nuclear disintegration is a pair of γ-rays, propagating in opposite directions, produced by the annihilation of the emitted positron in the tissues.

In both cases it is necessary to detect the γ-rays coming from well-defined regions of the body and, to this purpose, different methods are used in each case.

In SPECT, the discrimination of the γ-rays is obtained by means of a collimator, consisting of holes in a large lead slab covering the crystal detector face. In PET the collimation is obtained by means of pairs of detectors in coincidence. This technique, which is also called electronic collimation, is more accurate than the physical collimation used in SPECT and allows the design of systems with a great efficiency.

The basic reconstruction method in TCT, namely FBP, is often used in the reconstruction of SPECT and PET data. However, several corrections are necessary in practice. The principal ones are due to the collimator blur and to the scattering of photons in the body. If one develops a more accurate model of data acquisition by taking into account these effects, then the restoration problem implies the inversion of a very large matrix which is sparse and ill-conditioned. To this purpose iterative regularization methods are used such that the basic operation required at each step is matrix-vector multiplication. Other imaging modalities, which have been proposed for medical applications, are electrical impedance and microwave tomography. The underlying inverse problems are basically nonlinear so that the computational cost of the methods for their solution is, in general, too high for clinical applications. However the research in these areas is very active and, therefore, the situation could be improved in the near future.

See also

Tomography: Tomography and Optical Imaging.

Further Reading

Bertero M (1989) Linear inverse and ill-posed problems. In: Hawkes PW (ed.) *Advances in Electronics and Electron Physics*. vol. 75, pp. 1–120. New York: Academic Press.

Bertero M and Boccacci P (1998) *Introduction to Inverse Problems in Imaging*. Bristol, UK: IOP Publishing.

Bertero M and De Mol C (1996) Super-resolution by data inversion. In: Wolf E (ed.) *Progress in Optics*. vol. XXXVI, pp. 129–178. Amsterdam, Elsevier.

Engl HW, Hanke M and Neubauer A (1996) *Regularization of Inverse Problems*. Dordrecht, Germany: Kluwer.

Groetsch CW (1993) *Inverse Problems in Mathematical Sciences*. Braunsschweig, Germany: Vieweg.

Herman GT (ed.) (1979) *Image Reconstruction from Projections*. Berlin: Springer.

Herman GT (1980) *Image Reconstruction from Projections. The Fundamentals of Computerized Tomography.* New York: Academic Press.

Huang TS (ed.) (1975) *Picture Processing and Digital Filtering*. Berlin: Springer.

Kak AC and Slaney M (1988) *Principles of Computerized Tomographic Imaging*. New York: IEEE Press.

Krestel E (ed.) (1990) *Imaging Systems for Medical Diagnostics*. Berlin: Siemens Aktiengesellschaft.

Natterer F (1986) *The Mathematics of Computerized Tomography*. New York: Wiley.

Tikhonov AN and Arsenin VY (1977) *Solutions of Ill-Posed Problems*. Washington, DC: Winston/Wiley.

Adaptive Optics

C Pernechele, Astronomical Observatory of Padova, Padova, Italy

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The image quality of a perfect optical system is ideally limited by its diffraction figure. In the real world there are many effects which degrade that physical limit, resulting in poorer image quality at the focal plane. These effects may be static (e.g., time-independent, as, for example, error in the alignment of the optical train) or dynamic (e.g., variable with time, such as optical misalignment introduced by thermo-mechanical distortion). Active and adaptive optics, the topics of this article, are technologies able to correct for the optical aberrations induced by dynamical effects.

There are a variety of causes liable for dynamical image degradation, among these time-variable optical misalignments, pointing and tracking errors (for motorized instruments), and atmospheric perturbations. In practice, both atmospheric turbulence and misaligned instrument introduce random spatial and temporal perturbations on the optical beam, distorting the spherical (ideal) wavefront incoming on to the focal plane. This leads to loss of both the diffraction limited condition and image resolution. A typical situation for astronomical application is shown in Figure 1. A target (a star in this case) emits light whose wavefront, being far from the observing system, can be considered plane. When this wavefront passes through the atmosphere it is distorted with a temporal frequency of the order of hundreds of Hertz. This dynamically distorted wavefront fills the aperture of the optical system and will once more be distorted by the dynamic misalignment of the optical system itself. The final wavefront will be deformed with respect to the ideal (spherical) wavefront.


Source
Plane wavefront
Light rays
Atmosphere
Wavefront aberrated by atmospheric turbulence (high frequency)
Reference (plane) wavefront
Wavefront aberrated by atmospheric turbulence + telescope quality (high + low frequency)
Reference (spherical) wavefront
Aberrated image

Figure 1 Dynamical wavefront aberration.

Dynamic optical misalignment may depend on gravitational and thermal deformation, while pointing error may appear as very slow (drift), slow (wander), or fast (jitter) tilt of the image on the focal plane. Atmospheric perturbations are produced by air turbulence and may be natural (as in the astronomical or satellite tracking cases) or induced by the experiment itself (thermal blooming in high power laser applications). All these effects appear on very different time-scales, as shown in Figure 2. As noticeable, atmospheric turbulence introduces aberrations of all orders, at a frequency above about 1 Hz. Pointing and tracking errors introduce an image tilt with different time-scale. Gravitational effects induce mechanical deformation of the optics, mainly in astronomical applications because of the massive components (the telescope primary mirror in particular). Thermal deformation produces optical misalignment among optical components mainly resulting in defocus. Figure 2 is purely illustrative, because some effects may produce wavefront aberrations at different frequencies than indicated there. For example, drift may be faster than indicated in the figure, and thermal blooming (a thermal effect) introduces aberrations at a higher frequency, and so on.

The correction of the wavefront errors is usually made by means of devices able to change the phase wave somewhere in the light path. Though the concept for correcting aberrated wavefront at slow or high frequency is the same, for example, the use of one or more deformable elements in the optical path, the technologies developed for each area are quite



Figure 2 Wavefront aberration time-scale and associated aberrations.

different: variations at slow frequency (approximately below 0.1 Hz in Figure 2) are indicated as quasi-static errors and the techniques developed to overcome them are properly called active optics, while adaptive optics indicates the techniques to overcome the unwanted effects at high frequency (above about 1 Hz in frequency). The frequency value dividing the active from adaptive optics is not well defined and depends on the field of application and its scientific engineering communities. The important point is that a correct use of a combination of the two techniques may ultimately lead to bringing the imaging system close to its diffraction limit.

Slow Corrections: Active Optics

The analysis of the wavefront is required before its correction, and one or more deformable/movable mirrors and their control system, to operate the corrections. A typical system for low frequency correction is shown in Figure 3. A telescope contains three mirrors (M1, M2, and M3) and an instrument to detect its scientific target, usually placed on its optical axis. The dynamic deformations present in this kind of instrument are mainly third-order spherical (thermal deformation of M1), third-order astigmatism (a saddle-horse deformation of M1 due to gravity when the telescope is pointing away from the zenith), and third-order coma (due to gravitational decentering between M1 and M2). Since a telescope has a tracking system some pointing error may be present, causing motion of the image in the focal plane. The observation of an off-axis target (typically a star for astronomical applications) is made to measure the deformations of the incoming wavefront by means of a wavefront sensor (WS) system. This step is completed using some of the wavefront sensing technique described elsewhere in this encyclopedia. The WS must measure the information on the wavefront distortion with adequate spatial resolution to compensate for aberrations across the full aperture of the system. Once the wavefront distortion has been measured by the WS, the needed corrections are sent to the control system which apply the appropriate mirror deformation/movements. In the example of Figure 3 only the primary mirror (entrance pupil) is deformable and it is used for correcting spherical and astigmatism aberrations. M2 is used to compensate the decentering coma by means of lateral displacement. M3 may be tilted to correct for low-frequency pointing errors. In astronomical applications active optics is essential for telescopes with primary-mirror diameters larger than approximately four meters which cannot be manufactured rigidly at reasonable cost. Active optics requires a thin deformable or a segmented primary mirror maintained on the correct shape at every elevation. Using this method, low-frequency correction has been achieved to date in telescopes with primary mirrors of the order of ten meters.



Figure 3 A typical system for correcting low-frequency dynamical aberrations (active optics).

Fast Corrections: Adaptive Optics

It is clear that corrections at high frequency are impossible using the approach discussed above, because of the large dimensions and weight of the mirror and the low response time required. For an adaptive correction it is necessary to image a smaller system pupil in the optical train and make the active correction of the wavefront. A typical configuration is shown in Figure 4. The light from the telescope focal plane (corrected for low frequency errors by means of active optics) is collimated and a pupil is located in this beam. Behind the active mirror a beamsplitter is used to send part of the light into the WS and measure wavefront distortions. The analysis results are sent to the control system which performs the active mirror deformation for the wavefront compensation. If the WS and the control system are sufficiently fast (typically faster than the time-variations of the wavefront distortion), this system is able to produce a plane wavefront which can be focused at the diffraction limit of the system. For this reason


Deformable
mirror
(pupil)
Distorted
wavefront
Control
system
Telescope
focal plane
Wavefront
sensor
Beamsplitter
Corrected
wavefront
AO
Focal plane

Figure 4 A typical setup for correcting high-frequency dynamical aberrations (adaptive optics).

adaptive optics are often referred to as real-time system.

The seminal paper on the adaptive optics concept was written by H.W. Babcock of the Mount Wilson and Palomar observatories in 1953. Since then a great improvement has been made, especially in military and astronomical fields. In recent years, however, many applications of adaptive optics have developed in fields different from traditional ones, such as precision manufacturing by means of high-power lasers, telecommunications, aero-optics, medical physics, and ophthalmology.

We describe adaptive optics with particular reference to astronomical applications. We provide a brief description of other applications at the end of this article.

Imaging Through the Atmosphere

The optical effects of the atmospheric turbulence are due to local temperature variations that induce fluctuations in the refractive index of air. The refractive index changes depend on the air density as well as the range of the temperature variations. Air density is highest at sea level and decreases exponentially with altitude. Optical effects of turbulence decrease with the altitude of the site, the reason for locating astronomical telescopes on mountains. The effects of turbulence on a point source image are depicted in Figure 5. Hereafter we consider an ideal telescope, for example, one without need for active correction at low frequencies. We consider the source 1 (continous line). The radiation emitted by the source is a spherical wavefront that can be treated as a plane, because of the very long distance to the Earth's atmosphere.


Source 2
Source 1
Isoplanatic
angle (θ)
Atmosphere
RO
Turbulence
layer
Distorted
wavefront for
source 1
Distorted
wavefront for
source 2
H
Ideal
telescope
2.44 λ/r_0
2.44 λ/D
Short
exposure
(speckles)
2.44 λ/r_0
Long
exposure
(seeing)
Diffraction
limited
(airy disk)
2.44 λ/D
Image of
source 1
Image of
source 2

Figure 5 Imaging through the atmosphere.

In absence of wavefront distortion, the angular diameter of the image (Airy disk), is approximately 2.44 λ/D, with λ the wavelength of the observation and D the telescope aperture (the mirror diameter). In this case the image is said to be diffraction limited, and it is the best possible performance for the observation. This is the performance of a space-based ideal telescope.

In the presence of the atmosphere the incoming wavefront is distorted by the turbulence and when it reaches the telescope aperture it is no longer a plane (see in Figure 5). The so-called Fried's parameter r_0 (also called atmospheric coherence length) is the most common parameter used to quantify the distortion effects of atmospheric turbulence. It is defined as the distance over which the wavefront phase is highly correlated (in this way it provides a measure of the turbulence scale size). For an undistorted plane wave, r_0 is infinity, while for atmospheric distortion it typically varies between 5 cm (bad sites) and 20 cm (excellent sites). We depict Fried's parameter schematically in Figure 5, as bubbles of dimension r_0 in the turbulent layer (referred to as Fried's cells). r_0 is a statistical parameter, which depends on time and wavelength ($r_0 = r_0(t, \lambda^{6/5})$). Its variability with time may be considerable, sometimes changing by a factor of 2 within a few seconds. A small telescope, with a diameter less than r_0, will always operate at this diffraction limit. When the r_0 is smaller than the telescope aperture, the angular size of the image is different if we consider long- or short-time exposures. If the exposure time is very short (less than hundredths of a second) it is possible to image a structure in the focal plane (see short exposure image in Figure 5). This structure, which varies with time, is due to high-order wavefront distortions that occur within the aperture. The short exposure image is broken into a large number of speckles of diameter 2.44 λ/D, which are randomly distributed over a circular region of approximately 2.44 λ/r_0 in angular diameter. A lower-order wavefront distortion is correlated with the size of the largest disturbances produced by atmospheric turbulence (the so-called outer scale) which varies considerably (from 1 m to over 1 km). Such disturbances produce a time-dependent tilt of the overall wavefront that causes fluctuations in the angle of arrival of the light from a star and randomly displace the image. For D of the order of the Fried parameter r_0, image motion dominates, and a simple tip-tilt mirror (not just deformable) provides useful correction. For D greater than r_0, speckles dominate and a deformable mirror is necessary to account for the wavefront distortion. For long exposures the dimension of the image is determined by the ratio λ/r_0 rather than λ/D. The angular resolution is diminished due to the atmospheric turbulence (see Figure 5). For a 4 m telescope, atmospheric distortion degrades the spatial resolution by more than one order of magnitude compared to the diffraction limit, and the intensity at the center of the star image is lowered by a factor of 100 or more. Even at the best astronomical sites, ground-based telescopes observing at visible wavelengths cannot, because of atmospheric turbulence alone, achieve an angular resolution better than telescopes of about 20 cm diameter.

Most of the distortions imposed by the atmosphere are in the wave-phase and an initially plane wavefront traveling 20 km through the turbulent atmosphere accumulates, across the diameter of a large telescope, phase errors of a few micrometers.

Turbulence is distributed along the propagation path through the atmosphere, and then the wavefront errors become uncorrelated as the field angle increases. This effect is known as angular isoplanatism and is one of the major limitations to the astronomical adaptive optics. The structure becomes completely uncorrelated out of the isoplanatic angle, approximately equal to r_0/H, where H is the altitude of the turbulence layer. This decorrelation is sketched in Figure 5, where the short exposure images for objects 1 and 2 have different speckles structure.

In Earth's atmosphere significant turbulence occurs at altitudes up to 20 km, often with large peaks in the vicinity of the tropopause, at around 10 km there exist, in practice, more than one parameter H in Figure 5, one for each turbulence layer. This three-dimensional distribution of the turbulence considerably restricts the angle over which adaptive compensation is effective and leads to the design of multiconjugate adaptive optics, as we next explain.

Adaptive System Design

As stated above, an active system is composed of at least one wavefront sensor and one deformable mirror. Typically, the wavefront is corrected by making independent tip, tilt, and piston movements of the deformable mirror surface, as shown in Figure 6. As a rule of thumb, a deformable mirror used for atmospheric correction should have one actuator for each Fried's cell, such that the total number of actuators should be equal to the number of Fried's cells filling the telescope aperture, i.e., D^2/r_0^2. For instance, a near-perfect correction for an observation in visible light (0.6 μm) with an 8 m telescope placed in a good astronomical site ($r_0 = 20$ cm), would require a deformable mirror with approximately 6400 actuators in its adaptive optics system. Recalling that r_0 is strongly dependent on the wavelength (i.e., proportional to $\lambda^{6/5}$), similar performance in the infrared at 2 μm requires only 250 actuators. This is one reason why adaptive correction is easier in the infrared. A large number



Figure 6 A sketch of a deformable mirror.

of Fried's cells requires a similarly large number of subapertures in the wavefront sensor. Commonly used WSs are based on modifications of the classic Hartmann screen test or of curvature type. In the former case the adaptive device is made with individual piezoelectric actuators (see Figure 6), while in the latter the correction is achieved with a bimorph adaptive mirror, made of two bonded piezoelectric plates. With both methods, wavefront sensing is done on a reference off-axis object (Figure 3), or even on the observed object itself (Figure 4) if it is bright enough. In the former case the angular distance of the reference object must fall inside the isoplanatic angle and must be sufficiently luminous. In typical astronomical sites the isoplanatic angle at a wavelength of 0.6 μm is ~5 arcsec, while it can be ~20 arcsec at 2 μm. This is an additional reason why the adaptive optics system is most efficient in the infrared range. Correction in the visible requires a reference star approximately 25 times brighter than in the infrared. Most current astronomical systems are designed to provide diffraction-limited images in the near-infrared (1 to 2 μm) with the capability for partial correction in the visible. However, some military systems for satellite observations do provide full correction in the visible on at least 1 m class telescopes.

The control system is generally a specialized computer that calculates, from the WS measurements, the commands to send the actuators of the deformable mirror. The calculation must be performed quickly (within 0.5 to 1 ms), otherwise the state of the atmosphere may have changed making the wavefront correction inaccurate. The required computing power can exceed several hundred million operations for each command set sent to a 250 actuator deformable mirror. As in active optics systems, zonal or modal control methods are used. In zonal control, each zone or segment of the mirror is controlled independently by wavefront signals that are measured for the subaperture of that zone. In modal control, the wavefront is expressed as the best-fit linear combination of polynomial modes of the wavefront distorted by the atmospheric perturbations.

Future Development

As explained above, a convenient method for measuring the wavefront distortion is to look for an off-axis reference star (also known as natural guide star, NGS) within the isoplanatic angle. However, it is generally impossible to find a bright reference star close to an arbitrary astronomical target. Conditions are far better in the infrared than in the visible because atmospheric turbulence (and in particular its high spatial frequencies) is, for a given AO correction, less pronounced at longer wavelengths. The spatial and temporal sampling of the disturbed wavefront can be reduced, which in turn can permit the use of fainter reference stars. Coupled with the larger isoplanatic angle in the infrared, this gives a much better outlook for AO correction than in the visible.

Nevertheless, even for observations at 2.2 μm, the sky coverage achievable by this technique (equal to the probability of finding a suitable reference star in the isoplanatic patch around the chosen target) is of the order of 0.5 to 1%. It is therefore unsurprising that most scientific applications of AO have to date been limited to the study of objects which provide their own reference object. The most promising way to overcome the isoplanatic angle limitation is by the use of artificial reference stars, also referred to as laser guide stars (LGS). These are patches of light created by the back-scattering of pulsed laser light of sodium atoms in the high mesosphere or by molecules and particles located in the low stratosphere. The laser beam is focused at an altitude of about 90 km in the first case (sodium resonance) and 10 to 20 km in the second case (Rayleigh diffusion). Such an artificial reference star can be created as close to the astronomical target as desired, and a wavefront sensor measuring the scattered laser light is used to correct the wavefront aberrations on the target object.

Military laboratories have reported the successful operation of adaptive optics devices at visible wavelengths using laser guide star on both a 60 cm telescope and a 1.5 meter telescope, achieving an image resolution of 0.15 arcsec. Nevertheless, there are still physical limitations of a LGS. The first problem, focus anisoplanatism, or cone-effect, was realized long ago. Since the artificial star is created at a relatively low altitude, back-scattered light collected by the telescope forms a conical beam, which does not cross the same turbulence-layer areas as light from the astronomical target. This leads to a phase estimation error, which in principle can be solved by the simultaneous use of several laser guide stars surrounding the targeted object. A more significant problem is image motion or tilt determination. Since the paths of the outgoing and returning light rays are the same, the centroid of the artificial light appears to be stationary in the sky, while the apparent position of an astronomical source suffers lateral motions (also known as tip/tilt). The simplest solution is to supplement the AO system and LGS with a tip/tilt corrector set on a (generally) faint close NGS. Performance is then limited by poor photon statistics in the tip/tilt correction.



Figure 7 Conjugated planes of turbulent layers.

Adaptive optics with a multicolor laser probe is another concept that has been studied to solve the tilt determination problem of laser beacon based AO. Only applicable to sodium resonant scattering at 90 km, it excites different states of the sodium atoms and makes use of the slight variation in the refraction index of air with wavelength. Its main drawback is the limited returned flux, due to the saturation of mesospheric sodium layer.

The quality of a site for adaptive optics is determined not only by the median seeing, but also by the height and thickness of the turbulent layers (often only a few thin layers dominate). Some adaptive-optics systems can be adapted to correct for turbulence originating at a particular height by using several reference stars. This technique is known as multiconjugate adaptive optics (MCAO) and is still in his infancy. This concept deals with a 3-D view of the atmosphere, and for this reason it is also called turbulence tomography. Several wavefront sensors are needed for tomography. Turbulence tomography is also useful to correct for the cone effect when using LGS. When several deformable mirrors are placed on the appropriate conjugate planes, as shown in Figure 7, anisoplanatism reduces and the size of the corrected field of view increases. The situation is roughly depicted in Figure 7, where each turbulent layer (indicated as TL) has a proper conjugated plane (C-TL).

Another challenging optical solution is one of utilizing large secondary adaptive mirrors. This application seems especially interesting at thermal wavelengths, where any additional mirror raises the significant thermal background detected by instruments.

Other Adaptive Optics Applications

In recent years the adaptive optics technique has been developed in many applications beside astronomy and the military, for example, as in high-power laser welding or cutting, in ophthalmology and in aero-optics.

In high-power laser applications, thermal blooming takes place when laser light is absorbed by the gases and particles that make up the atmosphere. Since energy is conserved, the energy lost by the laser (its intensity diminishes) is gained by the atmosphere that heats up. This inhomogeneity at the boundary of the laser beam generates wavefront distortions by turbulence, as shown in Figure 8. This means that laser light that passes through the air at a later time interacts with a different atmosphere than the light that passed by earlier. The net effect is that, in the case of a Gaussian laser beam, light following a wavefront which passed at an earlier time, ‘sees’ a concave lens that deflects the successive rays out of the beam (away from the axis) causing the beam to appear to grow in radius or ‘bloom’. Adaptive optics techniques for real-time compensation of blooming in laser beams were developed in the late 1960s. Given the high coherence and monochromaticity of a laser, the technique is more straightforward than for more common white-light applications of the astronomical applications.

Density fluctuations in a compressible shear layer are sufficiently high to cause a time varying index of refraction of the layer. This situation is common in a turbulent flowfield, and the study of the wavefront aberrations induced by this flowfield, when it is of relatively short propagation length in the near-field of the optical system, is referred to as aero-optics. Turbulent flowfield induces various types of degradations in the performances of an optical system. For example the jitter and defocusing of laser-based weapons cause a reduction in the amount of energy delivered to the target. Tracking systems experience bore-site errors and imaging systems experience blurring. Recent work suggests that adaptive optics compensation may successfully overcome these problems.

In ophthalmology the adaptive technique finds application in studying the retina of the eye. In this case the eye itself produces wavefront aberration, and the retina is seen as blurred. Techniques in ophthalmic laser surgery are being developed to use adaptive optics to correct for detected distortions.


Wind generated by thermal gradient
Cool air (higher density)
Laser beam
Hot air (lower density)
Defocused laser light
Cool air (higher density)

Figure 8 Thermal blooming effect in high-power laser applications.

In the field of telecommunications, studies are in progress for using adaptive techniques in data transmission between ground-based stations and satellites.

See also

Environmental Measurements: Doppler Lidar; Optical Transmission and Scatter of the Atmosphere. **Instrumentation:** Astronomical Instrumentation; Telescopes. **Phase Control:** Wavefront Coding; Wavefront Sensors and Control (Imaging Through Turbulence).

Further Reading

Beckers JM (1993) Adaptive optics for astronomy: principles, performance and application. *ARAA* 31: 13–62.

Fried DL (1965) Statistics of a geometric representation of wavefront distortion. *JOSA* 55: 1427–1435.

Hardy JW (1998) *Adaptive Optics for Astronomical Telescopes*. New York: Oxford University Press.

Jumper EJ and Fitzgerald EJ (2001) Recent advances in aero-optics. *Progress in Aerospace Sciences* 37: 299–339.

Liang J, Williams DR and Miller DT (1997) Supernormal vision and high-resolution retinal imaging through adaptive optics. *JOSA A* 14(11): 2884–2892.

Lukin VP (1995) *Atmospheric Adaptive Optics*. Bellingham: SPIE Optical Engineering Press.

Ragazzoni R, Marchetti E and Valente G (2000) Adaptive-optics corrections available for the whole sky. *Nature* 403(6765): 54–56.

Roddier F (1999) *Adaptive Optics in Astronomy*. Cambridge: Cambridge University Press.

Roggeman M and Welsh B (1996) *Imaging Through Turbulence*. Boca Raton, FL: CRC Press.

Tyson RK (2000) *Introduction to Adaptive Optics*. Bellingham: SPIE Optical Engineering Press.

Welford W (1974) *Aberrations of the Symmetrical Optical System*. New York: Academic Press.

Wilson RW and Jenkins CR (1996) Adaptive optics for astronomy: theoretical performance and limitations. *MNRAS* 268: 39.

Hyperspectral Imaging

M L Huebschman, R A Schultz and H R Garner,
University of Texas, Dallas, TX, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Hyperspectral imaging techniques on a microscopic level have paralleled the hyperspectral remote astronomical sensing which has developed over the years. It is especially apparent in remote sensing of our own planet's land masses and atmosphere, such as in the LANDSAT satellite program. In biology, biochemistry, and medicine, hyperspectral imaging and multispectral imaging are often interchanged, although there is a distinct difference in the two techniques.

A multispectral imager produces images of each of a number of discrete but relatively wide spectral bands. Multispectral imagers employ several wide bandpass filters to collect the data for the images. A hyperspectral imager produces images over a contiguous range of spectral bands and, thus, offers the potential for spectroscopic analysis of data. Hyperspectral imagers may use gratings or interferometers to produce the contiguous range of spectral bands to record.

Fluorescent dyes (also referred to as fluorophores or fluorochromes) and recently quantum dots, as markers, are a very powerful tool for analyzing organic tissues for researchers in cytology (study of cell function), cytogenetics (study of the human chromosomes), histology (study of structure and function of tissues), microarray scanning (analysis of concentrations of multiple varied probes), and biological material science. Without the correlation of the spectral and spatial data in biological images, there would be little useful information for the researcher. Therefore, hyperspectral imaging in the biological sciences must combine imaging, spectroscopy, and fluorescent probe techniques. Such imaging requires high spatial resolution to present a true physical picture, and the spectroscopy must also have high spectral resolution in order to determine the quantities of biochemical probes present. The correlation must provide the color-position relation for identification of meaningful information.

This description will begin with an initial review of multispectral imaging to lead into a discussion of hyperspectral imaging. The discussion will examine aspects of hyperspectral imaging based on an interferometric method and on a grating dispersion method similar to the methods in multispectral imaging.

Image Parameters

The analysis of fluorophores involves the excitation of the dye with a shorter wavelength and thus higher energy than the emission spectrum. The use of the appropriate excitation wavelength will yield a maximum emission intensity at a characteristic wavelength. The quality of a fluorescent image generally combines contrast and brightness. Contrast depends on the ratio of emission intensity to that of background light. Consequently, the use of filters to block the excitation wavelength and prevent it from overwhelming the field is critical in providing high contrast for the detection of fluorophore emission. However, the use of narrow filters to restrict the background can severely limit the brightness of the fluorescent image. This is due to the barrier filters allowing only a portion of the actual emission spectrum to pass. Brightness is an intrinsic property of each individual fluorophore, but is also dependent on the ability to illuminate with the peak excitation wavelength for that fluorophore.

The balance between contrast and brightness may be further complicated by applications designed to facilitate the evaluation of multiple fluorophores. The selection of appropriate excitation and emission filters within a single set to allow for the simultaneous viewing of multiple fluorophores can be very inhibiting. Although quad-band beamsplitters are currently available, commercial advances to date have yielded only triple-pass combinations for simultaneous detection, such as one of which permits the simultaneous detection of the widely used fluorophore combination fluorescein-5-isothiocyanate (FITC), Texas Red and 4′,6-diamidino-2-phenylindole (DAPI) (e.g., Chroma Technology Corp.).

Although the capture of digital images has propelled this field, efforts to collect multicolored images as digital files also suffer from technical limitations. Color CCD cameras often utilize filters or liquid crystals to segregate the red, green, and blue wavelengths onto the imaging chip. The employment of these cameras is restricted to resolving colors as discriminated by the filters used. For scientific applications, then, the greatest sensitivity and selectivity has been achieved through black and white CCD cameras with optimized filters for a specific application. While this approach is widely used, it suffers from the inherent limits of the spectra of data that can be analyzed since it is defined by the characteristics of the optical filters employed. Thus, the system is restricted to the use of fluorophores that can be effectively resolved from each other by filters, and the filters selected limit the data collected to a portion of the total emission spectrum for any one fluorophore.

Multispectral Imaging

Multispectral imaging systems in biomedical research are composed of a microscope, filters and/or interferometer for spectral selection, a charged coupled device (CCD) camera to record the data, and computer control for acquisition, analysis, and display (Figure 1a). The introduction of CCD cameras has offered a means to document results and capture images as digital computer files. This has facilitated the analysis of results with more and more complex probe sets and has allowed the use of more sophisticated computer algorithms for data analysis. The other major component of the multispectral imaging system is a light source to excite the sample's fluorescent dyes whose emissions are selected by filters or an interferometer for recording on the CCD camera.

An example of the use of multispectral imaging is in the identification of the 24 human chromosomes. A scheme was presented for the analysis of human chromosomes by differentially labeling each chromosome with a unique combination of 5 fluorophore-labeled nucleotides (building blocks of DNA and RNA, consisting of a nitrogenous base, a five-carbon sugar, and a phosphate group). These complex probes are simultaneously hybridized to metaphase chromosomes and analyzed to determine which of the fluorophores are present. Combinations of one, two, or three of the five fluorophores are enough to distinguish a particular chromosome from the others.

An interferometric multispectral system used to perform this type of analysis is the Spectral Karyotyping (chromosome typing) or SKY System (Figure 1a). This technology does not represent hyperspectral imaging, but is presented for comparison. Illumination light passes through a triple band-pass dichroic filter which allows for the simultaneous excitation of all the fluorochromes in, for instance, Speicher's scheme. Modern multi-band pass filters add little to image distortion while effectively blocking unwanted autofluorescence or excitation illumination. The fluorescence emissions from the sample are split into two separate beams by the interferometer. The beams are then recombined with an optical path difference (OPD) between them such that the two beams are no longer in register and interfere with each other. By adjusting the OPD, a particular wavelength band can be selected for, which results in constructive interference and thus can be collected by the CCD camera pixels. After adjusting the OPD to record


Filter sets
or
Interferometer
Computer
Excitation sources
Lasers
Arc lamps
Cooled/amplified CCD camera
Epi-fluorescence microscope
(a)
Interferometer
or
Grating spectrometer
And motorized stage
Computer
Excitation sources
Lasers
Arc lamps
Cooled/amplified CCD camera
Epi-fluorescence microscope
(b)

Figure 1 The instruments for multispectral and hyperspectral imaging are similar. (a) Multispectral imagers use interferometers or bandpass filters to collect noncontiguous emission wavelengths. (b) Hyperspectral imagers employ interferometers or gratings to collect a contiguous wavelength band. Computers, microscopes, CCD cameras, and excitation light sources are common to all the techniques. The systems which use filter sets or interferometers use motorized filter placement systems or automated interferometers. The gratings systems employ a motorized stage for the sample movement. Adapted with permission from Schultz RA, Nielsen T, Zavaleta JR, Ruch R, Wyatt R and Garner HR (2001) Hyperspectral imaging: a novel approach for microscopic analysis. *Cytometry* 43: 239–247.

the 5 dye wavelengths, each pixel's 5 records are then compared to the known probe-labeling scheme to identify the corresponding chromosome material. The image of the metaphase chromosome spread can be karyotyped using specific pseudo-colors for maximal visual discrimination of the chromosomes.

Another nonhyperspectral method is the Multi-Fluorescence *In Situ* Hybridization or M-FISH System. It uses five single-band-pass excitation/emission filter sets where each filter set is specific for one of the five fluorochromes used in the combinatorial labeling process (Figure 1a). Again, five separate exposures are taken (one exposure for each filter set) and combined to create a multicolor image. Most M-FISH systems now have motorized filter set selectors which minimize any image registration shifts that may occur between exposures. For each pixel, the presence/absence of signal from each of the five fluorochromes is assessed and then matched to the probe-coding scheme to determine which chromosome material is present. As with the SKY System, an image of the metaphase spread is converted into a karyotype and specific pseudo-colors are used to maximize visual discrimination of the chromosomes.

Hyperspectral Imaging

As has been stated, the main difference between multi- and hyper-spectral imaging is the collection of a broad contiguous band of wavelengths. The apparatus and methods for hyperspectral imaging are similar to multispectral imaging (Figure 1). Instead of collecting sections of the emission spectrum using filters or interferometers, hyperspectral imaging collects a continuous emission spectrum by dispersing the wavelength of light using gratings and measuring the wavelength intensity, or by dispersing Fourier components of light using interferometers and measuring interference intensity (Figure 1b). Multispectral images are limited to measuring total intensity within the selected wavelength band. Determining the abundance of more than one dye per pixel is less accurate when only a small segment of each dyes' spectrum is passed by the emission filter. This has not been considered a limitation in the past because most research depended on just identifying the presence and not the abundance of several spectrally broad and overlapping dyes which also occupied relatively large spatial areas. With the advent of smaller and smaller featured microarrays, the desire to use more dyes in identification schemes, and the use of quantum-dot markers which can be used to indicate both genetic makeup and quantity, the limitations of multispectral imaging has led to a move to hyperspectral imaging.

In contrast to the fluorescence multispectral imaging approaches, a hyperspectral image is fully three-dimensional. Every XY spatial pixel of the image has an arbitrarily large number of wavelengths allied with it. An intensity cube of data is collected. Two of the axes of the cube are spatial and one axis is wavelength (see Figure 2). At each of the 3D points, there is an associated intensity of emitted energy. Therefore, it is a four-dimensional information space. The individual intensity signature of differing emitting bodies can then be separated to give a complete view. Spectral decomposition is a mathematical/algorithmical process by which individual emission spectra of the dyes can be uniquely separated from a composite (full spectral) image by knowing the signature of each dye emission spectra component measured separately. Spectral decomposition may be performed using standard algorithms with codes which are readily available.

Interferometric Hyperspectral Imaging

The system architecture of the interferometric hyperspectral imager resembles that of the SKY System (Figure 1). But, instead of just sequencing the interferometer to select a set of specific wavelengths to record as in the SKY System, the interferometer in the hyperspectral imager is sequenced through



Figure 2 Intensity data cube. In this data cube, each CCD exposure captures a measurement in intensity (number of counts) by wavelength for a small spatial area in *Y* and Δ*X*. Many displacements in *X* with subsequent CCD acquisitions yield a 'cube' of data in *X*, *Y*, and λ. The intensity counts may be thought of as another dimension, *I*(*x*,*y*,λ). Another form of the data cube is with each CCD acquisition comprising intensity counts for a spatial *X* and *Y* area for a small Δλ and multiple displacements in λ for each acquisition.

discrete optical path differences to record the intensity at each pixel for each OPD. Fourier spectroscopy techniques are used to transform the OPD intensities at each pixel into the wavelength intensities at each pixel. Each pixel may be thought of as a Fourier spectrometer which is not dependent on any other pixel. Then, spectral decomposition algorithms can be run to determine which dyes are present (see the next section).

Like the multifilter methods, the interferometer approach provides a real two-dimensional image that can be observed, focused, and optimized prior to measurement. But like the filtering methods, the excitation source must be filtered for sufficient contrast to view the fluorescent emissions. Interferometers have high optical throughput, relative to other methods, and can have high and variable spectral resolution. The spectral range can cover from the ultraviolet to the infrared. The high and variable spectral resolution allows the user to trade off sensitivity, spectral resolution, and acquisition time in a way that is not possible with any other technique. And interferometers do not cause polarization of light as a filter may.

However, interferometric instruments are susceptible to image registration and lateral coherence difficulties. They are limited by the extreme precision required of the optical components which results in the continuous need for monitoring and adjustment, since aberrations are not tolerated in interferometric instruments. The throughput is reduced by loss due to the beamsplitter design and from the mirrors. Additionally, the Fourier transform instrument deconvolutes based on a two-step process; the correlation of the light passed by an interferometer followed by an inverse Fourier transform in software.

To mitigate the extreme precision and sensitivity of the most interferometric systems, Sagnac interferometers have been employed because of their common path intrinsic stability. The common path compensates any misalignment, vibration, or temperature affect. The OPD is provided by the Sagnac affect. When the Sagnac interferometer is rotated, the path traveled in one direction will be different from that of the light on the common path in the other direction. Although, this interferometer method is trading one difficulty for another, it is somewhat easier to manage the rotation of a physical system than to maintain the exacting precision of mirror alignments in a standard interferometer.

Spatial Resolution

The spatial resolution of a Sagnac Hyperspectral Imager is set by the size of the pixels of the CCD camera and the microscope system magnification, since the interferometric hyperspectral viewer sees the entire field of view at once. Let the x- and y- dimensions of the CCD pixel be δx and δy, respectively, and the magnification be M, then the spatial resolutions in the x and y directions are $2\delta x/M$ and $2\delta y/M$, respectively. For CCD pixel sizes of 10 microns square, binning together two pixels in the x- and two pixels in the y- direction, and an overall magnification of 60, the x and y resolutions are both 0.66 microns.

Field of View

For N pixel rows and C pixel columns, the field of view will be $N\delta y/M$ and $C\delta x/M$ for the length of the area along the y- and x- axis, respectively. For a CCD array of 1536 columns by 1024 rows, and the parameters above, the field of view is 171 microns by 256 microns, x and y, respectively.

The sensitivity, dynamic range, and spectral response are set by the CCD camera optical components.

Spectral Resolution

Spectral resolution will depend on the ability to vary the OPD and the Fourier transform. While the interferometer is used basically as a filter in the multispectral imager to select a wavelength, in the hyperspectral imager it is used to vary the OPD for all the wavelengths whose energy is integrated at the CCD camera pixels.

The electric field, E, for emissions at one wavelength, λ, or wave number, $k = 1/\lambda$, radial frequency, ω, and amplitude, A, can be written as

$$E(k) = A(k)\,\mathrm{e}^{-\mathrm{i}(2\pi kx-\omega t)} \qquad [1]$$

and the intensity which is measured is the magnitude squared of the electric field:

$$I = E^{*}E \qquad [2]$$

Emissions from fluorescent sources are usually noncoherent and composed of a range of wavelengths, even with only one dye present. The intensity measured at a pixel is the superposition of many wave numbers. After traveling a certain OPD, L, the intensity integrated over all wave numbers may be written as

$$I_{\mathrm{pxl}}(L) = \frac{1}{2}\left[\int I(k)\mathrm{d}k + \int I(k)\cos(2\pi kL)\mathrm{d}k\right] \qquad [3]$$

or

$$I_{\mathrm{pxl}}(L) = C_0 + C_1\cdot \mathrm{Re}\{\mathrm{FT}[I(k)]\} \qquad [4]$$

where FT stands for Fourier transform.

The inverse transform is

$$\int I_{\mathrm{pxl}}(L)\,\mathrm{e}^{-\mathrm{i}2\pi k'L}\,\mathrm{d}L = C_0\int \mathrm{e}^{-\mathrm{i}2\pi k'L}\,\mathrm{d}L + C_1\int\int I(k)\mathrm{e}^{-\mathrm{i}2\pi kL'}\,\mathrm{d}k\cdot\mathrm{e}^{\mathrm{i}2\pi k'L}\,\mathrm{d}L \quad [5]$$

$$\int I_{\mathrm{pxl}}(L)\mathrm{e}^{-\mathrm{i}2\pi k'L}\,\mathrm{d}L = C_3 + C_4 I(k)$$

The integration constant, C_3, can be ignored for large wave numbers, as in the case of the visible range, since C_3 will be proportional to the inverse of the wave number. The intensity as a function of wave number is then

$$I(k) = C_5\int I_{\mathrm{pxl}}(L)\mathrm{e}^{-\mathrm{i}2\pi kL}\,\mathrm{d}L \quad [6]$$

For absolute quantitative measurements, the constant C_5 can be determined by calibration with a known emission. For discrete measurements made by changing the optical path length, then the working formula is

$$I_{\mathrm{pxl}}(k) = \sum_{L_i} I_{\mathrm{pxl}}(L_i)\mathrm{e}^{-i2\pi kL_i}\,\Delta L \quad [7]$$

This is the discrete Fourier transform which must be preformed for each pixel to determine the intensity as a function of wavelength. Per the Nyquist sampling tenets:

$$\Delta L = \frac{1}{(N/2)\Delta k} \quad \text{or} \quad \Delta k = \frac{2}{N\Delta L} \quad [8]$$

where Δk is the discrete wave number interval and N the number of different OPDs. Sagnac interferometers can make rotations which give at least a change of $\Delta L = \lambda/4$, so substituting in eqn [8]:

$$\Delta k = k_1 - k_0 = \frac{1}{\lambda_1} - \frac{1}{\lambda_0} = \frac{\Delta\lambda}{\lambda^2 + \lambda\Delta\lambda} = \frac{8}{N\lambda} \quad [9]$$

$$\frac{\Delta\lambda}{\lambda^2} \approx \frac{8}{N\lambda} \quad \text{or} \quad \frac{\Delta\lambda}{\lambda} \approx \frac{8}{N}$$

A 5% resolution in wavelength (or 20 nm at 400 nm) requires $N = 160$ and, of course, a 2.5% resolution requires $N = 360$. Therefore, about 400 OPD changes and acquisitions of the intensity fringes will give calculated resolutions of less than 10 nm in wavelength.

Analysis of the spectrum based on this resolution can be conducted to determine which dyes are present. Software techniques for displaying data will be described in the next section.

Grating-Dispersion Hyperspectral Imaging

A hyperspectral imaging microscope collects the complete visible emission spectrum from a microscope slide by using a grating spectrometer to provide the wavelength dispersion. This microscope correlates spatial and spectral information with minimal use of optical filters. A hyperspectral microscope system is composed of a standard epi-fluorescence microscope (Olympus IX70) equipped with objectives lens (including 1.25 × and 10 × Plan Fluorite, 40 × Plan Apochromat Dry, and 60 ×, and 100 × Plan Apochromat Oil), as well as a set of standard filter cubes (Chroma Technology) to allow for traditional visualization of dyes through the eyepiece. (Prototype typical components are listed in parentheses.) Multiple excitation sources can be utilized including standard 100 W mercury and xenon arc lamps, tungsten brightfield illumination, a 532 nm solid state laser (Brimrose), a helium neon laser (Uniphase), an argon ion laser (Uniphase), and a pulsed-doubled nitrogen dye laser (Laser Science, Inc.) (Figure 1b).

One side port of microscope is optically coupled to a spectrograph (Acton Research SpectraPro® 556i). A narrow entrance slit into the spectrograph allows for only one line (ΔX) of the image to be captured at a time. A 50-micron slit permits 80% of maximum throughput for the spectrometer. The spectrograph separates the polychromatic light illuminated from this single line into its light components. Normal operation uses a grating with 50 grooves/mm and a 600 nm-blaze wavelength, which allows wavelengths of approximately 400–780 nm to be measured. Different spectrograph gratings can be used for special applications from near UV to near IR. The center wavelength and grating can be shifted under computer control. The output of the spectrograph is then captured with an air/liquid-cooled CCD camera (Photometrics-Quantix) and an optional image intensifier (Video Scope International VS4-1845). The camera has a resolution of 1536 × 1024 pixels with a depth of 12 bits per pixel. The 1536 pixels are aligned in the spatial direction to allow the greatest spatial resolution. During normal operation the wavelength resolution is ‘binned’ to 128 pixels, sufficient to resolve ~8 different spectra in a single excitation scan. Higher resolution can be employed for special applications.

A line of excitation light can be provided by a line generator when laser excitation is used or by a combination of slits and cylindrical lenses when using traditional lamps or burners (mercury or xenon). This line of light illuminates the sample in the same position that maps the resulting emission light through the imaging spectrograph and onto the camera. Some advantages of illumination with a line of light include decreased sample bleaching, reduced background due to scattering, and efficient use of available excitation power. A traditional bandpass, a low-pass dichroic filter, or a linear variable filter (Raynard Corp.) may be employed to select or restrict the excitation wavelength during specific applications.

Linear Variable Filter (LVF)

The linear variable filter (LVF) (Raynard Corporation) can be used to replace the standard excitation filter cube to provide a capability for continuous excitation wavelength band selection. The LVF is $1'' \times 2.25''$ and is coated such that it continuously filters light from ~400 nm to ~800 nm along its length. Custom filters that span other wavelengths are available. The coating and therefore wavelength is uniform along a short distance, making it an ideal method for selecting an excitation wavelength band to paint across the slide, excite the slide's contents, and map the contents' emission into the slit of the imaging spectrograph. The bandwidth passed is about 21 nm wide. The LVF introduces ~50% attenuation of the intensity.

Spatial Resolution

The spatial resolution of a grating spectrograph Hyperspectral Imager is set by the size of the pixels of the CCD camera in the y- direction and the microscope system magnification. However, differing from the interferometric system, the spatial resolution in the x- direction depends on the spectrometer slit width and the microscope system magnification. As before, let the x- and y- dimensions of the CCD pixel be δx and δy, respectively, and the magnification be M. Let w_s be the slit width of the spectrometer, and note than the slit width is always going to be larger than a few δx. Then the spatial resolution in the y-direction is again $2\delta y/M$, but the spatial resolution in the x- direction is now $2w_s/M$. Again, for CCD pixel sizes of 10 microns square, binning together two pixels in the y-direction, and an overall magnification of 60, the y- resolution is 0.66 microns, as it was for the interferometer method. For a slit width of 50 microns, the x- resolution is 1.67 microns, independent of the number of pixels binned in the x-direction. The control software moves the stage the right number of steps to minimize the overlap or skipped areas. The slit width can be reduced, but at a loss of throughput or increased exposure time. The control software can compensate for different spatial resolution to display the image as 1:1.

Field of View

For N pixel rows (y- dimension) and C pixel columns (x- dimension), the field of view will be $N\delta y/M$ for the length of the area along the y-axis. If the spectrometer slit length is less than the height of the CCD, then the length is just h_s/M, where h_s is the slit length. We orient our CCD array so that the 1536-pixel dimension is along the y-axis. The y-view is thus 256 microns as in the interferometric example. To achieve the same field of view as the Sagnac method imager, we would need to take 103 stage movements and acquisitions. This highlights the difference in the two hyperspectral methods. The grating method collects the complete spectrum on each acquisition with no spectrometer adjustment but needs to step down the slide to produce the full spatial image. The interferometer method collects the complete spatial image on each acquisition with no position adjustment but needs to step the interferometer through a range of optical path differences to acquire multispectral content.

The sensitivity, dynamic range, and spectral response are set by the CCD camera optical components.

Spectral Resolution

Spectral resolution depends on spectrometer instrument function which includes the slit width, the dispersion of the grating, the CCD pixel size, and number of pixels binned together. The dispersion for normal operation was determined to be ~40 nm/mm or 0.4 nm/pixel in the 10 micron CCD pixel example. For example, binning of 8 pixels yields a spectral resolution of 3.2 nm at all wavelengths. To achieve this spectral resolution, the interferometer method would require 1000 OPD increments and acquisitions.

Analysis of the spectrum based on this resolution can be conducted to determine which dyes are present. Although the spatial resolutions differ considerably in the two methods, as long as the dye peaks are separated by the spectral resolution spacing, the spectral decomposition algorithms will find all dyes within the spatial resolution area. We have demonstrated that the analysis algorithms can resolve 5 dyes with peaks separated by more than 6 nm in various combinations and known quantity ratios against the dye standards. The program successfully identifies the dyes present with a 91% accuracy in the quantities.

Software

Software (*Hyper*Scope, a 'C' language program) controls all the hardware components for acquisition.

It includes features for analyzing and displaying the resultant $X-Y$ images and spectral information for the grating spectrometer Hyperspectral Imager. During a scan, individual pictures are taken in the $Y-\lambda$ plane, while the stage is incremented in the X-direction. A collection of such $Y-\lambda$ scan files, which can total from 50–1000, is merged to build an image cube (Figure 2). Another advantage of the single-line acquisition mode is that time-dependent features can be monitored continuously. The software was designed to permit repeated collection of a single line at variable time points. The utility of this feature has been demonstrated by capturing images of fluorescent objects moving through UV-transparent capillaries.

The software was designed to display the resulting $X-Y$ plane extracted in various ways from the image cube. A graph of the emission spectrum for any pixel within that image may be viewed by clicking on any pixel of interest in the $X-Y$ image (Figure 3c). A standard linear curve-fitting algorithm is used to determine the contribution of individual dyes to the measured emission spectrum. The software also features a windowing technique (integration of the emission spectra over a fixed window) which emulates standard filtering. An overlay feature within the software allows the curve fitting results to be displayed in false color and compared by viewing the composite for multiple fluorophores in a single image. Additionally, it permits the contribution of a fluorophore to be emphasized for visualization purposes by either displaying the contribution of a single fluorescent signature in the absence of the others that were present in the image or by scaling individual display intensity values up or down. Overlapping pseudo-colors assigned to represent each fluorophore (either by curve fitting or by windowing) may be displayed as added, averaged, maximum or minimum values. For each new fluorophore–excitation source combination, the characteristic emission spectra is acquired and added to a library of available spectra that can be used as components in the spectral decomposition. This permits the user to introduce new fluorophores at any time. Moreover, background spectra (defined as a region of interest by the user) can be acquired and used as one element of the decomposition. This background component can be turned off in the false color view (as any of the spectral components may be) resulting in enhanced noise reduction and visual contrast improvement.



Figure 3 The benefit of spectral imaging is demonstrated in a spatial high-resolution scan of an expression microarray. (a) A portion of the scan of an expression microarray on a microscope slide using the Genepix4000 scanner. It records the intensity emitted by the Cy3 dye when excited with a 532 nm laser. (b) A portion of the scan of the same microarray with the Hyperspectral Imaging Microscope using a 40X objective and Hg excitation lamp. False color is displayed to indicate the intensity variations. (c) A *Hyper*Scope computer program display of the spectrum recorded when the cursor is placed over one pixel in a scan.

Description of Acquisition

In order to acquire a full image, a slide is placed on the microstage mover (Ludl Electronics) that allows for precise movement of the sample across the image acquisition plane. The user can position the stage via a joystick or via software to move to predetermined coordinates. The image is then scanned, with the number of scans being selected at the time of the image acquisition. Furthermore, the sample can be scanned at one magnification or resolution and then rescanned at another. Each $Y-\lambda$ image is saved as a single $Y-\lambda$ file for each increment along the sample. Thus, each image file corresponds to the excitation line of light and the emission collection region that maps through the imaging spectrograph to the CCD camera. Saving individual files permits unlimited $Y-\lambda$ image acquisition at the same Y coordinate, valuable for time-dependent studies. This feature also provides some robustness by enabling a partial $X-Y$ image to be displayed should acquisition of one or more Y scans fail for any reason. After acquiring each image, the stage is moved automatically, one or more steps in the X direction, to acquire emissions at the next line and generate the next $Y-\lambda$ file. Therefore, only the fluorescent probes in a line at a single X-location are examined at each acquisition time. Step sizes can be adjusted by the software to give: (i) the best resolution; (ii) the best 1:1 image; (iii) the minimum overlap; or (iv) the fast acquisition time.

After a variable number of rows of associated emission have been captured (typically 50–1000 scans), an image cube is loaded into memory comprising all the $Y-\lambda$ data files. A graph of the spectrum from any pixel (or bin) in the $X-Y$ plane may be displayed in a separate window by clicking on the cube (Figure 3c). A typical acquisition scan of 250 $Y-\lambda$ files, which are used to construct a $250 \times 768 \times 128$ ($\times$ 12 bit) image cube, consists of approximately 100 Mb of information.

MicroArray Scanning and Customized Excitation

Another use of this technology is to analyze spotted microarrays. The Hyperspectral Imager has been compared to commercial two-color scanners with comparable sensitivity at approximately 0.5 fluors per square micron (Figure 3). Increased sensitivity (500–10 000 gain) can be provided by using a microchannel plate amplifier (Model VS4-1845, Videoscope International, Ltd.) installed between the CCD camera and the imaging spectrograph.

Since the hyperspectral imaging microscope collects images that reflect only the $Y-\lambda$ plane, it contains the potential to use a single line of light as a source for image illumination. Therefore, lights systems being developed, which are capable of generating a line of light composed of variable or complex wavelengths, could be employed to precisely control excitation. The incorporation of such an excitation source in hyperspectral imaging microscopy could be useful in many clinical and basic research applications.

See also

Environmental Measurements: Hyperspectral Remote Sensing of Land and the Atmosphere. **Imaging:** Interferometric Imaging.

Further Reading

Anguiano A (2000) Fluorescence in situ hybridization (FISH): Overview and medical applications. *Journal of Clinical Ligand Assay* 23: 33–42.

Berland K, Jacobson K and French T (1998) Electronic cameras for low-light microscopy. *Methods in Cell Biology* 56: 19–44.

Bernheim A, Vagner-Capodano AM and Couturier J (2000) From cytogenetics to cytogenomics of tumors. *S-Medical Science* 16: 528–539.

Bezrookove V, Hansson K, van der Burg M, *et al.* (2000) Individuals with abnormal phenotype and normal G-banding karyotype: improvement and limitations in the diagnosis by the use of 24-colour FISH. *Human Genetics* 106: 392–398.

Boland MV and Murphy RF (1999) Automated analysis of patterns in fluorescence-microscope images. *Trends in Cell Biology* 9: 201–202.

Cardullo RA and Alm EJ (1998) Introduction to image processing. *Methods in Cell Biology* 56: 91–115.

Garini Y, Katzir N, Cabib D, Buckwald RA, Soenksen D and Malik Z (1996) Spectral bio-imaging. In: Wang XF and Herman B (eds) *Fluorescence Imaging Spectroscopy and Microscopy*, pp. 87–122. New York: John Wiley and Sons.

Garini Y, Macville MV, du Manoir S, *et al.* (1996) Spectral Karyotyping. *Bioimaging* 4: 65–72.

Gothot A, Grosdent J and Palulus J (1996) A strategy for multiple immunophenotyping by image cytometry: Model studies using latex microbeads labeled with seven Streptaviden-bound fluorochromes. *Cytometry* 24: 214–225.

Gribble SM, Roberts I, Grace C, Andrews KM, Green AR and Nacheva EP (2000) Cytogenetics of the chronic myeloid leukemia-derived cell line K562: Karyotype clarification by multicolor fluorescence *in situ* hybridization, comparative genomic hybridization, and locus-specific fluorescence in situ hybridization. *Cancer Genet Cytogenetics* 118: 1–8.

Han H, Gao X, Su J and Nie S (2001) Quantum-dot-tagged microbeads for multiplexed optical coding of bimolecules. *Nat Biotech.* 19: 631–635.

Huebschman ML, Schultz RA and Garner HR (2002) Characteristics and capabilities of the hyperspectral imaging microscope. *Eng in Med and Bio.* 21: 104–117.

Inoue T and Gliksman N (1998) Techniques for optimizing microscopy and analysis through digital image processing. *Methods in Cell Biology* 56: 63–90.

Jain AK (1997) *Fundamental of Digital Image Processing*, pp. 80–128. New Jersey: Prentice-Hall.

Jalal SM and Law ME (1999) Utility of multicolor fluorescent in situ hybridization in clinical cytogenetics. *Genet Med.* 1: 181–186.

Johannes C, Chudoba I and Obe G (1999) Analysis of X-ray-induced aberrations in human chromosome 5 using high-resolution multicolour banding FISH (mBAND). *Chromosome Research* 7: 625–633.

Kruse F (1993) The Spectral Image Processing System (SIPS) – Interactive visualization and analysis of imaging spectrometer data. *Remote Sensing Environment* 44: 145–163.

Lu YJ, Morris JS, Edwards PAW and Shipley J (2000) Evaluation of 24-color multifluor-fluorescence *in-situ* hybridization (M-FISH) karyotyping by comparison with reverse chromosome painting of the human breast cancer cell line T-47. *Chromosome Research* 8: 127–132.

Malik Z, Cabib D, Buckwald RA, Talmi A, Garini Y and Lipson SG (1996) Fourier transform multipixel spectroscopy for quantitative cytology. *Journal of Microscopy* 182: 133–140.

Press WH, Flannery BP, Teukolsky SA and Vetterling WT (1986) *Numerical Recipes, the Art of Scientific Computing*, pp. 546. New York: Cambridge University Press.

Raap AK (1998) Advances in fluorescence in situ hybridization. *Mutat. Res. Fundam. Mol. Mech. Mutagen* 400: 287–298.

Sakamoto M, Pinkel D, Mascio L, *et al.* (1995) Semiautomated DNA probe mapping using digital imaging microscope: II. system performance. *Cytometry* 19: 60–69.

Schrock E, duManoir S, Veldman T, *et al.* (1996) Multicolor spectral karyotyping of human chromosomes. *Science* 273: 494–497.

Schultz RA, Nielsen T, Zavaleta JR, Ruch R, Wyatt R and Garner HR (2001) Hyperspecteral imaging: a novel approach for microscopic analysis. *Cytometry* 43: 239–247.

Schwartz S (1999) Molecular cytogenetics: show me the colors. *Genet Med.* 1: 178–180.

Speicher MR, Ballard SG and Ward DC (1996) Karyotyping human chromosomes by combinatorial multi-fluor FISH. *Nature Genetics* 12: 368–375.

Wang YL (1998) Digital deconvolution of fluorescence images for biologists. *Methods in Cell Biology* 56: 305–315.

Zhao L, Hayes K and Glassman A (2000) Enhanced detection of chromosomal abnormalities with the use of RxFISH multicolor banding technique. *Cancer Genet Cytogenetics* 118: 108–111.

Imaging Through Scattering Media

A C Boccara, Ecole Supérieure de Physique et Chimie Industrielles and Centre National de la Recherche Scientifique, Paris, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

We are often faced with the problem of seeing through scattering media such as smoke, fog, clothes, blood, tissues, ceramics, walls, etc. Tremendous effort has been made to introduce techniques which will allow us to overcome the intrinsic difficulty of selecting 'good' photons which are able to provide valuable information on structures which appear fuzzy or, for most of the time, completely hidden.

Although a number of concepts and techniques that we will discuss in this article could be applied to a large number of scattering samples, we will restrict ourselves to biological tissues.

Studying light propagation through biological tissues is becoming more and more popular among physicists, biologists, engineers, and doctors. Indeed this research domain appears to be growing rapidly as seen by the number of published articles, conferences, and international meetings. Optical techniques are attractive and are starting to compete with other well-established techniques (magnetic resonance imaging, X-ray imaging, ultrasonic imaging, positron emission tomography, etc.), because they are nonionizing, nondestructive, they can reach high resolution and are usually much cheaper. Optical techniques reveal an optical contrast which is valuable in providing morphologic as well as functional information.

Most biological tissues are weakly absorbing in the deep red and near infrared region of the spectrum; the main difficulty in performing imaging arises from the high level of scattering. Figure 1 shows the picture of a small flash light bulb placed in the mouth: it appears fuzzy and red.

In Figure 2 we consider various photon trajectories between a short pulsed source S and a fast detector D.

Unscattered photons are called ‘ballistic’ photons, their number decreases exponentially, and they are completely damped after one or two millimeters.

Then there are scattered photons which propagate close to the ballistic trajectory reaching the detector; these are named ‘snake-like’ photons and can be used for imaging purposes.

Most of the energy which reaches D is related to the scattered photons which may exhibit very long trajectories (typically ~10 times the distance S–D).

The description of various experimental methods used to overcome the difficulty introduced by scattering will be associated with the various photon families that we have mentioned: ballistic, snake-like, and scattered photons. We will first give a few orders of magnitude of the parameters which will dictate the way light interacts with the tissues. Let us emphasize that these parameters also carry the information related to the contrast mechanism. The ultimate goal is to realize an ‘optical biopsy’, noninvasive but as close as possible to the regular biopsy followed by histopathology.



Figure 1 Biological tissues are highly scattering but the absorption is low in the red (as seen in this digital visible photography) and the near infrared.

Optical Parameters

Scattering Cross-Section

As shown in Figure 3, biological tissues are constituted of structures which exhibit various characteristic scales: from a few nanometers in membranes to about ten micrometers for an entire cell.

As we know from scattering theories these various scales correspond to various scattering properties. For small particles (‘small’ means much smaller than the optical wavelength λ) we are in the Rayleigh regime which is based on the evaluation of a time-varying dipole induced by a uniform time-varying (at the light frequency scale) electric field. This dipole radiates in the far field and its scattering cross-section, which is the ratio of the scattered power to the incoming irradiance for a sphere of radius r, is given by

$$\sigma = \frac{\langle P \rangle}{I} = \left(\frac{n^2 - 1}{n^2 + 2} \right)^2 \frac{8\pi}{3} r^6 k^4 \qquad [1]$$

n being the refractive index of the sphere divided by the index of the surrounding medium and $k = 2\pi/\lambda$. The scattering diagram for such particles is isotropic if we use unpolarized light. This cross-section is much smaller than the ‘geometrical’ section S of the particle; for instance, if $n = 1.5$, $a = 10$ nm, $\lambda = 0.6$ μm, $\sigma = 1510^{-8}$ μm^2, which is much smaller than the actual section (3×10^{-4} μm^2).

For larger particles the sphere (or the ellipse) interacting with a plane polarized wave is rather complicated because we are not restricted to the dipolar approximation (uniform field), but induced multipolar moments and their radiating fields have to be taken into account. This theory was proposed by Mie and can be found in optics textbooks. As an example, Figure 4 shows the scattering cross-section of a micron-size particle as a function of the



Figure 2 Between an ultrafast light source S and a detector D can be distinguished various classes of photons which can be used for imaging.



Figure 3 Various sizes of scatterers may be found in cell structures.



Figure 4 In the Mie scattering regime resonances are observed when varying the wavelength (here a 1 μm sphere, refractive index: 2).

wavelength: a number of 'resonances' can be observed.

The scattering diagram is no longer isotopic, it exhibits lobes, and forward scattering is much higher than back-scattering. Scattering is characterized by a scattering coefficient, μ_s, which is the inverse mean free path l_s of photons between scattering events:

$$l_s = 1/\mu_s = \sigma\rho \qquad [2]$$

where σ is the scattering cross-section and ρ the number of scatterers by unit volume.

The scattering coefficients μ_s of tissues are found within the range 100–1000 cm^{-1}. After a path length L, the number of ballistic photons will be damped by a factor $\exp(-L/l_s)$, so tissue imaging cannot rely only on ballistic photons as they survive only to a path length larger than about one mm. One needs to consider in more detail the scattering properties of the scatterers.

The dominant sizes of the scatterers in tissue (cells) demand consideration of the scattering in the Mie regime. Such a scattering event does not result in isotropic scattering angles. Instead, the scattering in tissue is biased in the forward direction.

Anisotropic scattering is quantified in a coefficient, g, which is defined as the mean cosine of the scattering angle θ, $p(\theta)$ being the probability of a particular scattering angle:

$$g \equiv \langle\cos(\theta)\rangle \equiv \frac{\int_0^{\pi} p(\theta)\cos(\theta)\sin(\theta)\mathrm{d}\theta}{\int_0^{\pi} p(\theta)\sin(\theta)\mathrm{d}\theta} \qquad [3]$$

For isotropic scattering, $g = 0$. For complete forward scattering, $g = 1$. In tissues, g varies from 0.7 to 0.95.

Photon migration, especially in the so-called diffusion regime, is often based on isotropic scattering such as for phonons (heat) or charge carriers scattering. For diffusion-like models, it has been shown that one may use an isotropic scattering model with a corrected scattering coefficient, μ_s', and obtain equivalent results using:

$$\mu_s' = \mu_s(1 - g) \qquad [4]$$

One can consider $l_s' = 1/\mu_s'$ as the length over which the incoming photon loses the memory of its initial direction, μ_s' is usually called the transport-corrected scattering coefficient.

Absorption Cross-Section

The absorption coefficient, μ_a (cm^{-1}) represents the inverse mean path length of photons before absorption. $1/\mu_a$ is also the distance in a medium at which intensity is attenuated by a factor of $1/e$ (Beer's Lambert law). Absorption in tissue is strongly wavelength dependent and is due to chromophores and water. Among the chromophores in tissue, the dominant component is the hemoglobin in blood. In the visible range, the blood absorption is relatively high, whereas it is much weaker in the near infrared. Water absorption is low in the visible and NIR region and increases above 1 μm, with tissues turning completely opaque above 2 μm. Thus, for greatest penetration of light in tissue, wavelengths in the 700–1300 nm spectrum are used. This region of the spectrum is called 'the therapeutic window'. Different spectra of chromophores allow one to separate the contribution of varying functional species in tissue such as quantification of oxy- and deoxy-hemoglobin to study tissue oxygenation.

Finally, when light is propagating in scattering media of thickness L, the damping of the incoming energy involves a combination of its absorption and scattering properties, and is given by

$$\exp(-L/a) \qquad \text{with} \qquad a^2 = 1/3\mu_a(\mu_s' + \mu_a) \qquad [5]$$

This formula reflects the fact that the photon's pathlength is increased by scattering, leading to an increase of the damping, which is related to absorption.

These few examples provide a 'static' view of light behavior in scattering media. Studying in a more detailed way, the spatial and temporal distribution of light, is more difficult.

Photon Migration in Scattering Media

Photon migration models have been inspired by other fields, such as astrophysics, soft matter physics, and neutronics, where physical media are random in both space and time. To avoid difficulties linked to the microscopic complexity such investigations rely on a statistical basis.

The most widely used theory is the time-dependent diffusion approximation to the transport equation:

$$\vec{\nabla}\cdot(D\vec{\nabla}\Phi(\vec{r},t)) - \mu_a\Phi(\vec{r},t) = \frac{1}{c}\frac{\partial\Phi(\vec{r},t)}{\partial t} - S(\vec{r},t) \qquad [6]$$

where $\vec{r}$ and t are spatial and temporal coordinates, c is the speed of light in tissue, and D is the diffusion coefficient related to the absorption and scattering coefficients by the formula:

$$D = \frac{1}{3[\mu_a + \mu_s']} \qquad [7]$$

The quantity $\Phi(\vec{r},t)$ is called the fluence, defined as the power divided by the unit area. This equation does not reflect the scattering angular dependence; the use of μ_s' instead of μ_s ensures that isotropic scattering has been reached. Indeed, for the use of the diffusion theory which implies anisotropic scattering, the diffusion coefficient is expressed in terms of the transport-corrected scattering coefficient; $S(\vec{r},t)$ is the source term.

The diffusion equation has been solved analytically for different types of measurements such as reflection and transmission modes, assuming that the optical properties remain invariant throughout the tissue. To incorporate the finite boundaries, the method of images has been used.

The diffusion approximation equation in the frequency-domain is the Fourier transform of the time-domain equation. This leads to the equation:

$$\vec{\nabla}\cdot(D\vec{\nabla}\Phi(\vec{r},\omega)) - \left[\mu_a + \frac{i\omega}{c}\right]\Phi(\vec{r},\omega) + S(\vec{r},\omega) = 0 \qquad [8]$$

Here the time variable is replaced by the frequency ω which is the modulation angular frequency of the source. In this model, the fluence can be seen as a complex number describing the amplitude and phase of the so-called 'photon density wave' in addition to a DC component:

$$\begin{aligned}\Phi(\vec{r},\omega) &= \Phi_{AC}(\vec{r},\omega) + \Phi_{DC}(\vec{r},0)\\ &= I_{AC}\exp(i\theta) + \Phi_{DC}(\vec{r},0) \qquad [9]\end{aligned}$$

where θ is the phase shift of the diffusing wave whose wavelength is:

$$2\pi\sqrt{\frac{2c}{3\mu_s'\omega}} \qquad [10]$$

Although analytical techniques provide a rapid understanding of most phenomena involved in static or dynamic situations, real biological samples are much more complex than homogeneous isotropic media. In these cases, direct and inverse algorithms map the spatially varying optical properties.

Monte Carlo simulations are very popular nowadays; a number of useful programs are available on the websites of various groups. Results may include time or polarization dependence of the photons along their paths.

The other method used in tissue optics is the random walk theory (RWT) on a lattice. RWT models the diffusion-like motion of photons in turbid media in a probabilistic manner. Using RWT, an expression may be derived for the probability of a photon arriving at any point and time given a specific starting point and time.

Imaging in the Ballistic Regime: Taking Advantage of Various Coherence Properties

Shallow Tissue Imaging Through Selection of Ballistic Photons

When imaging thin (less than 2 mm) tissue samples, it is possible to use photons which have not been scattered, called the ballistic photons which can be used to form high-resolution images in the same manner as if no scattering had taken place.

Their number, however, decreases exponentially with propagation distance and this ballistic signal is usually hidden by multiply scattered photons that obscure the image. For relatively shallow tissue depths it is possible to use various spatial filtering techniques to block the multiply scattered photons and there is much current research that aims to extend optical imaging and biopsy to depths of a few mm.

Confocal microscopy rejects much of the scattered light through spatial filtering and has been shown to form 3-D images at tissue depths of up to 200–300 μm, both *in vitro* and *in vivo*, which corresponds to about 50 dB of damping for the ballistic photons.

Two-photon fluorescence microscopy is particularly interesting in this regime since it ensures that all the detected fluorescence photons originate from the desired image plane. This technique also ensures a better penetration (using IR excitation) and a better resolution (nonlinear response) than single photon confocal microscopes.

Imaging to much greater tissue depths does not appear to be practical using optical microscopy and spatial filtering alone and more sophisticated techniques must also be employed to discriminate in favor of the ballistic photons. These techniques exploit either the fact that the ballistic signal photons retain spatial coherence of incident light or the fact that the ballistic photons keep the optical phase memory that multiply diffused photons have lost.

One of the most successful ballistic light-imaging techniques based on the latter filtering approach is optical coherence tomography (OCT) which uses coherence gating using low temporal coherence light and an interferometric detection. Coherent detection is used to discriminate against the multiply scattered photons that scatter back into the trajectories of ballistic photons. The ballistic light signal is measured by interference with a reference beam and the resulting pattern is detected with high sensitivity using homodyne or heterodyne detection. By using low coherence length sources and matching the time-of-flight of the reference beam signal to that of the desired ballistic light, OCT can acquire depth-resolved images in scattering media such as biological tissues. For powers in the mW range for tissue irradiation in the infrared, the unscattered ballistic (or more precisely single back scattered) component of the light will be limited by the shot noise detection limit after propagating through approximately 25 scattering mean free paths (MFP) of a scattering medium (or more than 100 dB). This corresponds to a ‘typical’ tissue thickness of about 1 mm tissue depth for the reflection geometry which is potentially useful for clinical applications such as screening for skin cancer, or for retinal examination.

OCT has proved clinically useful as a means of acquiring depth-resolved images in the eye and is being developed for application in strongly scattering biological tissue. Although the image acquisition requires pixel-by-pixel scanning, the use of new high-power superluminescent diodes in the 100 mW range or of ultrafast lasers to provide high average power, low coherence length radiation (sub-two cycle lasers) has resulted in an *in vivo* OCT system providing real-time imaging.

There are a number of other approaches to coherent imaging, including whole-field 2-D acquisition techniques which remove the need to scan transversely pixel by pixel.

Whole-field imaging using a temporally and spatially incoherent source and a well-balanced interferometric microscope intrinsically provides higher image acquisition rates and can take advantage of inexpensive spatially incoherent, broadband sources such as high-power LEDs, and white light thermal sources.

As an example, Figure 5 shows Linnik-type white light interferometer with optical path modulation and Figure 6 an image of an *ex-vivo* rat retina where one can recognize the main feature expected from histology.

Holography, which works in the Fourier space rather than in the object or image space, is also an interferometric technique able to discriminate between ballistic and scattered photons. Since the development of electronic holography, which takes advantage of available arrays of detectors with multimillion pixels, this approach is rapidly growing.

Real-time 3-D imaging systems based on photorefractive holography in multi-quantum-wells devices, which can potentially acquire depth-resolved images at thousands of frames per second, have been demonstrated.

These ballistic light techniques can extend the depth of tissue imaging to the mm range when



Figure 5 The full-field OCT setup based on a Linnik interferometer. The PZT actuator is used to modulate the path difference between the two arms.



Figure 6 OCT rat retinal image: retinal pigmented epithelium. PRL: photoreceptor layer. ONL: outer nuclear layer. OPL: outer plexiform layer. INL: inner nuclear layer. IPL: inner plexiform layer. GCL: ganglion cell layer. NFL: nerve fiber layer.

imaging in reflection. When it is necessary to image through cms, rather than mms of tissue, however, there will be no detectable ballistic light signal and one must extract useful information from the scattered photons.

Imaging in the Snake-Like Regime: Taking Advantage of Time (or Frequency) Gating

The first approach is to use time gating to select the earliest arriving scattered light, which will provide the most useful image information.

For moderate tissue depths one can exploit the fact that biological tissue is highly forward scattering, with most photons being only slightly deviated from their original direction upon each scattering event. After a few cm of tissue, there can be a significant number of photons that have followed reasonably well-defined 'snake-like' paths about the original direction through the tissue, arriving at the detector after the ballistic light but before the fully diffuse photons whose trajectories are effectively randomized. This early arriving light can be selectively gated using ultrafast lasers and a variety of detectors such as streak cameras, time-gated optical image intensifiers, and time-gated fast photon counting systems, which provide picoseconds time gates.

An alternative, sometimes cheaper, approach to temporal gating is the use of (high) frequency signal discrimination (which is the Fourier transform of the pulse experiment). The periodic solution of the diffusion equation with a periodic source term gives rise to the so-called 'photon density waves'. Such diffusive waves, like thermal waves, are used in the near-field regime (their amplitudes are damped by $\exp(-2\pi)$ after propagating over a single wavelength path) and they can reveal subsurface structures through their refractive and diffusive behavior. Coherence gating and polarization gating can be used when the early arriving light still retains some degree of coherence of the incident light. Indeed polarization discrimination has been used to select those photons which undergo few scattering events and therefore preserve a fraction of their initial polarization state, from the photons which experience multiple scattering resulting in a complete loss of memory of their initial polarization state.

As an example, Figure 7 shows the image of sub-mm light sources (LEDs) taken through 1 cm of polystyrene solution ($\mu_s' \sim \mu_s \sim 10\ \text{cm}^{-1}$) by selecting photons which kept the memory of their initial circular polarization (here a few less than 1%). One can see the sources quite clearly.

For many important biomedical applications, such as mammography or imaging brain function, it is necessary to penetrate through 5–10 cm of tissue, after which all the detected signal is diffuse. Detecting earlier arriving photons can provide more information but, if the time window is too narrow, the detected signal becomes too weak to use with acceptable data acquisition times.

This problem is, however, being addressed with some success using statistical models of photon transport, with different degrees of approximation ranging from full Monte Carlo simulation of photon propagation to the diffusion equation. The approach is to address the inverse problem, i.e. to measure the scattered light signal as comprehensively as is practical and to calculate what distribution of absorption and scattering properties would have produced the measured signal. This provides a means to quantify the optical properties of biological tissue, averaged over a volume corresponding to a particular distribution of photon paths, and to form relatively low-resolution tomographic images.

Multiplying the number of sources and detectors and correlating the various intensity distributions over the whole structure under examination gives, as expected, better precision in localizing the size and position of the local structure to be identified.

Despite the multiple input and multiple output approaches, real-life situations with the previously



Figure 7 Polarization imaging: here the degree of circular polarization is measured in the upper image. The lower image shows the field without polarization filtering.

mentioned problem of the inhomogeneity of the optical properties of human tissues means that the results are still poor in term of resolution and subcentimeter structures can hardly be observed in breast imaging, for instance.

One important exception to this limited success in finding precisely the position, the size, and the optical properties of hidden structures is the case of ‘activation’ studies. This corresponds to a ‘differential’ situation in which an unknown structure is locally changing with time. Here the goal is not to reach a full description of the unknown structure but only to characterize the local changes induced by the activation.

The main field of application of this approach is certainly in brain activation studies. A matrix of light emitters (usually at two wavelengths which differentiate oxy- and deoxy-hemoglobin, for instance 780 and 840 nm) is coupled to a matrix of light detectors. The signals are usually balanced and any local change which breaks the symmetry of the scattered photon paths induces a differential signal, easy to detect, because there is no background signal before activation takes place.

Moreover it has been demonstrated that for weak perturbations (weak variations of the optical parameters), the inverse problem can be rigorously solved. This geometrical selection provides a cheap and simple setup with rather spectacular results. Sometimes a modulation is added and the phase shift of the photon density wave is enhanced by the differential approach.

Imaging in the Multiple Scattering Regime: Taking Advantage of all the Photons

Light Only: Transillumination and Fluorescence Imaging

The optical systems used for CW measurements are rather simple and require only the alignment of a number of light sources and detectors. Compared to time-gated techniques due to multiple scattering a much stronger path length distribution is present in the signal and the result is a loss of localization and resolution. In the so-called transillumination geometry, collimated detection is used to isolate multiply scattered photons close to the normal emergence angle.

Direct imaging with the required resolution using CW techniques in very thick tissues, such as breast tissue, has not been established even with sophisticated multi-sources/multi-detectors combinations (typically a few tens of sources and detectors at three different wavelengths).

Despite rapid progress in the modeling of light behavior in scattering media it has not yet been demonstrated that CW imaging can provide images with suitable resolution in thick tissue and time-dependent measurement techniques discussed earlier are dominantly used.

For fluorescence imaging, one has to account for the strong attenuation of light as it passes through tissue. Fluorescent dyes (porphyrin, indo-cyanine, and more recently quantum dots) have been developed that are excited and re-emit in the ‘biological window’ at near-infrared (NIR) wavelengths, where scattering and absorption coefficients are lower, which is favorable for deep fluorescence imaging. Fluorescent intensity in deep tissues depends on the location, size, concentration, and intrinsic characteristics (e.g., lifetime, quantum efficiency) of the fluorophores, and on the scattering and absorption coefficients of the tissue at both the excitation and emission wavelengths. In order to extract intrinsic characteristics of fluorophores within tissue, it is necessary to describe the statistics of photon path lengths which depend on all these different parameters. The amount of light emitted at the site of the fluorophore is directly proportional to the total amount of light impinging on the fluorophore.

Using fluorescence contrast has the unique feature of carrying two spectroscopic contrasts related to both excitation and fluorescent photons.

The next two techniques take advantage of another way to handle the optical information by coupling optics and acoustics.

Coupling Light and Sound: Acousto-Optic and Photo-Acoustic

Although the two approaches that we will now describe are different in their basic principles as well as in the experimental setups, their names are similar – opto-acoustics (sometimes called photo-acoustics) and acousto-optics.

Opto- (or Photo-)Acoustics

In this technique a pulsed (or modulated) electromagnetic beam irradiates the structure under examination. Despite their tortuous paths (about 10 to 100 cm) photons propagate through the volume in a few nanoseconds. Local absorbing centers then absorb the electromagnetic energy, they experience a fast thermal expansion, and become sources of acoustic waves.

The optical problem of tomographic reconstruction is then transformed into a simpler problem of acoustic reconstruction of source distribution because the speed of the sound is much slower than the speed of the light. More precisely we can compute the signal generated by a short light pulse impinging on a scattering medium which contains an absorber (thickness e) as can be seen on Figure 8, when $e\mu_a \ll 1$.

The amount of power per unit surface which is deposited in the absorbing slice is $E\mu_a$ (E is the fluence in W/m^2). When the light pulse duration τ is short enough, despite the propagation in the scattering medium ($\tau \ll e/v$ where v is the speed of the sound),



Figure 8 Photo acoustic signal generation: 1-D model.

we find a variation of the mass by volume unit:

$$\Delta\rho \sim \rho\beta\Delta T \sim \rho\frac{\beta E\mu_{\mathrm{a}} e}{C_{\mathrm{v}} e} \qquad [11]$$

The corresponding pressure is:

$$\Delta\rho = \frac{v^2}{\gamma}\Delta\rho \qquad \text{or} \qquad \Delta\rho \sim \rho\frac{v^2\beta E}{C_\rho}\mu_{\mathrm{a}} \qquad [12]$$

Although this approach is new, compared to the purely optical transillumination approach, it has led to a large number of studies in which time gating brings new information to the accurate determination of the US emitter depth. It has been applied to breast tumor examination to complement standard imaging techniques such as echography and X-ray mammography. Recently this technique has demonstrated submillimeter resolution for *in vivo* blood distribution in rat brain imaging.

Acousto-Optic

Here a DC single frequency laser is used to illuminate the sample. For a typical biological sample a few cm thick the trajectories are distributed between the sample thickness value and more than ten times this value. Due to the good temporal coherence of the source all the scattered photons are likely to interfere when they emerge from the sample volume. These interferences are seen as a speckle field which can be observed at a suitable distance from the sample surface.

As seen in Figure 9, adding an ultrasonic field will mainly induce a small (smaller than the optical wavelength) displacement of the scatterers (it also induces local variation of the refractive index) which will cause a speckle modulation at the ultrasonic frequency.

If the zone irradiated by the ultrasonic field is optically absorbing, less photons will emerge from this zone than from a nonabsorbing one and thus less modulation will be seen when scanning across the sample volume. This modulation can be detected by selecting a single speckle grain and averaging over a number of uncorrelated speckle distributions to obtain a suitable average value (for instance with latex particles). This is not always possible, in particular because the overall geometry is rather stable in a semisolid tissue. Using a single detector which receives many speckle grains gives less contrast. A multiple detector and a parallel processing of many speckle grains improve greatly the speed and the signal-to-noise ratio: a typical image of absorbing spheres, embedded in a scattering phantom, is shown in Figure 10.



Figure 9 Acousto-optic imaging principle: photons are tagged by the acoustic field.



Figure 10 Acousto-optic imaging (lower image) of two absorbing spheres embedded in a scattering medium (upper image shows a section of the gel sample).

Conclusion

The complexity associated with multiple scattering in turbid media, such as tissues of the human body, prevents an easy use of light as a routine tool for in-depth examination, whereas superficial examinations have always been sources of diagnostics.

Optical techniques will obviously progress to better characterization of tissues' optical properties, improvement of laser properties and detection techniques, as well as new mathematical approaches of the inverse problem.

We believe that this field of research is still open to new ideas, and new experimental schemes leading to new breakthroughs in the delicate problem of using light in highly scattering media.

Acknowledgements

I would like to warmly thank all the research staff (Arnaud Dubois, Benoit Forget, François Ramaz, Vincent Loriette) and PhD students (Michael Atlan, Kate Grieve, Gael Moneron, Juliette Selb) at ESPCI whose results have been used to illustrate this article. I also acknowledge discussions with my colleagues Pr Paul French (Imperial College London) and Dr Amir Gandbjbakhche (NIH Bethesda).

See also

Coherence: Coherence and Imaging. **Holography, Techniques:** Digital Holography. **Imaging:** Interferometric Imaging. **Interferometry:** White Light Interferometry. **Microscopy:** Confocal Microscopy; Imaging Multiple Photon Fluorescence Microscopy. **Tomography:** Optical Coherence Tomography; Tomography and Optical Imaging.

Further Reading

Boccara AC and Fink M (eds) (2001) *Optical and Acoustical Imaging of Biological Media*. Compte Rendu de l'Académie des Sciences, Physics and Astrophysics série IV tome 2, no. 8. Paris: Elsevier.

Born M and Wolf E (1997) *Principles of Optics*. New York: Oxford University Press.

Goodman JW (2000) *Statistical Optics*. New York: Wiley-Interscience.

Hecht E and Zajac A (1979) *Optics*. Reading, MA: Addison-Wesley.

Sebbah P (ed.) (2001) *Waves and Imaging through Complex Media*. Dordrecht: Kluwer Academic Publishers.

Van de Hulst HC (1981) *Light Scattering by Small Particles*. New York: Dover.

Van Tiggelen B and Skipetrov S (eds) (2003) *Wave Scattering in Complex Media: From Theory to Applications*. Dordrecht: Kluwer Academic Publishers.

Infrared Imaging

K Krapels and R G Driggers, US Army Night Vision and Electronic Sensors Directorate, Fort Belvoir, VA, USA

Published by Elsevier Ltd.

Introduction

All objects above 0 Kelvin emit electromagnetic radiation associated with the thermal activity on the surface of the object. For terrestrial temperatures (around 300 Kelvin), objects emit a good portion of the electromagnetic flux in the infrared part of the electromagnetic spectrum. The visible band spans wavelengths from 0.4 to 0.7 micrometers (infrared engineers typically use micrometer/μm for wavelength rather than the nanometer or wavenumber more commonly used in other fields). Infrared imaging devices convert energy in the infrared portion of the electromagnetic spectrum into images that can be created by the human eye. The unaided human eye cannot image infrared energy because the lens of the eye is opaque to infrared radiation.

The infrared spectrum begins at the red end of the visible spectrum where the eye can no longer sense energy. It spans from 0.7 μm to 100 μm. The infrared spectrum is, by common convention, broken into five different bands (this may vary according to the application). The bands are typically defined as: near infrared (NIR) from 0.7 to 1.0 μm; short wavelength infrared (SWIR) from 1.0 to 3.0 μm; mid-wavelength infrared (MWIR) from 3.0 to 5.0 μm; long wavelength infrared (LWIR) from 8.0 to 14.0 μm; and far infrared (FIR) from 14.0 to 100 μm. These bands are depicted graphically in Figure 1, which shows the atmospheric transmission for a 1-kilometer horizontal ground path for a 'standard' day in the United States. These types of transmission graphs can be tailored for any conditions, using sophisticated atmospheric models such as MODTRAN (from www.ontar.com). Note that



Figure 1 Visible and infrared spectra.



Figure 2 Visible image–reflected energy.



Figure 3 Infrared image–self-emitted energy.

there are many atmospheric 'windows', such that an imager designed with such a band selection can see through the atmosphere.

The primary difference between a visible spectrum camera and an infrared imager is the physical phenomonology of the radiation from the scene being imaged. The energy used by a visible camera is predominantly reflected solar, or some other illuminating energy, in the visible spectrum. The energy imaged by infrared imagers (Forward Looking Infrared, commonly known as FLIRs) in the MWIR and LWIR bands, is primarily self-emitted radiation. From Figure 1, the MWIR band has an atmospheric window in the 3 to 5 μm region and the LWIR band has an atmospheric window in the 8 to 12 μm region. The atmosphere is opaque in the 5 to 8 μm region, so it would be pointless to construct a camera that responds to this waveband.

Figures 2 and 3 are images that show the difference in the source of the radiation sensed by the two types of cameras. The visible image (Figure 2) is light that was provided by the Sun, propagated through Earth's atmosphere, reflected off the objects in the scene, traversed through a second atmospheric path to the sensor, and then imaged with a lens and a visible band detector. A key here is that the objects in the scene are represented by their reflectivity characteristics. The image characteristics can also change by any change in atmospheric path or source characteristic change. The atmospheric path characteristics from the Sun to the objects change frequently, because the Sun angle changes throughout the day and also weather and cloud conditions change. The visible imager characterization model is therefore a multipath problem that is extremely difficult.

The LWIR image given in Figure 3 is obtained primarily by the emission of radiation by objects in the scene. The amount of electromagnetic flux depends on the temperature and emissivity of the objects. A higher temperature and a higher emissivity correspond to a higher flux. The image shown is 'white-hot' or the whiter a point in the image the higher the flux leaving the object. It is interesting to note that trees have a natural self-cooling process since a high temperature can damage foliage. Objects that have absorbed a large amount of solar energy are hot and are emitting large amounts of infrared radiation. This is sometimes called 'solar loading'.

The characteristics of the infrared radiation emitted by an object are described by Planck's black-body law in terms of spectral radiant emittance

$$M_\lambda = \varepsilon(\lambda)\frac{c_1}{\lambda^5(e^{c_2/\lambda T} - 1)}\ \mathrm{W/cm^2\ \mu m} \qquad [1]$$

where c_1 and c_2 are constants of 3.7418×10^4 W μm^4/cm^2 and 1.4388×10^4 μm K. The wavelength, λ, is provided in micrometers and $\varepsilon(\lambda)$ is the emissivity of the surface. A black-body source is defined as an object with an emissivity of 1.0, so it is a perfect emitter. Source emissions of black-bodies at typical terrestrial temperatures are shown in Figure 4. Often, in modeling, the terrestrial background temperature is assumed to be 300 K. The source emittance curves are shown for other temperatures for comparison purposes. One curve corresponds to an object colder than the background and two curves correspond to temperatures hotter than the background.

Planck's equation describes the spectral shape of the source as a function of wavelength. It is readily apparent that the peak shifts to the left (shorter wavelengths) as the body temperature increases. If the temperature of a black-body is increased to that of the Sun (5900 Kelvin), the peak of the spectral shape would decrease to 0.55 μm or green light. This peak wavelength is described by



Figure 4 Planck's blackbody radiation curves for four temperatures from 290 K to 320 K.



Figure 5 Location of peak of black-body radiation, Wien's Law.

Wien's displacement law

$$\lambda_{\max} = 2898/T, \ \mu\text{m} \qquad [2]$$

Figure 5 shows the peak wavelength as a function of temperature through the longwave region. It is important to note that the difference between the black-body curves is the 'signal' in the infrared bands. For an infrared sensor, if the background is at 300 K and the target is at 302 K, the signal is the difference in flux between these curves. Signals in the infrared ride on very large amounts of background flux. However, in the visible band this is not the case. For example, consider the case of a white target on a black background. The black background is generating no signal, whereas the white target is generating a maximum signal (given that the sensor gain has been adjusted). Dynamic range may be fully utilized in a visible sensor. In the case of an IR sensor, a portion of the dynamic range is used by the large background flux radiated by everything in the scene. This flux never has a small value, hence sensitivity and dynamic range requirements are much more difficult to satisfy in IR sensors than in visible sensors. Table 1 summarizes this characteristic numerically for the 300 K background and targets shown in Figure 4.

A typical infrared imaging system scenario is depicted in Figure 6. The scene consists of two major components, the target and the background. In an IR scene, the majority of the energy is remitted from the constituents of the scene. This emitted energy is transmitted through the atmosphere to the sensor. As it propagates through the atmosphere it is degraded by absorption and scattering. Obscuration by intervening objects and additional energy emitted by the path also affect the target energy. All of these contributors, which are not the target of interest, essentially reduce one's ability to discriminate the target. So, at the entrance aperture for the sensor, the target signature is reduced from the values observed at the target. Then, the signal is degraded by the optics and scanner (as applicable) of the sensor. The energy is then sampled by the detector array and converted to electrical signals. Various electronics amplify and condition this signal before it is presented to either a display for human interpretation or an algorithm like an automatic target recognizer for machine interpretation. A linear systems approach to modeling allows the components' transfer functions to be treated separately as contributors to the overall system performance. This approach allows for straightforward modifications to a performance model for changes in the sensor or environment when performing trade-off analyses.

Table 1 Signal/dynamic range limitation in IR bands

Blackbody temperature	*Exitance in 8–12 μm band (w/cm^{-2})*	*Contrast*
290 ($-10\Delta T$ K target)	1.25E − 02	−8.48%
300 (background)	1.48E − 02	
310 ($+10\Delta T$ target)	1.74E − 02	7.97%
320 ($+20\Delta T$ target)	2.02E − 02	15.39%

History of Infrared Imaging

Night vision systems began to be developed extensively during World War II. Satisfying the requirement to image at night was approached with two different methodologies. The first method was image intensification (I^2). This method involves amplification of any small light that was available and displaying it directly to the eye. Typically I^2 devices are sensitive to visible light and a small portion of the short-wave IR (SWIR, 0.7–3.0 μm) band. They are often classified (along with visible band imagers) as electro-optical (EO) imagers. With an I^2 imager, there must be some source of illumination for them to function well (as little as starlight is sufficient



Figure 6 Typical infrared imaging scenario.

Table 2 Applications of infrared imaging

Category	*User*	*Application*
Military	Intelligence analyst	Intelligence surveillance and reconnaissance
	Pilot, driver	Navigation/pilotage
	Gunner, weapons officer	Targeting/fire control
	Air defense	Search and track
Commercial	*Civil government*	
	Police	Surveillance, fugitive tracking
	Fire	Rescue, hot-spot location
	Environmental	
	EPA	Emission tracking
	Interior department	Resource management
	NIMA\USGS	Mapping
	NOAA\MWS	Weather forecasting
	Industrial	
	Manufacturers	Machine vision
	Maintenance	Non-destructive testing
	Medical	
	Doctors	Diagnostic imaging

for approx 20/40 acuity with current systems). The second type of night vision device is the infrared or thermal imager (also known as FLIRs). FLIRs are sensitive to the radiation in either the mid-wave IR (MWIR, 3–5 μm) or long-wave IR (LWIR, 8–14 μm) bands.

The first infrared cameras used photographic film that was sensitive to infrared wavelengths. Intelligence and reconnaissance imaging from aircraft drove the infrared system development as a night augmentation to existing visible cameras. These imagers used either continuous moving film or stationary film, like an ordinary camera. A slit aperture was used in the continuous moving film cameras and aircraft motion provided the scan of the scene along the film to build a continuous image. The introduction of television, as electronic imaging in the visible spectrum, led to the development of electronic imagers in the infrared band. Electronic infrared imagers were not restricted to looking down and using aircraft motion for scan, hence these devices came to be known as FLIRs (Forward Looking InfraRed). Today, an electronic infrared imager may be called a FLIR or a thermal imager, with the trend being to use FLIR to describe military applications.

Early FLIRs were often accompanied by illumination devices. They were not very sensitive compared to modern FLIRs so active illumination was necessary. Infrared searchlights or illuminators were used to get higher signal-to-noise ratios. These types of FLIRs are called 'active' IR imagers, while FLIRs that do not use illuminators are 'passive' imagers. Generally, active imagers are used in civil applications and are declining in military use. Broadly, applications for thermal imagers fall into two categories; military and commercial. Table 2 lists some of the purposes and users for modern thermal imagers. The design and performance criteria vary widely for some of the applications.

Types of Infrared Imagers

Infrared imagers are classified by different characteristics: scan type, detector material/cooling requirements, and detector physics. The scan type refers to the method used to construct the electronic image. The camera may use a single detector which is raster scanned over the input scene to build an image. Alternatively, a parallel scan uses a linear array of detectors scanned across a scene to build an image. The latest advances in materials have led to staring arrays of detectors. In a staring system, a detector is present in two dimensions to represent each image pixel and no mechanical motion of the focal plane is necessary to construct the image. There are some hybrid FLIR types that combine the different imaging techniques. Usually this combination leads to an improvement in signal-to-noise ratio or to reduce undersampling.

The second classification, by detector material/cooling requirements, usually describes FLIRs built using differing materials. For example, a typical LWIR FLIR material is mercury cadmium telluride (HgCdTe or MCT). In order to achieve high sensitivity, these devices are cooled to decrease dark current. Usually the cooling is based on liquid nitrogen or a cryogenic cooler, and the detectors operate at 77 K. Another common detector material is indium antimonide (InSb), which is used for MWIR FLIRs and is also cooled. A newer class of infrared cameras is not cooled, being referred to as 'uncooled' FLIRs. These uncooled FLIRs are microbolometers (resistive elements) or pyrometers (capacitive elements) and have less sensitivity than cooled imagers. Typically, the cooled imagers are comprised of photon detectors while the uncooled imagers are based on thermal detectors, the uncooled FLIRs being used in lower-performance applications.

Infrared Imager Performance

There are three general categories of infrared sensor performance characterizations. The first is sensitivity and the second is resolution. When end-to-end, or human-in-the-loop (HITL), performance is required, the third type of performance characterization describes the visual acuity of an observer through a sensor. The former two are both related to the hardware and software that comprises the system, while the latter includes both the sensor and the observer. Sensitivity is determined through radiometric analysis of the scene/environment and the quantum electronic properties of the detectors. Resolution is determined by analysis of the physical optical properties, the detector array geometry, and other degrading components of the system in much the same manner as complex electronic circuit/signals analysis.

Sensitivity describes how the sensor performs with respect to input signal level. It relates noise characteristics, responsivity of the detector, light gathering of the optics, and the dynamic range/quantization of the sensor. Radiometry describes how much light leaves the object and background and is collected by the detector. Optical design and detector characteristics are of considerable importance in sensor sensitivity analysis. In infrared systems, noise equivalent temperature difference (NETD) is often a first-order description of the system sensitivity. The 3D noise model describes more detailed representations of sensitivity parameters (see Further Reading).

The second type of measure is resolution. Resolution is the ability of the sensor to image small targets and to resolve fine detail in large targets. Modulation transfer function (MTF) is the most widely used resolution descriptor in infrared systems. Alternatively, it may be specified by a number of descriptive metrics such as the optical Rayleigh criterion or the instantaneous field-of-view of the detector. Where these metrics are component-level descriptions, the system MTF is an all-encompassing function that describes the system resolution.

Sensitivity and resolution can be competing system characteristics and they are the most important issues in initial studies for a design. For example, given a fixed sensor aperture diameter, an increase in focal length can provide an increase in resolution, but may decrease sensitivity. Typically, visible band systems have plenty of sensitivity and are resolution-limited, whereas infrared imagers have been more sensitivity-limited. With staring infrared sensors, the sensitivity has seen significant improvements.

Often metrics, such as NETD and MTF, are considered to be separable. However, in an actual sensor, sensitivity and resolution performance are not independent. As a result, minimum resolvable temperature difference (MRT or MRTD) has become the primary performance metric for infrared systems. MRT is a quantitative performance measure in terms of both sensitivity and resolution and a simple MRT curve is shown in Figure 7. The performance is bounded by the sensor's limits and the observer's limits. The temperature difference (or thermal contrast) required to image smaller details in a scene increases with detail size. The inclusion of observer performance yields a single sensor performance characterization, MRT. It describes sensitivity as a function of resolution, and includes the human visual system.



Figure 7 IR imager performance.

Many different sensor characteristics may be considered to increase the fidelity of a sensor model. A list of typical infrared imaging system parameters is given in Figure 8. When considering performance in the system sense, the groupings are often blocks in the system diagram, each with separate transfer functions. This approach works well unless the linear shift invariance assumption is not valid.

General Characteristics of Infrared Imagers

There are a number of imaging characteristics that make infrared systems a little different than conventional visible imaging systems. These include source flux levels, detector charge storage and sensitivity, detector size, diffraction blur, sampling, and uniformity characteristics.

First, we consider the source flux levels. The daytime and night-time flux levels (in photons per second per square centimeter) on Earth in the visible (0.3 to 0.7 μm) is 1.5×10^{17} and around 1×10^{10}, respectively. In the mid-wave (3 to 5 μm), the daytime and night-time flux levels are 4×10^{15} and 2×10^{15} μm where the flux is a combination of

- Illumination
  - Spectral irradiance
- Target
  - Reflectivity
  - Emissivity
  - Size and spatial characteristics
  - Temperature
- Atmosphere
  - Weather conditions
  - Obscurants
  - Transmission
  - Optical transfer function
  - Scattering
- Sensor optics
  - Lens transmissions
  - Mirror reflectivity
  - Filter transmission
  - Aberrations
  - Diffraction
  - Aperture size and shape
- Sensor detector
  - Responsivity
  - Detectivity
  - Noise characteristics
  - Detector angular substense
- Sensor electronics
  - Temporal characteristics
  - Digital and/or analog
  - Filter characteristics
- Display
  - Resolution
  - Brightness and contrast
- Human psychophysics
  - Temporal response
  - Image transfer function
  - Brightness dependence
- ATR or AiTR response
  - Discrimination probability
  - False alarm rate

Figure 8 Factors in infrared sensor modeling.

emitted and solar reflected flux. In the longwave, the flux is primarily emitted where both day and night yield a 2×10^{17} µm frequency, the AMOP drops rapidly to zero. The effect is to extend the prediction of the MRT beyond the half sample rate and introduce a parameter called minimum temperature difference perceived (MTDP) to replace MRT in the range performance estimate and also in the lab to characterize an undersampled system.

The concept of MTDP follows from observation of standard 4-bar images as the pattern frequency passes the imager half sample rate. The image changes from four bars to three, two, and finally one (can be perceived). The phase of the target image on the detector array may need to be adjusted to observe this progression. The standard MRT measurement requires that all four bars be resolvable by the observer during the measurement process. For use in the lab, the MTDP is defined as the minimum temperature difference at which two, three, or four bars can be resolved in the image of the standard 4-bar test pattern by an observer, with the test pattern positioned at optimum phase. The optimum phase is the phase at which two, three, or four bars are 'best perceived'. TRM3 uses the standard definition of MRT as for adequately sampled imagers. The TRM3 Approach Model is implemented if the imager is considered undersampled as defined when the prefilter MTF at the half-sample frequency is larger than 10%. The MTDP equation is given by

$$\mathrm{MTDP}(f) = \frac{\frac{\pi}{2}\mathrm{SNR}_{\mathrm{th}}\Psi(f)}{\mathrm{AMOP}(f)} \qquad [3]$$

where $\mathrm{SNR}_{\mathrm{th}}$ is a threshold signal-to-noise ratio and Ψ is the total system filtered noise. MTDP is used in the same manner as MRTD in range calculations.

Another approach is the triangle orientation discrimination (TOD) threshold. In the TOD, the test pattern is a (nonperiodic) equilateral triangle in four possible orientations (apex up, down, left, or right), and the measurement procedure is a robust 4AFC (four alternative forced-choice) psychophysical procedure. In this procedure, the observer has to indicate which triangle orientation he sees, even if he is not sure. Variation of triangle contrast and/or size leads to a variation in the percentage correct between 25% (complete guess) and 100%, and by interpolation the exact 75% correct threshold can be obtained. A complete TOD curve (comparable to an MRTD curve) is obtained by plotting the contrast thresholds as a function of the reciprocal of the triangle angular size (Figure 9).

The TOD method has a large number of theoretical and practical advantages: it is suitable for undersampled and well-sampled electro-optical and optical



Figure 9 Modeling, testing and performance triangle.

imaging systems in both the thermal and visual domains, it has a close relationship to real target acquisition, and the observer task is easy. The results are free from observer bias and allow statistical significance tests. The method may be implemented in current MRTD test equipment with little effort, and the TOD curve can be used easily in a target acquisition (TA) model such as ACQUIRE. Two validation studies with real targets show that the TOD curve predicts TA performance for under-sampled and well-sampled imaging systems very well. Currently, a theoretical sensor model to predict the TOD (comparable to NVTherm or TRM3) is under development. The lab measurement and field performance appear sound, but the model is not yet available.

Testing Infrared Imagers: NETD, MTF, and MRTD (Sensitivity, Resolution and Acuity)

In general, imager sensitivity is a measure of the smallest signal that is detectable by a sensor. Sensitivity is determined using the principles of radiometry and the characteristics of the detector. For infrared imaging systems, noise equivalent temperature difference (NETD) is a measure of sensitivity. The system intensity transfer function (SITF) can be used to estimate the NETD, which is the system noise rms voltage over the noise differential output. NETD is the smallest measurable signal produced by a large target (extended source).

Equation [4] describes NETD as a function of noise voltage and the system intensity transfer function. The measured values are determined from a line of video stripped from the image of a test target, as depicted in Figure 10. A square test target is placed before a black-body source. The delta T is the difference between the black-body temperature and the mask. This target is then placed at the focal point of an off-axis parabolic mirror. The mirror serves the purpose of a long optical path length to the target, yet relieves the tester from concerns over atmospheric losses to the temperature difference. The image of the target is shown in Figure 10b. The SITF slope for the scan line in Figure 10c is the $\Delta S/\Delta T$ where ΔS is the signal measured for a given ΔT. The N_{rms} is the background signal on the same line.

$$\mathrm{NETD} = \frac{N_{\mathrm{rms}}[\mathrm{volts}]}{\mathrm{SITF\_Slope}[\mathrm{volts/K}]} \qquad [4]$$

Resolution is a general term that describes the size of resolvable features in an imager's output. With infrared imaging systems, the resolution is described by the system modulation transfer function (MTF). Consider Figure 11 for the determination of MTF, from either point spread function or edge spread function (psf or esf). In Figure 11a, a test target is placed at the focal point of a collimator. The target may be a point, edge, or line as shown in Figure 11b. The IR system images this target. The output of a detector scan, or a line of detectors in the staring array case, is taken for analysis, in Figure 11c. For the edge spread function, the spatial derivative is taken to get the psf. The Fourier transform is then calculated to give the system MTF as shown in Figure 11d. The point spread function is really the impulse response of the system, so a smaller psf is desirable, where a wide MTF is desirable. Such a psf/MTF combination gives a higher resolution.

The MRTD of an infrared system is defined as the differential temperature of a four bar target that makes the target just resolvable by a particular observer. It is a measure of observer visual acuity when a typical observer is using the infrared imager. It results in a descriptor, which is a function not just of a single value. It is a plot of sensitivity as a function of spatial frequency.


Black-body target
FLIR
Filter
Output
Off-axis parabola
(a)
Test configuration
Target mask
Scan line
T1
BB
T2
ΔT=T1–T2
(b)
NETED target images
Signal level
ΔS
Time
(c)
Scan line output
ΔS
ΔT
(d)
SITE curve

Figure 10 NETD measurement.


Black-body target
FLIR
Output
Off-axis parabola
(a)
Test configuration
psf
Target
esf
Target
(b)
MTF targets
psf(x,y)
x
y
psf(x,0)
x
esf(x,0)
y
x
x
(c)
Scan line outputs
MTF
Cyc/mrad
(d)
MTF curve

Figure 11 MTF measurement.

This parameter can be extended to field performance using Johnson's criteria.

As a laboratory measurement, it uses a 7:1 aspect ratio bar target. The procedure is shown in Figure 12. A bar target mask, with a black-body illuminator, is placed at the focal plane of a collimator (Figure 12a and 12b). The temperature is increased from a small value until the bars are just resolvable to a trained



(a) Test configuration (b) MRT targets



(c) MRT target image (d) MRT curve

Figure 12 MRTD measurement.

observer (Figure 12c). Then the temperature difference is decreased until the bars are no longer visible. These are averaged for a particular target. The same procedure is performed with a negative contrast bar target. The average of the positive and negative values is the MRT for a particular spatial frequency. These data points are plotted and a curve may be fitted to interpolate/extrapolate performance at other than the discrete spatial frequencies of the targets, as in Figure 12d.

Summary

We have provided a general description of infrared imaging systems in terms of characteristics, modeling, field performance, and performance measurement. The characteristics of infrared imagers continue to change. Significant changes have occurred in the past five years, to include the development of higher performance uncooled imagers and ultra-narrow field of view photon systems. Large format detector arrays are commercially available in the mid-wave and are becoming more available in the longwave. Still in the research phase are dual-band focal plane level. At first sight, it appears that the longwave flux characteristics are as good as a daytime visible system; however, there are two other factors limiting performance. First, the energy bandgaps of infrared photons are much smaller than those photons in the visible, so the detectors suffer from higher dark current. The detectors are usually cooled to reduce this effect. Second, the reflected light in the visible is modulated with target and background reflectivities that typically range from 7 to 20%. In the infrared, all terrestrial objects are emitting with an emission temperature of around 300 Kelvin. Typically, a two-degree equivalent black-body difference in photon flux is considered a high contrast target to background flux. The flux difference between two black-bodies of 302 K compared to 300 K can be calculated in a manner similar to that shown in Figure 4. This is the difference in signal that provides an image, so note the difference in signal compared to the ambient background flux. In the longwave, the signal is three percent of the mean flux and in the mid-wave, it is six percent of the mean flux. This means that there is a large flux pedestal associated imaging in the infrared. Unfortunately, there are two problems accompanying this large pedestal. First, photon noise is the dominant noise and is determined by the mean of the pedestal and is compared to the small signal differences. Second, the charge well storage in infrared detectors is limited to around 10^7 charge carriers. A longwave system in a hot desert background would generate 10^{10} charge carriers in a 33 millisecond integration time. Smaller F-numbers, spectral bandwidths, and integration times are used so that the charge well does not saturate. This results in SNR of 10 to 30 times below the ideal. It has been suggested that some on-chip compression may be a solution to the well pedestal problem. In many scanning FLIR systems, the pedestal is eliminated by AC-coupling the detector signals. Infrared focal plane array (IRFPA) readout circuits have been previously designed and fabricated to perform charge skimming and charge partitioning.

Another major difference in infrared systems, from that of visible systems, is the size of the detector and diffraction blur. For infrared photon detectors, typical sizes range from 25 to 50 μm, where visible systems can be fabricated with 3 μm detectors. Also, the diffraction blur for the longwave is more than ten times larger than the visible blur and mid-wave blur is eight times larger than visible blur. Therefore, the image blur, due to diffraction and detector size, is much larger in an infrared system than a visible system. Also, it is common for infrared staring arrays to be sampling limited where the sample spacing is larger than the diffraction blur and the detector size. Dither and microscanning are frequently used to enhance performance.

Finally, both infrared photon and thermal detectors in staring arrays have responsivities that vary dramatically and it is current practice to correct for the resulting nonuniformity (nonuniformity correction or NUC). The nonuniformity can cause fixed pattern noise in the image that can limit the performance of the system even more than temporal noise (especially in static imaging or stabilized target acquisition imaging).

Modeling Infrared Imagers

Otto Schade Sr. developed the earliest imaging system models and performance measures. His work describing television in the 1950s and 1960s, pioneered the way for the characterizations of imaging sensors used by engineers today. His performance measure for still pictures, moving pictures and television systems was based on an observer resolving a three bar periodic target.

John Johnson developed the technique of relating the acquisition of military targets in the field to laboratory measurements of resolvable bar targets. He divided the discrimination tasks into four categories: detection, orientation, recognition, and identification. This technique was termed an 'equivalent bar pattern approach'. It related performance on a simple test target to performance with complex object targets. Johnson viewed scale models and bar targets in the laboratory against a bland background. The smallest discernible barchart target yielded the maximum resolvable bar pattern frequency. These results, tabulated in Table 3 as cycles across the minimum dimension, were the basis for the discrimination methodology in widespread use today. Note that detection took only one cycle, but as the tasks got more specific or difficult, the requirement went as high as 8 cycles across the target minimum dimension.

Table 3 Johnson's criteria

Target	*Resolution per minimum dimension*			
Broadside view	*Detection*	*Orientation*	*Recognition*	*Identification*
Truck	0.9	1.25	4.5	8
M-48 Tank	0.75	1.2	3.5	7
Stalin Tank	0.75	1.2	3.5	6
Centurion Tank	0.75	1.2	3.5	6
Half-track	1	1.5	4	5
Jeep	1.2	1.5	4.5	5.5
Command car	1.2	1.5	4.3	5.5
Soldier (standing)	1.5	4.8	3.8	8
105 howitzer	1	1.5	4.8	6
Average	1 ± 0.25	1.4 ± 0.35	4.0 ± 0.8	6.4 ± 1.5

Table 4 Moser's data

Discrimination task	Line pairs/critical dimension
Detect ship	Aperiodic treatment
Classify as combatant	4
Recognize type	10

Recognizing that typical vehicle aspect ratios were somewhat limited, Johnson and Lawson conducted further experiments. Paul Moser conducted some of his own, reanalyzed Johnson and Lawson's, and developed the concept that this task was related to the average or critical dimension instead of the minimum dimension. This led to the conversion of line pairs to resolution elements, introducing the second dimension. Additionally, he performed a similar experiment on marine targets, which is summarized in Table 4. Lloyd and Sendall developed the MRT metric, which combines both resolution and sensitivity characteristics. This measurement of MRT is described in detail in a following article, but there is a theoretical model that is used to evaluate new sensor designs and concepts. It relates the minimum temperature difference between bar pairs at which they are just resolvable as a function of spatial frequency. MRT describes the infrared imager sensitivity as a function of resolution. More specifically, MRT is a measure of thermal contrast sensitivity as a function of spatial frequency.

Ratches *et al.* developed the NVL (US Army Night Vision and Electronic Sensors Directorate formerly known as the Night Vision Laboratory) Static Performance Model, which predicted the end-to-end performance. It started with the target signature and carried through to the observer. The MRT, a laboratory measurement or a modeled value, was related to the probabilities of discrimination through the target transfer probability function, cumulative percentages related to Johnson's criteria.

D'Agostino and Webb created the 3D noise model, both spatial and temporal considerations, for analyzing system noise. This technique divided the noise components into manageable and understandable components. It also simplified the integration of these effects into models.

The introduction of focal plane array (FPA) imagers has created a requirement to improve the model performance to account for the difference between scanning arrays and staring arrays. This change has made sampling an important area for improvement. A new model called NVTHERM is a result of the NVESD model improvement effort, which addresses undersampled imaging system performance.

Sensor characterization is seen in three ways: theoretical models, field performance, and laboratory measurements (Figure 9). Theoretical models are developed that describe sensor sensitivity, resolution, and human performance for the purpose of evaluating new conceptual sensors. Acquisition models, and other models, are developed to relate the theoretical models to field performance. This link allows theoretical models to be converted to field performance quantities (e.g., probabilities of detection, recognition, and identification). Field performance is measured in the field so that the theoretical models can be refined and become more accurate with advanced sensor developments. Since field performance activities are so expensive, methods for the direct measurement of sensor performance are developed for the laboratory. Field performance testing of every infrared sensor built, including buy-off, acceptance, and life-cycle testing, is ridiculous and out of the question. Laboratory measurements of sensor performance are developed such that, given these measurements, the field performance of a system can be predicted. Sensor characterization programs require accurate sensor models, field performance estimates with acquisition models, and repeatable laboratory measurements.

There are a few alternatives to the US NVTherm model. One candidate approach to undersampled imager modeling is Germany's TRM3, or the MDTP approach. The impact of undersampling in the image of a 4-bar target can readily be seen by simply observing the change in the image as a function of spatial frequency and phase. The spatial frequency is defined as line pairs per angular extent of the target, and the phase specifies the relative location of the target image to the detector array raster. These effects are obviously not independent of each other, but for each target there can be found an optimal phase where the observer can see the maximum amplitude modulation in the image of the target. MRT measurements in the past have utilized this variation with phase by allowing the observer to optimize the displayed image through target or system line-of-sight changes during the measurement process. For undersampled imagers, TRM3 addresses the problem of the MRT calculation's inability to predict beyond the half sample rate of the sensor, by replacing the MTF in the denominator of the MRT equation with an appropriately scaled term called the average modulation at optimum phase (AMOP). AMOP is the average signal difference in the image of the 4-bar standard pattern, with the test pattern positioned at optimum phase. AMOP oscillates between the presample MTF and the bar modulation. Beyond a frequency of 0.8 times the sample rate or 1.6 times the half sample arrays and quantum well detector systems. These systems will find their place in applications to include both military and commercial sectors.

Further Reading

Bijl P and Valeton MJ (1998) Triangle orientation discrimination: the alternative to minimum resolvable temperature difference and minimum resolvable contrast. *Optical Engineering* 37(7): 1976–1983.

D'Agostino J and Webb C (1991) 3-D analysis framework and measurement methodology for imaging system noise. *Proceedings of SPIE* 1488: 110–121.

Driggers RG, Cox P and Edwards T (1998) *Introduction to Infrared and Electro-Optical Systems*. Boston, MA: Artech House, p. 8.

Holst GC (1995) *Electro-Optical Imaging System Performance*. Winter Park, FL: JCD Publishing, p. 347.

Holst GC (1995) *Electro-Optical Imaging System Performance*. Winter Park, FL: JCD Publishing, p. 432.

Johnson J (1958) Analysis of image forming systems. *Proceedings of IIS* 249–273.

Johnson J and Lawson W (1974) Performance modeling methods and problems. *Proceedings of IRIS*.

Ratches JA (1973) *NVL Static Performance Model for Thermal Viewing Systems*. USA Electronics Command Report ECOM 7043, AD-A011212.

Schade OH (1948) Electro-optical characteristics of television systems. *RCA Review* IX(1–4).

Sendall R and Lloyd JM (1970) Improved specifications for infrared imaging systems. *Proceedings of IRIS* 14(2): 109–129.

Vollmerhausen RH and Driggers RG (1999) NVTHERM: next generation night vision thermal model. *Proceedings of IRIS Passive Sensors* 1.

Wittenstein W (1998) Thermal range model TRM3. *Proceedings of SPIE* 3436.

Interferometric Imaging

D L Marks, University of Illinois at
Urbana-Champaign, Urbana, IL, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Interferometric imaging is image formation by measuring the interference between electromagnetic signals from incoherently emitting or illuminated sources. To learn about interferometric image formation using coherent light, *see* **Holography, Techniques:** Overview. To understand what optical coherence is, *see* **Coherence:** Overview. To learn what kinds of sources produce incoherent light, *see* **Incoherent Sources:** Lamps. To learn about interferometric instruments, *see* **Interferometry:** Overview. To learn about interferometric instruments utilizing incoherent light, *see* **Interferometry:** White Light Interferometry. To better understand the effect of the coherence of light sources on image formation, *see* **Coherence:** Coherence and Imaging.

Interferometric imaging attempts to improve the resolution of images by interferometrically combining the signals from several apertures. By doing so, a resolution can be achieved that is superior to that achievable through standard image formation by any of the individual apertures. This is especially useful in astronomy, where resolving more distant and smaller stellar objects is always desirable. It is also finding increasing use in microscopy. It has several advantages over conventional noninterferometric imaging methods. The method can combine the light gathered from several imaging instruments to form an image superior to that which can be formed by any one of the instruments. It can also obviate the need to produce a single very large aperture to achieve the equivalent resolution, which in many cases is of impractical size. In addition, because it can produce a phase-resolved measurement, the data can be processed more flexibly to form a computed image estimate. There are also considerable disadvantages to interferometric imaging compared to conventional imaging methods. The amount of signal gathered is far less than could be gathered with an equivalent single aperture. It is difficult to mechanically or feedback stabilize the time delay between two widely separated apertures to obtain an accurate phase measurement. Often only a small bandwidth of the source light can be utilized, further reducing the available signal. The interference component of the combined signal can be very small. Typically an interferometric image must be computed from the data, rather than being directly measured on photographic film or an electronic focal plane array. Even with these disadvantages, interferometric imaging is frequently more feasible than building a single large aperture to achieve the highest available resolution images.

In contrast to interferometric imaging, a standard image forming instrument such as a telescope has a resolution limited by the telescope mirror aperture in the absence of aberrations and atmospheric turbulence. As telescope mirrors become very large, they become bulky, extremely heavy, and difficult to manipulate, as well as deform under their own weight and temperature gradients. However, adaptive optics is being more frequently utilized to dynamically correct for instrument aberrations as well as atmospheric turbulence. The images captured by telescopes are typically intensity-only images, which are amenable to image processing and deconvolution, but nevertheless lack phase information. Interferometric imaging is an alternative, where the resolution of a large aperture can be attained by measuring the interference between individual points of the electromagnetic field within an area equivalent to the large aperture extent. The interferometric combining of light from sub-apertures to achieve the resolution of a larger aperture is called aperture synthesis.

Unlike image formation by a lens, interferometric images are never physically formed. Conventional images are formed when diverging spherical waves emanating from sources are focused by a lens to converging spherical waves on a photographic film or an electronic sensor. In this case, the image information is directly contained in the exposure at each position on the sensor. Interferometric measurements contain the image information as statistical correlations between the electromagnetic fields at pairs of spatial points. The statistical properties of electromagnetic waves are modeled by optical coherence theory. Interferometric imaging works by measuring the statistical correlations between various pairs of points in the electromagnetic field, and then uses optical coherence theory to infer what the image of the source of the radiation is.

The light that emanates from most natural and many artificial sources is incoherent. Incoherent radiation is optical random noise. It is analogous to the sound of static heard on a radio receiving no signal. Because it is random, the fluctuations of the electromagnetic field produced by an incoherent source are completely unrelated to the fluctuations of any other source. The origin of the randomness is usually from microscopic processes such as the thermal motions of electrons or the spontaneous emission of an excited atom. Because these microscopic processes tend to act independently of one another, the light produced by different sources tends to be mutually incoherent. Because incoherent sources do not radiate a deterministic field, the average amount of power they radiate is usually specified rather than the field itself, which is random.

However, as the fields propagate away from their sources, the fields can become partially coherent. To see this, consider the light waves propagating away from a single point-like incoherent source. The field produced at the source point consists of random fluctuations in time, but these fluctuations travel outward in a spherical wave at the speed of light. The fluctuations of the field of any two points an equal distance from the source will be the same, or perfectly correlated, because they arrive from the source at the same time. This is illustrated in Figure 1a, where a random wave is emanated from a point incoherent source. Because of the complete correlation, we can say that these two points are fully spatially coherent.



Figure 1 The distance between incoherent sources and two field points determines the coherence between the field points. (a) Because there is only one source, the field everywhere is determined by the radiation of that source. Therefore, the same fluctuations of the wave arrive at two points an equal distance from the source at the same time, and produce identical fields at both points, and so are completely coherent. (b) Two field points are now the same distance from two incoherent sources. Because both sources contribute identical fields to both points (because the fluctuations of the wave from both sources arrive at both points at the same time), the superposition of the fields from both sources at both field points are identical, and so the fields are coherent. (c) Two field points are now near two sources. Because each field point receives radiation mostly from its nearby source and very little from the other source, the fields at each field point are almost completely mutually incoherent.

So while the source itself produces random noise, the fluctuations of the field at points distant from the source become correlated because they originate from the same source.

Partially coherent waves occur when the measured field contains a superposition of the fields from more than one incoherent source. If there are now two point sources instead of one, each field point in space will receive radiation from both sources. The amount of the contribution from each source to each point in space depends on the distance between the field point and the source. In general, because both sources can be different distances from the two field points, the fluctuations at the field points will not be the same. For example, two field points that are the same distances from both sources will be perfectly correlated, or coherent, because they receive the same combination of fields from both sources. This situation is illustrated in Figure 1b. However, if one considers two points that are near both respective sources, the points will usually receive light from the nearby source. Because the sources are incoherent, and each point is mostly receiving radiation from its closer source, these points will be nearly uncorrelated, as shown in Figure 1c.

A spatial distribution of incoherent sources radiating various amounts of power will create a pattern of correlations in the field remote from the source. By using interferometry, the correlation between pairs of field points remote from the sources can be measured. The interference between two points in the electromagnetic field is achieved by relaying the two fields (e.g., with mirrors) to a common location that has an equal travel time for the fields from both points, where the fields are superimposed. The power of the superimposed beams is then detected, by a photocathode, for example. If the two signals being combined are incoherent, then no interference will take place, and the total power measured on the photodetector is simply the sum of the power of the two signals. However, if the two signals are partially coherent, there will be a deviation in the measured power from the sum of the power of the two signals. The magnitude of this deviation relative to the power of the constituent signals indicates the degree of partial coherence of the signal.

An interferometer, such as depicted in Figure 2, gathers the light from two areas of the electromagnetic field remote from an object and combines them together at the same point to form an interferogram. In this example, two telescopes of a known separation gather light from a star. The primary mirror of each telescope is of insufficient size to resolve the star as anything but a point. However, a telescope is used in practice to collect enough light to produce a



Figure 2 Two telescopes receive radiation from a stellar object. The light is collimated and directed down the baseline to a point halfway between the telescopes, where the two images are interfered together onto a focal plane.



Incoherently superimposed images | Partially coherent images | Partially coherent images | Fully coherent images

Figure 3 The image of two interfering wavefronts from a point object with various states of coherence.

measurable interference signal. Each telescope primary mirror forms a point image of the star. At the image plane of each telescope a mirror directs the point image to a measurement plane equidistant between the two telescopes. This line that joins the two telescopes is called the baseline, and it is the baseline length rather than the individual telescope mirror size that determines the minimally resolvable size. The image from each telescope is superimposed by mirrors (or perhaps beamsplitters) and imaged onto a focal plane, to get an image similar to that of Figure 3. If the light arriving from one telescope is blocked, then the image formed looks like an Airy ring pattern formed by an image, a point-like object, which is the incoherent image of Figure 3. However, when both signals are allowed to interfere, the image will have vertical stripes superimposed on it. If these stripes are very prominent, so that the image is fully darkened inside the stripes, then an image similar to the rightmost image of Figure 3 is obtained, complete intereference is occurring and the two field points at which the telescopes are situated are coherent or completely correlated. If the stripes disappear, then no interference is occurring and the two field points at which the telescopes reside are incoherent. These examples are shown in Figure 3, with images of two superimposed points with varying degrees of coherence on the top row, and a line plot of the measured field through the center of the images in the bottom row. The degree to which the contrast of the stripes is enhanced by coherence is referred to as the ‘modulation’ and indicates the degree or magnitude of partial coherence.

In addition to having a degree of coherence, the correlation between two electromagnetic field points also has a relative phase shift. This phase shift is given by the relative position of the interference maxima, as shown in Figure 4. As the relative phase between the



Images with 0 degrees phase difference | Images with 90 degrees phase difference | Images with 180 degrees phase difference | Images with 270 degrees phase difference

Figure 4 The image of two interfering wavefronts from a point object with various phase differences between the two wavefronts.

fields collected by the telescopes changes (which is a function of the path length difference between the light arriving at the two telescopes), the peaks of the interferogram between the two telescope images shift position. By observing the depth of the formed interference fringes and the position of the fringes, both the amplitude and the phase of the correlation between the two field points can be simultaneously measured. The amplitude of the modulation and the phase of the interference are used to compute the complex degree of coherence that is used in the computation of interferometric images.

In practice, the phase of the complex degree of coherence is much more difficult to measure than its magnitude. This is because while the amplitude tends to change very slowly as the positions of the two correlated points change, the phase is sensitive to changes in relative path length on the order of an optical wavelength. Even though a long baseline produces better resolution, the baseline length must be known to a small fraction of a wavelength to obtain a meaningful phase measurement. Minute vibrations in the positions of the mirrors on the baseline can easily cause fluctuations in the path length greater than a wavelength. This is observed as wild oscillations in the position of the fringes on the image plane. In addition, atmospheric turbulence can also produce large random phase shifts. Achieving a stable phase measurement is one of the most challenging engineering aspects of interferometric imaging.

To model realistic sources, we must determine the coherence produced by sources of a finite size. Finite size incoherent radiators can be regarded as an arrangement of an infinite number of point-like incoherent sources radiating various amounts of power. When an interferogram is made of a field which has two superimposed incoherent sources, the power of the interferograms that each would make alone is added together, rather than the fields of the interferograms. This is because when the fields of the two sources interfere, the phases of both sources are varying randomly over time. The two fields will randomly vary between constructively and destructively interfering with each other. Over a long time, the constructive and destructive interference averages out to no interference. We can then calculate what the interferogram of many incoherent sources combined is by computing the interferogram of a point source and adding the power of many such interferograms together.

To figure out what the power of an interferogram of an arbitrary object is, first consider what the interferogram of a single point source is. Consider a situation depicted in Figure 5, but with a single point illuminator at the source plane positioned at (x,y,z) with radiant power I. We will have a receiving plane at a distance z from the source plane with two telescopes located symmetrically about the origin at $(\Delta x/2, \Delta y/2, 0)$ and $(-\Delta x/2, -\Delta y/2, 0)$. The fields received at the telescopes from the point will be interfered together at the center of the baseline, which is at the origin. We will assume that the point source produces a narrow band of radiation centered at wavelength λ. The point source produces a spherical wave that is received at both telescopes. The interference power is proportional to the two intensities measured at each telescope with the relative phase at the two telescopes causing constructive or destructive interference:



Figure 5 Diagram of source and telescope plane used for derivation of Van Cittert–Zernike theorem. A source at a distance z from the telescope plane has a power density $I(x,y)$. The telescope plane has two movable apertures symmetric about the origin of the telescope plane separated by $(\Delta x, \Delta y)$. The light from both apertures is directed to the center of the baseline at the origin of the telescope plane, where it is interfered on the sensor.

$$P \propto I_1 + I_2 + 2\sqrt{I_1 I_2} \cos \phi \qquad [1]$$

where I_1 and I_2 are the intensities of the field at each telescope, and ϕ is the phase difference between the two fields at each telescope. We will assume that the point (x,y,z) is very far away from the telescopes, and so the intensities at the two telescopes are equal and proportional to the point intensity I, so that $P \propto I(1 + \cos \phi)$. The phase ϕ is given by the difference in distance from the the source point at (x,y,z) to the receivers at $(\Delta x/2, \Delta y/2, 0)$ and $(-\Delta x/2, -\Delta y/2, 0)$. The phase is given by the difference in the Euclidean distances:

$$\phi = \frac{2\pi}{\lambda}\left(\sqrt{z^2 + (x + \Delta x/2)^2 + (y + \Delta y/2)^2} - \sqrt{z^2 + (x - \Delta x/2)^2 + (y - \Delta y/2)^2}\right) \approx \frac{2\pi(x\Delta x + y\Delta y)}{z\lambda} \qquad [2]$$

where the second term gives the difference in the distance to a first-order approximation in x and y. The interference intensity relation is then $P \propto I(1 + \cos(2\pi(x\Delta x + y\Delta y)/z\lambda))$.

If the source is now of a finite site, we can regard it as radiating an intensity (power per unit area) $I(x, y)$. To compute the total intensity of the interferogram, we integrate over all the sources in the source plane:

$$P(\Delta x,\Delta y) \propto \int I(x,y)(1+\cos(2\pi(x\Delta x+y\Delta y)/z\lambda))\mathrm{d}x\mathrm{d}y = \int I(x,y)\mathrm{d}x\mathrm{d}y + \int I(x,y)\cos(2\pi(x\Delta x+y\Delta y)/z\lambda)\mathrm{d}x\mathrm{d}y \qquad [3]$$

This result can be interpreted as follows. The intensity of the interference when the two telescopes are separated by a distance $(\Delta x,\Delta y)$ is proportional to the real part of the two-dimensional Fourier transform of the intensity distribution $I(x,y)$ evaluated at spatial frequencies $(\Delta x/z\lambda,\Delta y/z\lambda)$, plus a constant intensity. This result, related to the Van Cittert–Zernike theorem, is a commonly used result in interferometric imaging. It is covered in more detail in **Coherence:** Overview.

By moving the telescopes to various horizontal and vertical separations and measuring the interference intensity, the real part of the Fourier transform of the intensity is inferred. In practice the imaginary part can also be found by varying the baseline optical path length difference by a quarter wavelength. With these samples of the Fourier transform, the inverse Fourier transform computes the image intensity distribution $I(x,y)$. This is how simple computational image formation occurs with interferometric data.

One application of the Van Cittert–Zernike theorem and interferometric imaging is the measurement of the diameter of stars. When observing coherence, the correlations between field points tend to decrease as the separation between the points grows. By observing this decrease of the coherence, the angular size of a star can be measured. This method was pioneered by Albert Michelson in 1890 with the invention of the Michelson Stellar Interferometer. It is needed because the aperture size required to measure the angular diameter of most nearby stars in the Milky Way is larger than the size of most telescope apertures. Stars usually have a circular profile that produces a circularly symmetric pattern of correlations. The coherence between field points as the distance between them is increased does not decrease monotonically, but disappears at certain separations, and has many revivals. The first separation distance at which interference disappears (and the degree of coherence is zero) for a circular profile object is $\mathrm{d}_0 = 0.61\lambda/\alpha$, where λ is the wavelength of the light measured from the star, α is the angular diameter (in radians), and d_0 is the first separation from zero at which the interference disappears. In practice, each wavelength produces a null in interference at a different separation, so all but a small bandwidth of the star's light is filtered out before measurement to achieve a suitably strong interference null. For example, for the star Sirius, which has an angular diameter of 0.0068 arc seconds viewed from the Earth, measuring at a wavelength of $\lambda = 500$ nm (blue-green in the visible spectrum), the first separation distance at which no interference will be observed is at 18.5 m. This is larger than the largest available telescope aperture, and therefore an image cannot be directly formed that can resolve the size of Sirius.

Modern examples of stellar interferometry include the European Southern Observatory in Paranal, Chile, the CHARA Array at Mt Wilson, California, USA, and the NASA Jet Propulsion Laboratory Keck Interferometer in Hawaii, USA. The ESO main telescope system is the Very Large Telescope Interferometer (VLTI) consisting of four 8.2 m diameter telescopes as well as several smaller ones that can be moved independently, and will achieve milliarcsecond resolution through the interferometric combination of the telescopes. These telescopes are connected by underground tunnels through which the collected light from each telescope is combined. To measure the phase of the interference, extreme positioning precision is required in the relative delay between the light collected by the telescopes along the baseline, of 50 nm over 120 m, or 1 part in 2400 million, equivalent to 1.6 cm over the circumference of the Earth. Achieving this requires combinations of electronic and mechanical feedback systems with laser stabilized interferometric position measurement. The CHARA array has a very large 330-meter baseline, with 1-meter telescope apertures. The Keck Interferometer consists of two 10 m diameter telescopes with a baseline separation of 85 m. One of the main goals of achieving such high resolution is to be able to observe planets and planet formation around distant stars, to identify possible signs of life in other solar systems.

A similar principle is used for interferometric image formation in radio astronomy. The chief differences are the methods used to collect, detect, and correlate the electromagnetic radiation. Radio astronomical observatories, such as the Very Large Array in New Mexico, USA, and MERLIN at the Jodrell Bank Observatory in Cheshire, UK, use collection dishes and radio antennas to directly measure the electric field, which is not feasible at optical frequencies. These fields are converted to electrical voltages, which can then be directly correlated using electronic mixers, rather than detecting the correlation indirectly through interference. Because the wavelength is much larger, the stability requirements are greatly relaxed. Radio and optical frequency interferometric images are formed in essentially the same way, using the Van Cittert–Zernike theorem.

Interferometric imaging methods have also become of interest for microscopy applications. Aperture synthesis is not needed in microscopy, because the objects of interest are very small and therefore single apertures can be used to achieve diffraction-limited resolution. However, interferometric detection of partially coherent light affords greater flexibility because an image may be computed from the data rather than being directly detected. Typically this is achieved by creating an incoherent hologram of the object, typically through shearing interferometry. For example, by using a Rotational Shearing Interferometer, one can measure an incoherent hologram that can be used to produce a representation of an object with a greatly increased depth-of-field. In addition, direct detection of the partial coherence of sources can allow the methods of computed tomography to be used to produce three-dimensional images of volumes of incoherently emitting objects. Because of the versatility that interferometric detection can provide, interferometric imaging will surely be increasingly used outside of astronomy.

See also

Coherence: Coherence and Imaging; Overview. **Holography, Techniques:** Overview. **Incoherent Sources:** Lamps. **Interferometry:** Overview; White Light Interferometry.

Further Reading

Baldwin JE and Haniff CA (2002) The application of interferometry to optical astronomical imaging. *Philosophical Transactions of the Royal Society of London A* 360: 969–986.

Beckers JM (1991) Interferometric imaging with the very large telescope. *Journal of Optics* 22: 73–83.

Born M and Wolf E (1997) *Principles of Optics*. New York: Cambridge University Press.

Goodman JW (1996) *Introduction to Fourier Optics*. New York: McGraw-Hill Inc.

Goodman JW (2000) *Statistical Optics*. New York: Wiley-Interscience.

Mandel L and Wolf E (1995) *Optical Coherence and Quantum Optics*. New York: Cambridge University Press.

Marks DL, Stack RA, Brady DJ, Munson DC Jr and Brady RB (1999) Visible cone-beam tomography with a lensless interferometric camera. *Science* 284: 2164–2166.

Monnier JD (2003) Optical interferometry in astronomy. *Reports on Progress in Physics* 66: 789–857.

Potuluri P, Fetterman MR and Brady DJ (2001) High depth-of-field microscopic imaging using an interferometric camera. *Optics Express* 8: 624–630.

Thompson AR, Moran JM and Swenson GW (2001) *Interferometry and Synthesis in Radio Astronomy.* New York: Wiley-Interscience.

Lidar

M L Simpson and D P Hutchinson, Oak Ridge National Laboratory, Oak Ridge, TN, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Light detection and ranging (LIDAR) refers to an optical system that measures any or all of a variety of target parameters including range, velocity, and chemical constituents. Usually a LIDAR system consists of a transmitting laser source, transmitter optics, receiver optics, and a detector. Several configurations of LIDAR systems are possible, based on the type of laser source and detection scheme selected. Basically, sources can be continuous wave (CW), pulsed, or chirped. Sources that are CW are most often used to measure velocity or chemical constituents. Pulsed and chirped sources provide the additional capability of measuring range. LIDAR receivers are either incoherent (direct detection – amplitude only) or coherent (heterodyne detection – amplitude and frequency). Generally, for velocity detection, a coherent receiver with a local oscillator (LO) laser is required. A coherent receiver is also needed if a chirped laser source is used, for instance, in frequency modulation continuous wave (FM-CW) LIDAR.

For the special case of imaging LIDAR, the detector has multiple elements. In an imaging LIDAR system, the detector, or focal plane array (FPA), and the receiver optics are designed to image independent volumes in object space onto individual elements in the FPA. Each detector element, therefore, contains information for a specific volume in space and can be thought of as an independent LIDAR system. The advantage of an imaging LIDAR system is that multiple measurements can be made on extended target(s) at the same time. Thus, characterization of rapidly changing events (like wake vortices), speckle reduction by spatial averaging, synthetic aperture radar, multiple target tracking, and target identification are all possible without the sophisticated algorithms and hardware platforms required in single channel scanning systems. In addition because the multiple pixels allow parallel image capture, a true imaging LIDAR can acquire data much more rapidly than a scanning system.

In this chapter, for clarity, the emphasis will be on imaging LIDAR systems applied to hard body targets for the measurement of range and velocity. The basic configurations presented here, though, are extensible to distributed targets and measurements of wind profiles and atmospheric constituents. Also, since general textbooks are available that cover LIDAR systems and incoherent imaging systems, the concentration will be on architectures, optics, detectors, and design considerations that are specifically applicable to coherent imaging LIDAR.

Frequency Modulated Continuous Wave (FM-CW) LIDAR

One LIDAR technique, which is particularly suited for imaging due to the simplicity of the processing, is FM-CW LIDAR. FM-CW LIDAR simultaneously measures range and velocity (Doppler shift) by using a frequency chirped waveform. Referring to Figure 1, assume that a continuous wave (CW) laser frequency is linearly modulated (chirped) by a triangular wave about an offset frequency, such that the modulated signal is given as:

$$f(t) = f_o + \alpha\tau \qquad [1]$$

where f_o is the subcarrier offset frequency and α is the linear modulation rate in frequency/second, and τ is a time variable. The transmitted beam is focused by the optical system onto the target surface, reflected (or absorbed or scattered) and arrives at the receiver after τ seconds, where

$$\tau = 2\frac{R}{c} \qquad [2]$$

and R is the distance to the target surface, and c is the speed of light. The returning signal is optically mixed with the LO on the detector and produces a sum/difference beat frequency (Δf). Figure 1 shows the incident wave with its linear or chirped frequency characteristics and the delayed version returned from the target. Only the difference frequency can be optically detected since only it falls within the detector's bandwidth. Assuming the target is not moving, the result is

$$\Delta f = f(t+\tau) - f(t) = f_o + \alpha(t+\tau) - (f_o + \alpha t) = \alpha\tau \qquad [3]$$

where $\alpha = B/T$, the chirp rate of the modulator in units of Hz/s, B is the modulation bandwidth, and T is the period of the chirp. Substituting into eqn [3] for



Figure 1 Triangular-wave modulation Envelope on the transmitted beam (black) and return beam (gray).

τ and α we have

$$\Delta f = \frac{B}{T}\left(2\frac{R}{c}\right) \qquad [4]$$

Finally, one can solve for the distance to the target, R, as a function of the beat frequency and chirp rate:

$$R = \frac{cT}{2B}\Delta f \qquad [5]$$

The difference frequency, Δf, is the same for the up and down ramp of the modulation signal. Figure 2 demonstrates the return signal for the case of a target moving toward the LIDAR system. The difference frequency now contains a component proportional to the target induced Doppler shift given by

$$f_\mathrm{d} = 2\frac{v}{\lambda} \qquad [6]$$

where v is the line-of-sight target velocity and λ is the laser wavelength. From Figure 2, the Doppler shift causes the difference frequency on the up ramp to be less than the range induced frequency shift given by eqn [5] and the net difference frequency is greater on the down slope. In this case, the difference frequency is given by

$$\Delta f = \frac{B}{T}\left(2\frac{R}{c}\right) + f_\mathrm{d} \qquad [7]$$

The range and Doppler contributions to the difference frequency may be separated by measuring the frequency difference over both the up and down chirp of the waveform. The Doppler frequency $f_\mathrm{d} = \Delta f(\mathrm{up}) - \Delta f(\mathrm{down})$ and the range is given by the average of Δf(up) and Δf(down) over a complete cycle of the modulating triangular wave. Therefore, substituting in eqns [5] and [6], the range may be determined from the equation

$$R = \frac{cT}{2B}\left\{\Delta f(\mathrm{up}) - \Delta f(\mathrm{down})\right\} \qquad [8]$$

and the line-of-sight (LOS) velocity is

$$v = \frac{\lambda}{2}\left\{\frac{\Delta f(\mathrm{up}) + \Delta f(\mathrm{down})}{2}\right\} \qquad [9]$$

The range resolution of a FM-CW LIDAR system is the range for which the difference frequency equals 1 cycle in the sweep time interval of T or $\Delta f = 1/T$. Then, from eqn [5], the range resolution, ΔR, is given by

$$\Delta R = \frac{cT}{2B}\frac{1}{T} = \frac{c}{2B} \qquad [10]$$

Therefore, the range resolution is only a function of the sweep bandwidth and not the laser wavelength. However, the Doppler shift is dependent on the laser frequency. The accuracy with which the difference frequency may be determined is a function of the number of cycles over which the measurement is made. The number of cycles is maximized for the case of $\tau = T/2$ or T should be set for twice the time delay for the maximum range of interest.

Numerical Example

A range resolution of 30 cm requires a chirp bandwidth, B, of 500 MHz. For a total range of interest of 10 km, the chirp time, T, should be 133.33 μs or the chirp rate should be 3750 Hz (1 up and 1 down ramp per cycle). The difference frequency for a 10 km range target will be 250 MHz, which demonstrates the need for wideband detectors to capture high-resolution range images (Table 1).



Figure 2 Lidar return with Doppler shift proportional to target velocity.

Table 1 Summary of FM-CW LIDAR characteristics

Parameter	*Value*
Range resolution (m)	0.3
Chirp rate (Hz)	3750
Chirp bandwidth (Hz)	500×10^6
Maximum range (km)	10

Optical Configuration for Imaging LIDAR

Imaging LIDAR systems can be constructed for virtually any wavelength range with appropriate sources, optical components, and detectors. The design of an optical receiver system capable of recording coherent images requires additional considerations over those necessary for a video camera or single-channel receiver. First, the collection optics must have resolution capabilities consistent with both the detector grid dimensions and the coherence properties of the source. Next, the local oscillator (LO) power must be applied to each array element. For a typical infrared (HgCdTe) detector, one to ten milliwatts of LO power might be required to reach the shot noise limit. For large arrays, this may result in unacceptable heat loads, even for momentary application. Thus, detector arrays with substantial spacing between detector elements benefit from the application of individual LO 'beamlets' to shield the insensitive portions of the array substrate. These beamlets can be generated by illuminating a mask containing an array of holes with the LO Gaussian laser beam. This scheme is illustrated in Figure 3.

In the configuration shown in the figure, the signal beam (from the target) and the LO beamlets are combined at the beamsplitter prior to being focused onto the detector plane by the objective lens. The detector plane coincides with the far-field image plane of the objective lens, and any additional optical elements utilized to enhance the camera's resolution are not shown. An expanded LO beam illuminates an aperture array located at the far-field object plane of the ancillary lens. For instance, if the objective lens and the ancillary lens are identical, the LO mask is imaged onto the detector plane with unity magnification. The detector surface is assumed to be flat with uniform video and heterodyne quantum efficiency.

Several aspects of this design are discussed below. We first discuss how the optical parameters may be adjusted to give nearly-Gaussian LO profiles at each detector position. The receiver antenna array is then shown to consist of nonoverlapping sub-beams spaced with the detector array geometry. Signal considerations for both incoherent and coherent sources are then discussed, and it is found that optimal detector size and array-spacing is dependent on the coherence properties of the intended object field.

Aperture Array

As an alternative to holographic LO beam array generation, the LO mask design presented here consists of an array of apertures with size and spacing equal to the detector dimensions. The LO is expanded to coherently illuminate the entire mask with approximately uniform intensity. The mask is located at the front focal plane of the ancillary lens and its image is located at the back focal plane (detector plane) of the objective lens. The coherent image of the mask formed at the detector plane by the ancillary-objective lens combination can be described by a two-stage Fraunhofer diffraction process.

Finite dimensions of the ancillary pupil results in spatial filtering which can affect the image profile of the LO mask. If desired, the ancillary pupil may be chosen to provide nearly-Gaussian LO beamlet profiles with beam waists at each detector location.

It is useful to first consider the coherent image of a single aperture uniformly illuminated with plane LO wavefronts. In one dimension, this wave train diffracts from the aperture to form a far-field diffraction pattern at the Fraunhofer plane of the ancillary lens given by

$$E_{\mathrm{F}}(\beta) = E_{\mathrm{F}} \frac{\sin(\beta)}{\beta} \qquad [11]$$

where $\beta = \frac{1}{2} kb \sin(\theta)$, $k = 2\pi/\lambda$, λ is the wavelength, b is the aperture width, and θ is measured from the optical axis. For small θ, $\beta = \pi b \nu/(\lambda f)$ where ν measures a point on the Fraunhofer plane and f is the focal length of the ancillary lens. The finite diameter D (determined by an aperture stop in the Fraunhofer plane) of the ancillary lens spatially filters the diffraction pattern and this limits the range of β values in eqn [11]. We define an aperture-limited pupil as one which limits β to the range $-\pi < \beta < \pi$; this will be the case when $f/D = b/2\lambda$.

Consider now a linear aperture array consisting of N individual apertures of width b and separation $a > b$. Assume that each aperture is illuminated by plane, uniform, mutually coherent LO wavefronts of equal intensity. In this case, the LO profile at the Fraunhofer plane is characterized by the diffraction pattern for a coherently illuminated linear diffraction grating:

$$E_{\mathrm{F}}(\theta) = E_0 \operatorname{sinc}(\beta) \frac{\sin(N\alpha)}{N \sin(\alpha)} \qquad [12]$$

where $\alpha = \frac{1}{2} ka \sin\theta$ and where β, θ, and k are defined above.



Figure 3 The individual beamlets are generated by the local oscillator or aperture mask. Reproduced with permission from Simpson ML, Bennett CA, Emery MS, *et al.* (1997) Coherent imaging with two-dimensional focal-plane arrays: design and applications. *Applied Optics* 36: 6913–6920.

Propagation of the LO from the ancillary lens Fraunhofer plane to the detector plane can be described by applying the Fraunhofer diffraction integral to eqn [12] with integration limits appropriate to the ancillary pupil dimensions. The larger pupil gives increased illumination at the detector edges while the aperture-limited pupil gives a nearly Gaussian LO profile with 1/*e* points close to the detector edges.

Receiver Antenna Array

The requirement of wavefront matching between the LO field and the signal field leads to the notion of an 'antenna beam' or equivalently, 'backward propagating LO' (BPLO) to define the field of view of an individual heterodyne receiver element. This beam is formed by allowing a reverse projection of the local oscillator field to diffract from the detector surface, through all collection optics in the signal beam path to a point on the object field of the imaging system. A receiver array will produce an array of such BPLO beams which must maintain the detector array geometry in the object field if the LO and signal beams are to mix efficiently.

As above, spatial filtering by the receiver pupil (assumed to be located at the Fraunhofer plane of the objective lens) will affect the BPLO profile. In the Fraunhofer plane of the objective lens, the uniformly illuminated single-detector BPLO profile is given by eqn [11], and we define an aperture-limited detector as one which limits the range of β to $\pm\pi$. Similarly, eqn [12] characterizes the BPLO profile resulting from a detector array uniformly illuminated with an extended uniform LO wavefront. The uniform illumination BPLO profiles in the object field differ from the detector plane profiles only in horizontal scale which now is consistent with the magnified detector dimensions.

For our purposes, we may define the far field of the objective lens according to the condition for maximum Gaussian beam collimation:

$$\omega_d \omega_0 = \frac{f\lambda}{\pi} \qquad [13]$$

where ω_0 is an effective BPLO Gaussian beam waist at the Fraunhofer plane and ω_d is an effective BPLO beam waist at the detector. Under this circumstance, the BPLO Rayleigh range is $Z_D = \pi\omega_0^2/\lambda = f(\omega_0/\omega_d)$. Identifying ω_0/ω_d as the magnification (notice that for the BPLO, the magnification is greater than unity) gives $d_o = (d_i/f)Z_D \sim Z_D$ where d_o is the object distance and d_i is the image distance. Thus the far-field of the objective lens is at least one BPLO Rayleigh range away.

The object field BPLO profiles for an aperture-limited detector array consists of nearly Gaussian sub-beams with 1/*e* points located approximately at the magnified detector edge locations. Since the far-field object distance exceeds Z_D, the divergence of each BPLO sub-beam is constant and remains distinct and nonoverlapping for all $d_o > Z_D$.

Imaging Applications Involving Incoherent Sources

For an object plane in the far field of aperture-limited collection optics, the nearly Gaussian-profile BPLO propagates from the receiver aperture according to the condition for maximum Gaussian beam collimation. The waist is at the Fraunhofer plane where the BPLO wavefront is nearly plane, while at the object field the BPLO wavefronts are spherical with radius equal to

$$R(d_o) = d_o\left[1 + \left(\frac{Z_D}{d_o}\right)^2\right] \qquad [14]$$

where we have set $d_o - f \approx d_o$.

It will generally be the case that an imaging system will be used to analyze extended objects whose size exceeds the resolution limit. Following convention, we define a spatially coherent source as one which is illuminated with spatially coherent light with appreciable structure and roughness of depth within the coherence length of the illuminating light, and where the target motion does not appreciably perturb the speckle field during the measurement process. The speckle effects, which so seriously degrade the information content in images formed of spatially coherent objects, are not present in images formed of incoherent objects such as thermal emitters. Speckle may be reduced by time-averaging speckle fluctuations resulting from target motion, atmospheric effects, and independent transmitter pulses, and in the limit such objects become incoherent pseudothermal sources. Similar remarks apply to spatial averages over detector subarrays.

Independent radiators on the object field produce disturbances which can diffract to illuminate the entire receiver aperture as well as a finite coherence area in the image field A_{ci} given by

$$A_{ci} \gg \frac{\lambda^2}{\Omega_{ci}} \qquad [15]$$

where Ω_{ci} is the solid angle subtended by the receiver aperture at the image field. Alternatively, we may interpret A_{ci} as the area of an aperture in the object plane which, if illuminated with wavefronts characterized by eqn [14] (reciprocal illumination), would just fill the receiver aperture with a central diffraction order. Thus the combination of independent disturbances within the detector's field of view on the object plane, combine to form a spatially coherent disturbance over the receiver aperture and within A_{ci}.

According to the Van Cittert–Zernike theorem, the complex degree of spatial coherence μ_s is a unity amplitude wavetrain that propagates exactly as a signal beam resulting from the reciprocal coherent illumination of an object-field aperture of area A_{ci}. Thus, μ_s and the BPLO are Helmholtz-reciprocal pairs whose overlap determines the mixing efficiency with which heterodyne signal is generated from radiation collected from an extended incoherent source. Following convention, we refer to the overlap of μ_s and the BPLO as the effective receiver aperture.

Detectors larger than the aperture-limit, whose area exceeds A_{ci}, exhibit reduced receiver apertures and a corresponding decrease in heterodyne mixing efficiency. For example, varying the receiver pupil, while maintaining constant LO illumination, results in a heterodyne signal proportional to the received power for detector diameters much less than the aperture-limit, while detector diameters much greater than the aperture-limit produce heterodyne signal only in proportion to the square-root of the received power. Thus, for constant LO illumination and incoherent sources, increasing the entendue past the aperture limit will always increase the heterodyne signal, but less than for direct detection.

Optimal Detector Size

As noted above, an aperture-limited system is one where detectors of diameter d are matched with an objective lens with $f/D = d/2\lambda$. Commercially available detectors for use at 10 μm are commonly 100 μm wide suggesting the use of a $f/5$ lens, however aspheric lenses as fast as $f/1$ are also commercially available. Apart from aberrations, it would be advantageous to utilize a 5 × 5 subarray of 20 μm detectors with an $f/1$ lens in place of a single 100 μm detector for applications involving coherent sources. Applications involving incoherent thermal sources would generally favor a wide detector/fast lens combination since thermal sources provide weak heterodyne signals.

Noise Analysis and Performance

Radar Range Equation

The laser power requirements for the LIDAR system depend on the signal-to-noise ratio of the FPA, the i.f. amplifier performance, atmospheric transmission, and the optics system design. The following calculations are used to determine the performance of the LIDAR system for a single pixel of the FPA. The radar range equation is

$$P_r = P_t\left(\frac{G_t}{4\pi R^2}\right)\left(\frac{\sigma_{pt}}{4\pi R^2}\right)\left(\frac{\pi D^2}{4}\right)\eta_{atm}\eta_{sys} \qquad [16]$$

where P_r = received power; P_t = transmitted power; G_t = antenna gain; σ_{pt} = radar cross-section; R = range; D = transmitting and receiving aperture diameter; η_{atm} = atmospheric transmission; and η_{sys} = optical system efficiency.

The beam divergence of the transceiver is

$$\theta_t = \left[\left(\frac{D}{R}\right)^2 + \left(\frac{\lambda}{D}\right)^2\right]^{0.5} \qquad [17]$$

where λ = wavelength and the antenna gain is

$$G_t = \frac{4\pi}{\theta_t^2} \qquad [18]$$

The radar cross-section for a lambertian diffuse point target is $\sigma_{pt} = 4\rho_t dA$. The target reflectivity is ρ_t and dA is the target area, which is effectively the size of a pixel of the FPA projected onto the target. For purposes of the following calculations, a surface reflectivity of 0.1 is assumed. The pixel size at the target (assuming Gaussian beam optics) is given by

$$dA = \pi\left(\frac{D}{3}\right)^2\left[1 + \left[\frac{\lambda R}{\pi}\left(\frac{3}{D}\right)^2\right]^2\right] \qquad [19]$$

where D = transmitter and receiver mirror diameter and it is assumed that the target is larger than dA.

Finally, the signal-to-noise (SNR) ratio for a coherent receiver is given by

$$\mathrm{SNR} = \frac{\eta P_r}{h\nu B_{if}} \qquad [20]$$

where η = detector quantum efficiency; P_r = received power from eqn [16]; h = Planck's constant; ν = frequency of laser; and B_{if} = post-detection bandwidth of signal processor.

Numerical example

Assuming an atmospheric transmission efficiency, η_{atm}, of 98%, an optical system efficiency, η_{sys}, of 30%, and a detector efficiency, η, of 10%, the SNR was calculated as a function of the transmitting/receiving telescope (assumed to be a mirror) diameter, D, with target range as a parameter and plotted in Figure 4. This calculation assumed that the pixel field-of-view (FOV) at the target was illuminated with 1 watt of power. Even at a range of 10 km, the 32 × 32 element imaging LIDAR receiver with a SNR of 100 for each pixel will require only 75 watts (approximately 74-milliwatts per pixel) of total transmitted power for a mirror diameter of 30 cm. From Figure 4, it appears that the telescope mirror size could be reduced to a diameter of 20 cm and still maintain an excellent SNR. However, the SNR is not the only consideration on the transmitting telescope diameter. The cross-range target resolution is determined by the projected pixel size at the target. This target pixel size is plotted versus the telescope mirror diameter in Figure 5. Diffraction from the transmitting and receiving optic sets the limiting resolution that can be achieved with the LIDAR system and is only a function of the diameter and wavelength. A transmit/receive telescope aperture of 30 cm seems to represent a good trade-off between cross-range resolution and SNR.



Figure 4 The SNR saturates for a mirror diameter greater than 30 cm at long range.



Figure 5 The pixel size determines the target cross-range image resolution.

Applications and Future Directions

The remote sensing community has recognized the advantages of coherent receivers over conventional direct IR detection with respect to increased measurement sensitivity and multidimensional information capability. These advantages, however, come at a price of added system complexity, power, size, weight, and cost. In addition, choices of components, particularly in the long wavelength infrared (LWIR) region of the spectrum, have been limited to liquid nitrogen-cooled nonimaging detectors and table-top-sized gas lasers. Thus, implementations of imaging LIDAR systems have been primarily single detector, single source scanning systems which require high pulse repetition frequency lasers, complex tracking systems, and platforms, and augmentation of automated target recognition input to compensate for multiple, simultaneous measurements on the same target. New technology developments in quantum well infrared photodetector (QWIP) detectors and arrays, and in HgCdZnTe technology are now paving the way toward thermo-electrically cooled LWIR imaging array detectors. Also waveguide, folded cavity, laser resonator designs are providing compact, lightweight packages for CO_2 lasers. Coherent receivers, that use the new focal plane arrays and compact sources, provide the capability of making parallel LIDAR measurements without the added hardware and software overhead of scanning systems. In the following section, several examples are provided that demonstrate the versatility of imaging LIDAR systems that use detector arrays for measurement applications such as chemical plumes, velocity gradients, and speckle reduction.

Wideband heterodyne receivers are useful in measuring chemical species whose absorption peaks are not well aligned with the laser source line. If the species absorption peak corresponds directly with the laser line, an absorption measurement can be made using direct detection (amplitude only). For off-line (off-resonance) measurements, heterodyning is needed, where the bandwidth of the heterodyne receiver dictates how far away from the laser line an absorption peak can be measured. For example, the CO_2 laser line spacing in the 9 to 12 micron region of the spectrum averages around 50 GHz. With the new QWIP detectors theoretically having heterodyne bandwidths of 30 GHz or more, full high-resolution spectral coverage for the long-wave IR is within grasp. For chemical detection with heterodyne receivers, there are two modes of operation. The first is termed passive heterodyne radiometry where the source is a black-body radiator and the absorption is measured for chemical species located between the blackbody and the receiver. The second mode of operation is thermoluminescence where a laser transmitter is used to excite a chemical species in the atmosphere and the resulting emission (luminescence) is measured with the heterodyne receiver. The advantage of imaging in both cases is the ability to capture chemical plumes in the presence of wind and other anomalies.

To illustrate the ability of heterodyne imaging receivers to spectroscopically resolve chemical plumes, Figure 6 shows a series of 10 × 10 pixel images of a small bottle of concentrated ammonium hydroxide against a 212 °C blackbody recorded in both passive heterodyne radiometry and direct detection modes. Figure 6a shows a heterodyne image of the bottle with the top in place where, in Figure 6b the top is removed and the absorbing plume is clearly imaged. The heterodyne images in Figures 6a and 6b were recorded with the LO adjusted to emit the 9R(30) line which is known to


NH₄OH
(a) 9R30 Heterodyne: cap on
(b) 9R30 Heterodyne: cap off
(c) Video: cap off
(d) 10R20 Heterodyne: cap off

Figure 6 Ammonia plume characterization.

be absorbed strongly by NH_3. In Figure 6c, the same image was recorded by direct detection and fails to detect the ammonia plume. Similarly, in Figure 6d, the LO was adjusted to emit a nearby line known not to be absorbed by NH_3 and the plume is again not detected. Both the objective and ancillary lens were *f*/1 38 mm, and the object field was about three meters away. The top of the bottle was approximately 2 cm in diameter and is located at the bottom of the field of view. Measurements utilizing hot ammonium hydroxide imaged against a cold background resulted in similar images (albeit at substantially reduced signal to noise ratios) where the plume was bright and the background was dark.

Another use of imaging LIDAR is the measurement of velocity profiles. Applications include wake vortex measurements for aircraft, wind shear detection, and vibration signature measurements for identification. In another experiment, active mode images were recorded by illuminating the target with a portion of the LO laser beam which had been shifted in frequency by 40 MHz using an acousto-optic modulator. The resulting Doppler image is recorded using an 8 × 8 HgCdTe array with discrete electronics for each pixel element in the array. Figure 7 shows the active image of a vertical squirrel cage fan where each pixel is rendered to represent the peak Doppler shift measured with the detector at the corresponding location in the image plane. The moving target scatters incoherently and thus speckle effects do not degrade the image. The measured Doppler shifts are consistent with the known rotational velocity of the target.

Speckle effects associated with coherent mixing of laser light reflected from an extended target (constructive and destructive interference) are a major source of noise in LIDAR measurements. These speckle effects can be reduced by signal averaging. For single detector LIDAR, averaging over many transmitter pulses can reduce speckle but this technique also reduces temporal resolution. The alternative considered here is to sacrifice spatial resolution by averaging over an array of detectors, all of which record the signal returned from a single transmitter pulse. Detectors separated by a coherence area diameter will record signals that approach statistical independence, and in this case speckle effects can be reduced by an amount approaching the square-root of the number of detectors in the subarray.



Figure 7 Doppler image of a rotating squirrel cage fan.

The following laboratory experiment demonstrates speckle reduction by spatial averaging with a fixed focal plane array. The receiver used in this experiment consists of a 3 × 3 array of HgCdTe detectors. The 50-micron diameter detectors are arranged in a square pattern, with 100 micron center-to-center spacing. Custom electronics multiplex the output of each detector for subsequent processing. As with the velocity profile experiment, LIDAR illumination is produced by frequency shifting a portion of the LO beam by 40 MHz with an acousto-optic modulator prior to illuminating the object field. Polarization of the illumination beam in the experiment is parallel to the LO prior to scattering from the target. The measured receiver bandwidth, limited mostly by the dewar design, is about 100 MHz, which permits the acquisition of the 40 MHz heterodyne signal. The collection optic consists of a 38 mm *f*/2 asphere which produces a 2 mm diameter pixel image at a 3 m object distance.

The target for this experiment is a 30 cm diameter disk coated with an aluminum powder. The particle size of this powder ranges from 1 to 100 microns as determined by electron microscopy. The disk is attached to a stepper motor that is incremented between frames to provide statistically independent speckle fields. Figure 8 shows the distribution of



Figure 8 Speckle reduction using spatial averaging over a coherent array.

measurements taken with a single pixel superimposed on the distribution taken by averaging over the focal plane array. A reduction in speckle noise by a factor of the square root of the number of averaged pixels is obtained as predicted.

In this chapter, an overview of imaging LIDAR systems has been presented. Imaging LIDAR system design, performance, and application were discussed. With new technology developments in wide-bandwidth QWIP detector arrays, thermo-electrically cooled detectors, and compact sources, substantial potential exists for imaging LIDAR systems in the next generation in remote sensing. Due to the parallel, multifunction measurement capability of these new receivers a single sensor system can provide three-dimensional information, including range, shape, velocity, and chemical composition. In addition to the sensor fusion advantages, snapshot imaging allows the capture of high-speed, rapidly evolving events that elude present scanning systems.

See also

Environmental Measurements: Doppler lidar. **Imaging:** Infrared Imaging.

Further Reading

Born M and Wolf E (1964) *Principles of Optics*. London: Pergamon.

Forrestor AT (1956) On coherence properties of light waves. *American Journal of Physics* 24: 192–196.

Goodman JW (1975) Statistical properties of laser speckle patterns. In: Dainty JC (ed.) *Laser Speckle and Related Phenomena*, Chap. 2, pp. 9–75. New York: Springer-Verlag.

Haner AB and Isenor NR (1970) Intensity correlations from pseudothermal light sources. *American Journal of Physics* 38: 748–750.

Holzhauser E and Massig JH (1978) An analysis of optical mixing in plasma scattering experiments. *Plasma Physics* 20: 867–877.

Jelalian AV (1992) *Laser Radar Systems*, pp. 3–5. Norwood, WA: Artech House.

Kogelnik H and Li T (1966) Laser beams and resonators. *Applied Optics* 5: 1550–1566.

Kusters JF, Rye BJ and Walker AC (1989) Spatial weighting in laboratory light scattering experiments. *Applied Optics* 28: 657–664.

Martienssen W and Spiller E (1964) Coherence and fluctuations in light beams. *American Journal of Physics* 32: 919–926.

Measures RM (1984) *Laser Remote Sensing Fundamentals and Applications*. New York: John Wiley.

Rye BJ (1979) Antenna parameters for incoherent backscatter heterodyne lidar. *Applied Optics* 18: 1390–1398.

Shannon RR (1997) *The Art and Science of Optical Design*. New York: Cambridge University Press.

Siegman AE (1966) The antenna properties of optical heterodyne receivers. *Applied Optics* 5: 1588–1594.

Simpson ML, Bennett CA, Emery MS, *et al.* (1997) Coherent imaging with two-dimensional focal-plane arrays: design and applications. *Applied Optics* 36: 6913–6920.

Veldkamp WB (1983) Holographic local oscillator beam mutiplexing for array heterodyne detection. *Applied Optics* 22: 891–900.

Veldkamp WB and Van Allen EJ (1983) Binary holographic LO beam multiplexer for IR imaging detector arrays. *Applied Optics* 22: 1497–1506.

Zernike F (1938) The concept of degree of coherence and its application to optical problems. *Physica* V8: 785–795.

Multiplex Imaging

A Lacourt, Université de Franche-Comté, Besancon, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The ability to project an image onto a screen in a darkened room has been known since antiquity and Leonardo da Vinci (1515) precisely described principles of the Camera oscura. When one exposes a paper sheet directly to sunlight, it is uniformly lighted. However, if one pierces a little hole through the paper sheet then an image of the sun can be displayed on a screen beyond the hole (Figure 1). Similarly, the shape of the light spot we can see in a dark room, from the rays passing through a small aperture of a closed shutter, is not that of the aperture. Generally, the spot has a circular shape, as an image of the sun. Actually, it is neither a shadow of the hole nor an image of the sun but a combination of both. Light incident on an aperture contains the entire information about the light distribution of the object, but this information has to be 'deblurred', or decoded. The aperture acts as an elementary spatial 2D-filter that selects and preserves the direction and intensity of light rays coming from each point of the scene. The projection on the screen of each pencil of light passing through the hole is a small light spot, the geometry of which is the same as the aperture, and



Figure 1 Principle of darkroom.

the intensity is proportional to that of the emitting point. The smaller the hole, the more detail the image exhibits, but with less luminosity. Thus, we must adopt a compromise between the resolution and the illumination of the image.

Now, if the mask has several holes, the amount of light reaching the screen, being proportional to the whole aperture area, is extensively increased. On the other hand, as each hole displays an image on the screen, the overlapping of these multiple images gives a new but blurred image. However, the information exists and we should be able to retrieve it if we know the characteristics of the complex aperture. This is the basic concept of multiplex imaging. The crucial question is: what is a good aperture design and a good way to reconstruct images having high resolution and with high illumination levels? The suitable masks with this aim are named synthetic apertures.

Porta (1589) and Kepler (1611) found the perfect solution, by setting up a lens in front of a large hole. Indeed, one can regard a lens as a wide aperture made of continuously juxtaposed microprisms (Figure 2). The lens obtains such refractive properties that the image displayed by each of these microprisms is moved toward a center. Moreover, as the angle of the microprisms varies continuously, it focuses on a single point, all the rays coming from a given object point. Thus, the blurring is suppressed and the illumination is increased. The way was opened toward the invention of optical instruments and photography and the 'pinhole' has fallen into oblivion for a long time.

Two new problems awake interest in synthetic apertures, around 1960. First, the domain of imaging has extended out of visible light: infrared and ultraviolet light, γ-rays, X-rays, ultrasound waves, and others. Materials suitable for making lenses or mirrors, operating with such waves, are expensive or often do not exist. For example, most of the transparent materials have a refractive index close to 1 for γ-rays and X-rays. However, some are opaque enough to enable the use of masks.



Figure 2 A lens can be modeled as a juxtaposition of microprisms with continously variable angles.

The second challenge appeared with progress in astronomy. In order to explore the universe more, further from Earth and closes to the Big Bang, astrophysicists needed telescopes providing very high luminosity and high resolution, since distant stars, nebulae, and other galaxies are extremely weak and small luminous objects. This exploration can be achieved by increasing the diameter of the primary mirror of telescopes. Indeed, due to diffraction of light by the pupil of the primary mirror, the theoretical limit of resolution of a telescope (i.e., the smaller distance between two points that one can discriminate), is inversely proportional to the diameter of the mirror. In addition, the illumination is proportional to its area. However, the working of large mirrors is a technical prowess that is very expensive and has high risks. Defect of a fraction of micrometer when polishing the surface can have dramatic consequences, e.g., Hubble. Also, such mirrors, being heavy, can bend out of shape under their own weight. Nevertheless, outstandingly large telescopes have been implemented, based on Adaptive optics: the deformations of the mirror are measured in real time by an interference method and compensated by activating a mosaic of jacks (New Technology Telescope – NTT – European program, 1989). Another way consists in replacing the solid-state mirror by a mosaic of 36 mirrors accurately directed (Keck telescope, USA). However, in either case, the mirror diameter does not exceed 8 to 10 meters. Synthetic apertures could be a solution to that difficulty, as earlier demonstrated by Fizeau (1868) and Michelson (1890).

In the first part of this article, any fundamentals are briefly recalled about properties of light and imaging.

The second part describes recent experimental methods and results obtained in synthetic aperture imaging. The last part reports the important programs in progress today relating to stellar interferometry.

Background

Electromagnetic Waves Propagation

Light power, which is involved in image formation, is carried by the electric field of an electromagnetic wave (Figure 3). The electric field $\vec{E}$ has properties of a vector orthogonal to the direction of propagation $\vec{N}$ of the light ray. It is characterized by its amplitude $\vec{E}_0$, the angular time frequency of vibration ω, and the wavevector $\vec{k}$, which specifies the propagating direction of the ray. Let $P(\vec{d})$ be a current point on a plane wavefront, defined by the position vector $\vec{d}$ from the origin of the reference frame. The electric field propagation of a monochromatic wave is expressed as:

$$\vec{E}(\vec{d}, t) = \vec{E}_0 \exp[\mathrm{i}(\vec{k}\cdot\vec{d} - \omega t)] \qquad [1]$$

The light power carried by the electromagnetic field is proportional to $I = \|\vec{E}_0\|^2 = \vec{E}\cdot\vec{E}^*$ where $\vec{E}^*$ is the complex conjugate of $\vec{E}$. The time frequency $\nu = \omega/2\pi$, or the wavelength $\lambda = c/\nu$, where c is the electromagnetic wave celerity, characterize the hue of the light. The wavevector $\vec{k} = \vec{N}\omega/c$, where $\|\vec{N}\| = 1$ is an angular space frequency vector, as $\vec{n} = \vec{N}/\lambda = \vec{N}\nu/c$ is a space frequency vector. We have $\vec{k} = 2\pi\vec{n}$. As λ is a constant for a given monochromatic light, $\vec{n}$ defines the direction of propagation of a ray.

Spatially Coherent Light

Consider a very small source stated as the point source S_1, emitting uniform lightwaves in any direction (Figure 4). The wave reaching a farfield point, P, from S_1, propagates along a direction defined by the wavevector $\vec{k}_1$. The vectors $\vec{k}_1$ and $\vec{d}_1 = \overrightarrow{S_1P}$ are collinear. Another point source, S_2 is characterized from P by the wavevector $\vec{k}_2$, such that $\vec{k}_2$ and $\vec{d}_2 = \overrightarrow{S_2P}$ are collinear. When the distances d_1 and d_2 are close to each other, the amplitudes $\vec{E}_{01}$ and $\vec{E}_{02}$ of the waves at P are proportional to those of the corresponding emitting sources, S_1 and S_2. According to the principle of superposition, the resulting field at the point P, $\vec{E} = \vec{E}_1 + \vec{E}_2$, and the instant wavevector $\vec{k}$, are unique vectors.



Figure 3 Electromagnetic wave propagation.



Figure 4 Spatially coherent light.

If S_1 and S_2 are two synchronous sources, the amplitude $\vec{E}_0$ of $\vec{E}$ and the wavevector $\vec{k}$ are constant versus time at any point P. This is still the case when an extended object is made of an arrangement of synchronous points. That situation defines a spatially coherent object. Thus, one cannot recover multiple data about the object's distribution, from the field framework at a single point P, since the relationship between the two is multi-unequivocal. Nevertheless, due to diffraction, one can retrieve them by knowing the complex amplitude distribution of light on a set of wavevectors available over an extensive area of a screen. Let $\vec{E}_0(\vec{r})$ be the amplitude of the electric field at the object point $M(\vec{r})$ and let $\vec{E}_0(\vec{n})$ be the one diffracted by the object to farfield toward the direction corresponding to the space frequency $\vec{n}$. Fourier transforms give the connection between $\vec{E}_0(\vec{r})$, and $\vec{E}_0(\vec{n})$:

$$\left\{ \begin{aligned} \vec{E}_0(\vec{n}) &= \int \vec{E}_0(\vec{r}) \exp[\mathrm{i}2\pi\vec{n}\cdot\vec{r}]\mathrm{d}\vec{r}, \\ \vec{E}_0(\vec{r}) &= \int \vec{E}_0(\vec{n}) \exp[-\mathrm{i}2\pi\vec{n}\cdot\vec{r}]\mathrm{d}\vec{n}. \end{aligned} \right\} \qquad [2]$$

This is the situation encountered when an object is illuminated by a laser or by a point source such as a single star.

Spatially Incoherent Light

When the point sources S_1 and S_2 are independent – spatially incoherent – both wavevectors $\vec{k}_1$ and $\vec{k}_2$



Figure 5 Spatially incoherent light.

coexist at the point P, each characterizing the angular position of S_1 and S_2 (Figure 5). If S_1 and S_2 are part of an extended intensity distribution $I_0(\vec{r})$, fans of wavevectors and fields are mixed at P, each coming from an independent point source S. Together, they carry the whole data on the object distribution. Those data are partially uncorrelated at any two points P and P' on a screen, related to the different optical paths from any point S to P and P' and to the finite time of coherence of light. The correlation between data available to farfield in two directions $\vec{n}$ and $\vec{n}'$ from the object, is given by the mutual intensity function, $\Gamma(\delta\vec{n}) = \int \vec{E}(\vec{n})\cdot\vec{E}^*(\vec{n}+\delta\vec{n})\mathrm{d}\vec{n}$, where $\delta\vec{n} = \vec{n}' - \vec{n}$. Fourier transforms give the relation between $I_0(\vec{r})$ and $\Gamma(\delta\vec{n})$:

$$\left\{\begin{array}{l} \Gamma(\delta\vec{n}) = \displaystyle\int I(\vec{r})\exp[\mathrm{i}2\pi\delta\vec{n}\cdot\vec{r}]\mathrm{d}\vec{r}, \\ I(\vec{r}) = \displaystyle\int \Gamma(\delta\vec{n})\exp[-\mathrm{i}2\pi\delta\vec{n}\cdot\vec{r}]\mathrm{d}\delta\vec{n} \end{array}\right\} \qquad [3]$$

Therefore, by drawing a map of $\Gamma(\delta\vec{n})$, one can recover the object distribution $I_0(\vec{r})$ by a Fourier transformation. Most of time, one uses the spatial degree of coherence function, $\gamma(\delta\vec{n}) = \Gamma(\delta\vec{n})/\Gamma(\vec{0})$. When the object illuminates a screen, at a large distance d, the degree of coherence of light between two points P and P' on the screen is $\gamma(\delta\vec{\rho}/\lambda d)$, with $\delta\vec{\rho} = \overrightarrow{PP'}$. The 2D extension of $\gamma(\delta\vec{\rho}/\lambda d)$ defines the area of coherence of light on the screen. The width of the area of coherence, $\Delta\rho$, and that of the object distribution, Δr, are inversely proportional:

$$\Delta\rho\cdot\Delta r \sim \lambda d \qquad [4]$$

If a mask perforated by two pinholes, separated by a distance $\delta\vec{\rho}$, replaces the screen, one can observe Young fringes of interference beyond the mask, the visibility of them being precisely $\gamma(\delta\vec{\rho}/\lambda d)$. Therefore, one can built a map of $\gamma(\delta\vec{\rho}/\lambda d)$ versus $\delta\vec{\rho}$ from a set of 2D measurements of visibilities of fringes, then reconstruct the object distribution by a Fourier transformation.

Notice that the entire data of the object distribution is available from a single coherence area. That is, a pinhole covering exactly one area of coherence would select the entire available data from the object and would display to farfield the most accurate image possible. Generally, such a pinhole is so small that practically no light passes through it. However, we can regard each area of coherence as an independent channel of information. Then an imaging device based on a juxtaposition of such reduntant channels can be considered as a multiplex imaging device.

Self-luminous objects such as extended or double stars, and artificial thermic sources are spatially incoherent sources.

Multiplex Imaging

Methods of multiplex – or lensless – imaging are performed either with coherent of incoherent light. The very different properties of the two types of light leads to completely different methods, even if all are related to holography. Holography with coherent light is an interference method for local recording of both the direction and modulus of the wavevectors and the amplitude of the field contained in many juxtaposed grains of speckle, scattered by the object. Each grain is an independent channel of imaging.

Synthetic Apertures with Spatially Incoherent Objects

As interferences are impossible by this method with incoherent light, we must improve other methods of imaging. Synthetic aperture is a concept consisting of using a redundant multichannel system to increase the luminosity of images without loss of resolution. The basic principle is that of a multiple holes darkroom. The processing is in two steps: recording and reading the image. The recording step consists in illuminating a photosensitive receptor with the object through a mask (Figure 6). Generally, the receptor is a



Figure 6 Principle of synthetic aperture: recording.

photographic plate. Obviously, the light distribution on the plate is blurred. Indeed, any elementary transparencies on the mask project on the receptor inverted images of the object located the shadow of the mask. Such a distribution is expressed by a convolution. Let $O(x, y)$ be the conical projection of the object on the receptor and $Z(x, y)$ that of the mask. The shadows distribution on the receptor is (the variable being normalized):

$$I'(x', y') = Z(x, y) * O(x, y) = \int Z(x, y) O(x' - x, y' - y) \mathrm{d}x\, \mathrm{d}y \qquad [5]$$

The reading step is a decorrelation processing from the recorded intensity (Figure 7). It consists in achieving a new correlation of I' with an arbitrary function T:

$$I''(x, y) = T(x, y) * [Z(x, y) * O(x, y)] = [T(x, y) * Z(x, y)] * O(x, y) \qquad [6]$$

$R[x, y] = [T(x, y) * Z(x, y)]$ is the system point spread function (SPSF) of the processing. It expresses the image distribution of a single-point. The perfect image is obtained when $R(x, y)$ is a 2D *Dirac* – or *delta*– distribution, $\delta(x, y)$:

$$R(x, y) = \delta(x, y), \quad \text{as} \quad \int \delta(x, y) O(x' - x, y' - y) \times \mathrm{d}x\, \mathrm{d}y = O(x', y') \qquad [7]$$

Fresnel zone plates

First Mertz and Young used Fresnel zone plate (FZP) as a synthetic aperture for X-ray imaging purposes. FZPs are made of alternate transparent and opaque concentric crowns of equal area. The radius of the nth circle is $r_1\sqrt{n}$, r_1 being the smallest. When illuminated by a cylindrical light beam, the FZP is a multiple foci diffractive lens (Figure 8).



Figure 7 Synthetic aperture: reading.

The reading step is either analogical or numerical. Through the analogical method, we consider the recorded plate as a pseudohologram (Figure 9). When the ‘shadowgram’ is lighted with a parallel beam of laser light, the FZPs recorded around each point concentrates the light on its foci. Then an image of the object is reconstructed on the focal planes; a method that is simple and elegant. Nevertheless, the processing is not linear since we record an intensity distribution at the recording step, while the reading step by diffraction involves amplitude. Moreover, the S/N ratio decreases as the amount of data increases, recorded on the photographic plate because of its finite dynamic.

Mertz and Young had the idea of using a second FZP to perform the deconvolution processing by optical methods. In this case, the SPSF, $R(x, y)$, is the autocorrelation function of the FZP transparency (Figure 10). It presents a narrow central peak, emerging from a pyramidal ground (Figure 11). The optical setup is the same as the recording step.



Figure 8 Properties of FZP.



Figure 9 Recording and analogical reading with a FZP.



Figure 10 Optical decorrelation.



Figure 11 System point spread function with a Fresnel zone plate.

The FZP scale factor only must be adjusted to compensate for the magnification ratio generated by the conical projection at the recording step.

In either digital or analogical deconvolution, the image reconstructed is accurate, with good sharpness, if the number of zones is sufficient. Ceglio *et al.* obtained relevant images of 8 μm targets with FZP having 100 zones. Nevertheless, the multiple foci of FZP induces decreasing of the S/N ratio which is an important limitation. Besides, we pointed out above that the larger the object, the more the decrease in the S/N ratio.

Random and uniformly redundant arrays

Dicke and Ables substituted a random array to the FZP. The mask is made of randomly distributed holes and the expected advantage is doubled. First, one can reduce the transparent area of the mask by less than 50% in order to increase the S/N ratio when the object is wide. Second, the autocorrelation function of such an array is theoretically a Dirac distribution when its width is infinite. Thus, one can hope to narrow the system point response. However, when the width is finite, the pyramidal ground of the point response mentioned above is present and the advantage is not clearly demonstrated. In order to correct this effect, Chris Brown used a 'mismatched' function, for the postprocessing deconvolution. This function is calculated, first by achieving the complement of the recording mask function, then subtracting from it. Thus, the 1 transparencies result in +1 while the 0 transparencies are changed by −1. Brown shows images digitally reconstructed of X-ray sources, 30 sec. of arc wide. Fenimore and Cannon conceived a uniformly redundant array. The center random motif of the mask is half replicated on each side with only the center area being used for the recording step. The deconvolution is calculated by taking into account the whole area in a mismatched way. The result is an exact delta function. The authors show images of 200 μm-wide microspheres with a similar resolution but a signal 7100 times stronger than with a comparable pinhole camera.

Theta Rotating Interferometer

The theta shearing interferometer enables us to record complete data from the Fourier transform of a spatially incoherent object (Figure 12). The source can be any natural one, but monochromatic. This is easily practicable using a good filter or monochromator.

The device is based on a Michelson interferometer, the plane mirrors being replaced by two roof prisms. One of the roof prisms is fixed so the other can rotate around the axis of the interferometer. As a result, we have two images of the object. Let θ be the angle between the two edges of the prisms. The angle between the images is 2θ. Since the original object is noncoherent, and two homologous points being mutually coherent, the light they emit interferes, resulting in fringes.

The intensity, space frequency, and direction of the fringes characterize the intensity and the position of the point source. One shows that the farfield visibility distribution of fringes $V(\delta\vec{n})$ and the object distribution $O(\vec{r})$ are related by Fourier transforms:

$$\left\{\begin{aligned} V(\delta\vec{n}) &= \int O(\vec{r})\exp\left[\mathrm{i}2\pi\frac{\delta\vec{n}\cdot\vec{r}}{2\sin\theta}\right]\frac{\mathrm{d}\vec{r}}{2\sin\theta}, \\ O(\vec{r}) &= \int V(\delta\vec{n})\exp\left[-\mathrm{i}2\pi\frac{\delta\vec{n}\cdot\vec{r}}{2\sin\theta}\right]\mathrm{d}\delta\vec{n} \end{aligned}\right\} \qquad [8]$$

Then, one can see that the visibility of the interference pattern is an image of the degree of coherence $\gamma(\delta\vec{n})$, with a scale factor $1/2\sin\theta$.

Such a pattern recorded on a photographic plate is a Fourier hologram of the noncoherent object. An image can be reconstructed by diffraction at infinity or near a focus (see Figure 13, examples performed in 1972 by the author). The technique was successfully applied to the determination of the modulation transfer function of optical systems. C Roddier and F Roddier applied the method to astronomy.



Figure 12 Theta shearing interferometer.



Figure 13 Incoherent light holograms.

For instance, they examined Alpha Orionis and discovered the evolution of its dust envelope and the possible existence of a companion.

High Resolution Imaging in Astronomy

In astronomy, the limit of resolution depends chiefly on two factors. The first is a technical one. Adaptive optics and very large telescopes (VLT) brought spectacular progress to clarity and resolution of telescopes. The 8.2 m VLT of Kueyen set up in 1989, shows images easily resolved of HIC 69495 Centauri, separated by 0.12 sec. of arc. Nevertheless, working of large mirrors for telescopes reaches its limits. Therefore, their clarity remains too weak. On the other hand, atmospheric turbulences make the refractive index of air unstable and the position of the images in the focal plane of telescopes unsettled. Thus, the point response is a granular spot named 'speckle'. Short exposure times relieve that inconvenience, but they prohibit the observation of weak stars. In 1970, Labeyrie proposed a method of speckle interferometry consisting of a statistical analysis of a set of speckles. The result is a display of a diffraction-limited image. He resolved many tens of single and double stars. Only Hubble, above the atmosphere, is able to do it by direct imaging. However, the primary mirror of Hubble being only 2.40 m wide, has clarity much lower. Stellar interferometry is a very promising alternative solution.

Principles of Stellar Interferometry

Stellar interferometry is based on eqn [3]. The light emitted by double or wide stars is noncoherent, so that one can access an image of them trough 2D measurements of the degree of coherence of light. We showed above that one could achieve this by using interference devices such as Young holes. Eqn [3] shows that if we measure the visibility of Young fringes at increasing distances $\delta\rho$ between the pinholes, the distance $\Delta\rho$ from which the visibility is zero gives the angular width of the star, $\Delta\alpha$, under the formula:

$$\Delta\rho \cdot \Delta\alpha \sim \lambda \qquad [9]$$



Figure 14 Stellar interferometer of Michelson.

where $\Delta\alpha = \Delta r/d$. In the case of a double star, the visibility varies periodically versus $\delta\rho$ when the pinholes are aligned along the axis of two stars. Let $\Delta\alpha$ be the angular distance between the stars: the smallest distance $\Delta\rho$ for which the visibility is zero is given by:

$$\Delta\rho \cdot \Delta\alpha = \lambda/2 \qquad [10]$$

The larger the uttermost distance between the holes, the more the limit of resolution of the processing is potentially sharp.

In order to exploit this idea, Stephan placed and rotated a mask with two holes in front of the objective of a refractive telescope. He established that the diameter of the stars he observed was much less than 0.16 sec. of arc. Then, Michelson built up, on top of a 30 cm refractive telescope, a stellar interferometer consisting of two arms catching the light at 7 m of distance from each other (Figure 14). He measured correctly the diameter of the satellites of Jupiter. Hale carried the distance of the base up to 15 m in 1920.

The Two Telescopes Interferometer of Labeyrie

In 1975, Labeyrie improved the idea by setting up two separate 25 cm diameter Cassegrain-coudé telescopes on a 12 m baseline, oriented north–south (Figure 15). The setting and mechanical stability of the device are extremely sensitive. The tolerances do not exceed any μm. A mobile table near the common focal plane of the two telescopes compensates for the optical path differences due to stars tracking. In spite



Figure 15 The two telescopes interferometer of Labeyrie.

of the acute difficulties, he succeeded in observing fringes on Vega. He obtained a resolution of 0.01 sec. of arc versus 0.5 sec. with a single 25 cm telescope. Later, one telescope was rendered mobile bringing the base width variable between 4 and 67 m. The resolution reaches up to 0.00015 sec. of arc. Note that the rotation of Earth also enables east–west analysis with resolution of 0.005 sec., and today, the 25 cm telescopes are replaced by 1.5 m ones.

The Very Large Telescope Interferometer (VLTI)

The two telescopes interferometer of Labeyrie is a first step toward a very ambitious project: the telescope at synthetic aperture and very large base. Proofs of reliability of such a principle was already given by the very large array (VLA) experimented in radio astronomy. Labeyrie with Lena, and the team of the ESO (Ecole Supérieure d'Optique, Paris), imagined a very large telescope interferometer (VLTI) made of 6 telescopes of 2 m, in a 2D structure on a base of 100 m. The European VLTI was built at Cerro Paranal. It is made of four 8.2 m telescopes corrected in real time by adaptive optics (NTT technology) and three 1.8 m telescopes. The fourth 8.2 m telescope was put in service in 2001. Some days, each of the 8.2 m telescopes used separately gives a resolution close to that of Hubble. However, the clarity is much better because of the larger primary mirror diameter (8.2 m against 2.4 m). In May 2003, the team of J-G Cuby observed a galaxy the farthest away ever seen, only 900 millions years old since the Big Bang. Obviously, a drastic gain of resolution (by a factor 10) is expected from the interference configuration.

See also

Coherent Lightwave Systems. **Diffraction:** Fresnel Diffraction. **Imaging:** Adaptive Optics; Interferometric imaging. **Instrumentation:** Telescopes. **Interferometry:** Overview.

Further Reading

Labeyrie A (1976) High resolution techniques in optical astronomy. In: Wolf E (ed.) Progress in Optics, vol. XIV, pp. 49–85. New York: North-Holland.

Mertz L (1965) *Transformations in Optics*. Amsterdam, Oxford: John Wiley & Sons, Inc.

Photon Density Wave Imaging

V Toronov, University of Illinois at Urbana-Champaign, Urbana, IL, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Photon density wave imaging (PDWI) employs diffused light, usually in the near-infrared band, for imaging inhomogeneous structures in a highly scattering medium. The other names for PDWI are diffuse optical tomography and photon migration imaging. The term photon density wave (PDW) refers to the wave of light density spreading in the highly scattering medium from the source whose power changes in time. Therefore, rigorously speaking, photon density wave imaging uses intensity-modulated light sources, such as pulsed lasers, or sources whose power is harmonically modulated. However, many applications employ steady-state light sources. Most applications of PDWI are in the field of imaging of biological tissues, including medicine and cognitive neuroscience.

As in the other imaging methods, such as x-ray, computed tomography (CT) or ultrasound imaging, the problem of PDWI consists in the reconstruction of the internal structure of the medium from the measurements made outside the medium (on its surface). In the case of PDWI the internal structure of the medium is represented by the spatial distribution of its optical properties. The reconstruction procedure is essentially an iterative mathematical algorithm, which includes the modeling of the light propagation inside the medium assuming a certain distribution of the optical properties, and the correction of this distribution to match the model prediction with the actual measurement. The modeling part of the imaging problem is usually referred to as the forward problem, and the correction procedure is known as an inverse problem.

Forward Problem: Photon Density Waves

Unlike optically transparent media, in a highly scattering medium the coherence of light from the coherent source very rapidly decays with distance. This happens due to the interference of many randomly and multiply scattered light waves at every point of the medium that is distanced from the source much farther than the photon mean free path l, which is the mean distance at which a light wave undergoes a single scattering event. For biological tissues, where light scattering occurs on cell membranes and other heterogeneities of the index of refraction, l is typically about 1 mm. Although high scattering eliminates the coherence of the electromagnetic waves at the short time intervals corresponding to oscillation at optical frequencies ($\sim 10^{-15}$ s), in the case of an intensity-modulated light source, the macroscopic wave of the density of light energy, called 'photon density wave', forms in the highly scattering medium. The properties of PDW depend on the type of the source modulation and on the local optical properties of the medium, which are the scattering coefficient μ_s [cm^{-1}] and the absorption coefficient μ_a [cm^{-1}].

Because of the complexity and incoherence of the macroscopic electromagnetic field in highly scattering media, i.e. media with $\mu_a \ll \mu_s$, the fundamental Maxwell equations of electrodynamics do not provide a convenient approach to the solution of the problem of light propagation in such media at distances much larger than l. Therefore, statistical approaches have been developed, such as the photon transport model and its diffusion approximation. In the photon transport model the light is characterized by the radiance $L(\mathbf{r}, \hat{\Omega}, t)$ [W cm^{-2} steradian^{-1}] (where the steradian is the unit solid angle), which is the power of radiation near the point $\mathbf{r}$ propagating within a small solid angle around the direction $\hat{\Omega}$ at time t. The photon transport model accounts for the possible nonisotropy of the radiation flux. For the given spatio-temporal distribution of the optical properties, μ_a and μ_s, and for the given spatial and angular distribution of light source power $S(\mathbf{r}, \hat{\Omega}, t)$ [W cm^{-3} steradian^{-1}] the radiance $L(\mathbf{r}, \hat{\Omega}, t)$ can be found from the linear radiation transfer equation, also called the photon transport equation, or simply the transport equation (TE):

$$\frac{1}{v}\frac{\partial L(\mathbf{r}, \hat{\Omega}, t)}{\partial t} + \nabla \cdot L(\mathbf{r}, \hat{\Omega}, t)\hat{\Omega} + (\mu_s + \mu_a)L(\mathbf{r}, \hat{\Omega}, t) = \mu_s \int L(\mathbf{r}, \hat{\Omega}', t) f(\hat{\Omega}, \hat{\Omega}')\mathrm{d}\hat{\Omega}' + S(\mathbf{r}, \hat{\Omega}, t) \qquad [1]$$

where $f(\hat{\Omega}, \hat{\Omega}')$ is the phase function, which represents the portion of light energy scattered from the direction $\hat{\Omega}$ to the direction $\hat{\Omega}'$, and v is the speed of light in the medium. TE is equivalent to the Boltzmann transport equation describing the transport of particles undergoing scattering.

Equation [1] is difficult to solve even numerically. Therefore, a hierarchy of approximations to the PTM was developed. This hierarchy, known as the P_N approximation, is based on the expansion of the radiance in a series of spherical harmonics $Y_{nm}(\hat{\Omega})$ truncated at $n = N$. In the P_1 approximation the coefficients of the series are proportional to the radiation fluence

$$\Phi(\mathbf{r}, t) = \int L(\mathbf{r}, \hat{\Omega}, t)\mathrm{d}\hat{\Omega}, \qquad [2]$$

and the flux

$$J(\mathbf{r}, t) = \int L(\mathbf{r}, \hat{\Omega}, t)\hat{\Omega}\mathrm{d}\hat{\Omega}, \qquad [3]$$

both having units of [W cm^{-2}]. By substituting the P_1 series for $L(\mathbf{r}, \hat{\Omega}, t)$ and $S(\mathbf{r}, \hat{\Omega}, t)$ into eqn [1] and assuming isotropic light sources and sufficiently slow change of source intensity, one can obtain the equation that includes only $\Phi(\mathbf{r}, t)$ as the unknown. Usually, this equation

$$v\mu_a U(\mathbf{r}, t) + \frac{\partial U(\mathbf{r}, t)}{\partial t} - D\Delta U(\mathbf{r}, t) = Q(\mathbf{r}, t) \qquad [4]$$

is written in terms of the value $U(\mathbf{r}, t) = \frac{1}{v}\Phi(\mathbf{r}, t)$ [J cm^{-3}], which has units of energy density, and is called the photon density. In eqn [4] $D = v/(3\mu_a + 3\mu_s')$ [cm^2/s] is the light diffusion coefficient, and $\mu_s' = \mu_s(1 - g_1)$ [cm^{-1}] is the reduced scattering coefficient; g_1 is the average cosine of the scattering angle. The source term $Q(\mathbf{r}, t)$ [J cm^{-3} s^{-1}] in the right-hand side of the equation [4] describes the spatial distribution of light sources (in the isotropic approximation, i.e., neglecting the dipole and higher momenta of $S(\mathbf{r}, \hat{\Omega}, t)$) and the temporal modulation of source intensity.

Equation [4] is mathematically equivalent to the equation describing the density of the medium consisting of the particles undergoing linear diffusion. Therefore, it is called the diffusion equation (DE), and the P_1 approximation is also known as the diffusion approximation. The diffusion approximation is valid under the following three conditions: (a) the light sources are isotropic or the distance between the source and the detector is much larger than l; (b) characteristic source modulation frequencies ν are low enough that $\upsilon\mu_s{}'/(2\pi\nu) \gg 1$; and (c) $\mu_a \ll \mu_s'$. In the biomedical applications of PDWI the condition (a) is fulfilled when the source–detector distance is larger than 1 cm. The condition (b) is valid when the characteristic modulation frequencies of the light source are less than 1 GHz. The condition (c) is fulfilled in most biological tissues, for which the scattering is highly isotropic, i.e. $g_1 \ll 1$. Thus, the forward problem of PDWI, i.e., the modeling of light propagation, can be solved using the diffusion approximation in a large variety of situations.

PDWs described by equation [4] are the scalar damped traveling waves, characterized by the coherent changes of light energy (photon density) in different locations on time intervals from microseconds to nanoseconds. Usually pulsed or harmonically modulated light sources are used to generate PDWs. The properties of the PDWs from a harmonic source are fundamental, because the PDW from the source of any type of modulation can be considered as a superposition of harmonic waves from sources having different frequencies using the Fourier transform.

In order to get an idea of the basic properties of PDW, one can consider the analytical solution of [4] for the case of a harmonically modulated point-like source placed in an infinite homogeneous scattering medium. This solution is

$$U(r,t) = U_{dc}(r) + U_{ac}(r)\exp[-i\omega t + i\phi(r)] \qquad [5]$$

where U_{ac}, U_{dc}, and ϕ are the ac, dc and phase, respectively, of the wave measured at the distance r from the source, and $\omega = 2\pi\nu$. U_{ac}, U_{dc}, and ϕ depend on the medium optical properties, source intensity Q_0, modulation amplitude A_0, and initial phase ψ_0 as

$$U_{ac}(r) = \frac{Q_0 A_0}{4\pi D} \times \frac{\exp\left[-r\left(\frac{\upsilon\mu_a}{2D}\right)^{1/2}((1+x^2)^{1/2}+1)^{1/2}\right]}{r} \qquad [6a]$$

$$U_{dc}(r) = \frac{Q_0}{4\pi D}\;\frac{\exp\left[-r\left(\frac{\upsilon\mu_a}{D}\right)^{1/2}\right]}{r} \qquad [6b]$$

$$\phi(r) = r\left(\frac{\upsilon\mu_a}{2D}\right)^{1/2}\sqrt{(1+x^2)^{1/2}-1} \qquad [6c]$$

where $x = \omega/(\upsilon\mu_a)$. Equations [5]–[6] describe a spherical wave whose wavelength at $\mu_a = 0.1\,\text{cm}^{-1}$ and $\mu_s' = 8\,\text{cm}^{-1}$ (typical for biological tissues) and at modulation frequency $\nu = 100$ MHz, is close to 35 cm, so that the phase of the wave changes approximately by 10° per cm. In the same time, the wave decays exponentially at a distance of about 3 cm, so that PDWs are strongly damped. A similar analytical solution in the form of a spherical wave can be obtained for the case of a semi-infinite homogeneous medium and point source placed on the surface of the medium (see Figure 1). These analytical solutions are employed to measure μ_a and μ_s' of the homogeneous medium. The method is based on fitting measured ac, dc, and phase of the PDW as functions of source–detector distance by the analytical solution.

Inhomogeneities in the optical properties of a turbid medium cause distortion of the PDW from sphericity (see Figure 1). PDWs in homogeneous media of limited size or with strong surface curvature also usually have complex structure. For a limited number of configurations one can obtain solutions to the DE using analytical methods of mathematical physics, such as the method of Green's functions. However, in practice the complexity of the inhomogeneities and surfaces usually requires numerical solution of the DE. This can be achieved using numerical methods for the solution of partial differential equations, such as the finite element method and the finite difference method. The finite difference method can also be used to solve the TE. This may be necessary in situations when the DE is not valid, for example to accurately account for the influence of the cerebrospinal fluid (which has relatively low scattering) on light transport in the human skull. However, the solution of the TE requires formidable computational resources, which increase proportionally to the volume of the medium. Therefore, hybrid DE-TE methods were developed, in



Figure 1 Equiphase surfaces of the PDW induced by a point source in a semi-infinite homogeneous medium (solid lines) and in a medium including heterogeneity (dashed lines).

which DE is used to describe light propagation in most of the medium except small low-scattering areas described by the TE.

One should note that although the term 'photon' suggests quantum properties of light, no consistent application of quantum theory to problems related to PDWI has been developed so far. Also, it should be noted that the notion of a photon as a particle of light having certain energy, momentum, and localization at the same time is not completely consistent with quantum electrodynamics. However, since the theoretical models of light transport in a scattering medium (such as TE and DE) are mathematically equivalent to the models describing systems of randomly moving particles, the notion of a photon as a 'particle of light' may be accepted as adequate and is widely used in the limits of PDWI.

Inverse Problem and Imaging Algorithm

Mathematically the forward problem can be expressed in the form of a general nonlinear operator F:

$$G = F[\{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\}] \qquad [7]$$

where G is the set of measured values (ac, dc, and phase), $\mathbf{r}$ is the coordinate vector of a medium element (voxel), and $\{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\}$ denotes the set of tissue optical properties corresponding to whole collection of voxels. The problem of finding the spatial distribution of medium optical properties can be formalized as

$$\{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\} = F^{-1}[G] \qquad [8]$$

Neither the transport model nor the diffusion model allow inversion in a closed analytical form for a general boundary configuration and spatial distribution of optical properties. The basic reason for the complexity of the inverse problem is in the complexity of the light paths in the highly scattering medium. This situation is opposite to that in CT, where the x-ray radiation propagates through the medium along straight lines almost without scattering, which significantly simplifies the forward problem and allows its analytical inversion. From the mathematical point of view, the complexity of the inverse problem of PDWI is due to its nonlinearity and ill-posedness. Only approximate methods of inversion have been developed so far.

The simplest method is called backprojection by analogy with the method of the same name used in CT. The method attempts to reconstruct the actual spatial distribution of the optical properties μ_a and/or μ_s' from the 'measured' bulk values μ_a^m and $\mu_s'^m$ obtained at a variety of locations assuming homogeneity of the medium. The measured values are considered as a result of the volumetric 'projection'

$$\{\mu_a^m(\mathbf{r}), \mu_s'^m(\mathbf{r})\} = \int \{\mu_a(\mathbf{r}'), \mu_s'(\mathbf{r}')\} h(\mathbf{r} - \mathbf{r}')\mathrm{d}^3\mathbf{r}' \qquad [9]$$

of the actual distribution, where $\mathbf{r}$ and $\mathbf{r}'$ are the locations of the measurement and reconstruction, respectively. A weight function $h(\mathbf{r})$ accounts for the contribution of the particular region to a measured value and should be derived from the forward model. Different versions of the backprojection method use different weight functions $h(\mathbf{r})$. In the backprojection method the values of μ_a and/or μ_s' are obtained by inverting the convolution [9]. In practice the convolution integral is usually estimated by a sum over a limited number of voxels for a limited number of measurements. Therefore, the inversion of the convolution reduces to the solution of the set of algebraic equations corresponding to [9]. The advantage of the method is high speed, which allows real-time imaging of the dynamic processes, for example, functional hemodynamic changes in the brain. However, the backprojection method provides a phenomenological rather than a self-consistent inversion of the forward problem, and its quantitative accuracy is low.

A more consistent method is based on the perturbation approach to the solution of the inverse problem [8]. If we have an estimate $\{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\}_e$ that is close to the ideal solution, then $G_e = F[\{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\}_e]$ (see eqn [7]) is close to S. Then the difference $G - G_e$ can be written as a Taylor series:

$$G - G_e = J[\{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\}_e]\{\Delta\mu_a(\mathbf{r}), \Delta\mu_s'(\mathbf{r})\} + \ldots \qquad [10]$$

where $J[\ldots]$ is the Jacobian, and $\{\Delta\mu_a(\mathbf{r}), \Delta\mu_s'(\mathbf{r})\} = \{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\} - \{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\}_e$. Neglecting terms after the first one in [10], the problem of finding the correction $\{\Delta\mu_a(\mathbf{r}), \Delta\mu_s'(\mathbf{r})\}$ to the estimate $\{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\}_e$ reduces to the calculation of the Jacobian and to the solution of a linear algebraic equation.

This approach provides a basis for the PDWI algorithm, which is the following. First one makes an initial guess at the optical properties of the medium. Then one calculates the ac, dc, and phase of the PDW using a model of light propagation through the tissue and the geometry of the source–detector configuration. The calculated values are compared with the measured ones. If the error is above a set tolerance level, one calculates corrections to the current values of μ_a and μ_s' by solving eqn [10]. The algorithm is completed when the required error level is achieved. Thus, the PDWI algorithm iteratively applies both the forward and inverse problems. Since at each of many iterations one should solve the forward problem, which in the simplest case is a partial differential equation, the algorithm typically requires considerable computational resources.

One should note that the success of the method is largely dependent on the closeness of the initial guess to the actual values of the optical properties. In many studies the 'first guess' of the tissue optical properties was obtained by measuring the bulk absorption and reduced scattering coefficients. However, because of the ill-posedness of the inverse problem, homogeneous initial conditions did not always lead to the correct reconstruction. A more productive approach to the problem of the initial conditions is to assign approximate initial values of the optical properties known for example from *in vitro* measurements to different structures revealed by nonoptical imaging techniques, such as magnetic resonance imaging (MRI) or CT.

Applications

PDWI was proposed and developed as a noninvasive biomedical imaging technique. Although the spatial resolution of PDWI cannot compete with that of CT or MRI, PDWI has the advantages of low cost, high temporal resolution, and high biochemical specificity. The latter is based on the optical spectroscopic approach. Biological tissues are relatively transparent to light in the near-infrared band between 700 and 1000 nm (a near-infrared window). The major biological chromophores in this window are oxy- and deoxyhemoglobin, and water. One can separate contributions of these chromophores into light absorption by employing light sources at different wavelengths. Multi-wavelength PDWI can also be used to measure the redox state of the cytochrome oxidase, which is the terminal electron acceptor of the mitochondrial electron transport chain and responsible for 90% of cellular oxygen consumption.

One of the hot topics in cognitive neuroscience is the hemodynamic mechanism of the oxygen supply to neurons and removal of products of cerebral metabolism. High temporal resolution and biochemical specificity make PDWI a unique noninvasive tool for studies of functional cerebral hemodynamics, although light can penetrate no deeper than the very surface of the adult brain. Figure 2 displays a typical arrangement of light sources and detectors used in PDWI of functional cerebral hemodynamics, and the images of the activated area in the brain.

Because of its low cost, noninvasiveness, and compact size of the optical sensors, PDWI is also considered to be a promising tool for mammography and structural imaging of anomalies in the brain. PDWI is an especially promising tool for neonatology, because the infant tissues have low absorption.



Figure 2 (a) Geometrical arrangement of the 16 sources and two detectors on the head of a human subject. Each one of the eight small red circles (numbered 1–8) represents one pair of source fibers at 758 and 830 nm. Two larger green circles represent detector fiber bundles. The rectangle inside the head outline is the $4 \times 9\ \mathrm{cm}^2$ imaged area. (b) Maps of oxyhemoglobin ([HbO$_2$], left panels) and deoxyhemoglobin ([Hb] right panels) concentration changes at rest (top) and at the time of maximum response during the third tapping period (bottom). The measurement protocol involved hand-tapping with the right hand (contralateral to the imaged brain area). Adapted with permission from Franceschini MA, Toronov V, Filiaci M, Gratton E, Fantini S (2000) On-line optical imaging of the human brain with 160-ms temporal resolution. *Optics Express* **6**(3), 49–57 (Figures 1 and 4).

PDWI instruments employ lasers, light-emitting diodes and gas-discharge tubes as sources of light. Among the detectors there are photomultiplier tubes, avalanche photodiodes, and CCD cameras. Both sources and detectors can be coupled with the tissue by means of optical fibers. A number of commercially produced near-infrared instruments for PDWI are available on the market. According to the type of source modulation, there are three groups of instruments: frequency domain (harmonically modulated sources), time domain (pulsed sources), and steady state. Steady-state instruments are simpler and cheaper than frequency-domain and time-domain ones, but their capabilities are much lower. Time-domain instruments can theoretically provide a maximum of information about the tissue structure, but technically it is difficult to build a time-domain instrument with high temporal resolution and high signal-to-noise ratio. Frequency-domain instruments provide temporal resolution up to several milliseconds and have high quantitative accuracy in the determination of optical properties.

Nomenclature

Absorption coefficient, μ_a [cm^{-1}]
Alternating part of PDW, alternating current (ac)
Average cosine of the scattering angle, g_1
Circular modulation frequency, ω [s^{-1}]
Computed tomography (CT)
Difference between the estimate and actual optical properties, $\{\Delta\mu_a(\mathbf{r}), \Delta\mu_s'(\mathbf{r})\} = \{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\} - \{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\}_e$ [cm^{-1}]
Diffusion coefficient, $D = v/(3\mu_a + 3\mu_s')$ [cm^2/s]
Diffusion equation (DE)
Distribution of light source power $S(\mathbf{r}, \hat{\Omega}, t)$ [$\mathrm{W\,cm}^{-3}$ $\mathrm{steradian}^{-1}$]
Divergence operator, ∇ [cm^{-1}]
Estimate of optical properties, $\{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\}_e$ [cm^{-1}]
General nonlinear operator, F
Jacobian, J
Laplace operator, Δ [cm^{-2}]
Magnetic resonance imaging (MRI)
Measured bulk optical properties (absorption and reduced scattering coefficients) $\{\mu_a^m \mu_s'^m\}$ [cm^{-1}]
Modulation frequency, ν [s^{-1}]
Non-alternating part of PDW, direct current (dc)
Optical properties of the medium (absorption and reduced scattering coefficients) as functions of spatial coordinate, $\{\mu_a(\mathbf{r}), \mu_s'(\mathbf{r})\}$ [cm^{-1}]
Phase as a function of source–detector distance $\phi(r)$
Phase function, $f(\hat{\Omega}, \hat{\Omega}')$
Photon density, $U(\mathbf{r}, t)$ [$\mathrm{J\,cm}^{-3}$]
Photon density wave imaging (PDWI)
Photon density wave (PDW)
Photon mean free path, l [cm]
Radiance, $L(\mathbf{r}, \hat{\Omega}, t)$ [$\mathrm{W\,cm}^{-2}$ $\mathrm{steradian}^{-1}$]
Radiation fluence, $\Phi(\mathbf{r}, t)$ [$\mathrm{W\,cm}^{-2}$]
Radiation flux, $J(\mathbf{r}, t)$ [$\mathrm{W\,cm}^{-2}$]
Reduced scattering coefficient, μ_s' [cm^{-1}]
Scattering coefficient, μ_s [cm^{-1}]
Set of measured values (ac, dc, and phase), G
Set of predicted values (ac, dc, and phase), G_e
Source term $Q(r, t)$ [$\mathrm{J\,cm}^{-3}$ s^{-1}]
Source–detector distance, r [cm]
Spatial coordinate, $\mathbf{r}$ [cm]
Speed of light in medium, v [cm/s]
Spherical harmonics $Y_{nm}(\hat{\Omega})$
Transport equation (TE)
Weight function, $h(\mathbf{r})$
$x = \omega/(v\mu_a)$

See also

Coherence: Coherence and Imaging. **Fiber and Guided Wave Optics:** Light Propagation. **Imaging:** Imaging Through Scattering Media. **Optical Materials:** Heterogeneous Materials. **Scattering:** Scattering Theory.

Further Reading

Arridge SR (1999) Optical tomography in medical imaging. *Inverse Problems* 15: R41–R93.

Boas DA (1996) *Diffuse Photon Probes of Structural and Dynamical Properties of Turbid Media: Theory and Biomedical Applications*. PhD Thesis, University of Pennsylvania.

National Research Council (US), Institute of Medicine (US) (1996) *Mathematics and Physics of Emerging Biomedical Imaging*. Washington, DC: National Academy Press.

O'Leary MA (1996) *Imaging with Diffuse Photon Density Waves*. PhD Thesis, University of Pennsylvania.

Special Issue (1997) Near-infrared spectroscopy and imaging of living systems. *Philosophical Transactions of the Royal Society B* 352(1354).

Tuchin V (2002) *Handbook of Optical Biomedical Diagnostics*. Bellingham, WA: SPIE Press.

Tuchin VV, Luo Q and Ulyanov SS (2001) *Imaging of Tissue Structure and Function*. Proceedings of SPIE 4427. Bellingham, WA: SPIE Press.

Villringer A and Chance B (1997) Non-invasive optical spectroscopy and imaging of human brain function. *Trends in Neuroscience* 20: 435–442.

Villringer A and Dirnagl U (1993) *Optical Imaging of Brain Function and Metabolism*. New York: Plenum Press.

Villringer A and Dirnagl U (1997) *Optical Imaging of Brain Function and Metabolism 2: Physiological Basis and Comparison to Other Functional Neuroimaging Methods*. New York: Plenum Press.

Three-Dimensional Field Transformations

R Piestun, University of Colorado, Boulder, CO, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Conventional optical imaging is understood as an isomorphic mapping from an object space onto an image space. The object space is composed of scattering or emitting objects. The scattering objects can be opaque, transparent, or partially absorbing, while emitting objects can be as diverse as stars in astronomical imaging or fluorescent molecules in microscopic imaging. The image space is an optical field representation of the object.

In most classical applications of optical imaging the goal is to optimize the mapping between one plane in the object space and one plane in the image space. Modern optical systems, though, are aimed at acquiring three-dimensional information regarding the object. The image is thus a three-dimensional field representation of the object.

While many imaging systems are aimed at obtaining visually appealing images, many modern imaging systems register the field information in some type of sensitive device such as film or CCD cameras for later processing. This processing is typically performed electronically by a computer and the final image is ultimately a mathematical digital representation of the object. This type of imaging is called computational imaging. An example of computational imaging is optical tomography, which involves the registration of a set of images that do not necessarily resemble the object, and off-line digital processing to obtain a three-dimensional representation of the object.

In this article we will focus on imaging in the conventional sense but will also focus on the three-dimensional aspects of the image.

Geometrical Optics Transformations

In many optical problems it is appropriate to consider the wavelength of the electromagnetic wave as infinitely small. This approximation is the origin of the field of geometrical optics in which the propagation of light is formulated in terms of geometrical laws. Accordingly, the energy is transported along light rays and their trajectories are determined by certain differential or integral equations that can be directly derived from Maxwell's equations. One of these formulations uses Fermat's principle that states the principle of the shortest optical path. The optical path between two points P_1 and P_2 is defined as:

$$OP = \int_{P_1}^{P_2} n(P)\,\mathrm{d}s \qquad [1]$$

where n is the refractive index of the medium. Fermat's principle states that the optical path of a real ray is always a local minimum.

In ideal optical imaging systems, every point P_o of the so-called object space will generate a sharp image point P_i, that is a point where infinite rays emerging from P_o pass through P_i. Perfect imaging occurs when every curve defined by object points is geometrically similar to its image. Perfect imaging can occur between three-dimensional spaces or between surfaces.

An interesting result of geometrical optics is Maxwell's theorem. This theorem states that if an optical instrument produces a sharp image of a three-dimensional domain, the optical length of any curve in the object is equal to the optical length of its image. More explicitly, if the object space has index n_o and the image space index n_i, the theorem states that:

$$\int_{C_\mathrm{o}} n_\mathrm{o}\,\mathrm{d}s_\mathrm{o} = \int_{C_\mathrm{i}} n_\mathrm{i}\,\mathrm{d}s_\mathrm{i} \qquad [2]$$

where C_i is the image of the object curve C_o.

An important consequence of Maxwell's theorem is a theorem by Carathéodory which states that any imaging transformation has to be a projective transformation, an inversion, or a combination of them. Another consequence of this theorem is that if the two media are homogeneous, perfect imaging can only occur if the magnification is equal to the ratio of the refractive indices in the object and image space. If the media have the same index, the imaging is trivial with unit magnification. The simplest example of a perfect imaging instrument is a planar mirror. Therefore, if we want to achieve nontrivial imaging between homogeneous spaces with equal index, we must give up either the perfect imaging (similarity) or the sharpness of the image.

The geometrical optics approximation is very useful in the design of optical imaging systems. However, it fails to provide a complete description of wave optical effects, notably diffraction. Therefore, the following sections provide a description of field transformations based on wave optics.

Systems Approach to 3D Imaging

In this article we deal with linear imaging systems. Hence the relation between three-dimensional (3D) input (object) signals and 3D output (image) signals can be completely specified by the 3D impulse response or point spread function (PSF) of the system $h(x, y, z; x'y', z')$. This function specifies the response of the system at image space coordinates (x, y, z) to a δ-function input (point source) at object coordinates (x', y', z'). The optical system object and image signals are related by the superposition integral:

$$\mathrm{i}(x,y,z) = \int\int\int_{\Omega} \mathrm{o}(x',y',z')h(x,y,z;x'y',z')\mathrm{d}x'\,\mathrm{d}y'\,\mathrm{d}z' \quad [3]$$

where Ω is the object domain. It is clear that for a generic linear imaging system the image signal is completely specified by the response to input impulses located at all possible points of the image domain.

If the system is shift invariant, the PSF due to a point source located anywhere in the object domain will be a linearly shifted version of the response due to a reference point source. This approximation is in general not valid and the system's PSF is a function of the position of the point source in the object domain. Shift invariance is traditionally divided into radial and axial shift invariance. Radial shift variance is the change in the image of a point source as a function of its radial distance from the optical axis. Radial shift variance is caused by lens aberrations. Axial shift variance is the change in the image of a point source as a function of its axial position, z', in the object space. Axial shift variance is inherent to any rotationally symmetric lens system because they can only have one pair of conjugate surfaces, i.e., object–image corresponding surfaces.

In most practical cases the image is detected at a single plane, $z = z_1$ transverse to the optical axis Oz. In those situations, we need to specify the impulse response on this plane:

$$h(x,y,z_1;x'y',z') = h_{z'}(x,y;x'y') \quad [4]$$

The condition for lateral shift invariance is then expressed as $h_{z'}(x, y; x'y') = \tilde{h}_{z'}(x - x', y - y')$. In this case, the superposition integral is a two-dimensional (2D) convolution and it is possible to define the transfer function of the system that is the 2D Fourier transform of the impulse response $\tilde{h}_{z'}(x - x', y - y')$.

Point Spread Function for Coherent, Incoherent, and Partially Coherent Illumination

The input–output relations of an optical imaging system relate different magnitudes according to the type of illumination. If the illumination is coherent, the system is linear in the complex amplitude, while if the illumination is fully incoherent the system is linear in intensity. The 3D impulse response of the incoherent (h_{Inc}) and coherent (h_{Coh}) systems are related as follows:

$$h_{\mathrm{Inc}}(x,y,z;x'y',z') = \left|h_{\mathrm{Coh}}(x,y,z;x'y',z')\right|^2 \quad [5]$$

Notwithstanding, many optical systems cannot be considered fully coherent or fully incoherent. In these situations the system is said partially coherent. If the optical path differences within the optical system are much shorter than the coherence length of the illumination, the light effectively has complete temporal coherence and the magnitude of interest is the mutual intensity. The mutual intensity is defined as the statistical correlation of the complex wavefunction $U(\mathbf{r}, t)$ between different points in space:

$$J(\mathbf{r}_1,\mathbf{r}_2) = \langle U^*(\mathbf{r}_1,t)U(\mathbf{r}_2,t)\rangle \quad [6]$$

where $\mathbf{r}_i = (x_i, y_i, z_i), i = 1, 2$. The illumination is then called quasi-monochromatic. For the case of partially coherent quasi-monochromatic illumination, the system is linear in the mutual intensity. The partially coherent impulse response (h_{PC}) is also related to the coherent impulse response as follows:

$$h_{\mathrm{PC}}(\mathbf{r}_1,\mathbf{r}_2;\mathbf{r}'_1,\mathbf{r}'_2) = h^*_{\mathrm{Coh}}(\mathbf{r}_1;\mathbf{r}'_1)h_{\mathrm{Coh}}(\mathbf{r}_2;\mathbf{r}'_2) \quad [7]$$

The 3D superposition integral that relate object and image mutual intensities is now:

$$J_{\mathrm{image}}(\mathbf{r}_1,\mathbf{r}_2) = \int\int\int_{\Omega} h_{\mathrm{PC}}(\mathbf{r}_1,\mathbf{r}_2;\mathbf{r}'_1,\mathbf{r}'_2) \times J_{\mathrm{object}}(\mathbf{r}'_1,\mathbf{r}'_2)\mathrm{d}\mathbf{r}'_1\,\mathrm{d}\mathbf{r}'_2 \quad [8]$$

Therefore, we conclude that knowledge of the coherent PSF is enough to characterize the optical system for illumination of various degrees of coherence.

Spatial Frequency Content of the 3D Point Spread Function

As previously stated, the coherent impulse response of the optical system completely defines its imaging characteristics. Therefore, it is justified to wonder what the limitations are in the specification of this response. In this section we analyze the frequency domain of coherent and incoherent impulse responses.

The impulse response of the optical system will satisfy the corresponding wave equations regardless of the particulars of the optical system. In particular, assuming a homogeneous isotropic medium in the imaging domain, the coherent response $h(\mathbf{r})$ to an impulse at $\mathbf{r}'$ will satisfy the homogeneous Helmholtz equation in the image domain:

$$\nabla^2 h(\mathbf{r}) + k^2 h(\mathbf{r}) = 0 \qquad [9]$$

where $h(\mathbf{r})$ is the complex amplitude and $k = 2\pi/\lambda$, with λ the wavelength in the medium. If the field at a given origin of coordinates $z = 0$, $f(x, y)$, is known, $h(\mathbf{r})$ can be calculated using the angular spectrum representation as follows:

$$h(x, y, z) = \int\int_{-\infty}^{\infty} F(f_x, f_y) \times \exp[i2\pi(f_x x + f_y y + f_z z)]\mathrm{d}f_x\, \mathrm{d}f_y \qquad [10]$$

where $f_z = \sqrt{\lambda^{-2} - (f_x^2 + f_y^2)}$ and $F(f_x, f_y) = \mathrm{FT}\{f(x, y)\}$; FT represents a 2D Fourier transformation and f_x, f_y are the spatial frequencies along the x and y axes respectively.

Equation [10] can be written as a 3D integral as follows:

$$h(x, y, z) = \int\int_{-\infty}^{\infty} F(f_x, f_y)\cdot\delta\left[f_z - \sqrt{\lambda^{-2} - f_x^2 - f_y^2}\right] \times \exp[i2\pi(f_x x + f_y y + f_z z)]\mathrm{d}f_x\, \mathrm{d}f_y\, \mathrm{d}f_z \qquad [11]$$

where δ represents the dirac impulse. Next we represent the 3D impulse response $h(x, y, z)$ as a 3D Fourier decomposition:

$$h(x, y, z) = \int\int_{-\infty}^{\infty} H(f_x, f_y, f_z) \times \exp[i2\pi(f_x x + f_y y + f_z z)]\mathrm{d}f_x\, \mathrm{d}f_y\, \mathrm{d}f_z \qquad [12]$$

where $H(f_x, f_y, f_z) = \mathrm{FT}^{3\mathrm{D}}\{h(x, y, z)\}$. Comparing eqns [11] and [12] we can infer that:

$$H(f_x,f_y,f_z) = F(f_x,f_y)\cdot\delta\left[f_z - \sqrt{\lambda^{-2} - f_x^2 - f_y^2}\right] \qquad [13]$$

This relation implies that the domain of the Fourier transform of the impulse response is confined to a spherical shell of radius $1/\lambda$. Alternatively, $H(f_x,f_y,f_z)$ is zero everywhere, except from the surface of the sphere.

The previous derivation did not consider any limitation in the range of spatial frequencies allowed through the system. We now assume a finite aperture that will introduce an effective radial cutoff frequency $f_c < 1/\lambda$ and will further limit the spatial spectral domain of $h(x, y, z)$. This is depicted in Figure 1. Note that the transverse and longitudinal spatial frequencies are related, hence the longitudinal spatial frequencies are located within a bandpass of width $\Delta f_z = 1 - \sqrt{\lambda^{-2} - f_c^2}$.

Let us now consider the frequency content of possible incoherent PSFs. From eqn [5] we derive the 3D Fourier transform of the incoherent impulse response:

$$\begin{aligned} H_{\mathrm{Inc}}(f_x, f_y, f_z) &= \mathrm{FT}\left\{h_{\mathrm{Inc}}(x, y, z; x'y', z')\right\} \\ &= \mathrm{FT}\left\{|h_{\mathrm{Coh}}(x, y, z; x'y', z')|^2\right\} \\ &= H \otimes H(f_x, f_y, f_z) \end{aligned} \qquad [14]$$

where $\otimes$ represents a 3D correlation. The domain of H_{Inc} now becomes a volume of revolution as shown in Figure 2. Moreover, because h_{Inc} is real, H_{Inc} is conjugate symmetric, i.e., $H_{\mathrm{Inc}} = H_{\mathrm{Inc}}^*$. Now, the transverse cutoff frequency is $f_{\mathrm{c}}^{\mathrm{Inc}} = 2f_{\mathrm{c}}$ while the longitudinal cutoff frequency is $f_{\mathrm{cl}}^{\mathrm{Inc}} = 2\Delta f_z$.



Figure 1 Three-dimensional spatial-frequency domain of the coherent point spread function.



Figure 2 Three-dimensional spatial-frequency domain of the incoherent point spread function.

Diffraction Calculation of the 3D Point Spread Function

The 3D-image field created by a point source in the object space can be predicted by proper modeling of the optical system. In the absence of aberrations, the distortion of the PSF is originated in the diffraction created by the limiting aperture of the optical system. Diffraction is thus the ultimate limitation to the resolution of the optical system. Under the design conditions of the system, i.e., assuming all aberrations are corrected, the image of a point source is the diffraction pattern produced when a spherical wave converging to the (geometrical) image point is diffracted by the limiting aperture of the system. This is called a diffraction limited image.

There are many formulations to describe the 3D diffraction pattern obtained with a converging wave through an aperture. Here we review the Kirchhoff formulation. Let us consider the aperture **A** and the field at a point P_{d} originated from a converging spherical wave focused at point P_{F} (see Figure 3). We define the vectors **r** joining a generic point on the aperture P_0 and P_{F}, and **s** joining P_0 and P_{d}. The Kirchhoff formulation states that the complex amplitude $U(P_{\mathrm{d}}/P_{\mathrm{F}})$ is the integral over the aperture of the complex amplitude at each point propagated to P_{d} by a spherical wave $\exp(iks)/s$ modified by the directional factor $\cos(\hat{\mathbf{n}},\mathbf{r}) - \cos(\hat{\mathbf{n}},\mathbf{s})$. $\hat{\mathbf{n}}$ is the unit vector normal to the aperture:



Figure 3 Diffraction of a spherical wave by a planar aperture.

$$U(P_{\mathrm{d}}/P_{\mathrm{F}}) = \frac{-iC}{2\lambda}\int\!\!\int_{\mathbf{A}} \frac{\exp[-ik(r-s)]}{rs} \times [\cos(\hat{\mathbf{n}},\mathbf{r}) - \cos(\hat{\mathbf{n}},\mathbf{s})]\mathrm{d}S \qquad [15]$$

where $r = \|\mathbf{r}\|, s = \|\mathbf{s}\|$, and C is the amplitude of the spherical wave.

The directional factor varies slowly and in many situations can be approximated by a constant equal to 2 for small image-field angles. The amplitude over the aperture is also slowly varying and can be approximated by a constant, i.e., $C/r \approx C_0$. Different formulations of the Kirchhoff integral differ in the estimates of the factor $1/s$ and the phase $k(r - s)$. For example, one such formulation leads to the following expression for the 3D diffraction pattern for a focal point on the axis of an optical system with circular aperture:

$$U(P_{\mathrm{d}}/P_{\mathrm{F}}) = \frac{-ika^2C_0}{z_d}\exp\left[ik\left(z_{\mathrm{d}} - z_{\mathrm{F}} + \frac{r_{\mathrm{d}}^2}{2z_{\mathrm{d}}}\right)\right] \times \int_0^1 J_0\left(\frac{ka\rho r_{\mathrm{d}}}{z_{\mathrm{d}}}\right)\exp\left[\frac{-ika^2\rho^2(z_{\mathrm{d}} - z_{\mathrm{F}})}{2z_{\mathrm{d}}z_{\mathrm{F}}}\right]\rho\mathrm{d}\rho \qquad [16]$$

where a is the radius of the aperture, r_{d} is the radial coordinate of P_{d}, and ρ is the radial coordinate of P_0.



Figure 4 Lines of equal intensity in a meridional plane near the focus of a converging spherical wave diffracted at a circular aperture ($\lambda = 0.5\ \mu$, $a = 0.5$ cm, $z_{\mathrm{F}} = 4$ cm).

To illustrate the use of eqn [16], we calculated the intensity around the focus of a spherical wave diffracted through a circular aperture of radius $a = 0.5$ cm, focusing at distance $z_F = 4$ cm from the screen. We assumed the wavelength to be $\lambda = 0.5\ \mu$. Figure 4 depicts the magnitude of the complex amplitude in a meridional plane near the focus of the converging spherical wave.

Models that take into account off-axis focal points have also been developed. For the most accurate calculations, it is necessary to consider the full electromagnetic nature of the optical field.

Conclusions

Classical imaging theory can be applied to the 3D imaging transformation from object to image. The systems approach to the imaging problem implies that knowledge of the 3D coherent PSF suffices to predict the 3D response of the system under illumination of varying degrees of coherence. The PSF response can be predicted using well-known formulations of diffraction.

See also

Coherent Lightwave Systems. **Fourier Optics**.

Further Reading

Born M and Wolf E (1999) *Principles of Optics*, 7th edn. New York: Cambridge University Press.

Gibson SF and Lanni F (1989) Diffraction by a circular aperture as a model for three-dimensional optical microscopy. *Journal of the Optical Society of America A* 6: 1357–1367.

Goodman JW (1996) *Introduction to Fourier Optics*. New York: McGraw-Hill.

Li Y and Wolf E (1984) Three-dimensional intensity distributions near the focus in systems of different Fresnel numbers. *Journal of the Optical Society of America A* 1: 801–808.

Piestun R and Shamir J (2002) Synthesis of 3D light fields and applications. *Proceedings of the IEEE* 90: 222–244.

Saleh BEA and Teich MC (1991) *Fundamentals of Photonics*. New York: Wiley.

Stamnes JJ (1986) *Waves in Focal Regions*. Bristol: Hilger.

Volume Holographic Imaging

G Barbastathis, Massachusetts Institute of Technology, Cambridge, MA, USA

© 2005 Published by Elsevier Ltd.

Volume holographic imaging (VHI) refers to a class of imaging techniques which use a volume hologram in at least one location within the optical path. The volume hologram acts as a ‘smart lens,’ which processes the optical field to extract spatial information in three dimensions (lateral as well as longitudinal) and spectral information.

Figure 1 is a generic VHI system. The object is either illuminated by a light source (e.g., sunlight or a pump laser) as shown in the figure, or it may be self-luminous. Light scattered or emitted by the object is first transformed by an objective lens and then illuminates the volume hologram. The role of the objective is to form an intermediate image which serves as input to the volume hologram. The volume hologram itself is modeled as a three-dimensional (3D) modulation $\Delta\varepsilon(\mathbf{r})$ of the dielectric index within a finite region of space. The light entering the hologram is diffracted by $\Delta\varepsilon(\mathbf{r})$ with efficiency η, defined as

$$\eta = \frac{\text{Power diffracted by the volume hologram}}{\text{Power incident to the volume hologram}} \qquad [1]$$

We assume that diffraction occurs in the Bragg regime. The diffracted field is Fourier-transformed by the collector lens, and the result is sampled and measured by an intensity detector array (such as a CCD or CMOS camera).

Intuitively, we expect that a fraction of the illumination incident upon the volume hologram is Bragg-matched and is diffracted towards the Fourier-transforming lens. The remainder of the incident illumination is Bragg-mismatched, and as result is transmitted through the volume hologram un-diffracted. Therefore, the volume hologram acts as a filter which admits the Bragg-matched portion of the object and rejects the rest. When appropriately designed, this ‘Bragg imaging filter’ can exhibit very rich behavior, spanning the three spatial dimensions and the spectral dimension of the object.

To keep the discussion simple, we consider the specific case of a transmission geometry volume



Figure 1 Volume holographic imaging (VHI) system.

hologram, described in Figure 2. The volume hologram is created by interfering a spherical wave and a planewave, as shown in Figure 2a. The spherical wave originates at the coordinate origin. The planewave is off-axis and its wavevector lies on the xz plane. As in most common holographic systems, the two beams are assumed to be at the same wavelength λ, and mutually coherent. The volume hologram results from exposure of a photosensitive material to the interference of these two beams.

First, assume that the object is a simple point source. The intermediate image is also approximately a point source, that we refer to as 'probe,' located somewhere in the vicinity of the reference point source. Assuming the wavelength of the probe source is the same as that of the reference and signal beams, volume diffraction theory shows that:

(i) If the probe point source is displaced in the y direction relative to the reference point source, the image formed by the volume hologram is also displaced by a proportional amount. Most common imaging systems would be expected to operate this way.

(ii) If the probe point source is displaced in the x direction relative to the reference point source, the image disappears (i.e., the detector plane remains dark).

(iii) If the probe point source is displaced in the z direction relative to the reference point source, a defocused and faint image is formed on the detector plane. 'Faint' here means that the fraction of energy of the defocused probe transmitted to the detector plane is much smaller than the fraction that would have been transmitted if the probe had been at the origin.

Now consider an extended, monochromatic, spatially incoherent object and intermediate image, as in Figure 2f. According to the above description, the volume hologram acts as a 'Bragg slit' in this case: because of Bragg selectivity, the volume hologram transmits light originating from the vicinity of the y axis, and rejects light originating anywhere else. For the same reason, the volume hologram affords depth selectivity (like the pinhole of a confocal microscope). The width of the slit is determined by the recording geometry, and the thickness of the volume hologram. For example, in the transmission recording geometry of Figure 2a, where the reference beam originates a distance z_0 away from the hologram, the planewave propagates at angle θ with respect to the optical axis z (assuming $\theta \ll 1$ radian), and the hologram thickness is L (assuming $L \ll z_0$), the width of the slit is found to be

$$\Delta x \approx \frac{\lambda z_0}{L\theta} \qquad [2]$$

The imaging function becomes richer if the object is polychromatic. In addition to its Bragg slit function, the volume hologram exhibits then dispersive behavior, like all diffractive elements. In this particular case, dispersion causes the hologram to image simultaneously multiple Bragg slits, each at a different color and parallel to the original slit at wavelength λ, but displaced along the z axis. Light from all these slits finds itself in focus at the detector plane, thus forming a 'rainbow image' of an entire slice through the object, as shown in Figure 2g.

To further exploit the capabilities of volume holograms, we recall that in general it is possible to 'multiplex' (superimpose) several volume gratings


x
Reference beam
(spherical wave)
y
z
θ
Signal beam
(plane wave)
L
z_0
Volume
hologram
(a)
x
Probe
beam
y
z
Volume
hologram
Collector
lens
Detector
plane
(Image
forms)
(b)
x
Probe
beam
y
z
Volume
hologram
Collector
lens
Detector
plane
(Displaced
image)
(c)

Figure 2 (a) Recoding of a transmission-geometry volume hologram with a spherical wave and an off-axis plane wave with its wave-vector on the *xz* plane. (b) Imaging of a probe point source that replicates the location and wavelength of the reference point source using the volume hologram recorded in part (a). (c) Imaging of a probe point source at the same wavelength but displaced in the *y* direction relative to the reference point source. (d) Imaging of a probe point source at the same wavelength but displaced in the *x* direction relative to the reference point source. (e) Imaging of a probe point source at the same wavelength but displaced in the *z* direction relative to the reference point source. (f) 'Bragg slitting:' Imaging of an extended monochromatic, spatially incoherent object using a volume hologram recorded as in (a). (g) Joining Bragg slits from different colors to form rainbow slices: Imaging of an extended polychromatic object using a volume hologram recorded as in (a). (h) Multiplex imaging of several slices using a volume hologram formed by multiple exposures.


x
Probe beam
y
z
Detector plane (No image)
Volume hologram
Collector lens
(d)
x
Probe beam
y
z
Detector plane (Faint, defocused image)
Volume hologram
Collector lens
(e)
x
Virtual 'Bragg slit'
y
z
Detector plane (Image of slit)
Extended monochromatic object
Volume hologram
Collector lens
(f)
x
Red-shifted wavelengths
y
Wavelength λ
z
Red
λ
Blue
Blue-shifted wavelengths
Detector plane (Plane slice)
Extended polychromatic object
Volume hologram
Collector lens
(g)

Figure 2 *Continued.*



Figure 2 *Continued.*

within the same volume by successive exposures. In the imaging context, suppose that we multiplex several gratings similar to the grating described in Figure 2a but with spherical reference waves originating at different locations and plane signal waves at different orientations. When the multiplexed volume hologram is illuminated by an extended polychromatic source, each grating forms a separate image of a rainbow slice, as described earlier. By spacing appropriately the angles of propagation of the plane signal waves, we can ensure that the rainbow images are formed on nonoverlapping areas on the detector plane, as shown in Figure 2h. This device is now performing true four-dimensional (4D) imaging: it is separating the spatial and spectral components of the object illumination so that they can be measured independently by the detector array. Assuming the photon count is sufficiently high and the number of detector pixels is sufficient, this 'spatio-spectral slicing' operation can be performed in real time, without need for mechanical scanning.

The complete theory of VHI in the spectral and spatial domains is given in the Further Reading section below. Experimental demonstrations of VHI have been performed in the context of a confocal microscope where the volume hologram performs the function of a 'Bragg pinhole' as well as a real-time 4D imager. The limited diffraction efficiency η of volume holograms poses a major concern for VHI systems. Holograms, however, are known to act as matched filters. It has been shown that the matched filtering nature of volume holograms as imaging elements is superior to other filtering elements (e.g., pinholes or slits) in an information-theoretic sense. Efforts are currently underway to strengthen this property by design of volume holographic imaging elements which are more elaborate than described here.

See also

Holography, Techniques: Overview. **Imaging:** Three-Dimensional Field Transformations.

Further Reading

Barbastathis G and Brady DJ (1999) Multidimensional tomographic imaging using volume holography. *Proceedings of the IEEE* 87(12): 2098–2120.

Barbastathis G and Sinha A (2001) Information content of volume holographic images. *Trends in Biotechnology* 19(10): 383–392.

Barbastathis G, Balberg M and Brady DJ (1999) Confocal microscopy with a volume holographic filter. *Optics Letters* 24(12): 811–813.

Barbastathis G, Sinha A and Neifeld MA (2001) Information-theoretic treatment of axial imaging. In: *OSA Topical Meeting on Integrated Computational Imaging Systems*, pp. 18–20. Albuquerque, NM.

Liu W, Psaltis D and Barbastathis G (2004) Real time spectral imaging in three spatial dimensions. *Optics Letters* in press.

van-der Lugt A (1964) Signal detection by complex spatial filtering. *IEEE Transactions on Information Theory* IT-10(2): 139–145.

Wavefront Sensors and Control (Imaging Through Turbulence)

C L Matson, Air Force Research Laboratory,
Kirtland, NM, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In many situations, distant objects are imaged using optical or near-infrared imaging systems. Examples include terrestrial surveillance from space, tactical surveillance from airborne imaging systems, and ground-based astronomical imaging. Ideally, the resolution in these images is limited only by the wavelength of light λ used to create the images divided by the imaging system's effective diameter D. The ratio λ/D is called the diffraction limit of the imaging system. Unfortunately, when the imaging system is located in the Earth's atmosphere, it is often atmospheric turbulence fluctuations that limit the level of detail in the long-exposure images, not the diffraction limit of the telescope. For example, the Keck telescopes, located on top of Mauna Kea in Hawaii, are 10 m diameter telescopes that have a diffraction-limited angular resolution of 0.2 μrad for an imaging wavelength of 2 μm. However, atmospheric turbulence limits the achievable resolution in long-exposure images to the order of 1–5 μrad at this wavelength.

The important discovery by Anton Labeyrie in 1970 that short-exposure images of objects retain meaningful diffraction-limited information about the object, where 'short' means that the exposure time is less than the atmospheric turbulence coherence time, has revolutionized imaging through turbulence. Atmospheric coherence times depend upon a number of factors, including wind speeds, wind altitudes, and observation wavelength. At astronomical observatories for visible observation wavelengths, a rule of thumb is that atmospheric turbulence stays essentially constant for exposure times of one to ten milliseconds under average clear-sky weather conditions. A variety of techniques that exploit this discovery have been developed. These techniques can be grouped into three different categories: techniques that remove blurring from the detected intensity images (post-detection compensation), techniques that modify the optical field prior to detecting the light (pre-detection compensation), and hybrid techniques that use both post-detection and pre-detection compensation. In this article, a variety of these techniques are presented that are representative of the myriad of methods that have been developed during the past decades. To simplify the discussion, it is assumed that the blurring due to atmospheric turbulence is the same at every point in the image (isoplanaticity), that the images are formed using incoherent light as emitted by the sun and stars, and that a single filled aperture is used to create the images. Interferometric techniques that use multiple apertures to estimate the mutual coherence function of the optical field and calculate an image from it, are discussed in a separate article (*see* **Imaging:** Interferometric Imaging).

The emphasis in this article is on identifying and removing atmospheric blurring in images. As part of this process, regularization techniques must be included in the image reconstruction algorithms in order to obtain the best possible resolution for an acceptable level of noise. Although regularization techniques are not discussed in this article, information can be found in the Further Reading section at the end of this article (*see* **Imaging:** Inverse Problems and Computational Imaging).

Imaging and Atmospheric Turbulence

In Figure 1, a conceptual diagram illustrates the impact that atmospheric turbulence has upon resolution in classical imaging systems. A distant star is being imaged by a telescope/detector system. In the absence of atmospheric turbulence, the field emitted by the star has a planar wavefront over the extent of the lens since the star is a long distance from the imaging system and thus unresolved by the telescope. When imaged by the telescope, the diffraction pattern of the telescope is obtained, resulting in a diffraction-limited image (Figure 2). However, in the presence of atmospheric turbulence near the telescope, the planar wavefront is randomly distorted by the turbulence, resulting in a corrugated wavefront with a spatial correlation scale given by the Fried parameter r_o. For visible wavelengths, at good astronomical observing sites, r_o ranges from 5 cm to 20 cm. When this corrugated wavefront is converted to an image by the telescope, a distorted image is obtained (Figure 3). Because atmospheric turbulence is time-varying, the distortions in the image also change over time. If the imaging shutter on the telescope remains open for many occurrences of atmospheric turbulence, the resulting image will be an average of all the individually distorted images, resulting in what is known as the seeing disk (Figure 4). It is the seeing disk that typically limits spatial resolution in long-exposure images, not the diffraction pattern of the



Figure 1 Conceptual diagram of imaging through atmospheric turbulence.



Figure 2 Computer-simulated diffraction-limited image of a point source.



Figure 3 Computer-simulated short-exposure image of a point source through atmospheric turbulence.

telescope. As a result, the effective spatial resolution in long-exposure images in the presence of atmospheric turbulence is given by λ/r_o, not λ/D.

Atmospheric turbulence distorts a field's wavefront by delaying it in a way that is spatially and temporally random. The origin of these delays is the random variation in the index of refraction of the atmosphere as a result of turbulent air motion brought about by temperature variations. A Fourier optics imaging model is useful in characterizing the effects of atmospheric turbulence on spatial resolution in images. Let $i(\vec{x})$ be an image of an object $o(\vec{x})$, where $\vec{x}$ is a two-dimensional spatial vector, and let $I(\vec{f})$ and $O(\vec{f})$ be their spatial Fourier transforms, where $\vec{f}$ is a two-dimensional spatial frequency vector. In the absence of atmospheric turbulence, the diffraction-limited Fourier transform $I(\vec{f})$ is given by

$$I_d(\vec{f}) = O(\vec{f})H_d(\vec{f}) \qquad [1]$$

where the subscript 'd' denotes the diffraction-limited case and where $H_d(\vec{f})$ is the diffraction-limited



Figure 4 Computer-simulated long-exposure image of a point source through atmospheric turbulence.



Figure 5 Plots of the Fourier amplitudes of the diffraction-limited transfer function (dashed line), Fourier amplitudes of the long-exposure transfer function (dotted line), and the square root of the average short exposure energy spectrum. The spatial frequency axis is normalized to one at the diffraction limit of the telescope.

telescope transfer function. In the presence of atmospheric turbulence, the Fourier transform of a long exposure image $i_{\mathrm{le}}(\vec{x})$ is given by

$$I_{\mathrm{le}}(\vec{f}) = O(\vec{f})H_{\mathrm{d}}(\vec{f})H_{\mathrm{le}}(\vec{f}) = I_{\mathrm{d}}(\vec{f})H_{\mathrm{le}}(\vec{f}) \qquad [2]$$

where the subscript 'le' denotes long exposure. If the turbulence satisfies Kolmogorov statistics, as is typically assumed, then:

$$H_{\mathrm{le}}(\vec{f}) = \exp\left[-3.44\left(\frac{\lambda d|\vec{f}|}{r_{\mathrm{o}}}\right)^{5/3}\right] \qquad [3]$$



Figure 6 Computer-simulated diffraction-limited image of a binary star.



Figure 7 Computer-simulated long-exposure image of a binary star.

where d is the distance between the imaging system's exit pupil and detector plane. As can be seen from eqn [2], the effect of atmospheric turbulence on a long-exposure image is a multiplication of the diffraction-limited image's Fourier transform by a transfer function due to atmospheric turbulence. In Figure 5, an amplitude plot of a diffraction-limited transfer function is displayed along with an amplitude plot of a long-exposure transfer function for a 2.3 m diameter telescope, an imaging wavelength of 0.5 μm, and an r_o value of 10 cm. Notice that the long exposure transfer function significantly reduces the amount of high spatial frequency information in an image. Diffraction-limited and long-exposure turbulence-limited images of a binary star are shown in Figures 6 and 7, illustrating the significant loss of spatial resolution brought on by atmospheric turbulence.

Post-Detection Compensation

Speckle Imaging

Labeyrie's 1970 discovery was motivated by his analysis of short-exposure star images. In these images (see Figure 3), a number of speckles are present, where the individual speckle sizes are roughly the size of the diffraction-limited spot of the telescope. From this, he realized that high spatial frequency information is retained in short-exposure images, albeit distorted. He then showed that the energy spectra $E_I(\vec{f})$ of the individual short-exposure images can be averaged to obtain an estimate of the average energy spectrum that retains high signal-to-noise ratio (SNR) information at high spatial frequencies. The square root of the average energy spectrum (the amplitude spectrum) of a star, calculated using Labeyrie's method (also known as speckle interferometry), is shown in Figure 5, along with the diffraction-limited and long-exposure amplitude spectra. Notice that meaningful high spatial frequency information is retained in the average amplitude spectrum out to the diffraction limit of the telescope. Because the atmospherically corrupted amplitude spectrum estimate is significantly lower than the diffraction-limited amplitude, a number of short exposure images must be used to build up the SNRs at the higher spatial frequencies.

To reconstruct an image, both the Fourier amplitudes and Fourier phases of the image must be known. In fact, it is well known that the Fourier phase of an image carries most of the information in the image. Because only the Fourier amplitudes are available using Labeyrie's method, other techniques were subsequently developed to calculate the Fourier phase spectrum from a sequence of short-exposure images. Techniques that combine amplitude spectrum estimation using Labeyrie's method along with phase spectrum estimation are called speckle imaging techniques. The two most widely used phase spectrum estimation methods are the Knox–Thompson (or cross spectrum) and bispectrum algorithms. Both of these algorithms calculate Fourier-domain quantities that retain high spatial frequency information about the Fourier phase spectrum when averaged over multiple short-exposure images. The cross spectrum and bispectrum techniques calculate the average cross spectrum $C(\vec{f},\Delta\vec{f})$ and bispectrum $B(\vec{f}_1,\vec{f}_2)$, respectively, that are given by

$$C(\vec{f},\Delta\vec{f}) = I(\vec{f})I^*(\vec{f}+\Delta\vec{f}) \qquad [4]$$

$$B(\vec{f}_1,\vec{f}_2) = I(\vec{f}_1)I(\vec{f}_2)I^*(\vec{f}_1+\vec{f}_2) \qquad [5]$$

where the superscript * denotes complex conjugate. Although the cross spectrum is defined for all values of $\vec{f}$ and $\Delta\vec{f}$, only for values of $\Delta\vec{f}$ or $\vec{f}$ less than r_o/λ are the cross spectrum elements obtained with sufficiently high SNRs to be useful in the reconstruction process. The equivalent constraint on the bispectrum elements is that either $\vec{f}_1, \vec{f}_2$, or $\vec{f}_1+\vec{f}_2$ must be less than r_o/λ. Once the average cross spectrum or bispectrum is calculated from a series of short-exposure images, the phase spectrum $\phi_I(\vec{f})$ of the underlying image can be calculated from their phases using one of a number of algorithms based upon the following equations:

$$\phi_I(\vec{f}+\Delta\vec{f}) = \phi_I(\vec{f}) - \phi_C(\vec{f}+\Delta\vec{f}) \qquad [6]$$

for the cross spectrum and:

$$\phi_I(\vec{f}_1+\vec{f}_2) = \phi_I(\vec{f}_1) + \phi_I(\vec{f}_2) - \phi_B(\vec{f}_1+\vec{f}_2) \qquad [7]$$

for the bispectrum. Because the phases are only known for units of 2π, phasor versions of eqns [6] and [7] must be used. For the cross spectrum technique, each short-exposure image must be centroided prior to calculating its cross spectrum and adding it to the total cross spectrum. The bispectrum technique is insensitive to tilt, so no centroiding is necessary; however, the bispectrum technique requires setting two image phase spectrum values to arbitrary values to initialize the phase reconstruction process. Typically, the image phase spectrum values at $\vec{f} = (0,1)$ and $\vec{f} = (1,0)$ are set equal to zero, which centroids the reconstructed image but does not affect its morphology.

To obtain an estimated Fourier transform $I_e(\vec{f})$ of the image from the energy and phase spectrum estimates, the square root of the average energy spectrum is combined with the average phase spectrum calculated from either the bispectrum or cross spectrum. The result is given by

$$I_e(\vec{f}) = [E_I(\vec{f})]^{1/2} \exp[j\phi_I(\vec{f})] \qquad [8]$$

where $j = \sqrt{-1}$. The result in eqn [8] includes atmospheric attenuation of the Fourier amplitudes, so it must be divided by the amplitude spectrum of the atmosphere to obtain the desired object spectrum estimate. The atmospheric amplitude spectrum estimate is obtained by using Labeyrie's technique on a sequence of short-exposure images of a nearby unresolved star. No phase spectrum correction is necessary because it has been shown theoretically and verified experimentally that atmospheric turbulence has a negligible effect upon $\phi_I(\vec{f})$.

Blind Deconvolution

Speckle imaging techniques are effective as well as easy and fast to implement. However, it is necessary to obtain a separate estimate of the atmospheric energy spectrum using an unresolved star in order to reconstruct a high-resolution image. Usually, the star is not co-located with the object and the star images are not collected simultaneously with the images of the object. As a result, the atmospheric energy spectrum estimate may be inaccurate. At the very least, collecting the additional star data expends valuable observation time. In addition, there is often meaningful prior knowledge about the object and the data, such as the fact that measured intensities are positive (positivity), that many astronomical objects are imaged against a black background (support), and that the measured data are band-limited, among others. Speckle imaging algorithms do not exploit this additional information. As a result, a number of techniques have been developed to jointly estimate the atmospheric blurring effects as well as an estimate of the object being imaged using only the short-exposure images of the object and available prior knowledge. These techniques are called blind deconvolution techniques. Two of the most common techniques are known as multi-frame blind deconvolution (MFBD) and projection-based blind deconvolution (PBBD).

The MFBD algorithm is based upon maximizing a figure of merit to determine the best object and atmospheric short-exposure point spread function (PSF) estimates given the data and available prior knowledge. This figure of merit is created using a maximum likelihood problem formulation. Conceptually, this technique produces estimates of the object and the atmospheric turbulence short-exposure PSFs that most likely generated the measured short-exposure images. Mathematically, the MFBD algorithm obtains these estimates by maximizing the conditional probability density function (pdf) $p[i_m(\vec{x})|o(\vec{x}); h_m(\vec{x}),\ m = 1, \ldots, M]$, where $i_m(\vec{x})$ is the mth of M short exposure images and is given by

$$i_m(\vec{x}) = h_m(\vec{x}) * o(\vec{x}) + n_m(\vec{x}) \qquad [9]$$

where $h_m(\vec{x})$ and $n_m(\vec{x})$ are the atmospheric/system blur and detector noise functions for the mth image, respectively, and the asterisk denotes convolution. The noise is assumed to be zero mean with variance $\sigma^2(\vec{x})$. The conditional pdf $p[i_m(\vec{x})|o(\vec{x}); h_m(\vec{x}),\ m = 1, \ldots, M]$ is the pdf of the noise with a mean equal to $h_m(\vec{x}) * o(\vec{x})$ and, as a function of $o(\vec{x})$ and $h_m(\vec{x})$, it is known as a likelihood function. For spatially independent Gaussian noise, as is the case for camera read noise, the likelihood function is given by

$$\begin{aligned} L_G[o(\vec{x}); h_m(\vec{x}),\ m = 1, \ldots, M] &= \prod_m \prod_{\vec{x}} \frac{1}{\sqrt{2\pi\sigma^2(\vec{x})}} \\ &\times \exp\{-[i(\vec{x}) - (o * h_m)(\vec{x})]^2/2\sigma^2(\vec{x})\} \end{aligned} \qquad [10]$$

For Poisson noise, the likelihood function is given by

$$\begin{aligned} &L_P[o(\vec{x}); h_m(\vec{x}), \mathrm{m} = 1, \ldots, M] \\ &= \prod_m \prod_{\vec{x}} \frac{[(o * h_m)(\vec{x})]^{i(\vec{x})} \exp\{-[(o * h_m)(\vec{x})]\}}{i(\vec{x})!} \end{aligned} \qquad [11]$$

In practice, logarithms of eqns [10] and [11] are taken prior to searching for the estimates of $o(\vec{x})$ and $h_m(\vec{x})$ that maximize the likelihood function.

In general, there are an infinite number of estimates of $o(\vec{x})$ and $h_m(\vec{x})$ that reproduce the original dataset when convolved together. However, when additional prior knowledge is included to constrain the solution space, such as positivity, support, and the knowledge that $h_m(\vec{x})$ is band-limited, along with regularization, the MFBD algorithm almost always converges to the correct estimates of $o(\vec{x})$ and $h_m(\vec{x})$.

The PBBD technique also uses prior knowledge constraints to jointly estimate $o(\vec{x})$ and $h_m(\vec{x})$. However, instead of creating and maximizing a likelihood function, the PBBD technique uses the method of convex projections to find estimates of $o(\vec{x})$ and $h_m(\vec{x})$ that are consistent with the measured short-exposure images and all the prior knowledge constraints. The data consistency constraint and the prior knowledge constraints are mathematically formulated as convex sets and the PBBD technique repeatedly takes the current estimates of $o(\vec{x})$ and $h_m(\vec{x})$ and projects them onto the convex constraint sets. As long as all the sets are truly convex, the algorithm is guaranteed to converge to a solution that is in the intersection of all the sets as long as the algorithm doesn't stagnate at erroneous solutions called traps. These traps are the projection equivalent of local minima in cost function minimization algorithms.

A key component of this algorithm is the ability to formulate the measured short-exposure images and prior knowledge constraints into convex sets. As an example, consider the convex set $C_{\mathrm{pos}}[u(\vec{x})]$ that corresponds to the positivity constraint. This set is given by

$$C_{\mathrm{pos}}[u(\vec{x})] \triangleq \{u(\vec{x}) \text{ such that } u(\vec{x}) \geq 0\} \qquad [12]$$

It is straightforward to show that $C_{\mathrm{pos}}[u(\vec{x})]$ is a convex set. Other constraints can be converted into convex sets in a similar manner. Although all constraints can be formulated into sets, most but not all of these sets are convex.

The projection process is straightforward to implement. For example, the projections of the current estimates of $o(\vec{x})$ and $h_{\mathrm{m}}(\vec{x})$ onto $C_{\mathrm{pos}}[u(\vec{x})]$ are carried out by zeroing out the negative values in these estimates. Similarly, the projections of $o(\vec{x})$ and $h_{\mathrm{m}}(\vec{x})$ onto the convex sets that correspond to their support constraints are carried out by zeroing out all their values outside of their supports. In practice, some versions of PBBD algorithms have been formulated to use minimization routines as part of the projection process in order to minimize the possibility of stagnation.

Deconvolution from Wavefront Sensing

A key distinguishing feature of post-detection compensation algorithms is the type of additional data required to estimate and remove atmospheric blurring in the measured short-exposure images. Blind deconvolution techniques need no additional data. Speckle imaging techniques estimate average atmospheric blurring quantities and need an estimate of the average atmospheric energy spectrum. Because average quantities are calculated when using speckle imaging techniques, only an estimate of the average atmospheric energy spectrum is needed, not the specific energy spectra that corrupted the measured short-exposure images. As a result, the additional data need not be collected simultaneously with the short-exposure images. The technique described in this section, deconvolution from wavefront sensing (DWFS), seeks to deconvolve the atmospheric blurring in each short-exposure image by estimating the specific atmospheric field phase perturbations that blur each short-exposure image. Thus, the additional data must be collected simultaneously with the short-exposure images. The atmospheric field phase perturbations are calculated from data obtained with a wavefront sensor using a different region of the optical spectrum than used for imaging so that no light is taken from the imaging sensor. Most commonly, the wavefront sensor data consists of the first derivatives of the phasefront (phase differences) as obtained with Shack–Hartmann or shearing interferometer wavefront sensors, but curvature sensing wavefront sensors are also used that produce data that are proportional to the second derivatives of the phasefront.

The original algorithm to implement the DWFS technique produced an estimate $\hat{O}(\vec{f})$ of the Fourier transform $O(\vec{f})$ of the object being imaged using the following estimator:

$$\hat{O}(\vec{f}) = \frac{\sum_{m} I_{\mathrm{m}}(\vec{f})\tilde{H}^{*}_{\mathrm{m}}(\vec{f})}{\sum_{m} |\tilde{H}_{\mathrm{m}}(\vec{f})|^{2}} \qquad [13]$$

where $\tilde{H}_{\mathrm{m}}(\vec{f})$ is the overall system transfer function (including the telescope and atmospheric effects) for the mth short-exposure image estimated from the wavefront sensor data. To create $\tilde{H}_{\mathrm{m}}(\vec{f})$, the atmospheric field phase perturbations corrupting the mth image must be calculated from the wavefront sensor measurements. This topic is discussed in more detail in **Imaging**: Adaptive Optics. Then $\tilde{H}_{\mathrm{m}}(\vec{f})$ is obtained using standard Fourier optics techniques. Although eqn [13] is easily implemented given an existing system that includes a wavefront sensor, it suffers from the fact that it is a biased estimator. An unbiased version of eqn [13] is given by

$$\hat{O}(\vec{f}) = \frac{\sum_{m} I_{\mathrm{m}}(\vec{f})\tilde{H}^{*}_{\mathrm{m}}(\vec{f})}{\sum_{n} H_{\mathrm{n,ref}}(\vec{f})\tilde{H}^{*}_{\mathrm{n,ref}}(\vec{f})} \qquad [14]$$

where $\tilde{H}_{\mathrm{n,ref}}(\vec{f})$ and $H_{\mathrm{n,ref}}(\vec{f})$ are estimates of the overall system transfer function obtained from data collected on a reference star using wavefront sensor data and image-plane data, respectively. Thus, to obtain an unbiased estimator, two more datasets must be collected. The number of frames in the reference star dataset need not be the same as for the imaging dataset. As for speckle imaging, the atmospheric statistics must be the same for the reference star and imaging datasets.

Another technique that uses at least one additional data channel along with the measured image is called phase diversity. In the additional data channels, images are also recorded, but with known field phase aberrations intentionally introduced to add known diversity to the unknown field phase corrupting the measurements. The most commonly introduced field phases aberration in an additional channel is defocus due to its ease of implementation. In the case of defocus, the additional data channel along with the imaging channel can be viewed as samples of the focal volume of the imaging system. Both the noise-free object and the unknown field phase aberrations can be recovered from the measured data using optimization techniques to enforce data consistency along with other prior knowledge constraints. These types of systems can use higher-order aberrations as well. The phase diversity concept has been generalized to an approach known as computational imaging, where an imaging system is designed by taking into account its intended use, the expected image degradation mechanisms, and the fact that the image will be the product of both an optical system and a postprocessing algorithm.

Pre-Detection Compensation

The primary pre-detection-only compensation technique in use today employs dynamical electro-optical systems to sense and remove the phases in the impinging wavefront due to atmospheric turbulence. This technique, known as adaptive optics, provides much higher-quality data than post-detection compensation techniques, when there is enough light from the object being imaged or a guidestar (artificial or natural) to drive the adaptive optics system at a bandwidth high enough to keep up with the temporal changes in atmospheric turbulence. It consists of a wavefront sensor that measures the portion of the phasefront in the pupil of the telescope that is due to atmospheric turbulence, a wavefront reconstructor that generates the deformable mirror drive signals from the wavefront sensor data, and a deformable mirror that applies the conjugate of the atmospheric phase distortions to a reimaged pupil. Some of the light reflected off the deformable mirror is then sent to the imaging sensor. Adaptive optics systems are discussed in much greater detail in **Imaging**: Adaptive Optics. Here, it suffices to say that no adaptive optics system produces imagery that is diffraction limited in quality, although, under the right conditions, the images can be near diffraction limited. However, atmospheric seeing conditions fluctuate significantly over a night as well as seasonally. Therefore, virtually all adaptive optics images benefit from applying post-compensation techniques, as is discussed next.

Hybrid Techniques

Adaptive Optics and Post-Processing

Often, an adaptive optics system does not fully correct for atmospheric turbulence. This can occur when atmospheric conditions become worse than the system is designed to handle. Also, an adaptive optics system may be intentionally designed to only partially correct for atmospheric turbulence in order to lower the cost of the system. As a result, there still may be significant atmospheric blurring in systems that use adaptive optics. For this reason, additional post-processing of adaptive optics imagery can result in significant improvement in image quality. All of the techniques discussed in the section on post-detection compensation can be applied to adaptive optics imagery. Applying these techniques should never degrade image quality, and will improve the quality if the adaptive optics system doesn't fully correct for atmospheric turbulence. Generally speaking, the amount of improvement decreases as the performance of the adaptive optics system increases. Because the adaptive optics system's performance parameters can vary as atmospheric conditions vary, the blind deconvolution algorithms are especially applicable to processing adaptive optics imagery since they estimate the overall system transfer function from the imaging data. Because speckle imaging techniques require a separate estimate of the overall system transfer function, it can be difficult and time-consuming to obtain all of the additional data necessary to apply these techniques to adaptive optics data. Since these post-detection compensation techniques require short-exposure images, the adaptive optics system needs to have a camera capable of collecting short-exposure images. Finally, even if an adaptive optics system fully corrects for the atmosphere, deconvolution techniques that remove the diffraction-limited transfer function amplitude attenuation can improve image quality.

Partially Redundant Pupil Masking

Although adaptive optics systems can function very well, currently they are expensive and require significant maintenance. The primary benefit of adaptive optics systems is that they remove atmospheric turbulence phase distortions in the pupil of the telescope, thus permitting light from all areas of the pupil to interfere in phase when creating an image. An interferometric view of imaging reveals that multiple regions of the light in the pupil contribute to a single spatial frequency in the image. When the phasefront in the pupil is distorted by the atmosphere, these multiple regions tend to not interfere in phase, reducing the amplitude of the image's Fourier component at that spatial frequency. This amplitude reduction effect occurs for all spatial frequencies greater than the limit imposed by the atmosphere, r_0/λ. Therefore, techniques have been developed to modify the wavefront by masking part of the pupil prior to measuring the field with an imaging sensor. This class of techniques has various names including optical aperture synthesis, pupil masking, and aperture masking. Here this class of techniques will be referred to as partially redundant pupil masking (PRPM).

PRPM techniques function by masking the pupil in such a way as to minimize the amount of out-of-phase interference of light on the imaging detector. Early efforts used pupil masks that were opaque plates with r_0-sized holes in them. Because the atmospheric coherence length is r_0, all the light from an r_0-sized hole is essentially in phase. By choosing the holes in the mask so that only two holes contribute to a single spatial frequency in the image, out-of-phase interference problems are removed. This type of mask is called a nonredundant pupil mask. Of course, a significant amount of light is lost due to this masking, so only bright objects benefit from this particular implementation. Often, the pupil mask needs to be rotated in order to obtain enough spatial frequencies in the image to be able to reconstruct a high-quality estimate of the object. To increase the light levels in the image, masks have been made to allow some out-of-phase interference for a given spatial frequency, thus trading off the amplitude of the spatial frequencies allowed in the image with the amount of light in the image. Masks with this property are called partially redundant pupil masks.

One version of PRPM is called the variable geometry pupil (VGP) technique. It is envisioned to work in conjunction with an adaptive optics system that does not fully correct the wavefront for atmospheric phase distortions. It employs a spatial light modulator or a micro-electromechanical mirror between the deformable mirror and the imaging sensor. Either of these two devices is driven by signals from the wavefront sensor in the adaptive optics system in such a way that the portions of the pupil where the phasefront has a sufficiently large second derivative is blocked, while the remainder of the phasefront is transmitted.

All PRPM techniques benefit from post-compensation processing. For the case of nonredundant pupil masks, post-processing techniques are required to convert the discrete-spatial-frequency information into an image with reasonable quality. These techniques are essentially the same techniques as used in interferometric imaging, not those described in this article. When partially redundant pupil masks are used (including VGP masks), the image may include enough spatial frequency content that the methods described in the post-detection compensation section can be applied.

See also

Imaging: Adaptive Optics; Interferometric Imaging; Inverse Problems and Computational Imaging.

Further Reading

Ayers GR, Northcott MJ and Dainty JC (1988) Knox–Thompson and triple-correlation imaging through atmospheric turbulence. *Journal of the Optical Society of America A* 5: 963–985.

Bertero M and Boccacci P (1998) *Introduction to Inverse Problems in Imaging*. Bristol, UK: Institute of Physics Publishing.

Craig IJD and Brown JC (1986) *Inverse Problems in Astronomy*. Bristol, UK: Adam Hilger Ltd.

Dainty JC (1984) Stellar speckle interferometry. In: Dainty JC (ed.) *Topics in Applied Physics, vol. 9: Laser Speckle and Related Phenomena*, 2nd edn, pp. 255–320. Berlin: Springer-Verlag.

Goodman JW (1985) *Statistical Optics*. New York: John Wiley and Sons.

Haniff CA and Buscher D (1992) Diffraction-limited imaging with partially redundant masks I: Infrared imaging of bright objects. *Journal of the Optical Society of America A* 9: 203–218.

Katsaggelos AK and Lay KT (1991) Maximum likelihood identification and restoration of images using the expectation-maximization algorithm. In: Katsaggelos AK (ed.) *Digital Image Restoration*, pp. 143–176. Berlin: Springer-Verlag.

Nakajima T and Haniff CA (1993) Partial adaptive compensation and passive interferometry with large ground-based telescopes. *Publications of the Astronomical Society of the Pacific* 105: 509–520.

Roggemann MC and Welsh B (1996) *Imaging Through Turbulence*. Boca Raton, FL: CRC Press.

Schulz TJ (1993) Multiframe blind deconvolution of astronomical images. *Journal of the Optical Society of America A* 10: 1064–1073.

Tyson RK (1991) *Principles of Adaptive Optics*. San Diego, CA: Academic Press.

Youla DC and Webb H (1982) Image restoration by the method of convex projections: Part 1 – Theory. *IEEE Transactions on Medical Imaging* M1-1: 81–94.

INCOHERENT SOURCES

Contents

Lamps
Synchrotrons

Lamps

V Roberts, Roberts Research and Consulting, Inc., Burnt Hills, NY, USA

© 2005 Roberts Research and Consulting, Inc. Published by Elsevier Ltd. All rights reserved.

Introduction

Electric lamps are by far the most common source of light used on Earth, other than our sun. These sources are composed of a very large number of individual radiating elements, all acting independently. This independence causes the light generated by electric lamps to have a very low degree of spatial and temporal coherence. When compared to lasers, lamps are usually considered to be incoherent sources.

Electric lamps are widely used for general lighting, such as residential, commercial and industrial space, and task lighting. A much less frequent use of incoherent sources, but perhaps of more interest to the reader, is as wavelength, intensity, and total light output standard used to calibrate various coherent light sources. We will discuss the general characteristics of incandescent, gas discharge, and solid state lamps, with sources in the Further Reading section at the end of this article, which are used as calibration standards for coherent sources.

Definitions

Before discussing individual lamp technologies, we need to define some of the key terms that are used for describing the performance of electric lamps. Most of these definitions are based on or abstracted from the IESNA Lighting Handbook:

- *Efficacy*: The total light output of a lamp, measured in lumens, divided by the power input in watts. Efficacy has the units of lumens per watt, or $\mathrm{l\,m\,W^{-1}}$, and can be greater than 100. The efficacy of common light sources varies from $10\,\mathrm{l\,m\,W^{-1}}$ to over $200\,\mathrm{l\,m\,W^{-1}}$.
- *Correlated Color Temperature* (*of a light source*) (*CCT*): the absolute temperature of a blackbody whose chromaticity most nearly resembles that of the light source. CCT is measured in Kelvin (K). The CCT of typical light sources varies from 2000 K to 6000 K, with the most popular sources being in the range from 2700 K to perhaps 4500 K.
- *Color Rendition Index* (*of a light source*) (*CRI*): a measure of the degree of color shift objects undergo when illuminated by the light source as compared with those same objects when illuminated by a reference source of comparable color temperature. The highest possible CRI is 100. The lowest theoretical CRI is less than zero, but CRI less than 50 is generally considered to have no value in determining the color quality of a light source.
- *Photopic Luminous Efficiency Function* (V_λ): a measure of the sensitivity of the human eye in lumens per watt of radiation received, as a function of wavelength, for luminance levels higher than $\sim 3\,\mathrm{cd\,m^{-2}}$. V_λ is based on relatively few observations, and individuals may differ significantly from the standard V_λ function. V_λ provides the basis for measuring the efficacy of all light sources.
- *Visible Light*: generally accepted to mean radiation between 380 nm and 780 nm.

Incandescent Lamps

Incandescent lamps are quasi-blackbody thermal radiators. A true blackbody radiator would generate light according to Planck's Law, as shown in eqn [1] and Figure 1, for various temperatures. Most incandescent lamps use tungsten filaments, and the emissivity of tungsten, the ratio of its radiative output to that of a blackbody at the same temperature, is about 0.44 in the visible region of the spectrum and about 0.33 in the infrared. The radiative output of a tungsten incandescent lamp is, therefore, less than half that of a blackbody of the same temperature and the intensity versus wavelength curve does not exactly follow Plank's law, being slightly favorable to visible



Figure 1 Radiation from blackbody source at various temperatures. © 2005 Roberts Research and Consulting, Inc. Published by Elsevier Ltd. All rights reserved.



Figure 2 Radiation from blackbody source at various temperatures with visible band. © 2005 Roberts Research and Consulting, Inc. Published by Elsevier Ltd. All rights reserved.

radiation:

$$E(\lambda) = \frac{2\pi h c^2 10^{-9}}{\lambda^5(\exp^{hc/k\lambda T} - 1)} \quad [1]$$

where:

E = power per square meter of surface area per nm of wavelength
λ = wavelength in meters
h = Plank's constant, 6.63×10^{-34} Joule seconds
c = speed of light, 3×10^8 meters sec^{-1}
κ = Boltzman's constant, 1.38×10^{-23} Joule K^{-1}
T = temperature of the source in K

Tungsten lamps have excellent color quality, reflected in a perfect CRI of 100, are inexpensive, available in a great variety of sizes, shapes, and operating voltages, have a small source size that permits excellent light control with relatively small reflectors and lenses, run equally well on AC or DC power, can be easily dimmed, can have very long life, are insensitive to operating position, are relatively insensitive to ambient temperature, contain no hazardous materials, and light virtually instantly, though not as fast as LEDs. However, incandescent lamps have one major disadvantage; they are very inefficient. Most of the energy consumed by incandescent lamps is radiated in the infrared, while only 5% to 10% is radiated in the visible portion of the spectrum. The reason for this is shown in Figure 2, which shows the visible region of the spectrum superimposed on the blackbody radiation curves.

There a number of techniques that have been used or are being investigated to increase the efficacy of incandescent lamps. First, as can be seen in Figure 2, increasing the filament temperature shifts the wavelength for peak emission toward lower wavelengths, and will result in a larger fraction of the radiated energy being in the visible region. Unfortunately, increasing filament temperature also increases the rate of tungsten evaporation and therefore shortens the life of tungsten lamps, since evaporation of tungsten is the dominant incandescent lamp failure mode. In a similar manner, the life of incandescent lamps can be increased to arbitrarily long times by decreasing filament temperature. This technique, which is the means used in far too many ‘long life’ incandescent lamps, unfortunately leads to a decrease in the already low efficacy of incandescent lamps. The approximate dependences of life, efficacy, and color temperature on operating voltage, for common incandescent lamps operating between 90% to 110% of rated voltage, are shown in eqns [2], [3], and [4]:

$$\frac{\mathrm{LIFE}_1}{\mathrm{LIFE}_2} = \left(\frac{\mathrm{VOLTS}_2}{\mathrm{VOLTS}_1}\right)^{13} \quad [2]$$

$$\frac{\mathrm{EFFICACY}_1}{\mathrm{EFFICACY}_2} = \left(\frac{\mathrm{VOLTS}_1}{\mathrm{VOLTS}_2}\right)^{1.9} \quad [3]$$

$$\frac{\mathrm{COLOR\_TEMPERATURE}_1}{\mathrm{COLOR\_TEMPERATURE}_2} = \left(\frac{\mathrm{VOLTS}_1}{\mathrm{VOLTS}_2}\right)^{0.42} \quad [4]$$

Combining eqns [2] and [3] yields eqn [5]:

$$\frac{\mathrm{LIFE}_1}{\mathrm{LIFE}_2} = \left(\frac{\mathrm{EFFICACY}_2}{\mathrm{EFFACACY}_1}\right)^{6.84} \quad [5]$$

Under the assumption that the color temperature of an incandescent lamp is approximately the same as the operating temperature of the filament, we can combine eqns [2] and [4] to obtain eqn [6], and combine eqns [3] and [4] to obtain eqn [7]:

$$\frac{\mathrm{LIFE}_1}{\mathrm{LIFE}_2} = \left(\frac{\mathrm{TEMPERATURE}_2}{\mathrm{TEMPERATURE}_1}\right)^{30.95} \qquad [6]$$

$$\frac{\mathrm{EFFACACY}_1}{\mathrm{EFFICACY}_2} = \left(\frac{\mathrm{TEMPERATURE}_1}{\mathrm{TEMPERATURE}_2}\right)^{4.52} \qquad [7]$$

One way to allow operation with higher filament temperatures, while not decreasing filament life, is to fill the lamp with a high molecular weight and/or high pressure gas, as either will retard tungsten evaporation. Lamps using krypton or xenon in place of the normal argon fill allow for a moderate increase in filament temperature. Better yet is a fill of halogen gas, such as HBr, CH_3Br, or CH_2Br^2 plus Kr or Xe at total pressures that range from 2 to 15 atmospheres. The high total pressure inhibits tungsten evaporation from the filament, and the halogen fill gas reacts with tungsten that deposits on the wall of the lamp to remove this tungsten and maintain light output over the life of the lamp. The tungsten removed from the wall of the lamp is redeposited on the tungsten filament, increasing lamp life under some circumstances. Due to the high gas pressures involved, tungsten halogen incandescent lamps are constructed in small 'filament tubes' to minimize both the amount of gas needed and the total explosive energy. The filament tubes are manufactured from quartz or special high temperature glass. For general purpose applications, the quartz or high temperature glass filament tube is enclosed in a larger glass envelope to protect the user should the filament tube explode and to protect the filament tube from environmental contaminants, such as salts from human fingers.

Since 90% to 95% of the energy consumed by an incandescent lamp is radiated as infrared energy, it is easy to see that the potential exists to dramatically increase the efficacy of incandescent lamps by reflecting some of this infrared energy back onto the filament, thus allowing the filament to be maintained at its normal operating temperature with far less electrical power. The reflector must have very low absorption in the visible region of the spectrum, high reflectivity in the IR and a reasonably sharp transition between the two, because the greatest IR emission is just below the visible band. The reflector and filament must also be precisely positioned so that the reflected IR radiation hits the filament, and the reflector must also be low enough in cost to be commercially viable. Successful IR reflectors have been made from multilayer dielectric films. These are similar to the coatings used to make high reflectivity mirrors for He–Ne lasers, but they have much broader bandwidth and lower reflectivity. The reflector-filament alignment problem is most easily solved using the geometry of a tungsten halogen filament tube as the carrier for the IR reflector. The typical efficacy gain is about 50%: a 60-watt IR-halogen lamp produces about as much light as a 90-watt halogen lamp.

Other methods being investigated to increase the efficacy of incandescent lamps involve modification of the filament to decrease its emissivity in the IR and/or increase its emissivity in the visible, and hence turn it into more of a 'selective radiator' than natural tungsten. Three general methods are under investigation: one involves creating a dense pattern of submicron size cavities on the surface of the tungsten to inhibit IR radiation; a second involves coating the tungsten with a material that is itself a selective radiator that favors the visible portion of the spectrum, while a third involves replacing the tungsten filament with a material that is a natural selective radiator. No products exist that employ these techniques, but active R&D projects are underway that may yield a more efficient incandescent lamp in the future.

Incandescent lamps can be used as standards for total flux and color temperature if carefully constructed and operated. The National Institutes for Standards and Technology (NIST) in the US sells 1000-watt tungsten halogen lamps calibrated to an accuracy of 0.6% in luminous intensity and 8 K in color temperature at a color temperature of 2856 K. Similar service are provided by standards organizations in other countries.

Discharge Lamps

The most efficient lamps produced today are based on electric discharges in gasses. These include 'low pressure' lamps such as fluorescent lamps and low pressure sodium lamps; and 'high pressure' or high intensity discharge (HID) lamps such as metal halide, high pressure sodium, high pressure mercury, and sulfur lamps. These lamps are all more efficient than incandescent lamps because they are 'selective radiators' instead of blackbody sources and have been designed to generate as much radiant energy as possible in the visible band while minimizing energy produced outside the visible band. The best white light discharge lamps have conversion efficiencies from electric power to visible light of 25% to 30%, making them almost five times as efficient as the typical incandescent lamp.

Fluorescent Lamps

Fluorescent lamps, as shown in Figure 3, are generally constructed in a cylindrical soda lime glass envelope with a length to diameter ratio significant greater than one. Most contain thermionic electrodes at each end to generate an electric field that establishes and sustains the discharge. The lamps are filled with about 2 Torr of Argon and/or another rare gas, and a few mg of liquid mercury, while the inside surface of the tube is coated with a phosphor that converts UV radiation generated by excited mercury atoms into visible light.

As with any other low pressure gas discharge, various discharge regions are aligned along the axis of the tube:

- Aston Dark Space
- Cathode Glow
- Cathode Dark Space
- Negative Glow
- Faraday Dark Space
- Positive Column
- Anode Glow
- Anode Dark Space

The axial lengths of all these regions, except for the positive column, are fixed by the properties of the cathode and anode, the fill gas type and pressure, and the discharge current. The length of the positive column is variable and fills the space between the Faraday Dark Space and the Anode Glow. The cathode and anode regions of the discharge have a total axial length of about twice the diameter of the discharge tube. Therefore, if the length-to-diameter ratio of the discharge tube is substantially greater than one, the majority of the tube is filled by the Positive Column, as shown in Figure 3. The positive column is the part of the discharge that creates the UV photons that excite the phosphor and cause it to generate visible light. The remainder of this discussion will therefore focus on the positive column.

The basic operation of a fluorescent lamp positive is shown in Figure 4. Free electrons are accelerated by the electric field established between the two electrodes. These electrons collide with both the mercury and rare gas atoms, but selectively excite and ionize mercury atoms, since the excitation and ionization energies of mercury are significantly lower than that of any rare gas used in the lamps. Ionization of mercury creates more free electrons to sustain the discharge. The gas density in the lamp is low enough to require that most of the recombination of mercury ions and free electrons takes place on the wall of the tube, since this recombination requires a three-body collision. The excited mercury atoms generate both UV and visible photons, and the UV photons generate visible light once they reach the phosphor coated on the inner surface of the lamp.



Figure 3 Linear fluorescent lamp. © 2005 Roberts Research and Consulting, Inc. Published by Elsevier Ltd. All rights reserved.



Figure 4 Operation of fluorescent lamp positive column. © 2005 Roberts Research and Consulting, Inc. Published by Elsevier Ltd. All rights reserved.

The high efficiency of fluorescent lamps is directly related to the fact that 60% to 65% of the electric power consumed by the positive column of the fluorescent lamp discharge is converted into 245 nm UV photons as a result of the resonance transition from the 6^3P_1 state of mercury at 4.86 eV to the 6^1S_0 ground state. The resonance transition from the 6^1P_1 state of mercury generates 185 nm UV photons that carry about 10% of the energy. About 3% of the positive column energy ends up in mercury visible lines at 405 nm, 436 nm, 546 nm, 577 nm, and 579 nm.

The 245 nm and 185 nm photons generated by the excited mercury atoms travel only a fraction of a mm before they are absorbed by a ground-state mercury atom. However, due to the relative absence of other de-excitation mechanisms, a large fraction of these absorbed photons are re-emitted by the absorbing atoms, and most of the UV photons generated in the core of the discharge eventually reach the phosphor coated interior wall of the discharge tube where they are converted into visible light (and waste heat).

The phosphors used in modern fluorescent lamps are a blend of three rare-earth phosphors:

- Blue: $BaMg_2Al_{16}O_{27}:Eu^{2+}$
- Green: $CeMgAl_{11}O_{19}(Ce^{3+}):Tb^{3+}$
- Red: $Y_2O_3:Eu^{3+}$

Rare earth phosphors provide a combination of high efficiency, high color rendition index, and high resistance to degradation that far exceeds the performance of the halophosphate phosphors used in older generations of fluorescent lamps.

However, due to the Stokes Shift, there is a substantial energy loss converting the UV photons produced by excited mercury atoms into visible light, even using a 'perfect' phosphor that has quantum efficiency of 1.0. The average energy of a visible photon is 2.43 eV, using the 380 nm to 780 nm limits for visible radiation discussed at the start of this article. When one 245 nm photon that has 4.885 eV of energy is converted to one visible photon with an average energy of 2.43 eV, a bit over 50% of the photon's energy is lost. The situation is worse for the 185 nm photons, which each have 6.707 eV of energy. They lose 64% of their energy when they are converted to visible photons, so it is good that the fluorescent lamp discharge generates six to seven 245 nm photons for each 185 nm photon. The Stokes shift is responsible for the largest single energy loss mechanism in fluorescent lamps. Work is underway to develop phosphors with a quantum efficiency greater than 1.0, so less energy will be lost in the UV-to-visible light conversion process, but no practical phosphors have been developed to date.

The mercury pressure for optimum UV production is about 6×10^{-3} Torr, which is the vapor pressure of mercury over a liquid pool at 40 °C. At higher mercury pressure there is too much absorption by ground state mercury atoms, and at lower pressures there is an insufficient number of mercury atoms for excitation by the electrons. The diameter of most linear lamps is chosen so that the coolest spot on the interior of the lamp wall will be at 40 °C when the lamp is operated at its design power in an ambient temperature of 25 °C. Usually this 'cold spot' will be near the middle of the lamp, but in some higher power linear lamps the wall temperature is well over 40 °C. In these lamps a cold spot is often created at the end of the lamp by use of a longer electrode mount and a heat shield mounted between the electrode and the end of the lamp. Obviously, the performance of fluorescent lamps designed in this manner is highly sensitive to ambient temperature. In some smaller, high-power density lamps, most commonly compact fluorescent lamps (CFLs), it is not possible to create a region with a temperature as low as 40 °C. In these lamps the mercury pressure is controlled by amalgamating the mercury with Pb, Bi, or Sn, creating a compound that both reduces the mercury vapor pressure at any given temperature and also reduces the variability of mercury vapor pressure with temperature. These mercury amalgams have the secondary advantage of making the fluorescent lamp less sensitive to ambient temperature.

Mercury, which is the key ingredient in fluorescent lamps, is considered to be a hazardous material by regulatory agencies in many countries. At least as early as the mid-1980s researchers began to study ways to reduce or eliminate mercury from fluorescent lamps.

Development of a mercury-free fluorescent lamp is very difficult and the only mercury-free fluorescent lamp that exists, as of mid-2003 has an efficacy of about 10 l mW $^{-1}$, one-tenth the efficacy of the best mercury-based fluorescent lamp (Osram Sylvania LINEX® Linear Excimer Lamp System, Model LINEX A3-10W40). There are three key problems that have to be solved to develop an efficient mercury-free fluorescent lamp system:

(i) Identify a nontoxic material that generates UV photons and has its optimum gas density at a convenient and safe temperature. The most promising candidate is xenon, used as either an atomic radiator or an excimer.

(ii) Develop a phosphor that produces high-quality white light with high efficiency when excited by UV photons from the chosen mercury-replacement material. This has proven a major challenge. The resonance line of atomic Xe has a wavelength of 147 nm, while the output from a xenon excimer discharge is at 172 nm. The Stokes shift loss converting each of these to visible light is 71% for atomic xenon and 66% for xenon excimers. To reduce the Stokes shift loss, a quantum-splitting phosphor, one that generates more than one visible photon for each UV photon, is needed. Most of the effort to develop mercury-free fluorescent lamps has been concentrated in this area. No viable phosphor has been developed, but work continues.

(iii) Develop a 'reservoir' for xenon or the other working gas. The mass of 'active' gas needed for a fluorescent lamp is small; a 4-foot, 1.5-inch diameter lamp needs 0.1 mg of mercury in the gas phase to operate properly. However, during life, some of this gas is consumed through physical attachment or chemical reaction and must be replaced. The drop of liquid mercury or small mass of mercury amalgam used in conventional fluorescent lamps provides a reservoir that maintains the mercury gas pressure in the presence of these consumption mechanisms.

In contrast to the failure to develop a mercury-free fluorescent lamp, there has been great success in reducing the amount of mercury used in each lamp. A typical 4-foot, 1.5-inch diameter fluorescent lamp produced in the 1970s would have 50 mg to 100 mg of mercury. This high amount of mercury was mostly the result of the type of manufacturing equipment used, but mercury consumption required that each lamp had 15 mg to 20 mg of mercury in order to survive for its rated 20 000-hour life. The development of coatings and other materials that reduce mercury consumption, when combined with new manufacturing technology, has allowed the amount of mercury used in modern 4-foot fluorescent lamps to be reduced to 3 mg to 5 mg, and further reductions are possible with improved technology.

As stated above, the length-to-diameter ratio of most fluorescent lamps is significantly greater than one. The reason for this is that there is a 10 to 15 volt drop at the electrodes, and the power lost in these regions does not produce a significant amount of light. A large length-to-diameter ratio increases the voltage and power of the positive column, where the bulk of the UV photons are generated, relative to the power lost in the electrode regions. When the energy crunch hit in the mid-1970s, there was strong interest in developing a fluorescent lamp that could replace the inefficient incandescent lamp. However, the need for high length-to-diameter ratios meant that it would not be practical to make a fluorescent lamp shaped like an incandescent lamp. This need created the technology to manufacture CFLs which are constructed of long tubes bent or coiled into shapes that allow them to fit into spaces occupied by incandescent lamps.

Fluorescent lamps and other discharge lamps have a negative incremental voltage vs. current (V/I) characteristic, which means that their operating voltage decreases as the operating current increases. Due to this, such discharges need to be operated from a current limited power source, commonly known as a 'ballast' in the lighting industry. Ballasts were originally simple series inductors and lamps operated at the power line or mains frequency, though many line frequency ballasts are now considerable more complex than an inductor. In the 1940s, it was discovered that the efficacy of fluorescent lamps could be increased by operation at frequencies of a few kHz. It was not until the 1970s, however, until the cost of power electronics came down to the point where it was possible to make affordable high frequency electronic ballasts. Electronic ballasts operating in the 20 kHz to 100 kHz range are now used with almost all CFLs and in most commercial applications using linear fluorescent lamps.

The desire for fluorescent lamps shaped like incandescent lamps also sparked the development of electrodeless fluorescent lamps. Since the need for high length-to-diameter ratios is driven by the losses at the lamp electrodes, researchers realized they could make fluorescent lamps in short, wide shapes if they eliminated the electrodes. As shown in Figure 5, an electrodeless lamp is just like a transformer, except it has a single-turn discharge secondary instead of a multiturn copper or aluminum secondary. An open core version of an electrodeless fluorescent lamp with integral ballast is shown in Figure 6. The electric field is created by a time-varying magnetic field. Because of the relative high voltage-per-turn imposed by the discharge secondary, these lamps operate only at high frequency. There are three electrodeless fluorescent lamps on the market. The closed core design


Ferrite core
AC power in
$\bar{E}$
$\bar{E}$
A
$\bar{B}$
$\oint_c \bar{E}\cdot d\bar{l} = -\frac{\partial}{\partial t}\int_s \bar{B}\cdot d\bar{S}$

Figure 5 Basic electrodeless fluorescent lamp with closed ferrite core. © 2005 Roberts Research and Consulting, Inc. Published by Elsevier Ltd. All rights reserved.



Figure 6 Open core electrodeless lamp with integral ballast. © 2005 Roberts Research and Consulting, Inc. Published by Elsevier Ltd. All rights reserved.

shown in Figure 7 operates near 250 kHz with an external ballast, while the open core design shown in Figure 8 operates near 2.5 MHz. Figure 9 shows an open core design with an integral ballast that also operates near 2.5 MHz. Some people have suggested that electrodeless fluorescent lamps are fundamentally different from normal fluorescent lamps and the high frequency field drives the phosphor to emit light. This is incorrect. Other than the manner in which the electric field is created, and the new shapes this allows, electrodeless fluorescent lamps operate in the same manner as normal fluorescent lamps.

Due to the strong dependence of fluorescent performance on mercury temperature, these lamps are not useful as flux standards. However, the five mercury visible lines listed above, plus the 365 nm line of mercury, make the ordinary fluorescent lamp an ideal source for wavelength calibration of spectrometers. Germicidal lamps, which do not use phosphor but are constructed in quartz envelopes and use the same type of mercury-rare gas discharge as fluorescent lamps, are a convenient source of 254 nm radiation that can be used to calibrate UV spectrometers. Care should be taken when using these lamps, as the 254 nm radiation can damage human eyes and skin.

High Intensity Discharge Lamps

If the mercury pressure in a discharge lamp is raised from 6×10^{-3} Torr to an atmosphere or



Figure 7 Closed core electrodeless fluorescent lamp, Osram Sylvania Icetron/Endura Lamp, from US Patent 5,834,905.



Figure 9 GE Genura® open core electrodeless fluorescent lamp with integral ballast. Courtesy of General Electric Company.



Figure 8 Open core electrodeless fluorescent lamp with separate ballast, Philips QL lamp, from US Patent 6,373,198 B1.

greater, the 245 nm and 185 nm resonance lines are trapped via absorption by ground-state mercury atoms and the radiation output from the discharge shifts to the five optically thin visible lines listed in the discussion of fluorescent lamps, plus the 365 nm near-UV line and a number of lines near 300 nm. The result is a high pressure mercury lamp that operates with an efficacy of about $55\,\mathrm{l\,m\,W^{-1}}$ and has a CRI of about 50. The high-mercury vapor pressure requires a wall temperature of at least 360 °C, which in turn requires that the arc tube be constructed from quartz and operated at high power density. A 400-watt high-pressure mercury arc tube has a diameter of 22 mm and length of about 100 mm. In contrast, a 32-watt fluorescent lamp has a diameter of 25.4 mm and a length of about 1200 mm. This accounts for the classification of these high pressure lamps as high intensity discharge (HID) lamps. Due to the high temperature of the arc tube, most HID lamps are constructed with the arc tube mounted inside a hard glass outer jacket that protects both the user and the arc tube. The high-pressure mercury lamp is a direct visible radiator, but the arc tube does generate a small amount of radiation in the 254 nm to 365 nm region, that radiation is trapped by the outer glass jacket. Some high-pressure mercury lamps have a phosphor coating on the inside of the outer jacket to convert this UV radiation into visible radiation, mostly in regions of the spectrum where the high-pressure mercury arc is deficient in radiation, thus improving the color of the lamp.

Most high-pressure mercury lamps operate at a mercury pressure of about four atmospheres. Because their spectrum is dominated by mercury line emission, the output of these lamps is deficient in the red portion of the spectrum and the lamps have poor color rendition. In 1992, Philips received a US patent for a new type of ultra-high pressure mercury lamp that they call UHP for ‘Ultra High Performance’. This lamp operates at a mercury pressure of 200 atmospheres or more. The output spectrum is characterized by a significant amount of continuum radiation from quasi-molecular states of mercury and this continuum includes energy in the red portion of the spectrum that is missing from conventional high pressure mercury lamps. UHP lamps also include a small amount of halogen, such as bromine, which creates a tungsten-halogen cycle similar to that discussed earlier in relation to tungsten-halogen incandescent lamps. During lamp operation, tungsten is sputtered and evaporated from the electrodes. In the absence of the halogen fill, this tungsten rapidly deposits on the walls, leading to very short lamp life. The halogen combines with most of the tungsten before it has a chance to reach the wall of the arc tube. The halogen will also combine with any tungsten that has deposited on the wall of the arc tube. The tungsten-halogen compound formed is gaseous at the operating temperature of the lamp and will diffuse back toward the core of the discharge where the high temperature of the arc dissociates the tungsten-halogen compound. The tungsten is deposited back on the electrodes, thereby greatly extending the life of the lamp. Due to their very high pressures, UHP lamps are constructed in small discharge tubes and have a very short discharge length, typically 1 to 2 mm, making these lamps a virtual point source. Due to their excellent spectral characteristics and small source size, UHP lamps have found application in various projection applications, including LCD-based electronic projectors.

The performance of high-pressure mercury lamps can be substantially improved by adding metals such as sodium and scandium to the high-pressure mercury arc. The sodium emits near the peak of the eye sensitivity curve, providing high efficacy, while the scandium has many transitions in the visible, which fill out the spectrum and provide high CRI. If metallic elements are added directly to the high-pressure mercury arc they would deposit on or react with the wall of the arc tube. To prevent this they are added as iodides, such as NaI or $\mathrm{ScI_3}$. This creates a regenerative cycle in which the NaI and $\mathrm{ScI_3}$ are heated and dissociated in the 5000 K core of the arc, allowing the free metals to radiate. As the metals diffuse toward the cooler sections of the arc near the walls, they recombine with the iodine to reform the iodides. These metal halide lamps have produce light with an efficacy of about $90\,\mathrm{l\,m\,W^{-1}}$ to $100\,\mathrm{l\,m\,W^{-1}}$ and a CRI of about 65 to 75.

The high-pressure sodium (HPS) lamp is an HID lamp that uses hot sodium vapor to generate a golden white light. The lamp uses a mixture of sodium, mercury, and rare gas such as xenon. The core temperature of the sodium-mercury-xenon discharge is typically about 4000 K, while the temperature at the edge of the discharge and the walls of the ceramic arc tube is typically about 1500 K. At low pressure, emission from sodium is dominated by the resonance lines at 589.0 and 589.6 nm, so the light is virtually monochromatic. However, in the HPS lamp, the sodium pressure is typically 75 Torr, which is high enough to almost completely trap emission from the resonance lines, forcing radiant energy to escape in the wings of these lines, thereby increasing the color quality of the light. Since sodium will attack quartz, this mixture is contained in a translucent alumina (aluminum oxide) ceramic arc tube. As with other HID lamps, the alumina arc tube is contained in a hard glass outer bulb. HPS lamps are the most efficient generators of 'white light' available. A typical 400 watt HPS lamp produces light with an efficacy of $125\,\mathrm{l\,m\,W^{-1}}$, this high efficacy being due to the fact that the emission matches the peak of the eye sensitivity curve. The light has a CRI of only 22; however, the HPS lamp is widely used for roadway and other outdoor lighting applications.

Solid State Sources

The newest incoherent sources to be used for general purpose lighting are solid state devices: light emitting diodes (LEDs), and organic light emitting diodes (OLEDs). LEDs are very similar to laser diodes but without the two mirrors used to form the laser cavity in laser diods. Photons are generated as a result of electron-hole recombination as electrons move across the energy gap of a biased p-n junction. By appropriate selection of materials, photons can be created at visible wavelengths. Low brightness infrared and red LEDs have been available for quite some time. It was not until the mid-1980s that high brightness red LEDs were developed. These were followed by increasingly more challenging yellow, green, and then blue high brightness LEDs, developed in 1994 by Shuji Nakamura, of Nichia Chemical Industries. Nakamura added phosphor to his high brightness blue LEDs in 1996 and developed the first 'white' LED, thus triggering the current level of excitement concerning the use of LEDs to replace incandescent and discharge lamps. Monochromatic high brightness LEDs have already replaced color-filtered incandescent lamps in many applications, such as traffic lights, vehicle signal lights, and signage. In these applications, LEDs are the clear winner in life and efficacy. However, when compared to unfiltered sources, the best white LEDs are about as efficient as tungsten halogen incandescent lamps and far less efficient than fluorescent and metal halide lamps. They also cost far more per lumen than even the most expensive discharge lamp. LEDs have high internal quantum efficiency, so the main technical challenges are to fabricate devices to minimize internal light trapping in order to improve device efficiency and reduce the cost per lumen produced.

Organic light emitting diodes (OLEDs) generate light by the passage of electric current through special organic molecules, using a process known as electrophosphorescence. The electrophosphorescent material is usually coated on a transparent and perhaps flexible substrate, and overcoated with a transparent conductor. OLEDs currently have lower efficacy and shorter life than LEDs, but they also have lower manufacturing costs. If LEDs are the 'new' point sources that replace incandescent lamps and perhaps CFLs, then OLEDs are the 'new' diffuse sources that some say will replace liner fluorescent lamps.

See also

Light Emitting Diodes.

Further Reading

Cobine JD (1958) *Gaseous Conductors: Theory and Engineering Applications*. New York: Dover Publications.

de Groot JJ and van Vliet JAJM (1986) *The High Pressure Sodium Lamp*. Philips Technical Library. Deventer–Antwerprn: MacMillian Education.

Elenbass W (1951) *The High Pressure Mercury Vapor Discharge*. Amsterdam: North-Holland Publishing Company.

Fisher HE (1996) *High Pressure Mercury Discharge Lamp*, U.S. Patent, 5,497,049.

Fisher HE and Hörster H (1998) *High-Pressure Mercury-Vapor Discharge Lamp*, U.S. Patent 5,109,181.

Godyak VA (2002) Bright Idea: Radio-frequency light sources. *IEEE Industry Applications Magazine* 8: 42–49.

Hirsh MN and Oskam HJ (1978) *Gaseous Electronics, Volume 1, Electrical Discharges*. New York: Academic Press.

Mitchel AGC and Zemansky MW (1971) *Resonance Radiation and Excited Atoms*, 2nd edn. London: Cambridge University Press.

Nichia's Shuji Nakamura: Dream of the Blue Laser Diode, ScienceWatch, January/February 2000. Available at: http://www.sciencewatch.com/jan-feb2000/sw_jan-feb2000_page3.htm

Pekarski P, Hechtfischer U, Heusler G, Koerber A, Moonch H, Retsch JP, Weichmann U and Kitz A (2003) *UHP Lamps for Projection Systems*, XXVI International Conference on Phenomena in Ionized Gasses, Greifswald, Germany. Available at: http://www.icpig.uni-greifswald.de/proceedings/data/Pekarski_1

Raizer YP (1991) *Gas Discharge Physics*. Berlin: Springer-Verlag.

Rea MS (2000) *IESNA Lighting Handbook*, 9th edn. New York: Illuminating Engineering Society of North America.

Roberts VD (2003) *Radio-Frequency Lighting*. McGraw-Hill Yearbook of Science & Technology, pp. 349–352. New York: The McGraw-Hill Companies, Inc.

Schewe PF and Stein B (1999) *Physics News Update*, Number 437 (Story #2), The American Institute of Physics Bulletin of Physics News. Available at: http://www.aip.org/enews/physnews/1999/split/pnu437-2.htm

Waymouth JF (1971) *Electric Discharge Lamps*. Cambridge, Massachusetts: MIT Press.

Wharmby DO (1993) Electrodeless Lamps for Lighting: A Review. *IEE Proceedings-A* 140(6): 465–473.

Synchrotrons

R Clarke, University of Michigan, Ann Arbor, MI, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Since their discovery by Röntgen in 1895, X-rays have been used in a wide variety of applications ranging from medical and industrial radiography to crystallographic studies of the structure of biomolecules. The short wavelength ($\lambda \sim 0.1$ nm) and high penetrating power of hard X-rays makes them an ideal probe of the internal structure and composition of condensed matter. Indeed, Watson and Crick's elucidation of the double helix structure of DNA in the early 1950s, based on the X-ray diffraction patterns of Rosalind Franklin, has revolutionized biology and provided an atomistic view of the stuff of life.

The quest for ever higher spatial resolution, and the desire to obtain high-quality X-ray data on shorter time-scales, have both been prime motivations for the development of high intensity hard X-ray sources since the mid-1970s. This evolutionary trend has led to the design and construction of large synchrotron radiation facilities, serving many thousands of users and enabling forefront experimental studies across a broad range of disciplines. One such example of a national facility, dedicated to high-brightness X-ray synchrotron radiation, is the Advanced Photon Source (APS), located at Argonne National Laboratory in the United States (Figure 1). Facilities of a similar scope and purpose have also been constructed in Europe and Japan, and a number of new high brightness sources are currently under construction in several countries around the world (see Table 1).



Figure 1 Aerial view of the Advanced Photon Source, Argonne National Laboratory. Courtesy of Advanced Photon Source.

Table 1 Third-generation synchrotron radiation sources

Location	*Facility*	*Electron energy (GeV)*
Grenoble, France	European Synchrotron Radiation Facility (ESRF)	6
Argonne, Illinois, USA	Advanced Photon Source (APS)	7
Nishi Harima, Japan	8-GeV Super Photon Ring (SPring-8)	8
Berkeley, CA, USA	Advanced Light Source (ALS)	1.5–1.9
Canberra, Australia	Boomerang[a]	3
Didcot, UK	DIAMOND[a]	3
Orsay, France	SOLEIL (LURE)	2.75
Karlsruhe, Germany	Angströmquelle-Karlsruhe (ANKA)	2.5
Hamburg, Germany	PETRA III[b]	6
Indore, India	INDUS II[a]	2.5
Villigen, Switzerland	Swiss Light Source (SLS)	2.4
Saskatoon, Canada	Canadian Light Source[a]	2.9
Stanford, CA, USA	SPEARS	3
Upton, New York, USA	NSLS II[b]	2.5–2.8
Trieste, Italy	Elettra	2.0–2.4

[a] Under construction as of March 2004.
[b] Planning stage.

In this article we will draw on examples from APS to illustrate the characteristics and performance of the current generation of synchrotron sources in the hard X-ray region.

From the earliest days of particle physics studies in the 1930s and 40s, it was realized that copious amounts of X-rays could be produced by accelerating charged particles in a curved trajectory, as in a cyclotron or a synchrotron. For particle physics such radiation is highly detrimental because it limits the ultimate energy of particle accelerators and forces their circumference to become inordinately large in order to reduce radiation losses.

Originally considered to be a major source of concern in particle accelerator design, synchrotron radiation soon began to emerge as a boon to X-ray science. This came about in the early 1970s after the capability was developed to produce and store significant circulating currents of high-energy charged particles (electrons or positrons) for colliding beam experiments. At that time X-ray scientists were tolerated as 'parasitic' experimenters at such storage rings, taking X-ray radiation from the bending magnets which maintained the stored current in an overall circular trajectory. The PETRA (Positron–Electron Tandem Ring Accelerator) facility at HASYLAB/DESY in Hamburg, Germany, and the Cornell Electron Storage Ring (CESR)/Cornell High-Energy Synchrotron Source (CHESS) at Cornell University, Ithaca, New York, are examples of accelerator facilities that were primarily intended for particle physics experiments and then became partly dedicated to X-ray production. Such shared synchrotron facilities are referred to as 'first-generation sources'.

The first generation sources demonstrated several attractive features of synchrotron radiation, including a high degree of collimation in the vertical direction with a divergence half-angle given approximately by the relativistic factor $\gamma^{-1} = m_0c^2/E$, where m_0c^2 is the rest-mass energy (0.51 MeV) of the electron (or positron) and E is the energy of the stored particle beam. For a bending magnet source with $E = 2-3$ GeV the beam would have a vertical collimation of ~ 0.3 mrad (17 mdeg). This would produce an X-ray beam with a vertical extent of ~ 3 mm at a distance of 10 m from the bending magnet source. The horizontal fan of bend magnet radiation is broad and is usually limited by a mask or a slit to a few mrad. The most useful characteristic of bend magnet radiation is its large bandwidth whereby the X-ray spectrum is continuous and increasing in intensity (see Figure 2) until some critical energy above which the intensity begins to fall off. Bending magnet radiation is therefore useful for X-ray measurements requiring a 'white' beam, for example, Laue X-ray diffraction, energy dispersive diffraction, and Extended X-ray Absorption Fine Structure (EXAFS) analysis.

Beginning in the 1980s, several second-generation storage rings were constructed in various locations around the world. The design of these facilities for the first time was optimized for the production of bright beams of X-ray and XUV (soft X-ray to ultraviolet) and their operation was dedicated exclusively to synchrotron radiation science. The increase in brightness provided by these new storage ring sources, compared to standard laboratory X-ray sources (e.g., rotating anode generators), was dramatic (5 or 6 orders of magnitude) and this opened up many new experiments that were not previously feasible. However, it was soon realized that the capabilities of such sources could be extended to



Figure 2 Comparison of bending magnet and wiggler sources. With permission from Stanford Synchrotron Radiation Laboratory, Stanford Linear Accelerator Center, Menlo Park, CA.

even higher levels of intensity and to significantly higher X-ray energies.

One of the limitations of bending magnet sources relates to the X-ray critical energy alluded to above:

$$E_c = 3\hbar c\gamma^3/4\pi\rho \qquad [1]$$

where ρ is the radius of curvature imposed on the particle beam trajectory by the bending magnet. For a given particle acceleration energy, E, eqn [1] leads to a critical X-ray energy given by:

$$E_c\,(\text{keV}) = 2.2\,E^3\,(\text{GeV})/\rho\,(\text{m}) \qquad [2]$$

For a typical second-generation machine with $E = 2.5$ GeV and $\rho = 7$ m (limited by the magnetic field generated by the dipole electromagnet), the critical energy is only about 5 keV. There is useable flux well above this energy, but X-ray photons become scarce in the energy range above 10 keV for a bending magnet source with these characteristics. Since E is effectively fixed by the design parameters of the storage ring, the only possibility to achieve higher photon energies is to install additional magnetic devices which will introduce perturbations of the trajectory with effectively smaller radius of curvature in the denominator of eqn [2]. Such a device, known as a 'wiggler', shifts the effective critical X-ray energy to higher values in proportion to the strength of the magnetic field B (see Figure 2). Using wigglers based on superconducting magnets ($B \sim 5$ Tesla), E_c can be raised to >20 keV, a value which would require accelerator energies of more than 6 GeV using conventional bending magnets alone. In addition to shifting the output spectrum to higher energies, it is possible to enhance the intensity at a given energy by producing multiple wiggles with no net displacement of the particle trajectory. Multipole wigglers are able to produce significant increases in flux in the hard X-ray range. The 27-pole hybrid wiggler installed on beamline X25 at the National Synchrotron Light Source, a second generation facility at Brookhaven National Laboratory, Upton, New York, is one of the most successful designs of its kind, providing $\sim 6 \times 10^{14}$ photons/sec per 1% bandwidth at 8 keV. When focused with a toroidal X-ray mirror, this beam is about an order of magnitude brighter than the standard bending magnet sources at NSLS. For reasons that will become clear later in this article, the radiation from multiple wiggles in such a device adds incoherently.

Insertion Devices

The idea of using wigglers to enhance the characteristics of synchrotron radiation sources has led to the design and construction of storage rings with many straight sections to accommodate wigglers and other types of 'insertion devices'. Such facilities are referred to as third-generation sources. Coming on-line in the mid-1990s, several such sources are now in mature operation and are supporting a large international community of X-ray scientists.

One of the most important types of insertion device to emerge from the development of third-generation facilities is the undulator. Conceptually, the idea behind an undulator is similar to that of the wiggler, i.e., it provides additional tightly curved transverse displacements in the particle beam. There are two important differences: in an undulator the displacements are smaller and they are more numerous, being produced by a linear periodic array of many short alternating dipoles (Figure 3). Under these conditions the synchrotron radiation emitted from each 'undulation' of the particle beam trajectory adds coherently and therefore the peak intensity from such a device can be enhanced by a factor of N^2 where N is the number of dipole magnet pairs, or periods.

A simple theoretical description of the basic operation of an undulator can be discussed in terms of radiation from a charged particle moving at



Figure 3 Schematic of undulator. Courtesy of Advanced Photon Source.

relativistic speeds through an alternating magnetic field. The magnetic field in the vertical direction (y) is taken to be periodic:

$$B_y = B_0 \sin[(2\pi/\lambda_u)z] \qquad [3]$$

where z is in the direction of average particle motion.

The transverse particle trajectory is described by:

$$x = (\lambda_u \phi_{\max}/2\pi)\sin[(2\pi/\lambda_u)z] \qquad [4]$$

where λ_u is the magnet period, and $\phi_{\max}$ is the maximum particle deflection angle:

$$\phi_{\max} = (eB_0\lambda_u c)/2\pi m_0 c^2 \gamma = K/\gamma \qquad [5]$$

where

$$K = 93.4 B_0\ (\text{Tesla})\lambda_u\ (\text{meters}) \qquad [6]$$

The field strength parameter K serves as a useful quantity for discussing the characteristics of various insertion device designs. For $K \le 1$, which defines the undulator regime, the transverse angular deflections are less than or on the order of the angular spread of the emitted radiation and in this case the radiation from each of the deflections adds coherently. This is distinguished from the case of a multipole wiggler where $K \gg 1$ leading to incoherent superposition.

Most of the interesting features of undulator radiation are revealed by considering the trajectory of the particle in a Lorentz frame moving at speed v^* with respect to the laboratory frame. In this frame the particle will execute oscillatory motion with the period of oscillations T' given by the Lorentz transformation:

$$T' = \gamma^*(T - \beta^*\lambda_u/c) = \lambda_u/(v^*\gamma^*) \qquad [7]$$

with a corresponding oscillation frequency $\omega' = 2\pi/T' = (2\pi c/\lambda_u)\gamma^*$.

For $K \ll 1$, the motion in the co-moving frame is purely transverse and nonrelativistic. However, for $K \sim 1$, the oscillatory motion in this frame can have a longitudinal component and in this case the transverse motion becomes nonharmonic with frequency components at odd multiples of the fundamental frequency ω'. This nonharmonic motion is a consequence of the fact that in the laboratory frame the particle is moving with constant speed $\approx c$ but its path length is slightly longer than λ_u, owing to the transverse motion. This constrains the motion in the co-moving frame to be nonharmonic.

Undulator Spectrum

It now remains to transform ω' into the laboratory frame so that we can obtain the spectral distribution of the output of the undulator. Invoking the Doppler transformation:

$$\omega = \gamma^*\omega'(1 + \beta^* \cos\theta') \qquad [8a]$$

$$\tan\theta = (\sin\theta')/[\gamma^*(\cos\theta' + \beta^*)] \qquad [8b]$$

where θ is the angle at which the radiation is observed:

$$\omega_n(\theta) = (4\pi c n \gamma^2)/(\lambda_u[1 + \tfrac{1}{2}K^2 + (\gamma\theta)^2]) \qquad [9a]$$

or in terms of wavelength:

$$\lambda_n(\theta) = (\lambda_u/2n\gamma^2)[1 + \tfrac{1}{2}K^2 + (\gamma\theta)^2] \qquad [9b]$$

Equation [9] is the central expression describing the spectral output of an undulator. Notice how the macroscopic period of the undulator λ_u is transformed into a microscopic wavelength $\lambda_n(\theta)$ by the relativistic factor γ^2. For third-generation hard X-ray sources with particle energies in the 6–8 GeV range, $\gamma \sim 14\,000$, taking cm scales down to the angstrom level.

Equation [9] describes a spectrum of monochromatic peaks, for on-axis radiation ($\theta = 0$), with wavelengths that increase with increasing K. Since $K \sim B_0\lambda_u$ (eqn [6]) any particular harmonic can be tuned either by changing B_0 or λ_u. In most undulator designs, λ_u is fixed by the construction of the permanent magnet array, so the tuning is conveniently accomplished by varying B_0. In practice this is done by changing the vertical distance between the poles



Figure 4 Undulator spectrum (upper panel) and tuning range for first, third and fifth harmonics (lower panel) of Advanced Photon Source Undulator A.

of the magnets (the 'undulator gap') similar to opening the jaws of a vise. Typical tuning ranges for the $n = 1$, 3, and 5 harmonics are illustrated in Figure 4.

Since the number of undulator oscillations of the particle beam is finite, the nth harmonic is not strictly monochromatic and has a spectral broadening of order $1/nN$, where N is the number of oscillator periods. In practice with N typically ~100, a bandwidth of ~1% is expected for the first harmonic. Additional broadening of a similar magnitude might also be expected from the θ-dependence in eqn [9], depending on the acceptance angle of the optics that is used in a particular experiment. This quasi-monochromatic radiation is sometimes referred to as 'pink beam'.

The storage ring energy of the APS was carefully chosen so that the tuning ranges of the different harmonics would overlap in energy, thus providing a continuous tuning of the X-ray energy over a wide range (Figure 4). Note also that the discrete spectral characteristics of the undulator can be deliberately smeared out to mimic the broadband (white beam) characteristics of a bend magnet (with consequent reduction in brightness). This is done simply by tilting the jaws of the undulator with respect to each other so that B_0 is made to vary along the length of the undulator. The ability to taper the undulator in this way is a standard feature of most designs.

The radiation from an undulator is sharply peaked in the forward direction in both the vertical and horizontal directions. The half-angle of the emission cone is given by:

$$\theta_{1/2} = (1/\gamma)[(1 + \tfrac{1}{2}K^2)/2Nn]^{1/2} = [\lambda_n/L]^{1/2} \qquad [10]$$

where L is length of the undulator. For a typical third-generation source undulator, such as the Type A undulator at the Advanced Photon Source, $L = 2.4$ m, giving $\theta_{1/2} \approx 6$ μrad for the first harmonic tuned to 12 keV. This corresponds to an X-ray beam size of ~180 μm at a distance 30 m from the source.

The very tight collimation of undulator radiation (eqn [10]) highlights the importance of distinguishing between the brightness and the 'brilliance' of the beam. The latter term takes into account the natural collimation of the beam, as reflected in its units of photons/sec/mm^2/mrad^2/0.1% bandwidth. Undulator radiation is well matched to the acceptance angle of ideal crystal monochromators and is ~10 000 times more brilliant than the radiation from a bend magnet source. The high brilliance of undulator X-ray beams is extremely advantageous in X-ray imaging applications, X-ray microprobe measurements, and in experiments where the sample size is very small (e.g., high-pressure diamond anvil cell measurements).

In practice the emission cone of the source might be broadened a little when the undulator characteristics are convolved with those of the storage ring. The largest effect is in the horizontal direction where the photon beam divergence is dominated by the electron beam divergence. This is a consequence of the particular conditions under which the storage ring is operated in order to stabilize the particle beam orbit.

Equation [10] demonstrates that preserving the exquisite performance capabilities of an undulator insertion device places severe demands on the stability and precision of the storage ring orbit. An important measure of this precision is characterized by the 'emittance' of the particle beam defined in terms of the area of phase space (position and angular divergence) occupied by the stored beam. In general, storage rings are designed to achieve very low emittances and in current third-generation sources they are close to being diffraction limited. Table 2 summarizes the characteristics of the APS storage ring operated in 'high-emittance' and 'low-emittance' modes.

The large power densities resulting from the extreme brightness of undulator sources (up to 160 kW/mrad^2 for APS Undulator A) necessitates careful design of the X-ray optical components that are used to condition the beam. For example, if a double-bounce Silicon crystal pair is used as the first optical component to monochromatize the undulator

Table 2 Advanced photon source storage ring parameters

Parameter	*Low emittance*	*High emittance*
Storage ring energy, E	7.0 GeV	7.0 GeV
Storage ring current, I	100 mA	100 mA
Beam energy spread, $\delta E/E$	0.096%	0.096%
Horizontal emittance, ε_x	3.5×10^{-9} m-rad	7.7×10^{-9} m-rad
Vertical emittance, ε_y	3.5×10^{-11} m-rad	7.7×10^{-11} m-rad
Coupling constant	1%	1%
Horizontal beta function, β_x	14.4 m	16.1 m
Vertical beta function, β_y	4.0 m	4.3 m
Dispersion function, η_x	0.124 m	0.0 m
Horizontal beam size, σ_x	254 μm	351 μm
Vertical beam size, σ_y	12 μm	18 μm
Horizontal beam divergence, $\sigma_{x'}$	15.6 μrad	21.8 μrad
Vertical beam divergence, $\sigma_{y'}$	3.0 μrad	4.2 μrad

beam, the first crystal is normally cooled with liquid nitrogen to dissipate the heat. Alternately, high thermal conductivity diamond crystals are sometimes used as monochromators.

Helical Undulators

The use of undulators to produce extremely bright, tunable X-ray beams has enabled many new applications of X-ray science, as well as offering significant improvements to existing techniques in terms of quality of data and the time required to accumulate a high degree of statistical accuracy. One of the areas that has benefited significantly from novel undulator design is research on magnetic materials and other spin-dependent phenomena. It is often advantageous to probe such systems with circularly polarized X-rays, for example to study magnetic X-ray circular dichroism (MXCD). Early MXCD measurements utilized the left and right elliptical polarization of bending magnet radiation above and below the plane of the ring. Such measurements are difficult because the intensity falls off dramatically out of the plane. The problem to produce high-brightness beams of circularly polarized X-rays is effectively solved by designing an undulator which produces a transverse periodic helical magnetic field of constant magnitude. Several helical undulators are now in operation at third-generation sources. The soft X-ray region (500–1500 eV) is particularly interesting because it covers the L-edges of the 3d transition elements.

Coherence

While this article describes what would be nominally considered as 'incoherent' sources in the parlance of conventional optics, it should be pointed out that undulators are in fact excellent sources of coherent X-rays. This is by virtue of the high degree of collimation inherent in the emission of radiation from the undulations of a highly relativistic charged particle (eqn [10]). The spatial (transverse) coherence angle is given by:

$$\lambda_n/2d \qquad [11]$$

where d is the source size. This is the angle within which the beam is spatially coherent.

For APS undulator A, the source size is ~15 μm (vertical) × 240 μm (horizontal), giving a coherence angle in the vertical direction of 6.5 μrad and 0.4 μrad in the horizontal direction. The X-ray beam divergence is approximately 4 μrad (vertical) by 15 μrad (horizontal). This means that the beam has complete spatial coherence in the vertical direction and is coherent over about 3% of the horizontal fan. At a distance of 30 m from the source, an on-axis pinhole of ~12 micron diameter will be completely illuminated by coherent X-rays. Transversely coherent X-ray beams are finding novel applications in X-ray photon correlation spectroscopy, coherent X-ray scattering, and phase reconstruction (lensless) imaging.

Timing Structure

X-ray storage rings produce pulsed X-rays. In the Advanced Photon Source, one or more long trains of electron bunches (15 ns long) are accelerated by the linac to 325 MeV. The electron bunches are injected into a booster that ramps the single bunch from 325 MeV to 7 GeV in about 225 ms. At the end of the booster cycle, the bunch is extracted and injected into the storage ring. The bunch can be injected into any of 1296 'buckets' that are spaced by 2.842 ns, forming any arbitrary pattern after several injection cycles.

The APS storage ring rf frequency of 351.927 MHz determines the bucket spacing of 2.842 ns. The circumference of 1104 m gives a revolution frequency of 271.5 kHz which allows for 1296 buckets in 3683 ns. The storage ring is filled with a selected bunch pattern depending on the requirements for a particular operations cycle. The standard 'singlets' bunch pattern at APS is 102 mA of average current in a train of 23 bunches (4.43 mA per bunch) each spaced by 153 ns (54 buckets). There is a gap of 306 ns (108 buckets) in this pattern, useful as a timing guide. The singlets pattern has a lower lifetime than patterns with less charge per bunch, due to natural internal scattering processes. A 'top-up' mode has been devised to overcome the problem of overall intensity fall-off due to the exponential decay of the stored current. In top-up mode, new bunches are injected into the storage ring every few minutes to maintain the stored current at 102 mA.

A second fill pattern, known as the 'hybrid' pattern, is again 102 mA but distributed in one bunch of 5 mA, plus 8 groups of 7 consecutive bunches (1.73 mA/bunch), spaced by 68 ns (24 buckets). The 8 groups are diametrically opposite the 5 mA bunch, allowing for a 1.5 μs gap on both sides of the 5 mA bunch. This hybrid mode permits a single bunch to be isolated using a mechanical chopper or a fast framing camera. Since the RMS width of the single bunch is ~36 ps, relatively fast time-resolved experiments can be performed stroboscopically using this pulsed X-ray beam. In another implementation of time-resolved experiments, the singlet pattern is used, isolating each bunch with a fast avalanche photodiode detector, or an X-ray streak camera. With the streak camera it is possible to achieve time resolutions of a few picoseconds. This approach has been used to study impulsive phonon excitations and ultrafast strain wave propagation in solids.



Figure 5 Comparison of spectral brilliance of X-ray sources. Courtesy of Linear Coherent Light Source, Stanford Linear Acceleration Center.

The Future

This article highlights current (third-generation) storage ring sources based on undulator-type insertion devices. These sources will provide high-brightness tunable X-rays in support of a wide range of experiments for many years to come. The brightness of these sources will increase steadily into the future as continual improvements are made, such as further reducing the emittance of the particle beam, improved undulator design, increasing the average storage ring current, and making changes to the storage ring lattice. These incremental improvements will be important to maintain the vitality and usefulness of national user facilities based on third-generation sources. New storage ring sources with designs and specifications optimized for low emittance and new types of undulators (e.g., in-vacuum undulators) will come online and will undoubtedly lead to new technical advances, supporting new and exciting science. It seems likely that linear accelerator (linac) based undulator sources will provide a promising route towards higher brilliance in the future. The superconducting Energy Recovery Linac (ERL) proposed by CHESS is an interesting concept which uses regeneration of the electron beam to overcome the high energy cost of single pass particle acceleration.

A new generation of X-ray sources (the 'fourth generation') is envisioned to take on the task of providing vastly brighter beams (>10 orders more peak brilliance than at present, see Figure 5) with much shorter pulses (~100 fs). These facilities will also be based on linear accelerators. Two such *Free Electron Laser* sources are currently being designed and should be operational towards 2010: the Linac Coherent Light Source (LCLS), to be built at the Stanford Linear Accelerator Center (SLAC), and the X-ray Free Electron Laser (XFEL) Source, to be constructed by the TESLA collaboration at HASYLAB, Hamburg.

See also

Coherence: Overview. **Physical Applications of Lasers:** Free Electron Lasers in Physics.

Further Reading

Brown G and Lavender W (1991) Synchrotron radiation spectra. In: Brown GS and Moncton DE (eds) *Handbook on Synchrotron Radiation*, vol. 3. Amsterdam: North Holland.

Duke PJ (1993) Synchrotron radiation sources. In: Michette AG and Buckley CJ (eds) *X-Ray Science and Technology*. Bristol: Institute of Physics Publishing Ltd.

Duke PJ (2000) *Synchrotron Radiation: Production and Properties*. Oxford, UK: OUP.

Mills DM (ed.) (2002) *Third Generation Hard X-ray Synchrotron Radiation Sources*. Berlin: Wiley, VCH.

INFORMATION PROCESSING

Contents

All-Optical Multiplexing/Demultiplexing
Coherent Analog Optical Processors
Free-Space Optical Computing
Incoherent Analog Optical Processors
Optical Bit-Serial Computing
Optical Digital Image Processing
Optical Neural Networks

All-Optical Multiplexing/Demultiplexing

Z Ghassemlooy, Northumbria University, Newcastle upon Tyne, UK

G Swift, Sheffield Hallam University, Sheffield, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The ever-increasing aggregate demand of electrically based time division multiplexing systems should have coped with the steady growth rate of voice traffic. However, since 1990, the explosive growth of the Internet and other bandwidth-demanding multimedia applications, has meant that long-haul telecommunication traffic has been increasingly dominated by data, not voice traffic. Such systems suffer from a bandwidth bottleneck due to speed limitations of the electronics. This limits the maximum data rate to considerably less than the THz bandwidth offered by an optical fiber. Optical technology is proposed as the only viable option and is expected to play an ever increasing role in future ultrahigh-speed links/networks. There are a number of multiplexing techniques, such as space division multiplexing (SDM), wavelength division multiplexing (WDM), and optical time division multiplexing (OTDM), that are currently being applied to effectively utilize the bandwidth of optical fiber as a means to overcome the bandwidth bottleneck imposed by electrical time division multiplexing (TDM). In SDM a separate optical fiber is allocated to each channel, but this is the least preferred option for increasing channel numbers. In WDM, a number of different data channels are allocated to discrete optical wavelengths for transmission over a single fiber. Dense WDM technology has been improving at a steady rate in recent years, with the latest systems capable of operating at a data rate of >1 T bps, using a large number of wavelengths over a single fiber link. However, there are a number of problems associated with the WDM systems such as:

- Performance of WDM is highly dependent on the nonlinearities associated with fiber, i.e.:
  - *Stimulated Raman scattering*: degrades the signal-to-noise (SNR) as the number of channels increases;
  - *Four-wave mixing*: limits the channel spacing;
  - *Cross-phase modulation*: limits the number of channels.
- Relatively static optical paths, thus offering no fast switching with high performance within the network;

- Switching is normally carried out by separating each wavelength of each fiber onto different physical outputs. Space switches are then used to spatially switch the separated wavelengths, an extremely inefficient way of utilizing network resources;
- The need for amplifiers with high gain and flat spectra.

In order to overcome these problems, OTDM was introduced that offers the following:

- Flexible high bandwidth on demand (>1 Tbit/s compared to the bit rates of 2.5–40 Gbit/s per wavelength channel in WDM systems);
- The total bandwidth offered by a single channel network is equal to DWDM;
- In a network environment, OTDM provides potential improvements in:
  - Network user access time, delay and throughput, depending on the user rates and statistics.
  - Less complex end node equipment (single-channel versus multichannels).
- Self-routing and self-clocking characteristics;
- Can operate at second- and third-transmission windows:
  - 1500 nm (like WDM) due to Erbium doped fiber amplifier (EDFA);
  - 1300 nm wavelengths.
- Offers both broadcast and switched based networks.

Principle of OTDM

Figure 1 show the generic block diagram of a point-to-point OTDM transmission link, where N optical data channels, each of capacity M Gbps, are multiplexed to give an aggregate rate of $N \times M$ Gbps. The fundamental components are a pulsed light source, an optical modulator, a multiplexer, channel, add/drop unit, and a demultiplexer. The light source needs to have good stabilities and be capable of generating ultrashort pulses (<1 ps). Direct modulation of the laser source is possible but the preferred method is based on external modulation where the optical signal is gated by the electronic data. The combination of these techniques allows the time division multiplexed data to be encoded inside a subnanosecond time slot, which is subsequently interleaved into a frame format. Add/drop units provide added versatility (see Figure 2) allowing the 'adding' and 'dropping' of selected OTDM channels to interchange data at chosen points on the link. At the receiving end, the OTDM pulse stream is demultiplexed down to the individual channels at the initial M Gbps data rate. Data retrieval is then within the realm of electronic devices and the distinction between electronic and optical methods is no longer relevant. Demultiplexing requires high-speed all optical switching and can be achieved using a number of methods, which will be discussed in more detail below.

The optical multiplexing (or interleaving) can be carried out at the bit level (known as bit interleaving) or at the packet level (known as packet interleaving), where blocks of bits are interleaved sequentially. This is in accord with the popular conception of packet switched networks. The high data rates required and consequently narrow time slots necessitate the need for strict tolerances at processing nodes, e.g., switches. As such, it is important that the duration



Figure 1 Block diagram of a typical OTDM transmission system.

of the optical pulses is chosen to be significantly shorter than the bit period of the highest multiplexed line rate, in order to reduce the crosstalk between channels.

Bit Interleaved OTDM

A simple conceptual description of a bit interleaved multiplexer is shown in Figure 3. It uses a number of different length optical fiber delay lines (FDL) to interleave the channels. The propagation delay of each FDL is chosen to position the optical channel in its corresponding time slot in relation to the aggregate OTDM signal. Prior to this, each optical pulse train is modulated by the data stream. The output of the modulators and an undelayed pulse train, labeled the framing signal, are combined, using a star coupler or combiner, to produce the high bit rate OTDM signal (see Figure 3b). As shown in Figure 3b, the framing pulse has a higher intensity for clock recovery purpose. At the demultiplexer, the incoming OTDM pulse train is split into two paths (see Figure 4a). The lower path is used to recover the framing pulse by means of thresholding, this is then delayed by an amount corresponding to the position of the *i*th (wanted) channel (see Figure 4b). The delayed framing pulse and the OTDM pulse stream are then passed through an AND gate to recover the *i*th channel. The AND operation can be carried out all optically using, for example, a nonlinear loop mirror, a terahertz optical asymmetric demultiplexer, or a soliton-trapping gate.


Fiber
OTDM pulse stream in p_i
OTDM DEMUX
Splitter
OTDM
αp_i
$P_i(1-\alpha)$
OTDM MUX
Fiber
OTDM pulse stream out
All optical clock extraction
Synchronization
Drop a channel
Add a channel

Figure 2 Add/drop unit in an OTDM network node.

Packet Interleaved OTDM

Figure 5a shows the block diagram of a system used to demonstrate packet interleaving. Note that the time interval between successive pulses now needs to be much less than the bit interval *T*. This is achieved by passing the low bit rate output packet of the modulator into a compressor, which is based on a feed forward delay line structure. The feed forward delay lines are based on a cascade of passive M–Z interferometers with unequal arm lengths. This configuration generates the delay times required, i.e., $T-\tau, 2(T-\tau)\ldots(2^{n-1})(T-\tau)$, etc., where $n = \log_2 k$ is the number of stages, T and τ are the


Fiber delay
Data
Splitter
τ
Node 1
MoD1
Mode locked laser
$i\tau$
MoD*i*
Combiner or star coupler
OTDM
$(N-1)\tau$
Node $N-1$
MoD($N-1$)
(a)
Modulator
Frame pulse
Framing pulses
Channels
T_b
Time
Frame 1
Frame 2
(b)

Figure 3 Bit interleaved OTDM; (a) block diagram and (b) timing waveforms.

incoming bit duration and the outgoing bit duration, respectively, and k is the packet length in bits. Pulse i's location at the output is given by $(2^n - 1)(T - t) + (i - 1)\tau$. The signal at the input of the compressor is:

$$I_{\text{in}}(t) = \sum_{i=0}^{k-1} \delta(t - iT)A_i \qquad [1]$$

Where $\delta(\cdot)$ is the optical carrier pulse shape, and A_i is the ith data bit in the packet.


OTDM in
Splitter
A
Fiber
Threshold level detector
B
Fibre delay $i\tau$
C
&
Recovered channel i
(a)
A
B
Threshold level
$i\tau$
C
Recovered channel i
(b)

Figure 4 Bit interleaving demultiplexer: (a) block diagram and (b) typical waveforms.

As shown in Figure 5b, each bit is split, delayed, and combined to produce the four bit packets O_i:

$$O_i(t) = \frac{1}{2^{n+1}} \sum_{i=0}^{k-1} I_i[t - i(T - \tau)] \qquad [2]$$

Note the factor of $1/(2^{n-1})$ is due to the signal splitting at the 2×2 3-dB coupler at the input of each stage.

The combined signal is shown in Figure 5b, and is defined as:

$$I_{\text{out}} = \sum_{i=0}^{k-1} O_i = \frac{1}{2^{n+1}} \sum_{i=0}^{k-1} \sum_{j=0}^{k-1} I_i[t - (i + j)T + j\tau]A_i \qquad [3]$$


Mode-locked laser
a
Splitter
Data signal
b
c
Modulator
Modulator
Packet compressor
Packet compressor
Packet gating pulse
OTDM
Gating
Compressed OTDM packet
Input $I_{\text{in}}(t)$
$(T-\tau)$
d
$2(T-\tau)$
e
$4(T-\tau)$
Output I_{out}
f
1st stage
2nd stage
ith stage
Fiber delay lines
(a)
Fiber
a)
T
b)
1
1
1
1
0
1
c)
d)
$T-\tau$
e)
ith
f)
Gating pulse
Compressed OTDM packet
(b)

Figure 5 Packet interleaving multiplexer: (a) block diagram and (b) typical waveforms.



Figure 6 Packet interleaving demultiplexer: (a) block diagram and (b) typical waveforms.

For a packet delay of $(i+j)T$ packets are being built up. For the case $(i+j)=3$, four bits are compressed into a packet (see Figure 5b). An optical gating device is used to select the only complete usable compressed copy of the incoming packets from the unwanted copies.

At the receiving end, demultiplexing is carried out by decompressing the OTDM packet stream using the same delay line structure (see Figure 6). Multiple copies of the compressed packet are generated, and each is delayed by $(T-\tau)$. An optical demultiplexer placed at the output of the delay lines generates a sequence of switching window at the rate of $1/T$. By positioning the switching pulses at the appropriate position, a series of adjacent packet (channel) bits from each of the copied compressed packets is extracted (see Figure 6b). The output of the demultiplexer is the decompressed packet signal, which can now be processed at a much slower rate using electronic circuitry.

Components of an OTDM System

Optical Sources

In an ultrahigh speed OTDM system, it is essential that the optical sources are capable of generating transform-limited subnanosecond pulses having low duty cycles, tuneability, and a controllable repetition rate for synchronization. A number of suitable light sources are: gain-switch distribute feedback laser (DFB), active mode locked lasers (MLL) (capable of generating repetitive optical pulses), and harmonic mode-locking Erbium-doped fiber (EDF) lasers. Alternative techniques include super-continuum pulse generation in a dispersion shifted fiber with EDF pumping, adiabatic soliton compression using dispersion-flattened dispersion decreasing fiber, and pedestal reduction of compressed pulses using a dispersion-imbalanced nonlinear optical loop mirror. As shown in Figure 1, the laser light source is power split to form the pulse source for each channel. These are subsequently modulated with an electrical data signal (external modulation). External modulation is preferred in an OTDM system as it can achieve narrow carrier linewidth, thus reducing the timing jitter of the transmitted pulse. For ultrahigh bit rate OTDM systems, the optical pulses emerging from the external modulators may also need compressing. One option is to frequency-chirp the pulses and pass them through an anomalous dispersive medium. Using this approach, it is essential that the frequency chirp be linear throughout the duration of the pulse, in addition the midpoint of the linear-frequency chirp should coincide with the center of the pulse. When a frequency-chirped pulse passes through a dispersive medium, different parts of the pulse travel at different speeds, due to a temporal variation of frequency. If the trailing edge travels faster than the leading edge, the result would be pulse compression. An optical fiber cable or a semiconductor laser amplifier (SLA) can be used to create the frequency chirp.

Multiplexers

Multiplexing of the pulses generated by the optical sources can be implemented either passively or actively. The former method is commonly implemented using a mono-mode optical fiber. This method has the advantage of being simple and cost-effective. The latter method uses devices more complex in nature, for example, electro-optic sampling switches, semiconductor optical amplifiers, and integrated optics.

An integrated active multiplexer can be made by integrating semiconductor laser amplifiers (SOA) into a hybrid planar light-wave circuit (PLC). If the optical path length is kept short then temperature control is made easier. An alternative to this approach is to use lithium niobate (LiNb) technology. Periodically poled LiNb (PPLN) based OTDM multiplexers offer compact size and low noise (due to the absence of amplifier spontaneous emission noise and pattern effect, which is a feature of SOA based devices). Figure 7 is a schematic of a PLC-based OTDM multiplexer composed of two PLCs (R and L), composed of 1 × 8 and 8 × 1 couplers, eight 2 × 1 couplers, and eight different path length PPLN waveguides. The input clock pulse is split into eight by the 1 × 8 coupler in PLC-L, and are combined with the modulated optical pulse trains using the 2 × 1 couplers. The outputs of the 2 × 1 couplers are then passed through a PPLN waveguide to generate a return-to-zero (RZ) optically modulated signal. These are then combined, using the 8 × 1 coupler in PLC-R. When the path-length difference between the waveguides is set to one time slot (equal to 1/8 of the base data rate), then the output of the 8 × 1 coupler is the required high-bit rate OTDM pulse.

Demultiplexers

In contrast to multiplexing, demultiplexing must be performed as an active function. It can be implemented electro-optically or optically. The former method needs to complete demultiplexing of all channels in order to extract a single channel (see Figure 8). The demultiplexer in Figure 8 uses two LiNb Mach–Zehender (M–Z) modulators in tandem. The first and second modulators are driven with a sinusoidal signal of amplitudes $2V_\pi$ and V_π, respectively, to down-covert the N-bit rate to $N/2$ and $N/4$, respectively. Channels can be selected by changing either the DC-bias V + to the M–Zs, or the electrical phase delay. At ultrahigh speed implementation of an electro-optics demultiplexer becomes increasingly difficult due to the higher drive voltage requirement by the M–Z. An alternative is to use all optical demultiplexing based on the nonlinear effect in a fiber and optical active devices offering switching resolution in the order of picoseconds. There are a number of methods available to implement all optical demultiplexing. The most popular methods that use fast phase modulation of an optical signal are based on M–Z and Sagnac interferometers. Four-wave mixing is another popular method.

Mach–Zehnder (M–Z) Interferometers

The key to interferometric switching is the selection of an appropriate material for the phase modulation. Semiconductor materials, often in the form of an SLA, are suitable devices for this purpose.



Figure 7 Configuration of a PLC-OTDM-MUX. Reproduced with permission from Ohara T, Takara H and Shake I, *et al.* (2003). 160-Gb/s optica-time-division multiplexing with PPLN hybrid integrated planar lightwave circuit. *IEEE Photonics Letters* 15(2): 302–304. © 2003 IEEE.



Figure 8 Electro-optics demultiplexer and receiver system block diagram.



Figure 9 SLA carrier density response to input pulse.

The refractive index of an SLA is a function of the semiconductor carrier density, which can be modulated optically resulting in fast modulation. If a high-intensity pulse is input to an SLA the carrier density changes nonlinearly, as shown in Figure 9. Phase modulation is affected via the material chirp index (dN/dn), which represents the gradient of the refractive index carrier density curve for the material. The phase modulation is quite strong and, in contrast to the intensity-based nonlinearity in an optical fiber, (see Kerr effect below), is a consequence of a resonant interaction between the optical signal and the material. The nonlinearity is relatively long-lived and would be expected to limit the switching speed when using semiconductors. Semiconductors, when in excitation from an optical field, tend to experience the effect quite quickly (ps) with a slow release (hundreds of picoseconds) time. Advantage can be taken of this property by allowing the slow recovery to occur during the time between channels of an OTDM signal, as this time may be of the order of hundreds of pico-seconds or more. A Mach–Zehnder configuration using two SLAs, one in each arm of the interferometer placed asymmetrically, is shown in Figure 10. An optical control pulse entering the device via port 3 initiates the nonlinearity. The transmission equation relating the input signal (port 1) to the output port is given by

$$\frac{I_{\text{out}}(t)}{I_{\text{in}}(t)} = 0.25\Big(G_{\text{SLA1}}(t) + G_{\text{SLA2}}(t) \pm 2\sqrt{G_{\text{SLA1}}(t)G_{\text{SLA2}}(t)}\cos\Delta\phi(t)\Big) \qquad [4]$$

where $G_{\text{SLA1}}(t)$ and $G_{\text{SLA2}}(t)$ refer to the gain profiles of the respective SLAs, and $\Delta\phi(t)$ is the time-dependent phase difference between them. Assuming that the gain and phase profiles of an excited amplifier are given by $G(t)$ and $\phi(t)$, respectively, then the signals passing through the upper and lower arms experience optical properties of the material given by:

$$G(t),\ G(t - T_{\text{d}}),\ \phi(t) \text{ and } \phi(t - T_{\text{d}}) \qquad [5]$$

where T_{d} is given by $2L_{\text{d}}N_{\text{SLA}}/c$, L_{d} is the distance between SLA1 and SLA2, N_{SLA} is the SLA index, and c is the speed of light in a vacuum. As the width of the $\Delta\phi(t)$ profile is dependent on the distance between the SLAs, placing them in close proximity allows high-resolution switching. Less emphasis has been placed on the SLA gain as this is considered to be less effective when phase differences of π are reached. It only remains for the gain and phase



Figure 10 Asymmetric TWSLA Mach–Zehnder devices.

modulation to recover, and as indicated previously, this is allowable over a time-scale commensurate with tributary rates.

Sagnac Interferometers

There are two main types; the nonlinear optical loop mirror (NOLM), and the terahertz optical asymmetric demultiplexer (TOAD).

NOLM

In this method of switching the inherent nonlinearity of an optical fiber known as the Kerr effect is used. The phase velocity of any light beam passing through the fiber will be affected by its own intensity and the intensity of any other beams present. When the intrinsic third-order nonlinearity of silica fibers is considered via the intensity-dependent nonlinear refraction component, then the signal phase shift is

$$\Delta\phi_{\text{signal}} = \frac{2\pi}{\lambda_{\text{ds}}} n_2 L I_{\text{ds}} + 2\frac{2\pi}{\lambda_{\text{ds}}} n_2 L I_{\text{c}} \qquad [6]$$

where n_2 is the Kerr coefficient, I_{ds} is the intensity of the data signal to be switched, I_{c} is the intensity of the control signal used to switch the data signal, λ_{ds} is the data signal wavelength, and L is the fiber length. The optical loop mirror consists of a long length of mono-mode fiber formed into a fiber coupler at its free ends (see Figure 11). The input to the loop comprises the high-frequency data stream plus a control pulse at the frame rate. The data split at the coupler and propagate around the loop in contra directions (clockwise E_{CW} and counter-clockwise E_{CCW}) recombining back at the coupler. In the absence of a control pulse, the pulse exits via port 1. If a particular pulse in the loop (in this example E_{CW}) is straddled by the control pulse (see Figure 12), then that pulse experiences cross-phase modulation, according to the second term on the right-hand side of eqn [6], and undergoes a phase change relative to E_{CW}. The difference in the phase between E_{CW} and E_{CCW} causes the pulse to exit via port 2. The phase shift profile experienced by the co-propagating pulse is



Figure 11 Nonlinear optical loop mirror.



Figure 12 Control and data pulses propagation in the fiber.

$$\Delta\phi(t) = \frac{4\pi}{\lambda_{\text{ds}}} n_2 \int_0^L I_{\text{c}}(t)\,\mathrm{d}x \qquad [7]$$

Assuming unity gain around the loop, the transmittance of the NOLM is

$$T_x = 1 - \cos^2\left(\frac{\Delta\phi}{2}\right) = \Delta\phi(t)$$
$$= 1 - \cos^2\left(\frac{2\pi}{\lambda_{\mathrm{ds}}} n_2 \int_0^L I_C(t)\,\mathrm{d}x\right) \qquad [8]$$

As it stands, the switching resolution is determined by the width of the control pulse; however, it is possible to allow the signal and control to 'walk off' each other, allowing the window width to be increased by an amount determined by the 'walk off'. The phase shift is now

$$\Delta\phi(t) = 2\frac{2\pi}{\lambda_{\mathrm{ds}}} n_2 \int_0^L I_C(t - T_w x)\mathrm{d}x \qquad [9]$$

where the parameter T_w, is the walk off time per unit length between control and signal pulses. The increased window width is accompanied by a lower peak transmission (see Figure 13).



Figure 13 Transmittance profiles with the walk-off time as a parameter.

TOAD

The TOAD uses a loop mirror architecture that incorporates an SLA and only needs a short length of fiber loop (see Figure 14a). The SLA carrier density is modulated by a high-intensity control pulse, as in the M–Z-based demultiplexer. The operation of the TOAD is similar to the NOLM, where the loop transmittance is determined by the phase difference between CW and CCW traveling pulses. Strictly speaking, the gain of the SLA must also be taken into account; however, without any loss of generality the effect is adequately described by considering only the phase property. Figure 14a shows the timing diagram associated with a TOAD demultiplexer. The control pulse, shown in Figure 14b(1), is incident at the SLA at a time t_1; the phase profiles for the CCW and CCW data pulses are shown in Figures 14b(2) and (3), respectively. The resulting transmission window is shown in Figure 14b(4). The window width is given by $t_{\mathrm{asy}} = 2\Delta x / c_{\mathrm{f}}$, where Δx is the SLA offset from the loop center and c_{f} is the speed of light in the fiber. As in NOLM, if the phase difference is of sufficient magnitude, then data can be switched to port 2. The switch definition is, in principle, determined by how close the SLA is placed to the loop center when the asymmetry is relatively large. However, for small asymmetries the switching window is asymmetric, which is due to the CW and CCW gain profiles being different (see Figure 15). Assuming the phase modulation dominates the transmission then the normalized transmission for a small asymmetry loop is as depicted in Figure 16. The gain response (not shown) would have a similar shape and temporal position as the phase response.



Figure 14 TOAD: (a) architecture and (b) timing diagrams.

Four-Wave Mixing (FWM)

FWM demultiplexing uses a concept whereby two optical signals of different wavelengths are mixed together in a nonlinear medium to produce harmonic components. The nonlinearity in this case arises from the third-order nonlinear susceptibility $\chi^{(3)}$ of an optical fiber, such that the polarization P induced on a pair of electric fields propagating through the fiber is

$$P = \varepsilon_0 \chi^{(3)} (E_{\mathrm{ds}} + E_{\mathrm{c}})^3 \quad [10]$$



Figure 15 Phase responses for CW and CCW components of TOAD.



Figure 16 TOAD transmission window profile for small asymmetry loop.

where ε_0 is the vacuum permittivity of the medium, E_{ds} and E_{c} are the electric fields of data and control signals, respectively. The mixing of the two signals takes place in a long length of fiber in which the control signal propagates alongside the channel to be demultiplexed (see Figure 17). The control signal is of sufficient intensity to cause the fiber to operate in the nonlinear regime. The nonlinear relationship causes a number of frequencies to be generated, with the ones of interest having a frequency given by

$$f_{\mathrm{FWM}} = 2f_{\mathrm{c}} - f_{\mathrm{ds}} \quad [11]$$

An optical filter is then used to demultiplex the required channel from the composite signal. The nonlinearity is detuned from the resonant frequency of the fiber glass and as such tends to be weak, requiring long lengths of fiber to give a measurable effect. The power in the demultiplexed signal, for given data and control signal wavelengths and fiber material, depends on the input power and the fiber length according to

$$P_{\mathrm{FWM}} = kP_{\mathrm{ds}}P_{\mathrm{c}}L_{\mathrm{E}}^2 \quad [12]$$

where k is a constant, P_{ds} is the signal launch power, P_{c} is the control signal launch power, and L_{E} is the fiber effective length. FWM is essentially an inefficient method as power is wasted in the unused frequency components of the four-wave signal. More in line with integrated structures, the nonlinear properties of a semiconductor laser amplifier can be used. Here a relatively high-power optical signal is input to the SLA (see Figure 18). This enables saturation and operation in the nonlinear regime


Control pulse (λ_c)
Long length of fiber
Optical filter
Selected channel
Data pulse train (λ_s)
Mixed signal (λ_{FWM})

Figure 17 Block diagram of FWM demultiplexer.


DC bias current
Light input: data and control E_D, E_C
Nonlinear SLA
Light output: Four-wave components E_{FWM}

Figure 18 Four-wave mixing in SOA.



Figure 19 SLA output–input power curve.

(see Figure 19). Operating the SLA in saturation allows the nonlinear effects to produce the FWM components as in the fiber method.

Clock and Data Synchronization in OTDM

In common with electronically based TDM systems, clock recovery is fundamental to the recovery of data in ultrahigh-speed OTDM systems. Two main methods are proposed: (i) clock signal transmitted with the OTDM signal (i.e., multiplexed); and (ii) extraction of clock signal from the incoming OTDM pulse stream. In a packet-based system, synchronization between the clock and the data packet is normally achieved by sending a synch pulse with each packet. However, techniques based on optical-phased locked loops are proving popular and remove the need for a separate clocking signal.

Clock Multiplexing

(i) *Space division multiplexing*: This is conceptually the simplest to implement, where the clock signal is carried on a separate fiber from the data. However, it is susceptible to any differential delay between the different paths taken by clock and data due to temperature variation. It is difficult to justify in systems where the installed fiber base is at a premium.

(ii) *Wavelength division multiplexing*: Here different wavelengths are allocated to the clock, and payload. It is only really practical for predetermined path lengths between nodes in single-hop networks such as point–point links or broadcast-and-select star networks. It also suffers from random delays between the clock and the payload, which is problematic in an asynchronous packet switched based network, where the optical path length a packet may take is nondeterministic.

(iii) *Orthogonal polarization*: This is suitable for small links, where separate polarizations are used for the clock and data. However, in large networks it is quite difficult to maintain the polarization throughout the transmission link due to polarization mode dispersion and other nonlinear effects.

(iv) *Intensity division multiplexing*: This uses higher-intensity optical clock pulses to differentiate it from the data pulses as discussed above. However, in long-distance transmission links, it is difficult to maintain both the clock intensity and its position, due to the fiber nonlinearity.

(v) *Time division multiplexing*: In this scheme a single clock pulse, which has the same wavelength, polarization, and amplitude as the payload pulses, is separated in time, usually ahead of the data pulses.

Synchronization – Optical Phased Locked Loops (PLL)

The PLL is a common technique used for clock recovery in electronic TDM systems. However, the speed of conventional electronic PLLs tends to be limited by the response of the phase comparators used. There are a number of approaches based on opto-electronic PLL. Opto-electronic PLLs based on four-wave mixing in a traveling wave laser amplifier are complex and can suffer from frequency modulation in the recovered clock. However, others based on balanced photo-detectors, result in low timing jitter and good phase stability. In contrast, a number of all optical methods clock recovery scheme exist, one technique based on the TOAD (see above) is depicted in Figure 20. The high-speed data stream enters the TOAD at a rate $n \times R$ where n is the number of channels per OTDM frame, and R is the frame rate. A pulse generator, such as a mode locked fiber laser (MLFL) clocked by a local oscillator (LO), is used as the TOAD control input (MLFL-C). The OTDM data is switched by the TOAD at a frequency of say, $R + \Delta f$ Hz. Thus, the switching window samples data pulses at a rate higher or lower than $n \times R$ Hz and uses this signal for cross correlation in the PLL unit. The output of the phase comparator is used to regulate a voltage controlled oscillator (VCO)


SLA
Fiber loop
Coupler
Control pulse
MLFL-C
3dB coupler
OTDM data in
LO ~
Phase comparator
×
VCO
R Hz
$S_c(t)$
PLL

Figure 20 Ultrafast clock recovery using TOAD.

running at R Hz, which in turn feeds the control signal. The PLL circuit locks into the clock frequency, generating the clock signal $S_c(t)$.

OTDM Bit-Error Rate (BER) Performance

Figure 21 shows a typical block diagram of a high-speed optical receiver for an OTDM system, composed of a NOLM or a TOAD demultiplexer, an optical pre-amplifier, an optical bandpass filter, and a conventional optical receiver using a PIN photodiode. Due to the crosstalk introduced in the demultiplexing process, the demultiplexed optical signal contains not only the target channel but may also contain nontarget channels with reduced amplitude (see the inset in Figure 21). The intensity of the demultiplexed optical signal is boosted by the optical pre-amplifier (EDFA). Amplified spontaneous emission (ASE) from the optical preamplifier adds a wide spectrum of optical fields onto the demultiplexed optical signal. Although an optical bandpass filter (BPF) can reduce the ASE, it still remains one of the major noise sources. The function of the optical filter is to reduce the excess ASE to within the range of the signal spectrum. The PIN photodiode converts the received optical power into an equivalent electrical current, which is then converted to a voltage signal by an electrical amplifier. Finally, the output voltage is sampled periodically by a decision circuit for estimating the correct state (mark/space) of each bit.


Target channel
Non-target channels
Channels 1 2 3 4 5 1
OTDM pulse train
Control pulse train
All-optical Demux
EDFA
BPF
Error detection
Optical receiver
Optical fiber

Figure 21 Block diagram of OTDM receiver.



Figure 22 BER versus the average received optical power for 100 Gb/s (10 channels) OTDM system.

The BER performance of an OTDM system deteriorates because of the noise and crosstalk introduced by the demultiplexer and is:

$$\mathrm{BER} = \frac{1}{\sqrt{2\pi}} \frac{\exp\left(-Q^2/2\right)}{Q} \qquad [13]$$

where Q is defined as:

$$Q = \frac{\bar{I}_\mathrm{m} - \bar{I}_\mathrm{s}}{\sqrt{\sigma^2_{\mathrm{RIN,m}} + \sigma^2_{\mathrm{RIN,s}} + \sigma^2_{\mathrm{amp,m}} + \sigma^2_{\mathrm{amp,s}} + \sigma^2_{\mathrm{rec,m}} + \sigma^2_{\mathrm{rec,s}}}} \qquad [14]$$

and $\bar{I}_\mathrm{m}$ and $\bar{I}_\mathrm{s}$ are the average photocurrents for a mark and a space, respectively. $\sigma_{x,i}$ are the variances of the relative intensity noise (RIN), further optical pre-amplifier and receiver for a mark and a space.

For 100 Gb/s (10 channels) OTDM system, the BER against average received optical power for optimized NOLM and TOAD demultiplexers, is shown in Figure 22.

List of Units and Nomenclature

A_i	ith data bit in a packet
c	Speed of light in a vacuum
c_f	Speed of light within the fiber
E_c	Electric fields of control signals
E_ds	Electric fields of data signals
f_FWM	Frequency due to four-wave mixing
$G_\mathrm{SLA}(t)$	Gain profiles of SLA
I_c	Intensity of the control signal
I_D	Intensity of the data signal
$\bar{I}_\mathrm{m}$	Average photo current for a mark
$\bar{I}_\mathrm{s}$	Average photo current for a space
k	Packet length in bits
L	Fiber length
L_d	Distance between two SLAs
L_E	Fiber effective length
n	Number of stages
n_2	Kerr coefficient
N_SLA	SLA index
P	Polarization
P_c	Control signal launch power
P_ds	Data signal launch power
t_asy	The window width is given by $t_\mathrm{asy} = 2\Delta x/c_f$
T	Incoming bit interval
T_w	Walk off time per unit length between control and data pulses
T_x	Transmittance of the NOLM
$\delta(\cdot)$	Optical carrier pulse shape
$\Delta\phi(t)$	Time-dependent phase difference
Δx	SLA offset from the fiber loop center
ε_0	Vacuum permittivity of the medium
λ_s	Data signal wavelength
$\sigma_\mathrm{amp,m}$	Variances for optical pre-amplifier for a mark
$\sigma_\mathrm{amp,s}$	Variances for optical pre-amplifier for a space
$\sigma_\mathrm{rec,m}$	Variances for receiver for a mark
$\sigma_\mathrm{rec,s}$	Variances for receiver for a space
$\sigma_\mathrm{RIN,m}$	Variances of RIN for a mark
$\sigma_\mathrm{RIN,s}$	Variances of RIN for a space
τ	Outgoing bit interval
$\phi(t)$	Phase profile of SLA
$\chi^{(3)}$	Third-order non-linear susceptibility of an optical fiber

See also

Interferometry: Overview. **Nonlinear Optics, Basics**: Four-Wave Mixing. **Optical Communication Systems**: Optical Time Division Multiplexing; Wavelength Division Multiplexing.

Further Reading

Agrawal GP (2002) *Fiber-Optic Communication Systems*, 3rd edn. New York: J Wiley and Sons Inc.

Chang K (ed.) (2003) *Handbook of Optical Components and Engineering*, 2nd edn. New York: Wiley and Sons Inc.

De Marchis G and Sabella R (1999) *Optical Networks Design and Modelling*. Dordrecht: Kluwer Academic.

Hamilton SA, Robinson BS, Murphy TE, Savage SJ and Ippen EP (2002) 100 Gbit/s optical time-division multiplexed networks. *Journal of Lightwave Technology* 20(12): 2086–2100.

Jhon YM, Ki HJ and Kim SH (2003) Clock recovery from 40 gbps optical signal with optical phase-locked loop based on a terahertz optical asymmetric demultiplexer. *Optics Communications* 220: 315–319.

Kamatani O and Kawanishi S (1996) Ultrahigh-speed clock recovery with phase locked loop based on four wave mixing in a traveling-wave laser diode maplifier. *Journal of Lightwave Technology* 14: 1757–1767.

Nakamura S, Ueno Y and Tajima K (2001) Femtosecond switching with semiconductor-optical-amplifier-based symmetric-Mach–Zehnder-type all-optical switch. *Applied Physics Letters* 78(25): 3929–3931.

Ohara T, Takara H, Shake I, *et al.* (2003) 160-Gb/s optica-time-division multiplexing with PPLN hybrid integrated planar lightwave circuit. *IEEE Photonics Letters* 15(2): 302–304.

Ramaswami R and Sivarajan KN (2002) *Optical Network; a Practical Perspective*. Morgan Kaufman.

Reman E (2001) Trends and evolution of optical networks and technology. *Alcatel Telecommun. Rev. 3rd Quarter* 173–176.

Sabella R and Lugli P (1999) *High Speed Optical Communications*. Dordrecht: Kluwer Academic.

Seo SW, Bergman K and Prucnal PR (1996) Transparent optical networks with time division multiplexing. *Journal of Lightwave Technology* 14(5): 1039–1051.

Sokolloff JO, Prucnal PR, Glesk I and Kane M (1993) A terahertz optical asymmetric demultiplexer (TOAD). *IEEE Photonics Technology Letters* 5(7): 787–790.

Stavdas A (ed.) (2001) *New Trends in Optical Network Design and Modelling*. Dordrecht: Kluwer Academic.

Ueno Y, Takahashi M, Nakamura S, Suzuki K, Shimizu T, Furukawa A, Tamanuki T, Mori K, Ae S, Sasaki T and Tajima K (2003) Control scheme for optimizing the interferometer phase bias in the symmetric-Mach–Zehnder all-optical switch (invited paper). Joint special issue on recent progress in optoelectronics and communications. *IEICE Trans. Electron.* E86-C(5): 731–740.

Coherent Analog Optical Processors

H H Arsenault, S Roy and D Lefebvre, University of Laval, Quebec, PQ, Canada

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Linear filtering is a useful tool commonly used in image processing. The correlation operation can be defined as:

$$f(x,y)*h(x,y)=\int_{-\infty}^{\infty}\int_{-\infty}^{\infty}f(x,y)h(x-x',y-y')\mathrm{d}x'\mathrm{d}y' \qquad [1]$$

where $*$ denotes the correlation. The operation of correlation and the Fourier transform

$$G(\mu,\nu)=\int_{-\infty}^{\infty}\int_{-\infty}^{\infty}g(x,y)\mathrm{e}^{-j2\pi(\mu x+\nu y)}\mathrm{d}x\mathrm{d}y \qquad [2]$$

are intimately related through the correlation theorem of Fourier theory, which states that the correlation between two functions $f(x,y)$ and $h(x,y)$ is equal to the inverse Fourier transform of the product of the Fourier transforms:

$$f(x,y)*h(x,y)=FT^{-1}[F(\mu,\nu)H^{*}(\mu,\nu)] \qquad [3]$$

where $F(\mu,\nu)$ and $H(\mu,\nu)$ are the Fourier transforms of $f(x,y)$ and of $h(x,y)$ respectively, and where H^{*} designates the complex conjugate of H. The ability to carry out and display Fourier transforms in two dimensions, by means of optical systems, is at the root of optical information processing.

One of the main advantages of correlation is that the operations do not require segmentation of the regions of interest. This means that the locations of objects do not have to be segmented from the scene and that the detection is shift-invariant, that is the correlation peaks appear at locations in the scene corresponding to locations of the targets. These advantages are clearer for detection in uncontrolled conditions, for example for detecting vehicles in natural scenes. But they are also useful in security applications, such as identity verification or for detecting defects in assembly lines.

The Optical Fourier Transform

The Fourier transform of eqn [2] is widely used in the field of information processing. The inverse Fourier transform is simply defined as:

$$g(x,y)=\int_{-\infty}^{\infty}\int_{-\infty}^{\infty}G(\mu,\nu)\mathrm{e}^{i2\pi(\mu x+\nu y)}\mathrm{d}\mu\mathrm{d}\nu \qquad [4]$$

We will now discuss how to perform Fourier transforms by means of four different optical setups.

FT Without a Lens

If we illuminate a transparency $U(x_0,y_0)$ with a coherent plane wave, the diffraction pattern we observe at a point d from the input plane is given by the following relation, known as the Fresnel approximation for diffraction (Figure 1):

$$U(x_1,y_1)=\frac{\exp\left(i\dfrac{2\pi d}{\lambda}\right)}{j\lambda d}\int_{-\infty}^{\infty}\int_{-\infty}^{\infty}U(x_0,y_0)\times\exp\left\{i\frac{\pi}{\lambda d}[(x_0-x_1)^2+(y_0-y_1)^2]\right\}\mathrm{d}x_0\mathrm{d}y_0 \qquad [5]$$

where λ is the wavelength of the light and d is the distance between the diffracting screen and the observed pattern.

In order to use the Fresnel approximation we need only to satisfy the geometrical optics paraxial conditions. If we add an additional approximation, we can further simplify this equation to yield the Fourier transform of $U(x_0,y_0)$. The extra condition is known as the Fraunhofer or far-field approximation, which is only satisfied when the diffracted image is observed far away from the diffracting screen or when the extent of $U(x_0,y_0)$ is very small. Mathematically this condition is expressed by:

$$\frac{\pi}{\lambda d}(x_0^2+y_0^2)\ll 1 \qquad [6]$$



Figure 1 Fresnel diffraction without a lens.

After expanding the squares in the exponentials, there will be three terms: one can go outside the integral and one will be approximately equal to unity so the diffracted pattern becomes

$$U(x_1, y_1) = \frac{\exp\left(i\frac{2\pi d}{\lambda}\right)}{i\lambda d} \times \exp\left[i\frac{\pi}{\lambda d}(x_1^2 + y_1^2)\right]\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} U(x_0, y_0) \times \exp\left[-i\frac{2\pi}{\lambda d}(x_0x_1 + y_0y_1)\right]\mathrm{d}x_0\mathrm{d}y_0 \quad [7]$$

This is the Fourier transform of $U(x_0, y_0)$, scaled by a factor λd, with an extra quadratic phase factor

$$\exp\left[\frac{i\pi}{\lambda d}(x_1^2 + y_1^2)\right]$$

The factor $\exp(i2\pi d/\lambda)/i$ is usually of no importance since it is a phase factor distributed across the output plane. In some applications we only want to know the power spectrum (squared modulus) of the Fourier transform. In such cases the quadratic phase factor disappears because the squared modulus of any complex exponential is equal to 1. Performing a Fourier transform without a lens is possible within the Fraunhofer approximation. But if it is required to obtain the Fourier transform of an image which extends about 1 cm from the optical axis using a coherent He–Ne laser ($\lambda = 632.8$ nm), the condition to be satisfied is $d \gg 496$ m: the required observation distance d is at least a few kilometers. This kind of optical setup is usually impractical, but can fortunately be alleviated by means of lenses.

Object on the Lens

Instead of having only the transparency in the input plane, we place a lens immediately after it as shown in Figure 2. For mathematical simplicity the lens and input plane are superimposed (more realistic cases are considered below). The lens acts as a phase factor

$$\exp\left[-i\frac{\pi}{\lambda f}(x_0^2 + y_0^2)\right]$$

where f is the focal length of the lens. Now in the input plane the object $U(x_0, y_0)$ is multiplied by the phase factor of the lens:

$$U'(x_0, y_0) = U(x_0, y_0)\exp\left[-i\frac{\pi}{\lambda f}(x_0^2 + y_0^2)\right] \quad [8]$$

Inserting this expression into the integral formula for Fresnel diffraction yields the diffraction pattern observed in the focal plane of the lens:

$$U(x_1, y_1) = \frac{\exp\left(i\frac{2\pi f}{\lambda}\right)}{i\lambda f} \times \exp\left[i\frac{\pi}{\lambda f}(x_1^2 + y_1^2)\right]\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} U(x_0, y_0) \times \exp\left[-i\frac{2\pi}{\lambda f}(x_0x_1 + y_0y_1)\right]\mathrm{d}x_0\mathrm{d}y_0 \quad [9]$$

The lens exactly compensates for the other phase factor that was in the integral. This expression for the Fraunhofer approximation is almost the same as before, but the focal length f of the lens replaces the distance d. So by placing a lens immediately after the input plane we can have a much more compact setup since lenses are available with a wide range of focal lengths, usually from a few centimeters to a few meters. Another way to look at this is to consider that the effect of a lens is to bring the pattern at infinity to the focal plane of the lens – except for the phase factor.

Object Before the Lens

Another setup used to perform the Fourier transform is shown in Figure 3, where the lens is placed somewhere between the input and the output planes. Using the Fresnel formula for diffraction it can be



Figure 2 Diffraction with the object on the lens.



Figure 3 Diffraction with the object before the lens.

shown that the diffraction pattern in the focal plane is:

$$U(x_1, y_1) = \frac{1}{i\lambda f} \times \exp\left[i\frac{\pi}{\lambda f}\left(1 - \frac{d}{f}\right)(x_1^2 + y_1^2)\right]\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} U(x_0, y_0) \times \exp\left[-i\frac{2\pi}{\lambda f}(x_0x_1 + y_0y_1)\right]\mathrm{d}x_0\mathrm{d}y_0 \qquad [10]$$

where d is the distance between the input plane and the lens. If we set d equal to the focal length f of the lens, the quadratic phase factor in front in the integral vanishes and we have an exact Fourier transform. This setup with the object and filter in the front and back focal planes of the lens respectively is the one most frequently seen in scientific articles and is known as the *f-f* Fourier transform system.

Object After the Lens

Still another configuration is the one shown in Figure 4, where the lens is placed at a distance d before the input plane. For this configuration the Fresnel diffraction yields the following pattern in the focal plane of the lens:

$$U(x_1, y_1) = \frac{\exp\left[i\frac{\pi}{\lambda d}(x_1^2 + y_1^2)\right]}{i\lambda d}\frac{f}{d}\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} U(x_0, y_0) \times \exp\left[-i\frac{2\pi}{\lambda d}(x_0x_1 + y_0y_1)\right]\mathrm{d}x_0\mathrm{d}y_0 \qquad [11]$$

Once again the Fourier transform of $U(x_0, y_0)$ is multiplied by a quadratic phase factor. It is interesting to note that, in this case, the Fourier transform is scaled by a factor λd. This can be used to control the scale of the Fourier transform by changing the distance between the lens and the object.



Figure 4 Diffraction with the object after the lens.

Note that although two of the three methods yield Fourier transforms that are accompanied by a quadratic phase factor, the latter is not necessarily an impediment to correlation, contrary to popular belief. Indeed all three configurations have been used for correlation pattern recognition, and each configuration has its advantages.

Optical Correlation

The last section showed how to obtain Fourier transforms by means of an optical setup. The proposed optical setups cannot perform the inverse Fourier transform. Because the Fourier transform and its inverse are very similar, the Fourier transform is performed instead, yielding the mirror image of the correlation:

$$(f * h)(-x, -y) = \mathrm{FT}[F(\mu, \nu)H^*(\mu, \nu)] \qquad [12]$$

The correlation can be considered as the result of three operations: a Fourier transform; a product; and an additional Fourier transform. The Fourier transform of a 2D function can be obtained by means of coherent optics. The equivalent of multiplication in optics is transmissivity, so multiplication is accomplished by sending light successively through two superimposed transparencies.

There are two main categories of optical correlators, serial correlators and joint transform correlators.

Serial Correlators

A serial correlator functions in two stages. The first stage performs the Fourier transform of the input image $f(x, y)$, which is multiplied in the Fourier plane with a transparency $H(\mu, \nu)$. The filter $H(\mu, \nu)$ can be a hologram, a spatial light modulator (SLM) or a simple transparency. A second Fourier transform displays in the output plane the correlation of the input image with the impulse response $h(x, y)$, which is the Fourier transform of the filter function $H(\mu, \nu)$.

Serial correlators directly implement the two Fourier transforms and the multiplication operation in a pipelined manner. The input plane and the correlation plane are conjugate planes of the system, that is in the absence of a filter, the output plane displays an inverted image of the input $f(x, y)$. Between those conjugate planes, at the conjugate plane of the source with respect to the first lens, is the Fourier plane where the spatial frequency filter is placed. When the input is illuminated with parallel light, the frequency plane is at the back focal plane of the first lens. A SLM can be placed in the input plane to feed the images to be correlated; a second SLM can be placed in the Fourier plane to display the filter. The filter is often calculated by a digital computer, and usually takes the form of a hologram if phase information must be used in the filter.

The 4-*f* correlator

The 4-*f* correlator is the most intuitive optical correlator system. We showed above that an *f*-*f* system can be used to optically obtain a Fourier transform (Figure 5). If $f(x, y)$ is in the front focal plane, its Fourier transform $F(\mu, \nu)$ appears at the back focal plane of the first lens. If a filter function $H^*(\mu, \nu)$ is inserted at this point, by means of a SLM or a hologram, then a second *f*-*f* system can perform a second Fourier transform to yield the correlation plane at the back focal plane of the second lens.

Convergent beam correlator

This kind of correlator consists of two conjugate systems. This time, the Fourier transform is obtained by placing the input object in a convergent beam after the first lens. The second lens is placed so that the output plane is conjugate to the input plane, and as before, the filter is placed at the point of convergence of the light after the first lens. It is important to note that this is not the focal plane of the lens, but the conjugate plane of the source of light. In order to have an imaging system between the input and output planes, the distances must satisfy the conjugate relation:

$$\frac{1}{s_0} + \frac{1}{s_i} = \frac{1}{f_2} \qquad [13]$$

where s_i and s_0 are defined in Figure 6. As previously discussed for convergent light, the Fourier transform will have an additional parabolic phase factor. This must be taken into account when constructing the filter H.

This configuration has some advantages over the 4-*f* correlator. By moving the object between the first lens and the filter, it is possible to control the scale of the Fourier transform. And because the first lens is imaging only a single point on the optical axis, only spherical aberration needs to be compensated for. In 4-*f* systems, the first lens must be corrected for all aberrations for the whole input plane, and for a given extent of the input object, the first lens must be larger than that for the convergent system in order to avoid space variance effects. Unfortunately, specially designed expensive lenses are required to correct for those aberrations, so well-corrected Fourier transform lenses for 4-*f* systems are expensive, whereas a simple doublet is sufficient to correct for on-axis spherical aberration, which is all that is required for the convergent light system. In addition, the convergent light system does not require an expensive collimator that is required in the 4-*f* system to obtain the parallel illuminating beam. Aberration correction requirements for the second lens are less stringent



Figure 5 4-*f* correlator setup.



Figure 6 Convergent beam correlator setup.



Figure 7 Single lens correlator setup.

than for the first, because in most cases, a slight deformation of the output plane can be acceptable, whereas comparable distortions in the Fourier plane can cause misregistrations between the Fourier transform and the filter that can seriously degrade the correlation.

Divergent beam correlators

Instead of placing the input object in the convergent beam, as in the previous case, another configuration that has been used places the input object in the divergent beam before the first lens. This configuration is rarely seen today, because it exacerbates the space variance and aberration problems of the 4-*f* system, and the control it allows over the scale of the Fourier transform can be achieved with fewer penalties by means of the convergent light system.

Single lens correlator

Consider an imaging system using only one lens illuminated with a parallel beam of coherent light (Figure 7). The input and output planes are located at distances $2f$ on either side of the lens – the shortest conjugate distances possible. If a filter $H(\mu, \nu)$ is placed at the focal plane of the lens on the object's Fourier transform, the correlation will appear on the output plane. This system requires satisfying impractical conditions: aberration corrections for both the Fourier transform and for the imaging operation, so it is rarely seen.

Filters

Many types of filters can be used for different applications. Table 1 lists some commonly used filters for pattern recognition. The classical matched filter yields the optimum signal to noise ratio in the presence of additive noise. The phase-only filter (POF) is frequently used because of its high discrimination capability. The inverse filter is sometimes used because it theoretically yields very sharp correlation peaks, but is very sensitive to noise, and when the spectrum $F(\mu, \nu)$ has some zeros, the realization of $1/F(\mu, \nu)$ can be impossible. A close relative of the inverse filter is the Wiener filter, which avoids the problem of the inverse filter by introducing a quantity $S(\mu, \nu)$ in the denominator of the filter function. The function $S(\mu, \nu)$ can sometimes be a constant. $H(\mu, \nu)$ is usually chosen to minimize the effect of noise or to optimize some parameter such as the peak to sidelobe ratio, or the discrimination ability of the system.

Table 1 Commonly used filters for image processing

Name	*Filter*
Matched filter	$H_{\mathrm{CMF}}(\mu, \nu) = F(\mu, \nu)$
Phase-only filter	$H_{\mathrm{POF}}(\mu, \nu) = \dfrac{F(\mu, \nu)}{\lvert F(\mu, \nu)\rvert}$
Inverse filter	$H_{\mathrm{INV}}(\mu, \nu) = \dfrac{1}{F(\mu, \nu)}$
Wiener filter	$H_{\mathrm{W}}(\mu, \nu) = \dfrac{F^*(\mu, \nu)}{\lvert F(\mu, \nu)\rvert^2 + S(\mu, \nu)}$

Joint Transform Correlators

In serial transform correlators, the filter is generally a complex function. Spatial light modulators are usually conceived with only one degree of freedom for each pixel, which can be optimized for amplitude modulation or for phase modulation. In order to achieve a fully complex filter, two modulators are required, or some spatial bandwidth of a modulator is sacrificed to encode a computer-generated hologram.

The joint-transform correlator (JTC) does not require a fully complex filter. The filter is stored in the spatial domain so there is usually no need for the computation of a filter in the spectral domain. In the JTC, the correlation of a scene with a reference image is contained in the power spectrum of an input plane consisting of the scene placed side by side with the reference. The correlation terms are revealed when the Fourier transform of the power spectrum is computed. The joint transform correlation can be summarized in three steps:

1. The scene and the reference are located side by side in the input plane.
2. The Fourier transform of the input plane is computed or carried out optically by one of the methods previously described. The transform intensity is measured and constitutes the joint power spectrum. Some optional enhancements, based on spatial filtering and/or nonlinear processing on the power spectrum, can also be performed.
3. The Fourier transform of this joint power spectrum is carried out, yielding the correlation plane containing the correlation of the reference with the scene.

A mathematical analysis is required to understand the location of the correlation peaks. The side-by-side input scene $s(x, y)$ and reference image $r(x, y)$ are

$$i(x, y) = r(x - x_{\mathrm{r}}, y - y_{\mathrm{r}}) + s(x - x_{\mathrm{s}}, y - y_{\mathrm{s}}) \qquad [14]$$

The joint power spectrum $E(\mu, \nu)$ is equal to the modulus squared of the Fourier transform of the input plane:

$$\begin{aligned} I(\mu, \nu) &= R(\mu, \nu)\mathrm{e}^{-i2\pi(\mu x_{\mathrm{r}} + \nu y_{\mathrm{r}})} + S(\mu, \nu)\mathrm{e}^{-i2\pi(\mu x_{\mathrm{s}} + \nu y_{\mathrm{s}})} \\ E(\mu, \nu) &= \|I(\mu, \nu)\|^2 = \\ &\|R(\mu, \nu)\|^2 + \|S(\mu, \nu)\|^2 \\ &+ R(\mu, \nu)S^*(\mu, \nu)\mathrm{e}^{-i2\pi[\mu(x_{\mathrm{r}} - x_{\mathrm{s}}) + \nu(y_{\mathrm{r}} - y_{\mathrm{s}})]} \\ &+ R^*(\mu, \nu)S(\mu, \nu)\mathrm{e}^{-i2\pi[\mu(x_{\mathrm{s}} - x_{\mathrm{r}}) + \nu(y_{\mathrm{s}} - y_{\mathrm{r}})]} \end{aligned} \qquad [15]$$

The joint power spectrum contains the Fourier transforms of the autocorrelation of the input scene, the autocorrelation of the reference, the correlation of the scene with the reference and its complex conjugate. The correlation peaks are obtained from the Fourier transform of the joint power spectrum:

$$\begin{aligned} C(x', y') = \; & R_{\mathrm{ss}}(x', y') + R_{\mathrm{rr}}(x', y') \\ & + R_{\mathrm{sr}}\big(x' - (x_{\mathrm{r}} - x_{\mathrm{s}}),\ y' - (y_{\mathrm{r}} - y_{\mathrm{s}})\big) \\ & + R_{\mathrm{sr}}\big(x' + (x_{\mathrm{r}} - x_{\mathrm{s}}),\ y' + (y_{\mathrm{r}} - y_{\mathrm{s}})\big) \end{aligned} \qquad [16]$$

where

$$R_{\mathrm{ab}}(x', y') = \int_{-\infty}^{\infty}\int_{-\infty}^{\infty} a(\xi, \zeta)b^*(\xi - x', \zeta - y')\mathrm{d}\xi\mathrm{d}\zeta \qquad [17]$$

Multiple targets and multiple references

The input scene of the JTC may contain multiple targets. Each target in the scene will correlate with the other targets. The additional correlation peaks can clutter the correlation plane, so some care must be taken when positioning the scene with respect to the reference. Let $s(x, y)$ contain multiple targets $s_i(x, y)$:

$$s(x, y) = \sum_{i=1}^{N} s_i(x - x_i, y - y_i) \qquad [18]$$

The joint power spectrum becomes:

$$\begin{aligned} E(\mu, \nu) = \; & \|R(\mu, \nu)\|^2 + \sum_{i=1}^{N} \|S_i(\mu, \nu)\|^2 + \sum_{i=1}^{N} \sum_{\substack{k=1 \\ i \neq k}}^{N} \\ & \times S_i(\mu, \nu)S_k^*(\mu, \nu)\mathrm{e}^{-i2\pi[\mu(x_i - x_k) + \nu(y_i - y_k)]} + \mathrm{C.C.} \\ & + \sum_{i=1}^{N} R(\mu, \nu)S_i^*(\mu, \nu)\mathrm{e}^{-i2\pi[\mu(x_{\mathrm{r}} - x_i) + \nu(y_{\mathrm{r}} - y_i)]} + \mathrm{C.C.} \end{aligned} \qquad [19]$$

where C.C. denotes the complex conjugate of the preceding term. The correlation plane will now be:

$$\begin{aligned} C(x', y') = \; & R_{\mathrm{rr}}(x', y') + \sum_{i=1}^{N} R_{\mathrm{s}_i\mathrm{s}_i}(x', y') \\ & + \sum_{i=1}^{N} \sum_{\substack{k=1 \\ i \neq k}}^{N} R_{\mathrm{s}_i\mathrm{s}_k}\big(x' - (x_i - x_k),\ y' - (y_i - y_k)\big) \\ & + \sum_{i=1}^{N} R_{\mathrm{rs}_i}\big(x' - (x_{\mathrm{r}} - x_i),\ y' - (y_{\mathrm{r}i} - y_i)\big) \\ & + \sum_{i=1}^{N} \sum_{\substack{k=1 \\ i \neq k}}^{N} R_{\mathrm{s}_k\mathrm{s}_i}\big(x' + (x_i - x_k),\ y' + (y_i - y_k)\big) \\ & + \sum_{i=1}^{N} R_{\mathrm{s}_i\mathrm{r}}\big(x' + (x_{\mathrm{r}} - x_i),\ y' + (y_{\mathrm{r}i} - y_i)\big) \end{aligned} \qquad [20]$$

The second lines of eqns [9] and [20] are the cross-correlation terms between the targets. In order to avoid confusion between reference–target correlations and target–target correlations, special care must be taken in positioning the reference with respect to the scene. All the target–target correlations will be inside a centered box that has twice the length and twice the width of the input scene, so the reference should be placed at least at twice the length or width of the scene.

Multiple targets in the input scene can be viewed as multiple references, and the correlation of multiple references with multiple targets are all computed simultaneously. This property has led to applications in multiclass pattern recognition problems and in optical neural networks, where each neuron of a layer is coded as a reference object. This is one of the advantages of the JTC compared to serial correlators, since serial correlators are limited to one filter at a time.

Example

Here is an example of joint transform correlation. The input plane is shown in Figure 8a. The plane is composed of the input scene in the top third of the input plane and the reference is placed in the center. This input scene contains two targets. The joint power spectrum is shown in Figure 8b with its pixels mapped to a logarithmic intensity scale. The correlation plane is shown in Figure 8c and d with the central peak truncated. The central peak contains the autocorrelation terms R_{ss} and R_{rr}. On each side of the autocorrelation peak are the cross-correlations between the different targets of the input scene. The correlation between the reference image and the input scene is located in the top part of the correlation plane. The correlation plane is symmetrical with respect to the origin, so the correlation peaks are reproduced on the bottom half of the output plane.

Joint transform correlator architectures

Different architectures have been used for JTCs. Three setups are presented here. This is not an exhaustive list. The simplest optical setup shown in Figure 9 is an optoelectronic implementation of a power spectrum machine. A convergent beam



Figure 8 Joint transform correlation example. (a) Input scene; (b) joint power spectrum; (c) correlation plane (top view); (d) correlation plane (mesh view).



Figure 9 Joint transform correlator implementation as an optical power spectrum machine.



Figure 10 Optical JTC using two SLMs in the input plane.

optical Fourier transform system is used to produce the Fourier transform of an image displayed on a single spatial light modulator (SLM). A CCD camera is placed in the Fourier plane to measure the joint power spectrum. The joint transform correlation is a two-step process: the input plane containing the scene and the reference is first displayed on the SLM, and the camera simultaneously captures the joint power spectrum. In the second step, the joint power spectrum is displayed on the SLM, so the correlation plane is now on the camera. An optional second camera with intensity filters can be added to this setup. In this case, one camera serves to digitize the joint power spectrum during step 1 and the second camera captures the correlation plane at step 2 and transmits it to a display device. This optional configuration is useful to keep both the correlation plane and the joint power spectrum within the dynamic range of their specific cameras.

The setup shown in Figure 9 has two main disadvantages: the correlation is performed in two steps and requires some processing to construct the input plane, and only half of the spatial light modulator can be used to display the input scene. There are alternative setups to alleviate those drawbacks, but they require the use of two or three SLMs. Two modulators can be used in the input plane to simulate a full modulator for the scene, as shown in Figure 10. The original setup can also be doubled with one optical Fourier transform system for the joint power spectrum and one for the correlation plane (Figure 11). With three modulators, it is possible to perform the joint transform correlation in a single step with a full modulator for the input scene.

Comparison to serial transform correlators

The joint transform correlator has some advantages over the serial transform correlator. Since the phase of the Fourier transform is destroyed in the JTC, there are much fewer constraints on the design. So it is advantageous to use an optical convergent beam setup to obtain the Fourier transform. As mentioned before, there is no need for a fully complex spatial light modulator in the joint transform correlator.



Figure 11 JTC implementation using two power spectrum machines.

This allows the use of commercially available spatial light modulators primarily designed for projectors or for displays, where phase modulation is not required. Since there is a wider market for such devices, they are cheaper.

For pattern recognition, the joint transform correlator has some properties that a serial transform correlator cannot reproduce. Some pattern recognition techniques require a linear combination of multiple amplitude correlations of the scene with different references. This is impossible with serial correlators because only the intensity of the correlation plane is detected. In a JTC, the joint power spectrum is linked to the correlation plane by the Fourier transform. So it is possible to obtain linear combinations of correlation planes by performing the corresponding operations on the joint power spectra. Some recent pattern recognition techniques such as morphological correlation and the sliced orthogonal nonlinear generalized (SONG) correlation, have been optically implemented using a JTC, but the required operations could not be carried out by means of serial optical correlators.

Whereas optical serial transform correlators always carry out linear filtering operations, optical joint transform correlators can be made to carry out nonlinear filtering. This is achieved by imposing a nonlinear characteristic curve on the joint power spectrum, instead of the usual squaring operation inherent to the detection process. The nonlinearity can be intrinsic to the components (saturation, dynamic range) or obtained by introducing electronics between the CCD camera and the second SLM, or by using an optically addressed spatial light modulator. Nonlinear processing can enhance the weights of the high frequencies in the correlation, resulting in sharper correlation peaks and improved discrimination. To illustrate this effect, the joint power spectrum of the example of Figure 8 has been modified with a logarithmic transformation:



Figure 12 Correlation plane with a logarithmic transformation of the joint power spectrum.

$$E(\mu, \nu) = \ln(1 + \beta\|I(\mu, \nu)\|^2) \qquad [21]$$

with $\beta = 0.25$. The correlation plane for the transformed joint power spectrum is shown in Figure 12.



Figure 13 Optical vector–matrix multiplier.

It is clear that the discrimination has improved over that of the previous case.

Optical Vector–Matrix Multiplier

An operation that is frequently required in information processing is the product of a matrix and a vector. This can be accomplished by means on anamorphic optics as shown in Figure 13.

Here the input vector is a set of vertical fans of light from the source array, that are spread out, each over one row of the matrix mask by means of anamorphic optics. The inverse operation is carried out in the second half, so that the vertical array of spots in the output contains the vector–matrix product between the intensities of the source array and the transmissivities of the mask array.

A vector–matrix product can also be carried out by means of a conventional optical correlator as shown in Figure 14.

The input vector **a** is placed in a parallel beam at the focal plane of a conventional 2D correlator. A hologram in the Fourier plane contains a vector array **H**. The vector–matrix product **aH** appears along the axis in the correlation plane.

The above figure shows an input vector $f(x,b)\delta(y-b)$ containing the vector components $f(x1, x2, \ldots, xN)$ arrayed along the horizontal axis x, and shifted a distance a from the horizontal axis. If the Fourier transform of the mask in the filter plane is $h(x,y)$, then the output plane has the distribution:

$$g(x,y)=\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} f(\mu,v)\delta(\mu-b)h(x+\mu,y+v)\mathrm{d}\mu\mathrm{d}v \quad [22]$$

$$g(x,y)=\int_{-\infty}^{\infty} f(\mu,a)h(x+\mu,b-y)\mathrm{d}\mu \quad [23]$$

$$g(x,b)=\int_{-\infty}^{\infty} f(\mu,b)h(x+\mu,b)\mathrm{d}\mu \quad [24]$$

$$g(0,b)=\int_{-\infty}^{\infty} f(\mu,b)h(\mu,b)\mathrm{d}\mu \quad [25]$$



Figure 14 A vector–matrix product using a conventional 2D optical correlator.

So the output value along the y-axis at a distance a from the horizontal axis is equal to the scalar product of the vector $f(x,b)$ with the vector $h(x,b)$. Now if input vectors are stacked up one over the other in the input plane, each one will yield along the output y-axis a value that is the scalar product of the corresponding vector with the vector **h**. The set of values along the y-axis is therefore the vector–matrix product of the matrix constituted by the set of vectors in the input plane, with the vector **h** that is the impulse response of the filter. The cost for this operation is some considerable loss of light, since only the light along the y-axis is used in the output.

Applications of the optical vector–matrix product are optical crossbar, numerical matrix operations such as the solving of linear equations, optical neural networks, spectrum analysis and discrete Fourier transforms.

Conclusion

It has been estimated that serial coherent optical correlators should be able to attain data rates of up to 10^{12} operations per second, using the fastest spatial light modulators available. Joint transform correlators are somewhat slower, due to the input plane being divided between the object and the reference, to geometrical constraints in placement of targets, and due to the need to use electronics to carry out some of the operations. Until now, speeds have been limited by the data rates at the input, but as the speeds of optically addressed SLMs increase, the problem could be shifted to the output, where the lack of optical high spatial bandwidth threshold devices could cause a bottleneck.

List of Units and Nomenclature

A	Vector or matrix
CCD	Charge coupled device
$F(\mu, \nu)$	Fourier transform of $f(x, y)l$
FT	Fourier transform
FT^{-1}	Inverse Fourier transform
H^*	Complex conjugate of H
JTC	Joint-transform correlator
POF	Phase-only filter
R_{ab}	Correlation between functions *a* and *b*
(x, y)	Spatial coordinates
λ	Wavelength of light
(μ, ν)	Spatial frequencies
$*$	Correlation
SLM	Spatial light modulator
SONG	Sliced orthogonal nonlinear generalized correlation

See also

Coherence: Coherence and Imaging. **Diffraction:** Fraunhofer Diffraction; Fresnel Diffraction. **Fourier Optics**. **Geometrical Optics:** Aberrations. **Holography, Techniques:** Computer-Generated Holograms. **Imaging:** Information Theory in Imaging. **Information Processing:** Incoherent Analog Optical Processors; Optical Neural Networks.

Further Reading

Arsenault HH, Szoplik T and Macukow B (eds) (1989) *Optical Processing and Computing*. New York: Academic Press.

Bartelt H (1987) Unconventional correlators. In: Horner JL (ed.) *Optical Signal Processing*, pp. 97–128. New York: Academic Press.

Garcia-Martinez P, Arsenault HH and Ferreira C (2001) Time sequential nonlinear correlations for optical pattern recognition. Optoelectronic Information processing: optics for information systems. *Proceedings of SPIE* CR81-12: 186–207.

Goodman JW (1988) *Introduction to Fourier Optics*. New York: McGraw-Hill.

Javidi B (1994) Nonlinear joint transform correlators. In: Javidi B and Réfrégier P (eds) *Workshop on Optical Pattern Recognition*. Bellingham, WA: SPIE – The International Society for Optical Engineering, PM-12.

Javidi B and Horner JL (eds) (1994) *Real-Time Optical Information Processing*. New York: Academic Press.

Javidi B and Johnson KM (eds) (1996) *Optoelectronic Devices and Systems for Processing*. Bellingham, WA: SPIE – The International Society for Optical Engineering, CR65.

Lu XL, Yu FTS and Gregory D (1990) Comparison of Vander Lugt and joint transform correlators. *Applied Physics B* 51: 153–164.

McAulay AD (1991) *Optical Computer Architectures*. New York: Wiley & Sons.

Preston K (1972) *Coherent Optical Computers*. New York: McGraw-Hill.

Vander Lugt AB (1992) *Optical Signal Processing*. New York: John Wiley & Sons.

Free-Space Optical Computing

A A S Awwal, Lawrence Livermore National Laboratory, Livermore, CA, USA

M Arif, Infineon Technologies, Longmont, CO, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Free space optical computing encompasses a vast field, from digital and discrete to analog and hybrid optical computing. This article gives an overview of various algorithms, such as shadow-casting, symbolic substitution to nonlinear optics-based processors. Some of the core devices, such as modulators and nonlinear logic elements, are discussed. The optical computing concepts, originated with nonlinear optics and analog optical computing, are more commonly known as optical signal processing. Now they have culminated into digital optical computing, opening the door to highly specialized parallel computing architecture.

Parallel computation is a direct approach to enhance the speed of digital computations which are otherwise inhibited by the sequential processing bottleneck. Physical limitations – such as limited interconnections, interactions amongst electrons, with the consequent inability to share a data bus simultaneously, and constant propagation delay of electronic circuits – place an upper bound on the speed of the fastest operation possible with an electronic computer, without a modification to the computing architecture. Optics provides an architectural advantage over electronics, due to the fact that the most natural way to use optics lends itself to a parallel implementation. Optical signals propagate in parallel, cross each other without interference (whereas charged electrons interact heavily with each other), have the lowest possible propagation delay of all signals, and can provide million channel free-space interconnections with simple lenses (whereas an unrealistic number of connections are necessary for electrons). Thus, optics is an excellent candidate for implementing parallel computing machines using the 3D space connectivity. While electronic architecture is naturally 2D, optical free space architecture is 3D, exploiting the third dimension of space. The communication bottleneck forces electronic computers to update the computation state space sequentially, whereas the use of optics will empower one to change the entire computation space in parallel.

Historical Perspective

Historically, digital optical computing was proposed as a natural extension of nonlinear optics. Just as transistors, which are nonlinear electronic devices, led to the realization of the computing logic using transistors, it was envisioned that nonlinear optical effects would give rise to optical transistors which would lead to development of optical logic gates. One of the limitations of nonlinear optical device-based computation is the high laser power requirement to demonstrate any nonlinear optical effect.

One of the effects used to demonstrate nonlinearity is to change the refractive index with the incident intensity. In other words, most materials will behave linearly with low optical energy. The refractive index expressed as $n = n_0 + n_2 I$ is nominally linear because the nonlinear co-efficient n_2 is usually very small. In the presence of high power, the $n_2 I$ is significant enough to cause an optical path change by altering the refractive index. When such a medium is placed inside a Fabry–Perot resonator, it will allow one to control the transmission of the filter by changing the incident intensity. Thus, at high power, it shows a nonlinear behavior or bistability. The term optical bistability was coined, which meant the presence of two stable states of output for the same intensity value.

Another development took place at the University of Michigan by the development of a precision optical processor; this was an optical processor which could process radar signals using optics, this is the example of an analog optical computing processor.

A third area which is in between the digital and the analog are the discrete level devices which most often take the form of matrix-based processors. Free space optical matrix vector multipliers are examples of such processors.

The latest field of optical computing research is in the algorithms and architecture area. The motivation here is to develop new algorithms which take advantage of optics. The thing that is lacking is the presence of appropriate device technology that can implement the algorithm in a given architecture. In terms of practical realization, analog optical computing is the most successful one. Adaptive optic processors have found success both in astronomy as well as vision sciences, and more recently in optical imaging through the atmosphere.

Development of free space optical computing has two main driving forces: the technology (device) base and the algorithm base. In this classification, since the field is in its infancy, both device-based classes and architectural (algorithm) classes are listed side-by-side as separate entities, ignoring the natural overlap that may be present in some instances. For example, nonlinear optical devices could be implemented into a variety of architecture that is listed below. Holographic processor is another technology-based class while some other architectures, such as, symbolic substitution may involve use of holograms, but it does not exclude it being a class by itself. The following list gives a classification of optical free space computing:

1. Digital Optical Computing:
    (a) Pattern coded computing or cellular logic:
        (i) Optical shadow-casting processor;
        (ii) Symbolic substitution;
        (iii) Theta logic based computation.
    (b) Parallel arithmetic circuits:
    (c) Hybrid optical computing:
    (d) Nonlinear optical device based:
    (e) Threshold logic.
2. Discrete optical computing:
    (a) Optical fuzzy logic:
    (b) Optical matrix processors:
        (i) Vector matrix multiplier;
        (ii) Differential equation solver;

      - (iii) Linear algebra processor;
      - (iv) DFT processor;
      - (v) Programmable logic array;
      - (vi) Associative memory processor.
   - (c) Optical neural network.
3. Analog optical computing:
   - (a) Adaptive optics processor;
   - (b) Partially coherent processing (white light processing):
   - (c) Fourier transform based processor:
   - (d) Nonlinear contact screen based:
   - (e) Holographic processors:
   - (f) Linear optical processors (image differentiation).

We start by discussing some of the device based classes and their underlying concepts: (a) nonlinear optics; (b) SLMs; and (c) hologram based.

Core Device Technologies Used for Free-Space Optical Computing

One of the most difficult challenges of optical computing (OC) is inventing devices that can realize aforementioned key advantages of optics. There exist, however, several key technology areas, where a breakthrough in any one of these will pave the way to real-world optical computing. We discuss here some of the major device technologies that relate to OC.

Spatial light modulator (SLM) converts information from different forms to the optical domain. As a result, SLM is used as an input device to an optical computing system. High contrast ratio, very high speed, and parallel addressing scheme are desirable properties of an SLM as an input device. For example, the SLM could be used to input a 2-dimensional signal or an image into a Fourier transform-based processor. Several applications of SLM are possible:

1. *Optical encoding*: Pattern coded logic can perform logic operations if inputs can be encoded using certain pattern;
2. *Encoding complex filter*: It could encode phase, amplitude or both; and
3. *As phase modulator*: for adaptive optics.

Two types of SLMs are liquid-crystal based and micro-electromechanical (MEM) based. The former uses liquid crystals to change the phase of transmitted or reflected light leading to modulation of phase. Although the most successful commercial application of MEMs is its use in consumer electronics, such as projection TVs or video projectors, in free-space optical computing it can be used as:

- (a) an interconnection device;
- (b) an SLM for matrix; or
- (c) a phase modulating device in AO close loop control of optical phase aberrations or phase only filter.

The heart of the MEMs is tiny electrically controllable mirrors which can steer the incoming beam in a different direction or bend to create a relative optical path difference for the reflected beam.

Algorithms, where an SLM plays a major role, are pattern coded computing, optical matrix processors, adaptive optic processors, partially coherent processing, Fourier transform based processors, and linear optical processors.

Nonlinear Optical Element

A nonlinear optical element is an architecture or device structure which allows for utilization of the nonlinearity of the optical material that produces detectable changes of optical intensity. Figure 1 shows the basic block diagram for an optical computing basic element. To achieve an optical logic gate, one needs a scheme where light can be controlled by light, as current is controlled by current in a transistor. An optical device showing optical bistability can be used for this purpose. Optical bistability is defined as the situation where two different output intensities are possible for a given input intensity.

For example, as shown in Figure 2 below, at the intensity level of C, there are two stable states, one HIGH and one LOW. Just as the transistor has two stable states ON and OFF, the optical bistable device exhibits two states ON and OFF. The fact that such nonlinear behavior could implement logic behavior



Figure 1 Block diagram of an optical logic gate using nonlinear optical element.



Figure 2 Bistable behavior, a typical AND behavior with inputs A and B.



Figure 3 Bistable optical device, nonlinear medium in a Fabry–Perot cavity.

can be explained as follows. Assume that a two input device possesses a nonlinear characteristic as shown in Figure 2. Assume that the input intensity value of 1 is indicated by an intensity level equal to A. When both A and B are equal to 1, then the combined intensity switches the device to HIGH output state. However, if only one input is present, the output will be LOW. Thus, this bistable device acts as a logical AND gate.

To achieve optical bistability, two features are required, namely, nonlinearity and feedback. One way to achieve this is by placing a nonlinear medium in a Fabry–Perot cavity. Figure 3 shows a schematic of these devices. In Figure 3, A_1 is the incident field, A_1' is the reflected field, A_2 and A_2' are the forward and backward fields inside the cavity, respectively, and l is the cavity length.

The coupled wave equation for this system is given by

$$A_2' = \rho A_2 e^{2ikl-\alpha l} \qquad [1a]$$

$$A_2 = \tau A_1 + \rho A_2' \qquad [1b]$$

where, ρ is the amplitude reflectivity and τ is the amplitude transmissivity. The wave vector $k = n\omega/c$ and α is the absorption coefficient. In deriving the above equations, it was assumed that k and α are spatially invariant and real. Solving for A_2, from eqns [1a] and [1b] yields

$$A_2 = \frac{\tau A_1}{1 - \rho^2 e^{2ikl-\alpha l}} \qquad [2]$$

Equation [2] is the so-called Airy's equation which describes the properties of the Fabry–Perot cavity. From eqn [2] it can be seen that if k or α is a sufficiently nonlinear function, this device will show bistability. In general, both k and α can show nonlinearity. Hence optical bistability can be either absorptive or dispersive.

Absorptive Bistability

If the absorption coefficient α depends nonlinearly on the intensity, assuming k is constant, after some manipulation, eqn [2] can be written as

$$I_2 = \frac{TI_1}{[1 - R(1 - \alpha l)]^2} \qquad [3]$$

where, $I_i \propto |A_i|^2$, $T = |\tau|^2$ and $R = |\rho|^2$. In deriving eqn [3], it was assumed that the mirror separation is such that the system is in resonance and $\alpha l \ll 1$. If α depends on the intensity, it can be assumed that it follows the relationship of two level saturable absorbers, for simplicity, which is

$$\alpha = \frac{\alpha_0}{1 + I/I_s} \qquad [4]$$

where, α_0 denotes the unsaturated absorption coefficient, I is the local value of intensity, and I_s is the saturation intensity. Using eqn [4] in eqn [3] yields

$$I_1 = TI_2\left(1 + \frac{C_0}{1 + 2I_2/I_s}\right)^2 \qquad [5]$$



Figure 4 The input–output relationship of absorptive bistability predicted by eqns [5] and [6].

where, $C_0 = R\alpha_0 l/(1 - R)$. Also the output intensity I_3 is related to I_2 by

$$I_3 = TI_2 \qquad [6]$$

Using eqns [5] and [6], it can be shown that there can be multiple solutions to the above input–output relationship which predicts the optical bistability. Figure 4 shows a plot of DI_1 versus DI_3, where $D = 2/TI_s$, as a function of various C_0. As can be seen from Figure 4, for a high enough value of C_0, the system possesses multiple solutions.

Dispersive Bistability

The intensity dependence of the refractive index can be written as

$$n = n_0 + n_2 I \qquad [7]$$

If the refractive index n varies nonlinearly with intensity, assuming $\alpha = 0$ and using eqn [7], eqn [2] can be written as

$$A_2 = \frac{\tau A_1}{1 - \rho^2 e^{2ikl}} = \frac{\tau A_1}{1 - Re^{i\delta}} \qquad [8]$$

where, $\delta = \delta_0 + \delta_2$. δ_0 and δ_2 are given by

$$\delta_0 = \varphi + 2n_0 \frac{\omega c}{l}$$
$$\delta_2 = 2n_2 I \frac{\omega c}{l} \qquad [9]$$

where, φ is the phase associated with ρ and the fact that $k = n\omega/c$ is used.



Figure 5 Plots of both sides of eqn [10] as a function of I_2 and for increasing values of input intensity I_1. The oscillatory curve represents the right-hand side of eqn [10] and the straight lines represent the left-hand side with increasing values.

After some manipulation, eqn [8] can be rewritten in terms of intensity as

$$\frac{I_2}{I_1} = \frac{1/T}{1 + (4R/T^2)\sin^2(\delta/2)} \qquad [10]$$

and

$$\delta = \delta_0 + \left(4n_2 \frac{\omega}{c} l\right) I_2 \qquad [11]$$

Equation [10] can be solved graphically to show the introduction of bistable behavior as a function of input intensity. Figure 5 shows the plots of both sides of eqn [10] as a function of I_2 and for increasing values of input intensity I_1. The oscillatory curve represents the right-hand side of eqn [10] and the straight lines represent the left-hand side with increasing values of I_1. It can be readily seen from Figure 5 that at sufficiently high values of I_1, multiple solutions are possible for eqn [10]. This again will give rise to the bistable behavior.

Nonlinear Interference Filters

The optical bistability from the nonlinear interference filters (or etalons) can be used to achieve optical logic gates. The transmission property of these etalons can be modified by another optical beam, known as a bias beam. A typical logic gate and the transmission property are shown in the following figure. If the bias beam is such that, $P_{\text{switch}} - (P_a + P_{\text{bias}}) < P_b$, then the transmitted beam shown in Figure 6b readily follows an AND gate. The truth table for such configurations is shown in Figure 6d.

Four-Wave Mixing

Four Wave Mixing (FWM) can be used to implement various computing functions. Using the photorefractive effect and FWM in a third-order nonlinear optical material, optical phase conjugate beams can be obtained. A schematic of FWM and phase conjugation is shown in Figure 7. The forward pump beam interferes with the probe beam to produce a grating in the photorefractive material. The backward pump beam is then diffracted to produce a beam which retraces the path of the probe beam but has an opposite phase. It can be seen from Figure 7, that the optical phase conjugation can be readily used as an AND logical operator. By using the four-wave mixing, an optical counterpart of transistors has been introduced. FWM have also been used in AND-based optical symbolic substitution (OSS) operations. FWM is also used to produce matched filter-based optical correlators.

Another device showing the optical bistability is the self electro-optic effect device (SEED). SEEDs were used to implement optical logic circuits. The SEEDs are produced by putting multiple quantum wells (MQW) in the intrinsic region of a p-i-n structure. The MQWs are created by placing alternating thin layers of high (barriers) and low (wells) bandgap materials. An electric field is applied to the SEEDs externally. The absorption coefficient is a function of applied bias voltage. When a light beam is incident on these devices, it creates a photocurrent, consequently lowering the bias voltage across the MQW. This, in turn, increases the absorption and when the input optical power is high enough, the system sees a peak absorption and suddenly switches to a lower state and thus shows the bistable behavior. A schematic of SEED is shown in Figure 8.



Truth table for an AND function from the above setup from the transmitted beam

P_A= input 1	P_B = input 2	P_T = output
0	0	0
0	1	0
1	0	0
1	1	1

(d)



Figure 6 A typical optical logic gate configuration using nonlinear interference filter: (a) schematic; (b) the transmitted power output; (c) reflected power output (both as functions of inputs); and (d) the truth table for AND operation with beams A and B as inputs.



Figure 7 Four-wave mixing setup.



Figure 8 Schematic of self electro-optic effect devices.

Replacing the resistive load by a photodiode, a diode-based SEED (D-SEED) can be constructed, which is analogous to the way diode transistor logic was developed from resistor transistor logic in electronics. Electrically connecting two MQW p-i-n structure symmetric SEEDs (S-SEED) are constructed, which are less sensitive to optical power fluctuations and effectively provide isolation between input and output.

Pattern Coded Optical Computing: Symbolic Substitution or Cellular Logic

This is a keyword which is equivalent to simple digital logic operation. In digital logic, a truth table can describe the relationship between input and output variable. In symbolic substitution logic, this relationship is expressed as a 2D pattern rule. In any specific rule (equivalent to a row in the truth table) of SS logic, a specific 2D pattern is identified and replaced by another pattern. For example, in the case of binary logic, we can express the addition of two binary bits with the following truth table:

Rule number	*Input*		*Output*	
	A	*B*	*C*	*S*
1	0	0	0	0
2	0	1	0	1
3	1	0	0	1
4	1	1	1	0



Figure 9 Symbolic substitution example, the two inputs are coded using dual rails. The second column shows the four combinations of inputs (00, 01, 10, and 11). They are shifted and overlapped creating the fourth column. A mask detects the output as a dark pixel appearing through the transparent opening. The dark is inverted to create a detection output.

Here A and B are the two digits to be added, C and S are the sum and the carry bit, respectively. To convert this operation to an SS operation, we can say that a two bit binary pattern is identified and replaced by a sum bit and a carry bit. If we now express the above in terms of symbolic substitution, we will say let 0 and 1 be represented by the following 2D symbol. Then the rule for the carry bit generation is shown in Figure 9.

Note that each of these rules has to be implemented individually. However, one can implement these by only generating the 1 output or the zero output, whichever leads to the minimum rule. Here implementing the last rule is convenient, one can make a copy of the whole pattern and then overlap it with its left shift version. This will result in a dark pixel at the origin. This is inverted and then produces a detection output. Natural extension of SS is in signed digit computing, where carry free addition can be achieved, allowing parallel implementation of numerical algorithm using free space optics.

Optical Shadow Casting (OSC)

All digital logic is nonlinear. The nonlinearity of the digital logic is converted into nonlinearity of coding. The OSC system originally proposed by Tanida and Ichioka uses two-dimensional spatially encoded patterns as data input and light emitting diodes (LEDs) as light sources. In the original shadow-casting system, the inputs were represented by vertical and horizontal stripes of opaque and transparent bars. With this system, programmability was attained by changing the LED pattern and it was possible to realize 16 logical operations between two



Figure 10 An optical shadow-casting system.

variables as well as a half addition as an example of arithmetic operation. Later, polarized codes were introduced into shadow-casting systems. This improved technique, called the polarization-encoded optical shadow casting (POSC), enabled complex combinational logic units like binary and trinary full adders, as well as image processing applications, to be realized.

The lensless OSC system, as shown in Figure 10, consists of spatially encoded 2D binary pixel patterns as the inputs. The input patterns are kept in close contact at the input plane and the resulting input overlapped pixel pattern is illuminated by a set of LEDs from the source plane. The light originating from each of the LEDs located at the source plane produces a shadow of the input overlap pixel pattern at the output plane. The overlap of these relatively displaced shadows results in an output overlap pixel pattern at the output plane. A decoding mask placed at the output plane is then used to spatially filter and detect the logical output. To prevent crosstalk, specific spacing among the different processing elements must be maintained.

Discrete Processors: Optical Matrix Processor

Most of the discrete optical processing schemes revolve around optical matrix–vector multiplication. Many numerically useful operations such as: (a) linear algebraic operations; (b) signal processing algorithms; (c) Boolean logic; (d) digital multiplication by analog convolution; and (e) neural networks, can be formulated as matrix–vector multiplication. An example of the digital multiplication by analog convolution (DMAC) can be understood by the following numerical example:



$$1\ \ 7\ \ 12 = 1\times100+7\times10+12\times1=182$$

The two numbers are convolved as shown above. This is done by reversing one of the numbers (4 1), while keeping the other number in the same order (1 3), then sliding the reversed number to the right, and collecting the element by element products. The second partial products are 4 × 1 and 1 × 3 which are then added to give the convolution results. Surprisingly, the weighted number in mixed radix (since numbers that have digits higher than 9, are no longer decimal) has the same value as the product shown in the upper left. It is possible to have fast parallel convolution optically, resulting in fast parallel multiplier. However, an efficient electronic post processor is necessary to convert the mixed radix numbers to the radix of the to-be-multiplied numbers.

A basic optical matrix–vector multiplier is shown in Figure 11. Here the vector, represented by an expanding column of light, is projected onto the 2D matrix, possibly represented by a glass plate or electronically addressable spatial light modulator. As the light representing the vector passes through the transmitting medium, each element of the vector (**I**) gets multiplied by a column of matrix represented by the transmittance of the matrix (T). The product (**I**T)



Figure 11 A matrix–vector multiplier.

is integrated horizontally using a cylindrical lens. This leads to an addition operation of the partial products, resulting in the generation of the output product vector. Mathematically:

$$y = \begin{bmatrix} a_{11} & a_{12} & a_{13} & a_{14} \\ a_{21} & a_{22} & a_{23} & a_{24} \\ a_{31} & a_{32} & a_{33} & a_{34} \\ a_{41} & a_{42} & a_{43} & a_{44} \end{bmatrix} \begin{bmatrix} b_1 \\ b_2 \\ b_3 \\ b_4 \end{bmatrix} = \begin{bmatrix} a_{11}b_1 + a_{12}b_2 + a_{13}b_3 + a_{14}b_4 \\ a_{21}b_1 + a_{22}b_2 + a_{23}b_3 + a_{24}b_4 \\ a_{31}b_1 + a_{32}b_2 + a_{33}b_3 + a_{34}b_4 \\ a_{41}b_1 + a_{42}b_2 + a_{43}b_3 + a_{44}b_4 \end{bmatrix} \quad [12]$$

The above can be achieved if the vector b is expanded as

$$\begin{bmatrix} b_1 & b_2 & b_3 & b_4 \\ b_1 & b_2 & b_3 & b_4 \\ b_1 & b_2 & b_3 & b_4 \\ b_1 & b_2 & b_3 & b_4 \end{bmatrix}$$

and a point-by-point multiplication is performed between the expanded vector and the original matrix. Then the addition is performed by the cylindrical lenses.

Another simple application of vector matrix multiplier is in digital logic, known as programmable logic array (PLA). PLA is an electronic device that consists of a set of AND gates followed by a set of OR gates, which can be organized in AND–OR format suitable for realizing any arbitrary general purpose logic operation. AND logic is performed when light representing a logic level is passed through a transparency representing the other variable; OR is achieved by converging light to a common detector.

$$\text{Assume a function } F = AC + \bar{A}BD + A\bar{B}C \quad [13]$$

where $\bar{A}$ represents the logical inverse of A. Using DeMorgans' theorem in digital logic, this can be expressed as

$$\begin{aligned} F &= \overline{(\bar{A} + \bar{C})} + \overline{(A + \bar{B} + \bar{C})} + \overline{(\bar{A} + B + \bar{C})} \\ &= \bar{y}_1 + \bar{y}_2 + \bar{y}_2 \end{aligned} \quad [14]$$

Now the y_is can be generated by the vector matrix product, as shown below:

$$\text{where} \begin{pmatrix} y_1 \\ y_2 \\ y_3 \end{pmatrix} = \begin{pmatrix} 0 & 1 & 0 & 0 & 0 & 1 & 0 & 0 \\ 1 & 0 & 0 & 1 & 0 & 0 & 0 & 1 \\ 0 & 1 & 1 & 0 & 0 & 1 & 0 & 0 \end{pmatrix} \begin{pmatrix} A \\ \bar{A} \\ B \\ \bar{B} \\ C \\ \bar{C} \\ D \\ \bar{D} \end{pmatrix} \quad [15]$$

Note here that the AND has been converted to OR, which needs to be inverted and then ORed to generate the function F. A setup shown in Figure 11 can be used to accomplish this. In step 1, the y_is are generated, and then in step 2 they are inverted and summed by a second pass through the same system with a different mask. Other applications of vector–matrix multipliers are in neural networks, where the interconnection weights are represented by the matrix and the inputs are the vector.

Analog Optical Computing

Correlation is a way to detect the presence of signal in additive noise. Optics offer a fast way of performing correlations. The practical motivation of this area comes from the fact that a lens performs a Fourier transform of a two-dimensional signal at its focal plane. The most famous analog optical computing is known as optical matched filter. The theoretical basis of an optical matched filter is in the Fourier theorem of matched filtering which states that the cross correlation between two signals can be formed by multiplying the Fourier transform of the signal and the complex conjugate of the second signal and followed by a subsequent Fourier transform operation. Mathematically:

$$\text{Correlation}(f, g) = \mathrm{F}^{-1}[\mathrm{F}\{f\}^{*}\text{conjugate}(\mathrm{F}\{g\})] \quad [16]$$

where F represents a Fourier transform operation and F^{-1} represents an inverse transform. Since the lens can easily perform the Fourier transform, and multiplication can be performed by light passing through a medium, the only problem that has to be



Figure 12 An optical 4-*f* set up. Lenses perform Fourier transform at their focal plane.

solved is to represent the signal and the filter in the optical domain. Since an SLM can represent both the real signal and the complex filter, thus the whole operation can be performed in a 4-*f* setup as shown in Figure 12. The input is displayed in the input plane by an SLM, the first lens performs a Fourier transform. This filter (conjugate F{*g*}) is encoded using another SLM and placed at the filter plane. When light from the F{*f*} passes through the filter, it performs the required multiplication. The second lens performs a second Fourier transform and produces the correlation output at the output plane. Variations of the basic setup exist as a joint transform correlator (JTC) or binary phase-only filter (BPOF). While the JTC achieves the product of the complex domain by adding the two signals and squaring, the BPOF is achieved by simplifying the complex domain filter by numerically approximating it with the binarized phase. Other applications of linear optical processing can be performed in the basic 4-*f* optical setup where filters such as low-pass or high-pass filters, can be set up in the correlation plane.

The hologram base computing treats holograms as a legitimate way of signal transformation from one form to another, just as a lens transforms from one domain to another. Holograms are complex representations that can act on a signal. A lens can be approximated by a hologram, in reality functions of many optical elements, such as lens, grating, prism, and other transformation such as beamsplitting, it can be combined into single computing element known as computer-generated hologram (CGH). The smartness of this type of system depends on how many operations have been replaced by a single CGH.

It is envisioned that optical computing is better suited for special purpose computing rather than general purpose computing. However, the future of optical computing lies in the marriage of appropriate device technology with the right architecture at the right applications. The development of quantum computing may hold new promises for optical computing.

List of Units and Nomenclature

DMAC	Digital multiplication by analog convolution
JTC	Joint transform correlator
OC	Optical computing
PLA	Programmable logic array
QC	Quantum computing
SLM	Spatial light modulator

See also

Nonlinear Optics, Basics: Four-Wave Mixing; Nomenclature and Units. **Quantum Optics:** Quantum Computing with Atoms.

Further Reading

Arsenault H, Szoplik T and Macukow B (eds) (1989) *Optical Processing and Computing*. San Diego, CA: Academic Press.

Boyd RW (1992) *Nonlinear Optics*. San Diego, CA: Academic Press.

Gaskill J (1978) *Linear Systems Fourier Transform and Optics*. New York: Wiley.

Gibbs HM (ed.) (1982) *Optical Bistabiligy II*. New York: Plenum Press.

Goodman JW (1996) *Introduction to Fourier Optics*, 2nd edn. New York: McGraw Hill.

Ichioka Y and Tanida J (1984) Optical parallel logic gates using a shadow-casting system for optical digital computing. *Proceedings of the IEEE* 72: 787.

Karim MA and Awwal AAS (1992) *Optical Computing: An Introduction*. New York: Wiley.

Koren I (1993) *Computer Arithmetic Algorithms*. New Jersey: Prentice Hall.

McAulay A (1992) *Optical Computing Architecture*. New York: Wiley.

Reynolds GO, DeVelis JB, Parrent GB and Thompson BJ (eds) (1989) *Physical Optics Notebook: Tutorials in Fourier Optics*. Bellingham, CA: SPIE Optical Engineering Press.

Saleh BEA and Teich MC (1991) *Fundamentals of Photonics*. New York: John Wiley & Sons.

VanderLugt A (1992) *Optical Signal Processing*. New York: Wiley.

Yu FTS and Jutamulia S (1992) *Optical Signal Processing, Computing and Neural Networks*. New York: Wiley.

Incoherent Analog Optical Processors

S Jutamulia, University of Northern California, Petaluma, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

After low-cost lasers became widely available, it seemed that incoherent analog optical processing was no longer important. In general, incoherent optical processing has no apparent significant advantages, as compared with its coherent optical counterpart or digital computer processing. However, although nobody now attempts to build an incoherent optical processor, such as an incoherent correlator, most instruments are still operating using incoherent or natural light. These incoherent instruments relate to imaging, including cameras, microscopes, telescopes, projection displays, and lithographic equipment. From this point of view, it is still very important to study the principles of incoherent analog optical processing, in order to further progress or improve the incoherent image.

Incoherent Image Formation

The image formation in a coherent optical system can be explained using the linear system. A perfect point $\delta(x, y)$ in the input plane is imaged in the output plane as the impulse response of the system $h(x, y)$. When the input is only a single point, the output amplitude is simply $h(x, y)$ and the output intensity is $|h(x, y)|^2$. Accordingly, the function of $|h(x, y)|^2$ is called point spread function (PSF).

If we consider that the input object is the collection of a large number of very fine points, under coherent light illumination, the output image will be the collection of the same number of blurred spots. The shape of each blurred spot is $h(x, y)$. If the amplitude function of input object is $f(x, y)$, the amplitude function of output image is

$$o(x, y) = \iint_{-\infty}^{\infty} f(p, q) h(x - p, y - q) \mathrm{d}p \, \mathrm{d}q \qquad [1]$$

which is a convolution of $f(x, y)$ and $h(x, y)$. The intensity function of output image is

$$|o(x, y)|^2 = \left| \iint_{-\infty}^{\infty} f(p, q) h(x - p, y - q) \mathrm{d}p \, \mathrm{d}q \right|^2 \qquad [2]$$

According to the convolution theorem, in the Fourier transform domain or frequency domain, we have

$$O(u, v) = F(u, v) H(u, v) \qquad [3]$$

where $O(u, v)$, $F(u, v)$, and $H(u, v)$ are the Fourier transforms of $o(x, y)$, $f(x, y)$, and $h(x, y)$, respectively. $H(u, v)$ is the transfer function of the coherent imaging system. To distinguish it from the incoherent imaging system, it is also called coherent transfer function (CTF).

The same optical imaging system is now illuminated with incoherent light instead of coherent light. The amplitude impulse response is still the same $h(x, y)$, and the point spread function is also the same $|h(x, y)|^2$. Similarly, the input object is the collection of perfect points, and the output image is the collection of blurred images of each point. However, since the illuminating light is incoherent, light from any point in the input object is not coherent with light from any other points. Thus, there is no interference with light from different points. The output image is simply the addition of intensity patterns generated by each point in the input object. The amplitude function of the output image is not computable. However, the intensity function of the output image is

$$|o(x, y)|^2 = \iint_{-\infty}^{\infty} |f(p, q)|^2 |h(x - p, y - q)|^2 \mathrm{d}p \, \mathrm{d}q \qquad [4]$$

In the frequency domain, we now have

$$O_I(u, v) = F_I(u, v) H_I(u, v) \qquad [5]$$

where $O_I(u,v)$, $F_I(u,v)$, $H_I(u,v)$ are Fourier transforms of $|o(x,y)|^2$, $|f(x,y)|^2$, and $|h(x,y)|^2$, respectively. The intensity impulse response $|h(x,y)|^2$ is the PSF. Note that the index I of O_I, F_I, and H_I denotes intensity. The function $H_I(u,v)$ is now the transfer function of the incoherent imaging system, which is called optical transfer function (OTF).

Referring to Fourier analysis, if $H(u, v)$ is the Fourier transform of $h(x, y)$, the Fourier transform of $|h(x, y)|^2$ is the autocorrelation of $H(u, v)$ as follows:

$$H_I(u, v) = \iint_{-\infty}^{\infty} H(p, q) H^*(p - u, q - v) \mathrm{d}p \, \mathrm{d}q \qquad [6]$$

The OTF (the function $H_I(u, v)$) is the autocorrelation of CTF (the function $H(u, v)$), which is a complex function in general. It can be written as

$$\mathrm{OTF} = |\mathrm{OTF}| \exp(i\phi) \qquad [7]$$

We can further write

$$\mathrm{MTF} = |\mathrm{OTF}| \qquad [8]$$

where MTF stands for modulation transfer function, and

$$\mathrm{PTF} = \phi \qquad [9]$$

where PTF stands for phase transfer function.

Measurement of MTF

The MTF of an incoherent imaging system can be measured empirically using an input that is a cosine grating having intensity transmittance function:

$$|f(x)|^2 = 1 + \cos(2\pi a x) \qquad [10]$$

where a is the frequency of grating. The output or the image intensity function will be

$$|o(x)|^2 = 1 + m\cos(2\pi a x + \varphi) \qquad [11]$$

where m, the contrast, can be measured by

$$m = \frac{|o(x)|^2_{\max} - |o(x)|^2_{\min}}{|o(x)|^2_{\max} + |o(x)|^2_{\min}} \qquad [12]$$

In the frequency domain, the Fourier transform of the input function is

$$F_I(u) = \delta(u) + \tfrac{1}{2}\delta(u-a) + \tfrac{1}{2}\delta(u+a) \qquad [13]$$

The Fourier transform of the output function will be

$$O_I(u) = F_I(u)\mathrm{OTF}(u) \qquad [14]$$

Substitution of eqn [13] yields

$$O_I(u) = \delta(u)\mathrm{OTF}(0) + \tfrac{1}{2}\delta(u-a)\mathrm{OTF}(a) + \tfrac{1}{2}\delta(u+a)\mathrm{OTF}(-a) \qquad [15]$$

Notice that

$$\mathrm{OTF}(0) = 1 \qquad [16]$$

due to normalization, and

$$\mathrm{OTF}(a) = \mathrm{OTF}(-a) \qquad [17]$$

Because OTF is an autocorrelation function, it must be a symmetric function. Substitution of eqns [16] and [17] into eqn [15] yields

$$O_I(u) = \delta(u) + \tfrac{1}{2}\delta(u-a)\mathrm{OTF}(a) + \tfrac{1}{2}\delta(u+a)\mathrm{OTF}(a) \qquad [18]$$

Remembering that OTF is a complex function given in eqn [7], we can write

$$\mathrm{OTF}(a) = \mathrm{MTF}(a)\exp(i\phi(a)) \qquad [19]$$

Substitution of eqn [19] into eqn [18] yields

$$O_I(u) = \delta(u) + \tfrac{1}{2}\delta(u-a)\mathrm{MTF}(a)\exp(i\phi(a)) + \tfrac{1}{2}\delta(u+a)\mathrm{MTF}(a)\exp(i\phi(a)) \qquad [20]$$

The inverse Fourier transform of eqn [20] is

$$|o(x)|^2 = 1 + \mathrm{MTF}(a)\cos(2\pi a x + \phi(a)) \qquad [21]$$

By comparing eqn [21] and eqn [11], we find

$$\mathrm{MTF}(a) = m \qquad [22]$$

and the PTF

$$\phi(a) = \varphi \qquad [23]$$

Therefore, the MTF at frequency $u = a$ of the incoherent imaging system can be measured using eqn [12]. To get the complete MTF(u), the measurement is repeated using cosine gratings with different frequencies. The PTF can also be measured at the same time.

Incoherent Spatial Filtering

In the 4f coherent optical processor, the first lens performs the Fourier transform, and the second lens performs the inverse Fourier transform, as shown in Figure 1. The Fourier transform domain or frequency domain is materialized in the frequency plane that is the back focal plane of the first lens.



Figure 1 4f coherent optical processor consists of two Fourier transform lenses.

Thus, the Fourier transform of the object can be visualized in the frequency plane. For example, if the object is a grating, we will see its frequency components in the frequency plane. However, if the coherent illumination (e.g., from a laser) is replaced with incoherent illumination (e.g., from a lightbulb), the pattern of Fourier transform in the frequency plane disappears. Does it mean that we can no longer perform spatial filtering? No, we still can perform spatial filtering, although the pattern of Fourier transform is no longer visualized.

Consider that we have a spatial filter in the frequency plane whose physical form can be expressed by the function $H(u, v)$. For illustration, this spatial filter is simply a small one-dimensional window $H(u)$, as shown in Figure 2a. If the 4f optical processor is illuminated with coherent light, the CTF of the system is $H(u)$ itself as shown in Figure 2b. However, if the 4f optical processor is illuminated with incoherent light, we will use OTF instead of CTF in the analysis of linear system. The OTF is the autocorrelation of CTF, which is graphically depicted in Figure 2c. In this example, since the OTF is real and positive, the MTF is identical to the OTF.



Figure 2 (a) One-dimensional window in frequency plane functions as a spatial filter. (b) CTF and (c) OTF or MTF produced by spatial filter (a).

For simplicity, we analyze and show a one-dimensional filter only in a two-dimensional graph. It certainly can be extended to the two-dimensional filter. And we need a three-dimensional graph to show the two-dimensional autocorrelation.

It is important to note that, although the CTF is a high pass filter that passes frequencies in the band of $u = a$ to $u = a + b$, the MTF is a low pass filter that passes frequencies from $u = -b$ to $u = b$, independent of a. This indicates that an incoherent processor cannot enhance high frequency. It is always a low pass processor. It is interesting to note that the OTF is independent of the location of the filter $u = a$, but it is determined by the width of the filter $\Delta u = b$ only.

Accordingly, an aperture made up of randomly distributed pinholes behaves as a low pass filter in an incoherent imaging system. The cut-off frequency of such a filter can be derived from the diameter of the pinhole, which is equivalent to Figure 2b. The procedure for using this filter is simple. If a camera is used to take a picture, the random pinhole filter can be simply attached to the camera lens. The picture taken will not consist of high-frequency components, because the filter acts like a low pass filter. The low pass filtering can also be done by reducing the aperture of camera. However, by doing so, the light entering the camera is also reduced. The use of a random pinhole filter removes high frequencies without reducing the light intensity. When the random pinhole filter is placed in the frequency plane of a 4f coherent optical processor, it can be used to reduce the speckle noise. Note that the speckle noise is the main drawback in coherent optical processing.

Incoherent Complex Matched Spatial Filtering

Lohmann and Werlich pointed out that the Vander Lugt correlator can also be operated with incoherent light. In the coherent Vander Lugt correlator the correlation term is:

$$o_3(\xi, \eta) = \iint_{-\infty}^{\infty} f(\alpha, \beta) g*(\alpha - \xi, \beta - \eta) \mathrm{d}\alpha \mathrm{d}\beta \quad [24]$$

Its intensity distribution is

$$|o_3(\xi,\eta)|^2 = \left| \iint_{-\infty}^{\infty} f(\alpha,\beta) g*(\alpha-\xi,\beta-\eta)\mathrm{d}\alpha\,\mathrm{d}\beta \right|^2 \quad [25]$$

However, when the input object is illuminated with incoherent light instead of coherent light, the intensity distribution of the correlation term becomes

$$|o_3(\xi,\eta)|^2 = \iint_{-\infty}^{\infty} |f(\alpha,\beta)|^2 |g(\alpha-\xi,\beta-\eta)|^2 \mathrm{d}\alpha\,\mathrm{d}\beta \quad [26]$$

Equation [26] shows the correlation of $|f(x,y)|^2$ and $|g(x,y)|^2$. Therefore, when $f(x,y)$ is identical to $g(x,y)$, the correlation peak always appears regardless of whether the illumination is coherent or incoherent. However, the detailed structures of the coherent and incoherent correlation outputs are different. Note that the joint transform correlator cannot be operated using incoherent light, since no joint Fourier spectra will be formed.

Depixelization of Projection Display

Recently, a technique to remove the pixel structure from an image projected by liquid crystal projection display has been reported. A liquid crystal projection display must have a pixel structure to form an image. Can we remove this pixel structure from the projected image to obtain a movie-like image? It is well known that a single hole in the frequency plane can perform a coherent spatial filtering, such that the pixel structure will disappear from the output image.

Because of the pixel structure, we get multiple Fourier spectra in the frequency plane. By passing only one spectrum order through the hole in the frequency plane, the pixel structure can be removed as shown in Figure 3.

It is interesting to note that selecting any one of the spectra will produce the image at the same location.



Figure 3 Removal of pixel structure using a single hole in frequency plane. Most of the energy is wasted and the output intensity is dim.



Figure 4 Removal of pixel structure using multiple phase filters with different thickness to cover each Fourier spectrum order. No energy is wasted and the output intensity is very bright.

However, if two spectra are passed, on the top of the produced image, Young interference fringes are also produced. If all spectra are passed, the produced interference fringes are in fact the pixel structure itself. By passing only one spectrum order and blocking most spectrum orders, we lose most of the energy. The projected image will be very dim, although the pixel structure is removed.

To overcome this problem, we may cover each spectrum order with a transparent material having different thickness as shown in Figure 4. Thus, every spectrum order is passed and delayed by a phase filter with a different thickness. If the delay produced by the phase filter is larger than the coherent length of light, every spectrum order is no longer coherent to each other. In other words, the resultant image is the sum of the intensities of all images. As a result, the pixel structure does not appear, and no intensity is lost. For a white light source, since the frequency bandwidth is large, the coherent length is typically on the order of several tens of μm.

This technique can significantly improve the quality of the liquid crystal projection display. Figure 5 shows the experimental result of a depixelated projection image. Figure 5a shows the projected image of an input with pixel structure when no phase filter is applied in the frequency plane. Figure 5b shows the projected image of the same input with pixel structure when phase filters are applied in the frequency plane. The pixel structure is successfully removed as shown in Figure 5b.

Computed Tomography

The computed tomography or CT using X-ray is usually considered beyond optical information processing. However, it is interesting to review the principle of the X-ray CT, since the X-ray source is incoherent, and the CT image reconstruction utilizes Fourier transformation that is commonly used in



Figure 5 (a) Projected image consists of pixel structure when no phase filter is applied in the frequency plane. (b) Depixelated image is produced when phase filters are applied in the frequency plane.

optical information processing. The X-ray CT is used for taking the cross-section picture of the human body. Note that a conventional X-ray picture only provides a projection instead of a cross-section picture.

Consider the case when an X-ray penetrates through an object characterized by its attenuation coefficient or density function $f(x,y)$ as shown in Figure 6. The detected X-ray intensity is

$$I = I_0 \exp - \left\lfloor \int f(x,y)\mathrm{d}s \right\rfloor \qquad [27]$$

where I_0 is the original intensity. Equation [27] can be written as

$$\int f(x,y)\mathrm{d}s = -\ln \frac{I}{I_0} \qquad [28]$$

Apparently, we cannot directly measure $f(x,y)$, although we can obtain $\int f(x,y)\mathrm{d}s$ from the measurement of I and I_0. However, we want to get the cross-section picture which is the density function $f(x,y)$. The basic idea is to compute $f(x,y)$ from its Fourier transform $F(u,v)$, and $F(u,v)$ is derived from eqn [28]. $F(u,v)$ can be expressed as

$$F(u,v) = \int\int_{-\infty}^{\infty} f(x,y) \exp[-\mathrm{i}2\pi(ux+vy)]\mathrm{d}x\,\mathrm{d}y \qquad [29]$$

For $v = 0$, eqn (29) becomes

$$F(u,0) = \int\int_{-\infty}^{\infty} f(x,y) \exp[-\mathrm{i}2\pi ux]\mathrm{d}x\,\mathrm{d}y \qquad [30]$$



Figure 6 X-ray passes through object having density function $f(x,y)$.

which can be written

$$F(u,0) = \int_{-\infty}^{\infty} p(x) \exp[-\mathrm{i}2\pi ux]\mathrm{d}x \qquad [31]$$

where

$$p(x) = \int_{-\infty}^{\infty} f(x,y)\mathrm{d}y \qquad [32]$$

The projection function $p(x)$ given by eqn [32] can be obtained using an X-ray parallel beam as shown in Figure 7. Then $F(u,0)$ can be computed using computer based on eqn [31]. $F(u,0)$ is the Fourier transform along the u-axis. To get other data, we rotate the coordinate (u,v) to (u',v') by a small angle α. Correspondingly, the coordinate (x,y) is also rotated to (x',y') by the same angle α while the object is not rotated as shown in Figure 8.

From the measurement shown in Figure 8, we can get $p(x')$, which, in turn, provides $F(u',v'=0)$. By increasing the rotation angle α, we will get other data of $F(u'',v''=0)$. The completion of rotation of 180 degrees will give us the data in the frequency domain (u,v) as shown in Figure 9.

After the data $F(u,v)$ is collected, as shown in Figure 9, $F(u,v)$ can be inverse Fourier transformed to



Figure 7 X-ray parallel beam passes through the object to produce projection function $p(x)$.



Figure 8 Rotated X-ray parallel beam produces the rotated projection function $p(x')$.



Figure 9 $F(u,v)$ computed from a set of rotated projection functions.

produce $f(x,y)$. There are two approaches in the inverse Fourier transform. The first approach is to interpolate the computed value $F(u,v)$ such that the value of $F(u,v)$, on a regular grid structure, can be defined before an inverse Fourier transform can be taken.

The second approach is to apply polar coordinates, instead of Cartesian coordinates, to the inverse Fourier transform, such that no interpolation in frequency domain (u,v) is required. The inverse Fourier transform in Cartesian coordinates is as follows:

$$f(x,y)=\int\int_{-\infty}^{\infty} F(u,v)\exp[\mathrm{i}2\pi(ux+vy)]\mathrm{d}u\,\mathrm{d}v \qquad [33]$$

It can be written in polar coordinates as:

$$f(x,y)=\int_0^{2\pi}\int_0^{\infty} F(\rho\cos\phi,\rho\sin\phi) \times\exp[\mathrm{i}2\pi\rho(x\cos\phi+y\sin\phi)]|\rho|\mathrm{d}\rho\,\mathrm{d}\phi \qquad [34]$$

where

$$u=\rho\cos\phi \qquad [35]$$

$$v=\rho\sin\phi \qquad [36]$$

Therefore $f(x,y)$ can be obtained from the collected $F(u,v)$, as shown in Figure 9, without further interpolation using eqn [34]. Note that eqns [31], [33], and [34] are computed using a computer program.

See also

Spectroscopy: Fourier Transform Spectroscopy.

Further Reading

Bracewell RN (1965) *The Fourier Transform and its Applications*. New York: McGraw-Hill.

Hounsfield GN (1973) Computerized transverse axial scanning (tomography): Part I. *British Journal of Radiology* 46: 1016–1022.

Iizuka K (1985) *Engineering Optics*. New York: Springer-Verlag.

Jutamulia S, Toyoda S and Ichihashi Y (1995) Removal of pixel structure in liquid crystal projection display. *Proceedings of SPIE* 2407: 168–176.

Klein MV (1970) *Optics*. New York: Wiley.

Lohmann AW and Werlich HW (1971) Incoherent matched filtering with Fourier holograms. *Applied Optics* 10: 670–672.

Reynolds GO, DeVelis JB, Parrent GB Jr and Thompson BJ (1989) *The New Physical Optics Notebook: Tutorials in Fourier Optics*. Bellingham, WA: SPIE.

Vander Lugt A (1964) Signal detection by complex spatial filtering. *IEEE Trans. Inf. Theo.* IT-10: 139–145.

Yang X, Jutamulia S and Li N (1996) Liquid-crystal projection image depixelization by spatial phase scrambling. *Applied Optics* 35: 4577–4580.

Yu FTS and Wang EY (1973) Speckle reduction in holography by means of random spatial sampling. *Applied Optics* 12: 1656–1659.

Optical Bit-Serial Computing

A D McAulay, Lehigh University, Bethlehem, PA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Why Optical Bit-Serial Computing?

Optical bit-serial computing will lower cost and improve dataflow rates in optical telecommunications and associated computing. Moreover, the electromagnetic immunity of optics will enhance security for computing as well as for communications. Also, absence of sparking with optics enables safe operation, even in hazardous environments.

Currently, optical bit-serial communication involves passing terabits of data per second (10^{12} bps) – thousands of encyclopedias per second – along an optical fiber by switching light of multiple colors on and off, representing ‘1’ and ‘0’ bits respectively. Replacing electronic computing functions, constrained to tens of gigabits per second (10^9 bps), with integrated optics, ones of much higher speed, enables faster flow rates – allowing continuation of the annual doubling of capacity-distance that has occurred since the 1970s. Cost is reduced by eliminating the demultiplexing and multiplexing for optic-electronic-optic (OEO) conversions. Two illustrative areas of optical bit-serial computing for replacing electronic computing functions are described: computing at up to 40 Gbps with semiconductor optical amplifiers (SOAs) and computing at higher bit rates with integrated optic components. Several books address the relevant technical background: free-space optical information processing, optical computer architectures, optical fiber communications, and integrated optics.

Computing with Semiconductor Optical Amplifiers

Semiconductor optical amplifiers, SOAs, allow nonlinear operations (switching, logic) at low power (mW) because of amplification – typically up to 1000. An SOA is a laser diode with antireflection coatings in place of reflecting facets. Light pulses at bit rates in excess of 40 Gbps are amplified by absorbing power from an electronic pump. SOAs are used in the following, at bit rates up to 40 Gbps, for nonlinear operations in cross-gain, cross-phase, or cross-polarization.

SOA-XGM for Logic

Figure 1 shows an SOA in cross-gain modulation (XGM) performing a NOR function. Either A or B inputs at a ‘1’ level, driving the SOA through couplers into saturation, lowering its gain. A continuous wave at C, having a different frequency λ_3, from that of A, λ_1 and B, λ_2, experiences the decrease in gain, resulting in an output ‘0’ level at frequency λ_3. The filter in Figure 1 can be avoided by counter-propagating A and B through the SOA from right to left. XOR gates use interference between two incoming streams of bits (locked to identical frequency, phase, polarization) to correlate headers on internet protocol (IP) address headers – similar to matching zip codes in postal mail routing machines. Bit-serial-adders are constructed from combinations of XOR and NOR gates; subsequently the adders are used to construct ripple-carry-adders for word addition. In addition, NOR gates are used to construct flip-flops; hence registers which form short-term memory.



Figure 1 Optical XGM-SOA NOR gate.



Figure 2 Optical XGM-SOA 2R signal regeneration.


Control signal input
Semiconductor optical amplifier (SOA)
Directional coupler 10/90
Optical bit-serial data input
Optical bit-serial data output

Figure 3 XPM-SOA in Sagnac interferometer for optical manipulation of bits at high data rates.



Figure 4 Integrated optic Optiwave layout for microring resonator.

SOA-XGM for Frequency Conversion

Ignoring input B, the bit information in Figure 1 has been transferred from carrier frequency A onto the carrier frequency C, with inversion. This enables switching of signals in wavelength division multiplexing (WDM), for example, color reuse is simplified and a color red is routed to the location where blue was previously routed; this is equivalent to time slot interchangers for switching in time division multiplexing (TDM).

SOA-XGM for 2-R Signal Regeneration

Figure 2 show how two SOAs may be used in sequence to restore signal levels distorted by propagation or computation; reamplification and reshaping (2-R). The ‘1’ level at the output of the first SOA is clipped by gain saturation, removing noise, this becoming the ‘0’ level at the output of the second SOA. The second SOA clips the ‘1’ level at the output.

SOA-XPM with Interferometer

In cross-phase modulation (XPM), the signal at A, Figure 1, changes the phase of carrier for signal C passing through the SOA (signal levels may be less than for XGM). Inclusion of an SOA in an interferometer, Mach–Zehnder or Sagnac, converts phase to intensity for frequency conversion, switching or high-speed bit manipulation. Figure 3 shows a control pulse entering a coupler at the left and providing a control input to the SOA at one frequency. The bits circulating round the loop at a different frequency can be switched on and off by the control pulse, to synchronize or manipulate high bit rate signals or for frequency conversion.

Computing with Integrated Optics

Combining several discrete optical components into a single optical chip is more beneficial than in electronic very large-scale integration (VLSI) because optical connections require greater precision; moreover bit rates are higher because photons, unlike electrons, have no mass or charge (only spin).

Integrated Optic Microring Resonator

Figure 4 shows a microring resonator in an integrated optic chip for optical filtering, light entering at the left couples into the loop. For loop lengths that are a multiple of wavelength, light cycling the loop is in phase and resonance occurs. At resonant frequencies,



Figure 5 Integrated optic Optiwave layout for Bragg microring resonator.

light exiting the loop is out of phase with that in the linear guide, causing cancellation of the input. As frequency varies away from resonance, light passes and the device acts as a notch filter to block light at the resonant frequencies. With nonlinear Kerr material, low-level light intensity may be used to change a resonant frequency to make a switch.

Bragg Integrated Optic Microring Resonator

Performance is improved by using a Bragg microring resonator, Figure 5, which confines light in the central light colored ring by dielectric mirror reflection from Bragg gratings on either side. The refractive index is less in the ring than in the surrounding regions, in contrast to a conventional waveguide (used in Figure 4) that guides by total internal reflection. The higher reflectivity, smaller ring radius and lower refractive index – these help to reduce power loss, volume, and travel time around the ring. This increases filter selectivity, drives up peak power for enhanced nonlinearity for switching, decreases stored energy for fast response, and increases frequency range (free spectral range, *FSR*). In this case, an equivalent photonic crystal may be more expensive because it requires higher resolution lithography and greater refractive index contrast.

Photonic Crystal Mach–Zehnder Switch



Figure 6 Proposed photonic crystal Mach–Zehnder interferometer.

Recently developed photonic crystal technology allows a reduction in integrated optic chip size from centimeters to submillimeters. The 2D or 3D periodic structure of dielectric variations emulates crystals and provides dielectric mirror reflections in multiple dimensions for lossless waveguide bends, high *Q* resonators, and slowing of wave propagation to enhance effective nonlinearity of materials. Figure 6 shows a proposed 2D photonic crystal Mach–Zehnder interferometer switch in which light is split into two paths by a coupler and propagation velocity is slowed for enhancing nonlinearity by using coupled-resonator optical waveguides (CROWs), in which alternate posts of different dielectric constant remain in the waveguides to form coupled cavities.

Conclusion

Optical bit-serial computing can reduce cost and increase flow-rate for expanding telecommunication network capacity, while providing enhanced security from electromagnetic sabotage and tampering. Advances in integrated optics (microring resonators), progress in optoelectronic components (SOAs), improved materials and fabrication techniques – these technologies enable cost-effective optical bit-serial computing solutions for future telecommunication evolution.

See also

All-Optical Signal Regeneration. **Information Processing:** All-Optical Multiplexing/Demultiplexing.

Further Reading

Agrawal G (2002) *Fiber-Optic Communication Systems*. New York: Wiley.

Connelly MJ (2002) *Semiconductor Optical Amplifiers*. Boston, MA: Kluwer Academic Publishers.

Goodman JW (1996) *Introduction to Fourier Optics*, 2nd edn. New York: McGraw-Hill.

Heuring VP, Jordan HF and Pratt JP (1992) A bit serial architecture for optical computing. *Applied Optics* 31(17): 3213–3224.
Hunsperger RG (2002) *Integrated Optics*, 5th edn. New York: Springer.
Joannopoulios JD, Meade RD and Winn JN (1995) *Photonic Crystals*. Princeton, NJ: Princeton University Press.
McAulay AD (1991) *Optical Computer Architectures*. New York: Wiley.
McAulay AD (2004) Novel all-optical flip-flop using semiconductor optical amplifiers in innovating frequency-shifting inverse-threshold pairs. *Optical Engineering* 43(5): 1115–1120.
Scheuer J and Yariv A (2003) Two-dimensional optical ring resonators based on radial Bragg resonance. *Optics Letters* 28(17): 1528–1530.
Xu L, Glesk I, Baby V and Prucnal PR (2004) All-optical wavelength conversion using SOA at nearly symmetric position in a fiber-based Sagnac interferometric loop. *IEEE Photonics Technical Letters* 16(2): 539–541.
Yariv A (1997) *Optical Electronics in Modern Communications*, 5th edn. New York: Oxford University Press.

Optical Digital Image Processing

B L Shoop, United States Military Academy, West Point, NY, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Optical approaches to image processing provide a natural method by which to obtain the inherent advantages associated with optics including massive parallelism, high-speed processing, and the inherent compatibility with image formats. Early applications of optics employed analog processing techniques with the most common being the optical Fourier transform, matrix-vector processors, and correlators. Later, advances in digital signal processing (DSP), digital storage, and digital communication systems demonstrated the potential for higher resolution, improved flexibility and functionality, and increased noise immunity over analog techniques and quickly became the preferred method for accurate signal processing. Consequently, optical processing architectures, that incorporated digital processing techniques, were explored. Advances in very large-scale integration (VLSI) electronic circuitry and optoelectronic devices later enabled smart pixel technology, which integrates the programmability and processing of electronic circuitry with the two-dimensional (2D) nature of an optical architecture and made possible a particular realization of optical digital image processing. This chapter describes an application of optical digital image processing, based on smart pixel technology, called digital image halftoning.

Natural images are, by definition, continuous in intensity and color. Halftoning is the process by which a continuous-tone, gray-scale image is converted to one containing only binary output pixels. Halftoning can be thought of as an image compression technique whereby a high-resolution image is transformed to a low-resolution image containing only black-and-white pixels. The transformation from a continuous-tone, gray-scale image to one containing only binary-valued pixels is also similar, in principle, to low-resolution analog-to-digital (A/D) conversion.

An early manual approach to printing continuous-tone images, using only the presence or absence of ink, is the Mezzotint. Ludwig von Siegen (1609–1680), an amateur Dutch printmaker, first invented the mezzotint, or ‘half tone process’, in 1640. The process later came into prominence in England during the early eighteenth century. Mezzotints are produced on copper plates where the surface of the plate is roughed with a tool called the Mezzotint Rocker, shaped like a wide chisel with a curved and serrated edge. By rocking the toothed edge backwards and forwards over the plate, a rough burr is produced which holds the ink. The dark regions of an image were roughed in a random fashion, while the areas to be lightened were scraped and burnished. This process was found to be especially useful for the reproduction of paintings, due to its ability to capture the subtlest gradations of tone from rich, velvety blacks to glowing highlights. The mezzotint is, therefore, an early artistic predecessor to the modern day halftone.

Optical halftoning has been in use by commercial printers for over 100 years. Commercial halftone screens are based on a discovery made by William Henry Fox Talbot (1800–1877), in 1852. He demonstrated the feasibility of optical halftoning by photographing an image through a loosely woven fabric or ‘screen’. In the 1890s, this process came into practical use when the halftone screen, consisting of two ruled glass plates cemented together, became commercially available. Commercial halftone screens produce an effect of variably sized dots on the photographic plate that gives the illusion of a continuous tone image.

Digital image halftoning, sometimes referred to as spatial dithering, is the process of converting an electronic continuous-tone, gray-scale image to one containing only binary-valued pixels, for the purpose of displaying, printing, or storing the image. The underlying concept is to provide the viewer of the image with the illusion of viewing a continuous-tone image when, in fact, only black and white pixel values are used in the rendering. This process is particularly important in applications such as laser printing, bilevel displays, xerography, and more recently, facsimile.

There are a number of different methods by which this digital image halftoning can be accomplished, which are generally classified as either point or neighborhood processes. A point process is one which computes the output pixel value based strictly on some characteristic of the corresponding input pixel. In contrast, a neighborhood process computes a single output pixel based on a number of pixels in a neighborhood or region of the input image. Ordered dither, which is considered a point process, produces an output by comparing a single continuous-tone input value against a deterministic periodic array of threshold values. If the value of the input pixel under consideration is greater than the corresponding threshold value, the corresponding output pixel is rendered white. If the intensity is less that the threshold, it is rendered black. Dispersed-dot ordered dither is a subset of ordered dither in which the halftone dots are of a fixed size while clustered-dot ordered dither uses variable-sized dots and simulates the variable-sized dots of a printer's halftone screen in the rendering. Among the advantages of point process halftoning, in general and ordered dither halftoning specifically, are simplicity and speed of implementation. The primary disadvantage is that ordered dither produces patterns in the halftoned image, which are visually undesirable.

In contrast, halftoning using the error diffusion algorithm, first introduced by Floyd and Steinberg in 1975, employs neighborhood operations and is currently the most popular neighborhood process. In this approach to halftoning, the output pixel value is determined, not solely by the value of the input pixel and some deterministic pattern, but instead by a weighted average of values from pixels in a neighborhood surrounding the specific pixel being computed. Here, the error of the quantization process is computed and spatially distributed or diffused within a local neighborhood in order to influence future pixel quantization decisions within that neighborhood and thereby improve the overall quality of the halftoned image. In classical unidirectional error diffusion, the image is processed sequentially, proceeding from the upper-left to the lower-right. Starting in the corner of the image, the first pixel is thresholded and the quantizer error is calculated. The error is then diffused to neighboring pixels that have not yet been processed according to the scaling and interconnect defined by the error diffusion filter. The remainder of the pixels in the image are subsequently processed with each quantizer input, now being the algebraic sum of the corresponding original input pixel intensity and the weighted error from previously processed pixels. While error diffusion produces halftone images of superior quality, the unidirectional processing of the algorithm continues to introduce visual artifacts that are directly attributable to the algorithm itself.

In an effort to overcome the implementation constraints of serial processing and improve overall halftone image quality, a number of different parallel architectures have been investigated, including several based on neural network algorithms. While neural network approaches can provide distinct advantages in improved halftone image quality, they also present challenges to hardware implementations, including speed of convergence and the physical interconnect requirements. These challenges, in addition to the natural compatibility with imaging media, provide the motivation for developing optical image processing architectures for these types of applications.

The Error Diffusion Algorithm

Figure 1 shows a block diagram of the error diffusion architecture used in digital image halftoning. The input image is represented as $x_{m,n}$, $w_{m,n}$ is the impulse response of a 2D causal, unity gain error diffusion filter, and the output quantized image is described by $y_{m,n} \in \{-1, 1\}$. The quantizer $q[u_{m,n}]$ provides the one-bit thresholding functionality necessary to convert each analog input pixel to a low-resolution digital output pixel. The quantizer error $\varepsilon_{m,n}$ is computed as the difference between the output and input to the quantizer and distributed to adjacent pixels according to the weighting and interconnection specified by the error diffusion filter. The unity gain constraint ensures



Figure 1 Block diagram of recursive error diffusion architecture.

that no amplification or attenuation of the error signal occurs during the error diffusion process and preserves the average intensity of the image.

In this architecture, the error associated with the quantizer decision at spatial coordinates (m, n) is diffused within a local 2D region to influence adjacent quantization decisions. All of the state variables in this architecture are scalar values since this architecture represents a recursive algorithm in which each pixel in the image is processed sequentially. In the general case, where $w_{m,n}$ is assumed to be a 2D finite impulse response (FIR) filter with coefficients that span a region of support defined by $R_{m,n}$, the quantizer input state $u_{m,n}$ can be written as

$$u_{m,n} = x_{m,n} - \sum_{i,j \in R_{m,n}} w_{i,j} \varepsilon_{m-i,n-j} \qquad [1]$$

Here, $w_{i,j} = 0$, for all $i = j$, since the error signal is diffused spatially within the region of support $R_{m,n}$ and does not influence the pixel under consideration. In this unidirectional error diffusion, the 2D error diffusion filter is therefore noncausal. Figure 2 shows the impulse response of several popular error diffusion filters that have been used in rectangular grid architectures. Figure 2a shows the original error diffusion filter weights developed by Floyd and Steinberg. They argued that the four weights were the smallest number of weights that would produce good halftone images. Figure 2b is a filter that contains a larger region of support developed by Jarvis, Judice, and Ninke in 1976. Finally, the filter in Figure 2c, developed by Stucki, contains the same region of support with coefficients that are a multiple of 2 for digital compatibility and computational efficiency. Here, '•' represents the pixel being processed and the weights describe the local region over which the error is diffused. The normalization factors ensure that the filter coefficients sum to one and therefore meet the unity gain criterion.

To understand the effect of error diffusion and its impact on the quantizer error, it is instructive to describe the effect of error diffusion mathematically. Consider the relationship between the quantizer error $\varepsilon_{m,n} \equiv y_{m,n} - u_{m,n}$ and the overall quantization error $\hat{\varepsilon}_{m,n} \equiv y_{m,n} - x_{m,n}$ in the frequency domain. If we assume that the error is uncorrelated with the input and has statistical properties consistent with a white process, z-transform techniques can be applied to show that the feedback architecture provides the following noise-shaping characteristics:

$$H_{\mathrm{ns}}(z_1, z_2) \equiv \frac{\hat{E}(z_1, z_2)}{E(z_1, z_2)} = 1 - W(z_1, z_2) \qquad [2]$$

Here, $\hat{E}(z_1, z_2)$, $E(z_1, z_2)$, and $W(z_1, z_2)$ represent the z-transforms of $\hat{\varepsilon}_{m,n}$, $\varepsilon_{m,n}$, and $w_{m,n}$, respectively. Equation [2] shows that the noise-shaping characteristic of the error diffusion architecture is directly related to the spectral characteristics of $W(z_1, z_2)$. Appropriate selection of $W(z_1, z_2)$ can spectrally shape the quantizer noise in such a way that minimizes the effect of the low-resolution quantization process on the overall halftoning process. An error diffusion filter with low-pass spectral characteristics produces an overall noise-shaping characteristic $1 - W(z_1, z_2)$, which has the desired high-pass frequency characteristics. This noise-shaping function suppresses the quantization noise within those frequencies occupied by the image and spectrally shapes the noise to high frequencies, which are less objectionable to the human visual system. Circular symmetry is another important characteristic in the error diffusion filter since the human visual system is particularly sensitive to directional artifacts in the image.

In the following qualitative description of digital image halftoning, a 348 × 348 natural image of the Cadet Chapel at West Point was selected as the test image. This image provides a variety of important image characteristics, with regions of uniform grayscale, edges, and areas with fine detail. This image was scanned from a high-resolution black and white photograph at 150 dots per inch (dpi) and then printed using a 300 dpi laser printer.

Figure 3 shows the test image of the Cadet Chapel rendered using dispersed-dot ordered dither and results in 256 gray-levels at 300 dpi. Figure 4 shows the halftone image of the Cadet Chapel using the error diffusion algorithm and the Floyd–Steinberg filter coefficients shown in Figure 2a. The unidirectionality of the processing and the causality of the diffusion filter result in undesirable visual artifacts in the halftone image. These include directional hysteresis, which is manifested as 'snakes' running from upper-left to lower-right, and transient behavior near boundaries, which appears as 'shadows' below and to the right of sharp-intensity changes. The directional

$$\left(\tfrac{1}{16}\right)\times \begin{array}{ccc} & \bullet & 7 \\ 3 & 5 & 1 \end{array}$$

(a)

$$\left(\tfrac{1}{48}\right)\times \begin{array}{ccccc} & & \bullet & 7 & 5 \\ 3 & 5 & 7 & 5 & 3 \\ 1 & 3 & 5 & 3 & 1 \end{array}$$

(b)

$$\left(\tfrac{1}{42}\right)\times \begin{array}{ccccc} & & \bullet & 8 & 4 \\ 2 & 4 & 8 & 4 & 2 \\ 1 & 2 & 4 & 2 & 1 \end{array}$$

(c)

Figure 2 Three common error diffusion filters used in rectangular grid architectures. (The '•' represents the origin.)

hysteresis is particularly objectionable in uniform gray intensity areas such as the cloud structure in the upper-left of Figure 4. Similar artifacts are also present in images halftoned using the error diffusion algorithm and other causal diffusion kernels. The logical conclusion to draw from this limited, qualitative analysis is that if we could diffuse the error symmetrically and simultaneously process the entire image in parallel, we could reduce some of these visual artifacts and thereby improve overall halftone image quality.



Figure 3 Original gray-scale image of the Cadet Chapel rendered using dispersed-dot ordered dither.



Figure 4 Halftone image of the Cadet Chapel produced using the error diffusion algorithm and the Floyd–Steinberg weights.

The Error Diffusion Algorithm and Neural Networks

The popularity of the neural network-based approach to signal and image processing lies in the ability to minimize a particular performance metric associated with a highly nonlinear system of equations. Specifically, the problem of creating a halftone image can be cast in terms of a nonlinear quadratic optimization problem where the performance measure to be minimized is the difference between the original and the halftone images.

The Hopfield-Type Neural Network

Tank and Hopfield first proposed a mathematical description of the functionality of the neural processing network for signal processing applications. Figure 5 shows an electronic implementation of a four-neuron architecture. Here, a single neuron is comprised of both a standard and inverting amplifier and the synapses or neural interconnections are represented by the physical connections between the input and output of the amplifiers. If the input to amplifier i is connected to the output of amplifier j by a resistor with resistance $R_{i,j}$, the amplitude of the connection $T_{i,j}$ is the conductance $1/R_{i,j}$.

The dynamic behavior of an N-neuron Hopfield-type neural network can be described by the following system of N nonlinear differential equations:

$$c\frac{\mathrm{d}u_i(t)}{\mathrm{d}t} = -u_i(t) + \sum_j T_{i,j}\Im[u_j(t)] + x_i \qquad [3]$$

where $i = 1, 2, \ldots N$, $\Im[\cdot]$ is a monotonically increasing sigmoid function, x_i is an input vector containing N



Figure 5 Electronic realization of a four-neuron Hopfield-type neural network.

elements, and c is a scaling factor. In equilibrium, eqn [3] implies that

$$u_i = x_i + \sum_j T_{i,j}\Im[u_j] \qquad [4]$$

Hopfield showed that when the matrix of interconnection weights $\mathbf{T}$ is symmetric with zero diagonal elements and the high-gain limit of the sigmoid $\Im[\cdot]$ is used, the stable states of the N functions $y_i(t) = \Im[u_j]$ are the local minima of the energy function:

$$E = -\frac{1}{2}\mathbf{y}^{\mathrm{T}}\mathbf{T}\mathbf{y} - \mathbf{x}^{\mathrm{T}}\mathbf{y} \qquad [5]$$

where $\mathbf{y} \in \{-1, 1\}$ is the N-vector of quantized states. As a result, if the neural network can be shown to be stable, as the network converges the energy function is minimized. In most neural network applications, this energy function is designed to be proportional to a performance metric of interest and therefore as the network converges, the energy function and consequently the performance metric is also minimized.

The Error Diffusion Neural Network

An understanding of the operation and characteristics of the Hopfield-type neural network can be applied to the development and understanding of a 2D extension of the error diffusion algorithm. Figure 6 shows an electronic implementation of a four-neuron error diffusion-type neural network, where the individual neurons are represented as amplifiers and the synapses by the physical connections between the input and output of the amplifiers.



Figure 6 Four-neuron electronic implementation of the error diffusion neural network.

In equilibrium, the error diffusion neural network can be shown to satisfy

$$\mathbf{u} = \mathbf{W}(\mathbf{y} - \mathbf{u}) + \mathbf{x} \qquad [6]$$

Here, $\mathbf{u}$ is the state vector of neuron inputs, $\mathbf{W}$ is a matrix containing the interconnect weights, $\mathbf{x}$ is the input state vector, and $\mathbf{y}$ is the output state vector. For an $N \times N$ image, $\mathbf{W}$ is an $N^2 \times N^2$ sparse, circulant matrix derived from the original error diffusion weights $w_{m,n}$. If we define the coordinate system such that the central element of the error diffusion kernel is $(i, j) = (0, 0)$, then the matrix $\mathbf{W}$ is defined as $W(i, j) = -w[(j - i) \text{ div } N, (j - i) \text{ mod } N]$ where:

$$x \text{ div } y = \left\lfloor \frac{x}{y} \right\rfloor \text{ if } xy \geq 0 \text{ or } \left\lceil \frac{x}{y} \right\rceil \text{ if } xy < 0 \qquad [7]$$

An equivalence to the Hopfield network can therefore be described by

$$\mathbf{u} = \mathbf{A}(\mathbf{W}\mathbf{y} + \mathbf{x}) \qquad [8]$$

where $\mathbf{A} = (\mathbf{I} + \mathbf{W})^{-1}$. Effectively, the error diffusion network includes a pre-filtering of the input image $\mathbf{x}$ by the matrix $\mathbf{A}$ while still filtering the output image $\mathbf{y}$ but now with a new matrix, $\mathbf{AW}$. Recognizing that $\mathbf{AW} = \mathbf{I} - \mathbf{A}$ and adding the arbitrary constant $k = \mathbf{y}^{\mathrm{T}}\mathbf{y} + \mathbf{x}^{\mathrm{T}}\mathbf{A}\mathbf{x}$, we can write the energy function of the error diffusion neural network as

$$\hat{E}(x, y) = \mathbf{y}^{\mathrm{T}}\mathbf{A}\mathbf{y} - 2\mathbf{y}^{\mathrm{T}}\mathbf{A}\mathbf{x} + \mathbf{x}^{\mathrm{T}}\mathbf{A}\mathbf{x} \qquad [9]$$

This energy function is a quadratic function, which can be factored into

$$\hat{E}(x, y) = [\mathbf{B}\underbrace{(\mathbf{y} - \mathbf{x})}_{\text{error}}]^{\mathrm{T}}[\mathbf{B}\underbrace{(\mathbf{y} - \mathbf{x})}_{\text{error}}] \qquad [10]$$

where $\mathbf{A} = \mathbf{B}^{\mathrm{T}}\mathbf{B}$. From eqn [10] we find that as the error diffusion neural network converges and the energy function is minimized, so too is the error between the output and input images.

If the neurons update independently, the convergence of the error diffusion network is guaranteed if

$$\forall k : [\mathbf{AW}]_{k,k} \geq 0 \qquad [11]$$

We find in practice, that even in a synchronous implementation, the halftoned images converge to a solution, which results in significantly improved halftone image quality over other similar halftoning algorithms.

The Error Diffusion Filter

The purpose of the error diffusion filter is to spectrally shape the quantization noise in such a way that the quantizer error is distributed to higher spatial frequencies, which are less objectionable to the human visual system. In this application, a feedback filter for the error diffusion neural network was designed using conventional 2D filter design techniques resulting in the 7 × 7 impulse response shown in Figure 7. Figure 8 shows the same image of the Cadet Chapel halftoned using the error diffusion neural network algorithm and the 2D error diffusion filter shown in Figure 7. There is clear improvement in halftone image quality over the image produced using sequential error diffusion in Figure 4. Notice particularly the uniform distribution of pixels in the cloud formation in the upper-left of Figure 8. Also noteworthy is the improvement around the fine detail portions of the tree branches and next to the vertical edges of the chapel.

0.0003	0.0019	0.0051	0.0068	0.0051	0.0019	0.0003
0.0019	0.0103	0.0248	0.0328	0.0248	0.0103	0.0019
0.0051	0.0248	0.0583	0.0766	0.0583	0.0248	0.0051
0.0068	0.0328	0.0766	•	0.0766	0.0328	0.0068
0.0051	0.0248	0.0583	0.0766	0.0583	0.0248	0.0051
0.0019	0.0103	0.0248	0.0328	0.0248	0.0103	0.0019
0.0003	0.0019	0.0051	0.0068	0.0051	0.0019	0.0003

Figure 7 Impulse response of a 7 × 7 symmetric error diffusion filter. ('•' represents the origin.)



Figure 8 Halftone image of the Cadet Chapel using the error diffusion neural network and the 7 × 7 symmetric error diffusion filter shown in Figure 7.

Smart Pixel Technology and Optical Image Processing

The concept underlying smart pixel technology is to integrate electronic processing and individual optical devices on a common chip, to take advantage of the complexity of electronic processing circuits and the speed of optical devices. Arrays of these smart pixels then allow the advantage of parallelism that optics provides. There are a number of different approaches to smart pixel technology that differ primarily in the kind of opto-electronic devices, the type of electronic circuitry, and the method of integration of the two. Common opto-electronic devices found in smart pixels include: light-emitting diodes (LEDs); laser diodes (LDs); vertical cavity surface emitting lasers (VCSELs); multiple quantum well (MQW) modulators; liquid crystal devices (LCDs); and photodetectors (PDs). The most common types of electronic circuitry are silicon-based semiconductors such as complementary metal oxide semiconductors (CMOS) and compound semiconductors such as gallium arsinide (GaAs)-based circuitry. There are a number of different approaches to smart pixels, which generally differ in the way in which the electronic and optical devices are integrated. Monolithic integration, direct epitaxy, and hybrid integration are the three most common approaches in use today.

Smart pixel technology provides a natural methodology by which to implement optical image processing architectures. The opto-electronic devices provide a natural optical interface while the electronic circuitry provides the ability to perform either analog or digital computation. It is important to understand that any functionality that can be implemented in electronic circuitry can be integrated into a smart pixel architecture. The only limitations arise from physical space constraints imposed by the integration of the opto-electronic devices with the electronic circuitry. While smart pixels can be fabricated with digital or analog circuitry, the smart pixel architecture described subsequently uses mixed-signal circuitry.

A Smart Pixel Implementation of the Error Diffusion Neural Network

A smart pixel hardware implementation of the error diffusion neural network provides the potential to simultaneously achieve the computational complexity of electronic circuitry and the parallelism and high-speed switching of optics. The specific smart pixel architecture described here integrates MQW modulators called self electro-optic effect devices (SEEDs) with silicon CMOS

VLSI circuitry, using a hybrid integration approach called flip-chip bonding. This type of smart pixel is commonly referred to as CMOS-SEED smart pixel technology.

To provide an example of the application of smart pixel technology to digital image halftoning, a 5 × 5 CMOS-SEED smart pixel array was designed and fabricated. The CMOS circuitry was produced using a 0.5 μm silicon process and the SEED modulators were subsequently flip-chip bonded to silicon circuitry using a hybrid integration technique. The central neuron of this new smart pixel array consists of approximately 160 transistors while the complete 5 × 5 array accounts for over 3,600 transistors. A total of 50 optical input/output channels are provided in this implementation.

Figure 9 shows the circuitry associated with a single neuron of the smart pixel error diffusion neural network. All state variables in each circuit of this architecture are represented as currents. Beginning in the upper-left of the circuit and proceeding clockwise, the input optical signal incident on the SEED is continuous in intensity and represents the individual input analog pixel intensity. The input SEED at each neuron converts the optical signal to a photocurrent and subsequently, current mirrors are used to buffer and amplify the signal. The width-to-length ratio of the metal oxide semiconductor field effect transistors (MOSFETs) used in the CMOS-SEED circuitry provide current gain to amplify the photocurrent. The first circuit produces two output signals: $+I_u$ which represents the state variable $u_{m,n}$ as the input to the quantizer and $-I_e$ which represents the state variable $-\varepsilon_{m,n}$ as the input to the feedback differencing node. The function of the quantizer is to provide a smooth, continuous threshold functionality for the neuron that produces the output signal I_{out}, corresponding to the output state variable $y_{m,n}$. This second electronic circuit is called a modified wide-range transconductance amplifier and produces a hyperbolic tangent sigmoidal function when operated in the sub-threshold regime. The third circuit takes as its input I_{out}, produces a replica of the original signal, and drives


VS1
SEED
Ipd
VDD
2.5 M11
2.5 M13
2.5 M15
2.5 M17
2.5 M19
2.5 M21
2.5 M23
0.5 M1
0.5 M3
0.5 M5
0.5 M7
0.44 M9
VS2
SEED
M26 4
M10 0.12
Ipd
Iu
I2
M2 1.5
I2
I1
M4 1.5
Vth
I1
Iout=I2-I1
I2
M12 1
M14 1
M16 1
M18 1
M20 1
M24 1
Iu
M24 1
Vb
Mb 1
M6 0.15
M8 0.15
Iu
Ie(out)
Ie(in)
VDD
2.5 M115
0.38 M113
2.5 M111
2.5 M109
2.5 M105
2.5 M107
2.5 M117
2.5 M119
2.5 M121
M116 1
M114 0.12
M112 1
M110 1
M106 1
M108 1
M118 1
M118 1
M120 1
VDD
0.5 M101
0.5 M103
Iout1A
Iout1B
Iout1C
Iout1D
Error voltage to other weights
Voffset weight 1
M104 0.15
M105 0.15

Figure 9 Circuit diagram of a single neuron and a single error weight of the 5 × 5 error diffusion neural network based on a CMOS-SEED-type smart pixel architecture. (Reprinted with permission from Shoop BL, *Photonic Analog-to-Digital Conversion*, Springer Series in Optical Sciences, Vol. 81 [1], Fig. 8.6, p. 222. Copyright 2001, Springer-Verlag GmbH & Co. KG.)

the output optical SEED. In this case, the output optical signal is a binary quantity represented as the presence or absence of light. When the SEED is forward-biased, light is generated through electroluminescence. The last circuit at the bottom of the schematic implements a portion of the error weighting and distribution function of the error diffusion filter. The individual weights are implemented by scaling the width-to-length ratio of the MOSFETs to achieve the desired weighting coefficients. The neuron-to-neuron interconnections are accomplished using the four metalization layers of the 0.5 μm silicon CMOS process. In this design, the error diffusion filter was limited to a 5 × 5 region of support because of the physical constraints of the circuitry necessary to implement the complete error diffusion neural network in silicon circuitry. The impulse response of the 5 × 5 filter used in this particular smart pixel architecture is shown in Figure 10. The error weighting circuitry at the bottom of Figure 9 represents only the largest weight (0.1124) with interconnects to its four local neighbors ($I_{\mathrm{outA}} - I_{\mathrm{outD}}$).

0.0023	0.0185	0.0758	0.0185	0.0023
0.0185	0.0254	0.1124	0.0254	0.0185
0.0758	0.1124	●	0.1124	0.0758
0.0185	0.0254	0.1124	0.0254	0.0185
0.0023	0.0185	0.0758	0.0185	0.0023

Figure 10 Error diffusion filter coefficients used in the 5 × 5 CMOS-SEED error diffusion architecture. ('•' represents the origin.)

Figure 11 shows a photomicrograph of a 5 × 5 error diffusion neural network, which was fabricated using CMOS-SEED smart pixels. Figure 12 shows a photomicrograph of a single neuron of the 5 × 5 CMOS-SEED neural network. The rectangular features are the MQW modulators while the silicon circuits are visible between and beneath the modulators. The MQW modulators are approximately 70 μm × 30 μm and have optical windows, which are 18 μm × 18 μm.

Simulations of this network predict individual neuron switching speeds of less than 1 μs, which corresponds to network convergence speeds capable of providing real-time digital image halftoning. Individual component functionality and dynamic operation of the full 5 × 5 neural array were both experimentally characterized. Figure 13 shows CCD images of the operational 5 × 5 CMOS-SEED smart pixel array. The white spots show SEED MQW modulators emitting light. Figure 13a shows the fully functioning array while Figure 13b shows the 5 × 5 CMOS-SEED neural array under 50% gray-scale input. Here 50% of the SEED modulators are shown to be in the *on*-state demonstrating correct operation of the network and the halftoning architecture.

Both the simulations and the experimental results demonstrate that this approach to a smart pixel implementation of the error diffusion neural network provides sufficient accuracy for the digital halftoning application. The individual neuron switching speeds also demonstrate the capability for this smart pixel hardware implementation to provide real-time halftoning of video images.



Figure 11 Photomicrograph of a smart pixel implementation of a 5 × 5 CMOS-SEED error diffusion neural network for digital image halftoning. (Reprinted with permission from Shoop BL, *Photonic Analog-to-Digital Conversion*, Springer Series in Optical Sciences, Vol. 81 [1], Fig. 8.5, p. 221. Copyright 2001, Springer-Verlag GmbH & Co. KG.)



Figure 12 Photomicrograph of a single neuron of the 5 × 5 error diffusion neural network. (Reprinted with permission from Shoop BL, *Photonic Analog-to-Digital Conversion*, Springer Series in Optical Sciences, Vol. 81 [1], Fig. 8.4, p. 220. Copyright 2001, Springer-Verlag GmbH & Co. KG.)



(a) (b)

Figure 13 CCD images of the 5 × 5 CMOS-SEED array. (a) Fully-operational array, and (b) under 50% gray scale illumination. (Reprinted with permission from Shoop BL, *Photonic Analog-to-Digital Conversion*, Springer Series in Optical Sciences, Vol. 81 [1], Figs. 8.19 and 8.20, p. 236. Copyright 2001, Springer-Verlag GmbH & Co. KG.)

Image Processing Extensions

Other image processing functionality is also possible by extending the fundamental concepts of 2D, symmetric error diffusion to other promising image processing applications. One important application includes color halftoning while other extensions include edge enhancement and feature extraction. In the basic error diffusion neural network, the error diffusion filter was specifically designed to produce visually pleasing halftoned images. Care was taken to ensure that the frequency response of the filter was circularly symmetric and that the cutoff frequency was chosen in such a way as to preserve image content. An analysis of the error diffusion neural network shows that the frequency response of this filter directly shapes the frequency spectrum of the output halftone image and therefore directly controls halftone image content. Other filter designs with different spectral responses can provide other image processing features such as edge enhancement, which could lead to feature extraction and automatic target recognition applications.

See also

Detection: Smart Pixel Arrays. **Information Processing:** Optical Neural Networks. **Optical Processing Systems**.

Further Reading

Dudgeon DE and Mersereau RM (1984) *Multidimensional Digital Signal Processing*. Englewood Cliffs, NJ: Prentice-Hall.
Lau DL and Arce GR (2001) *Modern Digital Halftoning*. New York: Marcel Dekker.
Lim JS (1990) *Two-Dimensional Signal and Image Processing*. Englewood Cliffs, NJ: Prentice Hall.
Mead CA (1989) *Analog VLSI and Neural Systems*. New York: Addison-Wesley.
Poon T-C and Banerjee PP (2001) *Contemporary Optical Image Processing with Matlab*. New York: Elsevier.
Russ JC (1998) *The Image Processing Handbook*. Boca Raton, FL: CRC Press.
Shoop BL (2001) *Photonic Analog-to-Digital Conversion*. Springer Series in Applied Optics, vol. 81. Berlin: Springer-Verlag.
Shoop BL, Sayles AH and Litynski DM (2002) New devices for optoelectronics: smart pixels. In: De Cusatis (ed.) *Fiber Optic Data Communication: Technological Trends and Advances*, pp. 352–421. San Diego, CA: Academic Press.
Ulichney R (1987) *Digital Halftoning*. Cambridge, MA: The MIT Press.
Wax C (1990) *The Mezzotint: History and Technique*. New York: Harry N. Abrahms, Inc.

Optical Neural Networks

H J Caulfield, Fisk University, Nashville, TN, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

An artificial neural network (ANN) is a nonlinear signal processing system based on the neural processes observed in animals. Usually they have multiple inputs and often multiple outputs also. Conventionally, each input sends its signal to many neurons, and each neuron receives signals from many inputs. The neuron forms an intermediate sum of weighted inputs and transforms that sum, according to some nonlinearity, to form an output signal. Often the output signal from one neuron is used as the input signal for another in feed forward, feedback, or mixed mode complex neural networks.

ANNs are of value in helping us understand how biological neural networks perform and in a variety of technical applications, most of which involve pattern association. An auto-associative neural network, that associates patterns with themselves, can have useful noise cleanup or pattern completion properties. A hetero-associative neural network is often used in pattern recognition to associate input patterns with preselected class labels.

Neural Networks – Natural and Artificial

The most primitive one-celled organisms have no nerve cells, but they do exhibit various chemical means for interacting with their environments, within their own cells, and among individuals of the same or different types. As organisms increased in size, a common chemical environment became impractical, and nerves arose as a means for long-distance communication within larger organisms. One thing seen in evolution is that widespread useful adaptations are often modified but seldom discarded. Thus, it should not be surprising to find that chemical interactions play a major role in the most complex thing we know of – the human brain. Chemicals play a huge role in making us who we are, setting our moods, and so forth. Realizing this, in the late twentieth century, psychiatrists started to make serious progress in treating mental diseases through the use of chemistry.

There are a variety of processes that we use as humans, but the primary means is neural. Only some animals and no plants have neurons, but soon after neurons evolved, they began to concentrate in special regions of the body that developed into primitive brains. Not only were there many neurons, but also they were densely and complexly interconnected to form neural networks.

Neural networks did not replace chemical interactions, they used and supplemented them. Chemical communication across the synaptic cleft dominates communication between networks, but the neural networks also control chemical production and distribution within the brain, and those chemicals change the behavior of the neurons that cause their secretion. The functioning of real brains is incredibly complex, possibly irreducibly complex in terms of current mathematics and logic.

These things are noted to avoid a confusion that is distressingly common. Technologists produce simplified ANNs and then try to interpret the behavior of brains in those terms. Quite often, ANNs yield useful insight into brain behavior but seldom offer a detailed account of them. Reality is far more complex than any ANN. Current mathematics provides no means to describe continuous sets of events, each of which both causes and is caused by the others.

ANNs themselves have grown much more complicated as well. Starting out as simple, feed-forward, single-layer systems, they rapidly became bidirectional and even multilayered as well. Higher-order neural networks processed the input signals before inserting them into the neural network. Pulse coupled neural networks (PCNNs) arose that more closely modeled the pulsations in real brains. Learning was broken into learning with instruction, following example, and self-organizing, the latter leading to self organized maps and adaptive resonance theory, and many related subjects. These are but crude pointers to the wealth and variety of concepts now part of the ANN field.

The history of ANNs is both complicated and somewhat sordid. This is not the occasion to retrace the unpleasant things various members of this community have done to others in their quests for stature in the field. One result of that history is a dramatically up-and-down pattern of interest in and support for ANNs. The first boom followed the development of a powerful single-layer neural network called the Perceptron by its inventor Rosenblatt. Perceptrons were biologically motivated, fast, and reasonably effective; so interest in the new field of ANNs was high. That interest was destroyed by a book on the field arguing that Perceptrons were only linear discriminants and most interesting problems are not linearly discriminable. Ironically, the same argument has been made about optical Fourier correlators, and it is true there as well. But optical processing folk largely ignored the problem and kept working on it. Sociologists of science might enjoy asking why reactions differed so much in the two fields. Funding and interest collapsed and the field went into hibernation.

It was widely recognized that multilayer ANNs would comprise nonlinear discriminants, but training them presented a real problem. The simple rewards and punishment of weights depending on performance was easy when each output signal came from a known set of weighted signals that could be rewarded or punished jointly, according to how the output differed from the sought-after output. With a multilayer perceptron, credit assignment of inner layers is no longer simple. It was not until Werbos invented ‘backward error propagation’ that a solution to this problem was available and the field started to boom again. Also key to the second boom were enormously popular articles by Hopfield on rather simple auto- and hetero-associative neural networks. Basically, those networks are almost never used, but they were of great value in restarting the field. In terms of research and applications, we are still in that second boom, that began during the 1980s.

> An ANN is a signal processor comprised of a multiplicity of nodes which receive one or more input signals and generate one or more output signals in a nonlinear fashion wherein those nodes are connected with one or two way signaling channels.

Note also that biological inspiration is no longer a part of the definition. Most ANNs used for association are only vaguely related to their biological counterparts.

Optical Processors

Optics is well-suited for massive parallel interconnections, so it seems logical to explore optical ANNs. The first question to address is “Why bother to use optical processors at all?” as electronic digital computers seem to have everything:

- Between the writing of this article (on an electronic computer) and its publication, the speed of electronic computers will almost double and they will become even cheaper and faster.
- They can have arbitrary dynamic range and accuracy.
- Massively improved algorithms also improve their speed. For instance, the wonderful fast Fourier transform (FFT) that opticists have used to simulate optics for decades has been replaced by an even faster fastest Fourier transform in the West (FFTW). And for wavelets, the fast wavelet transform (FWT) is even faster.

Optical processors, on the other hand, have severely limited analog accuracy and few analog algotectures or archirithms. They are specialized systems (equivalent in electronics, not to computers but to application specific integrated circuits (ASICs)). They are usually larger and clumsier than electronic systems and always cost more.

There are several reasons why optics may still have a role in some computations. First, many things on which we wish to perform computations are inherently optical. If we can do the computations optically before detection, we can avoid some time and energy and sensitivity penalties inflicted, if we first detect the signals then process them electronically, and then (sometimes) convert them back to optics. Examples include spectroscopy and optical communication.

Second, pure optics is pure quantum mechanics. Input of data and setup of the apparatus is experiment preparation. Readout of data is classical measurement. Nature does the rest free of charge. There is a unitary transformation from input to output that requires no human intervention and is, in fact, destroyed by human intervention. Those intermediate (virtual) computations require no energy and no time, beyond the time taken for light to propagate through the system. Speed and power consumption are limited only by the input and output. This applies for everything from Fourier optics to digital optics to logic gates. Thus, optics can have speed and power consumption advantages over electronics.

Third, if quantum computers involving entanglement ever emerge, they may well be optical. Such computers would be used for nondeterministic solutions of hard problems. That is, they would explore all possible paths at once and see which one does best. This is something we can already do electronically or optically for maze running (using classical, not quantum entanglement) means.

Fourth, most optical processors are analog, which is sometimes superior to digital. In those cases, we would still have to choose between analog optics and analog electronics, of course.

So, optical processing (like all other processing) is a niche market. But some of the niches may be quite large and important. It is not a universal solution, but neither is digital electronics.

The Major Branches of Optical Processing and Their Corresponding Neural Networks

Every branch of optical processing leads to its own special purpose optical neural networks, so those branches become a good place to start an article such as this one.

Optical Linear Algebra

Many neural network paradigms use linear algebra followed by a point-by-point nonlinearity in each of multiple stages. The linear operation is a matrix–vector multiplication, a matrix–matrix multiplication, or even a matrix–tensor multiplication. In any case, the key operations are multiplication and addition – operations very amenable to performance with analog optics. With effort, it is possible to combine simple electronics with analog optics operating on non-negative signals (the amount of light emitted from a source, the fraction of light passing through a modulator, etc.) to expand to real or even complex numbers. With even more effort, we can use multiple analog non-negative signals to encrypt a digital signal, allowing digital optical processors. Almost all optical neural networks using linear algebra use only real numbers. In most of these, the real number is encoded as a positive number and a negative number. Data are read in parallel using spatial light modulators (SLMs), source arrays, acousto-optic modulators, etc. They are operated upon by other SLMs, acousto-optic systems, and so forth. Finally, they are detected by individual detectors or detector arrays. The required nonlinearities are then done electronically. It is a theory that holds for all linear algebraic processes up to computational complexity $O(N^4)$ that they can be performed with temporal complexity $O(N^0)$ if the extra dimensions of complexity are absorbed in space, up to $O(N^2)$ through 2D arraying and in fanin/fanout, the ability of multiple beams of light to be operated upon in parallel by the same physical modulator – this has the same complexity as the 2D array of modulators, namely $O(N^2)$. Thus, we can invert a matrix, an order $O(N^4)$ for an $N \times N$ matrix, $O(N^0)$ in time, that is, independently of the size of N, as long as that matrix is accommodated by the apparatus. This offers a speed electronics cannot match.

Most of the optical neural networks of the mid-1980s had optical vector–matrix multipliers at their heart. Most were a few layers of feed forward systems, but by the 1990s feedback had been incorporated as well. These are typically N inputs connected to N outputs through an $N \times N$ matrix, with N varying from 100 to 1000. With diffuser interconnection and a pair of SLMs, it is possible to connect an $N \times N$ input with an $N \times N$ output using N^4 arbitrary weights, but that requires integrating over a time up to N^2 intervals. Most of the N^4-dimensional matrices can be approximated well by fewer than N^4 terms using singular value decomposition (SVD) and (as this version of the interconnection uses outer products), that reduces the number of integration times considerably in most cases. We have shown, for instance, that recognizing M target images can be accomplished well with only M terms in the SVD.

Coherent Optical Fourier Transformation

It took opticists several years, during the early 1960s, to realize that if Fourier mathematics was useful in describing optics, optics might be useful in performing Fourier mathematics. The first applications of optical Fourier transforms were in image filtering and particularly in pattern recognition. Such processors are attractive not only for their speed but also for their ability to locate the recognized pattern in 1D, 2D, or even 3D. It was soon obvious that a Fourier optical correlator was a special case of a single layer perceptron. Of course, it inherits the weaknesses of a single layer perceptron too. Soon, workers had added feedback to create a winner-takes-all type of auto-associative optical neural network, a system that associated images with themselves. This proved useful in restoring partial or noisy images. It was not until 2003 that we learned how to make powerful hetero-associative networks with Fourier optical systems. This creates a nonlinear discrimination system that maintains the target location and generalizes well from a few samples of multiple classes to classify new data quite accurately.

Imaging

Imaging is the central act of optics and might seem to be of little value in optical processing. But multiple imaging (with lenslets, self-focusing fibers, holograms, and the like) has been the basis of numerous optical neural networks. Multiple imaging is a nonrandom way of distributing information from one plane to the next. Diffusers have also been used to produce fully interconnected optical neural networks. If each broad image point contains the whole image (something easily arranged with a diffuse hologram), then we have an auto-associative memory. Different such auto-associative networks can be superimposed in a single hologram. Then feedback after nonlinear image filtering can be used to make a general auto-associative memory.

Even deliberately poor imaging has been used. A blurred or out-of-focus image can accomplish the lateral signal spreading needed to facilitate a PCNN. These networks are substantially more like real brain networks than those discussed so far. It starts with a 2D array of integrate-and-fire units. The firing rate of each depends only in the incident power (how long integration to the thresholding firing takes). But if the fired signal is spread to its neighbors, the firing of a neighbor can hasten any unit's firing. This causes firings to synchronize and results in 'autowaves' of firing patterns moving across the 2D plane. Thus an incident 2D image is converted to a 3D signal – the two spatial dimensions and time. This results, for all but some very simple cases, in a chaotic signal occupying a strange attractor. It is interesting but not very revealing in itself. But suppose we 'integrate out' either the two spatial dimensions or the time dimension. If we integrate out the spatial dimensions, we are left with a time signal. Its strange attractors are remarkably useful in pattern recognition, because they are more syntactic than statistical (in pattern recognition terms). They describe the shape as similar, independently of the size, rotation, perspective, or even shading of the pattern! If we integrate out the time dimension, we restore the original image – almost. In fact, we can use this aspect of PCNNs for optimum blind segmentation of images. The autowaves can be made to 'leave tracks' so they can be reversed, which allows them to solve maze problems nondeterministically, because they can take all the paths. When the first wave exits, we simply retrace it to find the shortest path through the maze – a prototypical nondeterministic polynomial operation.

Holograms

Holograms are the most general, complex, and flexible means of light manipulation so far invented. Naturally, they have many applications in optical neural networks. One such application is the interconnection of each of an $N \times N$ array of inputs to each of an $N \times N$ array of outputs with its own unique connection strength (weight in the language of neural networks). The practical limit seems to be around $N = 1000$, yielding 10^{12} weights, roughly the same number as in the human brain! The brain, however, is not fully interconnected, so this produces an entirely different type of neural network. The resulting network would have fixed weights, but it could perform a variety of useful operations and be both forward and backward connected.

Special on-axis holograms, called diffractive optical elements, can be mass manufactured very effectively and inexpensively to perform tasks such as multiple imaging.

Photorefractive Neural Networks

A very complex thing happens when a pattern of fringes, such as those that form an interference pattern for hologram recording, strike materials such as lithium niobate, strontium barium niobate, gallium arsenide, and many others that fall into this category of 'photorefractive' materials. Of course, 'photo' refers to light and 'refractive' refers to the speed of light in a material – the speed of light in a vacuum divided by the index of refraction. These materials are photoconductive, so the light releases charge carriers in what would otherwise be an electrical insulator. The periodic charge pattern sets up a periodic space charge within the material. But the material is also electro-optic, that is, its index of refraction changes with applied electric field, thus generating a periodic index of refraction grating in the material. Finally, that index of refraction pattern (a phase hologram) diffracts the incoming light. Usually, but not always, a steady-state situation is reached after time that depends on the material and the photon density, although chaos can arise under some conditions. This makes for a dynamic hologram, one that can change or adapt over time as the input pattern changes. Once a satisfactory photorefractive hologram is formed, it can be stabilized (fixed) if desired. Most optical neural network uses envision a dynamic situation with changing interconnections.

What has not been discussed above is that the index of refraction varies with the light's electric field vector cubed, so photorefractives provide a convenient way to accomplish such nonlinear operations as winner-takes-all.

Sometimes, we can record holograms with photorefractives that cannot be recorded by conventional holograms in conventional materials. To explain this, a hologram is a transducer between two optical wavefronts – usually called the reference and object beams. If the reference beam is incident on the hologram, it is (fully or partially) converted into the object beam. If the precisely reversed (phase conjugated) reference beam is incident on it, the precisely reversed (phase conjugated) object beam is derived from it. Likewise, the object wavefront (or its phase conjugate) produces the reference wavefront (or its phase conjugate). The hologram is made by recording the interference pattern between the two wavefronts: the reference and object beams. The ability of two wavefronts to form a temporally stable interference pattern at some point in space is called the mutual coherence of those wavefronts. Usually, both wavefronts are derived from the same laser beam to make achieving high mutual coherence possible. And, of course, both beams must be present to form an interference pattern. In some cases of photorefractive holograms, all of those conditions can be violated. The two wavefronts can derive from two sources that are different in wavelength, polarization, etc., and need not be simultaneously present. This phenomenon, called mutual phase conjugation, converts each wavefront into the phase conjugate of the other, but for effects due to any differences in wavelength and polarization. This allows new freedoms that have been exploited in optical neural networks.

Photorefractive materials also tend to be piezoelectric. It has been found that up to about 20 totally independent reflective holograms can be stored with different applied electric field in lithium niobate. Changing electric fields so changes the fringe spacings and indices of refraction, that only one of those holograms has any appreciable diffraction efficiency at any one electric field value. The result is an electrically selectable interconnection pattern. The same hologram can contain the information needed for many neural networks or multiple layers of fewer of them. There is no need, in general, to have more than an input layer, an output layer, and two intermediate or hidden layers.

Others have used photorefractive material to implement learning in neural networks. In biological neural networks the synaptic strengths (the weights between neurons) continue to adapt. With photorefractive holograms, we can achieve this in an optical ANN.

As previously discussed, a key development in the history of ANNs was a way to train multilayer neural networks and thus accomplish nonlinear discrimination. The first, and still most popular, way to do this is called backward error propagation. Several groups have been implemented in photorefractive optical neural networks.

Conclusions

Essentially every major type of neural network has been implemented optically. Every major tool of optics has found its way into these optical neural networks. Yet, it remains the case that almost every neural network used for practical applications is electronic. The mere existence proof of a use for optical neural networks may be what the field needs to move forward from the demonstration stage to the application stage. The tools exist and there are niches where optics seems more appropriate than electronics. Hopefully, the next review of the field will include a number of commercial successes. Nothing spurs science better than the funds that follow successful applications.

List of Units and Nomenclature

Adaptive resonance theory (ART)	Another self-organized neural net categorizer that works by mutual adjustment between bottom-up and top-down neural connections.
Computational complexity	The measure of how the number of required calculations scales with the problem size, usually denoted by N. The scaling is represented by the Big O form of (N), where $f(n)$ shows how it scales asymptotically (large N). Problems that scale as $O(N^P)$ are said to be of polynomial complexity. Unfortunately, some of the most important problems have exponential complexity.

Fanin/Fanout	Beams of light (unlike beams of electrons or holes) do not interfere with one another, so many of them can be modulated by the same physical elements quite independently, so long as they can be identified. This is usually done by sending the different beams in at different angles, giving rise to the words fanin and fanout, as suggested by the drawing below: 
Self organized maps (Kohonen networks)	A means of self-organization of inputs into (normally 2D) maps wherein every concept falls into some category and the categories themselves develop out of application of the Kohonen's algorithm and user-selected parameters applied to the given data.
Singular value decomposition (SVD)	Any matrix can be broken into (decomposed) a weighted sum of simpler, rank-one matrices. The simplest such decomposition (in the sense of fewest number of terms) is the SVD. The weights are the singular values and are indicators of the importance of that term in the decomposition.
Spatial light modulator (SLM)	A 1D or 2D array of elements under electronic or optical control that change some property of the light incident on them. Usually, it is the index of refraction in some direction that is changed. That change can be used to modulate the amplitude, the polarization, or the phase of the light.

See also

Fourier Optics. **Holography, Techniques:** Overview. **Nonlinear Optics, Basics:** Photorefraction. **Optical Communication Systems:** Local Area Networks. **Optical Processing Systems**.

Further Reading

Abu-Mostafa YS and Psaltis D (1987) Optical neural computers. *Scientific American* 256(3): 88–95.

Anderson DZ and Erie MC (1987) Resonator memories and optical novelty filters. *Optical Engineering* 26: 434–444.

Brady D, Psaltis D and Wagner K (1988) Adaptive optical networks using photorefractive crystals. *Applied Optics* 27: 1752–1759.

Caulfield HJ, Kinser J and Rogers SJ (1987) Optical neural networks. *Proc. IEEE* 77: 1573–1583.

Chavel P, Lalanne P and Taboury J (1989) Optical inner-product implementation of neural network models. *Applied Optics* 28: 377–385.

Collins SA, Ahalt SC, Krishnamurthy AK and Stewart DF (1993) Optical implementation and applications of closest-vector selection in neural networks. *Applied Optics* 32: 1297–1303.

Farhat NH, Psaltis D, Prata A and Paek E (1985) Optical implementation of the Hopfield model. *Applied Optics* 24: 1469–1475.

Galstyan T, Frauel Y, Pauliat G, Villing A and Roosen G (1997) Topological map from a photorefractive self-organizing neural network. *Optics Communications* 135: 179–188.

Goodman JW, Dias AR and Woody JM (1978) Fully parallel, high-speed incoherent optical method for performing discrete Fourier transforms. *Optics Letters* 2: 1–3.

Johnson JL (1994) Pulse-coupled neural nets: Translation, rotation, scale, distortion, and intensity signal invariance for images. *Applied Optics* 33: 6239–6253.

Jutamulia S (1994) *Selected Papers on Optical Neural Networks*. Bellingham: SPIE Press.

Kinser JM, Caulfield HJ and Shamir J (1988) Design for a massive all-optical bidirectional associative memory: the big BAM. *Applied Optics* 27: 3442–3444.

Neifeld MA and Psaltis D (1993) Optical implementations of radial basis classifiers. *Applied Optics* 32: 1370–1379.

Owechko Y, Dunning GJ, Marom E and Soffer BH (1987) Holographic associative memory with nonlinearities in the correlation domain. *Applied Optics* 26: 1900–1910.

Paek EG and Psaltis D (1987) Optical associative memory using Fourier-transform holograms. *Optical Engineering* 26: 428–433.

Psaltis D and Farhat NH (1985) Optical information processing based on associative-memory model of neural nets with thresholding and feedback. *Optics Letters* 10: 98–100.

Soffer BH, Dunning GJ, Owechko Y and Marom E (1986) Associative holographic memory with feedback using phase-conjugate mirrors. *Optics Letters* 11(2): 118–120.

Yu FTS (1993) Optical neural networks – architecture, design and models. In: Wolf E (ed.) *Progress in Optics*, II, pp. 63–144. Amsterdam: North-Holland.

INSTRUMENTATION

Contents

Astronomical Instrumentation
Ellipsometry
Photometry
Scatterometry
Spectrometers
Telescopes

Astronomical Instrumentation

J Allington-Smith, University of Durham, Durham, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

This article describes the requirements placed on astronomical instruments and the methods used to achieve them, making reference to generic techniques described elsewhere in this encyclopedia. It is limited in scope to electromagnetic radiation with wavelengths from the atmospheric cutoff in the ultraviolet (0.3 μm) to the point in the near-infrared where the technology changes radically (5 μm), taking in the transition from uncooled to cooled instruments at ~1.7 μm. Thus, it excludes the extreme UV and X-ray regimes, where standard optical techniques become ineffective (e.g., requiring grazing incidence optics) and all mid-infrared, sub-mm, THz, and radio-frequency instruments. Terrestrial telescopes are the main focus but space-borne telescopes are subject to similar design considerations, except that the diffraction limit of the optics may be achieved at short wavelengths. Adaptive optics (AO), of increasing importance in astronomy and almost essential for the next generation of extremely large telescopes (ELTs), is covered elsewhere in this encyclopedia.

Astronomical Data

The purpose of astronomical instruments is to measure the following properties of photons arriving on or near to the Earth and brought to a focus by an astronomical telescope:

(i) direction of arrival;
(ii) energy;
(iii) polarization state; and
(iv) time of arrival.

In practice, these properties cannot be measured simultaneously, requiring the following generic classes of instrument:

- *Imagers* to measure (i) and, if equipped with ultra-low-noise detectors, (iv);
- *Spectrographs* to measure (ii), although some can be configured to do a good job on (i) as well. *Integral field spectrographs* can measure (i) and (ii) simultaneously; and
- *Polarimeters* for (iii) plus (i) and *spectropolarimeters for* (iii) plus (ii).

In principle, energy-resolving detectors, such as arrays of superconducting tunnel-junction devices (STJs) can replace (i), (ii), and (iv).

These must interface to the telescope which provides a focal surface with an image scale which is approximately constant over the field. Currently, almost all telescopes are based on the Cassegrain or Ritchy-Chretien reflecting configurations, comprising a large curved primary mirror (M1) which defines the collecting aperture (diameter D_T) and a curved secondary mirror (M2). This feeds the Cassegrain focus via a hole in M1 in line with the central obstruction caused by M2, or the Nasmyth focus if a tertiary (usually plane) mirror is added to direct light from M2 along the elevation axis to a location in which the gravity vector changes only in rotation about the optical axis. For the Cassegrain focus, the full range of change in the gravity vector is experienced as the telescope tracks objects during long exposures or slews between targets. It is also possible to dispense with M2 and mount the

Table 1 Optical interfaces to representative types of telescope and achievable angular resolution

Aperture diameter D_T (m)	*Primary focus*			*Final focus*			*Diffraction limit $2.44\lambda/D_T$(mas)*	
	F/#	*Image scale (μm/″)*	*FOV (′)*	*F/#*	*Image scale (μm/″)*	*FOV (′)*	*$\lambda = 0.5\ \mu$m*	*$\lambda = 5.0\ \mu$m*
2.4^{i}	2.3			24	279	25	101	1007
4.2^{ii}	2.8	60	40	11	221	15	60	600
8.0^{iii}	1.8	(70)	(45)	16	621	10	32	315
30^{iv}	1–1.5	~180	~20	15–19	~2500	~20	8.4	84
100^{v}	~1.4			~6.5	~3000	~10	2.5	25
			For enclosed telescopes				500–1500	
All	Obtainable angular resolution for terrestrial telescopes		Free-atmosphere seeing at good site		Best		250	160
					Median		420	270
			With adaptive optics (approx)				50–200	*Diff. limit*[a]

[a] The diffraction limit listed in the column above for $\lambda = 5.0\ \mu$m applies.

Exemplars: (i) Hubble Space Telescope; (ii) Herschel Telescope, La Palma; (iii) Gemini telescopes, Hawaii/Chile; (iv) CELT/GSMT (USA); (v) OWL (Europe).

instrument directly at the focus of M1 (prime focus), although this imposes severe restrictions on the mass and size of the instrument. An alternative mounting for instruments is via optical fibers. The input, with any fore-optics required to couple the telescope beam into the fiber, is mounted at the appropriate focus while the output, possibly several tens of meters distant, is mounted where the instrument is not subjected to variations in the gravity vector.

The useful field of view (FOV) of the telescope is determined by how rapidly the image quality degrades with radius in the field; restrictions on the size of the Cassegrain hole and the space set aside for the star trackers required for accurate guiding and auxiliary optics involved in target acquisition, AO, etc.

Typical telescope parameters are shown in Table 1, of which the last two entries are speculative examples of ELTs. The table also lists the diffraction limit of the telescopes and the limits imposed by seeing, with and without the effects of the telescope structure and enclosure, and approximate limits for performance with AO which approaches the diffraction limit in the infrared.

Instrument Requirements

Efficiency

Almost all astronomical observations are of very faint objects or require very high signal-to-noise (SNR) to extract the desired subtle information. The former, for example, might reveal the initial phase of galaxy or star formation, while the latter could reveal the mix of elements in the big bang or uncover changes in fundamental constants on cosmological timescales ($\sim 10^{10}$ years). The term 'efficiency' has several components:

(i) Throughput of the optical system, including the efficiency of the optical components (lenses or mirrors), dispersers, filters, and also detectors and also includes losses due to transmission/reflection, diffraction, scattering, and vignetting by internal obstructions;
(ii) Noise from all sources: the detector, including time-independent (read-noise) and time-dependent (dark-current) components; thermal emission from the instrument, telescope, enclosure and sky; straylight (see above), and electronic interference;
(iii) Efficient use of the instrument and telescope to maximize the fraction of the time spent accumulating useful photons instead of, say, calibrating; reconfiguring the instrument; or acquiring targets;
(iv) Parallelizing the observations so that the same instrument records data from many objects at the same time. This is discussed further below.

Angular Resolution

The required angular resolution is summarized in Table 2 for key features in galaxies. The resolutions currently achievable with AO systems (with severe restrictions on sky coverage pending routine availability of laser beacons), or without, are shown in bold. Finer resolution is possible using interferometric techniques, but is limited to a handful of bright stars.

Table 2 Typical requirements for angular resolution and single-object field of view

Target	*Distance*[a]	*Active nucleus*		*Star cluster (10 pc)*	*Visible extent*
		Central engine (10 AU)	*Dynamical core (0.5 pc)*		
Milky Way	8 kpc	1 mas	10″	4′	
Local group galaxy (M31)	800 kpc	0.01 mas	100 mas	3″	100″
Distant galaxy	>1 Gpc	10^{-5} mas	0.1 mas	2 mas	0.5–2″
Cluster of galaxies	>1 Gpc				3′
Cosmological structure	>1 Gpc				~1°

[a] 1 pc = 3.1×10^{16} m.

Field of View and Multiplexing

The FOV of an individual observation must be sufficient to cover the angular extent of the object with the minimum number of separate pointings of the telescope. As well as minimizing the total observation time, this reduces photometric errors caused by changes in the ambient conditions (e.g., flexure, thermal effects, and changes in the sky background). (Photometry is the measurement of the flux density received from an astronomical object, usually done with the aid of an imager employing filters with standardized broad passbands. Spectrophotometry is the same but in the much narrower passbands obtained by dispersing the light.) The last column of Table 2 indicates the required size of FOV. It is also highly desirable to observe many objects simultaneously since most studies require large statistically homogenous samples. The precise requirement depends on the surface number density of potential targets and the sampling strategy adopted to create the sample. Cosmological studies of the large-scale distribution of galaxies and clusters emphasize the size of the field ($\geq 0.5°$), since the targets may be sparsely sampled, while studies of clustered objects (galaxies or stars) aim to maximize the surface density of targets (≤ 1000 arcmin^{-2}) within a modest FOV ($\sim 5'$).

Spectral Resolution

The required energy resolution is specified in terms of the spectral resolving power, $R \equiv \lambda/\delta\lambda$, where $\delta\lambda$ is the resolution in wavelength defined usually in terms of the Rayleigh criterion. One of the main data products required in astrophysics is the velocity along the line of sight (radial velocity) obtained through measurement of the wavelength of a known spectral feature (emission or absorption line). This may be determined to an accuracy of:

$$\delta v = \frac{Qc}{R} \qquad [1]$$

where Q is the fraction of the width of the spectral resolution element, $\delta\lambda$, to which the centroid can be determined. This is limited by either the SNR of the observation of the line via $Q \approx 1/\mathrm{SNR}$, or by the stability of the spectrograph via:

$$Q = \frac{\Delta x}{\chi}\left(\frac{\mathrm{d}\chi}{\mathrm{d}x}\right) \qquad [2]$$

where χ is the angular width of the slit measured on the sky and $\delta\chi/\mathrm{d}x$ is the image scale at the detector. Δx is the amount of uncorrectable flexure in units of the detector pixel size. This is the part of the motion of the centroid of the line which is not susceptible to modeling with the aid of frequent wavelength calibration exposures. Typically, $\Delta x \approx 0.2$ pixels is achievable (roughly 3 μm at the detector or 10 μm at the slit for an 8 m telescope) implying $Q \approx 1/30$ for a typical $(\mathrm{d}\chi/\mathrm{d}x) = 0.1–0.2''$/pixel and $\chi = 0.5–1''$. Table 3 gives typical requirement for R and the value of Q required to achieve it, given the spectral resolution obtainable for different types of current spectrograph. Extrasolar planet studies require very high stability.

Some spectral observations require very accurate measurements of the shape of the spectral features to infer the kinematics of ensembles of objects which are individually not resolvable (e.g., stars in distant galaxies, gas in blackhole accretion disks). Other applications require accurate measurements of the relative flux of various spectral features within the same spectrum (e.g., to reveal abundances of elements or different types of star).

Optical Principles

Imaging

The simplest type of imager consists of a detector, comprising a 2D array of light-sensitive pixels (Table 4) placed at a telescope focal surface without any intervening optics except for the filters required for photometry. Although maximizing throughput, this arrangement removes flexibility in changing the image scale since the physical size of pixels (typically 15–25 μm) is fixed. Thus the Gemini telescopes

Table 3 Typical requirements for spectral resolution and stability

Target	*δv or required data product*	*Required $\lambda/\delta\lambda$*	*Spectral regime*	*Available R*	*Stability required = 1/Q*	*Simultaneous wavelength range*
Cosmological parameters	1000 km/s (line centroid)	300	*Low dispersion*	300–3000	1	≳1 octave
Galaxies						
Intra-cluster	100 km/s (line centroid)	3000			1–10	100 nm
Element abundance	Ratio of line fluxes	1000–3000				1 octave
Stellar orbits	10 km/s (line shapes)	3×10^4	*Medium*	$1–3 \times 10^4$	(1)	10 nm
Individual stars	1 km/s (line centroid)	3×10^5			10–30	10 nm
Extrasolar planets	<1 m/s (line centroid)	$>3 \times 10^8$	*High*	$\sim 10^5$	>3000	<1 nm

Table 4 Detectors in current use for astronomy

Wavelength (μm)	*Material/ type*	*Pixel size (μm)*	*Format*		*Read noise (e-/pix)*	*Dark current (e-/pix/hr)*	*QE range (%)*
			Single	*Mosaic*			
		Typical	*State-of-the-art*				
0.3–1.0	CCD	10–20	4k × 4k	12k × 8k	2	Negligible	10–90[a]
	CMOS	5–10	4k × 4k		5–30		
1–2.5 +	HgCdTe	15–20					
0.6–5	InSb	20–30	2k × 2k	4k × 4k	10	0.01–0.1	70–90

[a] Quantum efficiency varies strongly over quoted wavelength range.

($D_T = 8$ m) provides an uncorrected image scale of 25–40 mas/pixel at its sole F/16 focus. Although well-suited to high-resolution observations with AO, this is inappropriate for most observations of faint galaxies where 100–200 mas/pixel is required. This arrangement also provides limited facilities for defining the wavelength range of the observations since there is no intermediate focal surface at which to place narrowband filters, whose performance is sensitive to field angle and are, therefore, best placed at an image conjugate. There is also no image of the telescope pupil at which to place a cold stop to reject the external and instrumental thermal radiation which is the dominant noise source at $\lambda > 1.5$ μm.

The alternative is to use a focal-reducer consisting of a collimator and camera. The auxiliary components (filters, cold-stops, Fabry–Perot etalons, etc.) then have an additional image and pupil conjugate available to them and the image scale may be chosen by varying the ratio of the camera and collimator focal lengths. The extra complexity of optics inevitably reduces throughput but, through the use of modern optical materials, coatings such as Sol–Gel and the avoidance of internally obstructed reflective optics, losses may be restricted to 10–20% except at wavelength shorter than ~0.35 μm. An imaging focal reducer is a special case of the generic spectrograph described in the next section.

Spectroscopy

Basic principles

Astronomical spectrographs generally employ plane diffraction gratings. The interference between adjacent ray paths as they propagate through the medium is illustrated in Figure 1. From this, we obtain the grating equation:

$$m\rho\lambda = n_1 \sin\alpha + n_2 \sin\beta \equiv G \qquad [3]$$

where α and β are the angles of incidence and diffraction respectively, $\rho = 1/a$ is the ruling density, λ is the wavelength, and m is the spectral order. The refractive indices in which the incident and diffracted rays propagate are n_1 and n_2 respectively.

The layout of a generic spectrograph employing a plane diffraction grating in a focal reducer arrangement is shown in Figure 2. The spectrograph re-images the slit onto the detector via a collimator and camera. The disperser is placed in the collimated beam close to a conjugate of the telescope pupil.

A field lens placed near the focus is often incorporated in the collimator for this purpose.

The geometrical factor, G, defined in the equation is constrained by the basic angle of the spectrograph:

$$\psi = \alpha - \beta \qquad [4]$$

which is the (normally fixed) angle between the optical axes of the collimator and camera. $\psi = n\pi$, corresponds to the Littrow configuration (for integer n).



Figure 1 Derivation of the grating equation by consideration of the optical path difference between neighboring ray paths AB and A′B′.

Considering the case of a diffraction grating in vacuo, differentiation of the grating equation with respect to the diffracted angle yields the angular dispersion:

$$\frac{d\lambda}{d\beta} = \frac{\cos\beta}{m\rho} \qquad [5]$$

from which the linear dispersion is obtained by considering the projection of dβ on the detector, dx:

$$\frac{d\lambda}{dx} = \frac{d\lambda}{d\beta}\frac{d\beta}{dx} = \frac{\cos\beta}{m\rho f_2} \qquad [6]$$

where f_2 is the focal length of the camera (see Figure 2).

In the diffraction-limited case, where the slit is arbitrarily narrow, the resolving power is given simply by the total number of rulings multiplied by the spectral order:

$$R^* = m\rho W \qquad [7]$$

where w is the length of the disperser as defined below. But in astronomy, it is usually determined by the width of the image of the slit, s, projected on the detector, s'. By conservation of Etendue:

$$s' = s\frac{F_2}{F_1} \qquad [8]$$

where F_1 and F_2 are the collimator and camera focal ratios, respectively. The spectral resolution of the spectrograph is simply the width of this expressed in



Figure 2 Generic spectrograph employing a plane diffraction grating. Note that according to the sign convention implicit in Figure 1, the diffraction angle, β, is negative in this configuration.

wavelength units:

$$\delta\lambda = \left(\frac{\mathrm{d}\lambda}{\mathrm{d}x}\right)s' = \frac{\cos\beta}{m\rho f_2} s \frac{F_2}{F_1} = \frac{sD_1\cos\beta}{m\rho D_2 f_1} \qquad [9]$$

The length of the intersection between the collimated beam and the plane of the grating (not necessarily the actual physical length of the grating) is

$$W = \frac{D_2}{\cos\beta} = \frac{D_1}{\cos\alpha} \qquad [10]$$

Using this to eliminate cos β, the spectral resolution becomes

$$\delta\lambda = \frac{s}{m\rho F_1 W} \qquad [11]$$

and the resolving power is

$$R \equiv \frac{\lambda}{\delta\lambda} = \frac{m\rho\lambda F_1 W}{s} = G\frac{F_1 W}{s} \qquad [12]$$

where G is the quantity defined in eqn [3]. Note that R is now independent of the details of the camera. This expression is useful for the laboratory since it is expressed in terms of the parameters of the experimental apparatus; but, for astronomy, it is more useful to express the resolving power in terms of the angular slit width, χ, and the telescope aperture diameter, D_T, via:

$$s = \chi f_T = \chi F_T D_T = \chi F_1 D_T \qquad [13]$$

since the collimator and telescope focal ratios are the same if the spectrograph is directly beam-fed from the telescope. Note that even if the telescope focal surface is re-imaged onto the slit, the expression for the resolving power still holds due to the conservation of Etendue in the re-imaging optics. Thus the resolving power is

$$R = \frac{m\rho\lambda W}{\chi D_T} = \frac{GW}{\chi D_T} \qquad [14]$$

Note that the resolving power obtained with a nonzero slit width is always less than the theoretical maximum, $R \leq R_*$, for wavelengths:

$$\lambda < \lambda_* = \chi D_T \qquad [15]$$

Thus, long-wavelength applications may approach the theoretical limit; in which case they are said to be diffraction-limited. If so, the resolving power is independent of the slit width, simplifying the interface to different telescopes. For a nondiffraction-limited spectrograph, the resolving power obtained depends on the aperture of the telescope to which it is fitted.

Optical configuration

The non-Littrow configuration shown in Figure 2 introduces anamorphism into the recorded spectra such that a monochromatic image of the slit mask is compressed in the dispersion direction by a factor:

$$A = \frac{D_2}{D_1} = \frac{\cos\beta}{\cos\alpha} \qquad [16]$$

which varies, depending on the choice of angles required to place the chosen wavelength on the detector using eqns [3] and [4].

Practical configurations that maximize R, do so by increasing $W = D_1/\cos\alpha$. This implies maximizing cos β, since $\psi = \alpha - \beta$, which results in $A > 1$. This is known as the grating-to-camera configuration since the grating normal points more towards the camera than to the collimator. The grating-to-collimator configuration may also be used at the penalty of lower R but does permit a smaller camera. Thus the camera aperture must be oversized in the dispersion direction since $D_2 > D_1$. The Littrow configuration is rarely used with reflective designs when large FOV is required because of internal vignetting and consequent light loss. However, it can be used effectively with transmissive dispersers.

If the disperser is replaced by a plane mirror (or if the disperser is removed in a transmissive system), the system acts as a versatile imager, with $A = 1$. This also facilitates target acquisition which requires that the telescope attitude be adjusted until the targets are aligned with apertures cut in an opaque mask placed at the input of the spectrograph. These apertures (normally slits) are usually oversized in the direction perpendicular to the dispersion to allow the spectrum of the sky to be recorded directly adjacent to that of the target to permit accurate subtraction of the background.

The slit width is chosen by trading off the desire to maximize the amount of light entering the instrument from the target (but not so much as to admit excessive background light) and the need to maximize spectral resolving power, R, by reducing the slit width, χ, according to eqn [14].

Since $|G| \leq 2$, the maximum attainable resolving power, according to eqn [14], is determined chiefly by the telescope aperture and angular slitwidth. The only important parameter of the spectrograph is the illuminated grating length, W. Therefore, maintaining the same resolving power as the telescope aperture increases, requires W to increase in direct proportion. Because of limits placed on the geometry by the need to avoid obstructions, etc., this means that both the collimated beam diameter and the size of the disperser must increase. This is one of the major problems in devising instruments for ELTs. Current instruments on 8 m telescopes feature collimated beam diameters of $D_1 \approx 150$ mm. For ELTs, the implied sizes are 0.5–2 m, requiring huge optics, accurately co-aligned mosaics of dispersing elements, and enormous support structures to provide the required stability. A simple calculation indicates that the ruling stylus for a classically ruled diffraction grating would have to cover a thousand kilometers without significant wear unless the disperser was made from smaller pieces.

Choice of dispersing element

Astronomical spectrographs mostly use surface-relief diffraction (SL) gratings. These are ruled with groove densities $50 < \rho < 3000\ \mathrm{mm}^{-1}$.

Blazing diffraction gratings. The intensity of the multibeam interference pattern from N rulings of finite width is given by

$$I = \left(\frac{\sin^2 N\phi}{\sin^2 \phi}\right)\left(\frac{\sin^2 \theta}{\theta^2}\right) \qquad [17]$$

where 2ϕ is the phase difference between the center of adjacent rulings and θ is the phase difference between the center and edge of a single ruling. To be useful for astronomy, the peak in this pattern, determined by the second term, must coincide with a useful order, such as $m = 1$, rather than zero order. This can be done by introducing a phase shift into the second term, which represents the diffraction of a single ruling, such that:

$$\theta = \frac{\pi \cos \gamma}{\rho\lambda}(\sin i - \sin r) \qquad [18]$$

where the groove angle, γ, is the angle by which the facets are tilted with respect to the plane of the grating. With the aid of Figure 3, it can be seen that $i = \alpha - \gamma$ and $r = \gamma - \beta$ so that the maximum efficiency, which occurs when $\theta = 0$, corresponds to $i = r$, which is equivalent to simple reflection from the facets, and $\alpha + \beta = 2\gamma$.

Thus, through this process of blazing, the grating eqn [3], at the blaze wavelength, λ_B, becomes:

$$\rho m \lambda_B = 2 \sin \gamma \cos \frac{\psi}{2} \qquad [19]$$

where ψ, is given by eqn [4] using the identity: $\sin x + \sin y \equiv 2 \sin\left(\frac{x+y}{2}\right) \cos\left(\frac{x+y}{2}\right)$. Thus, the resolving power at blaze is obtained from eqns [10], [14], and [19] as:



Figure 3 Blazing of ruled diffraction grating.

$$R_B = \frac{2D_1}{\chi D_T} \frac{\sin\gamma \cos(\psi/2)}{\cos(\gamma + \psi/2)} \qquad [20]$$

Use of grisms. An alternative configuration uses transmission gratings. The advantage here is that the collimator and camera can share the same optical axis in a straight-through configuration with unit anamorphism, $A = 1$, which does not require oversizing of the camera. The same phase-shift can be applied as before by making the facets into prisms with the required groove angle. However, this would only allow zero-order to propagate undeviated into the camera so an additional prism is required with vertex angle $\phi = \gamma$ to allow first-order light to pass undeviated into the camera. This composite of blazed transmission grating and prism is called a grism (Figure 4).

The grating equation (eqn [3]) is modified for a grism in the blaze condition to $m\rho\lambda_B = (n-1)\sin\phi$ since $\alpha = -\beta = \phi$ and $n_1 \equiv n, n_2 = 1$. Noting that $\psi = 0$, the resolving power at blaze is then:

$$R_B = \frac{D_1}{\chi D_T}(n-1)\tan \phi \qquad [21]$$

where n is the refractive index of the prism and grating material. Due to problems such as groove shadowing (illustrated for reflection gratings in Figure 3), these lack efficiency when $\phi \gtrsim 30°$ restricting their use to low-resolution spectroscopy.

Use of volume phase holographic gratings. A newer alternative to surface-relief (SR) dispersers are volume phase holographic (VPH) gratings in which the interference condition is provided by a variation of refractive index of a material such as dichromated gelatine, n_g, which depends harmonically on position inside the grating material as:

$$n_g(x,z) = \bar{n}_g + \Delta n_g \cos[2\pi\rho_g(x\sin\gamma + z\cos\gamma)] \qquad [22]$$

where ρ_g is the density of the lines of constant n_g and $\bar{n}_g$ and Δn_g are the mean refractive index and its modulation amplitude, respectively (Figure 5). These are described by the same grating (eqn [3]), as before leading to an identical expression for the resolving power at blaze, where $m\rho\lambda_B = 2\sin\alpha$, to that of a blazed plane diffraction grating in the Littrow configuration (eqn [20]):

$$R_B = \frac{D_1}{\chi D_T} 2\tan\alpha \qquad [23]$$



Figure 4 Typical configuration of a grism. The prism vertex and groove angles are chosen for maximum efficiency on the assumption that refractive indices, $n_G = n_R = n$ and $n' = 1$. The blaze condition occurs when $\delta = 0$. In this configuration, $\phi = \gamma = \alpha$.

Unlike SR gratings, the blaze condition of VPH gratings may be varied by changing the basic angle of the spectrograph, $\psi = 2(\gamma + \alpha)$, although this is often mechanically inconvenient. They may also be sandwiched between prisms to provide the necessary incident and diffraction angles while retaining the advantage of a straight-through configuration, to form an analogue of a grism, sometimes termed a vrism. Unlike grisms, these are not constrained by groove shadowing and so can be efficient at relatively high dispersion, subject to the constraint imposed by the size of the device.

Use of echelle gratings. Another option to increase the resolving power is to use a coarse grating in high order via the use of an echelle format. The resolving power in the near-Littrow configuration in which it is usually operated, is given by eqn [20] with $\psi = 0$.

$$R_B = \frac{D_1}{\chi D_T} 2\tan\gamma \qquad [24]$$

where γ is the groove angle.



Figure 5 Various configurations of volume phase holographic gratings. The blaze condition is when $\beta = \alpha$. The inset shows how the blaze condition may be altered by changing the basic angle of the spectrograph.



Figure 6 (a) Basic layout of an Echelle grating used in a near-Littrow configuration. (b) Illustrative cross-dispersed spectrogram showing a simplified layout on the detector. The numbers 10–16 label the different spectral orders. The numbers labeling the vertical axis are the wavelength (nm) at the lowest end of each complete order. Other wavelengths are labeled for clarity. For simplicity the orders are shown evenly spaced in cross-dispersion.

In the configuration shown in Figure 6, R is maximized by increasing W. This also means that $G = m\rho\lambda$ is large. In order to avoid excessively high ruling densities, the grating may be used in high orders. However, this presents the problem of order overlap since the wavelength in order m occurs in the same place as wavelength $\lambda_n = (m/n)\lambda_m$ in order n. Limiting the observation to a single order via the use of order-sorting filters is one solution while another is to use cross-dispersion via a chain of prisms or a grating with dispersion perpendicular to that of the echelle to separate the orders out. This option severely curtails the use of such spectral formats in multi-object spectroscopy.

Increasing resolving power using immersed gratings. All the methods of using diffraction gratings discussed so far are subject to various geometric constraints which ultimately limit the maximum obtainable resolving power by placing limits on W (e.g., in eqn [14]). These may be partly overcome by optically coupling the dispersers to immersing prisms. This can lead to a doubling of the resolving power in some cases.

Use of prisms. The final method of dispersion is to use a prism. This has the advantage that, since it does not work by multibeam interference, the light is not split into separate orders which removes the problem of order-overlap and improves efficiency. However, it does not produce the high spectral resolution required for some applications and the dependency of dispersion on λ is often markedly nonlinear.

From a consideration of Fermat's principle, it can be shown that the resolving power of a prism is:

$$R = \frac{\lambda t}{\chi D_{\mathrm{T}}}\left(\frac{\mathrm{d}n}{\mathrm{d}\lambda}\right) \qquad [25]$$

where t is the baselength of the prism. Using modern materials, $R \lesssim 300$ may be obtained. The problem of the nonlinearity in dispersion can be alleviated by the use of composite materials with opposite signs of dispersion.

Multiobject spectroscopy (MOS)

As discussed above, there is great value in increasing the multiplex gain. This can be done in two ways:

(i) *Increasing the number of apertures in the slit mask (Multislits).* This requires that each slit is carefully cut in the mask because, although the telescope attitude (translation and rotation) may be adjusted to suit one aperture, errors in the relative positions of slits cannot be compensated since the image scale is fixed. Each aperture produces a spectrum on the detector and the mask designer must ensure that the targets and their matching slits are chosen to avoid overlaps between spectra and orders. This has the effect of limiting the surface density of targets which can be addressed in one observation. Passband filters can be used to limit the wavelength range and reduce the overlap problem. This option requires superior optics able to accommodate both a wide FOV and large disperser.

(ii) *Using optical fibers (Multifibers).* A number of fibers may be deployed at the telescope focus to direct light from the various targets to a remote spectrograph whose input focus consists of one or more continuous pseudoslits. These are made up of the fiber outputs arranged in a line. The continuous nature of the slit means that spectral overlap is avoided without restricting the surface density of addressable targets; although there is a limit imposed by the distance of closest approach of the fibers. The method of deploying the fiber inputs may be a plugplate consisting of pre-cut holes into which encapsulated fibers are manually plugged, or a pick-and-place robot which serially positions the fiber inputs at the correct location on a magnetized field plate. The latter is highly versatile but mechanically complex with a significant configuration time that may erode the actual on-target integration time.

The two systems have contrasting capabilities (Figure 7). The multislit approach provides generally better SNR since the light feeds into the spectrograph directly, but is compromised in terms of addressable surface density of targets, by the need to avoid spectral overlap and in FOV by the difficulty of the wide-field optics. A current example of this type of instrument, GMOS, is shown in Figure 8 and described in Table 5. The multifiber approach is limited in SNR by modal noise in the fibers and attendant calibration uncertainties and the lack of contiguous estimates of the sky background. However, it is easier to adapt to large fields since the spectrograph field can be much smaller than the field over which the fiber inputs are distributed. In summary, multislit systems are best for narrow-but-deep surveys while the multifiber systems excels at wide-but-shallow surveys. Fiber-fed instruments may further prove their worth in ELTs where technical problems may require that these bulky instruments are mounted off the telescope (see below for further discussion).

Of paramount importance in MOS is the quality of the background subtraction as discussed above. Traditionally, this requires slits which sample the sky background directly adjacent to the object. An alternative is nod-and-shuffle (va-et-vient) in which nearby blank regions are observed alternately with the main field using the same slit mask by moving the telescope (the nod). In the case of CCDs, the photo-generated charge from the interleaved exposures is stored temporarily on the detector by moving it to an unilluminated portion of the device (the shuffle). After many repeats on a timescale less than that of variations in the sky background (a few minutes), the accumulated charge is read out, incurring the read-noise penalty only once. Although requiring an effective doubling of the exposure time and an



Figure 7 Illustration of the difference between the multislit and multifiber approaches to multi-object spectroscopy.


Gemini instrument
support structure
Fore optic
support
structure
On-instrument
wavefront
sensor
Collimator
Filter wheels
IFU/mask
cassettes
GMOS
without enclosure and
electronics cabinets
Grating turret
& indexer unit
Camera
Main optical
support structure
shutter
CCD unit Dewar

Figure 8 The Gemini Multiobject Spectrograph (GMOS). One of two built for the two Gemini 8-m telescopes by a UK–Canadian consortium. It includes an integral field capability provided by a fiber-lenslet module built by the University of Durham. The optical configuration is the same as shown in Figure 2. It is shown mounted on an instrument support unit which includes a mirror to direct light from the telescope into different instruments. The light path is shown by the red dashed line. The slit masks are cut by a Nd-YAG laser in 3-ply carbon fiber sheets. See Table 5 for the specification.

Table 5 Main characteristics of the Gemini multiobject spectrographs

Image scale	72 mas/pixel	FOV	$5.5' \times 5.5'$
Detector	CCD with 13.5 μm pixels Format: 3 × (4608 × 2048)	Slit/mask configuration	$\leq$few × 100 slits of width $\geq 0.2''$
Wavelength range	Total: 0.4–1.0 μm Simultaneous: ≤ 1 octave	Integral field unit	$1500 \times 0.2''$ samples in 50 sq.″
Spectral resolving power	$R \leq 5000$ with $0.5''$ slit	Dispersion options	3 gratings + mirror for imaging

increase in the size of the detector, this technique allows the length of the slits to be reduced since no contiguous sky sample is required, thereby greatly increasing the attainable multiplex gain if the number density of potential targets is sufficiently high.

Integral field spectroscopy (IFS)

IFS provides a spectrum of each spatial sample simultaneously within a contiguous FOV. Other approaches provide the same combination of imaging and spectroscopy but require a series of nonsimultaneous observations. Examples include imaging through a number of narrow passband filters with different effective wavelength and spectroscopy with a single slit which is stepped across the object. Other such techniques are Fabry–Perot, Fourier-transform and Hadamard spectroscopy. Since the temporal variation of the sky background is a major limitation in astronomy of faint objects, IFS is the preferred technique for terrestrial observations of faint objects, but nonsimultaneous techniques are preferable in certain niche areas, and relatively more important in space where the sky background is reduced.

The main techniques (Figure 9) are as follows:

(i) *Lenslets*. The field is subdivided by placing an array of lenslets at the telescope focus (or its conjugate following re-imaging fore-optics) to form a corresponding array of micropupils. These are re-imaged on the detector by a focal



Figure 9 Main techniques of integral field spectroscopy.

reducer using a conventional disperser. The spectra are, therefore, arranged in the same pattern as that of the lenslet array. Spectral overlap is reduced by angling the dispersion direction away from the symmetry axes of the lenslet array and by the fact that the pupil images are smaller than the aperture of the corresponding lenslet.

(ii) *Fibers + lenslets*. The field is subdivided as in (i) but the pupil images are relayed to a remote spectrograph using optical fibers which reformat the field into linear pseudoslits. This avoids the problem of overlap, allowing a greater length of spectrum than in (i), but is more complex since the arrays of fibers and lenslets must be precisely co-aligned and are subject to modal noise in the fibers.

(iii) *Image slicer*. The field is subdivided in only one dimension by a stack of thin slicing mirrors placed at a conjugate of the telescope focus (Figure 10). Each mirror is angled so as to direct light to its own pupil mirror which re-images the field to form part of a linear pseudoslit. Thus the slices into which the image is divided are rearranged end-to-end to form a continuous slit at the spectrograph input. Unlike the other techniques, this retains spatial information along the length of each slice. This is dispersed by conventional means via a focal-reducer. An additional optic is often required at the image of each slice at the slit to reimage the micropupil images produced by the slicing mirrors onto a common pupil inside the spectrograph. In principle this is the most efficient of the three methods since the one-dimensional slicing produces fewer diffraction losses in the spectrograph than the two-dimensional division used by the others, and minimizes the fraction of the detector surface which must be left unilluminated in order to avoid cross-talk between noncontiguous parts of the field. However the micromirrors are difficult to make since they require diamond-turning or grinding in metal or glass with a very fine surface finish (typically with RMS ~ 1 nm for the optical and ~ 10 nm in the infrared). This sort of system is, however, well-matched to cold temperatures, since the optical surfaces and mounts may be fabricated from the same material (e.g., Al) or from materials with similar thermal properties.

The data are processed into a datacube whose dimensions are given by the two spatial coordinates, x, y, plus wavelength. The datacube may be sliced up in ways analogous to tomography to understand the physical process operating in the object.

Spectropolarimetry and Polarimetry

Spectropolarimetry and polarimetry are analogous to spectroscopy and imaging, where the polarization state of the light is measured instead of the total intensity. Like IFS, spectropolarimetry is a photon-starved (i.e., limited in SNR by photon noise) area which benefits from the large aperture of current and projected telescopes.

The Stokes parameters of interest are I, Q, and U. V is generally very small for astronomical objects.



Figure 10 Principle of the advanced image slicer. Only three slices are shown here. Real devices have many more, e.g., the IFU for the *Gemini Near-Infrared Spectrograph* has 21 to provide a 5″ × 3″ field with 0.15″ × 0.15″ sampling. Reproduced from Content R (1997) A new design for integral field spectroscopy with 8 m telescopes. *Proceedings SPIE* 2871: 1295–1305.

From these, the degree and azimuthal angle of linear polarization are obtained as:

$$\pi_L = \left(\frac{Q^2 + U^2}{I^2}\right) \qquad \psi = \frac{1}{2}\arctan\left(\frac{U}{Q}\right) \qquad [26]$$

The Stokes parameters may be estimated using a modified spectrograph with a rotatable achromatic half-wave retarder, characterized by the angle of rotation about the optical axis, θ, placed before the instrument and a polarizing beamsplitter which separates the incident beam into orthogonal polarization states (Figure 11). The two states are recorded simultaneously on different regions of the detector. The separation is achieved usually through the angular divergence produced by a Wollaston prism placed before the disperser or through the linear offset produced by a calcite block placed before the slit. The intensity as a function of the waveplate rotation angle, $S(\theta)$, is recorded for each wavelength and position in the spectrum or image. The Stokes parameters for each sample are then given by

$$\begin{aligned}\frac{Q}{I} &= \frac{S(0) - S(\pi/2)}{S(0) + S(\pi/2)} \\ &= \left\langle \frac{A_1 - \omega_{AB}B_1}{A_1 + \omega_{AB}B_1}, \frac{A_2 - \omega_{AB}B_2}{A_2 + \omega_{AB}B_2} \right\rangle \\ \frac{U}{I} &= \frac{S(\pi/4) - S(3\pi/4)}{S(\pi/4) + S(3\pi/4)} \\ &= \left\langle \frac{C_1 - \omega_{CD}D_1}{C_1 + \omega_{CD}D_1}, \frac{C_2 - \omega_{CD}D_2}{C_2 + \omega_{CD}D_2} \right\rangle \\ I &= S(0) + S(\pi/2) \\ &= \left\langle \frac{A_1 + \omega_{AB}B_1}{\eta_{A1}}, \frac{A_2 + \omega_{AB}B_2}{\eta_{A2}} \right\rangle \text{ etc.}\end{aligned} \qquad [27]$$

where A and B are the signals (functions of position and/or λ) recorded with the waveplate at $\theta = 0$ and $\theta = \pi/2$ and the subscripts 1 and 2 refer to the two polarization states produced by the beamsplitter.



Figure 11 Schematic layout of spectropolarimeter using a polarizing beamsplitter in the collimated beam (e.g., a Wollaston prism producing *e*- and *o*-states) to produce separate spectra for orthogonal polarization states on the detector. Alternative configurations in which the two polarizations have a linear offset (e.g., a calcite block) may be used in which case the beamsplitter is placed before the slit.

Likewise, C and D are a pair of observations taken with $\theta = \pi/4$ and $\theta = 3\pi/4$. The angled brackets indicate a suitable method of averaging the quantities inside. The factors ω_{AB} and ω_{CD} are estimated as

$$\omega_{AB} = \sqrt{\frac{A_1 A_2}{B_1 B_2}} \qquad \omega_{CD} = \sqrt{\frac{C_1 C_2}{D_1 D_2}} \qquad [28]$$

and η_{A1} is a single calibration factor for polarization state 1 of observation A, etc. One problem is instrumental polarization caused by oblique reflections from telescope mirrors upstream of the polarizing waveplate, such as the fold mirror external to GMOS (see Figure 8). This must be carefully accounted for by taking observations of stars with accurately known polarization. The dispersing element is also likely to be very strongly dependent on the polarization state of the incident light with widely different efficiency as a function of wavelength. Although this effect is cancelled out using the procedure described above, it introduces a heavy toll in terms of SNR reduction.

Technology Issues

Use of Optical Fibers in Astronomy

As discussed above, optical fibers are commonly used in astronomy for coupling spectrographs to wide, sparsely sampled FOVs in the case of MOS, or small contiguously sampled FOVs in the case of IFS. For both applications, the most important characteristics are:

(i) *Throughput*. Near-perfect transmission is required for wavelength intervals of ~1 octave within the overall range of 0.3–5 μm. For MOS, a prime focus fiber feed to an off-telescope spectrograph implies fiber runs of several tens of meters for 8 m telescopes, increasing proportionally for ELTs. For IFS, runs of only ~1 m are required for self-contained par-focal IFUs. For $\lambda < 2.5$ μm, fused silica is a suitable material, although it is not currently possible to go below ~0.35 μm, depending on fiber length. Newer techniques and materials may improve the situation. For $\lambda > 2.5$ μm, alternative materials are required, such as ZrF4 and, at longer wavelengths, chalcogenide glasses, but these are much more expensive and difficult to use than fused silica.

(ii) *Conservation of Etendue*. Fibers suffer from focal ratio degradation, a form of modal diffusion, which results in a speeding up of the output beam with respect to the input. Viewed as an increase in entropy, it results in a loss of information. In practice, this implies either reduced throughput, as the fiber output is vignetted by fixed-size spectrograph optics, or a loss in spectral resolution if the spectrograph is oversized to account for the faster beam from the fibers. This effect may be severe at the slow focal ratios pr oduced by many telescopes ($F > 10$) but is relatively small for fast beams ($F < 5$). Thus, its effect may be mitigated by speeding up the input beam by attaching lenslets directly to the fibers, either individually (for MOS) or in a close-packed array (for IFS). If the spectrograph operates in both fiber- and beam-fed modes (e.g., Figure 8), it is also necessary to use lenslets at the slit to convert the beam back to the original speed.

(iii) *Efficient coupling to the telescope*. This requires that the fibers are relatively thick to match the physical size of the sampling at the telescope focus which is typically $\chi_s = 0.1''$ for IFS and $\chi_s = 2''$ for MOS. By conservation of Etendue, the physical size of the fiber aperture is

$$d_f = \chi_s D_T F_f \qquad [29]$$

where F_f is the focal ratio of the light entering the fiber and D_T is the diameter of the telescope aperture. Using the above values with $F_\mathrm{f} = 4$, as required to maintain Etendue, implies $15 < d_\mathrm{f} < 300\ \mu\mathrm{m}$ for an 8 m or $60 < d_\mathrm{f} < 1200\ \mu\mathrm{m}$ for a 30 m telescope. Except at the lower end, this implies the use of multimode (step-index) fibers. However, the need in IFS to oversize the fibers to account for manufacturing errors and current requirements of $\chi_\mathrm{s} \geq 0.2''$ to produce sufficient SNR in a single spatial sample gives a practical limit of $d_\mathrm{f} > 50\ \mu\mathrm{m}$ which is in the multimode regime.

Recently, the use of photonic crystal fibers in astronomy has been investigated. These, together with other improvements in material technology may improve the performance of optical fibers, which will be of special relevance to ELTs where, for example, there will be a need to couple very fast beams into fibers.

Cooling for the Near-Infrared

As shown in Figure 12, it is necessary to cool instruments for use in the infrared. This is to prevent thermal emission from the instrument becoming the dominant noise source. The minimum requirement is to place a cold stop at a conjugate of the telescope pupil. However, much of the rest of the instrument requires cooling because of the nonzero emissivity of the optics. The telescope also requires careful design. For example, the Gemini telescopes are optimized for the NIR by undersizing M2 so that the only stray light entering the final focal surface is from the cold night sky.

Irrespective of the thermal background and wavelength, all detectors (see Table 4), require cooling to reduce internally generated noise to acceptable levels. For the CCDs used in the optical, the cryogen is liquid nitrogen, but for the infrared, cooling with liquid helium is required.

Structure

As discussed above, the necessity for instruments to scale in size with the telescope aperture cannot be achieved by simply devising a rigid structure, since the required materials are generally not affordable (instruments on 8 m telescopes cost roughly €/$ 5–15 M, including labor). Furthermore, the stability also depends critically on the mounting of the individual optical elements, where the choice of material is constrained by the need for compliance with the optical materials. The solution adopted for GMOS was to design the collimator and camera mounting so that variations in the gravity vector induce a translation in each component orthogonal to the optical axis without inducing tilts or defocus. Therefore, the only effect of instability is a translation of the image of the slit on the detector. Since the slit area is rigidly attached to the telescope interface, the image of a celestial object does not move with respect



Figure 12 Illustration of the need for cooling in NIR instruments. This is modeled for the case of a spectrograph on an 8 m telescope with $0.2'' \times 0.2''$ sampling with both throughput and total emissivity of 50%. The curves indicate the cumulative thermal background for wavelengths shortward of that shown on the scale. For comparison, a typical dark current is shown for NIR detectors (see Table 4). Also shown is the background from the night sky for the case of the *H*-band, for two values of spectral resolution, *R*. The mean sky background level is shown for both values of *R*. For $R = 3000$, the continuum level found between the strong, narrow OH-lines which make up most of the signal is also shown. To observe in the *H*-band, cooling to −40 °C is required for high spectral resolution, but is unnecessary at low resolution. At longer wavelengths, fully cryogenic cooling with liquid nitrogen is generally required.

to the slit providing that the telescope correctly tracks the target. The motion of the image of the slit on the detector is then corrected by moving the detector orthogonal to the optical axis to compensate. Taking account of nonrepeatable motion in the stucture and the detector mounting, it proved possible to attain the desired stability in open-loop by measuring the flexure experienced with the control system turned off, making a look-up table to predict the required detector position for each attitude setting (elevation and attitude) and applying the correction by counting pulses sent to the stepper motors which control the detector translation.

Some instruments require much greater stability than GMOS does. The flexure-control outlined above may be augmented by operation in closed-loop so that nonrepeatable movements may be accounted for. However, this ideally requires a reference light source which illuminates the optics in the same way as the light from the astronomical target and which is recorded by the science detector without adversely impacting the observation. Alternatively, partial feedback may be supplied by repeated metrology of key optical components such as fold-mirrors.

One strategy to measure radial velocities to very small uncertainities (a few meters per second) is to introduce a material (e.g., iodine) into the optical path, which is present throughout the observations. This absorbs light from the observed object's continuum at one very well-defined wavelength. Thus, instrument instability can be removed by measuring the centroid of the desired spectral line in the object relative to the fixed reference produced by the absorption cell. However, flexure must still be carefully controlled to avoid blurring the line during the course of a single exposure.

Mounting of instruments via a fiber-feed remotely from the telescope, at a location where they are not subjected to variations in the gravity vector, is a solution for applications where great stability is required. But, even here, care must be taken with the fore-optics and pickoff system attached to the telescope, and to account for modal noise induced by changes in the fiber configuration as the telescope tracks.

Finally, the instrument structure has other functions. For cooled instruments, a cryostat is required inside which most of the optical components are mounted. For uncooled instruments, careful control of temperature is needed to avoid instrument motion due to thermal expansion. This requires the use of an enclosure which not only blocks out extraneous light, but provides a thermal buffer against changes in the ambient temperature during observations and reduces thermal gradients by forced circulation of air.

See also

Diffraction: Diffraction Gratings. **Fiber and Guided Wave Optics**: Fabrication of Optical Fiber. **Imaging**: Adaptive Optics. **Instrumentation**: Telescopes; Spectrometers. **Spectroscopy**: Fourier Transform Spectroscopy; Hadamard Spectroscopy and Imaging.

Further Reading

Allington-Smith JR, Murray G, Content C, *et al.* (2002) Integral field spectroscopy with the Gemini Multiobject Spectrograph. *Publications of the Astronomical Society of the Pacific* 114: 892.

Bjarklev A, Broeng J and Sanchez Bjarklev AS (2003) *Photonic Crystal Fibers*. Kluwer.

Bowen IS (1938) The Image-Slicer: a device for reducing loss of light at slit of stellar spectrograph. *Astrophysical Journal* 88: 113.

Carrasco E and Parry I (1994) A method for determining the focal ratio degradation of optical fibres for astronomy. *Monthly Notices of the Royal Astronomical Society* 271: 1.

Courtes G (1982) *Instrumentation for Astronomy with Large Optical Telescope, IAU Colloq, 67*. In: Humphries CM (ed.) Astrophysics and Space Science Library, vol. 92, pp. 123. Dordrecht: Reidel.

Glazebrook K and Bland-Hawthorn J (2001) Microslit nod-shuffle spectrocopy: a technique for achieving very high densities of spectra. *Publications of the Astronomical Society of the Pacific* 113: 197.

Lee D, Haynes R, Ren D and Allington-Smith JR (2001) Characterisation of microlens arrays for astronomical spectroscopy. *PASP* 113: 1406.

McLean I (1997) *Electronic Imaging in Astronomy.* Chichester, UK: John Wiley and Sons Ltd.

Palmer C (2000) *Diffraction Grating Handbook*. Richardson Grating Laboratory, 4th edn. Rochester, NY.

Ridgway SH and Brault JW (1984) Astronomical Fourier transform spectroscopy revisited. *Ann. Rev. Astron. Astrophys.* 22.

Saha SK (2002) Modern optical astronomy: technology and impact of interferometry. *Review of Modern Physics* 74: 551.

Schroeder D (2000) *Astronomical Optics*, 2nd edn. San Diego, CA: Academic Press.

van Breugel W and Bland-Hawthorn J (eds) *Imaging the Universe in Three Dimensions*, ASP Conference Series, vol. 195.

Weitzel L, Krabbe A, Kroker H, *et al.* (1996) 3D: The next generation near-infrared imaging spectrometer. *Astron. & Astrophys. Suppl.* 119: 531.

Ellipsometry

J N Hilfiker, J A Woollam & Co., Inc., Lincoln, NE, USA

J A Woollam, University of Nebraska, Lincoln, NE, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Ellipsometry measures a change in polarization as light reflects from or transmits through a material structure. The polarization-change is represented as an amplitude ratio, Ψ, and a phase difference, Δ. The measured response is dependent on optical properties and thickness of each material. Thus, ellipsometry is primarily used to determine film thickness and optical constants. However, it is also applied to the characterization of composition, crystallinity, roughness, doping concentration, and other material properties associated with a change in optical response.

Interest in ellipsometry has grown steadily since the 1960s as it provided the sensitivity necessary to measure nanometer-scale layers used in microelectronics. Today, the range of applications has spread to basic research in physical sciences, semiconductor, data storage, flat panel display, communication, biosensor, and optical coating industries. This widespread use is due to increased dependence on thin films in many areas and the flexibility of ellipsometry to measure most material types: dielectrics, semiconductors, metals, superconductors, organics, biological coatings, and composites of materials.

This article provides a fundamental description of ellipsometry measurements along with the typical data analysis procedures. The primary applications of ellipsometry are also surveyed.

Light and Materials

Ellipsometry measurements involve the interaction between light and material.

Light

Light can be described as an electromagnetic wave traveling through space. For ellipsometry, it is adequate to discuss the electric field behavior in space and time, also known as polarization. The electric field of a wave is always orthogonal to the propagation direction. Therefore, a wave traveling along the z-direction can be described by its x- and y-components. If the light has completely random orientation and phase, it is considered unpolarized. For ellipsometry, we are interested in the case where the electric field follows a specific path and traces out a distinct shape at any point. This is known as polarized light. When two orthogonal light waves are in-phase, the resulting light will be linearly polarized (Figure 1a). The relative amplitudes determine the resulting orientation. If the orthogonal waves are 90° out-of-phase and equal in amplitude, the resultant light is circularly polarized (Figure 1b). The most general polarization is 'elliptical', which combines orthogonal waves of arbitrary amplitude and phase (Figure 1c). This is how ellipsometry gets its name.

Materials

Two values are used to describe optical properties, which determine how light interacts with a material.



Figure 1 Orthogonal waves combine to demonstrate polarization: (a) linear; (b) circular; and (c) elliptical.

They are generally represented as a complex number. The complex refractive index ($\tilde{n}$) consists of the index (n) and extinction coefficient (k):

$$\tilde{n} = n + \mathrm{i}k \qquad [1]$$

Alternatively, the optical properties can be represented as the complex dielectric function:

$$\tilde{\varepsilon} = \varepsilon_1 + \mathrm{i}\varepsilon_2 \qquad [2]$$

with the following relation between conventions:

$$\tilde{\varepsilon} = \tilde{n}^2 \qquad [3]$$

The index describes the phase velocity for light as it travels through a material compared to the speed of light in vacuum, c:

$$v = \frac{c}{n} \qquad [4]$$

Light slows as it enters a material with higher index. Because frequency remains constant, the wavelength will shorten. The extinction coefficient describes the loss of wave energy to the material. It is related to the absorption coefficient, α, as:

$$\alpha = \frac{4\pi k}{\lambda} \qquad [5]$$

Light loses intensity in an absorbing material, according to Beer's Law:

$$I(z) = I(0)\,\mathrm{e}^{-\mathrm{i}\alpha z} \qquad [6]$$

Thus, the extinction coefficient relates how quickly light vanishes in a material. These concepts are demonstrated in Figure 2, where a light wave travels from air into two different materials of varying properties.



Figure 2 Wave travels from air into absorbing Film 1 and then transparent Film 2. The phase velocity and wavelength change in each material depending on index of refraction (Film 1: $n = 4$, Film 2: $n = 2$).

The optical constants for TiO_2 are shown in Figure 3 from the ultraviolet (UV) to the infrared (IR). The optical constants are wavelength dependent with absorption ($k > 0$) occurring in both UV and IR, due to different mechanisms that take energy from the light wave. IR absorption is commonly caused by molecular vibration, phonon vibration, or free-carriers. UV absorption is generally due to electronic transitions, where light provides energy to excite an electron to an elevated state. A closer look at the optical constants in Figure 3 shows that real and imaginary optical constants are not independent. Their shapes are mathematically coupled together through Kramers–Krönig consistency. Further details are covered later in this article.

Interaction Between Light and Materials

Maxwell's equations must remain satisfied when light interacts with a material, which leads to boundary conditions at the interface. Incident light will reflect and refract at the interface, as shown in Figure 4. The angle between the incident ray and sample normal



Figure 3 Complex dielectric function for TiO_2 film covering wavelengths from the infrared (small eV) to the ultraviolet (high eV).



Figure 4 Light reflects and refracts according to Snell's law.

(ϕ_i) will be equal to the reflected angle, (ϕ_r). Light entering the material is refracted to an angle (ϕ_t) given by:

$$n_0 \sin(\phi_i) = n_1 \sin(\phi_t) \qquad [7]$$

The same occurs at every interface where a portion reflects and the remainder transmits at the refracted angle. This is illustrated in Figure 5. The boundary conditions provide different solutions for electric fields parallel and perpendicular to the sample surface. Therefore, light can be separated into orthogonal components with relation to the plane of incidence. Electric fields parallel and perpendicular to the plane of incidence are considered p- and s-polarized, respectively. These two components are independent for isotropic materials and can be calculated separately. Fresnel described the amount of light reflected and transmitted at an interface between materials:

$$r_s = \left(\frac{E_{0r}}{E_{0i}}\right)_s = \frac{n_i \cos\theta_i - n_t \cos\theta_t}{n_i \cos\theta_i + n_t \cos\theta_t} \qquad [8a]$$

$$r_p = \left(\frac{E_{0r}}{E_{0i}}\right)_p = \frac{n_t \cos\theta_i - n_i \cos\theta_t}{n_i \cos\theta_t + n_t \cos\theta_i} \qquad [8b]$$

$$t_s = \left(\frac{E_{0t}}{E_{0i}}\right)_s = \frac{2n_i \cos\theta_i}{n_i \cos\theta_i + n_t \cos\theta_t} \qquad [8c]$$

$$t_p = \left(\frac{E_{0t}}{E_{0i}}\right)_p = \frac{2n_i \cos\theta_i}{n_i \cos\theta_t + n_t \cos\theta_i} \qquad [8d]$$

Thin film and multilayer structures involve multiple interfaces, with Fresnel reflection and transmission coefficients applicable at each. It is important to track the relative phase of each light component to correctly determine the overall reflected or transmitted beam. For this purpose, we define the film phase thickness as:

$$\beta = 2\pi\left(\frac{t_1}{\lambda}\right) n_1 \cos\theta_1 \qquad [9]$$

The superposition of multiple light waves introduces interference that is dependent on the relative phase of each light wave. Figure 5 illustrates the combination of light waves in the reflected beam and their corresponding Fresnel calculations.

Ellipsometry Measurements

For ellipsometry, primary interest is measurement of how p- and s-components change upon reflection or transmission relative to each other. In this manner, the reference beam is part of the experiment. A known polarization is reflected or transmitted from the sample and the output polarization is measured. The change in polarization is the ellipsometry measurement, commonly written as:

$$\rho = \tan(\Psi)\, e^{i\Delta} \qquad [10]$$


r_{01}
$t_{01} r_{12} t_{10} e^{-2i\beta}$
$t_{01} r_{12} r_{10} r_{12} t_{10} e^{-4i\beta}$
$\tilde{n}_0$
$\tilde{n}_1$
$\tilde{n}_2$

Figure 5 Light reflects and refracts at each interface, which leads to multiple beams in a thin film. Interference between beams depends on relative phase and amplitude of the electric fields. Fresnel reflection and transmission coefficients can be used to calculate the response from each contributing beam.

An example ellipsometry measurement is shown in Figure 6. The incident light is linear with both p- and s-components. The reflected light has undergone amplitude and phase changes for both p- and s-polarized light, and ellipsometry measures their changes.

The primary methods of measuring ellipsometry data all consist of the following components: light source, polarization generator, sample, polarization analyzer, and detector. The polarization generator and analyzer are constructed of optical components that manipulate the polarization: polarizers, compensators, and phase modulators. Common ellipsometer configurations include rotating analyzer (RAE), rotating polarizer (RPE), rotating compensator (RCE), and phase modulation (PME).

The RAE configuration is shown in Figure 7. A light source produces unpolarized light, which is sent through a polarizer. The polarizer passes light of a preferred electric field orientation. The polarizer axis is oriented between the p- and s-planes, such that both arrive at the sample surface. The linearly polarized light reflects from the sample surface, becoming elliptically polarized and travels through a continuously rotating polarizer (referred to as the analyzer). The amount of light allowed to pass will depend on the polarizer orientation relative to the electric field 'ellipse' coming from the sample. The detector converts light from photons to electronic signal to determine the reflected polarization. This information is used with the known input polarization to determine the polarization change caused by the sample reflection. This is the ellipsometry measurement of Ψ and Δ.

Single Wavelength Ellipsometry (SWE)

SWE uses a single frequency of light to probe the sample. This results in a pair of data, Ψ and Δ, used to determine up to two material properties. The optical design can be simple, low-cost, and accurate. Lasers are an ideal light source with well-known wavelength and significant intensity. The optical elements can be optimized to the single wavelength. However, there is relatively low information content (two measurement values). SWE is excellent for quick measurement of


1. Known input polarization
E
p-plane
s-plane
Plane of incidence
3. Measure input polarization
p-plane
E
s-plane
2. Reflect off sample . . .

Figure 6 Typical ellipsometry configuration, where linearly polarized light is reflected from the sample surface and the polarization change is measured to determine the sample response.



Figure 7 Rotating analyzer ellipsometer configuration uses a polarizer to define the incoming polarization and a rotating polarizer after the sample to analyze the outgoing light. The detector converts light to a voltage with the time-dependence leading to measurement of the reflected polarization.

nominally known films, like SiO_2 on Si. Care must be taken when interpreting unknown films, as multiple solutions occur for different film thickness. The data from a transparent film will cycle through the same values as the thickness increases. From Figure 5, it can be seen that this is related to interference between the multiple light beams. The refracted light may travel through different thicknesses to emerge in-phase with the first reflection, but is the returning light delayed by one wavelength or multiple wavelengths? Mathematically, the thickness cycle can be determined as:

$$D_\phi = \frac{\lambda}{2\sqrt{\tilde{n}_1^2 - \tilde{n}_0^2 \sin^2\phi}} \qquad [11]$$

This is demonstrated in Figure 8, where the complete thickness cycle is shown for SiO_2 on Si at 75° angle of incidence and 500 nm wavelength. A bare silicon substrate would produce data at the position of the star. As the film thickness increases, the data will move around this circle in the direction of the arrow. From eqn [11], the thickness cycle is calculated as 226 nm. Thus the cycle is completed and returns to the star when the film thickness reaches 226 nm. Any data point along the cycle represents a series of thicknesses which depend on how many times the cycle has been completely encircled. For example, the square represents a data point for 50 nm thickness. However, the same data point will represent 276 and 502 nm thicknesses. A second data point at a new wavelength or angle would help determine the correct thickness.



Figure 8 Data from a single wavelength will cycle through the same points as the film thickness increases. The star represents the starting point, with no SiO_2 film on Si. As the thickness increases, the data follow the cycle in the direction of the arrow. After the cycle is complete (thickness = D_ϕ), the data repeat the cycle. Thus, any point along the curve represents multiple possible thicknesses – example shown by a square at 50 nm thickness, which is also equal to 276 and 502 nm.

Spectroscopic Ellipsometry (SE)

Spectroscopic measurements solve the 'period' problem discussed for SWE. Data at surrounding wavelengths insure the correct thickness is determined, even as there remain multiple solutions at one wavelength in the spectrum. This is demonstrated in Figure 9, showing the spectroscopic data for the first three thickness results. The SE data oscillations clearly distinguish each thickness. Thus, a single thickness solution remains to match data at multiple wavelengths.

SE provides additional information content for each new wavelength. While the film thickness will remain constant regardless of wavelength, the optical constants will change across the spectrum. The optical constant shape contains information regarding the material microstructure, composition, and more. Different wavelength regions will provide the best information for each different material property. For this reason, SE systems have been developed to cover very wide spectral regions from the UV to the IR.

Spectroscopic measurements require an additional component, a method of wavelength selection. The most common methods include the use of monochromators, Fourier-transform spectrometers, and gratings or prisms with detection on a diode array. Monochromators are typically slow as they sequentially scan through wavelengths. Spectrometers and diode arrays allow simultaneous measurement at multiple wavelengths. This has become popular with the desire for high-speed SE measurements.

Variable Angle Ellipsometry

Ellipsometry measurements are typically performed at oblique angles, where the largest changes in polarization occur. The Brewster angle, defined as:

$$\tan(\phi_B) = \frac{n_1}{n_0} \qquad [12]$$



Figure 9 Three spectroscopic ellipsometry measurements that match at 500 nm wavelength, but are easily distinguishable as a function of wavelength.

gives the angle where reflection of p-polarized light goes through a minimum. Ellipsometry measurements are usually near this angle, which can vary from 55° for low-index dielectrics to 75° or 80° for semiconductors and metals.

It is also common to measure at multiple angles of incidence in ellipsometry. This allows additional data to be collected for the same material structure under different conditions. The most important change introduced by varying the angle is the change in path length through the film as the light refracts at a different angle. Multiple angles do not always add new information about a material structure, but the extra data builds confidence in the final answer.

In Situ

Within the last decade, it has become common to employ optical diagnostics during processing. *In situ* ellipsometry allows the optical response to be monitored in real-time. This has also led to feedback control for many processes. While *in situ* is generally restricted to a single angle of incidence, there is a distinct advantage to collecting data at different 'times' during processing to get unique 'glimpses' of the sample structure as it changes.

In situ SE is commonly applied to semiconductors. Conventional SE systems measure from the UV to NIR, which matches the spectral region where semiconductors absorb due to electronic transitions. The shape and position of the absorption can be very sensitive to temperature, composition, crystallinity, and surface quality, which allows SE to closely monitor these properties. *In situ* SE has also been used to monitor numerous material types, including metals and dielectrics. A promising *in situ* application is for multilayer optical coatings, where thickness and index can be determined in real-time to allow correction of future layers, to optimize optical performance.

Data Analysis

Ellipsometry measures changes in polarization. However, it is used to determine the material properties of interest, such as film thickness and optical constants. In the case of a bulk material, the equations derived for a single reflection can be directly inverted to provide the 'pseudo' optical constants from the ellipsometry measurement, ρ:

$$\langle \tilde{\varepsilon} \rangle = \sin^2(\phi)\left[1 + \tan^2(\phi)\left(\frac{1-\rho}{1+\rho}\right)\right] \qquad [13]$$

This equation assumes there are no surface layers of any type. However, there is typically a surface oxide or roughness for any bulk material and the direct inversion would incorporate these into the bulk optical constants. The more common procedure used to deduce material properties from ellipsometry measurements follows the flowchart in Figure 10. Regression analysis is required because an exact equation cannot be written. Often the answer is overdetermined with hundreds of experimental data points for a few unknowns. Regression analysis allows all of the measured data to be included when determining the solution.



Figure 10 Flowchart for ellipsometry data analysis.

Data analysis proceeds as follows. After the sample is measured, a model is constructed to describe the sample. The model is used to calculate the predicted response from Fresnel's equations. Thus, each material must be described with a thickness and optical constants. If these values are not known, an estimate is given for the purpose of the preliminary calculation. The calculated values are compared to experimental data. Any unknown material properties can then be varied to improve the match between experiment and calculation. The number of unknown properties should not exceed the information content contained in the experimental data. For example, a single-wavelength ellipsometer produces two data points (Ψ,Δ) which allows a maximum of two material properties to be determined. Finding the best match between the model and experiment is typically done through regression. An estimator, like the mean squared error (MSE), is used to quantify the difference between curves. The unknown parameters are allowed to vary until the minimum MSE is reached.

Care must be taken to ensure the best answer is found, corresponding to the lowest MSE. For example, Figure 11a shows the MSE curve versus film thickness for a transparent film on silicon. There are multiple 'local' minima, but the lowest MSE value occurs at a thickness of 749 nm. This corresponds to the correct film thickness. It is possible that the regression algorithm will mistakenly fall into a 'local' minima, depending on the starting thickness and the MSE structural conditions. Comparing the results by eye for the lowest MSE and a local minima easily distinguish the true minima (see Figures 11b and c).

Ellipsometry Characterization

The two most common material properties studied by ellipsometry are film thickness and optical constants. In addition, ellipsometry can characterize material properties that affect the optical constants. Crystallinity, composition, resistivity, temperature, and molecular orientation can all affect the optical constants and in turn be measured by ellipsometry. This section details many of the primary applications important to ellipsometry.

Film Thickness

The film thickness is determined by interference between light reflecting from the surface and light traveling through the film. Depending on the relative phase of the rejoining light to the surface reflection, there can be constructive or destructive interference.



Figure 11 (a) MSE curve versus thickness shows the 'global' minimum where the best match between model and experiment occurs, and 'local' minima that may be found by the regression algorithm, but do not give the final result. (b) The experimental data and corresponding curves generated for the model at the 'global' minimum. (c) Similar curves at the 'local' minimum near 0.45 microns thickness is easily distinguishable as an incorrect result.



Figure 12 (a) Reflected intensity and (b) ellipsometric delta for three thin oxides on silicon show the high sensitivity of Δ to nanometer-scale films not available from the intensity measurement.

The interference involves both amplitude and phase information. The phase information from Δ is very sensitive to films down to submonolayer thickness. Figure 12 compares reflected intensity and ellipsometry for the same series of thin SiO_2 layers on Si. There are large variations in Δ, while the reflectance for each film is nearly the same.

Ellipsometry is typically used for films with thickness ranging from sub-nanometers to a few microns. As films become greater than several tens of microns thick, it becomes increasingly difficult to resolve the interference oscillations, except with longer infrared wavelengths, and other characterization techniques become preferred.

Thickness measurements also require a portion of the light to travel through the entire film and return to the surface. If the material is absorbing, thickness measurements by optical instruments will be limited to thin, semi-opaque layers. This limitation can be circumvented by measuring in a spectral region where there is lower absorption. For example, an organic film may strongly absorb UV and IR light, but remain transparent at mid-visible wavelengths. For metals, which strongly absorb at all wavelengths, the maximum layer for thickness determination is typically ~100 nm.

Optical Constants

Thickness measurements are not independent of the optical constants. The film thickness affects the path length of light traveling through the film, but the index determines the phase velocity and refracted angle. Thus, both contribute to the delay between surface reflection and light traveling through the film. Both n and k must be known or determined along with the thickness to get the correct results from an optical measurement.

The optical constants for a material will vary for different wavelengths and must be described at all wavelengths probed with the ellipsometer. A table of optical constants can be used to predict the response at each wavelength. However, it is less convenient to adjust unknown optical constants on a wavelength-by-wavelength basis. It is more advantageous to use all wavelengths simultaneously. A dispersion relationship often solves this problem, by describing the optical constant shape versus wavelength. The adjustable parameters of the dispersion relationship allow the overall optical constant shape to match the experimental results. This greatly reduces the number of unknown 'free' parameters compared to fitting individual n, k values at every wavelength.

For transparent materials, the index is often described using the Cauchy or Sellmeier relationship. The Cauchy relationship is typically given as:

$$n(\lambda) = A + \frac{B}{\lambda^2} + \frac{C}{\lambda^4} \qquad [14]$$

where the three terms are adjusted to match the refractive index for the material. The Sellmeier relationship enforces Kramers–Krönig (KK) consistency, which ensures the optical dispersion retains a realistic shape. The Cauchy is not constrained by KK consistency and can produce unphysical dispersion. The Sellmeier relationship can be written as:

$$\varepsilon_1 = \frac{A\lambda^2\lambda_0^2}{(\lambda^2 - \lambda_0^2)} \qquad [15]$$

Absorbing materials will often have a transparent wavelength region that can be modeled with the Cauchy or Sellmeier relationships. However, the absorbing region must account for both real and imaginary optical constants. Many dispersion relationships use oscillator theory to describe the absorption for materials, which include the Lorentz, Harmonic, and Gaussian oscillators. They all share similar attributes, where the absorption features are described with an amplitude, broadening, and center energy (related to frequency of light).



Figure 13 Lorentz oscillator illustrating the primary oscillator parameters: amplitude (A), broadening (B), and center energy (E_c) to describe the imaginary dielectric function shape and an offset ($\varepsilon_{1,\text{offset}}$) to help match the real component after KK transformation has defined its shape.

Kramers–Krönig consistency is used to calculate the shape of the real component after the imaginary behavior is described by the oscillator. An offset to the real component is added to account for extra absorption outside the measured spectral region. The Lorentz oscillator can be written as:

$$\tilde{\varepsilon} = \varepsilon_{1,\text{offset}} + \frac{AE_c}{E_c^2 - E^2 - \mathrm{i}BE} \qquad [16]$$

where the parameters for amplitude (A), broadening (B), center energy (E_c), and offset ($\varepsilon_{1,\text{offset}}$) are also shown in Figure 13 for a typical Lorentz oscillator. The energy, E, is related to the frequency of a wave, ν:

$$E = h\nu \cong \frac{1240}{\lambda_{\text{nm}}} \qquad [17]$$

where h is Planck's constant and the wavelength, λ, is given in nanometers. More advanced dispersion models, like the Tauc–Lorentz and Cody–Lorentz, will include terms to describe the bandgap energy.

Mixing Materials

When two or more materials are mixed on a microscopic level, an effective medium approximation (EMA) may be used to determine the resulting optical constants. In the case of the Bruggemann EMA, which is commonly used, the mixture optical constants ($\tilde{\varepsilon}_{\text{eff}}$) relate to those of the individual materials, as:

$$f_a \frac{\varepsilon_a - \varepsilon_{\text{eff}}}{\varepsilon_a + 2\varepsilon_{\text{eff}}} + f_b \frac{\varepsilon_b - \varepsilon_{\text{eff}}}{\varepsilon_b + 2\varepsilon_{\text{eff}}} = 0 \qquad [18]$$

This can be interpreted as small particles of material A suspended in host material B. The length-scale for mixed particles must satisfy certain electromagnetic equations: typically smaller than one tenth the wavelength of light. In practice, EMA theory is useful for studying very thin surface roughness or interfacial intermixing of materials. These cases are both generally approximated by mixing the two surrounding materials in equal portions. In the case of surface roughness, the second material is void ($n = 1$). EMA theory has also been extended for application to porous materials where the directional dependence of the inclusions is handled mathematically.

Crystallinity

Semiconductors such as Si, are widely used materials, but their properties depend strongly on crystallinity. The UV absorption features in crystalline silicon are broadened and shifted as the material becomes more amorphous. This change in optical properties related to the degree of crystallinity has been used to advantage with ellipsometry measurements to monitor semiconductors and other films. Polysilicon films are used in both the display and semiconductor industry. The degree of crystallinity varies for different process conditions and can be monitored optically to ensure consistent material properties.

Composition

The composition of many alloys will affect the optical constants. The strongest changes often occur in the absorbing region, with shifts in position and amplitude of absorption features. For example, the electronic transitions in $Hg_{1-x}Cd_xTe$ move to higher energy with Cd concentration increase (Figure 14). This material is used for IR detectors that require precise control of composition. Spectroscopic ellipsometry performs this task in real-time with instant feedback to correct the composition during processing. Other applications include AlGaN and InGaN for optoelectronics.



Figure 14 Optical properties for $Hg_{1-x}Cd_xTe$ vary with changes in composition.



Figure 15 Experimental ellipsometry data and corresponding fit when the model is described as (a) a homogeneous single-layer and (b) a graded film with index variation through the film. (c) The best model to match subtleties in experimental data allows the index to increase toward the surface of the film, with a thin roughness layer on the surface.

Doping Concentration

Dopants in a material will introduce absorption in the infrared due to free-carriers. Spectroscopic ellipsometry measurements at long wavelengths can characterize this optical absorption, thus characterizing the doping concentration. This is common for highly doped semiconductors and transparent conductors such as indium tin oxide (ITO).

Optical Variation (Grading)

Many thin film properties change vertically throughout the film (along the direction perpendicular to the surface). This is most often induced by processing conditions, whether intentional or unintentional. Figure 15a shows the fit to experimental spectroscopic ellipsometry data taken from a single-layer film when it is modeled as a homogeneous layer. To improve the agreement between experimental and model-generated curves, the index was allowed to vary in a linear manner throughout the film. The best fit is shown in Figure 15b, where the model includes the index variation and a thin surface roughness layer. The sample structure is demonstrated in Figure 15c.

Optical Anisotropy

Many materials are optically anisotropic; i.e., their optical properties vary in different film directions. Typical ellipsometry measurements assume no cross-coupling between p- and s-polarizations. This cannot be assumed with anisotropic materials, which has led to ‘generalized’ ellipsometry measurements. Generalized ellipsometry measures additional information regarding the p- to s- and s- to p- conversion upon reflection. This allows characterization of anisotropic materials, which contain directionally dependent optical constants.

Conclusions

Ellipsometry is a common optical technique for measuring thin films and bulk materials. It relies on the polarization changes due to reflection or transmission from a material structure to deduce material properties, like film thickness and optical constants. This technique continues to develop as the requirement for thin film characterization increases.

See also

Geometrical Optics: Lenses and Mirrors; Prisms. **Optical Coatings:** Thin-Film Optical Coatings. **Optical Materials:** Measurement of Optical Properties of Solids.

Polarization: Introduction; Matrix Analysis. **Semiconductor Physics:** Band Structure and Optical Properties. **Spectroscopy:** Fourier Transform Spectroscopy.

Further Reading

Aspnes DE (1985) The accurate determination of optical properties by ellipsometry. In: Palik ED (ed.) *Handbook of Optical Constants of Solids*, pp. 89–112. Orlando FL: Academic Press.

Azzam RMA and Bashara NM (1987) *Ellipsometry and Polarized Light*. Amsterdam, The Netherlands: Elsevier Science B.V.

Boccara AC, Pickering C and Rivory J (eds) (1993) *Spectroscopic Ellipsometry*. Amsterdam: Elsevier Publishing.

Collins RW, Aspnes DE and Irene EA (eds) (1998) *Proceedings from the Second International Conference on Spectroscopic Ellipsometry*. Thin Solid Films, vols. 313–314.

Gottesfeld S, Kim YT and Redondo A (1995) Recent applications of ellipsometry and spectroellipsometry in electrochemical systems. In: Rubinstein I (ed.) *Physical Electrochemistry: Principles, Methods, and Applications*. New York: Marcel Dekker.

Herman IP (1996) *Optical Diagnostics for Thin Film Processing*, pp. 425–479. San Diego, CA: Academic Press.

Johs B, Woollam JA, Herzinger CM, *et al.* (1999) Overview of variable angle spectroscopic ellipsometry (VASE), Part II: Advanced applications. *Optical Metrology*, vol. CR72, pp. 29–58. Bellingham, Washington: SPIE, Bellingham.

Johs B, Hale J, Ianno NJ, *et al.* (2001) Recent developments in spectroscopic ellipsometry for *in situ* applications. In: Duparré A and Singh B (eds) *Optical Metrology Roadmap for the Semiconductor, Optical, and Data Storage Industries II*, vol. 4449, pp. 41–57. Bellingham, Washington: SPIE.

Roseler A (1990) *Infrared Spectroscopic Ellipsometry*. Berlin: Akademie-Verlag.

Rossow U and Richter W (1996) Spectroscopic ellipsometry. In: Bauer G and Richter W (eds) *Optical Characterization of Epitaxial Semiconductor Layers*, pp. 68–128. Berlin: Springer-Verlag.

Tompkins HG (1993) *A User's Guide to Ellipsometry*. San Diego, CA: Academic Press.

Tompkins HG and Irene EA (eds) (in press) *Handbook of Ellipsometry*. New York: William Andrew Publishing.

Tompkins HG and McGahan WA (1999) *Spectroscopic Ellipsometry and Reflectometry*. New York: John Wiley & Sons, Inc.

Woollam JA (2000) Ellipsometry, variable angle spectroscopic. In: Webster JG (ed.) *Wiley Encyclopedia of Electrical and Electronics Engineering*, pp. 109–116. New York: John Wiley & Sons.

Woollam JA and Snyder PG (1992) Variable angle spectroscopic ellipsometry. In: Brundle CR, Evans CA and Wilson S (eds) *Encyclopedia of Materials Characterization: Surfaces, Interfaces, Thin Films*, pp. 401–411. Boston, MA: Butterworth-Heinemann.

Woollam JA, Johs B, Herzinger CM, *et al.* (1999) Overview of variable angle spectroscopic ellipsometry (VASE), Part I: Basic theory and typical applications. *Optical Metrology*, vol. CR72, pp. 3–28. Washington: SPIE, Bellingham.

Photometry

J Schanda, University of Veszprém, Veszprém, Hungary

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Fundamentals of Photometry

Photometry is defined by the International Commission on Illumination (internationally known as CIE from the abbreviation of its French name: Commission Internationale de l'Eclairage) as 'measurement of quantities referring to radiation as evaluated according to a given spectral efficiency function, e.g., $V(\lambda)$ or $V'(\lambda)$.' A note to the above definition states that in many languages it is used in a broader sense, covering the science of optical radiation measurement. We will restrict our treatise to the above fundamental meaning of photometry.

Under spectral efficiency function we understand the spectral luminous efficiency function of the human visual system. The internationally agreed symbols are $V(\lambda)$, for photopic vision (daylight conditions) and $V'(\lambda)$ for scotopic vision (nighttime conditions). CIE standardized the $V(\lambda)$ function in 1924 and the $V'(\lambda)$ function in 1951; their spectral distribution is shown in Figure 1. The $V(\lambda)$ function was determined using mainly the so-called flicker photometric technique, where the light of a reference stimulus and of a test stimulus of varying wavelengths are alternatively shown to the human observer at a frequency at which the observer is already unable to perceive the difference in color (due to the different wavelength of the two radiations), but still perceives a



Figure 1 Spectral efficiency functions of the human eye under photopic $V(\lambda)$ and scotopic $V'(\lambda)$ conditions (see CIE The basis of physical photometry. CIE 18.2:1983).

flicker sensation if the luminances of the two stimuli are different. Adjusting the radiance of the test stimulus, we can reach the situation of minimum flicker sensation. In this case we state that we set the two stimuli to equal luminance. Luminance is the quantity that the human observer perceives as brightness (in the case of near white stimuli, see below); radiance is the physical counterpart measured in $\mathrm{W\,m^{-2}\,sr^{-1}}$. For the $V'(\lambda)$ function one can just project the two stimuli side by side, as under scotopic adaptation we cannot distinguish colors, only brightness differences are perceived, thus one can set equal scotopic luminance for the two stimuli by adjusting the brightness of the test stimulus until it agrees with that of the reference stimulus.

Illuminating engineering was mainly interested in describing the effect of near white light, and therefore a psychophysical correlation was selected that described the perceived brightness sensation reasonably well. For near white stimuli, additivity holds, i.e., if A, B, C, and D are four stimuli, and the A stimulus matches the B stimulus and the C stimulus matches the D stimulus, then the superposition of the A and C stimuli matches the superposition of the B and D stimuli. The 'match' word is used here to describe stimuli that produce the same perception. It could be shown that for these stimuli, if the radiance is weighted with the $V(\lambda)$ function, the constructed luminances will be equal, i.e:

$$\text{if} \qquad L_\mathrm{A} = L_\mathrm{B} \text{ and } L_\mathrm{C} = L_\mathrm{D}$$

$$\text{then} \quad L_\mathrm{A} + L_\mathrm{C} = L_\mathrm{B} + L_\mathrm{D}, \text{ or } L_\mathrm{A} + L_\mathrm{D} = L_\mathrm{B} + L_\mathrm{C}$$

where

$$L_\mathrm{x} = K_\mathrm{m} \int_{380\ \mathrm{nm}}^{780\ \mathrm{nm}} S_{\lambda\mathrm{x}} V(\lambda)\mathrm{d}\lambda \qquad [1]$$

and x refers to A, or B, or C, or D, and $S_{\lambda\mathrm{x}}$ is the spectral radiance distribution that produces the stimulus

$$S_\lambda = \frac{\mathrm{d}S(\lambda)}{\mathrm{d}\lambda}$$

where $S(\lambda)$ is the spectral radiance. K_m is the maximum value of the luminous efficacy of radiation, its value is $683\ \mathrm{lm\,W^{-1}}$ (see the discussion of luminous flux in the sub-section on photometric quantities). To be precise the integration should go from 0 nm to infinity, but it is usual to define the lower and upper wavelength limits of the visible spectrum as 380 nm and 780 nm. $V(\lambda)$ is defined between 360 nm and 830 nm, and $V'(\lambda)$ between 380 nm and 780 nm, see Figure 1.

We have to stress that the concept of luminance – and the entire system of the present-day photometry – is not to quantify brightness perception; it is only a reasonable approximation for near white stimuli. For colored lights a brightness–luminance discrepancy exists (called the Helmhotz–Kohlrausch effect: saturated colors look brighter than predicted by luminance). Luminance is, however, a good description for the visibility of fine details, thus it is a good concept for lighting calculations.

Photometry has a unique situation in the SI system of units: the candela (cd) is a base unit of the SI system, the only one that is connected to psychophysical phenomena. By 1979, in the definition of the 16th General Conference of Weights and Measures, the candela was traced back to radiation quantities; nevertheless it was kept as the base unit of photometry:

> The candela is the luminous intensity, in a given direction, of a source that emits monochromatic radiation of frequency 540×10^{12} Hz and that has a radiant intensity in that direction of $1/683\ \mathrm{W\,sr^{-1}}$. ($540 \times 10^{12}$ Hz corresponds approximately to 555 nm.)

To be able to calculate a photometric quantity of radiation of other wavelengths, one of the psychophysical functions $V(\lambda)$ or $V'(\lambda)$ has to be used and eqn [1] applied. We will see later that besides $V(\lambda)$ and $V'(\lambda)$ in modern applications, a number of further spectral luminous efficiency functions might be used.

Photometric Quantities

As discussed in the previous section, from the point of view of vision, the most important quantity is luminance. Looking, however, at the definition of the base unit, it is obvious that from the physical point of view the definition of a quantity corresponding to radiant power, measured in watts, can help to bridge the gap between photometry and radiometry: luminous flux, measured in lumens (lm), with the symbol Φ, is defined by eqn [1], with $S_\lambda(\lambda)$ inserted in W m^{-1}.

Based on this more practical quantity of luminous flux and its unit, lm, the different quantities used in photometry can be built up as follows:

$$\textit{Luminous flux}: \quad \Phi = K_m \int_0^\infty \frac{\mathrm{d}\Phi_e(\lambda)}{\mathrm{d}\lambda} V(\lambda)\mathrm{d}\lambda \qquad [2]$$

where $\Phi_e(\lambda)$ is the radiant flux measured in W,

$$\Phi_{e,\lambda} = \frac{\mathrm{d}\Phi_e(\lambda)}{\mathrm{d}\lambda}$$

is the spectral distribution (or spectral concentration) of the radiant flux (W m^{-1}). $K_m = 683$ lm W^{-1}, is the maximum value of the luminous efficacy of radiation for $\lambda_m \approx 555$ nm.

Similar equations can be written for scotopic luminous flux, with $V(\lambda)$ exchanged with $V'(\lambda)$, where $K'_m = 1700$ lm W^{-1} for $\lambda_m \approx 507$ nm. All further quantities can be defined both for photopic and scotopic conditions. Here we write them only as photopic quantities.

$$\textit{Luminous intensity}: \quad I = \frac{\mathrm{d}\Phi}{\mathrm{d}\Omega} \qquad [3]$$

where $\mathrm{d}\Phi$ is the luminous flux traveling in an elementary solid angle $\mathrm{d}\Omega$, assuming a point source (see Figure 2). The unit of luminous intensity is the candela (cd = lm sr^{-1}).

$$\textit{Luminance}: \quad L = \frac{\partial^2\Phi}{\partial A \cos\Theta\, \partial\Omega} \qquad [4]$$

where $\mathrm{d}\Phi$ is the luminous flux traveling in an elementary solid angle $\mathrm{d}\Omega$, $\mathrm{d}A$ is the elementary surface area emitting the radiation, and Θ is the angle between the normal of $\mathrm{d}A$ and the direction of luminance measurement (see Figure 3). The unit of luminance is cd m^{-2} (in some older literature called nit).

$$\textit{Illuminance}: \quad E = \frac{\mathrm{d}\Phi}{\mathrm{d}A} \qquad [5]$$

where $\mathrm{d}\Phi$ is the luminous flux incident on the $\mathrm{d}A$ element of a surface (see Figure 4). The unit of illuminance is the lux (lx = lm m^{-2}).

A remark on the use of SI units and related quantities

No prefixes can be added to the SI units, thus irrespective whether one measures luminance based



Figure 2 Concept of point source, solid angle, and luminous intensity.



Figure 3 Geometry for the definition of luminance.



Figure 4 Illuminance is the total luminous flux per unit area incident at a point coming from a hemispherical solid angle.

on the photopic $V(\lambda)$ function, or the scotopic $V'(\lambda)$ function, the so-determined photopic luminance or scotopic luminance is measured in cd m^{-2} (no photopic or scotopic lumen, candela, etc., exist!). This often creates confusion, because only for a 555 nm monochromatic radiation will a 1 cd m^{-2} photopic or scotopic luminance produce equal visual sensation, for every other wavelength the two are not commensurable. One can only relate photopic measurement results to photopic ones, and scotopic measurement results to scotopic ones.

Concepts of Advanced Photometry

The quantities and units, as described in the previous section, are the quantities and units internationally agreed by the Meter Convention and the International Standards Organization (ISO). Modern photometric applications need, however, some further quantities and weighting functions. Thus CIE, the international organization for the development of standards in the field of optical radiation measurements, has defined a series of further weighting functions and quantities. The most important ones are the following:

$V_M(\lambda)$ function

In the blue part of the spectrum (below 460 nm) the values of the $V(\lambda)$ function turned out to be too low. For decades this was only of concern for the vision research community, but with the introduction of blue LEDs and other short wavelength emitting sources (e.g., blue channel of displays) this shortcoming of the $V(\lambda)$ function became of practical importance. The 'CIE 1988 2° spectral luminous efficiency function for photopic vision' corrects this anomaly (see Figure 5).

$V_{10}(\lambda)$ function

The official $V(\lambda)$ function is valid only for foveal vision (i.e., for targets that are smaller than 4° of visual angle). The foveal area of the retina is covered with a yellow pigmented layer (macula lutea) that absorbs in the blue part of the spectrum, at larger visual angles this screening is not effective anymore. The $V_{10}(\lambda)$ function was determined for a visual angle of 10° (see Figure 5). Its international recommendation is still under consideration at the time of writing this article and if accepted, it will be recommended for targets seen at approximately 10° off-axis, e.g., for measuring the photometric properties of traffic signs and signals, where the driver has to observe the information in the periphery of his or her eye.



Figure 5 Spectral luminous efficiency (SPL) functions defined or under consideration for international adoption: V2: standard $V(\lambda)$ function; VM2: CIE 1988 $V_M(\lambda)$ function, this is equivalent to the brightness SPL for a point source; V10: 10° visual field SPL, Vb,2: 2° visual field brightness SPL, $V_{b,2}(\lambda)$; Vb,10: 10° visual field brightness SPL, $V_{b,10}(\lambda)$.

Brightness matching functions

As already mentioned in the Introduction, luminance is not a good correlate of brightness, which is a human perception. To find a better correlation of brightness the problem to be addressed is that brightness is a nonadditive phenomenon, i.e., in eqn [1] one cannot add (integrate) the monochromatic radiations to get a brightness correlation for a nonmonochromatic radiation. Brightness evaluating spectral luminous efficiency functions can be used only to compare monochromatic radiations. The CIE has compiled such functions for point sources, 2° and 10° visual field sizes. Figure 5 also shows these functions.

Due to the fact that the brightness perception is nonadditive in respect of the stimuli that produce it, no brightness photometry can be built that uses equations, as shown in eqn [1]. For brightness description we have to rely on the concept of equivalent luminance, a term the definition of which has recently been updated.

Equivalent luminance

Of a field of given size and shape, for a radiation of arbitrary relative spectral distribution L_{eq} : Luminance of a comparison field in which monochromatic radiation of frequency 540×10^{12} Hz has the same brightness as the field considered under the specified photometric conditions of measurement; the comparison field must have a specified size and shape which may be different from that of the field considered.

To build an instrument that measures this quantity is a real challenge for the future.

Advanced Use of Photometry

Based on above newly defined quantities, several attempts are under way to extend the usefulness of photometry in designing the human visual environment. The eye is an optical system and as in every such system, the depth of focus and the different aberrations of the system will decrease with decreasing pupil size. Pupil size will decrease with increasing illumination, and in the case of constant luminance with higher content of short wavelength radiation. Thus, there exists a school of researchers who advocate that increased blue content in the light has beneficial effects on vision, and one should extend the classical photopic-based photometry with a scotopic-based one to properly describe the visual effect of lighting.

Other investigations are concerned about the visibility at low light levels, the range used in street lighting (from about a few thousands of a candela per square meter to about a few candelas per square meter, according to one definitions: 10^{-3}cd m^{-2}–3 cd m^{-2}). In this mesopic range both rods and cones are contributing to vision, and this changes with lighting level and direction of view (for foveal vision, i.e., looking straight ahead, photopic photometry seems to hold even at low light levels). For peripheral visual angles brightness perception and the perception of an object (a signal, sign or obstacle in a nighttime driving situation) seem to have different spectral responsivity. In driving situations the necessary reaction time of the driver is an important parameter, thus experiments are going on to define a photometric system based on reaction time investigations.

In indoor situations apart from the necessary level of illumination, the observed glare is a contributor whether an environment will be accepted as pleasing or annoying. Illuminating engineering distinguishes between two types of glare: disability glare reduces visibility, discomfort glare is just an annoying experience without influencing the short-term task performance. An interesting question is the spectral sensitivity to discomfort glare, as it can influence not only indoor but also outdoor activity. Preliminary experiments seem to show that luminance sensitivity and discomfort glare sensitivity have different spectral distribution; glare sensitivity seems to peak at shorter wavelengths.

The above might be related to a further question, lying already at the boundaries of photometry, but that has to be considered in photometric design and measurement: the human daily and yearly rhythm (circadian and seasonal rhythm) of human activity coupled to hormone levels. They are influenced by light, as, for example, the hormone melatonin production is influenced by light exposure. Physiological investigations showed that melatonin production suppression has a maximum around 460 nm and might be coupled to a radiation sensitive ganglion cell in the retina. Whether discomfort sensation is mediated via the same neural pathway or via a visual one has not yet been decided. But photometry has to take these also into consideration and in the future, measurement methods and instruments to determine them, will have to be developed.

Advances in Photometric Measurements

Primary Standards

The main concern in photometry is that the uncertainty of photometric measurements is still much higher than that in other branches of physics. This is partly due to the higher uncertainty in radiometry and partly to the increase in uncertainty within the chain of uncertainty propagation from the National Laboratory to the workshop floor measurement.

In National Standards Laboratories, very sophisticated systems are used to determine the power of the incoming radiation and then elaborated spectroradiometric techniques are used to evaluate the radiation in the form of light, i.e., perform photometric measurements (e.g., NIST CIRCUS equipment, where multiple laser sources are used as power sources, and highly sophisticated methods to produce a homogeneous nonpolarized radiation field for the calibration of secondary photometric detectors).

There is, however, also a method to supply end users with absolute detectors for the visible part of the spectrum. Modern high-end Si photovoltaic cells have internal quantum efficiencies in the visible part of the spectrum of over 99.9%. Reflection losses at the silicon surface are minimized by using three or more detectors arranged in a trap configuration, where the light reflected from one detector is fed to the second one, from there to the third one, and eventually to some further ones. In a three detector configuration, as shown in Figure 6, the light from the third detector is reflected back to the second and from there to the first one. As every detector reflects only a small amount of radiation, by the fifth reflection practically



Figure 6 Schematic layout of a three Si-cell trap detector: light comes in from the left, is first partly absorbed, partly reflected on Detector 1, then on Detector 2, then on Detector 3, from where it is reflected back to Detector 2 and 1.



Figure 7 Arrangement of the absolute integrating sphere system developed at NIST for the detector-based total luminous flux calibration. By permission of IESNA from Ohno Y and Bergman R (2003) Detector-referenced integrating sphere photometry for industry. *J. IES Summer* 21–26.

all the radiation is absorbed and contributes to the electric signal. Such trap detectors have an almost 100% quantum efficiency in the visible part of the spectrum, and can be used as photometric detectors if a well designed color correcting filter is applied in front of the detector.

Secondary Type Measurements

In practical photometry the three most important quantities to be measured are the total luminous flux of different lamps, the illuminance in a plane and the luminance.

Light source measurement

Total luminous flux. The two methods to measure the total luminous flux is to use a goniophotometer or a photometer (Ulbicht) sphere. In goniophotometry, recent years have not brought major breakthroughs, the automation of the systems got better, but the principles are unchanged.

The integrating sphere photometer (a sphere with inner white diffuse coating, where the lamp is in the middle of the sphere) used to be a simple piece of equipment to compare total luminous flux lamps against flux standards. In recent years a new technique has been developed at NIST–USA. This enables the absolute measurement of luminous flux from illuminance measurement, the fundamentals of this new arrangement being shown in Figure 7: the test lamp is as usual in the middle of the sphere, but now light from an external source is introduced into the sphere. An illuminance meter measures the flux entering from this source. The sphere detector compares the two signals (y_i and y_e). Knowing the absolute characteristics of the sphere (a difficult measurement) one can determine the total luminous flux of the test lamp using the absolute illuminance value. As illuminance is easily determined from luminous intensity (from eqns [3] and [5] one gets with $\mathrm{d}\Omega = \mathrm{d}A/r^2$ that $E = I/r^2$, where r is the distance between the source and the illuminated surface, supposed to be perpendicular to the direction to the source), this technique permits us to derive the total luminous flux scale from illuminance or luminous intensity measurement using an integrating sphere.

Luminous intensity of LEDs. An other major break-through achieved during the past years was the unified measurement of LED intensity. Light-emitting diodes became, in recent years, important light sources for large scale signaling and signing, and it is foreseen that they will become important contributors in every field of light production (from car headlamps to general illumination). The most fundamental parameter of the light of an LED is its luminous intensity. The spatial power distribution of LEDs is usually collimated, but the LEDs often squint, as seen in Figure 8. In the past, some manufacturers measured the luminous intensity in the direction of maximum emission, others used the direction of the optical axis for this quantity. The highly collimated character of the radiation made measurements in far field rather difficult. Therefore, CIE recommended a new term and measuring geometry: average LED intensity can be measured under two measuring conditions, as shown in Figure 9. The detector has to be set in the direction of the LED mechanical axis (discussions are still going on as to what the reference direction should be with modern surface mounted LEDs, as with those the mechanical axis is ill-defined, the normal to the base-plane could be a better reference direction). The detector has to have an exactly 1.00 cm^2 circular aperture, and the distance between this aperture and the tip of the LED is for condition A, $d = 0.316$ m, and for Condition B, $d = 0.100$ m (these two distances with the 1.00 cm^2 detector area provide 0.001 sr (steradians) and 0.01 sr opening angles). Recent international round-robins have shown that, based on the new recommendations, agreement between different laboratories decreased from the 10 to 20% level to 1 to 2%. The remaining difference is mainly due to the fact that the LEDs emit in narrow wavelength bands, and the transfer of the calibration value for the 100 mm^2 detector from a white (CIE Standard Illuminant A color temperature) incandescent lamp to the narrow band LED emission is still uncertain, mainly due to stray light effects in the spectral responsivity and emission measurement.



Figure 8 Spatial light distribution of an LED, Figure 8a shows the distribution of a 'squinting' LED in a plane including the optical axis, Figure 8b shows light distribution in a plane perpendicular to the optical axis. By permission of the Commission Internationale de l'Eclairage, from the Publication "Measurement of LEDs" CIE 127-1997; CIE Publications are obtainable from the CIE Central Bureau: Kegelgasse 27, A-1033 Wien, Austria.

Luminance distribution measurement

The human observer sees luminance (and color) differences. Thus for every illuminating engineering design task the luminance distribution in the environment is of utmost importance. Traditionally this was measured using a spot-luminance meter, aiming the device into a few critical directions. The recent development of charge coupled device (CCD) two-dimensionally sensitive arrays (and other, e.g., MOS-FET, CMOS, Charge injection device (CID), charge imaging matrix (CIM) systems: as for the time being the CCD technology provides best performance, we will refer to two-dimensional electronic image capture devices as to CCD cameras) opened the possibility of using an image-capturing camera for luminance distribution measurements. Such measurements are badly needed in display calibration, near-field photometry (photometry in planes nearer than in which the inverse square law holds), testing of car headlamp light distribution, glare, and homogeneity studies indoors and outdoors, etc.

Solid-state cameras have the big advantage over older type vacuum-tube image capturing devices, that the geometric position and alignment of the single pixels is well-defined and stays constant. Nowadays, CCD image detector chips are mass produced, and one can get a variety of such devices and cameras starting with some small resolution



Figure 9 Schematic diagram of CIE Standard Conditions for the measurement of Average LED Intensity. Distance $d = 0.316$ m for Condition A and $d = 0.100$ m for Condition B. By permission of the Commission Internationale de l'Eclairage, from the Publication "Measurement of LEDs" CIE 127-1997; CIE Publications are obtainable from the CIE Central Bureau: Kegelgasse 27, A-1033 Wien, Austria.

(few thousand pixels) devices up to cameras with tens of mega pixel resolution. Detectors are now available with internal intensification enabling measurements down to a few photons per second intensity levels.

Main problems with these detectors are:

- spectral and absolute nonuniformities of the single pixels (see Figure 10), where a spatial homogeneity map of a CCD two-dimensional array detector is shown; the irregular 3% sensitivity change on the surface of the detector is negligible for imaging purposes, but has to be corrected in cases of photometric measurements. Even if the receptor chip would have an absolutely homogeneous sensitivity, there would be a drop in response from the middle of the imaging area to the boarders: Light reaching the edges of the detector reach the detector at an oblique angle and this produces a decrease of sensitivity with α^4, where α is the angle of incidence, measured from the middle of the lens to the given pixel of the detector and the surface normal of the detector.
- aliasing effects if the pixel resolution is not large enough to show straight lines as such when they are not in line with a pixel row or column.
- nonlinearity and cross-talk among the adjacent pixels. Figure 11 shows the so-called 'inverse gamma' characteristic of a CCD camera. The digital electronic output of the camera shows a $Y = E^{-\gamma}$ type function, where Y is the output DAC (digital-analog converter) values, E is the irradiance of the pixel, and γ is the exponent (this description comes from the film industry, where the film density depends exponentially on the irradiation; display devices have usually a nonlinear input (DAC value) – output (luminance) characteristic, and the camera inverse gamma value corrects for this output device characteristic. This is, however, not required if the camera is used for photometric measurements; this built-in nonlinearity has to be corrected in the evaluating software if the camera is intended for photometric measurements.
- to be able to perform photometric measurements the camera has to have a spectral responsivity corresponding to the CIE $V(\lambda)$-function. Many cameras have built-in filters to do this – eventually also red and blue filters to be able to capture color – but the color correction of cameras, where the correction is made by small adjacent filter chips, is usually very poor. Figure 12 shows the spectral



Figure 10 Spatial homogeneity of a two-dimensional CCD array.



Figure 11 'Inverse gamma' characteristic of a commercial digital photographic camera, measurement points are shown at different speed settings, curve is a model function representative of the camera response.



Figure 12 Spectral sensitivity of a commercial digital photographic camera.

sensitivity curve of a digital photographic camera; the output signal is produced by an internal matrix transformation of the signals produced by adjacent pixels equipped with different color filters. Figure 13 shows the spectral sensitivity of a CCD camera specially designed for photometric measurements. Naturally, meaningful photometric measurements can be made only with such a camera. Very often, however, an approximate luminance distribution is enough, and then a picture captured by a digital photographic camera, plus one luminance measurement of a representative object for absolute calibration, suffices.

Above nonspectral systematic errors can be corrected by appropriate soft-ware, so a CCD camera photometer, as shown schematically in Figure 14, is well suited to measure display characteristics, indoor and outdoor luminance distributions. The challenge for illuminating engineering is at present how the many millions of luminance values can be evaluated to get to meaningful light measurement data.



Figure 13 Spectral sensitivity of a CCD camera specially designed for photometric measurements. Kindly supplied by INPHORA Inc.



Figure 14 Cross-section of a photometric CCD camera.

The real challenge will come if visual science provides better hints how the human visual system evaluates the illuminance distribution on the retina, and instrument manufacturers will be able to capture signals corresponding to those produced by the receptor cells and provide the necessary algorithms our brain uses to get to brightness, lightness, color, luminance contrast, and glare type of output information.

Concluding Remarks

Advances in optical instrumentation, both in the field of light sources and detectors – coupled with the possibilities modern digital computation (eventually in the future increasing the use of neural networks) – provide already many new measurement technical solutions and further ones are certainly underway.

The use of LEDs needs the rethinking of many classical illuminating engineering concepts, from visibility and glare evaluation, evenness of illumination to color rendering. All of them are coupled with problems in basic photometry. Thus, there is a need to re-evaluate concepts used in design techniques. The new area-sensitive detectors provide methods of determining classical photometric quantities of entire visual fields in one shot, but already foreshadow the development of new quantities that correlate better with visual perceptions.

List of Units and Nomenclature

Terms with an $*$ refer to definitions published by the CIE in the International Lighting Vocabulary, CIE 17.4:1986, where further terms and definitions related to light and lighting are to be found.

Candela*: SI unit of luminous intensity: The candela is the luminous intensity, in a given direction, of a source that emits monochromatic radiation of frequency 540×10^{12} hertz and that has a radiant intensity in that direction of 1/683 watt per steradian. (16th General Conference of Weights and Measures, 1979).

$$1 \text{ cd} = 1 \text{ lm sr}^{-1}$$

Equivalent luminance*: Luminance of a comparison field in which monochromatic radiation of frequency 540×10^{12} Hz has the same brightness as the field considered under the specified photometric conditions of measurement; the comparison field must have a specified size and shape which may be different from that of the field considered.

$$\text{unit} : \text{cd m}^{-2}$$

Notes:

1. Radiation at a frequency of 540×10^{12} Hz has a wavelength in standard air of 555.016 nm.
2. A comparison field may also be used in which the radiation has any relative spectral distribution, if the equivalent luminance of this field is known under the same conditions of measurement.

Far field photometry: Photometry where the inverse square law is valid.

Flicker photometer*: Visual photometer in which the observer sees either an undivided field illuminated successively, or two adjacent fields illuminated alternately, by two sources to be compared, the frequency of alteration being conveniently chosen so that it is above the fusion frequency for colours but below the fusion frequency for brightnesses.

Fovea*: Central part of the retina, thin and depressed, which contains almost exclusively cones and forming the site of most distinct vision.

Note: The fovea subtends an angle of about 0.026 rad (1.5 degree) in the visual field.

Goniophotometer*: Photometer for measuring the directional light distribution characteristics of sources, luminaires, media or surfaces.

Illuminance*: Quotient of the luminous flux $d\Phi_v$ incident on an element of the surface containing the point, by the area dA of that element.

Equivalent definition. Integral, taken over the hemisphere visible from the given point, of the expression $L_v \cos\theta \, d\Omega$, where L_v is the luminance at the given point in the various directions of the incident elementary beams of solid angle $d\Omega$, and θ is the angle between any of these beams and the normal to the surface at the given point.

$$E_v = \frac{d\Phi_v}{dA} = \int_{2\pi sr} L_v \cos\theta \, d\Omega$$

$$\text{unit} : \text{lx} = \text{lm m}^{-2}$$

Inverse square law: The illumination at a point on a surface varies directly with the luminous intensity of the source, and inversely as the square of the distance between the source and the point if the source is seen as a point source.

Lumen*: SI unit of luminous flux: Luminous flux emitted in unit solid angle (steradian) by a uniform point source having a luminous intensity of 1 candela. (9th General Conference of Weights and Measures, 1948).

Equivalent definition. Luminous flux of a beam of monochromatic radiation whose frequency is 540×10^{12} hertz and whose radiant flux is 1/683 watt.

Luminance*: Quantity defined by the formula

$$L = \frac{\partial^2\Phi}{\partial A \cos\theta \, \partial\Omega}$$

where $\partial\Phi$ is the luminous flux transmitted by an elementary beam passing through the given point and propagating in the solid angle $d\Omega$ containing the given direction; dA is the area of a section of that beam containing the given point, θ is the angle between the normal to that section and the direction of the beam.

$$\text{unit} : \text{cd m}^{-2}$$

Luminous intensity*: Quotient of the luminous flux $d\Phi_v$ leaving the source and propagated in the element of solid angle $d\Omega$ containing the given direction, by the element of solid angle:

$$I_v = \frac{d\Phi_v}{d\Omega}$$

$$\text{unit} : \text{cd} = \text{lm sr}^{-1}$$

Lux*: SI unit of illuminance: Illuminance produced on a surface of area 1 square meter by a luminous flux of 1 lumen uniformly distributed over that surface.

$$1 \text{ lx} = 1 \text{ lm m}^{-2}$$

Note: Non-metric unit: **lumen per square foot** (lm ft^{-2}) or **footcandle** (fc) (USA) = 10.764 lx.

Near-filed photometry: photometry made in the vicinity of an extended source, so that the inverse square law is not valid.

Photometer (or Ulbicht) sphere*: A hollow sphere, whitened inside. Owing to the internal reflexions in the sphere, the illumination on any part of the sphere's inside surface is proportional to the luminous flux entering the sphere, or produced inside the sphere by a lamp. The illuminance of the internal sphere wall is measured via a small window.

Pixel: The individual picture elements of an image or elements in a display that can be addressed individually.

Radiance*: Quantity defined by the formula

$$L = \frac{\partial^2\Phi}{\partial A \cos\theta \, \partial\Omega}$$

where $\partial\Phi$ is the radiant flux transmitted by an elementary beam passing through the given point and propagating in the solid angle $d\Omega$ containing the given direction; dA is the area of a section of that beam containing the given point, θ is the angle between the normal to that section and the direction of the beam.

$$\text{unit} : \text{W m}^{-2} \text{ srad}$$

Retina*: Membrane situated inside the back of the eye that is sensitive to light stimuli; it contains photoreceptors, the cones and the rods, and nerve cells that interconnect and transmit to the optic nerve the signals resulting from stimulation of the photoreceptors.

Spectral*: An adjective that, when applied to a quantity X pertaining to electromagnetic radiation, indicates:

- either that X is a function of the wavelength λ, symbol: $X(\lambda)$,
- or that the quantity referred to is the spectral concentration of X, symbol: $X_\lambda \equiv \mathrm{d}X/\mathrm{d}\lambda$.

X_λ is also a function of λ and in order to stress this may be written $X_\lambda(\lambda)$ without any change of meaning.

Spectral luminous efficiency function: for photopic vision, *V*(λ); for scotopic vision *V*′(λ)*: Ratio of the radiant flux at wavelength λ_m to that at wavelength λ such that both radiations produce equally intense luminous sensations under specified photometric conditions and λ_m is chosen so that the maximum value of this ratio is equal to 1.

Unless otherwise indicated, the values used for the spectral luminous efficiency in photopic vision are the values agreed internationally in 1924 by the CIE (*Compte Rendu* 6^e session, p.67), completed by interpolation and extrapolation (*Publications CIE* No.18 (1970), p.43 and No. 15 (1971), p.93), and recommended by the International Committee of Weights and Measures (CIPM) in 1972. For *scotopic vision*, the CIE in 1951 adopted, for young observers, the values published in *Compte Rendu* 12^e session, Vol. 3, p. 37, and ratified by the CIPM in 1976. These values define respectively the $V(\lambda)$ or $V'(\lambda)$ functions.

Total luminous flux: luminous flux of a source emitted into 4π steradians.

Trap detector: Detector array prepared from detectors of high internal quantum efficiency, where the reflected radiation of the first detector is directed to the second one, and so on so that practically all the radiation is absorbed by one of the detectors (the radiation is "trapped" in the detector system).

See also

Displays. **Incoherent sources:** Lamps.

Further Reading

Commission Internationale de l'Eclairage: *The basis of physical photometry* (1983) CIE 18.2.

Commission Internationale de l'Eclairage: Proceedings of the CIE Symposium 2002 on *Temporal and Spatial Aspects of Light and Colour Perception and Measurement*, August 2002: Publ.CIE x025:2003.

Cromer CL, Eppledauer G, Hardis JE, Larason TC and Parr AC (1993) National Institute of Standards and Technology detector-based photometric scale. *Applied Optics* 32: 2936–2948.

Decusatis C (ed.) (1997) *Handbook of Applied Photometry*. Woodbury, New York: American Institute of Physics.

Rea MS (ed.) (2000) Illuminating Engineering Society of North America. *The IESNA Lighting Handbook: Reference and Application*, 9th edn.

Kaiser PK and Boynton RM (1966) *Human Color Vision*, 2nd edn. Washington, DC: Optical Society of America.

McCluney WR (1994) *Introduction to radiometry and photometry*. Boston, London: Artech House.

Ohno Y and Bergman R (2003) Detector-referenced integrating sphere photometry for industry. *J IES Summer* 21–26.

Walsh JWT (1953) *Photometry*. London: Constable.

Scatterometry

J C Stover, The Scatter Works, Inc., Tucson, AZ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Scattered light is a limiting source of optical noise in many advanced optical systems, but it can also be a sensitive indicator of optical component quality. Consider the simple case of a telescope successfully used to image a dim star against a dark background; however, if light from a bright source (such as the moon located well out of the field of view) enters the telescope, it will scatter from the interior walls and the imaging optics themselves. Some of this light eventually reaches the detector and creates a dim background haze that washes out the image of the distant star. A good telescope design accounts for these effects by limiting potential scatter propagation paths and by requiring that critical elements in the optical system meet scatter specifications. This means doing a careful system analysis and a means to quantify the scattering properties of the telescope components. This article discusses modern techniques for quantifying, measuring, and analyzing scattered light, and reviews their development.

Like many scientific advances moving scatterometry from an art to a reliable metrology was done in a series of small hops (not always in the same direction), rather than a single leap. It started in 1961 when a paper by Hal Bennett and Jim Porteous reported measurements made by gathering most of the light scattered from front surface mirrors and normalizing this signal by the much larger specular reflection. They defined this ratio as the total integrated scatter (TIS), and using a scalar diffraction theory result drawn from the radar literature, related it to the surface root mean square (rms) roughness. By the mid-1970s, several angle-resolved scatterometers had been built as research tools in university, government, and industry labs. Unfortunately, instrument operation and data manipulation were generally poor, and meaningful comparison measurements were virtually impossible due to instrument differences, sample contamination, and confusion over what parameters should be compared. Analysis of scatter data, to characterize sample surface roughness, was the subject of many publications. A derivation of what is commonly called 'BRDF' (bidirectional reflectance distribution function) was published by Nicodemus and co-workers at the National Bureau of Standards (now the National Institute of Science and Technology or NIST) in 1970, but did not gain common acceptance as a way to quantify scatter measurements until the late 1980s when the advent of small computers, combined with inspection requirements for defense-related optics, dramatically stimulated the development of scatter metrology. Commercial laboratory instrumentation became available that could measure and analyze as many as 50 to 100 samples a day, and the number (and sophistication) of measurement facilities increased dramatically. The first ASTM Standards were published (TIS in 1987 and BRDF in 1991), but it was still several years before most publications correctly used these quantifying terms. Government defense funding decreased dramatically in the early 1990s, following the end of the Cold War, but the economic advantages of using scatter metrology and analysis for space applications and in the rapidly advancing semiconductor industry, continued state-of-the-art advancements.

The following sections detail how scatter is quantified when related to area (roughness) and local (pit/particle) generating sources. Instrumentation and the use of scattering models are also briefly reviewed.

Quantifying Scattered Light

Scatter signals can be easily quantified as scattered light power per unit solid angle (in watts per steradian); however, in order to make the results more meaningful, these signals are usually normalized, in some fashion, by the light incident on the scatter source. The three ways commonly employed to do this are defined below.

If the scattering feature in question is uniformly distributed across the illuminated spot on the sample (such as surface roughness), then it makes sense to normalize the collected scattered power in watts/steradian by the incident power. This simple ratio, which has units of inverse steradians, was commonly referred to as 'the scattering function.' Although this term is occasionally still found in the literature, it has been generally replaced by the closely related BRDF, which is defined by the differential ratio of the sample radiance normalized by its irradiance. After some simplifying assumptions are made, this reduces to the original scattering function with a cosine of the polar scattering angle in the denominator. The BRDF, defined in this manner, has become the standard way to report angle-resolved scatter from features that uniformly fill the illuminated spot. The cosine term results from the fact that NIST used radiometric terms to define BRDF:

$$\mathrm{BRDF} = \frac{\mathrm{Ps}/\Omega}{\mathrm{Pi}\cos\theta_s} \qquad [1]$$

The scatter function is often referred to as the 'cosine corrected BRDF' and is simply equal to the BRDF multiplied by the cosine of the polar scattering angle. Figure 1 gives the geometry for the situation, and defines the polar and azimuthal angles (θ_s and ϕ_s), as well as the solid collection angle (Ω). Other common abbreviations are BSDF, for the more generic bidirectional scatter distribution function, and BTDF for quantifying transmissive scatter.



Figure 1 Scatter analysis uses standard spherical coordinates to define terms.

Integration of the scatter signal over much of the scattering hemisphere allows calculation of TIS, as the ratio of the scatter signal to the reflected specular power. This integration is usually carried out experimentally in such a way that both the incident beam and reflected specular beam are excluded. In the most common TIS situation, the beam is incident at a small angle near surface normal, and the integration is done from small values of θ_s to almost 90 degrees. If the fraction of light scattered from the specular reflection is small and if the scatter is caused by surface roughness, then it can be related to the rms surface roughness of the reflecting surface. As a ratio of powers, the TIS is a dimensionless quantity. The normalization is by Pr (instead of Pi) because reductions in scatter caused by low reflectance do not influence the roughness calculation. The pertinent relationships are given below, where σ is the rms roughness and λ is the light wavelength:

$$\mathrm{TIS} = \mathrm{Ps}/\mathrm{Pr} \cong (4\pi\sigma/\lambda)^2 \qquad [2]$$

Of course, all scatter measurements are integrations over a detector collection aperture, but the TIS designation is reserved for situations where the aim is to gather as much scattered light as possible, while ‘angle resolved’ designs are created to gain information from the distribution of the scattered light. Notice that TIS values become very large when measured from a diffuse surface, where the specular reflection is very small. Although TIS can be measured for any surface, the diffuse reflectance (equal to Ps/Pi) would often be more appropriate for diffuse surfaces. The various restrictions associated with relating TIS to rms roughness are detailed below.

Scatter from discrete features, such as particles and pits, which do not completely fill the illuminated spot, must be treated differently. This is because changes in spot size, with no corresponding change in total incident power, will change the incident intensity (watts/unit area) at the feature and thus also change the scatter signal (and BRDF) without any corresponding changes in the scattering feature. Clearly this is unacceptable if the object is to characterize the defect with scatter measurements. The solution is to define another quantification term, known as the differential scattering cross-section (DSC), where the normalization is the incident intensity at the feature (the units for DSC are area/steradian). Because this was not done in terms of radiometric units at the time it was defined, the cosine of the polar scattering angle is not in the definition. The same geometrical definitions, found in Figure 1, also apply for the DSC:

$$\mathrm{DSC} = \frac{\mathrm{Ps}/\Omega}{Ii} \qquad [3]$$

If the DSC is integrated over the solid angle associated with a collection aperture then the value has units of area. Because relatively small area focused laser beams are often used as a source, area is most commonly given in micrometers squared.

These three scatter parameters, the BRDF, the TIS, and the DSC, are obviously functions of system variables such as geometry, scatter direction (both in and out of the incident plane), incident wavelength and polarization, as well as feature characteristics. It is the dependence of the scatter signal on these system parameters that makes the scatter models useful for optimizing instrument designs. It is their dependence on feature characteristics that makes scatter measurement a useful metrology tool.

A key point needs to be stressed. When applied appropriately, TIS, BRDF, and DSC are absolute terms, not relative terms. The DSC of a 100 nm PSL in a given direction for a given source is a fixed value, which can be repeatedly measured and even accurately calculated from models. The same is true for TIS and BRDF values associated with surface roughness of known statistics. Scatter measuring instruments, such as particle scanners or lab scatterometers, can be calibrated in terms of these quantities. As has already been pointed out, the user of a scanner will almost always be more interested in characterizing defects than in the resulting scatter values, but the underlying instrument calibration can always be expressed in terms of these three quantities. This is true even though designers and users may find it convenient to use other metrics (such as polysterene latex (PSL) spheres) as a way to relate calibration.

Angle Resolved Scatterometers

The diagram in Figure 2 shows the most common scatterometer configuration. The source is fixed and the sample is rotated to the desired incident angle. The receiver is then rotated about the sample during scatter measurement. Most commonly, scatterometers operate just in the plane of incidence; however, instruments capable of measuring at virtually any location in either the reflective or transmissive hemispheres have been built. Although dozens of instruments have been built following this general design, other configurations are in use. For example, the source and receiver may be fixed and the sample rotated so that the scatter pattern moves past the receiver. This is easier mechanically than moving the receiver at the end of an arm, but complicates analysis because the incident angle and the observation angle change simultaneously. Another combination is to fix the source and sample together, at constant incident angle, and rotate this unit (about the point of illumination on the sample) so that the scatter pattern moves past a fixed receiver. This has the advantage that a long receiver/sample distance can be used without motorizing a long (heavy) receiver arm. It has the disadvantage that heavy (or multiple) sources are difficult to deal with. Other configurations, with everything fixed, have been designed that employ several receivers to merely sample the BSDF and display a curve fit of the resulting data. This is an economical solution if the BSDF is relatively uniform without isolated diffraction peaks. The goniometer section of a real instrument, similar to that of Figure 2, is shown in Figure 3.



Figure 2 Basic elements of an incident plane scatterometer are shown.



Figure 3 The author's scatterometer, which is similar to the diagram of Figure 2 is shown. In this case a final focusing lens is introduced to produce a very small illuminated spot on the silicon wafer sample. The white background was introduced to make the instrument easier to view.

Computer control of the measurement is essential to maximize versatility and minimize measurement time. The software required to control the measurement plus the display and analysis of the data can be expected to be a significant portion of total instrument development cost. The following reviews typical design features (and issues) associated with the source, sample mount and receiver components.

The source in Figure 2 is formed by a laser beam that is chopped, spatially filtered, expanded, and finally brought to a focus on the receiver path. The beam is chopped to reduce both optical and electronic noise. This is usually accomplished through the use of lock-in detection in the electronics package which suppresses all signals except those at the chopping frequency. Low noise, programmable gain electronics are essential to reducing system noise. The reference detector is used to allow the computer to ratio out laser power fluctuations and, in some cases, to provide the necessary timing signal to the lock-in electronics. Polarizers, wave plates, and neutral density filters are also commonly placed prior to the spatial filter. The spatial filter removes source scatter from the laser beam and presents a point source which is imaged by the final focusing element, in this case a mirror, to the detector zero position. Focusing the beam at this location allows near specular scatter to be more easily measured. Lasers are convenient sources, but are not necessary. Broadband sources are often required to meet a particular application or to simulate the environment where a sample will be used. Monochromators and filters can be used to provide scatterometer sources of arbitrary wavelength. The noise floors with these tunable incoherent sources increases as the spectral bandpass is narrowed, but they have the advantage that the scatter pattern does not contain laser speckle.

The sample mount can be very simple or very complex. In principal, six degrees of mechanical freedom are required to fully adjust the sample. The order in which these stages are mounted affects the ease of use (and cost) of the sample holder. In practice, it often proves convenient to either eliminate, or occasionally duplicate, some of these degrees of freedom. In addition, some of these axes may be motorized to allow the sample area to be raster-scanned to automate sample alignment or to measure reference samples. As a general rule, the scatter pattern is insensitive to small changes in incident angle but very sensitive to small angular deviations from specular. Instrumentation should be configured to allow location of the specular reflection (or transmission) very accurately. Receiver designs vary, but changeable entrance apertures, bandpass filters, lenses, and field stops are generally positioned in front of the detector.

A serious measurement problem is getting light scattered by the instrument, called instrument signature, confused with light scattered by the sample. An example of instrument signature is shown by the dotted line in Figure 2, which represents scatter from the final mirror. The signature is often measured in the straight through (transmission) direction, multiplied by the measured specular reflectance and then compared to the measured sample BRDF. Another issue is the fact that the measured BRDF is really the convolution of the receiver aperture with the actual (incremental) BRDF. When the scatter signal varies slowly across the aperture the measurement is virtually identical to the true BRDF. Near the specular reflection, or at diffraction peaks, the differences between the measurement (or convolution) and the actual (incremental) BRDF can be huge. Measurements made using invisible sources and measurements of curved samples present additional problems. These problems and the issues of calibration and accuracy are covered in the Further Reading section at the end of this article.

TIS Instruments

The two common methods of making TIS measurements are shown in Figures 4 and 5. The first one is based on a hemispherical mirror (or Coblentz sphere) to gather scattered light from the sample and image it onto the scatter detector. The specular beam enters and leaves the hemisphere through a small circular hole. The diameter of that hole defines the near specular limit of the instrument. The reflected beam (not the incident beam) should be centered in the hole because the BRDF will be symmetrical about it. Alignment of the hemispherical mirror is critical, and not trivial, in this approach. The second approach involves the use of an integrating sphere. A section of the sphere is viewed by a recessed detector. If the detector field of view (FOV) is limited to a section of the sphere that is not directly illuminated by scatter from the sample, then the signal will be proportional to total scatter from the sample. Again, the reflected beam should be centered on the exit hole. The Coblentz sphere method presents more signal to the detector; however, some of this signal is incident on the detector at very high angles. Thus, this approach tends to discriminate against high-angle scatter (which is not a problem for many samples). The integrating sphere is easier to align, but has a lower signal to noise ratio (less signal on the detector) and is more difficult to build in the IR where uniform diffuse surfaces are harder to obtain. A common mistake with TIS measurements is to assume that for near normal incidence, the orientation between source polarization and sample orientation is not an issue. TIS measurements made with a linearly polarized source on a grating at different orientations will quickly demonstrate this dependence.



Figure 4 A diagram showing the Coblentz sphere approach to TIS measurements used in the early development of scatter instrumentation.



Figure 5 More modern TIS instruments make use of an integrating sphere approach which is easier to align and does not suffer from problems associated with measuring high-angle scatter from the sample.

TIS measurements can be made very near the specular reflection by utilizing a diffusely reflecting plate with a small hole in it. A converging beam is reflected off the sample and through the hole. Scatter is diffusely reflected from the diffuse plate to a receiver designed to uniformly view the plate. The reflected power is measured by moving the plate so the specular beam misses the hole and then taking that measurement. The ratio of the two scatter measurements gives the TIS. Measurements starting closer than 0.1 degrees from specular can be made in this manner and it is an excellent way to check incoming optics or freshly coated optics for low scatter.

Analyzing Scatter from Surface Roughness

The preceding sections have concentrated on obtaining and quantifying accurate scatter data, but that leaves the question of what to do with it once you have it. In rare situations you may be given a scatter (BRDF) specification – such as, the BRDF from the mirror must be less than 10^{-4} sr^{-1} 10 degrees from specular when measured at a wavelength of 633 nm incident at 5 degrees with an S polarized source. Unfortunately this is very uncommon. If the issue is limiting scatter as a noise source, you will probably have to generate your own specification based on specific system requirements. More difficult, and often of more economic value, is the situation where scatter measurements are being used as a metrology to learn something about the sample characteristics – like roughness or defect size and/or type.

The relationship between the measured BRDF and reflector roughness statistics was a subject of intense interest from the mid-1970s through the early 1990s. Dozens of papers, and even some books, have been written on the subject, and it can only be outlined here. The relatively easy case of scatter from roughness on a clean, optically smooth, front surface reflector was first published in 1975; however it was several years later before confirming experiments were completed. The deceptively simple relationship, based on vector perturbation theory, is shown below.

$$\mathrm{BRDF} = (16\pi^2/\lambda^4)\cos\theta_\mathrm{i}\cos\theta_\mathrm{s}\, QS(f_x, f_y) \qquad [4]$$

Q is the polarization factor and is determined by the material constants of the reflector, as well as the system geometry. In many cases, it is numerically about equal to the specular reflectance and this approximation is often justified. Exact expressions are available in the literature. $S(f_x, f_y)$ is the surface power spectral density function (or PSD). It may be thought of as roughness power (surface height variations squared) per unit spatial frequency (undulations per unit distance instead of per unit time). Integration of the PSD over spatial frequency space results in the mean square roughness over that band of frequencies. Taking the square root gives the root mean square roughness (or rms). Frequencies in both the x and y directions on the surface are involved and they are defined by the well-known grating equations as:

$$f_x = (\sin\theta_\mathrm{s}\cos\phi_\mathrm{s} - \sin\theta_\mathrm{i})/\lambda \qquad \text{and}$$

$$f_y = (\sin\theta_\mathrm{s}\sin\phi_\mathrm{s})/\lambda \qquad [5]$$

Thus eqn [4] becomes a model for surface roughness that allows BRDF measurement to be used to find and/or verify surface roughness specifications. Of course, there are exceptions. If the ‘clean, optically smooth, front surface reflector’ limitations are violated, then the surface will have more than just roughness as a source of scatter and the PSD found from eqn [4] will be too large. Obtaining the same PSD from BRDF measurements made at different wavelengths, or different polarizations, is an indication that the surface is scattering ‘topographically’ and the PSD can be found using this technique. Because some scatter measurements can be made very rapidly, there are industry situations where scatter metrology offers a very fast means of monitoring surface quality.

A little study of eqns [4] and [5] makes it clear that ranges of spatial frequencies in the PSD correspond directly to angular ranges of the BRDF. Scatter from a single spatial frequency corresponds to a single scatter direction.

Following the above discussion, it becomes clear why the pioneering integrated (TIS) scatter measurements could be used to produce surface rms values as indicated by eqn [2]. Unfortunately, the result of eqn [4] was not available in 1961. Instead eqn [2] was derived for the special case of a smooth surface with Gaussian statistics. Nobody was thinking about spatial bandwidths and angular limits. When striking differences were found between roughness measurements made by TIS and profilometer, the Gaussian assumption became the ‘whipping boy,’ and TIS scatter measurements took an underserved hit. In fact, integration of eqn [4] results in the TIS result given in eqn [2] under the generally true small angle assumption that most of the scatter is close to the specular reflection. The differences make sense when the concept of spatial frequency bandwidths (or appropriate angular limits) is introduced. It becomes clear that different wavelengths, incident angles and scatter collection angles will also generate different rms values (for the same surface) and why so much confusion resulted following the definition of TIS in terms of rms roughness. There is no such thing as a unique rms roughness for a surface, anymore than there is a single spatial bandwidth for the PSD, or a single set of angles over which to integrate the BRDF. TIS measurements and rms measurements should always be given with enough information to determine bandwidth limits.

Measuring and Analyzing Scatter from Isolated Surface Features

Understanding scatter from discrete surface features has led to big changes in the entertainment business (CDs, DVDs, digitized music, and films, etc.) as well as providing an important source of metrology for the semiconductor industry as they develop smaller faster chips for a variety of modern uses. Thus, just about everybody in the modern world utilizes our understanding of scatter from discrete surface features.

On the metrology side, the roughness signals described in the last section are a serious source of background noise that limits the size of the smallest defects that can be found. Discrete surface features come in a dazzling array of types, sizes, materials, and shapes – and they all scatter differently. A 100 nm silicon particle scatters a lot differently than a 100 nm silicon oxide particle (even if they have the same shape), and a 100 nm diameter surface pit will have a different scatter pattern. Models describing scatter from a variety of discrete surface features have been developed. Although many of these are kept confidential for competitive reasons, NIST offers some models publicly through a web site.

Confirming a model requires knowing exactly what is scattering the light. In order to accomplish this, depositions of PSLs of known size are made on the surface. Scatter is measured from one or more spheres. A second measurement of background scatter is then subtracted and the net BRDF is converted to DSC units using the known (measured) illuminated spot size. Measurements of this type have been used to confirm discrete feature scatter models. The model is then used to calculate scatter from different diameters and materials. Combined with the model for surface roughness to evaluate system noise, this capability allows signal to noise evaluation of different defect scanners designs.

Practical Industrial Instrumentation

Surface defects and particles, smaller than 100 nm are now routinely found on silicon wafers using scatter instruments known as particle scanners. Thousands of these instruments (with price tags approaching a million dollars each depending on type and use) are in daily use. These instruments are truly amazing; they inspect 200 mm wafers at a rate of one every thirty seconds reporting feature location, approximate size, and in some cases even type (pit or particle) by analyzing scatter signals that last only about 100 nanoseconds. Similar systems are now starting to be used in the computer disk industry and flat panel display inspection of surface features will follow.

Scanners are calibrated with PSLs of different sizes. Because it is impossible to identify all defect types and because diameter has little meaning for irregularly shaped objects, feature ‘size’ is reported in ‘PSL equivalent diameters.’ This leads to confusing situations for multiple detector systems, which (without some software help) would report different sizes for real defects that scatter much differently than PSLs. These difficulties have caused industry confusion similar to the ‘Gaussian statistics/bandwidth limited’ issues encountered before roughness scatter was understood. The publication of international standards relating to scanner calibration has reduced the level of confusion.

Scatter Related Standards

Early scatter related standards for BRDF, TIS, and PSD calculations were written for ASTM (the American Society for Testing Materials), but as the industrial need for these documents moved to the semiconductor industry, there was pressure to move the documents to SEMI (Semiconductor Equipment and Materials Inc.), which is an international organization. By 2004, the process of rewriting the ASTM documents in SEMI format was well underway in the Silicon Wafer Committee. Topics covered include: surface defect specification (M35), defect capture rate (M50), scanner specifications (M52), scanner calibration (M53), particle deposition testing (M58), BRDF measurement (ME1392), and PSD calculation (MF1811). This body of literature is probably the only place where all aspects of these related problems are brought together in one place.

Conclusion

The bottom line is that scatter measurement and analysis has moved from an art to a working metrology. Dozens of labs around the world can now take the same sample and get about the same measured BRDF from it. Thousands of industrial surface scanners employing scattered light signals are in use every day on every continent. In virtually every house in the modern world there is at least one entertainment device that depends on scatter signals. In short – scatter works.

See also

Scattering: Scattering Theory.

Further Reading

Bennett JM and Mattsson L (1995) *Introduction to Surface Roughness and Scattering*, 2nd edn. Washington, DC: Optical Society of America.

Bennett HE and Porteus JO (1961) Relation between surface roughness and specular reflectance at normal incidence. *Journal of the Optical Society of America* 51: 123.

Cady FM, Bjork DR, Rifkin J and Stover JC (1989) BRDF error analysis. *Proceedings of SPIE* 1165: 154–164.

Church EL and Zavada JM (1975) Residual surface roughness of diamond-turned optics. *Applied Optics* 14: 1788.

Doicu A, Eremin Y and Wriedt T (2000) *Acoustic & Electromagnetic Scattering Analysis Using Discrete Sources*. San Diego, CA: Academic Press.

Gu ZH, Dummer RS, Maradudin AA and McGurn AR (1989) Experimental study of the opposition effect in the scattering of light from a randomly rough metal surface. *Applied Optics* 28(3): 537.

Nicodemus FE, Richmond JC, Hsia JJ, Ginsberg IW and Limperis T (1977) *Geometric Considerations and Nomenclature for Reflectance*. NBS Monograph 160, US Dept. of Commerce.

Scheer CA, Stover JC and Ivakhnenko VI (1998) Comparison of models and measurements of scatter from surface-bound particles. *SPIE Proceedings* 3275.

Schiff TF, Stover JC and Bjork DR (1992) Mueller matrix measurements of scattered light. *Proceedings of SPIE* 1753: 269–277.

Stover JC (1975) Roughness characterization of smooth machined surfaces by light scattering. *Applied Optics* 14(8): 1796.

Stover JC (1995) *Optical Scattering: Measurement and Analysis*, 2nd edn. Bellingham, WA: SPIE.

Stover JC (2001) Calibration of particle detection systems. In: Alain Diebold (ed.) *Handbook of Silicon Semiconductor Metrology*, chap. 21. New York: Marcel Dekker.

Wolfe WL and Bartell FO (1982) Description and limitations of an automated scatterometer. *Proceedings of SPIE* 362-30.

Spectrometers

K A More, SenSyTech, Inc. Imaging Group, Ann Arbor, MI, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Sp7ectrometers were developed after the discovery that glass prisms disperse light. Later, it was discovered that diffraction from multiple, equally spaced, wires or fibers also dispersed light. About 100 years ago, Huygens proposed his wave theory of light and Fraunhofer developed diffraction theory, which allowed scientific development of diffraction gratings.

These discoveries then led to the development of spectrometers. Light theory was sufficiently developed such that spectrometer designs, developed over 100 years ago, are still being used today. These theories and designs are briefly described along with comments on how current technology has improved upon these designs. This is followed by some examples of imaging spectrometers which have wide spectral coverage from 450 nm to 14 µm and produce images of more than 256 spectral bands.

The basic elements of a spectroscopic instrument are shown in Figure 1. The source, or more usually an image of the source, fills an entrance slit and the radiation is collimated by either a lens or mirror. The radiation is then dispersed, by either a prism or a grating, so that the direction of propagation of the radiation depends upon its wavelength. It is then brought to a focus by a second lens or mirror and the spectrum consists of a series of monochromatic images of the entrance slit. The focused radiation is detected, either by an image detector such as a photographic plate, or by a flux detector such as a photomultiplier, in which case the area over which the flux is detected is limited by an exit slit. In some cases the radiation is not detected at this stage, but passes through the exit slit to be used in some other optical system. As the exit slit behaves as a monochromatic source, the instrument can be regarded as a wavelength filter and is then referred to as a monochromator.

Prisms

The wavelength dependence of the index of refraction is used in prism spectrometers. Such an optical



Figure 1 The basic elements of a spectroscopic instrument. With permission from Hutley MC (1982) *Diffraction Gratings*, pp. 57–232. London: Elsevier.



Figure 2 Elementary prism spectrometer schematic. *W* is the width of the entrance beam; S_p is the length of the prism face; and *B* is the prism base length. Reproduced with permission from *The Infrared Handbook* (1985). Ann Arbor, MI: Infrared Information Analysis Center.

element disperses parallel rays or collimated radiation into different angles from the prism according to wavelength. Distortion of the image of the entrance slit is minimized by the use of planewave illumination. Even with planewave illumination, the image of the slit is curved because not all of the rays from the entrance slit can traverse the prism in its principal plane. The prism is shown in the position of minimum angular deviation of the incoming rays in Figure 2. At minimum angular deviation, maximum power can pass through the prism. For a prism adjusted to the position of minimum deviation:

$$r_1 = r_2 = A_p/2 \qquad [1]$$

and

$$i_1 = i_2 = (D_p + A_p)/2 \qquad [2]$$

where

D_p = angle of deviation
A_p = angle of prism
r_1 and r_2 = internal angles of refraction
i_1 and i_2 = angles of entry and exit.

The angle of deviation, D_p, varies with wavelength. The resulting angular dispersion is defined as $\mathrm{d}D_p/\mathrm{d}\lambda$, while the linear dispersion is $\mathrm{d}x/\mathrm{d}\lambda = F\,\mathrm{d}D_p/\mathrm{d}\lambda$, where F is the focal length of the camera or imaging lens and x is the distance across the image plane.



Figure 3 Infrared spectrograph of the Littrow-type mount with a rock salt prism. Reproduced with permission from *The Infrared Handbook* (1985) Ann Arbor, MI: Infrared Information Analysis Center.

It can be shown that:

$$dD_p/d\lambda = [B/W][dn/d\lambda] = [dD_p/dn][dn/d\lambda] \quad [3]$$

where

B = base length of the prism,
W = width of the illumination beam
n = index of refraction

while

$$dx/d\lambda = F[B/W][dn/d\lambda] \quad [4]$$

One may define the resolving power, RP, of an instrument as the smallest resolvable wavelength difference, according to the Rayleigh criterion, divided into the average wavelength in that spectral region. Thus:

$$\mathrm{RP} = \lambda/\Delta\lambda = [\lambda/dD_p][dD_p/d\lambda]$$

$$= [\lambda/dD_p][B/W][dn/d\lambda] \quad [5]$$

The limiting resolution is set by diffraction due to the finite beamwidth, or effective aperture of the prism, which is rectangular. Thus:

$$\mathrm{RP} = [\lambda/(\lambda/W)][B/W][dn/d\lambda] \quad [6]$$

so that:

$$RP = B[dn/d\lambda] \quad [7]$$

If the entire prism face is not illuminated, then only the illuminated base length must be used for B.

Littrow showed that aberrations would be minimized by making the angle of incidence equal to the angle of refraction β (also known as the Littrow Configuration). Littrow used a plane mirror behind the prism for a double pass through the prism, as shown in Figure 3.

Gratings

Rowland is credited with the development of a grating mount that reduced aberrations in the spectrogram. He found that a grating ruled on a concave surface of radius R and locating the entrance and exit slits on the same radius would give the least aberrations, as shown in Figure 4. $r = R\cos\alpha$ is the distance to the entrance slit *(r)* and $r_1 = R\cos\beta$ is the distance to the focal point for the exit slit (r_1). Rowland showed that:

$$\cos\alpha/R - \cos^2\alpha/r + \cos\beta/R - \cos^2\beta/r_1 = 0 \quad [8]$$

One solution to this equation is for α and β to each be zero and

$$r = R\cos\alpha$$

and

$$r_1 = R\cos\beta$$

This condition is met if r and r_1 lie on the Rowland circle.

There are various ways in which the Rowland circle condition may be satisfied and some of them are shown in Figure 5. The simplest mounting of all is that due to Paschen and Runge (Figure 5a) in which the entrance slit is positioned on the Rowland circle and a photographic plate (or plates) is constrained to fit the Rowland circle. Alternatively, for photoelectric detection, a series of exit slits is arranged around the Rowland circle each having its own detector. In the latter case, the whole spectrum is not recorded, only a series of predetermined wavelengths, but when used in this 'polychromator' form, it is very rugged and convenient for applications such as the routine analysis of samples of metals and alloys. In this case, slits and detectors are set up to measure the light in various spectral lines, each characteristic of a particular component or trace element.



Figure 4 The construction of the Rowland Circle. With permission from Hutley MC (1982) *Diffraction Gratings*, pp. 57–232. London: Elsevier.

The oldest concave grating mount is that designed by Rowland himself and which bears his name (Figure 5b). In this case, the grating and photographic plates are fixed at opposite ends of the diameter of the Rowland circle by a moveable rigid beam. The entrance slit remains fixed above the intersection of two rails at right angles to each other and along which the grating plate holder (or the exit slit) is free to move. In this way, this entrance slit, grating, and plate holder are constrained always to lie on the Rowland circle and it has the advantage that the dispersion is linear, which is useful in the accurate determination of wavelengths. Unfortunately, this mounting is rather sensitive to small errors in the position of the entrance slit and in the orthogonality of the rails, and is now very rarely used.

A variation on this mounting was devised by Abney, who again mounted the grating and the plate holder on a rigid bar at opposite ends of the diameter of the Rowland circle (Figure 5c). The entrance slit is mounted on a bar of length equal to the radius of the Rowland circle. In this way, the slit always lays on the Rowland circle, but it had to rotate about its axis in order that the jaws should remain perpendicular to the line from the grating to



Figure 5 Mountings of the concave grating: (a) Paschen–Runge; (b) Rowland; (c) Abney; (d) and (e) Eagle; (f) Wadsworth; (g) Seya–Namioka; (h) Johnson–Onaka. With permission from Hutley MC (1982) *Diffraction Gratings*, pp. 57–232. London: Elsevier.

the slit. It also had the disadvantage that the source must move with the exit slit, which could be inconvenient.

In the Eagle mounting (**Figures 5d** and **5e**), the angles of incidence and diffraction are made equal, or very nearly so, as with Littrow mounting for plane gratings. Optically, this system has the advantage that the astigmatism is generally less than that of the Paschen–Runge or Rowland mounting, but on the other hand, the dispersion is nonlinear. From a mechanical point of view, it has the disadvantage that it is necessary with great precision both to rotate the grating and to move it nearer to the slits in order to scan the spectrum. However, it does have the practical advantage that it is much more compact than other mountings, and this is of particular importance when we bear in mind the need to enclose the instrument in a vacuum tank. Ideally, the entrance slit and exit slit or photographic plate should be superimposed if we are to set $\alpha = \beta$. In practice, of course, the two are displaced either sideways, in the plane of incidence as shown in **Figure 5**, or out of the plane of incidence, in which case the entrance slit is positioned below the meridonal plane and the plate holder just above it, as shown in **Figure 5**. The out-of-plane configuration is generally used for spectrographs and the in-plane system for monochromators. The penalty incurred in going out of plane is that coma is introduced in the image, and slit curvature becomes more important. This limits the length of the ruling that can effectively be used.

The second well-known solution to the Rowland equation is the Wadsworth mounting (**Figure 5f**), in which the incident light is collimated, so r is set at infinity and the focal equation reduces to $r_1 = R\cos^2\beta/(\cos\alpha + \cos\beta)$. One feature of this mounting is that the astigmatism is zero when the image is formed at the center of the grating blank, i.e., when $\beta = 0$. It is a particularly useful mounting for applications in which the incident light is naturally collimated (for example, in rocket or satellite astronomy, spectroheliography and in work using synchrotron radiation). However, if the light is not naturally collimated, the Wadsworth mount requires a collimating mirror, so one has to pay the penalty of the extra losses of light at this mirror. The distance from the grating to the image is about half that for a Rowland circle mounting which makes the instrument more compact and, since the grating subtends approximately four times the solid angle, there is a corresponding increase in the brightness of the spectral image.

Not all concave grating mountings are solutions to the Rowland equation. In some cases, other advantages may compensate for a certain defect of focus. A particularly important example of this is the Seya–Namioka mounting (**Figure 5g**), in which the entrance slit and exit slit are kept fixed and the spectrum is scanned by a simple rotation of the grating (**Figure 5g**). In order to achieve the optimum conditions for this mounting, we set $\alpha = \varphi + \theta$ and $\beta = \theta - \varphi$, where 2φ is the angle subtended at the grating by the entrance and exit slit and θ is the angle through which the grating is turned. The amount of defocus is given by:

$$F(\theta,\varphi,r,r_1) = [\cos^2(\theta+\varphi)/r] + [\cos(\theta+\varphi)/R] + [\cos^2(\theta-\varphi)/r_1] + [\cos(\theta-\varphi)/R] \qquad [9]$$

and the optimum conditions are those for which $F(\theta,\varphi,r,r_1)$ remains as small as possible as θ is varied over the required range. Seya set F and three derivatives of F with respect to θ equal to zero for $\theta = 0$ and obtained the result:

$$\varphi = \sin^{-1}(1/\sqrt{3}) = 35°15' \qquad [10]$$

and

$$r = r_1 = R\cos\varphi \qquad [11]$$

which corresponds to the Rowland circle either in zero order or for zero wavelength. In practice, it is usual to modify the angle slightly so that the best focus is achieved in the center of the range of interest rather than at zero wavelength.

The great advantage of the Seya–Namioka mounting is its simplicity. An instrument need consist only of a fixed entrance and exit slit, and a simple rotation of the grating is all that is required to scan the spectrum. It is, in fact, simpler than instruments using plane gratings. Despite the fact that at the ends of the useful wavelength range the resolution is limited by the defect of focus and the astigmatism is particularly bad, the Seya–Namioka mounting is very widely used, particularly for medium-resolution rather than high-resolution work.

A similar simplicity is a feature of the Johnson–Onaka mounting (**Figure 5h**). Here again, the entrance and exit slits remain fixed, but the grating is rotated about an axis which is displaced from its center; in this way, it is possible to reduce the change of focus that occurs in the Seya–Namioka mounting. The system is set up so that at the center of the desired wavelength range, the slits and grating lie on the Rowland circle, as shown in **Figure 5h**. The optimum radius of rotation, i.e., the distance GC, was found by



Figure 6 Ebert mounting of the plane grating designed by Fastie. 'Sl' is the entrance slit; *G* is the grating; *M* is the concave mirror; and *P* is the photographic plate. The horizontal section is at the top and the vertical section is at the bottom. Reproduced with permission from *The Infrared Handbook* (1985) Ann Arbor, MI: Infrared Information Analysis Center.

Onaka to be:

$$\mathrm{GC}_{\mathrm{opt}} = [R \sin\tfrac{1}{2}(\alpha+\beta)]/[1 - \tfrac{1}{2}\tan(\alpha+\beta) \times (\tan\beta - \tan\alpha)] \qquad [12]$$

Another non-Rowland spectrometer is the Ebert–Fastie mount, which mounts the slit, flat grating, and a detector array in the arrangement shown in Figure 6. Ebert first developed the design using two separate concave mirrors, one for collimating the incident beam and the second to focus the diffracted spectrum. Fastie used a single but larger concave mirror, which simplified the mounting structure and produced a rugged, compact spectrometer that has been used in rocket flights and space satellite observatories for astronomical and upper atmospheric applications. The Czerny–Turner mount is similar to the Ebert mount, except the flat grating is located in the same plane that contains the entrance and exit slits.

Advanced Spectrometers

While the above spectrometer designs are still used, major advances in implementation are now available. Ray tracing allows the designer to quantify the aberrations and determine solutions to remove them. Aspheric optic elements can now be fabricated to correct aberrations. Gratings can be ruled on aspherical surfaces to not only disperse the light beam, but also be an element in the optical design. Holography has been developed to etch gratings for use over a wide spectral range and to not only disperse the light, but also work as an optical element. Because holographic gratings are chemically etched, there are no machine burrs to scatter light and the hologram is free of periodic differences in groove widths that create ghosts in ruled gratings. Linear and array photodetectors have replaced film. An advantage of film was its ability to fit curved focal planes. Photodetectors are etched into flat wafers of the photodiode material. To adapt flat arrays to a curved focal plane, fiber optic face plate couplers have been ground on one side to match the focal plane curvature and the flat back side is either optically coupled to the detector or closely coupled for proximity focusing. The photodetector arrays are available in multiple materials to cover the spectral range, from soft X-rays to the thermal infrared. Often cooling is required to obtain low noise. They are now available with sensitivities never reached with film and the ease of coupling the output data to a computer for real-time analysis has taken much of the labor out of analyzing the spectrograph. Another advance is precision motor drives with precision motion sensors, some using laser interferometry, to provide feedback on automated movement of gratings, slits, and detectors as a spectrometer cycles through its wavelength range.

Imaging Spectrometers

Spectrometers that image the spectral characteristics in each pixel of the image to form a data cube, as shown in Figure 7, are named imaging spectrometers, and if the spectra have high resolution and blocks of consecutive neighbors, then the data are called hyperspectral. Imaging spectrometers have several applications that range from medical to remote sensing of land use and environment. This article will cover examples for remote sensing imaging spectrometers which require spectral coverage in all of the atmospheric windows from the UV to thermal IR.

Imaging spectrometers require a combination of spectrometers, light collecting optics, and scan mechanisms to scan the instantaneous field of view of the spectrometer over a scene. Remote sensing of the Earth applications requires an aerial platform. Either a helicopter, an aircraft, or orbital space satellites are used. The platform motion is used as part of the scanning process so that the optics image a single point on the ground so that a scanner (called a line scanner) scans a long line that is cross tracked to the platform motion. Or, the optics image a slit that is parallel to the platform track that covers many scan lines and a scanner moves the slit cross track to the platform motion. This scanner is called a whisk-broom scanner. Or, the optics image a large slit so no scan mechanism is needed other than the platform


Flight line
Cross track scan
Single pixel spectral band
Electromagnetic spectrum
Images taken simultaneously in adjacent spectral bands inherently registered
Visible portion of electromagnetic spectrum
Hydrogen
Helium
Line spectra
Spectral pixel spectral samples
Each spectral sample represents the reflectance in a narrow spectral band
Spectra
Reflectance
Wavelength

Figure 7 Hyperspectral Data Cube. Hyperspectral imagers divide the spectrum into many discrete narrow channels. This fine quantization ofn spectral information on a pixel by pixel basis enables researchers to discriminate the individual constituents in an area much more effectively. For example, the broad spectral bands of a multispectral sensor allow the user only to coarsely discriminate between areas of deciduous and coniferous forest, plowed fields, etc., whereas a hyperspectral imager provides characteristic signatures which can be correlated with specific spectral templates to help determine the individual constituents and possibly even reveal details of the natural processes which are affecting them.


Spectrometer
Diffraction grating
Short wave pass filter (Cooled)
Diffraction grating
Diffraction grating
Imaging lens
Detector array
Detector array
Filter
Long wave pass filter
Imaging lens
Imaging lens
Relay optic
Detector array
Imaging lens
Detector array
(Magnified)
Diffraction grating
Dichroic filter
Dichroic filters
Rotating scan mirror
Folding mirrors
Secondary paraboloid
Primary paraboloid
Field stop
Scan head

EXAMPLE SPECTRAL COVERAGE

Spectro-meter	Spectral range (micrometers)	Channels	Bandwidth (micrometers)
1	0.433–0.833	20	0.02
2	1.15–1.55	8	0.05
3	2.00–2.50	64	0.008
4	8.20–12.70	10	0.40–0.50
Total = 102 channels, expandable to 128 channels			

Figure 8 Multispectral infrared and visible imaging spectrometer optical schematic.

motion to form an image. This scanner is called a pushbroom scanner.

One important requirement is that all spectral measurements of a pixel be coregistered. Most airborne imaging spectrometers use a common aperture for a line scanner, or a slit for whisk and pushbroom scanners, so that platform instability from pitch roll and yaw and from inability to fly in a straight line do not compromise the coregistration of spectral data on each pixel. The image data may require geometric correction, but the spectral data are not compromised.

There is one other type of imaging spectrometer that uses a linear variable filter (also known as a wedge filter) over a 2D array of photodetectors. Each image contains a different spectral band over each row of pixels so that each frame images a scene with a different spectral band over each row of pixels. The array is oriented so the rows of spectral bands are perpendicular to the flight track. After the platform motion moves over one ground pixel, the whole array is read out and the frame is shifted one row of pixels so the second frame adds a second spectral band to each row imaged in the first frame. This frame stepping is carefully timed to the platform velocity and is repeated until each row of pixels is imaged in all spectral bands. This type of imaging spectrometer has been flown in aircraft and satellites. In aircraft, the platform motion corrupts the coregistration of the spectrum in each pixel. Extensive ground processing is required to geometrically correct each frame to improve spectral coregistration. This is a difficult task and this type of imaging spectrometer has lost favor for airborne use. Stabilized satellites have been a better platform and the wedge type of imaging spectrometer has been used successfully in space.

As examples of airborne and ground-based imaging spectrometers, a line scanner imaging

Table 1 MIVIS physical properties

	Height		*Width*		*Depth*^{a}		*Weight*	
	in	*cm*	*in*	*cm*	*in*	*cm*	*lbs*	*kg*
Scan head	26.5	67.0	20.6	52.0	28.1	71.0	220	100
Electronics	40.0	102.0	19.0	48.3	24.0	61.0		
Total system weight (approx.)							460	209

[a] Not including connectors or cable bends.

Table 2 MIVIS spectral coverage (μm)

OPTICAL PORT 1			*OPTICAL PORT 3*						*OPTICAL PORT 4*		
CH #	*Band Edges*		*CH #*	*Band Edges*		*CH #*	*Band Edges*		*CH #*	*Band Edges*	
	Lower	*Upper*		*Lower*	*Upper*		*Lower*	*Upper*		*Lower*	*Upper*
1	0.43	0.45	29	2.000	2.008	61	2.250	2.258	93	8.20	8.60
2	0.45	0.47	30	2.008	2.016	62	2.258	2.266	94	8.60	9.00
3	0.47	0.49	31	2.016	2.023	63	2.266	2.273	95	9.00	9.40
4	0.49	0.51	32	2.023	2.031	64	2.273	2.281	96	9.40	9.80
5	0.51	0.53	33	2.031	2.039	65	2.281	2.289	97	9.80	10.20
6	0.53	0.55	34	2.039	2.047	66	2.289	2.297	98	10.20	10.70
7	0.55	0.57	35	2.047	2.055	67	2.297	2.305	99	10.70	11.20
8	0.57	0.59	36	2.055	2.063	68	2.305	2.313	100	11.20	11.70
9	0.59	0.61	37	2.063	2.070	69	2.313	2.320	101	11.70	12.20
10	0.61	0.63	38	2.070	2.078	70	2.320	2.328	102	12.20	12.70
11	0.63	0.65	39	2.078	2.086	71	2.328	2.336			
12	0.65	0.67	40	2.086	2.094	72	2.336	2.344			
13	0.67	0.69	41	2.094	2.102	73	2.344	2.352			
14	0.69	0.71	42	2.102	2.109	74	2.352	2.359			
15	0.71	0.73	43	2.109	2.117	75	2.359	2.367			
16	0.73	0.75	44	2.117	2.125	76	2.367	2.375			
17	0.75	0.77	45	2.125	2.133	77	2.375	2.383			
18	0.77	0.79	46	2.133	2.141	78	2.383	2.391			
19	0.79	0.81	47	2.141	2.148	79	2.391	2.398			
20	0.81	0.83	48	2.148	2.156	80	2.398	2.406			
OPTICAL PORT 2			49	2.156	2.164	81	2.406	2.414			
21	1.15	1.20	50	2.164	2.172	82	2.414	2.422			
22	1.20	1.25	51	2.172	2.180	83	2.422	2.430			
23	1.25	1.30	52	2.180	2.188	84	2.430	2.438			
24	1.30	1.35	53	2.188	2.195	85	2.438	2.445			
25	1.35	1.40	54	2.195	2.203	86	2.445	2.453			
26	1.40	1.45	55	2.203	2.211	87	2.453	2.461			
27	1.45	1.50	56	2.211	2.219	88	2.461	2.469			
28	1.50	1.55	57	2.219	2.227	89	2.469	2.477			
			58	2.227	2.234	90	2.477	2.484			
			59	2.234	2.242	91	2.484	2.492			
			60	2.242	2.250	92	2.492	2.500			

spectrometer and a ground-based scanned push broom scanner are described below.

MIVIS (multispectral infrared and visible imaging spectrometers) hyperspectral scanner developed by SenSyTech Imaging Group (formerly Daedalus Enterprises) for the CNR (Consiglio National Researche) of Italy is a line scanner imaging spectrometer. The optical schematic is shown in Figure 8. A rotating 45° mirror scans a line of pixels on the ground. Each pixel is collimated by a parabolic mirror in a Gregorian telescope mount. The collimated beam is reflected by a Pfund assembly to an optical bench that houses four spectrometers. An aperture pinhole in the Pfund assembly defines a common instantaneous field of view for each pixel. The collimated beam is then split off with either thin metallic coated or dielectric coated dichroics to four spectrometers. The thin metallic mirrors reflect long wavelengths and transmit short wavelengths. The multiple dielectric layers cause interference such that light is reflected at short wavelengths and transmitted at long wavelengths. After splitting off four wide bands (visible, near infrared, mid-wave infrared, and thermal infrared) each band is dispersed in its own spectrometers.

The wavelength coverage for each spectrometer is based on the wavelength sensitivity of different photodetector arrays. The visible spectrometer uses a silicon photodiode array; the near infrared spectrometer, an InGaAs array, the mid-infrared a InSb array and the thermal infrared, a MCT (mercury doped cadmium teluride) photo-conductor array. Note the beam expander in spectrometer 3 for the

Table 3 LAFS technical specifications

Spatial resolution	1.0 mrad IFOV vertical and horizontal (square pixels). Optical lens for 0.5 mrad IFOV
Spatial coverage	15° TFOV horizontal, nominal. A second, 7.5° TFOV, is an option
Focus range	5′ to infinity
Spectral resolution	5.0 nm per spectral channel, sampled at 2.5 nm interval
Spectral range	400–1100 nm
Dynamic range	8 bit (1 part in 256)
Illumination	Solar illumination ranging from 10:00 a.m. to 2:00 p.m. under overcast conditions to full noon sunshine
Acquisition time	1.5 sec for standard illuminations. Option for longer times for low light level conditions
Viewfinder	Near real time video view of the scene
Calibrations	Flat fielding to compensate for CCD variations in responsivity. Special calibration
Data displays	Single band imagery, selectable Waterfall Chart (one spatial line by spectral, as acquired by the CCD). Single pixel spectral display
Data format	Convertible to format compatible with image processors
Data storage	Replaceable hard disc, 14 data cubes/disk



Figure 9 LAFS system block diagram.

mid-infrared (IR). Since wavelength resolution increases with the size of the illuminated area of a diffraction grating a beam expander was needed to meet the specified mid-IR resolution.

The physical characteristics of MIVIS are given in Table 1 and the spectral coverage in Table 2.

An example of a push broom imaging spectrometer is the large area fast spectrometer (LAFS), which is a field portable, tripod mounted, imaging spectrometer. LAFS uses a push broom spectrometer with a galvanometer driven mirror in front of the entrance slit. The mirror is stepped to acquire a 2D image × 256 spectral bands data cube.

LAFS was developed for the US Marine Corps under the direction of the US Navy Coastal Systems Station of the Dahlgren Division. The technical specifications are shown in Table 3. Various concepts for the imaging spectrometer were studied and the only concept that could meet the above specification was a Littrow configuration grating spectrometer that imaged one line in the scene and dispersed the spectra perpendicular to the line image onto a CCD array. A galvanometer mirror stepped the line image over the scene to generate a spectral image of the scene. A block diagram of LAFS is shown in Figure 9 and a photograph of the prototype in Figure 10. Figure 11 is a photograph of the optical head. Data from a single frame are stored in computer (RAM) memory then transferred to a replaceable hard disk for bulk storage. Data are collected in a series of 256 CCD frames and each CCD frame has a line of 256 pixels along one axis and 256 spectral samples along the second axis. The 256 CCD frames constitute a data cube as shown in Figure 12. This does not allow field viewing of an image in a single spectral band. Earth View™ software is used in the field portable computer



Figure 10 LAFS.


Grating
tilt
adjustments
Spectrometer
focus
stage
lock
Spectrometer
focus
stage
Grating
roll
adjustment
Grating
roll
lock
Attachment point
for spectrometer
adjustment screw (shown detached)
DALSA INC

Figure 11 LAFS optical head.


256 Vertical spatial pixels
256 Spectral pixels
'Water fall' chart
from a single
camera frame
256 Vertical spatial voxels
256 Spectral voxels
256 Horizontal spatial voxels
generated from 256
camera frames
Image data cube,
256 x 256 spatial
by 256 spectral voxels
Each data cube has
256 images of a scene.
one for each of the
256 spectral bands
256 Vertical spatial pixels
256 Horizontal
spatial
pixels
Single spectral
band image display

Figure 12 Arrangement of image memory and construction of image displays.

Table 4 LAFS physical properties

Dimensions and weight	*Size (inches)*	*weight (lbs)*
Optical head	7 × 9 × 8	11
Electronics	12 × 15.5 × 9	30
Battery	4.5 × 16.5 × 2	7
		48 + cables

Power: Less than 150 W at 12 VDC; Battery time – 45 min/charge.

to reorder the data cube into 256 spatial images, one for each spectral band as shown in Figure 12.

The prototype is packaged in two chassis, a compact optical head and a portable electronic chassis. The size, weight, and power are shown in Table 4.

LAFS was designed to also work as an airborne imaging spectrometer. The framing mirror can be locked so it views a scene directly below the aircraft (push broom mode) or the mirror can be programmed to sweep a 256 lines cross track to the aircraft flight path (whisk broom mode). In the whisk broom mode, the scan mirror rotation arc can be increased for a wider field of view than in the push broom mode. LAFS illustrates the decrease in size, weight, and power of a push broom imaging spectrometer that results from a 256 × 256 pixel array rather than single pixel line arrays of a line scanner. The array increases integration time of a line by a factor of 256, which allows longer detector integration dwell time on each pixel and thus smaller light collecting optics.

List of Units and Nomenclature

Data cube	Multiple images of a scene in many spectral bands. The spectra of each pixel can be obtained by plotting the spectral value on the same pixel in each spectral band image.
Pixel	An image point (or small area) defined by the instantaneous-field-of-view of either the optics, entrance aperture or slit, and the detector area, or by some combination of these components. A pixel is the smallest element in a scene that is resolved by the imaging system.
Instantaneous-field-of-view (IFOV)	The IFOV is used in describing scanners to define the size of the smallest field-of-view (usually in milliradians or microradians) that be resolved by a scanner system.
Field-of-view	The total size in angular dimensions of a scanner or imager.
Hyperspectral	A data cube with many (>48) spectral bands.
Line scanners	An optical/mechanical system that scans one pixel at a time along a line of a scene.
Whisk broom	An optical/mechanical system that scans two or more lines at a time.
Push broom	An optical system that images a complete line at a time.

See also

Diffraction: Diffraction Gratings; Fraunhofer Diffraction. **Fiber Gratings**. **Geometrical Optics:** Prisms. **Imaging:** Hyperspectral Imaging; Interferometric Imaging. **Interferometry:** Overview. **Modulators:** Acousto-Optics. **Optical Materials:** Color Filters and Absorption Glasses. **Semiconductor Materials:** Dilute Magnetic Semiconductors; Group IV Semiconductors, Si/SiGe; Large Gap II–VI Semiconductors; Modulation Spectroscopy of Semiconductors and Semiconductor Microstructures. **Spectroscopy:** Fourier Transform Spectroscopy; Raman Spectroscopy.

Further Reading

Baselow R, Silvergate P, Rappaport W, *et al.* (1992) *HYDICE (Hyperspectral Digital Imagery Collection Experiment Instrument Design*. International Symposium on Spectral Sensing Research.

Bianchi, R, Marino, CM and Pignatti, S *Airborne Hyperspectral Remote Sensing in Italy.* Pomezia (Roma), Italy: CNR, Progetto LARA, 00040.

Borough HC, Batterfield OD, Chase RP, Turner RW and Honey FR (1992) *A Modular Wide Field of View Airborne Imaging Spectrometer Preliminary Design Concept*. International Symposium on Spectral Sensing Research.

Carmer DC, Horvath R and Arnold CB (1992) *M7 Multispectral Sensor Testbed Enhancements*. International Symposium on Spectral Sensing Research.

Hackwell JA, Warren DW, Bongiovi RP, *et al.* (1996) LWIR/MWIR Imaging Hyperspectral Sensor for Airborne and Ground-Based Remote Sensing. In: Descour M and Mooney J (eds) *Imaging Spectrometry II*. Proc. SPIE 2819, pp. 102–107.

Hutley MC (1982) *Diffraction Gratings*. London: Academic Press.

James JF and Sternberg RS (1969) *The Design of Optical Spectrometers*. London: Chapman and Hall.

Kulgein NG, Richard SP, Rudolf WP and Winter EM (1992) *Airborne Chemical Vapor Detection Experiment*. International Symposium on Spectral Sensing Research.

Lucey PG, Williams T, Horton K, Hinck K and Buchney C (1994) *SMIFTS: A Cryogenically Cooled, Spatially Modulated, Imaging Fourier Transform Spectrometer for Remote Sensing Applications*. International Symposium on Spectral Sensing Research.

Mourales P and Thomas D (1998) Compact Low-Distortion Imaging Spectrometer for Remote Sensing. *SPIE Conference on Imaging Spectrometry IV* 3438: 31–37.

Pagano TS (1992) *Design of the Moderate Resolution Imaging Spectrometer – NADIR (MODIS-N)*. American Society of Photogrametry & Remote Sensing, pp. 374–385.

Stanich CG and Osterwisch FG (1994) *Advanced Operational Hyperspectral Scanners MIVIS and AHS*. First International Airborne Remote Sensing Conference and Exhibition, Strasbourg, France: Environmental Research Institute of Michigan.

Sun X and Baker JJ (2001) *A Hight Definition Hyperspectral Imaging System*. Proceedings, Fifth International Airborne Remote Sensing Conference and Exhibition, Veridian.

Torr MR, Baselow RW and Torr DG (1982) Imaging Spectrascopy of the Thermosphere from the Space Shuttle. *Applied Optics* 21: 4130.

Torr MR, Baselow RW and Mounti J (1983) An imaging spectrometric observatory for spacelab. *Astrophys. Space Science*. 92: 237.

Vane G, Green RO, Chrien TG, Enmark HT, Hansen EG and Porter WM (1993) The Airborne Visible/Infrared Imaging Spectrometer (AVIRIS). *Remote Sensing of the Environment* 44: 127–143.

Warren CP, Anderson RD, Velasco A, Lin PP, Lucas JR and Speer BA (2001) *High Performance VIS and SWIR Hyperspectral Imagers for Airborne Applications*. Fifth International Conference and Exhibition, Veridian.

Wolfe WL (1997) *Introduction to Imaging Spectrometers*. SPIE Optical Engineering Press.

Wolfe WL and Zisfis GJ (eds) (1985) *The Infrared Handbook*, revised edition. Washington, DC: Office of Naval Research, Department of the Navy.

Zywicki RW, More KA, Holloway J and Witherspoon N (1994) *A Field Portable Hyperspectral Imager: The Large Area Fast Spectrometer*. Proceedings of the International Symposium on Spectral Sensing Research.

Telescopes

M M Roth, Astrophysikalisches Institut Potsdam, Potsdam, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In a broad sense, telescopes are optical instruments which provide an observer with an improved view of a distant object, where improved may be defined in terms of magnification, angular resolution, and light collecting power. Historically, the invention of the telescope was a breakthrough with an enormous impact on fundamental sciences (physics, astronomy), and, as a direct consequence, on philosophy; but also on other technological, economical, political, and military developments. It seems that the first refractive telescopes were built in the Netherlands near the end of the sixteenth century by Jan Lipperhey, Jakob Metius, and Zacharias Janssen. Based on reports of those first instruments, Galileo Galilei built his first telescope, which was later named after him, and made his famous astronomical observations of sunspots, the phases of Venus, Jupiter's moons, the rings of Saturn, and his discovery of the nature of the Milky Way as an assembly of very many stars. The so-called astronomical telescope was invented by Johannes Kepler, who in 1611 also published in *Dioptrice* the theory of this telescope. The disturbing effects of spherical and chromatic aberrations were soon realized by astronomers, opticians, and other users, but it was not before Moor Hall (1792) and John Dollond (1758) that at least the latter flaw was corrected for by introducing the achromat. Later, the achromat was significantly improved by Peter Dollond, Jesse Ramsden, and Josef Fraunhofer. The catadioptric telescope was probably introduced by Lenhard Digges (1571) or Nicolas Zucchius (1608). In 1671, Sir Isaac Newton was the first to use a reflector for astronomical observations. Wilhelm Herschel improved this technique and began in 1766 to build much larger telescopes with mirror diameters up to 1.22 m. When, in the nineteenth century, the conventional metal mirror was replaced by glass, it was Léon Foucauld (1819–1868) who applied a silver coating in order to improve the reflectivity of its surface.

Modern refractors can be built with superb apochromatic corrections, and astronomical reflectors have advanced to mirror diameters of up to 8.4 m (monolithic mirror), and 10 m (segmented mirror).

While the classical definition of a telescope involves an observer, i.e., the eye, in modern times often electronic detectors have replaced human vision. In the following, we will, therefore, use a more general definition of a telescope as an optical instrument, whose purpose is to image a distant object, either in a real focal plane, or in an afocal projection for the observation by eye.

Basic Imaging Theory

In the most simple case, a telescope may be constructed from a single lens or a single mirror, creating a real focal plane. Let us, therefore, introduce some basic principles of imaging using optical elements with spherical surfaces.

Refraction at a Spherical Surface

Figure 1 shows an example of refraction at a spherical surface. A ray emerging from object O hits the surface between two media of refractive index n and n' at point P. After refraction, the ray continues at a deflected angle ε' towards the normal and intersects the optical axis at point O′. In the ideal case, all rays emerging from O at different angles σ are collected in O′, thus forming a real image of object point O in O′. In the paraxial approximation, we have $\sin\sigma = \tan\sigma = \sigma$, and $p \approx 0$. In triangle (O, O′, P): $\sigma' - \sigma = i - i'$. Using Snell's law $ni = n'i'$, we obtain:

$$\sigma' - \sigma = i'\frac{n' - n}{n} \qquad [1]$$

Since $\phi = \sigma' + i'$, and in the paraxial approximation:

$$\sigma' n' - \sigma n = \phi(n' - n) \qquad [2]$$

$$\frac{h}{s'}n' - \frac{h}{s}n = \frac{h}{r}(n' - n) \qquad [3]$$

we obtain finally:

$$\frac{n'}{s'} - \frac{n}{s} = \frac{n' - n}{r} \qquad [4]$$

For an object at infinity, where $s = \infty$, s' becomes the focal distance f':

$$f' = r\frac{n'}{n' - n} \quad \text{and} \quad \tilde{f} = -r\frac{n}{n' - n} \qquad [5]$$

Lenses

Combining two or more refractive surfaces, as in the preceding section, allows us to describe a single lens or more complex optical systems with several lenses in series. For a single lens in air, we just give the lens equation (without deriving it in detail):

$$s_2'(F') = \frac{1}{n - 1}\,\frac{r_2[nr_1 - (n - 1)d]}{(n - 1)d + n(r_2 - r_1)} \qquad [6]$$

where d is the lens thickness, measured between the vertices of its surfaces, r_1, r_2 are the radii of the surfaces, n the index of refraction of the lens material, and $s_2'(F')$ the distance of the object image from the vertex of the last surface, facing the focal plane.

The back focal distance is given by:

$$f' = \frac{1}{n - 1}\,\frac{nr_1r_2}{(n - 1)d + n(r_2 - r_1)} \qquad [7]$$

An important special case is where the lens thickness is small compared to the radii of the lens surfaces, i.e., when $d \ll |r_2 - r_1|$. In this case we can neglect the term of $(n - 1)d$ and write:

$$f' = \frac{1}{n - 1}\,\frac{r_1r_2}{(r_2 - r_1)} \qquad [8]$$

Reflection at a Spherical Surface

Let us now consider the other simple case of imaging object O into O′ by reflection from the concave spherical surface, as depicted in Figure 2. In the paraxial case, we have:

$$\begin{aligned} &\sigma = y/s, \qquad i = \phi - \sigma, \qquad \sigma' = y/s', \\ &i' = \phi - \sigma', \qquad \phi = y/r \end{aligned} \qquad [9]$$



Figure 1 Refraction at a spherical surface between media with refractive indices n and n'.

With $i = -i'$, we obtain:

$$\frac{1}{s'} - \frac{1}{s} = -\frac{2}{r} \tag{10}$$

Again, with $s = \infty$, the focal length becomes:

$$f' = -\frac{r}{2} \tag{11}$$

In what follows, we will now assume that the distance of the object is always large (∞), which, in general, is the situation when a telescope is employed. The image is formed at a surface defined by O′, ideally a focal plane (paraxial case). We will consider deviations from the ideal case below.

Simple Telescopes

As we have observed above, a telescope is in principle nothing but an optical system, which images an object at infinity. In the most simple case, a lens with positive power or a concave mirror will satisfy this condition. The principle of a refractor and a reflecting telescope is shown in Figures 3 and 4. In both cases, parallel light coming from the distant object is entering through the entrance pupil, experiences refraction (reflection) at the lens (mirror), respectively, and is converging to form a real image in the focal plane.

Two point sources, for example two stars in the sky, separated by an angle δ, will be imaged in the focal plane as two spots with separation Δy. When f is the focal length of the telescope, we therefore have:

$$\tan\delta = \frac{\Delta y}{f} \tag{12}$$



Figure 2 Reflection at a spherical surface with radius r.

The so-called plate scale m of the telescope in units of arcsec/mm is given by:

$$m = 3600\,\mathrm{atan}\frac{1}{f} \quad (f \text{ in mm}) \tag{13}$$

In the case of the refractor, we have also shown an eyepiece, illustrating that historically the instrument was invented to enhance the human vision. The eye is located at the position of the exit pupil, thus receiving parallel light, i.e., observing an object at infinity, however (i) with a flux which is increased by a factor A, given by the ratio of the area of the telescope aperture with diameter D to the area of the eye's pupil d with $A = (D/d)^2$, and (ii) with a magnification M of the apparent angle between two separate objects at infinity, which is given by the ratio of the focal lengths of the objective and the eyepiece:

$$\Gamma = \frac{f_{\mathrm{obj}}}{f_{\mathrm{ocl}}} \tag{14}$$

The magnification can also be expressed as the ratio of the diameters of the exit pupil and the entrance pupil:

$$\Gamma = \frac{D_{\mathrm{expup}}}{D_{\mathrm{enpup}}} \tag{15}$$

The first astronomical telescopes with mirrors were equipped with an eyepiece for visual observation. The example in Figure 4 shows a configuration which is more common nowadays for professional astronomical observations, using a direct imaging detector in the focal plane (photographic plate, electronic camera).

Aberrations

Reflector Surfaces

We shall now study the behavior of a real telescope beyond the ideal in the case of a reflector. Figure 5 shows the situation of a mirror, imaging an on-axis



Figure 3 Refractor, astronomical telescope for visual observations with eyepiece (Kepler telescope).



Figure 4 Reflector, astronomical telescope with prime focus imager.



Figure 5 Imaging an object at infinity with reflector.

object at infinity into focus at point O′. With Fermat's principle, the optical paths of all rays forming the image must have identical length l. For all j, we must satisfy:

$$Z_j + f = l \qquad [16]$$

From the geometry in Figure 5, we find also:

$$y_i^2 + (f - Z_j)^2 = l^2 \qquad [17]$$

Combining eqns [16] and [17], we obtain the equation for a surface which satisfies the condition for perfect on-axis imaging:

$$y^2 = -4fz \qquad [18]$$

Obviously only a paraboloid is capable of fulfilling the condition for all rays parallel to the optical axis at whatever separation y. Also, we see that spherical mirrors are less than ideal imagers: rays at increasing distance y from the axis will suffer from increasing path length differences. The effect is called spherical aberration. We will investigate aberrations more quantitatively further below.

Elementary axisymmetrical surfaces can be expressed as follows, with parameter C being the conic constant:

$$y^2 - 2Rz + (1 + C)z^2 = 0 \qquad [19]$$

and the following characteristics:

$C > 0$	ellipsoidal, prolate
$C = 0$	spherical
$-1 < C < 0$	ellipsoidal, oblate
$C = -1$	paraboloidal
$C < -1$	hyperboloidal

Let us now leave the paraxial approximation and determine the focal length of rays which are parallel to, but further away at a distance y from the optical axis. Figure 5 shows the relevant geometrical relations. The intersection of the reflected ray with the optical axis at distance f from the vertex can be found from:

$$f = z + (f - z) \quad \text{where} \quad \frac{y}{f - z} = \tan(2i) \qquad [20]$$

We use the slope of the tangent in point P:

$$\frac{dz}{dy} = \tan i \qquad [21]$$

differentiate eqn [19] to get:

$$\frac{dz}{dy} = \frac{y}{R - (1 + C)z'} \qquad [22]$$

use the trigonometrical relation:

$$\tan 2\phi = \frac{2 \tan \phi}{1 - \tan^2 \phi} \qquad [23]$$

and substitute for tan(2i) in eqn [20] to obtain:

$$f = \frac{R}{2} + \frac{(1 - C)z}{2} - \frac{y^2}{2(R - (1 + C)z)} \qquad [24]$$

In order to express eqn [24] solely in terms of y, we rewrite eqn [19]:

$$z = \frac{R}{1 + C}\left(1 - \sqrt{1 - \frac{y^2}{R^2}(1 + C)}\right) \qquad [25]$$

Expanding z in a series and neglecting any orders higher than 6:

$$z = \frac{y^2}{2R} + (1 + C)\frac{y^4}{8R^3} + (1 - C)^3\frac{y^6}{16R^5} \qquad [26]$$



Figure 6 Transverse spherical aberration.

we obtain finally:

$$f = \frac{R}{2} - \frac{1+C}{4R}y^2 - \frac{(1+C)(3+C)}{16R^3}y^4 \qquad [27]$$

.

Transverse Spherical Aberration

Obviously, for any $C \neq -1$, rays of different distance y to the optical axis are focused at different focal lengths f (spherical aberration). The net effect for a distant point source is that the image is blurred, rather than forming a sharp spot. The lateral deviation of nonparaxial rays intersecting the nominal focal plane at $f_0 = R/2$ is described by the transverse spherical aberration A_{tr} (Figure 6):

$$A_{\mathrm{tr,sph}} = \frac{y}{f-z}(f_0 - f) \qquad [28]$$

Using eqns [19] and [27], one obtains:

$$A_{\mathrm{tr,sph}} = -\frac{1+C}{2R^2}y^3 + \frac{3(1+C)(3+C)}{8R^4}y^5 + \cdots \qquad [29]$$

Angular Spherical Aberration

It is sometimes more convenient to consider the angular spherical aberration, since a telescope is naturally measuring angles between objects at infinity. To this end, we compare an arbitrary reflector surface according to eqn [19] with a reference paraboloid, which is known to be free of on-axis spherical aberration (Figure 7). For any given ray, we observe how the reflected ray under study is tilted towards the reference ray, which would be reflected from the ideal surface of the paraboloid. While the former is measured under an exit angle of $2i$ towards the optical axis (see Figure 5), we designate the latter $2i_{\mathrm{p}}$. The angular spherical aberration is defined as the difference of these two angles:



Figure 7 Angular aberration determined with reference to a paraboloid.

$$A_{\mathrm{ang,sph}} = 2i - 2i_{\mathrm{p}} = 2(i - i_{\mathrm{p}}) \qquad [30]$$

Again, we can use the slope of the tangent to determine the change of angles $i \rightarrow i_{\mathrm{p}}$:

$$A_{\mathrm{ang,sph}} = 2\left(\frac{\mathrm{d}z}{\mathrm{d}y} - \frac{\mathrm{d}z_{\mathrm{p}}}{\mathrm{d}y}\right) = 2\frac{\mathrm{d}}{\mathrm{d}y}\Delta z \qquad [31]$$

It is, therefore, sufficient to consider the difference in z between the surface under study and the reference paraboloid. From eqn [26], we obtain as an approximation to third order:

$$A_{\mathrm{ang,sph}} = -(1+C)\frac{y^3}{R^3} \qquad [32]$$

Aberrations in the Field

Since the use of a telescope exclusively on-axis would be somewhat limited, let us finally investigate the behavior under oblique illumination, i.e., when an object at infinity is observed under an angle Θ towards the optical axis of the system. This will allow us to assess aberrations in the field. For simplicity, we are considering a paraboloid, remembering that on-axis the system is free of spherical aberration. Again, we are employing an imaginary reference paraboloid which is pointing on-axis towards the object at angle Θ (Figure 8). Its coordinate system (O', z', y') is displaced and tilted with regard to the system under study (O, z, y). One can show that the offset Δz, which is used to derive the angular aberration in the same way as above, is given by:

$$2\Delta z = a_1\frac{y^3\Theta}{R^2} + a_2\frac{y^2\Theta^2}{R} + a_3 y\Theta^3 \qquad [33]$$

The angular aberration in the field is then:

$$A_{\mathrm{ang,f}} = 3a_1\frac{y^2\Theta}{R^2} + 2a_2\frac{y\Theta^2}{R} + a_3\Theta^3 \qquad [34]$$

The coefficients are called:

a_1: coma

a_2: astigmatism

a_3: distortion



Figure 8 Aberration in the field, oblique rays.

Chromatic Aberration

So far we have only considered optical aberrations of reflecting telescopes. Spherical aberration in the case of a lens is treated in analogous ways and will not be discussed again. However, the wavelength dependence of the index of refraction in optical media (dispersion) is an important factor and gives rise to chromatic aberrations which are only encountered in refractive optical systems. We can distinguish two principal effects in the paraxial approximation: (i) longitudinal chromatic aberration, resulting in different axial image positions as a function of wavelength; and (ii) lateral chromatic aberration, which can be understood as an aberration of the principal ray as a function of wavelength, leading to a varying magnification as a function of wavelength (plate scale in the case of a telescope).

As an example, let us determine the wavelength dependence of the focal length of a single thin lens. Opticians are conventionally using discrete wavelengths of spectral line lamps of different chemical elements, e.g., the Mercury *e* line at 546.1 nm, Cadmium F' 480.0 nm, or Cadmium C' 643.8 nm, covering more or less the visual wavelength range of the human eye. Differentiation of eqn [8] yields for the wavelength of *e*:

$$\frac{f'}{\mathrm{d}n} = -\frac{1}{(n_e-1)^2}\frac{r_1 r_2}{r_2 - r_1} \qquad [35]$$

Substituting

$$\frac{r_1 r_2}{r_2 - r_1} = f'_e(n_e - 1) \qquad [36]$$

we get:

$$\mathrm{d}f' = -\frac{\mathrm{d}n}{n_e - 1}f'_e \qquad [37]$$

Replacing the differential by the differences $\Delta f' = f'_{F'} - f'_{C'}$ and $\Delta n = n_{F'} - n_{C'}$, then:

$$f'_{F'} - f'_{C'} = -\frac{n_{F'} - n_{C'}}{n_e - 1}f'_e = -\frac{f'_e}{\nu_e} \qquad [38]$$

ν_e is called Abbe's Number:

$$\nu_e = \frac{n_e - 1}{n_{F'} - n_{C'}} \qquad [39]$$

It is a tabulated characteristic value of dispersion for any kind of glass and allows one to quickly estimate the difference in focal length at the extreme wavelengths F' and C' when the nominal focal length of a lens is known as *e*.

Angular Resolution

In the previous sections, we have exclusively employed geometrical optics for the description of telescope properties. With geometrical optics and in the absence of aberrations, there is no limit to the angular resolution of a telescope, i.e., there is no limiting separation angle δ_{lim}, below which two distant point sources can no longer be resolved. However, real optical systems experience diffraction, leading to the finite width of the image of a point source (Airy disk), whose normalized intensity distribution in the focal plane as a function of radius r' from the centroid for the case of a circular aperture of diameter D can be conveniently described by a Bessell function (λ: wavelength, f': focal length of the objective):

$$\frac{I(r)}{I_0} = \left[\frac{2J_1(\nu)}{\nu}\right]^2 \quad \text{where} \quad \nu = \frac{\pi D r'}{\lambda f'} \qquad [40]$$

The intensity distribution is plotted in Figure 9. The first four minima of the diffraction ring pattern are listed in Table 1. Two point sources are defined to be at the resolution limit of the telescope when the maximum of one diffraction pattern happens to coincide with just the first diffraction minimum of the other one (Figure 9, right). As a rule of thumb, the angular resolution is of a telescope with diameter D is given by:

$$\delta_{\min} = 1.22\frac{\lambda}{D} \rightarrow \frac{138}{D} \qquad [41]$$

the latter in units of arcsec for a wavelength of 550 nm and D in mm.



Figure 9 Left: radial intensity distribution of diffraction pattern (Airy disk). Right: two overlapping point source images with same intensity at limiting angular separation δ.

Table 1 Diffraction minima of airy disk

n	ν_n	$r'D/2f'\lambda$
1	3.83	0.61
2	7.02	1.12
3	10.2	1.62
4	13.3	2.12

Types of Telescopes

There are very many different types of telescopes which were developed for different purposes. In order to obtain an impression, we will only briefly introduce a nonexhaustive selection of refractors and reflectors, which by no means is representative of the whole. For a more complete overview, the reader is referred to the literature.

Refractor Objectives

Refractors are first of all characterized by their objectives. Figure 10 shows a sequence of lenses, indicating the progress of lens design developments from left to right. All lenses are groups 2 or 3, designed to compensate for chromatic aberration through optimized combinations of crown and flint glasses. The first lens is a classical C achromat, e.g., using BK7 and SF2 glass, which is essentially the design which was introduced by Hall and Dollond. It is still a useful objective for small telescopes, where a residual chromatic aberration is tolerable. The second lens is the Fraunhofer E type, which is characterized by an air gap between the two lenses (BK7, F2), which helps to optimize the image quality of the system, reducing spherical aberration and coma. As a disadvantage, the two additional glass–air interfaces lead to ghost images (reflected light) and Fresnell losses. The objective is critical with regard to the alignment of tip and tilt. The third example is an improved AS type achromat (KzF2, BK7), which is similar to the E type in



Figure 10 Different types of refractor objectives, from left to right: classical C achromat, Fraunhofer E achromat with air gap, AS achromat, APQ apochromat.

that it also possesses an air gap, however with an improved chromatic aberration correction in comparison to the Fraunhofer objective. The lenses show a more pronounced curvature and are more difficult to manufacture. The beneficial use of KzF2 glass is an example of the successful research for the development of new optical media, which was pursued near the end of the nineteenth century in a collaboration between Otto Schott and Ernst Abbé. The last example is a triplet, employing ZK2, CaF_2, and ZK2. This APQ type of objective is an apochromat, whose chromatic aberration vanishes at 3 wavelengths. It is peculiar for its use of a crystal (calcium fluoride, CaF_2) as the optical medium of the central lens. The manufacture of the CaF_2 lens is critical and expensive, but it provides for an excellent correction of chromatic and spherical aberration of this high quality objective. The triplet is also difficult to manufacture because of the coefficient of thermal expansion, which is roughly different by a factor of two between CaF_2 and the glass. In order to avoid disrupture of the cemented lens group, some manufacturers have used oil immersion to connect the triplet. Since CaF_2 not only has excellent dispersion properties to correct for chromatic aberration, but also exhibits an excellent transmission beyond the visual wavelength regime, this type of lens is particularly useful for applications in the blue and UV.

Finally, Figure 11 shows the complete layout of an astrograph, which is a telescope for use with photographic plates. The introduction of this type of instrument meant an important enhancement of astrophysical research by making available a significantly more efficient method, compared to the traditional visual observation of individual stars, one by one. Using photographic plates, it became possible to measure position and brightness of hundreds and thousands of stars, when previously one could investigate tens. Typical astrographs were built with apertures between 60 and 400 mm, and a field-of-view as large as 15 degrees. Despite the growing importance of space-based observatories for astrometry, some astrographs are still in use today.

Basic Oculars

While the general characteristics of a refractor are dominated by the objective, the eyepiece nevertheless plays an important role for the final appearance to the observer, with an effect on magnification, image quality, chromatism, field of view, and other properties of the entire system. From a large variety of different ocular types, let us briefly consider a few simple examples.



Figure 11 Astrograph.

The first eyepiece in Figure 12 is the one of the Kepler telescope, which was already introduced in Figure 3. It has a quite simple layout with a single lens of positive power. The lens is located after the telescope focal plane at a distance which is equal to the ocular focal length f_oc. The telescope and the ocular focal planes are coinciding, and as a result, the outcoming beam is collimated, forming the system exit pupil after a distance f_oc. This is where ideally the observer's eye is located. The focal plane is creating a real image, which is a convenient location for a reticle. The Kepler telescope is, therefore, a good tool for measurement and alignment purposes. We note that the image is inverted, which is relatively unimportant for a measuring telescope and astronomy, but very annoying for terrestrial use.



Figure 12 Elementary eyepieces after Kepler, Galilei, Huygens, and Ramdsen.

This latter property has been avoided in the next example, which is the ocular of the Galilean telescope, which was built by Galileo and used for his famous observations of planets and moons in the solar system. It uses a single lens, but contrary to the Kepler type with negative power. The lens is located in the telescope beam in front of the focal plane of the objective, which means that the exit pupil is virtual and not accessible to the observer (indicated by dotted lines in Figure 12). The overall length of the telescope is somewhat shorter than Kepler's, however at the expense of the lack of a real focal plane, so no reticle can be applied.

The third example is the 2-lens-ocular of Christian Huygens, who was able to prove with his design that it is possible to correct paraxially the lateral chromatic aberration. The eyepiece is still being built today.

Another elementary ocular is shown in Figure 12, which is the eyepiece after Ramsden. This system is also corrected for lateral chromatic aberration. The real image is formed on the front surface of the second lens, providing a location for a reticle or a scale for measuring purposes. The exit pupil is interior to the ocular. In addition to these selected basic types, there are many more advanced multilens oculars in use today, with excellent correction and large field of view (up to 60°).

Reflectors

Let us now describe several basic types of reflectors (see Figure 13). The first example is the Newton reflector, which uses a flat folding mirror to create an accessible exterior focus. It is conceptually simple and still in use today for amateur astronomy. When the main mirror is a paraboloid, the spherical aberration is corrected on the axis of the system.

The second example represents an important improvement over the simple 1-mirror design of Newton's telescope, in that the combination of a parabolic first mirror (main mirror, M1) with a hyperbolic secondary mirror (M2) eliminates spherical aberration, but not astigmatism and coma. The Cassegrain telescope has a curved focal surface which is located behind the primary mirror. Due to the onset of coma and astigmatism, the telescope has a modest useful field-of-view. Besides the correction properties, the system has significant advantages in terms of mechanical size and weight, playing an important role for the construction of large telescopes. The basic type of this design has practically dominated the construction of the classical large astronomical telescopes with M1 diameters of up to 5 m, and, more recently, the modern 8–10 m class telescopes. On the practical side, the external focus of the Cassegrain on the bottom of the mirror support cell is a convenient location for mounting focal plane instruments (e.g., CCD cameras, spectrographs, and others).



Figure 13 Reflectors, from top to bottom: Newton, Cassegrain, Gregory, Schmidt.

The more common variant of the Cassegrain type, which was actually used for the design of these telescopes, is the layout of Ritchey (1864–1945) and Cretien (1879–1956), which combines two hyperbolic mirrors for M1 and M2 (RCC), but otherwise has the same appearance as the Cassegrain. Besides spherical aberration, it also corrects for coma, giving a useful field-of-view of up to 1°. Like in the case of the Cassegrain telescope, the RCC exhibits some curvature of the focal plane.

Our third example is the Gregory reflector, which also is a 2-mirror system, however with a concave elliptical secondary mirror. The correction of this telescope is similar, but somewhat inferior to the one of the Cassegrain. The use of a concave M2 is advantageous for manufacture and testing. Nevertheless, the excessive length of the system has precluded the use of this layout for large astronomical telescopes, except for stationary beams, for example, in solar observatories.

The last example is the design put forward by Bernhard Schmidt (1879–1935) who wanted to create a telescope with an extremely wide field-of-view. The first telescope of his new type achieved a field-of-view of 16° – something which had not been feasible with previous techniques. The basic idea is to use a fast spherical mirror, and to correct for spherical aberration by means of an aspherical corrector plate in front of the mirror, which also forms the entrance pupil of the telescope. The focal surface is strongly curved, making it necessary to employ a detector with the same radius of curvature (bent photographic plates), or to compensate the curvature by means of a field lens immediately in front of the focus. The presence of the corrector plate and, if used, the field flattener, gives rise to significant chromatism. Nevertheless, the Schmidt telescope was a very successful design and dominated wide-angle survey work in astronomy for many decades.



Figure 14 Principle of prism binoculars with folded beams.

Applications

General Purpose Telescopes

According to the original meaning of the Greek ‘tele–skopein’, the common conception of the telescope is the one of an optical instrument, which provides an enlarged view of distant objects. In addition, a large telescope aperture, compared to the eye, improves night vision and observations with poorly illuminated scenes. There are numerous applications in nautical, security, military, hunting, and other professional areas. For all of these applications, an intuitive vision is important, essentially ruling out the classical astronomical telescope (Kepler telescope, see Figure 3), which produces an inverted image.

Binoculars with Porro prisms are among the most popular instruments with upright vision, presenting a compact outline due to the folded beam geometry (Figure 14), but also single tube telescopes with re-imaging oculars are sometimes used.

Metrology

As we have realized in the introduction, telescopes are instruments which perform a transformation from angle of incidence in the aperture to distances from the origin in the focal plane. If the focal length of the objective is taken sufficiently long, and a high-quality eyepiece is used, very small angles down to the arcsec regime can be visually observed. Telescopes are, therefore, ideal tools to measure angles to very high precision.

In Figure 15 we see a pair of telescopes, facing each other, where one instrument is equipped with a light source, and the other one is used to observe the first one. The first telescope is also called a collimator. It possesses a lamp, a condensor system, a focal plane mask (usually a pinhole, a crosshair, or some other useful pattern imprinted on a transparent plate), and the telescope objective. The focal plane mask is projected to infinity. It can thus be observed with the



Figure 15 Collimator and telescope.

measuring telescope, such that an image of the collimator mask appears in the telescope focal plane. Also the telescope is equipped with a mask in its focal plane, usually with a precision scale or another pattern for convenient alignment with the collimator mask. If now the collimator is tilted by a small angle δ against the optical axis of the telescope, the angle of incidence in the measuring telescope changes by this same amount, giving rise to a shift of the image by $\Delta x = f \tan \delta$. Note that the measurement is completely insensitive to parallel shifts between the telescope and the collimator, since it is parallel light which is transmitted between the two instruments.



Figure 16 Autocollimator.

Another special device, which combines the former two instruments into one, is the Autocollimator. The optical principle is shown in Figure 16: in principle, the autocollimator is identical to a measuring telescope, except that a beamsplitter is inserted between the focal plane and the objective. The beamsplitter is used to inject light from the same kind of light source device as in the normal collimator. The axis of the folded light source beam and of the illuminated collimator mask are aligned to match the focal plane mask of the telescope section: the optical axis of the emerging beam is identical to the optical axis of the telescope. Under this condition, the reflected light from a test object will be exactly centered on the telescope focal plane mask, when it is perfectly aligned to normal incidence. Normally, a high-quality mirror is attached to the device under study, but sometimes also the test object itself possesses a plane surface of optical quality, which can be used for the measurement.

Figure 17 shows schematically an example for such a measurement, where a mirror is mounted on a linear stage carriage for the purpose of measuring the flexure of the stage to very high precision. With a typical length of ≈ 1 m, this task is not a trivial problem for a mechanical measurement.



Figure 17 Using an autocollimator to measuring the flexure of a linear stage.



Figure 18 The 80 cm + 60 cm 'Great Refractor' at the Astrophysical Observatory Potsdam. The correction of the 80 cm objective of this telescope led Johannes Hartmann to the development of the 'Hartmann Test', which was the first quantitative method to measure aberrations. This method is still in use today, and has been further developed to become the 'Shack-Hartmann' technique of wavefront sensing. Courtesy of Astrophysikalisches Institut Potsdam.

By measurement with the autocollimator the tilt of the mirror consecutively for a sufficiently large number of points x_i along the rail, we can now plot the slope of the rail at each point x_i as tan d:

$$\frac{\mathrm{d}y}{\mathrm{d}x} = \tan \delta \qquad [42]$$

Integrating the series of slope values reproduces the shape of the rail $y = f(x)$.

Other applications include multiple autocollimation, wedge measurements, and right angle measurements.

Multiple autocollimation is achieved by inserting a fixed plane-parallel and semi-transparent mirror between the autocollimator and the mirror under study. Light coming from the test mirror will be partially transmitted through the additional mirror towards the autocollimator, and partially reflected back to the test mirror, and so forth. After k reflections, a deflection of $k\delta$ is measured, when δ is the tilt of the test mirror.

The wedge angle α of a plane-parallel plate with refractive index n_w is easily measured by observing the front and back surface reflections from the plate, keeping in mind that the beam bouncing back from the rear will also experience refraction in the plate. If δ is the measured angle difference between the two front and rear beams, then $\alpha = \delta/2n_\mathrm{w}$.

Two surfaces of an object can be tested for orientation at right angles by attaching a mirror to surface 1 and observe the mirror with the fixed autocollimator. In a second step, an auxiliary pentaprism is inserted into the beam, deflecting the light towards surface 2, where the mirror is attached next. If a precision pentaprism is used, any deviation from right angles between the two surfaces is seen as an offset between step 1 and 2.

These are only a few examples of the very many applications for alignment and angle measurements in optics and precision mechanics.

Without going into much detail, we are just mentioning that also the theodolite and sextant make use of the same principle of angular measurements, however without the need of a collimator or autocollimation.

Astronomical Telescopes

Despite its importance as a measurement and testing device for optical technology and manufacture as described in the preceeding paragraph, it is the original invention and subsequent improvement of the telescope for *Astronomy* which is probably the most fascinating application of any optical system known to the general public. The historical development of the astronomical telescope spans from the 17th century Galileian refractor with an aperture of just a few centimeters in diameter, over the largest refractors built for the Lick and Yerkes observatories with objectives of up to ≈ 1 m in diameter (see also Figures 18–20), the 4 m-class reflectors of the second half of the 20th century like e.g. the Hale Observatory 5m, the Kitt Peak and Cerro Tololo 4 m, the La Silla 3.6 m, or the La Palma 4.2 m telescopes (to name only a few), to the current state-of-the-art of 8–10 m class telescopes, prominent examples being the two Keck Observatory 10 m telescopes on Mauna Kea (Hawaii), or the ESO Very Large Observatory (Paranal, Chile), consisting of four identical 8.2 m telescopes (Figures 21–24).

This development has always been driven by the discovery of fainter and fainter celestial objects, whose quantitative study is the subject of modern astrophysics, involving many specialized disciplines such as atom/quantum/nuclear physics, chemistry, general relativity, electrodynamics, hydrodynamics, magneto-hydrodynamics, and so forth. In fact, cosmic objects are often referred to as 'laboratories'



Figure 19 Pistor & Martin Meridian Circle at the former Berlin Observatory in Potsdam Babelsberg. The instrument was one of the finest art telescopes with ultra-high precision for astrometry, built in 1868. Courtesy of Astrophysikalisches Institut Potsdam.



Figure 20 Architect's sketch of historical 'Einsteinturm' solar telescope, Astrophysical Observatory Potsdam. The telescope objective is mounted in the tower structure, facing upward a siderostat which is mounted inside the dome. The light is focused in the basement after deflection from a folding mirror on the slit of a bench-mounted high resolution spectrograph. The telescope represented state-of-the-art technology at the beginning of the twentieth century. Courtesy of Astrophysikalisches Institut Potsdam.



Figure 21 The Very Large Telescope Observatory (VLT) on Mt Paranal, Chile, with VLT Interferometer (VLTI). The four large enclosures are containing the active optics controlled VLT unit telescopes, which are operated either independently of each other, or in parallel to form the VLTI. The structures on the ground are part of the beam combination optics/delay lines. Courtesy of European Southern Observatory.



Figure 22 Total view of Kueyen, one of four unit telescopes of the VLT observatory. Courtesy of European Southern Observatory.

with extreme conditions of density, temperature, magnetic field strength, etc., which would be impossible to achieve in any laboratory on Earth. Except for particles (neutrinos, cosmic rays), gravitational waves, and the physical investigation of meteorites and other solar system material collected by space probes, telescopes (for the entire wavelength range of the electromagnetic spectrum) are the *only* tool to accomplish quantitative measurements of these cosmic laboratories.



Figure 23 8.2 m thin primary mirror for the VLT. The VLT design is based on thin meniscus mirrors, made out of ZERODUR, which have low thermal inertia and which are always kept at ambient temperature, thus virtually removing the effect of thermal turbulence (mirror seeing). Seeing is the most limiting factor of ground-based optical astronomy. The optimized design of the VLT telescopes has introduced a significant leap forward to a largely improved image quality from the ground, and, consequently, improved sensitivity. The thin mirrors are constantly actively controlled in their mounting cells, using numerous piston actuators on the back surface of the mirror. Another key technology under development is 'adaptive optics', a method to compensate atmospheric wavefront deformations in real-time, thus obtaining diffraction limited images. Courtesy of European Southern Observatory.

In an attempt to unravel the history of the birth and evolution of the universe, to discover and to measure the first generation of stars and galaxies, and to find evidence for traces of life outside of planet Earth, plans are currently underway to develop yet another new generation of giant optical telescopes with apertures of 30–100 m in diameter (ELT: extremely large telescope). The technological challenges in terms of precision and stability are outstanding.

Along with the impressive growth of light collecting area, we must stress the importance of angular resolution, which has also experienced a significant evolution over the history of astronomical telescopes: from ≈5 arcsec of the Galilei telescope, which already provided an order of magnitude improvement over the naked eye, over roughly 1 arcsec of conventional telescopes in the 20th century, a few hundredths of an arcsec for the orbiting Hubble Space



Figure 24 Top: spin-cast 8.4 m honeycomb mirror #1 for the Large Binocular Telescope, the largest monolithic mirror of optical quality in the world. Shown in the process of applying a protective plastic coating to the end-polished surface. Bottom: LBT mirror #1, finally mounted in mirror cell. Courtesy of Large Binocular Telescope Observatory.

Telescope (Figure 25), down to milli-arcsec resolution of the Keck and VLT Interferometers. The development of the aforementioned ELTs is thought to be only meaningful if operated in a diffraction-limited mode, using the emerging technique of *adaptive optics*, which is a method to correct for wavefront distortions caused by atmospheric turbulence (image blurr) in real-time.

The combination of large optical/infrared telescopes with powerful detectors and focal plane instruments (*see* **Instrumentation:** Astronomical Instrumentation) has been a prerequisite to make astrophysics one of the most fascinating disciplines of fundamental sciences.

See also

Geometrical Optics: Aberrations. **Imaging:** Adaptive Optics. **Instrumentation:** Astronomical Instrumentation.



Figure 25 Hubble Space Telescope (HST) in orbit. This 2.4 m telescope is probably the most productive telescope which was ever built. Due to the absence of the atmosphere, the telescope delivers diffraction-limited, extremely sharp images, which have revealed unprecedented details of stars, star clusters, nebulae and other objects in the Milky Way and in other galaxies. Among the most spectacular results, HST has provided the deepest look into space ever, revealing light from faint galaxies that was emitted when the universe was only at 10% of its present age. Courtesy of Space Telescope Science Institute, Baltimore.

Further Reading

Bely PY (ed.) (2003) *The Design and Construction of Large Optical Telescopes*. New York: Springer.

Born M and Wolf E (1999) *Principles of Optics*, 7th ed. Cambridge: Cambridge University Press.

Haferkorn H (1994) *Optik*, 3rd ed. Leipzig: Barth Verlagsgesellschaft.

Korsch D (1991) *Reflective Optics*. San Diego: Academic Press.

Laux U (1999) *Astrooptik*, 2nd ed. Heidelberg: Verlag Sterne und Weltraum.

McCray WP (2004) *Giant Telescopes: Astronomical Ambition and the Promise of Technology*. Cambridge: Harvard University Press.

Osterbrock DE (1993) *Pauper and Prince: Richey, Hale, and Big American Telescopes*. Tucson: University of Arizona Press.

Riekher R (1990) *Fernrohre und ihre Meister*, 2nd ed. Berlin: Verlag Technik GmbH.

Rutten HGJ and van Venrooij MAM (1988) *Telescope Optics*. Richmond, VA: Willman-Bell.

Schroeder DJ (1987) *Astronomical Optics*. San Diego: Academic Press.

Welford WT (1974) *Aberrations of the Symmetrical Optical System*. London: Academic Press.

Wilson RN (1996) *Reflecting Telescope Optics I: Basic Design Theory and its Historical Development*. Berlin: Springer.

Wilson RN (1999) *Reflecting Telescope Optics II: Manufacture, Testing, Alignment, Modern Techniques*. Berlin: Springer.

INTERFEROMETRY

Contents

Overview
Gravity Wave Detection
Phase-Measurement Interferometry
White Light Interferometry

Overview

J C Wyant, University of Arizona, Tucson, AZ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Interferometers are a powerful tool used in numerous industrial, research, and development applications, including measuring the quality of a large variety of manufactured items such as optical components and systems, hard disk drives and magnetic recording heads, lasers and optics used in CDs and DVD drives, cameras, laser printers, machined parts, components for fiber optics systems, and so forth. Interferometers can also be used to measure distance, spectra, and rotations, etc. The applications are almost endless.

There are many varieties of interferometers. Some interferometers form interference fringes using two beams and some use multiple beams. Some interferometers are common path; some use lateral shear; some use radial shear; and some use phase-shifting techniques. Examples of the various types are given below, but first we must give the basic equation for two-beam interference.

Two-Beam Interference

When two quasi-monochromatic waves interfere, the irradiance of the interference pattern is given by

$$I = I_1 + I_2 + 2\sqrt{I_1 I_2}\cos[\phi] \qquad [1]$$

where the I's represent the irradiance of the individual beams and ϕ is the phase difference between the two interfering beams. The maximums of the interference occur when $\phi = 2m\pi$, where m is an integer. In most applications involving interferometers, ϕ is the quantity of interest since it is related to the quantity being measured. Figure 1 shows typical two-beam interference fringes.

There are many two-beam interferometers and we will now look at a few of them.

Fresnel Mirrors

Fresnel Mirrors are a very simple two beam interferometer. A beam of light reflecting off two mirrors, set at a slight angle to one another, will produce an interference pattern. The fringes are straight and equally spaced. The fringes become more finely spaced as the angle between the two mirrors increases, d increases, and D becomes smaller (Figure 2).

Plane Parallel Plate

When a monochromatic source illuminates a plane parallel plate, as shown in Figure 3, the interference



Figure 1 Typical two-beam interference fringes.



Figure 2 Fresnel mirrors.



Figure 3 Plane parallel plate interferometer.

fringes are circles centered on the normal to plate. The fringes are called Haidinger fringes, or fringes of equal inclination since, for a given plate thickness, they depend on the angle of incidence. If the maximum or minimum occurs at the center, the radii of the fringes are proportional to the square root of integers. If the plate has a slight variation in thickness and it is illuminated with a collimated beam then the interference fringes are called Fizeau fringes of equal thickness and they give the thickness variations in the plate.

Michelson Interferometer

A Michelson interferometer is shown in Figure 4. Light from the extended source is split into two beams by the beamsplitter. The path difference can be viewed as the difference between the mirror M1 and the image of mirror M2, M2′. With the M1 and M2′ parallel, the fringes are circular and localized at infinity. With M1 and M2′ at a slight angle, the interference fringes are straight lines parallel to the equivalent intersection of the mirrors and localized approximately at the intersection. When the mirrors are only a few wavelengths apart, white light fringes appear, and can be used to determine their coincidence.



Figure 4 Michelson interferometer.



Figure 5 Twyman–Green interferometer for testing a concave spherical mirror.

Twyman–Green Interferometer

If a point source is used in a Michelson interferometer it is generally called a Twyman–Green interferometer. Twyman–Green interferometers are often used to test optical components such as flat mirrors, curved mirrors, windows, lenses, and prisms. Figure 5 shows a Twyman–Green interferometer for the testing of a concave spherical mirror. The interferometer is aligned such that the focus of the diverger lens is at the center of curvature of the spherical mirror. If the mirror under test is perfect, straight equi-spaced fringes are obtained. Figure 6 shows two interference fringes and the relationship between surface height error for the mirror being tested and fringe deviation. λ is the wavelength of the light.

Fizeau Interferometer

The Fizeau interferometer is a simple device used for testing optical surfaces, especially flats and spheres

(Figure 7). The fringes are fringes of equal thickness. It is sometimes useful to tilt the reference surface a little to get several nearly straight interference fringes. The relationship between surface height error and fringe deviation from straightness is the same as for the Twyman–Green interferometer.

Mach–Zehnder Interferometer

A Mach–Zehnder interferometer is sometimes used to look at samples in transmission. Figure 8 shows a typical Mach–Zehnder interferometer for looking at a sample in transmission.


S
Δ(x,y)
Surface height error = $\left(\frac{\lambda}{2}\right)\left(\frac{\Delta}{S}\right)$

Figure 6 Relationship between surface height error and fringe deviation.


Light source
Beamsplitter
Eye
Test surface
Lens
Reference surface

Figure 7 Fizeau interferometer.

Murty Lateral Shearing Interferometer

Lateral shearing interferometers compare a wavefront with a shifted version of itself. While there are many different lateral shear interferometers, one that works very well with a nearly collimated laser beam is a Murty shearing interferometer shown in Figure 9. The two laterally sheared beams are produced by reflecting a coherent laser beam off a plane parallel plate. The Murty interferometer can be used to measure the aberrations in the lens or it can be used to determine if the beam leaving the lens is collimated. If the beam incident upon the plane parallel plate is collimated a single fringe results, while if the beam is not perfectly collimated straight equi-spaced fringes result where the number of fringes gives the departure from collimation.

Radial Shear Interferometer

Radial shear interferometers compare a wavefront with a magnified or demagnified version of itself. While there are many different radial shear


Sample
Imaging lens
Interferogram
Laser
Beamsplitter

Figure 8 Mach–Zehnder interferometer.


Murty shear plate
Source
Collimator lens
Interferogram
Shear = Δx

Figure 9 Murty lateral shear interferometer.

interferometers, one that works very well with a nearly collimated beam is shown in Figure 10. It is essentially a Mach–Zehnder interferometer where, in one arm, the beam is magnified and in the other arm the beam is demagnified. Interference fringes result in the region of overlap. The sensitivity of the interferometer depends upon the amount of radial shear. If the two interfering beams are approximately the same size there is little sensitivity, while if the two beams greatly differ in size there is large sensitivity. Sometimes radial shear interferometers are used test the quality of optical components.

Scatterplate Interferometer

A scatterplate interferometer, invented by Jim Burch in 1953, is one of the cleverest interferometers. Almost any light source can be used and no high-quality optics are required to do precision interferometry. The critical element in the interferometer is the scatterplate which looks like a piece of ground glass, but the important item is that the scattering points are arranged so the plate has inversion symmetry as shown in Figure 11. The light that is scattered the first time through the plate, and unscattered the second time through the plate, interferes with the light unscattered the first time and scattered the second time. The resulting interference fringes show errors in the mirror under test. This type of interferometer is insensitive to vibration because it is what is called a common path interferometer, in that the test beam (scattered–unscattered) and the reference beam (unscattered–scattered) travel along almost the same paths in the interferometer.



Figure 10 Radial shear interferometer.

Smartt Point Diffraction Interferometer

Another common path interferometer used for the testing of optics is the Smartt point diffraction interferometer (PDI) shown in Figure 12. In the PDI the beam of light being measured is focused onto a partially transmitting plate containing a pinhole. The pinhole removes the aberration from the light passing through it (reference beam), while the light passing through the plate (test beam) does not have the aberration removed. The interference of these two beams gives the aberration of the lens under test.

Sagnac Interferometer

The Sagnac interferometer has beams traveling in opposite directions, as shown in Figure 13. The interferometer is highly stable and easy to align. If the interferometer is rotated with an angular velocity there will be a delay between the transit times of the clockwise and the counterclockwise beams. For this reason, the Sagnac interferometer is used in laser gyros.



Figure 11 Scatterplate interferometer.

Fiber Interferometers

Fiber interferometers were first used for rotation sensing by replacing the ring cavity in the Sagnac interferometer with a multiloop made of a single-mode fiber. Fiber-interferometer rotation sensors are attractive as rotation sensors because they are small and low-cost.

Since the optical path in a fiber is affected by its temperature and it also changes when the fiber is stretched, fiber interferometers can be used as sensors for mechanical strains, temperature, and pressure. They can also be used for the measurement of magnetic fields by bonding the fiber to a magneto-restrictive element. Electric fields can be measured by bonding the fiber to a piezoelectric film.

Multiple Beam Interferometers

In general, multiple beam interferometers provide sharper interference fringes than a two beam interferometer. If light is reflected off a plane parallel plate there are multiple reflections. If the surfaces of the plane parallel plate have a low reflectivity, the higher-order reflections have a low intensity and the multiple reflections can be ignored and the resulting interference fringes have a sinusoidal intensity profile, but if the surfaces of the plane parallel plate have a high reflectivity, the fringes become sharper. Figure 14 shows the profile of the fringes for both the reflected and the transmitted light for different values of surface reflectivity. Multiple beam interference fringes are extremely useful for measuring the spectral content of a source. One such multiple beam interferometer, that is often used for measuring spectral distributions of a source, is a Fabry–Perot interferometer that consists of two plane-parallel plates separated by an air space, as shown in Figure 15.



Figure 12 Smartt point diffraction interferometer.



Figure 13 Sagnac interferometer.

Phase-Shifting Interferometry

The equation for the intensity resulting from two-beam interference, contains three unknowns, the two individual intensities and the phase difference between the two interfering beams. If three or more measurements are made of the intensity of the two-beam interference as the phase difference between the two beams is varied in a known manner, all three unknowns can be determined. This technique, called phase-shifting interferometry, is an extremely powerful tool for measuring phase distributions. Generally the phase difference is



Figure 14 Multiple beam interference fringes for the transmitted and reflected light for a plane parallel plate.



Figure 15 Fabry–Perot interferometer.


Laser
Diverger
PBS
QWP
Optical transfer and HOE
CCD
Test mirror
Holographic element
Phase mask, polarizer and sensor array
Four phase-shifted Interferograms on detector

Figure 16 Vibration-insensitive phase-shifting interferometer.

changed by 90 degrees between consecutive measurements of the interference intensity in which case the three intensities can be written as

$$I_a(x,y) = I_1 + I_2 + 2\sqrt{I_1 I_2}\cos(\phi(x,y) - 90°)$$
$$I_b(x,y) = I_1 + I_2 + 2\sqrt{I_1 I_2}\cos(\phi(x,y))$$
$$I_c(x,y) = I_1 + I_2 + 2\sqrt{I_1 I_2}\cos(\phi(x,y) + 90°)$$

and the phase distribution is given by

$$\phi(x,y) = \mathrm{ArcTan}\left(\frac{I_a(x,y) - I_c(x,y)}{-I_a(x,y) + 2I_b(x,y) - I_c(x,y)}\right)$$

Phase-shifting interferometry has greatly enhanced the use of interferometry in metrology since it provides a fast low noise way of getting interferometric data into a computer.

Vibration-Insensitive Phase-Shifting Interferometer

While phase-shifting interferometry has greatly enhanced the use of interferometry in metrology, there are many applications where it cannot be used because of the environment, especially vibration. One recent phase-shifting interferometer that works well in the presence of vibration is shown in Figure 16. In this interferometer, four phase-shifted frames of data are captured simultaneously. The test and reference beams have orthogonal polarization. After the test and reference beams are combined they are passed through a holographic element to produce four identical beams. The four beams are then transmitted through wave retardation plates to cause 0, 90, 180, and 270 phase difference between the test and reference beams. After passing through a polarizer the four phase-shifted interferograms fall on the detector array. Not only can the effects of vibration be eliminated, but by making short exposures to freeze the vibration, the vibrational modes can be measured. Movies can be made showing the vibration. Likewise, flow fields can be measured.

Combining modern electronics, computers, and software with old interferometric techniques, provides for very powerful measurement capabilities.

List of Units and Nomenclature

I	irradiance
R	intensity reflectance
λ	wavelength
ϕ	phase

See also

Coherence: Speckle and Coherence. **Detection:** Fiber Sensors. **Holography, Techniques:** Computer–Generated Holograms; Digital Holography; Holographic Interferometry. **Imaging:** Adaptive Optics; Interferometric Imaging; Wavefront Sensors and Control (Imaging Through Turbulence). **Interferometry:** Phase Measurement Interferometry; White Light Interferometry; Gravity Wave Detection. **Microscopy:** Interference Microscopy. **Tomography:** Optical Coherence Tomography.

Further Reading

Candler C (1951) *Modern Interferometers*. London: Hilger and Watts.

Francon M (1966) *Optical Interferometry*. New York: Academic Press.

Hariharan P (1991) Selected papers on interferometry. *SPIE*, vol. 28.

Hariharan P (1992) *Basics of Interferometry*. San Diego: Academic Press.

Hariharan P (2003) *Optical Interferometry*. San Diego: Academic Press.

Hariharan P and Malacara D (1995) Selected papers on interference, interferometry, and interferometric metrology. *SPIE*, vol. 110.

Malacara D (1990) Selected papers on optical shop metrology. *SPIE*, vol. 18.

Malacara D (1992) *Optical Shop Testing*. New York: Wiley.

Malacara D (1998) *Interferogram Analysis for Optical Testing*. New York: Marcel Decker.

Robinson D and Reid G (1993) *Interferogram Analysis*. Brisol, UK: Institute of Physics.

Steel WH (1985) *Interferometry*. Cambridge: Cambridge University Press.

Tolansky S (1973) *An Introduction to Interferometry*. New York: Longman.

Gravity Wave Detection

N Christensen, Carleton College, Northfield, MN, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In the later part of the nineteenth century Albert Michelson performed extraordinary experiments that shook the foundations of the physics world. Michelson's precise determination of the speed of light was an accomplishment that takes great skill to reproduce today. Edward Morley teamed up with Michelson to measure the velocity of the Earth with respect to the aether. The interferometer that they constructed was exquisite, and through amazing experimental techniques the existence of the aether was disproved. The results of Michelson and Morley led to a revolution in physics, and provided evidence that helped Albert Einstein to develop the general theory of relativity. Now the Michelson interferometer may soon provide dramatic confirmation of Einstein's theory through the direct detection of gravitational radiation.

An accelerating electric charge produces electromagnetic radiation – light. It should come as no surprise that an accelerating mass produces gravitational light, namely gravitational radiation. In 1888 Heinrich Hertz had the luxury to produce and detect electromagnetic radiation in his laboratory. There will be no such luck with gravitational radiation because gravity is an extremely weak force.

Albert Einstein postulated the existence of gravitational radiation in 1916, and in 1989 Joe Taylor and Joel Weisberg indirectly confirmed its existence through observations of the orbital decay of the binary pulsar 1913 + 16. Direct detection of gravity waves will be difficult. For humans to have any chance of detecting gravity waves there must be extremely massive objects accelerating up to relativistic velocities. The only practical sources are astrophysical: supernovae, pulsars, neutron star or black hole binary systems, black hole formation or even the Big Bang. The observation of these types of events would be extremely significant for contributing to knowledge in astrophysics and cosmology. Gravity waves from the Big Bang would provide information about the Universe at its earliest moments. Observations of supernovae will yield a gravitational snapshot of these extreme cataclysmic events. Pulsars are neutron stars that can spin on their axes at frequencies in the hundreds of hertz, and the signals from these objects will help to decipher their characteristics. Gravity waves from the final stages of coalescing binary neutron stars could help to accurately determine the size of these objects and the equation of state of nuclear matter. The observation of black hole formation from these binary systems would be the *coup de grace* for the debate on the existence of black holes, and the ultimate triumph for general relativity.

Electromagnetic radiation has an electric field transverse to the direction of propagation, and a charged particle interacting with the radiation will experience a force. Similarly, gravitational radiation will produce a transverse force on massive objects, a tidal force. Explained via general relativity it is more accurate to say that gravitational radiation will deform the fabric of space-time. Just like electromagnetic radiation there are two polarizations for gravity waves. Let us imagine a linearly polarized gravity wave propagating in the z-direction, $h(z,t) = h_{0+}e^{i(kz-\omega t)}$. The fabric of space is stretched due to the strain created by the gravity wave. Consider a length L_0 of space along the x-axis. In the presence of the gravity wave the length oscillates like

$$L(t) = L_0 + \frac{h_{0+}L}{2}\cos\omega t$$

hence there is a change in its length of

$$\Delta L_x = \frac{h_{0+}L}{2}\cos\omega t$$

A similar length L_0 of the y-axis oscillates, like

$$L(t) = L_0 - \frac{h_{0+}L}{2}\cos\omega t$$

or

$$\Delta L_y = \frac{-h_{0+}L}{2}\cos\omega t$$

One axis stretches while the perpendicular one contracts, and then vice versa, as the wave propagates through. The other polarization ($h_{0\times}$) produces a strain on axes 45° from (x,y). Imagine some astrophysical event produces a gravity wave that has amplitude h_{0+} on Earth; in order to detect a small distance displacement ΔL one should have a detector that spans a large length L. A supernova within our own Galaxy might possibly produce a gravity wave of size $h \sim 10^{-18}$ with characteristic frequencies around

1 kHz, but the occurrence of an event such as this will be extremely rare. More events will come from novae in other galaxies, but due to the great distances and the fact that the magnitude of the gravity wave falls of as $1/r$, such events will be substantially diminished in magnitude.

A Michelson interferometer, with arms aligned along the x- and y- axes, can measure small phase differences between the light in the two arms. Therefore, this type of interferometer can turn the length variations of the arms produced by a gravity wave into changes in the interference pattern of the light exiting the system. This was the basis of the idea from which modern laser interferometric gravitational radiation detectors have evolved. Imagine a gravity wave of amplitude h is incident on an interferometer. The change in the arm length will be $h \sim \Delta L/L_0$, so in order to optimize the sensitivity it is advantageous to make the interferometer arm length L_0 as large as possible. Detectors coming on-line are attempting to measure distance displacements that are of order $\Delta L \sim 10^{-18}$ m or smaller, less that the size of an atomic nucleus! If the interferometers can detect such distance displacements, and directly detect gravitational radiation, it will be one of the most spectacular accomplishments in experimental physics. The first implementation of a laser interferometer to detect a gravity wave was by Forward who used earphones to listen to the motion of the interference signal. The engineering of signal extraction for modern interferometers is obviously far more complex.

Numerous collaborations are building and operating advanced interferometers in order to detect gravitational radiation. In the United States there is the Laser Interferometer Gravity Wave Observatory (LIGO), which consists of two 4-km interferometers located in Livingston, Louisiana and Hanford, Washington. In addition, there is an additional 2-km interferometer within the vacuum system at Hanford. An Italian–French collaboration (VIRGO) has a 3-km interferometer near Pisa, Italy. GEO, a German–British collaboration, is a 600-m detector near Hanover, Germany. TAMA is the Japanese 300-m interferometer in Tokyo. The Australians (AIGO) are constructing a 500-m interferometer in Western Australia. All of the detectors will be attempting to detect gravity waves with frequencies from about 50 Hz to 1 kHz.

As will be described below, there are a number of terrestrial noise sources that will inhibit the performance of the interferometric detectors. The sensitivity of detection increases linearly with interferometer arm length, which implies that there could be advantages to constructing a gravity wave detector in space. This is the goal of the Laser Interferometer Space Antenna (LISA) collaboration. The plan is to deploy three satellites in a heliocentric orbit with a separation of about 5×10^6 km. The launch for LISA is planned for around 2015, and the detector will be sensitive to gravity waves within the frequency range of 10^{-3} to 10^{-1} Hz. Due to the extremely long baseline, LISA is not strictly an interferometer, as most light will be lost as the laser beams expand while traveling such a great distance. Instead, the phase of the received light will be detected and used to lock the phase of the light that is re-emitted by another laser.

Joe Weber pioneered the field of gravitational radiation detection in the 1960s. He used a 1400-kg aluminum cylinder as an antenna. Gravitational waves would hopefully excite the lowest-order normal mode of the bar. Since the gravity wave is a strain on space-time, experimentalists win by making their detectors longer in length. This provides a long-term advantage for laser interferometers, which can scale in length relatively easily. However, as of 2002, interferometers and bars (now cooled to 4 K) have comparable sensitivities.

Interferometer Styles

The Michelson interferometer is the tool to be used to detect a gravitational wave. Figure 1 shows a basic system. The beamsplitter and the end mirrors would be suspended by wires, and effectively free to move in the plane of the interferometer. The arms have lengths L_1 and L_2 that are roughly equal on a kilometer scale. With a laser of power P and wavelength λ incident on the beamsplitter, the light



Figure 1 A basic Michelson interferometer. The photodetector receives light exiting the dark port of the interferometer and hence the signal.

exiting the dark port of the interferometer is

$$P_{\text{out}} = P \sin^2\left[\frac{2\pi}{\lambda}(L_1 - L_2)\right]$$

The interferometer operates with the condition that in the absence of excitation the light exiting the dark port is zero. This would be the case for a simple and basic interferometer. However, interferometers like those in LIGO will be more sophisticated, and will use a heterodyne detection strategy. If E_0 is the amplitude of the electric field from the laser, and assuming the use of a 50–50 beamsplitter, the electric field (neglecting unimportant common phase shifts) for the light incident on the photodetector would be

$$E_{\text{out}} = \frac{E_0}{2}\left(e^{i\delta\phi_1} - e^{i\delta\phi_2}\right) \approx i\frac{E_0}{2}(\phi_1 - \phi_2)$$
$$= iE_0\frac{2\pi}{L}(L_1 - L_2)$$

The laser light will be phase modulated at a frequency in the MHz regime. As such, the deconvolved current from the photodiode that detects light at the interferometer output will be proportional to the phase acquired by the light, namely $I \propto \frac{2\pi}{\lambda}(L_1 - L_2)$.

A gravity wave of optimal polarization normally incident upon the interferometer plane will cause one arm to decrease in length while the other increases. The Michelson interferometer acts as a gravity wave transducer; the change in arm lengths results in more light exiting the interferometer dark port. The mirrors in the interferometer are suspended via wires so that they are free to move under the influence of the gravity wave.

An interferometer's sensitivity increases with arm length, but geographical and financial constraints will limit the size of the arms. If there could be some way to bounce the light back and forth to increase the effective arm length it would increase the detector performance. Fabry–Perot cavities on resonance light have a storage time of $2L/[c(1 - \sqrt{R_1 R_2})]$. Figure 2 shows the system of a Michelson interferometer with Fabry–Perot cavities. This gravity wave interferometer design was proposed and tested in the late 1970s by Ron Drever. The far mirror R_2 has a very high reflectivity ($R_2 \sim 1$) in order to ultimately direct the light back towards the beamsplitter. The front mirror reflectivity R_1 is such that LIGO's effective arm length increases to $L \sim 300$ km. The optical properties of the mirrors of the Fabry–Perot cavities must be exquisite in order to achieve success. LIGO's mirrors were tested, and the root mean squared surface uniformity is less than 1 nm, scattered light is less than 50 parts per million (ppm), absorption is less than 2 ppm, and the radii of curvature for the mirrors are matched to less than 3%. A LIGO test mass (and therefore a Fabry–Perot mirror) can be seen in Figure 3.



Figure 2 A Michelson interferometer with Fabry–Perot cavities in each arm. The front cavity mirrors have reflectivity R_1 while the end mirrors have $R_2 \sim 1$. By using Fabry–Perot cavities LIGO will increase the effective arm length by a factor of 75.



Figure 3 A picture of a mirror and test mass for LIGO. The fused silica component is 10.7 kg in mass and 25 cm in diameter. Photograph courtesy of Caltech/LIGO.

In 1888 Michelson and Morley, with their interferometer, had a sensitivity that allowed the measurement of 0.02 of a fringe, or about 0.126 radian. Prototype interferometers constructed by the LIGO science team have already demonstrated a phase noise spectral density of $\phi(f) = 10^{-10}$ radian/$\sqrt{\text{Hz}}$ for frequencies above 500 Hz. Assuming a 1 kHz signal with 1 kHz bandwidth this implies a phase sensitivity of $\Delta\phi = 3.2 \times 10^{-9}$ radian. This is about the phase sensitivity that LIGO hopes to accomplish in the 4-km Fabry–Perot system. There has been quite an evolution in interferometry since Michelson's time.

The noise sources that inhibit the interferometer performance are discussed below. However, let us



Figure 4 A power recycled Michelson interferometer with Fabry–Perot cavities in each arm. Normally light would exit the interferometer through the light port and head back to the laser. Installation of the recycling mirror with reflectivity R_r sends the light back into the system. A Fabry–Perot cavity is formed between the recycling mirror and the first mirror (R_1) of the arms. For LIGO this strategy will increase the power circulating in the interferometer by a factor of 50.



Figure 5 A signal recycled and power recycled Michelson interferometer with Fabry–Perot cavities in each arm. Normally light containing the gravity wave signal would exit the interferometer through the dark port and head to the photodetector. Installation of the signal recycling mirror with reflectivity R_s sends the light back into the system. The phase of the light acquired from the gravity wave will build up at a particular frequency determined by the reflectivity R_s.

consider one's ability to measure the relative phase between the light in the two arms. The Heisenberg uncertainty relation for light with phase ϕ and photon number N is $\Delta\phi\Delta N \sim 1$. For a measurement lasting time τ using laser power P and frequency f, the photon number is $N = P\lambda\tau/hc$, and with Poisson statistics describing the light $\Delta N = \sqrt{N} = \sqrt{P\lambda\tau/hc}$. Therefore

$$\Delta\phi\Delta N = \frac{2\pi}{\lambda}\Delta L\sqrt{P\lambda\tau/hc} = 1$$

implies that

$$\Delta L = \frac{1}{2\pi}\sqrt{\frac{hc\lambda}{P\tau}}$$

With more light power the interferometer can measure smaller distance displacements and achieve better sensitivity. LIGO will use about 10 W of laser power, and will eventually work towards 100 W. However, there is a nice trick one can use to produce more light circulating in the interferometer, namely power recycling. Figure 4 displays the power recycling interferometer design. The interferometer operates such that virtually none of the light exits the interferometer dark port, and the bulk of the light returns towards the laser. An additional mirror, R_r in Figure 4, recycles the light. For LIGO, recycling will increase the effective light power by another factor of 50. The higher circulating light power therefore improves the sensitivity.

There is one additional modification to the interferometer system that can further improve sensitivity, but only at a particular frequency. A further Fabry–Perot system can be made by installing what is called a signal recycling mirror; this would be mirror R_s in Figure 5. Imagine light in arm 1 on the interferometer that acquires phase as the arm expands due to the gravity wave. The traveling gravity wave's oscillation will subsequently cause arm 1 to contract while arm 2 expands. If the light that was in arm 1 could be sent to arm 2 while it is expanding, then the beam would acquire additional phase. This process could be repeated over and over. Mirror R_s serves this purpose, with its reflectivity defining the storage time for light in each interferometer arm. The storage time defined by the cavity formed by the signal recycling mirror, R_s, and the mirror at the front of the interferometer arm cavity, R_1, determines the resonance frequency. Signal recycling will give a substantial boost to interferometer sensitivity at a particular frequency, and will eventually be implemented in all the main ground-based interferometric detectors.

The LIGO interferometers are infinitely more complex than the relatively simple systems displayed in the figures of this paper. Figure 6 presents an aerial view of the LIGO site at Hanford, Washington. The magnitude of the 4-km system is apparent.



Figure 6 Arial view of the LIGO Hanford, Washington site. The vacuum enclosure at Hanford contains both 2-km and 4-km interferometers. Photograph courtesy of Caltech/ LIGO.

Noise Sources and Interferometer Sensitivity

If the interferometers are to detect distance displacements of order $\Delta L \sim 10^{-18}$ m then they must be isolated from a host of deleterious noise sources. Seismic disturbances should not shake the interferometers. Thermal excitation of components will affect the sensitivity of the detector and should be minimized. The entire interferometer must be in an adequate vacuum in order to avoid fluctuations in gas density that would cause changes in the index of refraction and hence modification of the optical path length. The laser intensity and frequency noise must be minimized. The counting statistics of photons influences accuracy. If ever there was a detector that must avoid Murphy's law this is it; little things going wrong cannot be permitted if such small distance displacements are to be detected. The expected noise sensitivity for the initial LIGO interferometers is displayed in Figure 7.

In the best of all worlds the interferometer sensitivity will be limited by the counting statistics of the photons. A proper functioning laser will have its photon number described by Poisson statistics, or shot noise; if the mean number of photons arriving per unit time is N then the uncertainty is $\Delta N = \sqrt{N}$, which as noted above implies an interferometer displacement sensitivity of

$$\Delta L = \frac{1}{2\pi}\sqrt{\frac{hc\lambda}{P\tau}}$$

or a noise spectral density of

$$\Delta L(f) = \frac{1}{2\pi}\sqrt{\frac{hc\lambda}{P}} \quad \text{(in units of m}/\sqrt{\text{Hz}})$$



Figure 7 The target spectral density of the noise for the initial LIGO system. LIGO will be dominated by seismic noise at low frequencies (10–100 Hz), thermal noise (from the suspension system and internal modes within the mirrors) in the intermediate regime (100–300 Hz), and photon shot noise thereafter. Other sources of noise are also noted, specifically gravity gradients (gravitational excitation of masses from the seismic motion of the ground), radiation pressure of photons on the mirrors, stray (scattered) light, and index of refraction fluctuations from residual gas in the vacuum.

Note also that the sensitivity increases as the light power increases. The reason for this derives from the statistics of repeated measurements. The relative lengths of the interferometer arm lengths could be measured, once, by a photon. However, the relative positions are measured repeatedly with every photon from the laser, and the variance of the mean decreases as $\sqrt{N}$, where N is the number of measurements (or photons) involved. The uncertainty in the difference of the interferometer arm lengths is therefore inversely proportional to photon number, and hence the laser's power. In terms of strain sensitivity this would imply

$$h(f) = \frac{1}{2\pi L}\sqrt{\frac{hc\lambda}{P}} \quad \text{(in units of } 1/\sqrt{\text{Hz}})$$

This assumes the light just travels down the arm and back once. With Fabry–Perot cavities the light is stored, and the typical photon takes many trips back and forth before exiting the system. In order to maximize light power the end mirrors ($R_2 \sim 1$) and the strain sensitivity is improved to

$$h(f) = \frac{1}{2\pi L'}\sqrt{\frac{hc\lambda}{P}}$$

where $L' = 4L/(1 - R_1)$.

As the frequency of gravity waves increases the detection sensitivity will decrease. If the gravity wave causes the interferometer arm length to increase, then decrease, while the photons are still in the arm cavity, then the phase acquired from the gravity wave will be washed away. This is the reason why interferometer sensitivity decreases as frequency increases, and explains the high-frequency behavior seen in Figure 7. Taking this into account, the strain sensitivity is

$$h(f) = \frac{1}{2\pi L'}\sqrt{\frac{hc\lambda}{P}}\left(1 + \left(\frac{2\pi L' f}{c}\right)^2\right)^{1/2}$$

where $L' = 4L/(1 - R_1)$ and f is the frequency of the gravity wave.

If the gravitational wave is to change the interferometer arm length then the mirrors that define the arm must be free to move. In systems like LIGO wires suspend the mirrors; each mirror is like a pendulum. While allowing the mirrors to move under the influence of the gravity wave is a necessary condition, the pendulum itself is the first component of an elaborate vibration isolation system. Seismic noise will be troublesome for the detector at low frequencies. The spectral density of the seismic noise is about $(10^{-7}/f^2)\mathrm{m}/\sqrt{\mathrm{Hz}}$ for frequencies above 1 Hz. A simple pendulum, by itself, acts as a motion filtering device. Above its resonance frequency the pendulum filters motion with a transfer function like $T(f) \propto (f_0/f)^2$. Detectors such as LIGO will have a pendulum with resonant frequencies of about $f_0 \approx 1$ Hz, thus providing an isolation of 10^4 when looking for signals at $f = 100$ Hz. The various gravity wave detector collaborations have different vibration isolation designs. The mirrors in these interferometers will be suspended in elaborate vibration isolation systems, which may include multiple pendulum and isolation stacks. Seismic noise will be the limiting factor for interferometers seeking to detect gravity waves in the tens of hertz range, as can be seen in the sensitivity curve presented in Figure 7.

Due to the extremely small distance displacements that these systems are trying to detect it should come as no surprise that thermal noise is a problem. This noise enters through a number of components in the system. The two most serious thermal noise sources are the wires suspending the mirrors in the pendulum, and the mirrors themselves. Consider the wires; there are a number of modes that can oscillate (i.e. violin modes). At temperature T each mode will have energy of $k_B T$, but distributed over a band of frequencies determined by the quality factor (or Q) of the material. Low-loss (or high-Q) materials work best; for the violin modes of the wires there will be much noise at particular frequencies (in the hundreds of hertz). The mirror is a cylindrical object, which will have normal modes of oscillation that can be thermally excited. The first generation of LIGO will have these masses composed of fused silica, which is typical for optical components. The Qs for the internal modes are greater than 2×10^6. A switch may eventually be made to sapphire mirrors, which have better thermal properties. The limitation to the interferometers' sensitivity due to the thermal noise internal to the mirrors can be seen in Figure 7, and will be a worrying noise source for the first-generation LIGO in the frequency band around 100–400 Hz.

The frequency noise of the laser can couple into the system to produce length displacement sensitivity noise in the interferometer. With arm lengths of 4 km, it will be impossible to hold the length of the two arms absolutely equal. The slightly differing arm spans will mean that the light sent back from each of the two Fabry–Perot cavities will have slightly differing phases. As a consequence, great effort is made to stabilize the frequency of the light entering the interferometer. The LIGO laser can be seen in Figure 8. The primary laser is a Lightwave Model 126 nonplanar ring oscillator. High power is generated from this stabilized laser through the use of optical amplifiers. The beam is sent through four optical amplifiers, and then retro-reflected back



Figure 8 A picture of the Nd:YAG laser and amplifier system that produces 10 W of light for LIGO. Photograph courtesy of Caltech/LIGO.



Figure 9 The optical system for the LIGO system. Light moves from the frequency-stabilized laser to a mode cleaner, and then to the interferometer. Presently 8 W of TEM_{00} laser power is delivered to the interferometer.

through the amplifiers again. For LIGO, the laser is locked and held to a specific frequency by use of signals from a reference cavity, a mode cleaner cavity, and the interferometer. For low-frequency stabilization the temperature of the ring oscillator is adjusted. At intermediate frequencies adjustment is made by signals to a piezo-electric transducer within the ring oscillator cavity. At high frequencies the noise is reduced with the use of an electro-optic crystal. The LIGO lasers currently have a frequency noise of $2 \times 10^{-2}\,\text{Hz}/\sqrt{\text{Hz}}$ at frequencies above 1 kHz.

It will prove important to worry about the stability of the laser power for the interferometric detectors. The hope is to be shot noise limited at frequencies above a few hundred hertz. The Nd:YAG power amplifiers used are pumped with an array of laser diodes, so the light power is controlled through feedback to the laser diodes. The LIGO requirements for the fluctuations on the power P are $\Delta P/P < 10^{-8}/\sqrt{\text{Hz}}$. The spatial quality of the light is ensured through the use of a mode-cleaning cavity. LIGO uses a triangular array of mirrors separated by 15 m. LIGO's input optical system can be seen in Figure 9. The current LIGO optical system yields 8 W of 1.06 μm light in the TEM_{00} mode.

Conclusion

The attempt to measure gravitational radiation with laser interferometers could possibly be the most difficult optical experiment of our time. Over a hundred years ago Michelson succeeded in carrying off experiments of amazing difficulty as he measured the speed of light and disproved the existence of the aether. Gravity wave detection is an experiment worthy of Michelson, and there are hundreds of physicists striving to make it a reality.

Great success has already been achieved. The TAMA 300-m interferometer is operational and has achieved a sensitivity $h(f) = 5 \times 10^{-21}/\sqrt{\text{Hz}}$ in the 700 Hz to 1.5 kHz frequency band. The LIGO interferometers are now operating, and scientists are presently de-bugging the system in order to achieve the target sensitivity. The first scientific data taking for LIGO commenced in 2002, and is continuing at the time of writing.

This will be a new telescope to peer into the heavens. With every new means of looking at the sky there has come unexpected discoveries. Physicists do know that there will be signals that they can predict. Binary systems of compact objects (neutron stars or black holes) will produce chirp signals that may be extracted by matched filtering techniques. A supernova will produce a burst that will hopefully rise above the noise. Pulsars, or neutron stars spinning about their axes at rates sometimes exceeding hundreds of revolutions per second, will produce continuous sinusoidal signals that can be seen by integrating for sufficient lengths of time. Gravity waves produced by the Big Bang will produce a background stochastic noise that can possibly be extracted by correlating the outputs from two or more detectors. These are exciting physics results that will come through tremendous experimental effort.

See also

Imaging: Interferometric Imaging. **Interferometry:** Overview.

Further Reading

Barish BC (1997) Gravitational wave detection. In: Tsubono K, Fujimoto MK and Kurodo K (eds) *Gravitational Wave Detection*, pp. 155–161. Tokyo: Universal Academic.

Blair DG, Taniwaki M, Zhao CN, *et al.* (1997) Progress in the development of technology for advanced laser interferometric gravitational wave detectors. In: Tsubono K, Fujimoto MK and Kurodo K (eds) *Gravitational Wave Detection*, pp. 75–94. Tokyo: Universal Academic.

Brillet A (1997) Virgo status report. In: Tsubono K, Fujimoto MK and Kurodo K (eds) *Gravitational Wave Detection*, pp. 163–173. Tokyo: Universal Academic.

Danzmann K (1997) LISA–A gravitational wave observatory in heliocentric orbit. In: Tsubono K, Fujimoto MK and Kurodo K (eds) *Gravitational Wave Detection*, pp. 111–116. Tokyo: Universal Academic.

Drever RWP, Ford GM, Hough J, *et al.* (1980) A gravity-wave detector using optical cavity sensing. In: Schmutzer E (ed.) *Proceedings of the Ninth International Conference on General Relativity and Gravitation*, pp. 265–267. Berlin: Springer.

Forward RL (1978) Wideband laser-interferometer gravitational-radiation experiment. *Physical Review* D17: 379.

Hough J and the GEO 600 Team (1997) GEO 600 Current status and some aspects of the design. In: Tsubono K, Fujimoto MK and Kurodo K (eds) *Gravitational Wave Detection*, pp. 175–182. Tokyo: Universal Academic.

Robertson NA (2000) Laser interferometric gravitational wave detectors. *Classical Quantum Gravity* 17: R19–R40.

Saulson PR (1994) Fundamentals of Interferometric Gravitational Wave Detectors. Singapore: World Scientific.

Taylor JH and Weisberg JM (1989) Further experimental tests of relativistic gravity using the binary pulsor PSR 1913 + 16. *Astrophysical Journal* 345: 434–450.

Thorne KS (1987) Gravitational radiation. In: Hawking S and Isreal W (eds) *300 Years of Gravitation*, pp. 330–458. Cambridge, UK: Cambridge University Press.

Tsubono K and the TAMA collaboration (1997) TAMA Project, Gravitational wave detection. In: Tsubono K, Fujimoto MK and Kurodo K (eds) *Gravitational Wave Detection*, pp. 183–191. Tokyo: Universal Academic.

Weiss R (1972) Electromagnetically coupled broadband gravitational antenna. *MIT Quarterly Progress Report* no. 105.

Phase-Measurement Interferometry

K Creath, Optineering and University of Arizona, Tucson, AZ, USA

J Schmit, Veeco Instruments, Inc., Tucson, AZ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Phase-measurement interferometry is a way to measure information encoded in interference patterns generated by an interferometer. Fringe patterns (fringes) created by interfering beams of light are analyzed to extract quantitative information about an object or phenomenon. These fringes are localized somewhere in space and require a certain degree of spatial and temporal coherence of the source to be visible. Before these techniques were developed in the late 1970s and early 1980s, fringe analysis was done either by estimating fringe deviation and irregularity by eye or by manually digitizing the centers of interference fringes using a graphics tablet. Digital cameras and desktop computers have made it possible to easily obtain quantitative information from fringe patterns. The techniques described in this article are independent of the type of interferometer used.

Interferometric techniques using fringe analysis can measure features as small as a micron wide or as large as a few meters. Measurable height ranges vary from a few nanometers up to 10s of mm, depending upon the interferometric technique employed. Measurement repeatability is very consistent, and typically repeatability of 1/100 rms of a fringe is easily obtainable while 1/1000 rms is possible. Actual measurement precision depends on what is being measured and how the technique is implemented, while accuracy depends upon comparison to a sanctified standard.

There are many different types of applications for fringe analysis. For example, optical surface quality can be determined using a Twyman–Green or Fizeau interferometer. In addition, wavefront quality measurements of a source or an optical system can be made in transmission, and the index of refraction and homogeneity of optical materials can be mapped out. Many nonoptical surfaces can also be measured. Typically, surface topography information at some specific spatial frequency scale is extracted. These measurements are limited by the resolution of the optical system and the field of view of the imaging system. Lateral and vertical dimensions can also be measured. Applications of nonoptical surfaces include disk and wafer flatness, roughness measurement, distance and range sensing. Phase measurement techniques used in holographic interferometry, TV holography, speckle interferometry, moiré, grating interferometry, and fringe projection are used for nondestructive testing to measure surface structure as well as displacements due to stress and vibration. This article outlines the basics of phase measurement interferometry (PMI) techniques as well as the types of algorithms used. The bibliography lists a number of references for further reading.

Background

Basic Parts of a Phase-Measuring Interferometer

A phase-measuring interferometer consists of a light source, an illumination system (providing uniform illumination across the test surface), a beamsplitter (usually a cube or pellicle so both beams have the same optical path), a reference surface (needs to be good because these techniques measure the difference between the reference and test surface), a sample fixture, an imaging system (images a plane in space where the surface is located onto the camera), a camera (usually a monochrome CCD), an image digitizer/frame grabber, a computer system, software (to control the measurement process and calculate the surface map), and often a spatial or temporal phase shifter to generate multiple interferograms.

Steps of the Measurement Process

To generate a phase map, a sample is placed on a sample fixture and aligned, illumination levels are adjusted, the sample image is focused onto the camera, the fringes are adjusted for maximum contrast, the phase shifter or fringe spacing is adjusted or calibrated as necessary, a number of images is obtained and stored with the appropriate phase differences, the optical path difference (OPD) is calculated as the modulo 2π phase and then is unwrapped at each pixel to determine the phase map.

To make consistent measurements, some interferometers need to be on vibration isolation systems and away from heavy airflows or possible acoustical coupling. It helps to cover any air paths that are longer than a few millimeters. Consideration needs to be made for consistency of temperature and humidity.

The human operating the interferometer is also a factor in the measurement. Does this person always follow the same procedure? Are the measurements sampled consistently? Are the test surfaces clean? Is the sample aligned the same and correctly? Many different factors can affect a measurement. To obtain repeatable measurements it is important to have a consistent procedure and regularly verify measurement consistency.

Common Interferometer Types

One of the most common interferometers used in optical testing is the Twyman–Green interferometer (Figure 1). Typically, a computer controls a mirror pushed by a piezo-electric transducer (PZT). The test surface is imaged onto the camera and the computer has a frame grabber that takes frames of fringe data.



Figure 1 Twyman–Green interferometer.

The most common commercially available interferometer for optical testing is the Fizeau interferometer (Figure 2). This versatile instrument is very insensitive to vibrations due to the large common path for both interfering wavefronts. The reference surface (facing the test object) is moved by a PZT to provide the phase shift.

Interference microscopes (*see* **Microscopy:** Interference Microscopy. **Interferometry:** White Light Interferometry) are used for looking at surface roughness and small structures (see Figure 3). These instruments can employ Michelson, Mirau, and Linnik interference objectives with a laser or white light source, or Fizeau-type interference objectives that typically use a laser source because of the unequal paths in the arms of the interferometer. The phase shift is accomplished by moving the sample, the reference surface, or parts of the objective relative to the sample. Figure 3 shows a schematic of a Mirau-type interferometric microscope for phase measurement.



Figure 2 Fizeau interferometer.



Figure 3 Mirau interference microscope.

Determination of Phase

The Interference Equation

Interference fringes from a coherent source (e.g., a laser) are theoretically sinusoidal (Figure 4a), while fringes from an incoherent source (e.g., white light) are localized in a wavepacket at a point in space (Figure 4b) where the optical paths of the arms of the interferometer are equal and marked on Figure 4 as scanner positions $z = 0$ (*see* **Interferometry:** White Light Interferometry). For generality, this analysis considers the determination of phase within the wave packet for fringes localized in space.

Interference fringes at any point in the wavepacket can be written in the following form:

$$I(x, y) = I_0\{1 + \gamma(x, y, z)\cos[\phi(x, y)]\} \qquad [1]$$

where I_0 is the dc irradiance, γ is the fringe visibility (or contrast), $2I_0\gamma$ is the modulation (irradiance amplitude or the ac part of the signal), and ϕ is the phase of the wavefront as shown in Figure 5. For simplicity, this drawing assumes that the interference fringe amplitude is constant.

Fringe visibility can be determined by calculating

$$\gamma = \frac{I_{\max} - I_{\min}}{I_{\max} + I_{\min}} \qquad [2]$$

where $I_{\max}$ is the maximum value of the irradiance for all phase values and $I_{\min}$ is the minimum value. The fringe visibility has a real value between 0 and 1 and varies with the position along the wavepacket. The fringe visibility, as defined here, is the real part of the complex degree of coherence.

Types of Phase Measurement Techniques

Phase can be determined from either a number of interference fringe patterns or from a single interferogram with appropriate fringe spacing. Temporal techniques require an applied phase shift between the test and reference beams as a function of time while multiple frames of interference fringe data are obtained. Spatial techniques can obtain data from a single interferogram that requires a carrier pattern of almost straight fringes to either compare phases of adjacent pixels or to separate orders while performing operations in the Fourier domain. Spatial techniques may also simultaneously record multiple interferograms with appropriate relative phase shift differences separated spatially in space. Multiple frame techniques require more data than single frame techniques. Temporal techniques require that the interference fringes be stable over the time period it takes to acquire the number of images. While single-frame spatial techniques require less data and can be done with a single image, they generally have a reduced amount of resolution and less precision than temporal techniques.

There are literally hundreds of algorithms and techniques for extracting phase data from interference fringe data. The references listed in the Further Reading offer more details of these techniques.

Temporal Phase Measurement

Temporal techniques use data taken as the relative phase between the test and reference beams is modulated (shifted). The phase (or OPD) is calculated at each measured point in the interferogram. As the phase shifter is moved, the phase at a single point in the interferogram changes. The effect looks like the fringes are moving across the interferogram, and because of these techniques are sometimes called fringe scanning or fringe shifting techniques. However, the fringes are not really moving; rather the irradiance at a single detector point is changing (hopefully sinusoidally) in time (see Figure 6). A 180° or π phase causes a bright fringe to become a dark fringe.

Phase Modulation Techniques

There are many ways to introduce a phase modulation (or shift). These include moving a mirror or the



(a) Coherent source

(b) Incoherent source

Figure 4 Interference fringes for coherent and incoherent sources as observed at point $x, y, z = 0$ corresponds to equal optical path lengths of the reference and object beams.

sample, tilting a glass plate, moving a diffraction grating, rotating a polarizer, analyzer, or half-wave plate, using a two-frequency (Zeeman) laser source, modulating the source wavelength, and switching an acousto-optic Bragg cell, or magneto-optic/electro-optic cell. While any of these techniques can be used for coherent sources, special considerations need to be made for temporally incoherent sources (*see* **Interferometry:** White Light Interferometry). Figure 7 shows how moving a mirror introduces a relative phase shift between object and reference beams in a Twyman–Green interferometer.

Extracting Phase Information

Including the phase shift, the interference equation is written as

$$I(x,y) = I_0(x,y)\{1+\gamma_0(x,y)\cos[\phi(x,y)+\alpha(t)]\} \quad [3]$$

where $I(x,y)$ is the irradiance at a single detector point, $I_0(x,y)$ is the average (dc) irradiance, $\gamma_0(x,y)$ is the fringe visibility before detection, $\phi(x,y)$ is the phase of the wavefront being measured, and $\alpha(t)$ is the phase shift as a function of time.



Figure 5 Variable definitions for interference fringes.


No phase shift (0°) π/2 phase shift (90°) π phase shift (180°)

Figure 6 Interference fringe patterns corresponding to different relative phase shifts between test and reference beams.



Figure 7 Moving a mirror to shift relative phase by λ/4.

Since the detector has to integrate for some finite time, the detected irradiance at a single point becomes an integral over the integration time Δ (Figure 8) where the average phase shift for the ith frame of data is α_i:

$$I_i(x,y) = \frac{1}{\Delta}\int_{\alpha_i-(\Delta/2)}^{\alpha_i+(\Delta/2)} I_0(x,y)\{1+\gamma_0(x,y) \times \cos[\phi(x,y)+\alpha(t)]\}\,\mathrm{d}\alpha(t) \quad [4]$$

After integrating over $\alpha(t)$, the irradiance of the detected signal becomes

$$I_i(x,y) = I_0(x,y)\left\{1+\gamma_0(x,y)\,\mathrm{sinc}\left(\frac{\Delta}{2}\right) \times \cos[\phi(x,y)+\alpha_i]\right\} \quad [5]$$

where $\mathrm{sinc}(\Delta/2) = \sin(\Delta/2)/(\Delta/2)$, which reduces the detected visibility.

Ramping Versus Stepping

There are two different ways of shifting the phase; either the phase shift can be changed in a constant and linear fashion (ramping) (see Figure 8) or it can be stepped in increments. Ramping provides a continuous smooth motion without any jerking motion. This option may be preferred if the motion does not wash out the interference fringes. However, ramping requires good synchronization of the camera/digitizer and the modulator to get the correct OPD (or phase) changes between data frames. Ramping allows faster data taking but requires electronics that are more sophisticated. In addition, it takes a finite time for a mass to move linearly. When ramping, the first frame or two of data usually needs to be discarded because the shift is not correct until the movement is linear.

The major difference between ramping and stepping the phase shift is a reduction in the modulation of the interference fringes after detection (the sinc(Δ/2) term in eqn [5]). When the phase shift is stepped ($\Delta = 0$), the sinc term has a value of one. When the phase shift is ramped ($\Delta = \alpha$) for a phase



Figure 8 Change in OPD integrating over a Δ phase shift with sample separation α.

shift of $\alpha = 90° = \pi/2$, this term has a value of 0.9. Therefore, ramping slightly reduces the detected fringe visibility.

Signal Modulation

Phase measurement techniques assume that the irradiance of the interference fringes at the camera covers as much of the detector's dynamic range as possible and that the phase of the interference fringe pattern is modulating at each individual pixel as the phase between beams is modulated. If the irradiance at a single detector point does not modulate as the relative phase between beams is shifted, the height of the surface cannot be calculated. Besides the obvious reductions in irradiance modulation due to the detector sampling and pixel size or a bad detector element, scattered light within the interferometer, and defects or dirt on the test object, can also reduce signal modulation. Phase measurement techniques are designed to take into account the modulation of the signal at each pixel. If the signal does not modulate enough at a given pixel, then the data at that pixel are considered unusable, flagged as 'bad' and are often left blank. Phase values for these points may be interpolated from surrounding pixels if there are sufficient data.

Three-Frame Technique

The simplest method to determine phase uses three frames of data. With three unknowns, three sets of recorded fringe data are needed to reconstruct a wavefront providing a phase map. Using phase shifts of $\alpha_i = \pi/4$, $3\pi/4$, and $5\pi/4$, the three fringe measurements at a single point in the interferogram may be expressed as

$$\begin{aligned} I_1 &= I_0\left[1 + \gamma\cos\left(\phi + \frac{\pi}{2}\right)\right] \\ &= I_0\left[1 + \frac{\sqrt{2}}{2}\gamma(\cos\phi - \sin\phi)\right] \end{aligned} \qquad [6]$$

$$\begin{aligned} I_2 &= I_0\left[1 + \gamma\cos\left(\phi + \frac{3\pi}{2}\right)\right] \\ &= I_0\left[1 + \frac{\sqrt{2}}{2}\gamma(-\cos\phi - \sin\phi)\right] \end{aligned} \qquad [7]$$

$$\begin{aligned} I_3 &= I_0\left[1 + \gamma\cos\left(\phi + \frac{5\pi}{2}\right)\right] \\ &= I_0\left[1 + \frac{\sqrt{2}}{2}\gamma(-\cos\phi + \sin\phi)\right] \end{aligned} \qquad [8]$$

Note that (x, y) dependencies are still implied. The choice of the specific phase shift values is to make the math simpler. The phase at each detector point is

$$\phi = \tan^{-1}\left(\frac{I_3 - I_2}{I_1 - I_2}\right) \qquad [9]$$

In most fringe analysis techniques, we are basically trying to solve for terms such that we end up with the tangent function of the phase. The numerator and denominator shown above are respectively proportional to the sine and cosine of the phase. Note that the dc irradiance and fringe visibility appear in both the numerator and denominator. This means that variations in fringe visibility and average irradiance from pixel to pixel do not affect the results. As long as the fringe visibility and average irradiance at a single pixel is constant from frame to frame, the results will be good. If the different phase shifts are multiplexed onto multiple cameras, the results will be dependent upon the gain of corresponding pixels.

Bad data points with low signal modulation are determined by calculating the fringe visibility at each data point using:

$$\gamma = \frac{\sqrt{(I_3 - I_2)^2 + (I_1 - I_2)^2}}{\sqrt{2}I_0} \qquad [10]$$

It is simpler to calculate the ac signal modulation $(2I_0\gamma)$ and then set the threshold on the modulation to a typical value of about 5–10% of the dynamic range. If the modulation is less than this value at any given data point, the data point is flagged as bad. Bad points are usually caused by noisy pixels and can be due to scratches, pits, dust and scattered light.

Although three frames of data are enough to determine the phase, this and other 3-frame algorithms are very sensitive to systematic errors due to nonsinusoidal fringes or nonlinear detection, phase shifter miscalibration, vibrations and noise. In general, the larger the number of frames of data used to determine the phase, the smaller the systematic errors.

Phase Unwrapping

The removal of phase ambiguities is generally called phase unwrapping, and is sometimes known as integrating the phase. The phase ambiguities owing to the modulo 2π arctangent calculation can simply be removed by comparing the phase difference between adjacent pixels. When the phase difference between adjacent pixels is greater than π, a multiple of 2π is added or subtracted to make the difference less than π. For the reliable removal of



(a) Fringes for concave surface



(b) Wrapped phase



(c) Unwrapped phase

Figure 9 Fringes, wrapped, and unwrapped phase maps.

discontinuities, the phase must not change by more than π ($\lambda/2$ in optical path (OPD)) between adjacent pixels. Figure 9 shows an example of wrapped and unwrapped phase values.

Given a trouble-free wrapped phase map, it is enough to search row by row (or column by column) for phase differences of more than π between neighboring pixels. However, fringe patterns usually are not perfect and are affected by systematic errors. Some of the most frequently occurring error sources are noise, discontinuities in the phase map, violation of the sampling theorem and invalid data points (e.g., due to holes in the object or low modulation regions). Some phase maps are not easily unwrapped. In these cases different techniques like wave packet peak sensing in white light interferometry are used.



Figure 10 Angles of illumination and viewing.

From Wavefront to Surface

Once the phase of the wavefront is known, surface shape can be determined from the phase map. Surface height H of the test surface relative to the reference surface at a location (x, y) is given by

$$H(x, y) = \frac{\phi(x, y)\lambda}{2\pi(\cos\theta + \cos\theta')} \qquad [11]$$

where λ is the wavelength of illumination, and θ and θ' – the angles of illumination and viewing with respect to the surface normal – are shown in Figure 10. For interferometers (e.g., Twyman–Green or Fizeau) where the illumination and viewing angles are normal to the surface ($\theta = \theta' = 0$), the surface height is simply:

$$H(x, y) = \frac{\lambda}{4\pi}\phi(x, y) \qquad [12]$$

Since the wavefront measured represents the relative difference between the interfering reference and test wavefronts, this phase map only directly corresponds to the surface under test when the reference wavefront is perfectly flat. In practice, the shape of the reference surface needs to be accounted for by measuring it using a known test surface and subtracting this reference measurement from subsequent measurements of the test surface.

Phase Change on Reflection

Phase shifting interferometry measures the phase of reflected light to determine the shape of objects. The reflected wavefront will represent the object surface (within a scaling factor) if the object is made of a single material. If the object is comprised of multiple materials that exhibit different phase changes on reflection, the measured wavefront needs to be corrected for these phase differences (*see* **Interferometry:** White Light Interferometry).

Overview of Phase Measurement Algorithms and Techniques

There are literally hundreds of published algorithms and techniques. The optimal algorithm depends on the application. Most users prefer fast algorithms using a minimal amount of data that are as accurate and repeatable as possible, immune to noise, adaptable, and easy to implement. In practice, there are trade-offs that must be considered when choosing a specific algorithm or technique. This section provides an overview of the types of algorithms to aid the reader in sifting through published algorithms.

Synchronous Detection

One of the first techniques for temporal phase measurement utilized methods of communication theory to perform synchronous detection. To synchronously detect the phase of a noisy sinusoidal signal, the signal is first correlated (or multiplied) with sinusoidal and cosinusoidal reference signals (signals in quadrature) of the same frequency and then averaged over many periods of oscillation. This method of synchronous detection as applied to phase measurement can be extracted from the least squares estimation result when the phase shifts are chosen such that N measurements are equally spaced over one modulation period. With phase shifts α_i such that:

$$\alpha_i = \frac{2\pi}{N} i, \qquad \text{with } i = 1, \ldots, N \tag{13}$$

the phase can be calculated from

$$\phi(x, y) = \tan^{-1}\left[\frac{\sum I_i(x, y)\sin\alpha_i}{\sum I_i(x, y)\cos\alpha_i}\right] \tag{14}$$

Note that N can be any number of frames (or samples). The more frames of data, the smaller the systematic errors. This technique does not take large amounts of memory for a large number of frames, because only the running sums of the fringes multiplied by the sine and cosine of the phase shift need to be remembered. The 4-frame algorithm from Table 1 is an example of a direct adaptation of synchronous detection where simple values of 1, -1 or 0 for every $\pi/2$ phase shift can be assigned to the sine and cosine functions.

Algorithm Design

In the last ten years, a lot of work has been done to generalize the derivation of fringe analysis algorithms. This work has enabled the design of algorithms for specific applications, which are insensitive to specific systematic error sources.

Table 1 Sampling function weights for a few selected algorithms

N frames	*Phase shift*	*Coefficients*
3	$\frac{\pi}{2}$	$\frac{1, -1, 0}{0, 1, -1}$
4	$\frac{\pi}{2}$	$\frac{0, -1, 0, 1}{1, 0, -1, 0}$
5	$\frac{\pi}{2}$	$\frac{0, -2, 0, 2, 0}{1, 0, -2, 0, 1}$
7	$\frac{\pi}{3}$	$\frac{\sqrt{3}[0, 1, 1, 0, -1, -1, 0]}{-1, -1, 1, 2, 1, -1, -1}$
8	$\frac{\pi}{2}$	$\frac{1, 5, -11, -15, 15, 11, -5, -1}{1, -5, -11, 15, 15, -11, -5, 1}$
12	$\frac{\pi}{3}$	$\frac{\sqrt{3}[0, -3, -3, 3, 9, 6, -6, -9, -3, 3, 3, 0]}{2, 1, -7, -11, -1, 16, 16, -1, -11, -7, 1, 2}$

Most algorithms use polynomials for the numerator and denominator. Given fringe data:

$$I_i = I_0[1 + \gamma\cos(\phi + \alpha_i)] \tag{15}$$

the phase is calculated using

$$\phi = \tan^{-1}\left[\frac{\sum_i n_i I_i}{\sum_i d_i I_i}\right] \tag{16}$$

The numerator and denominator of the arctangent argument are both polynomials. The numerator is a sum proportional to the sine (imaginary part) and the denominator is a sum proportional to the cosine (real part),

$$\text{num} = 2kI_0\gamma\sin\alpha_i = \sum_i n_i I_i \tag{17}$$

$$\text{den} = 2kI_0\gamma\cos\alpha_i = \sum_i d_i I_i \tag{18}$$

where the constant k depends on the values of coefficients. From this the fringe visibility is given by

$$\gamma = \frac{\sqrt{(\text{num})^2 + (\text{den})^2}}{2kI_0} \tag{19}$$

The coefficient vectors for the numerator and denominator are window functions. For an algorithm such as the 4-frame technique, the weights of all samples are equal $[1, 1, 1, 1]$. This makes the coefficients all equal. For other algorithms, such as the 5-frame technique, the weights are larger on the middle frames than on the outer frames. The weights for the 5-frame technique are $[1, 2, 2, 2, 1]$. A property of the coefficient vectors is that the sum of the coefficients for each, the numerator and denominator, should be zero. Examples of coefficient vectors for a few selected algorithms are given in Table 1.

Heterodyne Interferometry

Historically, heterodyne techniques were developed and used before temporal phase-shifting techniques. These techniques generally determine the phase electronically at a single point by counting fringes and fractions of fringes. Areas are analyzed by scanning a detector.

Phase shifts are usually obtained using two slightly different frequencies in the reference and test beams. The beat frequency produced by the interference between the reference and test beams is compared to a reference sinusoidal signal, which may be produced either optically or electronically. The time delay (or distance traveled) between the crossing of the zero phase points of the test and reference sinusoidal signals is a measure of the phase. Every time the test signal passes through another zero in the same direction as the test surface is moved, another fringe can be counted. This is how fringe orders are counted. If the beam is interrupted as the detector is scanned across the interferogram, the fringe count is corrupted and the measurement needs to be started again. Frequency multiplication (harmonics) can also be used to determine fractions of fringes. Today, heterodyne techniques are used mainly in distance measuring interferometers. The precision and accuracy of distance measuring interferometers is at least on the order of 1 part in 10^6.

Fourier-Transform Technique

The Fourier-transform technique is a way to extract phase from a single interferogram. It is used a lot in nondestructive testing and stellar interferometry where it is difficult to get more than a single interferogram. The basic technique is shown schematically in Figure 11. The recorded interferogram distribution is Fourier transformed, and one order (usually the + or − first order) is either isolated and shifted to zero frequency or filtered out using a rectangular window. After an inverse Fourier transform, the result is the phase.



Figure 11 Fourier transform technique.

To illustrate this technique mathematically, the interference equation is rewritten as

$$I(x, y) = I_0(x, y) + c(x, y)\exp(i2\pi f_0 x) + c^*(x, y)\exp(-i2\pi f_0 x) \qquad [20]$$

where $c(x, y) = I_0(x, y)\gamma(x, y)\exp[i\phi(x, y)]$ and the $*$ indicates a complex conjugate. The term $c(x, y)$ contains the phase information we wish to extract. After performing a one-dimensional Fourier transform:

$$I(\xi, y) = I_0(\xi, y) + c(\xi - f_0, y) + c^*(\xi - f_0, y) \qquad [21]$$

where ξ is the spatial frequency in the x direction, and italics indicate Fourier transforms. The next step is to filter out and isolate the second term, and then inverse Fourier transform to yield $c(x, y)$. The wavefront modulo 2π is then given by

$$\phi(x, y) = \tan^{-1}\left\{\frac{\mathrm{Im}[c(x, y)]}{\mathrm{Re}[c(x, y)]}\right\} \qquad [22]$$

where Re and Im refer to the real and imaginary part of the function.

This technique has limitations. If the fringes are nonsinusoidal, there will not be a simple distribution in the frequency space; there will be many orders. Another problem is overlapping orders. There needs to be a carrier frequency present that ensures that the orders are separated in frequency space. This carrier frequency is produced by adding tilt fringes until the orders are separated. This means that the aberration (fringe deviation) has to be less than the fringe spacing. Another problem is aliasing. If the interferogram is not sampled sufficiently, there will be aliasing and it will not be possible to separate the orders in frequency space. Finally, large variations in average fringe irradiance and fringe visibility across the interferogram can also cause problems.

Spatial Carrier-Frequency Technique

This is essentially the equivalent of the Fourier transform technique but is performed in the spatial domain. It is also used when there is only one interferogram available and its major applications include nondestructive testing and measurement of large optics.

These techniques relate closely to the temporal phase-measurement methods; however, instead of using a number of interferograms they can obtain all the information from a single interferogram. As an example, let's assume that the fringes are vertical and parallel to the columns on the detector array.

The carrier frequency (i.e., the number of tilt fringes) is adjusted so that there is an α phase change from the center of one pixel to the next. As long as there is not much aberration (deviation), the phase change from pixel to pixel across the detector array will be approximately constant.

When the fringes are set up this way, the phase can be calculated using adjacent pixels (see Figure 12). If one fringe takes up 4 pixels, the phase shift α between pixels will be 90°. An algorithm such as the three-frame, four-frame, or five-algorithm can be used with adjacent pixels as the input. Therefore, 3, 4, or 5 pixels in a row will yield a single-phase point. Then, the analysis window is shifted sideways one pixel and phase is calculated at the next point. This technique assumes that the dc irradiance and fringe visibility do not change over the few pixels used to calculate each phase value.

Spatial Multichannel Phase-Shift Techniques

These techniques detect all phase maps simultaneously and multiplex the phase shift using static optical elements. This can be done by using either separate cameras as illustrated below or by using different detector areas to record each of the interferograms used to calculate the phase. The phase is usually calculated using the same techniques that are used for the temporal phase techniques.



Figure 12 Spatial phase shifting. Different relative phase shifts are on adjacent detector elements.



Figure 13 Spatial phase shifting using four cameras.

As an example, a four-channel interferometer can be made using the setup shown in Figure 13 to record four interferograms with 90° phase shifts between them. Camera 1 will yield fringes shifted 180° with respect to camera 2, and cameras 3 and 4 will have phase shifts of 90° and 270°. The optical system may also utilize a holographic optical element to split the beam to multiplex the four phase shifts on four quadrants of a single camera.

Signal Demodulation Techniques

The task of determining phase can be broadened by looking toward the field of signal processing. For communication via radio, radar, and optical fibers electrical engineers have developed a number of ways of compressing and encoding a signal as well as decompressing a signal and decoding it. An interference fringe pattern looks a lot like an am radio signal. Thus, it can be demodulated in similar ways. In recent years many new algorithms have been developed by drawing on techniques from communication theory and applying them to interferogram processing. Many of these use different types of transforms such as Hilbert transforms for straight fringes or circular transforms for closed fringes.

Extended Range Phase Measurement Techniques

A major limitation of phase measurement techniques is that they cannot determine surface discontinuities larger than $\lambda/4$ ($\lambda/2$ in optical path (OPD)) between adjacent pixels. One obvious solution is to use longer wavelength sources in the infrared where optically rough surfaces look smooth and their shape can be measured. An alternative is two-wavelength interferometry where two measurements at different wavelengths are taken and the measurable height limitation is now determined by the equivalent wavelength:

$$\lambda_{\mathrm{eq}} = \frac{\lambda_1 \lambda_2}{|\lambda_1 - \lambda_2|} \qquad [23]$$

Another method that allows for measurement of smooth surfaces with large height discontinuities that is limited only by the working distance of the objective combines a white light and a phase measurement interferometric technique in one long scan. The position of the wave packet resolves 2π ambiguities that result from the arctangent function (see Phase unwrapping section above). The phase of the fringe close to the wave packet maximum is determined without ambiguity. Sometimes it is not the step height discontinuity that is a problem but rather the high slope of the measured surface. If we know that the surface is continuous, then the unwrapping procedure can take advantage of this a priori information to look for a continuous.

Techniques for Deformation Measurement

Some of the techniques for deformation measurement have already been described earlier (see sections on Single frame techniques and Spatial multichannel phase-shift techniques). However, fringes in any interferometer can be analyzed not only in the x, y planes but also in the x, z, or y, z planes for which the carrier frequency of the fringes is introduced. Analysis of fringes in any plane has the same restrictions.

If the initial static object shape is measured using conventional phase measurement techniques, not only can the motion of each object point be determined but also the deformation of the whole object in time. If the motion of the object is periodic, then the object motion can be 'frozen' by using stroboscopic illumination of the same frequency as the object's motion. Once the motion is frozen, any temporal technique can be used to measure object shape at some phase of its motion. Changing the time offset between stroboscopic illumination and the periodic signal driving the motion, the object can be 'frozen' and thus measured at different phases of its periodic motion.

Systematic Errors

Noise Sensitivity

Measurement noise mostly arises from random fluctuations in the detector readout and electronics. This noise reduces precision and repeatability. Averaging multiple measurements can reduce effects of these random fluctuations.

Phase Shifter Errors

Phase shifter errors can be due to both miscalibration of the system and nonlinearities in the phase shift. It is possible to purchase very linear phase shifters. It is also possible to correct nonlinearities by determining the voltage signal making the phase shifter provide a linear phase shift.

Linear phase shifter errors (miscalibration) of the phase shift have an error signature that is at twice the frequency of the fringes. If there are two fringes across the field of view, the error signature will have four across the field of view. Figure 14 shows the difference between a calibrated and an uncalibrated phase shifter as well as the difference in error for two different phase measurement algorithms. Some algorithms are obviously more sensitive than others to this type of error.



(a) Fringes on flat



(b) 5 frame calibrated



(c) 4 frame-miscalibrated



(d) 5 frame-miscalibrated

Figure 14 Comparison of phase maps for calibrated and uncalibrated phase shifts using two different phase measurement algorithms.

Other Types of Systematic Errors to Consider

Other types of errors to consider are detector nonlinearities, quantization errors due to analog-to-digital converters, and dissimilar materials (see Phase change upon reflection). For temporal phase measurement techniques errors due to vibration and



Figure 15 Measurements of (a) hard disc substrate with a vertical range is 2.2 micrometers and (b) binary grating roughness standard.

air turbulence need to be considered as well. Spatial phase measurement techniques are sensitive to miscalibrated tilt (wrong carrier frequency), unequally spaced fringes, and sampling and windowing in Fourier transform techniques.

Choosing an Algorithm or Technique

Each algorithm and type of measurement technique is sensitive to different types of systematic errors. Choosing a proper algorithm or technique for a particular type of measurement depends on the specific conditions of the test itself and reducing the systematic errors for a particular type of measurement. This is the reason that so many algorithms exist. The references in the bibliography will help the reader determine what type of algorithm will work best for a specific application.

Examples of Applications

Phase shifting interferometry can be used for measurements such as hard disk flatness, quality of optical elements, lens curvature, dimensions and quality of air-bearing surfaces of magnetic read/write heads, cantilevers, and semiconductor elements. Figure 15 shows results for measurements of a hard disk substrate and a roughness grating.

Conclusions

Phase measurement interferometry techniques have increased measurement range and precision enabling the production of more complex and more precise components. As work continues on development of interferometric techniques, phase measurement techniques will continue to become more robust and less sensitive to systematic errors. Anticipated advances will enable measurements of objects that were unimaginable 20 or 30 years ago.

See also

Interferometry: White Light Interferometry. **Microscopy:** Interference Microscopy.

Further Reading

Bruning JH (1978) Fringe scanning interferometers. In: Malacara D (ed.) *Optical Shop Testing*, pp. 409–438. New York: Wiley.

Creath K (1988) Phase-measurement interferometry techniques. In: Wolf E (ed.) *Progress in Optics*, vol. 26, pp. 349–393. Amsterdam: Elsevier.

Creath K (1993) Temporal phase measurement methods. In: Robinson DW and Reid GT (eds) *Interferogram Analysis*, pp. 94–140. Bristol: IOP Publishing.

Creath K and Schmit J (1996) N-point spatial phase-measurement techniques for non-destructive testing. *Optics and Lasers in Engineering* 24: 365–379.

Ghiglia DC and Pritt MD (1998) *Two-Dimensional Phase Unwrapping*. New York: Wiley.

Greivenkamp JE and Bruning JH (1992) Phase shifting interferometry. In: Malacara D (ed.) *Optical Shop Testing*, 2nd edn, pp. 501–598. New York: Wiley.

Hariharan P (1992) *Basics of Interferometry*. New York: Academic Press.

Kerr D (ed.) (2004) FASIG special issue on fringe analysis. *Optics and Lasers in Engineering* 41: 597–686.

Kujawinska M (1993) Spatial phase measurement methods. In: Robinson DW and Reid GT (eds). *Interferogram Analysis*, pp. 141–193. Bristol, UK: IOP Publishing.

Larkin KG (1996) Neat nonlinear algorithm for envelope detection in white light interferometry. *Journal of Optical Society of America A* 13: 832–842.

Malacara D (1992) *Optical Shop Testing*, 2nd edn. New York: Wiley.

Malacara D, Servin M and Malacara Z (1998) *Interferogram Analysis for Optical Testing*. New York: Marcel Dekker.

Robinson DW and Reid GT (1993) *Interferogram Analysis: Digital Processing Techniques for Fringe Pattern Measurement*. Bristol, UK: IOP Publishing.

Schmit J and Creath K (1996) Window function influence on phase error in phase-shifting algorithms. *Applied Optics* 35: 5642–5649.

Surrel Y (2000) Fringe analysis. *Photo-Mechanics: Topics in Applied Physics* 77: 55–102.

White Light Interferometry

J Schmit, Veeco Instruments, Inc., Tucson, AZ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In 1960 the development of the laser injected new possibility into an old discipline, interferometry (*see* **Interferometry**: Overview). The excellent spatial and temporal coherence (ideally a single point and a single wavelength source) of the laser allowed for the formation of nonlocalized interference fringes. With lasers, researchers could easily generate good contrast fringes practically anywhere where the beams overlapped. These excellent-quality fringes from laser interferometers enabled high-resolution distance and displacement measurements on the order of meters and made possible noncontact surface probing with nanometer and subnanometer resolution. This kind of precision, which was supported by the advent of computers and the advancement of detectors, was previously unimaginable.

However, interference phenomena were used in metrology long before lasers and can be observed without any complicated device or source. On a rainy day we can observe the colorful interference patterns that have formed on a thin layer of gasoline in a puddle. The relationship between colors and the small distance between reflecting surfaces, observed as far back as 1665 by Hook, is still used to approximate layer thicknesses. The colors in interference patterns have been used to determine the spectral components of beams. By the end of the nineteenth century, Michelson and Benoit were using interference phenomena to determine distances, long before the invention of the computer and the laser.

While the application of lasers in interferometry has advanced the science, white light interferometry (WLI), which uses a spatially and temporally incoherent source and creates fringes localized over a few microns in space, has also benefited from technological advancements. The development of solid state detectors, fast computers, electronic signal processing, and precise scanning stages has allowed for incredibly fast analysis of white light interferograms. In fact, WLI is used in many applications from film thickness and surface measurement, through spectroscopy to astronomy.

This chapter focuses on the formation of white light fringes. We first examine the existence of white light fringes in the everyday world. A description of different interferometric setups and their uses follows. The bulk of this article details the formation of white light fringes and examines their different applications with an emphasis on the analysis of object structure. Suggestions for further reading, both within this encyclopedia and from outside sources, can be found at the end of this article. A basic theory of interferometry and coherence is to be found in corresponding articles of this encyclopedia.

White Light Interference in Everyday Life

The effects of interference display spectacular colors when observed in white light, such as the sun. We often see these effects in oil or gasoline spills, in soap bubbles, or between two smooth pieces of glass in contact (separated by a very thin layer of air film) – which are the simplest everyday white light interferometers. The colors we see in these displays are interference colors, and their origin is interference rather than dispersion as in the colors of a rainbow or light reflected from a CD. The picture in Figure 1 is of a gasoline spill under cloudy sky illumination; we see beautiful interference colors that are hard to find in a rainbow: iron-gray, magenta, grayish blue, whitish green, and brownish yellow. Interference colors will differ not only with the thickness of the layer but also with the layer's absorption and dispersion, the relative indices of refraction of the film, the surrounding media, and the illumination. Interference colors can be observed for layers from a fraction of a micron to a few microns thick.

Interferometers for White Light Observation

In a white light interferometer, either the colors or the intensity distribution of the fringes is typically analyzed to retrieve the necessary encoded information, such as the film thickness, birefringence, index of refraction, dispersion, spectral properties, and surface structure. White light interference can be observed only in interferometric designs where the optical paths in both arms of the interferometer are (nearly) equal and the system is (nearly) compensated for dispersion.

Interference in Thin Film

Beams of light of different wavelengths incident on a transparent thin film (such as the ones in the puddle) are partially reflected from the top air/film interface



Figure 1 Interference colors in a gasoline spill in a puddle. This picture would closely resemble a picture from an interference microscope, if not for the leaf in the top left corner.

and partially from the bottom film/substrate interface and then beams of the same wavelength interfere with each other. The optical path difference (OPD) traveled by the interfering beams is related to the film thickness, the index of refraction for the given wavelength and the angle of incidence.

Fringes of equal thickness will be observed if the film thickness (distance between interfering wavefronts) varies. These fringes represent points of equal distance between the two surfaces of the film and are formed close to the film (see Figure 2). This situation is typical in any interferometer since rarely are wavefronts perfectly plane and parallel.

For any individual wavelength, λ_i, where the OPD is equal to $m\lambda_i$, and where m is an integer, a bright fringe of the color of the wavelength, λ_i, will be observed due to constructive interference. For white light illumination, the color at a given point will be dominated by the color of the wavelength for which the interference will be constructive. This color can be used to estimate the optical thickness of the film.

An additional factor needs to be taken into account when color is used for estimating optical thickness, namely the phase change on reflection. Different colors will be observed if the ratio of indices of refraction for both film interfaces is <1 (or >1) as opposed to when the ratio of indices is <1 for one interface and >1 for the other.



Figure 2 Formation of fringes of equal thickness for film with wedge.

Polarization Microscope

Interference colors that correspond to equal thickness fringes can represent the birefringence of an object; these colors are often observed using a polarization microscope (*see* **Microscropy:** Interference Microscopy). The polarization microscope is a conventional microscope with a set of polarizers with crossed polarization axes, one placed above and the other placed below the tested birefringent object.

Interference colors have been tabulated for many years and for many different purposes. Newton devised his color scale to describe interference fringes for two pieces of glass in contact with each other. Michel-Lévy and Lacroix in 1889, created a color scale to help recognize different rock forming minerals. For more information about colors in white light interference see sections on *White Light Interference* and *Spectral Interference* below.

Michelson Interferometer

A Michelson interferometric setup, shown in Figure 3, is often used to analyze white light interference, but the intensity of the fringes is observed as one mirror is scanned rather than the color of fringes that is usually observed.

Two plane mirrors (equivalent to the top and bottom surfaces of a thin film) return the beams to the beamsplitter, which recombines parts of the returned beams and directs them towards the detector where the interference is observed. Beam S1 travels through the parallel plate three times while beam S2 passes through the plate only once causing the system to be not well compensated (balanced) for dispersion. Thus, for observation of white light interference, an identical plate is placed in the path of beam S2. As one of the plane mirrors moves along the optical axis to change the OPD, the detector collects the irradiance, the intensity. Fringes will be observed if the system is well-compensated for dispersion and for optical path lengths. Any spectral changes or changes in optical path lengths in the interferometer affect the shape or position of the fringes, and the interferometer measures these changes.

Common-path interferometers, like the Mach–Zender or Jamin interferometers, are naturally compensated interferometers and can be used for measurement of dispersion in gases. Other interferometers, such as the Twyman–Green or Fizeau interferometers, make use of their unequal interferometer arms and their nonlocalized fringes from laser sources for testing different optical elements and systems in reflection and transition (*see* **Interferometry:** Phase Measurement Interferometry).



Figure 3 Michelson interferometer.

White Light Interference

A white light source consists of a wide spectrum of wavelengths in visible spectrum, from about 380 up to 750 (violet to red) nanometers. However, the principles of WLI described in this article basically apply when any low coherence source is used. Low coherence refers to a source of not only low temporal but also low spatial coherence; WLI can also be referred to as low coherence interferometry. We will be concerned mainly with temporal effect of the source, the source spectrum.

Since different wavelengths from the source spectrum are mutually incoherent, we will first look at interference between two waves of a selected monochromatic illumination with wave number $k = 2\pi/\lambda$, where λ is the wavelength. The intensity of the interference fringes at point x, y (these coordinates are omitted in all equations), as one of the mirrors is scanned along the optical axis, z can be described as

$$I(k,z) = I_1 + I_2 + 2\sqrt{I_1 I_2}|\gamma(z)|\cos(kz) \qquad [1]$$

or can be written in the form:

$$I(k,z) = I_0\left[1 + \frac{2\sqrt{I_1 I_2}}{I_1 + I_2}|\gamma(z)|\cos(kz)\right] \qquad [2]$$

where I_1 and I_2 are intensities of each of the beams and $I_0 = I_1 + I_2$, $|\gamma(z)|$ is the modulus of the complex mutual coherence function (*see* **Coherence:** Overview) assumed here to equal 1 (perfect coherence for each wavelength). The optical path difference z equals $z_1 - z_2$ where z_1 and z_2 are the optical path lengths that the interfering waves have traveled. The difference in the traveled paths, z, corresponds to the position of the scanning mirror.

White light interference (polychromatic interference) is the overlaying of all the monochromatic fringes created for each wavelength of the source spectrum (Figure 4a). A detector observes the sum of all the fringe intensities.

In mathematical form, this interference can be described as the integral of all the fringes $I(k,z)$ for all



Figure 4 Formation of white light fringes: (a) fringes for individual wavelengths; (b) fringes for white light.

wavenumbers k:

$$I(z) = \int_{k_1}^{k_2} S(k)D(k)I(k,z)\mathrm{d}k \qquad [3]$$

where $S(k)$ is the spectral distribution of the light source, with $S(k) = 0$ outside of k_1 through k_2 range of wave numbers, and $D(k)$ is a spectral response of the detector. We assume that the detector's response $D(k)$ equals 1 over the whole spectrum. Because the spacing of the fringes for each wavelength emitted by the white light source is different, the maxima of fringes will align around only one point for a well-compensated interferometer, as shown in Figure 4a. This alignment around a single point, occurs because in a well-compensated interferometer there is one point for which the OPD is zero for all wavelengths. Away from this point, the observed sum of the intensities quickly falls off, as shown in Figure 4b. The maximum fringe, the fringe that marks the zero OPD, is called the zero-order fringe, and each next fringe of smaller amplitude on either side is called $+1$ and -1, $+2$ and -2 order fringe, and so on.

Because white light fringes are localized and can only be found within microns or tens of microns of the zero OPD, white light interferometers are excellent distance and 3D position sensors. However, this same characteristic makes them more difficult to align than interferometers with nonlocalized fringes.

Envelope of Fringes Due to Source Spectrum

The resultant intensity of interference from a broad spectrum source (see eqn [3]) can be described in general form as

$$I(z) = I_0[1 + V(z)\cos(k_0 z)] \qquad [4]$$

where $I_0 = I_1 + I_2$ is the background intensity, $V(z)$ is the fringe visibility function or coherence envelope, and $k_0 = 2\pi/\lambda_0$ is the central wave number for fringes under the envelope. The $V(z)$ is proportional to the modulus of the Fourier transform of the source spectrum $S(k)$. Generally, if the light source has a Gaussian spectrum $S(k)$, then the envelope of the fringes can be described also as a Gaussian function $V(z)$. If the spectrum of the source is rectangular, then the envelope of the fringes will be a sinc function. The wider that the spectrum of the source is the narrower the width of the envelope will be, as shown in Figure 5. The width of the fringe envelope determines the coherence length of the source (*see* **Coherence:** Overview); for a white light source this width is in the order of 1–2 microns.

Different white light sources, such as tungsten-halogen, incandescent, or arc lamps, have different spectra and thus create different coherence envelopes, as shown in Figure 5. The spectra of semiconductor light sources, such as LEDs and SLDs, are similar in shape to a Gaussian function.

The fact that the coherence envelope is related to the spectrum of the source by its Fourier transform is commonly used in Fourier transform spectroscopy, where the Fourier transform of the detected fringes is calculated to find the spectral components of the beams.

Position of Fringes Under Envelope Due to Reflection of Dielectric

Thus far we have assumed that in WLI the interferometer is compensated for all wavelengths, and thus, for this position the maximum of the fringes aligns with the maximum of the envelope, namely where there is a zero phase shift $\varphi_0 = 0$ between fringe and envelope maxima.

If there is an odd number of reflections from dielectric surfaces in one arm of the interferometer and an even number in the other, the fringes will be shifted by $\varphi_0 = 180°$ under the coherence envelope and the minimum of the fringe will align with the maximum of the coherence envelope. Thus eqn [4]



Figure 5 Spectrum and interferogram for (a) tungsten-halogen lamp and for (b) red LED sources.

can be expressed in a more general form:

$$I(z) = I_0[1 + V(z)\cos(k_0 z + \varphi_0)] \qquad [5]$$

Figure 6 shows color fringes for such a case; the dark fringe marks the zero OPD, and this fringe is surrounded by the greenish blue colors of shorter wavelengths. In contrast, the bright fringe at the maximum envelope position or marking the zero OPD would be surrounded by the reddish colors of longer wavelengths.

In a real system the fringes may be shifted with respect to the envelope by any amount of φ_0, and this shift may be due to any number of factors, such as the phase shift on reflection from nondielectric surfaces and dispersion, which we consider next.

Changes in Envelope and Fringes Due to Reflection of Nondielectric Materials

The relative position of the envelope maximum and fringe position will be different if the beam is reflected from different nondielectric materials. This difference exists because the phase change on reflection from a test surface, like metals or heavily doped semiconductors, varies with each wavelength. This variance in fringe and peak coherence position may be predicted and corrected for in surface height calculations. The linear dependence of the phase change on reflection versus wave number shifts the location of the coherence envelope peak position of fringes by different amounts. The constant phase change on reflection and higher-order terms only shift the fringes underneath the coherence envelope. As long as the change on reflection has a small dependence on the second- and higher-order of the wave number, the shape of the coherence envelope is preserved.

Changes in Envelope and Fringes Due to Dispersion

Dispersion in an interferometer that is not balanced, perhaps because a dispersive element was placed in one arm or the compensating plate has an incorrect thickness, will influence fringe formation. The phase delay between interference patterns for individual wavelengths is proportional to the product of the geometrical path and the index of refraction equal to $d \times n(k)$.

The intensity may be described as:

$$I(z) = \int_{k_1}^{k_2} \langle 1 + V(z)\cos\{kz - kd[n(k)]\}\rangle \, \mathrm{d}k \qquad [6]$$



Figure 6 Formation of white light fringes with destructive interference for OPD = 0.

The dependence of the refractive index on the wave number k can be described as a linear expansion:

$$n(k) = n(k_0) + \frac{\mathrm{d}n}{\mathrm{d}k}(k - k_0) \qquad [7]$$

The linear dispersion shifts the envelope by the group index of refraction times the thickness of the dispersive element; this dispersion also shifts the fringes under the envelope slightly. In other words, the linear phase delay for a range of wavelengths causes a group delay of the whole envelope (wave packet). Higher-order dispersion, absorption of the elements, or effects due to thin films can cause the envelope to widen or even become asymmetrical, the position of the fringes under the envelope to shift, the fringes to lose contrast, and the period of the fringes to change or vary with the z position. Dispersion effects will be stronger for sources that have a wider spectrum; however, the observed changes will be different for different shapes of spectra.

The phase of the fringes under the envelope and the position of the envelope itself are parameters often used in astronomy. Highly accurate white light fringe estimation, using the optical path-length delay between the two arms of the interferometer, is a cornerstone of stellar interferometry.

Fourier Analysis of White Light Interferograms

Wavelength-dependent changes in a white light interferogram can be more easily analyzed in the spectrum rather than the spatial domain. The Fourier transform of a white light interferogram yields two symmetrical side lobes at the mean wavelength of the interferogram; analysis of just one of these side lobes is sufficient. The spectral amplitude of the side lobe contains information about the spectral components of the interfering beams, while the spectral phase in regions with appreciable spectral amplitude supplies information about any unbalanced dispersion in the interferometer, as shown in Figure 7. Fourier transform analysis is extensively used in Fourier transform spectrometry (*see* **Spectroscopy:** Fourier Transform Spectroscopy).

For a dispersion-balanced interferometer, the interferogram is symmetrical around the zero OPD position. For a symmetrical interferogram, the spectral phase will be zero if the zero OPD position of the sampled interferogram is in the middle of sampling range; otherwise a linear factor appears in the spectral phase. This linear term, while useful to surface profiling, because it determines the position of the coherence signal with respect to scanner sampling, is unwanted in Fourier spectroscopy and needs to be corrected for. Dispersion and possible thin-film effects will commonly introduce a nonlinearity in the spectral phase.

Controlled Phase Shift of Fringes Under the Envelope – Geometric Phase Shift

Many techniques in interferometry depend on shifting the phase of the interfering wavefronts. Mechanical shifters used in white light interferometry will introduce the same shift measured in nanometers for all wavelengths; however, when measured in degrees or radians, the shift will vary for different wavelengths. Geometric phase shifters (achromatic phase shifters operating on the principle of geometric phase) introduce for all wavelengths the same shift when measured in degrees and are based on polarization elements like a rotating wave plate in circularly polarized light or a rotating polarizer in a circularly polarized beam. Fringes underneath the coherence envelope shift, as shown in Figure 8, while the coherence envelope stays in place.

The advantage to these techniques is that only the phase of fringes changes, not the fringe contrast



Figure 7 Spectral amplitude (a) and spectral phase (b) for input from unbalanced interferometer (c).

(*see* **Interferometry:** Phase Measurement Interferometry). A geometrical phase shifter can be very useful in polarization microscopes (Figure 9), white light shearing interferometers, or any system where the phase of the white light fringes needs to be measured.

Spectral Interference

White light fringes, because they are made up of fringes of many wavelengths, are observed only over very small path differences. If we filter only a narrow band from the white light spectrum, fringes would be visible over a much larger scan. For different wavelengths we would observe different color and frequency fringes; this is simply the reverse process of the description in the white light interference section.

If we place a spectrometer in the observation plane of the white light interferometer (Figure 10), we will observe fringes with continuously changing wavelengths in dispersed light. These fringes are called fringes of chromatic order or channeled spectrum fringes and find their application in film thickness measurement or absolute distance measurement in the range up to 1 mm. Channeled spectra were used for analysis of dispersion, thin film, and spectroscopic measurements. The number of observed fringes for a given wavelength is directly proportional to the measured optical path difference. The optical path difference can be determined if the difference in fringe numbers is determined for two well-known wavelengths (this is equivalent to two-wavelength interferometry). The optical path difference can be also quickly estimated from the frequency of fringes for a given wavelength; the larger the optical path difference, the denser the fringes.



Figure 8 Fringes for two different geometric phase shifts.



Figure 9 Polarization interferometer with geometric phase shift.

Surface Topography and Object Structure Measurement

Although WLI has many applications, this section focuses on white light interference as applied to surface topography measurement. Interference microscopes that use white light illumination are often based on the Michelson setup shown in Figure 11.





Figure 10 Interferometers with prism spectrometer to observe fringes of equal chromatic order for OPD measurement.

A beamsplitter cube is placed underneath the bright field objective, and one mirror is placed to the side at the focus plane of the objective while the other mirror is replaced by the measured surface with respect to which the whole interference objective is scanned. The narrowly localized fringes at the best focus position for each point of the surface corresponding to a pixel on the CCD camera is observed during the scan. Because of the design of the Michelson objective, in order to accommodate higher magnification objectives constraints, other interference setups like Mirau and Linnik were developed (*see* **Microscopy:** Interference Microscopy). However, these designs are still based on the Michelson interferometer, being also compensated interferometers with equal lengths and amounts of glass in each arm.

These interference microscopes typically have two complementary modes of operation; one mode uses monochromatic illumination and the other employs a white light source. Monochromatic illumination provides excellent vertical resolution but is limited in its range. It cannot correctly assign fringe order to discontinuous surfaces larger than 160 nanometers. Figure 12a shows monochromatic fringes for the surface of the profile shown in Figure 13. We see that with the monochromatic illumination the height of the grooves remains unknown because it is impossible to assign order numbers to these fringes.



Figure 11 Michelson interferometric objective.

To resolve this ambiguity, white light illumination is employed because it allows for easy identification of the zero order fringe. Figure 12b shows white light fringes created for the same surface. We see the zero-order fringe for the zero OPD as well as the next orders due to the decreasing contrast of the fringes. The position of the zero-order fringe can be followed and approximate heights can be determined visually. Thus, white light illumination permits the measurement of a broader range of surfaces that are rough or have large height variations up to a few millimeters.

The white light interferometer is a great focus detector (Figure 14) at each point of the field of view. The principle behind WLI is finding these individual focus positions using localized fringes observed during the surface scan. WLI interferometers provide high lateral resolution and large vertical range in the order of hundreds of nanometers or micrometers (Figure 15). White light interferometers are commonly used to measure magnetic heads, MEMS devices, binary optic, and machined surfaces.

Signal Processing of White Light Interferograms

For WLI topographic measurements, each pixel registers an interferogram whose position varies


(a) (b)

Figure 12 Fringes in quasimonochromatic and white light for object similar to one as presented in Figure 13.



Figure 13 3D object profile – binary grating.

with the surface height. Figure 16 shows two interferograms for two positions in the field of view of a measured step height surface; the first shows the top surface of the step height and the second shows the bottom surface of the step height.

Algorithms have been developed to analyze the signal in different ways. Some focus on finding the fringe envelope position and others examine the position of the fringe underneath the envelope. These algorithms work under the assumption that white light fringes can be described by the same function over the whole field of view of the interferometer. Algorithms are applied to a signal so as to find the position of the coherence envelope for each pixel. This process is called coherence gating, and all algorithms perform coherence gating.

Some algorithms look for the position of the envelope's maximum in a process whereby first the coherence envelope of the fringes is found using signal filtering. Then, the curve is fit to a few points around the envelope's maximum, and finally the position of the envelope's maximum is found. Other algorithms calculate the center of mass of the coherence signal, as described in eqn [8]:

$$H(x, y) = \frac{\sum_{n=1}^{N-1} \left(I_i(x, y) - I_{i+1}(x, y)\right)^2 z_i}{\sum_{n=1}^{N-1} \left(I_i(x, y) - I_{i+1}(x, y)\right)^2} \qquad [8]$$

This method is very fast and computationally efficient. Center of mass calculations are equivalent to calculations of the maximum of the envelope position, but only for a symmetrical signal. For an asymmetrical signal a piston is introduced for each point; however, this piston does not affect the whole measurement. Still another method calculates the spectral phase slope in the Fourier domain to determine the position of the coherence envelope in a process that is equivalent to finding the center of mass. Finally, a different group of algorithms tracks the position of the bright or dark fringe close to the envelope's maximum.

Scanner Speed – Sampling Rate

A practical sampling rate of the white light interference signal is around four pixels per fringe. Because in most algorithms it is not the position of the fringes that we want to determine but rather the position of the envelope of the fringes, sampling the envelope of the fringes with four samples is usually sufficient. However, this sufficiency comes at the expense of lower repeatability (higher noise). The advantage to this sampling rate is short measurement time; higher sampling rates increase measurement time. Measurement speed can be increased by up to 25 times when the envelope of the fringes is widened by filtering light of a bandwidth about 20–40 nm from the white light source.

Scanner Nonlinearity

Scanner motion is assumed to be linear, but nonlinearity in this motion impairs measurement



Figure 14 Operation of white light interferometer for surface topography measurement.



Figure 15 WLI measurement of Fresnel lens in a high-resolution mode. Courtesy of Glimmerglass.

accuracy. To account for this, simple algorithms can calculate the average steps along each interferogram in scanning direction (Figure 17) and measured steps can be used in coherence detection algorithms.

In order to have continuous information about the scan steps, the fringes should be visible somewhere in the field of view at each moment of the scan. This task may require introducing a large tilt for samples with large discontinuities such as stepped surfaces. For large discontinuities where introducing sample tilt may not be sufficient, the envelope of the fringes can be extended by increasing the spatial or temporal coherence of the light source. An alternate solution involves measuring the scanner motion with a distance-measuring interferometer or triggering the camera to collect intensity data at every equal scan step, which can be determined by using the zero-crossing technique, as is commonly done in Fourier transform spectroscopy. Equal scan steps are more suitable for techniques based on transform techniques that assume equal sampling. Other peak detection algorithms, such as center of mass calculations, make use of measured but not necessarily equal steps directly in the algorithm.

Observing the phase along the interferogram can also provide information that is important in optical fiber sensing. These observed changes, which assume that sampling rates of the interferogram are known,



Figure 16 White light fringes as seen by two pixels during scan through focus for object in form of step.



Figure 17 Phase calculated along the white light interferogram. This calculated phase can be used to determine scanner motion.

enable correction for changes in wave number value k_0 which can be due to such things as changes in the working voltage of bulb, an introduced higher-order dispersion, or a large tilt of the sample.

Increased Resolution White Light Interferometry

Interferometric methods that employ a monochromatic light source to detect the phase of the fringes (*see* **Interferometry:** Phase Measurement Interferometry) can achieve about 10 times better (0.3 nanometers versus 3 nanometers) vertical resolution than the WLI methods described so far. Combining coherence position detection from WLI to determine fringe order with the phase detection of phase shifting techniques allows for the measurement of samples with height discontinuities larger than 160 nanometers with the resolution and accuracy of phase shifting interferometry (PSI). This combination is particularly well-suited for determining the shape of smooth surfaces with large height differences such as binary diffractive optics or micro-electromechanical systems (MEMS) (see Figure 15).



Figure 18 Fringes for (a) thin and (b) thick film.

Using this combined method we obtain both a lower-resolution map of the envelope position and a higher-resolution map of the phase (position) of the zero order fringe. These maps may differ slightly due to effects similar to those discussed in sections *Changes in Envelope and Fringes Due to Reflection of Nondielectric* and *Changes in Envelope and Fringes Due to Dispersion* above. In interference microscopes, shifts in the envelope and fringe position may be introduced by field-dependent and chromatic aberrations of the system and the system's effective numerical aperture. These shifts can vary for different points on the tested surface, but for simplicity are assumed to be constant over the field. Some correction for these effects can be applied.

Film Thickness Measurement

White light interferograms that are obtained in an optical profiler can be used to measure transparent film thicknesses because the character of the interferogram changes with the thickness of the film (Figure 18). Two different techniques, a thin or thick film technique, are used depending of the range of the film thickness. A thick film technique is used if two



Figure 19 Thick film (see **Figure 18b**) irradiance.

sets of best contrast white light fringes from each interface are clearly separated, meaning that no interference occurs between the wavefronts reflected from the top and bottom surfaces of the film. A thin film technique is employed when the two sets of fringes overlap.

Thick film measurement

A simple technique for finding the relative position of the peaks of the fringe envelopes can be implemented to find the thickness of a film. Figure 19 shows two clearly separated sets of fringes formed for the air/film and film/substrate interfaces. Whether these two sets of fringes are separated or not depends mainly on the geometrical thickness of the film and its group index of refraction, which is determined by the dispersion of the film. The typical range of measurable film thicknesses runs from 3 to 150 microns, depending on the dispersion of the film. This measurement allows for the detection of flows on the surface and interface of the film. Similar principles based on finding the position of the coherence envelopes are used for distance sensing, thickness measurement of plates, and the cornea of the eye, in low coherence reflectometry and structure measurements in biological samples in optical coherence tomography.

Thin film measurement

For thicknesses of five microns down to tens of nanometers, the white light interferogram is created from the interference between the beams reflected from the reference mirror and the two beams reflected from the thin film layer. Once the interferogram is registered while the objective is scanned vertically with a constant velocity, the spectral phase is calculated by applying a Fourier transform to the measured signal at each pixel as described in the section *Fourier Analysis of White Light Interferograms* above. The phase slope is subtracted and the dispersion of the system needs to be known. The spectral phase for the thin film interference has the form of a polynomial; thus, the polynomial for the chosen film model (n and k) is fitted, and regression analysis is used to find the best fit and, therefore, the film thickness (Figure 20).



Figure 20 Thin film (see **Figure 18a**): (a) irradiance, (b) spectral amplitude and (c) spectral phase.

Spatial Coherence Effects in the Interference Microscope

So far we have been discussing temporal coherence effects, but everywhere that the source has a wavelength bandwidth, spatial coherence may play an important role. In an interference microscope for surface topography measurement, the size of the aperture of the condenser is on the order of the aperture of the objective that illuminates the surface with a wide range of angles. For large angles, which are determined by the numerical aperture (NA) of the objective, where $\mathrm{NA} = 0.5\text{–}0.95$, the combination of the influence of the spatial and temporal coherence is clearly visible. The additional spatial effects include a reduction of the fringe envelope width and a decrease in fringe spacing corresponding to k_0. Calibration of fringe spacing is typically done on the system and accounts for spatial effects as well as for any uncertainty of k_0 due to the source spectra, the working temperature of the source, the spectral response of the detector and the influence of other factors like the intensity distribution in the illuminating aperture. The spatial influences can be reduced by stopping down the condenser, which causes an increase in the contrast of the fringes.

Rough Surfaces

Rough surfaces are difficult to measure using interferometric techniques, but under certain coherence conditions white light interference can do the job. For rough surfaces, if the microstructure of the object is not resolved by the imaging system, speckles, rather than fringes, are observed. Each speckle has a random phase which is approximately constant in the whole speckle area. If the rough surface is scanned through focus, each individual speckle exhibits the intensity modulation that is typical for WLI. These speckles enable the measurement, but they also introduce noise proportional to the roughness of the measured surface.

Despite the noise that speckles introduce into the WLI measurement, WLI has an advantage because it rejects the light that has undergone scattering outside of a small sample volume, thus allowing precise noninvasive measurement of object structure, even in dense media.

Applications

WLI is used in many disciplines and instruments such as:

- Fourier transform spectroscopy – source and material properties;
- Michelson stellar interferometer – angular size of star, binary stars, delay measurement in optical paths of interferometer;
- Shearing interferometry – structure measurement;
- DIC Nomarski interferometry – structure measurement;
- Speckle interferometry – structure measurement;
- Holography – structure measurement;
- Optical sensors – temperature, pressure, distance;
- Optical coherence tomography – structure measurement.

See also

Coherence: Coherence and Imaging; Overview. **Holography, Techniques:** Holographic Interferometry. **Interferometry:** Phase Measurement Interferometry. **Microscopy:** Interference Microscopy. **Spectroscopy:** Fourier Transform Spectroscopy.

Further Reading

Born M and Wolf E (1997) *Principles of Optics*. New York: Cambridge University Press.

Creath K (1997) *Sampling requirements for white light interferometry*. Fringe'97 Proceedings of the 3rd International Workshop on Automatic Processing of Fringe Patterns, pp. 52–59.

Danielson BL and Boisbert CY (1991) Absolute optical ranging using low coherence interferometry. *Applied Optics* 30: 2975–2979.

Davis SP, Abrams MC and Brault JW (2001) *Fourier Transform Spectrometry*. London: Academic Press.

de Groot P and Deck L (1995) Surface profiling by analysis of white light interferograms in the spatial frequency domain. *Journal of Modern Optics* 42: 389–401.

Dresdel T, Hausler G and Venzke H (1992) Three dimensional sensing of rough surfaces by coherence radar. *Applied Optics* 31(7): 919–925.

Harasaki A, Schmit J and Wyant JC (2001) Offset envelope position due to phase change on reflection. *Applied Optics* 40: 2102–2106.

Hariharan P (1992) *Basics of Interferometry*. New York: Academic Press.

Hariharan P, Larkin KG and Roy M (1994) The geometric phase: interferometric observation with white light. *Journal of Modern Optics* 41: 663–667.

Larkin KG (1996) Neat nonlinear algorithm for envelope detection in white light interferometry. *Journal of the Optical Society of America A* 13: 832–842.

Michelson AA and Benoit JR (1895) Détermination expérimentale de la valeur du métre en longueurs d'ondes lumineuses. *Travaux et Mémoires des Bureau International des Poids et Mesures* 11: 1.

Olszak AG and Schmit JG (2003) High stability white light interferometry with reference signal for real time correction of scanning errors. *Optical Engineering* 42(1): 54–59.

Park M-C and Kim S-W (2000) Direct quadratic polynomial fitting for fringe peak detection of white light scanning interferograms. *Optical Engineering* 39: 952–959.

Pavlicek P and Soubusta J (2004) Measurement of the influence of dispersion on white light interferometry. *Applied Optics* 43: 766–770.

Schmit JG and Olszak A (2002) High precision shape measurement by white light interferometry with real time scanner error correction. *Applied Optics* 41(28): 5943–5950.

Sheppard CJR and Larkin KG (1995) Effects of numerical aperture on interference fringe spacing. *Applied Optics* 34: 4731–4734.

Sheppard CJR and Roy M (2003) Low-coherence interference microscopy. In: Torok P and Kao F-J (eds) *Optical Imaging and Microscopy*, pp. 257–273. Berlin, Heidelberg, New York: Springer-Verlag.

Steel W (1987) *Interferometry*. New York: Cambridge University Press.

Turyshew SG (2003) Analytical modeling of the white light fringe. *Applied Optics* 42(1): 71–90.

L

LASERS

Contents

Carbon Dioxide Laser
Dye Lasers
Edge Emitters
Excimer Lasers
Free Electron Lasers
Metal Vapor Lasers
Noble Gas Ion Lasers
Optical Fiber Lasers
Organic Semiconductors and Polymers
Planar Waveguide Lasers
Semiconductor Lasers
Up-Conversion Lasers

Carbon Dioxide Laser

C R Chatwin, University of Sussex, Brighton, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

This article gives a brief history of the development of the laser and goes on to describe the characteristics of the carbon dioxide laser and the molecular dynamics that permit it to operate at comparatively high power and efficiency. It is these commercially attractive features and its low cost that has led to its adoption as one of most popular industrial power beams. This outline also describes the main types of carbon dioxide laser and briefly discusses their characteristics and uses.

Brief History

In 1917 Albert Einstein developed the concept of stimulated emission which is the phenomenon used in lasers. In 1954 the MASER (Microwave Amplification by Stimulated Emission of Radiation) was the first device to use stimulated emission. In that year Townes and Schawlow suggested that stimulated emission could be used in the infrared and optical portions of the electromagnetic spectrum. The device was originally termed the optical maser, this term being dropped in favor of LASER, standing for: Light Amplification by Stimulated Emission of Radiation. Working against the wishes of his manager at Hughes Research Laboratories, the electrical engineer Ted Maiman created the first laser on the 15 May 1960. Maiman's flash lamp pumped ruby laser produced pulsed red electromagnetic radiation at a wavelength of 694.3 nm. During the most active period of laser systems discovery Bell Labs made a very significant contribution. In 1960, Ali Javan, William Bennet and Donald Herriot produced the first Helium Neon laser, which was the first continuous wave (CW) laser operating at 1.15 μm. In 1961, Boyle and Nelson developed a continuously operating Ruby laser and in 1962, Kumar Patel, Faust, McFarlane and Bennet discovered five noble gas lasers and lasers using oxygen mixtures. In 1964, C.K.N. Patel created the high-power carbon dioxide laser operating at 10.6 μm. In 1964, J.F. Geusic and R.G. Smith produced the first Nd:Yag laser using neodymium doped yttrium aluminum garnet crystals and operating at 1.06 μm.

Characteristics

Due to its operation between low lying vibrational energy states of the CO_2 molecule, the CO_2 laser has a high quantum efficiency, ~40%, which makes it extremely attractive as a high-power industrial materials processing laser (1 to 20 kW), where energy and running costs are a major consideration. Due to the requirement for cooling to retain the population inversion, the efficiency of electrical pumping and optical losses – commercial systems have an overall efficiency of approximately 10%. Whilst this may seem low, for lasers this is still a high efficiency. The CO_2 laser is widely used in other fields, for example, surgical applications, remote sensing, and measurement. It emits infrared radiation with a wavelength that can range from 9 μm up to 11 μm. The laser transition may occur on one of two transitions: $(00^01) \rightarrow (10^00)$, $\lambda = 10.6\ \mu m$; $(00^01) \rightarrow (02^00)$, $\lambda = 9.6\ \mu m$, see Figure 1. The 10.6 μm transition has the maximum probability of oscillation and gives the strongest output; hence, this is the usual wavelength of operation, although for specialist applications the laser can be forced to operate on the 9.6 μm line.

Figure 1 illustrates an energy level diagram with four vibrational energy groupings that include all the significantly populated energy levels. The internal relaxation rates within these groups are considered to be infinitely fast when compared with the rate of energy transfer between these groups. In reality the internal relaxation rates are at least an order of magnitude greater than the rates between groups.

Excitation of the upper laser level is usually provided by an electrical glow discharge. However, gas dynamic lasers have been built where expanding a hot gas through a supersonic nozzle creates the population inversion; this creates a nonequilibrium region in the downstream gas stream with a large population inversion, which produces a very high-power output beam (135 kW – Avco Everett Research Lab). For some time the gas dynamic laser was seriously considered for use in the space-based Strategic Defence Initiative (SDI-USA). The gas mixture used in a CO_2 laser is usually a mixture of carbon dioxide, nitrogen, and helium. The proportions of these gases varies from one laser system to another, however, a typical mixture is 10%-CO_2;


Group(5)
Population = n_5
Vibrationally excited nitrogen
Group(1)
Population = n_1
Asymmetric stretching mode
Group(2)
Population = $n_2 = n_{21} \cdot n_{22}$
Symmetric stretching
and bending modes
Group(3)
Population = $n_3 = n_{31} \cdot n_{32}$
Bending modes
K_{51}
$v=1$
00^01
K_{sp}
K_{15}
LASER ACTION
n_{21}
$[\overset{\circ}{1}00, 0\overset{\circ}{2}0]_I$
n_{22}
$[\overset{\circ}{1}00, 0\overset{\circ}{2}0]_{II}$
K_{2131}
K_{2231}
02^20
n_{31}
K_{3132}
γ
β
α
η
K_{132}
01^10
n_{32}
K_{320}
Group(4)
Ground level population = n_4
Nitrogen
Group(0)
Ground level population = n_0
Carbon dioxide

Figure 1 Six level model used for the theoretical description of CO_2 laser action.

10%-N_2; 80%-He. Helium plays a vital role in the operation of the CO_2 laser in that it maintains the population inversion by depopulating the lower laser level by nonradiative collision processes. Helium is also important for stabilization of the gas discharge; furthermore it greatly improves the thermal conductivity of the gas mixture, which assists in the removal of waste heat via heat exchangers.

Small quantities of other gases are often added to commercial systems in order to optimize particular performance characteristics or stabilize the gas discharge; for brevity we only concern ourselves here with this simple gas mixture.

Molecular Dynamics

Direct Excitation and De-excitation

It is usual for excitation to be provided by an electrical glow discharge. The direct excitation of carbon dioxide (CO_2) and nitrogen (N_2) ground state molecules proceeds via inelastic collisions with fast electrons. The rates of kinetic energy transfer are α and γ, respectively, and are given by eqns [1] and [2]:

$$\alpha = \frac{F_{CO_2} \times IP}{E_{00^01} \times n_0} (\mathrm{sec}^{-1}) \qquad [1]$$

$$\gamma = \frac{F_{N_2} \times IP}{E_{v=1} \times n_4} (\mathrm{sec}^{-1}) \qquad [2]$$

where:

F_{CO_2} = Fraction of the input power (IP) coupled into the excitation of the energy level E_{00^01}, n_0 is the CO_2 ground level population density;

F_{N_2} = Fraction of the input power (IP) coupled into the excitation of the energy level $E_{v=1}$; and n_4 is the N_2 ground level population density.

The reverse process of the above occurs when molecules lose energy to the electrons and the electrons gain an equal amount of kinetic energy; the direct de-excitation rates are given by η and β, eqns [3] and [4], respectively:

$$\eta = \alpha \times \exp\left(\frac{E_{00^01}}{E_e}\right)(\mathrm{sec}^{-1}) \qquad [3]$$

$$\beta = \gamma \times \exp\left(\frac{E_{v=1}}{E_e}\right)(\mathrm{sec}^{-1}) \qquad [4]$$

where E_e is the average electron energy in the discharge.



Figure 2 Electron energy distribution function.

E_e, F_{CO_2}, and F_{N_2} are obtained by solution of the Boltzmann transport equation (BTE); the average electron energy can be optimized to maximize the efficiency (F_{CO_2}, F_{N_2}) with which electrical energy is utilized to create a population inversion. Hence, the discharge conditions required to maximize efficiency can be predicted from the transport equation. Figure 2 shows one solution of the BTE for the electron energy distribution function.

Resonant Energy Transfer

Resonant energy transfer between the CO_2 (00^01) and N_2 ($v = 2$) energy levels (denoted 1 and 5 in Figure 1) proceeds via excited molecules colliding with ground state molecules. A large percentage of the excitation of the upper laser level takes place via collisions between excited N_2 molecules and ground state CO_2 molecules. The generally accepted rate of this energy transfer is given by eqns [5] and [6]:

$$K_{51} = 19\,000\, P_{CO_2}\, (\mathrm{sec}^{-1}) \qquad [5]$$

$$K_{15} = 19\,000\, P_{N_2}\, (\mathrm{sec}^{-1}) \qquad [6]$$

where P_{CO_2} and P_{N_2} are the respective gas partial pressures in Torr.

Hence, CO_2 molecules are excited into the upper laser level by both electron impact and impact with excited N_2 molecules. The contribution from N_2 molecules can be greater than 40% depending on the discharge conditions.

Collision–Induced Vibrational Relaxation of the Upper and Lower Laser Levels

The important vibrational relaxation processes are illustrated by Figure 1 and can be evaluated from eqns [7–10]; where the subscripts refer to the rate between energy levels 1 and 32; 21 and 31; 22 and 31; 32 and 0, respectively:

$$K_{132} = 367\,P_{CO_2} + 110\,P_{N_2} + 67\,P_{He}\ (\text{sec}^{-1}) \qquad [7]$$

$$K_{2131} = 6 \times 10^5\,P_{CO_2}\ (\text{sec}^{-1}) \qquad [8]$$

$$K_{2231} = 5.15 \times 10^5\,P_{CO_2}\ (\text{sec}^{-1}) \qquad [9]$$

$$K_{320} = 200\,P_{CO_2} + 215\,P_{N_2} + 3270\,P_{He}\ (\text{sec}^{-1}) \qquad [10]$$

K_{132}, K_{2131}, and K_{2231} are vibration/vibration transfer rates and K_{320} is a vibration/translation transfer rate. Note the important effect of helium on eqn [10]; helium plays a major role in depopulating the lower laser level, thus enhancing the population inversion. P_{He} is the partial pressure of helium in Torr.

Radiative Relaxation

Spontaneous radiative decay is not a major relaxation process in the CO_2 laser but it is responsible for starting laser action via spontaneous emission. The Einstein 'A' coefficient for the laser transition is given by eqn [11]:

$$A = (\tau_{sp})^{-1} = 0.213\ (\text{sec}^{-1}) \qquad [11]$$

Gain

The gain (g) is evaluated from the product of the absorption coefficient (σ) and the population inversion, eqn [12]:

$$g = \sigma\left(n_{00^01} - \frac{g_1}{g_2}n_{10^00}\right)\ \text{cm}^{-1} \qquad [12]$$

For most commercial laser systems the absorption coefficient is that for high-pressure collision-broadening ($P > 5.2$ Torr) where the intensity distribution function describing the line shape is Lorentzian. The following expression describes the absorption coefficient, eqn [13]:

$$\sigma = \frac{692.5}{T n_{CO_2}\left(1 + 1.603\dfrac{n_{N_2}}{n_{CO_2}} + 1.4846\dfrac{n_{He}}{n_{CO_2}}\right)}(\text{cm}^2) \qquad [13]$$

where T is the absolute temperature and n refers to the population density of the gas designated by the subscript.

This expression takes account of the different constituent molecular velocity distributions and different collision cross-sections for $CO_2 \rightarrow CO_2$, $N_2 \rightarrow CO_2$ and $He \rightarrow CO_2$ type collisions. Equation [13] also takes account of the significant line broadening effect of helium.

Neglecting the unit change in rotational quantum number, the energy level degeneracies g_1 and g_2 may be dropped. n_{10^00} is partitioned such that $n_{10^00} = 0.1452 n_2$ and eqn [12] can be re-cast as eqn [14]:

$$g = \sigma(n_1 - 0.1452 n_2)\ \text{cm}^{-1} \qquad [14]$$

where n_1 and n_2 are the population densities of energy groups '1' and '2' respectively.

Stimulated Emission

Consider a laser oscillator with two plane mirrors, one placed at either end of the active gain medium, with one mirror partially transmitting (see Figure 4). Laser action is initiated by spontaneous emission that happens to produce radiation whose direction is normal to the end mirrors and falls within the resonant modes of the optical resonator. The rate of change of photon population density (I_p) within the laser cavity can be written as eqn [15]:

$$\frac{dI_p}{dt} = I_p c g - \frac{I_p}{T_0} \qquad [15]$$

where the first term on the right-hand side accounts for the effect of stimulated emission and the second term represents the number of photons that decay out of the laser cavity, T_0 is the photon decay time, given by eqn [16], and is defined as the average time a photon remains inside the laser cavity before being lost either through the laser output window or due to dispersion; if dispersion is ignored, I_p/T_0, is the laser output:

$$T_0 = \frac{2L}{c\,\log_e\left(\dfrac{1}{R_B R_F}\right)} \qquad [16]$$

where L is the distance between the back and the front mirrors, which have reflectivities of R_B and R_F, respectively. The dominant laser emission occurs on a rotational–vibrational P branch transition $P(22)$, that is $(J = 21) \rightarrow (J = 22)$ line of the $(00^01) \rightarrow (10^00)$, $\lambda = 10.6\ \mu\text{m}$ transition, where J is the rotational quantum number. The rotational level relaxation rate is so rapid that equilibrium is maintained between rotational levels so that they feed all their energy through the $P(22)$ transition. This model simply assumes constant intensity, basing laser performance on the performance of an average unit volume. By introducing the stimulated emission term into the molecular rate equations, which describe the rate of transfer of molecules between the various energy levels illustrated in Figure 1, a set of molecular rate eqns [17–21] can be written that permit simulation of the performance of a carbon dioxide laser:

$$\frac{\mathrm{d}n_1}{\mathrm{d}t} = \alpha n_0 - \eta n_1 + K_{51}n_5 - K_{15}n_1 - K_{\mathrm{sp}}n_1 - K_{132}\left(n_1 - \left[\frac{n_1}{n_{32}}\right]_{\mathrm{e}} n_{32}\right) - I_{\mathrm{p}}cg \qquad [17]$$

$$\frac{\mathrm{d}n_2}{\mathrm{d}t} = K_{\mathrm{sp}}n_1 + I_{\mathrm{p}}cg - K_{2131}\left(n_{21} - \left[\frac{n_{21}}{n_{31}}\right]_{\mathrm{e}} n_{31}\right) - K_{2231}\left(n_{22} - \left[\frac{n_{22}}{n_{31}}\right]_{\mathrm{e}} n_{31}\right) \qquad [18]$$

$$\frac{\mathrm{d}n_3}{\mathrm{d}t} = 2K_{2131}\left(n_{21} - \left[\frac{n_{21}}{n_{31}}\right]_{\mathrm{e}} n_{31}\right) - 2K_{2231}\left(n_{22} - \left[\frac{n_{22}}{n_{31}}\right]_{\mathrm{e}} n_{31}\right) + K_{132}\left(n_1 - \left[\frac{n_1}{n_{32}}\right]_{\mathrm{e}} n_{32}\right) - K_{320}\left(n_{32} - \left[\frac{n_{32}}{n_0}\right]_{\mathrm{e}} n_0\right) \qquad [19]$$

$$\frac{\mathrm{d}n_5}{\mathrm{d}t} = \gamma n_4 - \beta n_5 - K_{51}n_5 + K_{15}n_1 \qquad [20]$$

$$\frac{\mathrm{d}I_{\mathrm{p}}}{\mathrm{d}t} = I_{\mathrm{p}}cg - \frac{I_{\mathrm{p}}}{T_0} \qquad [21]$$

The terms in square brackets ensure that the system maintains thermodynamic equilibrium; subscript 'e' refers to the fact that the populations in the square brackets are the values for thermodynamic equilibrium. The set of five simultaneous differential equations can be solved using a Runge–Kutta method. They can provide valuable performance prediction data that is helpful in optimizing laser design, especially when operated in the pulsed mode. Figure 3a illustrates some simulation results for the transverse flow laser shown in Figure 9. The results illustrate the effect of altering the gas mixture and how this can be used to control the gain switched spike that would result in unwelcome work piece plasma generation if allowed to become too large. Figure 3b shows an experimental laser output pulse from the high pulse repetition frequency (prf–5kHz) laser illustrated in Figure 9. This illustrates that even a quite basic physical model can give a good prediction of laser output performance.

Optical Resonator

Figure 4 shows a simple schematic of an optical resonator. This simple optical system consists of two mirrors (the full reflector is often a water cooled gold coated copper mirror), which are aligned to be orthogonal to the optical axis that runs centrally along the length of the active gain medium in which there is a population inversion. The output coupler is a partial reflector (usually dielectrically coated zinc selenide – ZnSe–that may be edge cooled) so that some of the electromagnetic radiation can escape as an output beam. The ZnSe output coupler has a natural reflectivity of about 17% at each air–solid interface. For high power lasers (2 kW) 17% is sufficient for laser operation; however, depending on the required laser performance the inside surface is often given a reflective coating. The reflectivity of the inside face depends on the balance between the gain (eqn [14]), the output power and the power stability requirements. The outside face of the partial reflector must be anti-reflection (AR) coated.

Spontaneous emission occurs within the active gain medium and radiates randomly in all directions; a fraction of this spontaneous emission will be in the same direction as the optical axis, perpendicular to the end mirrors, and will also fall into a resonant mode of the optical resonator. Spontaneous emission photons interact with CO_2 molecules in the excited upper laser level, excited state (00^01), which stimulates these molecules to give up a quanta of vibrational energy as photons via the radiative transition $(00^01) \rightarrow (10^00)$, $\lambda = 10.6\,\mu\mathrm{m}$. The radiation given up will have exactly the same phase and direction as the stimulating radiation and thus will be coherent with it. The reverse process of absorption also occurs, but so long as there is a population inversion there will be a net positive output. This process is called light amplification by stimulated emission of radiation (LASER). The mirrors continue to redirect the photons parallel to the optical axis and so long as the population inversion is not depleted, more and more photons are stimulated by stimulated emission which dominates the process and also dominates the spontaneous emission, which is important to initiate laser action.

Light emitted by lasers contains several optical frequencies, which are a function of the different modes of the optical resonator; these are simply the standing wave patterns that can exist within the resonator structure. There are two types of



Figure 3 (a) Predicted output pulses for transverse flow CO_2 laser for different gas mixtures, (b) Experimental output pulse from transverse flow CO_2 laser.



Figure 4 Optical resonator.

resonator modes: longitudinal and transverse. Longitudinal modes differ from one another in their frequency of oscillation whereas transverse modes differ from one another in their oscillation frequency and field distribution in a plane orthogonal to the direction of propagation. Typically CO_2 lasers have a large number of longitudinal modes; in CO_2 laser applications these are of less interest than the transverse modes, which determine the transverse beam intensity and the nature of the beam when focused. In cylindrical coordinates the transverse modes are labelled TEM_{pl}, where subscript '*p*' is the number of radial nodes and '*l*' is the number of angular nodes. The lowest order mode is the TEM_{00}, which has a Gaussian-like intensity profile with its maximum on the beam axis. A light beam emitted from an optical resonator with a Gaussian profile is said to be operating in the 'fundamental mode' or the TEM_{00} mode. The decrease in irradiance (I) with distance '*r*' from the axis (I_0) of the Gaussian beam is described by eqn [22]:

$$I(r) = I_0 \exp(2r^2/w^2) \qquad [22]$$

where w is the radial distance, where the power density is decreased to $1/e^2$ of its axial value. Ideally a commercial laser should be capable of operation in the fundamental mode as, with few exceptions, this results in the best performance in applications. Laser cutting benefits from operation in the fundamental mode; however, welding or heat treatment applications may benefit from operation with higher-order modes. Output beams are usually controlled to be linearly or circularly polarized, depending upon the requirements of the application. For materials processing applications the laser beam is usually focused via a water cooled ZnSe lens or, for very high power lasers, a parabolic gold coated mirror. Welding applications will generally use a long focal length lens and cutting applications will use a short focal length, which generates a higher irradiance at the work piece than that necessary for welding. The beam delivery optics are usually incorporated into a nozzle assembly that can deliver cooling water and assist gases for cutting and anti-oxidizing shroud gases for welding or surface engineering applications.

Laser Configuration

CO_2 lasers are available in many different configurations and tend to be classified on the basis of their physical form and the gas flow arrangement, both of which greatly affect the output power available and beam quality. The main categories are: sealed off lasers, waveguide lasers, slow axial flow, fast axial flow, diffusion cooled, transverse flow, transversely excited atmospheric lasers, and gas dynamic lasers.

Sealed-Off and Waveguide Lasers

Depopulation of the lower laser level is via collision with the walls of the discharge tube, so the attainable output power scales with the length of the discharge column and not its diameter. Output powers are in the range 5 W to 250 W. Devices may be constructed from concentric glass tubes with the inner tube providing the discharge cavity and the outer tube acting to contain water-cooling of the inner discharge tube. The inner tube walls act as a heat sink for the discharge thermal energy (see Figure 5). The DC electrical discharge is provided between a cathode and anode situated at either end of the discharge tube. A catalyst must be provided to ensure regeneration of CO_2 from CO. This may be accomplished by adding about 1% of H_2O to the gas mixture, or alternatively, recombination can be achieved via a hot (300 °C) Ni cathode, which acts as a catalyst. RF-excited all metal sealed-off tube systems can deliver lifetimes greater than 45 000 hours.



Figure 5 Schematic of sealed-off CO_2 laser, approximately 100 W per meter of gain length, gas cooled by diffusion to the wall.

Diffusion-cooled slab laser technology will also deliver reliable sealed operation for 20 000 hrs. Excitation of the laser medium occurs via RF excitation between two water-cooled electrodes. The water-cooled electrodes dissipate (diffusion cooled) the heat generated in the gas discharge. An unstable optical resonator provides the output coupling for such a device (see Figure 6). Output powers are in the range 5 W to 300 W and can be pulsed from 0 to 100 kHz. These lasers are widely used for marking, rapid prototyping, and cutting of nonmetals (paper, glass, plastics, ceramics) and metals.

Waveguide CO_2 lasers use small bore tubes (2–4 mm) made of BeO or SiO_2 where the laser radiation is guided by the tube walls. Due to the small tube diameter, a gas total pressure of 100 to 200 Torr is necessary, hence the gain per unit length is high. This type of laser will deliver 30 W of output power from a relatively short (50 cm long) compact sealed-off design; such a system is useful for microsurgery and scientific applications. Excitation can be provided from a longitudinal DC discharge or from an RF source that is transverse to the optical axis; RF excitation avoids the requirement for an anode and cathode and results in a much lower electrode voltage.

Slow Axial Flow Lasers

In slow flow lasers the gas mixture flows slowly through the laser cavity. This is done to remove the products of dissociation that will reduce laser efficiency or prevent it from operating at all, and the main contaminant is CO. The dissociated gases (mainly CO and O_2) can be recombined using a catalyst pack and then reused via continuous recirculation. Heat is removed via diffusion through the walls of the tube containing the active gain medium. The tube is frequently made of Pyrex glass with a concentric outer tube to facilitate water-cooling of the



Figure 6 Schematic for sealed-off slab laser and diffusion cooled laser with RF excitation (courtesy of Rofin).

laser cavity (see Figure 7). Slow flow lasers operate in the power range 100 W to 1500 W, and tend to use a longitudinal DC electrical discharge which can be made to run continuously or pulsed if a thyratron switch is build into the power supply; alternatively, electrical power can be supplied via transverse RF excitation. The power scales with length, hence high power slow flow lasers have long cavities and require multiple cavity folds in order to reduce their physical size.



Figure 7 Slow flow CO_2 laser, approximately 100 W per meter of gain length, gas cooled by diffusion to the wall.

Fast Axial Flow Lasers

The fast axial flow laser, Figure 8, can provide output powers from 1 kW to 20 kW; it is this configuration that dominates the use of CO_2 lasers for industrial applications. Industrial lasers are usually in the power range 2–4 kW. The output power from these devices scales with mass flow, hence the gas mixture is recycled through the laser discharge region at sonic or supersonic velocities. Historically this was achieved using Rootes blowers to compress the gas upstream of the laser cavity. Rootes compressors are inherently inefficient and the more advanced laser systems utilize turbine compressors, which deliver greater efficiency and better laser stability. Rootes compressors can be a major source of vibration. With this arrangement heat exchangers are required to remove heat after the laser discharge region and also after the compressor stage, as the compression process heats up the laser gases. Catalyst packs are used to regenerate gases but some gas replacement is often required. These laser systems have short cavities and use folded stable resonator designs to achieve higher output powers with extremely high-quality beams that are particularly suitable for cutting applications. They also give excellent results when used for welding and surface treatments.

Fast axial flow lasers can be excited by a longitudinal DC discharge or a transverse RF discharge. Both types of electrical excitation are common. For materials processing applications it is often important to be able to run a laser in continuous wave (CW) mode or as a high pulse repetition rate (prf) pulsed laser and to be able to switch between CW and pulsed in real time; for instance, laser cutting of accurate internal corners is difficult using CW operation but very easy using the pulsed mode of operation. Both methods of discharge excitation can provide this facility.

Diffusion Cooled Laser

The diffusion-cooled slab laser is RF excited and gives an extremely compact design capable of delivering 4.5 kW pulsed from 8 Hz to 5 kHz prf or CW with good beam quality (see Figure 6). The optical resonator is formed by the front and rear mirrors and two parallel water cooled RF-electrodes. Diffusion cooling is provided by the RF-electrodes, removing the requirement for conventional gas recirculation via Rootes blowers or turbines.



Figure 8 Fast axial flow carbon dioxide laser.

This design of laser results in a device with an extremely small footprint that has low maintenance and running costs. Applications include: cutting, welding, and surface engineering.

Fast Transverse Flow Laser

In the fast transverse flow laser (Figure 9a) the gas flow, electrical discharge, and the output beam are at right angles to each other (Figure 9b). The transverse discharge can be high voltage DC, RF, or pulsed up to 8 kHz (Figure 9c). Very high output power per unit discharge length can be obtained with an optimal total pressure (*P*) of ~100 Torr; systems are available delivering 10 kW of output power, CW or pulsed (see Figures 3a and b). The increase in total pressure requires a corresponding increase in the gas discharge electric field, *E*, as the ratio *E*/*P* must remain constant, since this determines the temperature of the discharge electrons, which have an optimum mean value (optimum energy distribution, Figure 2) for efficient excitation of the population inversion. With this high value of electric field, a longitudinal-discharge arrangement is impractical (500 kV for a 1 m discharge length); hence, the discharge is applied perpendicular to the optical axis. Fast transverse flow gas lasers provided the first multikilowatt outputs but tend to be expensive to maintain and operate. In order to obtain a reasonable beam quality, the output coupling is often obtained using a multipass unstable resonator. As the population inversion is available over a wide rectangular cross-section, this is a disadvantage of this arrangement and beam quality is not as good as that obtainable from fast axial flow designs. For this reason this type of laser is suitable for a wide range of welding and surface treatment applications.

Transversely Excited Atmospheric (TEA) Pressure

If the gas total pressure is increased above ~100 Torr it is difficult to sustain a stable glow discharge, because above this pressure instabilities degenerate into arcs within the discharge volume. This problem can be overcome by pulse excitation; using submicrosecond pulse duration, instabilities do not have sufficient time to develop; hence, the gas pressure can be increased above atmospheric pressure and the laser can be operated in a pulsed mode. In a mode locked format optical pulses shorter than 1 ns can be produced. This is called a TEA laser and with a transverse gas flow is capable of producing short high power pulses up to a few kHz repetition frequency. In order to prevent arc formation, TEA lasers usually employ ultraviolet or e-beam preionization of the gas discharge just prior to the main current pulse being applied via a thyratron switch. Output coupling is usually via an unstable resonator. TEA lasers are used for marking, remote sensing, range-finding, and scientific applications.

Conclusions

It is 40 years since Patel operated the first high power CO_2 laser. This led to the first generation of lasers which were quickly exploited for industrial laser materials processing, medical applications, defense,


Laser cavity
Flow shaping
Flow shaping
Bellows
Heat exchanger
Rootes blower
18 kW motor
Heat exchanger
(a)
I_p
Pulse current
Rear mirror
Anode
Output mirror
Gas flow
Cathode
(b)
Anode
Cathode
(c)

Figure 9 (a) Transverse flow carbon dioxide laser gas recirculator, (b) Transverse flow carbon dioxide electrodes, (c) Transverse flow carbon dioxide gas discharge as seen from the output window.

and scientific research applications; however, the first generation of lasers were quite unreliable and temperamental. After many design iterations, the CO_2 laser has now matured into a reliable, stable laser source available in many different geometries and power ranges. The low cost of ownership of the latest generation of CO_2 laser makes them a very attractive commercial proposition for many industrial and scientific applications. Commercial lasers incorporate many novel design features that are beyond the scope of this article and are often peculiar to the particular laser manufacturer. This includes gas additives and catalysts that may be required to stabilize the gas discharge of a particular laser design; it is this optimization of the laser design that has produced such reliable and controllable low-cost performance from the CO_2 laser.

List of Units and Nomenclature

α	The direct excitation of carbon dioxide (CO_2) ground state molecules (sec^{-1})
β	The direct de-excitation of nitrogen (N_2) (sec^{-1})
γ	The direct excitation of nitrogen (N_2) ground state molecules (sec^{-1})
η	The direct de-excitation of carbon dioxide (CO_2) (sec^{-1})
λ	wavelength (m)
σ	absorption coefficient (cm^2)
τ	Electrical current pulse length (μs)
τ_{sp}	Spontaneous emission life time of the upper laser level (sec)
$A = (\tau_{sp})^{-1} = 0.213(sec^{-1})$	The Einstein 'A' coefficient for the laser transition
c	velocity of light ($cm\ sec^{-1}$)
C_c	Coupling capacitance (nF)
CO_2	Carbon dioxide
e	subscript 'e' refers to the fact that the populations in the square brackets are the values for thermodynamic equilibrium
E	Electric Field ($V\ cm^{-1}$)
F_{CO_2}	Fraction of the input power (IP) coupled into the excitation of the energy level E_{00^01}
F_{N_2}	Fraction of the input power (IP) coupled into the excitation of the energy level $E_{v=1}$
g	gain (cm^{-1})
g_1 and g_2	energy level degeneracy's of levels 1 and 2
He	Helium
I	beam irradiance ($W\ cm^{-2}$)
I_0	beam irradiance at the center of a Gaussian laser beam ($W\ cm^{-2}$)
I_p	Photon population density ($photons\ cm^{-3}$)
$\mathrm{I_p}$	Input current (A)
IP	Electrical input power ($W\ cm^{-3}$)
J	the rotational quantum number
K_{51}, K_{15}	Resonant energy transfer between the CO_2 (00^01) and $N_2(v = 2)$ energy levels proceeds via excited molecules colliding with ground state molecules (sec^{-1})
K_{132}, K_{2131}, K_{2231}	are vibration/vibration transfer rates (sec^{-1}) between energy levels 1 and 32; 21 and 31; 22 and 31, respectively (see Figure 1)
K_{320}	is a vibration/translation transfer rate (sec^{-1}) between energy levels 32 and 0 (see Figure 1)
K_{sp}, A	Spontaneous emission rate (sec^{-1})
L	The distance between the back and the front mirrors, which have reflectivity's of R_B and R_F (cm)
n	molecular population ($molecules\ cm^{-3}$)
N_2	Nitrogen
P	Pressure (Torr)
P_{CO_2}, P_{He} and P_{N_2}	The respective gas partial pressures (Torr)
P_{in}	Electrical input power (kW)
r	radius of laser beam (cm)
R_B	Back mirror reflectivity
R_F	Front mirror reflectivity
t	time (sec)
T	Temperature (deg K)
T_0	the photon decay time (sec)
w	the radial distance where the power density is decreased to $1/e^2$ of its axial value

See also

Fiber and Guided Wave Optics: Overview. **Lasers:** Noble Gas Ion Lasers.

Further Reading

Anderson JD (1976) *Gasdynamic Lasers: An Introduction*. New York: Academic Press.

Chatwin CR, McDonald DW and Scott BF (1991) Design of a High P.R.F. Carbon Dioxide Laser for Processing High Damage Threshold Materials. Selected Papers on Laser Design, SPIE Milestone Series, pp. 425–433. Washington: SPIE Optical Engineering Press.

Cool AC (1969) Power and gain characteristics of high speed flow lasers. *Journal of Applied Physics* 40(9): 3563.

Crafer RC, Gibson AF, Kent MJ and Kimmit MF (1969) Time-dependent processes on CO_2 laser amplifiers. *British Journal of Applied Physics* 2(2): 183.

Gerry ET and Leonard AD (1966) Measurement of 10.6-μ CO_2 laser transition probability and optical broadening cross sections. *Applied Physics Letters* 8(9): 227.

Gondhalekar A, Heckenberg NR and Holzhauer E (1975) The mechanism of single-frequency operation of the hybrid CO_2 laser. *IEEE Journal of Quantum Electronics* QE-11(3): 103.

Gordiets BF, Sobolev NN and Shelepin LA (1968) Kinetics of physical processes in CO_2 lasers. *Soviet Physics JETP* 26(5): 1039.

Herzberg G (1945) *Molecular Spectra & Molecular Structure*. Infra-red and Raman Spectra of Polyatomic Molecules, vol. 2. New York: Van Nostrand.

Hoffman AL and Vlases GC (1972) A simplified model for predicting gain, saturation and pulse length for gas dynamic lasers. *IEEE Journal of Quantum Electronics* 8(2): 46.
Johnson DC (1971) Excitation of an atmospheric pressure CO_2–N_2–He laser by capacitor discharges. *IEEE Journal of Quantum Electronics* Q.E.-7(5): 185.
Koechner W (1988) *Solid State Laser Engineering*. Berlin: Springer Verlag.
Kogelnik H and Li T (1966) Laser beams and resonators. *Applied Optics* 5: 1550–1567.
Levine AK and De Maria AJ (1971). *Lasers*, vol. 3. New York: Marcel Dekkar, Chapter 3.
Moeller G and Ridgen JD (1965) *Applied Physics Letters* 7: 274.
Moore CB, Wood RE, Bei-Lok Hu and Yardley JT (1967) Vibrational energy transfer in CO_2 lasers. *Journal of Chemical Physics* 11: 4222.
Patel CKN (1964) *Physics Review Letters* 12: 588.
Siegman A (1986) *Lasers*. Mill Valley, California: University Science.
Smith K and Thomson RM (1978) *Computer Modeling of Gas Lasers*. New York and London: Plenum Press.
Sobolev NN and Sokovikov VV (1967) CO_2 lasers. *Soviet Physics USPEKHI* 10(2): 153.
Svelto O (1998) *Principles of Lasers*, 4th edn. New York: Plenum.
Tychinskii VP (1967) Powerful lasers. *Soviet Physics USPEKHI* 10(2): 131.
Vlases GC and Money WM (1972) Numerical modelling of pulsed electric CO_2 lasers. *Journal of Applied Physics* 43(4): 1840.
Wagner WG, Haus HA and Gustafson KT (1968) High rate optical amplification. *IEEE Journal of Quantum Electronics* Q.E.-4: 287.
Witteman W (1987) *The CO_2 Laser.* Springer Series in Optical Sciences, vol. 53.

Dye Lasers

F J Duarte, Eastman Kodak Company, New York, NY, USA

A Costela, Consejo Superior de Investigaciones Cientificas, Madrid, Spain

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Background

Dye lasers are the original tunable lasers. Discovered in the mid-1960s these tunable sources of coherent radiation span the electromagnetic spectrum from the near-ultraviolet to the near-infrared (Figure 1). Dye lasers spearheaded and sustained the revolution in atomic and molecular spectroscopy and have found use in many and diverse fields from medical to military applications. In addition to their extraordinary spectral versatility, dye lasers have been shown to oscillate from the femtosecond pulse domain to the continuous wave (cw) regime. For microsecond pulse emission, energies of up to hundreds of joules per pulse have been demonstrated. Further, operation at high pulsed repetition frequencies (prfs), in the multi-kHz regime, has provided average powers at kW levels. This unrivaled operational versatility is summarized in Table 1.

Dye lasers are excited by coherent optical energy from an excitation, or pump, laser or by optical energy from specially designed lamps called flashlamps. Recent advances in semiconductor laser



Figure 1 Approximate wavelength span from the various classes of laser dye molecules. Reproduced with permission from Duarte FJ (1995) *Tunable Laser Handbook*. New York: Academic Press.

Table 1 Emission characteristics of liquid dye lasers

Dye laser class	*Spectral coverage*[a]	*Energy per pulse*[b]	*Prf*[b]	*Power*[b]
Laser-pumped pulsed dye lasers	350–1100 nm	800 J[c]	13 kHz[d]	2.5 kW[d]
Flashlamp-pumped dye lasers	320–900 nm	400 J[e]	850 Hz[f]	1.2 kW[f]
CW dye lasers	370–1000 nm			43 W[g]

[a] Approximate range.
[b] Refers to maximum values for that particular emission parameter.
[c] Achieved with an excimer-laser pumped coumarin dye laser by Tang and colleagues, in 1987.
[d] Achieved with a multistage copper-vapor-laser pumped dye laser using rhodamine dye by Bass and colleagues, in 1992.
[e] Reported by Baltakov and colleagues, in 1974. Uses rhodamine 6G dye.
[f] Reported by Morton and Dragoo, in 1981. Uses coumarin 504 dye.
[g] Achieved with an Ar^+ laser pumped folded cavity dye laser using rhodamine 6G dye by Baving and colleagues, in 1982.

technology have made it possible to construct very compact all-solid-state excitation sources that, coupled with new solid-state dye laser materials, should bring the opportunity to build compact tunable laser systems for the visible spectrum. Further, direct diode-laser pumping of solid-state dye lasers should prove even more advantageous to enable the development of fairly inexpensive tunable narrow-linewidth solid-state dye laser systems for spectroscopy and other applications requiring low powers. Work on electrically excited organic gain media might also provide new avenues for further progress.

The literature of dye lasers is very rich and many review articles have been written describing and discussing traditional dye lasers utilizing liquid gain media. In particular, the books *Dye Lasers*, *Dye Laser Principles*, *High Power Dye Lasers*, and *Tunable Lasers Handbook* provide excellent sources of authoritative and detailed description of the physics and technology involved. In this article we offer only a survey of the operational capabilities of the dye lasers using liquid gain media in order to examine with more attention the field of solid-state dye lasers.

Brief History of Dye Lasers

1965: Quantum theory of dyes is discussed in the context of the maser (R. P. Feynman).
1966: Dye lasers are discovered (P. P. Sorokin and J. R. Lankard; F. P. Schäfer and colleagues).
1967: The flashlamp-pumped dye laser is discovered (P. P. Sorokin and J. R. Lankard; W. Schmidt and F. P. Schäfer).
1967–1968: Solid-state dye lasers are discovered (B. H. Soffer and B. B. McFarland; O. G. Peterson and B. B. Snavely).
1968: Mode-locking, using saturable absorbers, is demonstrated in dye lasers (W. Schmidt and F. P. Schäfer).
1970: The continuous-wave (cw) dye laser is discovered (O. G. Peterson, S. A. Tuccio, and B. B. Snavely).
1971: The distributed feedback dye laser is discovered (H. Kogelnik and C. V. Shank).
1971–1975: Prismatic beam expansion in dye lasers is introduced (S. A. Myers; E. D. Stokes and colleagues; D. C. Hanna and colleagues).
1972: Passive mode-locking is demonstrated in cw dye lasers (E. P. Ippen, C. V. Shank, and A. Dienes).
1972: The first pulsed narrow-linewidth tunable dye laser is introduced (T. W. Hänsch).
1973: Frequency stabilization of cw dye lasers is demonstrated (R. L. Barger, M. S. Sorem, and J. L. Hall).
1976: Colliding-pulse-mode locking is introduced (I. S. Ruddock and D. J. Bradley).
1977–1978: Grazing-incidence grating cavities are introduced (I. Shoshan and colleagues; M. G. Littman and H. J. Metcalf; S. Saikan).
1978–1980: Multiple-prism grating cavities are introduced (T. Kasuya and colleagues; G. Klauminzer; F. J. Duarte and J. A. Piper).
1981: Prism pre-expanded grazing-incidence grating oscillators are introduced (F. J. Duarte and J. A. Piper).
1982: Generalized multiple-prism dispersion theory is introduced (F. J. Duarte and J. A. Piper).
1983: Prismatic negative dispersion for pulse compression is introduced (W. Dietel, J. J. Fontaine, and J-C. Diels).
1987: Laser pulses as short as six femtoseconds are demonstrated (R. L. Fork, C. H. Brito Cruz, P. C. Becker, and C. V. Shank).
1994: First narrow-linewidth solid-state dye laser oscillator (F. J. Duarte).
1999–2000: Distributed feedback solid-state dye lasers are introduced (Wadsworth and colleagues; Zhu and colleagues).

Molecular Energy Levels

Dye molecules have large molecular weights and contain extended systems of conjugated double bonds. These molecules can be dissolved in an adequate organic solvent (such as ethanol, methanol, ethanol/water, and methanol/water) or incorporated into a solid matrix (organic, inorganic, or hybrid). These molecular gain media have a strong absorption generally in the visible and ultraviolet regions, and exhibit large fluorescence bandwidths covering the entire visible spectrum. The general energy level diagram of an organic dye is shown in Figure 2. It consists of electronic singlet and triplet states with each electronic state containing a multitude of overlapping vibrational–rotational levels giving rise to broad continuous energy bands. Absorption of visible or ultraviolet pump light excites the molecules from the ground state S_0 into some rotational–vibrational level belonging to an upper excited singlet state, from where the molecules decay nonradiatively to the lowest vibrational level of the first excited singlet state S_1 on a picosecond time-scale. From S_1 the molecules can decay radiatively, with a radiative lifetime on the nanosecond time-scale, to a higher-lying vibrational–rotational level of S_0. From this level they rapidly thermalize into the lowest vibrational–rotational levels of S_0. Alternatively, from S_1, the molecules can experience nonradiative relaxation either to the triplet state T_1 by an intersystem crossing process or to the ground state by an internal conversion process. If the intensity of the pumping radiation is high enough a population inversion between S_1 and S_0 may be attained and stimulated emission occurs. Internal conversion and intersystem crossing compete with the fluorescence decay mode of the molecule and therefore reduce the efficiency of the laser emission. The rate for internal conversion to the electronic ground state is usually negligibly small so that the most important loss process is intersystem crossing into T_1 that populates the lower metastable triplet state. Thus, absorption on the triplet–triplet allowed transitions could cause considerable losses if these absorption bands overlap the lasing band, inhibiting or even halting the lasing process. This triplet loss can be reduced by adding small quantities of appropriate chemicals that favor nonradiative transitions that shorten the effective lifetime of the T_1 level. For pulsed excitation with nanosecond pulses, the triplet–triplet absorption can be neglected because for a typical dye the intersystem crossing rate is not fast enough to build up an appreciable triplet population in the nanosecond time domain.



Figure 2 Schematic energy level diagram for a dye molecule. Full lines: radiative transitions; dashed lines: nonradiative transitions; dotted lines: vibrational relaxation.

Dye molecules are large (a typical molecule incorporates 50 or more atoms) and are grouped into families with similar chemical structures. A survey of the major classes of laser dyes is given later. Solid-state laser dye gain media are also considered later.

Liquid Dye Lasers

Laser-Pumped Pulsed Dye Lasers

Laser-pumped dye lasers use a shorter wavelength, or higher frequency, pulsed laser as the excitation or pump source. Typical pump lasers for dye lasers are gas lasers such as the excimer, nitrogen, or copper lasers. One of the most widely used solid-state laser pumps is the frequency doubled Nd:YAG laser which emits at 532 nm.

In a laser-pumped pulsed dye laser the active medium, or dye solution, is contained in an optical cell often made of quartz or fused silica, which provides an active region typically some 10 mm in length and a few mm in width. The active medium is then excited either longitudinally, or transversely, via a focusing lens using the pump laser. In the case of transverse excitation the pump laser is focused to a beam ~10 mm in width and ~0.1 mm in height. Longitudinal pumping requires focusing of the excitation beam to a diameter in the 0.1–0.15 mm range. For lasers operated at low prfs (a few pulses per second), the dye solution might be static. However, for high-prf operation (a few thousand pulses per second) the dye solution must be flowed at speeds of up to a few meters per second in order to dissipate the heat. A simple broadband optically pumped dye laser can be constructed using just the pump laser, the active medium, and two mirrors to form a resonator. In order to achieve tunable, narrow-linewidth, emission, a more sophisticated resonator must be employed. This is called a dispersive tunable oscillator and is depicted in Figure 3. In a dispersive tunable oscillator the exit side of the cavity is comprised of a partial reflector, or an output coupler, and the other end of the resonator is composed of a multiple-prism grating assembly. It is the dispersive characteristics of this multiple-prism grating assembly and the dimensions of the emission beam produced at the gain medium that determine the tunability and the narrowness, or spectral purity, of the laser emission.



Figure 3 Copper-vapor-laser pumped hybrid multiple-prism near grazing incidence (HMPGI) grating dye laser oscillator. Adapted with permission from Duarte FJ and Piper JA (1984) Narrow linewidth high prf copper laser-pumped dye-laser oscillators. *Applied Optics* 23: 1391–1394.

In order to selectively excite a single vibrational–rotational level of a molecule such as iodine (I_2), at room temperature, one needs a laser linewidth of $\Delta\nu \approx 1.5$ GHz (or $\Delta\lambda \approx 0.0017$ nm at $\lambda = 590$ nm). The hybrid multiple-prism near-grazing-incidence (HMPGI) grating dye laser oscillator illustrated in Figure 4 yields laser linewidths in the 400 MHz $\leq \Delta\nu \leq$ 650 MHz range at 4–5% conversion efficiencies whilst excited by a copper-vapor laser operating at a prf of 10 kHz. Pulse lengths are ~10 ns at full-width half-maximum (FWHM). The narrow-linewidth emission from these oscillators is said to be single-longitudinal-mode lasing because only one electromagnetic mode is allowed to oscillate.

The emission from oscillators of this class can be amplified many times by propagating the tunable narrow-linewidth laser beam through single-pass amplifier dye cells under the excitation of pump lasers. Such amplified laser emission can reach enormous average powers. Indeed, a copper-vapor-laser pumped dye laser system at the Lawrence Livermore National Laboratory (USA), designed for the laser isotope separation program, was reported to



Figure 4 Flashlamp-pumped multiple-prism grating oscillators. From Duarte FJ, Davenport WE, Ehrlich JJ and Taylor TS (1991) Ruggedized narrow-linewidth dispersive dye laser oscillator. *Optics Communications* 84: 310–316. Reproduced with permission from Elsevier.

yield average powers in excess of 2.5 kW, at a prf of 13.2 kHz, at a better than 50% conversion efficiency as reported by Bass and colleagues in 1992. Besides high conversion efficiencies, excitation with copper-vapor lasers, at $\lambda = 510.554$ nm, has the advantage of inducing little photodegradation in the active medium thus allowing very long dye lifetimes.

Flashlamp-Pumped Dye Lasers

Flashlamps utilized in dye laser excitation emit at black-body temperatures in the 20 000 K range, thus yielding intense ultraviolet radiation centered around 200 nm. One further requirement for flashlamps, and their excitation circuits, is to deliver light pulses with a fast rise time. For some flashlamps this rise time can be less than a few nanoseconds.

Flashlamp-pumped dye lasers differ from laser-pumped pulsed dye lasers mainly in the pulse energies and pulse lengths attainable. This means that flashlamp-pumped dye lasers, using relatively large volumes of dye, can yield very large energy pulses. Excitation geometries use either coaxial lamps, with the dye flowing in a quartz cylinder at the center of the lamp, or two or more linear lamps arranged symmetrically around the quartz tube containing the dye solution. Using a relatively weak dye solution of rhodamine-6G (2.2×10^{-5} M), a coaxial lamp, and an active region defined by a quartz tube 6 cm in diameter and a length of 60 cm, Baltakov and colleagues, in 1974, reported energies of 400 J in pulses 25 μs long at FWHM.

Flashlamp-pumped tunable narrow-linewidth dye laser oscillators described by Duarte and colleagues, in1991, employ a cylindrical active region 6 mm in diameter and 17 cm in length. The dye solution is made of rhodamine 590 at a concentration of 1×10^{-5} M. This active region is excited by a coaxial flashlamp. Using multiple-prism grating architectures (see Figure 4) these authors achieve a diffraction limited TEM_{00} laser beam and laser linewidths of $\Delta\nu \approx 300$ MHz at pulsed energies in the 2–3 mJ range. The laser pulse duration is reported to be $\Delta t \approx 100$ ns. The laser emission from this class of multiple-prism grating oscillator is reported to be extremely stable. The tunable narrow-linewidth emission from these dispersive oscillators is either used directly in spectroscopic, or other scientific applications, or is utilized to inject large flashlamp-pumped dye laser amplifiers to obtain multi-joule pulse energies with the laser linewidth characteristics of the oscillator.

Continuous Wave Dye Lasers

CW dye lasers use dye flowing at linear speeds of up to 10 meters per second which are necessary to remove the excess heat and to quench the triplet states. In the original cavity reported by Peterson and colleagues, in 1970, a beam from an Ar^+ laser was focused on to an active region which is contained within the resonator. The resonator comprised dichroic mirrors that transmit the blue-green radiation of the pump laser and reflect the red emission from the dye molecules. Using a pump power of about 1 W, in a TEM_{00} laser beam, these authors reported a dye laser output of 30 mW. Subsequent designs replaced the dye cell with a dye jet, an introduced external mirror, and integrated dispersive elements in the cavity. Dispersive elements such as prisms and gratings are used to tune the wavelength output of the laser. Frequency-selective elements, such as etalons and other types of interferometers, are used to induce frequency narrowing of the tunable emission. Two typical cw dye laser cavity designs are described by Hollberg, in 1990, and are reproduced here in Figure 5. The first design is a linear three-mirror folded cavity. The second one is an eight-shaped ring dye laser cavity comprised of mirrors M_1, M_2, M_3, and M_4. Linear cavities exhibit the effect of *spatial hole burning* which allows the cavity to lase in more than one longitudinal mode. This problem can be overcome in ring cavities (Figure 5b) where the laser emission is in the form of a traveling wave.

Two aspects of cw dye lasers are worth emphasizing. One is the availability of relatively high powers in single longitudinal mode emission and the other is the



Figure 5 CW laser cavities: (a) linear cavity and (b) ring cavity. Adapted from Hollberg LW (1990) CW dye lasers. In: Duarte FJ and Hillman LW (eds) *Dye Laser Principles*, pp. 185–238. New York: Academic Press. Reproduced with permission from Elsevier.

demonstration of very stable laser oscillation. First, Johnston and colleagues, in 1982, reported 5.6 W of stabilized laser output in a single longitudinal mode at 593 nm at a conversion efficiency of 23%. In this work eleven dyes were used to span the spectrum continuously from ~400 nm to ~900 nm. In the area of laser stabilization and ultra narrow-linewidth oscillation it is worth mentioning the work of Hough and colleagues, in 1984, that achieved laser linewidths of less than 750 Hz employing an external reference cavity.

Ultrashort-Pulse Dye Lasers

Ultrashort-pulse, or femtosecond, dye lasers use the same type of technology as cw dye lasers configured to incorporate a saturable absorber region. One such configuration is the ring cavity depicted in Figure 6. In this cavity the gain region is established between mirrors M_1 and M_2 whilst the saturable absorber is deployed in a counter-propagating arrangement. This arrangement is necessary to establish a collision between two counter-propagating pulses at the saturable absorber thus yielding what is known as colliding-pulse mode locking (CPM) as reported by Ruddock and Bradley, in 1976. This has the effect of creating a transient grating, due to interference, at the absorber thus shortening the pulse. Intracavity prisms were incorporated in order to introduce negative dispersion, by Dietel and colleagues in 1983, and thus subtract dispersion from the cavity and ultimately provide the compensation needed to produce femtosecond pulses.



Figure 6 Femtosecond dye laser cavities: (a) linear femtosecond cavity and (b) ring femtosecond cavity. Adapted from Diels J-C (1990) Femtosecond dye lasers. In: Duarte FJ and Hillman LW (eds) *Dye Laser Principles*, pp. 41–132. New York: Academic Press. Reproduced with permission from Elsevier.

The shortest pulse obtained from a dye laser, 6 fs, has been reported by Fork and colleagues, in 1987, using extra-cavity compression. In that experiment, a dye laser incorporating CPM and prismatic compensation was used to generate pulses that were amplified by a copper-vapor laser at a prf of 8 kHz. The amplified pulses, of a duration of 50 fs, were then propagated through two grating pairs and a four-prism sequence for further compression.

Solid-State Dye Laser Oscillators

In this section the principles of linewidth narrowing in dispersive resonators are outlined. Albeit the discussion focuses on multiple-prism grating solid-state dye laser oscillators, in particular, the physics is applicable to pulsed high-power dispersive tunable lasers in general.

Multiple-Prism Dispersion Grating Theory

The spectral linewidth in a dispersive optical system is given by

$$\Delta\lambda \approx \Delta\theta(\nabla_\lambda \theta)^{-1} \qquad [1]$$

where $\Delta\theta$ is the light beam divergence, $\nabla_\lambda = \partial/\partial\lambda$, and $\nabla_\lambda\theta$ is the overall dispersion of the optics. This identity can de derived either from the principles of geometrical optics or from the principles of generalized interferometry as described by Duarte, in 1992.

The cumulative single-pass generalized multiple-prism dispersion at the *m*th prism, of a multiple-prism array as illustrated in Figure 7, as given by Duarte and Piper, in 1982,

$$\nabla_\lambda \phi_{2,m} = H_{2,m}\nabla_\lambda n_m + (k_{1,m}k_{2,m})^{-1} \times \left(H_{1,m}\nabla_\lambda n_m \pm \nabla_\lambda \phi_{2,(m-1)}\right) \qquad [2]$$

In this equation

$$k_{1,m} = \cos\psi_{1,m}/\cos\phi_{1,m} \qquad [3a]$$

$$k_{2,m} = \cos\phi_{2,m}/\cos\psi_{2,m} \qquad [3b]$$

$$H_{1,m} = \tan\phi_{1,m}/n_m \qquad [4a]$$

$$H_{2,m} = \tan\phi_{2,m}/n_m \qquad [4b]$$



Figure 7 Generalized multiple-prism arrays in (a) additive and (b) compensating configurations. From Duarte FJ (1990) Narrow-linewidth pulsed dye laser oscillators. In: Duarte FJ and Hillman LW (eds) *Dye Laser Principles*, pp. 133–183. New York: Academic Press. Reproduced with permission from Elsevier.

Here, $k_{1,m}$ and $k_{2,m}$ represent the physical beam expansion experienced by the incident and the exit beams, respectively.

Equation [2] indicates that $\nabla_\lambda \phi_{2,m}$, the cumulative dispersion at the mth prism, is a function of the geometry of the mth prism, the position of the light beam relative to this prism, the refractive index of the prism, and the cumulative dispersion up to the previous prism $\nabla_\lambda \phi_{2,(m-1)}$.

For an array of r identical isosceles, or equilateral, prisms arranged symmetrically, in an additive configuration, so that the angles of incidence and emergence are the same, the cumulative dispersion reduces to

$$\nabla_\lambda \phi_{2,r} = r \nabla_\lambda \phi_{2,1} \qquad [5]$$

Under these circumstances the dispersions add in a simple and straightforward manner. For configurations incorporating right-angle prisms, the dispersions need to be handled mathematically in a more subtle form.

The generalized double-pass, or return-pass, dispersion for multiple-prism beam expanders was introduced by Duarte, in 1985:

$$\nabla_\lambda \Phi_P = 2M_1M_2 \sum_{m=1}^{r} (\pm 1) H_{1,m} \left(\prod_{j=m}^{r} k_{1,j} \prod_{j=m}^{r} k_{2,j} \right)^{-1} \nabla_\lambda n_m + 2 \sum_{m=1}^{r} (\pm 1) H_{2,m} \left(\prod_{j=1}^{m} k_{1,j} \prod_{j=1}^{m} k_{2,j} \right) \nabla_\lambda n_m \qquad [6]$$

Here, M_1 and M_2 are the beam magnification factors given by

$$M_1 = \prod_{m=1}^{r} k_{1,m} \qquad [7a]$$

$$M_2 = \prod_{m=1}^{r} k_{2,m} \qquad [7b]$$

For a multiple prism expander designed for an orthogonal beam exit, and Brewster's angle of incidence, eqn [6] reduces to the succinct expression given by Duarte, in 1990:

$$\nabla_\lambda \Phi_P = 2 \sum_{m=1}^{r} (\pm 1)(n_m)^{m-1} \nabla_\lambda n_m \qquad [8]$$

Equation [6] can be used to either quantify the overall dispersion of a given multiple-prism beam expander or to design a prismatic expander yielding zero dispersion, that is, $\nabla_\lambda \Phi_P = 0$, at a given wavelength.

Physics and Architecture of Solid-State Dye-Laser Oscillators

The first high-performance narrow-linewidth tunable laser was introduced by Hänsch in 1972. This laser yielded a linewidth of $\Delta\nu \approx 2.5$ GHz (or $\Delta\lambda \approx 0.003$ nm at $\lambda \approx 600$ nm) in the absence of an intracavity etalon. Hänsch demonstrated that the laser linewidth from a tunable laser was narrowed significantly when the beam incident on the tuning grating was expanded using an astronomical telescope. The linewidth equation including the intracavity beam magnification factor can be written as

$$\Delta\lambda \approx \Delta\theta(M\nabla_\lambda\Theta_G)^{-1} \qquad [9]$$

From this equation, it can be deduced that a narrow $\Delta\lambda$ is achieved by reducing $\Delta\theta$ and increasing the overall intracavity dispersion ($M\nabla_\lambda\Theta_G$). The intracavity dispersion is optimized by expanding the size of the intracavity beam incident on the diffractive surface of the tuning grating until it is totally illuminated.

Hänsch used a two-dimensional astronomical telescope to expand the intracavity beam incident on the diffraction grating. A simpler beam expansion method consists in the use of a single-prism beam expander as disclosed by several authors (Myers, 1971; Stokes and colleagues, 1972; Hanna and colleagues, 1975). An extension and improvement of this approach was the introduction of multiple-prism beam expanders as reported by Kasuya and colleagues, in 1978, Klauminzer, in 1978, and Duarte and Piper, in 1980. The main advantages of multiple-prism beam expanders, over two-dimensional telescopes, are simplicity, compactness, and the fact that the beam expansion is reduced from two dimensions to one dimension. Physically, as explained previously, prismatic beam expanders also introduce a dispersion component that is absent in the case of the astronomical telescope. Advantages of multiple-prism beam expanders over single-prism beam expansion are higher transmission efficiency, lower amplified spontaneous emission levels, and the flexibility to either augment or reduce the prismatic dispersion.

In general, for a pulsed multiple-prism grating oscillator, Duarte and Piper, in 1984, showed that the return-pass dispersive linewidth is given by

$$\Delta\lambda = \Delta\theta_R(MR\nabla_\lambda\Theta_G + R\nabla_\lambda\Phi_P)^{-1} \qquad [10]$$

where R is the number of return-cavity passes. The grating dispersion in this equation, $\nabla_\lambda\Theta_G$, can be either from a grating in Littrow or near grazing-incidence configuration. The multiple-return-pass equation for the beam divergence was given by Duarte, in 2001:

$$\Delta\theta_R = (\lambda/\pi w)\left(1 + (L_R/B_R)^2 + (A_R L_R/B_R)^2\right)^{1/2} \qquad [11]$$

Here, $L_R = (\pi w^2/\lambda)$ is the Rayleigh length of the cavity, w is the beam waist at the gain region, while A_R and B_R are the corresponding multiple-return-pass elements derived from propagation matrices.

At present, very compact and optimized multiple-prism grating tunable laser oscillators are found in two basic cavity architectures. These are the multiple-prism Littrow (MPL) grating laser oscillator, reported by Duarte in 1999 and illustrated in Figure 8, and the hybrid multiple-prism near grazing-incidence (HMPGI) grating laser oscillator, introduced by Duarte in 1997 and depicted in Figure 9. In early MPL grating oscillators the individual prisms integrating the multiple-prism expander were deployed in an additive configuration thus adding the cumulative dispersion to that of the grating and thus contributing to the overall dispersion of the cavity. In subsequent architectures the prisms were deployed in compensating configurations so as to yield zero dispersion and thus allow the tuning characteristics of the cavity to be



Figure 8 MPL grating solid-state dye laser oscillator: optimized architecture. The physical dimensions of the optical components of this cavity are shown to scale. The length, of the solid-state dye gain medium, along the optical axis, is 10 mm. Reproduced with permission from Duarte FJ (1999) Multiple-prism grating solid-state dye laser oscillator: optimized architecture. *Applied Optics* 38: 6347–6349.



Figure 9 HMPGI grating solid-state dye laser. Schematics to scale. The length of the solid state dye gain medium, along the optical axis, is 10 mm. Reproduced with permission from Duarte FJ (1997) Multiple-prism near-grazing-incidence grating solid-state dye laser oscillator. *Optics and Laser Technology* 29: 513–516.

determined by the grating exclusively. In this approach the principal role of the multiple-prism array is to expand the beam incident on the grating thus augmenting significantly the overall dispersion of the cavity as described in eqns [9] or [10]. In this regard, it should be mentioned that beam magnification factors of up to 100, and beyond, have been reported in the literature. Using solid-state laser dye gain media, these MPL and HMPGI grating laser oscillators deliver tunable single-longitudinal-mode emission at laser linewidths 350 MHz $\leq \Delta\nu \leq$ 375 MHz and pulse lengths in the 3–7 ns (FWHM) range. Long-pulse operation of this class of multiple-prism grating oscillators has been reported by Duarte and colleagues, in 1998. In these experiments laser linewidths of $\Delta\nu \approx$ 650 MHz were achieved at pulse lengths in excess of 100 ns (FWHM) under flashlamp-pumped dye laser excitation.

The dispersive cavity architectures described here have been used with a variety of laser gain media in the gas, the liquid, and the solid state. Applications to tunable semiconductor lasers have also been reported by Zorabedian, in 1992, Duarte, in 1993, and Fox and colleagues, in 1997.

Concepts important to MPL and HMPGI grating tunable laser oscillators include the emission of a single-transverse-mode (TEM_{00}) laser beam in a compact cavity, the use of multiple-prism arrays, the expansion of the intracavity beam incident on the grating, the control of the intracavity dispersion, and the quantification of the overall dispersion of the multiple-prism grating assembly via generalized dispersion equations. Sufficiently high intracavity dispersion leads to the achievement of return-pass dispersive linewidths close to the free-spectral range of the cavity. Under these circumstances single-longitudinal-mode lasing is readily achieved as a result of multipass effects.

A Note on the Cavity Linewidth Equation

So far we have described how the cavity linewidth equation

$$\Delta\lambda \approx \Delta\theta(\nabla_\lambda \theta)^{-1}$$

and the dispersion equations can be applied to achieve highly coherent, or very narrow-linewidth, emission. It should be noted that the same physics can be applied to achieve ultrashort, or femtosecond, laser pulses. It turns out that intracavity prisms can be configured to yield negative dispersion as described by Duarte and Piper, in 1982, Dietel and colleagues, in 1983, and Fork and colleagues in 1984. This negative dispersion can reduce significantly the overall dispersion of the cavity. Under those circumstances, eqn [1] predicts broadband emission which according to the uncertainty principle, in the form of,

$$\Delta\nu\Delta t \approx 1 \qquad [12]$$

can lead to very short pulse emission since $\Delta\nu$ and $\Delta\lambda$ are related by the identities

$$\Delta\lambda \approx \lambda^2/\Delta x \qquad [13]$$

and

$$\Delta\nu \approx c/\Delta x \qquad [14]$$

Distributed-Feedback Solid-State Dye Lasers

Recently, narrow-linewidth laser emission from solid-state dye lasers has also been obtained using a distributed-feedback (DFB) configuration by Wadsworth and colleagues, in 1999, and Zhu and colleagues, in 2000. As is well known, in a DFB laser no external cavity is required, the feedback being provided by Bragg reflection from a permanently or dynamically written grating structure within the gain medium as reported by Kogelnik and Shank, in 1971. By using a DFB laser configuration where the interference of two pump beams induces the required periodic modulation in the gain medium, laser emission with linewidth in the 0.01–0.06 nm range have been reported. Specifically, Wadsworth and colleagues reported a laser linewidth of 12 GHz (0.016 nm at 616 nm) using Perylene Red doped PMMA at a conversion efficiency of 20%.

It should also be mentioned that the DFB laser is also a dye laser development that has found wide and extensive applicability in semiconductor lasers employed in the telecommunications industry.

Laser Dye Survey

Cyanines

These are red and near-infrared dyes which present long conjugated methine chains (!CH = CH!) and are useful in the spectral range longer than 800 nm, where no other dyes compete with them. An important laser dye belonging to this class is 4-dicyanomethylene-2-methyl-6-(*p*-dimethylamino-styryl)-4H-pyran (DCM, Figure 10a), with laser emission in the 600–700 nm range depending on the pump and solvent, liquid or solid, used.

Xanthenes

These dyes have a xanthene ring as the chromophore and are classified into rhodamines, incorporating



Figure 10 Molecular structures of some common laser dyes: (a) DCM; (b) Rh6G; (c) PM567; (d) Perylene Orange (R = H) and Perylene Red (R = C_4H_6O); (e) Coumarin 307 (also known as Coumarin 503); (f) Coumarin 153 (also known as Coumarin 540A).

amino radicals substituents, and fluoresceins, with hydroxyl (OH) radical substituents. They are generally very efficient and chemically stable and their emission covers the wavelength region from 500 to 700 nm.

Rhodamine dyes are the most important group of all laser materials, with rhodamine 6G (Rh6G, Figure 10b), also called rhodamine 590 chloride, being probably the best known of all laser dyes. Rh6G exhibits an absorption peak, in ethanol, at 530 nm and a fluorescence peak at 556 nm, with laser emission typically in the 550–620 nm region. It has been demonstrated to lase efficiently both in liquid and solid solutions.

Pyrromethenes

Pyrromethene.BF_2 complexes are a new class of laser dyes synthesized and characterized more recently as reported by Shah and colleagues, in 1990, Pavlopoulos and colleagues, in 1990, and Boyer and colleagues, in 1993. These laser dyes exhibit reduced triplet–triplet absorption over their fluorescence and lasing spectral region while retaining a high quantum fluorescence yield. Depending on the substituents on the chromophore, these dyes present laser emission over the spectral region from the green/yellow to the red, competing with the rhodamine dyes and have been demonstrated to lase with good performance when incorporated into solid hosts. Unfortunately, they are relatively unstable because of the aromatic amine groups in their structure, which render them vulnerable to photochemical reactions with oxygen as indicated by Rahn and colleagues, in 1997. The molecular structure of a representative and well-known dye of this class, 1,3,5,7,8-pentamethyl-2,6-diethylpyrromethene-difluoroborate complex (pyrromethene 567, PM567) is shown in Figure 10c. Recently, analogs of dye PM567 substituted at position 8 with an acetoxypolymethylene linear chain or a polymerizable methacryloyloxy polymethylene chain have been developed. These new dipyrromethene.BF_2 complexes have demonstrated improved efficiency and better photostability than the parent compound both in liquid and solid state.

Conjugated Hydrocarbons

This class of organic compounds includes perylenes, stilbenes, and *p*-terphenyl. Perylene and perylimide dyes are large, nonionic, nonpolar molecules (Figure 10d) characterized by their extreme photostability and negligible singlet–triplet transfer, as discussed by Seybold and Wagenblast and colleagues, in 1989, which have high quantum efficiency because of the absence of nonradiative relaxation. The perylene dyes exhibit limited solubility in conventional solvents but dissolve well in acetone, ethyl acetate, and methyl methacrylate, with emission wavelengths in the orange and red spectral regions.

Stilbene dyes are derivatives of uncyclic unsaturated hydrocarbons such as ethylene and butadiene, with emission wavelengths in the 400–500 nm range. Most of them end in phenyl radicals. Although they are chemically stable, their laser performance is inferior to that of coumarins. *p*-Terphenyl is a valuable and efficient *p*-oligophenylene dye with emission in the ultraviolet.

Coumarins

Coumarin derivatives are a popular family of laser dyes with emission in the blue-green region of the spectrum. Their structure is based on the coumarin ring (Figure 10e,f) with different substituents that strongly affect its chemical characteristics and allow covering an emission spectral range between 420 and 580 nm. Some members of this class rank among the most efficient laser dyes known, but their chemical photobleaching is rapid compared with xanthene and pyrromethene dyes. An additional class of blue-green dyes is the tetramethyl derivatives of coumarin dyes introduced by Chen and colleagues, in 1988. The emission from these dyes spans the spectrum in the 453–588 nm region. These coumarin analogs exhibit improved efficiency, higher solubility, and better lifetime characteristics than the parent compounds.

Azaquinolone Derivatives

The quinolone and azaquinolone derivatives have a structure similar to that of coumarins but with their laser emission range extended toward the blue by 20–30 nm. The quinolone dyes are used when laser emission in the 400–430 nm region is required. Azaquinolone derivatives, such as 7-dimethylamino-1-methyl-4-metoxy-8-azaquinolone-2 (LD 390), exhibit laser action below 400 nm.

Oxadiazole Derivatives

These are compounds which incorporate an axodiazole ring with aryl radical substituents and which lase in the 330–450 nm spectral region. Dye 2-(4-biphenyl)-5-(4-*t*-butylphenyl)-1,3,4-oxadiazole (PBD), with laser emission in the 355–390 nm region, belongs to this family.

Solid-State Laser Dye Matrices

Although some first attempts to incorporate dye molecules into solid matrices were already made in the early days of development of dye lasers, it was not until the late 1980s that host materials with the required properties of optical quality and high damage threshold to laser radiation began to be developed. In subsequent years, the synthesis of new high-performance dyes and the implementation of new ways of incorporating the organic molecules into the solid matrix resulted in significant advances towards the development of practical tunable solid-state dye lasers. A recent detailed review of the work done in this field has been given by Costela *et al.*

Inorganic glasses, transparent polymers, and inorganic–organic hybrid matrices have been successfully used as host matrices for laser dyes. Inorganic glasses offer good thermal and optical properties but present the difficulty that the high melting temperature employed in the traditional process of glass making would destroy the organic dye molecules. It was not until the development of the low-temperature sol-gel technique for the synthesis of glasses that this limitation was overcome. The sol-gel process, based on inorganic polymerization reactions performed at about room temperature and starting with metallo-organic compounds such as alkoxides or salts, as reported by Brinker and Scherrer, in 1989, provides a safe route for the preparation of rigid, transparent, inorganic matrix materials incorporating laser dyes. Disadvantages of these materials are the possible presence of impurities embedded in the matrix or the occurrence of interactions between the dispersed dye molecules and the inorganic structure (hydrogen bonds, van der Waals forces) which, in certain cases, can have a deleterious effect on the lasing characteristics of the material.

The use of matrices based on polymeric materials to incorporate organic dyes offers some technical and economical advantages. Transparent polymers exhibit high optical homogeneity, which is extremely important for narrow-linewidth oscillators, as explained by Duarte, in 1994, good chemical compatibility with organic dyes, and allow control over structure and chemical composition making possible the modification, in a controlled way, of relevant properties of these materials such as polarity, free volume, molecular weight, or viscoelasticity. Furthermore, the polymeric materials are amenable to inexpensive fabrication techniques, which facilitate miniaturization and design of integrated optical systems. The dye molecules can be either dissolved in the polymer or linked covalently to the polymeric chains.

In the early investigations on the use of solid polymer matrices for laser dyes, the main problem to be solved was that of the low resistance to laser radiation exhibited by the then existing materials. In the late 1980s and early 1990s new modified polymeric organic materials began to be developed with a laser-radiation-damage threshold comparable to that of inorganic glasses and crystals as reported by Gromov and colleagues, in 1985, and Dyumaev and colleagues, in 1992. This, together with the above-mentioned advantages, made the use of polymers in solid-state dye lasers both attractive and competitive.

An approach that intends to bring about materials in which the advantages of both inorganic glasses and polymers are preserved but the difficulties are avoided is that of using inorganic–organic hybrid matrices. These are silicate-based materials, with an inorganic Si–O–Si backbone, prepared from organosilane precursors by sol-gel processing in combination with organic cross-linking of polymerizable monomers as reported by Novak, in 1993, Sanchez and Ribot, in 1994, and Schubert, in 1995. In one procedure, laser dyes are mixed with organic monomers, which are then incorporated into the porous structure of a sol-gel inorganic matrix by immersing the bulk in the solution containing monomer and catalyst or photoinitiator as indicated by Reisfeld and Jorgensen, in 1991, and Bosch and colleagues, in 1996. Alternatively, hybrids can be obtained from organically modified silicon alkoxides, producing the so-called ORMOCERS (organically modified ceramics) or ORMOSILS (organically modified silanes) as reported by Reisfeld and Jorgensen, in 1991. An inconvenient aspect of these materials is the appearance of optical inhomogeneities in the medium due to the difference in the refractive index between the organic and inorganic phases as well as to the difference in density between monomer and polymer which causes stresses and the formation of optical defects. As a result, spatial inhomogeneities appear in the laser beam, thereby decreasing its quality as discussed by Duarte, in 1994.

Organic Hosts

The first polymeric materials with improved resistance to damage by laser radiation were obtained by Russian workers, who incorporated rhodamine dyes into modified poly(methyl methacrylate) (MPMMA), obtained by doping PMMA with low-molecular weight additives. Some years later, in 1995, Maslyukov and colleagues demonstrated lasing efficiencies in the range 40–60% with matrices of MPMMA doped with rhodamine dyes pumped longitudinally at 532 nm, with a useful lifetime (measured as a 50% efficiency drop) of 15 000 pulses at a prf of 3.33 Hz.

In 1995, Costela and colleagues used an approach based on adjusting the viscoelastic properties of the material by modifying the internal plasticization of the polymeric medium by copolymerization with appropriate monomers. Using dye Rh6G dissolved in a copolymer of 2-hydroxyethyl methacrylate (HEMA) and methyl methacrylate (MMA) and transversal pumping at 337 nm, they demonstrated laser action with an efficiency of 21% and useful lifetime of 4500 pulses (20 GJ/mol in terms of total input energy per mole of dye molecule when the output energy is down to 50% of its initial value). The useful lifetime increased to 12 000 pulses when the Rh6G chromophore was linked covalently to the polymeric chains as reported by Costela and colleagues, in 1996.

Comparative studies on the laser performance of Rh6G incorporated either in copolymers of HEMA and MMA or in MPMMA were carried out by Giffin and colleagues, in 1999, demonstrating higher efficiency of the MPMMA materials but superior normalized photostability (up to 240 GJ/mol) of the copolymer formulation.

Laser conversion efficiencies in the range 60–70% for longitudinal pumping at 532 nm were reported by Ahmad and colleagues, in 1999, with PM567 dissolved in PMMA modified with 1,4-diazobicyclo[2,2,2] octane (DABCO) or perylene additives. When using DABCO as an additive, a useful lifetime of up to 550 000 pulses, corresponding to a normalized photostability of 270 GJ/mol, was demonstrated at a 2 Hz prf.

Much lower efficiencies and photostabilities have been obtained with dyes emitting in the blue-green spectral region. Costela and colleagues, in 1996, performed some detailed studies on dyes coumarin 540A and coumarin 503 incorporated into methacrylate homopolymers and copolymers, and demonstrated efficiencies of at most 19% with useful lifetimes of up to 1200 pulses, at a 2 Hz prf, for transversal pumping at 337 nm. In 2000, Somasundaram and Ramalingam obtained useful lifetimes of 5240 and 1120 pulses, respectively, for coumarin 1 and coumarin 490 dyes incorporated into PMMA rods modified with ethyl alcohol, under transversal pumping at 337 nm and a prf of 1 Hz.

A detailed study of photo-physical parameters of R6G-doped HEMA-MMA gain media was performed by Holzer and colleagues, in 2000. Among the parameters determined by these authors are quantum yields, lifetimes, absorption cross-sections, and emission cross-sections. A similar study on the photophysical parameters of PM567 and two PM567 analogs incorporated into solid matrices of different acrylic copolymers and in corresponding mimetic liquid solutions was performed by Bergmann and colleagues, in 2001.

Preliminary experiments with rhodamine 6G-doped MPMMA at high prfs were conducted using a frequency-doubled Nd:YAG laser at 5 kHz by Duarte and colleagues, in 1996. In those experiments, involving longitudinal excitation, the pump laser was allowed to fuse a region at the incidence window of the gain medium so that a lens was formed. This lens and the exit window of the gain medium comprised a short unstable resonator that yielded broadband emission. In 2001, Costela and colleagues demonstrated lasing in rhodamine 6G- and pyrromethene-doped polymer matrices under copper-vapor-laser excitation at prfs in the 1.0–6.2 kHz range. In these experiments, the dye-doped solid-state matrix was rotated at 1200 rpm. Average powers of 290 mW were obtained at a prf of 1 kHz and a conversion efficiency of 37%. For a short period of time average powers of up to 1 W were recorded at a prf of 6.2 kHz. In subsequent experiments by Abedin and colleagues the rpf was increased to 10 kHz by using as pump laser a diode-pumped, *Q*-switched, frequency doubled, solid state Nd:YLF laser. Initial average powers of 560 mW and 430 mW were obtained for R6G-doped and PM567-doped polymer matrices, respectively. Lasing efficiency was 16% for R6G and the useful lifetime was 6.6 min (or about 4.0 million shots).

Inorganic and Hybrid Hosts

In 1990, Knobbe and colleagues and McKiernan and colleagues, from the University of California at Los Angeles, incorporated different organic dyes, via the sol-gel techniques, into silicate (SiO_2), aluminosilicate (Al_2O_3–SiO_2), and ORMOSIL host matrices, and investigated the lasing performance of the resulting materials under transversal pumping. Lasing efficiencies of 25% and useful lifetimes of 2700 pulses at 1 Hz repetition rate were obtained from Rh6G incorporated into aluminosilicate gel and ORMOSIL matrices, respectively. When the dye in the ORMOSIL matrices was coumarin 153, the useful lifetime was still 2250 pulses. Further studies by Altman and colleagues, in 1991, demonstrated useful lifetimes of 11 000 pulses at a 30 Hz prf when rhodamine 6G perchlorate was incorporated into ORMOSIL matrices. The useful lifetime increased to 14 500 pulses when the dye used was rhodamine B.

When incorporated into xerogel matrices, pyrromethene dyes lase with efficiencies as high as the highest obtained in organic hosts but with much higher photostability: a useful lifetime of 500 000 pulses at 20 Hz repetition rate was obtained by Faloss and colleagues, in 1997, with PM597 using a pump energy of 1 mJ. The efficiency of PM597 dropped to 40% but its useful lifetime increased to over 1 000 000 pulses when oxygen-free samples were prepared, in agreement with previous results that documented the strong dependence of laser parameters of pyrromethene dyes on the presence of oxygen. A similar effect was observed with perylene dyes: deoxygenated xerogel samples of Perylene Red exhibited a useful lifetime of 250 000 pulses at a prf of 5 Hz and 1 mJ pump energy, to be compared with a useful lifetime of only 10 000 pulses obtained with samples prepared in normal conditions. Perylene Orange incorporated into polycom glass and pumped longitudinally at 532 nm gave an efficiency of 72% and a useful lifetime of 40 000 pulses at a prf of 1 Hz as reported by Rhan and King, in 1998.

A direct comparison study of laser performance of Rh6G, PM567, Perylene Red, and Perylene Orange in organic, inorganic, and hybrid hosts was carried out by Rahn and King in 1995. They found that the nonpolar perylene dyes had better performance in partially organic hosts, whereas the ionic rhodamine and pyrromethene dyes performed best in the inorganic sol-gel glass host. The most promising combinations of dye and host for efficiency and photostability were found to be Perylene Orange in polycom glass and Rh6G in sol-gel glass.

An all-solid-state optical configuration, where the pump was a laser diode array side-pumped, Q-switched, frequency-doubled, Nd:YAG slab laser, was demonstrated by Hu and colleagues, in 1998, with dye DCM incorporated into ORMOSIL matrices. A lasing efficiency of 18% at the wavelength of 621 nm was obtained, and 27 000 pulses were needed for the output energy to decrease by 10% of its initial value at 30 Hz repetition rate. After 50 000 pulses the output energy decreased by 90% but it could be recovered after waiting for a few minutes without pumping.

Violet and ultraviolet laser dyes have also been incorporated into sol-gel silica matrices and their lasing properties evaluated under transversal pumping by a number of authors. Although reasonable efficiencies have been obtained with some of these laser dyes, the useful lifetimes are well below 1000 pulses.

More recently, Costela and colleagues have demonstrated improved conversion efficiencies in dye-doped inorganic–organic matrices using pyrromethene 567 dye. The solid matrix in this case is poly-trimethyl-silyl-methacrylate cross-linked with ethylene glycol and copolymerized with methyl methacrylate. Also, Duarte and James have reported on dye-doped polymer-nanoparticle laser media where the polymer is PMMA and the nanoparticles are made of silica. These authors report TEM_{00} laser beam emission and improved dn/dT coefficients of the gain media that results in reduced $\Delta\theta$.

Dye Laser Applications

Dye lasers generated a renaissance in diverse applied fields such as isotope separation, medicine, photochemistry, remote sensing, and spectroscopy. Dye lasers have also been used in many experiments that have advanced the frontiers of fundamental physics.

Central to most applications of dye lasers is their capability of providing coherent narrow-linewidth radiation that can be tuned continuously from the near ultraviolet, throughout the visible, to the near infrared. These unique coherent and spectral properties have made dye lasers particularly useful in the field of high-resolution atomic and molecular spectroscopy. Dye lasers have been successfully and extensively used in absorption and fluorescence spectroscopy, Raman spectroscopy, selective excitations, and nonlinear spectroscopic techniques. Well documented is their use in photochemistry, that is, the chemistry of optically excited atoms and molecules, and in biology, studying biochemical reaction kinetics of biological molecules. By using nonlinear optical techniques, such as harmonic and sum frequency and difference frequency generation, the properties of dye lasers can be extended to the ultraviolet.

Medical applications of dye lasers include cancer photodynamic therapy, treatment of vascular lesions, and lithotripsy as described by Goldman in 1990.

The ability of dye lasers to provide tunable sub-GHz linewidths in the orange-red portion of the spectrum, at kW average powers, made them particularly suited to atomic vapor laser isotope separation of uranium as reported by Bass and colleagues, in 1992, Singh and colleagues, in 1994, and Nemoto and colleagues, in 1995. In this particular case the isotopic shift between the two uranium isotopes is a few GHz. Using dye lasers yielding $\Delta\nu \leq 1$ GHz the ^{235}U can be selectively excited in a multistep process by tuning the dye laser(s) to specific wavelengths, in the orange-red spectral region, compatible with a transition sequence leading to photoionization. Also, high-prf narrow-linewidth dye lasers, as described by Duarte and Piper, in 1984, are ideally suited for guide star applications in astronomy. This particular application requires a high-average power diffraction-limited laser beam at $\lambda \approx 589$ nm to propagate for some 95 km, above the surface of the Earth, and illuminate a layer of sodium atoms. Ground detection of the fluorescence from the sodium atoms allows measurements on the turbulence of the atmosphere. These measurements are then used to control the adaptive optics of the telescope thus compensating for the atmospheric distortions.

A range of industrial applications is also amenable to the wavelength agility and high-average power output characteristics of dye lasers. Furthermore, tunability coupled with narrow-linewidth emission, at large pulsed energies, make dye lasers useful in military applications such as directed energy and damage of optical sensors.

The Future of Dye Lasers

Predicting the future is rather risky. In the early 1990s, articles and numerous advertisements in commercial laser magazines predicted the demise and even the oblivion of the dye laser in a few years. It did not turn out this way. The high power and wavelength agility available from dye lasers have ensured their continued use as scientific and research tools in physics, chemistry, and medicine. In addition, the advent of narrow-linewidth solid-state dye lasers has sustained a healthy level of research and development in the field. Today, some 20 laboratories around the world are engaged in this activity.

The future of solid-state dye lasers depends largely on synthetic and manufacturing improvements. There is a need for strict control of the conditions of fabrication and a careful purification of all the compounds involved. In the case of polymers, in particular, stringent control of thermal conditions during the polymerization step is obligatory to ensure that adequate optical uniformity of the polymer matrix is achieved, and that intrinsic anisotropy developed during polymerization is minimized. From an engineering perspective what are needed are dye-doped solid-state media with improved photostability characteristics and better thermal properties. By better thermal properties is meant better dn/dT factors. To a certain degree progress in this area has already been reported. As in the case of liquid dye lasers, the lifetime of the material can be improved by using pump lasers at compatible wavelengths. In this regard, direct diode laser pumping of dye-doped solid-state matrices should lead to very compact, long-lifetime, tunable lasers emitting throughout the visible spectrum. An example of such a device would be a green laser-diode-pumped rhodamine-6G doped MPMMA tunable laser configured in a multiple-prism grating architecture.

As far as liquid lasers are concerned, there is a need for efficient water-soluble dyes. Successful developments in this area were published in the literature with coumarin-analog dyes by Chen and colleagues, in 1988, and some encouraging results with rhodamine dyes have been reported by Ray and colleagues, in 2002. Efficient water-soluble dyes could lead to significant improvements and simplifications in high-power tunable lasers.

See also

Coherent Control: Experimental. **Nonlinear Optics, Applications:** Pulse Compression via Nonlinear Optics. **Quantum Optics:** Entanglement and Quantum Information. **Relativistic Nonlinear Optics**.

Further Reading

Costela A, García-Moreno I and Sastre R (2001) In: Nalwa HS (ed.) *Handbook of Advanced Electronic and Photonic Materials and Devices*, vol. 7, pp. 161–208. San Diego, CA: Academic Press.

Diels J-C and Rudolph W (1996) *Ultrashort Laser Pulse Phenomena*. New York: Academic Press.

Demtröder W (1995) *Laser Spectroscopy*, 2nd edn. Berlin: Springer-Verlag.

Duarte FJ (ed.) (1991) *High Power Dye Lasers*. Berlin: Springer-Verlag.

Duarte FJ (ed.) (1995) *Tunable Lasers Handbook*. New York: Academic Press.

Duarte FJ (ed.) (1995) *Tunable Laser Applications*. New York: Marcel Dekker.

Duarte FJ (2003) *Tunable Laser Optics*. New York: Elsevier Academic.

Duarte FJ and Hillman LW (eds) (1990) *Dye Laser Principles*. New York: Academic Press.

Maeda M (1984) *Laser Dyes*. New York: Academic Press.

Schäfer FP (ed.) (1990) *Dye Lasers*, 3rd edn. Berlin: Springer-Verlag.

Radziemski LJ, Solarz RW and Paisner JA (eds) (1987) *Laser Spectroscopy and its Applications*. New York: Marcel Dekker.

Weber MJ (2001) *Handbook of Lasers*. New York: CRC.

Edge Emitters

J J Coleman, University of Illinois, Urbana, IL, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The semiconductor edge emitting diode laser is a critical component in a wide variety of applications, including fiber optics telecommunications, optical data storage, and optical remote sensing. In this section, we describe the basic structures of edge emitting diode lasers and the physical mechanisms for converting electrical current into light. Laser waveguides and cavity resonators are also outlined. The power, efficiency, gain, loss, and threshold characteristics of laser diodes are presented along with the effects of temperature and modulation. Quantum well lasers are outlined and a description of grating coupled lasers is provided.

Like all forms of laser, the edge emitting diode laser is an oscillator and has three principal components; a mechanism for converting energy into light, a medium that has positive optical gain, and a mechanism for obtaining optical feedback. The basic edge emitting laser diode is shown schematically in Figure 1. Current flow is vertical through a pn junction and light is emitted from the ends. The dimensions of the laser in Figure 1 are distorted, in proportion to typical real laser diodes, to reveal more detail. In practical laser diodes, the width of the stripe contact is actually much smaller than shown and the thickness is smaller still. Typical dimensions are (stripe width × thickness × length) $2 \times 100 \times 1000\ \mu\text{m}$. Light emission is generated only within a few micrometers of the surface, which means that 99.98% of the volume of this small device is inactive.

Energy conversion in diode lasers is provided by current flowing through a forward-biased pn junction. At the electrical junction, there is a high density of injected electrons and holes which can recombine in a direct energy gap semiconductor material to give an emitted photon. Charge neutrality requires equal numbers of injected electrons and holes. Figure 2 shows a simplified energy versus momentum (E–k) diagrams for (a) direct, and (b) indirect semiconductors. In a direct energy gap material, such as GaAs, the energy minima have the same momentum vector, so recombination of an electron in the conduction band and a hole in the valence band takes place directly. In an indirect material, such as silicon, momentum conservation requires the participation of a third particle – a phonon. This third-order process is far less efficient than direct recombination and, thus far, too inefficient to support laser action.

Optical gain in direct energy gap materials is obtained when population inversion is reached.



Figure 1 Schematic drawing of an edge emitting laser diode.



Figure 2 Energy versus momentum for (a) direct, and (b) indirect semiconductors.



Figure 3 Density of states versus energy for conduction and valence bands.

Population inversion is the condition where the probability for stimulated emission exceeds that of absorption. The density of excited electrons n, in the conduction band is given by

$$n = \int_{E_c}^{\infty} \rho_n(E) f_n(E) \mathrm{d}E \text{ cm}^{-3} \qquad [1]$$

where $\rho_n(E)$ is the conduction band density of states function and $f_n(E)$ is the Fermi occupancy function. A similar equation can be written for holes in the valence band. Figure 3 shows the density of states ρ versus energy as a dashed line for conduction and valence bands. The solid lines in Figure 3 are the $\rho(E)f(E)$ products, and the areas under the solid curves are the carrier densities n and p.

The Fermi functions are occupation probabilities based on the quasi-Fermi levels E_{Fn} and E_{Fp}, which are, in turn, based on the injected carrier densities, δn and δp. Population inversion implies that the difference between the quasi-Fermi levels must exceed the emission energy which, for semiconductors, must be greater than the bandgap energy:

$$E_{Fn} - E_{Fp} \geq \hbar\omega \sim E_g \qquad [2]$$

Charge neutrality requires that $\delta n = \delta p$. Transparency is the point where these two conditions are just met and any additional injected current results in optical gain. The transparency current density J_o, is given by

$$J_o = \frac{q n_o L_z}{\tau_{\text{spon}}} \qquad [3]$$

where n_o is the transparency carrier density ($\delta n = \delta p = n_o$ at transparency), L_z is the thickness of the optically active layer, and τ_{spon} is the spontaneous carrier lifetime in the material (typically 5 nsec).

A resonant cavity for optical feedback is obtained simply by taking advantage of the natural crystal formation in single crystal semiconductors. Most III–V compound semiconductors form naturally into a zincblende lattice structure. With the appropriate choice of crystal planes and surfaces, this lattice structure can be cleaved such that nearly perfect plane–parallel facets can be formed at arbitrary distances from each other. Since the refractive index of these materials is much larger (~3.5) than that of air, there is internal optical reflection for normal incidence of approximately 30%. This type of optical cavity is called a Fabry–Perot resonator.

Effective lasers of all forms make use of optical waveguides to optimize the overlap of the optical field with material gain and cavity resonance. The optical waveguide in an edge emitting laser is best described by considering it in terms of a transverse waveguide component, defined by the epitaxial growth of multiple thin heterostructure layers, and a lateral waveguide component, defined by conventional semiconductor device processing methods. One of the simplest, and yet most common, heterostructure designs is shown in Figure 4. This five-layer separate confinement heterostructure (SCH) offers excellent carrier confinement in the active layer as well as a suitable transverse waveguide.

Clever choice of different materials for each layer results in the energy band structure, index of refraction



Figure 4 Schematic cross-section of a typical five-layer separate confinement heterostructure (SCH) laser.



Figure 5 Energy band structure, index of refraction profile, and optical field mode profile of the SCH laser of Figure 4.

profile, and optical field mode profile shown in Figure 5. The outer confining layers are the thickest (~1 μm) and have the largest energy bandgap and lowest refractive index. The inner barrier layers are thinner (~0.1 μm), have intermediate bandgap energy and index of refraction, and serve both an optical role in defining the optical waveguide and an electronic role in confining carriers to the active layer. The active layer is the narrowest bandgap, highest index material, and is the only layer in the structure designed to provide optical gain. It may be a single layer or, as in the case of a multiple quantum well laser, a combination of layers. The bandgap energy, E, of this active layer plays a key role in determining the emission wavelength, λ, of the laser:

$$E = \frac{hc}{\lambda} \qquad [4]$$

where h is Planck's constant and c is the speed of light.

The bandgap energy of the SCH structure is shown in Figure 5. The lowest energy active layer collects injected electrons and holes and the carrier confinement provided by the inner barrier layers allows the high density of carriers necessary for population inversion and gain. The layers in the structure also have the refractive index profile shown in Figure 5 which forms a five-layer slab dielectric waveguide. With appropriate values for thicknesses and indices of refraction, this structure can be a very strong fundamental mode waveguide with the field profile shown. A key parameter of edge emitting diode lasers is Γ, the optical confinement factor. This parameter is the areal overlap of the optical field with the active layer, shown as dashed lines in the figure and can be as little as a few percent, even in very high performance lasers.

Lateral waveguiding in a diode laser can be accomplished in a variety of ways. A common example of an index guided laser is the ridge waveguide laser shown in Figure 6. After the appropriate transverse waveguide heterostructure sample is grown, conventional semiconductor processing methods are used to form parallel etched stripes from the surface near, but not through, the active layer. An oxide mask is patterned such that electrical contact is formed only to the center (core) region between the etched stripes, the core stripe being only a few microns wide. The lateral waveguide that results arises from the average index of refraction (effective index) in the etched regions outside the core being smaller than that of the core. Figure 7 shows the asymmetric near field emission profile of the ridge waveguide laser and cross-sectional profiles of the laser emission and effective index of refraction.

The optical spectrum of an edge emitting diode laser below and above threshold is the superposition of the material gain of the active layer and the resonances provided by the Fabry–Perot resonator. The spectral variation of material gain with injected carrier density (drive current) is shown in Figure 8. As the drive is increased, the intensity and energy of peak gain both increase.

The Fabry–Perot resonator has resonances every half wavelength, given by

$$L = \frac{m}{2}\frac{\lambda}{n} \qquad [5]$$



Figure 6 Schematic diagram of a real index guided ridge waveguide diode laser.



Figure 7 Near field emission pattern, cross-sectional emission profiles (solid lines), and refractive index profiles (dashed lines) from an index guided diode laser.



Figure 8 Gain versus emission energy for four increasing values of carrier (current) density. Peak gain is shown as a dashed line.



Figure 9 Emission spectra from a Fabry–Perot edge emitting laser structure at, and above, laser threshold.

where L is the cavity length, λ/n is the wavelength in the medium (n is the refractive index), and m is an integer. For normal length edge emitter cavities, these cavity modes are spaced only 1 or 2 Å apart. The result is optical spectra, near laser threshold and above, that look like the spectra of Figure 9. Many cavity modes resonate up to threshold, while above threshold, the superlinear increase in emission intensity with drive current tends to greatly favor one or two of the Fabry–Perot longitudinal cavity modes.

Laser threshold can be determined from a relatively simple analysis of the round trip gain and losses in the Fabry–Perot resonator. If the initial intensity is I_o, after one round trip the intensity will be given by

$$I = I_o R_1 R_2 e^{(g-\alpha_i)2L} \qquad [6]$$

where R_1 and R_2 are the reflectivities of the two facets, g is the optical gain, α_i are losses associated with optical absorption (typically 3–15 cm^{-1}), and L is the cavity length. At laser threshold, $g = g_{th}$ and $I = I_o$, i.e., the round trip gain exactly equals the losses. The result is

$$g_{th} = \alpha_i + \frac{1}{2L}\ln\frac{1}{R_1R_2} \qquad [7]$$

where the second term represents the mirror losses α_m. Of course, mirror losses are desirable in the sense that they represent useable output power. Actually, the equation above does not take into account the incomplete overlap of the optical mode with the gain in the active layer. The overlap is defined by the confinement factor Γ, described above, and the equation must be modified to become

$$\Gamma g_{th} = \alpha_i + \frac{1}{2L}\ln\frac{1}{R_1R_2} \qquad [8]$$

For quantum well lasers, the material peak gain, shown in Figure 8, as a function of drive current is given approximately by

$$g_t = \beta J_o \ln\frac{J}{J_o} \qquad [9]$$

where J_o is the transparency current density. The threshold current density J_{th}, which is the current density where the gain exactly equals all losses, is given by

$$J_{th} = \frac{J_o}{\eta_i}\exp\frac{\alpha + \frac{1}{2L}\ln\frac{1}{R_1R_2}}{\Gamma\beta J_o} \qquad [10]$$

Note that an additional parameter η_i has appeared in this equation. Not all of the carriers injected by the drive current participate in optical processes; some are lost to other nonradiative processes. This is accounted for by including the internal quantum efficiency term η_i, which is typically at least 90%. The actual drive current, of course, must include the geometry of the device and is given by

$$I_{th} = wLJ_{th} \qquad [11]$$

where L is the cavity length, and w is the effective width of the active volume. The effective width is basically the stripe width of the core but also includes current spreading and carrier diffusion under the stripe.

The power–current characteristic (P–I) for a typical edge emitting laser diode is shown in Figure 10. As the drive current is increased



Figure 10 Power versus current (*P*–*I*) curve for a typical edge emitting laser diode.

from zero, the injected carrier densities increase and spontaneous recombination is observed. At some point the gain equals the internal absorption losses, and the material is transparent. Then, as the drive current is further increased, additional gain eventually equals the total losses, including mirror losses, and laser threshold is reached. Above threshold, nearly all additional injected carriers contribute to stimulated emission (laser output). The power generated internally is given by

$$P = wL(J - J_{th})\eta_i \frac{h\nu}{q} \qquad [12]$$

where wL is the area and $h\nu$ is the photon energy. Only a fraction of the power generated internally is extracted from the device

$$P_o = wL(J - J_{th})\eta_i \frac{h\nu}{q} \frac{\alpha_m}{\alpha_i + \alpha_m} \qquad [13]$$

Clearly a useful design goal is to minimize the internal optical loss α_i. The slope of the P–I curve of Figure 10 above threshold is described by an external differential quantum efficiency η_d, which is related to the internal quantum efficiency by

$$\eta_d = \eta_i \left[\frac{\alpha_m}{\alpha_i + \alpha_m} \right] \qquad [14]$$

Other common parameters used to characterize the efficiency of laser diodes include the power conversion efficiency η_p

$$\eta_p = \frac{P_o}{V_F I} \qquad [15]$$

and the wall plug efficiency η_w

$$\eta_w = \frac{P_o}{I} \qquad [16]$$

The power conversion efficiency η_p, recognizes that the forward bias voltage V_F is larger than the photon energy by an amount associated with the series resistance of the laser diode. The wall plug efficiency η_w, has the unusual units of WA^{-1} and is simply a shorthand term that relates the common input unit of current to the common output unit of power. In high performance low power applications, the ideal device has minimum threshold current since the current used to reach threshold contributes little to light emission. In high power applications, the threshold current becomes insignificant and the critical parameter is external quantum efficiency.

Temperature effects may be important for edge emitting lasers, depending on a particular application. Usually, concerns related to temperature arise under conditions of high temperature operation ($T > 50\,°C$), where laser thresholds rise and efficiencies fall. It became common early in the development of laser diodes to define a characteristic temperature T_o for laser threshold, which is given by

$$I_{th} = I_{t\hbar o} \exp\left(\frac{T}{T_o}\right) \qquad [17]$$

where a high T_o is desirable. Unfortunately, this simple expression does not describe the temperature dependence very well over a wide range of temperatures, so the appropriate temperature range must also be specified. For applications where the emission wavelength of the laser is important, the change in wavelength with temperature $d\lambda/dT$ may also be specified. For conventional Fabry–Perot cavity lasers, $d\lambda/dT$ is typically 3–5 $\text{Å}C^{-1}$.

In order for a diode laser to carry information, some form of modulation is required. One method for obtaining this is direct modulation of the drive current in a semiconductor laser. The transient and temporal behavior of lasers is governed by rate equations for carriers and photons which are necessarily coupled equations. The rate equation for carriers is given by

$$\frac{dn}{dt} = \frac{J}{qL_z} - \frac{n}{\tau_{sp}} - (c/n)\beta(n - n_o)\varphi(E) \qquad [18]$$

where J/qL_z is the supply, n/τ_{sp} is the spontaneous emission rate, and the third term is the stimulated emission rate $(c/n)\beta(n - n_o)\varphi(E)$ where β is the gain coefficient and $\varphi(E)$ is the photon density.

The rate equation for photons is given by

$$\frac{\mathrm{d}\varphi}{\mathrm{d}t} = (c/n)\beta(n - n_o)\varphi + \frac{\theta n}{\tau_{sp}} - \frac{\varphi}{\tau_p} \qquad [19]$$

where θ is the fraction of the spontaneous emission that couples into the mode (a small number), and τ_p is the photon lifetime (~1 psec) in the cavity. These rate equations can be solved for specific diode laser materials and structures to yield a modulation frequency response. A typical small signal frequency response, at two output power levels, is shown in Figure 11. The response is typically flat to frequencies above 1 GHz, rises to a peak value at some characteristic resonant frequency, and quickly rolls off. The characteristic small signal resonant frequency ω_r, is given by

$$\omega_r^2 = \frac{(c/n)\beta\bar{\varphi}}{\tau_p} \qquad [20]$$

where $\bar{\varphi}$ is the average photon density. Direct modulation of edge emitting laser diodes is limited by practicality to less than 10 GHz. This is in part because of the limits imposed by the resonant frequency and in part by chirp. Chirp is the frequency modulation that arises indirectly from direct current modulation. Modulation of the current modulates the carrier densities which, in turn, results in modulation of the quasi-Fermi levels. The separation of the quasi-Fermi levels is the emission energy (wavelength). Most higher-speed lasers make use of external modulation schemes.

The discussion thus far has addressed aspects of semiconductor diode edge emitting lasers that are common to all types of diode lasers irrespective of the choice of materials or the details of the active layer structure. The materials of choice for efficient laser devices include a wide variety of III–V binary compounds and ternary or quaternary alloys. The particular choice is based on such issues as emission wavelength, a suitable heterostructure lattice match, and availability of high-quality substrates. For example, common low-power lasers for CD players ($\lambda \sim 820$ nm) are likely to be made on a GaAs substrate using a GaAs–$Al_xGa_{1-x}As$ heterostructure. Lasers for fiberoptic telecommunications systems ($\lambda \sim 1.3$–1.5 μm) are likely to be made on an InP substrate using an InP–$In_xGa_{1-x}As_yP_{1-y}$ heterostructure. Red laser diodes ($\lambda \sim 650$ nm) are likely to be made on a GaAs substrate using a GaAs–$In_xGa_{1-x}As_yP_{1-y}$ heterostructure. Blue and ultraviolet lasers, a relatively new technology compared to the others, make use of $Al_xGa_{1-x}N$–GaN–$In_yGa_{1-y}N$ heterostructures formed on sapphire or silicon carbide substrates.



Figure 11 Direct current modulation frequency response for an edge emitting diode laser at two output power levels.

An important part of many diode laser structures is a strained layer. If a layer is thin enough, the strain arising from a modest amount of lattice mismatch can be accommodated elastically. In thicker layers, lattice mismatch results in an unacceptable number of dislocations that affect quantum efficiency, optical absorption losses, and, ultimately, long-term failure rates. Strained layer GaAs–$In_xGa_{1-x}As$ lasers are a critical component in rare-earth doped fiber amplifiers.

The structure of the active layer in edge emitting laser diodes was originally a simple double heterostructure configuration with a single active layer of 500–1000 Å in thickness. In the 1970s however, advances in the art of growing semiconductor heterostructure materials led to growth of high-quality quantum well active layers. These structures, having thicknesses that are comparable to the electron wavelength in a semiconductor (<200 Å), revolutionized semiconductor lasers, resulting in much lower threshold current densities, higher efficiencies, and a broader range of available emission wavelengths. The energy band diagram for a quantum well laser active region is shown in Figure 12.

This structure is a physical realization of the particle-in-a-box problem in elementary quantum mechanics. The quantum well yields quantum states in the conduction band at discrete energy levels, with odd and even electron wavefunctions, and breaks the degeneracy in the valence band, resulting in separate energy states for light holes and heavy holes. The primary transition for recombination is from the $n = 1$ electron state to the $h = 1$ heavy hole state and takes place at a higher energy than the bulk bandgap energy. In addition, the density of states for quantum wells becomes a step-like function and optical gain is enhanced. The advantages in practical edge



Figure 12 Energy band diagram for a quantum well heterostructure.



Figure 13 Schematic diagram of distributed feedback (DFB) and distributed Bragg reflector (DBR) edge emitting laser diodes.

emitting lasers that are the result of one-dimensional quantization are such that virtually all present commercial laser diodes are quantum well lasers. These kinds of advantages are driving development of laser diodes with additional degrees of quantization, including two dimensions (quantum wires) and three dimensions (quantum dots).

The Fabry–Perot cavity resonator described here is remarkably efficient and relatively easy to fabricate, which makes it the cavity of choice for many applications. There are many applications, however, where the requirements for linewidth of the laser emission or the temperature sensitivity of the emission wavelength make the Fabry–Perot resonator less desirable. An important laser technology that addresses both of these concerns involves the use of a wavelength selective grating as an integral part of the laser cavity. A notable example of a grating coupled laser is distributed feedback laser shown schematically in Figure 13a. This is similar to the SCH cross-section of Figure 4 with the addition of a Bragg grating above the active layer.

The period Λ, of the grating is chosen to fulfill the Bragg condition for mth-order coupling between forward- and backward-propagating waves, which is

$$\Lambda = \frac{m\lambda}{2n} \qquad [21]$$

where λ/n is the wavelength in the medium. The index step between the materials on either side of the grating is small and the amount of reflection is also small. Since the grating extends throughout the length of the cavity, however, the overall effective reflectivity can be large. Another variant is the distributed Bragg reflector (DBR) laser resonator, shown in Figure 13b. This DBR laser has a higher index contrast, deeply etched surface grating located at one or both ends of the otherwise conventional SCH laser heterostructure. One of the advantages of this structure is the opportunity to add a contact for tuning the Bragg grating by current injection.

Both the DBR and DFB laser structures are particularly well suited for telecommunications or other applications where a very narrow single laser emission line is required. In addition, the emission wavelength temperature dependence for this type of laser is much smaller, typically 0.5 ÅC^{-1}.

See also

Semiconductor Physics: Quantum Wells and GaAs-based Structures.

Further Reading

Agrawal GP (ed.) (1995) *Semiconductor Lasers Past, Present, and Future*. Woodbury, NY: American Institute of Physics.

Agrawal GP and Dutta NK (1993) *Semiconductor Lasers*. New York: Van Nostrand Reinhold.

Bhattacharya P (1994) *Semiconductor Optoelectronic Devices*. Upper Saddle River, NJ: Prentice-Hall.

Botez D and Scifres DR (eds) (1994) *Diode Laser Arrays*. Cambridge, UK: Cambridge University Press.

Chuang SL (1995) *Physics of Optoelectronic Devices*. New York: John Wiley & Sons.

Coleman JJ (1992) *Selected Papers on Semiconductor Diode Lasers*. Bellingham, WA: SPIE Optical Engineering Press.
Einspruch NG and Frensley WR (eds) (1994) *Heterostructures and Quantum Devices*. San Diego, CA: Academic Press.
Iga K (1994) *Fundamentals of Laser Optics*. New York: Plenum Press.
Kapon E (1999) *Semiconductor Lasers I and II*. San Diego, CA: Academic Press.
Nakamura S and Fasol G (1997) *The Blue Laser Diode*. Berlin: Springer.
Verdeyen JT (1989) *Laser Electronics*, 3rd edn. Englewood Cliffs, NJ: Prentice-Hall.
Zory PS Jr (ed.) (1993) *Quantum Well Lasers*. San Diego, CA: Academic Press.

Excimer Lasers

J J Ewing, Ewing Technology Associates, Inc., Bellevue, WA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

We present a summary of the fundamental operating principles of ultraviolet, excimer lasers. After a brief discussion of the economics and application motivation, the underlying physics and technology of these devices is described. Key issues and limitations in the scaling of these lasers are presented.

Background: Why Excimer Lasers?

Excimer lasers have become the most widely used source of moderate power pulsed ultraviolet sources in laser applications. The range of manufacturing applications is also large. Production of computer chips, using excimer lasers as the illumination source for lithography, has by far the largest commercial manufacturing impact. In the medical arena, excimer lasers are used extensively in what is becoming one of the world's most common surgical procedures, the reshaping of the lens to correct vision problems. Taken together, the annual production rate for these lasers is a relatively modest number compared to the production of semiconductor lasers. Current markets are in the range of $0.4 billion per year (Figure 1). More importantly, the unique wavelength, power, and pulse energy properties of the excimer laser enable a systems and medical procedure market, based on the excimer laser, to exceed $3 billion per year. The current average sales price for these lasers is in the range of $250 000 per unit, driven primarily by the production costs and reliability requirements of the lasers for lithography for chip manufacture. Relative to semiconductor diode lasers, excimer lasers have always been, and will continue to be, more expensive per unit device by a factor of order 10^4. UV power and pulse energy, however, are considerably higher.

The fundamental properties of these lasers enable the photochemical and photophysical processes used in manufacturing and medicine. Short pulses of UV light can photo-ablate materials, being of use in medicine and micromachining. Short wavelengths enable photochemical processes. The ability to provide a narrow linewidth using appropriate resonators enables precise optical processes, such as lithography. We trace out some of the core underlying properties of these lasers that lead to the core utility. We also discuss the technological problems and



Figure 1 The sales of excimer lasers have always been measured in small numbers relative to other, less-expensive lasers. For many years since their commercial release in 1976 the sales were to R&D workers in chemistry, physics and ultimately biology and medicine. The market for these specialty but most useful R&D lasers was set to fit within a typical researcher's annual capital budget, i.e., less than $100K. As applications and procedures were developed and certified or approved, sales and average unit sales price increased considerably. Reliance on cyclical markets like semiconductor fabrication led to significant variations in production rates and annual revenues as can be seen.

solutions that have evolved to make these lasers so useful.

The data in Figure 1 provide a current answer to the question of ‘why excimer lasers?’ At the dawn of the excimer era, the answer to this question was quite different. In the early 1970s, there were no powerful short wavelength lasers, although IR lasers were being scaled up to significant power levels. However, visible or UV lasers could in principle provide better propagation and focus to a very small spot size at large distances. Solid state lasers of the time offered very limited pulse repetition frequency and low efficiency. Diode pumping of solid state lasers, and diode arrays to excite such lasers, was a far removed development effort. As such, short-wavelength lasers were researched over a wide range of potential media and lasing wavelengths. The excimer concept was one of those candidates.

We provide, in Figure 2, a ‘positioning’ map showing the range of laser parameters that can be obtained with commercial or developmental excimer lasers. The map has coordinates of pulse energy and pulse rate, with diagonal lines expressing average power. We show where both development goals and current markets lay in a map. Current applications are shown by the boxes in the lower right-hand corner. Excimer lasers have been built with clear apertures in the range of a fraction of 0.1 to 10^4 cm^2, with single pulse energies covering a range of 10^7. Lasers with large apertures require electron beam excitation. Discharge lasers correspond to the more modest pulse energy used for current applications. In general, for energies lower than ~5 J, the excitation method of choice is a self-sustained discharge, clearly providing growth potential for future uses, if required.



Figure 2 The typical energy and pulse rate for certain applications and technologies using excimer lasers. For energy under a few J, a discharge laser is used. The earliest excimer discharge lasers were derivatives of CO_2 TEA (transversely excited atmospheric pressure) and produced pulse energy in the range of 100 mJ per pulse. Pulse rates of order 30 Hz were all that the early pulsed power technology could provide. Early research focused on generating high energy. Current markets are at modest UV pulse energy and high pulse rates for lithography and low pulse rates for medical applications.

The applications envisaged in the early R&D days were in much higher energy uses, such as in laser weapons, laser fusion, and laser isotope separation. The perceived need for lasers for isotope separation, laser-induced chemistry, and blue-green laser-based communications from satellites, drove research in high pulse rate technology and reliability extension for discharge lasers. This research resulted in prototypes, with typical performance ranges as noted on the positioning map that well exceed current market requirements. However, the technology and underlying media physics developed in these early years made possible advances needed to serve the ultimate real market applications.

The very important application of UV lithography requires high pulse rates and high reliability. These two features differentiate the excimer laser used for lithography from the one used in the research laboratory. High pulse rates, over 2000 Hz in current practice, and the cost of stopping a computer chip production line for servicing, drive the reliability requirements toward 10^{10} shots per service interval. In contrast, the typical laboratory experiments are more often in the range of 100 Hz and, unlike a lithography production line, do not run 24 hours a day, 7 days a week. The other large market currently is in laser correction of myopia and other imperfections in the human eye. For this use the lasers are more akin to the commercial R&D style laser in terms of pulse rate and single pulse energy. Not that many shots are needed to ablate tissue to make the needed correction, and shot life is a straightforward requirement. However, the integration of these lasers into a certified and accepted medical procedure and an overall medical instrument drove the growth of this market.

The excimer concept, and the core technology used to excite these lasers, is applicable over a broad range of UV wavelengths, with utility at specific wavelength ranges from 351 nm in the near UV to 157 nm in the vacuum UV (VUV). There were many potential excimer candidates in the early R&D phase (Table 1). Some of these

Table 1 Key excimer wavelengths

Excimer emitter	*λ (nm)*	*Comment*
Ar_2	126	Very short emission wavelength, deep in the Vacuum UV; inefficient as laser due to absorption, see Xe_2.
Kr_2	146	Broad band emitter and early excimer laser with low laser efficiency. Very efficient converter of electric power into Vacuum UV light.
F_2	157	Molecule itself is not an excimer, but uses lower level dissociation; candidate for next generation lithography.
Xe_2	172	The first demonstrated excimer laser. Very efficient formation and emission but excited state absorption limits laser efficiency. Highly efficient as a lamp.
ArF	193	Workhorse for corneal surgery and lithography.
KrCl	222	Too weak compared to KrF and not as short a wavelength as ArF.
KrF	248	Best intrinsic laser efficiency; numerous early applications but found major market in lithography. Significant use in other materials processing.
XeI	254	Never a laser, but high formation efficiency and excellent for a lamp. Historically the first rare gas halide excimer whose emission was studied at high pressure.
XeBr	282	First rare gas halide to be shown as a laser; inefficient laser due to excited state absorption, but excellent fluorescent emitter; a choice for lamps.
Br_2	292	Another halogen molecule with excimer like transitions that has lased but had no practical use.
XeCl	308	Optimum medium for laser discharge excitation.
Hg_2	335	Hg vapor is very efficiently excited in discharges and forms excimers at high pressure. Subject of much early research, but as in the case of the rare gas excimers such as Xe_2 suffer from excited state absorption. Despite the high formation efficiency, this excimer was never made to lase.
I_2	342	Iodine UV molecular emission and lasing was first of the pure halogen excimer-like lasers demonstrated. This species served as kinetic prototype for the F_2 'honorary' excimer that has important use as a practical VUV source.
XeF	351, 353	This excimer laser transition terminates on a weakly bound lower level that dissociates rapidly, especially when heated. The focus for early defense-related laser development; as this wavelength propagates best of this class in the atmosphere.
XeF	480	This very broadband emission of XeF terminates on a different lower level than the UV band. Not as easily excited in a practical system, so has not had significant usage.
HgBr	502	A very efficient green laser that has many of the same kinetic features of the rare gas halide excimer lasers. But the need for moderately high temperature for the needed vapor pressure made this laser less than attractive for UV operation.
XeO	540	This is an excimer-like molecular transition on the side of the auroral lines of the O atom. The optical cross-section is quite low and as a result the laser never matured in practice.

candidates can be highly efficient, >50% relative to deposited energy, at converting electrical power into UV or visible emission, and have found a parallel utility as sources for lamps, though with differing power deposition rates and configurations. The key point in the table is that these lasers are powerful and useful sources at very short wavelengths. For lithography, the wavelength of interest has consistently shifted to shorter and shorter wavelengths as the printed feature size decreased. Though numerous candidates were pursued, as shown in Table 1, the most useful lasers are those using rare gas halide molecules. These lasers are augmented by dye laser and Raman shifting to provide a wealth of useful wavelengths in the visible and UV.

All excimer lasers utilize molecular dissociation to remove the lower laser level population. This lower level dissociation is typically from an unbound or very weakly bound ground-state molecule. However, halogen molecules also provide laser action on excimer-like transitions, that terminate on a molecular excited state that dissociates quickly. The vacuum UV transition in F_2 is the most practical method for making very short wavelength laser light at significant power. Historically, the rare gas dimer molecules, such as Xe_2, were the first to show excimer laser action, although self absorption, low gain, and poor optics in the VUV limited their utility. Other excimer-like species, such as metal halides, metal rare gas continua on the edge of metal atom resonance lines, and rare gas oxides were also studied. The key differentiators of rare gas halides from other excimer-like candidates are strong binding in the excited state, lack of self absorption, and relatively high optical cross-section for the laser transition.

Excimer Laser Fundamentals

Excimer lasers utilize lower-level dissociation to create and sustain a population inversion. For example, in the first excimer laser demonstrated, Xe_2, the lasing species is one which is comprised of two atoms that do not form a stable molecule in the ground state, as xenon dimers in the ground state are not a stable molecule. In the lowest energy state, that with neither of the atoms electronically excited, the interaction between the atoms in a collision is primarily one of repulsion, save for a very weak 'van der Waals' attraction at larger internuclear separations. This is shown in the potential energy diagram of Figure 3. If one of the atoms is excited, for example by an electric discharge, there can be a chemical binding in the electronically excited state of the molecule relative to the energy of one atom with an electron excited and one atom in the ground state. We use the shorthand notation * to denote an electronically excited atomic molecular species, e.g., Xe^*. The excited dimer, excimer for short, will recombine rapidly at high pressure from atoms into the Xe_2^* electronically excited molecule. Radiative lifetimes of the order 10 nsec to 1 μsec are typical before photon emission returns the molecule to the lower level. Collisional quenching often reduces the lifetime below the radiative rate. For Xe_2^* excimers, the emission is in the vacuum ultraviolet (VUV).

There are a number of variations on this theme, as noted in Table 1. Species, other than rare gas pairs, can exhibit broadband emission. The excited state binding energy can vary significantly, changing the fraction of excited states that will form molecules. The shape of the lower potential energy curve can vary as well. From a semantic point of view heteronuclear, diatomic molecules, such as XeO, are not excimers, as they are not made of two of the same atoms. However, the more formal name 'exciplex' did not stick in the laser world; excimer laser being preferred. Large binding energy is more efficient for capturing excited atoms into excited excimer-type molecules in the limited time they have before emission. Early measurements of the efficiency of converting electrical energy deposited into fluorescent radiation showed that up to 50% of the energy input could result in VUV light emission. Lasers were not this efficient due to absorption.



Figure 3 A schematic of the potential energy curves for an excimer species such as Xe_2. The excited molecule is bound relative to an excited atom and can radiate to a lower level that rapidly dissociates on psec timescales since the ground state is not bound, save for weak binding due to van der Waals forces. The emission band is intrinsically broad.

The diagram shown in Figure 3 is simplified because it does not show all of the excited states that exist for the excited molecule. There can be closely lying excited states that share the population and radiate at a lower rate, or perhaps absorb to higher levels, also not shown in Figure 3. Such excited state absorption may terminate on states derived from higher atomic excited states, noted as Xe^{**} in the figure, or yield photo-ionization, producing the diatomic ion-molecule plus an electron, such as:

$$Xe_2^* + h\nu \rightarrow Xe_2^+ + e \qquad [1]$$

Such excited state absorption limited the efficiency for the VUV rare gas excimers, even though they have very high formation and fluorescence efficiency.

Rare gas halide excimer lasers evolved from 'chemi-luminescence' chemical kinetics studies which were looking at the reactive quenching of rare gas metastable excited states in flowing after glow experiments. Broadband emission in reactions with halogen molecules was observed in these experiments, via reactions such as:

$$Xe^* + Cl_2 \rightarrow XeCl^* + Cl \qquad [2]$$

At low pressure the emissions from molecules, such as $XeCl^*$, are broad in the emissions bandwidth. Shortly after these initial observations, the laser community began examination of these species in high-pressure, electron-beam excited mixtures. The results differed remarkably from the low-pressure experiments and those for the earlier excimers such as Xe_2^*. The spectrum was shifted well away from the VUV emission. Moreover, the emission was much sharper at high pressure, though still a continuum with a bandwidth of the order of 4 nm. A basis for understanding is sketched in the potential energy curves of Figure 4. In this schematic we identify the rare gas atoms by Rg, excited rare gas atoms by



Figure 4 The potential energy curves for rare gas halides are sketched here. Both relatively sharp continuum emission is observed along with broad bands corresponding to different lower levels. The excited ion pair states consist of 3 distinct levels, two that are very close in energy and one that is shifted up from the upper laser level (the B state) by the spin orbit splitting of the rare gas ion.

Rg^*, and halogen atoms by X. Ions play a very important role in the binding and reaction chemistry, leading to excited laser molecules.

The large shift in wavelength from the VUV of rare gas dimer excimers, ~308 nm in $XeCl^*$ versus 172 nm in Xe_2^*, is due to the fact that the binding in the excited state of the rare gas halide is considerably stronger. The sharp and intense continuum at high pressure (> ~100 torr total pressure) is due to the fact that the 'sharp' transition terminates on a 'flat' portion of the lower-level potential energy curve. Indeed, in XeCl and XeF, the sharp band laser transition terminates on a slightly bound portion of the lower-level potential energy curve. Both the sharp emissions and broad bands are observed, due to the fact that some transitions from the excited levels terminate on a second, more repulsive potential energy curve.

An understanding of the spectroscopy and kinetic processes in rare gas plus halogen mixtures is based on the recognition that the excited state of a rare gas halide molecule is very similar to the ground state of the virtually isoelectronic alkali halide. The binding energy and mechanism of the excited state is very close to that of the ground state of the most similar alkali halide. Reactions of excited state rare gases are very similar to those of alkali atoms. For example, Xe^* and Cs are remarkably similar, from a chemistry and molecular physics point of view, as they have the same outer shell electron configuration and similar ionization potentials. The ionization potential of Xe^* is similar to that of cesium (Cs). Cs, and all the other alkali atoms, react rapidly with halogen molecules. Xenon metastable excited atoms react rapidly with halogen molecules. The alkali atoms all form ionically bonded ground states with halogens. The rare gas halides are effectively strongly bonded ion pairs, $Xe^{(+)}X^{(-)}$, that are very strongly bonded relative to the excited states that yield them. The difference between, for example, $XeCl^*$ and CsCl, is that $XeCl^*$ radiates in a few nanoseconds while CsCl is a stable ground-state molecule. The binding energy for these ionic bonded molecules is much greater than the more covalent type of bonding that is found in the rare gas excimer excited states. Thus XeI^*, which is only one electron different (in the I) than Xe_2^*, emits at 254 nm instead of 172 nm.

The first observed and most obvious connection to alkali atoms is in formation chemistry. Mostly, rare gas excited states react with halogen molecules rapidly. The rare gas halide laser analog reaction sequence is shown below, where some form of electric discharge excitation kicks the rare gas atom up to an excited state, so that it can react like an alkali atom, eqn [3]:

$$e_{\text{fast}} + \text{Kr} \rightarrow \text{Kr}^* + e_{\text{slow}} \qquad [3]$$

$$\text{Kr}^* + \text{F}_2 \rightarrow \text{KrF}^*(v, J)_{\text{high}} + \text{F} \qquad [4]$$

There are subtle and important cases where the neutral reaction, such as that shown in eqn [2] or [4], is not relevant as it is too slow compared to other processes. Note that the initial reaction does not yield the specific upper levels for the laser but states that are much higher up in the potential well of the excited rare gas halide excimer molecule. Further collisions with a buffer gas are needed to relax the states to the vibrational levels that are the upper levels for the laser transition. Such relaxation at high pressure can be fast, which leads the high-pressure spectrum to be much sharper than those first observed in flowing after-glow experiments.

The excited states of the rare gas halides are ion pairs bound together for their brief radiative lifetime. This opens up a totally different formation channel, indeed the one that often dominates the mechanism, ion–ion recombination. Long before excimer lasers were studied, it was well known that halogen molecules would react with 'cold' electrons (those with an effective temperature less than a few eV) in a process called attachment. The sequence leading to the upper laser level is shown below for the Kr/F_2 system, but the process is generically identical in other rare gas halide mixtures.

KrF^* formation kinetics via ion channel:

$$\text{Ionization:} \qquad e + Kr \rightarrow Kr^{+} + 2e \tag{5}$$

$$\text{Attachment:} \qquad e + F_2 \rightarrow F^{(-)} + F \tag{6}$$

Ion–ion recombination:

$$Kr^{+} + F^{(-)} + M \rightarrow KrF^{*}(v, J)_{\text{high}} + M \tag{7}$$

Relaxation:

$$KrF^{*}(v, J)_{\text{high}} + M \rightarrow KrF^{*}(v, J)_{\text{low}} + M \tag{8}$$

Finally, there is one other formation mechanism, displacement, that is unique to the rare gas halides. In this process, a heavier rare gas will displace a lighter rare gas ion in an excited state to form a lower-energy excited state:

$$ArF^{*} + Kr \rightarrow KrF^{*}(v, J)_{\text{high}} + Ar \tag{9}$$

In general, the most important excimer lasers tend to have all of these channels contributing to excited state formation for optimized mixtures.

These kinetic formation sequences express some important points regarding rare gas halide lasers. The source of the halogen atoms for the upper laser level disappears via both attachment reactions with electrons and by the reaction with excited states. The halogen atoms eventually recombine to make molecules, but at a rate too slow for sufficient continuous wave (cw) laser gain. For excimer-based lamps, however, laser gain is not a criterion and very efficient excimer lamps can be made. Another point to note is that forming the inversion requires transient species (and in some cases halogen fuels) that absorb the laser light. Net gain and extraction efficiency are a trade-off between pumping rate, an increase in which often forms more absorbers and absorption itself. Table 2 provides a listing of some of the key absorbers. Finally, the rare gas halide excited states can be rapidly quenched in a variety of processes. More often than not, the halogen molecule and the electrons in the discharge react with the excited states of the rare gas halide, removing the contributors to gain. We show, in Table 3, a sampling of some of the types of formation and quenching reactions with their kinetic rate constant parameters. Note that one category of reaction, three-body quenching, is unique to excimer lasers. Note also that the three-body recombination of ions has a rate coefficient that is effectively pressure dependent. At pressures above ~3 atm, the diffusion of ions toward each other is slowed and the effective recombination rate constant decreases.

Though the rare gas halide excited states can be made with near-unity quantum yield from the primary excitation, the intrinsic laser efficiency is not this high. The quantum efficiency is only ~25% (recall rare gas halides all emit at much longer wavelengths than rare gas excimers); there is inefficient extraction due to losses in the gas and windows. In practice there are also losses in coupling the power into the laser, and wasted excitation during the finite start-up time. The effect of losses is shown in Table 4 and Figure 5 where the pathways are charted and losses identified. In KrF, it takes ~20 eV to make a rare gas ion in an electron beam excited mixture,

Table 2 Absorbers in rare gas halide lasers

Species	*XeF*	*XeCl*	*KrF*	*ArF*
Laser λ (nm)	351, 353	308	248	193
F_2 absorption σ (cm^2)	8×10^{-21}	NA	1.5×10^{-20}	
Cl_2 absorption σ (cm^2)	NA	1.7×10^{-19}	NA	NA
HCl absorption σ (cm^2)	NA	Nil	NA	NA
$F^{(-)}$ absorption σ (cm^2)	2×10^{-18}	NA	5×10^{-18}	5×10^{-18}
$Cl^{(-)}$ absorption σ (cm^2)	NA	2×10^{-17}	NA	NA
$Rg_2^{(+)}$ diatomic ion absorption σ (cm^2)[a]	Ne: $\sim 10^{-18}$ Ar: $\sim 3 \times 10^{-17}$ Xe: $\sim 3 \times 10^{-17}$	Ne: $\sim 10^{-17}$ Ar: $\sim 4 \times 10^{-17}$ Xe: $\sim 3 \times 10^{-18}$	Ne: $\sim 2.5 \times 10^{-17}$ Ar: $\sim 2 \times 10^{-18}$ Kr $< 10^{-18}$	Ne: $\sim 10^{-18}$ Ar: NIL
Other transient absorbers	Excited states of rare gas atoms and rare gas dimer molecules $\sigma \sim 10^{-19}$–10^{-17}	Excited states of rare gas atoms and rare gas dimer molecules $\sigma \sim 10^{-19}$–10^{-17}	Excited states of rare gas atoms and rare gas dimer molecules $\sigma \sim 10^{-19}$–10^{-17}	Excited states of rare gas atoms and rare gas dimer molecules $\sigma \sim 10^{-19}$–10^{-17}
Other	Lower laser level absorbs unless heated	Weak lower level absorption $\sigma \sim 4 \times 10^{-16}$	Windows and dust can be an issue	Windows and dust can be an issue

[a] Note that the triatomic rare gas halides of the form Rg_2X will exhibit similar absorption as the diatomic rare gas ions as the triatomic rare gas halides of this form are essentially ion pairs of an $Rg_2^{(+)}$ ion and the halide ion.

Table 3 Typical formation and quenching reactions and rate coefficients

Formation	
Rare gas plus halogen molecule	$Kr^* + F_2 \rightarrow KrF^*(v, J)+F$ $k \sim 7 \times 10^{-10}$ cm^3/sec; Branching ratio to $KrF^* \sim 1$ $Ar^* + F_2 \rightarrow ArF^*(v, J)+F$ $k \sim 6 \times 10^{-10}$ cm^3/sec; Branching ratio to $ArF^* \sim 60\%$ $Xe^* + F_2 \rightarrow XeF^*(v, J)+F$ $k \sim 7 \times 10^{-10}$ cm^3/sec; Branching ratio to $XeF^* \sim 1$ $Xe^* + HCl(v = 0) \rightarrow Xe + H + Cl$ $k \sim 6 \times 10^{-10}$ cm^3/sec; Branching ratio to $XeCl^* \sim 0$ $Xe^* + HCl(v = 1) \rightarrow XeCl^* + H$ $k \sim 2 \times 10^{-10}$ cm^3/sec; Branching ratio to $XeCl^* \sim 1$
Ion–ion recombination	$Ar^{(+)} + F^{(-)} + Ar \rightarrow ArF^*(v,J)$ $k \sim 1 \times 10^{-25}$ cm^6/sec at 1 atm and below $k \sim 7.5 \times 10^{-26}$ cm^6/sec at 2 atm; Note effective 3-body rate constant decreases further as pressure goes over ~2 atm $Kr^{(+)} + F^{(-)} + Kr \rightarrow KrF^*(v, J)$ $k \sim 7 \times 10^{-26}$ cm^6/sec at 1 atm and below; rolls over at higher pressure
Displacement	$ArF^*(v, J)+Kr \rightarrow KrF^*(v, J)+Ar$ $k \sim 2 \times 10^{-10}$ cm^3/sec; Branching ratio to $KrF^* \sim 1$
Quenching	
Halogen molecule	$XeCl^* + HCl \rightarrow Xe + Cl + HCl$ $k \sim 5.6 \times 10^{-10}$ cm^3/sec; $KrF^* + F_2 \rightarrow Kr + F + F$ $k \sim 6 \times 10^{-10}$ cm^3/sec; All halogen molecule quenching have very high reaction rate constants
3-body inert gas	$ArF^* + Ar + Ar \rightarrow Ar_2F^* + Ar$ $k \sim 4 \times 10^{-31}$ cm^6/sec $KrF^* + Kr + Ar \rightarrow Kr_2F^* + Ar$ $k \sim 6 \times 10^{-31}$ cm^6/sec $XeCl^* + Xe + Ne \rightarrow Xe_2Cl^* + Ne$ $k \sim 1 \times 10^{-33}$ cm^6/sec; 4×10^{-31} cm^6/sec with Xe as 3rd body These reactions yield a triatomic excimer at lower energy that can not be recycled back to the desired laser states
Electrons	$XeCl^* + e \rightarrow Xe + Cl + e$ $k \sim 2 \times 10^{-7}$ cm^3/sec In 2-body quenching by electrons, the charge of the electron interacts with the dipole of the rare gas halide ion pair at long range; above value is typical of others
2-body inert gas	$KrF^* + Ar \rightarrow Ar + Kr + F$ $k \sim 2 \times 10^{-12}$ cm^3/sec $XeCl^* + Ne \rightarrow Ne + Xe + Cl$ $k \sim 3 \times 10^{-13}$ cm^3/sec 2-body quenching by rare gases is typically slow and less important than the reactions noted above

somewhat less in an electric discharge. The photon release is ~5 eV; the quantum efficiency is only 25%. Early laser efficiency measurements (using electron beam excitation) showed laser efficiency in the best cases slightly in excess of 10%, relative to the deposited energy. The discrepancy relative to the quantum efficiency is due to losses in the medium. For the sample estimate in Table 4 and Figure 5 we show approximate density of key species in the absorption chain, estimated on a steady-state approximation of the losses in a KrF laser for an excitation rate of order 1 MW/cc, typical of fast discharge lasers. The net small signal gain is of the order of 5%/cm. The key absorbers are the parent halogen molecule, F_2, the fluoride ion $F^{(-)}$, and the rare gas excited state atoms. A detailed pulsed kinetics code will provide slightly different results due to transient kinetic effects and the intimate coupling of laser extraction to quenching and absorber dynamics. The ratio of gain to loss is usually in the range of 7 to 20, depending on the actual mixture used and the rare gas halide wavelength. The corresponding extraction efficiency is then limited to the range of ~50%. The small signal gain, g_o, is related to the power deposition

Table 4 Typical ground and excited state densities shown for KrF at $P_{in} \sim 1$ MW/cm^3

Species	*Amount particles/cm^3*	*Absorption σ (cm)^2*	*Loss %/cm*
F_2	$\sim 1.2 \times 10^{17}$	1.5×10^{-20}	0.18
Kr	$\sim 3 \times 10^{18}$	–	–
Buffer	4×10^{19}	–	–
$F^{(-)}$	$\sim 10^{14}$	5×10^{-18}	0.05
Rg^*, Rg^{**}	1×10^{15}	$\langle 10^{-18} \rangle$ depends on ratio of Rg^{**}/Rg^*	0.1
KrF (before dissociating)	$\sim 10^{12}$	2×10^{-16}	0.02
Rg_2F^*	8×10^{14}, Note this species density decreases as flux grows	1×10^{-18}	0.08
KrF^* (B)	2.5×10^{14}	2×10^{-16}	5 (gain)


Pumping @ 1MW/cc
~3×10^23 Excitations/cc sec
KrF* (B,C)
Fluorescence
Quenching
(τ)^-1 ~1.4×10^8/sec
Stimulated Emission and Losses
3-body: (τ)^-1 ~1.4×10^8/sec
electrons: (τ)^-1 ~1×10^8/sec
F2: (τ)^-1~0.6×10^8/sec
Net small signal Gain: go~5%/cm
Loss
Laser output ~ 55% of power @ ROPTIMUM
Gain to nonsaturable loss ratio ~13/1
Saturable loss
Windows ~0.05%/cm equivalent
F2 ~0.18%/cm
F(-) ~0.05%/cm
Rg*, Rg** ~0.1%/cm
Rg2(+) Rg2F ~0.08%/cm

Figure 5 The major decay paths and absorbers that impact the extraction of excited states of rare gas halide excimers. Formation is via the ion–ion recombination, excited atom reaction with halogens and displacement reactions, not shown. We note for a specific mixture of KrF the approximate values of the absorption by the transient and other species along with the decay rates for the major quenching processes. Extraction efficiency greater than 50% is quite rare.

rate per unit volume, $P_{\text{deposited}}$, by eqn [10].

$$P_{\text{deposited}} = g_0 E^* (\tau_{\text{upper}} \eta_{\text{pumping}} \eta_{\text{branching}} f \sigma)^{-1} \qquad [10]$$

E^* is the energy per excitation, ~20 eV or 3.2×10^{-18} J/excitation, f is the fraction of excited molecules in the upper laser level, ~40% due to KrF^* in higher vibrational states and the slowly radiating 'C' state. The laser cross-section is σ, and the η terms are efficiencies for getting from the primary excitation down to the upper laser level. The upper state lifetime, τ_{upper}, is the sum of the inverses of radiative and quenching lifetimes. When the laser cavity flux is sufficiently high, stimulated emission decreases the flow of power into the quenching processes.

The example shown here gives a ratio of net gain to the nonsaturating component of loss of 13/1. Of the excitations that become KrF^*, only ~55% or so will be extracted in the best of cases. For other less ideal rare gas halide lasers, the gain to loss ratio, the extraction efficiency, and the intrinsic efficiency are all lower. Practical discharge lasers have lower practical wall plug efficiency due to a variety of factors, discussed below.

Discharge Technology

Practical discharge lasers use fast-pulse discharge excitation. In this scheme, an outgrowth of the CO_2 TEA laser, the gas is subjected to a rapid high-voltage pulse from a low-inductance pulse forming line or network, PFL or PFN. The rapid pulse serves to break down the gas, rendering it conductive with an electron density of $> \sim 10^{14}$ electrons/cm^3. As the gas becomes conductive, the voltage drops and power is coupled into the medium for a short duration, typically less than 50 nsec. The discharge laser also requires some form of 'pre-ionization', usually provided by sparks or a corona-style discharge on the side of the discharge electrodes. The overall discharge process is intrinsically unstable, and pump pulse duration needs to be limited to avoid the discharge becoming an arc.

Moreover, problems with impedance matching of the PFN or PFL with the conductive gas lead to both inefficiency and extra energy that can go into post-discharge arcs, which both cause component failure and produce metal dust which can give rise to window losses. A typical discharge laser has an aperture of a few cm^2 and a gain length of order 80 cm and produces outputs in the range of 100 mJ to 1 J. The optical pulse duration tends to be ~20 nsec, though the electrical pulse is longer due to the finite time needed for the gain to build up and the stimulated emission process to turn spontaneously emitted photons into photons in the laser cavity.

The pre-ionizer provides an initial electron density on the order of 10^8 electrons/cm^3. With spark pre-ionization or corona pre-ionization, it is difficult to make a uniform discharge over an aperture greater than a few cm^2. For larger apertures, one uses X-rays for pre-ionization. X-ray pre-ionized discharge excimer lasers have been scaled to energy well over 10 J per pulse and can yield pulse durations over 100 nsec. The complexity and expense of the X-ray approach, along with the lack of market for lasers in this size range, resulted in the X-ray approach remaining in the laboratory.

Aside from the kinetic issues of the finite time needed for excitation to channel into the excimer upper levels and the time needed for the laser to 'start up' from fluorescent photons, these lasers have reduced efficiency due to poor matching of the pump source to the discharge. Ideally, one would like to have a discharge such that when it is conductive the voltage needed to sustain the discharge is less than half of that needed to break the gas down. Regrettably for the rare gas halides (and in marked distinction to the CO_2 TEA laser) the voltage that the discharge sustains in a quasi-stable mode is ~20% of the breakdown voltage, perhaps even less, depending on the specific gases and electrode shapes.

Novel circuits, which separate the breakdown phase from the fully conductive phase, can readily double the efficiency of an excimer discharge laser, though this approach is not necessary in many applications. The extra energy that is not dissipated in the useful laser discharge often results in arcing or 'hot' discharge areas after the main laser pulse, leading to electrode sputtering, dust that finds its way to windows, and the need to service the laser after ~10^8 pulses. When one considers the efficiency of the power conditioning system, along with the finite kinetics of the laser start-up process in short pulses, and the mismatch of the laser impedance to the PFN/PFL impedance, lasers that may have 10% intrinsic efficiency in the medium in e-beam excitation may only have 2% to 3% wall plug efficiency in a practical discharge laser.

A key aspect of excimer technology is the need for fast electrical circuits to drive the power into the discharge. This puts a significant strain on the switch that is used to start the process. While spark gaps, or multichannel spark gaps, can handle the required current and current rate of rise, they do not present a practical alternative for high-pulse rate operation. Thyratrons and other switching systems, such as solid state switches, are more desirable than a spark gap, but do not offer the desired needed current rate of rise. To provide the pumping rate of order 1 MW/cm^3 needed for enough gain to turn the laser on before the discharge becomes unstable, the current needs to rise to a value of the order of 20 kA in a time of ~20 nsec; the current rate of rise is ~10^{12} A/sec. This rate of rise will limit the lifetime of the switch that drives the power into the laser gas. As a response to this need, magnetic switching and magnetic compression circuits were developed so that the lifetime of the switch can be radically increased. In the simplest cases, one stage of magnetic compression is used to make the current rate of rise to be within the range of a conventional thyratron switch as used in radar systems. Improved thyratrons and a simple magnetic assist also work. For truly long operating lifetimes, multiple stages of magnetic switching and compression are used, and with a transformer one can use a solid state diode as the start switch for the discharge circuit. A schematic of an excimer pulsed power circuit, that uses a magnetic assist with a thyratron and one stage of magnetic compression, is shown in Figure 6. The magnetic switching approach can also be used to provide two separate circuits to gain high efficiency by having one circuit to break down the gas (the spiker) and a second, low-impedance 'sustainer' circuit, to provide the main power flow. In this approach, the laser itself can act as part of the circuit by holding off the sustaining voltage for a μ-sec or so during the charge cycle and before the spiker breaks down the gas. A schematic of such a circuit is shown in Figure 7. Using this type of circuit, the efficiency of a XeCl laser can be over 4% relative to the wall plug. A wide variety of technological twists on this approach have been researched.



Figure 6 One of the variants on magnetic switching circuits that have been used to enhance the lifetime of the primary start switch. A magnetic switch in the form of a simple 1 turn inductor with a saturable core magnetic material such as a ferrite allows the thyratron to turn on before major current flows. Other magnetic switches may be used in addition to peak up the voltage rate of rise on the laser head or to provide significant compression. For example one may have the major current flow in the thyratron taking place on the 500 nsec time scale while the voltage pulse on the discharge is in the 50 nsec duration. A small current leaks through and is accommodated by the charging inductor.



Figure 7 For the ultimate in efficiency the circuit can be arranged to provide a leading edge spike that breaks the gas down using a high impedance 'spiker' and a separate circuit that is matched to the discharge impedance when it is fully conductive. High coupling efficiency reduces waste energy that can erode circuit and laser head components via late pulse arcs. The figure shows a magnetic switch as the isolation but the scheme can be implemented with a second laser head as the isolation switch, a rail gap (not appropriate for long life) or a diode at low voltage.

Excimer lasers present some clear differences in resonator design compared to other lasers. The apertures are relatively large, so one does not build a TEM$_{00}$ style cavity for good beam quality and expect to extract any major portion of the energy available. The typical output is divergent and multimode. When excimer lasers are excited by a short pulse discharge, ~30 nsec, the resulting gain duration is also short, ~20 nsec, limiting the number of passes a photon in a resonator can have in the gain. The gain duration of ~20 nsec only provides ~3.5 round trips of a photon in the cavity during the laser lifetime, resulting in the typical high-order multimode beam. Even with an unstable resonator, the gain duration is not long enough to collapse the beam into the lowest-order diffraction-limited output. If line narrowing is needed, and reasonable efficiency is required, an oscillator amplifier configuration is often used with the oscillator having an appropriate tuning resonator in the cavity. If both narrow spectral linewidth and excellent beam quality are needed one uses a seeded oscillator approach where the narrowband oscillator is used to seed an unstable resonator on the main amplifier. By injecting the seed into the unstable resonator cavity, a few nsec before the gain is turned on, the output of the seeded resonator can be locked in wavelength, bandwidth, and provide good beam quality. Long pulse excimer lasers, such as e-beam excited lasers or long pulse X-ray pre-ionized discharge devices can use conventional unstable resonator technology with good results.

Excimer lasers are gas lasers that run at both high pressure and high instantaneous power deposition rates. During a discharge pulse, much of the halogen bearing 'fuel' is burned out by the attachment and reactive processes. The large energy deposition per pulse means that pressure waves are generated. All of these combine with the characteristic device dimensions to require gas flow to recharge the laser mixture between pulses. For low pulse rates, less than ~200 Hz, the flow system need not be very sophisticated. One simply needs to flush the gas from the discharge region with a flow having a velocity of the order of 5 m/sec for a typical discharge device. The flow is transverse to the optical and discharge directions. At high pulse rates, the laser designer needs to consider flow in much more detail to minimize the power required to push the gas through the laser head. Circulating pressure waves need to be damped out so that the density in the discharge region is controlled at the time of the next pulse. Devices called acoustic dampers are placed in the sides of the flow loop to remove pressure pulses. A final subtlety occurs in providing gas flow over the windows. The discharge, post pulse arcs, and reactions of the halogen source with the metal walls and impurities creates dust. When the dust coats the windows, the losses in the cavity increase, lowering efficiency. By providing a simple gas flow over the window, the dust problem can be ameliorated. For truly long life, high-reliability lasers, one needs to take special care in the selection of materials for electrodes and insulators and avoid contamination, by assembling in clean environments.

See also

Lasers: Carbon Dioxide Lasers. **Laser-Induced Damage of Optical Materials**. **Nonlinear Optics,**

Applications: Pulse Compression via Nonlinear Optics; Raman Lasers. **Scattering:** Raman Scattering.

Further Reading

Ballanti S, Di Lazzaro P, Flora F, *et al.* (1998) Ianus the 3-electrode laser. *Applied Physics B* 66: 401–406.

Brau CA (1978) Rare gas halogen lasers. In: Rhodes CK (ed.) *Excimer Lasers, Topics of Applied Physics*, vol. 30. Berlin: Springer Verlag.

Brau CA and Ewing JJ (1975) Emission spectra of XeBr, XeCl, XeF, and KrF. *Journal of Chemical Physics* 63: 4640–4647.

Ewing JJ (2000) Excimer laser technology development. *IEEE Journal of Selected Topics in Quantum Electronics* 6(6): 1061–1071.

Levatter J and Lin SC (1980) Necessary conditions for the homogeneous formation of pulsed avalanche discharges at high pressure. *Journal of Applied Physics* 51: 210–222.

Long WH, Plummer MJ and Stappaerts E (1983) Efficient discharge pumping of an XeCl laser using a high voltage prepulse. *Applied Physics Letters* 43: 735–737.

Rhodes CK (ed.) (1979) *Excimer Lasers, Topics of Applied Physics*, vol. 30. Berlin: Springer-Verlag.

Rokni M, Mangano J, Jacob J and Hsia J (1978) Rare gas fluoride lasers. *IEEE Journal of Quantum Electronics* QE-14: 464–481.

Smilanksi I, Byron S and Burkes T (1982) Electrical excitation of an XeCl laser using magnetic pulse compression. *Applied Physics Letters* 40: 547–548.

Taylor RS and Leopold KE (1994) Magnetic-spiker excitation of gas discharge lasers. *Applied Physics B, Lasers and Optics* 59: 479–509.

Free Electron Lasers

A Gover, Tel-Aviv University, Tel-Aviv, Israel

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The Free Electron Laser (FEL) is an exceptional kind of laser. Its active medium is not matter, but charged particles (electrons) accelerated to high energies, passing in vacuum through a periodic undulating magnetic field. This distinction is the main reason for the exceptional properties of FEL: operating at a wide range of wavelengths – from mm-wave to X-rays with tunability, high power, and high efficiency.

In this article we explain the physical principles of FEL operation, the underlying theory and technology of the device and various operating schemes, which have been developed to enhance performance of this device.

The term ‘Free Electron Laser’ was coined by John Madey in 1971, pointing out that the radiative transitions of the electrons in this device are between free space (more correctly – unbound) electron quantum states, which are therefore states of continuous energy. This is in contrast to conventional atomic and molecular lasers, in which the electron performs radiative transition between bound (and therefore of distinct energy) quantum states. Based on these theoretical observations, Madey and his colleagues in Stanford University demonstrated FEL operation first as an amplifier (at $\lambda = 10.6\ \mu\text{m}$) in 1976, and subsequently as an oscillator (at $\lambda = 3.4\ \mu\text{m}$) in 1980.

From the historical point of view, it turned out that Madey’s invention was essentially an extension of a former invention in the field of microwave-tubes technology – the Ubitron. The Ubitron, a mm-wave electron tube amplifier based on a magnetic undulator, was invented and developed by Philips and Enderbry who operated it at high power levels in 1960. The early Ubitron development activity was not noticed by the FEL developers because of the disciplinary gap, and largely because its research was classified at the time. Renewed interest in high-power mm-wave radiation emission started in the 1970s, triggered by the development of pulsed-line generators of ‘Intense Relativistic Beams’ (IRB). This activity, led primarily by plasma physicists in the defense establishment laboratories of Russia (mostly IAP in Gorky – Nizhny Novgorod) and the US (mostly N.R.L. – DC) led to development of high-gain high-power mm-wave sources independently of the development of the optical FEL. The connection between these devices and between them to conventional microwave tubes (as Traveling Wave Tubes – TWT) and other electron beam radiation schemes, like Cenenkov and Smith-Purcell radiation that may also be considered FELs, was revealed in the mid-1970s, starting with the theoretical works of P. Spangle, A. Gover and A. Yariv who identified that all these devices satisfy the same dispersion equation as the TWT derived by John Pierce in the 1940s. Thus, the optical FEL could be conceived as a kind of immense electron tube, operating with a high-energy electron beam in the low gain regime of the Pierce TWT dispersion equation.

The extension of the low-gain FEL theory to the general 'electron-tube' theory is important because it led to development of new radiation schemes and new operating regimes of the optical FEL. This was exploited by physicists in the discipline of accelerator physics and synchrotron radiation, who identified, starting with the theoretical works of C. Pellegrini and R. Bonifacio in the early 1980s, that high-current, high-quality electron beams, attainable with further development of accelerators technology, could make it possible to operate FELs in the high-gain regime, even at short wavelengths (vacuum ultra-violet – VUV and soft X-ray) and that the high-gain FEL theory can be extended to include amplification of the incoherent synchrotron spontaneous emission (shot noise) emitted by the electrons in the undulator. These led to the important development of the 'self (synchrotron) amplified spontaneous emission (SASE) FEL', which promised to be an extremely high brightness radiation source, overcoming the fundamental obstacles of X-ray lasers development: lack of mirrors (for oscillators) and lack of high brightness radiation sources (for amplifiers).

A big boost to the development of FEL technology was given during the period of the American 'strategic defense initiative – SDI' (Star-Wars) program in the mid-1980s. The FEL was considered one of the main candidates for use in a ground-based or space-based 'directed energy weapon – DEW', that can deliver megawatts of optical power to hit attacking missiles. The program led to heavy involvement of major American defense establishment laboratories (Lawrence–Livermore National Lab, Los-Alamos National Lab) and contracting companies (TRW, Boeing). Some of the outstanding results of this effort were demonstration of the high-gain operation of an FEL amplifier in the mm-wavelength regime, utilizing an Induction Linac (Livermore, 1985), and demonstration of enhanced radiative energy extraction efficiency in FEL oscillator, using a 'tapered wiggler' in an RF-Linac driven FEL oscillator (Los-Alamos, 1983). The program has not been successful in demonstrating the potential of FELs to operate at the high average power levels needed for DEW applications. But after the cold-war period, a small part of the program continues to support research and development of medical FEL application.

Principles of FEL Operation

Figure 1 displays schematically an FEL oscillator. It is composed of three main parts: an electron accelerator, a magnetic wiggler (or undulator), and an optical resonator.

Without the mirrors, the system is simply a synchrotron undulator radiation source. The electrons in the injected beam oscillate transversely to their propagation direction z, because of the transverse magnetic Lorenz force:

$$\mathbf{F}_\perp = -ev_z \hat{\mathbf{e}}_z \times \mathbf{B}_\perp \tag{1}$$

In a planar (linear) wiggler, the magnetic field on axis is approximately sinusoidal:

$$\mathbf{B}_\perp = B_\mathrm{w} \hat{e}_y \cos k_\mathrm{w} z \tag{2}$$

In a helical wiggler:

$$\mathbf{B}_\perp = B_\mathrm{w}(\hat{\mathbf{e}}_y \cos k_\mathrm{w} z + \hat{\mathbf{e}}_x \sin k_\mathrm{w} z) \tag{3}$$



Figure 1 Components of a FEL-oscillator. (Reproduced from Benson SV (2003) Free electron lasers push into new frontiers. *Optics and Photonics News* 14: 20–25. Illustration by Jaynie Martz.)

In either case, if we assume constant (for the planar wiggler – only on the average) axial velocity, then $z = v_z t$. The frequency of the transverse force and the mechanical oscillation of the electrons, as viewed transversely in the laboratory frame of reference, is:

$$\omega_{0s} = k_w v_z = 2\pi \frac{v_z}{\lambda_w} \qquad [4]$$

where $\lambda_w = 2\pi/k_w$ is the wiggler period.

The oscillating charge emits an electromagentic radiation wavepacket. In a reference frame moving with the electrons, the angular radiation pattern looks exactly like dipole radiation, monochromatic in all directions (except for the frequency-line-broadening due to the finite oscillation time, i.e., the wiggler transit time). In the laboratory reference-frame the radiation pattern concentrates in the propagation ($+z$) direction, and the Doppler up-shifted radiation frequency depends on the observation angle Θ relative to the z-axis:

$$\omega_0 = \frac{\omega_{0s}}{1 - \beta_z \cos\Theta} \qquad [5]$$

On axis ($\Theta = 0$), the radiation frequency is:

$$\omega_0 = \frac{c k_w \beta_z}{1 - \beta_z} = (1 + \beta_z)\beta_z \gamma_z^2 c k_w \cong 2\gamma_z^2 c k_w \qquad [6]$$

where $\beta_z \equiv v_z/c$, $\gamma_z \equiv (1 - \beta_z^2)^{-1/2}$ are the axial (average) velocity and the axial Lorenz factor, respectively, and the last part of the equation is valid only in the (common) highly relativistic limit $\gamma_z \gg 1$.

Using the relations $\beta_z^2 + \beta_\perp^2 = \beta^2$, $\beta_\perp = a_w/\gamma$, one can express γ_z:

$$\gamma_z = \frac{\gamma}{1 + a_w^2/2} \qquad [7]$$

(this is for a linear wiggler, in the case of a helical wiggler the denoninator is $1 + a_w^2$):

$$\begin{aligned} \gamma \equiv (1 - \beta^2)^{-1/2} &= 1 + \frac{\varepsilon_k}{mc^2} \\ &= 1 + \varepsilon_k\,[\mathrm{MeV}]/0.511 \end{aligned} \qquad [8]$$

and a_w – (also termed K) 'the wiggler parameter' is the normalized transverse momentum:

$$a_w = \frac{eB_w}{k_w mc} = 0.093 B_w\,[\mathrm{KGauss}]\lambda_w\,[\mathrm{cm}] \qquad [9]$$

Typical values of B_w in FEL wigglers (undulators) are of the order of Kgauss', and λ_w of the order of CMs, and consequently $a_w < 1$. Considering that electron beam accelerator energies are in the range of MeV to GeV, one can appreciate from eqns [6]–[8], that a significant relativistic Doppler shift factor $2\gamma_z^2$, in the range of tens to millions, is possible. It, therefore, provides incoherent synchrotron undulator radiation in the frequency range of microwave to hard X-rays.

Synchrotron undulator radiation was studied in 1951 and since then has been a common source of VUV radiation in synchrotron facilities. From the point of view of laser physics theory, this radiation can be viewed as 'spontaneous synchrotron radiation emission' in analogy to spontaneous radiation emission by electrons excited to higher bound-electron quantum levels in atoms or molecules. Alternatively, it can be regarded as the classical shot noise radiation, associated with the current fluctuations of the randomly injected discrete charges comprising the electron beam. Evidently this radiation is incoherent, and the fields it produces average in time to zero, because the wavepackets emitted by the randomly injected electrons interfere at the observation point with random phase. However, their energies sum up and can produce substantial power.

Based on fundamental quantum-electrodynamical principles or Einstein's relations, one would expect that any spontaneous emission scheme can be stimulated. This principle lies behind the concept of the FEL, which is nothing but stimulated undulator synchrotron radiation. By stimulating the electron beam to emit radiation, it is possible, as with any laser, to generate a coherent radiation wave and extract more power from the gain medium, which in this case is an electron beam, that carries an immense amount of power. There are two kinds of laser schemes which utilize stimulation of synchrotron undulator radiation:

(i) *A laser amplifier.* In this case the mirrors in the schematic configuration of Figure 1 are not present, and an external radiation wave at frequencies within the emission range of the undulator is injected at the wiggler entrance. This requires, of course, an appropriate radiation source to be amplified and availability of sufficiently high gain in the FEL amplifier.

(ii) *A laser oscillator.* In this case an open cavity (as shown in Figure 1) or another (waveguide) cavity is included in the FEL configuration. As in any laser, the FEL oscillator starts building up its radiation from the spontaneous (synchrotron undulator) radiation which gets trapped in the resonator and amplified by stimulated emission along the wiggler. If the threshold condition is satisfied (having single path gain higher than the round trip losses), the oscillator arrives to saturation and steady state coherent operation after a short transient period of oscillation build-up.

Because the FEL can operate as a high-gain amplifier (with a long enough wiggler and an electron beam of high current and high quality), also a third mode of operation exists: self amplified spontaneous emission (SASE). In this case, the resonator mirrors in Figure 1 are not present and the undulator radiation generated spontaneously in the first sections of the long undulator is amplified along the wiggler and emitted at the wiggler exit at high power and high spatial coherence.

The Quantum-Theory Picture

A free electron, propagating in unlimited free space, can never emit a single photon. This can be proven by examining the conservation of energy and momentum conditions:

$$\varepsilon_{k_\mathrm{i}} - \varepsilon_{k_\mathrm{f}} = \hbar\omega \qquad [10]$$

$$\mathbf{k}_\mathrm{i} - \mathbf{k}_\mathrm{f} = \mathbf{q} \qquad [11]$$

that must be satisfied, when an electron in an initial free-space energy and momentum state $(\varepsilon_{k_\mathrm{i}}, \hbar k_\mathrm{i})$ makes a transition to a final state $(\varepsilon_{k_\mathrm{f}}, \hbar k_\mathrm{f})$, emitting a single photon of energy and momentum $(\hbar\omega, q)$. In free space:

$$\varepsilon_k = c\sqrt{(\hbar \mathbf{k})^2 + (mc^2)^2} \qquad [12]$$

$$\mathbf{q} = \frac{\omega}{\mathrm{c}}\hat{\mathrm{e}}_q \qquad [13]$$

and eqns [10]–[13] have only one solution, $\omega = 0$, $\mathbf{q} = 0$. This observation is illustrated graphically in the energy–momentum diagram of Figure 2a in the framework of a one-dimensional model. It appears that if both eqns [10] and [11] can be satisfied, then the phase velocity of the emitted radiation wave $v_\mathrm{ph} = \omega/q$ (the slope of the chord) will equal the electron wavepacket group velocity $v_\mathrm{g} = v_\mathrm{z}$ at some intermediate point $k^* = p^*/\hbar$:

$$v_\mathrm{ph} = \frac{\omega}{q} = \frac{\varepsilon_{k\mathrm{i}} - \varepsilon_{k\mathrm{f}}}{\hbar(k_\mathrm{i} - k_\mathrm{f})} = \left.\frac{\partial\varepsilon}{\partial p}\right|_{\mathrm{p}^*} = v_\mathrm{g} \qquad [14]$$

For a radiation wave in free space (eqn [13]), this results in $c = v_\mathrm{g}$, which contradicts special relativity.

The reason for the failure to conserve both energy and momentum in the transition is that the photon momentum $\hbar q$ it too small to absorb the large momentum shift of the electron, as it recoils while releasing radiative energy $\hbar\omega$. This observation leads to ideas on how to make a radiative transition possible:

(i) *Limit the interaction length*. If the interaction length is L, the momentum conservation



Figure 2 Conservation of energy and momentum in forward photon emission of a free electron: (a) The slope of the tangent to the curve at intermediate point k^*, $\partial\varepsilon_k(k^*)/\partial k$ may be equal to the slope of the chord $\hbar\omega/q$ which is impossible in free space. (b) electron radiative transition made possible with an electromagnetic pump (Compton Scattering). (c) The wiggler wavenumber – k_w conserves the momentum in electron radiative transition of FEL.

condition in eqn [11] must be satisfied only within an uncertainty range $\pm\pi/L$. This makes it possible to obtain radiative emission in free electron radiation effects like 'Transition Radiation' and in microwave tubes like the Klystron.

(ii) *Propagate the radiation wave* in a 'slow wave' structure, where the phase velocity of the radiation wave is smaller than the speed of light, and satisfaction of eqn [14] is possible. For example, in the Cerenkov effect, charged particles pass through a medium (gas) with index of refraction $n > 1$. Instead of eqn [13], $\mathbf{q} = n(\omega)(\omega/c)\hat{e}_q$, and consequently $q_z = n(\omega)(\omega/c)\cos\Theta_q$, where we assume radiative emission at an angle Θ_q relative to the electron propagation axis z. Substitution in eqn [14] results in the Cerenkov radiation condition $v_g n(\omega)\cos\Theta_q = 1$.

Another example for radiation emission in a slow-wave structure is the Traveling Wave Tube (TWT). In this device, a periodic waveguide of periodicity λ_w permits (via the Floquet theorem) propagation of slow partial waves (space harmonics) with increased wavenumber $q_z + mk_w$ ($m = 1, 2, \ldots$), and again eqn [14] can be satisfied.

(iii) *Rely on a 'two-photon' radiative transition.* This can be 'real photon' Compton scattering of an intense radiation beam (electromagnetic pump) off an electron beam, or 'virtual photon' scattering of a static potential, as is the case in bremsstrahlung radiation and in synchrotron–undulator radiation. The latter radiation scheme may be considered as a 'magnetic brehmsstrahlung' effect or as 'zero frequency pump' Compton scattering, in which the wiggler contributes only 'crystal momentum' $\hbar k_w$, to help satisfy the momentum conservation condition in eqn [11]. The Compton scattering scheme is described schematically for the one-dimensional (back scattering) case in Figure 3, and its conservation of energy and momentum diagram is depicted in Figure 2b (a 'real photon' (ω_w, k_w) free-space pump wave is assumed with $k_w = \omega_w/c$). The analogous diagram of a static wiggler ($\omega_w = 0$, $k_w = 2\pi/\lambda_w$) is shown in Figure 2c. It is worth noting that the effect of the incident scattered wave or the wiggler is not necessarily a small perturbation. It may modify substantially the electron energy-dispersion diagram of the free electron and a more complete 'Brillouin diagram' should be used in Figure 2c. In this sense, the wiggler may be viewed as the analogue of a one-dimensional crystal, and its period λ_w analogous to the crystal lattice constant. The momentum conservation during a radiation transition, with the aid of the wiggler 'crystal momentum' $\hbar k_w$ is quite analogous to the occurrence of vertical radiative transitions in direct bandgap semiconductors, and thus the FEL has, curiously enough, some analogy to microscopic semiconductor lasers.



Figure 3 The scheme of backward scattering of an electromagnetic wave off an electron beam (Doppler shifted Compton scattering).

All the e-beam radiation schemes already mentioned can be turned into stimulated emission devices, and thus may be termed 'free electron lasers' in the wide sense. The theory of all of these devices is closely related, but most of the technological development was carried out on undulator radiation (Magnetic brehmsstrahlung) FELs, and the term FEL is usually reserved for this kind (though some developments of Cerenkov and Smith–Purcell FELs are still carried out).

When considering a stimulated emission device, namely enhanced generation of radiation in the presence of an external input radiation wave, one should be aware, that in addition to the emission process described by eqns [10] and [11] and made possible by one of the radiation schemes described above, there is also a stimulated absorption process. Also, this electronic transition process is governed by the conservation of energy and momentum conditions, and is described by eqns [10] and [11] with k_i and k_f exchanged.

Focusing on undulator-radiation FEL and assuming momentum conservation in the axial (z) dimension by means of the wiggler wavenumber k_w, the emission and absorption quantum transition levels and radiation frequencies are found from the solution of equations:

$$\varepsilon_{k_{zi}} - \varepsilon_{k_{zf}} = \hbar\omega_e \qquad [15a]$$

$$k_{zi} - k_{zf} = q_{ze} + k_w \qquad [15b]$$

$$\varepsilon_{k_{za}} - \varepsilon_{k_{zi}} = \hbar\omega_a \qquad [16a]$$

$$k_{za} - k_{zi} = q_{za} + k_w \qquad [16b]$$

For fixed k_w, fixed transverse momentum and given e-beam energy $\varepsilon_{k_{zi}}$ and radiation emission angle Θ_q ($q_z = (\omega/c)\cos\Theta_q$), eqns [15] and [16] have separately



Figure 4 The figure illustrates that the origin of difference between the emission and absorption frequencies is the curvature of the energy dispersion line, and the origin of the homogeneous line broadening is momentum conservation uncertainty $\pm\pi/L$ in a finite interaction length. (Reproduced with permission from Friedman A, Gover A, Ruschin S, Kurizki G and Yariv A (1988) Spontaneous and stimulated emission from quasi-free electrons. *Reviews of Modern Physics* 60: 471–535. Copyright (1988) by the American Physical Society.)

distinct solutions, defining the electron upper and lower quantum levels for radiative emission and absorption respectively. The graphical solutions of these two set of equations are shown in Figure 4, which depicts also the 'homogeneous' frequency-line broadening $\hbar\Delta\omega_e$, $\hbar\Delta\omega_a$ of the emission and absorption lines due to the uncertainty in the momentum conservation $\pm\pi/L$ in a finite interaction length. In the quantum limit of a cold (monoenergetic) e-beam and a long interaction length L, the absorption line center ω_a is larger than the emission line center ω_e, and the linewidths $\Delta\omega_e \cong \Delta\omega_a = \Delta\omega_L$ are narrower than the emission and absorption lines spacing $\omega_a - \omega_e$, as shown in Figure 5a. The FEL then behaves as a 3-level quantum system, with electrons occupying only the central level, and the upper level is spaced apart from it more than the lower level (Figure 4).



Figure 5 Net gain emission/absorption frequency lines of FEL: (a) in the quantum limit: $\omega_a - \omega_e \gg \Delta\omega_L$, (b) in the classical limit: $\omega_a - \omega_e \ll \Delta\omega_L$.

In the classical limit $\hbar \to 0$, one can Taylor-expand ε_{kz} around k_{zi}. Using:

$$v_z = \frac{1}{\hbar}\frac{\partial \varepsilon_{kz}}{\partial k_z}, \qquad \frac{1}{\gamma_z^2 \gamma m} = \frac{1}{\hbar^2}\frac{\partial^2 \varepsilon_{kz}}{\partial k_z^2}$$

one obtains:

$$\omega_e \cong \omega_a \cong \omega_0 = v_z(q_{z0} + k_w) \qquad [17]$$

which for $q_{z0} = (\omega/c)\cos\Theta_q$ reproduces the classical synchronism condition in eqn [5]. The homogeneous broadening linewidth is found to be:

$$\frac{\Delta\omega_L}{\omega_0} = \frac{1}{N_\mathrm{w}} \qquad [18]$$

where $N_\mathrm{w} = L/\lambda_\mathrm{w}$ is the number of wiggler periods.

The classical limit condition requires that the difference between the emission and absorption line centers will be smaller than their width. This is expressed in terms of the 'recoil parameter ε' (for $\Theta_q = 0$):

$$\varepsilon = \frac{\omega_\mathrm{a} - \omega_\mathrm{e}}{\Delta\omega_L} = \frac{1+\beta}{\beta_z^2}\frac{\hbar\omega_0}{\gamma mc^2}N_\mathrm{w} \ll 1 \qquad [19]$$

This condition is satisfied in all practical cases of realizable FELs. When this happens, the homogeneous line broadening dominates over the quantum-recoil effect, and the emission and absorption lines are nearly degenerate (Figure 5b). The total quantum-electrodynamic photonic emission rate expression:

$$\frac{\mathrm{d}\nu_q}{\mathrm{d}t} = \Gamma_\mathrm{sp}\left[(\nu_q+1)F(\omega-\omega_\mathrm{e}) - \nu_q F(\omega-\omega_\mathrm{a})\right] \qquad [20]$$

reduces then into:

$$\frac{\mathrm{d}\nu_q}{\mathrm{d}t} = \nu_q\Gamma_\mathrm{sp}\varepsilon\Delta\omega_L\frac{\mathrm{d}}{\mathrm{d}\omega}F(\omega-\omega_\mathrm{e}) + \Gamma_\mathrm{sp}F(\omega-\omega_0) \qquad [21]$$

Here ν_q is the number of photons in radiation mode q, Γ_sp – the spontaneous emission rate, and $F(\omega-\omega_0)$ is the emission (absorption) lineshape function. Figure 5b depicts the transition of the net radiative emission/absorption rate into a gain curve which is proportional to the derivative of the spontaneous emission lineshape function (first term in eqn [21]). Equation [21] presents a fundamental relation between the spontaneous and stimulated emission of FELs, which was observed first by John Madey (Madey's theorem). It can be viewed as an extension of Einstein's relations to a classical radiation source.

The Classical Picture

The spontaneous emission process of FEL (synchrotron undulator radiation) is nothing but dipole radiation of the undulating electrons, which in the laboratory frame of reference is Doppler shifted to high frequency. The understanding of the stimulated emission process requires a different approach.

Consider a single electron, following a sinusoidal trajectory under the effect of a planar undulator magnetic field in eqn [2] (Figure 1):

$$v_x = v_\mathrm{w}\cos k_\mathrm{w}z_\mathrm{e}(t) \qquad [22]$$

$$x = x_\mathrm{w}\sin k_\mathrm{w}z_\mathrm{e}(t) \qquad [23]$$

where $v_\mathrm{w} = ca_\mathrm{w}/\gamma$ and $x_\mathrm{w} = v_\mathrm{w}/(v_z k_\mathrm{w})$. An electromagnetic wave $E_x(z,t) = E_0\cos(\omega t - k_z z)$ propagates collinearly with the electron. Figure 6 displays the electron and wave 'snap-shot' positions as they propagate along one wiggler period λ_w.

If the electron, moving at average axial velocity v_z, enters the interaction region $z = 0$ at $t = 0$, its axial position is $z_\mathrm{e}(t) = v_z t$, and the electric force it experiences is $-eE_x(z_\mathrm{e}(t),t) = -eE_0\cos(\omega - k_z v_z)t$. Clearly, this force is (at least initially at $t = 0$) opposite to the transverse velocity of the electron $v_x = v_\mathrm{w}\cos(k_\mathrm{w}v_z)t$ (imply in deceleration) and the power exchange rate $-ev_\mathrm{e}\cdot E = -ev_x E_x$ corresponds to transfer of energy into the radiation field on account of the electron kinetic energy. Because the phase velocity of the radiation mode is larger than the electron velocity, $v_\mathrm{ph} = \omega/k_z > v_z$, the electron phase $\varphi_\mathrm{e} = (\omega - k_z v_z)t$ grows, and the power exchange rate $-ev_x E_x$ changes. However, if one synchronizes the electron velocity, so that while the electron traverses one wiggler period ($t = \lambda_\mathrm{w}/v_z$), the electron phase advances by $2\pi : (\omega - k_z v_z)\cdot\lambda_\mathrm{w}/v_z = 2\pi$, then the power exchange rate from the electron to the wave remains non-negative through the entire interaction length, because then the electron transverse velocity



Figure 6 'Snapshots' of an electromagnetic wave period slipping relative to an undulating electron along one wiggler period λ_w. The energy transfer to the wave $-$ $e\mathbf{v}\cdot\mathbf{E}$ remains non-negative all along.

v_x and the wave electric field E_x reverse sign, at each period exactly at the same points $(\lambda_w/4, 3\lambda_w/4)$. This situation is depicted in Figure 6, which shows the slippage of the wave crests relative to the electron at five points along one wiggler period. The figure describes the synchronism condition, in which the radiation wave slips one optical period ahead of the electron, while the electron goes through one wiggle motion. In all positions along this period, $v{\cdot}E \geq 0$ (in a helical wiggler and a circularly polarized wave this product is constant and positive $v{\cdot}E > 0$ along the entire period). Substituting $\lambda_w = 2\pi/k_w$, this phase synchronism condition may be written as:

$$\frac{\omega}{v_z} = k_z + k_w \qquad [24]$$

which is the same as eqns [17] and [5].

Figure 6 shows that a single electron (or a bunch of electrons of duration smaller than an optical period) would amplify a co-propagating radiation wave, along the entire wiggler, if it satisfies the synchronism condition in eqn [24] and enters the interaction region ($z = 0$) at the right (decelerating) phase relative to the radiation field. If the electron enters at the opposite phase it accelerates (on account of the radiation field energy which is then attenuated by 'stimulated absorption'). Thus, when an electron beam is injected into a wiggler at the synchronism condition with electrons entering at random times, no net amplification or absorption of the wave is expected on the averages. Hence, some more elaboration is required, in order to understand how stimulated emission gain is possible then.

Before proceeding, it is useful to define the 'pondermotive force' wave. This force originates from the nonlinearity of the Lorenz force equation:

$$\frac{\mathrm{d}}{\mathrm{d}t}(\gamma m\mathbf{v}) = -e(\mathbf{E} \times \mathbf{v} \times \mathbf{B}) \qquad [25]$$

At zero order (in terms of the radiation fields), the only field force on the right-hand side of eqn [25] is due to the strong wiggler field (eqns [2] and [3]), which results in the transverse wiggling velocity (eqn [22] for a linear wiggler). When solving next eqn [25] to first order in terms of the radiation fields:

$$\begin{aligned} \mathbf{E}_s(r,\mathbf{t}) &= \mathrm{Re}\left[\tilde{\mathbf{E}}_s\, \mathrm{e}^{\mathrm{i}(k_z z - \omega t)}\right] \\ \mathbf{B}_s(r,\mathbf{t}) &= \mathrm{Re}\left[\tilde{\mathbf{B}}_s\, \mathrm{e}^{\mathrm{i}(k_z z - \omega t)}\right] \end{aligned} \qquad [26]$$

the cross product $\mathbf{v} \times \mathbf{B}$ between the transverse components of the velocity and the magnetic field generates a longitudinal force component:

$$\mathrm{F}_{\mathrm{pm}}(z,t) = \mathrm{Re}\left[\hat{\mathrm{e}}_z \tilde{\mathrm{F}}_{\mathrm{pm}} \mathrm{e}^{\mathrm{i}(k_z + k_w)z - \mathrm{i}\omega t}\right] \qquad [27]$$

that varies with the beat wavenumber $k_s + k_w$ at slow phase velocity ($v_{\mathrm{ph}} = \omega/(k_z + k_w) < c$). This slow force-wave is called the pomdermotive (PM) wave. Assuming the signal radiation wave in eqn [26] is polarization-matched to the wiggler (linearly polarized or circularly polarized for a linear or helical wiggler respectively), the PM force amplitude is given by:

$$|\tilde{F}_{\mathrm{pm}}| = e|\tilde{E}_{s\perp}|a_w/\gamma\beta_z \qquad [28]$$

With large enough k_w, it is always possible to slow down the phase velocity of the pondermotive wave until it is synchronized with the electron velocity:

$$v_{\mathrm{ph}} = \frac{\omega}{k_z + k_w} = v_z \qquad [29]$$

and can apply along the interaction length a decelerating axial force, that will cause properly phased electrons to transfer energy to the wave on account of their longitudinal kinetic energy.

This observation is of great importance. It reveals that even though the main components of the wiggler and radiation fields are transverse, the interaction is basically longitudinal. This puts the FEL on an equal footing with the slow-wave structure devices as the TWT and the Cerenkov–Smith–Purcell FELs, in which the longitudinal interaction takes place with the longitudinal electric field component of a slow TM radiation mode. The synchronism condition in eqn [29] between the pondermotive wave and the electron, which is identical with the phase-matching condition in eqn [24], is also similar to the synchronism condition between an electron and a slow electromagnetic wave (eqn [14]).

Using the pondermotive wave concept, we can now explain the achievement of gain in the FEL with a random electron beam. Figure 7 illustrates the interaction between the pondermotive wave and electrons, distributed at the entrance ($z = 0$) randomly within the wave period. Figure 7a shows 'snap-shots' of the electrons in one period of the pondermotive wave $\lambda_{\mathrm{pm}} = 2\pi/(k_z + k_w)$ at different points along the wiggler, when it is assumed that the electron beam is perfectly synchronous with the pondermotive wave $v_{\mathrm{ph}} = v_0$. As explained before, some electrons are slowed down, acquiring negative velocity increment Δv. However, for each such electron, there is another one, entering the wiggler at an accelerating phase of the wave, acquiring the same positive velocity increment Δv. There is then no net change in the energy of the e-beam or the wave, however, there is clearly an effect of 'velocity-bunching' (modulation), which turns along the wiggler into 'density-bunching' at the same



(a) Pure bunching : $v_{ph} = v_{z0}$, $\Delta\varphi(z) = 0$



(b) Optical Klystron : $v_{ph} = v_{z0}$, $\Delta\varphi[L_b+L_d] = \frac{\pi}{2}$



(c) FEL : $v_{z0} \geq v_{ph}$, $\Delta\varphi_c(L) = 2.6$

Figure 7 'Snapshots' of a pondermotive wave period interacting L with an initially uniformly distributed electron beam taking place respectively along the interaction length $0 < z < L_b$. (a) Exact synchronism in a uniform wiggler (bunching). (b) Energy bunching, density bunching and radiation are in the energy buncher, dispersive magnet $L_b < z < L_b + L_d$ and radiating wiggler $L_b + L_d < z < L_b + L_d + L_r$ sections of an Optical–Klystron. (c) Slippage from bunching phase to radiating phase at optimum detuning off synchronism in a uniform wiggler FEL.

frequency ω and wavenumber $k_z + k_w$ as the modulating pondermotive wave. The degree of density-bunching depends on the amplitude of the wave and the interaction length L. In the nonlinear limit the counter propagating (in the beam reference frame) velocity modulated electrons may over-bunch namely cross over, and debunch again.

Bunching is the principle of classical stimulated emission in electron beam radiation devices. If the e-beam had been prebunched in the first place, we would have injected it at a decelerating phase relative to the wave and obtained net radiation gain right away (super radiant emission). This is indeed the principle behind the 'Optical-Klystron' (OK) demonstrated in Figure 7b. The structure of the OK is described ahead in Figure 19. The electron beam is velocity (energy) modulated by an input electromagnetic radiation wave in the first 'bunching-wiggler section' of length L_b. It then passes through a drift-free 'energy-dispersive magnet section' (chicane) of length L_d, in which the velocity modulation turns into density bunching. The bunched electron beam is then injected back into a second 'radiating-wiggler section', where it co-propagates with the same electromagnetic wave but with a phase advance of $\pi/2 - m2\pi$, $m = 1, 2, \ldots$ (spatial lag of $\lambda_{pm}/4 - m\lambda_{pm}$ in real space) which places the entire bunch at a decelerating phase relative to the PM-wave and so amplifies the radiation wave.

The principle of stimulated-emission gain in FEL, illustrated in Figure 7c, is quite similar. Here the wiggler is uniform along the entire length L, and the displacement of the electron bunches into a decelerating phase position relative to the PM-wave is obtained by injecting the electron beam at a velocity v_{z0}, slightly higher than the wave v_{ph} (velocity detuning). The detailed calculation shows that detuning corresponding to a phase shift of $\Delta\Psi(L) = [(\omega/v_{z0}) - (k_z + k_w)]L = -2.6$ (corresponding to spatial bunch advance of $0.4\lambda_{pm}$ along the wiggler length), provides sufficient synchronism with the PM-wave in the first half of the wiggler to obtain bunching, and sufficient deceleration-phasing of the created bunches in the second part of the wiggler to obtain maximum gain.

Principles of FEL Theory

The 3D radiation field in the interaction region can be expanded in general in terms of a complete set of free-space or waveguide modes $\{\varepsilon_q(x,y)\mathcal{H}_q(x,y)\}$:

$$E(r,t) = \mathrm{Re}\Big[\sum_q c_q(z)\varepsilon_q(x,y)\mathrm{e}^{\mathrm{i}(k_{zq}z-\omega t)}\Big] \qquad [30]$$

The mode amplitudes $C_q(z)$ may grow along the wiggler interaction length $0 < z < L$, according to the mode excitation equation:

$$\frac{\mathrm{d}}{\mathrm{d}z}C_q(z) = -\frac{1}{4\mathcal{P}}\mathrm{e}^{-\mathrm{i}k_{zq}}\iint \mathrm{J}(x,y,z)\cdot\varepsilon_q^*(x,y)\,\mathrm{d}x\,\mathrm{d}y \qquad [31]$$

where $\mathcal{P} = -\frac{1}{2}\mathrm{Re}\int\int \varepsilon_q \times \mathcal{H}_q \cdot \hat{e}_z\,\mathrm{d}x\,\mathrm{d}y$ is the mode normalization power, and $\tilde{\mathrm{J}}$ is the bunching current component at frequency ω, that is phase matched to the radiation waves, and needs to be calculated consistently from the electron force equations.

The FEL Small Signal Regime

We first present the basic formulation of FEL gain in the linear (small signal) regime, namely the amplified radiation field is assumed to be proportional to the input signal radiation field, and the beam energy loss is negligible. This is done in the framework of a one-dimensional (single transverse radiation mode) model.

The electron beam charge density, current density, and velocity modulation are solved in the framework of a one-dimensional plasma equations model (kinetic or fluid equations). The longitudinal PM-force in eqn [27] modulates the electron beam velocity via the longitudinal part of the force eqn [25]. This brings about charge modulation $\rho(z,t) = \mathrm{Re}[\tilde{\rho}(k_z + k_\mathrm{w},\omega)\mathrm{e}^{\mathrm{i}(k_z+k_\mathrm{w})z-\mathrm{i}\omega t}]$ and consequently, also longitudinal space-charge field $\tilde{E}_\mathrm{sc}(k_{zq}+k_\mathrm{w},\omega)$ and longitudinal current density modulation $\tilde{J}_z(k_z+k_\mathrm{w},\omega)$, related through the Poison and continuity equations:

$$\mathrm{i}(k_z + k_\mathrm{w})\tilde{E}_\mathrm{sc}(k_z + k_\mathrm{w},\omega) = \tilde{\rho}(k_z + k_\mathrm{w},\omega)/\varepsilon \qquad [32]$$

$$(k_z + k_\mathrm{w})\tilde{J}_z(k_z + k_\mathrm{w},\omega) = \omega\tilde{\rho}(k_z + k_\mathrm{w},\omega) \qquad [33]$$

Solving the force eqn [25] for a general longitudinal force $F_z(z,t) = \mathrm{Re}[\tilde{F}_z(k_z,\omega)\mathrm{e}^{\mathrm{i}(k_z z-\omega t)}]$ results in a linear longitudinal current response relation:

$$\tilde{J}_z(k_z,\omega) = -\mathrm{i}\omega\chi_\mathrm{p}(k_z,\omega)\tilde{F}_z(k_z,\omega)/(-e) \qquad [34]$$

where $\chi_\mathrm{p}(k_z,\omega)$ is the longitudinal susceptibility of the electron beam 'plasma'.The beam charge density in the FEL may be quite high, and consequently the space charge field $\tilde{E}_\mathrm{sc}$, arising from the Poison eqn [32], may not be negligible. One should take into consideration then that the total longitudinal force $\tilde{F}_z$ is composed of both the PM-force of eqn [27] and an arising longitudinal space-charge electric force $-e\tilde{E}_\mathrm{sc}$. Thus, one should substitute in eqn [34]:

$$\tilde{F}_z(k_z + k_\mathrm{w},\omega) = -e[\tilde{E}_\mathrm{pm}(k_z + k_\mathrm{w},\omega) + \tilde{E}_\mathrm{sc}(k_z + k_\mathrm{w},\omega)] \qquad [35]$$

and solve it self-consistently with eqns [32] and [33] to obtain the 'external-force' response relation:

$$\tilde{J}_z(k_z + k_\mathrm{w},\omega) = \frac{-\mathrm{i}\omega\chi_\mathrm{p}(k_z + k_\mathrm{w},\omega)}{1 + \chi_\mathrm{p}(k_z + k_\mathrm{w},\omega)/\varepsilon}\tilde{E}_\mathrm{pm}(k_z + k_\mathrm{w},\omega) \qquad [36]$$

where we defined the PM 'field': $\tilde{E}_\mathrm{pm} = \tilde{F}_\mathrm{pm}/(-e)$.

In the framework of a single-mode interaction model, we keep in the summation of eqn [30] only one mode q (usually the fundamental mode, and in free space – a Gaussian mode). The transverse current density components in eqn [31] $\tilde{J}_\perp = \frac{1}{2}\tilde{\rho}\,\tilde{v}_w$ are found using eqns [22], [33], and [36]. Finally, substituting $C_q(z) = \tilde{C}_q\,\mathrm{e}^{\mathrm{i}\delta kz}$ (where $\delta k \equiv k_z - k_{qz}$ and $k_z \cong k_{qz}$ is the wavenumber of the radiation wave modified by the interaction with the electrons) results in the general FEL dispersion relation:

$$(k_z - k_{zq})[1 + \chi_\mathrm{p}(k_z + k_\mathrm{w},\omega)/\varepsilon] = \kappa\chi_\mathrm{p}(k_z + k_\mathrm{w},\omega)/\varepsilon_0 \qquad [37]$$

Equation [37] is a general expression, valid for a wide variety of FELs, including Cerenkov–Smith–Purcell and TWT. They differ only in the expression for κ. For the conventional (magnetic wiggler) FEL:

$$\kappa = \frac{1}{4}\frac{A_\mathrm{e}}{A_\mathrm{em}}\frac{a_\mathrm{w}^2}{\gamma^2\beta_z^2}\frac{\omega}{c}A_\mathrm{JJ}^2 \qquad [38]$$

where A_e is the cross-section area of the electron beam, and $A_\mathrm{em} \equiv \mathcal{P}_q/[\frac{1}{2}\sqrt{\varepsilon_0/\mu_0}|\varepsilon_{q\perp}(0,0)|^2]$ is the effective area of the interacting radiation-mode q, and it is assumed that the electron beam, passing on axis $(x_\mathrm{e}, y_\mathrm{e}) = (0,0)$, is narrow relative to the transverse mode variation $A_\mathrm{e}/A_\mathrm{em} \ll 1$. The 'Bessel-functions coefficient' A_JJ is defined for a linear wiggler only, and is given by:

$$A_\mathrm{JJ} = J_0\left[\frac{a_\mathrm{w}^2}{2(a_\mathrm{w}^2+2)}\right] - J_1\left[\frac{a_\mathrm{w}^2}{2(a_\mathrm{w}^2+2)}\right] \qquad [39]$$

In a helical wiggler, $A_\mathrm{JJ} \equiv 1$. Usually $a_\mathrm{w} \ll 1$, and therefore $A_\mathrm{JJ} \cong 1$.

The Pierce Dispersion Equation

The longitudinal plasma response susceptibility function $\chi_\mathrm{p}(k_z,\omega)$ has been calculated, in any plasma formulation, including fluid model, kinetic model, or even quantum-mechanical theory. If the electron beam axial velocity spread is small enough (cold beam), then the fluid plasma equations can be used. The small signal longitudinal force equation derived from eqn [25], together with eqn [33] and the small signal current modulation expression:

$$\tilde{J}_z \cong \rho_0 \tilde{v}_z + v_z \tilde{\rho} \qquad [40]$$

result in:

$$\chi_p(k_z, \omega) = -\frac{\omega_p'^2}{(\omega - k_z v_z)^2}\varepsilon \qquad [41]$$

where $\omega_p' = (e^2 n_0/\gamma\gamma_z^2 \varepsilon m)^{1/2}$ is the longitudinal plasma frequency, n_0 is the beam electrons density ($\rho_0 = -en_0$), v_z is the average axial velocity of the beam.

In this 'cold-beam' limit, the FEL dispersion eqn [37] reduces into the well-known 'cubic dispersion equation' derived first by John Pierce in the late 1940s for the TWT:

$$\delta k(\delta k - \theta - \theta_{pr})(\delta k - \theta + \theta_{pr}) = Q \qquad [42]$$

where $\delta k = k_z - k_{zq}$, θ is the detuning parameter (off the synchronism condition of eqn [24]):

$$\theta \equiv \frac{\omega}{v_z} - k_{zq} - k_w \qquad [43]$$

$$\theta_p = \frac{\omega_p}{v_z} \qquad [44]$$

$$Q = \kappa\theta_p^2 \qquad [45]$$

Here $\theta_{pr} = r_p\theta_p$, where $r_p < 1$ is the plasma reduction factor. It results from the reduction of the longitudinal space-charge field $\tilde{E}_{sp}$ in a beam of finite radius r_b due to the fringe field effect ($r_p \to 1$ when the beam is wide relative to the longitudinal modulation wavelength: $r_b \gg \lambda_{pm} = 2\pi/(k_{zq} + k_w)$).

The cubic equation has, of course, three solutions δk_i ($i = 1, 2, 3$), and the general solution for the radiation field amplitude and power is thus:

$$C_q(z) = \sum_{j=1}^{3} A_j\, e^{i\delta k_j z} \qquad [46]$$

$$P(z) = |C_q(z)|^2 \mathcal{P}_q \qquad [47]$$

The coefficients A_i can be determined from three initial conditions of the radiation and e-beam parameters $C_q(0)$, $\tilde{v}(0)$, $\tilde{i}(0)$, and can be given as a linear combination of them (here $\tilde{i} = A_e\tilde{J}_z$ is the longitudinal modulation current):

$$A_j = A_j^E(\omega)C_q^{\omega}(0) + A_j^v(\omega)\tilde{v}^{\omega}(0) + A_j^i(\omega)\tilde{i}^{\omega}(0) \qquad [48]$$

Alternatively stated, the exit amplitude of the electromagnetic mode can in general be expressed in terms of the initial conditions:

$$C_q(L) = H^E(\omega)C_q(\omega, 0) + H^v(\omega)\tilde{v}_q(\omega, 0) + H^i(\omega)\tilde{i}(\omega, 0) \qquad [49]$$

where

$$H^{(E,v,i)}(\omega) = \sum_{j=1}^{3} A_j^{(E,v,i)}(\omega)e^{i\delta k_j L} \qquad [50]$$

In the conventional FEL, electrons are injected in randomly, and there is no velocity prebunching ($\tilde{v}(\omega, 0) = 0$) or current prebunching ($\tilde{i}(\omega, 0) = 0$) (or equivalently $\tilde{n}(\omega, 0) = 0$). Consequently, $C_q(z)$ is proportional to $C_q(0)$ and one can define and calculate the FEL small-signal single-path gain parameter:

$$G(\omega) \equiv \frac{P(L)}{P(0)} = \frac{|C_q(\omega, L)|^2}{|C_q(\omega, 0)|^2} = |H^E(\omega)|^2 \qquad [51]$$

The FEL Gain Regimes

At different physically meaningful operating regimes, some parameters in eqn [42] can be neglected relative to others, and simple analytic expressions can be found for δk_i, A_i, and consequently $G(\omega)$. It is convenient to normalize the FEL parameters to the wiggler length: $\bar{\theta} = \theta L$, $\bar{\theta}_{pr} = \theta_{pr}L$, $\bar{Q} = QL^3$. An additional figure of merit parameter is the 'thermal' spread parameter:

$$\bar{\theta}_{th} = \frac{v_{zth}}{v_z}\frac{\omega}{v_z}L \qquad [52]$$

where v_{zth} is the axial velocity spread of the e-beam (in a Gaussian velocity distribution model: $f(v_z) = \exp[(v_z - v_{z0})/v_{zth}]/\sqrt{\pi}v_{zth}$). The axial velocity spread can result out of beam energy spread or angular spread (finite 'emittance'). It should be small enough, so that the general dispersion relation of eqn [37] reduces to eqn [42] (the practical 'cold beam' regime).

Assuming now a conventional FEL ($\tilde{v}_z(0) = 0$, $\tilde{i}(0) = 0$), the single path gain in eqn [51] can be calculated. We present next this gain expression in the different regimes. The maximum values of the gain expression in the different regimes are listed in Table 1.

Low gain

This is the regime where the differential gain in a single path satisfies $G - 1 = [P(L) - P(0)]/P(0) \ll 1$. It is not useful for FEL amplifiers but most FEL oscillators operate in this regime.

Table 1 The gain regimes maximum gain expressions

	Gain regime	*Parameters domain*	*Max. gain expression*
I	Tenuous beam low-gain	$\bar{Q}, \bar{\theta}_{\mathrm{pr}}, \bar{\theta}_{\mathrm{th}} < \pi$	$\frac{P(L)}{P(0)} = 1 + 0.27\bar{Q}$
II	Collective low-gain	$\bar{\theta}_{\mathrm{pr}} > \frac{\bar{Q}}{2}, \bar{\theta}_{\mathrm{th}}, \pi$	$\frac{P(L)}{P(0)} = 1 + \bar{Q}/2\bar{\theta}_{\mathrm{pr}}$
III	Collective high-gain	$\bar{Q}/2 > \bar{\theta}_{\mathrm{pr}} > \bar{Q}^{1/3}, \bar{\theta}_{\mathrm{th}}, \bar{Q} > \pi$	$\frac{P(L)}{P(0)} = \frac{1}{4}\exp(\sqrt{2\bar{Q}/\bar{\theta}_{\mathrm{pr}}})$
IV	Strong coupling high-gain	$\bar{Q}^{1/3} > \bar{\theta}_{\mathrm{pr}}, \bar{\theta}_{\mathrm{th}}, \bar{Q} > \pi$	$\frac{P(L)}{P(0)} = \frac{1}{9}\exp(\sqrt{3}\bar{Q}^{1/3})$
V	Warm beam	$\bar{\theta}_{\mathrm{th}} > \bar{\theta}_{\mathrm{pr}}, \bar{Q}^{1/3}, \pi$	$\frac{P(L)}{P(0)} = \exp(3\bar{Q}/\bar{\theta}_{\mathrm{th}}^2)$



Figure 8 The low-gain cold-beam small-signal gain curve of FEL as a function of the detuning parameter $\bar{\theta}(\omega)$.

The three solutions of eqn [42] – namely the terms of eqn [46] – are reminiscent of the three eigenwaves of the uncoupled system ($\kappa = Q = 0$) : the radiation mode and the two plasma (space-charge) waves of the e-beam (the slow and fast waves, corresponding respectively to the forward and backward propagating plasma-waves in the beam rest reference-frame). In the low-gain regime, all three terms in eqn [46] are significant. Calculating them to first order in κ, results in analytical gain expressions in the collective ($\bar{\theta}_{\mathrm{pr}} \gg \pi$) and tenuous-beam ($\bar{\theta}_{\mathrm{pr}} \ll \pi$) regimes (note that $\bar{\theta}_{\mathrm{pr}}/2\pi = f'_{\mathrm{pr}}L/v_z$ is the number of plasma oscillations within the wiggler transit time L/v_z).

In most practical situations the beam current density is small enough, and its energy high enough, to limit operation to the tenuous-beam regime. The gain curve function is then:

$$G(\omega) - 1 = \bar{Q}F(\bar{\theta}(\omega)) = \bar{Q}\frac{\mathrm{d}}{\mathrm{d}\bar{\theta}}\operatorname{sinc}^2(\bar{\theta}/2) \qquad [53]$$

$$\bar{\theta}(\omega) \equiv \theta(\omega)L = 2\pi\frac{\omega - \omega_0}{\Delta\omega_L} \qquad [54]$$

where $\operatorname{sinc}(u) \equiv (\sin u)/u$, and in free space (no waveguide) propagation ($k_{zq} = \omega/c$), the FWHM frequency bandwidth of the $\operatorname{sinc}^2(\bar{\theta}/2)$ function is:

$$\frac{\Delta\omega_L}{\omega_0} = \frac{1}{N_{\mathrm{w}}} \qquad [55]$$

The small signal gain curve is shown in Figure 8. There is no gain at synchronism – $\omega = \omega_0$. Maximum gain – $G - 1 = 0.27\bar{Q}$, is attained at a frequency slightly smaller than ω_0, corresponding to $\bar{\theta} = -2.6$. The small gain curve bandwidth is $\Delta\omega_{\mathrm{SG}} \cong \Delta\omega_L/2$, namely:

$$\frac{\Delta\omega_{\mathrm{SG}}}{\omega_0} = \frac{1}{2N_{\mathrm{w}}} \qquad [56]$$

High gain

This is the regime where the FEL gain in a single path satisfies $G = P(L)/P(0) \gg 1$. It is useful, of course, when the FEL is used as an amplifier.

Since the coefficients of the cubic eqn [42] are all real, the solutions δk_i ($i = 1, 2, 3$) must be either all real, or composed of one real solution δk_3 and two complex solutions, which are complex conjugate of each other: $\delta k_1 = \delta k_2^*$. In the first case, all terms in eqn [46] are purely oscillatory, there is no exponential growth, and the FEL operates in the low gain regime. In the second case, assuming $\mathrm{Im}(\delta k_1) < 0$, $\mathrm{Im}(\delta k_2) > 0$, the first term grows exponentially, and if L is long enough it will dominate over the other decaying ($j = 2$) and oscillatory ($j = 3$) terms, and result in an exponential gain expression:

$$G(\omega) = \left(\frac{A_1}{A_1 + A_2 + A_3} \right)^2 \mathrm{e}^{2(\mathrm{Im}\ \delta k_1)L} \qquad [57]$$

If we focus on the tenuous-beam strong coupling (high–gain) regime $\theta_{\mathrm{pr}} \ll |\delta k|$, then the cubic eqn [42] gets the simple form:

$$\delta k[(\delta k)^2 - \theta^2] = \Gamma^3 \qquad [58]$$

where

$$\Gamma = Q^{1/3} = \left(\pi \frac{a_{\mathrm{w}}^2}{\gamma^3 \gamma_z^2 \beta_z^5} \frac{\omega/c}{A_{\mathrm{em}}} \frac{I_{\mathrm{b}}}{I_{\mathrm{A}}} A_{\mathrm{JJ}}^2 \right)^{1/3} \qquad [59]$$

and $I_{\mathrm{A}} = 4\pi\varepsilon_0 m_{\mathrm{e}} c^3/e \cong 17$ kA is the Alfven current. The solution of eqn [58] near synchronism ($\theta \cong 0$) is:

$$\delta k_1 = \frac{1 - \sqrt{3}\mathrm{i}}{2}\Gamma, \qquad \delta k_2 = \frac{1 + \sqrt{3}\mathrm{i}}{2}\Gamma, \qquad \delta k_3 = -\Gamma \qquad [60]$$

resulting in:

$$\begin{aligned} H^{\mathrm{E}}(\omega) &= \frac{C_q(z)}{C_q(0)} \\ &= \frac{1}{3}\left[\mathrm{e}^{\frac{\sqrt{3}+\mathrm{i}}{2}\Gamma z} + \mathrm{e}^{\frac{-\sqrt{3}+\mathrm{i}}{2}\Gamma z} + \mathrm{e}^{-\mathrm{i}\Gamma z} \right] \end{aligned} \qquad [61]$$

and for $\Gamma L \gg 1$:

$$G \cong \frac{1}{9}\mathrm{e}^{\sqrt{3}\Gamma L} \qquad [62]$$

The FEL gain is then exponential and can be very high. The gain exponential coefficient is characterized then by its third-order root scaling with the current, $\alpha I_{\mathrm{b}}^{1/3}$. The high-gain frequency detuning curve (found by solving eqn [58] to second order in θ) is:

$$\begin{aligned} G &\cong \frac{1}{9}\mathrm{e}^{\sqrt{3}\Gamma L} \exp(-\theta^2/\Gamma L 3^{3/2}) \\ &\equiv \frac{1}{9}\mathrm{e}^{\sqrt{3}\Gamma L} \exp\left[-\frac{(\omega - \omega_0)^2}{\Delta\omega_{\mathrm{HG}}^2} \right] \end{aligned} \qquad [63]$$

where $\Delta\omega_{\mathrm{HG}}$ is the 1/e half-width of the gain curve:

$$\frac{\Delta\omega_{\mathrm{HG}}}{\omega_0} = \frac{3^{3/4}}{2\pi} \frac{\lambda_{\mathrm{w}}}{(L/\Gamma)^{1/2}} \qquad [64]$$

Super-Radiance, Spontaneous-Emission and Self Amplified Spontaneous Emission (SASE)

Intense coherent radiation power can be generated in a wiggler or any other radiation scheme without any input radiation signal ($C_q(\omega, 0) = 0$) if the electron beam velocity or current (density) are prebunched. Namely, the injected e-beam has a frequency component $\tilde{v}(\omega)$ or $\tilde{i}(\omega)$ in the frequency range where the radiation device emits. In the case of pure density bunching ($\tilde{v}(\omega) = 0$), the coherent power emitted is found from eqns [46, 47, 49]:

$$(P_q)_{\mathrm{SR}} = P_q |H^i(\omega)|^2 |\tilde{i}(\omega, 0)|^2 \qquad [65]$$

A 'prebunched-beam FEL' emits coherent radiation based on the process of Super-radiant Emission (in the sense of Dike). Because all electrons emit in phase radiation wavepackets into the radiation mode, the resultant field amplitude is proportional in this case to the beam current I_{b} and the radiation. By contrast, spontaneous emission from a random electron beam (no bunching) is the result of incoherent superposition of the wavepackets emitted by the electrons and its power is expected to be proportional to the current I_{b}.

When the current to radiation field transfer function $H^i(\omega)$ is known, eqn [65] can be used to calculate the superradiant power, and in the high-gain regime also the amplified-superradiant power. The latter is the amplification of the superradiant radiation in the downstream sections of a long wiggler. Such unsaturated gain is possible only when the beam is partly bunched $\tilde{i}(\omega)(I_{\mathrm{b}})$ (because the FEL gain process requires enhanced bunching).

The expressions for the current to field transfer function, in the superradiant gain and the high-gain amplified superradiance limits respectively, are:

$$|H^i(\omega)| = \frac{(P_{\mathrm{pb}}/P_q)^{1/2}}{I_{\mathrm{b}}} \mathrm{sinc}(\theta L/2) \qquad [66]$$

$$\left|H^i(\omega)\right| = \frac{(P_{\mathrm{pb}}/P_q)^{1/2}}{3\Gamma L I_{\mathrm{b}}} \mathrm{e}^{(\sqrt{3}/2)\Gamma L}\ \mathrm{e}^{-(\omega-\omega_0)^2/2(\Delta\omega)_{\mathrm{HG}}^2} \qquad [67]$$

where

$$P_{\mathrm{pb}} = \frac{I_{\mathrm{b}}^2 Z_q}{32} \left(\frac{a_{\mathrm{w}}}{\gamma \beta_z} \right)^2 \frac{L^2}{A_{\mathrm{em}}} \qquad [68]$$

Z_q is the radiation mode impedance (in free-space $Z_q = \sqrt{\mu_0/\varepsilon_0}$). From these expressions one can calculate the power and spectral power of both coherent (superradiant) and partially coherent (spontaneous emission) radiation of FEL in the negligible gain and high gain regimes. The corresponding super-radiant power is in the negligible superradiance gain limit:

$$P_{\mathrm{SR}} = P_{\mathrm{pb}} \left| \frac{\tilde{i}(\omega)}{I_{\mathrm{b}}} \right|^2 \mathrm{sinc}^2(\theta L/2) \qquad [69]$$

(proportional, as expected, to the modulation current squared) and in the high-gain amplified superradiance limit (assuming initial partial bunching $|i(\omega)/I\mathrm{b}| \ll 1$):

$$P_{\mathrm{SR}} = P_{\mathrm{pb}}\left|\frac{\tilde{i}(\omega)}{I_{\mathrm{b}}}\right|^2 \frac{1}{9(\Gamma L)^2}\, \mathrm{e}^{\sqrt{3}\Gamma L}\, \mathrm{e}^{-(\omega-\omega_0)^2/(\Delta\omega)^2_{\mathrm{HG}}} \qquad [70]$$

The discussion is now extended to incoherent (or partially coherent) spontaneous emission. Due to its particulate nature, every electron beam has random frequency components in the entire spectrum (shot noise). Consequently, incoherent radiation power is always emitted from an electron-beam passing through a wiggler, and its spectral-power can be calculated through the relation:

$$\frac{\mathrm{d}P_q}{\mathrm{d}\omega} = \frac{2}{\pi}\mathcal{P}_q |H^i(\omega)|^2 \frac{\langle|\tilde{i}(\omega)|^2\rangle}{T} \qquad [71]$$

Here $\tilde{i}(\omega)$ is the Fourier transform of the current of randomly injected electrons $i(t) = -e\sum_{j=1}^{N_T} \delta(t - t_{oj})$, where N_T is the average number of electrons in a time period T, namely, the average (DC) current is $I_{\mathrm{b}} = -eN_T/T$. For a randomly distributed beam, the shot noise current is simply $\langle|i(\omega)|^2\rangle/T = eI_{\mathrm{b}}$, and therefore the spontaneous emission power of the FEL, which is nothing but the 'synchrotron-undulator radiation', is given by (see eqn [66]):

$$\frac{\mathrm{d}P_q}{\mathrm{d}\omega} = \frac{1}{16\pi} eI_{\mathrm{b}} Z_q \frac{L^2}{A_{\mathrm{em}}}\left(\frac{a_{\mathrm{w}}}{\gamma\beta_z}\right)^2 \mathrm{sinc}^2(\theta L/2) \qquad [72]$$

If the wiggler is long enough, the spontaneous emission emitted in the first part of the wiggler can be amplified by the rest of it (SASE). In the high-gain limit (see eqn [67]), the amplified spontaneous emission power within the gain bandwidth of eqn [64] is given by:

$$P_q = \frac{2}{\pi}\mathcal{P}_q eI_{\mathrm{b}} \int_0^\infty |H^i(\omega)|^2 \mathrm{d}\omega = \frac{1}{9} P_{\mathrm{sh}}\, \mathrm{e}^{\sqrt{3}\Gamma L} \qquad [73]$$

where P_{sh} is an 'effective shot-noise input power':

$$P_{\mathrm{sh}} = \frac{2}{\sqrt{\pi}} \frac{eP_{\mathrm{pb}}}{I_0(\Gamma L)^2}(\Delta\omega)_{\mathrm{HG}} \qquad [74]$$

Saturation Regime

The FEL interaction of an electron with an harmonic electromagnetic (EM) wave is essentially described by the longitudinal component of the force in eqn [25], driven by the pondermotive force of eqns [27] and [28]:

$$\frac{\mathrm{d}}{\mathrm{d}t}(\gamma_i m v_{zi}) = |\tilde{F}_{\mathrm{pm}}| \cos[\omega t - (k_z + k_{\mathrm{w}})z_i] \qquad [75]$$

$$\mathrm{d}z_i/\mathrm{d}t = v_{zi} \qquad [76]$$

As long as the interaction is weak enough (small signal regime), the change in the electron velocity is negligible – $v_{zi} \cong v_{z0}$, and the phase of the force-wave, experienced by the electron, is linear in time $\Psi_i(t) = [\omega - (k_z + k_{\mathrm{w}})v_{z0}](t - t_{0i}) + \omega t_{0i}$. Near synchronism condition $\theta \cong 0$ (eqn [24]), eqn [75] results in bunching of the beam, because different acceleration/deceleration forces are applied on each electron, depending on their initial phase $\Psi_i(0) = \omega t_{0i}(-\pi < \Psi_i(0) < \pi)$ within each optical period $2\pi/\omega$ (see Figure 7). Taylor expansion of v_{zi} around v_{z0} in eqns [75] and [76], and use of conservation of energy between the e-beam and the radiation field, would lead again to the small signal gain expression eqn [53] in the low gain regime.

When the interaction is strong enough (the nonlinear or saturation regime), the electron velocities change enough to invalidate the assumption of linear time dependence of Ψ_i and the nonlinear set of eqns [75] and [76] needs to be solved exactly.

It is convenient to invert the dependence on time $z_i(t) = \int_{t_{0i}}^{t} v_{zi}(t')\mathrm{d}t'$, and turn the coordinate z to the independent variable $t_i(z) = \int_0^z \mathrm{d}z'/v_{zi}(z') + t_{0i}$. This, and direct differentiation of $\gamma_i(v_{zi})$, reduces eqns [75] and [76] into the well-known pendulum equation:

$$\frac{\mathrm{d}\theta_i}{\mathrm{d}z} = K_{\mathrm{s}}^2 \sin\Psi_i \qquad [77]$$

$$\frac{\mathrm{d}\Psi_i}{\mathrm{d}z} = \theta_i \qquad [78]$$

where

$$\Psi_i = \int_0^z (\omega/v_{zi}(z') - k_z - k_{\mathrm{w}})\,\mathrm{d}z' \qquad [79]$$

$$\theta_i = \frac{\omega}{v_{zi}} - k_z - k_{\mathrm{w}} \qquad [80]$$

are respectively the pondermotive potential phase and the detuning value of electron i at position z.

$$K_{\mathrm{s}} = \frac{k\sqrt{a_{\mathrm{w}} a_{\mathrm{s}} A_{\mathrm{JJ}}}}{\gamma_0\gamma_{z0}\beta_{z0}^2} \qquad [81]$$

is the synchrotron oscillation wavenumber, where a_{w} is given in eqn [9], $a_{\mathrm{s}} = e|\tilde{E}|\omega/mc$, and $\gamma_0 = \gamma(0)$, $\gamma_{z0} = \gamma_z(0)$, and $\beta_{z0} = \beta_z(0)$ are the initial parameters of the assumed cold beam.

The pendulum eqns [77] and [78] can be integrated once, resulting in:

$$\tfrac{1}{2}\theta_i^2(z) - K_{\mathrm{s}}^2 \cos\Psi_i(z) = C_i \qquad [82]$$

and the integration constant is determined for each electron by its detuning and phase relative to the pondermotive wave at the entrance point ($z = 0$): $C_i = \frac{1}{2}\theta_i^2(0) - K_s^2 \cos \Psi_i(0)$.

The $\theta(z)$, $\Psi(z)$ phase-space trajectories of eqn [82] are shown in Figure 9 for various values of C_i (corresponding to the initial conditions $\theta_i(0)$, $\Psi_i(0)$). The trajectories corresponding to $|C_i| > K_s^2$ are open; namely electrons on these trajectories, while oscillating, can slip-off out of the pondermotive–potential wave period to adjacent periods, ahead or backward, depending on the value of their detuning parameter $\bar{\theta}$. The trajectories corresponding to $|C_i| < K_s^2$ are closed, namely the electrons occupying these trajectories are 'trapped', and their phase displacement is bound to a range $|\Psi_i(z) - n\pi| < \Psi_{\mathrm{im}} \equiv \arccos(|C_i|/K_s^2) < \pi$ within one pondermotive-wave period. The trajectory $C_i = K_s^2$ defines the 'separatrix':

$$\theta_i(z) = \pm 2K_s \cos(\Psi_i/2) \qquad [83]$$

which is sometimes referred to as the 'trap' or 'bucket'. Every electron within the separatrix stays trapped, and the ones out of it are free (untrapped). The height of the separatrix (maximum detuning swing) is $\Delta\theta_{\mathrm{trap}} = 4K_s$. The oscillation frequency of the trapped electrons can be estimated for deeply trapped electrons ($\Psi_m \ll 2\pi$). In this case the physical pendulum eqns [77] and [78] reduce to the mathematical pendulum equation with an oscillation frequency K_s, in the z coordinate. This longitudinal oscillation, called 'synchrotron oscillation', takes place as a function of time at the 'synchrotron frequency' $\Omega_s = K_s v_z$.

Differentiation of $\theta_i(v_{zi})$ and $v_{zi}(\gamma_i)$ permits to describe the phase-space dynamics in terms of the more physical parameters $\delta v_{zi} = v_{zi} - v_{\mathrm{ph}}$ and $\delta\gamma_i = \gamma_i - \gamma_{\mathrm{ph}}$, where:



Figure 9 The (θ–Ψ) phase-space trajectories of the pendulum equation.

$$v_{\mathrm{ph}} = \frac{\omega}{k_z + k_w} \qquad [84]$$

is the phase velocity of the pondermotive wave and $\gamma_{\mathrm{ph}} \equiv (1 - \beta_{\mathrm{ph}}^2)^{-1/2}$:

$$-\theta_i = \frac{\omega}{c^2\beta_{z0}^2}\delta v_{zi} = \frac{k}{\beta_{z0}^3\gamma_{z0}^2\gamma_0}\delta\gamma_i \qquad [85]$$

Figure 10 displays a typical dynamics of electron beam phase-space (γ, Ψ) evolution for the case of a cold beam of energy $\gamma(0)$ entering the interaction region at $z = 0$ with uniform phase distribution (random arrival times t_{0i}). The FEL is assumed to operate in the low-gain regime (typical situation in an FEL oscillator), and, therefore, the trap height (corresponding to $\Delta\theta_{\mathrm{trap}} = 4k_s$):

$$\Delta\gamma_{\mathrm{trap}} = 8\beta_z^2\gamma_z^2\gamma K_s/k \qquad [86]$$

remains constant along the interaction length. Figure 10a displays the e-beam phase-space evolution in the small signal regime. The uniform phase distribution evolves along the wiggler into a bunched distribution (compare to Figure 7c), and its average kinetic energy goes down $(\Delta E_k) = [\langle\gamma_i(L)\rangle - \gamma(0)]mc^2 < 0$, contributing this energy to the field of the interacting radiation mode, $\Delta P_q = (\Delta E_k)I_0/e$. In this case (corresponding in an FEL oscillator to the early stages of oscillation build-up), the electrons remain free (untrapped) along the entire length L.

Figure 10b displays the e-beam phase-space evolution in the large signal (saturation) regime (in the case of an oscillator – at the steady-state saturation stage). Part of the electrons are found inside the trap, immediately upon entering the interaction region ($z = 0$), and they lose energy of less than (but near) $mc^2\Delta\gamma_{\mathrm{trap}}$ as they pass through the interaction region ($z = L$). A portion of the electrons remain outside the traps upon entrance. They follow open trajectories and lose less energy or may even become accelerated due to their interaction with the wave.

It can be appreciated from this discussion that a good design strategy in attempting to extract maximum power from the electron beam in the FEL interaction, is to set the parameters determining the synchrotron oscillation frequency K_s in eqn [81] so that only half a synchrotron oscillation period will be performed along the interaction length:

$$K_s L = \pi \qquad [87]$$

This is controlled in an amplifier by keeping the input radiation power $P_q(0)$ (and consequently a_s) small enough, so that K_s will not exceed the value set



Figure 10 'Snapshots' of the ($\gamma - \Psi$) phase-space distribution of an initially uniformly distributed cold beam relative to the PM-wave trap at three points along the wiggler (a) Moderate bunching in the small-signal low gain regime. (b) Dynamics of electron beam trapping and synchrotron oscillation at steady state saturation stage of a FEL oscillator ($K_s L = \pi$).

by eqn [87]. In an oscillator, this is controlled by increasing the output mirror transmission sufficiently, so that the single path incremental small signal gain G-1 will not be much larger than the round trip loss, and the FEL will not get into deep saturation. When the FEL is over-saturated ($K_s L > \pi$), the trapped electrons begin to gain energy as they continue to rotate in their phase-space trajectories beyond the lowest energy point of the trap, and the radiative energy extraction efficiency drops down.

A practical estimate for the FEL saturation power emission and radiation extraction efficiency can be derived from the following consideration: the electron beam departs from most of its energy during the interaction with the wave, if a significant fraction of the electrons are within the trap and have positive velocity δv_{zi} relative to the wave velocity v_{ph} at $z = 0$, and if at the end of the interaction length ($z = L$), they complete half a pendulum swing and reverse their velocity relative to the wave $\delta v_{zi}(L) \cong -\delta v_{zi}(0)$. Correspondingly, in the energy phase-space diagram (Figure 10b) the electrons perform half a synchrotron oscillation swing and $\delta\gamma_i(L) = \gamma_i(L) - \gamma_{ph} = -\delta\gamma_i(0)$. In order to include in this discussion also the FEL amplifier (in the high gain regime), we note that in this case the phase velocity of the wave v_{ph} in eqn [84], and correspondingly γ_{ph}, are modified by the interaction contribution to the radiation wavenumber – $k_z = k_{z0} + \mathrm{Re}(\delta k)$, and also the electron detuning parameter (relative to the pondermotive wave) θ_i in eqn [80] differs from the beam detuning parameter θ in eqn [43]: $\theta_i = \theta - \mathrm{Re}(\delta k)$. Based on these considerations and eqn [85], the maximum energy extraction from the beam in the saturation process is:

$$\Delta\gamma = 2\delta\gamma_i(0) = 2\beta_{z0}^3\gamma_{z0}^2\gamma_0\frac{\mathrm{Re}\,\delta k - \theta}{k} \qquad [88]$$

where θ is the initial detuning parameter in eqn [43].

In an FEL oscillator, operating in general in the low-gain regime, $|\mathrm{Re}\,\delta k| \ll |\theta|$, oscillation will start usually at the resonator mode frequency, corresponding to the detuning parameter $\theta(\omega) = -2.6/L$, for which the small signal gain is maximal (see Figure 8). Then the maximum radiation extraction efficiency can be estimated directly from eqn [88]. It is, in the highly relativistic limit ($\beta_{z0} \cong 1$):

$$\eta_{\mathrm{ext}} = \frac{\Delta\gamma}{\gamma_0} \cong \frac{1}{2N_{\mathrm{w}}} \qquad [89]$$

In an FEL amplifier, in the high-gain regime $\mathrm{Re}\,\delta k = \Gamma/2 \gg |\theta|$, and consequently in the same limit:

$$\eta_{\mathrm{ext}} \cong \frac{\Gamma\lambda_{\mathrm{w}}}{4\pi} \qquad [90]$$

It may be interpreted that the effective wiggler length for saturation is $L_{\mathrm{eff}} = 2\pi/\Gamma$.

Equation [90], derived here for a coherent wave, is considered valid also for estimating the saturation efficiency also in SASE-FEL. In this context, it is also called 'the efficiency parameter' $-\rho$.

FEL Radiation Schemes and Technologies

Contrary to conventional atomic and molecular lasers, the FEL operating frequency is not determined by natural discrete quantum energy levels of the lasing matter, but by the synchronism condition of eqn [24] that can be predetermined by the choice of wiggler period, $\lambda_w = 2\pi/k_w$, the resonator dispersion characteristics $k_{zq}(\omega)$, and the beam axial velocity v_z.

Because the FEL design parameters can be chosen at will, its operating frequency can fit any requirement, and furthermore, it can be tuned over a wide range (primarily by varying v_z). This feature of FEL led to FEL development efforts in regimes where it is hard to attain high-power tunable conventional lasers or vacuum-tube radiation sources – namely in the sub-mm (far infrared or THz) regimes, and in the VUV down to soft X-ray wavelengths.

In practice, in an attempt to develop short wavelength FELs, the choice of wiggler period λ_w is limited by an inevitable transverse decay of the magnetic field away from the wiggler magnets surface (a decay range of $\approx k_w^{-1}$) dictated by the Maxwell equations. To avoid interception of electron beam current on the walls or on the wiggler surfaces, typical wiggler periods are made longer than $\lambda_w > 1$ cm. FELs (or FEMs – free electron masers) operating in the long wavelengths regime (mm and sub-mm wavelengths) must be based on waveguide resonators to avoid excessive diffraction of the radiation beam along the interaction length (the wiggler). This determines the dispersion relation $k_{zq}(\omega) = (\omega^2 - \omega_{coq}^2)^{1/2}/c$ where ω_{coq} is the waveguide cutoff frequency of the radiation mode q. The use of this dispersion relation in eqn [24] results in an equation for the FEL synchronism frequency ω_0. Usually the fundamental mode in an overmoded waveguide is used (the waveguide is overmoded because it has to be wide enough to avoid interception of electron beam current). In this case ($\omega_0 \gg \omega_{co}$) and certainly in the case of an open resonator (common in FELs operating in the optical regime) $k_{zq} = \omega/c$, and the synchronism condition in eqn [24] simplified to the well-known FEL radiation wavelength expression in eqn [6]:

$$\lambda = (1 + \beta_z)\beta_z \gamma_z^2 \lambda_w \cong 2\gamma_z^2 \lambda_w \qquad [91]$$

where γ_z, a_w are defined in eqns [7]–[9].

To attain strong interaction, it is desirable to keep the wiggler parameter a_w large (eqn [38]), however, if $a_w > 1$, this will cause reduction in the operating wavelength according to eqns [7] and [91]. For this reason, and also in order to avoid harmonic frequencies emission (in case of a linear wiggler), $a_w < 1$ in common FEL design. Consequently, considering the practical limitations on λ_w, the operating wavelength eqn [91] is determined primarily by the beam relativistic Lorentz factor γ (eqn [8]).

The conclusion is that for a short wavelength FEL, one should use an electron beam accelerated to high kinetic energy E_k. Also, tuning of the FEL operating-wavelength can be done by changing the beam energy. Small-range frequency tuning can be done also by changing the spacing between the magnet poles of a linear wiggler. This varies the magnetic field experienced by the e-beam, and effects the radiation wavelength through change of a_w (see eqns [7] and [91]).

Figure 11 displays the operating wavelengths of FEL projects all over the world versus their e-beam energy. FELs were operated or planned to operate over a wide range of frequencies, from the microwave to X-ray – eight orders of magnitude. The data points fall on the theoretical FEL radiation curve eqns [7], [8], and [91].

FEL Accelerator Technologies

The kind of accelerator used is the most important factor in determining the FEL characteristics. Evidently, the higher the acceleration energy, the shorter is the FEL radiation wavelength. However, not only the acceleration beam energy determines the shortest operating wavelength of the FEL, but also the e-beam quality. If the accelerated beam has large energy spread, energy instability, or large emittance (the product of the beamwidth with its angular spread), then it may have large axial velocity spread v_{zth}. At high frequencies, this may push the detuning spread parameter $\bar{\theta}_{th}$ (eqn [52]) to the warm beam regime (see Table 1), in which the FEL gain is diminished, and FELs are usually not operated.

Other parameters of the accelerator determine different characteristics of the FEL. High current in the electron beam enables higher gain and higher power operation. The e-beam pulse shape (or CW) characteristics, affect, of course, the emitted radiation waveform, and may also affect the FEL gain and saturation characteristics. The following are the main accelerator technologies used for FEL construction. Their wavelength operating-regimes (eqn [91]) (determined primarily by their beam acceleration energies), are displayed in Figure 12.

Modulators and pulse-line accelerators

These are usually single pulse accelerators, based on high voltage power supplies and fast discharge stored



Figure 11 Operating wavelengths of FELs around the world vs. their accelerator beam energy. The data points correspond in ascending order of accelerator energy to the following experimental facilities: NRL (USA), IAP (Russia), KAERI (Korea), IAP (Russia), JINR/IAP (Russia), INP/IAP (Russia), TAU (Israel), FOM (Netherlands), KEK/JAERI (Japan/Korea), CESTA (France), ENEA (Italy), KAERI-FEL (Korea), LEENA (Japan), ENEA (Italy), FIR FEL (USA), mm Fel (USA), UCSB (USA), ILE/ILT (Japan), MIRFEL (USA), UCLA-Kurchatov (USA/Russia), FIREFLY (GB), JAERI-FEL (Japan), FELIX (Netherlands), RAFEL (USA), ISIR (Japan), UCLA-Kurchatov-LANL (USA/RU), ELSA (France), CLIO (France), SCAFEL (GB), FEL (Germany), BFEL (China), KHI-FEL (Japan), FELI4 (Japan), iFEL1 (Japan), HGHG (USA), FELI (USA), MARKIII (USA), ATF (USA), iFEL2 (Japan), VISA (USA), LEBRA (Japan), OK-4 (USA), UVFEL (USA), iFEL3 (Japan), TTF1 (Germany), NIJI-IV (Japan), APSFEL (USA), FELICITAI (Germany), FERMI (Italy), UVSOR (Japan), Super-ACO (France), TTF2 (Germany), ELETTRA (Italy), Soft X-ray (Germany), SPARX (Italy), LCLS (USA), TESLA (Germany). X, long wavelengths; $*$, short wavelengths; ○, planned short wavelengths SASE-FELs. Data based in part on H. P. Freund, V. L. Granatstein, Nucl. Inst. and Methods In Phys. Res. A249, 33 (1999), W. Colson, Proc. of the 24th Int. FEL conference, Argone, Ill. (ed. K. J. Kim, S. V. Milton, E. Gluskin). The data points fall close to the theoretical FEL radiation condition expression (91) drawn for two practical limits of wiggler parameters.

electric energy systems (e.g., Marx Generator), which produce short pulse (tens of nSec) Intense Relativistic Beam (IRB) of energy in the range of hundreds of keV to few MeV and high instantaneous current (order of kAmp), using explosive cathode (plasma field emission) electron guns. FELs (FEMs), based on such accelerators, operated mostly in the microwave and mm-wave regimes. Because of their poor beam quality and single pulse characteristic, these FELs were, in most cases, operated only as Self Amplified Spontaneous Emission (SASE) sources, producing intense radiation beams of low coherence at instantaneous power levels in the range of 1–100 MW. Because of the high e-beam current and low energy, these FEMs operated mostly in the collective high-gain regime (see Table 1).

Some of the early pioneering work on FEMs was done in the 1970s and 1980s in the US (NRL, Columbia Univ., MIT), Russia (IAP), and France (Echole Politechnique), based on this kind of accelerators.

Induction linacs

These too are single pulse (or low repetition rate) accelerators, based on induction of electromotive potential over an acceleration gap by means of an electric-transformer circuit. They can be cascaded to high energy, and produce short pulse (tens to hundreds



Figure 12 Approximate wavelength ranges accessible with FELs based on current accelerator and wiggler technologies.

of nSec), high current (up to 10 kA) electron beams, with relatively high energy (MeV to tens of MeV). The interest in FELs, based on this kind of accelerator technology, stemmed in the 1980s primarily from the SDI program, for the propose of development of a DEW FEL. The main development of this technology took place on a 50 MeV accelerator – ATA (for operating at 10 μm wavelength) and a 3.5 MeV accelerator – ETA (for operating at 8 mm wavelength). The latter experiment, operating in the high-gain regime, demonstrated record high power (1 GW) and energy extraction efficiency (35%).

Electrostatic accelerators

These accelerators are DC machines, in which an electron beam, generated by a thermionic electron-gun (typically 1–10 Amp) is accelerated electrostatically. The charging of the high voltage terminal can be done by mechanical charge transport (Van de Graaff) or electrodynamically (Crockford–Walton accelerator, Dynamitron). The first kind can be built at energies up to 25 MeV, and the charging current is less than mAmp. The second kind have terminal voltage less than 5 MeV, and the charging current can be hundreds of mAmps.

Because of their DC characteristics, FELs based on these kinds of accelerators can operate at arbitrary pulse shape structure and in principle – continuously (CW). However, because of the low charging current, the high electron beam current (1–10 Amp), required for FEL lasing must be transported without any interception along the entire way from the electron gun, through the acceleration tubes and the FEL wiggler, and then decelerated down to the voltage depressed beam-collector (multistage collector), closing the electric circuit back to the e-gun (current recirculation). The collector is situated at the e-gun potential, biased by moderate voltage high current power supplies, which deliver the current and power needed for circulating the e-beam and compensates for its kinetic energy loss in favor of the radiation field in the FEL cavity. This beam current recirculation is, therefore, also an 'Energy retrieval' scheme, and can make the overall energy transfer efficiency of the electrostatic-accelerator FEL very high.

In practice, high-beam transport efficiency in excess of 99.9% is needed for CW lasing, and has not been demonstrated yet. To avoid HV-terminal voltage drop during lasing, electrostatic-accelerator FELs are usually operated in a single pulse mode. Few FELs of this kind have been constructed. The first and main facility is the UCSB FEL shown in Figure 13. It operates in the wavelength range of 30 μm to 2.5 mm (with three switchable wigglers) in the framework of a dedicated radiation user facility. This FEL operates in the negatively charged terminal mode, in which the e-gun and collector are placed in the negatively charged HV-terminal inside the pressurized insulating gas tank, and the wigglers are situated externally at ground potential. An alternative operating mode of positively charged terminal internal cavity electrostatic-accelerator FEM was demonstrated in the Israeli Tandem–Accelerator FEM and the Dutch F.O.M. Fusion-FEM projects. This configuration enables operating with long pulse, high coherence, and very high average power. Linewidth of $\Delta\omega/\omega \cong 10^{-5}$ was demonstrated in the Israeli FEM and high power (730 kW over few microseconds) was demonstrated in the Dutch FEM, both at mm-wavelengths. The goal of the latter development project (which was not completed) was quasicontinuous operation at 1 MW average power for application in fusion plasma heating.

Radio-frequency (RF) accelerators

RF-accelerators are by far the most popular electron-beam sources for FELs. In RF accelerators, short electron beam bunches (bunch duration 1–10 pSec) are accelerated by the axial field of intense RF radiation (frequency about 1 GHz), which is applied in the acceleration cavities on the injected short e-beam bunches, entering with the accelerating-phase of the RF field. In microtrons, the electron bunches perform circular motion, and get incremental acceleration energy every time they re-enter the acceleration cavity. In RF-LINACs (linear accelerator), the electron bunches are accelerated in a sequence of RF cavities or a slow-wave structure, which keep an accelerating-phase synchronization of the traversing electron bunches with the RF field along a long linear acceleration length. The bunching of the electrons, prior to the acceleration step, is traditionally performed by bunching RF-cavities and a dispersive magnet (chicane) pulse compression system.

The FEL small signal gain, must be large enough to build-up the radiation field in the resonator from noise to saturation well within the macropulse duration.

RF-Linacs are essential facilities in synchrotron radiation centers, used to inject electron beam current into the synchrotron storage ring accelerator from time to time. Because of this reason, many FELs based on RF-LINACs were developed in synchrotron centers, and provide additional coherent radiation sources to the synchrotron radiation center users.

Figure 15 displays FELIX – a RF-LINAC FEL which is located in one of the most active FEL radiation user-centers in FOM – Holland.

Storage rings

Storage rings are circular accelerators in which a number of electron (or positron) beam bunches (typically of 50–500 pS pulse duration and hundreds of ampere peak current) are circulated continuously by means of a lattice of bending magnets and quadrupole lenses. Typical energies of storage ring accelerators are in the hundreds of MeV to GeVs range. As the electrons pass through the bending magnets, they lose a small amount of their energy due to emission of synchrotron radiation. This energy is replenished by a small RF acceleration cavity placed in one section of the ring. The electron beam bunch dimensions, energy spread, and emittance parameters are set in steady state by a balance between the electrons oscillations within the ring lattice and radiation damping due to the random synchrotron emission process. This produces high-quality (small emittance and energy spread) continuous train of electron beam bunches, that can be used to drive a FEL oscillator placed as an insertion device in one of the straight sections of the ring between two bending magnets.

Demonstrations of FEL oscillators, operating in a storage ring, were first reported by the French (LURE-Orsay) in 1987 (at visible wavelengths) and the Russians (VEPP-Novosibirsk) in 1988 (in the ultra-violet). The short wavelength operation of storage-ring FELs is facilitated by the high energy, low emittance and low energy spread parameters of the beam.

Since storage ring accelerators are at the heart of all synchrotron radiation centers, one could expect that FEL would be abundant in such facilities as insertion devices. There is, however, a problem of interference of the FEL operating as an insertion device in the normal operation of the ring itself. The energy spread increase, induced in the electron beam during the interaction in a saturated FEL oscillator, cannot be controlled by the synchrotron radiation damping process, if the FEL operating power is too high.



Figure 15 The FELIX RF-Linac FEL operating as a radiation users center in F.O.M. Netherlands. (Courtesy of L. van der Meer, F.O.M.)

This limits the FEL power to be kept as a fraction of the synchrotron radiation power dissipation all around the ring (the 'Renieri Limit'). The effect of the FEL on the e-beam quality, reduces the lifetime of the electrons in the storage ring, and so distrupts the normal operation of the ring in a synchrotron radiation user facility.

To avoid the interference problems, it is most desirable to operate FELs in a dedicated storage ring. This also provides the option to leave long enough straight sections in which long enough wigglers provide sufficient gain for FEL oscillation. Figure 16 displays the Duke storage ring FEL, which is used as a unique radiation user facility, providing intense coherent short wavelength radiation for applications in medicine, biology, material studies, etc.

Superconducting (SC) RF-LINACS

When the RF cavities of the accelerator are superconducting, there are very low RF power losses on the cavity walls, and it is possible to maintain continuous acceleration field in the RF accelerator with a moderate-power continuous RF source, which delivers all of its power to the electron beam kinetic energy. Combining the SC-RF-LINAC technology with an FEL oscillator, pioneered primarily by Stanford University and Thomas Jefferson Lab (TJL) in the US and JAERI Lab in Japan, gave rise to an important scheme of operating such a system in a current recirculating energy retrieval mode. This scheme revolutionized the development of FELs in the direction of high-power, high-efficiency operation, which is highly desirable, primarily for industrial applications (material processing, photochemical production, etc.).

In the recirculating SC-RF-LINAC FEL scheme the wasted beam emerging out of the wiggler after losing a fraction of only few percents (see eqn [89]) out of its kinetic energy, is not dumped into a beam-dump, as in normal cavity RF accelerators, but is re-injected, after circulation, into the SC-RF accelerator. The timing of the wasted electron bunches re-injection is such that they experience a deceleration phase along the entire length of the accelerating cavities. Usually, they are re-injected at the same cell with a fresh new electron bunch injected at an acceleration phase, and thus the accelerated fresh bunch receives its acceleration kinetic energy directly from the wasted beam bunch, that is at the same time decelerated. The decelerated wasted beam bunches are then dumped in the electron beam dump at much lower energy than without recirculation, at energies that are limited primarily just by the energy spread induced in the beam in the FEL laser-saturation process. This scheme, not only increases many folds the over-all energy transformation efficiency from wall-plug to radiation, but would solve significant heat dissipation and radioactivity activation problems in a high-power FEL design.

Figure 17 displays the TJL Infrared SC-RF-LINAC FEL oscillator, that demonstrated for the first time



Figure 16 The Duke – University Storage Ring FEL operating as a radiation-users center in N. Carolina, USA. (Mendening: Matthew Busch, courtesy of Glenn Edwards, Duke FEL Lab.)

record high average power levels – nearly 10 kWatt at optical frequencies (1–14 μm). The facility is in upgrade development stages towards eventual operation at 100 kWatt in the IR and 1 kWatt in the UV. It operates in the framework of a laser material processing consortium and demonstrates important material processing applications, such as high-rate micromachining of hard materials (ceramics) with picoSecond laser pulses.

The e-beam current recirculation scheme of SC-RF-LINAC FEL has a significant advantage over the e-beam recirculation in a storage ring. As in electrostatic accelerators, the electrons entering the wiggler are ‘fresh’ cold-beam electrons from the injector, and not a wasted beam corrupted by the laser saturation process in a previous circulation through the FEL. This also makes it possible to sustain high average circulating current despite the disruptive effect of the FEL on the e-beam. This technological development has given rise to a new concept for a radiation-user facility light-source 4GLS (fourth-generation light source), which is presently in a pilot project development stage at Daresbury Lab in the UK (see Figure 18). In such a scheme, IR and UV FEL oscillators and XUV SASE-FEL can be operated together with synchrotron magnet dipole and wiggler insertion devices without disruptive interference. Such a scheme, if further developed, can give rise to new radiation-user, light-source facilities, that can provide a wider range of radiation parameters than synchrotron centers of previous generation.


Optical system
IR wiggler
Injector
Linac
Beam transport
10 m

Figure 17 The Thomas Jefferson Lab. recirculating beam-current superconducting Linac FEL operating as a material processing FEL-user center in Virginia USA (Courtesy of S. Benson, Thomas Jefferson Laboratory).


Photoinjectors
High average current injector
Temporal mode injector
50 MeV SC LINAC
IR-FEL
Bunch expander
Bunch compressor
e⁻ Beam dump
Undulator structure
600 MeV superconducting LINAC
Final deceleration
Bending magnet radiation
XUV - FEL
VUV - FEL
Undulator radiation
Bending magnet radiation
Undulator radiation
Undulator radiation

Figure 18 The Daresbury Fourth Generation Light-Source concept (4GLS). The circulating beam-current superconducting Linac includes SASE-FEL, bending magnets and wigglers as insertion devices. (Courtesy of M. Poole, Damesbury Laboratory)

Magnetic Wiggler Schemes

The optical klystron

The stimulated emission process in FEL (see Figure 7c) is based on velocity (energy) bunching of the e-beam in the first part of the wiggler, which turns into density bunching along the central part of the wiggler, and then the density-bunched electron beam performs 'negative work' on the radiation wave and emits radiative energy in the last part of the wiggler. In the OK, these steps are carried out in three separate parts of the wiggler: the energy bunching wiggler section, the dispersive magnet density buncher, and the radiating wiggler section (see Figure 7b).

A schematic of the OK is shown in Figure 19. The chicane magnetic structure in the dispersive section brings all electrons emerging from the bunching wiggler back onto the axis of the radiating wiggler, but provides variable delay $\Delta t_{\mathrm{d}i} = \int_{L_\mathrm{b}}^{L_\mathrm{b}+L_\mathrm{d}} (v_{zi}^{-1} - v_{\mathrm{ph}}^{-1})\,\mathrm{d}z = [\mathrm{d}(\Delta t_\mathrm{d})/\mathrm{d}\gamma]\delta\gamma_i$ relative to the pondermotive wave phase to different electrons, which acquired different energy modulation increments $\delta\gamma_i = \gamma_i - \gamma_{\mathrm{ph}}$ in the final section. The radiation condition is satisfied whenever the bunch-center phase satisfies $\Delta\varphi_\mathrm{d} = \omega\Delta t_\mathrm{d} = \pi/2 - 2m\pi$ (see Figure 7b). However, because the energy dispersion coefficient $\mathrm{d}(\Delta t_\mathrm{d})/\mathrm{d}\gamma$, is much larger in the chicane than in a wiggler of the same length, the density bunching amplitude, and consequently the OK gain, are much larger than in a uniform wiggler FEL of the same length.

The OK was invented by Vinokurov and Skrinsky in 1977 and first demonstrated in 1987 at visible wavelengths in the ACO storage ring of LURE in Orsay, France, and subsequently in 1988 at UV wavelengths, in the VEPP storage ring in Novosibirsk, Russia. The OK is an optimal FEL configuration, if used as an insertion device in a storage ring, because it can provide sufficient gain to exceed the high lasing threshold at the short operating wavelengths of a high-energy storage-ring FEL, and still conform with the rather short straight sections available for insertion devices in conventional synchrotron storage rings. It should be noted that the OK is equivalent to a long wiggler FEL of length L_{eff} of equal gain and therefore its axial velocity spread acceptance is small (this is determined from the cold beam limit $\bar{\theta}_{\mathrm{th}} \ll \pi$ with L_{eff} used in eqn [52]). This too is consistent with storage ring accelerators, which are characterized by small energy spread and emittance of the electron beam.

Radiation emission at harmonic frequencies

In a linear wiggler (eqn [2]), the axial velocity:

$$\beta_z = [\beta^2 - (a_\mathrm{w}/\gamma)^2\cos^2 k_\mathrm{w}z]^{1/2} \qquad [92]$$

is not constant. It varies with spatial periodicity $\lambda_\mathrm{w}/2$, and in addition to its average value $\bar{\beta}_z = [\beta^2 - a_\mathrm{w}^2/2\gamma^2]^{1/2}$, contains Fourier components of spatial frequencies $2mk_\mathrm{w}$ $(m = 1, 2, \ldots)$. When $a_\mathrm{w} \gg 1$, the axial oscillation deforms the sinusoidal trajectory of the electrons in the wiggler (eqns [22] and [23]), and in a frame of reference moving at the average velocity $\bar{\beta}_z$, the electron trajectories in the wiggling $(x-z)$ plane forms an figure 8 shape, rather than a pure transverse linear motion. In the laboratory frame this leads to synchrotron undulator emission in the forward direction at all odd harmonic frequencies of ω_0, corresponding to substitution of $k_\mathrm{w} \rightarrow (2m+1)k_\mathrm{w}$ $(m = 1, 2, 3, \ldots)$ in eqn [6]:

$$\omega_{2m+1} = (2m+1)\omega_0 \cong 2\gamma_z^2 c(2m+1)k_\mathrm{w} \qquad [93]$$

All the stimulated emission gain expressions, presented earlier for the fundamental harmonic, are valid with appropriate substitution of

$$\theta_{2m+1} = \frac{\omega}{v_z} - k_z - (2m+1)k_\mathrm{w} \qquad [94]$$

instead of eqn [43], and substitution of the harmonic-weight Bessel-function coefficient of



Figure 19 Schematics of the Optical–Klystron, including an energy bunching wiggler, a dispersive magnet bunching section and a radiating wiggler.

synchronism with the beam. Slowing down the PM wave can be done by the gradual increase of the wiggler wavenumber $k_w(z)$ (or decrease of its period $\lambda_w(z)$), so that eqns [29] or [91] keep being satisfied for a given frequency, even if v_z (or γ_z) goes down.

A more correct description of the nonlinear interaction dynamics of the electron beam in a saturated tapered-wiggler FEL is depicted in Figure 20: the electron trap synchronism energy $\gamma_{ph}(z)$ tapers down (by design) along the wiggler, while the trapped electrons are forced to slow down with it, releasing their excess energy by enhanced radiation. An upper limit estimate for the extraction efficiency of such a tapered wiggler FEL would be:

$$\eta_{ext} = \frac{\gamma_{ph}(0) - \gamma_{ph}(L)}{\gamma_{ph}(0)} \qquad [99]$$

and the corresponding radiative power generation would be: $\Delta P = \eta_{ext} I_b E_k / e$. In practice, the phase-space area of the tapered wiggler separatrix is reduced due to the tapering, and only a fraction of the electron beam can be trapped, which reduces correspondingly the practical enhancement in radiative extraction efficiency and power.

An alternative wiggler tapering scheme consists of tapering the wiggler field $B_w(z)$ (or wiggler parameter amplitude $a_w(z)$). If these are tapered down, the axial velocity and axial energy (eqn [7]) can still keep constant (and in synchronism with the PM wave) even if the beam energy γ goes down. Thus, in this scheme, the excess radiative energy extracted from the beam comes out of its transverse (wiggling) energy.

Efficiency and power enhancement of FEL by wiggler tapering have been demonstrated experimentally both in FEL amplifiers (first by Livermore, 1985) and oscillators (first by Los-Alamos, 1983). This elegant way to extract more power from the beam still has some limitations. It can operate efficiently only at a specified high radiation power level for which the tapering was designed. In an oscillator, a long enough untapered section must be left to permit sufficient small signal gain in the early stages of the laser oscillation build-up process.

FEL Oscillators

Most FEL devices are oscillators. As in any laser, in order to turn the FEL amplification process into an oscillation process, one provides a feedback mechanism by means of an optical resonator. In steady state saturation, $GR_{rt} = 1$, where R_{rt} is the round trip reflectivity factor of the resonator and $G = P(L)/P(0)$ is the saturated single-path gain coefficient of the FEL. To attain oscillation, the small signal (unsaturated) gain, usually given by the small gain expression in eqn [53], must satisfy the lasing threshold condition $G > 1/R_{rt}$, as in any laser.

When steady state oscillation is attained, the oscillator output power is:

$$P_{out} = \frac{T}{1 - R_{rt}} \Delta P_{ext} \qquad [100]$$

where $\Delta P_{ext} = \eta_{ext} I_0 (\gamma_0 - 1) mc^2/e$ and η_{ext} is the extraction efficiency, usually given by eqn [89] (low-gain limit).

Usually, FEL oscillators operate in the low-gain regime, in which case $1 - R_{rt} = L + T \ll 1$ (where L is the resonator internal loss factor). Consequently, then $P_{out} \cong \Delta P_{ext} T/(L + T)$, which would give a maximum value, depending on the saturation level of the oscillator. In the general case, one must solve the nonlinear force equations together with the resonator feedback relations of the oscillating radiation mode, in order to maximize the output power (eqn [100]) or efficiency by choice of optimal T for given L.



Figure 20 'Snapshots' of the trap at three locations along a tapered wiggler FEL.

In an FEL oscillator operating with periodic electron bunches (as in RF-acclerator based FEL), the solution for the FEL gain and saturation dynamics requires extension of the single frequency solution of the electron and electromagnetic field equations to the time domain. In principle, the situation is similar to that of a mode-locked laser, and the steady state laser pulse train waveform constitutes a superposition of the resonator longitudinal modes that produces a self-similar pulse shape with the highest gain (best overlap with the e-beam bunch along the interaction length). Because the e-beam velocity v_{z0} is always smaller (in an open resonator) than the group velocity of the circulating radiation wavepacket, the radiation wavepacket slips ahead of the electron bunch one optical period λ in each wiggling period (Slippage effect). This reduces the overlap between the radiation pulse and the e-beam bunch along the wiggler (see **Figure 14**) and consequently decreases the gain. Fine adjustment of the resonator mirrors (as shown in **Figure 14**) is needed to attain maximal power and optimal radiation pulse shape. The pulse-slippage gain reduction effect is negligible only if the bunch length is much longer than the slippage length $N_w\lambda$, which can be expressed as:

$$\tau_p \gg 2\pi/\Delta\omega_L \qquad [101]$$

where $\Delta\omega_L$ is the synchrotron undulator radiation frequency bandwidth (eqn [55]). This condition is usually not satisfied in RF-accelerator FELs operating in the IR or lower frequencies, and the



Figure 21 Anticipated peak brightness of SASE FELs (TTF-DESY, LCLS-SLAC) in comparison to the undulators in present third generation Synchrotron Radiation sources. Figure courtesy of DESY, Hamburg, Germany.

slippage effect gain reduction must be then taken into account.

An FEL operating in the cold-beam regime constitutes an 'homogeneous broadening' gain medium in the sense of conventional laser theory. Consequently, the longitudinal mode competition process that would develop in a CW FEL oscillator, leads to single-mode operation and high spectral purity (temporal coherence) of the laser radiation. The minimal (intrinsic) laser linewidth would be determined by an expression analogous to the Schawlow–Towns limit of atomic laser:

$$(\Delta f)_{\mathrm{int}} = \frac{(\Delta f_{1/2})^2}{I_{\mathrm{b}}/e} \qquad [102]$$

where $\Delta f_{1/2}$ is the spectral width of the cold resonator mode. Expression [102] predicts extremely narrow linewidth. In practice, CW operation of FEL was not yet attained, but Fourier transform limited linewidths in the range of $\Delta f/f_0 \cong 10^{-6}$ were measured in long-pulse electrostatic accelerator FELs. In an FEL oscillator, based on a train of e-beam bunches (e.g., an R.F. accelerator beam), the linewidth is very wide and is equal to the entire gain bandwidth (eqn [56]) in the slippage dominated limit, and to the Fourier transform limit $\Delta\omega \cong 2\pi/\tau_{\mathrm{p}}$ in the opposite negligible-slippage limit (eqn [101]). Despite this slippage, it was observed in RF-LINAC FEL that the radiation pulses emitted by the FEL oscillator are phase corrected with each other, and therefore their total temporal coherence length may be as long as the


4 MeV
16 MeV
120 MeV
233 MeV
Laser driven electron gun
Pre-accelerator
Superconducting accelerating cavities
Undulator
Photon beam diagnostics
Laser
e⁻- beam diagnostics
Bunch compressor
e⁻- beam diagnostics
(a)
100 m
Free electron laser experimental hall
Beam dump
Linac and undulator tunnel
Transport tunnel
Cryogenic hall
TESLA test facility
50 m
(b)

Figure 22 Phase 1 of the SASE FE L (TTF VUV-FEL1): (a) Accelerator layout scheme; (b) General view of the TESLA test facility. Figure courtesy of DESY, Hamburg, Germany.

Metal Vapor Lasers

D W Coutts, University of Oxford, Oxford, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Metal vapor lasers form a class of laser in which the active medium is a neutral or ionized metal vapor usually excited by an electric discharge. These lasers fall into two main subclasses, namely cyclic pulsed metal vapor lasers and continuous-wave metal ion lasers. Both types will be considered in this article, including basic design and construction, power supplies, operating characteristics (including principal wavelengths), and brief reference to their applications.

Self-Terminating Resonance-Metastable Pulsed Metal Vapor Lasers

The active medium in a self-terminating pulsed metal vapor laser consists of metal atoms or ions in the vapor phase usually as a minority species in an inert buffer gas such as neon or helium. Laser action occurs between a resonance upper laser level and a metastable lower laser level (Figure 1). During a fast pulsed electric discharge (typically with a pulse duration of order 100 ns) the upper laser level is preferentially excited by electron impact excitation because it is strongly optically connected to the ground state (resonance transition) and hence has a large excitation cross-section. For a sufficiently large metal atom (or ion) density, the resonance radiation becomes optically trapped, thus greatly extending the lifetime of the upper laser level such that decay from the upper laser level is channelled through the emission of laser radiation to the metastable lower laser level. Lasing terminates when the electron temperature falls to a point such that preferential pumping to the upper laser level is no longer sustained, and the build-up of population in the metastable lower laser level destroys the population inversion. Therefore after each excitation pulse, the resulting excited species in the plasma (in particular the metastable lower laser levels which are quenched by collisions with cold electrons) must be allowed sufficient time to relax and the plasma must be allowed to partially recombine before applying the next excitation pulse. The relaxation times for self-terminating metal vapor lasers correspond to operating pulse repetition frequencies from 2 kHz to 200 kHz.



Figure 1 Resonance-metastable energy levels for self-terminating metal vapor lasers.

Many metal vapors can be made to lase in the resonance-metastable scheme and are listed together with their principal wavelengths and output powers in Table 1. The most important self-terminating pulsed metal vapor laser is the copper vapor laser and its variants which will be discussed in detail in the following sections. Of the other pulsed metal vapor lasers listed in Table 1, only the gold vapor laser (principal wavelengths 627.8 nm and 312.3 nm), and the barium vapor laser which operates in the infrared (principal wavelengths 1.5 μm and 2.55 μm) have had any commercial success. All the self-terminating pulsed metal vapor lasers have essentially the same basic design and operating characteristics as exemplified by the copper vapor laser.

Copper Vapor Lasers

Copper vapor lasers (CVLs) are by far the most widespread of all the pulsed metal vapor lasers. Figure 2 shows the energy level scheme for copper. Lasing occurs simultaneously from the $^2P_{3/2}$ level to the $^2D_{5/2}$ level (510.55 nm) and from the $^2P_{1/2}$ level to the $^2D_{3/2}$ level (578.2 nm). Commercial devices are available with combined outputs of over 100 W at 510.55 nm and 578.2 nm (typically with a green-to-yellow power ratio of 2:1).

A typical copper vapor laser tube is shown in Figure 3. High-purity copper pieces are placed at intervals along an alumina ceramic tube which typically has dimensions of 1–4 cm diameter and 1–2 m long. The alumina tube is surrounded by a solid fibrous alumina thermal insulator, and a glass or quartz vacuum envelope. Cylindrical electrodes made of copper or tantalum are located at each end of the plasma tube to provide a longitudinal discharge

Table 1 Principal self-terminating resonance-metastable metal vapor lasers

Metal	*Principal wavelengths (nm)*	*Powers*		*Total efficiencies*	*Pulse repetition frequency (kHz)*	*Technological development*
		Typical (W)	*Maximum (W)*			
Cu	510.55	2–70	2500 total	1%	4–40	Highly developed and commercially available
	578.2	1–50				
Au	627.8	1–8	20	0.13%	2–40	Commercially available
	312	0.1–0.2	1.2		1–8	
Ba	1500	2–10	12	0.5%	5–15	Have been produced commercially, but largely experimental
	2550	1	1.5			
	1130	0.5	1.0			
Pb	722.9		4.4	0.15%	10–30	Experimental
Mn	534.1 (>50%)		12 total	0.32%	~10	Experimental
	1290					


4
3
2
1
0 eV
Electron-impact excitation
Green (511 nm)
Yellow (578 nm)
Optically trapped resonance radiation
Collisional deactivation
$3d^{10}4p\ ^2P_{3/2}$
$3d^{10}4p\ ^2P_{1/2}$
Resonance Upper laser levels
$3d^94s^2\ ^2D_{3/2}$
$3d^94s^2\ ^2D_{5/2}$
Metastable lower laser levels
$3d^{10}4s^2\ ^2S_{1/2}$
Ground state

Figure 2 Partial energy level scheme for the copper vapor laser.


Electrode
Water-cooled current return
Electrode
Copper pieces
Neon gas out
Neon gas in
Alumina plasma tube
Fibrous alumina insulation
Silica vacuum envelope

Figure 3 Copper vapor laser tube construction.

arrangement. The cylindrical electrodes and silica laser end windows are supported by water-cooled end pieces. The laser windows are usually tilted by a few degrees to prevent back reflections into the active medium. The laser head is contained within a water cooled metal tube to provide a coaxial current return for minimum laser head inductance. Typically a slow flow (~5 mbar l min^{-1}) of neon at a pressure of 20–80 mbar is used as the buffer gas with an approximately 1% H_2 additive to improve the afterglow plasma relaxation. The buffer gas provides a medium to operate the discharge when the laser is cold and slows diffusion of copper vapor out of the ends of the hot plasma tube. Typical copper fill times are of order 200–2000 hours (for 20–200 g copper load). Sealed-off units with lifetimes of order 1000 hours have been in production in Russia for many years.

During operation waste heat from the repetitively pulsed discharge heats the alumina tube up to approximately 1500 °C at which point the vapor pressure of copper is of approximately 0.5 mbar which corresponds to the approximate density required for maximum laser output power. Typical warm-up times are therefore relatively long at around one hour to full power.

One way to circumvent the requirement for high temperatures required to produce sufficient copper density by evaporation of elemental copper (and hence also reduce warm-up times) is to use a copper salt with a low boiling point located in one or more side-arms of the laser tube (Figure 4). Usually copper halides are used as the salt, with the copper bromide laser being the most successful. For the CuBr laser, a temperature of just 600 °C is sufficient to produce the required Cu density by dissociation of CuBr vapor in the discharge. With the inclusion of 1–2% H_2 in the neon buffer gas, HBr is also formed in the CuBr laser, which has the additional benefit of improving recombination in the afterglow via dissociative attachment of free electrons: $\text{HBr} + e^- \rightarrow \text{H} + \text{Br}^-$, followed by ion neutralization: $\text{Br}^- + \text{Cu}^+ \rightarrow \text{Br} + \text{Cu}^*$. As a result of the lower operating temperature and kinetic advantages of HBr, CuBr lasers are typically twice as efficient (2–3%) as their elemental counterparts. Sealed-off CuBr systems with powers of order 10–20 W are commercially produced.

An alternative technique for reducing the operating temperature of elemental CVLs is to flow a buffer gas mixture consisting of ~5% HBr in neon at approximately 50 mbar l min^{-1} and allow this to react with solid copper metal placed within the plasma tube at about 600 °C to produce CuBr vapor *in situ*. The so-called Cu HyBrID (hydrogen bromide in discharge) laser has the same advantages as the CuBr laser (e.g., up to 3% efficiency) but at the cost of requiring flowing highly toxic HBr in the buffer gas, a requirement which has so far prevented commercialization of Cu HyBrID technology.

The kinetic advantages of the hydrogen halide in the CuBr laser discharge can also be applied to a conventional elemental CVL through the addition of small partial pressure of HCl to the buffer gas in addition to the 1–2% H_2 additive. HCl is preferred to HBr as it is less likely to dissociate (the dissociation energy of HCl at 0.043 eV is less than HBr at 0.722 eV). Such kinetic enhancement leads to a doubling in average output power, a dramatic increase in beam quality through improved gain characteristics, and shifts the optimum pulse repetition frequency for kinetically enhanced CVLs (KE-CVLs) from 4–10 kHz up to 30–40 kHz.

Preferential pumping of the upper laser levels requires an electron temperature in excess of the 2 eV range, hence high voltage (10–30 kV), high current (hundreds of A), short (75–150 ns) excitation pulses are required for efficient operation of copper vapor lasers. To generate such excitation pulses CVLs are typically operated with a power supply incorporating a high-voltage thyratron switch. In the most basic configuration, the charge-transfer circuit shown


Silica baffles to confine discharge
Electrode and bromine trap
Heated copper bromide reservoirs
Electrode and bromine trap

Figure 4 Copper bromide laser tube construction.

in Figure 5a, a dc high-voltage power supply resonantly charges a storage capacitor (C_S, typically a few nF) through a charging inductor L_C, a high-voltage diode and bypass inductor L_B, up to twice the supply voltage V_S in a time of order 100 μs. When the thyratron is triggered, the storage capacitor discharges through the thyratron and the laser head on a time-scale of 100 ns. Note that during the fast discharge phase, the bypass inductor in parallel with the laser head can be considered to be an open circuit. A peaking capacitor C_P ($\sim 0.5\ C_S$) is provided to increase the rate of rise of the voltage pulse across the laser head. Given the relatively high cost of thyratrons, more advanced circuits are now often used to extend the service lifetime of the thyratron to several thousand hours. In the more advanced circuit (Figure 5b) an LC inversion scheme is used in combination with magnetic pulse compression techniques and operates as follows. Storage capacitors C_S are resonantly charged in parallel to twice the dc supply voltage V_S as before. When the thyratron is switched, the charge on C_{S1} inverts through the thyratron and transfer inductor L_T. This LC inversion drags the voltage on the top of C_{S2} down to $-4V_S$. When the voltage across the first saturable inductor L_{S1} reaches a maximum ($-4V_S$) L_{S1} saturates, and allows current to flow from the storage capacitors (now charged in series) to the transfer capacitor ($C_T = 0.5C_{S2}$) thereby transferring the charge from C_{S1} and C_{S2} to C_T in a time much less than the initial LC inversion time. At the moment when the charge on transfer capacitor C_T reaches a maximum (also $-4V_S$), L_{S2} saturates, and the transfer capacitor is discharged through the laser tube, again with a peaking capacitor to increase the voltage rise time. By using magnetic pulse compression the thyratron switched voltage can be reduced by 4 and the peak current similarly reduced (at the expense of increased current pulse duration) thereby greatly extending the thyratron lifetime. Note that in both circuits a ‘magnetic assist’ L_A saturable inductor is provided in series with the thyratron to delay the current pulse through the thyratron until after the thyratron has reached high conductivity thereby reducing power deposition in the thyratron.



Figure 5 Copper vapor laser excitation circuits. (a) Charge transfer circuit; (b) LC inversion circuit with magnetic pulse compression.

Copper vapor lasers produce high average powers (2–100 W available commercially, with laboratory devices producing average powers of over 750 W) and have wall-plug efficiencies of approximately 1%. Copper vapor lasers also make excellent amplifiers due to their high gains, and the amplifiers can be chained together to produce average powers of several kW. Typical pulse repetition frequencies range from 4 to 20 kHz, with a maximum reported pulse repetition frequency of 250 kHz. An approximate scaling law states that for an elemental device with tube diameter D (mm) and length L (m) the average output power in watts will be of order $D \times L$. For example, a typical 25 W copper vapor laser will have a 25 mm diameter by 1 m long laser tube, and operate at 10 kHz corresponding to 2.5 mJ pulse energy and 50 kW peak power (50 ns pulse duration). Copper vapor lasers have very high single-pass gains (greater than 1000 for a 1 m long tube), large gain volumes and short gain durations (20–80 ns, sufficient for the intracavity laser light to make only a few round trips within the optical resonator). Maximum output power is therefore usually obtained in a highly ‘multimode’ (spatially incoherent) beam by using either a fully stable or a plane–plane resonator with a low reflectivity output coupler (usually Fresnel reflection from an uncoated optic is sufficient). To obtain higher beam quality a high magnification unstable resonator is required (Figure 6). Fortunately, copper vapor lasers have sufficient gain to operate efficiently with unstable resonators with magnifications ($M = R_1/R_2$) up to 100 and beyond. Resonators with such high magnifications impose very tight geometric constraints on propagation of radiation on repeated round-trips within the resonator, such that after two round-trips the divergence is typically diffraction-limited. Approximately half the stable-resonator


Concave high reflector radius of curvature R_1
Plasma tube
Scraper mirror with 1 mm diameter hole
Small concave mirror radius of curvature R_2

Figure 6 Unstable resonator configuration often used to obtain high beam quality from copper vapor lasers.

output power can therefore be obtained with near diffraction-limited beam quality by using an unstable resonator. Often, a small-scale oscillator is used in conjunction with a single power amplifier to produce high output power with diffraction-limited beam quality. Hyperfine splitting combined with Doppler broadening lead to an inhomogeneous linewidth for the laser transitions of order 8–10 GHz corresponding to a coherence length of order 3 cm.

The high beam quality and moderate peak power of CVLs allows efficient nonlinear frequency conversion to the UV by second harmonic generation (510.55 nm → 255.3 nm, 578.2 nm → 289.1 nm) and sum frequency generation (510.55 nm + 578.2 nm → 271.3 nm) using β-barium borate β-BaB_2O_4 (BBO) as the nonlinear medium. Typically average powers in excess of 1 W can be obtained at any of the three wavelengths from a nominally 20 W CVL. Powers up to 15 W have been obtained at 255 nm from high-power CVL master-oscillator power-amplifier systems using cesium lithium borate; $CsLi\ B_6O_{10}$ (CLBO) as the nonlinear crystal.

Key applications of CVLs include pumping of dye lasers (principally for laser isotope separation) and pumping Ti:sapphire lasers. Medically, the CVL yellow output is particularly useful for treatment of skin lesions such as port wine stain birth marks. CVLs are also excellent sources of short-pulse stroboscopic illumination for high-speed imaging of fast objects and fluid flows. The high beam quality, visible wavelength and high pulse repetition rate make CVLs very suited to precision laser micromachining of metals, ceramics and other hard materials. More recently, the second harmonic at 255 nm has proved to be an excellent source for writing Bragg gratings in optical fibers.

Afterglow Recombination Metal Vapor Lasers

Recombination of an ionized plasma in the afterglow of a discharge pulse provides a mechanism for achieving a population inversion and hence laser output. The two main afterglow recombination metal vapor lasers are the strontium ion vapor laser (430.5 nm and 416.2 nm) and calcium ion vapor laser (373.7 nm and 370.6 nm) whose output in the violet and UV spectral regions extends the spectral coverage of pulsed metal vapor lasers to shorter wavelengths.

A population inversion is produced by recombination pumping where doubly ionized Sr (or Ca) recombines to form singly ionized Sr (or Ca) in an excited state: $Sr^{++} + e^- + e^- \rightarrow Sr^{+*} + e^-$. Note that recombination rates for a doubly ionized species are much faster than for singly ionized species hence recombination lasers are usually metal ion lasers. Recombination (pumping) rates are also greatest in a cool dense plasma, hence helium is usually used as the buffer gas as it is a light atom hence promotes rapid collisional cooling of the electrons. Helium also has a much higher ionization potential than the alkaline-earth metals (including Sr and Ca) which ensures preferential ionization of the metal species (up to 90% may be doubly ionized).

Recombination lasers can operate where the energy level structure of an ion species can be considered to consist of two (or more) groups of closely spaced levels. In the afterglow of a pulsed discharge electron collisional mixing within each group of levels will maintain each group in thermodynamic equilibrium yielding a Boltzmann distribution of population within each group. If the difference in energy between the two groups of levels ($5\ eV >> kT$) is sufficiently large then thermal equilibrium between the groups cannot be maintained via collisional processes. Given that recombination yields excited singly ionized species (usually with a flux from higher to lower ion levels), it is possible to achieve a population inversion between the lowest level of the upper group and the higher levels within the lower group. This is the mechanism for inversion in the Sr^+ (and analogous Ca^+) ion laser as indicated in the partial energy level scheme for Sr^+ shown in Figure 7.

Strontium and calcium ion recombination lasers have similar construction to copper vapor lasers described above. The lower operating temperatures (500–800 °C) mean that minimal or no thermal insulation is required for self-heated devices.


11
10
9
8
7
6
5
4
3
2
1
0 eV
Sr++ level
Recombination pumping
Upper group
6s $^2S_{1/2}$ Upper laser level
Stepwise ionization
430.5 nm Laser transition
416.2 nm Laser transition
5p $^2P_{3/2}$ Lower laser levels
5p $^2P_{1/2}$
Lower group
4d $^2D_{5/2}$
4d $^2D_{3/2}$
$3d^{10}4s^2$ $^2S_{1/2}$
Sr+ Ground state
= 5.7 eV above Sr ground state
Collisional deactivation

Figure 7 Partial energy level scheme for the strontium ion laser.

For good tube lifetime BeO plasma tubes are required due to the reactivity of the metal vapors. Usually helium at a pressure of up to one atmosphere is used as the buffer gas. Typical output powers at 5 kHz pulse repetition frequency are of order 1 W (~0.1% wall plug efficiency) at 430.5 nm from the He Sr^+ laser and 0.7 W at 373.7 nm from the He Ca^+ laser. For the high specific input power densities (10–15 W cm^{-3}) required for efficient lasing, overheating of the laser gas limits aperture scaling beyond 10–15 mm diameter. Slab laser geometries have been used successfully to aperture-scale strontium ion lasers. Scaling of the laser tube length beyond 0.5 m is not practical as achieving high enough excitation voltages for efficient lasing becomes problematic. Gain in strontium and calcium ion lasers is lower than in resonance-metastable metal vapor lasers such as the CVL, hence optimum output coupler reflectivity is approximately 70%. The pulse duration is also longer at around 200–500 ns resulting in moderate beam quality with plane–plane resonators.

For both strontium and calcium ion lasers the two principal transitions share upper laser levels and hence exhibit gain competition such that without wavelength-selective cavities usually only the longer wavelength of the pair is produced. With wavelength-selective cavities up to 60% (Sr^+) and 30% (Ca^+) of the normal power can be obtained at the shorter wavelength.

Many potential applications exist for strontium and calcium ion lasers, given their ultraviolet (UV)/violet wavelengths. Of particular importance is fluorescence spectroscopy in biology and forensics, treatment of neonatal jaundice, stereolithography, micromachining and exposing photoresists for integrated circuit manufacture. Despite these many potential applications, technical difficulties in power scaling mean that both strontium ion and calcium ion lasers have only limited commercial availability.

Continuous-Wave Metal Ion Lasers

In a discharge excited noble gas, there can be a large concentration of noble gas atoms in excited metastable states and noble gas ions in their ground states. These species can transfer their energy to a minority metal species (M) via two key processes: either charge transfer (Duffendack reactions) with the noble gas ions (N^+):

$$M + N^+ \rightarrow M^{+*} + N + \Delta E$$

(where M^{+*} is an excited metal ion state)

or Penning ionization with a noble gas atom in an excited metastable state (N^*):

$$M + N^* \rightarrow M^{+*} + N + e^-$$

In a continuous discharge in a mixture of a noble gas and a metal vapor, steady generation of excited metal ions via energy transfer processes can lead to a steady state population inversion on one or more pairs of levels in the metal ion and hence produce cw lasing.

Several hundred metal ion laser transitions have been observed to lase in a host of different metals. The most important such laser is the helium cadmium laser, which has by far the largest market volume by number of unit sales of all the metal vapor lasers. In a helium cadmium laser, Cd vapor is present at a concentration of about 1–2% in a helium buffer gas which is excited by a dc discharge. Excitation to the upper laser levels of Cd (Figure 8) is primarily via Penning ionization collisions with He^+ 2^3S_1 metastable ions produced in the discharge. Excitation via electron-impact excitation from the ion ground state may also play an important role in establishing a population inversion in Cd^+ lasers. Population inversion can be sustained continuously because the $^2P_{3/2}$ and $^2P_{1/2}$ lower laser levels decay via strong resonance transitions to the $^2S_{1/2}$ Cd^+ ground state, unlike in the self-terminating metal vapor lasers. Two principal wavelengths can be produced, namely 441.6 nm (blue) and 325.0 nm (UV) with cw powers up to 200 mW and 50 mW available respectively from commercial devices.

Typical laser tube construction (Figure 9) consists of a 1–3 mm diameter discharge channel typically 0.5 m long. A pin anode is used at one end of the laser tube together with a large-area cold cylindrical cathode located in a side-arm at the other end of the tube. Cadmium is transported to the main discharge tube from a heated Cd reservoir in a side-arm at 250–300 °C. With this source of atoms at the anode end of the laser a cataphoresis process (in which the positively charged Cd ions are propelled towards the cathode end of the tube by the longitudinal electric field) transports Cd into the discharge channel. Thermal insulation of the discharge tube ensures that it is kept hotter than the Cd reservoir to prevent condensation of Cd from blocking the tube bore. A large-diameter Cd condensation region is provided at the cathode end of the discharge channel. A large-volume side arm is also provided to act as a gas ballast for maintaining correct He pressure. As He is lost through sputtering and diffusion through the Pyrex glass tube walls, it is replenished from a high-pressure He reservoir by heating a permeable glass wall separating the reservoir from the ballast chamber which allows He to diffuse into the ballast chamber. Typical commercial sealed-off Cd lasers have operating lifetimes of several thousand hours. Overall laser construction is not that much more



Helium
Cadmium
Cd++ level
26
24
22
20
18
16
14
12
10
8
0eV
He+
Penning ionization
He 2³S₁
4d⁹5s² ²D3/2 Upper laser
4d⁹5s² ²D5/2 levels
441.6 nm Laser transition
325.0 nm Laser transition
4d¹⁰5p ²P3/2
4d¹⁰5p ²P1/2 Lower laser levels
Direct electron-impact excitation from ion ground state
Fast radiative decay: 227 nm and 214 nm
4d¹⁰5s ²S1/2
Cd+ Ground
4d¹⁰5s² ¹S0
Cd Ground

Figure 8 Partial energy level diagram for helium and cadmium giving HeCd laser transitions.



Figure 9 Helium cadmium laser tube construction.

complex than a HeNe laser, hence unit costs are considerably lower than low-power argon ion lasers which also provide output in the blue. Usually Brewster angle windows are provided together with a high Q stable resonator (97–99% reflectivity output coupler) to provide polarized output.

With their blue and UV wavelengths and relatively low cost (compared to low-power argon ion lasers), HeCd lasers have found wide application in science, medicine and industry. Of particular relevance is their application for exposing photoresists where the blue wavelength provides a good match to the peak photosensitivity of photoresist materials. A further key application is in stereolithography where the UV wavelength is used to cure an epoxy resin. By scanning the UV beam in a raster pattern across the surface of a liquid epoxy, a solid three-dimensional object may be built up in successive layers.

List of Units and Nomenclature

Boltzmann constant	[eV K^{-1}]	k
Excited metal ion		M^{+*}
Excited noble gas atom		N^*
Energy difference	[eV]	ΔE
Electron		e^-
Gas flow	[mbar l min^{-1}]	
Mirror curvatures	[m]	R_1, R_2
Metal atom		M
Noble gas atom		N
Noble gas ion		N^+
Pulse duration	[ns]	
Pulse repetition frequency	[kHz]	
Quality factor		Q
Temperature	[K]	T
Tube diameter	[mm]	D
Tube length	[m]	L
Wavelength	[nm], [μm]	
Unstable resonator magnification		M

See also

Nonlinear Sources: Harmonic Generation in Gases.

Further Reading

Little CE (1999) *Metal Vapor Lasers*. Chichester, UK: John Wiley.

Ivanov IG, Latush EL and Sem MF (1996) *Metal Vapor Ion Lasers, Kinetic Processes and Gas Discharges*. Chichester, UK: John Wiley.

Little CE and Sabotinov NV (eds) (1996) *Pulsed Metal Vapor Lasers*. Dordrecht, The Netherlands: Kluwer.

Lyabin NA, Chursin AD, Ugol'nikov SA, Koroleva ME and Kazaryan MA (2001) Development, production, and application of sealed-off copper and gold vapor lasers. *Quantum Electronics* 31: 191–202.

Petrash GG (ed.) (1989) *Metal Vapor and Metal Halide Vapor Lasers*. Commack, NY: Nova Science Publishers.

Silfvast WT (1996) *Laser Fundamentals*. New York: Cambridge University Press.

Noble Gas Ion Lasers

W B Bridges, California Institute of Technology, Pasadena, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

History

The argon ion laser was discovered in early 1964, and is still commercially available in 2004, with about $70 million in annual sales 40 years after this discovery. The discovery was made independently and nearly simultaneously by four different groups; for three of the four, it was an accidental result of studying the excitation mechanisms in the mercury ion laser (historically, the first ion laser), which had been announced only months before. For more on the early years of ion laser research and development, see the articles listed in the Further Reading section at the end of this article.

The discovery was made with pulsed gas discharges, producing several wavelengths in the blue and green portions of the spectrum. Within months, continuous operation was demonstrated, as well as oscillation on many visible wavelengths in ionized krypton and xenon. Within a year, over 100 wavelengths were observed to oscillate in the ions of neon, argon, krypton, and xenon, spanning the spectrum from ultraviolet to infrared; oscillation was also obtained in the ions of other gases, for example, oxygen, nitrogen, and chlorine. A most complete listing of all wavelengths observed as gaseous ion lasers is given in the Laser Handbook cited in the Further Reading section. Despite the variety of materials and wavelengths demonstrated, however, it is the argon and krypton ion lasers that have received the most development and utilization.

Continuous ion lasers utilize high current density gas discharges, typically 50 A or more, and 2–5 mm in diameter. Gas pressures of 0.2 to 0.5 torr result in longitudinal electric fields of a few V/cm of discharge, so that the power dissipated in the discharge is typically 100 to 200 W/cm. Such high-power dissipation required major technology advances before long-lived practical lasers became available. Efficiencies have never been high, ranging from 0.01% to 0.2%. A typical modern ion laser may produce 10 W output at 20 kW input power from 440 V three-phase power lines and require 6–8 gallons/minute of cooling water. Smaller, air-cooled ion lasers, requiring 1 kW of input power from 110 V single-phase mains can produce 10–50 mW output power, albeit at even lower efficiency.

Theory of Operation

The strong blue and green lines of the argon ion laser originate from transitions between the 4p upper levels and 4s lower levels in singly ionized argon, as shown in Figure 1. The 4s levels decay radiatively to the ion ground state. The strongest of these laser lines are listed in Table 1. The notation used for the energy levels is that of the L–S coupling model. The ion ground state electron configuration is $3s^23p^5(^2P^o_{3/2})$. The inner ten electrons have the configuration $1s^22s^22p^6$, but this is usually omitted for brevity. The excited states shown in Figure 1 result from coupling a 4p or 4s electron to a $3s^23p^4(^3P)$ core, with the resulting quantum numbers S (the net spin of the electrons), L (the net angular momentum of the electrons), and J (the angular momentum resulting from coupling S to L) are represented by $^{2S+1}L_J$, where $L = 0, 1, 2, \ldots$ is denoted S, P, D, F, … The superscript 'o' denotes an odd level, while even levels omit a superscript. Note that some weaker transitions involving levels originating from the $3s^23p^4(^1D)$ core configuration also oscillate. Note also that the quantum mechanical selection rules for the L–S coupling model are not rigorously obeyed, although the stronger laser lines satisfy most or all of these rules. The selection rule $|\Delta J| = 1$ or 0, but not $J = 0 \rightarrow J = 0$ is always obeyed. All transitions shown in Figure 1 and Table 1 belong to the second spectrum of argon, denoted Ar II. Lines originating from transitions in the neutral atom make up the first spectrum, Ar I; lines originating from transitions in doubly ionized argon are denoted Ar III, and so forth for even more highly ionized states.

Much work has been done to determine the mechanisms by which the inverted population is formed in the argon ion laser. Reviews of this extensive research



Figure 1 4p and 4s doublet levels in singly ionized argon, showing the strongest blue and green laser transitions.

Table 1 Ar II laser blue-green wavelengths

Wavelength (nanometers)	*Transition*[a] *(upper level) → (lower level)*	*Relative strength*[b] *(Watt)*
454.505	$4p\ ^2P^o_{3/2} \rightarrow 4s\ ^2P_{3/2}$	0.8
457.935	$4p\ ^2S^o_{1/2} \rightarrow 4s\ ^2P_{1/2}$	1.5
460.956	$(^1D)4p\ ^2F^o_{7/2} \rightarrow (^1D)4s\ ^2D_{5/2}$	–
465.789	$4p\ ^2P^o_{1/2} \rightarrow 4s\ ^2P_{3/2}$	0.8
472.686	$4p\ ^2D^o_{3/2} \rightarrow 4s\ ^2P_{3/2}$	1.3
476.486	$4p\ ^2P^o_{3/2} \rightarrow 4s\ ^2P_{1/2}$	3.0
487.986	$4p\ ^2D^o_{5/2} \rightarrow 4s\ ^2P_{3/2}$	8.0
488.903	$4p\ ^2P^o_{1/2} \rightarrow 4s\ ^2P_{1/2}$	[c]
496.507	$4p\ ^2D^o_{3/2} \rightarrow 4s\ ^2P_{1/2}$	3.0
501.716	$(^1D)4p\ ^2D^o_{5/2} \rightarrow 3d\ ^2D_{3/2}$	1.8
514.179	$(^1D)4p\ ^2F^o_{7/2} \rightarrow 3d\ ^2D_{5/2}$	[c]
514.532	$4p\ ^4D^o_{5/2} \rightarrow 4s\ ^2P_{3/2}$	10
528.690	$4p\ ^4D^o_{3/2} \rightarrow 4s\ ^2P_{1/2}$	1.8

[a] All levels are denoted in $L-S$ coupling with the (^{3}P) core unless otherwise indicated. Odd parity is denoted by the superscript 'o'.
[b] Relative strengths are given as power output from a commercial Spectra-Physics model 2080-25S argon ion laser.
[c] These lines may oscillate simultaneously with the nearby strong line, but are not resolved easily in the output beam.



Figure 2 Schematic representation of energy levels in neutral and singly ionized argon, indicating alternative pathways for excitation and de-excitation of the argon ion laser levels.

are found in the Further Reading section. While a completely quantitative picture of argon ion laser operation is lacking to this day, the essential processes are known. Briefly, the 4p upper levels are populated by three pathways, as illustrated in Figure 2:

(i) by electron collision with the $3p^6$ neutral ground state atoms. This 'sudden perturbation process' requires at least 37 eV electrons, and also singles out the $4p\ ^2P^o_{3/2}$ upper level, which implies that only the 476 and 455 nm lines would oscillate. This is the behavior seen in pulsed discharges at very low pressure and very high axial electric field. This pathway probably contributes little to the 4p population under ordinary continuous wave (cw) operating conditions, however.

(ii) by electron collision from the lowest-lying s and d states in the ion, denoted M(s,d) in Figure 1. This only requires 3–4 eV electrons. These states have parity-allowed transitions to the ion ground state, but are made effectively metastable by radiation trapping (that is, there is a high probability that an emitted photon is re-absorbed by another ground state ion before it escapes the discharge region), or by requiring $|\Delta J|$ to be 2 to make the transition (forbidden by quantum selection rules). Thus, these levels are both created and destroyed primarily by electron collision, causing the population of the M(s,d) states to follow the population of the singly ionized ground state, which, in turn, is approximately proportional to the discharge current. Since a second electron collision is required to get from the M(s,d) states to the 4p states, a quadratic variation with current for the laser output power would be expected, and that is what is observed over some reasonable range of currents between threshold and saturation. Note that radiative decay from higher-lying opposite-parity p and f states, denoted X(p,f), can also contribute to the population of M(s,d), but the linear variation in population of the M(s,d) with discharge current is assured by electron collision creation and destruction.

(iii) by radiative decay from higher-lying opposite-parity s and d states, denoted C(s,d). These states are populated by electron collision with the $3p^5$ ion ground states, and thus have populations that also vary quadratically with discharge current. The contribution of this cascade process has been measured to be 20% to 50% of the 4p upper laser level population.

Note that it is not possible to distinguish between processes (ii) and (iii) by the variation of output power with discharge current; both give the observed quadratic dependence.

The radiative lifetimes of the 4s ^{2}P levels are sufficiently short to depopulate the lower laser levels by radiative decay. However, radiation trapping greatly lengthens this decay time, and a bottleneck can occur. In pulsed ion lasers, this is exhibited by the laser pulse terminating before the excitation current pulse ends, which would seem to preclude continuous operation. However, the intense discharge used in continuous operation heats the ions to the order of 2300 K, thus greatly Doppler broadening the absorption linewidth and reducing the magnitude of the absorption. Additionally, the ions are attracted to the discharge tube walls, so that the absorption spectrum is further broadened by the Doppler shift due to their wall-directed velocities. The plasma wall sheath gives about 20 V drop in potential from the discharge axis to the tube wall, so most ions hit the wall with 20 eV of energy, or about ten times their thermal velocity. A typical cw argon ion laser operates at ten times the gas pressure that is optimum for a pulsed laser, and thus the radiation trapping of the $4s \rightarrow 3p^5$ transitions is so severe that it may take several milliseconds after discharge initiation for the laser oscillation to begin.

As the discharge current is increased, the intensities of the blue and green lines of Ar II eventually saturate, and then decrease with further current. At these high currents, there is a buildup in the population of doubly ionized atoms, and some lines of Ar III can be made to oscillate with the appropriate ultraviolet mirrors. Table 2 lists the strongest of these lines, those that are available in the largest commercial lasers. Again, there is no quantitative model for the performance in terms of the discharge parameters, but the upper levels are assumed to be populated by processes analogous to those of the Ar II laser. At still higher currents, lines in Ar IV can be made to oscillate as well.

Much less research has been done on neon, krypton, and xenon ion lasers, but it is a good assumption that the population and depopulation processes are the same in these lasers. Table 3 lists both the Kr II and Kr III lines that are available from the largest commercial ion lasers. Oscillation on lines in still-higher ionization states in both krypton and xenon have been observed.

Operating Characteristics

A typical variation of output power with discharge current for an argon ion laser is shown in Figure 3. This particular laser had a 4 mm diameter discharge in a water-cooled silica tube, 71 cm in length, with a 1 kG axial magnetic field. The parameter is the argon pressure in the tube before the discharge was struck. Note that no one curve is exactly quadratic, but that the envelope of the curves at different filling pressures is approximately quadratic. At such high discharge current densities (50 A in the 4 mm tube is approximately 400 A/cm^2) there is substantial pumping of gas out of the small-bore discharge region. Indeed, a return path for this pumped gas must be provided from anode to cathode ends of the discharge to keep the discharge from self-extinguishing. The axial electric field in this discharge was 3–5 V/cm, so the input power was of the order of 10 to 20 kW, yielding an efficiency of less than 0.1%, an unfortunate characteristic of all ion lasers.

Table 2 Ultraviolet argon ion laser wavelengths

Wavelength (nanometers)	*Spectrum*	*Transition*[a] *(upper level) → (lower level)*	*Relative strength*[b] *(Watt)*
275.392	III	$(^2D^o)4p\ ^1D_2 \rightarrow (^2D^o)4s\ ^1D^o_2$	0.3
275.6	?	?	0.02
300.264	III	$(^2P^o)4p\ ^1P_1 \rightarrow (^2P^o)3d\ ^1D^o_2$	0.5
302.405	III	$(^2P^o)4p\ ^3D_3 \rightarrow (^2P^o)4s\ ^3P^o_2$	0.5
305.484	III	$(^2P^o)4p\ ^3D_2 \rightarrow (^2P^o)4s\ ^3P^o_1$	0.2
333.613	III	$(^2D^o)4p\ ^3F_4 \rightarrow (^2D^o)4s\ ^3D^o_3$	0.4
334.472	III	$(^2D^o)4p\ ^3F_3 \rightarrow (^2D^o)4s\ ^3D^o_2$	0.8
335.849	III	$(^2D^o)4p\ ^3F_2 \rightarrow (^2D^o)4s\ ^3D^o_1$	0.8
350.358	III	$(^2D^o)4p\ ^3D_2 \rightarrow (^2D^o)4s\ ^3D^o_2$	0.05
350.933	III	$(^4S^o)4p\ ^3P_0 \rightarrow (^4S^o)4s\ ^3S^o_1$	0.05
351.112	III	$(^4S^o)4p\ ^3P_2 \rightarrow (^4S^o)4s\ ^3S^o_1$	2.0
351.418	III	$(^4S^o)4p\ ^3P_1 \rightarrow (^4S^o)4s\ ^3S^o_1$	0.7
363.789	III	$(^2D^o)4p\ ^1F_3 \rightarrow (^2D^o)4s\ ^1D^o_2$	2.5
379.532	III	$(^2P^o)4p\ ^3D_3 \rightarrow (^2P^o)3d\ ^3P^o_2$	0.4
385.829	III	$(^2P^o)4p\ ^3D_2 \rightarrow (^2P^o)3d\ ^3P^o_1$	0.15
390.784	III	$(^2P^o)4p\ ^3D_1 \rightarrow (^2P^o)3d\ ^3P^o_0$	0.02
408.904	IV?	?	0.04
414.671	III	$(^2D^o)4p\ ^3P_2 \rightarrow (^2P^o)4s\ ^3P^o_2$	0.02
418.298	III	$(^2D^o)4p\ ^1P_1 \rightarrow (^2D^o)4s\ ^1D^o_2$	0.08

[a] All levels are denoted in $L-S$ coupling with the core shown in ( ). Odd parity is denoted by the superscript 'o'.

[b] Relative strengths are given as power output from a commercial Spectra-Physics model 2085-25S argon ion laser.

Table 3 Krypton ion laser wavelengths

Wavelength (nanometers)	*Spectrum*	*Transition*[a] *(upper level) → (lower level)*	*Relative strength*[b] *(Watt)*
337.496	III	$(^2\mathrm{P^o})5\mathrm{p}\ ^3\mathrm{D}_3 \rightarrow (^2\mathrm{P^o})5\mathrm{s}\ ^3\mathrm{P}^o_2$	–
350.742	III	$(^4\mathrm{S^o})5\mathrm{p}\ ^3\mathrm{P}_2 \rightarrow (^4\mathrm{S^o})5\mathrm{s}\ ^3\mathrm{S}^o_1$	1.5
356.432	III	$(^4\mathrm{S^o})5\mathrm{p}\ ^3\mathrm{P}_1 \rightarrow (^4\mathrm{S^o})5\mathrm{s}\ ^3\mathrm{S}^o_1$	0.5
406.737	III	$(^2\mathrm{D^o})5\mathrm{p}\ ^1\mathrm{F}_3 \rightarrow (^2\mathrm{D^o})5\mathrm{s}\ ^1\mathrm{D}^o_2$	0.9
413.133	III	$(^4\mathrm{S^o})5\mathrm{p}\ ^5\mathrm{P}_2 \rightarrow (^4\mathrm{S^o})5\mathrm{s}\ ^3\mathrm{S}^o_1$	1.8
415.444	III	$(^2\mathrm{D^o})5\mathrm{p}\ ^3\mathrm{F}_3 \rightarrow (^2\mathrm{D^o})5\mathrm{s}\ ^1\mathrm{D}^o_2$	0.3
422.658	III	$(^2\mathrm{D^o})5\mathrm{p}\ ^3\mathrm{F}_2 \rightarrow (^2\mathrm{D^o})4\mathrm{d}\ ^3\mathrm{D}^o_1$	–
468.041	II	$(^3\mathrm{P})5\mathrm{p}\ ^2\mathrm{S}^o_{1/2} \rightarrow (^3\mathrm{P})5\mathrm{s}\ ^2\mathrm{P}_{1/2}$	0.5
476.243	II	$(^3\mathrm{P})5\mathrm{p}\ ^2\mathrm{D}^o_{3/2} \rightarrow (^3\mathrm{P})5\mathrm{s}\ ^2\mathrm{P}_{1/2}$	0.4
482.518	II	$(^3\mathrm{P})5\mathrm{p}\ ^4\mathrm{S}^o_{3/2} \rightarrow (^3\mathrm{P})5\mathrm{s}\ ^2\mathrm{P}_{1/2}$	0.4
520.832	II	$(^3\mathrm{P})5\mathrm{p}\ ^4\mathrm{P}^o_{3/2} \rightarrow (^3\mathrm{P})5\mathrm{s}\ ^4\mathrm{P}_{3/2}$	–
530.865	II	$(^3\mathrm{P})5\mathrm{p}\ ^4\mathrm{P}^o_{5/2} \rightarrow (^3\mathrm{P})5\mathrm{s}\ ^4\mathrm{P}_{3/2}$	1.5
568.188	II	$(^3\mathrm{P})5\mathrm{p}\ ^4\mathrm{D}^o_{5/2} \rightarrow (^3\mathrm{P})5\mathrm{s}\ ^2\mathrm{P}_{3/2}$	0.6
631.024	III	$(^2\mathrm{D^o})5\mathrm{p}\ ^3\mathrm{P}_2 \rightarrow (^2\mathrm{P^o})4\mathrm{d}\ ^3\mathrm{D}_1$	0.2
647.088	II	$(^3\mathrm{P})5\mathrm{p}\ ^4\mathrm{P}^o_{5/2} \rightarrow (^3\mathrm{P})5\mathrm{s}\ ^2\mathrm{P}_{3/2}$	3.0
676.442	II	$(^3\mathrm{P})5\mathrm{p}\ ^4\mathrm{P}^o_{1/2} \rightarrow (^3\mathrm{P})5\mathrm{s}\ ^2\mathrm{P}_{1/2}$	0.9
752.546	II	$(^3\mathrm{P})5\mathrm{p}\ ^4\mathrm{P}^o_{3/2} \rightarrow (^3\mathrm{P})5\mathrm{s}\ ^2\mathrm{P}_{1/2}$	1.2
793.141	II	$(^1\mathrm{D})5\mathrm{p}\ ^4\mathrm{F}^o_{7/2} \rightarrow (^3\mathrm{P})4\mathrm{d}\ ^2\mathrm{F}_{5/2}$	0.3
799.322	II	$(^3\mathrm{P})5\mathrm{p}\ ^4\mathrm{P}^o_{3/2} \rightarrow (^3\mathrm{P})4\mathrm{d}\ ^4\mathrm{D}_{1/2}$	

[a] All levels are denoted in $L-S$ coupling with the core shown in ( ). Odd parity is denoted by the superscript 'o'.
[b] Relative strengths are given as power output from a commercial Spectra-Physics model 2080RS ion laser.

Technology

With such high input powers required in a small volume to produce several watts output, ion laser performance has improved from 1964 to the present only as new discharge technologies were introduced. The earliest laboratory argon ion lasers used thin-walled (≈1 mm wall thickness) fused silica discharge tubes, cooled by flowing water over the outside wall of the tube. The maximum input power per unit length of discharge was limited by thermal stresses in the silica walls caused by the temperature differential from inside to outside. Typically, ring-shaped cracks would cause the tube to fail catastrophically. Attempts to make metal–ceramic structures with alumina (Al_2O_3) discharge tubes to contain the plasma were made early on (1965) but were not successful. Such tubes invariably failed from fracture by thermal shock as the discharge was turned on. Later, successful metal–ceramic tubes were made with beryllia (BeO), which has a much higher thermal conductivity than silica or alumina and is much more resistant to thermal shock. Today, all of the lower power (less than 100 mW output) are made with BeO discharge tubes. Some ion lasers in the 0.5 to 1 W range are also made with water-cooled BeO discharge tubes.

A typical low-power air cooled argon ion laser is shown in Figure 4. The large metal can (2) on the right end of the tube contains an impregnated-oxide hot cathode, heated directly by current through ceramic feed-through insulators (3). The small (≈1 mm diameter) discharge bore runs down the center of the BeO ceramic rod (1), and several smaller diameter gas return path holes run off-axis parallel to the discharge bore to provide the needed gas equalization between cathode can and anode region. A copper honeycomb cooler is brazed to the cathode can, two more to the outer wall of the BeO cylinder, and one to the anode (4) at the left end of the tube. The laser mirrors (5) are glass-fritted to the ends of the tube, forming a good vacuum seal. Note that in this small laser, the active discharge bore length is less than half of the overall length.

The very early argon ion lasers were made with simple smooth dielectric tubes, allowing the continuous variation in voltage along the length of the tube required by the discharge longitudinal electric field. However, this variation can be step-wise at the discharge walls, and still be more or less smooth along the axis. Thus, the idea arose of using metal tube segments, insulated one from another, to form the discharge tube walls. The first version of this idea (1965) used short (≈1 cm) metal cylinders supported by metal disks and stacked inside a large diameter silica envelope, with each metal cylinder electrically isolated from the others. The tubes and disks were made of molybdenum, and were allowed to heat to incandescence, thus radiating several kilowatts of heat through the silica vacuum envelope to a water-cooled collector outside. While this eliminated the problems of thermal shock and poor thermal conductivity inherent in dielectric wall discharges, it made another



Figure 3 Laser output power (summed over all the blue and green laser lines) versus discharge current for a laser discharge 4 mm in diameter and 71 cm long, with a 1 kilogauss longitudinal magnetic field. The parameter shown is the argon fill pressure in mTorr prior to striking the discharge. The envelope of the curves exhibits the quadratic variation of output power with discharge current.

problem painfully evident. The intense ion bombardment of the metal tube walls sputtered the wall material, eventually eroding the shape of the metal cylinders and depositing metal films on the insulating wall material, thus shorting one segment to another.

Many different combinations of materials and configurations were investigated in the 1960s and 1970s to find a structure that would offer good laser performance and long life. It was found that simple thin metal disks with a central hole would effectively confine the discharge to a small diameter (on the order of the hole size) if a longitudinal d-c magnetic field of the order of 1 kiloGauss were used. The spacing between disks can be as large as 2–4 discharge diameters. Of the metals, tungsten has the lowest sputtering yield for argon ions in the 20 eV range (which is approximately the energy they gain in falling to the wall across the discharge sheath potential difference). An even lower sputtering yield is exhibited by carbon, and graphite cylinders contained within a larger diameter silica or alumina tube were popular for a while for ion laser discharges. Unfortunately, graphite has a tendency to flake or powder, so such laser discharge tubes became contaminated with 'dust' which could eventually find its way to the optical windows of the tube. Beryllia and silica also sputter under argon ion bombardment, but with still lower yields than metals or carbon; however, their smaller thermal conductivities limit them to lower-power applications.

The material/configuration combination that has evolved for higher-power argon ion lasers today is to use a stack of thin tungsten disks with 2–3 mm diameter holes for the discharge. These disks, typically 1 cm in diameter, are brazed coaxially to a larger copper annulus (actually, a drawn cup with a 1 cm hole on its axis). A stack of these copper/tungsten structures is, in turn, brazed to the inside wall of a large diameter alumina vacuum envelope. The tungsten disks are exposed to and confine the discharge, while the copper cups conduct heat radially outward to the alumina tube wall, which, in turn, is cooled by fluid flow over its exterior. Thus, the discharge is in contact only with a low-sputtering material (tungsten) while the heat is removed by a high thermal conductivity material (copper). Details differ among manufacturers, but this 'cool disk' technology seems to have won out in the end. A photo of a half-sectioned disk/cup stacked assembly from a Coherent Innova™ ion laser is shown in Figure 5. The coiled impregnated-tungsten cathode is also shown.

Sputtering of the discharge tube walls is not uniform along the length of the gas discharge. The small diameter region where the laser gain occurs is always joined to larger diameter regions containing cathode and anode electrodes (as shown in Figure 5, for example). A plasma double sheath (that is, a localized increase in potential) forms across the discharge in the transition region between large and small diameter regions (the discharge 'throats,' which may be abrupt or tapered). This sheath is required to satisfy the boundary conditions between the plasmas of different temperatures in the different regions. Such a double sheath imparts additional energy to the ions as they cross the sheath, perhaps



Figure 4 A typical commercial low-power, air-cooled argon ion laser. The cathode can (2) is at the right and the beryllia bore (1) and anode (4) is at the left. The cathode current is supplied through ceramic vacuum feed-throughs (3). Mirrors (5) are glass fritted onto the ends of vacuum envelope. (Photo courtesy of JDS Uniphase Corp.)



Figure 5 Discharge bore structure of a typical commercial high-power argon ion laser, the Coherent Innova™. Copper cups are brazed to the inner wall of a ceramic envelope, which is cooled by liquid flow over its outer surface. A thin tungsten disk with a small hole defining the discharge path is brazed over a larger hole in the bottom of the copper cup. Additional small holes in the copper cup near the ceramic envelope provide a gas return path from cathode to anode. Also shown is the hot oxide-impregnated tungsten cathode. (Photo courtesy of Coherent, Inc.)

an additional 20 eV. When these ions eventually hit the discharge walls near the location of the sheath, they have 40 eV of energy rather than the 20 eV from the normal wall sheath elsewhere in the small diameter discharge. Sputtering yield (number of sputtered wall atoms per incident ion) is exponentially dependent on ion energy in this low ion energy region, so the damage done to the wall in the vicinity of the 'throat' where the double sheath forms may be more than ten times that elsewhere in the small diameter bore region. This was the downfall of high-power operation of dielectric discharge bores, even BeO; while sputtering was acceptable elsewhere in the discharge, the amount of material removed in a small region near the discharge throat would cause catastrophic bore failure at that point. This localized increase in sputtering in the discharge throat is common to all ion lasers, including modern cooled tungsten disk tubes. Eventually, disks near the throat are eroded to larger diameters, and more material is deposited on the walls nearby. Attempts to minimize localized sputtering by tapering the throat walls or the confining magnetic field have proven unsuccessful; a localized double sheath always forms somewhere in the throat. Because of the asymmetry caused by ion flow, the double sheath is larger in amplitude in the cathode throat than the anode throat, so that the localized wall damage is larger at the cathode end of the discharge than at the anode end.

Another undesirable feature of sputtering is that the sputtered material 'buries' some argon atoms when it is deposited on a wall. This is the basis of the well-known Vac-Ion® vacuum pump. Thus, the operating pressure in a sealed laser discharge tube will drop during the course of operation. In low-power ion lasers, this problem is usually solved by making the gas reservoir volume large enough to satisfy the desired operating life (for example, the large cathode can in Figure 4). In high-power ion lasers, the gas loss would result in unacceptable operating life even with a large reservoir at the fill pressure. Thus, most high-power ion lasers have a gas pressure measurement system and dual-valve arrangement connected to a small high-pressure reservoir to 'burp' gas into the active discharge periodically to keep the pressure within the operating range. Unfortunately, if a well-used ion laser is left inoperative for months, some of the 'buried' argon tends to leak back into the tube, with the gas pressure becoming higher than optimum. The pressure will gradually decrease to its optimum value with further operation of the discharge (in perhaps tens of hours). In the extreme case, the gas pressure can rise far enough so that the gas discharge will not strike, even at the maximum power supply voltage. Such a situation requires an external vacuum pump to remove the excess gas, usually a factory repair.

In addition to simple dc discharges, various other techniques have been used to excite ion lasers, primarily in a search for higher power, improved efficiency and longer operating life. Articles in the Further Reading section give references to these attempts. Radio-frequency excitation at 41 MHz was used in an inductively coupled discharge, with the laser bore and its gas return path forming a rectangular single turn of an air-core transformer. A commercial product using this technique was sold for a few years in the late 1960s. Since this was an 'electrode-less' discharge, ion laser lines in reactive gases such as chlorine could be made to oscillate, as well as the noble gases, without 'poisoning' the hot cathode used in conventional dc discharge lasers. A similar electrode-less discharge was demonstrated as a quasi-cw laser by using iron transformer cores and exciting the discharge with a 2.5 kHz square wave. Various microwave excitation configurations at 2.45 GHz and 9 GHz also resulted in ion laser oscillation. Techniques common to plasma fusion research were also studied. Argon ion laser oscillation was produced in Z-pinch and Θ-pinch discharges and also by high-energy (10–45 keV) electron beams. However, none of these latter techniques resulted in a commercial product, and all had efficiencies worse than the simple dc discharge lasers.

It is interesting that the highest-power output demonstrations were made in less than ten years after the discovery. Before 1970, 100 W output on the argon blue-green lines was demonstrated with dc discharges two meters in length. In 1970, a group in the Soviet Union reported 500 W blue-green output from a two-meter discharge with 250 kW of dc power input, an efficiency of 0.2%. Today, the highest output power argon ion laser offered for sale is 50 W output.

Manufacturers

More than 40 companies have manufactured ion lasers for sale over the past four decades. This field has now (2004), narrowed to the following:

Coherent, Inc.	http://www.coherentinc.com
INVERSion Ltd.	http://inversion.iae.nsk.su
JDS Uniphase	http://www.jdsu.com
Laser Physics, Inc.	http://www.laserphysics.com
Laser Technologies GmbH	http://www.lg-lasertechnologies.com
LASOS Lasertechnik GmbH	http://www.LASOS.com
Lexel Laser, Inc.	http://www.lexellaser.com
Melles Griot	http://lasers.mellesgriot.com
Spectra-Physics, Inc.	http://www.spectraphysics.com

Further Reading

Bridges WB (1979) Atomic and ionic gas lasers. In: Marton L and Tang CL (eds) *Methods of Experimental Physics, Vol 15: Quantum Electronics, Part A*, pp. 31–166. New York: Academic Press.

Bridges WB (1982) Ionized gas lasers. In: Weber MJ (ed.) *Handbook of Laser Science and Technology, Vol. II, Gas Lasers*, pp. 171–269. Boca Raton, FL: CRC Press.

Bridges WB (2000) Ion lasers – the early years. *IEEE Journal of Selected Topics in Quantum Electronics* 6: 885–898.

Davis CC and King TA (1975) Gaseous ion lasers. In: Goodwin DW (ed.) *Advances in Quantum Electronics*, vol. 3, pp. 169–469. New York: Academic Press.

Dunn MH and Ross JN (1976) The argon ion laser. In: Sanders JH and Stenholm S (eds) *Progress in Quantum Electronics*, vol. 4, pp. 233–269. New York: Pergamon.

Weber MJ (2000) *Handbook of Laser Wavelengths.* Boca Raton, FL: CRC Press.

Optical Fiber Lasers

G E Town, Macquarie University, NSW, Australia

N N Akhmediev, Australian National University, ACT, Australia

© 2005, Elsevier Ltd. All Rights Reserved.

Optical fiber lasers were first demonstrated in the 1960s, and since then have developed to become versatile optical sources with many desirable properties. Aided by developments in associated technologies, such as fiber design and fabrication methods, semiconductor pump diode technology, and fiber-coupled and in-fiber components such as Bragg grating filters, optical fiber lasers now compete with other laser technologies in many applications, from telecommunications to materials processing.

An optical fiber laser is fundamentally an optical oscillator, which converts input pump power to coherent optical output power at one or more well-defined wavelengths. Optical oscillators require two basic elements: optical gain, and optical feedback. For sustained oscillation to occur the round-trip gain in the laser cavity must be unity, and the round-trip phase a multiple of 2π. In optical fiber lasers the optical gain is provided by an optical fiber amplifier using one or a combination of fundamental physical processes, e.g., stimulated emission, stimulated scattering, or nonlinear parametric processes. Early fiber amplifiers used stimulated Raman scattering to produce optical gain; however, rare-earth-doped fiber amplifiers, in which gain is provided by stimulated emission, are now more common. The reader is referred to **Optical Amplifiers:** Erbrium Doped Fiber Amplifiers for Lightwave Systems, for more details on doped fiber amplifiers, and to **Scattering:** Stimulated Scattering, **Nonlinear Optics, Applications:** Raman Lasers, **Optical Parametric Devices:** Optical Parametric Oscillators (Pulsed), and **Scattering:** Raman Scattering, for more details on stimulated scattering and parametric gain processes. Optical feedback may be provided in two fundamental ways, e.g., by using a closed ring of fiber, or from reflections from nonuniformities and discontinuities in the waveguide such as in Bragg grating filters or at fiber ends. The reader is referred to **Fiber Gratings** for more details on fiber Bragg gratings.

The main advantages of optical fiber lasers are derived from the confinement of the pump and signal in a small optical waveguide. In contrast with bulk lasers, the pump intensity in the fiber waveguide is largely independent of the laser length, resulting in large amplifier gain and low laser threshold, even for gain media with small absorption and emission cross-sections. The large gain enables lossy elements such as optical fiber-coupled devices and bulk optical elements to be incorporated into the laser cavity, providing additional control over the optical signal being generated. To obtain a large gain optical fiber amplifiers must usually be relatively long (i.e., from several centimeters to many meters), and so the linear and nonlinear properties of the fiber waveguide can have a significant influence on the optical signal being generated, resulting in some interesting and useful phenomena, e.g., as in soliton fiber lasers. The reader is referred to **Fiber and Guided Wave Optics:** Optical Fiber Cables, for fiber-based components, to **Fiber and Guided Wave Optics**: Dispersion, Light Propagation, and Nonlinear Effects (Basics), for a review of the linear and nonlinear properties of optical fibers, and to **Solitons:** Soliton Communication Systems, and Temporal Solitons, for the theory and applications of temporal solitons.

Whilst optical fibers may be fabricated in a range of materials, including polymer and crystalline materials, most fibers and fiber lasers are currently made of silica containing rare-earth ion dopants – see **Fiber and Guided Wave Optics:** Fabrication of Optical Fiber, for details. Lasers in silica optical fiber have much in common with other glass-host lasers, including a wide range of potential pump and lasing wavelengths, and broadband absorption and gain due to homogeneous and inhomogeneous broadening of the lasing energy levels in the amorphous glass host. For example, erbium-doped amplifiers in alumino-silicate glass fibers at room temperature have lasing transitions with homogeneous and

Table 1 Commonly used pump and signal transitions in rare-earth doped fiber lasers

Rare earth dopant	*Pump wavelengths [nm]*	*Signal wavelengths [nm]*	*Excited state lifetime [ms]*	*Energy levels*
Praseodymium	480, 585	885, 1080	0.1	4
Neodymium	590, 800	920 (900–950)	0.5	3
		1060 (1055–1140)		4
Samarium	488	651	1.5	4
Holmium	455, 650, 1150	2040	0.6	3
Erbium	800, 975, 1480	1550 (1530–1610)	10	3
Thulium	790, 1210 (1060–1320)	1480 (1460–1520)		
		1850 (1650–2050)	0.3	3
Ytterbium	920 (840–980)	975	0.8	3
		1040 (1010–1160)		4



Figure 1 Example of a simple all-fiber optical oscillator. The rare-earth doped fiber provides optical gain, and the Bragg gratings provide narrowband optical feedback.

inhomogeneous linewidths of several nanometers, and can be optimized to provide around 30 dB gain over an 80 nm bandwidth centered around 1570 nm. The large gain-bandwidth is useful for achieving either wide tunability of the lasing wavelength and/or ultrashort pulse generation. Table 1 summarizes the most commonly used pump and signal transitions for a range of rare-earth dopants in silicate optical fibers.

Other desirable properties of silica fiber lasers include high efficiency, excellent thermal dissipation, substantial energy storage, high power capability, and compatibility with a wide range of optical fiber devices and systems. The characteristics of optical fiber lasers can be optimized for some very different applications, ranging from narrow linewidth and low-noise lasers to broadband pulsed lasers with high energy and/or high peak power. In the following sections the fundamentals of laser theory as applied to fiber lasers will be reviewed, highlighting the reasons underlying such versatility.

Fiber Laser Fundamentals

An example of a simple all-fiber laser is shown schematically in Figure 1. The laser contains the basic elements of optical gain (e.g., a rare-earth doped fiber amplifier) and optical feedback (e.g., a pair of Bragg grating filters). In the laser shown, the two Bragg gratings provide optical feedback only over a narrow range of wavelengths, which further restricts the range of possible lasing wavelengths. One grating must have a reflectivity less than unity to allow a proportion of the lasing signal to be coupled out of the laser cavity. At threshold, the gain in the amplifier exactly compensates for the loss in the output coupler.

The optical pump, typically from a semiconductor laser diode, is absorbed as is propagates along the fiber amplifier, e.g., by rare-earth ion dopants, which are raised to an excited state. The absorbed energy is stored and eventually emitted at a longer wavelength by either spontaneous or stimulated emission. Spontaneous emission produces unwanted noise and is associated with a finite excited state lifetime, whilst stimulated emission produces optical gain provided the gain medium is ‘inverted’, i.e., with more active ions in the upper lasing energy level than the lower lasing energy level. In practice some energy is also lost to nonradiative (thermal) emissions, e.g., in the transfer of energy between the pump and upper lasing energy levels. In an ideal gain medium the nonradiative transfer rate between the pump and upper lasing energy levels is much larger than the spontaneous or stimulated emission rates, so the inversion may usually be assumed to be independent of nonradiative transfer rates. Energy level diagrams for three- and four-level atoms are shown in Figure 2.

The local optical gain coefficient (i.e. power gain per unit length, in nepers^2) in a fiber amplifier is proportional to the local inversion, i.e., $g(z) \sim \sigma_S \Delta N(z)$, where σ_S is the emission cross-section at the



Figure 2 Energy level diagrams for three- and four-level laser transitions. *W* represents the probability of an optical transition per unit time associated with stimulated absorption or emission, and $1/\tau$ is the rate of spontaneous emission. Dotted lines represent nonradiative transitions (e.g., between the pump and upper lasing level).

signal wavelength, and $\Delta N(z)$ the difference in population density between the upper and lower lasing energy levels ($\Delta N > 0$ if the gain medium is inverted). The local inversion can be calculated by solving the rate equations including all stimulated and spontaneous transitions between the laser energy levels. The end-to-end amplifier power gain, $G = P_S(L_A)/P_S(0)$, in length L_A of amplifying fiber is then

$$G = \exp\left[\int_0^{L_A} g(z)\,\mathrm{d}z\right] \qquad [1]$$

which in decibels is

$$G = 4.34\int_0^{L_A} g(z)\,dz$$

A large gain coefficient is desirable for amplification with minimal added noise (i.e., low noise figure), and a large gain per unit pump power is desirable for low threshold lasing. For a given gain medium the only factor usually accessible to control the inversion and hence gain is the pump rate, i.e., the rate at which pump energy is absorbed by the gain medium, which for an unbleached amplifier is proportional to pump intensity. For example, in an ideal four-level unsaturated laser medium with uniform pump intensity, the small signal gain is approximately

$$\int_0^{L_A} g(z)\,\mathrm{d}z \approx \sigma_S \frac{P_{\mathrm{Pabs}}\tau}{h\nu_P A} \qquad [2]$$

in which τ is the lifetime of the upper lasing level, P_{Pabs} is the pump power absorbed in the fiber amplifier with cross-sectional area A, h is Planck's constant, and ν_P is the pump frequency.

For a three-level laser under the same conditions, the small signal gain is

$$\int_0^{L_A} g(z)\,\mathrm{d}z \approx -\sigma_S N L_A + \sigma_S \frac{2P_{\mathrm{Pabs}}\tau}{h\nu_P A} \qquad [3]$$

in which the first term corresponds to ground state absorption of the signal, in which N is the dopant ion density, and the factor of 2 in the second term is due to the fact that in an ideal three-level system every absorbed pump photon increases the inversion, ΔN, by two. Equation [3] can be approximated by multiplying [2] by the factor $(\mathrm{P}_{\mathrm{Pabs}} - \mathrm{P}_{\mathrm{Psat}})/(\mathrm{P}_{\mathrm{Pabs}} + \mathrm{P}_{\mathrm{Psat}})$, where $P_{\mathrm{Psat}} = h\nu_P A/(\sigma_P \tau)$ is the pump power which must be absorbed to reduce the pump absorption coefficient to half its unpumped value (or the signal absorption coefficient to zero), and σ_P is the pump absorption cross-section. Unlike four-level lasers in which gain is available as soon as pump power is applied, three-level lasers require half the active ions to be excited before the inversion becomes positive and gain is produced.

The main advantages of optical fiber amplifiers are now clear; in an optical fiber waveguide the light is confined in a very small cross-sectional area, typically less than ten microns diameter. Consequently even a small coupled pump power can have a large intensity and produce a large gain coefficient, or low laser threshold. Even if the pump absorbed per unit length in the fiber amplifier is small (e.g., due to low dopant concentration or low absorption coefficient), this can often be compensated by using a long length of fiber with small intrinsic loss. Furthermore, rare-earth dopants have relatively long metastable state lifetimes, τ, which further assists in producing a large inversion throughout the fiber, and hence large overall gain or low lasing threshold, even at low pump powers. For example, a typical four-level neodymium doped fiber amplifier providing gain at $\lambda_S = 1.06\ \mu\mathrm{m}$, pumped at $\lambda_P = 0.8\ \mu\mathrm{m}$, with core diameter $7\ \mu\mathrm{m}$, $\tau = 0.5$ ms, $\sigma_S = 1.4\times 10^{-20}\ \mathrm{cm}^2$, and $\sigma_P = 23\times 10^{-21}\ \mathrm{cm}^2$, could theoretically provide a small signal gain of 0.3 dB for every milliwatt of absorbed pump power.

Whilst the above analysis highlights the main advantages of fiber amplifiers, it is approximate in a number of respects. For example, eqns [2] and [3] assume both pump and signal have a uniform intensity distribution across the gain medium, and completely overlap. In single mode optical fibers the intensity distribution across the fiber core is not uniform but approximately Gaussian, with a width and effective area that depends on the numerical aperture of the waveguide and the wavelength. Consequently the overlap of the pump and signal beams with the doped fiber core and with each other is less than 100%, and the pump and signal intensities are higher in the center of the fiber than at the core-cladding boundary. The nonuniform distribution of pump and signal beams slightly modifies both the gain efficiency and gain saturation behavior (i.e., the dependence of gain on signal power) in fiber amplifiers. More accurate analysis would also take into account factors such as the rare-earth dopant distribution (which may not be uniform), the variation of pump and signal intensities along the fiber, spectral variation in the absorption and emission cross-sections, spatial and spectral hole-burning in the gain medium, degeneracies in the energy levels, excited state absorption and other loss mechanisms, temperature, and spontaneous emission noise.

Continuous Wave Fiber Lasers

The ideal continuous wave (cw) laser converts input pump power with low coherence to a highly coherent optical output signal which is constant in amplitude and wavelength, with the spectral purity of the output (i.e., linewidth) limited only by cavity losses. Practical continuous wave lasers may be characterized by four parameters: the pump power required for the onset of oscillation (i.e., threshold); the conversion efficiency of pump to signal power above threshold; the peak wavelength of the optical output; and the spectral width of the optical output. Continuous wave fiber lasers often have a low threshold, high efficiency, and narrow linewidth relative to other types of laser. Output powers approaching 100 watts have been achieved using specialized techniques.

The threshold power is determined by the total cavity loss and gain efficiency (i.e., gain per unit of absorbed pump power) of the fiber amplifier. For example, for the laser shown in Figure 1 the internal losses are minimal, and the pump power required to reach threshold may be calculated by setting the product of the round-trip small-signal gain, and the output mirror reflectivity, G^2R, equal to unity. For the laser configuration shown in Figure 1, and using eqns [1] and [2] for a four-level laser, the pump power which must be absorbed in the amplifier for the laser to reach threshold is

$$P_{\mathrm{th}} = \alpha_{\mathrm{cav}} L_{\mathrm{C}} \frac{h\nu_{\mathrm{P}} A}{\sigma_{\mathrm{S}} \tau} \qquad [4]$$

in which L_{C} is the cavity length, and $\alpha_{\mathrm{cav}} = \alpha_{\mathrm{int}} + \frac{1}{2} L_{\mathrm{C}} \ln(1/R)$ is the total cavity loss per unit length, comprising both internal losses, α_{int}, and outcoupling losses through a mirror with reflectivity R. For example, if the internal losses were negligible and the transmittance, $T = 1 - R$, of the output reflector in the laser shown in Figure 1 was 50% (i.e. 3 dB), and the other fiber parameters were the same as above (i.e. $G = 0.3$ dB/mW), then the laser threshold would be 5 mW. In three-level fiber lasers ground state absorption of the signal is usually the dominant loss mechanism which must be overcome before a net gain is produced, and hence the threshold of three-level lasers is given approximately by eqn [4] with $\alpha_{\mathrm{int}} = \sigma_{\mathrm{S}} N L_{\mathrm{A}} 2 L_{\mathrm{C}}$, and increases with amplifier length. In either case the pump power required at the input of the laser to reach threshold, $P_{\mathrm{P}}(0)$, may be approximated using the relation $P_{\mathrm{Pabs}} = P_{\mathrm{P}}(0) - P_{\mathrm{P}}(L_{\mathrm{A}}) \approx P_{\mathrm{P}}(0)[1 - \exp(-\sigma_{\mathrm{P}} N L_{\mathrm{A}})]$.

For either three- or four-level lasers pumped above threshold, the inversion of the gain medium remains at its threshold level as the internal round-trip gain must remain unity; however a coherent optical output signal at the peak emission wavelength grows from noise until its amplitude is limited by saturation of the amplifier gain. Provided the output coupling loss is not too large (e.g., $T < 60\%$) such that the total signal intensity is constant along the whole length of the fiber amplifier, it can be shown that changes in pump power above threshold cause a proportional change in the signal power coupled out of the Fabry–Perot cavity in one direction, P^{+}_{Sout}, i.e.

$$P^{+}_{\mathrm{Sout}} = \frac{(1-R)}{\delta_0} \frac{\nu_{\mathrm{S}}}{\nu_{\mathrm{P}}} (P_{\mathrm{Pabs}} - P_{\mathrm{th}}) \qquad [5]$$

in which $\delta_0 = 2\alpha_{\mathrm{int}} L + \ln 1/R$ represents the total round-trip loss at threshold. The relationship between absorbed pump power and output signal power is shown schematically in Figure 3. The constant of proportionality is known as the slope or conversion efficiency, defined as $\eta_{\mathrm{S}} = P_{\mathrm{Sout}}/(P_{\mathrm{Pabs}} - P_{\mathrm{th}})$. In both three- and four-level fiber lasers with small intrinsic losses $\alpha_{\mathrm{int}} \approx 0$, and small output coupling (i.e., $R \approx 1$), the slope efficiency can approach the intrinsic quantum efficiency, $\nu_{\mathrm{S}}/\nu_{\mathrm{P}}$.

Sustained oscillation can only occur if the optical path length around the cavity is an integral number of wavelengths. Wavelengths satisfying this condition are called ‘modes’ of the cavity, determined by



Figure 3 Representative plot of laser output power versus absorbed pump power.

$2nL_C = m\lambda_0$, where n is the effective refractive index seen by light propagating in the cavity, L_C is the cavity length, m is an integer, and λ_0 is the free-space wavelength. In Figure 1, the cavity length comprises the amplifying fiber, and two Bragg grating filters which may be regarded as having an effective length (i.e., less than the actual grating length) which depends on the grating characteristics. In fiber lasers the cavity is typically between several centimeters and many meters in length, hence there are usually very many potential lasing modes within the gain-bandwidth of the amplifying medium. For example, in the Fabry–Perot cavity of Figure 1, if the cavity length was 5 meters, the mode spacing would be $\nu_{m+1} - \nu_m = c/(2nL_C) = 20$ MHz, i.e. orders of magnitude less than the bandwidth of the optical amplifier.

Ideally the first mode to reach threshold would determine the laser output wavelength and the spectral width, or linewidth, of the laser output would be $\Delta\nu_L = h\nu/(2\pi\tau_C^2 P_{\text{Sout}})$, in which τ_C is the lifetime of photons in the cavity and determined by cavity losses, including outcoupling, and given by $\tau_C = t_R/\varepsilon$, where t_R is the cavity round trip time and ε the fractional energy loss in the cavity per round trip. In practice, the linewidth is usually significantly larger than the latter theoretical limit due to transient lasing of different modes within the bandwidth of the optical amplifier and environmental perturbations to the fiber cavity. Fiber amplifiers typically have a large homogeneously broadened gain-bandwidth, and being long and flexible are susceptible to acoustic and thermal perturbations, hence care must be taken to physically stabilize the laser cavity to minimize both mode-hopping and the output linewidth.

Whilst the CW laser shown in Figure 1 has the advantage of simple construction, it would not be ideal for narrow linewidth CW generation. The reason is that counterpropagating waves in the Fabry–Perot cavity form a standing wave, i.e., in which the local signal intensity varies due to interference between forward and backward propagating waves. The standing wave can cause spatial hole-burning in the gain medium (i.e., a spatial variation in gain, linked to the spatial variation in intensity) which in turn reduces the average gain for the lasing mode and promotes mode-hopping and hence spectral broadening of the output.

A preferable arrangement for many fiber lasers is a traveling wave laser, which can be realized using a ring configuration, as shown in Figure 4. In this configuration the optical isolator ensures unidirectional lasing and avoidance of spatial hole-burning. Additional components in the cavity can include a wavelength selective coupler (WSC), i.e., to couple the pump wavelength into the laser cavity whilst not coupling the signal wavelength out, and a narrowband filter (e.g. a small Fabry–Perot resonator) to further stabilize and/or narrow the lasing linewidth. Rare-earth doped fiber lasers with similar cavity configurations have been realized with linewidths of approximately 10 kHz, limited by environmental (e.g., acoustic) perturbations.



Figure 4 Schematic of a traveling wave laser, useful for low noise continuous wave oscillation. The wavelength selective coupler (WSC) is required to couple pump power into the laser cavity without coupling signal out.

Pulsed Fiber Lasers

There are two main types of fiber laser useful for generating short high-power pulses: *Q*-switched lasers, and mode-locked lasers. *Q*-switched fiber lasers are useful for generating large energy pulses (e.g., microjoules) with very high peak power (e.g., kilowatts) with relatively long pulse duration (e.g., tens of nanoseconds), whilst mode-locked fiber lasers are typically capable of generating ultrashort pulses (e.g., sub-picosecond) with moderate energy (e.g., nanojoules) and moderate-to-high peak power (e.g., tens of watts). Pulsed lasers typically produce less average output power than CW lasers (e.g., up to about 10 W). Both types of pulsed laser typically contain an element for loss modulation within the cavity, however the pulse generation mechanisms are very different.

Q-switched lasers operate by rapid switching of the cavity loss. Whilst the intracavity loss is high and the laser below threshold, energy is transferred from the pump to the lasing medium. The long excited state lifetime and small emission cross-sections of rare-earth dopants assists greatly in the latter process, so that a significant amount of energy can be stored in long fiber amplifiers before amplification of spontaneous emission noise begins to deplete the inversion. After the gain medium is fully inverted the cavity loss is suddenly reduced, and the laser is taken well above threshold, resulting in a rapid build-up of noise and the formation of a pulse which ideally extracts all the stored energy within a few round-trips in the laser cavity. The situation is shown schematically in Figure 5.



Figure 5 Pulse generation in a *Q*-switched laser. Initially the intracavity loss is high, the laser remains below threshold, and the inversion of the gain medium increases. When the intracavity loss is suddenly reduced, the laser goes well above threshold and spontaneous emission noise is rapidly amplified into a large pulse which extracts much of the energy previously stored in the gain medium.

An upper limit on the pulse energy obtainable from a *Q*-switched laser may be determined by assuming all active ions in the laser cavity are excited before the pulse is generated (i.e., at the time the cavity *Q* is switched high), that no ions remain excited immediately after the pulse is generated, and that the pulse generated is much shorter than the time required to pump all the ions into their excited state. The energy stored in the gain medium, and hence the maximum conceivable pulse energy, would then be $E = h\nu_S NV$, where N is the density of active ions and V is the cavity volume. For example, a typical erbium-doped fiber laser of length 10 m and dopant density $N = 10^{19}$ ions/cm in a single-mode fiber with core diameter 7 μm could ideally store up to 500 μJ of energy.

Two things limit the maximum inversion and energy storage achievable in practice: spontaneous emission noise (due to the finite excited-state lifetime) which is amplified and depletes the inversion, and unwanted feedback (e.g., due to the finite extinction ratio of the *Q*-switching element) which results in cw lasing which limits the inversion. Following from eqns [1] and [2], the unidirectional gain per unit of stored energy in a fiber laser may be expressed as $G = 4.34/(A_{core}F_{sat}) = 4.34/E_{sat}$ decibels per joule, where $F_{sat} = h\nu_S/\sigma_S$ is the saturation fluence, and $E_{sat} = A_{sat}F_{sat}$ is the saturation energy. For example, if the maximum gain achievable before the onset of cw lasing was 30 dB (i.e., even when the *Q*-switch introduces a large loss), then the maximum energy storable in the gain medium would be $E = 6.9E_{sat}$. For the same erbium-doped fiber parameters as used in the previous paragraph, the maximum storable energy would be $E \approx 70$ μJ.

Only a proportion of the energy stored in the gain medium may usually be converted into a *Q*-switched output pulse. The actual *Q*-switched pulse energy, duration, and peak power can be calculated by solving the rate equations for the photon flux and the population difference between the lasing energy levels in the gain medium. The equations must usually be solved numerically, however assuming the *Q* changes much more rapidly than the pulse build-up time, which is in turn much shorter than the time taken for a significant change in inversion to either pumping or spontaneous emission, the pulse parameters may be approximated analytically and are found to be determined by only two parameters, i.e., the population inversion (or stored energy) just before *Q*-switching, and the lifetime of photons within the cavity, τ_C, defined previously.

Under the conditions described above, standard analysis gives the *Q*-switched pulse duration as

$$T_P \approx \frac{\tau_C(r-1)}{(r-1-\ln r)} \qquad [6]$$

where r is the ratio of the inversion just before *Q*-switching (low *Q*) to the threshold inversion for cw lasing after *Q*-switching (*Q* high). In fiber lasers the gain can be very high, hence it is common for $r \gg 1$ and almost all available energy stored in the gain medium is extracted as a *Q*-switched laser pulse. The *Q*-switched pulse duration is then determined primarily by the cavity lifetime; shorter pulses can be obtained only by shortening the laser cavity and/or increasing the cavity loss. For example, for a 10 m long ring cavity in which the sum of cavity and outcoupling losses is 10 dB and $r \gg 1$, the pulse duration would be $T_P\tau_C = 22$ ns.

The exact proportion of energy stored in the gain medium that is converted to a *Q*-switched pulse depends on the number of energy levels in the lasing medium, the degeneracy of those levels, and the rate of nonradiative energy transfer between those levels. For example, for an ideal three-level gain medium (e.g., erbium dopant) with no internal cavity losses the maximum available Q-switched pulse energy is half the stored energy, or $E_{\text{pulse}} = E/2$. It can be shown that the peak of the output pulse power occurs as the inversion decreases through threshold, and may be approximated by dividing the pulse energy by the pulse duration. Even for moderate pulse energies the peak power is potentially very high. For the erbium-doped fiber laser parameters used previously, the peak pulse power would be approximately 1600 W, i.e., sufficient to cause significant spectral broadening of the output wavelength due to stimulated Raman scattering and other nonlinear effects within the optical fiber.

Mode-locked lasers generate optical pulses by forcing many cavity modes to be locked in phase. As per Fourier theory, the pulse repetition rate is related to the spacing of the lasing modes, and the more modes that add coherently, the greater the pulse bandwidth and the shorter the transform-limited pulse duration. For example, the relationship between mode spacing and pulse repetition rate, and between the spectral and temporal envelopes of a train of Gaussian pulses is shown in Figure 6.

In mode-locked lasers a nonlinear or time-varying element must be present which synchronously modulates the optical signal circulating in the cavity in amplitude or phase at a frequency which is a harmonic of the cavity mode spacing. There are two main methods of mode locking:

(i) active mode locking (e.g., by an electro-optic modulator), in which amplitude or phase modulation is driven by an external source; and
(ii) passive mode locking (e.g., by a fast or slow saturable absorber), in which an element with nonlinear gain or loss responds to the optical signal in the laser cavity itself.



Figure 6 Schematic showing the Fourier-transform relationship between an infinite train of Gaussian pulses and the lasing modes in a mode-locked laser. The temporal and spectral widths are measured full width at half the maximum intensity.

In both cases the modulation provided by the mode-locking element distributes energy between neighboring modes, effectively injection-locking them in phase. A variation of mode locking techniques often present in fiber lasers is soliton mode-locking, in which the active or passive modulation is weak, and a balance between nonlinearity and dispersion is the dominant process underlying pulse formation. Hybrid mode-locking techniques can also be used to combine the best aspects of different pulse-generation methods.

Whilst the latter frequency-domain view of mode locking is helpful, nonlinear effects are almost always significant in mode-locked fiber lasers, and hence the linear concept of a mode is not appropriate for detailed analysis. Hence it is usually preferable to describe pulse generation in mode-locked fiber lasers in the time domain; for stable operation the pulse at any point in the cavity must self-replicate after each round-trip, with the net effects of temporal and spectral loss, gain, dispersion and nonlinearity all canceling.

An optical pulse propagating in a fiber laser is usually described by a slowly varying complex envelope, $\Psi(z,t)$, where $|\Psi(z,t)|^2$ is the instantaneous power in a frame of reference moving at the pulse group velocity, and $\arg[\Psi(z,t)]$ is the instantaneous phase relative to the optical carrier. The various elements in the laser cavity, such as the passive fiber, optical fiber amplifier, filters, and mode-locking devices, each modify the complex pulse envelope as it propagates around the laser cavity.

For example, in the absence of other effects, group velocity dispersion (GVD) causes different wavelengths to travel at different velocities along the fiber, resulting in 'chirping' and temporal broadening of optical pulses by an amount proportional to the distance propagated. The effect can be described mathematically as the accumulation of a phase shift which is quadratic in frequency, i.e., $\Psi(z,\omega) = \Psi(0,\omega)\exp[i\beta_2\omega^2 z/2]$. Taking the derivative with respect to propagation distance, and using $\partial/\partial t = -i\omega$, the incremental change in the complex envelope with propagation distance is

$$\frac{\partial \Psi}{\partial z} = -\mathrm{i}\frac{\beta_2}{2}\frac{\partial^2 \Psi}{\partial t^2} \quad [7]$$

If the GVD parameter, β_2, is positive then long wavelengths propagate faster than shorter wavelengths, and the dispersion is called 'normal'. If the reverse is true, the dispersion is 'anomalous'. In standard single-mode step index optical fibers the dispersion passes through zero at wavelengths around 1300 nm, and is anomalous for longer wavelengths. It is often necessary to control the net dispersion in a fiber laser, and this can be done by incorporating specially designed fibers with wavelength-shifted or otherwise modified dispersion characteristics, or by using chirped Bragg grating reflectors.

Whilst silica is not commonly regarded as a nonlinear medium (i.e., in which the optical properties are a function of the intensity of light), in ultrashort pulsed fiber lasers the peak powers are usually such that nonlinear effects cannot be ignored. In silica the main nonlinearity is associated with the Kerr effect, and is readily observed as an intensity-dependent refractive index, i.e. $n = n_0 + n_2 I$, where the nonlinear index, n_2, is typically about $3 \times 10^{-20}\ \mathrm{m^2/W}$ in silica fibers. Other nonlinear effects related to the Kerr nonlinearity which can sometimes be important are cross-phase-modulation and four-wave mixing. In the absence of other effects, the nonlinear index results in self-phase modulation (SPM), or a phase shift in the optical carrier which is proportional to the instantaneous intensity of the signal. Mathematically, $\Psi(z,t) = \Psi(0,t)\exp[\mathrm{i}\gamma|\Psi(0,t)|^2 z]$, in which $\gamma = n_2\omega_0/(cA)$ is the nonlinear coefficient of the fiber, ω_0 is the radian frequency of the optical carrier, and A is the effective core area for the guided mode. The incremental change per unit length in the complex pulse envelope induced by self-phase modulation is then

$$\frac{\partial \Psi}{\partial z} = \mathrm{i}\gamma|\Psi|^2\Psi \quad [8]$$

For example, self-phase-modulation is used to realize a nonlinear switching element in the passively mode-locked laser cavity shown schematically in Figure 7. For obvious reasons the laser is called a 'figure-8' laser, though it is actually a ring laser into which a device known as a nonlinear amplifying loop-mirror (NALM) has been incorporated. The NALM acts as a fast saturable absorber, with transmittance dependent on the instantaneous optical intensity. The NALM operates as follows: light propagating through the optical isolator is divided equally into co- and counter-propagating waves in the loop-mirror on the right-hand side. The light propagating in a clockwise direction is amplified immediately, and propagates around the loop with high intensity, whilst the counter-clockwise propagating signal has a low intensity for most of its time in the loop. The difference in intensity means that the co- and counter-propagating waves experience different nonlinear phase shifts. When they are recombined at the coupler, high-intensity light is transmitted back into the ring, whilst low-intensity light is reflected back to the isolator, and lost. In this way the NALM provides both gain and a nonlinear transmittance which depends on the instantaneous power of the input, described by

$$T \approx G\left\{1 - \frac{1}{2}\left[1 + \cos\left(\frac{1}{2}\gamma L P_{\mathrm{in}} G\right)\right]\right\} \quad [9]$$



Figure 7 Schematic of a 'figure-8' fiber laser. The laser is passively mode-locked by the nonlinear amplifying loop mirror on the right, which acts as a fast saturable absorber, transmitting and amplifying high-power optical signals whilst reflecting low optical power signals.

in which G is the linear gain of the amplifier, and L the loop length, P_{in} is the input power, and T the ratio of transmitted power to input power. The nonlinear transmittance of the NALM promotes pulse formation and shortening in the laser cavity, and hence passively mode-locks the laser. The polarization controllers are to compensate for unwanted birefringence in the optical fiber, and to control the transmittance of the loop-mirror at low input powers. The fiber dispersion and nonlinearity, together with other factors, further influence the pulses generated in the laser, as described in the following paragraphs.

The combined effects of dispersion and self-phase-modulation can give rise to some interesting and useful physical phenomena. In lossless optical fibers, or fiber lasers in which loss is balanced by gain, pulse propagation is described by the nonlinear Schrödinger equation (NLSE), i.e., a nonlinear wave equation including the effects of both group velocity dispersion and intensity-dependent refractive index. The NLSE may be derived by combining eqns [8] and [9], i.e.

$$\mathrm{i}\frac{\partial \Psi}{\partial z} - \frac{\beta_2}{2}\frac{\partial^2 \Psi}{\partial t^2} + \gamma|\Psi|^2\Psi = 0 \qquad [10]$$

It can be shown that if the dispersion is anomalous ($\beta_2 < 0$) then for a particular shape of pulse envelope the distributed effects of dispersion and nonlinearity can exactly cancel, so $\partial\Psi/\partial z = 0$, and the pulse propagates without changing shape. Such pulses are called fundamental solitons, the solution for which is $\Psi(z,t) = \Psi_0 \operatorname{sech}(t/T_0)\exp[\mathrm{i}z/(2L_{\mathrm{D}})]$, in which the peak amplitude is $\Psi_0 = 1/\sqrt{\gamma L_{\mathrm{D}}}$, T_0 is the pulse width parameter, and $L_{\mathrm{D}} = T_0^2/\beta_2$ is known as the dispersion length. For example, in a standard silica fiber at $\lambda = 1.55\ \mu\mathrm{m}$, $\beta_2 \approx -20\ \mathrm{ps}^2/\mathrm{km}$ and $\gamma \approx 10\ \mathrm{W}^{-1}\mathrm{km}^{-1}$, hence a soliton with $T_0 = 1$ ps would have peak power 2 W and energy $E_0 = 2|\beta_2|/(\gamma T_0) = 4$ pJ. The energy of a soliton is quantized, in that pulses with initial energy between 0.5 and 1.5 times E_0 can evolve into a fundamental soliton during propagation. Consequently solitons behave somewhat like particles, and are robust even in the presence of significant perturbations. The pulses which form spontaneously in the figure-8 fiber laser have many of the properties of solitons.

Mode-locked fiber lasers, such as that shown in Figure 7, can often be described by a generalized nonlinear Schrödinger equation, in which extra terms are included in eqn [10] to account for the average effects of an excess linear gain or loss, nonlinear gain and loss (e.g., due to a saturable absorber), spectral filtering, and temporal modulation, etc. Assuming the effects of the added elements can be regarded as distributed over the length of the cavity rather than lumped, such that the envelope of any pulse generated in the laser does not change shape significantly as it propagates around the cavity, then the master differential equation describing propagation of an optical signal within a fiber laser which is passively mode-locked by a fast saturable absorber can be written

$$\mathrm{i}\frac{\partial U}{\partial \zeta} + \left(\frac{D}{2} - \mathrm{i}\beta\right)\frac{\partial^2 U}{\partial \tau^2} + (1-\mathrm{i}\varepsilon)|U|^2 U$$
$$= \mathrm{i}\delta U - (\nu - \mathrm{i}\mu)|U|^4 U \qquad [11]$$

Equation [11] is known as the Ginzburg–Landau equation, which describes propagation of the normalized pulse envelope, $U(\zeta,\tau)$, as a function of delayed time, τ, and normalized distance, ζ, and under the combined influence of group velocity dispersion ($D = \pm 1$ for anomalous or normal group velocity dispersion, respectively), dispersion due to band-limiting by amplification in a homogeneously broadened gain medium ($\beta > 0$), nonlinear refractive index, nonlinear gain or loss (ε), linear gain (δ), and quintic terms, μ and ν, which if less than zero relate to saturation of the nonlinear gain and refractive index, respectively. Note that if the right-hand side of the equation is set to zero, and $\varepsilon = \beta = 0$, then the equation reduces to the normalized form of the nonlinear Schrödinger equation. Stable pulses generated within the laser are solutions of the above equation with $\partial U/\partial \zeta = 0$, and hence the effect of all terms must balance. Consequently it is possible for stable pulses to be generated even with normal dispersion in the cavity, though the pulses are then generally strongly chirped, and have an envelope which is approximately Gaussian shaped rather than the hyperbolic secant shape expected with anomalous dispersion. Stable soliton-like pulses can be found by solving the Ginzburg–Landau equation for specific ranges of parameters. There are many numerical solutions, and some analytical solutions, but in general the dynamics of pulse formation and propagation in passively mode-locked fiber lasers can be quite complex, and for some sets of parameters remarkable and unexpected numerical solutions can be found. One such example which has been observed experimentally is the 'exploding' soliton, which unlike the usual soliton is periodically unstable, as shown in the plot of pulse evolution in Figure 8.

Other Fiber Lasers

The lasers discussed in the previous sections are indicative of the main types of fiber laser in terms of their output characteristics; however it should be



Figure 8 Two periods of the evolution of an exploding soliton found by numerical solution of the quintic Ginzburg–Landau equation with normalized parameters $\varepsilon = 1.0$, $\delta = 0.1$, $\beta = 0.125$, $\mu = 0.1$, and $\nu = 0.6$. The process never repeats itself exactly in successive 'periods'; however the pulse always returns to the same shape. Such solutions cannot be found in analytic form; nevertheless they are as common as stationary pulse solutions and exist for a wide range of parameters.

noted that there is a wide range of other fiber laser configurations with similar behaviors incorporating a variety of other fiber and/or bulk elements. For example, specially designed fibers in which the pump and/or signal has a large cross-sectional area can be used to realize fiber lasers with a high output power, comparable to that in many bulk laser systems. Linear and/or nonlinear processing of the output of fiber lasers can be used to increase their peak output power and/or pulse energy, or to change their output wavelength (i.e., by harmonic generation) from that achievable in the laser cavity itself. In mode-locked fiber lasers it is now common to include passive semiconductor devices which provide a slow saturable absorber action to initiate and stabilize soliton mode-locking.

It should also be noted that there are a number of fiber lasers which generate optical outputs using different or modified physical processes compared to those described in previous sections. For example, it is possible to realize up-conversion fiber lasers in which the output wavelength is shorter than the pump wavelength, multiwavelength fiber lasers (pulsed and cw) which produce outputs at several wavelengths simultaneously, and lasers with limited output coherence such as chaotic fiber lasers and broadband superfluorescent sources, etc. Lastly, whilst the rare-earth doped fiber lasers dealt with in previous sections have some very desirable properties, it should be recognized that optical fiber lasers based on other optical gain mechanisms, such as stimulated scattering and parametric effects, can also be realized (e.g., as in fiber Raman lasers, and fiber Brillouin lasers). In the latter cases the lasing wavelength is limited only by available pump wavelengths. The reader is referred to the references in the Further Reading for information on the wide range of fiber lasers that are possible in practice.

List of Units and Nomenclature

Absorption cross-section	σ_a	$[\mathrm{m}^{-2}]$
Amplifier length	L_A	[m]
Area	A	$[\mathrm{m}^2]$
Cavity length	L_C	[m]
Complex amplitude	Ψ	$[\mathrm{W}^{0.5}]$
Dispersion length	L_D	[m]
Distance	z	[m]
Emission cross-section	σ_e	$[\mathrm{m}^{-2}]$
Frequency	v	[Hz]
Gain coefficient	g	$[\mathrm{m}^{-1}]$
Group velocity dispersion	β_2	$[\mathrm{s}^2\mathrm{m}^{-1}]$
Inversion ratio	r	
Lifetime	τ	[s]
Loss coefficient	α	$[\mathrm{m}^{-1}]$
Nonlinear coefficient	γ	$[\mathrm{m}^{-1}\mathrm{W}^{-1}]$
Nonlinear refractive index	n_2	$[\mathrm{m}^2\mathrm{W}^{-1}]$
Number density	N	$[\mathrm{m}^{-3}]$
Power gain	G	
Pump power	P_P	[W]
Pump wavelength	λ_P	[m]
Reflectivity	R	
Saturation energy	E_{sat}	[J]
Saturation fluence	F_{sat}	$[\mathrm{J.m}^{-2}]$
Signal power	P_S	[W]
Signal wavelength	λ_S	[m]
Threshold power	P_{th}	[W]

See also

Fiber and Guided Wave Optics: Dispersion; Fabrication of Optical Fiber; Light Propagation; Nonlinear Effects (Basics); Optical Fiber Cables. **Fiber Gratings**. **Lasers:** Up Conversion Lasers. **Nonlinear Optics, Applications:** Raman Lasers. **Optical Amplifiers:** Basic Concepts; Erbrium Doped Fiber Amplifiers for Lightwave Systems. **Optical Parametric Devices:** Optical Parametric Oscillators (Pulsed). **Solitons:** Temporal Solitons. **Scattering:** Raman Scattering; Stimulated Scattering. **Ultra-Fast Laser Techniques:** Generation of Femtosecond Pulses.

Further Reading

Agrawal GP (2001) *Nonlinear Fiber Optics*, 3rd edn. San Diego, CA: Academic Press.

Agrawal GP (2001) *Applications of Nonlinear Fiber Optics*. San Diego, CA: Academic Press.

Akhmediev NN and Ankiewicz A (1997) *Solitons*. London: Chapman and Hall.

Becker PC, Olsson NA and Simpson JR (1999) *Erbium-Doped Fiber Amplifiers: Fundamentals and Technology.* San Diego, CA: Academic Press.

Desurvire E (1994) *Erbium-Doped Fiber Amplifiers: Principles and Applications*. New York: Wiley.

Digonnet MJF (ed.) (2001) *Rare-Earth-Doped Fiber Lasers and Amplifiers,* 2nd edn. New York: Marcel Dekker.

Duling IN (ed.) (1995) *Compact Sources of Ultrashort Pulses*. Cambridge, UK: Cambridge University Press.

France PW (ed.) (1991) *Optical Fibre Lasers and Amplifiers*. Glasgow, UK: Blackie.

Jeunhomme LB (1990) *Single-Mode Fiber Optics: Principles and Applications*, 2nd edn. New York: Dekker.

Kashyap R (1999) *Fiber Bragg Gratings*. San Diego, CA: Academic Press.

Siegman AE (1986) *Lasers*. Oxford, UK: Oxford University Press.

Weber MJ (ed.) (1995) *CRC Handbook of Laser Science and Technology.* Boca Raton, FL: CRC Press.

Organic Semiconductors and Polymers

G A Turnbull, University of St Andrews, Fife, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Organic semiconductors, and conjugated polymers in particular, are emerging as an interesting new class of visible laser media. The polymers are electroluminescent, broadband visible emitters and exhibit large optical gain coefficients. As plastics, they are amenable to simple processing, and can be shaped into complex structures. This combination of photonic, electronic, and processing properties make these materials extremely well suited to forming novel microlasers, with future prospects as inexpensive, plastic diode lasers operating throughout the visible spectrum.

Conjugated Polymers

Plastics are widely used in low-cost optical components such as lenses, diffraction gratings, optical fibers, and adhesives. Their common use derives from a combination of qualities: good optical transmission, a wide range of mechanical properties and simple fabrication via molding: extrusion or solution processing. Functional optical polymers, including liquid crystals and photorefractives, have also been widely applied to polarization control and for nonlinear- and electro-optics. Conjugated polymers are a remarkable class of functional plastics that exhibit some unusual properties. Firstly, they are plastics that can conduct electricity; and in fact are electrically semiconducting. Secondly, they are plastics that can be stimulated either optically or electrically to emit visible light.

These two unusual properties derive from a particular chemical structure specific to this family of plastics. In all conjugated polymers, the backbone of the molecule is a chain of carbon atoms joined by alternating single and double covalent bonds. The simplest example is illustrated in Figure 1a, which shows the chemical structure of the polymer poly(acetylene). Structural integrity of the polymer is provided by a string of single σ-bonds between adjacent carbon atoms. The additional bonding electrons in the double bonds are located in π-orbitals oriented perpendicular to the polymer chain. Adjacent π-orbitals overlap, and their electrons can be widely delocalized along the polymer backbone. The delocalized electrons can move relatively freely along the chain, giving the electronic properties of the material. The π-orbitals can be transformed between bonding and anti-bonding states by the absorption or emission of light, leading to strong optical transitions. While poly(acetylene) is a very inefficient light emitter, other conjugated polymers, notably those that include phenyl rings in the backbone (Figure 1b–d), can be highly emissive. Photoluminescence quantum



Figure 1 Chemical structures of several conjugated polymers. (a) poly[acetylene]; (b) poly[2-methoxy-5-(2′-ethylhexyloxy)-1,4-phenylene vinylene], (MEH-PPV); (c) ladder-type poly[1,4-phenylene], (MeLPPP); (d) poly[9,9-dioctylfluorene], (PFO).

efficiencies, approaching unity in solution and as high as 60% in the semiconducting solid state, have been realized.

Organic Semiconductor Lasers

While organic dye lasers have been widely used since the mid-1960s, the history of organic semiconductor lasers is much more recent. Other than a few early observations of lasing in molecular crystals in the 1970s by Karl and others, the field of organic semiconductor lasers began in earnest following the related discovery in 1990 by Burroughes *et al.* of electroluminescence in a conjugated polymer. In 1992, Moses demonstrated lasing for the first time in a solution of the conjugated polymer MEH-PPV (Figure 1b). However, it was another four years – once material synthesis had been sufficiently refined – before stimulated emission and then true laser action were observed in polymers in the semiconducting solid state. In the following year the first demonstrations were made of dye-doped small molecular semiconductor lasers. Since that time, there has been a great growth in interest in the field with an average of ~30 research papers per year. Further details of the development of the field of organic semiconductor lasers can be found in the Further Reading.

So what are the particular properties of conjugated polymers that have stimulated interest in developing organic semiconductor lasers? Firstly these materials are broadband visible emitters. Through appropriate chemical design, their emission can be tuned throughout the visible spectrum, from 400 nm to 700 nm (Figure 2). The polymers exhibit large optical gain coefficients, because the optical transitions are dipole-allowed. Compared with small molecular dyes, polymers exhibit a relatively low degree of self-absorption of the emitted light, and much reduced quenching of the luminescence with increased concentration. This means that it is possible to work with much higher chromophore densities than conventional laser dyes, which is advantageous for achieving very low threshold lasing in extremely compact resonators. Furthermore, because these materials are semiconducting, they have the potential for direct electrical excitation. This could lead to semiconductor diode lasers operating throughout the visible spectrum and, in particular, in the blue and green spectral bands where currently there are few commercially viable inorganic semiconductor sources. Finally, these materials are plastics and so are amenable to simple processing, and can be shaped and structured into complex feedback resonators.



Figure 2 Photoluminescence spectra of three commonly used conjugated polymers; chemical structures inset.

Organic Semiconductor Gain Materials

A great advantage of organic laser media is that a very wide range of materials can be readily synthesized, and through minor changes in the molecular structure one can relatively simply tune the emission properties of the material. Many different organic semiconductors have been applied as lasers, though they fall into three major categories. These are conjugated polymers, dye-doped small molecular semiconductors, and molecular single crystals. Conjugated polymers make up the most diverse materials set, most notably including derivatives of poly(paraphenylene-vinylene), poly(paraphenylene), and poly(fluorene) (Figure 1b–d). The second category comprises small molecular semiconductors that are co-evaporated under vacuum with a dopant laser dye. In this blend of materials, the organic semiconductor functions simply as an energy transfer host for the emitting dye molecules. In the third category are organic single crystals, including materials such as polyacenes and thiophene oligomers. These materials have the advantage of having the highest electrical mobilities of any organic semiconductors, which is important for electrical excitation. However, they can be demanding to grow into high-quality single crystals, and so lack the key processing advantages of the other families of organic semiconductors.

Figure 3a shows a typical exciton energy level structure of a semiconducting polymer. Similar to a conventional laser dye, the energy levels comprise a manifold of singlet states and a manifold of triplet states, each with vibrational sublevels. The laser transition occurs from the bottom of the first excited singlet state S_1 to the vibronic overtones of the ground



Figure 3 (a) Generic energy level structure and optical transitions of a conjugated polymer. S_N refers to the Nth singlet state; T_N refers to the Nth triplet state; ISC: intersystem crossing. (b) Absorption and photoluminescence spectra of the polymer MEH-PPV.

state S_0, so forming a classic 4-level laser system. The optical transition is dipole-allowed and so has a high oscillator strength. As a result, conjugated polymers typically exhibit simulated emission cross-sections in the range $10^{-16}\,\mathrm{cm}^2$ to $10^{-15}\,\mathrm{cm}^2$, while the population inversion lifetime is as short as a few hundred picoseconds.

There are, however, several other transitions that can compete with the stimulated emission process. There can be excited-state absorption from the S_1 singlet state into higher-lying singlet states. Additionally intersystem crossing from the S_1 state to the lowest excited triplet state T_1 can subsequently lead to excited triplet absorption. Other processes in the polymer can also impede the stimulated emission. Firstly, charged excitations can exhibit absorption bands that overlap with the emission. Secondly, at high excitation densities, exciton–exciton annihilation can significantly deplete the excited states available for stimulated emission. Ultimately, singlet–singlet annihilation is the limiting factor for the maximum excitation density possible, and while polymer films can have a repeat-unit density of $\sim 10^{21}\,\mathrm{cm}^{-3}$, the excited state density is typically limited to around $10^{18}\,\mathrm{cm}^{-3}$. In many materials this is not restrictive on achieving optical gain because stimulated emission can occur at densities of $10^{17}\,\mathrm{cm}^{-3}$ and below.

An important factor that distinguishes the photophysics of semiconducting polymers from conventional laser dyes is an internal process of exciton migration between the absorption and emission of a photon. Excitations are confined to short straight sections of the polymer between kinks or twists in the chain. These straight sections, or 'sites', are typically a few repeat units in length, though there is a statistical spread of site lengths in any given material. When formed, excitons tend to hop to the longest, lowest-energy, sites before emitting a photon. The exciton migration process has two effects. First, it means the emission takes place from a subset of the chain segments, resulting in a lower degree of inhomogeneous broadening of the emission spectrum (vibronic peaks are better resolved than in absorption (see Figure 3b)). Second, the peaks of the absorption and emission spectra tend to be widely separated in wavelength, reducing the level of self-absorption at the lasing wavelength.

As mentioned above, blending materials is a particularly attractive approach towards further reducing self-absorption in organic semiconductor lasers. In such systems, a narrow bandgap dopant chromophore is blended with a concentration of 1–2% in a wider bandgap semiconducting host. Emission from the host is strongly quenched via nonradiative Förster energy transfer to the guest molecule. The blended material exhibits an absorption profile that is dominated by the host absorption, while the emission profile is almost completely that of the guest dopant. By strongly separating the emission peak from the absorption edge of the host, it is possible to achieve a substantially reduced (by perhaps an order of magnitude or more) residual absorption coefficient at the lasing wavelength. In doing so, the combined material acts much more like an ideal 4-level laser medium and can thereby have substantially lower pump thresholds for stimulated emission.

Measuring Gain

The dynamics of the excited state population in semiconducting polymers have been widely studied using femtosecond transient absorption experiments.

This is a pump–probe technique in which the transmission of the broadband probe pulse is compared in the presence and absence of a pump pulse that excites molecules into the first excited state. Such measurements have the time resolution of the pump pulses used and so can typically be ~100 fs. By systematically delaying the arrival of the broadband probe pulse, it is possible to map out the evolution of the gain dynamics across the emission spectrum of the material with very high time resolution.

Figure 4 shows a series of snapshots of the absorption induced by a pumping pulse in a poly(thiophene) derivative. This figure shows the changing absorption of the sample between 200 fs and 400 ps after excitation. Within the absorption band of the material, one finds that the level of absorption is slightly reduced because the pump pulse has partly depleted the ground state. In the emission band there is also a reduction in the absorption that mimics in shape the photoluminescence spectrum of the polymer. This negative absorption – or optical gain – shows direct evidence for stimulated emission through much of the emission band. In the low energy tail of the emission, however, there is an increase in absorption that arises due to the excited-state absorption process mentioned earlier. Clearly, for a good laser material, the spectra of excited-state and charge-induced absorptions should overlap as little as possible with the photoluminescence.

Many other investigations of gain in semiconducting polymer films have used a phenomenon known as spectral line narrowing to explore indirectly the amplifying properties of the medium. The experimental procedure for such studies is as follows. A thin film of the semiconducting material, of typically 100 nm thickness, is excited by a pulsed pump laser focused to a stripe of dimensions ~100 μm wide by a few millimeters in length. A significant fraction of the light emitted by the material is trapped in the film by total internal reflection at the polymer–air and polymer–substrate interfaces, and is thereby waveguided along the length of the excitation stripe. This waveguided spontaneous emission can be amplified by stimulated emission before being emitted out the edge of the film.

One finds that, above a particular threshold of pump energy, there is a superlinear increase in the output energy with pump intensity. Associated with this is a dramatic narrowing of the broad emission spectrum to a linewidth of typically less than 10 nm, as illustrated in Figure 5. These two features are signatures of gain narrowing via the process of amplified spontaneous emission. The line-narrowed feature usually appears at the first vibronic overtone of the optical transition, where the gain exceeds the losses in the material by the greatest amount. This particular wavelength experiences the greatest amplification and, above a particular pumping density, undergoes a runaway effect in which most of the light is stimulated to emit at that wavelength at the expense of the rest of the spectrum.

In the case of amplified spontaneous emission or mirrorless lasing as it is also known, the spontaneous emission guided along the length of the stripe acts as



Figure 4 Transient absorption spectra of poly[3-(2,5-dioctylphenyl)-thiophene]; chemical structure inset. (Reproduced from Ruseckas A, Theander M, Valkunas L, Andersson MR, Ingänas O and Sundström V (1998) Energy transfer in a conjugated polymer with reduced inter-chain coupling. *Journal of Luminescence* 76 & 77: 474–477. Copyright (1998), with permission from Elsevier.)



Figure 5 The change in spectral shape with increasing excitation density (from 10 to 133 μJ cm^{-2}) of the edge emission from a PFO film – the normalized spectra show a significant spectral line narrowing at high excitation densities. (Adapted from Heliotis G, Bradley DDC, Turnbull GA and Samuel IDW (2002) Light amplification and gain in polyfluorene waveguides. *Applied Physics Letters* 81: 415–417. Copyright (2002), with permission from American Institute of Physics.)

the ‘probe pulse’. In these experiments it is therefore necessary to extract information indirectly about the net gain in the material. By integrating the spontaneous and stimulated emission along the length of the stripe, one finds that the wavelength-dependent output intensity $I(\lambda)$ of the spectral line narrowed light is given by the relationship

$$I(\lambda) \propto \frac{1}{g(\lambda)}[\exp[g(\lambda)l] - 1] \quad [1]$$

where I_p is pumping intensity, l is the length of the stripe, and $g(\lambda)$ is the net gain coefficient. Therefore, by monitoring the intensity of the line-narrowed emission as a function of the length of the pump stripe, one can extract the value of the net gain for the material. Similarly, by progressively moving the stripe further and further away from the edge of the film, it is possible to evaluate the waveguide losses of light propagating through an unpumped region of the waveguide. Waveguide losses in conjugated polymers typically lie in the range of 3–50 cm^{-1}. Net gains can be as high as 60 cm^{-1} or 260 dB cm^{-1} at modest pumping densities of 4 kW cm^{-2}. These substantial gains, in very small propagation lengths, therefore highlight the attraction of waveguide-based resonators for polymer lasers. In the next section we will discuss the most commonly used feedback structures that have been used for polymer lasers.

Polymer Laser Resonators

The first demonstration of cavity lasing in a conjugated polymer was made by Moses in 1992. The resonator consisted simply of two flat dielectric mirrors on either side of a cuvette containing the polymer in solution. Lasing occurred at the peak wavelength of the gain profile. Subsequent developments in solid-state polymer lasers have involved more sophisticated resonators that exploit the capacity of these materials for very simple processing. For example, solution-processing methods such as spin-casting or dip-coating, make it possible to fabricate very high-quality optical waveguides. Wavelength-scale microstructures can also be readily formed, allowing the straightforward fabrication of laser microresonators.

Many different resonators have been explored for solid-state polymer lasers. Some of the key types are shown in Figure 6, including different geometries of both microcavities and distributed feedback structures. The first resonator used, by Tessler *et al.*, was a planar microcavity (Figure 6a), in which the polymer film was sandwiched between two mirrors. The structure supported standing-wave resonances perpendicular to the plane of the film, at three wavelengths in the emission band of the polymer. Above laser threshold, light was preferentially stimulated into only one of these modes. Microcavities of other geometries have also been studied, including annular and spherical microresonators (Figure 6b,c), in which the optical field is confined in waveguide modes, whispering gallery modes, or a superposition of the two. Such structures provide a longer interaction length in the gain medium for stimulated emission; though tend to lase on many longitudinal modes and have no directional output beam.



Figure 6 Resonators used for conjugated polymer lasers. (a) Planar microcavity; (b) annular microcavity; (c) spherical microcavity; (d) distributed feedback resonator; (e) 2D DFB/ photonic crystal resonator; (f) random laser.

The final key group of resonators are distributed feedback (DFB) structures, which researchers have progressively favored to attain the low pump threshold densities that will be required to realize electrically pumped lasing. Figure 6d shows a typical DFB laser structure. The device is based on a thin polymer film that is typically 100 nm in thickness deposited on top of a silica substrate. The silica–polymer–air structure forms an asymmetric slab waveguide that supports only the lowest order transverse electric mode TE_0. To provide the feedback, the substrate is modulated with a wavelength-scale periodic grating structure. These corrugations give rise to Bragg scattering of the waveguide mode. Through careful selection of the grating period, one may arrange that optical wavelengths close to the peak of the polymer gain will be Bragg scattered from the propagating TE_0 mode to the counter-propagating TE_0 mode. This is achieved when the Bragg equation

$$2n_{\text{eff}}\Lambda = m\lambda_B \quad [2]$$

is satisfied, where Λ is the grating period, n_{eff} is the effective refractive index of the waveguide, m is an integer, and λ_B is the Bragg wavelength. In so doing, one may arrange that two counter-propagating waveguide modes can be coupled together, thereby providing the distributed resonant feedback for the laser process. Commonly in semiconducting polymer lasers, a second-order (i.e., $m = 2$) Bragg grating has been favored to provide the feedback for the laser, so that the first-order scattering provides a surface-emitted output coupling, perpendicular to the plane of the guide. This surface-emitting geometry is particularly attractive in polymer lasers because it is relatively difficult to achieve a high optical quality edge to the waveguide. DFB lasers have the advantage over simple microcavity resonators in that they can combine long interaction lengths, limited by the scattering length of the Bragg grating, with excellent wavelength selection, which is controlled by the grating period.

In addition to conventional 1D DFB gratings, a number of more exotic 2D and 3D DFB, and photonic crystal resonators have been explored in semiconducting polymers. Even randomly located scattering sites in a polymer film have been used to provide a weak closed-loop cavity feedback. Examples of 2D gratings are given in Figure 7, which shows atomic force micrographs of an eggbox structure, formed from two orthogonal gratings, and a circular DFB grating. Such 2D DFB structures can significantly improve the operation of surface-emitting polymer lasers compared with 1D gratings. Improved feedback yields lower oscillation thresholds, combined with higher slope efficiencies and significantly improved beam quality. Indeed, such surface emitting DFB lasers can produce nearly diffraction limited laser beams.

Typical operating characteristics of an egg-box DFB polymer laser are shown in Figure 8. This laser, which is based on the material MEH-PPV, is transversely pumped with a pulsed pump laser focused onto a small region of the waveguide; up to 90% of the incident pump light is absorbed in the 100 nm thick film. The laser has a threshold pump energy of 4 nJ and an external slope efficiency of >7%, and operates on a single frequency close to the Bragg wavelength of the periodic waveguide. Lasing does not occur exactly at the Bragg wavelength, because at this wavelength the propagation of light is suppressed by the periodic structure. This leads to a photonic stopband within which the emission is reduced. At the edges of this stopband the microstructure can support standing wave electric field patterns of the same spatial period. At these wavelengths there can be a strong interaction between the electric field and excited states in the gain medium, which leads to low-threshold band edge lasing as observed in the figure.

Although DFB resonators have advantages over microcavity devices, the complicated lithographic and etching steps involved in their fabrication can detract from the key material advantage of simple processing. To address this issue, several different techniques for simply replicating the complicated microstructures have been explored. These include UV embossing of flexible plastic substrates, and hot embossing and micromolding of the active



Figure 7 Atomic force microscope images of (a) 'egg-box' DFB grating, and (b) circular DFB grating; grating period is 400 nm in each structure.



Figure 8 (a) Energy characteristic of an egg-box DFB laser; (b) normalized emission spectra above and below lasing threshold, showing lasing in the edge of the photonic stopband. (Reprinted from Turnbull GA, Andrew P, Barnes WL and Samuel IDW (2002) Operating characteristics of a semiconducting polymer laser pumped by a microchip laser. *Applied Physics Letters* 82: 313–315. Copyright (2003). With permission from American Institute of Physics.)

polymer itself. Such techniques can very readily reproduce structures with feature sizes as small as 100 nm and could allow future mass production of photonic microstructures in these materials.

Towards Plastic Diode Lasers

A typical experimental configuration for characterising optically pumped polymer lasers is shown in Figure 9. The laser is mounted in a vacuum chamber in order to isolate the polymer from oxygen and water. A pulsed visible or ultraviolet pump laser is attenuated and then focused onto the waveguide to transversely pump the polymer laser. The emission is collected using a CCD spectrograph for spectral measurements and energy meter and beam profilers for other characteristics. Typical pulsed pump lasers, which have been used, include nitrogen laser pumped dye lasers, and spectral harmonics of regeneratively amplified Ti^{3+}-sapphire lasers or flashlamp pumped Nd^{3+}:YAG lasers. Recent advances have shown the thresholds to be low enough to be successfully pumped with a modest Nd^{3+} pulsed microchip laser.

So while optically pumped polymer lasers are now proving to be compact, functional light sources, a major motivation for research in this field remains the prospect of electrically driven plastic diode lasers. Such lasers could be very low-cost, flexible light sources that would access any wavelength throughout the visible spectrum. In particular, there are exciting prospects of producing blue and green diode lasers in spectral regions currently difficult to access with inorganic semiconductors. The lowest threshold densities reported for optically pumped organic semiconductor lasers are of the order of 100 W cm^{-2}. To achieve similar excitation densities electrically, one requires pump current densities of ~200 A cm^{-2}. This is substantially more than the few mA cm^{-2} commonly used in polymer LEDs for display applications. Presently, such high current densities are infeasible with continuous excitation, but can be exceeded with short current pulses of a few tens of nanoseconds duration.

Electroluminescence in conjugated polymers was first achieved in 1990 by Burroughes and co-workers. Since that time there has been remarkable progress made in the science and technology of organic LEDs. Commercial products are now on the market, and the feasibility of both flexible and full-color light-emitting displays, in which the individual pixels have been ink-jet printed, have been demonstrated in the laboratory. Despite such rapid progress in the field of organic LEDs, there have been no successful demonstrations to date of electrically pumped lasing in any organic semiconductor. In this section we highlight some of the challenges that must be faced if electrically pumped lasing is to be achieved. To understand the problems associated with electrical driving of organic semiconductor lasers, it is useful first to review the generic structure of organic light-emitting diodes.

A generic organic LED structure is shown in Figure 10. The device consists of one or more organic layers sandwiched between two electrical contacts. Usually a transparent anode is used, commonly made from ITO, which allows light to be emitted from the front face of the LED. A low work-function metal, such as calcium or aluminum, is used as the cathode. The organic part of the device may consist of several layers. These include one or more charge transport layers, plus a light-emitting layer in which the electrons and holes combine to form excitons before emitting light. Typically, the combined thickness of these organic layers is as little as 100 nm. Such thin devices are necessary to keep operating voltages low, to overcome potential barriers for injection, and because charge mobilities in organic semiconductors are very low (10^{-5} to 10^{-2} cm^2 V^{-1} s^{-1}).

The inclusion of electrical contacts into organic semiconductor laser structures can be problematic since they need to be situated very close to the emitting region. Metallic contacts can quench the luminescence and introduce losses to the waveguide mode, thereby increasing the oscillation thresholds. Furthermore, the ITO anode has a high refractive index and so can reduce the spatial overlap of the



Figure 9 Schematic of a typical experimental configuration for characterizing polymer lasers.



Figure 10 Schematic structure of a generic organic light-emitting diode.

guided mode with the active medium. Such issues indicate that the design of organic LEDs needs to be somewhat modified for achieving electrically pumped lasing. In particular, there needs to be a trade-off between the optimum electronic and photonic designs. To address these issues, various device structures have been proposed that distance the optical mode from metallic contacts, while reducing the thickness of the ITO layer to optimize the mode confinement in the active material.

A more demanding obstacle to electrically pumped lasing is the additional excited state absorption associated with the electrical pumping scheme. As many as three-quarters of the generated excitons in an organic LED are formed in the triplet state which is nonemissive and can lead to excited-state absorption, albeit principally at lower energies than the lasing wavelength. Additionally, injected charges that have not yet formed excitons, exhibit strong absorption, which overlaps significantly with the peak of the material gain. Indeed, this charge-induced absorption has so far prevented the demonstration of injection lasing in conjugated polymers, even in optimized device structures mentioned above. A possible alternative route for efficient pumping of polymer lasers could be through indirect electrical pumping. For example, an inorganic diode laser or LED, or even an organic LED, could be used as an electrically efficient optical pump for the semiconducting polymer laser. Recent advances in GaN-based LEDs and lasers provide interesting prospects for such alternative systems.

Research on semiconducting polymer lasers continues, both to reduce the excitation densities needed for threshold and to investigate new material systems that could overcome the obstacle of charge-induced absorption. By building on recent developments in resonator geometries, material blends, and compact pumping schemes, semiconducting polymer laser systems, whether optically or electrically pumped, should soon become practical, visible light sources for a range of applications.

List of Units and Nomenclature

Charge mobility	[$\mathrm{cm}^2\,\mathrm{V}^{-1}\,\mathrm{s}^{-1}$]
Current density	[$\mathrm{A\,cm}^{-2}$]
Energy density	[$\mu\mathrm{J\,cm}^{-2}$]
Excited state densities	[cm^{-3}]
Gain coefficient α ($\exp(\alpha z)$)	[cm^{-1}]
Intensity/power density	[$\mathrm{kW\,cm}^{-2}$]
Optical gain	[$\mathrm{dB\,cm}^{-1}$]
Stimulated emission cross-section	[cm^2]
Waveguide propagation loss coefficient γ ($\exp(-\gamma z)$)	[cm^{-1}]
Wavelength	[nm]

See also

Diffractive Systems: Diffractive Laser Resonators. **Lasers:** Dye Lasers; Planar Waveguide Lasers. **Optical Amplifiers:** Basic Concepts. **Optical Materials:** Plastics. **Photonic Crystals:** Photonic Crystal Lasers, Cavities and Waveguide.

Further Reading

Burroughes JH, Bradley DDC, Brown AR, *et al.* (1990) Light-emitting-diodes based on conjugated polymers. *Nature* 347: 539–541.

Friend RH, Gymer RW, Holmes AB, *et al.* (1999) Electroluminescence in conjugated polymers. *Nature* 397: 121–128.

Karl N (1972) Laser emission from an organic molecular crystal. *Physica Status Solidi (a)* 13: 651–655.

Kranzelbinder G and Leising G (2000) Organic solid-state lasers. *Reports on Progress in Physics* 63: 729–762.

McGehee MD and Heeger AJ (2000) Semiconducting (conjugated) polymers as materials for solid-state lasers. *Advanced Materials* 12: 1655–1668.

Miyata S and Nalwa HS (eds) (1997) *Organic Electroluminescent Materials and Devices*. Amsterdam: OPA.

Moses D (1992) High quantum efficiency luminescence from a conducting polymer in solution – a novel polymer laser-dye. *Applied Physics Letters* 60: 3215–3216.

Pope M and Swenberg CE (1999) *Electronic Processes in Organic Crystals and Polymers*. New York: Oxford University Press.

Samuel IDW (2000) Polymer electronics. *Philosophical Transactions of the Royal Society of London A* 358: 193–210.

Scherf U, Riechel S, Lemmer U and Mahrt RF (2001) Conjugated polymers: lasing and stimulated emission. *Current Opinion Solid State and Materials Science* 5: 143–154.

Tessler N (1999) Lasers based on semiconducting organic materials. *Advanced Materials* 11: 363–370.

Tessler N, Denton GJ and Friend RH (1996) Lasing from conjugated-polymer microcavities. *Nature* 382: 695–697.

Planar Waveguide Lasers

S Bhandarkar, Alfred University, Alfred, NY, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Lasers have evolved to become true marvels of technology. From their invention in the early 1960s, laser light has changed the way society operates, its application stretching to virtually every aspect of human activity. The versatility of lasers is derived from the fact that there are several different types, each with a unique set of advantages. Solid-state lasers, made from specific semiconducting materials, are commonly used in the optical networks that underlie the greatest machine on Earth – the Internet. High power gas lasers, such as CO_2 lasers, are used in industrial machining, whereas rare-earth doped and dye lasers have found applications ranging from eye surgery to tattoo removal.

Planar waveguide lasers are a relatively new class of lasers made possible by advances in the field of optical waveguides. Over the past decade, with the aim to miniaturize optical components, planar waveguide technology has been developed to a high degree of sophistication. Likewise, Er and other rare-earth doping was studied extensively owing to its importance in all-optical amplification. These elements turned out to be the building blocks for the development of fiber lasers and subsequently planar waveguide lasers.

This chapter will discuss the basic concepts underlying this category of lasers, the variations therein, and the main characteristics. It is important to understand the basic features of waveguides and lasers, which is included as a prelude. We will then discuss planar waveguide lasers with emphasis on the essential elements: the laser materials, the various designs, their performance, and the resultant advantages as well as the applications.

Waveguides

A waveguide is a general conduit for efficient propagation of an electromagnetic field. It is usually defined by making a region of higher refractive index within a dielectric medium. This behaves as an attractive potential well that confines light in the form of bound modes, much like a potential well that confines electrons to a bound state. The propagating field is referred to as the lightwave and is governed by Maxwell's equation. For a weakly guiding approximation, as is the case when the refractive index contrast (Δn) is small, Maxwell's equation can be reduced to a scalar wave equation for the transverse electric field. For a given wavelength (λ) and polarization, the scalar wave equation in a nonmagnetic medium is

$$\nabla^2 E(x) + \frac{4\pi^2}{\lambda^2} n(x)^2 E(x) = 0 \qquad [1]$$

where E is the electric field. For a waveguide aligned in the z direction, the field is the sum of the two propagating transverse modes, each with the form $E(x) = \Phi(x, y)e^{ik_z z}$ where $\Phi(x, y)$ is the field distribution and k_z is the propagation constant. The wave equation for the transverse mode reduces to

$$\frac{\lambda^2}{4\pi^2}\left(\frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2}\right)\Phi(x, y) + n(x, y)^2\Phi(x, y) = (\bar{n})^2\Phi(x, y) \qquad [2]$$

Here, $\bar{n}$ is referred to as the effective refractive index and is given by $\bar{n} = k_z\lambda/2\pi$. The effective index dictates the occurrence of bound modes – these states occur when $\bar{n}$ is between n_{core} and n_{cladding}. For smaller values of $\bar{n}$, there is a continuum of unbound and radiation modes. These are leaky modes that are dispersed quickly over a short distance. Only bound modes are guided in the core of the waveguide structure.

Planar Waveguides

Waveguides formed on a flat substrate are called planar waveguides. These are typically made by stepwise deposition of films of dielectric materials (typically glass). The waveguide core is defined by one of several methods, the most common of which uses lithography and etching. In this case, a film of an appropriately higher index material is deposited on an 'under-cladding' film and then selectively etched to define a core. This is generally covered with a suitable 'upper-cladding' layer so that the index contrast is controlled in all directions. Other methods of forming the core include patterned ion exchange or ion implantation or increasing the index of the medium using a femtosecond laser, etc. In all these cases, the end result is the formation of an embedded higher-index region whose locus defines the optical path for the lightwave. A circuit made from these waveguides is known as planar lightwave circuits (PLC).



Figure 1 Range of different waveguide designs, with the core represented by the darker regions: (a) Optical fiber; (b) slab waveguide; (c) channel waveguide; (d) embedded channel waveguides with a layer of the overcladding; (e) rib waveguide; (f) inverted rib; (g) ion diffused; and (h)strip loaded, comprising of a strip of a different higher index material (that serves to confine light) on a core layer.

Waveguide cores may be designed in several different configurations, as shown in Figure 1. These designs allow for different fabrication processes as well as the control over the modal properties of the lightwave. For a given index contrast, the number of modes traveling in the waveguide is primarily determined by the dimensions of the waveguide. The aspect ratio of the waveguide affects the propagation of the transverse electric (TE) and the transverse magnetic (TM) modes, due to different propagation constant k_z for each mode.

Lasers

The generation of laser light requires four basic conditions to be satisfied:

- a source capable of light emission;
- an energy supply source – typically electrical, optical, or chemical;
- population inversion to the excited state in the lasing medium; and
- absence of parasitic effects that would absorb the emitted light.

Laser light is often a result of either electronic or vibrational excitation. This is because these excitations involve transfer between energy states that coincide with the radiation of UV, visible, or infrared light. Population inversion is an important requirement in lasers since the emission is stimulated. This involves having a greater fraction of the atoms or molecules in the excited state so that a stimulating photon can cause a radiative decay to the lower energy level. The stimulated light from most lasing media is weak, which requires unacceptably long lengths to generate sufficient power. Instead, as shown in Figure 2, lasers are made with two parallel mirrors with an axial light-generating source in between. This configuration is known as a resonant cavity, a resonator, or an oscillator. The back mirror is usually fully reflective but a partial front mirror allows a portion of the light in the cavity to pass through. The two mirrors cause the light to bounce to and fro, forcing it into making multiple passes through the cavity. Light emanating from this structure is thus amplified and is also coherent (that is the lightwaves are in phase



Figure 2 Conceptual representation of a simple Fabry–Perot laser.

with each other spatially and temporally). This has come to represent the signature output of a laser.

Planar Waveguide Lasers (PWL)

By way of an example, let us consider a solid state, rare-earth doped laser, such as an Nd-doped YAG laser. All rare-earth ions are able to fluoresce, some (e.g., Nd) more efficiently than others, and hence can be light emitters. These ions have to be dissolved (doped) into a solid host, say, a glass or a single crystal such as YAG (**Y**ttrium **A**luminum **G**arnet). The excitation of these ions is done optically with light of a suitably higher energy (or lower wavelength). When this 'pump' light is made incident on a rod of the rare earth doped material, it is absorbed by the rare earth ions and used to reach an excited electronic state. Amongst all the possible higher energy states, only certain ones are sustainable because the electron resides in that state for an acceptably long period of time (called the lifetime). Hence, population inversion can be more readily achieved in these longer lifetime states and stimulated processes such as amplification and lasing are readily possible. The laser light generated in the doped rod is emitted across its entire cross-section.

Planar waveguide lasers are designed to miniaturize the kinds of stand-alone solid state lasers describe above. In principle, a PWL is a laser where the light emitting resonant cavity is a planar waveguide. This topic of our interest is a relatively recent development that renders some unique advantages. These can be broadly classified into two categories: one relating to making efficient high-power lasers and the other, to the integration of lasers with other optical components.

An example of the first type is a Nd-YAG laser configured into a planar geometry so that the laser light is now contained within the waveguide. One design that has evolved to achieve this well is shown in Figure 3. The light is guided by the waveguiding structure setup by the sapphire planes. Since both the excitation (or pump) and the lasing modes are well confined, high modal overlap is achieved. These PWLs can be edge-pumped or face-pumped and high powers (measured in the order of Watts) can be achieved.



Figure 3 End view of a planar waveguide form of a Nd-YAG laser made using sapphire (single crystal Al_2O_3) for cladding.

In the above design, the cavity is defined by two parallel reflectors bracketing the light-generating medium and is known as a Fabry–Perot etalon. The distance between the two mirrors sets up a wavelength filtering mechanism whereby only resonant wavelengths are sustained. These are related to the intra-mirror distance by the simple equation shown below:

$$L_c = \frac{a\lambda}{2n} \qquad [3]$$

where L_c is the length of the cavity, a is an integer, n is the refractive index of the medium, and λ is the wavelength in vacuum. As the cavity length increases, the number of possible resonant wavelengths increases and the spacing between wavelengths is reduced. These are called the longitudinal modes (Figure 4a). Likewise, lateral modes (Figure 4b) can be generated in the cavity as well, tending to make the operation of the laser multimoded, as shown in Figure 5. This is characteristic of a Fabry–Perot laser, which can be overcome by embellishing the basic etalon design.

As stated above, another big advantage here is that the platform for fabricating PWLs can be chosen to be the same as to make PLCs. Waveguide comprizing the laser can be continued further and configured into other desirable components, such as splitters, couplers, etc. Thus the laser does not have to be separately coupled to the waveguide. This is a major advantage as this connecting process is time-consuming and incurs loss of light. In the field of photonics, the ability to integrate active components with passive ones onto the same chip is considered to be the first step toward photonic chips, analogous to the integrated circuit chip that has revolutionalized our world. This is the driver behind continued research and development of active elements such as PWLs that can be coupled with other actives, such as thin film electro-optic modulators or acousto-optic filters, etc.

Waveguide Laser Materials

The waveguiding structure is comprised of materials that are either dielectrics or semiconductors, both inorganic and organic. For their homogeneity and broad transmittance, high silica glasses are ideal



Figure 4 Generation of longitudinal (a) and lateral modes (b) in a Fabry–Perot laser.



Figure 5 The output of a Fabry–Perot laser: (b) is governed by the number of modes within the gain spectrum of the lasing medium shown by the dotted lines (a). The spacing between the modes can be altered changing the length of the cavity. The smallest mode in output spectrum (b) needs to have enough gain to overcome the lasing threshold.

materials for waveguiding. The chief advantages of high silica waveguides are easy index and mode matching to standard optical fibers, low propagation loss, and good durability. When crystalline materials are used, they have to be single-crystalline to avoid grain boundary scattering (for instance, Ti-diffused waveguide in single-crystal $LiNbO_3$). If semiconductors are used, the bandgap of the material needs to be sufficiently high so as to avoid absorption of the photons. Silicon waveguide (bandgap = 1.1 eV) on a silica cladding (SOI) is commonly used system in PLCs used for telecommunication applications.

The PWLs described above are fabricated in rare-earth doped glass waveguides. Waveguides have to be much shorter than fiber, so the challenge of incorporating the rare-earth ions at high concentration in the host material has to be overcome. Planar waveguide lasers are a compressed version fiber lasers that have the unique advantage that they can be directly integrated with other components on the same chip using very large-scale integration (VLSI)-style processing. The concentration of Er (or the lasing ion in general) in a PWL needs to be many times that in fiber amplifiers (~100 ppm). The need for high gain in a short length requires high pump powers and high lasing ion concentration, both of which lead to nonideal behavior. Since rare earth ions tend to have multiple excited electronic states, there can be absorption at the excited state level as well. When a higher energy state is separated from the upper emission level by the energy in one laser photon, the ions can undergo excited state absorption or ESA (Figure 6). Rare-earth ions in close proximity tend to undergo cooperative upconversion processes, where two excited ions transfer energy between each other so that neither ion may fluoresce at the desired wavelength. These processes can negatively affect the



Figure 6 The energy level diagram for a representative two level system. The inset (a) shows the excitation and emission process. Excited state absorption is shown in (b) and cooperative upconversion is shown in (c).

useful gain of the system. Ensuring high spatial dispersion of the Er atoms is critical to minimize this effect. Special glass compositions, such as phosphate glasses, are used here to ensure that the Er is not phase separated or clustered. These glasses also provide a high induced cross-section for gain. Glasses with low phonon energy are also desirable to minimize phonon-mediated nonradiative decays in the rare earths. Light emitting semiconductors and polymers containing fluorescent dyes have also been used to make PWLs.

Now that we have gained an overall perspective of PWLs, we can discuss different manifestations. The following discussion uses a Er doped system as a model since there is a substantial body of work on this system.

Distributed Bragg Reflector (DBR) PWL

In planar waveguide systems, it is difficult to construct efficient mirrors or reflective facets perpendicular to the waveguide. However, mirrors can be replaced by Bragg gratings, which be fabricated relatively easily. In-line Bragg gratings result in wavelength specific reflection as per eqn [4]:

$$\Lambda = \frac{m\lambda}{2\bar{n}} \qquad [4]$$

where Λ is the grating pitch, m is the order of the grating, and λ is the central Bragg wavelength. Gratings have another important benefit in that they ensure that unwanted frequencies outside the limited reflection spectrum are dispersed before they reach the lasing threshold.

A DBR laser is similar in principle to a Fabry–Perot design but uses a Bragg grating on either end of planar Er-doped waveguide. This is shown schematically in Figure 7. Gratings can be made in a number of different ways. One popular way is to exploit the photosensitivity of glasses using 193 nm or 244 nm UV light to periodically alter the refractive index of a glass waveguide. Photosensitivity occurs by a combination of molecular changes (such as the formation of oxygen deficiency sites or color centers) as well as changes in the material strain in the region exposed to the UV light (Figure 7c). Alternatively, gratings can also be formed using etching to make periodic grooves in the waveguide. These are called corrugated or surface relief gratings (Figure 7a and 6b).

The back Grating 1 has a high reflectance of almost 100%, whereas Grating 2 is a weaker grating. The reflectance strength of Grating 2 is determined by taking into account the gain coefficient of the material and the output power required from the laser. The reflection intensity can be altered according to the following equation:

$$R = \tanh^2\left[\frac{\pi L_G \Delta n_{\text{eff}}\, \eta(V)}{\lambda_B}\right] \qquad [5]$$

where L_G is the grating length, Δn_{eff} is the index modulation of the grating, λ_B is the Bragg wavelength, $\eta(V)$ is the confinement factor, a function of the waveguide parameter V that represents the fraction of the integrated mode intensity contained in the core. Increasing the reflectance strength also widens the linewidth of reflected light. The overlap of the spectral width between the back (Grating 1) and the front grating (Grating 2) becomes the effective output window within the gain spectrum of the lasing material (Figure 8).

Not unexpectedly, a DBR structure generates longitudinal and lateral modes. These modes are, however, limited to the overlapping section of the reflection spectrum of the two gratings, as opposed to the entire gain spectrum as in Fabry–Perot lasers (Figure 9). Yet, this can lead to problems such as spectral hole burning and mode hopping, whereby the dominant mode hops from one wavelength to another. The separation between the modes needs to



Figure 7 DBR planar waveguide laser. The PWLs shown in (a) and (b) have sinusoidal and trapezoidal surface-relief gratings respectively etched in their cores. An in-line grating of the kind seen in (c) could be fabricated using the photosensitivity of the glass. The top cladding is shown only in (a).



Figure 8 The reflection spectrum of the back (1) and the front (2) gratings. As the intensity of the reflected light is made to increase, so does the linewidth. Hence, the narrower spectrum of partially reflecting grating 2 tends to dictate the operating wavelength range of a DBR.



Figure 9 A sample output from a DBR laser, shown in this case with 3 modes. The dotted line shows the effective overlap between the two gratings. The existence of the modes depends on several factors, in particular the pump intensity.

be made sufficiently high compared to the spectral overlap so that single-mode operation can be achieved. But in practice the length of the cavity (L_c in eqn [3]) is determined by factors such as power and space and may not be independently altered to achieve this. However, the reflection spectrum of the back and the front gratings could be slightly shifted in opposite directions to realize a smaller overlap within which only one or a few modes may exist (Figure 10). The occurrence of a single mode also depends on the gain profile of the lasing material and the optical pump power. In Er-doped PWLs, modes other than the primary one can be suppressed by using a pump power below a threshold limit and stable operation can be thus achieved.



Figure 10 Shifting the front and back gratings is one means of controlling the width of the overlap region, shown in gray. This way a single mode operation can be achieved even for a longer cavity with many modes.

Distributed Feedback (DFB) PWL

The modal problems listed above can be addressed by having a single, distributed grating that is placed along the entire length of the lasing waveguide itself (Figure 11). Alternatively, the gratings may be also placed in the upper or the lower claddings to minimize loss of optical power due to scattering because of the longer grating. In this case, it is the evanescent portion of the light that interacts with the grating. In all cases, the periodicity of the grating leads to a condition for a single lasing wavelength based on constructive interference. The strongest mode occurs when the period Λ of the Bragg grating satisfies the primary Bragg condition (for first order grating or $m = 1$) in eqn [4]. The device will also function if the grating pitch is equal to small integer multiples of $(\lambda/2\bar{n})$.

The grating needs to be made strong enough to generate sufficient feedback (reflections), which also widens the linewidth of the spectrum. To ensure a single narrow linewidth output, a quarter wave phase shift is introduced in the grating, as seen in Figure 11. This phase shift creates a transmission fringe in the spectrum (Figure 12) that significantly narrows the linewidth of the output signal. This design is considered to be standard for the DFB lasers of today. Figure 13 shows a typical output of a DFB laser.

Any of the geometries seen in Figure 1 can be used to make the waveguide for the laser. Due to processing constraints, rib (c) and ion diffused (d) configurations are commonly used. Waveguide losses, characteristically due to scattering from sidewall roughness, have to be low. Otherwise, this adds a



Figure 11 A DFB planar waveguide laser.



Figure 12 The reflection spectrum of a grating with a central λ/4 shift in the pitch, showing the transmission fringe.



Figure 13 The typical output of a DFB PWL. The linewidth can be made to be as narrow as a few hundred kHz.

significant overhead onto the pump power and lowers the output of the PWL. Birefringence caused by thermal expansion coefficient differences and excessive sidewall roughness also need to be minimized as they can substantially alter the loss of the TE mode compared to TM.

Though their spectral properties are ideal as sources for long haul transmission, DFB lasers tend to be less powerful than the corresponding DBR designs. But the DBR PWLs are very sensitive to reflections that can cause a broadening of the laser linewidth or can act as a source of noise. In both cases, single mode lasers with very narrow linewidths in the kHz range with low radiance and noise, have been demonstrated. But neither is known to have been commercialized yet.

PWL Arrays

One of the unique advantages of the PWLs is that they are often processed using VLSI techniques. One important implication of this is the ability to make a PWL array where multiple lasers are formed simultaneously on the same chip, each with a unique output (Figure 14). Such arrays are likely to be very useful in future dense wave division multiplexing (DWDM) optical network systems where as many as 128 channels (and more) are planned. Since packaging of individual lasers can be up to 75% of the total cost, making chips with multiple lasers is very attractive. The lasers may be DBRs or DFBs whose output wavelength is controlled by changing the grating parameters. To vary the individual wavelengths either the effective index and/or the pitch of the grating can be changed. Thus, any output spectrum can be designed and executed merely by making the appropriate lithography mask.



Figure 14 Idealized output from a 4-PWL array.

The gratings are often written holographically, where the wafer is exposed to an interference pattern caused by two coherent light beams. The wafer underneath can be sensitized with a photosensitive glass layer or a film a photoresist. It is not efficient to do multiple holographic exposures to individually change each of the gratings in the array. One way of doing this with a single holographic exposure is by constructing the waveguides at different relative angles. Then the component of the index modulation, resolved along the axis of the waveguide, would vary for each waveguide depending on the relative waveguide angle (Figure 15); this would lead to differences in $\bar{n}$. Alternatively, the waveguide array can be made of the same height but of different widths. This is easily done since waveguide height is usually deposited uniformly but the width is a function of the mask layout. Here the waveguide and the grating are orthogonal to each other and the variation in wavelengths is achieved by the fact that the effective propagation constant for each of the waveguides is different.

Arrays of PWLs have been made on a silicon substrate using deposition of an Er containing glass that is subsequently patterned into waveguide, and ultimately laser, arrays. Another approach has been to start with a phosphate glass as the host and the substrate. A phosphate glass is a superior host for rare-earth ions such as Er since the sensitization efficiency is nearly unity and much high doping levels are possible before concentration quenching effects set in. Waveguides are created by ion-exchange by immersion in a hot bath containing suitable ions (Na for Li, for instance). When starting with a uniformly doped glass, one issue in the assimilation of the laser array with other components is the fact that Er-doped region does not start and end with the waveguide laser section. Recently, the Er has been deposited selectively in the laser waveguide in phosphate glass using methods such as ion implantation, bringing the concept of integration closer to reality.



Figure 15 Two different means of making planar waveguide laser array with a single holographic exposure to write the gratings. The darker rectangular blocks represent the core channels or ribs. In (a) the width and hence the effective index of the waveguide is varied whereas the relative angle between the waveguides is altered in (b). The lines represent the direction of the gratings, which is orthogonal only to the left most waveguide in (b).

Pumping

One of the key issues here is the optical pumping of the rare-earth PWLs to generate acceptably high output power. Individual diode lasers or an array of diode lasers all on a single chip (called a diode bar) have been utilized as pumps. Both single and multimode diode lasers are available and have been used. There are pros and cons for either choice: whereas single mode lasers are less powerful (in the range of few 100 mW), it is difficult to convert the multimoded output of their counterparts to useful power. The choice is determined by the waveguide design, which needs to be optimized for high overlap of the lasing mode with the pump. Carefully tapered waveguides can be used distribute the pump power from a diode bar to the various lasers in an array without significant loss.

PWL Stability

Stable operation of a PWL is one of the big challenges. In DBR PWLs, it is seen that there is a threshold for pump power only below which single moded operation can be achieved. Additionally, any PWL die needs to be made immune to ambient temperature changes. These changes can affect many of the critical output parameters of the PWL: wavelength, linewidth, power and in the case of an array, the wavelength separation. This occurs primarily due to the thermal shift in the grating pitch as well as the thermo-optic effect. It is overcome by supplanting the laser die onto a heat spreader chip made from conducting material such as Cu or BeO, followed by a thermoelectric cooler. Ironically, the laser's output wavelength and linewidth are fine-tuned and 'fixed' using temperature to overcome any drifts due to processing errors or other reasons.

Reliability is another important issue that needs to be addressed, especially for telecommunication applications where these types of components have to pass high quality standards such as the Telecordia qualification in the USA.

Other PWL Systems

Many of the PWLs to date have been developed using Er doping, which emits light in the range of interest for telecommunications (the C-band and even the L-band). Here, Yb can be added as a co-dopant to improve power conversion efficiency. Other fluorescing ions have also been used: Nd, Tm, Ho, and Cr. Several research teams have successfully demonstrated Nd-YAG PWLs, in particular. Ridge waveguide lasers have been made using semiconductor materials InGaAs/InP heterojunctions in both Fabry–Perot and DFB configurations. These systems are electrically pumped. DFB PWLs have also been made using dye doped polymers.

It must be mentioned that there are other ways to use waveguides to make lasers. The primary example is a configuration where the waveguide resonator is external to the active region. Designs, such as ring resonator lasers and an external cavity lasers, fall in this category.

Future research and development of PWLs would undoubtedly utilize photonic crystal structures. These structures have a periodic fluctuation in the index of refraction in two or three dimensions. Owing to the resultant Bragg reflections, specific allowed and forbidden states are created which can be used to control the confinement of light. Hitherto, these structures have been used to form mirrors or hexagonal ring resonators. These more sophisticated laser designs are likely to enable new functions such as tunability of the output spectrum.

Summary

Planar waveguide lasers are a special class of laser where light is confined to a waveguide. They have distinctive advantages that include high optical gains, low laser thresholds, narrow linewidths in the kHz range, and optimal thermal management. Significantly, they afford a platform that can be readily expanded to include an array of lasers, each with an unique output, and can ultimately be combined with multiple optical components on the same chip. Such compact integrated devices are bound to take photonics to a new high level of capability.

List of Units and Nomenclature

a	integer denoting number of laser modes
E	electric field
k_z	propagation constant for travel in z direction
L_c	length of laser cavity
L_G	length of grating
m	order of the grating, an integer
n	refractive index of the medium
$\bar{n}$	modal effective refractive index
R	reflectance
V	normalized frequency or the V parameter of the waveguide
Δn_{eff}	modulation of the effective index of the grating
η	confinement factor or fraction of the light confined in the region of interest
λ	wavelength of the lightwave
λ_B	resonant wavelength of a Bragg grating or Bragg wavelength
Λ	grating pitch
Φ	electric field distribution

See also

Lasers: Carbon Dioxide Lasers; Dye Lasers. **Optical Amplifiers:** Erbium Doped Fiber Amplifiers for Lightwave Systems.

Further Reading

Carroll JE, Whiteaway JEA, Plumb RGS and Plumb D (1998) *Distributed Feedback Semiconductor Lasers*. London: IEE Publishing.

Ghafouri-Shiraz H (2003) *Principles of Semiconductor Laser Diodes and Amplifiers: Analysis and Transmission Line Laser*. London: Imperial College.

Hecht J (2001) *Understanding Lasers: An Entry Level Guide*. New York: Wiley Interscience.

Lee JR, Baker HJ, Friel JG, Hilton GJ and Hall DR (2002) High-average-power Nd:YAG planar waveguide laser, face-pumped by 10 laser diode bars. *Optical Letters* 27: 524–526.

Milonni PW and Eberly JH (1988) *Lasers*. New York: John Wiley and Sons.

Saleh BEA and Teich MC (1991) *Fundamentals of Photonics*. New York: John Wiley & Sons.

Shepherd DP, Hettrick SJ, Li C, *et al.* (2001) High-power planar dielectric waveguide lasers. *Journal of Physics D: Applied Physics* 34: 2420–2432.

Siegman AE (1986) *Lasers*. Harendon, Virginia: University Science Books.

Svelto O (ed.) (1998) *The Principles of Lasers*. Dordrecht, The Netherlands: Kluwer Academic Publishers.

Veasey DL, Funk DS and Sanford A (1999) Arrays of distributed-Bragg-reflector waveguide lasers at 1536 nm in Yb/Er codoped phosphate glass. *Applied Physics Letters* 74(6): 789–791.

Young M (2001) *Optics and Lasers: Including Fibers and Optical Waveguides*. NewYork: Springer-Verlag New York, Inc.

Semiconductor Lasers

S W Koch, Philipps-University, Marburg, Germany

M R Hofmann, Ruhr-Universität Bochum, Bochum, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

This article discusses the principle of operation and the basic material engineering aspects for the design of semiconductor lasers. The physics of the gain medium is analyzed in detail and the role of many-body effects due to the Coulomb interaction of the carriers for the optical properties of the active semiconductor material is demonstrated. The two main types of laser resonators for diode lasers, Fabry–Perot resonators and vertical cavity structures, are described. Finally, the dynamics of semiconductor lasers, including the principles of short pulse generation and nonequilibrium gain dynamics, is addressed.

Basic Principles

The optical emission from semiconductor lasers arises from the radiative recombination of charge carrier pairs, i.e., electrons and holes in the active area of the device. The conduction-band electron fills the valence-band hole by simultaneously transferring the energy difference to the light field. This is called radiative recombination. Hence, the frequency of the laser light is mainly determined by the bandgap of the semiconductor laser material. In order to achieve lasing, one needs carrier inversion, i.e., a sufficient number of electrons in the conduction band so that the probability of light absorption is lower than the probability of emission.

It has been shown that a large variety of semiconductor materials is suited for semiconductor lasers. The most stringent requirement for the material is that it has a direct bandgap. In other words, the maximum of the valence band and the minimum of the conduction band have to be at the same position in *k*-space (in the center of the Brillouin zone). The elemental semiconductors silicon and germanium do not fulfill this condition and therefore cannot be used for semiconductor lasers.

In order to achieve carrier inversion, it is necessary to pump the semiconductor laser, i.e., to excite a sufficient number of electrons from the valence band into the conduction band. Even though this pumping in semiconductors, as in other solid state laser materials, can be done optically, the large technological impact of semiconductor lasers is at least in part due to the possibility of electrical pumping with a few tens of milli-amperes at low voltages.

The original version of such a semiconductor laser device is shown in Figure 1, The laser structure consists of a GaAs-based p-n junction which is biased in the forward direction. Electrons are injected from the n region and holes from the p region, respectively. Due to the diode characteristics of the p-n junction, semiconductor lasers are often also called laser diodes. In the device shown in Figure 1, the laser mirrors are formed by the cleaved facets of the semiconductor crystal. Because of the high refractive index of GaAs, the semiconductor–air interface provides a reflectivity of about 32% which is sufficient for laser emission.

However, the early type of laser, the so-called homojunction device, was not very efficient because of the low carrier density in the active area and because of the weak overlap between the inverted region and the optical mode. Considerable improvement towards room-temperature continuous wave (cw) operation was achieved by the introduction of the so-called double heterostructure. Its principle is shown in Figure 2.

The basic idea behind the double heterostructure laser is that the active material (e.g., GaAs) is embedded in another semiconductor with a slightly larger bandgap (e.g., (AlGa)As). This causes a potential well in which electrons and holes are confined in order to achieve high carrier densities in the active area. Moreover, the smaller refractive index of the surrounding high-bandgap material helps to guide the optical field within the region of highest inversion. Additional ridge-shaped lateral structuring is frequently used to form a complete optical waveguide.



Figure 1 Principle of operation of a semiconductor laser.



Figure 2 Double heterostructure laser diode.

Nowadays, even more advanced laser structures can be fabricated, as modern crystal growth techniques such as molecular beam epitaxy (MBE) and metal organic chemical vapor deposition (MOCVD) have become available. These techniques allow the grower not only to determine the composition of the semiconductors with remarkable precision, but also to define the shape virtually on an atomic scale. In particular, it is now possible to grow microstructures so small that their electronic and optical properties deviate substantially from those of the corresponding bulk materials. So-called quantum-well (QW) structures, in particular, turned out to be superior to bulk materials in many respects and are currently the active medium in most commercial semiconductor lasers. The gain medium in QW laser structures consists of one or more films with a thickness of a few atomic monolayers. These are embedded in a barrier material with a larger bandgap that serves to confine the carriers to the wells. In QWs the quantum confinement restricts the free carrier motion to the two dimensions within the plane of the films, since the well thickness is comparable to or less than the thermal wavelength of the carriers. Hence, one speaks of quasi-two-dimensional structures where no free motion perpendicular to the films is possible. The corresponding energy states of the carriers are quantized, i.e., only discrete values are allowed for that part of the carrier kinetic energy which is related to the confined direction.

A major consequence of this restriction of the carrier motion to two dimensions is a change in the (single particle) density of states. This density of states is altered in QWs in comparison to bulk material. The density of states for bulk material is zero at the bandgap energy and rises with the square root of the energy for higher energies. In contrast, the density of states for a two-dimensional carrier system in a QW is a step-like function with a density of states different from zero at the QW-well bandgap (the bandgap energy of the active material plus the quantization energies of electrons and holes in the well). This increase of the density of states at the bandgap promises important advantages of QW structures over bulk material. Most importantly, the number of states that have to be occupied before inversion is obtained is considerably reduced in QW structures. This reduces the threshold current and increases the modulation speed of the laser structures. Accordingly, most of the modern laser structures are QW structures.

These arguments have encouraged many researchers to develop structures with further increased carrier confinement in two dimensions (quantum wires) and three dimensions (quantum dots). The single-particle density of states is even more favorable in quantum wires and quantum dots than in QWs: in both cases the single-particle density of states peaks at the effective bandgap energy. This argument seems to promise even better performance of quantum wire and quantum dot lasers as compared to QW devices. However, the single-particle density of states description completely neglects the Coulomb interaction of the carriers which strongly influences the optical and electronic properties of semiconductor structures. The absorption is modified by excitonic effects that lead to additional resonances below the bandgap and to changes of the continuum absorption. These changes are often quantified by the so-called Sommerfeld factor, which depends on the dimensionality of the system, i.e., it differs for bulk, QW, quantum wire and quantum dot structures. For example, the Sommerfeld factor completely suppresses the singularity of the density of states at the bandgap of quantum wire structures. Accordingly, with inclusion of Coulomb effects, the benefit of the quantum confinement is much less than expected from the single-particle density of states.

The use of quantum wire and quantum dot structures as a semiconductor laser gain medium is still in its infancy even though they can be grown with various degrees of precision. However, quantum dot structures, especially, hold great promise for the future, since they can be grown in large numbers using techniques similar to those already used for QWs. The possibility of layer growth under strained conditions, such as QWs between barrier material with a slightly different atomic lattice constant, also results in a greater flexibility to design the laser gain medium with the desired emission wavelength.

In principle, the emission wavelength of a semiconductor laser can be roughly designed by the choice of the material. Different semiconductors have different bandgaps between the valence band and conduction band and the bandgap energy determines the spectral range of the emission. One can tune the bandgap and thus the spectral range of the emission by fabricating semiconductor alloys as, e.g., (GaIn)As or (AlGa)As. Presently, a large variety of different materials is commercially available covering, for example, the red ((AlGaIn)P), the near infrared ((AlGa)As, (GaIn)As), the telecom ((GaIn)(AsP)) and even the blue–ultraviolet range ((GaIn)N).

Great care has to be taken that the crystal used for a semiconductor laser is of almost perfect quality. Dislocations in the crystal, for example, have to be avoided as well as any kinds of defects since they act as nonradiative recombination centers. Nonradiative recombination competes with the radiative recombination that is essential for the laser process. Nonradiative recombination effects include Auger recombination and recombination via defects. Auger recombination is the process where an electron and a hole recombine and completely transfer the energy difference to another carrier (electron or hole) which is excited to a higher state. This is an intrinsic effect that depends mainly on the band structure and the relevant values of the transition probabilities (transition matrix elements). The probability for Auger recombination is temperature- and carrier-density-dependent and can be minimized, e.g., by properly cooling the device and by keeping the carrier densities as low as possible.

Nonradiative recombination via defects is an extrinsic effect that depends on the material quality and can thus be minimized by optimized growth. However, trying to avoid dislocations limits the choice of materials for laser structures severely. The growth processes require ‘host’ crystals, so-called substrates, on which the real structure can be grown. GaAs, InP, SiC and sapphire wafers are available in sufficient quality as standard substrates for optoelectronic applications. The epitaxially grown material adapts to the crystal structure of the substrate which implies that the lattice constant of the substrate and structure material should be very similar. If the lattice constants do not agree, i.e., if there is a structural mismatch, a certain amount of strain develops which increases with increasing lattice mismatch. Too much strain leads to the formation of dislocations which are detrimental to laser applications. Control of the dislocation density is currently one of the critical issues for the wide-gap III–V materials, such as GaN, because no substrate is available that matches the GaN lattice constant. However, a small amount of strain is often even desirable as long as it does not cause dislocations. Strain influences the band structure of the material in a predictable way and can therefore be used to tailor the laser emission properties.

Thus laser materials for a certain desired wavelength range have to fulfill two important requirements: first, the bandgap of the material has to fit the desired photon energy; and second, and more crucial, an appropriate substrate with the right lattice constant has to be available. This second condition excludes many material compositions from laser applications. In many cases, both conditions can only be simultaneously met with quaternary semiconductor alloys (for example (GaIn)(AsP) on InP substrates).

Physics of the Gain Medium

From a material physics point of view, the important structural aspects of a certain laser material are summarized in the band structure of the gain medium, i.e., in the quantum mechanically allowed energy states of the material electrons. The calculation of the band structure of a particular gain medium is therefore a crucial aspect of semiconductor laser modelling. Additionally, however, one has to understand the relevant properties of the excited electron–hole plasma in the active region of the laser.

In its ground state, i.e., without excitation and at very low temperatures, a perfect semiconductor is an insulator where no electrons are in the conduction-band states. The presence of a population inversion, i.e., occupied conduction band and empty valence band states in a certain range of frequencies, is, however, a requirement for obtaining optical gain and light amplification from a semiconductor. Sufficiently strong pumping leads to the generation of an electron–hole plasma, where the term ‘electron’ specifically refers to conduction-band electrons and ‘holes’ to the missing electrons in the originally full valence bands. Holes are also quasiparticles, just as the electrons. Electrons in a solid are quasiparticles with an effective mass that is considerably different from the free-electron mass in vacuum and that is determined by the band structure, i.e., the interaction with all the ions of the solid. The properties of the missing electrons, such as a positive charge for the missing negative electron charge, a spin opposite to that of the missing electron, etc., are attributed to the holes. As a consequence of their electrical charges, the excited electrons and holes interact via the Coulomb potential which is repulsive for equal charges (electron–electron, hole–hole) and attractive for opposite charges (electron–hole). Furthermore, electrons and holes obey Fermi–Dirac statistics and the Pauli exclusion principle that forbids two Fermions from occupying the same quantum state. The consequences of the Pauli principle are often referred to as ‘band-filling effects’ in the physics of semiconductor lasers.

The theory therefore has to account not only for the band-structure but also for this band filling, i.e., the detailed population of the electron and hole states. Taking into account only the band structure and band filling leads to a so-called free-carrier theory. But the electron–hole plasma in a semiconductor gain medium is an interacting many-body system because of the carrier interactions and the exclusion principle. In a many-body system the properties of any one carrier are influenced by all the other carriers in their respective quantum states. Generally, advanced many-body techniques are needed to systematically analyze such an interacting electron–hole plasma and to compute the resulting optical properties, such as gain, absorption or refractive index, all of which are changing in a characteristic way with the changing electron–hole density.

It is often helpful to investigate the characteristic time-scales and the most direct consequences of the various interaction effects even though the consequences of the different many-body effects are in general not additive. The fastest interaction, under typical laser conditions, is the carrier–carrier Coulomb scattering that acts on scales of femto- to picoseconds to establish Fermi–Dirac distributions of the carriers within their bands. These distributions are often referred to as 'quasi-equilibrium distributions' since they describe electrons and holes in the conduction and valence bands which may be characterized by an 'electronic temperature' or 'plasma temperature.' The plasma temperature is a measure for the mean kinetic energy of the respective carrier ensemble and relaxes towards the lattice temperature as a consequence of electron–phonon (= quantized lattice vibration) coupling, i.e., the carriers can emit or absorb phonons. The coupling to longitudinal optical phonons in polar materials is especially strong with scattering times in the picosecond range. The corresponding times for the electron–acoustic phonon scattering are in the nanosecond range. Generally, the carrier–phonon interaction provides an exchange of kinetic energy of the carriers with the crystal lattice in addition to the relaxation of the initial nonequilibrium distribution. Deviations between plasma and lattice temperature may occur, especially when lasers are subject to strong pumping or rapid dynamic changes.

The Coulomb interaction not only causes rapid carrier scattering but also directly influences the laser gain spectrum. Gain, i.e., negative absorption, occurs in the spectral region of population inversion, in other words, where the net probability for a test photon to be absorbed is lower than the probability to be amplified by stimulated electron–hole recombination. Energetically, the gain region is bounded from below by the effective (or renormalized) semiconductor bandgap and from above by the electron–hole chemical potential. Here, the chemical potential is the energy at which neither absorption nor amplification occurs, i.e., where the semiconductor medium is effectively transparent.

The effective bandgap energy for elevated carrier densities is significantly below the fundamental absorption edge of an unexcited semiconductor. This 'bandgap renormalization' is a consequence of the fact that the Pauli exclusion principle reduces the repulsive Coulomb interaction between carriers of equal charge. Furthermore, the Coulomb screening, i.e., the density-dependent weakening of the effective Coulomb interaction potential, contributes to the reduction of the bandgap.

Another many-body effect originates in the Coulomb attraction between an electron and a hole, and leads to an excitonic or Coulomb enhancement of the interband transition probability. All these effects contribute to the detailed characteristics of the optical spectra of a semicondcutor gain medium. Figure 3 shows an example of calculated spectra in comparison to experimental data.

The example demonstrates that the microscopic theory correctly accounts for the changes in the gain spectrum with changing carrier density by means of a consistent treatment of band structure, band-filling, and many-body Coulomb effects.

The Resonator

In addition to a gain medium, a laser needs a positive feedback process for the amplified stimulated emission. Hence, the inverted medium has to be



Figure 3 Comparison of experimental and theoretical gain spectra of a (GaIn)(Nas)/GaAs laser.

embedded into a resonator. One of the conceptually simplest versions of such a resonator is a so-called Fabry–Perot resonator which consists of two parallel plane mirrors. A double heterostructure Fabry–Perot laser is shown in Figure 2. Such Fabry–Perot resonators are very easy to fabricate for semiconductor lasers: the semiconductor crystal is cleaved perpendicular to the optical waveguide. The cleaved edges provide a reflectivity of about 32% due to the high refractive index of the semiconductor. This is sufficient to provide enough feedback for laser operation.

However, despite its conceptual simplicity, the cleaved-edge Fabry–Perot concept also introduces a number of problems. First, the light output occurs on two sides of the laser, whereas for most applications all the output power should be emitted out of one facet only. For practical applications, this problem can be solved by depositing coatings onto the cleaved facets of the structure. For example, deposition of a 10% reflectivity coating on one facet and of a 90% reflectivity coating on the other facet concentrates the laser emission almost completely to the facet of lower reflectivity. Antireflection coatings with reflectivities below 10^{-4} are used when laser diodes are coupled to external cavities, e.g., in tunable lasers.

A second problem with Fabry–Perot lasers is that the emission wavelength is often not well defined. A Fabry–Perot resonator of length L (optical length nL) has transmission maxima – so-called modes – at all multiples of $c/2nL$ where c is the speed of light and n the refractive index. That means that for typical devices with a length of 500 μm, hundreds of modes are present even within the limited gain bandwidth of a semiconductor. These modes often compete with each other resulting in multimode emission which may become particularly complex and uncontrollable when the laser is modulated for high-speed operation.

This problem can be overcome in so-called distributed feedback (DFB) lasers. In these devices, the refractive index is periodically modulated along the waveguide. In a simplified picture, this periodic pattern causes multiple reflections at different locations within the waveguide. For certain wavelengths, these multiple reflections interfere constructively to provide enough ‘distributed’ feedback for laser operation. With the DFB concept, single-mode emission can be realized even for high-speed modulation of the lasers. Alternatively, the region of distributed feedback can be separated from the region of amplification in so-called distributed Bragg reflector (DBR) lasers. These are devices with multiple sections where one section is responsible for the optical gain and another section (the DBR section) is responsible for the optical feedback.

So far, we have discussed so-called edge emitting lasers where the light emission is in the plane of the active area of the device. The lengths of these lasers are typically hundreds of microns and thus correspond to a few hundreds of optical wavelengths. This causes one of the major disadvantages of edge emitters – the multimode emission. Another disadvantage is the poor elliptic beam profile due to diffraction at the small rectangular output aperture. Finally, the fabrication procedure of edge emitters is complex since it requires multiple steps of cleaving before it is even possible to test the laser.

A novel alternative semiconductor laser concept was realized in the early 1990s: the vertical-cavity surface-emitting laser (VCSEL). A typical VCSEL structure is shown in Figure 4. In VCSELs, the light emission is parallel to the growth direction, i.e. perpendicular to the epitaxial layers of the structure. The cavity length of a VCSEL is in the order of a few (1–5) multiples of half the wavelength of the emitted light in the material. These small dimensions imply that the interaction length between the active medium and the light field in the resonator is very short. Therefore, the mirrors of a VCSEL have to be of very good quality; reflectivities of more than 99% are required in most configurations.

Very high reflectivities can be achieved with dielectric multilayer structures, so-called Bragg reflectors. Bragg reflectors consist of a series of pairs of layers of different refractive indices, where each layer has the thickness of a quarter of the emission wavelength. Most preferably, Bragg reflectors are epitaxially grown together with the active area of the device in only one growth process.

Small VCSEL resonators with Bragg reflectors at both ends of the cavity are called microcavities. They are designed in such a way that only one longitudinal mode is present in the region of the semiconductor gain spectrum. Accordingly, VCSELs are well suited to provide single-mode characteristics. Moreover, a round aperture for light emission can be realized with a diameter of a few micrometers so that



Figure 4 Vertical-cavity surface-emitting laser (VCSEL).

diffraction is weak and the beam profile is almost perfect.

VCSELs can be tested on wafer without further processing and can be arranged in two-dimensional arrays. A major disadvantage of VCSELs is their temperature dependence. The bandgap of the active material and the cavity mode depend on temperature in such a way that the cavity mode shifts away from the region of maximum gain when the temperature is varied. This severely limits the temperature range of operation for VCSELs.

Semiconductor Laser Dynamics

The dynamical behavior of semiconductor lasers is rather complex because of the coupled electron–hole and light dynamics in the active material. Like other laser materials, semiconductor lasers exhibit a typical threshold behavior when the pump intensity is increased. For weak pumping, the emission is low and spectrally broad; the device operates below threshold and shows (amplified) spontaneous emission. At threshold, the optical gain compensates the losses in the resonator (i.e., internal losses and mirror losses) and lasing action starts. Ideally the output power increases linearly with the injection current above threshold. The derivative of this curve is proportional to the differential quantum efficiency. The differential quantum efficiency can reach values close to unity and even the overall efficiency of the diode laser, i.e., the conversion rate from electrical power into optical power, can be as high as 60% which is far higher than for any other laser material.

Ideally, the laser emission is single mode above threshold. However, as discussed above, edge-emitting diode lasers tend to emit on multiple longitudinal modes and the competition of these modes can lead to complex dynamical behavior which is significantly enhanced as soon as the laser receives small amounts of optical feedback. Semiconductor lasers are extremely sensitive to feedback and tend to show dynamically unstable, often even chaotic, behavior under certain feedback conditions.

Like other lasers, semiconductor lasers respond with relaxation oscillations when they are suddenly switched on or disturbed in stationary operation. Relaxation oscillations are the damped periodic response of the total carrier density and the optical output intensity as a dynamically coupled system. Both are important for many aspects of semiconductor laser dynamics. The relaxation oscillation frequency determines the maximum modulation frequency of diode lasers. This frequency is strongly governed by the differential gain in the active material, i.e., by the variation of the optical gain with carrier density.

An important application of relaxation oscillations is short pulse generation by gain switching of laser diodes. The idea of gain switching is to inject a short and intense current pulse or an optical pump pulse into the laser structure. This pulse initiates relaxation oscillations but it is so short that already the second oscillation maximum is not amplified. As a consequence, only one intense pulse is emitted. The shortest pulse widths achieved with this scheme so far are in the few picoseconds range. For short pulse generation, a further complexity of the diode laser comes into play. The emitted pulses are observed to be strongly chirped, i.e., the center frequency changes during the pulse. This complex self-phase-modulation is a result of the strong coupling of the real and the imaginary parts of the susceptibility in the semiconductor. If the gain (which is basically given by the imaginary part of the susceptibility) changes during a pulse emission, the refractive index (basically the real part of the susceptibilty) also changes considerably. This leads to a self-phase-modulation if a strong optical pulse is emitted. This strong phase–amplitude coupling is also responsible for the high feedback sensitivity of diode lasers, for complex spatio-temporal dynamics (e.g., self-focusing, filamentation), and for a considerable broadening of the emission linewidth. The phase–amplitude coupling is often quantified with the so-called linewidth enhancement or α factor. This parameter, however, is a function of carrier density, photon wavelength, and temperature.

Diode lasers are also suited for the generation or amplification of extremely short pulses with durations below 1 picosecond. The concept used for such extremely short pulse generation is called mode-locking. The idea of mode-locking is to synchronize the longitudinal modes of the laser so that their superposition is a sequence of short pulses. The most successful concept to achieve mode-locking of diode lasers is to introduce a saturable absorber into the laser cavity and to additionally modulate the injection current synchronously to the cavity roundtrip frequency. A saturable absorber exhibits nonlinear absorption characteristics: the absorption is high for weak intensities and weak for high intensities so that high peak power pulses are supported. Such absorbers can be integrated as a separate section into multiple-section diode lasers which have already been successfully used for subpicosecond pulse generation. Furthermore, electro-absorption modulators, passive waveguide sections, and tunable DBR segments for wavelength tuning can also be integrated into such multiple-section devices.

However, when subpicosecond pulses are generated or amplified in semiconductor laser amplifiers the dynamics of the pulse generation or pulse amplification is strongly governed by complex nonequilibrium carrier dynamics in the semiconductor. The most prominent effects are spectral hole burning and carrier heating. Spectral hole burning occurs if an intense laser field removes carriers from a certain area in *k*-space faster than carrier–carrier scattering can compensate for. This leads to nonthermal carrier distributions and a gain suppression in certain energy regimes. As mentioned above, a nonthermal carrier distribution relaxes quickly (100 femtoseconds) into a thermal (quasi-equilibrium) distribution if the intense laser field is switched off, but this carrier distribution may have a plasma temperature much higher than the lattice temperature. This effect, which is referred to as carrier heating, also leads to a transient reduction of the gain on a few picoseconds timescale until the carrier distributions have cooled down to the lattice temperature by interactions with phonons. These ultrafast effects are of course particularly important for amplification and generation of short pulses but they generally influence the whole dynamical behavior of diode lasers including, e.g., the modulation behavior.

See also

Coherent Transients: Ultrafast Studies of Semiconductors. **Quantum Optics:** Entanglement and Quantum Information.

Further Reading

Chow WW and Koch SW (1999) *Semiconductor-Laser Fundamentals: Physics of the Gain Materials*. Berlin: Springer-Verlag.

Chuang SL (1995) *Physics of Optoelectronic Devices*. New York: Wiley.

Delfyett PJ, Dienes A, Heritage JP, Hong MY and Chang YH (1994) Femtosecond hybrid mode-locked semiconductor laser and amplifier dynamics. *Applied Physics* B 58: 183–195.

Haug H and Koch SW (2004) *Quantum Theory of the Optical and Electronic Properties of Semiconductors*, 4th edn. Singapore: World Scientific Publisher.

Hofmann M (1999) Gain and emission dynamics of semiconductor lasers. *Recent Research Developments, in Applied Physics* 2: 269–290.

Koch SW, Jahnke F and Chow WW (1995) Physics of semiconductor microcavity lasers, review article. *Semiconductor Science and Technology* 10: 739–751.

Osinski M and Buus J (1987) Linewidth broadening factor in semiconductor lasers – an overview. *IEEE Journal of Quantum Electronics* QE-23: 9–29.

Up-Conversion Lasers

A Brenier, University of Lyon, Villeurbanne, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Under photoluminescence excitation, a luminescent center located inside a transparent material usually emits at a longer wavelength than the excitation. This is because of the existence of de-excitation losses inside the material. Thus, efficient down-conversion lasers can be built, for example, the commercial Nd^{3+}:$Y_3Al_5O_{12}$ laser which works at 1064 nm, under usual pumping near 800 nm. More surprisingly, it has been demonstrated that fluorescence can also be emitted at shorter wavelength than the excitation. This is possible if the losses are reduced and overcome by so-called ‘up conversion mechanisms’. Generally speaking, a laser emitting at a shorter wavelength than the excitation is classified as an up-conversion laser.

These lasers are able to generate coherent light in the red, green, blue, and uv spectral ranges. A point of practical importance is that some of them can be pumped in the near-infrared range (around 800 nm or 980 nm) by commercially available laser diodes. They can be based on all-solid-state technology and share its advantages: compactness of devices, low maintenance, and efficiency. They are needed for a variety of applications: color displays, high density optical data storage, laser printing, biotechnology, submarine communications, gas-laser replacement, etc.

Because the emitted photons have higher energy than the excitation ones, more than one pump photon is needed to generate a single laser photon, so the physical processes involved in the up-conversion laser are essentially nonlinear. Two kinds of laser devices can be considered. In the first one, the excitation of the luminescent center up-migrates through the electronic levels and reaches the initial laser level. This step is due to some luminescence mechanisms. Then, in a second step, lasing at a short wavelength occurs through a transition towards the final laser level. In the second kind of device, the pump excitation activates a down-conversion lasing, but the laser wave is maintained inside the cavity, cannot escape, and is up-converted in short wavelengths by the second-order nonlinear susceptibility of the crystal host. This requires bifunctional nonlinear optical and laser crystals. The device is thus a self-frequency doubling laser or a self-sum frequency mixing laser. If the nonlinearity is not an intrinsic property of the laser crystal but is due to a second nonlinear optical crystal located inside or outside the cavity, the device operates intracavity or extracavity up conversion.

Up-Conversion from Luminescence Mechanisms

The numerous $^{2S+1}L_J$ energy levels ($4f^n$ configuration) of the trivalent rare earth ions, inserted in crystals or glasses, offer many possibilities for up conversion, particularly from long-lived intermediate levels that can be populated with infrared pumping. Crystal field induced transitions between them are comprised of sharp lines, because the $4f^n$ electrons are protected from external electric fields by the $5s^2p^6$ electrons. Their fluorescence spectra can exhibit cross-sections high enough (10^{-19} cm^2) to lead to laser operation in the visible range. For up-conversion purposes, the most popular ions are Er^{3+}, Pr^{3+}, Tm^{3+}, Ho^{3+}, and Nd^{3+}. Up conversion in Er^{3+} was used for the first time in 1959, to detect infrared radiation.

Energy Transfers

Two ions in close proximity interact electrostatically (Coulomb interaction) and can exchange energy. The ion which gives energy is called the sensitizer S or donor, and the energy receiving ion is the activator A or acceptor. Two examples discussed below are shown in Figure 1. The most typical case of such nonradiative energy transfer in trivalent rare earth ions in insulating materials is due to electrical dipole–dipole interaction. For the latter, the transition probability $W(\mathrm{s}^{-1})$ takes the form:

$$W = \frac{3\hbar^4 c^4}{4\pi n^4}\frac{1}{R^6}\frac{Q_A}{\tau_{\mathrm{rad}}}\int \frac{f_A(E) f_S(E)}{E^4}\,\mathrm{d}E \qquad [1]$$

where R is the S–A distance, E is the photon energy of the transition operated by each ion, n the refractive index, and Q_A is the integrated absorption cross-section of the A-transition:

$$Q_A = \int \sigma_A(E)\,\mathrm{d}E, \qquad f_A = \frac{\sigma_A}{Q_A} \qquad [2]$$

In eqn [1], τ_{rad} is the radiative emission probability of S for the involved transition calculated from the emission probability A_S:

$$\frac{1}{\tau_{\mathrm{rad}}} = \int A_S(E)\,\mathrm{d}E, \qquad f_S = \tau_{\mathrm{rad}} A_S \qquad [3]$$

The integral in eqn [1] is called the overlap integral and shows that the transfer is efficient if the luminescence spectrum of S is resonant with the absorption spectrum of A (corresponding to the S and A transitions involved in the nonradiative transfer). The transitions are often not in perfect resonance but remain efficient enough to be used in practice. Then the energy mismatch is compensated by phonons, and the energy transfer is said to be phonon-assisted.

The energy transfer visualized in Figure 1a is an up-conversion cross-relaxation. It is often met in the rare earth ions cited above when they are sufficiently concentrated in the material. The S and A ions can be of the same or of different chemical species. Successive energy transfers can promote the activator from its ground state towards higher energy levels, up to the one from which lasing can occur. This is the so-called 'Addition de Photons par Transferts d'Energie', sometimes appointed 'APTE'. Yb^{3+} is the most used ion as sensitizer and leads to the following transfers in examples of Er^{3+} or Ho^{3+} co-doping:

$$\begin{aligned} &^2F_{5/2}(\mathrm{Yb}) + {}^4I_{15/2}(\mathrm{Er}) \rightarrow {}^2F_{7/2}(\mathrm{Yb}) + {}^4I_{11/2}(\mathrm{Er}) \\ &^2F_{5/2}(\mathrm{Yb}) + {}^4I_{11/2}(\mathrm{Er}) \rightarrow {}^2F_{7/2}(\mathrm{Yb}) + {}^4F_{7/2}(\mathrm{Er}) \end{aligned} \qquad [4]$$

$$\begin{aligned} &^2F_{5/2}(\mathrm{Yb}) + {}^5I_8(\mathrm{Ho}) \rightarrow {}^2F_{7/2}(\mathrm{Yb}) + {}^5I_6(\mathrm{Ho}) \\ &^2F_{5/2}(\mathrm{Yb}) + {}^5I_6(\mathrm{Ho}) \rightarrow {}^2F_{7/2}(\mathrm{Yb}) + {}^5S_2(\mathrm{Ho}) \end{aligned} \qquad [5]$$

If several sensitizers give their energy simultaneously to a single activator, promoting it directly from its ground state towards a high energy level without intermediate levels, the sensitization is said to be 'cooperative'.



Figure 1 (a) Up-conversion cross-relaxation energy transfer. (b) Down-conversion cross-relaxation energy transfer. The example in (a) is phonon assisted, the example in (b) is resonant.

The energy transfer shown in Figure 1b is a down-conversion cross-relaxation. It is the inverse of the previous one. At first sight it is, of course, undesirable in an up-conversion laser. However, we notice that one ion in the upper level will lead to two ions in the intermediate level. This fact can be exploited in special conditions (see below) and be beneficial for up conversion.

The dynamical study of the energy transfers, starting from the microscopic point of view contained in eqn [1], is very complicated because of the random locations of the ions or because of other processes, such as energy migration among sensitizers and back transfers. A popular method leading to useful predictions in practice is the rate equation analysis dealing with average parameters. The time evolution of the population densities n_i of the various levels i are described by first-order coupled equations, solved with adequate initial conditions and including the pumping rate. As an example, the rate equations for levels 1 and 2 in Figure 1a take the form:

$$\frac{\mathrm{d}n_1}{\mathrm{d}t} = -\frac{n_1}{\tau_1} - 2kn_1^2 + \frac{\beta_{21}}{\tau_2}n_2 + W \qquad [6]$$

$$\frac{\mathrm{d}n_2}{\mathrm{d}t} = -\frac{n_2}{\tau_2} + kn_1^2 \qquad [7]$$

$$n_0 + n_1 + n_2 = 1 \qquad [8]$$

where $\tau_{1,2}$ are the lifetimes of levels 1 and 2, k is the up-conversion transfer rate, β_{21} is the branching ratio for the 2 → 1 transition, and W is the pump rate (not shown in Figure 1).

Sequential Two-Photon Absorption

Pumping the ground state of a luminescent ion (Figure 2a) with a wave at angular frequency ω, leads to population with density n_1 of an excited state in a first step. Because the rare earth ions have numerous energy levels, it is possible for the pump to also be resonant with the transition from level 1 towards a higher energy level 2, and is further absorbed. Such a process leading to n_2 up-conversion population is a sequential two-photon absorption. If there is no $1 \rightarrow 2$ resonant transition for the ω frequency, it is possible to use a second pump wave at a different angular frequency ω' resonant with the $1 \rightarrow 2$ transition (Figure 2b). Of course, in practice, it is advantageous when a single pump beam is required for up conversion.

Let us show the relevant terms of the rate equation analysis describing the process in Figure 2a:

$$\frac{\mathrm{d}n_1}{\mathrm{d}t} = -\frac{n_1}{\tau_1} + I\sigma_0 n_0 - I\sigma_1 n_1 + \frac{\beta_{21}}{\tau_2}n_2 \qquad [9]$$

$$\frac{\mathrm{d}n_2}{\mathrm{d}t} = -\frac{n_2}{\tau_2} + I\sigma_1 n_1 \qquad [10]$$

$$n_0 + n_1 + n_2 = 1 \qquad [11]$$

where I is the photon density of the pump (photons $\mathrm{s}^{-1}\,\mathrm{cm}^{-2}$) and σ_0 and σ_1 are the absorption cross-sections (cm^2) of the $0 \rightarrow 1$ and $1 \rightarrow 2$ transitions, respectively. The n_2 population density shows a nonlinear I dependence, most often close to I^2.

Photon Avalanche

In rare earth doped materials, an up-conversion emission, intense enough for visible lasing, can result from a more complex mechanism. In this case, absorption of the pump is not resonant with a transition from the ground state (weak ground-state absorption), but on the contrary, the photon pump energy matches the gap between two excited states (high excited state absorption). These levels are labeled 1 and 2 in Figure 3. Level 1 generally has a rather long lifetime in order to accumulate



Figure 2 Two-photon absorption up-conversion.



Figure 3 Photon avalanche up-conversion.

population and level 2 is the initial up-conversion laser level. When the pump light is turned on, the populations of levels 1 and 2 first grow slowly, and then can accelerate exponentially. This is generally referred to as ‘photon avalanche’. The term ‘looping mechanism’ also applies, because we can see in Figure 3 that the excited state absorption 1 → 2 is followed by a cross-relaxation energy transfer (quantum efficiency up to two) that returns the system back to level 1. So after one loop, the n_1 population density has been amplified, and is further increased after successive loops. This pumping scheme was discovered in 1979, with $LaCl_3$:Pr^{3+} crystal used as an infrared photon counter.

The rate equation analysis applied to the three-level system in Figure 3 leads to the following time evolutions:

$$\frac{dn_1}{dt} = -\frac{n_1}{\tau_1} + I\sigma_0 n_0 - I\sigma_1 n_1 + \frac{\beta_{21}}{\tau_2} n_2 + 2kn_0 n_2 \qquad [12]$$

$$\frac{dn_2}{dt} = -\frac{n_2}{\tau_2} + I\sigma_1 n_1 - kn_0 n_2 \qquad [13]$$

$$n_0 + n_1 + n_2 = 1 \qquad [14]$$

where the parameters have the same meaning as in eqns [6]–[11].

The steady state limit of the populations at infinite time, upon continuous excitation starting at $t = 0$, can be obtained from canceling the time derivative in the left-hand side of the equation. Let us point out the interesting result. Two different dynamical regimes and analytical expressions for $n_2(\infty)$ are obtained. In the usual case of low pumping rate in the ground state and if the parameters of the systems satisfy: $k < \frac{1-\beta_{21}}{\tau_2}$, then the first regime is observed, whatever the pumping rate $I\sigma_1$ in the excited state.

If the parameters satisfy:

$$k > \frac{1-\beta_{21}}{\tau_2} \qquad [15]$$

the first regime is still observed at low pumping rate $I\sigma_1$ in the excited state, more precisely at pumping rate low enough such that

$$I\sigma_1 < \frac{\left(k + \dfrac{1}{\tau_2}\right)\dfrac{1}{\tau_1}}{k - \dfrac{(1-b_{21})}{\tau_2}}$$

But interestingly, the second regime, the so-called photon avalanche, is obtained at high pumping rate $I\sigma_1$ in the excited state, that is to say if:

$$I\sigma_1 > \frac{\left(k + \dfrac{1}{\tau_2}\right)\dfrac{1}{\tau_1}}{k - \dfrac{(1-b_{21})}{\tau_2}} \qquad [16]$$

So the right-hand side of eqn [16] appears to be a pump threshold separating two dynamical regimes when the condition in eqn [15] is satisfied, as the insert in Figure 3 shows.

Another way to distinguish between the two regimes is given by linearization of the system of eqns [12]–[14] ($n_0 \cong 1$). Then the description will only be valid close to $t = 0$. We know from standard mathematical methods that the solutions of eqns [12]–[14] are then a combination of $\exp(\alpha t)$ terms. If the threshold condition in eqn [16] is satisfied, a parameter α in the combination becomes positive, so the population of level 2 increases exponentially (photon avalanche) at early times and the dynamics of the system is unstable.

The physical meaning of eqns [15] and [16] is clarified by introducing the yield η_{CR} of the cross-relaxation process:

$$\eta_{CR} = \frac{k}{k + 1/\tau_2} \qquad [17]$$

and the yield η of the 2 → 1 de-excitation:

$$\eta = \frac{b_{21}/\tau_2}{k + 1/\tau_2} \qquad [18]$$

Then, the threshold condition in eqn [16] can be written as:

$$\left(\frac{I\sigma_1}{I\sigma_1 + 1/\tau_1}\right)(2\eta_{CR} + \eta) > 1 \qquad [19]$$

Starting with one ion in level 1, the first parenthesis in eqn [19] is the yield with which it will be promoted to level 2, and the second parenthesis is the yield of the backward path 2 → 1. So, the left-hand side of eqn [19] is the new number of ions after a looping path 1 → 2 → 1, which has to be higher than 1 for the avalanche to occur. If we consider a lot of successive loops, the origin of the exponential behavior is clear. The role of the first ion in level 1 (and the weak pumping rate in the ground state $I\sigma_0$) is limited to initialize the process. Note that the value of the first parenthesis in eqn [19] is less than 1, so the second parenthesis has to be higher than 1. This condition is equivalent to eqn [15].

Materials: The Energy Gap Law

As we can see from the above mechanisms, up conversion needs intermediate energy levels and is not efficient if these cannot accumulate populations due to a short lifetime. The spontaneous rate of de-excitation of an electronic level is the sum of a radiative part W^{rad} and of a nonradiative part W^{nrad}. The radiative part can be obtained through the absorption cross-section corresponding to the transition or from the Judd–Ofelt theory which also exploits the absorption spectrum. The nonradiative rate is then obtained by subtracting W^{rad} from the measured fluorescence decay rate of the level. Based on the measurements in many hosts for the different trivalent rare earth ions, at different temperatures, the nonradiative decay rate of a J-level towards the next lower J′-level was found to have the form:

$$W_{\mathrm{JJ'}}^{\mathrm{nrad}} = B\exp(-\beta\Delta E_{\mathrm{JJ'}})\left(1-\exp\left(-\frac{\omega_{\max}}{kT}\right)\right)^{-p} \qquad [20]$$

where $\Delta E_{\mathrm{JJ'}}$ is the energy gap between the two levels, $p = \Delta E_{\mathrm{JJ'}}/\omega_{\max}$, $\omega_{\max}$ being the energy of an effective optical phonon of the host. The values of B, β and $\omega_{\max}$ are found by fitting with experimental data. An example of such a fit is represented in Figure 4.

Equation [20] is the well-known and familiar 'energy gap law'. We have represented it for several oxide and nonoxide hosts at $T = 300$ K in Figure 5. It is clear that chloride, bromide, fluoride will be favorable hosts for up conversion due to their low phonon energy (LaBr$_3$: $\omega_{\max} = 175\ \mathrm{cm}^{-1}$, LiYF$_4$: $\omega_{\max} = 400\ \mathrm{cm}^{-1}$, Y$_3Al_5O_{12}$: $\omega_{\max} = 700\ \mathrm{cm}^{-1}$, silicate glass: $\omega_{\max} = 1100\ \mathrm{cm}^{-1}$). Let us mention also a fluorozirconate glass, ZBLAN, widely used in up-conversion fiber lasers.



Figure 4 Energy-gap dependence of nonradiative decay rates in YAlO$_3$.



Figure 5 Energy-gap law for different hosts at 300 K.

Up-Conversion from Second-Order Optical Nonlinearity

The inter-atomic electric field acting on the electrons inside a medium has a magnitude of $\sim 10^8$ V/cm and derives from a potential that is anharmonic. The electric field **E** of an electromagnetic wave propagating through the medium drives the electrons beyond the quadratic region of the potential in the case of high **E**. So, the electron response and the associated polarization **P** take the form of a function of **E**:

$$\mathbf{P}(\mathbf{E}) = \mathscr{E}_0(\chi^{(1)} : \mathbf{E} + \chi^{(2)} : \mathbf{E}^2 + \chi^{(3)} : \mathbf{E}^3 + \cdots) \qquad [21]$$

The different terms in eqn [21] are responsible for many optical phenomena because in Maxwell electromagnetic theory, the polarization is the source of the waves. We have selected in Table 1 the terms relevant for linear effects and for the purpose of frequency up conversions: second-harmonic generation (SHG) and sum-frequency mixing, due to second-order terms. It should be noticed that the latter have a nonzero value only in noncentrosymmetric materials.

Figure 6 visualizes the up conversion from SHG: two photons of the fundamental field at angular frequency ω_1 are annihilated while one photon at twice the angular frequency is created. A similar picture could be drawn for sum-frequency up conversion: SHG is the degenerate case where $\omega_1 = \omega_2$.

The second-order nonlinear processes have an efficiency given by an effective coefficient d_{eff} given hereafter:

$$d_{\mathrm{eff}} = \sum_{ijk} e_i(\omega_3)d_{ijk}e_j(\omega_1)e_k(\omega_2) \qquad [22]$$

where $e_i(\omega_l)$ is the ith component of the unit vector of the electric field of the wave l at angular frequency ω_l and $d_{ijk} = (1/2)\chi_{ijk}$.

Table 1 Relevant terms for frequency up-conversion

Optical process	*Term*	*New wave*
Linear		
Refractive index, absorption, stimulated emission	$\chi^{(1)}(-\omega;\omega)$	
Second order nonlinear		
Second harmonic generation	$\chi^{(2)}(-\omega_3;\omega_1,\omega_1)$	$\omega_3 = 2\omega_1$
Sum-frequency mixing	$\chi^{(2)}(-\omega_3;\omega_1,\pm\omega_2)$	$\omega_3 = \omega_1 + \omega_2$



Figure 6 Up-conversion from second harmonic generation.

Moreover, the wave propagation equations in the slow varying envelope approximation, given hereafter for the E_3 electric field of the sum-frequency mixing wave:

$$\frac{dE_3}{dz} = \frac{i\omega_3 d_{\mathrm{eff}}}{n_3 c} E_1 E_2 \quad \exp(i(k_1 + k_2 - k_3)z) \qquad [23]$$

$$(\text{with } k_j = \omega_j n_j / c)$$

impose that the frequency conversion is efficient in practice, only if the following phase matching condition is satisfied:

$$\omega_1 n_1 \uparrow (\theta, \varphi) + \omega_2 n_2 \uparrow (\theta, \varphi) = \omega_3 n_3 \downarrow (\theta, \varphi) \qquad [24]$$

where $n_i \uparrow$ and $n_i \downarrow$ are respectively the upper and lower refractive index in the direction of propagation (θ, φ) (n_i in eqn [23] are the same with a simplified notation). Equation [24] is restricted here for simplicity to collinear type I (waves 1 and 2 and the same polarization) and is the expression of photon momentum conservation. It is usually achieved from the birefringence of the crystals. When this is not possible, another technique can be used, namely quasi-phase matching, which involves reversing periodically the sign of the nonlinear optical coefficient.

In bifunctional crystals, the laser effect and the $\chi^{(2)}$ interaction occur simultaneously inside the same crystal. In the case of the self-frequency doubling laser, the angular frequency $\omega_1 = \omega_2$ in eqn [24] is that of the fundamental laser wave. In the case of the self-sum frequency mixing laser, ω_1 corresponds to the fundamental laser wave and ω_2 to the pump wave. As we can see from eqns [22]–[24], the polarization of the laser emission is crucial in order for the device to work. So, the laser stimulated emission cross-section σ for propagation in the phase matching direction (θ, ϕ) in the adequate polarization has to be evaluated. This can be performed with the formula:

$$\sigma(\theta, \varphi) = \frac{\sigma_X \sigma_Y \sigma_Z}{\sqrt{\sigma_Y^2 \sigma_Z^2 e_X^2 + \sigma_X^2 \sigma_Z^2 e_Y^2 + \sigma_X^2 \sigma_Y^2 e_Z^2}} \qquad [25]$$

where $\sigma_{X,Y,Z}$ are the emission cross-sections for X, Y, Z-polarizations and $e_{X,Y,Z}$ are the components of the unit vector or the electric field of the laser wave.

To summarize, the conditions necessary for a crystal to be a bi-functional material are: (i) it must be noncentrosymmetric; (ii) it must accept fluorescent doping (usually with Nd^{3+} or Yb^{3+}); and (iii) it must be phase matchable for its laser emission. In practice, only a few crystals satisfy these requirements and have been tried with some success. The main ones are $LiNbO_3$, $LaBGeO_5$, $Ba_2NaNb_5O_{15}$, β'-$Gd_2(MoO_4)_3$, $YAl_3(BO_3)_4$, $GdAl_3(BO_3)_4$, $CaY_4(BO_3)_3O$, and $CaGd_4(BO_3)_3O$.

Up-Conversion Lasers Based on Luminescence Mechanisms in Materials

Energy Transfers

Up-conversion lasers from energy transfers have the advantage of using a single pump laser. This latter populates firstly a long-lived intermediate level. A typical example, based on $LiYF_4{:}Er^{3+}$ crystal, is provided by Figure 7.

The pump at 802 nm from a GaAlAs diode laser, or at 969 nm, populates efficiently at the 8 ms lifetime $^4I_{11/2}$ level. The green laser, at 551 nm, corresponds to the $^4S_{3/2} \rightarrow {}^4I_{15/2}$ transition and it can be shown that energy transfer is an essential part of the mechanism by stopping abruptly the pump laser: green lasing continues to occur for several hundred microseconds because the $^4S_{3/2}$ level is still fed (an excited-state absorption would stop immediately). The involved energy transfer is:

$$^4I_{11/2} + {}^4I_{11/2} \rightarrow {}^4F_{7/2} + {}^4I_{15/2} \qquad [26]$$

and leads to a 20 mW laser threshold and 2.3 mW green output power at 50 K temperature upon 95 mW of incident power.

By using mirrors with high transmission in the green range but having high reflectivity at blue wavelengths, blue laser emission at 470 nm can be sustained, corresponding to the $^2P_{3/2} \rightarrow {}^4I_{11/2}$ transition. It originates from a mechanism involving three up-conversion energy transfers:

$$\begin{aligned} &^4I_{11/2} + {}^4I_{11/2} \rightarrow {}^4F_{7/2} + {}^4I_{15/2} \\ &^4I_{11/2} + {}^4I_{13/2} \rightarrow {}^4F_{9/2} + {}^4I_{15/2} \qquad [27] \\ &^4S_{3/2} + {}^4F_{9/2} \rightarrow {}^4I_{15/2} + {}^2K_{13/2} \end{aligned}$$



Figure 7 Energy level diagram of LiYF$_4$:Er^{3+}. The dashed lines indicate the energy transfers responsible for the green and blue up-conversion lasing. Reproduced with permission of American Institute of Physics from Macfarlane RM, Tong F, Silversmith AJ and Lenth W (1988) Violet CW neodymium upconversion lasers. *Applied Physics Letters* 52(16): 1300.

The illustration in Figure 7 shows up-conversion energy transfers between ions of the same chemical species, but co-doping the laser host with two ions of different chemical species provides the opportunity of separating their roles: one species is devoted to pump absorption (this is the sensitizer) and the other one is devoted to lasing (this is the activator). Due to the development of efficient semiconductor InGaAs diodes emitting near 980 nm, the most widely used sensitizer is Yb^{3+}. Table 2 provides a list of several up-conversion lasers based on energy transfer mechanisms, operating at room temperature. We can see that among the most efficient lasers, are those based on rare-earth ions doped glass fibers. The reason is that in fibers, the pump and laser waves remain confined inside a core (typically 5 μm diameter) and have high energy densities over a long length (tenths of cms), which is favorable for all up-conversion mechanisms.

Sequential Two-Photon Absorption

An example of an up-conversion laser pumped by a two-photon absorption mechanism is represented in Figure 8. The material is LaF$_3$:Nd^{3+} and violet lasing at 380 nm corresponds to the $^4D_{3/2} \rightarrow {}^4I_{11/2}$ transition.

Transition from the ground state up to the $^4F_{5/2}$ level is firstly obtained from an infrared beam at 790 nm in order to feed the $^4F_{3/2}$ intermediate level after a fast nonradiative de-excitation. The $^4F_{3/2}$ level has a rather long lifetime: 700 μs, so it accumulates

Table 2 Main room temperature up-conversion lasers operating from energy transfers

Laser material	*Laser wavelength (nm)*	*Pump wavelength (nm)*	*Output power*
BaY$_{1.4}$Yb$_{0.59}$Ho$_{0.01}$F$_8$	670	1540 + 1054	
BaYYb$_{0.998}$Tm$_{0.002}$F$_8$	649	1054	1%
BaYYb$_{0.99}$Tm$_{0.01}$F$_8$	799–649–510–455	960	
BaYYb$_{0.99}$Tm$_{0.01}$F$_8$	348	960	
LiYF$_4$:Er(1%):Yb(3%)	551	966	37 mW
LiY$_{0.89}$Yb$_{0.1}$Tm$_{0.01}$F$_4$	810–792	969	80 mW
LiY$_{0.89}$Yb$_{0.1}$Tm$_{0.01}$F$_4$	650	969	5 mW
LiKYF$_5$:Er (1%)	550	808	150 mW
Fiber:Yb:Pr	635	849	20 mW
Fiber:Yb:Pr	635	1016	6.2 mW
Fiber:Yb:Pr	521	833	0.7 mW
Fiber:Yb:Pr	635	860	4 mW



Figure 8 Simplified energy level diagram of LaF$_3$:Nd^{3+} and up-conversion lasing from two-photon absorption. (a) Two different pump wavelengths, (b) doubly resonant single pump wavelength. Reproduced with permission of American Institute of Physics from Lenth W, Silversmith AJ and Macfarlane RM (1988) Green infrared pumped erbium up conversion lasers. In: TAM AC, Gole JL and Stwalley WC (eds) *Advances in Laser Science – III*. AIP Conference Proceedings n°172: 8–12.

enough population that a second yellow pumping at 591 nm (Figure 8a) can efficiently populate the $^4D_{3/2}$ initial laser level. With 110 mW of infrared pump and 300 mW of yellow pump, 12 mW of violet output were obtained at 20 K temperature.

A simpler device is obtained if a single-pump beam is used. This is the case in Figure 8b, where a yellow pump at 578 nm provides both ground state and excited state absorption. This doubly resonant scheme is less efficient in LaF$_3$:Nd^{3+} than the previous one but in Figure 9, we show another example: LiYF$_4$:Er^{3+}, working at room temperature. The lasing $^4S_{3/2} \rightarrow {}^4I_{15/2}$ transition at 551 nm delivers 20 mW upon 1600 mW pumping at 974 nm.

The simplified Er^{3+} level scheme of Figure 9 contains four main levels with population densities: $n_0 = [^4I_{15/2}]$, $n_1 = [^4I_{13/2}]$, $n_2 = [^4I_{11/2}]$, $n_3 = [^4S_{3/2}]$. The rate equations of populations of this system can



Figure 9 Simplified energy level diagram of LiYF$_4$:Er^{3+} and up-conversion lasing from two-photon absorption (doubly resonant). Reproduced with permission of Institute of Physics Publishing from Huber G (1999) Visible cw solid-state lasers. *Advances in Lasers and Applications*, Bristol and Philadelphia: Scottish Universities Summer School in Physics & Institute of Physics Publishing, 19.

Table 3 Main room temperature up-conversion lasers operating from two-photon absorption

Laser material	*Laser wavelength (nm)*	*Pump wavelength (nm)*	*Output power*
Y$_3$Al$_5$O$_{12}$:Er 1%	561	647 + 810	
LiYF$_4$:Er 1%	551	647 + 810	0.95 mJ
LiYF$_4$:Er 1%	551	810	40 mW
LiYF$_4$:Er 1%	551	974	45 mW
LiYF$_4$:Er	551	974	20 mW
KYF$_4$:Er 1%	562	647 + 810	0.95 mJ
LiLuF$_4$:Er	552	974	70 mW
LiLuF$_4$:Er	552	970	213 mW
LiYF$_4$:Tm 1%	453–450	781 + 649	0.2 mJ
Fiber:Tm	480	1120	57 mW
Fiber:Tm	480	1100–1180	45 mW
Fiber:Tm	455	645 + 1064	3 mW
Fiber:Tm	803–816	1064	1.2 W
Fiber:Tm	482	1123	120 mW
Fiber:Yb:Tm	650	1120	
Fiber:Ho	540–553	643	38 mW
Fiber:Ho	544–549	645	20 mW
Fiber:Er	548	800	15 mW
Fiber:Er	546	801	23 mW
Fiber:Er	544	971	12 mW
Fiber:Er	543	800	
Fiber:Pr	635	1010 + 835	180 mW
Fiber:Pr	605	1010 + 835	30 mW
Fiber:Pr	635	1020 + 840	54 mW
Fiber:Pr	520	1020 + 840	20 mW
Fiber:Pr	491	1020 + 840	7 mW
Fiber:Nd	381	590	74 μW
Fiber:Nd	412	590	500 μW

be written and solved because all the implied parameters (lifetimes, branching ratios, ground, and excited states absorption cross-sections) have been measured in this material. Predictive models of the up-conversion green laser are successful, matching experimental measurements, and confirm that the doubly resonant mechanism is realistic at low doping concentration.

Table 3 summarizes the performances of the main up-conversion lasers based on sequential photon absorption and working at room temperature.

Photon Avalanche

Photon avalanche up-conversion was observed mainly in Nd^{3+}, Tm^{3+}, Er^{3+}, and Pr^{3+} doped materials. As an illustration of this mechanism, let us consider the case of the continuous wave Pr^{3+}–Yb^{3+}-doped fluorozirconate fiber laser (3000 ppm Pr, 20 000 ppm Yb). With two Ti:sapphire pump lasers operating at 852 and 826 nm (Figure 10), an output power at 635 nm as high as 1.02 W was obtained with an incident pump power of 5.51 W (19% slope efficiency).



Figure 10 Experimental set-up for Yb–Pr-doped fiber up-conversion laser. M1: dichroic mirror, C1, C2: lenses, M2 dichroic input mirror. Reproduced with permission of Optical Society of America from Sandrock T, Scheife H, Heumann E and Huber G (1997) High power continuous wave up-conversion fiber laser at room temperature. *Optics Letters* 22(11): 809.

This remarkable result can be explained quantitatively by modeling the photon avalanche with a five-level diagram and restricted in Figure 11 to a single laser pump at 850 nm. The laser emission corresponds to the $^3P_0 \rightarrow {}^3F_2$ transition. The five relevant levels have the population densities: $n_0 = [^3H_4(Pr)]$, $n_1 = [^1G_4(Pr)]$, $n_2 = [^3P_0(Pr)]$, $n_3 = [^2F_{7/2}(Yb)]$, $n_4 = [^2F_{5/2}(Yb)]$.

The two components of the mechanism are:

(i) the excited state absorption of the pump by the spin allowed transition: $^1G_4 \rightarrow {}^1I_6$

(ii) the process leading to the doubling of the $^1G_4$ population, in this instance through two energy transfers:

$$\begin{aligned} &^1I_6(Pr) + {}^2F_{7/2}(Yb) \rightarrow {}^1G_4(Pr) + {}^2F_{5/2}(Yb) \\ &^2F_{5/2}(Yb) + {}^3H_4(Pr) \rightarrow {}^2F_{7/2}(Yb) + {}^1G_4(Pr) \end{aligned} \qquad [28]$$

The rate equation analysis predicts that the avalanche threshold occurs at about 1 W pump and the long fluorescence rise time is somewhat shortened at higher pump power, as observed experimentally.



Figure 11 Energy level diagram of fluorozirconate: Yb^{3+}:Pr^{3+} fiber. The dashed lines indicate the energy transfers. Reproduced with permission of the Optical Society of America from Sandrock T, Scheife H, Heumann E and Huber G (1997) High power continuous wave up-conversion fiber laser at room temperature. *Optics Letters* 22(11): 809.

Table 4 Main room temperature up-conversion lasers operating from photon avalanche

Laser material	*Laser wavelength (nm)*	*Pump wavelength (nm)*	*Output power*
BaY_2F_8:Yb:Pr	607.5	822	55 mW
BaY_2F_8:Yb:Pr	638.7	841	26 mW
$LiY_{0.89}Yb_{0.1}Pr_{0.01}F_4$	720	830	1%
$LiY_{0.89}Yb_{0.1}Pr_{0.01}F_4$	639.5	830	
Fiber:Yb:Pr	635–637	780–880	300 mW
Fiber:Yb:Pr	605–622	780–880	44 mW
Fiber:Yb:Pr	517–540	780–820	20 mW
Fiber:Yb:Pr	491–493	780–880	4 mW
Fiber:Yb:Pr	635	850	1.02 W
Fiber:Yb:Pr	635	850	2.06 W
Fiber:Yb:Pr	520	850	0.3 W



Figure 12 Scheme of a self-frequency doubling laser. Note that in reality the three beams are superimposed.

Table 4 summarizes the performances of the main up-conversion lasers based on photon avalanche mechanisms.

Up-Conversion Lasers Based on Bi-Functional Crystals

The laser stimulated emission in a bi-functional crystal was first obtained in 1969 with Tm^{3+} in $LiNbO_3$ but the most used ion is, of course, Nd^{3+} working in the two channels:

$$^4F_{3/2} \rightarrow {}^4I_{11/2} \tag{29}$$

$$^4F_{3/2} \rightarrow {}^4I_{13/2} \tag{30}$$

and more recently Yb^{3+} working in the channel:

$$^2F_{5/2} \rightarrow {}^2F_{7/2} \tag{31}$$

Channels in eqns [29] and [31] operate around 1060 nm wavelength and the channel in eqn [30] near 1338 nm.

The Self-Frequency Doubling Laser

A typical laser scheme is shown in Figure 12.

Table 5 Main results of Nd^{3+} and Yb^{3+} green self-frequency doubling lasers near 530 nm (eqns [29] and [31])

Crystal	*Input power (mW)*	*Output power (mW)*	*Pumping*
$LiNbO_3$:MgO:Nd	215	1	Dye laser
$YAl_3(BO_3)_4$:Nd	870	10	Laser diode
$YAl_3(BO_3)_4$:Nd	280	3	Laser diode
$YAl_3(BO_3)_4$:Nd	400	69	Laser diode
$YAl_3(BO_3)_4$:Nd	1380	51	Laser diode
$YAl_3(BO_3)_4$:Nd	369	35	Laser diode
$LiNbO_3$:MgO:Nd	850	18	Dye laser
$LiNbO_3$:Sc_2O_3:Nd	65	0.14	Ti:sapphire laser
$LiNbO_3$:MgO:Nd	100	0.2	Laser diode
$YAl_3(BO_3)_4$:Nd	1600	225	Laser diode
$YAl_3(BO_3)_4$:Nd	2200	450	Ti:sapphire laser
$(Y,Lu)Al_3(BO_3)_4$:Nd	880	24	Laser diode
$LiNbO_3$:ZnO:Nd	430	0.65	Ti:sapphire laser
$Ba_2NaNb_5O_{15}$:Nd	270	46	Ti:sapphire laser
$CaY_4(BO_3)_3O$:Nd	900	62	Laser diode
$CaGd_4(BO_3)_3O$:Nd	1600	192	Ti:sapphire laser
$CaGd_4(BO_3)_3O$:Nd	1250	115	Laser diode
$CaGd_4(BO_3)_3O$:Nd	1560	225	Ti:sapphire laser
$YAl_3(BO_3)_4$:Yb	11 000	1100	Laser diode
$GdAl_3(BO_3)_4$:Nd	2.8 mJ/pulse	0.12 mJ/pulse	Pulsed dye laser

The laser beam cannot escape from the cavity and dichroic mirrors are used. The input mirror has high transmission at the pump wavelength and is highly reflective at laser- and second-harmonic wavelengths. The output mirror is highly reflective at laser wavelength and has high transmission for second harmonic. Channels in eqns [29] and [31] generate green light near 530 nm and the channel in eqn [30] generates red light near 669 nm.

The most exploited bi-functional crystal is $YAl_3(BO_3)_4:Nd^{3+}$, well-known as NYAB. It is a negative uniaxial trigonal crystal (extraordinary index lower than the ordinary one) and its laser emission is easily observed in ordinary polarization with a high cross-section: $2 \times 10^{-19}\,cm^2$ at 1063 nm. Type I phase matching occurs at a polar angle $\theta = 30.7°$ and 26.8° for channels in eqns [29] and [30] respectively. The effective nonlinear optical coefficient d_{eff} is close to 1.4 pm V^{-1} at azimuthal angle $\phi = 0°$.

The Yb^{3+} ion has some advantages over the Nd^{3+} ion due to its very simple energy level scheme: there is no excited state absorption at the laser wavelength, no up-conversion losses, no concentration quenching, and no absorption in the green. The small Stokes shift between pump and laser emission reduces the thermal loading of the material during laser operation. A self-doubling laser based on $YAl_3(BO_3)_4:Yb^{3+}$ of crystal has produced 1.1 W green power upon 11 W diode pumping.

The drawback of $YAl_3(BO_3)_4$ is that it is rather difficult to grow because it is not congruent. This difficulty was overcome by the discovery at Ecole Nationale Supérieure de Chimie de Paris of the rare-earth calcium oxoborate $CaGd_4(BO_3)_3O$ which can be grown to a large size by the Czokhralski method. It is a monoclinic biaxial crystal and doped with Nd^{3+}, it was firstly exploited (channel in eqn [29]) in the XY principal plane at $\theta = 90°$, $\phi = 46°$ with ($d_{eff} = 0.5$ pm V^{-1}). It was soon recognized that the optimum phase matching direction ($d_{eff} = 1.68$ pm × V^{-1}) occurred out of the principal planes, in the direction $\theta = 66.8°$, $\phi = 132.6°$, and high green power can be obtained: 225 mW under 1.56 W pump.



Figure 13 Scheme of a self-sum frequency mixing laser. Note that in reality the three beams are superimposed.

Table 5 summarizes the main self-frequency doubling results obtained with the channel in eqn [29].

The Self-Sum Frequency Mixing Laser

The example in Figure 13 gives the main features of such a laser. The input mirror has high transmission at the pump wavelength and both mirrors are highly reflective at laser wavelength. The output mirror has high transmission at sum frequency mixing wavelength.

The laser wave at angular frequency ω_1 in Table 1 corresponds to the channel in eqns [29] or [30] in the case of Nd^{3+}. The wave at angular frequency ω_2 in Table 1 has two different roles: first it excites the Nd^{3+} laser center and secondly its nonabsorbed part is up converted by the second-order nonlinear process. ω_2 (corresponding to the wavelength λ_2) is then chosen to match the main Nd^{3+} absorption lines:

$$\begin{aligned} &{}^4I_{9/2} \rightarrow {}^4G_{5/2} - {}^2G_{7/2}\ (\lambda_2 = 590\ \text{nm}) \\ &{}^4I_{9/2} \rightarrow {}^4F_{7/2} - {}^4S_{3/2}\ (\lambda_2 = 750\ \text{nm}) \\ &{}^4I_{9/2} \rightarrow {}^4F_{5/2} - {}^2H_{9/2}\ (\lambda = 800\ \text{nm}) \\ &{}^4I_{9/2} \rightarrow {}^4F_{3/2}\ (\lambda_2 = 880\ \text{nm}) \end{aligned} \qquad [32]$$

The most efficient self-frequency mixing lasers based on channels in eqns [29]–[31] are gathered in Table 6.

See also

Materials Characterization Techniques: $\chi^{(2)}$. **Nonlinear Optics, Applications:** Phase Matching. **Nonlinear Optics, Basics:** $\chi^{(2)}$–Harmonic Generation.

Table 6 Main results of Nd^{3+} self-sum frequency mixing lasers based on eqn [29]

Crystal	*Pump wavelength (nm)*	*Generated wavelength (nm)*	*Output power*
$YAl_3(BO_3)_4:Nd$	740–760	436–443	0.16 mJ/pulse
$GdAl_3(BO_3)_4:Nd$	740–760	436–443	0.403 mJ/pulse
$CaGd_4(BO_3)_3O:Nd$	811	465	1 mW
$YAl_3(BO_3)_4:Nd$	585–600	377–383	0.25 mJ/pulse
$GdAl_3(BO_3)_4:Nd$	587–597	378–382	0.105 mJ/pulse
$YAl_3(BO_3)_4:Nd$	488, 515	330, 380	0.2 mW

Further Reading

Brenier A (2000) The self-doubling and summing lasers: overview and modeling. *Journal of Luminescence* 91: 121–132.

Butcher PN and Cotter D (1990) *The Elements of Nonlinear Optics*. Cambridge, UK: Cambridge University Press.

Huber G (1999) Visible cw solid-state lasers. *Advances in Lasers and Applications*. Bristol and Philadelphia: Scottish Universities Summer School in Physics & Institute of Physics Publishing.

Joubert MF (1999) Photon avalanche up-conversion in rare earth laser materials. *Optical Materials* 11: 181–203.

Kaminskii AA (1996) *Crystalline Lasers: Physical Processes and Operating Schemes*. CRC Press, Inc.

Lenth W and Macfarlane RM (1992) Upconversion lasers. *Optics & Photonics News* 3: 8–15.

Powell RC (1998) *Physics of Solid-State Laser Materials*. New York: Springer-Verlag.

Risk WP, Gosnell T and Nurmikko AV (2003) *Compact Blue-Green Lasers*. Cambridge, UK: Cambridge University Press.

Weber MJ (2001) *Handbook of Lasers*. Boca Raton, FL: CRC Press.

Yariv A (1995) *Quantum Electronics,* Third Edition. John Wiley & Sons.

LASER-INDUCED DAMAGE OF OPTICAL MATERIALS

A J Glass and A H Guenther, The University of New Mexico, Albuquerque, NM, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Shortly after the invention of the laser, in the early 1960s, it became apparent that laser performance was limited by the ability of optical materials to withstand high energy and power densities. Broadly speaking, laser damage arises from two causes: (i) thermal effects, which are associated with high average power; and (ii) dielectric breakdown, which is associated with high values of the local electric field. Early researchers quickly recognized that most of the observed damage effects arose from extrinsic causes, such as impurities and inclusions in the bulk material, or particles or defects on exposed optical surfaces. At that time, optical materials had not been developed for high-power use, and lacked the quality needed for laser applications. In fact, in many situations, the laser provided the inspection light source used to assess the properties of the materials, such as absorption, defects, scattering centers, surface topography, and dynamic behavior. Thus, the field of laser damage studies was broadened to include many aspects of material preparation and characterization. At high-power densities, nonlinear effects become important, often limiting performance without creating any irreversible change in the material's properties. The most general definition of laser-induced damage includes all effects arising in optical materials and components that limit or degrade the performance of laser systems.

The pursuit of improved performance at high values of power and energy densities was motivated by several factors and applications. In general, improved tolerance to high flux and fluence leads to smaller, lighter, and more efficient systems. These are particularly important for military and energy applications. Since the 1970s, the laser fusion program alone has produced an extensive body of research on laser-induced damage in high-power nanosecond-scale systems, which has enabled orders of magnitude improvement in the damage resistance and extraction efficiency of glass lasers. More recently, with the development of fiber laser systems producing and transporting a kilowatt of average power in a fiber of less than 100 μm diameter, laser damage phenomena on an entirely different spatial scale have become important.

Since the early 1970s, the literature of laser damage research has been collected in a series of annual publications of the Boulder Damage Symposium, initiated by the authors of this article, which was first held in 1969. Recently the papers presented at the Damage Symposium in the years 1969 to 1998 were collected and published in CD form by the SPIE. A CD containing the proceedings of the next five years (1999–2003) will be released by SPIE this year. Also in the late 1960s, in the Soviet Union, Academician Aleksei Bonch-Bruevich launched a comprehensive research project on the nonresonant interaction of laser radiation with matter, opening up a new branch of photonics research, known in the Soviet Union as power optics. In 1969, he founded the All-Union Conference on Interaction of Optical Radiation with Matter (AURICOM), which was held every two to three years until 1990. After 1990, the conference was renamed Nonresonant Laser-Matter Interaction (NLMI), and chaired by Professor Mikhail Libenson. NLMI was held in St Petersburg in 1996, 2000, and

2003. The proceedings of the 1996 AURICOM and subsequent NLMI conferences have been published by the SPIE. We are saddened to note that Professor Libenson died in February 2004.

The Boulder Damage Symposium grew out of a one-day Symposium convened in Boulder in 1969 under the auspices of the ASTM Subcommittee on Lasers, to establish standards for laser materials. In their summary of the first Symposium, the conference organizers remarked:

> The entire question of the nature of the standards remains to be addressed. Should they take the form of energy density at which catastrophic damage is likely to occur, or should they be specified in terms of a mean number of shots at a given level of energy density before certain degradation of performance is measured? The latter would seem to express the kind of information that the buyer of laser materials would find most useful. Once a standard is agreed upon, a meaningful test configuration must be established. It is likely that this will be a well-controlled oscillator amplifier chain with the test specimen an active element of the system, but this is not certain. Another point to be determined is that of the accuracy to which its specifications should be written. This depends in part on the kind of quality control the producers of laser glass believe is feasible.

The questions raised in this first Symposium remain at the core of laser damage studies today. How do we define damage, in terms of the physical effect on the material or in terms of the degradation of performance of the system? How do we measure damage thresholds or values? How do we specify the properties and preparation of the sample, including the relevant experimental and material variables? How can we ensure that damage values are reproducible, unless we make the measurements in a very well controlled and characterized system? With what precision should damage levels be stated, in order to be useful? Extensive research was required in order to answer these questions, and to elucidate the fundamental nature of damage mechanisms. Many of the results of this research are documented in the 35 year record of the Boulder Damage Symposium and the corresponding Russian-based conferences.

From the beginning of this area of research, investigators devoted a significant effort to establishing the ‘first causes’ of damage phenomena. However, they quickly realized that in most cases, damage occurred at surfaces and material interfaces, or was mediated by impurities or inclusions in bulk materials. As material fabrication processes improved, and higher-quality materials became available, observed damage thresholds approached the intrinsic limits of the pure material. This was particularly true of silicate glass, metal reflectors, and in some cases, polymers. In fact, silicate glass has become one of the purest noncrystalline materials available in bulk quantities. However, for practical purposes, most laser systems are limited by damage at surfaces, coatings, or impurities. Impurities aggregate at grain boundaries in crystalline materials, and coalesce into inclusions in glasses, resulting in absorption, scattering, and field enhancement.

The coherent nature of laser light makes any scattering phenomena potentially damaging, because the scattered light interferes constructively with the laser beam, leading to the formation of intensity hot spots. Every interface in an optical system is potentially a source of constructive interference between the reflected and incident waves. Multilayer dielectric coatings are particularly vulnerable to damage, due to the presence of residual stress as well as field enhancement from Fresnel reflection. This has led to attempts to mitigate the problem by use of specific designs, such as avoiding AR coatings by using Brewster-angle surfaces, or use of nonquarter wave layers to move the peak field away from the vicinity of boundaries where impurities tend to collect. Other damage-sensitive design considerations can be found in the literature. Multiple reflections are the basis of photonic crystal optics, and applications of these devices to high-power density systems will undoubtedly be limited by field-enhanced damage phenomena.

In CW operation, of course, thermal effects dominate. They may be irreversible, creating permanent damage sites in the medium, or reversible, such as color centers that can be bleached out. As laser pulse durations vary from nanosecond to picosecond and femtosecond durations, the nature of the dominant damage mechanisms changes as well. As a rule of thumb, the scaling of damage thresholds as $\tau^{1/2}$, where τ is the pulse duration, was established empirically, and was found to be valid over a wide range of pulse durations. This scaling implies the presence of diffusion effects, either of heat or of electrons, in the vicinity of a damage center. As might be expected, this scaling does not apply for very short pulses (femtoseconds or less), where the extremely high field values can lead to instantaneous breakdown of the material.

Whether the damage is due to field enhancement or is impurity-mediated, it is difficult to establish a reproducible value for a damage threshold, unless the sample is macroscopic in extent, and the sampling laser beam is reproducibly of high spatial and temporal quality, preferably truly single-mode. Damage measurements on microscopic areas are unlikely to be representative of the entire sample. Damage will occur first at a point where the field is strongest or the material is weakest, and a sufficient area must be tested to ensure that it includes such sites. Also, unless the beam quality of the laser used for testing is well controlled and well characterized, it will not be possible to reproduce the test results. It is equally important to characterize the samples, including their method of preparation, cleaning, and test environment. For damage research, as opposed to simple threshold testing, postmortem examination is also required, to elucidate the mechanism of the observed damage effect. However, we now have several techniques, such as photothermal deflection, that can provide useful pre-catastrophic indicators of the onset of laser damage, and thus are appropriate for quality control.

Professor Roger Wood had published a series of reviews and textbooks on laser damage in optical materials, which provide an overview of the field, with appropriate emphasis on measurement techniques, characterization of the test setup and sample, and implications for system design. He has also edited a collection of seminal publications in the field, published by the SPIE in 1990.

It is gratifying to those working in this field to observe how much of the research carried out to elucidate and, if possible, avoid the deleterious effects of laser damage has been applied to the constructive purpose of laser-assisted material processing and manufacturing. The introduction of low-cost, reliable femtosecond lasers has stimulated activity in this field, since it enables the experimenter to control to exquisite precision the power and energy deposited on a material. With femtosecond pulses, one can ablate material from the surface of an object while minimizing any collateral damage to the interior material. Surface layers of dirt can be removed from priceless art works such as oil paintings, without concern for damage to the object itself. Objects with arbitrary shape can be built up from metal particles, using laser additive manufacturing techniques. Thin films and photonic crystal structures can be created using laser-assisted deposition. Laser irradiation provides a power tool for surface cleaning, conditioning, and annealing. Laser interaction with materials and laser-assisted manufacturing techniques comprise a vital area of research in the materials science community.

In both the US and Russia, study of the interaction of intense coherent light with optical materials began with a disarmingly simple objective; to understand the fundamental mechanisms of interaction. In the review and summary of the 1969 ASTM Symposium, the editors wrote:

> In view of the number of problems remaining to be resolved, it is suggested that another Symposium on laser damage be held in 1970. Hopefully, at that time a better understanding of the nature of damage in laser glass will have been obtained. Higher threshold values will have been reproducibly achieved, and some agreement can be arrived at regarding useful and realistic standards.

Thirty-five years later, damage levels in optical materials have been significantly improved, and realistic and useful standards have been developed under the auspices of the International Organization for Standardization (ISO), and are now accepted globally. However, as the operating regimes of lasers have moved to femtosecond temporal scale and micrometer dimensions, new phenomena have arisen that require further research. An entirely new technology of laser-enabled manufacturing and materials conditioning has developed, based on the same physics as laser damage. Combining the disciplines of materials science and applied optics, the interaction of intense light with materials remains a scientifically challenging and economically important field of research.

See also

Optical Coatings: Laser Damage in Thin Film Coatings.

Further Reading

Bonch-Bruevich AM, Konov VI and Libenson MN (eds) (1990) *Optical Radiation Interaction with Matter*. SPIE Proceedings, vol. 1440.

Glass AJ and Guenther AH (eds) (1969) *Damage in Laser Glass Symposium: Review and Summary*. ASTM Special Technical Publication 469.

ISO Online Catalogue, Section 31.260, http://www.iso.ch/iso/en/CatalogueListPage.CatalogueList

Laser-Induced Damage in Optical Materials, Collected Papers 1969–1998, (CD-ROM), SPIE, Bellingham, Washington (1999).

Laser-Induced Damage in Optical Materials, Collected Papers 1999–2003, (CD-ROM), SPIE, Bellingham, Washington (2004) (To be published).

Libenson MN (ed.) (1997) *Non-Resonant Laser-Matter Interaction (NLMI-9)*. SPIE Proceedings, vol. 3093.

Libenson MN (ed.) (2001) *Non-Resonant Laser-Matter Interaction (NLMI-10)*. SPIE Proceedings, vol. 4423.

Libenson MN (ed.) (2004) *Non-Resonant Laser-Matter Interaction (NLMI-11)*. SPIE Proceedings, vol. 5506, (To be published).

Wood RM (ed.) (1986) *Laser Damage in Optical Materials*. Bristol, UK: Adam Hilger.

Wood RM (ed.) (1990) *Selected Papers on Laser Damage in Optical Material*. SPIE Milestone Series, vol. MS24. SPIE Optical Engineering Press.

Wood RM (ed.) (2003) *Laser-Induced Damage in Optical Materials*. Bristol, UK: Institute of Physics.

Wood RM (ed.) (2003) *The Power- and Energy-Handling Capability of Optical Materials, Components, and Systems*. SPIE Press Tutorial Texts in Optical Engineering, vol. TT60.

LIGHT EMITTING DIODES

J Schanda, University of Veszprém, Veszprém, Hungary

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Short Historic Overview

During the second half of the nineteenth century, electric lighting became possible. In 1879, Edison demonstrated his incandescent lamp, and although some electric arc lamps competed with the incandescent lamp bulb for a few years, the first 50 years of electrical lighting was dominated by the incandescent lamp. Gas discharge lamps (both low- and high-pressure lamps) became more widely distributed only by the end of the third decade of the twentieth century, and widespread distribution of the fluorescent lamp, that still dominates our offices and many other lighting applications today, was generally accepted only after the Second World War.

The early incandescent lamps had an efficacy of a few lm/W, but by 1920 this could be increased by up to 10–15 lm/W. Gas discharge lamps started with approximately 30 lm/W, but by 1960 their efficacy increased to about 70 lm/W. Fluorescent lamps still provide only 70 to 100 lm/W; high-pressure lamp efficacy could be increased above this value. The different lamp types can be used, however, in different applications, depending on the size and the unit power of the lamp type. Nonincandescent light generation in solid-state materials dates back to the 1920s: a faint glow of a SiC crystal was observed when current passed through it at a point contact. In the 1930s, electroluminescence of ZnS powder layers was detected (Destriaux effect). By the mid-1960s, it became clear that by using the then available technology, good luminous efficiency could be expected only in III–V compounds (GaAs, GaP, and their ternary and quaternary compounds using Al, In, and N in the compounds). Pure GaAs has a bandgap in the infrared (IR), thus one can build good IR-emitters using this material, but no visible light emitter. However, GaAs proved to be an excellent coherent light-emitting material and enabled the construction of IR-emitting semiconductor lasers.

First visible light-emitting diodes were fabricated using a GaAsP alloy. Figure 1 shows how the efficacy of III–V compound LEDs can be increased by introducing new compositions, and later, new technologies and better light extraction techniques. In the figure we also show the efficacy values of average incandescent, high-pressure Hg- and fluorescent lamps. The first LEDs emitted in the red part of the spectrum, and only by 1975 was the green LED invented. By 1985, practically any color between red and green became possible, and the efficacy of these lamps reached a level where for monochromatic light applications, their efficacy could compete favorably with filtered incandescent light. LEDs emit in a relatively narrow wavelength band (20 nm–30 nm bandwidth), and if one has to filter from the continuous spectrum of an incandescent lamp such a narrowband, the loss becomes considerable. LEDs needed only a few volts to function and it became general practice to build LEDs with approximately a 20 mA current load. These LEDs became very popular for interior signaling (on instruments, household appliances, and in similar applications). The goal was, however, to be able to produce white light, but the blue-emitting LED was still missing. Only after 1990 could the problem of producing p–n junctions from GaN, that had a bandgap large enough to emit blue light, be solved. Different ternary and quaternary compounds, as shown in Figure 1, enabled efficacies comparable to incandescent lamp efficacy, and the race for producing white light began.



Figure 1 Increase of luminous efficacy of LEDs during the past 40 years. Courtesy of Lumileds Lighting.

Physical Fundamentals

Figure 2 shows a forward-biased p–n junction. As injected free electrons and holes are driven towards the junction, they can radiatively recombine, emitting a photon. The probability of photon emission versus nonradiative recombination will depend on the band



Figure 2 Forward biased p–n junction, light generation via recombination of free charge carriers.



Figure 3 Band to band recombination in direct and indirect band semiconductor.

structure of the semiconductor. Figure 3 shows the two possibilities of a direct and an indirect bandgap semiconductor. GaAs is, for example, a direct bandgap material. In this material free electrons at the bottom of the conduction band can recombine with free holes at the top of the valence band, as the momentum of the two ‘particles’ is the same and a photon emission takes care of the principle of energy conservation. GaP is an indirect bandgap material where the momentum of the free electrons at the bottom of the conduction band differs from the momentum of the free holes at the top of the valence band, and thus the recombination needs not only the fulfilment of the conservation of energy, but also of momentum. Thus, besides photon emission, phonon emission or absorption has to take place. Thus, the probability of the transition will decrease and competing nonradiative processes will become important. Using N doping produces very shallow donor states and from these an efficient recombination can take place. This enabled the production of early relatively efficient green-emitting LEDs.



Figure 4 Relative spectral power distribution of some LED structures.



Figure 5 Spectral power distribution of a red LED at different temperatures.

GaN is ideal for producing LEDs, as it is a direct gap material and has a high bandgap. The technological difficulties are, however, enormous. Modern high-efficiency LEDs use (Al)InGaN-based materials for shorter wavelength LEDs, and AlInGaP-based materials for longer wavelength LEDs. Figure 4 shows a number of LED spectra of different wavelengths including a white LED. Its spectrum consists of a blue maximum produced by the LED emission and a yellow broader band produced by the luminescent material excited by the blue emission of the LED.

LEDs are semiconductor materials, and as with every semiconductor the LED characteristics are also temperature dependent. Not only the efficiency of the current carrier–photon emission process depends on the temperature, but the bandgap of the base material also depends on the temperature, and thus both the efficacy and the relative spectral distribution of the emission change with temperature. Figure 5 shows the spectral power distribution of a red LED at different temperatures.

Modern High Brightness LEDs

Besides the high quantum efficiency of the semiconductor junction, two further requirements to achieve high luminous efficacy are the efficient light extraction from the junction and keeping the temperature of the semiconductor chip low.

All semiconductors for producing LEDs have a high refractive index, thus light reflection at the semiconductor–air interface is relatively high, and for obliquely impinging rays the critical angle for total internal reflection is soon reached. Different manufacturers shaped the semiconductor chip in different forms to secure maximum light extraction. Figure 6 shows the cross-section of an LED, where the side planes have been cut obliquely to secure good light extraction.

The other problem that has to be solved is good heat conduction from the chip to a heat sink. At the time of writing, highest single chip power loads were in the order of 5 W. The structure of such a construction is seen in Figure 7. The GaN-based LED is grown on a visible light transparent sapphire (Al_2O_3) substrate. In modern LEDs the structure itself is quite complicated; in the vicinity of the p–n junction some nanometer thick layers are deposited forming quantum wells (QW(s)). The p-type original upper layer is metalized and soldered to the submount serving as heat-sink. The n-type layer gets a second soldered heat conducting current leading to the submount. As seen, the original structure grown on the sapphire substrate is inverted, and now the light can be extracted through the sapphire layer. The metalization on the p-type layer serves at the same time as a mirror. High brightness LEDs are now available in package sizes of over 100 lumen.



Figure 6 Truncated pyramid structure to secure good light extraction from the LED chip. Courtesy of Lumileds Lighting.



Figure 7 Inverted, flip-chip structure for good heat-sinking of the LED. Courtesy of Lumileds Lighting.

White LED Structures

The advantages of LEDs (low drive voltage, extreme long lifetime of 50000 to 100000 hours, robust shock-resistant construction) can open up a new era of lighting engineering, if white light emission can be obtained. The LED structure in itself is a narrowband emitter, thus – with inorganic LEDs – it is not possible to produce white light within one chip. Organic LEDs (OLEDs) promise the production of broadband and white light emission, but these are still in an experimental phase. At present they are used in smaller, portable displays, such as those used on portable phones, cam-coders, etc. To get further information, go to the Further Reading section at the end of this article.

At present three techniques to generate white light get thorough investigation: first, mixing the light of a red, a green, and a blue LED. This should theoretically give the highest efficiency; the problem is, however, that the three LEDs have different temperature dependence and aging characteristics, and thus it is difficult to keep the chromaticity of the mixed color constant (the three colored LEDs can be used in LED-based displays to produce full-color reproduction). At present the following technique is widely used. A blue LED excites a yellow phosphor, so that the mixture of the blue and yellow lights produce a white appearance. The color rendering of such white LEDs is not too good, and therefore alternative techniques using a green and a red phosphor are receiving increasing attention. The third method uses the same principle, but with an LED emitting in the near ultraviolet. This has the advantage that it provides a greater selection of phosphors, but as the energy difference between the UV photon and the photon emitted by the phosphor is larger than in the case of a blue-emitting LED, the theoretical efficiency is lower.

The phosphor layer is deposited on the chip surface, and for blue-emitting diodes special care has to be taken that the LED light and the phosphor light are properly mixed so that the emitted light shows no directional color shift. Early white LEDs suffered much from the fact that the spectral distribution of the light changed considerably with viewing angle.

The problems with phosphor-coated white LEDs are how a suitable correlated color temperature and color rendering can be obtained. Early white LEDs had very bluish chromaticity, their correlated color temperature was very high, above 7000 K. Preferred white light has different chromaticity in different cultural regions, in the Far East 6000 K to 6500 K is preferred, in Europe and North America for general lighting a correlated color temperature of 4000 K is well accepted and for social and home lighting even lower correlated color temperatures, 2800 K to 3200 K are preferred. Recently, white LEDs based on blue chips and special phosphor blends have been produced that meet these requirements.

A further problem is the color rendering of the white LEDs. The Commission Internationale d'Eclairage (CIE), the International Commission on Illumination, provides standards, recommendations, and technical reports in the field of light and lighting, including vision, color, and image processing. Photometry and colorimetry are based on the standards and recommendations of the CIE.

The CIE established a method of calculating a color-rendering index in 1965 and updated it in 1974. Despite several attempts, the lighting community has been unable to agree on a revision of this outdated document since the 1970s. Thus, color-rendering indices are still calculated based on this method, although several investigations have shown that the calculated indices do not correspond with the visual observation. CIE, therefore, established a technical committee (TC) dealing only with the question of LED color rendering. It is hoped that this TC will be able to come up with some recommendations soon and, therefore, that LED manufacturers can tailor the emission spectra of their LEDs for optimal efficacy and color rendering. Until this happens, however, the published color rendering indices, especially the General Color Rendering Index (R_a) have to be handled carefully. The color appearance of objects under LED illumination might deviate considerably from what one expects based on the R_a index.

Application of LEDs

LEDs are the solution for practically every signaling application. Figure 8 shows an LED traffic light. Here it is also shown that, despite the fact that LEDs have extremely long life expectancy, the failure of the electronic circuitry can lead to unpleasant dark spots and rows in the display.



Figure 8 Green LED traffic light. Due to an electronic failure some LEDs stay dark.

LEDs are increasingly used in large active posters and displays. In such applications the highly saturated color of LED light is an advantage: LED displays can be very bright and emit saturated colors.

LEDs have an advantage in every situation where colored light has to be produced. Thus, they become the preferred automotive stoplights, dashboard lights, and are widely used in other signaling applications on the roads, at airfields, and in other traffic situations; much decorative lighting is now using LEDs.

Experiments are underway to find the best applications for white LEDs. Their drawback at the moment is still that their single unit power is below ten watts, as we often need ten to a hundred times larger units. For such applications, some LED clusters have been built, but these are still not competitive with other light sources. At places where the ruggedness of the LEDs is of an advantage, white LED lights are used – for example, in aircraft reading lights. One area where we will probably soon find higher-intensity white LEDs is car headlamps. Both the efficacy and the luminous flux output of the single LED units is increasing continuously. Applications, unbelievable only a few years ago, can now be realized efficiently with LEDs. Thus it is very difficult to foresee in which applications – beyond signaling – LEDs will first supersede other light sources, but it is certain that within the next decade we will see many new applications of LED sources.

List of Units and Nomenclature

Chromatic adaptation	Adaptation by stimuli in which the dominant effect is that of different relative spectral distributions.
Chromaticity	Partial description of the color stimulus, describing only chromatic aspects and not the ‘intensity’ (the luminance) of the stimulus. In light sources, chromaticity is an important descriptor, as the level of illumination can be changed by changing the distance between the source and the illuminated object. The luminance of the object will depend on the illumination and the reflection (transmission) characteristics of the object.
Color	In color science one distinguishes between color (perception), characteristic of visual perception that can be described by attributes of hue, brightness (or lightness) and colorfulness (or saturation or chroma), and color stimulus, a specification of the optical stimulus in terms of operationally defined values, such as three tristimulus values, or luminance, and chromaticity (or dominant wavelength and saturation).
Color rendering	Measure of the degree to which the psychophysical color of an object illuminated by the test illuminant conforms to that of the same object illuminated by the reference illuminant, suitable allowance having been made for the state of chromatic adaptation.
Correlated color temperature	The temperature of the Planckian radiator whose perceived color most closely resembles that of a given stimulus at the same brightness and under specified viewing conditions.
Efficacy (luminous efficacy of a source)	Quotient of the luminous flux emitted by the power consumed by the source.
Luminous efficiency	Ratio of radiant flux weighted according to $V(\lambda)$, the spectral luminous efficiency of the human eye, to the corresponding radiant flux.
Spectral luminous efficiency (of the human observer)	Ratio of the radiant flux at wavelength λ_m to that at wavelength λ, such that both radiations produce equally intense luminous sensations under specified photometric conditions and λ_m is chosen so that the maximum value of this ratio is equal to 1.

See also

Incoherent Sources: Lamps. **Lasers:** Semiconductor Lasers.

Further Reading

Fukuda M (1991) *Reliability and Degradation of Semiconductor Lasers and LEDs*. Boston, MA: Artech House.

Rudden MN and Wilson J (1993) *Elements of Solid State Physics*. Chichester, UK: Wiley.

Sze SM (1985) *Semiconductor Devices: Physics and Technology*. New York: Wiley.

Wenckebach WT (1999) *Essentials of Semiconductor Physics*. Chichester, UK: Wiley.

Žukauskas A, Shur MS and Gaska R (2002) *Introduction to Solid-State Lighting*. New York: Wiley.

M

MAGNETO-OPTICS

Contents

Faraday Rotation, CARS, ODMR, ODSR, Optical Pumping
Interband Magnetoabsorption, Cyclotron Resonance, Spin Flip Raman Scattering

Faraday Rotation, CARS, ODMR, ODSR, Optical Pumping

H Pascher, Universität Bayreuth, Bayreuth, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

A complete understanding of the band structure of a semiconductor close to the Fermi energy requires information on the fundamental energy gap, the effective masses and the effective g-factors of the valence and conduction band. Magneto-optical methods in principle allow one to determine all these quantities; they are particularly well suited to measure the spin splittings of the energy bands.

Faraday rotation is the rotation of the plane of polarization of linearly polarized light propagating through a sample parallel to an external magnetic field. The magneto-optical Kerr effect is the analog for reflection. Though in general it yields much smaller angles of rotation than the Faraday effect, it has to be applied in spectral ranges where the investigated sample is not transparent.

If a semiconductor is excited by circularly polarized light with photon energies not too high above the energy gap a spin polarization in the conduction band can be obtained (optical pumping). A small transverse magnetic field reduces the degree of this spin polarization (the Hanle effect). Owing to the spin polarization of the photo-excited conduction electrons the photoluminescence radiation is partly circularly polarized. Thus mounting the sample in a microwave resonator and applying a longitudinal magnetic field, electron spin resonance transitions can be detected optically by monitoring the degree of polarization of the photoluminescence (ODCESR: optically detected conduction electron spin resonance). Via a 'nuclear Hanle effect' mediated by the hyperfine interaction, nuclear magnetic resonance transitions can also be detected optically (ODNMR). ODCESR and ODNMR are summarized under ODMR (optically detected magnetic resonance).

In modern optics nonlinear optical effects have gained particular importance. Since electron spin resonances in semiconductors are Raman-active transitions, coherent Raman methods such as CARS (coherent anti-Stokes Raman scattering) or CSRS (coherent Stokes Raman scattering) are of great importance for the determination of spin splittings of energy bands and the investigation of magnetic structures in semiconductors.

In the present contribution the physical basis for these methods will be discussed and typical examples for their application will be presented.

For Faraday rotation and CARS the systems from which these examples will be taken are magnetic or dilute magnetic semiconductors. In these materials paramagnetic ions like Mn^{++} or Eu^{++} are incorporated. There are two types of exchange interactions: (i) between the magnetic ions which in most cases causes an antiferromagnetic coupling; and (ii) between the ions and free carriers which causes a strong modification of the spin splittings of the energy bands with respect to nonmagnetic materials. Thus the Faraday effect or CARS are particularly well-suited methods for the investigation of such systems.

As examples of optical pumping and ODMR, results obtained with III–V semiconductors will be presented, which show the most important applications of these experimental methods.

Faraday Rotation and Magneto-optical Kerr Effect

Basic Principles

As already pointed out in the Introduction, the Faraday effect is the rotation of the plane of polarization of linearly polarized light traversing a sample parallel to a magnetic field. The angle of rotation Θ_{Far} is proportional to the length l of the sample and to the strength B of the magnetic field:

$$\Theta_{\mathrm{Far}} = VlB \qquad [1]$$

where V is called Verdet's constant.

For a phenomenological understanding of the effect one can consider plane polarized light as a superposition of right- and left-hand circularly polarized components. If the indices of refraction are different for both components, then at the end of the sample, when the two components are recombined, a phase shift occurs which manifests itself as a rotation of the polarization plane. The angle resulting from this consideration is

$$\Theta_{\mathrm{Far}} = \frac{l\omega}{2c}(n_- - n_+) \qquad [2]$$

where ω is the frequency, c the velocity of light, and n_- and n_+ are the refractive indices for left- and right-hand polarized light, respectively. If one neglects ellipticity of the light behind the sample only the real parts of the complex refractive indices $\tilde{n}_\pm$ are important,

$$\tilde{n}_\pm = n_\pm - \mathrm{i}\kappa_\pm \qquad [3]$$

The imaginary parts, however, are needed to understand the magneto-optical Kerr effect which occurs in the light reflected from the sample surface. According to Fresnel's formula for vertical incidence the field amplitude of the reflected beam is:

$$\tilde{E}^{\mathrm{r}}_\pm = \frac{1-\tilde{n}_\pm}{1+\tilde{n}_\pm}\tilde{E}^{\mathrm{i}}_\pm = \tilde{r}_\pm \tilde{E}^{\mathrm{i}}_\pm \qquad [4]$$

where the superscript 'r' refers to the reflected beam and 'i' to the incident beam. The complex reflection coefficient can be split into an amplitude and a phase factor:

$$\tilde{r}_\pm = r_\pm \exp(\mathrm{i}\psi_\pm) \qquad [5]$$

By comparing eqns [4] and [5] the phase shifts during reflection can be expressed in terms of the refractive index:

$$\psi_\pm = \arctan\frac{2\kappa_\pm}{1-n_\pm^2-\kappa_\pm^2} \qquad [6]$$

Finally the Kerr angle of rotation is obtained from the phase shifts in an analogous way to the Faraday rotation:

$$\Theta_{\mathrm{Kerr}} = \tfrac{1}{2}(\psi_- - \psi_+) \qquad [7]$$

It is seen that both effects can be understood in terms of the refractive index. In a simple oscillator model the refractive index has the form given in eqn [8]:

$$\tilde{n}_\pm^2 = \tilde{\varepsilon}_\pm(\omega, B) = \varepsilon_\infty + \sum_{i,j}\frac{F^\pm_{i,j}}{\hbar\omega^\pm_{i,j} - \hbar\omega - \frac{1}{2}\mathrm{i}\Gamma^\pm_{i,j}} \qquad [8]$$

with $\hbar\omega^\pm_{i,j}$ representing the transition energies between the energy levels i and j in σ^+ and σ^- polarization, respectively, and $F^\pm_{i,j}$ and $\Gamma^\pm_{i,j}$ are the respective oscillator strength and linewidth parameter.

From eqn [8] it is seen that when tuning the frequency, ω, resonant enhancements of the rotation angles are expected whenever the frequency corresponds to an allowed electronic transition, e.g., an exciton in a wide-gap semiconductor. This is the reason why the Faraday and magneto-optical Kerr effect can yield information on interband transition energies. In the case of such a resonance, the refractive index will be dominated by the particular term in the sum, corresponding to that transition. By a Taylor expansion one can then show that the difference of the refractive indices for σ^+ and σ^- polarization and thus the angles of rotation (see eqns [2] and [7]) are proportional to the difference of the transition energies for right- and left-hand circularly polarized light, and this difference depends on the spin splittings of the valence and conduction band. So we understand why the most important information obtained from Faraday or magneto-optical Kerr effect studies is on the spin splittings of the energy bands.

A quantum mechanical description of the relation between the material properties and the magneto-optical effects beyond the simple oscillator model given here is published by Boswarva *et al.* and the reader is referred to this paper for further studies. A matrix formalism to describe the effects for a multilayer system has been developed by Nies and Kessler.

Examples of Experimental Results

The straightforward method to measure Faraday rotation is to put the sample between polarizers and sweep the magnetic field. Then the transmitted intensity is proportional to a $\cos^2$ function. Subsequent maxima demonstrate a rotation by 180°. There have been numerous successful investigations done in this way, but the possibilities of detecting small angles of rotation are very limited in this method. Therefore differential methods have been developed either using a polarizing beam splitter, or a photo-elastic modulator which periodically switches the state of polarization. Rotation angles of the order of 10^{-4} rad can be detected in this way.

Figure 1 shows the Faraday rotation of an epitaxial film of $Pb_{0.933}Eu_{0.067}Te$ (thickness 11 μm) for two temperatures. The plot demonstrates behavior typical for a diluted magnetic semiconductor in its paramagnetic phase. The spin splittings of the valence and conduction band and accordingly the Faraday rotation are proportional to the magnetization of the sample which behaves like a Brillouin function. (The lines without noise are fitted Brillouin functions.)

Examples of the application of the magneto-optical Kerr effect to the investigation of semiconductors, particularly multilayer systems, are published, e.g., by Pohlt *et al.* and Krenn *et al.*



Figure 1 Faraday rotation as a function of magnetic field of a PbEuSe epitaxial film for two temperatures. Lines with noise: experimental recordings; lines without noise: fitted Brillouin functions.

Coherent Raman Scattering

Basic Principles

A more direct method for the determination of spin splittings of energy bands is provided by Raman scattering. There is a huge number of investigations of spin transitions in semiconductors using spontaneous Raman scattering (for a review of spontaneous Raman scattering in dilute magnetic semiconductors see the article by Ramdas and Rodriguez). However, there are several advantages in the spectroscopic application of the nonlinear Raman techniques compared to spontaneous Raman scattering:

(i) The scattered radiation is emitted as a collimated beam which is more easily detectable than the light spontaneously scattered into the entire solid angle. This advantage is particularly important for the investigation of narrow-gap semiconductors which have to be investigated by infrared light, a spectral range where the detectors are less sensitive than in the visible.
(ii) Fluorescence can be strongly suppressed by spatial filtering.
(iii) The spectral resolution is determined by lasers instead of a classical spectrometer.
(iv) Raman scattering cross-sections can be calculated from the intensity of a collimated beam without taking care of the aperture of the detecting system.

The coherent Raman techniques are special cases of optical four-wave mixing where two laser beams with frequencies ω_L and ω_S ($\omega_L > \omega_S$) are superimposed in the sample. Due to nonlinear interactions radiation with new frequencies is generated, among them:

$$\omega_{CARS} = 2\omega_L - \omega_S \qquad [9]$$

If one identifies ω_L with the frequency of the pump laser and ω_S with that of the scattered Stokes radiation of a spontaneous Raman experiment, then ω_{CARS} is the frequency of the anti-Stokes radiation. For the intensity of the radiation generated at ω_{CARS} one finds:

$$I_{CARS} = \frac{9}{16 c_0^4 \varepsilon_0^2} \frac{\omega_{CARS}^2}{n_{CARS} n_S n_L^2} \left|\chi^{(3)}\right|^2 l^2 I_S I_L^2 \times \left[\frac{\sin(\overrightarrow{\Delta k}\,\vec{l}/2)}{\overrightarrow{\Delta k}\,\vec{l}/2} \right]^2 \qquad [10]$$

where c_0 is the velocity of light, l is the length of the sample, I denotes the intensity, and n the refractive index at the respective frequency. $\chi^{(3)}_{kjkj}$ is the third-order nonlinear susceptibility of the scattering medium and

$$\overrightarrow{\Delta k} = 2\vec{k}_{\mathrm{L}} - \vec{k}_{\mathrm{S}} - \vec{k}_{\mathrm{CARS}} \qquad [11]$$

is the phase mismatch. $\overrightarrow{\Delta k} = 0$ can be achieved by noncollinear alignment of the laser beams. However, for very thin epitaxial layers with $l \ll \pi/\Delta k$ the phase factor in eqn [10] can be approximated by 1.

The information on the investigated material is contained in the nonlinear susceptibility. It can be calculated by time-dependent perturbation theory taking into account a ground state $|a>$ and intermediate states $|b>$, $|c>$ and $|d>$. It turns out that $\chi^{(3)}$ is proportional to a sum over all states of the system as intermediate states; in the sum 24 terms like the one given in eqn [12] have to be added:

$$\frac{\mu_{ijkl}}{(\omega_{ba} - \omega_{\mathrm{L}} - \mathrm{i}\Gamma_{ba})(\omega_{ca} - \omega_{\mathrm{L}} + \omega_{\mathrm{S}} - \mathrm{i}\Gamma_{ca})(\omega_{da} - \omega_{\mathrm{CARS}} - \mathrm{i}\Gamma_{da})} \qquad [12]$$

μ_{ijkl} is a product of four dipole matrix elements between states $|a>:|b>$; $|b>:|c>$; $|c>:|d>$ and $|d>:|a>$ with field polarizations as given by the indices. $\omega_{\alpha\beta} = (E_\alpha - E_\beta)/\hbar$ and $\Gamma_{\alpha\beta}$ is the linewidth of the respective transition. Resonances of the susceptibility are found by inspection of the denominators. $\chi^{(3)}$ exhibits Raman-like resonances whenever $\hbar(\omega_{\mathrm{L}} - \omega_{\mathrm{S}})$ is equal to the excitation energy of a Raman allowed transition (see the second factor in the denominator of eqn [12]). If in this case the laser beams are polarized according to the Raman selection rules then μ_{ijkl} is not zero. For spin transitions in a semiconductor in a magnetic field (free electron spin flip as well as transitions within the magnetic ions) this is the case if in the Voigt configuration ($\vec{k}_{\mathrm{L,S}} \perp \vec{B}$) the beams with frequencies ω_{L} and ω_{S} are polarized perpendicular to one another. In the case of a spin transition $\omega_{ca} = g^*\mu_{\mathrm{B}}B$ (g^* being the effective Landé-factor and μ_{B} the Bohr magneton). Thus holding the frequencies ω_{L} and ω_{S} fixed and tuning the magnetic field a resonance in I_{CARS} will be observed from the position of which the effective g-factor can be obtained. Using tunable dye lasers, of course, the laser frequencies can be tuned as well.

Close to the resonance the real part of the susceptibility becomes small and the imaginary part is not negligible. Furthermore, one-photon resonances may occur if the laser frequency ω_{L} corresponds to the energy of a real electronic transition, e.g., an allowed interband transition. If one-photon and Raman-like resonances occur simultaneously one talks about resonance CARS.

As discussed in the literature $\chi^{(3)}$ can be split into a resonant part χ_{r}, summing up all the resonant terms, and a nonresonant part χ_{nr}. In a semiconductor there are contributions to χ_{nr} due to free carriers and a background due to bound valence electrons. The background contribution in general is real. As can be seen from eqn [10],

$$I_{\mathrm{CARS}} \propto \left|\chi^{(3)}_{\mathrm{CARS}}\right|^2 = |\chi_{\mathrm{nr}}|^2 + |\chi'|^2 + |\chi''|^2 + 2\cdot\chi_{\mathrm{nr}}\chi' \qquad [13]$$

χ' and χ'' being the real and imaginary parts of the resonant contribution. Depending on the relative strength of resonant and nonresonant contributions to $\chi^{(3)}$ the last term in eqn [13] may cause complicated lineshapes which make it difficult to find the correct transition energy in spectroscopic applications of CARS. If more than one resonance is not completely resolved the lineshape is even more complicated and a careful analysis has to be performed to get the correct resonance positions and linewidths of the transitions.

Examples of Experimental Results

Figure 2 shows a scheme of a CARS setup suitable to measure spin transitions in a semiconductor. The scheme is drawn for backscattering geometry; forward detection is accomplished by directing the incoming beams onto the sample from the opposite side to that plotted.

Two dye lasers (frequencies ω_{L} and ω_{S}) are pumped by a frequency-doubled Nd:YAG laser. A Glan–Thomson prism combines the two beams. The monochromator is set to $2\omega_{\mathrm{L}} - \omega_{\mathrm{S}}$. The iris and the polarizer PZ3 reduce stray light. The experiment is performed either at fixed magnetic field and tuning one of the dye lasers (with the monochromator swept accordingly) or by keeping the laser frequencies fixed and sweeping the magnetic field. The latter method is also applicable in the mid-infrared using step-tunable CO or CO_2 lasers.

As an example, in Figure 3 a spectrum obtained from a CdMnTe alloy crystal is reproduced. There are two peaks observed due to the paramagnetic resonance of the Mn 3d electrons and due to the spin resonance of photo-excited free electrons in the conduction band. The inset shows the paramagnetic resonance on an extended scale. The linewidth of 0.5 cm^{-1} is not limited by the experimental resolution, which in the present case is about a factor of 10 better.


Nd:YAG laser
SHG
CCD controller
Computer
CCD
P
BS
PZ 3
BS
Iris
L 4
Double monochromator
dye laser
dye laser
$2\omega_L - \omega_S$
PZ 2
PZ 1
ω_S
ω_L
BS
BS
GTP
L 3
Sample in Voigt configuration
Superconducting magnet

Figure 2 Scheme of the experimental arrangement for CARS. Bold full lines: light beams; dashed and dotted lines: data connections; BS: beam splitter; PZ1,2: Pockels cells for rotation of linear polarization; PZ3: polarizer; GTP: Glan–Thomson prism for superposition of beams polarized orthogonally to each other; L: lenses.



Figure 3 Coherent Raman intensity of a CdMnTe bulk crystal as a function of frequency difference $\omega_L - \omega_S$. Inset: Region of paramagnetic resonance in an extended scale. Adapted from Rupprecht R, Müller B, Pascher H, *et al.* (1998) Coherent Raman scattering from magnetic excitations in diluted magnetic semiconductors: Bulk crystals of CdMnTe. *Physical Review B* 58: 16123. Copyright (1998) by the American Physical Society.

Optical Pumping

The basic principles of optical pumping have been developed by Kastler. A material (gas or solid) is excited by absorption of circularly polarized light. Lampel was the first to demonstrate the possibility of optical spin orientation of free electrons in a semiconductor. The method has the most important applications in zincblende materials. Thus it is explained here with the example of GaAs.

Principles of Optical Spin Orientation

Most of the III–V and II–VI semiconductors have direct gaps at the center of the Brillouin zone. The conduction band (cb) is doubly degenerate with spin. The valence band consists of the heavy hole band (hh; $m_j = \pm 3/2$), the light hole band (lh; $m_j = \pm 1/2$) and the split-off band (so; $m_j = \pm 1/2$), each doubly degenerate. In bulk material hh and lh are degenerate at $k = 0$. The transition probabilities for interband transitions between hh and cb are three times larger than for transitions between lh and cb. Due to the selection rules, e.g., for the absorption of σ^+ circularly polarized light, transitions $-3/2 \rightarrow -1/2$ and $-1/2 \rightarrow +1/2$ are allowed, the first having three times higher probability. The electronic spin polarization P is defined as:

$$P = \frac{n_+ - n_-}{n_+ + n_-} \qquad [14]$$

where n_+ and n_- are the densities of electrons with the two spin orientations with respect to the direction of propagation of light. These considerations yield $P_\mathrm{i} = -0.5$ as the initial spin polarization under excitation with σ^+ circularly polarized light with a photon energy between the fundamental gap and the energy difference from the spin–orbit split valence band to the conduction band. Due to relaxation processes the actual electronic steady state polarization P is smaller than P_i:

$$P = P_\mathrm{i} \frac{T_1}{T_1 + \tau} \qquad [15]$$

with T_1 being the spin relaxation time, which in zero magnetic field is equal to the transverse relaxation time T_2, and τ is is the lifetime of conduction electrons.

The spin polarization of the electrons can be detected by analyzing the degree of circular polarization of the luminescence light which is defined as:

$$\Pi = \frac{I_+ - I_-}{I_+ + I_-} \qquad [16]$$

where I_+ and I_- are the intensities of σ^+ and σ^- polarized light, respectively. Since for emission due to free-electron/free-hole or free-exciton recombination the same transition probabilities as for absorption are obtained, one finds:

$$\Pi = 0.5\,P = 0.25 \frac{T_1}{T_1 + \tau} \qquad [17]$$

In the case of quantum wells, the lh-hh degeneracy is lifted due to different confinement energies. Then the maximum polarization of cb → hh as well as for cb → lh luminescence light is 0.5.

Of course these considerations are only true for intrinsic or p-type materials where the number of photo-excited electrons is high compared to the equilibrium number of electrons.

Hyperfine Interaction of Spin-Polarized Electrons and Atomic Nuclei

In GaAs three isotopes exist with spin 3/2, namely ^{69}Ga, ^{71}Ga and ^{75}As. Owing to the small energy separation of the nuclear spin levels in moderate magnetic fields, in thermal equilibrium no significant nuclear spin polarization exists even at a temperature of 2 K. However, the hyperfine interaction between electrons and nuclei allows so-called flip-flop processes, that is a simultaneous reversal of electronic and nuclear spins. This causes a considerable dynamic spin polarization of the nuclei if the electronic spin system is polarized due to optical pumping. Under most experimental conditions and when nuclear spin relaxation mechanisms other than via the hyperfine interaction are negligible, the mean nuclear spin is approximately:

$$\langle I \rangle = \frac{I(I+1)}{S(S+1)} \frac{P}{2} \qquad [18]$$

where I and S are the operators for nuclear and electron spin. These dynamically polarized nuclei act on the electrons and shift their spin resonance magnetic field by an effective nuclear field (the Overhauser shift). This shift is proportional to $\langle I \rangle$ and to the probability of finding the electrons at the nuclear sites, and is inversely proportional to g^*. In GaAs due to the small value of g^* this field can reach several tesla.

Effect of a Constant Transverse Magnetic Field – The Hanle Effect

In a transverse (with respect to the direction of propagation of light) magnetic field the spin-oriented electrons precess around the field with an angular frequency $\Omega = g^{*}\mu_{\mathrm{B}}B/\hbar$. If the spin lifetime T_{S} $(1/T_{\mathrm{S}} = 1/T_2 + 1/\tau)$ is long enough, this precession diminishes the average spin polarization and consequently the degree of circular polarization of the photoluminescence according to:

$$\Pi(B) = \Pi(0)\frac{1}{1 + \Omega^2 T_{\mathrm{S}}^2} \qquad [19]$$

This is a Lorentzian with a width at half height of $\Delta B = \hbar/(g^{*}\mu_{\mathrm{B}}T_{\mathrm{S}})$.

It is seen that by measuring $\Pi(B)$ the spin lifetime can be determined if g^{*} is known. Together with eqn [17] the spin and interband lifetime can be determined in a steady-state experiment. If, on the other hand, T_{S} is known from a time-resolved experiment, g^{*} can be found from a Hanle effect measurement.

Optically Detected Conduction Electron Spin Resonance (ODCESR)

Optical spin orientation of conduction electrons is the presupposition for ODCESR. Suppose now, a longitudinal magnetic field $\mathbf{B}_0$ is applied on the sample ($\mathbf{B}_0$ parallel to $\mathbf{k}$, the direction of propagation of light, which is parallel to the direction of the optically oriented spins). If the field is not too high the considerations of optical spin orientation remain unchanged. In higher fields the spin polarization may be modified due to the energy splitting of the spin levels. In this case the spin polarization is enhanced or diminished, depending on the direction of the field parallel or antiparallel to $\mathbf{k}$. If now an additional transverse microwave field B_1 of frequency ω_0, which fulfills the resonance condition $\hbar\omega_0 = g^{*}\mu_{\mathrm{B}}B_0$, is applied, transitions between the two spin levels will occur which resonantly decrease the spin polarization. This decrease manifests itself in a decrease of the degree of circular polarization of the photoluminescence.

The method has several advantages compared to conventional ESR. Microwave photons with frequency of about 10^{10} Hz change the state of polarization of optical photons with frequency of about 10^{14} Hz. Thus the sensitivity is that of the optical detection which is much higher than in conventional ESR. Even electrons in a single quantum well or heterostructure can be detected by the optical method. There is also the possibility to distinguish between electrons in different quantized levels in heterostructures due to the different spectral position of their photoluminescence. Another advantage is that the electrons are photo-excited; the sample does not need to be n-doped. High-purity samples can be investigated which exhibit narrower linewidths.

Optically Detected Nuclear Magnetic Resonance (ODNMR)

With the presuppositions provided in the preceding sections the basic principle of ODNMR is easily understood. As in ODCESR we assume that an external magnetic field $\mathbf{B}_0$ is applied parallel to $\mathbf{k}$. Perpendicular to it a radio-frequency field $\mathbf{B}_2$ with frequency ω is applied. The NMR resonance frequency is $\omega_0 = \gamma_n \cdot B_0$ with γ_n being the gyromagnetic ratio of the nucleus under consideration. In the frame rotating with ω around the direction of $\mathbf{B}_0$ an effective field $\mathbf{B}_{\mathrm{eff}} = \mathbf{B}_0 - \boldsymbol{\omega}/\gamma_n + \mathbf{B}_2$ acts on the nuclei. The nuclear magnetization is oriented parallel to $\mathbf{B}_{\mathrm{eff}}$. It is seen that in resonance $\mathbf{B}_{\mathrm{eff}}$ is parallel to $\mathbf{B}_2$, which means perpendicular to $\mathbf{k}$. Via the hyperfine interaction this nuclear field acts on the electrons, diminishing their spin polarization via the Hanle effect. So the nuclear magnetic resonance can be detected as a reduction of the degree of circular polarization of the photoluminescence.

The simplified model given above does not take into account several effects which influence the lineshape, position and intensity of the observed resonance lines.

Examples of Experimental Results for Optical Pumping and Optically Detected Magnetic Resonances

These experiments can be performed at liquid helium temperature in a standard photoluminescence setup. In addition one has to provide the possibility of applying transverse (Hanle effect) or longitudinal (ODCESR, ODNMR) magnetic fields. For ODCESR the sample is mounted in a microwave resonator with optical access; for ODNMR a radio-frequency coil is wound around the sample. The state of circular polarization of the exciting laser light has to be controlled. The measured quantity is the sign and degree of circular polarization of the luminescence light at a certain wavelength. The sensitivity can be enhanced by periodically σ^{+}/σ^{-}-modulating either the exciting light or the detection. Which one of these possibilities is used depends on whether or not a high nuclear spin polarization is wanted.

As pointed out above the dynamically polarized nuclei, particularly in GaAs, strongly affect the

ODCESR resonant field. To get reliable values for the effective g-factor, the nuclear spin polarization must be completely suppressed. This can be achieved by σ^+/σ^--modulation of the exciting light with a modulation period much shorter than the nuclear spin relaxation time. But due to imperfections, e.g., if the intensities of σ^+ and σ^- light or their time intervals are not equal, residual optical fields may remain. To get precise values for g^* in addition the NMR has to be saturated by a suitable radio-frequency field. On the other hand, the strong Overhauser shift of the CESR can be useful for the determination of nuclear spin relaxation times. To perform such experiments the nuclei are first polarized by optical pumping with fixed circular polarization and afterwards, for the detection, σ^+/σ^--modulation is switched on.

For the optical detection of NMR a high nuclear spin polarization is favorable. Thus for those experiments one uses fixed polarization of the exciting beam and modulates the detected light.

Figure 4 shows examples of results obtained with a p-channel AlGaAs/GaAs single heterostructure. In this sample due to the doping profile a triangular potential well at the interface in the valence band of the GaAs layer is built, in which quantized hole levels exist. The luminescence band shown in Figure 4a between 821 nm and 825 nm is due to recombination of electrons with holes in these quantized states. For the experiments shown in the other panels of the figure the spectrometer is set at a position within this band. The other lines are due to excitons and impurities and are not interesting for what follows.

In Figure 4b the results of a Hanle experiment are reproduced. The line without noise is the fitted Lorentzian. The fit yielded $\tau = 8.1$ ns and $T_1 = 4.7$ ns.

In Figure 4c a typical ODNMR spectrum of the same sample is plotted. One observes resonances due to ^{75}As at 1.36 MHz, ^{69}Ga at 1.9 MHz and ^{71}Ga at 2.4 MHz. In the inset the ^{75}As resonance is plotted in an extended scale. A quadrupole splitting into three components is clearly resolved. This result demonstrates that the tetrahedral symmetry at the nuclear site is broken either due to local defects or due to the (rather small) lattice mismatch close to the AlGaAs/GaAs interface.

Finally Figure 4d shows the ODCESR spectrum. For the experiment the exciting beam was σ^+/σ^--modulated and in addition during the sweep the NMR of all three nuclei was permanently saturated to make sure that no Overhauser shift



Figure 4 (a) Photoluminescence spectrum of a p-channel AlGaAs/GaAs heterostructure; (b) Hanle curve (luminescence polarization as a function of transverse magnetic field); (c) ODNMR recording; (d) ODCESR recording. Adapted from Schreiner M, Pascher H, Denninger G, *et al.* (1997) Nuclear spin relaxation in AlGaAs/GaAs heterostructures observed via optically detected magnetic resonance (ODMR) experiments. *Solid State Communications* 102: 715. Copyright (1997), with permission from Elsevier.

affects the result. The g-factor calculated from this plot is $|g^*| = 0.468$, which is larger than that found for bulk GaAs. This value was also used for fitting the Hanle curve.

List of Units and Nomenclature

Angle	[rad]
Angular frequency ω	[rad s^{-1}]
Bohr magneton μ_B	9.2742×10^{-24} J T^{-1}
Degree of circular polarization of light Π	
Electric field E	[V m^{-1}]
Gyromagnetic ratio γ	[T^{-1} s^{-1}]
Imaginary unit i	
Intensity I	[W m^{-2}]
Magnetic displacement B	[T]
Permittivity of free space ε_0	8.8542×10^{12} V s A^{-1} m^{-1}
Planck's constant $\hbar$	1.0546×10^{-34} J s
Refractive index n	
Speed of light in vacuum c_o	2.9979×10^{8} m s^{-1}
Spin polarization P	
Susceptibility χ	

CARS	coherent anti-Stokes Raman scattering
CSRS	coherent Stokes Raman scattering
ODCESR	optically detected conduction electron spin resonance
ODMR	optically detected magnetic resonance
ODNMR	optically detected nuclear magnetic resonance

Acknowledgments

The author thanks W. Herbst, B. Müller, R. Rupprecht and M. Schreiner for making unpublished results available.

See also

Magneto-Optics: Interband Magnetoabsorption, Cyclotron Resonance, Spin Flip Raman Scattering. **Semiconductor Physics:** Light Scattering; Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures.

Further Reading

Boswarva IM, Howard RE and Lidiard AB (1964) Faraday effect in semiconductors. *Proceedings of the Royal Society* A269: 125–141.

Dyakonov MI and Perel VI (1984) Theory of optical spin orientation of electrons and nuclei in semiconductors. In: Meier F and Zakharchenya BP (eds) *Optical Orientation*, pp. 11–71. Amsterdam: North-Holland.

Eesley GL (1981) *Coherent Raman Spectroscopy.* Oxford: Pergamon Press.

Furdyna JK (1988) Diluted magnetic semiconductors. *Journal of Applied Physics* 64: R29–R64.

Geist F and Pascher H (1996) Resonance CARS in narrow gap semiconductors. *Journal of Raman Spectroscopy* 27: 289–295.

Geist F, Herbst W, Mejia-Garcia C, *et al.* (1997) Magneto-optical investigations of Eu-based diluted magnetic lead chalcogenides. *Physical Review B* 56: 13042.

Hermann C and Weisbuch C (1984) Optical detection of conduction electron spin resonance in semiconductors and its application to $\mathbf{k} \cdot \mathbf{p}$ perturbation theory. In: Meier F and Zakharchenya BP (eds) *Optical Orientation*, pp. 463–508. Amsterdam: North-Holland.

Krenn H, Herbst W, Pascher H, *et al.* (1999) Interband Faraday and Kerr rotation and magnetization of Pb$_{1-x}$Eu$_x$Te in the concentration range $0 \times \sim 1$. *Physical Review B* 60: 8117.

Levenson MD and Kano SS (1987) *Introduction to Nonlinear Laser Spectroscopy.* San Diego: Academic Press.

Nies R and Kessler FR (1989) Coherent and incoherent magnetooptical reflection and transmission effects of multilayer structures. *Phys. Stat. Sol. (a)* 111: 639–654.

Oh E, Bartholomew DU, Ramdas AK, Furdyna JK and Debeska U (1988) Interband Faraday effect in CdMnSe. *Physical Review B* 38(18): 13183–13190.

Paget D and Berkovits VL (1984) Optical investigation of hyperfine coupling between electronic and nuclear spins. In: Meier F and Zakharchenya BP (eds) *Optical Orientation*, pp. 404ff. Amsterdam: North-Holland.

Pascher H, Geist F, Springholz G, *et al.* (1997) Coherent anti-Stokes Raman scattering in diluted magnetic IV–VI epilayers and superlattices. In: Shen SC, Tang DY, Zheng GZ and Bauer G (eds) *Narrow Gap Semiconductors*, pp. 269–278. Singapore: World Scientific.

Pohlt M, Herbst W, Pascher H, Faschinger W and Bauer G (1998) Magneto-optical Kerr effect in short-period CdTe/MnTe superlattices. *Physical Review B* 57(16): 9988–9994.

Ramdas AK and Rodriguez S (1988) Raman scattering in diluted magnetic semiconductors. In: Furdyna JK and Kossut J (eds) *Diluted Magnetic Semiconductors, Semiconductors and Semimetals*, vol. 25, pp. 345–412. London: Academic Press.

Schreiner M, Pascher H, Denninger G, *et al.* (1997) Nuclear spin relaxation in AlGaAs/GaAs heterostructures observed via optically detected resonance (ODMR) experiments. *Solid State Communications* 102: 715–720.

Interband Magnetoabsorption, Cyclotron Resonance, Spin Flip Raman Scattering

C R Pidgeon, Heriot-Watt University, Edinburgh, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The addition of a magnetic field to an optical study of a semiconductor generally improves the specificity of the experiment, but in particular affects primarily the electrons rather than the lattice so that the magneto-optical properties are determined to a large degree by the electrons alone. The major interest has been in the determination of the electronic energy band structure of semiconductors, both in their bulk and low-dimensional (two-, one-, and zero-dimensional) quantum forms. The magneto-optical experiments fall mainly into two categories according to whether the effects are associated with intraband (within a single conduction or valence band) or interband (valence to conduction band) transitions; there are also hybrid (i.e., higher-order) effects such as spin-flip Raman scattering or two-photon absorption where both inter- and intraband transitions are involved in a two-stage process. Interband transitions occur typically in the visible to mid-infrared (MIR) region, and intraband transitions in the MIR to far-infrared (FIR) region.

Theoretical Background

The most common band structure involved in semiconductor magneto-optics is the so-called quasi-Ge model, which gives an accurate description of group IV, and zincblende (III–V and II–VI) semiconductors, so it is convenient to describe the theory in terms of this model. In this model the small terms associated with inversion asymmetry are neglected to a first approximation. At the Brillouin zone center (i.e., at $k = 0$) the conduction band has s-like symmetry and the triply degenerate valence band p-like symmetry. In the presence of strong spin–orbit coupling, part of this degeneracy is raised resulting in the doubly degenerate (at $k = 0$) heavy and light mass valence bands and a so-called spin–orbit split-off band. The reader should go to the general reviews quoted under 'Further Reading' for the equivalent coverage of other common systems such as the wurzite II–VI and the lead salt systems.

The dynamics of a free electron subject to an external magnetic field have been given by a variety of authors, but the most universally used treatment is that of Landau. For the motion of an electron in a semiconductor we treat first the case of a simple parabolic energy band. For the case of the magnetic field, B, along the z-direction, k_z remains a good quantum number, but k_x and k_y are subsumed into the new magnetic orbital (Landau) quantum number, n. The original three-dimensional energy band, $E = \hbar k^2/2m^*$, is coelesced into a series of one-dimensional Landau sub-bands in the k_z-direction (where the motion along k_z remains unchanged):

$$E_n^{\pm}(k_z) = (n + 1/2)\,\hbar\omega_c + \frac{\hbar k_z^2}{2m^*} \qquad [1]$$

The cyclotron frequency is $\omega_c = eB/m^*$ and μ_{B} is the Bohr magneton. The resulting electron energy eigenvalues at $k_z = 0$ in an external magnetic field (i.e., Landau sub-band extrema) are referred to as Landau levels, LLs. In practice each state is doubly degenerate with spin which results in an additional term $\pm g^* \mu_{\mathrm{B}} B$ on the right-hand side, where g^* is the effective g-factor. (Note that in the presence of strong spin–orbit coupling and small m^*, there is a corresponding g^* which becomes negative and substantially different from the free-electron g-factor; the largest value for a binary elemental compound is that for InSb, where $g^* \approx -50$.) The situation for a simple parabolic conduction band near $k = 0$ is shown in Figure 1a,b. Intraband optical absorption associated with direct transitions between successive Landau sub-bands is referred to as cyclotron resonance (CR) absorption. There are corresponding Landau sub-bands in the valence band, and direct transitions between valence and conduction sub-bands give rise to the so-called interband magneto-optical (IMO) effects.

Expressions for the density of states (DOS) in three, two, and one dimensions in the absence of a magnetic field are given elsewhere ('semiconductor basics' – Pidgeon). In the presence of a magnetic field the three-dimensional energy band is reduced to one-dimensional sub-bands so that the energy dependence of the DOS has the one-dimensional form with the energy given by eqn [1]. Performing this substitution and multiplying by a term for the degeneracy of the Landau levels (LLs) gives the following expression for the total DOS per unit volume:

$$g(E) = \frac{(2m^*)^{1/2}}{4\pi^2\hbar}\,\frac{eB}{\hbar}\sum_n \left[E - (n + 1/2)\,\hbar\omega_c\right]^{-1/2} \qquad [2]$$



Figure 1 (a) Landau sub-bands according to eqn [1] with the magnetic field applied in the *z*-direction. The dashed line shows the parabolic conduction band for *k* along k_z and $B = 0$. (b) Schematic outline of the density of states (DOS) for free electrons in a magnetic field. It comprises the sum of identical contributions from each Landau sub-band. The density of states with $B = 0$ is shown dashed.

Thus, the DOS for Landau sub-bands is quite different from the zero-field DOS, and is a series of square-root singularities with divergences at the energies $(n + 1/2)\hbar\omega_c$. The two cases are illustrated schematically in Figure 1b. Since the optical absorption strength for both interband and intraband transitions is proportional to the joint density of states for the initial and final states, this result shows the important advantage of the use of a magnetic field in semiconductor spectroscopy because it means that the absorption lines for CR or IMO transitions are strongly peaked at the sub-band extrema (i.e., at $k_z = 0$). This allows accurate measurement of LL energy differences for transitions observed in a single experiment, and hence, by comparison to theoretical models, leads to the best determination of fundamental energy-band parameters. The basic LL selection rule can be shown straightforwardly from time-dependent perturbation theory to be $\Delta n = 0$, $\Delta m_s = 0$ for IMO transitions and $\Delta n = 1$, $\Delta m_s = 0$ for CR absorption, where m_s is the spin quantum number (i.e., $\pm\frac{1}{2}$, for spin up and spin down). The cyclotron resonance absorption occurs only for one sense of circularly polarized light, but the IMO effect can occur for all polarizations. The choice then of magnetic field direction, crystal orientation, and polarization of the optical radiation allows extremely detailed determination of the energy band parameters for particular crystal symmetries.

The data are often summarized in a so-called fan diagram of the energy levels, or transition energies, versus magnetic field. Such a plot is shown for hypothetical conduction and valence band LLs in Figure 2a, together with interband and CR transitions. The states are labeled by the Landau quantum number, with selection rules $\Delta n = 0$ and $\Delta n = 1$ for interband and CR absorption transitions, respectively (or $\Delta n = -1$ for CR emission). If the energies of the transitions themselves are plotted versus the magnetic field, then the intercept of the fan plots at $B = 0$ gives the zero-field energy gap. Note that in the presence of excitonic effects (see below) the intercept will give the energy gap plus the exciton binding energy.



Figure 2 Fan plots of the conduction and valence band Landau levels versus magnetic field for simple parabolic bands: (a) a three-dimensional semiconductor; (b) quasi-two-dimensional systems. Some CR and interband magneto-optical transitions are shown by vertical arrows.

For a strictly two-dimensional system the DOS per unit area is independent of energy: $g(E) = m^*/\pi\hbar^2$. In the case of quasi two-dimensional confinement in the *z*-direction the motion in the *z*-direction is quantized, and the total energy becomes (*see* **Semiconductor Physics:** Quantum Wells and GaAs-Based Structures):

$$E = E_i + \frac{\hbar^2}{2m^*}(k_x^2 + k_y^2) \qquad [3]$$

Equation [3] describes a set of confinement sub-bands (parabolas induced by geometric, as opposed to magnetic, confinement), the bottoms of which are at the energies E_i, where i is the sub-band index. The energies, E_i, depend on the shape of the confining potential. The DOS per unit area is in this case a series of step functions of height $m^*/\pi\hbar^2$. From the point of view of magneto-optics, the main effect of the quantum confinement is to suppress the k_z motion, so that in the presence of an external magnetic field along the *z*-direction, the motion is completely quantized. The energy eigenvalues are given by:

$$E_{n,i} = E_i + (n + 1/2)\,\hbar\omega_c \qquad [4]$$

The total DOS becomes:

$$g(E) = \frac{m^* \omega_c}{\pi \hbar} \delta[E - (n + 1/2)\, \hbar \omega_c] \qquad [5]$$

a series of delta-functions located at the energy positions of the LLs. The DOS is obviously more singular in two dimensions than in three dimensions, and leads to substantially sharper magneto-optical and magneto-transport effects. For confined structures the selection rules for interband and intersub-band transitions are identical to the bulk case for the electromagnetic (em) radiation polarized in the xy plane provided that the external magnetic field is along the confinement (z-) direction. The only difference is that the conservation of momentum in the z-direction ($\Delta k_z = 0$) is replaced by a selection rule on the sub-band index, $\Delta i = 0$. A fan plot for this configuration is shown schematically in Figure 2b. For each confinement sub-band transition there is a set of LL transitions. When the energy positions are plotted against B, this leads to a set of Landau 'fans', each of which extrapolates to the sum of a valence plus conduction confinement sub-band energy at $B = 0$. Allowed transitions are shown for the lowest two confinement sub-bands in Figure 2b. Again this picture may be complicated in the presence of excitonic effects at low temperature.

Turning again to the bulk semiconductor picture, eqns [1]–[5] apply for a single parabolic energy band and are valid for the conduction band in the quasi-Ge model. In actual semiconductors further complications arise. Most importantly the triply degenerate p-like valence band (heavy hole, light hole, and split-off band) must be treated by so-called degenerate perturbation theory. In the quasi-Ge model the conduction and three valence bands are treated together as one coupled band system using the so-called $\mathbf{k} \cdot \mathbf{p}$ method (described elsewhere by Zawdzki). With spin this results in an 8×8 matrix equation which has to be diagonalized for the eigenvalues and eigenvectors of the system. The spin–orbit coupling results in so-called complex, mixed-spin valence bands and anomalously spaced low quantum number LLs (the so-called quantum effects). The overall energy band scheme for InSb, near the fundamental direct gap in the center of the Brillouin zone for conduction and (heavy and light mass) valence bands is shown schematically in Figure 3, for no magnetic field and for an applied magnetic field. Each LL is doubly degenerate with spin, the a-set representing the so-called spin-up and the b-set the spin-down states.



Figure 3 (a) Schematic diagram of the conduction and valence bands for InSb (symmetry labels Γ_6 and Γ_8 respectively) at $B = 0$. (b) Computed Landau levels for the conduction and valence bands of InSb at 4 K ($E_g = 0.23$ eV) with $B = 5$ T along the [100] direction, grouped according to the so-called a- and b-spin sets (see text).

Experimental

The first serious use of magneto-optics to study effective mass and energy band structure of semiconductors was in the microwave cyclotron resonance (i.e., intraband) investigations of Ge and Si in the early 1950s. Classically it can be shown that the ratio of the radiation power absorbed, P, to power absorbed in zero magnetic field, P_0, is given by:

$$\frac{P}{P_0} = \frac{1 + (\omega^2 + \omega_c^2)\tau^2}{[1 + (\omega_c^2 - \omega^2)\tau^2]^2 + 4\omega^2\tau^2} \qquad [6]$$

where τ is the collision time of the carriers. This expression for P/P_0 describes cyclotron resonance absorption and is plotted as a function of frequency in Figure 4 for different values of the parameter $\omega_c\tau$. Clearly the peak absorption occurs at $\omega = \omega_c$, namely at cyclotron resonance. Also evident is the very important requirement for observation of a clear resonance that $\omega_c\tau > 1$; this condition corresponds physically to a travel time between collisions of the particle of at least $1/2\pi$ of a revolution so that the particle can interact for a sufficiently long time



Figure 4 Ratio of the radiation power absorbed to the power absorbed at zero magnetic field, P/P_0, plotted as a function of ω/ω_c according to eqn [6], for different values of $\omega_c\tau$ from 0.5 to 5.0.

with the electromagnetic wave to absorb energy. For pure materials and low temperatures (where the condition $\omega_c\tau > 1$ is achievable) this is the best technique for obtaining the details of the electron and hole band parameters of a semiconductor near $k = 0$. The most thorough and successful studies of this type have been achieved in pure Si, Ge, and InSb where (with the aid of optical excitation to populate the levels shown in Figure 3) all possible electron, light and heavy hole cyclotron resonances have been resolved. In this way the valence band quantum effects, described above, have been observed in detail. The technique is equally applicable in low-dimensional systems where CR of both electrons and holes has been resolved in a large number of n- and p-type semiconductor heterostructures and quantum wells.

In interband – either absorption or photoluminescence (PL) – spectroscopy at low temperatures, the photo-excited electrons and holes interact and form excitons (*see* **Semiconductor Physics:** Excitons). In many cases the excitonic state may be described in the so-called envelope function approximation as a hydrogenic system, in which the electron and hole are bound by their mutual Coulomb attraction. The energy spectrum of such a hydrogenic exciton is given by

$$E_n = \frac{\mu e^4}{2\hbar^2\varepsilon^2 n^2} \qquad [7]$$

where n is the principal quantum number ($n = 1, 2, 3, \ldots$, but note that the symbol n is also used for the Landau quantum number above), μ is the electron–hole reduced effective mass, and ε is the background dielectric constant. In low-dimensional (i.e., confined) semiconductor systems of the type described above the degeneracy of the valence bands at $k = 0$ is removed, and two types of excitons are observed; these are referred to as 'heavy' and 'light' hole excitons in the literature, where heavy and light refer to the effective masses along the confinement direction. These excitons can move freely (in the remaining two unconfined directions) or be bound to an impurity or defect. In these systems exciton absorption may be observed involving not only the ground-state excitons, but also excitons associated with higher confinement sub-bands. This is shown for the so-called asymmetric quantum well system $\mathrm{Al}_y\mathrm{Ga}_{1-y}\mathrm{As}/\mathrm{In}_x\mathrm{Ga}_{1-x}\mathrm{As}/\mathrm{GaAs}$ in Figure 5a. The data are taken both by the direct PL method (where the exciting beam has an energy much larger than the bandgap and the electrons and holes de-excite instantaneously to the bottom of the bands before recombining as exiton recombination radiation), and so-called PL excitation spectroscopy (where the exciting beam is a tunable laser, tuned into resonance with the successive exciton resonances).

The interband Landau transitions can be observed either in PL or as excitations in a magneto-absorption or magnetoreflection experiment. Excitons are affected differently by the application of an external magnetic field depending whether the ratio $\gamma = \hbar\omega_c/2E_B$ (where E_B is the exciton binding energy with $n = 1$ above) is less than or greater than one. In the so-called magnetic limit where $\gamma \gg 1$, the excitonic ground state moves approximately as $\frac{1}{2}\hbar\omega_c$, i.e., linearly with B. In this regime the magnetic field energy is the dominant term in the exciton Hamiltonian. The various states of the exciton (ground and excited states) become associated with the interband LL transition, and exhibit an energy dependence that is nearly identical to the free carrier LL transitions. The energies of the various excitonic transitions are shifted down with respect to the corresponding LL transitions by an amount equal to the binding energy of the excitonic state to that LL. Typical PL and PLE (photoluminescence excitation)



Figure 5 Interband transition data obtained in zero magnetic field (a) and fields of 5 T (b) and 10 T (c) from asymmetric quantum wells. The dashed lines indicate data obtained from PL and the solid lines data from PLE. The arrows in (a) indicate the calculated interband transition energies 1 → 1, 2 → 1, and 2 → 2, the latter being clearly resolved in PLE (the asymmetric wells mean that transitions with $\Delta i \neq 0$ are allowed). In (b) and (c) the development of the spectra into LL transitions is clearly seen, although beyond 1.48 eV the analysis is obviously extremely complicated by the overlap of LL transitions associated with all three of the above sub-bands.

spectra for interband magneto-optical transitions are shown in Figure 5b,c for a fixed applied magnetic field in the asymmetric quantum well system $Al_yGa_{1-y}As/In_xGa_{1-x}As/GaAs$.

Spin Flip Raman Scattering

In addition to the interband transitions discussed above, Raman scattering of intersub-band transitions between conduction or valence band LLs can also be studied. It provides a versatile means of probing band edge parameters of electrons and holes in semiconductors since the excitation (normally a laser pump) is not confined to the resonance frequencies under investigation, i.e., any pumping energy below the band edge will do. Electronic Raman scattering is then allowed between LLs via virtual interband transitions. In the presence of spin–orbit coupling strong spin-flip processes via electric dipole transitions become allowed giving rise to the so-called spin-flip Raman (SFR) cross-section. This is a single-particle process in which electrons or holes interacting with the radiation change their spin state. This process can be made to go stimulated particularly easily when the pump radiation is resonant with the bandgap of the semiconductor, forming the spin-flip Raman laser. The most important practical case has probably been that of InSb, resonantly pumped near 5 μm with the CO laser. In this case the small effective mass of a narrow-gap semiconductor in the presence of substantial spin–orbit coupling leads to both an extremely large anomalous effective *g*-factor ($g^* \sim -50$) – giving a large tuning range, $\Delta E = \hbar\omega_{SF} = g^*\beta B$ – and a strong cross-section which is larger than that of the free electron by a factor $(m_0/m^*)^2$. Efficient cw operation is possible with threshold powers less than 50 mW.

SFR scattering has enabled the observation of a great variety of excitations in nonmagnetic and dilute magnetic semiconductors, including: free electrons and holes, electrons bound to donors and holes bound to acceptors, scattering from bound magnetic polarons, and scattering due to SF transitions within the Zeeman multiplets of paramagnetic ions. In addition to pure SF transitions, combined resonances with combinations such as $\omega_{CR} \pm \omega_{SF}$ have also been detected. The process has also been used in a similar manner to electron spin resonance to study coherent processes, including Raman photon echo spectroscopy in semiconductors.

See also

Magneto-Optics: Faraday Rotation, CARS, ODMR, ODSR, Optical Pumping. **Semiconductor Physics:** Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures.

Further Reading

Häfele HG (1991) Spin-flip raman scattering. In: Landwehr G and Rashba WI (eds) *Landau Level Spectroscopy in Modern Problems in Condensed Matter Sciences*, 27.1, 207–275.

Petrou A and McCombe BD (1991) Magnetospectroscopy of confined semiconductor systems. In: Landwehra G and Rashba WI (eds) *Landau Level Spectroscopy in Modern Problems in Condensed Matter Sciences*, 27.1, 679–775.

Pidgeon CR (1980) Free carrier optical properties of semiconductors. In: Balkanski M (ed.) *Optical Properties of Solids. Handbook of Semiconductors*, pp. 223–328. Amsterdam, The Netherlands: North-Holland.

Zawadzki W (1991) Intraband and interband magneto-optical transitions in semiconductors. In: Landwehr G and Rashba WI (eds) *Landau Level Spectroscopy in Modern Problems in Condensed Matter Sciences*, 27.1, 483–512.

MATERIALS CHARACTERIZATION TECHNIQUES

Contents

$\chi^{(2)}$
$\chi^{(3)}$

$\chi^{(2)}$

R C Eckardt, Cleveland Crystals, Inc., Highland Heights, OH, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Techniques used to measure second-order susceptibility $\chi^{(2)}$ or nonlinear optical coefficients are described in this article, and some measured values are quoted. These are the parameters that describe the property of a material that is responsible for second-harmonic generation and other three-wave nonlinear optical interactions. These other interactions include sum- and difference-frequency generation in which two waves combine to generate a third wave of a frequency that is the sum or difference of the first two waves. Also included are optical parametric generation and optical parametric oscillation, in which a single pump wave generates two resulting waves with frequencies that sum to the frequency of the pump wave. The measurement techniques involve measuring the efficiency of nonlinear frequency conversion by these processes.

The measurements require a great deal of care and precision, and it is advisable to perform a comparison with previous measurements and obtain correlation with accepted standards whenever possible. A great deal of effort continues to be expended by researchers to establish correlations between measurements and provide additional values that are accepted as standards. A number of techniques have been used for these measurements sometimes yielding results that disagree. There are, however, values derived from early measurements that have proven accurate. In these measurements it is necessary to accurately control and characterize the polarization, power, spectral distribution, and spatial and temporal intensity distribution of the incident radiation and accurately measure the frequency-converted light, which can be many orders of magnitude smaller.

The development and availability of single-longitudinal-mode and nearly diffraction-limited lasers has greatly reduced the ambiguity and simplified increased accuracy of measurements of second-order nonlinear optical coefficients. The improved optical quality of nonlinear-optical crystals has also been an important component of the increased accuracy of measurement. Measurement techniques have also improved, providing absolute measurements of optical intensity over wide dynamic ranges at different wavelengths. Until the early 1990s, there was a range of measured values for nonlinear optical coefficients of common nonlinear materials, and numerous definitions were in use. Caution is required when consulting early publications on this topic, and some of this ambiguity is carried over to present time. Different definitions vary by factors of 2 and the permittivity of free space, $\varepsilon_0 \cong 8.854 \times 10^{-12}$ C/N $\times$ m^2. It is important that the definition of a nonlinear optical coefficient is clear before a value is used. This can be done through a statement of the nonlinear electric polarization or the coupled equations for nonlinear frequency conversion.

The standard techniques that have been used to measure nonlinear optical coefficients are covered in detail in publications listed in the Further Reading at the end of this article. Brief descriptions of some of these techniques, such as Maker-fringe and wedge, optical parametric fluorescence, and phase-matched second-harmonic generation, will be presented in this article. Each of these techniques has a unique set of advantages and disadvantages. There was some lively controversy over the technique that provided the most accurate measurements and those measurements that should be dismissed. Measurements based on phase-matched second-harmonic generation had the advantage of being most similar to practical application of nonlinear optical frequency conversion. However, the large divergence and multiple-longitudinal-mode operation of early lasers made this method unreliable. Even relative comparisons of nonlinear optical coefficients between different materials were inaccurate because highly structured laser pulses had different conversion characteristics due to differences in bandwidth acceptance, group velocity walkoff, and birefringent walkoff in different materials.

Nonlinear optical coefficients of improved accuracy were required for analysis of optical harmonic conversion in the large, well-characterized laser systems used in inertial-confinement fusion research. The development of these systems provided a standardization on the value of $d_{36} = 0.39\ \mathrm{pm\,V^{-1}}$ ($1\ \mathrm{pm} = 10^{-12}\ \mathrm{m}$) for second-harmonic generation of neodymium laser radiation in the material potassium dihydrogen phosphate (KH_2PO_4 or KDP). The development of injection-seeded Q-switched lasers provided single-longitudinal-mode laser output that allowed the phase-matched second-harmonic techniques to be extended to provide more accurate absolute measurements and relative comparisons on KDP and a number of other materials. Correlation was achieved on a larger number of relative and absolute measurements of nonlinear optical coefficients to provide some systematic agreement. It is not well understood why the earlier measurements referenced to optical parametric fluorescence produced values that were higher by about 60%. Measurement techniques have been further refined, and more exacting measurements are leading agreement, using different methods of measurement on an increasing number of nonlinear optical materials.

Definitions

The definition of the nonlinear optical coefficient can be specified in a number of ways. Examples given here are how the coefficient relates to the nonlinear electric polarization in a material, the coupled equations for nonlinear frequency conversion, and expressions describing second-harmonic generation with a monochromatic plane-wave fundamental.

The second-order optical nonlinearity is reported as both the second-order susceptibility $\chi^{(2)}$ and the second-order nonlinear optical coefficient d, which usually differ in definition by a factor of two. These are third-rank tensors that relate products of components of the electric field vector E_j and E_k to the vector components of the nonlinear polarization P_i^NL. The second-order susceptibility typically is used to express instantaneous values:

$$P_\mathrm{i}^\mathrm{NL}(t) = \varepsilon_0 \sum_{j,k} \chi_{ijk}^{(2)} E_j(t) E_k(t) \tag{1}$$

whereas the nonlinear optical coefficient more often is used to relate the vector amplitudes of frequency components of these quantities. The electric field at the fundamental angular frequency ω can be expressed as

$$E_j(\omega, \mathbf{r}, t) = \frac{1}{2}\{E_j(\omega) \exp \mathrm{i}(\mathbf{k}_\omega \cdot \mathbf{r} - \omega t) + c.c.\} \tag{2}$$

and the nonlinear polarization at the harmonic frequency 2ω can be expressed as

$$P_\mathrm{i}^\mathrm{NL}(2\omega,\mathbf{r},t) = \frac{1}{2}\left\{P_\mathrm{i}^\mathrm{NL}(2\omega) \exp \mathrm{i}(2\mathbf{k}_\omega \cdot \mathbf{r} - 2\omega t) + c.c.\right\} \tag{3}$$

The intensity is given by $I = (nc\varepsilon_0/2)|E|^2$. The relationship between the complex amplitudes expressed in terms on the nonlinear optical coefficient tensor is

$$P_\mathrm{i}^\mathrm{NL}(2\omega) = \varepsilon_0 \sum_{j,k} d_{ijk}(-2\omega;\omega,\omega) E_j(\omega) E_k(\omega) \tag{4}$$

When waves of three different frequencies are involved, the expression becomes

$$P_\mathrm{i}^\mathrm{NL}(\omega_3) = 2\varepsilon_0 \sum_{j,k} d_{ijk}(-\omega_3;\omega_2,\omega_1) E_j(\omega_2) E_k(\omega_1) \tag{5}$$

Expressing the coefficient as $d_{ijk}(-\omega_3;\omega_1,\omega_2)$ allows for dispersion and indicates that fields at frequencies ω_1 and ω_2 interact to produce a nonlinear polarization at frequency ω_3, the sum of the first two frequencies. The relationship between the second-order electrical susceptibility and the second-order nonlinear optical coefficient is

$$\chi_{ijk}^{(2)} = 2 d_{ijk} \tag{6}$$

The dispersion of nonlinear optical coefficients is approximated by the use of Miller's delta:

$$\delta_{ijk} = \frac{d_{ijk}(-\omega_3;\omega_2,\omega_1)}{(n_\mathrm{i}^2(\omega_3)-1)(n_j^2(\omega_2)-1)(n_k^2(\omega_1)-1)} \tag{7}$$

The indices of refraction in the direction of the electric field components $E_m(\omega_n)$ are $n_m(\omega_n)$ for $m=i,j,k$ and $n=1,2,3$. There is some theoretical and experimental justification for treating the components of Miller's delta as constants. Earlier definitions of Miller's delta included multiplication by ε_0, the permittivity of free space.

The nonlinear optical coefficient is usually reduced to a scalar quantity, the effective nonlinear coefficient or d_{eff}, that relates only the specific vector components of the fields involved in the interaction. The effective nonlinear optical coefficient will be discussed in more detail later. The coupled equations for second-harmonic generation using d_{eff} are

$$\frac{\mathrm{d}E_{2\omega}(z)}{\mathrm{d}z} = \mathrm{i}\,\frac{\omega d_{\text{eff}}}{n_{2\omega}c} E_\omega(z)E_\omega(z)\exp(-\mathrm{i}\,\Delta kz) \qquad [8]$$

$$\frac{\mathrm{d}E_{\omega}(z)}{\mathrm{d}z} = \mathrm{i}\,\frac{\omega d_{\text{eff}}}{n_{\omega}c} E_\omega(z)E^*_\omega(z)\exp(\mathrm{i}\,\Delta kz) \qquad [9]$$

Here ω is the angular frequency of the fundamental wave; z is distance in the direction of propagation, $n_{2\omega}$ and n_ω are the refractive indices of the harmonic and fundamental respectively; and c is the speed of light in free space. The complex electric field amplitudes of the harmonic and fundamental, $E_{2\omega}(z)$ and $E_\omega(z)$, respectively, are assumed to be slowly varying functions of position compared with the oscillation of the carrier waves $\exp \mathrm{i}(\mathbf{k}_{2\omega}\cdot\mathbf{r} - 2\omega t)$ and $\exp \mathrm{i}(\mathbf{k}_{\omega}\cdot\mathbf{r} - \omega t)$, with $\mathbf{k}_{2\omega}$ and $\mathbf{k}_\omega$ the wavevectors of harmonic and fundamental; the asterisk indicates complex conjugate. The quantity Δk is the wavevector mismatch and is given by $\Delta k = k_{2\omega} - 2k_\omega$. These are simplified expressions that apply to nearly monochromatic plane waves. Two solutions to the coupled equations are

$$I_{2\omega}(z) = \frac{2\omega^2 d_{\text{eff}}^2 l^2 I_\omega^2(0)}{n_{2\omega}n_\omega^2 c^3 \varepsilon_0}\,\frac{\sin^2(\Delta kz/2)}{(\Delta kz/2)^2} \qquad [10]$$

for insignificant depletion of the fundamental amplitude and

$$I_{2\omega}(z) = I_\omega(0)\tanh^2\sqrt{\frac{2\omega^2 d_{\text{eff}}^2 z^2 I_\omega(0)}{n_{2\omega}n_\omega^2 c^3 \varepsilon_0}} \qquad [11]$$

for the case of perfect phase matching $\Delta k = 0$ and allowing depletion of the fundamental. The quantity $I_{2\omega}(z)$ is the harmonic intensity after propagating a distance z in the nonlinear material, and $I_\omega(0)$ is the fundamental intensity at the input surface of the nonlinear material where $I_{2\omega}(0) = 0$.

The above relationships for nonlinear polarization, the coupled equations for second-harmonic generation, or harmonic conversion of a monochromatic plane wave, each determine the definition of the second-order nonlinear optical coefficient.

Symmetry

Symmetry has an important role in the measurement of nonlinear optical coefficients. Indeed the second-order nonlinear optical coefficient must be identically zero if the material has inversion symmetry. This restricts materials to noncentrosymmetric crystals or isotropic materials in which inversion symmetry is removed by such techniques as application of an electric field or polymeric materials in which alignment of molecules is achieved by some poling process. The discussion here is limited to noncentrosymmetric crystals.

The nonlinear optical coefficient is a tensor of rank 3. Representation of the tensor in a rotated coordinate system is described by

$$d'_{ijk} = \sum_{l,m,n} R_{il}R_{jm}R_{kn}d_{lmn} \qquad [12]$$

where R_{il} is the matrix that describes rotation of the initial coordinate system xyz to the new coordinate system $x'y'z'$. The representation of a vector r_l in the original coordinate system becomes $r'_{\mathrm{i}} = \sum_l R_{il}r_l$ in the new coordinate system. A required symmetry property of the nonlinear optical tensor, that exchange of the second two indices of a component does not change the value of the component $d_{ijk} = d_{ikj}$, allows the third-rank tensor to be written as a 3 by 6 matrix:

$$\begin{pmatrix} d_{11} & d_{12} & d_{13} & d_{14} & d_{15} & d_{16} \\ d_{21} & d_{22} & d_{23} & d_{24} & d_{25} & d_{26} \\ d_{31} & d_{32} & d_{33} & d_{34} & d_{35} & d_{36} \end{pmatrix} \qquad [13]$$

with the components of the matrix related to the tensor components by

$$\begin{aligned} &d_{i1} = d_{i11} \quad d_{i4} = d_{i23} = d_{i32} \\ &d_{i2} = d_{i22} \quad d_{i5} = d_{i13} = d_{i31},\; i = 1,2,3 \\ &d_{i3} = d_{i33} \quad d_{i6} = d_{i12} = d_{i21} \end{aligned} \qquad [14]$$

A further property, tensor components with any permutation of the indices are equal $d_{ijk} = d_{kij}$, called Kleinman symmetry or Kleinman's conjecture, is often applied if there is no absorption at any of the wavelengths involved. Kleinman symmetry assures that the amount of energy depleted from the fundamental is equal to the amount of energy gained by the second harmonic. This reduces the number of independent components of the nonlinear optical matrix to 10: d_{11}; $d_{12} = d_{26}$; $d_{13} = d_{35}$; $d_{14} = d_{25} = d_{36}$; $d_{15} = d_{31}$; $d_{16} = d_{21}$; d_{22}; $d_{23} = d_{34}$; $d_{24} = d_{32}$; and d_{33}. Sometimes components equal, according to Kleinman symmetry, are measured individually, either as a check of the measurement or to check the validity of the conjecture.

Crystal symmetry places additional constraints on the components of the nonlinear optical matrix. These constraints determine the components that must be zero and determine additional relationships between the nonzero components. Matrices for selected crystal point groups are given in Table 1. Effective nonlinear optical coefficients can be found by a coordinate frame transformation in which the rotated axes align with the direction of propagation and the eigen polarizations. Effective nonlinear coefficients for a few crystal point groups are given in Table 2. More complete listings of both the reduced matrices and effective nonlinear optical coefficients are given elsewhere.

Table 1 Nonlinear coefficient matrices for selected crystal point groups

Orthorhombic *mm*2	Hexagonal 6
$\begin{pmatrix} 0 & 0 & 0 & 0 & d_{15} & 0 \\ 0 & 0 & 0 & d_{24} & 0 & 0 \\ d_{31} & d_{32} & d_{33} & 0 & 0 & 0 \end{pmatrix}$	$\begin{pmatrix} 0 & 0 & 0 & d_{14} & d_{15} & 0 \\ 0 & 0 & 0 & d_{15} & -d_{14} & 0 \\ d_{31} & d_{31} & d_{33} & 0 & 0 & 0 \end{pmatrix}$
Tetragonal $\bar{4}2m$	Hexagonal 6*mm*
$\begin{pmatrix} 0 & 0 & 0 & d_{14} & 0 & 0 \\ 0 & 0 & 0 & 0 & d_{25} & 0 \\ 0 & 0 & 0 & 0 & 0 & d_{36} \end{pmatrix}$	$\begin{pmatrix} 0 & 0 & 0 & 0 & d_{15} & 0 \\ 0 & 0 & 0 & d_{15} & 0 & 0 \\ d_{31} & d_{31} & d_{33} & 0 & 0 & 0 \end{pmatrix}$
Trigonal 3*m* $m \perp X$	Cubic $\bar{4}3m$
$\begin{pmatrix} 0 & 0 & 0 & 0 & d_{15} & -d_{22} \\ -d_{22} & d_{22} & 0 & d_{15} & 0 & 0 \\ d_{31} & d_{31} & d_{33} & 0 & 0 & 0 \end{pmatrix}$	$\begin{pmatrix} 0 & 0 & 0 & d_{14} & 0 & 0 \\ 0 & 0 & 0 & 0 & d_{14} & 0 \\ 0 & 0 & 0 & 0 & 0 & d_{14} \end{pmatrix}$

Measurements

Usually the symmetry of a nonlinear crystal is determined by techniques such as X-ray diffraction or surface morphology. Crystal symmetry determines the nonzero components of the second-order nonlinear optical tensor. Nonphase-matched second-harmonic-generation techniques, such as Maker-fringe and wedge measurements, allow selection of polarizations and propagation directions relative to the crystal lattice that isolates individual components of the tensor. Phase-matched measurement techniques usually require propagation in a direction for which an effective nonlinear optical coefficient applies and can involve more than one tensor component. Parametric fluorescence and sum- and difference-frequency-generation measurements are phase-matched processes that involve three wavelengths. All of the measurement techniques have been used with pulsed and continuous-wave laser output. In all of these methods, except parametric fluorescence, it is necessary to accurately characterize the incident radiation. Measurements relative to a standard material avoid some of the concerns of characterization of the fundamental radiation. Relative measurements are important in that they allow correlation between different sets of measurements. Measurement sets, that include both relative and absolute measurements on a number of materials, are useful in developing correlations that achieve more accurate compilations of values.

It is desirable to have an incident beam with a Gaussian-like transverse intensity distribution and close to diffraction limited propagation. Gaussian beams have advantages that they are most easily characterized and their propagation is described with relatively simple analytical methods. Accurate temporal characterization of the incident light is also essential. Here it is desirable to have stable single-mode laser operation to produce narrow bandwidth light that is well within phase-matching acceptance bandwidths and that has temporal structure slow enough to be easily characterized and slow enough

Table 2 Effective nonlinear optical coefficient for a few symmetries

*mm*2, a point group with biaxial birefringence		
$\phi = 0$, two waves $E \parallel Y$, one wave $E \parallel XZ$	$d_{\mathrm{eff}} = d_{32} \sin\theta$	
$\phi = 90°$, two waves $E \parallel XY$, one wave $E \parallel Z$	$d_{\mathrm{eff}} = d_{31} \cos^2\phi + d_{32} \sin^2\theta$	
$\phi = 90°$, two waves $E \parallel X$, one wave $E \parallel YZ$	$d_{\mathrm{eff}} = d_{31} \sin\theta$	
Some crystal symmetry groups with uniaxial birefringence		
point group	two e rays and one o ray	two o rays and one e ray
$\bar{4}2m$	$d_{\mathrm{eff}} = d_{14} \sin^2 2\theta \cos 2\phi$	$d_{\mathrm{eff}} = -d_{14} \sin\theta \sin 2\phi$
3*m*	$d_{\mathrm{eff}} = d_{22} \cos^2\theta \cos 3\phi$	$d_{\mathrm{eff}} = d_{15} \sin\theta - d_{22} \cos\theta \sin 3\phi$
6 and 6*mm*	$d_{\mathrm{eff}} = 0$	$d_{\mathrm{eff}} = d_{15} \sin\theta$



Figure 1 Schematic illustration of an experimental setup to record Maker-fringe measurements.

that group-velocity mismatch will be of no concern. Generating such laser output usually requires special techniques, such as injection-seeded pulse operation or stabilized single-frequency cw operation. Often spatial filters are required to improve the beam quality on the laser output. Even though these topics are only mentioned here, the techniques are important and demand much effort.

The analysis of measurements can also be complicated. Consider the Maker-fringe measurement technique (Figure 1). In this method a focused fundamental beam is incident on a thin slab of oriented nonlinear optical material for nonphase-matched second-harmonic generation. The thickness of the slab is large enough that the function $\sin(\Delta kz/2)$ has gone through many cycles. As the crystal is rotated both the path length in the material l and the wave vector mismatch Δk change, and $\sin^2(\Delta k{\cdot}l/2)$ oscillates between maxima and minima (Figure 2). The coherence length $L_c = \pi/\Delta k$ is normally small enough that conversion remains in the region of small depletion of the fundamental. Knowledge of the material dispersion and birefringence, required to calculate Δk, or L_c, can be obtained from the fringe spacing. Ideally, the incident fundamental beam will be focused to a spot size w_0, small enough to provide measurable harmonic conversion but large enough that the near-field approximation, in which diffraction is not significant, can be used for analysis of harmonic generation. In this case integration over the incident fundamental intensity distribution $I_\omega(r, z = 0) = I_{\omega,0} \exp(-2r^2/w_0^2)$ yields an expression for the harmonic power:

$$W_{2\omega}(\alpha) = \frac{8\omega^2 d_{\mathrm{eff}}^2(\alpha) W_\omega^2 L_c^2(\alpha)}{\pi^3 w_0^2 n^3 c^3 \varepsilon_0} \sin^2\left(\frac{\pi l(\alpha)}{2L_c(\alpha)}\right) \times \text{correction factors} \qquad [15]$$



Figure 2 The envelope and spacing of the fringes allow determination of the second-order nonlinear optical coefficient and the coherence length.

where α is the angle of incidence of the fundamental radiation, $W_{2\omega}(\alpha)$ is the second harmonic power, and W_ω is the incident fundamental power. This equation applies to cw radiation. It is necessary to integrate over the temporal distributions for pulsed fundamental light. The effective nonlinear coefficient $d_{\mathrm{eff}}(\alpha)$, the path length in the crystal $l(\alpha)$, and the coherence length $L_c(\alpha)$ change with the angle of incidence α. The correction factors include Fresnel losses at the crystal surfaces, harmonic generation at the surfaces, multiple reflections between the surfaces, absorption at either fundamental or harmonic wavelengths, and walkoff due to non-normal incidence and birefringence.

The wedge technique (Figures 3 and 4) also uses nonphase-matched second-harmonic generation. A wedged sample is translated through a focused fundamental beam, and the above equation applies with the angle α constant. The crystal length l varies with transverse position. It is important that the wedge angle and the fundamental beam spot size are chosen so that the entire beam fits well within a maximum of conversion and the beam is large enough to avoid divergence due to diffraction. Both the Maker-fringe



Figure 3 The setup for wedge measurements is similar to that used for Maker-fringe measurements but with a wedged sample translated in the fundamental beam to change path length.



Figure 4 The harmonic intensity cycles between a minimum and maximum when the path is changed by one coherence length.

and wedge measurements have the advantage of being able to isolate individual components of the nonlinear optical tensor. Harmonic power can be low with cw beams requiring chopped, lock-in detection methods or even photon-counting techniques. Even with pulsed fundamental radiation, peak harmonic power may only be at the level of milliwatts. It is necessary to isolate the harmonic radiation from the fundamental radiation that could have peak power in the range of 10^5 W for a Q-switch laser.

Phase-matched second harmonic generation (Figure 5) offers a measurement technique that is similar to practical applications. Harmonic signals are large, thus simplifying detection. However, it is helpful to keep conversion levels below a few percent to allow the use of small depletion approximations in data analysis. Good optical quality of the nonlinear optical material and good quality and accurate characterization of the fundamental radiation are important in this measurement technique. The analysis is simplified for low levels of conversion, spectral distribution well within the phase-matching bandwidth, no absorption or other losses, and no significant diffraction or walkoff. If the fundamental intensity is a pulse with distribution of $I_\omega(r,t) = I_{\omega,0} \exp(-t^2/\tau^2)\exp(-2r^2/w_0^2)$, integration yields second-harmonic energy:

$$\begin{aligned} U_{2\omega} &= \int_{-\infty}^{\infty} \mathrm{d}t \int_0^{\infty} 2\pi r\, \mathrm{d}r I_{2\omega}(r, z=l) \\ &\approx \frac{2\sqrt{2}\omega^2 d_{\mathrm{eff}}^2 l^2 U_\omega^2}{n^3 c^3 \varepsilon_0 \pi^{3/2} \tau w_0^2} \frac{\sin^2(\Delta k l/2)}{(\Delta k l/2)^2} \end{aligned} \qquad [16]$$

where $U_{2\omega}$ is the second harmonic energy and U_ω is the fundamental energy, r is the radial coordinate, t is time, and l is the length of the material. Harmonic conversion can be measured as Δk and varied, either by crystal rotation or temperature change, to confirm that optical quality of the nonlinear material and incident fundamental radiation are a level of tuning that is accurately predicted by theory (Figure 6). Even this simplified equation shows the importance of accurate characterization of the fundamental radiation and second-harmonic conversion in obtaining values of the nonlinear optical coefficient. Conversion efficiency is calculated more accurately with detailed analytical techniques or numerical methods, provided accurate and complete characterization of the fundamental radiation is available.

Parametric fluorescence, in principle, offers an experimental simplification over second-harmonic generation techniques. Parametric fluorescence (Figure 7) is a phase-matched technique in which a pump beam of angular frequency ω_p produces a signal beam and an idler beam of angular frequencies $\omega_\mathrm{s} + \omega_\mathrm{i} = \omega_\mathrm{p}$ by the process of spontaneous parametric generation. It is only necessary to measure the ratio of the generated signal power W_s and the incident pump power W_p. The signal power is given by

$$W_\mathrm{s} = \frac{2(h/2\pi)\omega_\mathrm{s}^4 \omega_\mathrm{i} d_{\mathrm{eff}}^2 n_\mathrm{s} l W_\mathrm{p} \Omega}{(2\pi)^2 \varepsilon_0 c^5 n_\mathrm{i} n_\mathrm{p} |\partial \Delta k / \partial \omega_\mathrm{s}|_{\omega p}} \qquad [17]$$

where h is Planck's constant, Ω is the solid angle of detection (inside the crystal), and n_s, n_i, and n_p are



Figure 5 A setup for a relative measurement of second-order nonlinear optical coefficient based on phase-matched second-harmonic generation is shown.



Figure 6 Observation of a theoretically predicted phase-matching tuning curve confirms required optical quality.

the indices of refraction of the signal, idler, and pump respectively. The absolute value of the partial derivative of $\Delta k = k_p - k_s - k_i$, with respect to signal frequency with the pump frequency held constant, is

$$|\partial \Delta k / \partial \omega_s|_{\omega p} = \frac{1}{c}\left| n_s - n_i + \omega_s \frac{dn_s}{d\omega_s} - \omega_i \frac{dn_i}{d\omega_i} \right| \quad [18]$$

It is still not well understood why the carefully performed earlier measurements by this method produced nonlinear optical coefficient values larger than those obtained by other techniques.

Tabulations of measurements of nonlinear optical coefficients are included in handbooks. The Internet posting ‘SNLO’ listed in the Further Reading is a good source of up-to-date values. Table 3 lists some nonlinear optical coefficients obtained from several sources. Signs of these coefficients are not always well determined, and they are reproduced where given and may only indicate relative polarity. Point group symmetry is given with some comments about axis assignments for the *mm*2 point group. The fundamental wavelength is given for second-harmonic measurements and twice the shortest wavelength is given for three-wave processes. Many of the values obtained by Shoji *et al.* are based on carefully performed wedge measurements with single frequency cw lasers and taking detailed account of multiple reflections in the analysis. Their measurements for congruent $LiNbO_3$ reported agreement between Maker-fringe and wedge measurements, and phase-matched difference-frequency generation measurements, and finally agreement with parametric fluorescence. The measurements of Alford and Smith combined optical-parametric amplification and second-harmonic generation at a number of different wavelengths and correlation with values previously reported in the literature to examine the validity of using a constant Miller’s delta, and reported best-fit values for the second-order nonlinear coefficient. Constant Miller’s delta provided reasonably accurate wavelength scaling, with good agreement for most materials in recent measurements.

The measurements of the nonlinear optical coefficients of $KNbO_3$, listed in Table 3 are of particular interest. These measurements were performed by the separated-beam wedge technique (Figure 8). With this technique, a large wedge angle is used in a relatively long crystal and with a larger fundamental beam than in the conventional wedge technique. The beam is large enough that many fringes are present in the second-harmonic at the exit surface. The fringe structure causes focused harmonic radiation to diffract into two clearly resolved spots. Integration of an earlier equation, with constant fundamental field amplitude $E_\omega(0)$, provides a simplified expression of the second-harmonic field $E_{2\omega}(z, t)$ in terms of a free wave with propagation constant



Figure 7 Spontaneous optical parametric fluorescence requires measurement of the ratio of the power of the signal fluorescent to the power of the pump radiation. The calibration laser is used to measure the signal transmission of the filtering system used to block the pump radiation from reaching the photomultiplier tube (PMT).

Table 3 Selected nonlinear optical coefficients

Material	*Point group*	*Nonlinear optical coefficient (pm V^{-1})*		*Wavelength*	*Source*
$AgGaS_2$	$\bar{4}2m$	$d_{14} = d_{24} = d_{36}$	11.2	10.6 µm	a
		$d_{14} = d_{24} = d_{36}$	17.5	1064 nm	a
$AgGaSe_2$	$\bar{4}2m$	$d_{14} = d_{24} = d_{36}$	33	10.6 µm	a
BaB_2O_4 (BBO)	$3m$	d_{22}	2.3	1064 nm	a–f
		$d_{16} = d_{21} = -d_{22}$	−2.3	1064 nm	a
		$d_{15} = d_{31} = d_{24} = d_{32}$	0.04	1064 nm	d
		d_{33}	0.04	1064 nm	d
CdS	$6mm$	d_{33}	32	10.6 µm	a
		$d_{15} = d_{31} = d_{24} = d_{32}$	−16	10.6 µm	a
		d_{33}	19.1	1064 nm	e
		$d_{15} = d_{31}$	10.1	1064 nm	e
		$d_{24} = d_{32}$	10.7	1064 nm	e
CdSe	$6mm$	d_{33}	36	10.6 µm	a
		$d_{15} = d_{31} d_{24} = d_{32}$	−18	10.6 µm	a
CdTe	$\bar{4}3m$	$d_{14} = d_{24} = d_{36}$	109	1064 nm	e
		$d_{14} = d_{24} = d_{36}$	168	10.6 µm	c
$CsLiB_6O_{10}$	$\bar{4}2m$	$d_{14} = d_{24} = d_{36}$	0.74	1064 nm	f
GaAs	$\bar{4}3m$	$d_{14} = d_{24} = d_{36}$	83	10.6 µm	a
			170	1064 nm	e
GaP	$\bar{4}3m$	$d_{14} = d_{24} = d_{36}$	37	10.6 µm	a
			70.6	1064 nm	e
KD_2PO_4 (KD*P)	$\bar{4}2m$	d_{36}	0.37	1064 nm	a,b
KH_2PO_4 (KDP)	$\bar{4}2m$	d_{36}	0.39	1064 nm	a,b,e,g,h
$KNbO_3$	$mm2$	d_{33}	21.9	1064 nm	h
$Z = Z_L = x = l$		d_{15}	13	1064 nm	h
$X = Y_L = z = s$		d_{31}	12.4	1064 nm	h
$\mathrm{Y} = \mathrm{X_L} = -\mathrm{y} = \mathrm{m}$		d_{24}	9.2	1064 nm	h
		d_{32}	8.9	1064 nm	h
$KTiOAO_4$ (KTA)	$mm2$	$d_{15} = d_{31}$	4.2	1064 nm	e
$Z = Z_L = z = m$		d_{15}	2.91	2128 nm	g
$X = Y_L = -y = s$		$d_{24} = d_{32}$	2.8	1064 nm	e
$Y = X_L = x = l$		d_{33}	16.2	1064 nm	e
$KTiOPO_4$ (KTP)	$mm2$	d_{33}	14.6	1064 nm	e
$Z = Z_L = z = m$		d_{15}	3.7	1064 nm	e
$X = Y_L = -y = s$		d_{31}	3.7	1064 nm	e
$Y = X_L = x = l$		d_{24}	1.9	1064 nm	e
		d_{32}	2.2	1064 nm	e
LiB_3O_5 (LBO)	$mm2$	d_{33}	±0.04	1064 nm	a,b
$Z = Z_L = y = s$		$d_{15} = d_{31}$	±0.85	1064 nm	a,b
$X = Y_L = z = m$		d_{15}	1.04	1064 nm	g
$Y = X_L = x = l$		$d_{24} = d_{32}$	∓0.67	1064 nm	a,b
$LiIO_3$	6	d_{33}	4.5	1064 nm	a,b
		$d_{15} = d_{31}$	4.4	1064 nm	a,b
congruent	$3m$	d_{33}	−27.2	1064 nm	a,b
$LiNbO_3$		$d_{31} = d_{15} = d_{32} = d_{24}$	−4.35	1064 nm	a,b
		$d_{22} = -d_{21} = -d_{16}$	2.1	1064 nm	a,b

Table 3 (*Continued*)

Material	*Point group*	*Nonlinear optical coefficient (pm V^{-1})*		*Wavelength*	*Source*
Agreement of measurements of d_{31} by Maker fringe and wedge SHG (4.6 pm V^{-1}) and parametric fluorescence and parametric amplification (4.3 pm V^{-1})					
				1064 nm	[e]
5%MgO:LiNbO$_3$	3*m*	d_{33}	25	1064 nm	[e]
		d_{31}	4.4	1064 nm	[e]
LiTaO$_3$	3*m*	d_{33}	13.8	1064 nm	[e]
		d_{31}	0.85	1064 nm	[e]
NH$_4$H$_2$PO$_4$ (ADP)	$\bar{4}2m$	$d_{14} = d_{24} = d_{36}$	0.47	1064 nm	[a,e]
αSiO$_2$	32	d_{11}	0.3	1064 nm	
ZnGeP$_2$	$\bar{4}2m$	$d_{14} = d_{24} = d_{36}$	69	10.6 μm	[a,b]

[a] Roberts DA (1992) Simplified characterization of uniaxial and biaxial nonlinear optical crystals: a plea for standardization of nomenclature and conventions. *IEEE Journal of Quantum Electronics* 28: 2057–2074.

[b] Dmitriev VG (1997) *Handbook of Nonlinear Optical Crystals*, 2nd edn. Berlin: Springer-Verlag.

[c] Sutherland RL (2003) *Handbook of Nonlinear Optics*, 2nd edn, chs 4 and 5. New York: Marcel Dekker.

[d] Shoji I, Nakamura H, Ohdaira K, *et al.* (1999) Absolute measurement of second-order nonlinear-optical coefficients of β-BaB$_2$O$_4$ for visible to ultraviolet second-harmonic wavelengths. *Journal of the Optical Society of America B* 16: 620–624.

[e] Shoji I (1997) Absolute scale of second-order nonlinear-optical coefficients. *Journal of the Optical Society of America B* 14: 2268–2294.

[f] Shoji I, Nakamura H, Ito R, *et al.* (2001) Absolute measurement of second-order nonlinear-optical coefficients of CsLiB$_6$O$_{10}$ for visible-to-ultraviolet second-harmonic wavelengths. *Journal of the Optical Society of America B* 18: 302–307.

[g] Alford WJ and Smith AV (2001) Wavelength variation of the second-order nonlinear coefficients of KNbO$_3$, KTiOPO$_4$, KTiOAsO$_4$, LiNbO$_3$, LiIO$_3$, β-BaB$_2$O$_4$, KH$_2$PO$_4$, and LiB$_3$O$_5$ crystals, a test of Miller wavelength scaling. *Journal of the Optical Society of America B* 18: 524–533.

[h] Pack MV, Armstrong DJ and Smith AV (2003) Measurement of the $\chi^{(2)}$ tensor of the potassium niobate crystal. *Journal of the Optical Society of America B* 20: 2109–2116.



Figure 8 In the separated-beam wedge measurement technique, a fundamental beam of large transverse size generates harmonic radiation that is separated into a free harmonic wave and a driven harmonic wave after exiting the crystal.

$k_{2\omega}$ and a driven wave with propagation constant $2k_\omega$:

$$E_{2\omega}(z,t) = \frac{\omega d_{\text{eff}} E_\omega^2(0)}{n_{2\omega} c} \frac{1}{\Delta k}\{\exp i(k_{2\omega} z - 2\omega t) + c.c.\} - \frac{\omega d_{\text{eff}} E_\omega^2(0)}{n_{2\omega} c} \frac{1}{\Delta k}\{\exp i(2k_\omega z - 2\omega t) + c.c.\} \quad [19]$$

The two beams with different propagation constants are refracted at different angles at the wedged exit surface. The detailed analysis must include losses due to absorption and reflections at the surfaces and also nonlinear effects at the surfaces. Precision again is required in characterizing the fundamental beam and incident and generated intensities or energies as well as the geometry of the measurement. The large wedge eliminates problems of multiple reflections, and it is no longer necessary to carefully choose the beam spot size to fit within one fringe maximum, yet be large enough to allow use of the near field approximation. The accuracy of this measurement is demonstrated when the coefficients are expressed as Miller-delta values: $\delta_{24} = 0.153\,\text{pm V}^{-1}$, $\delta_{32} = 0.150\,\text{pm V}^{-1}$, $\delta_{15} = 0.195\,\text{pm V}^{-1}$, and $\delta_{31} = 0.192\,\text{pm V}^{-1}$. These values satisfy Kleinman symmetry, $\delta_{24} = \delta_{32}$ and $\delta_{15} = \delta_{31}$, well within the reproducibility of the measurement, which was about ±3%.

The nonlinear optical coefficients of BBO d_{22}(1064 nm) = 2.3 pm V^{-1} and KDP d_{36}(1064 nm) = 0.39 pm V^{-1} are gaining agreement from a number of independent measurements. The apparent disparity in the values for GaAs d_{36}(10.6 μm) = 83 pm V^{-1} and d_{36}(1064 nm) = 170 pm V^{-1}, is resolved when the coefficients are converted to Miller's delta values: $\delta_{36} = 0.089$ pm V^{-1} and $\delta_{36} = 0.086$ pm V^{-1}, respectively. The same thing can be done for GaP, for which d_{36}(10.6 μm) = 37 pm V^{-1} and d_{36}(1064 nm) = 70.6 pm V^{-1} convert to $\delta_{36} = 0.085$ pm V^{-1} and $\delta_{36} = 0.077$ pm V^{-1}, respectively. However, the older and newer values for other materials such as CdTe and CdS do not achieve this agreement. Other materials such as CLBO and LBO need additional investigation to resolve differences. The measurement of nonlinear optical coefficients is a continuing process.

Other techniques for measurement involving different nonlinear-optical processes are possible. Parametric amplification was mentioned above. Generally more complicated processes are less well suited for measurement of fundamental properties. Integrated-optical devices such as waveguides are even more complex. Often nonlinearity is measured in fractional conversion per unit of pump power to characterize overall device performance. There are survey techniques for evaluating materials such as grinding the material to a powder, illuminating with intense laser radiation, and looking for harmonic conversion. A surprising amount of information, such as a rough estimate of nonlinearity and the possibility of birefringent phase matching, can be gleaned by sorting the power and measuring the scattered harmonic radiation. Second-harmonic reflections from surfaces and thin film can be used in some instances. Electric fields can be use to orient molecules in polymers and solute molecules in solution to measure the hyperpolarizability of individual molecules.

Reporting Frames

Standardized axis specifications avoid confusion, but nonstandard axes can prove convenient in some applications provided care is used. The crystal $KNbO_3$ has *mm*2 point group; it could also be *m*2*m* or 2*mm* depending on the choice of axes to describe the crystal properties. The axis assignment for the orthorhombic class *mm*2, as it is used in Table 3, follows the IEEE/ANSI Std. 176-1987: Z is the polar axis, X is parallel to the shorter of the remaining unit cell dimensions, and Y is chosen to complete a right-handed coordinate frame. Polarity of the axes can be assigned by pyroelectric properties and piezoelectric properties of the crystal. The common assignments of the axes in the literature are given by X_L, Y_L, Z_L in the table. Reference to the biaxial indices of refraction are given by the lower case x, y, z with $n_x < n_y < n_z$. Finally the axes are identified by the unit cell dimensions $s < m < l$. Either a plus or minus rotation about the Y axis will bring the crystal into an *xyz* frame. However, a $+90$ degree rotation will give coefficients that are opposite in sign from a -90 degree rotation. The signs of the nonlinear optical coefficients are often not well determined because sign is not obtained from conversion efficiency in a single crystal. However, coefficient signs can be compared in the same crystal or between two crystals to determine if they are the same or opposite.

The crystals KTP or KTA are used here as an example. A 90° rotation about the Z-axis gives a new coordinate system $X'Y'Z'$ aligned with the *xyz* frame determined by the indices of refraction. In the new frame, the component of the nonlinear optical tensor, in terms of the standard frame, are $d_{zxx} = d_{32}$ and $d_{zyy} = d_{31}$. All that is needed here is to exchange d_{32} and d_{31} to change the standard frame to the one commonly used in the literature, X_L, Y_L, Z_L. When the largest index of refraction is not aligned with the polar axis, as is the case for LBO and $KNbO_3$, the specification of tensor components can become confusing if a standard frame is not used.

Often crystallographers and crystal manufacturers can identify axes by surface morphology or by poling processes of ferroelectric crystals. With other crystal symmetries a change in the reporting frame that does not change linear optical properties may change the sign of some of the nonlinear optical tensor components while leaving others unchanged. For a crystal of *3m* point group, a 180° rotation about Z will change the sign of d_{22}, d_{21}, and d_{16} and leave the other coefficients unchanged. The *xyz* frame with $n_x < n_y < n_z$ is convenient for calculations of optical propagation, and the standard *XYZ* frame is unambiguous for reporting of tensor properties.

Conclusion

There is still a range of values for nonlinear optical coefficients of many materials. Standardization is evolving on more commonly used materials. Greater precision in measurement and extension of measurement techniques are providing better accuracy. However, caution is still required when accessing values. It is necessary to scrutinize the sources of values to obtain the highest accuracy. Accurate measurements need to be extended to difficult spectral ranges of the ultraviolet and infrared. The ambiguity of the sign of tensor components needs to be resolved. In recent measurements, carefully executed wedge measurements are producing more reliable results. The separated beam wedge technique appears to be particularly promising. Phase-matched second-harmonic generation and other practical applications of nonlinear optical materials will continue to serve as techniques to verify accuracy. Current analytical and numerical techniques provide a method for precise modeling of nonlinear optical processes and the need for more accurate material characterization.

See also

Fiber and Guided Wave Optics: Nonlinear Optics. **Nonlinear Optics, Basics:** $\chi^{(2)}$-Harmonic Generation.

Further Reading

Alford WJ and Smith AV (2001) Wavelength variation of the second-order nonlinear coefficients of $KNbO_3$, $KTiOPO_4$, $KTiOAsO_4$, $LiNbO_3$, $LiIO_3$, β-BaB_2O_4, KH_2PO_4, and LiB_3O_5 crystals, a test of Miller wavelength scaling. *Journal of the Optical Society of America B* 18: 524–533.

Dmitriev VG (1997) *Handbook of Nonlinear Optical Crystals*, 2nd edn. Berlin: Springer-Verlag.

Gehr RJ (1998) Separated-beam non-phase-matched second-harmonic method of characterizing nonlinear optical crystals. *Journal of the Optical Society of America B* 15: 2109–2116.

Kurtz SK (1975) Measurement of nonlinear optical susceptibilities. In: Rabin H and Tang CL (eds) *Quantum Electronics: A Treatise, vol. 1, part A*, pp. 209–281. New York: Academic Press.

Pack MV (2003) Measurement of the $\chi^{(2)}$ tensor of the potassium niobate crystal. *Journal of the Optical Society of America B* 20: 2109–2116.

Roberts DA (1992) Simplified characterization of uniaxial and biaxial nonlinear optical crystals: a plea for standardization of nomenclature and conventions. *IEEE Journal of Quantum Electronics* 28: 2057–2074.

Shoji I (1997) Absolute scale of second-order nonlinear-optical coefficients. *Journal of the Optical Society of America B* 14: 2268–2294.

SNLO nonlinear optics code available from Smith AV Sandia National Laboratories, Albuquerque, NM 87185-1423. (an Internet publication) http://www.sandia.gov/imrl/XWEB1128/xxtal.htm.

Sutherland RL (2003) *Handbook of Nonlinear Optics*, 2nd edn, chs 4 and 5. New York: Marcel Dekker.

$\chi^{(3)}$

P P Banerjee, University of Dayton, Dayton, OH, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Over the past 30 years, several methods have been used to measure and characterize optical nonlinearities. With increasing interest in nonlinear optics beyond the traditional harmonic generation, third-order nonlinear processes have been shown to be responsible for self-focusing and defocusing of optical beams, phase conjugation, optical bistability, etc. Third-order nonlinear processes in Kerr materials arise from the cubic dependence of the polarization $P = P^L + P^{NL}$, $P^{NL} = \chi^{(3)} \vdots E \cdot E \cdot E$ in a material on the optical field E, through the nonlinear susceptibility tensor $\chi^{(3)}$. The cubic nonlinearity in turn results in a nonlinear refractive index coefficient n_2 defined through:

$$n = n_0 + n_2 |E_p^{\omega_0}|^2 \tag{1}$$

where $E_p^{\omega_0}$ is the phasor part of $E : E = Re[E_p^{\omega_0} \exp \times \mathrm{j}\omega_0 t]$. The relation between $\chi^{(3)}$ and n_2 can be expressed as:

$$n_2 = (3/8n_0)\chi^{(3)}_{1111}(-\omega_0; \omega_0, \omega_0, -\omega_0) \tag{2}$$

In some materials, an effective $\chi^{(3)}$ or an effective n_2 can be defined as well. For instance, in a second-order nonlinear material, an effective $\chi^{(3)}$ is established through cascading of $\chi^{(2)}$s, and in the presence of phase mismatch between the fundamental and the second harmonic. In other materials, such as liquid crystals, an effective n_2 can be defined due to the nonlinear dependence of the reorientation of the director axis on the optical field. In photorefractive materials, the induced nonlinearity stems from the nonlinear dependence of the induced space charge distribution in the material on the optical field. Some of the techniques used to measure the third-order nonlinearity in materials include degenerate four-wave mixing (DFWM) or phase conjugation, interferometry, ellipse rotation, and beam self-refraction and/or distortion and bending.

For instance, in DFWM, two contradirectional propagating pumps and the probe beam having the same frequency ω_0 interact to give rise to the conjugate, whose amplitude depends on the magnitude of the cubic nonlinearity coefficient. The conservation of energy and momentum describes a parametric interaction of the form $\omega_0 + \omega_0 - \omega_0 \rightarrow \omega_0$ (in frequency space) and, $\mathbf{k}_{\text{probe}} + \mathbf{k}_{\text{pump1}} - \mathbf{k}_{\text{pump2}} \rightarrow \mathbf{k}_{\text{conj}}$ (in $\mathbf{k}$-space). The conjugate beam is clearly distinguishable by its spatial separation from the other interacting waves. However, alignment of the three waves is critical to obtain a good phase conjugate; furthermore, the sign of the nonlinearity cannot be determined.

In the interferometric method, a laser beam is split into two parts, one serving as the reference, and the other being incident on the nonlinear sample. As in the case of interferometers, if the two beams are then recombined and introduced through a lens, an interference pattern forms at the focal plane of the lens. While the information about the magnitude of the nonlinearity can be found from the fringes and their change when the incident power is varied, information of the sign of the nonlinearity is still not readily inferable.

In this article, we will concentrate on self-refraction, particularly in light of the fact that it results in a sensitive and at the same time simple method called the *z*-scan©, requiring the propagation of a single beam through the nonlinear sample. We comment that self-diffraction does also cause self-bending of an asymmetric beam due to the asymmetric phase change induced through the cubic nonlinearity; however, extracting the information of the sign and magnitude of the nonlinearity can be effectively done only if the sample is thin, implying that there is negligible linear diffraction of the beam as it passes through the sample. In the rest of the article, we will therefore concentrate on the *z*-scan method, since it is an elegant and simple single (symmetrical) beam technique that yields information on the magnitude and sign of the cubic nonlinearity, as well as its real and imaginary parts. We will describe in detail how the *z*-scan can measure the real part of the cubic nonlinearity, for both thin and thick samples, as well as showing its application in determining the reorientational nonlinearity of liquid crystals and the nonlinearity of photorefractive materials, where photovoltaic effect and diffusion of charge carriers contribute to the effective nonlinearity.

Since the mid-1990s *z*-scan has evolved as a standard method for determining effective nonlinear refractive index coefficients of nonlinear materials. The name *z*-scan is derived from the fact that the nonlinear test sample is scanned along the direction of propagation (z) of a beam about the back focal plane of an external lens illuminated by an incident Gaussian beam from a laser. The far-field diffraction pattern yields information about the nonlinearity of the test material. The *z*-scan technique has been used to measure and characterize the nonlinear refractive index coefficient and nonlinear absorption coefficient in materials such as CS_2, ZnSe, Cs atoms, multiphoton absorption in GaN, organic dyes, thermal nonlinearities in liquids, liquid crystals, photorefractive materials, etc., to name a few. *z*-scan measurements have been made using non-Gaussian incident beams, and *z*-scans have been performed using both CW and pulsed laser sources.

The first extensive series of work on the *z*-scan technique, including analysis and application to the measurement of the cubic nonlinearity, was performed by the group of Van Stryland at the Center of Electro-Optics and Lasers (CREOL) at the University of Central Florida. Other investigators later performed similar measurements and characterization during the study of nonlinear optical properties of a solution of chlorophyll in acetone, and Chinese tea.

Theory of the Thin Sample *z*-Scan

We will first analyze propagation of a (circularly symmetric) Gaussian beam which is initially focused by an external lens and is then incident on a 'thin' slice of a cubically nonlinear Kerr medium. This case is important because, as explained below, it provides a basis for the measurement of the nonlinear refractive index coefficient n_2.

Figure 1 shows a simple ray diagram to demonstrate what happens if the cubically nonlinear material is thin. The propagating Gaussian beam induces its own lens, which is positive for a material having a positive n_2, for reasons that will become clear to the reader later on in this section. Note that if the position of the induced lens is at the back focal plane of the external lens, the former does not affect the propagation of the beam behind the nonlinear material. The situation is thus the same as the propagation of the externally focused Gaussian beam in a linear diffraction-limited environment. However, if the separation between the external lens and the sample is less than the focal length f of the external lens, the beam in the far field is wider than the linear diffraction-limited case. Conversely, if the lens-sample separation is larger than f, the beam width is smaller. This is the basis of the *z*-scan: for a material with a positive n_2, the scanning of a thin nonlinear sample through the back focal plane of the external lens, starting from a position to the left of the focus, yields far-field profiles which are initially larger and eventually smaller than the width in the linear diffraction-limited case. The opposite is true for materials with a negative n_2. For very large displacements of the sample from the back focal plane of the



Figure 1 Geometrical optics picture of *z*-scan setup for nonlinear refractive index n_2. Reproduced with permission from Banerjee PP (2004) *Nonlinear Optics: Theory, Numerical Modeling, and Applications.* New York: Marcel Dekker.

external lens, the beam power is small enough that nonlinear lensing is negligible, and hence the beam widths return to the linear diffraction-limited case. The variation of the on-axis intensity or transmittance as a function of scan distance is complementary to the variation of the width, due to conservation of power, to be explained further below. A sketch of the on-axis transmittance during a z-scan for a positive n_2 material, is shown in Figure 2.

The simpler ray picture described above can be augmented by using a q parameter approach to Gaussian beam propagation. For the sake of simplicity, we prefer to introduce the q parameter approach here, instead of the more rigorous Gaussian decomposition of the induced phase as computed by Van Stryland's group. The q of a Gaussian beam in air is defined through the relation $1/q = 1/R - \mathrm{i}(2/k_0 w^2)$, where R and w denote the radius of curvature and the beamwidth, respectively, and k_0 is the propagation constant in air. Assume a Gaussian beam with a waist w_0 (implying initially planewave fronts) incident on the external lens. The Gaussian can be described by $q = q_0 = \mathrm{i}z_{R0}$, where $z_{R0} = k_0 w_0^2/2$ is called the Rayleigh length of the incident Gaussian. The laws of q transformation of a Gaussian beam are:

(i) for translation through a distance d, the q changes to $q + d$; and
(ii) for a Gaussian with q-parameter q incident on a lens, the q immediately behind the lens, is given by $(1/q - 1/f)^{-1}$.



Figure 2 Typical z-scan plots for positive (top) and negative (bottom) cubic nonlinearities. The vertical axis is in arbitrary units.

Using these laws, the $q = q_{\mathrm{obs}}$ of the Gaussian at a distance d from the nonlinearly induced lens of the focal length f_{ind}, which is located at a distance $s = f + \Delta s$ behind the external lens, can be found as:

$$q_{\mathrm{obs}} = \frac{f_{\mathrm{ind}}[q_0 f + (f - q_0)(f + \Delta)]}{f_{\mathrm{ind}}(f - q_0) - [q_0 f + (f - q_0)s]} + d \qquad [3]$$

In deriving eqn [3], we have used the laws of q transformation on the initial Gaussian beam of q-parameter q_0 passing through the external lens, being translated a distance $f + \Delta s$, passing through the induced lens, and finally being translated a distance d to the observation plane.

To determine $f_{\mathrm{ind}}(\Delta s)$, assume a Gaussian of the form:

$$|E_{\mathrm{p}}^{\omega_0}(x, y, z)| = E(z)\exp(-(x^2 + y^2)/w^2(z)) \qquad [4]$$

Since

$$n = n_0 + n_2|E_{\mathrm{p}}^{\omega_0}|^2 \approx n_0 - 2n_2E^2(z)(x^2 + y^2)/w^2(z) \qquad [5]$$

the nonlinearly induced phase change is

$$\Delta\phi = k_0 n\Delta z \approx k_0[n_0 - 2n_2E^2(z)(x^2 + y^2)/w^2(z)]\Delta z \qquad [6]$$

so that

$$f_{\mathrm{ind}}(z) = n_0 w^2(z)/4n_2 a^2(z)\Delta z \qquad [7]$$

Note that $f_{\mathrm{ind}}(z)$ is inversely proportional to $n_2E^2(z)$ and Δz. The longer the sample length, the more the nonlinear induced phase, implying a stronger lensing (smaller f_{ind}). Also, the stronger the nonlinearity parameter n_2 and/or on-axis intensity ($E^2(z)$), the stronger the focusing since the change in n is larger.

We must point out that the focal length f_{ind} of the induced lens is also a function of Δs, since it depends on the beam intensity at the location of the nonlinear sample. In fact, the focal length f_{ind} of the nonlinearly induced lens can be expressed in terms of the beam power P, the beam width w at the position Δs, f (the focal length of the external lens), the linear refractive index n_0, the nonlinear refractive index coefficient n_2 defined through eqn [1] where $|E_{\mathrm{p}}^{\omega_0}| = E$ is the optical field in the nonlinear material of length L, assumed 'thin' for now. The term 'thin' means that the sample length is smaller than the depth of focus of the externally focused Gaussian beam. In this case, we can assume that the beam width is a constant through the sample, and the induced focal length is then only directly dependent on the total thickness L of the sample. The focal length of a nonlinearly induced 'thin' Kerr lens can be written as

$$f_{\text{ind}}(\Delta s) = \frac{n_0 w^2(\Delta s)}{4n_2|E|^2 L} \approx \frac{\pi f^4 n_0}{k_0^4 w_0^4 \eta_0 P L n_2} \tag{8}$$

for small Δs, where η_0 is the (linear) characteristic impedance of the nonlinear medium. Note that in eqn [8], the beam width w is given by

$$w^2(\Delta s) = w_{\text{f}}^2\left[1 + \frac{4(\Delta s)^2}{k_0 w_{\text{f}}^4}\right] \text{ and } w_{\text{f}} \cong \frac{2f}{k_0 w_0} \tag{9}$$

In eqn [9], w_{f} denotes the waist size of the Gaussian beam at the back focal plane of the external lens. In deriving eqn [8], one has to use the power conservation relation $|E|^2 w^2 = (4/\pi)\eta P$ to re-express the dependence of the induced focal length on the field amplitude in terms of the corresponding width at the same point.

Our final interest is to find the imaginary part of $1/q_{\text{obs}}(= -2/k_0 w_{\text{obs}}^2)$, in order to ascertain the width w_{obs} of the Gaussian beam on the observation plane. Simple but tedious algebra leads us to the relation:

$$\frac{k_0 w_{\text{obs}}^2}{2} = \frac{[(ff_{\text{ind}}d - f^2 d + f^2 f_{\text{ind}}) + f(f_{\text{ind}} - d)\Delta s]^2 + z_{R0}^2[(f_{\text{ind}} - d)\Delta s + f_{\text{ind}} d]^2}{z_{R0} f^2 f_{\text{ind}}^2} \tag{10}$$

It can be shown simply that when $\Delta s = 0$, and for $|f_{\text{ind}}| \gg f$, $w_{\text{obs}} = w_0 d/f$ for large d. In other words, in the linear case, i.e., when $f_{\text{ind}} = \infty$, as well as in the nonlinear case when $\Delta s = 0$, the far-field width of the Gaussian beam is what is predicted by geometrical optics. Furthermore, from eqn [10], the rate of change of the width with Δs around $\Delta s = 0$, (assuming $z_{R0} \gg f$, and for large d) can be found as

$$\frac{\mathrm{d}w_{\text{obs}}}{\mathrm{d}\Delta s} = \frac{-2d^2 z_{R0}}{k_0 w_{\text{obs}} f^2 f_{\text{ind}}} = -\frac{w_0 d}{f f_{\text{ind}}} \tag{11}$$

provided we invoke the relation for w_{obs} derived above. In eqn [11], f_{ind} refers to the value of the induced focal length (eqn [8]) with $\Delta s = 0$. Equation [11] may be written as

$$\frac{\mathrm{d}w_{\text{obs}}}{\mathrm{d}\Delta s} = -\frac{k_0^4 w_0^5 P L n_2}{2\pi n_0 f^5} \tag{12}$$

This means that in a material with a positive (negative) n_2, implying a positive (negative) induced lens, the rate of change of the observed width with the position of the nonlinear sample about the focal plane of the external lens will be negative (positive), in agreement with the results from geometrical optics. Furthermore, the rate of change is proportional to the angle of convergence w_0/f of the externally focused Gaussian, and to the position d of the observation plane.

In z-scan, it is often important to relate the on-axis transmittance in the far field to the scan distance s for measurement purposes. Since for power conservation, the intensity is inversely proportional to the width of the beam in the far field, a positive n_2 would imply a positive slope as a function of scan distance with increasing s, and a negative slope for negative n_2. The value of the slope of the on-axis transmittance could give the information of the n_2 of the material. Note that the z-scan graph in this case is an odd function of the scan distance, measured about the back focal plane of the external lens.

In practice, a detector with a finite aperture area is placed on-axis, and the detected power monitored as a function of scan distance. The transmitted power through the aperture is obtained by

$$\begin{aligned} P_{\text{T}} &= \frac{1}{2}\int_0^{2\pi}\int_0^{r_{\text{a}}} \frac{E_{\text{a}} E_{\text{a}}^*}{\eta_0}\,\mathrm{d}A \\ &= \frac{\pi w_0}{2}\left(\frac{E_0^2}{2\eta_0}\right)\left(1 - \exp\left(-\frac{2r_{\text{a}}^2}{w_{\text{obs}}^2}\right)\right) \\ &= P\left(1 - \exp\left(-\frac{2r_{\text{a}}^2}{w_{\text{obs}}^2}\right)\right) \end{aligned} \tag{13}$$

where r_{a} is the radius of aperture. The rate of change of P_{T} with Δs can be found as

$$\frac{\mathrm{d}P_{\text{T}}}{\mathrm{d}\Delta s} = \frac{-4r_{\text{a}}^2 P}{w_{\text{obs}}^3}\exp\left(-\frac{2r_{\text{a}}^2}{w_{\text{obs}}^2}\right)\frac{\mathrm{d}w_{\text{obs}}}{\mathrm{d}\Delta s} \tag{14}$$

Substituting eqn [12] into eqn [14] and using the approximation $w_{\text{obs}} = w_0 d/f$, eqn [14] can be rewritten as

$$\frac{\mathrm{d}P_{\text{T}}}{\mathrm{d}\Delta s} \cong \frac{4r_{\text{a}}^2 f^2 P}{f_{\text{ind}} d^2 w_0^2}\exp\left(-\frac{2r_{\text{a}}^2 f^2}{d^2 w_0^2}\right) \tag{15}$$

from which

$$\frac{\mathrm{d}P_{\text{T}}}{\mathrm{d}\Delta s}(\Delta s \approx 0) \cong \frac{4k_0^4 w_0^2 \eta_0 r_{\text{a}}^2 P^2 L}{\pi f^2 d^2 n_0}\exp\left(-\frac{2r_{\text{a}}^2 f^2}{d^2 w_0^2}\right) n_2 \tag{16}$$

When r_a approaches 0;

$$\frac{dP_T}{d\Delta s}(\Delta s \approx 0) = 4\left(\frac{k_0^2 w_0 r_a P}{fd}\right)^2 \frac{\eta_0 L}{\pi n_0} n_2 \qquad [17]$$

Therefore, n_2 can be estimated as

$$n_2 = \left(\frac{\pi n_0}{\eta_0 L}\right)\left(\frac{d}{2k_0^2 w_0 P}\right)^2 \left(\frac{f}{r_a}\right)^2 \frac{dP_T}{d\Delta s} \qquad [18]$$

Thus, if one knows the slope of the z-scan graph around $\Delta s \approx 0$, the value of n_2 can be found. Another way to state this result is to say that the n_2 is related to the peak-to-valley change in the on-axis transmittance ΔT_{p-v}, which is proportional to $dP_T/d\Delta s$.

In passing, we comment that the z-scan method can be also adapted to determine the nonlinear absorption coefficient α_2 of a material, defined through the relation $\alpha = \alpha_0 + \alpha_2 I$, where α is the total absorption coefficient and I denotes the intensity. In order to achieve this, the aperture is assumed to be completely open, in order to collect all the light behind the nonlinear absorptive sample. For $\alpha_2 > 0$, maximum absorption is experienced when the nonlinear sample, assumed thin, is at the back focal plane of the lens since the optical intensity is a maximum due to the external focusing. The z-scan graph is an even function of scan distance, measured about the back focal plane of the external lens.

Thick Sample *z*-Scan

Contrary to the thin sample case, a thick sample is defined as one whose thickness may be comparable to the depth of focus of the externally focused Gaussian beam. In this case, the beamwidth changes during propagation through the sample, so that the induced focal length also changes with propagation. This makes the problem substantially more involved. Indeed, to track the far-field profile in this case, one needs to describe the propagation of the Gaussian beam inside the nonlinear sample using the q parameter formalism. Since both the width and the radius of curvature of the beam at the exit face of the sample are required to predict the far-field behavior, one can write a simple differential equation describing the variation of the q through the nonlinear sample. This equation can be composed from the laws of q-transformation described earlier, and the effects of propagation and nonlinear lensing can be added assuming each is small over an infinitesimal distance of propagation, much like the numerical method called the split step beam propagation method (BPM), often used to analyze such problems. We will not present details of the computation, rather show calculation results for a typical thick sample case, and point out differences with the thin sample predictions for z-scan.



Figure 3 Plot of width of the beam in the far field as a function of the scan distance s. The light wavelength is 640 nm. Reproduced with permission from Banerjee PP (2004) *Nonlinear Optics: Theory, Numerical Modeling, and Applications.* New York: Marcel Dekker.

Figure 3 shows the beamwidth as a function of scan distance for the case where the observation plane is at a distance $d = 1$ m from the exit face of a 1 cm thick. Assume that a hypothetical sample with $n_0 = 1$, $n_2 = \pm 10^{-15}$ m^2/V^2 is scanned about the back focal plane of an external lens with focal length $f = 5$ cm. For comparison, the case of a linear sample is also superposed on the same graph. Note that with the variation of s, the far-field width initially increases, and then decreases before starting to increase again, for a material with a positive n_2. Note that around the point where the variations intersect the graph for the linear case, the slope of the curves are negative and positive for materials with positive and negative n_2, respectively. The graphs for the variation of on-axis transmittance are opposite to the variation of the widths, as mentioned earlier. This is also in agreement with the results predicted from geometrical optics and the q formalism for a thin sample, described earlier.

How do thick and thin sample z-scans differ? Important differences are: (i) the position of the points where the graphs for positive and negative, n_2s, intersect the graph for the linear case; and (ii) the slope of the graphs, predicted from thin and thick sample calculations. For instance, for the thin sample approximation, the value of the slope around $s = f$ is about -4 for a material with a $n_2 = 10^{-15}$ m^2/V^2. Recall from the previous section, the z-scan plot for a thin sample always intersects the graph for the linear case at the back focus of the external lens, and therefore, it is easy to determine the slope of the z-scan at this point. From the graph in the thick sample case, it is perhaps difficult to ascertain at exactly which point one must determine the slope. A figure of merit would be the minimum value, which occurs for a value of s slightly smaller than $f = 5$ cm. A conservative estimate yields a slope of approximately -1 for this particular example. Note, however, that in the thick lens analysis, we have taken a paraxial approximation to the Gaussian at every stage of its propagation through the nonlinear sample. Strictly speaking, this is not true, and to alleviate this problem, Van Stryland's group included a correction factor with the width of the Gaussian beam.

We would like to mention that values of $n_2 \approx -10^{-15}$ m^2/V^2 can indeed be measured for thermal nonlinearities in liquids. In fact, this is a typical value that we measured for our solution of chlorophyll in ethanol during our first experiments on z-scan. Values of effective $n_2 \approx 10^{-14}$ m^2/V^2 can be measured for liquid crystals with orientational nonlinearities, and will be described below.



Figure 4 z-scan simulation results for $f = 50.2$ mm and $V/V_o = 1.01, 1.1, 1.2, 1.3, 1.4$ with $E_{op} = 2 \times 10^5$ V/m. z-scan simulation results for $f = 50.2$ mm and $V/V_o = 1.4, 1.8, 2.2, 2.6, 4$ with $E_{op} = 2 \times 10^5$ V/m. Reproduced with permission from Banerjee PP (2004) *Nonlinear Optics: Theory, Numerical Modeling, and Applications.* New York: Marcel Dekker.

Example of *z*-Scan: Effective Cubic Nonlinearity of Liquid Crystals

The induced refractive index in a nematic liquid crystal, due to reorientational nonlinearity, is a function of position in the crystal and depends on the intensity of the incident optical plane wave, its angle with respect to the direction of propagation, and on the applied voltage. Because of the fact that the nonlinearity depends on the direction of propagation of the planewave and the director axis of the crystal, modeling Gaussian beam propagation is rather complicated. Moreover, the director axis has a certain distribution in the material due to the applied voltage, and hence, the electrostatic field in the material, as well as the optical field. This poses a level of complexity a degree higher than that discussed above for the simple thick sample case. Since the induced refractive index is not a constant, and more importantly, a function of the spatial frequency of the optical beam (which determines the angle between a planewave component of the Gaussian beam spectrum and the director axis distribution under external field), one is compelled to analyze optical propagation using split-step BPM. A typical set of simulated z-scan plots is shown in Figure 4, assuming one transverse dimension for simplicity, and the same parameters as in the experiment described below. Actual experimental results from a z-scan of a biased liquid crystal sample is shown in Figure 5 for transmitted power versus sample position in a z-scan experiment for a liquid crystal sample for applied voltages 0.8, 1.0, 1.2, 1.8, and 2.2 V. In this case, the focal length of the external lens is approximately 50 mm and aperture diameter on the observation plane is 1 mm. The scan range is 0.15 inches or approximately 4 mm. The scan step, ΔZ, is varied from about 0.002 inches to about 0.01 inch, depending on the position of the sample. This is done so as to get the maximum information around the back focal plane of the external lens where the measurement values are to be used to find the slope of the z-scan graph, and hence the effective nonlinear refractive index coefficient.

The plots of the effective $n_2 = n_{2\text{eff}}$ (simulated and measured) are shown in Figure 6a and b, respectively. As seen from both plots, the $n_{2\text{eff}}$ increases and



Figure 5 Measured *z*-scan graph for *f* = 50.2 mm and aperture diameter = 1 mm. Reproduced with permission from Banerjee PP (2004) *Nonlinear Optics: Theory, Numerical Modeling, and Applications.* New York: Marcel Dekker.

reaches a maximum at $V/V_o = 1.4$, before starting to decrease. Simulated and experimental $n_{2\text{eff}}$ have similar trends. Furthermore, there is reasonable agreement between the calculated and measured values of $n_{2\text{eff}}$.

Discussion: Effective n_2 of Other Materials

The *z*-scan is a powerful tool in the measurement and characterization of effective cubic nonlinearities of different materials. The method is simple and easy to set up, and can be readily automated. We provide two other examples of *z*-scans below, as examples. For instance, photorefractive materials are commonly used for dynamic holography, in order to record and reconstruct volume holograms. Photorefractive materials are doped light-sensitive electro-optic materials in which optical radiation creates mobile charge carriers which redistribute themselves to create an induced space-charge field. This electrostatic field in turn modulates the refractive index which phase modulates the optical beam. A figure of merit for the effectiveness of such a material, e.g., lithium niobate, for holographic storage, is the donor to acceptor ratio in such materials. It turns out that this ratio, along with the photovoltaic coefficient, can be related to an effective n_2 in lithium niobate. This is also responsible in producing an elliptic beam in the far field by starting out from a circularly symmetric Gaussian beam focused onto the sample. The ellipticity stems from the tensor nature of the electro-optic coefficients. Typical simulated *z*-scan plots for lithium niobate are shown in Figure 7, and carries the signature variation of the scan in the variation of the beam ellipticity with scan distance. From this plot, we are able to determine the effective n_2 and hence, the donor to acceptor concentration ratio.

In other photorefractive materials, such as barium titanate, in which diffusion of charge carriers plays a dominant effect, the induced change in the refractive index is proportional to the gradient of the intensity, rather than the intensity itself, as was the case in all previous examples. In this case, as seen in Figure 8, it can be shown that the *z*-scan plot for on-axis transmittance with a small finite aperture on the observation plane is an even function of scan distance. This, however, should not be confused with the open aperture *z*-scan that is also even, but which yields information of the nonlinear absorption coefficient, as described earlier. Experiments with a new material, manganese aluminum oxide, which is thought to have both photovoltaic and diffusive contribution to space charge field distribution, yields a *z*-scan that has both odd and even components. Through careful analysis of the *z*-scan results, one is able to determine the relative contributions of each of these effects. Care should be taken in the interpretation of the results in this case, since in an actual experiment, the aperture size cannot be infinitely small, and thus, an optimum aperture size must be determined that allows for sufficient detected power,



Figure 6 (a) Calculated $n_{2\text{eff}}$ for $f = 50.2$ mm with $E_{\text{op}} = 2 \times 10^5$ V/m; (b) Experimental $n_{2\text{eff}}$ for $f = 50.2$ mm with aperture diameter = 1 mm. Reproduced with permission from Banerjee PP (2004) *Nonlinear Optics: Theory, Numerical Modeling, and Applications.* New York: Marcel Dekker.



Figure 7 Typical simulated *z*-scan plot showing variation of beam ellipticity as a function of scan length. Reproduced with permission from Banerjee PP (2004) *Nonlinear Optics: Theory, Numerical Modeling, and Applications.* New York: Marcel Dekker.



Figure 8 Typical *z*-scan plots of a diffusion dominated photorefractive material, with $\Delta n = C\nabla I$. Different values of *C* are written on the graph.

but at the same time allows one to neglect any effects of nonlinear absorption.

In summary, it is hoped that this article illuminates readers on the history of the *z*-scan, its application to thin and thick samples, its effectiveness in measurement and characterization of effective third-order optical nonlinearities for a wide class of nonlinear materials, such as $\chi^{(3)}$ materials, materials with cascaded second-order nonlinearities, liquid crystals, photorefractives, etc., and its potential for automation, while at the same time pointing out areas where care should be taken in the interpretation of the measured data. With appropriate modification in the theory, it can also be applied to characterization of linear lenses, possibly voltage controllable lenses and lenslet arrays, suitable for dynamic imaging in biomedical applications.

See also

Materials for Nonlinear Optics: Liquid Crystals for NLO. **Nonlinear Optics, Basics:** Four-Wave Mixing; $\chi^{(3)}$–Third-Harmonic Generation.

Further Reading

Banerjee PP (2004) *Nonlinear Optics: Theory, Numerical Modeling, and Applications*. New York: Marcel Dekker.

Banerjee PP, Danilieko A, Hudson T and McMillen D (1998) P-scan analysis of induced inhomogeneous optical linearities. *Journal of the Optical Society of America* 15: 2446.

Banerjee PP, Misra RM and Maghraoui M (1991) Theoretical and experimental studies of propagation of beams through a finite sample of a cubically nonlinear material. *Journal of the Optical Society of America* 8: 1072.

Boyd R (2002) *Nonlinear Optics*, 2nd edn. New York: Academic Press.

Butcher P and Cotter D (1990) *The Elements of Nonlinear Optics*. New York: Cambridge University Press.

Chapple PB, Staromlynska J and McDuff RG (1994) *Z*-scan studies in the thin- and the thick-sample limits. *Journal of the Optical Society of America B* 11: 975.

Noginov M, Helzer SW, Loutts GB, Banerjee PP, Morrisey M and Kim Y (2003) Study of photorefraction response and diffraction efficiency in Mn:YalO$_3$ crystals. *Journal of the Optical Society of America B* 20: 1233.

Sheik-Bahae M, Said AA and Van Stryland EW (1989) High-sensitivity, single beam n_2 measurements. *Optics Letters* 14: 955.

Sheik-Bahae M, Said AA, Wei TH, Hagan DJ and Van Stryland EW (1990) Sensitive measurement of optical nonlinearities using a single beam. *IEEE Journal of Quantum Electronics* 26: 760.

Sutherland RL (1996) *Handbook of Nonlinear Optics*. New York: Marcel Dekker.

Yeh P (1993) *Introduction to Photorefractive Nonlinear Optics*. New York: Wiley.

MATERIALS FOR NONLINEAR OPTICS

Contents

Liquid Crystals for NLO
Organic Nonlinear Materials

Liquid Crystals for NLO

I C Khoo, Pennsylvania State University, University Park, PA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Liquid crystals are complex organic molecular systems that exhibit various mesophases characterized by the degree of order. In this review, we shall focus mainly on thermotropic liquid crystals which exhibit various mesophases in the temperature range between the crystalline and the isotropic liquid states. In particular, we shall discuss the extraordinarily large optical nonlinearities of nematic liquid crystals, as well as the electronic nonlinearities of isotropic-phase liquid crystals. Recent studies have shown that these materials are promising candidates for advanced photonic applications.

Nematic liquid crystals (NLC) possess directional ordering, i.e., when placed in thin cells with surface



Figure 1 Nematic liquid crystals (NLC) which exhibit directional ordering characterized by the director axis. The lower figure shows how the NLC molecules are aligned in a typical cell with surfactant coated windows.

treated boundaries, the NLC molecules will self-assemble into a birefringent crystal characterized by a so-called director axis $\hat{n}$, cf. Figure 1. For light polarized parallel to $\hat{n}$, the refractive index is n_e, while for light polarized perpendicular to $\hat{n}$, the refractive index is n_0. Typically n_e is ~1.7 and n_0 is ~1.5. This large birefringence $\Delta n = n_e - n_0$ of NLC holds throughout the near UV to the far infrared spectral regime, cf. Figure 2. Perhaps the most important characteristics of NLCs is the easy susceptibility of the birefringent director (crystalline) axis orientation to externally applied fields, which has led to their ever increasing widespread use in various opto-electronics information and image display and processing devices. In analogy to dc and ac field effects, the director can easily be reoriented by an optical field, and thus cause a large optically induced index of refraction change. By doping the NLC with photosensitive or photo-charge producing agents, this process of refractive index change can be enhanced considerably. The refractive indices of NLC are also very strongly temperature dependent.



Figure 2 Broadband birefringence of nematic liquid crystals from the near ultraviolet to far infrared.

Accordingly, a large refractive index change can also be generated with laser absorption induced density and order parameter changes. In the following sections, we will broadly classify these nonlinear optical processes originating from the collective response of NLC to external fields as *nonelectronic nonlinearities*.

On the other hand, individual NLC molecules also respond to an optical field through the electronic dipolar interaction. A typical electronic energy level structure of liquid crystal molecules is shown in Figure 3. The dipolar interaction gives rise to the usual nonlinear polarization characterized by the second, third and higher-order nonlinear susceptibilities $\chi^{(2)}, \chi^{(3)}, \ldots$ etc. The complex imaginary parts of these linear and nonlinear susceptibilities account for the photonic absorption processes. Most liquid crystalline molecules possess small linear absorption in the visible region (400–700 nm), and begin to absorb near the UV region (<350 nm), cf. Figure 4. This absorption spectrum translates into a (usually) large nonlinear two-photon absorption spectrum in the visible. In some organic molecules, the intermediate absorption cross-section σ_i or the excited state absorption cross-section σ_e is much larger than the ground state linear absorption σ_g, giving rise to reverse saturable absorption (RSA) and excited state


Excited state absorption
Excited electronic states
Cis-trans isomerization
isomer formation
singlet-triplet state crossing
Two-photon transition
Single photon transition
Single photon transition
Intermolecular relaxation with other molecules
ΔT, Δρ, ΔS, Δθ
Electronic ground state
Nonelectronic responses, e.g. thermal, density, order parameter change, and crystalline axis reorientation (nematic liquid crystals)

Figure 3 Schematic depiction of the typical energy level structure of liquid crystal molecules and various linear and nonlinear optical processes.



Figure 4 Molecular structure and absorption spectrum of typical isotropic liquid crystal molecules.

absorption (ESA), respectively. As we will see presently, these so-called *electronic nonlinearities* are quite useful for optical limiting applications.

Following photo-absorption, the liquid crystal molecules could undergo intersystem crossing, *cis-trans* or other conformational changes, and form isomers or charge transfer complexes. These processes will contribute to the nonelectronic nonlinearities such as reorientational, order parameter changes and thermal effects.

Orientational Nonlinearities

Purely Optically Induced Orientation

Figure 5 depicts schematically various processes that could occur in an aligned nematic film upon irradiation by an optical field. The reorientation of the director axis $\hat{n}$ is governed by the system's tendency to minimize the overall free energy, which consists of several bulk and surface interaction terms, and the interaction energy with the applied field. In purely dielectric nonabsorbing nematic liquid crystals, director axis reorientation is caused by the torque Γ_{opt} between the anisotropic nematic and the optical electric field,

$$\Gamma_{\text{opt}} = \left(\frac{\Delta\varepsilon}{8\pi}\right)(\hat{n}\cdot\mathbf{E}^*)(\hat{n} \times \mathbf{E}) \qquad [1]$$

which competes with the elastic restoring torque Γ_{el} of the surrounding NLC molecules:

$$\Gamma_{\text{el}} = \frac{(K_1 \sin^2\theta + K_3 \cos^2\theta)\mathrm{d}^2\theta}{\mathrm{d}z^2} + \left[(K_1 - K_3)\sin\theta\cos\theta\right]\left(\frac{\mathrm{d}\theta}{\mathrm{d}z}\right)^2 \qquad [2]$$

where the K's are the elastic constants, and $\Delta\varepsilon$ is the (optical) dielectric anisotropy.

As a result of the director axis reorientation, an optical wave propagating through the medium will 'see' a refractive index change. A frequently employed method for measuring the refractive index change in nematic liquid crystal films is the grating diffraction setup, as shown in Figure 6a. Two polarized coherent writing beams are overlapped on a nematic film, which is probed by a polarized reading beam. If the writing beams are copolarized, they impart an optical intensity grating onto the nematic film $I = I_0(1 + \cos qx)$, where q is the grating wavevector, cf. Figure 6b. On the other hand, if the writing beams are orthogonally polarized, the resulting intensity is uniform over the illuminated area, and instead a polarization grating is created, cf. Figure 6c. The polarization state of the light in the overlapped region varies from circular, through elliptical to linear in accordance to the phase difference between the two coherent writing beams. Using a linearly polarized probe beam, this setup allows one to distinguish various intensity and reorientation dependent effects, and assess their contribution to the induced refractive index change Δn.

The magnitude of the induced reorientation angle, and therefore the extraordinary index change, depends on whether the interaction is transient or steady state. In the steady state case, to the first order of approximation, Δn is proportional to the optical intensity I, i.e., $\Delta n = n_2^{\text{SS}} I$. Under some experimental conditions, one can also show that the transient nonlinear index coefficient $n_2\ (\tau_{\text{p}})$ is given by $n_2\ (\tau_{\text{p}}) \sim n_2^{\text{SS}}\tau_{\text{p}}/\tau_{\text{r}}$, where $\tau_{\text{r}} = \gamma d^2/K\pi^2$ is the orientational relaxation time constant. For $d = 100\ \mu\text{m}$, $\gamma = 0.1$ poise and $K = 10^{-6}$ dynes, we have $\tau_{\text{r}} \sim 1$ s. Typical observed values of $n_2^{\text{SS}}(\theta)$ are



Figure 5 Schematic depiction of various laser-induced optical processes in a nematic liquid crystal film.



Figure 6 (a) Schematic depiction of grating formation and probe diffraction from the index grating induced in a nematic film. (b) Optical intensity grating formed by interfering two coherent copolarized writing beams. (c) Optical polarization grating formed by interfering two coherent crossed-polarized writing beams.

in the range of 10^{-5}–10^{-4} cm^2 W^{-1}. In the transient case, if $\tau_p = 1$ ns, then n_2 $(\tau_p) \sim 10^{-12}$ cm W^{-1} [$\chi^{(3)} \sim 2 \times 10^{-11}$ esu].

Excited Dye-Dopant Induced Intermolecular Torque

Studies of nematic liquid crystals doped with anthraquinone or dichroic dyes have shown that the excited dye molecules could exert an intermolecular torque Γ_{mole} that could be much larger in magnitude than Γ_{op}. By considering the interaction energies between ground and excited dyes with the surrounding LC molecules, one can show that Γ_{mole} may be written as:

$$\Gamma_{\text{mole}} = \zeta \Gamma_{\text{op}} \qquad [3]$$

where the proportionality constant ζ can be much larger than unity. The nonlinear index coefficients n_2 obtained in these films are on the order of 10^{-3} cm^2 W^{-1}. The response times for the director axis reorientation and relaxation are similar to the optically induced reorientation process discussed in the preceding section.

Photorefractive Effect

Another mechanism, namely, orientational photorefractivity, could also result in a very large optical nonlinearity. This effect occurs in nematic liquid crystals doped with photo-charge producing agents such as fullerene C_{60} or rhodamine 6G dye, in conjunction with a small applied dc field. For a 25 μm thick film with a dc bias voltage of ~1 V, the observed nonlinear coefficient n_2 is in the range of 10^{-3}–10^{-2} cm^2 W^{-1}. Figure 7 illustrates the orientational photorefractive effect. An incident optical field excites the doped liquid crystals to form charge transfer complexes (CTCs). The CTCs subsequently dissociate and create dc space charge fields through ionic diffusion, migration and other electrodynamical processes. The space charge fields, in combination with the applied dc field, create a dc field induced torque of the form:

$$\Gamma_{\text{dc}} = \left(\frac{\Delta\varepsilon_{\text{dc}}}{8\pi}\right)(\hat{n}\cdot\mathbf{E}^*_{\text{int}})(\hat{n} \times \mathbf{E}_{\text{int}}) \qquad [4]$$

Here the total internal dc field $\mathbf{E}_{\text{int}}$ contains the applied dc field $\mathbf{E}_{\text{dc}}$ and the generated dc space charge fields $\mathbf{E}_{\text{sc}}$. This causes director axis reorientation and refractive index change.

The space charge fields consist of one photorefractive and two anisotropy components. For an incident optical intensity grating function of the form $I_{\text{op}} = I_0(1 + m \cos q\xi)$, the photorefractive space charge



Figure 7 Schematic depiction of photo-induced space charge field formation in a nematic liquid crystal illuminated by a monotonic (upper curve) or a sinusoidal (lower curve) laser intensity function.

field is given by:

$$E_{\mathrm{ph}} = q\nu\, mk_{\mathrm{B}}T\left(\frac{\sigma - \sigma_{\mathrm{d}}}{2e\sigma}\right)\cos\left(\frac{q\xi - \pi}{2}\right) \qquad [5a]$$

where k_{B} is the Boltzmann constant, σ is the illuminated conductivity, σ_{d} is the dark state conductivity, $\nu = (D_+ - D_-)/(D_+ + D_-)$, where D_+ and D_- are the diffusion constants for the positively and negatively charged ions, respectively; m is the optical intensity modulation factor, $q = 2\pi/\Lambda$ is the magnitude of the grating wavevector, and ξ is the coordinate along q.

Two other sources of space charge fields are also at work, and they arise from the conductivity and dielectric anisotropies of the nematic under the action of the dc bias field E_{dc}:

$$E_{\Delta\sigma} = E_{\mathrm{dc}}\left(\frac{(\sigma_{//} - \sigma_{\perp})\sin\theta\cos\theta}{\sigma_{//}\sin 2\theta + \sigma_{\perp}\cos 2\theta}\right) \qquad [5b]$$

$$E_{\Delta\varepsilon} = E_{\mathrm{dc}}\left(\frac{(\varepsilon_{//} - \varepsilon_{\perp})\sin\theta\cos\theta}{\varepsilon_{//}\sin 2\theta + \varepsilon_{\perp}\cos 2\theta}\right) \qquad [5c]$$

where $(\sigma_{//} - \sigma_{\perp})$ is the low-frequency **conductivity anisotropy** and $(\varepsilon_{//} - \varepsilon_{\perp})$ the **dielectric anisotropy** of the liquid crystal, and θ is the reorientation angle of the director axis.

In addition to these space charge field induced effects, the **flows** of the charged ions and complexes under the applied dc field and the generated space charge fields also contribute significantly to reorienting the director axis. For an interaction geometry similar to Figure 5, the flow creates a shear torque Γ_{shear} of magnitude proportional to the velocity gradient

$$\Gamma_{\mathrm{shear}} = \frac{\mathrm{d}v(\zeta)}{\mathrm{d}\zeta}(\alpha_2\sin^2\theta - \alpha_3\cos^2\theta) \qquad [6]$$

where the α's are the viscosity coefficients, and $\mathbf{v}(\zeta)$ is the flow velocity. The combined action of the above space charge fields and the flow effects on director axis reorientation have been quantitatively formulated and shown to describe experimental results very well, including, in particular, the observation that maximal diffraction is obtained for a grating constant $\lambda_{\mathrm{g}} \sim 2d$. Furthermore, the flow-reorientation and adsorption of the excited dopant molecules on the surfaces are believed to be responsible for quasi-permanent and permanent director axis reorientation in rhodamine 6G- and C_{60}-doped nematic films, respectively.

Supra-Nonlinear Methyl-Red Doped NLC – Observed Phenomena

Recent studies in methyl-red doped nematic liquid crystals (MRNLCs) have ushered in the era of supra-nonlinearity. Unlike photorefractive nematic liquid crystals, no external bias field is needed. The observed n_2 values could be as large as $10\,\mathrm{cm^2\,W^{-1}}$. In MRNLC, a large photovoltage drop across the sample is also observed upon irradiation. The polarity of the photovoltage is reversed if the light impinges from the opposite cell window. The extremely nonlinear optical response of MRNLC is attributed to nematic director axis reorientation by the optically induced space charge fields, similar to the effect discussed in the previous section. The unusually large response is possibly due to several factors, including the higher photo-charge producing abilities of methyl red, and the large difference in the positive and negative photo-ion diffusion constants. Another cause of director axis reorientation is the intermolecular torque exerted by the photo-excited dye molecules on the NLC. This is particularly evident in experiments using an input polarization grating on planar aligned samples. Because the laser excited dye molecules are adsorbed and strongly 'anchored' on the cell walls, they cause permanent realignment of the nematic liquid crystal. This process usually occurs upon prolonged illumination of the liquid crystal cells with a low-power laser, and can be sped up with higher laser power.

Trans–Cis Isomerization and Order Parameter Change

Some nematic liquid crystals are azo-compounds, i.e., their molecular structures are analogous to the typical one depicted in Figure 8. An azo-compound when irradiated at its absorption wavelength will change from the *trans* to the *cis* form, cf. Figure 8. *Trans–cis* isomerization of these azo-nematic liquid crystals or azo-dopants in NLC's could also give rise to a refractive index change through modification of the NLC's order parameter and/or director axis reorientation. The *trans* species are oblong in shape, and align parallel to the director axis. On the other hand, the 'bent' structure of the *cis* species is incongruous to the nematic order, and thus causes an order parameter change, and therefore a refractive index modification. Such refractive index changes owing to order parameter modification are similar to thermal effects discussed in the next section. The response [on-] time for these *trans–cis* isomerization induced order-parameter changes can be quite fast (as fast as nanoseconds in some cases). The relaxation time (typically in the millisecond regime) is decided by the director axis relaxation rate as discussed earlier.



Figure 8 *Trans–cis* isomerization of azo-molecules upon optical illumination. The upper diagram depicts molecular structural changes; the lower diagram shows the excitation energy versus the molecular coordinate associated with these photo-excited processes.

The other index-changing mechanism is the tendency of the *trans* molecule to align with its transition moment perpendicular to the optical polarization in order to minimize the interaction (absorption) energies. This in turn causes the NLC director axis to realign through the intermolecular torque effect. Both mechanisms are characterized by a nonlinear index coefficient n_2 on the order of $10^{-3}\,\mathrm{cm^2\,W^{-1}}$.

Thermal and Density Effect

Laser induced temperature and density changes are described by time-dependent coupled hydrodynamics equations. In grating diffraction experiments, cf. Figure 6, the problem can be simplified to a one-dimensional one, i.e., along the grating wavevector direction, if the grating spacing is smaller than the nematic film thickness and the beam size. In that case, the thermal and Brillouin (sound wave) decay time constants are given by, respectively:

$$\tau_T = \frac{\rho_0 C_v}{\lambda_T q^2} \qquad [7a]$$

$$\tau_B = \frac{2\rho_0}{\eta q^2} \qquad [7b]$$

where $q = 2\pi/\lambda_q$ is the grating wavevector, ρ_0 the unperturbed density, C_v the specific heat, λ_T the thermal conductivity, and η the viscosity. The values of these parameters depend on the director axis alignment relative to the optical fields, thermal diffusion and sound propagation directions. For typical values of $\eta = 7\times10^{-2}\,\mathrm{kg\,m^{-1}\,s^{-1}}$, $\rho_0 = 10^3\,\mathrm{kg\,m^{-3}}$, $D = \lambda_T/\rho_0$, $C_v \sim 1.6\times10^{-7}\,\mathrm{m^2\,s^{-1}}$ and a grating spacing $\lambda_q = 20\,\mu\mathrm{m}$, we have $\tau_T \sim 50\,\mu\mathrm{s}$, whereas $\tau_B \sim 200\,\mathrm{ns}$. Such a vast difference between the relaxation times allows one to distinguish the contribution from thermal and density origins.

Table 1 Nonelectronic nonlinearities of nematic liquid crystals

Nonlinear processes	*Typical magnitude*	*Time-scale*	*Liquid crystal*
Orientational nonlinearities			
Purely optically induced n_2	10^{-4} cm^2 W^{-1}	ms	pure 5CB
Excited dopant assisted n_2	10^{-3} cm^2 W^{-1}	ms	dyed 5CB
Photorefractive	10^{-3} cm^2 W^{-1}	ms	5CB
Photorefractive + Methyl-red doped 5CB	10 cm^2 W^{-1}	ms	
Trans–Cis and order parameter modification	10^{-4} cm^2 W^{-1}	ms	dyed 5CB
Thermal nonlinearities			
n_2	10^{-6} cm^2 W^{-1}	ms	E7
n_2	10^{-11} cm^2 W^{-1}	ns	E7
Density effect			
electrostrictive n_2	10^{-11} cm^2 W^{-1}	ns	E7

In the steady state, i.e., when the laser–nematic interaction time is much longer than τ_T and τ_B, the nonlinear index coefficient is given by:

$$n_2^{SS}(\Delta T) = \left(\frac{dn}{dT}\right)\frac{\alpha\tau_r}{\rho_0 C_V} \qquad [8]$$

where dn/dT is the appropriate thermal index coefficient. The absorption constant α of liquid crystals varies widely in the visible–infrared spectrum. Near the phase transition temperature, $dn_{//,\perp}/dT$ also changes dramatically. The magnitude of $n_2^{SS}(\Delta T)$ could therefore vary by several orders of magnitude. For $\alpha = 100\ \text{cm}^{-1}$, $dn_{//,\perp}/dT \sim 10^{-3}\ \text{K}^{-1}$, and $\lambda_q = 20\ \mu\text{m}$, we have $n_2^{SS}(\Delta T) \sim 10^{-6}\ \text{cm}^2\ \text{W}^{-1}$. This is the typical value observed in wave mixing experiments with infrared [CO_2] or visible lasers.

In the transient regime ($\tau_p \ll \tau_r, \tau_B$), the nonlinear index coefficient is proportional to the laser pulse duration:

$$n_2(\tau_p) = n_2^{SS}(\Delta T)\tau_p/\tau_r \qquad [9]$$

With $\tau_r \sim 0.5 \times 10^{-4}$ s and $\tau_p = 1$ ns, $n_2(\tau_p) \sim 5 \times 10^{-11}\ \text{cm}^2\ \text{W}^{-1}$. Such nonlinearities have been observed in transient dynamic grating diffraction studies involving nanosecond laser pulses. In these studies, it is found that the contribution from the electrostrictive effect (movement of the nematic due to the optical intensity gradient) to the refractive index change can be as large as the absorptive thermal component.

In Table 1, we give a concise summary of these nonelectronic optical nonlinearities observed in nematic liquid crystals.

Electronic Nonlinearities

Second and Third Order Nonlinear Susceptibilities

Electronic interaction involves the perturbation of the electronic wavefunctions by the impinging optical fields. The induced dipole moment of a molecule is given by:

$$\mathbf{d} = \boldsymbol{\alpha}:\mathbf{E} + \boldsymbol{\beta}:\mathbf{EE} + \boldsymbol{\gamma}:\mathbf{EEE} + \cdots \qquad [10]$$

where $\boldsymbol{\alpha}$, $\boldsymbol{\beta}$, and $\boldsymbol{\gamma}$ are the linear, second-order and third-order nonlinear polarizability tensors, $\mathbf{E}$ is the optical electric field and : denotes tensorial operation. The macroscopic polarization $\mathbf{P}$ (dipole moment per unit volume) is

$$\mathbf{P} = \varepsilon_0\boldsymbol{\chi}^{(1)}:\mathbf{E} + \boldsymbol{\chi}^{(2)}:\mathbf{EE} + \boldsymbol{\chi}^{(3)}:\mathbf{EEE} + \cdots \qquad [11]$$

where $\boldsymbol{\chi}^{(1)}$, $\boldsymbol{\chi}^{(2)}$, and $\boldsymbol{\chi}^{(3)}$ are the linear, second and third-order nonlinear susceptibilities, respectively. The macroscopic parameters $\boldsymbol{\chi}$ are related to $\boldsymbol{\alpha}$, $\boldsymbol{\beta}$ and $\boldsymbol{\gamma}$ by the local field correction factors.

A well-known process associated with the second-order nonlinear polarization is second harmonic generation, in which two incident photons of frequency ω are converted into a photon of frequency 2ω. Symmetry rules require that a material should be non-centrosymmetric in order to exhibit second-order nonlinear polarization. In centrosymmetric nematic liquid crystals, an applied dc field or discontinuity at a surface or interface, or director orientational curvature, could provide the required symmetry-breaking mechanism.

In ferroelectric or smectic C* liquid crystals, the molecules possess permanent polarization, i.e., the centrosymmetry is broken, and it is possible to observe second harmonic generation associated with the second-order nonlinear polarization. Typically, the observed nonlinear coefficients β_{2HG} are on the order of $\sim 10^{-14}\ \text{mV}^{-1}$. In contrast to inorganic crystals of much larger dimensions, these thin liquid crystal films are not useful for practical devices. Nonetheless, because of the sensitivity of second harmonic generation to surface and interface conditions, second harmonic generation has been proven to be an effective spectroscopic tool.

In dc field induced second harmonic generation, the nonlinear polarization involved is actually the

Table 2 Electronic optical nonlinearities of nematic liquid crystals

Nonlinear optical phenomena and nonlinearities	*Magnitude*	*Time-scale (pulse duration of laser used)*
Second harmonic generation (dc field induced),		
$\chi_{//}^{(3)}$	2.7×10^{-12} esu	ns
$\chi_{\perp}^{(3)}$	0.55×10^{-12} esu	ns
Second harmonic generation β_{2HG}	10^{-12} mV^{-1}	ps (ferroelectric)
Two-photon absorption, β	5 cm GW^{-1}	80 ps
Effective nonlinear absorption, β_{eff}	200 cm GW^{-1}	10 ns
Degenerate four-wave mixing		
electronic $\chi^{(3)}(\omega; \omega, -\omega, \omega)$	10^{-12} esu	ns

third-order nonlinear polarization given by $P(2\omega) = \boldsymbol{\chi}^{(3)}E(0)E(\omega)E(\omega)$. Typically measured values of $\boldsymbol{\chi}^{(3)}$ are $\sim 10^{-12}$ esu, expressed in the commonly used cgs units. The conversion factor between cgs and SI unit is given by

$$\boldsymbol{\chi}^{(3)}[\text{esu}] = 3^4 \times 10^{17} \boldsymbol{\chi}^{(3)}[\text{SI unit}] \qquad [12]$$

There is relatively little work done on measuring or studying the third-order nonlinear electronic polarizabilities of nematic liquid crystals. Most of the studies are centered on the molecular correlation effects associated with the nematic–isotropic phase transition. The typical magnitude of electronic $\boldsymbol{\chi}^{(3)}$ is 10^{-12} esu.

Nonlinear Absorption and Limiting

Two-photon absorption occurs where the molecule is excited to a real electronic excited state by simultaneous absorption of two photons from the incident light. Since the absorption is proportional to the square of the optical intensity, the incident light will experience an increasing absorption effect, and its transmission at high intensity will be 'quenched' to an almost constant level. Two-photon absorption is usually characterized by the two-photon absorption coefficient β, which is related to the imaginary part of $\boldsymbol{\chi}^{(3)}$. For liquid crystals, they are on the order of 5×10^{-12}–10^{-11} mW^{-1} (equivalent to 0.5–5 cm GW^{-1} in the more commonly used units).

Liquid crystalline materials in their (less scattering) isotropic phase have been extensively studied in the last few years for application in optical limiting devices as a result of their large nonlinear absorption constant. In the nanosecond time regime, the RSA and ESA effects, cf. Figure 3, act to give rise to a very large effective nonlinear absorption coefficient β on the order of several hundreds of cm GW^{-1}. In combination with special device structure such as a nonlinear fiber array, it has become possible to clamp the transmitted nanosecond laser pulse energy to below the retina damage level (below 0.5 μJ).

In Table 2, we give a concise summary of these electronic optical nonlinearities of nematic liquid crystals.

Concluding Remarks

We have presented a concise review of the nonlinear optics of liquid crystals in their nematic and isotropic phases. Nematic liquid crystals in their various pure and doped forms possess many interesting nonlinear optical responses, with nonlinearities ranging over 16 orders of magnitude. Some of the extraordinarily large nonlinearities enable the performance of several all-optical switching and limiting, image modulation and sensing processes at unprecedented low threshold power. In particular, self-defocusing and optical limiting effects with nanowatt-power lasers, and incoherent–coherent image conversion at μW cm^{-2} optical intensity have been demonstrated. Liquid crystal films have been used in selective attenuation of glares and blinding laser light. Stimulated scattering that used to be the domain of high-power lasers can now be performed in thin nematic films with mW-power cw laser. Readers can consult the Further Reading section for some of these advanced photonic devices and applications based on nonlinear optics of liquid crystals. Current active studies by several research groups worldwide are likely to result in even more interesting nonlinear optical effects and useful applications in the near future.

List of Units and Nomenclature

Absorption coefficient	α [cm^{-1}]
Density	ρ_0 [kg m^{-3}]
Eleastic constant	K [dynes]
Intensity (optical)	I [W cm^{-2}]
Nonlinear susceptibility	$\chi^{(3)}$ [esu]
Second harmonic generation coefficient	β_{2HG} [mV^{-1}]
Specific heat	C_V [m^2 s^{-1}]
The nonlinear index coefficients	n_2 [cm^2 W^{-1}]
Time constants	τ [s]

Two-photon absorption constant	β [cm GW^{-1}]
Viscosity	η [kg m^{-1} s^{-1}]
Viscosity coefficient	γ [poise]

See also

Nonlinear Optics, Basics: Cascading; Kramers–Krönig Relations in Nonlinear Optics; Nomenclature and Units; Photorefraction.

Further Reading

Khoo IC (1995) *Liquid Crystals: Physical Properties and Nonlinear Optical Phenomena*. New York: Wiley Interscience.

Khoo IC (1996) Orientational photorefractive effects in nematic liquid crystal films. *IEEE Journal of Quantum Electronics* 32: 525–534.

Khoo IC and Liang Y (2000) Stimulated orientational and thermal scatterings and self-starting optical phase conjugation with nematic liquid crystals. *Physical Review* E62: 6722–6733.

Khoo IC and Wu ST (1993) *Optics and Nonlinear Optics of Liquid Crystals*. Singapore: World Scientific.

Khoo IC, Chen PH, Wood MV and Shih MY (1999) Molecular photonics of a highly nonlinear organic fiber core liquid for picosecond–nanosecond optical limiting effect. *Chemical Physics* 245: 517–531.

Khoo IC, Wood MV, Shih MY and Chen PH (1999) Extremely nonlinear photosensitive liquid crystals for image sensing and sensor protection. *Optics Express* 4(11): 431–442.

Khoo IC, Shih MY, Wood MV, *et al.* (1999) Dye-doped photorefractive liquid crystals for dynamic and storage holographic grating formation and spatial light modulation. *IEEE Proceedings* 87: 1897–1911.

Marrucci L and Papara D (1997) Photoinduced molecular reorientation of absorbing liquid crystals. *Physical Review* E56: 1765–1772.

Rau H (1990) Photoisomerization of Azobenzenes. In: Rabeck FJ (ed.) *Photochemistry and Photophysics*, vol. 2, chap. 4, pp. 119–141. Boca Raton, FL: CRC Press.

Shen YR (1990) *Principles of Nonlinear Optics*. New York: Wiley Interscience.

Organic Nonlinear Materials

F Kajzar and I Rau[*], Commissariat à l'Energie Atomique, Gif sur Yvette, France

© 2005, Elsevier Ltd. All Rights Reserved.

Nonlinear Medium Polarization

Macroscopic

Photons are neutral, noninteracting bosons. Interaction is possible only through a material medium. Indeed, photons can be absorbed by electrons leading to excited states. A reverse transition may go through radiative channels, with emission of photons, usually with a different energy than the excitation energy. Interaction of photons with matter may also lead to other types of excitation, such as vibronic, rotational, libronic, etc., or just to a change in the medium polarization. This change may be expanded in the power series of the electric forcing field strength with ith component given by:

$$\begin{aligned} P_I(\omega_\sigma) = P_{0I}(\omega_\sigma) + \varepsilon_0[&K_1\chi^{(1)}_{IJ}(-\omega_\sigma;\omega_\sigma)E_J^{\omega_\sigma} \\ &+ K_2\chi^{(2)}_{IJK}(-\omega_\sigma;\omega_1,\omega_2)E_J^{\omega_1}E_K^{\omega_2} \\ &+ K_3\chi^{(3)}_{IJKL}(-\omega_\sigma;\omega_1,\omega_2,\omega_3)E_J^{\omega_1}E_K^{\omega_2}E_{\mathrm{L}}^{\omega_3} + \cdots] \end{aligned} \qquad [1]$$

where the expansion coefficients $\chi^{(n)}$ are $(n+1)$ rank three-dimensional tensors, describing linear $(n = 1)$ and nonlinear $(n > 1)$ responses of the medium, $P_{0i}(\omega_\sigma)$ is its permanent polarization (at frequency ω_σ) and the coefficients K_i $(i = 1, 2, 3, \ldots)$ take account of the conventions for the Fourier transform of electric field and polarization vectors used, as well as the degeneracy of nonlinear optical processes. For historical reasons two conventions in quantitative description of NLO processes are used:

$$\mathrm{E}(\mathrm{r}, t) = \tfrac{1}{2}[\mathrm{E}(\mathrm{r})\mathrm{e}^{\mathrm{i}\omega t} + \mathrm{c.c.}] \qquad \text{(Convention I)} \qquad [2]$$

and

$$\mathrm{E}(\mathrm{r}, t) = \mathrm{E}(\mathrm{r})\mathrm{e}^{\mathrm{i}\omega t} + \mathrm{c.c.} \qquad \text{(Convention II)} \qquad [3]$$

and similarly for the polarization field. As researchers often use different conventions, it is important to bear this in mind when comparing NLO properties of materials coming from different sources. The tabulated data and the formulas used here are within convention I, with the permutation factors included explicitly in coefficients K_i (eqn [1]). In centrosymmetric media and in dipolar approximation, the static polarization P_0, as well as all even order NLO susceptibilities, are equal to zero, as it follows from time reversal symmetry.

---

[*] On leave from POLITECHNICA University of Bucharest, Romania.

Relations Between Macroscopic and Microscopic Polarizations

Microscopic Polarization

Similar expansions to eqn [1] also obey the conventions on a molecular level. Similarly, as for bulk polarization, the ith component of the molecule dipole moment can also be expanded into the series of the local field strength giving:

$$\begin{aligned}\mu_i(\omega_\sigma) &= \mu_{0i}(\omega_\sigma) + K_1\alpha_{ij}(-\omega_\sigma;\omega_\sigma)E_j^{\omega_\sigma}\\ &\quad + K_2\beta_{ijk}(-\omega_\sigma;\omega_1,\omega_2)E_j^{\omega_1}E_k^{\omega_2}\\ &\quad + K_3\gamma_{ijkl}(-\omega_\sigma;\omega_1,\omega_2,\omega_3)E_j^{\omega_1}E_k^{\omega_2}E_l^{\omega_3} + \cdots\\ &= \mu_{0i}(\omega_\sigma) + \mu_{\text{ind}}(\omega_\sigma,\omega_1,\omega_2,\ldots,\omega_n,\alpha,\beta\ldots,\zeta,\\ &\quad E^{\omega_1},E^{\omega_2},\ldots,E^{\omega_n})\end{aligned} \qquad [4]$$

where α is the linear molecular polarizability, β is the first order and γ is the second molecular hyperpolarizability. μ_{in} in eqn [4] denotes the induced dipole moment. The expansions [1] and [4] may be also considered as the Tamm–Dancoff perturbation development as functions of an increasing number of interacting photons. In this case, the second term on the right-hand sides of eqns [1] and [4] describes the interaction of two photons, the third term that of three photons, etc. The electric field in eqn [4] is the effective field experienced by the molecule and is given by

$$E = fE \qquad [5]$$

where f is the local field factor, depending on the form of molecule. In eqns [1] and [4] Einstein's notation is used.

For a single crystal and for noninteracting molecules there exists a straightforward relationship between the macroscopic and microscopic quantities given by:

$$\begin{aligned}\chi^{(2)}_{IJK}(-\omega_\sigma;\omega_1,\omega_2) &= \sum_n f_n^{\omega_\sigma} f_n^{\omega_1} f_n^{\omega_2} N_n\\ &\quad\times\sum_{ijk} a_{Ii}a_{Jj}a_{Kk}\beta^n_{ijk}(-\omega_\sigma;\omega_1,\omega_2)\end{aligned} \qquad [6]$$

for the second-order NLO susceptibility and

$$\begin{aligned}\chi^{(3)}_{IJKL}(-\omega_\sigma;\omega_1,\omega_2,\omega_3) &= \sum_n f_n^{\omega_\sigma} f_n^{\omega_1} f_n^{\omega_2} f_n^{\omega_3} N_n\\ &\quad\times\sum_{ijkl} a_{Ii}a_{Jj}a_{Kk}a_{Ll}\gamma^n_{ijkl}(-\omega_\sigma;\omega_1,\omega_2,\omega_3)\end{aligned} \qquad [7]$$

for the third-order NLO susceptibility, respectively. The coefficients a_{Ij} in eqns [6] and [7] are Wigner rotation matrix elements, N_n denoting the number density of species (n). The subscripts ($ijkl$) refer to the molecule, and ($IJKL$) to the laboratory reference frames, respectively.

For disordered (or partly ordered) materials, the macroscopic NLO susceptibility depends on the orientation average of nonzero molecular hyperpolarizability components:

$$\begin{aligned}\chi^{(2)}_{IJK}(-\omega_\sigma;\omega_1,\omega_2) &= \sum_n f_n^{\omega_\sigma} f_n^{\omega_1} f_n^{\omega_2} N_n\\ &\quad\times\sum_{ijk} < \beta^n_{ijk}(-\omega_\sigma;\omega_1,\omega_2) >_{IJK}\end{aligned} \qquad [8]$$

and similarly for $\chi^{(3)}$ susceptibility. The average in eqn [8] is taken over all NLO molecule orientations and all β tensor components. Fortunately, the number of the nonzero β tensor components (21 for β tensor) is limited by the molecular symmetry and in the case of charge transfer (CT) molecules, only the component in the charge transfer direction β_{xxx} may be retained. The others are usually significantly smaller and can be neglected with respect to this one.

Second-Order Nonlinear Optical Materials

The research on nonlinear optical materials is boosted by the potentiality of their applications in photonics, and particularly in optical signal processing, image recognition, frequency conversion, and light amplification. New fields of applications open in biology, medicine (photodynamic therapy), material processing (optical engineering), etc. Depending on the targeted application, the materials showing enhanced second-, third-, and/or higher-order nonlinear optical properties are developed and optimized. The optimization is performed on both molecular and macroscopic levels. Indeed, the bulk nonlinear optical response depends not only on the individual hyperpolarizabilities but also on the way the molecules are assembled into the bulk material. As already mentioned, only the noncentrosymmetric materials exhibit the second-order nonlinear optical response.

Molecules

The most promising molecules for the application in second-order NLO devices are intramolecular CT compounds, composed from an electron donating (D), an electron accepting (A) part, linked by a π conjugated backbone (Figure 1). The CT molecules exhibit a large first-order susceptibility β tensor component β_{xxx}, enhanced in the charge transfer direction x. The value of β_{xxx} depends on the strength of electron donating and electron accepting groups (amount of the charge transfer)



Figure 1 Schematic representation of a charge transfer molecule.

Table 1 Chemical structures of commonly used electron donating and electron accepting groups

Donors	*Acceptors*
$-N(CH_3)_2$	$-NO$
$-NH_2$	$-NO_2$
$-OCH_3$	$-CHO$
$-OH$	$-CN$
$-CH_3$	$-SO_2CH_3$
$-SCH_3$	$-SO_2CF_3$
$-N(CH_3)_2$	$=C(CN)_2$

and on the conjugation length of the transmitter. Table 1 shows the chemical structures of typical electron donating and electron accepting groups. Chemical structures of selected CT molecules are given in Table 2, together with the values of the β_{xxx} tensor component, as determined by the electric field induced second-harmonic generation technique (EFISH).

The dependence of β_{xxx} on the conjugation length L of the conjugated transmitter is given by the scaling law:

$$\beta_{xxx} \propto L^{\alpha_s} \qquad [9]$$

with $\alpha_s > 1$. Usually the conjugated backbone is composed of a number of alternate single/double (or single/triple) bonds and in this case, the scaling law is tested as a function of the number of double (or triple) bonds N:

$$\beta_{xxx} \propto N^{\alpha_\beta} \qquad [10]$$

For a number of CT oligomers with the same electron donating and electron accepting groups, differing only in the length of the conjugated transmitter, the exponent $\alpha_\beta \sim 2.5$. The β_{xxx} value saturates for a larger number of double bonds ($N > 4$, in the case of phenyl oligomers used as transmitter).

A number of studies are in progress on octupolar molecules which exhibit large β hyperpolarizabilities. However, their processing into efficient, noncentrosymmetric bulk materials is still at its initial stage and up to now no practical application has been demonstrated.

Bulk Materials

In order to obtain noncentrosymmetric materials, different approaches are used such as:

(i) single crystals growth;
(ii) epitaxy or heteroepitaxy;
(iii) Langmuir–Blodgett films;
(iv) self-assemblies;
(v) intermolecular charge transfer structures;
(vi) poled polymers; and
(vii) chiral structures.

The growth of good-quality optical single crystals is costly and difficult, especially as the charge transfer molecules usually exhibit a large ground state dipole moment (Table 2). The strong dipole–dipole interaction usually leads to their antiparallel alignment, and as a consequence, a centrosymmetric bulk structure. Only a few molecules crystallize in a noncentrosymmetric structure. One of the approaches used consists of design and synthesis of molecules with a negligible ground state dipole moment such as POM (Table 3). Therefore, a lot of effort has been put into forcing molecules to build into noncentrosymmetric bulk materials (ii)–(vi). Owing to the fact that most of applications are targeted in waveguiding configuration, a significant effort has been made to grow noncentrosymmetric thin films (ii)–(vi). While the chiral molecules form spontaneously noncentrosymmetric films, in other techniques, this is obtained more easily by application of an external electric field (poled polymers), by use of an adequate substrate (epitaxy, pseudoepitaxy, self assembly), intramolecular charge transfer in ordered layered structures (v), and interaction between molecules and molecules–substrate (Langmuir–Blodgett films). In the last case, three types of well-ordered structures, with controllable thickness are obtained: X, Y, Z (Figure 2). Only X and Z type structures give noncentrosymmetric thin films exhibiting second-order NLO properties.

Poled polymers

Up to now, the best results in getting efficient materials for second-order NLO application are obtained with poled polymers. The materials consist of a polymer matrix, exhibiting excellent optical properties, functionalized with active NLO chromophores (CT molecules). Four kinds of structures, shown schematically in Figure 3, are realized:

(i) guest–host systems;
(ii) side chain polymers;
(iii) main chain polymers; and
(iv) thermally or photo-crosslinked polymers.

Table 2 Molecular first hyperpolarizabilities and dipole moments of selected CT molecules

Molecule	*Chemical structure*	λ_{max} *[nm]*	*Solvent*	*Ground state dipole moment,* μ *[D]*	*Product* $\mu\beta$ *[*10^{-77} *Cm*^{5} *V*$^{-1}$*]*	β *[*10^{-40} *m*^{4} *V*$^{-1}$*]*	λ_{meas} *[nm]*	β_0 *[*10^{-40} *m*^{4} *V*$^{-1}$*]*
p-NA (*para*-nitroaniline)		358	1,4 dioxane	5.5	1.30 0.74	71.0 40.2	1064 1907	35
MNA (2-methyl-4-nitroaniline)		361	1,4 dioxane	7.4	1.72 0.98	69.9 39.8	1064 1907	33
NPP (*N*-(4-nitrophenyl)-(L)-prolinol)		397	acetone	7.3	4.28	176	1064	67
POM (3-methyl-4-nitropyridine-1-oxide)		320	from crystal data	0	0	36	1064	21
PNP (1-(*N*-prolinol)-5-nitropyridine)		376	1,4 dioxane	7.2	2.28 1.41	95 59	1064 1907	38
MMONS (3-Methyl-4-methoxy-4′ nitrostilbene)		366	1,4 dioxane	5.2	2.14	123.9	1907	90
DR1 (4-[*N*-ethyl-*N*-(2-hydroxyethyl)]amino-4′-nitroazobenzene (dispersed red 1))		509 455	DMSO 1,4 dioxane			525 234.1	1356 1907	197 150
DADAB (4-(*N*,*N*-diethylamino)-4′-tricyanovinylazo benzene)		582	DMSO			1640	1580	648

1D = (1/3) × 10^{-39} Cm.

Table 3 Bulk second-order nonlinear optical properties of selected organic materials

Material	*Chemical structure*	*Form*	*Point group*	λ_{meas} *[nm]*	*Refractive index*	*SHG susceptibility* $\chi^{(2)}_{ijk}(-2\omega; \omega, \omega)$ *[pm V^{-1}]*	*Electrooptical coefficient, r, [pm V^{-1}]*
MNA (2-methyl-4-nitroaniline)		Single crystal	*m*	514.5 1064	2.0	$\chi^{(2)}_{111} = 500$ $\chi^{(2)}_{122} = 76$	70 ± 14
POM (3-methyl-4-nitropyridine-1-oxide)		Single crystal	222	514.5 600 10 600 1064	1.712 1.919 1.638	$\chi^{(2)}_{123} = 19.2$ $\chi^{(2)}_{123} = \chi^{(2)}_{251} = \chi^{(2)}_{312}$	4.0 5.1 3.7
COANP (2 cyclooctylamino-5 nitropyridine)		Single crystal	*mm*2	514.5 600 10 600 1064	1.672 1.781 1.647	$\chi^{(2)}_{322} = 108$ $\chi^{(2)}_{333} = 48$	9.3 ± 1.5 15.4 ± 3.2
PNP (2-(N-prolinol)-5-nitropyridine)		Single crystal	2	514.5 600 10 600 1064	1.990 1.788 1.467	$\chi^{(2)}_{211} = 170$ $\chi^{(2)}_{223} = 55$	8.0 ± 1.4 13.0 ± 2.2
MNBA (4′-nitrobenzylidene-3-acetamino-4-methoxyaniline)		Single crystal	*m*	514.5 600 10 600 1064	2.024 1.585 1.652	$\chi^{(2)}_{111} = 437$	–
MMONS (3-Methyl-4-methoxy-4′-nitrostilbene)		Single crystal	*mm*2	514.5 600 10 600 1064	1.569 1.693 2.129	$\chi^{(2)}_{333} = 368^{a}$ $\chi^{(2)}_{223} = 142^{a}$	19.3 ± 4 39.9 ± 7

PMMA + DR 1 (Poly(methyl methacrilate) + 4-[N-ethyl-N-(2-hydroxyethyl)] amino-4′-nitroazobenzene (Dispersed red 1))		PP/GH	1580	$\chi^{(2)}_{333} = 5$	
			633		$r_{33} = 2.5$
PMMA + DCV (Poly(methyl metacrilate) + 4-dicyanovinyl-4′- [N-ethyl-(2 hydroxyethyl)] azobenzene)		PP/SC	1580	$\chi^{(2)}_{333} = 42$	
			799		$r_{33} = 18$
PMMA + 3RDCVXY (Poly(methyl metacrilate) + 4-dicyanovinyl-4′ (diethylamino) diazobenzene)		PP/SC	1064	$\chi^{(2)}_{333} = 840$	
			633		$r_{33} = 40$

Table 3 (*Continued*)

Material	*Chemical structure*	*Form*	*Point group*	*λ_{meas} [nm]*	*Refractive index*	*SHG susceptibility $\chi^{(2)}_{ijk}(-2\omega;\omega,\omega)$ [pm V^{-1}]*	*Electrooptical coefficient, r, [pm V^{-1}]*
NNDN + NAN (N,N-diglycidyl-4-nitroaniline + N-(2-aminophenyl)-4-nitroaniline)	 +	PP/CL		1064		$\chi^{(2)}_{311} = 28$	
				530.9			$r_{13} = 6.5$
DCANP		LB film		632.8	1.598 (TE$_0$-mode)		
				1064		$\chi^{(2)}_{333} = 19.5 \pm 2.5$	
FA06		LB film		1064		$\chi^{(2)}_{322} = 20$	

PP, poled polymer; GH, guest host system; SC, side chain polymer; CL, cross linked polymer; LB, Langmuir–Blodgett film.

[a] Calibrated with KTP single crystal ($\chi^{(2)}_{333} = 27.4$ pm/V).



Figure 2 Schematic representation of *X, Y, Z* type Langmuir–Blodgett films. The arrows symbolize the direction of dipole moments, which usually are tilted with respect to the normal to film surface.



Figure 3 Schematic representation of functionalized polymers for second-order NLO effects: guest–host systems (a), side chain polymers (b), main chain polymers (c), photo and thermally cross-linking polymers (d). Arrows represent the NLO chromophores.

The guest–host systems are just solid solutions of NLO chromophores in an inert matrix. The concentration of NLO chromophores is limited because of already-mentioned strong dipole–dipole interaction leading to antiparallel alignment, resulting in an increase in propagation losses and decrease of $\chi^{(2)}$ susceptibility. The polar order is obtained by applying an external field. In order to increase the rotational mobility of chromophores, the material is heated to the glass transition temperature of polymer. The interaction of dipole moments with the external field forces them to orient in its direction. The orientation is frozen by cooling the material (usually a thin film) to room temperature. However, the stability induced in this way results in a polar order that is poor. Better stability and higher concentration of chromophores is obtained by attaching chemically the NLO active molecules to the polymer backbone (side-chain polymers). However, it requires a significant effort in chemical synthesis. The stability of induced order depends strongly on the difference between the glass transition and the operation temperatures. The larger the difference, the less relaxation is observed. Therefore, a lot of effort is going into developing functionalized high glass transition temperature polymers such as polyimides, polyurethanes, polyvinyl carbazoles, etc.

The main-chain polymers (iii) attract a relatively weak interest. This is due, not only to the difficulties encountered with chemical synthesis, but also with the efficient chromophore orientation. More promising is the last class of functionalized polymers (iv). Here the active chromophores are used to link covalently the polymer chains through a thermal or photo-crosslinking process. However, the poling process is very delicate as the glass transition temperature is increasing with the poling time, so the time process has to be carefully monitored. Also the cross-linking may lead to shrinkage and crackling of thin films and as a consequence, to the increase of propagation losses.

A special class of functionalized materials, similar to poled polymers, represent sol–gels. Here the active chromophores either fill the pores of sol–gel or are chemically bonded to the matrix. The poling process is very similar to that applied to the thermally and photo cross-linking polymers and also has to be carefully monitored. The main advantage of these materials consists of excellent optical properties, and the disadvantage on a relatively low chromophore content, limiting the bulk $\chi^{(2)}$ susceptibility value. The representative values of second-order nonlinear optical susceptibility $\chi^{(2)}_{ijk}$ for different materials for second-order NLO optics, are listed in Table 3.

Poling efficiency

The DC poling of functionalized polymers leads to birefringent noncentrosymmetric materials with two nonzero $\chi^{(2)}$ tensor components: the diagonal:

$$\chi^{(2)}_{ZZZ}(-\omega_0;\omega_1,\omega_2) = NF\beta_{xxx}(-\omega_\sigma;\omega_1,\omega_2) \times \langle\cos^3\Theta\rangle \qquad [11]$$

and the off-diagonal:

$$\chi^{(2)}_{XXZ}(-\omega_\sigma;\omega_1,\omega_2) = \frac{1}{2}NF\beta_{xxx}(-\omega_\sigma;\omega_1,\omega_2) \times \langle\sin^2\Theta\cos\Theta\rangle \qquad [12]$$

where we assumed for simplicity, that only one nonlinear species, as is usually the case. Z, in eqns [11] and [12], is the direction of the applied external field and Θ is the angle between the electric field and the molecule dipole moment. The efficiency of poling is measured by the ratio:

$$a = \frac{\chi^{(2)}_{ZZZ}(-\omega_\sigma; \omega_1, \omega_2)}{\chi^{(2)}_{XXZ}(-\omega_\sigma; \omega_1, \omega_2)} \qquad [13]$$

It varies between 1 and ∞ (perfect alignment). For isotropic poled polymers $a = 3 \div 6$ and for nematic liquid crystal side-chain polymers, values of $a \propto 18$ were obtained.

Usually, the second-order NLO susceptibility is measured by the second-harmonic generation technique ($\omega_\sigma = 2\omega$; $\omega_1 = \omega_2 = \omega$), giving the electronic part of $\chi^{(2)}$ susceptibility, with ultrafast response time as the generated harmonic wave has to follow the fundamental one. This susceptibility is important, not only for frequency conversion through the second-harmonic generation, but also for sum and difference frequency generation as well as for optical parametric oscillation (OPO) and amplification (OPA). Another important effect described by $\chi^{(2)}(-\omega; \omega, 0)$ susceptibility is the linear electro-optic effect (Pockels effect). It finds application in electro-optic modulation for signal transmission. Traditionally, this effect is described by the electro-optic coefficient r_{ijk}, which is a third-rank three-dimensional tensor. The variation of the medium refractive index under the applied electric field is given by the following formula:

$$\Delta n_i = -\frac{2}{n_i^3} r_{ij} E_j \qquad [14]$$

The electro-optic coefficient is directly linked to the $\chi^{(2)}(-\omega; \omega, 0)$ susceptibility:

$$r_{ijk} = -\frac{2\chi^{(2)}_{ijk}(-\omega; \omega, 0)}{(n_i n_j)^2} \qquad [15]$$

The measured values of electro-optic coefficient for some selected organic single crystals and thin films are also given in Table 3.

Third-Order Nonlinear Optical Materials

There is no symmetry restriction on molecules and materials for third- (or higher-odd-) order nonlinear optical effects. These materials are used in significantly larger classes of applications than the materials for second-order NLO effects, particularly in logic systems, all optical switching, frequency conversion (e.g., frequency tripling in third-harmonic generation), light amplification, optical bistability, all optical switching, etc. In the case of organic materials, it was shown that the conjugated quasi 1D π electron systems, such as semiconducting polymers (Figure 4) exhibit an enhanced third-order NLO response.

Molecules

Similarly, as in the case of second-order NLO materials, the NLO response depends strongly on the conjugation length. In the case of conjugated quasi 1D molecules, such as polymers with a chemical structure as shown in Figure 4, the γ tensor component in the conjugation direction (largest hyperpolarizability) is strongly enhanced and described by a scaling law:

$$\gamma_{xxxx} \propto L^{\alpha_t} \qquad [16]$$

where L is the conjugation length and the exponent $\alpha_t > 1$. The scaling law, eqn [16], can also be presented as dependent on γ on a number of π conjugated double or triple bonds N:

$$\gamma_{xxxx} \propto N^{\alpha_\gamma} \qquad [17]$$

It was extensively studied for a series of conjugated oligomers polyenes, oligothiophenes, etc., and the exponential coefficients are listed in Table 4, together with the calculated values. For a larger value of double (or triple) bonds, a saturation in $\chi^{(3)}$ susceptibility is observed.

The molecular second hyperpolarizability measurements are derived from solution measurements. Some typical values, obtained by the third-harmonic generation technique (THG) are listed in Table 5. Although other NLO property determination techniques were used, the THG method gives the fast, electronic part of molecular hyperpolarizability.

Bulk Materials

Importance of Order

Similarly, as in the case of materials for second-order NLO effects for practical applications the value of $\chi^{(3)}$ susceptibility is important, which on the other hand depends on the molecular second hyperpolarizability γ. Although the noncentrosymmetry is not required in the case of third-order NLO materials, the values of the bulk $\chi^{(3)}$ susceptibility depend on the order, as it follows from eqn [7]. This is particularly clear in the case of conjugated molecules, with enhanced γ_{xxxx} component. In the case of parallel polarizations


Polypyrrole (PP)
Polythiophene (PT)
poly (3 alkyl thiophene) (PAT)
cis – poly acetylene (*cis* PA)
trans – poly acetylene (*trans* PA)
poly (p – phenylene vinylene) (PPV)
polydiacetylene – butatrienic form (PDA)
polydiacetylene – acetylenic form (PDA)
N
S
C_mH_{2m+1}
H
C
R_1
R_2
n

Figure 4 Chemical structures of selected conjugated quasi 1D organic polymers.

Table 4 Calculated (calc) and measured (meas) values of the scaling low exponent $\gamma \propto N^{\alpha_\gamma}$ for different conjugated oligomers

Oligomers	$\alpha_{\gamma calc}$	*Remark*	$\alpha_{\gamma meas}$	*Remark*
Polyene oligomers	5	free electron model	2.82	CT polyenes ($\omega = 0$)
		INDO ($\omega = 0$)	3.5	$\lambda_\omega = 1.907$ μm
	3	SCF/STO-3G	2.3	Symmetric A-A
	3.27	SCF/3-21G		THG 1.907 μm
	3.14	$N = 2$	3.3	Asymmetric D-A
	3.67	$N = 6$, decrease		THG 1.907 μm
	3.98	For $N > 6$ DVB-PPP	4.4	Symmetric D-D
				EFISH 1.34 μm
				no saturation up to $N = 14$
	3.8	neutral solitons		
	3.85	charged polarons		
	6.32	*trans* form		
	5.4	*cis* form		
	4.7			
Thiophene oligomers	4.5	CNDO $N < 6$	4.05	DFWM in solutions
		Saturation $N > 6$	4.54	EFISH in solid solutions $N = 3, 5, 6$
			3.4	THG 1.907 μm

of $\omega_\sigma, \omega_1, \omega_2, \omega_3$ fields, the bulk susceptibility is given by:

$$\chi^{(3)}(-\omega_\sigma; \omega_1, \omega_2, \omega_3) = NF\gamma_{xxxx}(-\omega_\sigma; \omega_1, \omega_2, \omega_3) \times \langle \cos^4 \Phi \rangle \qquad [18]$$

where F is the total field factor and Φ is the angle between the polarization direction of $\omega_\sigma, \omega_1, \omega_2, \omega_3$ fields and a chosen direction in the laboratory reference frame. The value of $\langle \cos^4 \Phi \rangle$ varies between 0.2 for an isotropic distribution of polymer chains and 1 for perfectly aligned, respectively. It gives a factor of 5 difference in the macroscopic $\chi^{(3)}$ susceptibility. Some examples of third-order NLO susceptibilities for representative conjugated polymers are given in Table 6. These were obtained by third-harmonic generation technique which measures the fast, electronic contribution to $\chi^{(3)}$.

Table 5 Molecular off resonance second hyperpolarizability γ for selected organic molecules

Molecule	*$\gamma(-3\omega; \omega, \omega, \omega)$ 10^{-50} m^5/V^2*	*λ_{meas} nm*
Carbon tetrachloride	5.1	1064
	4.7	1907
Chloroform	3.8	1064
	3.2	1907
Acetone	2.5	1064
	2.6	1907
Methanol	1.16	1064
	1.21	1907
Ethanol	1.8	1064
	2.1	1907
Propanol	2.4	1064
	2.5	1907
Water	0.46	1064
Nitrobenzene	9.2	1907
Chlorobenzene	5.8	1907

Calibrated with silica value: $\chi^{(3)}(-3\omega; \omega, \omega, \omega) = 3.9 \times 10^{-22}$ m^2/V^2 at 1907 nm.

Two-Photon Absorbing Materials

Two-photon absorbing (TPA) materials are a special class of third-order NLO materials exhibiting a complex Kerr susceptibility $\chi^{(3)}(-\omega; \omega, -\omega, \omega)$. In this case, the nonlinear refractive index, derived from eqn [1] is complex too.

$$n = n_0 + n_2 I = n_0 + (n_2^r + \kappa_2)I \qquad [19]$$

where I is the light intensity, n_2^r is the real part and κ_2 is the imaginary part (nonlinear extinction coefficient) of the nonlinear index of refraction, respectively. The nonlinear index of refraction is directly related to the Kerr susceptibility $\chi^{(3)}(-\omega; \omega, -\omega, \omega)$:

$$n_2 = \frac{3\chi^{(3)}(-\omega; \omega, -\omega, \omega)}{4\varepsilon_0 c n_0^2} \qquad [20]$$

where c is the light velocity. If $\chi^{(3)}(-\omega; \omega, -\omega, \omega)$ is complex (close to a resonance) then n_2 is complex too and the light beam propagating in such a medium in direction z is attenuated through the two-photon absorption process:

$$I(z) = I_0 \, e^{-(\alpha_L + \alpha_{TPA} I)z} \qquad [21]$$

Table 6 Resonant and nonresonant values of cubic susceptibility $\chi^{(3)}$ for selected organic materials

Material	*Form*	*λ_{meas} nm*	*$\chi^{(3)}(-3\omega; \omega, \omega, \omega)$ 10^{-22} m^2/V^2*	*Remark*
PDA-PTS	Single crystal	1890	119 (70) × 10^3	∥ chain, 3ph
			<1400	⊥ chain
		2620	22.4 (14) × 10^3	∥ chain
			<280	⊥ chain
PDA-TCDU	Single crystal	1890	9.8 (7) × 10^3	∥ chain
			<70	⊥ chain
		2620	51.8 (20) × 10^2	∥ chain
			<40	⊥ chain
DEANS	Single crystal	1900	1.4 × 10^4	∥ (mol. axis)
			127	⊥ (mol. axis)
PDA-AFA	LB film (blue)	1350	7.8 (1.4) × 10^3	2ph
PDA-AFA	LB film (blue)	1907	11.6 (1.2) × 10^3	3ph
PA	Isotropic oriented	1907	78.4 (22) × 10^4	3ph
			2.4 × 10^6	3ph
PDA-C_4UC_4	Oriented film	1907	2.9 × 10^4	∥ chain, 3ph
			3 × 10^2	⊥ chain
C_{60}	Isotropic film	1064	11.5 (1.1) × 10^3	3ph
C_{70}	Isotropic film	1420	13 (1.4) × 10^3	3ph
PPV	Isotropic film	1450	1.96 × 10^4	3ph

Numbers in brackets are standard deviations. Data calibrated with silica: $\chi^{(3)}(-3\omega;\omega,\omega,\omega) = 3.9 \times 10^{-22}$ m^2/V^2; 2ph, two photon resonance enhancement; 3ph, three photon resonance enhancement; for chemical structures see Figure 4.

Table 7 Two photon absorption cross-sections σ_{TPA}, maximum TPA wavelength (λ_{max}), measurement wavelength (λ_{meas}), pulse duration and measurements technique for a series of organic molecules

Molecule/material	*Chemical structure*	*Solvent*	λ_{max}^{TPA} *[nm]*	σ_{TPA} *[GM]*	*Pulse duration*	λ_{meas} *[nm]*	*Measurement technique*
BDBAS (Bis(di-*n*-butylamino)stilbene)		Toluene	600	310	4 ps	600	NLT
				9300	5 ns	600	
				1000	5 ns	700	
			600	210	5 ns	600	TPF
				6	5 ns	698	
				110	100 fs	620	
		Acetone		17 700	5 ns	600	NLT
		Toluene	755	10 000	5 ns	700	NLT
				17 000	5 ns	755	
				290	4 ps	700	
			730	300	5 ns	698	TPF
				790	5 ns	730	
BDPAS (Bis(diphenylamino)stilbene)		Toluene		13 000	5 ns	700	NLT
				110	4 ps	700	
Trans-stilbene		Toluene	514	12	5 ns	514	TPF
		Toluene	730	995	5 ns	730	TPF
			~725	635	100 fs	725	
		Toluene	730	900	5 ns	730	TPF
			~725	680	100 fs	725	

Table 7 (*Continued*)

Molecule/material	*Chemical structure*	*Solvent*	λ_{max}^{TPA} *[nm]*	σ_{TPA} *[GM]*	*Pulse duration*	λ_{meas} *[nm]*	*Measurement technique*
		Toluene	775 ~750	1250 1270	5 ns 100 fs	775 750	TPF
		Toluene	835 810	1940 3670	5 ns 100 fs	835 810	TPF
		Toluene	825 940 815 910	480 620 650 470	5 ns 100 fs	825 940 815 910	TPF
		Toluene	970	1750	5 ns	970	TPF
		Toluene	975 945	4400 3700	5 ns 100 fs	975 945	TPF

		Toluene	~800	450	5 ns	800	TPF
CZ-DTT-CZ (2,6 -Bis [2-(9-ethylcarbazol-3-yl) vinyl] thiopheno [3′,2′-2,3] thiopheno [4,5-b] thiophene)		1,1,2,2-Tetra chloro-ethane		105 000	8 ns	810	NLT
CZ-DTT-OX (2-[2-(4-(5-(4-*tert*-Buthyl phenyl-1,3,4-oxadiazol-2-yl) phenyl) vinyl)-6-[2-(9-ethyl carbazol-3-yl) vinyl] thiopheno [3′,2′-2,3] thiopheno [4,5-b] thiophene)		1,1,2,2-Tetra chloro-ethane		33 500	8 ns	810	NLT
TP-DTT-TP ([4-(2-(6-(2-(4-Diphenylamino) phenyl)vinyl) thiopheno [2′,3′-4,5] thiopheno [3,2-b] thiophen 2-yl-vinyl) phenyl] diphenylamine)		1,1,2,2-Tetra chloro-ethane		199 000	8 ns	810	NLT
TP-DTT-OX ([4-(2-(6-(2-(4-(5-(4-*tert*-Buthylphenyl-1,3,4-oxadiazol-2-yl)) phenyl) vinyl) thiopheno [2′,3′-4,5] thiopheno [3,2-b] thiophen 2-yl)-vinyl) phenyl] diphenylamine)		1,1,2,2-Tetra chloro-ethane		119 000	8 ns	810	NLT
Biphenyl				80			Theoretical calculus
Terphenyl				330			Theoretical calculus

Table 7 (*Continued*)

Molecule/material	*Chemical structure*	*Solvent*	λ_{max}^{TPA} *[nm]*	σ_{TPA} *[GM]*	*Pulse duration*	λ_{meas} *[nm]*	*Measurement technique*
Sexiphenyl				2090			Theoretical calculus
AF 50		Tetrahydro-furan Benzene		11 560 19 300	8 ns	800	NLT
AF 80		Tetrahydro-furan		6840	8 ns	800	NLT
ASPT		Poly hydroxyethyl metacrylate		12 000	10 ns	1064	NLT
DEANST		Tetrahydro-furan		200	46 ps	1064	KE
Rhodamine B		Methanol		50	100 fs	730	TPES
DR1 (4-[*N*-ethyl-*N*-(2-hydroxyethyl)] amino-4′-nitroazobenzene (dispersed red 1))		Tetrahydro-furan		102	42 ps	1064	KE

KE, optical Kerr effect; NLT, nonlinear transmission; TPF, two photon fluorescence; TPS, two photon excitation spectroscopy.
1 GM = 10^{-50} cm^4 s/photon-molecule.

Table 8 Two photon absorption coefficients for different molecules and extrapolated bulk values

Molecule	*α_{TPA} cm/GW*	*λ_{max} nm*	*λ_{TPA} nm*	*Concentration g/l*	*Solvent*	*Bulk value cm/GW*
DR 1	0.8	490	835	70	THF	11.4
DBANS	1.1	450	808	70	THF	15.7
DCNP	0.06	460	920	30	THF	2.3
DEANST	0.64	440	920	105	THF	6.1
DCM	0.1	480	950	11	DMSO	9.1
PDA-PTS	80	620	1064 not max of λ_{TPA}	Bulk	Single crystal	80
PDA-PTS	800	620	925	Bulk	Single crystal	800
Poly(3-octyl thiophene)	0.27	435 (142)	720 (94)	25	THF	9.6
Poly(3-octyl thiophene) regioregular	0.85	550 (170)	730 (70)	11.2	THF	76

λ_{max} corresponds to the maximum linear and λ_{TPA} to the maximum nonlinear absorption wavelengths, respectively, DCNP: 3-(1,1-dicyanoethenyl)-1-phenyl-4,5-dihydro-1H-pyrazole, for other molecules see Figures 4 and 5 and preceding tables.

where α_{L} is the linear and α_{TPA} is the two-photon absorption coefficient, respectively. The last coefficient can be explicitly expressed by the imaginary part of the nonlinear index of refraction:

$$\alpha_{\mathrm{TPA}} = \frac{2\pi\kappa_2}{\lambda_\omega} \qquad [22]$$

where λ_ω is the wavelength of the propagating beam. On the molecular level one also defines the two-photon absorption cross-section given by

$$o_{\mathrm{TPA}} = \frac{\hbar\omega}{N}\alpha_{\mathrm{TPA}} \qquad [23]$$

where N is the number density of molecules. The values of TPA absorption cross-sections and two-photon absorption coefficients for selected organic molecules and solids are listed in Tables 7 and 8, respectively.

Photorefractive Materials

The photorefractive effect consists of the generation of a refractive index grating in an NLO material by its inhomogeneous illumination. This is a necessary condition but not a sufficient one. The sufficient condition consists of the possibility of creating the space charge field, which combined with the applied external field, leads to the refractive index modulation through the Pockels effect. In that case, the refractive index grating is phase mismatch with the intensity grating, leading to the transfer of photons from one beam to another, as occurs in two-beam coupling experiments, and thus applies to light amplification. Although the photorefractive effect was first observed in ferroelectric single crystals, the researchers at IBM demonstrated, at the beginning of 1990s, the photorefractive effect in organic composite materials. However, the main contribution in these materials comes from the rotational mobility of nonlinear optical (NLO) chromophores under the applied external electric field. Thus, to exhibit a photorefractive effect, the organic material has to possess the following properties:

(i) charge generation and separation capacity;
(ii) charge mobility;
(iii) linear electro-optic (Pockels) effect; and
(iv) rotational mobility.

Composite Materials

The different properties satisfying the above requirement to exhibit a photorefractive effect, are obtained by mixing together four types of molecules:

(i) photoconducting polymer;
(ii) highly second order nonlinear CT molecules;
(iii) photoensitizer for charge generation under illumination; and
(iv) plasticizer, lowering the glass transition temperature, thus increasing the rotational mobility.

Some examples of different types of molecules used are shown in Figure 5. Although these structures exhibit large exponential gain coefficients Γ and high diffraction efficiencies η, their main disadvantage consists of slow, seconds-duration response times


PVK
PBPES
BisA-NAS
Photoconducting polymers
DHD
MTFNS
EPNA
DEANST (R=H), FDEANST (R=F)
Second order NLO chromophores
TNFDM
C60
TNF
Photosensitizers
ECZ
BBP
TCP
Plasticizers

Figure 5 Chemical structures of photoconducting polymers, CT chromophores, photosensitizers and plasticizers commonly used for the fabrication of photorefractive polymers.

Table 9 Photorefractive properties of selected single crystals at zero external field, composite photorefractive polymers and liquid crystals

Structure	*Form*	*Thickness* μm	*Composition w%*	*Laser intensity W/cm*^{2}	*Exponential gain* Γ *cm*$^{-1}$	*Electric field V/*μm	*Response time s*	*Diffraction efficiency %*	λ_{meas} *nm*
COANP: TCNQ	Single crystal			0.08			100–1000 depending on grating period Λ		514.5
MNBA	Single crystal			0.1	2		10–100		514.5
DMNPAA/PVK/TNF/ECZ	Composite material	105	50: 33: 16: 1		220 (p-polarized) -40 (s-polarized)	90	1	86	514.5
Doped: 5 CB/C_{60}	Composite material	25	95: 5		2890	0.07	0.3		514.5
Doped: 8 OCB/5 CB /PER/NI	Composite material	37			640	0.04	0.04		514.5
SCLCP/E7/C_{60}	Composite material	50	49.975: 49.975: 0.05		600	0.7	3.5		632.8
PVA/E44/C_{60}	PDLC	25				40	On: 8 s Off: >3 days	52	
PMMA/E49/ETZ/TNF	PDLC	53	45: 33: 21: 1		41	22		8	675
POT/LC	HPCPLC	10			965	0.6	0.011	26	514.5
POT/DR1/LC	HPCPLC	10			2600	0.6	0.010	31	514.5
PVK/TNF/LC	HPCPLC	10			3700	0.9	0.010	45	514.5

LC, liquid crystals; PDLC, polymer dispersed liquid crystals; HPCPLC, hybrid photoconducting polymer–liquid crystal; COANP-2-cyclooctalamino-5 nitropyridine, TCNQ, 7,7,8,8-tetracyanoquinodimethane; MNBA4′, nitrobenzylidene-3 acetamino-4-methoxyaniline; 5-CB-4′, (*n*-octyloxy)-4-cyanobiphenyl; 8OCB-4′, (*n*-octhyloxy)-4-cyanobiphenyl; PER, perylene; NI, *N*,*N*-di(*n*-octyl)1,4,5,8-naphtalenediimide; SCLCP, side chain liquid crystalline polymer (PMMA-4-cyanophenyl benzoate); E7, E44, E49, commercial LC mixtures (Merck, Germany); other molecules in **Figure 5** and **Tables 2** and **3**.

and require large external operation electric fields (~100 V/μm).

Photorefractive Liquid Crystals

In order to improve the performances of organic photorefractive materials the use of nematic liquid crystals was proposed as active media. These materials exhibit a large rotational mobility, requiring a relatively small electric field with response time of milliseconds. The reorientation of domains requires 2 ÷ 3 orders of magnitude electric fields as compared with the composite materials (reorientation of individual molecules). Several types of structures of liquid crystal based photorefractive structures are realized, such as:

- composite materials in which the liquid crystals mesogens are NLO chromophores;
- polymer dispersed liquid crystals (PDLCs);
- hybrid photoconducting polymers – liquid crystals (HPCPLCs), in which the rotational mobility is separated from the charge mobility. Moreover the use of photoconducting polymer allows the modulation of the electric field on the liquid crystal layer, enhancing the effect.

The performances of different, representative, organic photorefractive structures are listed in Table 9.

See also

Nonlinear Optics, Basics: Photorefraction; $\chi^{(2)}$–Harmonic Generation. **Polarization:** Introduction.

Further Reading

Agranovich VM and La Rocca GC (eds) (2002) Organic Nanostructures: Science and Applications. *Proceed. International School of Physics "Enrico Fermi", Course CXLIX*. Amsterdam: IOS Press.

Bosshard Ch, Sutter K, Pretre Ph, Hulliger J, *et al.* (1995) In: Kajzar F and Garito AF (eds) *Organic Nonlinear Optical Materials*, *Advances in Nonlinear Optics*, vol. 1. Amsterdam: Gordon and Breach Publishers.

Bredas JL and Silbey R (eds) (1991) *Conjugated Polymers*. Dordrecht: Kluwer Academic Publishers.

Charra F, Agranovich V and Kajzar F (2003) *Organic Nanophotonics*. NATO Science Series 2. Dordrecht: Kluwer Academic Publishers.

Chemla DS and Zyss J (eds) (1987) *Nonlinear Optical Properties of Organic Molecules and Polymers*. Orlando, FL: Academic Press.

Graja A, Bulka B, Kajzar F (eds) (2002) *Molecular Low Dimensional-and Nano-Structured Materials for Advanced Applications*. NATO Science Series 2. Dordrecht: Kluwer Academic Publishers.

Hornac LA (ed.) (1992) *Polymers for Lightwave and Integrated Optics. Technology and Applications*. New York: Marcel Dekker, Publishers.

Kajzar F and Agranovich VM (eds) (2000) *Multiphoton and Light Driven Multielectron Processes in Organics: New Phenomena, Materials and Applications*. Dordrecht: Kluwer Academic Publishers.

Kajzar F and Reinisch R (eds) (1998) *Beam Shaping and Control with Nonlinear Optics*. NATO ASI Series, Series B: Physics, vol. 369. New York: Plenum Press.

Kajzar F and Swalen J (eds) (1996) *Thin Films for Waveguiding Nonlinear Optics*. Amsterdam: Gordon and Breach Scientific Publishers.

Kajzar F, Agranovich VM and Lee CY-C (1996) *Photoactive Organic Materials: Science and Application*. Dordrecht: Kluwer Academic Publishers.

Kuzyk M and Dirk C (eds) (1998) *Characterization Techniques and Tabulations for Organic Nonlinear Optical Materials*. New York: Marcel Dekker.

Lee KS and Wegner G (eds) (2003) *Polymers for Photonics Applications II: Nonlinear Optical, Photorefractive and Two-Photon Absorption Polymers*. Advances in Polymer Sciences 161. Berlin: Springer-Verlag.

Lessard R and Franke H (eds) (1997) *Materials Characterization and Optical Probe Techniques*. Critical Reviews of Optical Science and Technology, vol. CR69. Bellingham: SPIE.

Messier J, Kajzar F, Prasad P and Ulrich D (1989) *Nonlinear Optical Effects in Organic Polymers*. Dordrecht: Kluwer Academic Publishers.

Messier J, Kajzar F and Prasad P (1991) *Organic Molecules for Nonlinear Optics and Photonics*. Dordrecht: Kluwer Academic Publishers.

Miyata S and Sasabe H (eds) (1997) *Poled polymers and their Application to SHG and EO Devices*. Amsterdam: Gordon and Breach Scientific Publishers.

Prasad PN and Williams DJ (1991) *Introduction to Nonlinear Optical Effects in Molecules and Polymers*. New York: Wiley.

Richardson T (ed.) (1999) *Functional Polymers and Polymeric Materials*. Chichester, UK: John Wiley & Sons.

MICROSCOPY

Contents

Overview
Confocal Microscopy
Imaging Multiple Photon Fluorescence Microscopy
Interference Microscopy
Nonlinear Microscopy
Phase Contrast Microscopy

Overview

C J R Sheppard, National University of Singapore, Singapore

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The basic construction and imaging properties of the optical microscope, one of the most important optical instruments, are described. But the restrictive meaning of a microscope as a device that the user looks down to see a magnified image is far from the present terminology that includes scanning systems (where the image is stored in a computer), nonvisible radiation, such as electrons or X-rays, and a variety of different contrast mechanisms.

According to the *Oxford English Dictionary* a microscope is 'an instrument magnifying objects by means of lenses so as to reveal details invisible to the naked eye'. Thus, basically a microscope forms a magnified image of an object. The first microscopes used visible light and formed an image showing variations in the intensity of light scattered by the object. This intensity is in general related to the optical properties of the object in a complicated way.

Nowadays there are many different types of microscope. Our understanding of a microscope must therefore be generalized in the following ways.

- The microscope may not be a conventional imaging system using lenses or mirrors. For example, it may be a scanning imaging system. A confocal system is a combination of a conventional and a scanning system. Another important category of microscopes is that of probe microscopes, including near-field optical microscopes. Some probe microscopes, for example the atomic force microscope (AFM) do not even seem at first glance to rely on the direct use of radiation.
- The microscope may not use visible light, but other electromagnetic radiation, or even other forms of radiation.
- The image can be formed using a variety of different contrast mechanisms. Some of these, such as phase contrast, are designed to image particular optical properties of the sample. Others image the generation of a form of radiation when the object is stimulated by another form of radiation. In particular, in principle, virtually any form of spectroscopy can be the basis of building up an image by measuring the spatial variations in the signal.

Different Forms of Microscopes

The Conventional Microscope

In a simple microscope, an objective lens forms a real, magnified, and inverted image of an object. In a compound microscope, an eyepiece is added, forming a virtual image that is viewed by eye to give real image on the retina. The eye can be replaced by CCD camera to record moving or still images. In early microscopes, the objective lens and eyepiece are mounted in the two ends of a brass tube. The objective screws into the tube using an RMS (Royal Microscopical Society) thread (0.8″ Whitworth 36 threads per inch), until its mounting face is flush with the end of the tube. The length of the tube is the mechanical tube length. The distance from the mounting face of the objective to the plane of the real image is the optical tube length, which varied according to different manufacturers in the range 160–210 mm. Now most objectives have infinity tube length, so that they collimate the light from the object. The collimated light is brought to a focus by an additional tube lens. An objective of correct tube length should always be used as otherwise spherical aberration is introduced. As the objective, tube lens, and eyepiece are designed together as a system, great care should be exercised when mixing components from different manufacturers.

Abbe showed that in order to form a perfect lateral image the objective must satisfy a different condition called the Herschel condition. Otherwise the image of an off-axis point will suffer from coma. An aberration-free system satisfying the sine condition is called an aplanatic system. A microscope produces a three-dimensional (3D) image of a 3D object. A point of the object closer to the lens appears further from the lens in the image. If the lateral magnification is M, the longitudinal magnification is approximately equal to M^2. However, it can be shown that it is impossible to devise an instrument that can produce a perfect 3D image of a 3D object, because to have a perfect transverse image the system must satisfy Abbe's sine condition, but to have a perfect axial image the system must satisfy the Herschel condition. These two conditions are not mutually compatible. Actually, we find that the longitudinal magnification is not exactly equal to M^2, and is not even constant in space. Different depths of the object are imaged differently: the microscope objective only produces a good image for one plane of focus, and other planes will exhibit spherical aberration. However, all of these problems can be overcome by bringing the part of the object under observation into focus, without refocusing the eye or other detector. A 3D image can thus be generated by scanning the object stage in the axial direction, and recording a stack of images from different depths in a computer. For modern objectives of infinite tube length, focusing can be alternatively achieved by piezoelectric scanning of the objective lens.

Resolution

For an object consisting of a single bright point object in a dark background, the image produced by a perfect microscope, according to paraxial diffraction theory, is the so-called Airy disk, consisting of a bright central spot, surrounded by a series of rings. The intensity in a meridional cross-section through the Airy disk is the same for any aperture of objective, or wavelength of light, but its width varies. The intensity of the first bright ring is 1.75% of that at the peak. The radius of the first dark ring of the Airy disk is

$$r_0 = \frac{0.61\lambda}{n \sin \alpha} \qquad [1]$$

where λ is the wavelength, n is the refractive index of the immersion medium, and α is the angle subtended at the edge of the objective aperture. The radius depends on $n \sin \alpha$, which is called the numerical aperture and should be as large as possible for good resolution. Thus, high-magnification lenses often use an immersion fluid, usually oil with a refractive index of 1.518 (ISO 8036/1).

The optical coordinate v is defined as

$$v = \frac{2\pi}{\lambda} rn \sin \alpha \qquad [2]$$

so that the dark ring of the Airy disk occurs at a value of v of $2\pi \times 0.61 = 3.83$. Resolution is sometimes expressed in terms of the full width at half maximum (FWHM) of the image of a point object, which is 3.232 in optical coordinates. A full nonparaxial theory does not give a very different figure.

Resolution of a microscope is often specified by two-point resolution, which describes whether the image of two points can be distinguished from that of a single point. According to the Rayleigh criterion of two-point resolution, two points are just resolved if the second point is placed on the first dark ring of the first. The separation is then $0.61\lambda/(n \sin \alpha)$. A cross-section through the image in an incoherent optical system of two bright point objects of equal strength and different separations is shown in Figure 1. The intensity in the image between the points decreases as the separation is increased. The ratio of the intensity midway between the points to that at the points for the Rayleigh criterion to be satisfied is then found to be 0.735.

The concept of resolution should be distinguished from sensitivity or precision. An object much smaller than the resolution limit can still be detected, perhaps weakly, in a microscope: this detection of weak contrast depends on the sensitivity of the microscope rather than its resolution. The size of an object can also be measured with a precision much greater than the resolution of the microscope.

Illumination

If the object is not self-luminous, in order to be imaged in a microscope it must be illuminated. A semitransparent object, such as a biological slice, is illuminated in transmission. For observation of bulk objects, or surfaces, we use illumination in the reflection geometry, called epi-illumination. Either a tungsten halogen lamp or an arc source is usually used. In critical illumination, the source is focused on to the object by a condenser lens. The disadvantage of this approach is that variations in emission of the source are imaged directly into the image.

Cheaper microscopes avoid this problem by using a diffuser. Better microscopes use instead the Köhler illumination system, where the source is placed in the front focal plane of the condenser lens. Figure 2 shows a Köhler illumination system in which the source is imaged into the front focal plane of the condenser lens by another, projector, lens. The system incorporates a separate field stop and aperture stop. In practice, the size of the field stop should be reduced to illuminate as small a region of the object as necessary in order to minimize stray light. An important part of setting up a microscope to operate properly consists in centering the aperture stop of the condenser. This is often done using a so-called Bertrand lens that allows imaging of the aperture stop.



Figure 1 A cross-section through the image of two equal point objects in an incoherent microscope. The separation of the points is that for the Rayleigh criterion to be satisfied, and for changes of ±10, 20% of the Rayleigh separation.

Image formation

The Rayleigh criterion was originally specified for an incoherent optical system. It is thus applicable in fluorescence microscopy, as fluorescence is an incoherent process as two fluorescent point objects fluoresce independently. But for the image of a trans-illuminated object, the resolution depends on the coherence of the illumination. This is controlled by the numerical aperture of the condenser lens as compared with that of the objective. The ratio of these numerical apertures is called the coherence parameter, S, so that

$$S = \frac{n_c \sin \alpha_c}{n \sin \alpha} \qquad [3]$$

For $S = 0$ the illumination is purely coherent, while for $S \to \infty$ imaging becomes purely incoherent, thus corresponding to the Rayleigh criterion, so S should really be called an incoherence parameter. An important in-between case is when $S = 1$, when the apertures of objective and condenser are equal. This is termed matched, full, or complete illumination. According to the generalized Rayleigh criterion, the points are just resolved when the ratio of the intensity midway between the points to that at the points is 0.735, which is called the generalized Rayleigh criterion. We require that the distance between the points is as small as possible when this occurs. The generalized Rayleigh separation is the same for incoherent illumination and for $S = 1$, and corresponds to a distance of $2v_0 = 3.83$ in optical coordinates. Note, however, that for other separations of the points, the ratio is different for these two cases: it is not true, but often erroneously stated, that $S = 1$ corresponds to incoherent imaging. Resolution improves as the aperture of the condenser is increased ($2v_0 = 5.15$ in optical coordinates for coherent illumination) reaching a maximum when $S = 1.46$, when resolution is 9% better than for incoherent imaging ($2v_0 = 3.58$). This maximum in resolution is achieved when the numerical aperture of the condenser is larger than that of the objective, which is not



Figure 2 Geometry of the Köhler illumination system. In practice an arrangement with a smaller number of lenses is usually used.

physically achievable if the objective has the highest possible numerical aperture. Similarly, it is impossible to achieve incoherent illumination with very large objective numerical apertures.

The effect of coherence on the resolution of an image depends on the form of the object, and on the particular resolution criterion employed. In practice, contrast also depends on the aperture of the condenser. Usually, opening the condenser improves resolution, but reduces contrast, so there will be an optimum condenser aperture size.

Abbe theory of microscope imaging

Abbe argued that for coherent illumination of a grating, the grating spectra can be observed in the back focal plane of the objective. The tube lens then forms an image from the grating components. Thus, this is an early description of Fourier optics. The strength of the grating components can be altered in the back focal plane to give various optical effects, such as phase contrast. Abbe's theory was not properly appreciated at the time because it was known that in practice, resolution could be improved by using a larger condenser aperture, which does not give coherent illumination. There was much controversy about the merits of Köhler versus critical illumination, and different sizes of condenser aperture.

We now know that Köhler and critical illumination are in principle equivalent. The aberrations of the condenser lens are not important, so that the source and condenser together behave simply as a partially coherent effective source. Imaging can still be described by Fourier optics within the framework of partially coherent imaging theory.

Although Köhler and critical illumination are equivalent in principle, Köhler illumination is in practice better because of its improved illumination uniformity.

Depth of focus

The longitudinal image of a point object is found to be approximately invariant when expressed in terms of an optical coordinate u, defined as

$$u = \frac{8\pi}{\lambda} zn \sin^2 \frac{\alpha}{2} \qquad [4]$$

The axial resolution, and thus also the depth of focus, varies strongly with aperture. The FWHM for longitudinal imaging is 11.13 in optical coordinates.

Microscope objectives

Because microscope objectives often have large apertures, aberrations will be very strong, unless the objective is designed correctly. The basic design principle for a high aperture lens is the aplanatic front element (Figure 3). It is found that all rays from a point A in a sphere of refractive index n, where A is a distance r/n from its center, appear to come from a point B, distance rn, without any aberration. This principle is used by employing a front element that has one surface of the same radius of curvature as the sphere. The front surface is a sphere centered on A (Figure 3b), so that the rays are not deviated on crossing it.

A low-power achromat uses just two components with different optical dispersion to cancel chromatic aberration and correct for other aberrations (an achromatic doublet). For higher powers, two separated doublets are necessary. For the highest apertures, an aplanatic front is used. However, this can never converge the light, but only makes it less divergent. It is thus used together with an achromatic doublet. For oil immersion, the interface between the oil and the front element is not very important, so it is made planar to simplify manufacture. In practice, it is



Figure 3 The principle of the aplanatic front: (a) an aplanatic surface; (b) a meniscus lens that acts as an aplanatic system.

usually made planar even for a dry lens, and the resulting aberrations cancelled out elsewhere in the objective. Apochromats, corrected for three colors, use more elements, which may include two or more stages of aplanatic front. The final objective thus consists of a number of elements that must be accurately aligned relative to one another. The objective is adjusted by the manufacturer to give a good star image (image of a point object). First a spacer is selected to optimize spherical aberration. Then a sleeve is adjusted to make the objective parfocal with others. Finally a screw is used to center the assembly to remove coma.

Conventional and Scanning Microscopes

Conventional microscope

Various different types of transmission microscope are illustrated in Figure 4. We consider image formation in a conventional microscope as illustrated schematically in Figure 4a, showing a microscope with critical illumination. A large area incoherent source is focused by the condenser lens on to the specimen, illuminating a comparatively large area of the specimen, corresponding to the whole field of view of the objective. Information from each illuminated point in the specimen is simultaneously transmitted by the objective lens to form the primary image. The objective is responsible for forming the image, with the condenser playing only a secondary role in determining the resolution of the system, through control of the coherence of the illumination. Figure 4b shows a conventional microscope in which the image is measured point by point by a detector. In practice this could be achieved by using a CCD detector.

Scanning microscope

An image can be generated by a scanning system, as illustrated in Figure 4c. A probe of light is formed by demagnification of a source, and is scanned over the object in a raster. The transmitted (or reflected) light is detected by a photodetector and thus builds up an image. The size of the probe of light limits the resolution of the system, that is, the smallest detail in the object that can be seen in the image. It should be noted that the magnification of the image is given simply by the ratio of the distance scanned in the image to the distance scanned by the probe. It is thus unrelated to the demagnification of the source. The image magnification can be altered without changing the lens and is not in any way related to the resolution.

It has been shown that the imaging properties of scanning and conventional microscopes are identical under analogous conditions, this being known as the principle of equivalence. This property is based on the principle of reciprocity, which is a very general physical law that holds even with diffraction,



Figure 4 Different geometries of transmission microscope: (a) a conventional microscope; (b) a conventional microscope with a point detector; (c) a scanning microscope; (d) a confocal microscope.

absorption, multiple scattering, and stray light. The principle of equivalence is generally valid except if there are nonreciprocal magnetic or polarization effects, or energy losses involved (such as in fluorescence microscopy, and with inelastic scattering in electron microscopy).

Scanning systems exhibit a number of important advantages over conventional systems. Broadly, these are based on two classes of property. First, in a scanning system the image is in the form of an electronic signal. As a result, this is advantageous for quantitative measurements, as well as for image processing, including image enhancement, image restoration, and image analysis. Second, in a scanning system the object is illuminated by a focused spot, which extends the range of imaging modes available.

Confocal microscope

Finally in Figure 4d, we combine the arrangements of Figures 4b and c to give a confocal scanning optical microscope, in which a point source illuminates just a small region of the object, and a confocal point detector detects light from this illuminated region. If the point source and detector are scanned in unison, a two-dimensional image is generated. However, this system now behaves very differently from the previous ones. The confocal microscope is thus not a special case of the general partially coherent conventional imaging system. From the symmetry of Figure 4d, it is clear that the two lenses play an equal part in the imaging process. This results in an improvement in resolution. In fact, the confocal system behaves as a coherent imaging system, but with a sharper effective point spread function than in a conventional coherent microscope.

Although Figure 4 is drawn for the transmission geometry, in practice most confocal systems operate in the reflection or epi-illumination mode, in which the same objective lens is used both for illumination and detection. For a specimen placed in the focal plane, the properties of confocal transmission and reflection systems are identical. However, once the object is moved from the focal plane, certain differences arise: in particular in confocal reflection a strong optical sectioning effect occurs that allows a single section through a thick object to be imaged. This is the major advantage of the confocal microscope arrangement. Figure 4 also applies equally well to fluorescence imaging. However, in this case, because of the incoherent nature of fluorescence emissions after excitation by coherent light, imaging is then incoherent.

Confocal microscopes can be achieved by using either a point detector, in practice performed by placing a pinhole in front of a photodetector, or by using a coherent detector. Such a coherent detector, sensitive to the amplitude of the incident radiation, is not directly available for light, but is available for acoustic radiation, as in a scanning acoustic microscope. For light, a confocal effect can also be achieved by using an interferometric method to synthesize a coherent detector. Thus, in interference microscopes using the high aperture condenser and objective lenses, an optical sectioning effect arises similar to that in the confocal microscope. Another way of producing a coherent detector is to use a single-mode optical fiber.

Probe Microscopes

Scanning tunneling microscope

The scanning tunneling microscope was the first of the family of probe microscopes, relying on a fundamentally different principle from the usual forms of microscope. A physical tip in the nanometer range is brought close, also in the nanometer range, to a conducting sample. If an electric potential is applied, electrons can tunnel across between the sample and the tip. By scanning the tip mechanically across the sample, an image can be generated with a resolution in the subnanometer range. The surface topography can also be measured with subnanometer sensitivity. While interference microscopy can measure surface topography with subnanometer sensitivity, in this case the profile is averaged over the lateral resolution of the microscope, of the order of the wavelength in dimensions. The scanning tunneling microscope can image individual atoms. The signal is related to the work function of the material. Altering the bias voltage allows the band structure of the material to be investigated.

Atomic force microscope

In the atomic force microscope, the force between the surface and the tip is measured using a cantilever beam and used to build up an image. Atomic force microscopy can be performed in either a contact or noncontact mode. It can be used with insulating specimens. Optical methods, often using a position-sensitive detector, are used to measure displacements of the cantilever.

Near-field scanning optical microscope (NSOM)

In a near-field scanning optical microscope, a very small tip or aperture is scanned relative to the specimen to attain resolution greater than the classical limit set by the wavelength of the radiation. As Figure 5 shows, various different designs of near-field microscope have been proposed. It is evident that



Figure 5 Different forms of near-field microscope: (a) illumination-mode NSOM; (b) collection-mode NSOM; (c) a near-field probe used for both illumination and collection in a confocal arrangement; (d) photon tunneling microscope (PTM). Reproduced with permission from Sheppard CJR (1978) The scanning optical microscope. *The Physics Teacher* 16: 648–651. © 1978 American Association of Physics Teachers.

these again form into the conventional/scanning categories described earlier. The sample can be illuminated using the near-field probe, as in Figure 5a. This is called the illumination-mode NSOM. Or the sample can be uniformly illuminated, and a signal detected using a near-field probe as in Figure 5b, giving a collection-mode NSOM. Or a confocal arrangement can be used, with a near-field probe used for both illumination and collection (c). In this case, an uncoated tip can be used; as otherwise the detected signal will be very small. Finally, Figure 5d shows the photon tunneling microscope (PTM), in which the sample is illuminated with evanescent waves produced by total internal reflection and an uncoated tip used to probe the evanescent field in the presence of the sample.

Different Types of Radiation

Electromagnetic Radiation

UV radiation and X-rays

The first microscopes used visible light, but, in fact, we do not need to use visible light, but can use any electromagnetic radiation, over a broad range of different available wavelengths. In Figure 6 we show the wavelength of the electromagnetic spectrum, illustrating how the wavelength in air varies with frequency. Instead of using visible light, shorter wavelengths allow greater resolution to be achieved. Ultra-violet light is commonly used to excite fluorescence. X-rays have also successfully been used to image biological samples.

IR and microwave radiation

In the longer wavelength region, infra-red radiation is used for observation of semiconductors or for molecular spectroscopic imaging. Imaging of emitted midinfra-red radiation can show up variations in temperature, such as hot spots in semiconductors. Microwaves have also been used, but resolution is limited by the long wavelength. For this reason microwaves (and mid-IR) have also been used for near-field microscopy.

Other Radiation

Electron microscope

The other important class of radiation that can be used for illumination is matter waves. The most common of these, of course, is electrons, the wavelength of which, as a function of acceleration voltage, is shown in Figure 7. The bend in the curve at very high voltages is caused by relativistic effects. The wavelength of the electrons is very small: even for 100 V electrons, the wavelength is only 0.1 nm. But aberrations caused by the electron lenses limit



Figure 6 The wavelength of different forms of electromagnetic radiation and acoustic radiation. Reproduced with permission from Sheppard CJR (2002) The generalized microscope. In: Diaspro A (ed.) *Confocal and Two-Photon Microscopy: Foundations, Applications and Advances*, pp. 1–18. New York: Wiley-Liss.



Figure 7 The wavelength of matter waves (electrons and protons) as a function of accelerating voltage. Reproduced with permission from Sheppard CJR (2002) The generalized microscope. In: Diaspro A (ed.) *Confocal and Two-Photon Microscopy: Foundations, Applications and Advances*, pp. 1–18. New York: Wiley-Liss.

resolution so that at present atomic resolution is only just achievable, even with much higher voltages.

In a transmission electron microscope (TEM), a beam of electrons is produced by an electron gun. The specimen is illuminated via a condenser lens (or lenses). Usually these are magnetic lenses in which a current in a coil produces a magnetic field that focuses the electrons. The electrons that are transmitted through the specimen are then focused by a series of lenses to form a final image that can be viewed directly on a phosphor screen. An X-ray detector can be used to characterize the elements in the specimen. An electron-energy-loss spectrometer, together with a detector, can measure the energy of the electrons in a particular region of the image.

Other matter radiation

Instead of electrons, other particle beams can be used for illumination. Figure 7 shows the wavelength of a beam of protons, as function of the accelerating voltage. Because of the larger mass of protons, relativistic effects are not apparent for protons in the curve in Figure 7. Microscope images have also been formed using ions, and even neutral particles such as neutrons. Neutral atom microscopes are also under development.

Acoustic radiation

Instead of electromagnetic waves, acoustic radiation can be used to form a scanning acoustic microscope (SAM). Ultrasonic waves are focused into a water immersion medium. Mechanical scanning is again used to build up an image. Figure 6 shows the wavelength of the acoustic wave as a function of frequency. By using microwave frequencies, wavelengths, and therefore resolution, in the submicron range, can be generated. The SAM acts as a confocal microscope because the detector is sensitive to the amplitude of the acoustic wave. The acoustic microscope provides information on variations in the elastic properties (viscosity and elasticity) of the sample.

Different Contrast Mechanisms

The bright field microscope detects the intensity of the light transmitted through the object. A microscope with a condenser aperture of appreciable size behaves as a partially coherent system, and the image will, in general, depend on the phase of the light coming from the object as well as its intensity. Many objects are weakly scattering, so the contrast of this phase information is weak. In this case, the microscope effectively images variations in the transmittance or reflectance of the sample. Different designs of microscope can be used to image various properties of the object, thus providing new and complementary information. Phase contrast microscopy provides but one example of a different contrast mechanism. In fact, in general, any physical or chemical interaction of the illuminating radiation with the sample can be used as the basis for a contrast mechanism. These different contrast mechanisms can be performed in either a conventional or scanning arrangement, or in a confocal system.

Phase Contrast Microscopy

Phase contrast is a widely used technique in both biological microscopy (in transmission) and materials microscopy (in reflection). Its importance in biological microscopy stems, firstly, from the fact that contrast may otherwise be too weak to be visible, but secondly because the phase variations are caused by changes in optical thickness, related to physical density. In reflection microscopy, phase is related to surface height variations, but also depends on the optical material properties of the sample.

Polarization Microscopy

The polarization state of light transmitted through or reflected from a sample can also be changed. This change is detected in polarization microscopy, for example by placing the sample between crossed polarizers. The birefringence detected can be either material birefringence, or form birefringence (caused by the shape of the microstructure). Polarization microscopy is widely used in biological microscopy, and in mineralogy.

Fluorescence Microscopy

In fluorescence microscopy, electrons excited by illumination decay to the ground state and emit photons of light. Autofluorescence is natural fluorescence of the sample. Fluorescent dyes can be used as labels for particular biological or chemical constituents. Fluorescence microscopy is usually performed in the epi-illumination geometry to assist rejection of light from the source. Often it is performed in a confocal microscope, allowing 3D localization of the fluorescent labels.

Raman Microscopy

Raman spectroscopy can be performed on a microscopic scale to produce images of presence of particular molecular bonds. It is usually performed in a scanning system, often of the confocal type.

This is one example of the wider class of spectroscopic microscopies: in principle, any form of spectroscopy can be used as the basis for a microscope contrast mode.

Nonlinear Microscopy

Another class of contrast mechanisms is based on nonlinear optical interactions. Again, any nonlinear mechanism can be used as the basis for a contrast mechanism. These include two- (or multiphoton) fluorescence, second- (or higher-order) harmonic generation, sum or difference frequency generation, and coherent anti-Stokes Raman scattering (CARS). Probably other nonlinear optical mechanisms will be exploited in microscopy in the future.

Other Contrast Mechanisms

The contrast mechanisms described above, all rely on illumination and detection of light. But in many other modes, radiation of one form can be converted into another. These include cathodoluminescence microscopy (electrons to light), X-ray microanalysis (electrons to X-rays), photo-emission microscopy (light, usually UV, to electrons), photo-acoustic microscopy (light to ultrasonics), photothermal microscopy (light to thermal waves), optical or electron beam induced current (OBIC/EBIC). Again, in many of these, the illuminating or emitted radiation can be focused, or a combination can be used in a confocal arrangement.

See also

Microscopy: Confocal Microscopy; Imaging Multiple Photon Fluorescence Microscopy; Interference Microscopy; Nonlinear Microscopy; Phase Contrast Microscopy.

Further Reading

Born M and Wolf E (1999) *Principles of Optics*, 7th edn. Cambridge: Cambridge University Press.

Bradbury S and Bracegirdle B (1997) *Introduction to the Optical Microscope*. Oxford: Bios Scientific Publishers.

Inoue S and Spring KR (1997) *Video Microscopy: The Fundamentals*, 2nd edn. New York: Plenum.

Martin LC (1966) *Theory of the Microscope*. London: Blackie.

Paesler MA and Moyer P (1996) *Near-Field Optics: Theory, Instrumentation, and Applications*. New York: Wiley InterScience.

Pluta M (1988) *Advanced Light Microscopy, Volume 1: Principles and Basic Properties*. Amsterdam: Elsevier.

Sheppard CJR (1987) Scanning optical microscopy. In: Barer R and Cosslett VE (eds) *Advances in Optical and Electron Microscopy*, vol. 10, pp. 1–98. London: Academic Press.

Sheppard CJR (2002) The generalized microscope. In: Diaspro A (ed.) *Confocal and Two-Photon Microscopy: Foundations, Applications, and Advances*, pp. 1–18. New York: Wiley-Liss.

Slayter EM and Slayter HS (1992) *Light and Electron Microscopy*. Cambridge: Cambridge University Press.

Wiesendanger R (1994) *Scanning Probe Microscopy and Spectroscopy*. Cambridge: Cambridge University Press.

Wilson T and Sheppard CJR (1984) *Theory and Practice of Scanning Optical Microscopy*. London: Academic Press.

Confocal Microscopy

T Wilson, University of Oxford, Oxford, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

It is probably fair to say that the development and wide commercial availability of the confocal microscope has been one of the most significant advances in light microscopy in the recent past. The main reason for the popularity of these instruments derives from their ability to permit the structure of thick specimens of biological tissue to be investigated in three dimensions. It achieves this important goal by resorting to a scanning approach together with a novel (confocal) optical system.

The traditional wide-field conventional microscope is a parallel processing system which images the entire object field simultaneously, which is a severe requirement for the optical components. We can relax this requirement if we no longer try to image the whole object at once. The limit of this relaxation is to require a good image of only one object point at a time. The price that we have to pay is that we must scan in order to build up an image of the entire field.

A typical arrangement of a scanning confocal optical microscope is shown in Figure 1 where the system is built around a host conventional microscope. The essential components are some form of mechanism for scanning the light beam (usually from a laser) relative to the specimen and appropriate photodetectors to collect the reflected or transmitted light.



Figure 1 Schematic diagram of a confocal microscope.

Most of the early systems were analog in nature, but it is now universal, due to the serial nature of the image formation, to use a computer both to drive the microscope and to collect, process, and display the image.

In the beam scanning confocal configuration of Figure 1, the scanning is typically achieved by using vibrating galvanometer-type mirrors or acousto-optic beam deflectors. The use of the latter gives the possibility of TV-rate scanning, whereas vibrating mirrors are often relatively slow when imaging an extended region of the specimen, although significantly higher scanning speeds are achievable over smaller scan regions. We should note that other approaches to scanning may be implemented, such as specimen-scanning and lens-scanning. These methods, although not generally available commercially, do have advantages in certain specialized applications. Since this article is necessarily limited in length much additional material may be found in other sources listed in the Further Reading at the end of this article.

Image Formation in Scanning Microscopes

We will not discuss the fine detail of the optical properties of confocal systems. However, the essence is shown in Figure 1 where we see that the confocal optical system consists simply of a point source of light which is then used to probe a single point on the specimen. The strength of the reflected or fluorescence radiation from the single object point is then measured via a point, pinhole detector. The confocal – point source and point detector – optical system therefore merely produces an 'image' of a single object point and hence some form of scanning is necessary to produce an image of an extended region of the specimen. However, the use of single-point illumination and single-point detection results in novel imaging capabilities which offer significant advantages over those possessed by conventional wide-field optical microscopes. In essence, these are enhanced lateral resolution and, perhaps more importantly, result in a unique depth discrimination or optical sectioning property. It is this latter property which leads to the ability to obtain three-dimensional images of volume specimens.

The improvement in lateral resolution may at first seem implausible. However, it can be explained simply by the principle which states that resolution can be increased at the expense of field of view, which can then be increased by scanning. One way of taking advantage of this principle is to place a very small aperture extremely close to the object. The resolution is now determined by the size of the aperture rather than the radiation. In the confocal microscope we do not use a physical aperture in the focal plane but rather use the back-projected image of a point detector in conjunction with the focused point source. Figure 2 indicates the improvement in lateral resolution that may be achieved.

The confocal principle was introduced in an attempt to obtain an image of a slice within a thick specimen which was free from the distracting presence of out-of-focus information from surrounding planes. The confocal optical systems fulfills this requirement and its inherent optical sectioning or depth discrimination property has become the major



Figure 2 The point spread functions of the conventional and confocal microscopes showing the improvement in lateral resolution which may be obtained in the confocal case.



Figure 3 The origin of the optical sectioning or depth discrimination property of the confocal optical system.

motivation for using confocal microscopes, and is the basis of many of the novel imaging modes of these instruments. The origin of the depth discrimination property may be understood easily from Figure 3, where we show a reflection-mode confocal microscope and consider the imaging of a specimen with an undulating surface. The full lines show the optical path when an object feature lies in the focal plane of the lens. At a later scan position, the object surface is supposed to be located in the plane of the vertical dashed line. In this case, simple ray tracing shows that the light reflected back to the detector pinhole arrives as a defocused blur, only the central portion of which is detected and contributes to the image. In this way the system discriminates against features which do not lie within the focal region of the lens. A very simple method of both demonstrating the effect and giving a measure of its strength is to scan a perfect reflector axially through focus and measure the detected signal strength. Figure 4 shows a typical response. These responses are frequently termed the $V(z)$, by analogy with a similar technique in scanning acoustic microscopy. A simple paraxial theory models this response as

$$I(u) = \left[\frac{\sin(u/2)}{u/2} \right]^2 \qquad [1]$$

where u is a normalized axial coordinate which is related to real axial distance, z, via

$$u = \frac{8\pi}{\lambda} nz \sin^2(\alpha/2) \qquad [2]$$

where λ is the wavelength and $n \sin \alpha$ the numerical aperture. As a measure of the strength of the sectioning, we can choose the full width at half intensity of the $I(u)$ curves. Figure 5 shows this value as a function of numerical aperture for the specific case of imaging with red light from a helium neon laser. These curves were obtained using a high aperture theory which is more reliable than eqn [1]



Figure 4 The variation in detected signal as a plane reflector is scanned axially through focus. The measurement was taken with a 1.3 numerical aperture objective and 633 nm radiation.



Figure 5 The optical sectioning width as a function of numerical aperture. The curves are for red light (0.6328 μm wavelength). Δz is the full width at the half-intensity points of the curves of $I(u)$ against u.

at the highest values of numerical aperture. We note, of course, that these numerical values refer to nonfluorescence imaging. The qualitative explanation of optical sectioning, of course, carries over to the fluorescence case but the actual value of the optical sectioning strength is different in the fluorescence case.

Applications of Depth Discrimination

Since this property is one of the major reasons for the popularity of confocal microscopes, it is worthwhile, at this point, to review briefly some of the novel imaging techniques which have become available with confocal microscopy.

Figure 6 illustrates the essential effect: Figure 6a shows a conventional image of a planar microcircuit which has deliberately been mounted with its normal at an angle to the optic axis. We see that only one portion of the circuit, running diagonally, is in focus. Figure 6b shows the corresponding confocal image: here the discrimination against detail outside the focal plane is clear. The areas which were out of focus in Figure 6a have been rejected. Furthermore, the confocal image appears to be in focus throughout the visible band, which illustrates that the sectioning property is stronger than the depth of focus.

This suggests that if we try to image a thick translucent specimen, we can arrange, by the choice of our focal position, to image detail exclusively from one specific region. In essence, we can section the specimen optically without having to resort to mechanical means. Figure 7 shows an idealized schematic of the process. The portion of the beehive-shaped object that we see is determined by the focus position. In this way it is possible to take a through-focus series and obtain data about the three-dimensional structure of the specimen. If we represent the volume image by $I(x, y, z)$, then by focusing at a position $z = z_1$, we obtain, ideally, the image $I(x, y, z_1)$. This, of course, is not strictly true in practice because the optical section is not infinitely thin.

It is clear that the confocal microscope allows us to form high-resolution images with a depth of focus sufficiently small that all the detail which is imaged appears in focus. This suggests immediately that we can extend the depth of focus of the microscope by adding together (integrating) the images taken at different focal settings without sacrificing the lateral resolution. Mathematically, this extended-focus image is given by

$$I_{\mathrm{EF}}(x, y) = \int I(x, y, z)\mathrm{d}z \qquad [3]$$

As an alternative to the extended-focus method, we can form an auto-focus image by scanning the object axially and, instead of integrating, selecting the focus at each picture point by recording the maximum in the detected signal. Mathematically, this might be written as

$$I_{\mathrm{AF}}(x, y) = I(x, y, z_{\max}) \qquad [4]$$

where $z_{\max}$ corresponds to the focus setting giving the maximum signal. The images obtained are somewhat similar to the extended focus and, again, substantial increases in depth of focus may be obtained. We can go one step further and turn the microscope into a noncontacting surface profilometer. Here we simply display $z_{\max}$.

It is clear by now that the confocal method gives us a convenient tool for studying three-dimensional structures in general. We essentially record the image as a series of slices and play it back in any desired fashion. Naturally, in practice it is not as simple as this, but we can, for example, display the data as an $x - z$ image rather than an $x - y$ image. This is somewhat similar to viewing the specimen from the side. As another



Figure 6 (a) Conventional scanning microscope image of a tilted microcircuit: the parts of the object outside the focal plane appear blurred. (b) Confocal image of the same microcircuit: only the part of the specimen within the focal region is imaged strongly.



Figure 7 An idealization of the optical sectioning property showing the ability to obtain a through-focus series of images, which may then be used to reconstruct the original volume object at high resolution.

example, we might choose to recombine the data as stereo pairs by introducing a slight lateral offset to each image slice as we add them up. If we do this twice, with an offset to the left in one case and the right in another, we obtain, very simply, stereo pairs. Mathematically, we form images of the form:

$$\int I(x \pm \gamma z, y, z) \mathrm{d}z \qquad [5]$$

where γ is a constant. In practice it may not be necessary to introduce offsets in both directions to obtain an adequate stereo view.

Our discussion so far on these techniques has been by way of a simplified introduction. In particular, we have not presented any fluorescence images. The key point is that, in both brightfield and fluorescence modes, the confocal principle permits the imaging of specimens in three dimensions. The situation is, of course, more involved than we have implied. A thorough knowledge of the image formation process, together with the effects of lens aberrations and absorption, is necessary before accurate data manipulation can take place.

In conclusion to this section it is important to emphasize that the confocal microscope does not produce three-dimensional images. It essentially produces very high-quality two-dimensional images of a (thin) slice within a thick specimen. A three-dimensional rendering of the entire volume specimen may then be generated by suitably combining a number of these two-dimensional image slices from a through focus series of images.

Fluorescence Microscopy

We now turn our attention to confocal fluorescence microscopy, because this is the imaging mode which is usually employed in biological applications.

Although we have introduced the confocal microscope in terms of bright-field imaging the comments we have made concerning the origin of the optical sectioning, etc., carry over directly to the fluorescence case although the numerical values describing the strength of the optical sectioning are, of course, different and we will return to this point later.

If we assume that the fluorescence in the object destroys the coherence of the illuminating radiation and produces an incoherent fluorescent field proportional to the intensity of the incident radiation, $I(v, u)$, then we may write the effective intensity point spread function, which describes image formation in the incoherent confocal fluorescence microscope, as

$$I(v, u) I\left(\frac{v}{\beta}, \frac{u}{\beta}\right) \qquad [6]$$

where the optical coordinates u and v are defined relative to the primary radiation and $\beta = \lambda_2/\lambda_1$ is the ratio of the fluorescence to the primary wavelength. We note that $v = (2\pi/\lambda) rn \sin \alpha$, where r denotes the actual radial distance.

This suggests that the imaging performance depends on the value of β. In order to illustrate this we show in Figure 8 the variation in detected signal strength as perfect fluorescent sheet scans through focus. This serves to characterize the strength of the optical sectioning in fluorescence microscopy in the same way that the mirror was used in the brightfield case. We note that the half-width of these curves is



Figure 8 The detected signal as thin fluorescent sheet is scanned axially through focus for a variety of fluorescent wavelengths. We note that if we measure the sectioning by the half width of these curves, the strength of the sectioning is essentially proportional to β.

essentially proportional to β and so for optimum sectioning the wavelength ratio should be as close to unity as possible.

We have just discussed what we might call one-photon fluorescence microscopy in the sense that a fluorphore is excited by a single photon of a particular wavelength. It then returns to the ground state and emits a photon at the (slightly longer) fluorescence wavelength. It is this radiation which is detected via the confocal pinhole. Recently, however, much interest has centered on two-photon excitation fluorescence microscopy. This process relies on the simultaneous absorption of two, longer wavelength photons, following which a single fluorescence photon is emitted. The excitation wavelength is typically twice that used in the one-photon case. The beauty of the two-photon approach lies in the quadratic dependence of the fluorescence intensity on the intensity of the illumination. This leads to fluorescence emission which is always confined to the region of focus. In other words the system possesses an inherent optical sectioning property. Other benefits of two-photon fluorescence over the single photon case include the use of red or infra-red lasers to excite ultra-violet dyes, confinement of photo-bleaching to the focal region (the region of excitation), and the reduced effects of scattering and greater penetration. However, it should also be remembered that, compared with single photon excitation, the fluorescence yield of many fluorescent dyes under two-photon excitation is relatively low.

In order to make a theoretical comparison between the one- and two-photon modalities, we shall assume that the emission wavelength λ_{em} is the same, irrespective of the mode of excitation. Since the wavelength required for single-photon excitation is generally shorter than the emission wavelength, we may write it as $\gamma\lambda_{\mathrm{em}}$ where $\gamma < 1$. Since two-photon excitation requires the simultaneous absorption of two photons of half the energy we will assume that the excitation wavelength may be written as $2\gamma\lambda_{\mathrm{em}}$ which has been shown to be a reasonable approximation for many dyes.

If we now introduce optical coordinates u and v, normalized in terms of λ_{em}, we may now write the effective point spread functions in the one-photon confocal and two-photon case as

$$I_{\text{1p-conf}} = I\left(\frac{v}{\gamma}, \frac{u}{\gamma}\right) I(v, u) \qquad [7]$$

and

$$I_{\text{2p}} = I^2\left(\frac{v}{2\gamma}, \frac{u}{2\gamma}\right) \qquad [8]$$

respectively. We note that although a pinhole is not usually employed in two-photon microscopy it is possible to include one if necessary. In this confocal two-photon geometry the effective point spread function becomes

$$I_{\text{2p-conf}} = I^2\left(\frac{v}{2\gamma}, \frac{u}{2\gamma}\right) I(v, u) \qquad [9]$$

If we now look at eqns [7] and [8] in the $\gamma = 1$ limit, we find that

$$I_{\text{1p-conf}} = I^2(v, u) \qquad [10]$$

and

$$I_{\text{2p}} = I^2\left(\frac{v}{2}, \frac{u}{2}\right) \qquad [11]$$

We now see that because of the longer excitation wavelength used in two-photon microscopy the effective point spread function is twice as large as that of the one-photon confocal in both the lateral and axial directions. The situation is somewhat improved in the confocal two-photon case but it is worth remembering that the advantages of two-photon excitation microscopy are accompanied by a reduction in optical performance as compared to the single-photon case.

From the practical point of view it is worth noting that the two-photon approach has certain very important advantages over one-photon excitation, in terms of image contrast, when imaging through scattering media apart from the greater depth of penetration afforded by the longer wavelength excitation. In a single-photon confocal case it is quite possible that the desired fluorescence radiation from the focal plane may be scattered after generation in such a way that it is not detected through the confocal pinhole. Since the fluorescence is generated throughout the entire focal volume it is also possible that undesired fluorescence radiation, which was not generated within the focal region, may be scattered so as to be detected through the confocal pinhole. In either case this leads to a reduction in image contrast. The situation is, however, completely different in the two-photon case. Here the fluorescence is generated only in the focal region and not throughout the focal volume. Furthermore since all the fluorescence is detected via a large area detector – no pinhole is involved – it is not so important if further scattering events take place. This leads to high-contrast images which are less sensitive to scattering. This is particularly important for specimens which are much more scattering at the fluorescence ($\lambda/2$) wavelength than the excitation (λ) wavelength.

The Use of Structured Illumination to Achieve Optical Sectioning

An alternative approach to obtain optical sectioning is to use structured illumination in a conventional microscope. This approach is attractive since the conventional light microscope already possesses many desirable properties: real-time image capture, standard illumination, ease of alignment, etc. However, it does not produce optically sectioned images in the sense usually understood in confocal microscopy. In order to see how this deficiency may be corrected via a simple modification of the illumination system let us begin by looking at the theory of image formation in a conventional fluorescence microscope and start by asking in what way the image changes as the microscope is defocused. We know that in a confocal microscope the image signal from all object features attenuates with defocus and that this does not happen in a conventional microscope. However, when we look closely at the image formation process we find that it is only the zero spatial frequency (constant) component which does not change with defocus (Figure 9); all other spatial frequencies actually do attenuate with defocus to a greater or lesser extent. Figure 10 illustrates this by showing the image of a single spatial frequency one-dimensional bar pattern object for increasing degrees of defocus. When the specimen is imaged in focus, a good image of the bar pattern is obtained. However with increasing defocus the image becomes progressively poorer and weaker until it eventually disappears leaving a uniform gray level. This observation is the basis of a simple way to perform optical sectioning in a conventional microscope.

If we simply modify the illumination path of the microscope so as to project onto the object the image of a one-dimensional, single spatial frequency fringe pattern, then the image we see through the microscope will consist of a sharp image of those parts of the object where the fringe pattern is in focus together with an out-of-focus blurred image of the rest of the object. In order to obtain an optically sectioned image it is necessary to remove the blurred out-of-focus portion as well as the fringe pattern from the in-focus optical section. There are many ways to do this – one of the simplest involves simple processing of three images taken at three different spatial positions of the fringe pattern. The out-of-focus regions remain fairly constant between these images and the relative spatial shift of the fringe pattern allows the three images to be combined in such a way as to remove the fringes. This permits us to retrieve both an optically sectioned image as well as a conventional image in real time.



Figure 9 The transfer function for a conventional fluorescence microscope for a number of values of defocus (measured in optical units). We notice that the response for all nonzero spatial frequencies decays with defocus.



Figure 10 The image of a one-dimensional single spatial frequency bar pattern for varying degrees of defocus. We note that for sufficiently large values of defocus the bar pattern is not imaged at all.

Since the approach involves processing three conventional microscope images, the image formation is fundamentally different from that of the confocal microscope. However, the depth discrimination or optical sectioning strength is very similar and this approach, which requires very minimal modifications to the instrument, has been used to produce high-quality three-dimensional images of volume objects which are directly comparable to those obtained with confocal microscopes. A schematic of the optical arrangement is shown in Figure 11a, together with experimentally obtained axial responses in Figure 11b. It will be noted that these responses are substantially similar to those obtained in the true confocal case. As an example of the kind of images which can be obtained with this kind of microscope, we show in Figure 12 two images



Figure 11 (a) Shows the optical system of the structured illumination microscope together with experimentally obtained axial responses in (b) which confirm the optical sectioning ability of the instrument.



Figure 12 Two images of the region around the spiracle of a head louse. As in the previous figure, (a) is an autofocus image and (b) shows a mid-focus conventional image. The scale bar depicts a length of 10 µm.

of a spiracle of a head louse. The first is an auto-focus image of greatly extended depth of field constructed from a through-focus series of images. The second is a conventional image taken at mid-focus. The dramatic increase in depth of field is clear when compared with a mid-focus conventional image. We note that these images were taken using a standard microscope illuminator as light source. Indeed, the system is so light efficient that good-quality optical sections have been obtained or transistor specimens using simply a candle as light source!

Imaging using fluorescence light is also possible using this technique. However, an alternative approach that does not require a physical grid is possible if a laser is used as the light source. In this system the laser illumination is split into two beams which are allowed to interfere at an angle in the fluorescent specimen. This has the effect of directly ‘writing’ a one-dimensional fringe pattern in the specimen. Spatial shift of the fringe pattern is achieved by varying the phase of one of the interfering beams. As before, three images are taken from which both the optically sectioned image and conventional image may be obtained. The beauty of this approach is that no imaging optics are required at the illuminating wavelength and system.

Summary

We have discussed the origin of the optical sectioning property in the confocal microscope in order to introduce the range of imaging modes which this unique form of microscope leads to. A range of optical architectures have also been described. By far the most universal is that shown in Figure 1 where a confocal module is integrated around a conventional optical microscope. Other, more recent, real-time implementations have also been described. A number of practical aspects of confocal microscopy have not been discussed. This is because they are readily available elsewhere, such as advice on the correct choice of detector pinhole size or because they are still the focus of active research, such as the development of new contrast mechanisms for achieving enhanced three-dimensional resolution such as the stimulated emission depletion method, STED or 4-Pi which are still under development but offer great promise.

See also

Microscopy: Imaging Multiple Photon Fluorescence Microscopy; Overview.

Further Reading

Corle TR and Kino GK (1996) *Confocal Scanning Optical Microscopy and Related Imaging Systems*. New York: Academic Press.

Denk W, Strikler JH and Webb WW (1990) Two photon laser scanning fluorescence microscopy. *Science* 248: 73.

Diaspro A (2002) *Confocal and Two-Photon Microscopy*. New York: Wiley-Liss.

Gu M (1996) *Principles of Three-Dimensional Imaging in Confocal Microscopes*. Singapore: World Scientific.

Hell S and Stelzer EHK (1992) Fundamental improvements of resolution with a 4Pi-confocal fluorescence microscope using two-photon excitation. *Optics Communication* 93: 277.

Hell S and Wichmann J (1994) Breaking the diffraction limit by stimulated emission. *Optics Letters* 19: 870.

Lukosz W (1966) Optical systems with resolving power exceeding the classical limit. *Journal of the Optical Society of America* 56: 1463.

Masters BR (1996) *Confocal Microscopy*. Bellingham: SPIE.

Minsky M (1961). Microscopy Apparatus. United States Patent 3,013,467, Dec 19, 1961 (Filed Nov 7, 1957).

Neil MAA, Juskaitis R and Wilson T (1997) Method of obtaining optical sectioning by using structured illumination in a conventional microscope. *Optics Letters* 22: 1905.

Pawley JB (ed.) (1995) *Handbook of Biological Confocal Microscopy*. New York: Plenum Press.

Wilson T (ed.) (1990) *Confocal Microscopy*. London: Academic Press.

Wilson T and Sheppard CJR (1984) *Theory and Practice of Scanning Optical Microscopy*. London: Academic Press.

Imaging Multiple Photon Fluorescence Microscopy

M Previte, Massachusetts Institute of Technology, Cambridge, MA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The field of light microscopy started with Ernst Abbe's introduction of the diffraction-limited objective lens in the late nineteenth century. Over the last 60 years, new imaging modalities, such as video, fluorescence, confocal, near field, and more recently multi-photon microscopy, have enabled the experimentalist to observe a plethora of new phenomena in the biological and physical sciences. Of these techniques, multi-photon microscopy has emerged not only as a valuable imaging technique but it also forms the technology base for emerging fields of optical memory and microfabrication.

The history of multi-photon microscopy (MPM) began with Göppert-Mayer's theoretical prediction of two-photon excitation in 1931. Although the theoretical groundwork was established, it took another 30 years for this process to be experimentally realized when Kaiser and Garrett observed two-photon absorption fluorescence emission from $CaF_2:Eu^{+2}$. Soon after this observation was made, Singh and Bradley witnessed higher-order multi-photon processes in 1964.

Historically, three-dimensional imaging was first achieved using confocal microscopy. In contrast to MPM, photo-interaction and fluorescence emission occurs throughout the excitation light path in confocal microscopy. Confocal microscopy selects the signal from the focal plane by the use of a conjugated pinhole aperture. In order to construct 3D images, successive planes must be imaged. As a result, the entire sample volume is exposed to the excitation light multiple times, and inevitably, photobleaching and photodamage occurs throughout the imaging volume. Furthermore, the pinhole aperture in the emission path causes additional signal reduction in optically thick specimens where the emission photon is scattered. Consequently, the utility of confocal microscopy is limited for imaging living biological specimens. The introduction of multi-photon microscopy, by Denk and Webb in 1990, addressed many of these limitations. By combining the methodology of multi-photon excitation with scanning microscopy, MPM offered advantages such as 3-D localized, femtoliter excitation volumes, reduced scattering and absorption of the infrared excitation light by the specimen, and a large separation between the excitation and emission wavelengths. MPM can produce excellent three-dimensional images with increased signal to noise ratios.

Theoretical Basis of Multi-Photon Microscopy

Multi-photon Excitation Selection Rules

Unlike direct ground state to excited state one-photon transitions, multi-photon transitions depend on the presence of virtual electronic intermediate states to reach an excited state (see Figure 1).

Using perturbative expansion, the probability of excitation for one-photon transitions is described by the first-order solution, and multi-photon transitions can be determined by including the higher order solutions. The interaction of an electric field vector E_λ with a molecule's dipole, $\vec{r}$, is described by the respective one-photon and two-photon transition probabilities:

$$P_{1h\nu} \approx \langle \Psi_f | \vec{E}_\lambda \cdot \vec{r} | \Psi_i \rangle^2$$

$$P_{2h\nu} \approx \left| \sum_m \frac{\langle \Psi_f | \vec{E}_\lambda \cdot \vec{r} | \Psi_m \rangle \langle \Psi_m | \vec{E}_\lambda \cdot \vec{r} | \Psi_i \rangle}{\varepsilon_\lambda - \varepsilon_{m,i}} \right|^2 \qquad [1]$$

where Ψ_i, Ψ_m, and Ψ_f are the initial, intermediate, and final transition states, $\vec{E}_\lambda$ is the electric field associated with the excitation light, ε_λ is the energy difference between the ground state and excited states, $\varepsilon_{m,i}$ is the energy difference between the intermediate state m and the ground state, i, and the summation is over all possible intermediate states m. Although electronic transitions, that result from the interaction of a strong electric field with a molecular dipole, are affected by vibrational mode overlap (Franck Condon factors) and anharmonic perturbative effects, the presence of intermediate transition states creates a set of general selection rules for multi-photon absorption processes.

Molecular states have eigenfunctions with a defined parity: 'gerade' describing even or symmetric states (no change in the sign of the wavefunction when the sign changes in the spatial coordinates) and 'ungerade' describing odd or antisymmetric states (the sign of the wavefunction changes when the sign changes in the spatial coordinates). Selection rules arise from the physics inherent in these even and odd eigenfunctions and the odd dipole operator that couples transitions between ground and excited states. In one-photon excitation, transitions are allowed for ground state and excited state transitions of opposite parity. In contrast, two-photon excitation occurs between ground and excited states with the same parity, by coupling through intermediate states with opposite parity. In general, ground and excited states with the same parity have a high excitation probability for an even number of photons; ground and excited states with different parity have a high transition probability for excitations involving an odd number of photons.

In the absence of major vibrational perturbations, inductive effects, or solvent relaxation, the probability of the transition depends on the magnitude of the integral overlap between the ground, intermediate, and excited states. As a result, molecule absorption cross-sections for one-photon, two-photon, three-photon, or multi-photon excitation processes can be estimated. Choosing fluorophores with higher multi-photon cross-sections allows more efficient excitation with lower excitation intensity. Finally, it should be noted that while the absorption cross-sections for one-, two-, and multi-photon excitation of a given fluorophores are different, the molecules rapidly relax to the same vibrational level in the excited electronic state. The excited state residence time (fluorescence lifetime), and the fluorescence decay processes depend only on the molecular structure and its microenvironment. Therefore, the fluorescence



Figure 1 Jablonski diagram of a fluorescent dye molecule in one-, two- and *n*-photon excitation mode.

quantum yield and emission spectra is independent of the initial excitation process.

Enhanced Microscope Resolution Based on Multi-photon Excitation

The number of photons that are absorbed in a multi-photon process is proportional to the fluorophore concentration, $C(\vec{r},t)$, the molecule's absorption cross-section, σ_n, which depends on n, the number of photons involved in the absorption process, and the intensity of the excitation source, such that

$$N_{\text{abs}}(t) = \int \mathrm{d}\vec{r} I_0^n(\vec{r},t) C(\vec{r},t)\sigma_n \qquad [2]$$

When estimating $N_{\text{abs}}(t)$, the spatial and temporal intensity distribution of the excitation intensity are considered independently:

$$I_0(\vec{r},t) = S(\vec{r}) I_0(t) \qquad [3]$$

such that for an n-photon process, $I_0(t)$ is the temporal dependence of the excitation intensity at the maxima of the spatial distribution and $S(\vec{r})$ is the unitless spatial distribution of the excitation light. Combining eqns [2] and [3] gives

$$N_{\text{abs}}(t) = \int \mathrm{d}\vec{r} S^n(\vec{r}) I_0^n(t) C(\vec{r},t)\sigma_n \qquad [4]$$

If it is assumed that fluorophore distribution is uniform and the system does not undergo photobleaching or ground-state depletion, $C(\vec{r},t)$ can be considered a constant and the previous equation can be rewritten as

$$N_{\text{abs}}(t) = C\sigma_n I_0^n(t) \int_V S^n(\vec{r})\mathrm{d}\vec{r} \qquad [5]$$

By expanding the incident laser beam and overfilling the back aperture of the objective lens, the paraxial form of the normalized intensity point spread function (PSF, $h^2[u,v]$) determines the properties for a diffraction-limited lens. The dimensionless radial distance, v, from the optic axis and the distance from the in-focus plane, u, are given by

$$v = \frac{2\pi(\text{NA})r}{\lambda} \qquad [6]$$

$$u = \frac{2\pi(\text{NA})^2 z}{n_0\lambda} \qquad [7]$$

where $\text{NA} = n_0 \sin\theta$ (θ being the half-angle of collection for the lens and n_0 is the index of refraction the medium) is the numerical aperture. Expressing the spatial distribution function with the optical units, v, u, and θ gives the following equation:

$$S(\vec{r}) = h^2[u,v] = 2\left|\int J_0(v\theta)\mathrm{e}^{-(1/2)\mathrm{i}u\theta^2}\,\theta\,\mathrm{d}\theta\right|^2 \qquad [8]$$

where J_0 is the zero-order Bessel function. If an oil immersion objective with a $\text{NA} < 1.0$ is used, the paraxial approximation accurately estimates the spatial distribution, and the integral of $S(\vec{r})$ evaluates as

$$\int_{V=\infty} S^n(\vec{r})\mathrm{d}\vec{r} = a_n\left[\frac{n_0\lambda^3}{8\pi^3(\text{NA})^4}\right] \qquad [9]$$

where $a_n = \int_0^\infty 2\pi v\,\mathrm{d}v \int_{-\infty}^{\infty} \mathrm{d}u[h(u,v)]^{2n}$. Since this integral cannot be solved analytically, the values of a_n are determined using numerical integrations of $h^2(u,v)$ over all space. As a result, the volume integral of the spatial distribution is always proportional to NA^{-4} and therefore independent of the number of photons involved in the excitation process. For higher NA objectives, the paraxial form of the normalized intensity PSF may no longer be an adequate approximation. The expression for temporal part of eqn [5] can be written as

$$I_0(t) = \left(\frac{\pi\text{NA}^2}{\lambda^2}\right)P(t) \qquad [10]$$

where $P(t)$ is the excitation power and λ is the center wavelength of the pulsed excitation source. The temporal dependence can be described with the time average expression:

$$\langle I_0^n(t)\rangle = \left(\frac{\pi\text{NA}^2}{\lambda^2}\right)^n \frac{1}{T}\int_0^T P^n(t)\mathrm{d}t \qquad [11]$$

where T is an arbitrary time interval for continuous wave lasers and $T = 1/f_{\text{p}}$ for a pulsed laser with a repetition rate, f_{p}. Since multi-photon microscopy uses pulsed laser systems, the integral in eqn [11] must be evaluated accordingly. For a pulsed laser with a pulse width, τ, repetition rate, f_{p}, and averaged power, P_0, the pulse profile can be approximated as

$$P(t) = \frac{P_0}{f_{\text{p}}\tau} \qquad \textit{for } 0 < t < \tau \qquad [12]$$

$$P(t) = 0 \qquad \textit{for} \qquad \tau < t < \frac{1}{f_{\text{p}}} \qquad [13]$$

such that eqn [11] can be expressed as

$$\langle I_0^n(t)\rangle = \left(\frac{\pi\text{NA}^2}{\lambda^2}\right)^n \left(\frac{P_0}{f_{\text{p}}\tau}\right)^n \frac{1}{T}\int_0^T \mathrm{d}t \qquad [14]$$

and evaluated as

$$\langle I_0^n(t)\rangle = \left(\frac{\pi \mathrm{NA}^2}{\lambda^2}\right)^n (P_0)^n \left(\frac{1}{f_\mathrm{p}\tau}\right)^{n-1} \qquad [15]$$

Assuming no stimulated emission and no self-quenching, the quantity of emitted photons collected per unit time, $F(t)$, is

$$F(t) = \frac{1}{n}\phi\eta N_\mathrm{abs}(t) \qquad [16]$$

where η and ϕ are the fluorescence quantum efficiency of the dye and collection efficiency of the system, respectively. Since n photons are needed for each individual excitation event, $1/n$ is a normalization factor for N_abs which describes the total number of photons absorbed. Rewriting this expression in terms of the average number of absorbed photons, $\langle N_\mathrm{abs}(t)\rangle$, gives the average fluorescence intensity:

$$\langle F(t)\rangle = \frac{1}{n}\phi\eta\langle N_\mathrm{abs}(t)\rangle \qquad [17]$$

where $\langle N_\mathrm{abs}(t)\rangle$ is

$$\langle N_\mathrm{abs}(t)\rangle = C\sigma_n \langle I_0^n(t)\rangle \int_V S^n(\vec{r})\mathrm{d}\vec{r} \qquad [18]$$

such that the measured fluorescence intensity or time averaged photon flux is expressed as

$$\langle F(t)\rangle = \frac{1}{n}\phi\eta C\sigma_n \langle I_0^n(t)\rangle \int_V S^n(\vec{r})\mathrm{d}\vec{r} \qquad [19]$$

Since the time averaged fluorescence is proportional to $\langle I_0^n(t)\rangle$, eqns [9] and [15] can be substituted into eqn [19] to give a practical expression that relates average fluorescence to measurable laboratory quantities, such as P_0, τ_p, f_p, C, σ_n, n, η, and ϕ, NA, and associated numerical constants such that

$$\langle F(t)\rangle = \frac{1}{n}\phi\eta C\sigma_n \left(\frac{\pi \mathrm{NA}^2}{\lambda^2}\right)^n (P_0)^n \left(\frac{1}{f_\mathrm{p}\tau}\right)^{n-1} \times a_n\left[\frac{n_0\lambda^3}{8\pi^3(\mathrm{NA})^4}\right] \qquad [20]$$

As eqn [19] shows, the fluorescence intensity has an *n*th order dependence on the spatial and temporal distribution of the excitation power. Therefore, appreciable multi-photon probability occurs only at a region of high temporal and spatial concentration of photons. Confocal pinholes can be eliminated making this technique better suited for 3D biological imaging.

The higher order (>2) dependence of the fluorescence signal upon the excitation intensity distribution results in axial confinement. Experimentally, it can be shown that over 80% of fluorescence signal emanates from a 1 μm thick region about the focal point for objectives with a numerical aperture of 1.25 under two-photon excitation. This confinement is significantly different from one-photon excitation where a spatially uniform fluorescent sample contributes equal fluorescence intensities from each *z*-section above and below the focal plane (assuming negligible excitation attenuation). For an excitation wavelength of 960 nm, the typical point spread function of two-photon absorption has FWHM of 0.3 μm in the radial direction and 0.9 μm in the axial direction. In comparison with confocal microscopy, the localization of the volume of excitation instead of the volume of observation, as in confocal microscope, allows 3D imaging with minimal photobleaching and damaging.

Basic Imaging Applications of Multi-Photon Microscopy

Multi-photon microscopy finds an increasingly broad range of applications, especially in biological and medical areas. For example, multi-photon microscopy has been utilized to study the physiological and biological states in various highly scattering tissues such as cornea, skin, and pancreas islet. Also, multi-photon microscopy is used in embryology to study the development of sea urchin, *Caenorhabditis elegans*, hamster, and zebra fish. Neurobiological applications include qualifying calcium dynamics dendritic spines, memory and structural plasticity, hemodynamics, and plaque evolution in Alzheimer's disease. MPM has been applied to study pharmacological distribution in tissues and in the quantification of transdermal drug delivery. Due to minimally invasive capability of multi-photon microscopy, intra-vital microscopy imaging into thick tissues of living animals is possible leading to applications in the study of cancer biology.

Although the advantages of MPM are less compelling in studying cell cultures where the specimen is optically thin, a number of uniquely exciting uses have been identified. For instance, the significantly broader two-photon absorption spectra of many fluorophores allow convenient imaging of specimens labeled with multiple color fluorophores. The localized excitation volume reduces photo-interaction with fluorophores outside the excitation volume allowing better 3D images to be obtained from cellular systems labeled with easily photobleachable fluorophores. The use of three and higher photon excitation has also allowed the excitation and imaging of important biomolecules with deep ultraviolet absorption. Another interesting application of multi-photon excitation in cellular systems is based on the ability of this method to produce localized chemical reactions. Through the photoactivation or photolysis of 'caged' molecules, their chemical structures are altered to produce biologically active molecules, fluorescent species, or other observable chemical changes. Multi-photon excitation has been used to locally uncage neurotransmitters for mapping ion channels in neurons and to uncage calcium in studying signal transduction events. In cellular systems, MPM is being used to image normally nonfluorescent biomolecules, such as serotonin in neurons, based on multi-photon induced chemical conversion and multi-photon excitation. Finally, multi-photon microscopy has also found applications in studying the conformation, aggregation, diffusion, and transport of single molecules and proteins. Two-photon fluorescence correlation spectroscopy and photon counting histograms are powerful techniques that have been applied to study protein aggregation, conformation changes, and diffusion *in vitro* with applications ranging from cell biology to high throughput drug discovery. The large separation of excitation and emission spectra of two-photon excitation also allows high sensitivity detection of fluorescence from single chromophore; however, the higher photobleaching rate at the excitation volume for some chromophores may lessen or even reverse this advantage.

Advanced Multi-Photon Microscopy Techniques

As described in the previous sections, excitation processes involving multiple numbers of photons offers considerable advantages for the imaging process in fluorescent microscopy. 4Pi Confocal Microscopy and high-speed Multifocal Multi-photon Microscopy MMM are advanced multi-photon microscopy techniques that capitalize on these advantages to improve image resolution and acquisition times in fluorescence imaging.

4Pi Confocal Microscopy

In contrast to near-field microscopy, far-field light microscopes, i.e. confocal and multi-photon microscopes, can create three-dimensional images of the interior of cells. The lateral and axial resolution of these systems is limited between 180 nm and 300 nm and 500–1000 nm, respectively. This limitation is dictated by the Abbe theory where resolution is inversely proportional to the numerical aperture of the focusing lens. When focusing with a single lens, geometric constraints limit the numerical aperture to about 1. 4Pi microscopy was developed to overcome this limitation. By utilizing two opposing objective lenses whose spherical wavefronts are coherently combined, a greater total effective numerical aperture is achieved. This results in a higher axial resolution, while the lateral resolution of the 4Pi microscope remains unchanged with respect to its confocal counterpart.

In the setup of a 4Pi microscope, the illuminating wavefronts emanate from a common point light source. The path is split by a beamsplitter, guided through two optically identical paths, and through two opposing high NA lenses that share a common focus. The fluorescence light is then collected through one lens and a confocal pinhole. In the axial direction, this arrangement yields a PSF with one main maximum lobe that is 3–4 times sharper along the optic axis than the PSF of a conventional confocal microscope, and two undesired side-lobes.

These side lobes can produce artifacts in the image and their effect needs to be suppressed for unambiguous 3D imaging. Lobe suppression can be achieved in a 4Pi system using two-photon excitation resulting in a quadratic decrease in the ratio of the side-lobe and the main lobe amplitudes. Using an excitation wavelength of 800 nm and 1.4 NA oil-immersion objectives, a FWHM along the axial direction of the main lobe is about 145 nm and side lobes are approximately 25–35% of the maximum lobe intensity. These side lobes can be further mathematically reduced by means of a linear filter after (or during) image acquisition. The filter can be applied at lobe heights below 50%, and an effective 3D PSF consisting of a single spot with a 250 nm lateral and 145 nm axial FWHM is achieved. When combined with nonlinear image restoration, 4Pi confocal microscopy achieves a 3D resolution in the 100 nm range. This resolution is similar to that obtained with near-field optical microscopy in biological applications with an added advantage of 3D imaging of the cell interior.

Since resolution improvement in 4Pi microscopy can be negated by the presence of aberrations, the usage of oil immersion lenses requires the specimen to be fixed and mounted in glycerol to minimize aberrations resulted from index mismatch. The sample thickness is further limited in the range of 20–30 μm. Due to significant index mismatches between oil and water, the imaging of live cells in aqueous medium is extremely difficult, if not impossible. In order to circumvent this difficulty, water immersion objective lenses are introduced into the 4Pi system. These lenses have a lower aperture angle $\alpha = 62°$ (NA = 1.2) than oil immersion lenses



Figure 2 (a) Two-photon confocal and (c) 4Pi confocal point deconvolved images of an immunolabelled microtubule network in fixed NIH3T3 cells. The 3D rendered images in (a) and (c) were generated out of a large XZ-image-stack, partly shown in (b) and (d). As indicated in the XZ-images, the axial resolution is 820 nm and 190 nm for the two-photon confocal and the two-photon 4Pi confocal images, respectively. The images were taken with water immersion lenses (NA = 1.2). Reproduced from Bahlmann K, Jakobs S, *et al.* (2001) 4Pi-confocal microscopy of live cells. *Ultramicroscopy* 87(3): 155–164, with permission from Elsevier.

$\alpha = 68°$ (NA = 1.4) and therefore are expected to produce higher side lobes, which are reduced by 35% with careful aberration studies such that linear filtering is possible. Nonetheless, the use of water-immersion lenses solves two major problems. First, they extend the possible sample thickness to the working distance of the objective lens (~200 μm); second they allow the imaging of live cells in aqueous medium. As a result, microtubule networks (see Figure 2) and live bacteria can be imaged with a resolution of 280 nm in lateral and 190 nm in axial direction. The water immersion 4Pi microscope, utilizing two-photon excitation, is capable of the highest 3D resolution so far reported in live cell imaging to date.

Multifocal Multi-Photon Microscopy (MMM)

Improving imaging speed is critical for applying 3D microscopy in biological specimens. An MMM scans an object with an array of high-aperture foci whereas a conventional multi-photon microscope scans with a single beam. An MMM combines nonlinear fluorescence excitation with parallelized 3D imaging. The technical design consists of a densely packed microlens array; each microlens transmitting a collimated beam at a slightly different angle, overfilling the back aperture of the objective. Consequently, from the arrangement of the microlenses, an array of foci is reproduced in the image plane. The foci are scanned rapidly across the image plane to ensure full coverage of the focal plane and real-time imaging (a stack of 50 images of 30–70 μm diameter can be acquired within a few seconds). The foci's movements are either generated by rotating a microlens array that is arranged in a Lasserie pattern or by rectilinear scanning of a square microlens matrix.

MMM development was initiated because nonlinear optical damaging processes limit the usable focal peak intensity to about 200 GW/cm^2, which can be reached by a tightly focused 7–15 mW femtosecond laser beam. This power consumption makes use of only a fraction of the laser output of a typical mode-locked titanium-sapphire laser light source. The MMM better exploits the 1–2 W of the beam power by dividing the power among 25–40 foci and scanning each in parallel. With this method, typical acquisition times are cut from ~1000 ms to 10–50 ms. MMM provides an excellent method for real time 3D multi-photon imaging.

A fundamental problem in parallelized 3D microscopy is that increasing density of the foci over a certain level decreases the axial resolution. The reduction of the distance between the foci increases not only the speed or image brightness, but it also increases the interference between neighboring focal fields; especially in planes shortly before and after the focal plane. For neighboring foci in high NA objective lenses, interference effects can be significant. The relatively short laser pulses that are commonly used in multi-photon excitation provide a means to reduce this interference by using time multiplexing. Experimentally, the femtoseconds pulses of the Ti:sapphire laser, going through each lenslet, can be scheduled to arrive at the focal plane at different times by a mask of glass in front of each microlens, varying the optical path lengths of these beams. The different arrival time eliminates interference effects. The resolution of the parallelized system remains unchanged as compared with the conventional one foci system. In conclusion, the MMM enables increased image acquisition speed by a factor of the number of foci in the optical plane without compromising image resolution.

Advanced Multi-Photon Microscopy Applications

As described by the previous section, MPM technology is undergoing rapidly development with improved resolution and increased instrument throughput. Recently, MPM has also found applications in exciting new areas of optical memory and microfabrication.

Multi-Photon 3D Optical Memory

Researchers in the field of optical memory are challenged to develop instrumentation that records three-dimensional, high density, robust bitwise information in low-cost and readily available storage materials. Initially, early optical memory techniques relied on higher energy pulsed recording beams and red shifted reading beams. Aided by the development of the Ti:sapphire laser and high numerical aperture objectives that can confine laser light to a volume of the order, λ^3, the power of the focused femtosecond pulses at the focal point can reach over 10^{18} W/cm^2 with electrical field strengths reaching 2.7×10^{10} V/cm. These fields are substantial enough to locally change the optical properties of selected materials. Thus, multi-photon processes were intertwined with the field of optical memory. Recent experiments showed that with properly chosen materials and instrumentation, high density, three-dimensional data storage was possible.

Optical memory is based on photochromic material whose optical properties are changed upon irradiation such that initial and final chemical states have different absorption spectra or indices of refraction. In 1989, Parthenopoulos and Rentzepis first showed that 3D information could be stored in a polymer film doped with photochromic molecules. Although the recorded information is lost when the photo-excited compound spontaneously reverts back to the original nonfluorescent compound, Dvornikov and Rentzepis later improved the material such that the stored information was stably recorded at room temperature.

For photochromic materials, the recording and reading mechanisms often required multiple laser sources and complex optical setups. Kawata *et al.* addressed these issues with the development of an alternative optical method that used photorefractive crystals as the storage media, a Ti:sapphire as the recording device, and a phase-contrast microscope configuration for data readout of bits separated by 20 μm. Using this method, Kawata avoided the complication of different recording and read-out laser sources, thereby simplifying the instrumentation. However, in photorefractive material, poor refractive index matching, between the storage medium and the objective, results in aberration and degrades storage densities. Recent advances in objective lens design have attempted to address these limitations. Kawata and Kawata describe many of these optical memory devices in a recent review. A recent publication by Olson *et al.* describes a method for multi-photon data storage in molecular glasses and highly cross-linked polymers. These materials prove to be highly efficient and robust for long-term data storage.

Although the field of optical memory has made great progress since 1989, further advances are required before this field becomes a widely adopted technology. For example, simpler recording and reading techniques are required to insure a cost-effective and reliable data storage technology. Consequently, further progress in the production of compact ultrafast lasers and high-speed scanning instrumentation will be needed before broader acceptance of optical memory storage devices.

Multi-Photon 3D Microfabrication

Another promising emerging application of multi-photon excitation is 3D microfabrication. 3D microfabrication processes can be performed with two-photon absorption. Maruo *et al.* and Sun *et al.* provide examples of microfabricated structures generated with femtosecond pulses to induce photopolymerization. Much like the optical memory techniques, this methodology relies on photoinitiators with large two-photon cross-sections to initiate polymerization of surrounding monomer or polymer molecules. Kawata *et al.* and Sun *et al.* showed that two-photon photopolymerization could be used successfully to create intricate three-dimensional microstructures. These systems offer lower polymerization thresholds, higher polymerization rates, and wider dynamic write ranges such that rapid fabrication and low-power writing are possible. Recently, Cumpston *et al.* described a class of π-conjugated compounds with large two-photon cross-sections, which can be effectively used for two-photon polymerization initiators in three-dimensional optical data storage and microfabrication processes.

As with most of these processes, the techniques have proven to be successful, but the mechanisms behind the multi-photon initiated chemical processes are not completely understood. With further work to optimize the reaction parameters, it is possible to design experiments that will allow new materials to be synthesized or patterned based on processes such as dielectric breakdown, microexplosions, optical damage, and pyrolytic effects.

Conclusion

Relying on femtoliter excitation volumes and large separations between excitation and emission wavelengths, multi-photon microscopy has emerged as a powerful technology that allows for increased resolution and enhanced signal-to-noise ratios. It has also enabled scientists to avoid complications in imaging biological systems due to decreased sample photodamage and in some instances, photobleaching of fluorophores. Advancements in multi-photon imaging applications, such as 4Pi Confocal microscopy and multifoci multi-photon microscopy, have further enhanced the resolution of imaging technology and improved the speed of data acquistion respectively. Furthermore, the application of multi-photon technology in the fields of microfabrication and optical memory promises to address some of the difficulties involved in designing three-dimensional high-density storage devices and microfabricated components. Overall, multi-photon microscopy provides the scientific community with an invaluable tool in the study and design of biological and physical systems.

See also

Microscopy: Confocal Microscopy; Imaging Multiple Photon Fluorescence Microscopy; Overview.

Further Reading

Bahlmann K, Jakobs S, *et al.* (2001) 4Pi-confocal microscopy of live cells. *Ultramicroscopy* 87(3): 155–164.

Bewersdorf J, Pick R, *et al.* (1998) Multifocal multiphoton microscopy. *Optical Letters* 23: 655.

Denk W, Strickler JH, *et al.* (1990) Two-photon laser scanning fluorescence microscopy. *Science* 248(4951): 73–76.

Kawata S and Kawata Y (2000) Three-dimensional optical data storage using photochromic materials. *Chem. Rev.* 100(5): 1777–1788.

Olson CE, Previte MJR, *et al.* (2002) Efficient and robust multiphoton data storage in molecular glasses and highly crosslinked polymers. *Nature Materials* 1(4): 225–228.

Pawley JB (ed.) (1995) *Handbook of Biological Confocal Microscopy.* New York: Plenum Press.

So PT, Dong CY, *et al.* (2000) Two-photon excitation fluorescence microscopy. *Annu. Rev. Biomed. Eng.* 2: 399–429.

Xu C and Webb WW (1997) Multiphoton excitation of molecular fluorophores and nonlinear laser microscopy. In: Lakowicz JR (ed.) *Topics in Fluorescence Spectroscopy.* New York: Plenum Press.

Xu C, Zipfel W, *et al.* (1996) Multiphoton fluorescence excitation: new spectral windows for biological nonlinear microscopy. *Proceedings of the National Academy of Science of the USA* 93(20): 10763–10768.

Interference Microscopy

E Novak, Veeco Instruments, Inc., Tucson, AZ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Interference microscopy is a powerful noncontact metrology technique for reflection and transmission characterization of samples. The field can be divided roughly into two main categories, polarization-splitting interferometers and amplitude-splitting interferometers. In both cases, the light incident on a test sample is first divided into two beams and later recombined to form an interference pattern. This interference pattern is analyzed by one of a variety of methods to determine the difference in the optical paths the two beams traversed. This optical path difference may be used to quantify surface shape, refractive index variations, or thickness variations of the sample to a very high accuracy. This article describes the background of the two categories of interference microscopy, specifics of their implementations for different types of measurements, current state of the technologies, and examples of different measurements performed using these techniques.

Background

Interference fringes were first observed in a microscope by Robert Hooke in 1665. In the late 1800s, several practical versions of interference microscopes entered use to examine transparent specimens, though none gained widespread commercial success. Then in the 1950s, differential interference contrast (DIC) microscopy was invented to increase image contrast when examining semi-transparent samples under a microscope, particularly biological specimens. As this technique does not require staining of samples, and avoids the halo effect common in phase contrast microscopy (*see* **Microscopy:** Phase Contrast Microscopy), such systems became widely used in a variety of biological applications. In the early 1960s, Krug, Rienitz and Shulz published a comprehensive book to summarize all of the various interference microscope designs that had been produced thus far, showing the large depth and breath of research to that point.

With the advent of affordable computers and CCD cameras in the 1970s and 1980s, various commercial systems were developed using a variety of interferometric configurations to quantify the measured interference patterns from small samples. Due to their noncontact nature and ability to provide area measurements, as opposed to the two-dimensional traces produced by contact stylus techniques, such systems gained rapid acceptance in a variety of industries. Performance has steadily improved such that vertical resolution is sub-nm and accuracy on the nm-level is readily achievable. Lateral resolution is limited only by the optics of the microscope, with high numerical aperture objectives achieving resolution below 0.5 μm. Today, commercial systems are used in such measurements as index variations of biological samples, roughness of paper, microfluid channel volume, MEMS properties, hard drive head dimensions, drug coating thickness, and machine part characterization.

Polarization-Division Interference Microscopes

While the concepts behind polarization division interference microscopes have been known for well over a century, they did not gain widespread use until after Georges Nomarski invented the DIC microscope, also referred to as a polarization interference contrast microscope, in 1955. A schematic of a transmission-based and reflection-based Nomarski setup is shown in Figure 1, where the displacement of the beams has been greatly exaggerated for clarity.

The illumination in Nomarski systems is generally from an unpolarized broadband source, such as a


Recombined, interfering beams
Analyzer
Recombined, orthogonally polarized beams
Wollaston prism pair
Converging, orthogonally polarized, beams
Microscope objective
Sheared orthogonally polarized beams
Specimen slide
Condenser lens
Diverging, orthogonally polarized, beams
Wollaston prism pair
Polarized light
Polarizer
Unpolarized light
Light source
(a)
Recombined, Interfering beams
Analyzer
Light source
Condenser lens
Polarizer
Recombined, orthogonally polarized beams
Wollaston prism pair
Converging, orthogonally polarized, beams
Microscope objective
Sheared orthogonally polarized beams
Sample
(b)

Figure 1 (a) Schematic of transmission-based Nomarski interferometer and (b) reflection-based Nomarski interferometer.

tungsten–halogen bulb. A polarizer in the illumination path is then used to set the polarization state of the light incident on a modified Wollaston prism pair. The modified Wollaston prism consists of two birefringent wedge prisms which divide the beam in two parts, each with orthogonal polarization states. The two beams travel in slightly different directions from one another. The condenser lens brings the light to illuminate the sample, with each of the two orthogonally polarized beams slightly sheared from one another. This shear is typically much less than the resolution limit of the microscope objective, typically from tens of nanometers to several hundred nanometers, such that only one image is seen by the observer. After passing through or reflecting from the sample and the imaging microscope objective, a Wollaston prism pair is used to recombine the two polarized beams. Finally, an analyzer is used to bring both beams to a common polarization state, allowing interference between the two beams.

As the system is very sensitive to the position and optical properties of the prisms, different Wollaston prism pairs are used for each objective, usually rotating into the path automatically on a turret as the objectives are changed. In a reflection system, this prism also recombines the displaced beams after they reflect from the test piece; a transmission system will usually have only one Wollaston prism pair after the sample that can handle all objectives, instead of requiring a different recombining prism for each objective.

The observed interference pattern is an image of the gradient in the sample in the direction of shear created by the Wollaston prism pairs. In order to fully characterize the surface, the sample or optics must be rotated to capture shear images in both orthogonal directions. Essentially the technique acts as a high-pass filter, emphasizing edges and lines on the test piece.

With a white-light source, dispersion effects will cause one side of a feature to appear brighter or in a specific color range whereas the other side appears darker or in different colors. This gradient effect confers a pseudo three-dimensional appearance to the specimen. The images are quite colorful, with different colors shearing differently; by adjusting the Nomarski prisms along the optical axis, one can vary the retardation between the two beams, producing more or less contrast or color variation in the observed images.

The Nomarski system has several appealing qualities for surface and index characterization over other interferometric and polarization-based techniques. First, it is a common-path interferometer; with the exception of the slight shear, both beams pass through exactly the same optics. This means that these interferometers are mostly insensitive to vibration, as both interfering beams will be affected in the same manner. In addition, the common path nature of the system reduces the quality requirements on the optics, improving measurement quality and reducing overall system cost. In addition, Nomarski techniques do not suffer the halos associated with phase contrast imaging techniques (*see* **Microscopy:** Phase Contrast Microscopy) and provide better out of focus rejection and higher light levels since they can use the entire aperture of the microscope objective.

For reflection-based systems, the observed fringes relate to the surface slope along the direction of shear; for transmission systems, index of refraction gradients or thickness variations are observed, producing much higher contrast images of biological samples than conventional bright-field techniques. The good out-of-focus rejection mentioned earlier makes possible more accurate optical sectioning of samples, where each vertical layer of the specimen is in focus while all others are out of focus. These features, combined with the fact that high contrast images can be obtained without chemical staining, have made these systems widely used in biology. In addition, the high sensitivity to slope has made DIC systems commonly used in semiconductor inspection applications and other precision surface characterization and defect inspection applications, where automatic image processing is combined with the highly sensitive measurements to quantify both surface and subsurface defects. For instance, Figure 2 shows a bright-field image of a laser diode facet as



Figure 2 Bright field (left) and Nomarski (right) images of laser diode facet defects. Courtesy of Royce Instruments, Inc., Napa, CA.

well as a Nomarski image, with the facet defects greatly emphasized by the Nomarski optics.

Initial systems using differential interference contrast were strictly qualitative, with the user manually rotating the incoming polarization to produce the best contrast for a given sample and visually evaluating the resulting image. As mentioned above, visual inspection of biological specimens and defect review remain primary applications of these devices, though quantitative. By translating the Wollaston prisms laterally or rotating the analyzer in the system, one can phase shift the interference pattern. Storing multiple phase shifted images on a computer, one can obtain quantitative data about the shear using standard phase shifting interferometry equations. In addition to phase shifting through translation of the prism, quantitative data may be performed through analysis of the colors of the observed fringes or through geometric phase shifting techniques. More details on these methods can be found in the articles on **Interferometry:** Phase Measurement Interferometry; and **Interferometry:** White Light Interferometry.

Once quantitative information about the shear between the beams is obtained, the resulting data may be integrated to get back the original surface or index profile. Performing this operation on data with shear in two orthogonal directions allows the complete surface profile to be obtained. Unfortunately, since Nomarski setups are typically employed as add-on modules to standard microscope platforms rather than custom-designed metrology instrumentation, such quantitative phase shifting capability has not been widely commercialized; only a few custom or laboratory systems are in use when compared with white-light optical profilers described below. However, many research groups report nm-level surface characterization, and have developed a variety of techniques to accurately quantify thickness and index changes. The primary limitation of the quantitative techniques comes from the depth of focus of the microscope objective, which limits the vertical heights, thickness range, and index gradients that can be measured in a single measurement. Phase shifting at multiple vertical locations can be performed, but unless greatly increases the complexity of the measurement and reconstruction algorithms.

Amplitude-Division Interference Microscopes

White Light Optical Profilers

Probably the most common amplitude division interferometric microscopes are white-light interferometers, also often called optical profilers. These systems consist of three main elements: the base microscope, with illuminator and imaging optics; an interferometric element to divide and recombine the wavefront, and a scanning mechanism by which the optical path between the test and reference beams may be varied in a known manner. As the name implies, these systems typically employ spectrally broad sources, generally from a tungsten–halogen bulb. Unlike Nomarski interferometers, white light interferometers are used only in reflection-mode, as their noncommon-path nature and low-coherence source preclude interference from thick samples measured in transmission.

Figure 3 shows a schematic of a typical white light interferometer. Light from the illuminator arm, typically in a Kohler configuration, is coupled into the system with a first beamsplitter and passes through a second beamsplitter which is typically inside the microscope objective. This beamsplitter divides the beam into two parts, one of which travels to the sample and reflects from it, while the other reflects from a very high-quality reference surface. The reflected light is then recombined by the same beamsplitter and the resulting interfering light is imaged onto a camera. The static interferogram thus produced is usually by changing the optical path difference between the test and reference beams through translation of the objective with respect to the sample. The resulting signal is analyzed by one of a variety of methods as described below.

White light interferometers generally have two distinct modes of operation. In the first mode, generally referred to as phase shifting mode, a filter



Figure 3 Schematic of white light optical profiler showing the illuminator, and translating interferometric objective.

is used to produce quasi-monochromatic light for the measurement process. This produces a large number of high-contrast interference fringes that obey the classical interference formula:

$$I_i(x,y) = I_t(x,y) + I_r(x,y) + 2\sqrt{I_t I_r}(\cos(\phi(x,y) + \alpha_i) \qquad [1]$$

In the above $I_i(x,y)$ is the irradiance observed at any one point of the image, $I_t(x,y)$ and $I_r(x,y)$ are the irradiances of the test and object beams, $\phi(x,y)$ is the optical path difference between the two beams, and α_i is a phase offset introduced by the interferometric instrument. By varying α_i in a known manner and collecting at least three irradiance patterns, any of the three unknowns in the above equation can be determined; specifically, the optical path difference may be solved for every point. Assuming measurements are in a medium of known and constant refractive index, such that the only contributions to the OPD are height variations rather than index variations, surface height at each point is simply:

$$H(x,y) = \frac{\lambda}{4\pi}\phi(x,y) \qquad [2]$$

Phase shifting techniques produce sub-nm repeatability and very high accuracy, but suffer from a 2π phase ambiguity from the calculation of phase from irradiance data. Thus, this technique cannot handle surfaces with point-to-point steps greater than one quarter of the wavelength of the light used. Calibration methods and further information may be found in the article on **Interferometry:** Phase Measurement Interferometry.

In order to extend interference microscopy to cover large steps, steep slopes, and vertical ranges greater than the depth-of-focus of the microscope objectives, a second technique of fringe analysis may be employed, that of coherence sensing. In this method an incoherent light source is used, such as a tungsten–halogen bulb. Due to the wide spectral range of the source, as interference patterns from different wavelengths add in the observation plane, the observed interference fringes will rapidly wash out for nonzero optical path difference between the two beams. See the article on **Interferometry:** White Light Interferometry, for further details and illustrations of this effect.

With the localization of fringes only at the point of zero optical path, the instrument scans the interference objective over the desired range and then calculates the position at which maximum fringe contrast occurs for each point. Calculating this position across all points within the field creates a height map of the surface; the interference fringes serve as a tool for depth discrimination in much the same way that the pinhole in a confocal microscope does (*see* **Microscopy:** Confocal Microscopy), another technique finding wide use in surface profiling. No phase unwrapping is required, with each pixel height calculated independently of all others, avoiding ambiguities associated with phase shifting methods. The vertical range is limited only by the scan range of the measurement and the working distance of the microscope objectives; current commercial instruments can achieve vertical ranges of over 8 mm. Figure 4 shows the fringes one would observe at a given scan location during measurement of a test piece with three steps. As the OPD between the test and reference arms varies, the fringes will



Figure 4 Localized fringes (left) of a 3-tiered surface structure (right). As the OPD is varied, the fringes will scan through the field, with the point of maximum contrast corresponding to the relative surface height of each pixel.

translate across the steps, and the surface plot at the right can be generated by calculating the scanner location of the peak contrast condition for each pixel.

There are a variety of methods for calculating the position of maximum fringe contrast using the coherence-sensing method. These include center-of-mass calculations of the peak fringe position, various frequency-space techniques and correlation of the measured fringe pattern with a theoretical pattern. Calibration of these systems generally involves repeated measurement of a known step height standard and varying the scanner motion until the step height is accurately calculated, though some systems employ separate distance-measuring interferometers to perform on-the-fly calibration for each scan. Generally speaking, coherence sensing techniques have repeatability in the range of a few nm, as opposed to the sub-nm repeatability of phase shifting techniques. This reduced sensitivity is the trade-off for avoiding the height and slope limitations of phase-shifting techniques. More details can again be found in the article on **Interferometry:** White Light Interferometry.

Recent advances in computing power have enabled an additional method of calculating surface height by combining coherence sensing with phase shifting. Coherence sensing methods are used to determine the point of best fringe contrast, and uses this information combined with the phase calculations to overcome ambiguities caused by large steps or steep slopes. Thus, one can obtain the sub-nm repeatability of phase-shifting methods without limitations on the vertical range or slope of the sample to be measured.

New fringe analysis techniques are extending the utility of these systems even further. Strobed sources are now available which effectively freeze the periodic motion for the instrument; this allows dynamic properties of samples to be measured, from surface deformation under motion to resonance frequency and switching time calculations. By analyzing the multiple interference patterns generated by transparent films deposited on a surface, film thickness, homogeneity, and differences between substrate and film surface properties may be determined.

Interferometric Microscope Objectives

One of the most critical elements in white light interferometers is the interferometric objective which splits and recombines the wavefront to form an interference pattern. Three primary interferometric configurations are used to divide and recombine the wavefront: Michelson, Mirau, and Linnik. Each of the three types of objectives is described below.

For low-magnification objectives, typically 5X or below, a Michelson interferometer configuration is typically used. A schematic of such an objective is shown in Figure 4. The illuminating beam passes through the objective and is divided by a beamsplitter placed just underneath the objective. A portion of the light travels to the test sample and the rest to a high-quality reference surface. The light reflected from each beam path is recombined by the beamsplitter and propagates to the observation plane. Note that it is important that the distance between the beamsplitter and reference surface match the distance between the beamsplitter and focus position of the sample. If the reference surface is defocused, fringe contrast will be reduced, aberrations increased, and overall system accuracy and repeatability will suffer.

This objective configuration has several advantages. First, one can add a Michelson housing to almost any standard objective with sufficient working distance for the beamsplitter, making these objectives easy to produce and relatively inexpensive. Second, the reference surface can be easily changed by the user to closely match the reflectivity of the test piece, ensuring maximum fringe contrast in the interfered beam (*see* **Interferometry:** Phase Measurement Interferometry). Third, provided there is distance between the beamsplitter and reference, one can insert a dispersion-compensating plate into the reference arm to allow measurement of parts beneath a cover glass or other dispersive medium; without such compensation, fringe contrast is generally insufficient for accurate measurements for transmissive media beyond a few hundred micrometers thickness.

As one moves towards higher magnifications, however, the working distance of the objective is typically insufficient to accommodate a large beamsplitter and still leave a reasonable distance between the objective and sample. In addition, a large cube beamsplitter will generally introduce unacceptably high aberrations in these higher numerical aperture objectives. For this reason, objectives from 10X magnification to 50X magnification are typically of the Mirau configuration, shown schematically in Figure 5.

Mirau objectives contain two additional plates compared to a standard bright-field objective: one is coated and acts as a beamsplitter, splitting the incident beam, while a second holds a small, high-quality reference surface and acts as a compensating plate so that optical paths in both arms of the interferometer are balanced (Figure 6). Such objectives are more expensive than Michelson designs, but maintain long working distances even at higher magnifications. Thermal stability becomes



Figure 5 Schematic of a Michelson interference objective used for low-magnification applications.



Figure 6 Schematic of a Mirau interference objective used for medium-magnification applications.

very important, as depth of focus is much reduced over lower-magnification objectives and the path from beamsplitter to reference still must be the same as from beamsplitter to in-focus test object, and most Mirau designs are therefore thermally compensated.

As one moves to even higher magnifications and numerical apertures, such as 75X or 100X, the microscope objectives do not have sufficient working distance to allow for any reasonable beamsplitter after the objective unless the numerical aperture is greatly reduced. To maintain high numerical aperture and high lateral resolution, a Linnik configuration must be used. A schematic of this configuration is shown in Figure 5. In this configuration, two separate microscope objectives are used after a beamsplitter, with one beam again reflecting from a high-quality reference and the other from the sample.

A Linnik objective is generally the most difficult to use and expensive interferometric configuration (Figure 7). High numerical aperture typically limits working distance to a few hundred micrometers. In addition, depth of focus is very small, and thus these objectives must often actively adjust the reference mirror position to maintain focus over long periods of time and environmental conditions. Also, the dispersion and aberrations in the two objectives must be closely matched to ensure good fringe contrast, as there are many noncommon-path optical elements in this design; typically many objectives must be evaluated to find two that suitably match, another contributor to cost. However, these objectives do have the highest lateral resolution, and with an NA of up to 0.95, can measure the steepest slopes due to a large collection angle.



Figure 7 Schematic of a Linnik interference objective used for high-magnification applications.

Applications

White-light interferometers are noncontact, and thus will not damage samples under test. They provide true three-dimensional surface characterization with nm-level accuracy and repeatability, and can be employed in production and laboratory environments. The various interferometric objectives allow for lateral resolutions and ranges to meet most needs; fields of view may even be stitched together to create surface maps whose extent is limited only by the range of the translation stage employed. In addition, each scan is typically quite fast, from under one second in phase-shifting mode to vertical scan rates of up to 100 μm/sec in coherence-sensing mode, with no sample preparation time. While the systems must be properly calibrated, vibration minimized, contrast maximized, and potential error sources such as dispersion and phase change on reflection effects must be managed, they remain one of the most accurate surface characterization tools available.

All of the above factors have enabled the use of white light interferometers in a variety of fields. The semiconductor and data storage industries



Figure 8 Surface plots from a white light optical profiler. (a) Human skin sample, (b) MEMS microgears, (c) binary optic, and (d) 1 Euro coin. Pictures courtesy of Veeco Instruments.

perform critical dimension and surface characterization of various components using these systems, some of which are configured for full wafer-handling capabilities. Systems are also used to measure precision machine parts, optics, and medical instrumentation and implants. The high sensitivity of the coherence sensing techniques allows surfaces with less than 0.1% reflectivity to be measured, so that characterization of paper, abrasives, and even different foods has been measured with these instruments. With the addition of the advanced technologies mentioned above, these systems are also now doing dynamic measurements of MEMS and thermal response characterization of precision surfaces, and also are measuring thicknesses of adhesives, drug coatings, photoresist, and a variety of other semi-transparent layers in various applications. Figure 8 shows several surface measurements, including human skin, MEMS microgears, a binary optic, and 1 Euro coin.


CCD
Imaging lens
Diverger lenses
Beamsplitter
Laser
Phase-shifting reference surface
Microscope objective/ diverger
Sample

Figure 9 Schematic of a micro-LUPI interferometer operating in reflection mode.

Laser-based Interference Microscopes

Another, less common type of amplitude-division interference microscope has recently been commercialized, primarily for use in examining micro-optics. These laser-based systems employ a Tywman–Green interferometric configuration combined with a microscope, and are generally called micro-LUPI (laser unequal path interferometer) systems. A schematic of a micro-LUPI interferometer is shown in Figure 9. A beamsplitter divides the incident laser beam, half of which travels to a generally flat reference surface, while the other half typically travels through a microscope objective that acts as a diverger lens and is incident on the test sample.

Due to the long-coherence length of the laser source, the two optical paths do not have to be equal in order to observe interference fringes, and samples may be measured either in reflection or transmission, depending on the desired test result. Collimated, diverging or converging illumination may be brought incident on the sample, depending on the optics in the test beam and their placement. The diverger elements are noncommon-path optics, and reduce the ultimate accuracy of the system to approximately lambda/10, similar to laser-based Fizeau interferometers.

Micro-LUPI-based systems have several advantages for testing small optics over other interference microscopes. First, the ability to measure both transmission and reflection properties of the optics, as well as different incident illumination schemes, means they can test the optics in their use configuration rather than inferring optical properties based solely on surface measurements. They can determine imaging properties, inhomogeneities and thickness variations in addition to characterizing the surfaces under test. Also, the curved test wavefront better matches spherical test surfaces, minimizing the number of observed fringes and making testing of small aspheres easier. Lastly, these systems can have curved reference surfaces as well as flat, and with the proper configuration aberrations in measurements due to the interferometric microscope can be minimized, ensuring high-quality measurements of the optic under test.

These systems have only phase-shifting measurement capability, as the coherence length of the source is too long for white-light interferometric techniques. Transmission tests necessitate a more complex part handling structure, with both the test piece and reflective return optic needing adjustment for tip/tilt and vertical and lateral translation. Therefore, such systems are more costly and not as versatile as a white light optical profiler, but do provide a valuable capability to the micro-optics community.

See also

Coherence: Coherence and Imaging. **Imaging:** Interferometric Imaging. **Interferometry:** Overview; Phase Measurement Interferometry; White Light Interferometry. **Microscopy:** Confocal Microscopy; Overview; Phase Contrast Microscopy.

Further Reading

Advanced Light Microscopy: Measuring Techniques; *Maksymilian Pluta*; North-Holland (1993).

Born M and Wolf E (eds) (1999) *Principles of Optics: Electromagnetic Theory of Propagation, Interference and Diffraction of Light*, 7th edn. Cambridge University Press.

Creath K (1988) Phase-measurement interferometry techniques. In: Wolf E (ed.) *Progress in Optics*, vol. XXVI, pp. 349–393. North-Holland, Amsterdam.

Hariharan P (2003) *Optical Interferometry*, 2nd edn. Academic Press.

Hariharan P and Malacara D (eds) (1995). Selected Papers on Interference, Interferometry, and Interferometric Metrology. *SPIE Milestone*. MS 110.

Krug W, Rienitz J and Shulz G (1964) *Contributions to Interference Microscopy* (translated from the German edition of 1961 by J. Home Dickson): Hilger and Watts Ltd.

Malacara D (ed.) (1992) *Optical Shop Testing*. John Wiley & Sons.

Massie NA (ed.) (1988). Interferometric Metrology. *SPIE* 816.

Polarvarapu PL (ed.) (1997) *Principles and Applications of Polarization-Division Interferometry*. John Wiley & Sons.

Tolansky S (1970) *Multiple-beam Interferometry of Surfaces and Films*. Dover Publications.

Nonlinear Microscopy

S Lévêque-Fort and P Georges, Université Paris Sud, Orsay, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Nonlinear microscopy has become an important tool for the investigation of biological applications where high resolution and three-dimensional imaging are essential for understanding the underlying biological function. Two-photon excitation fluorescence (TPEF) microscopy has opened the way to nonlinear techniques and is now widely available. As this new technology enables noninvasive study of biological specimens with high resolution, the number of applications in biology and medicine is still increasing. By exploiting autofluorescence of cells or tissues components, or by coupling with genetically modified fluorescent indicators or small extrinsic probes, high contrast and localization can be obtained. Different detection techniques (fluorescence lifetime imaging (FLIM), fluorescence correlation spectroscope (FCS), intensity, and spectral imaging) permits the analyze of several fluorescence properties and so obtains complementary informations.

The successful development of two-photon techniques has generated substantial interest in the scientific imaging community in further developing and exploiting optical nonlinearities for generating new image contrast. All these new developments have strongly benefited from the major advances in ultrafast lasers which have become more compact and reliable. Second- and third-harmonic generation (SHG, THG) as well as coherent anti-Stokes Raman scattering microscopy (CARS) have thus benefited from the fact that it is now easier to generate ultrashort pulses at almost any desired wavelengths. Association of these new nonlinear techniques in the same instrument (TPEF-SHG/TPEF-CARS, TPEF/THG) is commonly encountered and provides a powerful instrumental tool for probing biological samples.

Basic Principles of Two-Photon Microscopy (TPM)

Two photon microscopy is preferred over single photon method in many biological applications due to several intrinsic advantages which arise from having a nonlinear intensity depend absorption. In general, the nonlinear polarization for a material can be expressed as

$$P = \chi^{(1)}E^1 + \chi^{(2)}E^2 + \chi^{(3)}E^3 + \cdots \qquad [1]$$

where P is induced polarization, $\chi(n)$ is the nth order nonlinear susceptibility, and E the electric field vector of the incident light. The first term describes normal absorption and reflection of light; the second term describes SHG, hyper-Rayleigh scattering, sum and difference frequency generation, and the third terms covers multiphoton absorption, third-harmonic generation and stimulated Raman processes.

In 1931 Maria Goppert Mayer predicted that photons of lesser energy can together cause an excitation ‘usually’ produced by the absorption of a single photon of higher energy, in a process call multiphoton excitation. The hypothesis could not be confirmed until the invention of pulsed ruby lasers, in the 1970s, and was first applied to microscopy with the work of Denk *et al.* Two-photon microscopy used the simplest version of her theory: two photons of equal energy (from the same laser) can excite a molecule, and the excitation is similar to that obtained with a single photon possessing twice the energy (Figure 1). Thus, the molecule can emit a fluorescent photon just as if it was excited with a single higher energy photon (Figures 1 and 2). Of course, the absorption of the two photons must occurs nearly simultaneously (~10^{-16} s), resulting in a quadratic dependence on the light intensity rather than the linear dependence of conventional one photon fluorescence.



Figure 1 Jablonski diagram for one and two-photon excitation.



Figure 2 Localization of excitation under two photon excitation (left) compared to one photon excitation (right).

The nonlinear optical absorption property of two-photon excitation, limits the fluorochrome excitation to the point of focus. This localized excitation volume results in greatly improved axial resolution and image contrast compared with conventional microscopy, but also significantly decreases sample photobleaching and photodamage by reducing the region of photointeraction (Figure 2).

Another major advantage of TPEF is its ability to image deeper inside biological samples, owing to the reduced scattering and absorption of near infrared wavelength compared to UV and visible light. Near infrared light (700–1000 nm) is located within the 'therapeutic optical window' where the absorption of the main cells and tissue components is low.

TPEF also permits a high rejection of residual excitation light: in standard one-photon microscopy, the excitation wavelength can be spectrally close to the fluorescence emission band. Filters used to eliminate the leakage of excitation light into the detection channel often cuts off a part of the fluorescence emission. For TPEF excitation and emission band are well separated, and highly efficient filters can remove the residual excitation light without compromising the microscope sensitivity.

Under two-photon excitation, the fluorescence photon flux depends on the square of incident photon flux:

$$F \propto \sigma_{2P} C I^2 \qquad [2]$$

where σ_{2P} is the two-photon cross-section (cm^4 s) with 10^{-50} cm^4 s, called a Goppert–Mayer (GM), C the fluorophore concentration, and I^2 the incident photon flux. The two-photon cross-section is a quantitative measure of the probability of two-photon absorption and as a second-order process is low. As it is difficult to directly measure two-photon cross-sections, we usually use the cross-section of two photon-induced fluorescence (σ_{TPEF}) as the product of two photon absorption cross-section (σ_{2P}) with the fluorescence quantum yield ϕ_F $\sigma_{TPEF} = \sigma_{2P}\phi_F$.

Intrinsic fluorophore, such as nicotinamide adenine dinucleotide (NADH), have low cross-sections ($<10^{-4}$ GM), usual fluorescent dye in biology ranging between 1 and 300 GM and quantum dots approaching 50 000 GM. As the probability of two-photon absorption is quiet low, high incident photon flux needs to be delivered to the sample to generate efficient absorption:

$$I \propto E \frac{1}{\Delta\tau\omega^2} \qquad [3]$$

I depends on the energy per impulsion E (mean power/pulse frequency), the pulse duration $\Delta\tau$, and the beam waist ω. The expression of I clearly demonstrates that by using ultrashort pulses and by reducing the beam waist, one can maximize the incident flux. Currently the most commonly used laser source for multiphoton microscopy is the femtosecond titanium-sapphire (Ti:Sa) system. These pulsed femtosecond lasers deliver a 100 fs pulse train at a repetition rate of ~80 MHz with a tuning range from 700 to 1000 nm. The beam waist depends on the objective numerical aperture. If we consider a Gaussian beam profile, with radial and axial parameters of σ_r and σ_z respectively and for a high numerical aperture NA > 0.8:

$$V = \left(\frac{\pi}{2}\right)^{3/2} \sigma_r^2 \sigma_z \qquad [4]$$

with $\sigma_r \approx 0.52\lambda/\sin\alpha$ and $\sigma_z \approx 0.76\lambda/(1-\cos\alpha)$. where λ is the excitation wavelength, α is the one-half of the objective angular aperture ($NA = n \sin\alpha$, n index of the immersion medium). So for a wavelength of 780 nm and an objective working with water immersion with a numerical aperture of 0.9, the excitation volume can be described as an obloidal shape with a radial axis of typically 500 nm and an axial axis of 1.90 μm. It corresponds to an excitation volume of ≈1 fL ou 1 μm^3. Higher resolution can be achieved using an immersion oil objective (NA = 1.3) at the cost of a higher cost and a shorter working distance.

Typical powers used to generate two-photon excitation without damaging the sample are between 1 and 10 mW for the mean incident power. For a laser beam of 1 mW, at a rate of 76 MHz with 100 fs pulse duration, and with an objective leading to a surface in the focal plane of 1 μm^2, the peak power is 0.13×10^9 W/cm^2 at the focal plane of the sample. Of course each samples has its own limits regarding incident intensity, and the key to use TPEF safely is always to reduce the excitation intensity in order to avoid photodamage.

Fluorescent Probes

Biological systems often possess endogenous fluorescent molecules that can be imaged, revealing important sample characteristics without the need of labeling (Figure 3a,b). Cells or tissues can be imaged through their autofluorescent, with the emission of several components, NADH, flavins, collagen fibers, etc. Pharmacology studies also exploit the natural autofluorescence of aromatic drugs, to



Figure 3 Applications showing various capabilities of TPEF: (a) Hela cells in transmitted image and corresponding autofluorescence image (b) under TPE (780 nm). (c) After adding 40 μM of an anti-HIV drug on similar cells, intrinsic fluorescence of the drug allows us to find its preferable localization inside the cytoplasm.

localize drug inside cells and study their reactivity without any labeling.

However, for some specific applications where the autofluorescence is too low, or if one needs to specifically identify different cells components (Figure 3g), or follow protein mobility, the samples need to be labeled your with extrinsic fluorophores. Extrinsic fluorophores are organic molecules, first developed for one-photon excitation, and are used under two-photon excitation with more or less efficiency as OPE and TPEF have different quantum mechanical selection rules, and the TPE spectrum is not always scaled to the half of OPE spectrum. Current works are focused on the development of specific markers for TPE or SHG to enhance contrast and also reduce incident laser power.

Two new generations of marker have been developed: the development of the green fluorescent protein (GFP) and its mutant introduces a convenient method for monitoring gene expression in cells and tissues; quantum dots are the latest focus in fluorescence labeling. They are promising reporters as their size (1–100 nm) induces a specific narrow emission spectrum in the visible. Absorption can occur over a wide range of short wavelengths because of the existence of multiple electronic states. Time-domain measurement has been performed with CdSe quantum dots which shows multiexponential decay with fluorescence lifetime of 3.4 ns, 16.1 ns, and 35.6 ns, much longer than autofluorescence lifetimes, hence providing greater sensitivity than intensity-based measurement. However, like GFPs, quantum dots display blinking behavior.

Two-photon Applications

Two-photon excitation has become the technique of choice for fluorescence microscopy and is applied to a variety of imaging tasks on samples ranging from single molecules to thick tissues. Owing to the high NIR penetration depth, biopsies and living tissue can be noninvasively investigated by morphological and functional fluorescence imaging of endogenous (Figure 3b) or exogenous fluorophores to depths of more than 300 μm. In genomics, multiphoton multicolour fluorescence *in situ* hybridization (FISH) are used to label various specific regions of DNA, and identified different genes and chromosome regions. In pharmacology, a higher penetration and localization of photodynamic therapy is observed, detection of low drug concentration inside cells facilitates the reactivity comprehension (Figure 3b,c). Neurobiologists investigate calcium dynamics inside brain slices and live animals, or follow neurotransmitter diffusion. Of course, these are only a few examples among the increasing number of applications, and some of them are illustrated in Figure 3.

Two-photon Instrumentation

Two-photon microscopes are now commercially available, however a large number of groups have built their own from separate components or by modifying an existing confocal microscope. Home-made microscopes present a higher configuration flexibility for excitation/detection at a much lower price.

Femtosecond, picosecond, and continuous wave (CW) laser sources have been used for TPM. By using a cw laser sources such as ArKr and NdYag, the average power increases by ~200-fold to achieve the same excitation rate obtained with a femtosecond laser, which is not highly desirable for biological samples. So as previously shown, the TPE efficiency is higher with shorter pulses, so Ti:Sa femtosecond lasers are most commonly used.

One of the drawbacks of TPM is that it is a laser scanning technique. To reconstruct an image you need either to move the sample or the laser beam. Most commonly x–y mirrors driven by a galvanometer scanner are used to scan the laser at the focal plane of the sample. Lenses are used to expand the beam to overfill the objective back aperture and so obtain a diffraction limited focal volume. The excitation light enters the modified inverted epi-fluorescence microscope (Figure 4).



Figure 4 Schematic of a typical two-photon microscope.

A dichroic mirror transmits the excitation light and reflects fluorescence. High numerical aperture objectives are used to provide a high resolution but also maximize fluorescence collection. They are usually mounted on piezo-electric translators to provide a fast *Z*-scan. The fluorescence is collected by the same objective, reflected by the dichroic to the detector. A filter is placed in front of the detector to remove any residual excitation light. Typical detectors used are the photomultiplier tube (PMT), microchannel plate-PMT (MCP-PMT), avalanche photodiode or charge-coupled device (CCD) cameras. PMTs are the most commonly implemented because they are robust, low-cost, have large, active areas, and good sensitivity.

As TPE is intrinsically confined to the focal volume, two-photon microscopy unlike confocal microscopy, does not need emission pinholes and descanning optics to achieve axial depth discrimination Some authors have, however, added a pinhole to enhance resolution but at the cost of important sign al loss. Concerning the design of the detection pathway, depending on the size of the sample scanned, the objective magnification and the detector area, one may need to use a lens to collect the fluorescence onto the detector.

Fluorescence Detection

Contrast in fluorescence imaging can be provided through several complementary parameters such as steady-state intensity, spectral dependence (at absorption and emission), or fluorescence lifetime.

Intensity Imaging

Intensity images are obtained by summing all the incoming photons during an acquisition time (typically ~1 to 10 ms) which strongly depends on the fluorescence quantum yield of the sample. The whole samples intensity image is obtain by scanning the beam on the focal plane with the $X-Y$ scanner, leading to an acquisition time of 25 s for a 50×50 μm image (1 μm step).

Spectral Imaging

Spectral imaging can be a powerful way to discriminate different molecules, and to identify cellular components or perform co-localization of different proteins. It can be performed by either using an interference filter in front of the detector to extract the contribution in a specific band, or more precisely with a spectrometer. However, autofluorescent spectral bands are usually broad and sometimes it is difficult to separate the different emissions. Extrinsic trackers are thus used to labels specifically, for example, the nucleus, the plasma membrane, and mitochondria, and each tracker usually emits in a specific and well-known spectral band, allowing to easily discriminate and localize the different cellular components. Quantum dots offer narrow emission spectra and allow high spatial resolution, and with the rapid development of their functionalization, they should lead to rapid progress in intracellular imaging.

Fluorescence Lifetime Imaging (FLIM)

Imaging of fluorescence lifetimes is a useful contrast-enhancing method that provides information related to the microenvironment with spatial resolution. The fluorescence lifetime τ corresponds to the average time a fluorophore stays in its excited state is given by $\tau = 1/(k_f + k_{nr})$ with k_f the radiative decay and k_{nr} the nonradiative decay rate.

The radiative decay rate is a characteristic property of a molecule and therefore may be used to contrast different chemical species or fluorophores.

The nonradiative decay rate is a function of the local environment of an excited molecule, and so fluorescence lifetime measurements can provide information about environmental changes (e.g., pH, pO_2, $[Ca^{2+}]$). Furthermore, different cellular probes or tissue components with similar emission spectra but different lifetimes can be distinguished. Another advantage of lifetime measurement is that as a relative measurement of the fluorescence intensity, it does not depend on a non-uniform intensity excitation of the sample, and also does not depend on molecular concentration, allowing one to detect very low quantity of molecules.

Following a delta excitation, the fluorescence intensity de-excitation is given by$I(t) = I_0\, e^{(-t/\tau)}$, with I_0 the initial amplitude. Fluorescence lifetime measurement has been demonstrated either in frequency or time-domains. Time-resolved measurements in the frequency domain are based on the determination of demodulation M and phase shift $\Delta\varphi$ and require modulated light sources (modulation frequency $\omega = 2\pi f$).

The excitation source $I_E(t)$ and induced fluorescence $I_F(t)$ can be written as:

$$I_E(t) = I_{E0} + I_{E\omega}\cos(\omega t + \varphi_E)$$
$$I_F(t) = I_{F0} + I_{F\omega}\cos(\omega t + \varphi_F) \qquad [5]$$



Figure 5 Time course of excitation and emission light in frequency domain fluorescence lifetime measurements techniques.

In the case of fluorescence with mono-exponential decay, the lifetime τ can deduced from the relations (Figure 5):

$$M = \frac{I_{F\omega}/I_{F0}}{I_{E\omega}/I_{E0}}. \qquad \omega\tau = \tan(\Delta\varphi) = \sqrt{\frac{1}{M^2} - 1} \qquad [6]$$

In order to translate the phase and demodulation information from the 80 MHz frequency to a lower kHz frequency, a modulated gain $G(t)$ at the frequency ω' can be applied to the detector (heterodyne detection):

$$G(t) = G_0 + G_{\omega'}\cos(\omega' t + \varphi_G) \qquad [7]$$

The detector response $S(t)$ is thus proportional to the fluorescence intensity:

$$S(t) = G_0 I_{F0} + \frac{G\omega' I_{F\omega}}{2}\frac{1}{\sqrt{1 + (\omega\tau)^2}} \times \cos[(\omega - \omega')t + \varphi_G - \varphi_E + \Delta\varphi] \qquad [8]$$

In the time-domain, the single point detection system is called time-correlated single-photon counting (TCSPC). The principle of the TSCPC system is shown in Figure 6. For each excitation pulse a trigger signal is sent to a time-to-amplitude converter (TAC) within which a capacitor starts charging linearly with time. Upon arrival of each fluorescence photon on the detector a second trigger pulse stops the capacitor charging. The charge is proportional to the delay between the excitation pulse and the fluorescence photon. By repeating the measurement over many thousands of excitation pulse, a histogram of photon arrival can be build up. As each photon must be record individually, the incident power is reduce to avoid the detection of only photons from the beginning of the decay (pile-up) which would lead to shorter lifetimes. To match detector dead-time and TAC counting rate, the TAC is oftenly used in reverse mode: the fluorescence photon starts the TAC and the following pulse stops it.



Figure 6 Schematic of time correlated single photon counting system.



Figure 7 Typical instrumental response of MCP-PMT (black curve), and fluorescence decay curve of rhodamine B (grey curve) with $\tau \sim 1.7$ ns.

Typical detectors used are the photomultiplier tube (PMT), microchannel plate-PMT (MCP-PMT), and avalanche photodiode.

Typical instrumental response of our MCP-PMT is represented in Figure 7 (black curve) leading to a resolution of 30 ps. Depending on the fluorescence quantum yield of the sample, in order to have a good signal to noise ration, acquisition time is ranging between 1 and 30 s per point. Fluorescence decay of rhodamine B with a lifetime $\tau \sim 1.7$ ns is also presented in Figure 7.

For both detection approaches, single point lifetime measurements can be extended to lifetime imaging by synchronizing the sample scanning and the lifetime detection. However, due to the long time acquisition needed, images are only limited to small interesting areas rather than the whole sample. We will see in the recent development section below, new ways to overcome this issue.

Fluorescence Correlation Spectroscopy (FCS)

FCS experiments are performed by recording fluorescence intensity fluctuations (i.e., fluorescence bursts (Figure 8)) from the small focal volume (<1 fl). Applications include diffusion, chemical reactions, molecule concentration, or hydrodynamic flow–FCS under TPE benefits from all the advantages of TPE versus OPE.

Various experimental parameters can be extracted through temporal analysis of fluorescence intensity fluctuations by calculating the autocorrelation or cross-correlation of the fluorescence signal defined as:

$$g(\tau) = \frac{\langle I_{\mathrm{F}}(t) I_{\mathrm{F}}(t+\tau)\rangle}{\langle I_{\mathrm{F}}^2(t)\rangle} = \frac{\int I_{\mathrm{F}}(t) I_{\mathrm{F}}(t+\tau)\mathrm{d}t}{\int I_{\mathrm{F}}^2(t)\mathrm{d}t} \qquad [9]$$



Figure 8 Fluorescence intensity raw data along the time. Bursts are observed when molecules cross the focal volume.



Figure 9 Correlation function observed for microspheres placed in different viscous solution.

where I_{F} is the time-dependent fluorescence signal. By considering that the fluorescence intensity fluctuates around a mean value:

$$I_{\mathrm{F}}(t) = \langle I_{\mathrm{F}}\rangle + \delta I_{\mathrm{F}}(t) \qquad [10]$$

the autocorrelation function can be written as:

$$g(\tau) = 1 + \frac{\langle \delta I_{\mathrm{F}}(t) \delta I_{\mathrm{F}}(t+\tau)\rangle}{\langle I_{\mathrm{F}}^2\rangle} \qquad [11]$$

FCS have been extensively used to extract diffusion coefficient of small fluorescent latex bead in solution, showing the influence of the bead radius or solvent properties. Figure 9 clearly exhibits the influence of the viscosity of the solvent on the diffusion of microspheres. Single molecule detection has also been reached. FCS as also been extended to biological applications where the low background associated with TPE and the reduced autofluorescence is critical. Diffusion of microbeads inside cells cytoplasm or bacterial biofilms have been successfully demonstrated.

Recent Developments in Two-Photon Microscopy

Towards video microscopy

All the nonlinear microscopies share an important limitation: the image build up pixel-by-pixel by scanning across the sample, leading to long-time acquisition. Depending on the sample's emission and the area studied, scanning rates between 0.5 Hz and 30 Hz can be reached for intensity images. To speed up this acquisition time, a first approach is based on a line excitation, in combination with widefield CCD detection. This provides real-time image acquisition rates at the expense of a reduced axial resolution (5 μm instead of 1 μm). A more ideal way of spreading the available excitation power over the sample and speed up image buildup, is the simultaneous use of several well separated foci, each of them generating a diffraction limited spot. In combination with whole field detector, as with a CCD camera, image acquisition rates can be strongly enhanced without compromising resolution. The spacing between the foci must be carefully chosen in order to avoid out-of-focus interference. By introducing time-delay between the different foci, larger than the pulse duration, each foci of a microlens array can be position very closed without loss of resolution. An alternative way has been proposed; a special beamsplitter has been developed to create multiple beams with a higher efficiency, furthermore this setup inherently induced time-delay between each foci. Time-domain has been demonstrated in both approach, and FLIM maps on cells imaging have been obtained in only few second with 200 ps time resolution.

Sharpen the focal point

Nonlinear microscopy facilitates 3D-imaging but the resolution is still limited to 180 nm in the focal plane and 500–800 nm along the optical axis. According to the diffraction theory, the resolution of a focusing light microscope is related to the size of its focal point. In the mid-1990s, new concepts appeared to break this diffraction theory and sharpen the focal volume. In 4-pi microscopy the sample is placed between two large NA objective lenses in a single axis at their common focus. Coherent interference of beams passing through the two lenses generate a point spread function whose central maximum is 3–4 times narrower than in the normal confocal case, but which also has side lobes. This last issue can be overcome using two-photon excitation. A two-photon 4-pi microscopy can thus result in a resolution of ~100 nm in all directions, and has been demonstrated successfully on filamentous actin and immunofluorescently labeled microtubules. However, a 4-pi microscopy requires the sample to be thin and mounted between two coverslips, unless one of the lenses is a dipping lens. Recent development on sample chambers allows one to overcome this issue, and results in live mammalian cells have been shown. A compact 4-pi commercial version has recently been proposed (Leica), achieving a seven-fold-improved axial resolution (80 nm) compared to the classical two-photon microscope.

Another technique, also developed by Professor Hell's group, is called stimulated emission depletion (STED) microscopy. The fluorophore in the fluorescent state S1 is stimulated to the ground state S0 with a doughnut-shaped beam. The depletion of the S1 saturates with increased I_{STED} intensity, and therefore establishes a nonlinear relationship between the fluorescence and the intensity applied to the STED. The saturation of S1 depletion is the essential element for breaking the diffraction limit as it confines fluorescence to the center. Spot size is not limited, but in practise depends on the quality and the saturation factor limited depletion. Using STED microscopy with wavelengths of 750–800 nm leads to a lateral resolution of up to 28 nm on single molecules experiments.

STED microscope has been successfully combined to 4-pi microscopy, and lateral resolution of 30–40 nm has been demonstrated.

Others Nonlinear Imaging Techniques

The success of two-photon microscopy has opened the way for other nonlinear microscopy. As opposite to multiphoton fluorescence absorption techniques where the induced signal is incoherent fluorescence, the signal generated by harmonic generation and stimulated Raman scattering is coherent with specific directional and polarization properties, as such fluorescence and harmonic images are derived from fundamentally different contrast mechanisms. However, both techniques share many features like intrinsic three-dimensionality, reduce photobleaching or deep sectioning, and require essentially identical equipment, allowing one to combine these two techniques as discussed further below.

Second-Harmonic Generation Microscopy

SHG is a second-order nonlinear optical process that can only arise from a medium lacking a center of symmetry, for example, an anisotropic crystal or at an interface of a membrane. SHG can be used to image tissue, muscles, cells membranes, or protein array, and has been recently reported to enhance membrane potential by using voltage sensitive dye.

SHG does not arise from an absorptive process, as the intense laser field induces a nonlinear, second-order, polarization in the assembly of molecules, resulting in the production of a coherent wave at exactly twice the incident frequency (half the wavelength). As represented in Figure 10, for an excitation at 800 nm, the SHG is observed at 400 nm and depending on the fluorescence properties of the molecule, a broadband fluorescent spectra is emitted in the visible.

Contrary to TPEF, where the emission properties depend only on the molecular properties and are independent of the laser source, the spectral and temporal characteristics of SHG are derived from the laser source. The SHG is temporally synchronous with the excitation pulse and its bandwidth is $1/\sqrt{2}$ of the laser's bandwidth. As SHG is an instantaneous process, the signal is only generated during the duration of the laser pulse (Figure 11), in contrary to TPEF where de-excitation of the molecules can occur over several nanoseconds after the pulse excitation.

A major difference between SHG and TPEF is that SHG requires a noncentrosymmetric environment to produce a signal. By examining the second term of eqn [1] $P = \chi^{(2)}E^2$ where the polarization and electric field are vector quantities and $\chi^{(2)}$ is a tensor, this condition is only satisfied for a birefringent crystal, an order array, or an interface. For example, the induced polarization from molecules in a dye cuvette (centrosymmetric sample) would be equal and opposite in all directions, leading to a vector sum zero. The SHG propagation is essentially in the forward direction, and the emission pattern is confined to twin lobes in the case of surface generation, or a cone in the case of volume generation. The off-axis of the two lobes critically depend on the tight focus of the driving field.



Figure 10 Wavelength domain for two-photon induced fluorescence and second-harmonic generation: excitation meets the same criteria and Ti: Sa are typically used in the range 700–1000 nm. For a typical excitation at 800 nm, fluorescence will be observed over ~450 nm, and SHG, at exactly 400 nm.

The total radiated SHG power can be derived by integrating the radiation profile from all the emission directions: $P_{\mathrm{SHG}} = \frac{1}{2}\theta_2 N^2 \sigma_2 I_0^2$ with $\sigma_2 \propto |\chi_2|^2$, I_0 the driving field intensity at the focal center, N the effective number of radiative molecules, and $\theta_2 \approx (0.1\lambda/w_0)^2$.

A schematic of a typical SHG/TPEF microscope is shown in Figure 12. The excitation source is a mode locked Ti:Sa laser which delivers ~120 fs at 76 MHz. The laser light is focused into the sample with a water immersion microscope objective (Olympus, LUMplanFl 60x) and the resultant SHG is collected in a forward direction, while TPEF is collected in the backward direction.

Figure 13 illustrates SHG and TPEF images of Di-6-ASPBS molecules under 880 nm excitation.



Figure 11 Typical time-response for two-photon induced fluorescence and SHG. SHG signal is an instantaneous process whereas fluorescence emission can occur several nanoseconds after the pulse excitation.



Figure 12 Schematic of SHG setup combined with TPEF extracted from (DM dichroic mirror, MO microscope objective NA 0.9 water immersion, C condenser, F colored glass filter, BP bandpass filter, PMT photomultiplier tube). Reproduced with permission from Moreaux L, Sandre O, Blanchard-Desce M and Mertz J (2000) Membrane imaging by simultaneous second-harmonic generation and two-photon microscopy. *Optics Letters* 25: 320–322, © 2000 Optical Society of America.



Figure 13 (a) SHG and (b) TPEF of two adhering vesicles labeled with Di-6-ASPBS (equatorial slice) excited at 880 nm. (c) The forward-detected SHG spectra (left peak) and the backward broad band fluorescence spectra (right peak). The Stokes shift in fluorescence leads to an important spectral separation between the two peaks. An expanded view of the SHG peak is presented in the inset. Reproduced with permission from Moreaux L, Sandre O, Blanchard-Desce M and Mertz J (2000) Membrane imaging by simultaneous second-harmonic generation and two-photon microscopy. *Optics Letters* 25: 320–322, © 2000 Optical Society of America.

The total acquisition time for the images was 1.5 s for an excitation power less than 1 mW. The adhesion area where the membranes are fused exhibits a centrosymmetric molecular distribution wherein TPEF is allowed, but not SHG. The corresponding forward-detected emission spectra of SHG (left peak) and TPEF (right peak) is shown in Figure 13c.

Third-Harmonic Generation (THG)

Third harmonic generation takes advantage of the discontinuity of third-order nonlinear susceptibility $\chi^{(3)}$ at material interfaces. At the focus point of an input laser beam with wavelength λ, this discontinuity gives rise to a new wave in the forward direction at the third-harmonic, $\lambda/3$. This signal can be analyzed in the transmission mode either with a single pixel detector or with a CCD camera. As with the other nonlinear techniques, THG offers a high 3D sectioning capability. Since all materials have nonvanishing third-order susceptibilities, THG microscopy can utilized as a general-purpose microscopy technique, with no need for fluorescence labeling or staining. Experimental setup for THG are very closed to SHG microscope. The need for efficient THG in the sample, together with low average laser power to avoid heating, dictates a laser source that operates with femtosecond pulses. The lasers that are often used THG microscopy are a synchronously pumped OPO at the wavelength of 1500 nm, a low repetition-rate OPA at 1200 nm and a Cr:Forsterite laser at 1240 nm. All these lasers are in the infrared above 1200 nm, thus generating THG signals in the visible range. These visible signals are compatible with the collection optics. A infrared laser undergoes low scattering, however absorption in water strongly increases.

THG have been demonstrated from subcellular to millimeter-size organisms with imaging of nerve cells, chloroplasts of a leaf, or Ca^{2+} intracellular dynamics.

Coherent Anti-Raman Stokes (CARS)

Chemical imaging by use of inherent molecular vibration signals avoids the photobleaching problem and perturbations to cell function induced by fluorophore labeling. Confocal Raman microscopy can provide 3D spatial resolution but it requires high average power due to small cross-section of Raman scattering, or long-time exposure which is not desirable in studying dynamic living system.

The above difficulties can be circumvented by multiphoton vibrational microscopy based on coherent anti-stokes Raman scattering (CARS). CARS is a four-wave mixing process in which a pump field $E_p(\omega_p)$, a Stokes field E_S (ω_S), and a probe field $E_{p'}$ ($\omega_{p'}$). Interact with a sample and generate an anti-Stokes field E_{AS}, at the frequency $\omega_{AS} = \omega_p - \omega_S + \omega_{p'}$. In practise, the pump and the probe fields derive from the same laser $\omega_p = \omega_{p'}$ and $\omega_{AS} = 2\omega_p - \omega_S$. The energy diagram of CARS is shown on Figure 14.

The CARS intensity is the square modulus of the induced polarization, $P^3 = \chi^{(3)} E_p^2 E_s$, with $\chi^{(3)}$ the third-order susceptibility.

The application of the CARS process to microscopy opens up a new method for chemical imaging. In CARS microscopy, the signal is also dependent on the square of the pump field intensity, so the temporally and spatially overlapped pump and Stokes laser pulses tightly focused into a sample, generate a signal of a small excitation volume ($<1\ \mu m^3$). As with all other nonlinear imaging techniques, the image is obtained by raster scanning the sample or the laser beams. The vibrational contrast in CARS microscopy arises from signal enhancement when $\omega_p - \omega_s$ is tuned to Raman-active vibrational frequency Ω. CARS signal generation needs to fulfill the phase-matching condition, $l < lc = \pi/|\Delta\mathbf{k}| = \pi/|\mathbf{k}_{as} - (2\mathbf{k}_p - \mathbf{k}_s)|$, where $\mathbf{k}_p$, $\mathbf{k}_s$, and $\mathbf{k}_{as}$ are wavevectors of the pump, Stoke and CARS fields, respectively, and $\Delta\mathbf{k}$ is the wavevector mismatch.

CARS presents several advantages similar to TPEF: high 3D sectioning capabilities, a low scattering and absorption of the excitation beams. CARS signal is higher in frequency than one-photon fluorescence, so it can be detected in the presence of a strong fluorescent background. Vibrational contrast is intrinsic to biological samples. Fluorescent probes are not necessary and photobleaching is thus circumvented. The coherent signal accumulation in the CARS process produces a strong and directional signal, making CARS microscopy much more sensitive than the conventional Raman microscopy. Consequently, CARS microscopy requires only a moderate average power tolerable by biological samples and has a high data acquisition speed. However, CARS microscopy is not without shortcomings. First, the intrinsically weak induced nonlinear polarizability requires sophisticated laser excitation sources with high peak power and moderate average power, and with low jitter. Second, unlike fluorescence imaging, CARS measurement is not background free, and the nonresonant signal limits the image contrast.



Figure 14 Energy diagram for Coherent anti-Raman spectroscopy (CARS).

The typical setup is very similar equipment compared to TPEF and SHG. The main difference arise from the excitation, two laser beams, the pump, and Stokes laser beams overlapping (in space and time) and are tightly focused into the sample using a high NA objective. The CARS signal can be detected in the forward (F-CARS) and the epi-detection (E-CARS). Unlike fluorescence emission and spontaneous Raman scattering, the radiation pattern of CARS is dependent on both the size and shape of a scatterer. The two detection geometry are thus complementary, the forward detection is suitable for imaging objects of a size comparable to or larger than the excitation wavelength.

For smaller objects, the F-CARS contrast is limited by the large nonresonant background from the solvent. Epi-detected CARS (E-CARS) microscopy provides a sensitive means of imaging objects having an axial length much smaller than the excitation wavelength because it avoids the large background from the solvent.

On the application side, CARS microscopy has been used for mapping the distribution, orientation, and diffusion of specific molecules in dynamic samples, for imaging lipids, proteins, and chromosomes in unstained live cells, and for monitoring cellular processes. CARS is a very promising technique to image small molecules such as lipids, hormones, and drug molecules, for which fluorescence labeling is prone to alter their function in cells and tissues. As for SHG, CARS microscopy is often combined with TPEF in order to obtain simultaneously the complementary contrasts.

Conclusion

Since its introduction more than a decade ago, two-photon fluorescence microscopy has quickly become a standard tool in biophotonic with applications ranging from the study of single molecules to thick tissue imaging. TPEF has opened the way to new coherent nonlinear imaging techniques such as SHG, THG, or CARS which all shared a high spatial resolution. Based on different contrasts these different approaches are often combined for a more complete diagnosis. With developments of new low cost, compact, and reliable lasers with tuning wavelength covering the spectra of a wide range of endogenous or extrinsic markers, nonlinear imaging will continue its successful implementation outside physics labs. Development of endoscopy systems in which ultrafast pulse duration is preserved, will open a new range of *in vivo* studies. Nonlinear imaging still has more to offer and will definitely be a powerful tool for biomedical applications.

See also

Microscopy: Overview. **Nonlinear Optics, Basics:** $\chi^{(2)}$–Harmonic Generation; $\chi^{(3)}$–Third-Harmonic Generation. **Nonlinear Sources:** Harmonic Generation in Gases. **Spectroscopy:** Second Harmonic Spectroscopy.

Further Reading

Cheng J and Xie XS (2004) Coherent anti-stokes Raman scattering microscopy: instrumentation, theory and applications. *Journal of Physical chemistry B* 108: 827–840.

Gratton E, Breusegem S, Sutin J, Ruan Q and Barry N (2003) Fluorescence lifetime imaging for the two-photon microscope: time-domain and frequency-domain methods. *Journal of Biomedical Optics* 8: 381–390.

Hell SW (2003) Towards fluorescence nanoscopy. *Nature Biotechnology* 21: 1347–1355.

Konig K (2000) Multiphoton microscopy in life sciences. *Journal of microscopy* 200: 83–104.

Moreaux L, Sandre O, Blanchard-Desce M and Mertz J (2000) Membrane imaging by simultaneous second-harmonic generation and two-photon microscopy. *Optics Letters* 25: 320–322.

Schwille P, Haupts U, Maiti S and Webb WW (1999) Molecular dynamics in living cells observed by fluorescence correlation spectroscopy with one- and two-photon excitation. *Biophysics Journal* 77: 2251–2265.

So PTC, Dong CY, Masters BR and Berland KM (2000) Two photon micrscopy excitation fluorescence microscopy. *Annual Review of Biomedical Engineering* 399–429.

Squier J and Muller M (2001) High resolution nonlinear microscopy: a review of sources and methods for achieving optimal imaging. *Review of Science Instruments* 72: 7.

Zipfel WR, Williams RM and Webb WW (2003) Nonlinear magic: multiphoton microscopy in the biosciences. *Nature Biotechnology* 21: 1369–1377.

Zipfel WR, Williams RM, Christie R, Nikitin AY, Hyman BT and Webb WW (2003) Live tissue intrinsic emission microscopy using multiphoton-excited native fluorescence and second harmonic generation. *Proceedings of the National Academy of Science of USA* 100: 7075–7080.

Phase Contrast Microscopy

C J R Sheppard, National University of Singapore, Singapore

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Many biological specimens behave as phase objects, that is, they alter the phase of the light transmitted through them, rather than its intensity. Similarly, reflection from a surface with height variations alters the phase of the reflected light. Observation of phase objects requires special imaging techniques. These include defocusing, dark field, Zernike phase contrast, Schlieren imaging, Hoffmann modulation contrast, differential phase contrast, interference microscopy, shearing interferometry, Nomarski differential interference microscopy, and digital phase retrieval. The imaging performance of these different methods are most easily appreciated and compared by consideration of the transfer function approach. In particular, we can consider weakly scattering objects and slowly varying phase objects as special cases.

When a thin unstained biological specimen is illuminated, in general the transmitted light suffers changes in amplitude, phase, and polarization. The change in polarization is related to the birefringence of the sample, which is neglected in the following. Thus the object (complex) amplitude transmittance can be written:

$$t(x,y) = a(x,y)e^{i\phi(x,y)} \qquad [1]$$

where $a(x,y)$ is real and represents the modulus (also called amplitude) of the light wave on exiting from the sample, and $\phi(x,y)$, also real, represents the phase. In a perfect microscope, we observe the intensity of the transmitted light, so the image is given by

$$I(x,y) = |a(x,y)e^{i\phi(x,y)}|^2 = a^2(x,y) \qquad [2]$$

Thus the phase information is invisible in the image. A perfect microscope does not image phase variations in the object, but results in an image that depends on the amplitude of the transmittance, called amplitude contrast. Usually the change in modulus is also small, so that the image will exhibit weak contrast, which may not be discernable. In order to render the phase variations visible it is necessary to modify the microscope in one of a number of different ways.

This conclusion is also relevant in incident light microscopy of surface structures. Then phase changes result from variations in surface height, and can be made visible by phase contrast microscopy. Quantitative measurement of the phase allows quantitative measurement of the surface profile. But care must be taken to avoid errors caused by phase change on reflection from a conducting material, or from effects of the numerical aperture of the optical system. In transmission microscopy quantitative phase measurement can be useful too, for example giving the concentration of a solute.

Some of these phase contrast methods are easily understood using the simple imaging model described above. Others are more easily appreciated by considering imaging in terms of Fourier optics, equivalent to Abbe's theory of microscope imaging. We introduce the angular spectrum of the object amplitude transmittance:

$$T(m,n) = \int_{-\infty}^{\infty}\int_{-\infty}^{\infty} t(x,y)\exp[-i2\pi(mx+ny)]\mathrm{d}x\,\mathrm{d}y \qquad [3]$$

where m,n are spatial frequencies in the x,y directions. We can write for the object amplitude transmittance:

$$t(x,y) = e^{b(x,y)} \qquad [4]$$

where $b(x,y)$ is in general complex. For a weak object we have

$$t(x,y) \approx 1 + b(x,y) \qquad [5]$$

and the spectrum is

$$T(m,n) = \delta(m)\delta(n) + B(m,n) \qquad [6]$$

where δ is a Dirac delta function and $|B| \ll 1$. The problem with imaging of phase arises because a change in the imaginary part of b produces only a small change in the modulus of t.

For a coherent imaging system, with coherent transfer function $c(m,n)$, the image intensity is

$$I(x,y) = \left|\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} c(m,n)T(m,n) \times \exp\left[\frac{i2\pi}{M}(mx+ny)\right]\mathrm{d}m\,\mathrm{d}n\right|^2 \qquad [7]$$

where M is the magnification. The coherent transfer function $c(m,n)$, is equal to the scaled pupil function $P(\lambda fm, \lambda fn)$, where f is the focal length of the objective. Substituting eqn [6] into eqn [7] and dropping terms of second order we obtain:

$$I(x,y) = |c(0,0)|^2 + 2\Re\left\{c^*(0,0)\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} \times c(m,n)B(m,n)\exp\left[\frac{i2\pi}{M}(mx+ny)\right]\mathrm{d}m\,\mathrm{d}n\right\} \qquad [8]$$

Normalizing the transfer function to unity at the origin:

$$I(x,y) = 1 + 2\Re\left\{\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} c(m,n)B(m,n) \times \exp\left[\frac{i2\pi}{M}(mx+ny)\right]\mathrm{d}m\,\mathrm{d}n\right\} \qquad [9]$$

For an axially symmetric aberration-free system, the coherent transfer function is real and even, so that a pure phase object is not imaged (only the Hermitian component of B is imaged). Many phase contrast methods in principle rely on appropriate modification of the coherent transfer function, either by making it complex or asymmetric.

However, this theory is an approximation as microscope systems are in practice partially coherent. For a partially coherent system the image intensity is

$$I(x,y) = \int_{-\infty}^{\infty}\int_{-\infty}^{\infty}\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} C(m,n;p,q)T(m,n) \times T^*(p,q)\exp\left\{\frac{i2\pi}{M}[(m-p)x+(n-q)y]\right\}\mathrm{d}m\,\mathrm{d}n \qquad [10]$$

where $C(m,n;p,q)$ is the partially coherent transfer function, sometimes called the transmission cross-coefficient, which can be calculated as an integral over the objective and condenser pupils. The partially coherent transfer function is nonzero over a finite region of $m,n;p,q$ space, thus limiting the resolution of the system. Then eqn [8] for a weak object becomes, normalizing so that $C(0,0;0,0)=1$:

$$I(x,y)=1+2\Re\left\{\int_{-\infty}^{\infty}\int_{-\infty}^{\infty}C(m,n;0,0)B(m,n)\times\exp\left[\frac{\mathrm{i}2\pi}{M}(mx+ny)\right]\mathrm{d}m\,\mathrm{d}n\right\} \qquad [11]$$

where $C(m,n;0,0)$ is called the weak object transfer function.

For the image of a general object that is not necessarily weak, eqn [10] is often difficult to interpret. We can gain much insight into the imaging process by considering another special form of object, this time a slowly varying object:

$$t(x,y)=a(x,y)\exp\left[\mathrm{i}\left(x\frac{\partial\phi}{\partial x}+y\frac{\partial\phi}{\partial y}\right)\right] \qquad [12]$$

where a and ϕ are assumed slowly varying. Thus, the object spectrum, assumed now as slowly spatially varying, is

$$T(m,n)\approx a\delta\left(m-\frac{1}{2\pi}\frac{\partial\phi}{\partial x}\right)\delta\left(n-\frac{1}{2\pi}\frac{\partial\phi}{\partial y}\right) \qquad [13]$$

Substituting in eqn [10], we then find:

$$\begin{gathered}I(x,y)=a^2(x,y)C(m,n;m,n)\\ m=\frac{1}{2\pi}\frac{\partial\phi}{\partial x},\quad n=\frac{1}{2\pi}\frac{\partial\phi}{\partial y}\end{gathered} \qquad [14]$$

in which C is called the phase gradient transfer function, and is real. For an ordinary bright field system, C is an even function. Thus a phase gradient results in a change in image intensity, but for an axially symmetric system the sign of the change is independent of the sign of the phase change.

Defocused Imaging

Historically, the oldest method of phase contrast is simply to defocus the object. The transfer function is then complex, and phase detail is imaged. If the system is aberration-free, the contrast of the phase information reverses on the opposite side of focus. The strength of the contrast increases with defocus, until eventually artifacts are introduced when the imaginary part of the transfer function becomes negative. If the relative condenser aperture is too large, contrast is reduced.

Assume a pure weak phase object:

$$t(x,y)=1+\mathrm{i}d\cos(2\pi\nu x) \qquad [15]$$

so that

$$T(m,n)=\left[\delta(m)+\mathrm{i}\frac{d}{2}\delta(m-\nu)+\mathrm{i}\frac{d}{2}\delta(m+\nu)\right]\delta(n) \qquad [16]$$

Then:

$$I(x,y)=1-dC_{\mathrm{i}}(\nu,0;0,0)\cos\left(\frac{2\pi\nu x}{M}\right) \qquad [17]$$

where C_{i} is the imaginary part of C. Thus the phase information is imaged by the imaginary part of the weak object transfer function.

Dark Field Microscopy

Dark field microscopy can be used to visualize weak amplitude and phase information. The constant background in eqn [5] is eliminated, so we obtain an image of b. Note that eqns [8] and [11] are no longer valid because we cannot neglect the second-order term. For a coherent system, the background can be eliminated by use of a central stop to intercept the nondiffracted light. For a partially coherent microscope, an annular condenser aperture (larger in diameter than the objective pupil) is used (Figure 1). In both cases, in practice a range of low spatial frequencies are eliminated, resulting in the appearance of halo artifacts.

For the pure weak phase object of eqn [12], the image in a coherent microscope is

$$I(x,y)=\frac{1}{2}d^2c^2(\nu,0)\left[1+\cos\left(\frac{4\pi\nu x}{M}\right)\right] \qquad [18]$$



Figure 1 Schematic diagram of dark field microscopy.

so that the spatial frequency is double that in the original object. For the partially coherent microscope, we have

$$I(x,y) = \frac{1}{2}d^2\Big[C(\nu,\nu;0,0) + C(\nu,-\nu;0,0)\cos\Big(\frac{4\pi\nu x}{M}\Big)\Big] \qquad [19]$$

in which the two terms represent difference and sum frequency components. However, it can be shown that for the annular dark field system the transfer function for sum frequencies is zero, so the image intensity is a constant. The system images only difference frequencies of pairs of spatial frequencies, and not sum frequencies.

For a slowly varying phase object, zero intensity results from a region of constant phase, but the intensity rises quickly for small values of phase gradient, thus giving strong contrast. For larger phase gradients, the intensity falls off slowly.

Zernike Phase Contrast

The Zernike phase contrast method is similar to dark field except that the direct (nondiffracted) light has its relative phase changed by 90°, rather being eliminated. In practice this is achieved using an annular condenser aperture and an objective with a phase ring (Figure 2). The phase change can be ±90°, giving positive or negative phase contrast. The phase ring is usually only partially transmitting, which has the effect of enhancing the sensitivity. From eqns [8] or [11], imaging of a weak object is linear in phase. The halo artifact is present, as in dark field microscopy. Weak amplitude information is imaged as in dark field microscopy.



Figure 2 Schematic diagram of Zernike phase contrast microscopy.

For the weak phase object eqn [12], we then have

$$I(x,y) = 1 \pm \frac{2d}{g}C(\nu,0;0,0)\cos\Big(\frac{2\pi\nu x}{M}\Big) \qquad [20]$$

for positive or negative phase contrast, respectively, where g is the amplitude transmittance of the phase ring. The response of the weak object transfer function is improved as a result of the annular condenser aperture.

Schlieren Imaging, Hoffman Modulation Contrast, and Differential Phase Contrast (DPC)

In Schlieren imaging with coherent illumination, a half plane mask (a Foucault knife edge) is inserted to eliminate say the negative spatial frequencies in x. Taking now $c(0,0) = 1/2$, eqn [8] becomes, after normalization:

$$I(x,y) = 1 + 4\Re\Big\{\int_{-\infty}^{\infty}\int_{0}^{\infty} c(m,n)B(m,n) \times \exp\Big[\frac{i2\pi}{M}(mx+ny)\Big]\mathrm{d}m\,\mathrm{d}n\Big\} \qquad [21]$$

For the weak phase object eqn [15], we then have:

$$I(x,y) = 1 - dc(\nu)\sin\Big(\frac{2\pi\nu x}{M}\Big) \qquad [22]$$

The image exhibits a variation in phase quadrature to the original phase variation, that is, it is related to the x-derivative of the phase. The effect occurs because the coherent transfer function contains an odd (but real) part.

For a partially coherent microscope a similar effect can be achieved simply by offsetting the illumination system, but now the transfer function is no longer single-sided. It can be resolved into odd and even parts that result in differential phase contrast and amplitude contrast, respectively. The amplitude contrast component merely contributes to the background for a phase-only object, and can be removed simply by contrast enhancement of a digital image. The offset can be introduced in practice by inserting a half-plane mask into the condenser aperture stop. Imaging of a slowly varying object can be explained by eqn [14], in which the transfer function is not symmetrical. The image shows a pseudo-three-dimensional bas relief effect. A commercial implementation of an asymmetric transfer function is Hoffman modulation contrast, which uses offset illumination together with an amplitude mask in the objective pupil (Figure 3). Advantages of Hoffman contrast are that it uses standard bright-field objectives and avoids problems from birefringent specimens.

A similar method can be used in scanning laser microscopy. In a scanning microscope the effect of the illumination and detection systems are interchanged. Thus DPC can be achieved in a scanning laser microscope by offsetting the detector. In practice this is conveniently done by using a split detector (Figure 4), a detector divided into two semicircular elements. If the signal of one half is subtracted from that of the other, the amplitude contrast component cancels out, so that pure differential phase contrast results. For weak phase gradients, the intensity varies linearly with phase gradient, again showing the bas relief effect. It is thus bi-directional, and the difference signal can become negative. A constant value is, therefore, usually added to it before display. The sum of the two detector elements results in a conventional bright-field image. From eqn [14], both difference and sum signals are proportional to $a^2(x, y)$, so that if the ratio of these two signals is extracted, an image of the phase gradient in the x direction results. The response to either weak phase gradients or fine detail can be enhanced by modifications using annular split detectors. Use of a quadrant detector allows the phase gradients in the x and y directions to be imaged. DPC microscopy has been demonstrated to be sensitive enough to observe monomolecular films and atomic surface steps.



Figure 3 Schematic diagram of Hoffmann modulation contrast microscopy.



Figure 4 Schematic diagram of differential phase contrast (DPC) microscopy.

Interference Microscopy

Interference microscopy allows quantitative measurement of the object phase by interference of the object beam with a reference beam. In the transmission geometry, a Mach–Zehnder interferometer is used, which is effectively two parallel microscopes, each with matched condenser and objective lenses. In the reflection geometry we can use a Michelson, a Mirau, or a Linnik interferometer. The Michelson interferometer has an inclined beamsplitter and the reference mirror situated between the objective and object, and hence can be used only with low numerical aperture objectives. The Linnik interferometer has matched objectives in the object and reference beam paths. There is no limit to the numerical aperture that can be used, but it is not a common-path interferometer and is hence sensitive to vibrations and air currents. Probably the most practicable system for interference microscopy in the reflection geometry is based on the Mirau interferometer that uses a beamsplitter with its normal parallel to the optic axis. Until recently, interference microscopes used a small condenser aperture giving nearly coherent illumination. The image consists of three components: an object beam term (noninterference image) a reference beam term, and the interference term. The phase (and amplitude) of the object beam can be extracted using phase stepping or heterodyning techniques. The measured phase is wrapped, and requires unwrapping to obtain the absolute phase.

If the condenser aperture is opened up, the behavior is modified. The interference term is

given by

$$I_{\mathrm{int}}(x,y) = 2\Re\left\{ r^* \int\int c_{\mathrm{int}}(m,n) T(m,n) \times \exp\left[\frac{\mathrm{i}2\pi(mx+ny)}{M} \right] \mathrm{d}m\,\mathrm{d}n \right\} \qquad [23]$$

where $c_{\mathrm{int}}(m,n)$ is the coherent transfer function for interference imaging, given by a convolution integral of the object path objective pupil with the product of the reference pupil and the source. The first thing to note is that for a high numerical aperture, the spacing of the interference fringes is increased by 20–40%, and depends on defocus, tilt, and central obscuration. Thus accurate measurement of phase requires careful calibration. The objective pupil exhibits a phase variation when defocused that reduces the modulus of the coherent transfer function, resulting in the fringes being modulated by an envelope the width of which becomes smaller as the aperture becomes larger. The envelope is similar to that of the optical sectioning effect in confocal microscopy. This envelope allows the zero-order fringe to be identified, although simulations have suggested that fringe hopping could occur at phase jumps as a result of diffraction effects.

Multiple Beam Interferometry

The topography of a surface can be investigated by using a Fizeau interferometer formed by bringing a coated optical flat near to the surface. Then if the surface and flat have high reflectivity, multiple beam interference occurs and the width of the bright fringes can be much reduced. The system can be used with a tilted flat, to give fringes that are substantially straight, or with an almost parallel flat, so that the entire field of view is occupied by a single fringe. In the latter case, the sensitivity can be in the subnanometer range. Multiple beam interference also enhances the contrast of weak amplitude information.

Shearing Interferometry

In conventional interferometry, the object beam is arranged to interfere with a constant reference beam. In shearing interferometry, on the other hand, it interferes with a shifted version of itself.

Lateral Shearing Interferometry

An approach that is suitable for quantitative optical path measurements is to use an interferometer that shears the microscope image. The Interphako system uses a Mach–Zehnder interferometer that can measure optical path differences as low as ~3 nm in either the reflection or transmission geometry. The interferometer allows the shear distance to be varied.

Differential Interference Microscopy (DIC)

The most common form of shearing interferometry is differential interference microscopy, usually associated with the name of Nomarski. DIC microscopy can be performed in either the transmission or the reflection geometry. A plane polarized illumination beam is split into two orthogonally polarized beams traveling at slightly differing angles by a Wollaston prism in the front focal plane of the condenser lens (Figure 5). The beams are thus sheared laterally in the object plane. The light from the sample travels through the objective and a second Wollaston prism, which recombines the two beams into one. In the reflection geometry, a single lens and Wollaston prism are used. An analyzer set at 45° allows the two beams to interfere. The shear is arranged to be smaller than the width of the point spread function. Different prisms are supplied for use with different magnification objectives. The system results in



Figure 5 Nomarski differential interference contrast (DIC) microscopy.

differential phase contrast, but there are differences as compared with the DPC microscope described above.

There are two different implementations of DIC in use. In one implementation, the illumination polarizer and analyzer are crossed. The relative phase difference between the two beams (the bias retardation) is adjusted by moving the Wollaston prism laterally. It is claimed that rotation of the analyzer can be useful when observing mixed phase/amplitude objects. In the second arrangement (the Sénarmont compensator) the position of the Wollaston prism is fixed, and the analyzer rotated to change the relative phase.

A recent variation of DIC uses circularly polarized illumination. The Wollaston prism still produces two plane polarized components, but with an additional phase difference of $\pi/2$. The advantage of using circular polarization is that the prism can then be rotated to change the direction of shear.

If the shear is 2Δ, and the phase difference is $\pi - 2\phi_0$ (i.e., if $\phi_0 = 0$ then the two beams are in anti-phase), then the effective object spectrum is:

$$T_{\text{eff}}(m,n) = -2\sin(2\pi m\Delta - \phi_0)T(m,n) \qquad [24]$$

Thus the effective transfer function can be written:

$$\begin{aligned} C_{\text{eff}}(m,n;p,q) &= 4\sin(2\pi m\Delta - \phi_0)\sin(2\pi p\Delta - \phi_0) \\ &\quad \times C(m,n;p,q) \\ &= 2\{\cos[2\pi(m-p)\Delta] \\ &\quad - \cos 2\phi_0 \cos[2\pi(m+p)\Delta] \\ &\quad - \sin 2\phi_0 \sin[2\pi(m+p)\Delta]\} \\ &\quad \times C(m,n;p,q) \qquad [25] \end{aligned}$$

It is the final term of the three in braces that, because it is an odd function, results in differential phase contrast. We can now examine imaging of special forms of object. For a weak object, putting $p = 0$ as in eqn [11]:

$$\begin{aligned} C_{\text{eff}}(m,n;0,0) &= 2\{(1-\cos 2\phi_0)\cos[2\pi m\Delta] \\ &\quad - \sin 2\phi_0 \sin[2\pi m\Delta]\}C(m,n;0,0) \end{aligned} \qquad [26]$$

The first term in braces corresponds to an amplitude contrast background component because it is real and even. The second term results in DPC, because it is real and odd. For zero bias retardation, dark-field imaging results. As the bias retardation is increased from zero, the strength of both the amplitude contrast and the DPC components increase, but that of the DPC component increases more rapidly. For visual observation we require good contrast, and hence we choose a small value of bias retardation, just large enough so that the background is large enough to avoid artifacts in the DPC image. In digital microscopy, contrast is not so important as it can be enhanced digitally, and hence we can increase ϕ_0 to a value of $\pi/4$, which maximizes the strength of the DPC component. Further increase in bias retardation decreases the DPC signal, until for $\pi/2$ pure amplitude contrast results. The actual form of the weak object transfer function depends on the magnitude of the shear. The condition $m_0\Delta = 1/4$, where m_0 is the cut-off in spatial frequency, gives optimum performance for the imaging of weak objects.

The phase gradient transfer function is:

$$C_{\text{eff}}(m,n;m,n) = 4\sin^2(2\pi m\Delta - \phi_0)C(m,n;m,n) \qquad [27]$$

For the bright-field microscope the phase gradient transfer function falls off symmetrically from its value at zero phase gradient. The effect of the premultiplying factor in eqn [27] is to increase the fall-off for positive phase gradients and reduce it for negative ones. A bas-relief effect occurs, with highlighting for negative phase gradients for some values of the parameters. Increasing the value of the shear increases the highlighting effect, but, unlike in DPC, the behavior is not anti-symmetric.

Because interference is dependent on the wavelength of the light, useful and beautiful effects can be seen with DIC microscopy using white light. Usually it is regarded as a qualitative, rather than a quantitative, imaging method. However, as from eqn [14], the intensity can be written:

$$I(x,y) = 2a^2(x,y)[1 - \cos(2\pi m\Delta - \phi_0)]C(m,n;m,n) \qquad [28]$$

By recording images at different bias retardations, conventional phase stepping methods can be used to extract the phase gradient $2\pi m = \partial\phi/\partial x$.

Axial Shearing Interferometry

Instead of shearing in the transverse direction, a shear in the axial direction can be used. In the reflection geometry, the complex amplitude from the point of observation is compared with the average over a defocused spot. This method has proved to be extremely sensitive, and can detect height changes smaller than 0.1 nm.

Phase Retrieval

Digital Phase Retrieval

The phase of a single two-dimensional (2D) measurement of intensity can be retrieved by an iterative procedure, if constraints such as nonnegativity and band-limitedness can be assumed. If the modulus of both an object and its Fourier transform are known, then the phases can also be recovered. In this case, the two 2D real data sets have information content sufficient to reconstruct the 2D complex object. This approach has been extended to the case of measurement of two defocused images, using the method of phase diversity.

Imaging Using the Transport of Intensity Equation

The transport equation of intensity can be used to recover the phase of a partially coherent wavefield directly (i.e., noniteratively) from two 2D intensity measurements. If the wavefield is represented in terms of its intensity I and phase ϕ in a plane, the transport equation can be written in the paraxial approximation and in the absence of phase singularities:

$$-k\frac{\partial I}{\partial z} = \nabla_T \cdot [I \nabla_T \phi] \qquad [29]$$

where ∇_T is a 2D operator acting in the plane. This expression can be inverted to give ϕ quantitatively, if I and $\partial I/\partial z$ are known. However, it gives the phase of the image field, rather than the phase of the object, so that obtaining quantitative values for a strong object may be difficult. The transport of intensity method is valid with partially coherent illumination: if the relative condenser aperture is too great then contrast becomes weak. Further, an effect similar to the variation in fringe spacing with aperture in interference microscopy is introduced because oblique illuminating rays traverse the sample at an angle to the axis. In practice, a series of three images are usually taken at different focus positions. Then, from the quantitative phase data, various different contrast mechanisms such as DIC, Zernike phase contrast, and so on, can be simulated.

Surface Profiling Methods: Triangulation and Coherence Domain Methods

Although strictly they are not phase imaging methods, other surface profiling methods can be used to measure optical path. These could also be adapted to measure optical path in transmission. It is important also to be aware of these methods, as they could affect measurements made using other phase contrast techniques.

Apart from the phase measurement techniques described above, surface profiling methods fall into one of two categories: triangulation and coherence domain methods. An example of a technique that relies on triangulation is confocal microscopy. Confocal microscopy exhibits an optical sectioning effect similar to that described for interference microscopy. The effect is stronger for higher numerical aperture. As a reflector is scanned through focus the intensity goes through a maximum. By locating the position of the maximum, the local surface height can be obtained. In a similar way, in a confocal transmission system, introduction of an object with some optical thickness has the effect of altering the axial position of the confocal pinhole, with a resultant drop in intensity. This effect can be used to image the optical thickness of the sample.

Coherence domain methods rely on the finite coherence length of the light. In an interferometer, this results in an envelope that multiplies that arising from the nonzero relative condenser aperture. Measurement of the peak of the envelope allows local surface height to be measured. Unlike the confocal approach, the width of this coherence envelope is independent of the numerical aperture of the system.

In reflection, both the confocal and the coherence domain methods have the advantage over direct phase imaging techniques that they allow measurement of surface height changes without errors caused by the phase change on reflection from a conducting medium.

See also

Interferometry: Phase Measurement Interferometry. **Microscopy:** Interference Microscopy. **Phase Control:** Phase Conjugation and Image Correction.

Further Reading

Bennett AH, Jupnik H, Osterberg H and Richards OW (1952) *Phase Microscopy*. New York: Wiley.

Born M and Wolf E (1999) *Principles of Optics*, 7th edn. Cambridge: Cambridge University Press.

Bradbury S and Evenett PJ (1996) *Contrast Techniques in Light Microscopy*. Oxford: Bios Scientific Publishers.

Françon M (1950) *Le Contraste de Phase en Optique et en Microscopie*. Paris: Revue d'Optique.

Françon M (ed.) (1952) *Le Contraste de Phase et le Contraste par Interférences*. Paris: Revue d'Optique.

Inoue S and Spring KR (1997) *Video Microscopy: The Fundamentals*, 2nd edn. New York: Plenum.

Lessor DL, Hartman JS and Gordon RL (1979) Quantitative surface topography determination by Nomarski reflection microscopy. *Journal of the Optical Society of America* 69: 357–366.

Pluta M (1989) *Advanced Light Microscopy*. Specialized Methods, vol. 2. Amsterdam: Elsevier.

Sheppard CJR and Wilson T (1980) Fourier imaging of phase information in conventional and scanning microscopes. *Philosophical Transactions of Royal Society A* 295: 513–536.

Wilson T and Sheppard CJR (1984) *Theory and Practice of Scanning Optical Microscopy*. London: Academic Press.

MODULATORS

Contents

Acousto-Optics
Electro-Optics
Modulation and Demodulation of Optical Signals

Acousto-Optics

M Gottlieb and D Suhre, Carnegie Mellon University, Pittsburgh, PA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Acousto-optics deals with the interaction of light waves with sound waves and has given rise to a large number of devices related to various laser systems for display, information handling, optical signal processing, and numerous other applications requiring the spatial or temporal modulation of coherent light. The basic principles and phenomena controlling these interactions were largely understood by the mid-1930s, but had little practical significance because very high acoustic power levels were required to attain good optical efficiency and there were few good sources of well-collimated monochromatic light. During the period from 1960 to the present, several key technologies were developing rapidly, at the same time that many applications of the laser were being suggested which require high-speed, high-resolution scanning methods. These new technologies gave rise to high-efficiency, wideband acoustic transducers capable of operation to several gigahertz, high-power wideband solid-state amplifiers to drive such transducers, and the development of a number of new, synthetic acousto-optic crystals with low-drive-power requirements and low acoustic losses at high frequencies. This combination of properties makes acousto-optics feasible for many systems, and for several is the method of choice to satisfy demanding requirements. This chapter will summarize the basic features of acousto-optic interactions and the operating principles of the most common acousto-optic devices.

The Photo-Elastic Effect

The change induced in the refractive index of a transparent material by the pressure change produced by an acoustic disturbance is the underlying mechanism of all acousto-optic interactions. An acoustic wave produces periodic regions of compression and rarefaction in the material, which modulates the density. The Lorentz–Lorenz relation relates the refractive index to the density, for the simplest case of an ideal gas

$$\frac{(n^2-1)}{(n^2+2)} \propto \rho \qquad [1]$$

where n is the refractive index and ρ is the density. This relation is followed to a good approximation for most simple solid materials as well. The elastooptic coefficient is

$$\frac{\rho\,\mathrm{d}n}{\mathrm{d}\rho} = \frac{(n^2-1)/(n^2+2)}{6n} = p \qquad [2]$$

The fundamental quantity given by eqn [2], also known as the photo-elastic constant p, is related to the pressure applied by

$$p = \frac{1}{\beta}\left(\frac{\mathrm{d}n}{\mathrm{d}p}\right) \qquad [3]$$

where P is the applied pressure and β is the compressibility of the material. The photo-elastic constant of an ideal material with refractive index of 1.5 is 0.59. The photo-elastic constants of a wide variety of materials lie in the range from about 0.1 to 0.6.

The relation in eqn [3] follows from the usual definition of the photo-elastic constant:

$$\Delta(1/\varepsilon) = \Delta(1/n^2) = pe \qquad [4]$$

where ε is the dielectric constant, $\varepsilon = n^2$, and e is the acoustic strain amplitude. The induced change in refractive index, Δn, is

$$\Delta n = -n^3 pe \qquad [5]$$

Strain amplitudes typically lie in the range of 10^{-8} to 10^{-5}, with Δn in the range of about 10^{-8} to 10^{-5} (for $n = 1.5$). Devices based upon such a small change in refractive index are capable of generating large effects because these devices are configured in a way that can produce large phase changes at optical wavelengths.

The more complete relation defining the photo-elastic interaction is more complex than the simple scalar eqn [5] in which the photoelastic constant is independent of the directional properties of the material. In fact, even for an isotropic material such as glass, longitudinal acoustic waves and transverse (shear) acoustic waves cause the photoelastic interaction to assume different parameters. A tensor relation between the dielectric properties, the elastic strain, and the photo-elastic coefficient describes the interaction, particularly for anisotropic materials. The tensor equation is

$$\Delta(1/n^2) = \sum_{kl} p_{ijkl}\, e_{kl} = \Delta(1/\varepsilon)_{ij} \qquad [6]$$

where $(1/\varepsilon)_{ij}$ is a component of the optical index ellipsoid, e_{kl} are the Cartesian strain components, and p_{ijkl} are the components of the photo-elastic tensor. The crystal symmetry of the photoelastic material places limits on the possible configurations of interaction geometry.

Diffraction by Acoustic Waves

For typical acousto-optic devices the acoustic wave acts as a diffraction grating, made up of periodic changes in optical phase, moving at sound velocity. These features determine the properties of acousto-optic diffraction. Using a quantum-based model, the light and sound may be thought of as particles, photons and phonons, undergoing collisions in which energy and momentum are conserved. Either of these descriptions may be used to obtain all the important diffraction effects, but some are more easily understood on the basis of one or the other. A description of both is given here. Consider Figure 1 in which the light wave, of frequency ω and wavelength λ, is incident into the material with an acoustic wave of frequency f and wavelength Λ. If the refractive index of the medium is $n + \Delta n$ in the presence of the acoustic wave, the phase of the optical wave will be changed by an amount

$$\Delta\phi = 2\pi(L/\lambda)\Delta n \qquad [7]$$

where L is the length of the interaction region. Some typical values of $\Delta\phi$ can be obtained by assuming $L = 2.5$ cm and $\lambda = 0.5$ μm, with Δn reaching a peak value of 10^{-5}. This yields a phase change of π rad, which is, of course, quite large. It is large because L/λ, the number of optical wavelengths, is 50 000, so that a very small Δn can still produce a sizable $\Delta\phi$. If the electric field incident on the delay line is represented by

$$E = E_0\, e^{i\omega t} \qquad [8]$$

then the field of the phase-modulated emerging light will be

$$E = E_0\, e^{(i\omega t + \Delta\phi)} = e^{i\omega t}\, e^{2\pi i (L/\lambda)\sin(ft)} \qquad [9]$$

where f is the acoustic frequency.

A detailed derivation of the resulting temporal and spatial distribution of the light field is mathematically complex, but, analogy with radio-wave modulation can be used to arrive at the resultant fields. The spectrum of a phase-modulated carrier of frequency ω consists of components separated by multiples of the modulation frequency f, as shown in Figure 2. Sidebands are produced about the carrier frequency, such that the frequency of the mth sideband is



Figure 1 Interaction of light waves with acoustic waves.



Figure 2 Spectrum of a phase-modulated wave of carrier frequency ω_0, and modulation index $\Delta\phi$.

$\omega + mf$, where m may be positive or negative. The amplitude of each of the sidebands is proportional to the Bessel function of order equal to the sideband number, and whose argument is the modulation index $\Delta\phi$. The odd-numbered negative orders are 180° out of phase with the even-numbered ones, a feature that may be useful for certain signal processing applications. The light emerging from the delay line is composed of a number of light waves whose frequencies have been shifted by mf from the frequency ω of the incident light. The relative amplitudes will be determined by the peak change in the refractive index. The two extremes of the diffraction process are simplified in the 'thin grating' and the 'thick grating' models. The ratio of the interaction length, L, to the acoustic wavelength, Λ, will determine the character of the diffraction process. The plane wave approximation in which the acoustic energy propagates as a plane wave is valid when this ratio is very large. However, when this ratio is small, the acoustic propagation can be described in terms of a sum of plane waves, the angular spectrum of which increases as the ratio decreases. In this phenomenological model the partial wave which is propagating at an angle λ/Λ to the forward direction may diffract the light second time into an angle $2\theta = 2\lambda/\Lambda$, and the frequency of this light will once again be up-shifted, for a total frequency shift of $2f$. If the spectrum of acoustic waves contains sufficient power of still higher orders, then this rediffraction process can be repeated, so that light will be multiply diffracted m times into higher-order angles, $m\theta = m\lambda/\Lambda$ each with a frequency shift mf. A similar argument holds for the negative orders, so that a complete set of diffracted light beams will appear as shown in Figure 3, where the deflection angle corresponding to the mth order is given by $\sin\theta_m = m\lambda/\Lambda$ and the frequency of the light deflected into the mth order is $\omega_m = \omega + mf$. The intensity of the carrier wave, or zero order, will be zero when the modulation index $\Delta\phi$ is equal to 2.4. The first order will be a maximum for $\Delta\phi = 1.8$, corresponding to the maximum of the first-order Bessel function B_1, and decreasing for larger modulation indices. These phenomena were described by Debye and Sears and so are often referred to as Debye–Sears diffraction. An extensive theoretical analysis of the effect was given by Raman and Nath and is alternatively referred to as Raman–Nath diffraction. As the interaction length is increased the Raman–Nath diffraction gradually weakens. The weakening begins around an interaction length $L \sim \Lambda^2/4\lambda$. This value of L is expressed in the Q parameter



Figure 3 Diffraction of light in the Raman–Nath limit.

$$Q = 4L\lambda/\Lambda^2 \qquad [10]$$

which is known as the Raman–Nath parameter. A different regime of diffraction takes effect for values of the interaction length $Q \gg 1$.

The phenomena in this regime can be more easily understood in terms of the quantum description of the light and sound waves as collisions between photons and phonons. In this model, the dynamics of the collisions of the light and sound are governed by the laws of conservation of energy and momentum. The momentum vectors magnitudes of the light and sound, **k** and **K**, are given by the well-known expressions

$$|\mathbf{k}| = 2\pi n/\lambda \text{ and } |\mathbf{K}| = 2\pi/\Lambda \qquad [11]$$

where the acoustic wavelength, Λ, is related to the acoustic velocity, V, by $\Lambda = V/f$.

Conservation of momentum is expressed by the vector relation

$$\mathbf{k}_\mathrm{i} + \mathbf{K} = \mathbf{k}_\mathrm{d} \qquad [12]$$

the diagram for which is shown in Figure 3, where $\mathbf{k}_i$, and $\mathbf{k}_d$ represent the momentum of the incident photon and the diffracted photon, respectively. In this notation

$$\mathbf{k}_i = 2\pi n_i/\lambda, \qquad [13a]$$

and

$$\mathbf{k}_d = 2\pi n_d/\lambda \qquad [13b]$$

If the material is anisotropic (birefringent), n_i and n_d may be different.

Conservation of energy requires that

$$h\omega_d = h\omega_i + hf \qquad [14]$$

in which h is Planck's constant. Since ω_i lies in the optical frequency range, $\sim 10^{13}$ Hz, and f lies in the RF or microwave range, 10^6–10^9 Hz, then $\omega_d \sim \omega_i$. This results, for isotropic materials, in the magnitudes of $\mathbf{k}_i$ and $\mathbf{k}_d$ being equal and resulting in the isosceles momentum triangle of Figure 4. The angles of incidence and diffraction (with respect to the planar acoustic wavefronts), called the Bragg angles, are equal for this case, and are

$$\theta_B = (1/2)\lambda/\Lambda \qquad [15]$$

A schematic diagram for this process is shown in Figure 5. The interaction will be large only if the light is well-collimated, and incident at this angle. Unlike the Debye–Sears regime, there is only a single diffracted beam. The energy of the phonon may either be added to that of the incident photon, increasing its frequency to $\omega_d = \omega_i + f$, or the reverse, resulting in $\omega_d = \omega_i - f$. The sense of the momentum vectors determines which of these occurs. The Debye–Sears effect and Bragg diffraction are not different phenomena, but are the limits of the same mechanism. The Raman–Nath parameter Q determines which is the appropriate limit for a given set of values λ, Λ, and L.



Figure 4 Momentum diagram for diffraction of light.



Figure 5 Acousto-optic diffraction cell.

Anisotropic Bragg Diffraction

In optically anisotropic materials, acousto-optic Bragg diffraction can occur between an ordinary and extraordinary optical beam, and vice versa. This is generally referred to as birefringent diffraction, and it offers additional design capabilities compared to the isotropic case, such as enhancing the angular aperture, and extending the aperture–bandwidth product.

The theory of diffraction of light so far described has assumed that the optical medium is isotropic. A number of important acousto-optic devices make use of the properties of birefringent materials. It is different from diffraction in isotropic media in that the magnitude of the momentum vector of the light will in general be different for different light polarization directions. Thus, the vector diagram representing conservation of momentum will no longer be the simple isosceles triangle of Figure 4. The momentum vector for ordinary polarized light will, in general, be different from the momentum vector for light that is extraordinary polarized. To understand the effect of anisotropy on diffraction, it is necessary to mention another phenomenon which occurs when light interacts with shear acoustic waves, i.e., waves in which the displacement of matter is perpendicular to the direction of propagation of the acoustic wave. A shear acoustic wave may cause the direction of polarization of the diffracted light to be rotated by 90°. The underlying reason for this is that the shear disturbance induces a birefringence which causes the plane of polarization to be rotated. The acousto-optic tunable filter (AOTF) is a particularly interesting birefringent device. It was first developed for the case of collinear optical and acoustic beams, and was used for wavelength selection in a dye laser.

Diffraction Efficiency

The acoustic power required to diffract light will be determined by the geometric parameters as well as by the properties of the medium. A simplified calculation leads to results that are useful. Referring to the spectrum of a phase-modulated wave shown in Figure 2, we can see that the ratio of the intensity in the first order to that in the zero order is

$$I_1/I_0 = \left[B_1(\Delta\phi)/B_0(\Delta\phi)\right]^2 \qquad [16]$$

By analogy this same result comes about for acousto-optically diffracted light. The acoustic power flow is given by

$$P_a = \frac{1}{2}cVe^2 \qquad [17]$$

where c is the elastic stiffness constant. The elastic stiffness constant is related to the bulk modulus β, the density ρ, and acoustic velocity v through the expression

$$c = \frac{1}{\beta} = \rho V^2 \qquad [18]$$

and the acoustic power density is

$$P_a = \frac{1}{2}\rho V^3 e^2 \qquad [19]$$

The optical phase modulation of the medium resulting from the change in refractive index, Δn, is

$$\Delta\phi = 2\pi(L/\lambda)\Delta n \qquad [20]$$

Using eqn [5] for Δn, the phase modulation is related to the acoustic power density by

$$\Delta\phi = -\pi(L/\lambda)\, n^3 p\, (2P_a/\rho V^3)^{1/2} \qquad [21]$$

The diffraction efficiency can now be calculated by using this value for the optical phase change in eqn [16]. The first- and second-order Bessel functions can be approximated for small modulation index by

$$\begin{aligned} &B_0(\Delta\phi) \sim \cos(\Delta\phi) \sim 1 - (\Delta\phi)^2, \quad \text{and} \\ &B_1(\Delta\phi) \sim \sin(\Delta\phi) \sim \Delta\phi \end{aligned} \qquad [22]$$

The small signal approximation to the diffraction efficiency is then

$$I_1/I_0 \sim (\Delta\phi)^2 = \left(\pi^2 L^2/2\lambda^2\right)\left(n^6 p^2/\rho V^3\right)P_a \qquad [23]$$

The expression $n^6 p^2/\rho V^3$ is known as the figure of merit of the material, and is designated as M_2; it is comprised entirely of intrinsic material properties.

Acousto-optic Materials

Acousto-optic device technology has matured to the point that performance is chiefly limited by material parameters, particularly the figure of merit and acoustic attenuation. Nature has arranged that materials with high figures of merit usually have high attenuation and vice versa. The widely used acousto-optic materials are fused quartz, tellurium dioxide, and lithium niobate. Development work on new infrared materials has been reported recently. A list of commonly used acousto-optic materials is given in Table 1. For materials with a low figure of merit, a higher drive power can be used to obtain the required efficiency.

Experience has indicated that the upper limit for very small devices (active area ~0.1 mm^2) is a drive power density of 100–500 mW/mm^2, provided there is proper heat sinking to transfer the heat energy. For larger devices, sizes greater than ~1 cm^2, the limit is closer to a few W/cm^2. At the high drive power levels, the acoustic attenuation may cause significant optical distortion.

AO Devices

Resolution, bandwidth, and speed are the important characteristics of acousto-optic scanners, shared by all types of scanning devices. Depending upon the application, only one, or all, of these characteristics may have to be optimized. Consider the acousto-optic scanner in Figure 6 with a collimated incident beam of width D, diffracted to an angle θ_B at its RF bandcenter, and whose bandwidth is Δf. If the diffracted beam is focused onto a plane by a lens, or lens combination, at the scanner, the diffraction spread of the optical beam will be

$$\Delta x = F\Delta\phi \sim F - \lambda/D \qquad [24]$$

Table 1 Selected acousto-optic materials

Material	*Transmission range* (μm) mission	*Acoustic mode & propagation direction*	*v* *(cm/s × 10^5)*	*Acoustic attenuation (dB/cm GHz^2)*^{c}	*n*	*M_2* *(s^3/g × 10^{-18})*
Visible–near-infrared (VIS-NIR)						
$LiNb0_3$	0.04–4.5	L[100][a]	6.57	0.15	2.20	7.0
		S[001][b]	3.59	2.6	2.29	2.92
TiO_2,	0.45–6	L[001]	10.3	0.55	2.58	1.52
α-SiO_2;	0.12–4.5	L[001]	6.32	2.1	1.54	1.48
		L[100]	5.72	3.0	1.55	2.38
TeO_2.	0.35–5	L[001]	4.20	15	2.26	34.5
		S[110]	0.616	90	2.26	793
Far IR						
Ge	2–20	L[111]	5.50	30	4.00	840
$T1_3AsS_4$ (TAS)	0.6–12	L[001]	2.5	29	2.63	510
GaAs	1–11	L[110]	5.15	30	3.37	104
ZnTe	0.55–20	L[110]	3.37	130	2.77	18
GaP	0.6–10	L[110]	6.32	60	3.31	30
$T1_3PSe_4$	0.85–9	L[100]	2.0	150	2.9	2069
Te	5–20	L[100]	2.2	60	4.8	4400
CdS	0.5–11	L[100]	4.17	90	2.44	12
GaP	0.6–10	L[110]	6.32	60	3.31	30
ZnS	0.4–12	L[001]	5.82	27	2.35	3.4
		S[001]	2.63	130	2.35	8.4

[a] Longitudinal acoustic waves propagating along the [100] crystallographic direction.

[b] Shear acoustic waves propagating along the [001] crystallographic direction.

[c] Attenuation constant at 1 GHz; the frequency dependence of the attenuation for most crystals is quadratic.

where F is the focal length of the lens. The light intensity will be distributed in the focal plane with a sinc^2 distribution by aperture diffraction. The number of resolvable spots, N, will be the angular scan range divided by the angular diffraction spread,

$$N = \frac{\Delta\theta}{\Delta\phi} \qquad [25]$$

where $\Delta\theta$ is the range of the angular scan. Differentiating the Bragg angle formula yields

$$\Delta\theta = (\lambda/V \cos\theta_0)\Delta f \qquad [26]$$

and

$$N = \Delta f(D/V \cos\theta_0) = \Delta f\tau \qquad [27]$$

where θ_0 is the Bragg angle at band center, and τ is the time that it takes the acoustic wave to cross the optical aperture. The resulting expression is the time–bandwidth product of the acousto-optic scanner, a concept applied to a variety of electronic devices as a measure of information handling capacity. The time–bandwidth product of an acousto-optic Bragg cell is equivalent to the number of bits of information which may be instantaneously processed by the system. In order to maximize the number of resolution elements, it is desirable to have as large a bandwidth as possible (i.e., large frequency range) and also as large an aperture delay time as possible. There are two factors limiting the bandwidth of an acousto-optic device: the bandwidth of the transducer structure (discussed later), and acoustic absorption in the delay medium. The acoustic absorption increases with increasing frequency; for high-purity single crystals the increase generally goes with the square of the frequency. For glassy materials, on the other hand, the attenuation will increase more slowly with frequency, often approaching a linear function. The maximum frequency is generally taken as that for which the attenuation of the acoustic wave across the optical aperture is equal to



Figure 6 Acousto-optic scanner.

3 dB. A reasonable approximation of the maximum attainable bandwidth is

$$\Delta f = 0.7 f_{\max} \qquad [28]$$

Birefringent Scanners

The birefringent scanner is a significant use for anisotropic Bragg diffraction. There are a number of advantages with the birefringent scanner over the anisotropic scanner, such as a larger angular scan range along with lower frequencies. There are also disadvantages, such as lower speed due to generally lower shear wave velocities, and the particular application will dictate whether an isotropic or birefringent scanner is better. Scanners represent a fairly important aspect of acousto-optic devices due to the widespread commercial use of laser beam deflectors for displays and laser printers. For applications where the required speed is beyond that of mechanical scanners, the acousto-optic scanner is an ideal candidate. However, unlike mirrors, acousto-optic deflectors are wavelength sensitive, and can only be used with single-wavelength laser beams.

The birefringent scanner can be described with the wavevector diagram, as shown in Figure 7 for a positive uniaxial crystal where the extraordinary index of refraction is larger than the ordinary. The acoustic wavevector is tangent to the diffracted surface, which produces the largest scan angle for a given acoustic bandwidth. This is also the degenerate case, where only a single diffracted beam results, whereas two beams at two different acoustic frequencies will generally result from arbitrary input and acoustic propagation directions. The azimuthal acceptance angles (angles normal to the plane of incidence) of the acoustic and optical wavevectors can be different, although propagation and polarization directions must be selected that will produce high efficiency.



Figure 7 Wavevector diagram for birefringent scanner using a positive uniaxial crystal.

For the positive uniaxial case, the acoustic and diffracted wavevectors will be perpendicular at the design point, which allows the center frequency to be calculated from geometry as

$$f_0 = (V/\lambda)(n_i^2 - n_0^2)^{1/2} \qquad [29]$$

where n_i is the index of refraction at the incidence angle. Due to the typically low velocity of shear waves, this frequency can be much lower than an isotropic scanner, and the incidence angle can also be chosen to adjust the frequency. It is also possible to use the optical activity of certain materials such as TeO_2, along with circularly polarized light to further reduce the acoustic frequency. It is important to maintain as low a frequency as possible due to acoustic attenuation, which is especially high with the soft materials typically used for birefringent applications.

The bandwidth over which the scanner can efficiently operate is fairly large due to having the acoustic and diffracted wavevectors perpendicular, and is approximately $\Delta f = 2f_0$, assuming an octave of bandwidth for the isotropic scanner. This will produce a larger scan angle than an isotropic scanner, and more spots of resolution. The number of resolution spots is determined through diffraction by the aperture size and diffraction, along with the scan angle. Since a larger aperture requires a longer time for the acoustic waves to propagate across the aperture, the response time τ to access the scanner will increase, and the product of τ and f is related to the number of spots by eqn [27]. The advantage of the birefringent scanner is that it can operate at a lower frequency f_0 with better performance. However, since other factors such as acoustic attenuation are important in designing a scanner, for some applications it might be better to operate an isotropic scanner at a higher frequency.

AOTFs

With anisotropic Bragg diffraction, the magnitude of the diffracted wavevector $\mathbf{k}_d$ will differ from the incident wavevector $\mathbf{k}_i$, which cannot occur for the isotropic case. This is illustrated in Figure 8 for an AOTF utilizing a negative uniaxial crystal where an extraordinary input wave propagating at an incident angle θ_i relative to the crystal axis is diffracted into an ordinary output wave at an angle θ_d. This occurs through an acoustic wave propagating at an angle θ_a



Figure 8 Wavevector diagram for an AOTF using a negative uniaxial crystal.

with wavevector $\mathbf{K}_a$, where all the wavevectors lie in a plane through the optic axis of the crystal. This diagram is identical to the index ellipsoid for the crystal, scaled by $2\pi/\lambda$, where λ is the vacuum wavelength. The acoustic wavevector is shown as adding to the incident wavevector, which increases the frequency of the optical wave by the acoustic frequency. It can also be represented in the reverse direction, which would reduce the optical frequency by the same amount.

An AOTF spectrally filters the optical input, and maintains its spectral purity over a large angular aperture. These conditions are maximized when the power flow or ray directions of the input and output beams are collinear. This produces a parallel-tangents condition, where lines drawn tangent to the wavevector surfaces and connecting the input and diffracted wavevectors are parallel. For beams at 90° to the optical axis, it is referred to as the collinear case, whereas all other parallel-tangents conditions are noncollinear. The diffracted beam is rotated by 90° during anisotropic Bragg interaction, so that crossed polarizers can be used to separate the input and diffracted beams. For the collinear case polarization separation must be used, whereas angular separation can also be used for the noncollinear case.

The AOTF design equations can be derived from the geometrical conditions imposed by the wavevector matching condition

$$\mathbf{k}_d = \mathbf{k}_i + \mathbf{K} \qquad [30]$$

along with decomposing the acoustic wave into its Fourier components which result from the finite interaction length produced by the transducer. These components allow for phase matching over a range of input angles, and they also allow for a spectral spread of the interaction. The full width half maximum (FWHM) resolution is given by

$$\Delta\lambda = \frac{1.8\lambda^2}{bL\sin 2\theta_i} \qquad [31]$$

where λ is the vacuum wavelength, b is the dispersion term (essentially $2\pi\Delta n$, where the birefringence Δn is the difference between the ordinary index n_0 and extraordinary index n_e of refraction), L is the interaction length of the input beam defined geometrically by the acoustic beam, and θ_i refers to the angle of the central or cardinal ray of the input beam, and the AOTF is designed around this angle. It is therefore a sensitive function of the incidence design angle, with the highest resolution occurring for the collinear case. The resolution is also narrower for larger birefringence.

The geometry of a noncollinear AOTF is shown schematically in Figure 9. The acoustic waves propagate in the correct direction and are generated by a transducer of length L_t, which is related geometrically to the interaction length. These waves are generally absorbed at the other side of the AOTF to prevent interfering reflections, and the sides may also be wedged to eliminate reflections into the interaction region. The optical beam enters the AOTF at the correct angle to the crystal optic axis, and either diffracts or passes through as the zero order. The input beam will have an angular spread, producing an acceptance angle that is a function of the interaction length, wavelength, and crystal parameters, and the external solid angular aperture



Figure 9 Noncollinear AOTF orientation of optical and acoustic beams.

is roughly given by

$$\Delta\Omega = \frac{\pi n^2 \lambda}{\Delta n L} \qquad [32]$$

where n refers to the diffracted beam index of refraction, which can be either n_0 or n_e depending upon the design. The resolution and solid angle are therefore related through the transducer length, and the product of the resolving power times the solid angle is given by

$$(\lambda/\Delta\lambda)(\Delta\Omega) = 2\pi n^2 \sin^2\theta_i / |F_\theta F_\varphi|^{1/2} \qquad [33]$$

where

$$F_\theta = 2\cos^2\theta_i - \sin^2\theta_i \qquad [34a]$$

$$F_\varphi = 2\cos^2\theta_i + \sin^2\theta_i \qquad [34b]$$

are form factors for the polar and azimuthal components of the optical field. Since all the wavectors lie in a plane containing the optic axis, the azimuthal components of the incident, diffracted, and acoustic wavevectors must always be identical under the parallel-tangents condition.

The product $(\lambda/\Delta\lambda)(\Delta\Omega)$ forms a figure of merit for spectrometers, and for the collinear case, the product is identical to a Fabry–Perot etalon having an index of n, and at other angles it is more complicated due to the angular dependence. The angular field is also symmetrical for the collinear AOTF, but nowhere else other than along the optic axis, where the resolving power becomes zero.

The great advantage of the AOTF designed under the parallel-tangents condition is the large angular aperture compared to the general case. Under this condition, the dependence of the angular aperture on resolving power is second order rather than first order, and the angular aperture can be tens of degrees for a typical resolution, which is useful for imaging applications. At the special angle of 54.7°, the second-order dependence is also zero, and the aperture can be extremely large relative to the resolving power, although this requires a high-resolution device with a corresponding narrow field, since the condition would soon be violated at larger field angles.

The efficiency of the AOTF under phase matching is given by

$$\eta = \sin^2[\pi^2 M_2 P_a L^2/(2\lambda^2)]^{1/2} \qquad [35]$$

which depends on θ_i and various material properties. Since the interaction is anisotropic, M_2 must be taken as a tensor quantity, in which both the polarization and propagation directions of the acoustic and optical waves must be accounted for. For acoustic waves, the polarization direction is the particle motion, which is perpendicular to the propagation direction for shear waves. In general, M_2 is much larger for a specific configuration of a particular material, and AOTFs are designed around this condition. The range of useful design angles is also usually limited since M_2 is generally a sensitive function of θ_i. The angular dependence on M_2 is important in designing an efficient device since it can be near zero at specific design angles for some materials, such as with TeO_2 for the collinear case.

The AOTF must be designed to optimize performance. The resolution is generally given as a system requirement, and the design angle along with the transducer length must be adjusted to optimize the throughput, or total optical power through the AOTF. This requires maximizing the efficiency, angular aperture, and aperture dimension. The maximum crystal size that can be grown ultimately limits these parameters, both in the interaction length and in the aperture size.

AOTFs have been used for a wide range of spectral filtering applications for spectroscopy and laser applications. Both collinear and noncollinear devices have electronically tuned a variety of lasers, including dye, semiconductor, and Ti:sapphire lasers. The AOTF is placed within the laser cavity, which requires high transmission on the laser line, with enough resolution to separate nearby laser transitions. A related application is the multiplexing of optical communications systems, where the AOTF is used to separate the various laser diode wavelengths. Perhaps the most widely used application is spectroscopy, and single-point detection systems have been used for a variety of biological and chemical applications in the visible and infrared. These techniques have been extended to spectral imaging, again in the visible and the infrared. Due to a variety of AOTF aberrations the image quality will be somewhat degraded. Since the AOTF is electronically tunable, it can be rapidly modulated both in amplitude and wavelength, which allows for modulation spectroscopy to detect small signals in a large background. By applying multiple frequencies, the AOTF has also been used as a rejection filter, in which all wavelengths other than that selected are allowed to pass.

Modulators

Acousto-optic modulators are used to vary and control laser beam intensity. A Bragg configuration gives a single first-order output beam, where intensity is directly linked to the power of RF control signal. The rise time of the modulator is the time required for the acoustic wave to traverse the laser beam. For minimum rise time the laser beam will be focused down, forming a beam waist as it passes through the modulator.

A Bragg configuration gives a single first-order output beam, the intensity of which is controlled by the RF signal power, and diffaction angle controlled by the drive frequency. Two deflectors can be used in series and at right angles to each other to give full two-dimensional scanning.

One requirement in the design of acousto-optic modulators is that the diffracted beam and undiffracted beam must be well separated. For an adequate extinction ratio, the Bragg angle should be at least as large as the divergence of the optical beam. This condition puts a minimum value on the center frequency. Equating the Bragg angle

$$\theta_{\mathrm{B}} = \frac{\lambda f_0}{2nV} \qquad [36]$$

and the diffraction angle of the Gaussian beam

$$\delta\theta_0 = \frac{4\lambda}{\pi(nd)} \qquad [37]$$

where d is the beam diameter at the minimum, it follows that the lower limit of the acoustic frequency is given by

$$f_0 = \frac{8}{\pi\tau} \qquad [38]$$

We may combine these expressions to determine a limit of modulator bandwidth of acousto-optic modulators, with the result

$$\Delta f \sim \frac{1}{4} f_m \qquad [39]$$

i.e., the modulation bandwidth is approximately equal to 25% of the midband acoustic frequency, f_{m}. In view of the present status of transducer technology, the modulation bandwidth of acousto-optic modulators is limited to several hundred MHz.

A frequency shifter uses the shift inherent in the acousto-optic interaction to up- or down-shift a laser's frequency. Two kinds of shifters can be distinguished: the fixed frequency shifter, and the variable frequency shifter. The frequency shift is equal to the signal frequency applied to the transducer. Various device configurations can be used to shift the laser beam, such as multiple travels inside the shifter to double or triple the frequency shift, or a combination of two frequency shifters in series. Acousto-optic frequency shifters can be used, for example, in optical heterodyning and interferometry, or in laser Doppler velocimetry for particle velocity analysis.



Figure 10 An acousto-optic *Q*-switch in a laser cavity.

Q-Switches

A *Q*-switch is a special modulator which introduces high repetition rate losses inside a laser cavity (typically 1 to 100 KHz). They are designed for minimum insertion loss and to be able to withstand very high laser powers. In normal use an RF signal is applied to diffract a portion of the laser cavity flux out of the cavity. This increases the cavity losses and prevents oscillation. When the RF signal is switched off, the cavity losses decrease rapidly and an intense laser pulse evolves. A diagram of a typical acousto-optic *Q*-switched laser cavity is shown in Figure 10. *Q*-switches are the preferred method of intracavity modulation where high speed, high stability, and modest cost are important design factors.

List of Units and Nomenclature

b	dispersion constant	–
c	elastic stiffness	dynes cm^{-2}
D, d	optical beam diameters	cm
e	elastic strain	–
f	acoustic frequency	hertz
F	optical focal length	cm
F_ϕ, F_θ	angular form factors	–
$\mathbf{k}$	optical momentum wavevector	cm^{-1}
$\mathbf{K}$	acoustic momentum wavevector	cm^{-1}
M_2	acousto-optic figure of merit	sec^3 gram^{-1}
n	refractive index	
p	photo-elastic constant	–
P	pressure	dynes cm^{-2}
P_{a}	acoustic power	watts cm^{-2}
V	acoustic velocity	cm sec^{-1}
β	compressibility	cm^2 dyne^{-1}
η	diffraction efficiency	–
ε	dielectric constant	–
ω	optical frequency	hertz
Ω	solid angle	steradians
ρ	density	grams cm^{-3}
θ	Bragg angles	radians
τ	acoustic wave travel time	sec

See also

Modulators: Acousto-Optics. **Optical Amplifiers:** Raman, Brillouin and Parametric Amplifiers. **Scattering:** Raman Scattering. **Spectroscopy:** Raman Spectroscopy.

Further Reading

Chang IC (1976) Acousto-optic devices and applications. *IEEE Transactions: Sonics and Ultrasonics* SU-23: 2–22.
Chang IC (1981) Acousto-optic tunable filter. *Optical Engineering* 20: 824–829.
Dixon RW (1967) Photo-elastic properties of selected materials and their relevance for applications to acoustic light modulators and scanners. *Journal of Applied Physics* 38: 5149–5153.
Gordon EI (1966) A review of acousto-optical deflection and modulation devices. *Proceedings of the IEEE* 54: 1391–1401.
Gottlieb M, Ireland CLM and Ley JM (1983) *Electro-optic and Acousto-optic Scanning and Deflection*. New York: Marcel Dekker.
Goutzoulis AP and Pape DR (1994) *Design and Fabrication of Acousto-optic Devices*. New York: Marcel Dekker.
Uchida N and Niizeki N (1973) Acousto-optic deflection materials and techniques. *Proceedings of the IEEE* 61: 1073–1092.
Xu J and Stroud R (1992) *Acousto-optic Devices: Principles, Design, and Applications*. New York: Wiley.

Electro-Optics

L R Dalton, University of Washington, Seattle, WA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

The electro-optic (EO) effect can be described as any one of a number of phenomena that occur when an electromagnetic wave in the optical spectrum (e.g., characterized by wavelengths in the range 200 to 2000 nm) interacts with an electric field, or with matter under the influence of an electric field. Two of the most important electro-optic phenomena are the Kerr effect (discovered by John Kerr in 1875) and the Pockels effect (discovered by Friedrich Pockels in 1893), in which birefringence is induced or modified in a liquid (the Kerr effect) or a solid (the Pockels effect). Birefringence is the difference in refractive indices for light of orthogonal line polarizations, one of which is parallel to the induced optical axis. The Kerr effect involves creation of birefringence in a liquid that is otherwise not birefringent. The degree of birefringence is quadratically proportional to the applied electric field strength. Hence, the Kerr effect is frequently referred to as the quadratic electro-optic effect while the Pockels effect involves a linear dependence on the applied electric field and is referred to as the linear electro-optic effect. In considering practical applications of the electro-optic effect, a commonly encountered term is that of 'electro-optic modulator', which can be described as a device wherein a signal control element is used to modulate a beam of light. The control element is typically an electric field with frequency components in the zero (DC) to hundreds of gigahertz ($1\ \mathrm{GHz} = 10^9\ \mathrm{Hz}$) range (or even tens of terahertz ($1\ \mathrm{THz} = 10^{12}\ \mathrm{Hz}$). The modulation may be imposed on the phase, frequency, amplitude, or direction of the modulated optical beam.

Electro-optic effects are one class of second-order nonlinear optical phenomena. Other important second-order nonlinear optical phenomena include sum (e.g., second-harmonic) and difference frequency generation. Such phenomena derive from the second-order term in the power series expansion of macroscopic (material) polarization, P, in terms of applied electric fields:

$$P_i = \chi_{ij}^{(1)} E_j + \chi_{ijk}^{(2)} E_j E_k + \chi_{ijkl}^{(3)} E_j E_k E_l + \cdots \qquad [1]$$

where $\chi_{ij}^{(1)}$, $\chi_{ijk}^{(2)}$, and $\chi_{ijkl}^{(3)}$ are the linear, second-, and third-order optical susceptibilities, respectively. Second-harmonic generation (SHG) or frequency doubling (2ω) effects, where a beam at twice the frequency of the input beam is generated, can be seen by substituting a sinusoidal field, $E_\omega \cos(\omega t - kz)$; for E_j and E_k. After using a well-known trigonometric identity, the equation for macroscopic polarization becomes (through second-order and dropping the subscript i):

$$\begin{aligned} P = {} & \chi^{(1)} E_\omega \cos(\omega t - kz) + (1/2)\chi^{(2)} E_\omega^2 \\ & \times [1 + \cos(2\omega t - 2kz)] + \cdots \qquad [2] \end{aligned}$$

The electro-optic effect can be appreciated by considering interaction of the medium with an optical field $E_\omega \cos(\omega t - kz)$ and a low-frequency field E_0. Note that although we have used the symbol zero to denote the frequency of the low-frequency electrical field, actual frequencies can extend to hundreds of gigahertz or even tens of terahertz. Again substituting (and now keeping terms to third order), the equation for polarization can be written as:

$$\begin{aligned} P &= \chi^{(1)}E_\omega \cos(\omega t - kz) + 2\chi^{(2)}E_0 E_\omega \cos(\omega t - kz) \\ &\quad + 3\chi^{(3)}E_0^2 E_\omega \cos(\omega t - kz) + (3/4)\chi^{(3)}E_\omega^3 \cos(\omega t - kz) \\ &= \chi_{\text{eff}} E_\omega \cos(\omega t - kz) \end{aligned} \qquad [3]$$

The equation for the nonlinear index of refraction, n, can be expressed as

$$\begin{aligned} n^2 &= 1 + 4\pi\chi_{\text{eff}} \\ &= 1 + 4\pi[\chi^{(1)} + 2\chi^{(2)}E_0 + 3\chi^{(3)}E_0^2 + (3/4)\chi^{(3)}E_\omega^2] \end{aligned} \qquad [4]$$

Denoting the linear index of refraction as n_0, the above equation can be rewritten as

$$n^2 - n_0^2 = 8\pi\chi^{(2)}E_0 + 12\pi\chi^{(3)}E_0^2 + 3\pi\chi^{(3)}E_\omega^2 \qquad [5]$$

which in turn leads to

$$\begin{aligned} n &= n_0 + (4\pi/n_0)\chi^{(2)}E_0 + (6\pi/n_0)\chi^{(3)}E_0^2 \\ &\quad + (3\pi/2n_0)\chi^{(3)}E_\omega^2 \end{aligned} \qquad [6]$$

The definition of light intensity in cgs units is $E_\omega^2 = (8\pi/cn_0)I(\omega)$, which when substituted into the above equation gives

$$\begin{aligned} n &= n_0 + (4\pi/n_0)\chi^{(2)}E_0 + (6\pi/n_0)\chi^{(3)}E_0^2 \\ &\quad + (12\pi/cn_0^2)\chi^{(3)}I(\omega) \end{aligned} \qquad [7]$$

The index of refraction can now be written as

$$n(\omega) = n_0(\omega) + n_1(\omega)E_0 + n_2(0)E_0^2 + n_3(\omega)I(\omega) \qquad [8]$$

where the terms $n_1(\omega)$, $n_2(0)$, $n_3(\omega)$ correspond to the linear electro-optic effect, the quadratic electro-optic effect, and the optical Kerr effect, respectively. The above equation can also be expressed as

$$n = n_0 - (1/2)n^3 rE_0 - (1/2)n^3 sE_0^2 - \cdots \qquad [9]$$

where r and s are the linear and quadratic electro-optic coefficients, respectively.

Unfortunately, a great deal of confusion exists concerning the use of the terms electro-optic effect and electro-optic modulator. First of all, the terms 'electro-optic' and 'opto-electronic' are frequently confused and used interchangeably. Opto-electronic devices function as electrical-to-optical or optical-to-electrical signal transducers. Examples of commonly used opto-electronic devices include light-emitting diodes (LEDs), photodiodes (PDs), injection laser diodes (ILDs), and integrated optical circuit (IOC) elements. An electro-optic device can also function as an electrical-to-optical signal transducer (e.g., a Mach–Zehnder interferometer or a birefringent modulator employing polarizers at the input and the output); however, the mode of operation is entirely different for electro-optic and opto-electronic devices. For example, with LEDs or modulated lasers, the applied electric field produces modulation of transmission of light by altering the excited state population of the light emitting (lasing) state of the material. With electro-optic materials, no actual excited state population is generated. Electro-optic devices typically operate in regions of the optical spectrum removed from resonant transitions, i.e., regions of relatively high transparency. The applied electric field acts only to perturb the charge distribution of the material (the spatial positions of the electrons and nuclei). The altered charge distribution interacts with the optical beam transmitting the material with the result that the speed of light in the material (i.e., the index of refraction or birefringence) is altered. The response times of opto-electronic and electro-optic phenomena (and hence bandwidths of devices exploiting these phenomena) are quite different. In the former case, response will be limited by the lifetime of the relevant (emitting) excited state while in the latter case, response will be defined by the relaxation time of the material (e.g., reorientation time of a liquid or lattice relaxation time of a solid) following removal of the perturbing electric field.

An even greater confusion can arise due to the jargon used in particular technologies, such as telecommunications. A telecommunications engineer frequently refers to 'electro-optic switching' when describing opto-electronic transduction of an optical signal to an electrical signal, followed by re-routing in the electrical domain, and finally opto-electronic transduction of the electrical signal back to the optical domain. Electro-optic switching (in the sense used in this article) involves quite a different operation and would be described by that same telecommunications engineer as 'all-optical switching' – a term reserved by physicists for the optical Kerr effect (control of one light beam by another light beam).

A second point of confusion involves distinguishing between the terms 'electro-optic' and 'electro-absorptive' modulation. Again, the terms are frequently used interchangeably. However, they involve quite different physical mechanisms. An electro-absorptive modulator is, like a modulated laser or LED, a 'resonant' device. In a device such as a gallium arsenide (GaAs) or indium phosphide (InP) quantum dot electro-absorptive modulator, the position and width of an optical absorption (resonant transition) are defined by the physical dimensions of the quantum dot. Application of an electric field shifts the spectral wavelength of the quantum dot absorption. This phenomenon can be used to dramatically change optical transmission through (or equivalently, absorption by) the material by choosing the wavelength of the propagating beam of light to be near the resonant absorption. With the electric field off, the material is reasonably transparent but becomes strongly absorbing when the electric field is applied, shifting the resonant absorption to the wavelength of the propagating beam. Obviously, the voltage required to achieve a desired change in optical transmission will depend on control of quantum dot dimensions in fabrication, which has been and continues to be a topic of research focus for electro-absorptive materials. Likewise, control of insertion losses of such devices is a concern as the wavelength used for the transmissive state of the device must be sufficiently close to the optical resonance to achieve the desired attenuation with application of a modest control voltage. Another issue to be faced with electro-absorptive devices is that of 'chirp' (optical signal distortion arising from the fact that both absorption and index of refraction – the imaginary and real parts of the optical susceptibility – change with application of the electric control field). On the positive side, electro-absorptive modulators are 'polarization-insensitive' modulators and are thus conveniently used with multimode (as well as single mode) optical transmission.

Further confusion exists because widely different types of materials can be used in electro-optic and electro-absorptive devices. As these materials are frequently competing for the same applications (signal transduction, optical switching, etc.), the advantages and disadvantages of different materials are often compared without maintaining the context that quite different phenomena are involved. Even restricting our discussion to electro-optic materials, we note that materials can range from organic liquid crystalline materials (nematic, smetic, ferroelectric, etc.) to organic electro-optic materials (both crystalline and 'macromolecular') to inorganic crystalline materials (lithium niobate, $LiNbO_3$; barium titanate, $BaTiO_3$; barium borate, BBO; potassium dihydrogen phosphate, KDP; lithium tantalate, $LiTaO_3$; zinc telluride, ZnTe, etc.). The response times of these materials to transient application of an applied electric field will be quite different, reflecting the different types of lattice motion involved. With liquid crystalline materials, particularly nematic materials, considerable molecular reorientation is involved and due to the mass that must be moved, response times are quite slow although the index change will be relatively large. With use of liquid crystalline materials, device bandwidths will typically be limited to tens of megahertz (MHz) or less. In contrast, conjugated π-electron organic materials typically exhibit response times of tens to hundreds of femtoseconds, which translates to potential device bandwidths of tens of terahertz (actual device bandwidths may be less due to factors other than material response). For conjugated π-electron organics, the response time is the phase relaxation time of the π-electron system. Because only a slight change in bond length alternation of the conjugated π-electron system occurs with application of an applied electric field and because strong electron–phonon coupling and resonance stabilization of the π-electron system act to reduce the barrier to lattice relaxation, the response times of π-electron organic materials are among the fastest observed in nature. With crystalline inorganic materials, the ionic constituents move to new locations with application of an electric field with the exact movement determined by the field strength, the charge on the ions, and the restoring force. Unequal restoring forces along the three mutually orthogonal (perpendicular) axes of the crystal lead to anisotropy in the optical properties of the material. The applied electric field will induce a change in the anisotropy (the principal refractive indices). The symmetry of the electro-optic tensor will be closely related to the symmetry of the piezoelectric tensor. The linear electro-optic effect requires that the crystal exhibit noncentrosymmetric (acentric or ferroelectric) symmetry. A centrosymmetric crystal possesses a center of symmetry defined by identical particles existing in the lattice at vectors $\mathbf{r}$ and $-\mathbf{r}$, where $\mathbf{r}$ is a position vector measured from an arbitrary origin. A centrosymmetric crystal, like an isotropic liquid or gas, can exhibit a quadratic electro-optic effect.

For the sake of completeness, it can also be noted that index of refraction changes can be induced by acoustic waves (acousto-optic modulation) and by heating (thermo-optic modulation). Also, elasto-optic and photo-elastic effects can produce index of refraction changes.

To keep this article to a manageable length, discussion is limited to solid-state electro-optic materials. Design principles being used to produce new organic electro-optic materials will be illustrated. Since inorganic materials exist as crystals, limited chemical modification of such materials is possible, although processing techniques for fabricating thin films of such crystalline materials have been developed in a number of cases. For organic macromolecular materials, development of new materials is an on-going activity. Several representative devices being fabricated, using electro-optic materials, will be discussed. Four of the most commonly encountered types of EO devices include: (i) stripline devices; (ii) prism, cascaded prism, and superprism devices; (iii) resonated devices, such as ring microresonator and photonic bandgap devices, and (iv) waveplates. Of course, devices such as stripline devices can be configured in a variety of ways to produce polarization-sensitive and polarization-insensitive electrical-to-optical signal transducers, optical switches either using simple 1 × 2 or 2 × 2 switch architectures or multimode interference (MMI) switches, optical gyroscopes, photonically controlled phased array radar systems, spectrum analyzers, optical digital signal processors, analog-to-digital (A/D) and digital-to-analog (D/A) signal converters, electromagnetic (radiofrequency to millimeter wave) signal generators, voltage sensors, etc. Prism-type devices are typically used for spatial light modulation or laser beam deflection. Ring microresonator devices afford a rich array of applications ranging from active wavelength division multiplexing (WDM) to active optical interconnect reconfiguration, to voltage-controlled wavelength tuning of laser outputs.

Basic Relationships

The effect of the applied field is to deform the index of refraction ellipsoid, which can be represented as

$$\left(\frac{1}{n^2}\right)_1 X^2 + \left(\frac{1}{n^2}\right)_2 Y^2 + \left(\frac{1}{n^2}\right)_3 Z^2 + 2\left(\frac{1}{n^2}\right)_4 YZ + 2\left(\frac{1}{n^2}\right)_5 XZ + 2\left(\frac{1}{n^2}\right)_6 XY = 1 \qquad [10]$$

leading to the corrections

$$\Delta\left(\frac{1}{n^2}\right)_i = \sum_{j=1}^{3} r_{ij} E_{0j} \qquad [11]$$

where the electro-optic tensor components are related to the tensor components of the second-order nonlinear optical susceptibility by $r_{ij} = -(8\pi/n_{0i}^2 n_{0j}^2)\chi_{ji}^{(2)}$. The full tensorial equation for change of the 'indicatrix' (index of refraction ellipsoid) can be expressed as

$$\begin{pmatrix} \Delta\left(\frac{1}{n^2}\right)_1 \\ \Delta\left(\frac{1}{n^2}\right)_2 \\ \Delta\left(\frac{1}{n^2}\right)_3 \\ \Delta\left(\frac{1}{n^2}\right)_4 \\ \Delta\left(\frac{1}{n^2}\right)_5 \\ \Delta\left(\frac{1}{n^2}\right)_6 \end{pmatrix} = \begin{pmatrix} r_{11} & r_{12} & r_{13} \\ r_{21} & r_{22} & r_{23} \\ r_{31} & r_{32} & r_{33} \\ r_{41} & r_{42} & r_{43} \\ r_{51} & r_{52} & r_{53} \\ r_{61} & r_{62} & r_{63} \end{pmatrix} \begin{pmatrix} E_{0X} \\ E_{0Y} \\ E_{0Z} \end{pmatrix} \qquad [12]$$

The electro-optic tensor reduces considerably for specific materials reflecting the symmetry of the particular material. For inorganic crystalline materials, the electro-optic tensor can be reasonably complex (containing many nonzero elements). It is also helpful to note that for crystalline inorganic materials, the electric-field-induced change in crystal shape leads to strain and the orientation of the indicatrix is altered, leading to an additional contribution to the change in index coefficients:

$$\Delta(1/n^2)_i = \sum_k p_{ik} S_k + \sum_j r_{ij} E_j \qquad [13]$$

where S_k is a component of the strain and p_{ik} is the elasto-optic tensor. At high frequencies, the inertia of the crystal prevents macroscopic straining so that the first term of the above equation vanishes. At low frequencies, elasto-optic effects cannot be ignored. Because the deformation leading to strain is generally caused by the inverse piezoelectric effect, it is linearly related to the applied electric field (the same dependence as the linear electro-optic effect). This can lead to a frequency dependence of the 'effective' electro-optic coefficient for crystalline materials.

A brief comment on the photo-elastic effect (the change in index coefficients produced directly by applied stress) is warranted. This effect has the form:

$$\Delta(1/n^2)_i = \sum_l \pi_{il} \sigma_1 \qquad [14]$$

where σ_l are the components of the stress and π_{il} are the piezo-optical coefficients. Note that this effect is independent of the applied electric field.

For axially symmetric 'charge-transfer type' organic chromophores prepared by deposition or electric field poling, only two unique tensor elements, r_{33} and r_{13}, survive:

$$\tilde{r} = \begin{pmatrix} 0 & 0 & r_{13} \\ 0 & 0 & r_{13} \\ 0 & 0 & r_{33} \\ 0 & r_{13} & 0 \\ r_{13} & 0 & 0 \\ 0 & 0 & 0 \end{pmatrix} \qquad [15]$$

The electro-optic effect for organic macromolecular materials derives from molecules with conjugated π-electrons confined within molecules (chromophores). The electro-optic tensor elements can be related to molecular first hyperpolarizability, β, and the chromophore number density, N (molecules/cm^3), by

$$\begin{aligned} r_{33} &= -2Nf(0)\beta\langle\cos^3\theta\rangle/n_0e^4 \\ r_{13} &= -Nf(0)\beta\langle\sin^2\theta\cos\theta\rangle/n_{0o}^2n_{0e}^2 \end{aligned} \qquad [16]$$

The expressions in brackets are 'order parameters' describing the degree of noncentrosymmetric order. $\langle\cos^3\theta\rangle = 1$ corresponds to all 'dipolar' (charge transfer type) molecules pointing in the same direction (perfect noncentrosymmetric or ferroelectric order) while $\langle\cos^3\theta\rangle = 0$ corresponds to complete disorder and no electro-optic effect. The reason that three angles appear in the order parameter is that an angle is required to represent the principal symmetry axis for the chromophore, the principal symmetry axis of the optical field, and the principal symmetry axis of the electric control field. Thus, averaging (denoted by brackets) must be carried out over each of these three angles. The tensor element r_{33} corresponds to the electric control field applied along the principal axis of the ordered chromophores and the principal axis of the optical field vector, transverse magnetic (TM) polarized light. The tensor element r_{13} corresponds to the control electric field applied along the principal axis of the optical field, transverse electric (TE) polarized light, and orthogonal to the principal chromophore axis. The notation r_{33} is contracted notation for r_{333}. The factor $f(0)$ takes into account the dielectric nature of the medium into which the chromophores (molecules with large first hyperpolarizability) are embedded.

For organic electro-optic materials, elasto-optic effects do not appear to make significant contributions. Moreover, electro-optic activity can be systematically improved by improving β and by optimizing the product of chromophore number density and order parameter. Due to the presence of intermolecular electrostatic interactions, W, among chromophores, order parameters and number density are not independent, e.g., for materials that are prepared by electric field poling the order parameter relevant to the principal component of the electro-optic tensor can be expressed approximately as

$$\langle\cos^3\theta\rangle = L_3(\mu f(0)E_\mathrm{p}/kT)[1 - L_1(W/kT)^2] \qquad [17]$$

where L_3, and L_1 are Langevin functions, μ is the chromophore dipole moment, E_p is the strength of the electric poling field, k is the Boltzmann constant, and T is the Kelvin poling temperature. W is a quadratic function of chromophore number density, N. The above equation indicates that a maximum will be observed in the graph of r_{33} versus N.

Materials

With inorganic and organic crystalline materials, very little can be done to optimize electro-optic activity other than discovering new EO crystalline materials or employing isotopic (e.g., deuterium for hydrogen) or ion substitution with existing materials.

As with organic liquid crystalline materials, the electro-optic activity of macromolecular organic second-order nonlinear materials can be systematically improved by molecular modification. As shown in Figure 1, quantum mechanical calculations can provide useful guidance as to which structural modifications will lead to improvements in molecular (first) hyperpolarizability and ultimately electro-optic activity. The molecular hyperpolarizability (long wavelength limit) can be increased by a factor of two by simple variation of the acceptor structure. The calculated values of wavelengths for the interband charge transfer transitions are 390 nm, 403 nm, and 430 nm. Since dipole moments do not change significantly with structure, intermolecular electrostatic interactions should be similar for these three chromophores and the improvement in β should translate to an improvement in electro-optic activity. This theoretical prediction has been experimentally verified. This is just one example of use of quantum mechanics to guide the improvement of electro-optic activity for organic materials. This figure also illustrates the typical structure of an organic electro-optic chromophore, which consists of an electron donor region (an amine donor in the example shown), a connective conjugated π-electron bridge, and an electron deficient electron acceptor region. The theoretically predicted (by density functional theory, DFT, calculations) variation of molecular first hyperpolarizability with molecular structure has been verified for the structures shown. However, the critical point is that electro-optic activity of organic materials (currently exhibiting a maximum value of 182 pm/V at 1.3 microns wavelength) is likely to be improved for some time to come. This value is to be compared to a value of 32 pm/V for lithium niobate. Another factor influencing the value of macroscopic electro-optic activity realized for electrically poled organic materials is the effect of intermolecular electrostatic interactions on optimization of $N\langle\cos^3\theta\rangle$. Statistical mechanical calculations can provide guidance as to how this is achieved (see Figure 2 where the role of chromophore shape is illustrated). Approximating the chromophore shape by a rigid prolate ellipsoid with embedded dipole moment yields nearly quantitative reproduction of the experimental data. If the π-electron structure (dipole moment) is left unchanged but the shape of the chromophore is altered to a spherical shape, a significant improvement in electro-optic activity is predicted. The shape effect arises because there are two components to the electronic dipole–dipole intermolecular electrostatic potential function describing the many body interaction of chromophores.



1 2 10

	1	2	10	
Dipole moment:	11.8	11.9	11.7	Debye
Hyperpolarizability	23.8	34.4	43.0	$*10^{-30}$ esu

Figure 1 Density functional calculations (DFT) of molecular first hyperpolarizability (β) and dipole moment (μ) for three chromophore structures.



Figure 2 Two theoretical (statistical mechanical) simulations of the variation of electro-optic activity with chromophore number density are shown and compared with experimentally observed results for the CLD chromophore (structure shown) dissolved in an amorphous polycarbonate host polymer.

One component favors centrosymmetric ordering while the second component favors noncentrosymmetric ordering. Their relative weighting in defining macroscopic order depends on chromophore shape. Theoretical calculations have also shown that embedding chromophores in nanoscopic macromolecular objects (such as dendrimers and dendronized polymers) can dramatically enhance electro-optic activity. This type of engineering can also be used to control auxiliary properties such as optical loss and stability. The exceptional processability of organic electro-optic materials has permitted conformal and flexible devices to be fabricated and has permitted electro-optic circuitry to be integrated vertically on top of semiconductor VLSI (very large-scale integration) electronics. Mach–Zehnder modulators, with 3 dB operational bandwidths of 200 GHz, have been fabricated from organic electro-optic materials as have Mach–Zehnder devices with operational drive voltages of less than one volt. The major advantage that crystalline inorganic materials possess, relative to macromolecular organic EO materials, is superior thermal and photostability. A comparison of lithium niobate and the best organic EO materials, is given in Table 1. Cost is a significant factor if electro-optic materials are to compete with modulated lasers and other opto-electronic devices for applications in communications, computing, transportation, and defense. Currently, manufacturing costs for both crystalline and macromolecular materials are very high (several thousand dollars per modulator). Recently, it has been demonstrated that organic macromolecular materials can be used with soft lithography techniques to mass-produce electro-optic circuitry. This could conceivably dramatically reduce manufacturing costs. Also, the fact that organic macromolecular materials can be directly integrated with silicon photonics and VLSI semiconductor electronics, may influence future commercial utilization of electro-optic materials, which is currently dominated by lithium niobate.

Table 1 Comparison of electro-optic performance for inorganic and organic EO materials at 1.3 microns wavelength

Parameter	*LiNbO$_3$*	*NLO polymer*
Effective EO coefficient, r_{eff}, pm/V	32	182
Index of refraction (n)	2.2	1.6–1.7
Dielectric permittivity (ε)	30	3
Material Figure of Merit, $n^3(r_{\mathrm{eff}})/\varepsilon$	10	270
Bandwidth × length product, GHz cm	7	>100
$V_\pi L$, V cm	5	1.5
Optical loss, dB/cm	0.2	0.2–1.0
Processing temperature (°C)	1000	<200
Multiple layers possible	No	Yes

Devices

Representative simple device structures are shown in Figure 3. For a simple stripline phase (birefringence) modulator (Figure 3, upper left), the phase retardation produced by application of an electric field is given by

$$\Delta\phi = 2\pi\Delta nL/\lambda = \pi n^3 rEL/\lambda = \pi n^3 rVL/\lambda d \qquad [18]$$

where L is the electrode length (the distance over which the electrical and optical fields co-propagate),


Optical phase modulator
E(t) = E$_0$e$^{i\phi(V(t))}$
V$_{mod}$(t)
Optical Mach–Zehnder amplitude modulator
E(t) = E$_0$sin(V(t)/V$_\pi$)
V$_{mod}$(t)
Optical amplitude modulator with complementary outputs
V$_{mod}$(t)
Optical micro-resonator modulator
V$_{mod}$(t)

Figure 3 Schematic representation of simple electro-optic device structures are shown: Upper left (birefringent modulator), upper right (Mach–Zehnder interferometer), lower left (1 × 2 optical switch), lower right (ring microresonator).

λ is the optical wavelength, $V = E/d$ is the electric field felt by the material, and d is the electrode spacing. Electro-optic device performance is frequently characterized by the voltage, V_π, required to produce a phase shift of π radians. For a TM polarized light propagating through a birefringent modulator:

$$V_\pi = \lambda d/(n_{0e}^3 r_{33} L\Gamma) \qquad [19]$$

where Γ characterizes the overlap of the optical and electrical waves.

A simple Mach–Zehnder interferometer (electro-to-optical signal transducer) is shown in the upper right of Figure 3. When such a device is constructed from electrically poled organic electro-optic chromophores and a voltage is applied to one arm, a retardation of light propagating in that arm will be effected. This, in turn, will result in a change in the constructive/destructive interference of the beams at the output of the device. The consequence of applying an electrical signal to one arm of a Mach–Zehnder interferometer is that the applied voltage is transduced onto the optical output beam as an amplitude modulation of that beam. The voltage required to achieve full wave modulation for an optical beam of TM polarization is

$$V_\pi = \lambda d/(n_{0e}^3 r_{33} L\Gamma) \qquad [20]$$

Amplitude modulation can also be achieved using a birefringent modulator by placing polarizers at the input and output of the device. If an input polarizer is used to launch TM and TE modes, the birefringent modulator functions to produce a rotation of light, which is turned into an amplitude modulation by inserting a polarizer at the output. For such a device, V_π depends upon the difference in r_{33} and r_{13}. Note that for poled organic chromophores, $r_{33} \approx 3r_{13}$, $(V_\pi)_{\mathrm{BRM}} \approx 1.5(V_\pi)_{\mathrm{MZM}}$. For the above devices, it is clear that V_π will depend on the length over which the electrical and optical fields co-propagate in phase. For low electrical field frequencies, L will be the electrode length. The electrode spacing d, that can be used, will depend on the index of refraction difference between the core (electro-optic material) and a cladding material used to prevent the optical field experiencing the metal electrodes (an event that would dramatically increase propagation loss). For poled organic macromolecular materials and standard commercial claddings, d is typically in the order of 10 microns. Electrode lengths usually range from 1 to 3 cm. Two factors limit bandwidth in stripline devices: (i) velocity mismatch between the electrical and optical waves (which relates to the difference between n_0^2 and ε, where ε is the dielectric permittivity of the material – see Table 1); and (ii) microwave and millimeter wave loss in the metal electrodes. For organic electro-optic materials, the latter defines operational 3 dB bandwidth of devices.

Optical routing switches (see Figure 3, lower left) are more complicated to understand and typically require somewhat larger V_π voltages to effect a switching operation (e.g., $(V_\pi)_{\mathrm{simple2\times2crossbar}} \approx 1.7(V_\pi)_{\mathrm{MZM}}$).

Two conditions must be satisfied for light to be coupled into a ring microresonator device (see Figure 3, lower right): (i) the circumference of the ring must be a multiple of the wavelength of light, and (ii) the velocity of light in the ring must equal the velocity of light at the input. If a ring microresonator is fabricated from an electro-optic material, then an applied electrical voltage can be used to control coupling of light into and out of the ring microresonator. The same electrode structure, that is used to achieve voltage-controlled wavelength selective filtering, can also be used to transduce electrical information onto the optical beam while it is in the ring resonator. The quality (Q) factor of a ring microresonator defines both the wavelength selectivity and the bandwidth of the device. Ring microresonator devices also have the advantage of permitting a long interaction length to be achieved in a very compact device structure. The dimensions (radii) of ring microresonator structures are defined by bending loss and thus by the difference between core and cladding materials. Typical radii can range from hundreds of nanometers to hundreds of microns. With ring microresonators, a reduction in drive voltage requirements can be achieved by trading off bandwidth. Another price paid in the use of ring microresonator device structures is that of bending loss, which is not present in the other device structure shown. Ring microresonators can be used for active wavelength division multiplexing (WDM), voltage-controlled optical signal routing, and wavelength tuning of optical sources.

The interaction length of a prism optical beam deflector can be increased by cascading prisms together. For such a device structure, the angle of deflection becomes

$$\theta = n_0^3 r_{33}(V/d)(L/h) \qquad [21]$$

where h is the height of an individual prism and L is the length of the prism array. For currently available electro-optic materials only small deflection angles (a few degrees or less) can be achieved with practical voltage levels. Superprism structures may permit large deflection angles to be achieved but such devices have yet to be demonstrated in a convincing manner.

See also

Interferometry: Overview. **Modulators:** Acousto-Optics. **Optical Communication Systems:** Wavelength Division Multiplexing.

Further Reading

Butcher PN and Cotter D (1990) *The Elements of Nonlinear Optics*. New York: Cambridge University Press.

Dagli N (1999) Wide-bandwidth lasers and modulators for RF photonics. *IEEE Trans. Microwave Theor. Techniques* 47: 1151–1171.

Dalton LR (2003) Rational design of organic electro-optic materials. *Journal of Physical Condensed Materials* 15: R897–R934.

Dalton L, Harper A, Ren A, *et al.* (1999) Polymeric electro-optic modulators: from chromophore design to integration with semiconductor very large scale integration electronics and silica fiber optics. *Ind. Eng. Chem. Res.* 38: 8–33.

Hornak LA (1992) *Polymers for Lightwave and Integrated Optics*. New York: Marcel Dekker.

Khazaei HR, Wang WJ, Berolo E and Ghannouchi F (1998) High speed GaAs/AlGaAs traveling wave electro-optic modulators. *Proceedings of SPIE* 3278: 94–100.

Lawetz C, Cartledge JC, Rolland C and Yu J (1997) Modulation characteristics of semiconductor mach-zehnder optical modulators. *IEEE Journal of Lightwave Technology* 15: 697–702.

Lee KS (2002). *Advances in Polymer Science*, vol. 158. Heidelberg: Springer.

Lee M, Katz HE, Erben C, *et al.* (2002) Broadband modulation of light using an electro-optic polymer. *Science* 298: 1401–1403.

Nalwa HS and Miyata S (1997) *Nonlinear Optics of Organic Molecules and Polymers*. Boca Raton, FL: CRC Press.

Noguchi K, Mitomi O and Miyazawa H (1998) Millimeter-wave Ti:$LiNbO_3$ optical modulators. *IEEE Journal of Lightwave Technology* 16: 615–619.

Shen YR (1984) *The Principles of Nonlinear Optics*. New York: John Wiley & Sons.

Shi Y, Zhang C, Zhang H, *et al.* (2000) Low (sub-1 volt) halfwave voltage polymeric electro-optic modulators achieved by controlling chromophore shape. *Science* 288: 119–122.

Wise DL, Wnek GE, Trantolo DJ, Cooper TM and Gresser JD (1998) *Electrical and Optical Polymer Systems. Fundamentals, Methods and Applications*. New York: Marcel Dekker.

Yariv A and Yeh P (1984) *Optical Waves in Crystals*. New York: John Wiley & Sons.

Modulation and Demodulation of Optical Signals

R A Minasian, University of Sydney, Sydney, NSW, Australia

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Since earliest times, light has been used for communication purposes. In order to convey information, a physical variable of light, such as the optical intensity or field amplitude, must be modulated to encode a signal onto the optical carrier, and it must be demodulated or decoded after transmission. Laser sources provide the capability of extremely high modulation speeds, which result in high information-carrying capacity in optical communication systems. After transmission, semiconductor photodetectors demodulate the optical signals to recover the original information (*see* **Optical Communication Systems:** Basic Concepts).

The modulation of optical signals can be classified into two types: field modulation and intensity modulation, which is illustrated in Figure 1. In field modulation, the physical variable that is modulated is the frequency, phase, or amplitude of the optical field. These three techniques are sometimes referred to as frequency shift keying (FSK), phase shift keying (PSK) and amplitude shift keying (ASK). Figure 1b shows an example of frequency modulation of light. Field modulation requires keeping track of the phase of the carrier, which imposes strict requirements on the optical coherence (*see* **Coherent Lightwave Systems**). Because the optical carrier is at an extremely high frequency of around 2×10^{14} Hz at fiber-optic communication wavelengths of 1.5 μm, the required optical coherence is very difficult to realize, and moreover the receiver requires complex optical heterodyne methods to detect the phase of the optical field.

In intensity modulation, the physical variable that is modulated is the optical power. Figure 1c shows that it is the envelope of the light power that contains the information. The optical field oscillations at 10^{14}–10^{16} Hz in this case are not related to the



Figure 1 Types of modulation of optical signals. (a) unmodulated optical field; (b) frequency-modulated field; (c) intensity or envelope modulation of the optical power.

modulation and demodulation process, and only the optical power variation is important. This is a key advantage, and as a result intensity modulation systems are prevalent for optical communications. Here, we discuss how varying the injected current in a semiconductor laser or light emitting diode, or by operating the source with constant output and introducing an external modulator, can realize modulation of the optical power of the source. The process by which the optical power variations can be detected at the receiver with semiconductor photodiodes are also discussed, including detection noise characteristics and means of enhancing the responsivity by introducing internal gain mechanisms or wavelength selectivity. The speed capabilities of optical modulation and demodulation in semiconductor lasers and photodetectors are discussed, based on the rate equations for carrier and photon dynamics.

The Modulation of Semiconductor Lasers

Townes, Basov and Prokhorov, who shared the Nobel Prize in 1964, developed the principle of lasers. Semiconductor lasers emit light through a stimulated emission mechanism. The required optical gain for the lasing action is obtained by injecting a forward bias current into a heavily doped p-n junction, thereby injecting carriers into the active junction layer and creating a population inversion. Here we limit our discussion to the optical modulation characteristics of the laser in response to changes in the injection current.



Figure 2 Light-current properties and the dynamic modulation characteristics of semiconductor lasers.

Figure 2 shows the typical light-current characteristics of semiconductor lasers. For drive currents above the threshold value I_{th}, the emitted optical power is predominantly by stimulated emission and it increases linearly with the drive current up to moderate currents. The differential responsivity of the laser, defined by the ratio of optical power increase to electric current increase above threshold, is typically around 0.5 mW/mA. At high current levels, the light output deviates from a proportional dependence on the current because of saturation effects and the differential responsivity decreases.

The dynamic response of the semiconductor laser to modulation of the injection drive current is governed by the rate equations for the carrier density and the photon density in the active junction region. Figure 3 shows the active layer under consideration (*see* **Lasers:** Edge Emitters). The electron concentration in the active layer is denoted N and the photon concentration in the active layer is denoted S. The dynamic behavior of the electron concentration and photon density is governed by the following rate equations:

$$\frac{\partial N(x)}{\partial t} = \frac{I(x)}{qv_a} + D_n \frac{\partial^2 N(x)}{\partial x^2} - \frac{N(x)}{\tau_{ns}} - G(x)\cdot S(x) \qquad [1]$$



Figure 3 Semiconductor laser. (a) intrinsic device; (b) active region with injected current I, electron concentration N, and photon concentration S.

$$\frac{\partial S(x)}{\partial t} = \Gamma \cdot \beta \frac{N(x)}{\tau_{ns}} + \Gamma \cdot G(x) \cdot S(x) - \frac{S(x)}{\tau_p} \qquad [2]$$

where I is the injected current, q is the electronic charge, ν_a is the volume of the active layer, D_n is the diffusion constant, τ_{ns} is the carrier lifetime, Γ is the confinement factor (defined as the fraction of the optical power in the active region), β is the fraction of the spontaneous emission power coupled into the lasing mode, τ_p is the cavity or photon lifetime, and

$$G(x) = \gamma[N(x) - N_t] \qquad [3]$$

where G is the net rate of stimulated emission, and N_t is the electron concentration at transparency.

Equations [1] and [2] are statements of the fundamental continuity equations for electrons and photons in the active layer. Hence, eqn [1] expresses the fact that the rate of increase of electron concentration in the active layer is given by the rate of increase of electron concentration due to injected current, the rate of increase of electron concentration due to diffusion current, the rate of decrease of electron concentration due to spontaneous recombination, and the rate of decrease in electron concentration due to stimulated photon emission. Equation [2] expresses the fact that the rate of increase of photon density in the active layer is given by the rate of increase in photon density due to spontaneous emission coupled into the lasing mode, the rate of increase of photon density due to stimulated emission coupled into the active layer, and the rate of decrease of photon density due to cavity loss mechanisms.

The actual electron and photon distribution varies across the active layer. However, for simplicity, it is convenient to use average values of N and S, and the simplified rate equations in terms of position independent variables are given by:

$$\frac{\mathrm{d}N}{\mathrm{d}t} = \frac{I_i}{q\nu_a} - \frac{N}{\tau_{ns}} - G(1 - \varepsilon S)S \qquad [4]$$

$$\frac{\mathrm{d}S}{\mathrm{d}t} = \Gamma \cdot \beta \frac{N}{\tau_{ns}} + \Gamma \cdot G(1 - \varepsilon S)S - \frac{S}{\tau_p} \qquad [5]$$

where the scaling factor $(1 - \varepsilon S)$ accounts for gain saturation arising from several phenomena such as spatial hole burning, spectral hole burning, carrier heating and two-photon absorption, and ε is a nonlinear gain parameter.

The modulation response of the laser is obtained by solving the rate eqns [4] and [5] for a time dependent input current of the form

$$I(t) = I_b + I_m x(t) \qquad [6]$$

where I_b is the steady-state bias current, I_m is the modulation current amplitude and $x(t)$ represents the normalized shape of the modulation waveform.

The small-signal modulation bandwidth of the laser is obtained by considering the response to small amplitude sinusoidal current modulation at frequency ω, so that $x(t) = \sin(\omega t)$, around a steady-state bias current above lasing threshold. Under the small signal condition, the rate equations can be linearized and combined to result in a second order differential equation. The solution for the photon output exhibits a damped resonant type response. Hence the modulation response displays some peaking at the relaxation oscillation resonance frequency ω_r, and is flat for frequencies much lower than ω_r. The resonance frequency $\omega_r \propto \sqrt{S_o}$, where S_o is the photon density at the laser bias level, so the bandwidth can be increased by biasing the laser further above its threshold current. Semiconductor laser bandwidth to 30 GHz has been observed; however, it is often limited to around 10 GHz due to electrical parasitics in the current drive circuit and interface.

The large-signal modulation response of the laser is obtained by solving the differential eqns [4] and [5]. The response of the carrier-photon coupled system to a step change of drive current has the potential for damped oscillation. This is caused by a resonant type of behavior in which, for example, an increase in photon density causes a depletion in population inversion which leads to a decrease in photon density enabling the carrier density to recover, thus producing a time lag between cause and effect resulting in damped oscillations before settling to the steady state value. These dynamic characteristics are illustrated in Figure 2. For a step modulation of the laser drive current, the optical output response exhibits a delay time, a risetime, an overshoot, and damped oscillations. The risetime of the laser output is typically in the range of 100–300 ps. The turn-on time of the laser and the overshoot are improved by ensuring that the minimum drive current does not fall below threshold. The damped oscillations in the optical output occur at the relaxation oscillation frequency of the laser.

These laser pulse waveform imperfections cause deteriorations in the eye diagram of the laser transmitter that is modulated by very high speed digital bit streams (*see* **Optical Communication Systems:** Lightwave Transmitters). Figure 4 shows the eye diagram for the optical output of a semiconductor laser directly modulated by a 5 Gbit/s pseudo-random bit stream of length $2^{15}-1$. The output waveform imperfections cause a partial closure of the eye, which ultimately limits the modulation speed that can be obtained by directly modulating the laser drive current. Although the semiconductor laser optical output does not exactly replicate the applied electrical drive waveform, the deviations are small enough so that these lasers can be used for data transmission up to around 10 Gbit/s.

Another inherent consequence of direct modulation of semiconductor lasers is the production of laser frequency chirp. This arises from the fact that modulation induced changes in the carrier density in the active region of the laser cavity cause a change in the refractive index of the active layer, which results in a chirping in the output wavelength during modulation. Hence amplitude modulation of semiconductor lasers is fundamentally accompanied by phase modulation from the basic physical mechanism of carrier induced changes in the refractive index. The resulting transient changes in the output wavelength of the laser causes a chirping phenomenon as it is being modulated. The order of chirp magnitude is about 0.1–1 GHz/mA of drive current change. During digital pulse modulation, the laser wavelength shifts to the blue side near the leading edge and towards the red side near the trailing edge of the pulse. Chirp results in a broadening of the laser linewidth. This wavelength change effect in combination with the dispersion characteristics of optical fiber (*see* **Fiber and Guided Wave Optics:** Dispersion; Light Propagation) causes an important limitation to the transmission capacity of fiber optic communication systems. The chirp in semiconductor lasers can be reduced, but not entirely eliminated, by using modulation-doped strained multiquantum-well lasers, which reduce the linewidth enhancement factor.



Figure 4 Eye diagram for the optical output of a semiconductor laser directly modulated by a 5 Gbit/s pseudo-random bit stream.

The Modulation of Light Emitting Diodes

The light emitting diode (LED) generates light through spontaneous emission. A semiconductor p-n junction is pumped with a forward current, so that electrons are provided in the upper energy state that can recombine radiatively to produce incoherent light by a spontaneous emission mechanism. The rate of photon generation is directly proportional to the carrier injection rate, and hence the modulating drive current.

Figure 5 shows the typical light-current properties and the modulation characteristics of a LED. The responsivity of the LED, defined as the ratio of the emitted optical power to the injected current, is typically in the range of 10 to 50 μW/mA. The optical output power generated is linearly related to the injection (drive) current up to moderate currents, and is given by

$$P = \eta \cdot h\nu \cdot \frac{I}{q} \qquad [7]$$

where η is the emission quantum efficiency (defined as the ratio of the radiative recombination rate to the total recombination rate), h is Planck's constant, ν is the optical frequency, I is the injected current, and q is the electronic charge. For larger currents, the light output deviates from a proportional dependence on the current because of saturation effects and the responsivity decreases.

The modulation response of the LED is governed by the rate equation for the carrier density N

$$\frac{\mathrm{d}N}{\mathrm{d}t} = \frac{I}{qv_a} - \frac{N}{\tau_c} \qquad [8]$$



Figure 5 Light-current properties and the modulation characteristics of light emitting diodes.

where I is the injected current, q is the electronic charge, ν_a is the volume of the active region, and τ_c is the carrier lifetime. Equation [8] expresses the fact that the rate of increase of carrier concentration is given by the rate of increase of carriers through current injection and the rate of carrier loss through radiative and nonradiative recombination. The small signal response arising from this first order differential equation, exhibits a simple single pole response and the resulting modulation bandwidth of the LED is given by

$$B = 1/(2\pi\tau_c) \qquad [9]$$

The pulse modulation response of the LED is shown in Figure 5. The output modulated optical waveform is not square but exhibits risetimes and falltimes determined by the carrier lifetime τ_c. This sets a limit to the maximum modulation rate that the LED can achieve. The bandwidth can be increased by decreasing the radiative lifetime, which can be controlled to a limited extent by the choice of doping level. Typical lifetimes for InGaAsP LEDs are in the range of 1–5 ns, which corresponds to attainable modulation data rates of several hundred Mbit/s.

The External Modulation of Lasers

Modulation of lasers realized by changing the injection current, as described above, is classed as direct modulation. This is the simplest method of modulation; however, it is limited by several physical phenomena. These include bandwidth limitations due to carrier dynamics in the laser active region, waveform limitations due to relaxation oscillations and overshoot effects, and chirping which causes transmission limitations in optical fibers arising from dispersion effects.

A superior modulation technique, classed as external modulation, operates the laser with continuous wave (CW) output and impresses the modulation by means of a device external to the laser. Although more complex, this approach has many modulation performance advantages. Because the laser is operated CW, this technique removes chirping effects and also enables higher power lasers to be used. Moreover, it is capable of much higher modulation bandwidths, larger on–off extinction ratios, and superior modulation spectral purity.

Electro-optic Modulation of Light

The linear electro-optic effect in materials was first described by Friedrich Pockels in 1893. The Pockels effect is the change in refractive index of the material resulting from the application of an electric field, and is given by

$$n(E) = n - \frac{1}{2} r n^3 E \qquad [10]$$

where n is the refractive index, E is the applied electric field, and r is the electro-optic coefficient. Typical values of r lie in the range 10^{-12} to 10^{-10} m/V, and the most common electro-optic materials used include $LiNbO_3$, GaAs, InP, InGaAsP, and synthetic polymers such as polymethylmethacrylate (*see* **Modulators:** Electro-optics).

If light traverses an optical waveguide of length L, to which an electric field E is applied, it undergoes a phase shift given by

$$\Delta\phi = -\frac{\pi r n^3 E L}{\lambda} \qquad [11]$$

The electric field can be produced by applying a voltage V across the waveguide of width d, hence $E = V/d$. It is therefore possible to modulate the phase of the light by varying the voltage V that is applied to the material through which the light passes. The voltage required to produce a phase shift of π is given by

$$V_\pi = \frac{\lambda d}{n^3 r L} \qquad [12]$$

The parameter V_π, known as the half-wave voltage, is an important characteristic that expresses the applied voltage required to give a phase shift of π.

Intensity modulation of light can be obtained by placing the phase modulator in one arm of an optical interferometer. The structure, known as a Mach-Zehnder modulator, is shown in Figure 6a. The optical output is the phasor sum of two lightwaves that travel through the two arms, resulting in constructive or destructive interference depending on the optical phase difference. The electric field is applied to the optical waveguide in a direction perpendicular to the direction of light propagation using the metal electrodes, see Figure 6a. Hence the refractive index of the waveguide and thus the phase of the light can be modulated by varying the voltage V. When no voltage is applied, the optical fields in the two arms of the interferometer experience identical phase shifts, and hence interfere constructively at the output. When a voltage is applied, the waveguide index changes, and the light in that arm experiences a phase shift with respect to the light in the other arm. This destroys the constructive nature of the interference at the output, and reduces the transmitted light emitted at the output. The extreme case is when the phase difference between the two arms equals π, which causes complete destructive interference resulting in no light transmission.



Figure 6 Mach-Zehnder electro-optic intensity modulator. (a) Structure; (b) transfer function and modulation characteristics.

The modulation transfer function is given by

$$P_{\text{out}} = \frac{1}{2} P_{\text{in}}[1 + \cos(\Delta\phi)] \qquad [13]$$

where $\Delta\phi$ is the phase difference encountered by light as it travels through the two arms. In terms of the applied voltage, the optical power transmitted through the modulator is given by

$$P_{\text{out}} = \frac{1}{2} P_{\text{in}}\left[1 + \cos\left(\pi \frac{V}{V_\pi}\right)\right] \qquad [14]$$

This transfer characteristic is shown in Figure 6b. The modulator may be operated as an analog optical modulator by operating in the nearly linear region around point Q. Alternately, it may be operated as a digital modulator by operating between points A and B, thus switching the light on and off as V is switched between 0 and V_π.

Improved efficiency of modulation, and hence a reduction in the value of V_π (typically a few volts) can be obtained by placing a second electrode on the other arm of the interferometer, and using a push-pull configuration to drive the interferometer. Hence the phase modulators in both arms are driven with modulating voltages of opposite polarities so the phase is advanced in one arm and is retarded in the other arm. This produces a net phase difference, which is double that produced in either arm.

The Pockels effect is an extremely fast physical mechanism, hence in principle external modulation is capable of achieving extremely high speeds. In practice, the modulation speed of an electro-optic modulator is limited by the capacitive effects at the electrodes and by the transit time of the light through the material. If the electric field varies significantly within the time it takes for light to transit through the waveguide, then the travelling optical wave will be subjected to different electric fields as it traverses the waveguide, and this results in a transit time limitation to the modulation bandwidth. A technique to avoid this limitation is to apply the voltage at one end of the waveguide and to design the electrodes to form a transmission line. By this means it is possible to make the velocity of the electrical wave match that of the optical wave to essentially eliminate the transit time effects. These external modulators have demonstrated speeds well in excess of 100 GHz.

Electro-absorption Modulation of Light

Electro-absorption external modulators are based on the principle of semiconductor bandgap decrease that occurs upon application of an electric field (the Franz-Keldysh and Stark effect). With no applied voltage, the semiconductor waveguide is transparent to light having a photon energy smaller than the bandgap, and such wavelengths are transmitted with very little attenuation. When a voltage is applied, the bandgap of the semiconductor decreases and the material absorbs the light once the photon energy exceeds the bandgap energy, and this produces optical attenuation. Hence by applying a modulation voltage to the semiconductor waveguide, the absorption property of the waveguide and hence the output light intensity can be modulated.

Improved modulation efficiency, and hence a reduction in the voltage required to decrease the bandgap energy, is obtained by using multiquantum-well semiconductor structures, which exhibit enhanced electro-absorption effects arising from the quantum confined Stark effect. The conventional technique of applying a transverse field across a multiquantum-well is to apply a reverse voltage across it. Modulator drive voltages of a few volts can be obtained. The on/off extinction ratio of modulation depends on the value of the field-dependent absorption coefficient at the operating voltage, and typical on/off extinction ratios are 10–15 dB.

The modulation bandwidth is determined by intrinsic factors related to carrier dynamics, such as exciton formation and dissociation times and the time taken to remove electrons and holes from the wells by thermionic emission and tunelling. It is also determined by extrinsic factors related to the capacitance of the junction diode. These modulators can have bandwidths of around 50 GHz. They also enable low chirp modulation to be obtained. The optical power handling capability of electro-absorption modulators is lower than for electro-optic modulators. However, a principal advantage of the electro-absorption modulator is that the semiconductor waveguide can be fabricated onto one substrate with the semiconductor laser, enabling the realization of monolithic integration on the same chip.

The Demodulation of Optical Signals

The process of demodulation converts the modulated intensity of an optical wave into an electrical signal to recover the information content. Semiconductor photodetectors are based on the principle of absorption of photons to generate mobile electron-hole pairs, and the transport of these mobile carriers via an applied electric field to create a flow of current.

Demodulation using PIN Photodiodes

The PIN photodiode comprises a P-doped/intrinsic/N-doped semiconductor structure. An applied reverse voltage bias creates a depletion region with a high electric field in the intrinsic layer. When the intrinsic layer is illuminated with light, photons are absorbed and electron-hole pairs are created, which are swept by the built-in electric field. The resulting flow of current is proportional to the incident optical power.

The quantum efficiency of the photodetector is defined as the ratio of electron generation rate to the photon incidence rate, and is given by

$$\eta = \frac{h\nu}{q} \cdot \frac{I_p}{P} \qquad [15]$$

where I_p is the photocurrent, P is the incident optical power, ν is the optical frequency, h is Planck's constant and q is the electron charge. If the width of the absorbing intrinsic region is large enough to capture all the light, quantum efficiency values approaching 100% can be achieved.

The current-voltage characteristics of the photodiode under optical illumination are shown in Figure 7a. The dark current I_d, which is the current generated in the photodetector in the absence of light originates from thermally generated electron-hole pairs, and is typically extremely small (<5 nA). Figure 7b shows the transfer characteristic of the



Figure 7 Semiconductor photodiode. (a) Current-light characteristics under optical illumination; (b) transfer function and demodulation photocurrent versus incident optical power.

photodetector. The current is linearly proportional to the optical power up to moderate power levels, when saturation mechanisms occur. The responsivity of the photodiode $\Re$, defined as the ratio of the generated electric current to the incident optical power, is given by

$$\Re = \frac{\eta q}{h\nu} \qquad [16]$$

The responsivity is an important parameter, and provides a measure of the photodetection efficiency of the device for demodulating optical signals. Typical responsivity values for PIN photodiodes are around 1 A/W.

The bandwidth B of demodulation of the photodetector is determined by the speed with which it responds to variations in the incident optical power. This is limited by the transit time τ_{tr} and the RC time constant τ_{RC} and is given by

$$B = \frac{2\pi}{\tau_{tr} + \tau_{\mathrm{RC}}} \qquad [17]$$

The transit time limitation arises because of the time it takes for the generated carriers to traverse the absorption region and be collected. To maximize the bandwidth, the transit time needs to be reduced, which can be achieved by decreasing the width of the absorption region. However, this requires a trade-off with the responsivity, which drops because a smaller fraction of the light can be absorbed under these conditions. The capacitance C and the resistance R of the photodetector and its circuitry form the RC time constant. To maximize the bandwidth, the photodiode capacitance needs to be reduced by decreasing the area of the photodiode. The demodulation bandwidth of PIN photodiodes can exceed 100 GHz.

Photodetection shot noise is a fundamental noise mechanism that introduces noise in the demodulation process of optical signals. This leads to fluctuations in the photocurrent, even for a constant incident optical power, because the photocurrent actually consists of a stream of electrons that are generated at random times. The photodiode current generated by a constant incident optical power is given by

$$I(t) = I_{\mathrm{avg}} + i_{\mathrm{shot}}(t) \qquad [18]$$

where I_{avg} is the average photocurrent generated, and $i_{\mathrm{shot}}(t)$ is the current fluctuation due to shot noise and which is described by a stationary random process with Poisson statistics. The mean-square noise current is given by

$$< i^2_{\mathrm{shot}}(t) >= 2qI_{\mathrm{avg}}\Delta f \qquad [19]$$

where Δf is the effective noise bandwidth of the receiver. The shot noise degrades the signal to noise ratio of the demodulated signal, and causes a fundamental limit to the sensitivity of the PIN photodetection.

Demodulation using Avalanche Photodiodes

Demodulation using avalanche photodiodes detectors (APD) has the advantage of significantly increased responsivity. This is achieved by providing an internal current gain mechanism within the device. The APD operates by generating more than one electron-hole pair per absorbed photon. This is achieved by strongly reverse biasing the diode to create a large junction electric field, so photoelectrons accelerate and acquire enough energy to produce new carriers by the process of impact ionization. These devices incorporate a modification to the PIN structure, by including an additional doped layer known as the multiplication layer, which under reverse bias provides a region of very high electric field that can produce avalanche breakdown. Hence a single primary electron generated through absorption of a photon, generates many secondary electrons and holes in the avalanche multiplication layer, and all these secondary carriers contribute to the photocurrent. As a result of this current gain mechanism, the responsivity of the APD is increased by a multiplication factor M, and is given by

$$\Re_{ADP} = \frac{M\eta q}{h\nu} \qquad [20]$$

where M can range between 5–50 depending on the bias voltage.

The bandwidth of the APD depends on the multiplication factor M. This is because the avalanche process takes additional time. The frequency response can be written

$$M(\omega) = \frac{M_0}{[1 + (\omega\tau_e M_0)^2]^{\frac{1}{2}}} \qquad [21]$$

where M_0 is the low frequency gain and τ_e is the effective transit time that depends on the ionization coefficient. The intrinsic APD bandwidth (assuming no RC limitations) is approximately given by

$$B_{\mathrm{APD}} = \frac{1}{2\pi\tau_e M_0} \qquad [22]$$

Hence the bandwidth decreases as the multiplication factor increases, and there exists a trade-off between the bandwidth and the responsivity. The demodulation characteristics of the avalanche photodiode can be expressed by means of a gain-bandwidth product $B_{\mathrm{APD}} \cdot M_0$, and this can exceed 150 GHz.

Photodetection noise in APDs has an additional contribution because the avalanche gain itself is a random variable. Hence the secondary electron-hole pairs are generated at random times and this adds a noise component to the basic shot noise associated with the generation of primary electro-hole pairs. The total shot noise is given by

$$< i^2_{\mathrm{shot,APD}}(t) >= 2qM^2F(M)I_{\mathrm{avg}}\Delta f \qquad [23]$$

where $I_{\mathrm{avg}} = \Re P$, and F is the excess noise factor expressed by

$$F = \frac{< M^2 >}{< M >^2} \qquad [24]$$

and is approximately given by $F \approx M^x$, where $0.2 < x < 1$. Hence the excess noise increases with the multiplication ratio, so there exists an optimum avalanche photodiode gain that maximizes the signal to noise ratio of the demodulated signal. Despite the fact that additional noise is introduced, because of the higher responsivity, APDs can provide higher sensitivity in demodulating optical signals than PIN photodiodes.

Demodulation using Metal-Semiconductor-Metal (MSM) Photodiodes

Demodulation using MSM photodiodes enables extremely high bandwidths to be achieved. The MSM photodiode comprises two reverse-biased metal-to-semiconductor Schottky contacts formed on a semiconductor layer that prevents flow of electrons from metal to semiconductor. Photons incident between the contacts create electron-hole pairs that are collected by the electric field to generate a photocurrent proportional to the incident optical power. The metal contacts are usually fabricated on the same side of the semiconductor to create a planar structure, which is suitable for monolithic integration. However, a drawback of the MSM device is that the electrodes block some of the light from reaching the absorption region, which results in a reduced responsivity.

The bandwidth of demodulation of the MSM photodiode is determined by the transit time of the photogenerated carriers and the RC time constant. Since the electrode spacing can be around 1 μm, the transit time is extremely small. Moreover, since in the planar structure the parasitic capacitance is inherently low, the RC time constant is also extremely small. This results in demodulation bandwidths of up to 300 GHz.

Wavelength Selective Demodulation

A technique to obtain both wavelength selective demodulation and high-speed, high-responsivity demodulation involves the use of microcavity resonant photodetectors. This is useful for very high-speed detection in wavelength multiplexed systems.

The microcavity photodiode comprises a Fabry-Perot cavity placed around the photodetector absorption region, to enhance the responsivity. The mirrors are typically formed using Bragg reflectors or dielectric mirrors implemented in the semiconductor. A resonance is built up in the cavity at the wavelengths of incoming light for which the round-trip phase shift is 2π, which corresponds to constructive interference. Hence at the resonant wavelength, the incoming light is reflected at the two mirrors and permits the absorbing layer to be reused many times by effectively recirculating the optical signal, thus enhancing the absorption and the responsivity. However, the transit length can remain extremely small, because the photogenerated carriers only have to traverse the thickness of the absorption region to be collected. This solves the problem of the fundamental responsivity-bandwidth trade-off in normal photodetectors, in which increasing the absorption layer width to increase responsivity increases the transit time thus reducing the bandwidth. Microcavity resonant photodiodes enable the simultaneous achievement of large bandwidth and high responsivity possible. Also, the resonant behavior leads to wavelength selectivity, which can be used to advantage in some wavelength division multiplexed WDM applications (*see* **Optical Communication Systems:** Wavelength Division Multiplexing). This approach can provide demodulation of optical signals with quantum efficiencies close to 100% and with bandwidths in excess of 100 GHz.

Optical Receivers – Preamplification and Clock Recovery

The front end of an optical receiver comprises the photodiode and a preamplifier to amplify the electrical signal for further processing. In order to obtain a high demodulation bandwidth, it is important to minimize the photodetector capacitance and to minimize the input resistance of the preamplifier that acts as the load resistance. However, because the thermal noise current is inversely proportional to the load resistance, minimizing the load resistance causes excessive noise and degraded demodulation sensitivity. An alternative approach is to use a high-impedance preamplifier. This reduces the noise at the price of a lower bandwidth. Thus there is a trade-off between the bandwidth and sensitivity. The trans-impedance front-end, in which the load resistor is connected as a feedback resistor around an inverting amplifier, is often used as an optimum compromise that combines high sensitivity together with large bandwidth. This enables the use of a large resistance, which minimizes noise, but at the same time the effect of negative feedback reduces the input impedance by a factor equal to the amplifier gain, thus increasing the bandwidth.

In digital optical transmission systems the data recovery section of the optical receiver comprises a clock recovery circuit and a decision circuit. Accurate timing (clock) information about the bit slot, in order to synchronize the decision process, is obtained from the amplified front-end waveform using a timing extraction circuit (*see* **All-Optical Signal Regeneration**). Typical clock recovery circuits comprise a high-Q resonant circuit which rings at the bit rate frequency or a phase locked loop. This enables precise data time sampling in the following decision circuit within the bit intervals of the original pulse train.

See also

All-Optical Signal Regeneration. **Fiber and Guided Wave Optics:** Dispersion; Light Propagation. **Lasers:** Edge Emitters. **Modulators:** Electro-Optics. **Optical Communication Systems:** Basic Concepts; Lightwave Transmitters; Wavelength Division Multiplexing.

Further Reading

Agrawal GP (1997) *Fiber-Optic Communication Systems*. New York: Wiley.

Coldren L and Corzine S (1995) *Diode Lasers and Photonic Integrated Circuits*. New York: Wiley.

Gowar J (1993) *Optical Communication Systems*. Englewood Cliffs: Prentice Hall.

Kazovsky L, Bendetto S and Willner AE (1996) *Optical Fiber Communication Systems*. Boston: Artech House.

Keiser GE (1991) *Optical Fiber Communications*. New York: McGraw-Hill.

Miller SE and Kaminow I (eds) (1988) *Optical Fiber Telecommunications II*. New York: Academic Press.

Personick SD (1985) *Fiber Optics: Technology and Applications*. New York: Plenum Press.

Petermann K (1991) *Laser Diode Modulation and Noise*. Boston: Kluwer Academic.

Saleh BEA and Teich MC (1991) *Fundamentals of Photonics*. New York: Wiley.

Senior J (1992) *Optical Fiber Communications*. NJ: Prentice Hall.

Siegman AE (1986) *Lasers*. Sausalito, CA: University Science Books.

NONCLASSICAL LIGHT

H Walther, University of Munich and
Max-Planck-Institute for Quantum Optics,
Garching, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The pioneering experiments by Hanbury-Brown and Twiss, and the subsequent development of the quantum theory of electromagnetic radiation by Glauber and Sudarshan, raised the interest in the question of photon statistics. It followed from their theories that states of the electromagnetic field which can only exist in a quantum treatment. These nonclassical states show up in photon statistics through the phenomenon of antibunching. Later, further nonclassical states of the radiation field were found in the so-called squeezed fields, which are fields with phase-sensitive quantum fluctuations being at certain phase angles smaller than those of a perfect classical coherent field. In order to achieve squeezing of laser radiation, various forms of nonlinear optical interactions can be used.

Classical Versus Quantum Waves

In classical electrodynamics, a monochromatic wave (e.g., an extended light beam) is often described using the complex representation:

$$\begin{aligned} E(r,t) &= E^{-}(r,t) + E^{+}(r,t) \\ &= \frac{1}{2}[\varepsilon(r,t)\mathrm{e}^{-\mathrm{i}\omega t} + \varepsilon^{*}(r,t)\mathrm{e}^{\mathrm{i}\omega t}] \end{aligned} \qquad [1]$$

In classical theory, this complex description is merely a tool for the simplification of some calculations. However, there is some physical significance when using the quantum description, where ε and ε^* lead to the lowering and raising operators of the field. The above field can also be represented in the following way:

$$E(r,t) = \frac{\varepsilon + \varepsilon^*}{2}\cos\omega t + \frac{\varepsilon - \varepsilon^*}{2}\sin\omega t \qquad [2]$$

with real coefficients $\varepsilon_1 = (\varepsilon + \varepsilon^*)/2$ and $\varepsilon_2 = (\varepsilon - \varepsilon^*)/2\mathrm{i}$. This description gives the state of the field in a two-dimensional phase diagram where the sin-component is plotted versus the cos-component. In this plot, the wave above is represented by one point giving phase and amplitude of the field. These phase diagrams will play an important role in characterizing the nonclassical fields in a quantum phase diagram, as discussed below.

The properties of a field are described by the first- and second-order correlation functions. The first-order correlation function is given by

$$G^{(1)}(r_1, t_1, r_2, t_2) = \langle \varepsilon^*(r_1, t_1)\varepsilon(r_2, t_2)\rangle \qquad [3]$$

It is obtained by multiplying the electric field amplitudes at two spacetime points and taking the ensemble average. For $r_1 = r_2$ and $t_1 = t_2$, $G^{(1)}$ is proportional to the intensity at this point and is, therefore, called the first-order in intensity. The first-order correlation function is connected to the spectrum $I(\omega)$ of the field through its Fourier transform.

The second-order correlation function is necessary to characterize the radiation field completely. It describes the intensity fluctuations, being the classical equivalent to photon statistics, and is given in the general form:

$$\begin{aligned} &G^{(2)}(r_1, t_1, r_2, t_2, r_3, t_3, r_4, t_4) \\ &\quad = \langle \varepsilon^*(r_1, t_1)\varepsilon^*(r_2, t_2)\varepsilon(r_3, t_3)\varepsilon(r_4, t_4)\rangle \end{aligned} \qquad [4]$$

If $G^{(2)}$ is considered for two spacetime points $r_1 = r_2$, the connection to intensity fluctuations becomes obvious:

$$G_{\mathrm{I}}^{(2)}(\tau) = 4\langle I(t_1)I(t_2)\rangle = \langle \varepsilon^*(t_1)\varepsilon(t_1)\varepsilon^*(t_2)\varepsilon(t_2)\rangle \qquad [5]$$

The subscript I indicates that we have to deal with intensity correlations; τ stands for $t_2 - t_1$.

In connection with the Hanbury-Brown, Twiss experiment, in general, the normalized intensity correlation is given by

$$g_{\mathrm{I}}^{(2)}(\tau) = \langle I(t)I(t+\tau)\rangle / \langle I(t)\rangle^2 \qquad [6]$$

$I(t)$ stands for the intensity which is given by the mean value $\langle I(t)\rangle$ plus fluctuations $\Delta I(t)$ for which the mean value is zero. The mean value of the squared intensity is then $\langle I^2\rangle = \langle I\rangle^2 + \langle \Delta I^2\rangle$. It follows for the normalized intensity correlation function:

$$\begin{aligned} g_{\mathrm{I}}^{(2)}(\tau) &= \langle I(t)I(t+\tau)\rangle / \langle I(t)\rangle^2 \\ &= \left\{ \begin{array}{ll} 1 + \langle \Delta I^2\rangle / \langle I\rangle^2 & \text{for } \tau = 0 \\ 1 & \text{for } \tau \to \infty \end{array} \right\} \end{aligned} \qquad [7]$$

For $\tau \to \infty$, the intensities are not correlated and $g_{\mathrm{I}}^{(2)}(\tau)$ becomes 1. Otherwise $\langle \Delta I^2\rangle / \langle I\rangle^2 \geq 0$; this means that $g_{\mathrm{I}}^{(2)}(\tau)$ is always equal to or larger than 1, and $g_{\mathrm{I}}^{(2)}(\tau)$ smaller than 1 is not possible classically. The photon correlation is usually measured by the classical Hanbury-Brown, Twiss setup shown in Figure 1.

The maximum of $g_{\mathrm{I}}^{(2)}(\tau)$ at $\tau = 0$ is called intensity bunching and was first observed by Hanbury-Brown and Twiss. The decrease of $g_{\mathrm{I}}^{(2)}(\tau)$ as a function of τ is a measure of the coherence length of the light source.

When the experiment in Figure 1 is considered in the photon picture there is a principal difference compared to the classical intensity. In the classical case, the intensity on the two detectors is the same if the beamsplitter is dividing the light beam in equal portions. Both detectors, therefore, measure the same fluctuations. In the quantum picture, however, a photon can only be detected in one of the two detectors; this leads to the result that values for $g_{\mathrm{I}}^{(2)}(\tau)$ smaller than 1 can be found. The effect of photon bunching was initially thought to be an inherent property of light owing to the boson nature of photons. Therefore, it came as a big surprise when Glauber showed theoretically that for the quantized radiation field $g_{\mathrm{I}}^{(2)}(\tau)$, <1 is possible. This effect, known as photon antibunching, and its experimental observation constitutes an unambiguous proof of the quantum nature of light.

In the quantum description of the electromagnetic field, the electric field amplitudes ε and ε^* are replaced by $\hat{a}$ and $\hat{a}^+$, the photon annihilation and creation operators.

In this case, the electric field operator is written as

$$\hat{E} \propto \frac{\hat{a} + \hat{a}^+}{2} \cos\omega t \frac{\hat{a} - \hat{a}^+}{2\mathrm{i}} \sin\omega t \qquad [8]$$

In analogy, the operators $\hat{a}_1 = (\hat{a} + \hat{a}^+)/2$ and $\hat{a}_2 = (\hat{a} - \hat{a}^+)/2\mathrm{i}$, can be defined describing the amplitude of the cosine and sine parts of the wave. $\hat{a}_1$ and $\hat{a}_2$ do not commute $[\hat{a}_1, \hat{a}_2] = (\mathrm{i}/2)1$, therefore, the expectation values of the two operators $\hat{a}_1$ and $\hat{a}_2$ underlie an uncertainty relation given by

$$\langle \Delta\hat{a}_1^2\rangle = \langle \hat{a}_2^2\rangle - \langle \Delta\hat{a}_i\rangle^2 \geq 1/16 \qquad [9]$$

with $\langle \Delta\hat{a}_i^2\rangle = \langle \hat{a}_i^2\rangle - \langle \Delta\hat{a}_i\rangle^2$. In the corresponding phase diagram, the expectation values for $\hat{a}_1$ and $\hat{a}_2$ are represented by a shaded area defined by the uncertainty (Figure 2). The state of the radiation field, where both phase and amplitude fluctuations are symmetrically minimized, $\langle \Delta\hat{a}_1^2\rangle = \langle \Delta\hat{a}_2^2\rangle = \frac{1}{4}$, best approximates the classical wave with well-defined phase and amplitude. The state with symmetrical minimum uncertainty is the coherent state describing laser radiation. It is an eigenstate of $\hat{a}$ with a photon number fluctuation given by a Poissonian distribution with $\langle \Delta n^2\rangle = \langle n\rangle$.

There are other minimum uncertainty states, however, with unsymmetrical uncertainty regions



Figure 1 Experimental setup for the Hanbury-Brown, Twiss experiment.



Figure 2 Phase diagram of the quantum mechanical field amplitudes $\langle \hat{a}_1\rangle$ and $\langle \hat{a}_2\rangle$ for coherent radiation.

with the uncertainty squeezed into mainly one component. These states, which are called squeezed states, are defined by $\langle \Delta \hat{a}_1^2 \rangle < 0.25$ or $\langle \Delta \hat{a}_2 \rangle < 0.25$. Squeezed state may also refer to a state which is not a minimum uncertainty state but where, nevertheless, the mean square fluctuation in one of the two components is less than 0.25.

A classical electromagnetic field consists of waves with well-defined amplitude and phase. This is not the case in a quantum treatment: fluctuations are associated with both conjugate variables. The case of a coherent state that most nearly describes a classical electromagnetic field has an equal amount of uncertainty in the two variables (when normalized to the field of a single photon). Equivalently, the field can be described in two conjugate quadrature components and the uncertainties in the two conjugate variables satisfy an uncertainty relation. The coherent state represents a minimum uncertainty state with equal uncertainties in the two quadrature components. This case is usually called the shot-noise limit; it is represented in Figure 2 as a phase diagram.

In a quantum treatment of radiation, it is also possible to generate states that are not present in the classical limit. They can show fluctuations reduced below the classical limit in one of the quadrature components, while the canonically conjugate quadrature component must display enhanced fluctuations in order to fulfill the uncertainty relation. Those states are called 'squeezed states.' An electromagnetic field with fluctuations below the standard quantum limit in one of the quadrature components has, in principle, many attractive applications, for example, in optical communication, in precision and sensitive measurements such as gravitational wave detection, or in noise-free amplification. Therefore, there has been great interest in generating squeezed radiation. Optical measurements have three characteristics that enable them to reach the quantum noise level more readily than in other fields of physics: (i) optical signals are naturally immune to external sources of noise; (ii) thermal noise at room temperature is negligible in the optical domain; and (iii) the outstanding equalities of the optical sources and detectors allow a very-low-level instrumental noise.

Squeezed states with reduced photon number fluctuations (sub-Poissonian photon statistics) correspond to a light beam in which the photons arrive more equally spaced than in a coherent beam for which $g_{\mathrm{I}}^{(2)}(0) = 1$. Therefore, sub-Poissonian number fluctuations correspond to photon antibunching. This shows that photon antibunching and squeezing are related. The state with the largest possible antibunching is the number state, represented by a circle in the phase diagram. It has large fluctuations in both components a_1 and a_2 and, therefore, is not a squeezed state. Thus, it is obvious that antibunching does not imply squeezing. On the other hand, weak squeezing of a coherent state may result in antibunching. If the state is squeezed harder the a_1 component will be better defined. The amplitude fluctuations, however, will start increasing and there will be a transition from antibunching to bunching.

The quantum calculation of the normalized second-order correlation function leads to the following result:

$$g_{\mathrm{I}}^{(2)}(0) = 1 + (\langle \Delta n^2 \rangle - \langle n \rangle / \langle n \rangle^2) \qquad [10]$$

A pure number state of the radiation field with $\langle \Delta n^2 \rangle = 0$, leads to $g_{\mathrm{I}}^{(2)}(0) < 1$, as discussed above. For a coherent state, $\langle \Delta n^2 \rangle = \langle n \rangle$ yielding $g_{\mathrm{I}}^{(2)}(0) = 1$, corresponding to the classical calculations.

It can be concluded that although antibunching and squeezing are related and nonclassical phenomena, one does not imply the other. Thus, the detection schemes necessary to determine the existence of one or the other are quite different. Antibunching or sub-Poissonian statistics can be detected via intensity correlations. Squeezing, on the other hand, is a property of either $\langle a_1 \rangle$ or $\langle a_2 \rangle$, and phase sensitive homo- or heterodyne detection is needed.

Nonclassical states of the radiation field are very sensitive to linear attenuation. Coherent and thermal light fields are the only ones that do not change their photon statistics when attenuated. This is different for nonclassical light. The change depends on the particular case and has to be carefully evaluated.

The first observation of squeezing was achieved in 1985, in an experiment of parametric generation involving four-wave mixing in sodium vapor.

Nonclassical Light from a Single Atom

Resonance fluorescence of atoms is a basic process in radiation–atom interactions, and has therefore always generated considerable interest. The methods of experimental investigation have changed continuously due to the availability of new experimental tools. A considerable step forward occurred when tunable and narrowband dye laser radiation became available. These laser sources are sufficiently intense to easily saturate an atomic transition. In addition, the lasers provide highly monochromatic light with coherence times much longer than typical natural lifetimes of excited atomic states. Excitation spectra with laser light using well-collimated atomic beams lead to a width, being practically the natural width of the resonance transition, therefore it became possible to investigate the frequency spectrum of the fluorescence radiation with high resolution and to also study the photon statistics of the fluorescent light.

Previous experiments to investigate antibunching in resonance fluorescence have been performed by means of laser-excited collimated atomic beams. The initial results obtained in 1977 showed for the second-order correlation function $g^{(2)}(t)$, a positive slope characteristic of photon antibunching, but $g^2(0)$ was larger than $g^2(t)$ for $t \rightarrow \infty$. This was due to number fluctuations in the atomic beam and to the finite interaction time of the atoms. In 1978, the analysis of the experiment was refined and in 1982, another experiment with a longer interaction time was performed. In the latter experiment, the photon correlation was also measured for very low laser intensities. The ideal experiment to study the photon statistics in resonance fluorescence is the investigation of a trapped ion since, in such an experiment, the fluctuations of the atomic number are excluded.

The fluorescence of a single ion should also display the following property. The probability distribution of the photon number recorded in a finite time interval t is narrower than Poissonian, which means, that the variance is smaller than the mean value of the photon number. This is because the single ion can only emit a single photon. Antibunching and sub-Poissonian statistics are often associated. They are, nevertheless, distinct properties and need not necessarily be simultaneously observed, as is the case in the experiment described here. Although there is evidence of antibunching in the atomic-beam experiments, the photon counts are not sub-Poissonian as a result of fluctuations in the number of atoms. In further experiments this effect was excluded by use of a special trigger scheme for the single-atom event. In the setup with a trapped ion these precautions are not necessary since there are no fluctuations in the atomic number. Figure 3 shows the photon correlation of a single trapped ion. The measurements are performed using the $3^2S_{1/2} - 3^2P_{3/2}$ transition of the $^{24}Mg^+$-ion at a wavelength of 280 nm. The laser is tuned slightly below resonance in order to Doppler-cool the secular motion of the ion.

The investigation of the photon correlation employed the ordinary Hanbury-Brown and Twiss setup with two photomultipliers and a beamsplitter (Figure 1). The time delay τ between the photomultiplier signals was converted by a time-to-amplitude converter into a voltage amplitude proportional to the time delay. A delay line of 100 ns in the stop channel allowed for the measurement of $g^{(2)}(\tau)$ for both positive and negative τ in order to check the symmetry of the measured signal. The output of the time-to-amplitude converter was accumulated by a multichannel analyzer in pulse height analyzing mode. Three typical measurements, each at small values of the laser intensity but with different detunings, are shown in Figure 3. The solid curve is a theoretical fit to the measurements. For small time delays (<20 ns), the nonclassical antibunching effect is observed, superimposed with Rabi oscillations being damped out with a time constant corresponding to the lifetime of the excited state.



Figure 3 Antibunching signals of a single $^{24}Mg^+$-ion for different laser intensities (decreasing from (a) to (c)). At larger intensities (a) and (b) the Rabi oscillations owing to a strong coherent coupling between ground and excited state are observed.

Recently it also became possible to combine a trapped ion with a cavity. In this way the emission of a photon in the cavity mode can be achieved. This leads to a directed emission of the photon being more efficient than the fluorescence occurring in the entire 4π geometry. In this way, a deterministic single photon source is obtained.

Survey on the Experiments on Squeezing

In order to produce squeezed light from nonlinear optical phenomena, a variety of methods has been used, depending on the type of nonlinearity and the number of interacting modes involved. The choice of optical nonlinearity reduces to either three-wave or four-wave mixing, leading to quadratic or cubic nonlinear response functions, respectively. Each of these methods has advantages and disadvantages. Three-wave mixing requires a pump field at twice the frequency of the field-mode being squeezed. However, it has the advantage as any sidebands induced on the pump, owing to phase noise, have a large frequency offset from the squeezed fields. The other method, the much simpler four-wave mixing, does not require any frequency-doubling step. This was, therefore, the first method used to obtain squeezing with quadrature noise below the vacuum level.

Most of the early experiments on squeezing were performed with one or two cavity modes with the squeezed modes being transferred to propagating external modes via beamsplitters for measurement. This narrowband procedure is followed in more recent experiments commonly used for three-wave (parametric) squeezing. Also squeezing in waveguides was achieved leading to a relatively simple and broadband implementation of squeezing, with, mostly a four-wave mixing with short pulses or solitons being performed.

The main limiting factors that remain include control over the driving laser phase and intensity noise, absorption in the dielectric material and associated devices, and phase fluctuations caused both by low-frequency technical noise in components, and by intrinsic material properties of phonon interactions and refractive index fluctuations. It appears not impossible to reach squeezing levels of 10 dB or more below shot noise, over bandwidths of up to 1 THz. At this level of noise reduction, the main problem is the issue of improving detector technology to allow such low noise levels to be investigated.

Squeezing in Lasers

The quantum noise properties of the laser were studied intensively after its invention in the early 1960s. The conclusion of these studies is that the laser output approaches quite closely the noise properties of a coherent state, provided the laser is operated well above threshold. That is, the spectral variance of the photon number and phase fluctuations at high enough Fourier frequencies will be at the Poissonian or quantum noise limit (also referred to as the shot noise level). On the other hand, the phase of the laser is unconstrained and drifts as a function of time, so-called laser phase diffusion. As a result, the phase fluctuations show excess noise at low frequencies.

In the early 1980s, it was realized that if the pumping mechanism for the laser could be made sub-Poissonian then amplitude squeezing could be obtained at low frequency. A few years later it was shown that sub-Poissonian pumping could be realized in semi-conductor lasers by regularizing the pump current. An experimental demonstration of amplitude squeezing from semi-conductor lasers was soon achieved. Although still requiring rather specialized lasers, many groups now routinely obtain squeezing from semi-conductor lasers.

There are a number of disadvantages to semi-conductor lasers, including their poor beam quality and short coherence length. As a result, interest in other possible squeezing mechanisms continues. It has been found that intrinsic dynamical effects can also lead to amplitude squeezing in the laser output.

Laser squeezing is of a different character to that produced by more ‘traditional squeezers.’ For example, in parametric amplification, the de-amplification of phase fluctuations is accompanied by an equal and opposite amplification of amplitude fluctuations which preserves the uncertainty relationship between them. However, in laser squeezing the reduction in amplitude fluctuations is not linked to any increase in phase fluctuations. Thus, in laser squeezing we take advantage of the fact that the laser output is not in a minimum uncertainty state to suppress amplitude noise. This means that laser squeezing is always amplitude or intensity squeezing.

Application of Nonclassical Light

The applications of nonclassical light are numerous. The single photon sources discussed above have their main applications in quantum communication with single photons where they may be used to establish secure signal transmission. There is also a decisive advance in the field of quantum information expected from the combination of local atomic quantum processing with photonic transmission of quantum states. Conceptually, new possibilities would arise to enhance quantum computational capabilities. For example, separate local quantum processors of moderate size could be linked in a quantum network, with quantum information being exchanged by means of photons.

Although a large number of phenomena have been predicted in which the quantum nature of the squeezed vacuum plays an essential role in modifying atomic properties, only the linear dependence of the two-photon absorption rate of a three-level ladder atom has been confirmed experimentally but classical sources show a quadratic dependence. In 1998 an important series of experiments was reported which investigated the interaction of a beam of Cs atoms with squeezed light in the Fabry–Perot cavity environment. The principal phenomena examined were the modification of the transmission spectrum of a weak, tunable probe beam due to the presence of the squeezed light, and the variation of the transmission modulation with the phase of the squeezed vacuum relative to that of an applied, saturating, coherent field.

There have been many proposed practical applications of squeezed light, and some experiments have already demonstrated its potential in precision measurements and improvement of spectroscopic sensitivity. Squeezed light may be used in optical communications to enhance signal-to-noise ratio, gravitational wave detection, and quantum nondemolition measurements.

The wider applications of squeezed light are numerous. An idea of the range and variety of applications is provided by the following selection: the protective measurement of a single squeezed harmonic oscillator state, coherent nonlinear spectroscopy using number squeezed light, the improvement of quantum nondemolition measurements using a squeezed meter input, sub-shot-noise Doppler anemometry with amplitude squeezed light, noiseless transfer of nonclassical light through bistable systems, generation of few photon states from squeezed atoms, and spin squeezing in a collection of atoms illuminated with squeezed light.

Einstein–Podolsky–Rosen (EPR) Correlations and Entanglement of Photons

In 1986, a quantum nondemolition experiment confirming the quantum correlation of the quadrature phase amplitudes of two spatially separated fields, was reported. In 1987, two-mode squeezing with two spatially separated detectors was experimentally demonstrated using parametric oscillation. With the experimental realization of such two-mode squeezing and quantum nondemolition measurements, the possibility of testing for continuous variable EPR-type correlations became apparent. In these proposals, the conjugate 'position' and 'momentum' observables would be the two orthogonal quadrature phase amplitudes of the field. The high efficiency of detectors used in the quadrature phase amplitude squeezing experiments was an important issue in this connection. Experimental tests of EPR correlations at the time were based on Bohm's version of the EPR paradox, and in fact, focused on Bell's extension of this work. These tests involved measurements performed on individual photon pairs, and used very inefficient detectors.

A specific proposal and a criterion to demonstrate the continuous variable EPR correlations for real experiments by way of a realization of the 1935 EPR paradox, was put forward in 1989. This proposal employed the two-mode squeezed state as the EPR source. The first experimental achievement, using the parametric oscillator, of the 1989 EPR criterion, for efficient measurements with continuous variable outcomes, was reported in 1992.

The EPR fields have proved significant in enabling the experimental realization of continuous variable quantum teleportation, and may have application also to quantum cryptography. Again, because of the efficient nature of the measurement of field quadrature phase amplitudes, and the intrinsic macroscopic nature of the correlated fields, continuous variable teleportation and cryptography may provide large advantages over protocols using a finite number state basis, where signals of individual photons are sent. At the moment, several groups are working in this promising direction.

Conclusions

In this contribution the generation of nonclassical light was reviewed. The generation of nonclassical light became possible after stable and reliable laser sources were available. There are many sources of nonclassical light available now. It is clear that we will see many new applications in the future. Especially in connection with optical communication, rather interesting improvements can be expected.

See also

Coherent Lightwave Systems. **Photonic Crystals:** Electromagnetic Theory. **Quantum Optics:** Atomic Coherence Effects.

Further Reading

Caves CM and Drummond PD (1994) Quantum limits on Bosonic communication rates. *Review of Modern Physics* 44: 481–537.

Cresser JD, Häger J, Leuchs G, Rateike FM and Walther H (1982) Resonance fluorescence of atoms in strong monochromatic laser fields. *Topics in Current Physics* 27: 21–59.

Dagenais M and Mandel L (1978) Investigation of two-time correlations in photon emissions from a single atom. *Physical Review A* 18: 2217–2228.

Diedrich F and Walther H (1987) Nonclassical radiation of a single stored ion. *Physical Review Letters* 58: 203–206.

Drummond PD and Ficek Z (eds) (2004) Springer Series on Atomic, Optical, and Plasma Physics, vol. 27. Berlin, Heidelberg, New York: Springer Verlag.

Gatti A, Lugiato LA and Wiedemann H (1997) In: Giacobino E, Reynaud S, and Zinn-Justin J (eds). *Quantum Fluctuations*, p. 431. Amsterdam: Elsevier.

Georgiades NP, Polzik ES, Edamatsu K, Kimble HJ and Parkins AS (1995) Nonclassical excitation for atoms in a squeezed vacuum. *Physical Review Letters* 75: 3426–3429.

Glauber R (1963) The quantum theory of optical coherence. *Physical Review* 130: 2529–2539.

Glauber R (1963) Coherent and incoherent states of the radiation field. *Physical Review* 130: 2766–2788.

Guthöhrlein GR, Keller M, Hayasaka K and Lange W (2001) A single ion as a nanoscopic probe of an optical field. *Nature* 414: 49–51.

Heidmann A, Horowicz RJ, Reynaud S, Giacobino E, Fabre C and Camy G (1987) Observation of quantum noise reduction on twin laser beams. *Physical Review Letters* 59: 2555–2557.

Höffges JT, Baldauf HW, Eichler T, Helmfrid SR and Walther H (1997) Heterodyne measurement of the fluorescent radiation of a single trapped ion. *Optical Communications* 133: 170–174.

Hood CJ, Kimble HJ, Turchette QA, Georgiades NPh and Parkins AS (1998) Squeezed excitation in cavity QED: experiment and theory. *Physical Review A* 58: 4056–4077.

Jakeman E, Pike ER, Pusey PN and Vaugham JM (1977) Effect of atomic number fluctuations on photon antibunching in resonance fluorescence. *Journal of Physics A: Mathematical and General* 10: L257–L259.

Kimble HJ, Dagenais M and Mandel L (1977) Photon antibunching in resonance fluorescence. *Physical Review Letters* 39: 691–695.

Kimble HJ, Dagenais M and Mandel L (1978) Multiatom and transit-time effects on photon-correlation measurements in resonance fluorescence. *Physical Review A* 18: 201–207.

Kimble HJ, Carnal O, Hu Z, Mabuchi H, Polzik ES, Thompson RJ and Turchette QA (1995) *Annals of the New York Academy of Sciences* 755: 87.

Levenson MD, Shelby RM, Reid MD and Walls DF (1986) Quantum nondemolition detection of optical quadrature amplitudes. *Physical Review Letters* 57: 2473–2476.

Loudon R (2000) *The Quantum Theory of Light*, 3rd edn. Oxford, New York: Oxford University Press.

Ou ZY, Pereira SF, Kimble HJ and Peng KC (1992) Realization of the Einstein–Podolsky–Rosen paradox for continuous variables. *Physical Review Letters* 68: 3663–3666.

Reid MD (1989) Demonstration of the Einstein–Podolsky–Rosen paradox using nondegenerate parametric amplification. *Physical Review A* 40: 913–923.

Short R and Mandel L (1983) Observation of sub-Poissonian photon statistics. *Physical Review Letters* 51: 384–387.

Short R and Mandel L (1984) Sub-Poissonian photon statistics in resonance fluorescence. In: Mandel L and Wolf E (eds). *Coherence and Quantum Optics*, vol. V, pp. 671–678. New York: Plenum.

Slusher RE, Hollberg LW, Yurke B, Mertz JC and Vally JF (1985) Observation of squeezed states generated by four-wave mixing in an optical cavity. *Physical Review Letters* 55: 2409–2412.

Walls DF (1979) Evidence for the quantum nature of light. *Nature* 280: 451–453.

Wu LA, Kimble HJ, Hall J and Wu H (1986) Generation of squeezed states by parametric down conversion. *Physical Review Letters* 57: 2520–2523.

Yamamoto Y and Machida S (1987) High-impedance suppression of pump fluctuation and amplitude squeezing in semiconductor lasers. *Physical Review A* 35: 5114–5130.

NONLINEAR OPTICS AT THE CRITICAL FIELD LIMIT

G A Mourou, University of Michigan, Ann Arbor, MI, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

It is now possible to produce, with compact lasers, intensities so large that the relativistic character of the electrons dominates laser–matter interactions. This is a fundamentally new regime in optics where optics, confined to the study of eV characteristic phenomena, are now addressing phenomena with characteristic energies vastly greater in the MeV–GeV (TeV in the near future) range. With relativistic optics, the field of nonlinear optics found a number of novel applications, including fast ignition of inertially compressed fusion target, bright sources of energetic electrons, protons, ions, positrons, pions, etc., but also nuclear physics, high energy physics, astrophysics, and general relativity.

Relative optics has been one of the most active fields of optics and it is impossible to describe all the applications here. So, this new regime will be illustrated with few examples of the key relativistic mechanisms – reminiscent of conventional nonlinear optics, such as relativistic harmonics, relativistic optical rectification (wake-field acceleration), and relativistic self-focusing in refraction and reflection. We finally show that relativistic optics offers a new and efficient gateway to attosecond physics and nonlinear quantum electrodynamics (QED).

Optics is the study of how electrons respond to light. All material optical properties are the consequence of how light interacts with electrons in materials. Because, in the visible regime the photon energy is of the order of 1 eV, optics deals with phenomena with eV characteristic energy. Light is a wave composed of coupled electric and magnetic fields oscillating in synchrony at high frequencies. The electric and magnetic field oscillate perpendicular to each other, and perpendicular to the direction of propagation, k. Because of the electric field E, electrons under the action of the Lorentz force, $F = eE$, moves a distance $x = a_1 E$ transversally to the propagation direction. In classical optics, the oscillation amplitude x is small compared to the wavelength, and the electrons oscillate and radiate at the laser frequency. The radiated field amplitude and phase depend on how the electron is bound to the atom of the material. The invention of the laser in 1960 gave access to much larger intensities and electromagnetic fields. The laser field became strong enough that the electron displacement, x, in this field could no longer be considered as strictly proportional to the laser field. This departure from linearity is addressed by the addition of new terms in the Taylor series expansion of the displacement:

$$x = a_1 E + a_2 E^2 + a_3 E^3 + \cdots \qquad [1]$$

These additional terms are responsible for all the effects that form the field of nonlinear optics. Note here that the field is still not strong enough to ionize an electron from its parent atom and is therefore below the field that could irreversibly damage the material. Thus, the typical intensity must be kept to a value of less than $\sim 10^{14}$ W/cm^2, where the quiver energy E_Q starts to challenge the ionization energy of a few eV, depending on the material:

$$E_Q = \left\langle \frac{e^2 E^2}{4 m \omega^2} \right\rangle \qquad [2]$$

The bracket denotes the time average over one cycle and ω is the laser angular frequency. Above this limit, the material response is dominated by multiphoton ionization or tunneling, as shown in Figure 1. During the ionization event, high harmonics are produced. Note here again that because the electron is still bound to its nucleus during the emission, we can consider the process of high harmonic generation as bound-electron nonlinear optics. As the intensity increases from 10^{14} to 10^{18} W/cm^2 (Figure 1), we are entering the regime of relativistic intensity or relativistic nonlinear optics. This is a regime that was predicted and discussed in the 1960s but that could be accessed only after the technique of chirped pulse amplification (CPA) was demonstrated, followed by significant progress in the areas of short pulse generation and pulse focusing.

Relativistic Optics

In classical optics one always assumes that during a laser oscillation period the electron mass m_0 stays constant. It is a reasonable assumption since the quiver velocity v of the electron is small compared to the speed of light c. As the intensity is increased a point is reached where the electron quiver velocity approaches the speed of light. This has several implications; first, the mass of the electron changes to become

$$m = \gamma m_0 \qquad [3]$$

where γ is the Lorentz factor given by

$$\gamma = \left(1 - \frac{v^2}{c^2}\right)^{-1} \qquad [4]$$

Second, because v is close to c, the magnetic force component needs to be added and the Lorentz force becomes:

$$\vec{F} = e\vec{E} + \frac{\vec{v}}{c} \times \vec{B} \qquad [5]$$

Until recently, in classical optics and laser physics, the $v \times B$ component was totally ignored. However, in the relativistic regime, this component is as large as



Figure 1 Laser intensity versus years. Note the very steep slope in intensities that occurs during the 1960s. This period corresponds to the discovery of most nonlinear optics effects. Since 1985 after the CPA invention followed by the successive laser short pulse improvements, we are experiencing a similar increase in intensity opening a new regime in optics at 10^{18} W/cm^2 dominated by the relativistic character of the electrons.

the electric one. It pushes the electron forward and is the tenet of the relativistic regime.

At this point, it is convenient to introduce the normalized vector potential:

$$a_0 = \frac{e\lambda E}{m_0c^2} \quad [6]$$

which represents the energy gain by the electron over one period (λ) normalized to the electron rest mass energy. At $a_0 = 1$, corresponding to 10^{18} W/cm^2 for 1 μm wavelength light, the laser–matter interaction is strongly dominated by the relativistic character of the electrons. At these intensities, the motion of the electrons becomes relativistic and the trajectory of the electron dramatically changes. Figure 2 depicts the difference between the two regimes. It can be shown that independently of the intensity regime, the electron transverse motion is always proportional to a_0, while the longitudinal motion is always proportional to a_0^2. This means that for classical



Figure 2 A comparison between classical optics and relativistic optics. The transverse electron displacement scales as a_0 and the longitudinal scales as a_0^2. (a) In classical optics $a_0 < 1$ the transverse electron displacement is proportional to a_0. It is larger than the longitudinal proportional to a_0^2. (b) In relativistic optics it is the opposite, $a_0 > 1$ the transverse displacement becomes smaller than a_0^2.

optics or even bound-electron nonlinear optics with a_0 varying from 10^{-10} to 10^{-4}, the longitudinal motion is $\sim 10^{-10}$ to 10^{-4} smaller than the transverse motion. Of course, the situation reverses completely for $a_0 > 1$, where the longitudinal motion becomes larger than the transverse motion. The departure of the electron motion from the linear regime, due to its relativistic character, gives rise to a new kind of nonlinear optical effects that constitutes the field of relativistic nonlinear optics. This area has become one of the most active in laser physics. In many cases, there are strong similarities between conventional and relativistic optics, and it is the purpose of this article to illustrate the field of relativistic optics by using some of the effects well established in bound electron nonlinear optics.

Considering the rapid progress in laser intensities that the field experienced in the 1960s, as indicated in Figure 1, scientists expected to observe the manifestation of relativistic effects in the 1970s. Formidable intensities on the order of 10^{18} W/cm^2 for 1 μm wavelength light were necessary, however, and could not be readily obtained. Such intensity levels could only be produced in the early 1980s with large-scale sources such as the Helios laser at Los Alamos National Laboratory (LANL) (Figure 3a). Work in relativistic optics virtually could not be conducted in university research laboratories, but rather only in government laboratories. The first relativistic harmonics produced by the critical surface nonlinear motion were observed in 1980 with a kJ-pulse-energy laser at mHz repetition rates (one shot/20 m).

The advent of CPA (Figure 4) revolutionized the field of relativistic optics, placing it within reach of more researchers through enormous reductions in laser size and cost. Further advances in the ultrashort-pulse duration of lasers and in laser focusing made relativistic optics more accessible, especially to universities. Relativistic intensities can be achieved with mJ energy levels at kHz repetition rates by university-size lasers (Figure 3b) instead of with large, kJ, sub-Hz-repetition-rate government-type lasers. Figures 3a and b illustrate the revolution in the relativistic laser evolution representing the Helios (LANL) system. Figure 3b depicts the relativistic λ^3 laser target chamber. The λ^3 laser reaches its relativistic intensity (10^{18} W/cm^2) with pulse energy only on the order of 1 mJ and pulse duration on the order of 10 fs, i.e., a few light periods. Its energy is concentrated on a single wavelength spot size using an f#1 paraboloid corrected by a deformable mirror. Note that all the energy is contained in a focal volume of a few λ^3, hence its name.


(a)


(b)

Figure 3 Two relativistic lasers. (a) Helios at LANL, was the first relativistic laser with $a_0 \sim 1$ at mHz repetition rate. (b) The λ^3 at the University of Michigan has an $a_0 \sim 1$ at kHz repetition rate.

Some Examples of Relativistic Nonlinear Optics

We will illustrate the field of relativistic optics by comparing relativistic effects with some well-known nonlinear effects.

(a) Relativistic optical rectification (laser wake-field acceleration of electrons and ions)

One well-known bound-electron optical effect coming from the second-order term in eqn [1] is optical rectification. This effect, which takes place in noncentrosymmetric crystals, gives rise to a DC field transverse to the propagation direction. In the relativistic regime, a similar effect known as wake-field acceleration will also contribute to rectification of the optical field. We have seen that in vacuum, electrons are strongly pushed forward by $v \times B$ force. In a plasma, the electromagnetic wave will also push



Figure 4 The concept of CPA is the key technique to get relativistic intensity. An initial short pulse is first stretched out (chirped) by a factor $\sim 10^4$, for instance by a pair of diffraction gratings. The stretched pulse intensity becomes lowered by the same factor of $\sim 10^4$. The stretched pulse intensity can then be amplified to a level 10^4 times higher. Once the laser energy has been extracted from the amplifier the stretched pulse is recompressed by the same factor ($\sim 10^4$) to its initial value. This way the laser intensity has been boosted to 10^4 times the peak intensity that the amplifier could have withstood.

forward the electrons, dragging the much heavier positive ions behind, as shown in Figures 5a and b. The charge separation that ensues will produce a strong electrostatic field that can be of the order of the transverse light electric field, which is huge. Unlike in classical optical rectification, in the relativistic regime the effect can be very efficient. Of the order of 10% or more of the transverse field may be rectified. For an intensity of 10^{18} W/cm^2, the electric field can be on the order of 10^{12} V/m (CERN on one meter), or 10^5 times larger than the field that can be obtained by more conventional technology. In addition, the rectified field is flipped along the longitudinal direction. Note also that since the field is created within a plasma, the medium cannot be broken down further and can support these extremely high fields. This effect had to wait for the relativistic-intensity lasers to become a reality before being demonstrated. Today energies up to 200 MeV have been demonstrated by using a 50 TW laser focused on a gas jet. Because the electrons drag the ions, a beam of ions is also observed concomitant with the electron beam. The generation of protons with energy up to 56 MeV has been reported by LLNL.

(b) Relativistic harmonic generation

Harmonic generation in the relativistic regime can be produced in two ways, as a result of the laser plasma interaction with electron density n_e, either below or above the critical density n_c. The first is for $n_e < n_c$ and corresponds to an underdense plasma where light can propagate. Harmonics generation was predicted in the late 1960s. Even-order harmonics are observed with linear and circular polarizations. This is the signature of relativistic effects since even-harmonics cannot occur in conventional nonlinear optics in centrosymmetric media.



Figure 5 Relativistic rectification in plasma. (a) The high intensity pulse before entering the plasma. (b) Illustrate the $v \times B$ pushing first the plasma electrons. The electrons then drag the heavy ions behind them like a horse pulling a cart. The longitudinal electrostatic field that is generated is almost as large as the transverse laser field.

Harmonic generation can also be produced in over-critical plasmas, where $n > n_c$. In this case, the light cannot propagate and be reflected. The strong $v \times B$ oscillatory force applied to the critical surface will produce a self-modulated reflected beam. This effect was first observed using the Helios laser. The idea of the moving-mirror model was first put forward in the early 1980s. Generation of frequencies up to the 70th harmonic has been demonstrated so this method could provide an efficient way to produce high harmonics. This technique has the advantage over conventional high harmonic generation in that it is capable of accommodating a pulse of large energy, since one can focus the beam over a small area, limited only by the laser wavelength, without fear of disrupting the plasma.

(c) Relativistic self-focusing in refraction

In bound-electron nonlinear optics, the third-order term in eqn [1] is responsible for self-focusing. A similar effect also exists in relativistic optics; it is described in Figure 6a. In the relativistic regime, the electron driven by the laser field changes its mass. In turn, this mass change will modify the index of refraction according to:

$$n^2 = 1 - \left(\frac{\omega_p}{\omega}\right)^2 \qquad [7]$$

where the plasma frequency is given by

$$\omega_p^2 = \frac{e^2}{m} n_e \qquad [8]$$

where n_e is the plasma electron density, and m is the intensity-dependent mass according to eqn [1].

For $\omega > \omega_p$, the index of refraction is positive and the pulse can propagate in the plasma. For the higher-beam-intensity part of the beam, i.e., on the beam axis, the plasma frequency will be less than the frequencies corresponding to the pulse wing. This will cause a modification of the laser wavefront and the beam to self-focus.

(d) Relativistic self-focusing in reflection and isolated attosecond pulse generation

For $\omega < \omega_p$, (eqn [7]) is negative and the pulse cannot propagate and so is reflected at the critical surface. However, the large light pressure will push the plasma critical-density surface at twice the laser frequency, making it cancel out the beam spatial intensity profile. In the relativistic λ^3 regime, the laser is focused at one wavelength. If the light is linearly polarized, the electron density will be collectively moved back and forth along the critical surface. This time-dependent deformation of the critical surface will produce a deflection of each electromagnetic half-cycle in a specific direction (Figure 7), providing a simple means for generating isolated attosecond pulses efficiently. The relativistic motion of the critical surface compresses (relativistic Doppler) the incident femtosecond pulse to the attosecond regime. To understand this compression, recall that the incident pulse travels opposite to the mirror motion formed by the critical surface (for a fraction of the cycle). As we have seen in this regime the critical surface moves also at close to the speed of light, v. Since the reflected light must also travel at c, it has no choice but to be compressed, producing an electromagnetic accumulation along the critical surface. The compression factor will



Figure 6 Relativistic self-focusing. (a) Relativistic self-focusing in refraction. Here the index of refraction is modified by the change in the electron mass. The electron mass change will in turn modify the plasma frequency across the beam and consequently the index of refraction. (b) Relativistic self-focusing in reflection showing the deformation of the critical surface by the light pressure from a strongly focused beam. The light is reflected in a series of ultrashort pulses in the attosecond domain.



Figure 7 Compressed and deflected attosecond pulses. The combination of relativistic deflection and compression leads to 200 as isolated pulses.

depend on the critical surface velocity and is dependent on the plasma stiffness, i.e., the plasma density. Low-density plasmas are softer than high-density ones; here, n_c is the plasma critical density. The compressed pulse duration has been determined by a particles-in-cell (PIC) simulation to be given by $\tau = 600/a_0$. From the PIC simulation, it can be determined that the compressed pulse optimum duration is obtained for $n_e = a_0 n_c/2$. This technique is an interesting alternative to the one based on high-harmonic generation due to bound electrons, which has been recently demonstrated. The advantage of the relativistic optics approach is that it can be scaled up to large energies, from the mJ to the several-joule level, in contrast with demonstrated attosecond schemes that can only compress mJ pulse energies with an efficiency of 10^{-6}. For a_0 ~100, corresponding to incident intensities of ~10^{22} W/cm^2, a 10-as pulse can be produced by relativistic compression and deflection.

(e) Nonlinear QED on a table top

Looking at Figure 1, we see that there is a regime around 10^{29} W/cm^2 where it becomes possible to produce electron–positron pairs. The condition to fulfill this is given by

$$E_s \lambda_c e = 2m_0 c^2 \qquad [9]$$

Here $\lambda_c = h/m_0 c$ is the Compton wavelength, E_s the Schwinger field, and h the Planck constant. This expression states that for pair creation the work of the laser field over a Compton wavelength must be equal to the electron–positron rest-mass energy. This field E_s, also known as the critical field, E_s ~10^{16} V/cm, corresponds to a laser intensity of 10^{29} W/cm^2.

An alternative way to depict the process of electron–positron generation from vacuum is by considering the vacuum as a dielectric medium with a gap $E_G = 2m_0 c^2$. The field to produce an electron–positron pair is the one necessary to bend the bands so that an electron can tunnel from the Dirac sea into the vacuum states (Figure 8). The probability for such an event is given by

$$W \propto \exp\left(-\frac{\pi E_s}{E}\right) \qquad [10]$$

Today, the intensity necessary to reach pair creation is more than six orders of magnitude higher


$E_s = \frac{2m_0c^2}{e\lambda_c}$ with $\lambda_c = \frac{\hbar}{m_0c}$
$2m_0c^2$
e^+e^- Dirac sea
$W \propto \exp\left(-\frac{\pi E_s}{E}\right)$

Figure 8 Pair creation. Electron tunneling from the Dirac sea into the vacuum state.

than what we could produce, $\sim 10^{22}$ W/cm^2. To bridge this enormous gap the electric field has been enhanced by colliding a short and intense pulse with a Stanford Linear Accelerator Center (SLAC) super-relativistic, 50 GeV electron beam. The Lorentz factor is $\gamma = 10^5$, and the laser field of 210^{10} V/cm (corresponding to an intensity of 10^{18} W/cm^2) can be enhanced by 10^5 to reach the critical field.

The progress in relativistic compression described above could make possible the generation of electron–positron pairs directly from the laser. We are on the verge of having a tabletop laser that could produce an intensity close to 10^{23} W/cm^2, corresponding to $a_0 > 100$. From the scaling law described previously, we should get $\tau < 6$, where the wavelength of such a compressed pulse would also be reduced by ~100. The focal volume would then be reduced by six orders of magnitude. If we assume an efficiency of 10^{-1}, an intensity close to the critical intensity of 10^{29} W/cm could be reached with a tabletop laser and boil vacuum.

Conclusion

Today, laser intensities are such that during light–matter interaction, the electron motion is dominated by relativistic effects responsible for a new type of nonlinear optics called relativistic nonlinear optics. Relativistic nonlinear optics is characterized by extreme field gradients (TV/m) and light pressure in the Gbar regime. Relativistic nonlinear optics offers an attractive and novel way for efficient attosecond pulse generation with intensities near the critical (Schwinger) field, opening optics to vast new horizons.

See also

Relativistic Nonlinear Optics.

Further Reading

Agostini P, Barjot G, Bonnal JF, Mainfray G and Manus C (1968) *IEEE Journal of Quantum Electronics* QE-4: 667.

Albert O, Wang H, Liu D, Chang Z and Mourou G (2000) *Optics Letters* 125: 1125.

Bloembergen N (1965) *Nonlinear Optics*. New York: Benjamin.

Boyd RW (1992) *Nonlinear Optics*. San Diego: Academic.

Brabec T and Krausz F (2000) *Review of Modern Physics* 72: 545.

Brezin E and Itzykson C (1970) *Physics Review D* 2: 1191.

Bula C, McDonald KT, Prebys EI, *et al.* (1996) *Physics Review Letters* 76: 3116.

Bulanov SV, Naumova NM and Pegoraro F (1994) *Physics Plasmas* 1: 745.

Carman RL, Benjamin RF and Rhodes CK (1981) *Physics Review A* 24: 2649.

Chen S-Y, Maksimchuk A, Esarey E and Umstadter D (2000) *Physics Review Letters* 84: 5528.

Eberly J (1969) *Progress in Optics* 7: 361.

Franken PA, Hill A, Peters C and Weinreich G (1961) *Physics Review Letters* 7: 118.

Hentschel M, Kienberger R, Spielmann Ch, *et al.* (2001) *Nature* 414: 509.

Joshi C and Katsouleas T (2003) Plasmas accelerators at the energy frontier and on tabletops. *Physics Today* 56: 47.

Litvak AG (1969) *Soviet Physics JETP* 30: 344.

Malka V, Fritzler S, Lefebvre E, *et al.* (2002) Electron acceleration by a wakefield forced by an intense ultra-short laser pulse. *Science* 22: 298.

Max C, Arons J and Langdon A (1974) *Physics Review Letters* 33: 209.

Mourou GA, Barty CPJ and Perry MD (1998) *Physics Today* 51(1): 22.

Naumova NM, Nees JA, Sokolov IV, Hou B and Mourou GA (2004) Relativistic generation of isolated attosecond pulses in a λ^3 focal volume. *Physics Review Letters* 92: 063902.

Norreys PA, *et al.* (1996) *Physics Review Letters* 76: 1832.

Sarachik E and Schappert G (1970) *Physics Review D* 1: 2738.

Shen YR (1984) *The Principles of Nonlinear Optics*. New York: Wiley.

Snavely RA, *et al.* (2000) *Physics Review Letters* 85: 2945.

Strickland D and Mourou G (1985) *Optics Communications* 55: 219 and 447.

Tajima T and Dawson JM (1979) *Physics Review Letters* 43: 262.

Tarasevitch A, Orisch A, von der Linde D, *et al.* (2000) *Physics Review A* 62: 023816.

Umstadter D, Chen S-Y, Maksimchuk A, Mourou G and Wagner R (1996) *Science* 273: 472.

NONLINEAR OPTICS, APPLICATIONS

Contents

Phase Matching
Pulse Compression via Nonlinear Optics
Raman Lasers
Self-Focusing and Related Effects (Solitons and Multiphoton Absorption)
Three-Dimensional Microfabrication

Phase Matching

A V Smith, Sandia National Laboratories,
Albuquerque, NM, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Phase matching is important in any process that coherently transfers energy from one optical mode to another over a long interaction length. We will start by illustrating the principle, by imagining that the original mode is a single transverse mode of a waveguide, and that microscopic scattering centers distributed uniformly throughout the waveguide weakly scatter light into a second mode with orthogonal polarization. Then suppose that the scattering process preserves phase so the phase of the wavelet scattered at each point into mode two is the same as that of the original wave in mode one. Such a process is shown in Figure 1 where the propagation constant of the initially excited mode is k_1 and the propagation constant of the second mode is k_2. At each z location the light scattered into the second mode has the phase $\phi = k_1 z$, and after propagating to the end of the waveguide $(z = L)$ with the phase velocity characteristic of the second mode, it has the phase $\phi_z = [k_1 z + k_2(L - z)] = [k_2 L + z(k_1 - k_2)]$. Coherently summing the fields scattered at all of the z positions, gives the net output field in the second mode. Figure 2 shows how this field can be constructed graphically. The rotation angle of each phasor represents its phase, ϕ_z, while the length of each phasor represents the magnitude of the field contribution from the corresponding z segment. It is apparent that the energy transfer is maximized if the contributions from all z positions have the same phase, in which case the phasors form a straight line, and the power in the second mode is proportional to L^2. This corresponds to $(k_1 - k_2 = 0)$. When this condition is met the waves in the two



Figure 1 An input wave with propagation constant k_1 in a waveguide mode is weakly scattered into a second waveguide mode with propagation constant k_2. The phase mismatch is $\Delta k \equiv k_2 - k_1$.



Figure 2 Phasor diagram showing the net output field contributions from segments 1–11. The net field at the output end, E_{net}, is the vector sum of the phasors. The phasors are complex quantities whose angles represent their relative phases according to $E_n = E_o \exp(i\phi_n)$ where $\phi_n = \phi_o - \Delta k(z_n - z_1)$.

modes have equal phase velocities, and the process is phase matched.

The quantity $(k_2 - k_1)$ is called Δk, the phase mismatch. If $\Delta k \neq 0$ the phasors curl to form a section of a circle, reducing the net field in mode two. If all the phasors have the same length, as they would if the wave in mode one is undepleted, the size of the mode two field at position z is

$$E(z) = Kz\frac{\sin(\Delta kz/2)}{\Delta kz/2} = Kz\,\mathrm{sinc}\left(\frac{\Delta kz}{2}\right) \qquad [1]$$

where K is a constant describing the scattering strength. The corresponding power in mode two is plotted in Figure 3 for various values of Δk. When $\Delta k = 0$ the power grows quadratically with z, but for $\Delta k \neq 0$ it is proportional to $\sin^2(\Delta kz/2)/\Delta k^2$. If we plot the normalized output power in mode two $(z = L)$ versus Δk, we have the curve shown in Figure 4 which is $\mathrm{sinc}^2(\Delta kL/2)$.

When $\Delta k = 2\pi/L$ the phasors form a complete circle so the power in mode two first grows with z but then shrinks back to zero at $z = L$. For a given value of Δk the length for which the phasors form a complete circle is known as the coherence length, $L_{\mathrm{coh}} = 2\pi/\Delta k$.

Reducing the z increments to infinitesimals, we can write the output field for mode two in integral form:

$$E_{\mathrm{net}} = \int_0^L S(z)e^{-i\Delta kz}\,\mathrm{d}z \qquad [2]$$

This shows that when Δk is independent of z, the output field is the Fourier transform of a source term, $S(z)$, transformed into Δk space. Where $S(z)$ has a constant value from $z = 0$ to $z = L$ and is zero outside that range, the Fourier transform has the form given by eqn [1], with $z = L$.



Figure 3 Plot of power in second mode versus z for different values of Δk. For $\Delta k = 0$ the power is proportional to z^2. For $\Delta k = 2\pi/L$ the phasors form a closed circle so the net field is zero at $z = L$. For $\Delta k = 4\pi/L$ the phasors trace two complete overlapped circles so again the field is zero at the $z = L/2$ and at $z = L$.



Figure 4 The plotted function indicates the relative irradiance of the output field, $|E|^2$, versus the phase mismatch Δk. The full width at half maximum is $\Delta k = 1.77\pi/L = 5.57/L$.

The $L^2\,\mathrm{sinc}^2(\Delta kL/2)$ form for the output power is ubiquitous in functions that describe the efficiency of nonlinear optical interactions, as well as acousto-optic and electro-optic modulation of light waves. However, it should be kept in mind that $L^2\,\mathrm{sinc}^2(\Delta kL/2)$ holds only when $S(z)$ is independent of z. If the scattering is strong enough to alter the phase or amplitude of the driving wave, or if the coupling strength varies with z for any other reason, $S(z)$ is not independent of z and the $L^2\,\mathrm{sinc}^2(\Delta kL/2)$ dependence is modified.

Our simple example relied on scattering in a waveguide, with a source term that was linear in the field in mode one. In practice, most optical devices that couple light between modes, rely on nonlinear interactions among multiple optical fields, or between an optical field and an acoustic or an rf electric wave. These nonlinear interactions produce a polarization wave in a suitable material at a sum or difference frequency. Each point of this polarization radiates a wavelet in all directions. These wavelets interfere constructively only in directions that are nearly phase matched. Examples include traveling wave acousto-optic filters, in which an acoustic wave traveling parallel to an input light beam of one polarization in a birefringent material, couples light into the orthogonal polarization via the elasto-optic effect. Traveling wave electro-optic modulators are similar but rely on the linear electro-optic effect for the coupling. Optical frequency mixing uses the nonlinearity of various materials to mix multiple optical waves, creating polarization waves at sum and difference frequencies. A wide variety of such nonlinear interactions is discussed in textbooks on nonlinear optics, electro-optics, and acousto-optics. In all of these cases the phase velocity mismatch of interest is that between an induced polarization wave and a radiated mode, and the phase mismatch is $\Delta k = k_{\text{radiation}} - k_{\text{polarization}}$.

To find $S(z)$ and Δk for these nonlinear mixing processes, we must construct the polarization wave. We consider only monochromatic plane waves here, considering beams with spatial or temporal structure in a later section. The electric field of a monochromatic plane optical wave propagating in direction $\mathbf{r}_o$ can be described by

$$\begin{aligned} E &= E_o \cos(\omega_o t - \mathbf{k}_o \cdot \mathbf{r}_o + \phi_o) \\ &= \tfrac{1}{2}[E\, e^{-i(\omega_o t - \mathbf{k}_o \cdot \mathbf{r}_o)} + E^*\, e^{i(\omega_o t - \mathbf{k}_o \cdot \mathbf{r}_o)}] \end{aligned} \qquad [3]$$

The complex notation is a convenience that simplifies algebraic book-keeping. Similarly, an acoustic field propagating in direction $\mathbf{r}_a$ can be written:

$$\begin{aligned} A &= A_o \cos(\omega_a t - \mathbf{k}_a \cdot \mathbf{r}_a + \phi_a) \\ &= \tfrac{1}{2}[A\, e^{-i(\omega_a t - \mathbf{k}_a \cdot \mathbf{r}_a)} + A^*\, e^{i(\omega_a t - \mathbf{k}_a \cdot \mathbf{r}_a)}] \end{aligned} \qquad [4]$$

In a suitable material the polarization induced by the product of the optical and acoustic waves has a term of the form:

$$P = sEA \qquad [5]$$

P has components at both the sum and difference frequency. The sum frequency component is:

$$P_{\omega_o+\omega_a} = \frac{1}{4} s[EA\, e^{-i(\omega_o+\omega_a)t + i(\mathbf{k}_o+\mathbf{k}_a)\cdot\mathbf{r}} + \text{cc}] \qquad [6]$$

where ‘cc’ indicates the complex conjugate of the first term. The component at the difference frequency is

$$P_{\omega_o-\omega_a} = \frac{1}{4} s[EA^*\, e^{-i(\omega_o-\omega_a)t + i(\mathbf{k}_o-\mathbf{k}_a)\cdot\mathbf{r}} + \text{cc}] \qquad [7]$$

An important point is that the k vector of the sum-frequency polarization is $(\mathbf{k}_o + \mathbf{k}_a)$. Phase matching requires that the radiated sum-frequency wave has the same propagation vector. The radiated difference frequency wave must have the propagation vector $(\mathbf{k}_o - \mathbf{k}_a)$ to be phase matched. Phase matching for these two cases is shown in Figure 5. Note the general rule that if the frequency of a wave appears as $+\omega$ in the induced polarization, the associated k vector contribution to the polarization wave is $+\mathbf{k}$, while if it appears as $-\omega$, the k vector contribution is $-\mathbf{k}$. For example, the acoustic wave in $P_{\omega_o+\omega_a}$ is associated with $+\mathbf{k}_a$ contribution to the polarization wave, while in $P_{\omega_o-\omega_a}$ it is associated with a $-\mathbf{k}_a$ contribution.



Figure 5 An optical wave with propagation vector k_o and an acoustic wave with propagation vector k_a produce a polarization wave at the sum frequency with the propagation vector k_{o+a} (top diagram), and a polarization wave at the difference frequency with the propagation vector k_{o-a} (bottom diagram).

Using the definition of k:

$$\mathbf{k} = \frac{2\pi}{\lambda}\hat{\mathbf{k}} = \frac{\omega}{v}\hat{\mathbf{k}} \qquad [8]$$

where v is the phase velocity, we can write Δk as

$$\begin{aligned} \Delta\mathbf{k} &= \mathbf{k}_{o+a} - \mathbf{k}_o - \mathbf{k}_a \\ &= \left(\frac{\omega_{o+a}}{v_{o+a}}\hat{\mathbf{k}}_{o+a} - \frac{\omega_o}{v_o}\hat{\mathbf{k}}_o - \frac{\omega_a}{v_a}\hat{\mathbf{k}}_a\right) \end{aligned} \qquad [9]$$

Clearly, if all of the waves had equal phase velocities, phase matching would be achieved for collinear interactions, where all of the propagation vectors are parallel, because the frequencies inside the parentheses sum to zero. This is seldom the case as for example, the phase velocity of an acoustic wave is much less than that of an optical wave, making an acoustic wave’s k-vector disproportionately long compared with that of an optical wave. On the other hand, an rf wave usually has a disproportionately short k-vector compared with an optical wave. Even when all of the waves are optical, dispersion of the refractive index usually makes the k-vector of the bluer waves disproportionately long compared with those of the red waves. A wide variety of methods are used separately or in combinations to compensate for these effects in order to achieve phase matching and these are discussed below.

Phase Matching Techniques

Noncollinear Phase Matching

If one of the low frequency waves in a three wave mixing process, such as the acousto-optic interaction discussed above, has a lower phase velocity than the bluest wave, then noncollinear phase matching may be possible. Acousto-optic deflectors are often phase matched with a noncollinear geometry, such as that shown in Figure 6. An input optical wave of frequency ω_o reflects from a traveling acoustic wave with frequency ω_a in an optically isotropic material to produce an output optical wave of frequency $\omega_o + \omega_a$. The Bragg condition for efficient reflection is

$$\sin\theta = \frac{k_a}{2k_o} \qquad [10]$$

which may be seen from the figure to be the same as the phase matching condition, assuming k_{out} and k_{in} have the same magnitude, which is a good approximation for typical acoustic frequencies less than a few GHz.

Stimulated Brillouin scattering is another example of noncollinear mixing of acoustic and optical waves. One possible geometry has the input optical and acoustic waves traveling in opposite directions to create a reflected optical wave at the sum frequency. The phase matching condition is then

$$k_{\text{acoustic}} \approx 2k_{\text{optical}} \qquad [11]$$

which implies

$$\omega_{\text{acoustic}} = \frac{2n\omega_{\text{optical}}}{c} v_{\text{acoustic}} \qquad [12]$$

The acoustic frequency that phase matches such counter propagating Brillouin scattering is usually a few GHz in liquids and solids.

If noncollinear phase matching in an isotropic material is not possible, as is usually the case for electro-optic modulation and for all-optical sum and difference frequency mixing, it is sometimes possible to use the properties of nonisotropic media to adjust the phase velocity of one or more of the waves. There are several possibilities, such as natural birefringence, form birefringence, photonic band edge tuning, wave guide modal propagation, and various forms of quasi phase matching. Each is briefly described below.



Figure 6 Phase matching in an acousto-optic deflector.

Birefringent Phase Matching

Natural birefringence

Naturally birefringent crystals can be categorized as either uniaxial or biaxial. In either case, light propagating along any direction (except along an optical axis) has two orthogonal eigen polarizations with different refractive indices. In uniaxial crystals, one of these indices is independent of the propagation direction and is called the ordinary index, n_o. The refractive index for the other polarization, known as the extraordinary polarization, is given by

$$\frac{1}{n_e^2(\theta)} = \frac{\sin^2\theta}{n_e^2} + \frac{\cos^2\theta}{n_o^2} \qquad [13]$$

where θ specifies the propagation direction measured from the z, or optical, axis, and n_e and n_o are the refractive indices for light polarized parallel and perpendicular to z. The two eigen polarizations are aligned with the lines of constant or latitude (o-wave) or constant longitude (e-wave). The variation of the two refractive indices with propagation angle θ is shown in Figure 7 for a negative uniaxial crystal which is characterized by $n_e < n_o$, and for a positive uniaxial crystal, characterized by $n_e > n_o$.

The acousto-optic tunable filter relies on natural birefringence to achieve a phase match. An optical and an acoustic wave propagate normal to the optical axis of a uniaxial crystal. If the crystal is negative uniaxial, with an input optical polarization of 'e', and an output optical polarization of 'o', the k vector of the acoustic wave must make up the difference



Figure 7 The circle and ellipse represent the two refractive indices for a negative uniaxial crystal (left diagram) and a positive uniaxial crystal (right diagram) for different propagation directions specified by the angles (θ, ϕ) with ϕ fixed. These curves are independent of the azimuthal angle ϕ, so in three dimensions the ordinary refractive index, n_o, forms a sphere in both cases, while the extraordinary index, n_e, forms a prolate ellipsoid for a negative uniaxial crystal, or an oblate ellipsoid for a positive uniaxial crystal.

$k_o - k_e$. This may be expressed as

$$k_a = \frac{\omega_a}{v_a} = \frac{(\omega + \omega_a)n_o}{c} - \frac{\omega n_e}{c} \qquad [14]$$

or, ignoring the difference between ω and $\omega + \omega_a$, the optical frequency that is phase matched is

$$\omega = \frac{\omega_a c}{v_a \Delta n} \qquad [15]$$

where v_a is the phase velocity of the acoustic wave, and $\Delta n = n_o - n_e$. The phase matched optical frequency is seen to be tunable with ω_a. A typical acoustic frequency for a visible filter is a few hundred MHz. The phase matching bandwidth set by the $\mathrm{sinc}^2(\Delta kL/2)$ function can be quite narrow, with a subnanometer optical bandpass in a crystal a few cm long.

Natural birefringence is also widely used to phase match all-optical sum and difference frequency mixing. To counter normal optical dispersion, the bluest wave is polarized in the direction associated with the smaller refractive index, while at least one of the two redder waves has the opposite polarization. By adjusting the propagation angle, θ, the refractive index of the extraordinary waves can be adjusted until exact phase matching is achieved. If the two redder waves both have the high index polarization the process is sometimes called type I, whereas if they have opposite polarizations it is called type II.

Figure 8 illustrates type I phase matched second harmonic generation in a negative uniaxial crystal. The fundamental wave with frequency ω is o-polarized, while the second harmonic wave at frequency 2ω is e-polarized. The circle drawn in dashes represents the line swept out by the polarization wave vector $2k_\omega$ as the propagation direction θ is swept, while the ellipse represents the loci of $k_{2\omega}$ for the same angle. Collinear phase matching is achieved at the point of intersection of the two curves. This sets the angle θ_{pm}. For angles greater than θ_{pm}, dispersion is over-compensated and $\Delta k < 0$ so noncollinear phase matching is possible. All ϕ angles have equivalent propagation properties, so the loci of phase matched propagation directions form a cone at $\theta = \theta_{pm}$. Usually the propagation angle ϕ is chosen to maximize the nonlinear response of the crystal.

Biaxial crystals share with uniaxial crystals the property of two orthogonal eigen polarizations with different refractive indices, but the angular dependence of the indices is more complex. The two indices associated with propagation along direction (θ, ϕ) can be found by solving

$$\frac{\sin^2\theta\cos^2\phi}{1/n^2 - 1/n_x^2} + \frac{\sin^2\theta\sin^2\phi}{1/n^2 - 1/n_y^2} + \frac{\cos^2\phi}{1/n^2 - 1/n_z^2} = 0 \qquad [16]$$

for the two possible values of n. Here n_x, n_y, and n_z are the refractive indices for light polarized along the respective principal axes, where the convention is $n_x < n_y < n_z$. There are two optical axes lying in the x–z plane at an angle determined by the values of n_x, n_y, and n_z. The phase matching loci are no longer lines of constant latitude as they were for uniaxial crystals, but instead are curves that encircle either the optical axes or one of the principal axes. Figure 9 shows an



Figure 8 Collinear phase matching of second harmonic generation in a negative uniaxial crystal. The second harmonic light is *e*-polarized with a refractive index indicated by the solid line while the fundamental light is o-polarized as indicated by the dashed line. The crossing point of the two refractive indices determines the phase matching angle θ_{pm}.



Figure 9 Calculated loci of propagation directions that achieve birefringent phase matching for type I collinear second harmonic generation of different wavelengths in the crystal CsB_3O_5. The fundamental wavelengths are 2,700 nm (dotted curve looping around the *x* axis), 3,000 nm (dashed curve looping around the *y* axis), 1,000 nm (solid curve looping around the optical axis 'oa'), and 800 nm (chained curve looping around the *z* axis). For clarity only a single octant of the sphere of propagation directions is shown. The loci in the other octants of the sphere are formed by reflections in the three principal planes.

example of each type of phase matching curve associated with second harmonic generation of different wavelengths in the crystal CsB_3O_5.

Note that because these curves always intersect at least one of the principal planes, if phase matching in biaxial crystals is possible at all, it is also possible in a principal plane. Biaxial crystals are usually phase matched in a principal plane, but phase matching outside the principal planes can in some cases maximize the nonlinear response, minimize the temperature sensitivity, or adjust the relative group velocities.

Form birefringence

Some materials, such as GaAs, have a strong nonlinear optical response but are not birefringent, so optical frequency mixing cannot be phase matched using natural birefringence. However, form birefringence can be engineered by layered growth, and it can be used to phase match. If many alternating layers of two materials with different refractive indices are stacked together with a layer thickness comparable to the wavelength of light, the material is birefringent for light propagating parallel to the layers. Light polarized with its E field parallel to the layers will have a higher refractive index than light polarized with its field perpendicular to the layers. The strength of birefringence, $(n_{\parallel} - n_{\perp})$, can be engineered by varying the relative thicknesses and refractive indices of the two layered materials. This has been demonstrated in GaAs/AlAs waveguide structures in which the AlAs layers were oxidized to form Al_2O_3, which has a refractive index of 1.6, compared with an index of 3.4 for GaAs. The resulting large birefringence was used to phase match infrared difference frequency mixing.

Photonic Lattice Phase Matching

The propagation constant of a light wave can be controlled by tuning its frequency near the bandgap of a Bragg structure. The Bragg structure can be a stack of layers with alternating refractive index. If the stack consists of layers of thickness and refractive index l_1, n_1 and l_2, n_2, the Bragg condition at normal incidence is

$$\phi_1 + \phi_2 = \frac{\omega_{\mathrm{Bragg}}}{c}(n_1 l_1 + n_2 l_2) = m\pi \qquad [17]$$

where m is an integer. Frequencies near ω_{Bragg} are strongly reflected. The width of the reflective band of a structure with many layers is proportional to the refractive index contrast, $(n_1 - n_2)/(n_1 + n_2)$. At certain frequencies, on both sides of the bandgap, the reflectivity vanishes. The first transmission peak on the red side of the bandgap has an effective refractive index that is greater than the average $(n_1 + n_2)/2$, while the first peak on the blue side has an effective index less than the average. This effect can be used to adjust the effective value of Δk in the structure. As a bonus, operating on one of the transmission peaks near the bandgap enhances the optical field in the material, increasing the strength of the nonlinear interaction.

It is also possible to use a Bragg structure in reflection mode. Tuning to the red side of the band center increases the effective refractive index of the reflected wave, while tuning to the blue side decreases it. The internal fields are not enhanced in this case and the interaction length may be quite short.

Quasi-Phase Matching (QPM)

Quasi-phase matching uses spatial modulation of the polarization source with a modulation period of $L_{\mathrm{mod}} = 2\pi/\Delta k$ to boost the efficiency of the mixing process even though $\Delta k \neq 0$. We can consider the periodic modulation as another interacting wave that is included in the creation of the polarization wave. The modulation wave has $\omega = 0$ and is stationary with period L_{mod}. Because the modulation is usually a square wave rather than sinusoidal, it is made up of multiple sinusoidal waves with periods L_{mod}/m, all of which can participate in generating a polarization wave. Like traveling waves, the stationary modulation waves can be oriented in any direction, and any Fourier component of the modulation wave with wave vector $\Lambda_m = 2\pi m/L_{\mathrm{mod}}$ can participate in (quasi) phase matching, as shown in Figure 10.

Usually the spatial modulation is achieved by periodically reversing the sign of the nonlinear coupling coefficient. Figure 11 shows the associated phasor diagram for perfect first-order QPM. The net fields from the first two modulation periods are labeled E_1 and E_2. If the sign of the nonlinearity in the first half of the modulation period were not reversed in the second half, the phasors would form a complete circle resulting in a null net field. All following periods would also produce null net fields. However, if the sign is reversed midway through the first period, the phasors from the second half are sign reversed and the net field is E_1 as shown. The magnitude of E_1 is smaller than for a truly phase matched segment by the



Figure 10 Quasi-phase matching vector diagram for sum frequency mixing. The mth Fourier component of the grating vector is indicated by Λm.



Figure 11 Phasor diagram for a quasi-phase matched interaction in a material with alternating signs of the nonlinear coefficient. The contributions from four segments, each of length $L_{coh}/2$ are shown. The net field from the first QPM period is labeled E_1, and that from the second period is E_2. The dashed line shows the path the phasors would trace if the nonlinear coefficient were not sign reversed in the even numbered segments.

ratio of the diameter of the circle to its circumference, or by $2/\pi$. Coherence lengths in crystals are typically 5–50 μm so crystals that are several mm long have a large number of periods, in which case the net phasors $E_1, E_2, \ldots$ can themselves be considered elementary phasors that form the net field for the full crystal. For example, if the modulation period L_{mod} is not exactly equal to $2\pi/\Delta k$, QPM is imperfect and phasors $E_1, E_2, \ldots$ curl up to give a net field of $\text{sinc}(\Delta k' L/2)$ where $\Delta k' = \Delta k - 2\pi/L_{mod}$. For all practical purposes, a QPM crystal containing many modulation periods performs the same as a phase matched crystal with its nonlinear coupling reduced by $2/\pi$.

Referring to eqn [2], we note that periodic modulation of the source term $S(z)$ produces peaks in the phase matching curves at $\Delta k = m2\pi/L_{mod}$ where m is an integer. If $S(z)$ is a square wave of alternating sign over $0 < z < L$, its Fourier transform is the convolution of $\text{sinc}(\Delta k L/2)$ with a picket fence function with spikes at $\Delta k = m2\pi/L_{mod}$. If $L_{mod} \ll L$, the crystal contains many periods of the square wave and the spikes are separated by many times the width of the $\text{sinc}(\Delta k L/2)$ function. This results in well separated sinc functions centered at $\Delta k = 2\pi m/L_{mod}$, and any process with a coherence length of L_{mod}/m will be quasi-phase matched. That is, one of the Fourier peaks in Δk space will be centered on the corresponding value of Δk.

The magnitudes of the QPM peaks are maximized if the modulation of $S(z)$ is a sign reversal, as described above. If the positive and negative segments have unequal lengths, we can define the duty cycle as $D = l_+/(l_+ + l_-)$. The heights of the pickets in the picket fence are then

$$h_m = \frac{2}{m\pi}\sin(\pi m D) \qquad [18]$$

The largest magnitude peak is for $m = 1$ and $D = 0.5$ in which case $h_1 = 2/\pi$.

Unlike birefringent phase matching, QPM can, in principle, phase match any set of polarizations for the interacting waves. This makes it possible to use a polarization set that maximizes the nonlinear response of the crystal.

Ferroelectric poling

There are various ways to achieve QPM. By far the most popular and versatile is by ferroelectric poling. Ferroelectric crystals have an internal electric field that can be reversed by the application of a sufficiently strong external poling field. Reversing the internal field also reverses the sign of the nonlinearity for some light polarizations but does not alter the refractive indices. Crystals of $LiNbO_3$ and $KTiOPO_4$, with thickness up to 1 mm, can be poled with periods as short as 5 μm. This is sufficient to quasi-phase match frequency mixing of visible or near infrared light. Figure 12 shows an example of the orientation of the internal fields of patterned ferroelectric domains.

It is possible to pole a crystal aperiodically so that multiple mixing processes are quasi-phase matched simultaneously. To design the poling pattern for such a device, the Fourier transform of an initial trial pattern can be calculated and compared with the target spectrum in Δk space. Iterative algorithms can be used to modify the poling pattern, zeroing in on the target spectrum.

Ferroelectric poling can also form two-dimensional poling patterns, corresponding to a two-dimensional set of Fourier components in Δk space. It can also produce chirped gratings which have a broad phase matching peak. Chirped gratings can be used to simultaneously frequency convert and tailor the temporal shapes of the output pulse when the input pulses are frequency chirped. Poling can also yield fanned poling patterns so the poling period and thus the phase matching wavelength can be shifted by translating the grating.



Figure 12 Diagram of a poled ferroelectric crystal. The four crystal segments represent four ferroelectric domains with internal crystal field directions indicated by the arrows. Reversal of the internal field is accompanied by reversal of the nonlinear coefficient, so this is a quasi-phase matched structure with alternating signs of d_{eff}.

Wafer stacking and patterned crystal growth

Another method of quasi-phase matching relies on stacks of thin plates oriented so the sign of the nonlinearity reverses in adjacent plates. Each plate has a thickness of $mL_{\mathrm{coh}}/2$ where m is an odd integer. If all the plates are identically prepared crystals, it is often possible to reverse the sign of their nonlinearity by reorienting them. It is sometimes possible to optically contact the plates or even to diffusion bond them, avoiding reflective losses at the interfaces. This technique is conducive to large aperture QPM crystals. However, the plates are thin so fabrication is a challenge.

Quasi-phase matched crystals of GaAs have also been epitaxially grown on patterned substrates. The patterning serves as a template for growth of zones with alternating crystal orientation and sign of the nonlinear coefficient.

Total internal reflection

Total internal reflection in a thin slab has also been exploited for QPM (Figure 13). Two effects contribute to the source modulation, one is the rephasing of the waves on total internal reflection; the other is the change in nonlinearity that may accompany the change in propagation direction. Usually plates much thicker than one coherence length are used, so the quasi-phase matching is of high order ($m \gg 1$).

Wave Guide Modal Phase Matching

In waveguides the size and shape of the guide influence the transverse field distributions and the propagation constants for the transverse modes. Generally the higher order transverse modes have higher phase velocities than the lower order modes. This can be used to counteract index dispersion in three wave mixing if the bluest wave propagates in a higher order mode than the redder waves. A problem frequently encountered in using this effect is that the transverse modes are orthogonal, or nearly so. Because the nonlinear response is proportional to the overlap integral

$$\mathrm{d}_{\mathrm{eff}} \propto \int\!\!\int_A \mathrm{d}(x,y)E_1(x,y)E_2(x,y)E_3(x,y)\mathrm{d}x\,\mathrm{d}y \qquad [19]$$

where the E's are the transverse field distributions of the three waves, the nonlinear response is often quite small. If the local nonlinearity $\mathrm{d}(x,y)$ can be engineered to maximize the integral, this problem can be alleviated. This may be thought of as transverse quasi-phase matching.

Waveguides can also be designed for Cerenkov phase matching where the phase velocity of the radiated wave is less than that of the polarization wave. Figure 14 shows an example. The emission angle is

$$\cos\theta = \frac{2k_\omega}{k_{2\omega}} = \frac{v_{2\omega}}{v_\omega} \qquad [20]$$

where the v's are phase velocities. The transverse momentum Λ must be supplied by the waveguide. In other words, the source harmonic polarization must have a transverse Fourier component with spatial frequency Λ. This is another example of transverse quasi-phase matching.

Another application of waveguide phase matching is in traveling wave electro-optic modulation, where the rf wave travels along an rf waveguide parallel to the light path. For maximum modulation bandwidth, the phase velocity of the rf wave should equal that of the light wave over the desired modulation bandwidth. Because the phase velocity of the rf wave in the bulk medium is usually faster than that of the light wave, the rf guide must be designed for a slow phase velocity.

Compensated Phase Matching (CPM)

Compensated phase matching is somewhat like QPM in that multiple crystal segments are used, but it differs by requiring that sequential crystal segments have ΔkL's of equal magnitude but opposite sign. Ideally the nonlinearity would be the same in all segments. Figure 15 shows the phasor diagram for one such arrangement, in this case with unequal nonlinearity in alternating segments. CPM is realized



Figure 13 Diagram of quasi-phase matching based on total internal reflection. Relative phases acquired by the waves upon total internal reflection, combined with the path lengths and possible changes in the value of d_{eff} for alternating legs, can be combined to achieve quasi-phase matching.



Figure 14 Cerenkov phase matched second harmonic generation. The phase velocity of the fundamental wave in the waveguide is greater than the phase velocity of the harmonic wave in the cladding.



Figure 15 Phasor diagram for four segments of a device with compensated phase matching device. The magnitude of ΔkL is equal in each segment but the sign of Δk alternates. The length of the E_n field from segment n is proportional to $\mathrm{sinc}(\Delta kL/2)$ so the net field ΣE_n must also be proportional to this function.

in walkoff compensated geometries where a sequence of crystals is arranged so $\Delta k = 0$ in each for a particular monochromatic plane wave. In the case of spatial walkoff compensation the walkoff direction in alternating crystals is reversed so the walkoff is exactly compensated in pairs of adjacent crystals. Tilting the input beams by a small amount changes the values of the Δk's in such a way that CPM is achieved. In the case of temporal walkoff compensation, temporal walkoff is reversed in alternating crystals, in which case tuning the input frequency leads to CPM. The advantage of CPM is that the acceptance bands, which will be discussed in the next section, are those of the individual crystal segments which are larger than those of a single crystal of equivalent length without walkoff compensation.

Spatial and Temporal Effects

Acceptance Bands

Our discussion to this point has been based on monochromatic plane waves. Real beams have spatial and temporal structure which means they can be decomposed into sets of monochromatic plane waves with tilted propagation directions relative to the nominal direction, and with detuned frequencies relative to the nominal frequency. As we showed above for monochromatic plane waves, there is a range of angles and frequencies, called the acceptance bands, over which $\Delta kL < 2\pi$. If the interacting beams' angular spectra and frequency spectra lie within these bands, the process is well phase matched for all angular and frequency components, and efficiency is maximized. This statement is equivalent to saying that if the spatial walkoff due to beam tilts and birefringence, and the temporal walkoff due to differing group velocities are small enough that the interacting beams stay well overlapped in space and time, the efficiency of energy transfer to the output channel does not suffer. Consider, for example, second harmonic generation of short pulses. The frequency acceptance bandwidth for the fundamental wave, $\Delta\omega_1$, is found using

$$\frac{\mathrm{d}(\Delta k)}{\mathrm{d}\omega_1}\Delta\omega_1 = \left(\frac{2\mathrm{d}k_2}{\mathrm{d}\omega_2} - \frac{2\mathrm{d}k_1}{\mathrm{d}\omega_1}\right)\Delta\omega_1 = \frac{2\pi}{L} \qquad [21]$$

Using the usual definition of the group velocity:

$$v_\mathrm{g} = \frac{\mathrm{d}\omega}{\mathrm{d}k} \qquad [22]$$

this can be written

$$\Delta\omega_1 = \frac{\pi}{L(1/v_{\mathrm{g}2} - 1/v_{\mathrm{g}1})} = \frac{\pi}{\tau_2 - \tau_1} = \frac{\pi}{\Delta\tau} \qquad [23]$$

where τ_1 and τ_2 are the passage times through a crystal of length L for the fundamental and harmonic pulses, and $\Delta\tau = (\tau_2 - \tau_1)$ is the temporal walkoff between the two. This shows that the acceptance bandwidth is approximately equal to the transform bandwidth of a pulse whose duration is equal to the temporal walkoff $\Delta\tau$. Input pulses shorter than $\Delta\tau$ will not convert efficiently because the fundamental and harmonic pulses do not remain overlapped as they propagate through the crystal. In the frequency domain it is said that pulses shorter than the $\Delta\tau$ have spectral widths larger than the acceptance bandwidth, meaning they are not well phase matched across their full spectra, and hence do not convert efficiently. Parallel arguments apply to spatial walkoff and angular acceptance bandwidths. Beams that do not remain spatially overlapped through the crystal do not convert efficiently. Equivalently, if the angular spectra of the beams exceed the acceptance angle, efficiency suffers.

Sometimes these notions are described in terms of an effective interaction length or an effective crystal length. For short pulses the effective interaction length is that for which temporal walkoff is equal to the pulse duration. Equivalently it is the length for which the acceptance bandwidth is equal to the spectral width of the pulse. Crystals shorter than this will have mixing efficiencies nearly equal to that expected for a phase matched process, while longer crystals have efficiencies that fall short of this expectation.

Focused beams

Focused Gaussian beams are a particularly important class of spatially structured beams. In passing through a focus, a lowest order Gaussian beam acquires a phase shift relative to an unfocused beam. The phase velocity near the focus is higher for the focused beam, leading to a phase shift of π through the focus. For second harmonic generation the phase shift of the second harmonic polarization is twice this, or 2π.

A second harmonic wave also acquires a phase shift of π, but this leaves a π phase shift between the harmonic polarization source wave and a freely propagating harmonic wave. The phasors representing harmonic radiation from symmetrically located points well before and well after the focus will therefore be 180° out of phase. Point pairs closer to the focus will have less severe cancelation, but it is not surprising that the maximum efficiency is achieved, not at $\Delta k = 0$, but for a slightly negative value Δk. The phase matching function $\mathrm{sinc}(\Delta kL/2)$ is shifted and distorted for focused beams. Its exact shape depends on the nature of the mixing process. For example, the phase matching peak is different for third harmonic generation and second harmonic generation, and it is different for mixing with small birefringence and mixing with large birefringence.

Phase Conjugation

Degenerate four-wave mixing

Some wave mixing processes are automatically phase matched. One example is phase conjugation by degenerate four wave mixing. This process creates a polarization wave that is the time reversed image of one of the input waves. Figure 16 compares the reflection from a conventional mirror with that from a phase conjugate mirror.

The mixing process shown in Figure 17 is one that can act as a phase conjugate mirror. Waves *f* and *b* are strong pump waves that are phase conjugates of one another. In their presence a weak signal field at the same frequency produces a polarization given by

$$P = sE_f E_b E_s^* \, e^{-i\omega t + i(\mathbf{k}_f - \mathbf{k}_b - \mathbf{k}_s)\cdot \mathbf{r}} \qquad [24]$$



Figure 16 Comparison of a normal and a phase conjugate mirror. The wavy lines represent the phases of the incident and reflected waves.



Figure 17 Phase conjugation via degenerate four wave mixing near a one photon resonance. Two counter propagating pump waves with fields E_f and E_b interact with a signal beam, E_s, to produce a polarization wave P_c where the frequencies obey $\omega_f - \omega_s + \omega_b = \omega_c$ (upper left), implying the *k*-vector of the polarization wave is given by $k_c = k_f - k_s + k_b$ (upper right). The lower diagram shows the grating induced by waves *f* and *s* that scatters wave *b* into the direction of *c*.

The two pump propagation vectors cancel one another leaving

$$P = sE_f E_b (E_s^* \, e^{-i\omega t - i\mathbf{k}_s \cdot \mathbf{r}}) \qquad [25]$$

The quantity in parentheses is the phase conjugate of the signal wave, so the polarization wave exactly phase matches a radiated conjugate wave.

Brillouin scattering

Other possibilities for automatic phase matching are processes that involve a stimulated wave in the nonlinear medium such as an acoustic wave (Brillouin scattering) or waves of coherent molecular vibration or rotation (Raman scattering). Phase conjugation, based on Brillouin scattering, is widely used to reduce phase distortions acquired on passing through an amplifier, for example. A single beam of light is focused into a material that has a high polarizability. Example media include high pressure gases Xe and SF_6, liquids acetone and freon, and fused silica. The conjugation process is not as simple to describe as it was in the case of four wave mixing because many acoustic waves can be generated. The key is that the phase conjugate wave has the highest gain under certain conditions and can dominate the Brillouin scattering process, so the reflected wave is nearly a phase conjugate of the incoming wave.

See also

Modulators: Acousto-Optics; Electro-Optics. **Nonlinear Optics, Basics:** Cascading; Four-Wave Mixing; Nonlinear Optical Phase Conjugation; $\chi^{(3)}$–Third-Harmonic Generation. **Nonlinear Sources**: Harmonic Generation in Gases. **Optical Parametric Devices:** Overview. **Optical Parametric Devices:** Optical Parametric Oscillators (Pulsed).

Phase Control: Phase Conjugation and Image Correction. **Photonic Crystals:** Nonlinear Optics in Photonic Crystal Fibers. **Scattering**: Raman Scattering.

Further Reading

Born M and Wolf E (1970) *Principles of Optics*. New York: Pergamon Press.

Boyd RW (1992) *Nonlinear Optics*. New York: Academic Press.

Dmitriev VG, Gurzadyan GG and Nikogosyan DN (1999) *Handbook of Nonlinear Optical Crystals*. Berlin: Springer-Verlag.

Hanna DC, Yuratich MA and Cotter D (1979) *Nonlinear Optics of Free Atoms and Molecules*. Berlin: Springer-Verlag.

Mills DL (1991) *Nonlinear Optics*. Berlin: Springer-Verlag.

Shen YR (1984) *The Principles of Nonlinear Optics*. New York: John Wiley & Sons.

Sutherland RL (1996) *Handbook of Nonlinear Optics*. New York: Marcel Dekker.

Yariv A and Yeh P (1984) *Optical Waves in Crystals*. New York: John Wiley & Sons.

Zel'dovich BY, Pilipetsky NF and Shkunov VV (1985) *Principles of Phase Conjugation*. Berlin: Springer-Verlag.

Zernike F and Midwinter JE (1973) *Applied Nonlinear Optics*. New York: John Wiley & Sons.

Pulse Compression via Nonlinear Optics

M F S Ferreira, University of Aveiro, Aveiro, Portugal

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Ultrashort pulses have a great potential in several areas of research and application, such as measurements of ultrafast physical processes, infrared time-resolved spectroscopy, and sampling systems, but they are also invaluable for communications. With increasing demands being put on the performance of optical fiber communications, the emphasis now is on producing a source of ultrashort optical pulses that can be used in high-bit rate and long-distance optical communication systems.

Several optical pulse compression techniques are described in the literature. These techniques utilize dispersion, possibly from gratings or prisms, simultaneously to compensate for chirp and achieve pulse compression. In fact, when a chirped optical pulse propagates in a linear dispersive medium, it acquires a dispersion-induced chirp. If the initial chirp is in the opposite direction to that imposed by the group-velocity dispersion (GVD), the two tend to cancel each other, resulting in the compression of the optical pulse.

Early work on optical pulse compression did not make use of any nonlinear optical effects. Only during the 1980s, when the use of single-mode silica fibers as nonlinear media became widespread, the self-phase modulation (SPM) effect was used to achieve pulse compression. It has led, in 1987, to the production of optical pulses as short as 6 fs in the 620 nm wavelength region. Such advances were possible, only after having understood the evolution of optical pulses in silica fibers.

We can consider two main categories of pulse compressors which make use of nonlinear effects in optical fibers: grating-fiber and soliton-effect compressors. In a grating-fiber compressor, the input pulse is propagated in the normal-dispersion regime of the fiber, which imposes a nearly linear, positive chirp on the pulse through a combination of SPM and GVD. The output pulse is then sent through a grating pair where it experiences anomalous GVD and gets compressed. In the case of a soliton-effect compressor, the fiber itself acts as a compressor without the need of an external grating pair. The input pulse propagates in the anomalous-GVD regime of the fiber and is compressed through an interplay between SPM and GVD. This compression mechanism is related to a fundamental property of the higher-order solitons. These solitons follow a periodic evolution pattern such that they go through an initial narrowing phase at the beginning of each period. If the fiber length is suitably chosen, the input pulses can be compressed by a factor that depends on the soliton order.

Grating-Fiber Compressors

The grating-fiber compressor is generally used at wavelengths $\lambda < 1.3\ \mu\text{m}$. At these wavelengths, optical pulses acquire a positive chirp across its entire width during their passage through conventional silica fibers. A schematic of a grating-fiber compressor in the double pass configuration is shown in Figure 1. After the propagation in the fiber, the optical pulse is sent through a grating pair, which provides the anomalous (or negative) GVD required to get the pulse compression.



Figure 1 Schematic representation of a grating-fiber compressor in the double-pass configuration. (Reproduced with permission from Agarwal GP (2001) *Applications of Nonlinear Fiber Optics*. San Diego: Academic Press.)

Different frequency components of an optical pulse incident at one grating are diffracted at slightly different angles. As a consequence, they experience different time delays during their passage through the grating pair, the blue-shifted components arriving earlier than the red-shifted ones. In the case of an optical pulse with a positive chirp, the blue-shifted components occur near the trailing edge of the pulse and the passage through the grating pair provides its compression.

A limitation of the grating pair is that the spectral components of the pulse are dispersed not only temporally but also spatially. As a consequence, the optical beam becomes deformed, which is undesirable. This problem can be avoided simply by using a mirror to reflect the pulse back through the grating pair. Mirror M_1, in Figure 1, performs this function. Reversing the direction of propagation not only allows the beam to recover its original cross-section, but also doubles the amount of GVD, thereby reducing the grating separation by a factor of 2. The mirror M_2 in Figure 1 is used to deflect the compressed pulse out of the compressor.

The phase shift acquired by the spectral component of the pulse at the frequency ω passing through the grating pair can be written in the form:

$$\phi_g = \phi_0 + \phi_1(\omega - \omega_0) + \frac{1}{2}\phi_2(\omega - \omega_0)^2 + \frac{1}{6}\phi_3(\omega - \omega_0)^3 + \cdots \qquad [1]$$

where ω_0 is the pulse center frequency, ϕ_0 is a constant, ϕ_1 is a constant delay, and ϕ_2 and ϕ_3 are parameters that take into account the GVD effects associated with the grating pairs. These parameters depend on the grating period (line spacing), as well as on the orientation and separation of the two gratings. In most cases of practical interest, the spectral width of the pulse satisfies the condition $\Delta\omega \ll \omega_0$ and the cubic and higher-order terms in eqn [1] can be neglected.

To achieve optimum performance from a grating-fiber compressor, it is necessary to optimize the fiber length, as well as the grating separation. Concerning the first aspect, the effects of both GVD and SPM during the propagation of the pulse inside the fiber must be considered. SPM alone determines a linear chirp only over the central part of an optical pulse. Since the grating pair compresses only this region, while a significant amount of energy remains in the wings, the compressed pulse is not of high quality in this case. The effect of GVD turns out to be important, since it broadens and reshapes the pulse, which develops a nearly linear chirp across its entire width. In these circumstances, the grating pair can compress most of the pulse energy into a narrow pulse.

The balanced effects of both GVD and SPM explain the existence of an optimum fiber length, z_{opt}, for maximum pulse compression. In fact, when the fiber length is less than z_{opt}, the SPM-induced chirp has not yet been linearized. On the other hand, when it is longer than z_{opt}, the SPM effects become negligible due to the GVD-induced pulse broadening.

If the input pulse is unchirped and presents a hyperbolic secant shape, the optimum fiber length for maximum pulse compression is well approximated by

$$z_{\text{opt}} \approx (6L_D L_{NL})^{1/2} \qquad [2]$$

where

$$L_D = \frac{T_0^2}{|\beta_2|} \qquad [3]$$

and

$$L_{NL} = \frac{1}{\gamma P_0} \qquad [4]$$

are length scales associated with the GVD and the SMP effects, respectively. In eqns [3] and [4], T_0 is the input pulsewidth, β_2 is the fiber GVD parameter, γ is the nonlinearity parameter of the fiber, and P_0 is the peak power of the input pulse.

If the input pulse presents a negative chirp, this must be compensated for by the positive chirp provided by the fiber. As a result, the optimum fiber length increases. The opposite occurs in the case of an input pulse with a positive chirp.

The optimum compression factor, F_{opt}, in the case of a grating-pair compressor, is given by

$$F_{\text{opt}} = \frac{T_{\text{FWHM}}}{T_{\text{comp}}} \approx 0.625\left(\frac{L_D}{L_{NL}}\right)^{1/2} \qquad [5]$$

where T_{FWHM} is the full width at half maximum (FWHM) of the input pulse ($T_{\text{FWHM}} \approx 1.76T_0$ for a hyperbolic secant pulse) and T_{comp} is the FWHM of the compressed pulse. Equations [2] and [5] provide a good estimate even for pulse shapes other than a hyperbolic secant as long as $\frac{L_{\text{D}}}{L_{\text{NL}}} > 100$.

The previous results were obtained neglecting the higher-order nonlinear and dispersive effects, which is acceptable for pulsewidths $T_0 > 0.1$ ps. However, when shorter pulses are used at the input, their spectral width $\Delta\omega$ is large enough that the cubic term in the expansion [1] must be taken into account. In this case, the compression factor turns out to be smaller than that given by eqn [5].

The third-order dispersion (TOD) of the grating pair, resulting from cubic term in eqn [1], has been compensated for in one experiment using a combination of gratings and prisms. Performing such compensation, a reduction of the pulsewidth to about 6 fs has been achieved. Such a pulse at 620 nm consists of only three optical cycles.

Even though the compression factor $F_{\text{c}} \propto \sqrt{P_0}$, the peak power of the input pulse must be kept below the Raman threshold to avoid the loss of pulse energy through the stimulated Raman scattering (SRS) process. If this condition is not then satisfied, besides the energy loss problem, the Raman pulse can interact with the input pulse through cross-phase modulation and deform the linear nature of the frequency chirp. As a result, the compression factor is reduced from the predictions of eqn [5].

Fiber Bragg Gratings

A uniform fiber Bragg grating (FBG) reflects light whose wavelength is within the stop-band centered at the Bragg wavelength. The GVD is anomalous on the high-frequency side of the stop-band and becomes normal on the low-frequency side. Near the stop-band edges, the grating exhibits large GVD. Since a FBG acts as a dispersive delay line, it can be used in place of the bulk-grating pair in a grating-fiber compressor, providing a compact all-fiber device. In fact, a typical 1 cm long fiber grating may provide as much dispersion as a bulk-grating pair with more than one meter spacing. However, the grating induced TOD can affect significantly the quality of the pulses when the optical frequency falls close to the edges of the stop-band.

The compression factor as well as the pulse quality can be significantly improved by using a FBG in which the grating optical period changes along its length – the so-called chirped fiber grating. In this case, different frequency components of the pulse are reflected from different regions of the grating. Such a device has been used since the mid-1990s to compensate for dispersion-induced broadening of pulses in fiber-optic communication systems, and compression factors above 100 have been achieved. In practice, the only disadvantage of a chirped fiber grating is that the compressed pulse is reflected rather than transmitted.

Soliton-Effect Compressors

Optical pulses at wavelengths exceeding 1.3 μm generally experience both SPM and anomalous GVD during their propagation in silica fibers. Such a fiber can act as a compressor by itself without the need of an external grating pair. In the case of a fundamental or first-order soliton, the effects of SPM cancel the effects of anomalous GVD perfectly, and the soliton propagates whilst preserving its hyperbolic secant shape in a lossless optical fiber. A higher-order soliton, on the other hand, changes its shape periodically as it propagates in a fiber. Such a soliton always experiences an initial pulse narrowing phase before recovering its original hyperbolic secant profile at integral multiples of the soliton period z_0, and this behavior is exploited to achieve pulse compression. Optimum compression is achieved when the higher-order soliton leaves the fiber just as it attains its narrowest width.

The evolution of a soliton of order N inside an optical fiber is governed by the nonlinear Schrödinger equation (NLSE), which can be written in the following form:

$$\mathrm{i}\frac{\partial q}{\partial \xi} + \frac{1}{2}\frac{\partial^2 q}{\partial \tau^2} + N^2|q|^2 q = 0 \qquad [6]$$

where q is the normalized amplitude, $\xi = z/L_{\text{D}}$, $\tau = T/T_0$, and the parameter N is the soliton order, given by

$$N^2 = \frac{L_{\text{D}}}{L_{\text{NL}}} = \frac{\gamma P_0 T_0^2}{|\beta_2|} \qquad [7]$$

The soliton period, z_0, is given by

$$z_0 = \frac{\pi}{2}L_{\text{D}} = \frac{\pi T_0^2}{2|\beta_2|} \qquad [8]$$

In writing eqn [6], the fiber losses were neglected, since fiber lengths employed in practice are relatively small. Even though higher-order solitons follow an exact periodic evolution only for integer values of N, eqn [6] can be used to describe pulse evolution for arbitrary values of N.

In practice, soliton effect compression is carried out by initially amplifying optical pulses up to the power level required for the formation of higher-order solitons. The peak optical power of the initial pulse required for the formation of the *N*th-order soliton is given by

$$P_\mathrm{N} = 3.11\frac{|\beta_2|N^2}{\gamma T^2_\mathrm{FWHM}} \qquad [9]$$

These *N*th-order solitons are then passed through the appropriate length of optical fiber to achieve a highly compressed pulse. The optimum fiber length, z_opt, and the optimum pulse compression factor, F_opt, of a soliton-effect compressor can be estimated from the following empirical relations:

$$z_\mathrm{opt} \approx z_0\left(\frac{0.32}{N} + \frac{1.1}{N^2}\right) \qquad [10]$$

$$F_\mathrm{opt} \approx 4.1N \qquad [11]$$

These relations are accurate to within a few percent for $N > 10$.

Compression factors as large as 500 have been attained using soliton-effect compressors. In fact, considering the same input pulse, the soliton-effect compressor provides a pulse compression that is larger with a fiber that is shorter than a grating-fiber compressor. However, the pulse quality is poorer, since the compressed pulse carries only a fraction of the input energy, while the remaining energy appears in the form of a broad pedestal. From a practical point of view, the pedestal is deleterious since it causes the compressed pulse to be unstable, making it unsuitable for some applications. Despite this, soliton-effect compressed pulses can still be useful because there are some techniques that can eliminate the pedestal.

One difficulty faced, when using the soliton-effect compressor, is that pulses with high peak power are required for the formation of high-order solitons in conventional fibers. As suggested by eqn [9], the use of dispersion-shifted fibers (DSFs) with small values of β_2 at the operating wavelength can reduce the peak power required for soliton generation by an order of magnitude. However, because the soliton period z_0 is inversely proportional to $|\beta_2|$ (see eqn [8]), eqn [10], indicates that longer lengths of DSFs will be required for solitons to achieve optimum compression. As a result, the total fiber loss experienced by those solitons will be larger and the loss-induced pulse broadening will have a significant impact on the compressor global performance.

Another problem introduced by the use of DSFs in soliton-effect compressors is the TOD, which generally degrades the quality of the compressed pulse. In the case of soliton-effect compressors using conventional optical fibers, the effects of TOD become significant only when the widths of the compressed pulse become very short ($\ll$1 ps). In DSFs, however, the relative importance of TOD is increased and those effects become more pronounced because the GVD parameter, β_2, is small. In this case, TOD is detrimental in the compression, even of pulses with widths of a few picoseconds, resulting in serious degradation of the optimum compression factor F_opt.

The result given by eqn [11] for the optimum compression factor holds only for the case of an ideal soliton-effect compressor, when high-order nonlinear and dispersive effects, such as intrapulse Raman scattering (IRS), TOD and self-steepening, are neglected. However, these effects cannot be neglected for the highly compressed pulses because of their subpicosecond widths and high intensities.

For not-too-short optical pulses (widths >50 fs) propagating not too close to the zero-dispersion wavelength of the fiber, the dominant higher-order effect is IRS, which manifests as a shift of the pulse spectrum toward the red side – the so-called soliton self-frequency shift. As a consequence, the group velocity is reduced and there is a delay of the optical pulse. This delay affects substantially the interplay between GVD and SPM that is responsible for pulse compression.

Interestingly, the IRS effect can be used to improve the quality of the compressed pulse, by removing the pedestal mentioned above. In fact, as a consequence of the change in the group velocity induced by the IRS effect, the sharp narrow spike corresponding to the compressed pulse travels more slowly than the pedestal and separates from it. Moreover, the pedestal can be removed by spectral filtering and a red-shifted, pedestal-free, and highly compressed pulse is then produced.

Compression of Fundamental Solitons

As described in the last section, the propagation of higher-order solitons provide a rapid compression method, but it suffers from the existence of residual pedestals. Some techniques can help to reduce or even eliminate those pedestals, but energy is always wasted in this process.

A less rapid technique that provides better pulse quality is adiabatic amplification of fundamental or first-order solitons, which are of primary importance in the domain of optical communications. Solitons have fixed area, so the increased energy from amplification is accommodated by an increase in power and a decrease in width. To avoid distortion, the amplification per soliton period cannot be too great.

The same effect as adiabatic amplification can be achieved using an optical fiber with dispersion that decreases along the length of the fiber. In fact, for optical solitons, a small variation in the dispersion has a similar perturbative effect as an amplification or loss: such a variation perturbs the equilibrium between the dispersion and nonlinearity in such a way that when, for example, the dispersion decreases, the soliton pulse is compressed. It can be seen from eqn [7] that if the value of $|\beta_2|$ decreases along the fiber and to keep the soliton order N ($N = 1$ for the fundamental soliton), the pulsewidth must indeed decrease as $|\beta_2|^{1/2}$. Hence, the use of fibers with variable dispersion is viewed as a passive and effective method to control optical solitons in soliton communication systems. Dispersion-decreasing fibers (DDFs), in particular, have been recognized to be very useful for high-quality, stable, polarization-insensitive, adiabatic soliton pulse compression and soliton train generation. These fibers can be made by tapering the core diameter of a single-mode fiber during the drawing process, and hence changing the waveguide contribution to the second-order dispersion.

In a DDF of certain length, the dispersion is monotonically and smoothly decreased from an initial value to a smaller value at the end of the length according to some specified profile. Provided the dispersion variation in the DDF is sufficiently gradual, soliton compression can be an adiabatic process where an input fundamental soliton pulse can be ideally compressed as it propagates, while retaining its soliton character and conserving the energy.

The evolution of the fundamental soliton in a DDF can be described by the following NLSE:

$$\mathrm{i}\frac{\partial q}{\partial \xi} + \frac{1}{2}p(\xi)\frac{\partial^2 q}{\partial \tau^2} + |q|^2 q = 0 \qquad [12]$$

where the variable coefficient $p(\xi) = |\beta_2(\xi)/\beta_2(0)|$ takes into account the variation of dispersion along the fiber. Using the transformations $s = \int_0^\xi p(y)\mathrm{d}y$ and $U = q/\sqrt{p}$, eqn [12] assumes the form:

$$\mathrm{i}\frac{\partial U}{\partial s} + \frac{1}{2}\frac{\partial^2 U}{\partial \tau^2} + |U|^2 U = \mathrm{i}GU \qquad [13]$$

where

$$G = -\frac{1}{2p}\frac{\mathrm{d}p}{\mathrm{d}s} \qquad [14]$$

Equation [13] shows clearly that the effect of decreasing dispersion is mathematically equivalent to the effect of an optical amplifier, adding a gain term to the NLSE. The effective gain coefficient G is related to the rate at which GVD decreases along the fiber.

Since decreasing dispersion is equivalent to an effective gain, a DDF can be used in place of a conventional fiber amplifier to generate a train of ultrashort pulses. To achieve such an objective, a continuous wave (CW) beam with a weak sinusoidal modulation imposed on it is injected into the DDF. The sinusoidal modulation can be imposed, for example, by beating two optical signals. As a result of the combined effect of GVD, SPM, and decreasing GVD, the nearly CW beam is converted into a high-quality train of ultrashort solitons, whose repetition rate is governed by the frequency of the initial sinusoidal modulation.

Different approaches have been developed to determine the optimum GVD profile and its dependence on the width and peak power of input pulses. In the case of picosecond soliton pulse compression, direct numerical simulations of the NLSE show that linear, Gaussian, and exponential dispersion profiles may all be used effectively to provide ideal, adiabatic compression, where the input pulse energy is conserved and remains localized within the pulse. In this case, the final pulse compression factor at the end of a certain length L of DDF is equal to the ratio of the initial to the final second-order dispersions:

$$F_\mathrm{c} = \frac{T_\mathrm{FWHM}}{T_\mathrm{comp}} = \frac{\beta_2(0)}{\beta_2(L)} \qquad [15]$$

Compression factors larger than 50 are possible launching input pulses with peak powers corresponding to the fundamental soliton into a DDF whose length is about one soliton period. This technique takes advantage of soliton-effect compression but requires lower peak powers and produces compressed pulses of better quality.

In the case of subpicosecond soliton pulses, the influence of higher-order nonlinear and dispersive effects must be accounted for. Some studies show that, in this case, the linear and Gaussian dispersion profiles are the most suitable to achieve high-quality, pedestal-free, adiabatic compression of fundamental solitons. However, in the presence of higher-order effects, the final compression factor is generally lower, and after reaching a maximum at a particular length of DDF, it decreases steadily. This can be explained in terms of pulse compression stabilization, which originates from a competition between the rate of dispersion decrease in the DDF and the rate of dispersion increase due to the combined effects of soliton self-frequency shift and third-order dispersion.

List of Units and Nomenclature

F_c	compression factor
F_{opt}	optimum compression factor
G	amplifier gain
L	fiber length (m)
L_D	dispersion length (m)
L_{NL}	nonlinear length (m)
N	soliton order
P_N	peak power of the Nth-order soliton (W)
P_0	pulse peak power (W)
q	normalized pulse amplitude
T_0	input pulse (s)
T_{comp}	compressed pulse FWHM (s)
T_{FWHM}	pulse full width at half maximum (s)
z_0	soliton period (m)
z_{opt}	optimum fiber length (m)
β_2	group-velocity dispersion coefficient ($s^2\ m^{-1}$)
γ	fiber nonlinearity coefficient ($W^{-1}\ m^{-1}$)
ξ	normalized distance
τ	normalized time
ϕ_g	phase shift induced by the grating pair (rad)
ω_0	pulse center frequency (rad s^{-1})
ω	optical frequency (rad s^{-1})
$\Delta\omega$	pulse spectral width (rad s^{-1})

See also

Chirped Pulse Amplification. **Fiber Gratings**. **Scattering:** Raman Scattering. **Solitons:** Soliton Communication Systems. **Ultrafast Laser Techniques:** Pulse Characterization Techniques.

Further Reading

Agrawal GP (1995) *Nonlinear Fiber Optics*, 2nd edn. San Diego: Academic Press.

Agrawal GP (1997) *Fiber-Optic Communication Systems*, 2nd edn. New York: John Wiley & Sons.

Agrawal GP (2001) *Applications of Nonlinear Fiber Optics*. San Diego: Academic Press.

Barty C, White W, Sibbett W and Trebino R (eds) (1998) Special issue on ultrafast optics. *IEEE Journal of Selected Topics on Quantum Electronics* 4: 157.

Buck JA (1995) *Fundamentals of Optical Fibers*. New York: John Wiley & Sons.

Kashyap R (1999) *Fiber Bragg Gratings*. San Diego, CA: Academic Press.

Mamyshev PV (1992) Generation and compression of femtosecond solitons in optical fibers. In: Taylor JR (ed.) *Optical Solitons – Theory and Experiment*. Cambridge, UK: Cambridge University Press.

Raman Lasers

M Santagiustina, Istituto Nazionale di Fisica della Materia, Università degli Studi di Padova, Padova, Italy

© 2005, Elsevier Ltd. All Rights Reserved.

The Raman effect bears the name of the Indian scientist Chandrasekhara V. Raman (1888–1970) who received the Nobel Prize in the year 1930 for the discovery, published in 1928, of this scattering phenomenon.

The Raman effect is an inelastic light scattering process, occurring in gaseous, liquid, and solid media. The frequency of the scattered photon can be either down-shifted or up-shifted and the result of the process is the generation of new radiation. Frequency down-shifted and up-shifted waves are respectively called Stokes and anti-Stokes waves. The energy difference between input and output photons is either absorbed by, or released from, the atoms or molecules of the medium, which are left in different energy states; jumps can be between electronic states, but more often they are among vibrational or rotational states. The upper energy state involved in the scattering process can be either a true energy state, and this case is referred to as resonant Raman scattering, or a virtual one. The off-resonance effect has a lower probability to occur and high-power beams are needed to observe it. The emission of anti-Stokes waves requires either an inverted Raman medium or particular four-wave-mixing phase-matching conditions to be satisfied in order to occur. The second condition is referred to as coherent anti-Stokes Raman scattering. Here we will consider mainly Stokes wave generation, which is the most common in Raman lasers.

When pumping is very hard, or a seed wave is provided, stimulated Raman scattering can also occur and a high percentage of the input pump radiation can be converted into Stokes, or anti-Stokes, radiation. The stimulated process efficiency, defined as the ratio between the output Raman wave energy and the input pump wave energy, depends on the imaginary part of the third-order nonlinear susceptibility coefficient and on the pump intensity. Stimulated Raman scattering observation dates back to 1962 during the pioneering studies with lasers sources by Woodbury and Ng; their experiment with a ruby laser was actually the first example of an intracavity Raman laser.

Since its discovery, Raman scattering has become a valuable tool for spectroscopy and a practical technique to extend laser light emission to wavelengths not directly generated by laser active materials. This fundamental property stems from the fact that Raman scattering does not require an upper energy state to occur. Hence, the frequency of the emitted radiation can be any, if a suitable incident radiation wavelength is provided. New frequencies are constrained only by the available powerful pump laser sources and by Raman medium shifts.

The frequency shifts provided by some of the materials that are most often used in Raman lasers are presented in Table 1. Finally, it is important to note that Raman scattering can also occur for the newly generated radiation through an identical process in which a Stokes photon is Raman scattered. This radiation, which is generated if the Stokes radiation intensity grows large enough, is referred to as a second-order Stokes wave. For very large pump intensity, a cascading process to several Stokes orders can take place, thus extending the range of generated frequencies to the far-infrared portion of the spectrum.

We will describe the design of Raman lasers that are most commonly used, as well as their performances, also taking into consideration the Raman medium that sets the main constraint to the laser characteristics. Continuous wave as well as pulse Raman lasers will be described and the tuning capability will be discussed.

Raman Shifters

The simplest conversion scheme is obtained when a Raman medium is placed at the output end of a laser. This single-pass setup, shown in Figure 1, provides a fairly efficient frequency shifter.

Single-pass amplification of the spontaneous scattering or of an injected seed copropagating with an intense pump is usually modeled by a couple of equations whose derivation, under a plane, continuous wave approximation, can be found in the

Table 1 Measured Raman frequency shifts and steady-state gain for some of the most important Raman media

Medium	*Frequency shift [THz]*	*Gain [cm/GW]*
Calcite ($CaCO_3$)	32.58(1)	5.5(1)
Lithium iodate ($LiIO_3$)	23.1–24.66(2)	4.8(3)
Barium nitrate ($Ba(NO_3)_2$)	31.46(4)	11(5)
Potassium gadolinium tungstate ($KGd(WO_4)_2$)	27.03 or 23(6)	6(6)
Silica fiber (SiO_2)	13.2(7)	0.01(7)
Hydrogen gas (H_2) ($p = 10$ atm, $T = 293$ K)	124.65(8)	1.53(9)
Nitrobenzene	40.35(10)	3(10)

(1) Pump wavelength 694 nm; from Zverev PG, Basiev TT and Prokhorov AM (1999) Stimulated Raman scattering of laser radiation in Raman crystals. *Optical Materials* 11: 335–352.

(2) Values refer to a propagation direction respectively perpendicular or orthogonal to the crystal axis; from Guadalberto GM and Arguello CA (1974) Raman spectra from oblique phonons in powdered samples. *Solid State Communications* 14: 911–914.

(3) Pump wavelength 1064 nm; from Falk J and Moshrefzadeh (1985) Oblique Raman and polariton scattering in kithium iodate. *IEEE Journal of Quantum Electronics* QE-21: 110–113.

(4) Pump wavelength 1064 nm; from Basiev TT, Sobol AA, Zverev PG, Ivleva LI, and Osiko VV (1999) Raman spectroscopy of crystals for stimulated Raman scattering. *Optical Materials* 11: 307–314.

(5) Pump wavelength 1064 nm; from Basiev TT, Voitsekhovskii VN, Zverev PG, *et al.* (1987) Conversion of tunable radiation from a laser utilizing an LiF crystal containing F_2^- color centers by stimulated Raman scattering in $Ba(NO_3)_2$ and $KGd(WO_4)_2$ crystals. *Soviet Journal of Quantum Electronics* 17: 1560–1561.

(6) Values refer respectively to two linear and orthogonal pump beams at the wavelength 1064 nm; from Zverev PG, Basiev TT and Prokhorov AM (1999) Stimulated Raman scattering of laser radiation in Raman crystals. *Optical Materials* 11: 335–352.

(7) Pump wavelength 1064 nm; from Stolen RH (1978), Fibre Raman lasers. In Ostrowsky D (ed) *Fiber and Integrated Optics*, NATO ASI Series B41. New York, Plenum Press, 157–182.

(8) From Bischel WK and Dyer MJ (1986) Temperature dependence of the Raman linewidth and lineshift for the Q(0)–Q(1) transition in normal and para H_2. *Physical Review* A 33: 3113–3123.

(9) Pump wavelength 1064 nm; from Ottusch JJ and Rockwell DA (1988) Measurements of Raman gain coefficients in hydrogen, deuterium and methane. *IEEE Journal of Quantum Electronics* 24: 2076–2080.

(10) Pump wavelength 694 nm; from Bloembergen N (1967) The stimulated Raman effect. *American Journal of Physics* 35: 989–1023.



Figure 1 Experimental setup of a single-pass Raman shifter.

literature:

$$\frac{dI_S(z)}{dz} = g_R I_S(z) I_P(z) - \alpha_S I_S(z) \qquad [1]$$

I_S, I_P are the continuous wave intensities of the Stokes and pump waves, z is the propagation distance, g_R the Raman steady-state gain coefficient, and α_S, α_P are the attenuation coefficients at the Stokes and pump frequencies. The Raman gain coefficients, whose general expression as a function of the microscopic material properties can be found in many textbooks, of some of the most commonly used Raman laser media are listed in Table 1.

For short propagation lengths the medium loss can usually be neglected, and if the pump beam is well collimated, the pump intensity can be considered as a constant. For a long interaction length or very absorptive media, the evolution of the pump intensity must also be considered. Though the pump beam is depleted by the scattering process an undepleted pump approximation is often used until high conversion is reached. Under this approximation, the evolution of the pump intensity is mainly governed by diffraction spreading, by losses or by both. In bulk media, single-pass scattered radiation has a coaxial component whose divergence is dictated by the geometry of the pump beam, because Stokes radiation is close to the diffraction limit. Besides this radiation, a nonaxial component can also be observed; this phenomenon stems from the well-known effect of conical emission, which is a phase-matched parametric process. If the Raman medium is within a waveguide, losses are usually the dominating effect. In the undepleted approximation, the evolution of the pump beam intensity as a function of the propagation distance z, either dictated by diffraction or by losses, is known. Then the general solution of eqn [1] is:

$$I_S(z) = I_S(0) \exp\left[g_R \int_0^z I_P(z')dz' - \alpha_S z \right] \qquad [2]$$

where $I_S(0)$ is either the input Stokes signal intensity or an equivalent spontaneous scattering intensity. Then, the amplification gain G of the Stokes beam in the single-pass shifter, for a medium of length L, is given by

$$G = \frac{I_S(L)}{I_S(0)} = \exp\left[g_R \int_0^L I_P(z')dz' - \alpha_S L \right] \qquad [3]$$

Though single-pass Raman shifters are appealing for their simplicity, their application is hampered by the high power necessary for reaching a sufficient efficiency due to the short interaction length that can be obtained, in particular in bulk media, where diffraction dominates. Q-switched pulsed pump lasers are often required, but the propagation in the Raman medium of very powerful pulses requires special precautions to prevent other linear and nonlinear effects occurring. In fact, optical breakdown, thermal and Kerr self-focusing, four-wave mixing, and Brillouin scattering can take place, thus reducing the efficiency of the converter. Precautions may include the optimization of the pump pulse duration, of the focusing, of the interaction length, and the control of the input beam spot size. The multipass configuration has also been exploited to avoid many of the single-pass configuration shortcomings; the typical experimental setup is presented in Figure 2. Note that neither the pump nor the Stokes wave are resonant within the cavity.

The primary advantage of the multipass configuration is the lowering of the pump power required to realize an appreciable conversion. This is due to the increased total gain coefficient, that has been found to be equal to

$$G_n = G\frac{1 - R^n}{1 - R} + (n - 1)\log R \qquad [4]$$

where G is the single-pass gain of eqn [3], R the reflectivity of the mirrors at the Stokes wavelength, and n the number of passes through the Raman medium. There are two main drawbacks of multipass Raman shifters that finally limit the conversion efficiency of this setup. The first is the simultaneous generation of many undesired and uncontrolled Stokes orders, because the first-order Stokes intensity grows rapidly during propagation. The second is the



Figure 2 Experimental setup of a multipass Raman shifter. Mirrors M$_1$ and M$_2$ reflect both Stokes and pump waves.

intensity decrease associated with the dispersion of pulses, in particular if the Raman medium is a solid. These problems have limited the applications of multipass shifters to hydrogen gas.

Raman Lasers

By placing the Raman medium into an optical cavity, Stokes radiation can be selectively enhanced and Raman oscillation takes place. The two main experimental setups, either with the Raman medium placed in an external cavity or within the pump laser cavity (intracavity), are represented in Figures 3 and 4. In some cases, for the intracavity configuration, the Raman medium may also be the host of the doping laser active material.

For the external resonator Raman laser, the reflectivity of the mirrors is such that they are almost transparent for the pump but highly reflective (resonant) for the shifted radiation. The threshold condition of Raman lasers can be obtained by requiring that the net round trip gain equals the total cavity losses. The net round trip gain, under the plane wave, steady-state, undepleted pump approximation, is given by the single-pass gain G, multiplied by a factor of two to account for the forward and backward amplification. In fact, Raman scattering takes place also between the pump and the counter-propagating Stokes wave reflected by mirror M_2. Losses are given by the medium contribution, which is already accounted for in eqns [2] and [3], and by the energy leakage from the mirrors. Assuming that the mean reflectivities of the mirrors, at the Stokes wavelength, are respectively R_1, R_2, then the threshold condition is $GR_1R_2 = 1$. Through eqn [3] we obtain

$$g_R \int_0^L I_P(z')\mathrm{d}z' - \alpha_S L = -\log(R_1R_2) \qquad [5]$$

Equation [5] can be used to evaluate the pump intensity because at threshold low depletion occurs and the approximation taken to obtain [5] is valid. Raman steady-state gain is not very different for gases, liquids and crystals, as shown in Table 1 and oscillation thresholds depend more on the interaction length and the focusing properties of the pump and Stokes beams. Nonetheless, the type of Raman medium imposes many practical constraints for laser design, which are addressed in the next paragraphs.



Figure 3 Experimental setup of an externally pumped Raman oscillator. Mirrors M_1 and M_2 are highly reflective for the Stokes wave but not for the pump wave.



Figure 4 Experimental setup of an intracavity Raman oscillator. Mirrors M_1 and M_2 are highly reflective for both the Stokes and the pump wave.

With gas media it is hard to maintain a high pump intensity over the entire length of the cell, which must be used to contain the gas. Usually gas cells can be from 5 to 30 cm long; this means that Q-switched pump lasers are required to set intensities above 10^4 GW m^{-2}, that is the typical threshold value of Raman oscillation. Continuous wave oscillation of gas Raman lasers is, nonetheless, possible when the pump wavelength is near a medium resonance. In fact, the imaginary part of the third-order non-linear polarization coefficient, to which the Raman gain is proportional, is enhanced near energy transitions because of the resonance in correspondence of that photon energy. The main limitations of this setup are that pump wavelengths are dictated by the Raman medium transitions, and thus also Stokes wavelengths are fixed, and finally conversion efficiency is usually low (about 5% is reported) possibly because of the high absorption. Off-resonance, continuous wave operation can also be attained by using high finesse cavities in a doubly resonant cavity. In fact, by resonating both Stokes and pump wave with high reflectivity mirrors ($R \geq 0.999$), the threshold intensity is lowered and conversion efficiency is high (about 35% has been demonstrated). In spite of the relatively high Raman gain and the large Stokes shifts obtainable, the exploitation of gas cell Raman oscillators is mainly hampered by the need of a high-pressure-resistant vessel and a constant gas flow. The latter is needed because of the low thermal conductivity of gases that might cause local temperature variations and thermal-optical distortions that diminish the output beam uniformity and stability. Moreover the repetition rate of pump pulses must be small (below 50 Hz) so as not to impose a too strong thermal load on the gas.

Liquid media suffer basically the same problems as gases and, moreover, they show higher non-linear refractive indices that result in strong self-focusing. This lens effect results in filamentation, optical breakdown, and high beam divergence. Often Raman liquids are also toxic and very volatile; their use has been slowly but steadily decreasing.

Solid media, in particular crystals, do not show many of the problems listed above and present the advantages of solid-state technology such as compactness, low maintenance, and opportunity of integration. The high density and the restricted atom motion result in high Raman steady-state gains and minimal line broadening. Precise resonance enhancement, as well as low threshold intensities, can be obtained by choosing an adequate mirror reflectivity spectral response. Pump intensities as low as 10^3 GW m^{-2} were reported for the oscillation of an external cavity Raman laser whose medium was a 5-cm-long, barium nitrate (see Table 1) crystal, with mirror reflectivity $R = 0.49$ at the Stokes wavelength. Though the intensity threshold is about an order of magnitude smaller than for gas Raman lasers, Q-switched input pump pulses are still required. Solid-state Raman lasers can be easily forced to oscillate on a $\mathrm{TEM}_{0,0}$ mode with divergence close to the diffraction limit even with multimode pumps. Moreover the Stokes beam is subject to a very complex clean-up process; this can be basically explained by the fact that the Stokes beam, growing from the spontaneous emission, does not retain the pump spatial characteristics. Pulse duration is equal to or slightly less than the input one. Conversion efficiency, which depends strongly on mirror reflectivity, can reach 60%, where saturation occurs due to higher-order Stokes wave generation. Solid-state Raman lasers can be easily forced to oscillate also at these higher-order Stokes frequencies if mirror reflectivity is large enough at the relative wavelengths. Second- and third-order Stokes conversion efficiencies of 30% and 20% have been reported.

The theoretical determination of the cavity pump and Stokes fields does not have an analytical solution. For continuous wave or long Q-switched pulsed lasers, eqns [1] must be extended to include all forward and backward Stokes and pump waves and boundary conditions due to the mirrors must be imposed. This problem can only be solved numerically.

The experimental setup of intracavity Raman lasers is shown in Figure 4; both the Raman and the laser medium are placed within the cavity and sometimes the two media coincide. This is, for example, the case of potassium gadolinium tungstate which can be doped with neodymium ions (see Table 1). The cavity is usually resonant for both the pump and the Stokes waves; very high conversion efficiency (up to 80%) is attained when special dichroic coatings are provided such that pump output is suppressed (high-finesse cavity for the pump). Besides the nearly diffraction-limited property of output radiation and clean output beams that are common characteristics of all Raman lasers, enhanced brightness is also observed in this setup. This effect is probably due to the high thermal loading, the consequent linear and nonlinear lens effects, and also to a short pulse generation mechanism that increases output beam intensity. This regime can be reached by reducing the Stokes cavity length with respect to the pump cavity length. A first setup is to use an additional dichroic intracavity mirror that is transparent for the pump but highly reflective for the Stokes; an alternative setup exploits a double ring cavity configuration as depicted in Figure 5.

The principle governing the compression can be explained as follows. The optical paths of the pump and Stokes pulses are made different by an amount ΔL. Then the Stokes pulse generated within the Raman medium, once re-injected into the cavity from mirror M_{S1}, will overlap with an undepleted portion of the recirculating pump pulse. Hence, another Stokes pulse is generated at each round trip, until the pump pulse is completely depleted; the Stokes output finally consists of a train of pulses of duration $\Delta L/c$, at a repetition rate equal to the cavity round-trip. This mechanism leads to pulses as short as the limit imposed by the Raman gain bandwidth. In fact, when the pulse duration becomes comparable to the inverse of the gain bandwidth, transient effects take place because of the delay in the nonlinear medium response. Ring Raman lasers have been obtained with



Figure 5 Experimental setup of an intracavity, double ring, Raman oscillator. Mirrors M_{S2}, M_{S3}, M_{P2}, and M_{P3} are highly reflective respectively for the Stokes and the pump wave. M_{S1}, M_{P1} are partially reflective respectively for the Stokes and pump wave.

gases (e.g., hydrogen) and crystal media (barium nitrate and lithium iodate).

Another commonly used experimental setup is that of synchronously pumped ring Raman lasers. In such devices, whose typical setup is sketched in Figure 6, a new input pump pulse is synchronized with the output Stokes pulse thus enhancing the conversion within the Raman medium.

Though electronic trigger detection is needed to lock the pump pulse time repetition rate to a multiple or submultiple of the cavity round-trip, synchronously pumped Raman lasers are relatively simple, stable, high repetition rate sources of radiation. Very compact and reliable synchronously pumped Raman lasers can be realized with optical fibers; in this case the feedback of the ring resonator can be realized by means of a fiber directional coupler. The device, besides the high integration achieved by the all-fiber technology, can also be continuously tuned over a large bandwidth.

Continuous tuning of the same laser source is a very desirable property; the Raman lasers so far described can generate radiation at wavelengths restricted to a few values. In fact, output spectral lines can be changed either by replacing the Raman medium, or the pump laser, or by exploiting cascade Raman scattering or finally resonating a different vibrational line of the same material (if there are many as for example in hydrogen gas); all these cases require substantial cavity changes. Frequency switching without setup changes is attained only in case of potassium gadolinium tungstate. For this medium there exist two independent directions, orthogonal to the crystal optical axis, for which the Raman shifts are different if the pump polarization changes. Then, the wavelength selection is just a matter of controlling the input pump polarization. Though Raman lasers can greatly expand the wavelength range of available laser sources, controlled, continuous tuning of the same Raman laser over a certain frequency band can be obtained only in a few particular cases.



Figure 6 Experimental setup of a synchronously pumped, ring, Raman oscillator. Mirrors M_2 and M_3 are highly reflective for both the Stokes and the pump wave. M_1 is partially reflective for both the Stokes and pump wave.

Wavelength tuning can be attained by selecting the direction of propagation in polar crystals (like lithium niobate and lithium iodate). Different directions allow for wavevector matching of polariton scattering at different frequencies. Also phase matching of parametric interactions, like four-wave mixing, is a possible technique to attain wavelength tuning. However, such Raman lasers cannot operate at maximum gain, and this fact decreases the output energy, the conversion efficiency, and the stability, and increases the pump intensity threshold. Continuous tuning with an external control parameter is attained in the spin-flip Raman semiconductor laser. Semiconductors are Raman media that can be exploited to build far-infrared or even submillimeter Raman lasers, with pump intensity thresholds that are comparable with those of gas and liquid media. Though frequency shifts are fixed, under normal conditions, tuneable operation can be achieved if the semiconductor is placed in a magnetic field. Each energy level of an electron in the solid is, in fact, split into two, depending on the orientation of the electron spin with respect to the magnetic field. When there is a transition involving Raman scattering, the electron spin can change its direction. Then the wavelength of the laser can be continuously varied by changing the magnetic field applied. Tuning over a range of several micrometers in the infrared has been attained and spin-flip Raman lasers have been developed with semiconductors like InSb, $Hg_{0.77}Cd_{0.23}Te$, and $Pb_{0.88}Sn_{0.12}Te$. Use of this technique is severely limited by the need for magnetic field sources.

The simplest method to achieve tuneable radiation is through the use of a material that shows a broad Raman linewidth. Inhomogeneous broadening of the energy level is a well-known effect that takes place in noncrystalline solid media, such as glasses. Though line broadening is accompanied by a decrease in the steady-state Raman gain of about two orders of magnitude with respect to a crystalline medium, this disadvantage can be over-compensated by the increase in the Raman medium length that can be of 3 or 4 orders of magnitude. In fact, glasses are commonly exploited to make optical waveguides, in particular optical fibers, that present very low optical absorption coefficients, in the near-infrared part of the spectrum (1200–1600 nm).

Optical fiber Raman lasers based on silica telecommunication fibers are very versatile, compact, and simple to implement. In principle the setup is not very different from the corresponding external cavity or intracavity Raman lasers so far presented; however, fiber lasers show the great advantage of an integrated, all-fiber technology.

Cavity mirrors can be replaced by fiber Bragg grating reflectors (Figure 7) that can be constructed with a very well-defined spectral reflectivity, thus allowing fine enhancement or suppression of the desired wavelengths. By splicing the Raman fiber, which can be several hundred meters long, with the gratings, the net losses are very low, finally decreasing the pump intensity threshold. The pump threshold for first-order Stokes generation can be easily as low as 200 mW; this means that diode lasers can be used for pumping. Moreover, the need for cavity alignment is eliminated, the laser stability increased and the construction simplified. This simplification allows us to build, much more easily than by using bulk optics, nested multiple resonant cavities, to generate higher-order Stokes beams (Figure 8).

Continuous-wave lasing of up to six Stokes orders has been reported for a fiber Raman laser of this type, with a total injected power of about 7 W. Another key advantage of Bragg gratings is that their reflectivity can be adjusted by means of a piezoelectric stretching of the fiber support; this allows one to control the output intensity of all waves. As previously mentioned, ring cavities can also be constructed by exploiting an all-fiber technology, if feedback is provided by a fiber directional coupler (Figure 9).



Figure 7 Experimental setup of a continuous-wave, all-fiber, Raman oscillator. FBG_{S1} are fiber Bragg gratings highly reflective for both the first Stokes wave.



Figure 8 Experimental setup of a continuous-wave, all-fiber, *n*th-order Stokes, Raman oscillator. FBG_{Si} are fiber Bragg gratings highly reflective for the *i*th Stokes wave.

Pulsed operation of fiber Raman lasers has been obtained too; due to the long interaction length, Q-switched pump lasers are no longer needed but rather mode-locked sources can be used. This means that trains of very short laser pulses, down to the hundreds of femto-second regime, can be obtained from fiber Raman lasers, the limit being represented by the Raman bandwidth, which is as large as about 7 THz, at the half maximum, in silica fibers. Propagation of short and intense laser pulses in an optical fiber may induce several other nonlinear effects, like self-, cross-phase modulation, and four-wave mixing. Besides nonlinearity, linear dispersion and velocity mismatch become important too, due to the long propagation. All these linear and non-linear effects limit the Stokes pulse quality. In more detail: self- and cross-phase modulations lead to the spectral broadening of both pump and Stokes waves; broadening is asymmetric, because of the contemporary action of group velocity mismatch. In fact during the propagation the Raman pulse walks off the pump pulse, because of velocity mismatch, and this induces an asymmetry in gain depletion and in nonlinear index modulation. The final outcome is that Stokes waves can be asymmetric both in time and in frequency, and also highly chirped. Four-wave mixing is usually negligible, if phase-matching conditions are not imposed and Brillouin scattering is not an issue for short pulses. Very symmetric and low chirped pulses are attained as soon as the fiber Raman laser is working in the soliton regime, that is when compensation between the dispersion and the nonlinear phase shift occurs. Synchronously pumped, fiber Raman, soliton lasers are able to provide 200-fs pulses, at various wavelengths and with very high conversion efficiency (50%). Intracavity fiber Raman lasers have



Figure 9 Experimental setup of an all-fiber, ring Raman oscillator.

also been realized by doping the fiber with neodymium, erbium, or ytterbium ions.

The extremely broad Raman spectral linewidth of the glass allows for broadband tuning of the emitted wavelength. For continuous and pulsed wave operation the change in the peak Stokes wavelength can be attained through an intracavity frequency selective element, like for example a prism or a grating. In this case tuning is not obtained in an all-fiber configuration but rather with bulk optical elements and thus additional lenses or objective are needed to collimate the Stokes wave at the fiber ends. The experimental setup is shown in Figure 10.

The laser can be continuously tuned, over about 6 THz, by adjusting the prism or grating rotation. All-fiber Raman laser tuning is possible in a double ring configuration with an inserted optical filter, whose experimental setup is shown in Figure 11. Stokes and pump waves are counterpropagating in the Raman fiber; the Stokes wave frequency is selected by the tuneable optical filter.



Figure 10 Experimental setup of a tuneable, fiber Raman oscillator. Mirrors M_1 and M_2 are highly reflective for the Stokes wave but not for the pump wave. L_1 and L_2 are collimating lenses or objectives. The tuning prism is rotated to control wavelength selection.

The devices of Figures 10 and 11 stop emitting Stokes radiation for frequencies at which the Raman gain has decreased to a level such that laser threshold is higher than the pump intensity. Due to the fact that Raman gain in fibers is almost constant over about 3 THz, tuning within this frequency range does not lead to any sensible decrease in conversion efficiency. For synchronously pumped ring fiber Raman lasers another technique, named time dispersion tuning, can be used. The experimental setup is shown in Figure 12.

The output fiber end is placed on a moveable mount, that controls the relative delay between the Stokes pulse and the new pump pulse at the fiber input. Since Stokes pulses are dispersed during fiber propagation, to each time slot within a pulse there corresponds a certain portion of the Stokes spectrum. By properly delaying the time of injection of the Stokes pulse back into the fiber the most powerful part of the pump pulse is overlapped to a different part of the Stokes pulse, and this causes a preferred amplification of certain frequencies with respect to others. The shift of the Stokes peak wavelength $\Delta\lambda$ is given by:

$$\Delta\lambda = \frac{\Delta l}{cLD(\lambda)} \qquad [6]$$

where Δl is the translation step, c the speed of light, L the fiber length, and $D(\lambda)$ the fiber dispersion at the Stokes wavelength λ. A total tuning range of 10 nm can be obtained with this technique that can also be used as a test measurement of fiber dispersion.



Figure 11 Experimental setup of a double-ring fiber Raman oscillator. OC_1 and OC_2 are fiber optic circulators, and TOF is a tuneable optical filter.



Figure 12 Experimental setup of a time dispersion tuned, ring fiber Raman oscillator. L_1 and L_2 are lenses or objectives. The output collimating lens L_2 and the fiber end are mounted on a translation stage to control wavelength selection by time delaying the re-entrant Stokes pulse.

Applications

Raman lasers have found a large variety of applications. Gas and liquid Raman lasers are fundamental tools for spectroscopic investigation. Solid-state Raman lasers have been shown to be very powerful, eye-safe sources for light detection and ranging (LIDAR) and medical applications. Fiber Raman lasers are exploited for long-haul fiber optics transmission. They can be either sources of short pulses and solitons or high-power continuous-wave sources at multiple wavelengths for subsequent link-distributed Raman broadband amplification.

List of Units and Nomenclature

Amplification gain	[dimensionless]
Efficiency	[dimensionless]
Energy	[J]
Frequency	[Hz]
Intensity	[W m^{-2}]
Length	[m]
Loss coefficient	[m^{-1}]
Power	[W]
Raman bandwidth	[Hz]
Raman gain	[m W^{-1}]
Reflectivity	[dimensionless]
Wavelength	[m]

See also

Fiber and Guided Wave Optics: Dispersion; Light Propagation; Measuring Fiber Characteristics; Nonlinear Effects (Basics); Overview. **Fiber Gratings**. **Optical Amplifiers:** Optical Amplifiers Long-Haul Transmission Systems. **Imaging:** Lidar. **Laser-Induced Damage of Optical Materials**. **Nonlinear Optics, Basics:** Four-Wave Mixing. **Magneto-Optics:** Interband Magnetoabsorption, Cyclotron Resonance, Spin Flip Raman Scattering. **Nonlinear Optics, Applications:** Pulse Compression via Nonlinear Optics; Phase Matching; Self-Focusing and Related Effects (Solitons and Multiphoton Absorption). **Optical Materials:** Optical Glasses. **Solitons:** Temporal Solitons. **Scattering:** Raman Scattering; Stimulated Scattering. **Spectroscopy:** Nonlinear Laser Spectroscopy; Raman Spectroscopy.

Further Reading

Band YB, Ackerhalt JR, Krasinski JS and Heller DF (1989) Intra-cavity Raman lasers. *IEEE Journal of Quantum Electronics* QE-25: 208–213.

Basiev TT and Powell RC (eds) (1999) Special issue on solid-state Raman lasers. *Optical Materials* 11: 301–390.

Bloembergen N (1967) The stimulated Raman effect. *American Journal of Physics* 35: 989–1023.

Eckhardt G (1966) Selection of Raman laser materials. *IEEE Journal of Quantum Electronics* QE-2: 1–8.

Grasiuk AZ and Zubarev IG (1978) High power tunable IR Raman lasers. *Applied Physics* 17: 211–232.

Kaiser W and Maier M (1972) Stimulated Rayleigh, Brillouin and Raman spectroscopy. In: Arecchi FT and Schulz-Dubois D (eds) *Laser Handbook*. Amsterdam: North Holland.

Koechner W (1999) *Solid-state Laser Engineering*. Berlin: Springer-Verlag.

Pask HM (2003) The design and operation of solid-state Raman lasers. *Progress in Quantum Electronics* 27: 3–56.

Stolen RH (1978) Fibre Raman lasers. In: Ostrowsky D (ed.) *Fiber and Integrated Optics*, NATO ASI Series B41, pp. 157–182. New York: Plenum Press.

Suto K and Nishizawa J (1994) *Semiconductor Raman Lasers*. Norwood, MA: Artech House.

Weber A (1979) *Raman Spectroscopy of Gases and Liquids*. Topics in Current Physics, vol. 11, Berlin: Springer.

Self-Focusing and Related Effects (Solitons and Multiphoton Absorption)

R L Sutherland, Science Applications International Corporation, Dayton, OH, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

When an intense beam of light with axial symmetry propagates in a medium possessing a nonlinear index of refraction, it will induce its own lens in the medium and be focused. This phenomenon, first discovered just a few years after the invention of the laser, is called self-focusing. It is one of many phenomena under the general classification of self-action, which includes such effects as self-trapping, self-bending, self-phase modulation, and self-steepening. This general class of phenomena involves action on the beam of light induced by the beam itself: light causes a change in an optical property of the medium, which in turn produces an effect back on the light beam. We will discuss the mechanisms responsible for self-focusing in nonlinear optical media and the resultant action on the optical beam. In this we will see how the topics of self-trapping and self-phase modulation are intimately connected to self-focusing. This will lead to a discussion of related effects as well as many potential applications.

It is instructive to first review the properties of a conventional thin lens, illustrated in Figure 1. By 'thin', we mean that just before and just after the lens, the beam size and shape are approximately the same. However, the phase of the optical wave is changed on passage through the lens. We apply the paraxial (aberrationless) approximation where only rays that lie near the lens axis are considered. In this treatment the spherical surfaces of the lens are approximated as parabolic surfaces. For a symmetric double-convex lens (as shown in Figure 1), this phase change is

$$\Delta\varphi(r) = -k(n-1)\frac{r^2}{R} \equiv -\frac{kr^2}{2f}, \quad f^{-1} = (n-1)\frac{2}{R} \qquad [1]$$

where n is the index of refraction of the lens material, and R is the radius of curvature of the lens surfaces. The light beam has a wavevector $k = \omega/c$, where ω is the frequency and c the speed of light in a vacuum. The phase retardation is a maximum on the lens axis (z) and decreases quadratically with the radial coordinate r. In other words, the phase advances quadratically with distance from the axis and forms a spherical, converging wave that comes to focus on the z-axis a distance f (the focal length) from the lens.



Figure 1 Focusing with a conventional lens, a graded-index (GRIN) lens, and a nonlinear self-focusing lens.

Next consider a graded-index (GRIN) lens, also illustrated in Figure 1. This is a flat slab of material with thickness L and an inhomogeneous index of refraction given by $n(r) = n_0(1 - 1/2\alpha^2 r^2)$. The index has a maximum (n_0) on the lens axis and decreases quadratically with radial distance from the axis. The constant α is a measure of the rate of the index change with r. Upon passage of light through a GRIN lens, the phase change is

$$\Delta\varphi(r) = -kn_0\alpha^2 L\frac{r^2}{2} \equiv -\frac{kr^2}{2f}, \quad f^{-1} = n_0\alpha^2 L \qquad [2]$$

Because of the parabolic nature of the index distribution, the phase retardation again decreases quadratically with r and thus forms a converging spherical wave. Notice that for both the conventional and GRIN lenses, the optical thickness of the lens is parabolic. In the conventional lens the index is constant, but the physical thickness varies continuously. In the GRIN lens, the physical thickness remains constant while the index varies continuously. Both produce the same kind of focusing action.

Finally, consider a flat slab of homogeneous material that has a nonlinear index of refraction. Light of intensity I induces a change in the refractive index given by $\Delta n = n_2 I$. The parameter n_2 is called the nonlinear refractive index coefficient and has physical units of cm^2 W^{-1}. There are other definitions of n_2 given in the literature where the index change is given in terms of the square of the electric field, which would obviously have different physical units. We will adopt the intensity form of n_2 in this discussion. We now assume the light incident on this slab is a plane wave with a Gaussian intensity distribution given by $I(r) = I_0 \exp(-2r^2/w^2)$ as shown in Figure 1. I_0 is the peak intensity along the z-axis, and w is the radius of the beam at $1/e^2$ of the peak intensity. Consistent with the paraxial approximation, we expand the exponential function, keeping only the first two terms, to yield $I(r) \approx I_0(1 - 2r^2/w^2)$. This parabolic approximation to the intensity is sketched as the dotted curve in Figure 1. The index distribution induced in the medium by the intensity approximately follows this parabolic shape, and the resultant phase change is

$$\Delta\varphi(r) = -k4n_2I_0\frac{L}{w^2}\frac{r^2}{2} \equiv -\frac{kr^2}{2f},\qquad f^{-1} = \frac{4n_2I_0L}{w^2} \tag{3}$$

Note the similarity to the GRIN lens, with the association of the peak index $n_0 \rightarrow n_2I_0$, and $\alpha^2 \rightarrow 4/w^2$. We can say that the nonlinear medium acts like a GRIN lens with an intensity-dependent focal length. However, this correspondence is only accurate within the parabolic approximation, and the nonlinear lens can introduce significant aberrations to the focal properties of the full beam.

In the paraxial approximation, the conventional, GRIN, and nonlinear lenses all have the same effect on an incident beam of light. Although we have considered only plane parallel incident waves, it should be obvious that the GRIN and nonlinear lenses will produce analogous effects on converging and diverging wavefronts as the conventional lens. The effect of a stack of nonlinear lenses in an optical train can also be analyzed in the same way as a stack of conventional lenses, with the exception that the focal length of each lens will depend on the local intensity and hence size of the beam. Finally, we note that if we change the sign of R, α^2, or n_2, we obtain a negative focal length. This is a diverging lens, and in the nonlinear optics realm the effect is called self-defocusing.

Nonlinear Index of Refraction

The concept of an intensity-dependent refractive index has its roots in the power series expression of the nonlinear dielectric polarization P in terms of the electric field E of the optical wave, which in its simplest form is

$$\begin{aligned} P &= \varepsilon_0\left(\chi^{(1)}E + D^{(2)}\chi^{(2)}E^2 + D^{(3)}\chi^{(3)}E^3 + \cdots\right) \\ &= \varepsilon_0\left(\chi^{(1)} + D^{(2)}\chi^{(2)}E + D^{(3)}\chi^{(3)}E^2 + \cdots\right)E \end{aligned} \tag{4}$$

where $\chi^{(m)}$ $(m = 1, 2, 3\ldots)$ is called the m-th order susceptibility. The quantity $D^{(m)}$ is called the degeneracy factor and is 3 for $m = 3$ in the self-focusing case. This leads directly to the definition of a nonlinear susceptibility $\chi(E)$. All materials have first- and third-order susceptibilities. Centrosymmetric materials (e.g., gases, liquids, cubic crystals) do not possess a second-order susceptibility. Here, we will consider only centrosymmetric media and briefly discuss second-order materials later.

The refractive index is $n = [1 + \chi(E)]^{1/2}$. Consequently, the linear index (small electric field) is $n_0 = (1 + \chi^{(1)})^{1/2}$. The leading nonlinear term in $\chi(E)$ is generally small. Expanding the square root in a binomial series, the first nonlinear term in the refractive index can be approximated by $3\chi^{(3)}E^2/2n_0$. Since $I = 2\varepsilon_0 n_0 cE^2$, we see that

$$n = n_0 + n_2I \tag{5}$$

where $n_2 = 3\chi^{(3)}/4\varepsilon_0 n_0^2 c$. Third-order (cubic) materials that exhibit an intensity-dependent refractive index described by eqn [5] are called Kerr or Kerr-like.

Several physical mechanisms produce a refractive index of the form given in eqn [5]. A list of the significant ones is presented in Table 1. We emphasize that these mechanisms lead to eqn [5] over a limited range of intensity. For example, in materials where the main mechanism is electronic state population redistribution, when the incident intensity becomes comparable with the saturation intensity, the index begins to saturate (i.e., the change of index with

Table 1 Physical mechanisms responsible for the nonlinear index of refraction

Mechanism	*Typical n_2 ($cm^2\ W^{-1}$)*	*Typical sign*	*Typical response time (seconds)*
Electronic polarization	$\sim10^{-16}$–10^{-15}	+	$\sim10^{-15}$
Molecular orientation			
Isotropic liquids	$\sim10^{-15}$–10^{-14}	+	$\sim10^{-12}$
Liquid crystals	$\sim10^{-4}$–10^{-3}	+	$\sim10^{-3}$–10^{-2}
Electrostriction	$\sim10^{-13}$–10^{-12}	+	$\sim10^{-9}$
Population redistribution			
Atomic vapors (ω below resonance)	$\sim10^{-10}$–10^{-9}	−	$\sim10^{-8}$
Atomic vapors (ω above resonance)	$\sim10^{-10}$–10^{-9}	+	$\sim10^{-8}$
Semiconductors	$\sim10^{-6}$	+	$\sim10^{-8}$
Band filling (semiconductors)	$\sim10^{-6}$–10^{-4}	±	$\sim10^{-8}$–10^{-7}
Exciton saturation (quantum wells)	$\sim10^{-4}$	−	$\sim10^{-8}$
Thermal	$\sim10^{-8}$	±	$\sim10^{-4}$

intensity becomes sublinear). The simple expression in eqn [5] no longer applies. These types of effects can be important and will be discussed later. Finally, we mention that other mechanisms exist that produce self-focusing related effects, but they are not Kerr-like and will be briefly discussed later.

We learn from Table 1 that values of n_2 range over several orders of magnitude. High-intensity lasers are required to observe the effects of small optical nonlinearities. Hence pulsed lasers are often used in self-focusing applications. Laser pulse widths can generally range from 100 s of nanoseconds to 10 s of femtoseconds. Consequently, one must keep in mind the response time of the mechanism/material when analyzing experiments. If the pulse width is long compared to the response time, a quasi-steady-state self-focusing regime results. If the pulse is too short, transient effects will appear. Also, as one goes to longer response time mechanisms, lower intensities can be used. In some cases it is even possible to use cw lasers.

Self-Lensing

Thin nonlinear media can be employed in self-lensing applications, where self-focusing is used to modify the far field properties of a beam, just as a conventional lens would do, but with effects dependent on the beam intensity. Gaussian beams are usually employed in the paraxial approximation.

A popular technique employing this effect to measure the magnitude and sign of n_2 is the Z-scan. A typical experiment is illustrated in Figure 2. A thin nonlinear medium is scanned axially between a focusing lens and an aperture in the far field. Consider a material with positive n_2. When the sample is close to the lens the intensity is too low to induce significant self-lensing. As the sample approaches the focal point of the lens, the intensity rises and a positive self-lens is induced that focuses the beam more strongly. This displaces the focus to the left, causing the beam to spread out more in the far field and less power to pass through the aperture. As the sample passes to the right of the focal point, the positive self-lens reduces the divergence of the beam so that more power is passed through the aperture. Near the focal point the self-lens is strongest, but a thin lens at this point has no effect on the beam passing through the far-field aperture. The measured aperture transmittance as a function of scan-position Z is sketched in Figure 2. The peak and valley of this dispersion-shaped curve will be interchanged for a negative n_2. For a small aperture and fixed power of the laser, the difference between the peak and valley transmittance is proportional $|n_2|$.

The same experimental configuration is also popular for measuring small absorption coefficients or thermo-optic coefficients ($\mathrm{d}n/\mathrm{d}T < 0$ for most materials). Under steady-state conditions (cw beam), the thermal n_2 is given by

$$n_2 = \frac{\alpha\tau}{\rho C}\frac{\mathrm{d}n}{\mathrm{d}T} \qquad [6]$$

where α is the absorption coefficient, τ is the thermal diffusion time, ρ is the mass density, and C is the specific heat. This technique is extremely sensitive and can easily be observed, for example, with a ~1 mW laser pointer and a 1 cm cuvette filled with minute quantities of ink or food coloring dissolved in methanol.

This combination of self-lensing and a hard aperture has also been put to use in devices. One such device is the optical power limiter. A typical configuration is similar to the Z-scan experiment in Figure 2, with the sample fixed near the lens focal point. Thick media in the focal region have also been used. At sufficiently low optical power, the medium acts like a flat window. As the input power rises, self-lensing sets in and spreads the beam out at the aperture, limiting the transmitted power. The higher the incident power gets, the more the beam spreads. The result is a transmitted power that is clamped below a preferred level. Thermal lensing has been used for cw beams, while positive Kerr



Figure 2 A Z-scan experiment. The transmittance through the aperture as a function of the position (Z) of the thin nonlinear medium is sketched at the right.

self-lensing has been employed for Q-switched lasers.

A less obvious but very important application of this configuration is for mode-locking lasers (see Figure 3). Mode-locking is a coherent phenomenon that locks the relative phase of multiple longitudinal modes in a laser having a broadband gain profile. These stabilized modes interfere to form a train of short pulses with pulsewidth inversely proportional to the gain bandwidth. A common technique for passively mode-locking a laser is to insert a saturable absorber into the laser cavity. A saturable absorber blocks low-power light, keeping the round-trip gain below the oscillation threshold, but transmits high-power light as the absorption coefficient saturates. Thus the mode-locked condition is favored for gain and oscillation since the peak power of the pulses is high. It turns out that transverse spatial modulation, due to self-focusing combined with an aperture, can produce the same type of effect in a laser cavity. The laser rod acts as both the gain medium and nonlinear lens. For example, titanium: sapphire ($Ti:Al_2O_3$) has $n_2 = 3 \times 10^{-16}\ \mathrm{cm^2\ W^{-1}}$. Thus, in a $Ti:Al_2O_3$ laser the rod produces self-lensing that modifies the beam shape propagating through an intracavity aperture. The loss due to the aperture is intensity dependent, as in the Z-scan. Therefore, the net round-trip gain of the cavity is low for low-power but high for high-power pulses, and the mode-locking condition is fulfilled. These types of lasers are called Kerr lens mode-locked (KLM) lasers. KLM lasers are generally not self-starting, but can be self-sustaining. They, therefore, require some active means of starting the mode-locking. Ultrashort pulses (<100 fs) have been obtained with a cw KLM $Ti:Al_2O_3$ laser. For pulsewidths this short, the simple quasi-steady-state self-focusing picture is not entirely adequate to describe the dynamics. Other factors, such as group-velocity dispersion (GVD) and self-phase modulation (SPM), must be considered. Moreover, since the laser rod is typically several millimeters long, it is more appropriate to model it as a thick rather than a thin nonlinear lens.

Beam Trapping

When an intense beam propagates in a thick nonlinear medium, a question arises as to the ultimate fate of the beam. A possibility that has intrigued researchers for a long time is diffractionless propagation of a beam over long distances. In other words, self-focusing exactly balances diffraction to force the beam into a nonlinear waveguiding mode. This phenomenon is called beam trapping or self-trapping. A simplified analysis of a uniform beam captures the essential physics (see Figure 4). The refractive index inside the beam is higher than outside by eqn [5]. Therefore, light incident on the 'interface' at the edge of the beam can experience total internal reflection if its angle of incidence exceeds the critical angle, dependent on the value of the nonlinear index. If the complement of the critical angle matches the diffraction angle of the beam, the beam is trapped in its own self-induced waveguide. The critical power $\mathscr{P}_{cr2}$ at which this occurs is given in Table 2. The condition for beam trapping is independent of beam size since both diffraction and self-focusing depend on beam area, and these size effects cancel.

A detailed solution of the wave equation for a Gaussian beam using the parabolic approximation yields a slightly different critical power $\mathscr{P}_{cr1}$, also given in Table 2. Numerical analyses of the wave


High reflector
Gain medium
Saturable absorber
Output coupler
High reflector
Gain/self-lensing medium
Aperture
Output coupler
Absorber prevents light oscillation/gain
Aperture prevents light oscillation/gain
High loss, below threshold, not mode-locked
High peak power pulses bleach path through absorber
High peak power pulses self-focus light through aperture
Low loss, above threshold, mode-locked

Figure 3 Laser mode-locking using a saturable absorber (left) and self-lensing in combination with an intracavity aperture (right).


$n_I = n_0$
$n_{II} = n_0 + n_2 I$
$\theta_{cr} = \sin^{-1}(n_I/n_{II})$
$\theta_d = 0.61\lambda/2n_0 w$
$2w$

Figure 4 Self-trapping conditions for a uniform beam of intensity I and width $2w$ in a Kerr medium.

Table 2 Critical power for beam trapping (collapse)

Gaussian beam (parabolic approximation)	$\mathscr{P}_{cr1} = \frac{1}{2}\frac{\lambda^2}{4\pi n_0 n_2}$
Gaussian beam ('whole beam' collapse)	$\mathscr{P}_{cr2} \approx \frac{(1.22\pi)^2}{8}\frac{\lambda^2}{4\pi n_0 n_2}$
Townes soliton, lower bound for arbitrary beam shape	$\mathscr{P}_{crT} \approx 1.86225\frac{\lambda^2}{4\pi n_0 n_2}$
Arbitrary beam (upper bound)[a]	$\mathscr{P}_{cr3} = G[f]\frac{\lambda^2}{4\pi n_0 n_2}$

[a] $G[f]$ defined in text.

equation for a whole Gaussian beam have shown for incident power such that $\mathscr{P}_{cr1} < \mathscr{P} < \mathscr{P}_{cr2}$ the beam comes to a 'soft' focus and then diffracts (partial beam focusing), but for $\mathscr{P} > \mathscr{P}_{cr2}$ the whole beam catastrophically collapses (i.e., the beam approaches a singularity). Catastrophic self-focusing has been observed experimentally, but as the beam collapses the intensity becomes so large that additional nonlinear effects, such as multiphoton absorption and stimulated Raman scattering, come into play. These effects rob the beam of energy and terminate the collapse. At this stage the beam will then spread by diffraction.

A more rigorous analysis of this problem is obtained by examining the nonlinear wave equation in the slowly varying amplitude approximation (propagation along z), but including the transverse variation of the wave. If the electric field of the optical wave is of the form $E(\mathbf{r}) = A(\mathbf{r})\exp(ikz)$, where now $k = n_0\omega/c$, then the wave equation can be written as

$$2ik\frac{\partial A}{\partial z} + \nabla_\perp^2 A + 4\varepsilon_0 n_2 ck^2|A|^2 A = 0 \qquad [7]$$

where the transverse Laplacian $\nabla_\perp^2$ is $\partial^2/\partial x^2 + \partial^2/\partial y^2$ in rectangular Cartesian coordinates, or $\partial^2/\partial r^2 + (1/r)\partial/\partial r$ in cylindrical coordinates (assuming azimuthal symmetry). This equation is known as the nonlinear Schrödinger equation (NLSE). In normalized coordinates $\xi = x/w$, $\eta = y/w$, $\rho = r/w$, $\zeta = z/2kw^2$, where w is the input beam radius, and $\psi = 2kw(c\varepsilon_0 n_2)^{1/2}A$, eqn [7] takes the normalized form of the NLSE:

$$i\frac{\partial\psi}{\partial\zeta} + \nabla_\perp^2\psi + |\psi|^2\psi = 0$$
$$\nabla_\perp^2 = \frac{\partial^2}{\partial\xi^2} + \frac{\partial^2}{\partial\eta^2} = \frac{\partial^2}{\partial\rho^2} + \frac{1}{\rho}\frac{\partial}{\partial\rho} \qquad [8]$$

A waveguiding (i.e., diffractionless) solution of the form $\psi(\zeta,\rho) = \exp(i\zeta)R(\rho)$ exists for eqn [8], where $R(\rho)$ is a solution of

$$\nabla_\perp^2 R - R + R^3 = 0,\quad R'(0) = 0,\quad R(\infty) = 0 \qquad [9]$$

$R(\rho)$ is known as the Townes soliton. It has a radial profile similar to a Gaussian but differing in fine detail. Since the Townes soliton exactly balances diffraction and self-focusing, it carries a critical power $\mathscr{P}_{crT}$ given by the expression in Table 2. For comparison, $(1.22\pi)^2/8 = 1.83624$. Therefore, $\mathscr{P}_{crT}$ and $\mathscr{P}_{cr2}$ differ by only about 1%. However, the Townes soliton is unstable. An analysis of the solutions of the NLSE shows that a beam will not catastrophically collapse (i.e., its intensity will not blow up) if its power is less than $\mathscr{P}_{crT}$. Thus $\mathscr{P}_{crT}$ forms a lower bound for the critical power. An upper bound can also be found from analysis of the NLSE. It depends on the input beam profile $[\psi(\rho,0) \propto f(\rho)]$ and is given as $\mathscr{P}_{cr3}$ in Table 2. The quantity $G[f]$ characterizes the input beam profile and is given by

$$G[f] = \frac{2\int|f|^2\rho\mathrm{d}\rho\int|\nabla f|^2\rho\mathrm{d}\rho}{\int|f|^4\rho\mathrm{d}\rho} \qquad [10]$$

For example, a Townes soliton, a Gaussian beam, and a hyperbolic secant beam yield $G = 1.86225$, $G = 2$, and $G = 1.86257$, respectively. Thus, if the beam power is such that $\mathscr{P}_{crT} \leq \mathscr{P} \leq \mathscr{P}_{cr3}$, the beam may collapse, but it will definitely collapse if $\mathscr{P} > \mathscr{P}_{cr3}$. We note that if the input beam is elliptical, with ellipticity $e = b/a$ (where a and b are the semi-major and semi-minor widths, respectively), then

$$\mathscr{P}_{crT}(e) \approx \left(0.6 + 0.2\frac{e^2+1}{e}\right)\mathscr{P}_{crT} \qquad [11]$$

This expression is accurate to within 1.5% of numerical simulations of the NLSE, and also holds well for Gaussian input beams.

The conclusion is that there is no stable self-trapped (2 + 1)-D beam (two diffracting dimensions, one propagating dimension) in a Kerr medium. The beam will diffract, blow up in a finite distance, or go through a single focusing–defocusing cycle. For an incident plane wave, the distance from the input plane to the blowup point is (assuming a Gaussian input)

$$z_{\mathrm{f}} \approx \frac{0.369\pi w^2/\lambda}{(\mathscr{P}/\mathscr{P}_{\mathrm{cr2}})^{1/2} - 0.858} \qquad [12]$$

where the approximation holds well for $\mathscr{P} > 1.2 \times \mathscr{P}_{\mathrm{cr2}}$.

Why, then, does self-trapping appear to occur in Kerr media? Time integrated photographs show what appears to be the formation of a filament, and laser damage tracks in solids follow the shape of a self-trapped filament. This can be explained in terms of the moving focus model. In the quasi-steady-state approximation, each time slice of the pulse comes to focus independently at different times and positions. Figure 5 shows a series of snapshots of a Gaussian spatial and temporal pulse (assume axial symmetry), where the peak power of the pulse is greater than $\mathscr{P}_{\mathrm{cr2}}$. Slices of the pulse with $\mathscr{P} > \mathscr{P}_{\mathrm{cr2}}$ will come to a focus at a finite distance $z_{\mathrm{f}}(\mathscr{P})$, which can be approximated by eqn [12]. The time at which that focus appears is determined by the time it takes for that slice of power $\mathscr{P}$ to propagate to the input plane ($z = 0$) plus propagate to $z_{\mathrm{f}}(\mathscr{P})$. As illustrated in Figure 5, slice 1a takes the minimum time to come to a focus. At a later time slices 2a and $2'$ come to focus simultaneously but at different positions, 2a to the left and $2'$ to the right of 1a, since $\mathscr{P}(2\mathrm{a}) > \mathscr{P}(1\mathrm{a})$ and $\mathscr{P}(2') < \mathscr{P}(1\mathrm{a})$. The solid curves in the left of Figure 5 are the trajectories of the beam rays showing where each slice will come to focus. Slice 2b, having the same power as 2a, comes to focus at the same position as 2a, but later in time, and so on. The original focus thus appears to split in two, with one branch propagating forward and the other backward. The backward branch comes to a turning point when slice 4 of maximum power in the pulse center comes to focus, then propagates forward as time slices in the back part of the pulse come to focus. The motion of the foci traces out the U-shaped curve shown to the right in Figure 5. The time-integrated picture that appears like a filament is thus just the tracks of moving foci.

The question remains, do conditions exist under which stable self-trapped beams can form? The answer is yes, and these types of beams are called spatial solitons. The (1 + 1)-dimensional NLSE admits the fundamental spatial soliton solution:

$$A(x,z) = A_0 \operatorname{sech}(x/w)\exp(iz/2kw^2)$$
$$|A_0|^2 = \frac{1}{2\varepsilon_0 c n_2 (kw)^2} \qquad [13]$$



Figure 5 Moving focus model of apparent filament formation by quasi-steady-state self-focusing of a pulsed Gaussian beam. The series of snapshots on the left illustrate when and where different time slices of the pulse come to focus. The tracks of moving foci trace out the curve shown on the right.

The wave given by eqn [13] propagates along z with a constant width w along the x-axis. Such a (1 + 1)-D soliton can be formed in a slab waveguide, as illustrated in Figure 6, consisting of a nonlinear thin film deposited on a linear slab, where the wave is confined along y but can diffract along x. These types of solitons have been confirmed experimentally and shown to be quite robust. They are stable against perturbations and propagate as a self-induced waveguide. Since a soliton changes the refractive index where it propagates, it can also attract and guide other beams. The interactions or 'collisions' of solitons are an active area of current research. Intriguing potential applications include all-optical reconfigurable interconnects for telecommunications and optical computing based on the properties of soliton collisions.

Although (2 + 1)-D spatial solitons are not stable in ideal Kerr media, they can be in Kerr-like media with a saturating nonlinearity. For example, a two-level saturable absorber (e.g., an atomic vapor) at a wavelength tuned above the natural absorption frequency will exhibit a positive Kerr-like response at low intensity ($I \ll I_{\text{sat}}$), but then saturates as $(1 + I/I_{\text{sat}})^{-1}$ for $I \sim I_{\text{sat}}$ or larger, where I_{sat} is the saturation intensity. This can form a stable trapped beam, as was first reported in 1974 for a cw laser in Na vapor, because as the beam self-focuses and the intensity rises, the nonlinear index levels off asymptotically until a balance between diffraction and focusing is reached. This type of situation is stable against perturbations, but may undergo almost periodic focusing–defocusing cycles.



Figure 6 Spatial soliton propagation in a nonlinear slab waveguide.

Spatial solitons employing mechanisms other than the Kerr nonlinearity are also being vigorously studied. One of these is the photorefractive effect. An illustration of the generation of a slab soliton is shown in Figure 7. A Gaussian beam is focused to a line (e.g., by a cylindrical lens) and propagated as an extraordinary wave along the optic (z) axis of a uniaxial photorefractive crystal. A dc electric field is also applied along z. Charge carriers are generated in the slab beam by photo-ionization of dopant atoms and drift in the dc field. The lower resistivity in this region causes the voltage drop to be smaller and hence the field to be lower. The field induces a refractive index change by the Pockels effect ($\Delta n = -n_0^3 |r_{\text{eff}} E|/2$, where r_{eff} is the effective Pockels coefficient and n_0 is the background index). The index change is negative, but is reduced in magnitude where the field is lower. The index change depends on the local intensity, and the


Background light
Line focus (parallel to y) of incident laser
I(x)
x
Carrier generation, drift, screening
⊗ E_dc, Optic axis
Pockels effect
E(x)
Δn(x)
x
x
Electric field distribution, E(x), directed along optic axis, z

Figure 7 Mechanism of slab soliton formation in a photorefractive material.

photorefractive mechanism produces an effective saturable self-focusing nonlinearity. (There are a limited number of charge carriers, and the field cannot be reduced below zero.) This produces a waveguide that traps the slab beam, which then propagates without spreading. Thus the photorefractive soliton is stable. This effect can be observed with milliwatt-level cw lasers, but the space-charge field takes time to build up to a steady state (typically of the order of seconds). Needle (circularly symmetric) solitons have also been observed by launching a TEM_{00} Gaussian beam in a photorefractive crystal, but the theoretical description is not as simple. Other types of spatial solitons and other mechanisms have been explored using the photorefractive and photovoltaic effects. The reader is referred to the literature for a more in-depth discussion.

Another mechanism useful for soliton formation is cascaded second-order (quadratic) effects. This includes such phenomena as second-harmonic generation (SHG) and other frequency conversion processes. Consider SHG with imperfect phase matching. (The reader is referred to other articles discussing harmonic generation and phase matching.) A fundamental (F) wave generates its second harmonic (SH), but because of dispersion $n(\omega)$, the two waves travel at different phase velocities. The SH(2ω) beats with the F(ω) wave to generate, via the second-order nonlinear polarization, another wave at ω that adds to the incident F wave. This produces a net phase shift of the F wave that accumulates continuously as the waves propagate together and periodically exchange power; this is called cascading. In the nondepleted pump approximation, this phase accumulation can be expressed as

$$\Delta\varphi = -\frac{\Delta k z}{2}\left\{1 - \left[1 + \left(\frac{2\kappa\sqrt{I}}{\Delta k}\right)^2\right]^{1/2}\right\}$$
$$\kappa = \frac{\omega\chi_{\mathrm{eff}}^{(2)}}{\sqrt{2\varepsilon_0 n_0^3 c^3}} \qquad [14]$$

where $\chi_{\mathrm{eff}}^{(2)}$ is an effective second-order susceptibility (dependent on crystal symmetry, polarization vectors, and propagation direction), $\Delta k = 2k(\omega) - k(2\omega)$ is the phase mismatch, I is the intensity of the F wave, and n_0 is the approximate refractive index for both F and SH waves. Although not due to a refractive index change, this phase change produces a self-focusing effect for a bell-shaped intensity. For a small enough pump intensity or sufficiently large phase mismatch, an equivalent n_2 can be approximated by

$$n_2 = \frac{\omega(\chi_{\mathrm{eff}}^{(2)})^2}{2\varepsilon_0 n_0^3 c^2 \Delta k} \qquad [15]$$

Note that the sign of n_2 depends on the sign of Δk. For $I \sim (\Delta k/2\kappa)^2$ or larger, eqn [15] is not valid and eqn [14] must be used. Note that the equivalent index change is then sublinear with respect to I, and soliton formation is stable. When pump depletion cannot be ignored, the F and SH coupled-wave equations must be solved numerically to analyze soliton dynamics. Figure 8 illustrates the difference between a beam diffracting normally and a diffractionless quadratic soliton. When an F beam is launched in a nonlinear medium, it does not immediately form a soliton, but evolves into one, shedding some energy in the process. Note that this soliton does not consist of a single frequency beam, but depends on the nonlinear coupling between the ω- and 2ω-waves that continuously exchange energy as the beams propagate. For this reason, these solitons are called simultons.

Self-Focusing in Space–Time

The moving focus model describing the self-focusing of optical pulses becomes inadequate when dispersion effects must be included. This is true in the case of ultrashort pulses (typically ~100 fs or less). To properly describe the propagation of a pulse with group velocity v_g, eqn [7] must be modified by $\partial A/\partial z \rightarrow [\partial/\partial z + (1/v_g)\partial/\partial t]A$. In addition, to include the effects of GVD, a term $-k_2 k(\partial^2 A/\partial t^2)$ is added, where $k_2 = (\partial^2 k/\partial\omega^2)$ is the GVD coefficient. For anomalous GVD, $k_2 < 0$. Taking this to be the case and defining another normalized coordinate $\tau = (t - z/v_g)/(|k_2|k)^{1/2}w$, the normalized NLSE (eqn [8]) becomes

$$i\frac{\partial\psi}{\partial\zeta} + \left(\frac{\partial^2}{\partial\xi^2} + \frac{\partial^2}{\partial\eta^2} + \frac{\partial^2}{\partial\tau^2}\right)\psi + |\psi|^2\psi = 0 \qquad [16]$$

Note the complete symmetry in eqn [16] between the transverse space (ξ, η) and time (τ) variables. There is thus a correlation between diffraction (space) and dispersion (time). The corresponding phenomenon to self-focusing is self-phase modulation (SPM). This effect denotes the additional phase retardation experienced by a pulse in a Kerr medium due to its time-dependent intensity: $\Delta\varphi(t) = -(\omega_0/c)n_2 I(t)z$, where ω_0 is the center (carrier) frequency of the pulse. SPM produces new frequencies ($\mathrm{d}\varphi/\mathrm{d}t$) that are red-shifted on the leading edge of the pulse and blue-shifted on the trailing edge. The frequency shifts in a self-focused filament can be quite sizeable and create a large continuum (a white light pulse) that


Normal beam propagation (diffraction)
Beam
Intensity distribution
Simulton propagation (diffractionless)
SH(2ω)
F(ω)
F – fundamental
SH – second harmonic

Figure 8 Comparison of normal beam propagation to simulton propagation in a quadratic nonlinear medium. In a simulton, the F and SH waves periodically exchange energy as they co-propagate in the medium.

can be used for ultrafast spectroscopy. In a medium with normal GVD the pulse spreads in time because blue frequencies in the trailing edge travel slower than red frequencies in the leading edge. However, for anomalous GVD the opposite is true, and the pulse can 'focus' or collapse in time.

The simultaneous spatiotemporal collapse of a beam of ultrashort pulses leads to the consideration of $(3+1)$-D soliton generation, where the third 'transverse' dimension is time. While the NLSE leads to unstable solitons for transverse dimensions >1, a saturating nonlinearity could possibly bound the collapse and lead to the formation of stable, diffractionless, dispersionless pulses. These types of pulses are called light bullets. Light bullets have a particle-like nature and display many interesting, exotic properties that could lead to ultrafast switching rates for optical digital logic systems in telecommunications and computing.

The saturable nature of self-focusing in quadratic nonlinear media makes them natural candidates in the search for light bullets, and $(2+1)$-D spatiotemporal simultons have been observed in crystals of lithium iodate. The drawback of ultrashort pulse simulton generation in quadratic media is the added complications of requiring anomalous GVD at both ω and 2ω, and dealing with the effects of group-velocity mismatch (GVM). The phenomenon of GVM involves the different group velocities of the F and SH pulses, which makes them walk away from one another. Without the physical overlap of these two pulses, the simulton will cease to exist. By tilting the amplitude front of the pulses with respect to their phase fronts, it is possible (over a limited distance) to compensate pulse walkoff due to GVM with spatial walkoff due to the birefringence of the quadratic medium. Accomplishing this, however, requires the beam to be in the form of a narrow stripe, and the propagation distance over which pulse overlap is good is greater for a longer stripe. This can be achieved by focusing a beam onto the medium with a cylindrical lens. The simulton then propagates without a change of width temporally or spatially (in 1-D). This is not a light bullet, however, because the confinement is not in all three dimensions.

The elliptic nature of the diffraction–dispersion operator in eqn [16] makes pulse collapse a possibility in nonlinear media with anomalous GVD. With normal GVD, the operator is hyperbolic. For such a medium, it has been predicted and observed that instead of collapsing, a self-focused pulse in a Kerr medium will split in time. Since the red-shifted frequencies generated at the front of the pulse travel faster than the blue-shifted frequencies produced at the back, the front of the pulse separates from the back part. Collapse of the pulse, as well as self-trapping, is not favored under conditions of pulse splitting.

Given this property of the NLSE, it is somewhat surprising that the reportedly first observation of light bullets was in a quadratic medium with normal GVD.

Focusing a beam of Gaussian profile in both space and time near the entrance to a lithium triborate crystal under the condition of a large positive phase mismatch, the pulses propagated without spread temporally or spatially (2D) over a distance ~20 mm (the length of the crystal). However, the pulse did not retain its shape, but evolved into a so-called 'X-wave', or X-shaped soliton. A generic X-shaped soliton (or, strictly speaking, simulton) is shown in Figure 9. The pulse has a conical (clepsydra, or hourglass-shaped) 3D structure with a central hump and slowly decaying conical tails. Interestingly, an X-shaped pulse has been shown to propagate without spreading in a linear optical medium exhibiting normal GVD. But such a pulse must be specially contrived at the input and may be impossible in many cases. In a quadratic nonlinear medium with normal GVD, the X-shaped light bullet appears to form spontaneously. The physics of this evolution lies buried in the coupled wave equations for the fundamental and second harmonic. In the strong phase-mismatched SHG process, weak perturbations in the waves at specific spatial and temporal frequencies can grow exponentially. The hyperbolic nature of the diffraction–dispersion operator with normal GVD leads to amplification of conical wave perturbations with frequencies approaching that of the X-wave. This amplification of the proper frequency components acts as a trigger that drives the evolution of the Gaussian spatiotemporal input pulse into the X-wave. This basic shape has been confirmed in experiments that outline the spatiotemporal intensity profile of the pulse exiting the rear of the crystal.

Other Related Effects (Multiphoton Nonlinearities)

At this point we should note that the susceptibility is frequency dependent. Optical waves couple principally to bound electrons, which can only occupy discrete energy levels. When the photon energy $\hbar\omega$ is nearly resonant with a difference between these energy levels, the dielectric response of the medium is enhanced. This well-known property of linear optics, accounting for absorption of light as well as normal and anomalous dispersion, is also applicable in nonlinear optics. The third-order susceptibility is actually a complex number. A sketch of its real and imaginary parts is given in Figure 10, the real part relating to n_2. The imaginary part is associated with optical loss, if positive, or gain when it is negative. In the present case the frequency dependence of the susceptibility displays a resonance (i.e., peak of the imaginary part) at a frequency $\omega = 2\omega_0$. Referring to Figure 10, when the optical frequency is significantly less than ω_0, the imaginary part of $\chi^{(3)}$ is small compared to the real part and nonlinear refraction dominates. However, when the frequency is comparable to ω_0, the resonance at $2\omega_0$ plays a major role. The real part of $\chi^{(3)}$ is resonantly enhanced, but the imaginary part signifies loss: two photons are simultaneously absorbed. This is called two-photon absorption (2PA). The intensity-dependent absorption loss per unit length is given by $\alpha_2 I$, where α_2 is called the two-photon absorption coefficient (often designated by β) and has physical units of cm W^{-1}.



Figure 9 Generic shape of an X-wave light bullet as a function of space and retarded time ($t - z/v_g$) coordinates. The light bullet has radial symmetry.



Figure 10 Sketch of the real and imaginary parts of the frequency-dependent third-order susceptibility $\chi^{(3)}$ illustrating a two-photon resonance.

In many materials at a variety of optical frequencies, 2PA will naturally accompany self-focusing. Since these two phenomena are both intensity dependent, while one decreases the intensity and the other increases it, there is an obvious interplay between the two. We illustrate the effect of 2PA in Figure 11 by comparison of the phase retardance of a Gaussian beam (in the parabolic approximation) with and without 2PA in a 'thin' medium, for which the size of an optical beam is nearly constant (diffraction ignored). Obviously, $\Delta\varphi(r)$ does not reproduce the parabolic shape when strong 2PA is present. Actually, it is possible to have multiphoton absorption (MPA) of m photons with corresponding coefficient α_m (related to $\chi^{(m)}$). The effects of 3PA and 4PA are also shown in Figure 11. 2PA, or more generally MPA, distorts the phase and modifies the focusing properties of the beam. This shows up in the Z-scan, for example, as a distortion of the dispersion-like transmittance curve: the valley is deeper and the peak is suppressed.

The reason for this phase distortion is that nonlinear absorption changes the shape of the beam: absorption is stronger where the intensity is higher. For MPA, the intensity at position z in a thin medium is

$$I(r,z) = \frac{I(r,0)}{\left[1 + (m-1)\alpha_m I^{m-1}(r,0)z\right]^{1/(m-1)}} \qquad [17]$$

The other obvious effect of MPA is that it reduces the strength of self-focusing since it robs power from the beam. The interplay of the two effects shows up more in thick media where the beam can diffract and change size. When self-focusing is dominant at the front of the medium, the intensity will start to blow up as the beam collapses, but the intensity becomes so large that MPA becomes much stronger. This robs energy from the beam and can stop or reverse the collapse. When MPA is dominant at the start, the beam will still self-focus, but MPA flattens the beam in the center causing the edges of the beam to experience dramatic diffraction effects; for example, a ring structure can develop.

The intensity of a self-focused filament can be quite high. At a level ~10^{11} W cm^{-2} or higher, it is possible for MPA to lead to multiphoton ionization (MPI) of the medium. This is illustrated in Figure 12 where the absorption of m photons promotes an electron from the ground state to the continuum in a gas, or from the valence band to the conduction band in a solid. The ionization rate is $\sigma_m I^m$, where m depends on the optical frequency and the ionization potential of the material. For example, at a wavelength of 810 nm, $m = 11$ for nitrogen and $\sigma_{11} = 5.08 \times 10^{-144}$ s^{-1} cm^{22} W^{-11}. We note that for intensities larger than ~10^{14} W cm^{-2}, the dominant ionization mechanism is tunneling, where a 'quivering' electron has sufficient energy to tunnel through the coulombic barrier. MPI can create a plasma whose optical properties depend on the density of free electrons. The refractive index of the plasma is nonuniform, and for $\omega > \omega_p = (N_e e^2/\varepsilon_0 m_e)^{1/2}$, the plasma frequency is <1; N_e, e, and m_e are the electron density, charge, and mass, respectively. Hence, plasma formation leads to defocusing. Consequently, self-focusing in air (which has a positive n_2) can lead to plasma formation by MPI, and the resultant defocusing can stabilize the formation of a self-trapped filament of light propagating over a distance of meters. These filaments have been called 'gas-induced solitons'. High peak power femtosecond pulses are typically used to generate these. The pulse width is short compared to the mean



Figure 11 The effects of two-, three-, and four-photon absorption on the intensity-induced phase retardation due to a Kerr self-focusing nonlinearity. The radial dependence of $\Delta\varphi$ on MPA in the parabolic approximation is shown on the left, and the peak of $\Delta\varphi$ as a function of nonlinear absorption loss is plotted on the right.



Figure 12 Multiphoton ionization in a gas (left) and a solid (right).

collision time of molecules, and the energy is low so that plasma heating is negligible.

The electron density in plasmas induced by MPI in gases is typically low enough that absorption by free electrons can be ignored. This is generally not the case in solids. MPI can provide enough 'seed' electrons to induce avalanche ionization. As illustrated in Figure 12, impurities may also supply these seed electrons by thermal ionization if they lie within an energy $\sim k_BT$ of the conduction band (k_B is the Boltzmann constant and T is the temperature). Free electrons can absorb electromagnetic energy while colliding with ions or atoms (a process called inverse bremsstrauhlung) and accelerate in a high-intensity field. They strip electrons from other atoms or molecules by impact ionization. The process multiplies free electrons and avalanche ionization ensues. A plasma forms, absorbs more energy and expands, developing a shock wave that can lead to a permanent crack in the solid. This phenomenon is called optical breakdown. Typically observed with nanosecond and picosecond pulses, permanent laser damage of the material also robs energy from the beam and generally terminates the collapse of a self-focused beam. When the electron density is sufficiently high so that $\omega_p > \omega$, the plasma absorbs and scatters light, a process that can be put to use in optical power limiters.

Many additional nonlinear phenomena play important roles when the intensity of a self-focused beam gets this large (e.g., stimulated Raman scattering, stimulated Brillouin scattering, etc.). The reader is referred to the literature on nonlinear optics for more in-depth discussions of these effects.

List of Units and Nomenclature

Critical power	[W]
Electric field	[V m^{-1}]
Four-photon absorption coefficient	[cm^5 W^{-3}]
Intensity	[W cm^{-2}]
Multiphoton (m-photon) absorption coefficient	[cm^{2m-3} W$^{-(m-1)}$]
Multiphoton (m-photon) ionization rate coefficient	[s^{-1} cm^{2m} W^{-m}]
Nonlinear refractive index coefficient	[cm^2 W^{-1}]
Pockels coefficient	[m V^{-1}]
Second-order susceptibility	[m V^{-1}]
Third-order susceptibility	[m^2 V^{-2}]
Three-photon absorption coefficient	[cm^3 W^{-2}]
Two-photon absorption coefficient	[cm W^{-1}]
Vacuum permittivity	[C V^{-1} m^{-1}]

See also

Laser-induced Damage of Optical Materials. **Materials Characterization Techniques:** $\chi^{(3)}$. **Nonlinear Optics, Applications:** Pulse Compression via Nonlinear Optics. **Nonlinear Optics, Basics:** Cascading; Kramers–Krönig Relations in Nonlinear Optics; Nomenclature and Units; Photorefraction; Ultrafast and Intense-Field Nonlinear Optics; $\chi^{(2)}$–Harmonic Generation. **Photonic Crystals**: Nonlinear Optics in Photonic Crystal Fibers. **Scattering:** Stimulated Scattering. **Solitons:** Bright Spatial Solitons.

Further Reading

Boyd RW (1992) *Nonlinear Optics*. Boston, MA: Academic Press.

Butcher PN and Cotter D (1990) *The Elements of Nonlinear Optics*. New York: Cambridge University Press.

Chiao RY, Garmire E and Townes CH (1964) Self-trapping of optical beams. *Physics Review Letters* 13: 479–482.

Crosignani B and Salamo G (2002) Photorefractive solitons. *Optics and Photonics News* 13: 38–41.
Kivshar YS and Stegeman GI (2002) Spatial optical solitons. *Optics and Photonics News* 13: 59–63.
Marburger JH (1975) Self-focusing: theory. *Progress in Quantum Electronics* 4: 35–110.
Sheik-bahae M, Said AA, Wei TH, Hagan DJ and Van Stryland EW (1989) Sensitive measurement of optical nonlinearities using a single beam. *IEEE Journal of Quantum Electronics* 26: 760–769.
Sheldon SJ, Knight LV and Thorne JM (1982) Laser-induced thermal lens effect: a new theoretical model. *Applied Optics* 21: 1663–1669.
Shen Y (1984) *The Principles of Nonlinear Optics*. New York: Wiley.
Silberberg Y (1990) Collapse of optical pulses. *Optics Letters* 15: 1282–1284.
Sutherland RL (2003) *Handbook of Nonlinear Optics*, 2nd edn. New York: Marcel Dekker.
Torner L and Sukhorukov AP (2002) Quadratic solitons. *Optics and Photonics News* 13: 42–47.
Trillo S and Torruellas WE (eds) (2001) *Spatial Solitons*. Berlin: Springer-Verlag.
Wise F and Di Trapani P (2002) The hunt for light bullets – spatiotemporal solitons. *Optics and Photonics News* 13: 28–32.

Three-Dimensional Microfabrication

S M Kuebler, University of Central Florida, Orlando, FL, USA

M Rumi, Georgia Institute of Technology, Atlanta, GA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Nonlinear optical three-dimensional microfabrication (3DM) is a photolithographic technique that enables topologically complex 3D microstructures with feature size as small as 1 μm or less to be generated in a single exposure step by nonlinear photopatterning in a material. In the broadest context, 3DM encompasses schemes based on single-beam serial patterning and parallel patterning achieved by multiple-beam interference exposure. In both cases, the photopatterning is initiated by coherent multiphoton excitation (MPE). The material may be a glass, a polymerizable resin, or even a heterogeneous composite, such as a resin containing dispersed nano-particles. The limiting resolution, or the dimensions of the smallest feature that can be generated, is determined by the optical parameters of the excitation geometry and the physical and chemical response of the material to MPE.

3DM offers great promise as a tool for generating complex microdevices, such as micro-electromechanical systems (MEMS), microfluidics, and micro-optical components. New frontiers in the technology of microdevices require that complex 3D structures can be produced in one or more materials that are optimized for a target application in terms of physical, chemical, and mechanical properties. Rapid and versatile fabrication is also essential. Extensive work has been done with conventional photolithography or electron-beam lithography, and more recently using soft-lithography approaches, such as microcontact printing. 3DM provides a new set of tools that overcomes some of the limitations inherent to other methods.

Single-Beam Three-Dimensional Microfabrication

3D Confinement

The simplest form of 3DM involves patterning a microstructure within a material using a single tightly focused laser beam that can activate the medium or one of its constituents by two-photon excitation (TPE) (Figure 1). The TPE initiates a photochemical or photophysical process (e.g., a polymerization reaction or a phase change) within the focal volume and results in an irreversible change in the material. The pattern of the target structure is impressed point by point as the focus is translated within the volume of the material. For some applications the final 3D microstructure is obtained when the unexposed material surrounding the photopatterned regions is removed. In the first report of this type of 3DM in 1990 two-photon-induced polymerization (TPIP) of an acrylate resin was used to fabricate free-standing 3D micron-scale letters on a substrate (Figure 2). The unexposed material does not have to be removed in a post-exposure process when the target structure consists of the phototransformed material supported within the matrix of the unexposed media, as in the case of 3DM of waveguide circuits embedded within a host slab.

3DM is possible because, under tight focusing, TPE and the subsequent material transformation are



Figure 1 General scheme for single-beam 3DM based on TPE. (1. TPE patterning): The 3DM medium is supported on a substrate and translated in 3D-space relative to a tightly focused laser beam. The laser transforms the material only in the region around the focal point through a photochemical or photophysical process initiated by TPE. (2. Development): In cases where the final structure is needed free from the unexposed material, the sample is treated with a 'developer' that removes the unexposed material, for example by dissolving it in a solvent. (3. Completed structure): Following removal of the unexposed material, the final 3D structure is obtained free-standing on the substrate.



Figure 2 Scanning electron micrograph of a structure obtained by TPIP-3DM in an acrylate-ester resin. The excitation wavelength was 630 nm. The voxel dwell time was 10 ms along the letters. The thin filaments connecting some of the letters are approximately 100 nm wide. Reproduced from Strickler JH and Webb WW (1990) Two-photon excitation in laser scanning fluorscence microscopy. *Proceedings of the Society of Photo-Optical Instrumentation Engineers* 1398: 107–118. Copyright (1990), with permission of SPIE.

confined at the focus within a volume of $\sim(\lambda/n_0)^3$, where λ and n_0 are the vacuum wavelength of the exciting radiation and the refractive index of the material, respectively. Degenerate TPE is a resonant third-order nonlinear optical process in which a species is promoted to an excited electronic state by the simultaneous absorption of two photons of equal energy. Relative to conventional one-photon excitation (OPE), TPE is typically achieved using longer-wavelength radiation (often red or near infrared), for which the combined energy of two photons is sufficient to promote the species into one of its lower lying excited electronic states (Figure 3, left). The rate of TPE, that is the number of species excited per unit volume and time, $R_{2h\nu}$, is proportional to the square of the intensity, I. For a focused Gaussian beam, the on-axis intensity attains its maximum, I_0, at the focus and decreases with distance from the focal plane, z, approximately as $I \propto z^{-2}$. For a focused Gaussian beam, the on-axis intensity is given by $I = I_0/[1 + (z/z_R)^2]$, where z_R is the Rayleigh range of the focused wavefront. Thus, $I \propto z^{-2}$ in the limit of $z \gg z_R$. Consequently, the excitation rate decreases as $R_{2h\nu} \propto z^{-4}$. Similarly, the excitation rate decreases rapidly away from the propagation axis. This results in a region of high excitation, and thus material transformation, that is tightly confined both laterally and longitudinally in space about the focal point (Figure 3, right). This situation may be contrasted with that for OPE, for which the excitation rate, $R_{1h\nu}$, is linearly proportional to I, so $R_{1h\nu} \propto z^{-2}$. The weaker dependence of $R_{1h\nu}$ on z results in material being excited appreciably throughout the irradiation volume, with less longitudinal confinement at the focus than is achieved under TPE. Similar arguments can be used to describe 3DM involving higher-order excitation, for which the excitation is confined to an even smaller volume for a given λ.

The rate for molecular n-photon excitation, $R_{nh\nu}$, represents the average number of molecules that are excited per unit volume per unit time and is given by

$$R_{nh\nu} = \frac{1}{n(h\nu)^n}\sigma^{(n)} N I^n \qquad [1]$$

where n is the order of the excitation process, h is Planck's constant, ν is the frequency of the exciting radiation, $\sigma^{(n)}$ is a molecular n-photon absorption cross-section, which has units of $[\mathrm{cm}^{2n}\,\mathrm{s}^{n-1}\,\mathrm{photon}^{-(n-1)}]$, N is the number density of the photo-excitable species $[\mathrm{cm}^{-3}]$, and I is the intensity $[\mathrm{W\,cm}^{-2}]$. The factor of $1/n$ accounts for the fact that n photons must be absorbed to promote a single molecule to an excited state. Note that $\sigma^{(n)}$ is a



Figure 3 (Left) Jablonski representation of electronic one- and two-photon excitation (OPE and TPE, respectively). (Right) Illustration of a 3DM medium undergoing OPE and TPE using focused short- (black) and long-wavelength (dark gray) radiation, respectively. The regions that are appreciably excited are shown in light gray. Under OPE the medium is excited throughout the length of the interaction volume. Under TPE the excitation is confined in three dimensions to a small region around the focal point.

molecular parameter that is independent of the intensity. The molecular cross-sections for OPE and TPE, $\sigma^{(1)}$ and $\sigma^{(2)}$, are respectively equivalent to the parameters σ and δ that are commonly encountered in the literature.

For MPE to occur, the intensity must be sufficiently large that there is a high probability of more than one photon arriving simultaneously at the species to be excited. Typical magnitudes of the OPE and TPE cross-sections are $\sigma^{(1)} \approx 10^{-17}\,\text{cm}^2$ and $\sigma^{(2)} \leq 10^{-47}\,\text{cm}^4\,\text{s photon}^{-1}$, and under conventional excitation conditions, $R_{2h\nu} \ll R_{1h\nu}$. To achieve $R2h\nu \approx R1h\nu$, $I \approx 2h\nu\sigma^{(1)}/\sigma^{(2)}$ is required. For the cross-sections given above, this condition corresponds to $I \approx 500\,\text{GW cm}^{-2}$ at $\lambda = 800\,\text{nm}$. Such peak powers can be achieved by focusing ultra-short laser pulses, so mode-locked femtosecond- or picosecond-pulse lasers are generally used for 3DM. Tight focusing in 3DM is desirable then, not only to provide a means for 3D confinement, but also to increase the intensity to a level that $R_{nh\nu}$ becomes large enough to produce a significant material change.

Opto-Mechanical Implementation

One method for implementing single-beam 3DM is illustrated in Figure 4. An excitation laser beam is directed onto a high numerical aperture (NA) objective. A beamsplitter, detector, attenuator, and shutter are placed upstream of the objective to measure and control the average power at the sample, $\langle P \rangle$. A substrate is coated with the photo-active medium and attached to a 3-axis nano/micro-positioner under the objective. The interior of the photo-active material is patterned during the exposure by translating the sample relative to the focus of the laser beam and shuttering the beam as needed. The process is automated as a computer controls the sample translation coordinates and the exposure conditions for each volume element (voxel). This configuration is well suited for patterning solid or semi-solid photo-media. An index-matching fluid must be used with high-NA objectives to achieve the smallest focal spot size. If the photo-medium is a liquid, a coverslip or other thin transparent barrier must be placed between the index matching fluid and the photomedium so that the latter does not become contaminated.

Alternatively, an inverted configuration may be used. Here, the laser is focused through the substrate into the medium. The objective and the index matching fluid are kept out of contact with the medium by the substrate. In this case, the maximum depth that can be patterned is limited by at least two conditions: (i) The working distance of high-NA objectives is small, often no more than 200 μm, so the substrate must be kept thin (~100 μm); and (ii) unless the viscosity of the medium is very high, patterning must begin at the medium/substrate interface and proceed layer by layer away from it, so that the structure remains anchored to the substrate. This could be disadvantageous, as the change in refractive index in the previously patterned layers could alter the intensity distribution



Figure 4 Optomechanical setup for single-beam 3DM.

at the focus. In all configurations, it is best to minimize the number of optical interfaces to maintain the quality of the focus.

A scanning confocal microscope system provides a convenient platform for single-beam 3DM. The nano/micro-positioner can be mounted directly on the sample stage of the microscope, and the optical components of the confocal system can be used directly for 3DM. The confocal system also enables the medium and the structure to be imaged *in situ*, using confocal reflectance or fluorescence imaging. If the material is fluorescent under MPE, a 3D image can be obtained by scanning multiphoton fluorescence microscopy. These imaging modes facilitate 3DM by providing a means for locating the focus at an absolute position within the photo-active medium.

3DM can also be realized by moving the focused beam relative to a fixed sample. One convenient implementation utilizes galvanometer-driven mirrors to scan the beam in planes parallel to the substrate (xy-plane). Motion in the z-direction is accomplished by raising and lowering the objective relative to the substrate. A galvo-based system typically enables faster fabrication, but may not afford motion as precise as that obtained using a multi-axis nanopositioner.

Excitation Sources

The most commonly used and arguably the most convenient and reliable laser for 3DM is the continuous-wave (CW) mode-locked titanium sapphire (Ti:S) laser. Ti:S lasers routinely produce sub-100 fs pulses at high repetition rates (~80 MHz) with single-pulse energies, E_p, of ~1 nJ. The Ti:S laser emission spans the range of 700–1050 nm, making it particularly well suited for two- and three-photon excitation. $\langle P \rangle$ can be as high as several watts at the peak of the gain curve ($\lambda \approx 800$ nm) with high pulse-to-pulse and time-averaged stability (RMS $\approx 1\%$). Such systems may also produce a nearly Gaussian TEM_{00} mode, which is helpful in achieving the tightest focus in the material. Note that focusing a 1 nJ, 100 fs pulse to a 1 μm-radius spot generates a focused average peak intensity of 320 GW cm^{-2}, as is needed to achieve photo-excitation rates of $R_{2h\nu} \approx R_{1h\nu}$.

For higher peak powers, amplified femtosecond (AFS) lasers can be used for 3DM. These systems can produce ~100 fs pulses with $E_p \approx 1$ mJ or higher at repetition rates of 1–100 kHz. Given that a continuous microfabricated structure should be generated from partly overlapping voxels, a low repetition rate reduces the speed with which the laser beam may be scanned within the material. An AFS laser can be used to pump an optical parametric generator to extend the output wavelength range.

Recently, some researchers have turned their attention toward identifying compact solid-state turn-key lasers for 3DM that could be more convenient and cheaper alternatives to the complex systems described above. A commercial Nd:YAG microlaser ($\lambda = 1064$ nm, $E_p = 5.4$ μJ, $\tau_p = 640$ ps, 13.6 kHz) and a mode-locked erbium-doped fiber laser ($\lambda = 780$ nm, $E_p \approx 0.5$ nJ, $\tau_p = 100$ fs, 50 MHz) have both been shown to be satisfactory for 3DM in certain acrylate-based media.

Material Systems

Structural Materials

The most widely used materials for 3DM are based on acrylates that are patterned by multiphoton induced polymerization. The process begins when an initiator chromophore **C** is excited by *n*-photon absorption to $\mathbf{C}^*$, with an efficiency specified by the *n*-photon cross-section $\sigma^{(n)}$. $\mathbf{C}^*$ then generates an initiating radical **I·**. Acrylate monomers (**M**) can react with **I·** and undergo a free-radical chain reaction that leads to high molecular weight polymer. With sufficient exposure, the starting material is converted to less soluble high-molecular weight polymer chains or densely cross-linked polymer networks. The photo-patterned structure can then be 'developed' by immersing the sample into a solvent that removes the unexposed material, leaving behind a free-standing structure that is a replica of the photopattern.

Photo-polymerization starts when the MPE exposure generates enough **I·** to react with and consume all of the inhibitor in the local volume at point $\vec{r}$ within a homogeneous medium. In this discussion we assume that the local concentration of inhibitors is not changed by diffusion on the exposure timescale. The total number of **I·** generated during an exposure at $\vec{r}$ per unit volume, $N_{\mathrm{I\cdot}}(\vec{r},t)$, is obtained from the time-integrated MPE rate:

$$N_{\mathrm{I\cdot}}(\vec{r},t) = \frac{\phi_{\mathrm{c}}^{(n)}\sigma^{(n)}N_{\mathrm{C}}}{n(h\nu)^n}\int_{-\infty}^{t} I(\vec{r},t')^n \mathrm{d}t' \qquad [2]$$

Here, N_{C} is the number density of **C**, and $\phi_{\mathrm{c}}^{(n)}$ is the *n*-photon chemical quantum yield, defined as the number of **I·** generated divided by the number of $\mathbf{C}^*$ present after excitation. If we identify the initial number density of the inhibitors as N_{Inh}, then polymerization occurs when $N_{\mathrm{I\cdot}}(\vec{r},t) > N_{\mathrm{Inh}}$. In multiphoton-induced polymerization, $N_{\mathrm{I\cdot}}(\vec{r},t)$ is a nonlinear function of I, which generally involves a rapidly varying time envelope, as from a mode-locked ultrashort-pulse laser.

Several different commercial acrylate systems have been used successfully for 3DM, such as Nopcocure 800 (San Nopco), NOA 72 (urethane acrylate oligomer, Norland Products), and SCR 500 (blend of urethane acrylate monomers and oligomers, Japan Synthetic Rubber Co.). Researchers have also successfully developed custom formulations using blends of commercially available monomers, oligomers, and polymer additives to create resins with tailored physical, chemical, and optical properties. This aspect of acrylates, and more generally polymer-based systems, makes them one of the most attractive classes of materials for 3DM. Conventional one-photon UV- or blue-sensitive radical generators (e.g., benzil, benzoin methyl ether, 4,4′-bis(*N*,*N*′-dimethylamino)benzophenone, to name just a few) have most often been used, and these were activated by promoting the molecule into one of its low-lying electronic states by MPE over the range of 730–800 nm.

3DM based on epoxide polymerization has also been demonstrated using commercial resins including cross-linkable small molecular weight monomers (e.g., 4-vinyl-1-cyclohexene diepoxide) and epoxide oligomers (e.g., SU-8, first developed by IBM). Epoxide polymerization is most commonly initiated by molecules that, after excitation, generate a Brønsted acid, H^+. The propagating species is a carbocation, and bases present in the medium act as inhibitors. Relative to acrylates, epoxides shrink substantially less upon polymerization, leading to less distortion of the microstructure after development.

Acrylate chemistry has also been exploited for 3DM of functional composite materials. Acrylamide resin mixtures were used to fabricate bi-layer micro-cantilevers that deflect from the surface when illuminated with UV light. This type of microstructure could form the basis of a photo-activatable MEMS. 3D gratings were fabricated from an acrylate pre-polymer containing a dendrimer functionalized with cross-linkable acrylic *L*-phenylalanine groups. The dendrimer acts as a host encapsulation site that enables a laser dye to be loaded in the material at high weight-percent (see below). A variety of complex micro-structures have also been fabricated using 'Ormocer-I', an ORganically MOdified CERamic. Ormocer-I is an inorganic-organic hybrid polymer consisting of a Si–O–Si (siloxane) backbone that is functionalized with organic moieties, including cross-linkable methacryloxypropyl groups. Ormocers are extremely promising for 3DM because of the thermal stability and chemical inertness of the backbone and their attractive physical and optical properties.

3DM could be a powerful tool for fabricating biologically active structures and devices. In this context, hydrogels and Ormocers should be useful material systems as some formulations are known to be bio-compatible. Microstructures can also be fabricated from proteinaceous material. 3D microstructures were produced by patterned MPE of solutions containing the dye rose bengal and the proteins bovine serum albumin or fibrinogen.

The material systems discussed thus far are 'negative-tone' media. This means that only the exposed regions of the material remain after the post-exposure development, so the final structure is a replica of the exposure pattern. In contrast, 'positive-tone' media are solid-state systems for which the exposed regions become soluble in a developer. The final structure is then the inverse of



$\sigma^{(2)} = 690 \times 10^{-50}\ \mathrm{cm}^4\ \mathrm{s\ photon}^{-1}$ at 705 nm

$\phi_{H+} = 0.50 \pm 0.05$

Figure 5 A 3D micro-channel structure fabricated by TPE-3DM using the positive-tone chemically amplified resist THPMA-MMA containing the two-photon PAG **BSB-S**$_2$. A 50 μm-thick film of the resist was exposed in the pattern of the target structure at 745 nm with tightly focused 80 fs pulses at $\langle P \rangle = 40$ μW and a linear scan speed of 50 μm s^{-1}. (a) Target structure consisting of two rectangular cavities (width: 100 μm, length: 20 μm, depth: 20 μm) with a sloped side-wall, that are connected by 12 channels (length: 50 μm; 4 μm by 4 μm cross-section) lying 10 μm below the surface and spaced apart by 8 μm (center-to-center). (b) Scanning electron micrograph of the final structure, viewed normal to the substrate. (c to e) Two-photon-fluorescence images of the final structure (viewed normal to the substrate): (c) at the surface of the film; (d) 10 μm below the surface; (e) 19 μm below the surface. (f) Two-photon-fluorescence cross-sectional image of the buried channels. The scale bar in b to f corresponds to 20 μm. Reproduced from Zhou W, *et al.* (2001) *Science* 296: 1106–1109. Copyright (2001), with permission of The American Association for the Advancement of Science.

the exposure pattern. Positive-tone 3DM was first demonstrated as early as 1992 with the generation of high aspect ratio trenches in thin layers of commercial photoresists. A positive-tone material system was designed for 3DM (Figure 5), is based on a chemically amplified resist and a high-sensitivity two-photon-activatable photo-acid generator (PAG) (discussed below). Using this medium, it was possible to fabricate subsurface microchannel structures and microgratings, using moderate laser scan speeds (50 μm s^{-1}) and exceptionally low $\langle P \rangle$ (40 μW).

Composites have been formulated that enable 3D-patterning of nanoscale metal features within a host matrix. A two-step process has been described that involves MPE of a Ag^+-containing sol–gel followed by thermal development of the latent image with a $AgClO_4$ solution. Using this system, 3D spirals of silver nano-particles embedded within the sol–gel matrix were generated. A $HAuCl_4$-doped poly(vinyl alcohol) composite was used to 3D-pattern gold nano-particles. It was shown that after TPE a particular sensitizer dye hosted in a poly(vinylcarbazole) matrix containing $AgBF_4$ and ligand-stabilized Ag nanoparticles, electron transfer from the dye to Ag^+ leads to nucleation of Ag^0 at the nanoparticles and the formation of conducting bulk metal features (Figure 6). Material systems like these should find wide application for generating micro- and nano-scale structures, having unusual and useful optical and electronic properties.

3DM in glasses is of great interest for photonic applications. Several groups have demonstrated that tightly focused infrared or visible amplified ultrashort laser pulses can be used to 3D-pattern pure and doped silica and other glasses. The patterned voxels can be generated as a result of photo-induced changes in the refractive index or extreme dielectric breakdown, resulting in pits within the material. The mechanisms for these two cases are not fully understood, but both are thought to be activated through an initial MPE event. The leading edge of the laser pulse generates a free-carrier plasma through MPE. The remainder of the pulse is increasingly absorbed by the plasma leading to avalanche ionization. The optical energy deposited into the local lattice results in cavitation, creating a pit at the focal point. Based on the electronic bandgap of silica, the process likely involves three- and six-photon absorption when 400- and 800-nm light is used, respectively. This approach has been used for the 3D-patterning fused silica and germanium doped glasses.



Figure 6 Metallic structures fabricated by TPE-3DM using a silver nanoparticle/polymer composite. (a) Model of the ‘stack-of-logs’ target structure. (b) 3D image constructed from a series of two-photon fluorescence microscopy images of the silver structure immediately following 3DM. (c) Scanning electron micrograph of the free-standing silver structure following removal of the surrounding unexposed composite. The scale bar corresponds to 10 μm. (d) Transmission optical microscopy image of the silver structure immediately following 3DM. The scale bar corresponds to 25 μm. Reproduced from Stellacci F, *et al.* (2001) *Advanced Materials* 14: 194–198. Copyright (2001), with permission of Wiley.

Multiphoton Initiators

For 3DM to develop into a widely used fabrication tool, material systems and patterning methods must be developed that enable rapid microfabrication at low cost. ‘Soft materials’, such as the polymer systems described above, are promising in this respect, as both the initiating species and the host resin can be engineered to optimize the multiphoton response and the physical and chemical properties of the patterned medium. It may also prove possible to create doped glasses that have physical properties close to that of neat silica and yet offer higher multiphoton sensitivity.

To develop this concept, let us consider 3DM in acrylates further. A high-sensitivity acrylate medium is one for which: (i) **C** strongly absorbs *n*-photons (large $\sigma^{(n)}$); (ii) $\mathbf{C}^*$ efficiently generates the initiating species **I·** (large $\phi_c^{(n)}$); and (iii) **I·** is an efficient initiator (high initiation rate). As criteria (i) and (ii) are predominantly determined by the molecular properties of **C**, it should be possible to engineer soft materials for 3DM by optimizing multiphoton initiators and incorporating these into pre-polymer resins that once patterned have the correct properties for the target application. The sensitivity of materials can be compared on the basis of the minimum average laser power, $\langle P \rangle_{\min}$, that is required to pattern a material using a fixed scan speed (or exposure time). Alternatively, we can use the product $\sigma(n)\phi c(n)$ as a multiphoton initiator figure-of-merit (FOM) that accounts for the strength of the multiphoton absorption and the efficiency with which **I·** is generated.

The chromophores that have been used most frequently for polymerization-based 3DM do efficiently generate highly active initiating species once excited; however, they were developed for one-photon response to UV and blue radiation and generally have low multiphoton FOMs. The use of xanthene dyes was explored as initiators for free-radical polymerization of acrylamides and it was found that the multiphoton sensitivity was low. As a result, 3DM using conventional initiators requires high laser power (typically $\langle P \rangle_{\min} \approx 10-100$ mW) and slow laser scan speeds ($\sim 50\ \mu\mathrm{m\ s^{-1}}$). Under tight-focusing conditions, the resulting peak powers are often near the damage threshold of the materials, rendering the process unreliable from a manufacturing stand-point.

A series of **D–π–D** molecules was examined (Figure 7), where **D** is an electron-donating group and **π** is a conjugated *π*-electron bridge. This class of **D–π–D** chromophores was found to have large TPE cross-sections ($\sigma^{(2)} > 200 \times 10^{-50}\ \mathrm{cm^4\ s\ photon^{-1}}$) and to initiate the polymerization of acrylates following TPE in the visible and near infrared, with $\langle P \rangle_{\min}$ a factor of 30–50 times lower than for conventional one-photon initiators. The sensitivity achieved with **D–π–D** initiators is so enhanced that TPIP-3DM was performed at laser scan-speeds as high as $9\ \mathrm{cm\ s^{-1}}$, using $\langle P \rangle = 3$ mW, enabling a volume of $180\ \mu\mathrm{m} \times 180\ \mu\mathrm{m} \times 20\ \mu\mathrm{m}$ to be polymerized in 200 s.

D–π–A molecules have also been examined for TPIP (Figure 7), where **A** is an electron accepting functionality. Such molecules can have large TPE cross-sections, and some have been shown to activate TPIP efficiently in acrylates at $\lambda \approx 800$ nm. A derivative of Michler’s ketone was synthesized with an extended *π*-conjugated system (Figure 7). This molecule exhibited strong two-photon absorption over the broad range of 800–1100 nm and was also shown to be active toward acrylate polymerization at 1064 nm. A strategy was implemented for enhancing two-photon sensitivity based on up-converted fluorescence and used for 3DM of waveguide structures. The strongly two-photon-absorbing dye AF-183 was incorporated into a commercial acrylate photoresist containing a radical-generator that is activated by OPE at 315–450 nm. After AF-183 undergoes TPE at 800 nm, it fluoresces efficiently at ~465 nm. The up-converted emission then excites the one-photon initiator and radicals are generated.

The strategies discussed above are oriented toward enhancing multiphoton sensitivity by increasing $\sigma^{(2)}$ of the initiating chromophore. Little attention has been paid to the need of ensuring that the MPE couples to a mechanism for efficiently generating an active initiating species. This problem was addressed with the design of a two-photon PAG by covalently linking a **D–π–D** chromophore and sulfonium moieties, which can generate H^+ when reduced by photo-induced electron transfer (**BSB-S$_2$** in Figure 5). **BSB-S$_2$** features strong two-photon absorption and its quantum yield for the generation of H^+ per photo-excited molecule (ϕ_{H^+}) exceeds that of some commercial one-photon PAGs. Based on $\langle P \rangle_{\min}$, **BSB-S$_2$** was found to be 10 to 100 times more sensitive toward multiphoton epoxide polymerization than one-photon UV/blue-sensitive PAGs.

It should be understood that this discussion of multiphoton initiators is not comprehensive of all work that has been done in the field. Rather, it is intended as a highlight of the many outstanding examples of progress in this area. The use of inexpensive low-power lasers for 3DM should become more practical as high-sensitivity

Donor-π-Donor initiators



$n = 1$: $\sigma^{(2)} = 900 \times 10^{-50}$ cm^4 s photon^{-1} at 730 nm
$n = 2$: $\sigma^{(2)} = 1250 \times 10^{-50}$ cm^4 s photon^{-1} at 775 nm

Donor-π-Acceptor initiators



$\sigma^{(2)} = 100 \times 10^{-50}$ cm^4 s photon^{-1} at 775 nm

$\sigma^{(2)} = 880 \times 10^{-50}$ cm^4 s photon^{-1} at ~830 nm (calculated)

Extended Michler's ketone initiator



$\sigma^{(2)} = 200 \times 10^{-50}$ cm^4 s photon^{-1} at 950 nm

Figure 7 Examples of high-sensitivity initiators for 3DM based on TPIP of acrylates.

3DM media are developed. This should, in turn, facilitate the widespread use of 3DM as a microfabrication tool.

Resolution

The resolution of single-beam 3DM is determined by the size of the smallest voxel that can be reliably produced. Both the optical parameters and the material response under MPE affect the size of the voxel. Given the wide range of physical and chemical mechanisms that can be involved, no single set of guidelines can be outlined regarding the effect of the material response on voxel size. Additionally, this aspect of 3DM remains relatively unexplored. However, as 3DM based on TPIP of acrylates has been examined in some detail, an overview of this material response provides some valuable insight into the overall problem of resolution. The following simplified discussion is based on the local response of the material to photo-excitation.

TPIP initiated in the vicinity of the focus could, in principle, propagate throughout the entire volume of the medium, were it not for termination by inhibitors. Let us consider further the expression for $N_{\mathrm{I}^\cdot}(\vec{r}, t)$, expanding the intensity as:

$$I(z, r, t') = i(z, r) f(t') \qquad [3]$$

Here, $f(t')$ is a time-dependent amplitude function, $i(z, r)$ is the peak intensity, and the position vector $\vec{r}$ is expressed in cylindrical coordinates (z, r) with the origin at the focus. As before, z denotes the direction in which the beam propagates (longitudinal). The radial coordinate orthogonal to the z-axis (lateral) is denoted by r. The beam is taken to have cylindrical symmetry, so I does not depend on the angular coordinate. For a fixed exposure time $t \rightarrow \tau_{\mathrm{ex}}$, we can identify a polymerization-threshold peak intensity, I_{th}, for which $i(z, r) > I_{\mathrm{th}}$ results in $N_{\mathrm{I}^\cdot}(z, r, \tau_{\mathrm{ex}}) > N_{\mathrm{Inh}}$ and polymerization occurs. The polymerized voxel consists then of all points within the volume centered at the focal point and bounded by the I_{th} isophote.

The shape of the I_{th} isophote depends upon the optical parameters of the system. The tightest focusing is achieved when the highest NA objective is used to focus parallel incident rays that overfill the entrance aperture. This situation generates a diffraction limited intensity pattern about the focal point. Within the focal plane the lateral intensity distribution follows the Airy pattern:

$$i(0, r) = [2J_1(\rho)/\rho]^2 I_0 \qquad [4]$$

where J_1 is the first-order Bessel function:

$$\rho = 2\pi r \mathrm{NA}/\lambda \qquad [5]$$

and I_0 is the peak intensity at the origin. Near the focus, the longitudinal intensity distribution is given by

$$i(z, 0) = [\sin(\zeta/4)/(\zeta/4)]^2 I_0 \qquad [6]$$

where

$$\zeta = 2\pi \mathrm{NA}^2 z/(n_0 \lambda) \qquad [7]$$

Let us define the longitudinal and lateral widths of the focal spot, Z and R respectively, to be twice the distance along the corresponding z- and r-axes over which the peak intensity of the central bright fringe decreases to $I_0/2$. If $\langle P \rangle$ is adjusted so that $I_0/2 = I_{\mathrm{th}}$, then to first order we can expect the polymerization voxel to be a solid of rotation centered about the focus having a longitudinal and lateral width of Z and R, respectively. Numerical evaluation shows that the $I_0/2$-points occur at $\rho = \pm 1.6154$ and $\zeta = \pm 5.5661$. For $\lambda = 800$ nm, NA = 1.4, and $n_0 \approx 1.5$, we find $R = 0.29$ μm and $Z = 1.1$ μm.

Several groups have demonstrated that voxels generated under conditions similar to those discussed above do indeed have dimensions comparable to those calculated, based on diffraction limited propagation. As shown in Figure 8, voxels with lateral and longitudinal widths below the diffraction limit can be fabricated by steadily reducing τ_{ex} (or I_0) so that an increasingly smaller portion of the central bright fringe exceeds I_{th}. In this way, voxels having $R \approx 100$ nm and $Z < 800$ nm have been generated, which convincingly demonstrates the potential of this technique as a nano-fabrication tool.

Post-exposure material processing can also have a profound impact on the resolution. In the case of TPIP-3DM, material near the boundary of the I_{th} isophote may not have sufficient molecular weight or cross-linking density to resist removal in a development step. In this case, the final voxel will be smaller than the I_{th} isophote defined strictly in terms of a polymerization threshold. Additionally, a solvent-based developer can swell or otherwise distort the voxels. Overall, three important factors determine the final size of the voxel: (i) the exposure and focusing conditions; (ii) the response of the material to photo-excitation; and (iii) the behavior of the photoconverted material during the development process. It should be emphasized that 3D confinement is due to the combined effects of nonlinear photo-excitation and the nonlinearity inherent in the photoconversion and post-exposure development of the material. More advanced treatments have also attempted to address the effects of radical and inhibitor diffusion on the size of the voxel.

Previously, we assumed that the voxel is cylindrically symmetric. The intriguing result of some recent work has shown that the widths of the voxel in the transverse directions can actually differ by as much as 10% when linearly polarized radiation is used because the symmetry of the electric field vectors in the x- and y-directions is broken in high-NA focusing geometries. Cylindrically symmetric voxels can be obtained by using depolarized or circularly polarized radiation. Clearly, study of the combined effects of optical parameters and material response remains an important area for further research in this rapidly advancing field. Although this discussion has centered on TPIP, similar arguments can be developed for 3DM based on other photomaterials and higher-order processes.



Figure 8 Single voxels produced by TPIP-3DM in an acrylate medium. (a) Scanning electron microscope (SEM) images of a single voxel showing its longitudinal (top) and lateral (bottom) width. (b) Dependence of the longitudinal and lateral widths of voxels on exposure time, as measured from SEM images following fabrication. Reproduced from Kawata S and Sun H-B (2003) Two-photon photopolymerization as a tool for making micro-devices. *Applied Surface Science* 208–209: 153–158. Copyright (2003), with permission of The American Institute of Physics.

Multibeam-Interference Three-Dimensional Microfabrication

Multibeam-interference (MBI) 3DM is an alternative approach to 3DM that enables large volumes of material to be simultaneously patterned into a 3D periodic structure. In MBI-3DM, multiple coherent laser beams interfere within a photo-active medium. A periodic structure results because the material undergoes photo-induced changes that occur maximally in the regions of peak intensity across the periodic interference pattern. Depending on the number of beams utilized and their reciprocal orientation, periodic structures in one, two, or three dimensions can be generated, and the periodicity is of the order of λ. This technique is often referred to as holographic lithography or recording.

MBI-3DM has most often been achieved using one-photon-induced polymerization; however, higher-order excitation may be used as well. In this discussion we will focus on multiphoton MBI-3DM, with the understanding that most of the concepts apply equally well to the case of linear photo-excitation. When the power of the incident beams is adjusted so that the intensity at the peaks of the interference pattern just exceeds I_{th}, polymerization only occurs in the local vicinity of these points, whereas the 3DM medium is not appreciably polymerized in regions where the intensity is below I_{th} and may be removed by dissolution in a solvent. The result is a periodic porous structure with highly interconnected parts, that extends over the whole volume where the beams overlapped.

Let us assume that m-beams are directed onto a photosensitive material. The intensity of light at a given point $\vec{r}$ in the region where the beams overlap is proportional to:

$$\begin{aligned} I(\vec{r}) \propto \vec{E}\cdot\vec{E}^* &= \left(\sum_{j=1}^{m} \vec{E}_{0j}\, e^{i(\vec{K}_j\cdot\vec{r}-\omega t)}\right)\cdot\left(\sum_{l=1}^{m} \vec{E}^*_{0l}\, e^{-i(\vec{K}_l\cdot\vec{r}-\omega t)}\right) \\ &\propto \sum_{j,l=1}^{m} \vec{E}_{0j}\cdot\vec{E}^*_{0l}\, e^{i(\vec{K}_j-\vec{K}_l)\cdot\vec{r}} \\ &\propto \sum_{j=1}^{m} \vec{E}_{0j}\cdot\vec{E}^*_{0j} + \sum_{j\neq l}^{m} \vec{E}_{0j}\cdot\vec{E}^*_{0l}\, e^{i(\vec{K}_j-\vec{K}_l)\cdot\vec{r}} \end{aligned} \qquad [8]$$

where $\vec{E}_{0j}$ and $\vec{K}_j$ are the electric field and wavevector of beam j, and ω is its angular frequency ($\omega = 2\pi\nu$). Equation [8] indicates that the intensity distribution depends on the difference between pairs of wavevectors of the interfering beams, $\vec{K}_j - \vec{K}_l$. This distribution is periodic in space and can be described as a crystal lattice with reciprocal lattice vectors equal to $\vec{K}_j - \vec{K}_l$ and with a unit cell structure determined by the pre-factors $\vec{E}_{0j}\cdot\vec{E}^*_{0l}$. By choosing the intensity of the incident beams and the exposure time appropriately, it is thus possible to generate a pattern in the medium that has the same periodicity and structure as the I_{th} isophote of the interference pattern.

The simplest implementation of MBI-3DM involves interfering two linearly polarized beams at angles $\pm\theta/2$ with respect to the normal to the film being patterned (θ is the angle between the two beams in vacuum). From eqn [8], it can be shown that the intensity is maximum if $(\vec{K}_1 - \vec{K}_2)\cdot\vec{r} = 2q\pi$, where q is an integer, or $K[\sin(\theta/2)]r' = q\pi$, where K is the magnitude of both $\vec{K}_1$ and $\vec{K}_2$, and r' is the component of $\vec{r}$ along $(\vec{K}_1 - \vec{K}_2)$. Thus, the two beams generate an interference pattern with periodicity (in one dimension) given by $\Lambda = \lambda/[2\sin(\theta/2)]$, if λ is the



Figure 9 (a) Relative orientation of the beams in a four-beam interference scheme to obtain a face-centered cubic lattice. The beams have wave vectors along the directions [−3/2, −3/2, −3/2], [−5/2, −1/2, −1/2], [−1/2, −5/2, −1/2], and [−1/2, −1/2, −5/2]. (b) One of the isophotes generated by the interference of the four beams in (a). The inset represents the shape of the unit cell. Reproduced with permission from *Nature*, Campbell M, *et al.* (2000) *Nature* 404: 53–56. Copyright (2000), Macmillan Magazines Limited.

vacuum wavelength of the exciting beam ($\lambda = 2\pi/K$). When a film of a polymerizable material is placed at the intersection of the beams, a series of ridges is generated in the resist, spaced by Λ and with a width dependent on the beam intensity. For example, if a laser beam at 800 nm is split in two components forming an angle of 30°, $\Lambda = 1.5$ μm. The periodicity becomes smaller as the angle between the beams is increased.

By interfering three beams it is possible to obtain a two-dimensional periodic structure. For example, the interference of three beams forming an angle θ with respect to the medium normal and symmetrically arranged around it was used to generate an hexagonal lattice of rods that extends parallel to the normal. At least four beams must interfere to obtain a microstructure with 3D periodicity. The beam geometry shown in Figure 9a was used to produce a microstructure with the symmetry of a face-centered cubic lattice (Figure 9b). Beam geometries for generating interference patterns having other symmetries, such as body-centered cubic and body-centered tetragonal, have also been described.

An advantage of MBI-3DM is that it enables rapid patterning of large volumes during a single exposure. In fact, the polymerization takes place, in principle, throughout the region in which the beams overlap. When the process is activated by OPE, the beams can be attenuated significantly by absorption in the material. This can limit the thickness of the fabricated structure or result in spatial variation in the filling ratio. The use of TPIP can overcome this limitation and allow for thicker media to be patterned uniformly. Structures with the same symmetry are generated if either one- or two-photon processes are exploited to induce the material transformation. However, the structures will be different for at least two reasons: (i) if the same initiator is used in both cases, the wavelength used for TPE is approximately twice that for OPE, and



Figure 10 (a) Optical image of a diffraction grating obtained by TPIP using a two-beam interference scheme ($\lambda = 810$ nm). The spacing period is 3.4 μm and film thickness is 40 μm. The grating is made of an acrylate-based resin. (b) Diffraction pattern of the grating in (a) generated using a Helium–Neon laser (632.8 nm). The maximum diffraction efficiency was measured to be 57%. Reproduced from Guo H, *et al.* (2003) *Chemical Physics Letters* 374: 381–384. Copyright (2003), with permission from Elsevier.



Figure 11 Emission spectra of the laser dye DCM encapsulated in a dendrimer-based resin that was patterned into a grating microstructure by single-beam 3DM. The grating was pumped at 532 nm (8 ns pulses) with excitation energies of (a) 0.03, (b) 0.05, and (c) 0.20 μJ. Starting at excitation energies as in (b), a narrow band at 612 nm appears over the spontaneous emission. The relative intensity of this lasing emission increases with excitation intensity with respect to the spontaneous emission. Reproduced from Yokoyama S, *et al.* (2003) *Thin Solid Films* 438–439: 452–456. Copyright (2003), with permission from Elsevier.

the periodicity of the structure is correspondingly different; and (ii) the I_{th} isophote, and thus the details of the polymerized structure inside each unit cell, is different under OPE and TPE because the excitation rate is proportional to I and I^2, respectively. In principle, better defined features can be obtained using two-photon or higher-order excitation because the transition between regions of low- and high-exposure is sharper than that under OPE, due to the nonlinear dependence on I. Interference fabrication techniques can enable the generation of features considerably smaller than the diffraction limit, when the beam geometry and excitation intensity are chosen appropriately.

The beams used to generate the interference pattern are usually obtained by splitting the output of a single laser source into the desired number of components. The intensity and polarization of each beam are then independently controlled. Temporal overlap of the beams at the sample can be ensured by introducing an optical delay into each of the beam paths. As fluctuations in the beam intensity can cause changes in the lattice unit cell or its filling ratio, the use of a laser with good stability is imperative in cases where exposure time extends over more than a single laser pulse.



Figure 12 Example of a wood-pile PhC structure obtained by single-beam TPIP-3DM. The periodicity is 5 μm. The change in the cross-section of the structure from top to bottom, is due to shrinking of the material during development, whose effect is largest in the region farthest from the substrate. Reproduced with permission from *Nature*, Cumpston BH, Ananthavel SP, Barlow S, *et al.* (1999) Two-photon polymerization initiators for three-dimentional optical data storage and microfabrication. *Nature* 398: 51–54, Copyright (1999), Macmillan Magazines Limited.

Structures and Functional Devices

The versatility of 3DM is easily appreciated by surveying the variety of microstructures that have been fabricated over the years. These may be divided into two categories: (i) structures whose characteristics lay in their form and in the interconnectivity of their parts; and (ii) structures that incorporate an active functionality that can be exploited in a specific application. Some of these microstructures are described below.

Fabricating functional micro-optical devices is a promising application of 3DM. Figure 10 shows a grating fabricated by two-beam-interference TPIP in an acrylate with a period of 3.4 μm, whose diffraction efficiency is 28% as fabricated and 57% after annealing. The same method was used to generate a surface relief grating in a resin containing a polycationic peptide. In the presence of aqueous silicic acid, the peptide catalyzes the formation of ordered arrays of silica nanospheres in



Figure 13 (a) Cross-sectional optical images of various planes of a diamond lattice fabricated in glass. The numbers to the right are the relative positions of the planes, in units of the lattice constant. (b) Diagram of the expected position of lattice points in a diamond structure. Points located in different planes have different shading. Reproduced from Mizeikis V, *et al.* (2001) *Journal of Photochemistry and Photobiology A* 145: 41–47. Copyright (2001), with permission from Elsevier.



Figure 14 (a) Illustration of a diamond lattice. (b) Scanning electron micrograph of a polymeric microstructure with the symmetry of a diamond lattice, obtained by single-beam TPE-3DM. The letters A, B, C, D, A′ refer to the lattice planes at 0, 1/4, 1/2, 3/4, and 1 lattice units in the vertical direction. Reproduced from Kaneko K, *et al.* (2003) *Applied Physics Letters* 83: 2091–2093. Copyright (2003), with permission of The American Institute of Physics.



Figure 15 (Left) Images obtained by laser scanning confocal microscopy of linear defects generated by three-photon-induced polymerization of a triacrylate resin backfilled into a silica colloidal crystal. The spacing between the planes of the images is 0.5 μm. (Right) Cross-sectional image in the *xz*-plane of the same structure. Reproduced with permission from Lee W, *et al.* (2002) *Advanced Materials* 14: 271–274. Copyright (2002), with permission of Wiley.



Figure 16 Microstructure of a bull fabricated by single-beam 3DM. The scale bar corresponds to 2 μm. Reproduced with permission from *Nature*, Kawata S, *et al.* (2001) *Nature* 412: 697–698. Copyright (2001), Macmillan Magazines Limited.

the troughs of the grating, which increases the diffraction efficiency 50-fold. 3DM was used to fabricate a grating structure in an acrylate resin containing the laser dye 4-(dicyanomethylene)-2-methyl-6-(4-dimethylaminostyryl)-4H-pyrane (DCM) encapsulated in a host dendrimer (see above) as an active optical medium. When pumped at 532 nm above a certain threshold, lasing emission from DCM was observed at 612 nm, with a bandwidth of 0.15 nm (Figure 11).

Several groups have explored the potential of 3DM as a tool for patterning waveguide-based optical circuitry. For example, a mixture of thermally and photocurable resins was used to generate embedded waveguides by photocross-linking within the thermally set medium. A Y-coupler was created in fused silica through the refractive index change generated by patterned MPE.

3DM provides a powerful route to 3D photonic crystals (PhC). PhCs are structures in which a basic motif, or ‘unit cell’, is repeated within the material with a given periodicity. PhCs have attracted great interest, because the modulation of the refractive



Figure 17 Scanning electron micrographs of two structures in the form of (a) a hand and (b) a robot which were fabricated by single-beam 3DM. Reproduced from Maruo S and Ikuta K (2000) *Proceedings of the Society of Photo-Optical Instrumentation Engineers* 3937: 106–112. Copyright (2000), with permission of SPIE.

index between the 'filled' areas and the surrounding space provides a means for controlling the propagation of electromagnetic radiation within the structure. PhC with periodicities in the submicron and micron range exhibit their peculiar properties in the visible and near infrared spectral region. Optical wavelength PhCs can be fabricated in a straightforward way by 3DM, either by serial patterning using the single beam approach or by parallel patterning using the interference method, for which the number and orientation of the beams is dictated by the symmetry of the desired structure. Typical examples are woodpile structures (Figure 12), which consist of layers of rods of a material fabricated side by side with a fixed spacing, and alternate layers are rotated by 90° with respect to one another. If the rods in one layer are displaced by half the lattice constant with respect to the previous layer with the same orientation, the structure obtained has the symmetry of a face-center cubic lattice. PhCs with the symmetry of the diamond crystal have also been fabricated, either by inducing changes in a glass



Figure 18 Scanning electron micrograph of a series of connected chain links obtained by single beam TPIP-3DM in an acrylate resin. Notice the tilt angle between the central links, indicating that each link can move with respect to the others. Reproduced from Kuebler SM, Rumi M, Watanabe T, *et al.* (2001) Optimizing two-photon initiators and exposure conditions for three-dimentional lithographic microfabrication. *Journal of Photopolymer Science and Technology* 14: 657–668. Copyright (2001), with permission of the Technical Association of Photopolymers Japan.



Figure 19 Optical image of a micro-wheel obtained by single-beam 3DM. (a) Structure before development. (b) When ethanol is used to remove the unpolymerized material, the wheel rotates around the axle in the solvent. Reproduced from Maruo S and Ikuta K (2000) *Proceedings of the Society of Photo-Optical Instrumentation Engineers* 3937: 106–112. With permission of the Institute of Electrical Engineers of Japan.



Figure 20 Optical image of a micro-spring tethered to a polymer block. The structure in (a) is at its resting point in ethanol. In (b) the spring was elongated by displacing the polymer bead at the free end using laser trapping. Reproduced with permission from *Nature*, Kawata S, *et al.* (2001) *Nature* 412: 697–698. Copyright (2001), Macmillan Magazines Limited.



Figure 21 Hollow micro-tubule generated by single-beam TPIP-3DM in a urethane acrylate. The inner diameter is 1.8 μm. Reproduced from S Maruo and S Kawata (1998) *Journal of Microelectromechanical Systems* 7: 411–415. Copyright (1998), with permission of IEEE.

substrate at lattice points (Figure 13), or by constructing a network of polymeric rods connecting nearest neighbor points (Figure 14). It was showed that a PhC created by TPIP-3DM does exhibit a partial bandgap in the infrared spectral region. The position of the bandgap can be tuned by fabricating the structure with the appropriate periodicity.

The ability to introduce defects in PhCs in a controlled fashion is of key importance for the application of these structures in optical circuitry, as they can act as waveguides for channeling light into preferential directions. Point, line, and plane defects can be generated easily, by locally altering the fabrication pattern in the PhC. Point-by-point MPE of a Ge-doped glass was used to pattern a cubic lattice containing systematic defects that defined a Y-shaped waveguide splitter in a [100] plane. 3DM can also be used to modify a structure that is created using another fabrication method, and additional materials can be introduced into the structure in this second fabrication step. A silica colloidal crystal was backfilled with a polymerizable material and waveguides were generated by photocross-linking channels in the medium through three-photon-excitation 3DM (Figure 15).

The full potential of single-beam 3DM can be appreciated by surveying some of the structures that have been fabricated, featuring topologically complex shape, high interconnectivity, and extreme under-cut. Examples include those of Figures 16, 17, and the diamond-lattice PhC of Figure 14. Structures with freely movable parts, like those needed for MEMS, are difficult to obtain by other fabrication techniques, but can often be made by 3DM in a single exposure step. The ability to generate structures with independent but interconnected parts is exemplified by the microchain of Figure 18. A further example is the microgear in Figure 19, which is shown to spin around its axle when the sample is flooded with a liquid. Other functional microstructures have also been reported, such as the microspring in Figure 20, fabricated in a urethane acrylate resin and characterized by a core diameter of only 300 nm. When the sample is immersed in ethanol, the pendant mass can be captured and extended with optical tweezers. When the mass is released, the spring behaves like a damped oscillator.

Promising results have also been obtained in the production of structures to be used in micro-fluidics applications. Of key importance, in this case, is the ability to pattern channels, cavities, and other hollow structures that can be used to store or transfer small amounts of fluids between different parts of a device, as needed to perform, for example, analytical processes on a femtoliter scale. Examples include the hollow microtubule (Figure 21), and the submersed channels structure fabricated in a positive-tone resist (Figure 5).

List of Units and Nomenclature

A	Electron accepting molecular fragment
AFS	Amplified femtosecond
C	Chromophore
$\mathbf{C}^*$	Excited chromophore
CW	Continuous wave
D	Electron donating molecular fragment
3D	Three-dimensional
3DM	Three-dimensional microfabrication
$\vec{E}_0$	Spatial component of the electric field vector [$\mathrm{V\,m^{-1}}$]
E_p	Laser pulse energy [J]
$f(t)$	Normalized temporal distribution of the beam intensity [dimensionless]
FOM	Figure of merit
h	Planck's constant [J s]
$i(z, r)$	Spatial distribution of the beam intensity [$\mathrm{W\,cm^{-2}}$]
I	Intensity of a propagating beam [$\mathrm{W\,cm^{-2}}$]
I_0	Maximum on-axis intensity for a Gaussian beam [$\mathrm{W\,cm^{-2}}$]
I_th	Threshold intensity (minimum peak intensity at which polymerization occurs for a given exposure time) [$\mathrm{W\,cm^{-2}}$]
$\mathbf{I\cdot}$	Initiating radical
j, l, q	Integers [dimensionless]
J_1	First order Bessel function [dimensionless]
K	Amplitude of a beam wave vector ($K = 2\pi/\lambda$) [$\mathrm{m^{-1}}$]
$\vec{K}$	Wave vector of a beam [$\mathrm{m^{-1}}$]
m	Number of beams in a multi-beam interference configuration [dimensionless]
M	Monomer
MBI	Multi-beam interference
MEMS	Micro-electromechanical systems
MPE	Multi-photon excitation
n	Number of photons involved in MPE [dimensionless]
n_0	Linear refractive index of the medium [dimensionless]
N	Number density (concentration) of a species [$\mathrm{cm^{-3}}$]
NA	Numerical aperture of a lens [dimensionless]
N_C	Number density of chromophores present [$\mathrm{cm^{-3}}$]
Nd:YAG	Neodymium:Yttrium aluminum garnet
$N_{\mathrm{I\cdot}}$	Number density of initiating radicals generated [$\mathrm{cm^{-3}}$]
N_Inh	Number density of inhibitors present [$\mathrm{cm^{-3}}$]
OPE	One-photon excitation
Ormocer	Organically modified ceramic
$\langle P\rangle$	Average laser power [W]
$\langle P\rangle_\mathrm{min}$	Minimum average laser power for patterning a material [W]
	Repetition rate (number of laser pulse per unit time) [Hz]
PAG	Photo-acid generator
PhC	Photonic crystal
r	Radial coordinate (distance from optical axis) [m]
r'	Component or $\vec{r}$ along a given wave vector [m]
$\vec{r}$	Position vector in three-dimensional space [m]
R	Twice the radial coordinate of the point at which the intensity is $I_0/2$ [m]
$R_{1h\nu}$	Molecular one-photon excitation rate (number of molecules excited per unit volume and time via OPE) [$\mathrm{cm^{-3}\,s^{-1}}$]
$R_{2h\nu}$	Molecular two-photon excitation rate (number of molecules excited per unit volume and time via TPE) [$\mathrm{cm^{-3}\,s^{-1}}$]
$R_{nh\nu}$	Molecular n-photon excitation rate (number of molecules excited per unit volume and time via n-order MPE) [$\mathrm{cm^{-3}\,s^{-1}}$]
RMS	Root-mean-square
t	Time [s]
TEM_{00}	Lowest order transverse electromagnetic mode of a laser
Ti:S	Titanium:sapphire
TPE	Two-photon excitation
TPIP	Two-photon induced polymerization
z	Coordinate along the beam propagation direction [m]
z_R	Rayleigh range of a Gaussian beam; axial distance between the point of minimum beam waist and the point at which the waist has increased by a factor of $\sqrt{2}$ [m]
Z	Distance between the points of intensity $I_0/2$ along the coordinate z [m]
ζ	Longitudinal optical coordinate ($\zeta = 2\pi Z(\mathrm{NA})^2/n_0\lambda$) [dimensionless]
θ	Angle between a beam wave vector and the normal to a substrate [rad]
λ	Wavelength (in vacuum) [m]
Λ	Period of a one-dimensional grating [m]

ν	Frequency [s^{-1}]
$\boldsymbol{\pi}$	π-conjugated molecular fragment
ρ	Transverse optical coordinate ($\rho = 2\pi r\mathrm{NA}/\lambda$) [dimensionless]
$\sigma^{(1)}$	One-photon absorption cross-section [cm^2]
$\sigma^{(2)}$	Two-photon absorption cross-section [$\mathrm{cm}^4\ \mathrm{s\ photon}^{-1}$]
$\sigma^{(n)}$	n-photon absorption cross-section [$\mathrm{cm}^{2n}\ \mathrm{s}^{n-1}\ \mathrm{photon}^{-(n-1)}$]
τ_{ex}	Exposure time [s]
τ_{p}	Laser pulse duration [s]
$\phi_{\mathrm{c}}^{(n)}$	n-photon chemical quantum yield [(# of chemical species generated)/(# of n-photon-excited species)] [dimensionless]
$\phi_{\mathrm{H+}}$	Chemical yield for the generation of H^+ (number of H^+ generated per excited molecule) [dimensionless]
ω	Angular frequency ($\omega = 2\pi\nu$) [Hz]

See also

Chemical Applications of Lasers: Nonlinear Spectroscopies. **Diffractive Systems:** Applications of Diffractive and Micro-Optics in Lithography; Design and Fabrication of Diffractive Optical Elements. **Holography, Techniques:** Overview. **Imaging:** Volume Holographic Imaging. **Laser-Induced Damage of Optical Materials**. **Materials for Nonlinear Optics:** Organic Nonlinear Materials. **Microscopy:** Confocal Microscopy; Imaging Multiple Photon Fluorescence Microscopy; Nonlinear Microscopy; Overview. **Photonic Crystals:** Electromagnetic Theory; Nonlinear Optics in Photonic Crystal Fibers; Self-Assembled and Functionalized Photonic Crystals. **Ultrafast Laser Techniques:** Generation of Femtosecond Pulses.

Further Reading

Belfield KD, Schafer KJ, Liu YU, Liu J, Ren XB and van Stryland EW (2000) Multiphoton-absorbing organic materials for microfabrication, emerging optical applications and non-destructive three-dimensional imaging. *Journal of Physical Organic Chemistry* 13: 837–849.

Born M and Wolf E (1980) *Principles of Optics*, 6th edn. Cambridge, UK: Cambridge University Press.

Cumpston BH, Ananthavel SP, Barlow S, *et al.* (1999) Two-photon polymerization initiators for three-dimensional optical data storage and microfabrication. *Nature* 398: 51–54.

Joshi MP, Pudavar HE, Swiatkiewicz J, Prasad PN and Reinhardt BA (1999) Three-dimensional optical circuitry using two-photon-assisted polymerization. *Applied Physics Letters* 74: 170–172.

Kawata S and Sun H-B (2003) Two-photon photopolymerization as a tool for making micro-devices. *Applied Surface Science* 208–209: 153–158.

Kuebler SM, Rumi M, Watanabe T, *et al.* (2001) Optimizing two-photon initiators and exposure conditions for three-dimensional lithographic microfabrication. *Journal of Photopolymer Science and Technology* 14: 657–668.

Kuebler SM, Braun KL, Zhou W, *et al.* (2003) Design and application of high-sensitivity two-photon initiators for three-dimensional microfabrication. *Journal of Photochemistry and Photobiology A: Chemistry* 158: 163–170.

Martineau C, Anémian R, Andraud C, Wang I, Bouriau M and Baldeck PL (2002) Efficient initiators for two-photon induced polymerization in the visible range. *Chemical Physics Letters* 362: 291–295.

Odian G (1981) *Principles of Polymerization*, 2nd edn. New York: Wiley.

Pitts JD, Campagnola PJ, Epling GA and Goodman SL (2000) Submicron multiphoton free-form fabrication of proteins and polymers: studies of reaction efficiencies and applications in sustained release. *Macromolecules* 33: 1514–1523.

Ren Y, Yu X-Q, Zhang D-J, *et al.* (2002) Synthesis, structure and properties of a new two-photon photopolymerization initiator. *Journal of Materials Chemistry* 12: 3431–3437.

Strickler JH and Webb WW (1990) Two-photon excitation in laser scanning fluorescence microscopy. *Proceedings of the Society of Photo-Optical Instrumental Engineers* 1398: 107–118.

Sun H-B and Kawata S (2003) Two-photon laser precision microfabrication and its applications to micro-nano devices and systems. *Journal of Lightwave Technology* 21: 624–633.

Sun H-B, Maeda M, Takada K, Chon JWM, Gu M and Kawata S (2003) Experimental investigation of single voxels for laser nanofabrication via two-photon photopolymerization. *Applied Physics Letters* 83: 819–821.

Wu ES, Strickler JH, Harrell WR and Webb WW (1992) Two-photon lithography for microelectronic application. *Proceedings of the Society of Photo-Optical Instrumental Engineering* 1674: 776–782.

Wu P-W, Cheng W, Martini IB, Dunn B, Schwartz BJ and Yablonovitch E (2000) Two-photon photographic production of three-dimensional metallic structures within a dielectric matrix. *Advanced Materials* 12: 1438–1441.

Xu C and Webb WW (1997) Multiphoton excitation of molecular fluorophores and nonlinear laser microscopy. In: Lakowicz JR (ed.) *Topics in Fluorescence Spectroscopy*, vol. 5, pp. 471–540. New York: Plenum.

NONLINEAR OPTICS, BASICS

Contents

Cascading
$\chi^{(2)}$–Harmonic Generation
$\chi^{(3)}$–Third-Harmonic Generation
Four-Wave Mixing
Kramers–Krönig Relations in Nonlinear Optics
Nomenclature and Units
Nonlinear Optical Phase Conjugation
Photorefraction
Ultrafast and Intense-Field Nonlinear Optics

Cascading

G Assanto, University 'Roma Tre', Rome, Italy

G I Stegeman, University of Central Florida, Orlando, FL, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Historically the field of nonlinear optics has evolved along two main axes, depending on the order of the nonlinearity used. The phenomena associated with the second-order nonlinearity $\chi^{(2)}$ have dealt with frequency conversion requiring wavevector matching (i.e., momentum conservation), such as second harmonic and optical parametric generation. On the other hand, effects associated with the third-order susceptibility $\chi^{(3)}$ have focused on inherently phase-matched phenomena at a single frequency, for example an intensity-dependent refractive index or degenerate four-wave mixing.

In cascading, multiple sequential nonlinear events based on $\chi^{(2)}$ can mimic some well-known $\chi^{(3)}$ phenomena. For example, it leads to nonlinear phase shifts $\Delta\phi^{\mathrm{NL}}$ reminiscent of those obtained through self-phase modulation over a distance L, i.e.,

$$\Delta\phi^{\mathrm{NL}}(L, I) = k_0 L n_2 I \qquad [1]$$

where I is the irradiance, k_0 the vacuum wavevector, and n_2 the Kerr coefficient or nonlinear refractive index. These can be used for all-optical switching, the generation of spatio-temporal solitons, etc. Some of these cascading effects have been known from the very earliest days of nonlinear optics, but their effectiveness was not realized until recently, when it proved possible to phase match second-order interactions with usefully large nonlinearities. Note that the medium must be $\chi^{(2)}$-active, i.e., noncentrosymmetric, which usually requires crystals rather than amorphous materials (such as glass).

Here we review the basic concepts, the characteristic interactions, some of the numbers involved and, finally, a few applications.

Physics of Cascading

Nonlinear Phase Shift in Collinear Second Harmonic Generation

The most important cascading effect, the nonlinear phase shift, is rooted in the fundamentals of the parametric interaction when two or three waves of different frequencies ($\omega_3 = \omega_1 \pm \omega_2$) are coupled by the second-order susceptibility $\chi^{(2)}(-\omega_3; \omega_1, \pm\omega_2)$. The simplest case is 'Type I' second harmonic generation (SHG), in which one eigenwave at the fundamental (FF) and one at the harmonic frequency (SH) interact with $\omega_1 = \omega_2 = \frac{1}{2}\omega_3$. When the waves have different phase velocities, this process involves simultaneously up-conversion ($\omega_1 + \omega_1 \rightarrow \omega_3$) and down-conversion ($\omega_3 - \omega_1 \rightarrow \omega_1$). By the latter the FF is regenerated from the harmonic after a characteristic propagation distance called the coherence length. This phenomenon is cyclic (see Figure 1a).


$I_{2\omega}$
Δk_1
$\Delta k_2 > \Delta k_1$
Δk_2
Distance
(a)
v_ω
$\chi^{(2)}(-2\omega;\,\omega,\,\omega)$
$v_{2\omega}$
$\chi^{(2)}(-\omega;\,2\omega,\,-\omega)$
(b)

Figure 1 Phase-mismatched SHG. (a) Typical evolution of the generated second harmonic irradiance versus propagation for different mismatches. The period is twice the coherence length. (b) Intuitive picture of phase shift through cascading: the fraction of the initial energy which is first up-converted (SHG) and later down-converted (DFG), having traveled at a different phase velocity due to the wavevector mismatch, recombines with the through-FF causing an overall phase shift.

The field amplitudes in normalized form are

$$E_1(z,t) = \frac{1}{2}\sqrt{\frac{2}{c\varepsilon_0 n_1}}\,a_1(z)e^{i(\omega_1 t - k_1 z)} + \text{c.c.}$$
$$E_3(z,t) = \frac{1}{2}\sqrt{\frac{2}{c\varepsilon_0 n_3}}\,a_3(z)e^{i(\omega_3 t - k_3 z)} + \text{c.c.} \qquad [2]$$

where $|a_1|^2$ and $|a_3|^2$ are power densities, c is the speed of light in vacuum, and n_j and k_j are the refractive indices and wavevectors at angular frequencies $\omega_j\,(j = 1, 3)$, respectively. As is common in nonlinear optics, the efficiency of these processes depends on the irradiance of the different waves, and on the wavevector mismatch between them, i.e., $\Delta k = 2k_1 - k_3$ for collinear beams. Since the phase velocities of the two waves, $v_{\omega_1} = \omega_1/k_1$ and $v_{\omega_3} = \omega_3/k_3$, are generally different and $\Delta k \neq 0$, their phase fronts fall out of synchronism during propagation. This leads to a periodic oscillation with distance (coherence length $= \frac{1}{2}$period $= \pi/|\Delta k|$) in the irradiances of the fundamental and harmonic waves, conserving the total energy but giving rise to a cascading phase shift, as pictured in Figure 1b.

The equations that describe the evolution of the fields stem from coupled mode theory, and are given by

$$\frac{d}{dz}a_3(z) = -i\Gamma a_1^2(z)e^{-i\Delta k z}$$
$$\frac{d}{dz}a_1(z) = -i\Gamma a_3(z)a_1^*(z)e^{i\Delta k z} \qquad [3]$$

where

$$\Gamma = \frac{\omega_1 \chi_{\text{eff}}^{(2)}}{\sqrt{2n^3c^3\varepsilon_0}} \qquad [4]$$

$\chi_{\text{eff}}^{(2)}$ is the 'effective' nonlinearity (for a specific crystal orientation and field polarization) and we assumed $n = n_1 \cong n_3$. In the limit of a large mismatch, the energy conversion to the harmonic is negligibly small, and it is possible to find an analytical expression for an effective 'n_2', $n_{2,\text{eff}}$. In this limit $|a_1(z)| = |a_1(0)| =$ constant, and, in the absence of loss, solving for the small SH wave and substituting back into the equation for $da_1(z)/dz$ gives

$$\frac{d}{dz}a_1(z) = -i\frac{\Gamma^2}{\Delta k}\Big\{1 - \cos(\Delta k z) - i\sin(\Delta k z)\Big\}|a_1(0)|^2 a_1(z) \qquad [5]$$

By comparing this with the corresponding equation based on n_2 ($\propto \chi^{(3)}[-\omega; \omega, -\omega, \omega]$) and describing self-phase modulation, namely

$$\frac{d}{dz}a_1(z) = -in_2\frac{\omega_1}{c}|a_1(z)|^2 a_1(z) \qquad [6]$$

we can define an equivalent nonlinear refractive index

$$n_2(z) = \frac{\pi\{\chi_{\text{eff}}^{(2)}\}^2}{2\varepsilon_0 c n^4 \lambda_1 \Delta k}[1 - \cos(\Delta k z)] \qquad [7]$$

which turns out to be strictly nonlocal because it relies on propagation. Since the cos(Δkz) term oscillates rapidly in space, the above averages to

$$n_{2,\text{eff}} = \frac{\pi\{\chi_{\text{eff}}^{(2)}\}^2}{2\varepsilon_0 c n^4 \lambda_1 \Delta k} \qquad [8]$$

In this so-called 'Kerr limit' cascading leads to a Kerr-like nonlinear response, with either a self-focusing ($\Delta k > 0$, $n_{2,\text{eff}} > 0$) or a self-defocusing nonlinearity, depending on the sign of Δk.

It is worthwhile to link the above equations to the physics of cascading with a simple argument. The evolution of the waves on propagation depends on their fields (in both amplitude and phase) at the input. When only the fundamental beam at $\omega = \omega_1$ is incident (the classical case of SHG), the harmonic is initially up-converted $\pi/2$ out of phase with the input (first of eqns [3]) via $\chi^{(2)}(-2\omega; \omega, \omega)$. If $\Delta k = 0$, the phase fronts travel at the same velocity and the relative phase is locked in at $\pi/2$. Difference frequency generation (DFG, second of eqns [3]) results in a down-converted fundamental which is an additional $\pi/2$ out of phase, i.e., exactly out of phase with the original input field. This leads to the monotonic depletion of the input and the growth of the SH with distance. If $\Delta k \neq 0$, there is only partial and periodic conversion to the harmonic, the wavefronts travel at different velocities (v_ω and $v_{2\omega}$, respectively), and the relative phase between the two waves changes with distance. As a result, the down-converted FF is no longer π out of phase with the input, thereby changing the overall phase of the total input-frequency wave by a cascaded amount $\Delta\phi^{\text{NL}}$. This is the mechanism sketched in Figure 1b and buried in the better-known Maker-fringe effect represented in Figure 1a. Its magnitude depends on the irradiance and the mismatch, and its sign on that of Δk (see eqn [8]). The higher the input irradiance, the larger the harmonic conversion, and hence the larger $\Delta\phi^{\text{NL}}$.

Alternatively, with a harmonic input at high irradiance and a weak seed at the FF, parametric amplification makes the fundamental grow via down-conversion. If $\Delta k = k_3 - 2k_1 \neq 0$, self-focusing (-defocusing) is obtained on the strong harmonic for $\Delta k > 0$ ($\Delta k < 0$). These phenomena can be generalized to the nondegenerate cases of sum and difference frequency generation, keeping in mind that when using three input waves their mutual phase relationship is essential in determining the details of the interaction.

The solutions to eqns [3] can be obtained numerically or written in terms of Jacobi elliptic integrals subject to boundary conditions ($a_3(0) = 0$, $a_1(0) \neq 0$) at $z = 0$, providing additional insight into the cascading phenomenon. In contrast to the Kerr case given by eqn [1], the variation in n_2 with distance implies a staircase-like increase in $\Delta\phi^{\text{NL}}$ with distance for various detunings ΔkL, as shown in Figure 2a. This is consistent with our intuitive picture above, the increase in $\Delta\phi^{\text{NL}}$ being maximized where the fundamental is the smallest (see Figure 2b for the oscillations in the fundamental amplitude), with the step-period corresponding to twice the coherence length. Conversely, for a fixed input irradiance, the evolution of $\Delta\phi^{\text{NL}}$ exhibits two extrema with detuning ΔkL, as shown in Figure 3a. Note also that, for small ΔkL and large



Figure 2 Calculated nonlinear phase (a) and throughput (b) of the fundamental field versus normalized propagation distance, for three values of phase mismatch.



Figure 3 Calculated FF phase shift (a) and generated SH fraction (b) versus phase mismatch, i.e., the detuning curve, for three different nonlinear strengths (unitary FF irradiance).

(unrealistically high) irradiances, the increase in $\Delta\phi^{\mathrm{NL}}$ tends to become proportional to the field amplitude, a clear indication that cascading depends on a different order of nonlinearity than $\chi^{(3)}$, namely $\chi^{(2)}$. On the other hand, for large ΔkL the growth of $\Delta\phi^{\mathrm{NL}}$ is slower but linear with distance and irradiance, as in eqn [1].

There are trade-offs between the fundamental output and the net nonlinear phase shift. This is clearly visible in Figures 3a,b: the maxima in $\Delta\phi^{\mathrm{NL}}$ correspond to a reduced FF throughput. Although it is possible to operate cw at the zeros of the SHG, their location changes with the irradiances required for useful phase shifts ($>\pi$), complicating the trade-offs and the response to temporal pulses (encompassing a continuous irradiance distribution). The problem can be alleviated at the expense of reducing the net phase shift for a given irradiance and propagation length, by introducing regions with a nonuniform matching condition at both ends of the sample. The goal at the input end is to first adiabatically generate the SH required for optimum $\Delta\phi^{\mathrm{NL}}$. At the output, this harmonic is adiabatically converted back to the FF. The corresponding output for wavelengths larger than the phase-matching condition exhibits a $\Delta\phi^{\mathrm{NL}}$ with negligible fundamental depletion. This approach has been used in temperature-tuned and quasi phase matched (QPM, where a periodic modulation of the nonlinearity provides phase matching via the additional grating momentum) lithium niobate waveguides to generate phase shifts of π with less than 10% net loss of the fundamental wave to the harmonic.

While the preceding discussion has focused on Type I SHG, it is also valid for Type II SHG (i.e., with two FF input waves), provided the two fundamental inputs have equal input energy. In fact, an input imbalance between the two fundamental polarizations could give rise to a phase shift on the weaker field even when $\Delta k = 0$, leading to all-optical modulation and transistor action, as demonstrated in potassium titanyl phosphate (KTP) crystals.

Finally, due to the nature of the quadratic nonlinearity, the phase and/or amplitude of a coherent SH seed can have a large effect on the cascaded outcome, both in the phase and amplitude of the fundamental, as shown in Figure 4 for a fixed irradiance seed 1000 times weaker than the FF input. This can be used in seed-controlled optical processors.



Figure 4 FF transmission (solid line) and phase shift (dashed line) versus the relative phase of a much weaker (three orders of magnitude) SH seed. Here perfect phase matching was assumed.



Figure 5 Wavelength shifter: (a) single-pass and (b) double-pass configurations. In (b) a dichroic mirror reflects the second harmonic of the pump.

Frequency Shifting

In the nondegenerate case of $\chi^{(2)}$ sum and difference frequency generation, two successive operations can perform the useful function of a frequency shifter (Figure 5). The idea is to shift the signal frequency ($\omega_p - \delta$) by first generating from the pump (ω_p) a second harmonic ($2\omega_p$), followed by DFG involving the latter and the signal. This leads to an output at $\omega_p + \delta$ through $\chi^{(2)}(-(\omega_p + \delta); 2\omega_p, -(\omega_p - \delta))$, i.e., a frequency shift of 2δ with an output spectrally mirror-imaged about the pump frequency. This feature is useful in WDM (wavelength division multiplexing) systems, and guarantees a protocol-insensitive wavelength shift with an additional phase conjugation useful in dispersion-compensating schemes. Notice that, since $\omega_p + \delta \cong \omega_p - \delta$ and $\delta << \omega_p$, the bandwidth is large because the interaction is near the degeneracy point.

Figure 5 shows two possible configurations for the same device length. The efficiency of the process can be increased in a double-pass geometry by using a back-propagating signal and a mirror-coated facet to reflect the SH, as sketched in Figure 5b. The best results to date were obtained at communication wavelengths with single-pass waveguides in periodically poled (QPM) $LiNbO_3$, including shift of multiple wavelength-channels with low cross-talk.

Multiple Beam Generation

Two successive $\chi^{(2)}$ processes can also be used to mimic three-wave mixing, a classic noncollinear $\chi^{(3)}$ interaction where two photons are taken out of one beam and one out of the second. In cascading, first a second harmonic is generated by one of the inputs, and then difference frequency mixing (DFM) between that SH and the second input leads to the signal of interest. In the simplest configuration, two equi-frequency (ω) beams of wavevectors $\mathbf{k}_1$ and $\mathbf{k}_2$ are incident in slightly different directions close to phase-matching and overlap inside the sample. When wave 1 is doubled (2ω) and wave 2 mixes with this harmonic via DFM, a new beam (at $2\omega - \omega \rightarrow \omega$) is generated with wavevector $2\mathbf{k}_1 - \mathbf{k}_2$. Of course the complementary output at $2\mathbf{k}_2 - \mathbf{k}_1$ is also generated via the SHG of wave 2. If these two new beams are strong enough, they can generate another pair via cascading, and so on. The generation of more than six extra beams has been demonstrated in β-barium borate with 1064 nm inputs.

This interaction can be applied to the control of the frequency chirp in pulses. For example, if wave 1 has a frequency chirp α_1 and wave 2 a chirp α_2, then the chirp of the beam scattered into the direction $2\mathbf{k}_1 - \mathbf{k}_2$ is $2\alpha_1 - \alpha_2$. This becomes especially interesting if $\alpha_2 = -\alpha_1$ so that the chirp in the new beam is $3\alpha_1$, as observed and subsequently employed in enhancing pulse compression. Note that, since a cascaded phase shift occurs on the down-conversion step back to the original fundamental (wave 1), it is not present in the scattered beam resulting in a clean transfer of the chirp.

Typical Numbers

From eqn [8] it is clear that the figure of merit (FOM) for cascaded processes is the same as for all second-order processes, namely $|\chi^{(2)}|^2/n^4$. The key is to find materials phase-matchable at the wavelengths of interest. Therefore, basically any material that is suited for frequency conversion, either SHG or parametric generation, will work. The most versatile material, which also has the largest easily usable nonlinear coefficient (18 pm/V), is lithium niobate when QPM is employed. As a reference, Table 1 gives the maximum $n_{2,\mathrm{eff}}$ for 1-cm-long samples, obtained by extrapolating eqn [8] to the ΔkL which maximizes the nonlinear phase shift. This is not strictly valid for such small ΔkL, but it is a useful estimate.

Other Implications of Cascading

A straightforward conclusion that could be drawn is that cascading with its $n_{2,\mathrm{eff}}$ and $\Delta\phi^{\mathrm{NL}}$ can generally replace the Kerr n_2. This is true for self-phase modulation and the applications stemming from it, including all-optical guided-wave switches such as directional couplers, Mach–Zehnder interferometers, etc. However, this is not necessarily true for other applications, because all the waves have to be coupled through $\chi^{(2)}$ interactions (at most three at a time) and must be nearly phase-matched for efficient effects. For example, cross-phase modulation between two input FF polarization components is feasible via Type II SHG cascading, but specific wavelengths will require different crystals, or crystal cuts. The nonlinear phase shift can also be used in all-optical devices for analog processing, such as isolators, modulators, and transistors, in laser mode-locking, etc.

In the following subsections we discuss a few additional applications. Specifically, we describe a non-reciprocal device that operates as an isolator, and the cascading of beams of finite extent in space or time. The latter can counterbalance either spatial diffraction or temporal dispersion or both and gives rise to solitons of various dimensionalities.

An Optical Diode

A nonlinear response, when combined with a device structure that is asymmetric about its midpoint, can provide nonreciprocal behavior upon excitation of the structure (crystal, waveguide) from different ends.

Table 1 Figures for cascading in various materials. The effective nonlinear coefficient is estimated under optimum conditions and a 1 cm propagation length

Material L = *1 cm*	d_{ii} *(pm/V)*	d_{ij} *(pm/V)*	$n_{2,\mathit{eff}}$ *(cm^2/W)*
$LiNbO_3$	36		2×10^{-11}
$LiNbO_3$		5.8	5×10^{-13}
MNA(1)	165		7×10^{-10}
NPP(2)		84	2×10^{-10}
DAST(3)	600		6×10^{-9}

(1)MNA: 2-methyl-4-nitroaniline
(2)NPP: N-(4-nitrophenyl)-(L)-prolinol
(3)DAST: dimethyl amino stilbazolium tosylate

In analogy to the standard electronic element, we can refer to such device as a power-dependent optical diode. Dealing with quadratically nonlinear waveguides, simple ways to induce a directional asymmetry are variations in wavevector mismatch, or in QPM periodicity. A mismatch profile which depends on distance from one end, or a localized defect (i.e., an isolated domain in a QPM grating), will give rise to different throughputs when the waveguide is excited from opposite sides, up to complete FF depletion in one direction, and complete transmission in the opposite one. This can be explained by the fact that the output depends on the evolution and interaction of the FF field with its harmonic. The amount and phase of the latter, however, do depend on the details of the propagation path and can substantially change the FF throughput as in the case of seeded SHG.

The sketch of an all-optical diode in a QPM waveguide with its calculated response is shown in Figure 6a,b. Clearly, total depletion is obtained via SHG in backward propagation, whereas unity FF transmission is recovered by the insertion of a phase discontinuity (and seeded interaction) in the forward path. As demonstrated at 1.55 μm in lithium niobate, different degrees of isolation are available at various excitations, with a large extinction ratio at a given power when launching FF waves from opposite ends.

Quadratic Solitons

When beams propagate in a two- (planar waveguides) or three-dimensional (bulk) medium with a quadratic response, cascading induces a nonlinear phase-front distortion which, coupled to the inherent parametric gain, can effectively counteract diffraction and lead to diffractionless propagation or 'spatial solitons' (Figure 7). In contrast to the Kerr case, such solitons are multifrequency solutions or 'simultons' with field components (FF and SH in the degenerate SHG process) bound together in propagation despite possible walk-off or transverse velocity mismatch. Moreover, since the second-order nonlinearity is inherently saturable, the solitons are stable and robust even in bulk media, and provide 'clean' filtered beam profiles at FF and SH frequencies, as has been demonstrated in KTP. Just like other cascading phenomena, quadratic solitons can be controlled by a weak seed, by polarization imbalance at the input (Type II SHG), by direction of propagation (due to birefringence), by phase mismatch, etc. Employing quadratic spatial solitons, phenomena such as collisions, soliton fusion, spatial reshaping, and transverse light localization and instabilities have been studied and constitute an active field of investigation.



Figure 6 All-optical diode: (a) sketch of implementation with an engineered 'defect' in a QPM grating (*z*-cut periodically poled lithium niobate), and (b) example of FF transmittance *T* versus propagation for forward (solid line) and backward (dashed line) FF excitation of power P_λ.



Figure 7 Top: sketch of a quadratic spatial soliton excited by an FF input: when the irradiance is high enough, linear diffraction is overcome by parametric self-trapping and a two-color simulton is obtained. Bottom: sample photograph (top view) of a quadratic soliton experimentally observed in a potassium niobate crystal excited by a 1064-nm laser beam.

When employing pulses, the cascaded phase shift can balance dispersion (material, chromatic, or photonics bandgap) leading to temporal simultons with frequency components locked together despite their individual group-velocity differences and dispersion. This feature can also substantially broaden the bandwidth available for parametric generation. Finally, in analogy to the cubic case, a combination of space and time effects is expected to lead to the formation of 'light bullets' in (3 + 1) dimensions.

List of Units and Nomenclature

Angular frequency	$[s^{-1}]$	ω
Dielectric constant of vacuum	$[FV^{-1}\,m^{-1}]$	ε_0

Electric field	[V m^{-1}]	E
Irradiance, intensity	[W m^{-2}]	I
Length	[m]	L
Refractive index	[ ]	n
Speed of light in vacuum	[m s^{-1}]	c
Second-order electronic susceptibility	[m V^{-1}]	$\chi^{(2)}$
Third-order electronic susceptibility	[m^2 V^{-2}]	$\chi^{(3)}$
Wavevector in medium	[m^{-1}]	$k = n\omega/c$
Wavevector in vacuum	[m^{-1}]	$k_0 = \omega/c$
Wavelength	[m]	$\lambda = 2\pi n/k = 2\pi/k_0$

See also

Solitons: Bright Spatial Solitons; Soliton Communication Systems. **Spectroscopy:** Second Harmonic Spectroscopy.

Further Reading

Assanto G (1995) All-optical switching in integrated structures. In: DeGiorgio V and Flytzanis C (eds) *Nonlinear Optical Materials: Principles and Applications*. Amsterdam: IOS Press.

Assanto G and Stegeman GI (2002) Simple physics of quadratic spatial solitons. *Optics Express* 10: 388–396.

Assanto G, Stegeman GI, Sheik-Bahae M and VanStryland E (1993) All optical switching devices based on large nonlinear phase shifts from second harmonic generation. *Applied Physics Letters* 62: 1323–1325.

Assanto G, Stegeman GI, Sheik-Bahae M and VanStryland EW (1995) Coherent interactions for all-optical signal processing via quadratic nonlinearities. *IEEE Journal of Quantum Electron* 31: 673.

Assanto G, Stegeman GI and Schiek R (1998) Thin film devices for all-optical switching and processing via quadratic nonlinearities. *Thin Solid Films* 331: 291–297.

Boardman AD (ed.) (1999) *Advanced Photonics with Second-Order Optically Nonlinear Processes*. Dordrecht, The Netherlands: Kluwer.

Boardman AD (ed.) (2001) *Soliton Driven Photonics*. Dordrecht, The Netherlands: Kluwer.

Gallo K and Assanto G (1999) Analysis of lithium niobate all-optical wavelength shifters for the third spectral window. *Journal of the Optical Society of America B* 16: 741–753.

Gallo K, Assanto G, Parameswaran KR and Fejer MM (2001) All-optical diode in a periodically poled lithium niobate waveguide. *Applied Physics Letters* 79: 314–316.

Kajzar F and Reinisch R (eds) (1997) *Beam Shaping and Control with Nonlinear Optics*. New York: Plenum Press.

Stegeman GI, Hagan DJ and Torner L (1996) $\chi^{(2)}$ cascading phenomena and their applications to all-optical signal processing, mode-locking, pulse compression and solitons. *Journal of Optics and Quantum Electronics* 28: 1691.

Stegeman GI and Assanto G (1999) Nonlinear integrated optical devices. In: Murphy EJ (ed.) *Design and Application of Integrated Optical Circuits and Components*. New York: Marcel Dekker.

$\chi^{(2)}$–Harmonic Generation

R C Eckardt, Cleveland Crystals, Inc., Highland Heights, OH, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical harmonic generation is nonlinear conversion of laser output to light, of a frequency that is an integer multiple of that of the fundamental. It is used over a wide range of applications, from battery-operated, pencil-sized pointers emitting less than a milliwatt of light to installations that occupy large buildings and generate thousands of Joules of ultraviolet energy in nanosecond-duration pulses. The applications also range from frequency-stable continuous-wave light to generation of pulses a few femtoseconds in duration. Laser output with specific properties may only be available in narrow spectral regions, and harmonic generation is a method to convert the laser output to spectral regions of shorter wavelength. It is customary to call light of twice the frequency of the fundamental the second harmonic; three times the third harmonic, and so on.

The conversion of light by harmonic generation is a process that is driven by the nonlinear electric polarization. The total polarization $\mathbf{P}(t)$, including the linear term, is a vector quantity related to the electric field $\mathbf{E}(t)$ by the susceptibility tensors

χ of a material:

$$\mathbf{P}(t) = \varepsilon_0\chi^{(1)} : \mathbf{E}(t) + \varepsilon_0\chi^{(2)} : \mathbf{E}(t)\mathbf{E}(t) + \varepsilon_0\chi^{(3)} : \mathbf{E}(t)\mathbf{E}(t)\mathbf{E}(t) + \dots, \qquad [1]$$

where $\varepsilon_0 \cong 8.854 \times 10^{-12}$ C/N·m^2 is the permittivity of free space. The first-order tensor describes linear optical properties on the material. The second-order tensor $\chi^{(2)}$ describes second-harmonic generation and sum- and difference-frequency generation. This is the term that is of interest here. The second-order nonlinear optical tensor, equal to half the second-order susceptibility, is used widely instead of the susceptibility:

$$d_{ijk} = \chi^{(2)}_{ijk}/2 \qquad [2]$$

In calculations of harmonic generation and sum- and difference-frequency generation, the coefficient is usually reduced to a scalar quantity d_{eff}, the effective nonlinear coefficient that expresses the relationship between only the specific vector components involved in an interaction. The second-order optical nonlinearity, when present, is usually significantly larger than higher-order optical nonlinearities. When optical frequency conversion is possible, using the second-order nonlinearity, it is generally preferred. Any material that has inversion symmetry, however, will have vanishing second-order nonlinearity. Although there is continuing interest in developing other materials, such as poled polymers for future applications, materials for current practical applications are restricted to noncentrosymmetric crystals.

This article will provide a description of the process of optical harmonic generation and discuss some of the concerns in the design of harmonic generation systems. In many cases, harmonic generation can be modeled accurately by analytic or numerical techniques. Some of the theoretical development that is the basis for this modeling will be presented along with examples. There are several essential considerations that must be made in selecting a harmonic generation process. These involve both material properties and conditioning of the fundamental radiation.

General Considerations

The nonlinear optical material must be highly transmitting at the fundamental and harmonic wavelengths and must have a laser-induced-damage threshold high enough to allow optical intensities that will provide adequate conversion efficiency. Phase matching must be possible in the material. Other material characteristics must be considered for specific applications. The harmonic generation process requires that the phase velocities of the fundamental and harmonic radiation be matched. Without phase matching, power converted to the harmonic is back converted to the fundamental in a rapid oscillation, and harmonic conversion remains at low levels. The material also needs to be of good optical quality to provide optical transmission without distortion, which would destroy the phase relationship. Continuous-wave harmonic generation may involve local intensities of the order of 1 megawatt per square cm (1 MW/cm^2). Pulsed applications with Q-switched laser output of a few nanoseconds duration typically employ intensities of several hundred MW/cm^2, and harmonic-generation applications with mode-locked lasers may involve pulse durations of tens of femtoseconds with peak intensities of tens of gigawatts per square cm. Many other properties are desirable, but it is necessary to work within the limitations of available materials.

Phase matching is an essential requirement. When harmonic and fundamental waves of different eigen polarizations are coupled through the nonlinear optical tensor, it may be possible to use crystal birefringence to provide phase matching. The birefringence, if large enough, can compensate dispersion. The fundamental wave is introduced into the crystal with the polarization of the larger refractive index, and the harmonic is generated in the polarization of the smaller index. This is a description of type-I birefringent phase matching. Phase matching is achieved by selecting the direction of propagation in the crystal or by changing the temperature of the crystal. Type-II phase matching with the fundamental wave resolved into the two eigen polarizations is possible with large birefringence. Quasi phase matching involves periodically structuring the nonlinear material in a way that spatial modulation of the optical nonlinearity compensates for dispersion. Quasi phase matching is tuned by selection of the modulation period, and temperature control may provide a fine tuning. Periodic poling, one method of quasi phase matching, involves changing the orientation of ferroelectric domains after each coherence length of the harmonic generation process. These methods of phase matching are sketched in Figure 1.

The physical arrangement of the harmonic generation process depends on properties of the available fundamental light and the properties of the selected nonlinear material. The single-pass techniques, shown in Figure 1, may have the advantage of simplicity, but expanding or focusing the fundamental beam may be required. Crystal length and clear



Figure 1 Different methods of phase matching optical harmonic generation are illustrated. The arrows indicate the directions of electric-field polarization and directions of propagation.



Figure 2 Placing a harmonic-generation crystal inside a laser cavity with mirrors highly reflecting at the laser wavelength is one technique of increasing the intensity of the fundamental beam.

aperture need to be selected. Intracavity harmonic generation (Figure 2), or external-resonant-cavity harmonic generation, may provide advantages in other cases. Analysis of harmonic generation provides the means to select among the options.

Basic Equations

Much of the analysis of second-harmonic generation follows from the differential equations that describe the interaction between the fundamental and harmonic fields, and it is appropriate to describe the development of these coupled equations. The wave equation:

$$\nabla^2\mathbf{E}(\mathbf{r},t) - \mu_0\sigma\frac{\partial\mathbf{E}(\mathbf{r},t)}{\partial t} - \mu_0\varepsilon_0\frac{\partial^2\mathbf{E}(\mathbf{r},t)}{\partial t^2} = \mu_0\frac{\partial^2\mathbf{P}(\mathbf{r},t)}{\partial t^2} \qquad [3]$$

is obtained from Maxwell's equations. Here $\mu_0 = 4\pi\times10^{-7}$ is the permeability of free space, and σ is the conductivity, which later will be incorporated into the optical absorption coefficient $\alpha = \mu_0\sigma c/2$, and $(\varepsilon_0\mu_0)^{-1/2} = c \cong 2.998\times10^8$ m/s is the speed of light in vacuum. The electric field of a planewave, at angular frequency ω, is expressed in complex notation as the product of a slowly varying complex amplitude and a carrier wave:

$$\mathbf{E}_\omega(\mathbf{r},t) = (1/2)\{\mathbf{E}_\omega \exp \mathrm{i}(\mathbf{k}_\omega\cdot\mathbf{r} - \omega t) + \text{c.c.}\} \qquad [4]$$

The intensity of this plane wave is

$$I_\omega = (nc\varepsilon_0/2)|E_\omega|^2 \qquad [5]$$

Here n is the index of refraction of the material in which E is specified. The nonlinear polarization resulting from the second-order susceptibility driven by the plane wave $\mathbf{E}_\omega(\mathbf{r},t)$ is expressed as

$$\mathbf{P}_{2\omega}^{\mathrm{NL}}(\mathbf{r},t) = (1/2)\{\mathbf{P}_{2\omega}^{\mathrm{NL}} \exp \mathrm{i}(2\mathbf{k}_\omega\cdot\mathbf{r} - 2\omega t) + \text{c.c.}\} \qquad [6]$$

The individual components of the polarization amplitude vector are

$$P_{2\omega,i}^{\mathrm{NL}} = \varepsilon_0 \sum_{j,k} d_{ijk}(-2\omega;\omega,\omega)E_{\omega,j}E_{\omega,k} \qquad [7]$$

If the nonlinear polarization is produced by two distinguishable waves, such as for sum-frequency generation of the third harmonic by the second harmonic and the fundamental, the nonlinear polarization is

$$\mathbf{P}_3^{\mathrm{NL}}(\mathbf{r},t) = (1/2)\big\{\mathbf{P}_3^{\mathrm{NL}} \exp \mathrm{i}[(\mathbf{k}_1 + \mathbf{k}_2)\cdot\mathbf{r} - (\omega_1 + \omega_2)t] + \text{c.c.}\big\} \qquad [8]$$

where

$$P_{3,i}^{\mathrm{NL}} = 2\varepsilon_0 \sum_{j,k} d_{ijk}(-\omega_3;\omega_1,\omega_2)E_{1,j}E_{2,k} \qquad [9]$$

and

$$\omega_3 = \omega_1 + \omega_2 \qquad [10]$$

A number of simplifications are used to arrive at the coupled equations for harmonic generation with monochromatic plane waves. All waves are assumed to be propagating collinearly in the z direction. Only the vector components involved in the interaction are retained, and the nonlinear optical tensor is replaced by the scalar effective nonlinear coefficient d_{eff}. Finally, the slowly varying envelope approximation is invoked and the higher-order derivatives of the amplitudes are ignored, as are time derivatives of the envelopes. The wave equation simplifies to

$$\frac{\mathrm{d}E(z)}{\mathrm{d}z}+\alpha E(z)=\mathrm{i}\frac{\mu_0 c\omega}{2n}P(z) \qquad [11]$$

where n is the index of refraction.

With three distinguishable waves, as with sum-frequency generation and type-II second-harmonic generation, there are three coupled equations:

$$\frac{\mathrm{d}E_3(z)}{\mathrm{d}z}+\alpha_3 E_3(z)=\mathrm{i}\frac{\omega_3 d_{\text{eff}}}{n_3 c}E_1(z)E_2(z)\exp(-\mathrm{i}\Delta kz) \qquad [12]$$

$$\frac{\mathrm{d}E_1(z)}{\mathrm{d}z}+\alpha_1 E_1(z)=\mathrm{i}\frac{\omega_1 d_{\text{eff}}}{n_1 c}E_3(z)E_2^*(z)\exp(\mathrm{i}\Delta kz) \qquad [13]$$

$$\frac{\mathrm{d}E_2(z)}{\mathrm{d}z}+\alpha_2 E_2(z)=\mathrm{i}\frac{\omega_2 d_{\text{eff}}}{n_2 c}E_3(z)E_1^*(z)\exp(\mathrm{i}\Delta kz) \qquad [14]$$

Here the wave vector mismatch is

$$\Delta k = k_3 - k_1 - k_2 \qquad [15]$$

and

$$\omega_3 = \omega_1 + \omega_2 \qquad [16]$$

with the convention of $\omega_1 \le \omega_2 < \omega_3$. The indices of refraction of the three waves are n_1, n_2, and n_3, respectively, and α_1, α_2, and α_3 are the respective amplitude absorption coefficients.

With type-I second-harmonic generation, the fundamental field consists of only a single eigen polarization, and there are two coupled equations:

$$\frac{\mathrm{d}E_{2\omega}(z)}{\mathrm{d}z}+\alpha_{2\omega} E_{2\omega}(z)=\mathrm{i}\frac{\omega d_{\text{eff}}}{n_{2\omega} c}E_\omega(z)E_\omega(z)\exp(-\mathrm{i}\Delta kz) \qquad [17]$$

$$\frac{\mathrm{d}E_\omega(z)}{\mathrm{d}z}+\alpha_\omega E_\omega(z)=\mathrm{i}\frac{\omega d_{\text{eff}}}{n_\omega c}E_\omega(z)E_\omega^*(z)\exp(\mathrm{i}\Delta kz) \qquad [18]$$

Indices of refraction at the harmonic and fundamental are $n_{2\omega}$ and n_ω respectively; $\alpha_{2\omega}$ and α_ω are the respective absorption coefficients; and the wavevector mismatch is

$$\Delta k = k_{2\omega} - 2k_\omega \qquad [19]$$

The equations for type-II second-harmonic generation, where $\omega_1 = \omega_2$ and $\omega_3 = 2\omega_1$, become equivalent for those for type-I second-harmonic generation, providing intensities of the two fundamental polarizations are equal, $I_1 = I_2$ and $\alpha_\omega = \alpha_{2\omega}$.

Steady-State Solutions

Three monochromatic planewave solutions for type-I second-harmonic generation are discussed. These solutions address type-I harmonic generation; first for low levels of conversion with arbitrary phase mismatch; next for high levels of conversion with perfect phase matching; and last for arbitrary levels of conversion with arbitrary amounts of phase mismatch. Near-field and focused-beam approximations also exist. Beyond that, numerical techniques, such as split-step Fourier transform methods can handle more complicated conditions. The simple approximations of monochromatic planewaves, or steady-state solutions, however, yield useful information.

The coupled equations for type-I second-harmonic generation can be solved by simple integration for low levels of fundamental depletion, where $E_\omega(z)$ is treated as constant and there is insignificant absorption. Initial conditions are $I_\omega(0)$, incident on the crystal and $I_{2\omega}(0) = 0$. Integration of the equation for the harmonic electric field yields an expression for electric field after propagating a distance of l in the crystal:

$$E_{2\omega}(l)=\frac{\omega d_{\text{eff}}E_\omega^2(0)}{n_{2\omega}c}\frac{1}{\Delta k}\left\{\exp \mathrm{i}(k_{2\omega}l)-\exp \mathrm{i}(2k_\omega l)\right\} \qquad [20]$$

Expressed as intensity the solution is

$$I_{2\omega}(l)=I_\omega(0)\Gamma^2 l^2 \operatorname{sinc}^2(\Delta kl/2) \qquad [21]$$

where $\operatorname{sinc}(x) = \sin(x)/x$ and

$$\Gamma^2 = 2\omega^2 d_{\text{eff}}^2 I_\omega(0)/(n_{2\omega}n_\omega^2 c^3 \varepsilon_0) \qquad [22]$$

When $\Delta k = 0$ and $\alpha_\omega = \alpha_{2\omega} = 0$, conditions of perfect phase matching and no absorption, the coupled equations for type-I second-harmonic generation can be combined into a single equation. This is done using conservation of energy, which requires $E_\omega^2(z) + E_{2\omega}^2(z) = E_\omega^2(0)$, in this case with no initial harmonic intensity. The equation can then be manipulated into a standard integral that yields the inverse hyperbolic tangent. Rewritten and expressed in terms of intensity the result is

$$I_{2\omega}(l) = I_{\omega}(0)\tanh^2(\Gamma l) \qquad [23]$$

The two solutions for $I_{2\omega}(l)$ given above serve well for a number of applications. The $\mathrm{sinc}^2(\Delta k \cdot l/2)$ function is widely used to determine phase-matching acceptances. The $\tanh^2(\Gamma l)$ function is a good approximation for local conversion with large, well-collimated fundamental beams.

An exact solution to the coupled equations, however, gives insight to conditions such as high initial fundamental intensity with small amounts of phase mismatch. After extensive algebraic manipulation, a solution in the form of a Jacobian elliptic function $\mathrm{sn}(u|m)$ is obtained:

$$I_{2\omega}(l) = I_{\omega}(0)\nu_b^2 \mathrm{sn}^2\left(\frac{\Gamma l}{\nu_b}\middle|\nu_b^4\right) \qquad [24]$$

where

$$1/\nu_b = \Delta s/4 + \sqrt{1 + (\Delta s/4)^2} \qquad [25]$$

$$\Delta s = \Delta k/\Gamma$$

and Δk and Γ retain the earlier definitions. This solution can be extended to provide the phase of the fundamental and harmonic as the conversion process evolves. Expressing the complex harmonic and fundamental field amplitudes as the product of a real amplitude and a complex exponential:

$$E(z) = A(z)\exp \mathrm{i}\phi(z) \qquad [26]$$

the harmonic phase is

$$\phi_{2\omega}(z) = (\pi - \Delta kz)/2 \qquad [27]$$

The fundamental phase, however, is found to be dependent on the conversion process:

$$\begin{aligned}\phi_{\omega}(z) = {} & (1/2)\arccos[A_{2\omega}(z)\Delta k/(2\kappa A_{\omega}^2(z))] \\ & - (\pi - \Delta kz)/z \end{aligned} \qquad [28]$$

where $\kappa = \omega d_{\mathrm{eff}}/(n_{\omega}c)$. Small amounts of phase mismatch significantly change the phase of the fundamental at high levels of conversion. This phase change is used for switching applications in waveguide interferometers. It also makes phase-matching requirements more stringent at high levels of conversion. The three planewave solutions are illustrated in Figure 3. The narrowing of phase matching at higher conversion is illustrated in Figure 4.



Figure 3 Monochromatic plane-wave solutions of the coupled equations for second-harmonic generation are illustrated for different amounts of wavevector mismatch. The solution takes the form $\tanh^2(\Gamma l)$ when $\Delta k = 0$ and $(\Gamma l)^2\mathrm{sinc}^2(\Delta kl/2)$ when conversion is small.

There is a Jacobian elliptic function solution for intensities with the coupled waves of type-II second-harmonic generation and sum-frequency generation. The phases of the individual waves can be recovered with elliptic integrals of the third kind. Both sets of equations, the two coupled equations for type-I phase matching and the three coupled equations for type-II phase matching, are amenable to numerical solution by Runge–Kutta methods.

Phase Matching

Phase matching is achieved in birefringent materials by balancing the dispersion of the material with the difference between the indices of refraction of the fast and slow waves. With adequate birefringence it may be possible to obtain phase matching by selecting the direction of propagation in the crystal. Equations describing the dispersion and birefringence of nonlinear crystals, necessary for calculating phase matching, along with the nonlinear optical coefficients and expressions for the effective nonlinear optical coefficients, are tabulated in handbooks. Values for a few examples are given here.

The negative uniaxial crystal potassium dihydrogen phosphate (KH_2PO_4 or KDP) is used as an illustrative example. The harmonic wave is chosen to have extraordinary polarization with the smaller index of refraction in this crystal with negative birefringence. With type-I phase matching, the fundamental consists of only an ordinary polarized wave. To have phase matching, $\Delta k = 0$, it is necessary to choose a direction of propagation that makes an angle θ with the optic axis that satisfies:

$$n_{\mathrm{e},2\omega}(\theta) = n_{\mathrm{o},\omega} \qquad [29]$$



Figure 4 High levels of overall second-harmonic conversion require higher levels of conversion at peak pulse intensity. Phase-matching bandwidths narrow at the higher levels of peak conversion. The broken curve is the $(\Gamma l)^2 \mathrm{sinc}^2(\Delta kl/2)$ small conversion approximation.

The extraordinary index for propagation at an angle of θ to the optical axis in a uniaxial crystal $n_e(\theta)$ is given by

$$\frac{1}{n_e^2(\theta)} = \frac{\cos^2\theta}{n_o^2} + \frac{\sin^2\theta}{n_e^2} \qquad [30]$$

where n_o is the ordinary index and n_e is the extraordinary index for propagation at 90° to the optic axis. The phase-matching angle is obtained by using the identity $\cos^2\theta = 1 - \sin^2\theta$ and solving for θ:

$$\theta_{PM} = \sin^{-1}\left\{\frac{n_{e,2\omega}^2(n_{o,2\omega}^2 - n_{o,\omega}^2)}{n_{o,\omega}^2(n_{o,2\omega}^2 - n_{e,\omega}^2)}\right\}^{1/2} \qquad [31]$$

where the subscripts refer to ordinary and extraordinary indices at the fundamental and second-harmonic frequencies.

The effective nonlinear coefficient is determined by crystal symmetry, the type of phase matching, the birefringence of the crystal, and the direction of propagation. For crystals of point group $\bar{4}2m$ with negative birefringence, such as KDP, the effective nonlinear coefficient for type-I phase matching is given by

$$d_{\mathrm{eff}} = -d_{36}\sin\theta\sin 2\phi \qquad [32]$$

The azimuthal angle ϕ is measured from the crystal x-axis. The x-axis and y-axis are specified by X-ray diffraction and piezoelectric coefficients and can be determined from the growth morphology. The azimuthal orientation of a finished crystal, however, is not obvious, and requires X-ray orientation, piezoelectric characterization, or nonlinear optical measurements, if the record of crystal orientation is lost. The nonlinear coefficient d_{36} is an abbreviation for the d_{312} and d_{321} tensor components, which are equal. For harmonic generation with a 1064 nm fundamental in KDP, $d_{36} = 0.39 \times 10^{-12}$ m/V. The unit of 10^{-12} m/V is usually expressed as picometers per volt (pm/V). The effective nonlinear coefficient for type-II phase matching for this class of crystals is

$$d_{\mathrm{eff}} = d_{36}\sin 2\theta\cos 2\phi \qquad [33]$$

Type-I and type-II crystals cut from the same material are not interchangeable. The type-II phase-matching angle for KDP can be found by iterative solution of the equation:

$$n_{e,2\omega}(\theta) = \{n_{o,\omega} + n_{e,\omega}(\theta)\}/2 \qquad [34]$$

The birefringent walkoff angle, that is the angle the Poynting vector of an extraordinary wave makes with the wavevector, is another consideration for birefringent phase matching. There will be no further harmonic generation when the extraordinary and ordinary fundamental beams of type-II phase matching no longer overlap. For type-I phase matching, birefringent walkoff can limit the interaction length, but there can be several interaction lengths in a crystal. The birefringent walkoff of an extraordinary wave propagating at an angle θ to the optic axis in a uniaxial crystal is given by

$$\rho = \tan^{-1}\left\{\frac{n_e^2(\theta)}{2}\left[\frac{1}{n_e^2} - \frac{1}{n_o^2}\right]\sin(2\theta)\right\} \qquad [35]$$

Refractive indices for 1064 nm to 532 nm second-harmonic generation in KDP are $n_{e,2\omega} = 1.4709$, $n_{o,2\omega} = 1.5129$, $n_{e,\omega} = 1.4603$, and $n_{o,\omega} = 1.4944$. The dispersion of KDP and indices at the phase-matching angles are shown in Figure 5. For type-I phase matching $d_{\text{eff}} = 0.26$ pm/V, $\theta_{\text{PM}} = 41.2°$, and $\rho_{2\omega} = 28$ milliradians (mr), and for type-II phase matching $d_{\text{eff}} = 0.34$ pm/V, $\theta_{\text{PM}} = 59.1°$, $\rho_\omega = 20$ mr, and $\rho_{2\omega} = 25$ mr. Type-II phase matching in KDP for this application offers an advantage of larger effective nonlinear coefficient. Also the angular acceptance is larger for type-II phase matching.

The angular acceptance is calculated from dispersion equations by first evaluating the derivative $\partial\Delta k/\partial\theta$ and then finding the value of $\Delta\theta$ corresponding to the full width at half maximum (FWHM) of the $\text{sinc}^2(\Delta k \cdot l/2)$ function:

$$\frac{\partial\Delta k}{\partial\theta}\Delta\theta_{\text{FWHM}} \cong 4 \times 1.39 \text{ radians}/l \qquad [36]$$

When θ is 0° or 90° for uniaxial crystals, or for propagation along one of the refractive index principal axes in a biaxial crystals, the first derivative $\partial\Delta k/\partial\theta$ becomes zero, and the angular acceptance must be calculated from the second derivative $\partial^2\Delta k/\partial\theta^2$. This case is called noncritical phase matching (NCPM), and the case for θ between 0° and 90° is called critical phase matching.



Figure 5 Dispersion of the birefringent nonlinear material KH_2PO_4 with refractive indices indicated for type-I and type-II 1064 nm to 532 nm second-harmonic generation. (Adapted from Byer RL (1977) Parametric oscillators and nonlinear materials. In: Harper PG and Wherrett BS (eds) *Nonlinear Optics*, pp. 47–159. San Francisco, CA: Academic Press.)

Second-harmonic generation of 1064 nm fundamental radiation in the crystal lithium triborate (LBO or LiB_3O_5) is an example of NCPM. At 149°C, this crystal will phase match for type-I SHG for propagation along the x-axis in the xyz frame determined by the indices of refraction of this biaxial crystal $n_x < n_y < n_z$. The following are calculated from dispersion equations for this case: $\partial\Delta k/\partial\theta = 0$; $\partial^2\Delta k/\partial\theta^2 = 2.04 \times 10^4$ (rad/cm)/rad^2; $\partial\Delta k/\partial\phi = 0$; and $\partial^2\Delta k/\partial\phi^2 = 6.45 \times 10^3$ (rad/cm)/rad^2. The FWHM angular acceptances for a 1.5 cm-long LBO crystal are $\Delta\theta_{\text{FWHM}} = 1.09°$ and $\Delta\phi_{\text{FWHM}} = 1.94°$. Angle-tuned CPM at 23°C in LBO occurs at $\theta = 90°$ and $\phi = 11°.5$. For this case $\partial\Delta k/\partial\phi = 1.32 \times 10^4$ (rad/cm)/rad, and the azimuthal angular acceptance decreases to $\Delta\phi_{\text{FWHM}} = 0.16°$. Also there is a birefringent walkoff angle of $\rho_{2\omega} = 19$ mr, which results in a displacement of 0.29 mm of the extraordinary-like harmonic beam for a 1.5 cm-long crystal. Both the larger angular acceptance and the absence of birefringent walkoff are advantages for harmonic generation. The effective nonlinear coefficient of LBO is reported as 0.85 pm/V and 1.04 pm/V by different sources.

Quasi phase matching offers the possibility, in principle, of noncritical phase matching at any wavelength in the transmission range of a material. However, it may be difficult producing the periodic structure that is required for phase matching in a particular application. The ferroelectric crystals lithium niobate ($LiNbO_3$), lithium tantalate ($LiTaO_3$), and potassium titanyl phosphate ($KTiOPO_4$ or KTP) can be processed by electric-field poling to produce domains of alternating polarity. Lithography techniques are used to apply a patterned electrode structure on the surface of a wafer or thin slab. Domains are reversed by the application of a carefully monitored and controlled electric field. Thicknesses of several mm have been achieved in periodically poled KTP (PPKTP). The higher coercive field of 21 kV/mm has limited the thicknesses that can be achieved in periodically poled lithium niobate (PPLN), particularly at shorter wavelengths for which poling periods become small. Progress is now being made with zincblende materials such as gallium arsenide. These materials have large linearity and good transmission in the infrared, but they are not birefringent. Epitaxial growth on patterned substrates is now being used to produce periodically structured GaAs on a research basis, and bonded stacks of wafers of alternating orientation also have been used. Harmonic conversion with quasi phase matching is compared with conventional phase matching and nonphase-matched harmonic generation in Figure 6.



Figure 6 The growth of harmonic intensity is illustrated schematically for a quasi-phase-matched process in which the polarity of the nonlinearity is reversed after each coherence length. Conversion for $\Delta k = 0$, $\Delta k \neq 0$, and a uniform effective nonlinear coefficient are shown for comparison. (Adapted from Fejer MM (1992) Quasi-phase-matched second harmonic generation: tuning and tolerances. *IEEE Journal of Quantum Electronics* 28: 2631–2654.)



Figure 7 Random variations in domain length will lower harmonic conversion efficiency and have effect on back conversion. RMS variations in domain length are indicated in the legend for this specific example.

Quasi phase matching also provides access to tensor components that are not accessible with birefringent phase matching. This is the case for lithium niobate; the largest tensor component is $d_{333} = d_{33}$, which has a value of 25 pm/V. The effective nonlinear coefficient is the relevant Fourier component of the modulated nonlinearity:

$$d_{\text{eff}} = (2/\pi) d_{33} \approx 16 \text{ pm/V} \quad [37]$$

This is a larger effective nonlinearity than is available with common birefringently phase matched materials in the visible and near-infrared. A more accurate treatment of second-harmonic generation involves application of the Jacobian-elliptic-function solution to each domain. After nearly complete conversion is reached, the phase perturbations on the individual domains have effect, and back conversion takes over (Figure 7). Conversion is lower and back conversion can set in sooner with random differences in the domain length. There is some experimental evidence that this type of back conversion has been observed in guided-wave harmonic conversion devices. Guided-wave nonlinear optical interaction can have long interaction lengths not limited by diffraction. Quasi phase matching is particularly useful in waveguide second-harmonic generation because the direction of propagation is fixed.

Gaussian Beams and Pulses

A radially symmetric Gaussian light beam has transverse intensity of

$$I(r) = I_0 \exp(-2r^2/w^2) \quad [38]$$

where r is the radial coordinate and w is called the spot size. Harmonic generation in the low-conversion limit by a Gaussian beam, with a focus of spot size w_0 at the center of a crystal with optimized phase matching, is described by

$$p_{2\omega}(l)/p_\omega(0) = 2\omega^2 d_{\text{eff}}^2 p_\omega(0) lkh(B,\xi)/(\pi n^3 \varepsilon_0 c^3) \quad [39]$$

The harmonic power after propagating distance l in the crystal is $p_{2\omega}(l)$, and $p_\omega(0)$ is the incident fundamental power. The function $h(B,\xi)$ is the Boyd and Kleinman focusing factor. It is a function of the walkoff parameter:

$$B = \rho\sqrt{lk}/2 \quad [40]$$

and the focusing parameter:

$$\xi = l/(kw_0^2) \quad [41]$$

The spot size w_0 of the fundamental beam at its waist is used to described the fundamental intensity distribution at the focus at the center of the crystal:

$$I_\omega(r) = (2p_\omega(0)/(\pi w_0^2))\exp(-2r^2/w_0^2) \quad [42]$$

Values of the focusing factor for arbitrary focusing and walkoff are usually displayed in the form of a graph (Figure 8). In the case of weak focusing $\xi \ll 1$ and relatively small walkoff $w_0 > \rho l$, the focusing factor is given by

$$h(B,\xi) \approx \xi(1 - t^2/12 + t^4/120 - t^6/1344 + \ldots) \quad [43]$$

where $t = 2B(2\xi)^{1/2}$.

An example of continuous-wave second harmonic generation is used. This calculation models a conversion experiment published in the literature. External-resonant-cavity second-harmonic generation of 6.5 W of 532 nm radiation was reported. The 1064 nm fundamental radiation with 378 W of circulating power in a resonant cavity external to the laser was focused to a 32 μm spot size in the center of a 6 mm-long LBO crystal (Figure 9). This corresponds to a focusing factor of $\xi = 0.62$ in the index $n = 1.6053$ material. The value of the focusing parameter is $h(0, 0.62) = 0.58$. The nonlinear optical coefficient for this process is reported as 0.85 pm/V and 1.04 pm/V by different sources. When these values are inserted into the earlier equation for $p_{2\omega}(l)/p_\omega(0)$, the higher coefficient yields a conversion efficiency of 0.0273 and 10.3 W of 532 nm output, whereas the lower coefficient yields a conversion efficiency of 0.0182 and 6.9 W of 532 nm radiation. Differences in published values of nonlinear optical coefficients are common. The reported precision of the experiment and the measured values tend to support the lower value. Practical applications are useful to check the accuracy of parameter values. With many variables and the added complication of operation at high intensity there is uncertainty that demands caution in accepting the derived parameter values. It is interesting to note that the power and beam size of the example result in a maximum intensity of 17 MW/cm^2 at the surface of this crystal. Many vendors will warranty antireflection coatings for only 1 MW/cm^2 maximum continuous-wave intensity.



Figure 8 The Boyd and Kleinman focusing factor *h*(*B*,*ξ*) for type-I second-harmonic generation is shown as a function of the focusing parameter *ξ* for different values of the walkoff parameter *B*. The curves shown were generated with a split-step Fourier transform calculation. (Adapted from Boyd GD (1968) Parametric interactions of focused Gaussian light beams. *Journal of Applied Physics* 39: 3597–3639.)

For a pulsed fundamental with temporal shape $p_\omega(t) = p_\omega(0)\exp(-t^2/\tau^2)$, integration over time gives a calculated energy conversion efficiency of:

$$\begin{aligned}\eta_{\text{calc}} &= U_{2\omega}(l)/U_\omega(0)\\ &= \sqrt{2}\omega^2 d_{\text{eff}}^2 U_\omega(0) lkh(B,\xi)/(\tau\sqrt{\pi^3}n^3\varepsilon_0 c^3) \qquad [44]\end{aligned}$$

where $U_{2\omega}(l)$ is the harmonic energy generated after propagation distance l in the crystal and $U_\omega(0)$ is the incident fundamental energy. This is still a low conversion approximation. An estimate of conversion efficient at arbitrary levels of depletion η_{est} is obtained with the empirical expression:

$$\eta_{\text{est}} = \eta_{\text{calc}}/(1 + \eta_{\text{calc}}) \qquad [45]$$

Returning to the example 1.064 nm to 532 nm, type-II SHG in KDP and using $l = 3$ cm, $U_\omega(0) = 0.3$ J, and $\tau = 3.6$ ns for a 6 ns FWHM pulse duration, the above two relationships predict a conversion efficiency of 50%. These parameters give a peak intensity of 330 MW/cm^2, a value typical for efficient harmonic conversion, while avoiding laser-induced damage in a long-term, repetitive-pulse application using KDP. Single-shot laser-induced-damage thresholds for KDP are about 10 times higher.


Resonated fundamental light
Mirror mounted on piezoelectric translator
Mirror
Incident fundamental beam
Concave mirror
Concave mirror
LBO crystal in oven
Harmonic output beam

Figure 9 A bow-tie cavity for externally resonant second-harmonic generation is illustrated. The reflected fundamental beam is used to develop an error signal to drive the piezoelectric translator and hold the cavity in resonance.



Figure 10 Short crystals less than 1 mm in length are typically used for second-harmonic generation with fundamental pulses that are only ten's of femtoseconds in duration. It is necessary to separate fundamental and second-harmonic pulses and recombine them with appropriate delay to compensate for group-velocity mismatch before sum-frequency generation to the third harmonic.

As a final example, consider second-harmonic generation of a 100 fs ($1\ \text{fs} = 10^{-15}$ s) duration pulse from a mode-locked $Ti{:}Al_2O_3$ laser operating at 800 nm. Typical laser output might consist of 10 nJ (10×10^{-9} Joule) pulses at 80 MHz repetition rate. Group velocity walkoff is a concern for this short pulse duration (Figure 10). Barium borate (BaB_2O_4 or BBO) is a common crystal for this application. The group velocity walkoff rate between the ordinary-polarization 800 nm fundamental pulse and the extraordinary-polarization 400 nm harmonic pulse is 190 fs/cm. A crystal length no longer than 0.5 mm is needed to avoid lengthening the harmonic pulse in time. Fortunately, the laser-induced-damage-threshold intensity increases approximately as the inverse of the square root of the pulse length between roughly 10 ns and 1 ps, and it is possible to focus the beam to achieve higher intensity without crystal damage and compensate for the short crystal length. However, the 68-milliradian birefringent walkoff of the harmonic will limit the size of the focus. A 20 μm spot size will allow an interaction length that roughly matches the crystal length and provides a peak fundamental intensity around 16 GW/cm^2 and a conversion efficiency of nearly 30%. Now suppose the 100 fs pulse is amplified to 100 mJ in a large chirped-pulse regenerative amplifier. A larger diameter crystal is required, and KDP is an appropriate choice. The group velocity walkoff rate in KDP is 78 fs/mm, and a crystal of 1.5 mm thickness could be used. With the beam spot size increased to 30 mm, the peak intensity will be 71 GW/cm^2, and the conversion efficiency will be about 40%. Material availability, such as the large sizes possible with KDP, often determines a choice.

Conclusion

Basic techniques for describing and modeling second-harmonic generation have been discussed. Birefringent phase matching and quasi phase matching were reviewed. Three examples were used to illustrate considerations for implementing harmonic-generation systems. There are many more parameters to be considered for other applications and for more detailed analysis. The examples presented illustrate the demands nonlinear optical frequency conversion places on materials. A few materials have been established as primary choices in common applications. But for many applications, available materials or laser system performance are limiting and it is necessary to use the materials and systems that are available. The importance of using the analysis methods is stressed. It is possible to sacrifice performance by improperly specifying a crystal. Choosing the best crystal for a harmonic-generation application with an appropriate optical design will optimize harmonic conversion.

See also

Nonlinear Optics, Applications: Phase Matching. **Nonlinear Sources:** Harmonic Generation in Gases. **Spectroscopy:** Second Harmonic Spectroscopy.

Further Reading

Akhmanov SA (1975) Optical harmonic generation and optical frequency multipliers. In: Rabin H and Tang CL (eds) *Quantum Electronics. A Treatise, vol. 1, part B*, pp. 475–583. New York: Academic Press.

Armstrong JA (1962) Interaction between lightwaves in a nonlinear dielectric. *Physics Review* 127: 1918–1962.

Boyd GD (1968) Parametric interactions of focused Gaussian light beams. *Journal of Applied Physics* 39: 3597–3639.

Boyd RW (2003) *Nonlinear Optics*, 2nd edn. New York: Academic Press.

Byer RL (1977) Parametric oscillators and nonlinear materials. In: Harper PG and Wherrett BS (eds) *Nonlinear Optics*, pp. 47–159. San Francisco, CA: Academic Press.

Dmitriev VG (1997) *Handbook of Nonlinear Optical Crystals*, 2nd edn. Berlin: Springer-Verlag.

Fejer MM (1992) Quasi-phase-matched second harmonic generation: tuning and tolerances. *IEEE Journal of Quantum Electronics* 28: 2631–2654.

Shen YR (1984) *The Principles of Nonlinear Optics*. New York: John Wiley & Sons.

Sutherland RL (2003) *Handbook of Nonlinear Optics*, 2nd edn. New York: Marcel Dekker.

Yang SL (1991) 6.5 W, 532 nm radiation by cw resonant external-cavity second-harmonic generation of an 18 W Nd:YAG laser in LiB_3O_5. *Optical Letters* 16: 1493–1495.

Yariv A (1989) *Quantum Electronics*, 3rd edn. New York: John Wiley & Sons.

$\chi^{(3)}$–Third-Harmonic Generation

B Y Soon, Thales Electro-Optics PTE Ltd., Singapore

J W Haus, University of Dayton, Dayton, OH, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The invention of the ruby laser, in 1960, provided a revolutionary new light source, which emits an intense, highly collimated polarized beam of light. The new source opened the way for developments that have enabled new technologies, thus profoundly changing our way of life. One of these new frontiers opened by the laser was the field of nonlinear optics. In 1961, Franken *et al.* were the first to report the observation of second-harmonic generation from a quartz crystal, using ruby laser light. Third-harmonic generation (THG) was soon discovered by Terhune and co-workers in 1962.

THG has found applications as a spectroscopic tool to probe optical properties of materials, but recently it has been developed as a microscopy tool and a pulse measurement technique. More efficient THG is possible by engineering the materials; for instance, one way to improve conversion efficiency is to use periodic structured dielectric materials, called photonic bandgap structures.

Polarization and the Third-Order Susceptibility

THG is a nonlinear optical phenomenon, where light of angular frequency ω is converted into light at an angular frequency 3ω that is three times higher. Light is made of particles called photons and the nonlinear medium enables the process whereby three photons of frequency ω are annihilated to create one photon of frequency 3ω. The nonlinear interactions are strongly dependent on the polarization or the dipole moment per unit volume, which is written as a series

$$P(t) = \chi^{(1)} \times E(t) + \chi^{(2)} : E^2(t) + \chi^{(3)} \vdots E^3(t) + \cdots \qquad [1]$$

where χ is the susceptibility of the optical material, the superscript of χ in parentheses denotes the order of nonlinearity, t is the time variable, and E is the electric field. Both the electric field and the polarization are vectors; therefore the susceptibilities are tensors. The first-order or linear susceptibility $\chi^{(1)}_{ij}$ is a second-order tensor. This term constitutes the linear polarization of the medium denoted a P^{L}. It has nine elements, but only up to three independent elements depending on the symmetry of the lattice. The other terms represent an expansion for the nonlinear polarization of the medium, P^{NL}. Note that the superscripts 'L' and 'NL' denote linear and nonlinear polarization contributions, respectively. The third-order susceptibility $\chi^{(3)}_{ijkl}$ is a four-rank tensor, which usually has 81 elements $(3 \times 3 \times 3 \times 3 = 81)$. In asymmetric crystalline solids, all 81 elements can be of nonzero value and independent. With a higher degree of symmetry in other optical materials, the 81 elements are no longer all independent, and thus the number of independent elements can be reduced to a lower number. For example, isotropic material such as glass, liquid, or vapor has only three independent elements. For illustration, we consider a general case where the applied frequencies ω are arbitrary, and the third-susceptibility is given as

$$\chi_{ijkl} \equiv \chi^{(3)}_{ijkl}(\omega_4 = \omega_1 + \omega_2 + \omega_3) \qquad [2]$$

Note that the superscript has been removed. In the isotropic material, the coordinate axes must be equivalent. Thus, the susceptibility has symmetry given by

$$\chi_{1111} = \chi_{2222} = \chi_{3333} \qquad [3a]$$

$$\chi_{1122} = \chi_{1133} = \chi_{2211} = \chi_{2233} = \chi_{3311} = \chi_{3322} \qquad [3b]$$

$$\chi_{1212} = \chi_{1313} = \chi_{2323} = \chi_{2121} = \chi_{3131} = \chi_{3232} \qquad [3c]$$

$$\chi_{1221} = \chi_{1331} = \chi_{2112} = \chi_{2332} = \chi_{3113} = \chi_{3223} \qquad [3d]$$

For the isotropic material, there are only 21 nonzero elements, as given in eqns [3a]–[3d], because these elements have a Cartesian index (1, 2, or 3) that appears an even number of times. The reason for nonexistence of the elements with an index appearing an odd number of times is because, for example, χ_{1222} would give a response in the $\hat{x}_1$ direction due to a field applied in the $\hat{x}_2$ direction. This response must vanish in an isotropic material, because there is no reason why the response should be in the $+\hat{x}_1$ direction rather than in the $-\hat{x}_1$ direction. In summary, the elements in the third-order susceptibility of the isotropic material have the relationship given by

$$\chi_{ijkl} = \chi_{1122}\delta_{ij}\delta_{kl} + \chi_{1212}\delta_{ik}\delta_{jl} + \chi_{1221}\delta_{il}\delta_{jk} \qquad [4]$$

where δ is the Kronecker delta function; it has a unit value, $\delta_{ij} = 1$, if and only if $i = j$, otherwise, it is zero, $\delta_{ij} = 0$. Thus, we see from eqn [4] that there are only three independent elements in the isotropic material. Crystalline materials have more independent components and they have been determined for the 32 crystals classes. The relationships between the elements for these crystalline classes are tabulated in books by Boyd and by Butcher and Cotter.

A block diagram of a material illustrates THG and its corresponding energy-level diagram is depicted in Figure 1. Figure 1a shows that fields of frequency ω excite the χ^3 optical material to generate the third-harmonic field with the residual of the fundamental harmonic field. Figure 1b shows that three photons of frequency ω are destroyed to generate a photon of frequency 3ω in the third-harmonic generation.

For third-harmonic generation, the frequency dependence of the susceptibility is expressed as $\chi_{ijkl}(3\omega = \omega + \omega + \omega)$. With the intrinsic permutation symmetry of the nonlinear susceptibility, the elements of the susceptibility tensor has a relationship such that $\chi_{1122} = \chi_{1212} = \chi_{1221}$. So we can further reduce eqn [4] for the third-harmonic generation as

$$\chi_{ijkl}(3\omega = \omega + \omega + \omega) = \chi_{1122}(3\omega = \omega + \omega + \omega) \times (\delta_{ij}\delta_{kl} + \delta_{ik}\delta_{jl} + \delta_{il}\delta_{jk}) \qquad [5]$$

Therefore, we see that the third-harmonic susceptibility tensor has only one independent element.

Wave Equation for χ^3 Third-Harmonic Generation

Theoretically, we have to use the wave equation to observe how an intense laser field interacts with the nonlinear material, so that the polarization of the medium could develop new frequency components that are not present in the incident field. Thus, these new frequency components of the polarization become the sources of the new frequency components of the electromagnetic field.

To formally describe THG, we begin with Maxwell's equations (in Gaussian units), and we have

$$\nabla \times D = 4\pi\rho \qquad [6a]$$

$$\nabla \times B = 0 \qquad [6b]$$

$$\nabla \times E = \frac{-1}{c}\frac{\partial B}{\partial t} \qquad [6c]$$

$$\nabla \times H = \frac{-1}{c}\frac{\partial D}{\partial t} + \frac{4\pi}{c}J \qquad [6d]$$

where H is the magnetic field, B is the magnetic flux density, D is the electric flux density, ρ is the charge density, and J is the current density. The desired solution is in the region of space in the nonlinear material that has no free charge ($\rho = 0$), and therefore, there is no free current ($J = 0$). We assume



Figure 1 The third-harmonic (a) block diagram; and (b) energy level description.

that the nonlinear material is nonmagnetic, so that $B = \mu H = H$, where $\mu = 1$ in a nonmagnetic environment. In nonlinear material, the electric flux is defined as

$$D = E + 4\pi P \qquad [7]$$

so that the polarization depends nonlinearly on the strength of E. Using eqns [6c] and [6d], we have

$$\nabla \times \nabla \times E + \frac{1}{c^2}\frac{\partial^2 D}{\partial t^2} = 0 \qquad [8]$$

Substituting eqn [7] into [8], we have

$$\nabla \times \nabla \times E + \frac{1}{c^2}\frac{\partial^2 E}{\partial t^2} = \frac{-4\pi}{c^2}\frac{\partial^2 P}{\partial t^2} \qquad [9]$$

Using an identity from the vector calculus, we have

$$\nabla \times \nabla \times E = \nabla(\nabla \times E) - \nabla^2 E \qquad [10]$$

In linear optics, we see from eqn [6a] that when there is no free charge in source-free isotropic material, $\nabla \times D = \nabla \times E = 0$. Thus, the first term on the right-hand side of eqn [10] has no effect. Whereas in nonlinear optics, $\nabla \times E \neq 0$ in isotropic material, but the contribution from the first term on the right-hand side of eqn [10] is negligible, therefore, we can ignore it. Thus, eqn [9] can be simplified as

$$\nabla^2 E - \frac{1}{c^2}\frac{\partial^2 E}{\partial t^2} = \frac{4\pi}{c^2}\frac{\partial^2 P}{\partial t^2} \qquad [11]$$

For distinction of the linear and nonlinear contributions, we modified eqn [7] to get

$$D = E + 4\pi P^{\mathrm{L}} + 4\pi P^{\mathrm{NL}}$$

where $P = P^{\mathrm{L}} + P^{\mathrm{NL}}$. Let $D^{\mathrm{L}} = E + 4\pi P^{\mathrm{L}}$, and we rewrite eqn [11] as

$$\nabla^2 E - \frac{1}{c^2}\frac{\partial^2 D^{\mathrm{L}}}{\partial t^2} = \frac{4\pi}{c^2}\frac{\partial^2 P^{\mathrm{NL}}}{\partial t^2} \qquad [12]$$

Equation [12] is the most general form of the wave equation seen in nonlinear optics, and could be used as our starting point for our study of third-harmonic generation.

Methods of Third-Harmonic Generation

Since nonlinear optics is a popular research topic, there are a handful of existing methods that can be used for third-harmonic generation, and possibly new methods may be developed in the future. Here, we will discuss three methods using χ^3 material: (i) photonic crystal; (ii) defect mode using photonic crystal; and (iii) homogeneous nonlinear crystal.

Photonic Crystal

After the invention of electronic bandgap structure, the optical scientists and engineers saw the possibility to extend the operating waveband into the visible, and thus we have the photonic bandgap structure. The geometry and material choices of the photonic bandgap structure create a unique bandgap in frequency spectrum that has potential applications in laser optics, telecommunication, medical imaging, optical limiting, etc. A photonic bandgap structure is also commonly known as the photonic crystal. For a one-dimensional photonic crystal, two materials of certain thicknesses each, repeat themselves a number of times. For example, the first and second materials are of thickness '*a*' and '*b*', respectively, so that their combined thickness is '*d*', and have a periodicity of 10. The schematic of such a one-dimensional photonic crystal, with its corresponding dielectric function as a function of axial distance z, is depicted in Figure 2.

By using χ^3 materials for photonic crystal, and using method of multiple scales (MMS), we have the nonlinear polarization given as

$$P^{\mathrm{NL}} = \lambda\chi^{(3)}E^3 \qquad [13]$$

where λ is the perturbation parameter. With reference to Figure 2, assume that '*a*' is equal to '*b*' so that $d = 2a$, then the Fourier expansion of the dielectric



Figure 2 The schematic of the one-dimensional photonic crystal.

function is given as

$$\varepsilon(z,\omega) = \bar{\varepsilon}(\omega) + \lambda\Delta\varepsilon(\omega)\cos(2\pi z/d) - \frac{1}{3}\lambda\Delta\varepsilon(\omega)\cos(6\pi z/d) + \cdots \qquad [14]$$

where $\bar{\varepsilon}(\omega)$ is the zeroth-order coefficient, and $\Delta\varepsilon(\omega)$ is first-order coefficient of the Fourier series expansion. Without going through the mathematics of MMS, we use eqns [12] and [13] to obtain the solution of the wave equation and two sets of coupled mode equations. The solution to the wave equation in eqn [12] is given by

$$E_0=\left(\frac{1}{\sqrt{k_1}}A_{f1}(z_1,t_1)e^{ik_1z_0}+\frac{1}{\sqrt{k_1}}A_{b1}(z_1,t_1)e^{-ik_1z_0}\right)e^{-i\omega t_0} + \left(\frac{1}{\sqrt{k_3}}A_{f3}(z_1,t_1)e^{ik_3z_0}+\frac{1}{\sqrt{k_3}}A_{b3}(z_1,t_1)e^{-ik_3z_0}\right)e^{-3i\omega t_0} + \text{c.c.} \qquad [15]$$

where A is the amplitude of the field, k is the wavenumber such that $k_1^2=\omega^2\varepsilon(\omega)/c^2$, and $k_3^2=(3\omega)^2\varepsilon(3\omega)/c^2$ where c is the speed of light, and 'c.c.' refers to the complex conjugate. Note that the subscript 'f' and 'b' refer to the forward and backward modes, respectively. Also, the subscript '0' refers to the slowest scale, and '3' refers to the fastest scale chosen in the analysis using MMS. Let $a_{f1}=NA_{f1}e^{i\pi\delta_1z_1/d}$, $a_{b1}=NA_{b1}e^{-i\pi\delta_1z_1/d}$, $a_{f3}=NA_{f3}e^{i\pi\delta_3z_1/d}$, and $a_{b3}=NA_{b3}e^{-i\pi\delta_3z_1/d}$, such that

$$N^2=\frac{2d\sqrt{3k_3}(3\omega)^2\chi^{(3)}}{k_3c^2k_1\sqrt{k_1}}$$

The coupled mode equations for the fundamental field are given as

$$\frac{\partial a_{f1}}{\partial z_1}+\frac{d}{\pi v_{g1}}\frac{\partial a_{f1}}{\partial t_1}=\frac{id}{2\pi k_1}\nabla_\perp^2 a_{f1}+i\delta_1a_{f1}-i\kappa_1a_{b1} - \frac{\alpha_1}{2}a_{f1}+ia_{f1}[2|a_{b1}|^2+|a_{f1}|^2] + ia_{f1}^{*2}a_{f3} \qquad [16a]$$

$$\frac{-\partial a_{b1}}{\partial z_1}+\frac{d}{\pi v_{g1}}\frac{\partial a_{b1}}{\partial t_1}=\frac{id}{2\pi k_1}\nabla_\perp^2 a_{b1}+i\delta_1a_{b1}-i\kappa_1a_{f1} - \frac{\alpha_1}{2}a_{b1}+ia_{b1}[2|a_{f1}|^2+|a_{b1}|^2] + ia_{b1}^{*2}a_{b3} \qquad [16b]$$

where, at the fundamental harmonic, v_{g1} is the group velocity of the homogeneous medium, δ_1 is the laser detuning, κ_1 is the coupling coefficient, α_1 is the absorption coefficient, $\nabla_\perp^2$ is the transverse Laplacian and the whole term ($\nabla_\perp^2 a_{f1}$ and $\nabla_\perp^2 a_{b1}$) accounts for diffraction effects, and '$*$' denote the complex conjugate of the corresponding term. Similarly, the coupled mode equations for the third-harmonic field are given as

$$\frac{\partial a_{f3}}{\partial z_1}+\frac{d}{\pi v_{g3}}\frac{\partial a_{f3}}{\partial t_1}=\frac{id}{2\pi k_3}\nabla_\perp^2 a_{f3} + ia_{f3}\left[\delta_3+6\sqrt{\frac{3k_1}{k_3}}(|a_{f1}|^2+|a_{b1}|^2)\right] - i\kappa_3a_{b3}-\frac{\alpha_3}{2}a_{f3}+ia_{f1}^3 \qquad [17a]$$

$$-\frac{\partial a_{b3}}{\partial z_1}+\frac{d}{\pi v_{g3}}\frac{\partial a_{b3}}{\partial t_1}=\frac{id}{2\pi k_3}\nabla_\perp^2 a_{b3} + ia_{b3}\left[\delta_3+6\sqrt{\frac{3k_1}{k_3}}(|a_{b1}|^2+|a_{f1}|^2)\right] - i\kappa_3a_{f3}-\frac{\alpha_3}{2}a_{b3}+ia_{b1}^3 \qquad [17b]$$

where at the third harmonic, v_{g3} is the group velocity of the homogeneous medium, δ_3 is the laser detuning, κ_3 is the coupling coefficient, and α_3 is the absorption coefficient. Note that in the limit when $k_3 \approx 3k_1$, the coupling coefficient between the fundamental and third harmonics are related by

$$\kappa_3=3\left(\frac{d}{\pi}\right)\frac{\Delta\varepsilon\omega_0^2}{2k_3c^2}+3\delta_1=\kappa_1 \qquad [18]$$

Also, note that the laser detuning between the fundamental and third harmonics are expressed as

$$\delta_3=\left(\frac{d}{\pi}\right)\Delta k+3\delta_1 \qquad [19]$$

where $\Delta k=k_3-3k_1 \times$ Equation [19] described the phase matching condition, which determines the efficiency of the third-harmonic generation. When the phase is completely matched ($\Delta k=0$), then we can achieved the most efficient in third-harmonic generation when $\delta_3=3\delta_1$. Equations [16] and [17] are useful equations which are commonly used for numerically simulation of beam propagation.

Defect Mode Using Photonic Crystal

A defect mode can be generated in the photonic crystal if we introduce a defect in the geometry of the photonic crystal. The schematic of the photonic crystal with a defect of length d_d located at the center of the photonic crystal, where the subscript *'d'* denotes defect, is depicted in Figure 3. For the convenience of the analysis, we divide the entire photonic crystal into three regions: (i) Region I; (ii) Region II; and (iii) Region III. Since we arbitrarily



Figure 3 The schematic of the photonic crystal with a defect of length d_d.

put the defect in the center of the photonic crystal, Region I and II will be identical, thus it will be easier for us in our analysis. The strategy of our analysis is to solve the wave equation for Region I of the photonic crystal, and apply the result to the Region II analysis. Similarly, we apply the corresponding result of Region II to Region III. Thus, by breaking up the entire photonic crystal into three regions, we can then easily analyze the propagation of a field through the entire photonic crystal.

Assume that Region I and II are each of length $L/2$. Using the coupled mode equations without considering the effect of absorption, the fundamental fields in the forward and backward modes in Region I is given as

$$a_{f1(\mathrm{REG})}(z_1) = \left(\cos(\Delta_1 z_1) - \frac{i\delta_1}{\Delta_1}\sin(\Delta_1 z_1)\right)a_{f1(\mathrm{REG})}(0) + \frac{i\kappa}{\Delta_1}\sin(\Delta_1 z_1)a_{b1(\mathrm{REG})}(0) \qquad [20a]$$

$$a_{b1(REG)}(z_1) = \left(\cos(\Delta_1 z_1) + \frac{i\delta_1}{\Delta_1}\sin(\Delta_1 z_1)\right)a_{b1(\mathrm{REG})}(0) - \frac{i\kappa}{\Delta_1}\sin(\Delta_1 z_1)a_{f1(\mathrm{REG})}(0) \qquad [20b]$$

where

$$\Delta_1 = \sqrt{\delta_1^2 - \kappa^2}, \qquad \kappa = \frac{d\omega_0^2 \Delta\varepsilon(\omega)}{2\pi k_1 c^2}$$

and the subscript '(REG)' denotes solution in either Region I, II, or III. The boundary conditions for the fundamental harmonic field, at the interface between Region I and II, are given as

$$a_{f1(\mathrm{II})}(d_d) = e^{ikd_d} a_{f1(I)}(L/2) \qquad [21a]$$

$$a_{b1(\mathrm{II})}(d_d) = e^{-ikd_d} a_{b1(I)}(L/2) \qquad [21b]$$

where $k = n\omega/c$. The field that propagates through Region II can be determined using eqns [20] and [21]. Also, the boundary conditions at the front and end faces of the Region III of the photonic crystal are given as

$$a_{f1(\mathrm{III})}(0) = a_{f1(\mathrm{II})}(d_d) \qquad [22a]$$

$$a_{b1(\mathrm{III})}(L/2) = 0 \qquad [22b]$$

Using eqns [20] and [22], we can determine the field that propagates through Region III. Similarly, we can use the same approach to analyze the third-harmonic field.

Homogeneous Nonlinear Crystal

If we examine Figure 2, we see that when $\Delta\varepsilon(\omega) = 0$, the photonic crystal becomes a homogeneous nonlinear crystal. In another word, $\kappa_3 = 0$ when we set the laser detuning to zero, thus there is no more coupling between the layers, and we are left with only the forward mode. Without going through the mathematics of four-wave mixing to describe the THG in a homogeneous nonlinear crystal, we can obtain the fundamental and third-harmonic coupled mode equations from eqns [16] and [17]. This will make it easier to make comparisons between the photonic crystal and the homogeneous nonlinear crystal, rather than comparing the coupled mode equation with the four-wave mixing equations among them. Since no backward wave is generated in the homogeneous nonlinear crystal when there is no coupling between the forward and backward modes, eqn [16] can remove the coupling term and the backward mode equation, and the modification is given as

$$\frac{\partial a_{f1}}{\partial z_1} + \frac{d}{\pi v_{g1}}\frac{\partial a_{f1}}{\partial t_1} = \frac{id}{2\pi k_1}\nabla_\perp^2 a_{f1} + i\delta_1 a_{f1} - \frac{\alpha_1}{2}a_{f1} + ia_{f1}|a_{f1}|^2 + ia_{f1}^{*2}a_{f3} \qquad [23]$$

$$\frac{\partial a_{f3}}{\partial z_1} + \frac{d}{\pi v_{g3}}\frac{\partial a_{f3}}{\partial t_1} = \frac{id}{2\pi k_3}\nabla_\perp^2 a_{f3} + ia_{f3}\left[\delta_3 + 6\sqrt{\frac{3k_1}{k_3}}|a_{f1}|^2\right] - \frac{\alpha_3}{2}a_{f3} + ia_{f1}^3 \qquad [24]$$

for the fundamental and third-harmonic fields, respectively.

Applications

Generation of short wavelength radiation is possible using THG. Therefore, it becomes less expensive to generate green, blue, or ultraviolet light with the infrared and the red light. In order to improve THG conversion efficiency, a beam with a tight focus is used, which results in an electric field of highest intensity, and has the highest possible χ^3 polarization effect. Normally, due to the phenomenon of the Gouy phase shift at a tight focal point of the beam, third-harmonic generation is suppressed. However, in the presence of an interface within the focal volume, the phase is disturbed and a third-harmonic signal is generated. This phenomenon has been used to image cells in *in vivo* microscopy on a femtosecond timescale. The ultrashort pulses have little energy and therefore little heat is deposited in the material. The cells can be continuously imaged without damage.

See also

Materials Characterization Techniques: $\chi^{(3)}$. **Photonic Crystals:** Photonic Crystal Lasers, Cavities and Waveguides.

Further Reading

Barad Y, Eisenberg H, Horovitz M and Silberberg Y (1997) Nonlinear scanning laser microscopy by third harmonic generation. *Applied Physics Letters* **70**: 922–924.

Boyd RW (1992) *Nonlinear Optics*. Boston, MA: Academic Press.

Butcher PN and Cotter D (1990) *The Elements of Nonlinear Optics*. Cambridge: Cambridge University Press.

Franken PA, Hill AE, Peters CW and Weinreich G (1961) Generation of optical harmonics. *Physics Review Letters* 7: 118.

Markowicz PP, Tiryaki H, Pudavar H, Prasad PN, Lepeshkin NN and Boyd RW (2004) Dramatic enhancement of third-harmonic generation in three-dimensional photonic crystals. *Physics Review Letters* 92: 083903.

Petrov GI, Shcheslavskiy V, Yakovlev VV, Ozerov I, Chelnokov E and Marine W (2003) Efficient third-harmonic generation in a thin nanocrystalline film of ZnO. *Applied Physics Letters* **83**: 3993–3995.

Schins J, Schrama T, Brakenhoff G, Muller M and Squier J (2002) Determination of material properties using third harmonic generation microscopy. *Journal of the Optical Society of America B* 19: 1627.

Squier J, Mueller M, Brakenhoff GJ and Wilson KR (1998) Third harmonic generation microscopy. *Optics Express* 3: 315.

Terhune RW, Maker TD and Savage CM (1962) Optical harmonic generation in calcite. *Physics Review Letters* 8: 404.

Viswanathan R (1999). Enhanced Frequency Conversion in Periodic Structures. Ph.D. dissertation, Rensselaer Polytechnic Institute.

Four-Wave Mixing

L Canioni and L Sarger, University of Bordeaux, Talence, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Light waves propagate along straight lines in a vacuum and in materials. However, their amplitude and phase can only be affected by the intrinsic properties of the sample, such as absorption and refraction index. Experimental work from the early 1960s, has deviated from this simple approach, mainly through propagating intense light beams in crystals and glasses. Among many puzzling new effects, frequency conversion and beam coupling have triggered intense studies and opened a whole new field, theoretically and experimentally. These various phenomena have been classified according to the order of their optical nonlinearity. The second order mainly occurs in frequency generation and has already been discussed in previous articles of this encyclopedia. Therefore, this article will be devoted to the higher order, in which self focusing, coupling, and mixing of light beams will be explained. We will illustrate some simple ideas with a convenient model before describing a few applications.

The framework of electromagnetic wave interaction with matter is embedded in the Lorentz force. The oscillating electric field drives the components, ions, and electrons, but due to the large mass differences, only the electron movement is strongly perturbed. In dielectric media, these carriers are connected with static bonds such that the applied electric field modulates the spatial position of equilibrium of the charges. As a result, a dipolar moment is created and oscillates quasi-adiabatically at very high frequencies (between 10^{14} and 10^{17} Hz) for an applied optical wave. These collective oscillations of the induced dipoles compose the so-called matter polarization, proportional to the driving electric field amplitude. Magnetic field interaction is usually much weaker and so can be neglected in nonmagnetic media.

As an electromagnetic wave, lasers are a coherent source of very high intensity, i.e., large electric fields. For example, in standard pulsed lasers focused on a target, the light intensity can easily reach 10 Tw/cm^2, corresponding to an electric field of the order of magnitude of the internal bonding field (10^{10} V/m). At this level of interaction, dipolar moments are no longer strictly proportional to the applied electric field, as depicted in Figure 1. In the weak field regime, the simple perturbation approach displaces the carriers in a power series of the applied electric field. The polarization is thus developed in series, in respect to this electric field.

Formalism

Relation Between Field and Polarization: The Response Function

Although numerous works have been published with a frequency description of the material polarization, we will discuss here the study of nonlinearity in the time domain in order to follow the physical reality. In most processes, both spaces are equal and can be selected at will, as long as the entire requirements are fully understood; the electromagnetic field is classically described.

In the time domain, the polarization can be developed as

$$P(r,t) = P_{\text{Linear}}(r,t) + P_{\text{Nonlinear}}(r,t) \qquad [1]$$

where the linear part of the polarization can be written as

$$P_{\text{Linear}}(r,t) = \varepsilon_0 \int_{R^3} \int_{-\infty}^{\infty} R^{(1)}(r_1,t_1) \times E(r-r_1, t-t_1)\mathrm{d}t_1\,\mathrm{d}r_1 \qquad [2]$$



Figure 1 Polarization for various field amplitude: (a) Weak field case, linear response. (A) Strong field, distortion and nonlinearity.

This general expression is rather complex but shows that the polarization, due to collective movement of carriers in a macroscopic volume (thousands of dipoles) centered at position r, always depends on the applied electric field. This expression is also nonlocal as dipoles–dipoles interactions play an important role.

In general, for the nonlinear (NL) part of the polarization, an approximation of the local interaction is described for simplicity. For a second-order interaction, one can write:

$$P_{\text{NL}}^{(2)}(r,t) = \varepsilon_0 \int_{-\infty}^{+\infty}\int_{-\infty}^{+\infty} R^{(2)}(t_1,t_2) \times E(r,t-t_2)E(r,t-t_2-t_1)\mathrm{d}t_1\,\mathrm{d}t_2 \qquad [3]$$

For the other series expansion – at third order, one obtains

$$P_{\text{NL}}^{(3)}(r,t) = \varepsilon_0 \int_{-\infty}^{+\infty}\int_{-\infty}^{+\infty}\int_{-\infty}^{+\infty} R^{(3)}(t_1,t_2,t_3)E(r,t-t_3) \times E(r,t-t_3-t_2)E(r,t-t_3-t_2-t_1)\mathrm{d}t_1\,\mathrm{d}t_2\,\mathrm{d}t_3 \qquad [4]$$

This third-order polarization already combines three electric fields. This nonlinear polarization also radiates a fourth wave and is therefore the adopted framework for describing four-wave mixing experiments (Figure 2).

As the physical properties of materials depend only on time intervals between the different pulse interactions, eqn (4) can be rearranged as

$$P_{\text{NL}}^{(3)}(r,t) = \varepsilon_0 \int_{-\infty}^{+\infty}\int_{-\infty}^{+\infty}\int_{-\infty}^{+\infty} R^{(3)}(t-\tau_1,t-\tau_2,t-\tau_3) \times E(r,\tau_1)E(r,\tau_2)E(r,\tau_3)\mathrm{d}\tau_1\,\mathrm{d}\tau_2\,\mathrm{d}\tau_3 \qquad [5]$$

If the sample response time is much shorter than pulse duration, the so-called adiabatic limit (as for electronic cloud deformation excited distant from



Figure 2 Three incoming beams E_1, E_2, E_3 create a polarization (nonlinear). The sample responds while radiating a fourth field E_4.

resonance) the polarization is written as

$$P_{\mathrm{NL}}^{(3)}(r,t)=\varepsilon_0\sigma^{(3)}E(r,t)E(r,t)E(r,t) \qquad [6]$$

We will see later how this expression is useful for third-harmonic generation and optical Kerr effects, etc. This expression is accurate for materials excited at a distance from resonances and care must be taken to reserve such a model for corresponding processes. In this case, the frequency approach is quite simple too and both spaces, time or Fourier, can be chosen at will.

For very long response time, such as orientational or structural molecular reorganization, one can use the Born–Oppenheimer approximation and present the nonlinear polarization as

$$P_{\mathrm{NL}}^{(3)}(r,t)=\varepsilon_0 E(r,t)R'(t) \qquad [7]$$

Similar is linear polarization, where the response function takes into account the changes of the molecular structure under the light intensity stress:

$$R'(t)=\int_{-\infty}^{+\infty} d^{(3)}(t-t_1)E(r,t_1)E(r,t_1)\,\mathrm{d}t_1 \qquad [8]$$

The material response will then be mostly driven by the field amplitude rather than the frequency.

Properties of Nonlinear Susceptibilities

The third-order nonlinear susceptibility $\chi^{(3)}$ is the Fourier transform of the response function R and has proved to be a most practical tool in optical nonlinear theory. The symmetry properties of the material lead to simplification on the tensor of rank 4 (fourth rank tensor), involved in four-wave mixing:

$$P_i^{(3)}(\omega_m)=\varepsilon_0\sum_{n_1,\ldots,n_p}\sum_{i_1,\ldots,i_p}\chi_{i,i_1,\ldots,i_p}^{(3)}(\omega_m;\omega_{n_1},\ldots,\omega_{n_p})\times E_{i_1}(\omega_{n_1})\cdots E_{i_p}(\omega_{n_p}) \qquad [9]$$

The nonlinear susceptibility tensor must account for all the spatial and symmetrical order of the sample. This will eventually reduce the number of independent elements from a possible 81.

Wave Equation in Nonlinear Regime

From Maxwell's equations, with a sample without free carriers and current, one can deduce the wave equation in the time domain, as:

$$\Delta E-\frac{1}{c^2}\frac{\partial^2 E}{\partial t^2}-\frac{1}{c^2}\frac{\partial^2 P_{\mathrm{L}}}{\partial t^2}=\frac{1}{c^2}\frac{\partial^2 P_{\mathrm{NL}}}{\partial t^2} \qquad [10]$$

In the frequency domain, this equation reduces to

$$\Delta\tilde{E}(r,\omega)+k(\omega)^2\tilde{E}(r,\omega)=-\mu_0\omega^2\tilde{P}_{\mathrm{NL}}(r,\omega) \qquad [11]$$

In order to solve these (coupled) wave equations in relation to four-wave mixing, we must develop the electric field and the polarization in a slowly varying envelope approximation, using the following conventions:

$$E_i(r,t)=\frac{1}{2}\left(A_i(r,t)\mathrm{e}^{\mathrm{i}(\omega_i t-k(\omega_i)z)}+\bar{A}_i(r,t)\mathrm{e}^{-\mathrm{i}(\omega_i t-k(\omega_i)z)}\right) \qquad [12]$$

$$P_{\mathrm{NL}}(r,t)=\frac{1}{2}\left(p_{\mathrm{nl}}(r,t)\mathrm{e}^{\mathrm{i}(\omega t-k(\omega)z)}+\bar{p}_{\mathrm{nl}}(r,t)\mathrm{e}^{-\mathrm{i}(\omega t-k(\omega)z)}\right) \qquad [13]$$

Within the framework of small perturbations, diffraction can be neglected and the wave equation can be easily reduced to one dimension:

$$\frac{\partial A}{\partial z}=\frac{\mathrm{i}\omega}{2n(\omega)\varepsilon o c}p^{\mathrm{NL}}(z,\omega)\exp(-\mathrm{i}k(\omega)z) \qquad [14]$$

where ω represents the sum or difference permutations over all the frequencies ω_i, thus reflecting the law of energy conservation.

In the case of four-wave mixing, one has to solve four coupled equations for the four interacting waves. Using the polarization eqn [13], one gets:

$$\frac{\partial A_j}{\partial z}=\frac{\mathrm{i}\omega_j}{2n(\omega_j)c}\chi^3 A_1^{(*)}A_2^{(*)}A_3^{(*)}\times\exp\left(\sum_{i=1,2,3}\exp(\pm\mathrm{i}k_i(\omega_i)z)\right)\exp(-\mathrm{i}k(\omega_j)z) \qquad [15]$$

This set of generic equations respectively represent indifferently, either the three incoming beams ($j=1,2,3$), or the radiated field E_4 at ω. The algebra used here associates at each complex conjugate field (*) with the counter propagating wave ($-k$). The amplitude variation of the j field at frequency ω_j is due to the coupling of the three other fields within the sample. The accumulated field is nevertheless always strongly dependent of the phase term and will vanish except when this phase term is zero. This is known as the phase matching condition which has to be fulfilled to ensure an efficient energy conversion. A more general approach of this condition can be found in the corresponding article of this encyclopedia.

Example and Selected Applications

When inserting the full material polarization (linear and nonlinear) into the propagation equation, even restricted at third order, a whole set of processes must be considered. All of them are described by the generic equation already presented, but only a few very important processes – with increasing complexity – will be described here.

Optical Kerr Effect

We consider one single beam incident at frequency ω on a sample. The non-linear polarization is given by

$$P_{\mathrm{NL}}^{(3)}(r,t)=\frac{\varepsilon_0}{8}\chi^{(3)}\big(E(r,t)^3+E^*(r,t)^3+3E(r,t)^2E^*(r,t)+3E(r,t)E^*(r,t)^2\big) \quad [16]$$

The polarization at frequency ω reduces to

$$P_{\mathrm{NL}}^{(3)}(r,t)=\frac{3\varepsilon_0}{4}\chi^{(3)}|E(r,t)|^2E(r,t) \quad [17]$$

This term has the same phase as the incident beam and, therefore, the phase matching is automatic. Using eqns [12] and [13], one can rewrite the wave equation for the optical Kerr effect in the thin sample approximation:

$$\frac{\partial A}{\partial z}=\frac{3\mathrm{i}\omega}{8nc}\chi^{(3)}|A|^2A \quad [18]$$

The solution of this equation is

$$A(z)=A(0)\exp\left(\frac{3\mathrm{i}}{8nc}\chi^{(3)}|A(0)|^2z\right) \quad [19]$$

Along the beam, the amplitude of the input pulse stays constant for this process but its phase is affected by a nonlinear shift proportional to power density I.

In literature, one can find the concept of n_2, the sample nonlinear index, in the following formula:

$$\psi_{\mathrm{NL}}(z)=\frac{\omega}{c}n_2Iz \quad [20]$$

In this way of describing the total phase along the beam, the index of refraction in the nonlinear regime can be expressed more conveniently as

$$n=n_0+n_2I \quad [21]$$

One of the most significant demonstrations of this effect is the self-focusing phenomenon. The usual Gaussian transverse structure of a laser beam presents high intensity at the center of the beam, therefore creating an index variation in the isotropic sample due to this optical Kerr effect. An induced lens can then be applied to this refractive index gradient, following the field distribution. As a result, the beam focuses itself along the propagation and can result in a complete breakdown.

Third Harmonic Generation

In the third harmonic generation, i.e., the third-order nonlinear process where the frequency of the generated wave is three times the frequency of the input wave at ω, only two waves are in the sample (at ω and 3ω). For the nonlinear wave, the master equation is then:

$$\frac{\partial A_{3\omega}}{\partial z}=\frac{3\mathrm{i}\omega}{8n(3\omega)c}\chi^{(3)}A_\omega^3\exp((3\mathrm{i}k(\omega)-\mathrm{i}k(3\omega))z) \quad [22]$$

Here, propagation effects have to be carefully considered as theses waves do travel at different velocities and will eventually be out of phase. Obviously this discrepancy of phase velocities precludes the co-propagation and strongly affects the global efficiency. The only way to ensure a coherent generation of the harmonic wave throughout the material is to fulfill the relation:

$$k(3\omega)=3k(\omega) \quad [23]$$

This is the so-called phase matching condition. Although difficult because the usual dispersion of materials is very large for such a frequency difference, this can be satisfied using either geometrical arrangement or, if possible, using the birefringent properties of the material. The efficiency of this method is poor and a better approach is implemented when two $\chi^{(2)}$ processes are cascaded (doubling and sum frequency mixing).

Degenerate Four-Wave Mixing and Phase Conjugation

One of the most popular and intriguing interactions is depicted in Figure 3. Where the sample is excited by three fields at the same frequency ω in this particular geometry: two-waves, named pump beams E_1 and E_2, are exactly counter-propagating with opposite wave vectors of $+k_1$ and $k_2=-k_1$, while the third wave (E_3) arrives at the sample with a given wave vector of k_3.

Of possible couplings, one contribution E_4 corresponds to a re-emitted beam along $k_4=-k_3$, i.e., opposite to the E_3 wave.

The third-order nonlinear polarization is given here by

$$P_{\mathrm{NL}}^{(3)}(r,t) = \frac{\varepsilon_0}{8}\chi^{(3)}(E_1(r,t) + E_1^*(r,t) + E_2(r,t) + E_2^*(r,t) + E_3(r,t) + E_3^*(r,t))^3 \qquad [24]$$

This E_4 wave (along $-k_3$) originates in this product from source terms including:

$$E_1(r,t)E_2(r,t)E_3^*(r,t) \qquad [25]$$

and thus present an evolution driven by:

$$\frac{\partial A_4}{\partial z} = \frac{3\mathrm{i}\omega}{4n(\omega)c}\chi^{(3)}A_1A_2A_3^* \qquad [26]$$



Figure 3 Two counter-propagating fields (E_1, E_2) and the third field E_3 create a polarization (nonlinear). The sample responds while radiating a fourth field E_4 opposite to the E_3 wave.



Figure 4 (a) Snell refraction in a conventional mirror; (b) Phase conjugate mirror.

where the phase matching condition is automatically fulfilled. Interesting facts can be described using this expression. First, the radiated amplitude is proportional to the complex conjugate of the E_3 field. This nonlinear process is not only able to reverse the direction of propagation but also the whole phase of an arbitrary incoming beam of light. This 'phase conjugator' can be considered as a kind of mirror with very unusual reflection properties. Unlike a conventional mirror, where a ray is redirected according to the ordinary law of reflection, a phase-conjugate mirror (PCM) retro-reflects all incoming rays back to their origin (Figure 4).

Second, the reflectivity of this mirror depends on the susceptibility and the amplitude of the first two fields, usually called pump beams. This will allow reflectivity that is much higher than the unity, unlike with conventional mirrors.

The remarkable reflection properties of the PCM have found many important applications. The most useful undoubtedly is related to distortion correction. If the image information has been distorted by the transmitting medium on its way to the PCM, then these aberrations will be corrected when the reflected signal retraces its original path through the medium. Through this amazing 'healing' property of optical phase conjugation, a high-quality optical beam can be double passed through a distorting medium, such as an imperfect imaging device or a turbulent atmosphere, without any loss of beam quality. Figure 5 shows the basic two-pass geometry for imaging and aberration correction using a PCM.

The spherical wave from the object point P is aberrated by the distorting medium. The wave-front is reversed by the PCM and a second passage through the same distorting path restores the initial field. The resulting spherical wave converges to the image point P', separated from P by the beamsplitter.

Numerous other applications for PCM and the various underlying nonlinear optical interactions have been proposed. These include effects as diverse



Figure 5 A basic two-pass system for imaging and distortion compensation using optical phase conjugation.

as parametric oscillation, optical tracking and pointing, spatial and temporal image processing, optical computing, optical filtering, etc. The PCM is also successfully implemented for aberration correction in high-power laser resonators.

Nondegenerate Four-Wave Mixing

If the frequencies of the impinging fields build a nonlinear polarization with an oscillating term close to absorption (or emission) frequencies of the sample, the nonlinear susceptibility increases tremendously. The radiated field amplitude changes by orders of magnitude and allows spectroscopic studies of the sample. The most popular process used to perform gas spectroscopy is CARS, an acronym for coherent anti-Stokes Raman scattering (or spectroscopy). In this case, the three incoming beams have different frequencies and the phase matching condition is eventually fulfilled in the 3D space.

Usually, two beams at the same frequency ω_P (pump beams), are mixed with a third beam at a tunable frequency ω_S, according to the energy scheme in Figure 6. As the radiated frequency ω_{CARS} is higher, the Raman spectroscopic notation is used and the subscripts 'S' hold for 'Stokes' and 'P' for 'anti-Stokes'.



Figure 6 Energy diagram for a CARS experiment. Four-wave mixing efficiency increases when the frequency difference $\omega_P - \omega_S$ is close to a resonant frequency of the sample, $\omega_{molecule}$.

Whenever $\omega_P - \omega_S = \omega_{molecule}$, then an increase of the CARS intensity by many orders of magnitude is observed. Therefore, a Raman spectrum can be obtained by continuously changing, the Stokes laser and simultaneously recording the intensity of the CARS beam. This procedure is called scanning CARS, an interesting technique insofar as it allows taking high-resolution spectra, as well as measuring temperature of the sample while scanning over the Boltzmann distribution of the electronic ground state.

Figure 7 displays a classical geometrical arrangement where the phase matching condition fully determines the directionality of the radiated field at ω_{CARS}. Although the alignment of the setup can become tedious, this technique has been widely used, even in hostile industrial environments. The coherent aspect of this four-wave mixing process, imbedded in the phase matching condition, has a huge benefit over classical spectroscopic techniques and thus isotropic techniques, such as laser-induced fluorescence or Raman spectroscopy.

The CARS process is an interference process comparable to diffraction of a grating. The two fields at ω_P and ω_S form a laser-induced moving grating and the third field, at ω_P, undergoes a Doppler shift at ω_{CARS}. This scattered field undergoes a coherent amplitude addition in the Bragg direction.

Conclusion

In this article, we have discussed a set of optical nonlinear processes occurring at the third order of the development in series of the material polarization. At this order, wave mixing obviously shows most



Figure 7 Layout of the CARS beams near a sample (a flame here). This particular arrangement is called folded (or 3D) Boxcars.

significant behavior and has been extensively studied and applied in many scientific areas. The general framework presented here can be further investigated using some books listed in Further Reading below.

See also

Fiber and Guided Wave Optics: Nonlinear Optics. **Nonlinear Optics, Applications:** Phase Matching. **Nonlinear Optics, Basics:** $\chi^{(3)}$–Third-Harmonic Generation. **Nonlinear Sources:** Harmonic Generation in Gases. **Optical Parametric Devices:** Optical Parametric Oscillators (Continuous Wave); Optical Parametric Oscillators (Pulsed).

Further Reading

Bloembergen N (1996) *Nonlinear Optics*. Singapore: World Scientific Pub Co.

Bloom DM and Bjorklund GC (1977) Conjugate wave-front generation and image reconstruction by four-wave mixing. *Applied Physics Letters* 31: 592–594.

Born M and Wolf E (1999) *Principles of Optics*. Cambridge, UK: Cambridge University Press.

Butcher PN and Cotter D (1991) *The Elements of Nonlinear Optics*. Cambridge, UK: Cambridge University Press.

Eaton DF (1991) Nonlinear optical materials. *Science* 253: 281–287.

Fisher RA (1984) *Optical Phase Conjugation*. San Diego, CA: Academic.

Flytzanis C (1975) Theory of nonlinear optical susceptibilities. In: Rabin H and Tang CL (eds) *Quantum Electronics*, vol. 1, pp. 9–207. New York: Academic Press.

Hellwarth RW (1977) Generation of time-reversed wave fronts by nonlinear refraction. *Journal of the Optical Society of America* 67: 1–3.

Jackson JD (1998) *Classical Electrodynamics*. New York: Wiley.

Marburger JH (1975) Self-focusing: Theory. *Progress in Quantum Electronics* 4: 35–110.

Mittra R and Habashy TM (1984) Theory of wave-front-distortion correction by phase conjugation. *Journal of the Optical Society of America A* 1: 1103–1109.

Rockwell DA (1988) A review of phase-conjugate solid-state lasers. *IEEE Journal of Quantum Electronics* 24: 1124–1140.

Shen YR (2002) *The Principles of Nonlinear Optics*. New York: Wiley.

Yariv A (1977) Compensation for atmospheric degradation of optical beam transmission. *Optical Communication* 21: 49–50.

Yariv A (1989) *Quantum Electronics*, 3rd edn. New York: Wiley.

Yariv A and Pepper DM (1977) Amplified reflection, phase conjugation, and oscillation in degenerate four-wave mixing. *Optical Letters* 1: 16–18.

Zel'dovich BYa, Pilipetsky NF and Shkunov VV (1985) *Principles of Phase Conjugation*. Berlin: Springer-Verlag.

Kramers–Krönig Relations in Nonlinear Optics

M Sheik-Bahae, The University of New Mexico, Albuquerque, NM, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Since their introduction nearly 75 years ago, the Kramers–Krönig (KK) dispersion relations have been widely appreciated and applied in the analysis of linear optical systems. Because they are a consequence of strict causality, the KK relations apply not only to optical systems, but also to any linear, causal system such as electrical networks and particle scattering. In this article, we review the formulation and application of these relations in nonlinear optical systems. Simple logical arguments are used to derive dispersion relations that relate the nonlinear absorption coefficient to the nonlinear refraction coefficient. More general formalisms are then derived that apply to all nonlinear susceptibilities including the harmonic generating cases. Examples of recent successful application of these dispersion relations in analyzing various nonlinear materials will be presented.

The mathematical formalism of the KK dispersion relations in nonlinear optics was studied in the formative days of the field. The great usefulness of these relations was appreciated only recently, however, when they were used to derive the dispersion of the optical Kerr effect in solids from the corresponding nonlinear absorption coefficients, including two-photon absorption.

Before examining the details of KK relations in nonlinear optical systems, it is instructive to revisit the linear dispersion relations and their derivation based on the logic of causality. We will begin this task by introducing the definition of the linear as well as nonlinear susceptibilities $\chi^{(n)}$. In most nonlinear optics texts, the total material polarization (P) that drives the wave equation for the electric field (E) is expressed as

$$\begin{aligned} P_i(t) = {} & \varepsilon_0 \int_{-\infty}^{\infty} R_{ij}^{(1)}(t-t_1)E_j(t_1)\mathrm{d}t_1 + \varepsilon_0 \int_{-\infty}^{\infty}\int_{-\infty}^{\infty} \\ & \times R_{ijk}^{(2)}(t-t_1, t-t_2)E_j(t_1)E_k(t_2)\mathrm{d}t_1\,\mathrm{d}t_2 \\ & + \varepsilon_0 \int_{-\infty}^{\infty}\int_{-\infty}^{\infty}\int_{-\infty}^{\infty} R_{ijkl}^{(3)}(t-t_1, t-t_2, t-t_3) \\ & \times E_j(t_1)E_k(t_2)E_l(t_3)\mathrm{d}t_1\,\mathrm{d}t_2\,\mathrm{d}t_3 + \cdots \end{aligned} \qquad [1]$$

where $R^{(n)}$ is defined as the nth-order, time-dependent response function or time-dependent susceptibility. The subscripts are polarization indices indicating, in general, the tensor nature of the interactions. The summation over the various indices $j, k, l, \ldots$ is implied for the various tensor elements of $R^{(n)}$. Upon Fourier transformation, we obtain:

$$\begin{aligned} \vec{P}_i(\omega) = {} & \varepsilon_0 \int_{\infty}^{-\infty} \mathrm{d}\omega_1\, \chi_{ij}^{(1)}(\omega_1)\vec{E}_j(\omega_1)\delta(\omega-\omega_1) \\ & + \varepsilon_0 \int_{\infty}^{-\infty} \mathrm{d}\omega_1 \int_{\infty}^{-\infty} \mathrm{d}\omega_2 \\ & \times \chi_{ijk}^{(2)}(\omega_1,\omega_2)\vec{E}_j(\omega_1)\vec{E}_k(\omega_2)\delta(\omega-\omega_1-\omega_2) \\ & + \varepsilon_0 \int_{\infty}^{-\infty} \mathrm{d}\omega_1 \int_{\infty}^{-\infty} \mathrm{d}\omega_2 \int_{\infty}^{-\infty} \mathrm{d}\omega_3 \\ & \times \chi_{ijkl}^{(3)}(\omega_1,\omega_2,\omega_3)\vec{E}_j(\omega_1)\vec{E}_k(\omega_2)\vec{E}_l(\omega_3) \\ & \times \delta(\omega-\omega_1-\omega_2-\omega_3), \cdots \end{aligned} \qquad [2]$$

where δ is the Dirac delta-function. Here the $E(\omega)$ are Fourier transforms of the corresponding electric field. The nth-order susceptibility is defined as the Fourier transform of the nth-order response function:

$$\begin{aligned} \chi_{ijk\ldots n}^{(n)}(\omega_1,\omega_2,\ldots,\omega_m) = {} & \int_{-\infty}^{+\infty}\mathrm{d}\tau_1 \int_{-\infty}^{+\infty}\mathrm{d}\tau_2 \cdots \int_{-\infty}^{+\infty} \\ & \times \mathrm{d}\tau_n R_{ijk\ldots m}^{(n)}(\tau_1,\tau_2,\ldots,\tau_m)\mathrm{e}^{\mathrm{i}(\omega_1\tau_1+\omega_2\tau_2+\cdots+\omega_m\tau_m)} \end{aligned} \qquad [3]$$

For simplicity, we drop the polarization indices $i, j, \ldots$, and thus ignore the tensor properties of $\chi^{(n)}$ as well as the vector nature of the electric fields.

Let us for the moment concentrate on the linear polarization alone and derive the linear KK relations for the first-order susceptibility $\chi^{(1)}(\omega)$. For this, we rewrite eqn [3] for $n = 1$:

$$\chi^{(1)}(\omega) = \int_{-\infty}^{\infty} R^{(1)}(\tau)\mathrm{e}^{-\mathrm{i}\omega\tau}\,\mathrm{d}\tau \qquad [4]$$

(As defined above, $\chi^{(1)}(\omega)$ and $R^{(1)}(\tau)$ are not a strict Fourier transform pair because of a missing factor of 2π.) Causality means that the effect cannot precede the cause. This can be restated mathematically as:

$$R^{(1)}(t) = R^{(1)}(t)\Theta(t) \qquad [5]$$

i.e., the response to an impulse at $t = 0$ must be zero for $t < 0$. Here $\Theta(t)$ is the Heaviside step function defined as $\Theta(t) = 1$ for $t > 0$ and $\Theta(t) = 0$ for $t < 0$. Upon Fourier transforming this equation, the product in the time domain becomes a convolution integral in frequency space

$$\begin{aligned} \chi^{(1)}(\omega) &= \chi^{(1)}(\omega)\left[\frac{\delta(\omega)}{2} + \frac{\mathrm{i}}{2\pi\omega}\right] \\ &= \frac{\chi^{(1)}(\omega)}{2} + \frac{\mathrm{i}}{2\pi}\wp\int_{-\infty}^{\infty}\frac{\chi^{(1)}(\omega')}{\omega-\omega'}\mathrm{d}\omega' \\ &= \frac{1}{\mathrm{i}\pi}\wp\int_{-\infty}^{\infty}\frac{\chi^{(1)}(\omega')}{\omega'-\omega}\mathrm{d}\omega' \end{aligned} \qquad [6]$$

which is the KK relation for the linear optical susceptibility. The symbol $\wp$ stands for the Cauchy principal value of the integral. The KK relation is thus a restatement of the causality condition [5] in the frequency domain. Taking the real part we have,

$$\Re e\{\chi^{(1)}(\omega)\} = \frac{1}{\pi}\wp\int_{-\infty}^{\infty}\frac{\Im m\{\chi^{(1)}(\omega')\}}{\omega'-\omega}\mathrm{d}\omega' \qquad [7]$$

Taking the imaginary part of eqn [6] leads to a similar relation relating the imaginary part to an integral involving the real part. It is conventional to write the optical dispersion relations in terms of the more familiar quantities of refractive index, $n(\omega)$, and absorption coefficient, $\alpha(\omega)$. For $|\chi^{(1)}| \ll 1$ then $n - 1 = \Re e\{\chi^{(1)}\}/2$ and $\alpha = \omega\Im m\{\chi^{(1)}\}/c$, and eqn [7] is transformed into

$$n(\omega) - 1 = \frac{c}{\pi}\wp\int_{0}^{\infty}\frac{\alpha(\omega')}{\omega'2-\omega^2}\mathrm{d}\omega' \qquad [8]$$

where we additionally used the reality conditions of $n(\omega) = n(-\omega)$, and $\alpha(\omega) = \alpha(-\omega)$ to change the lower integral limit to 0. More rigorous analysis shows that eqn [8] is general and valid for any value of $|\chi^{(1)}|$. Although the KK dispersion relations and the extent of their applications in linear optics are well understood, some confusion sometimes exists about their applications to nonlinear optics. Causality clearly holds for both linear and nonlinear systems. The question is: what form do the resulting dispersion relations take in a nonlinear system? The linear Kramers–Krönig relations were derived from linear system theory, so it would appear to be impossible to apply the same logic to a nonlinear system. The key insight is that one can linearize the system. This is illustrated in Figure 1 where a linear



Figure 1 (a) A causal linear system obeying KK relations. (b) The system in (a) when externally perturbed by ξ. The dotted box now represents our new linear causal system whose altered $\chi^{(1)}$ obeys the KK relations.

(and of course, causal) optical material is transformed into a 'new' linear system that now contains the material and an external perturbation denoted by ξ. Although we are interested in perturbations of an optical nature, this formalism is general under any type of perturbation. It is important to appreciate the fact that our new system is causal even in the presence of the perturbation. This allows us to write down a modified form of the Kramers–Krönig relation linking the index of refraction to the absorption:

$$[n(\omega) + \Delta n(\omega;\zeta)] - 1 = \frac{c}{\pi}\wp\int_0^\infty \frac{\alpha(\omega') + \Delta\alpha(\omega';\zeta)}{\omega'2 - \omega^2}\mathrm{d}\omega' \qquad [9]$$

which, after subtracting the linear relation between n and α leaves a relation between the changes in index and absorption:

$$\Delta n(\omega;\zeta) = \frac{c}{\pi}\wp\int_0^\infty \frac{\Delta\alpha(\omega';\zeta)}{\omega'2 - \omega^2}\mathrm{d}\omega' \qquad [10]$$

where ζ denotes a general perturbation. An equivalent relation also exists whereby the change in absorption coefficient can be calculated from the change in the refractive index. It is essential that the perturbation be independent of frequency of observation, ω', in the integral (i.e., the excitation ζ must be held constant as ω' is varied).

Equation [10] has been used to determine refractive changes due to 'real' excitations such as thermal and free-carrier nonlinearities in semiconductors. In those cases, ζ denotes either ΔT (change of temperature) or ΔN (change of free-carrier density), respectively. In the former case, one calculates the refractive index change resulting from a thermally excited electron–hole plasma and the temperature shift of the band edge. For cases where an electron–hole plasma is injected (e.g., optically), the change of absorption gives the plasma contribution to the refractive index. In this case, the ζ parameter in eqn [10] is taken as the change in plasma density regardless of the mechanism of generation or the optical frequency.

Let us now extend this formalism to the case where the perturbation is virtual, occurring at an excitation frequency Ω that is below any material resonance. To the lowest order in the excitation irradiance I_Ω, we write

$$\Delta\alpha(\omega;\zeta) = \Delta\alpha(\omega;\Omega) = 2\alpha_2(\omega;\Omega)I_\Omega \qquad [11]$$

and

$$\Delta n(\omega;\zeta) = \Delta n(\omega;\Omega) = 2n_2(\omega;\Omega)I_\Omega \qquad [12]$$

where n_2 and α_2 are the nonlinear refractive index and absorption coefficients of the material, respectively. By definition, these coefficients are related to the third-order nonlinear susceptibility $\chi^{(3)}(\omega_1,\omega_2,\omega_3)$ via (*see* **Nonlinear Optics, Basics**: Nomenclature and Units)

$$n_2(\omega;\Omega) = \frac{3}{4\varepsilon_0 n_0(\omega)n_0(\Omega)c}\Re e\{\chi^{(3)}(\omega,-\Omega,\Omega)\} \qquad [13]$$

and

$$\alpha_2(\omega;\Omega) = \frac{3\omega_a}{2\varepsilon_0 n_0(\omega)n_0(\Omega)c^2}\Im m\{\chi^{(3)}(\omega,-\Omega,\Omega)\} \qquad [14]$$

We can therefore write the dispersion relations between α_2 and n_2:

$$n_2(\omega;\Omega) = \frac{c}{\pi}\wp\int_0^\infty \frac{\alpha_2(\omega';\Omega)}{\omega'2 - \Omega^2}\mathrm{d}\omega' \qquad [15]$$

Note that even when the degenerate $n_2(\omega) = n_2(\omega;\omega)$ is desired (at a given ω), the dispersion relation requires that we should know the nondegenerate absorption spectrum $\alpha_2(\omega';\omega)$ at all frequencies ω'.

Let us pause here and discuss some physical mechanisms that can be involved for a given system of interest. Consider a material characterized by an optical resonance occurring at, say ω_0 (i.e., a degenerate two-level system). For a solid, this resonance can be regarded as that of the fundamental energy gap; $\omega_0 = \omega_g = E_g/\hbar$ in a two-band system. Now, let us examine how the presence of an optical excitation at $\Omega < \omega_0$ can alter the absorption spectrum (at a variable probe ω'). In the quantum mechanical picture, this gives rise to a 'new' material whose perturbed wave functions are 'dressed' by the intensity and frequency of the applied optical field.

The lowest-order correction to the absorption is given by $\alpha_2(\omega';\Omega)$ which involves three major physical processes. Recalling that $\Omega < \omega_0$, these processes include (1) two-photon absorption (2PA) when $\omega' + \Omega \rightarrow \omega_0$ and (2) Raman-induced absorption when $\omega' - \Omega \rightarrow \omega_0$, both implying an absorption of a photon at the probe frequency ω' (i.e., $\alpha_2 > 0$). The third process can be identified as resulting from the blue-shift (for $\Omega < \omega_0$) of the resonance (known as the quadratic optical Stark effect) caused by the excitation field. For our two-level system, the latter results in a decrease followed by an increase in absorption in the vicinity of ω_0. An example of the overall absorption changes due to such processes is shown in Figure 2 where $\alpha_2(\omega';\Omega)$ is qualitatively plotted for a degenerate two-level system. We should note that the relative magnitude of each contribution as well as the width and shape of the resonances are chosen arbitrarily for the purpose of illustration. Using the KK relation in eqn [15], we can now arrive at the nonlinear index coefficient $n_2(\omega;\Omega)$. The result of this transformation is also given in Figure 2. The above simple example elucidates the key concepts involving the relationship between nonlinear absorption and refraction in materials for third-order processes. These concepts, when applied more rigorously to semiconductors, have been successful in predicting the sign, magnitude, and dispersion of n_2 due to the anharmonic motion of bound electrons. This will be briefly discussed later. Returning to the mathematical foundation of KK relations, we use eqns [13] and [14] to write eqn [15] in terms of the nonlinear susceptibility $\chi^{(3)}$:

$$\Re e\{\chi^{(3)}(\omega_1,\omega_2,-\omega_2)\} = \frac{1}{\pi}\wp\int_{-\infty}^{\infty}\frac{\Im m\{\chi^{(3)}(\omega',\omega_2,\omega_2)\}}{\omega'-\omega_1}\,\mathrm{d}\omega' \qquad [16]$$

The above dispersion relation for $\chi^{(3)}$ was obtained using the physical and intuitive arguments that followed the linearization scheme depicted in Figure 1. General dispersion relations can be formulated following a mathematical procedure that is similar to the derivation of the linear KK relations. In this case we apply the causality condition directly to the nth-order nonlinear response $R^{(n)}$. For example, without loss of generality, we can write

$$R^{(n)}(\tau_1,\tau_2,\ldots,\tau_n) = R^{(n)}(\tau_1,\tau_2,\ldots,\tau_n)\Theta(\tau_j) \qquad [17]$$

and then calculate the Fourier transform of this equation. Here j can apply to any one of the indices $1,2,\ldots,n$. Following the same procedure as for a linear response, we obtain

$$\chi^{(n)}(\omega_1,\omega_2,\ldots,\omega_j,\ldots,\omega_n) = \frac{-\mathrm{i}}{\pi}\wp\int_{-\infty}^{\infty}\frac{\chi^{(n)}(\omega_1,\omega_2,\ldots,\omega',\ldots,\omega_n)}{\omega_j-\omega'}\mathrm{d}\omega' \qquad [18]$$



Figure 2 Upper trace: the nonlinear absorption coefficient in a fictitious 'degenerate' two-level system. Lower trace: the resulting nonlinear refractive index obtained using the KK relations. The insets show the three possible physical mechanisms involved.

By separating the real and imaginary parts of this equation, we get the generalized Kramers–Krönig relation pairs for a nondegenerate, *n*th-order nonlinear susceptibility:

$$\Re e\{\chi^{(n)}(\omega_1,\omega_2,\ldots,\omega_j,\ldots,\omega_n)\} = \frac{1}{\pi}\wp\int_{-\infty}^{\infty}\frac{\Im m\{\chi^{(n)}(\omega_1,\omega_2,\ldots,\omega',\ldots,\omega_n)\}}{\omega'-\omega_j}\mathrm{d}\omega' \qquad [19]$$

and

$$\Im m\{\chi^{(n)}(\omega_1,\omega_2,\ldots,\omega_j,\ldots,\omega_n)\} = -\frac{1}{\pi}\wp\int_{-\infty}^{\infty}\frac{\Re e\{\chi^{(n)}(\omega_1,\omega_2,\ldots,\omega',\ldots,\omega_n)\}}{\omega'-\omega_j}\mathrm{d}\omega' \qquad [20]$$

In particular, for $\chi^{(3)}$ processes having $\omega_1=\omega_a,\omega_2\omega_b$, and ${}_3b$, this becomes identical to eqn [16].

Note that in describing the nonlinear susceptibilities, no special attention was given to the harmonic generating susceptibility $\chi^{(N)}(N\omega)\equiv\chi^{(N)}(\omega,\omega,\ldots\omega)$, i.e., the susceptibility generating the *N*th harmonic at $N\omega$. It turns out that in addition to the KK relations given by eqns [19] and [20], the real and imaginary parts of $\chi^{(N)}(N\omega)$ can also be related in different sets of dispersion integrals that involve only the degenerate forms of the susceptibilities. A more general yet simple analysis gives the most general form of KK relations for any type of $\chi^{(n)}$:

$$\chi^{(n)}(\omega_1+p_1\omega,\omega_2+p_2\omega,\ldots,\omega_m+p_m\omega) = \frac{1}{\mathrm{i}\pi}\wp\int_{-\infty}^{\infty}\frac{\chi^{(n)}(\omega_1+p_1\Omega,\omega_2+p_2\Omega,\ldots,\omega_m+p_m\Omega)}{\Omega-\omega}\mathrm{d}\Omega \qquad [21]$$

for all $p_1,p_2,\ldots,p_m\geq 0$. Setting $\omega_1=\omega_2=\cdots=\omega_m\equiv 0$, and $p_1=p_2=\cdots=p_m=1$ in eqn [21] yields an interesting form of the KK relations for the *N*th-harmonic susceptibilities:

$$\Re e\{\chi^{(N)}(N\omega)\}=\frac{1}{\pi}\wp\int_{-\infty}^{\infty}\frac{\Im m\{\chi^{(N)}(N\omega')\}}{\omega'-\omega}\mathrm{d}\omega' \qquad [22]$$

These dispersion relations have allowed calculations of $\chi^{(2)}(2\omega)$ and $\chi^{(3)}(3\omega)$ in semiconductors using full band structures.

At the beginning of this article, it was noted that all the KK relations for nonlinear optics were known in the early days of the field. Their application in unifying nonlinear absorption (in particular two-photon absorption) and the optical Kerr effect (n_2) in solids came only much later. More recent work demonstrated that the KK relations are a powerful analytical tool in nonlinear optics. Following the picture of a degenerate two-level system shown in Figure 2, a simple two-band model has been used to calculate the nonlinear absorption coefficient, $\alpha_2(\omega_1;\omega_2)$, resulting from three mechanisms: 2PA, the Raman absorption process, and the ac Stark effect. The optical Kerr coefficient $n_2(\omega_1;\omega_2)$ was then calculated using eqn [15]. Of particular practical interest is the degenerate case ($\omega_1=\omega_2=\omega$), from which the 2PA coefficient $\beta(\omega)=\alpha_2(\omega;\omega)$ can be extracted. Figure 3 depicts the calculated dispersion of n_2 and β as a function of $\hbar\omega/E_g$ where E_g is the bandgap energy of the solid. The dispersion of n_2 and its sign reversal shown in Figure 3 has been observed experimentally in many optical solids.

Finally, let us discuss a related implication of causality in nonlinear optics. The KK dispersion relations are traditionally derived in terms of internal material parameters such as susceptibility, absorption coefficient, and refractive index. Similar to the case of electrical circuits, one can obtain dispersion relations that apply to an external transfer function of the system that relates an input signal to an output signal. In this case, the dispersion of the transfer function includes system structure as well as the intrinsic dispersion of the material. As an optical (and linear) example, consider a Fabry–Perot etalon. The optical transmission of this system has well-known spectral



Figure 3 The two-photon absorption coefficient in semiconductors (β) calculated for a two-band model. The resultant nonlinear refractive index (n_2) obtained using a KK transformation of the calculated nondegenerate nonlinear absorption coefficient includes all major mechanisms.

features that are primarily caused by structural dispersion (i.e., interference) in addition to the intrinsic dispersion of the material. Causality still demands that the transmitted signal has a phase variation whose value and dispersion can be determined using a KK relation linking the real and imaginary parts of the transmission coefficient. In other words, the KK relations provide a spectral correlation between the real and imaginary components of the transfer function which in turn may translate to a spectral correlation between the phase and amplitude of the transmitted signal. However, the variations in phase do not necessarily imply the presence of a varying index of refraction, nor does an amplitude variation suggest the existence of material absorption (dissipation). Ultimately, this implies that any mechanism causing a variation in amplitude (including reflection, scattering, or absorption) must be accompanied by a phase variation. (One should note that the reverse of the previous statement is not necessarily true; i.e., a variation in phase does not have to be accompanied by an amplitude modulation.)

In nonlinear optics with the 'black box' approach of Figure 1, the optical perturbation ξ (with frequency Ω) can render an amplitude variation in the probe (at ω) using various frequency mixing schemes in a noncentrosymmetric material (i.e., with nonzero $\chi^{(2)}$). For instance, the probe at ω can be depleted by nonlinear conversion to $\omega_{\text{sum}} = \omega + \Omega$ via sum-frequency generation involving $\chi^{(2)}(\omega, \Omega)$ and/or to $\omega_{\text{diff}} = \omega - \Omega$ via difference-frequency generation involving $\chi^{(2)}(\omega, -\Omega)$. Such a conversion (or depletion) should be accompanied by a phase variation according to the KK dispersion relations. This type of nonlinear phase modulation is known as a $\chi^{(2)}$:$\chi^{(2)}$ cascaded nonlinearity. Such cascaded processes are routinely (and more simply) analyzed with Maxwell's equations governing the propagation of beams in a second-order nonlinear material. The KK relations, however, provide an interesting physical perspective of the process. We find that cascaded second-order nonlinearities are yet another manifestation of causality in nonlinear optics.

List of Units and Nomenclature

α	linear absorption coefficient
α_2	nonlinear absorption coefficient
β	two-photon absorption coefficient
$\chi^{(n)}$	*n*th-order nonlinear optical susceptibility
n	linear refractive index
n_2	nonlinear refractive index coefficient, coefficient of optical Kerr effect
$\Theta(t)$	step function
$\wp$	principal value
2PA	two-photon absorption
KK relations	Kramers–Krönig relations

See also

Materials for Nonlinear Optics: Liquid Crystals for NLO. **Nonlinear Optics, Basics:** Cascading; Nomenclature and Units.

Further Reading

Bassani F and Scandolo S (1991) Dispersion-relations and sum-rules in nonlinear optics. *Physical Review B–Condensed Matter* 44: 8446–8453.

Caspers PJ (1964) Dispersion relations for nonlinear optics. *Physical Review A* 133: 1249–1251.

Hutchings DC, Sheik-Bahae M, Hagan DJ and Van Stryland EW (1992) Kramers–Krönig relations in nonlinear optics. *Optical and Quantum Electronics* 24: 1–30.

Kogan SM (1963) On the electromagnetics of weakly nonlinear media. *Soviet Physics JETP* 16: 217–219.

Nussenzveig HM (1972) Causality and Dispersion Relations. New York: Academic Press.

Price PJ (1964) Theory of quadratic response functions. *Physical Review* 130: 1792–1797.

Ridener FLJ and Good RHJ (1975) Dispersion relations for nonlinear systems of arbitrary degree. *Physical Review B* 11: 2768–2770.

Sheik-Bahae M and Van Stryland EW (1999) Optical nonlinearities in the transparency region of bulk semiconductors. In: Garmire E and Kost A (eds) *Nonlinear Optics in Semiconductors I*, 58, pp. 257–318. Academic Press.

Sheik-Bahae M, Hutchings DC, Hagan DJ and Van Stryland EW (1991) Dispersion of bound electronic nonlinear refraction in solids. *IEEE Journal of Quantum Electronics* 27: 1296–1309.

Smet F and Vangroenendael A (1979) Dispersion-relations for *N*-order non-linear phenomena. *Physical Review A* 19: 334–337.

Toll JS (1956) Causality and the dispersion relation: logical foundations. *Physical Review* 104: 1760–1770.

Nomenclature and Units

M P Hasselbeck, The University of New Mexico, Albuquerque, NM, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Nomenclature Associated with the Excitation Light

Particular care must be used when characterizing the excitation beam in nonlinear optical experiments compared to linear measurements. By definition, nonlinear optical phenomena depend on the electric field to high order. The higher the order, the more sensitive the observed behavior depends on the input. Extracting a representative nonlinear coefficient from an experiment, for example, becomes progressively more difficult as the order of the optical nonlinearity increases. In other words: the errors associated with optical beam characterization get magnified by the order of the nonlinearity under study.

There is an extensive nomenclature for characterizing the light (almost always laser light) interacting with the nonlinear optical medium. Different descriptions may be used depending on whether the excitation light is pulsed, continuous, or a continuous train of pulses. When a laser beam is constant or continuous, it is often described by its 'cw power'. 'Cw' stands for 'continuous wave', an acronym taken from the nomenclature of electronics. The cw power of a laser is determined by placing a power meter in the path of a beam. Repetitively pulsed lasers can be characterized in the same way, provided the response time of the power meter is slower than the pulse separation period. This will almost certainly be the case with a continuously pumped mode-locked laser such as a dye laser, fiber laser, or Ti:sapphire laser, which produce pulses at repetition frequencies of tens of megahertz. Cw power may also be suitable for describing pulsed flashlamp lasers, gas discharge lasers, or any laser that is excited in a periodic fashion.

When the optical output can be distinguished as individual pulses, additional metrics are used. A pulse, by definition, exists during a window of time, i.e., there is a time when light is present and a time when light is absent. How one characterizes the time light is present – the pulse duration – is critically important and not always obvious. There are a myriad of ways the pulse temporal envelope can manifest itself; common examples include square pulses, triangular pulses, Gaussian pulses, and hyperbolic secant pulses. These names refer to the mathematical waveforms that map the pulse envelope as a function of time.

A pulse waveform that exhibits symmetry about the peak in its temporal envelope is commonly characterized by its 'full-width, half-maximum', abbreviated FWHM. One obtains the full-width, half-maximum by locating the two points on the pulse profile that are at half the peak value. The temporal separation of these two points is the FWHM. One uses this measure because in a strict mathematical sense, waveforms such as the Gaussian or hyperbolic-secant exist even at times $t = \pm\infty$. A less common term is the 'half-width, half-maximum' or HWHM. As the name implies, the HWHM is exactly half the FWHM value. Not all light-pulses are temporally symmetric, however, so greater detail may be needed when giving a mathematical description of asymmetric pulses.

Light pulses are also characterized by their energy and peak power. The temporal envelope recorded by a so-called square-law detector (all laboratory detectors are square-law detectors) shows the power of the pulse as a function of time, provided the detector response time is sufficiently fast. Integrating this waveform gives the pulse energy. It makes no sense to talk about the energy of a cw beam of light, unless that beam is composed of repetitive, distinguishable pulses. Each pulse in the train carries a distinct amount of optical energy.

'Ultrafast' or 'ultrashort' laser pulses generally refer to light pulses that are of such small duration they cannot be measured directly with detectors and oscilloscopes because of bandwidth limitations. To infer the pulse duration, so-called intensity autocorrelation measurements are often made. The temporal power profile is then deduced from the autocorrelation signal with the appropriate mathematical conversion factor. Equally important is the spectrum of a short pulse. The optical bandwidth determines the lower limit of temporal compression; such ideally compressed pulses are said to be 'transform limited'. If different components of the spectrum can be distinguished at specific positions on the pulse temporal profile, then the pulse is 'chirped'. Information on the methods of ultrafast laser science can be found in **Ultrafast Laser Techniques:** Generation of Femtosecond Pulses.

Nonlinear optical effects take place when light is concentrated on a target – there is a cross-section or 'footprint' of the beam on the medium.

The interaction of the light and material takes place in a region called the beam area, beam cross-section, focal area, or focal volume. One must then define the appropriate interaction area or volume.

Specification of the beam area allows one to define two important quantities used frequently in nonlinear optics. The power/area is known as irradiance or power density. This quantity is commonly called the intensity, although the strict radiometric definition of intensity is power/(solid angle). The second important quantity is energy/area, which is called the energy density or fluence.

The convention in nonlinear optics is to define the optical electric field as:

$$\mathbf{E}(\mathbf{z},t) = \frac{1}{2}E_0 \exp[\mathrm{i}(\mathbf{k}\cdot\mathbf{z} - \omega t)] + \mathrm{c.c.} \qquad [1]$$

where E_0 is the peak field, **k** is the propagation vector, ω is the angular frequency of the light, and c.c. stands for complex conjugate. This represents a forward- and backward-propagating (in the z-direction) infinite, transverse plane wave. Other definitions are also used. In SI/mks units and using the convention of eqn [1], the irradiance (I in units of W/m^2) inside a material of refractive index n is related to the electric field vector of the light (**E** in units of V/m) as follows:

$$I = \frac{1}{2}cn\varepsilon_0|\mathrm{E}|^2 \qquad [2]$$

Here c is the speed of light (2.998×10^8 m/s) and ε_0 is the permittivity of free space (8.854×10^{-12} F/m). Nonlinear optics has an unfortunate tradition of mixing mks and cgs units, resulting in a lot of confusion. Irradiance is usually expressed in units of W/cm^2. One can calculate the peak electric field (in units of V/cm) of a laser beam given its irradiance (in units of W/cm^2) by using this simple formula:

$$E_0 = 38.82\sqrt{\frac{I}{n}}\left(\frac{\mathrm{V}}{\mathrm{cm}}\right) \qquad [3]$$

The root-mean-square value of the electric field is obtained by replacing the factor 38.82 by 27.45. In Gaussian/cgs units, irradiance is expressed in units of ergs/(cm^2 sec) and is related to the field as:

$$I = \frac{cn}{8\pi}|\mathbf{E}|^2 \qquad [4]$$

where the field is in units of statvolt/cm and $c = 2.998 \times 10^{10}$ cm/sec. Conversion between mks and cgs for the electric field is 3×10^4 V/m = 1 statvolt/cm; irradiance is converted using 1 erg/(cm^{2}sec) = 1×10^{-3}W/m^2. The following point must be emphasized: depending on how the electric field is defined, there can be factors of 2 or even 4 discrepancies in the irradiance values quoted by different authors. The common definitions are used here, although they are certainly not universal.

A very common realization of the spatial irradiance profile of a laser beam is the radially symmetric Gaussian function:

$$I(r) = I_0 \exp\left(-\frac{2r^2}{w^2}\right) \qquad [5]$$

where I_0 is the peak irradiance at the center of the beam ($r = 0$) and w is the 'spot size'. The spot size changes continuously as the beam propagates and the minimum spot size is known as the waist. One often hears the spot size referred to as the radius, but the radius of a Gaussian beam traditionally denotes the curvature of the phase front. By definition, the phase front radius is infinite at the waist. The factor of 2 appearing in the argument of the exponential in eqn [5] stems from the fact that the spot size w is conventionally defined for the electric field of the Gaussian beam. When the field is squared to obtain the irradiance, the factor of 2 appears. Using this function for the irradiance spatial profile leads to the common parameter '1/e^2 diameter'. The irradiance falls to 1/e^2 (0.1353) of its peak value when $r = w$.

The Gaussian spatial profile or 'Gaussian beam' results when the laser has been designed to operate in the lowest-order transverse mode, usually denoted TEM$_{00}$. The TEM$_{00}$ Gaussian beam is particularly convenient because the same relative power profile is maintained in the near- and far-field, whether or not the beam is collimated or focused.

The cross-sectional area of a TEM$_{00}$ Gaussian beam normally incident on a surface is found as follows. The power in the beam is obtained by integrating the irradiance profile (I) over the surface:

$$P = \iint_{\pm\infty} I\mathrm{d}A \qquad [6]$$

Referring to eqn [5], the integral becomes:

$$P = \int_0^{2\pi} \mathrm{d}\theta \int_0^{\infty} r\,\mathrm{d}r\, I_0 \exp\left(-\frac{2r^2}{w^2}\right) = I_0\frac{\pi w^2}{2} \qquad [7]$$

Hence the effective area of a TEM$_{00}$ Gaussian beam normally incident on a surface is:

$$A = \frac{\pi w^2}{2} \qquad [8]$$

There are many situations where the Gaussian formulation of eqn [5] is not suitable. Beams produced by unstable laser resonators, for example, are not Gaussian. A multitransverse mode beam profile obtained from a stable resonator does not usually lend itself to a simple mathematical characterization.

Nomenclature Associated with the Nonlinear Optical Medium

In nonlinear optics texts, the subject is often introduced by writing the macroscopic polarization in Maxwell's equations as a power series expansion in the electric field. This approach, proposed by Bloembergen and coworkers in the early 1960s, has been spectacularly successful for interpreting experiments, though it has also led to confusion in the definition of nonlinear optical coefficients. The confusion, which stems from arbitrary definitions and nomenclature used by different authors, cannot be resolved here. The reader should, however, be alert for these discrepancies. Comparison of results published by different laboratories requires that the fundamental equations for extracting the nonlinear coefficients from their data are known. As the discipline has matured, the nonlinear optics community largely recognized the ambiguities and confusion; precise definitions of terms and coefficients are now commonly provided in the research literature.

It should also be noted that the power-series framework may not always be the best formulation for modeling and characterizing nonlinear optical effects. A carefully designed optical limiter, for example, may exhibit an abrupt decrease of transmission at a specific 'threshold irradiance' or 'threshold fluence', perhaps at a given laser pulse duration. The physical phenomenon or phenomena driving this behavior may not readily succumb to characterization by an *n*th-order coefficient in a power series expansion. In this situation it may be appropriate to specify a threshold optical input parameter. Another example is a homogeneously broadened saturable absorber, in which the absorption of an optical medium decreases with increasing input irradiance. The irradiance-dependent absorption coefficient α (refer to eqn [26]) is characterized by a 'saturation irradiance' I_{sat}:

$$\alpha(I) = \frac{\alpha_0}{1 + \dfrac{I}{I_{\text{sat}}}} \qquad [9]$$

where α_0 is the linear absorption coefficient.

Nonlinear Susceptibility

The power-series expansion of the macroscopic polarization is the standard approach for modeling nonlinear optical behavior and categorizing the various phenomena. A common way to write the polarization, nonlinear in the electric field, is (mks units):

$$\mathbf{P} = \varepsilon_0\left(\chi^{(1)}\cdot\mathbf{E} + \chi^{(2)} : \mathbf{EE} + \chi^{(3)} \vdots \mathbf{EEE} + \ldots\right) \qquad [10]$$

where the polarization **P** is a time- and space-dependent vector and the terms $\chi^{(n)}$ are the various orders of the nonlinear susceptibility (the cgs equation is obtained by dropping the free-space permitivitty coefficient ε_0). A second-order effect is associated with $\chi^{(2)}$, a third-order with $\chi^{(3)}$, and so on. In general, there are distinguishable electric field vectors (in eqn [10], the fields have not been individually designated for clarity). The susceptibility terms are generally tensors, which means the medium is sensitive to the orientation of the input fields. The dots in eqn [10] indicate tensor products. The input field vectors can have different frequencies and the presence of complex conjugates in eqn [1] indicates that the frequency components will have both + and − signs, i.e. the *j*th electric field term will have associated frequency factors $\exp(\pm \mathrm{i}\omega_j t)$.

The nomenclature used here can be illustrated by example. In the case of the second-order nonlinear polarization (mks units):

$$\mathbf{P}_j = \varepsilon_0 \chi^{(2)}_{jkl} : \mathbf{E}_k \mathbf{E}_l \qquad [11]$$

Note that subscripts have been introduced. The indices correspond to Cartesian space vectors. This equation says that the polarization in the *j*-direction results from the tensor product of the appropriate $\chi^{(2)}$ with the input fields at $\mathbf{E}_k$ and $\mathbf{E}_l$. The *j*th component of polarization has an oscillation frequency that is determined by mixing of the input fields. In this example, the indices *j*, *k* and *l* can each take the value of *x*, *y*, and *z*. Let each input field be at one of two possible frequencies, call them ω_1 and ω_2. There are an enormous number of permutations (81 to be exact) of eqn [11]. One term is:

$$P_x(\omega_1 + \omega_2) = \varepsilon_0 \chi^{(2)}_{xzy}(\omega_1 + \omega_2) E_z(\omega_1) E_y(\omega_2) \times \exp[-\mathrm{i}(\omega_1 + \omega_2)t] \qquad [12]$$

Another possibility is:

$$P_z(\omega_2 - \omega_1) = \varepsilon_0 \chi^{(2)}_{zyx}(\omega_2 - \omega_1) E_y(\omega_2) E_x(-\omega_1) \times \exp[-\mathrm{i}(\omega_2 - \omega_1)t] \qquad [13]$$

Equation [12] corresponds to sum frequency generation $(\omega_1 + \omega_2)$ and eqn [13] shows difference frequency generation $(\omega_2 - \omega_1)$.

Not explicitly written on the right-hand side of the above equations is the exponential containing the mixing of the propagation vectors. To maximize the nonlinear polarization, which is the source of nonlinear behavior in Maxwell's equations, the vector sum $\sum \mathbf{k}_j$ for *all* the interacting fields should be close to zero. Arranging the propagation vectors to accomplish this is known as 'phase matching'.

It is important to point out that there are eight more terms describing the nonlinear polarization at $P_x(\omega_1 + \omega_2)$ in addition to eqn [12]; likewise for $P_z(\omega_2 - \omega_1)$. Also note that the indices k and l may be identical, hence a nonlinear polarization driven by $\chi^{(2)}_{xyy}$ for example, is allowed. Higher-order nonlinear polarizations get progressively more complicated. The general third-order nonlinear polarization is

$$\mathbf{P}_j = \varepsilon_0 \chi^{(3)}_{jklm} \vdots \mathbf{E}_k \mathbf{E}_l \mathbf{E}_m \qquad [14]$$

Sometimes the second-order nonlinear susceptibility is written with the coefficient d instead of $\chi^{(2)}$. The relation between the d-coefficient and $\chi^{(2)}$ depends arbitrarily on how it is defined; a common definition is

$$d_{jkl} = \frac{1}{2} \chi^{(2)}_{jkl} \qquad [15]$$

but the reader is cautioned that the factor $\frac{1}{2}$ is sometimes missing. In the preceding discussion it was pointed out how there can, in principle, be a large number of tensor components involved in the expansion of the nonlinear polarization. Simplification occurs when it is realized that there is no discernible physical difference between the frequency terms ω_j and $-\omega_j$ and that ordering of the fields in eqn [14] – which suggests a time order in the arrival of the fields – is irrelevant. These symmetry arguments show that $d_{jkl} = d_{jlk}$, which reduces the number of independent d-coefficients from 81 to 18. A simpler subscript notation is then introduced that uses the integers 1–6 to represent pairs of Cartesian components k and l. This reduces the number of subscripts from three to two. An example of this notation is $d_{xzz} = d_{14}$.

In certain situations, one can take advantage of crystal symmetry to further reduce the complicated summations to a single scalar coefficient for the nonlinear susceptibility, which is referred to as 'd-effective'. For these specialized cases, the nonlinear polarization is

$$P = \varepsilon_0 d_{\text{eff}} E_1 E_2 \qquad [16]$$

In SI/mks units, the polarization is in units of coul/m^2. The second-order susceptibility (i.e. $\chi^{(2)}$, d_{jkl}) must therefore have units of m/volt. The units of $\chi^{(3)}$ are m^2/volt^2, $\chi^{(4)}$ is m^3/volt^3, and so on. In Gaussian/cgs units, $\chi^{(2)}$ has dimensions cm/statvolt, $\chi^{(3)}$ will be cm^2/statvolt^2, etc. although sometimes in the Gaussian system *all* the coefficients $\chi^{(n)}$ are discussed with shorthand 'electrostatic units' or 'esu'.

Complex Quantities

In linear optics, the susceptiblity has real and imaginary parts

$$\chi^{(1)} = \chi^{(1)}_{\text{real}} + \mathrm{i}\chi^{(1)}_{\text{imaginary}} \qquad [17]$$

The complex linear index is, in turn, written as the sum of real and imaginary components, derived from the linear susceptibility as follows (mks units):

$$\sqrt{1 + \chi^{(1)}} = n_0 + \mathrm{i}\kappa \qquad [18]$$

where n_0 is the linear refractive index and κ is the imaginary term leading to absorption of light. In general, the nonlinear susceptibilty $\chi^{(n)}$ is also a complex number:

$$\chi^{(n)} = \chi^{(n)}_{\text{real}} + \mathrm{i}\chi^{(n)}_{\text{imaginary}} \qquad [19]$$

As in linear optics, the complex notation is a bookkeeping method that conveniently accounts for what is known as 'resonant enhancement'. Nonlinear optics research has revealed that the nonlinear susceptibility $\chi^{(n)}$ can be a strong function of frequency. Specifically, this quantity will be strongly enhanced when sums and/or differences of the photon energies in the interacting light beams coincide with quantum mechanical energy resonances in the material. When a resonance condition is achieved, $\chi^{(n)}$ will be dominated by its imaginary component. Far from the resonances, $\chi^{(n)}$ behaves more like a real quantity. These complex terms directly enter the wave equations describing how light propagates in a nonlinear medium and are particularly important for $\chi^{(3)}$; the complex quantity $\chi^{(3)}$ determines whether light will be refracted or absorbed and by how much. The real part of $\chi^{(3)}$ drives nonlinear refraction while the imaginary portion characterizes nonlinear absorption (e.g., two-photon absorption) and the inverse effect – gain. This rich subject – in particular the critical importance of the wavelength dependence of the nonlinear phenomena – is considered in **Nonlinear Optics, Basics:** Kramers–Krönig Relations in Nonlinear Optics.

Nonlinear Refraction

The most common manifestation of nonlinear refraction arises from the third-order nonlinear susceptibility, the so-called optical Kerr effect. In this case, the refractive index is linearly proportional to the irradiance (I) of a monochromatic light beam. The irradiance-dependent refractive index is

$$n(I) = n_0 + n_2 I \qquad [20]$$

where n_0 is the linear, irradiance-independent refractive index and n_2 is the nonlinear refractive index coefficient. Because n is a dimensionless quantity, n_2 must be in units of area/power.

The optical Kerr effect is usually written in mks units with the expression shown in eqn [20]. In cgs units, the common (but by no means universal) convention is to write:

$$n(E) = n_0 + \frac{1}{2}\tilde{n}_2 |\mathbf{E}|^2 \qquad [21]$$

where the field is in units of statvolts/cm. The nonlinear coefficient $\tilde{n}_2$ (cgs) must therefore be in units of cm^2/statvolt^2, which is sometimes abbreviated to 'esu'. The conversion for n_2 between these two equations is:

$$\tilde{n}_2(\text{cgs}) = \frac{n_0 c}{40\pi} n_2(\text{mks}) \qquad [22]$$

where n_2(mks) is in units of m^2/W and c is in m/sec. Also useful is the relation between n_2 and $\chi^{(3)}$, written in mks units as:

$$\Delta n = n_2 I = \frac{\mathrm{Re}\left(\chi^{(3)}\right)}{4\varepsilon_0 n^2 c} I \qquad [23]$$

where 'Re' denotes the real part of $\chi^{(3)}$. In cgs units we have:

$$\Delta n = \frac{1}{2}\tilde{n}_2 |\mathbf{E}|^2 = \frac{4\pi^2 \mathrm{Re}\left(\tilde{\chi}^{(3)}\right)}{n^2 c} I \qquad [24]$$

where I is in units of ergs/(cm^2 sec) defined by eqn [4]. The reader is again advised that different authors will show discrepancies of 2, 4, or even 8 when writing these equations. The susceptibilities $\chi^{(3)}$ are related as follows:

$$\tilde{\chi}^{(3)}(\text{cgs}) = \frac{9\times 10^8}{4\pi} \chi^{(3)}(\text{mks}) \qquad [25]$$

If the coefficients n_0 and n_2 exist, does the nomenclature imply there are terms n_1, n_3, and others? These coefficients are certainly allowed, but not often seen in discussions of nonlinear refraction. When one refers to nonlinear refraction, the common understanding is that the index depends linearly on irradiance, which is conveniently modeled by eqn [20]. But there are other physically relevant situations to consider. The coefficient n_1, for example, describes the linear electro-optic effect in which the change in index is linearly proportional to the electric field (although it is called the linear electro-optic effect, it is actually derived from the second-order nonlinear susceptibility). The electric field can be the oscillating field of a laser beam, for example, or a dc field applied to an electro-optic crystal (e.g., Pockel's cell). When other terms are added to eqns [20] or [21], the units of the coefficients must be chosen to keep the equation dimensionless.

In the preceding discussion, there is an implication that the nonlinear index is an instantaneous function of the irradiance or field. Although the material system can never respond instantaneously, this is a good approximation in many situations. Sometimes it is not. Consider a pulsed laser beam that heats the material. When the local temperature increases, the linear refractive index can change. A short, Q-switched laser can have a pulse duration far less than a microsecond, while the temperature change it induces can last many orders of magnitude longer. This means optical modification of the refractive index may persist long after the exciting pulse has vanished, i.e., when the irradiance is at zero.

Another example is when a laser beam promotes electrons from their ground state to higher energy states of the material system. These excited electrons may modify the refractive index of the material. In general, the excited electrons remain in high-energy states for some period of time before relaxing to the ground level – if this time is longer than the excitation, the change of the refractive index persists beyond the time the laser beam is present. In these situations, the model of nonlinear refraction suggested by the above equations is inaccurate. One cannot obtain the nonlinear refraction from a simple algebraic analysis. A system of time-dependent equations – describing the dynamics of excitation and relaxation – must be solved using numerical procedures. Such phenomena are sometimes loosely categorized as 'dynamic linear optical effects' or 'effective third-order nonlinearities'.

Nonlinear Absorption

Consider a single-frequency light beam passing through an optically absorbing region of length L.

For simplicity, neglect reflections caused by surfaces that may define the region of interest, i.e., ignore reflections at surfaces that may be located on the optical axis z at points $z = 0$, $z = L$, or any other point in the path. Linear absorption means that the optical power extracted from the light beam as it traverses the absorbing medium is a direct function of the power at a given point. This is described mathematically by an elementary, linear differential equation known as Beer's law:

$$\frac{\mathrm{d}}{\mathrm{d}z} I(z) = -\alpha I(z) \qquad [26]$$

The constant of proportionality is α, which is the linear absorption coefficient. Equation [23] is solved by direct integration:

$$\int_{I(0)}^{I(L)} \frac{\mathrm{d}I}{I} = -\alpha \int_0^L \mathrm{d}z \qquad [27]$$

This has the solution:

$$\frac{I(L)}{I(0)} = \exp(-\alpha L) \qquad [28]$$

which means the irradiance decreases exponentially as a function of propagation distance in a linearly absorbing medium.

In the nonlinear regime, we don't expect a classical Beer's law model to hold. By definition, the absorption will be a nonlinear function of irradiance at a given point. One makes the following power-series expansion to describe nonlinear absorption of monochromatic light:

$$\frac{\mathrm{d}}{\mathrm{d}z} I = -\alpha I - \beta I^2 - \gamma I^3 - \cdots \qquad [29]$$

The coefficient β corresponds to a two-photon absorption process and γ is the coefficient of three-photon absorption. What about four-photon and even higher-order processes? These are rarely encountered, but certainly possible. To make these distinctions, eqn [29] is sometimes written with coefficients K_i or α_i instead of the sequential Greek alphabet:

$$\frac{\mathrm{d}}{\mathrm{d}z} I = -K_1 I - K_2 I^2 - K_3 I^3 - K_4 I^4 - \cdots \qquad [30]$$

The units of the various absorption coefficients must maintain the dimensional consistency of eqns [29] and [30], which is irradiance/length or power/(length)^3. These are shown in Table 1.

Table 1 Dimensions of optical absorption coefficients

Process	*Coefficient*	*Units*
Linear absorption	α, K_1	(length)$^{-1}$
Two-photon absorption	β, K_2	length/power
Three-photon absorption	γ, K_3	length^3/power^2
Four-photon absorption	K_4	length^5/power^3

If there is linear absorption, the nonlinear processes at that wavelength are often (but not always) negligibly weak. This means we have the following inequalities:

$$K_1 I \gg K_i I^i, \qquad \text{where } i \geq 2 \qquad [31]$$

Nonlinear absorption is generally observed in the wavelength region where the medium is transparent to low-irradiance light, i.e., where linear absorption is negligible. It should be emphasized that there are situations where linear absorption is large and in fact a crucial component of the aggregate nonlinear effect. We will return to this point later in the discussion. For the moment, we neglect linear absorption. If the energy of the incident photons and energy levels of the system permit it, the lowest-order nonlinear process is two-photon absorption, described by the equation

$$\frac{\mathrm{d}}{\mathrm{d}z} I = -K_2 I^2 \qquad [32]$$

which can be solved by elementary integration:

$$\frac{I(L)}{I(0)} = \frac{1}{1 + I(0) K_2 L} \qquad [33]$$

Unfortunately, the situation is rarely this convenient. The above integration has ignored the fact that nonlinear absorption may enable significant linear absorption. This is possible because nonlinear absorption promotes electrons from low- to high-energy states in the medium. The change in excited electron density associated with absorption of light (both linearly and nonlinearly) is called 'photocarrier generation'. These photocarriers (e.g., photo-electrons) may modify the linear absorption as well as the refractive properties of the material. If two-photon absorption causes the linear absorption to increase, for example, the assumption that allowed us to ignore K_1 when writing eqn [32] ceases to be valid. While eqn [32] was appropriate at the very start of the light–matter interaction, the generation of photocarriers after the passage of time may change that condition. The behavior of the system is therefore time-dependent, i.e., it is dynamic. Simple analytic solutions are almost always not possible when dealing with nonlinear absorption.

The time rate of change of the photocarrier population (N) is modeled by the following equation:

$$\frac{\partial}{\partial t}N = \frac{K_1 I}{\hbar\omega} + \frac{K_2 I^2}{2\hbar\omega} + \frac{K_3 I^3}{3\hbar\omega} + \frac{K_4 I^4}{4\hbar\omega} + \cdots - \text{recombination} - \text{diffusion} \qquad [34]$$

where ω is the angular frequency ($\omega = 2\pi f$) of the incident light. Also included are place-holders for loss processes such as recombination and diffusion, which may themselves have complicated mathematical descriptions. The coefficients K_i have exactly the same units, dimensions, and interpretation as in eqn [30] and Table 1; in the spirit of the preceding discussion, these coefficients may be time dependent. Note that the dimensions of eqn [30] describe absorption of light (irradiance/length), while eqn [34] models the photocarrier population density (length^{-3} time^{-1}). The units of these two equations are very different.

List of Units and Nomenclature

CARS	Coherent anti-Stokes Raman scattering
c.c.	Complex conjugate
CSRS	Coherent Stokes Raman scattering
DFG	Difference frequency generation
DFM	Difference frequency mixing
DFWM, FWM	(Degenerate) Four wave mixing
DRO	Doubly resonant OPO
EIT	Electromagnetically induced transparency
ESA	Excited state absorption
GVD	Group velocity dispersion
GVM	Group velocity mismatch
NLA	Nonlinear absorption
NLR	Nonlinear refraction
OFID	Optical free-induction decay
OPA	Optical parametric amplification/amplifier
OPG	Optical parametric generation/generator
OPL	Optical power limiter
OPO	Optical parametric oscillation/oscillator
2PA, TPA	Two-photon absorption
PCM	Phase conjugate mirror
QPM	Quasi phase matching
RIKES	Raman-induced Kerr effect spectroscopy
RSA	Reverse saturable absorption
SBS	Stimulated Brillouin scattering
SFG	Sum frequency generation
SHG	Second harmonic generation
SIT	Self-induced transparency
SRO	Singly resonant OPO
SRS	Stimulated Raman scattering
SRWS	Stimulated Rayleigh wing scattering
SVEA, SVAA	Slowly varying envelope (amplitude) approximation
THG	Third harmonic generation
TPF	Two-photon fluorescence

See also

Fiber and Guided Wave Optics: Nonlinear Optics. **Nonlinear Optics, Basics:** Ultrafast and Intense-Field Nonlinear Optics. **Spectroscopy:** Nonlinear Laser Spectroscopy.

Further Reading

Bloembergen N (1992) *Nonlinear Optics*. Redwood City, CA: Addison-Wesley.

Boyd RW (1991) *Nonlinear Optics*. Boston, MA: Academic Press.

Levenson MD and Kano S (1988) *Introduction to Nonlinear Laser Spectroscopy*. Boston, MA: Academic Press.

Miller A, Miller DAB and Smith SD (1981) Dynamic nonlinear optical processes in semiconductors. *Advances in Physics* 30: 697–800.

Mills DL (1998) *Nonlinear Optics: Basic Concepts*. New York: Springer.

Newell C and Moloney JV (1992) *Nonlinear Optics*. Redwood City, CA: Addison-Wesley.

Sauter EG (1996) *Nonlinear Optics*. New York: Wiley.

Shen YR (1984) *The Principles of Nonlinear Optics*. New York: Wiley.

Sutherland RL (1996) *Handbook of Nonlinear Optics*. New York: Marcel Dekker.

Yariv A (1991) *Optical Electronics*, 3rd edn. New York: Holt, Rinehart, and Winston.

Yariv A (1989) *Quantum Electronics*. New York: Wiley.

Zernike F and Midwinter JE (1973) *Applied Nonlinear Optics*. New York: Wiley.

Nonlinear Optical Phase Conjugation

B Y Zeldovich, University of Central Florida,
Orlando, FL, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Phase conjugation (PC) beams and their applications are best illustrated by Figure 1, which shows the passage of a coherent planewave incident upon a transparent optical element with inhomogeneities of refractive index (Figure 1a). Reversibility of light propagation implies the existence of such an 'anti-distorted' beam, which reverts back to a planewave after reversing through the same inhomogeneities (Figure 1b). A real-valued monochromatic optical wave, $E_{\mathrm{real}}(\mathbf{R}, t)$, may be represented by the complex amplitude $E(\mathbf{R})$ via $E_{\mathrm{real}}(\mathbf{R}, t) = 0.5[E(\mathbf{R})\exp(-i\omega t) + E^*(\mathbf{R})\exp(i\omega t)]$, where $E^*(\mathbf{R})$ represents the complex conjugate of $E(\mathbf{R})$:

$$\begin{aligned} E(\mathbf{R}) &= |E(\mathbf{R})| \exp[i\varphi(\mathbf{R})] \\ E^*(\mathbf{R}) &= |E(\mathbf{R})| \exp[-i\varphi(\mathbf{R})] \end{aligned} \qquad [1]$$

Mathematical expression of time-reversal, $E_{\mathrm{real}}(\mathbf{R}, t) \rightarrow E_{\mathrm{real}}(\mathbf{R}, -t)$, becomes the exchange $E(\mathbf{R}) \leftrightarrow E^*(\mathbf{R})$ for monochromatic waves. The reversibility of propagation means that the complex propagating field $E(\mathbf{R})$ (for example, planewave $\exp(i\mathbf{k}\cdot\mathbf{R})$), is a wave equation solution equivalent to $E^*(\mathbf{R})$ (in this example, $\exp(-i\mathbf{k}\cdot\mathbf{R})$). Conjugation of complex amplitude means reversal of the sign of the phase, and a mixed label PC has been coined and nowadays is firmly established. Terms such as 'wave front reversal' and 'generation of time-reversed replica of the beam' are also used to describe PC.

Figure 1 also illustrates one of the most important applications of PC. If the element in question is a laser-type amplifier, then double-passage allows the extraction of energy from the optically inhomogeneous laser medium in the form of a perfectly collimated beam of diffraction-limited divergence. A PC device may also serve as a mirror of a laser resonator, resulting in the same beam-correction purpose.

One of the most practical and robust methods of PC is based on stimulated Brillouin back-scattering (SBS). The incident beam illuminates the SBS-active transparent medium, for example, liquids (CS_2, CCl_4, acetone, etc.), compressed gases (CH_4, SF_6, etc.), or solids (fused or crystalline quartz, glass, etc.). This 'pump' beam, $E(\mathbf{R}) \equiv E(\mathbf{r}, z)$, must possess well-developed transverse inhomogeneities of intensity $|E(\mathbf{r}, z)|^2$. Here, $\mathbf{r} = \{x, y\}$ is the part of coordinate vector transverse with respect to the central direction z of the beam in question, and $\mathbf{R} = \{\mathbf{r}, z\}$. These inhomogeneities may constitute a narrow focal waist in the case of weakly distorted focused beams, speckle-inhomogeneities in cases of strong distortions, or a combination thereof; see Figure 2, where solid lines symbolize the 'rays' of the incident pump.

Spontaneous scattering of the pump results in a multitude of possible transverse profiles $S(\mathbf{r}, z = 0)$ of the signal, whose 'rays' are depicted via the dotted lines on Figure 2. The signal is amplified exponentially due to SBS processes. This exponent in a simplified form may be represented as $|S(\mathbf{r}, z)|^2 \propto \exp(\int g dz)$, with the gain $g(z)$ being the result of transverse overlapping of the intensity profiles of signal and pump:

$$g(z) \approx \mathrm{const} \cdot \langle |E(\mathbf{r}, z)|^2 \cdot |S(\mathbf{r}, z)|^2 \rangle / \langle |S(\mathbf{r}, z)|^2 \rangle \qquad [2]$$

Thus, the similarity of the intensity profile of the signal to that of the pump is rewarded by the exponential preference in the output signal level. However, this is not enough to guarantee that the output backward-scattered signal $S(\mathbf{r}, z)$ is phase



Figure 1 (a) Collimated beam is distorted by propagation through inhomogeneous medium. (b) Conjugate, a.k.a. antidistorted beam becomes collimated after backward passage through the same medium.



Figure 2 Stimulated Brillouin Scattering (SBS) method of PC. Solid lines symbolize the rays of incident 'beam', while dotted lines depict the rays of the signal amplified by the SBS process.

conjugate with respect to the pump. It is here that the mutual reversibility of propagation of strongly inhomogeneous signal and pump becomes crucial. Namely, good transverse overlapping is sustained along the entire interaction length z, only if $S(\mathbf{r}, z) \propto E^*(\mathbf{r}, z)$. This constitutes the 'discrimination mechanism' of SBS-PC: the 'conjugate mode' of the signal has a z-sustained advantage in exponential gain and, under appropriate conditions, suppresses all nonconjugate signal configurations in competition for pump power. Nonlinear-optical wave theory of this discrimination process has been developed further.

The holographic mechanism of PC has a different nature. It may take the form of static holography or dynamic holography; the latter essentially may be considered as a part of nonlinear optics. Here is a simplified description of one of the variants. Suppose one wants to obtain a conjugate replica of the incident monochromatic signal, whose complex profile is $S(\mathbf{R})$. A plane reference wave $A(\mathbf{R}) = \exp(i\mathbf{k}_A \cdot \mathbf{R})$ is also directed to the registering medium. If $S(\mathbf{R})$ and $A(\mathbf{R})$ are mutually coherent, then an interference pattern of intensity is produced $\{S^*(\mathbf{R})A(\mathbf{R}) + \text{compl. conj.}\}$. The medium records this pattern in the form of the modulation of refractive index and/or of the absorption coefficient, $\delta\varepsilon(\mathbf{R}) \propto (c_1 + ic_2)\{S^*(\mathbf{R})A\ (\mathbf{R}) + \text{c.c.}\}$ (Figure 3a). At the 'reconstruction' stage, the hologram is illuminated by another plane reference wave, $B(\mathbf{R}) = B_0 \exp(i\mathbf{k}_B \cdot \mathbf{R})$. In the specific case, when $\mathbf{k}_B = -\mathbf{k}_A$, the source δD_{conj} of the reconstructed wave becomes, as shown by Figure 3b:

$$\delta D_{\text{conj}} = (c_1 + ic_2)[S^*(\mathbf{R})A(\mathbf{R})]\cdot B(\mathbf{R}) \propto S^*(\mathbf{R}) \times (c_1 + ic_2)A_0B_0 \qquad [3]$$



$A_0\exp(i\mathbf{k}_A\cdot\mathbf{R})$
$S(\mathbf{R})$
(a)
$B_0\exp(-i\mathbf{k}_A\cdot\mathbf{R})$
$S^*(\mathbf{R})$
(b)

Figure 3 (a) Recording of a hologram in a photosensitive medium by a reference wave A and signal wave S. (b) Read-out of that hologram by the wave B counter-propagating to A results in generation of the conjugated signal S^*.

Reversibility of propagation laws guarantees that this source will indeed excite a conjugate wave with high efficiency. Both processes, recording of the interference pattern and reconstruction of the conjugate wave, may occur simultaneously, if one deals with the dynamic holography. The same process may also be described as nonlinear-optical four-wave mixing (FWM) via cubic nonlinearity $\chi^{(3)}$:

$$\delta D_{\text{conj}}(\mathbf{R}) = \chi^{(3)}S^*(\mathbf{R})A(\mathbf{R})B(\mathbf{R}) = \chi^{(3)}S^*(\mathbf{R})A_0B_0 \qquad [4]$$

with the four waves; A, B, S, S^*.

Important characteristics of a PC device are: fidelity of conjugation, efficiency of returning back-reflected power/energy, and reaction time or build-up time. The fidelity parameter must show how close the output of the device $E_{\text{out}}(\mathbf{r})$ is to the perfectly conjugate profile $S^*(\mathbf{R})$ of the incident signal (up to an arbitrary constant complex factor). Among other definitions, the square modulus of the normalized transverse overlapping integral of the fields is often discussed:

$$f = \frac{|\iint E_{\text{out}}(x, y)S(x, y)\mathrm{d}x\mathrm{d}y|^2}{\left(\iint |E_{\text{out}}(x, y)|^2\mathrm{d}x\mathrm{d}y \cdot \iint |S(x, y)|^2\mathrm{d}x\mathrm{d}y\right)} \qquad [5]$$

To achieve good (close to 1) fidelity of PC in the holographic or FWM scheme, one has to guarantee that the reference waves, $A_0 \exp(i\mathbf{k}_A \cdot \mathbf{R})$ and $B_0 \exp(i\mathbf{k}_B \cdot \mathbf{R})$, are exactly conjugate to each other, $\mathbf{k}_A = -\mathbf{k}_B$. That, in turn, requires the absence of any distortions in the holographic or nonlinear medium. To the contrary, there are very modest requirements on the phase inhomogeneities of the medium in the SBS scheme of PC, and for that reason it is usually labeled as a scheme of self-phase conjugation.

A hybrid scheme, Brillouin-assisted FWM, has been suggested and implemented, where mutually conjugate reference waves are produced via SBS-PC, while FWM, in a separate medium, exploits SBS nonlinearity. This scheme has produced extremely high, up to about 10^{10}, reflectivity, accompanied by an extremely low-noise detection of incoming signals.

A number of other PC schemes were first realized with the use of an important class of materials for nonlinear optics: photo-refractive crystals (PRC). These are crystals where ionization of the dopants by the incident light creates interference pattern of charge separation. The linear electro-optic (Pockels) effect transforms the resulting patterns of the electrostatic field into patterns of refractive index, thus creating dynamic holograms. A remarkable property of these crystals is that most of them act as very good electrical insulators. Therefore, the only source of conductivity, which tends to erase the hologram, is photoconductivity, the value of the latter being proportional to the intensity of incident light itself. For this reason, the steady-state strength of the hologram turns out to be independent of the intensity. It is the build-up time that must be increased, if intensity is low. One can achieve various processes in PRC, including those similar to the $\chi^{(3)}$-type optical Kerr effect, stimulated scattering, etc.

The simplest use of PRC for generation of PC waves is to devise a FWM scheme (see Figure 3). However, a multitude of other, nontrivial schemes have been devised and implemented. The most impressive use of PRC for PC is based on interactions of the beams in the vicinity of a corner of a rectangular crystal, typically $BaTiO_3$, these interactions being of the stimulated scattering type. To honor J. Feinberg's cat, whose image was reconstructed in the first demonstration, this scheme is universally called 'cat conjugator'. It turned out to be a very reliable and robust scheme of self-phase-conjugation (SPC).

Another important group of the SPC scheme is called 'tail-biting'. One of the variants of the latter is shown in Figure 4. Incident 'pump' wave $A(\mathbf{R})$, whose transverse profile one wants to conjugate, enters the medium, and then is redirected by mirrors back into the same medium, to 'bite itself'. For the purpose of discussion, this redirected pump is labeled as wave $B(\mathbf{R})$ on its second arrival into the medium. Spontaneous scattering results in a seed for the amplification of the wave $C(\mathbf{R})$ via the process of stimulated scattering (SS) $A(\mathbf{R}) \rightarrow C(\mathbf{R})$.

Wave $C(\mathbf{R})$ is also redirected into the medium by the same mirrors, and is labeled as wave $D(\mathbf{R})$ on its second arrival into the medium. Both $C(\mathbf{R})$ and $D(\mathbf{R})$ are depicted in Figure 4 by white arrows. Wave $D(\mathbf{R})$ is also amplified due to the SS process $B(\mathbf{R}) \rightarrow D(\mathbf{R})$.



Figure 4 Tail-biting scheme of phase conjugation.

As it follows from the macroscopic description of SS process, volume gratings of refractive index are recorded in the medium, $\delta n(\mathbf{R}) \propto -i[A^*(\mathbf{R})C(\mathbf{R}) + B^*(\mathbf{R})D(\mathbf{R})]$. Among all the transverse profiles for the seed $C(\mathbf{R})$, the one that happens to be proportional to $B^*(\mathbf{R})$ will be reflected by the mirrors into the medium in the form $D(\mathbf{R}) \propto A^*(\mathbf{R})$. The latter case is again a consequence of the reversibility of propagation laws, where both gratings have the same profile and add coherently in the form $A^*(\mathbf{R})B^*(\mathbf{R})$. What is even more important, the grating $B^*(\mathbf{R})D(\mathbf{R}) \propto B^*(\mathbf{R})A^*(\mathbf{R})$ serves to close the feedback loop for seeding the appropriate $C(\mathbf{R})$. This, and other variants of tail-biting schemes, have also proved to be reliable and robust. Quite often a laser amplifier is inserted in the path $A \rightarrow B$ and $C \rightarrow D$, thus enhancing the feedback.

Another important scheme is traditionally called 'double PC'; albeit it may be better described as 'mutual PC'. Figure 5 should help in understanding that scheme. Consider the beam $A(\mathbf{R})$ incident to a medium active with respect to the stimulated-scattering-type process $A(\mathbf{R}) \rightarrow C(\mathbf{R})$. This process originates from a random seed and results in a fan of different waves $C(\mathbf{R})$. Such a process is characteristic of PRCs and is a consequence of recording dynamic gratings of refractive index $\delta n(\mathbf{R}) \propto -i[A^*(\mathbf{R})C(\mathbf{R})]$. Suppose another beam $B(\mathbf{R})$, typically incoherent with respect to $A(\mathbf{R})$, illuminates the medium from the other side, and also is engaged in the fanning process, this time $B(\mathbf{R}) \rightarrow D(\mathbf{R})$, with the grating of refractive index $\delta n(\mathbf{R}) \propto -i[B^*(\mathbf{R})D(\mathbf{R})]$ involved. Among all the transverse profiles for the seed grating $C(\mathbf{R})A^*(\mathbf{R})$, the one that happens to be proportional to $B^*(\mathbf{R})A^*(\mathbf{R})$ will be supported by similar profiles in the $B(\mathbf{R}) \rightarrow D(\mathbf{R})$ scattering. In this way, two fanning



Figure 5 Towards the mechanism of double PC (mutual PC).

processes enhance each other and close the feedback loop. An important consequence is that one obtains the following output waves:

$$\begin{aligned} C(\mathbf{R}) &= \mathrm{const}_1 \times B^*(\mathbf{R}) \\ D(\mathbf{R}) &= \mathrm{const}_2 \times A^*(\mathbf{R}) \end{aligned} \qquad [6]$$

One can say that the output wave $C(\mathbf{R})$ presents a conjugate replica of $B(\mathbf{R})$-beam, while the output wave $D(\mathbf{R})$ presents a conjugate replica of $A(\mathbf{R})$-beam; hence the label 'mutual PC'. In some experiments the incident beams, $A(\mathbf{R})$ and $B(\mathbf{R})$, were of somewhat different colors (i.e., from different lasers), or their pulses did not overlap in time in the medium. It is the grating memory that 'informs' one beam about the presence of the other. The mechanism of cat conjugator is considered to be a combination of tail-biting and double PC schemes.

Pumped laser material with saturable gain often serves as an important nonlinear-optical medium for implementing PC. One of the evident advantages is that possible low efficiency of properly nonlinear process may be compensated by the gain in the same piece of material.

Considerable attention is paid nowadays to the chirp reversal of optical pulses that are used in fiber optical communications. Such chirped pulses, $S(t) = \exp(-i\omega_0 t + i\beta t^2/2 - t^2/\tau_1^2)$, with the value of the 'chirp' $\mathrm{d}\omega/\mathrm{d}t = -\beta$ and an increased pulse duration τ_1, arise as a result of propagation in a fiber which possesses group velocity dispersion (GVD). Pulse stretching and chirp are the consequences of different propagation times for the different frequency constituents of the pulse. If some device changes the sign of that chirp, then subsequent propagation of the pulse, through a piece of fiber with the same GVD, restores the duration of the pulse to original shorter value τ_0. A scheme has been suggested to use nonlinear optical FWM in a $\chi^{(3)}$-medium or three-wave mixing (ThWM) in a $\chi^{(2)}$-medium:

$$\begin{aligned} \delta D_{\mathrm{conj}}(t) &= \chi^{(3)} S^*(t) A(t) B(t) \\ \delta D_{\mathrm{conj}}(t) &= \chi^{(3)} S^*(t) C(t) \end{aligned} \qquad [7]$$

Indeed, complex conjugation of the time dependence of the signal's field is equivalent to the change of the chirp sign. The second (ThWM) expression is written assuming that the reference wave $C(t) \propto \exp(-2i\omega_0 t)$, so that is has the frequency double that of the signal. The same process of ThWM has been shown to yield the conjugation of transverse phase profile of the beams, but for a number of reasons it was not applied.

As for the applications of PC, one of them was discussed above (Figure 1: double-pass scheme of a laser amplifier). Lasers with one or two PC mirrors, or with more complicated PC scheme, promise generation of high-transverse-quality beams with the use of realistic laser media, the latter inevitably possessing thermal and other distorting inhomogeneities. Another important potential application is free-space optical communications: Earth–Earth or Earth–satellite through atmosphere, or satellite–satellite communications. An 'interrogating' beam may be sent in one direction through an imperfect optical system and/or through turbulent atmosphere. Conjugation of transverse profile of the 'interrogating' beam at the other end of the communication link leads to an almost perfect redirection of the reflected beam towards the 'beacon' source, while time modulation may carry the information.

Readout of information data from a holographic storage is almost always performed in the regime of reading the conjugate wave, since it corrects for the most part of aberrations of optical systems in question.

To conclude, one may use a citation from the two consecutive *Scientific American* popular papers on PC: 'at present the number of applications would seem to be limited only by imagination.'

Reviews of various aspects of phase conjugation may be found in monographs and *Scientific American* papers listed below. The author of the present article was introduced to PC by his colleague V. V. Ragulskii, and has greatly benefited from collaboration with V. V. Ragulskii and V. V. Shkunov.

See also

Microscopy: Phase Contrast Microscopy. **Nonlinear Optics, Basics:** Four-Wave Mixing. **Phase Control:** Phase Conjugation and Image Correction. **Scattering:** Scattering Theory.

Further Reading

Bespalov VI and Pasmanik GA (1994) *Nonlinear Optics and Adaptive Laser Systems*. Commack, NY: Nova Science Publishers.

Feinberg J (1986) Self-pumped, continuous wave phase conjugator using internal reflection. *Optics Letters* 7: 486.

Fisher RA (ed.) (1983) *Optical Phase Conjugation*. New York: Academic Press.

Gower M and Proch D (eds) (1994) *Optical Phase Conjugation*. Berlin: Springer Verlag.

Hellwarth RW (1982) Optical beam conjugation by stimulated backscattering. *Optical Engineering* 21: 257.

Nosatch OYu, Popovichev VI, Ragulskii VV and Faizullov FS (1972) Compensation of phase distortions in an amplifying medium by a 'Brillouin mirror'. *JETP Letters* 16: 435.

Pepper DM (1986) Applications of optical phase conjugation. *Scientific American* 254: 74–83.

Shkunov VV and Zeldovich BYa (1985) Optical phase conjugation. *Scientific American* 253: 54–59.

Yariv A (1978) Phase conjugate optics and real-time holography. *IEEE Journal of Quantum Electronics* 14: 650.

Zeldovich BYa, Popovichev VI, Ragulskii VV and Faizullov FS (1972) On relation between wavefronts of reflected and exciting radiation in stimulated Brillouin scattering. *JETP Letters* 16: 109.

Zeldovich BYa, Shkunov VV and Pilipetsky NF (1985) *Principles of Phase Conjugation*. Berlin: Springer-Verlag.

Zeldovich BYa, Mamaev AV and Shkunov VV (1995) *Speckle-Wave Interactions in Application to Holography and Nonlinear Optics*. Boca Raton, FL: CRC Press.

Photorefraction

M Cronin-Golomb, Tufts University, Medford, MA, USA

B Kippelen, University of Arizona, Tucson, AZ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction and Basics of the Photorefractive Effect

In 1966 Ashkin and coworkers were pursuing research on optical devices using the electro-optic material lithium niobate. They noticed that the refractive index of lithium niobate would change when it was exposed to laser light, and upset the expected operation of their devices. They called the effect optical damage. Shortly thereafter, Chen, LaMacchia, and Fraser reported on the use of the optical damage effect for holographic data storage. Thus began the field of photorefractive nonlinear optics, which has been used in various applications such as real-time holography, optical data storage, optical image amplification, nondestructive testing, distortion compensation by phase conjugation, pattern recognition, and radar signal processing. Many inorganic and organic materials have been investigated for their photorefractive effects, including ferroelectrics, semiconductors, and sensitized polymers. The most well-known inorganic materials are lithium niobate, bismuth silicon oxide, barium titanate, and strontium barium niobate. Most organic photorefractive materials are based on polymeric photoconductors such as those used in xerography that are doped with electro-active molecules, some plasticizers, and sensitizers.

While in its broadest interpretation, the photorefractive effect occurs whenever light incident on a material causes a refractive index change, one usually applies the term to electro-optic index changes resulting from optically generated space charge fields. Materials that are photorefractive in this sense share the following properties

- high transmission at the operating wavelengths;
- linear electro-optic coefficients or orientational Kerr effects;
- charge carriers that become mobile when optically excited;
- trapping centers for these charge carriers to enable spatially non-uniform redistribution of charge.

Consider two beams from the same laser crossing inside a photorefractive material such as barium titanate. The interference pattern will have bright and dark fringes. Charge carriers are excited where the light is bright, then drift and diffuse to regions of relative darkness where they preferentially recombine into trapping centers. In this way, a net excess charge develops in the dark regions, and a net deficit of charge develops in the bright regions. The spatially varying charge distribution has an electric field associated with it and this electric field causes a spatially varying refractive index profile. Because the space charge, its field, and resulting refractive index have the same spatial periodicity as the original interference pattern we have a holographic phase grating. The diffraction efficiency of the hologram can easily approach 100% for materials such as barium titanate and strontium barium niobate which have high electro-optic coefficients. Likewise, such high diffraction efficiencies are easily obtained in 100 micrometer-thick photorefractive polymer films.

The Standard Rate Equation Model

The development of photorefractive gratings can be modeled using standard semiconductor rate equations. Figure 1 shows two beams incident


Beam 1
Beam 2
$I(x) = I_0\,(1 + m\cos k_g x)$
Space charge
$\rho(x) \propto m\cos k_g x$
$E(x) = \frac{1}{\varepsilon}\int\rho\,dx$
$\Delta n(x) = -\frac{1}{2}n^3 r E(x)$
+++ --- +++ --- +++ --- +++ ---
π/2
x

Figure 1 Diagram of two-beam coupling process showing optical interference pattern, space charge, resultant electric field, and π/2 phase shifted electro-optically induced refractive index grating.

symmetrically on a photorefractive crystal or polymer. They form an interference pattern whose intensity may be written:

$$I(x) = I_0(1 + m\cos(k_g x)) \qquad [1]$$

where x is the direction perpendicular to the interference fringes, I_0 is the average intensity, m is the modulation index, and k_g is the wavenumber of the interference pattern.

The crystal may be considered a wide bandgap semiconductor containing electron donors in the bandgap with density N_D and electron acceptors with density N_A. It is assumed that some electrons ionized from the donors permanently occupy these acceptors so that when charge in the crystal is distributed uniformly in the dark, the number density of ionized donors N_D^i is equal to N_A. Likewise, polymers contain donor and acceptor-like molecules that can be neutral or ionized. The spatially varying light distribution ionizes the donors at the following rate, assuming that $N_D^i \ll N_D$:

$$\frac{\partial N_D^i}{\partial t} = sIN_D - \gamma_R n_e N_D^i \qquad [2]$$

where s is a photoionization coefficient, γ_R is a recombination parameter, and n_e is the density of excited charge carriers, which we assume here to be electrons. The model can easily be generalized to include holes. We also use the equation of charge conservation:

$$\frac{\partial N_D^i}{\partial t} = \frac{\partial n_e}{\partial t} - \frac{1}{e}\nabla\cdot\mathbf{j} \qquad [3]$$

where e is the charge of an electron, and $\mathbf{j}$ is the current in the conduction band.

$$\mathbf{j} = \mu e n_e \mathbf{E} + k_B T \mu \nabla n_e \qquad [4]$$

where μ is the electron mobility, k_B is Boltzmann's constant, and T is the temperature. The electric field obeys Gauss's law:

$$\nabla\cdot\mathbf{E} = -e(n_e + N_A - N_D^i)/\varepsilon \qquad [5]$$

where N_A is the density of acceptors. These equations may be linearized by approximating the electron density, ionized donor density, and electric field with their first Fourier components:

$$\begin{aligned} E &= E_0 + \tfrac{1}{2}(E_1\exp(ik_g x) + E_1^*\exp(-ik_g x)) \\ N_D^i &= N_{D0}^i + \tfrac{1}{2}(N_{D1}^i\exp(ik_g x) + N_{D1}^{i*}\exp(-ik_g x)) \qquad [6] \\ n_e &= n_{e0} + \tfrac{1}{2}(n_{e1}\exp(ik_g x) + n_{e1}^*\exp(-ik_g x)) \end{aligned}$$

This assumption is strictly valid only when the modulation index m is much less than unity. Otherwise, a generalization to higher orders in the Fourier series is required. However, the linearized theory is sufficient to illustrate the most important features of the photorefractive effect. The solution for the space charge field E_1 for the case when the interference pattern is applied at time $t = 0$ is

$$E_1 = m\frac{-iE_Q(E_0 + iE_D)}{E_0 + i(E_D + E_Q)}(1 - \exp(-t/\tau)) \qquad [7]$$

where E_0 is an externally applied or photovoltaic field (if any), E_D is the diffusion field

$$E_D = \frac{k_B T k_g}{e} \qquad [8]$$

and E_Q is the limiting space charge field

$$E_Q = \frac{eN_A}{\varepsilon k_g} \qquad [9]$$

Some photorefractive crystals, most notably $LiNbO_3$, exhibit the photovoltaic effect in which optical illumination induces a dc field across the crystal.

The sinusoidally varying space charge field E_1 operates through the linear electro-optic effect with effective coefficient r to produce a sinusoidal variation in the refractive index n of the crystal:

$$n(x) = n_0 + \tfrac{1}{2}(n_1\exp(ik_g x) + n_1^*\exp(-ik_g x)) \qquad [10]$$

where

$$n_1 = -\frac{1}{2}rn_0^3 E_1 \qquad [11]$$

The effective electro-optic coefficient r may be found from tensor analysis of the electro-optic tensor and the vector space charge and optical fields. Notice that there is a 90-degree phase shift between the interference pattern and the refractive index grating when E_0 is zero. The time constant τ is given by

$$\tau = \frac{N_A}{sN_D I_0}\frac{E_0 + i(E_D + E_\mu)}{E_0 + i(E_D + E_Q)} \qquad [12]$$

where E_μ is a mobility field

$$E_\mu = \frac{\gamma_R N_A}{\mu k_g} \qquad [13]$$

When E_0 is nonzero, there is an oscillatory component to the time constant.

In contrast to the case of ordinary optical nonlinearities such as the optical Kerr effect, in which the nonlinear coupling strength is proportional to the optical intensity, the steady state strength of the photorefractive effect is independent of optical intensity while the time constant is inversely proportional to intensity in the basic model described above. The time constant varies with the photoconducting performance of a given material. In the fastest polymeric and inorganic materials it is, at the time of writing, of the order of a few milliseconds at 1 W cm^{-2} of incident optical intensity.

At low intensities (below the equivalent dark intensity, 1 W cm^{-2} in barium titanate), the above equations need to be modified to include the effect of dark conductivity. Even in the dark, there will be a few mobile charge carriers in the conduction band that tend to erase the grating. This will result in the effect appearing more Kerr-like, except still with the 90-degree phase shift between the index grating and the interference pattern.

Coupled Wave Equations

The change in refractive index n_1 can be large enough to produce substantial interactions between the writing beams. The writing beams generate a phase grating that diffracts the beams into each other. The grating influences the writing beams, which in turn influence the grating. In the cases where the diffusion field dominates, for example when the externally applied or photovoltaic field E_0 is absent, one beam is amplified by in-phase diffraction of the other beam from the grating. As shown in Figure 2, this amplification results from a 90-degree phase shift due to diffraction from a phase grating coupled with a -90-degree phase shift from the spatial phase shift between the interference pattern and the index grating. The second beam is attenuated by destructive interference with the first beam diffracted by the grating. These interactions can be modeled by standard coupled wave theory. Let the electric field amplitude associated with the jth beam be



Figure 2 Two-beam coupling amplification. Beam 1 is amplified by constructive interference. Beam 2 is de-amplified by destructive interference.

$$\mathbf{E}_j(\mathbf{r},t) = \mathbf{e}\Big[A_j(\mathbf{r})\exp(i(\mathbf{k}_j\cdot\mathbf{r} - \omega t)) + A_j^*\exp(-i(\mathbf{k}_j\cdot\mathbf{r} - \omega t))\Big] \qquad [14]$$

where $\mathbf{e}$ is the polarization unit vector. Using the scalar wave equation

$$\nabla^2\mathbf{E} + k^2\mathbf{E} = 0 \qquad [15]$$

and the slowly varying envelope approximation

$$\left|\frac{d^2A_j}{dz^2}\right| \ll k\left|\frac{dA_j}{dz}\right| \qquad [16]$$

we find

$$\begin{aligned}\frac{dA_1}{dz} &= +\gamma\frac{A_1|A_2|^2}{I_0}\\ \frac{dA_2^*}{dz} &= -\gamma\frac{A_2^*|A_1|^2}{I_0}\end{aligned} \qquad [17]$$

with the coupling constant γ given by

$$\gamma = -\frac{i\omega\Delta n_m}{c\cos\vartheta} \qquad [18]$$

where ϑ is the half-angle between the writing beams and Δn_m is given by

$$\Delta n_m = -\frac{1}{2}n_0^3 r\frac{E_1}{m} \qquad [19]$$

Equation [17] shows that beam 1 is amplified and beam 2 is attenuated. That beam 1 is amplified instead of beam 2 is a result of the choice of crystal orientation and hence the sign of γ. These nonlinear equations can be solved for normalized intensity $I_j = |A_j|^2$:

$$\begin{aligned} I_1(z) &= \frac{I_0}{1 + (I_2(0)/I_1(0))\exp(+\Gamma z)} \\ I_2(z) &= \frac{I_0}{1 + (I_1(0)/I_2(0))\exp(-\Gamma z)} \end{aligned} \qquad [20]$$

where $\Gamma = \gamma + \gamma^*$ is the intensity coupling constant. In the limit where $I_1 \ll I_2$, the weak beam, beam 1, experiences exponential amplification. This amplification can be used to build optical oscillators with many of the same properties as conventional laser oscillators. The solution can be generalized to the case where γ has an imaginary component due to an applied or photovoltaic field E_0. Linear absorption can also be included.

Materials

Photorefractive materials may be separated into two broad classes: inorganic and organic. The first materials investigated were inorganic oxides and semiconductors. Their success led to efforts to endow more easily produced organic materials with the required photoconductivity, charge trapping centers, and electro-optic coefficients.

Inorganic Materials

The first requirement in a classic photorefractive material is a linear electro-optic coefficient, such as appears in sillenites such as bismuth silicon oxide $Bi_{12}SiO_{20}$ and bismuth germanium oxide $Bi_{12}GeO_{20}$. These were some of the first photorefractive materials used for image processing and phase conjugation applications. However, their electro-optic coefficients (a few pm/V) are not large enough to easily give rise to large diffraction efficiencies, or to photorefractive oscillators. Materials at a temperature near a phase transition generally have higher electro-optic coefficients because their crystal structures are on the verge of changing. They are extremely susceptible to the effect of any external influence such as the application of electric fields including photorefractive space charge fields. That is why ferroelectric materials are good candidates for photorefractive materials. These include barium titanate $BaTiO_3$, potassium niobate $KNbO_3$, and strontium barium niobate $Sr_xBa_{1-x}Nb_2O_6$. The mean free path of charge transport is less than that in sillenites, so they require more photons to reach a steady state. Therefore, ferroelectric materials are typically less sensitive than sillenites.

The second requirement is for photoconductivity. This requires the existence of photoexcitable charge carriers, either from valence band to conduction band or from intraband trapping centers. The latter source of photocarriers is used most often because the absorption length of light whose energy is greater than the bandgap is usually only a few micrometers. This places a severe restriction on the beams' interaction length ℓ. Thus there has been considerable research on suitable dopants, most commonly $Fe^{2+}$and Fe^{3+}. These dopants also act as trapping centers.

Lithium niobate is an example of a material with a large photovoltaic effect. When illuminated, this crystal develops a large dc field, which acts to enhance the grating strength. In those cases where the photorefractive effect is not wanted, such as in the design of lithium niobate waveguide devices, the photovoltaic effect can be greatly diminished by the addition of MgO to the crystal melt during growth.

For photorefractivity in the near infrared, semiconductors such as gallium arsenide and indium phosphide have been used with success. These materials also have the advantage that they can be grown in layered structures to produce, for example, multiple quantum wells that can be used to tailor the characteristics of optical excitation and charge transport.

Organic Materials

First-generation photorefractive polymers were designed to mimic the properties of their inorganic counterparts. Owing to their rich structural flexibility, organic synthetic materials with suitable charge transport, trapping, linear electro-optic effects and low optical absorption, were developed. This approach did build on the know-how developed previously in making photoconducting polymers for xerography and electro-optic polymers for optical modulation. Current polymers are based on an orientational photorefractive effect that leads to higher refractive index changes compared with traditional photorefractive materials. In materials with orientational photorefractivity, the refractive index change is produced by the field induced reorientation of anisotropic conjugated molecules that possess a permanent dipole moment and that have a high polarizability anisotropy. The photorefractive space charge field together with the applied field will periodically reorient these molecules and produce a periodic refractive index modulation through an orientational Kerr effect. The build-up and dynamics of this space-charge field are similar to those of traditional photorefractive crystals and can be described by eqns [2]–[7]. The time constant of the hologram is a convolution of the build-up time of the space-charge and the orientational diffusion time of the dipolar molecules in the total electric field. In contrast to crystals, polymers are nearly amorphous and the transport properties are described by charge hopping processes instead of band-type transport in crystals. Consequently, the photoconducting properties of polymers are strongly field dependent and photorefractivity is mainly observed under strong applied voltages. Numerous polymer composites have been developed using the hole transport polymer poly(N-vinylcarbazole). Several materials with a refractive index modulation amplitude of the order of a percent and two-beam coupling constants $\gamma > 100\ \mathrm{cm}^{-1}$ have been reported. New polymer composites are continuously being tested. Photorefractivity is also studied in other organic materials including organic crystals, liquid crystals, nanocomposites such as polymer-dispersed liquid crystals, or hybrid materials such as sol-gels.

Applications

Holographic Data Storage

Holographic data storage takes advantage of the Bragg selectivity of thick gratings. This allows many holograms to be superimposed in the same small volume, typically of the order of one cubic centimeter. A page of data is displayed on a spatial light modulator and a laser beam passing through the modulator is holographically recorded in the crystal with a reference beam at a specific angle. Many pages of data can be superimposed by recording many holograms with angularly multiplexed reference beams. Other multiplexing schemes are implemented by changing the shape of the wavefront of the reference beam. In principle, the upper limit of recording density is determined by the wavelength of light: one bit per cubic wavelength. If the recording wavelength is 0.5 μm, then one cubic centimeter can contain 1000 gigabytes of data. In practical circumstances, when noise is taken into consideration, the capacity is more realistically of the order of one gigabyte if a 1000 × 1000 spatial light modulator is used.

Distortion Compensation by Phase Conjugation

Photorefractive materials can be used to make high-reflectivity phase conjugate mirrors. The phase conjugate of a laser beam is produced when a hologram of the beam is read by another beam traveling in the opposite direction to the original reference beam. The phase conjugate reconstruction is a time-reversed copy of the original beam. If the original beam has passed through distorting optics, then the phase conjugate beam will retrace the path of the original beam through the distortion and emerge in its undistorted original state. In the standard nomenclature of phase conjugation, the input beam is called the signal, or probe, and the two reference beams are called the pumps. The output beam at $z = 0$ is called the phase conjugate beam and has zero amplitude at its input at $z = \ell$, where ℓ is the interaction length. Applications for phase conjugation exist, for example, in signal transmission through distortions and laser cavity design. If a phase conjugate mirror is used as a cavity mirror, then the effects of intracavity distortions are removed.

Since the photorefractive gratings can be very strong, the diffraction efficiency of the counterpropagating reference beam can be so high that the phase conjugate reflectivity can exceed unity. The simplest generalization of eqn [17] to the four-wave mixing phase conjugation case is when only transmission gratings are important, as occurs in many circumstances depending on the mutual coherence properties of the beams, and the material's properties. The coupled wave equations are

$$\begin{aligned}
\frac{\mathrm{d}A_1}{\mathrm{d}z} &= \gamma\frac{(A_1A_4^* + A_2^*A_3)A_4}{I_0}\\
\frac{\mathrm{d}A_2^*}{\mathrm{d}z} &= \gamma\frac{(A_1A_4^* + A_2^*A_3)A_3^*}{I_0}\\
\frac{\mathrm{d}A_3}{\mathrm{d}z} &= -\gamma\frac{(A_1A_4^* + A_2^*A_3)A_2}{I_0}\\
\frac{\mathrm{d}A_4^*}{\mathrm{d}z} &= -\gamma\frac{(A_1A_4^* + A_2^*A_3)A_1^*}{I_0}
\end{aligned} \qquad [21]$$

In the undepleted pumps approximation, $(I_1, I_2 \gg I_3, I_4)$, the equations become linear and the solution for phase conjugate reflectivity $R = I_3(0)/I_4(0)$ is

$$R = \left|\frac{\sinh[\gamma\ell/2]}{\cosh[(\gamma\ell + \ln r)/2]}\right|^2 \qquad [22]$$

where $r = I_2/I_1$ is the ratio between the intensities of the pumping beams.

The fact that the reflectivity of the phase conjugate mirror can be greater than unity means that we can build an optical oscillator bounded by a regular mirror and a phase conjugate mirror only. Not only does it not require any additional optical gain, but it also compensates for intracavity distortions. The regular mirror can have any shape, provided that it is sufficiently reflective.

Self-pumped Phase Conjugate Mirrors

If a laser beam passes through a crystal placed inside an optical cavity formed by two facing mirrors, light scattered by imperfections in the crystal can be amplified through the photorefractive effect. The cavity provides feedback and optical oscillation can build up. The oscillation beams pump the crystal as a phase conjugate mirror for the incident beam, thus forming a self-pumped phase conjugate mirror. The feedback can even be provided by total internal reflection in the crystal in which case the crystal by itself can become a phase conjugate mirror.

Pattern Recognition and Image Filtering

Photorefractive wave mixing can be used to perform pattern recognition by matched filtering. One example would be to identify a tank in a battlefield scene, another would be to identify all of the occurrences of a particular word on a page of text. Suppose the input beams contain the corresponding pictorial information, such as might be obtained by passing the beams through an image-bearing transparency or spatial light modulator. Equation [21] shows that the source for beam 3 contains a term proportional to the product of the amplitudes of the three input beams. If lenses are placed in the input beams so that the crystal receives the Fourier transforms of those beams, then the output beam at the crystal, beam 3, will be proportional to the product of the Fourier transforms of the input beams 1, 2, and 4. A lens may then be used to perform the inverse Fourier transform of the product of the Fourier transforms of the input beams, producing an output proportional to beam 1 convolved with beam 2 correlated with beam 4. If beam 1 is a point source before its Fourier transforming lens, then it will be a plane wave at the crystal. Beam 3 after inverse Fourier transformation by its lens will be the correlation of beams 4 and 2. For example, suppose we want to find all the occurrences of a particular word, say 'optics' in a given page of text. Then we would make a transparency of the word 'optics' and place that in input beam 4. We would then place an image of the page of text in beam 2. Beam 3 would then contain a field with bright spots at the places containing the word 'optics' in the original text.

The real-time holographic recording properties of photorefractive materials can also be exploited in medical imaging applications by performing time-gated holography. In this method, a hologram is formed by the temporal overlap in the photorefractive sample of a reference pulse and the first-arriving (ballistic photons) light from a stretched image-bearing pulse that has propagated through a scattering medium. The filtering of the useful photons from the scattered ones is achieved by reconstructing the hologram formed with the ballistic photons in a four-wave mixing geometry.

Optical Limiting, the Novelty Filter, and Laser Ultrasonic Inspection

The attenuation of beam 2 in eqn [17] can be used in several applications including optical limiting and novelty filtering. If one wants to protect a sensor from high-intensity laser radiation, then one could split a small portion of the input beam directed at the sensor and use it as beam 1 in a photorefractive recording setup with the input beam acting as beam 2. If the laser intensity is above the equivalent dark intensity such that the optically excited charge density is greater than the thermally excited charge density, the photorefractive effect will be activated and the input beam will be de-amplified by destructive interference with beam 1, thus protecting the sensor. In materials with high gain–length products ($\gamma\ell > 1$), separate provision of beam 1 is unnecessary because light scattered from the input beam by imperfections in the material and other scattering centers will be greatly amplified, often to such an extent that the input beam is almost completely attenuated. This photorefractive amplification of scattered radiation is known as the fanning effect, because the amplified scattered light often appears as a fan, or brush of light, as can be seen in Figure 3. The effect can also be used to make a novelty filter, which transmits only the moving portion of a scene. The crystal is only fast enough to



Figure 3 Photorefractive barium titanate exhibiting amplified scattering. A helium neon laser beam is incident from the lower left, passes through the crystal to a screen where it is blacked out to prevent saturation of the camera. The screen shows brushes of amplified scattering, or fanning.

respond to the slowly changing or static components of an image-bearing beam. Since the grating formed is Bragg-matched only to the slow component, the grating will only attenuate that slow component. Any rapidly changing parts of a scene pass through the crystal unattenuated. Such a filter is useful for picking out moving objects in a static cluttered background, for example a tank on a battlefield, or a micro-organism swimming against a stationary background.

A related application is in laser ultrasonic inspection. Defects in industrial material processing such as welding have characteristic ultrasonic signatures. The part under test is pinged by a pulsed laser and a probe laser is reflected from the part. As the part is shaken by the ultrasound, speckle in the reflected beam vibrates. A photorefractive recording is made of the speckle beam. Electrodes are placed on the photorefractive material, so that any optically induced currents can be detected. If the speckle pattern is not moving, or is moving more slowly than the speed of response of the photorefractive material, the photorefractive grating will be essentially at steady state: the drift currents balance the diffusion currents so there is no net current. There is no signal as the part moves through the process line. However, if the speckle beam is moving faster than the response time of the material, it will move photoexcited charge back and forth past the quasistatic grating and generate a net current for detection via the electrodes.

Adaptive Signal Processing

The relatively slow speed of photorefractive devices can be used to advantage in radio-frequency (RF) signal processing, such as signal extraction and coherent combination of signals from antenna arrays. The signal extraction application depends on grating competition in two-beam coupling. Suppose we wish to separate signals on two different RF carrier frequencies ω_1 and ω_2, respectively. The combined signal is applied to an optical carrier beam using a high-speed modulator. The resulting optical field may be represented as

$$S_1(t)\exp(i\omega_1 t) + S_2(t)\exp(i\omega_2 t) \qquad [23]$$

It is used to pump a unidirectional ring resonator so that grating competition allows oscillation only on the strongest component of the combined signal, say S_1. The output of the oscillator is proportional to the extracted component S_1. The effectiveness of the intersignal competition is enhanced by placing another photorefractive material in the cavity. A portion of the intracavity beam is picked off by a beamsplitter and used as a two-beam coupling pump in the second material. The crystal is oriented so that the photorefractive grating diffracts the picked-off beam back into the cavity. The return of the picked-off component is most effective for the stronger component S_1 thus decreasing its loss compared to that of the weaker component S_2. This beamsplitter/crystal combination is known as a reflexive coupler.

Photorefractive Solitons

Under favorable conditions, a single beam incident on a photorefractive crystal will induce a positive refractive index change at the center of the beam. This provides a self-focussing tendency that counteracts the beam's divergence due to diffraction. When these two effects balance each other, the beam can propagate with a constant diameter. Such a beam is known as a spatial soliton in analogy with temporal solitons in optical fibers and can occur when there is a component of the photorefractive response due to drift. The drift component of the photorefractive effect appears when a dc field E_0 is applied to the material. Potential applications are optically written waveguides and couplers.

List of Units and Nomenclature

Amplitude gain	[cm^{-1}]	γ
Applied dc field	[Vm^{-1}]	E_0
Current	[Am^{-2}]	$\mathbf{j}$
Dielectric permittivity	[Farads m^{-1}]	ε
Diffusion field	[Vm^{-1}]	E_D
Electron acceptor density	[m^{-3}]	N_A
Electron charge	[C]	e
Electron donor density	[m^{-3}]	N_D
Grating wavenumber	[m^{-1}]	k_g
Intensity gain	[cm^{-1}]	Γ
Interaction length	[cm]	ℓ
Ionized donor density	[m^{-3}]	N_D^i
Limiting space charge field	[Vm^{-1}]	E_Q
Mobility	[m^2 V^{-1} sec^{-1}]	μ
Mobility field	[Vm^{-1}]	E_μ
Normalized intensity	[V^2 m^{-2}]	I
Photo-ionization coefficient	[kg sec^{-2}]	s
Photorefractive time constant	[sec]	τ
Pump ratio	[1]	r
Radian frequency	[sec^{-1}]	ω
Recombination coefficient	[m^3 sec^{-1}]	γ_R
Slowly varying optical electric field	[Vm^{-1}]	A

See also

Holography, Applications: Holographic Recording Materials and Their Processing. **Holography, Techniques:** Holographic Interferometry. **Imaging:** Volume Holographic Imaging. **Information Processing:** Free-Space Optical Computing; Optical Neural Networks. **Materials for Nonlinear Optics:** Organic Nonlinear Materials. **Modulators:** Electro-Optics. **Nonlinear Optics, Basics:** Four-Wave Mixing; Nonlinear Optical Phase Conjugation. **Phase Control:** Phase Conjugation and Image Correction. **Scattering:** Stimulated Scattering. **Solitons:** Bright Spatial Solitons.

Further Reading

Coufal HJ, Psaltis D and Sincerbox GT (eds) (2000) *Holographic Data Storage*. Berlin: Springer.

Gunter P and Huignard J-P (eds) (1988) *Photorefractive Materials and their Applications I*. Berlin: Springer-Verlag.

Gunter P and Huignard J-P (eds) (1989) *Photorefractive Materials and their Applications II*. Berlin: Springer-Verlag.

Nalwa HS and Miyata S (eds) (1997) *Nonlinear Optics of Organic Molecules and Polymers*. Boca Raton: CRC Press.

Nolte DD (ed.) (1995) *Photorefractive Effects and Materials*. Kluwer.

Pepper DM, Feinberg J and Kukhtarev NV (1990) The photorefractive effect. *Scientific American* 263: 62.

Solymar L, Webb DJ and Grunnet-Jepsen A (1996) The Physics and Application of Photorefractive Materials. Oxford: Clarendon Press.

Yeh P (1993) Introduction To Photorefractive Nonlinear Optics. New York: Wiley.

Yu F and Yin S (eds) (2000) *Photorefractive Optics: Materials, Properties, and Applications*. San Diego: Academic Press.

Ultrafast and Intense-Field Nonlinear Optics

A L Gaeta, Cornell University, Ithaca, NY, USA

R W Boyd, University of Rochester, Rochester, NY, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The tremendous development of high-powered femtosecond laser systems since the 1980s, has opened up new areas of research in nonlinear optics, plasma physics, atomic and molecular dynamics, and intense-field physics. For many of these applications, it is important to understand how ultrashort light pulses propagate through a medium under conditions in one or more of the processes in which nonlinear optics play an important role.

The starting point for the modeling of light propagation under these conditions is Maxwell's wave equation for the electric field $E(\mathbf{r}, t)$ which is given in Gaussian units as

$$\nabla^2 E - \frac{\partial^2 E}{\partial t^2} = 4\pi \frac{\partial^2 P}{\partial t^2} \qquad [1]$$

where the $P(\mathbf{r}, t)$ is the polarization inside the medium. Typically, the polarization is separated into a term P_l that depends linearly on the field E and into a term P_{nl} that depends nonlinearly on the applied field. The Fourier transform of the linear polarization can be expressed as $\tilde{P}_l(\mathbf{r}, \omega) = \chi^{(1)}(\omega)\tilde{E}(\mathbf{r}, \omega)$, where $\tilde{E}(\mathbf{r}, \omega)$ is the Fourier transform of electric field $E(\mathbf{r}, t)$. For the laser–matter interactions that we consider here, we assume that the linear susceptibility $\chi^{(1)}(\omega)$ is real, in which case the wave equation can be expressed as

$$\nabla^2 \tilde{E} + \left[\frac{n_l(\omega)\omega}{c}\right]^2 \tilde{E} = -\frac{4\pi\omega^2}{c^2}\tilde{P}_{\mathrm{nl}} \qquad [2]$$

where $n_l(\omega) = \sqrt{1 + 4\pi\chi^{(1)}(\omega)}$ is the frequency-dependent linear refractive index of the medium.

For light pulses that are longer than an optical period, the envelope description is valid and the electric field can be described by an amplitude envelope $A(\mathbf{r}, t)$ and a carrier frequency ω_0 such that

$$E(\mathbf{r}, t) = A(\mathbf{r}, t)\mathrm{e}^{\mathrm{i}(k_0 z - \omega_0 t)} + c.c \qquad [3]$$

where $k_0 = k(\omega_0) = n_0\omega_0/c$ is the wavevector amplitude and $n_0 = n_l(\omega_0)$. This envelope description is advantageous for performing analytical and numerical studies of pulse propagation. However, for sufficiently short laser pulses, where the shape of the envelope function does not depend on the carrier phase of the carrier wave, such a description is no longer applicable. Nevertheless the envelope description can be made valid for pulses that are nearly as short as a single cycle or, alternatively, that have spectral bandwidths that are comparable to the central frequency ω_0. To derive an equation for the spatio-temporal evolution of the pulse envelope, the relation for the electric field is substituted into the wave equation (eqn [2]) and the following two approximations are made: i) $k_0 \partial A/\partial z \ll \partial^2 A/\partial z^2$, which signifies that the envelope varies slowly in space over a distance compared to the central wavelength; ii) $v_{\rm ph} \sim v_{\rm gr}$ where $v_{\rm ph} = c/n_0$ is the phase velocity and $v_{\rm gr} = (\mathrm{d}k/\mathrm{d}\omega)^{-1}$ is the group velocity. This latter approximation is invariably well satisfied when the frequencies contained in the laser field are highly nonresonant with any transition frequencies of the medium.

For an input pulse at $z = 0$ with a peak amplitude A_0, and characteristic widths in space and time given by w_0 and τ_p, respectively, the equation for the normalized amplitude $u(r_\perp, z, t) = A(r_\perp, z, t)/A_0$ can be expressed as

$$\frac{\partial u}{\partial \xi} = \frac{i}{4}\left(1 + \frac{i}{\omega_0 \tau_p}\frac{\partial}{\partial \tau}\right)^{-1} \nabla_\perp^2 u - i \sum_{n=2} \frac{L_{\rm ds}}{n! L_{\rm ds}^{(n)}} \frac{\partial^n u}{\partial \tau^n} + i\left(1 + \frac{i}{\omega_0 \tau_p}\frac{\partial}{\partial \tau}\right) p^{\rm nl} \qquad [4]$$

where $\tau = (t - z/v_g)/\tau_p$ is the normalized retarded time for the pulse traveling at the group velocity v_g, $L_{\rm ds}^{(n)} = \tau_p^n/\beta_n$ is the nth-order dispersion length, $\beta_n (n \geq 2)$ is the nth-order dispersion constant, $L_{\rm ds} = |L_{\rm ds}^{(2)}|$ is the dispersion length, $\zeta = z/L_{\rm df}$ is the normalized distance, $L_{\rm df} = k w_0^2/2$ is the diffraction length, $p_{\rm nl}$ is the normalized nonlinear polarization, and $\nabla_\perp^2$ is the transverse Laplacian. The presence of the operator $(1 + i\partial/\omega_0 \partial \tau)$ in the diffraction term $(\nabla_\perp^2 u)$ of eqn [4] leads to space–time focusing, while its presence in the nonlinear term results in self-steepening and both these terms arise from not making the slowly varying envelope approximation in time (i.e., $k_0 \partial A/\partial t \ll \partial^2 A/\partial t^2$) in deriving eqn [4]. For a self-consistent analysis of pulse propagation in the nonlinear regime, both the effects of space–time focusing and self-steepening must be included.

Nonlinear Refractive Index

For an isotropic medium in the highly nonresonant limit, the third-order term is the lowest-order contribution to the nonlinear susceptibility. This term gives rise to the nonlinear refractive index, that is, the index of refraction depends on the local intensity of the laser field. For many materials there are two contributions to the nonlinear refractive index: i) an instantaneous part that arises from the electronic response of the medium; and ii) a noninstantaneous contribution due to the nuclear motion of the molecules (i.e, the Raman contribution). For such a medium, the nonlinear polarization may be expressed as

$$p_{\rm nl}(\zeta, \tau) = \frac{L_{\rm ds}}{L_{\rm nl}}\left[(1 - f)|u(\zeta, \tau)|^2 + f\gamma_R \int_{-\infty}^{\tau} \mathrm{d}\tau' R(\tau - \tau')|u(\zeta, \tau')|^2\right] u(\zeta, \tau) \qquad [5]$$

where $L_{\rm nl} = (c/\omega_0 n_2 I_0)$ is the nonlinear length, $I_0 = n_0 c|A_0|^2/2\pi$ is the peak input intensity, f is the fraction of the Raman contribution to the nonlinear refractive index, and $R(\tau) = \{[1 + (\Omega_R \tau_R)^2]/\Omega_R \tau_R\} \exp(-\tau/\tau_R)\sin(\Omega_R \tau)$ is the Raman response function, τ_R is the characteristic Raman response time, Ω_R is the characterstic Raman frequency, and $\gamma_R = \tau_p/\tau_R$. For example, for fused silica $f = 0.15$, $\tau_R = 50$ fs, and $\Omega_R \tau_R = 4.2$. For a noble gas such as Xe, there is no Raman contribution and $f = 0$.

Self Focusing, Supercontinuum Generation, and Filamentation

The presence of the nonlinear refractive index with $n_2 > 0$ can lead to self-focusing of a laser beam. For sufficiently long pulses such that dispersion, self-steepening, and space–time focusing effects can be neglected, it is found that laser beams with input powers greater than the critical power $P_{\rm cr} = \alpha\lambda^2/4\pi n_0 n_2$ will undergo catastrophic self-focusing collapse. The dimensionless parameter $\alpha \geq 1.86$ depends on the spatial profile of the input beam and for a Gaussian input beam is given by $\alpha = 1.9$, in which case the ratio of the input power P to the critical power satisfies the relation $P/P_{\rm cr} = 1.055 L_{\rm df}/L_{\rm nl}$. Extensive studies have been made on the dynamics of laser beams undergoing self-focusing. For example, it has been shown that the shape of the collapsing beam evolves to a radially symmetric profile as it approaches the collapse point and that the total power contained in the collapsing portion always corresponds to the minimum value (i.e., $\alpha \sim 1.86$) regardless of the initial power in the beam.

For light pulses shorter than a picosecond, the role of material dispersion plays an important role and completely alters the dynamics of the self-focusing process. These dispersive effects lead to a temporal splitting of the pulse into two pulses and the arrest of its collapse. At even higher powers, other phenomena can occur, such as 'optical shock' formation at the rear edge of the pulse, due to self-steepening and space–time focusing. Shock formation leads to the emission of a broad spectrum of radiation extending from the ultraviolet to the mid-infrared, known as supercontinuum generation (SCG). This phenomenon was first observed in 1970, and since then it has been observed in many different solids, liquids, and gases, under a wide variety of experimental conditions.

If the peak intensity of the pulse approaches intensities of $> 10^{13}$ W/cm^2, either through self-focusing or external focusing, multiphoton ionization occurs and a plasma is formed in the medium. (See section below on Plasma Nonlinearities and Relativistic Effects.) The generation of the plasma lowers the refractive index and effectively counteracts the self-focusing process, resulting in the spatial confinement of the pulse for distances far beyond what would be allowed by ordinary linear diffraction and has been observed in gases, liquids, and solids. A striking example of this apparent self-waveguiding is the observation of 'light strings' in air which can extend more than 10 km into the atmosphere. This phenomenon was first observed with 100 fs laser pulses in the near infrared ($\lambda = 800$ nm). Researchers found that pulses with energies greater than 10 mJ undergo self-focusing collapse in air and produce a highly intense ($> 10^{13}$ W/cm^2) 100-micron-diameter light filament tens of meters long.

Multiphoton Absorption

Multiphoton absorption is a process in which an atom or molecule makes a transition from a ground state to an excited state by means of the simultaneous absorption of N photons. In the lowest order of perturbation theory, such a process can be described by means of a susceptibility of order $(2N - 1)$, that is, by $\chi^{(2N-1)}$. Alternatively, this process can be described in terms of an N-photon cross-section $\sigma^{(N)}$ defined such that the transition rate per atom is given by

$$R^{(N)} = \sigma^{(N)} I^N \qquad [6]$$

where I is the intensity of the laser field. Quantum mechanical expressions for the N-photon cross-sections are readily obtained. One finds, for instance, that

$$R^{(2)}_{\text{ng}} = \left| \sum_m \frac{\mu_{\text{nm}}\mu_{\text{mg}}E^2}{\hbar^2(\omega_{\text{mg}} - \omega)} \right|^2 2\pi\rho_{\text{f}}(\omega_{\text{ng}} - 2\omega)$$

$$R^{(3)}_{\text{og}} = \left| \sum_{mn} \frac{\mu_{\text{on}}\mu_{\text{nm}}\mu_{\text{mg}}E^3}{\hbar^3(\omega_{\text{ng}} - 2\omega)(\omega_{\text{mg}} - \omega)} \right|^2 2\pi\rho_{\text{f}}(\omega_{\text{og}} - 3\omega) \qquad [7]$$

In each of these expressions, the quantity ρ_{f} represents the density of final states, or equivalently the atomic lineshape function, evaluated at the N-photon transition frequency.

Optical Damage

High-intensity laser fields can produce unwanted damage to optical materials. As a point of reference, the threshold for laser damage to fused silica at a wavelength of 1.05 micrometers for a pulse of 30 ps duration corresponds to an intensity of 230 GW/cm^2 or a fluence of 7 J/cm^2. Over a wide range of pulselengths (approximately 1 ps to 1 μs), the threshold intensity for laser damage decreases with pulse length T as $T^{-1/2}$ and correspondingly the threshold fluence for laser damage increases with pulse length $T^{1/2}$. In this range of pulse durations, the dominant mechanism of laser damage is avalanche breakdown. In this process, free electrons are accelerated by the laser field until they acquire sufficient energy to impact-ionize other atoms in the sample. These additional electrons are similarly accelerated and create still more free electrons. The combined action of the breaking of chemical bonds and the deposition of heat energy leads to the fracturing of the optical material. For pulses shorter than 1 ps, processes such as multiphoton absorption and multiphoton dissociation contribute to the mechanism of optical damage. For laser pulses longer than approximately 1 μs (including continuous wave laser beams), the dominant damage mechanism is direct heating of the optical material by linear absorption.

High-Harmonic Generation

Let us consider how nonlinear optical effects are modified when excited by a super-intense pulse. Nonlinear optical effects are traditionally modeled using a power-series expansion, such as

$$P = \chi^{(1)}E + \chi^{(2)}E^2 + \chi^{(3)}E^3 + \cdots \qquad [8]$$

but this series is not expected to converge if the laser field strength E exceeds the atomic unit of field strength $E_{\text{at}} = e/a_0^2 = 2 \times 10^7$ statvolt/cm $= 6 \times 10^9$ V/cm. This field strength corresponds to a laser intensity of $I_{\text{at}} = 4 \times 10^{16}$ W/cm^2, which constitutes the threshold intensity for exciting nonperturbative nonlinear optical response.

One of the consequences of excitation with intensities comparable to the atomic unit of intensity I_{at}, is the occurrence of high-harmonic generation. In a typical experimental arrangement, a gas jet is irradiated by high-intensity laser radiation, and all odd harmonics of the fundamental laser frequency, up to some maximum value N_{max}, are observed. The various harmonics below N_{max} are typically emitted with approximately equal intensity; such an observation is incompatible with a perturbative explanation of this phenomenon. Recent work has demonstrated harmonic generation with $N_{\max}$ as large as 341.

The phenomenon of high-harmonic generation can be understood in terms of a simple physical model. One imagines an atomic electron that has received kinetic energy from the laser field and is excited to a highly elliptical orbit. The positively charged atomic nucleus is at one focus of this ellipse, and each time the electron passes near the nucleus it undergoes strong acceleration and emits a short pulse of radiation. This radiation will occur in the form of a train of short pulses; the spectrum of the radiation will be the square of the Fourier transform of this pulse train, which will contain the odd harmonics of the oscillation frequency up to some maximum frequency, that is approximately the inverse of the time the electron spends near the atomic core. This argument can be made quantitative to show that the maximum harmonic number is given by

$$N_{\max}\hbar\omega = 3.17K + U_p \qquad [9]$$

where $K = e^2E^2/m\omega^2$ is the 'ponderomotive energy' (the kinetic energy of an electron in a laser field) and U_p is the ionization energy of the atom.

Plasma Nonlinearities and Relativistic Effects

The process of multiphoton ionization can liberate a sufficient number of free electrons to transform the optical medium into a plasma, that is, a fully or partially ionized gas. The process of plasma formation is described by the equation

$$\frac{dN_e}{dt} = \frac{dN_i}{dt} = (N_T - N_i)\sigma^{(N)}I^N - rN_eN_i \qquad [10]$$

where N_e is the number density of electons, N_i is the number density of ions, N_T is the total number of atoms (both ionized and un-ionized) in the material, and r is the electron–ion recombination coefficient. The optical properties of plasmas are very different from those of typical dielectric materials; the plasma contribution to the dielectric constant is given by

$$\epsilon(\omega) = 1 - \frac{\omega_p^2}{\omega^2} \qquad [11]$$

where $\omega_p = \sqrt{4\pi Ne^2/m}$ is known as the plasma frequency.

Nonlinear effects can occur in the propagation of light through a plasma. One example is the nonlinear response resulting from the relativistic change in mass of the electron due to the large velocity that it can attain in the field of an intense laser beam. Detailed consideration of this effect shows that the nonlinear change in refractive index can be described as $\Delta n = n_2 I$ where

$$n_2 = \frac{2\pi\omega_p^2 e^2}{n_0^2 m^2 c^3 \omega^4} = \frac{1}{2\pi n_0^2}\left(\frac{\omega_p}{\omega}\right)^2 1.1\times 10^{-26}\,\frac{\text{cm}^2}{\text{W}} \qquad [12]$$

Nonlinear Quantum Electrodynamics

One can imagine an electric field so intense that it could lead to the spontaneous creation of electron–positron pairs. Such a field would have a strength of the order of $E_{\text{QED}} = mc^2/e\lambdabar_c$ where $\lambdabar_c = \hbar/mc$ is the reduced Compton wavelength of the electron. The intensity of a light beam with a peak field amplitude of E_{QED} is $I_{\text{QED}} = 4\times 10^{29}$ W/cm^2. Detailed consideration shows that even for fields weaker than I_{QED} there will be a field-induced change in the dielectric tensor given by

$$\epsilon_{ik} = \delta_{ik} + \frac{e^4\hbar}{45\pi m^4 c^7}\left[2(E^2 - B^2)\delta_{ik} + 7B_iB_k\right] \qquad [13]$$

Because of the unusual tensor properties of this relation, it displays a different polarization dependence than typical optical nonlinearities. Nonetheless, to an order of magnitude one can describe the strength of this response as

$$n_2 = \frac{7}{15c}\frac{e^2}{\hbar c}\frac{1}{E_{\text{QED}}^2} = 5.6\times 10^{-34}\ \text{cm}^2/\text{W} \qquad [14]$$

See also

Fiber and Guided Wave Optics: Nonlinear Optics. **Quantum Electrodynamics:** Quantum Theory of the Electromagnetic Field.

Further Reading

Agostini P, Fabre F, Mainfray G, Petite G and Rahman NK (1979) Free-free transitions following six photon ionization of xenon. *Physics Review Letters* 42: 1127.

Alfano RR (ed.) (1989) *The Supercontinuum Laser Source*. New York: Springer-Verlag.

Bloembergen N (1997) A brief history of light breakdown. *Journal of Nonlinear Optical Physics and Materials* 6: 377.

Boyd RW (2003) *Nonlinear Optics, Second Edition*, Section 12.5. Amsterdam: Academic Press.

Braun A, Korn G, Liu X, Du D, Squier J and Mourou G (1995) Self-channeling of high-peak-power femtosecond laser pulses in air. *Optical Letters* 20: 73.

Brabec T and Krausz F (2000) Intense few-cycle laser fields: Frontiers of nonlinear optics. *Reviews of Modern Physics* 72: 545.

Chang Z, Rundquist A, Wang H, Murnane MM and Kapteyn HC (1997) Generation of coherent soft X-rays at 2.7 nm using high harmonics. *Physics Review Letters* 79: 2967.

Corkum PB (1993) Plasma perspective on strong field multiphoton ionization. *Physics Review Letters* 71: 1994.

Corkum PB, Rolland C and Srinivasanrao T (1986) Supercontinum generation in gases. *Physics Review Letters* 57: 2268.

Gaeta AL (2003) Collapsing light really shines. *Science* 301: 54.

Kasparian J, Rodriguez M, Mejean G, Yu J, Salmon E, Wille H, Bourayou R, Frey S, Andŕe Y-B, Mysyrowicz A, Sauerbrey R, Wolf J-P and Woste L (2003) White light filaments for atmospheric analysis. *Science* 301: 61.

Lewenstein M, Balcou Ph, Ivanov M Yu, L'Huillier A and Corkum PB (1994) Theory of high-harmonic generation by low-frequency laser fields. *Physics Review A* 49: 2117.

Max CE, Arons J and Langdon AB (1974) Self-modulation and self-focusing of electromagnetic waves in plasmas. *Physics Review Letters* 33: 209.

Moll KD, Fibich G and Gaeta AL (2003) Self-similar wave collapse: observation of the Townes profile. *Physics Review Letters* 90: 203902.

Monot P, Auguste T, Gibbon P, Jakober F, Mainfray G, Dulieu A, Louis-Jacquet M, Malka G and Miquel JL (1995) Experimental demonstration of relativistic self-channeling of a multiterawatt laser pulse in an under-dense plasma. *Physics Review Letters* 74: 2953.

Rairoux P, Schillinger H, Niedermeier S, *et al.* (2000) *Applied Physics B—Lasers Optics* 71: 573.

Ranka JK, Schirmer RW and Gaeta AL (1996) Observation of pulse splitting in nonlinear dispersive media. *Physics Review Letters* 77: 3783.

Rothenberg JE (1992) Pulse splitting during self-focusing in normally dispersive media. *Optical Letters* 17: 583.

Sprangle P, Tang C-M and Esarey E (1987) Relativistic self-focusing of short-pulse radiation beams in plasmas. *IEEE Transactions on Plasma Science* 15: 145.

Stuart BC, Feit D, Rubenchik AM, Shore BW and Perry MD (1995) Laser-induced damage in dielectrics with nano-second to subpicosecond pulses. *Physics Review Letters* 74: 2248.

Wagner R, Chen S-Y, Maksemchak A and Umstadter D (1997) Electron acceleration by a laser wakefield in a relativistically self guided channel. *Physics Review Letters* 78: 3125.

Wood RM (1986) *Laser Damage in Optical Materials*. Bristol, UK: Adam Hilger.

NONLINEAR SOURCES

Harmonic Generation in Gases

P Villoresi, University of Padova and INFM, Padova, Italy

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The generation of laser harmonics in gases provides high-brightness ultraviolet and soft X-ray radiation induced by an intense laser pulse. This phenomenon was discovered experimentally in the late 1980s, in a simple setup as that sketched in Figure 1. The laser pulse is focused in the interaction medium, which may be a gas jet formed by a pulsed electromagnetic valve, a capillary, or a small chamber filled with the gas. The beam leaving the interaction region includes a part of the laser pulse and a number of odd harmonics.

The harmonic orders generated in this way may reach and exceed an order of 300, so that this mechanism, often referred as high-order harmonics (HHs) generation (HHG), directly up-converts low frequency radiation, usually in the near-infrared spectrum, to extreme-ultraviolet (XUV) or soft X-rays. An example of a HH spectrum is shown in Figure 2, where several tens of discrete harmonic peaks are present. The striking difference with ordinary nonlinear processes is the flatness of the photon yield versus nonlinear order, up to a sharp cut-off point.

The HHG is based on the sequence of three processes: the electric field of an intense laser pulse ionizes atoms placed near the laser focus; the liberated electrons are driven by the laser electric field in a trajectory which returns on the parent ion; and the electron recombines releasing a photon whose energy is the ionization potential plus the electron's kinetic energy. The process is periodic in time, with the period of the laser pulse, and the emitted spectrum is then expressed by discrete components, multiples of the laser frequency. The emission is in the form of a traveling wave in the direction of the laser beam and so only odd harmonics are present.



Figure 1 Scheme of the interaction between a focused laser pulse and a gas jet. *z* axis originates at laser focus.



Figure 2 HHs experimental spectrum, obtained from helium gas, and a Ti:sapphire laser pulse at 790 nm, with 25 fs duration and 6×10^{14} W/cm^2 intensity.

The individual processes in HHG have highlighted the coherent response of electrons in the laser field, that show up interferences between quantum trajectories, as well as a nonlinear phase-matching issue – which have provided a simple method to investigate the interaction of single particles with the electromagnetic field, where plasma effects and bonds may be of minor influence.

Background

The interest to produce laser harmonics using gases instead of crystals was expressed by many. For the gas medium; the mass-density is three order of magnitude lower than for solids and the nonlinear susceptibility can be strongly enhanced for suitable resonance frequencies. Moreover, the phase-matching of the phase velocities may be achieved by tuning the gas pressure or by mixing diverse gases, so realizing a highly homogenous conversion region, free from walk-off and with an extension much longer than for crystals. In addition, gases have a high threshold for the intensity-induced damage, which is also non-permanent.

This research was made possible with the introduction of chirped-pulse laser amplifiers in the early 1980s, when picosecond lasers pulses reached intensities capable of directly ionizing solids and matter with their own electric field. This effect, known as optical ionization, was further enhanced when the laser pulses were reduced to subpicosecond duration, up to a few femtoseconds (10^{-15} s), close to their natural limit, which is the optical cycle. The experimental observation of HHs and of the ejection of electrons with unexpected high energy, the above threshold ionization (ATI), dramatically changed the scenario of laser matter interaction and has indicated a new regime in the coupling of laser radiation with the matter. The ordinary nonlinear optics, using the perturbative approach, was not capable of interpreting the findings and so the request was made for new models for the description of the interaction, which has been now named nonperturbative.

Typical Experimental Parameters

In the experimental investigation of the HHG, many laser wavelengths and pulse durations were used, including radiation from excimer, visible, Ti:sapphire, Nd:YAG (first and second harmonics) and CO_2 lasers, and pulses of duration from hundreds of picoseconds to a few femtoseconds. Among these, the more effective strategy in the generation of high harmonic order with high conversion efficiency, has been that of near infrared pulses with shortest duration. In order to induce optical single-ionization, the required laser intensity needs to span in the 10^{14} W/cm^2 range. Different elements are a possible choice for the gas in the interaction medium, though noble gases are used for the generation of the highest orders, since these have the higher ionization potential. Due to the very short duration of the laser pulse, the gas temperature is not relevant, while a pressure range of 10–500 mbar is usually chosen to balance, on one side, the needs of a large number of atoms that take part in the HHG and on the other side, the limit posed by the attenuation of the XUV and soft X-ray radiation after the generation, caused by the gas absorption. For the same reason, a powerful pumping system is needed, in order to reduce the ambient pressure in the apparatus below 10^{-5} mbar level.

The Models for the High Harmonics Generation

The physical processes involved in HHG are many: in the emission of the HH photons, the laser field interacts with a single atom of gas and induces the ionization, the electron's motion and its recollision with its parent ion; besides, the beam of HHs is the result of the superposition of the radiation from all the ionized atoms, as in an ordinary nonlinear medium, where the phase velocity of the laser field and of HHs is a function of the position and of the laser intensity and phase; therefore, the phase-matching issue has to be addressed in order to understand the global yield of HHG. The more relevant causes for the mismatch are the geometrical phase shift at the beam focus, which for Gaussian-profile beams is the Gouy phase, the nonlinear phase from the atomic polarization, and the effects of the plasma induced by the laser pulse itself. In addition, other effects have to be considered, such as the nonuniform density distribution of the target gas or the fact that the propagation of XUV radiation through a gas is usually influenced by a strong absorption, which is frequency dependent.

The study of HHG is first approached by introducing what is known as the simple man model, in which simplifications are introduced in order to treat the problem in a simple classical scheme, but from which the essential characteristics are derived. We then introduce the more complex quantum model based on the path integrals.

First Step: Ionization

The first step in the HHG model is the process with which the laser electric field applies to an electron, belonging to an atom or a molecule, a force that causes its detachment. This takes place only if such a field is strong enough to liberate the electron from its atomic bond. This may happen when the laser, which is taken here as linearly polarized and periodic in time, has modified the potential well so that the electrons may tunnel through it or pass over it. In fact, the sum of the atomic potential with that associated to the laser, which can be thought of as a plane that swings between a positive and negative slope at the laser frequency, gives rise to a finite sized well, through which the electron escapes by tunneling, or eventually to an aperture from which the electron is drawn away from the nucleus. In Figure 3, is shown such a well and the tunnel path for the electron.



Figure 3 Electron potential when the laser pulse shines on the atom; |g⟩ indicated the level of the ground state; in red, a possible trajectory of the liberated electron after tunneling.

Once freed, the electron responds to the periodic force from the laser which makes it oscillate. The average kinetic energy on such oscillations is known as the ponderomotive potential U_p, and is related to the laser intensity and wavelength, according to the following: $U_p = e^2E_0^2/4m\omega_0^2$, which reads numerically as $U_p(\mathrm{eV}) = 9.3I_0(10^{14}\ \mathrm{W/cm^2})\lambda^2(\mu\mathrm{m})$, where λ is the laser wavelength, E_0 and I_0 the laser peak electric field and intensity.

Second Step: Free-electron Trajectory

On the freed electron are applied both the time-varying force due to the laser field and the ionic potential. Its motion can be approximated according to the simple man model as a nonrelativistic classical-mechanics trajectory; its initial velocity is set to zero, and its initial position is by the ion; finally, the laser exerts a force much stronger than that from the ion as well as from the laser magnetic field, thus these two latter forces are cancelled out.

As mentioned above, the electron trajectories that induce HHs are those where the electron returns by the ion with strong kinetic energy. If the laser is linearly polarized, the induced trajectory takes place along a line, at which also belongs to the parent ion. Moreover, the electron final velocity is related to the actual instant of ionization, or phase of the field, with respect to the laser peak. Therefore, electron final energies span from zero to a maximum value $K_{\mathrm{max.}}$ By considering the first semi-cycle, K_{max} occurs at about 17° of field phase angle, while for the second semi-cycle it is at 197°.

In Figure 4 the electron trajectories for different ionization in the first semi-cycle are shown: the electron displacement in the laser-field direction with



Figure 4 Electron trajectories relative to different ionization instant within the first semi-cycle; in dotted red, half-cycle, in continuous red, the whole optical cycle. Trajectories for later times do not return to the ion, do not contribute to HHG and correspond to ejected photoelectrons.

respect to the ion position, which is the initial as well as the final position, is represented versus time, where the time origin is at the laser peak, where field phase is equal to zero. The laser intensity directly influences the value of $K_{\max}$, according to the following expression: $K_{\max} = 3.17\, U_p$. In the case shown in the figure, the peak laser intensity is $I_0 = 8 \times 10^{14}$ W/cm^2 and the ponderomotive potential is $U_p = 45$ eV and $K_{\max} = 143$ eV.

Moreover, for a given final energy below $K_{\max}$, there are more than one value of the phase of the laser field where the trajectory results with the same final kinetic energy. This indicates that multiple trajectories may produce a given HH, and this is relevant in terms of the interference between them.

Third Step: Recombination

The final process which occurs in the HHG, is the recombination of the ionized electron with the parent ion. The energy conservation means that the kinetic energy and the ionization potential have to be delivered to the emitted photon. In the simple man model, the spectrum of HH then spans from I_p to the maximum values of $E_{\max} = I_p + 3.17\, K_{\max}$. In the case of Figure 2, obtained using helium gas at 6×10^{14} W/cm^2, the spectral position of cutoff can be estimated at about 9 nm, or 140 eV, which is in good agreement with the prediction of the relationship described above.

The electron recombination is not a unique process occurring at this point: the electron may be scattered by the ion and be emitted with a kinetic energy of up to 10 U_p, which is known as the rescattering plateau in ATI, or it may ionize the ion by collision, leaving a double ionized atom via sequential ionization, with a strong increase in the observed cross-section of this process.

Feynman Path-Integral Approach

The ideas in the simple man model have been expanded in order to include the quantum mechanical description of the laser-electron-ion interaction. By using the Feynman path-integral approach, the evolution of the electron driven by the laser force is associated to a probability which depends on the sum of an infinite number of amplitudes $\mathbf{f}_n$. These are complex numbers and correspond to different trajectories, or quantum orbits, $\mathbf{r}_n(t)$, followed by the electron. Their phase is proportional to the classical action of the electron motion, $S[\mathbf{r}_n(t)]$, calculated along $\mathbf{r}_n(t)$, which begins at time t_i and ends at a later time $t_f = t_i + \tau$. Here τ defines the duration of the liberated electron trajectory. In our case, the action is the sum of three terms:

$$S[\mathbf{r}_n(t)] = S_{\text{bound},n} + S_{\text{free},n} + S_{\text{final},n} \qquad [1]$$

that correspond respectively to the electron ionization:

$$S_{\text{bound},n} = -E_0 t_{i,n} \qquad [2]$$

where E_0 is the binding energy of electron in the atom ground state, $E_0 < 0$, to the free electron trajectory:

$$S_{\text{free},n} = \int_{t_i}^{t_f} [\mathbf{k} - e\mathbf{A}(t)^2]\mathrm{d}t \qquad [3]$$

where $\mathbf{k}$ is the electron momentum after ionization, directed parallel the laser electric field, and $\mathbf{A}(t)$ is the vector potential of the laser field, and to the final recombination with the parent ion:

$$S_{\text{final},n} = (\hbar\omega_q + E_0)t_{f,n} \qquad [4]$$

The condition that normally points out the trajectory made by the electron may be obtained from the principle of least action. Within the path integral approach, this principle can be used to deduce some equations which have to be obeyed by the quantum orbits, and that express the energy conservation in both the ionization and recombination process and the fulfilment of boundary conditions for electron trajectory. These are known as saddle-point equations, and reads as:

$$[\mathbf{k} - e\mathbf{A}(t_i)]^2 = 2mE_0 \qquad [5]$$

for the ionization process:

$$\mathbf{k}\tau = e\int_{t_i}^{t_f} \mathbf{A}(t)\mathrm{d}t \qquad [6]$$

which compares the initial momentum with that exchanged with the laser field during the trajectory, and

$$[\mathbf{k} - e\mathbf{A}(t_f)]^2 = 2m(\hbar\omega_q + E_0) \qquad [7]$$

for the recombination process which emits an harmonic of order q.

From eqn [5] we note that the solution for the ionization time t_i is a complex number, since the right hand side is negative. This suggests that the quantum orbits are complex as well. The reason for this is that the tunnel through the potential well is a nonclassical process.

The orbits solutions to eqns [5]–[7] have different durations, and for some of them τ is shorter than an optical cycle, while for the others the electron returns in a later cycle than the one where it was ionized. This latter solution is of minor influence, since the electron wavefunction spreads out along the trajectory, decreasing the recombination probability. Those within the initial optical cycle sum the amplitudes to give the probability of the generation of q-th harmonic, and their interference is evident from the irregular single-atom spectrum.

The time evolution of the laser pulse as well as the interaction geometry are experimental tools that influence the relevance of the different trajectories. In particular conditions it is possible to set the condition for HHG from a single trajectory, with a very simple phase structure and clear spectrum; some cases are described below.

HHs Generated by Few-Optical-Cycle Pulses

The laser electric field considered so far has been taken as stationary, relying on the hypothesis that the pulse envelope has a duration much longer than the laser optical cycle. For the analysis of the electron trajectories, that last a fraction of the laser optical cycle, this hypothesis is valid for pulses down to about 20 fs. For shorter pulses, as those generated with the hollow fiber technique, there is a noticeable variation of the electric field between a cycle and the next. The generation process is now aperiodic, and the characteristics of HH spectrum and conversion is strongly influenced by the pulse actual duration.

In order to show the striking changes in this regime, Figure 5 shows the laser electric field, the envelope and the ionization probability of helium gas in the case of a pulse of 5 fs of full width at half-maximum (FWHM) duration and a laser intensity of 9×10^{14} W/cm^2. The atom can be ionized during only three intervals, of sub-fs duration but where only one is dominant.



Figure 5 Ionization rate for helium gas shined by a 5 fs FWHM pulse of intensity 9×10^{14} W/cm^2. The dotted line shows the normalized evolution of electric field of the pulse. Only the three central half-cycles induce ionization.

The HHG experiment in this temporal regime have revealed that the influence of the plasma in the interaction region is progressively reduced and eventually vanishes for pulses of duration of about 5 fs. This is because the atoms are exposed directly to the maximum electric field, and so there is no pre-ionization of the gas caused by the initial part of the pulse. This effect, which is present in the case of many-cycle pulses, causes a reduction in the HHG efficiency, due to a depletion of the neutral density available at the time of maximum electric field, where the higher HHs are produced with a large dispersion, which deteriorates the phase-matching.

Moreover, the effect of the carrier-envelope-phase in the HHs spectrum has been demonstrated as an evident spectral shift of the cut-off harmonics generated with few-cycle pulses. The reason can be found in the variation of the phase of the emission from each electron after its trajectory. For the few-cycle pulses, this phase changes for every laser semicycle, due to the change in the actual electric field which drives the electron motion.

This portion of the spectrum is also relevant to its phase structure, since here the HHs are generated by a single electron trajectory. This condition sets a constant phase difference between the subsequent harmonic orders. In this way, similarly to the mode locking laser, this effect allows the synthesis of a pulse, from the combination of several harmonic orders, which has a duration much lower than the individual harmonics. This process has been exploited to produce a soft X-ray pulse of duration of 650 as (1 as, attosecond = 1×10^{-18} s).

HHs Beam Characteristics

The HHG is a coherent process, in that the emitted radiation has a direct relationship with the laser pump. The emitted HH beam also reflects this fact in its good directional characteristics and in its spatial and temporal coherence, as different experiments have demonstrated.

Using a 110 fs laser pulse, the interference fringes produced in the far field of two spatially separated HH beams were measured as a function of the mutual delay. The HH coherence time t_c resulted in agreement with the expected duration of the HHs, which is a fraction of that of the laser pulse. Moreover, it has been observed at a different t_c in the central and external regions of the far field of harmonic 23rd, 50 fs and 20 fs respectively. This is because different phase-matching in the HHG contribute to the on-axis and off-axis part of the HHs beam, where the more prominent quantum orbit is also different.

The measurement of the beam divergence for different harmonic orders is relevant for both the estimate of the beam brightness and the irradiance available in the case of the HH applications. Moreover, it is useful for the understanding of the phase-matching which is realized in actual interaction geometry. The experimental measurements requires an astigmatic spectrometer, as is described later. In this kind of experiment, the focalplane images of the HH spectrum are taken for different generation conditions, usually moving the gas-jet position with respect to the laser focus, the z coordinate in Figure 1. The harmonic peaks appear as elongated spots, as shown in Figure 6 for helium gas and an intensity of 4×10^{14} W/cm^2 and duration of 20 fs, whose length in a transverse direction to the dispersion plane can be related, by a optical calculation, to the beam divergence.

A comparison between divergences for HHG driven by few- or many-optical-cycle pulses has revealed another aspect of the phase-matching condition. In this case, the laser pulse was compressed in time by means of the hollow fiber technique, and so the resulting phase front is of the Bessel-beam type, truncated at the first zero. The experiment indicates a divergence for plateau harmonics of about 3 mrad FWHM of the beam, in the case of the 7 fs pulse and larger values by more than 50% using the 20 fs pulse. In both cases, the beam divergence increase moving downstream the gas jet and with increasing harmonic order. The reduced divergence can be ascribed to a more regular wavefront of the harmonic beam, which can be related to the simpler phase structure of the few-cycle case.



Figure 6 Focal plane image obtained from the spectrograph shown in Figure 9, relative to the HHs spectrum of helium with 20 fs and 4×10^{14} W/cm^2. The bar in upper-left corner indicates the scale-length of vertical axis corresponding to a divergence of the HH beam of 1 mrad.



Figure 7 Peak brightness of the HHs beam determined from absolute-intensity and divergence measurements, using neon gas and a 790 nm laser pulse with 7 fs duration and 9×10^{14} W/cm^2 intensity.

By using an intensity-calibrated detector, the number of photons per harmonic order per laser shot can be measured. Combining this measure with that of the divergence, the HH beam brightness can be calculated. The source size and the HH pulse duration can be easily modeled from the experimental parameters. The result for the case of neon with 7 fs pump-pulse with intensity of 9×10^{14} W/cm^2 is shown in Figure 7, as a function of the gas-jet position, with positive values when the jet is downstream with respect to laser focus.

The large divergence reduces the brightness of downstream positions. Maximum values of about 8×10^{13} W/srad cm^2 are found close to the focus, relatively flat with respect to harmonic order.

The conversion efficiency η_{HH} from the fundamental intensity to that of the HHs can also be derived from this kind of measurement. The more convenient parameters for HHG in the range 41–71 were found using neon gas jet from a pulsed valve and a pulse duration of 7 fs, which leads to η_{HH} in the scale of 10^{-7}, while for lower orders, from 17 to 31, a value about two orders of magnitude larger has been obtained using a short hollow fiber filled with argon gas. A remarkable intracycle optimization mechanism was introduced in this case, in order to maximize the given harmonic order of chosen. This was done by tailoring the shape of the pump pulse in spectrum and time, using an adaptive component in the laser compressor. In this case, the optimal pulse shape to maximize the efficiency in the driving of the electron on a trajectory producing the required harmonic order, is sought by means of a genetic algorithm.

A strong efficiency enhancement has also been demonstrated by manipulating the laser wavefront by means of a deformable mirror (DM). In this case, the DM was controlled by a genetic algorithm, aiming to increase the HHs intensity in a given spectral interval. The purpose of this technique is the correction of the optical aberrations on the beam, introduced by both the optical components in the beam focusing line and the phase distortion caused by nonlinear effects leading to an optimum laser front. The effect is shown in Figure 8, where the spectrum obtained with the original beam is compared with that optimized by the genetic algorithm. It can be noticed there is both a remarkable extension of the HHs spectrum, of about 20 orders, as well as a strong enhancement of the plateau intensity.



Figure 8 Comparison of the HHs spectrum obtained with and without the wavefront correction using a deformable mirror. Neon gas was used and a 790 nm laser pulse with 6 fs duration and 0.3 mJ energy.

Spectrometers and Monochromators for HHs

The extended spectrum of HHs reaches the optical domains of the extreme-ultraviolet (XUV, 10–100 nm) and soft X-ray (1–10 nm). In these regions, the optical materials have very poor or zero transmission, and so the optical design of instruments for HHs analysis uses reflective optics only. Exceptions sometimes used are the frequency-selective XUV transmission filters, whose thickness does not exceed a few tenths of a micrometer, and the diffracting zone-plates. Moreover, for the radiation of wavelength shorter than 30 nm, even the reflectivity of optics becomes poor, and this forces the use of grazing-incidence mountings or the narrow band XUV and soft X-ray multilayer mirrors.

On the other hand, HHs as optical sources have favorable characteristics, in that they are emitted in a region smaller than the laser waist focus, so usually of a few tens of micrometers, and their divergence is small, as seen above. In addition, the very short duration of the pump pulses broadens the HHs spectrum, due to time-bandwidth inequality, usually smearing details below 0.1 nm of width.

The spectrograph is then realized with the least number of components, usually combining in one or two optics of the spectral dispersion, the gathering of the HH beam and its focusing on the detector. Moreover, it is not feasible to collect with a single detector all the broad HH spectrum in once, so usually a spectral interval of interest is selected and acquired with a linear or bidimensional detector, or scanned sequentially by rotating the grating.

An example of spectrograph with 2D-detector, is shown in Figure 9, the layout of the instrument developed for the simultaneous measure of the divergence and the intensity of HHs generated from few-optical-cycle pulses.



Figure 9 Optical layout of the astigmatic spectrometer for the divergence measurement.

The upper part of Figure 9 shows the optics in the dispersion plane, where the toroidal mirror gathers the HH radiation and relays it to the source point for the spherical grating. The latter has a varied line spacing (VLS) of the grooves, in order to image an erected spectrum in the focalplane. This feature is convenient in order to use a bidimensional detector. In the sagittal plane, the grating has negligible effect, and the toroidal mirror is designed to realize an astigmatic image of the source in the focalplane, from which the divergences can be extracted. The detector needs to be blind at the radiation of the laser and at the lower harmonics, and to have an extended linear response in the XUV and soft X-ray. A good solution can be obtained with an open micro-channel plate (MCP), with a suitable photocathode such as MgF_2, placed in the focalplane, coupled with a high-resolution and a high dynamic CCD camera.

For the selection of a single harmonic order or of a narrow spectral region, an XUV monochromator is used. This device is based on the spectral dispersion of the HHs beam by using a diffraction grating. The desired harmonic order is selected by scanning the wavelength which falls on the slit, usually by rotating the grating. This technique uses a single optical component, a concave grating, to reduce the reflection losses. On the other hand, the single-grating monochromator introduces a remarkable time broadening in the selected radiation. In fact, the grating diffraction is based on the optical path length difference for the rays diffracted by subsequent grating grooves. Therefore the selected beam, of wavelength λ, is composed of rays whose difference in length is $\Delta L = N_g m\lambda$, where m is the diffraction order and N_g is the number of illuminated grooves, given by the beam diameter on grating multiplied by the groove density. The time broadening of the selected pulse is then $\Delta\tau = \Delta L/c$. For a HH XUV pulse, the diffracted pulse results is 7 ps of duration, if beam size is of 3 mm and it is diffracted at 87° by a 1200 gr/mm grating.

The solution to this problem may be found in adopting a twin grating design. In this case, the dispersion induced by the first grating is used to select the desired spectral portion of the HH spectrum, and will be cancelled by the second grating. This latter grating has to be mounted in order to compensate for the different optical path length of different rays within the aperture of the HH beam. The layout of this optical scheme is reported in Figure 10. The ray tracing of this compensated monochromator indicates that for both the grazing incidence and the normal incidence regions, the residual broadening results is of the order of one femtosecond.



Figure 10 Scheme of the compensated XUV monochromator, for the selection of a spectral portion of the HHs spectrum without introducing temporal broadening. See also Villoresi P (1999) Compensation of optical path lengths in extreme-ultraviolet and soft X-ray monochromators for ultrafast pulses. *Applied Optics* 38: 6040.

HHs at Work: Applications and Perspectives

The advantages of HHs with respect to other XUV and soft X-ray sources, as laser-plasma, synchrotron radiation or X-ray lasers, are mainly the very short duration of their emission, their high brightness, and the source compactness and their intrinsic synchronization with a laser pulse. These aspects have been already exploited in a few experiments, based either on the detection of a photoelectron emitted in the time-dependent interaction of the matter with the HHs plus fundamental laser beams, or the observation of changes in the HHs XUV spectrum.

As examples of direct application, the interferometry of a laser-plasma has been obtained with HHs, to determine spatial distribution of the electron density. In this case, two beams of harmonic radiation were generated by splitting in equal parts the laser pulse, with one of them passing through a laser-generated plasma from a solid aluminum target. By means of a grating monochromator, a single harmonic order is selected, of both beams, and their interference pattern in the far field is acquired. From the shift in the fringes pattern, the map of the plasma electron density was estimated. Here, the broad spectrum of the HHs was exploited to operate the interference at the most convenient wavelength, far from atomic resonances and with fair fringe contrast.

The direct monitoring of a chemical reaction at the surface was achieved by pumping, with a part of the laser pulse, a platinum surface with some adsorbed molecular oxygen. By observing changes in the spectrum of the photoelectrons generated by the delayed HHs beam, the oxygen-platinum bond switch from a superoxo (O_2^-) to a peroxo (O_2^{2-}) state was observed in the time domain.

The electron bond in an atom may be dressed by a laser field, and the changes induced in its orbital are diagnosed by a HHs beam, which photo-ionizes the atom. This phenomenon have been exploited as a diagnostic of the temporal structure of a HHs beam: the sidebands in the photoelectron spectrum have been related to the phase of different harmonics. The findings indicate that HHs are locked in phase and their superposition produces a train of 250 as pulses.

By using the mixing scheme of some suitable orders of a HHs beam generated with few-optical-cycle pulses, mentioned already in section 'HHs beam characteristics,' a pulse with sub-femtosecond duration may be generated. This was used in the detailed analysis of the photoelectron spectrum in a pump-probe experiment, with time resolution of 150 as. Again using the IR and HHs radiation together, this technique has accessed the direct probe of the laser field oscillation, as demonstration by the use of HHs in the new domain of attosecond spectroscopy and metrology.

Finally, the HH radiation can also be considered as the seed for an amplifier of radiation in the soft X-ray region, as in the case of a free electron laser.

See also

Coherent Transients: Ultrafast Studies of Semiconductors. **Instrumentation:** Spectrometers. **Ultrafast Laser Techniques:** Generation of Femtosecond Pulses.

Further Reading

Bartels R, Backus S, Zeek E, *et al.* (2000) Shaped-pulse optimization of coherent emission of high-harmonic soft x-ray. *Nature (London)* 406: 164.

Bauer M, Lei C, Read K, *et al.* (2001) Direct observation of surface chemistry using ultrafast soft-X-ray pulses. *Physics Review Letters* 87: 025501.

Brabec T and Krausz F (2000) Intense few-cycle laser fields: frontiers of nonlinear optics. *Review Modern Physics* 72: 545.

Corkum PB (1993) Plasma perspective on strong-field multiphoton ionization. *Physics Review Letters* 71: 1994.

Descamps D, Lynga L, Norin J, *et al.* (2000) Extreme ultraviolet interferometry measurements with high-order harmonics. *Optic Letters* 25: 135.

Hentschel M, Kienberger R, Spielmann CH, *et al.* (2001) Attosecond metrology. *Nature (London)* 414: 509.

Kulander KC, Schafer KJ and Krause JL (1993) Dynamics of short-pulse excitation, ionization and harmonic conversion. In: Piraux B, L'Huillier A and Rzazewski K (eds) *Super-Intense Laser-Atom Physics*, pp. 95–110. New York: Plenum.

Lewenstein M, Balcou Ph, Ivanov M, *et al.* (1994) Theory of high-harmonic generation by low-frequency laser fields. *Physics Review A* 49: 2117.

L'Huillier A and Balcou P (1993) High-order harmonic generation in rare gases with a 1-ps 1053-nm laser. *Physics Review Letters* 70: 774.

McPherson A, Gibson G, Jara H, *et al.* (1987) Studies of multiphoton production of vacuum-ultraviolet radiation in the rare gasses. *Journal of the Optical Society of America B* 4: 595–601.

Nisoli M, Priori E, Sansone G, *et al.* (2002) High-brightness high-order harmonic generation by truncated bessel beams in the sub-10-fs regime. *Physics Review Letters* 88: 033902.

Nisoli M, Sansone G, Stagira S, *et al.* (2003) Effects of carrier-envelope phase differences of few-optical-cycle light pulses in single-shot high-order-harmonic spectra. *Physics Review Letters* 91: 213905.

Paul PM, Toma ES, Breger P, *et al.* (2001) Observation of a train of attosecond pulses from high harmonic generation. *Science* 292: 1689.

Poletto L, Tondello G and Villoresi P (2001) High-order laser harmonics detection in the EUV and soft x-ray spectral regions. *Review Scientific Instruments* 72: 2868.

Salières P, L'Huillier P, Antoine A, *et al.* (1999) Study of spatial and temporal coherence of high order harmonics. In: Bederson B and Walther H (eds) *Advances in Atomic, Molecular, and Optical Physics*, vol. 41, pp. 83. New York: Academic Press.

Villoresi P, Ceccherini P, Poletto L and Tondello G (2000) Spectral features and modeling of high-order harmonics generated by sub-10-fs pulses. *Physics Review Letters* 85: 2494.

Villoresi P, Bonora S, Pascolini M, *et al.* (2004) Optimization of high-order harmonic generation by adaptive control of sub-10 fs pulse wavefront. *Optic Letters* 29: 207.

O

OPTICAL AMPLIFIERS

Contents

Basic Concepts
Erbium Doped Fiber Amplifiers for Lightwave Systems
Optical Amplifiers in Long-Haul Transmission Systems
Raman, Brillouin and Parametric Amplifiers
Semiconductor Optical Amplifiers

Basic Concepts

M F S Ferreira, University of Aveiro, Aveiro, Portugal

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The transmission distance of a fiber-optic communication system is limited by fiber loss and dispersion. For long-haul lightwave systems, the loss limitations have traditionally been overcome by periodic regeneration of the optical signals at repeaters applying conversion to an intermediate electric signal. Because of the complexity and high cost of such regenerators, the need for optical amplifiers became obvious in the mid-1980s. The optical amplifier is ideally a transparent box that provides gain and is also insensitive to the bit rate, modulation format, power and wavelength of the signal passing through it.

Several means of obtaining optical amplification has been suggested since the 1970s, including direct use of the transmission fiber as gain medium through nonlinear effects, semiconductor amplifiers, or doping optical waveguides with an active material (rare-earth ions), that could provide gain. Due to the spectacular results on erbium-doped fiber amplifiers, which are particularly suitable in the third transmission window (around 1.5 μm), an intense worldwide research activity on optical amplifiers has developed. As a consequence, the development of erbium-doped fiber amplifiers has reached an industrial level, and commercial devices are now available.

Semiconductor amplifiers, on the other hand, have the same technical basis as semiconductor lasers. Although the strong nonlinearity of semiconductor amplifiers degrades the performances of transmission systems, the state-of-art semiconductor devices seem to be the most interesting amplifiers for transmission in the second transmission window (around 1.3 μm).

Amplifier Gain and Bandwidth

In a perfect amplifier, the amplification process would be insensitive to the bit rate, modulation format, power, state of polarization, wavelength, and optical bandwidth of the signal passing through it. On the other hand, no interaction would take place if more than one signal were amplified simultaneously. In practice, however, the optical gain depends not only on the wavelength (or frequency) of the incident signal, but also on the electromagnetic field intensity at any point inside the amplifier. Details of wavelength and intensity dependence of the optical signal depend on the amplifying medium.

We consider a case in which the gain medium is modeled as a homogeneously broadened two-level system. In such medium, the gain coefficient (i.e., the gain per unit length) can be written as:

$$g(\nu, P) = \frac{g_0}{1 + \dfrac{(\nu - \nu_0)^2}{\Delta\nu_0^2} + \dfrac{P}{P_{\text{sat}}}} \qquad [1]$$

where g_0 is the peak value of the gain coefficient determined by the pumping level of the amplifier, ν the optical frequency, ν_0 the atomic transition frequency, $\Delta\nu_0$ the 3 dB local gain bandwidth, P the optical power of the signal, and P_{sat} the saturation power, which depends on the gain medium parameters. It must be emphasized that $\Delta\nu_0$ and P_{sat} refer to the local gain. However, from the communication system point of view, it is more desirable to use the related concepts of amplifier bandwidth and amplifier saturation power that will be evaluated below.

The amplifier gain G is defined as

$$G = \frac{P_{\text{out}}}{P_{\text{in}}} \qquad [2]$$

where P_{in} is the input power and P_{out} the output power of a continuous wave (CW) signal being amplified. The amplifier gain G may be found by using the relation:

$$\frac{\mathrm{d}P}{\mathrm{d}z} = g(\nu, P)P \qquad [3]$$

where $P(z)$ is the optical power at a distance z from the amplifier input end.

If the signal power obeys the condition $P \ll P_{\text{sat}}$ throughout the amplifier, the gain coefficient given by eqn [1] can be considered independent of the signal power. In such a case, the amplifier is said to be operated in the unsaturated regime and works as a linear device. The gain coefficient presents in this situation a Lorentzian profile that is characteristic of homogeneously broadened two-level systems. However, the gain spectrum of actual amplifiers can deviate significantly from the Lorentzian profile.

The solution of eqn [3] in the unsaturated regime is an exponentially growing signal power, given by

$$P(z) = P_{\text{in}} \exp(gz) \qquad [4]$$

For an amplifier length L, we then find that the linear amplifier gain is

$$G(\nu) = \exp(gL) = \exp\left[\frac{g_0 L}{1 + (\nu - \nu_0)^2/\Delta\nu_0^2}\right] \qquad [5]$$

Both the amplifier gain $G(\nu)$ and the gain coefficient $g(\nu)$ are maximum when $\nu = \nu_0$. However, $G(\nu)$ decreases much faster than $g(\nu)$ with the signal detuning $\nu - \nu_0$, because of the exponential dependence of G on g. As a consequence, the amplifier bandwidth $\Delta\nu_A$, which is defined as the FWHM of $G(\nu)$, is much smaller than the gain bandwidth $\Delta\nu_0$ (Figure 1). This can result in signal distortion in the case where a broadband optical signal is transmitted through the amplifier. From eqn [5] we can obtain the following relation between the amplifier bandwidth and the gain bandwidth:



Figure 1 Gain coefficient profile $g(\nu)$ and the corresponding amplifier gain spectrum $G(\nu)$.

$$\Delta\nu_A = \Delta\nu_0 \sqrt{\frac{\ln 2}{g_0 L - \ln 2}} \qquad [6]$$

Gain Saturation

An important limitation of the nonideal amplifier is related with the power dependence of the gain coefficient given by eqn [1]. This property is known as gain saturation and it appears when the signal power ratio P/P_{sat} is non-negligible. Since the gain coefficient is reduced when the signal power P becomes comparable to the saturation power P_{sat}, the amplifier gain G will also decrease.

Assuming that $\nu = \nu_0$ and substituting g from eqn [1] in eqn [3] gives

$$\frac{\mathrm{d}P}{\mathrm{d}z} = \frac{g_0 P}{1 + P/P_{\text{sat}}} \qquad [7]$$

Considering the initial condition $P(0) = P_{\text{in}}$, we obtain from eqns [2] and [7] the following implicit relation for the amplifier gain:

$$(1 - G)\frac{P_{\text{in}}}{P_{\text{sat}}} = \ln\left(\frac{G}{G_0}\right) \qquad [8]$$

where $G_0 = \exp(g_0 L)$. The input saturation power P_{in}^{s} is defined as the input power for which the amplifier gain G is reduced by a factor of 2 from its unsaturated value G_0 (Figure 2). Indeed, it is obtained by using $G = G_0/2$ in eqn [8]:

$$P_{\text{in}}^{\text{s}} = \frac{2\ln(2)P_{\text{sat}}}{(G_0 - 2)} \qquad [9]$$



Figure 2 Saturated amplifier gain as a function of the input power.

As observed from eqn [9], the input saturation power P^s_{in} does not coincide with P_{sat}. The output saturation power is given by $P^s_{out} = G_0 P^s_{in}/2$. In practice, $G_0 \gg 2$ and P^s_{out} is found to be smaller than P_{sat}, by about 30%.

Gain saturation can be seen as a serious limitation, particularly for multichannel communication systems. However, the self-regulating effect of gain saturated amplifiers can be useful in long-haul lightwave communication systems, including many concatenated amplifiers. In fact, if the signal level in a chain of amplifiers is unexpectedly increased along the chain, the saturation effect causes a lower gain provided by the following amplifiers and vice versa for a sudden signal power decrease.

Amplifier Noise

Besides the bandwidth and gain saturation limitations, another property must be considered concerning practical optical amplifiers. In fact, optical amplifiers always add spontaneously emitted photons to the signal during the amplification process. Those photons are amplified besides the signal photons so that, at the amplifier output, an amplified spontaneous emission (ASE) noise is presented. Since spontaneous emission always takes place, ASE noise is unavoidable and does not depend on the amplifier temperature. This is one of the most important differences between optical and electrical amplifiers, where amplifier noise is of thermal origin and can be reduced by lowering the amplifier temperature.

The ASE determines a degradation of the signal-to-noise ratio (SNR). The SNR degradation is usually characterized by the amplifier noise figure, which is defined as the SNR ratio between input and output:

$$\mathrm{NF} = \frac{\mathrm{SNR_{in}}}{\mathrm{SNR_{out}}} \qquad [10]$$

The SNR is usually referred to the electrical power generated when the optical signal is converted to electrical current by using a photodetector. Therefore, the noise figure as defined in eqn [10] would usually depend on several detector parameters, which determine the shot noise and thermal noise associated with the practical detector. We will consider the case of an ideal detector, whose performance is limited by shot noise only.

The SNR of the input signal is simply determined by the detection shot noise and can be written as:

$$\mathrm{SNR_{in}} = \frac{P_{in}}{2h\nu\Delta f} \qquad [11]$$

where Δf is the detector bandwidth.

To evaluate the term $\mathrm{SNR_{out}}$, one should add the contribution of spontaneous emission to the receiver noise. The ASE noise spectral density is assumed to be constant and can be written as

$$S_{sp}(\nu) = (G-1)n_{sp}h\nu \qquad [12]$$

where G the amplifier gain and

$$n_{sp} = \frac{N_1}{N_1 - N_0} \qquad [13]$$

is known as the spontaneous emission factor or the population inversion factor. In eqn [13] N_0 and N_1 are the atomic populations for the ground and excited states, respectively.

Considering a low noise amplifier, the signal power impinging the photodetector is larger than the optical noise power and the shot noise power. As a consequence, the electrical noise, due to the signal-ASE beating, is the dominant contribution and the SNR of the amplified signal is given by:

$$\mathrm{SNR_{out}} \approx \frac{GP_{in}}{4S_{sp}\Delta f} \qquad [14]$$

Using eqns [11]–[14], the amplifier noise figure defined by eqn [10] becomes:

$$\mathrm{NF} = 2n_{sp}\frac{G-1}{G} \approx 2n_{sp} \qquad [15]$$

where the approximation holds when the gain is much higher than one. In the case of an ideal amplifier, $n_{sp} = 1$ and eqn [15] show that the SNR is degraded by 3 dB. For most practical amplifiers, NF can be as large as 6–8 dB.

Basic Amplifier Configurations

The relative importance of the different limiting factors discussed above depends on the actual



Figure 3 Four generic configurations for incorporating optical amplifiers into transmission systems: (a) as a power amplifier; (b) as in-line amplifiers; (c) as a preamplifier; (d) for compensation of distribution losses in local-area networks.

amplifier application. Figure 3 shows the four basic system configurations envisioned for the incorporation of optical amplifiers. The first configuration is to place the amplifier immediately following the laser transmitter to act as a power amplifier or booster (Figure 3a). The main purpose of such amplifiers is to boost the signal power, which can provide an increase of the transmission distance by 100 km or more. Since the signal input power is typically large (0.1–1.0 mW), the key parameter for the power amplifier will be to maximize the saturation output power and not necessarily the absolute gain.

The second configuration is to place the amplifier in-line and perhaps incorporated at one or more places along the transmission path (Figure 3b), replacing the electronic regenerators. The in-line amplifier corrects for periodic signal attenuation and may exist in a cascade form. The use of in-line optical amplifiers is particularly attractive for multichannel communication systems, since they can amplify all channels simultaneously.

The third configuration consists of using the amplifier immediately before the receiver, so it functions as a preamplifier (Figure 3c). The purpose of such an amplifier is to improve the receiver sensitivity. The main figures of merit are high gain and low amplifier noise, because the entire amplifier output is immediately detected.

In local-area networks (LANs), distribution losses often limit the number of possible nodes. The fourth application of optical amplifiers consists of using them for compensating such distribution losses (Figure 3d).

List of Units and Nomenclature

g_0	peak value of the gain coefficient at peak	m^{-1}
$g(\nu)$	gain coefficient	m^{-1}
G_0	unsaturated amplifier gain	
$G(\nu)$	amplifier gain	
L	amplifier length	m
n_{sp}	spontaneous emission factor	
P	signal power	W
P_{in}	input signal power	W
$P_{\mathrm{in}}^{\mathrm{s}}$	input saturation power	W
P_{out}	output signal power	W
$P_{\mathrm{out}}^{\mathrm{s}}$	output saturation power	W
P_{sat}	saturation power	W
$S_{\mathrm{sp}}(\nu)$	ASE noise spectral density	J
Δf	detector bandwidth	Hz
$\Delta \nu_0$	bandwidth of the gain coefficient	Hz
ν	optical frequency	Hz
ν_0	atomic transition frequency	Hz

See also

Optical Amplifiers: Optical Amplifiers in Long-Haul Transmission Systems. **Optical Communication Systems:** Architectures of Optical Fiber Communication Systems.

Further Reading

Agrawal GP (1992) *Fiber-Optic Communication Systems*. New York: Wiley.

Bjarklev A (1993) *Optical Fiber Amplifiers: Design and System Applications*. Boston, MA: Artech House.

Desurvire E (1994) *Erbium-Doped Fiber Amplifiers: Principles and Applications*. New York: Wiley.

Green PE Jr (1993) *Fiber Optic Networks*. Englewood Cliffs, NJ: Prentice Hall.

Iannone E, Matera F, Mecozzi A and Settembre M (1998) *Nonlinear Optical Communication Networks*. New York: Wiley.

Kazovsky L, Benedetto S and Willner A (1996) *Optical Fiber Communication Systems*. Boston, MA: Artech House.

Shimada S and Ishio H (eds) (1994) *Optical Amplifiers and their Applications*. New York: Wiley.

Erbrium Doped Fiber Amplifiers for Lightwave Systems

P Bollond, JDS Uniphase Corporation, Ewing, NJ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The telecommunications industry has undergone a revolution since the 1980s, by using glass optical fibers for the transmission of information encoded as pulses of light. A single telecommunications-grade optical fiber has been shown to support the propagation of more than 1 Tbit per second (1×10^{12} pulses per second) over distances comparable to typical city separations (>100 km). From this technology, optical fiber links have evolved to become a network on a planet-wide scale, and form the physical backbone of the information age.

Erbium-doped fiber amplifiers (EDFAs) are an enabling technology for optical fiber communication networks. They have several important properties that make them the amplification component of choice in long-distance commercial data transport networks. Erbium ions deposited in silica-based glass allow amplification in the lowest loss region of commercial-grade optical fiber (<0.25 dB/km from approximately 1530–1620 nm). Erbium-doped fiber (EDF) is manufactured in a form that allows for low-loss fusion splicing to standard communications fiber. Compact semiconductor laser diodes are available to excite the erbium ions into an amplification state. The long lifetime of the excited state of erbium provides the ability to simultaneously amplify multiple wavelength channels without significant cross-channel interference. Multiple channel systems have been deployed with more than 100 optical channels (or wavelengths) through each EDFA, and this has allowed network capacities to be dramatically increased. The low noise properties of the EDFA also allow networks to be constructed with many amplified spans before the optical signal has to be electronically regenerated. Practically unlimited transmission distance has been demonstrated using a small number of optical soliton channels through periodically amplified EDFA lightwave systems.

The development history of the EDFA can be traced back to the first optical amplifier. In 1962, a neodymium-based fiber amplifier was invented that operated at 1064 nm. During the 1980s, the need for an optical amplifier at telecommunications wavelengths initiated research at many locations throughout the world. In 1987, the University of Southampton (UK) was first to demonstrate an EDFA that had optical gain at 1550 nm, and during the following years the design of erbium-doped fiber was optimized for this application. In 1989, a practical semiconductor laser diode became available to pump EDF, and the first compact optical fiber amplifier modules soon appeared for commercial deployment. The traditional method of signal regeneration, prior to 1990, was to use electronics to detect the optical signal after each transmission span, recover the digital signal, and then retransmit using another laser diode. The EDFA allows practical wavelength division multiplexing (WDM) of multiple optical signals with all optical signal amplification, and provides significant performance and cost advantages over electronic regeneration.

EDFAs have emerged from the laboratory to be widely deployed in communication networks. EDFAs are used to boost transmitted power of the signal lasers (booster amplifier), amplify signals in transit to compensate losses sustained in the fiber (line amplifier), or amplify signals before a receiver (pre-amplifier). Typically, the amplifier module is specifically manufactured for particular systems that are mounted on electronic circuit boards. These circuit packs are then housed in central offices (local telephone exchanges), remote ‘repeater huts’, or even in undersea ‘bottles’ as part of a transoceanic cable. The high cost of network failure requires that the manufactured EDFA modules comply with stringent reliability criteria, to provide a useful operating lifetime greater than 25 years when subject to extreme environmental conditions.

Amplifiers are constructed for incorporation into either existing fiber links as part of an upgrade, or for newly planned systems. Because of the high cost of installing new fiber into the ground and securing property rights, it has become economically desirable to upgrade many existing fiber links rather than to build new systems. Transmission cables usually have many pairs of individual optical fibers, some of which will not initially be transporting data, and these ‘un-lit’ or ‘dark fibers’ can be activated as consumer demand increases over time. Typically, each fiber of a pair is used to carry either ‘east’- or ‘west’-bound traffic. Around city areas metropolitan area networks can be expanded in this way, but for long-distance links (long haul networks with distances >1000 km) operation is designed for a larger number of channels (40 to 120 wavelengths) at higher data rates (10 or 40 GHz per channel) over specialized transmission cables containing low numbers of fiber pairs. Typically communication systems are designed to meet certain cost targets, expressed as dollars per Gbit/s per km, for total transmission distances. The total transmission distance is limited by the optical signal to noise ratio (OSNR) degradation after each fiber-amplifier link, with a smaller permissible degradation at higher bit rates. The required gain and OSNR performance for the system is then translated to an EDFA module specification.

This article discusses EDFA design and applications, and shows the elements involved in producing reliable modules for commercial lightwave systems.

Components for EDFAs

EDFAs are comprised of passive optical components, erbium-doped fiber, and pump lasers. Passive components are chosen to meet optical and environmental specifications, while the erbium-doped fiber is selected based on the optical power, gain, and noise figure requirements. Pump lasers are a key influence on the price and performance of optical amplifiers.

The amplifier module is typically connected to the transmission fiber using fiber connectors. These polished fiber connectors have a higher insertion loss and reflectivity than fusion splicing, but allow for easy deployment in the network. Internal optical components are fusion spliced together to provide low loss, low back reflection, high strength, and high reliability joins. Fusion splicing is tailored to particular fiber types, so that optical components with dissimilar fiber types are joined with the lowest loss.

The signal and pump radiation is combined with low loss using optical components called wavelength division multiplexers (see Figure 1). These components are based on fused fiber or interference filter based technology. Fused fiber WDMs offer the lowest insertion loss (<0.1 dB is commercially available) but is restricted to widely spaced wavelengths (e.g., 980 nm pump and 1550 nm signal). Interference filter based WDMs are available for closely spaced wavelengths (e.g., 1480 nm pump and 1530 nm signal) and have a very low wavelength dependent insertion loss (flatness). Interference filters can be designed to produce sharp low-pass, high-pass, or bandpass type filters suitable for combining closely spaced wavelengths, as well as broader peaks suitable for lowering the gain in particular signal wavelength regions to produce gain flattened amplifiers.

Signal reflections can cause an amplifier to act as a laser, and this detrimental effect is eliminated in EDFAs by using optical isolators. In an isolator the signal light is coupled out of the single-mode fiber through a graded index (GRIN) lens and passes through a nonlinear crystal before being coupled back into the optical fiber. The isolator consists of a birefringent rutile (TiO_2) or Yttrium OrthoVanadate (YVO_4) wedge, followed by a Yttrium Iron Garnet (YIG) Faraday rotator, followed by another birefringent wedge. The YIG crystal is surrounded by a permanent magnet that rotates the light's polarization by 45 degrees. The 45-degree polarization rotation, coupled with the two birefringent wedges, ensures that light is efficiently coupled to the output fiber but not in the reverse direction. Commercial isolators are available with low insertion losses across the signal band, with some samples below 0.35 dB. Note that the YIG crystal works well for the 1480 nm pump and 1530–1620 nm signal bands, but currently there is no suitable isolator material that covers 980 to 1550 nm and this puts some limitations on certain EDFA designs.

The isolator design has been extended to make multiport circulators. A three-port circulator has the input into port 1 and output of port 2, light entering port 2 is directed to port 3, and light entering port 3 is blocked with an isolator. The circulator allows for adding and dropping of individual channels when a



Figure 1 Single-stage EDFA with features.

narrow bandwidth reflective filter is placed on port 2. Circulators also can be used to separate co-propagating and counter-propagating traffic on a single transmission fiber before amplification is done.

Erbium-doped fiber has two strong absorption bands around 980 nm and 1480 nm that are suitable for achieving a population inversion in the erbium ion. The 980 nm wavelength allows low noise amplification, while 1480 nm lasers provide higher EDFA output. 980 nm pump lasers usually incorporate fiber Bragg gratings to stabilize the laser wavelength to match the narrow EDF absorption peak, and also have lower drive current requirements. A 1480 nm pump can provide more amplification, since there are more photons in each mW of laser power at 1480 nm than 980 nm. High-output power pump lasers incorporate thermo-electric coolers (TECs) within the pump laser package and can provide fiber coupled power greater than 500 mW. Both high-power lasers have been qualified to meet the most stringent reliability standards, with typical mean time before failure beyond 25 years. Low-cost 980 nm pump lasers, that do not have TECs, are also available in smaller packages and can supply up to ~200 mW. By using wavelength division or polarization combining techniques, it is possible to further increase the available pump power in the erbium fiber.

The EDFA module is assembled into a package that may contain passive optical components, several meters of coiled EDF, pump lasers, photo-detectors, and electronic circuit boards. In some cases, it is advantageous to thermally stabilize the components so that the amplifier performance can be maintained when exposed to extreme environmental conditions. This may occur when the central office's environmental control is compromised (e.g., air conditioning failure). In particular, EDF can exhibit undesirable spectral gain changes if the ambient temperature changes by more than 5 °C.

Pump lasers with internal TECs can dissipate more than 5 Watts of heat per laser and since cooling fans usually do not have the required reliability, passive cooling is commonly used in the module in the form of a metal heat sink. The amplifier module's size can be compact, limited by the height of optical components or pump laser diodes, or by the size of a built-in heat sink. The module is designed to survive conditions of electrostatic discharge, humidity, temperature, thermal shock, extreme vibration, and other stresses that may be inadvertently present during operation in the field. In addition, all material in the EDFA module is also qualified against problems with out-gassing (e.g., hydrogen release), combustion and chemical or biological exposure.

The Single-Stage Amplifier

A simple single-stage EDFA consists of an erbium-doped fiber spool with signal and pump combining multiplexer. The fiber is optically pumped by 980 nm and/or 1480 nm laser(s), whose light is coupled into the signal fiber by a passive component called an optical multiplexer. The pump wavelengths are readily absorbed by erbium ions embedded in silica raising them to an excited state. Amplification occurs when, stimulated by a nearby signal photon, an excited erbium ion relaxes back to the ground state producing a second, identical signal photon. The erbium ion can be approximated as a three-level atomic system that can be completely inverted by a 980 nm photon, to provide the lowest noise amplification. In contrast, the 1480 nm pump will excite the erbium ion directly into the upper laser level as a two-level system, and because of rapid spontaneous emission from this level, the maximum inversion in this case cannot exceed approximately 75%. Note that as the pump photons are absorbed, the inversion will be nonuniform along the EDF length.

There are two signal wavelength regions commonly amplified by EDFAs, the C-band (conventional band) from approximately 1528 to 1565 nm, and the L-band (long band) from approximately 1570 to 1620 nm. Amplification in the C-band readily occurs when moderate pump power is available, and relies on the erbium ion's spectral absorption and emission wavelength window that is suited to high levels of atomic inversion. L-band amplification is also achieved with moderate pump powers, but because of the lower absorption and emission cross-sections, similar gain is reached using approximately five times more EDF with a lower average inversion. The C-band amplifier is typically less costly because less EDF is used, while high-concentration erbium fibers are available specifically for L-band EDFAs.

An EDFA's most critical performance parameters are its amplified signal output power (typically stated in dBm) and its noise figure (stated in dB). Output power is mainly determined by total pump power and the amplifier internal loss. The noise figure (NF) is defined as the ratio of the signal-to-noise ratio at the input to the signal-to-noise ratio at the output.

A single-stage amplifier typically has 1 or 2 pump lasers but can have more if polarization- or wavelength-pump-combining is implemented for higher power. When the pump radiation propagates in the same direction as the signal, the amplifier is co-pumped, while counter-pumping denotes the case when the pump laser propagates against the signal. For a single pump, a co-pumping 980 nm laser minimizes the NF (suitable for a pre-amplifier) while counter-pumped 1480 nm architecture optimizes output power at some expense to the NF (suitable for a booster amplifier). Recent semiconductor pump laser improvements have enabled 980 nm pump lasers with output powers >500 mW to be commercially available, allowing most single- or dual-stage EDFAs to be energized by one laser.

Single-stage designs can be enhanced, as shown in Figure 1. To control the network an optical signal may be used as a telemetry or network supervisory channel, and this is removed with a filter. Telemetry wavelengths are usually outside of the useful EDF amplification window, and commonly range from 1500–1520 nm and from 1620–1640 nm. An isolator may be used at the input and/or output to prevent pump laser or amplified spontaneous emission from the erbium-doped fiber 'leaking' into the transmission path. Optical taps may be included to provide information about signal spectra at the input and output sides. Their feedback can be used to control pump laser biases for tuning output power, monitoring amplifier performance, or simply to trigger alarms. In addition, a reflection monitor is sometimes placed at the output to observe backwards propagating optical signals arising from reflections. Electronics in the module will continuously monitor the pump lasers and photodetectors and, for example, can place the module in an 'eye-safe' low-output power (<10 mW) mode within milliseconds if a transmission fiber break is detected through increased back-reflected optical power.

The amplifier has a signal input power of −30 to −10 dBm (1–100 μW) for each optical channel, and has a gain of 25 dB to compensate for a typical span loss of 100 km optical fiber link. This signal level allows high powers at the receiver photodetector for high-quality signal detection, yet is low enough to avoid nonlinear propagation effects in the transmission fiber. The typical total output signal power of an 80 channel (wavelength) C-band EDFA is less than 200 mW (+23 dBm) to avoid stimulated Raman scattering (SRS) in standard transmission fiber. The use of improved low nonlinearity transmission fibers and longer transmission distances can lead to specified total EDFA output powers to be greater than 400 mW (+26 dBm). To provide the best performance, the amplifier usually will allow only a single direction of propagation, with bi-directional communications systems using one transmission fiber and circulators to separate 'east' and 'west' traffic into individual EDFAs.

Figure 2 shows the results of a numerical simulation for a single-stage amplifier as a function of the input power and EDF length. The amplifier was assumed to have EDF with peak absorption of 5.5 dB/m near 1530 nm, and was pumped with 100 mW at 980 nm. The amplifiers signal loss before and after the EDF was taken to be 0.8 and 1.2 dB, respectively. As amplifier input power increases there is a decrease in gain provided by the medium since there is a fixed amount of pump power available. The maximum gain is usually achieved near 1530 nm where the difference between the EDF's emission and absorption cross-sections is greatest. Selecting the length of EDF is critical to achieving the desired performance, and this can be examined using numerical simulation for a wide range of design options.

Undersea systems, with their long distances and large costs of network failure, place stringent design requirements on EDFAs. These systems mostly use single-stage designs with emphasis on low noise operation. This can be achieved by eliminating most of the optical components prior to the EDF, and also by co-propagating a strong 980 nm pump using a low loss fused fiber WDM. Undersea repeaters are spaced by 30 to 80 km, shorter than terrestrial networks, with each channel operated at higher power to achieve multi-thousand kilometer distances. For example, the trans-Pacific TPC-5J cable spans 8600 km from Coos Bay, Oregon (USA) to Ninomiya (Japan), using EDFAs spaced every 33 km. The tight electrical power budgets available to each repeater (powered from land) necessitate using pump lasers without TECs. During installation, the EDFA will experience large mechanical shock, as the cable and metal repeater bottles are unwound aboard ship and dropped into the ocean. Other design considerations are done for operation at the constant ambient temperature of the ocean bottom (∼+2 to 4 °C) or for seasonal temperature changes on the continental shelves, where the optics and EDF will operate at 15 to 30 degrees above ambient due to heating from the electronics.

Single-stage optical amplifiers are suited for a wide range of applications such as single-channel amplifiers, simple WDM amplifiers, and low-cost amplifiers. Using high-power pump lasers or combined pump laser schemes allows such amplifiers to deliver output powers >20 dBm. However, single-stage amplifiers cannot meet the requirements of all telecommunications architectures, leading to increasing demand for multiple-stage EDFAs that are discussed below.

Multiple-Stage EDFAs

The most common implementation of a multiple-stage EDFA is to improve the noise and output power



Figure 2 Typical single-channel performance of a single-stage EDFA.

characteristics by imbedding an optical isolator between two sections of EDF. The isolator blocks backward-traveling amplified spontaneous emission to improve the efficiency of the amplifier. This is shown in Figure 3 for two common single-pump designs. The first is the 'pump by-pass', design where the residual pump radiation from the first stage is redirected around the mid-stage isolator. This is often used when pumping with 980 nm since signal band optical isolators will not transmit 980 nm radiation. This design can introduce problems when using low-quality components as small signal levels can propagate around the pump by-pass fiber to create multiple path interference (MPI) effects. Although MPI effects can be eliminated by using a pump splitting coupler to directly pump each EDF section, the pump by-pass design makes the most efficient use of available pump power. The second design is called the 'pump through' design, and is used when pumping at 1480 nm since both the pump and signal band (e.g., 1550 nm) photons will transmit through commercial isolators with only small loss. Note that for cost and space constraints within the module, it is sometimes advantageous to use hybrid optical components, e.g., an isolator and WDM can be combined into one compact package.

An EDFA with multiple input signals will have a very nonuniform output gain profile. This is a consequence of the erbium ion's wavelength-dependent emission and absorption cross-sections in the host glass material. Figure 4 shows gain spectra for both C-band and L-band EDFAs with and without gain-flattening filters (GFFs). The gain spectrum is dependent on the EDF's chemical composition and EDFA design features. For an amplifier with 25 dB gain, a GFF with peak loss less than 10 dB is usually needed to correct for these gain deviations. Although many technologies are available for GFFs (e.g., thin-filter interference filters, Bragg gratings, tapered fiber filters, etc.) the basis function of these technologies is usually not identical to the EDF's gain profile, and this mismatch results in gain


EDF 1
Isolator/ WDM
WDM
Isolator
WDM
EDF 2
Isolator
Signal input
Pump path
Amplified signal output
Pump laser 1
EDF 1
Isolator/ WDM
Isolator
EDF 2
Isolator
Signal input
Amplified signal output
Pump laser 1

Figure 3 Imbedded Isolator EDFA designs.



Figure 4 Gain spectrum of a multi-staged optical amplifier with and without gain flattening filters.

flatness error. However, when using these technologies, manufactured EDFAs can have a gain error (flatness) less than 1.0 dB over bandwidths greater than 35 nm.

Early EDFAs for WDM systems used 16 optical channels spaced by 200 GHz in the 1540 to 1560 nm part of the C-band. In this case, the EDF gain profile is relatively smooth and no GFFs are needed to achieve a 1.0 dB gain flatness specification. It is important to note that for a particular level of signal and pump power, a longer length of EDF in the EDFA will produce more gain at the long wavelength end of the spectrum, hence by shortening the EDF length in Figure 4 the result will be relatively flat gain from approximately 1540 to 1560 nm. As EDFA technology has matured, the EDF can be the bandwidth-limiting component in a system, and it has become necessary to use GFFs to realize useable bandwidths of up to 55 nm when using regular silica-based EDF. The most economic EDFAs operate in the C-band where relative to the L-band, pump laser efficiency is highest, EDF lengths are shortest, and the chromatic dispersion of most installed transmission fiber limits nonlinear optical effects.

In single-stage amplifiers, the gain-flattening filter is at the amplifier output, and this results in lost output power. Wideband gain-flattened amplifiers usually have a multiple EDF stage design, with the GFF component between two EDF stages. The EDF sections that follow the attenuating GFF provide additional amplification, to give high power out of the EDFA module that has large internal losses.

In addition to GFF components inside the EDFA, an attenuator can be used to compensate for input signal power changes, which will produce a spectral gain rotation or tilt. The attenuator reduces the power on all optical channels equally and allows the amplifier to operate in a 'fixed gain' mode. In WDM systems, optical amplifiers may also need mid-stage access where the signal is fed into an external device between the amplifier stages. Reasons for doing this include monitoring, adding or dropping of individual channels, and dispersion compensation. Since additional losses up to 10 dB are introduced in the amplification path, the amplifier design has to be optimized for those losses.

Typical two-stage gain-flattened optical amplifier architecture is shown in Figure 5. Input and output couplers and telemetry WDMs can be included if required. A single pump can be split and shared between stages to save cost. When multiple pumps are needed, the most common configuration is a 980 nm pump laser co-pumping the first stage (EDF1) for low noise and a 1480 nm laser counter-pumping the second spool (EDF2) for high gain. A significant loss element, e.g., a gain-flattening filter, add/drop module or dispersion compensation module, is situated between the stages. Note that mid-stage access can be located before or after the gain flattening or between additional EDF stages. The gain spectrum of multistage gain-flattened EDFAs is shown in Figure 6, showing the gain equalization possible using a multistage amplifier design and gain-flattening filters. Using deeper GFFs can increase the usable bandwidth of the amplifiers, but this requires higher-power pump lasers to maintain the same gain and optical signal-to-noise ratio (OSNR) performance.

The two-stage EDFA shown in Figure 5 highlights a common problem for amplifier design. Given high-grade optical components and pump lasers, what



Figure 5 Typical multistage gain-flattened optical amplifier architecture.



Figure 6 Measured gain and noise spectra of multistaged gain-flattened C-band and L-band EDFAs.

length of erbium-doped fiber should be used to give the best amplifier performance? This question is best answered by using the results of extensive numerical simulations of the optical amplifier.

Figure 7 shows the results of numerical simulation for a two-stage amplifier as a function of the first and second EDF stage lengths. The amplifier was assumed to have EDF with a peak absorption of 5.5 dB/m near 1530 nm, and was pumped with 130 mW at 980 nm in the first stage and 160 mW at 1480 nm in the second stage. The total input power was assumed to be -2.5 dBm for 80 channels distributed from 1530 nm to 1563 nm. Note that each of the 80 channels is separated by 100 GHz, and will generally support a long-distance communications system with each wavelength modulated at 10 GHz.

Figure 7a shows that the optical output power is largest when both EDF stages are approximately 20 meters. For this design, EDF lengths significantly longer than 20 meters will produce less output power, since the pump radiation will have been completely absorbed in the first few meters of EDF. The spectral gain flatness is shown in Figure 7b. For this design, approximately 17 meters of EDF was needed to produce a flat gain spectrum, i.e., each optical channel had the same gain. Other combinations of EDF lengths were not matched to the particular gain-flattening filter and produced large gain variations across the band. In general as the amplifier's total EDF length increases the gain spectrum exhibits a positive tilt (e.g., longer wavelength channels will experience more gain). Figures 7c, d show the average channel and maximum channel NF, respectively. From a system design perspective, a link can be limited by the optical channel with the lowest optical signal-to-noise ratio (OSNR) or highest noise figure, and this is a critical parameter of interest when designing optical amplifiers. In practice the best amplifier design is a compromise between high-gain, low-gain flatness, and low NF. From extensive numerical simulations, for the two-stage gain flattened amplifier example it was for



Figure 7 (a) Total output power, (b) spectral flatness, (c) average noise figure, and (d) maximum channel noise figure of a two-stage optical amplifier with a gain-flattening filter.

approximately 4 meters in EDF stage 1, and 13 meters in stage 2.

Successful commercial EDFA products are more than a single amplifier design that can accommodate all applications. In some cases an economical solution is a modular design approach, where smaller capacity, lower-cost amplifiers are initially installed in a network. Additional gain can be added to the basic amplifier for longer-distance spans or as network traffic increases over time. This 'pay as you grow' approach can be done using additional gain stages, or pump lasers, and can be upgraded without interruption of revenue-generating network traffic.

Low-Noise Design of EDFAs

A key design feature of commercial EDFAs is low-noise operation since the degradation of the OSNR limits the reach of the system. The NF of an EDFA can be defined as

$$\mathrm{NF} = \mathrm{SNR}_{\mathrm{in}}/\mathrm{SNR}_{\mathrm{out}} \qquad [1]$$

The NF can also be calculated from

$$\mathrm{NF} = \frac{1}{G} \times \left[\frac{P_{\mathrm{ASE}}(\nu_{\mathrm{s}}, L)}{h\nu_{\mathrm{s}}} + 1 \right] \qquad [2]$$

where P_{ASE} is the amplified spontaneous emission (ASE) noise power at the signal frequency ν_{s} for an EDFA of gain G (h = Plancks constant). An alternative equation for the NF for a single section of EDF is

$$\mathrm{NF} = \int_0^L \frac{\gamma_{\mathrm{e}}(\nu_{\mathrm{s}}, z) - \gamma_{\mathrm{a}}(\nu_{\mathrm{s}}, z)}{P_{\mathrm{s}}(z)} \times P_{\mathrm{s}}(0)\mathrm{d}z + 1 \qquad [3]$$

where γ_{e} and γ_{a} are the EDF emission and absorption factors at the signal frequency ν_{s}, at distance z along the amplifying fiber. Equation [3] shows that low NF can result from rapid signal gain in the initial fiber along the EDF. This result indicates that co-propagating pump and signal photons, both into the same end of the EDF, combined with the maximum inversion obtained by using a 980 nm pump, will result in low-noise amplification. The NF is typically expressed in dB units, and using a full quantum mechanical theory, the lowest possible NF for a fully inverted EDF with a large signal gain can be shown to be approximately 3 dB. Actual EDFAs will only approach the '3 dB quantum noise limit' when the signal is significantly lower than the available pump power (e.g., low channel count applications) so that high inversion can be maintained along the EDF length. Optical components in the EDFA prior to the first EDF will attenuate the signal but not the noise, since ASE is only generated in the EDF, and this input stage loss will directly add to the EDFA's NF.

The use of 1480 nm pump lasers can also result in a further NF penalty of 0.3 to 1.5 dB since complete inversion cannot be achieved when the erbium ions are operating as a two-level atomic system and more ASE is generated. The ASE, like the signal gain, has a wavelength-dependent spectral profile and this results in each channel having a different NF. Typically, the optical channel with the largest NF (lowest OSNR) is used to define the EDFA's noise performance. EDFAs with low-input signal power (e.g., -15 dBm) and high gain (e.g., 25 dB) may be described as low noise when the NF is <4 dB. For large total input signal power (e.g., $+2.5$ dBm for high channel count operation) low noise may be NF <5 dB.

For an amplifier with multiple EDF sections, the noise figure can be calculated from

$$\mathrm{NF}_{\mathrm{System}} = \frac{\mathrm{NF}_1}{L_1} + \frac{\mathrm{NF}_2}{L_1 G_1 L_2} + \ldots + \frac{\mathrm{NF}_N}{L_1 G_1 L_2 G_2 \ldots L_{N-1} G_{N-1}} \qquad [4]$$

where L_i is the signal loss prior to the gain G_i of the EDF stage i. From eqn [4], multistage amplifiers with large inter-stage losses will have numerically larger NFs, but the total module NF is dominated by the first EDF stage. Undersea EDFAs, with a single short EDF section, very small L_i and 980 nm pumping, can have NF <3.5 dB.

Advanced EDFA Functions

An important trend in optical amplifiers, and systems in general, is the move towards dynamic control. Several technologies are being considered and the primary idea is to dynamically control the intensity level of each optical channel or wavelength to correct for any gain/loss inequalities in the network. This is particularly important as channel counts and bit rates rise concurrently with the functionality demanded of optical communication networks. A common requirement in this category is fast amplifier response so that in a network where individual optical channels can be added or dropped there are no power distortions at other surviving wavelengths. In a typical drop event, in less than 1 microsecond, 31 of 32 wavelengths can be completely removed from the input to the EDFA by an add/drop module located elsewhere in the network. This event will cause a total input power decrease of 15 dB and without rapid pump power adjustment the remaining channel will be excessively amplified.

Erbium ions have an excited state lifetime of approximately 10 ms, and this sets the time-scale for the transient signal response. A network transient usually manifests as a sharp optical amplifier (OA) gain fluctuation lasting up to several tens of microseconds that will pulse large signal levels through the entire optical network. Dynamic network loading necessitates controlling temporal gain transients, and this may be achieved by using a microprocessor in the amplifier module. These intelligent EDFA modules can rapidly adjust the pump laser power based on feedback from internal photo detectors to control gain transients.

The need for dynamic control also exists in the frequency domain. Wideband amplifiers have a gain variation among the optical channels of typically up to 1 dB over all operating conditions, and since these EDFAs are concatenated over many spans the electronic receiver circuit at the end of the network will have to detect optical channels with widely varying power levels. This can limit the number of spans that the network can bridge before electronic regeneration becomes necessary. This problem can be corrected using a dynamic gain equalizing filter (DGEF) to actively attenuate individual optical channels levels. A DGEF can be embedded inside an amplifier to create a loss-less component, and can be used to equalize channel powers for an entire network.

The problems of accumulation of gain ripple become more apparent in systems that employ amplifiers based on stimulated Raman scattering. A conventional EDFA amplified system may have 10 spans transmitting 100 optical channels at 10 Gbit/s each over a distance of approximately 800 km before electronic regeneration becomes necessary. To span longer distances with higher capacity, Raman amplifiers are used to amplify the transmission fiber along with EDFAs. This system architecture has the advantage of a higher effective OSNR for the individual spans, and has been demonstrated for distances over 4000 km with 40 Gbit/s channels. However, the variability of the Raman amplifier gain, due to network loading and differing transmission fiber properties, necessitates the use of loss-less DGEFs.

High-capacity transmission uses individual channels that are each modulated up to typical 2.5, 10, or 40 GHz, that requires that the optical amplifiers have low polarization mode dispersion (PMD) and low chromatic dispersion (CD). Polarization mode dispersion distorts the temporal spread of an ultra-short pulse as different polarization states travel at different speeds through the transmission fiber and amplifier components. PMD is particularly a problem in the first generation of installed transmission fiber and through polarization components (e.g., isolators) that are not PMD compensated. Without PMD compensation, 40 Gbit/s transmission, for example, can be limited to very short distances (several km). Fortunately, PMD compensators have been developed for upgrading aged installed networks, and also amplifiers are available with very low PMD.

To achieve long-distance transmission, a chromatic dispersion map is produced for all the optical spans, and by using a dispersion compensating module in each amplifier, the net dispersion across the channel wavelength window is controlled. Although optical amplifiers have approximately 1000 times less optical fiber in them compared to the transmission span that it is amplifying, chromatic dispersion in the amplifier can also be of concern for very long-haul networks. The CD of the amplifier is primarily in the EDF, and is specific to the EDF's geometric and chemical composition. Furthermore, since the erbium ion is a resonant atomic system, there may be a pump and signal power contribution to the dispersion (resonant dispersion) that could degrade network performance. Characterization of these optical effects is typically done on manufactured 'field grade' amplifiers as part of a quality control process.

Conclusion

As optical networks evolve EDFAs will continue to be an enabling technology for higher capacity and more dynamic communications networks. EDFA technology has already advanced to accommodate multiple channels, to span several wavelength windows and to provide features such as dispersion compensation, gain-transient suppression, and dynamic gain flatness. As future network architectures are introduced, to incorporate Raman amplification and additional wavelength windows, the demands placed upon EDFA design will continue to expand.

See also

Optical Communication Systems: Architectures of Optical Fiber Communication Systems; Wavelength Division Multiplexing. **Scattering:** Raman Scattering.

Further Reading

Agrawal G (1989) *Nonlinear Fiber Optics*. San Diego, CA: Academic Press.

Agrawal G (1997) *Fiber Optic Communication Systems*. New York: John Wiley and Sons.

Becker PC, Olsson NA and Simpson JR (1999) *Erbium-doped Fiber Amplifiers – Fundamentals and Technology*. San Diego, CA: Academic Press.
Desurvire E (1995) *Erbium Doped Fiber Amplifiers*. New York: John Wiley and Sons.
Pedersen B, Bjarklev A, Povlsen JH, *et al.* (1991) The design of erbium-doped fiber amplifiers. *Journal of Lightwave Technology* 9(9): 1105.
Sudo S (1997) *Optical Fiber Amplifiers: Materials, Devices and Applications*. Boston, MA: Artech House.

Optical Amplifiers in Long-Haul Transmission Systems

B M Desthieux, Xtera Communications, Inc., Allen, TX, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical amplifiers have been a key element for enabling the development of optical transmission systems, which have reached total capacity in the order of a few terabits per second. The first type of optical amplifier to see application in the telecom industry has been the erbium-doped fiber amplifier. Following its invention in the late 1980s, the mid-1990s saw its industrial application in submarine and terrestrial transmission systems.

Since then, optical transmission systems have been the predominant source for transmitting information over distances ranging from a few 100 km to more than 10 000 km, connecting cities, countries, and continents.

This article will describe the applications of optical-fiber amplifiers in long-haul transmission systems, focusing on erbium-doped fiber amplifiers and Raman amplifiers, the most popular type of optical amplifiers used in modern transmission optical systems.

Fundamentals of Long-Haul Transmission Systems

This section explains the key elements and parameters of an optical transmission system.

Key Elements

An optical transmission system consists of a transmitter, a receiver, one or more optical amplifiers, and one or more spans of transmission fiber. Figure 1 shows a simplified schematic of a bidirectional transmission system using a fiber pair.

Optical amplifiers are used to compensate for the loss of the transmission fiber and the other optical elements placed along the signal path. Boosters and pre-amplifiers refer to optical amplifiers which are located at, respectively, the input end and output end of the system. In-line amplifiers refer to optical amplifiers located between the transmission fiber spans.

The transmitter includes laser diodes to generate the signal power and optical modulators to transfer the data stream from the electrical input signals to optical signals. The optical signal is transmitted to the receiver after traveling through the transmission fiber. At the receiver are located the photodiodes, which transfer back the information into electrical output signals. In order to increase the total bandwidth of the transmission system, time-division multiplexing (TDM) and wavelength-division multiplexing (WDM) can be used. TDM techniques combine the electrical domain data stream of several electrical channels, which is carried by a single optical channel. An optical channel refers to an optical signal located at a particular wavelength and modulated with the transmission data. TDM increases, therefore, the bit rate supported by the optical channel. Typical bit rates used in modern optical transmission systems are 2.5 Gbit/s and 10 Gbit/s. With WDM, several optical channels are combined, in the optical domain, into a single optical beam, which is launched into the transmission fiber. For this technique, optical multiplexers (Mux) and de-multiplexers (Demux) are required at, respectively, the transmitter and the receiver.

Long-haul transmission systems typically operate at wavelengths around 1.5 μm, where the attenuation of fibers is the lowest. We label C-band the region located between 1530 nm and 1565 nm. Its lower bound is labeled S-band; the upper bound the L-band.

Apart from attenuation, several other effects existing in fiber can be responsible for degrading the quality of the transmission. Among those is chromatic dispersion, which distorts the optical signal as it travels along the transmission fiber. Several types of fiber have been deployed with different chromatic dispersion characteristics. The most common one is the standard single-mode fiber (SSMF), which has a zero-dispersion wavelength – wavelength for which no chromatic dispersion is observed – near 1.3 μm. The dispersion-shifted fiber (DSF) has a zero-dispersion wavelength near 1.55 μm, and the nonzero



Figure 1 Schematic of a bidirectional long-haul transmission system.

dispersion shifted fiber (NZDSF) has a zero-dispersion wavelength close to 1.5 μm. To remedy this effect, dispersion compensating modules (DCM) are placed along the link. These modules – generally a special type of fiber – have chromatic dispersion with inverted characteristics with respect to those of the transmission fiber.

Key Optical-Amplifier Parameters

Optical amplifiers spontaneously generate optical noise – referred to as amplified spontaneous emission (ASE) – that is added to the modulated signal and consequently degrades the quality of the transmission. It is essential to quantify the level of ASE for a given optical transmission system.

We define the optical signal-to-noise ratio (OSNR) in the bandwidth $\Delta\nu$ as

$$\mathrm{OSNR} = \frac{P_{\mathrm{Signal}}}{P_{\mathrm{ASE}}} \qquad [1]$$

where P_{signal} is the signal power and P_{ASE} is the ASE power in the bandwidth $\Delta\nu$.

The required OSNR at a receiver, to detect the information with high quality, depends on the modulation format and on the other sources of noise or signal degradation existing in the transmission system. If we assume a nonreturn to zero (NRZ) modulation format, and signal detection limited only by ASE noise, an OSNR, in 0.1 nm bandwidth, of about 18 dB, is required at the receiver for a bit-error rate – number of erroneously transmitted bits divided by number of transmitted bits – of 10^{-12}. Introduction of other transmission degradation sources requires a higher OSNR to maintain the same bit-error rate.

The decibel unit (dB) for a given ratio, R, is defined by

$$R_{\mathrm{dB}} = 10\,\log_{10} R_{\mathrm{linear}} \qquad [2]$$

Similarly we defined the power decibel unit (dBm) as

$$P_{\mathrm{dBm}} = 10\,\log_{10} P_{\mathrm{mW}} \qquad [3]$$

where P_{mW} is the power in mW.

In order to quantify the amount of ASE generated by an optical amplifier, we define the equivalent input noise factor (n_{eq}), in a linear unit, by

$$n_{\mathrm{eq}} = \frac{P_{\mathrm{ASE}}}{h\nu\Delta\nu G} \qquad [4]$$

where P_{ASE} is the output ASE power in one polarization state in the bandwidth $\Delta\nu$, h the Planck's constant, ν the frequency of the ASE, and G the gain of the amplifier.

We also define the noise figure of the amplifier (NF) – a universal parameter to characterize amplifier noise – as

$$\mathrm{NF} = 2n_{\mathrm{eq}} + \frac{1}{G} \qquad [5]$$

If an optical component, having a loss T_{in} ($T_{\mathrm{in}} < 1$), is inserted at the input of the amplifier, the total NF of the amplifier becomes $\mathrm{NF}_{\mathrm{total}} = \mathrm{NF}/T_{\mathrm{in}}$. If an optical component, having a loss T_{out} ($T_{\mathrm{out}} < 1$), is inserted at the output of the amplifier, $\mathrm{NF}_{\mathrm{total}} = \mathrm{NF} + 1/G(1/T_{\mathrm{out}} - 1)$. When $G \gg 1$, we have $\mathrm{NF}_{\mathrm{total}} \approx \mathrm{NF}$.

The OSNR in 0.1 nm bandwidth obtained after N fiber spans of loss, $\mathrm{Loss}_{\mathrm{Fiber}}$ (in dB), each having an amplifier, is in decibels:

$$\mathrm{OSNR} = P_{\mathrm{Signal}} - \mathrm{Loss}_{\mathrm{Fiber}} - \mathrm{NF} - 10\log_{10} N + 58 \qquad [6]$$

where P_{Signal} is the signal power at the output of the amplifier.

When the optical signal power is sufficiently high, nonlinear effects also become responsible for the degradation of the system performance. Therefore, choosing the value of the signal power launched into the transmission fiber results in a trade-off between increasing the OSNR, and reducing nonlinear effects.

Optical Fiber Amplifier

An optical fiber amplifier consists of fiber with an active medium and at least one optical pump source, which is launched simultaneously with the signal into the fiber by means of a dichroic coupler.

We define as forward and backward pumping, the case where the pump is launched, respectively, in the same direction as the signal and in the opposite direction to the signal. We define as bidirectional pumping, the case where the fiber is pumped from both ends. The most commonly used pump sources are the semiconductor laser diodes. These lasers may use different technologies to meet the various performance requirements with respect to the amplifier types and applications. The most popular pump diodes are the distributed Bragg reflector (DBR), distributed feedback (DFB), or external-grating stabilized lasers.

Erbium Fiber Amplifier

Fiber doped with the rare-earth Er^{3+} ion can amplify a signal located at 1.5 μm with the appropriate fiber host material and if pumped near 0.98 μm or near 1.48 μm. Silica is the most common material used for the fiber host. Er^{3+} has three energy levels, as described in Figure 2.



Figure 2 Energy level diagram for Er^{3+} ions.

0.98 μm pumping occurs between the upper level $^4\mathrm{I}_{11/2}$ and the ground level $^4\mathrm{I}_{15/2}$, and 1.48 μm pumping occurs between the metastable level $^4\mathrm{I}_{13/2}$ and the ground level.

The signal amplification takes place between the metastable level and the ground level. With 0.98 μm pumping, a rapid energy transfer occurs between the upper level and the metastable level via a phonon-assisted process. The lifetime of the upper level is much lower than the lifetime of the metastable level, about 10 ms. Therefore, with 0.98 μm pumping we can assume a two-level energy transfer, between the metastable and the ground levels, for the description of the amplification process in the Er^{3+} medium.

We define the normalized medium inversion (D) by

$$D = \frac{N_2 - N_1}{N_t} \qquad [7]$$

where N_2 is the population of the metastable level, N_1 the population of the ground level, and $N_t = N_2 + N_1$ the total population. $D = +1$ when the metastable level is fully populated and $D = -1$ when only the ground level is populated.

A simple approach for calculating the gain (G) with erbium-doped fiber amplifiers (EDFA) is given, in decibel units, by

$$G(\lambda) = \big((\alpha(\lambda) + g(\lambda)\big)\frac{D+1}{2} - \alpha(\lambda)L \qquad [8]$$

where λ is the wavelength of the signal, α the absorption coefficient in dB unit length at the signal wavelength, g the emission coefficient in dB unit length at the signal wavelength, and L the length of the erbium-doped fiber (EDF). Here D is the normalized path-average medium inversion of the EDF.

The gain per unit length, $G(\lambda)/L$, is equal to $g(\lambda)$ for $D = +1$ and to $-\alpha(\lambda)$ for $D = -1$.

The absorption and the emission coefficients depend on the EDF host material and the codoping element used for the realization of the EDF. With silicate EDF the most commonly used codoping elements are germanium, aluminum, and phosphorus.

In Figure 3 we show the dependence of the gain per unit length on the normalized path-average medium inversion, for a signal wavelength ranging from 1500 to 1560 nm.

For a more comprehensive description of the EDFA characteristics we use the standard confined-doping model. This model, which is also based on the two-level system, uses the following differential equations:

$$\frac{\mathrm{d}P_S^+(z)}{\mathrm{d}z} = \left(\frac{N_2}{N_t}(\alpha_S + g_S) - \alpha_s\right)P_S^+(z) \qquad [9]$$

$$\frac{\mathrm{d}P_{ASE}^+(z)}{\mathrm{d}z} = \left(\frac{N_2}{N_t}(\alpha_S + g_S) - \alpha_s\right) \times P_{ASE}^+(z) + \frac{N_2}{N_t}g_S 2h\nu_S\Delta\nu \qquad [10]$$

$$\frac{\mathrm{d}P_{ASE}^-(z)}{\mathrm{d}z} = \left(\alpha_s - \frac{N_2}{N_t}(\alpha_S + g_S)\right) \times P_{ASE}^-(z) - \frac{N_2}{N_t}g_S 2h\nu_S\Delta\nu \qquad [11]$$

$$\frac{\mathrm{d}P_P^+(z)}{\mathrm{d}z} = \left(\frac{N_2}{N_t}(\alpha_P + g_P) - \alpha_P\right)P_P^+(z) \qquad [12]$$

$$\frac{\mathrm{d}P_P^-(z)}{\mathrm{d}z} = \left(\alpha_P - \frac{N_2}{N_t}(\alpha_P + g_P)\right)P_P^-(z) \qquad [13]$$

where $P_S(z)$, $P_{ASE}(z)$, and $P_P(z)$ in W are, respectively, the signal power, the ASE power, and the pump power along the length (z-axis) of the EDF; $^+$ and $^-$ indicate, respectively, the backward-traveling and the forward-traveling directions; α_s and α_P in m^{-1} are the absorption coefficients at, respectively, the signal and pump wavelengths, g_s and g_p in m^{-1} are the emission coefficients at, respectively, the signal and pump wavelengths, ν_s and ν_p are the frequencies of, respectively, the signal and the pump beams; $\Delta\nu$ is the frequency bandwidth of the ASE; and h is the Planck's constant. N_2/N_1 is the medium inversion along the z-axis of the EDF, and is given by

$$\frac{N_2}{N_t} = \frac{\sum_k \dfrac{P_k(z)\alpha_k\tau}{h\nu_k B_{\mathrm{eff}}^2 N_t}}{1 + \sum_k \dfrac{P_k(z)(\alpha_k + g_k)\tau}{h\nu_k B_{\mathrm{eff}}^2 N_t}} \qquad [14]$$

where the index k represents all the beams, i.e., signal, ASE, and pump, traveling backward and forward along the EDF, τ is the lifetime of the metastable level, and B_{eff} is the effective erbium-doping area. For a typical silicate EDF, having a peak absorption coefficient of 1 dBm^{-1}, we have $\tau = 10$ ms, $B_{\mathrm{eff}} = 12\ \mu m^2$, and $N_t = 5 \times 10^{23}\ m^{-3}$.

Using the standard confined-doping model we calculate the dependence of the EDFA noise figure on the normalized path-average medium inversion, as shown in Figure 4. We vary the path-average normalized medium inversion by changing the length of the EDFA, while adjusting the pump power so that the signal gain is kept constant.

The noise figure decreases when the medium inversion increases, and approaches the quantum limit value of 3 dB when the path-average normalized medium inversion is close to unity. Near full inversion



Figure 3 Dependence of the gain per unit length on the normalized path-average medium inversion, D. D ranging from −1 to +1 with a 0.2 step (alumino-silicate EDF; peak absorption of 1 dB m^{-1}; peak emission of 0.93 dB m^{-1}).



Figure 4 Dependence of the noise figure on the normalized medium inversion (alumino-silicate EDF with peak absorption of 1 dB m^{-1}; EDF lengths ranging from 16 m to 60 m; gain equals to 15 dB; input signal power of −40 dBm at 1530 nm; backward pumping at 980 nm).

may be obtained with a pump located at 0.98 μm because the emission coefficient is null at this pump wavelength. However, this is not the case at 1.48 μm where the ratio g_p/α_p is about 0.3. The maximum medium inversion that can be obtained with 1480 nm is $D = 0.8$. Therefore, higher noise figures are obtained with 1.48 μm pumping than with 0.98 μm pumping. The pumping direction also has an effect on the noise figure, in particular with 0.98 μm. Since at 0.98 μm the emission coefficient is null, when backward pumping configuration is used the 0.98 μm pump is quickly absorbed along the EDF length. This leads to a low-medium inversion at the input end of the EDF, resulting in high noise figures. However, in order to achieve forward pumping, a dichroic coupler must be placed at the input end of the EDF, thus inducing an additional loss at the input of the amplifier. This increases the noise figure and, therefore, to some extent, counterbalances the NF improvement associated with forward pumping.

Raman Fiber Amplifier

Stimulated Raman scattering, an optical-phonon based nonlinear effect present in silica fiber, is used to convert energy from a pump located at a frequency ν_p, to a signal located at a lower frequency ν_s. The efficiency of the so-called Raman amplification depends on the frequency shift $\Delta\nu_r = \nu_p - \nu_s$. Figure 5 shows the dependence of the Raman gain on the frequency shift in standard single-mode fibers. The exact Raman gain spectrum depends on the doping elements used during the fabrication process of the fiber. With standard telecommunications fibers the Raman gain is maximum for $\Delta\nu_r$ close to 13 THz.

Raman amplification can be achieved within the transmission fiber of the system – distributed amplification – or within a specific fiber, such as a dispersion compensation fiber – discrete amplification. Contrary to EDFA, Raman amplification has a very fast response time – in the order of a few hundred femtoseconds – and is strongly dependent on the polarization state of the signal and the pump, the highest gain efficiency being obtained when the polarization states of the signal and the pump are parallel. Because of the nonpolarization-maintaining nature of standard telecommunications fibers, depolarized pump sources are preferable for Raman amplification. To avoid pump fluctuation being transferred to the signal, Raman amplifiers generally use backward pumping, which virtually averages the fluctuation. Forward pumping can also be employed with Raman amplifiers but with careful control of the pump characteristics.



Figure 5 Raman gain spectrum in standard single mode fiber.

If the signal is sufficiently low the pump depletion can be neglected. In that case the gain of the Raman amplifier is given by

$$G = \exp\left(\frac{g_R P_P}{A_{\text{eff}}\alpha_p}\left(1 - \exp^{-\alpha_p L}\right) - \alpha_S L\right) \qquad [15]$$

where P_p is the launched pump power, L is the length of the fiber, g_R is the Raman gain coefficient, and A_{eff} is the effective area of the fiber. We assume for the simulation examples given in this article that the peak value of g_R is equal to 6×10^{-14} m/W.

A more comprehensive model for Raman amplification is given by the following set of differential equations:

$$\frac{dP_S^+(z)}{dz} = -\alpha_s P_S^+(z) + \left(\frac{g_R}{A_{\text{eff}}}\right)\left(P_p^+(z) + P_p^-(z)\right)P_S^+(z) + r_S P_S^-(z) \qquad [16]$$

$$\frac{dP_S^-(z)}{dz} = \alpha_s P_S^-(z) - \left(\frac{g_R}{A_{\text{eff}}}\right)\left(P_p^+(z) + P_p^-(z)\right)P_S^-(z) - r_S P_S^+(z) \qquad [17]$$

$$\frac{dP_{\text{ASE}}^+(z)}{dz} = -\alpha_s P_{\text{ASE}}^+(z) + \left(\frac{g_R}{A_{\text{eff}}}\right)\left(P_p^+(z) + P_p^-(z)\right) \times \left[P_{\text{ASE}}^+(z) + 2h\nu_S\Delta\nu\right] + r_S P_{\text{ASE}}^-(z) \qquad [18]$$

$$\frac{dP_{\text{ASE}}^-(z)}{dz} = \alpha_s P_{\text{ASE}}^-(z) - \left(\frac{g_R}{A_{\text{eff}}}\right)\left(P_p^+(z) + P_p^-(z)\right) \times \left[P_{\text{ASE}}^-(z) + 2h\nu_S\Delta\nu\right] - r_S P_{\text{ASE}}^+(z) \qquad [19]$$

$$\frac{dP_p^+(z)}{dz} = -\alpha_p P_p^+(z) - \left(\frac{\nu_P}{\nu_S}\right)\left(\frac{g_R}{A_{\text{eff}}}\right)P_p^+(z) \times \left(P_S^+(z) + P_S^-(z) + P_{\text{ASE}}^+(z) + P_{\text{ASE}}^-(z)\right) + r_P P_p^-(z) \qquad [20]$$



Figure 6 Evolution of the signal power and pump power along fiber length with Raman amplification (standard single-mode fiber; fiber length of 15 km; input signal power of −10 dBm at 1550 nm; forward pumping with 400 mW at 1450 nm; total amplifier gain of 9.5 dB).



Figure 7 Dependence of the Raman amplifier gain and the noise figure on the pump power (standard single-mode fiber; fiber length of 15 km; input signal power of −10 dBm at 1550 nm; forward pumping at 1450 nm with power ranging from 100 mW to 800 mW).

$$\frac{\mathrm{d}P_{\mathrm{p}}^{-}(z)}{\mathrm{d}z} = \alpha_{\mathrm{p}} P_{\mathrm{p}}^{-}(z) + \left(\frac{\nu_{\mathrm{p}}}{\nu_{\mathrm{S}}}\right)\left(\frac{g_{\mathrm{R}}}{A_{\mathrm{eff}}}\right) P_{\mathrm{p}}^{-}(z) \times \left(P_{\mathrm{S}}^{+}(z) + P_{\mathrm{S}}^{-}(z) + P_{\mathrm{ASE}}^{+}(z) + P_{\mathrm{ASE}}^{-}(z)\right) - r_{\mathrm{P}} P_{\mathrm{p}}^{+}(z) \qquad [21]$$

where r_{S} and r_{p} are the Rayleigh backscattering coefficients at, respectively, the signal wavelength and the pump wavelength.

An example of the evolution of the signal power and pump power along fiber length is given by Figure 6.

Figure 7 shows the dependence of the Raman amplifier gain and noise figure on the pump power.

Distributed and Discrete Amplification

A system uses distributed amplification when the transmission fiber is used as the medium for generating the optical signal amplification. It uses discrete amplification when an optical amplifier is located between the transmission fiber spans.

Discrete Amplification

Both EDFA and Raman amplifiers can be used to provide discrete amplification. Discrete amplifiers can be used as booster, pre-amplifier, or in-line amplifier. They can also be used to compensate for the loss of additional elements such as DCM, which may be located between the fiber spans. In Figure 8 we show the path of the signal when a discrete amplification is used to compensate for the loss of the transmission fiber and for the loss of a DCM. In this example, we assume that the discrete amplifier is made of two amplifiers. The first-stage amplifier compensates mainly for the loss of the transmission fiber, while the second-stage amplifier compensates mainly for the loss of the DCM.

If a 'lossy' element is inserted between two amplifiers, the noise figure of the composite amplifier increases the total noise figure of the dual-stage amplifier.

The total noise figure of a dual-stage amplifier, $\mathrm{NF}_{\mathrm{total}}$, is given by

$$\mathrm{NF}_{\mathrm{total}} = \mathrm{NF}_1 - \frac{1}{G_1} + \frac{\mathrm{NF}_2}{G_1 T_{\mathrm{mid}}} \qquad [22]$$

where NF_1 is the noise figure of the first-stage amplifier, G_1 is the gain of the first-stage amplifier, NF_2 is the noise figure of the second-stage amplifier, and T_{mid} is the loss of the optical element inserted between the two amplifiers ($T_{\mathrm{mid}} < 1$).

Distributed Amplification

When fibers are deployed it is generally assumed, at least for terrestrial networks, that it can be used with different types of transmission systems, which may or



Figure 8 Schematic of a transmission system using discrete amplification to compensate for the loss of the transmission fiber and the dispersion compensating module.



Figure 9 Schematic of a transmission system using distributed Raman amplification.

may not use distributed amplification. Doping the transmission fiber with erbium is not a practical solution since the absence of a pump would result in high fiber loss. On the other hand, Raman amplification can be achieved with conventional fibers, and is consequently the preferred solution to generate distributed amplification. Raman amplification is then obtained by launching a pump signal into the transmission fiber. Figure 9 shows the schematic of a transmission system using distributed Raman amplification with backward pumping.

Even if distributed amplification can be used to compensate fully for the loss of the transmission fiber, discrete amplifiers are generally required to compensate for the loss of the transmitter and receiver terminals. In order to compare distributed amplification with discrete amplification we define the equivalent noise figure as follows:

$$\mathrm{NF}_{\mathrm{Equ}} = \frac{1}{G_{\mathrm{On/Off}}}\left(\frac{\mathrm{Pase}}{h\nu\Delta\nu} + 1\right) \qquad [23]$$

where Pase is the total ASE power at the output end of the transmission fiber and where the on/off gain, $G_{\mathrm{On/Off}}$ is given by

$$G_{\mathrm{On/Off}} = \frac{P_{\mathrm{signal}}^{\mathrm{On}}}{P_{\mathrm{signal}}^{\mathrm{Off}}} \qquad [24]$$

where $P_{\mathrm{signal}}^{\mathrm{On}}$ and $P_{\mathrm{signal}}^{\mathrm{Off}}$ are the signal power levels at the output end of the transmission fiber when the distributed amplifier is, respectively, turned on and off.

To illustrate the meaning of the on/off gain, we show in Figure 10 the evolution of the signal power along a fiber with and without Raman pump power. In this case, the on/off gain is 20 dB.

The equivalent noise figure, which has no real physical meaning, is equal to the noise figure of an imaginary discrete amplifier that would be located at the output end of the transmission fiber and would lead to the same OSNR. Figure 11 shows the dependence of the equivalent noise figure on the Raman gain, with no Rayleigh backscattering and with a Rayleigh backscattering level of -74 dB m^{-1}.



Figure 10 Evolution of signal power along the fiber length with and without pump power (standard single-mode fiber; fiber length of 100 km; fiber attenuation of 0.2 dB/km at signal wavelength; input signal power of 0 dBm at 1550 nm; backward pumping 400 mW at 1450 nm).

Once the on/off gain is higher than ~10 dB the equivalent noise figure becomes negative and it decreases when the on/off gain further increases. However, once the on/off is higher than 20 dB, Rayleigh backscattering limits the minimum equivalent noise figure that can be achieved. The lowest equivalent noise figure is observed for an on/off gain of ~33 dB. In addition, Rayleigh backscattering causes the reflected portion of the signal to be superimposed onto the transmitted signal, leading to multipath interference (MPI), which level increases with the gain. This results in an additional source of noise for the signal, and consequently degrades the system performance.

Hybrid Amplification

Discrete and distributed amplification can be used simultaneously in a same-transmission system. An example of the evolution of the signal power with hybrid amplification is represented in Figure 12, for the case where distributed Raman amplification and a dual-stage discrete amplifier are used to compensate for the loss of the transmission fiber and for the loss of a DCM.



Figure 11 Equivalent noise figure versus distributed on/off gain (standard single-mode fiber; fiber length of 250 km; fiber attenuation of 0.2 dB/km at 1550 nm; input signal power of 0 dBm at 1550 nm; backward pumping ranging from 0 to 1 W at 1450 nm).



Figure 12 Evolution of the signal power using discrete and distributed amplification (standard single-mode fiber of 100 km; fiber loss of 20 dB at signal wavelength; DCM loss of 8 dB; input signal power of 0 dBm at 1550 nm; Raman backward pumping with 200 mW at 1450 nm; Raman on/off gain of 10 dB).

Similar to the case of distributed amplification, the total equivalent noise figure of a hybrid amplifier can be defined by

$$\mathrm{NF}_{\mathrm{Equ}}^{\mathrm{Total}} = \mathrm{NF}_{\mathrm{Equ}}^{\mathrm{Distributed}} + \frac{\mathrm{NF}^{\mathrm{Discrete}} - 1}{G_{\mathrm{On/Off}}} \qquad [25]$$

where $\mathrm{NF}_{\mathrm{Equ}}^{\mathrm{Distributed}}$ is the equivalent noise figure of the distributed amplifier and $\mathrm{NF}^{\mathrm{Discrete}}$ is the noise figure of the discrete amplifier.

In Figure 13 we show the dependence of the total equivalent noise figure on the on/off gain for a hybrid amplifier with fixed discrete noise figure. The dependence of the distributed equivalent noise figure on the on/off gain is also plotted on the same graph.

Since the equivalent noise figure of the distributed amplifier is relatively low, the total equivalent noise figure is lower than the noise figure of the discrete amplifier once distributed amplification is used. Moreover, as the on/off gain becomes large, the total equivalent noise figure of the hybrid amplifier converges toward the distributed equivalent noise figure.

Wavelength-Division Multiplexing

The transmission of WDM signals over long distances requires meticulous control of the spectral characteristics of the amplifier gain. The amplifier gain excursion induces a power excursion between the channels of the WDM signal, which increases with the number of spans. Consequently, the available bandwidth for WDM transmission narrows with the total distance of the link. This is illustrated in Figure 14, where the power excursion observed after an amplifier chain is plotted for different numbers of amplifiers, a fiber span being included between each amplifier. With this example, the 1 dB-bandwidth drops from 9 nm after one span to 1.5 nm after 50 spans.

For a comprehensive analysis of the spectral gain characteristic of EDFA and Raman amplifiers we generalize the single-channel model described in the amplifier section of this article to the multichannel case. The generalization of the models is obtained by adding a frequency dimension to each beam propagating in the amplifier, as described in Table 1, where each k element represents the signal, the ASE noise or the pump, λ is the wavelength of the kth beam, $\Delta\nu$ is the frequency separation between the pump beam p, and the signal beam s.



Figure 13 Total noise figure of the hybrid amplifier and noise figure of the distributed amplifier versus on/off gain (noise figure of the discrete amplifier equals to 5 dB; standard single-mode fiber of 100 km; fiber loss of 20 dB at signal wavelength; input signal power of 0 dBm at 1550 nm; Raman backward pumping ranging from 0 mW to 600 mW at 1450 nm).



Figure 14 Dependence of the power excursion on the number of fiber spans. Number of spans equals, respectively, to 1, 2, 5, 10, 20, 30, 40, and 50 (amplifier with 15 m long alumino-silicate EDF; peak absorption of 1 dB m^{-1}; $D = 0.6$; fiber loss of 8.5 dB; flat fiber loss spectrum).

Table 1 Correspondence between parameters used for the EDFA and Raman amplifier models with the single-channel and the multichannel approaches (the multichannel approach is also used to describe the power evolution of pump beam when WDM pump scheme is used)

	Single-channel model	*Multichannel model*
Power	$P_k^{+,-}(z)$	$P_k^{+,-}(\lambda, z)$
Sum of power	$P_k^{+}(z)$ $+P_k^{-}(z)$	$\sum_\lambda P_k^{+}(\lambda, z)$ $+P_k^{-}(\lambda, z)$
Absorption coefficient	α_k	$\alpha(\lambda)$
Emission coefficient	g_k	$g(\lambda)$
Raman gain coefficient	g_R	$g_R(\Delta\nu_{p,s})$

With EDFAs, the main factors in the gain flatness are the path-average medium inversion, the EDF codopant composition, and fiber host material. Depending on the bandwidth and the wavelength of the WDM signal, the way the EDF is optimized may vary.

In the following example, we focus on the path-average medium inversion for the case of C-band applications. Figure 15 shows the output spectrum of a WDM signal amplified by an alumino-silicate EDFA having, respectively, a medium inversion of $D = +0.4$ and $D = 0$. The peak-to-peak gain excursion is, respectively, 2 dB and 14 dB for $D = +0.4$ and $D = 0$.

Application with C-band WDM signals requires amplifiers operating with high-medium inversion. As can be extrapolated from Figure 15, if the WDM signal is centered around 1560 nm, a lower medium inversion is more suitable. Indeed, as shown in Figure 3, when the medium inversion is close to zero the peak gain wavelength changes from 1530 nm to 1560 nm and higher; the optical window for L-band applications.

Regarding the doping elements, we show in Figure 16 the gain spectrum for a germano-silicate and an alumino-silicate EDF, respectively. The peak-to-peak gain excursion is 8 dB with the germano-silicate EDF compared to 2 dB with the alumino-silicate EDF.

With Raman amplifiers, the gain flatness can be adjusted by using wavelength-multiplexed pumps. In Figure 17 we show the power spectrum when a Raman amplifier is pumped with three wavelength-multiplexed pumps located, respectively, at 1430 nm, 1455 nm, and 1480 nm. The maximum power excursion between the channels is 2 dB.

For comparison, we also show in Figure 18 the power spectrum of the Raman amplifiers when only



Figure 15 Gain spectrum of an alumino-silicate EDF for $D = 0.4$ and $D = 0$ (C-band WDM signal made of 7 channels equally spaced ranging from 1530 nm to 1560 nm; flat input power of −10 dBm per channel; gain of channel located at 1545 nm of 10 dB for $D = 0.4$ and $D = 0$; EDF with peak absorption of 1 dB m^{-1}; EDF length of 30 m for $D = 0.4$; EDF length of 100 m for $D = 0$).



Figure 16 Gain spectrum of an alumino-silicate EDF and of a germano-silicate EDF for $D = 0.4$ (C-band WDM signal made of 7 channels equally spaced ranging from 1530 nm to 1560 nm; flat input power of −10 dBm per channel; gain of channel located at 1545 nm of 10 dB for $D = 0.4$ and $D = 0$; alumino-silicate EDF of 30 m with peak absorption of 1 dB m^{-1}; germano-silicate EDF of 40 m with peak absorption of 1 dB m^{-1}).



Figure 17 Output power spectrum of a Raman amplifier pumped with three wavelength-multiplexed pumps (standard single-mode fiber of 100 km; WDM signal made of 6 channels equally spaced ranging from 1530 nm to 1580 nm; pumping in forward direction with 100 mW per pump located at 1430 nm, 1455 nm, and 1480 nm).



Figure 18 Output power spectrum of Raman amplifiers pumped at three different wavelengths (standard single-mode fiber of 100 km; WDM signal made of 6 channels equally spaced ranging from 1530 nm to 1580 nm; pumping in forward direction with 300 mW at, respectively, 1430 nm, 1455 nm, and 1480 nm).

one of the three multiplexed pumps is used, with the same total pump power. The power excursion becomes 10 dB for the 1430 nm pump, 7 dB for the 1455 nm pump, and 8.5 dB for the 1480 nm pump, which are much higher values than are obtained with the multiplexed pump scheme.

To further reduce the gain excursion of the amplifiers an external gain equalizing filter can be used. The filter, which is located next to the amplifier, is manufactured so that its attenuation spectrum matches the gain spectrum of amplifier, as illustrated in Figure 19. Gain equalizing filters are generally made with thin film filters or fiber Bragg gratings (FBG).

In order to obtain amplification over ultra-wide bandwidths, amplifiers of smaller bandwidths, e.g., C-band and L-band EDFAs, can be operated in parallel by means of Mux and Demux. Another option is to use a Raman amplifier with multiple pumps having their wavelengths distributed over a very large bandwidth.

Long-Haul Transmission System Types

Long-haul optical transmission systems are appropriate for different types of applications. We distinguish here three types of transmission system: the submarine systems; the terrestrial systems; and the unrepeatered systems. Each of these applications requires a careful design of the system, with particular attention to the optical amplifiers. In this section we focus on the key points of their design.

Submarine Systems

Submarine systems are used to transmit information across the oceans, i.e., over distances of up to several thousand kilometers. The transmission fiber and the in-line optical amplifiers, which are packaged in the repeater modules, are deployed undersea at the same time. The drastic constraints imposed on the reliability of the repeaters lead to their high cost, and consequently minimizing their number in a link is essential. The optimum span length, and therefore the number of in-line amplifiers, depends on the total distance of the transmission system. To illustrate this point, we derive from eqn [6] which number of spans of a particular length can be used for a given received OSNR, launched signal power, amplifier noise figure, and span loss per km. Based on the number of spans and span length, we then calculate the maximum distance that can be reached. The result is represented in Figure 20.

With the assumption made here regarding the amplifier characteristics, in order to reach distances of more than 5000 km, span lengths close to 50 km are required.

Terrestrial Systems

Terrestrial systems are used to connect traffic from cities to cities and from cities to submarine-system landing sites. Their total distances vary from a few hundred kilometers to several thousand kilometers. Generally with terrestrial systems, the deployments of the transmission fibers and the transmission systems are done at different times. During its lifetime, the same fiber plant might be used with a different generation of transmission system. Furthermore, because of the geographical constraints that can be imposed on the



Figure 19 Combination of optical amplifier and gain equalizing filter to provide a flat gain amplifier.



Figure 20 Dependence of the maximum distance and span number of a system on its span length (signal power at the output of the amplifier of −2 dBm; amplifier noise figure of 5 dB; fiber loss of 0.2 dB/km; required OSNR of 20 dB/0.1 nm).

locations of the terminals and the in-line optical amplifiers, the different span lengths may greatly vary in a given link. Consequently, an important characteristic of the terrestrial systems is their capability to operate with different span parameters.

For terrestrial systems using large numbers of WDM channels, maintaining the gain excursion of the optical amplifiers as little as possible under different operating conditions is crucial. Approaches to limit the gain excursion under these variations can be taken. With EDFAs of a given length, the medium inversion depends on its operating gain. The EDFA can be forced to operate at constant gain, independent of the span loss, by adding an adjustable attenuator to the amplifier, e.g., in the middle of a dual-stage amplifier, such that the sum of the attenuator loss and the span loss remains constant. With Raman amplifiers, the control of the gain excursion can be realized by adjusting the power of the pumps when a wavelength-multiplexed pumping scheme is used. Another possibility is to insert dynamically adjustable gain flattening devices along the link. The automatic adjustment of the gain flatness requires the need of a feedback generally provided by an optical channel power monitor.

Unrepeatered Systems

Unrepeatered systems are used to connect mainland sites separated by a water area, such as islands or cities located on the coast. Their main characteristic is that they do not use any electronic component along the transmission fiber; therefore optical amplifiers cannot be placed under water. The length of such systems is typically of a few hundred kilometers, meaning that, even for those systems where very low loss fiber is used, the loss of the transmission fiber is in the order of several tens of dB. To allow sufficiently high OSNR at the receiver, several options can be used. Among them are the use of very high-power boosters, distributed Raman amplification, and remotely pumped discrete amplification. Remote amplification is obtained by inserting, along the submerged fiber cable, a piece of EDF. A 1.48 μm pump is launched into the EDF from the mainland via the transmission fiber or via a dedicated fiber running along the transmission fiber. Figure 21 shows a schematic of a possible configuration for unrepeatered systems when a very high-power booster, distributed Raman amplification, and remote discrete amplification are used simultaneously.



Figure 21 Schematic of unrepeatered systems using high-power booster, remote EDFA, and distributed Raman amplification.

The total equivalent noise figure, $\mathrm{NF}_{\mathrm{Equ}}^{\mathrm{Total}}$, of an unrepeatered transmission system, using remote discrete amplification and distributed amplification, is given by

$$\mathrm{NF}_{\mathrm{Equ}}^{\mathrm{Total}} = T\mathrm{NF}^{\mathrm{Remote}} + \frac{1}{G_{\mathrm{Remote}}} \times \left(\mathrm{NF}_{\mathrm{Equ}}^{\mathrm{Distributed}} + \frac{\mathrm{NF}^{\mathrm{Discrete}} - 1}{G_{\mathrm{On/Off}}} - T \right) \qquad [26]$$

where $\mathrm{NF}^{\mathrm{Remote}}$ and G_{Remote} are, respectively, the noise figure and the gain of the remote amplifier; T is the loss of the transmission fiber between the remote amplifier and the pre-amplifier ($T < 1$); $\mathrm{NF}_{\mathrm{Equ}}^{\mathrm{Distributed}}$ and $G_{\mathrm{On/Off}}$ are, respectively, the equivalent noise figure and on/off gain of the distributed amplifier; and $\mathrm{NF}^{\mathrm{Discrete}}$ is the noise figure of the pre-amplifier.

Assuming that the gain and noise figures of the remote EDFA are, respectively, 10 dB and 7 dB, that the remote EDFA is located at 100 km from the pre-amplifier, that the fiber loss per km is 0.2 dB/km, that the Raman distributed amplifier provides 30 dB of on/off gain with an equivalent noise figure of −3 dB, and that the pre-amplifier noise figure is 5 dB, the equivalent total noise figure of the unrepeatered system is −10 dB.

List of Units and Nomenclature

A_{eff}	effective area
ASE	amplified spontaneous emission
B_{eff}	effective erbium doping area
D	normalized medium inversion
dB	ratio in decibel
dBm	power in decibel
DBR	distributed Bragg reflector
DCM	dispersion compensating modules
Demux	optical de-multiplexers
DFB	distributed feedback
DSF	dispersion-shifted fiber
EDF	erbium-doped fiber
EDFA	erbium-doped fiber amplifiers
FBG	fiber Bragg gratings
g_{R}	Raman gain coefficient
G	gain
$G_{\mathrm{On/Off}}$	on/off gain
h	Planck's constant
Length	meter (m)
MPI	multi-path interference
Mux	optical multiplexers
n_{eq}	equivalent input noise factor
NF	noise figure of the amplifier
NRZ	non-return to zero
NZDSF	non-zero dispersion shifter fiber
N_2/N_1	medium inversion
OSNR	optical signal-to-noise ratio
Power	watt (W)
SSMF	standard single-mode fiber
TDM	time-division multiplexing
Time	second (s)
WDM	wavelength-division multiplexing
τ	lifetime

See also

Coherent Lightwave Systems. **Dispersion Management**. **Fiber and Guided Wave Optics:** Nonlinear Effects (Basics). **Optical Amplifiers:** Basic Concepts; Erbium Doped Fiber Amplifiers for Lightwave Systems; Raman, Brillouin and Parametric Amplifiers.

Optical Communication Systems: Architectures of Optical Fiber Communication Systems; Basic Concepts; Historical Development; Lightwave Transmitters; Optical Time Division Multiplexing; Wavelength Division Multiplexing. **Solitons:** Soliton Communication Systems.

Further Reading

Agrawal G (2001) *Nonlinear Fiber Optics*. London: Academic Press.

Chesnoy J (2002) *Undersea Fiber Communication Systems*. London: Academic Press.

Desurvire E (1994) *Erbium-Doped Fiber Amplifiers, Principles and Applications*. New York: John Wiley & Sons.

Desurvire E, Bayart D, Desthieux B and Bigo S (2002) *Erbium-Doped Fiber Amplifiers, Device and System Developments*. New York: John Wiley & Sons.

Emori Y, Kado S and Namiki S (2002) Broadband flat-gain and low-noise Raman amplifiers pumped by wavelength-multiplexed high-power laser diodes. *Optical Fiber Technology* 8: 107.

Hansen PB and Eskildsen L (1997) Remote amplification in repeaterless transmission systems. *Optical Fiber Technology* 3: 221.

Islam MN (2004) *Raman Amplifiers for Telecommunications*. New York: Springer-Verlag.

Kaminow I and Li T (2002) *Optical Fiber Telecommunications IV*. London: Academic Press.

Keiser G (2000) *Optical Fiber Communications*. New York: McGraw-Hill.

Raman, Brillouin and Parametric Amplifiers

M F S Ferreira, University of Aveiro, Aveiro, Portugal

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Glass fibers for optical communications are made of fused silica, an amorphous material, to which dopant materials of various kinds can be added to produce changes in refractive index. A number of third-order nonlinear processes can occur; these can grow to appreciable magnitudes over the long lengths available in fibers, even though the nonlinear coefficients in the materials are relatively small. The effects are particularly important in single-mode fibers, in which the small mode field dimensions result in substantially high light intensities with relatively modest input powers.

Nonlinear optical effects, such as stimulated Raman scattering (SRS), stimulated Brillouin scattering (SBS), and four-wave mixing (FWM), can cause some problems such as nonlinear loss, pulse distortion, and cross-talk between signals in wavelength division multiplexed (WDM) transmission systems. However, these effects are also useful for efficient amplification and frequency conversion of injected signals, as well as for generation of new frequencies. In this chapter the main properties of fiber Raman amplifiers (FRAs), fiber Brillouin amplifiers (FBAs), and fiber parametric amplifiers (FPAs) will be reviewed, regarding their applications in the field of fiber optic communications.

Fiber Raman Amplifiers

Stimulated Raman scattering is likely to occur in fibers, producing appreciable amplification for down-shifted signals when moderate pump power levels are used. This is largely because the process is phase-matched, so that the long interaction lengths available in fibers will enhance the process. Additionally, the small mode field cross-section yields high intensities for relatively modest power levels.

In the SRS process one has simultaneously the absorption of a photon from the pump beam at frequency ω_p and the emission of a photon at the signal (Stokes) frequency, stimulated by the incident signal beam at frequency ω_s (Figure 1a). The difference in energy is taken up by a high energy



Figure 1 (a) Energy-level illustration of the process of stimulated Raman scattering and (b) schematic diagram of a fiber Raman amplifier.

phonon (molecular vibration) at frequency ω_v. Thus, SRS provides for energy gain at the signal frequency at the expense of the pump.

Figure 1b shows schematically a fiber Raman amplifier. The pump and the signal beams are injected into the fiber through a WDM fiber coupler. The case illustrated in Figure 1a shows the two beams co-propagating inside the fiber, but the counter-propagating configuration is also possible. In fact, the SRS can occur in both directions, forwards and backwards. It was confirmed experimentally that the Raman gain is almost the same in both cases.

Raman Gain and Bandwidth

Figure 2 shows the Raman gain coefficient for fused silica as derived from the spontaneous Raman spectrum. At the peak, the Raman gain coefficient for silica fibers is 9.4×10^{-14} m W^{-1} for a pumping wavelength $\lambda_p = 1.0\ \mu m$ and varies as λ_p^{-1}. At this wavelength, a shift of 15 THz corresponds to 50 nm. The most significant feature of the Raman gain in silica fibers is that $\bar{g}_R$ extends over a large frequency range (up to 40 THz) with a broad dominant peak near 13 THz. This behavior is due to the amorphous nature of silica glass, whose molecular vibrational energy levels merge together to form a band.

The use of oxide glasses as dopants for fiber fabrication is suitable to enhance the Raman gain coefficient. For example, in the case of pure GeO_2, the Raman gain coefficient is about 9.2 times that for pure SiO_2 glass. In fact, doping the core of an SiO_2 Raman fiber amplifier with GeO_2 has two beneficial effects. First, the index difference Δ is raised, which increases the effective waveguiding and in turn reduces the effective cross-sectional area A_e. As a consequence, the rate of SRS is increased. Secondly, the Raman gain coefficient increases above that of pure SiO_2 in proportion to the concentration GeO_2, and is given by

$$g_R = (1 + 80\Delta)\bar{g}_R \qquad [1]$$

where $\bar{g}_R$ is the Raman coefficient for pure SiO_2.

In spite of the positive aspects mentioned above, doping with GeO_2 also increases the fiber losses, due to the concomitant rise in Rayleigh scatter and in the number of dopant-dependent loss centers. Thus, greatly increasing the GeO_2 concentration will not be worthwhile if the increased fiber losses outweigh the improvement in amplifier gain.



Figure 2 Measured Raman gain spectrum for fused silica at a pump wavelength $\lambda_p = 1.0\ \mu m$. The Raman gain scales inversely with λ_p. Reproduced with permission from Stolen RH and Ippen EP (1973) *Applied Physics Letters* 22: 276. © 1973 American Institute of Physics.

Gain Saturation

The interaction between the pump and Stokes waves is governed by the following coupled equations:

$$\frac{dP_s}{dz} = -\alpha_s P_s + \frac{g_R}{A_e} P_p P_s \qquad [2]$$

$$\frac{dP_p}{dz} = -\alpha_p P_p - \frac{\omega_p}{\omega_s}\frac{g_R}{A_e} P_s P_p \qquad [3]$$

where A_e is the effective cross-sectional area of the fiber mode, α_s and α_p are absorption coefficients which account for the fiber loss at the signal and pump frequencies, respectively, and the signal wave is considered to be co-propagating with the pump wave. Assuming that $\alpha_s = \alpha_p = \alpha$ (which is a reasonable approximation around the 1.5 μm wavelength region in a low loss fiber), the following approximate solutions of eqns [2] and [3] can be written when $P_p(0) \gg P_s(0)$:

$$P_p(z) = \frac{P_p(0)\exp(-\alpha z)}{1 + F(z)} \qquad [4]$$

$$P_s(z) = \frac{P_s(0)\exp(\Gamma(1 - e^{-\alpha z}) - \alpha z)}{1 + F(z)} \qquad [5]$$

where

$$\Gamma = \frac{g_R P_p(0)}{\alpha A_e} \qquad [6]$$

and

$$F(z) = \frac{\omega_p P_s(0)}{\omega_s P_p(0)} \exp(\Gamma(1 - e^{-\alpha z})) \qquad [7]$$

The dimensionless parameter $F(z)$ accounts for the effects of pump depletion and the attendant saturation of the gain seen by the signal.

Figure 3 shows the output signal power $P_s(L)$ versus the input signal power $P_s(0)$ for a Raman amplifier with length $L = 8$ km and several values of the input pump power. Typical values $g_R = 6.7 \times 10^{-14}$ m W^{-1}, $\alpha = 0.2$ dB km^{-1}, $A_e = 30 \times 10^{-12}$ m^2, $\lambda_p = 1.46$ μm and $\lambda_s = 1.55$ μm were assumed. The transfer characteristics are linear for $P_p(0) = 0.1$, 0.2, and 0.4 W, but the effects of pump depletion become discernible for input signal levels $P_s(0) > -15$ dB m when $P_p(0) = 0.6$ W. For a pump power $P_p(0) = 0.8$ W the linear behavior of the Raman amplifier cannot be observed, even for signal power levels as low as −25 dB m.

Since, in the absence of Raman amplification, the signal power at the amplifier output would be $P_s(L) = P_s(0)\exp(-\alpha L)$, the amplifier gain is given by

$$G_R = \frac{P_s(L)}{P_s(0)\exp(-\alpha L)} = \frac{\exp(g_R P_p(0) L_e / A_e)}{1 + F(L)} \qquad [8]$$

where

$$L_e = \frac{1}{\alpha}[1 - \exp(-\alpha L)] \qquad [9]$$

is the effective interaction length and L is the actual fiber length. The gain given by eqn [8] is seen to be a function of the input signal power (i.e., a saturation nonlinearity) through the term $F(L)$.

When $F(L) \gg 1$ we have from eqn [5], that

$$P_s(L) = \frac{\omega_s}{\omega_p} P_p(0)\exp(-\alpha L) \qquad [10]$$

In this case, the amplifier output reaches the pump level irrespective of the input signal level. This implies that any spontaneous Raman scatter in the fiber will be amplified up to power levels comparable to that of the pump. This is obviously inadmissible in an amplifier application, thus this operating regime must be avoided.

On the other hand, when $F(L) \ll 1$ we have, from eqn [5], that

$$P_s(L) = P_s(0)\exp(g_R L_e P_p(0)/A_e - \alpha L) \qquad [11]$$

In this case, the amplifier gain is

$$G_R = \frac{P_s(L)}{P_s(0)\exp(-\alpha L)} = \exp(g_R L_e P_0 / A_e) \qquad [12]$$

From eqn [12], the Raman gain in decibels is expected to increase linearly with the pump input power. Raman gains were experimentally confirmed to be almost the same for forwards and backwards pumping.

Figure 4 illustrates the variation of the amplifier gain (full curves, left scale) and the saturation parameter $F(L)$ (dashed curves, right scale) with the pump power $P_p(0)$ for a fixed input signal power $P_s(0) = 0$ dBm and amplifier lengths $L = 2$, 4, and 8 km. The full curve corresponding to $L = 2$ km shows a linear dependence of the gain on the pump power. However, the other two full curves show how the pump depletion limits the achievable gain. The black point on these curves marks the value of the pump power at which the depletion parameter F



Figure 3 Transfer characteristics for a Raman amplifier with a length $L = 8$ km and several values of the input pump power.



Figure 4 Raman amplifier gain (full curves, left scale) and parameter $F(L)$ (dashed curves, right scale) against input pump power for three values of the amplifier length.

becomes equal to unity. Only operating at pump powers sufficiently below each point ensures linear operation of the amplifier, whilst choosing to operate the amplifier significantly above that point will mean $F \gg 1$ and spontaneous scatter will be amplified to intolerable levels.

Noise Light Power

The dominant noise light in fiber Raman amplification is due to the amplified spontaneously Raman scattered light. In fact, a part of the pump energy is spontaneously converted into Stokes radiation extending over the entire bandwidth of the Raman gain spectrum and is amplified together with the signal. The output thus consists not only of the desired signal but also of background noise extending over a wide frequency range (~10 THz or more).

It has been shown that, for both forwards and backwards pumpings, the noise light power is equivalent to a hypothetical injection of a single-photon per unit frequency at the fiber input end for forwards pumping, and at some distance away from the fiber output for backwards pumping. Assuming that $G_R \gg 1$ and $\alpha_L \gg 1$, the noise light powers for forwards pumping, $P_{\mathrm{fasp}}(L)$, and backwards pumping, $P_{\mathrm{basp}}(L)$, are approximately given by

$$P_{\mathrm{fasp}}(L) \approx h\nu_s \Delta\nu_R (G_R - 1)\exp(-\alpha L) \qquad [13]$$

$$P_{\mathrm{basp}}(L) \approx h\nu_s \Delta\nu_R (G_R - 1)/\ln G_R \qquad [14]$$

where $\Delta\nu_R$ is the Raman gain bandwidth, h is Planck's constant, and ν_s is the signal frequency. We can observe from eqn [13] that the noise light power in the case of forward pumping decreases as the fiber length is increased. However, in the case of backwards pumping, it depends mainly on the Raman gain, being nearly independent of fiber length and loss.

FRA Performance and Applications

One main limitation affecting the operation of fiber Raman amplifiers is the requirement of a relatively high-power laser as a pump source. The experiments near 1.55 μm are usually carried out using color-center lasers for this purpose. However, such lasers are too bulky for communication applications and the use of compact high-power laser diodes (LDs) becomes desirable. This objective has recently been achieved with the advent of high-power multimode LDs. In some cases, the output lights from various LDs are combined to attain the necessary pump power.

In a Raman amplifier, SRS has to compete frequently with other nonlinear effects. For example, since the intrinsic gain coefficient for SBS is two orders of magnitude larger than that for SRS, in some cases the SBS may occur at lower pump powers and may affect significantly the SRS process. In particular, the Raman gain may not only be reduced but also become unstable. However, the SBS can be suppressed taking into account its narrow linewidth, which is typically less than 100 MHz. Therefore, if a pump laser with linewidth broader than the Brillouin bandwidth is employed, the SBS effect would not be significant. When a semiconductor laser is used as pump source, its spectral linewidth can be artificially increased by direct frequency modulation, resulting in effective SBS suppression.

Considering its broad bandwidth (>5 THz), fiber Raman amplifiers can be used to amplify several channels simultaneously in a multichannel communication system. The same characteristic also makes such amplifiers suitable for amplification of short optical pulses.

Considering a repeaterless transmission system, the FRA can be used in three different configurations: forwards pumping, backwards pumping, and bi-directional pumping. In the first case, the signal amplification occurs near the fiber input, where the signal power is relatively high. This configuration for the Raman amplification does not generally affect the transmission quality and can compensate for the transmission loss by approximately the value of the Raman gain. For example, 10 dB Raman gain provides an increase in transmission distance of 50 km when the fiber attenuation is 0.2 dB km^{-1}. In the case of backwards pumping, the signal amplification occurs near the fiber output end before photodetection, where the signal power may be very weak, comparable with the Raman noise power. This scheme for the Raman amplification can considerably reduce the minimum detectable signal power, which results in a corresponding increase of the transmission distance. However, the transmission quality is affected due to backwards noise light. The bi-directional pumping configuration uses both forwards and backwards pumping simultaneously and its performance can be estimated from those for the respective unidirectional schemes considered above.

The FRAs can also be used in nonregenerative all-optical multirepeater systems. In this case, the transmission loss is compensated for by both forwards and backwards Raman gain providing the periodically injected pump light. This scheme can be used to overcome the fiber loss in soliton-based communication systems. In this case, the pulse broadening due to chromatic dispersion of the fiber is also eliminated, which provides the possibility of achieving ultralong distance distortionless transmission.

Fiber Brillouin Amplifiers

The process of SBS can be described as a classical three-wave interaction involving the incident (pump) wave of frequency ω_p, the Stokes wave of frequency ω_s, and an acoustic wave of frequency ω_a. The pump creates a pressure wave in the medium owing to electrostriction, which in turn causes a periodic modulation of the refractive index. This process is illustrated schematically in Figure 5. Since the acoustic wavefronts are moving away from the incident pump wave, the scattered light is shifted downward in frequency to the Stokes frequency:

$$\omega_s = \omega_p - \omega_a \qquad [15]$$

The response of the material to the interference of the pump and Stokes fields tends to increase the amplitude of the acoustic wave. Therefore, the beating of the pump wave with the acoustic wave tends to reinforce the Stokes wave, whereas the beating of the pump wave and the Stokes waves tends to reinforce the acoustic wave. This explains the appearance of the stimulated Brillouin scattering process.

In spite of the apparent similarity between SBS and SRS, these processes differ in three important aspects: i) Brillouin amplification occurs only when the pump and signal beams counter-propagate inside the fiber; ii) the Stokes shift for SBS is smaller by three orders of magnitude compared with that of SRS; and iii) the Brillouin gain spectrum is extremely narrow, with a bandwidth <100 MHz. These characteristics significantly affect the performance and the fiber Brillouin amplifiers.

Brillouin Gain and Bandwidth

Physically, each pump photon in the SBS process gives up its energy to create simultaneously a Stokes photon and an acoustic phonon. Since both the energy and the momentum must be conserved in this process, the frequencies of the three waves must satisfy eqn [15], whereas the wave vectors are related by



Figure 5 Schematic illustration of the stimulated Brillouin scattering process.

$$\vec{k}_p = \vec{k}_s + \vec{k}_a \qquad [16]$$

where $\vec{k}_p$ and $\vec{k}_s$ are the wave vectors of the pump and signal beams, respectively. The frequency ω_a and the wave vector $\vec{k}_a$ of the acoustic wave satisfy the dispersion relation:

$$\omega_a = |\vec{k}_a| v_a = 2 v_a |\vec{k}_p| \sin(\theta/2) \qquad [17]$$

where v_a is the acoustic velocity, θ is the angle between the pump and signal waves, and $|\vec{k}_p| \approx |\vec{k}_s|$ was used. Equation [17] shows that ω_a vanishes in the forward direction ($\theta = 0$), whereas it is maximum in the backward direction ($\theta = \pi$). The frequency shift ν_B in the backward direction is given by

$$\nu_B = \frac{\omega_a}{2\pi} = \frac{2 n v_a}{\lambda_p} \qquad [18]$$

where eqn [17] was used with $|\vec{k}_p| = 2\pi n/\lambda_p$, λ_p is the pump wavelength, and n is the refractive index. Considering $n = 1.45$ and $v_a = 5.96\ \text{km s}^{-1}$ as typical values for silica fibers, we obtain $\nu_B = 11.1$ GHz at $\lambda_p = 1.55\ \mu\text{m}$.

Assuming a monochromatic pump, the spectrum of the scattered light depends on the uniformity of the fiber parameters. For a uniform medium the spectrum is Lorentzian with a width $\Delta\nu_B$ determined by the acoustic attenuation. For 1.5 μm light the width is about 17 MHz. However, both the frequency shift ν_B and the gain bandwidth $\Delta\nu_B$ can vary from fiber to fiber because of the guided nature of light and the presence of dopants in the fiber core. In particular, the inhomogeneities in the core section along the length determine an increase of the amplifier bandwidth, which can exceed 100 MHz, although typical values are 50–60 MHz for $\lambda_p \approx 1.55\ \mu\text{m}$.

The peak value of the Brillouin gain coefficient is given by

$$g_B(\nu_B) = \frac{2\pi n^7 p_{12}^2 \gamma}{c \lambda_p^2 \rho_0 v_a \Delta\nu_B} \qquad [19]$$

where p_{12} is the longitudinal elasto-optic coefficient, ρ_0 the average material density, n the refractive index, c the vacuum speed of light, and γ is a numerical factor that depends on the polarization properties of the optical fiber, which assumes the value $\frac{1}{2}$ for long lengths of nonpolarization-preserving optical fiber. By using the parameter values typical of fused silica, g_B is estimated to be about $2.5 \times 10^{-11}\ \text{m W}^{-1}$, which is two orders of magnitude larger than the Raman gain coefficient at $\lambda_p = 1.55\ \mu\text{m}$.

The expression for the Brillouin gain in eqn [19] assumes that the spectral width of the pump beam ($\Delta\nu_p$) is much narrower that the Brillouin linewidth ($\Delta\nu_B$). When such condition is not verified, the Brillouin gain is reduced according with the relation:

$$\tilde{g}_B(\nu_B) = \frac{\Delta\nu_B}{\Delta\nu_B + \Delta\nu_p} g_B(\nu_B) \qquad [20]$$

For this reason, fiber Brillouin amplifiers need to be pumped by narrow-linewidth semiconductor lasers ($\Delta\nu_p < 10$ MHz).

Gain Saturation

The slowly varying steady-state Fourier amplitudes of the Stokes (E_s) and pump (E_p) electric fields are related by the following coupled-wave equations:

$$\frac{\partial E_s}{\partial z} = \left[\mathrm{j}\frac{K_1 K_2 |E_p|^2}{\delta - \mathrm{j}\Gamma} + \frac{\alpha}{2} \right] E_s \qquad [21]$$

$$\frac{\partial E_p}{\partial z} = -\left[\mathrm{j}\frac{K_1 K_2 |E_s|^2}{\delta + \mathrm{j}\Gamma} + \frac{\alpha}{2} \right] E_p \qquad [22]$$

where Γ^{-1} is the acoustic phonon lifetime resulting in a spontaneous Brillouin scattering linewidth $\Delta\nu_B = \Gamma/\pi$, $\alpha = \alpha_s \approx \alpha_p$ is the absorption coefficient, and the coupling constants are

$$K_1 = \frac{K_2 \rho_0 n^2 \varepsilon_0}{2\nu_a}, \qquad K_2 = \frac{n^3 p_{12} \omega_s (\hat{e}_p \times \hat{e}_s)}{2c\rho_0} \qquad [23]$$

ε_0 being the free-space permittivity and $\hat{e}_p$ and $\hat{e}_s$ the unit vectors in the directions of the pump and Stokes optical fields, respectively. In eqns [21] and [22] it is assumed that the pump wave is launched at $z = 0$ and propagates in the $+z$ direction, whereas the signal wave is launched at $z = L$ and propagates in the $-z$ direction. The parameter $\delta \equiv \omega_p - \omega_s - \omega_a$ takes into account a possible detuning of the signal from the SBS gain line center.

Equations [21] and [22] can be written in terms of optical power as follows:

$$\frac{dP_s}{dz} = \alpha P_s - \frac{g_B(\delta)}{A_e} P_p P_s \qquad [24]$$

$$\frac{dP_p}{dz} = -\alpha P_p - \frac{g_B(\delta)}{A_e} P_s P_p \qquad [25]$$

where A_e is the effective core area and $g_B(\delta)$ is the Brillouin gain coefficient, given by

$$g_B(\delta) = \frac{\Gamma^2}{\delta^2 + \Gamma^2} g_B(\nu_B) \qquad [26]$$

where $g_B(\nu_B)$ is given by eqn [19].

Considering that $a \ll 1$, the following approximate solutions of eqns [24] and [25] can be written:

$$P_s(z) = P_s(0) D(z) e^{\alpha z} \qquad [27]$$

$$P_p(z) = P_p(0) D(z) H(z) e^{-\alpha z} \qquad [28]$$

where

$$D(z) = \frac{[P_p(0) - P_s(0)]}{[P_p(0) H(z) - P_s(0)]} \qquad [29]$$

and

$$H(z) = \exp\left\{ g_B [P_p(0) - P_s(0)][1 - \exp(-\alpha z)]/(A_e \alpha) \right\} \qquad [30]$$

The Brillouin amplifier gain is given from eqn [27] as

$$G_B = \frac{P_s(0)}{P_s(L) e^{-\alpha L}} = \frac{1}{D(L)} \qquad [31]$$

Figure 6 shows the output signal power $P_s(0)$ versus the input signal power $P_s(L)$ for a Brillouin amplifier with length $L = 8$ km and several values of the input pump power. Typical values $g_B(0) = 2.5 \times 10^{-11}$ m W^{-1}, $\alpha = 0.2$ dB km^{-1}, $A_e = 30 \times 10^{-12}$ m^2 were assumed. The transfer characteristics are linear for $P_p(0) = 0.2$ mW, but the effects of pump depletion become discernible



Figure 6 Transfer characteristics for a Brillouin amplifier with a length $L = 8$ km and several values of the input pump power.

for input signal levels $P_s(0) > 2\ \mu\text{W}$ when $P_p(0) = 1\ \text{mW}$. For a pump power $P_p(0) = 2\ \text{mW}$, linear behavior of the Brillouin amplifier cannot be observed even for signal powers as low as 10 nW.

The dependence of the Brillouin amplifier gain on the input pump power is illustrated in Figure 7 for several amounts of the signal detuning and two values of the signal power. The fiber length is $L = 5$ km and the gain bandwidth is $\Delta\nu_B = 30$ MHz, whereas the other parameter values are equal to those assumed in Figure 6. The saturated gain shows a significant dependence on the input signal power. An input signal of 1 nW, which is comparable to the original value of spontaneous emission, can be amplified by about 60 dB for a pump power $P_p(0) \approx 5$ mW. However, the amplifier gain can be considerably reduced when the signal is detuned from the gain peak. For example, for an input signal power $P_s(L) = 1$ nW and a pump power $P_p(0) \approx 3$ mW, a detuning of 15 MHz (which corresponds to a reduction of the gain coefficient to half of its maximum value) determines a reduction of about 25 dB on the amplifier gain.

Substituting eqn [28] for $P_p(z)$ in eqn [21], the following result is obtained for the Stokes field at the amplifier output:

$$E_s(0) = E_s(L)\sqrt{G_B}\exp\{-\alpha L/2 - j\phi\} \qquad [32]$$

where

$$\phi = \frac{\delta}{2\Gamma}\ln(G_B) \qquad [33]$$



Figure 7 Brillouin amplifier gain against the input pump power for an amplifier length $L = 5$ km and different amounts of detuning from the gain center. The full curves and the dashed curves correspond to input signal powers $P_s(L)$= 1 nW and $P_s(L)$= 1 μW, respectively. Reproduced with permission from Ferreira MFS, *et al.* (1994) *Optical and Quantum Electronics* 26: 35, with permission from Kluwer Academic Publisher.

represents a nonlinear phase change, which depends on the SBS gain, input signal power, and frequency detuning. This nonlinear phase shift can impose a stringent limit on the pump- and signal-frequency stability when FBAs are used in some phase-sensitive detection schemes.

Noise Light Power

To describe the spontaneous emission noise we must add a spontaneous emission term to the equations describing the evolution of the Stokes and pump waves. The amplified spontaneous scattered power per unit frequency is then obtained in the form:

$$P_{asp}(\nu, z) = (h\nu/A_e)g_B(\delta)(N+1)G(\nu, z) \times \int_z^L P_p(z')[G(\nu, z')]^{-1}\mathrm{d}z' \qquad [34]$$

where

$$G(\nu, z) = \exp\left\{\int_z^L [P_p(z)g_B(\delta)/A_e - \alpha]\mathrm{d}z\right\} \qquad [35]$$

is the gain function, h is Planck's constant, and N is the thermal equilibrium number of acoustic phonons, given by

$$N = \frac{1}{\exp(h\nu_B/kT)^{-1}} \approx kT/h\nu_B \approx 500 \qquad [36]$$

where k is the Boltzmann constant and T is the absolute temperature. The total amplified signal and spontaneous powers are given by integration of $P_s(\nu, z)$ over the gain profile.

Similarly to the behavior of the gain, the noise power depends significantly on the signal magnitude in the saturation regime and becomes particularly high for low signal powers. This high noise level, which is about 20 dB above that of an ideal amplifier, imposes some limitations on the use of FBA as a receiver preamplifier.

FBA Performance and Applications

Fiber Brillouin amplifiers can provide high gains at low pump powers. However, the gain bandwidth is small and the amplified spontaneous emission noise is substantially larger than that observed with other amplifiers, leading to a noise figure that is quite large (>15 dB). This fact limits their usefulness as a preamplifier. Use as in-line amplifiers at high signal levels is possible in some configurations. Some problems in this application are concerned with the narrow bandwidth and the small saturation power of the FBAs. In particular, the Brillouin linewidth strictly limits the bandwidth of data signals that can be amplified in a FBA.

The Brillouin gain bandwidth can be intentionally extended by more than one order of magnitude by applying frequency modulation to the pump laser. Of course, the bandwidth enhancement is accompanied by a reduction of the peak gain. Consequently, a higher pump power will be necessary to achieve the same gain.

The narrow bandwidth of the FBAs can be used to advantage in coherent lightwave systems to amplify selectively the carrier of a phase- or amplitude-modulated wave, thus allowing homodyne detection, using the amplified carrier as local oscillator. The scheme should work well at bit rates >100 Mb s^{-1} because the modulation sidebands then fall outside the amplifier bandwidth, and the optical carrier can be amplified selectively. However, an inevitable accompaniment of this narrow-band amplification is the nonlinear phase shift induced by the pump on the signal, given by eqn [33]. This phase shift imposes the most stringent limit on pump- and signal-frequency stability when FBAs are used for self-homodyne detection. In the case of amplitude-shift keyed (ASK) signals, for example, a phase stability of about 0.1 rad for the amplified signal carrier may be required, which corresponds to a pump-signal frequency offset <100 kHz. The nonlinear phase shift can be used with advantage in some self-homodyne schemes which require some specific adjustment of the carrier phase. In the case of a self-homodyne coherent receiver for phase-shift keyed (PSK) signals, for example, a quadrature phase correction is required. Typically, this requires a detuning of only a few MHz from the SBS gain peak, well within the Brillouin gain bandwidth.

Another application of the narrow linewidth associated with the Brillouin gain, is as a tunable narrow-band filter for channel selection in a densely packed multichannel communication system. A channel can be selectively amplified through Brillouin amplification by launching a pump beam at the receiver end so that it propagates inside the fiber in a direction opposite to that of the multichannel signal. Different channels can be selectively amplified by tuning the pump laser. The adjustable bandwidth and high out-of-band rejection can be used to advantage in this case. In another approach, the fiber Brillouin amplifier can be used to selectively amplify multiple subcarrier-multiplexed (SCM) channels carried by a single optical carrier within a WDM signal, or to amplify a backward-propagating supervisory signal.

Fiber Parametric Amplifiers

In both stimulated Raman scattering and stimulated Brillouin scattering, the optical fiber plays an active role through the participation of molecular vibrations or acoustic phonons. However, in many other nonlinear phenomena, the fiber plays a passive role except for mediating the interaction among several optical waves. Since these phenomena involve the light-induced modulation of some medium parameter, they are known as parametric processes.

The parametric processes can be classified as second-order or third-order processes, depending on whether the second-order susceptibility or the third-order susceptibility is responsible for them. Concerning the second-order parametric processes, they are not significant in silica fibers, due to the small value of the second-order susceptibility. In contrast, some third-order parametric processes, namely third-harmonic generation, four-wave mixing, and parametric amplification, can exhibit relatively high conversion efficiencies. The parametric gain in optical fibers can be used to make fiber parametric amplifiers, which find some interesting applications for squeezing and optical fiber communications.

Phase-Matching in Parametric Processes

The efficiency of the four-wave mixing process depends on the relative phase among the interacting optical waves. A high efficiency requires matching of the frequencies as well as of the wave vectors. The latter requirement is often referred to as phase-matching. In contrast with SRS and SBS, where phase-matching is automatically fulfilled as a result of the active participation of the nonlinear medium, the phase-matching condition in parametric processes requires a specific choice of the frequencies and the refractive indices.

Considering the case in which two photons at energies ω_1 and ω_2 are annihilated with simultaneous creation of two photons at frequencies ω_3 and ω_4, the matching of the frequencies imposes the condition:

$$\omega_1 + \omega_2 = \omega_3 + \omega_4 \qquad [37]$$

On the other hand, the phase-matching is given by the condition $\Delta k = 0$, where

$$\begin{aligned}\Delta k &= k_3 + k_4 - k_1 - k_2 \\ &= (\tilde{n}_3\omega_3 + \tilde{n}_4\omega_4 - \tilde{n}_1\omega_1 - \tilde{n}_2\omega_2)/c \qquad [38]\end{aligned}$$

where the $\tilde{n}_i$ are the effective refractive indices of the fiber modes. It is relatively easy to satisfy the phase-matching condition when $\omega_1 = \omega_2$. In this case, a strong pump at $\omega_1 = \omega_2 \equiv \omega_\mathrm{p}$ generates a low-frequency sideband at ω_3 and a high-frequency sideband at ω_4, when we assume $\omega_4 > \omega_3$. These sidebands are referred as the Stokes and anti-Stokes bands, respectively, which are also often called the signal and idler bands. The frequency shift of the two sidebands is given by

$$\Omega_s = \omega_p - \omega_3 = \omega_4 - \omega_p \qquad [39]$$

The effective indices $\tilde{n}_i$ in eqn [38] can be written as

$$\tilde{n}_i = n_i + \Delta n_i \qquad [40]$$

where Δn_i is the change of index refraction due to waveguiding. As a consequence, considering the eqn [40] and the case $\omega_1 = \omega_2$, eqn [38] can be written in the form:

$$\Delta k = \Delta k_m + \Delta k_w \qquad [41]$$

where

$$\Delta k_m = (n_3\omega_3 + n_4\omega_4 - 2n_1\omega_1)/c \qquad [42]$$

results from the material dispersion and

$$\Delta k_w = (\Delta n_3\omega_3 + \Delta n_4\omega_4 - (\Delta n_1 + \Delta n_2)\omega_1)/c \qquad [43]$$

results from the waveguide dispersion. We must note that although the two pump waves have the same frequency, Δn_1 and Δn_2 are, in general, different if these waves propagate in different modes.

The material contribution Δk_m can be expressed in terms of the frequency shift Ω_s given by eqn [39], if we use an expansion of Δk_m about the pump frequency $\omega_p = \omega_1 = \omega_2$. By retaining up to terms quadratic in Ω_s in this expansion, one obtains

$$\Delta k_m = \beta_2 \Omega_s^2 \qquad [44]$$

where $\beta_2 = d^2k/d\omega^2$ is the group-velocity dispersion (GVD) coefficient at the pump frequency. In the description of the evolution of the Stokes and anti-Stokes waves, an effective propagation constant appears, given by

$$\kappa = \Delta k + \Delta k_{NL} = \Delta k_m + \Delta k_w + \Delta k_{NL} \qquad [45]$$

In eqn [45], Δk_{NL} represents a nonlinear contribution, given by

$$\Delta k_{NL} = 2\gamma P_p \qquad [46]$$

where $P_p = P_1 = P_2$ is the power in each pump wave and

$$\gamma = \frac{\bar{n}_2 \omega}{c A_e} \qquad [47]$$

is the nonlinearity coefficient, $\bar{n}_2$ being the nonlinear-index coefficient.

Parametric Gain

The evolution of the Stokes and anti-Stokes waves are governed by the following coupled equations:

$$\frac{dE_3}{dz} = 2j\gamma P_p \exp(-j\kappa z)E_4^* \qquad [48]$$

$$\frac{dE_4^*}{dz} = -2j\gamma P_p \exp(j\kappa z)E_3 \qquad [49]$$

The general solution of eqns [48] and [49] is given by

$$E_3(z) = (c_1 \exp(g_P z) + c_2 \exp(-g_P z)) \exp(-j\kappa z/2) \qquad [50]$$

$$E_4^*(z) = (c_3 \exp(g_P z) + c_4 \exp(-g_P z)) \exp(j\kappa z/2) \qquad [51]$$

where the coefficients c_i are determined from the boundary conditions and the parametric gain g_P is given by

$$g_P = \sqrt{(2\gamma P_p)^2 - \left(\frac{\kappa}{2}\right)^2} \qquad [52]$$

In the range

$$-6\gamma P_p \le \Delta k \le 2\gamma P_p \qquad [53]$$

the radicand in eqn [52] is positive, so a gain occurs. The maximum gain is achieved when $\kappa = 0$ and it is given by

$$g_{P\max} = \Delta k_{NL} = 2\gamma P_p = \bar{g}_P \frac{2P_p}{A_e} \qquad [54]$$

where

$$\bar{g}_P = \frac{\omega_p \bar{n}_2}{c} \qquad [55]$$

Considering that $\bar{n}_2 = 3.2 \times 10^{-20}\ m^2\ W^{-1}$ and assuming a pump wavelength $\lambda_p = 1\ \mu m$, we find that the gain coefficient $\bar{g}_P$ is larger by a factor of 2 than the peak of the Raman gain coefficient g_R. Consequently, the threshold for the parametric process is lower than with the Raman effect. However, the Raman effect dominates in general for long fibers, since it is difficult to maintain phase matching because of fluctuations of the core diameter. One can define a coherence length, given by

$$L_{coh} = 2\pi/\kappa_{max} \qquad [56]$$

where κ_{max} is the maximum tolerable phase mismatch. Significant four-wave mixing occurs only if $L < L_{coh}$.

In the case of a monomode fiber, Δk_w is very small and can be ignored. For λ_p below the zero of dispersion $\lambda_\mathrm{D} \approx 1.3\ \mu\mathrm{m}$ $(\beta_2 > 0)$, one has to keep both Δk_m and Δk_NL small by using small frequency shifts Ω_s and low pump powers. When Δk_m dominates, we have

$$L_\mathrm{coh} \approx \frac{2\pi}{|\Delta k_\mathrm{m}|} = \frac{2\pi}{\beta_2 \Omega_\mathrm{s}^2} \qquad [57]$$

In the visible range, one has $\beta_2 \approx 50 - 60\ \mathrm{ps^2\,km^{-1}}$, and $L_\mathrm{coh} \approx 1$ km for $f_\mathrm{s} = \Omega_\mathrm{s}/2\pi \approx 50$ GHz. For a pump wavelength above the zero dispersion $(\beta_2 < 0)$, the negative value of Δk_m must be compensated by Δk_NL. For phase matching one has

$$\kappa = 0 \approx \Delta k_\mathrm{m} + \Delta k_\mathrm{NL} = \beta_2 \Omega_\mathrm{s}^2 + \Delta k_\mathrm{NL} \qquad [58]$$

From this, we obtain

$$\Omega_\mathrm{s} = \sqrt{2\gamma P_\mathrm{p}/|\beta_2|} \qquad [59]$$

which coincides with the frequency shift characteristic of the modulation instability.

Amplifier Gain and Bandwidth

Four-wave mixing can be used, for example, in a fiber-optical parametric amplifier. In fact, the main difference between the four-wave mixing experiments and the parametric-amplification experiments is whether a signal at the phase-matched frequency is co-propagated with the pump or not. In the absence of a signal, the signal and idler waves are generated from amplifications of noise.

Let us consider the situation in which a signal wave with a power P_3 is launched at $z = 0$, and simultaneously an idler wave appears, with $P_4(z = 0) = 0$. In this case, considering the solution given by eqs [50] and [51] and taking into account eqn [52], we can write the following results for the signal and idler powers:

$$P_3(z) = P_3(0)\left[1 + \left(1 + \frac{\kappa^2}{4g_\mathrm{P}^2}\right)\sinh^2(g_\mathrm{P} z)\right] \qquad [60]$$

$$P_4(z) = P_3(0)\left(1 + \frac{\kappa^2}{4g_\mathrm{P}^2}\right)\sinh^2(g_\mathrm{P} z) = P_3(z) - P_3(0) \qquad [61]$$

The single-pass gain of the parametric amplifier becomes

$$G_\mathrm{P} = \frac{P_3(L)}{P_3(0)} = 1 + \frac{P_4(L)}{P_3(0)} = 1 + \left(1 + \frac{\kappa^2}{4g_\mathrm{P}^2}\right)\sinh^2(g_\mathrm{P} L)$$
$$= 1 + \frac{(2\gamma P_\mathrm{p})^2}{g_\mathrm{P}^2}\sinh^2(g_\mathrm{P} L) \approx \left(1 + \frac{\kappa^2}{4g_\mathrm{P}^2}\right)\sinh^2(g_\mathrm{P} L) \qquad [62]$$

The approximation holds for $g_\mathrm{P} L \gg 1$. According to eqn [52], amplification $(g_\mathrm{P} > 0)$ occurs only in the case:

$$|\kappa| < 4\gamma P_\mathrm{p} \qquad [63]$$

Since $|\kappa|$ must be small, this also means good phase-matching. If one has complete phase-matching $(\kappa = 0)$ and still $g_\mathrm{P} L \gg 1$,one obtains exponential behavior for the amplifier gain:

$$G_\mathrm{P} = \sinh^2(g_\mathrm{P} L) \approx \frac{1}{4}\exp(2g_\mathrm{P} L) = \frac{1}{4}\exp(4\gamma P_\mathrm{p} L) \qquad [64]$$

From Eqs [44] and [45], we have that the phase mismatch κ and the frequency shift Ω_s are related by

$$\kappa = \beta_2 \Omega_\mathrm{s}^2 + \Delta k_\mathrm{w} + \Delta k_\mathrm{NL} \qquad [65]$$

From eqn [65] we have

$$\frac{\Delta\kappa}{\Delta\Omega_\mathrm{s}} = 2|\beta_2|\Omega_\mathrm{s} \qquad [66]$$

In order to estimate the amplification bandwidth $\Delta\Omega_\mathrm{s}$, we set

$$\Delta\kappa = \kappa_\mathrm{max} = 4\gamma P_\mathrm{p} \qquad [67]$$

From Eqs [66] and [67] we obtain

$$\Delta\Omega_\mathrm{s} = \frac{2\gamma P_\mathrm{p}}{|\beta_2|\Omega_\mathrm{s}} = \frac{2}{|\beta_2|\Omega_\mathrm{s} L_\mathrm{NL}} \qquad [68]$$

where $L_\mathrm{NL} = (\gamma P_\mathrm{p})^{-1}$ is the nonlinear length. Considering typical values $|\beta_2| = 20\text{–}60\ \mathrm{ps^2\,km^{-1}}$, $\Omega_\mathrm{s}/2\pi = 10\text{–}100$ THz, and $L_\mathrm{NL} \sim 1$ m, we obtain a bandwidth in the range ~10–100 GHz. This bandwidth lies between that of a fiber Raman amplifier (~5 THz) and a fiber Brillouin amplifier (~100 MHz).

For $|\kappa| > 4\gamma P_\mathrm{p}$ the parametric gain becomes imaginary and there is no longer amplification, but rather a periodical power variation of the signal and idler waves. In particular, if $|\kappa| \gg 4\gamma P_\mathrm{p}$, then

$g_P \approx j\kappa/2$ and the parametric amplifier gain is

$$G_P = (2\gamma P_p L)^2 \frac{\sin^2(\kappa L/2)}{(\kappa L/2)^2} \qquad [69]$$

A convenient measure for the width in this case corresponds to a wavevector mismatch $\Delta\kappa = 2\pi/L$, where L is the fiber length. Using eqn [66], we then have

$$\Delta\Omega_s = \frac{\pi}{L|\beta_2|\Omega_s} \qquad [70]$$

Amplifier Performance and Applications

Parametric amplification can induce considerable crosstalk in WDM communication systems. Such crosstalk affects the system performance, particularly for channel spacings less than 10 GHz. Considering a channel spacing of 5 GHz and −20 dB allowed crosstalk, calculations show that the input power per channel should be smaller than 1 mW for a 15 km-long monomode fiber, and 0.1 mW for 100 km-long fiber. However, this effect can be avoided by an appropriate frequency separation of the channels.

Besides the limitation mentioned above, parametric amplification may be useful in the field of optical fiber communication systems. In fact, parametric amplifiers have a bandwidth of ~100 GHz, which is smaller that the bandwidth of fiber Raman amplifiers (~5 THz) but still sufficiently large for many applications. On the other hand, the frequency shift in FPAs can be as large as ~100 THz, which must be compared with the pump-signal frequency shift of ~13 THz of FRAs. These characteristics of FPAs allow a considerable flexibility in the choice of the pump source.

Parametric amplifier gains above 40 dB, with a 30-m-long fiber for input signal powers less than 1 mW and a pump power $P_p \approx 70$ W, were already measured. Such large gain values show clearly the potential of fiber parametric amplifiers provided phase-matching can be achieved. In fact, this condition puts stringent limits on the control of frequency shift Ω_s between the pump and signal waves. One method to satisfy the phase-matching requirement consists in using large birefringence of polarization-preserving fibers. Several parametric amplifiers using this kind of fiber have been demonstrated. Moreover, the possibility to realize a parametric laser was also demonstrated, by placing the fiber inside a Fabry–Perot cavity.

Fiber-optic parametric amplifiers have also attracted considerable attention in the context of a phenomenon known as squeezing. In contrast to coherent light containing equal minimum noise fluctuations in cophasal and quadrature components, in squeezed states one of these components acquires a noise fluctuation below the quantum-noise level at the expense of the other component. This phenomenon can occur in a parametric amplifier for certain values of the relative phase between the signal and idler waves. In fact, spontaneous emission at the signal and idler frequencies generates photons with random phases. Four-wave mixing increases or decreases the number of specific signal-idler photon pairs, depending on their relative phases. The noise reduction below the quantum-noise level can be verified using a phase-sensitive detection scheme in which the phase of the local oscillator is conveniently adjusted. The phase-sensitive nature of parametric amplifiers can also be usefully exploited to reduce the timing jitter in soliton communication systems.

List of Units and Nomenclature

A_e	effective fiber core area, m^2
c	vacuum speed of light, m s^{-1}
E_p	amplitude of the pump wave electric field, V m^{-1}
E_s	amplitude of the signal wave electric field, V m^{-1}
g_B	Brillouin gain coefficient, m W^{-1}
G_B	Brillouin amplifier gain
g_P	parametric gain, m^{-1}
G_P	parametric amplifier gain
g_R	Raman gain coefficient, m W^{-1}
G_R	Raman amplifier gain
$\vec{k}_a$	wave vector of the acoustic wave, rad m^{-1}
$\vec{k}_p$	wave vector of the pump wave, rad m^{-1}
$\vec{k}_s$	wave vector of the signal wave, rad m^{-1}
L	amplifier length, m
L_{coh}	coherence length, m
L_e	effective amplifier length, m
L_{NL}	nonlinear length, m
n	refractive index
$\bar{n}_2$	nonlinear-index coefficient, m^2 W^{-1}
p_{12}	longitudinal elasto-optic coefficient
P_{asp}	amplified spontaneous scattered power, W
P_p	pump power, W
P_s	signal (Stokes) power, W
ν_a	acoustic velocity, m s^{-1}
ν_B	Brillouin frequency shift, s^{-1}
α_p	absorption coefficient at the pump frequency, m^{-1}

α_s	absorption coefficient at the signal frequency, m^{-1}
β_2	group-velocity dispersion coefficient, $s^2 m^{-1}$
γ	nonlinearity coefficient, $W^{-1} m^{-1}$
Γ	inverse acoustic phonon lifetime, s^{-1}
δ	frequency detuning from Brillouin gain peak, s^{-1}
$\Delta\nu_B$	Brillouin gain bandwidth, s^{-1}
$\Delta\nu_p$	pump linewidth, s^{-1}
$\Delta\nu_R$	Raman gain bandwidth, s^{-1}
ε_0	free-space permittivity, F m^{-1}
ρ_0	average material density, kg m^{-3}
ϕ	nonlinear phase shift, rad
ω_a	acoustic wave frequency, rad s^{-1}
ω_p	pump wave frequency, rad s^{-1}
ω_s	signal (Stokes) wave frequency, rad s^{-1}
Ω_s	sideband frequency shift, rad s^{-1}

See also

Optical Communication Systems: Wavelength Division Multiplexing. **Nonlinear Optics, Basics:** Four-Wave Mixing. **Scattering:** Raman Scattering.

Further Reading

Agrawal GP (1992) *Fiber-Optic Communication Systems*, Ch. 8. New York: John Wiley & Sons.

Agrawal GP (1995) *Nonlinear Fiber Optics*, 2nd edn, Ch. 8–10. San Diego, CA: Academic Press.

Boyd RW (1992) *Nonlinear Optics*, Ch. 8–10. San Diego, CA: Academic Press.

Buck JA (1995) *Fundamentals of Optical Fibers*, Ch. 7 and 8. New York: John Wiley & Sons.

Cotter D (1987) Fiber nonlinearities in optical communications. *Optical Quantum Electronics* 19: 1–17.

Cotter D (1993) Nonlinearity in optical fiber communication. In: Eason RW and Miller A (eds) *Nonlinear Optics in Signal Processing*, Ch. 9. London: Chapman & Hall.

Forghieri F, Thach RW and Chraplyvy AR (1997) Fiber nonlinearities and their impact on transmission systems. In: Kaminow IP and Koch TL (eds) *Optical Fiber Telecommunications – IIIA*, Ch. 8. San Diego, CA: Academic Press.

Sauter EG (1996) *Nonlinear Optics*, Ch. 5–11. New York: John Wiley & Sons.

Schubert M and Wilhelmi B (1986) *Nonlinear Optics and Quantum Electronics*, Ch. 11 and 12. New York: John Wiley & Sons.

Shen YR (1984) *The Principles of Nonlinear Optics*, Ch. 9–11, 14, 26. New York: John Wiley & Sons.

Semiconductor Optical Amplifiers

M J Connelly, University of Limerick, Limerick, Ireland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

There has been rapid growth in the deployment and capacity of optical fiber communication networks over the past 25 years. This growth has been made possible by the development of new optoelectronic technologies that can be utilized to exploit the enormous bandwidth of optical fiber. Today, systems are operational which operate at bit rates in excess of 100 Gb/s. Optical technology is the dominant carrier of global information. It is also central to the realization of future networks that will have the capabilities demanded by society. These capabilities include virtually unlimited bandwidth to carry communication services of almost any kind, and full transparency that allows terminal upgrades in capacity and flexible routing of channels. Many of the advances in optical networks have been made possible by the optical amplifier.

Optical amplifiers can be divided into two classes: the optical fiber amplifier and semiconductor optical amplifier (SOA). The former dominates conventional system applications such as in-line amplification to compensate for optical link losses. However, due to advances in optical semiconductor fabrication techniques and device design, the SOA is showing great promise for use in evolving optical communication networks. It can be utilized as a general gain element but also has many functional applications, including optical switching and wavelength conversion. These functions, where there is no conversion of optical signals into the electrical domain, are required in transparent optical networks.

We will review SOA basics, technology (materials and structures), signal transmission performance (pattern effects, crosstalk, and ultrashort pulse amplification), and some important functional applications (optical switching and wavelength conversion).

Basic Principles

The SOA is based on similar technology as a laser diode. Optical gain is achieved by electrically pumping a suitable semiconductor material, such that a population inversion occurs between the material conduction and valence bands. An incoming photon can then be amplified when the resulting stimulated emission exceeds losses due to stimulated absorption and internal material losses. SOAs can be designed to operate in either the 1300 nm or 1550 nm optical communication windows. The principle of operation of an SOA with low residual reflectivities ($R \approx 0$) is shown in Figure 1. An input optical power experiences a single-pass gain $G = \exp(gL)$ after traveling through the SOA active waveguide of length L. The net gain coefficient $g = \Gamma g_m - \alpha_{int}$, where Γ is the optical confinement factor (the fraction of the propagating signal power confined to the SOA waveguide), g_m the material gain, and α_{int} the optical loss coefficient. g_m is a function of the injected carrier (electron) density and wavelength. The single-mode active waveguide can support two orthogonal polarization modes: transverse electric (TE) and transverse magnetic (TM).

The amplification process also adds broadband noise, amplified spontaneous emission (ASE) to the output signal. The amplifier noise figure (NF) is a measure of the signal-to-noise ratio (SNR) degradation of the signal after amplification. It is defined as the ratio of the SNR of the input to that of the output when the input noise is shot noise limited. Expressions for the output SNR are usually calculated assuming that the SOA is followed by a narrowband optical filter and an ideal photodetector, such that the main source of detector noise is the beat noise between the signal and the ASE falling within the filter bandwidth. In this case the SOA noise figure is given by

$$\mathrm{NF} = 2n_{sp}K \qquad [1]$$

with the excess noise factor K given by

$$K = \frac{(1 + RG)(G - 1)\Gamma g_m}{(1 - R)G(\Gamma g_m - \alpha_{int})} \qquad [2]$$

where n_{sp} is the effective population inversion parameter. To achieve a low NF, the internal losses must be small and a value of n_{sp} close to one is required. A favorable value of n_{sp} is achieved by operating the SOA at high gain.

A low R is required to prevent the SOA from oscillating at high gains. The residual reflectivity is manifest as ripples in the amplifier gain spectrum and ASE spectrum.

SOA Structures

The key parameters required for a practical SOA are:

- low reflectivity ($<10^{-4}$) to ensure low gain ripple (<0.5 dB);
- low optical loss coefficient to achieve a high gain;
- high material gain to allow low drive current operation;
- low polarization sensitivity (<0.5 dB) because the polarization state of the optical signal coming from a link fiber is usually random;
- high saturation output power (P_{sat}), defined as the output power at which the gain is reduced by 3 dB; and
- low fiber-to-chip coupling losses (<3 dB per facet).

A schematic diagram of a commercial SOA chip is shown in Figure 2. The active waveguide consists of a 0.2 μm thick InGaAsP bulk active layer sandwiched between 0.1 μm thick InGaAsP separate confinement heterostructure (SCH) layers. The central section of the active waveguide is 600 μm long with a constant width of 1.4 μm. The mode-expanding active waveguide tapers are 150 μm long with a width that changes linearly from 1.4 μm to 0.4 μm at the tip. The tapers allow optical coupling to an underlying passive waveguide enabling efficient coupling to the input and output optical fibers. The structure provides a high confinement factor because of the refractive index mismatch between the layers in the gain section. The p-n junction formed by the p-InP



Figure 1 SOA basic structure.


Electrode
p-InP
n-InP
p-InP
Tensile-strained InGaAsP bulk active layer surrounded by InGaAsP SCH layers
Passive waveguide
AR coating
InGaAsP buried active waveguide
Buried window
AR coating
1.4 μm
7°
150 μm
600 μm
150 μm
15 μm

(a) Cross-section of the SCH SOA structure.

(b) Top view of the active waveguide.

Figure 2 SCH SOA with tensile-strained bulk active layer.

Table 1 Typical specifications of a commercial SOA

Wavelength of peak gain	1550 nm
Peak fiber-to-fiber gain	22 dB
Noise figure	6.5 dB
Saturation output power	10 dBm
Polarization sensitivity	0.2 dB
Gain ripple	0.1 dB
3 dB bandwidth	40 nm
Drive current	200 mA

and n-InP layers acts as a current block, thereby providing good confinement of the injected carriers from the drive current to the active layer. Very low-reflectivity ($<10^{-6}$) is obtained by combining buried windows with antireflection-coated tilted facets (7° tilt angle).

Because of the active waveguide asymmetry, the TE confinement factor is larger than the TM confinement factor. g_m is isotropic in bulk material. The introduction of tensile strain, due to the lattice mismatch between the active layer and SCH layers, causes the bulk material band structure to change in such a way that the TM material gain is greater than the TE material gain. The introduction of the correct amount of tensile strain compensates for the difference in the TE and TM confinement factors leading to low polarization dependence.

Other SOA structures that can achieve low polarization dependency are based on active waveguides with near square cross-section having almost the same TE and TM confinement factors or the combination of compressively strained quantum wells (higher TE gain) and tensile strained quantum wells (higher TM gain). Typical specifications and characteristics of a commercial SOA are listed in Table 1 and shown in Figure 3.

As Figure 3 shows, gain saturation in conventional SOAs is manifest at output signal powers well below P_{sat}. Because the gain recovery time (carrier lifetime) in SOAs is fast (typically 0.1–1 ns), this can lead to pattern effects in single-channel systems and severe crosstalk in wavelength division multiplexed (WDM) systems. This problem can be greatly reduced by the use of a gain-clamped SOA (GC-SOA). In a GC-SOA, lasing action is produced, at a wavelength remote from the operating wavelength range, by the introduction of wavelength specific feedback. Once lasing begins, the carrier density in the SOA active layer is clamped at a fixed value. Changes in the input signal power lead to opposing changes in the lasing mode power. This has the effect of keeping the carrier density fixed (i.e., clamped), thereby making the signal gain relatively insensitive to changes in the total input power. A common method of providing this feedback is the use of distributed Bragg reflectors (DBRs) as shown in Figure 4. A typical GC-SOA gain versus output power characteristic is shown in Figure 5.

Basic Applications of SOAs in Optical Communication Systems

The three basic applications of SOAs in optical communication systems are: booster amplifier, in-line amplifier, and preamplifier. The main requirements of SOAs for such applications are listed in Table 2.

A booster amplifier is used to increase the power of a high power signal. Boosting laser power in an optical transmitter can be used to overcome external modulator losses, compensate for splitting and tap losses in optical distribution networks and to increase the power budget of optical links. The most critical requirement of a booster amplifier is a high P_{sat}, to obtain a high output signal power and minimize pattern effects. SOAs with P_{sat} in excess of 10 dBm are now available commercially.

The sensitivity of a conventional optical receiver is limited by thermal noise. The sensitivity is the



Figure 3 Typical commercial SOA small-signal gain and noise figure versus bias current and gain versus output power characteristics.

minimum signal power required at the receiver input to achieve a desired bit-error-rate (typically 10^{-9}). An optical preamplifier can be used to increase the power level of an optical data signal prior to detection and demodulation, leading to an increase in sensitivity. The performance of a preamplified optical receiver is dependent on the detector signal-to-noise ratio, $\text{SNR} = i^2_{\text{sig}}/\overline{\imath}^2_{\text{noise}}$. The signal photocurrent i_{sig} is proportional to the amplified signal power. The mean square noise current $\overline{\imath}^2_{\text{noise}}$ includes circuit noise (thermal noise and detector dark current noise), signal shot noise, spontaneous emission shot noise, signal-spontaneous beat noise, and beat noise between the spectral components of the spontaneous emission. The best improvement in SNR occurs when the SOA is operated in the signal-spontaneous beat noise limit. In this regime, the signal power is sufficiently large such that the dominant receiver noise is the signal-spontaneous beat noise that falls within the signal bandwidth. This usually requires that the spontaneous emission from the SOA be reduced using a narrowband optical filter. The noise figure is a critical parameter in this application and should be as low as possible.

In long-haul optical transmission systems, in-line optical amplifiers can be used to compensate for link losses thereby increasing the spacing between optical regenerators. The main advantages of in-line SOAs are transparency to data rate and modulation format (unsaturated operation), bidirectionality, WDM capability, simple mode of operation, low power consumption, and compactness. The latter two advantages are important for remotely located optical components. To avoid noise accumulation in the link, it may be necessary to follow each SOA by a narrowband optical filter, but this can prevent capacity enhancements using WDM.

An example of a single channel optical transmission system utilizing booster, in-line, and preamplifier SOAs is shown in Figure 6. The transmitter comprised a 1309 nm gain-switched laser diode directly modulated with a 10 GHz sinusoid to produce a train of 40 ps wide pulses at a repetition rate of 10 GHz. At 1309 nm fiber dispersion is small and the maximum transmission distance is mainly limited by the link losses. The laser output was connected to an external modulator, driven by a 2^{31}-1 pseudo-random bit sequence (PRBS) to produce an optical data stream with an extinction ratio of 13 dB. A booster SOA was used to increase



Figure 4 Schematic structure of a GC-SOA.



Figure 5 Typical GC-SOA gain versus output power characteristic.

Table 2 Requirements of basic SOA applications

Requirement	*Booster amplifier*	*In-line amplifier*	*Preamplifier*
High gain	Yes	Yes	Yes
High P_{sat}	Yes	Yes	Not critical
Low noise figure	Not critical	Yes	Yes
Low polarization sensitivity	Not critical	Yes	Yes
Optical filter	Not necessary	Not critical	Yes



Figure 6 10 Gbit/s transmission experiment utilizing booster, in-line and preamplifier SOAs. (Adapted from Kuindersma *et al.* (1996) 10 Gbit/s RZ transmission at 1309 nm over 420 km using a chain of multiple quantum-well semiconductor optical amplifier modules at 38 km intervals. European Conference on Optical Communications 1996.)

the average transmitted power to between 0 and 2 dBm (7–9 dBm peak power). The transmission fiber length was 420 km with 12 in-line SOAs, used to compensate for fiber loss, spaced at 38 km intervals. At the receiver the signal was passed through a 1 nm bandpass filter, to reduce the accumulated spontaneous emission, amplified by an SOA preamplifier and filtered by a 1 nm bandpass filter. The signal was then detected by a p-i-n photodiode followed by an electronic clock and data recovery circuit. The SOA preamplifier and filter increased the receiver sensitivity from −14 dBm to −31 dBm for a BER of 10^{-10}. The receiver penalty after 420 km was 5 dB. In this experiment, the main limitation on transmission distance was the accumulation of spontaneous emission within the optical filter bandwidth.

Pattern Effects and Crosstalk

When an SOA is operated in the unsaturated regime, the amplifier gain is independent of the number of input signals and signal data rate. Outside this regime, the SOA will cause distortion because at high input powers, the gain saturates and compresses. Dynamic gain saturation occurs on the same time scale as the gain recovery time. This leads to pattern effects where the power of an incoming bit affects the gain experienced by subsequent bits. This is particularly important when the bit rate is of the same order as the inverse of the gain recovery time as shown in Figure 7. In WDM systems cross-gain modulation (XGM) between the channels can lead to severe interchannel crosstalk.

A further complication in WDM systems using SOAs is interchannel crosstalk caused by four-wave mixing (FWM). FWM is a coherent nonlinear process between two optical fields within the SOA, resulting in gain modulation at the beat frequency between the fields, and in the process generating new sidebands. In WDM systems with equally spaced wavelengths, the net effect of FWM is the generation of crosstalk terms interfering with the desired signals. Although the crosstalk can be relatively low in power terms, it can produce significant power penalties due to the coherent beat noise phenomena. The level of FWM crosstalk increases as the channel spacing decreases and the channel output power increases.



Figure 7 Typical eye diagrams of 10 Gb/s nonreturn to zero data (a) before and (b) after amplification by an SOA. ASE noise is present in the output eye diagram.

FWM crosstalk is of particular importance in dense WDM systems where the inter channel spacing is less than 100 GHz. Figure 8 shows a typical SOA output spectrum for an 8-channel multiplex with FWM-generated crosstalk signals.

Ultrashort Pulse Amplification

Optical time division multiplexing is an efficient method for increasing the bit rate of optical transmission systems. This requires the time interleaving of short optical pulses. The transmission distance is limited by the fiber group velocity dispersion, which is proportional to the pulse spectral width. Soliton transmission is also possible where the pulse shape is preserved as it propagates in the fiber.

Because an SOA has a very large bandwidth (typically 5 THz) it is capable of amplifying pulses as short as 100 fs. An input pulse can be amplified without significant distortion if the pulse energy is much less than the saturation energy E_{sat} of the SOA. Typical SOA saturation energies are of the order of a few pico Joules. As the pulse energy approaches E_{sat}, considerable spectral broadening and distortion can result. For an input pulse width τ_{p} (full width at half maximum) of the order of 10–100 ps spectral broadening is primarily due to self phase modulation (SPM). SPM is caused by gain saturation, which leads to intensity-dependent changes in the SOA active layer refractive index in response to carrier density variations. The degree of spectral broadening and distortion also depends on the input pulse shape. If τ_{p} is much less than the carrier lifetime, the output pulse power $P_{\text{out}}(t)$ and phase $\phi_{\text{out}}(t)$ are given approximately by

$$P_{\text{out}}(t) = P_{\text{in}}(t)\exp[h(t)] \qquad [3]$$

$$\phi_{\text{out}}(t) = \phi_{\text{in}}(t) - \frac{1}{2}\alpha h(t) \qquad [4]$$

with

$$h(t) = \left[1 - \left(1 - \frac{1}{G_0}\right)\exp\left(\frac{-U_{\text{in}}(t)}{E_{\text{sat}}}\right)\right]^{-1} \qquad [5]$$



Figure 8 Typical SOA output spectrum for an 8-channel WDM multiplex with 100 GHz spacing. Channel 6 has been dropped to show the FWM crosstalk signal caused by channels 5 and 7.

$$U_{\text{in}}(t) = \int_{-\infty}^{t} P_{\text{in}}(\tau)\mathrm{d}\tau \qquad [6]$$

where $P_{\text{in}}(t)$ and $\phi_{\text{in}}(t)$ are the input pulse power and phase, respectively. G_0 and α are the amplifier unsaturated gain and linewidth enhancement factor, respectively. Typical values for α are in the range 2–10 and depend on the amplifier active region material and operating conditions. The output pulse spectrum can be obtained from

$$S(\omega) = \left|\int_{-\infty}^{\infty}[P_{\text{out}}(t)]^{1/2}\exp[i\phi_{\text{out}}(t) + i(\omega - \omega_0)t]\mathrm{d}t\right|^2 \qquad [7]$$

where $\nu_0 = \omega_0/2\pi$ is the pulse optical frequency. The output pulse chirp (frequency variation) is given by

$$\Delta\nu_{\text{out}}(t) = -\frac{1}{2\pi}\frac{\partial\phi_{\text{out}}}{\partial t} = \Delta\nu_{\text{in}}(t) + \frac{\alpha}{4\pi}\frac{\partial h}{\partial t} \qquad [8]$$

where $\Delta\nu_{\text{in}}(t)$ is the input pulse chirp. Using the above theory the shape, chirp and spectrum of an amplified zero-chirp (transform limited) Gaussian pulse of input power

$$P_{\text{in}}(t) = \frac{E_{\text{in}}}{\tau_0\sqrt{\pi}} \exp\left(-\frac{t^2}{\tau_0^2}\right)$$

is shown in Figure 9. E_{in} is the pulse energy and $\tau_p \approx 1.665\tau_0$. The amplified pulse is asymmetric because the leading edge of the pulse experiences a larger gain than the trailing edge. The amplified pulse spectrum is broader than the input pulse and also develops a multipeak structure. This is due to the SPM-induced frequency chirp imposed on the pulse as it propagates through the amplifier. In this case the chirp is linear around the peak of the pulse power spectrum. It can be compensated by transmitting the pulse through an optical fiber with anomalous group-velocity dispersion. In practice optical pulses can be far from Gaussian and can also have an initial chirp. In this case the induced chirp and resulting pulse spectrum can be more complex and more difficult to compensate.



Figure 9 Amplified pulse shape, frequency chirp and spectrum for a transform-limited Gaussian input pulse with $E_{\text{in}}/E_{\text{sat}} = 0.1$ and $\alpha = 5$. ν is optical frequency. The parameter is the amplifier unsaturated gain.

When the input pulse width is less than ~10 ps, the above theory is no longer adequate and other nonlinear effects within the SOA such as carrier heating and spectral hole burning must be taken into account. The resulting pulse power and spectral distortions induced by an SOA on such pulses can be very complex.

Functional Applications

SOAs can be used to perform functions that are particularly useful in optically transparent networks. Recent advances in photonic integrated circuit and optoelectronic device packaging technology have made the deployment of SOA functional elements feasible. Two of the most important applications of SOAs are optical switching and wavelength conversion.

An example of a 2 × 2 SOA switch module used for optical routing is shown in Figure 10. Larger switch matrices can be constructed using this basic element. The module is based on a hybrid structure consisting of four integrated SOAs mounted on a silicon submount. The SOA-array is aligned to input and output polymer waveguides through V-grooves and alignment indentations. An incoming data packet can be routed to any output port by switching on the appropriate SOA. Switching times of the order of 1 ns are possible.

Ultrafast switching (<100 fs) can be achieved by incorporating SOAs in non-linear loop mirror structures, such as the terahertz optical asymmetric demultiplexer (TOAD) shown in Figure 11. Switching is achieved by placing an SOA offset from the center of an optical fiber loop mirror and injecting data into the loop via a 50:50 coupler. The two



Figure 10 2 × 2 hybrid SOA switch module.


Center
SOA
Δx
Switching pulses (λ_1)
Data pulse 1
Data pulse 2
Pulse to be switched
Input data pulses (λ_2)
50:50 coupler
Data and switching pulses out

Figure 11 Ultrahigh speed optical switching using a TOAD.



Figure 12 SOA Mach–Zehnder wavelength converter.

counter-propagating data pulse streams arrive asynchronously at the SOA. A switching pulse is timed to arrive after one data pulse but just before its replica. The switching pulse power is adjusted to impart a phase change of π radians onto the replica, so the data pulse is switched out when the two counter-propagating components interfere on their return to the coupler. The TOAD can also be used to demultiplex high-speed time division multiplexed pulse streams.

All-optical wavelength converters will play an important role in broadband optical networks. Their most important function will be to avoid wavelength blocking in optical cross-connects in WDM networks. Wavelength converters increase the flexibility and capacity of a network using a fixed set of wavelengths and can be used to centralize network management. In packet switching networks, tunable wavelength converters can be used to resolve packet contention and reduce optical buffering requirements.

Wavelength conversion in SOAs can be achieved using XGM, cross-phase modulation (XPM), or FWM. The design of an SOA wavelength converter based on XPM requires that one or more SOAs be incorporated into an interferometer, an example of which is the Mach–Zehnder interferometer (MZI) shown in Figure 12. An input data signal at wavelength λ_1 is used to modulate the upper SOA refractive index, which controls the phase shift experienced by a second unmodulated input signal at λ_2 in one of the interferometer arms. When the input data signal is low (logic 0), the arms are in phase and the λ_2 signal appears at the top output. When the input pump signal is high (logic 1) it produces an extra π phase shift between the two arms, causing them to be totally out of phase and the λ_2 signal to appear at the bottom output. Both outputs contain a copy of the original data signal imposed onto the new wavelength. Up and down conversion is possible. The lower SOA is used to equalize the gain experienced by the λ_2 signal in each of the arms. An optical filter is required at the output to remove λ_1. Such wavelength converters can operate at very high bit rates (>10 Gb/s). An important advantage of the MZI structure is that it also gives 2R regeneration (re-amplification and reshaping) of the input data signal with wavelength conversion. This is because the interferometer nonlinear response increases the converted signal extinction ratio compared to the input data. All-optical 3R (2R + retiming) regenerators are of great interest in future optical communication networks to restore degraded transmission signals. SOA-based interferometric structures can be used to achieve 3R (2R + retiming) regeneration at data rates >80 Gb/s.

See also

Coherent Lightwave Systems. **Lasers:** Semiconductor Lasers. **Optical Amplifiers:** Basic Concepts; Erbrium Doped Fiber Amplifiers for Lightwave Systems; Optical

Amplifiers in Long-Haul Transmission Systems. **Optical Communication Systems:** Optical Time Division Multiplexing; Wavelength Division Multiplexing. **Semiconductor Physics:** Band Structure and Optical Properties.

Further Reading

Agrawal GP and Olsson NA (1989) Self phase modulation and spectral broadening of optical pulses in semiconductor laser amplifiers. *IEEE Journal of Quantum Electronics* 25: 2297–2306.

Connelly MJ (2002) *Semiconductor Optical Amplifiers*. Boston, MA: Kluwer Academic.

Desurvire E (1994) *Erbium-Doped Fiber Amplifiers: Principles and Applications*. New York: Wiley.

Durhuus T, Mikkelsen B, Joergensen C, Lykke Danielsen S and Stubkjaer KE (1996) All-optical wavelength conversion by semiconductor optical amplifiers. *Journal of Lightwave Technology* 14: 942–954.

Ghafouri-Shiraz H (1995) *Fundamentals of Laser Diode Amplifiers*. New York: Wiley.

Shimada S and Ishio H (1992) *Optical Amplifiers and their Applications*. New York: Wiley.

OPTICAL COATINGS

Contents

Anti-Counterfeiting and Decorative Coatings
Diamond Optical Devices and Coatings
Laser Damage in Thin Film Coatings
Optical Black Surfaces
Thin Film Optical Coatings
X-Ray Coatings

Anti-Counterfeiting and Decorative Coatings

R W Phillips and R L Bonkowski, Flex Products, Inc., Santa Rosa, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Scientists are well known for the diversity of their interests. One topic that captures the interest of virtually all scientists, and people in general, is money. Not only are people engaged in obtaining money, but they are also fascinated about the manufacture of money and the protection of its value.

The relationship between manufacturing techniques and the protection of value documents (currency, stock shares, bonds, etc.) is not accidental. Technology has always been employed to counter the contemporary threats of counterfeiters. These threats vary, depending on the skill set and resources available to the criminal, as well as the counterfeiting strategy adopted. While we refer to banknotes repeatedly in this chapter, the information applies, as well, to passports, stamps, tax banderoles, identification cards, visas, licenses, checks, and bankcards. Banknotes can be considered the most challenging application for optical anticounterfeiting technologies. Stamps, banderoles, and checks are single-use items, and do not have to be as durable as currency. Identification cards, passports, and the like are used many times but are generally in protective covers and are examined by trained personnel. Currency must endure the rigors of commerce and travel, while still being easily authenticated by the average citizen.

The ever-increasing availability of low-cost computer hardware and software, along with color photocopiers and printers, has stimulated the use of optical and electro-optical technologies that were previously applied in a limited fashion or not at all. These optical techniques include: transmitted light devices, such as watermarks and threads; luminescent materials; reflective, interference, and diffraction schemes; modulation techniques (Moiré, for example); and light polarization effects.

Each of these concepts either has been or is likely to be applied to value documents to prevent counterfeiting. Each has its own set of potential benefits and application challenges. Also, some of these effects have been successfully applied to commercial decorative products. It is important to understand the difference between commercial and security uses. Effects aimed at commercial uses are mainly decorative or aesthetic, whereas security devices are functional and integrated into a security strategy. To ensure economic success, decorative products must be easily manufactured and widely distributed. In contrast, security products are carefully controlled in both their availability and the diffusion of manufacturing expertise.

Historical Perspective

Paper currencies (banknotes) have been printed for hundreds of years. Their history has been marked by a succession of technical changes in an effort to prevent counterfeiting. Sophisticated manufacturing techniques, such as intaglio printing and watermarks, along with special papers, made it difficult for counterfeiters to produce acceptable imitations. Intaglio is the centuries old method of printing, using incised or engraved metal plates. The tremendous pressure of the intaglio press forces the paper into an ink-coated plate engraving, forming patterns of ink on the paper.

In the eighteenth and nineteenth centuries, banknote printers often used unique engravings of guilloche patterns (intricate, overlapping curves), vignettes, and portraits as anticounterfeiting devices. These sophisticated patterns effectively discouraged early, relatively unskilled, counterfeiters. The development of photography and lithographic printing in the late nineteenth century created new opportunities for counterfeiting. Photochemical technology made it possible to produce suitable reproductions using print shop facilities throughout the world.

Photochemical techniques had significant limitations, however. The printed notes were passable but not high-quality imitations of genuine intaglio notes. Making lithographic plates required specific skill, considerable equipment, and left behind meaningful evidence (films, plates, press blankets, etc.) for police to find.

Until the 1980s, counterfeiting detection methods by governmental officials were relatively uncomplicated, as three general perpetrators could be classified in fairly predictable ways (Table 1).

Until the advent of home computers, optical scanners, color printers, and copiers, the challenge for law enforcement was difficult but focused. Amateur counterfeiting was virtually nonexistent. The effort required to make a few notes was daunting, the risk high, and potential profit meager. This meant that anticounterfeiting police efforts could be concentrated on criminal counterfeiters. Government-sponsored counterfeiting was certainly known (both the Germans and the British attempted to de-stabilize their opponents' national economies during World War II), but this was more an issue of foreign policy, diplomacy, and espionage and not the main province of national police.

The situation changed quickly and radically in the late 1980s. Color photocopiers had improved in cost, quality, and size to the point that commercial establishments were buying hundreds of machines. The 1990s introduced numerous new technologies to seduce the casual counterfeiter. These included home computers, graphics editing software, color printers, and low-cost scanners.

The amateur counterfeiter now had an array of sophisticated tools that could copy, edit, and reproduce virtually any kind of document. Banknotes made by the techniques of 'digifeiting' (a term coined by Dr. Sara Church of the US Treasury Department) were not of high quality, but passable in small quantities in low risk situations. It was now possible, economical, and relatively safe to make one or a dozen bills, especially in low denominations.

Police efforts were now severely challenged as the proliferation of amateur counterfeiters made investigation and prosecution costly. Especially in the United States, average citizens were lured by the prospect of augmenting their incomes by printing one or two notes a week. When apprehended, effective prosecution and punishment of such small-stakes criminals was expensive and unpopular.

Large-production criminal counterfeiting was augmented by new digital and electro-optical

Table 1

Class of threat	*Typical volume of notes*	*Resources and skills (1980)*
Amateur	Small (<100)	Retail paper, ink. Household chemistry
Criminal	Medium to large (1000 to 1 000 000)	Litho press, darkroom, plate making, cutting equipment. Skilled printing personnel
State-sponsored	Large (millions)	Intaglio press, currency paper. Skilled engravers and printers, Major distribution networks

breakthroughs. Lithographic plates could now be made without cameras or chemistry. Laser ablated plates made directly on the printing press (such as Heidelberg/Presstek) accurately duplicated features as small as 10 or 15 microns. Further, computer-to-plate technology with erasable plates presented an unusual opportunity for counterfeit production in small press shops.

The use of new electronic and optical tools by amateur and criminal counterfeiters coincided with a rise in state-sponsored counterfeiting. The United States, in particular, was victimized in the early 1990s by high-quality, intaglio-printed notes. One such note, dubbed the 'super $100' was allegedly produced in huge volumes in the Middle East and circulated widely in Europe.

Various means of detecting counterfeits were promoted but remain largely ineffective today. The so-called 'detector pen' applies a small amount of iodine solution onto a banknote. The iodine reacts with starch (often used to stiffen paper to give it a banknote 'feel'), turning the pen mark from light brown to black. Unfortunately, the presence or absence of starch in the paper is not a foolproof criterion. US currency paper contains no starch, while the currencies of other countries, such as Canada, have a starch component.

Concurrent with the availability of new high-tech counterfeiting tools, optical science has been hard at work to create protection schemes, utilizing the latest optical effects and manufacturing technologies. These new technologies have been largely outside the skill set and resources of amateur, criminal, and even state-sponsored counterfeiters.

An analysis of all the types of optical materials used for anticounterfeiting purposes as well as for decorative purposes shows that all are based on the control of electromagnetic radiation in the ultraviolet (UV), visible, and infrared. Exploiting various degrees of light transmission, reflectance, absorption, or scatter controls this radiation. In particular, all anticounterfeit devices fall into one or more of five basic categories: light patterning, light re-emission, light diffraction, polarization, or light interference. Characteristics of an effective anticounterfeiting solution include:

- quick verification by the average person;
- ability to function in a variety of lighting situations;
- deterrence of scanning and electronic photocopying;
- compatibility with existing banknote production schemes and equipment;
- ability to be verified by machines;
- durable and reliable despite strenuous handling conditions;
- tight control of materials and manufacturing processes.

Devices Based on Light Patterning

Watermarks

Images can be created in the paper substrate during the manufacturing process. Watermarks have been in use for at least 500 years and are produced by the arrangement of the paper fibers in the cylinder-mold paper machine or by impression in wet paper in the Fourdrinier paper machine. Because they are not on the surface of a document, watermarks are not readily visible in reflected light, but become apparent when light is transmitted through the paper substrate. Credible counterfeits, however, have been produced using images created by imprinting paper with waxy or oily substances. The fatty 'ink' is not readily detected on the surface of the document and serves to change the light transmission characteristics of the paper.

Watermarks serve chiefly to authenticate the paper substrate and to deter the practice of 'raising' notes, that is, bleaching a genuine low-denomination note and re-printing it as a higher value. The most effective watermarks are produced by the cylinder-mold process and use an image that is a duplicate of that image printed in ink (Figure 1) elsewhere on the document. This gives the examiner a reference point to compare the watermark as, for example, on all high-denomination US currency.

Watermarks are an effective counterfeiting deterrent when the general population is educated about their presence and their function. The limited opportunity to expose banknotes to a source of transmitted light (outdoors or in a dimly lit restaurant, for example) somewhat reduces their effectiveness.



Figure 1 Watermark portrait of Clara Schumann, famous pianist and wife of composer Schumann: far left – portrait in transmitted light; center – portrait in reflected and transmitted light; and right – banknote in reflection. Courtesy of Papierfabrik Louisenthal.

Threads

Thin strips of polymer or metallized polymer can be imbedded in the paper substrate during the paper-making process. Such strips are approximately 12 microns thick and 1–5 millimeters wide. These strips are known as threads because Crane & Company developed the original concept in the 1860s, using colored silk thread. Typically, threads are installed border-to-border in the narrow direction of the banknote. Because they are inside the paper, they are not seen in reflected light, but are readily visible when light is transmitted through the substrate. Such threads are effective deterrents against counterfeiting achieved by scanning or photocopying, as the scanner uses only reflected light and cannot duplicate the buried thread. Threads have evolved into several varieties:



Figure 2 Windowed thread. Reproduced with permission from De La Rue International Limited.



Figure 3 Fluorescent thread embedded into US $100 note. Reproduced with permission from Crane and Co., Inc.

- De-metallized threads: Thin polymer coated with an opaque metal. The metal is selectively removed to create text or images.
- 'Window' threads: Metallized polymer that is 'woven' in and out of the paper to permit observation in both reflected and transmitted light (Figure 2).
- Fluorescent threads: Polymer impregnated with ultraviolet inks that emit a specific color under UV irradiation (Figure 3). See the section 'Devices Based on Light Re-emission' later in this article.
- Diffractive threads: Metallized polymer strips that have been embossed with diffractive or holographic patterns and attached by hot-stamping or adhesive to the surface of the note. See the section 'Devices Based on Light Diffraction.'

Potential drawbacks to the use of threads are durability and the temptation of the general public to try to extract them from the banknote. Also, some threads can be simulated by printing or by attaching a polymer film to the surface of the banknote.

Laser Perforation

A modern 'watermark' concept is laser perforation of the banknote substrate. Precise patterns of microscopic holes (ca. 100 microns diameter) can be drilled using a high-power laser apparatus. The 200-Franc Swiss banknote features denomination numbers that are not readily visible in reflected light. However, when a light source is held behind the note, the numerals fabricated by laser perforation are clearly visible (Figure 4). In addition to being easily authenticated by non-expert observers with no special viewing apparatus, laser perforation has forensic advantages. The penetrations made by laser beams have a particular shape, spacing, and dimension, which are not easily mimicked. By clever adaptation of laser scanning software, holes of different shapes can be made and inter-mixed for additional security complexity. As a result, manual



Figure 4 Microperf® laser holes in banknote. Left image in transmitted light; right image in reflected light. Reproduced with permission from Orell Füssli Security Printing Ltd.

pin pricks and mechanically pierced holes can be discriminated as forgeries.

Reflective Foils

One of the earliest defenses against photocopying and digital scanning was the use of reflective metallic foils affixed to the surface of the document. Such foils yield >80% reflection during scanning and the resultant scanned image is usually a black field.

Attachment of foils to currency paper or documents is carried out by applying a thermoset adhesive under heat and pressure and releasing the optical film from its carrier web by means of a separate polymeric release layer. This process is known as hot-stamping. Alternatively, an ultraviolet curing adhesive can be used to affix the foil to the paper substrate using a cold roll-on process.

Foiling may impede the amateur counterfeiter; since decorative foiling of stationery and packaging is well known, it presents little challenge to the professional perpetrator.

Planchettes

Planchettes are small flakes or fragments a few millimeters in diameter and 10–25 microns thick. These are often colorful or reflective materials and can feature a variety of effects including iridescence, diffraction, fluorescence, magnetic properties, or thermochromic properties. These fragments are attached to the banknote substrate by an adhesive (Figure 5). Planchettes discourage scanning and photocopying, since the copier cannot duplicate their special properties. Unfortunately, planchettes have been found to be non-durable and easy to simulate. The generally random placement makes it difficult for an examiner to authenticate a genuine note.

Thermochromic Inks

Inks that react to temperature changes have been employed on checks and identity cards. Thermochromic inks fluctuate from one color to another when the temperature of the printed image is raised. While it is possible for body temperature to activate this change, the effect is more certain if infrared heat is used. Since the process requires several seconds to activate (depending on the heat source), thermochromic materials have not been widely used on banknotes where immediate authentication is necessary.



Figure 5 Peruvian 100 Nuevo Soles note showing iridescent planchettes. Reproduced with permission from Flex Products, Inc.

Colored Fibers

Extremely fine fibers (ca. 15 microns diameter) have been incorporated into currency papers for decades. The United States, for example, uses a few hundred grams of red and blue fibers per ton of paper in making currency. While of some forensic interest, the amount and size of the fibers makes them nearly undetectable by the average citizen.

Alternatively, fibers may be impregnated with fluorescent materials, or with absorbers that selectively absorb the wavelengths of light typically used in copy machines, producing obvious forgeries when copied.

Moiré Effects

Images can be created with very fine details that produce aliasing errors when digitized. Aliasing is the creation of new and spurious patterns through the superposition of two patterns whose periodicities are unequal. It represents interaction between the spatial frequency of the genuine document and the sampling frequency of the copying device. Aliasing is commonly known as moiré in the printing industry. Typical moiré generating patterns are constructed as closely spaced concentric circles, often found around the eyes in portraits on banknotes. When scanned digitally, the resulting copy will contain spurious images (scan traps) that are easily identified as fraudulent.

For example, if a genuine document is designed in a 1000 dpi (dots per inch) printing process it can later be scanned on a 1000 dpi scanner and, theoretically, all the data can be reproduced accurately. If, however, the scanner and the document are not in synchrony, the scanner will miss pieces of data, depending on the registration error, resulting in a digitized image that does not resemble the original.

In the scanned section of a US $5 note (Figure 6), one can see patterns of curved lines intersecting in the background, whereas the authentic image consists of fine parallel lines that do not intersect. The curvature and intersections are artifacts of the moiré created by digital scanning.



Figure 6 Scanned section of US $5 note showing moiré effect. Authentic image has no intersecting lines. Courtesy of Flex Products, Inc.

Modulation Techniques

Images produced by offset lithography are based on patterns (screens) of fine dots. By varying dot density, an array of shadings and tones can be created. More progressive modulation techniques, such as amplitude modulation (varying dot sizes) and frequency modulation (varying dot spacing) are often used to produce high-resolution images. To deter counterfeiting, banknotes can be printed using pixels, which are lines of equal length but assorted angular orientation. This technique is known as screen angle modulation (SAM).

SAM techniques can be used to defeat digital scanners by preventing the scanning of all available information due to under-sampling, or by concealing hidden patterns which are not demodulated by the human eye, but can be detected with suitable filters (Figure 7). A variant of this technology, called Scrambled Indicia®, has been used to protect US postage stamps (Figure 8).

Devices Based on Light Re-emission

Ultraviolet Fluorescent Inks

Ultraviolet (UV) inks are widely used on banknotes as semicovert deterrents. Images printed in UV inks are challenging to detect in normal lighting situations but are readily visible under UV (black light) illumination. Such printed images require a special light source for authentication and are subject to degradation over time from the handling and chemical exposure of banknotes. Typically, these products are sensitive to either short UV at 254 nanometers or long UV at 366 nanometers.

UV inks provide good protection against photocopying but can be readily simulated by more advanced counterfeiters.



Figure 7 Top image – hidden image as normally seen; Bottom image – Image decoded with visible line screen. Courtesy of Joh Enschedé Security Printing Ltd.


USA32
UNITED STATES POSTAL SERVICE
USPS EXCLUSIVE LICENSEE OF GSSC
©1975,1997-SCRAMBLED INDICIA®

Figure 8 Hidden image in 32¢ US postage stamp decoded by invisible line screen (left image – normal view; right image – with decoder in place). Courtesy of Flex Products, Inc.

UV Fibers

Several countries mix minute quantities of UV luminescent fibers into the paper substrate. In most cases, these are randomly placed and invisible to the naked eye.

Devices Based on Light Diffraction

Diffractive structures range from simple periodic surface relief structures (textured surfaces) to multilevel holographic structures that form a continuum of products ranging from decorative coatings to anticounterfeit devices. Figure 9 shows a generalized structure for all known types of reflective-based relief structures.

Most devices are based on reflection; however, in a few instances where clear polymer is used, devices may also be based on diffractive light transmission. The sizes, shapes, and orientation of the grooves vary according to the exact device. The opaque aluminum layer insures that the design works in reflected light. Most of these structures exhibit a rainbow effect where the color moves from short to long wavelength as the viewing angle increases. This rainbow effect can be found for all types of structures with grooves that have sizes near that of light wavelengths. The color shifts in a direction opposite to that of a thin film interference structure. Further, the rainbow effect can only be seen in a direction perpendicular to the groove direction. In the special case where the groove dimensions are less than the wavelength of light, the



Figure 9 Cross-section of diffraction device. Courtesy of Flex Products, Inc.

rainbow effects disappear and are replaced by another type of diffraction (zero-order diffraction), where only specific colors are seen in reflection. Groove height and width for all diffraction products range from 0.1 to 10 microns.

For a unique set of discrete angles and for a given spacing d, the diffracted light from each facet is in phase with the light diffracted from any other facet, so they combine constructively:

$$Gm\lambda = \sin\alpha + \sin\beta \qquad [1]$$

where $G = 1/d$ is the groove density or pitch, α is the angle between the incident light and the normal to the grating, β is the angle between the diffracted beam and the normal to the grating and m is an integer called the diffraction order.

For $m = 0$, $\beta = -\alpha$ for all λ, the grating acts as a mirror and the wavelengths are no longer separated. This is called specular or zero-order reflection.

In contrast to grating structures (linear grooves) that only modify light intensities, holographic structures are complex surface contours that modify both the phase and intensity of the reflected light. Light reflecting off a metallized holographic structure is capable of producing an image in either two dimensions (2D) or three dimensions (3D). Heat and pressure may emboss the relief structure into a metallized polymeric film by hot-stamping. Alternatively, an embossing metal roller presses the relief image into a thermoplastic film or thin ultraviolet curable coating. The embossed structure is subsequently metallized with opaque aluminum or with a high-index dielectric material such as zinc sulfide or zirconium dioxide. The latter layers allow printed information on the substrate to show, while at the same time provide a holographic image. However, such high-index holograms are not as bright, since some of the reflective light is lost in transmission. Polymethylmethacralate (PMMA), polycarbonate (PC), polyvinyl chloride (PVC), and polyester (type G) are typical materials that can accept such an embossing.

Thick metallized embossed plastic films of ca. 50 microns are used for decorative labels. Thin metallized embossed hardcoats of ca. 7 microns, which can be released from carrier sheets or embossed thin plastic films, are used for the security field.

Holograms used for high-security applications have one characteristic that distinguishes them from ordinary holograms or other diffractive devices used for decorative purposes. This characteristic finds itself in the complication of images, multilevel images at different focal depths, different images that appear at various viewing angles, images of 3D objects superimposed with synthetic 2D images, micro-images, or images that appear to move as the device is tilted back and forth. Specific types of diffractive structures are described below. The list starts with simple holograms used in decorative markets and progresses to high-security devices.

Diffractive grating: A structure comprised of square or sinusoidal linear grooves that breaks light into its component colors. An assemblage of abutting islands, each randomly oriented and with its own parallel grooves, gives the viewer a twinkling color effect (Figure 10).

2D hologram: A relief structure that, upon viewing with a point source of light, shows a 2D image of objects, text, logos, or lines that emerge over a background. Such holograms are often referred to as 'cartoon images' since they are images of original drawings (Figure 11). Because of their simplicity and frequent use as decorative packaging, these holograms are generally not used in the security market.

Multilevel 2D hologram: A relief structure that shows a simulated 3D effect. This is accomplished by creating an image with two or more layers of flat artwork, with each layer at a slightly different focal depth (Figure 12). These images are well suited for labels, cards, and other decorative products. They have also been used on coupons, gift certificates, and tickets.

3D hologram: A relief structure that reconstructs a 3D image from a real or computer-synthesized 3D object (Figure 13). A 3D dove has been used on the VISA credit card as a security device for many years, though many now consider it more of a marketing logo than a security feature.

2D/3D hologram: A relief structure that reconstructs an image showing both a 3D and a 2D object, created from a 3D sculpture and flat art drawings (Figure 14). The artwork is created in such a way that the images appear at different depths of view.

Stereo-hologram: A relief structure that reconstructs a 3D image such that upon tilting from side to side one can see around the object, and additional features can then be viewed. At any given angle, it appears to be a 3D hologram. The image is created through multiple exposures of a 3D object during the holographic mastering process.



Figure 10 Picture of a typical diffractive assemblage of gratings. Reproduced with permission from Amagic Holographics Inc./K-Laser Technology, Inc.



Figure 11 2D hologram. Courtesy of American Bank Note Holographics, Inc.



Figure 12 Multilevel, 2D hologram. Courtesy of American Bank Note Holographics, Inc.



Figure 13 3D hologram. Courtesy of American Bank Note Holographics, Inc.



Figure 14 2D/3D hologram. Courtesy of American Bank Note Holographics, Inc.



Figure 15 True color hologram. Reproduced with permission from Light Impressions International, Inc.



Figure 16 High-definition security hologram. Number 50 appears in various colors in first angle of view. Colored shells appear at another angle of view. Reproduced with permission from DeLaRue International Limited.



Figure 17 Left and center images – Exelgram™ at two different viewing angles. Reproduced with permission from CSIRO. Right image – HiMax® OVD high security device showing portrait of Sir Isaac Newton. Reproduced with permission from Light Impressions International, Inc.

True color hologram: In contrast to the holograms described above, a true color hologram is created by diffraction angle control of the colors red, green, and blue from a 3D object or color transparency. The relief structure, when viewed in white light, reveals a picture in true color, as opposed to the rainbow effect seen in regular 2D and 3D holograms (Figure 15).

High-definition security hologram: A relief structure that produces an image composed of multiple elements, such as fine line text and complex patterns that simulate movement as the device is tilted back and forth. Different images also appear at different angles (Figure 16). These images occur because different images are recorded in the holographic mastering process at different angles. The complicated imagery and the use of multiple images is the major holographic technique in use today for anticounterfeiting.

High-definition diffraction gratings: The relief structure in Figure 17 shows a multitude of elements, each with colors that change upon tilting. It consists of a very fine line grating structure, 1000 lines or greater per millimeter. These gratings are sometimes combined with holographic images that change depictions upon tilting, thus providing a high level of security.

Kinegrams®: This grating structure, based on computer-generated graphic images, is composed of light diffracting microstructures of less than one micron, with blaze (saw-tooth) contours that when viewed display optokinematic movements. This security device was first used in 1987 on Austrian 5000 Schillings. When the orientation of the blaze grating changes across the device, two distinct images are possible, depending on the view with respect to the blaze angles. The images do, however, require an aluminum reflective layer deposited onto the relief structure in order to generate the highly reflective colored images.

A 180° rotation of the device can lead to a marked change in the diffraction properties and, consequently, the image properties. This stands in contrast to holographic symmetrically based structures that yield identical images. An example of a Kinegram® security device is shown in Figure 18. The letter ‘K’ on the front facet of the cube is filled with an asymmetric structure, whereas the background is realized by using the same structure rotated by 180°. When viewed from one side, the letter ‘K’ appears bright on a dark background. Upon rotation in its plane by 180°, the contrast between the letter ‘K’ and the background is reversed.

Zero-order diffraction grating: This relief structure is quite different from holographic or normal grating structures, as it is based on an abrupt change in the



Figure 18 The Kinegram® security device as seen in two views differing from each other by a rotation of 180° in its plane, while illumination and viewing conditions remain unchanged. Reproduced with permission from OVD Kinegram Corporation.



Figure 19 Zero-order diffraction images in a DID® security device: two views 180° apart in planar rotation. Reproduced with permission from Hologram Industries.

refractive index from approximately 2.3 to 1.5. Rather than employing an aluminized layer for reflection, the structure uses a thin, high-index layer ($n = 2.3$, for example) embedded in an organic polymer with a refractive index of about 1.5. The high-index layer appears as a parallel series of lines, approximately 0.2 microns wide, with another parallel series of lines beneath the first set, but oriented under the spacing of the first set of lines at a depth of about 0.2 microns.

This structure not only changes color as the device is tilted back and forth but also as it is rotated. In rotation, the color changes from red to green (Figure 19). Further, the light is polarized as it reflects. When a linear polarizer is inserted between the eye and the device, the color changes to black. The colors seen are based on specular zero-order reflection, unlike standard diffraction gratings where the reflected color is based on first-order reflection. The preeminent effect is when the device is placed over a black background. Over a white background the colors are subtler. Viewing reflection in zero order allows one to see the reflected colors in both point and diffuse lighting. The combination of polarization effects and color in rotation is ideally suited to high-security applications.

Devices Based on Light Interference

Thin-Film Foils

There are two types of thin-film interference devices. The first is based on an all-dielectric filter, and the second is based on a Fabry–Perot resonance cavity structure of the type absorber/dielectric/reflector. The all-dielectric filter uses pairs of high and low refractive index materials at a quarter-wave thickness. A typical filter is the one used initially on Canadian currency that employed the design: ZrO_2 1QW/SiO_2 3QW/ZrO_2 1QW/SiO_2 3QW/ZrO_2 1QW, where the QW (quarter-wave optical thickness) is centered at 585 nm. This design exhibits a gold-to-green color shift with viewing angle.

A Fabry–Perot filter also has a gold-to-green color shift and typically uses the design Cr 5 nm/MgF_2 4QW @ 604 nm/Al (opaque). This filter has slightly higher color saturation than the all-dielectric filter. The design is opaque and, therefore, the color observed is independent of the substrate color onto which it is affixed. This stands in contrast to the all-dielectric filter that must be laid over a black background for optical color saturation. If the all-dielectric filter is placed on a white background, the transmitted light passing through the optical filter will reflect off the white background and combine with the filter's reflection to give white light. However, with a varied colored background, the reflected color will vary depending on the combination of reflected color from the substrate and the reflected color from the filter.

The gamut of reflected colors from a metal–dielectric foil covers all four-color quadrants in the CIE Lab color space. Brightness of the foil depends on the materials used and on the design. Figure 20 shows the theoretical gamut of colors as plotted on the a^* b^* plane for the design, using the materials Cr, MgF_2 and Al.

Foils based on thin film interference layers contain a reflectance peak property moving from long wavelength to short wavelength as the viewing angle is increased. This is true across the UV, through the visible and into the near-infrared. To the human eye, the color moves from red to blue. The anti-counterfeit foil shown in Figure 21 exemplifies this effect.

Shifts from long to short wavelength occur because the path light difference (see the bold line in Figure 22) between the rays of light that reflect from the surface and the reflector are a function of the cosine of the incidence angle.

The path length difference is shown by the term $2d \cos \theta$, where θ is the angle of incidence within the



Figure 20 Gamut of colors at 0° incidence viewing under Illuminant C produced from Fabry–Perot designs as a function of quarter-wave optical thickness. Courtesy of Flex Products, Inc.



Figure 21 Anticounterfeit interference foil on brake shoes. Reproduced with permission from November AG.



Figure 22 Diagram showing the principle of optical shift with viewing angle. Courtesy of Flex Products, Inc.

filter and d is the distance between the surface of the filter and the reflector. The angle θ and the angle ϕ are related by Snell's law: $n_0 \sin \phi = n_1 \sin \theta$.

Light interference occurs where the wavefronts superimpose on one another. The fractional number of wavelengths that can fit into this path length difference is given by $\Psi = 2n_1 d \cos(\theta)/\lambda$, where λ is the wavelength of light. Waves reflected from these two surfaces will interfere constructively when Ψ is an integral number of wavelengths and interfere destructively when Ψ is at multiples of half wavelengths. As the viewing angle (ϕ) increases, the angle θ also increases. Thus, constructive interference translates into a reflectance peak that moves toward shorter wavelengths as the angle of viewing is increased due to its cosine dependence.

The Fabry–Perot filter can use any transparent dielectric (colored or clear), a reflective metal, although optical metals are preferable since they have the highest reflectance (e.g., Ag, Al, Ni, Cu), and an absorber that is partially transmissive and partially reflective. Thin metals, absorbing dielectrics, and metal nitrides are typical materials used as an absorbing layer.

Light Interference Inks

Inks based on interference pigments have been developed over the last thirty years, starting with pigments based on high-index thin film coated micas (typically TiO_2 coated micas) and culminating with



Figure 23 Left image – cross-section of interference mica; right image – cross-section of optically variable pigment (OVP®). Courtesy of Flex Products, Inc.

OVP® pigments based on the Fabry–Perot structure (Figure 23).

Inks created from micas are known as pastel or pearlescent inks, whereas inks formulated from OVP® are known as optically variable inks (OVI®). The latter inks are used as a primary defense against counterfeiting, defeating color copying and color printing from computer images. The difficulty with using interference micas for security features is that they can be readily purchased in the commercial world. In contrast, OVP® is a tightly controlled material and cannot be purchased by the general public.

OVI® security ink has been formulated into intaglio, silkscreen, flexographic and gravure applications. Its use on security documents encompasses over 75 banknotes worldwide, including the newly issued Euro notes, post-1996 \$10, \$20, \$50, and \$100 US banknotes, and banknotes for China. With the use of such inks, postage stamps, tax stamps, identification cards, and other security documents have also been effectively protected against counterfeiting. Color control for OVI® is assured because OVP® can be blended according to additive color theory to produce a desired color and color shift. Two examples of OVI® – the 100 Pula Botswana note and the new 100 Euro note – can be seen respectively in Figures 24 and 25.

OVI® inks have been extremely successful for banknote protection and might even be a *de facto* standard, because they meet the seven characteristics of an effective anticounterfeit solution as described earlier.

Devices Based on Light Polarization

The use of light polarization as an anticounterfeit feature has taken several avenues, one as coatings or pigments, the other as invisible images that are detected with a linear polarizer. With the exception of the zero-order diffraction device described earlier, polarization devices are based on cholesteric liquid crystals, using either nematic (planar oriented) layers or helical twisted layers.



Figure 24 100 Pula Botswana note showing green-to-blue color shift OVI® with latent images. Reproduced with permission from SICPA.



Figure 25 100 Euro note showing magenta-to-green OVI®. Courtesy of Flex Products, Inc.

Liquid crystal pigments are constructed from cholesteric polysilozanes that have been oriented and cross-linked in place with photopolymerization. With this cross-linking, pigments are relatively stable to temperature changes. These materials can form helical structures in either right or left twist orientation. Such materials reflect 50% of a band of wavelengths, centered at wavelength, λ_0, of the incoming light as circularly polarized light and 50% of the band centered at λ_0 as transmitted, circular polarized light, but with the opposite twist. The remaining wavelengths pass through the structure with no interaction. The amount and type of the chiral phase (components that inherently orient into a helical structure) in the polymer determine the pitch of the helical structure. This, in turn, determines the wavelength of reflection, i.e. $\lambda_0 = nP$ where n is the average refractive index and P is the pitch length of the material (pitch length determined by 360° rotation of the helix). At tilted viewing angles, the color changes according to the formula $\lambda = \lambda_0 \cos\theta$ where θ is the viewing angle relative to the vertical, and λ_0 is the reflected wavelength seen perpendicular to the surface. By the judicious combination of left- and right-handed helical based layers, or by inserting a half-wave retarder layer between two layers having the same helical structure, the resulting pigments reflect nearly 100% at λ_0.

When these materials are properly processed and ground (particles 2–50 microns thick, with an aspect ratio of 3:1 in lateral/thickness dimensions), particles with the helical structure perpendicular to the planar surfaces can be realized. Such pigments, or liquid crystal polymeric coatings, when printed, have color-shifting properties with viewing angles that defeat color copiers and the like, since toners have no color-shifting properties (Figure 26). These pigments also have an additional security feature, namely, that when viewed through a circular polarizer having the opposite twist, the color-shifting pigments appear black.



Figure 26 Anticounterfeit label showing liquid crystal coating viewed straight-on and at tilt angles. Courtesy of Flex Products Inc.

A special technology known as linear photo-polymerization (LPP) is a process to produce photo-patterned liquid crystal polymer (LCP) $\lambda/4$ phase retarders, which, when combined with a series of layers involving a reflector, and a linear polarizer, shows positive and negative images. Without the diagnostic linear polarizer, however, the image is invisible (Figure 27).

Adding a nematic liquid crystal layer, which exhibits a helical twist configuration, extends this technology. The latter technology can produce colored images when viewed with a linear polarizer. Such devices can be coated or hot-stamped onto a substrate containing viewable information.

Combination Devices

Beginning in 2000, combinations of holographic structures with liquid crystal or interference thin films were developed, which could make counterfeiting even more difficult. Such structures emerge as a hologram floating on a color shifting background. Magnetic layers, integrated into part of the optical interference stack, allow spatial orientation and 3D effects during printing.

Decorative Coatings

Coatings Based on Diffractive Pigments

When pigments based on diffractive effects are created, individual flakes have surface contours of groove-like structures of 2000–3500 lines mm^{-1}. In spray-out coatings using such pigments, diverse interplay of subtle rainbow colors results (Figure 28). The effect is particularly striking in full sunlight as, for example, on curved surfaces found on cars and motorcycles. Some manufacturers have successfully used finely shredded diffraction gratings



Figure 27 Reflective optical LPP/LCP security device showing a complex LPP/LCP retarder image visualized with one polarizer; rotation of the polarizer changes the image from positive to negative. Reproduced with permission from Rolic Research, Ltd.



Figure 28 Motorcycle painted with diffraction-based pigments. Courtesy of Flex Products, Inc.

(ca. 25 microns thick) as flakes mixed in paints for decorative purposes. The use of such thick flakes seriously limits the applicability and uniformity of the coating.

Coatings Based on Interference Pigments

Pigment-based interference effects are widely known and have been used for decades in the paint, plastics, and cosmetic industries. These structures are based on TiO_2 coated mica, where the mica thickness is between 300 and 600 nm with planar diameters ranging from 1 to 200 microns, depending on the application.

Depending on the thickness of the TiO_2, different reflective colors of silver, gold, red, blue, and green are achievable. For maximum color reflection, a black substrate or viewing at a particular angle is required so as to prevent dilution of the reflected color from light reflected from the substrate surface. Colored mica pigments are platelets of mica coated with colored oxides. Metallic-like colors are also formed from iron oxide coated micas. In the first instance, two colors may be seen: the platelet color (due to absorption) and the interference color at one angle. Only the interference color may be seen at another viewing angle. If the substrate is colored, the color switches from the interference color to the substrate color as the viewing angle changes. More recently, laminar pigments with an all-dielectric optical stack have been produced with a low-index central core, encapsulated with high-index layers that cause interference.

Interference pigments based on absorber/dielectric/metal/dielectric/absorber have also been introduced into the decorative marketplace. These structures are based on aluminum as the central layer, a dielectric spacer layer, and either a wavelength selective absorber layer such as iron oxide (Fe_2O_3) or a nonwavelength selective absorber such as chromium (Cr). In Fe_2O_3 based pigments, the face-on colors are mainly found in the yellows and reds whereas for the Cr-based pigments, a full color gamut is possible.

Diffractive Foils

These foils are based on diffractive and grating surfaces where the contours are generally less than 2000 lines mm^{-1}. These materials show a glittering effect, i.e., multiple points of color, as the viewing angle is changed.

Interference Polymeric Films

These films are made from multilayer extrusions of pairs of polymers of 50 or more layers. Each pair is composed of two different polymers with a slightly different refractive index. Each layer is approximately one-quarter wave in thickness. Due to the small refractive index differences between layers, the resultant film is approximately 25 microns thick. Uniform color at a given viewing angle is generally not possible due to the lack of thickness control. Hence, they tend to look like oil slicks, with each color changing as the viewing angle changes (Figure 29). Interference polymeric films have found use as decorative gift wrapping material.

Holographic Foils

As indicated earlier, holograms designed for non-security markets may range from simple 2D holograms to more complex ones that function for either decorative or brand protection purposes. Another application of holographic foils is in holographic fabrics, whereby small holograms approximating several millimeters in diameter are affixed in a pattern to the cloth (Figure 30).

Aluminum Flake Based Inks and Coatings

These inks are composed of leafing or nonleafing aluminum powders and a polymeric vehicle. The use of leafing pigments produces images and coatings of high brilliance, whereas nonleafing pigments produce a matte or satin-like finish.

Figure 29 Visual effect from multilayer extruded polymeric film. Reproduced with permission from Englehard Corporation.

Summary and Challenges for the Future

Optical scientists have shown tremendous creativity in discovering and employing clever technical devices in the fight against counterfeiting of valuable documents. Optical solutions have been created that meet the functional as well as the economic needs of the document security industry. A cadre of research institutions and manufacturing companies has accepted the challenge of protecting the instruments of our economic and physical security.

This vigilance will have to continue in the future. Nearly as fast as new defenses are developed, criminals are illicitly using new tools to defeat the protection schemes. Financing for sophisticated counterfeiting efforts is likely to increase, whether sourced by international terrorists or drug dealers. Likewise, the more we move toward an information society, the more we depend on machines to count, sort, and verify documents and money. This machine-driven trend will mandate new features, especially in banknotes and cards.

Figure 30 Fabrics showing holographic effects. Reproduced with permission from Amagic Holographics, Inc./K-Laser Technology, Inc.

It is likely that the future of optical anticounterfeiting technology will be strongly influenced by:

- Active, rather than passive, devices. That is, devices that can be applied to a document and later stimulated or interrogated by a machine to elicit a specific effect or signal.
- Schemes that may be merged with new biometric technologies, especially for individualized documents, such as passports and identification cards. In such applications, it will be necessary to confirm that a document is genuine, and that it is in the possession of its rightful owner.
- The need to clearly differentiate security applications from decorative or aesthetic uses. Effective security products must always be carefully controlled and their availability limited.
- The willingness of the public to accept regular changes in the appearance of value documents. Currency will have to undergo redesign on a three-to-six year cycle, rather than the long cycles typical in the past.

This chapter was intended only as a survey of the issues involved in anticounterfeiting protection. To learn more about the optical methods discussed here, or to learn more about the science of anticounterfeiting, please consult the "Further Reading" section and the Internet sites listed in Table 2.

Table 2 Internet sites: Banknote Design & Protection

Sponsor	*Web Address*
Amagic Holographics, Inc.	http://www.amagic-usa.com/
American Bank Note Holographics, Inc.	http://www.abholographics.com/
Bank of England	http://www.bankofengland.co.uk/banknotes/index.htm
Bundesdruckerei GmbH	http://www.bundesdruckerei.de/en/products/index.html
Crane & Co.	http://www.crane.com/specialty_papers/default.asp
Engelhard Corporation	http://www.engelhard.com/
European Central Bank	http://www.ecb.int/
Flex Products, Inc.	http://www.ocli.com/markets/flex_products.html
Giesecke & Devrient	http://www.gdm.de/eng/main/home/index.php4
Graphic Security Systems Corp.	http://www.graphicsecurity.com
Hologram Industries	http://www.hologram-industries.com/pages/index.htm
Joh Enschedé	http://www.joh-enschede.nl/divisies/jess-engels.html
K-Laser Technology, Inc.	http://www.klaser.com.tw
Light Impressions International, Inc.	http://www.lightimpressions.com/
November AG	http://www.november-ag.de
OVD Kinegram Corporation	http://www.kinegram.com/
Papierfabrik Louisenthal GmbH	http://www.louisenthal.de/
Rolic Research, Ltd.	http://www.rolic.com/
SICPA Security Inks	http://www.sicpa.com/default.asp?lang=e
Thomas De La Rue	http://www.delarue.com/
United States Bureau of Engraving	http://www.bep.treas.gov/

The authors express their gratitude to Ms. Sue Spadini for the technical editing of this work, and to the many individuals and companies who provided exemplars and illustrations. Please see the figure captions and the reference lists for their names.

List of Units and Nomenclature

2D	two-dimensional
3D	three-dimensional
CIE	Commission Internationale de l'Eclairage; International Commission on Illumination
CIELAB color space	($L^* =$ Lightness; $a^*.b^* =$ chroma coordinates)
CMYK	cyan-magenta-yellow-black
QW	quarter wave

See also

Holography, Techniques: Color Holography; Holographic Interferometry; Holographic Recording Materials and their Processing; Sandwich Holography and Light in Flight. **Microscopy:** Interference Microscopy. **Optical Coatings:** Thin-film Optical Coatings. **Polarization:** Introduction; Matrix Analysis.

Further Reading

Committee on Next-Generation Currency Design, National Materials Advisory Board (1993) *Counterfeit Deterrent Features for the Next Generation Currency Design.* Washington, DC: National Academic Press.

Demus D, Goodby J, Gray GW, Spiess HW and Vill V (eds) (1998) *Handbook of Liquid Crystals*. Weinheim, Germany: Wiley-VCH.

Fagan WF (1990) *Optical Security and Anticounterfeiting Systems*. Volume 1210. SPIE Conference – The International Society for Optical Engineering. Bellingham, WA.

Faris SM (1994) US Patent 5,364,557: *Aligned Cholesteric Liquid Crystal Inks.*

Glausch R, Kieser M, Maisch R, *et al.* (eds) (1998) *Special Effect Pigments*. Hanover, Germany: Vincentz Verlag.

Hutley MC (1982) *Diffraction Gratings*. London: Academic Press.

Phillips RW and Bonkowski RL (2000) *Security Enhancement of Holograms with Interference Coatings*. Volume 3973. SPIE – The International Society for Optical Engineering. Bellingham, WA.

Phillips RW and Nofi M (1999) *Colors by Chemistry or by Physics?* Society of Vacuum Coaters 42nd Annual Technical Conference Proceedings, pp. 494–499, Chicago, IL.

Phillips RW, Nofi M and Slusser R (1994) *Color Effects From Thin Films Designs*. Eighth International Conference on Vacuum Web Coating, pp. 270–284. Las Vegas, NV.

Proceedings of the International Conference on Security Documents for the 21st Century (1987) San Diego, CA. Prepared by Oak Ridge National Laboratories, CONF-87040175, Contract DE-A-C05-840R2140, Oak Ridge, TN 37831.

Rancourt JD (1987) *Optical Thin Films, Users' Handbook*. New York: Macmillan.

US House of Representatives (1984) *The Currency Design Act*. Hearing Before the Sub-Committee on Banking, Finance, and Urban Affairs, Second Session on H.R. 6005, Serial No. 98-98. Washington, DC: US Government Printing Office.

Van den Assem B, Brongers D, Rath J, *et al.* (1994) *Practical Guide for the Security Documents Printing Sector.* The Hague: SDU Uitgevererij Koninginnegracht.

Van Renesse RL (1994) *Optical Document Security.* London: Artech House.

Van Renesse RL (1996) *Optical Security and Counterfeit Deterrence Techniques*. Volume 2659. SPIE Conference – The International Society for Optical Engineering. Bellingham, WA.

Van Renesse RL (1998) *Optical Security and Counterfeit Deterrence Techniques II*. Volume 3314. SPIE Conference – The International Society for Optical Engineering. Bellingham, WA.

Van Renesse RL and Vliegenthart WA (2000) *Optical Security and Counterfeit Deterrence Techniques III*. Volume 3973. SPIE Conference – The International Society for Optical Engineering. Bellingham, WA.

Diamond Optical Devices and Coatings

D M Aslam, Michigan State University, East Lansing, MI, USA

© 2005, Elsevier Ltd. All Rights Reserved.

What do a human, a plant, the photoresist used in microfabrication, and a polymer have in common? Why has carbon become a crucial part of all known living systems? The answer to these questions may be embedded in carbon's hybrid bonding structure (sp, sp^2, and sp^3 C–C bonds). Carbon has 4 electrons in its outermost shell (the valence shell), which is the second shell. At first sight, one would expect that these 4 electrons are distributed among its one 2s and three 2p orbitals. However, it is well known that, in the diamond lattice, each carbon atom bonds with its four neighbors. Are the electrons in 2s and 2p orbitals responsible for the four bonds? One possible answer is that the 2s, $2p_x$, $2p_y$, and $2p_z$ orbitals of the carbon atom form bonds with their neighbors. There are two problems with this answer. First, these bonds will have different strengths (s and p orbitals), which is in contradiction with the experimental fact indicating an equal strength for all the four C–C bonds in the diamond. Second, the computed strength of such bonds will be lower than that found experimentally. What is then the nature of C–C bonds found in organic compounds?



Figure 1 Hybridization of s and p orbitals in carbon to form sp^3 orbitals, which form the so-called sigma bonds responsible for the strong diamond lattice.

The answer to this difficult question was provided in 1931 by Linus Pauling (1901–1994), the winner of two Nobel prizes. With the help of quantum mechanical calculations, Pauling showed how one s orbital and three p orbitals can mix, or hybridize, to form four equivalent atomic orbitals with tetrahedral orientation. The resulting hybrid orbitals are called sp^3 orbitals as shown in Figure 1. The sp^2 or sp^1 orbital results if two or one p orbital combine with the s orbital, respectively, to form the hybrid. While sp^3 C–C bonds lead to a diamond lattice, the sp^2 C–C bonds lead to graphite, and a material which contains both sp^2 and sp^3 C–C bonds is called diamond-like carbon (DLC). The optical properties, such as the bandgap, of DLC depend on the sp^3/sp^2 ratio. If a sheet consisting of a monolayer of graphite, which consists of sp^2 bonds, is wrapped into a pipe, the resulting structure is called a single-wall nanotube (SWNT), as shown in Figure 2a. A multiwall nanotube (MWNT) has many such layers (Figure 2b–c). Other elements such as oxygen (in H_2O) and nitrogen (in NH_3) also form sp^3 orbitals but carbon seems to be only one which is capable of forming sp, sp^2, or sp^3 bonds, depending upon the bonding environment (Figure 3). This may explain why nature has selected carbon



Figure 2 CNT: (a) drawing of a single wall CNT showing sp^2 bonded layer; (b) a mat of multi-wall CNTs; and (c) a TEM of MWNT showing 13 sp^2 bonded layers.


Sp^3 C–C bonds; crystalline diamond inside the grain
Sp^2 and Sp^1 C–C bonds; non-diamond phases at the grain boundaries
2 micrometers

Figure 3 Polycrystalline diamond film; crystalline regions separated by grain boundaries containing non-diamond phases.

Table 1 Comparison of semiconductor properties

Property	*Diamond*		*Si*	*GaA*	*β*-SiC
	Poly-C	*Crystalline*			
Fig. of merit					
Johnson, 10^{23} W Ω s^{-2}		73 856	9	62.5	10 240
Keyes, 10^2 W cm^{-1} s^{-2} °C		444	13.8	6.3	90.3
Sat. electron vel., 10^7 cm s^{-1}		2.7	1	1	2.5
Carrier mobilities, (cm^2 V^{-1} s^{-1})					
Holes	1–165	1600	600	400	50
Electrons		2200	1500	8500	400
Resistivity, Ω cm	10^{-2}–10^8	10^{-3}–10^{13}	10^{-4}–10^8	?–10^8	150
Breakdown field, MV cm^{-1}	0.1–1	10	0.3	6	4
Band gap, eV		5.45	1.12	1.42	3
Dielectric constant	6.7	5.5	11.7	12.5	9.7
Thermal expan. coeff., 10^{-6} °C^{-1}	2.6	1.1	2.6	5.9	4.7
Thermal cond., W cm^{-1} K^{-1}	20	4–22	1.5	0.5	5
Lattice constant, Å		3.57	5.43	5.65	4.36
Density, g/cm^3		3.52	2.32	5.31	3.215
Melting point, °C		4000[a]	1412	1240	2540
Hardness, kg mm^{-2}		10 000	1000	600	3500
Poisson ratio	0.11	0.15	0.23	0.315	
Young's modulus, 10^{12} Pa	0.8–1.2	1.1–1.2	0.155	0.085	0.7

[a] Diamond may convert to graphite well below 4000 °C depending upon the ambient and it oxidizes at 650 °C to form CO_2/CO in O_2.

(perhaps due to its bonding flexibility, to form long C–C chains and rings) as the material of choice for building living systems.

The sp^3 bonding in a diamond lattice makes it a very unique material with a combination of properties not matched by any other known materials (Table 1). In fact, the C–C sp^3 bond in diamond is responsible for its remarkable properties leading to current and potential applications as shown in Figure 4. Although diamond (for centuries) and its bonding structure (for over 70 years) has been known for a long time, the growth of diamond films using chemical vapor deposition (CVD) took a long time to mature. Again, this delay relates to the difficulty with which the diamond lattice with sp^3 C–C bonds is fabricated.

Diamond Growth by CVD

First evidence of diamond growth by CVD, by Eversole in 1952–1953, led to the use of H_2 and CH_4 in the hot filament CVD (HFCVD) to grow diamond on diamond substrates (homoepitaxial growth) by Angus in 1971. The inexpensive CVD polycrystalline diamond (poly-C) was grown on non-diamond substrates by Deryagin in 1976, Spitsyn in 1981, and by Matsumoto *et al.* in 1983. Currently,


Sp^3 bonds
in the diamond
lattice lead to its
unique properties
C
Optical; windows,
coatings, RFMEMS,
Optical MEMS, switches,
microlenses, spectrometers, etc.
Mechanical; coatings, abrasives, tools, MEMS, etc.
Electrical; devices, semiconductor, packaging, sensors, etc.
Thermal; heat sinks, sensors, bolometers, heaters, etc.
Chemical; electrodes, sensors, coatings, etc.

Figure 4 Sp^3 bonds in diamond make it a unique material.

Table 2 Different diamond deposition methods

Methods	*HFCVD*	*MPCVD*	*DC-arc Jet CVD*	*Combustion synthesis*	*Multiple pulsed laser*
Deposition rate (μm/hr)	0.1–10	0.1–10	30–150	4–40	3600
Substrate temperature (°C)	300–1000	300–1200	800–1100	600–1400	50
Deposition area (cm^2)	5–900	5–100	<2	<3	N/A
Advantages	Simple, large area	Quality, stability	High rate, good quality	Simple, high rate	Ultra-high rate
Disadvantages	Contamination, fragile filament	Rate	Contamination, small area	Small area	Expensive

HFCVD, hot filament CVD.

it is believed that, during the CVD of diamond, the CH_3 is responsible for deposition of C as diamond and non-diamond phases. The atomic hydrogen, present in the growth environment, removes the non-diamond phases leaving behind the diamond phase. Near the end of the 1990s, basic science of CVD diamond was well understood, and today diverse plasma and thermal techniques have been developed to produce poly-C films several mm thick and over 12 inches in diameter. Optically smooth 300-micrometer thick undoped poly-C wafers are available on the market. Although there are some reports of n-type poly-C and crystalline diamond growth, the well-established techniques exist only for *in situ* doping of p-type diamond.

A number of diamond growth techniques are currently available for the growth of diamond and carbon nanotubes. Microwave plasma CVD (MPCVD) can be used for the growth of both diamond and carbon nanotubes. As shown in Table 2, the deposition rate of diamond shows a large variation (0.1–3600 micrometers/hour) depending on the growth technique. For applications of diamond in optical coatings, optoelectronic devices and optical systems, the study of transmission, reflection and absorption of light for diamond is very important. These properties of diamond are responsible for its beauty and glamor. For applications in optoelectronic materials, devices and systems, the micro-fabrication and -machining technologies are crucial, particularly in the case of inexpensive poly-C films.

Absorption, Reflection, and Transmission in Diamond

The optical properties, which have been studied for hundreds of years, of naturally occurring single crystal diamond have led to the gem commerce. The fundamental concept involved in the tremendous historical fame of diamond is its high refractive index, n_d (in the range of 2.38–2.64 depending upon the wavelength of light). The refractive index of a material is a measure of decrease of velocity of light (which is also true for all electromagnetic waves) when the wave enters the material. Mathematically, n_d is defined by

$$n_d = V_{vac}/V_d \qquad [1]$$

where V_{vac} and V_d are velocities of light in vacuum and diamond, respectively.

When a beam of light of intensity I_0 in air is incident normally on the surface of diamond, the reflected part of the beam, characterized by the reflection coefficient R, depends on n_d, and R is given by

$$R = \left(\frac{n_a - n_d}{n_a + n_d}\right)^2 \qquad [2]$$

where n_a is refractive index of air and n_d is given by Sellmeier dispersion equation:

$$n_d = \sqrt{1 + \frac{4.3\lambda^2}{\lambda^2 - 0.0121} + \frac{0.33\lambda^2}{\lambda^2 - 0.031}} \qquad [3]$$

where λ is the wavelength of light expressed in micrometers. When the beam enters diamond, part of it is absorbed in diamond. The absorption, characterized by the absorption coefficient α, is caused by: (i) impurities (such as nitrogen, boron, hydrogen, etc.); and/or (ii) intrinsic defects (such as dangling bonds, sp^2 bonds, and sp bonds). However, if the energy of light is close to or above the bandgap of diamond (5.5 eV), the absorption can be caused by electronic transitions from valence to conduction bands. The intensity $I(x)$ at a distance x below the diamond surface is given by

$$I(x) = I_0(1 - R)\exp(-\alpha x) \qquad [4]$$

The fundamental expressions for α are different for indirect and direct type semiconductors. However, the modeling of α, for energies close to the bandgap of diamond, can be accomplished empirically using Urbach's rule according to the following equation:

$$\alpha = \alpha_0 \exp\left[\frac{\sigma(T)(E - E_0)}{kT}\right] \qquad [5]$$

where α_0 and σ are Ubach tail parameters, and E_0 (6.5 eV) is direct gap energy of diamond. K is Boltzmann constant and T is the temperature. As at $T = 300$ K, $\alpha_0 = 4.23 \times 10^{11}$ cm^{-1} and $\sigma = 0.585$, eqn [5] can be simplified:

$$\alpha = 4.23 \times 10^{11}\ e^{22.6(E-6.5)} \qquad [6]$$

where the units for α and E are in cm^{-1} and eV, respectively. Using the expression $E = 1.24/\lambda$, where E is in eV and λ is in micrometers, eqn [6] can be written as

$$\alpha = 4.23 \times 10^{11}\ e^{27.9(1/\lambda - 5.24)} \qquad [7]$$

where λ is in micrometers. The variations of α and n_d with wavelength and energy of light are shown in Figure 5, which are plotted using eqns [3] and [7]. Impurities and intrinsic defects in diamond strongly affect α, n_d, and its other properties.

Impurities in Diamond

A pure diamond with perfect lattice structure is transparent to ultraviolet (UV), visible, infrared (IR), millimeter and microwave regions of the electromagnetic spectrum. However, even an impurity-free diamond has some absorption in the infrared due to phonon excitations and an ultraviolet cutoff due to band-to-band absorption. The defects, impurity-related and intrinsic, in single crystal diamond have been extensively studied because they strongly affect its properties. In fact, diamonds are classified according to the type of defects that are dominant.

Impurities in diamond give rise to additional energy levels in its bandgap. If the density of these impurities is sufficiently high, they can cause absorption of electromagnetic radiation (including light) on one hand and break the lattice symmetry on the other. The breaking of the lattice symmetry can lead to one-phonon IR absorption, which is forbidden in pure diamond. The fact that impurities affect the optical properties of diamond led to its classification into types Ia, Ib, IIa, and IIb which correspond to pale yellow, golden yellow, no color, and blue, respectively. The transmission properties of these various types of diamond are depicted in Figure 6. The dominant impurities are nitrogen



Figure 5 Wavelength and energy dependence of absorption coefficient and refractive index of diamond.



Figure 6 Transmission spectra of natural diamond and CVD polycrystalline diamond (poly-C).

(5–2500 ppm atomic) in type I and boron (10 ppm atomic) in type II. It may be pointed out that boron-doped diamond is a semiconductor with p-type conductivity measured at room temperature. Nitrogen-doped diamond does not show n-type conductivity at room temperature as the donor levels are too deep to be ionized.

Polycrystalline CVD Diamond

Due to the lack of a reliable hetero-epitaxial diamond growth technique, the crystalline diamond films are very expensive (require single crystal diamond substrates for their growth) and, consequently, their widespread commercial use is severely limited. Polycrystalline diamond (poly-C) grown by CVD, which can be as inexpensive as any other material if mass produced, is very attractive for optical and other applications (Figure 2). The properties of high-quality (with high density of sp^3 C–C bonds) poly-C films are comparable to those of crystalline films.

As shown in Figure 6, the transmission properties of poly-C are comparable to or better than those of type I and II diamonds for part of the energy range. Free-standing commercial poly-C films are typically polished and have thicknesses in the range of 50–300 micrometers (the least expensive are 300 μm thick). White poly-C films transparent to visible light are also available. Such films, with optically smooth surface, can be considered free of scattering effects. These films can be considered as a transparent plate in air and, for normal incidence of light with energy less than the bandgap, the transmission coefficient is given by

$$T = \frac{(1 - r_1^2)(1 - r_2^2)}{1 + r_1^2 r_2^2 + 2 r_1 r_2 \cos(2\delta)} \qquad [8]$$

where the Fresnel coefficients are given by

$$r_1 = \frac{n_a - n_d}{n_a + n_d}, \qquad r_2 = \frac{n_d - n_a}{n_d + n_a} \qquad [9]$$

where n_a and n_d are refractive indexes of air and poly-C, respectively, and δ is phase change for a poly-C film with a thickness of t:

$$\delta = \frac{2\pi}{\lambda} n_d t \qquad [10]$$

Using $n_a = 1.0003$, $n_d = 2.4$, and $t = 100$ μm, eqn [8] can be written as

$$T = \frac{1}{1.49 - 0.493 \cos\left(\frac{3015}{\lambda}\right)} \qquad [11]$$



Figure 7 Transmission coefficient of a polished poly-C film with a thickness of 100 μm as a function of (a) wavelength and (b) wavenumber.

or

$$T = \frac{1}{1.49 - 0.493 \cos(0.048\, k)} \qquad [12]$$

where λ is in μm and k, the wavenumber, is in cm^{-1}. Variation of T as a function of λ and k, is shown in Figure 7. A similar behavior is observed for non-polished poly-C films if the wavelength is larger than the surface roughness of the films. For a sample with a very rough surface, scattering effects need to be included in eqn [8].

Electroluminescence in Poly-C

In a luminescence process, the electron must first be excited to higher energy, which can be accomplished by light (photoluminescence), electron beam (cathodoluminescence) or electrical energy (electroluminescence). A subsequent electron transition to lower energies leads to emission of light. A common example of electroluminescence is a forward biased p–n junction made out of direct bandgap type semiconductor such as GaAlAs. The light emitting diodes (LED) and LASERS are based on electroluminescence. Red, green, and blue LEDs are made from GaAlAs, GaP, and SiC/GaN, respectively. Indirect bandgap type semiconductors, such as diamond, typically do not exhibit electroluminescence. The fact that electroluminescence has experimentally been observed in crystalline diamond and poly-C seems to be, at first sight, a contradiction of its indirect bandgap. In fact, defects in diamond are believed to be responsible for their luminescence properties. All types of diamond are found to have a number of defects related to vacancies and impurities. Due to a unique combination of properties of diamond (Table 1), its electroluminescence properties offer a very unique application potential in optical microelectromechanical systems (MEMS), displays and communication devices in IR, visible and UV regions.

Electroluminescence (EL) in optoelectronic devices is produced by excitation of electrons by electronic current. Yellow-green EL has been observed in Schottky diodes made of boron-doped poly-C. Blue-green and blue-violet EL has been observed in free-standing poly-C films, with thicknesses in the range of 15–400 micrometers, when the samples were subjected to applied fields in the range of 2 V/μm. The EL peaks are observed at energies in the range of 3–3.85 eV, with the main peak occurring at 3 eV.

Recently, a very interesting type of EL has been observed in poly-C and carbon nanotubes, which seems to have an application potential in displays and optical MEMS. Under applied electric fields in the range of 20–40 V/μm, electrons are known to tunnel out of a poly-C film into vacuum and the process is called field emission. EL has been observed during the field emission process, and this new effect is called field emission EL (FEEL). A typical FEEL spectra is shown in Figure 8. It is believed that FEEL results from direct type defects in poly-C, which are populated during the field emission process. The electrons in these defects, instead of being field emitted, make transitions to lower energy levels leading to light emission. The main FEEL peak is observed at 2.6 eV which is in the visible range.

Poly-C Applications

The current applications of diamond, which include optical windows, temperature sensors, heat sinks, cutting tools, surgical instruments, and optical coatings, are based on natural, synthetic, and CVD diamond. The cost of producing diamond has always been prohibitive in widespread diamond applications. Fortunately, over the past 20 years, the development of CVD diamond technologies has eradicated the fears of diamond being too expensive for its widespread applications. As the CVD poly-C can be as inexpensive as any other electronic material, widespread applications of diamond are expected for poly-C. In the area of micro- and nanostructures, the poly-C can provide a unique opportunity for both polycrystalline and crystalline microdevices. Using the present fabrication techniques, the grain size in poly-C can be varied in the range from a few tens of nanometers (nanocrystalline diamond) to hundreds of micrometers (commercial free-standing poly-C films). This leads to a whole range of device structures ranging from inter- to intra-grain devices. An intra-grain device made in poly-C will be an inexpensive single crystal device with properties better that those found in natural/synthetic diamonds, because an intra-grain poly-C device will have a higher degree of purity (because it is grown by CVD).

The applications of poly-C in microsystems (current, in-progress, and future) include optical MEMS, biological/protective/hard coatings, sensors,



Figure 8 FEEL spectra in poly-C as function of wavelength and emission current (inset).

field emission displays, and WIMS (wireless integrated microsystems). Intra-grain microlenses, RFMEMS, heat pipes, sensors, microabrasives, and spectrometers may lead the way for unique poly-C applications.

Optical MEMS

A basic MEMS structure, with electrostatic actuation mechanism, is shown in Figure 9. Currently, most of the Optical MEMS and RFMEMS (radio frequency MEMS) devices are made from poly-Si (polycrystalline Si) using surface or bulk micro-machining fabrication techniques. The ability to integrate micro-optical elements with movable structures and micro-actuators has opened up many new opportunities for optical and optoelectronics systems, as MEMS allow a more effective manipulation of optical structures than the conventional methods. Optical MEMS have applications in displays, sensing, data storage, and communication systems. Some of the examples are optical switches, optical cross-connects, wavelength division add/drop mixers, tunable filters/lasers/detectors, dispersion components, polarization dispersion components, and spectrometers.

Material-related limitations put some constraints on the current optical MEMS technologies and applications. Diamond is an excellent material for optical MEMS and can extend the application range and reliability. The use of poly-C in optical MEMS can also remove the traditional cost constraints associated with the use of single crystal diamond. Although the poly-C optical MEMS are in their infancy, recent developments are very exciting. Figure 10 shows a poly-C resonator structure fabricated using a poly-C fabrication technology compatible with Si processing techniques. Such structures, if used as filters and switches, can lead to a superior performance as compared to any other currently used material. Poly-C on-chip spectrometers are also expected to operate in a large wavelength range.



Figure 9 A simple MEMS structure with electrostatic moving of the cantilever beam.



Figure 10 A poly-C MEMS combdrive for high-quality factor resonators, inertial sensors, optical MEMS, etc. Poly-C is superior to poly-Si as its Young's modulus is 4 times higher than that of poly-Si.



Figure 11 Poly-C microabrasive structures two different densities of pyramids. (Courtesy of Dr. H. Bjorkman of Upsala University.)

Microabrasives

Poly-C is also a very promising material for microabrasives. Micromachined poly-C MEMS structures have recently been fabricated for possible use for microabrasives. Figure 11 shows micromachined MEMS structures which are expected to enhance the life of a tool. Such abrasives by design are inherently cost-effective because they are batch fabricated.

See also

Light Emitting Diodes.

Further Reading

Asmussen J and Reinhard D (2002) *Diamond Handbook*. New York: Marcel Dekker.

Kim U and Aslam DM (2003) Field emission electroluminescence on diamond and carbon nanotube films. *Journal of Vaccum Scientific Technology B* 21(4): 1291–1296.

McMurry J (1996) *Organic Chemistry*. New York: Brooks/Cole.

Pan LS and Kania DR (1996) *Diamond: Electronic Properties and Applications*. Boston, MA: Kluwer.

Spear KE and Dismukes JP (1994) *Synthetic Diamond: Emerging CVD Science and Technology*. New York: Wiley.

Laser Damage in Thin Film Coatings

D Ristau, Laser Zentrum Hannover e.V., Hannover, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Since the very beginning of laser technology, Laser-induced Damage Thresholds (LIDT) of optical components were always an obstacle for the development of laser systems operating at high power levels. In such systems, the surface or the bulk of the optical components can be damaged by laser radiation of sufficiently high power or energy density resulting in an uneconomical standstill of the laser and its application. In the early days of high power laser development, mainly inclusions in laser rod materials were discussed as a major complication for an augmentation of the output power in solid state laser systems. Nowadays, in the course of the development of optical materials with excellent quality and power handling capability, the problem of laser-induced damage has shifted from the bulk to the surface of the optical component. The optical surface is subjected to various production steps and environmental influences, which modify its structure and composition. Especially, the thin film coating, which is deposited on the optical surface to adapt its reflectance and transmittance to the application, contributes predominantly to the reduction of the LIDT values. As a consequence, the measurement and optimization of the power handling capability of thin films is considered as one of the primary research areas in modern optics technology and is supported by an extensive scientific community.

In the following, a brief review will be given on selected fundamental damage mechanisms in thin films, considering also the scaling of LIDT values for different operation conditions. Also, current standards for the measurement of LIDT will be described, and examples illustrating some practical aspects of high power optical coatings will be presented. Finally, a summary of the present state of the art will be given and recent trends in laser technology will be discussed in respect to research in laser-induced damage.

Fundamental Damage Mechanisms in Thin Films

During thirty years of intense research in laser damage of thin films, a broad spectrum of different damage and degradation mechanisms had been discovered and studied for a variety of laser operation conditions and wavelengths. For prominent high-power laser systems often applied in industrial production fields or fundamental research, specific models for laser-induced breakdown have been developed, which are also of practical relevance. In many experiments, damage sites with the morphology illustrated in Figure 1 are observed. The coating is delaminated from the surface of the optical component in the center of the laser beam area. Obviously, mechanical stress has built up in the coating by heating, which is induced by the absorbed laser power. At a certain stress level, exceeding the adhesion strength of the coating to substrate surface, the thin film cracks and may even delaminate from the component. In other cases of this absorption-induced damage effect, the film reaches its melting point prior to the mechanical threshold and



Figure 1 SEM-picture of a damage site on an alternating coating of SiO_2/HfO_2. The system was irradiated by a Nd:YAG-laser with an energy density of 45 J/cm^2. As a dominant damage mechanism, a delamination of the coating by extreme mechanical stress is suggested. Reproduced with permission from Ristau D, Ebert J and Welling H (1989) Optische Beschichtungen für Hochleistungslaser. *Laser und Optoelektronik* 21(4): S.49.



Figure 2 Nomarski micrograph (magnification 250×) of a damage site on an antireflecting coating of SiO_2/Ta_2O_5. The system was irradiated with an energy density of 51 J/cm^2 at a wavelength of 1.064 μm. A delamination of the coating in the center of the beam is surrounded by a recrystallization zone.

evaporates or changes its crystalline structure. The morphology of such damage sites exhibits a discoloring or an increased surface roughness in the center of the laser beam (see Figure 2). Absorption-induced damage is dominated by the instantaneous heating of the coating material in the area of interaction with the laser beam and can be described on the basis of the heat diffusion equation. In this approach, the source term in the heat diffusion equation is given by the heat coupled into the system by the absorbed laser power, and the boundary conditions are determined by the geometry and the structure of the layer system as well as the spatial laser beam profile. Apparently, absorption-induced damage has to be considered only for components with significant absorptance at their operation wavelength. Typical examples for coating materials and wavelength regimes, where absorption-induced damage is frequently observed, are the wavelength 10.6 μm of the CO_2-laser with ZnSe, ZnS, and fluorides as coating materials, or the DUV/VUV-wavelengths dominated by excimer lasers and fluoride coating materials. The effect of absorption-induced damage in optical materials is also of practical relevance for cw- and long-pulse operation conditions of the laser system corresponding to long thermal diffusion lengths. For cw-irradiation, the temperature rise in the component can be calculated by numerical methods involving finite elements or differences. For boundary conditions with circular symmetry and a Gaussian beam profile (beam diameter w, power P), an analytical expression can be derived for the temperature rise ΔT in the center of an irradiated circular component

$$\Delta T = \frac{2\beta_s P}{\pi^{3/2} k w} \tan^{-1}\left(\frac{16\kappa t_I}{w^2}\right)^{1/2} \qquad [1]$$

In this model the temperature rise is dependent on the thermal properties (k: thermal conductivity, κ: thermal diffusivity), on the surface absorption of the component (β_S), and on the beam diameter. For irradiation times t_I, long compared to the typical heat diffusion time w^2/κ, eqn [1] reduces to the asymptotic dependence

$$\Delta T \rightarrow \frac{\beta_s P}{\pi^{1/2} k w} \qquad t_I \rightarrow \infty \qquad [2]$$

Obviously, the temperature rise ΔT scales with the P/w for these long-time irradiation conditions compared to the short pulse regime, where the scaling of the temperature rise is proportional to P/w^2. For the application of optical components in high power cw- and long-pulse lasers, this P/w scaling law has to be considered carefully, because the power handling capability depends critically on the size of the irradiated area. Also, the onset of damage may be delayed in respect to the start of irradiation by time constants in the range of several 10 seconds.

In the course of the development of improved coating processes, optical absorptance could be reduced to very low levels in the near infrared and visible spectral region. For example, high reflecting mirrors for the wavelength of the Nd:YAG-laser with total losses below 1 ppm can be produced with advanced ion beam sputtering processes nowadays. Therefore, another principal damage mechanism, which is based on inclusions or defects in the coatings, is often found in the near infrared spectral range. A detail of a damage site representing inclusion dominated damage induced by a pulsed Nd:YAG-laser in a coating of HfO_2/SiO_2 is shown in Figure 3. In the laser beam area numerous craters are located, which extend from circular voids with different diameters in a range below 1 μm. At the high magnification of the employed electron microscope, the multilayer structure of the coating system can be resolved indicating an origin of damage approximately in the same depth of the layer structure at the substrate surface. The underlying damage mechanism is initiated by inclusions or other defects with an absorption, which is significantly higher than for the surrounding thin film material. As a consequence, the inclusion is rapidly heated during the interaction with the laser beam and explodes removing the covering layer structure. This inclusion breakdown can be modeled by calculating the temperature behavior $T(r)$ at the radial position r of a sphere (radius g, thermal conductivity k_E, diffusivity κ_E) which is embedded in a medium with defined properties (see eqn [3]). The interaction of the sphere, which has a size in the range of the wavelength λ and a refractive index n', with the laser irradiation, is described by the Mie absorption coefficient Q. For the instant of damage, a critical temperature at the outer surface of the sphere ($r = g$) is assumed, which is often related to the melting point of the layer material

$$T(r) = \frac{3QI}{4\pi k_E g}\left[\frac{k_E}{3k}+\frac{1}{6}\left(1-\frac{r^2}{g^2}\right) - \frac{2gb}{r\pi}\int_0^\infty \mathrm{d}y \exp\left(-\frac{y^2 t_p}{\tau_1}\right) \times \frac{(\sin y - y\cos y)(\sin ry/g)}{y^2\left[(c\sin y - y\cos y)^2+b^2y^2\sin^2 y\right]}\right] \quad [3]$$

$$Q = \pi g^2\left[1+\frac{2\exp(-8\pi n' g/\lambda)}{8\pi n' g/\lambda}+\frac{\exp(-8\pi n' g/\lambda)-1}{(8\pi n' g/\lambda)^2}\right]$$

$$\tau_1 = \frac{g^2}{\kappa_E} \quad b = \frac{k}{k_E}\left(\frac{\sqrt{\kappa_E}}{\sqrt{\kappa}}\right) \quad c = 1-\frac{k}{k_E}$$

Besides the thermal properties of the host material (thermal conductivity k, diffusivity κ), the properties and the statistic distribution of the inclusions have to be known for a quantitative description of inclusion breakdown.



Figure 3 SEM-picture of damage site on a high reflecting coating of SiO_2/HfO_2. This inclusion-dominated breakdown mechanism was initiated at an energy density of approximately 130 J/cm^2 with a Nd:YAG-laser.

In contrast to the nearly deterministic behavior of absorption induced damage, defect dominated damage mechanisms often exhibit a statistical nature. Since the inclusions are not homogeneously distributed in the layer structure, a variation of the threshold value is observed for different damage sites on a single sample. The assessment of the inclusion parameters is extremely difficult in practice. Therefore, the inclusion model is mainly employed for the prediction of tendencies for the LIDT as a function of the beam parameters and the properties of the layer materials.

Different aspects related to the substrate polishing, cleaning, and deposition process have to be considered for an investigation in the various origins of inclusions or defects in a layer structure. Besides contamination of the substrate surface prior to the deposition process, particles may be generated during the deposition process by mechanical abrasion of material from moving parts in the plant or by delamination of material coated on the inner walls. Also, the deposition source may contribute to the formation of defects by sputtering of particles or droplets from the melt or the target. Especially in low energetic thermal deposition processes, defects are often the origin for the formation of nodules. These conical faults in the layer structure reduce the LIDT because they are less resistant against intensive laser radiation than the bulk of the coating system.

Besides models, which are based on the transformation of laser radiation into heat, direct electronic excitation has to be considered as a breakdown mechanism for short-pulse lasers. In these intrinsic breakdown models for dielectric materials, the generation of a high electron density in the conduction band is assumed. This carrier generation can be explained by high field ionization of electrons in the valence band of the dielectric material. Many theoretical concepts introduce the avalanche effect as an important mechanism contributing to the generation of free electrons. Electrons excited by strong field ionization can interact with the electric field and accumulate excitation energy. By collisions with the lattice, this energy can be also transferred to the electrons in the valence band. Thus, when the energy of the free electrons exceed a critical value, other electrons can be excited to the conduction band, and a carrier generation like an avalanche arises. Another theoretical approach is the multiphoton model which is formulated on the basis of multiphoton absorption for the generation of free electrons. In most intrinsic models it is assumed, that laser-induced damage breakdown occurs when the electron density in the conduction band reaches a critical value of approximately 10^{21} $1/\mathrm{cm}^3$. At this high electron density, a plasma state is reached and the impinging radiation is coupled efficiently into the layer structure resulting in its destruction.

Intrinsic damage is often characterized by a deterministic damage behavior with a well defined threshold value which is also characteristic for damage in bulk materials. As a prominent example, damage induced by ultra-short pulses with a duration below 1 ps can be often attributed to intrinsic mechanisms, because the diffusion length of thermal effects can be neglected in comparison to the intensive interaction of the laser radiation with the electrons of the coating materials. In this case, the generation rate $\mathrm{d}n/\mathrm{d}t$ of electrons in the conduction band can be described on the basis of the impact ionization rate and multiphoton excitation

$$\frac{\mathrm{d}n}{\mathrm{d}t} = \alpha n(t) q I(t) + \beta_m \left[q I(t) \right]^m \qquad [4]$$

In this model $I(t)$ is the power density of the laser radiation, and q is a correction factor representing interference effects in the coatings, which may result in a local power exceeding the power density of the radiation impinging on to the layer system. The electron excitation mechanisms are described by the impact ionization coefficient α and the m-photon absorption coefficient β_m. The relative contributions of both excitation mechanisms to laser-induced breakdown are depending on the pulse duration and the bandgap energy of the layer material.

In a rough approximation, the damage threshold increases with the bandgap energy of the materials as a consequence of the photon absorption coefficient β_m decreasing with its order m. For short pulse durations below a few 10 fs, multiphoton processes contribute significantly in the range of some 10% to the free-carrier generation. In most materials, avalanche ionization develops to the dominant generation mechanism for pulse durations above 100 fs. These tendencies could be demonstrated for single layers of selected oxide material deposited by ion beam sputtering on quartz substrates, which were tested in a pulse duration regime from 20 fs to 1 ps. According to the theoretical model, the expected increase of the damage also influencing values with the pulse duration was observed in the damage experiments.

In practice, the power handling capability of optical components is also often limited by imperfections like scratches, digs, and areas with high roughness on the optical surface. In most deposition techniques applied in optical technology, the layer system tends to replicate or even enhance surface imperfections of the substrate. In the application, additional weak points may be introduced by improper handling or contamination of the optical surfaces. If the contaminants are not removed by the impinging high-power laser radiation, they increase the surface absorption and act as initiation points for laser-induced damage. Voids, grooves, pores, or scratches reduce the power capability of the optical element, because they act as concentrators for the electric field.

Units and Scaling of Laser-Induced Damage Threshold

According to the theoretical models of laser-induced damage, the appropriate units of measurement for LIDT values are mainly given by the dominant damage mechanism and the irradiation time. For pulsed laser radiation and dielectric breakdown effects, the laser-induced damage threshold is usually reported in $\mathrm{W/cm^2}$. In the case of absorption-induced damage or inclusion dominated breakdown and a pulse duration short compared to the thermal diffusion time in the layer structure, LIDT values are often scaled in $\mathrm{J/cm^2}$. The unit of linear power density (W/cm) is indicated for the LIDT of long-pulse, cw-lasers or other sources, which induce a temperature increase in the optical component with rise times in the regime of seconds.

Laser-induced damage thresholds of optical thin films are critically dependent on the operation conditions of the applied laser system and on the design of the layer structure. For example, even the damage mechanism can change if the wavelength or the pulse duration is varied. Therefore, LIDT values should be scaled with the irradiation parameters only for small intervals, in cases where the fundamental damage mechanism is clarified. In all other situations, the extrapolation of threshold values is extremely difficult and may lead to inaccurate results. Especially, an overestimation of the LIDT value holds severe dangers in practical applications, where the replacement of a damaged component and the repair of other parts impaired by the damage event causes high expenses. If the damaged components consist of toxic materials (e.g., ZnSe, GaAs, CdTe, ThF_4, chalcogenides, Be, Cr, etc.) severe health hazards may occur, and an expensive decontamination of the environment may be necessary. Therefore, the determination of the laser-induced damage threshold using the actual laser parameters under controlled environmental conditions is always recommended for unclear cases.

In the present state of research in laser-induced damage mechanisms, only few tendencies are generally accepted as confident for scaling of LIDT values. As a function of the pulse duration, laser-induced damage thresholds increase for longer pulses. For inclusion and absorption dominated breakdown, a $t_p^{1/2}$-law is often used in the pulse duration regime between 10^{-10} to 10^{-8}s. This dependency can be extended to other pulse regimes up to pulse lengths in the ms-range, if the exponent is replaced by a value between 0.5 to 2. In respect to the laser wavelength, a decrease of the LIDT value with decreasing wavelength is observed for most materials and operational conditions. Investigations in the influence of the beam diameter have been performed by many research groups, indicating a decrease of the LIDT values for increasing beam diameters. Especially for inclusion dominated breakdown, the event of damage for a certain laser irradiated site will be dependent on the distribution of inclusions at that position. If the beam size is small, the probability for interrogating a defect vulnerable to damage is low. By increasing the spot diameter, this probability will asymptotically reach unity, because at a certain beam diameter, at least one defect will always be covered by the beam. Therefore, the onset of laser-induced damage is not dependent on the beam diameter for inclusion-dominated breakdown, which is often encountered in conventional optical coating systems. Another special case is the scaling of the cw-damage threshold with the beam diameter. Since the cw-LIDT is expressed in linear power density, the power handling capability increases more slowly with the beam diameter for the cw-lasers than expected from the normal pulsed operation. For example, extrapolating the LIDT value of 100 W at a beam diameter of 1 mm for a laser mirror to a beam diameter of 10 mm, results in a maximum power load for the component of 1 kW according to the correct P/w-law. The threshold power would be extremely overestimated to approximately 3.2 kW, if the general P/w^2-dependence is applied.

Measurement of Laser-Induced Damage Thresholds

As a consequence of the complicated relation between the laser damage mechanism and a broad spectrum of thin film properties and laser parameters, laser-induced damage threshold measurements have to be performed under well-defined conditions. To investigate the comparability of LIDT measurements, an extended international round-robin experiment has been conducted on coated optics for the wavelength of 1.064 μm at the beginning of the 1980s. This experiment indicated the need for a clearly specified LIDT-measurement procedure, and conceptual work was initiated to develop a corresponding ISO-Standard series. During recent years, an International Standard (ISO 11254) has been adopted covering testing conditions relevant for most typical laser applications. In the first part of ISO 11254 1 on 1-testing of optical surfaces, in respect to laser damage, is described. The fundamental approach of the standard measurement procedure is illustrated in Figure 4. A laser source operating in transversal and longitudinal single mode is employed for the irradiation of the sample surface. The beam



Figure 4 Fundamental setup for the measurement of laser-induced damage thresholds.

parameters of the laser are assessed by a beam diagnostic system which monitors the spatial and temporal profile as well as the energy of the laser radiation in the target plane. In order to achieve the high energy density levels necessary to destroy the surface of the specimen, a well characterized focusing system is installed. For adjustment of the laser energy in the target plane, an attenuating system is employed. In the 1 on 1 measurement protocol, each site on the sample surface is subjected to a single laser pulse once only. In a test sequence, the test surface is examined by pulses of different energies, covering low values without damage and high values causing damage. After the test, the specimen will be inspected with a Nomarski interference contrast or a darkfield microscope at a magnification of 150× or higher to identify the damaged sites. For the evaluation of the damage test, the damage probability method is recommended. In this evaluation scheme, the ratio of the number of damaged sites to the total number of sites objected to a certain energy or power level is interpreted as the damage probability. The plot of these damage probability values as a function of energy or power, which is called the survival curve of the optical component, provides an insight into the damage mechanisms involved. The damage threshold is given by the highest quantity of laser radiation for which the extrapolated probability of damage is zero. A typical example for a 1 on 1 damage test at the wavelength 1.064 μm and the extrapolated LIDT value is depicted in Figure 5.

In most catalogs of optics manufacturers, the 1 on 1 LIDT values are used to illustrate the power handling capability of their products, even though 1 on 1 data are of limited importance for practical applications, where an optical component is always subjected more than one time to a laser beam. This customary situation is covered by Part 2 of the ISO-LIDT-Standard which describes a damage test procedure for a series of pulses (S on 1-tests). For an assessment of the reliability, the concept of the characteristic damage curve is introduced by this standard. This curve is deduced directly from the S on 1 test data by plotting the energy density for a selected damage probability as a function of the number of pulses (see Figure 6). By an extrapolation of the characteristic damage curve to high pulse numbers in the order of 10^9 to 10^{12} shots, the lifetime of the optical component can be roughly estimated. For a certification of optical components in respect to their power handling capability, a third part of ISO 11254 is under development, which is concentrated on different testing protocols of a defined surface fraction at power levels expected in the application. The fundamental approach of these tests is a simulation of conditions at the upper limits of operation parameters encountered in practice.



Figure 5 Survival curve of an anti-reflective layer system (two layer V-coating, SiO_2/Ta_2O_5) on fused silica substrate for the Nd:YAG-laser wavelength. The measurement was performed at a wavelength of 1.064 μm, a beam diameter of 420 μm, and a pulse duration of approximately 15 ns, respectively.



Figure 6 Characteristic damage curve of a high reflecting mirror of SiO_2/TiO_2 for fs-laser systems. The layer structure was tested with a high repetition (1 kHz repetition rate) fs laser system operating at a pulse duration of 150 fs.

Optical Coatings for High Power Lasers

For the development and application of coating systems with high LIDT values, several major aspects have to be considered. In the first approach, appropriate materials and processes have to be selected which deliver coatings with sufficient power resistance. In many studies, a correlation of the LIDT values of the constituent single layers to the power handling capability of a layer system was observed. Therefore, single layers of potential deposition materials were investigated at the wavelengths of prominent laser systems from the VUV- to the FIR-spectral region. For specific deposition processes, often a clear ranking of the coating materials in respect to their power handling capability could be demonstrated. An example for a Nd:YAG-laser with a pulse duration of 15 ns is illustrated by Table 1. With the exception of the ZrO_2-layer, which exhibited severe inhomogeneity and a high inclusion density, a correlation can be assumed between the LIDT value and the melting point of the bulk materials under these operation conditions. This dependency can be attributed to absorption-induced damage as well as to the inclusion model, and therefore, the damage morphology has to be studied in each case to identify the dominating damage mechanism. In the fs-regime or the UV/VUV-spectral range, often a dependence of the power handling capability on the bandgap of the materials is found. According to the relationships of the avalanche and other dielectric breakdown models, materials with highest bandgaps are frequently encountered at the top of an LIDT ranking.

For the influence of the coating process on the laser-induced breakdown of optical coatings, no clear tendencies can be detected. For example, Ion Beam Sputtering (IBS), which is considered as the deposition process for coatings with extremely low losses and contamination, cannot always surpass conventional thermal deposition processes in laser stability. In general, ion or plasma assisted deposition techniques produce coatings with lower LIDT values than conventional coating processes for most operation conditions. Sol-gel processes, which were developed for the deposition of removable coatings on large optics in laser fusion, can reach superior power handling capabilities. In general, as a consequence of the complicated relation between the production parameters and laser-induced breakdown, production processes for optical coatings have to be optimized separately for different wavelength regimes and irradiation conditions.

Table 1 Laser induced damage thresholds of selected single-layer coatings in relation to the melting points of the corresponding bulk materials. In the last column, LIDT values of anti-reflective coatings (AR-Coating) composed of the high index material and SiO_2 are compiled to illustrate the correlation between single LIDT values and the damage threshold of layer systems

Material	*Melting point (°C)*	*LIDT value (J/cm^2) single layer*	*LIDT value (J/cm^2) AR-coating*
TiO_2	1775	13 ± 1	14 ± 1
Ta_2O_5	1918	28 ± 2	32 ± 5
HfO_2	2758	41 ± 3	46 ± 6
ZrO_2	2700	34 ± 4	28 ± 1
Al_2O_3	2072	39 ± 1	
SiO_2	1723	34 ± 7	

Besides the fundamental production parameters, the design of the coating system is of similar importance for the achievement of high LIDT values, because damage is directly driven by the electric field strength in the layer structure. A standing wave field pattern is depicted in Figure 7 for a high reflecting stack of Ta_2O_5 and SiO_2. The design consisting of layers with an optical thickness of 1 QWOT is typical for most standard laser mirrors. The power density reaches extreme values always at the interfaces between the layers and even exceeds the incoming irradiation power density (100%). Interfaces between the layers can be considered as weak points in a coating system, because additional contamination may occur during the switching of the material in the production process. Also, the adhesion between the adjacent layers may be reduced, and mechanical stress may be built up by the different materials. To improve damage thresholds of laser mirrors, the thickness of the first few layer pairs can be adjusted to shift the points of maximum field strength into the bulk of the layer with higher damage resistivity (see Figure 8). Also, a thick layer can be attached to the system in order to stabilize the outer layer pair in respect to thermal or mechanical stress. Another technique, which can be applied to enhance the stability of the interface is the codeposition of materials, resulting in a gradual interface with a mixing zone of materials between the layers. This region of codeposited material exhibits a higher resistance against mechanical stress resulting in an improvement of LIDT values of up to 20%.

The effect of the internal electric field strength distribution on the power handling capability of a layer system should be most apparent for intrinsic damage mechanisms, which are dominant in the ultra short pulse regime below 1 ps. According to the fundamental model (see eqn [4]), a direct relationship of the damage threshold to the maximum field strength value within the layer system is expected. As an example, an investigation in the threshold behavior of ion beam sputtered coating systems with different field strength values is illustrated in Figure 9. In this experiment, the maximum field strength in the last low index layer of SiO_2 has been adjusted to factors between 0.4 and 1.6 of the impinging field strength (see upper diagram in Figure 9) by depositing different designs on a basic 1-QWOT layer stack of TiO_2/SiO_2. In the lower part of Figure 9, the S on 1 LIDT values, measured with a fs-laser, are depicted for selected pulse numbers N. For all layer systems,



Figure 7 Distribution of the power density in a high reflecting layer stack of SiO_2/Ta_2O_5. The first nine layers of the system and a final thick stabilizing layer of SiO_2 next to the air interface are depicted. The incoming energy density is calibrated to 100%. Reproduced with permission from Ristan D, Ebert J and Welling H (1989) Optische Beschichtungen für Hochleistungslaser. *Laser und Optoelektronik* 21(4): S.53.



Figure 8 Distribution of power density in a high reflecting layer stack of SiO_2/Ta_2O_5. The first nine layers of the system, which is designed for reduced power density at the interface in the first layer pair are depicted. Reproduced with permission from Ristan D, Ebert J and Welling H (1989) Optische Beschichtungen für Hochleistungslaser. *Laser und Optoelektronik* 21(4): S.53.



Figure 9 Damage thresholds (lower diagram) and internal field strength relative to the field strength of the impinging wave (upper diagram). The damage thresholds were measured with an ultrashort pulse laser operating at a repetition rate of 1 kHz, a pulse duration of 150 fs, and a beam diameter of 100 μm on the sample surface. Damage thresholds for selected numbers between $N = 30$ to $N = 30\,000$ of pulses are indicated by columns. The plotted maximum field strength in the last SiO_2-layer is adjusted on the basis of design variation.

which were deposited in separate deposition runs, a strong correlation between the maximum field strength and the laser threshold is observed. This experiment clearly demonstrates the role of the electric field strength distribution in high-power coatings and the potential of advanced thin film design strategies.

Besides the properties of the coatings, the quality of the substrate has to be considered in respect to surface imperfections and to the polishing procedure. For example, substrates for the production of high-quality optics with enhanced power handling capability in the VIS/NIR-spectral range should be polished to a surface roughness of less than 1 nm_{rms} with a surface imperfection value $5/1 \times 0,010$ according to ISO 10110. For an illustration of the effect of the polishing grade on the LIDT values, selected results are compiled in Table 2 for substrates of BK7-glass and high reflecting mirrors.

Table 2 Laser-induced damage threshold values of samples polished using compounds of different grain size. Besides the LIDT values of the uncoated surfaces, also data for anti-reflective coatings of selected materials on these surfaces are summarized

Coating type	*LIDT value (J/cm^2) polishing type I*	*LIDT value (J/cm^2) polishing type II*
Bare surface	76 ± 1	68 ± 12
Ta_2O_5/SiO_2	44 ± 2	38 ± 1
HfO_2/SiO_2	47 ± 16	35 ± 5
Nd_2O_3/MgF_2	34 ± 6	24 ± 8

Substrates with the polishing Type I and Type II were processed with powder of different grain diameter (2 μm and 3 μm) in conventional pitch polishing. For the LIDT values of the bare substrate and the coatings, a clear relation to the surface roughness can be observed. Especially for optical coatings with significant transmittance, subsurface damage in the substrate has to be taken into account. As a consequence of the chemical and mechanical interaction of the surface with the polishing compounds, impurities and dislocation are introduced in the surface structure resulting in a reduction of the damage threshold.

Summary

In the course of the rapid development of laser technology, a large background in high power optical coatings had been built up during the last three decades. Nowadays, the corresponding experience in the production of high power coatings is mainly located at industrial companies and a few research institutes, which are also involved in the characterization of optical coatings. For an illustration of the present state in thin film technology, damage threshold values of advanced optical components are summarized in Table 3 for laser systems and operation conditions often applied in industrial production environments.

Besides the spectacular experiments in laser fusion, isotope separation, and fundamental physics, industrial applications of lasers in material processing, medicine, information technology, and semiconductor lithography are considered as major pacemakers for the progress of high power optics. Therefore, trends in these technology fields will dominantly govern the future development of thin film technology. For example, in semiconductor lithography at a wavelength of 157 nm, which would open the way to feature sizes well below 100 nm, optical coatings with extended lifetimes are still on rank 6 of the list of challenges to achieve an effective lithographic production facility. In next generation lithography, optics

Table 3 Laser-induced damage threshold values of selected optical coating systems for laser applications (Types: HR: high reflecting mirror, AR: antireflective coating, th: thermal evaporation, IBS: ion beam sputtering)

Laser system wavelength	*Type*	*Laser-induced damage threshold ISO 11254*
193 nm, ArF-excimer	AR/th	1–2 J/cm^2 (1 on 1, 20 ns)
	HR/th	2–4 J/cm^2 (1 on 1, 20 ns)
248 nm, KrF-excimer	AR/th	10 J/cm^2 (1 on 1, 30 ns)
	HR/th	$>$20 J/cm^2 (1 on 1, 30 ns)
	HR/IBS	$>$3 J/cm^2 (1 on 1, 30 ns)
1,064 μm, Nd:YAG	AR/th	$>$60 J/cm^2 (12 ns, 0,25 mm)
	HR/th	$>$100 J/cm^2 (12 ns, 0,25 mm)
	HR/IBS	$>$80 J/cm^2 (12 ns, 0,25 mm)
10,6 μm, CO$_2$-Laser	AR/th	$>$20 J/cm^2 (100 ns, 1,4 mm)
		$>$2 kJ/cm^2 (1,2 ms, 250 μm)
		$>$3 kW/mm (cw, 100 μm)
	HR/th	$>$25 J/cm^2 (100 ns, 1,4 mm)
		$>$2 kJ/cm^2 (1,2 ms, 250 μm)

of even smaller wavelengths, around 13 nm, have to be optimized to achieve the 60 nm node. Ultra-short pulse lasers gain importance as innovative tools for material processing, laser medicine, and biology, as well as the analysis and control of chemical reactions. For the development of fs lasers needed in these applications, special high-power broadband coating systems are required. In addition to high LIDT values, these coatings have to fulfil demands with respect to their group delay dispersion for the compensation of dispersion effects in the laser systems. Other challenges have to be expected from applications, where a combination of the high-power handling capability with additional properties has to be achieved. As a typical example, high-power laser coatings with improved mechanical or chemical stability for applications in laser medicine can be considered.

List of Units and Nomenclature

dn/dt	generation rate of electrons in the conduction band
g	radius of a spherical inclusion; (cm)
$I(t)$	power density of laser radiation,
k	thermal conductivity; (W/(cm °C))
k_E	thermal conductivity of a spherical inclusion; (W/(cm °C))
LIDT	laser induced damage threshold (J/cm^2; W/cm^2; W/cm)
n'	refractive index of a spherical inclusion; (1)
P	output power of a laser; (W)
q	correction factor representing interference effects in coatings
Q	Mie absorption coefficient of a spherical inclusion;
QWOT	quarter wave optical thickness: unit for the thickness of the layer
t_I	irradiation time for a cw-laser; (s)
$T(r)$	temperature in a spherical inclusion at the radial position r; (°C)
w	diameter of a laser beam with Gaussian profile; (cm)
α	impact ionization coefficient; (1)
β_m	m-photon absorption coefficient; (1)
β_S	surface absorption of an optical component; (1)
ΔT	temperature rise in the center of an irradiated circular spot; (°C)
κ	thermal diffusivity; (cm^2/s)
κ_E	thermal diffusivity of a spherical inclusion; (cm^2/s)
λ	wavelength of a laser; (cm)

See also

Optical Coatings: Thin-Film Optical Coatings.

Further Reading

Bloembergen N (1973) Role of cracks, pores and absorbing inclusions on laser damage threshold of transparent dielectrics. *Applied Optics* 12(4): 661–664.

Genin FY and Stolz CJ (1996) *Morphologies of laser induced damage in hafnia-silica multilayer mirror and polarizer coatings*, Third International Workshop on Laser Beam and Optics Characterization. In: Morin M and Giesen A (eds). *Proc. SPIE 2870*, 439–448.

Guenther AH, *et al. Proceedings of the Symposium on Laser Induced Damage in Optical Materials, NBS (NIST) Special Publication 1969–1989*, SPIE vols. 1989–2003. CD-Rom version of collected papers from 1969 to 1998 available: Washington: SPIE.

Guenther KH, Ebert J, Kiesel E, *et al.* (1984) 1.06-m laser damage of thin film optical coatings: a round-robin experiment involving various pulse lengths and beam diameters. *Applied Optics* 23: 3743.

ISO 11254 (2001) *Test methods for laser induced damage threshold of optical surfaces*. Part 1: 1 on 1-test, 2000, Part 2: S on 1 test.

ISO 11254-3 (2002) *Laser and laser-related equipment – Determination of laser-induced damage threshold of optical surfaces – Part 3: Assurance of laser power handling capabilities*. Draft Standard. International Organization of Standardisation.

Jasapara J, Nampoothiri AVV, Rudolph W, Ristau D and Welsch E (2001) Femtosecond laser pulse induced breakdown in dielectric thin films. *Physical Review B* 63(4): 045117.

Puttick K, Holm R, Ristau D, *et al.* (1997) *Continuous wave CO$_2$ laser induced damage thresholds in optical* *components*, Proceedings of the Symposium on Laser Induced Damage in Optical Materials. SPIE vol. 3244, 188–197.

Rudolph W, Mero M, Liu J, *et al.* (2003) *Femtosecond pulse damage and pre-damage behavior of dielectric thin films*, Proceedings of the 34th Annual Symposium on Optical Materials for High Power Lasers. SPIE vol. 4932, 202–215.

Walker TW, Vaidyanathan A, Guenther AH and Nielsen P (1979) *Impurity breakdown in thin films*, Proceedings of the Symposium on Laser Induced Damage in Optical Materials. NBS Special Publication, No.568, 479–495.

Wood R (1990) *Laser Damage in Optical Materials.* Bristol and New York: Adam Hilger. Reprint with corrections.

Optical Black Surfaces

S M Pompea, National Optical Astronomy Observatory, Tucson, AZ, USA

S H McCall, Stellar Optics Research International Corporation (SORIC), Thornhill, ON, Canada

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Black surfaces play an important role in many, if not most, optical systems. Optical instruments and systems of all types often rely on black surfaces to help minimize the effect that stray or off-axis light can have in degrading optical system performance. The strategic selection and placement of appropriate black surfaces can often limit significant detrimental stray light effects in an optical systems, thereby dramatically improving system performance. The high emissivity of black surfaces also gives them an important role in the design and construction of black bodies, calibration surfaces, and radiator surfaces.

The characterization and selection of black surfaces is an important field of optics and optical system design. However, the selection of black surfaces is a specialized undertaking requiring careful study to ensure the proper selection of particular surfaces for each optical system. A black surface that works well in one application may not be at all appropriate for a different application, where different systems performance goals are desired. The wavelength of operation of the system is an important consideration since a surface which has low reflectance at one wavelength band may have different reflective properties at another wavelength or range of wavelengths. Specialized measuring devices called goniophotometers are often used to characterize the reflectance and scatter of black surfaces for a given wavelength or set of wavelengths. Goniophotometric measurements can be used to create a specialized functional description of reflectance and scatter off a surface, called the Bidirectional Reflectance Distribution Function (BRDF) or Bidirectional Scatter Distribution Function (BSDF). In practice, having the BRDF or BSDF of a surface is extremely valuable for surface selection and is more useful than other reflectance and scatter measurement measurements or descriptions. Comparing the measured BRDF or BSDF of several surfaces helps to distinguish the general optical properties of these surfaces and allows a direct comparison of the value of these different surfaces in an optical system as they contribute to overall system performance.

The BRDF distinguishes, at a particular wavelength, how a surface specularly reflects or how it scatters light in different directions when incident light from a particular direction relative to the surface (at a given angle of incidence) interacts with the surface. By understanding the BRDF of a surface, the optical designer can understand how the surface behaves in a given system location when illuminated from a specific direction. The BRDF of a black surface is also important because it can be used as a mathematical function in stray light analysis programs to predict system performance. The BRDF and other properties of surfaces can be input into stray light codes so that the propagation of light from black surfaces can be modeled through Monte Carlo-based propagation models. Using these models, the stray light can be directed through the placement of black surfaces into directions less likely to degrade system performance. Thus a measure of stray light control can be gained through absorption by black surfaces or by redirection of the stray light into less critical directions.

Black surfaces may be considered a subset of a class of surfaces known as spectrally selective surfaces. The term 'spectrally selective surface' indicates that the spectral properties of many surfaces are different when examined in various spectral regions. For applications such as the design of blackbodies, space radiators, and baffles, surfaces with unique spectral emissive and reflection properties are needed. Large databases of spectrally selective surfaces are available to allow the optical designer flexibility in choosing surfaces for applications where specific optical reflectance and optical scatter properties are desired. Spectrally selective surfaces are important for applications that range from solar energy to telescope design. In some applications, it is desirable for a surface to be highly absorbing at one wavelength and more reflective at another, rather than to be highly absorbing of light over a wide range of wavelengths. An analysis of the spectral properties of a large number of surfaces allows the optical designer to choose surfaces optimized for a particular application.

Black surfaces come in many types, but may be generally characterized as being more shiny (specular) or more diffuse (Lambertian) in their reflective and scattering properties, depending on the form of their BRDF curve. Surfaces are often described in computer models as a combination of their respective specular and Lambertian properties for a given wavelength. Many black surfaces have significant reflectivity at some region of the electromagnetic spectrum, even if they are highly absorbing at one wavelength. Some black surfaces are constructed to be remarkably nonreflecting over a range of wavelengths; these surfaces are often used as baffle surfaces for telescopes and instruments that must operate over a wide range of wavelengths. No black surface can work well in all optical systems. Optical designers must understand the specific optical properties of a black surface to determine if the surface can work in their particular system. To characterize a surface, it is helpful to know at least the BRDF of the surface at the wavelength of interest as well as basic materials properties of the surface. The specific BRDF at the most appropriate wavelength for the system can be used with the optical system stray light model to determine if the surface can fulfill the designer's, expectations of it for the system performance. The placement and choice of black surfaces in an optical system are often critical decisions with highly significant effects on overall system performance.

For this reason, optical designers rely greatly on databases of the reflection and scatter properties of black surfaces in order to make the right choice of surface. These databases have been created to provide the optical engineer with the information needed to understand a wide variety of candidate surfaces and select the most appropriate ones. These databases not only describe the optical properties of surfaces but also elucidate material properties so that the selection process can examine the heat resistance, outgassing rates, fade resistance, durability, and a myriad of other surface or material properties that may be relevant.

The reflectance and scatter data on black surfaces are often taken using a variety of reflectance-measuring instruments and the data format often varies greatly. When published and unpublished data sets are compiled, they are often confusing and sometimes even contradictory. This has made the comparison of surfaces a difficult proposition. In recent years, there have been successful attempts to gather existing large amounts of existing data so that comparisons among black surfaces can be made in a data-rich environment so that anomalous data can be ignored. A significant amount of reflectance data on black surfaces has been created by private or governmental organizations such as NASA and NIST – the US National Institute for Standards and Technology. These data now appear in databases of BRDF and reflectance measurements. Designers are relying increasingly on databases of BRDF surfaces rather than the individual measurements that can be found in the optical physics and applied optics published literature.

Uses of Black Surfaces

Table 1 lists some of the major areas in which black surfaces or black coatings may be used in instruments and optical systems. The optical properties of desirable surfaces may be different for the specific categories in the table. Plausible surfaces for these different applications can be found in materials databases such as the SOLEXIS™ database which contains a useful compilation of data from private

Table 1 Possible uses for black surfaces and black coatings in optical systems

Apertures	Baffles	Barrels	Calibration screens	Choppers
Cold shields	Detectors	Dewars	Diffusion screens	Domes for telescopes and instruments
Enclosures and curtains for rooms and instruments	Integrating sphere enclosures	Lens edges	Light traps	Mounts
Radiators	Radiometers	Solar collector absorbers and concentrators	Standards and references of reflectance	Targets

and governmental data compilations from the US, Canada, and the former Soviet Union.

Selection of Optical Black Surfaces

The selection of appropriate black surfaces for a given application becomes progressively harder as the number of optical requirements (e.g., reflectivity, scatter, emissivity, etc.) and materials requirements (e.g., stiffness, coefficient of thermal expansion, etc.) increase. Because of this, the selection process for specialized surfaces for space applications can be quite involved, since there are a large number of criteria, each of which may be regarded as an essential requirement.

The optical system designer must consider at least the following aspects of the system in selecting a surface:

- the wavelength(s) and waveband(s) of interest;
- the position of the surface in optical system;
- the general robustness required of the surface;
- the environment of the optical system;
- the cost including inspection, handling, and assembly; and
- the production and delivery schedule, including spares.

The selection process must carefully address the system needs as well. Poor decisions are often made when only a cursory study of potential black surfaces is made or when databases and the literature on the subject are neglected. Therefore, an important part of the selection process is the management of the timing of the selection, in order to give the designer time to access available information and to influence the system design in a timely manner.

If black surfaces are used for stray light control, then the use of these surfaces must be planned at the beginning of the optical system design process. If the placement of black surfaces and the array of potential surface treatments are examined early in the program, the optimal choices can often be determined in a careful manner that enhances the system performance. If the selection is saved until the very end of the program, the choice of surfaces will be more limited and improvements in system performance may be minimal, even with the most excellent black surfaces. This is because the location of the surfaces in the system often proves to be as critical as the choice of surface. If the surface is in the wrong location, the best optical black may not be able to improve the stray light performance. For best results, the layout of the system and the placement of baffles must be considered first, before the baffle surfaces are selected.

An optimal flowchart of good system design for black surface selection is given in Figure 1. Figure 2 describes a work flowchart where black surface selection is neglected until the end of the program, often with dire consequences for system performance, cost, and schedule.

For space-based systems, the effect of atomic oxygen in a low-earth orbit environment is an important consideration. For space systems, the designer must also examine how black surfaces may be affected by or contribute to contamination and outgassing. Other considerations are the generation of particles during launch, the effect of solar



Figure 1 Diagram of the system design process which treats black surface selection as an important part of basic system design, to be done early in the design process. This gives the designer an opportunity to conduct system tradeoffs to optimize system performance.



Figure 2 Diagram of a poor system design process. This process addresses the selection of black surfaces late in the system design process, where selection is significantly more difficult, expensive, and risky. Even with a late selection, there may be severe impacts on schedule.

ultraviolet radiation on black surfaces, and how spacecraft charging may affect conductive, dielectric, or insulating black surfaces. Since black surfaces may have a large surface area in an optical system, the designer must ensure that the black surfaces do not contribute significantly to the risk of system failure through some degradation process that may contaminate other optical surfaces. For space-based systems, data on surface outgassing and the past performance of a surface in a specific space environment is essential.

There are a variety of resources available to assist in the selection of black surfaces. The best databases allow the user to create 2-dimensional and 3-dimensional BRDF plots for extensive lists of potential black surfaces. For most surfaces, with no preferred directionality in the structure of the surface, a 2-dimensional BRDF plot is adequate. Most of these databases provide information on a wide variety of spectrally selective materials including black, white, and reflective surfaces for thermo-optical applications for ground and space-based instrumentation. The BRDF plots can be examined by the user or fed into existing, commercially available optical design and analysis software packages. The results of these models indicate whether the chosen surfaces give adequate performance or whether more specialized coatings are necessary to achieve the desired level of performance.

A significant problem for many designers is that the formulations of many paints and other surface treatments often change. Sometimes the name of the coating remains the same even as the optical properties change, due to a change in the compounds or methods used to prepare the coating. Sometimes the name changes with or without a change in the formulation. These often unpublished changes increase the risk of using older plots from the published literature as definitive optical modeling data. Experts in the optical blacks area continuously investigate these changes and their implications and can advise optical designers of the implications of recent changes in the paint and coating arena. These experts are often aware of situations where coating failures have occurred or where mission performance was degraded by unanticipated changes in coatings, even if reports of this incidents were never published.

In summary, the selection process, by its very nature, must be a deliberate and careful effort to examine the best surface options. Some of the better surfaces which were considered laboratory standards (e.g., 3M Black) are no longer easily available and replacements must be found. For the most systematic decision-making process, access is needed to the best optical black surface databases, often commercial databases with hundreds to thousands of BRDF curves on several hundred materials. The use of these optical surface databases can substantially reduce the costs, time, and scope of a measurement program, as well as streamline the selection process. Additionally it allows the designer to consider materials used successfully in other programs which may not be familiar to the designer. Finally, the designer may avoid using materials that have been rendered unreliable through changes in the manufacturing process or in the coating chemistry.

Characterization of Black and Spectrally Selective Surfaces

Optical Characterization

An understanding of black surfaces relies heavily upon an understanding of the meaning and use of the BRDF. While the optical properties of surfaces can be characterized through specular and diffuse reflectance measurements, the use of BRDF measurements has become extremely important. BRDF measurements are equally adept at characterizing highly specular and highly diffuse surfaces and the myriad of surfaces with both characteristics. The BRDF is often used in general to describe the angle-dependent optical scatter from these surfaces. This is important as the angular distribution of scatter can be used to calculate if the scatter from a black surface will be a limiting factor in the resolution or noise level of the system. BRDF measurements can even be used in computer graphics visualization programs that illustrate what a surface may look like under various illumination conditions. For example, the BRDF is used in computer graphics models to render a certain color for an automobile or a countertop in a kitchen. For some black surfaces, the angular distribution of scatter can be used to calculate a variety of surface parameters such as the surface roughness, given certain assumptions about the surface. For opaque black surfaces, BRDF measurements have proved to be one of the best overall descriptors of the optical properties of the surface.

BRDF is defined as the ratio of scattered radiance (watts/(cm^2 sr)) to surface irradiance (watts/cm^2); its units are inverse steradians. Radiance is used in the definition, in order to make the BRDF independent of the parameters of the measuring instrument, such as the detector aperture and distance to the detector. BRDF measurements are made by a variety of instruments for a number of wavelengths. For example, BRDF measurements of surfaces have been made in wavelengths ranging from the vacuum ultraviolet to the far infrared. The most common BRDF measurements made on black surfaces are made at laser wavelengths of 0.6328 and 10.6 micrometers. However, these measurements may be of limited value if the system is operating at substantially different wavelengths, where the surface's BRDF is significantly different.

To make a BRDF measurement requires a light source, a sample mounted and illuminated by that source, a receiver (detector) to measure the scatter from the sample, and the computer/electronics package to accurately record the detection of the scattered light. Additionally the sample and/or light source must be able to be moved so that the sample can be illuminated from nearly every angle, and scattered light from the surface can be detected in a hemisphere around the sample. The geometry of the BRDF measurement is illustrated in Figure 3.

To make a BRDF measurement on black surfaces, appropriate sources, detectors, and low-scatter optics must be used. This becomes more difficult for wavelengths less than about 0.25 micrometers. At longer, infrared wavelengths, diffraction effects become important. Despite the instrumental difficulties, it is often better to measure the amount of scatter at a specific wavelength λ and angle θ_s, rather than try to predict it from theoretical models. This is because the extrapolation to new angles or wavelengths using scaling theories is not always accurate or even possible. Methods for wavelength scaling (extrapolating from BRDF data for one wavelength to data for any other wavelength) or angle scaling (where data taken at particular incident and scatter angles are extrapolated to other angles) will not be discussed as BRDF curves are now widely available for many surfaces at a variety of wavelengths and angles.

The definitions of BRDF are given in Table 2.



Figure 3 Geometry of BRDF measurement and the angle conventions accepted by the American Society for Testing Materials (ASTM). The plane of incidence is the I-0-ZB plane and the scatter plane is the S-0-ZB plane.

Table 2 BRDF term definitions

Bidirectional reflectance distribution function BRDF	The sample radiance divided by the sample irradiance. The procedures given in this practice are correct only if the field of view (FOV) determined by the receiver field stop is sufficiently large to include the entire illuminated area
Scatter	The radiant flux that has been redirected (by interaction with the sample) over a range of angles
Sample coordinate system	A coordinate system is fixed to the sample and used to a specify position on the sample surface for the measurements. The sample coordinate system may be application and sample specific. A Cartesian coordinate system is recommended for flat samples, with the origin at the geometric center of the sample face with the Z axis normal to the sample
Plane of incidence, PLIN	The plane defined as containing the central ray of the incident flux and the sample normal
Beam coordinate system, XB, YB, ZB	A Cartesian coordinate system defined with the origin on the central ray of the incident flux at the sample surface, the XB axis in the plane of incidence (PLIN) and the ZB axis normal to the surface. The angle of incidence, scatter angle, and incident and scatter azimuth angles are defined with respect to the beam coordinate system
Incident direction	The central ray of the incident flux specified by θ_i and φi in the beam coordinate system
Angle of incidence, θ_i	Angle between the central ray of the incident flux and the ZB axis
Incident azimuth angle, φ_i	The fixed 180° angle from the XB axis to the projection of the incident direction onto the XB–YB plane. It is convenient to use a beam coordinate system in which $\varphi_i = 180°$ since this makes φ_s the correct angle to use directly in the familiar form of the grating equation. Conversion to a sample coordinate system is straight forward, provided the sample location and rotation are known
Scatter direction	The central ray of the scattered flux specified by θ_s and φ_s in the beam coordinate system
Scatter angle, θ_s	Angle between the central ray of the scattered flux and the ZB axis
Scatter azimuth angle, φ_s	Angle from XB axis to the projection of the scatter direction onto the XB–YB plane
Specular direction	The central ray of the reflected flux that lies in the PLIN with $\theta_i = \theta_s$ and $\varphi_s = 0$
Delta theta, $\Delta\theta$	The angle between the specular direction and the scatter direction
Delta beta, $\Delta\beta$	The projection of $\Delta\theta$ onto the XB–YB plane, that is, the $\Delta\theta$ angle measured in direction cosine space. For scatter in the PLIN, $\Delta\beta = \sin\theta_s - \sin\theta_i$. For scatter out of the PLIN, the calculation of $\Delta\beta$ becomes more complicated
Receiver solid angle, Ω	The solid angle subtended by the receiver aperture stop from the sample origin
Sample radiance, L_e	A differential quantity that is the reflected radiant flux per unit projected receiver solid angle Ω per unit sample area. L_e is often an average calculated from scattered power, P_s collected by the projected receiver solid angle $\Omega \cos\theta_s$, from the illuminated area, *A*. The receiver aperture and distance from the sample determines Ω and the angular resolution of the instrument
Sample irradiance, E_e	The radiant flux incident on the sample surface per unit area. In practice, E_e is an average calculated from the incident power, P_i, divided by the illuminated area, *A*. The incident flux should arrive from a single direction; however, the acceptable degree of collimation or amount of divergence is application specific and should be reported

Table adapted from ASTM E1392-90 “Standard Practice for Angle Resolved Optical Scatter Measurements on Specular or Diffuse Surfaces,” American Society for Testing Materials, 1990.

Given these definitions, BRDF, is mathematically described by

$$\mathrm{BRDF} = \frac{L_e}{E_e} = \frac{(P_s/\Omega A \cos\theta_s)}{(P_i/A)} = \frac{P_s}{P_i \Omega \cos_s}\ [\mathrm{sr}^{-1}]$$

The BRDF is a function of many measurable quantities. It depends on the angle of incidence of the incident flux and the wavelength of this radiation. It also depends on the direction in which the scattered light is measured as well as the wavelength and polarization of the incident and scattered flux. The BRDF can be calculated for a given angular configuration of incident source and detector from the average radiance divided by the average irradiance. The BRDF is therefore referenced by the incident power. The cos θ_s term in the formula accounts for the foreshortening of *A* as the angle θ_s increases, so that true radiance is being used in the calculation. Because of this, the BRDF is constant for a surface with Lambertian (uniformly diffuse) properties. The detector must have a field of view so that all of *A* can be viewed and such that P_i includes the entire beam. In practice, P_i is measured by removing the sample from the measurement position. Then the detector is moved into the straight-through position. Often a reference detector is used to monitor the incident beam power so that any changes after the initial V_i, measurement can be recorded.

For BRDF measurements to be meaningful, the instrument signature must be examined and understood. This is particularly important in the measurement of low-scatter surfaces. The instrument signature is the BRDF when the sample is removed and there is no sample scatter. In this case the stray light and scatter signature of the device will be apparent. Angular positioning errors and electronic noise can also be important. For example, as θ_s approaches 90° the accuracy of measuring θ_s becomes critical due to the $1/\cos\theta_s$ term in the BRDF equation. Ideally the instrument signature is a small fraction of the BRDF being recorded. An understanding of the instrument signature provides the needed information to decide where the BRDF data loses its meaning.

The BRDF is most often displayed in a plot, where the BRDF value (vertical axis) and the angle of scatter (horizontal axis) are plotted on logarithmic scales. In these 'log–log' plots it is easy to examine the scatter distribution close to the specular direction which, for shiny surfaces, represents the bulk of the scattered light. For surfaces that are diffuse in nature, a log–log plot of the BRDF generally yields a straight line. The slope of this plot is characteristic of the surface of the process which is used to produce the surface. This straight-line plot is useful in comparing samples made with the same process. Deviations from the slope of the line or the value of the points on the line indicate that there may be problems with a sample. Thus the simplest scattering instrument can be used for quality control of black samples. For a fixed angle of incidence and a fixed detection angle, variations in the BRDF value may indicate changes in the materials or the processes which created their surfaces. The quality control process can be performed by looking for variations in the BRDF among the different samples.

The BRDF can be used as a measure of surface roughness – an important attribute for a diffuse black surface. As random surface roughness features increase on a surface, the scatter from the surface also increases. Because of this, the BRDF can be used to characterize surface roughness parameters. If the surface roughness is all in the form of small, micro-rough surface features, the BRDF value then is very much proportional to the surface power spectral density function (PSD), which is a measure of the power plotted against spatial frequency. The characterization of surface roughness by BRDF scatter measurements only works if the scattered energy is due to surface micro-roughness. If the scatter is from larger surface features or from surface contamination, then it will be difficult to accurately characterize the surface roughness. Thus only smooth, mirror-like black surfaces can be used for this simple leap from BRDF values to surface roughness parameters. Some sample BRDFs of black surfaces are found in Figures 4–7.



Figure 4 BRDF at wavelength of 0.633 micrometers and 60° incidence angle of black anodize sample. Plot generated by SOLEXIS using CASI software from Schmitt Measurement Systems, Portland, OR, USA.



Figure 5 BRDF at wavelength of 10.6 micrometers of black anodize at 45° incidence. Plot generated by SOLEXIS using CASI software from Schmitt Measurement Systems, Portland, OR, USA.



Figure 6 BRDF at a wavelength of 10.6 micrometer of Martin Optical Black at 45° incidence. Plot generated by SOLEXIS using CASI software from Schmitt Measurement Systems, Portland, OR, USA.



Figure 7 BRDF at a wavelength of 0.488 micrometers of a glossy black surface at 60° incidence. Plot generated by SOLEXIS using CASI software from Schmitt Measurement Systems, Portland, OR, USA.

Examples of Black Surfaces

Black surfaces appear in many forms. They may be either diffuse or specular in nature, or both. Black surfaces may be created by painting a surface, by altering a surface (such as through an anodization process), or by any number of other surface treatment effects. For example, absorbing compounds may be added to paint or to a surface to decrease reflection. Adding large (compared to the wavelength) craters or holes to a surface may result in multiple reflections within the surface leading to decreased reflection. Surfaces may be modified to increase their light-scattering ability, with the hope that reflection in a specific direction will be reduced. Sometimes surfaces may be created in such a way as to enhance thin-film interference effects, leading to reduced reflection. These and other techniques may be combined together in an attempt to reduce reflection and make the material appear blacker in a particular wavelength range of interest or in a particular direction.

Some sample black surfaces are given in Table 3, although databases are much more current on current names and manufacturers.

Many black surfaces use surface texture to enhance their light-absorbing ability. Scanning electron micrographs of surfaces reveal the surface morphology and how multiple reflections can be used for light trapping. Surface chemistry, changes in the index of refraction, and the use of particles of different sizes are also used to create better absorbers. A variety of other proprietary methods are used as well (Figures 8–11).

Future Developments

There are many new kinds of black surfaces being developed for specialized applications. Black surfaces can be created using a variety of new techniques and materials. For example, new surfaces can be created using laser ablation or chemical microetching of surfaces. Surfaces can also be created using new materials such as carbon nanotubes or by using the technology used to create flocked materials. These new kinds of surfaces generally have good absorption at a variety of wavelengths. Even with the creation of these new surfaces, the greatest gain in an optical system will probably be attained through a concerted effort to choose the appropriate black surfaces early in the program and to place them properly in the optical system. An early selection of surfaces and an analysis of their performance will lead to a higher level of system performance than a search for an exotic, ultrablack surface at a late stage

Table 3 Selected optical black surfaces

Name	*Manufacturer*	*Notes*	*Type*
Aeroglaze L300	Lord Corporation Erie, PA	Formerly called Chemglaze L300	Paint
Aeroglaze Z004	Lord Corporation Erie, PA	Formerly called Chemglaze Z004	Paint
Aeroglaze Z302	Lord Corporation Erie, PA	Formerly called Chemglaze Z302	Paint
Aeroglaze Z306	Lord Corporation Erie, PA	Formerly called Chemglaze Z306	Paint
Aeroglaze Z306 with microspheres	Lord Corporation Erie, PA	Formerly called Chemglaze Z306 with microspheres	Paint
Aeroglaze Z307	Lord Corporation Erie, PA	Formerly called Chemglaze Z307	Paint
Aeroglaze Z313	Lord Corporation Erie, PA	Formerly called Chemglaze Z313	Paint
Ames 24E (Ames 24E2)	NASA Ames Research Center Moffett Field, CA		Paint
Cardinal 6450	Cardinal Industrial Finishes South Elmonte, CA	Formerly 'Cardinal 6550'	Paint
Cornell Black	Cornell University		Paint
DeSoto Flat Black	Courtaulds		Paint
Electrically Conductive Black Optical Paint	Jet Propulsion Laboratory Pasadena, CA	Has no trade name	Paint
IITRI Bone Black D-111 (IITRI D111)	Illinois Institute of Technology Chicago, IL		Paint
LMSC Black	Lockheed Martin Palo Alto		Painted multilayer coating
MH21-I	Illinois Institute of Technology Chicago, IL		Paint
MH55	Illinois Institute of Technology Chicago, IL		Paint
MH2200	Illinois Institute of Technology Chicago, IL	Formerly 3M's ECP 2200 paint, but sold to IIT	Paint
Solarchem	Eastern Chem Lac Corporation Malden, MA		Paint
463-3-8	Akzo Coatings, Inc. Orange, CA	Formerly called 'Cat-a-lac 463-3-8' diffuse black paint	Paint
443-3-8	Akzo Coatings, Inc. Orange, CA	Formerly called 'Cat-a-lac 443-3-8' glossy black	Paint
443-3-17	Akzo Coatings, Inc. Orange, CA	Formerly called 'Sikkens 443-3-17'	Paint
Infrablack	Lockheed Martin Denver, CO	For Al substrates only	Anodization process
Martin Black	Lockheed Martin Denver, CO	For Al substrates only	Anodization process
Martin Black, Enhanced	Lockheed Martin Denver, CO	For Al substrates only	Anodization process
Infrablack	Lockheed Martin Denver, CO	For Al substrates only	Anodization process
Black Chrome Type Surfaces	Lockheed Martin Denver, CO	For many kinds of metal substrates	Electrodeposition process
Black Cobalt Type Surfaces (Cobalt Black)	Lockheed Martin Denver, CO and many more companies	For many kinds of metal substrates. References to Black Copper, Black Steel etc. are covered by Black Cobalt	Electrodeposition process, and can be followed by chemical or thermal oxidation
Black Nickel	−NIST	For many kinds of metal substrates	Deposition and etching process
(NBS Black)	−Ball Aerospace		
(Ball Black)	−Lockheed Martin and others	Ball modified the process developed by NBS	
Black Kapton™ Foil			Foil
Black Tedlar™ Foil			Foil
Boron Black	Lockheed Martin Denver, CO	For many kinds of metals	Plasma spray deposition process
Boron Carbide	Lockheed Martin Denver, CO	For Ti substrates only	Proprietary process
Silicon Carbide	Lockheed Martin Denver, CO and other companies	For many kinds of metals	Chemical vapor deposition
Textured Surfaces	−NASA Ames Research Center Moffat Field, CA −SPIRE Corporation Bedford, MA −Optics MODIL Oak Ridge National Laboratory	For many kinds of metal substrates	Either: −sputter coated −ion beam etched −sputter coated then etched

Note that finish names and manufacturers change regularly. Table adapted from SOLEXIS™ database, Stellar Optics Research International Corporation (SORIC), 78 Normark Dr., Thornhill, Ontario, Canada L3T 3R1.



Figure 8 Scanning electron micrograph of Martin Optical Black surface on 6061T6 aluminum. This surface is a good absorber at ultraviolet, visible, and near infrared wavelengths. (Courtesy of Stephen Pompea and Donald Shepard.)



Figure 9 Scanning electron micrograph of phosphoric acid etched electroless nickel surface. This surface is a good absorber in the visible wavelength region. (Courtesy of Stephen Pompea and Donald Shepard.)



Figure 11 Scanning electron micrograph of tungsten hexafluoride surface. This surface is a good absorber at visible and near infrared wavelengths. (Courtesy of Stephen Pompea and Donald Shepard.)

in the program. Although better black surfaces are constantly being developed, the most important future development in the area of black surfaces may be a wider realization of the importance of an early and comprehensive surface selection process. The value of starting the selection process early using black surface databases has been confirmed repeatedly by optical designers.

See also

Instrumentation: Photometry; Telescopes. **Scattering:** Scattering from Surfaces and Thin Films.



Figure 10 Scanning electron micrograph of Aeroglaze Z-306 painted surface with embedded microspheres. This surface is used primarily at visible wavelength. (Courtesy of Stephen Pompea and Donald Shepard.)

Further Reading

American Society for Testing Materials (ASTM) (1990) ASTM E1392-90. *Standard Practice for Angle Resolved Optical Scatter Measurements on Specular or Diffuse Surfaces*. West Conshohocken, PA: ASTM.

Bennett JM and Mattsson L (1989) *Introduction to Surface Roughness and Scattering*. Washington, DC: Optical Society of America.

Bohren CF and Huffman DF (1983) *Absorption and Scattering of Light by Small Particles*. New York: John Wiley and Sons.

Breault RP (1995) Control of stray light. In: *Handbook of Optics*, 2nd edn. New York: Optical Society of America.

Church EL and Takacs PZ (1995) Surface scattering. In: Bass M (chief ed.) *Handbook of Optics*, 2nd edn. New York: Optical Society of America.

Granqvist CG (1989). *Spectrally Selective Surfaces for Heating and Cooling Applications*. Volume TT 1. Bellingham, WA: SPIE Optical Engineering Text.

Gunderson JA (1977) *Goniometric Reflection Scattering Measurements and Techniques at 10.6 Micrometers*. Thesis, University of Arizona.

Henninger JH (1984) Solar absorptance and thermal emittance of some common spacecraft thermal control coatings. *NASA Reference Publication 1121*.

Jelinsky P and Jelinsky S (1987) Low reflectance EUV materials: a comparative study. *Applied Optics* 26(4): 613–615.

Persky MJ (1999) Review of black surfaces for space-borne infrared systems. *Rev. Sci. Instruments* 70(5): 2193–2217.

McCall SHCP, Pompea SM, Breault RP and Regens NL (1992) Reviews of properties of black surfaces for ground and space-based optical systems. In: Breault RP (ed.) *Proceedings of the SPIE: Stray Radiation II*, vol. 1753.

Pompea SM and Breault RP (1995) Optical black surfaces. In: *Handbook of Optics*, 2nd edn. New York: Optical society of America.

Pompea SM, McCall SHCP (1992) Outline of selection process for black buffle surfaces in optical systems. In: Breault RP (ed.) *Proceedings of the SPIE: Stray Radiation in Optical Systems* II, vol. 1753.

Pompea SM, Shepard DF and Anderson S (1988) BRDF measurements at 6328 Angstroms and 10.6 micrometers of optical black surfaces for space telescopes. In: Breault RP (ed.) *Proceedings of the SPIE: Stray Light and Contamination in Optical Systems*, vol. 967, pp. 236–248.

Smith SM (1980) Far infrared (FIR) optical black bidirectional reflectance distribution function (BRDF). *Proceedings of the SPIE: Radiation Scattering in Optical Systems* 362: 161–168.

SOLEXIS™ Database of BRDF Measurements (2003) Stellar Optics Research International Corporation (SORIC), Ontario, Canada.

Stover J (1995) *Optical Scattering: Measurement and Analysis*, 2nd edn. Bellingham, WA: SPIE Optical Engineering Press.

Wolfe WL (1978) Optical materials. In: Wolfe WL and Zissis GJ (eds) *The Infrared Handbook*. Ann Arbor, Michigan: ERIM.

Thin Film Optical Coatings

D Ristau, Laser Zentrum Hannover e.V., Hannover, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Thin-film optical coatings are employed to adapt the properties of an optical surface to its specific application. Commonly, optical coatings comprise a sequence of single layers of different transparent materials with a thickness in the range of the operation wavelength. Depending on this coating design, the spectral characteristics of an optical surface can be tuned to nearly any required transfer function including a suppression of reflection for a broad spectral range by an antireflective coating or even the achievement of highest reflectance values up to 99.999% using a high reflecting layer stack. Besides these basic functions, optical coatings can be employed to realize a variety of transfer spectra specified for multiple wavelengths or wavelength ranges to manipulate radiation according to even extremely sophisticated demands in optical systems for laser technology, communication, or fundamental research. Moreover, the desired optical properties can be combined with additional specifications, for example, concerning the mechanical or chemical stability of an optical surface by selecting adapted coating materials. As a consequence of this enormous versatility, thin-film optical coatings can be found in nearly every product and development of modern optical technology today. Aside from the large market of consumer optics including ophthalmology, camera objectives, binoculars, and optical systems for data storage, progress in optical coating technology is predominantly driven by demanding applications in many future technology fields. As one prominent pace-setter, semiconductor lithography imposes new demands on optical coatings extending the operation wavelength of stepper systems in chip production to the extreme ultraviolet (EUV)-spectral range. Other examples can be found in communication technology, where thin-film filters with a bandwidth below

0.5 nm are required, or also in laser material processing, where coatings with high power handling capability and lifetime are indispensable for the development of cost-efficient laser tools.

In this article a concentrated review will be given on the design, production, and on specific properties of optical coatings. After an introduction to the fundamental principles of operation of coating systems, basic expressions for the optical transfer function of a single layer will be derived and extended to layer structures on the basis of the matrix method. Selected conventional and ion processes for the production of coatings will be discussed with respect to the achievable optical and structural properties of the coatings. Also, the thickness control of the coatings during production will be considered introducing the crystal monitoring technique as well as optical measurement strategies at a single wavelength or in a broad spectral range. The article will conclude with a review of the present state of optical coatings and an analysis of future trends.



Figure 1 Basic structure of a thin-film system. Transparent layers of at least two different materials (n_H, n_L) are deposited on a substrate with refractive index n_T.



Figure 2 Schematic path of a plane wave incident onto a single layer with refractive index n_1. The reflection and transmission coefficients for the amplitudes at the interfaces $m = 1, 2$ are denoted by t_m and r_m, respectively. A prime added to the coefficients indicates a transfer of the wave opposite to the direction of incidence.

Design of Optical Coatings

The colorful appearance of optical coatings and microstructures, which can be observed on some butterflies and other insects, was present in nature long before mankind invented them. The beginning of the technical evolution of optical surfaces may be dated back to Greek culture, where polished metal surfaces were used as mirrors. Considering the application of transparent coatings, the investigations of Joseph Fraunhofer in the reflectivity of aged glass surfaces during the year 1819 should be mentioned as a first approach towards an antireflective coating. On the basis of controlled etching, this technique was further developed for different glass materials by Dennis Taylor in 1891 to realize the first antireflective coatings on lenses for applications in optical devices. In 1899, the Fabry–Perot theory was developed as a milestone in the theoretical description of multilayer structures. This theory describes the interference of partial waves reflected from two parallel optical surfaces, which can be considered as the fundamental arrangement of a multilayer structure (see Figure 1). In an optical thin-film system, layers of different transparent materials are composed on a stack deposited on the surface of the optical component (substrate refractive index n_T). In general, to adjust the spectral characteristics of the layer system to the demanded specifications, at least two layer materials with a high refractive index n_H and a low index n_L have to be selected. The choice of the thin-film materials is dependent on the application wavelength and the desired stability of the coating system as well as on their optical properties essential for the specific design and the targeted optical quality. Similar to the Fabry–Perot principle, the optical function of the layer structure is based on the interference of partial waves reflected and transmitted at the interfaces between the layers. The trace of the incoming wave and the induced partial waves are depicted in Figure 2 for a single layer, which can be considered as the basic unit for coating systems even with highest complexity. For a theoretical description of the transfer function of this single layer, the contributions of the individual partial waves have to be calculated and accumulated to form the total transmitted and reflected wave. In this classic approach, the incoming wave can be described by the function of a plane wave with amplitude E_0, wavenumber $k = 2\pi/\lambda$ incorporating the wavelength λ, and frequency ω:

$$E(x,t) = E_0 \exp[-i(kx - \omega t)] \qquad [1]$$

At the first interface, a part of this plane wave is directly reflected with an amplitude of $A_0 = E_0 r_1$

(order zero), which can be calculated using the reflection coefficient r_1 given by the Fresnel formulas. After passing the first interface, a reflection and transmission of the incoming wave at the second interface has to be considered. Also a phase shift has to be taken into account, which is introduced by the path of the wave from the front to the rear interface of the single layer. This phase shift δ_i is dependent on the thickness d_i of the layer and the refractive index n_i:

$$\delta_i = \frac{2\pi n_i d_i \cos\theta_i}{\lambda} \qquad [2]$$

For oblique incidence also the angle of incidence θ_i in the layer, which has to be calculated by Snell's law, has to be taken into account. The index i has been chosen in this consideration for convenience to account for the layer number in coating systems, which will be discussed later. Following the wave reflected the first time inside the layer, a further phase shift for the path from the rear side to the front side has to be taken into account. This partial wave is then transmitted by the front surface resulting in an amplitude A_1 of the first-order wave leaving the layer:

$$A_1 = t_1 t'_1 r_2 E_0 \exp(-i2\delta) \qquad [3]$$

where t'_1 is the transmission coefficient for the amplitude of the wave passing the layer at the interface to the ambient. By following the wave further through the layer, the amplitudes A_k of each partial wave of order k can be determined:

$$A_k = t_1 t'_1 r_2 E_0 \exp(-i2\delta) * (r'_1 r_2 \exp(-i2\delta))^{k-1} \qquad [4]$$

Obviously the contributions of the partial waves follow the rule of a geometric expansion, and therefore the total amplitude of the wave reflected by the layer, which is the sum of the amplitudes of the partial waves, can be expressed in closed form:

$$A_{\mathrm{tot}} = \left[r_1 + \frac{t_1 t'_1 r_2 \exp(-i2\delta)}{1 - r'_1 r_2 \exp(-i2\delta)} \right] E_0 \qquad [5]$$

The reflection coefficient r_{S} of the single layer is given by the ratio between the total amplitude of the reflected wave and the amplitude of the incoming wave:

$$r_{\mathrm{S}} = \frac{r_1 + r_2 \exp(-i2\delta)}{1 + r_1 r_2 \exp(-i2\delta)} \qquad [6]$$

In this equation, the coefficients r'_1 and t'_1 have been replaced by using the relations

$$t_1 t'_1 = (1 - r'_1)(1 - r_1) = (1 - r_1)(1 + r_1) = 1 - r_1^2 \qquad [7]$$

In principle, this method of compiling the contributions of the partial waves reflected at the layer interfaces can be extended also to the calculation of systems with more than one layer. But, considering the enormously increasing number of partial beams, the resulting equations become extremely complicated for multilayer structures. Therefore, the matrix formalism, which can be deduced from the boundary conditions of the electric and magnetic field at the interfaces, is usually employed for the calculation of thin-film systems. The major advantage of this approach, which was developed in the 1940s, is the representation of each layer by a single matrix M_i containing all specific parameters of the film. The matrix M_i of a thin film at position i within the layer system relates the electric (E_{i-1}) and magnetic (H_{i-1}) field strength at the front face to the field strength values (E_i and H_i) at the rear face of the layer:

$$\begin{pmatrix} E_{i-1} \\ H_{i-1} \end{pmatrix} = \mathbf{M}_i \begin{pmatrix} E_i \\ H_i \end{pmatrix} = \begin{pmatrix} \cos\delta_i & \dfrac{i}{n_i}\sin\delta_i \\ in_i \sin\delta_i & \cos\delta_i \end{pmatrix} \begin{pmatrix} E_i \\ H_i \end{pmatrix} \qquad [8]$$

By considering the boundary conditions for the field strengths at the interfaces, the matrix components given in eqn [8] can be determined. On the basis of the matrix formalism, the transfer function of a layer system can be simply accomplished by multiplication of the matrices M_i representing the constituent single layers. Thus, the transfer matrix M_{S} of a stack, which is formed by a number K of single layers with layer 1 located at the first interface with respect to the incoming wave, is given by

$$\mathbf{M}_{\mathrm{S}} = \mathbf{M}_1 \mathbf{M}_2 \mathbf{M}_3 \ldots \mathbf{M}_i \mathbf{M}_{i+1} \ldots \mathbf{M}_K \qquad [9]$$

For calculating the reflection coefficient r_{SK} of the entire arrangement including the substrate (index of refraction n_{T}) and the ambient medium (index of refraction n_0), again the ratios of the amplitudes have to considered:

$$r_{\mathrm{SK}} = \frac{n_0 \mathbf{M}_{11} + i n_0 n_{\mathrm{T}} \mathbf{M}_{12} - i\mathbf{M}_{21} - n_{\mathrm{T}} \mathbf{M}_{22}}{n_0 \mathbf{M}_{11} + i n_0 n_{\mathrm{T}} \mathbf{M}_{12} + i\mathbf{M}_{21} + n_{\mathrm{T}} \mathbf{M}_{22}} \qquad [10]$$

As a consequence of its perceptible structure, the matrix method can be readily transferred into computer codes, which cover the calculation of all important properties of even extremely complicated layer systems. In particular, considering the fundamental relations of the matrix method, also the field strength distribution within the layer structure can be determined. In software packages, which are commercially available as standard tools for optical thin-film technology, often the film thickness D_i of the layers is expressed in the units of QWOT (quarter wave optical thickness) at the design wavelength λ_Z:

$$D_i = \frac{4n_i d_i}{\lambda_Z} \qquad [11]$$

In the case of normal incidence, the matrices M_i reduce to simple expressions for layers of integer QWOT values, because the corresponding phase shift terms are multiples of $\pi/2$. Clearly, an integer QWOT value of optical thickness also represents an extreme value in the spectral behavior at the design wavelength. This fact is often exploited for a precise thickness control by optically monitoring the reflectance or transmittance of the growing layer at the design wavelength λ_Z: by recording the transfer behavior as a function of time during production, extreme values and accordingly thickness values of multiple QWOT can be accurately determined. Thus, if a layer structure is composed only of multiple QWOT layers, switching between the layer materials can always be precisely performed at a minimum or maximum read-out of the optical monitor tuned to the design wavelength. In respect of this advantage in production, most coating designs are based on QWOT layers indicating the practical importance of the unit QWOT. For an efficient description of the designs, often a notation in capital letters is used, which indicate a 1 QWOT layer of a certain coating material. For example an alternating QWOT-stack with 11 layers of a high-index material (H, refractive index n_H) and a low-index material (L, refractive index n_L) is described by the sequence HLHLHLHLHLH or even more condensed by $(HL)^5H$. The QWOT stack is the fundamental design for dielectric high reflecting mirrors and represents the basis for a variety of functional coatings in optical thin-film technology. By applying the matrix method, an approximate expression for the reflectance R_S at the design wavelength can be derived for such a stack:

$$R_S \approx 1 - 4n_0 n_T \frac{n_L^{2N}}{n_H^{2(N+1)}} \qquad [12]$$

This expression is only valid for a large number N of QWOT layers and underlines the role of the materials for the practical production of optical coatings. Highest reflectivity with lowest number of layers can be achieved only by selecting materials with a high contrast of their refractive indices. This contrast also influences the spectral broadness of the high-reflecting region of the stack (Figure 3).

Besides highly reflecting mirrors, antireflective coatings are another important class of functional coatings for modern optics and laser technology. Antireflective coatings often involve non-QWOT layer structures of more than two materials in order to accomplish the demands of lowest residual reflectivity for a broad spectral range. Eye glasses with antireflective coatings covering the entire visible spectral range can be considered as a prominent example for consumer optics, which impose requirements on the coatings also in respect to their stability against cleaning and other environmental influences during normal use. In this context, the introduction of optical plastic materials is an additional challenge in consumer optics and ophthalmology, which has to be mastered by adapted designs and production processes. In contrast to the typical demands of consumer optics, antireflective coatings on laser windows are



Figure 3 Spectra calculated for high-reflecting QWOT stacks (15 layers, substrate index $n_T = 1.52$) composed of a low-index material ($n_L = 1.46$) and different materials with high indices of refraction varying between $n_H = 1.7$ (solid), 1.9 (dashed), 2.1 (dotted) and 2.3 (dash-dotted). The spectral broadness and the reflectivity increase with the ratio n_H/n_L.



Figure 4 Spectrum of an antireflective coating for the wavelength 1.064 μm, which is designed as a V-coating with two layers of Ta_2O_5 ($n_H = 2.03$; $d_H = 0.383$ QWOT) and SiO_2 ($n_L = 1.46$; $d_L = 1.308$ QWOT) for a quartz substrate (substrate index $n_T = 1.46$).



Figure 5 Boat evaporation source in operation. The deposition material is put into the boat which is made of a metal with high melting point. A high electric current is conducted through the boat for heating to temperatures up to 2000 °C.



Figure 6 Outline of a modern box coater used for the production of optical coatings with e-beam deposition processes.

often restricted to one wavelength, but have to fulfill extreme requirements with respect to optical losses and power handling capability. Therefore, most antireflective coatings in laser technology are composed only of two thin layers to minimize the total thickness, which is often a direct measure of the expected losses of the layer system. With such a coating, which is often called V-coating according to its spectral characteristic (Figure 4), the reflectivity of the window surface can be suppressed ideally for one wavelength.

Production of Optical Coatings

The industrial production of optical coatings started in the 1940s on the basis of glass bell jar systems equipped with diffusion pumps and boat evaporators for the deposition of single layers of metals for mirrors and fluoride materials for antireflective coatings. Metal containers are used as boat evaporation sources. These containers are filled with the deposition material and heated by electric currents up to several 100 A (Figure 5). In the course of the rapid improvement of vacuum systems and especially the development of the electron beam evaporator over the next three decades, new materials with improved optical and mechanical quality could be combined to form more complicated dielectric coating systems. The layout of an e-beam deposition plant of these times, which can still be considered as fundamental for the advanced deposition systems of today, is illustrated in Figure 6. In such a box coater, the substrates are installed in a calotte which is rotated to achieve a uniform distribution of the layer thickness. The deposition materials are put in water-cooled crucibles and are subjected to an electron beam operated at currents in the range between 0.1 A to more than 10 A and voltage levels of several kilovolts. As a consequence of the interaction with the energetic electrons, the deposition material can be heated to high temperatures above 5000 K allowing the evaporation of most of the desired deposition materials. These achievable high temperatures in conjunction with the good controllability are the major advantages of e-beam sources (Figure 7) in comparison with the classical boat evaporation process. In particular, e-beam evaporation opened the way for the deposition of oxide materials and other optical materials with high evaporation temperatures, which exhibit optical properties as well as a high mechanical and chemical stability superior to the material classes accessible with boat evaporation. However, the cost efficient boat evaporation technique is still applied today for the deposition of metals or temperature-sensitive materials for coating systems in the vacuum ultraviolet (VUV)/UV and mid-infrared (MIR) spectral ranges. If the shutter above the deposition source is opened, the evaporated material reaches the substrates and forms the layer by condensation. This condensation process is sensitively dependent on the environmental conditions of the substrates and the deposition sources. Sufficient microstructural properties of the growing layer can generally be achieved only under fine vacuum below 100 Pa and heating of the substrates to temperatures in the range of some 100 °C. Even under well-optimized conditions, the typical microstructure of such thermally evaporated coatings exhibits specific deficiencies (Figure 8) which influence the optical and mechanical properties of the layer systems. Often, microcrystallites with diameters in the range of a few nm are observed, which are arranged in columns of a typical size growing from the substrate interface to the outer surface of the layer. For a simulation of the growing mechanisms for this low energetic deposition process, uncomplicated models with a few input parameters already lead to satisfactory results. Assuming a kinetic energy of 0.1–0.3 eV, which is typical for thermal evaporation according to the Boltzmann distribution, the impinging atoms can move only a small distance or even adhere directly at their position of incidence on the growing layer. As a consequence of this small mobility, the atoms are not able to reach their energetically optimum positions in the layer, and they even obstruct the path of the following atoms by shadowing. On the basis of these assumptions, computer simulations of the growing process result in structures which are comparable to the columnar growth observed in practice. The packing density of such a columnar structure is significantly below the bulk values of the corresponding deposition materials, and it contains also a high number of defects and voids, which reduce the optical quality of the coating. In particular, the coating tends to



Figure 7 Electron beam source in operation. The deposition material is put in a water-cooled crucible and subjected to an e-beam. Since the zone heated by the e-beam is entirely embedded in the surrounding deposition material, very low contamination levels and temperatures above 5000 °C can be achieved. For the generation of the e-beam an arrangement similar to the system of a cathode ray tube is employed: the electrons emitted by a hot filament are focused by an aperture and accelerated by a high voltage.



Figure 8 Microstructure of a MgF_2 single layer (geometric thickness approximately 780 nm) deposited by conventional boat evaporation. For the preparation of the TEM picture, the coating has been fractured and replicated.

adsorb water from the normal atmospheric environment into its internal structure leading to a shift of the spectral characteristics as a function of the ambient conditions. Besides this loss of spectral stability, the adsorbed water also induces an increased optical absorption of the coatings in the VUV and the MIR spectral ranges.

The increasing demand in laser technology and other optical applications for coatings far exceeds the quality level of conventionally deposited coatings and this was the driving force for the development of advanced concepts for the production of optical coatings during the last three decades. Considering the fundamental growth mechanism of conventional optical coatings, two basic approaches for an improvement of the microstructure are available. On one hand, the mobility of the atoms on the surface of the growing layer can be increased by the insertion of additional energy from other sources. This concept leads to the development of ion-assisted deposition processes, where the additional energy is transferred to the adatoms by collisions with ions generated directly in the plant by an ion source at energy levels of approximately 30–300 eV (Figure 9). Especially, by the deposition of oxide materials, which can be assisted directly with oxygen ions for balancing their stoichiometry, coating systems with high environmental stability and low optical losses can be achieved for the VIS up to the MIR spectral range. On the other hand, the energy of the adatoms can be directly increased in sputter processes which deliver deposition energies orders of magnitude higher than the thermal energy range. Besides adapted activated reactive magnetron sputter processes, particularly ion beam sputtering (IBS) was developed for a coating process delivering high-end coatings mainly for laser technology with an unsurpassed optical quality (Figure 10). For example, mirrors with total losses below one ppm can be produced for the Nd:YAG laser (wavelength 1.064 μm) with adapted IBS processes.

In addition to stable deposition processes, precise control of the layer thickness with an accuracy below 1 nm is a further important step towards the realization of complex optical coatings. Most deposition plants are equipped with quartz crystal monitors, which measure the optical thickness on the basis of the resonance frequency shift of an oscillating quartz crystal induced by the increase in mass of the deposited coating. The relative accuracy of these monitors ranges from 2% to 10% and is well suited for the regulation of the deposition rate. In order to achieve the required precision for high-quality coatings, optical monitors are often employed, which record the transmittance of the growing layer system at a single wavelength or even in a broad spectral range. Since these systems account directly for the optical properties of the deposited layer system, an efficient and accurate control of the film thickness is possible allowing the production of extremely sensitive filters with bandwidths below 1 nm for telecommunications or mirrors with defined group delay dispersion for fs-laser systems (Figure 11).



Figure 9 Ion assisted deposition. An additional ion source is installed, which delivers inert or reactive ions impinging on the growing layer. The energy transfer from the ions to the adatoms results in improved microstructure of the produced coatings with higher packing density.



Figure 10 Principle of the ion beam sputtering (IBS) process. Inert ions with an energy in the range 1–2 KeV are generated in an ion source and directed onto the target which consists of the desired deposition material. Material is sputtered from the target and reaches the substrates. As a consequence of the high energy of the adatoms (5–30 eV) the formed layer exhibits a superior microstructure.

Quality Parameters of Optical Coatings

Besides the spectral characteristics, a variety of specific parameters has to be considered for each application of optical coating systems (Table 1). For laser systems the laser-induced damage threshold and the optical losses have to be evaluated in the context of technical and also economic requirements. Absorption is a loss channel, which transforms a fraction of the impinging radiation energy into heat, inducing a temperature increase in the coating. This generated temperature profile influences the imaging properties of the optical component via thermal expansion and temperature-induced alterations of the refractive indices of the coating as well as the substrate materials. Despite numerous technical problems, absorption always implies the loss of laser energy which is produced with high economic expense. Absorption losses are related to defects and impurities, which are introduced during the production process into the layer by a variety of contamination mechanisms. Furthermore, an unbalanced stoichiometry with a higher metal content is often observed as a cause for increased absorption in dielectric optical coatings, which are mainly composed of binary metal compounds. Absorptance values of optical components are determined by laser calorimetric techniques described in ISO 11551. In this measurement scheme, the temperature increase in the sample is monitored during irradiation with a well-characterized laser beam. After this heating phase, the laser beam is blocked and the temperature curve during the cool-down cycle is also recorded. On the basis of the measured temperature development, the absorptance can be calculated taking into account the laser power and the heat capacity of the specimen.

All mechanisms, which deflect radiation from its specular direction, contribute to optical scattering representing the second major loss channel in optical coatings. Since scatter losses are mainly attributed to microstructural imperfections and the surface roughness of the layers, a scaling with wavelength can be deduced from the corresponding theoretical models. Especially in the VUV/UV spectral range, high scatter values are apparent and may dominate the losses of the optical components. For longer wavelengths, the contribution of scattering is decreased to a point in the MIR spectral range where it can be neglected in comparison to the absorption losses. Scatter effects



Figure 11 Example of a complicated layer system deposited under the control of an advanced optical broadband monitoring device: double chirped mirror (56 non-QWOT layers of SiO_2/TiO_2). Only small deviations between the calculated spectrum and the spectrum of the produced coating can be observed.

Table 1 Selected quality parameters of optical coatings and surfaces in conjunction with corresponding ISO standards and measurement principles

Specification	*Parameter/Unit*		*Standard/Measurement principle*
Laser induced damage threshold (LIDT)	cw-LIDT	W/cm	ISO 11254-1: cw-laser irradiation
	1 on 1-LIDT	J/cm^2	ISO 11254-1: irradiation with single pulses
	S on 1-LIDT	J/cm^2	ISO 11254-2: repetitive irradiation with pulses
	Assurance	J/cm^2	DIS 11254-3: irradiation sequence
Optical losses	Absorptance	ppm	ISO 11551: laser calorimetry
	Total scattering	ppm	ISO 13696: integration of scattered radiation
Transfer function	Reflectance	%	CD 13697: precise laser ratiometric method
	Transmittance	%	DIS 15368: spectrophotometry
Surface quality	Scratch/Digs		ISO 10110: 13 parts containing different types of imperfections
	Roughness		
Stability	Abrasion		ISO 9211: different test methods
	Environmental Stability		ISO 9022: 21 parts containing a variety of conditioning methods

may impair the imaging properties or the resolution, and they reduce the efficiency of an optical system. Besides the economic aspect of each loss effect, scattering can also be considered as relevant for safety in high-power laser systems, where some 100 ppm of scattered radiation carry enough power to injure or blind the operator. In the ISO 13696 standard, measurement procedures based on the collection or integration of the total radiation scattered by the sample are described.

Depending on their application, coatings have to withstand also manifold mechanical, chemical, and environmental influences. Severe mechanical and chemical requirements are imposed onto coatings for ophthalmology or consumer optics, which are often cleaned with abrasive and aggressive cleaning solvents and tissues. To qualify coatings for these applications, various testing procedures have been developed and are routinely employed in industrial quality management. Coatings for laser systems and precision optics are predominantly certified according to conditioning methods described in the ISO standard series 9211. Test procedures with respect to environmental influences are extensively outlined in the more than 20 parts of ISO 9022, which is dedicated to a variety of climatic, mechanical, and chemical conditioning cycles.

Summary and Outlook

Optical coatings are the major tool for engineering the properties of functional optical surfaces for an extensive spectrum of applications. On the basis of the matrix algorithm, a comprehensive theoretical model for the spectral transfer characteristics of optical coatings is available, which has been transferred to commercial computer programs. Now, most design problems can be solved with these computer codes, whereas the reproducible and precise production of optical coatings with high quality could only be partially achieved until today (Table 2). Besides conventional thermal processes, new ion-assisted deposition processes and sputtering concepts are gaining importance in optical thin-film technology. For the quality management of optical coatings, a variety of often standardized testing procedures has been developed during the last two decades including the determination of the power handling capability, the measurement of the optical losses and a broad spectrum of conditioning methods for optical coatings.

Demanding future challenges will be imposed on optical coatings by the development of semiconductor lithography in the EUV spectral range to achieve nodes well below 100 nm in chip production. Another important trend is directed by new laser applications in material processing, medicine and communication technology, operating at extremely high repetition rates and power levels, or with ultrashort pulses in the fs-regime. Other requirements will be defined by the rapid development of optical technology towards a broad range of special products with short innovation cycles obligating significant progresses in thin-film technology in the direction towards flexible and reproducible process concepts

Table 2 Selected quality parameters of optical coating systems for laser applications

Laser, wavelength	*Type*	*Absorption ISO 11551*	*Total scattering ISO 13696*	*Laser induced damage threshold, ISO 11254*
157 nm, F_2 excimer	HR/th		1–4%	
193 nm, ArF excimer	AR/th	0.7–2.5%	0.2–0.5%	1–2 J/cm^2 (1on1, 20 ns)
	HR/th	0.4–2.0%	0.2–2.5%	2–4 J/cm^2 (1on1, 20 ns)
248 nm, KrF excimer	AR/th		<0.025%	10 J/cm^2 (1on1, 30 ns)
	HR/th	<500 ppm	<0.2%	>20 J/cm^2 (1on1, 30 ns)
	HR/IB		<0.1%	>3 J/cm^2 (1on1, 30 ns)
633 nm, HeNe laser	HR/th	<30 ppm	<30 ppm	–
	HR/IB	<5 ppm	<5 ppm	–
1.064 μm, Nd:YAG	AR/th	<20 ppm	<100 ppm	>60 J/cm^2 (12 ns, 0.25 mm)
	HR/th	<50 ppm	<100 ppm	>100 J/cm^2 (12 ns, 0.25 mm)
	HR/IB	<1 ppm	<1 ppm	>80 J/cm^2 (12 ns, 0.25 mm)
10.6 μm, CO_2 laser	AR/th	<0.16%	–	>20 J/cm^2 (100 ns, 1.4 mm) >2 kJ/cm^2 (1.2 ms, 250 μm) >3 kW/mm (cw, 100 μm)
	HR/th	<0.10%	–	>25 J/cm^2 (100 ns, 1.4 mm) >2 kJ/cm^2 (1.2 ms, 250 μm)

Types: HR: highly reflecting mirror; AR: antireflective coating; th: thermal evaporation; IB: ion beam sputtering.

for coatings with increasing complexity. In all fields of modern optics, optical thin films will represent an enabling technology which will play a key role for many future applications and products.

List of Units and Nomenclature

A_0	amplitude of partial wave of order zero
A_1	amplitude of first-order partial wave
A_k	amplitude of the partial wave of order k
d_i	thickness of layer number i
D_i	film thickness expressed in units of QWOT
E_0	amplitude of a plane wave
E_i, H_i	electric field strength and magnetic field strength at the rear front of layer number i
IAD	ion-assisted deposition
IBS	ion beam sputtering
k	wavenumber of a plane wave $k = 2\pi/\lambda$
M_i	matrix of layer number i
M_S	composite matrix of a layer stack of K single layers
n_0	index of refraction of the ambient medium
n_H	refractive index of a high-index material
n_i	refractive index of layer number i
n_L	refractive index of a low-index material
n_T	refractive index of the substrate
QWOT	quarter wave optical thickness: unit for the thickness of the layer
r_1, r_1'	reflection coefficients of the ambient–layer interface
r_2	reflection coefficient at the layer–substrate interface
r_S	reflection coefficient of a single layer
r_{SK}	reflection coefficient of a layer stack of K single layers
R_S	reflectance of a QWOT stack
t_1, t_1'	transmission coefficients of the ambient–layer interface
δ_i	phase shift of a plane wave in layer number i
λ	wavelength of a plane wave
λ_Z	design wavelength
θ_i	angle of incidence in layer number i
ω	frequency of a plane wave

See also

Optical Coatings: Laser Damage in Thin Film Coatings.

Further Reading

Guenther AH (ed.) (2002) *International Trends in Applied Optics*. Bellingham, Washington: SPIE Press.

ISO 11551 (1997) *Test Method for Absorptance of Optical Laser Components*. International Organization for Standardization.

ISO 13696 (2002) *Test Method for Radiation Scattered by Optical Components*. International Organization for Standardization.

ISO 9022 (1996, 1997) *Optics and Optical Instruments – Environmental Test Methods – Parts 1–21*. International Organization for Standardization.

ISO 9211 (1994–2001) *Optical Coatings, Parts 1–4*. International Organization for Standardization.

ISO/FDIS 15368 (2003) *Measurement of Reflectance of Plane Surfaces and Transmittance of Plane Parallel Elements*. International Organization for Standardization.

Jacobson MR (1989) *Deposition of Optical Coatings*. SPIE Milestone Series, Volume MS 6. Bellingham, Washington: SPIE Press.

Kaiser N and Pulker HK (2003) *Optical Interference Coatings*. Berlin: Springer.

Liddell HM (1980) *Computer-Aided Techniques for the Design of Multilayer Filters*. Bristol, UK: Adam Hilger.

Macleod HA (2001) *Thin Film Optical Filters*. Bristol, UK: Institute of Physics Publishing.

Rancourt JD (1996) *Optical Thin Films*. Bellingham, Washington: SPIE Press.

Thelen A (1988) *Design of Optical Interference Coatings*. New York: McGraw-Hill.

X-Ray Coatings

P Dhez, Université Paris Sud, Orsay, France

© 2005, Elsevier Ltd. All Rights Reserved.

In all spectral ranges, there exist two principal options for coating an optical element. This may be a simple layer, as for example a metallic layer is frequently used in the visible spectral region. The second option is to use a multilayer coating, making use of the optical properties of two or more materials to achieve enhanced reflectivity over a limited spectral range. In both cases, a knowledge of the refractive index of the materials (real or complex) is required, and of course one must choose materials that can be coated in a practical deposition process. A frequent side-advantage of coating is to make it possible to choose the material of the substrate for its mechanical or cooling properties without regard to the optical properties of the coatings.

Originally (at the beginning of the twentieth century) the progress of X-ray optics was hampered by a poor understanding of the nature of these rays, and in particular by the observation that they are very weakly reflected and refracted. After the electromagnetic nature of these rays had been confirmed, the problem of producing polished surfaces that were sufficiently smooth on an atomic scale to reflect X-rays still remained. Optical coatings gave little hope of improvement due to the growth of roughness during the coating process. Thus early attempts to make X-ray mirrors produced poor results and little progress was made until the 1960s. However, in the past 30 years, much technical progress has been made, and now many optical principles used in the visible spectral region have been extended to very short wavelengths. Even refractive and diffractive focusing lenses (not treated here) have been implemented in the X-ray region.

In the first section we outline the history of the discovery of the properties of X-rays, which were achieved mainly in experiments using crystals. This allows us to understand how their electromagnetic nature was discovered, and how they interact with materials. We then describe the phenomenon of the 'total reflection' of X-rays, which occurs only at very high angles of incidence ('grazing incidence') and its main applications in X-ray optics. Finally, we outline the principles of mirrors based on interference, their applications in the X-ray region, their advantages and their limitations.

X-rays Compared to the Other Electromagnetic Spectral Regions

Infrared radiation was discovered by W. Herschel in 1800, and ultraviolet rays by J. Ritter in 1801. These were the only 'invisible rays' known before Maxwell's contribution to the understanding of the electromagnetic spectra through the development of his equations in 1869. The discovery of radio waves by H. Hertz in 1887 confirmed that our eyes are blind to most of the electromagnetic spectrum.

In 1895, W. Roentgen discovered some previously unknown 'rays' that had the surprising property of being able to penetrate low-density material opaque to visible light. This discovery was a side-effect of his studies of low-pressure electrical discharges, fashionable at the time. The nature of these unknown or 'X'-rays as Roentgen named them, remained unknown for 12 years or so. Were they electromagnetic waves or particles? Roentgen used lenses, prisms and mirrors to try to detect a reflective, refractive or focusing effect, with inconclusive results. Although the electromagnetic nature of the X-rays was favored, the magnitude of the frequency or the refractive index was unknown. We note that natural radioactivity and gamma rays were discovered a year after X-rays, and the same questions concerning their nature were raised. However, in neither case did the ignorance of the nature of the radiation impede their use in medical radiography or in cancer therapy.

In 1906, the experiments of C. Barkla provided the first evidence of the electromagnetic nature of X-rays. In scattering X-rays from blocks of a light element (in this case, carbon), he was able to show that the scattered radiation was polarized, and therefore had the nature of a transverse wave. This kind of experiment had been performed almost a century previously to demonstrate the transverse wave nature of visible light. In 1916, following a suggestion by M. von Laue that X-rays might be diffracted from a grating of period comparable to their wavelength, Friedrich and Knipping succeeded in diffracting X-rays from the atomic planes of a natural crystal. This experiment established definitively the electromagnetic nature of X-rays and also the scale of their wavelength.

In 1915 W. L. Bragg summarized the diffraction rules for crystals through his equation [1], now known as the simplified Bragg law:

$$2d_i \sin\theta_i = N\lambda_i \qquad [1]$$

This equation relates the diffracted X-rays wavelength λ_i to a set of parallel atomic planes separated by a distance d_i and to the incidence angle θ_i. N is an integer indicating the order of diffraction, as in the grating equation. In using this equation, care is needed because of two peculiarities compared to the usual mirror or grating equations in the visible range. In the Bragg equation, the angle of incidence θ is measured from a given atomic plane to the incident rays. However, inside a crystal several different atomic planes exists, not only the planes parallel to the surface as indicated in Figure 1. In addition, θ is not measured from the normal as is usual in optics; hence the angle θ is referred to as the glancing or grazing angle of incidence.

We note that the Bragg equation is not restricted to X-rays, but is a coherent scattering phenomenon which is common to all cases where waves, such as



Figure 1 The geometry for the conditions leading to selective reflection on a periodic medium.

sound waves or ripples on water, are diffracted by regular arrays of scattering centers.

In order to visualize the phenomena, we refer to Figure 1 which is a schematic representation of a plane wave incident upon a two-dimensional array of scattering centers (electrons around nucleus, in the case of X-rays), shown here as dots. As the sine function has a maximum value of 1, the maximum wavelength λ that can be reflected from a spacing d is given by $\lambda = 2d_{\text{max}}$. As the largest value of $2d$ that can be found in natural crystals is about 2 nm (in natural muscovite mica, for example), X-rays of 2 nm, with an equivalent energy of about 620 eV, are the 'softest' (least energetic) that can be reflected in this manner.

The model shown in Figure 1, similar to that proposed by M. von Laue, does not take into account the detailed interaction of the atoms with the X-rays, and therefore ignores effects such as absorption and refraction, and discrete atomic transitions. A.H. Compton attempted the first treatment of the interaction of matter with X-rays from an atomic viewpoint. In 1917, he developed a classical theory in which the electrons bound to the nucleus are treated as harmonic oscillators. In this way, he was able to derive an expression for the atomic scattering coefficients and to describe resonance effects at frequencies corresponding to specific atomic transitions. A few years later, he was able to establish a link between these 'atomic scattering factors' and the macroscopic concept of refractive index. This new formulation allowed the use of the Fresnel equations, widely used in other spectral regions, to calculate the intensity of X-rays reflected from smooth, polished surfaces. These surfaces may be amorphous as well as crystalline.

The refractive index can be written in several ways; since it is close to unity over the X-ray range, the most common form is complex:

$$n = 1 - \delta - i\beta \qquad [2]$$

where δ is the refractive index decrement, and the imaginary part β the absorption index. For photon energies corresponding to X-rays, both have small negative values, typically 10^{-3}–10^{-6}, and are correcting factors to the vacuum index 1. As in other photon energy ranges, the absorption and the refraction coefficient variations are linked through the Kramers–Krönig relations. In the visible range the index values are usually larger than 1, being below 1 only around specific optical thresholds. In the UV region, the index values become smaller than unity at energies above about 30 eV, which corresponds to the energy range for which atoms can be ionized.

At an early stage, Roentgen demonstrated X-ray absorption by sheets of materials. The demonstration of refraction took much longer and was more difficult. The first direct X-ray refraction index measurement was achieved in 1924, using a prism and an X-ray tube. Figure 2 is the scheme of the experiment, which is easy to perform in the visible range to measure the refraction of a transparent material. The footprint of the direct beam on the photographic plate is made before inserting the prism. In the visible range for which $n > 1$, the beam is refracted at larger angle than the glancing incidence angle, and so below the direct beam direction as shown in Figure 2a. At the contrary, as indicated in Figure 2b, the X-ray beam is refracted toward the prism surface and such an experiment effectively demonstrated that the index was slightly inferior to unity, as suggested by A.H. Compton. We will return



Figure 2 The geometry of the experiment used to evaluate the magnitude and the sign of the refractive index in the X-ray and the visible ranges.

to this peculiarity in the following section, when the total reflection phenomenon is described.

More details about the successive steps in our understanding and the pioneering works on X-rays can be found in standard textbooks.

Total Reflection X-Ray Mirrors

Using Fresnel's equations and tabulated values of the refractive index one can verify that, on any material, grazing incidence is necessary to reflect X-rays. Reflectivity calculations over the range from EUV to X-rays (30 eV to 10 keV), with approximations to allow calculations for rough surfaces, can be carried out using the web site of the Center for X-ray Optics of Lawrence Berkeley Laboratory http://www-cxro.lbl.gov, and curves similar to those presented below can be reproduced.

In the case of normal incidence, Fresnel's equation indicates that for any material the X-ray reflectivity $R^2 = |(n-1)/(n+1)|^2$ is very low, typically below 10^{-4}. This is a direct consequence of the X-ray index values, which are close to unity, as mentioned above.

In the visible range, normal incidence reflectivity from the surface of a transparent medium is low but can be increased just by going to glancing incidence. This is also the case in the X-ray region but in addition as the real part of the X-ray refractive index is lower than that of the vacuum, we have an 'external' total reflection phenomenon. From Figure 2 one can see how, for a sufficiently small incidence angle, the refracted wave becomes parallel to the interface. This is well known in the visible range (in which case it is the 'internal' reflection) and the phenomenon is used, for example, in fiber optics.

Figure 3 shows examples of calculated reflectivity variations versus grazing incidence angles, for perfectly smooth glass (SiO_2), nickel, and platinum surfaces. Curves are drawn for the 8 keV energy photons, corresponding to the Cu Kα line produced by conventional X-ray tubes. One observes that for this energy the reflectivity is low beyond a grazing angle around 1°, then rises quickly at low angles. This is typical of the total reflection phenomenon. The grazing angle corresponding to a 50% reflectivity is called the critical angle Θ_c, its value being roughly proportional to the refractive index decrement at the relevant photon energy. Notice that weaker absorption materials, lower Z, lead to more abrupt reflectivity variation but with smaller critical angles.

Such reflectivity variations at grazing incidence were systematically studied with X-ray tubes as early as the 1930s. The penetration depth of X-rays at grazing incidence was also studied. The evanescent wave inside the material, under total reflection conditions, is confined to a surface layer of a few tens of wavelengths. Hence, in the total reflection of X-rays, a coating having a thickness of a few tenths of a micron, on any substrate, is all that is required.

Figure 4 shows examples of the variation in nickel reflectivity calculated over the energy range 0.3–10 keV, for several grazing incidence angles. Nickel is one of the coatings commonly used for X-ray mirrors. The abrupt reflectivity variations and the dips correspond to the energies of the nickel atomic thresholds L (0.85 keV) and K (7.5 keV) for which the index tables predict a rapid change in absorption and refraction coefficients. Choosing an incidence angle provides a practical way of limiting the reflected spectral range. The energy cut-off of the



Figure 3 Examples of calculated reflectivity variations versus the incidence angle in the case of 8 keV X-rays on perfect platinum, nickel and glass surfaces.



Figure 4 Calculated reflectivity variations versus photon energy, on a perfect nickel surface, for different incidence angles.

X-ray mirror acts as a filter for the higher-energy photons. That is effectively the method of suppressing the short wavelengths from an incident spectrum if they are not desired in an experiment.

When using highly divergent sources such as X-ray tubes, the restriction to operation at grazing incidence leads to a strong limitation of the collected solid angle, and thus of the beam size and angular aperture. These constraints are less stringent on highly collimated beams emitted by synchrotron sources. Thus, most synchrotron beam lines use total reflection optics in the form of curved mirrors, to refocus the beams and remove the undesired high X-ray energies. Recently, X-ray imaging optics, consisting of a series of parabolic and hyperbolic nested grazing incidence mirrors to increase the collected aperture, have been launched on satellites.

The reflectivity curves in Figures 3 and 4 are calculated for perfect surfaces. Real surfaces, even polished surfaces, have roughness created by defects over a large and continuous range of spatial frequencies, ranging from several centimeters down to the atomic scale. Coating a surface replicates the large period defects. Eventually new defects are added at near-atomic scale by nucleation of the coating material. Interferometric methods have been developed to study the range of defects from centimeter to micron spatial periods, whereas the atomic force microscope (AFM) is able to measure roughness from the micron down to the 0.1 nm scale. As waves are scattered most efficiently by asperities of a size comparable to their wavelength, scattering measurements are used in the X-ray region to probe defects of atomic scale. The prevalence of scattering explains why mirrors that reflect well in the visible range were disappointing when used in early X-ray experiments. The recent development of adaptive polishing methods has almost solved this problem.

The main effect of scattering by an optical system is not to decrease the number of photons coming out, but to modify their angular distribution. Scattering measurements are experimentally studied to test and evaluate the spatial defect distribution. In X-rays, one first characterizes the incident beam angular distribution in measuring its angular variation intensity after a scanning slit. Performing the same measurement after the optic, across the reflected beam in the case of mirrors, provides the modified angular distribution. From such a measurement, a few theoretical models adapted to the X-ray range can be used to deduce the mirror spatial defect distribution and so to check progress in polishing methods. The simplest model, coming from early crystal studies, is describing defects by a single parameter named roughness and denoted σ. Figure 5 shows an example of calculated reflectivity; on nickel surfaces versus photon energy and for increasing roughness; it shows how many photons have deviated from the symmetrical direction. Corresponding angular distributions can also be calculated.



Figure 5 Calculated reflectivity variations versus photon energy, on nickel surfaces having different roughness, for different incidence angles.

The coating systems used for X-ray mirrors are material dependent. Deposition methods are similar to those used for visible optics coatings, but specific effort has been devoted to avoid nucleation growth to achieve uniform smooth layers. In general, one tries to give the evaporated particles, ions or clusters a kinetic energy lying within a specific range, which promotes mobility on the surface but is below the energy needed for implantation. In the case of electron beam deposition the energy distribution is thermal, but an auxiliary ionic bombardment can be used during deposition to provide the necessary energy to the previously deposited atomic layer (ion assisted deposition). For each material, the specific sputtering deposition and ionic bombardment conditions need to be carefully studied.

Until the 1970s, Bragg reflection by crystals and the total reflection phenomenon was the only way to reflect X-rays.

Multilayer X-Ray Mirrors

In the visible range, optics are frequently coated with stacks of dielectric multilayers obtained by periodic deposition of layers of two amorphous transparent materials. Such stacks are highly selective reflectors, or bandpass filters. They operate on the principle of constructive interference between all the waves partially reflected by the successive interfaces. They can be regarded as analogous to two-dimensional Bragg reflectors, in which the interfaces play the same role as atomic planes in crystals. Hence the Bragg equation [1] can be applied, the relevant period *d* being the thickness of an individual bilayer, if the stack is truly periodic.

The concept of using artificially deposited stacks of thin films, of alternating high and low electron density, to reflect and diffract X-rays dates back at least to the 1920s. It was not until 1944, however, that DuMond and Youtz were able to demonstrate significant X-ray reflection from such an artificially layered structure. Their work used alternating layers of copper and gold, laid down by evaporation. Unfortunately these materials diffuse into one another, reducing the electron density contrast and hence the X-ray reflectivity. In 1967 Dinklage and Frerichs succeeded in making a structure of alternating layers of iron and magnesium, which do not interdiffuse quickly, and thus produced the first stable X-ray reflecting multilayer.

Since then, enormous progress has been made in the fabrication and application of such multilayer reflectors, principally because of the efforts of two pioneers. Troy Barbee, while at Stanford University, developed open loop sputtering methods for controlling the thickness of the many thin (~nm) layers required to make up such a stack, while Eberhard Spiller at IBM developed an evaporation method using *in situ* X-ray monitoring to achieve similar thickness control. Almost all of the many multilayer deposition systems in use around the world are based on one of these two methods.

As for the total reflection mirror, only recent progress in methods for deposition and controls has made this new kind of X-ray optics practical. Present applications range from the extreme ultra violet (30 eV) region to hard X-rays having energies of a few tens of keV.

Prediction of the reflectivity variations can be simulated by calculations on the same web site mentioned in the preceding section. Multilayer mirrors are based on interference, so the reflectivity coefficient and the width of the reflected bandpass are determined by the amount of absorption inside the stack and the partial reflectivity at each interface. The more efficient pairs of materials have the lowest X-ray absorption and the highest refractive index difference at the required energy. The selection of real materials is constrained by the coating conditions and the need to achieve smooth interfaces. In particular, a low interdiffusion coefficient between the successive material pairs is a requirement for temporal stability. Epitaxial deposition methods have been considered but no useful pair of materials has yet been found.

An example of a flourishing application is multilayer-coated normal incidence X-ray optics. Optical schemes used in the visible region for telescopes and microscopes have excellent optical performance and high numerical aperture but a very low reflectivity in the X-ray region if coated with a single layer. However, if coated with multilayers they can be used, providing that extremely low-roughness surfaces can be produced. The interface qualities of the deposited thin layers presently limit normal incidence optics to the soft X-ray energy range, typically below 300 eV so around the carbon edge. This corresponds to periods of about 2 nm, or a few atomic layers, and the resulting roughness seriously decreases the reflectivity.

Figure 6 is a reflectivity curve versus energy for a quasinormal incidence Mo/Si multilayer mirror optimized to get the first-order peak at 93 nm. On Mo/Si mirrors, precise control of the layer period and the quality of the interfaces allow the manufacture of mirrors with reflectivity only a few percent below the theoretical limit shown here. Considerable effort has been invested in such mirrors, with a view to applications to EUV projection lithography.

It is possible to build polarizer mirrors over the soft X-ray range. An incidence angle of 45° corresponds to the Brewster angle, because the X-ray index is close to unity. X-ray multilayer and semitransparent selective beam splitters now permit the development of Michelson interferometers for newly developed soft X-ray lasers.

Figure 7 is an example of a tungsten/carbon (W/C) reflectivity curve for a multilayer adapted to the 8 keV energy of Cu Kα, mentioned before. The curve



Figure 6 Calculated reflectivity versus incidence angle for a typical Mo/Si multilayer, optimized around 93 eV, under quasi-normal incidence.



Figure 7 Calculated reflectivity versus incidence angle for a typical W/C multilayer adapted to reflect 8 keV photons.

of reflectivity versus glancing angle has been calculated from the total reflection range to the second-order peak. This kind of multilayer is being used in X-ray tubes to premonochromatize the beam and make it parallel. In such an application, the period of the coating is continuously graded laterally to satisfy locally the Bragg law at each point of the curved mirror.

As a final example of the new possibilities offered by X-ray multilayers, we mention the possibility of widening the reflected bandpass by varying continuously the period from the bottom to the top of the deposited stack. This is the equivalent of multilayer neutron 'supermirrors'. Such interference mirrors are usable at quite high X-ray energies, and give high reflectivity and a larger incidence angle than total reflection mirrors working over the same energy range.

The continuous fast development of coating technologies and X-ray multilayer applications can be followed through the proceedings of dedicated meetings at, for example, on a web site like http://PXRM.

Summary and Perspectives

After the discovery of X-rays in 1895, almost 25 years were necessary to understand their characteristics compared to the visible range. Only in 1923 did F. Holweck and R.A. Millikan demonstrate the continuity of electromagnetic radiation from X-rays to ultraviolet. The selective Bragg reflection by natural crystals is limited to energy commonly larger than about 2 keV photons. Below this energy the total reflection mirror was the only optical device to reflect and focus wavelengths shorter than the far UV until the development of adapted interferential mirrors.

During the 1960s, the EUV and X-UV ranges gained interest due to the spread of fusion research and in the astrophysics community studying the Sun and stars. For both communities, the continuum and the lines emitted at short wavelengths by ionized matter were a convenient tool to evaluate high plasma temperatures. At about the same time, the development of synchrotron radiation sources increased the need for X-ray optics. In addition, this last source offered the possibility to attempt new optical solutions with convenient intense and parallel beams from UV to X-rays. Finally, the concomitant progress in various microtechnologies afforded the necessary tools to produce new adapted optical devices for short wavelengths. At the present time, adapted optics are under development to take advantage of various applications from microscopy to interferometry over the very large electromagnetic energy X-ray range.

As a matter of fact, it is now possible to tailor a choice of mirror coatings adapted to each X-ray photon energy and application. Such coatings are specific because they must be optimized to take into account the inevitable absorption energy dependence.

Progress achieved in blank polishing and evaporation methods has led to efficient and high-quality X-ray mirrors even able to keep the spatial coherence of synchrotron sources. Such technological advances are also steps to master surfaces and interfaces at the atomic scale. They are now becoming applicable to the other spectral ranges and to various micro- and nanotechnologies.

List of Units and Nomenclature

Crystal period	d	[nm]	1 nm = 10^{-9} m
Incidence Angle	Θ	[degree]	
Photon Energy	E	[eV]	$(h/2\pi)\omega.\lambda = hc =$ 1239.842 eV.nm
Wavelength	λ	[nm]	1 nm = 10^{-9} m

See also

Diffraction: Fresnel Diffraction. **Geometrical Optics:** Lenses and Mirrors. **Incoherent Sources:** Synchrotrons. **Optical Coatings:** Thin-film Optical Coatings.

Further Reading

Attwood D (1999) *Soft X-Rays and Extreme Ultraviolet Radiation*. Cambridge: Cambridge University Press.

Ditchburn RW (1963) *Light*. Appendix XIX, 2nd edn. London: Blackie.
Hecht E (1998) *Optics*, 3rd edn. Reading, MA: Addison-Wesley.
Henke BL, Gullikson EM and Davies JC (1993) *Atomic Data and Nuclear Data Tables* 54: 181.
James RW (1982) *The Optical Principles of the Diffraction of X-Rays*. Woodbridge, CT: Ox Bow Press.
Michette A and Pfauntsch S (1997) *X-Rays: The First Hundred Years*. New York: John Wiley.
Mould RF (1993) *A Century of X-Rays and Radioactivity in Medicine*. Bristol, UK: Institute of Physics Publishing.
Paratt LG (1954) Surfaces studies of solids by total reflection of x-rays. *Physical Review* 95: 359.
Spiller E (1972) Low-loss reflection coatings using absorbing materials. *Applied Physics Letters* 20(9): 365–367.
Underwood JH and Attwood DT (1984) The renaissance of x-rays optics. *Physics Today, April*: 44–51.

OPTICAL COMMUNICATION SYSTEMS

Contents

Basic Concepts
Historical Development
Architectures of Optical Fiber Communication Systems
Free Space Optical Communications
Lightwave Transmitters
Local Area Networks
Optical Time Division Multiplexing
Wavelength Division Multiplexing

Basic Concepts

S Lee and A E Willner, University of Southern California, Los Angeles, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Since modern lightwave communication started in the 1970s, extensive efforts have been made to increase data rate and transmission distance. Recently, the bit rates for single-channel and multichannel systems have exceeded 40 and 2 Tb/s on single fibers respectively, for transoceanic distances. One revolutionary development in lightwave systems has been the deployment of erbium doped fiber amplifiers (EDFAs). These amplifiers facilitate transmission of an optical signal over long distances, by providing periodic analog-like amplification rather than digital-like regeneration. The wide bandwidth provided by EDFAs has made possible the increased use of wavelength division multiplexing (WDM) in which multiple lightwave signals, each having a different wavelength, are co-propagated on a single fiber. EDFAs and WDM techniques can enhance the lightwave system capacity, both in terms of obtainable transmission distance, and total number of data rates (see Figure 1).



Figure 1 Bit rate product. Data from T. Li (private communication).

Optical Fiber

Most telecommunication fibers are made of silica, therefore following the attenuation of silica material. Figure 2 shows the silica fiber attenuation as a function of wavelength. The downward slope towards 1.6 μm and upward slope away from 1.6 μm, are the theoretical limits due to Rayleigh scattering and absorption of silica material, respectively. The absorption peak near 1.4 μm is due to water molecule absorption. There are two low attenuation regions: ~1.3 μm and 1.55 μm, both of which are used for communications in general, and some other wavelengths are also used for shorter distance communications. Figure 2 also shows the comparison between gain bandwidth of EDFA (~3 THz) and the low attenuation window around 1.55 μm (~25 THz). The typical values of attenuation at 1.3 μm and 1.55 μm for single-mode fiber (SMF) are ~0.35 dB/km, and 0.2 dB/km, respectively.

When an electromagnetic wave interacts with the bound electrons of a silica fiber, the medium response depends upon optical frequency (ω). This property, referred to as material dispersion, manifests itself through the frequency dependence of the refractive index $n(\omega)$. Fiber material dispersion plays a critical role in propagation of short optical pulses since different spectral components associated with the pulse travel at different speeds, given by $c/n(\omega)$. Consequently, the optical pulse at the output of the fiber is broadened in time. The commonly used system parameter is called the dispersion parameter D (the negative D value is called normal dispersion, and the positive D value is called anomalous dispersion), and is measured in ps/(nm·km); D for SMF is ~+ 17 ps/(nm · km) at 1.5 μm. However, because of dielectric waveguiding, the effective mode index is slightly lower than the material index $n(\omega)$, with the reduction itself being ω-dependent (waveguide dispersion). This results in a waveguide contribution that must be added to the material contribution to obtain the total dispersion (see Figure 3).



Figure 2 Silica fiber attenuation versus wavelength.

Generally, the waveguide contribution to dispersion D is to shift zero dispersion wavelength (λ_0) to longer wavelengths. Furthermore, the waveguiding can be tailored to shift the λ_0 from 1.3 μm to 1.5 μm, the wavelength at which the fiber has the minimum attenuation loss. The fiber having λ_0 in the neighborhood of 1.5 μm, is called dispersion-shifted fiber (DSF); D for DSF is usually between −2.5 and +2.5 ps/nm·km, at a wavelength of 1.5 μm. The typical dispersion parameter, D, as a function of a wavelength for both SMF and DSF, is shown in Figure 4.



Figure 3 Total dispersion (D) and contribution of material dispersion and waveguide dispersion in conventional SMF.



Figure 4 Dispersion versus wavelength for conventional SMF and DSF.

In addition to chromatic dispersion, optical fiber has another dispersion properties related to polarization. An optical wave of arbitrary polarization can be represented as the superposition of two orthogonally polarized modes. In an ideal fiber, these two modes are indistinguishable, and have the same propagation constants owing to the cylindrical symmetry of the waveguide. However, in real fibers there is some residual anisotropy due to unintentional circular asymmetry, usually caused by noncircular waveguide geometry or asymmetrical stress around the core, as shown in Figure 5.

In either case, the loss of circular symmetry gives rise to two distinct orthogonally-polarized modes with different propagation constants (differential phase velocity) responsible for polarization mode dispersion (PMD) in the fiber, and can be related to the difference in refractive indices (birefringence) between the two orthogonal polarization axes. The differential phase velocity indicated is accompanied by a difference in the group velocities for the two polarization modes, therefore the pulse at the end of the transmission fiber is broadened by this differential group delay (DGD). DGD is usually expressed in units of ps/km for a short length (1 m to 1 km) of birefringent fiber. However, DGD does not accumulate along a long fiber link in a linear fashion. Instead, because of random variations in the perturbations along a fiber span, the DGD in one section may either add to or subtract from another section of the fiber. As a result, average DGD in long fiber spans accumulates in a random-walk-like process that leads to a square root of transmission-length dependence. Therefore, average DGD is expressed in ps/km$^{1/2}$ in long fiber spans, referred to as the PMD of the fiber, and the typical PMD parameter has a value of 0.01 to 10 ps/km$^{1/2}$. Because of the many perturbations that act on a real-world fiber (e.g., temperature, vibration, etc.), transmission properties typically vary with time. Therefore, the PMD of the fiber link fluctuates randomly, thus causing random fluctuations in system performance.



Figure 5 Origin of PMD.

It is well known that optical fibers show nonlinear behavior under conditions of high power and long interaction length. The power-times-distance products for amplified transmission systems can be large enough to make fiber nonlinear effects the dominant factor in the design of long-distance systems.

There are two categories of fundamental optical nonlinear effects: stimulated scattering effects and refractive index effects. Stimulated scattering effects arise from parametric interactions between light and acoustic or optical phonons in the fiber. Two nonlinear effects fall into this category: stimulated Brillouin scattering (SBS) and stimulated Raman scattering (SRS). The main difference between the two is that optical phonons participate in SRS, while acoustic phonons participate in SBS. In a simple quantum-mechanical picture, a photon of the incident field is annihilated to create a photon at a longer wavelength. The new photon is co-propagated and counter-propagated along the original signal in SRS, while counter-propagated in SBS. Refractive index effects are caused by modulation due to changes in light intensity. There are three types of refractive index effects: self-phase modulation (SPM), cross-phase modulation (XPM), and four-wave mixing (FWM). SPM introduces the change of optical phase by its own intensity, and, this leads to frequency chirp of the pulse, depending on the relative position from the peak. When this nonlinear frequency chirp interacts with the fiber dispersion, the pulse either broadens or compresses, depending on the sign and the amount of dispersion along the fiber. In XPM, the phase of the signal in one wavelength channel is modulated by the intensity fluctuation of the other wavelength channels. In a WDM system, XPM imposes far more damaging effects than SPM because XPM is stronger by a factor of two than SPM when the channel power is the same, and large number of WDM channels can contribute to XPM. FWM is the generation of modulation sideband at new frequencies, due to the phase modulation of channels between lights at different frequencies in multichannel system. FWM causes penalties in a WDM system if the newly generated frequency is either equal to or close to the frequency of existing WDM channels.

Fiber nonlinearities impose significant degradation in optical transmission system, and limit the system on allowable number of channels, channel power, and channel spacing (see Figure 6). But, the effects can be well suppressed by carefully designing the fiber dispersion profile (i.e., dispersion map) in the transmission system, and controlling the optical launch power for each fiber span.



$\lambda = 1.55\,\mu\text{m}$, $\alpha = 0.2$ dB/km, $\Delta f = 10$ GHz

(a)

10 x 2.5 Gb/s Channels, 1 mW/ch, L = 2 Mm

(b)

Figure 6 Limitation due to fiber nonlinearities in (a) maximum channel power and number of channels, and (b) channel spacing and dispersion. Reproduced with permission from Chraplyvy AR (1990) Limitation on lightwave communications imposed by optical-fiber nonlinearities. *IEEE Journal of Lightwave Technology* 8:1548–1557. Copyright © 1990 IEEE.



Figure 7 (a) EOM: MZ interferometer on LiNbO2, (b) operation of EOM; constructive and destructive interference resulting in intensity modulation.

Communication Components

Distributed feedback laser (DFB) is widely used as a light source for metro, long-haul, and undersea applications, due to its narrow spectral width, and wavelength stability. Fabry–Perot (FP) lasers, and vertical cavity surface emitting lasers (VCSEL) are used for local area networks (LAN), and for access applications, because these are cheaper than DFB lasers. For an application, where the cost is the most important parameter with low data modulation speed, light-emitting diode (LED) is used as a light source.

In optical data modulation, the simplest and easiest technique is turning ON or OFF the laser, depending on the binary logic ‘1’ or ‘0’ (direct modulation). This type of modulation is simple and cheap compared to external modulation technique. But, its application is limited by the bandwidth of modulation, and the induced frequency chirp (i.e., difference in optical frequency at the turn ON state and just before the turn OFF state of laser) that limits the transmission distance. Two different types of external modulators are widely used for digital optical data transmission. Electro absorption modulator (EAM) uses the Franz–Keldysh effect, where it is observed that the wavelength of the optical absorption edge in a semiconductor is lengthened by applying an electric field. Electro-optic modulator (EOM) utilizes the linear electro-optic effect, called the Pokels effect, which changes the refractive index of the material caused by and proportional to an applied electric field, so therefore changes the phase of the optical signal. This phase change is used to modulate the intensity of a lightwave through a Mach–Zehnder (MZ) interferometer (see Figure 7). Because the Pockels effect exists only in crystal, lithium niobate crystal ($LiNbO_2$) or electro-optic polymers are used for EOM.

EDFA is a wideband optical amplifier that has merits in that: (i) erbium ions (Er^{3+}) emit light in the 1.55 μm loss-minimum band of optical fiber, (ii) a circular fiber-based amplifier is inherently compatible with a fiber optics system; (iii) it provides



Figure 8 Energy level and transition diagram of EDFA. Reproduced with permission from Willner AE (1997) Mining the optical bandwidth for a terabit per second. *IEEE Spectrum* Apr.: 32–41. Copyright © 1997 IEEE.

amplification independent of bit-rate, modulation format, power, and wavelength; and (iv) it has low distortion and low noise during amplification. EDFA contains a gain medium (i.e., erbium-doped fiber) that must be inverted by a pump source. A signal initiates stimulated emission, resulting in gain, and spontaneous emission occurs naturally, which results in noise.

Figure 8 shows the energy level and transition diagram of EDFA. A 0.98 μm pump photon is absorbed and excites a carrier (Er^{3+} ions) into higher excited states, and the excited carrier decays rapidly to the first excited state that has a very long lifetime of ~10 ms (metastable state). In contrast, a 1.48 μm pump photon is absorbed and excites a carrier into a metastable state. This long metastable state is one of the key advantages of EDFA, and intersymbol distortion and interchannel crosstalk are negligible as a result of these slow dynamics. Depending on the external optical excitation signal, this carrier will decay in a stimulated or spontaneous fashion to the ground state and emit a photon. Both absorption and emission spectra have an associated bandwidth depending on the spread in wavelengths that can be absorbed or emitted from a given energy level. This is highly desirable because (i) a pump laser does not need to be an exact wavelength; and (ii) the signal may be at one of several wavelengths, especially in a WDM system. Figure 9 shows the bandwidth in the 1.48 μm absorption and 1.55 μm fluorescence spectrum of a typical erbium-doped amplifier.

When the noise characteristics of EDFA are considered, noise figure (NF) is an important parameter, which is defined by $NF \equiv SNR_{in}/SNR_{out}$, where SNR_{in} (SNR_{out}) is the electrical equivalent signal-to-noise ratio (SNR) of the optical wave going into (coming out) of the amplifier, if it were be detected. The typical value of NF in commercially-available EDFA is 4.5–6 dB. The importance of NF in optical communication systems is presented later in this chapter, when the required optical SNR (OSNR) for error-free optical data transmission is considered. Figure 10 shows an example of EDFA diagram.



Figure 9 The absorption and fluorescence spectra for erbium near 1.5 μm. Reproduced with permission from Miniscalco WJ (1991) Erbium-doped glasses for fiber amplifiers at 1550 nm. *IEEE Journal of Lightwave Technology* 9: 234–250. Copyright © 1991 IEEE.



Figure 10 Typical EDFA diagram.

Recent development of EDFA in longer wavelength regimes or L-band (1570–1620 nm) has doubled the useful transmission bandwidth over the conventional band or C-band (1525–1265 nm). L-band gain of EDFA is generally achieved by proper arrangement of pump lasers through longer lengths of erbium-doped fiber than conventional C-band EDFA. Figure 11a shows the concept of wideband EDFA. The incoming



Figure 11 Wide band EDFA. Reproduced with permission from Yanada M (1997) *Electronics Letters*. Copyright © 1997 IEEE.



Figure 12 Block diagram of functions performed in advanced receiver packages.

WDM signal is split into two bands (C- and L-bands), amplified separately, and combined at the output. Gain and NF characteristics of this wideband EDFA is shown at Figure 11b.

Because SRS transfers the energy of a lower wavelength channel into the higher wavelength channel in the optical fiber, the transmission fiber itself can be used as a gain medium on specific channel (or channels) when the proper pump signal (or signals) are provided in the fiber. Even though Raman gain is much lower than the gain of EDFA (i.e., <0.1 dB gain/mW pump in Raman amplifier (RA) compared to a few dB gain/mW pump in EDFA), RA has several advantages over EDFA (i) RA has the capability to provide gain at any signal wavelengths, (ii) the amplification window is expandable by combining multipump wavelengths; and (iii) RA offers improved noise performance because the signal is amplified over transmission fiber (i.e., distributed amplifier). Especially improved noise performance increases system OSNR, which can be used to extend system reach or create more wavelength channels on the system. The Raman pumps are typically located ~100 nm shorter than the wavelength of the signal to be amplified, and a few 100s mW pump lasers are used to get a 10–15 dB gain.

In general, telecom receiver (RCVR) consists of photo diode (PD) with transimpedence amplifier (TIA), followed by limiting amplifier (LA) or automatic gain control amplifier (AGC), low pass filter, and clock data recovery circuit (CDR) (see Figure 12).

Vertically illuminated positive-intrinsic-negative (PIN) photodiode and avalanche photo diode (APD) are the most common PD that is used in RCVR. In PIN, incoming light is absorbed in the n^- (low doped or intrinsic) region and generates an electron-hole pair, which drifts to a depletion region and collected n^+ and p^+ regions, therefore generating electric current. APD is used for high-sensitivity detection up to 10 Gb/s. It is structured as absorption, grading, and multiplication layers. The multiplication layer of APD provides additional transit time delay compared to PIN, therefore the bandwidth of APD is smaller than PIN in general. TIA is a broadband low noise amplifier that is used to convert and amplify the weak current from PD to the desired output voltage. A low pass filter is used to suppress the noise and data distortion from high frequency components with a typical cut-off frequency ~0.7 bitrate. LA and AGC are amplifiers that limit the output voltage as a constant. LA is a nonlinear amplifier that makes a decision either to make logic ‘1’ or ‘0’ based on input voltage level, and limits output voltage as fixed values. AGC is a linear amplifier that limits the output voltage by adjusting the gain of the amplifier based on input voltage level. CDR consists of a phase lock loop (PLL) with a voltage controlled oscillator (VCO)



Figure 13 Amplitude modulation (a) nonreturn-to-zero (NRZ), and (b) return-to-zero (RZ).

and data flip-flop circuit. The PLL is used to synchronize the VCO to the incoming high-speed bit stream, therefore recovering the system clock. The recovered clock is used in D-FF to retime and regenerate the data.

Data Modulation Formats

In digital optical communications, numerous modulation formats have been developed and utilized, in order to achieve higher spectral efficiency (i.e., ratio of individual channel bit rate to dense WDM (DWDM) separation), and to improve system performance over fiber impairments. A simple amplitude modulation of lightwave is still the most widely used method for optical communication. The easiest amplitude modulation technique is to using a nonreturn-to-zero (NRZ) format. Figure 13a shows an example of NRZ binary sequence in time domain, and the corresponding frequency domain spectrum. In NRZ, data '1' and '0' correspond to the ON and OFF state of a lightwave transmitter, respectively, occupying entire bit time (i.e., binary symbol time). When the ON or OFF state of a lightwave transmitter does not occupy the entire bit time (T_B) (i.e., when the data pulse duration (T_d) is less then (T_B), it is called the return-to-zero (RZ). Figure 13b shows a binary sequence of RZ, and its frequency spectrum when $T_d \approx 0.5\ T_B$. The Fourier transform of the square wave is the Sinc function. Therefore, the frequency spectrum of an ideal NRZ and RZ follows the pattern of a Sinc square function. Note that the first null of frequency spectrum of RZ is about twice as high as the null of NRZ.

Even though NRZ is better in spectral efficiency than RZ, RZ has an advantage over NRZ in tolerance of fiber impairments. Figure 14 shows an example on eye closure penalty comparison between NRZ and RZ data formats at a 16-channel WDM system at 40 Gb/s data rate. It is clearly seen that the penalty of RZ is much less severe than the penalty of NRZ, as the transmission distance increases. (Note, nonlinearities and dispersion increases as the transmission distance increases.)



Figure 14 System performance of different modulation format (NRZ vs. RZ).

There has been much effort to increase the spectral efficiency, to improve the system performance over fiber impairments, or to achieve both simultaneously. Figure 15 shows some of examples of these. Chirped RZ (CRZ) is the modulation format inducing frequency chirp on conventional RZ. CRZ is robust on fiber impairment at the cost of losing spectral efficiency. In carrier-suppressed RZ (CS-RZ), a strong un-modulated optical carrier is removed from conventional RZ, therefore suppressing the nonlinear effects. Duo-binary is a three-level signal modulation format generated by a series of delay and added


Data
Clock
Clock
LD
Intensity modulator
Intensity modulator
Phase modulator
Output optical pulses (Clock)
Optical spectrum
M-Z output
V_{bias}
V_π
time
time
f_{clock}
f_{clock}
Driving signal (Clock)
Frequency
(a)
Data
Clock/2
Clock
LD
Intensity modulator
Intensity modulator
Phase modulator
Output optical pulses (Clock)
Optical spectrum
M-Z output
V_π
time
time
f_{clock}
Driving signal (Clock/2)
Frequency
(b)
Generation of duobinary signal
Binary
a_k
Ex-OR
$b_k = a_k + b_{k-1}$
T
T
Duobinary
$c_k = b_k + b_{k-1}$
Binary input a_k
1
0
Coding
Duobinary output c_k
2
1
0
(c)
Data
Clock
Optical filter
LD
Intensity modulator
Intensity modulator
VSB Filtering
(d)

Figure 15 Examples of bandwidth efficient modulation formats. (a) Chirped RZ (CRZ) generation, (b) carrier suppressed-RZ (CS-RZ) generation, (c) duo-binary generation, and (d) vestigial single side band (VSB) RZ generation.

circuits in the transmitter. The advantage of duo-binary is that its bandwidth is reduced to one half of conventional NRZ, therefore having enhanced spectral efficiency, and has a high tolerance in chromatic dispersion, and suppression of fiber nonlinearites.

Single-sideband (SSB) or vestigial singleside band (VSB) can be generated into either NRZ or RZ, by either optically utilizing optical filtering with a sharp cut-off filter, or electrically applying tapped-delay-line filter approximation on both amplitude and phase modulators. SSB (or VSB) has about a two times higher spectral efficiency and higher tolerance on chromatic dispersion than conventional modulation formats.

Data Multiplexing

At their most basic, optical networks can imitate electrical networks in which time division multiplexing (TDM) is overwhelmingly used for digital data transmission. A fiber can carry many time-multiplexed channels, in which each channel can transmit its data in an assigned time slot. A typical TDM link is shown in Figure 16, in which N transmitters are sequentially polled by a fast multiplexer to transmit their data. The time-multiplexed data are sequentially and rapidly demultiplexed at the receiving node.


$T_M = \frac{T_0}{\text{\# of TDM signals}}$
... 1 1 0 0 1 1 ...
Tx 1 ... 1 0 ...
Tx 2 ... 1 1 ...
Tx 3 ... 0 1 ...
T_0
t
T_M
High-BW fiber
High-speed mux
High-speed demux
... 1 0 ... Rx 1
... 1 1 ... Rx 2
... 0 1 ... Rx 3

Figure 16 Concept of bit-interleaving TDM.

Time multiplexing and demultiplexing functions can be performed either electrically with an electrical time (DE)MUX switch and an optical transmitter/receiver, or optically with multiple optical transmitters/receivers and an optical time (DE)MUX switch. The major advantage of TDM is that there is no output–port contention problem (each data bit occupies its own time slot and there is only a single high-speed signal present at any given instant). The disadvantage of TDM is that the scheme requires a ultra-high-speed switching component if the individual signals are themselves high-speed and if there are many users.

In WDM, multiple wavelength channels are transmitted through a single fiber, therefore enabling the fiber to carry more throughput. By using wavelength-selective devices for the ON and OFF ramps, independent signal routing also can be accomplished. Figure 17a shows a simple point-to-point WDM system in which several channels are multiplexed at one node, the combined signals transmitted across a distance of fiber, and the channels demultiplexed at a destination node. As shown in Figure 17b, the wavelength becomes the signature address for either the transmitter or the receivers, and the wavelength will determine the routing path through an optical network.

Many interesting challenges face the eventual implementation of WDM systems and networks. Several of these challenges involve the control and management of the data through this novel high-speed network. Figure 18 shows a small subset of critical component technologies typically required for a WDM system, including multiple-wavelength transmitters, multiport star couplers, passive and active wavelength routers, EDFAs, and tunable optical filters.

Some generic goals that a WDM-device technologist aims to achieve include; large wavelength tuning range; multi-user capability; wavelength selectivity and repeatability; low cross-talk; high extinction ratio; minimum excess losses; fast wavelength tunability; high-speed modulation bandwidth; low residual chirp; high finesse; low noise; robustness; high yield; potential low cost. Depending on system requirements, device availability and cost, WDM technologies divide into two; course-WDM (CWDM) and dense-WDM DWDM. Figure 19 shows the wavelength allocation for CWDM and


λ_1 λ_2 ... λ_n
λ
Tx's
λ_1
λ_2
λ_n
λ-MUX
λ-DEMUX
Rx's
Wavelength multiplexer
Wavelength demultiplexer
(a)
1
λ_3
N
User node
Optical network
4
λ_4
2
3
Wavelength-determined routing
(b)

Figure 17 (a) A simple point-to-point WDM transmission system; (b) a generic multiuser network in which the communication links and routing paths are determined by the wavelengths used within the optical switching fabric.


Multi-wavelength transmitter
Isolator
Optical amplifier
N X N STAR
Active or passive wavelength router
Rx
Tunable optical filter

Figure 18 Schematic of a small subset of enabling device technologies for a WDM system.


CWDM Grid (1310–1610 nm)
20 nm
DWDM 100 GHz Grid (1492.25–1611.79 nm)
100 GHz (~0.08 nm)
1300
1350
1500
1550
1600
λ

Figure 19 WDM wavelength allocation.

DWDM. CWDM technology uses an International Telecommunication Union (ITU) standard 20 nm spacing between the wavelengths from 1310 nm to 1610 nm. Also DWDM technology uses an ITU standard 100 GHz or 200 GHz between wavelengths, arranged in several bands at around 1500–1600 nm.

Dispersion Management and Compensation

As mentioned previously, chromatic dispersion is one of the most basic characteristics of fiber, although it is possible to manufacture fiber that induces zero chromatic dispersion. But such fiber is incompatible with the deployment of a WDM system since harmful nonlinear effects are generated, therefore chromatic dispersion must exist, and must be compensated for. The effect of chromatic dispersion is cumulative and increases quadratically with the data rate (see Figure 20).

The quadratic dependence of dispersion with the data rate is a result of two effects. First, a doubling of the data rate will double the Fourier-transformed frequency spectrum of the signal, thereby doubling the effect of dispersion. Second, the same doubling of the data rate makes the data pulse only half as long in time and therefore twice as sensitive to temporal spreading due to dispersion. The conventional wisdom for the maximum distance over which data can be transmitted is to consider a broadening of the pulse equal to the bit time period. For a bit period B, a dispersion value D and a spectral width $\Delta\lambda$, the dispersion-limited distance is given by $L_D = 1/(D{\cdot}B{\cdot}\Delta\lambda)$ (see Figure 21).

In theory, compensation of chromatic dispersion for high-speed or long-distance systems can be fixed in value if each link's dispersion value is known. A simple yet elegant solution is to create a dispersion 'map', in which the designer of a transmission link alternates elements that produce positive and then negative dispersion (see Figure 22). This is a very powerful concept: at each point along the fiber the dispersion has some nonzero value, effectively


No distortion of output bit stream
2.5 Gbit/s
Optical fiber
Distance = 0 km
100 km
Large distortion of output bit stream
10 Gbit/s
Optical fiber
Distance = 0 km
100 km

Figure 20 Pulse broadening at two different data rates (2.5 Gbit/s, and 10 Gbit/s) as a result of quadratic nature of chromatic dispersion.



Figure 21 Dispersion-limited (uncompensated) transmission distance in single-mode fiber (SMF) as a function of data rate for intensity-modulated optical signals. Courtesy of L.D. Garrett.


Positive dispersion transmission fiber
Negative dispersion element
–D
–D
–D
Dispersion (ps/nm)
+D
–D
+D
–D
+D
–D
D_{total}= 0
Distance (km)

Figure 22 Typical static management of chromatic dispersion.



Figure 23 Effect of tunable compensation at 40 Gb/s (OC-768); it allows a wide range of transmission distance. On the contrary, the 80 km fixed compensator allows only small range of transmission around 80 km.

eliminating FWM and XPM, but the total accumulated dispersion at the end of the fiber link is zero, so that minimal pulse broadening is induced. The specific system design, as to the periodicity of management, depends on several variables, but a typical number for SMF as the embedded base is a compensation at every 80 km in a 10 Gb/s system. Dispersion-compensating fiber (DCF) has been generally used as a dispersion compensating element.

However, there are several important aspects of optical systems and networks that make tunable dispersion compensation solutions attractive, including: (i) it significantly reduces the inventory of different required types of compensation modules; (ii) it tunes to adapt to routing path changes in a reconfigurable network, (iii) it tracks dynamic changes in dispersion due to environment, and (iv) it achieves a high degree of accuracy necessary for 40 Gb/s channels (see Figure 23).

One brute-force method to achieve tunable dispersion compensation is to build a module with optical switches used to add or remove sections of fixed DCF to achieve a discrete set of dispersion compensation. Many other elegant, yet viable, approaches have been developed for tunable dispersion compensation, and these approaches include linearly chirped FBG with nonuniform heating, nonlinearly chirped Fiber Bragg grating (FBG) with a simple mechanical stretcher, virtually imaged phase array, electronic tap delay filter with weights, multiple stage all pass filter, etc.

System Performance Parameters

An eye diagram provides a simple and useful tool to visualize intersymbol interference between data bits. Figure 24a shows a perfect eye diagram. A square bit stream (i.e., series of symbol '1's and '0's) is sliced into sub-bit stream with predetermined eye intervals (i.e., several bit periods), and displayed through bit analyzing equipment (e.g., digital channel analyzer), overlapping the sliced sub-bit stream in order to obtain the eye diagram. When a perfect transmitter and receiver (i.e., infinite receiver bandwidth with zero noise characteristics and jitter), and a perfect transmission media (i.e., no dispersion and nonlinearites) are used, the received eye diagram is shaped as a perfect rectangular. In reality, the transmitter and receiver have a limited bandwidth with noise and jitter, and the transmission media (i.e., optical fiber) has dispersion and nonlinearites. Therefore, the eye diagram deviates from the perfect rectangular shape. Figure 24b shows the eye diagram close to a real situation. The shape of the eye is generally broadened and distorted (i.e., eye is closed) due to limited bandwidth and fiber impairments, and noise and timing jitter are added onto this broadened and distorted eye shape.

The Q-factor (q) is also an important system parameter widely used in long-distance optical transmission system design. It is defined as the electrical signal-to-noise ratio before the decision circuit at receiver. The Q-factor is directly related to bit-error-rate (BER: the percentage of bits that has an error relative to total number of bits received in a specific time) by: $\mathrm{BER} = 0.5\cdot\mathrm{erfc}(q/2^{0.5})$, where $\mathrm{erfc}(x)$ is the complementary error function. The Q-factor is an unitless linear ratio, and is express in dB by $20\cdot\log(q)$. As a conventional relationship, Q-factor of 15.6 dB (i.e., linear ratio 6) is required to achieve $\mathrm{BER} = 10^{-9}$. Figure 25 shows the relationship of eye diagram, Q-factor, and BER.



Figure 24 (a) A perfect square eye diagram, (b) a closed eye diagram due to bandwidth, fiber impairments, noise, and timing jitter.



Figure 25 The relationship of eye diagram, Q-factor, and BER ($\mu1$, $\mu2$: mean levels of logic '1' and '0', $\sigma1$, $\sigma2$: standard deviation of logic '1' and '0').



Figure 26 BER curve and power penalty.

Power penalty (PP) is one of the most important system parameters, and is defined as the received optical power difference in dB with and without signal impairments at a specified BER (conventionally 10^{-9}), from measured BER versus optical power curve. Therefore, 1 dB PP means that a system with signal impairments requires 1 dB more optical power at the receiver in order to achieve the same BER performance compared to the system without signal impairments. Figure 26 shows the typical BER curve as a function of received optical power and PP. Note that PP reduces from ~3.5 dB to ~1 dB with dispersion compensation.

In long-haul and undersea transmission system with many EDFA chains, OSNR is an important system parameter to design and characterize the optical transport system. OSNR is defined as the ratio of the power of signal channel to the power of ASE in a specified optical bandwidth (conventionally 0.1 nm). The OSNR (in dB) of a signal channel at the end of the system is approximated by: $\text{OSNR (dB)} = 58 + P_{\text{out}} - L_{\text{span}} - \text{NF} - 10\log(N_{\text{amp}})$, when the system has N_{amp} fiber spans, span loss L_{span} (in dB) followed by an optical amplifier with output power P_{out} (in dBm) per channel launched into the span and noise figure (NF) (in dB). As an example, a typical OSNR requirement for $\text{BER} = 10^{-9}$ is about 17 dB at 10 Gb/s data rate. The required OSNR should be increased by 6 dB when the data rate is increased by a factor of 4. Improving the amplifier's NF can increase OSNR, and the improved OSNR can be used to increase the system reach, reducing the channel power in order to suppress the nonlinearities, etc.

See also

Fiber and Guided Wave Optics: Light Propagation. **Imaging:** Multiplex Imaging. **Optical Amplifiers:** Erbrium Doped Fiber Amplifiers for Lightwave Systems. **Optical Communication Systems:** Wavelength Division Multiplexing.

Further Reading

Leonid K, Sergio B and Alan W (1996) *Optical Fiber Communication Systems*. Norwood, MA: Artech House Inc.

Govind PA (1995) *Nonlinear Fiber Optics*. San Diego, CA: Academic Press.

Emmanuel D (1994) *Erbium-Doped Fiber Amplifiers*. New York: Wiley.

Ivan K and Tingye L (2002) *Optical Fiber Telecommunications IV A Components*. San Diego, CA: Academic Press.

Ivan K and Tingye L (2002) *Optical Fiber Telecommunications IV B Systems and Impairments*. San Diego, CA: Academic Press.

Historical Development

G Keiser, PhotonicsComm Solutions, Inc., Newton Center, MA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

This article describes the development of optical fiber communication systems. After describing some of the motivations for using optical fiber communications and the advantages of this technology, the key milestones and the principal people involved in developing optical fibers and compatible light sources are presented. Following this, the article looks at the evolution of fielded systems and the use of optical fiber links in undersea applications.

One of the principal needs of people since antiquity has been to communicate. This need created interests in devising communication systems for sending messages from one distant place to another. Many forms of such systems have appeared over the years. The basic motivations behind each new one were either to improve the transmission fidelity, to increase the data rate so that more information could be sent, or to increase the transmission distance between relay stations. Prior to the nineteenth century, all communication systems operated at a very low information rate and involved only optical or acoustical means, such as signal lamps or horns. One of the earliest known optical transmission links, for example, was the use of a fire signal by the Greeks in the eighth century BC for sending alarms, calls for help, or announcements of special events.

The invention of the telegraph by Samuel FB Morse in 1838 ushered in the era of electrical communications. In the ensuing years an increasingly larger portion of the electromagnetic spectrum, shown in Figure 1, was utilized for the conveying of information from one place to another. The reason for this trend is that, in electrical systems, the data usually are transferred over the communication channel by superimposing the information onto a sinusoidally varying electromagnetic wave, which is known as the carrier. When reaching its destination the information is removed from the carrier wave and processed as desired. Since the amount of information that can be transmitted is related directly to the frequency range over which the carrier operates, increasing the carrier frequency theoretically increases the available transmission bandwidth and, consequently, provides a larger information capacity. Thus the trend in electrical communication system developments was to employ progressively higher frequencies (shorter wavelengths), which offer corresponding increases in bandwidth or information capacity. This activity led to the birth of communication mechanisms such as radio, television, microwave, and satellite links.

Another important portion of the electromagnetic spectrum encompasses the optical region shown in Figure 1. In contrast to electrical communications, transmission of information in an optical format is carried out, not by frequency modulation of the carrier but by varying the intensity of the optical power. Similar to the radio-frequency spectrum, two classes of transmission medium can be used: an atmospheric channel or a guided-wave channel. Whereas transmission of optical signals through the atmosphere was done thousands of years ago, the use of a guided-wave optical channel such as an optical fiber is a fairly recent application.

Fiber optic communication systems have a number of inherent advantages over their copper-based and radio-transmission counterparts. Fiber optic cable can transmit at a higher capacity, thereby reducing the number of physical lines and the amount of equipment needed for a given transmission span. The lower weight and smaller size of optical fibers offer a distinct advantage over heavy, bulky copper cables in crowded underground cable ducts, in ceiling-mounted cable trays, and in mobile platforms such as aircraft and ships. Their dielectric composition is an especially important feature of optical fibers, since this ensures freedom from electromagnetic interference between adjacent fibers, eliminates ground loops, and results in extremely low fiber-to-fiber crosstalk. In addition, an optical fiber affords a high degree of data security since the optical signal is well confined within the optical waveguide.

Optical Fiber Development

Since an atmospheric channel requires a line-of-sight link and because it can be adversely affected by weather conditions, a guided-wave channel is the preferred approach in most cases for communication system applications. A challenge in using an optical fiber channel is to have a flexible, low-loss medium that transfers the optical signal over long distances



Figure 1 Electromagnetic spectrum for electrical and optical communications.

without significant attenuation and distortion. Glass is an obvious material for such applications. The earliest known glass was made around 2500 BC and glass already was drawn into fibers during the time of the Roman Empire. However, such glasses have very high attenuations and thus are not suitable for communication applications. One of the first known attempts of using optical fibers for communication purposes was a demonstration in 1930 by Heinrich Lamm of image transmission through a short bundle of optical fibers for potential medical imaging. However, no further work was done beyond the demonstration phase since the technology for producing reasonably low-loss fibers with good light confinement was not yet mature.

Further work and experiments continued on using optical fibers for image transmission and by 1960 glass-clad fibers had attenuations of about one decibel per meter. This attenuation allowed fibers to be used for medical imaging, but it was still much too high for communications. Optical fibers had attracted the attention of researchers at that time, because they were analogous in theory to plastic dielectric waveguides used in certain microwave applications. In 1961, Elias Snitzer demonstrated this similarity by drawing fibers with cores so small they carried light in only one waveguide mode. He published a classic theoretical description of single-mode fibers in May 1961. However, to be useful for communication systems, optical fibers would need to have a loss of no more than 10 or 20 decibels per kilometer.

As a reminder, decibels measure the ratio of the output power to the input power on a logarithmic scale. The abbreviation for a decibel is 'dB.' The power ratio in decibels is given by the expression '10 log (power out/power in).' As an example, a power loss of 20 dB over a 1-km distance in an optical fiber means that only 1% of the light injected into the fiber comes out of the other end. Table 1 gives some typical examples of various power ratios and their decibel equivalents.

In the early 1960s Charles Kao pursued the idea of using a clad glass fiber for an optical waveguide, building on optical waveguide research being done at the Standard Telecommunication Laboratories in England. After he and George Hockman painstakingly examined the transparency properties of various types of glass, Kao made a prediction, in 1966, that losses of no more than 20 dB/km were possible in optical fibers. In July 1966, Kao and Hockman presented a detailed analysis for achieving such a loss level. Kao then went on to actively advocate and promote the prospects of fiber communications, which generated interest in laboratories around the world to reduce fiber loss. It took four years to reach Kao's predicted goal of 20 dB/km, and the final solution was different from what many had expected.

Table 1 Examples of some optical power ratios and their decibel equivalents

Power ratio (P_{out}/P_{in})	*Decibel equivalent (dB)*
0.01	−20
0.10	−10
0.50	−3
1	0
2	3
10	10
100	20

To understand the process of making a fiber, consider the schematic of a typical fiber structure shown in Figure 2. A fiber consists of a solid dielectric (glass or plastic) cylinder of refractive index n_1 called the core. This is surrounded by a dielectric cladding which has a refractive index n_2, that is less than n_1, in order to achieve light guiding in the fiber. This structure is then encapsulated by a buffer coating to protect the fiber from abrasion and outside contaminants. The first step in making a fiber is to form the clear glass rod or tube called a preform. This normally is done by a vapor-phase oxidation process. The preform has two distinct regions that correspond to the core and cladding of the eventual fiber. Fibers are made from the preform by precision feeding it into a circular furnace that softens the end of the preform to the point where it can be drawn into a very thin filament which becomes the optical fiber.

Most researchers had tried to purify the compound glasses used for standard optics, which are easy to melt and draw into fibers. A different approach was taken at the Corning Glass Works where Robert Maurer, Donald Keck, and Peter Schultz started with fused silica. This material can be made extremely pure, but has a high melting point and a low refractive index. Silica has the approximate attenuation versus wavelength characteristic shown in Figure 3. Note that for early silica fibers there are regions of low attenuation around 850, 1310, and 1550 nm, which the literature refers to as the first, second, and third windows, respectively. The large attenuation spikes in the 1000- and 1400-nm spectral



Figure 2 Typical optical fiber structure.



Figure 3 Attenuation versus wavelength approximation for silica fibers.

regions are due to absorption by residual water molecules in the glass. Although ultra-pure material processing techniques can eliminate these spikes to produce what are known as full-spectrum or low-water-peak fibers, most installed fibers still have a relatively large attenuation between 1350 and 1500 nm.

Note that since the attenuation spikes no longer are present in various types of fibers, the idea of operating windows has been replaced by the concept of spectral bands. The International Telecommunications Union (ITU) has designated six spectral bands for use in intermediate-range and long-distance optical fiber communications within the 1260 to 1675-nm region. The regions, which are known by the letters O, E, S, C, L, and U, are defined as follows:

- Original Band (O-Band): 1260 to 1360 nm
- Extended Band (E-Band): 1360 to 1460 nm
- Short Band (S-Band): 1460 to 1530 nm
- Conventional Band (C-Band): 1530 to 1565 nm
- Long Band (L-Band): 1565 to 1625 nm
- Ultra-long Band (U-Band): 1625 to 1675 nm

The Corning team made cylindrical preforms by depositing purified materials from the vapor phase. To produce a fiber that has light guiding properties they carefully added controlled trace levels of titanium to the core to make its refractive index slightly higher than that of the cladding without raising the attenuation significantly. In September 1970, they announced the fabrication of single-mode fibers with an attenuation of 17dB/km at the 633-nm helium-neon line. The fibers were fragile, but independent tests at the British Post Office Research Laboratories facility in Martlesham Heath, England confirmed the low loss.

This dramatic breakthrough was the first among the many developments that opened the door to fiber optic communications. The ensuing years saw further reductions in optical fiber attenuations. By mid-1972, Maurer, Keck, and Schultz at Corning had made multimode germania-doped fibers with a 4-dB/km loss and much greater strength than the earlier brittle titania-doped fibers. In order to couple a sufficient amount of optical power into a fiber, early applications used multimode fibers with a refractive-index gradient between core and cladding of around 2% and core diameters of 50 or 62.5 micrometers.

Single-mode fibers have much smaller core diameters on the order of 9 micrometers in order to allow only one propagation mode. This type of fiber has a much higher transmission capacity since the effect of modal dispersion is eliminated. The first single-mode fibers were optimized to have a zero dispersion value at 1310 nm, since the silica material used at that time exhibited a low loss within a spectral band around this wavelength. Figure 4 shows the dispersion characteristic of this type of fiber as a function of wavelength in the S-, C-, and L-bands. As a result of its widespread use in early single-mode transmission systems, this fiber design has been standardized by the International Telecommunication Union (ITU-T) under the designation Recommendation G.652.

Standard G.652 silica fibers provide the lowest attenuation at 1550 nm, but have a much larger signal



Figure 4 Dispersion characteristics of three types of standard optical fibers.

dispersion at this wavelength than at 1310 nm. Since system designers wanted to use fibers at a 1550-nm wavelength, in order to transmit high-speed data over longer distances, fiber manufacturers overcame the larger signal dispersion limitation by creating the so-called dispersion-shifted fibers. This was done through a clever manipulation of the core and cladding designs that allowed the zero-dispersion point to shift to longer wavelengths. In particular, the ITU-T created a specification for operation at 1550 nm which is designated as recommendation G.653. Figure 4 also shows the dispersion characteristic of this type of fiber as a function of wavelength.

Although the G.652 and G.653 fibers work well for single-wavelength operation, a different type of fiber, having non-zero dispersion within a broad spectral range, is needed when implementing systems that use many independent light sources simultaneously within a particular wavelength band. This led to the specification of the non-zero dispersion shifted fiber (NZDSF) in the ITU-T Recommendation G.655 that are designated to operate around 1550 nm. The main purpose of having a positive dispersion value over the entire operating spectrum is to mitigate a nonlinear optical effect called four-wave mixing (FWM), which is analogous to intermodulation distortion in electrical systems. Figure 4 shows the dispersion characteristic of the G.655 fiber in the S-, C-, and L-bands.

Light Sources

The fiber by itself is not practical unless there is a compatible optical source for launching light signals into it. The most suitable device for this is a semiconductor light-emitting diode (LED) or a laser diode. In the 1960s, a great deal of effort took place to achieve laser action in pn-junction diodes. The early devices were GaAs and GaAsP lasers that operated at a temperature of 77 K, emitted at a wavelength around 850 nm, and had high lasing threshold current densities. To make devices that were more application-friendly by operating at room temperature, structures consisting of sandwiched layers of AlGaAs and GaAs were investigated. Finally, in 1970, researchers at Bell Laboratories and a team at the Ioffe Physical Institute in Leningrad made the first semiconductor diode lasers based on a layered AlGaAs/GaAs/AlGaAs structure that were able to emit continuous-wave light in the 850-nm region at room temperature.

Major improvements in laser diode performance and reliability followed this achievement during the next decade. In addition, around 1976, room-temperature laser diodes operating at longer wavelengths, in the 1100 to 1600-nm region, started to appear. Of particular interest were GaInAsP/InP-based laser diodes emitting in the 1310-nm and 1550-nm low-loss windows of optical fibers. The progressive development of ever-improving devices during the 1980s and 1990s, included single-frequency emission with narrow linewidths under continuous operation, low levels of chirp under direct modulation, high output power, and the ability to tune specially constructed laser diodes over a wavelength range of up to 30 nm.

Fielded Systems

The bit rate-distance product B × L, where B is the transmission bit rate and L is the repeater spacing, measures the transmission capacity of optical fiber links. Since the inception of optical fiber communications in the mid-1970s, the link transmission capacity has experienced a tenfold increase every four years. Several major technology advances spurred this growth. Among the technology developments are laser diodes emitting over an extremely narrow spectral band, optical amplifiers, fibers with low losses and low dispersions, and the concepts of wavelength division multiplexing.

Some of the initial telephone-system field trials in the USA were carried out in 1977 by GTE in Los Angeles and by AT&T in Chicago. These transmission links were largely for the trunking of telephone lines, which are digital links consisting of time-division-multiplexed 64-kb/s voice channels. Similar demonstrations were carried out in Europe and Japan. Applications ranged from 45 to 140 Mb/s with repeater spacings around 10 km.

With the advent of high-capacity fiber optic transmission lines in the 1980s, service providers established a standard signal format called synchronous optical network (SONET) in North America and synchronous digital hierarchy (SDH) in other parts of the world. These standards define a synchronous frame structure for sending multiplexed digital traffic over optical fiber trunk lines. The basic building block and first level of the SONET signal hierarchy is called the synchronous transport signal–level 1 (STS-1), which has a bit rate of 51.84 Mb/s. Higher-rate SONET signals are obtained by byte-interleaving N STS-1 frames, which are then scrambled and converted to an optical carrier–level N (OC-N) signal. Thus the OC-N signal will have a line rate exactly N times that of an OC-1 signal. For SDH systems, the fundamental building block is the 155.52-Mb/s synchronous transport module–level 1 (STM-1). Again, higher-rate information streams are generated by synchronously multiplexing N different STM-1 signals to form the STM-N signal. Table 2 shows commonly used SDH and SONET signal levels.

The development of optical sources and photodetectors capable of operating at 1310 nm allowed a shift in the transmission wavelength from 850 nm to 1310 nm. This resulted in a substantial increase in the repeaterless transmission distance for long-haul telephone trunks, since optical fibers exhibit lower power loss and less signal dispersion at 1310 nm. Intercity applications first used multimode fibers, but in 1984 switched exclusively to single-mode fibers, which have a significantly larger bandwidth. Bit rates for long-haul links typically range between 155 and 622 Mb/s (OC-3 and OC-12), and in some cases up to 2.5 Gb/s (OC-48), over repeater spacings of 40 km. Both multimode and single-mode 1310-nm fibers are used in local area networks, where bit rates range from 10 Mb/s to 100 Mb/s over distances ranging from 500 m to tens of kilometers.

In the next step of system evolution, links operating in the low-loss window around 1550 nm attracted much attention for high-capacity, long-span terrestrial and undersea transmission links. These links routinely carry traffic at 2.5 Gb/s over 90-km repeaterless distances. By 1996, advances in high-quality lasers and receivers allowed single-wavelength transmission rates of 10 Gb/s (OC-192).

In 1989, the introduction of optical amplifiers gave a major boost to fiber transmission capacity. Although there are GaAlAs-based solid-state optical amplifiers for the first window and InGaAsP amplifiers for the second window, the most successful and widely used devices are erbium-doped fiber amplifiers (commonly called EDFAs) operating in the 1530 to 1560-nm range and Raman fiber amplifiers that are used for operation in the 1560 to 1600-nm region.

During the same time period, impressive demonstrations of long-distance high-capacity systems were made using optical soliton signals. A soliton is a nondispersive pulse that makes use of nonlinear dispersion properties in a fiber to cancel out chromatic dispersion effects. As an example, solitons at rates of 10 Gb/s have been sent over a 12 200-km experimental link using optical amplifiers and special modulation techniques.

Entrance of Wavelength Division Multiplexing

The use of wavelength division multiplexing (WDM) offers a further boost in fiber transmission capacity. The basis of WDM is to use multiple sources operating at slightly different wavelengths to transmit several independent information streams over the same fiber. Although researchers started looking at WDM in the 1970s, during the ensuing years it generally turned out to be easier to implement higher-speed electronic and optical devices than to invoke the greater system complexity called for in WDM. However, a dramatic surge in WDM popularity started in the early 1990s, as electronic devices neared their modulation limit and high-speed equipment became increasingly complex.

Figure 5 shows the concept of implementing many closely spaced wavelengths within a spectral band centered around 1552.524 nm. This scheme is referred to as dense WDM or DWDM. Conceptually, the DWDM scheme is the same as frequency

Table 2 Commonly used SONET and SDH transmission rates

SONET level	*Electrical level*	*Line rate (Mb/s)*	*SDH equivalent*	*Common rate name*
OC-1	STS-1	51.84	–	
OC-3	STS-3	155.52	STM-1	155 Mb/s
OC-12	STS-12	622.08	STM-4	622 Mb/s
OC-24	STS-24	1244.16	STM-8	
OC-48	STS-48	2488.32	STM-16	2.5 Gb/s
OC-96	STS-96	4976.64	STM-32	
OC-192	STS-192	9953.28	STM-64	10 Gb/s
OC-768	STS-768	39,813.12	STM-256	40 Gb/s



Figure 5 Wavelength division multiplexing (WDM) concept.

division multiplexing (FDM) used in microwave radio and satellite systems. Just as in FDM, the wavelengths (or optical frequencies) in a DWDM link must be properly spaced to avoid interference between channels. In an optical system this interference may arise from the fact that the center wavelength of laser diode sources and the spectral operating characteristics of other optical components in the link may drift with temperature and time, thereby giving rise to the need for a guard band between wavelength channels.

Since WDM is essentially frequency division multiplexing at optical carrier frequencies, the ITU developed DWDM standards that specify channel spacings in terms of frequency. The ITU-T Recommendation G.694.1, which is entitled 'Dense Wavelength Division Multiplexing (DWDM),' specifies WDM operation in the S-, C-, and L-bands for high-quality, high-rate metro area network (MAN) and wide area network (WAN) services. It calls out for narrow frequency spacings of 100 to 12.5 GHz (or, equivalently, 0.8 to 0.1 nm at 1550 nm). This implementation requires the use of stable, high-quality, temperature-controlled and wavelength-controlled (frequency-locked) laser diode light sources.

With the production of full-spectrum (low-water-content) fibers, the development of relatively inexpensive optical sources, and the desire to have low-cost optical links operating in metro and local area networks, came the concept of coarse WDM (CWDM). In 2002, the ITU-T released a standard aimed specifically at CWDM. This is Recommendation G.694.2, which is entitled 'Coarse Wavelength Division Multiplexing (CWDM).' The CWDM grid is made up of 18 wavelengths defined within the range 1270 nm to 1610 nm (O-through L-bands) spaced by 20 nm with wavelength-drift tolerances of ± 2 nm. This can be achieved with inexpensive light sources that are not temperature-controlled. The targeted transmission distance for CWDM is 50 km on single-mode fibers, such as those specified in ITU-T Recommendations G.652, G.653, and G.655.

Wavelength tunability of a source is an important property of WDM systems. Obviously it is not desirable or practical to maintain an inventory of dozens of lasers that emit at different wavelengths for WDM applications. The ideal tunable laser should be adjustable to emit at a specific wavelength across a broad spectral range. One such device is a distributed Bragg reflector (DBR) laser diode that can be tuned over a 10 to 20 nm spectral range. Work on perfecting such devices are still underway.

Starting in the mid-1990s, a combination of EDFAs and WDM was used to boost fiber information capacity to even higher levels and to increase the transmission distance. A major system consideration in these super-high capacity links is to ensure that there is appropriate link and equipment redundancy, so that alternate paths are available in case of disruptions in communications resulting from cable ruptures (for example, caused by errant digging from a backhoe) or equipment failures at an intermediate node. Such disruptions otherwise could have a devastating effect on a large group of users.

Undersea Optical Cable Systems

The first transoceanic fiber optic cable systems were installed in the Atlantic and Pacific Oceans in 1988 and 1989. Initially these systems operated at 280 Mb/s per fiber pair using 1310-nm lasers and single-mode fibers. The links consisted of a series of point-to-point optical fiber segments between electronic-based undersea regeneration points that were located nominally 60 km apart. Later the transmission capacity of these links was upgraded to 2.5 Gb/s and the regenerator spacing was increased to 100 km by converting the 1310-nm multiple-frequency light sources to 1550-nm single-frequency laser diodes. Later, the regenerator spacing was increased to 140 km.

Although these cable systems significantly improved the quality of the international telephone service, the optical-to-electrical conversion process at each regeneration point remained a capacity bottleneck. The introduction of erbium-doped optical fiber amplifiers (EDFA) eliminated this bottleneck from undersea lightwave systems by amplifying signals directly in the optical domain. Since EDFAs operate over a 30-nm wavelength band, they are well suited for use with undersea WDM links, which have provided a further capacity increase. These undersea optical amplifiers are typically spaced about 45 km apart.

One example of the many worldwide installations of optically amplified WDM networks is the SEA-ME-WE-3 Cable System. This undersea network runs from Germany to Singapore, connecting more than a dozen countries in between. Hence the name SEA-ME-WE, which refers to Southeast Asia (SEA), the Middle East (ME), and Western Europe (WE). The network has two pairs of undersea fibers with a capacity of eight STM-16 wavelengths per fiber.

See also

Lasers: Optical Fiber Lasers. **Optical Communication Systems:** Architectures of Optical Fiber Communication Systems; Wavelength Division Multiplexing.

Further Reading

Bergano NS (1997) Undersea amplified lightwave system design. In: Kaminow IP and Koch TL (eds) *Optical Fiber Telecommunications*, vol. IIIA, pp. 302–335. New York: Academic.

Goralski WJ (2002) SONET/SDH, 3rd edn. New York: McGraw-Hill.

Hecht J (1999) *City of Light*. New York: Oxford University Press.

Joyner CH (1997) Semiconductor laser growth and fabrication technology. In: Kaminow IP and Koch TL (eds) *Optical Fiber Telecommunications*, vol. IIIB, pp. 163–199. New York: Academic.

Kaiser P and Keck DB (1988) Fiber types and their status. In: Miller SE and Kaminow IP (eds) *Optical Fiber Telecommunications II*, pp. 29–54. New York: Academic.

Kao KC and Hockman GA (July 1966) Dielectric-fibre surface waveguides for optical frequencies. *Proceedings IEE*, vol. 113, 1151–1158.

Keiser G (2003) *Optical Communications Essentials*. New York: McGraw-Hill.

Keiser G (2000) *Optical Fiber Communications*, 3rd edn. Burr Ridge, IL: McGraw-Hill.

Mollenauer LF, Gordon JP and Mamyshev PV (1997) Solitons in high bit rate long-distance transmission. In: Kaminow IP and Koch TL (eds) *Optical Fiber Telecommunications*, vol. IIIA, pp. 373–460. New York: Academic.

Nyman B, Farries M and Si C (Oct 2001) Technology trends in dense WDM demultiplexers. *Optical Fiber Technology* 7(4): 255–274.

Ramaswami R and Sivarajan KN (2002) *Optical Networks*, 2nd edn. San Francisco, CA: Morgan Kaufmann.

Snitzer E (May 1961) Cylindrical dielectric waveguide modes. *Journal Optical Society of America* 51: 491–498.

Trischitta PR and Marra WC (1998) Applying WDM technology to undersea cable networks. *IEEE Communication Magazine* 36(2): 62–66.

Architectures of Optical Fiber Communication Systems

G Keiser, PhotonicsComm Solutions, Inc.,
Newton Center, MA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Simple Optical Fiber Links

The most basic optical fiber communication system architecture is a point-to-point link consisting of the elements shown in Figure 1. The key sections are a transmitter consisting of a light source and its associated drive circuitry, a cable offering mechanical and environmental protection to the optical fibers contained inside, and a receiver consisting of a photodetector plus amplification and signal-restoring circuitry. Very long links may include periodic optical amplifiers for boosting the level of the optical signal. In networks that use only simple point-to-point links, the optical fiber is used principally as a transmission medium and all the switching and processing of information bits is done by electronics.

At the transmitting end of an optical fiber link, information bits consisting of electronic pulses are used to modulate the light output of the source. The resulting light pulses are coupled into an optical fiber. As they travel along the fiber these signal pulses become progressively weakened and distorted due to attenuation and dispersion mechanism that are characteristic of an optical fiber. At the end of the fiber link a photodetector converts the optical pulses back to an electrical format for switching to another link or for processing at the end station.


Cabled fibers
Light source and drive circuitry
Photodetector and amplifier circuitry
Optical amplifiers for long links

Figure 1 Basic elements of a point-to-point fiber optic link.

The cabled fiber is one of the most important elements in an optical fiber link, since it determines operational parameters such as transmission distance and achievable data rates. In addition to protecting the glass fibers during installation and service, the cable may contain copper wires for powering optical amplifiers or signal regenerators, which are needed periodically in long-distance links for amplifying and reshaping the signal.

Analogous to copper cables, the installation of optical fiber cables can be either aerial, in ducts, undersea, or buried directly in the ground. As a result of installation and/or manufacturing limitations, individual cable lengths will range from several hundred meters to several kilometers. Practical considerations such as reel size and cable weight determine the actual length of a single cable section. The shorter segments tend to be used when the cables are pulled through ducts. Longer lengths are used in aerial, direct-burial, or undersea applications. Splicing together individual cable sections forms continuous transmission lines for these long-distance links. For undersea installations, the splicing and repeater-installation functions are carried out on board a specially designed cable-laying ship.

One of the principal characteristics of an optical fiber is its attenuation as a function of wavelength, as shown in Figure 2. Early technology used the 800 to 900 nm wavelength band, since in this region the fibers made at that time exhibited a local minimum in the attenuation curve, and optical sources and photodetectors operating at these wavelengths were available. This region originally was referred to as the ‘first window’. By reducing the concentration of hydroxyl ions and metallic impurities in the fiber material, in the 1980s manufacturers were able to fabricate optical fibers with very low loss in the 1100 to 1600 nm region. Two windows are defined here, these being the ‘second window’ centered around 1310 nm and the ‘third window’ centered around 1550 nm.

In 1998 a new ultra-high purifying process patented by Lucent Technologies eliminated virtually all water molecules from the glass material. The resulting fiber is designated as either a low-water-peak or a full spectrum fiber. By dramatically reducing the water-attenuation peak around 1400 nm, this process opens the transmission region between the second and third windows to provide around 100 nm more bandwidth than in conventional single-mode fibers. This particular fiber allows wider spectral tolerances on optical components, which reduces costs for moderate-distance metropolitan network applications.

Since the attenuation of low-water-peak fibers makes the designation of transmission windows obsolete, the concept of operational spectral bands arose for the 1260–1675 nm region. As shown in



Figure 2 Attenuation versus wavelength for silica fibers and the concept of spectral bands.

Figure 2, the regions are known by the letters O, E, S, C, L, and U, which are defined as follows:

- Original band (O-Band): 1260–1360 nm;
- Extended band (E-Band): 1360–1460 nm;
- Short band (S-Band): 1460–1530 nm;
- Conventional band (C-Band): 1530–1565 nm;
- Long band (L-Band) 1565–1625 nm;
- Ultra-long band (U-Band): 1625–1675 nm.

Once the cable is installed, a light source that is dimensionally compatible with the fiber core is used to launch optical power into the fiber. Semiconductor light-emitting diodes (LEDs) and laser diodes are suitable for this purpose, since their light output can be modulated rapidly by simply varying the bias current at the desired transmission rate, thereby producing an optical signal. The electric input signals to the transmitter circuitry for the optical source can be either of an analog or digital form. For high-rate systems (nominally greater than 1 Gb/s), direct modulation of the source can lead to unacceptable signal distortion. In this case, an external modulator is used to vary the amplitude of a continuous light output from a laser diode source.

After an optical signal is launched into a fiber, it will become progressively attenuated and distorted with increasing distance because of scattering, absorption, and dispersion mechanisms in the glass material. At the receiver a photodiode will detect the weakened optical signal emerging from the fiber end and convert it to an electric current. The design of an optical receiver is inherently more complex than that of the transmitter, since it has to interpret the content of the weakened and degraded signal received by the photodetector. The principal figure of merit for a receiver is the maximum optical power necessary at the desired data rate to attain either a given error probability for digital systems or a specified signal-to-noise ratio for an analog system. The ability of a receiver to achieve a certain performance level depends on the photodetector type, the effects of noise in the system, and the characteristics of the successive amplification stages in the receiver.

Networks of Links

With the advent of fiber optic transmission lines, the next step in the evolution of the digital multiplexing scheme used by telecommunication providers was a standard signal format called synchronous optical network (SONET) in North America and synchronous digital hierarchy (SDH) in other parts of the world. In the mid-1980s, efforts started on developing a standard that would allow network engineers to interconnect fiber optic transmission equipment from various vendors through multiple-owner trunk networks. This resulted in a series of standards for SONET by the American National Standards Institute (ANSI) and a series of recommendations for SDH from the International Telecommunications Union (ITU). Examples of particular interest are the ANSI T1.105.06 standard and the ITU-T G.957 recommendation. Although there are some implementation differences between SONET and SDH, all SONET specifications conform to the SDH recommendations. A key characteristic of SONET and SDH is that they are usually configured as a ring architecture. This is done to create loop diversity for uninterrupted service protection purposes in case of link or equipment failures. The SONET/SDH rings commonly are called self-healing rings, since the traffic flowing along a certain path can be switched automatically to an alternate or standby path following failure or degradation of the link segment.

The basic building block and first level of the SONET signal hierarchy is called the Synchronous Transport Signal – Level 1 (STS-1), which has a bit rate of 51.84 Mb/s. Higher-rate SONET signals are obtained by byte-interleaving *N* STS-1 frames, which are then scrambled and converted to an Optical Carrier – Level *N* (OC-N) signal. Thus the OC-N signal will have a line rate exactly *N* times that of an OC-1 signal. For SDH systems the fundamental building block is the 155.52 Mb/s Synchronous Transport Module – Level 1 (STM-1). Again, higher-rate information streams are generated by synchronously multiplexing *N* different STM-1 signals to form the STM-N signal.

Three main features, each with two alternatives, classify all SONET/SDH rings, thus yielding eight possible combinations of ring types. First, there can be either two or four fibers running between the nodes on a ring. Second, the operating signals can travel either clockwise only (which is termed a unidirectional ring) or in both directions around the ring (which is called a bidirectional ring) Third, protection switching can be performed either via a line-switching or a path-switching scheme. Upon link failure or degradation, line switching moves all signal channels of an entire OC-N channel to a protection fiber. Conversely, path switching can move individual payload channels within an OC-N channel (e.g., an STS-1 channel within an OC-12 channel) to another path.

Of the eight possible combinations of ring types, the following two architectures have become popular for SONET and SDH networks:

- two-fiber unidirectional path-switched ring (two-fiber UPSR);
- two-fiber or four-fiber bidirectional line-switched ring (two-fiber or four-fiber BLSR).

The common abbreviations of these configurations are given in parentheses. They also are referred to as unidirectional or bidirectional self-healing rings (USHR or BSHR).

Figure 3 shows a two-fiber unidirectional path-switched ring network. By convention, in a unidirectional ring the normal working traffic travels clockwise around the ring, as indicated by the heavy arrows. For example, the connection from node 1 to node 3 uses links 1 and 2, whereas the traffic from node 3 to node 1 traverses links 3 and 4. Thus, two communicating nodes use a specific bandwidth capacity around the entire perimeter of the ring. If nodes 1 and 3 exchange information at an OC-3 rate in an OC-12 ring, then they use one-fourth of the capacity around the ring on all the primary links. In a unidirectional ring the counter-clockwise path is used as an alternate path for protection against link or node failures. To achieve this, the signal from a transmitting node is dual-fed into both the primary and protection fibers. This establishes a designated protection path on which traffic flows counter-clockwise, i.e., from node 1 to node 3 via links 5 and 6 (in that order), as shown in Figure 3b. A heavy line and a dashed line indicate the primary and protection paths, respectively.

Consequently, two identical signals from a particular node arrive at their destination from opposite directions, usually with different delays, as denoted in Figure 3b. The receiver normally selects the signal from the primary path. However, it continuously compares the fidelity of each signal and chooses the alternate signal in case of severe degradation or loss of the primary signal. Thus, each path is individually switched based on the quality of the received signal. For example, if path 2 breaks or equipment in node 2 fails, then node 3 will switch to the protection channel to receive signals from node 1.

Figure 4 illustrates the architecture of a four-fiber bidirectional line-switched ring. Here two primary fiber loops (with fiber segments labeled 1p through 8p) are used for normal bidirectional communication, and the other two secondary fiber loops are standby links for protection purposes (with fiber segments labeled 1s through 8s). In contrast to the two-fiber UPSR, the four-fiber BLSR has a capacity advantage since it uses twice as much fiber cabling and because traffic between two nodes is only sent partially around the ring.



Figure 3 Schematic of a two-fiber unidirectional path-switched ring network.

To see the function and versatility of the standby links in the four-fiber BLSR, consider first the case where a transmitter or receiver circuit card used on the primary ring fails in either node 3 or 4. In this situation the affected nodes detect a loss-of-signal condition and switch both primary fibers connecting them to the secondary protection pair, as shown in Figure 5. The protection segment between nodes 3 and 4 now becomes part of the primary bidirectional loop. The exact same reconfiguration scenario will


Primary two-fiber
bidirectional loop
4p
8p
4s
8s
Node
1
1p
5p
1s
5s
Secondary two-fiber
bidirectional protection loop
Node
4
Node
2
6p
2p
7s
6s
7p
3s
2s
3p
Node
3

Figure 4 The architecture of a four-fiber bidirectional, line-switched ring.


Node
1
Primary two-fiber loop
Two-fiber
protection
loop
Node
5
Node
2
Protection switching
Node 4
Node 3
Break in
primary fiber
Card failure

Figure 5 Reconfiguration of a four-fiber BLSR under transceiver failure.

occur when the primary fiber connecting nodes 3 and 4 breaks. Note that in either case the other links remain unaffected.

Now suppose an entire node fails, or both the primary and the protection fibers in a given span are severed, which could happen if they are in the same cable duct between two nodes. In this case the nodes on either side of the failed span internally switch the primary-path connections from their receivers and transmitters to the protection fibers, in order to loop traffic back to the previous node. This process again forms a closed ring, but now with all of the primary and protection fibers in use around the entire ring, as shown in Figure 6.

Single-Span WDM Links

An interesting and powerful aspect of an optical communication link is that many different wavelengths can be sent along a fiber simultaneously in the 1300–1600 nm spectrum. The technology of combining a number of wavelengths onto the same fiber is known as wavelength division multiplexing or WDM. Figure 7 shows the basic WDM concept. Here N independent optically formatted information streams, each transmitted at a different wavelength, are combined with an optical multiplexer and sent over the same fiber. Note that each of these streams could be at a different data rate. Each information stream maintains its individual data rate after being multiplexed with the other streams, and still operates at its unique wavelength. Conceptually, the WDM scheme is the same as frequency division multiplexing (FDM) used in microwave radio and satellite systems.

To see the potential of WDM, consider the characteristics of a high-quality optical source such as a distributed feedback (DFB) laser, which has a very narrow frequency spectrum on the order of 1 MHz, which is equivalent to a spectral linewidth of 10^{-5} nm. When using such a source, a guard band of 0.4–1.6 nm is typically employed. This is done to take into account possible drifts of the peak wavelength due to aging or temperature effects, and to give both the manufacturer and the user some leeway in specifying and choosing the precise peak emission wavelength. With such spectral band widths, simplex systems make use of only a very


Node
1
Primary two-fiber loop
Two-fiber
protection
loop
Node
5
Node
2
Protection-switching loopbacks
Node 4
Cable
failure
Node
failure
Node 3

Figure 6 Reconfiguration of a four-fiber BLSR under node or fiber-cable failure.


λ_1
λ_2
λ_N
$\lambda_1, \lambda_2, \ldots, \lambda_N$
Single
fiber line
Individual
fiber lines
Optical
multiplexer

Figure 7 The basic WDM concept.

small portion of the transmission bandwidth capability of a fiber. This can be seen from Figure 2, which depicts the attenuation of light in a silica fiber as a function of wavelength. The curve shows that the two low-loss regions of a single-mode fiber extend over the wavelengths ranging from about 1260 to 1360 nm (the O-band) and from 1460 to 1625 nm (the S-, C-, and L-bands).

These regions can be viewed either in terms of spectral width (the wavelength band occupied by the light signal and its guard band) or by means of optical bandwidth (the frequency band occupied by the light signal). To find the optical bandwidth corresponding to a particular spectral width in these regions, consider the fundamental relationship $c = \lambda\nu$, which relates the wavelength λ to the carrier frequency ν, where c is the speed of light. Differentiating this yields $\Delta\nu = (c/\lambda^2)\Delta\lambda$, where the deviation in frequency $\Delta\nu$ corresponds to the wavelength deviation $\Delta\lambda$ around λ. Thus the optical bandwidth is $\Delta\nu = 14$ THz for a usable spectral band $\Delta\lambda = 80$ nm in the O-band. Similarly, $\Delta\nu = 15$ THz for a usable spectral band $\Delta\lambda = 120$ nm in the region spanning the S-, C-, and L-bands.

Since the spectral width of a high-quality source occupies only a narrow optical bandwidth, the two low-loss windows provide many additional operating regions. By using a number of light sources, each emitting at a different peak wavelength that is sufficiently spaced from its neighbor so as not to create interference, the fidelities of the independent messages from each source are maintained for subsequent conversion to electrical signals at the receiving end.

Since WDM is essentially frequency division multiplexing at optical carrier frequencies, the WDM standards developed by the ITU specify channel spacings in terms of frequency. A key reason for selecting a fixed frequency spacing, rather than a constant wavelength spacing, is that when locking a laser to a particular operating mode it is the frequency of the laser that is fixed. The ITU-T Recommendation G.692 specifies selecting the channels from a grid of frequencies referenced to 193.100 THz (1552.524 nm) and spacing them 100 GHz (0.8 nm at 1552 nm) apart. Suggested alternative spacings include 50 GHz and 200 GHz.

Historically the term dense WDM (DWDM) was used somewhat loosely and generally referred to the spacings denoted by Recommendation G.692. In 2002 the ITU-T released an updated standard aimed specifically at DWDM. This is Recommendation G.694.1, which specifies WDM operation in the S-, C-, and L-bands for high-quality, high-rate metro area network (MAN) and wide area network (WAN) services. It calls out for narrow frequency spacings of 100 to 12.5 GHz (or, equivalently, 0.8 to 0.1 nm at 1550 nm).

Alternatively, by using the larger spectral window available in low-water-content fibers, one can relax the spectral tolerances on the optical components and space the individual sources much further apart. This is the basis of coarse WDM (CWDM), which is useful for metropolitan area networks where variations in attenuation between different wavelength channels is not critical over short transmission distances. In 2002 the ITU-T released Recommendation G.694.2, which is aimed specifically at CWDM. The CWDM grid is made up of 18 wavelengths defined within the range 1270–1610 nm (O- through L-bands) spaced by 20 nm with wavelength-drift tolerances of ±2 nm.

A key feature of WDM is that the discrete wavelengths form an orthogonal set of carriers which can be separated, routed, and switched without interfering with each other. This holds as long as the total optical power intensity is kept sufficiently low to prevent nonlinear effects such as stimulated Brillouin scattering and four-wave mixing processes from degrading the link performance.

The implementation of WDM networks requires a variety of passive and/or active devices to combine, distribute, isolate, and amplify optical power at different wavelengths. Passive devices require no external control for their operation, so they are somewhat limited in their application in WDM networks. These components are mainly used to split and combine or tap off optical signals. The performance of active devices can be controlled electronically, thereby providing a large degree of network flexibility. Active WDM components include tunable optical filters, tunable sources, and optical amplifiers.

Passive Optical Networks

Another step towards realizing the full potential of optical fiber transmission capacity is the concept of all-optical WDM networks to extend the versatility of communication networks beyond architectures such as those provided by SONET. These networks can be classified as either broadcast-and-select or wavelength-routing networks. In general, broadcast-and-select techniques employing passive optical stars, buses, or wavelength routers are used for local network applications, whereas active optical components form the basis for constructing wide-area wavelength-routing networks. Broadcast-and-select networks can be categorized as single-hop or multihop networks. Single-hop refers to networks where information transmitted in the form of light reaches its destination without being converted to an electrical form at any intermediate point. On the other hand, intermediate conversion can occur in a multihop network.

Figure 8 shows two alternate physical architectures for a WDM-based local network. Here *N* sets of transmitters and receivers are attached either to a star coupler or a passive bus. Each transmitter sends its information at a different fixed wavelength. All the transmissions from the various nodes are combined in a passive star coupler or coupled onto a bus and the result is sent out to all receivers.

Each receiver sees all wavelengths and uses a tunable filter to select the one wavelength addressed to it. In addition to point-to-point links, this configuration can also support multicast or broadcast services, where one transmitter sends the same information to several nodes. An interesting point is that these passive WDM networks are protocol transparent. This means that different sets of communicating nodes can use different information-exchange rules (protocols) without affecting the other nodes in the network. This is analogous to current time-division-multiplexed telephone lines in which voice, data, or facsimile services are sent in different time slots without interfering with each other.

Although the architectures of single-hop broadcast-and-select networks are fairly simple, there needs to be careful dynamic coordination between the nodes. For example, if the network is set up so that a transmitter sends its information at a unique fixed wavelength, then the destined receiver needs to be informed when a message is being sent to it, so that it can tune its selective filter to that wavelength. Also conflicts need to be resolved in cases where two stations transmitting at different wavelengths want to send information to the same recipient simultaneously.



Figure 8 Two alternate physical architectures for a WDM-based local network.



Figure 9 Example of a four-node broadcast-and-select multihop network.

A drawback of single-hop networks is the need for rapidly tunable lasers or receiver optical filters. The designs of multihop networks avoid this need. Multihop networks generally do not have direct paths between each node pair. Each node has a small number of fixed-tuned optical transmitters and receivers. Figure 9 shows an example of a four-node broadcast-and-select multihop network where each node transmits on one set of two fixed wavelengths and receives on another set of two wavelengths. Stations can send information directly only to those nodes that have a receiver tuned to one of the two transmit wavelengths. Information destined for other nodes will have to be routed through intermediate stations.

The flow of traffic can be seen from Figure 9. If node 1 wants to send a message to node 2, it first transmits the message to node 3 using λ_1. Then node 3 forwards the message to node 2 using λ_6. In contrast to single-hop networks, with this scheme there are no destination conflicts or packet collisions in the network, since each wavelength channel is dedicated to a particular source–destination link. However, for H hops between nodes, there is a network throughput penalty of at least $1/H$.

Wavelength-Routed Optical Networks

Wavelength-routed networks overcome the limitations of passive optical networks through wavelength reuse, wavelength conversion, and optical switching. The physical topology of a wavelength-routed network consists of optical wavelength routers interconnected by pairs of point-to-point fiber links in an arbitrary mesh configuration, as illustrated in Figure 10. Each link can carry a certain number of wavelengths, which can be directed independently to different output paths at a node. Each node may have logical connections with several other nodes in the network, where each connection uses a particular wavelength. Provided the paths taken by any two connections do not overlap, they can use the same wavelength. Thereby the number of wavelengths is greatly reduced. For example, the connection from node 1 to node 2 and from node 2 to node 3 can both be on λ_1, whereas the connection between nodes 4 and 5 requires a different wavelength (λ_2).


1
2
λ_1
λ_1
λ_2
3
4
5
Wavelength-routing node
End station

Figure 10 The physical topology of a wavelength-routed network.

A high degree of path modularity, capacity scaling, and flexibility in adding or dropping channels at a user site can be achieved by introducing the concept of an optical cross-connect architecture in the physical path structure (the so-called path layer) of an optical network. These optical cross-connects (OXCs) operate directly in the optical domain and can route very high-capacity WDM data streams over a network of interconnected optical paths.

Contentions could arise when channels having the same wavelength but traveling on different input fibers enter the OXC and need to be switched simultaneously to the same output fiber. This could be resolved by assigning a fixed wavelength to each optical path throughout the network, or by dropping one of the channels and retransmitting it at another wavelength. However, in the first case, wavelength reuse and network scalability (expandability) are reduced, and in the second case the add/drop flexibility of the OXC is lost. These blocking characteristics can be eliminated by using wavelength conversion at any output of the OXC.

As an example consider the 4 × 4 OXC shown in Figure 11. Here two input fibers are each carrying two wavelengths. Either wavelength can be switched to any of the four output ports. The OXC consists of three 2 × 2 switch elements. Suppose that λ_2 on input fiber 1 needs to be switched to output fiber 2 and that λ_1 on input fiber 2 needs to be switched to output fiber 1. This is achieved by having the first two switch elements set in the bar state (the straight-through configuration) and the third element set in the cross state, as indicated in Figure 11. Obviously without wavelength conversion there would be wavelength contention at both output ports.


2×2 optical switch elements
$\lambda_1\lambda_2$
Demux
λ_1
λ_2
$\lambda_1\lambda_2$
Demux
λ_1
λ_2
λ_1
λ_1
λ_2
λ_2
λ_1
λ_2
λ_1
λ_2
Mux
$\lambda_1\lambda_2$
Mux
$\lambda_1\lambda_2$
Bar states
Cross state
Wavelength converters

Figure 11 Example of a 4 × 4 optical cross-connect (OXC).

By using wavelength converters, the cross-connected channels can be converted to noncontending wavelengths.

See also

Lasers: Optical Fiber Lasers. **Optical Communication Systems:** Wavelength Division Multiplexing.

Further Reading

Blumenthal DJ, Prucnal PR and Sauer JR (1994) Photonic packet switches: architectures and experimental implementations. *Proceedings of the Institute of Electrical and Electronics Engineering* 82(11): 1650–1667.

Forouzan BA (2001) *Introduction to Data Communications and Networking*, 2nd edn. Burr Ridge, IL: McGraw-Hill.

Goralski WJ (2002) *SONET/SDH*, 3rd edn. New York: McGraw-Hill.

Gumaste A and Antony T (2003) *DWDM Network Designs and Engineering Solutions*. Upper Saddle River, NJ: Prentice Hall.

Hecht J (2002) *Understanding Fiber Optics*, 4th edn. Upper Saddle River, NJ: Prentice Hall.

Iannone E and Sabella R (1996) Optical path technologies: a comparison among different cross-connect architectures. *Journal of Lightwave Technology* 14(10): 2184–2196.

Keiser G (1999) A review of WDM technology and applications. *Optical Fiber Technology* 5(1): 3–39.

Keiser G (2000) *Optical Fiber Communications*, 3rd edn. Burr Ridge, IL: McGraw-Hill.

Keiser G (2002) *Local Area Networks*, 2nd edn. Burr Ridge, IL: McGraw-Hill.

Keiser G (2003) *Optical Communications Essentials*, New York: McGraw-Hill.

Ramaswami R and Sivarajan KN (2002) *Optical Networks*, 2nd edn. San Francisco: Morgan Kaufmann.

Special Issue (1995) *Undersea Communications Technology. AT&T Technical Journal* 74(1): 4–92.

Trischitta PR and Marra WC (1998) Applying WDM technology to undersea cable networks. *IEEE Communications Magazine* 36(2): 62–66.

Zang H, Jue JP, Sahasrabuddhe L, *et al.* (2001) Dynamic lightpath establishment in wavelength-routed WDM networks. *IEEE Communications Magazine* 39: 100–108.

Free Space Optical Communications

R Martini, Stevens Institute of Technology,
Hoboken, NJ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Free space optical (FSO) communication is the wireless transmission of data via a modulated optical beam directed through free space, without fiber optics or other optical systems guiding the light. The fundamental idea goes back to ancient times, as light (or smoke) signals were used to transmit information. From a more modern point of view, Graham Bell's patent on the photophone may mark the onset of modern FSO techniques, as it transmitted audio signals (i.e., voice) via the modulation of sunlight. A renaissance of FSO systems started with the availability of lasers, light sources with high output power and high coherence, which allowed the accurate direction of the light beams over long distances. During the 1970s and 1980s the main proposed application of FSO systems was for secure and long distance (50–1000 km) communication, mainly targeted for ground–satellite or satellite–satellite communication. This focus changed drastically over the last decade as a new market for FSO grew in the establishment of high bandwidth data link and their integration over a locally restricted area.

The main competitors in this market are the fiber-based optical network, the RF communication system, as well as the low bandwidth copper cable-based system. In comparison to the closely related wireless radio frequency transmission, the higher frequency of the optical carrier ($\sim 10^{14}-10^{15}$ Hz) thereby allows for much higher transmission rates, comparable to those of typical fiber optic networks. On the other hand, the use of an optical carrier also results in much more directed beam propagation, which requires an undisturbed line-of-sight between emitter and detector. This restricts the application of most FSO systems to a range between a few hundred meters up to several kilometers, which are still favorable for distribution of high bandwidth networks over a locally restricted area. This makes FSO a highly attractive candidate for the 'last-mile' distribution of high-bandwidth Ethernet to the individual homes.

The simplicity of setup of FSO links, as well as their modularity, is thereby their biggest advantage, compared to fiber-based networks. It makes them not only highly cost efficient, but it eases the maintenance or allows for fast and easy upgrades, as it does not require any extensive and time-consuming installation – in contrast to the installation of fiber optic cables. This advantage makes FSO highly attractive for temporary installations (emergency or short-time high broadcast situations, such as the Olympic Games), as well as to overcome geometrical restraints (river, seas, etc.). As most detector and emitter systems are typically based on the same electro-optical components used for fiber optic networks, they seamlessly integrate and expand an existing network without complications in data handling.

Standard FSO System

Figure 1 shows schematically the setup for a typical FSO system connecting two separate local networks. It consists of: an electronic data input; a small but powerful light source which can be modulated; emitter optics which shape the emitted beam to a highly directed beam; the atmosphere as transmitting device; detector optics which receive the transmitted light and focus it onto a photodetector; and an electronic amplifier which serves as data output.

Compared to a fiber optical communication system, the main difference is the use of the atmosphere as the transmission medium, in contrast to guided optical propagation. The transmission properties are thereby determined by the atmospheric conditions, which can lead to degradation and/or redirection of the beam. The main influences which have to be taken into account are atmospheric scattering, molecular absorption, turbulence effects (including beam wander and fading), as well as the impact of low-visibility weather situations like rain, snow, or fog. These depend strongly on wavelength and linewidth of the used emitter system, distance between emitter and receiver, as well as the environmental conditions. As a consequence, the characteristics of the atmospheric channel determine the layout of the other FSO components – and have to be considered first.

Atmospheric Losses

The overall losses of the atmospheric transmission are determined by the Beer–Lambert absorption law:

$$I = I_0 \exp[-\alpha L] \qquad [1]$$

where I is the intensity at the receiver, I_0 the intensity of the transmission beam after the emitter optics, and L is the range (i.e., distance between emitter and detector optics). The total extinction coefficient $\alpha = \alpha_{\text{Rayleigh}} + \alpha_{\text{Mie}} + \alpha_{\text{Absorption}}$ is based on three different contributions: Rayleigh scattering, Mie scattering, and absorption.

In contrast to absorption, the losses due to scattering originate from redirection of light and will be discussed first. Depending on the size of the scattering partner, two separate regimes have to be taken into account. For scatter smaller than the wavelength, the effect can be described based on Rayleigh's classical formula. The scattering cross-section of an element with mass m, charge q, natural oscillation wavelength λ_0, is then:

$$\sigma_s = \frac{f q^4 \lambda_0^4}{6\pi\varepsilon_0^2 m^2 c^4} \frac{1}{\lambda^4} \qquad [2]$$

where ε_0 is the dielectric constant, c the speed of light, and λ the wavelength of the incident light, leading to an extinction coefficient of $\alpha_{\text{Rayleigh}} = \sigma_s N_s$, where N_s is the concentration of the scattering elements. The λ^{-4} dependence in the scattering predicts stronger scattering for shorter wavelengths and Rayleigh scattering is therefore dominant for short and visible wavelengths (which gives the sky its blue color). For typical FSO



Figure 1 Typical components of a FSO system.

wavelengths in the region of near-infrared radiation (NIR, 800–2000 nm) or mid-infrared radiation (MIR, 2000–20 000 nm), the contribution of Rayleigh scattering is typically relatively low and can be neglected.

On the other hand, Mie scattering is, in most cases, the strongest contribution for FSO systems – but also the hardest to predict. It is due to resonant scattering effects, where the particle size is of the wavelength of the scattered light. For the typical FSO wavelengths these particles include water and oil droplets, dust, smog, fly ash, and aerosols (which can originate from pollution). A correct calculation of the Mie scattering coefficient is possible, but requires knowledge of the exact particle concentration as well as their size distribution. As these numbers are not only difficult to measure, but also fluctuate continuously depending on weather situation, time of day, season, temperature, climate, pollution, and other factors, a numerically correct evaluation is not possible.

Historically, most systems rely on an empirical formula, which estimates the attenuation coefficient to

$$\sigma_{\mathrm{Mie}} = \frac{3.91}{V}\left(\frac{\lambda}{550}\right)^{-p} \qquad [3]$$

where V denotes the visibility and the value of p ranges from 1.6 for high visibility ($V > 50$ km) and 1.3 for average visibility (50 km $> V >$ 6 km) down to 0.585 $V_{1/3}$, respectively for low visibility. The formula is based on data collected in the 1950s and 1960s. More accurate measurements show that the actual scattering cross-sections differ quite strongly, especially for low-visibility cases. Especially, the predicted dependence on wavelength is not correct. The failure of such a general model is not surprising, as the actual scattering properties are strongly dependent on the weather situation and the environmental conditions. It is the focus of ongoing research to find more accurate models describing the scattering condition in multiple environments and conditions to provide the background for more accurate empirical models.

Apart from the light redirection due to scattering, absorption either by molecules or aerosols is nearly as important for the transmission calculation of a FSO system. The strongest molecular absorptions are typically due to water, carbon dioxide, as well as ozone. A typical absorption spectrum can be easily calculated using standard software together with the publicly available HITRAN database, both available from ONTAR. The upper part of Figure 2 shows a low-resolution transmission spectrum for the interesting wavelength region for a path length of 1 km.



Figure 2 Upper: Low-resolution transmission spectrum of the atmosphere showing molecular absorption for a path length of 1 km. Lower: high-resolution spectrum of the atmospheric windows around 9.5 μm.

Within this spectrum, several well-known atmospheric windows exist, which are naturally preferred for FSO applications. These include the region around 830 nm, 1550 nm, and from 8 μm to 12 μm. For the exact selection of a wavelength, a closer look is needed. As an example, a high-resolution analysis of the atmospheric windows around 9.5 μm is shown in the lower part of Figure 2, which identifies additional absorption lines as well as highly transparent wavelength ranges within the window. Such substructure has to be taken carefully into account for the FSO wavelength selection, especially if lasers are employed, which have a linewidth comparable to the width of the absorption line.

Besides the molecules, aerosol particles also contribute to the absorption spectrum. Calculation of their contribution can also be performed using available software package, such as Air Force's MODTRAN and LOWTRAN program as well as OPAC from the LMU University in Munich. Figure 3 shows a typical low-resolution transmission spectrum for 50% humidity as well as 99% humidity, where by scattering as well as absorption effects have both been included in the calculation. The occurrence of sharp absorption features, as well as the increasing losses for wavelengths above 10 μm, is typically due to the aerosol absorption, whereas the scattering dominates the function for wavelengths below 3 μm. Losses due to the aforementioned Rayleigh scattering are also shown in the same diagram, demonstrating its low influence at longer wavelengths.

MODTRAN and LOWTRAN also allow the calculation of transmission spectra under rain and snow conditions, where rain and snow consist of



Figure 3 Typical low-resolution transmission spectrum calculated based on absorption and scattering losses from aerosols for 50% humidity (dashed line) and 99% humidity (solid line). The dotted line shows additionally the losses due to Rayleigh scattering.

clusters of water and aerosol with diameters from 200 μm to 2 mm and above. Depending on the severity of the precipitation, the losses can range from ~0.5 dB/km for light rain up to 13 dB/km for cloudbursts, requiring an additional power margin in the preparation of the FSO link. Significantly stronger is the impact of fog, as typically particles with much lower sizes are present. The losses inflicted by a moderate fog (visibility 500 m) range above 20 dB/km, surpassing the effect of a cloudburst; for thick fog the attenuation can even grow beyond 200 dB/km. However, depending on the size distribution within the fog itself, the losses can be highly wavelength dependent. Recent experiments show that long wavelength FSO systems operating in the MIR wavelength region have a much stronger stability under the influence of thick fog than one operating at NIR wavelengths.

Turbulence and Scintillation

In contrast to a static medium, the atmosphere is a dynamic mixture which undergoes continuous changes due to wind, temperature, and other influences. This creates a constant change in the parts of the atmosphere which are contributing to the FSO channel and therefore in the optical properties of the beam path. The index of refraction can differ, not only in its total value, but also within subsections of it, creating a random fluctuation in the beam paths. Such localized changes in the refractive index of the air are schematically shown in Figure 4, where turbulences of different sizes modify the beam path and disturb the beam front. The turbulence in the atmosphere can be quantified by the refractive-turbulence structure coefficient C_n^2, which can range from $10^{-13}\,\mathrm{m}^{-2/3}$ in the middle of the afternoon (highest value) to $10^{-17}\,\mathrm{m}^{-2/3}$ one hour after sunrise or sunset. As the turbulence effect is typically due to strong temperature difference, C_n^2 is strongest near hot surfaces (e.g., tar roofs or asphalt in the summer) and decreases with altitude. The effects of such turbulences on a directed light beam (such as used in FSO systems) include mainly beam wander and scintillation effects.

Beam wander is thereby based on large size turbulences which act as a lens on the propagating beam. Consequently, a narrow focused beam could be randomly steered away from the detector area, creating a fluctuation in the detected intensity.

Stronger impact for FSO links has scintillation, which is better known as the twinkling of a star or the heat shimmer of the horizon on a hot day. It is based on the continuous variation of the beam front which can lead to intensity fluctuations (like the twinkling) and loss in the image resolution (heat shimmer). Strong intensity fluctuations can thereby cause signal loss as well as receiver saturation, both resulting in downtime in the link. Such local intensity disturbances can occur up to sizes of $\sqrt{\lambda L}$, reaching, for example, 4 cm for a 1.55 μm link after 1 km. For small fluctuations, the intensity follows a classical stochastic behavior and can be described by the irradiance variation (normalized to its mean value) as

$$\sigma^2 = \exp\left[0.5\left(\frac{2\pi}{\lambda}\right)^{6/7} L^{11/6} C_n^2\right] - 1 \qquad [4]$$



Figure 4 Schematic depiction of atmospheric turbulences with different sizes in FSO systems. Shown below are illustrations of its main effects on a directed beam causing intensity fluctuations and beam wander.

with usual values in the range from 5 to 70%. Nonetheless, it should be pointed out that actual turbulence effects can differ quite strongly from these predictions, due to local inhomogeneities in temperature distribution. Consequently, test measurements are necessary for the correct evaluation of a specific installation site.

What makes scintillation effects difficult to handle for communications systems is the relatively slow frequency of fluctuations in the order of a few hundred Hz or less. The corresponding downtimes for a link can range from 1 ms to 10 ms, or even up to seconds. This is magnitudes higher than typical downtimes in standard communications links and cannot be compensated by standard forward error correction systems. One possibility to reduce the influence of scintillation is the method of aperture averaging, whereby multiple beams originating from slightly different positions are deployed and targeted at the same receiver. Assuming that the variation in each of the separate beam paths is random and uncorrelated, the signal-to-noise ratio will decrease by the square root of the number of beams. Recent experiments have impressively demonstrated this effect and allow reduction of intensity fluctuation to an acceptable level.

Another alternative to decreasing the scintillation effects is in the application of longer wavelength FSO systems. Whereas beam wander is relatively independent from the wavelength, scintillations effects scale with $\lambda^{7/6}$, as turbulences smaller than the wavelength cannot obscure its beam front. Using a 2 times longer wavelength, for example, should have the same impact as signal averaging with 4 different beams.

Beam Spreading and Pointing

Based on optical diffraction theory, the beam leaving the emitter optics will be divergent and its beam diameter will consistently increase during transmission through the optical channel. Assuming an optimal alignment and using standard geometrical optics, the losses due to beam spreading can estimate the ratio of emitted power (P_E) to received power (P_R):

$$R_{BS} = \frac{P_R}{P_E} = \frac{D_R}{(D_E + L\theta)} \qquad [5]$$

where D_R is the diameter of the receiving optics, D_E the diameter of the emitting optics, and θ the divergence of the beam. The minimal divergence of the beam is typically determined by the light source and is given by $\theta_L = \lambda/D_L M^2$, where D_L is the initial size of the laser beam and M^2 the laser-mode structure parameter, for a typical semiconductor laser θ_L below 0.1 mrad. In many cases, the divergence of the emitted beam is commonly enlarged by slight defocusing of the emitting optics – if the power budget allows for the additional losses. The beam size at the receiver is typically several times larger than the receiving aperture, which not only eases the alignment of the system, but also reduces pointing losses. This includes the effect of beam wander due to turbulence as well as swaying of the buildings or the mount. If those effects are solely compensated for by an increased beam spread, divergence can easily reach values of 2–20 mrad for short-distance links. Obviously this is not an option for longer-distance FSO links, as the losses will increase dramatically. In these cases, active tracking systems are incorporated in the emitter optics allowing for continuously adjustment to achieve and keep an optimal alignment. Typical tracking devices are thereby based on servo-driven Gimbal mounts, steering mirrors, or recently, MEMS devices.

Laser Eye Safety

As the atmospheric transmission channel of most FSO systems is not completely isolated, there exists the possibility of a human person intercepting the beam. To allow for this, most FSO systems are designed to be eye-safe following the voluntary ANSI standard, which limits the output irradiance to a certain value depending on the deployed wavelength. As radiation below 1400 nm is still being focused on the retina, it causes a higher irradiance, which results in a lower damage threshold. For 800 nm laser systems, the minimum permissible exposure (MPE) level for a 10 s long exposure is therefore recommended not to exceed 1 mW cm^{-2}, whereas for 1.55 μm or longer wavelength systems, an MPE of 100 mW cm^{-2} is suggested. The recommendations for incoherent light sources such as LEDs are thereby less stringent as they cannot be focused quite as strongly as laser light.

The Light Source

Following the discussion above, the optimal light source for FSO system should be emitting at a wavelength away from any absorption line (or should be much broader then the absorption line), have a relatively long wavelength as well as a relative low divergence, be eye-safe, and allow for high modulation speed. In reality, most FSO systems use either GaAsAl laser diodes or LEDs emitting at 0.8 μm, or the typically more expensive 1.5 μm laser diodes based on the InGaAsP semiconductor system. The output power of both laser systems is typically in the range of 1 mW to 100 mW, which for the longer wavelength case can be boosted to 1–10 W using erbium-doped fiber amplifiers (or even higher for specific applications). The longer wavelength system has the additional advantage of higher ANSI standards as discussed above, allowing stronger eye-safe emission power, but is typically far more expensive.

Both laser types were developed and optimized for standard fiber-based communication systems allowing direct modulation up to 10 Gbit/s. To achieve higher bandwidth in FSO systems, standard techniques known from fiber-based networks can easily be deployed, like wavelength division multiplexing which increases the bandwidth up to state-of-the-art levels of fiber-based networks.

Contrary to semiconductor lasers, LEDs provide a much less expensive alternative, but allow only for modulation up to 10–100 MHz. Their broad emission spectrum is thereby an advantage, as it is less sensitive to sharp absorption lines which – as discussed earlier – can have a drastic impact on the FSO link performance. Consequently, LEDs have been successfully implemented in several commercial FSO systems targeted at the short-range market.

Recently developed sources, which have also been applied for FSO systems, include vertical-cavity surface-emitting lasers as well as quantum cascade lasers (QCL) which emit in the mid-infrared regime. The latter devices have been predicted to have a strong impact on the FSO market, as they combine high-output power (up to 1 W) together with fundamentally high modulation bandwidth (2.5 Gbit/s recently demonstrated and higher rates predicted) at wavelengths ranging from 3.5 μm to 12 μm and beyond. They can access the long-wavelength atmospheric window atmospheric for the FSO systems (typically reserved for CO_2 lasers) with the convenience of direct semiconductor lasers like direct electrical modulation, small size, and low power consumption. Recently, first FSO experiments, employing experimental QCLs, demonstrated the predicted higher stability of the link in low-visibility situations, including strong fog as well as high dust concentration. Nonetheless, to date the high cooling requirement for QCLs restricts more general use of them, but their very fast development, recent reports of cw-operation of room-temperature QCLs as well as FSO links with TE-cooled QCLs in pulse operation, give hope for a solution to this problem.

The Detector System

Once the light reaches the receiver, it is typically collimated using a short focal length telescope or a single lens system. To optimize efficiency without sacrificing ease of alignment a compromise has to be made between a wide aperture for greater light collection and a short focal length. The concentrated light then hits the detector, which, depending on the wavelength, is either Si or InGaAs-photodiodes. Si-based devices can detect up to wavelengths of 1100 nm and InGaAs systems are typically used for the 1.5 μm region, respectively. To enhance the sensitivity of the detectors, avalanche photodiodes are preferred which internally enhance the detected signal by a factor ranging from 20 to 100. To ensure high bandwidth operation (10 MHz–10 GHz), the size of the detecting device has to be kept relatively small (20 to 100 μm) avoiding parasitical capacitance effects – but raising the requirement on the detecting optics.

The sensitivity of these NIR detectors is typically limited by the shot-noise, which is due to statistical fluctuations of the received phonons and scales with the square root of its number. For practical purposes the internal noise of the detector is quantified using the corresponding amount of incident optical power leading to a comparable signal. The values for this noise equivalent power (NEP) can range from microwatts to tens of nanowatts. Other sources for detector noise can include a background current from the detector–amplifier combination, typically referred to as Johnson noise.

Mid-infrared detectors are additionally objected to strong background radiation due to thermal emission, which peaks around the 10 μm at temperature of 300 K. The use of additional cold filters and high-resolution spectral filters can help to overcome this restriction, but still the sensitivity of those detectors is lacking compared to NIR systems.

For communication system the noise is more commonly quantified as bit error rate (BER), quantifying the average percentage of wrongly received bits (submitted ‘1’, detected ‘0’ or vice versa). A BER greater than 10^{-9} is usually referred to as an error-free system, as the residual errors can be corrected employing forward error correcting algorithms. In contrast, the performance of FSO systems can more easily be measured in its signal-to-noise ratio (SNR). Following standard communication theory, a peak SNR of 12 and an average SNR of 6 is required to achieve a BER of 10^{-9}, guaranteeing error-free communication. Consequently range limits for FSO links are typically based on $\text{SNR} = 6$.

Link Budget and FSO Range Equation

Classical link budget estimation is a commonly used tool to access the performance of FSO systems. To take into account the losses due to atmospheric absorption, scattering, turbulence, and beam spreading, as well as optical losses in the used receiver and emitter optics, they are deducted from the starting power emitted from the FSO light source. The estimated intensity at the detector is then compared with the intensity needed to establish error-free communication (for example $\mathrm{SNR} = 6$), the calculated difference is the link margin of the specific system, i.e., the amount of additional losses under which the FSO link will still be working.

Comparing this number to losses from nonpredictable fluctuations (like heavy rain or fog) gives an insight under which implications the link will fail. Using weather station data, the frequency of such extremely low-visibility occurrences can be obtained and a number for the reliability of the FSO link be estimated. Typical well-installed FSO systems estimate very high reliabilities, between 99.9% and 99.999%, which have been obtained in installation and verified in long-term measurements.

Another way to estimate the performance for a given system is based on the FSO range equation, where the received power on the detector (P_R) is calculated to

$$P_\mathrm{R} = P_\mathrm{E}\frac{D_\mathrm{R}}{(D_\mathrm{E} + L\theta)^2}TK\exp[-\alpha L] \qquad [6]$$

T denotes the optical losses of the transmission and receiver system, and K denotes additional losses for incoherent lights sources and is given by the ratio of LED emitting area to detector area, and is $K = 1$ for laser light sources. This equation can also be used to estimate losses for different weather situations and obtain the maximum range L of a specific FSO system.

Recent Research and Future Considerations

Existing FSO systems have impressively demonstrated their versatility and stability, as well as their seamless integration into existing networks, on multiple occasions. A prime example is the re-establishment of communication links between Merrill–Lynch Brokerage and Wall Street in New York, in the aftermath of the terrorist attack on September 11th, which destroyed one of the central fiber optic hubs in downtown Manhattan. The installation of a commercial FSO system by Terabeam ensured a fast replacement and a stable continuation of their work.

The demonstrated performance of such links compares to standard fiber-based links. The inclusion of wavelength division multiplexing as well as other standard or nonstandard techniques in FSO systems proves the strengths of a system, which is based on identical hardware for emitter and detectors as fiber-based networks. Nonetheless, FSO allows a multitude of applications not possible in fibers, which current research projects are targeted at. This includes, for example, long wavelength FSO communication systems, continuously ground-satellite links and free-space quantum communication for extreme secure data transmission – to list only a few of the possibilities. One very obvious example is extreme wavelength division multiplexing, which uses one link operating in all atmospheric windows at the same time. Such a FSO system would not only allow very high data rates and extreme stability against weather effects, but could also employ new kinds of wavelength-based modulation and encoding schemes increasing the security of the data link. Concluding the actual state of the FSO system as well as ongoing research, free space optical communication has all the ingredients needed to be one of the mayor key ingredients of future networks – and based on the increasing demand of bandwidths they will contribute strongly.

List of Units and Nomenclature

c	speed of light
C_n	refractive-turbulence structure coefficient
D_E	diameter of the emitting optics
D_R	diameter of the receiving optics
I	intensity
L	range (i.e., distance between emitter and detector optics)
m	mass
M^2	laser-mode structure parameter
N_s	concentration
P_E	emitted power
P_R	received power
q	charge
T	optical losses of the transmission and receiver system
V	visibility
α	extinction coefficient
ε_0	dielectric constant
θ	divergence of the light beam
λ	wavelength
λ_0	natural oscillation wavelength
σ_s	scattering cross-section

See also

Environmental Measurements: Doppler Lidar; Optical Transmission and Scatter of the Atmosphere. **Imaging:** Infrared Imaging; Lidar.

Further Reading

Andrews LC and Phillips RL (1998) *Laser Beam Propagation through Random Media*. Bellingham, CA: SPIE Optical Engineering Press.

Begley DL (ed.) (1991) *Selected Papers on Free-Space Laser Communications*. SPIE Milestone Series. Bellingham, CA: SPIE Optical Engineering Press.

IEE Proceedings Optoelectronics, *Special Issue on Free Space Optical Communications*. December 1996.

Jha AR (2000) *Infrared Technologies*. New York: John Wiley & Sons.

Killinger D (2002) *Free Space Optics for Laser Communications Through the Air*. Washington: Optics and Photonics News, Optical Society of America, p. 36.

Measures R (1984) *Laser Remote Sensing*. New York: John Wiley & Sons.

Mecherle GS (ed.) (2003) *Free-Space Laser Communication Technologies XV*. Bellingham, CA: SPIE Optical Engineering Press.

Weichl H (1990) *Laser Beam Propagation in the Atmosphere*. Bellingham, CA: SPIE Optical Engineering Press.

Willebrand H and Ghuman BS (2001) *Free-Space Optics: Enabling Optical Connectivity in Today's Networks*. Indianapolis, IN: SAMS.

Wolfe WL and Zissis GJ (1978) *The Infrared Handbook*. Ann Arbor: Enviromental Research Institute of Michigan.

Zuev VE (1988) *Laser Beams in the Atmosphere*. New York: Consultant Bureau.

Lightwave Transmitters

J G McInerney, National University of Ireland-Cork, Cork, Ireland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical fiber telecommunications has changed human society forever, providing the capacity for affordable and ubiquitous communication. It provides data rates and transport economies far in excess of those available using purely electronic means. It is doubtful whether the Internet and worldwide web, or the vast infrastructure of wireless cellular telephony, would be viable without optical fiber technology. Its rapid development and acceptance has been driven largely by contemporaneous successes in manufacturable low-loss optical fiber cables, sensitive pin-FET photoreceivers, and reliable high-performance laser diode-based transmitters. The earliest developments in silica glass fibers at Standard Telecommunication Laboratories, UK, (then part of the US-based ITT Corporation) and Corning Glass Works (USA) in the 1960s and 1970s, were pivotal in determining the directions of modern fiber technology, as were later key inventions of rare-earth doped fiber amplifiers at the University of Southampton (UK) and AT&T Bell Laboratories (USA) in the 1980s and early 1990s. However, perhaps the greatest contributors to the success of fiber optics have been semiconductor injection lasers, or laser diodes, which in various forms have made up the vast majority of all fiber optic transmitters, and the entirety of long-haul transmitters, as well as pump sources for the doped-fiber amplifiers which enable modern networks. The fascinating story of the development of fiber optics is to a large extent driven by the dramatic progress in the development of high-performance, reliable semiconductor lasers. These emitted at wavelengths near 1300 and 1550 nm, which respectively correspond to the dispersion and attenuation minima of single-mode silica optical fibers.

Semiconductor Laser Principles

Semiconductor lasers were first demonstrated in research laboratories at General Electric, IBM Corporation and the MIT Lincoln Laboratory (all USA) as early as 1962, although it took almost two decades for the basic science and engineering of materials, fabrication, reliability, and performance design issues to be developed sufficiently for their use in practical communication systems. Early successes were obtained using the GaAs/AlGaAs lattice-matched material system, in which a lightly doped GaAs or ternary compound AlGaAs active layer is sandwiched between two lattice-matched heterojunctions with n- and p-doped AlGaAs layers with higher Al fractions than the active layer, so that their refractive indices are lower and their bandgaps higher, providing optical and charge-carrier confinement. In all cases the material is epitaxially grown, meaning that the entire laser chip forms a single crystal. The gain, and hence the laser emission, occurs at the direct bandgap of the active layer, at wavelengths in the range 750–870 nm depending on the Al fraction.

Later evolutions used the quaternary compound GaInAsP clad by InP guiding layers, where the In and P fractions are chosen to match the lattice constant to the InP substrate.

In general, optical gain in a laser diode is generated by creating an electron-hole plasma in the vicinity of the forward-biased junction, a situation corresponding to population inversion in a conventional laser, and with sufficient forward current the material becomes transparent, in that the gain exactly equals the absorption and scattering losses, at a particular wavelength. When this arrangement is enclosed within a suitable optical cavity, and the forward current is increased further, the system begins to lase, that is to oscillate continuously to produce coherent optical radiation at a wavelength which satisfies two basic conditions: it must be within the set of wavelengths at which the material produces sufficient gain, and it must be close to one of the electromagnetic modes at which the optical cavity is resonant. These conditions, which define lasing threshold, are characterized by the equality of the optical gain and the total losses, that is the material losses (absorption, scattering, and free-carrier plasma) and the cavity losses which include the light output.

Early laser diodes in both the GaAs/AlGaAs and GaInAsP/InP systems were of the edge-emitting type, in which the light is emitted from the edge of the laser chip, perpendicular to the growth direction in the plane of the wafer. Although this geometry complicates laser production flow, particularly the testing function which requires that the wafer be scribed into bars to define the laser output facets, edge-emitting lasers (EELs) make up the vast majority of optical fiber transmission sources. An alternative laser diode structure is the vertical cavity surface-emitting laser (VCSEL), in which emission occurs in the growth direction perpendicular to the plane of the wafer. VCSELs offer major advantages in spectral stability, beam quality, manufacturability and cost, but their output powers are low (a few mW) and they are not yet available at the key telecommunication windows around 1300 nm and 1550 nm, due to difficulty in forming the necessary high-reflectivity Bragg mirrors in the GaInAsP/InP material system. Major initiatives are currently underway to produce long-wave VCSELs in the GaAs/AlGaAs system using InAs quantum dots, or dilute nitrides such as InGaAsN, or hybrid approaches such as InP-based gain media fused to high-reflectivity mirrors using GaAs/AlGaAs, dielectric coatings, air gaps, and others. At present, however, all long-haul optical fiber transmission is based on edge-emitting laser diodes fabricated in GaInAsP/InP.

General Structure and Requirements of Optical Fiber Communication Systems

The first optical fiber communication links were simple point-to-point affairs, consisting essentially of series-connected transmitters, fibers, and receivers. The transmitters were simple Fabry–Perot laser diodes, onto which data were encoded by direct digital modulation of the injection current at rates ~100 Mbit/s. The first commercial optical fiber link was built in 1976, a single fiber cable linking two switching centers of the Illinois Bell Telephone Co just 2.5 km apart in the Chicago metropolitan area, using 850 nm GaAs laser technology. In 1988, the first transatlantic fiber link, AT&T's TAT-8, was completed linking endpoints in New Jersey, England, and France with three fiber pairs carrying signals generated by 1300 nm GaInAsp single mode lasers. In these early systems, data were regenerated frequently by repeaters each consisting of a receiver, signal conditioner and transmitter. Each fiber in TAT-8 carried a single optical frequency modulated at 280 Mbit/s and the construction cost of the system was ~$50 k/km, resulting in an economic figure of merit of over $600 k/Mbit/s. Twenty-five years later, current systems cost the same per kilometer to build in absolute dollars despite inflation, a major effective cost reduction enabled largely by replacement of the expensive repeaters by doped-fiber optical amplifiers. Moreover, each fiber is now highly multiplexed, with the potential for hundreds of wavelengths each carrying 10 Gbit/s signals generated by 1550 nm laser transmitters, so that the unit cost has plummeted to ~$200/Mbit/s, a reduction of three and a half orders of magnitude.

In the remainder of this article, we will describe transmitters for both short- and long-haul systems where the channel spacing is only tens of GHz in the optical carrier frequency. Modern short-haul systems either feed client networks as part of bi-directional transceivers, or drive metro and local access networks connected directly by photonic switches to terminals of the long-haul systems.

DWDM Transceivers

Modern practice uses modular units containing transmitters and receivers allowing bi-directional data flow. In the send mode, data are applied to a long-haul transmitter at the local (client) source and coupled through the external fiber network to the remote long-haul receiver. In the receive mode, data arrive from a remote long-haul transmitter and are coupled (via a regenerator including signal conditioning, clock recovery, and error correcting steps) to a local short-haul transmitter leading to the client's internal network. Each transceiver card therefore contains a long-haul transmitter and receiver set (known collectively as dense wavelength division multiplexing (DWDM) transport devices) and a short-haul transmitter and receiver set (known as client interfaces or local transport devices).

Transmitter Requirements

Short-haul transmitters may be simple Fabry–Perot edge-emitting laser diodes, or vertical cavity laser diodes, or even superluminescent LEDs for sub-Gbit/s data rates. They are generally not required to be at one of the minimum-loss telecom windows near 1550 nm, as the transmission distances are short. However, as client networks grow into large metropolitan networks, it is likely that 1300 nm sources will be used to minimize dispersion. Power requirements are modest, a few mW peak, at data rates ~1–10 Gbit/s. Single mode laser emission and polarization control are not required by present day systems, although polarization-mode dispersion may limit transmission at higher data rates. Both return-to-zero (RZ) and nonreturn-to-zero (NRZ) coding may be used, and direct modulation of the laser amplitude is the norm.

For long-haul transmitters the situation is dramatically different. Operation in one of the standard erbium-doped fiber amplifier (EDFA) bands near 1550 nm is mandatory: the C (conventional) band extends from 1530–1565 nm, the S (short-wave) band from 1460–1530 nm) and the L (long-wave) band from 1565–1625 nm. In the C-band, output powers ~10 mW are generally sufficient, and powers above ~30 mW are limited by nonlinear effects such as self-phase modulation and four-wave mixing in the fiber. In the S- and L-bands, where the available gain from EDFAs is less, lasers may need to operate close to the nonlinear limit, several tens of mW, although various schemes (differential pumping, gain-flattening filters, etc.) are being evaluated to flatten the global EDFA gain spectrum.

In current practice, a single fiber utilizing DWDM, using only the C-band, can carry up to 1 Tbit/s comprising 100 channels at 10 Gbit/s on each channel, the current standard. For such performance a channel spacing of 50 GHz in optical frequency is required. Using all three bands with similar density would enable ~3 Tbit/s, which could be doubled by using 25 GHz channel spacings. Ultimately, even higher channel densities and hence overall system data rates are possible, with a practical limit ~10 Tbit/s. The channel spacing is a key parameter in that it determines the laser design, specifically its spectral stability and linewidth, and the overall transmitter design in that laser chirp (modulation induced dynamic spectral shift) must be less than half the channel spacing. In practice, only single-wavelength and coarse wavelength division multiplexing (CWDM) systems may be modulated directly. All modern DWDM systems require external modulation, for example using electro-absorption or Mach–Zehnder interferometric devices outside the laser cavity. For the latter cases, stabilization of the laser wavelength is required for example by on-chip gratings to form distributed feedback (DFB) or distributed Bragg reflector (DBR) lasers, or by external fiber gratings.

Directly Modulated Lasers

Direct modulation of semiconductor lasers is convenient and effective: by modulating the laser injection current, one modulates the carrier density and hence the optical gain, resulting in modulation of the laser output up to ~10 Gbit/s. The actual modulation bandwidth is determined by interactions between photons and carriers, whose respective decay lifetimes, τ_s and τ_p, are determined by cavity losses and total recombination rates. The simplest form of such interactions is described by the photon and carrier rate equations for the injected carrier density N and photon density S in a single lasing mode:

$$\mathrm{d}N/\mathrm{d}t = J/ed - gNS - N/\tau_s \qquad [1]$$

$$\mathrm{d}P/\mathrm{d}t = gNS + \beta N/\tau_s - S/\tau_p \qquad [2]$$

where J is the injected current density, e the electronic charge, d is the thickness of the active region (hence J/ed is the rate of injection of carriers per unit volume), g is the gain coefficient per unit length and β is the fraction of the spontaneous emission coupled into the lasing mode, typically $\sim 10^{-2}$–10^{-5} for edge-emitting lasers (product of geometric and spectral overlap factors). These equations simply state that the rate of change of the carriers or photons is given by the rate of generation less the loss rate. Additional terms are required in the presence of optical feedback or coupling (in which case the photon density is replaced by the complex amplitude and phase of the optical electric field) or for extremely rapid modulation where the traveling wave nature of the disturbances in the photon fields is significant. These so-called traveling-wave rate equations for the photons are of the form:

$$\mathrm{d}S_+/\mathrm{d}t + c\mathrm{d}S_+/\mathrm{d}z = gNS_+ + \beta N/\tau_s \qquad [3]$$

$$dS_-/dt - c dS_-/dz = gNS_- + \beta N/\tau_s \quad [4]$$

with the same carrier rate equation as [1] using the total photon number S made up of the forward-traveling component S_+ and the backward-traveling component S_- : $S = S_+ + S_-$.

Both sets of rate equations are based on approximations such as homogeneous gain broadening, neglect of transverse field effects, and diffusion. These are valid in most situations but care is required when analyzing lasers with large transverse apertures, or when ultrashort (picosecond) pulses are involved.

Small-Signal Modulation

Small-signal modulation may be analyzed by a linear perturbation analysis of the rate equations, leading to a conjugate pair of poles in the response function, with damped relaxation oscillations at frequency:

$$f_R = (1/2\pi)\surd(gS_0/\tau_p) \quad [5]$$

or, in terms of the injected current density J (assuming $S \sim G(J - J_{th})/ed$ with Γ the electromagnetic confinement factor of the mode):

$$f_R = (1/2\pi)\surd[\Gamma g(J - J_{th})/ed]$$

f_R can be regarded as the resonant frequency for the interaction between the carriers and photons. As a practical matter, lasers can be modulated up to $\sim 2f_R$ but the modulation response rolls off rapidly with increasing frequency above f_R. Using explicit expressions for the threshold gain, we can write f_R as:

$$f_R = (1/2\pi)\surd[(GN_T g\tau_p + 1)(J/J_{th} - 1)/\tau_s\tau_p] \quad [6]$$

where N_T is the transparency carrier density $\sim 10^{18}\,\text{cm}^{-3}$. f_R can take values in excess of 10 GHz for a well-designed laser. It should be noted, however, that high modulation bandwidth almost always requires high differential gain dg/dN and short τ_p. Increasing dg/dN requires p-doping (which increases optical loss) and/or some special quantum-confining structure such as wells, wires, or dots. Decreasing τ_p inevitably leads to greater optical loss and thus a higher threshold.

The damping rate of the relaxation oscillations is also important in limiting modulation bandwidth, and also (when increased) in reducing the sensitivity of the laser to optical feedback. For bulk or quantum well lasers, the condition for critical damping is $A^2 = 4B$ with $A = (S/g\tau_s) - \sigma[N - N_T]/g\tau_p$ and $B = \sigma[1 + (S_0/g\tau_s) - (1 - \beta)(N - N_T)]$. For quantum dot lasers there are additional damping terms due to carrier transport and thermalization which may restrict small-signal modulation bandwidths to a few GHz.

Experimentally, small-signal modulation properties may be determined using a simple sampling oscilloscope, low-noise tunable signal generator and spectrum analyzer. A combination of these elements with automated frequency sweeping may be found in a scalar network analyzer acting as an *s*-parameter test set. The modulated laser is connected to port 1 and a high speed photodetector connected to port 2, then a swept-frequency measurement of the transfer characteristic s_{21} is performed. In addition to the limitations on modulation response due to the carrier-photon resonance, practical lasers are limited by RC parasitics in the laser chip (junction impedance) and its package. For the highest modulation speeds, packages need to be designed as microwave transmission line components with effective impedance matching and low back reflections, as characterized by the voltage standing wave ratio (VSWR).

Large-Signal Modulation

Large-signal direct modulation can be analyzed by numerical integration of the rate equations. In general, its results are beyond the scope of this review, but for effective high-speed response, digital modulation of laser diodes should be carried out with a pre-bias close to threshold. Modulation bandwidth also increases with laser power, which is limited for systems considerations by fiber nonlinearities, and for reasons of laser reliability. In pulse code modulation, care must be taken that the laser is near critical damping, to minimize thermal patterning effects due to long strings of ones (high power) or zeros (low power). Experimentally, large signal modulation is analyzed by constructing eye diagrams, in which pulse traces on a fast oscilloscope are continuously overlaid when the laser is modulated using pseudorandom binary pulses. When the signal quality is high, the high and low digital levels are easily distinguishable, resulting in an open 'eye' in the accumulated traces.

Requirements for Externally Modulated Lasers

The requirement for external modulation occurs when the laser chirp exceeds half the desired channel spacing in the communication system. Chirp occurs due to changes in the refractive index, and hence the optical phase, during modulation. This dynamic phase shift then results in an instantaneous frequency shift.

For direct modulation we have instantaneous wavelength

$$\lambda(t) = \lambda(0)(\mu(t)/\mu(0) \quad [7]$$

Where $\mu(t)$ is the refractive index at time t. μ shifts with carrier density N due to combinations of several factors (free carrier plasma dispersion, thermal bandgap shrinkage, bandgap renormalization, dynamic Burstein–Moss effects) which give $\mathrm{d}\mu/\mathrm{d}N \sim -3 \times 10^{-20}\ \mathrm{cm}^3$, which for large signal digital modulation can result in tens of GHz. The actual degree of chirp depends on the so-called antiguiding or linewidth enhancement factor a given by

$$\alpha = -2k_0(\mathrm{d}\mu/\mathrm{d}N)/(\mathrm{d}g/\mathrm{d}N) \quad [8]$$

where $k_0 = 2\pi/\lambda_0$ is the free-space wavenumber. α as defined is positive, typically in the range 2–7 depending on the material, operating carrier density, and wavelength relative to the gain peak. Distributed feedback (DFB) or distributed Bragg reflector (DBR) lasers, which use integrated gratings to control the lasing wavelength, can have lower chirp by detuning from the gain peak but therefore are likely to require careful temperature stabilization. Quantum dot lasers, based on 3D nanoclustered active regions, have the potential for very low chirp, narrow linewidths, and reduced wavelength shifts, so that directly modulated DWDM transmitters may be possible.

Integration of laser diodes with electro-absorption or Mach–Zehnder type modulators is achieved in the transmitter optical subassembly and may in some cases be accomplished by monolithic integration on the same chip. Using separate modulators allows each device to be optimized independently but requires optical assembly, alignment, and retention. Mach–Zehnder modulators in X-cut lithium niobate, for example, have essentially zero chirp and can operate to 40 Gbit/s and above, with dynamic extinction ratios (ratio between fully on and fully off) of ~20 dB. Integrated semiconductor M-Z modulators have chirp an order of magnitude less than those of directly modulated lasers, so that channel spacings ~25 GHz are possible in DWDM systems with suitable temperature and wavelength controls. Although the details of such modulators are beyond the scope of this article, the laser requirements are to generate ~ 10 mW of continuous power with stable center wavelength and narrow linewidth. Such lasers are usually mounted in hermetic packages (e.g., the current 14-pin butterfly standard) with integrated thermo-electric cooler, power monitor photodiode, an optical isolator to suppress optical backreflections which cause instabilities and self-pulsing, and optional wavelength locking optics.

Reliability of Lasers in Fiber Optic Systems

From the early days, when laser diode lifetimes were measured in seconds even at cryogenic temperature, enormous progress has been made in achieving materials purity and reducing crystalline defects. Today's fiber optic laser transmitters have projected lifetimes of decades. In common with electronic devices, diode lasers fail at a rate given by a 'bathtub' curve, that is the failure rate $r(t)$ defined as the probability of failure per unit time at time t, has relatively high values at low t (early failures) and high t (wearout failures) and very low values in between. In terms of the population of lasers $n(t)$ we have:

$$r(t) = (-1/n(t))\,\mathrm{d}n(t)/\mathrm{d}t \quad [9]$$

If Δn is the number of samples which fail in time Δt, then assuming Δt begins at $t = 0$, the effective or average failure rate r_{eff} over the interval is

$$r_{\mathrm{eff}}(t) = \Delta t \Delta n/n(0) \quad [10]$$

In reliability science it is customary to define r_{eff} in FITs (failures integrated in time) with the time-span chosen to yield statistically significant numbers. For electronic and photonic devices, it is customary to select the time interval $\Delta t = 10^9$ h (1 billion operating hours), so that if 1% of the devices fail in 10 years ($\sim 10^5$ hours) we have $r_{\mathrm{eff}} \sim 100$ FITs, which is the order of magnitude required by modern fiber optic laser sources.

In terms of actual statistical models, failure rates can be estimated using failure probability density functions $f(t)$. This is related to $r(t)$ by $f(t) = r(t)S(t)$ where $S(t)$ is the cumulative probability of surviving until t. When $r(t)$ is nearly constant, as in early failures due to material defects or process errors, the statistics are approximately exponential:

$$f(t) + (1/\tau)\exp(-t/\tau) \quad [11]$$

or Weibull-distributed (an exponential is a Weibull distribution with $\beta = 1$):

$$f(t) = (\beta/t^{\beta})t^{b-1}\exp[-(t/\tau)^{b}] \quad [12]$$

but this description is not suited to wearout failures for which $f(t)$ shows a significant increase as the population ages. For such cases, the lognormal distribution is often applicable:

$$f(t) = (1/\sigma t\sqrt{}(2\pi))\exp[-(\ln t - \ln \tau)^2/2\sigma^2] \quad [13]$$

where in each case τ is approximately the mean time to failure (MTTF).

Laser diodes undergo standardized qualification tests to demonstrate sufficient reliability prior to being used in commercial systems. Operationally, failure statistics must be tabulated and the best fit obtained. Burn-in procedures are used to screen early failures. Chip and module failures should be distinguished clearly, as the latter includes many additional factors such as thermal and power management, light coupling, mechanical or chemical integrity.

Given that effective lifetimes of decades are required, it is clearly necessary to accelerate aging to produce statistically meaningful failure rates in reasonable times $\sim 10^3$ h. For the most common modes of laser chip degradation, due to recombination-induced aggregation of defects in the crystalline epitaxial material, these are thermally activated and current driven, so that it is customary to use a modified Arrhenius law at temperature T:

$$\tau \sim (1/J^n)\exp(E_a/k_B T) \qquad [14]$$

where J is the operating current density, n is an index ~ 2, E_a is the activation energy, and k_B is Boltzmann's constant. In terms of thermal acceleration, we have a factor $F = \tau(T_A)/\tau(T_B)$ with:

$$F = \exp[(E_a/k_B)(1/T_A - 1/T_B)] \qquad [15]$$

Typical values of E_a for laser diodes are ~ 1 eV so that acceleration factors $\sim 10^3$ are possible.

Finally, it should be noted that laser diodes are generally subject to catastrophic failure in the event of overdriving or static discharge, the failure mode being thermal facet damage at $\sim 1-10$ MW/cm^2 for continuous-wave operation, the exact value depending on the material, surface preparation and specifically surface state absorption and its temperature coefficient.

Conclusions

Laser diodes are ideal sources for optical fiber communication systems and have propelled the development of fiber optics from its origins in the 1960s to the present day. They are compact, rugged, efficient, and reliable sources of light at key wavelength ranges such as 1300–1310 nm (short haul high speed links) and 1500–1600 nm (long haul amplified systems). They are capable of direct modulation at gigabit rates for simple systems but require external modulation and careful wavelength control for dense wavelength division multiplexed terabit systems. Transmitter lasers for real systems must satisfy stringent reliability conditions.

See also

Lasers: Edge Emitters; Semiconductor Lasers. **Semiconductor Physics:** Quantum Wells and GaAs-based Structures.

Further Reading

Telcordia Technologies (formerly Bellcore): document family FR-796 on Reliability and Quality Generic Requirements for telecommunications equipment. Latest issue is 003 dated Jul 2003. The specific document related to laser reliability is GR-468 – Generic Reliability Assurance Requirements for Optoelectronic Devices used in Telecommunications Equipment. Standards for other network photonic, electronic and mechanical components may be found in the document family FR-2063 Network Equipment-Building System Family of Requirements, issue 003 dated Feb 2003 and specifically FR-357 – Network Equipment-Building System Family of Requirements: Component Design for Reliability.

Adams MJ and Thomas B (1977) Detailed calculations of transient effects in semiconductor injection lasers. *IEEE Journal of Quantum Electronics* QE-13: 580.

Agrawal GP (2002) *Fiber Optic Communication Systems*, 3rd edn. New York: Wiley.

Alferov ZhI, Andreev VM, Portnoi EL and Trukan MK (1970) AlAs-GaAs heterojunction injection lasers with a low room-temperature threshold. *Soviet Physics – Semiconductors* 3: 1107.

Basov NG, Krokhin ON and Popov YuM (1961) Production of negative-temperature states in p-n junctions of degenerate semiconductors. *Soviet Physics – JETP* 13: 1320.

Bernard MGA and Duraffourg G (1961) Laser conditions in semiconductors. *Physica Status Solidi* 1: 699.

Bhattacharya P (1996) *Semiconductor Optoelectronic Devices*, 2nd edn. Englewood Cliffs, NJ: Prentice-Hall.

Cheng J and Dutta NK (eds) (2000) *Vertical Cavity Surface-Emitting Semiconductor Lasers: Technology and Applications*. London: Taylor & Francis.

Chuang S-L (1995) *Physics of Optoelectronic Devices*. New York: Wiley.

Coldren LA and Corzine SW (1995) *Laser Diodes and Photonic Integrated Circuits*. New York: Wiley.

Dupuis RD (1987) An introduction to the development of the semiconductor laser. *IEEE Journal of Quantum Electronics* QE-23: 651.

Fukuda M (1991) *Reliability and Degradation of Semiconductor Lasers and LEDs*. Norwood, MA: Artech House.

Fukuda M (1998) *Optical Semiconductor Devices*. Wiley.

Guekos G (ed.) (1998) *Photonic Devices for Telecommunications*. New York: Springer.

Hall RN, Fenner GE, Kingsley JD, Soltys TJ and Carlson RO (1962) Coherent light emission from GaAs junctions. *Physical Review Letters* 9: 366.

Hayashi I, Panish MB, Foy PW and Sumski S (1970) Junction lasers which operate continuously at room temperature. *Applied Physics Letters* 17: 109.
Holonyak N Jr and Bevacqua SF (1962) Coherent (visible) light emission from Ga(As1-xPx) junctions. *Applied Physics Letters* 1: 82.
Ito R, Nakashima H, Kishino S and Nakada O (1975) Degradation sources in GaAs-AlGaAs double-heterostructure lasers. *IEEE Journal of Quantum Electronics* QE-11: 551.
Kaminow IP and Li T (eds) (2002) *Optical Fiber Telecommunications IV (two parts)*. Amsterdam: Elsevier.
Kaminow IP and Koch TL (eds) (1997) *Optical Fiber Telecommunications III (two parts)*. London: Academic Press.
Kapon E (1998) *Semiconductor Lasers, (two parts)*. London: Academic.
Kartalopoulos SV (1999) *Introduction to DWDM Technology*. New York: Wiley.
Kartalopoulos SV (1999) *Understanding SONET/SDH and ATM*. IEEE Press.
Kasap SO (2001) *Optoelectronics and Photonics: Principles and Practices*. Englewood Cliffs, NJ: Prentice-Hall.
Kazovsky L, Benedetto S and Willner A (1996) *Optical Fiber Communication Systems*. Norwood, MA: Artech House.
Keiser G (1991) *Optical Fiber Communications*. New York: McGraw-Hill.
Kressel H and Lockwood HF (1974) A review of gradual degradation phenomena in electroluminescent diodes. *Journal de Physique* 35: C3–223.
Lasher G and Stern F (1964) Spontaneous and stimulated recombination radiation in semiconductors. *Physical Review* 133: A553.
Milonni PW and Eberly JH (1988) *Lasers*. New York: Wiley.
Morthier G and Vankwikelberge P (1997) *Handbook of Distributed Feedback Laser Diodes*. Norwood, MA: Artech House.
Nathan MI, Dumke WP, Burns G, Dill FH Jr and Lasher G (1962) Stimulated emission of radiation from GaAs p-n junctions. *Applied Physics Letters* 1: 62.
Numai T (2004) *Fundamentals of Semiconductor Lasers*. New York: Springer.
Paoli TL (1977) Changes in the optical properties of cw (AlGa) as junction lasers during accelerated aging. *IEEE Journal of Quantum Electronics* QE-13: 351.
Paoli TL and Ripper TE (1970) Direct modulation of semiconductor lasers. *Proceedings of IEEE* 58: 1457.
Pearsall TP (2003) *Photonics Essentials: An Introduction with Experiments*. New York: McGraw-Hill.
Piprek J (2003) *Semiconductor Optoelectronic Devices: Introduction to Physics and Simulation*. London: Academic.
Quist TM, Rediker RH, Keyes RJ, Krag WE, Lax B, McWhorter AL and Zeiger HJ (1962) Semiconductor maser of GaAs. *Applied Physics Letters* 1: 91.
Reinhart FK, Hayashi I and Panish MB (1971) Mode reflectivity and waveguide properties of double-heterostructure injection. *Lasers* 42: 4466.
Saleh BEA and Teich MC (1991) *Fundamentals of Photonics*. New York: Wiley.
Senior JM (1992) *Optical Fiber Communications*, 2nd edn. Engelwood cliffs, NJ: Prentice-Hall.
Siegman AE (1986) *Lasers*. University Science Books.
Verdeyen JT (1994) *Laser Electronics*, 3rd edn. Englewood Cliffs, NJ: Prentice-Hall.
Yariv A (1989) *Quantum Electronics*, 3rd edn. New York: Wiley.
Zachos TH and Ripper JE (1969) Resonant modes of GaAs junction lasers. *IEEE Journal of Quantum Electronics* QE-5: 29.

Local Area Networks

E Wong, University of Melbourne, Melbourne, VIC, Australia

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Local area networks (LANs) are privately owned networks that are used to carry internal traffic loads within an organization. A LAN may exist on many levels categorized by its application and speed. This is illustrated in Figure 1 whereby, at the simplest requirement, a low-speed LAN may be used to interconnect a cluster of personal computers and workstations. Such a scenario may exist in a department within a university campus, or a building within a technology park. If need be, these individual departmental or building LANs may be interconnected using a moderately high-speed backbone LAN. The backbone LAN may also provide interconnection to servers which support mass storage devices that are shared by the individual lower speed LANs. In larger organizations, a much higher speed LAN is linked to the backbone LAN to support bulk data transfer between mainframes, supercomputers, and other office equipment.

The common transmission mediums for traditional low-speed LANs are coaxial cable and twisted pairs. High-speed backbone LANs advocate the use of the optical fiber. The continuing progress in fiber-optic technology and devices, and the availability of appropriate standards have given rise to LANs that can span distances of hundreds of kilometers or more, and that operate at data rates in the order of hundreds to thousands of megabits per second (Mb/s).


High-speed LAN supporting supercomputers mainframes
Moderately high-speed backbone LAN
Storage area network
Moderately low-speed LAN existing within a building

Figure 1 Interconnection of local area networks (LANs).

The increase in demand, to extend LAN capabilities towards higher data rates and across larger geographical areas, is fueled primarily by the need to provide new bandwidth intensive services such as multimedia teleconferencing, image processing, and streaming video, to a significantly higher number of end-users.

This article focuses on three existing fiber-optic LAN standards, namely Ethernet, Fiber Distributed Data Interface (FDDI), and Distributed Queue Dual Bus (DQDB). While the current uses of FDDI and DQDB are not as widespread as Ethernet, both standards have significantly contributed to the initial deployment of fiber-optics for LAN applications, with standard-based products still commercially available. In general, standards are required to ensure interoperability between components and equipment from different vendors and suppliers. Two key features are addressed by the standards: the physical topology, and the medium access control (MAC) protocol. A network's physical topology defines the way in which the users, or nodes, are interconnected to each other and to the transmission medium. Common optical LAN topologies are the star (e.g., Ethernet), bus (e.g., DQDB and Ethernet), and ring (e.g., FDDI). In comparison, the MAC protocol controls network access such that its capacity is efficiently and fairly shared amongst all nodes.

Access control can be either centralized or decentralized. In the former, a node wishing to transmit must wait until it receives permission from a controller, whereas in the latter, nodes collectively determine the transmission order. Further, capacity allocation to each node can be either synchronous or asynchronous. The synchronous approach guarantees a specific capacity to each node, e.g., using time division multiple access (TDMA), whereby nodes are allowed to transmit only during a designated time slot. In contrast, the asynchronous approach allows capacity to be dynamically allocated to each node. The asynchronous approach can be further categorized into round robin, reservation, and contention schemes. With round robin, nodes take it in turn to transmit in a cyclic manner and a node may transmit up to a maximum amount of data during its turn. With the reservation scheme, time on the medium is divided into slots, and a node wishing to transmit must reserve future slots by transmitting additional control information into the network. With the contention scheme, nodes randomly access the network. The Ethernet standard, discussed in the following section, is based on the contention scheme.

Ethernet

Overview

The IEEE (Institute of Electrical and Electronics Engineers) 802.3 standards committee first standardized 10 Mb/s Ethernet in 1985. It is now the most widely used technology for high-speed LANs, with standards extended to cater for operating speeds of 100 Mb/s, 1 Gb/s and 10 Gb/s, and encompassing the use of the optical-fiber transmission medium. Low-speed 10 Mb/s and 100 Mb/s Ethernet LANs use the carrier-sense multiple access with collision detection (CSMA/CD) MAC protocol, whereas a switched technique is used for the 1 Gb/s and 10 Gb/s options.

In CSMA/CD, a node wishing to transmit an Ethernet frame first listens to the transmission medium by detecting the presence of signals on the channel (i.e., carrier-sense). This process allows the node to determine if another transmission is in progress. If the medium is in use, the node continues to listen until the medium is idle, and then transmits immediately. While transmitting, the node continues to listen to the medium. It may happen that two or more nodes may attempt to transmit at the same time. If this occurs, there will be a collision, and data from both transmissions will become garbled.

A collision can be indicated by a combined signal that exceeds a predefined CD threshold voltage at the carrier-sense receiver, taking into account the collision between frames from nodes that are located furthest apart. If a collision is detected during transmission (i.e., collision detection), the transmitting node ceases transmission and proceeds to transmit a brief jamming signal to notify all nodes of the collision. After transmitting the jamming signal, the node must back off before attempting to transmit the same data frame again. The back-off period is random, and is determined by a binary exponential back-off algorithm. Every time a node attempts to retransmit, the mean value of the random back-off period is doubled until the tenth attempt. After that the node is allowed to retransmit a further six times with the same mean random delay before discarding the frame and reporting an error to higher control layers.

The transmission medium remains unusable when frames collide but only until the collision is detected. As such, the minimum transmission time of a frame must be longer than the maximum propagation delay of the network so that collision is detected prior to the end of transmission. If shorter frames are used, then collision detection does not occur, and CSMA/CD thus exhibits the same performance as its less efficient predecessor protocol, CSMA. Accordingly, the CSMA/CD standards specify a minimum frame length and maximum network size, which place fundamental limitations on the practical application of a pure CSMA/CD LAN.

IEEE 802.3 10 Mb/s Ethernet

In 1993, the IEEE 802.3 committee extended the 10 Mb/s Ethernet standard to include the optical-fiber transmission medium. The standard notation of this option is 10BASE-F. Each transmission link comprises a pair of graded-index 62.5 μm core multimode optical fibers (MMF), one for each direction of transmission. The transmission wavelength is 850 nm. 10BASE-F can be further categorized into three specifications. The first, denoted 10BASE-FP (fiber passive star), specifies a broadcast star topology that can interconnect up to 33 nodes and repeaters. Each of these devices is attached to a passive star coupler via two optical-fiber links with distances up to 500 m. The passive star coupler splits the optical power of any incoming frame equally amongst its output links, allowing all nodes or repeaters in the network to receive the frame, albeit at a lower optical power level.

The second and third specifications, denoted 10BASE-FL (fiber link) and 10BASE-FB (fiber backbone) respectively, define point-to-point links over distances of up to 2 km. 10BASE-FL supports both nodes and repeaters, whereas 10BASE-FB supports only repeaters. A repeater is a device that detects the optical signals on its incoming link, performs electrical signal regeneration, and then optically retransmits the signals on its output link. Repeaters used in 10BASE-FB have an additional function in which the detected signals are retimed with a local clock before being retransmitted. This prevents the propagation of timing distortions, allowing distances of up to 15 cascaded repeater links to be implemented. The characteristics of the three specifications for 10BASE-F, along with the 100 Mb/s and 1 Gb/s specifications to be discussed in the following sections, are summarized in Table 1.

IEEE 802.3 100 Mb/s Ethernet (Fast Ethernet)

Fast Ethernet refers to the standard developed by the IEEE 802.3 committee to provide low-cost, Ethernet-compatible LANs operating at 100 Mb/s. The optical-fiber transmission medium option is denoted 100BASE-FX. Originally defined for FDDI (covered in the section on FDDI below), 100BASE-FX specifies the use of two 62.5 μm MMF links, each operating at a unidirectional rate of 100 Mb/s. While 10 Mb/s Ethernet can only operate in half-duplex mode, whereby a station can either transmit or receive a frame but cannot do both simultaneously, Fast Ethernet can operate in either half- or full-duplex modes. A node operating in full-duplex mode can simultaneously transmit and receive data frames.

In order to deploy full-duplex Fast Ethernet, all repeaters must be replaced with switching hubs. Figure 2a illustrates a repeater located in the central point in an active star topology. Each node is attached to the repeater via two optical links. The repeater retransmits frames received from any one of its input

Table 1 Summary of IEEE 802.3 physical and MAC layer specifications for 10 Mb/s, 100 Mb/s and 1 Gb/s Ethernet

	10BASE-FP	*10BASE-FL*	*10BASE-FB*	*100BASE-FX*	*1000BASE-SX*	*1000BASE-LX*
Data rate	10 Mb/s	10 Mb/s	10 Mb/s	100 Mb/s	1 Gb/s	1 Gb/s
Transmission wavelength	850 nm	850 nm	850 nm	850 nm	850 nm	1310 nm
Transmission medium	62.5 µm MMF pair	62.5 µm MMF pair	62.5 µm MMF pair	62.5 µm MMF pair	50 µm or 62.5 µm MMF pair	10 µm SMF, 50 µm or 62.5 µm MMF pair
MAC protocol	CSMA/CD (half duplex)	CSMA/CD (half duplex)	CSMA/CD (half duplex)	CSMA/CD (half duplex) Switched (full duplex)	CSMA/CD (half duplex) Switched (full duplex)	CSMA/CD (half duplex) Switched (full duplex)



Figure 2 (a) Shared LAN repeater. (b) Collision at a shared LAN repeater due to simultaneous transmission of frames. (c) LAN switch (adapted from William S (2004) *Data and Computer Communications*, 7th edn, Ch. 15–16. Upper Saddle River, NJ: Pearson Education).

links to all of its output links. If more than one node transmits at the same time, then collisions will occur at the repeater, as illustrated in Figure 2b. A switching hub, on the other hand, switches an incoming frame from a particular input to an appropriate output line. The same switching function can be performed simultaneously on other input–output links without interference to the frames involved, as illustrated in Figure 2c. As such, each node has a dedicated capacity equal to that of the transmission rate of the LAN, and the switching hub can support mixed capacity links, e.g., 10 Mb/s and 100 Mb/s. With dedicated access to the medium and appropriate buffering at the switch to avoid contention of the same output link, there is no need to implement the CSMA/CD access algorithm. Nonetheless, the conventional Ethernet frame format is used to ensure inter-operability between existing 10 Mb/s and 100 Mb/s LANs.

IEEE 802.3 1 Gb/s Ethernet (Gigabit Ethernet)

The IEEE 802.3 1 Gb/s Ethernet standard, commonly referred to as Gigabit Ethernet, was finalized in 1998. An example of a Gigabit Ethernet backbone LAN is shown in Figure 3, whereby a Gigabit Ethernet backbone switch connects central servers to high-speed workgroup switches. In turn, each workgroup switch supports gigabit high-performance workgroup servers, as well as 100 Mb/s workstations and hubs. As in the 100 Mb/s standard, Gigabit Ethernet uses the conventional Ethernet frame format and allows both half-duplex and full-duplex operation. For half-duplex operation, the CSMA/CD access protocol is



Figure 3 Gigabit Ethernet backbone network (adapted from William S (2004) *Data and Computer Communications*, 7th edn, Ch. 15–16. Upper Saddle River, NJ: Pearson Education).

equipped with two additional features. The first feature, known as carrier extension, extends the propagation time of short frames by adding nondata symbols to the end of frames. The minimum length of a frame for Gigabit Ethernet is 512 bytes as opposed to the specified minimum of 64 bytes in the preceding two standards. The second feature, known as frame bursting, allows a node to transmit multiple consecutive frames, up to a specified maximum, without having to undergo the contention process for each transmission. Both features improve the efficiency of the protocol.

There are two optical-fiber transmission medium specifications for Gigabit Ethernet. The short wavelength option, denoted 1000BASE-SX, is for 850 nm transmission. Specified maximum link distances are 275 m using 62.5 μm MMF, and 550 μm using 50 μm MMF. The long wavelength option, denoted 1000BASE-LX, is for 1310 nm transmission. Achievable duplex link distances are 550 m using 62.5 μm or 50 μm MMF, and 5 km using 10 μm SMF.

IEEE 802.3 10 Gb/s Ethernet (10GbE)

The Ethernet standard was extended to incorporate 10 Gb/s (10GbE) in 2002, fueled by ever-increasing Internet traffic and bandwidth intensive applications. 10GbE fulfills not only LAN specifications, but also metropolitan and wide-area network specifications. It is envisioned that with the emergence of 10GbE metropolitan and wide-area networks, the deployment of 10GbE LANs will enable a seamless transport of Ethernet frames across different network boundaries, thus simplifying network management and optimizing operational costs.

Unlike its predecessor standards, the physical layer options for 10GbE include only the optical-fiber transmission medium and allow only for full-duplex operation. Four specifications are defined for 10GbE. 10GBASE-S is designed for 850 nm transmission on 63.5 μm MMF, while 10BASE-L and 10BASE-LE use 10 μm single mode fiber (SMF) for 1310 nm transmission and 1550 nm transmission, respectively. The corresponding maximum achievable distances are 300 m, 10 km, and 40 km, respectively. An alternative specification, 10GBASE-LX4, is designed for wavelength division multiplexed (WDM) transmission links. The specification caters for four 2.5 Gb/s transmission channels within the 1270–1355 wavelength region on either 10 μm SMF, 50 μm MMF, or 62.5 μm MMF. Single-mode transmissions can reach distances of up to 10 km, while multimode transmissions can reach distances up to 300 m. The characteristics of these physical layer specifications are summarized in Table 2.

Fiber Distributed Data Interface (FDDI)

Overview

The Fiber Distributed Data Interface (FDDI) standard was developed by the Accredited Standards Committee X3T9.5, and approved by both ANSI (American National Standards Institute) and ISO (International Standards Organization) in 1989. While not as

Table 2 Summary of IEEE 802.3 physical and MAC layer specifications for 10 Gb/s Ethernet

	10GBASE-S	*10GBASE-L*	*10GBASE-E*	*10GBASE-LX4*
Data rate	10 Gb/s	10 Gb/s	10 Gb/s	4 × 10 Gb/s
Transmission wavelength	850 nm	1310 nm	1550 nm	1270 nm to 1355 nm
Transmission medium	62.5 μm MMF pair	10 μm SMF pair	10 μm SMF pair	10 μm SMF or 50 μm, 62.5 μm MMF pair
MAC protocol	Switched (full duplex)	Switched (full duplex)	Switched (full duplex)	Switched (full duplex)


Node
Node
Node
Node
Transmission and reception on primary ring
(a)
Loop back
Link failure
Loop back
Both primary and secondary rings in use
(b)

Figure 4 (a) FDDI ring network. (b) Use of secondary ring for protection against link failures.

widely deployed as the Ethernet family of LANs, due to the high cost of equipment and devices, it remains as the first to be standardized for high-speed fiber-optic LAN applications and is now mainly used to interconnect existing FDDI-compatible LANs. Extensions have been made to the FDDI standard to incorporate single-mode fiber operation for increased signal reach.

FDDI specifies a dual counter-propagating ring network as shown in Figure 4a. Each ring operates at the speed of 100 Mb/s, and can reach a maximum length of 100 km. The dual ring topology is self-healing against fiber-cuts and node failures. Under normal operation, frame transmission and reception are performed on a primary ring. The secondary ring is utilized to form a closed loop when a node or link failure occurs, as illustrated in Figure 4b. In FDDI, the interface between each node and the optical-fiber transmission medium is a repeater. Data frames, each of which carries its source and a destination address in a defined field in the frame header, are transmitted sequentially around the ring from one repeater to another. Each frame can vary in length by up to 4550 bytes. Each repeater copies the destination address field of all incoming frames and, upon recognizing the destination address as its own, additionally copies the remainder of the frame. The repeater attached to the source node also facilitates the removal of frames it has transmitted after a round-trip propagation around the ring.

FDDI employs a distributed timer-controlled, token-passing mechanism, referred to as timed token rotation protocol, to control access to the shared optical fiber ring. While Ethernet-based LANs are highly suited to support throughput sensitive services which can sustain reasonable delay in return for high throughput, FDDI provides an additional capability to support delay sensitive services such as packetised voice and video. For such services, frames must be received within a certain time interval for quality of service requirements. A node connected to an FDDI network can therefore transmit both classes of services: the former referred to as burst traffic and the latter as stream traffic. In addition, the timed token rotation protocol can limit the amount of frames that can be transmitted by a particular node for each class of service, ensuring efficient and fair network access amongst all nodes and services. FDDI is thus well-suited to carry the mixture of burst and stream traffic expected in a backbone network which supports a number of smaller LANs.

MAC Protocol

Token-passing mechanism

In FDDI, access to the shared transmission medium is governed by a timed token rotation protocol. A token is a special frame created during network (re)-initialization by a pre-assigned node. The token circulates the ring network and gives the node that holds it the right to transmit. Figure 5 gives an example of a single frame transmission from Node A to Node C, and from Node B to Node A. Node A has a frame to transmit to Node C and thus waits for a token (Figure 5a). Upon recognizing that a token frame is passing through, it aborts the token transmission without regenerating the token bits. After Node A has completely received the token, the node begins transmitting frame FA addressed to Node C, and appending a new token upon completion (Figure 5b). Meanwhile, Node B regenerates and retransmits FA as it circulates past. When FA reaches Node C, the node copies FA in addition to regenerating and retransmitting FA. Node B captures the token issued by A and transmits FB to Node A (Figure 5c). Eventually FA recirculates back to its originating node, Node A, whereby it is removed from the ring (Figure 5d). At the same time, Node B finishes transmitting FB and releases the token. Nodes C and D, with no frames to transmit or receive, regenerate and retransmit both FB and the token. When FB reaches Node A, it is copied by the node. Node A also regenerates and retransmits both FB and the token. FB is finally removed from the ring by Node B (Figure 5e), and the token remains in the ring to be received by the next node with a frame to transmit (Figure 5f).

Aside from source and destination address fields, each dataframe also contains a frame status field which comprises error detected (E), address recognized (A), and frame copied (C) indicator bits. Each node can check passing frames for errors and can set the E indicator if an error is detected using the standard cyclic redundancy check procedure. If a node detects its own address, it sets the A indicator, and upon copying the frame, the station may also set the C indicator. When a dataframe recirculates back to its source node, the indicator bits are examined. If both A and C are not set, then the destination node does not exist or is inactive. On the other hand, if the frame has not been copied by an active destination node or an error has been detected, higher control layers are notified for future retransmission.

Time-controlled mechanism

FDDI uses a time-controlled mechanism to prevent nodes from dominating the network capacity. During initialization, a target token rotation time (TTRT) is established based on the shortest allowable time between token arrivals at each node. The same TTRT value is then stored at all nodes. In addition, each node has a maximum capacity guaranteed for the transmission of its stream traffic. The total transmission time of this stream traffic and the latency of the ring (i.e., total round-trip propagation time, the transmission time of a maximum length frame and the token frame) must never exceed the TTRT. During network operation, each node measures the



Figure 5 Fiber Distributed Data Interface (FDDI) token passing mechanism.

time interval between successive token arrivals, using a token-rotation timer (TRT). The TRT is enabled only upon a token arrival, and expires if the counter reaches the TTRT value. In turn, a late counter (LC) is incremented and TRT is reset to zero. The number of TRT expirations since a token was last received is, therefore, counted by LC. Any token that arrives at a node with a nonzero LC value is referred to as a late token. Likewise, an early token is one which arrives at a node with a zero LC value.

The action of a node when it receives a token depends on whether the token is early or late. When a late token is received, LC is reset to zero but TRT continues to run. The node then transmits for the period of time which corresponds to the predetermined bandwidth for steam traffic transmission. The node is not allowed to transmit any bursty traffic frames. In the event of an early token reception, the node transfers the current value of TRT to a second timer, the token-holding timer (THT) but does not enable it. TRT is reset to zero and is enabled to track the next rotation of the counter. The node then transmits stream traffic frames for the allocated period of time. After that, THT is enabled and bursty traffic frames are transmitted until THT reaches the TTRT value. The THT is then reset and the node releases the token into the ring. The transmission of bursty frames may be further controlled by two additional mechanisms. The restricted-token mechanism allows only two nodes in the network to use all the available bursty bandwidth, and restricts all other nodes to their stream bandwidth. This is facilitated by the use of a restricted token which is issued by one of the two nodes. The priority mechanism provides each station with the capability to transmit bursty frames according to eight priority levels. Each priority level corresponds to a different time threshold in the THT.

Note that the time-controlled mechanism of the MAC protocol guarantees a maximum response time for the ring because, in the worst case, the time between the arrival of two successive tokens will never exceed twice the value of TTRT. Most multimedia applications, such as video conferencing, real-time video, and entertainment video can be supported on FDDI with stream service and a small TTRT. However, since the TTRT cannot be less than the ring latency, applications requiring time bounds less than twice the ring latency cannot be supported by FDDI. Long and continuous isochronous services which must adhere to strict periodic access require FDDI-II.

FDDI-II

FDDI-II provides the additional circuit-switching capability to support constant bit-rate telecommunication applications. Like FDDI, the transmission bit-rate of FDDI-II is 100 Mb/s. FDDI-II can operate in either complete isochronous mode, complete packet-switching mode, or in hybrid mode in which both isochronous as well as bursty and stream services are supported. Strict periodic access required by isochronous services are accomplished with transmission opportunities repeated every 125 μs. At 100 Mb/s, time on the ring is divided into several frames, each 1562.5 bytes long. Out of the 1562.5 bytes, 1560 bytes are used for data transmission while the remaining 2.5 bytes are used as interframe gap. In turn, the 1560 bytes are divided into 16 wideband channels of 96 bytes each. Each wideband channel thus provides a bandwidth of 6.144 Mb/s, sufficiently adequate for television broadcast and multiple voice channels. For operation in the hybrid mode, some of the wideband channels are allocated for packet mode transmission. Likewise, if complete packet-switching operation is required, all wideband channels are allocated for packet switching transmission.

IEEE 802.6 Distributed Queue Dual Bus (DQDB)

Overview

The IEEE 802.6 Distributed Queue Dual Bus (DQDB) standard, finalized in 1990, specifies a dual bus network with an operating speed of 150 Mb/s. DQDB is now mainly used for MAN applications, although it can be readily deployed for LAN backbone interconnection. Figure 6 illustrates the basic architecture of a DQDB network with access nodes, Node 1 to Node *N*, distributed along two counter propagating buses, BUS A and BUS B. Each access node is considered to be connected to a lower speed LAN. At the head end of each bus, a slot generator continuously generates fixed-size time slots which propagate along its respective bus. The contents of each time slot are regenerated at each access node it passes, and upon reaching the end of the bus, a sink terminal receives and removes the time slots from the network. Data are transported across the network from one access node to another in the form of fixed-size segments. A node transmits a segment by changing the contents of a passing time slot. Each segment needs only be transmitted on one of the two buses, the choice depending on the locations of the transmitting and receiving nodes. For example, referring to Figure 6, a downstream transmission from Node i to Node $i+1$ requires the use of BUS A. On the contrary, an upstream transmission from Node i to Node $i-1$ uses BUS B.


Direction of propagation
Time slot
BUS A
Slot generator
Sink terminal
Node 1
Node 2
Node *i*
Node *i* +1
Node *N*
Slot generator
BUS B
Direction of propagation

Figure 6 Distributed Queue Dual Bus (DQDB) architecture.


IDLE
BUSY
BUS A
REQ_CNT
REQ
REQ
REQ
Node *i*
BUS B
REQ
(a)
IDLE
BUSY
BUS A
CD_CNT
REQ
REQ
SEGMENT
REQ_CNT
REQ
REQ
DQ as seen by Node *i*
Node *i*
BUS B
REQ
(b)

Figure 7 Behavior of Node *i* during (a) idle state; and during (b) countdown state.

MAC Protocol

In DQDB, permission to transmit segments into the network is determined by a global distributed queueing algorithm. The algorithm allows each node to continuously monitor both buses, counting the requests and available time slots that pass by. In addition to maintaining a global first-in-first-out queue (DQ) for each bus, the algorithm relies on information in the header of time slots, namely the BUSY and REQ fields, and counters at the access nodes to coordinate transmissions. A ‘BUSY = 0’ field represents the availability of a time slot for the transport of a segment. For example, time slots generated at the head end of each bus have default ‘BUSY = 0’ and ‘REQ = 0’ fields. The BUSY field is set to 1 when a segment is transmitted into an available time slot.

The REQ field is used in conjunction with the counters to inform nodes of an impending transmission from downstream. To simplify the explanation, consider only packets propagating on BUS A. A node wishing to transmit a segment downstream needs to queue the segment in the appropriate DQ. The node with an impending transmission must then notify all upstream nodes that it has inserted a segment in the DQ so that an available time slot can be reserved for the transmission. This is accomplished by setting the first time slot propagating in the opposite bus, BUS B, with REQ = 0 to REQ = 1. As such, the node maintains the outstanding segments in the DQ belonging to downstream nodes via the value in the REQ field.

To illustrate, Figure 7a shows an arbitrary node, Node *i*, in an idle state, whereby the node has no segments to transmit downstream on BUS A. With every ‘REQ = 1’ observed on BUS B, a request counter, REQ_CNT is incremented by one. However, with every empty slot, i.e., ‘BUSY = 0’, observed on

Table 3 Comparison of standardized local area networks

	Ethernet	*Fast Ethernet*	*Gigabit Ethernet*	*10GbE*	*FDDI*	*DQDB*
Data rate	10 Mb/s	100 Mb/s	1 Gb/s	10 Gb/s	100 Mb/s	150 Mb/s
MAC protocol	CSMA/CD	CSMA/CD or Switched technique	CSMA/CD or Switched technique	Switched technique	Timed token rotation	Distributed queue
Standard	IEEE 802.3	IEEE 802.3	IEEE 802.3	IEEE 802.3	ANSI-FDDI	IEEE 802.6

the BUS A, REQ_CNT is decremented by one. When Node *i* has a segment to transmit, it enters the countdown state as illustrated in Figure 7b. The value in REQ_CNT is transferred into an independent countdown counter, CD_CNT, and REQ_CNT is reset to zero. Node *i* also sets 'REQ = 1' in the opposite bus, BUS B. As in the idle state, each 'REQ = 1' observed on BUS B increments REQ_CNT while each 'BUSY = 1' observed on BUS A decrements it. When CD_CNT reaches zero, Node *i* transmits its segment in the first time slot with 'BUSY = 0' on BUS A and sets 'BUSY = 1'. The node returns to the idle state if there are no other segments to transmit. The algorithm allows the node to determine the number of time slots reserved by downstream nodes and the time to transmit a segment into an available time slot. Note that both the idle and countdown states are replicated for transmissions on BUS B.

The DQDB standard also specifies a limited support of isochronous services. Nodes which provide and receive such services are reserved a certain amount of time slots which are indicated with additional header information. The remaining time slots are used by all other access nodes for the transport of packet-switched traffic, and access to these time slots is managed by the global distributed queueing algorithm. A priority mechanism based on using multiple DQs, each with a different priority level, may also be implemented to guarantee access to certain segments in the network.

Summary

Due to the explosive demand for high-bandwidth applications, fiber-optics has become an essential technology in LANs. Table 3 compares the various fiber-optic LAN standards discussed in this article. The Ethernet family remains the most prevalent of LAN technologies. Its widespread use is contributed by the availability of low-cost chipsets, mature and familiar management and analysis tools. The future of fiber-optic LANs operating beyond 10 Gb/s will depend upon WDM solutions. The current usage of one transmission channel per network is impeded primarily by the limitation of the speed of electro-optic conversion, and thus does not fully exploit the massive transmission bandwidth of the optical fiber. With WDM, multiple transmission channels are concurrently transmitted on a single optical fiber, thereby greatly increasing the capacity of an optical LAN. Ongoing research efforts have been directly towards advancing WDM component technology and addressing prevailing issues such as polarization control, chromatic dispersion, and four-wave mixing among others.

List of Units and Nomenclature

CD_CNT	countdown counter
CSMA/CD	carrier-sense multiple access with collision detection
DQ	global first-in-first-out queue
DQDB	distributed queue dual bus
FDDI	fiber distributed data interface
LAN	local area network
LC	late counter
MAC	medium access control
MAN	metropolitan area network
MMF	multimode fiber
REQ_CNT	request counter
SMF	single mode fiber
TDMA	time division multiple access
THT	token-holding timer
TRT	token rotation timer
TTRT	target token rotation timer
WDM	wavelength division multiplexing

See also

Information Processing: Optical Neural Networks.

Further Reading

IEEE Std 802.6 (1990) IEEE standards for local and metropolitan area networks: distributed queue dual bus (DQDB) subnetwork of a metropolitan area network (MAN).

IEEE Std 802.3 (2002, Revision of IEEE Std 802.3, 2000 ed.) IEEE Standard for Information Technology – Telecommunications and Information Exchange Between Systems – Local and Metropolitan Area

Networks – Specific Requirements Part 3: Carrier Sense Multiple Access with Collision Detection (CSMA/CD) Access Method and Physical Layer Specifications.

ISO 9314-1,2 (1989) Information processing systems – Fibre Distributed Data Interface (FDDI) – Part 1: Token Ring Physical Layer Protocol (PHY) and Part 2: Token Ring Media Access Control (MAC).

Marco C, Enrico G and Luciano L (1997) *Metropolitan Area Networks*. New York: Springer-Verlag.

Mills A (1995) *Understanding FDDI*. Englewood Cliffs, NJ: Prentice Hall.

William S (2004) *Data and Computer Communications*, 7th edn, Ch. 15–16. Upper Saddle River, NJ: Pearson Education.

Optical Time Division Multiplexing

L P Barry, Dublin City University, Dublin, Ireland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

As the demand for bandwidth continues to grow, driven by the massive increase in Internet usage, so will the necessity to have communications networks that can handle very high data rates. The use of optical fiber networks is the clear choice for such systems given the huge available bandwidth of the fiber transmission medium. However, in a basic optical communication system comprising a laser transmitter, an optical fiber transmission medium, and a receiver, the capacity is essentially limited by the speed at which light can be modulated at the transmitter. To overcome this limitation, which is basically due to the speed of available electronics, it is necessary to use optical multiplexing techniques, and one such technique, known as optical time division multiplexing (OTDM), will be the subject of this article.

Principles of Time Division Multiplexing

Time division multiplexing (TDM) has long been the traditional method for electrically combining information channels. If we take the most fundamental data rate to be that of a simple voice call at 64 kbit/s, then the transmission of data at higher bit rates is achieved by electrically multiplexing a large number of 64 kbit/s channels in the time domain. With the evolution of standards, a number of different data rates have been specified as standard transmission rates. In Europe the synchronous digital hierarchy (SDH) has a basic data rate of 155.52 Mbit/s, which is known as the synchronous transport module – Level 1 (STM-1). This particular data rate is essentially obtained by electrically multiplexing over 2000 voice calls in the time domain (with some of the capacity required for overhead information). By subsequently multiplexing a number of STM-1 channels together we can obtain transmission at the higher standard data rates of STM-4 (622 Mbit/s), STM-16 (2.48 Gbit/s), and STM-64 (9.88 Gbit/s), as outlined in Table 1.

Figure 1 illustrates how basic electrical TDM is used in standard optical communication systems. Clearly as we approach the higher data rates of STM-64, a serious level of electrical multiplexing is required, and as the data rates increase so does the cost and complexity of the electrical equipment at the transmitter and receiver. Indeed the present state of the art in electronics seems to suggest 40 Gbit/s as the limit for electrically multiplexed communication systems. However, as we stated earlier, communications traffic has been growing explosively over the last decade and will continue to do so. In order to meet this demand for capacity, and better exploit the massive available bandwidth of optical fiber, it is necessary to use optical multiplexing techniques for communications systems. The two main optical multiplexing techniques available are wavelength division multiplexing (WDM) and optical time division multiplexing (OTDM). WDM essentially involves transmitting data at a number of different wavelengths on the same fiber. Although electrical multiplexing may be limited to data transmission rates of around 40 Gbit/s using one laser, by multiplexing together N different wavelength channels each carrying 40 Gbit/s, we can achieve overall data rates up to and beyond a terabit/s.

The second of these optical multiplexing techniques, OTDM, is the subject of this article. Whereas WDM multiplexes optical data channels in the

Table 1 Standard data rates for SDH transmission systems

SDH standard	*Data rate (Mbit/s)*
STM-1	155.52
STM-4	622.08
STM-16	2488
STM-64	9953
STM-256	39 813


STM-1
STM-1
STM-1
Electrical multiplexer
Laser transmitter
STM-16
TDM signal
Receiver
Electrical demultiplexer
STM-1
STM-1
STM-1

Figure 1 Electrical time division multiplexing (ETDM) in a basic optical communication system.


Pulse source
(repetition rate R, duration, τ)
Optical amplifier
Fiber coupler
Modulator
Modulator
Modulator
Electrical NRZ data
Electrical NRZ data
Optical delay
Fiber coupler
Optical amplifier
Clock recovery
Transmission fiber
Demultiplexed channels at bit rate R, sent to opto-electronic detectors
OTDM demultiplexer
Optical amplifiers

Figure 2 Basic configuration for an OTDM transmission system comprising transmitter, transmission fiber, and receiver.

wavelength domain, the basic principle of OTDM communications is to increase the system capacity by multiplexing optical data channels in the time domain. This multiplexing is usually achieved by a process known as bit-interleaving. This process can be explained by considering Figure 2, which shows a basic schematic of an OTDM based transmission system. The main component of the overall system is a source of ultrashort optical pulses (pulse duration τ) at a certain repetition rate, R. The optical pulse source is initially split into N channels using a passive fiber coupler, and each pulse train is subsequently modulated by electrical data which is at a data rate of R. The resulting output from each modulator is essentially an optical data channel where the data are represented using ultrashort optical pulses (return-to-zero data format). The data from each modulator then passes through a fixed fiber delay line which delays each channel by a time equal to $1/RN$ relative to its adjacent channel (as shown in Figure 2). The N modulated and delayed optical data channels are then recombined in another passive fiber coupler to form the OTDM data signal. We can consider that the delay lines essentially assign each data channel to a specific bit slot (of width $1/RN$) in the overall multiplexed signal. The multiplexed data signal may then be transmitted over optical fiber before arriving at the receiver which is responsible for demultiplexing the optical signal into its discrete channels.

The duration of the optical pulse source is extremely important in determining the maximum overall data rate which can be achieved. The overall data rate is basically defined by the temporal separation between channels in the multiplexor, but in order to avoid cross-channel interference, this separation must be significantly greater than the pulse duration. Thus to increase the overall data rate we must use shorter optical pulses. However, as we reduce the optical pulse width to raise the data rate we need to take into account the problems that may be encountered as this high-speed data signal propagates over optical fiber, and also the difficulty in demultiplexing a high-speed OTDM data signal. The following section will look in greater detail at these key elements of the OTDM communication system, namely the optical pulse source, the transmission of the ultrahigh capacity signal, and the demultiplexing at the receiver.

Key Elements of an OTDM Communication System

Ultra-Short Optical Pulse Sources

As stated earlier, the optical pulse source is a key element in any OTDM-based communication system. The important characteristics of the pulse source that will affect its usefulness in an OTDM system are the pulsewidth, the spectral width, and the temporal jitter. The pulse duration clearly has to be short enough to support the desired overall transmission rate. For example, if we wish to design an OTDM system with an aggregate data rate of 100 Gbit/s (which will have a delay of 10 ps between each channel in the multiplexed signal), then the pulsewidth should normally be less the 30% of the channel spacing to avoid cross-channel interference (i.e. around 3 ps). For terabit/s OTDM systems we would require pulsewidths less than 0.5 ps. The spectral width of the pulse source is also important, as it will have a major impact on how the pulse will evolve during propagation in the fiber. A standard figure of merit which is employed is the time–bandwidth product, and ideally we require the pulse source to be transform limited, which implies that the spectral width is as small as possible for the associated pulsewidth. The impact of temporal jitter on the pulses can be easily understood by considering the above example of a 100 Gbit/s system, employing 3 ps pulses, with the multiplexed channels spaced by 10 ps. Obviously if the jitter on the pulses becomes significant in relation to the channel spacing, then this can also lead to interference between adjacent channels in the overall OTDM system. A large number of techniques have been employed to develop ultrashort pulse sources suitable for use in OTDM systems, but the three main methods which will be described below are active mode-locking, gain-switching, and external modulation of a CW light signal.

Active mode-locking of laser diodes normally involves modulating the amplitude of the optical field inside the laser cavity at a frequency which is equal to the mode spacing of the laser. This can be achieved by applying an electrical sinusoidal signal at the correct frequency, and results in the generation of optical pulses at the repetition rate of the applied signal. This technique has been successfully employed in the generation of subpicosecond pulses at repetition rates up to and beyond 40 GHz, with excellent spectral and temporal jitter characteristics. However, an inherent problem in all mode-locked pulse sources is the difficulty in synchronizing the mode-locked frequency to a specific SDH standard data rate.

Gain switching of semiconductor laser diodes is probably the simplest and most reliable technique to generate optical pulses. The technique, which is presented in Figure 3, involves applying a high-power electrical pulse (or electrical sinusoidal signal) to the laser in conjunction with a certain bias current. By ensuring that the electrical pulse signal and the bias signal have the correct level, the relaxation oscillation phenomenon of the laser results in the production of optical pulses with durations between 10 and 30 ps, at the repetition rate of the applied electrical signal. The frequency of the electrical signal applied to the laser is essentially arbitrary (provided it is not larger than the modulation bandwidth of the diode), thus making it straightforward to synchronize the optical pulse train to a SDH line-rate. The main problem with this technique is that the spectral width of the pulses generated is such that the pulses are far from transform-limited, which would affect their subsequent propagation in the fiber. In addition, temporal jitter on gain-switched pulses can also be a problem. However, by using novel arrangements such as external injection into the gain-switched laser, this difficulty can be overcome.

The third pulse generation technique mentioned above involves external modulation of a cw light signal with an electro-absorption modulator. The experimental configuration for this pulse generation technique is shown in Figure 4. By biasing the modulator around its null point, and applying an electrical sinusoidal signal to it, the cw light passing through the modulator becomes shaped into optical pulses. The optical pulse train which is generated due


Bias current
Single mode laser diode
High power electrical pulse source (duration ~100 ps), or sinusoidal RF signal
Bias tee for combining RF and DC signals
Pulse processing fiber compression
Output pulses

Figure 3 Pulse generation using the gain-switching technique followed by pulse compression.



Figure 4 Pulse generation based on shaping of cw light using the nonlinear response of an external modulator biased about its null point.

the nonlinear response of the electro-absorption modulator is at a repetition rate of twice the applied electrical signal. The pulses generated are normally transform limited with extremely low temporal jitter, and the repetition rate is arbitrary as in the gain-switching technique (with the limit being ultimately determined by the modulation bandwidth of the modulator). This method may be readily used to generate pulses at repetition rates up to 40 GHz with pulsewidth around 5 ps, and it has the advantage that the optical source and the modulator can be integrated in a single device to form a compact pulse source suitable for OTDM communication systems.

It should also be noted that in addition to the various techniques that have been outlined, it is possible to use pulse compression in order to reduce the pulse width. The main issues concerned with pulse compression are the shape and spectral width of the optical pulses after compression. One of the most attractive methods of achieving pulse compression involves using nonlinear compression in dispersion-decreasing fiber, with the main advantage of this technique being the ability to maintain a transform limited pulse after compression. By employing this compression scheme, optical pulse sources at 10 GHz with pulsewidths below 200 fs have been developed, and such pulsewidths would be suitable for use in Tbit/s OTDM systems.

Transmission of an OTDM Signal over Fiber

The transmission performance of an OTDM data signal is vital in determining the distance over which the data can be transmitted successfully. The main fiber parameters, which will affect the signal transmission, are attenuation and dispersion. If we consider OTDM systems operating at a wavelength of around 1550 nm (minimum loss wavelength), to overcome the fiber attenuation and maintain a suitable optical power budget for the system, optical amplifiers are normally employed. If we thus assume that the amplifiers overcome the fiber loss problem, then the maximum transmission distance will be limited by the fiber dispersion. In a very basic OTDM system operating at 1550 nm, with transmitter and receiver linked using standard fiber (dispersion parameter of about 16 ps km^{-1} nm^{-1}), the maximum transmission distance will be limited by the overall data rate, and the pulsewidth and spectral width of the optical pulse source. For example, consider a 40 Gbit/s OTDM data signal which is formed using 8 ps optical pulses with a spectral width of 40 GHz (0.32 nm). From the spectral width we can calculate the signal broadening due to dispersion to be around 5 ps km^{-1}, and as the pulses broaden and spread into adjacent channels of the OTDM signal then this interference will make it increasingly difficult to correctly detect the signal at the receiver. In this case after propagation through 5 km of fiber, the signal pulses will have already dispersed to around 25 ps duration, the same value as the temporal bit slot into which each channel is placed. This will clearly result in serious loss of signal integrity. A straightforward possibility to increase the transmission distance of OTDM systems is to employ dispersion shifted fiber; the dispersion parameter is now around 1–2 ps km^{-1} nm^{-1}, at an operating wavelength of 1550 nm. This reduction in dispersion will obviously increase the allowed transmission distance by about an order of magnitude for the example described above. However, to develop ultrahigh-speed, long-haul OTDM communications we require more complex transmission schemes. Two possibilities for this include dispersion compensation, and soliton transmission techniques.

Dispersion compensation basically involves compensating for the dispersion that has been encountered during transmission by using some fiber with a total dispersion of opposite sign but equal magnitude to the transmission fiber. Dispersion compensation may also be achieved using a suitably designed fiber grating. For a long-haul OTDM system, a dispersion compensator may be used every 50 or 60 km, in conjunction with the optical amplifier, thus allowing us to compensate both fiber loss and attenuation periodically along the link. The main limitation, however, with the dispersion compensation technique is caused by the dispersion slope of the fiber, as for ideal compensation it is necessary to compensate completely for the dispersion slope in addition to the overall fiber dispersion. The second technique that may be employed to greatly extend the transmission distance of high-speed OTDM communication systems is the use of soliton transmission. The basic principle of soliton transmission is to use optical data pulses with a particular shape, pulsewidth, and peak power, such that as the pulse propagates, the effects of fiber dispersion and nonlinearity counterbalance to allow the signal to propagate undistorted. By using optical amplifiers to ensure that the optical pulse peak power does not vary too much along the transmission link, OTDM transmission at data rates greater than 100 Gbit/s, over distances approaching 500 km have been demonstrated.

Demultiplexing of OTDM Signal at Receiver

For OTDM communication systems with data rates above 40 Gbit/s, it is not feasible to use electrical switching. Indeed for ultrahigh-speed systems operating at 100 Gbit/s and beyond, the only solution for demultiplexing is to use all-optical switching in which optical control signals are used to switch the OTDM data signal. All-optical switches normally use nonlinear optical effects either in optical fiber or semiconductors. A typical scenario (as presented in Figure 5) involves the injection of both the OTDM data signal and an optical control signal into the nonlinear device. The control signal consists of high-power ultrashort pulses at the repetition rate of the individual channels within the temporally multiplexed signal, and by synchronizing it with one of the OTDM channels it is possible to demultiplex this channel from the high-speed OTDM signal.

Two of the most popular all-optical demultiplexers are the nonlinear optical loop mirror (NOLM), and the terahertz optical asymmetric demultiplexer (TOAD). The NOLM is based on the nonlinear refractive index of optical fiber. It essentially consists of a 2 × 2 fiber coupler with its two outputs joined using a certain length of fiber. When an OTDM signal is injected into an input port of the coupler, it splits into two counterpropagating components in the fiber loop, and when these components recombine and interfere at the coupler, the overall signal is output through its initial input port. If we now inject a high-power control signal directly into the loop, such that it propagates unidirectionally, and is



Figure 5 Configuration of OTDM demultiplexers using (a) an interferometer based on nonlinear phase shift in fiber or semiconductor optical amplifiers, and (b) four-wave mixing in fiber or semiconductor optical amplifiers.

synchronized with one of the OTDM data channels, then the phase shift induced by the control on the copropagating signal channel (via the nonlinear refractive index of the fiber) results in that particular channel being switched out to the second input port of the coupler. The remaining data channels of the OTDM signal are once again output through the same port that they entered the coupler. As this particular nonlinear effect in fiber (known as the Kerr effect) has a femtosecond response time, it should be possible to realize extremely high-speed switching with the NOLM. Demultiplexing at data rates in excess of 100 Gbit/s has already been achieved using this technique. One disadvantage of this method is that the nonlinear index coefficient of standard fiber is very small, so in order to achieve the required phase shift from the control pulse, it is necessary to use a fiber loop of around 1 km in length (depending on the power of the control pulse used). This length may affect the overall stability of the demultiplexer and its ability to be readily integrated into high-speed OTDM systems. However, it should be noted that recent developments in the design of high-nonlinearity fibers may reduce this problem.

The second all-optical switch mentioned above is known as a TOAD. Whereas the NOLM is based on the nonlinear refractive index of the fiber, the TOAD is based on a nonlinear optical effect in semiconductor optical amplifiers (SOA). The overall setup for a TOAD is very similar to that for a NOLM, except that a semiconductor amplifier, as shown in Figure 5, replaces the length of fiber in the loop. As for the NOLM, the OTDM data signal is injected into the TOAD using one input of the coupler, such that it splits into two counterpropagating signals, while the control signal propagates unidirectionally in the loop containing the SOA. By synchronizing the control with one channel in the OTDM signal, this particular channel is switched out. Although the response time of a TOAD-based switch may not be as fast as the NOLM, it does have the major advantage that it can be developed into a very compact demultiplexer, suitable for deployment in OTDM-based communication systems.

In addition to the NOLM and the TOAD structures, which are both interferometric-based switches, it is also possible to use four-wavemixing (FWM) in optical fiber or semiconductor optical amplifiers to carry out the demultiplexing of OTDM signals. In this case, the high-power control pulse is synchronized with one of the OTDM channels such that the wavelength of this channel is shifted as it passes through the nonlinear device. Optical filtering may then be used to select out the demultiplexed channel.

As we discussed in the section on demultiplexing, whatever specific all-optical switching technique is employed, we need to generate an optical clock signal for use as the control pulses. This implies that it is necessary to extract a clock at the base rate of the individual data channels from the high-speed OTDM signal. Depending on the base data rate, which may be anywhere from 2.5 to 40 Gbit/s for typical OTDM systems, different clock recovery techniques have been demonstrated. These range from basic electronic clock recovery schemes to more advanced techniques based on self-pulsating laser diodes and optical phase-locked loops.

OTDM Networking Issues

The previous section has predominantly dealt with the basic elements required to implement a high-speed OTDM transmission link. However, if we are to use OTDM technology for high-speed networking, then additional elements will be required. One of the most important of these is an add/drop multiplexer (ADM). The ADM allows us to switch out one channel from the OTDM signal, and then insert another data channel for transmission in the vacant bit slot. If we consider employing OTDM in a ring configuration network, then a typical architecture for the network will be as shown in Figure 6. The high-speed OTDM data signal propagates around the closed fiber loop, and each node in the network is responsible for switching out the data it requires, in addition to inserting the data it wishes to transmit onto the fiber ring. Add/drop multiplexing is thus imperative in developing such an OTDM ring network.

The configuration for each node in an OTDM ring network is shown in Figure 7. At each node it is initially necessary to recover the base rate clock signal. The recovered clock is then used in conjunction with the OTDM signal to switch out the required data channel from the multiplexed signal. When an add/drop multiplexer is used for this purpose we obtain two outputs, one being the demultiplexed data, and the other being the OTDM signal less the switched-out data channel. A simple fiber coupler can subsequently be used to allow this particular node to insert the data it wishes to send into the free bit slot of the overall OTDM signal. This obviously requires control of the relative delay between the OTDM signal and the local data channel to be inserted onto the fiber ring, to ensure that the local data are inserted into the vacant bit slot. A number of techniques have been used for implementing add/drop multiplexers in


Node a
Node b
Node c
Node d
Node e
Node f
Node g
Node h
High-speed OTDM signal
Optical clock

Figure 6 Schematic representation of a ring network employing OTDM with a separate fiber for clock distribution.


Optical clock
Coupler
Electrical data to be transmitted on ring
Electro-optic modulator
Variable delay
Optical clock
OTDM signal to next mode on fiber ring
Variable delay to determine OTDM channel switched
OTDM signal less demultiplexed channel
OTDM data from fiber ring
Channel demultiplexer
Demultiplexed channel

Figure 7 Configuration of an add/drop multiplexing node for use in OTDM-based communication systems.

OTDM-based networks. These have used either fiber interferometers, or interferometers using semiconductor optical amplifiers, in which we obtain both the demultiplexed data signal and the OTDM signal less the switched-out channel (to which the local data channel is then added). The continuing development and enhancement of ADM devices for OTDM systems will be vital for the future implementation of OTDM communication systems.

Conclusion

In this article we have explained the main ideas involved in building OTDM communication systems, and also introduced the principal technologies which are required to do so. OTDM is an extremely wavelength-efficient technique for delivering high-capacity data signals, and it may be used both for long-haul transmission and networking around metropolitan areas. In addition, unlike WDM, it does not require a different wavelength source for each channel in the multiplexed signal. Despite these and other advantages, OTDM is still way behind WDM when it comes to commercial maturity, with no OTDM systems currently available in the telecommunications market. However, the technologies required to implement high-speed OTDM systems (outlined in Table 2), including ultrashort pulse sources, clock extraction circuitry, and demultiplexing devices, are developing rapidly. It therefore seems

Table 2 Main elements of an OTDM communications system

Device	*Principal function*	*Technical implementation*
Optical pulse source	Generate ultrashort optical pulses suitable for transmission in high-speed OTDM systems	Gain-switching, mode-locking, or external modulation techniques
Multiplexer	Multiplex individual pulse data channels in the temporal domain using appropriate delays to achieve an OTDM signal	Passive couplers with fixed fiber delay lines, or planar waveguide circuits (for accurate control of delays)
Optical amplifier	Amplify the OTDM signal during fiber transmission to overcome fiber loss	Fiber doped with rare earth materials (e.g. erbium) in conjunction with pump laser
Transmission fiber	Transmit the OTDM data signal from transmission site to required receiver	Standard single-mode fiber, dispersion shifted fiber, or other specialty fiber may be used
Clock recovery	Extract clock (at base rate of individual channels) from OTDM data signal at receiver, for use in demultiplexing	Electronic or optical phase-locked loops, self-pulsating lasers, or mode-locked ring laser techniques
Demultiplexer	Demultiplex one of the channels from the overall OTDM signal	Interferometric or four-wave mixing techniques based on fiber or semiconductor nonlinearity
Add/drop demultiplexer	Extract one channel from OTDM data signal, and insert a local channel into the empty time slot for transmission	Similar technical implementations to demultiplexer described above

likely that in the future, OTDM technology may be used for enhancing the overall capacity of optical communication systems.

One possibility for employing OTDM systems would be for upgrading installed WDM networks. The current method for improving WDM networks involves using more wavelength channels, but it may also be feasible to increase the overall capacity by developing hybrid WDM/OTDM communications systems. In such a system, each wavelength channel may carry aggregate data rates in excess of 100 Gbit/s, achieved using OTDM. The design of these hybrid networks would permit switching of the optical data signals to be carried out at two different levels in the overall network. The WDM signals could be switched coarsely using passive filtering devices, and the OTDM data channels could be switched with fine granularity using one of the all-optical switching techniques available.

List of Units and Nomenclature

Dispersion	[ps km^{-1} nm^{-1}]
Transmission data rate	[bit s^{-1}]
ADM	Add drop multiplexer
CW	Continuous wave
FWM	Four-wave mixing
NOLM	Nonlinear optical loop mirror
OTDM	Optical time division multiplexing
SDH	Synchronous digital hierarchy
SOA	Semiconductor optical amplifier
STM	Synchronous transport module
TOAD	Terahertz optical asymmetric demultiplexer
WDM	Wavelength division multiplexing

See also

All-Optical Signal Regeneration. **Optical Communication Systems:** Basic Concepts; Wavelength Division Multiplexing.

Further Reading

Agrawal GP (1997) *Fibre Optic Communications*, 2nd edn., pp. 329–335. New York: Wiley.

Cole M (2000) *Introduction to Telecommunications: Voice, Data, and the Internet*, chapter 5. Englewood Cliffs, NJ: Prentice Hall.

Islam M (1992) *Ultrafast Fiber Switching Devices and Systems*. Cambridge, UK: Cambridge University Press.

Kawanishi S (1998) Ultrahigh-speed optical time-division-multiplexed transmission technology based on optical signal processing. *IEEE Journal of Quantum Electronics* 34: 2064–2079.

Midwinter JE and Guo YL (1992) *Optoelectronics and Lightwave Technology*, pp. 148–178. Chichester, UK: Wiley.

Mukherjee B (1997) *Optical Communications Networks*, pp. 493–506. New York: McGraw-Hill.

Nakazawa M, Kubota H, Suzuki K, Yamada E and Sahara A (2000) Ultrahigh-speed long distance TDM and WDM soliton transmission technologies. *IEEE Journal of Selected Topics in Quantum Electronics* 6: 363–396.

Prucnal PR, Santoro MA and Sehgal SK (1986) Ultrafast all-optical synchronous multiple access fiber networks.

IEEE Journal of Selected Areas of Communication 4: 1484–1493.

Spirit DM, Ellis AD and Barnsley PE (1994) Optical time division multiplexing: systems and networks. *IEEE Communications Magazine* 32(12): 56–62.

Spirit DM, Blank LC and Ellis AD (1995) Optical time division multiplexing for future high capacity network applications. In: Smith DW (ed.) *Optical Networking Technology*, pp. 54–77. London: Chapman and Hall.

Tucker RS, Einstein G and Korotky SK (1988) Optical time-division multiplexing for very high bit rate transmission. *IEEE Journal of Lightwave Technology* 6: 1737–1749.

Wavelength Division Multiplexing

J Bowers and H F Chou, University of California, Santa Barbara, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Wavelength division multiplexing (WDM) has enabled a revolution in communications technology. This article describes the technology, critical components of WDM systems, and transmission impairment and limits to transmission distance and capacity.

Multiplexing

There are three techniques used in fiber optics to multiplex the information that is transmitted from one point to another. The first is space division multiplexing (SDM), which simply consists of having multiple fibers in a cable or conduit. In a typical installation, there may be between 8 and 1000 fibers in parallel. The second approach is time division multiplexing (TDM) (*see* **Optical Communication Systems:** Optical Time Division Multiplexing), which consist of interleaving multiple data streams into one higher bit rate stream. For example, 672 voice channels (DS0) at 64 kbit/s are multiplexed into one T1 data stream at 1.544 Mbit/s. Eighty-four of these T1 channels are then multiplexed into a SONET (Synchronous Optical NETwork) OC-3 signal at 155 Mbit/s. The third multiplexing approach is wavelength division multiplexing (WDM), which consists of sending multiple signals at different wavelengths. These signals can be used to fill up the entire low loss transmission band of an optical fiber (Figure 1). The low loss transmission band extends from 1200 nm to 1600 nm, which corresponds to over 40 THz. One approach is to pack the signals densely together, as in dense wavelength division multiplexing (DWDM). This is a relatively expensive, but very high capacity approach. The other approach is to space the signals widely apart, (coarse WDM or CWDM) resulting in very low cost components, but with fairly limited transmission capacity.

Dense Wavelength Division Multiplexing (DWDM)

Most DWDM systems use multiple beams spaced at 100 GHz spacing centered at 193.1 GHz as defined by an International Telecommunications Union (ITU) standard (Figure 2a). Some higher capacity systems use finer spacing, 50, 25, or even 12.5 GHz spacing to pack more information into the fiber. The 100 GHz spacing used in DWDM systems corresponds to 0.8 nm spacing at 1.55 mm. In principle, 40 THz of information can be sent down an optical fiber. If high spectral efficiency (~1 bit/Hz) is maintained across the band, then this would correspond to 40 Tbit/s. Practical DWDM systems are limited by the bandwidth of erbium-doped fiber amplifiers (EDFAs) and by signal impairments discussed below. Consequently, most systems utilize a single band, typically the C-band extending from 1530 nm to 1565 nm. Additionally some transmission systems use multiplexers to combine other bands, typically C and L bands for additional transmission capability. The wavelength definitions are shown in Figure 1. Subbands are often used within a band to facilitate adding and dropping a group of wavelengths within a band. Typically 40 10 Gbit/s signals spaced at 100 GHz are used to fill the C-band. Higher capacity



Figure 1 Transmission spectrum of optical fiber. Also shown are the standard transmission bands.

systems with 80 to 200 wavelengths have also been deployed commercially.

The historical evolution of optical transmission systems can be seen in Figure 3. The lower line shows the increasing bit rate demonstrated in experimental TDM systems, which began in 1978 with 45 Mbit/s systems and has now reached 1.28 Tbit/s. The upper line shows what has been demonstrated with DWDM with over 10 Tbit/s transmission demonstrated.

Coarse Wavelength Division Multiplexing (CWDM)

The fine frequency requirements of DWDM systems result in significant cost for transmitters, multiplexers and other components. A low-cost approach is to space the colors widely apart. The ITU standard is 20 nm spacing from 1271 to 1611 nm (Figure 2b). Note that the spacing is uniform in wavelength, but varies in frequency because the frequency spacing is related to the wavelength spacing by

$$\Delta f = -\frac{c}{\lambda^2}\Delta\lambda \qquad [1]$$

The wide spacing of signal wavelengths means that temperature stabilization of elements is not needed and the yield of components is high, resulting in a lower-cost system.



(a) Dense wavelength division multiplexing spectrum



(b) Coarse wavelength division multiplexing spectrum

Figure 2 (a) DWDM spectrum (b) CWDM spectrum.

Point-to-Point DWDM Links

Point-to-point DWDM links were widely deployed during the 1990s. The essential elements are shown in Figure 4, namely single frequency lasers, optical multiplexers and demultiplexers, optical amplifiers, optical add drop multiplexers (OADM), and optical receivers. These will be described in more detail in subsequent sections. Essential parts of the design of these links are managing the signal-to-noise ratio and managing the pulse broadening. With periodic amplification in EDFAs and dispersion compensation, links of 1000 km are common. The widespread use of forward error correction (FEC) circuits allows error-free transmission over a link with limited signal-to-noise ratio. With careful design, ultra-long-haul



Figure 3 Historical evolution of transmission systems.


Channel 1
Channel 2
Channel 3
Channel 4
λ_1
λ_2
λ_3
λ_4
Mux
EDFA
Fiber
DeMux
Channel 1
Channel 2
Channel 3
Channel 4

Figure 4 Point-to-point WDM link.


Hub
$\lambda_1, \lambda_2, \dots \lambda_N$
OADM
λ_i λ_i
OADM
λ_k λ_k
OADM
λ_j λ_j
(a)
MSPP
Router
1 GbE
10 GbE
Collector ring
Photonic switches
OXC
DWDM
DWDM
Collector ring
DS3
OC-3
Ring DWDM
ADM
OC-48
OC-192
DS3
OC-3
Collector ring
MSPPs
DS3
OC-3
OC-12
OC-48
IGE
Lambda service
(b)

Figure 5 (a) WDM ring network. (b) DWDM mesh networks (after Basch B, Gringeri S, Goudreault R and Ravinkumar S (2002) Evolution of the photonic core within metropolitan and regional networks. *NFOEC*. Technical Proceedings).

transmission over 5000 km is possible, even with many 10 Gbit/s channels.

DWDM Networks

Point-to-point DWDM links are widely deployed in opaque networks with electronic regeneration and switching at nodes. The next stage in optical networks is the deployment of DWDM transparent ring and mesh networks. An example of a simple ring network is shown in Figure 5a where most of the light signals transit nodes transparently. The OADM elements drop particular wavelengths at each node. As more wavelengths are deployed in these ring networks, it becomes necessary to dynamically reallocate wavelengths and resources. Reconfigurable optical add/drop multiplexers (ROADMs) and optical switches have been developed to allow for dynamic transparent mesh networks (Figure 5b). This allows service providers to provision their networks remotely and quickly adapt to changing demand and restore vital connections when service interruptions occur.

Critical WDM Components

The previous sections described WDM networks. This section describes in more detail the critical components used in these networks.

Multiplexers/Demultiplexers

Multiplexers (MUXs) are used to combine multiple wavelength channels into a single fiber. They are usually wavelength selective and utilize wave phenomena such as diffraction and interference. A simple cascade of 3 dB couplers is not a practical multiplexer since the output power decreases exponentially with channel count. Due to the reciprocity of electromagnetic waves, most MUXs can also serve as a DEMUX. For high channel count systems, a multistage design may be necessary to overcome the limitations of a single MUX/DEMUX. This approach also provides a more flexible upgrading plan. In this case, wavelength channels can be grouped into bands or interleaved. Diffraction gratings and arrayed waveguide gratings (AWGs) are among the available technologies for MUX/DEMUX.

In a diffraction grating, narrow slits or micro structures are spaced evenly on the grating plane and serve as a secondary light source for the input light. The transmitted or reflected light (depending on the design) forms a diffraction pattern on the image plane. The locations of peak intensity on the image plane depend on the wavelength and the grating pitch. Therefore, wavelength channels can be separated in space and fibers can be positioned properly to couple individual channels. An AWG is a planar integrated and digitized form of diffraction grating as shown in Figure 6. It is usually fabricated on a silicon substrate with silica waveguides (silica-on-silicon). The input light is coupled into an array of waveguides with incremental difference in length. These tributaries are then combined in a free-propagating output coupler to several output waveguides. Due to the interference of these tributaries from the arrayed waveguides, different wavelength channels are focused to different output waveguides.



Figure 6 Schematic diagram of an AWG.

Optical Add/Drop Multiplexer

An optical add/drop multiplexer (OADM) provides critical networking capability for WDM systems. In an OADM, some of the wavelength channels are dropped from the input and are either terminated or routed. New channels at these wavelengths are then added with the through channels. This function can be done with the combination of a MUX and a DEMUX of any kind as shown in Figure 7a. However, if only one wavelength channel needs to be processed while others pass through, a simpler configuration can be used where a circulator drops the reflected wavelength from the fiber Bragg grating and a new channel is added with a coupler (Figure 7b).

The two approaches described above are termed static since the wavelength processed is fixed. To enable a more flexible network, reconfigurable OADM (ROADM) are required, where the wavelengths to be added or dropped can be dynamically specified. Figure 7c shows a configuration of ROADM based on a high port-count optical switch and a set of MUX/DEMUX. A tunable laser is highly desirable in this scenario since the wavelength of the added channel can be reconfigured to resolve wavelength contention in the network.

Optical Amplifiers

Erbium-doped fiber amplifiers (EDFA) (*see* **Optical Amplifiers:** Erbrium Doped Fiber Amplifiers for Lightwave Systems) provide simultaneous amplification of wavelength channels in the entire C-band (1530 to 1565 nm) and part of the L-band (1565 to 1605 nm). EDFAs were a key enabling technology for the deployment of WDM systems, especially for long-haul transmission where costly regenerators were eliminated. Both 980 nm and 1480 nm pumps can be utilized to achieve gain in erbium-doped fibers. The 980 nm pumps provide low-noise and high-gain operation while the 1480 nm pumps are more favorable for high-output power. One of the most significant advantages of an EDFA over a semiconductor optical amplifier (SOA) is that crosstalk among wavelength channels is much smaller in EDFA due to a millisecond-scale spontaneous emission lifetime. One critical issue for EDFAs is that the gain is not flat over the operation wavelength range and peaks around 1532 nm. However, this can be equalized by specially designed filters.


λ_1
λ_2
λ_3
λ_N
$\lambda_{1'}$
$\lambda_{2'}$
$\lambda_{3'}$
λ_N
DEMUX
MUX
$\lambda_1, \lambda_2, \lambda_3, ..., \lambda_N$
$\lambda_{1'}, \lambda_{2'}, \lambda_{3'}, ..., \lambda_N$
(a)
Drop
Add
Circulator
Fiber Bragg grating
$\lambda_1, \lambda_2, \lambda_3, ..., \lambda_N$
λ_2
$\lambda_1, \lambda_{2'}, \lambda_3, ..., \lambda_N$
Add $\lambda_{2'}$
(b)
Drop λ_2
λ_1
λ_2
λ_3
λ_N
DEMUX
Optical switch
λ_1
λ_2
λ_3
λ_N
MUX
$\lambda_1, \lambda_2, \lambda_3, ..., \lambda_N$
$\lambda_1, \lambda_2, \lambda_3, ...,$
$\lambda_{j'}, \lambda_{k'}, ..., \lambda_N$
(c)
$\lambda_j, \lambda_{j'}$
$\lambda_k, \lambda_{k'}$

Figure 7 (a) A parallel OADM architecture which allows multiple simultaneous add's and drop's; (b) a linear OADM architecture for processing a single channel; (c) an ROADM which enables reconfigurable processing of multiple wavelength channels.

Outside the gain spectrum of EDFAs, Raman amplifiers can be used, where the gain peak is about 13 THz (100 nm) below the frequency of the pump signal. Also, Raman amplification occurs in the same fiber used for transmission so that it can provide a distributed gain over the span of the fiber, which results in a better signal-to-noise ratio. This is particularly important for ultra-long-haul transmission. A counter-propagating pump scheme is preferable to reduce the influence of pump noise and depletion. The biggest challenge for Raman amplifiers is the availability of high-power pump lasers at the required wavelengths.

Optical Filters

Filters can find many applications in WDM systems, such as in multiplexers, demultiplexers, OADM, receivers and optical amplifiers. Fiber Bragg grating, Fabry–Perot filter, and multilayer thin-film filters are among the most widely used filters and utilize the interference property of optical waves. There are some general requirements for filters in WDM systems. First, the top of the pass-band must be flat enough so that cascading of filters in the network does not lead to a significant decrease of bandwidth. In addition, the roll-off of the pass-band must be sharp so that cross-talk from other channels is minimized.

A fiber Bragg grating has a periodic perturbation of refractive index made by exposing a photosensitive fiber to interfering ultraviolet lights. These perturbations reflect the input light as it propagates. At a specific wavelength, these reflected beams add in phase, which results in a strong overall reflection. The reflections at other wavelengths do not add up and these wavelengths will eventually pass through the grating. In short, the fiber Bragg grating acts as a wavelength-selective reflector and is usually used with a circulator or isolator to manage the reflected light. A Fabry–Perot filter is composed of two partially transmitting interfaces and a cavity in between. The underlying mechanism is similar to the fiber Bragg grating but the transmission is periodic in optical frequency. The spacing is called the free spectral range, which depends on the optical length of the cavity. The bandwidth of the passband is a strong function of the reflectivity of the partially transmitting interfaces. A multilayer thin-film filter is an extended form of Fabry–Perot filter where several layers of dielectric reflectors are formed with dielectric cavities in between. This allows for more tuning dimensions in the design of the passband shape in order to meet the requirements of WDM systems and the temperature tolerance is better than other kinds of filter.

Laser Sources

Semiconductor lasers (*see* **Lasers:** Semiconductor Lasers) are widely used in optical communication because they are compact, low cost and efficient. As a light source for transmission, single frequency operation is necessary for high-capacity WDM systems. Multilongitudinal mode lasers such as Fabry–Perot lasers have excess bandwidth which causes excessive penalty due to dispersion unless the transmission distance is short. They also result in crosstalk in DWDM systems. The most widely used single-frequency laser in WDM systems is the distributed-feedback laser (DFB), where a corrugated grating structure is fabricated on top of the gain region and only the wavelength which satisfies the Bragg condition can oscillate in the laser cavity and all other modes are suppressed.

As WDM networks advance, tunable lasers are strongly desired to reduce the excessive inventory of fixed wavelength lasers for DWDM and also to provide reconfigurability in the network. One possible structure is the distributed Bragg reflector (DBR) laser, in which the Bragg grating is decoupled from the gain region and the Bragg wavelength can be tuned independently by isolated current injection. More complicated variations of this concept such as the three-section DBR laser and the sampled grating DBR laser can provide more continuous and wider tuning in wavelength.

Photonic Switches

Photonic switches are necessary in transparent networks to allow reconfigurability in networks, and allow rapid provisioning and fault recovery. They provide connectivity between rings and between point-to-point links without requiring the DWDM signal to be broken into individual wavelengths and to be electronically regenerated. Photonic switches can be used to switch fibers, wavebands, or individual wavelengths. They are inherently transparent to bit-rate and data format. A number of different technologies have been developed.



Figure 8 3D MEMS optical switch.

Microelectromechanical system (MEMS) switches are widely used for 2 × 2 protection switches, wavelength selective switches and for nonblocking crossbar switches with sizes from 8 × 8 to 1024 × 1024. The technology usually used for large switches is called 3D MEMS switches (Figure 8), in contrast to 2D technologies where the optical beams are confined to a two-dimensional plane.

Transmission Issues

Chromatic Dispersion

Chromatic dispersion (*see* **Fiber and Guided Wave Optics:** Dispersion) means that the group velocity, which is the propagation speed of an optical signal, changes with wavelength. Since every real pulse has a finite bandwidth, each slice of wavelength within this bandwidth propagates with a different speed and results in the distortion of the pulse as it propagates along the fiber. Depending on the sign of the dispersion and the initial phase distribution, the pulse can either be broadened or compressed. However, if the fiber is long and nonlinear effects are small, the pulses will eventually be broadened and result in intersymbol interference. Dispersion compensating fibers (DCFs), which have an opposite sign of dispersion, can be used to reverse this process and restore the original pulse shape. In general, it is advantageous to minimize the length of DCF by keeping the dispersion low. Dispersion-shifted fibers (DSF) have a zero-crossing of dispersion around 1.5 μm and hence a reduced dispersion for the C-band.

For a WDM system, a very low dispersion will result in more severe nonlinear impairments since the distance pulses can overlap with each other along the fiber is long. Nonzero-dispersion-shifted fibers

(NZ-DSF), which introduce a suitable amount of dispersion, can be used instead to solve this issue. Chirped fiber Bragg grating can also be used, where different wavelengths are reflected at different positions in the grating so as to compensate the dispersion caused by transmission. It is capable of compensating a given amount of dispersion with a much shorter length when compared to DCF. For high channel count WDM systems, the dispersion experienced by each channel may be different and dispersion compensation needs to be implemented on a per-channel basis after a demultiplexer.

Polarization Mode Dispersion

Polarization mode dispersion (PMD) means that the group velocity dispersion of the two orthogonal polarizations in the fiber are different and cannot be simultaneously compensated by a single DCF. It is usually manifested as the splitting of a pulse at the receiver even after chromatic dispersion compensation and causes intersymbol interference. PMD can originate from the imperfections in the fiber or environmental factors like temperature and mechanical pressure. Therefore, the amount of PMD can vary with time for a given link, which means that dynamic compensation is necessary. Traditional electrical equalization after the optical signal is detected can be used for compensation but the highest bit-rate achievable is limited by the speed of electronics. Optical compensation is another choice. The optical signal is split into fast and slow components and the fast component is delayed properly before being recombined with the slow component.

Nonlinear Impairments

The most important nonlinear impairments for WDM systems are the cross-phase modulation (CPM) and the four-wave mixing (FWM). They are both third-order nonlinear effects, where the nonlinear dielectric polarization is proportional to the third power of the electric field of the signal. In CPM, the phase of a wavelength channel can be modified by other channels, which increases the chirp and results in more dispersion penalty. On the other hand, FWM can generate new waves at other wavelengths, causing unwanted crosstalk if the generated wave happens to coincide with another channel. The existence of dispersion in fiber can help to reduce the effects of both impairments since the pulses at different wavelengths propagate at different speeds and walk away from each other so that nonlinear interactions are reduced. This is why NZ-DSF is preferred over DSF. Self-phase modulation (SPM) is another third-order nonlinearity, where the phase distribution of a pulse is altered by its intensity profile. It will lead to the distortion of the pulse. Other nonlinear effects include stimulated Brillouin scattering and stimulated Raman scattering. Both originate from the interactions of phonons and photons in the fiber and cause power fluctuations at different wavelengths.

Forward Error Correction

To reduce the errors of a transmission link, extra information relating to the data can be sent by the transmitter and used by the receiver to detect and correct errors in the received data. This technique is called forward error correction (FEC) and imposes redundancy to the transmission which means that the bit-rate transmitted will be higher than the actual data rate. A measure of performance for FEC is the coding gain, which is defined as the decrease in receiver sensitivity at a given bit-error-rate. Reed–Solomon codes are one of these codes. With a 7% redundancy, up to 6 dB of coding gain can be achieved. This could correspond to more than 9 orders of magnitude improvement in bit-error-rate. Therefore, the use of FEC can increase the spacing between regenerators in ultra-long-haul transmission and reduces the cost. It is also useful to overcome error floor problems due to crosstalk in a WDM system, where a further increase in received power cannot reduce the bit-error-rate. Crosstalk among wavelength channels can happen due to nonlinear impairments during fiber transmission or due to imperfect channel isolation in components like multiplexers, demultiplexers, filters, and switches. The use of FEC can greatly increase the system margin.

Conclusions

WDM technology has enabled a huge increase in the transmission capacity of optical fibers and a huge reduction in the cost of fiber optic transmission since the cost of the installed fiber is shared between the signals traveling on different wavelengths. As new components have been developed, WDM technology has expanded simple point-to-point links to transparent networks. Great progress has been made over the past 20 years to solve transmission impairments and extend the reach and bandwidth of these systems. This is likely to continue to meet the increasing communication needs of our society.

List of Units and Nomenclature

Distance (km, m, μm)
Bit rate (bit/s)
Wavelength (nm)

See also

Color and the World. **Information Processing:** All-optical Multiplexing/Demultiplexing. **Fiber and Guided Wave Optics:** Optical Fiber Cables; Passive Optical Components. **Lasers:** Edge Emitters; Semiconductor Lasers. **Modulators:** Modulation and Demodulation of Optical Signals. **Optical Amplifiers:** Basic Concepts; Optical Amplifiers in Long-Haul Transmission Systems; Semiconductor Optical Amplifiers; **Optical Communication Systems:** Architectures of Optical Fiber Communication Systems; Basic Concepts; Historical Development; Lightwave Transmitters; Optical Time Division Multiplexing. **Solitons:** Soliton Communication Systems.

Further Reading

Agrawal GP (2002) *Fiber Optic Communication Systems*, 3rd edn. New York: John Wiley & Sons Inc.

Basch B, Gringeri S, Goudreault R and Ravinkumar S (2002) Evolution of the photonic core within metropolitan and regional networks. *NFOEC*. Technical Proceedings.

Green PE (1993) *Fiber Optic Networks*. Upper Saddle River, NJ: Prentice Hall.

Ramaswami R and Sivarajan KN (2002) *Optical Networks: A Practical Perspective*, 2nd edn. San Francisco, CA: Morgan Kaufmann Publishers.

OPTICAL MATERIALS

Contents

Color Filter and Absorption Glasses
Heterogeneous Materials
Lightweight Mirrors
Measurement of Optical Properties of Solids
Optical Glasses
Plastics
Sculptured Thin Films
Smart Optical Materials
Sol-Gel Materials

Color Filter and Absorption Glasses

J E Shelby, Alfred University, Alfred, NY, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical filter and absorbing glasses can be categorized by either the optical behavior of the filter, for example, bandpass, shortpass or longpass, neutral density, or interference filters – or by the method used to filter the light, i.e., glasses which absorb light themselves and those which serve as high quality, transparent substrates for coatings which either absorb or reflect light. The term ‘filter’ usually refers to glasses used in optical systems, to either transmit or prevent transmission of specific wavelengths. The term ‘absorber’ is usually reserved for glasses which are used for controlling light to provide protection from damage to humans, for example, for eye protection, as in sunglasses, or welder and laser goggles, or to materials exposed to light, for example, plastics and other components in the passenger compartment of automobiles. Manufacturing technology is normally based on the method used to produce the device, such as control of absorbing species in the glass or method of application of optical coatings. Terminology for optical applications is almost always based on optical behavior and not on the method used to produce that behavior.

Bandpass Filters

The first glasses used to filter light were colored by inclusion of ions from the first row of transition metals. These colored glasses still provide most of



Figure 1 Transmission spectra for bandpass filters with a large bandwidth (solid line), medium bandwidth (dashed line), and narrow bandwidth (dot dash line).

the glasses used to control the wavelength of light. They are widely used as absorbers in windows in buildings and automobiles, to control the entrance of ultraviolet and infrared light into these environments. These filters allow the passage of light over a significant range of wavelengths, while absorbing wavelengths outside that range. They are designated by the peak transmission wavelength, or central wavelength, and the bandwidth, or wavelength range, over which light is transmitted with at least some designated transmission value. Filters based on absorption by transition metal or rare earth ions usually have larger bandwidths and somewhat diffuse cutoffs at the edges of the transmitted spectral region (Figure 1).

The most common bandpass filters absorb radiation in a desired wavelength region. Historically, the first bandpass filters, which are still the most common, relied on absorption of light as a result of ligand field (also known as crystal field) effects and/or charge transfer processes within a glass, to create absorption bands in the spectrum.

Ligand field effects will produce optical absorption bands in glasses which contain transition metal (usually row 3d) or rare earth (lanthanide, or 4f) ions. The differences in the electronic structures of the transition metal and rare earth ions result in very different absorption spectra. Absorption spectra, due to transition metal ions, are characterized by broad bands and are frequently accompanied by charge transfer bands, due to the same ions, while the bands due to absorption of light by rare earth ions are very sharp and are not accompanied by charge transfer absorption bands.

Iron oxide was probably the first, and is still the most widely used additive for production of glasses which primarily transmit light in the visible portion of the spectrum. A large, broad absorption band due to ferrous ions is centered at ≈1050 nm in common soda-lime-silica glasses. The tails of this band extend into the visible portion of the spectrum, allowing passage of the blue-green portion of the spectrum, but absorbing much of the red light, and to wavelengths in excess of 2000 nm, absorbing much of the near infrared spectrum.

Ferric iron produces relatively small ligand-field absorption bands in the region from 380 to 440 nm. These bands remove most of the blue part of the spectrum, allowing passage of light with longer wavelengths. Both ferrous and ferric ions also display charge transfer bands in the ultraviolet, effectively eliminating transmission of light with a wavelength <300 nm. Glasses containing enough iron oxide, to effectively eliminate both ultraviolet and near infrared transmission, exhibit various shades of green, depending on the ratio of ferrous to ferric ions present. Melting under strongly reducing conditions yields blue-green glasses, whereas melting under strongly oxidizing conditions yields yellow-green glasses. Glasses containing ≧0.5 wt% iron oxide are used in windows of automobiles to minimize the amount of ultraviolet and infrared radiation entering the passenger compartment.

Copper oxide is also used to remove a portion of the near infrared spectrum from sunlight and to produce glasses which transmit in the green and blue region. The primary ligand-field absorption band of copper is due to cupric ions and is located near 800 nm. This band in similar in shape to that due to ferrous ions, with tails extending into the visible and near infrared regions of the spectrum. The shift in band position toward the visible, however, results in less absorption in the infrared and more in the visible than for ferrous iron. As a result, glasses containing copper are more strongly colored than those containing ferrous iron and are less effective filters for infrared light. Glasses colored with cupric ions can be used to produce a transmission window from about 350 to 600 nm in soda-lime-silica glasses. Cuprous ions do not create any significant absorption bands.

Glasses containing hexavalent chromium, which must be produced in a strongly oxidizing environment, effectively remove ultraviolet light between 300 and 400 nm, but allow transmission of ultraviolet light in a narrow range centered around 300 nm. A small tail of the charge transfer band due to Cr^{6+}extends into the visible, producing a yellow-green glass. The presence of a set of much weaker ligand-field bands, centered around 650 nm due to trivalent chromium, also contributes to the green color of these glasses. Combining chromium with copper ions in a glass yields a filter with a small transmission window centered at about 520 nm.

Combination of chromium with iron results in suppression of both hexavalent chromium and ferrous iron, yielding a green glass without either the strong ultraviolet absorption of hexavalent chromium or the strong near infrared absorption of ferrous iron.

Manganese oxide can be used to produce bandpass filters which block most of the visible, but allow transmission of ultraviolet and infrared light. Addition of manganese ions to a glass results in a set of absorption bands with a maximum intensity at about 500 nm and a tail extending to around 900 nm. Since these ions do not absorb in the ultraviolet, the transmission spectra of these glasses has a window between about 300 and 400 nm, which overlaps the transmission window due hexavalent chromium. The absorption bands due to manganese ions are relatively weak, so that concentrations of manganese oxide in excess of 1 wt% are needed to effectively block visible transmission.

Cobalt oxide is the strongest colorant of the oxides of 3d transition metals. A small addition of cobalt oxide to silicate glasses creates strong absorption bands between about 450 and 700 nm. The optical window of these glasses in the ultraviolet is centered near 380 nm and is somewhat broader than that of glasses containing manganese oxide, which have similar spectra. Since cobalt oxide is such a strong absorber, black glasses are easily produced by use of cobalt oxide in combination with other oxides. If cobalt oxide is combined with nickel oxide, the resulting glass retains a bandpass in the ultraviolet, while combining cobalt oxide with iron oxide, which has a complementary absorption spectrum, yields a black glass which also effectively eliminates transmission in the ultraviolet and near infrared.

The optical spectra of glasses containing most rare earth ions are characterized by sharp absorption bands. Some rare earth ions create spectra with many absorption bands, while others display only a few bands. The band structures which result from rare earth ions are not particularly useful for creation of bandpass filters, although Yb^{3+} ions do effectively remove light around 1100 nm, without absorbing light in the rest of the spectrum.

While not commonly used for filters, glasses containing rare earth ions have been used for wavelength calibration standards for uv-vis spectrophotometers. A common wavelength standard called a ‘didymium’ glass contains a combination of neodymium and prasedymium oxides. Since the optical spectrum from each of these ions contains many sharp bands, these glasses provide known wavelengths for absorption bands over a wide region of the spectrum. Neodymium ions, which have absorption bands near the D line of sodium, are used in goggles for eye protection for glassblowers, to remove the intense yellow light resulting from the sodium in the glass.

Interference Filters

Interference filters are a special case of bandpass filters which are created by application of dielectric films to glass substrates. The dielectric films are deposited on a glass substrate in alternating layers of high and low refractive index materials. The combination of refractive indices and thickness of the dielectric films determines the wavelength regions where constructive and destructive interference occur, i.e., those wavelength regions which will transmit or reflect the incident light. Since the choice of materials will control the indices, production of filters for different wavelengths usually relies on deposition of layers of differing thicknesses.

These filters can be produced with very narrow bandwidths (±10 nm) or with broader bandwidths (commonly ±50 or ±80 nm). The peak transmission frequently does not occur at the midpoint of the bandwidth. Since the wavelengths for constructive and destructive interference depend upon the path length through the dielectric layers, these filters are extremely dependent upon the incident light angle, with a shift toward lower wavelengths for incident angles other than normal to the filter surface. Interference filters typically reduce throughput of light as compared to absorption-based bandpass filters, but provide for much narrower transmission windows. If the dielectric layers are deposited in such a manner that their thickness varies along the length of the substrate, interference filters can be produced with a continually varying central transmission wavelength along the length of the substrate. While convenient for applications, which might otherwise require several filters of different central wavelengths, these linearly variable interference filters are much more expensive than those designed to block specific wavelengths.

Dispersion Filters

Dispersion filters are based on the passage of light through a medium consisting of a matrix material and dispersed, very small particles of a material which has a very different dispersion curve. The original version of these filters, called a Christiansen filter, consists of small glass particles with a controlled particle size suspended in a liquid. The dispersion curve for the glass is much less wavelength-dependent than that of the liquid. Transmission of light occurs at the wavelength where the refractive index of the glass and the liquid are equal, while light of other wavelengths is scattered. Since the refractive index of a typical liquid is highly temperature sensitive, the transmitted, or peak, wavelength can be shifted over a wide region by controlling the temperature of the mixture. The bandwidth of dispersion filters can be very narrow (<± 10 nm).

The large temperature dependence of the traditional dispersion filter can be useful in that it provides an optical filter with an adjustable peak wavelength. On the other hand, this sensitivity to temperature also results in a serious control problem, since a temperature change of only a few degrees can shift the transmission window by up to 100 nm. This problem can be decreased or even eliminated by making a solid dispersion filter using two glasses of different dispersions, with one glass distributed in the other, or a glass dispersed in some other transparent solid such as a polymer with a similar thermal expansion coefficient. Since the refractive index of solids tends to vary with thermal expansion coefficient, these solid state dispersion filters can be almost temperature independent.

Neutral Density Filters

Neutral density filters are used to reduce the throughput of light to some desired value over a wide spectral region. Gray glasses are used to reduce the intensity of light from a bright source such as the sun. Black glasses are used to completely block light in the visible region. Neutral density filters can be produced using a combination of transition metal ions or by use of optical coatings. They are characterized by their percent transmission, range of wavelength where the transmission is constant, and the 'ripple', or spectral flatness, within the designated spectral region (Figure 2).



Figure 2 Transmission spectra for neutral density filters with different % transmission.

An approximation to a neutral density filter for visible light is often created by combining the absorptions in the ultraviolet and near infrared from ferrous and ferric ions, with the multiple absorption bands centered in the region of 500 to 600 nm due to divalent cobalt ions. While the resulting absorption spectrum displays small ripples throughout the region from 350 nm to beyond 1200 nm, the transmission of the glass can be controlled to within a few percent by the proper balance of ferric and ferrous ions combined with the desired concentration of CoO. These glasses are generally gray, or, if enough of iron and cobalt oxides are present, black. Combination of CoO with NiO can produce similar filters covering a smaller wavelength range which maintain transmission in the ultraviolet. Filters with different transmission values can be produced by either varying the composition of the glass or by use of different glass thicknesses. A continuously graded neutral filter can be produced from a single piece of glass by etching or polishing to form a wedge. With more effort, a step-graded filter can be produced by etching or polishing to form sharply delineated thickness steps along the length of a glass plate.

Neutral density filters can also be produced by coating a glass substrate with a metal film. Coated neutral density filters have less ripple than absorptive filters based on iron and cobalt oxides dissolved in the glass. In order to produce a constant transmission throughout the desired wavelength region, the metal used (commonly inconel) should have a constant reflectance across the desired wavelength region. Use of a metal with a varying wavelength dependence in its reflectivity, such as silver, will result in a wavelength dependent transmission. Continuously graded neutral filters can be produced by varying the thickness of the film along the length of a strip of glass.

Longpass/Shortpass Filters

Longpass filters are designed to pass light with wavelengths longer than the specified cutoff value. They are frequently used to block ultraviolet light while transmitting visible light or to block visible light while transmitting infrared light. Shortpass filters provide the opposite effect, i.e. they pass light with wavelengths shorter than the specified cutoff value, while blocking light with longer wavelengths. Shortpass filters are often used to block passage of heat (infrared light), while allowing transmission of visible light (Figure 3).

Ultraviolet blocking longpass filters can be produced by varying the basic composition of a glass or



Figure 3 Transmission spectra for longpass filters with different cutoff wavelengths.

by addition of specific ions which absorb strongly in the ultraviolet. Varying the primary glassforming oxide can alter the ultraviolet cutoff frequency of a glass. Vitreous silica, for example, has an ultraviolet cutoff beyond 200 nm, so that it is a very effective transmitter of ultraviolet light. Vitreous germania, on the other hand, has an ultraviolet cutoff near 400 nm, so that it acts as an effective longpass filter for most ultraviolet light. While vitreous silica is widely used as an optical material, the poor chemical durability of vitreous germania prevents its use in most optical applications.

The ultraviolet cutoff wavelength of silicate glasses is shifted toward the visible by addition of alkali and alkaline earth oxides to silica. The addition of these oxides creates nonbridging oxygens in the vitreous network, which shift the ultraviolet cutoff toward the visible. These glasses are effectively opaque beyond their cutoff wavelength, creating longpass filter glasses with cutoff wavelengths which vary with the nonbridging oxygen concentration. Impurities such as iron or copper can also reduce the ultraviolet transmission of silicate glasses due to the creation of charge transfer bands, producing longpass filters with cutoffs in the range of 250 to 300 nm.

Longpass filters with tightly controlled ultraviolet cutoff wavelengths are often made by adding either cerium or a combination of cerium and titanium oxides to silicate glasses. Additions of cerium oxide result in a strong absorption band near 320 nm, which provides protection from ultraviolet light. Cerium also is routinely used to reduce radiation-induced coloration of glasses exposed to high energy radiation. An absorption band due to trivalent titanium also serves to cut off ultraviolet light, while producing a yellow glass. The use of a combination of cerium and titanium produces a very effective ultraviolet filter which eliminates transmission of almost all ultraviolet light.

Long bandpass absorption filters can also be based on precipitation of colloids of metals or semi-conductors in an otherwise colorless glass. The glasses are initially prepared in a colorless state, with the materials which will form the colloids dissolved as ions. The glasses are then reheated into the glass transformation region, where the desired ions are reduced to the atomic state and precipitated as colloids. Since this process is known as 'striking', these filters are known as striking filters. Colloids can be produced by striking from several elements, including silver, gold, copper, arsenic, antimony, lead, and bismuth, and from a number of compounds, including the cadmium chalcogenides and ZnS.

Formation of silver colloids in common soda-lime-silicate glasses results in a very strong optical absorption band centered near 400 nm. Glasses containing silver colloids are yellow, with a bandpass window in the ultraviolet. Since these glasses absorb so strongly at a wavelength commonly used to irradiate photosensitive polymers in the production of electrical circuit boards, they are frequently used for the production of beam masks. A pattern of silver colloids is easily produced in the surface of common float glasses by depositing metallic silver through a mask onto the surface of the glass and then heating the glass to 500 °C for a short time.

Copper can also be used to form longpass filters with a cutoff in the red portion of the spectrum by a similar process to that used to form the silver colloid filters. In this case, it is necessary to use a copper salt in place of the metallic silver, but the remainder of the process is essentially the same (Figure 4).



Figure 4 Transmission spectra for longpass filters containing silver or copper colloids.

Precipitation of semi-conducting colloids containing CdS, CdSe, and CdTe in silicate glasses results in sharp cutoffs in the range from the near ultraviolet to the near infrared. The cutoff is the direct result of the bandgap of these crystallites. Since these materials form a broad series of solid solutions, the desired cutoff wavelength can be obtained by use of an appropriate mixture of two of these compounds in the glass batch. Glasses containing only CdS, for example, have cutoffs in the range of 400 to 500 nm. Combining CdS with CdSe will shift the cutoff toward the infrared, with cutoffs in the range of 500 to 700 nm. Combining CdS with CdTe produces glasses with cutoffs near the edge of the visible region. Use of CdTe alone results in filters with cutoffs around 800 nm.

While the most common explanation for the shift in the cutoff in glasses containing the cadmium chalcogenides is based on solid solution arguments, it has been shown that the size of the particles also strongly affects the position of the cutoff for glasses containing CdSe. In this case, the energy gap, which determines the cutoff wavelength, varies inversely with the square of the particle size.

Glasses containing CdS and ZnS can be heat-treated to form filters with cutoffs in the range from 340 to 518 nm. Heat treatment at lower temperatures yields CdS colloids, with a cutoff around 500 nm. At higher heat treatment temperatures, the absorption edge shifts toward the ultraviolet, approaching the value of 340 nm representative of the lattice absorption of ZnS. This behavior has been interpreted as indicating that CdS crystals precipitate at lower temperatures, while at higher temperatures, solid solution crystals of ZnS and CdS are formed.

Colloids of arsenic, antimony, bismuth, and lead form less interesting filter glasses. The optical properties of these metals are such that there is no sharp cutoff wavelength. Growth of colloids produces wavelength-dependent scattering, with a long tail extending into the visible or infrared. These glasses can be produced in colors ranging from light tan to black by progressive heat treatments of the originally colorless glasses in hydrogen. The hydrogen serves to reduce the ions to the atomic state. The atoms then diffuse to form colloids. The growth process creates a sharp interface between the colored and colorless region of the glass, which can be used to produce windows for visible light of highly transmitting glass surrounded by essentially opaque glass.

Absorber Glasses

Glass filters are used to remove unwanted wavelengths from light. When the application is less demanding than those of complex optical devices or systems, the glasses are commonly called 'absorbers' rather than filters. These applications usually involve protection of humans or materials from damage by light, for example, sunglasses and goggles for welders and glassworkers, or to enhance the environment by controlling the entrance or exit of ultraviolet and infrared light. Most of these applications are variations on the filters discussed above.

The most common use of glass as an absorber for both protection from damage and enhancement of the environment is found in the soda-lime-silicate glasses used as windows in buildings and automobiles. The presence of a relatively large concentration of iron oxide provides absorption in both the ultraviolet and infrared regions of the spectrum. Since glasses containing iron do absorb some light in the visible, a compromise between total absorption of unwanted, nonvisible light and the desired visible light must be made. As a result, these glasses usually contain between 0.5 and 2 wt% iron oxide. Changes in melting conditions which alter the ratio of ferrous to ferric ions in the glass are used to tune the glass for specific applications. While these glasses are technically broad bandpass filters, their common applications are based on the favorable location and bandwidth of their transmission window, which roughly corresponds to the visible region.

Iron is also used for protection from ultraviolet and infrared radiation in welder goggles. These glasses contain much more iron (up to 8 wt% or more) than those used for windows, since the demand for protection from the intense light created in welding is much greater. The high absorption coefficient for infrared light results in considerable heating of the glass during lengthy use. A thin film of gold is often applied to the glass to reflect infrared radiation and reduce heating of the glass.

Other absorber applications are more demanding in terms of absorption wavelength. As mentioned earlier, glasses containing neodymium have a strong absorption band at the wavelength of the yellow sodium emission line. These glasses transmit visible light at other wavelengths, allowing their use by glassblowers, who need to be able to see the unheated part of the glass and their immediate surrounding area, while simultaneously reducing the intense yellow light given off by the sodium in the glasses normally used for glassworking.

Protection of the eye from laser radiation is even more demanding due to the very high intensity over very narrow wavelength ranges. Common ultraviolet longpass filters are usually satisfactory for absorption of light from ultraviolet lasers. Specific ions must be added to glasses to provide protection from many visible and near infrared lasers, since the glass must simultaneously permit transmission of visible light of other wavelengths and total absorption at the laser wavelengths. Light from lasers which operate in the far infrared is readily absorbed by most glasses, since the infrared cutoff of oxide glasses lies around 5 micrometers. Great caution should always be used in selecting glasses for eye protection from lasers. No assumptions regarding the degree of protection should ever be made without insuring that the glass is designed for the conditions under which it will be used.

See also

Optical Coatings: Thin-Film Optical Coatings. **Optical Materials:** Optical Glasses.

Further Reading

Bamford CR (1977) *Colour Generation and Control in Glass*. Amsterdam: Elsevier Scientific Publishing Company.

Deeg EW (1986) Optical glasses. In: Boyd DC and MacDowell JF (eds). *Commercial Glasses*, pp. 1–34. Columbus, OH: The American Ceramic Society, Inc.

Edmund Industrial Optics Catalog N017 (2001) pp. 68–87. Barrington, NJ: Edmund Industrial Optics.

Hillmann E and Neuroth N (1998) Glasses for eye protection. In: Bach H and Neuroth N (eds). *The Properties of Optical Glass*, pp. 370–379. Heidelberg, Germany: Springer-Verlag.

Kolberg U (1998) Coloured glasses. In: Bach H and Neuroth N (eds). *The Properties of Optical Glass*, pp. 350–370. Heidelberg, Germany: Springer-Verlag.

Neuroth N (1998) Transmission and reflection. In: Bach H and Neuroth N (eds). *The Properties of Optical Glass*, pp. 82–95. Heidelberg, Germany: Springer-Verlag.

Paul A (1982) *Chemistry of Glasses*, pp. 204–276. London: Chapman and Hall.

Vogel W (1991) Optical properties of oxide glasses. In: Ullmann DR and Kreidl NJ (eds). *Optical Properties of Glass*, pp. 1–36. Westerville, OH: The American Ceramic Society, Inc.

Weyl WA (1951) *Coloured Glasses*. Society of Glass Technology: Sheffield, England.

Heterogeneous Materials

U Kreibig and M Quinten, Aachen University of Technology, Aachen, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The term heterogeneous materials – being a quite diffuse classification of matter with discrete building units of different kinds, irrespective of their sizes – is defined here by scaling these inhomogeneities in relation to optical light wavelengths. Matter consisting of atoms in a regular structural order (or, alternatively, in fully statistical disorder) is classified as homogeneous since the inhomogeneities are too small to effect optical fields. This applies to crystalline, liquid, and glassy or amorphous matter likewise.

All geometrical/topological and chemical heterogeneities on a larger length-scale than the atomic scale, i.e., single crystallites, organic macromolecules, domains, extended lattice defects, clusters, and nanoparticles of chemical compositions differing from their host material, etc., result in a macroscopic material that is heterogeneous, in optical properties and optical experiments. Examples are multilayer-structures, heterogeneous in one dimension, three-dimensional heterogeneous composites, i.e., isometric building units distributed in some homogeneous host (photographic systems, drugs, cosmetics, color pigments in binders, etc.), and three-dimensional heterogeneous densely packed systems (poly- or nanocrystalline materials, ceramics, or nanoceramics, etc.).

The materials most intensively investigated, in the field of nanoscience, represent a subclass of heterogeneous materials.

Most of the common materials in our everyday environment have heterogeneous structures, often on larger characteristic size-scales. More generally, heterogeneous materials are so widespread that they are much more frequent than homogeneous materials. Some more examples, relevant for their optical properties, may illustrate this: pigment colors, photovoltaic composites, aerosol-systems, hydrosol-systems, many minerals, photonic crystals, island film devices, nanosensors, special biosystems, and polymer-systems. Most interesting optical features arise when these inhomogeneities are below or of the order of light wavelengths. Recent research has concentrated on a narrow size region on the lower nanometer scale where many-atoms-systems change from molecular to solid-state behavior with increasing sizes. This ‘transition’ is accompanied by drastic changes of almost all physical and chemical properties, hence these properties develop strong dependences on particle size in that size region, and materials with uncommon properties can be developed.

In contrast to the widespread applications and research perspectives, the basic theoretical understanding of heterogeneous material is generally still poor. One reason is that, since the beginning of the development of optics as a science, the homogeneous materials like glass, water, etc. were preferentially treated since they were easier to describe theoretically. Another reason is the extremely wide variability of existing heterogeneous structures usually based upon low symmetries. This variability is too large, and the resulting optical properties too complex and multifarious to enable a general and uniform description of heterogeneous matter on a quantitative level, like the one successfully developed for the much simpler topology of homogeneous crystals.

Qualitative general features, however, can be obtained from investigations of model systems, with especially simplified topological structures. In the following we describe the model system of nanoparticle/host-matter (or, synonymously, cluster-matter), which is based upon nanoparticles/clusters packed closely in a host material, thus forming macroscopic or microscopic heterogeneous many-particle systems. Even this model system exhibits broad variability of topologies and of chemical compositions, as shown in Figure 1.

The restriction in the present contribution to this topologically simple model system appears to be justified by the fact that the optical properties discussed below for this system are also qualitatively characteristic of other arbitrary heterogeneous materials. We also admit that the nanos may consist of a nucleus and a surrounding shell of different structure and/or different material.

Heterogeneous matter can be defined by its heterogeneous building units and by the borders of these units and by the host material and the borders between building units and host, i.e., the internal interfaces.

It is a general feature that structures are visible because of property changes at their terminating borders: borders create structures, and structures require borders. The more refined the structures are, the more increases the topological extent of the borders. This means that when sizes of building units, for example, in cluster matter decrease, the relative amount and the effects of surface/interface regions increase. Such interfaces in heterogeneous matter are not two-dimensional (as suggested by the term 'interface') but consist of three-dimensional



Cluster	metal	semicond.	dielectr.	none
Shell	metal	semicond.	dielectr.	none
Matrix	metal	semicond.	dielectr.	none

Figure 1 Examples of heterogeneous nanoparticle/host materials. Left: possible material combinations of the three building units: cluster, shell, matrix. Right: some examples of sample topologies.

interlayers, the atomic and electronic structure and the chemical composition of which are usually in complex disorder. In the case of very small particles the interface volume can easily exceed the volume of the building units themselves. There are, however, also examples where the atomic arrangement forms regular interfaces, such as at coherent grain boundaries.

Hence, heterogeneous materials are characterized by various building units, homogeneous matrices and the interface regions. To describe them, we will focus on our introduced model system of nanoparticle/host matter, where we further specialize to spherical shapes of the particles.

The investigation and description of optical properties of heterogeneous materials have to deal with the interior of the building units, e.g., characteristic optical size effects, and with the interfaces, e.g., optical interface effects. The importance of both increase with decreasing characterizing structural lengths. The role of the host materials, when present, can be different, depending on their concentration: in dilute particle systems they may act as bulk-like homogeneous matter (e.g., the electrolyte in colloidal liquid systems); at low amounts, the host may also develop size effects (e.g., the water layers in the opal).

General Optical Properties

Among the experimental characterization methods most frequently applied to heterogeneous matter, the optical ones are essential, ranging from spectroscopy in the frequency domain (from FIR to UV), to femtosecond analysis in the time domain.

Optics can mean physical optics, i.e., the science of optical material properties, including light emission (the 'active' properties) and light absorption (the 'passive' properties), and instrumental optics, i.e., special experimental techniques based upon propagation of light to analyze such samples.

The most usual experiments for the investigation of linear optical response are refraction, absorption, reflection, and elastic scattering. Also, there are the emission responses and the broad field of nonlinear optical responses.

Refraction, reflection, and absorption are typical of homogeneous matter. Elastic light scattering, on the other hand, can be used to define optical heterogeneous matter, since elastic scattering is a direct consequence of the existence of interior interfaces forming deviations from the homogeneous structure. While the grainy structure on the atomic level in homogeneous matter does not give rise to disturbances of the shape of a plane interacting optical wave, this does occur with heterogeneous matter. Each inhomogeneity gives rise to a wavefront deformation and, hence, to light scattering. Scattering spectra and intensities provide important information about the heterogeneous material, so such optical methods are frequently used for its identification.

Besides scattering, the electrical charging of the interior interfaces induced by the light field, can lead to spectacular multipolar optical absorption features, unseen in related macroscopic homogeneous materials, such as Mie resonance, discussed below.

The optical properties of our model system are composed of various contributions which all act together in a complex way, which can be described as:

1. the optical properties of the single building units. In the case of solid state units, they are characterized by the optical material properties, frequency dependent and, generally, complex dielectric function $\varepsilon(\omega)$ or, alternatively, the (generally complex) refraction index $n(\omega)$, which, in the nanometer-size region, both develop strong variations with size.
2. the optical interactions among all building units in the sample. There are different effects:
   - interference effects among the scattering radiation of the units;
   - electromagnetic coupling effects;
   - the contributions of host materials, if present; and
   - the interactions between heterogeneous building units and host.

The Optical Nanoparticle Resonances (Mie Resonances)

Metallic and semiconductor nanoparticles can exhibit special, spectrally selective absorption and scattering bands which do not have counterparts in the molecular state, in thin film structures, or in the extended bulk. They represent the most spectacular optical properties of matter with nanosized heterogeneities. Therefore they will now be treated in more detail in the frame of our model material of spherical inclusions in a homogeneous embedding medium. We begin with a comparison to thin film structures.

The interband transitions (in Ag below 325 nm) are almost equal in both spectra shown in Figure 2, of a thin Ag film and spherical Ag nanoparticles, respectively, while above 325 nm the flat relaxator spectrum of the conduction electrons in the metal film differs strongly from the oscillator spectrum of the same electrons in the clusters. The inset demonstrates the excitation of the dipolar surface oscillator mode by



Figure 2 Comparison of absorbances of a thin Ag film and spherical small Ag nanoparticles.

incident polarized light. This figure exemplifies the above-mentioned effect that charging of interfaces by the incident electromagnetic lightwave can give rise to electromagnetic multipole resonances, the Mie-resonances.

The monotonic conduction electron absorption spectrum of the thin film, ranging from UV to zero frequency (the dc current), is thereby compressed in the nanoparticles into the narrow Mie-absorption band with peak position in the blue, containing almost the whole oscillator strength of the conduction electrons. In particular, the Ag-spheres are therefore transparent in the low frequency region, and if we assume the conductivity according to the Drude model as being definitive for a metal, we must assume that these particles are no longer metallic. The conduction electrons no longer follow the Drude relaxator behavior; instead the narrow peak indicates the properties of an oscillator.

The origin of this oscillator and its excitation can be described, being a quantum phenomenon; due to the incident electrical field, the electron plasma, the 'electronic particle', is shifted against the fixed ionic background, the 'ionic particle', causing surface charges modulated with the light frequency. The surface charges produce restoring forces to the plasma, following the periodic field strength, which is the condition required for oscillator behavior. As every free oscillator the particle develops resonances at special eigenfrequencies, and in the case of our metal clusters these are close to the peak frequency of the Mie-absorption, the oscillations of which not being free but forced by the incident field. Analogous to the mechanical case, the resulting resonance frequencies of free and forced oscillations differ slightly. To distinguish them, Mie resonances in metallic particles, coupled to the external electromagnetic field, are called plasmon polaritons.

In the frame of classical electrodynamics each single particle in the heterogeneous material acts as a spherical nano-antenna. This acts as receiving antenna by absorption and, as with every other kinds of antenna, simultaneously becomes a transmitting antenna by re-radiating elastically scattered light.

In the case of Cu, Ag, and Au, and many other metals, these absorption frequencies are in the visible, hence beautiful colors appear. However, there are a lot of metals where this oscillator is overdamped due to low electron mobility. Under particular conditions, such resonances also occur in semiconductor nanoparticles, but due to the lower charge densities, in the IR. At weak fields, the optical response of the oscillator is linear. At higher fields it becomes nonlinear, and thus second and higher harmonics can be excited.

Such unique collective excitations are not restricted to electrons but also spherical surface phonon polaritons can be excited if the particles are nonmetallic (in this case, free electron excitations do not cover the spectral region of phonon excitations). Only in the most simple case of particles which are extremely small compared to wavelength ($R/\lambda \leq 1/20$), the dipolar mode of excitation described so far (i.e., homogeneous polarization of the whole particle) comprises the whole response. For larger particle sizes, a complicated, nonhomogeneous polarization of the whole particle occurs, which can be described by an orthogonal multipole expansion, i.e., multipolar oscillations. The according size (R-) dependent multipolar contributions, which are excited simultaneously and sum up to the total optical response. Further complications arise in larger particles by retardation-induced phase shifts of the lightwaves along the particles.

A complete description of this complex multipole excitation was given by Gustav Mie on the basis of classical electrodynamics. Mie's theory is the exact solution within the frame of Maxwell theory for spherical symmetry, as are the Fresnel-formulae for the planar geometry. However Mie's theory does not describe exactly the conditions which we observe in real heterogeneous systems, hence several extensions of Mie's theory will be presented in the section entitled *Beyond Mie's Theory,* below.

Mie's theory also gives some qualitative insight into the optical behaviour of other kinds of heterogeneous matter. A highly abridged summary of this theory will be presented below.

The Theory of Mie

In the following, an outline of the Mie theory for one spherical particle is given by listing the mathematical steps:

1. Introduction of spherical coordinates r, θ, ϕ. Particle radius R;

2. Incidence of a plane, monochromatic, harmonic electromagnetic wave (circular frequency ω, wavelength λ);
3. Solution of Maxwell's equations for the incident and scattered fields in the surrounding dielectric host medium with (real) dielectric constant $\varepsilon_{\text{matrix}}$, and in the interior of an arbitrary spherical particle of (complex) dielectric function $\varepsilon(\omega)$.

   There are two solutions for transverse fields: one with the radial component of the electric field $E_{\text{r}} = 0$, called 'transverse electric (TE) solution', and one with the radial component of the magnetic field $H_{\text{r}} = 0$, called 'transverse magnetic (TM) solution'. These solutions can be obtained in terms of vector spherical harmonics which can be derived from corresponding scalar potentials Π_{E} and Π_{H}. These are solutions of the Helmholtz-equation:

   $$\begin{aligned} &\nabla^2 \Pi_{\text{E,H}} + K^2_{\text{transverse}} \times \Pi_{\text{E,H}} = 0, \\ &K^2_{\text{transverse}} = \varepsilon_{\text{transverse}} \omega^2 / c^2 \end{aligned} \qquad [1a]$$

   In spherical coordinates, the Helmholtz equation is solved by a separation of variables ansatz and a multipole expansion, yielding an infinite number of independent partial solutions with multipolar order L, the TM partial waves or 'electric partial waves', and the TE partial waves or 'magnetic partial waves'.

   A third solution, the potential Γ, that only affects the electric field, can be found as the solution of

   $$\nabla^2 \Gamma = 0, \qquad \varepsilon_{\text{longitudinal}} = 0 \qquad [1b]$$

   and represents longitudinal excitations in the particle.
4. Boundary conditions at $r = R$:
   for the transverse fields:

   $$\begin{aligned} E_\theta^{\text{incident}} + E_\theta^{\text{scattered}} &= E_\theta^{\text{interior}} \\ E_\phi^{\text{incident}} + E_\phi^{\text{scattered}} &= E_\phi^{\text{interior}} \end{aligned} \qquad [2a]$$

   $$\begin{aligned} H_\theta^{\text{incident}} + H_\theta^{\text{scattered}} &= H_\theta^{\text{interior}} \\ H_\phi^{\text{incident}} + H_\phi^{\text{scattered}} &= H_\phi^{\text{interior}} \end{aligned} \qquad [2b]$$

   for the longitudinal fields:

   $$E_{\text{r}}^{\text{incident}} + E_{\text{r}}^{\text{scattered}} = E_{\text{r}}^{\text{interior}} \qquad [3]$$

   (Sauter–Forstmann condition)

   The linear response function of the particle material used here, is ε, where $\varepsilon = \varepsilon_1 + i\varepsilon_2$ is averaged over the particle volume, including the surface–interface region.

   The magnetic permeability μ is set 1 for the investigated high frequency regions.
5. Computation of cross-sections for extinction, scattering, and absorption from Poynting's law:
   - Extinction, i.e., the sum of absorption and scattering losses:

     $$\sigma_{\text{ext}} = \frac{2\pi}{k^2} \sum_{L=1}^{\infty} (2L+1) \text{Re}\{a_L + b_L\} \qquad [4]$$
   - Elastic scattering:

     $$\sigma_{\text{sca}} = \frac{2\pi}{k^2} \sum_{L=1}^{\infty} (2L+1) \left(|a_L|^2 + |b_L|^2 \right) \qquad [5]$$
   - Absorption, i.e., the energy dissipation (production of heat and thermal radiation):

     $$\sigma_{\text{abs}} = \sigma_{\text{ext}} - \sigma_{\text{sca}} \qquad [6]$$

     L indicates the multipolar order of the Mie resonances.

The coefficients a_L and b_L, following from the Maxwell boundary conditions for transverse fields, are

$$a_L = \frac{m\psi_L(mx)\psi'_L(x) - \psi'_L(mx)\psi_L(x)}{m\psi_L(mx)\eta'_L(x) - \psi'_L(mx)\eta_L(x)} \qquad [7a]$$

$$b_L = \frac{\psi_L(mx)\psi'_L(x) - m\psi'_L(mx)\psi_L(x)}{\psi_L(mx)\eta'_L(x) - m\psi'_L(mx)\eta_L(x)} \qquad [7b]$$

with $m = 2x/n_{\text{Matrix}}$, where m denotes the complex-valued index of refraction of the particle $\varepsilon = n'^2$ and n_{matrix} the real-valued index of refraction of surrounding medium. k is the wavevector and $x = k \cdot R$, the size parameter. $\Psi_L(z)$ and $\eta_L(z)$ are Riccati–Bessel functions of the first and third kind. The prime indicates differentiation with respect to the argument in parentheses. Including longitudinal fields, eqn [7] will be slightly modified.

Applying Lambert–Beer's law, these cross-sections are related to the absorption-, scattering-, and extinction-constant $A(\omega)$, $S(\omega)$, and $E(\omega)$, respectively, and the resulting intensity loss ΔI of a many-particle system of number-density Z of the (noninteracting) particles, is

$$\begin{aligned} &\Delta I = I_0 \left(1 - \exp(-Z \cdot \sigma_{\text{ext}} \cdot d)\right), \\ &d = \text{sample thickness} \end{aligned} \qquad [8]$$



Figure 3 Mie extinction spectra of various particle materials. $2R = 10\,\text{nm}$. The clusters are embedded in matrix materials with dielectric constants between 1 and 10, which are indicated for each spectrum. Obviously, the peak structure of the spectra strongly depends on the matrix.

Figure 3 gives a compilation of some spectra of general interest determined by evaluating Mie's theory.

Beyond Mie's Theory

Application of Mie's theory to experimental results is disappointing because, in most cases, quantitative coincidence is not obtained. One reason is that the simple assumptions incorporated either in Maxwell's theory or in Mie's derivation are not met by reality.

Mie's theory does not apply, if:

1. particle sizes in a diluted cluster matter sample are not uniform;
2. particle shapes differ from the sphere;
3. $\varepsilon_{\text{matrix}}$ varies with frequency, $\varepsilon_{\text{matrix}}(\omega)$
4. cluster-dependent dielectric functions differ from the according functions of the bulk;
5. the (step-function like) Maxwellian boundary conditions at the particle-matrix interface are not applicable;
6. dielectric functions of particles and/or matrix are nonlinear;
7. surrounding/embedding matrix material is absorbing;
8. particle structures are heterogeneous (core-shell structures, multi-grain clusters, etc); and
9. particles form close-packed aggregates instead of being well-separated, and hence, electromagnetic coupling among particles is important.

Of course, this list may be continued. Regarding realistic samples, it is obvious already from these deviations that quantitative correspondence between experiment and Mie theory usually cannot be expected. But, over time, each of these extra effects has been treated and included into extensions of Mie's theory, which should therefore be applied, instead of the original theory. In the following several of these effects will be treated in some detail.

Particle Shapes Deviating From the Sphere

Even metals of high structure-symmetry, like the fcc-Au, can yield nanoparticles with low symmetry habits. Figure 4 shows Au nanoparticles with exotic shapes ranging from triangle and hexagonal platelets over fivefold symmetry multitwin-particles to rodlike shapes. The majority of particles are multigrain structures of irregular isometric shapes.

Multishell Particles

In experiments, particle surfaces often react chemically with the surrounding media, thereby forming compound shells. Core/shell structures can be clearly visible in the optical absorption spectra. Figure 5 shows, as an example, the absorption spectra of nanoparticles of Ag core/Au shell and of Au core/Ag shell, respectively with varied shell thicknesses.



Figure 4 Chemically (Esiguondy method) produced Au clusters with extraordinary variety of different shapes. (Of special interest are the small particles of five-fold symmetry.) Mean sizes of the irregular, almost spherical particles: 36 nm.

Resonances will also occur, e.g., in metal-coated dielectric particles. An example is shown in Figure 6, with extinction spectra of silver-coated titanium-dioxide particles, computed by an extension of Mie's theory.

Aggregates of Nanoparticles with Electrodynamic Particle–Particle Coupling

The optical extinction and scattering spectra of many-particle systems with dense packing forming aggregates (see Figure 4) are strongly influenced by electromagnetic interactions: each particle feels the



Figure 5 Measured extinction spectra of (a) silver-coated gold particles (gold core $2R = 17$ nm, shell thickness varying from $d = 0$ to $d = 3.6$ nm from top to bottom), and (b) gold-coated silver particles (silver core $2R = 18$ nm, shell thickness varying from $d = 0$ to $d = 5$ nm from bottom to top).



Figure 6 Calculated extinction spectra of spherical silver-coated titanium dioxide particles. The shell thickness is kept constant at $d = 10$ nm, the core sizes amount to $2R = 30$ nm, 50 nm, and 80 nm, respectively, as indicated in the graph.

scattering near fields of all its neighbors, which give rise to splitting, broadening, and shifts of resonances. This is clearly demonstrated with colloidal Ag and Au particles in Figure 7.

The splitting, broadening, and shifts can be assigned to the shape and size of the resulting many-particle aggregates. An example for the influence of the topology of the many-particle system is given in Figure 8 with extinction and scattering spectra of silver particle aggregates of $N = 5$ identical silver particles with $2R = 40$ nm, which were computed by the Generalized Mie Theory (GMT). As a rough rule-of-thumb, such electrodynamic coupling effects of the oscillators only can be ignored if the smallest next neighbor center-to-center distance d_{cc} exceeds $d_{cc} \approx 5 \cdot R$.

Size Effects

The extraordinary practical success of Mie's theory is based upon the fact that this example of classical electrodynamics enables us to compute numerically the optical response for arbitrary realistic particle materials. In contrast quantum theoretical calculations are restricted, beyond the molecule-solid state transition, to jellium and jellium-related hypothetical material.

Classical electrodynamics, being a phenomenological theory to describe light propagation, does not yield information about optical material properties. These enter via the dielectric functions inserted into the Maxwell boundary conditions. They must be taken from elsewhere, such as from experiments or from quantum solid state theory model calculations. This twofold basis of Mie's theory is illustrated in Figure 9.

There are two different sources for particle size dependences of the optical extinction spectra:

1. The electrodynamics: the larger the particles, the larger are the number of contributing multipoles and the influences of retardation effects, both influencing strongly the optical spectra;
2. The optical material properties describing the particle material which, in the nanoscale size region, exhibit size dependences. These size dependences can be treated by corrections entering the bulk material function.

In general, the dielectric function $\varepsilon(\omega)$ of a metal or semiconductor is the sum of susceptibility contributions of the lattice, of the conduction electrons, and of the interband (electron–hole) excitations:

$$\begin{aligned}\varepsilon(\omega) &= \varepsilon_1(\omega) + i\varepsilon_2(\omega)\\ &= 1 + \chi^{\text{lattice}}(\omega) + \chi^{\text{free electrons}}(\omega)\\ &\quad + \chi^{\text{interband}}(\omega)\end{aligned} \quad [9]$$



Figure 7 Measured extinction spectra of aggregated samples of (a) silver particles with $2R = 28$ nm, and (b) gold particles with $2R = 38$ nm. The samples contain random distributions of aggregates of various topologies, but with increasing state of aggregation from bottom to top.



Figure 8 Calculated extinction and scattering spectra of aggregates with $N = 5$ almost touching identical silver spheres of $2R =$ 40 nm. From top to bottom, the spectra belong to the following particle arrangements in the aggregate: . The dashed line represents the single particle spectra.


MIE'S THEORY
LIGHT PROPAGATION
Classical electrodynamics
INTERACTION WITH MATTER
Dielectric functions
(Experimental data and/or Solid State Theory)
Additional size and interface effects

Figure 9 Scheme of the basics of Mie's theory.

A detailed expression was given by Bassani (here, the lattice contributions, mainly important in the IR, were disregarded):

$$\varepsilon(\omega) = 1 - \underbrace{\frac{(ne_0^2/\varepsilon_0 m_{\text{eff}})}{\omega^2 + i\gamma\omega}}_{\text{conduction electrons}} + \underbrace{\chi^{\text{interband}}(\omega)}_{\text{interband transitions}} \qquad [10]$$

with

$$\chi^{\text{interband}} = \frac{2\hbar^2 e^2}{\varepsilon_0 m_{\text{eff}}^2} \sum_{i,f} \int_{\text{BZ}} \frac{2d^3k}{(2\pi)^3} |\mathbf{e} \times M_{\text{if}}(\mathbf{k})|^2 \times \left\{ \frac{1}{[E_f(\mathbf{k}) - E_i(\mathbf{k})][(E_f(\mathbf{k}) - E_i(\mathbf{k}))^2 - \hbar^2\omega^2]} + i\frac{\pi}{2\hbar^2\omega^2}\delta(E_f(\mathbf{k}) - E_i(\mathbf{k}) - \hbar\omega) \right\} \qquad [11]$$

In this equation, the quantity n is the conduction electron density, $\mathbf{k}$ the wavevector of the electrons with norm k, and BZ denotes the Brillouin Zone. The vector $\mathbf{e}$ is the polarization vector of the incident light. M_{if} is the transition matrix element with i = initial and f = final states.

To which degree of approximation a single dielectric function can describe the optical response of a nanoparticle consisting of inner core and surface with differing local optical properties (i.e., polarizabilities), and how this function has to be modelled as an average, is still a problem. An easy, but only approximate answer is to identify terms in the eqns [10] and [11], which may change if the cluster size is reduced down to the nanometer scale, and to introduce correction terms.

In the case of the conduction electrons of eqn [10], these are the electron density n, the effective electron mass m_{eff}, and the relaxation frequency γ. In the terms of the interband transitions (index inter), these are the transition matrix elements M_{if} and the band structure energies of the initial and final states E_i and E_f. All of these quantities change, when the particle size is reduced, in different size regions and to different amounts, and detailed quantum theoretical investigations are required to derive proper correction terms.

The application of the continuum-based dielectric functions and of Mie's theory fail when the molecule-solid state transition region is reached.

The effects of size-dependent dielectric functions upon cluster absorption spectra are demonstrated in the series of absorption spectra of Figure 10, measured on highly diluted heterogeneous systems containing spherical Ag, Au, and Cu particles which were embedded in a glass matrix. If $\varepsilon(\omega)$ were independent of size, then the spectra should be identical, in the investigated particle size region. So, their differences reflect clearly that $\varepsilon = \varepsilon(R)$.

To describe the size effects of the conduction electrons, the relaxation frequency γ of eqn [10] has been modified introducing a parameter that is called A-parameter which also contains size effects and also particle–host interface effects. To explain the electronic size effects in detail, quantum effects have to be considered taking the discretization of the bandstructure into account, but they can also be treated by a simple classical approach: this is the mean free path effect (FPE), assuming the mean flight time of the effective conduction electrons (i.e., those with Fermi energy E_F) between subsequent surface collisions amount to

$$\tau\gamma_{\text{FPE}} = A_{\text{FPE}}\frac{v_{\text{Fermi}}}{R} \qquad [12]$$

The A-parameter is a measure of the effectiveness of the single collision in view of relaxation. Complete 'memory loss' of the drift momentum in each collision would lead to $A_{\text{FPE}} = 1$. Taking electron correlation effects and energy relaxation into account, A-values larger than 1 may also be realistic. Values larger than unity also occur in multigrain particles, due to grain boundary 'collisions'.

Various quantum mechanical models of electronic particle size effects result in relations, formally coinciding with the $1/R$-dependence in eqn [12]. Most relevant is the value of A for particles *in vacuo* with clean surface. This value has been determined theoretically and experimentally to $A \approx 0.25$ for Ag particles.

Properties of Internal Interfaces

Structures of Surfaces/Interfaces

Only mathematical interfaces in geometry can, in fact, be two-dimensional planes separating two different volume elements. This is assumed in the frame of Maxwell boundary conditions entering Mie's theory. In real nanostructured matter, however, the interface regions are three-dimensional layers formed by disturbances of atomic and/or of electronic structures, and/or of chemical compositions. In addition, due to the finite wavelengths of the conduction electrons, the according electron density 'spills out' and, as a consequence, we find electron density beyond the geometric surface. It should be kept in mind that these effects hold, with proper changes, for interfaces in nanostructured materials in general. Hence, an understanding of the interface regions is of key importance for all nano-material.

Electronic Interface States

Up to now, this discussion has been restricted to particles with uncovered, 'clean' surfaces. In most practical examples of heterogeneous materials however, the building units are embedded in a host matrix, deposited upon the surface of a substrate, or are in close contact to neighboring crystallites, etc., to stabilize the samples. Then, special electronic



Figure 10 Measured extinction spectra of Ag, Au, and Cu clusters of various mean sizes, grown in glass matrix. In the case of Cu-particles, measurements at 1.5 K are added.

interface states are created by contributions of particle electrons and host electrons, which are (disregarding their density on the surface) similar to adsorbate states.

One might assume that the broad knowledge about these states in surface science, obtained from samples with extended crystallographic planes, should be very useful here. However, the surface of a cluster, in principle, differs from the planar surface of a single crystal by containing a multitude of different local surface structures, atomic sites, and varying atomic coordination numbers. Even if the surface structure is not irregular (as is usual in nanoparticles), the surface consists of several facets of different orientation separated by edges and corners. The coordination numbers of surface atoms, thus, vary strongly (e.g., between 5 at a corner and 9 on a plane), indicating surface sites to have different energies.

We have shown that, if the particles are metallic, the ‘particle/host’-interface states give rise to two different electronic charge transfer processes of particle conduction electrons, the static and the dynamic charge transfer. This will be demonstrated qualitatively for metal particles by the example presented in Figure 11.

The Static Interface Charge Transfer and its Effects Upon Mie Resonance Positions

At the left side of Figure 11, the conduction band of the metal cluster close to its surface is shown, which is occupied with electrons up to the Fermi energy E_F. Chemisorption of a free atom (one energy level E_a of which is plotted at the right-hand side) is assumed to occur by approaching the atom to the cluster surface. The resulting energy states are also shown. Let us assume the marked electronic level E_a in the free atom is nonoccupied. During the chemisorption process, this level is shifted and broadened, developing density of nonoccupied states below the particle Fermi energy, which is localized at the three-dimensional interface region. After complete the process is, such a state will be occupied permanently by electrons of the cluster (static charge transfer), and the nanoparticle will have lost electrons, thus its electron density being reduced. The driving impact of this process is the equilibration of the chemical potential in the whole cluster-matrix system.

Now assume we embed a cluster into some surrounding material. Then all those atoms of the latter, which are situated directly at the interface, become chemisorbed at the cluster. Hence remarkable amounts of charges can be transferred into the interlayer region and an electrical double layer is created. As an example, a very strong amount of static charge transfer was observed experimentally when applying solid Fullerite (C_{60} molecules) as embedding matrix for Ag-nanoparticles: here, each C_{60} in direct contact with the Ag particle attracts one electron, forming (C_{60}^{-}). Hence, in this experiment with 500 atoms large particles, in total about 20% of the conduction electrons of the Ag-particle were transferred into the interlayer. Strictly speaking, such a nanoparticle of the heterogeneous material is no longer a silver particle because of the remarkable changes of electronic properties by static charge transfer.



Figure 11 Electron energy scheme for atomic adsorbation at a metal particle surface. The free atom (energy spectrum: right) approaches the particle surface (left; conduction band with Fermi-level E_F). Its energy level E_a is thereby shifted and broadened (including ensemble broadening of many atoms deposited at many clusters). The atoms are assumed to be separated from the metal by a tunnel barrier (see text).

Some consequences are listed in the following:

In a first step, let us assume that the electronic bandstructure is not altered by the charge transfer. Then we expect: (i) changes of level occupation; (ii) changes of Fermi energy and Fermi velocity; (iii) changes of effective masses close to E_F; (iv) changes of surface 'spill out'; (v) additional adsorbate levels and special surface states; and (vi) changes of the optical interband transition edge.

In a second step, we may consider possible changes of electronic bandstructure (e.g., energies) and, finally, also changes of atomic structures (i.e., lattice structures and/or surface structures).

Since plasmon frequencies depend on the conduction electron density, the resulting Mie resonance can monitor and give quantitative information of this effect. We find shifted by the static charge transfer:

$$\Delta\omega_{\text{resonance}} \approx (\sqrt{n_2} - \sqrt{n_1}) \times \sqrt{\frac{e_0^2}{\varepsilon_0 m_{\text{eff}}(2\varepsilon_{\text{matrix}} + 1 + \chi_1^{\text{interband}})}} \qquad [13]$$

with n_1 being the conduction electron density in the cluster *in vacuo*, and n_2 being the electron density after contact with foreign material (adsorbate, substrate, or host-matrix). This peak shift of the Mie resonance, however, is superimposed in the experiment by a much larger shift, following simply from the change of Maxwell boundary conditions by the altered dielectric constant of the particle surrounding $\varepsilon_{\text{matrix}}$, when going from vacuum to a matrix material. Hence, the experimental determination of static charge transfer processes is rendered more difficult.

The Dynamic Interface Charge Transfer and its Effects Upon Mie Resonance Widths

After the static charge transfer in Figure 11 has taken place, electrons close to E_F can fluctuate between the cluster and empty adsorbate levels, if present at E_F. The residence times in these levels, which are usually separated from the Fermi sea of the metal cluster by some tunnel barrier, vary statistically. If a plasmon is excited, i.e., mainly a collective, phase ordered motion of all conduction electrons superimposed to their statistical motion, we may assume that, after such electron transfer back and forth, the reminiscence to the primary drift momentum, and the phase of this excitation, has been lost. Thus, the phase relaxation of the plasmon is increased.

The consequences of this dynamic charge transfer effect ('chemical interface damping') have been investigated in detail. Here, we only state that the directly observable main consequence is the broadening of Mie resonances. If the particles are sufficiently small to neglect radiation damping (this is the case for Ag clusters smaller ≈15 nm), band broadening is only due to internal energy dissipation and the band width can be modeled quantitatively with the modified relaxation frequency γ in eqn [10] which yields an additive correction term:

$$\Gamma(A,R) \approx \Gamma_0 + \frac{2ne_0^2}{\varepsilon_0 m_{\text{eff}}\omega^3} \times \frac{A}{\sqrt{(\partial\varepsilon_1/\partial\omega)^2 + (\partial\varepsilon_2/\partial\omega)^2}} \frac{v_{\text{Fermi}}}{R} \qquad [14]$$

with the A-parameter extended to the additional electronic excitations in the particle/host interlayer:

$$A = A_{\text{size effects}} + A_{\text{interface effects}} \qquad [15]$$

The A-parameter of eqn [15] now expresses both the strengths of the particle size effects and of the chemical interface damping, due to statistically varying occupation of interface states near E_F.

An important feature of this model is that the dependence on the kinds of materials is described by specific material parameters ($A_{\text{size effects}}$ and $A_{\text{interface effects}}$), and the direct size dependence effects are given by an $1/R$-dependence, for both the direct size effects and the interface effects. For one fixed cluster size R, the magnitude of $A_{\text{interface effects}}$ directly characterizes the probability of the single temporal charge transfer, including the number and energies of contributing interface states; hence, important properties of the adsorption process can be investigated by determining the A-parameter.

Experimental Results

In the experiments presented in the following, we deal with the interfaces between clusters and a more or less homogeneous solid embedding medium. We selected very small silver nanoparticles of about 2 to 4 nm size with accordingly large ratio of surface- to volume-atoms, in order to optimize the sensitivity of the measurements. Silver is unique in having the most pronounced Mie resonance of all known materials.

In Figure 12 two classes of matrix materials are presented, fluorides and oxides. The absorption spectrum of the free particles with uncovered 'clean' surface (measured in a cluster beam in UHV) is added in both diagrams which is only influenced by size effect. General features are, that embedding in a host medium causes:

- drastic Mie resonance peak shifts toward IR, depending on the dielectric constant of the matrix



Figure 12 Measured optical extinction spectra of 2 nm Ag nanoparticles, embedded in various different embedding materials. For comparison, the spectrum of the free nanoparticle beam is added. Left side: oxidic materials, right side: fluoridic materials.

$\varepsilon_{\text{matrix}}$, which classically follow from Mie's theory and by comparingly small additional shift due to static charge transfer;

- drastic broadening (exceeding, in some cases, all known size effects), which according to eqn [14], can be described by characterizing values of the A-parameter. Recently, these parameters have been experimentally determined for Ag nanoparticles embedded in a broad variety of host materials. Their interpretation is rendered difficult, however, due to inhomogeneous broadening of varying magnitude.

We can immediately judge from Figure 12 that both shift and broadening are larger in the case of oxidic matrices than of fluoridic ones, i.e., oxides possess more interface states close to E_F of the material. In Figure 13, observed peak positions $\hbar\omega_{\max}$ and broadenings expressed in the resulting A-parameters, are summarized for a broad variety of different embedding materials.



Figure 13 Silver nanoparticles ($2R = 2$ nm) embedded in various solid host matrices: measured Mie peak positions and resonance halfwidths expressed by the A-parameters.

Comparison of Plasmon Polariton Lifetimes with Femtosecond Experiments

In the last section, experimental examples were presented to show how fundamental physical properties are changed by forming heterogeneous materials. Because the Mie resonance widths are mainly a consequence of finite plasmon polariton life times τ, (in addition, there are interband contributions, in larger particles radiation damping, and dispersion influence), the latter can be evaluated from measured optical absorption spectra. This supposes the bandwidth to be essentially homogeneous. From a width analysis fitting Mie's theory numerically we obtained for Ag particles, free flying in UHV with uncontaminated free surfaces and 2 nm in size, a plasmon lifetime of $\tau = 6$ fs. Under these experimental conditions, the measured bandwidth is the homogeneous one.

Concerning the size dependences, we can extrapolate to larger particles. The longest lifetimes are expected for 15 nm particles, for which $\tau = 15$ fs was obtained by extrapolating the experimental data for 2 nm particles to this size. The same width analysis was performed for the nanoparticles embedded in matrix materials, and as a result, the lifetimes drastically decrease down to 1–2 fsec. The observed increase of the A-parameter, as shown in the previous section, is thus directly correlated to the measured decrease of the plasmon polariton lifetime. Hence, we conclude that the decrease of the lifetime is mainly due to increased phase relaxation caused by the dynamic charge transfer effect.

These results can be compared with recent femtosecond spectroscopy experiments which have recently given much impact on the experimental investigation of the dynamics of Mie resonances in silver and gold nanoparticles. In these experiments data between 6 and 10 fsec were obtained for deposited Ag and Au particles of different sizes and different substrates. Regarding the complexity of the different experiments the correspondence of the data appears convincing.

Obviously the lifetimes evaluated in the frequency domain, from our spectra of particles *in vacuo*, coincide with the lifetimes determined in the time domain. The latter, though, were measured with larger particles deposited on substrates (i.e., not from free particles but including interactions with substrates).

As a concluding remark, it may be pointed out again, that the optical properties and the heterogeneity effects presented here for the model system of nanoparticle/host-matter, are also to be found in other examples of the large field of heterogeneous materials.

List of Units and Nomenclature

Absorption bandwidth	Γ
circular frequency [s^{-1}]	ω
dielectric constant/dielectric function [–]	ε
effective electron mass [kg]	m_{eff}
electric field [$\mathrm{V\,m}^{-1}$]	E
(electron) relaxation frequency [s^{-1}]	γ
electron state energies for initial and final state [J]	E_i, E_f
elementary charge [C]	e_0
extinction, scattering, absorption cross section [m^2]	σ_{ext}, σ_{sca}, σ_{abs}
Fermi energy [J]	E_{F}
Fermi velocity of electrons [$\mathrm{m\,s}^{-1}$]	v_{Fermi}
intensity [$\mathrm{W\,m}^{-2}$]	I
Kronecker energy distribution [J^{-1}]	$\delta(E)$
magnetic field [$\mathrm{A\,m}^{-1}$]	H
norm of wave vector of electrons [m^{-1}]	k
number density of conduction electrons [m^{-3}]	n
Riccati-Bessel functions of first kind [–]	$\psi_n(z)$
particle radius [m]	R
(phase-) life time [s]	τ
Planck constant [J_s]	$\hbar$
Riccati-Bessel functions of third kind [–]	$\eta_n(z)$
scalar electromagnetic potentials [V]	Π, Γ
susceptibility [–]	χ
transition matrix element [$\mathrm{kg\,m\,s}^{-1}$]	M_{if}
vacuum permittivity [$\mathrm{CV}^{-1}\,\mathrm{m}^{-1}$]	ε_0
vacuum velocity of light [$\mathrm{m\,s}^{-1}$]	c
vacuum wavelength of light [m]	λ
wave vector of electrons [m^{-1}]	$\mathbf{k}$

See also

Scattering: Scattering Theory. **Semiconductor Physics:** Polarons.

Further Reading

Bassani F and Parravicini G (1975) *Electronic States and Optical Transitions in Solids*. Oxford: Pergamon.

Bohren CF and Huffman DR (1983) *Absorption and Scattering of Light by Small Particles*. New York: Wiley.

Born M (1960) *Optik*. Berlin: Springer-Verlag.

Duncan M (ed.) (1998) Advances in Metal and Semiconductor Clusters, vol. IV. London: JAI Press Inc.

Haberland H (ed.) (1994) *Clusters of Atoms and Molecules*. Berlin: Springer Series in Chemical Physics 56.

Nalwa HS (ed.) (2001) *Handbook of Surfaces and Interfaces of Materials*, vol. 3. San Diego: Academic Press.

Hölzl J, Schulte F and Wagner H (1979) *Solid Surface Physics*. Springer Tracts in Modern Physics 85. Heidelberg: Springer.

Hummel R and Wissmann P (eds) (1997) *Handbook of Optical Properties*, vol. II: Optics of Small Particles, Interfaces and Surfaces. Boca Raton, FL: CRS Press.

Jena P, Khanna SN, Rao BK (eds) (2000) *Cluster and Nanostructure Interfaces*. New Jersey: World Scientific.

Kerker M (1969) *The Scattering of Light and Other Electromagnetic Radiation*. New York: Academic Press.

Kreibig U and Vollmer M (1995) *Optical Properties of Metal Clusters*. Berlin: Springer Series in Material Science 25.

Nanometer Scale Science and Technology, Internatl. School of Physics 'Enrico Fermi' (2001) CXLIV. Amsterdam: IOS Press.

Quinten M (1998) *Physical and Chemical Properties of Surfaces in Nano-Particle Systems*. Aachener Beiträge zur Physik kondensierter Materie, vol. 24. Mainz, Aachen: Wissenschaftsverlag.

Ruhbahn HG (2002) *Nanophysik und Nanotechnologie*. Stuttgart: Teubner.

Schmid G (1994) *Clusters and Colloids*. Weinheim: VCH Verlag.

van de Hulst HC (1957) *Light Scattering by Small Particles*. New York: Wiley.

von Plessen G (1998) *Ultrafast Dynamics of the Surface Plasmon in Gold Particles*. Advances in Solid State Physics 253. Berlin: Vieweg.

Lightweight Mirrors

J W Bilbro, George C Marshall Space Flight Center, AL, USA

Published by Elsevier Ltd.

The desire to probe the heavens is as old as humanity; the realization that the human eye could be aided in these investigations is somewhat more recent. In May 1609, Galileo Galilei, while visiting in Venice, heard about the new ‘telescope’ invented by the Dutch lens-maker Hans Lipershay and decided that it would be useful in his astronomical investigations. He returned to his home in Padua and made his own telescope comprised of 4.2 cm diameter plano-convex and plano-concave lenses. With this telescope, Galileo discovered the satellites of Jupiter; got tenure; had his salary doubled – and the race was on! It did not take too long to realize that ‘bigger’ was ‘better’, and from this point forward, there has been a continuous striving to increase collecting area and resolution, thereby enabling the astronomer to ‘see’ farther and farther into the heavens.

The limitations of refractive optics soon prompted investigations into reflecting optics – mirrors. In 1668, Isaac Newton produced the first reflecting telescope having a 2.5 cm diameter mirror made of speculum (copper (6), tin (2), and arsenic (1)). A little over 100 years later, in 1789, William Herschel constructed his ‘Great Telescope’, having a 1.22 m diameter mirror made of bronze. Of course as telescopes grew, so did mirror weight. In 1845, William Parsons’ ‘Leviathan’ was built. It had a 1.84 m diameter mirror made of speculum that weighed 3600 kg – a whopping 1354 kg m^{-2}.

Problems with corrosion in speculum and bronze mirrors led to a renewed interest in glass, and the development of highly reflective coatings soon made metal mirrors obsolete. In 1917, the mirror for the Hooker telescope arrived on Mount Wilson. Made by the Saint Gobain glassworks in France from the same material used for wine bottles, the mirror was 2.54 m in diameter, 33 cm thick and weighed over 4000 kg (789 kg m^{-2}).

The increasing weight of larger and larger mirrors produced practical problems for telescope makers and astronomers. Herschel’s telescope was so unwieldy that he found it almost impossible to use and returned to smaller telescopes for most of his observations, and the 2.54 m Hooker telescope required a 100 ton mount and drive system. Obviously, if telescope apertures were to increase, steps had to be taken to make mirrors lighter. The first major success in this arena was accomplished for what was to become the Hale Telescope commissioned at the Palomar Observatory in 1948. In 1936, Corning cast a mirror made of a new borosilicate glass blend called Pyrex. The blank was lightweighted by placing hexagonal shaped obstructions in the mold which created corresponding voids in the glass. The finished mirror (Figure 1) was 5.08 m in diameter, 61 cm thick at the edge and weighed approximately 13 000 kg (641 kg m^{-2}). Even with this degree of ‘lightweighting’ the mounting and drive mechanisms still weighed around 182 000 kg.

Although the desire for larger ground-based telescopes provided the initial impetus for developing lightweight mirrors, the advent of the space program and the desire to put telescopes in space became the main driver in the pursuit of ‘serious’ lightweighting techniques. The cost of launching



Figure 1 5.08 m Pyrex™ mirror made by Corning/Caltech for the Hale Telescope. Reproduced with permission from the Palomar Observatory/California Institute of Technology.

large telescopes into space quickly becomes prohibitive as aperture size increases. Consequently, the current emphasis is on developing ultra-lightweight, deployable telescopes that permit ever-increasing apertures to be placed in orbit. Fortunately, the zero gravity environment of space permits satisfactory operation of such ultra-lightweight telescopes and therefore the extent to which a mirror can be lightweighted is primarily dependent upon the mirror material and the manufacturing techniques utilized.

Manufacturing

Mirror manufacturing can, in some sense, be divided into two general classes, one that removes material (direct generation) and one that deposits material (replication). The two classes have significantly different limitations relative to producing lightweight mirrors. Direct generation encompasses the more traditional methods of mirror manufacturing, blank fabrication, and optical surface generation, i.e., grinding and polishing. Many innovative techniques have been developed over the past decade that have not only made significant strides in improving fabrication times, optical figure, and surface finish, but have also made possible the reduction of weight to unprecedented levels.

Although extremely lightweight mirrors are being fabricated using direct generation, in the end, there are limitations in the fabrication processes that are not present in replication. This process offers the fascinating potential to create mirrors that are only a few molecules thick, thereby bringing a new meaning to the term 'lightweight optics'.

Direct Generation

Mirror blank fabrication

Casting lightweight glass mirror blanks has evolved substantially since 1936. Four 8.2 m diameter Zerodur™ mirror blanks were spun cast for the European Southern Observatory's Very Large Telescope Interferometer. The largest mirror cast to date was the 8.4 m borosilicate mirror cast in a spinning oven for the Large Binocular Telescope on Mount Graham. Although not exactly lightweight by space standards – the blank weighs 15 455 kg (266 kg m^{-2}) – it is substantially less than a conventionally cast solid blank.

It has been postulated that an areal density of around 64 kg m^{-2} probably represents the limit of lightweight glass castings. Therefore, as the demand for lighter and lighter mirrors increased, methods other than casting had to be developed. Investigations in the 1960s indicated that mirrors could be lightweighted to about 180 kg m^{-2} by first fabricating a 'honeycomb' core and then fusing plates on the front and back of the core using a high-temperature fusion process. This process was used to produce the Hubble Space Telescope mirror (Figure 2). Hubble had a 2.5 cm thick face-sheet and back-sheet and a honeycomb interior constructed of individual pieces 0.5 cm thick. These pieces were assembled and placed in a large furnace where the temperature was increased until they fused together. The resulting 2.4 m diameter mirror weighed 828 kg (183 kg m^{-2}).

During the 1980s, Frit bonding technology was developed. Unlike the fusion process, Frit allowed the bonding of glass elements at a lower temperature. This allowed the cross-sections of the glass elements to be significantly reduced. The thicknesses of face-plates were typically reduced to around 7 mm and areal densities in the 40–50 kg m^{-2} range became routine. New advances were also made in core manufacturing. Diamond tooling was developed along with computer controlled systems to machine cores from solid blanks. High-pressure water jets were developed that allowed cores to be made much faster than with diamond tooling. In addition, the water jet cutting provided the ability to create very flexible geometries optimized to minimize weight while retaining stiffness. Water jets could machine core walls that could be held to a thickness of around 1.5 mm over a core depth of 20 cm. Computer controlled diamond machining has created even thinner cores (less than 1 mm in thickness) but the process requires longer generation times.



Figure 2 2.4 m ULE™ mirror made by Corning/Perkin Elmer for the Hubble Space Telescope. Photography courtesy of NASA.

Material removal

The evolution in blank manufacturing required a corresponding evolution in the process of material removal. Many new grinding and polishing techniques were developed over the years to more accurately and rapidly generate precision optical surfaces. These included adaptive force grinding, electrolytic in-process dressing (ELID), water jet figuring, computer controlled polishing, stress lap polishing, magneto-rhelogical figuring (MRF), plasma-assisted chemical etching (PACE), ion figuring, and vacuum lap figuring. Most of these processes induce localized forces on the face-sheet in the process of material removal, and for a 'honeycomb' mirror, the face-plate deflects away from the grinding/polishing tool as the tool reaches the center of the cell. This means that less material will be removed in the center of the cell than at the edge of the cell where the core wall holds the face-sheet against the tool. This creates a 'quilted' pattern in the surface that must be removed in subsequent steps. As face-sheets become thinner, quilting becomes more pronounced and the process of removing 'quilting' becomes exacerbated. For a number of years, this was the limiting factor in the development of high-precision lightweight mirrors.

Ion figuring is a noncontact process that has eliminated the problems associated with mechanical material removal. It bombards the surface of the optic with neutralized ions causing atoms to be dislodged. The process creates no deflection of the surface and therefore can remove quilting and other irregularities without generating further distortion in the surface. This has permitted 2–3 mm thick face-plates to be manufactured without concern for quilting effects. Primary limitations now being encountered are in face-plate generation and the various associated handling processes. Great care must be taken to avoid fracture. Spin casting ultra-thin face-plates is being investigated as a means of further reducing problems in the generation process. The 0.75 m mirror made for IKONOS, the high-resolution imaging satellite, represents the state-of-the-art in all-glass lightweight mirrors (28 kg m^{-2}).

Replication

Replication techniques are quite common in low-cost production mirrors and lenses for commercial purposes. However, there are also a number of techniques that hold great potential for precision mirrors as well. Chemical vapor deposition (CVD), plasma vapor deposition (PVD), plasma spray deposition, and electro-forming are all being investigated for producing lightweight precision mirrors. This class of mirror generation does not start with a mirror blank *per se*, rather it replicates a 'mandrel' that has the appropriate surface finish and the inverse of the shape desired in the final mirror. The mandrel can be made very rigid and therefore unperturbed by either gravitational forces or the localized forces generated by grinding and polishing. Extremely thin mirrors with areal densities on the order of 0.1 kg m^{-2} are currently being manufactured using replication techniques. These 'membrane' mirrors are currently being used for solar energy collection; however, recent advances in membrane quality and wavefront correction techniques hold out the promise of producing high-resolution, membrane imaging systems.

The Future?

Theoretically, single-molecule thick mirrors could be manufactured in space using self-replicating nanotechnology systems that 'grow' mirrors according to a mathematical description of the desired optical surface. These 'smart' mirrors could self-correct in the presence of physical disturbances and self-heal when damaged. They could be 'grown' to hitherto unimagined size, being limited only by the availability of raw material. Such mirrors, however, are definitely of the future and should merit re-examination 20 years hence.

Materials

A variety of materials have been developed over the years that have led to lighter and lighter mirrors. Recently, metals are coming back into play as means of fabricating stiff, lightweight mirrors. These metals include beryllium, nickel, nickel alloys, aluminum, and aluminum alloys. Composite materials are also playing a large role in lightweight mirror fabrication, both as a support structure and also as a reflecting surface (with appropriate coatings). Hybrid mirrors comprised of a combination of glass and composites have also been developed, as well as combinations of glass and beryllium. Various forms of silicon carbide have been extensively investigated and lightweight mirrors of pure silicon are being manufactured. Glass still plays a significant role in large lightweight mirrors, and various plastics are under investigation for the production of ultra-thin membrane mirrors.

Glass, Glass Ceramics, and Hybrids

The most common glass/glass ceramic materials used in large telescope mirrors are fused silica, ULE™ (Ultra-Low Expansion) glass, and Zerodur™, a glass ceramic. As was mentioned earlier, there are a variety



Figure 3 1.5 m ULE™ mirror made by Corning/Kodak for NASA's Next Generation Space Telescope Advanced Mirror System Demonstrator technology program. Photograph courtesy of NASA.

of methods available for the manufacture of glass mirrors depending upon the extent of lightweighting desired. Most of the current effort in lightweight mirrors is centered around hybrid mirrors. One method bonds very thin (2–3 mm) glass face-sheets to composite cores to form 'sandwich' mirrors. Another method attaches face-sheets to composite back-plane structures via actuators. In the latter case, the actuators can be used to actively control mirrors to correct for distortions. These mirrors were developed as part of the James Webb Space Telescope technology program, and typically have areal densities on the order of 15 kg m^{-2} (including back-plane structures). An all glass face-sheet and core is shown in Figure 3.

Silicon Carbide

Silicon carbide has long been a promising material for lightweight mirrors. It has many of the desirable properties of beryllium and is nontoxic. Until recently difficulties were encountered in producing mirrors larger than ~0.5 m in diameter. Of late, several manufacturers have produced large (<1 m) lightweight mirrors using different processes; sintering, liquid silicon infiltration and chemical vapor deposition.

The sintering process consists of preparing a finely ground silicon carbide powder mixed with organic binders and additives and then compacting the powder by isostatically pressing it at high pressure. The resulting compact is then machined to the desired shape and weight and the blank heated to cause agglomeration of the particles. The resulting material is known as reaction-bonded silicon carbide; it can be polished to around 30 angstroms and can be ion figured. If smoother surfaces are required, then a layer of CVD or PVD silicon carbide can be added. A 1.35 m diameter mirror has been fabricated as a demonstration for the European Space Agency's Herschel Space Observatory. The mirror was fabricated in nine segments that were then brazed together to form a unified 26 kg m^{-2} blank. This mirror was not designed to test the limits of lightweight and, consequently, there is no reason to believe that this process could not achieve an areal density comparable to the 7.8 kg m^{-2} of Cesic™ described in the following paragraph. The size of mirrors produced using this technique is currently limited to around 4 m due to the availability of the furnaces required for segment brazing.

The liquid infiltration process is used to create a biphase carbon, silicon carbide material known as Cesic™. This material is manufactured by creating a block of chopped carbon fibers embedded in a phenolic resin. The block is machined to the desired shape and then put into a furnace where the temperature is elevated until the resin is turned to carbon. The temperature is further elevated and liquid silicon infiltrated to produce silicon carbide. Bare Cesic™ can be polished to approximately 100 angstroms. In a subsequent step, a silicon carbide slurry can be applied to the blank that can be polished to around 30 angstroms. It is also possible to add a CVD or PVD silicon carbide layer to the blank that can be polished to obtain angstrom-level surfaces. A 1.04 m diameter Cesic™ mirror has been constructed for the NASA program, Solar Lite. The mirror weighs approximately 60 kg for an areal density of 56 kg m^{-2}. Again, this mirror was not designed to test the limits of lightweighting, but in a separate demonstration, an areal density of 7.8 kg m^{-2} was achieved. The size of mirrors produced using this technique is also currently limited to around 4 m due to the availability of existing furnaces required for infiltration.

The CVD process produces a SiC material that is highly polishable, yielding surface finishes on the order of angstroms. It has been used quite successfully as a coating layer, and has the potential to provide a means of replicating very lightweight mirrors by depositing a thin layer of SiC onto a mandrel. In one approach, the mandrel has the appropriate shape, but not the surface finish. In this case, once the SiC has been deposited, the mandrel is burned away and a SiC mirror blank is left. The blank is then ground and polished to produce the desired figure and finish. If the blank is too thin, this can present a problem in achieving a high-performance mirror. A second approach involves the deposition of SiC onto a figured and polished mandrel. In principle, both the figure and surface finish can be replicated. Success in this approach, however, has been somewhat limited, and although 20-angstrom surface finishes have been replicated, they have not been repeatable. A 1 m diameter blank was manufactured using the first approach, but it too has not been repeated and the lack of success appears to be due to high stress developed in the deposition process. The residual stress in the blank causes large-scale deformation and frequently fracture.

Beryllium

The extremely high stiffness of beryllium makes it a highly desirable candidate for lightweight mirrors. Unfortunately, it is a highly toxic material and there are only a very few companies involved in the manufacture of beryllium mirrors and even fewer that produce the raw material. Blanks are manufactured by isostatically compressing beryllium powder at high temperature and pressure. The blanks are then machined and subsequently ground and polished. Early beryllium mirrors often exhibited interesting, mysterious changes in figure after seemingly benign handling events. Unpredictable changes in figure also occurred as they were cycled between ambient and cryogenic temperatures. These problems appear to have been resolved with the production of spherical powder. The older powder consisted of irregularly shaped particles and when the powder was compressed, small, irregularly shaped voids were created throughout the material. It is hypothesized that these voids changed in size and shape as the blank was stressed, thereby causing unpredictable dimensional changes in the blank. The spherical powder permits uniform, high-density packing yielding homogeneous blanks that do not appear to exhibit unpredictable dimensional changes.

The lightest-weight beryllium mirror to date (11.8 kg m^{-2}) was made for NASA's James Webb Space Telescope technology program. This technology was selected for the flight mirror. The weight reduction was achieved by machining the blank to create an open back honeycomb structure with an integral face-sheet. The ability to fabricate large beryllium mirrors is limited by the availability of facilities capable of isostatically pressing the material at the requisite pressures and temperatures. Currently, blank sizes are limited by available isostatic presses to around 1.2 m in width and 1.6 m in length. The expense of construction of larger facilities combined with limited need make it highly unlikely that any larger mirrors will be manufactured in the near term. A brazing process, however, has been demonstrated for joining segments to form a large blank. This process could, in principle, permit the fabrication of mirrors several meters in diameter. Bare beryllium can be polished to around 30 angstroms surface finishes. If smoother surfaces are required, beryllium can be vacuum deposited on the blank. Nickel may also be deposited on the blank; this has the added benefit that it can be polished without the special facilities required for the hazardous beryllium polishing operations. The drawback of using nickel is that of the bimetallic effect if the mirror is to be operated over a wide temperature range. The Vavilov Institute in Russia has developed an alternative approach to obtaining good surfaces by creating a glass that matches the coefficient of thermal expansion (CTE) of beryllium over a 50° temperature range. The glass is then fused to the beryllium blank. There have been numerous attempts over the years to produce replicated mirrors using a CVD process to deposit beryllium on a mold. So far these attempts have been unsuccessful, the process producing a material structure that no longer has high stiffness.

Silicon

Silicon as a mirror material has the advantage of being a very homogeneous material that can be polished to very smooth surfaces (angstrom level) very rapidly. A lightweight mirror has been fabricated using a silicon face-sheet brazed to a central core of silicon foam. This mirror 'sandwich' has demonstrated an areal density of <15 kg m^{-2}. Technology has been developed to braze segments together in a manner that has been shown to have no adverse effects on either polishability or cryogenic performance (i.e., no distortion across the braze). Consequently, it should be possible to manufacture lightweight silicon mirrors of 1 m diameter or larger.

Composites

There have been many attempts to manufacture mirrors from composite materials, beginning initially with graphite/epoxy and more recently with graphite/cyanate-ester. These mirror are produced by laying up graphite sheets impregnated with epoxy, or cyanate-ester on a near net shape mold and then curing the material at elevated temperatures. The optical surface is typically created by coating another mold (this time with the desired optical surface) with a passivation layer and then with epoxy and placing the near net shape composite substrate on the epoxy. When the epoxy cures, the completed mirror is separated from the mold and the epoxy surface ion milled to remove residual errors such as fiber print-through. These mirrors can be very lightweight ($\sim$5 kg m^{-2}), but typically have problems with large-scale distortion due to inhomogeneities due to the lay-up process. The epoxy surface replication can also be a problem if the mirror is subjected to temperature extremes. A 3.5 m diameter composite mirror was made as a demonstration for the FIRST program. It has suitable performance for submillimeter and infrared wavelengths, but not for shorter wavelengths. At this time, the accuracy required for large (>1 m) visible imaging systems has not yet been achieved.

Gossamer Mirrors

The term ‘gossamer’ refers to that category of mirrors that in and of themselves have no structural rigidity beyond spatial scales of fractions of millimeters. Several materials are currently being used for these types of materials including Kapton™ and various other polyimide films. The initial shape of the membrane is formed by a variety of techniques including vacuum forming, pressure forming, spin casting, hot forming, and others. Early mirrors were manufactured by joining together triangular-shaped segments (gores) to form the desired shape. When deployed, these mirrors require some means of applying pressure to achieve the desired shape. Some methods have involved applying force at the edge to put the mirror in tension; some involve using a clear membrane as a face-sheet and then pressurizing the combination to create a ‘lens’ with a reflecting inner surface. Most recently, techniques have been demonstrated involving various forms of electrostatic deflection to achieve the desired shape after deployment. At present the primary applications are in the area of solar collection, power beaming, and thermal propulsion. The mirrors are approaching the quality required for imaging telescopes, particularly for small sizes. Techniques for correcting these mirrors with ‘downstream’ active optics have reached the point where it is not unrealistic to imagine that membrane optics could soon reach the accuracy required for imaging. There have been two space-based demonstrations, one by the Russians – a 20 m reflector – and the other by the USA – a 14 m inflatable antenna (Figure 4).



Figure 4 15 m antenna made by L’Garde for NASA’s Inflatable Antenna Experiment. Photograph courtesy of NASA.

Grazing Incidence Mirrors

Broadband X-ray telescopes make use of the reflection property of materials at angles of grazing incidence. The most common design is based on the X-ray microscope objective designs of Wolter in the early part of the twentieth century. These mirrors are hyperboloids and paraboloids of revolution. This configuration provides a structural rigidity not present in normal incidence mirrors; consequently, X-ray mirrors can be made much lighter. The largest mirror of the Chandra X-ray Observatory is made from Zerodur™ (Figure 5). It is a 1.2 m diameter, 0.9 m long cylindrical mirror with a wall thickness of only 24 mm. Such a thickness in a normal incidence mirror of this size could be easily deformed.

Lightweight approaches in grazing incidence optics are almost all concentrated in various forms of replication. Recent developments in electroformed nickel alloy mirror technology have resulted in a 0.5 m diameter 0.6 m long mirror that weighs only 1.2 kg (Figure 6). A similar-sized mirror in the Chandra telescope weighs over 100 kg. Extremely lightweight cylindrical mirrors have been made from graphite/epoxy and from CVD SiC. Various investigations are underway in producing segments of cylinders that are then mounted to form a complete



Figure 5 1.2 m Zerodur™ made by Schott Glass Werken/Hughes Danbury Optical Systems for NASA’s Chandra X-ray Observatory. Photograph courtesy of NASA.



Figure 6 0.5 m electro-formed nickel–cobalt technology mirror made by NASA's George C. Marshall Space Flight Center for NASA's Constellation X-ray Mission technology program. Photography courtesy of NASA.

cylindrical mirror. These techniques involve a variety of materials including aluminum foil, and beryllium plates. In segment replication, the mandrel is passivated and then coated with the desired reflecting material of the final optic (the passivation process prevents the coating from adhering too strongly to the mandrel.) After the mandrel has been coated with the reflecting material, an epoxy coating is applied and a preformed shell segment is placed on the epoxy. After the epoxy cures, the segment can be removed from the mandrel along with the desired reflective surface (typically gold). In this case, the preformed shell does not have to have as precise a figure, or surface as the mandrel, since the epoxy will accommodate minor differences.

See also

Geometrical Optics: Lenses and Mirrors. **Imaging:** Adaptive Optics; Wavefront Sensors and Control (Imaging through Turbulence). **Instrumentation:** Astronomical Instrumentation; Telescopes. **Optical Materials**: Smart Optical Materials.

Further Reading

Bilbro J (2001) Optics in orbit. *SPIE OE Magazine* (Aug. issue).

Breckinridge JB and Jakobsen P (eds) (2000) UV, Optical, and IR Space Telescopes and Instruments. *Proceedings of SPIE* 4013.

Chen PC, Bowers CW, Content DA, *et al.* (2000) Advances in very lightweight composite mirror technology. *Optical Engineering* 39(9).

Ealey MA (ed.) (1995) Silicon carbide materials for optics and precision structures. *Proceedings of SPIE* 2543.

Engelhaupt DE, Ramsey BD, O'Dell SL, *et al.* (2000) New alloys for electroformed replicated X-ray optics. *Proceedings of SPIE* 4138: 22.

Goodman WA and Jacoby MT (2000) Dimensionally stable ultra-lightweight silicon optics for both cryogenic and high-energy laser applications. *Proceedings of SPIE* 4198: 260–270.

Jenkins C (vol. ed.) (2001) Gossamer spacecraft: membrane and inflatable structures technology for space applications. In: Zarchan P (series ed.) *Progress in Astronautics and Aeronautics* 191. Reston, VA: American Institute of Aetronautics and Astronautics.

Kendrick SE, Reed T and Streetman S (2001) In-process status of the 1.4-m beryllium semi-rigid Advanced Mirror System Demonstrator (AMSD). In: Stahl HP (ed.) *Optical Manufacturing and Testing,* vol. IV. *Proceeding of SPIE* 4451: 58–66.

Mathews G (2001) Semi-rigid active mirror technology advancements. *Proceedings of SPIE* 4451.

Müller C, Papenburg U, Goodman WA and Jacoby M (2000) C/SiC high precision lightweight components for optomechanical applications. *Proceedings of SPIE* 4198: 51–57.

Truemper JE and Aschenbach B (eds) (2000) X-Ray optics, instruments, and missions III. *Proceedings of SPIE* 4012.

Measurement of Optical Properties of Solids

P Lucas, University of Arizona, Tucson, AZ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The interaction of light with solids takes place through different mechanisms, depending on the type of material and the range of wavelength investigated. Insulators or dielectrics are typically transparent to visible light while most semiconductors are opaque to visible light yet transparent to infrared radiations; in contrast metallic solids appear shiny because they reflect all wavelength up to the ultraviolet region. The optical properties of a solid depends on its chemical composition and its structural properties and vary for every material, though, one parameter, the complex refractive index **n**, is sufficient to characterize entirely the optical properties of a specific material.

In this article we will briefly review the physics underlining the nature of the refractive index **n**, in order to understand its relationship to the observable quantities such as absorption, reflection, and transmission routinely measured in optics experiments. A description of the experimental techniques, as well as a physical interpretation of the data, will also be presented.

Origin of Light Interaction with Matter

Light is described as a transverse electromagnetic wave consisting of an electric and magnetic field oscillating perpendicular to the direction of propagation at optical frequencies within $10^{13} \rightarrow 10^{17}$ Hz. This range of frequencies comprises the ultraviolet, visible, and infrared domain. On the other hand, solid mediums are composed of charged particles, negative electrons, and positive ions producing electric dipoles, which can be polarized under the action of an electric field. Hence, when electromagnetic radiation impinges upon a material it interacts by polarizing the molecular units, producing oscillating dipole moments. This interaction results in several observable optical phenomena such as reflection, transmission, absorption, or scattering, which will be described in more detail in a following section. The classical model of light propagation assumes that the oscillating electric field can interact with several different types of dipole oscillators within the material. Different dipoles are usually accessed by light wave from different frequency range depending on their mass.

Electronic Oscillators

Lorentz originally proposed that the electrons bound to the nucleus of an atom behave as oscillators. In this representation, electrons behave as if they were held by springs and subjected to a linear restoring force, therefore oscillating up and down (Figure 1a). This representation of an atom might seem to contradict the conventional picture of electrons orbiting around the nucleus; however, it is valid as far as light–matter interactions are concerned. The resonant frequency of such an oscillator is proportional to the inverse of its reduced mass μ defined as

$$\frac{1}{\mu} = \frac{1}{m_e} + \frac{1}{m_N} \qquad [1]$$

where m_N and m_e are the mass of the nucleus and electrons, respectively. The resonant frequency ω_0 is then related to μ according to

$$\omega_0 \propto \sqrt{\frac{1}{\mu}} \qquad [2]$$



Figure 1 (a) Classical oscillator model of a polyelectronic atom. The electrons depicted as black dots are bound to the positive nucleus by springs, which represent the electrostatic restoring forces between the charged particles. The electronic oscillators are distorted under the effect of an electric field. (b) Classical model of a diatomic vibrational oscillator. The chemical bond is represented as a spring and the charged ions vibrate around their equilibrium position under the effect of an oscillating electric field.

Considering that $m_N \ll m_e$ we can assume that $\mu = m_e$ and show that the smaller mass of the electron determines the resonant frequency of the oscillator. Hence, resonant electronic oscillations are accessed at higher frequencies in the ultraviolet and visible region of the spectrum. In solids, the quantum theory shows that these resonances correspond to excitation of electrons across the gap between a full valence band and an empty conduction band.

Vibrational Oscillators

The second type of dipoles contained in the medium are based on pairs of charged atoms vibrating around their equilibrium position in the solid. Every atom has a different electronegativity, hence the electronic density on atomic pairs is distorted and result in a charge imbalance, which can couple to the electric field of light. This generates oscillating dipoles, which involves the motion of atomic nucleus (Figures 1b). The nuclear mass being several orders of magnitude larger than the electronic mass, we can show by analogy with eqns [1] and [2] that the resonant vibration will occur at lower frequencies in the infrared region. In solids, the quantum theory shows that the lattice atoms vibrate cooperatively and generate quantized lattice waves called phonons.

Free Electron Oscillators

In contrast with the bound electrons from the electronic oscillator model, free electrons can move without being subjected to a restoring force. These correspond to the conduction electrons present in metals and to a smaller extent in doped semiconductors. The free electron oscillator model is therefore



Figure 2 Contributions to the polarizability of a medium as a function of light frequency. At optical frequencies, the molecules cannot re-orient fast enough to follow the reversing electric field and the contribution of dipole orientation is lost.

principally used to describe the optical properties of metals such as reflectivity. The free electrons are well described as conventional oscillator with a natural resonant frequency $\omega_0 = 0$.

The relationship between the applied electric field E and the resulting polarization of the medium P is expressed through the dielectric susceptibility χ as

$$P = \varepsilon_0 \chi E \qquad [3]$$

where ε_0 is the permittivity of vacuum. We can generally recognize three contributions to the dielectric susceptibility or the polarizability of an optical material (Figure 2). Applied fields in the radio or microwave region oscillate slowly enough that polar molecular units can reorient and align in the direction of the field. The characteristic time for orientational motion is fairly long and this contribution is quickly lost when the molecules cannot follow the field oscillating at higher frequency. When the field reaches optical frequency, the two remaining contributions are the vibrational and electronic dipoles mentioned above. The vibrational dipoles involve a distortion of the chemical bond and are the slowest process occurring only in the infrared region. This contribution is lost at visible frequencies and leaves only the fast electronic polarization processes.

If we treat it rigorously, the polarization P is actually expressed as a function of higher order terms according to

$$P = \varepsilon_0 \left(\chi E + \chi^{(2)} EE + \chi^{(3)} EEE + \ldots \right) \qquad [4]$$

This gives rise to nonlinear effects such as self-focusing and second or third harmonic generation. However, the higher order susceptibilities $\chi^{(n)}$ are very small and these effects are only significant for very high intensity light source such as lasers. In the following text we will only consider linear optical processes.

The Dipole Oscillator Model (Lorentz Oscillator)

In the Lorentz model, the bound electrons behave as harmonic oscillators and are constrained to vibrate at their natural resonant frequency ω_0. These oscillators are also submitted to a damping force corresponding to a resistance to the motion due to collisional processes. The equation of motion is then

$$m\left(\frac{d^2 x}{dt^2} + \gamma \frac{dx}{dt} + \omega_0^2 x \right) = qE \qquad [5]$$

where x is the displacement along E, γ is the damping factor, m is the mass of the electron and q its charge. The passage of an electromagnetic wave through a medium exerts an oscillating force on the electrons causing them to vibrate up and down. In other words these electronic dipoles are submitted to a forced oscillation induced by an electric field varying periodically with time. The electric field felt by the atomic dipoles is written as

$$E = E_0 e^{i\omega t} \qquad [6]$$

where ω is the frequency of the light.

The electric field of the light wave then drives the dipole oscillations at its own frequency ω and the dipoles displacement oscillates according to

$$x = x_0 e^{i\omega t} \qquad [7]$$

Solving eqn [5] for x in terms of E gives the expression for the displacement of the electrons

$$x = \frac{q/m}{\omega_0^2 - \omega^2 + i\gamma\omega} E \qquad [8]$$

The atomic dipole moment p induced by the electrons displacement is therefore

$$p = qx = \frac{q^2/m}{\omega_0^2 - \omega^2 + i\gamma\omega} E \qquad [9]$$

And for a medium with N atoms per unit volume the total polarization P is

$$P = N \frac{q^2/m}{\omega_0^2 - \omega^2 + i\gamma\omega} E \qquad [10]$$

Our result in eqn [10] only contains one natural frequency ω_0 and therefore only accounts for one single type of oscillator in the medium. However, normal optical mediums are composed of different kinds of atoms, each with several characteristic resonant frequencies ω_j. In our model, we can simply treat these multiple resonances by considering that each oscillator acts separately and add the contributions of all oscillators.

$$P = \left(\frac{q^2}{m} \sum_j \frac{N_j}{\omega_j^2 - \omega^2 + i\gamma_j \omega} \right) E \qquad [11]$$

Comparing eqns [3] and [11] then gives an expression for the polarizability χ of the medium

$$\chi = \frac{q^2}{\varepsilon_0 m} \sum_j \frac{N_j}{\omega_j^2 - \omega^2 + i\gamma_j \omega} \qquad [12]$$

Additionally, the polarization P is associated with Maxwell's displacement vector, D, through the relationship

$$D = \varepsilon_0 E + P \quad \text{and} \quad D = \varepsilon E \qquad [13]$$

where ε is the permittivity of the medium. The permittivity ε is normally expressed relative to the permittivity of vacuum ε_0 in terms of the dimensionless quantity $\varepsilon_r = \varepsilon/\varepsilon_0$. Where ε_r is the familiar dielectric constant of a material, which is related to the refracted index n as $n = \sqrt{\varepsilon_r}$.

Combining eqns [3] and [13] we obtain an important relationship linking χ to ε_r, and in turn χ to n.

$$\varepsilon_r = 1 + \chi \quad \text{or} \quad n^2 = 1 + \chi \qquad [14]$$

Finally, combining eqns [12] and [14] we obtain the expression for n in terms of the oscillator model.

$$n^2 = 1 + \frac{q^2}{\varepsilon_0 m} \sum_j \frac{N_j}{\omega_j^2 - \omega^2 + i\gamma_j \omega} \qquad [15]$$

The Refractive Index

Two important points should be made concerning the result of eqn [15]. The refractive index is a wavelength-dependent quantity and is a complex quantity. The complex refractive index **n** is indeed usually expressed as

$$\mathbf{n} = n + i\kappa \qquad [16]$$

where n is the real refractive index also defined as the ratio of the wave velocity in vacuum to the velocity in the medium $n = c/v$. And κ is the extinction coefficient, which is directly related to the absorption coefficient α as we shall see in the next section.

As we mentioned in the introductory section, the complex refractive index **n** is sufficient to characterize the optical properties of the solid. The real part of the index describes the change in velocity or wavelength of a wave propagating from a vacuum into a medium while the imaginary part is a measure of the dissipation rate of the wave in the medium.

By inspection of eqn [15] we can predict the form of the variation of n with wavelength. At frequencies ω below the resonant frequency ω_j, the terms ω^2 and $i\gamma_j\omega$ are much smaller than ω_j^2 and to a first approximation n is constant. When ω reaches a resonant frequency ω_j, the term $(\omega_j^2 - \omega^2)$ goes to zero and since the term $i\gamma_j\omega$ is very small, the value of n increases very sharply and exhibits a resonance line as depicted in Figure 3.

On closer inspection of eqn [15] however, we can see that n is not exactly constant in between resonance lines. As ω rises, the denominator slightly decreases and therefore n rises slowly with frequency. The refractive index is then slightly larger for wave of higher frequency. This is why a glass prism bends blue light more strongly than red light. This phenomenon is called dispersion as waves of different frequencies are 'dispersed' by the prism.

Another important point raised by eqn [15] is that because $(\omega_j^2 - \omega^2)$ goes to zero at a resonant frequency, the damping term $i\gamma_j\omega$ dominates and n becomes almost entirely imaginary. **n** is then mostly governed by the extinction coefficient κ. The damping associated with the coefficient γ_j corresponds to a friction force causing a loss of energy, which becomes the dominant effect during resonance. The resonance region is then associated with strong attenuation or



Figure 3 Variation of the refractive index of a hypothetical dielectric solid in the optical frequency range. At high frequency, ω is larger than all resonant frequencies and the refractive index n reaches unity.

absorption of the wave. In contrast, between resonant frequencies, the refractive index is almost entirely real as the imaginary part $i\gamma_j\omega$ is negligible in comparison with $(\omega_j^2 - \omega^2)$. Absorption is then very small and that region corresponds to the transparency domain of the material. In fact, we can assume that $\mathbf{n} = n$ in the transparent region, that is why tables of optical constants of transparent optical materials only list the real part of the refractive index n. However, at resonant frequencies on either side of the transparency domain, absorption becomes significant and the imaginary part of the refractive index must be taken into account so that $\mathbf{n} = n + i\kappa$.

The refractive index $\mathbf{n}$ being a complex quantity it ensues that ε_r must also be complex, since $n = \sqrt{\varepsilon_r}$. Hence we also define the complex dielectric constant as

$$\varepsilon_r = \varepsilon_1 + i\varepsilon_2 \qquad [17]$$

Both parameters describe equivalently the optical properties of a solid so that $\mathbf{n}$ or ε_r are called the optical constants of the material. Note that it is an unfortunate misnomer since they vary distinctly with wavelength (Figure 3).

Using equation [17] and $n = \sqrt{\varepsilon_r}$, we can establish the relationships between the real and imaginary parts of $\mathbf{n}$ and ε_r.

$$\varepsilon_1 = n^2 - \kappa^2 \qquad [18]$$

$$\varepsilon_2 = 2n\kappa \qquad [19]$$

We can see that $\mathbf{n}$ and ε_r are not independent variables but that the real and imaginary part of ε_r can be calculated, knowing the real and imaginary part of $\mathbf{n}$ and vice versa.

Moreover, it can be shown that the real and imaginary parts of each individual parameter are not independent either but can be computed from one another with use of the following Kramers–Kronig relations.

$$\varepsilon_1(\omega) = 1 + \frac{2}{\pi}\int_0^\infty \frac{\omega'\varepsilon_2(\omega')}{\omega'2 + \omega^2}\mathrm{d}\omega' \qquad [20]$$

$$\varepsilon_2(\omega) = -\frac{2\omega}{\pi}\int_0^\infty \frac{\varepsilon_1(\omega')}{\omega'2 + \omega^2}\mathrm{d}\omega' \qquad [21]$$

In these equations, only the principal value of the integral is calculated so that ε_1 can be computed if ε_2 is known over all frequencies and vice versa. The same equation connect n and κ together.

This analysis shows that it is only necessary to know one real or one imaginary part over a wide frequency range to determine all others. The interaction of light with matter is in fact characterized by a single independent real quantity.

Absorption

All electromagnetic phenomena are governed by Maxwell's equations. The form of an electromagnetic wave propagating through a medium is obtained by solving Maxwell's equation. For a wave propagating along z through a homogeneous, optically isotropic medium the form of the oscillating electric field is given by:

$$E = E_0 e^{i(kz-\omega t)} \qquad [22]$$

where k is the wave vector and ω the angular frequency of the light. For a wave traveling into a transparent medium of refractive index n, the relationship between k and ω is

$$k = \frac{n\omega}{c} \qquad [23]$$

However, for an ordinary optical material there are regions of absorption and the refractive index is therefore complex. We should then rewrite eqn [23] as

$$k = (n + i\kappa)\frac{\omega}{c} \qquad [24]$$

By substituting this value of k in eqn [22] we obtain an expression with two exponential terms

$$E = E_0 e^{-\frac{\omega\kappa z}{c}} e^{i\left(\frac{\omega n z}{c} - \omega t\right)} \qquad [25]$$

The term $e^{i\left(\frac{\omega n z}{c} - \omega t\right)}$ represents a wave traveling at a speed $v = c/n$, while the term $E_0 e^{-(\omega\kappa z/c)}$ represent the amplitude of this wave which decays exponentially with distance z. The intensity I of the wave is proportional to the square of the amplitude so that

$$I \propto e^{-\frac{2\omega\kappa z}{c}} \quad \text{or} \quad I \propto e^{-\alpha z} \qquad [26]$$

where α is the familiar absorption coefficient routinely measured by absorption spectroscopy. Hence we obtain an important relationship relating the observable quantity α to the imaginary part of the refractive index κ according to

$$\alpha = \frac{2\kappa\omega}{c} \qquad [27]$$

Local Field Correction

It should be pointed out that the derivation of our refractive index expression eqn [15] assumes that only the electric field of the light affects the polarization of the dipole oscillators. However, this assumption is not correct in dense materials because of the contribution from the electric field of neighboring atomic dipoles. The field generated by each dipole will affect all other dipoles in the vicinity. It is possible to approximate this contribution by accounting for the effect of dipoles within a local sphere. The result of this approximation is known as the Clausius–Mossotti equation, which is accurate for isotropic medium such as glasses and cubic crystals

$$\frac{n^2 - 1}{n^2 + 2} = \frac{\chi}{3} \qquad [28]$$

Measurable Optical Parameters

Four things can happen to a beam of light propagating through a thick slab of optical material (Figure 4). Some of the light can be reflected at the surface of the solid, some can be absorbed by the sample, some can be scattered in different directions, and some of the light can be transmitted through the sample. The effect on the light beam, resulting from these phenomena, can be quantified by a number of optical coefficients, which characterize the macroscopic properties of the material.

Reflection of light at the surface of a solid is described by the reflectance R defined as the ratio of the reflected intensity I to the incident intensity I_0. For a beam falling perpendicularly on a flat surface, the reflection is called specular and is governed by the complex refractive index according to the Fresnel equation

$$R = \frac{I}{I_0} = \frac{(n-1)^2 + \kappa^2}{(n+1)^2 + \kappa^2} \qquad [29]$$

This provides us with a second important formula relating a measurable quantity (R) to the optical constant of the material. For measurements performed within the transparency region of a solid, the value of κ is much less than n and eqn [29] reduces to the more familiar form

$$R = \frac{(n-1)^2}{(n+1)^2} \qquad [30]$$



Figure 4 Representation of the four main optical processes happening to a beam as it propagates through a slab of transparent material.

Absorption occurs when the light frequency reaches the natural resonance of some dipole oscillators in the medium. The energy of the electromagnetic wave is partly transferred to the material and generally dissipated in the form of heat. The light intensity is therefore attenuated as it propagates through the material and the attenuation efficiency is quantified by the absorption coefficient α. The intensity decreases exponentially with pathlength z according to Beer's law

$$I(z) = I_0 e^{-\alpha z} \qquad [31]$$

where I_0 is the incident intensity. The imaginary part κ of the optical constant can then be directly obtained from measurements of α using eqn [27].

Scattering is the process whereby light is redirected in different directions due to microscopic density fluctuation in the sample produced by defects, impurities, or structural inhomogeneities. The intensity of light propagating in the forward direction is attenuated by the scattering event and it can be quantified in a way equivalent to absorption. The intensity has an exponential dependence on pathlength z analogous to Beer's law

$$I(z) = I_0 e^{-Sz} \qquad [32]$$

where S is the scattering coefficient. When the scattering center is smaller than the wavelength of light this phenomenon is called Rayleigh scattering and the scattering coefficient S vary with the inverse fourth power of the wavelength

$$S(\lambda) \propto \frac{1}{\lambda^4} \qquad [33]$$

By measuring light attenuation we cannot tell the difference between absorption and scattering and the total attenuation is $\alpha_{\mathrm{Tot}} = \alpha + S$. However, the scattering contribution is generally much weaker than the absorption and can be neglected so that $\alpha_{\mathrm{Tot}} = \alpha$.

Transmission occurs when the light is neither reflected, absorbed, or scattered. The beam is then transmitted through the sample and the fraction of light exiting the back surface is quantified as the transmittance T. If we disregard scattering in comparison to absorption then conservation of energy require that

$$R + T + A = 1 \qquad [34]$$

where A is the fraction of light absorbed. The transmittance can then be compiled from R and α for an incident beam I_0 traveling across a sample of thickness l. In this case we must consider the reflection of the light on the front surface as well as on the back surface when it exits the transparent medium. The expression for the transmittance accounting for dual reflection is

$$T = (1 - R)^2 e^{-\alpha l} \qquad [35]$$

It should be noted that a rigorous treatment of eqn [35] should account for multiple reflections between the front and back surface in the interior of the sample. In this case, interference effects complicate the determination of **n** and a modified version of eqn [35] can be computed by summing up the intensities due to the contribution of the multiple reflections.

Transmission and reflection measurement are readily obtained using conventional spectrometers. Two types of spectrometers must be used to cover the entire optical spectral region. FTIR (Fourier Transform Infra Red) spectrometers use a glow bar as the light source, which enable it to cover the infrared and near infrared domain. The UV-VIS (ultraviolet visible) double beam spectrometers use a tungsten and deuterium lamp and cover the spectrum from the ultraviolet down to the near infrared. Using eqns [27], [29] and [35], the reflection and transmission measurements thus obtained are used to calculate the real and imaginary component of the optical constant over the entire optical frequency range.

An example of transmission measurement is shown in Figure 5, for a dielectric and a semiconductor. The two spectra have the same principal features. At short wavelength the edge of the transparency window is due to absorption of energy by the valence electrons. In classical terms this corresponds to the resonance of electronic oscillators, and in quantum mechanical terms to the excitation of electrons from the valence to the conduction band. This edge is due to a sharp increase of κ, which extends over a significant range of frequency corresponding to the domain of opacity or high absorption. The wavelength at the edge determines the minimum energy of the photon necessary to promote an electron across the bandgap E$_g$. Insulators have a large bandgap and appear transparent to the human eye because visible light is not energetic enough to promote an electron across E$_g$. In contrast, semiconductors have a smaller bandgap and appear black (opaque) because all the visible light is absorbed to induce electronic transitions. On the low frequency side the transparency window is limited by atomic vibrations in the solid structure. The wavelength of the vibrations increases with the mass of the atomic oscillators. Semiconductor compounds have higher atomic masses and therefore transmit at longer wavelength in the infrared while insulator have lower atomic mass and exhibit their vibrational absorption edge at shorter wavelength.

In between the two absorption regions, κ is very small and the material is transparent. The refractive index is almost entirely governed by the real part n. Eqn [15] shows that n is proportional to the number N of electronic oscillators. The refractive index will then be higher for heavy atoms with a high electronic



Figure 5 (a) Transmission spectrum of SiO$_2$ glass, a standard dielectric solid. (b) Transmission spectrum of GeSe$_3$ glass, a semiconductor (E$_g$ = 1.6 eV). (c) Reflectance spectrum of silver metal.



Figure 6 Refraction of a beam propagating across the interface between two mediums of different refractive index. The incident angle and the refraction angle are related to the index of refraction through Snell's Law.

density. Consequently, semiconductors exhibit a maximum transmission of only 60% because of significant surface reflectivity (eqn [35]) resulting from their higher refractive index n (eqn [30]).

Most applications of materials in optics are only concerned with the transparency domain so that the useful optical constant is reduced to the real part n. Hence a number of experimental techniques have been developed to obtain n, often by measuring angles of refraction with the use of Snell's law

$$n_1 \sin \theta_1 = n_2 \sin \theta_2 \qquad [36]$$

where θ_1 is the angle of the beam incident in the medium of index n_1, and θ_2 the angle of the beam refracted at the interface with a medium of index n_2 (Figure 6). The basic principle is to compare the sample with a standard glass of known refractive index and measure the refraction angle at their interface. The sample's index can then be obtained following eqn [36]. Since n varies with wavelength, these techniques are normally performed with monochromatic light and provide n at a single wavelength. Among these methods are: the *Abbe refractometer*, using a glass hemisphere as a standard, the *V-block refractometer*, using a V shaped prism as a standard, and the *prism goniometer* based on the relative deviation between a known glass prism and a prism shaped sample.

Ellipsometry is another technique widely used to measure the index n. This technique is normally used on thin films deposited on substrate, as it allows to simultaneously measure the thickness and the refractive index. However, the method can also be applied to bulk samples. The principle of ellipsometry is based on measuring the change in polarization of a beam reflected off the sample surface as a function of incidence angle. The reflected light is elliptically polarized to an extent depending on n. This technique is especially useful to measure n at frequency range above the absorption edge where the sample is highly absorbing.

Metals

The optical properties of metals are mainly characterized by their very high reflectivity, which causes their shiny appearance. All metals reflect light in the infrared and visible region up to a cutoff frequency in the ultraviolet. This critical frequency is called the plasma frequency ω_p. The physical significance of the plasma frequency can be understood using the Drude–Lorentz model of the free electron oscillator. As mentioned previously, the free electron can be described accurately as dipole oscillators with a resonant frequency $\omega_0 = 0$. If we consider a system with negligible damping, we can introduce $\gamma = 0$ and by assuming all free electrons to be equivalent we can consider only one type of oscillators so that eqn [15] reduces to

$$n^2 = 1 - \frac{\omega_p^2}{\omega^2} \qquad [37]$$

where

$$\omega_p^2 = \frac{Nq^2}{\varepsilon_0 m_e} \qquad [38]$$

Equation [37] means that in the low frequency domain $\omega < \omega_p$, the refractive index n must be imaginary ($n^2 < 0$) and in the high frequency domain $\omega > \omega_p$, n is a real positive number. The low frequency region is therefore dominated by the extinction coefficient κ and the reflectance R, given by eqn [29], is essentially unity. In the high frequency limit, R decreases and n is real. These features are shown in Figure 5c. Metals are opaque and highly reflective below the plasma frequency, while they become transparent in the ultraviolet.

List of Units and Nomenclature

A	absorbance
c	light velocity in vacuum
D	electric displacement
E	electric field
I	intensity of light (power per unit surface)
k	wave vector
m_e	mass of electron
m_N	mass of nucleus
$\mathbf{n}$	complex refractive index
n	real refractive index

p	dipole moment
P	polarization
q	charge of electron
R	reflectance
S	scattering coefficient
T	transmittance
v	phase velocity
α	absorption coefficient
ε_0	permittivity of vacuum
ε_r	relative dielectric constant
κ	extinction coefficient
λ	wavelength
μ	reduced mass
χ	dielectric susceptibility
ω	angular frequency
ω_0	resonant frequency
ω_p	plasma frequency

See also

Instrumentation: Ellipsometry; Spectrometers. **Scattering:** Scattering from Surfaces and Thin Films.

Further Reading

Abeles F (1972) *Optical Properties of Solids*. North Holland Publishing Company.

Born M and Wolf E (1999) *Principles of Optics*, 7th edn. Cambridge University Press.

Dragoman D and Dragoman M (2002) *Optical Characterization of Solids*. Springer.

Feynman RP (1970). *Lectures on Physics*, vol. I–III. Addison–Wesley.

Fox M (2001) *Optical Properties of Solids*. Oxford University Press.

Hecht E (1998) Optics, 3rd edn. Addison–Wesley.

Klingshirn CF (1997) *Semiconductor Optics*. Springer.

Nazarewick W, Rolland P, Dasilva E and Balkanski M (1962) ABAC chart for fast calculation of the absorption and reflection coefficients. *Applied Optics* 1(3): 369–370.

Palik ED (1985) *Handbook of Optical Constants of Solids*. Academic Press.

Savage JAR (1990) Signals radar. *Optical Materials* 1:323–419.

Simmons CJ and El-Bayoumi OH (1993) *Experimental Techniques of Glass Science*. The American Ceramic Society.

Simmons JH and Potter KS (2000) *Optical Materials*. Academic Press.

Optical Glasses

J E Shelby, Alfred University, Alfred, NY, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

While advances continue in this field, some optical glasses have histories which can be traced to the seventeenth century. These glasses are produced by direct melting of raw materials of relatively high purity. Modern, or nontraditional, optical glasses are more commonly used to transmit light outside the visible region and are often made by nontraditional methods, including many variations on chemical vapor deposition, reactive melt processing, and sol–gel techniques. These glasses are used for ultraviolet and infrared lenses and other optical components, for optical fibers, for glass lasers, and for photonic devices such as optical isolators. Purity requirements and production demands for these glasses are significantly greater than those for traditional optical glasses.

Traditional Optical Glasses

Traditional optical glasses are primarily used as components such as lenses, prisms, or windows for optical systems operating in the visible region. These applications require glasses of high homogeneity, with precisely known refractive indices and dispersions. Glasses, as defined in this article, are nonmetallic, inorganic materials which have no long-range atomic structure and which display a temperature region of time-dependent properties.

Crown and Flint Glasses

Traditional optical glasses are designated as either crown or flint glasses. Crown glasses were originally based on the soda-lime-silica ternary system and were developed for use as window glass. The crown process involved spinning a spherical gob of molten glass to form a flattened disk which was much thicker in the center than at the edges. The edges of these disks were used for window panes, while the ‘crown’ in the center was often used as a crude lens. Crown glasses have low refractive indices and low to moderate dispersions.

The first flint glasses were potash-lead-silicate glasses prepared using English ‘flint’ as the source of silica. The presence of lead in these glasses results in higher refractive indices and dispersions than those of crown glasses.

The designations of crown and flint have since been expanded to include glasses from many other compositional systems. Glasses with lower refractive indices and dispersions are designated as crowns, while those with higher refractive indices and dispersions are designated as flints. Modern crown glasses are based on silicate, phosphate, and borosilicate systems. Additions of fluorine are particularly useful for production of low refractive index, low dispersion glasses, and for adjusting these parameters to meet specific needs. The lowest combinations of refractive index and dispersion are found for glasses based on BeF_2, while the highest combinations of refractive index and dispersion are found in rare earth borate systems. Other common optical glasses contain barium or lanthanum, which can be used to produce either crown or flint glasses, depending on the other components of the glass.

The need for glasses with different combinations of refractive index and dispersion can be traced back to the development of the telescope. Use of lenses made of a single glass made it difficult to obtain sharp images. Newton recognized that this problem was due to divergence of light of different wavelengths while passing through a lens. He felt that this problem was inherent to lenses and could not be eliminated. Others eventually recognized that a compound lens containing a positive crown glass and a negative flint glass would result in cancellation of the divergences and produce a sharper image. While this development did not totally eliminate the colored fringes in telescope images due to the presence of the secondary spectrum, it did lead to major improvements in optical imaging. Binary compound lenses are still fashioned from a combination of crown and flint glasses, with much greater flexibility today due to development of glasses with much more varied combinations of refractive index and dispersion.

Notation for Optical Glasses

Since the refractive index and the dispersion are the two most important characteristics of an optical glass for use as a lens, a notation system has been developed to designate any glass by a six digit number. This notation system requires that the dispersion be expressed by the Abbe number, ν_d, which is defined as

$$\nu_d = (n_d - 1)/(n_F - n_c) \qquad [1]$$

where d, F, and c indicate the value of the refractive index measured at the yellow helium line at 587.6 nm, the blue hydrogen line at 486.1 nm, and the red hydrogen line at 656.3 nm, respectively. Since the Abbe number is a reciprocal dispersion, a large Abbe number indicates a low dispersion, while a small Abbe number indicates a larger dispersion. A glass is then designated by the expression

$$1000(n_d - 1)(10\nu_d) \qquad [2]$$

where each term is rounded to 3 significant digits. A common crown glass known as BK7, for example, which has a n_d of 1.516 800 and ν_d of 64.17 is designated as 517 642. A very high index flint glass, with $n_d = 1.807\,410$ and $\nu_d = 31.61$ would be designated as 807 316. This system can be used for all but the exceptional glasses with $n_d \geq 2.00$. Some tabulations are based on the green mercury line, or e line, at 546.1 nm instead of the yellow helium (d) line. The choice of the d or e line results in a small difference in the reported refractive index and Abbe number for any given glass (Figure 1).

Dispersion Formulae for Optical Glasses

The combination of a refractive index near the middle of the visible region of the spectrum and the Abbe number describe the contribution of an optical glass to the refractive power and chromatic aberration of a lens. This information was sufficient for many early applications of lenses and is still sufficient for the design of optical devices of modest expectations. More sophisticated optical devices require more information for proper design. The simple Abbe number is often insufficient for expressing the dispersion, since it is necessary to provide a



Figure 1 Relation between the refractive index and Abbe number of optical glasses. Commerical optical glasses lie in the regions labeled flint and crown above the curve.

detailed set of values of the refractive index as a function of wavelength across the entire visible region. The refractive index can be listed at a number of wavelengths, or described by an equation covering the entire wavelength range of interest. Although there are a number of expressions for the wavelength dependence of the refractive index, the most commonly used are the Cauchy dispersion formula, or

$$n = a + b\lambda^{-2} + c\lambda^{-4} \qquad [3]$$

where a, b, and c are constants derived from a best fit of the data to this expression, and variations of the Sellmeier dispersion formula, which is often simplified to the expression

$$n^2 = A_0 + A_1\lambda^2 + A_2\lambda^{-2} + A_3\lambda^{-4} + A_4\lambda^{-6} + A_5\lambda^{-8} \qquad [4]$$

where the six A_n constants are tabulated. The Cauchy dispersion formula is accurate to $\approx 10^{-4}$, while the modified Sellmeier dispersion formula is accurate to $\approx 3 \times 10^{-6}$. The validity of the latter expression can be extended further into the ultraviolet by adding a λ^{-10} term and into the infrared by adding a λ^4 term.

Annealing of Optical Glasses

Much of our knowledge of the behavior of glasses in the glass transformation region is based on studies of the annealing of optical glasses. Glass-forming melts have much higher thermal expansion coefficients than those of solid glasses of the same composition. During cooling of a melt, the density increases rapidly so long as the melt is relatively fluid. As the viscosity increases, the rate of structural rearrangement of the melt slows and eventually becomes fixed at some effective, or fictive, temperature. If the melt is cooled rapidly, the structure of the glass will be representative of a high temperature melt. If the melt is cooled more slowly, the structure will have time to equilibrate at lower temperatures and the glass formed will have the structure of a lower temperature melt and hence will be more dense. Since the refractive index of a solid is related to its density, the refractive index will be less for the glass produced by rapid cooling than for one produced by slower cooling.

There are two ramifications of the cooling effect on refractive index. First, the refractive index will be different for different cooling rates, even though the composition is identical. Statements regarding the refractive index of a glass are only applicable for a known thermal history. Second, but less obvious, the outside of a piece of glass will cool more rapidly than the inside due to the kinetics involved with removing heat from the glass. As a result, a refractive index gradient will exist in the glass, with a lower refractive index at the surface. If the glass is ground and polished to form a lens, the lens will not perform as expected if the shape is based on the assumption that the refractive index is constant through the entire lens. While cooling-induced differences in refractive index between the surface and center of a large block of glass are usually of the order of 0.000 1, they can be ≥ 0.001 for a rapidly cooled block.

Control of the cooling rate is essential for the production of a block of glass of uniform refractive index. The cooling rates used to reduce stresses to acceptable levels in the production of nonoptical glasses are much too fast for the production of optical glasses. Use of a constant cooling rate throughout the glass transformation region will not yield a block of uniform refractive index. Ideally, the cooling rate should be decreased gradually as the temperature decreases throughout the glass transformation region. The production of a fine annealed glass requires a very slow cooling process, with a gradually decreasing cooling rate with decreasing temperature within the temperature region where permanent changes in the structure of the glass can occur.

Athermal Lenses

While the thermal expansion coefficient of many glasses is relatively low, it is not zero. As a result, the dimensions and refractive index of a glass are functions of temperature. Temperature changes in an optical system therefore result in changes in optical path length. While changes in optical path length of this magnitude may be unimportant for optical systems used within a narrow temperature range, those used over ranges exceeding 10 to 20 K must be designed to minimize thermal effects. Production of athermal optical systems, i.e., systems of constant power over a range of temperatures, requires use of glasses where the thermal changes in refractive index are exactly offset by the changes in dimensions, i.e., the optical path length is independent of temperature. This condition is met if the temperature coefficients of the index and the thickness are equal and of opposite sign.

The overall effect of changes in temperature on the optical path length are tabulated in terms of the thermo-optical constant, G, given by

$$G = \alpha(n - 1) + \mathrm{d}n/\mathrm{d}T \qquad [5]$$

where α is the linear thermal expansion coefficient, n is the refractive index, and $\mathrm{d}n/\mathrm{d}T$ is the thermal coefficient of the refractive index. Perfect compensation between changes in index and dimensions are obtained when $G = 0$. Since α is positive for most optical glasses, with values in the range of 3 to 15 ppm/K, this condition requires a negative dn/dT. Negative values of dn/dT are found primarily for glasses containing some fluorine, such as fluoride glasses and those in which oxygen is partially replaced by fluorine, such as fluorosilicates, fluoroborates, etc., or for some phosphate glasses. Silicate glasses rarely, if ever, have a negative value of dn/dT. For the same glassformer, e.g., P_2O_5, use of modifier ions with large diameters and low field strengths favor increasingly negative values of dn/dT.

The value and sign of dn/dT is determined by the competition between the decrease in refractive index induced by an increase in molar volume and the increase in the refractive index induced by an increase in polarizability of the ions in the glass with an increase in temperature. Equation [5] indicates that the absolute value of the refractive index is also important in determining the value of G. If the refractive index is high, then dn/dT must be more negative to yield $G = 0$. As a result, most athermal glasses are crown glasses. The value of dn/dT is also wavelength-dependent, generally decreasing with increasing wavelength. In particular, dn/dT becomes more positive at wavelengths near the UV edge of the glass. An athermal lens is only perfectly athermal at the design wavelength.

A few special glasses and glass-ceramics used for optical applications, e.g., vitreous silica, titanium-doped silica, and some aluminosilicate glass-ceramics, have thermal expansion coefficients which approach zero or are slightly negative. Vitreous silica has a very low refractive index and thermal expansion coefficient and can be used to produce lenses which, while not truly athermal, have relatively low temperature sensitivity. These low thermal expansion materials are often used as substrates for coated reflective optics (mirrors), where dimensional stability is far more important than any change in the refractive index of the substrate.

Production of Traditional Optical Glasses

Quality requirements for optical glasses are much greater than those for other common glasses. A constant refractive index throughout the glass requires an extremely high degree of homogeneity. The glass must be free from defects such as striae (regions of refractive index variation due to density/composition variations) and stones (undissolved material) and the bubble content must be as low as possible. The thermal history of the glass must be such that the refractive index variation, due to differing fictive temperatures, is minimized. Internal stresses must be minimized to yield a low birefringence. The glass must also be free of any species which contribute to absorption in the desired spectral region.

The quality demands of optical glasses require use of much higher quality, and thus more expensive, raw materials. Concentrations of third-row transmission metal ions must be held to rigid specifications, with maximum values usually in the ppm, or even in the ppb range, for the highest quality glasses. Defects are reduced by melting in platinum containers instead of the oxide containers used in the past. Stirring the melt, using platinum wherever possible, is essential for obtaining acceptable homogeneity. Control of the melting atmosphere may be essential for controlling the redox state of the melt. Rigorous annealing schedules must be used to produce glasses with the desired thermal history so that the problems of stress-induced birefringence and refractive index gradients are reduced to acceptable levels.

Non-Traditional Optical Glasses

While most traditional applications of optical glasses involve transmission in the visible, many modern applications require high transmission in the ultraviolet, near-infrared, or infrared regions of the spectrum. Transmission in each of these regions is determined by both the bulk composition of the glass and by the concentration of impurities present. Most nontraditional applications place even more stringent requirements on the purity of the materials used in manufacturing the glass. An extreme example of the demand for purity is found in the glasses used for telecommunication optical fibers, where concentrations of some impurities must be held to the low ppb level.

Ultraviolet-Transmitting Glasses

The ultraviolet transmission of a glass is determined by the intrinsic electronic transitions of the material, by charge transfer absorption bands due to impurities, and by surface and bulk scattering. The first of these is determined by the electronic bandgap of the material, while the other two are controlled by the care taken during production of the glass. These glasses are used in spectroscopy for windows, lenses, UV-lamps, and sample cuvets, for microlithography, and for lenses in excimer laser optical systems.

Vitreous silica is widely used as an ultraviolet transmitting glass for transmission optics at wavelengths well below 200 nm. The lowest energy absorption band for this glass occurs at 10.2 eV, or 122 nm. Many UV–VIS spectrometers, which normally are capable of measurements extending to 185 to 190 nm, use vitreous silica as optical elements. Additions of alkali or alkaline earth oxides to silica produce nonbridging oxygens in the network. Nonbridging oxygens do not bind the excitable electrons as tightly as bridging oxygens, which shifts the absorption edge to lower energies, i.e., longer wavelenths. These glasses are incapable of high transmission beyond 5 eV, or about 250 nm, and are not used for applications requiring good ultraviolet transmission.

Addition of elements which eliminate nonbridging oxygens favors good ultraviolet transmission. Alumina and/or boric oxide are frequently used in conjunction with alkali or alkaline earth oxides to counter the formation of nonbridging oxygens and preserve the ultraviolet transparency of silicate glasses. This approach can be taken to its logical conclusion by eliminating silica from the composition and producing alkali/alkaline-earth-aluminoborate glasses with good ultraviolet transparency.

In theory, fluoride glasses should provide better ultraviolet transmission than oxide glasses due to the larger bandgaps of fluorides. This assumption is true for single crystals, where fluorides such as CaF_2 are under development for transmission to higher energies than those obtainable with oxide crystals or glasses. In practice, the superiority of fluoride glasses for ultraviolet transmitting glasses has proven difficult to achieve. Vitreous BeF_2 and related glasses have superior ultraviolet transmission when compared to silicate glasses. Unfortunately, BeF_2 is very volatile and quite toxic, which restricts production of glasses based on BeF_2. Some fluoroaluminate and fluorophosphate glasses also have excellent ultraviolet transparency, but difficulties in producing these glasses in large sizes and of optical quality has limited their application.

Impurities are particularly important in production of ultraviolet transmitting glasses. The third-row transition metals, platinum, and cerium are all known to absorb strongly in the region from 200 to 300 nm when dissolved in glasses. Ferric iron has such a strong absorption band at ≈ 230 nm that concentrations of ferric ions must be kept in the low ppm range in glasses used for ultraviolet transmission. Since iron is a very common impurity in the sands used to produce silicate glasses, special care must be taken to minimize the Fe^{3+} content of ultraviolet-transmitting silicate glasses. Since ferrous iron has lower absorption in the ultraviolet, the effect of iron can be reduced by melting under reducing conditions. Platinum can enter melts from the melting unit and can be present as either ions or metallic particles. The ionic form of platinum absorbs ultraviolet light, while the metallic form scatters the same light.

Near-Infrared-Transmitting Glasses

Most glasses have good intrinsic optical transmission in the near-infrared. Absorption in this region is primarily due to impurities. Ferrous iron is especially detrimental to transmission in this region as a result of an extremely broad ligand field absorption band centered at about 1050 nm and extending into the visible and out to over 2000 nm. Reduction of absorption due to ferrous ions is obtained by careful control of raw materials to minimize the amount of iron oxide present and by melting under oxidizing conditions, which converts the ferrous ions to ferric ions. Conversion from ferrous to ferric ions increases the ultraviolet absorption of the glass. If good transmission in both the ultraviolet and near infrared regions is required, the iron content must be held to very low levels.

Although many rare earth ions also have absorption bands in this region, these elements are rarely found as impurities in sufficient levels to impair transmission in the near-infrared region for lenses and other common optical components. A more serious problem occurs for glasses used as optical fibers, where the greater optical path length magnifies the effect of impurities which may be undetectable in the spectra of samples only a few mm thick. The same can be said of absorptions of other ions which have very weak absorption bands in this region. Even higher order overtones/combination bands of infrared vibration absorption bands due to hydroxyl become important in optical fibers. While the hydroxyl absorption in infrared-transmitting glasses used in mm thicknesses is insignificant for concentrations less than 1 ppm, the hydroxyl concentration of optical fibers must be reduced to levels of a few ppb to reduce the effect of the overtone/combination bands to acceptable levels.

Infrared-Transmitting Glasses

Infrared transparency is limited by the intrinsic vibration, or multiphonon, edge of the glass and by the presence of impurities, primarily hydroxyl and carbon dioxide, which absorb in the infrared. The position of the infrared edge is determined by the force constant, which is proportional to the bond strength, and the masses of the ions. The best infrared transmission is found for materials with weak bonds and heavy ions. Infrared transmitting glasses are used in infrared spectrometers, lenses for pyrometers, infrared transparent domes for aircraft and missiles, and optical components for many systems using infrared lasers.

The fundamental absorptions of B_2O_3, SiO_2, P_2O_5, and GeO_2 lie in the region from 7.5 to 12 μm. These bands have such strong absorptions that the first overtone, at half the wavelength of the fundamental vibration, effectively determines the infrared edge for samples of more than a few hundred micrometers in thickness. The best infrared-transmitting oxide glasses do not contain significant amounts of B_2O_3, SiO_2, or P_2O_5. The lower fundamental vibrational frequency of GeO_2 allows production of some glasses of limited use for infrared transmission to about 5 μm. Comparable transmission is obtained for calcium aluminate glasses. Better transmission has been obtained for glasses combining the oxides of lead, bismuth, or cadmium with gallium oxide. These gallate glasses are termed heavy metal oxide, or HMO, glasses and transmit to ≈7 μm in mm thicknesses. The HMO glasses transmit into the visible, with a cutoff at 400 to 500 nm. Since these glasses are transparent to visible light, they offer advantages over many other infrared-transmitting glasses which are opaque in the visible.

Recently, heavy metal halide (HMH) glasses have been found to exist in a wide range of compositional systems. HMH glasses transmit much further into the infrared than the best oxide glasses, with cutoff wavelengths extending beyond 20 μm. These glasses are much more difficult to prepare than oxide glasses and are highly prone to crystallization, less durable in water, and mechanically weaker than the HMO glasses. Improvements in infrared transmission correlate with degradation in the other properties needed for most applications. Oxide impurities severely degrade the infrared transmission of these glasses. While much greater infrared cutoffs can be obtained in the laboratory, glasses currently produced commercially transmit to ≈8 μm.

Chalcogenide glasses contain either S, Se, or Te as the glassforming anion and are free of oxygen. Commercial compositions transmit to 16 μm, while laboratory samples transmitting beyond 20 μm can be made. These glasses have refractive indices in the infrared in the range of 2 to 3, very low glass transformation temperatures, which limit their temperature range of application, and are, with few exceptions, opaque in the visible. Toxicity is also a problem for Se and Te. Oxygen impurities must be kept below the 1 ppm level to avoid unacceptable absorption bands.

All infrared-transmitting glasses suffer from transmission interference in the region from 2.5 to 6 μm, due to hydroxyl in the glass. Since hydroxyl readily forms in any melt exposed to an atmosphere containing water vapor, great care must be used to reduce the hydroxyl content to acceptable levels. Glasses can be melted in sealed containers, under reactive atmospheres containing fluorine or chlorine, or under vacuum. Some glasses are prepared under dry conditions and then remelted under a vacuum to reduce the hydroxyl content. Similar care must be used to exclude CO_2 from HMH glasses, where a band at 4.25 μm has been assigned to the asymmetric stretching vibration of the dissolved molecules (Figure 2).



Figure 2 Infrared transmission spectra of several optical glasses showing the effect of glass composition on the infrared cutoff frequency.

Optical Isolators

Optical isolators based on the Faraday effect contain high concentrations of rare earths for paramagnetic devices and lead for diamagnetic devices. The highest concentrations of rare earth ions are obtained in aluminosilicate, aluminoborate, and aluminogermanate systems, where excellent quality glasses can be produced, while the best diamagnetic isolators are obtained using the lead bismuth gallate glasses.

See also

Optical Materials: Color Filter and Absorption Glasses. **Magneto-Optics:** Faraday Rotation, CARS, ODMR, ODSR, Optical Pumping.

Further Reading

Deeg EW (1986) Optical glasses. In: Boyd DC and MacDowell JF (eds) *Commericial Glasses*, pp. 1–34. Columbus, OH: The American Ceramic Society, Inc.

Fanderlik I (1983) *Optical Properties of Glass*. Amsterdam: Elsevier Scientific Publishing Company.

Hoffmann HJ (1998) Differential changes in the refractive index. In: Bach H and Neuroth N (eds) *The Properties of Optical Glass*, pp. 96–123. Heidelberg, Germany: Springer-Verlag.

Lentes FT (1998) Refractive index and dispersion. In: Bach H and Neuroth N (eds) *The Properties of Optical Glass*, pp. 19–58. Heidelberg, Germany: Springer-Verlag.

Liepmann MJ and Neuroth N (1998) Ultraviolet-transmitting glasses. In: Bach H and Neuroth N (eds) *The Properties of Optical Glass*, pp. 288–297. Heidelberg, Germany: Springer-Verlag.

Liepmann MJ and Neuroth N (1998) Infrared-transmitting glasses. In: Bach H and Neuroth N (eds) *The Properties of Optical Glass*, pp. 297–308. Heidelberg, Germany: Springer-Verlag.

Pfander HG (1996) *Schott Guide to Glass*. London: Chapman & Hall.

Rawson H (1980) *Properties and Applications of Glass*. Amsterdam: Elsevier Scientific Publishing Company.

Shelby J (1997) *Introduction to Glass Science and Technology*. Cambridge, UK: Royal Society of Chemistry.

Vogel W (1991) Optical properties of oxide glasses. In: Ullmann DR and Kreidl NJ (eds) *Optical Properties of Glass*, pp. 1–36. Westerville, OH: The American Ceramic Society, Inc.

Plastics

T Bauer, Wahl Optoparts GmbH, Triptis, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Injection molded precision plastic optics in high volumes were first produced during the 1960s. After the development of sophisticated measuring and manufacturing methods in the late 1960s, precise aspheric surfaces were as easy to make as spheric contours in plastics. Today plastic is a widely used low-cost option compared to glass with even more degrees of freedom for optical and component design. Polymer optical systems are used in sensor applications, visual systems, cameras, mobile phones, video-conferencing cameras, scanners, security systems, and so on.

The physical and chemical properties of plastic materials are very different from those of glass. Generally speaking, glass materials are harder, more durable, and more stable against temperature and humidity than plastics. The variety of optical glasses comprises hundreds of different materials. Compared with this the choice for plastic materials is limited only to about 10 different materials (and even less optical parameter variations). However, plastic optics offers other design freedoms that are not achievable with glass optics.

The manufacturing technologies for glass and plastic optics are totally different. Glass lenses are made by a grinding and polishing process whereas precision plastic lenses are usually made by injection molding, compression molding, or casting. Because of the material's characteristics and the manufacturing process, plastic optics have some unique advantages.

High production numbers at low costs

Injection molding is ideal for high-volume production with low-unit costs. Moderate raw material costs and multicavity mold designs (up to 32 cavities) allow large production volumes at a reasonable unit price. In spite of considerable tooling costs, these costs compared to glass design versions, can be relatively low.

Lightweight and hardiness

For a given volume glass is much heavier than plastic (by a factor of 2.3 to 4.9). However, plastic materials are relatively shatter and impact resistant. These features are important for head-mounted systems and other weight-sensitive applications (mobile phones, cameras, etc.).

Design potentials

Injection molding makes it economical to produce sophisticated optical shapes such as aspheres, diffractive optical elements, or even freeform surface structures. From the design point of view, the more sophisticated surface shapes reduce costs or obtain better performance (Fresnel structures, lens arrays, diffractive optical elements, etc.).

Optical systems and component assembly

For typical optical system designs optical components (mirrors, lenses, prisms, etc.) must be fixed in a mounting. With plastic optics it is possible to mold mounting elements, posts, or alignment notches integrally with the optical component. This can reduce part and assembly costs considerably.

Technologies adapted to plastic materials, such as ultrasonic and laser welding, gluing and integrated snap-in structures, allow fast and cost-efficient automated and manually operated assembling solutions.

History of Transparent Plastic Materials

A Material With No Use

In 1840, the Austrian chemist Redtenbacher (1810–1870), a student of Justus Liebig, discovered during a chemical experiment a malodorous transparent liquidity, the acrylic acid. It was an unwanted byproduct which was not further analyzed at that time. Nevertheless, that discovery can be considered to be the origin of today's plastic optics.

The development of plastics began in the US in 1860 as people were searching for an alternative for ivory in the production of billiard balls.

In 1869 John Wesley Hyatt developed from cellulose nitrate and camphor the first plastic material: celluloid. At first it was used for dental plates and afterwards for shirt collars and as a film base material. Despite its flammability and its lack of light resistance, it was a first economical success.

In the following decades the first synthetical plastics were developed, for example, the material with the trade name Bakelite in 1906.

Otto Röhm's Doctorate

The basis of acrylates was rediscovered in the records of Redtenbacher in 1900. From 1901 onwards, Prof. Pechmann (1850–1902) asked his postgraduates to do more research into the acrylic acid. The acrylic acid is an acetylene compound which can be extracted from carbon, petroleum, or lime.

In 1901 Otto Röhm, a student of Pechmann, wrote his dissertation 'About polymerisation products of the acrylic acid' – the basis of the methacrylate chemistry.

Hermann Staudinger (1881–1965), head of the Institute of Chemistry in Freiburg started theoretical investigations into the structure and natural characteristics of natural and synthetical polymers in 1920. He assumed that the molecules of plastic materials consist of numerous small molecule units. Experiments as proof of the theory led to a rapid development of scientific research and to significant breakthroughs in plastic chemistry. Staudinger won the Nobel Prize for Chemistry for his work in the field of macromolecules in 1953.

In 1928 methyl methacrylate was syntheticized for the first time and patented. Acrylic resin was used as a binder in multi-layer glass.

In the 1920s and 1930s a number of plastic materials were developed, including cellulose acetate CA (photo film, synthetic fiber); polyvinyl chloride PVC (pipes, coatings, isolations); urea formaldehyde resin (dishes, electrical equipment).

Polystyrene resins were commercially produced for the first time in 1937. Polytetrafluoroethene (PTFE) was produced for the first time in 1938, and distributed as 'Teflon' since 1943. Another key development was the synthesis of Nylon, the first technical high-performance plastic material.

Plexiglas Captures the World

The industrial production of methacrylic acid methyl ester began in 1934. With its polymerization to a hard and transparent plastic material, polymethylmethacrylic (PMMA or acrylic) was developed. It was patented in 1936 and caused, under the registered trade name Plexiglas®, a sensation at the world exhibition in Paris in 1936, almost 100 years after the discovery of acrylic acid.

Plates of Plexiglas were manufactured by means of effusion and polymerization between glass plates. At first it was used for watch glass, cockpits, and the construction of street lighting and luminous advertising. People already experimented with Plexiglas injection moulding in 1935. Arthur Kingston, the founder of Combined Optical Industries Limited (COIL) had invented and patented the first plastic lens in 1933.

The First Plastic Lenses in Cameras

The first camera, incorporating plastic optical parts, to be mass produced was the 'Purma Special' introduced by RF Hunter Ltd., in 1937, using 'Perspex' (another brand name for Acrylic), for the direct-vision viewfinder.

Due to the scarcity of natural raw materials at the beginning of World War II, the plastic industry became a source of outstanding substitute materials. This development had a lasting effect far into the post-war period. Results were mainly achieved with technical plastics, such as polycarbonates, acetates, and polyamides. Other plastics were developed as a substitute for metals as well as for hardhats, for high-temperature constructions, and for products which are resistant against acids and bases.

The German chemist Karl Ziegler discovered polyethylene (Polyethen, PE) in 1953 and the Italian chemist Giulio Natta Polypropylene (PP) in 1954.

The Eastman Kodak company is credited with giving birth to the modern-day plastic Fresnel lens. In 1946 Kodak developed a tooling and manufacturing process to mass produce plastic Fresnel lenses.

The circular Fresnel lenses made at that time had spiral grooves like music records.

It took another 10 years of improvement in injection molding techniques to the first plastic lens camera – the Kodak Brownie 44A from 1959.

Between 1953 and 1959 the Polycarbonate polymer was developed by Bayer and General Electrics. Currently acrylics and polycarbonates are still the most important materials for plastic optics.

But not only thermoplastic materials were developed over this time. In May 1940 research work resulted in the monomer allyl diglycol carbonate (ADC). In the following years more than 180 different compounds of this monomer were investigated and examined.

During World War II Columbia Southern Chemical Company (a subsidiary of Pittsburgh Plate Glass) began research into ways of obtaining nonthermoplastic materials. The project was given the name 'Columbia Resins'. The 39th tested (CR 39) turned out to be the most significant due to its unique properties and was used since 1947.

At first, solely the low-refractive CR 39 was available for organic eyeglasses. Only in the mid-1980s did the development begin in the field of high-refractive nonthermoplastic materials.

Properties of Plastics for Optics

As already mentioned, the choice for plastic optical material is limited only to about 10 different types of material. Optical properties (abbe value, refractive index, transparency) as well as mechanical, thermal, and humidity boundary conditions are decisive for the material choice. Different to glass during plastic processing (injection molding, casting, etc.) the process affects not only the geometry but also inner properties like refractive index, transparency, and birefringence.

Optical Properties

Fundamental optical properties are defined by optical transmission, refractive index, and dispersion. For plastic optics birefringence is an important parameter too.

Although the total number of plastic materials has increased in recent years, the range of refractive index and dispersion characteristic is limited to almost two major groups – crown-like materials such as Acrylic (PMMA), Polyolefin (COC, COP) and flint-like materials such as Polystyrene (PS), Polycarbonate (PC) and Styrol-Acrylnitril-Copolymer (SAN).

This strongly limited variety of plastic optical materials significantly restricts the optical design freedom (Figures 1 and 2).

Physical Properties

Important physical properties are weight, impact, and abrasion resistance – and thermal properties like temperature resistance and thermal expansion. Already, during system design, both mechanical and thermal properties have to be taken into consideration. The thermal expansion of optical plastics is approximately ten times higher than that of glass materials. In an optical system this effect has to be compensated for by optical design or mounting.

Typically most optical plastics can withstand temperatures up to 90°C. The maximum service temperature of Polycarbonate and Poly-Olefin materials reaches 120°C.

The specific gravity of plastic optical materials ranges from 1 to 1.3.

Polycarbonate has the highest impact resistance of all optical plastics and so is used for windshields and crash helmets. Acrylic has the best abrasion resistance (Table 1).

Common Materials

Thermoplastics

Thermoplastics are polymers with a linear molecule structure – with or without side chains – which can be deformed reversibly without any modification of their thermoplastic characterization by means of the impact of heat. Optical elements can be manufactured by injection molding or hot embossing.



Figure 1 Abbe diagram.



PMMA

PC

PS

SAN

COC

Figure 2 Transmission characteristics.

Typical optical thermoplastic polymers are listed below.

Acrylic or PMMA (Polymethyl methacrylate)

Acrylic is the most commonly used optical plastic. It is moderately priced, easy to mold, scratch resistant, and not very water absorptive. Its transparency is greater than that of most optical glasses throughout the visible range of the spectrum (organic glass). PMMA can replace glass in every application as long as the service temperature is less than 90°C and a low chemical resistance is required. Additives to acrylic (as well as to several other plastics) considerably improve its ultraviolet transmittance and stability.

PC (Polycarbonate)

Polycarbonates are linear polyesters of the carbonic acid which combine many characteristics of metal, glass, and plastics.

Polycarbonate is very similar to styrene in terms of optical properties such as transmission, refractive index, and dispersion. Polycarbonate, however, has a much broader operating temperature band of up to more than 120°C. It is used as the flint material for systems that have to withstand severe thermal conditions.

Another advantage is the high-impact resistance of polycarbonate. Safety glasses and systems requiring durability often consist of polycarbonate. Because of its high ductility polycarbonate is not easily machined.

Table 1 Material properties

Material	*Characteristics*	*Acrylic (PMMA)*	*Polystyrene (PS)*	*Polycarbonate (PC)*	*Styrol-Acrylnitril (SAN)*	*Cyclic Olefin Polymer (COP)*	*Cyclic Olefin Copolymer (COC)*	*Polyether-sulfone (PES)*	*Acrylnitril-Butadien-Styrolco-polymere (ABS)*	*CR39*	*Optical glass (B7)*
Optical	Spectral Passing Band (nm)	390–1600	400–1600	360–1600	395–1600	300–1600					
	Refractive index at 587 nm and 20 °C	1.4918	1.5905	1.5855	1.5674	1.5261		1.6600	1.5380	1.501	1.517
	Abbe value $(nD - 1)/(nF - nC)$	57.2 (53)	30.8	34 (29.9)	34.8	55.8	58	19.4		58	64.4
	Transmittance (%) thickness 3.2 mm	92	87–92	85–91	88	92	92	80	85		
	Haze% thickness 3.2 mm	1.3	2–3	1.7	1.5	1.5	1.5	1.5			
Physical	Specific Gravity (g/cm)	1.18	1.06	1.25	1.07	1.01	1.03	1.37	1.05	1.32	2.53
	Max. Service Temperature (°C)	92	82	124	95	123	130	200	90	130	400
	Linear Expansion Coefficient $(1/K)$	6.8×10^{-5}	8.0×10^{-5}	6.6×10^{-5}	7.0×10^{-5}	7.0×10^{-5}	7.0×10^{-5}	5.5×10^{-5}	8.5×10^{-5}		1.1×10^{-4}
	Abrasion Resistance (1–10)	10	4	2		6	6				
Environmental	$\mathrm{d}n/\mathrm{d}T\ (\times 10^{-5})$	-8.5	-12	$-11.8 \ldots -14.3$		-8	-10.1				
	Sensitivity to Humidity	high	low	low	medium	low		high	medium		
	Water Absorbtion (weight %) 23 °C, ISO 61	0.30	0.20	0.15	0.30	<0.01	<0.01	0.70	0.45		0
Manufacturability	Processability	excellent	good	poor	excellent	good					
	Birefrigence	low	high	high		low					
Chemical	Resitance to Alcohol	limited	good	limited				good			
Costs	approx. Material costs (EUR/kg)	3.3	2.5	4.4	4.4	27.1		21.0	3.5		25.0

PS (Polystyrene)

Polystyrene or Styrene is a low-cost material with excellent molding properties. Styrene has a higher index and a lower numerical dispersion value than other plastics. It is often used as the flint element in color-corrected plastic optical systems.

Compared with acrylic, styrene has lower transmission in the UV range of the spectrum. It has a lower resistance to UV than acrylic but is more easily scratched than acrylic.

Because its surface is less durable, styrene is more typically used in nonexposed areas of a lens system. A styrene lens, when paired with an appropriate acrylic lens, offers an effective achromatic solution.

SAN (Styrol-Acrylnitril-Copolymer)

SAN is a copolymer of certain fractions of Polystyrene and Acrylic (typically 70/30), which allows adjusting refractive indexes. It is a glassy polymer with a low tendency to stress cracks. SAN has slightly more chemical durability than PS and is a low-cost material with excellent molding properties.

ABS/MABS (Acryl-Butadien-Styrol-Copolymer)

ABS is developed from polymerization of styrene and acrylnitrit on polybutadien during the emulsion process. Process variations lead to different material characteristics. Compared to PS, the chemical resistance and temperature stability of ABS is considerably better. ABS has a natural color so it cannot be used for every optical application.

PES (Polyethersulfon)

PES shows a remarkable temperature stability, a low transmission against UV-light, a limited transmission with a natural yellow color, and cannot be used for every optical application. Because of its excellent temperature stability, PES is suitable for assembling, even on electronic motherboards by reflow soldering. This process causes temperature stress up to 220°C (Figure 3).



Figure 3 PES.

COP and COC (Cyclic olefin polymer and copolymer)

Cyclic olefin (co-)polymer provides a high-temperature alternative to acrylic. Its refractive index and transmittance are similar but the heat distortion temperature is about 30°C higher than for acrylic. It has a remarkably low water absorption value of less than 0.01% (compared with Polycarbonate 0.2% and PMMA 0.3%).

Cyclic Olefin Polymer (COP) is a family of amorphous plastic resins with low native stress birefringence properties. Zeonex is a resin developed by the Nippon Zeon Company – one grade, E48R, has a heat distortion temperature of about 122°C. Zeon Chemicals has another class of polymers called Zeonor, that can be provided as a lower-cost alternative to Zeonex.

Cyclic Olefin Copolymer (COC), with the trade name of Topas, is another high-temperature alternative to acrylic. Generally, it is a lower-cost alternative to COP. Particularly favorable is the high flowability (good injection moldability) of these thermoplastics.

PMP (Polymethylpenten – TPX®)

PMP has a structure similar to PE, except that only the methyl groups are replaced with isobutyl groups. The chemical resistance can be compared to PP, although it tends to stress crack under the impact of ketones or chlorinated solvents. The main advantages of PMP are its excellent transparency and its good mechanical characteristics, even at high service temperatures of up to 150°C.

PE-HD (high density polyethylene)

If polymerization is controlled catalytically, molecules with a low number of side chains will be received. Compared to PE-LD (low density), the molecules are quite compact with a higher stability and chemical resistance and service temperature can be up to 105°C. PE shows a bad transparency (milky appearance) in the visible spectral range. However, this material is permeable for infrared beams and so is frequently used for motion detectors.

Elastomere

Elastomeres are plastics with loose and networked molecules which are rubber elastic at a normal temperature. The most popular elastomeres are natural rubber and silicone rubber. These materials are optically used as flexible light guides.

Duromeres

Organic glass is a fully synthetic plastic material available in a vitreous state. It consists of macromolecular organic compounds which do not follow any principle of periodic arrangement and are hence amorphous.

Duromeres are plastics with spacial closely networked molecules which are very hard and refractory at a normal temperature. Impact of heat causes an irreversible induration. In most cases, duromers are used to produce plastic lenses made of organic glass. Once they have been thermally treated after production, their shape can no longer be changed.

The well-known plastic CR 39 is one of the organic materials used for plastic lenses.

CR39 plastic is made by polymerization of the allyl diglycol carbonate (ADC). It is a transparent, thermosetting resin which combines an exceptional range of qualities which are not available in other plastic transparent materials. The CR39 plastic is colorless and completely transparent to the visible light and almost completely opaque in the infrared and ultraviolet region of the spectrum. For these reasons, it is largely used for the production of sunglass lenses. They can be colored by surface dyeing or bulk tinting, have high abrasion resistance, and high-quality optical properties. Their weight is about half as much as glass, they keep their excellent optical properties despite long-term exposure to chemicals and resist heat distortion up to 100°C. These qualities, combined with the exceptional optical characteristics, make CR39 the best choice for applications where severe conditions of use exclude all other optical materials.

Additives and Colors

The characteristics of many plastics, particularly of thermoplastic materials, can be changed by adding so-called additives.

UV-filter materials are frequently added to improve the stability of materials in the sunlight. Sometimes nonstabilized plastics tend to yellow (transmittance decreases). Color filters can also be generated by coloring. Infrared coloring permits the production of optical elements which appear black in the visible spectral range. These materials are particularly used for sensors, optical scanners, or remote control front windows. Even characteristics, such as temperature stability, can be influenced by additives.

Manufacturing Methods

The manufacturing processes for glass and plastic optics are totally different. Glass lenses are made by a grinding and polishing process. By contrast, typical manufacturing methods for precise technical plastic optical parts are diamond turning of plastic blocks, injection, and compression molding of granulates. Other methods, such as casting, have their application in special fields like ophthalmics (eyeglasses). In any case, processing transparent plastic materials for optical purposes should take place in a clean environment.

Diamond Point Turning

Diamond point turning is an ultra-precision machining process carried out on special high-performance, ultra-precision diamond CNC-machining systems.

In combination with vibration isolation systems, digital signal processor-based machine control and integrated measuring systems with nanometer programming resolution manufacturing of optical surfaces is possible. This method can be expanded to full 3D-milling systems. With such an arrangement the generation of free-form surface profiles is possible.

Because of the long production time and the high machine costs, this technology is used for prototyping in plastics and nonferrous metals, mold inserts, and series production plastic parts – which cannot be manufactured by injection molding (because of size or precision demands).

Injection Molding

Injection molding produces several parts per shot (molding cycle) in single or multicavity tools. This production method is used for most of the plastic optic parts. Other fabrication techniques are used only when molding is inappropriate.

A plastic injection-molding machine consists of a fixed platen, a moving platen, a clamping unit, and an injection unit. Molding of optical parts requires special machine configurations and auxiliary equipment.

Compression Molding

Compression molding is used in the making of Fresnel lenses or other micro-optical structures. The material is pressed between heated platens with accurately defined temperature cycling during pressing. Mold inserts are formed by electroplated copies, replicated from master structures. These masters can be, for instance, diamond turned structures or diffraction gratings made by holographic methods.

The compression molding process allows realizing small structures with high aspect ratios and tight angular and positioning tolerances.

Manufacturing Process

Optical and System Design

On the one hand, optic design for plastic optics in principle uses the same mathematical algorithms as optic design for glass. On the other hand, designing plastic optics requires a profound understanding of the material properties and the manufacturing processes. Knowledge of production technologies, material characteristics, and assembling methods, together with design expertise, are needed to fully exhaust what precision plastic optics can be. Simply substituting the indices of refraction and re-optimizing, the design will not succeed. Expert design assistance is essential at this stage.

Designing plastic optics with modern design tools allows greater design freedom. The advantage of combining integral mounting structures with the optical surfaces to create mounting flanges, alignment, and snap features, provides the ability to automated assembly. Aspheric, cylindric, or toroidal surfaces are as easy to realize as spherical ones. Microstructures such as diffractive optical elements can be integrated too.

Prototyping

After designing a plastic optical system, lens prototypes can be made by diamond point turning in various plastic materials. The best surface finishes can be obtained with PMMA. Materials such as polycarbonate, pleximid, or Zeonex do not yield smooth surface finishes.

A major problem is the availability of semi-finished plastic blocks in various materials. For PMMA, a wide variety of bars or plates are available. For other materials or colored options, semi-finished items have to be made by injection molding. Because of the high manufacturing costs, diamond point turning is only recommended for making a limited number of prototypes to verify functionality of the optical design and to perform first tests.

In this stage optical systems are normally assembled from single elements. Housing parts often are made from aluminum. The resulting surface quality and system performance cannot be a validation of the manufacturability by injection molding. To get reliable knowledge about this, making a molded prototype from a single-cavity prototype mold is recommended.

The Injection Mold

A high-quality injection mold is obviously essential for precise plastic optic parts. The parts can never be better than the tool – but good tooling, however, does not guarantee good parts. A strong understanding of the whole manufacturing process is the key to producing precision plastic components.

Any injection mold consists of three main parts. The upper half, which is affixed to the injection-side platen, the lower mold half, which is affixed to the ejector-side platen, and the mold-ejection mechanism. Guide pins and taper locks ensure proper alignment of the mold halves.

Production volume and precision required from a tool influences the selection of mold materials and built-in maintenance features.

Single-cavity and multi-cavity molds from two to eight, 16, or even 32 cavitys are used for plastic optic parts.

Thermoplastic materials shrink during cooling in the mold. This geometric effect has to be compensated for in the injection mold. Exact shrink rates can be calculated and the tool can be modified.

For manufacturing optical plastic parts by injection molding, the optical surfaces (plano or aspherical shapes, diffractive, conical, lenticular, and cylindrical surfaces) are generated as separate inserts in the tool.

Aspheric inserts are manufactured by two steps. First a best-fit curve is generated on a stainless steel substrate. The substrate is then subjected to a nickel-plating process (electroless nickel) that deposits a thin layer of nickel (up to 500 μm). In the second step, single-point diamond turning produces the final aspheric or diffractive curve in the nickel. Because the hardness of a nickel-plated insert is less than that of a steel spherical insert, it will be more susceptible to scratch defects (Figure 4).

Pre-Production

A pre-production stage is recommended to check the manufacturing process. Typically this is done by using a single-cavity prototype mold. This mold can be used to find optimal molding conditions.

Optical and mechanical design can be verified with real molded components and design revision is possible to affordable conditions. Often the prototype molds is used to start limited production since production tooling may take much more time.

Series Production

For series production of high volumes, multicavity production molds are required. Depending on quality,



Figure 4 Injection mold.

volume, throughput, and cost, the production tool may have 2, 4, 8 or even up to 32 cavities. The production molds function for at least several hundred of thousands of injection cycles.

Coating and Component Assembly

Coating

Because of their limited temperature and UV resistance, plastic lenses must not be coated in an elevated temperature and radiation environment. During the deposition of thin films onto plastic, the coating chamber temperature is significantly lower than that for glass optics. This requires deposition techniques such as ion-assisted deposition to apply antireflective, conductive, mirror, and beamsplitter coatings.

Today, multi-layer dielectric coatings are routinely deposited on plastic components. Typical broadband antireflection coatings reduce reflection to about 0.5% per surface across the entire visible spectrum. Narrowband, multilayer antireflection coatings can achieve surface reflectances less than 0.2%. Multilayer dielectric coatings can be modified easily to scratch-resistant designs for front lenses and windows.

Several front and back surface reflector coatings are available for plastic substrates. Standard coating metals include aluminum, silver, and gold. Aluminum coatings provide surface reflectances greater than 88% across the visible spectrum and gold coatings greater than 95% for the near-infrared region.

Component Assembly

Many advantages of using plastic optics will come out in manufacturing components. The integration of optical, mechanical, and electronic elements allows building low-cost polymer optical components such as small camera lenses or scanner heads.

Plastic optical assemblies are usually carried out in a clean room environment by manual, semi-, or fully automated processes. The components have to be designed to ensure ease of assembly. Snap-on features, UV-cementing, heat-staking, and ultrasonic and laser welding, can also be employed with plastic materials.

Since most optical tolerances are additive, it is essential to establish quality check points in the manufacturing process to sort out nonconforming sub-assemblies.

Automatic in-line optical performance, monitoring such as MTF testing, can be implemented. SPC techniques should be used here to ensure the process is not drifting out of the controllable range.

Summary

For centuries, glass proved to be the material of choice for all optical applications. During the twentieth century, applications for glass elements and complex optical systems greatly expanded. Early uses of plastic molded elements included toy objectives, gauge windows, and watch crystals. Throughout the 1970s and up to the present day, high-grade polymers were developed specifically for optical applications. These advancements in materials, coupled with improved mold design have enabled plastic optics to replace glass optics in a wide and growing number of applications.

Plastic optic technology permanently expands their traditional limits and fields of application. On the one hand, plastic optic is still limited by material properties but, on the other hand, design and assembling freedoms allow new approaches.

See also

Diffraction: Fresnel Diffraction. **Geometrical Optics:** Lenses and Mirrors. **Optical Coatings:** Thin-Film Optical Coatings. **Optical Materials:** Color Filter and Absorption Glasses.

Further Reading

Corning Precision Lens Inc. (2000) *The Handbook of Plastic Optics*, 2nd edn. Cincinatti, OH: Corning Precision Lens Inc.

OPTICAL MATERIALS

Sculptured Thin Films

K Robbie, Queen's University, Kingston, ON, Canada

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical materials, like all materials, ultimately derive their physical properties from their chemical composition and physical form. Aluminum behaves differently from copper because of a chemical difference, while graphite behaves differently from diamond because of a crystallographic difference. For materials that are not infinite perfect crystals, an important contribution to their electromagnetic (optical) response comes from the morphological form of the material. Morphological form describes the physical structure of the material: a perfect crystal is one type of morphological structure, a porous fibrous bundle is another. An example of a morphological difference is that between snow and ice. Snow and ice are chemically identical, composed of solid water, but they exhibit different optical properties because of a difference in morphology. The polished glasses and large perfect crystals that comprise most optical components have morphologies more like ice than snow; their morphologies are dense and crystalline, with few and small disordered 'defects'. Unlike ice, snow is rich with morphological structure (see Figure 1) arising from the complex growth of each flake in the clouds, and the aggregate growth of snow on the ground. The morphology of snow scatters all colors of visible light, giving it an opaque white appearance, while ice is transparent and nearly colorless.

Sculptured thin films (STFs) are materials with controlled and designed morphology that exhibit a rich behavior unlike that of the constituent materials in bulk; they are the snow to most optical materials' ice. Unlike snow, sculptured thin film morphology is designed to scatter light in a controlled manner to produce a desired optical response. A sculptured thin film could be a coating applied to an optical element where the coating converts polarizations of light, circular or linear, but is composed entirely of an optically isotropic material (which doesn't usually affect the polarization of light). The film morphology is designed to create the desired optical properties. Sculptured thin films are also useful for magnetics, where an example of a sculptured thin film is the metal film coated onto plastic tape for video, audio, and data recording. The film is deposited under conditions that impose an elongated shape onto the magnetic domains, altering the magnetic properties. The morphological form of a sculptured thin film defines the way it responds in electromagnetic, chemical, and biological interaction, and there is hope that these unique materials will someday form the core of technologies that make the world a better place.

Structure in Thin Films

As chemical composition and morphology determine the electromagnetic response of materials, it would be wonderful to have a technique where we could build materials atom by atom, placing each exactly where we wished, and varying the element at will. With this level of control it would be possible to design and fabricate materials for almost any conceivable optical application. In some sense this is what is done now to fabricate lasers and optical switches. Microelectronic and micromachining processes have produced fantastic optical devices by controllably mixing materials (mostly semiconductors) and patterning designed structures. These techniques typically employ a repeated series of thin-film depositions and photolithographic patterning. Examples of thin-film coatings include antireflection coatings on eyeglasses, hard coatings on grocery store barcode scanners,



Figure 1 Photograph of snow accumulating at −20 °C. Photo courtesy of Chelsea Elliott.

ultraviolet blocking aluminum inside potato chip bags, and all integrated electronic circuits. Thin films are usually produced by vapor deposition in vacuum, and can be made with most elements and inorganic compounds (and a growing list of organics). Most thin films grow as uniform, dense, two-dimensional (2D) layers, and three-dimensional structure (3D) is produced by removing portions of the film with photolithography and etching. Photolithography is a process where ultraviolet light is projected through a mask and microscope system onto a photosensitive polymer layer atop the thin film. The light hardens areas of the polymer in the pattern of the mask, preventing them from dissolving in a chemical developer solution. Exposed portions of the thin film can then be etched away with chemical or other means. Repeating as desired, many steps can create complex 3D designed structures. Computer chips and other integrated circuits are semiconductor crystals covered with a layered structure of conductors (aluminum, copper, platinum) and insulators (metal and semiconductor oxides) patterned with thin film deposition and lithography. Semiconductor lasers and many other optical devices are made this way as well, usually employing compound semiconductors (GaAs, AlGaAs, GaAsP, InP, etc.). The micrometer-scale patterning made possible with thin-film deposition and etching techniques has produced a wealth of semiconductor optical devices.

Optical lithography, however, is limited in size scale to dimensions comparable to the wavelength of light used to expose the photomask. Modern UV lithography can pattern 100–200 nm structures. Visible light has wavelengths from 400 nm (violet) to 700 nm (red). Shrinking the dimensions of physical structures is a great benefit for optical devices as it allows light to be controlled coherently without strong random scattering. Structures with dimensions comparable to the wavelengths of light strongly scatter light waves; scratches on optical components or imperfections in materials with dimensions comparable to the wavelength are considered defects, and are usually deleterious. However, materials with morphology much smaller than the wavelength (nanometer structure, or nanostructure) are seen by propagating light as homogeneous, with polarization and dispersion effects characteristic of the underlying structure. Sculptured thin films are materials where complex nanostructure has been created by controlling growth parameters dynamically during deposition of a thin film. The simplest sculptured thin film might be one where the temperature is periodically varied during thin-film deposition (although this is a very simple example, lacking the anisotropy central to the sculptured thin-film concept). Variation in the growth process with temperature affects film density, producing a porosity variation (periodic inhomogeneity) as a function of film thickness. Varying porosity produces varying refractive index, and this film would be an optical interference filter. The largest limitation of sculptured thin films is that all attainable structures must be characteristic of the growth process. As all morphological control is accomplished by varying film growth parameters, structure that is not characteristic of thin film growth is not possible. Fortunately, thin film deposition and growth is sufficiently complex to allow the fabrication of a large range of useful structures. As with lithographic patterning, the structural control is two dimensional, but now the third dimension is constructed by continuing the deposition, not by repeating the deposition and lithography cycle. Complex structures can be produced on the scale of tens or hundreds of atoms (approximately tens of nanometers) with controlled 3D morphology. This reduction in size scale compared to lithographic patterning is a huge benefit. Materials can now be designed and created with subwavelength structure to coherently scatter light. Because the morphological structure (<100 nm) is much smaller than the wavelength of visible light (~500 nm), light traveling in a sculptured thin film sees a medium with averaged properties. The material can be designed to control refractive index through a wide range, and birefringence and circular polarization effects are controllable.

The morphological structure of thin films is a vast topic. Thin films are produced with a nonequilibrium growth process, somewhat like the growth of clouds, and the mechanics of the growth determine the structure, which is often very different from that seen in a bulk sample of the same substance. Crystal and morphological structure vary with deposition process conditions, and vary during deposition to record a history of growth much like the rings of a tree, or stratified rock. If chemical composition is varied during the deposition, that change will be reflected in layers in the film. If vapor energy or temperature is varied, variations in density and crystal structure will result. Thin film growth is an aggregation process (the film accumulates over time), and exhibits many of the features of similar processes, sometimes producing materials with structures similar to broccoli or clouds. This self-affine (self-similar) structure is observed over a large range of sizes under some film deposition conditions. Under other deposition conditions, crystallographic effects dominate growth and films become layers of faceted crystals. In sculptured thin films, these growth characteristics are controlled and exploited in a functional manner to design material properties. For example, magnetic video and audio tapes that have the symbol ME, abbreviating ‘metal evaporated’, employ a structured magnetic thin film that has superior magnetic response for recording. Similar effects are observed in optical materials, and sculptured thin films appear promising for improving existing optical devices or enabling new ones to be developed.

The most studied form of sculptured thin films is that produced by an asymmetric deposition process. In deposition by vacuum evaporation, a thin film is fabricated by evaporating some source material in vacuum, and condensing a vapor onto a substrate. Eyeglasses, mirrors, television phosphor screens, etc. are coated this way. In most thin films the vapor arrives straight down (perpendicular) to the plane of a flat substrate. The film structure reflects the symmetry of the vapor, and is typically composed of a dense layer with some defects or voids oriented perpendicular to the substrate surface. A thin film exhibiting this morphology is shown in the scanning electron microscope image of Figure 2. When vapor arrives asymmetrically onto a substrate, however, that asymmetry is reflected in the growth, producing structural asymmetry in the resulting film, and altered physical properties. A second scanning electron microscope image is shown in Figure 3, of a sculptured thin film where the orientation of the substrate relative to the vapor is changed twice, producing three layers with different morphologies. The thin uniform gray at the absolute bottom of the image is the edge of the silicon crystal substrate which has been cleaved to reveal an interior section of the film. The bottom and first film layer is inclined to the right, toward the vapor source for the duration of this first part of the deposition. The middle and second film layer has a twisted structure created by slowly rotating the substrate relative to the vapor, while keeping the tilt fixed. The top layer has a vertical structure created by rapidly rotating the substrate. The entire film was produced with the vapor arriving at an angle of 45°, measured from either the plane of the substrate or its perpendicular. Varying the tilt angle has a profound effect on the morphology of thin films. The void structure in these films records the geometry of the deposition. When we cleave a film we are able to observe a 2D slice of this rich morphology. At large tilt angles, glancing angle deposition (GLAD) produces films with highly porous and complex structure. At these angles, the film structure becomes isolated columns of material where growth variations are now reflected in variations in the shape of individual columns. At less oblique vapor angles, growth variations are reflected in the shape of networks of atomic-scale voids within a largely dense film. Indeed, for the best optical devices fabricated to date (with the serial bideposition technique described later) it is difficult to distinguish any variation in structure even using a high-resolution scanning electron microscope. The film deposition process can be designed to control the morphology of the growing film, and to vary the structure as a function of time and thickness. The morphology of these films determines their optical properties; optical birefringence, second harmonic generation, filter bandwidth and attenuation, etc. can all be controlled in sculptured thin films.



Figure 2 Micrograph of MgF_2 film deposited onto a 75 mm silicon wafer substrate, then fractured to reveal the edge shown.



Figure 3 Micrograph of SiO film deposited with a tilt angle of 45° with one layer of no rotation, one layer with one rotation, then one layer with rapid rotation.

Optical Thin Films

Light can be described as a traveling wave with electric and magnetic fields oscillating perpendicular to each other, and to the direction of propagation. If the orientation of the electric field remains constant as the wave propagates, the light is said to be linearly polarized. If the orientation of the electric field rotates through a circular path, the light is circularly polarized, and can be left or right handed. In the most general description, the electric field traces an ellipse during propagation and the light is said to be elliptically polarized. The experimental study of light polarization is called ellipsometry. When light propagates through vacuum or air, the state of polarization remains constant. When light propagates through some types of materials, however, crystallographic or morphological asymmetry (or more correctly, anisotropy) results in different propagation conditions for different polarizations. Upon passage through these materials, the orientation and form of the state of polarization is changed, for example from left circularly polarized (LCP) to right circularly polarized (RCP). When multiple layers of anisotropic materials are combined into an optical circuit, as in the sculptured thin film concept, highly controlled optical response characteristics can be created.

The discussion of the optical properties of thin films begins with definitions of isotropic, uniaxial, and biaxial materials. Isotropic materials have optical properties that are independent of the direction that the light propagates through them. Vacuum and air are isotropic, as is glass. Rotation of the optical material relative to the light propagation direction has no effect on how the light propagates, and the state of polarization remains constant. Uniaxial materials have properties that vary with direction, but with one preferred direction (or axis) where response is independent of rotation. Biaxial materials have properties that are even more dependent on propagation direction, and require two axes to describe their optical properties. For biaxial materials there is no propagation direction where the optical response is independent of rotation. The mineral calcite is an example of a uniaxial material where the refractive index, and therefore the speed of light propagation, varies with direction relative to the crystal structure. This is a direct consequence of the trigonal crystal structure of calcite, and is an example of linear birefringence. Birefringence is the effect caused by anisotropic materials whereby light of different polarizations, even within one ray of light, travel with different speeds. When light propagates in a birefringent material, the orientation of the light's electric field relative to the material's optical axis determines the speed of propagation. Light with different polarization (orientation) propagates at different speeds, and a beam's polarization state is altered on passage through the material. Thin films can be isotropic, uniaxial, or biaxial, depending on the conditions under which the film is deposited. Sculptured thin films are films fabricated in a manner that controllably enhances the anisotropic optical response to produce materials with designed optical properties based on control of their morphological structure. As in calcite where the anisotropic crystal structure yields a uniaxial optical response, anisotropic morphological structure in sculptured thin films yields biaxial optical response. A plan view scanning electron microscope image of an anisotropic thin film is shown in Figure 4. The film was deposited with two vapor sources with the substrate placed between and the vapor arriving from both sides at an angle of 70° from the substrate perpendicular. This film is similar to those produced with the serial bideposition technique, and is optically birefringent. Polarization filters and other optical components can be constructed by designing the morphological structure of the thin film.

As discussed above, when a thin film is deposited from a vapor arriving perpendicular to a flat substrate surface, a structure composed of small (tens of nanometers diameter) columns of film material grows, with the columns oriented perpendicular to the substrate (Figure 2). This film is optically uniaxial, with the preferred axis perpendicular to the substrate, and parallel to the vapor flux. Light propagating along this optical axis (perpendicular to the substrate) travels at one speed regardless of polarization, and independent of rotations of the substrate around this axis. Light propagating along other paths will travel at a speed that depends on the polarization of the light



Figure 4 Micrograph of MgF_2 film, viewed from above, deposited with simultaneous growth from two vapor sources.

(orientation of the electric field relative to the propagation direction). The effect is small, and arises from the morphological structure of the film. More pronounced optical response is produced when the vapor arrives onto the substrate at an angle from the substrate perpendicular, producing optically biaxial materials, and enabling exciting polarization and filtering effects. If a thin film of magnesium fluoride is deposited onto a polished piece of glass with the vapor arriving at 45° (relative to an axis perpendicular to the substrate), a slanted columnar film is produced. The morphology of the film is tightly packed columns of polycrystalline magnesium fluoride with diameters between 50 and 200 nanometers (nm), inclined toward the vapor source, and penetrated by a network of atomic-scale voids. Because of the anisotropic nature of the deposition, the voids are anisotropic, and the film is optically biaxial. If the substrate is then held at that tilt angle and is rotated during deposition, the anisotropy in the structure rotates with the deposition, and an important type of sculptured thin film is produced. The electromagnetic description of this type of film is a 'helicoidal bianisotropic medium', describing both the helix shape of the rotation of the structure and the local bianisotropic (biaxial) physical, and optical, structure. Films with helicoidal symmetry are ideally suited for studies involving circular polarizations of light, and many demonstrations of sculptured thin films have involved these films and circularly polarized light. Like many organic molecules and some mineral crystals, these film are chiral, existing in two mirror image forms, called enantiomers. A right-handed structure rotates clockwise traveling away from an observer; a left-handed structure rotates counterclockwise. Also like some organic molecules and mineral crystals, helicoidal films are optically active – they affect the polarization of light. The observed effect depends on the wavelength of light relative to the physical helicoidal structure. If these two lengths match, a strong resonance effect is observed where the light wave coherently scatters from the anisotropic structure. Filters to produce and convert circular polarized light have been constructed with sculptured thin films of this type.

The range of structural control over the morphology of thin optical films limits the ability to tailor optical response for desired applications. While optical systems must always be treated as a whole to determine response properties, the description of some basic elements is useful. A film deposited at normal incidence will be uniaxial with the axis perpendicular to the substrate. For light propagation along this axis (common for optical systems), the material exhibits no birefringence. This structure is often called an isotropic element even though the columnar structure is slightly optically anisotropic. A truly isotropic layer could be produced by ion bombardment or elevated temperature during deposition, either of which would have the effect of eliminating the columnar structure and reducing anisotropy in the film. The second elemental structure is a slanted columnar film that is commonly described as a matchstick morphology. It is produced by changing the vapor incidence away from the substrate normal, leading to an inclination of the column structure toward the vapor source, as described above. Further structures can include: helicoidal structure where the anisotropy rotates through the thickness of the film, and periodically bent nematic structure where the anisotropy tilts in an s-shaped pattern through the film (fabricated with a complex pattern of rotations and depositions). These four elementary microstructures are shown in Figure 5. Electrical, optical, and magnetic anisotropy can also be increased by depositing obliquely from two sides instead of one, and this technique (called serial bideposition) can be used to increase the anisotropy in sculptured thin films. At extremely oblique deposition angles, a regime called glancing angle



Figure 5 Elementary microstructures of sculptured thin films. From Lakhtakia A, Messier R, Brett MJ and Robbie K (1996) Sculptured thin films (STFs) for optical, chemical and biological applications. *Innovations in Materials Research* 1(2): 165–176, reproduced with permission.



Figure 6 Micrograph of MgF_2 film deposited with a tilt angle of 85° and substrate rotation clockwise for the first half and counterclockwise for the second.

deposition, a rapid increase in porosity with approximately constant column tilt results from a competition between deposition processes. Films deposited here are highly porous and strongly scatter light, limiting their usefulness for conventional optical devices, though some application has been seen in these highly porous films when impregnated with liquid crystals, and switched similarly to liquid crystal displays. An example of a highly porous optical filter with circular polarization effects is shown in Figure 6, where two layers of helicoidal porous films are deposited with different handedness and pitch. Sculptured thin films for most optical devices are deposited at less oblique angles to reduce porosity and therefore diffuse light scatter (haze) as well as sensitivity to humidity and other environmental changes.

Combining the concepts of film growth and optical response to morphology leads to the hoped-for vision of sculptured thin films: optical circuits in a chip. Combining the elementary microstructures described above, and employing powerful computer growth modeling and optical design programs, researchers are currently defining and producing sculptured thin films with increasingly complex optical response characteristics. There are substantial steps required to move from the fairly simple optical filters fabricated today to large-scale devices with complex functionality, but continuing success and increasing interest suggest that sculptured thin films could become a dominant optical technology in years to come.

Current Research

While thin films deposited at off-perpendicular incidence angles have been studied for many years, the last decade has produced significant new insights into these materials, leading to the concept of sculptured thin films. Understanding that morphologically rich materials can be used to produce new optical effects has yielded some impressive demonstrations. Research is also underway to explore these materials for chemical, magnetic, biological, and other applications.

Significant research has been conducted in the past few years to develop and extend the concepts of sculptured thin films. Optical studies, both theoretical and experimental, have revealed a range of remarkable properties including circular birefringence and Bragg reflection, liquid crystal alignment and switching, optical interconnection, and even suggestions of photonic bandgaps. Studies of optical sensing of gases and other materials is progressing, and simulation and modeling of the growth processes is ongoing. The following are two examples of optical materials that have been fabricated with sculptured thin-film techniques; one is a polarization discriminatory light-handedness inverter and the second is a liquid crystal switching cell that can be used to electrically modulate the transmission of polarized light. The handedness inverter converts left circularly polarized light to right circularly polarized within a spectral band, and blocks right circular polarized light. It is constructed by combining a layer with vertical columnar, or matchstick, morphology together with a layer with helicoidal morphology. In keeping with the sculptured thin film concept, the films are deposited sequentially during the same deposition, and optical properties are monitored during growth. The transmission spectrum for the devices is shown in Figure 7, where T_{RL} and T_{LR} are the light transmittances of right circularly polarized light when the incident is LCP, and of LCP when the incident is RCP, respectively. LCP light is almost entirely converted to RCP upon transmission, and RCP light is blocked. The bandwidth of the devices is about 50 nm, determined by matching of the circularly polarized light with the layer with helicoidal morphology.

When films are deposited with helicoidal morphology at glancing angles, i.e., glancing angle deposition, highly porous structures are produced where the columns stand alone and are individually shaped by the deposition process. Optical devices can be constructed by filling these porous films with gases or liquids, and there have been demonstrations of display-type switching with liquid crystals, and discussions of chemical sensing possibilities.



Figure 7 Transmission spectrum for visible light through a polarization-discriminatory light-handedness inverter. Adapted with permission from Hodgkinson IJ, Lakhtakia A and Wu Q-H (2000) Experimental realization of sculptured-thin-film polarization-discriminatory light-handedness inverters, *Optical Engineering*, **39**: 2831–2834.


glass with transparent conductor
GLAD thin film
adhesive
glass substrate
with transparent conductor
fill port
device area
bottom electrode
top electrode
sealed after filling with liquid crystal

Figure 8 Liquid crystal switching cell schematic with highly porous glancing angle deposited (GLAD) film between glass plates coated with transparent electrodes. Reproduced with permission from Sit JC, Broer DJ and Brett MJ (2000) Alignment and switching of nematic liquid crystals embedded in porous chiral thin films. *Liquid Crystals* 27: 387–391, www.tandf.co.uk/journals.



Figure 9 Transmission spectrum for visible light through a liquid crystal cell where the difference between right- and left-circularly polarized light transmission is eliminated with applied electric field. Adapted with permission from Sit JC, Broer DJ and Brett MJ (2000) Alignment and switching of nematic liquid crystals embedded in porous chiral thin films. *Liquid Crystals* 27: 387–391, www.tandf.co.uk/journals.

The device shown in Figure 8 is a liquid crystal switching cell where the space between the electrodes, usually composed solely of liquid crystalline material, is now filled with a highly porous helical structured film. The film structure is somewhat similar to helicoidal film produced for the handedness inverter discussed above, but glancing angle deposition has produced a film of individual formed columns instead of a more dense film with a helicoidal void morphology. When the porous portions of the film are filled with simple nematic liquid crystalline material, the orientation of the rod-like molecules is strongly influenced by the helical columns. An orientational phase occurs in the liquid crystals mirroring the helical structure of the columns in the film, and producing optical properties similar to chiral nematic liquid crystals. The discrimination of left and right circularly polarized light increases relative to the unfilled film. When an electric field is applied across the liquid crystal cell, dipole moments in the liquid crystal molecules force them to align with the field, and chiral optical properties vanish (see Figure 9). Used as an electro-optic filter for circularly polarized light, this cell can switch light transmission on and off. Initial work has not shown clear benefits of this system over conventional liquid crystal display technology, but control of liquid crystal orientation throughout the cell instead of just at the glass plates appears promising. Possibly more complex optical circuits, incorporating layers of porous films filled with liquid crystals, will be useful.

Theoretical and experimental study of sculptured thin films is in its infancy, and many exciting uses for these materials are expected in coming years. Continuing study of thin film growth dynamics will improve and expand the range of structures attainable. Theoretical investigations will aid in the design and understanding of the optical response.

List of Units and Nomenclature

Aluminum (Al)	white metal used in airplanes, mirrors, and microelectronic circuits

Anisotropic	having properties that vary with orientation (rotation)
Biaxial	having anisotropic optical response characteristics that require two axes to describe
Chiral	having a shape that exists in two mirror image forms, called enantiomers
Diamond	carbon crystallographically ordered in a face-centered-cubic lattice, and used in cutting tools and jewelry
Electromagnetic waves	traveling waves of energy that compose light, x-rays, radio-waves, etc.
Epitaxy	growth of a thin film that preserves the crystal structure of the underlying film or substrate
Etching	removing material with chemical or physical atomic scale process
Graphite	carbon crystallographically ordered in hexagonal sheets, and used in pencils and lubricants
Inhomogeneity	varying with translation (position)
Isotropic	having properties that are identical in all directions
Lithography	process where patterns are produced in a sensitive layer by irradiating the layer through a mask with the desired pattern
Magnesium fluoride	ceramic (MgF_2) that is used in thin-film or single-crystal form in many optical systems
Morphology	microstructural shape, or physical arrangement of atoms in a material
Nanometers (nm)	one billionth of a meter, 10^{-9} m
Nematic liquid crystal	optical material composed of rod-shaped organic molecules that usually exhibits uniaxial optical properties
Pitch	physical period for one full rotation of a helical structure
Polarization	orientation and phase of the electric and magnetic fields in a traveling electromagnetic wave; can be linear, circular, or generally, elliptical
Refractive index	the ratio of the speed of light in vacuum to the speed of light in a material
Substrate	object that a thin film is deposited onto, often polished glass or semiconductors
Ultraviolet (UV)	electromagnetic radiation (light) with wavelength shorter than visible light and longer than X-rays
Uniaxial	having optical response characteristics that are anisotropic, but are rotationally symmetric about one axis
Vacuum	absence of matter, typically produced inside sealed glass or steel chambers by removing air with pumps
Vapor flux	moving gas-like collection of material, emitted from a source such as an evaporator or effusion cell, that will condense to form a thin film

See also

Coherence: Overview. **Coherent Lightwave Systems**. **Fiber and Guided Wave Optics:** Overview. **Imaging:** Imaging Through Scattering Media. **Information processing:** All-optical Multiplexing/Demultiplexing; Coherent Analogue Optical Processors; Optical Neural Networks. **Instrumentation:** Ellipsometry. **Optical Processing Systems**. **Optical Coatings:** Anti-Counterfeiting and Decorative Coatings; Optical Black Surfaces; Thin-Film Optical Coatings. **Optical Materials:** Measurement of Optical Properties of Solids. **Polarization:** Introduction; Matrix Analysis. **Scattering:** Scattering from Surfaces and Thin Films; Scattering Theory. **Semiconductor Materials:** Band Structure Engineering. **Terahertz Technology:** Coherent Terahertz Sources.

Further Reading

Ball P (1997) *Made to Measure*. Princeton, NJ: Princeton University Press.

Barabasi A-L and Stanley HE (1982) *Fractal Concepts in Surface Growth*. Cambridge, UK: Cambridge University Press.

Collins PJ (1990) *Liquid Crystals*. Princeton, NJ: Princeton University Press.

de Gennes PG and Prost J (1993) *The Physics of Liquid Crystals*. Oxford, UK: Clarendon Press.

Hodgkinson IJ and Wu Q-H (1997) *Birefringent Thin Films and Polarizing Elements*. Singapore: World Scientific Publishing.

Hodgkinson IJ, Lakhtakia A and Wu Q-H (2000) Experimental realization of sculptured-thin-film polarization-discriminatory light-handedness inverters. *Optical Engineering* 39: 2831–2834.

Hodgkinson IJ, Wu Q-H, Thorn KE, *et al.* (2000) Spacerless circular-polarization spectral-hole fitters using chiral sculptured thin films: theory and experiment. *Optics Communications* 184: 57–66.

Lakhtakia A, Messier R, Brett MJ and Robbie K (1996) Sculptured thin films (STFs) for optical, chemical and biological applications. *Innovations in Materials Research* 2: 165–176.

Liu F, Umlor MT, Shen L, *et al.* (1999) The growth of nanoscale structured iron films by glancing angle deposition. *Journal of Applied Physics* 85: 5486–5488.

Messier R, Venugopal VC and Sunal PD (2000) Origin and evolution of sculptured thin films. *Journal of Vacuum Science and Technology* 18: 1538–1545.

Ohring M (1992) *The Materials Science of Thin Films*. New York: Academic Press.

Robbie K, Brett MJ and Lakhtakia A (1996) Chiral sculptured thin films. *Nature* 384: 616.

Singh ON and Lakhtakia A (eds) (2000) *Electromagnetic Fields in Unconventional Materials and Structures*. New York: John Wiley.

Sit JC, Broer DJ and Brett MJ (2000) Alignment and switching of nematic liquid crystals embedded in porous chiral thin films. *Liquid Crystals* 27: 387–391.

Toader O and John S (2001) Proposed square spiral microfabrication architecture for large three-dimensional photonic band gap crystals. *Science* 292: 1133–1135.

Wang L and Clancy P (2001) Kinetic Monte Carlo simulation of the growth of polycrystalline Cu films. *Surface Science* 473: 25–38.

Smart Optical Materials

P M Martin, Pacific Northwest National Laboratory, Richland, WA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Smart optical materials are those materials whose optical properties (transmittance, reflectance, absorptance, emittance, fluorescence) can be controlled by external stimuli; either by an applied electric field or voltage, mechanical stress, incident light or electromagnetic field intensity, temperature variation, or time duration. This includes electrochromic, photochromic, thermochromic, nonlinear optical, light emitting, fluorescing, emissive, and piezochromic materials. These materials can be in various states, such as solids, gels, composites, and mesophases. Electrochromic and photochromic materials, however, are used most extensively.

The mechanism for adaptive control of light must be reversible, have a well-defined response time, and have an activation threshold, otherwise, the material is considered passive. The primary mechanisms that can cause variations in optical properties are crystal phase transitions, nonlinear effects in the polarizability, optical energy band transitions and band bending, compositional changes, defect and color center formation, and lattice strain. Crystal phase transitions change the bonding morphology of a material, which affects the energy bandgap. Most optical materials have several possible crystalline phases, depending on temperature. The optical properties of the anatase and rutile phases of TiO_2, for example, are very different, and result from different energy bandstructures (recall that the energy bandstructure depends on lattice spacing and crystalline plane orientation). The crystalline phase of several thermochromic materials changes from the martensite structure to the austenite structure with change in temperature, and an associated change in optical properties. Compositional changes are caused by chemical or physical reactions in the material, such as a metal ion bonding to an atom in the lattice, or loss of an atom in the lattice. The reaction can be caused by an energetic photon or ion driven by an electric field; electrochromic materials fit into this category. If their energy is high enough, incident photons can create defect states in the bandgap of materials, which in turn form color centers that absorb light. Modulated electric and electromagnetic fields can cause changes in the linear and nonlinear polarizability of the atoms in a lattice. Nonlinear optical and piezochromic effects are based on this mechanism.

Photochromic Glass

Photochromic glass is one of the most widely used smart optical materials, and definitely the most widely marketed. It has been around for over 30 years with hundreds of associated patents. The transmission of photochromic materials adjusts to the light level of their environment, but these materials give no output information for data processing or communications. They do, however, require no other external control mechanism other than the intensity of light (characteristics of a true smart material). Photochromic materials darken reversibly when exposed to sunlight or a specific optical (UV–LWIR) wavelength band. Absorption in specific narrow or broad wavelength bands is due to the formation of color centers, or point defect states in the lattice. The kinetics of darkening has been described by a two-color center model with two rate constants. Energy (usually in the ultraviolet wavelength range) of the incident photons, ionizes atoms in the glass, thus forming 'F' centers. F centers are highly absorptive and the absorption generally occurs in a broad wavelength band. The earliest photochromic glass developed utilized a dispersed and sensitized colloidal silver halide as the darkening agent. Copper oxide was a typical sensitizer and AgCl is also a fairly common impurity used in PC glass. This material darkens by the equation

$$\mathrm{Ag}^{\mathrm{I}} + \mathrm{Cu}^{\mathrm{I}} \rightleftharpoons \mathrm{Ag}^{0} + \mathrm{Cu}^{\mathrm{II}} \qquad [1]$$

This type of reaction is fairly typical of these materials. The defect state is created in the silver and copper, creating optical absorption. Photochromic glass can darken down to 22% transmittance in sunlight and become nearly clear indoors, transmitting 85% of visible light. Figure 1 shows the transmittance of the darkened and normal states. Temperature, however, does have an effect on the lenses. The glass will not darken completely at temperatures above 32 °C, and at cold temperatures the lens will get extremely dark in a shorter period of time. Recently, $\mathrm{BaO{-}R_2O_3{-}SiO_2}$ ($\mathrm{R = Al, B, La}$) nanoparticles have been introduced to enhance photochromicity.

Thermochromic Materials

Thermochromic materials darken and lose transmittance when heated above a critical temperature. They can be as sophisticated as a multilayer thin film optical interference coating or as mundane as a cereal bowl that changes color when heated.

Thermochromic products are used to darken windows of automobiles, for example, when the internal temperature gets above a specific value. The conductivity of these materials also decreases with darkening in many cases because additional electrons are excited into the conduction band due to the increased number of defect states in the bandgap. The most common inorganic thermochromic thin film materials are transition metal oxides, and among these, the vanadium oxide family (V_2O_5, VO_2) shows the best performance. Figure 2 shows the transmittance of a VO_2 thin film before and after heating. Here T_t is the transition temperature. When heated above T_t, the film darkens. Stoichiometric VO_2 darkens at a temperature near $T_t = 68\,°\mathrm{C}$ due to a semiconductor to metal transition. The resistivity of VO_2 decreases by three orders of magnitude and the emittance can be increased up to 90% at the transition temperature. This material has promising applications for thermal control of space structures, where surfaces are exposed to intense solar radiation and periods of darkness at very low temperatures. The transition temperature can be engineered (increased or decreased) by doping with metals such as W and Ta.

Loss of transmission can be achieved by absorption or increased reflectance. Reflectance increases with heating are observed in substoichiometric WO_3 films and absorptance increases in stoichiometric films. The reflectance increase is attributed to a decrease in W/O ratio and an associated increase in the refractive index (n) and extinction coefficient (k).



Figure 1 Transmittance of photochromic glass in darkened and normal states. (Reproduced with permission from Jorgenson GV and Lee JC (1985) Optical Materials for Energy Efficiency and Solar Energy Conversion IV, *SPIE Proceedings*, vol. 562. Bellingham, CA: SPIE.)



Figure 2 Change in transmittance of a thermochromic VO_2 film with heating. $T < T_t$ for normal transmission and $T > T_t$ when heated. (Reproduced with permission from Jorgenson GV and Lee JC (1985) Optical Materials for Energy Efficiency and Solar Energy Conversion IV, *SPIE Proceedings*, vol. 562. Bellingham, CA: SPIE.)

Electrochromic Materials

Electrochromic materials, also called switchable materials, are usually used in the form of thin film devices. Electrochromic windows, or smart windows, have finally reached maturity and promise to be the next major advance in energy-efficient window technology. These devices are used in architectural glazings, automotive mirrors, rear view mirrors, sunroofs, sunglasses, and other high-end applications. Electrochromic devices are well suited for both solar and thermal control. A window can be controllably darkened during periods of bright sunlight and switched back to transparency during the evening or during cloudy periods. Windows with multilayer thin film electrochromic coatings change color and darken with an applied voltage, and bleach with a reverse bias. The magnitude of the applied voltage determines the degree of coloring and bleaching. In addition to a change in visible transmission, the NIR transmission and reflectance, and the associated thermal properties, can also be controlled. The major advantages of electrochromic devices are: (1) power is used only during switching; (2) switching voltages are small (1–5 V); (3) reflectance and transmittance is always specular; (4) gray scale variations are possible; (5) polarization is minimal (reduces birefringence and distortion); and (6) the memory is adjustable in many cases.

The electrochromic effect occurs in inorganic compounds by dual injection (cathodic) or ejection (anodic) of ions (M) and electrons (e^-). A typical reaction for a cathodic coloring material is

$$\mathrm{WO_3(colorless)} + yM^+ + ye^- \rightleftharpoons My\mathrm{WO_3(blue)} \quad [2]$$

where M is H^+, Li^+, Na^+, Ag^+, etc.

A typical anodic reaction is

$$\mathrm{Ir(OH)}_x\mathrm{(colorless)} \rightleftharpoons \mathrm{IrO}_x\mathrm{(black)} + XH^+ + xe^- \quad [3]$$

Movement to the right creates color or darkening, and movement to the left results in bleaching. Figure 3 shows the spectral data for the switching of a tungsten oxide film over the solar spectrum; the spectral response of the coating in the bleached and colored (or 'switched') states, and Figure 4 shows the bleached and darkened states of an actual electrochromic window.

Figure 5 shows the design of a simple electrochromic coating. The basic electrochromic coating consists of a transparent top electrode (usually indium tin oxide – ITO), which also injects electrons into the electrochromic layer beneath. By far the most studied and most promising electrochromic material is tungsten oxide (WO_3), which can have either an amorphous or crystalline microstructure. WO_3 has a high coloration efficiency and capacity. Other inorganic materials that are presently being developed for solar control applications are various forms of WO_3, NiO, $WMoO_3$, MoO_3, and IrO_x. Many of these are doped with a conduction ion such as Li^+ or H^+. The ion conductor layer is used to transport protons (H^+), which are supplied by the ion storage or counter-electrode layer, into the electrochromic material. The most promising ion conductors are certain immobile solvent polymer systems, ionic glasses, and open-channel metal oxide structures such as perovskites. Oxides of Ta and Nb also show promise. The bottom layer is another transparent conducting coating. It is possible to inject both electrons and protons into the electrochromic material, thereby inducing a strong absorption band in a given region, e.g., the visible spectrum, that results in a color change. In an



Figure 3 Spectral switching of an electrochromic window for darkened (−2V bias) and bleached (2V bias) states. (Reproduced from Kre J, Topic M, Smole F, *et al.* (2002) *Solar Energy Materials and Solar Cells* 71: 387–395, with permission from Elsevier.)



Figure 4 Bleached (left) and darkened (right) states of an electrochromic window.



Figure 5 Basic layer design of electrochromic coating for use on a window.

Table 1 Electrochromic device structures

Electrochromic layer	*Ion conductor or electrolyte*	*Ion storage*
a-Li_xWO_3	$LiClO_4$ + PC	Redox Cple/NiO
a-WO_3	Ta_2O_5	$Ir_xSn_yO_2$:F
a-Li_xWO_3	$LiClO_4$ + PC	Prussian blue
a-H_xWO_3	Polymer	Polyaniline
a-H_xWO_3	SiO_2/metal	WO_3
Viologen	PMMA + organic	none
a-WO_3	Ta_2O_5	a-IrO_2
c-WO_3	Li–B–SiO Glass	IC/$Li_xV_2O_5$
a-WO_3	Li–PEO	CeO_x
a-Li_xWO_3	PPG–$LiClO_4$–MMA	$Li_yV_2O_5$
a-H_xWO_3	Ta_2O_5	NiO
a-WO_3	Li–PEO	NiO
NiO	a-PEO copolymer	Nb_2O_5, WO_3:Mo
a-WO_3	a-PEO copolymer	Polymer
Polyaniline	HCl	–

a, amorphous; c, crystalline; IC, ion conductor; MMA, methyl methacrylate; PC, polycarbonate; PEO, poly (ethylene oxide); PMMA, poly (methyl methacrylate); PPG, poly (propylene glycol).

electrochromic device, an externally applied electric field is used to control the injection process (voltage is applied across the two transparent electrodes). The coloration remains for some time, even after the external field is removed. The system returns to the initial state upon reversing the polarity of the external field. It is interesting to note that electrochromic windows being developed by NREL now employ solar cells to facilitate optical switching.

There are two major categories of electrochromic materials: transition metal oxides (including intercalated compounds) and organic compounds (including polymers). Table 1 shows a few of the most common electrochromic materials. Organic electrochromic materials are based on the viologens, anthraquinones, diphthalocyanines, and tetrathiafulvalenues. With organic compounds, coloration is achieved by an oxidation–reduction reaction, which may be coupled to a chemical reaction. The viologens are the most studied of the organic electrochromics. Originally, organic electrochromics tended to suffer from problems with secondary reactions during switching, but recently more stable organic systems have been developed. However, their reliability in harsh environments is questionable, and protective encapsulation may be required.

Electrochromic nickel oxide (NiO) is also being developed. NiO has been combined with manganese oxide, cobalt oxide, and niobium oxide in all alkaline devices.

Nonlinear Optical Materials

Nonlinear optical materials have evolved slowly over the past 20 years. At relatively low light intensities, the properties of most optical materials are independent of intensity of illumination. There is no interaction between the light waves in the medium. However, if the intensity of illumination gets high enough, nonlinear optical effects can occur and the optical properties become intensity dependent. When an electromagnetic field oscillating at optical frequencies ($\sim10^{13}$–$\sim10^{17}$ Hz) is applied to the lattice of a dielectric material, the electrical charges in the lattice become polarized and form electric dipoles. The positive ion cores do not move significantly, but the electrons are displaced in a harmonic motion. The polarization $\mathbf{P}$ is defined as $-Ne\mathbf{X}$, where N is the number of electric dipoles, $\mathbf{X}$ is the displacement of the electrons, and e is the charge on an electron. Here $\mathbf{X}$ is a complex number. Now, $\mathbf{P}$ is related to the electric field E by $\mathbf{P} = \varepsilon_0 \chi E$, where χ is the susceptibility and ε_0 is the permitivity of free space.

The linear dielectric constant is $\mathrm{Re}(1 + \mathbf{X})^{1/2}$, which is just the index of refraction. The imaginary part causes optical absorption.

When the intensity of illumination is high, the elastic limit of the electron's displacement is exceeded and the harmonic restoring force becomes nonlinear in $\mathbf{X}$, which adds quadratic and higher order terms to the expression for $\mathbf{X}$ and $\mathbf{P}$. In addition to the fundamental resonance, the dipoles now also oscillate at twice and thrice their fundamental resonant frequency (second and third harmonics). The polarization then is also nonlinear in displacement and can be expressed by the well-known relation

$$\mathrm{P} = \varepsilon_0(\chi^{(1)}\mathrm{E} + \chi^{(2)}\mathrm{E}^2 + \chi^{(3)}\mathrm{E}^3 + \ldots) \qquad [4]$$

where $\chi^{(2)}$ and $\chi^{(3)}$... are called the nonlinear susceptibilities. The second-order polarization $P^{(2)}$ causes optical mixing phenomena, involving sums and difference frequencies. When mixed with a DC field, the refractive index of the $\chi^{(2)}$ material can be controllably varied by varying the DC field. This is the well-known Pockels effect and is used in optical modulators. Figure 6 shows one method that is used to modulate the refractive index by the photorefractive effect. Here two laser beams (A_1 and A_2) are mixed in the $\chi^{(2)}$ material with the resulting intensity $I = I_o(1 + m\cos(kx))$. The material is polarized in phase with the mixed beams $\rho = \rho_o(1 + m\cos(kx))$, which results in a modulated electric field E_{sc}. The refractive index (Δn in the figure) is modulated in phase with the mixing signal. The $\chi^{(2)}$ materials are also used for frequency doubling.

Barium titanate ($BaTiO_3$), lithium niobate ($LiNbO_3$), KH_2PO_3 (KDP), lithium tantalite ($LiTaO_3$) and potassium niobate ($KNbO_3$) are $\chi^{(2)}$ optical switching and frequency doubling materials that have been studied for decades. Note that because they can be easily polarized, these are also excellent piezoelectric/ferroelectric smart materials.



Figure 6 Modulation of the refractive index of a nonlinear optical material with incident laser modulation. From top to bottom: modulated laser intensity I, density ρ, electric field E_{sc}, refractive index Δn, and phase angle $\pi/2$. (Reproduced with permission from Bass M (ed.) (1995) *Handbook of Optics II*. New York: McGraw-Hill.)



Figure 7 Optical switching behavior of a Fabry–Perot filter. I_I and I_T are the incident and transmitted intensities respectively. (Reproduced with permission from Butcher PN and Cotter D (1990) *The Elements of Nonlinear Optics*. Cambridge, UK: Cambridge University Press.)

The $\chi^{(3)}$ effects are sought after for applications such as laser eye protection, optical sensor protection, optical switching, optical limiting, and signal processing. In this case the refractive index (real and imaginary) depends on the intensity of the incident radiation. Figure 7 shows how this nonlinear effect is used in an optical switching device. It is all based on the change in the optical path length of a Fabry–Perot filter. At normal intensities, the refractive index of the spacer layer is n_0 and the filter is in the 'off' state. The refractive index becomes $n_0 + n_2 I$ and the optical thickness (nt) of the spacer layer changes at high illumination intensities, which in turn shifts the resonant wavelength (frequency) of the Fabry–Perot filter and creates the optical switch ('on' state).

There are a large number of $\chi^{(3)}$ and $\chi^{(2)}$ organic materials, including dyes, dimethylamino nitrostilbene, methyl nitroanaline, poly-BCMU, polydiacetylenes, and urea. Because they are essentially chains, many organic molecules can be easily polarized and possess higher order susceptibilities. The polarizability of organic materials is often enhanced by the mobility of delocalized π electrons in C–C bonds in aromatic rings. Hybrid nonlinear materials have even been formed by combining organic and inorganic components such as metallophthalocyanines which display very strong excited state absorptions. Most of these materials are deposited by spin casting.

Emissive Materials

Two of the newest applications of smart optical materials are emissive displays and electronic ink. This encompasses light-emitting polymers and small molecules, light-emitting diodes, and quantum cascade lasers. Organic light-emitting device (OLED) technology is leading the revolution in the flat panel display industry. This device was first invented by Tang and Van Slike and first reported in *Applied Physics Letters* in 1987. Figure 8a shows the layer structure of the OLED and Figure 8b shows a blue OLED pixel. The device is deposited onto an indium tin oxide (ITO)-coated glass or plastic substrate, with the ITO acting as the anode. The active layers can be either light-emitting polymers or small molecules. About 500 Å of a hole transport material (hole transport layer, HTL), here a tertiary amine, is deposited over the ITO. An aluminum trisquinalate (Alq), which transports electrons (electron transport layer, ETL) is deposited next. The device is topped off with



Figure 8 (a) Layer diagram of an OLED. (b) Blue OLED pixel.



Figure 9 Simple energy level diagram of an OLED showing the relationship between the ETL and LUMO, and HTL and HOMO.

a low work function cathode, usually Ag:Mg or Ca. The entire device thickness is about 1000 Å. Even a dust particle can ruin the operation of an OLED by creating inactive regions or shorting out the electrodes.

The OLED emits light in a blue, green, or red wavelength band when activated by an electric current, i.e., electron and hole injection. The device functions by injecting holes from the ITO into the HTL. As shown in the simplified energy band diagram (Figure 9) for an OLED, the hole moves into the HOMO (highest occupied molecular orbital), which loosely corresponds to the valence band of a semiconductor. Electrons are injected from the cathode into the ETL, where it is transported into the LUMO (lowest unoccupied molecular orbital), which loosely corresponds to the conduction band of a semiconductor. When a voltage is applied between the anode and cathode, an electron flows and the holes and electrons combine in the ALQ layer and form excitons. Light is emitted when the excitons decay back a lower energy state. The color of the emitted light (green, red, or blue) can be changed by changing the HTL and ETL material composition. Light is emitted by fluorescence processes, from both singlet and triplet states if the material chemistry is correct, which results in 100% internal quantum efficiency. Twenty percent external quantum efficiency results from using all available exciton states. Photons can be lost through absorption in the layers, scattering, reflection between layers, and waveguide modes. These factors must be minimized to maximize the external quantum efficiency.

OLED video displays now have outputs near 100 cd/m (20 lm/W), which is about twice the normal video brightness. Red, green, and blue OLEDs now emit with very high efficiencies. For comparison, a 100 W light bulb emits at 17 lm/W and the best fluorescent light emits at 80 lm/W. Today, OLEDs are already sitting at intensities of 50–60 lm/W, and could easily push 150 lm/W in the near future. Another advantage of OLED displays is their wide viewing angle, up to 160°.

There are several types of OLED display configurations. Figure 10 shows a passive matrix display geometry and placement of the OLED layers. Here the OLED is sandwiched between crossed cathode and anode contacts. By injecting current between sets of crossed anode and cathode rows, the OLED will light up, each contact point forming a pixel. Displays can typically have as many as 3 million pixels. OLED displays seem brighter and livelier to the eye because the colors are additive, rather than subtractive as with LCD displays. For a full-color passive matrix display green, red, and blue pixels must be located very close together. Sony has developed an active matrix 13-inch diagonal display with 800 × 600 pixels (∼150 000 functioning OLEDs).



Figure 10 Geometry of a passive matrix display.

Among the more promising pixel geometries is the SOLED, the stacked OLED, where, red, green, and blue pixels are stacked on top of each other. It is mandatory that the pixels and the electrical contacts be transparent for this design, or light will not be transmitted through each layer. Very thin Mg contacts are used with a top sputtered ITO cathode. The emitted color is simply changed by applying current across the pixels, with white being obtained when all pixels are activated.

The future of OLED displays is plastics, or the flexible OLED (FOLED). Plastic substrates are lightweight, low cost, and rugged. However, they have an inherent problem of being very permeable to oxygen and water vapor, both of which severely degrade performance of the OLED by reacting with the anode layer. For displays to be practical, they must have lifetimes in excess of 10 000 hr and preferably 20 000 hr. Barrier coatings are now being developed for plastics to prevent oxygen and water ingress and extend the life of the OLED to this goal.

Electronic ink is a display medium that can be formatted using a passive matrix. It consists of millions of tiny negatively charged microcapsules, about 100 microns in diameter, floating inside a liquid medium. Each microcapsule is filled with hundreds of pigmented chips. One half of each microcapsule is white and the other half is dyed blue. When an electric charge is applied to the microcapsules, the chips are drawn either to the bottom or top of the microsphere. The viewer sees dark areas when they are drawn to the top. In another version being developed by Xerox Corp., half the chip is white and half the chip is dark. When an electric charge is placed on the chip, the dark side is oriented up and the white side down, creating dark regions where charge is placed. This can be easily erased and reformatted into text, symbols, signs, and pictures.

Future smart optical materials will simulate biological systems such as an insect's eye and will employ quantum structures to achieve optical switching, emission, and control of optical properties.

List of Units and Nomenclature

Absorptance (A)	The amount of light absorbed by an optical element divided by the incident intensity. $A = 1 - T - R$.
Active matrix display	A display geometry in which the voltage to the pixel is controlled individually by a transistor.
Candela (cd)	Formerly known as a candle. The luminous intensity equal to 1/60 of the luminous intensity per square meter of a black body radiator operating at the temperature of freezing platinum.
Exciton	An electron–hole pair, usually generated by a photon.
FOLED	Organic light emitting device on a flexible plastic substrate.
LCD	Liquid crystal diode.
Lumen (lm)	A unit of luminous flux equal to the luminous flux emitted in a solid angle of one steradian for a point source having an intensity of one candela.
NIR	The near-infrared spectral region, consisting of wavelengths between 700 and 2500 nm.
Passive matrix display	A display geometry consisting of a grid of horizontal and vertical wires. At the intersection of each grid is an active element (LCD or OLED) which constitutes a single pixel, either letting light through or blocking it.
Piezoelectric	Capable of generating a voltage when a force or stress is applied.
Polarization (coulomb/m^3)	A vector quantity equal to the electric dipole moment per unit volume.
Quantum efficiency	The number of electrons, holes, or electron–hole pairs generated per incident photon at a given optical wavelength.
Reflectance (R)	The intensity of light reflected from an optical element divided by the incident intensity. $R = 1 - T - A$.
Susceptibility (no units)	A scalar quantity equal to the ratio of the electric polarization of a material to the electric field strength.
Transmission (T)	The intensity of light transmitted through an optical element divided by the incident intensity. Note that transmission + reflection + absorption = 1 $(T + R + A = 1)$.
UV	The ultraviolet spectral region consisting of wavelengths between 200 and 400 nm.
Visible	The spectral region consisting of wavelengths between 400 and 700 nm.
Wavelength (μm or nm)	The length of one oscillation of a light wave.

See also

Materials for Nonlinear Optics: Organic Nonlinear Materials. **Optical Coatings:** Thin-Film Optical Coatings. **Optical Materials:** Optical Glasses.

Further Reading

Butcher PN and Cotter D (1990) *The Elements of Nonlinear Optics*. Cambridge, UK: Cambridge University Press.

Chemla DS and Zyss J (1987) *Nonlinear Optical Properties of Organic Molecules and Crystals*, vol. 1. Orlando, FL: Academic Press.

Chemla DS and Zyss J (1987) *Nonlinear Optical Properties of Organic Molecules and Crystals*, vol. 2. Orlando, FL: Academic Press.

Clark DT (1994) Second European Conference on Smart Structures and Materials, *SPIE Proceedings*, vol. 2361. Bellingham, CA: SPIE.

Crowson A (1996) Smart Materials Technology and Biomimetics, *SPIE Proceedings*, vol. 2716. Bellingham, CA: SPIE.

Gobin P-F and Friend CM (2000) Smart Structures and Materials, *SPIE Proceedings*, vol. 4073. Bellingham, CA: SPIE.

Janocha H (1999) *Adaptronics and Smart Structures, Basics, Materials, Designs, and Applications*. Berlin: Springer.

Jorgenson GV and Lee JC (1985) Optical Materials for Energy Efficiency and Solar Energy Conversion IV, *SPIE Proceedings*, vol. 562. Bellingham, CA: SPIE.

Goff AH-L, Granqvist C-G and Lampert CM (1992) Optical Materials Technology for Energy Efficiency and Solar Energy Conversion XI: Chromogenics for Smart Windows, *SPIE Proceedings*, vol. 1728. Bellingham, CA: SPIE.

McDonuch A, Gardiner APT and McEwen KS (1994) In: Culshaw B (ed.) Second European Conference on Smart Structures and Materials, *SPIE Proceedings*, vol. 2361. Bellingham, CA: SPIE.

Zerbi G (ed.) (1993) *Organic Materials for Photonics*, European Materials Research Society Monographs, V6. Amsterdam: North-Holland.

Sol-Gel Materials

Lisa C Klein, Rutgers the State University of New Jersey, Piscataway, NJ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Sol-gel optics represents a methodology for fabricating optical materials in fiber, thin film, and bulk geometries. Defined broadly, sol-gel optics encompasses a variety of optical devices that contain sol-gel processed components. The optical device may be based wholly on sol-gel processing or incorporate a sol-gel material, along with conventional optical materials. Principally, the optical devices prepared by sol-gel processing or assembled with sol-gel materials are traditional optics or, in some cases, opto-electronics. Among the current sol-gel optical materials, by far the most common are oxides. Further, the majority of sol-gel optics is for transparent components, which typically means glasses, and, consequently, silicates.

In fact, most sol-gel materials have been developed to duplicate conventional silica optical materials. While glass melting technology is highly advanced for making quality lenses, an equivalent material can be made using a sol-gel route. Similarly, ultralow-loss optical fiber can be made by chemical vapor deposition (CVD). Now sol-gel processing can be used to prepare comparable fibers for telecommunications. In cases where sol-gel processing produces an exact duplicate of optical materials produced other ways, the perceived advantage is that sol-gel precursors have a higher purity and better level of mixing than powder raw materials. Perhaps, a more significant advantage is that sol-gel formulations can be designed to promote a particular geometry in the final material, essentially making near-net shape materials.

While sol-gel processing is not designed to produce new optical phenomena, it does offer new ways to assemble materials to produce new optical designs, such as filters, Bragg gratings, amplifiers, and beam splitters. One noted case of sol-gel materials in nonlinear optics is the case where semiconductor particles are trapped in nanometer-sized pores. This leads to so-called quantum dots. The microporosity of the gel, no doubt, assists in this effect, but it is not the gel itself that has produced the optical effect. The optical effect is derived from the nanometer size of the particles. The gel serves as a transparent host that restricts the size of the particles and provides for their uniform distribution.

Sol-Gel Chemistry of Oxide Optical Materials

The sol-gel process for oxides is the name given to any one of a number of processes involving a solution or sol that undergoes a sol-gel transition. Solution refers to a single-phase liquid, while a sol is a kinetically stabilized suspension of colloidal particles. At the transition, the solution or sol becomes a rigid, porous mass by destabilization, precipitation, or supersaturation. Once the solution or sol goes through a sol-gel transition, it is a rigid two-phase system of solid and solvent filled pores. The sol-gel transition is not reversible.

In using a sol-gel process, it is important to be familiar with the reagents, the intermediates and the products. The most important reagent in this case is a hydrolyzable organometallic which is called a metal alkoxide, $M(OR)_x$ where (OR) is an alkoxy group. Alkoxides are the precursors for SiO_2, GeO_2 or B_2O_3, among others. Hydrolysis occurs when the metal alkoxide and water are mixed in a mutual solvent.

The first step is choosing the right reagents. Since most of the glasses are silicates, we start with the silica precursor. Of the available silicon alkoxides, tetraethylorthosilicate (TEOS) is used most often, because it reacts slowly with water and comes to equilibrium as a complex silanol. The colorless liquid $Si(OC_2H_5)_4$ has a density of about 0.9 g/cm^3, is easy to handle safely and is extremely pure when distilled. Most metal alkoxides are prepared by the reaction of halogenated species or pure metals with alcohol.

The two other ingredients in a typical formulation are alcohol and distilled water. In the case of TEOS, ethanol serves as the mutual solvent for TEOS and water. Once TEOS is dissolved in ethanol to make it soluble in water, the chemical reactions hydrolyzation and polymerization begin. The chemical reactions are approximately:

Hydrolyzation



$$-\overset{|}{\underset{|}{Si}}-O-C_2H_5 + H_2O \rightarrow -\overset{|}{\underset{|}{Si}}-OH + C_2H_5OH \qquad [1]$$

Polymerization



$$-\overset{|}{\underset{|}{Si}}-O-C_2H_5 + Si-OH \rightarrow -\overset{|}{\underset{|}{Si}}-O-\overset{|}{\underset{|}{Si}} + C_2H_5OH \qquad [2]$$

An acid is usually added to control the rates of these reactions. The temperature is often ambient, and mixing is continued for between 1 and 3 hours. Complete hydrolysis does not occur. Instead, condensation occurs between silanol and ethoxy groups to give bridging oxygens or siloxane groups. The intermediates that remain soluble in the alcohol–water medium are silanols, ethoxysilanols, and polysiloxanes.

The equipment needed for laboratory-scale production consists of a narrow-necked glass flask with magnetic stir bar on a stirring hot plate. The reactants are added volumetrically to the flask in the order: solvent, TEOS, water, and acid. When everything is dissolved and the solution is clear, the hot plate may be turned on to accelerate reactions or a reflux condenser may be attached.

The parameters that influence the chemical reactions are temperature, pH, amount of water, solvent, and precursor. More complex compositions are easier to mix in longer chain alcohols, and longer chain organic groups give slower reaction rates. Low pH favors a polymerization scheme that gives linear molecules and the solution remains clear. High pH favors cluster growth and the solution may become cloudy. At high pH or high water, solutions produce cross-linked polymers or branched clusters. A small volume fraction of branched clusters restricts flow, when the same volume fraction of linear polymers does not. At a higher volume fraction, the linear polymers become tangled, and then low water solutions will gel. The result of these reactions under all conditions is an increase in the molecular weight of the oxide polymer. Eventually, the solution reacts to a point where the molecular structure is no longer reversible, and the sol-gel transition has been reached.

Shapes, Compositions and Precursor Concentrations

A sampling of compositions and precursors is given in Table 1. Some compositions such as SiO_2 and TiO_2-SiO_2 have been prepared in bulk, to duplicate materials made by melting for lenses and mirror blanks. Other compositions such as $B_2O_3-SiO_2$ have been prepared for thin-film applications. The distinguishing aspect between the solutions formulated for bulk objects and those formulated for thin films is the oxide concentration in the solution. An indication of the solution concentration is the molar ratio of water to alkoxide. The higher ratios are used when bulk objects are desired.

Table 2 gives a sampling of the geometries for sol-gel silica. For each geometry, an example of a shape is given, with an application for each shape and the approximate dimensions of the sol-gel material.

In terms of near-net shape processing, when the material goes through its sol-gel transition, it proceeds to dry and shrink. This phase is characterized either by isotropic shrinkage or anisotropic shrinkage. Monoliths fall into the first category with isotropic shrinkage following molding. Thin films on substrates fall into the second category with anisotropic shrinkage following dipping. Fibers also show

Table 1 Typical compositions of sol-gel optical materials

Oxides	*Precursors*	*Compositions in mol %*	*R**
Single oxide			
SiO_2	$Si(OC_2H_5)_4$	100 SiO_2	16
Two oxides			
B_2O_3–SiO_2	$Si(OC_2H_5)_4$ $B(OCH_3)_3$	80 SiO_2–20 B_2O_3	1.5
GeO_2–SiO_2	$Si(OCH_3)_4$ $Ge(OC_2H_5)_4$	90 SiO_2–10 GeO_2	4
TiO_2–SiO_2	$Si(OC_2H_5)_4$ $Ti(OC_3H_7)_4$	94 SiO_2–6 TiO_2	50
P_2O_5–SiO_2	$Si(OC_2H_5)_4$ H_3PO_4	90 SiO_2–10 P_2O_5	16
Three oxides			
Li_2O–Al_2O_3–SiO_2	$Si(OC_2H_5)_4$ $Al(OC_4H_9)_3$ $LiNO_3$	82 SiO_2–3 Al_2O_3–15 Li_2O	8
Na_2O–B_2O_3–SiO_2	$Si(OC_2H_5)_4$ $B(OCH_3)_3$ $NaNO_3$	82 SiO_2–12.4 B_2O_3–5.6 Na_2O	10

*Approximate ratio of water to alkoxide, e.g., $R = 16$ means 16 moles of H_2O per mole of $Si(OC_2H_5)_4$.

Table 2 Geometries and approximate dimensions for selected applications of sol-gel silica

Geometry	*Shape*	*Dimensions*	*Application*
Monolith	Flat disk	10 cm diameter 1 cm thick	Lens
	Cylinder	0.5 cm diameter 2 cm long	Rigid host for chromophores
Thin film	Film on Si wafer	500 nm thick	Antireflection
	Film on Hollow tube	~10 000 nm thick	Solar collector panel
Fiber	Rod	0.8 cm diameter 25 cm long	Preform for drawing
	Filament	150 micron diameter/100 m length	Lightguide

anisotropic shrinkage, though it depends on whether or not the fiber is drawn from a preform many times its diameter or produced from a filament that is closer to its diameter.

Sol-Gel Monolith Processing

Monoliths formed from an alkoxide solution are achieved only in dilute solutions. Therefore, alkoxide gels are somewhat difficult to dry because of their small pores (<10 nm). To avoid cracking in alkoxide gels, different treatments have been tried. Aerogels are dried in an autoclave by hypercritical techniques. That is, the solvent is removed above its critical point. The resulting gel is about 10% dense and shows no shrinkage. Xerogels are dried by natural evaporation. Xerogels are 60% dense and have reductions 40–60% in volume.

Alternatively, monoliths can be formed from colloidal solutions. These particles coalesce at gelling. Colloidal gels are easily dried, and they are less likely to crack than alkoxide xerogels. While alkoxide gels have small pores, colloidal gels have larger pores or voids between particles. For the same reason, colloidal gels densify at higher temperatures than alkoxide xerogels. The higher temperature for colloidal gels may lead to undesirable crystallization.

By either route, a serious problem for sol-gel processing is the presence of water. Especially when monoliths are used for fiber drawing, residual OH ions have a deleterious effect on optical properties. That is why non-aqueous solvents, as well as fluorination or chlorination treatments, have been investigated to reduce the OH content.

Sol-Gel Fiber Processing

While monolithic pieces need high water content, fibers can be drawn out of low water content solutions. The sol-gel process allows one to bait and draw a string of gel about the same diameter as the desired fiber directly from the solution. This has been shown where the water to alkoxide ratio was controlled to give the property of spinnability. The time and manner in which the system loses fluidity depend on composition and catalyst. Low water solutions show a gradual increase in viscosity before losing fluidity, while high water solutions lose fluidity more abruptly from a lower viscosity. A problem with this method is the shape of the fiber, which tends not to be cylindrical.

Another approach to making near-net shape fibers from a sol-gel process involves coating a shell or concentric shells of sol-gel glass on a filament of textile fiber. This approach is referred to as the volatile host method, where a plastic filament is used as a template. Multiple dipping or adjustment of the viscosity can lead to different thicknesses. Upon exposure to atmospheric moisture, the films gel. After gelling, a rigid, continuous shell runs the length of the filament.

Once the shell has hardened, solvent and water can escape through interconnected pores. The shell shrinks in the radial dimension, but remains continuous along its axis. During heat treatment and desiccation, little if any densification occurs at temperatures well below the glass transition. The interconnected pore structure remains open until the volatile host is eliminated and undesirable gases are removed. This method is capable of producing optical fibers, but is more suitable for hollow fibers or ion exchange media.

Sol-Gel Thin Film Processing

Like sol-gel fibers, sol-gel thin films are prepared from low water content solutions. The process is exceedingly simple. A solution containing the desired oxide precursors is applied to a substrate by dipping or spinning.

At this time, the majority of sol-gel coatings are applied by dipping. This is an approach that allows the properties of the solution to control the deposition. A substrate is lowered into a vessel containing the solution. A meniscus develops at the contact of the liquid and the substrate. As the substrate is withdrawn, the meniscus generates a continuous film on the substrate. The process is able to apply a coating to the inside and outside of complex shapes simultaneously.

The equipment is inexpensive, especially in comparison to any deposition techniques that involve vacuum. Coatings can be applied to metals, plastics, and ceramics. Typically, the coatings are applied at room temperature, although most need to be calcined and densified with heating. Dip films are typically one micron, uniform over large areas and adherent. The time-to-gel is especially important when it comes to coatings because film formation, drying, and creation of pores must be rapid. Optimum film formulations correspond to those solutions that lose tackiness quickly.

In most cases, the effect of the viscosity is far greater than the surface tension. Two simple relationships are that the film thickness increases with increasing withdrawal rate and, for a given withdrawal speed, the film thickness increases with an increase in oxide content. The process is frequently a batch process, certainly on the laboratory scale. However, the batch process can be scaled up. Repeated dipping builds up a thicker film.

For one-side coating, a technique that is often used is spin coating. In this case, the substrate, usually a silicon wafer, is placed on a spinner, rotated at perhaps 200 rpm while solution is dripped on the center of the substrate. As with dip coatings, a film between 50 and 500 nm results.

After the Sol-Gel Transition

Having selected a shape and designed the formulations accordingly, there are several further steps common to monoliths, fibers, and films. First of all, the gels must be dried. Using the example of silica, TEOS is less than 30% by weight silica and the solution is even less. From the time the solution is applied to the time it gels, there is about 50% weight loss. Then, as the gel dries there is another reduction in weight by one-half. To go along with the weight loss there is about 70% volume reduction.

Films can be dried quickly in air because of the one thin dimension. It has been shown repeatedly that all shrinkage is taken up in the thin dimension and not in the plane of the substrate. Yet, the films remain adherent and continuous and maintain complete surface coverage. To go from a tacky film to a hard film may take only a few minutes.

Following drying and shrinkage comes the heat treatment. It would be inaccurate to say that glass has been formed at room temperature by simply reacting, gelling, and drying the solutions. In this state, the materials have many of the characteristics of the corresponding glass, but they are more or less porous. Water and solvent escape through interconnected pores that remain open at the surface until the gels are fired to temperatures well above 600°C. When needed to fulfill the requirements of an application, the hard gel is heated to various degrees of collapse.

The microporosity in silica xerogels is not removed entirely until 1000°C.

Applications of Sol-Gel Optical Coatings

Sol-gel processing has a special relevance to optical coatings. In most cases, the applications are substitutions of a sol-gel coating for a coating obtainable by other means. Most optical coatings achieve their effect by selective absorption and interference. By depositing 1–14 or more layers of dielectric thin films, using two or more different compositions, a variety of antireflection (AR), half-mirror, hot-mirror and cold-mirror coatings can be designed. An early design was for rear-view mirrors for cars, where the coatings consisted of titania-silica-titania interference filters that gave the effect of total reflectance and replaced conventional metallizing. Another early application was solar reflecting films for windows. These coatings consisted of Pd-containing titania films which show selective absorption.

A sampling of optical coatings is given in Table 3. The application, the mechanism, and the oxide composition are listed. Generally, these coatings can be prepared by other deposition techniques. Those applications which are specific to sol-gel coatings relate to the microporous nature of the sol-gel processed films. In Table 3, there are antireflective coatings of several types. Both borosilicates and titania silicates have been developed for this application. Changes in the composition, changes in the microstructure, and changes in the porosity can be used to grade the index of refraction. Antireflection in the ultraviolet range has been accomplished with thoria and hafnia films. Broadband antireflection has been used for laser optics. The sol-gel coating technique provides control over composition and deposition thickness. The layers, being quarter wavelength in thickness, require precise control.

Table 3 Thin-film applications

Optical application	*Mechanism*	*Typical composition*
Color filters	Selective Absorption	Cr_2O_3–SiO_2
Mirror	Interference	14-layer TiO_2: SiO_2
Antiglare	Absorption	CoO–SiO_2
Antireflection		
Narrow	Graded porosity	SiO_2
Broadband	Interference	Three-layer
	1/4 wavelength	SiO_2–TiO_2:ZrO_2: SiO_2
	Graded porosity	SiO_2
IR reflector	Interference	Three-layer TiO_2:Ag:TiO_2

Sol-Gel Rigid Hosts

An exciting way of looking at sol-gel materials is to use the gel as a host. The important point to note is that the sol-gel materials are transparent. While most of the materials are porous, the porosity is on a scale that does not scatter visible light. Therefore, most light is transmitted. The appeal of the bulk shape host is that it can be molded to near-net shape and can be cut and polished.

Hybrids

Several approaches have been taken to prepare so-called hybrid gels incorporating organic and inorganic components. Those methods that mix the components on the nanometer scale include the infiltration of previously formed oxide gels with monomers, reacting of alkoxide and organic monomers, or organic polymers with alkoxides in mutual solvents. The products of these processes are variously called ormosils (organically modified silicates), ceramers (ceramic polymers), interpenetrating networks (IPNs) and nanocomposites.

The original route to hybrids was one where a gel was formed first as a rigid matrix. Monomer was infiltrated into the open porosity of the shaped gel and polymerized inside the gel using UV curing, for example. Since silica gel is the easiest gel to prepare in monolithic form, one combination that has been investigated widely is silica gel/polymethyl methacrylate (PMMA).

Silica and PMMA, which both have good visible light transmission and similar index of refraction, have been used in hybrids, although it turns out that the match in index of refraction is less critical on the nanoscale. They are also glassy materials with similar strength. PMMA has much higher fracture energy than silica and is often used as glazing in applications where impact resistance is a priority. However, PMMA has a much lower hardness than silica and is less resistant to abrasion. Ideally, silica–PMMA hybrid nanocomposites have the strength and impact resistance of PMMA, and the hardness of silica in one. One obvious application is transparent, lightweight windows.

Encapsulation

Sol-gel hosts have been used to encapsulate a variety of organic and inorganic molecules, chromophores, and biological agents. Whatever is incorporated into the gel can act in two ways, to give information about the gel host or to be influenced by the gel in its interaction with light. For example, spiropyrans have been incorporate for photochromics, CdS for nonlinear optics, Nd for tunable lasers, and various enzymes for sensors. Early on, silica gel hosts were used to encapsulate the electro-optically active organic compounds 2-methyl-4-nitroaniline (MNA). In comparison to conventional optical cells, MNA doped silica hosts retained optical quality at higher temperature and were more abrasion resistant. Since this discovery, silica hosts, in particular, and sol-gel processing, in general, has been used extensively for encapsulating molecules and species that cannot be heated, but need to be protected in a rigid matrix.

Future Directions

As more and more is learned about the sol-gel process, the greater the number of possibilities for useful optical devices. In the selected examples given above, a key feature is that the sol-gel material is transparent. In addition, the sol-gel material is suitable for application to a variety of substrates. Also, the process is a low-temperature process that is compatible with polymers and organic chromophores. In summary, sol-gel processing has had a number of successes in its application to optical materials, and its use is likely to expand.

See also

Optical Coatings: Thin-Film Optical Coatings.

Further Reading

Andrews MP and Najafi SI (eds) (1997) *Sol-Gel and Polymer Photonic Devices*. Bellingham, CA: SPIE Critical Reviews, CR68-03.

Brinker CJ and Scherer GW (1990) *Sol-Gel Science: The Physics and Chemistry of Sol-Gel Processing*. Boston, CA: Academic Press.

Dunn B and Zink JI (1991) Optical properties of sol-gel glasses doped with organic molecules. *Journal of Material Chemistry* 1: 903–913.

Klein LC (1993) Sol-gel optical materials. *Annual Reviews of Material Science* 23: 437–452.

Klein LC (ed.) (1994) *Sol-Gel Optics: Processing and Applications*. Dordrecht: Kluwer Academic.

Najafi SI (ed.) (1998) *Selected Papers on Sol-Gel for Photonics*. Bellingham, CA: SPIE Milestones Series, MS148.

Riesfeld R and Jorgenson CK (1992) Optical properties of colorants or luminescent species in sol-gel glasses. *Structure and Bonding* 77: 208–256.

Sol-Gel Optics. SPIE vols. 1328, 1758, 2288 and 3943, 1990–2000. Bellingham, CA: SPIE.

OPTICAL MICROLENSES

H Ottevaere and H Thienpont, Vrije Universiteit Brussel, Brussel, Belgium

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In today's world of information processing the role of optics and opto-electronics is expected to become increasingly important as the performance of communication, processing, sensing, and display technologies is continuously evolving. Making these photonics technologies faster and smaller requires, at the same time, the introduction of massive parallelism and miniaturization. As a result, high-quality, high-precision, and low-cost microlens arrays are becoming indispensable components. Moreover, the introduction of micro-optics provides new degrees of freedom for the system design and, therefore, also for the functionality. It allows solutions which are not possible with purely conventional optics such as the integration of different micro-optical components and systems, hence reducing the additional mechanical assembly cost as required in conventional optics.

Since the beginning of the 1990s, several research groups and industrial research labs have been focusing their attention on the development of fabrication techniques for refractive and diffractive microlenses. Microlenses and microlens arrays are used for beam shaping purposes such as collimation and focusing (e.g., in combination with laserdiode arrays, detector arrays, and fibers), for illumination (e.g., in display systems and projection systems), and for imaging purposes (e.g., in photocopiers).

In this article we will mainly focus on refractive microlenses and we intend to provide an introductory guide to those basic geometrical and optical parameters that are used to characterize refractive microlenses. Indeed, some elementary principles of geometrical optics (the geometrical laws for optical propagation without the inclusion of diffraction) and wave optics (in wave optics the imaging is studied as a result of the propagation of a wavefront to the image plane; diffraction effects can be explained on the basis of this wave theory) are required to understand the characterization and performance evaluation of these lenses. We, therefore, bring forward the basic nomenclature of refractive micro-optics and will highlight how the performance of an optical lens is affected when reducing its physical dimensions.

We start this article by introducing the imaging properties of both thick and thin lenses in the paraxial approximation. In the section on lens aberrations, we discuss the different primary aberrations that influence the imaging properties of a lens. Combined effects of aberrations and diffraction give rise to some frequently used lens performance criteria which we discuss in the section on diffraction. Different aspects have to be considered when discussing the quality of a lens, because each type of microlens application requires specific performances. It is, therefore, not possible to come up with a single figure of merit which satisfactorily evaluates the overall quality of a microlens. Moreover, one needs specific information about the characteristics of the light sources and detectors that are used in the system and also details about the imaging system geometry and the required imaging contrast. We review them in the section on quality criteria.

In the section on interference, we describe these phenomena and focus on two-beam interference that forms the basis of the photonic instrumentation that can be used to characterize discrete microlenses and microlens arrays. For a complete evaluation of a microlens it is essential to measure both its geometrical properties (diameter, sag, surface profile, etc.) and its optical performance (focal length, wave aberrations, etc.). In the final section of this article we introduce three interference-based instruments which are crucial to the full quantitative characterization of refractive microlenses: a noncontact optical profiler based on a Mirau interferometer, a transmission Mach–Zehnder interferometer, and a Twyman–Green interferometer.

Geometrical Optics

Introduction

Within the paradigm of geometrical optics or ray-optics, light travels from the source along straight lines or rays. When a light ray traverses an optical system consisting of several homogeneous media in sequence, the optical path is a chain of straight-line segments. Discontinuities in the line segments occur each time the light is refracted or reflected. The laws of geometrical optics that describe the direction of the rays are described below.

The law of refraction, also called Snell's law

The refraction of a ray at a 'well-polished' surface between two isotropic media, with indices of refraction n_1 and n_2, is given by

$$n_1 \sin \varphi_1 = n_2 \sin \varphi_2 \qquad [1]$$

where φ_1 and φ_2 are the angles between, respectively, the incident and the refracted ray and the normal to the surface.

The law of reflection

When a ray is reflected on a flat 'polished' interface dividing two uniform media, the reflected ray remains within the plane of incidence and the angle of reflection equals the angle of incidence.

Geometrical wavefronts can then be constructed from the optical rays propagating through the system. Locally they are orthogonal to the rays and the optical path lengths along all rays from one wavefront to another are equal. In regions where the wavelength is considered to be negligible, as compared to the dimensions of the relevant components of the optical system, geometrical wavefronts are close approximations of the physical wavefronts.

The Paraxial Approximation

The basic optics of image location and magnification is demonstrated by the application of paraxial or first-order optics, also called Gaussian optics. In the paraxial approximation, only those points and rays will be considered which lie in the immediate vicinity of the optical axis, so that all angles φ are small ($\varphi \leq 15°$). This assumption is true in lens systems with small object and image field sizes and small apertures of pupils. The terms involving squares and higher powers of the off-axis distances or of the angles, which the rays make with the optical axis, will not be discussed here. This leads to:

$$\sin \varphi = \tan \varphi = \varphi + O_{\geq 2}(\varphi) \approx \varphi \qquad [2]$$

With this assumption we can write the refraction law by the linear relation:

$$n_1 \varphi_1 = n_2 \varphi_2 \qquad [3]$$

Refraction at a spherical surface

In Figure 1 a spherical surface with a radius of curvature R forms an interface between two materials with indices of refraction n_1 and n_2. Two rays are shown emanating from an axial object point S. One is an axial ray, normal to the surface of the lens at its vertex V. The vertex of a lens is defined as the point on the refracting surface at the center of its free aperture. This assumes that the aperture is circular



Figure 1 Refraction at a spherical surface.

and centered and the surface is spherical. More generally, if the surface is not spherical but has rotational symmetry, the vertex is the point where the axis of symmetry intersects the optical surface. It is refracted without any change in direction. The other ray is an arbitrary ray incident at O and refracting there according to Snell's Law.

We can rewrite the paraxial refraction law (eqn [3]) and derive a relation between the object and image distances, s_o and s_i, respectively.

From the triangles SOC and POC, we have:

$$\varphi_1 = \alpha + |\theta| \qquad |\theta| = |\beta| + \varphi_2 \qquad [4]$$

where $|\theta|$ and $|\beta|$ represent the absolute values of θ and β.

We also have:

$$\tan\alpha = \frac{h}{|s_o| + \delta} \qquad \tan|\beta| = \frac{h}{s_i - \delta}$$
$$\tan|\theta| = \frac{h}{R - \delta} \qquad [5]$$

As discussed above, for paraxial rays we may approximate the sine and tangent of an angle by the angle itself and one can show that the small distance δ may be ignored. In accordance with the sign convention the object distance, being to the left of the refracting surface, is to be taken as negative. Inserting eqns [4] and [5] into [3] results in:

$$\frac{n_2}{s_i} - \frac{n_1}{s_o} = \frac{n_2 - n_1}{R} \qquad [6]$$

This equation does not contain the angle α, so the image distance s_i is the same for all paraxial rays starting from S.

The spherical surface power $\wp$ is now defined as:

$$\wp \equiv \frac{n_2 - n_1}{R} \qquad [7]$$

We can relate this power of the surface $\wp$ to the object and image distance, by combining eqns [6] and [7]:

$$\frac{n_2}{s_i} - \frac{n_1}{s_o} = \wp \qquad [8]$$

The distance from the object point to the vertex of the refractive surface is called the front focal length f_{FFL}, if the image is at infinity ($s_i = \infty$). Equations [6] and [8] then give:

$$f_{\mathrm{FFL}} = -\frac{n_1}{n_2 - n_1} R = -\frac{n_1}{\wp} \qquad [9]$$

Similarly, if the image is placed at the back focal length f_{BFL}, such that the object distance equals infinity ($s_o = \infty$), then:

$$f_{\mathrm{BFL}} = \frac{n_2}{n_2 - n_1} R = \frac{n_2}{\wp} \qquad [10]$$

Thick lenses

A thick lens can be treated as a component consisting of two spherical refracting surfaces separated by a distance d between their vertices V_1 and V_2, as shown in Figure 2. The determination of the focal length as a function of the object and image distance and of the radii of curvature can also be solved using the matrix formalism.

The first and second focal points or the object and image foci, F_o and F_i, can be measured from the two vertices or poles and are called the front and the back focal length denoted by f_{FFL} and f_{BFL}, respectively (Figure 2). The incident and the emerging rays will virtually meet at points that belong to two curved surfaces. These surfaces, approximating planes in the paraxial region, are termed the primary and secondary principal planes, PP_1 and PP_2. Points where the primary and secondary principal planes intersect the optical axis are known as the first and second principal points, H_1 and H_2, respectively.



Figure 2 The thick lens geometry.

They provide a set of very useful references from which to measure several of the system parameters. To fully describe a system by its cardinal points, two more points are needed in addition to the two focal points, F_o and F_i and the two principal points, H_1 and H_2. These points are called the nodal points. However, they coincide with the principal points when the lens is surrounded on both sides by the same medium, for example, air. Note that h_1 and h_2 determine the positions of the principal points relative to the vertices V_1 and V_2, while f determines the focal point position relative to the principal points. One can show that these distances are given by:

$$\begin{aligned} h_1 &= \frac{-R_1 n_m d}{n_l(R_2 - R_1) + (n_l - n_m)d} \\ h_2 &= \frac{R_2 n_m d}{n_l(R_2 - R_1) + (n_l - n_m)d} \\ f &= \frac{n_m}{(n_l - n_m)\left[\dfrac{1}{R_1} - \dfrac{1}{R_2} + \dfrac{d(n_l - n_m)}{n_l R_1 R_2}\right]} \end{aligned} \qquad [11]$$

We now derive the Gaussian formulae that describe imaging through two surfaces which are rotationally symmetric about the same axis. We assume here that the lens, with refractive index n_l, faces the same medium of refractive index n_m on both sides (Figure 3). We can correctly use this hypothesis since the microlenses which we discuss throughout this work are mainly surrounded by air. Let R_1 and R_2 be the radii of curvature of the surfaces at their axial points, measured as positive when the surface is convex towards the incident light.

The image of a given object, formed by refraction at the first surface with radius of curvature R_1, becomes the object for refraction at the second surface. The image formed by the second surface with R_2 as radius is then the final image due to the action of the thick lens. We know from eqn [6] that the paraxial rays issuing from S at a distance s_{o1} from V_1 will meet at P', at a distance which we call s_{i1}. This gives:



Figure 3 Refraction at both spherical surfaces of a thick lens.

$$\frac{n_l}{s_{i1}} - \frac{n_m}{s_{o1}} = \frac{n_l - n_m}{R_1} \qquad [12]$$

Thus, at the second spherical surface, eqn [6] becomes:

$$\frac{n_m}{s_{i2}} + \frac{n_l}{(s_{i1} - d)} = -\frac{n_m - n_l}{R_2} \qquad [13]$$

As discussed above, we have:

$$\begin{aligned} -\frac{1}{f_{FFL1}} &= \frac{n_l - n_m}{n_m}\frac{1}{R_1} \\ \frac{1}{f_{BFL2}} &= -\frac{n_m - n_l}{n_m}\frac{1}{R_2} \end{aligned} \qquad [14]$$

where f_{FFL1} is the front focal length of the first refracting surface and f_{BFL2} the back focal length of the second refracting surface.

Eliminating s_{i1} in eqns [12] and [13] and inserting [14] yields:

$$d = \frac{n_l}{n_m\left(\dfrac{1}{s_{o1}} - \dfrac{1}{f_{FFL1}}\right)} - \frac{n_l}{n_m\left(\dfrac{1}{f_{BFL2}} - \dfrac{1}{s_{i2}}\right)} \qquad [15]$$

where s_{o1} is measured with respect to V_1 and s_{i2} is measured with respect to V_2. After some calculations this equation may also be put in the form:

$$\begin{aligned} &s_{o1}s_{i2} - \frac{f_{BFL2}(n_l f_{FFL1} + d n_m)}{n_l(f_{FFL1} + f_{BFL2}) + d n_m} \\ &s_{o1} - \frac{f_{FFL1}(n_l f_{BFL2} + d n_m)}{n_l(f_{FFL1} + f_{BFL2}) + d n_m} \\ &s_{i2} + \frac{d n_m f_{FFL1} f_{BFL2}}{n_l(f_{FFL1} + f_{BFL2}) + d n_m} = 0 \end{aligned} \qquad [16]$$

Obviously eqn [16] is much too cumbersome to find image locations. However, we can transform and reduce the latter equation to the form:

$$\frac{1}{s_{i2} - h_2} - \frac{1}{s_{o1} - h_1} = \frac{1}{f} \qquad [17]$$

where h_1, h_2 and f are the unknowns.

Indeed, rewriting eqn [17] gives:

$$s_{o1}s_{i2} - (f + h_2)s_{o1} + (f - h_1)s_{i2} + f(h_1 - h_2) + h_1 h_2 = 0 \qquad [18]$$

Equations [16] and [18] will be identical if the coefficients of their corresponding terms are equal;

that is when:

$$\begin{aligned} f+h_2 &= \frac{f_{\mathrm{BFL2}}(n_{\mathrm{l}}f_{\mathrm{FFL1}}+dn_{\mathrm{m}})}{n_{\mathrm{l}}(f_{\mathrm{FFL1}}+f_{\mathrm{BFL2}})+dn_{\mathrm{m}}} \\ f-h_1 &= -\frac{f_{\mathrm{FFL1}}(n_{\mathrm{l}}f_{\mathrm{BFL2}}+dn_{\mathrm{m}})}{n_{\mathrm{l}}(f_{\mathrm{FFL1}}+f_{\mathrm{BFL2}})+dn_{\mathrm{m}}} \\ f(h_1-h_2)+h_1h_2 &= \frac{dn_{\mathrm{m}}f_{\mathrm{FFL1}}f_{\mathrm{BFL2}}}{n_{\mathrm{l}}(f_{\mathrm{FFL1}}+f_{\mathrm{BFL2}})+dn_{\mathrm{m}}} \end{aligned} \qquad [19]$$

These three equations may be solved for the three unknowns h_1, h_2, and f:

$$\begin{aligned} f &= \frac{n_{\mathrm{m}}}{(n_{\mathrm{l}}-n_{\mathrm{m}})\left[\dfrac{1}{R_1}-\dfrac{1}{R_2}+\dfrac{d(n_{\mathrm{l}}-n_{\mathrm{m}})}{n_{\mathrm{l}}R_1R_2}\right]} \\ h_1 &= \frac{-R_1n_{\mathrm{m}}d}{n_{\mathrm{l}}(R_2-R_1)+(n_{\mathrm{l}}-n_{\mathrm{m}})d} \\ h_2 &= \frac{R_2n_{\mathrm{m}}d}{n_{\mathrm{l}}(R_2-R_1)+(n_{\mathrm{l}}-n_{\mathrm{m}})d} \end{aligned} \qquad [20]$$

Thus we see that the relation between the object position and the image position (eqn [16]) is expressed in the more convenient form of eqn [17] with the values of h_1, h_2, and f given by eqn [20]. Here h_1, h_2 and f depend on the constants of the system where, as shown in eqn [11], h_{i} represents the distance between the vertex V_{i} and the principal point H_{i}, and f is the focal length measured from a principal point on the axis and not from the vertex of the lens. If we now assume that:

$$s_{\mathrm{o}} = s_{\mathrm{o}1} - h_1, \qquad s_{\mathrm{i}} = s_{\mathrm{i}2} - h_2 \qquad [21]$$

we can write the thick lens equation as:

$$\frac{1}{s_{\mathrm{i}}} - \frac{1}{s_0} = \frac{1}{f} \qquad [22]$$

where the object and image distance, s_{o} and s_{i}, respectively, are measured from the principal points of the lens. We can conclude that the formula that describes imaging through two surfaces may be simplified to the thick lens formulation given in eqn [22] by choosing the principal points H_{i} instead of the vertices V_{i}, from which S and P are to be measured.

Thin lenses

The preceding eqn [20] takes a particularly simple form when the lens is so thin that the axial thickness of the lens d may be neglected. But obviously there exists no real lens with a thickness equal to zero. A thin lens is only a concept which is an extremely useful tool in optical system design. When a lens or an optical system has a zero thickness, the object and image calculations can be greatly simplified. In this case, the two principal points are coincident and are located where the thin lens is situated.

As a further simplification, we assume that the surrounding medium of the lens is air which means that $n_{\mathrm{m}} \approx 1$. When $n_{\mathrm{l}} = n$, we find:

$$\frac{1}{f} = \frac{1}{s_{\mathrm{i}}} - \frac{1}{s_{\mathrm{o}}} = (n-1)\left(\frac{1}{R_1} - \frac{1}{R_2}\right) \qquad [23]$$

These equations are often called the thin-lens equation and the lensmaker's formula, respectively, because the latter predicts the focal length of a lens, fabricated with a given refractive index and radii of curvature. This formula is very useful in the optical design process as a first-order approach to calculate the features of the thin lenses and results in a set of lens powers (or focal lengths) for the different lenses and in the spacings between them. Once the thin lens optical system is solved and the primary aberrations are corrected for, one can design the thick lens system. The corresponding thick lens system must have the same component powers and the lenses must be spaced apart by the same distances as for the thin lens design, but the thick lens spacings must be measured from the principal points of the lenses instead of from the vertices of the lenses.

Other lens characteristics

Another basic parameter of a refractive lens is its focal number $f\#$. The f-number, also called the speed of the lens, is defined as the ratio of its effective focal length and the lens aperture diameter D (Figure 4):

$$f\# = \frac{f}{D} \qquad [24]$$



Figure 4 A lens with an aperture diameter D, a focal length f, and a semi-angle α.

The effective focal length f of a lens or often called the focal length is defined from a principal point on the axis of the lens and not from its vertex. Typical focal numbers for refractive microlenses range between 0.8 and 30.

The numerical aperture (NA), is another way of defining the same characteristic. It is described as the sine of the angular semi-aperture α in the object space multiplied by the refractive index n of the object space (Figure 4):

$$\mathrm{NA} = n \sin \alpha \qquad [25]$$

Both the focal number ($f\#$) and the NA are related in the paraxial approximation by

$$f\# = \frac{n}{2\mathrm{NA}} \qquad [26]$$

Lens Aberrations

Introduction to Third-Order Monochromatic Aberrations

An exact ray trace or a measurement on a real lens will certainly disclose inconsistencies with the corresponding paraxial description. Such deviations from the idealized Gaussian optics are known as aberrations. For monochromatic light there are five third-order or Seidel aberrations: three of them, namely spherical aberration, coma, and astigmatism, deteriorate the image by blurring it, while the remaining two, curvature of field and distortion, deform the image. An additional aberration, chromatic aberration, results from the wavelength dependence of the imaging properties of an optical system. We will not discuss the latter as this aberration can be minimized by selecting a lens material with a refractive index that only varies by a negligible amount over the wavelength range of interest.

For a brief discussion of aberrations we consider the case of a perfect lens focusing a collimated light beam. In this case, the lens transforms the incoming planewave into a spherical wave, also called the reference sphere. For a lens with aberrations, however, the real wavefront behind the lens shows deviations from the ideal spherical shape (Figure 5). The optical path length [AB] may be called the wavefront aberrations $\psi(x, y)$ and can be calculated as:

$$\psi(x, y) = W(x, y) - R(x, y) \qquad [27]$$



Figure 5 Relation between wavefront and ray aberration.

where $W(x, y)$ represents the spherical wavefront in the Gaussian approximation and $R(x, y)$ depicts the real wavefront. The wave aberration is given by the optical path difference along a ray between the reference sphere and the real wavefront behind the lens. Alternatively, the aberrations can be described in terms of the ray aberrations. In this case, not all the rays intersect the paraxial image plane at the same point and the distribution of the ray intercepts around the paraxial image point can be used to measure the amount of light blur. These two ways of quantitatively describing the aberrations are apparently not independent of each other, the ray aberrations being the derivate of the wavefront aberrations.

There are several sets of suitable polynomials over which the wavefront aberrations can be expanded. The Zernike polynomials will be further used in this work (see, for example, the Mach–Zehnder and Twyman–Green interferometers in the section on Microlens testing).

For rotational symmetric optical systems, the most common approach is to expand the aberration function ψ to the fourth order as a power series in polar pupil coordinates. This corresponds to the third-order ray aberrations or primary aberrations. The different terms in the aberration polynomial ψ are to the fourth power of the object coordinate h' and the pupil coordinate r. In that case, the wavefront aberration polynomial ψ, as a function of the object coordinate h' and the polar pupil coordinates r and θ (Figure 6), is given by

$$\psi(h', r, \theta) = {}_0C_{40} r^4 + {}_1C_{31} h' r^3 \cos\theta + {}_2C_{22} h'^2 r^2 \cos^2\theta + {}_2C_{20} h'^2 r^2 + {}_3C_{11} h'^3 r \cos\theta \qquad [28]$$

The ${}_iC_{jk}$ coefficients are subscripted by the numbers that specify the powers of the term dependence on h', r and $\cos\theta$, respectively. These terms comprise the five monochromatic or Seidel aberrations as shown in Table 1.

Each aberration is characterized by its dependence on the deviation from the optical axis h', on the aperture of the refracting surface r, and on the



Figure 6 (a) Imaging of an off-axis point P; (b) frontal view of a portion of the wavefront.

Table 1 The five monochromatic or Seidel aberrations

r^4	Spherical aberration
$h'r^3 \cos\theta$	Coma
$h'^2r^2 \cos^2\theta$	Astigmatism
h'^2r^2	Curvature of field
$h'^3r \cos\theta$	Distortion

symmetry around the optical axis θ. Equation [28] can be used to estimate how the aberration blurs change if the aperture or field of view of a lens is changed. In the following section we briefly describe each of these aberrations in terms of their visual effects.

Spherical Aberration

The first term in eqn [28], ${}_0C_{40}r^4$, is the only term in the third-order wave aberration that does not depend on the deviation h' from the optical axis. Thus, spherical aberration (SA) is the only monochromatic aberration that occurs on the optical axis and that exists even for axial object and image points. As shown in Figure 7a, SA results from the rays that enter via different zones of the aperture and are focused at different distances from the lens. It is evident from Figure 7a that the best focus is not at the paraxial plane. The best focus, however, is found at the location where the circular image blur is the same over the entire field of view and is called the circle of least confusion.

Because most applications consist of on-axis illuminated planoconvex microlenses, we will firstly focus our attention on how microlenses have to be positioned to minimize SA. When we consider a planoconvex lens with the curved surface towards the infinite conjugate for an incident parallel beam, both surfaces are contributing approximately equal amounts of ray bending. Figure 8a shows the ray diagram for a planoconvex lens as obtained with the ray-tracing program Solstis. Solstis is a commercial photonics design software, consisting of different modules, each of which is dedicated to a certain optical modeling approach. If, however, the flat surface is turned toward the incident rays, then the first surface does not bend the rays and all the ray-bending work is done by the second surface (Figure 8b). We can conclude here that the best orientation is that which distributes the ray bending equally between the two surfaces of the lens.



Figure 7 The primary aberrations: (a) spherical aberration – negative SA: the rays through the outer zones of the lens focus closer to the lens than the rays through the central zones; (b) coma – positive coma: the rays through the outer zones of the lens form a larger image than those going through the center; (c) astigmatism – negative astigmatism: the tangential or vertical fan of rays is focused to the left of the horizontal or sagittal fan; (d) curvature of field – negative curvature of field: images farther from the axis focus nearer to the lens than the on-axis images; (e) positive distortion – the magnification increases as the field angle increases; (f) negative distortion.



Figure 8 Ray diagram of a planoconvex lens ($D = 200$ μm; $f = 249$ μm) with planewave illumination incident on (a) the curved surface and (b) on the plane surface. LSA (longitudinal SA) represents the difference between the paraxial and the marginal focus while TSA (transversal SA) shows the radius of the spot in the paraxial focal plane.

Because the ray blur varies with the third power of the lens aperture, lowering the aperture diameter will cause a rapid decrease in the extent of the spherical



Figure 9 Ray diagram of a planoconvex lens (a) with a focal length *f* and (b) with a focal length *2f*.



Figure 10 (a) Ray diagram for a planoconvex lens ($D = 200$ µm; $f = 249$ µm). (b) The spherical aberration is reduced with a factor 4 by splitting the optical power of the original lens and using a doublet ($D = 200$ µm; $f = 621$ µm for both lenses).

aberration blur. For a given aperture of the lens, the spherical aberration is a function of the focal length of the lens and increases with a decreasing focal length or an increasing NA (Figure 9).

A change in SA, contributing to the wave aberration, for a variation of the lens diameter D or the focal length f can be estimated with the following rules:

$$\text{Spherical aberration} \div D^4 \quad \text{for a constant } f$$

$$\text{Spherical aberration} \div 1/f^3 \quad \text{for a constant } D$$

However, by preserving the focal length and hence the optical power of the lens, the SA can be changed by varying the radii of the surfaces. This would be the same as physically bending a lens made of flexible plastic. In Figure 10 we have reduced the spherical aberration with a factor of four by splitting a lens into two elements, each with a longer focal length, keeping the total optical power of the elements the same as the original lens. This means that, in practice, high NA microlenses can be replaced by a number of microlenses reducing the SA significantly.

However, in optical systems, where only a small number of surfaces are allowed, aspherical surfaces can be used to correct the SA. In Figure 11 we show that making the lens shape elliptical while maintaining the other characteristics of the microlens ($D = 200$ µm; $R = 150$ µm) results in a reduction of the SA. The most common form of an aspheric surface is a rotationally symmetric surface with the sag, defined as:

$$z_{\text{conic}} = \frac{R^{-1}(x^2 + y^2)}{1 + \sqrt{1 - (1 + K)R^{-2}(x^2 + y^2)}} \qquad [29]$$

where R is the radius of curvature, K the conic parameter, and x and y the coordinates in the substrate plane. The meaning of K is given in Table 2.

In eqn [28] we have shown that the wavefront aberrations can be written as the sum of the Seidel or third-order aberrations. Furthermore, we have seen that only the SA contributes to the wavefront aberration when we illuminate the microlens on-axis ($h' = 0$). When we limit our experiments to on-axis illumination during the optical characterization of the microlenses, the wavefront aberrations are a measure for the SA. To prove this, we have calculated and plotted in Figure 12, the SA and the wavefront aberrations as a function of the focal length for a 200 µm lens ($n = 1.48$).

Both the SA and wavefront aberration values are obtained with the ray-tracing software Solstis. The wavefront aberration is calculated here as the optical path difference [BA] between a real wavefront surface and a spherical reference surface. From these results we can observe that for microlenses with an $f > 330$ µm or an NA lower than 0.3 only the spherical aberration contributes to the root-mean-square (RMS) wavefront aberration. The RMS or standard deviation σ of a number N of data x_i ($i = 1, \ldots, N$) with a mean value X can be written as $\sigma = \sqrt{\sum_{i=1}^{N} (X - x_i)^2 / N}$. For smaller focal length microlenses, however, we notice that higher-order aberrations appear and compensate the SA, resulting in a lower wavefront aberration compared to the SA. We can conclude that the wavefront aberration values represent the optical performance of the microlenses with a main contribution from the SA for on-axis illumination.



Figure 11 (a) Ray diagram of a spherical planoconvex lens ($D = 200$ µm; $R = 150$ µm; $K = 0$) with planewave illumination. (b) The spherical aberration is reduced by making the lens shape elliptical ($K = -0.57$).

Table 2 The surface type for different conic parameters *K*

Conic constant K	*Surface type*
$K = 0$	Sphere
$K < -1$	Hyperboloid
$K = -1$	Paraboloid
$-1 < K < 0$	Ellipsoid
$K > 0$	Oblate ellipsoid



Figure 12 The spherical aberration SA and the RMS wave aberration as a function of the focal length for a 200 µm lens ($n = 1.48$).

Other Seidel Aberrations

Coma is an image-degrading aberration that increases rapidly with the lens aperture r. It indicates an off-axis aberration ($h' \neq 0$) that is nonsymmetrical around the optical axis ($\cos\theta \neq$ constant). Figure 7b illustrates the aberration due to a vertical fan of parallel rays refracted by a spherical lens. It results from a lens having different magnifications for rays passing different zones of its aperture. Each circular zone of the lens forms a circular image called the comatic circle. Every other fan of rays forms images that complete the comatic circle. The combination of all these circles causes a comet-shaped flare.

Astigmatism is the imaging of an off-axis point as two perpendicular lines at different distances. In this aberration the rays from a point object converge at a certain distance from the lens to a line which is called the primary image. This line lies in the sagittal plane and is perpendicular to the plane defined by the optical distance and the object point. At a somewhat different distance from the lens they converge to a second line, called the secondary image, which is parallel to the tangential plane. This effect is shown in Figure 7c. The elimination of astigmatism requires that the tangential and sagittal surfaces be made to coincide. The resulting surface is then called the Petzval surface. Although in that case astigmatism has been eliminated, the associated aberration, called curvature of field, remains. So off-axis images are focused on a curved saucer-shaped surface as drawn in Figure 7d, instead of on an ideal flat image surface.

The last of the five primary aberrations is distortion and causes straight lines which do not intersect the axis to be imaged as curved lines. This effect is not related to a lack of sharpness of the image but results from the fact that the magnification varies across the field and induces the image of a square object to be bowed outward (Figure 7e) or sagged inward (Figure 7f).

We have shown that three of the five Seidel aberrations (namely SA, coma, and astigmatism) are responsible for a lack of sharpness of the image. The other two (i.e., curvature of field and distortion) are related to the position and the form of the image. In general, it is impossible to design a system which is free from all the primary as well as the higher-order aberrations, and therefore, a suitable compromise as to their relative magnitude has to be made. In some cases, the effects of the Seidel aberrations are reduced by balancing them against aberrations of higher orders. In other cases, one has to eliminate certain aberrations completely, even at the price of introducing aberrations of other types. So far we have studied the aberration effects on the basis of geometrical optics only. However, if the aberrations are very small (wave aberrations of the order of a wavelength or less), diffraction starts to play an important role. That is why, in the next section, we will discuss the role of diffraction on the imaging quality of a lens.

Diffraction

Introduction

So far we have used simple geometrical optics to evaluate the effects of aberrations – deviations of the wavefront behind the lens from the ideal shape – that influence the quality of an image generated by a lens. However, we know that even for an aberration-free lens, blur of the spot in the image plane occurs. This means that diffraction effects at the lens aperture can also influence the spot size and the point spread function (PSF), certainly because diffraction gains importance when miniaturizing optical components. Therefore, we have to introduce diffraction before we can bring forward the most important figures of merit for microlens performance and study its effects on imaging quality.

Fraunhofer and Fresnel Diffraction

In certain regions of space occupied by our optical lens system, the simple geometrical model of energy propagation is inadequate. In particular, deviations from this model can be expected in the immediate vicinity of the boundaries of shadows and in regions where a large number of rays meet. These regions are of great practical interest, as they include that part of the image space in which the optical image is situated. These deviations are manifested by the appearance of diffraction fringes. Also, the phenomena involving the superposition of coherent wavefronts cannot be treated with a geometrical model of energy propagation. Thus a more accurate treatment is necessary where the wave nature of light and diffraction are taken into account. Wave optics is such an approach with which the actual light intensity, that will be observed as a result of the propagation of a wavefront to the image plane, can be constructed. According to Huygens' construction, every point of a wavefront may be considered as a center of secondary disturbance, which gives rise to spherical wavelets. The wavefront at any later instance may be regarded as the envelope of these wavelets. Fresnel was able to account for diffraction by supplementing Huygens' construction with the postulate that the secondary wavelets mutually interfere. We discuss diffraction here, on the basis of wave theory, by the application of Huygens' construction together with the principle of interference. The latter principle, also called the Huygens–Fresnel principle, sufficiently describes the propagation of light in free space.

This Huygens–Fresnel principle may be regarded as an approximate form of the integral theorem of Helmholtz and Kirchhoff. Kirchhoff's theory makes an approximation to the diffraction of scalar waves. This scalar theory is adequate enough for the treatment of problems in instrumental optics where polarization effects are of minor importance and can be neglected. If we consider a strictly monochromatic electric field $\varepsilon(x,y,z,t) = E(x,y,z)\cdot \mathrm{e}^{-\mathrm{i}\omega}$ in any ideal isotropic dielectric, the space-dependent part will satisfy the homogeneous time-independent wave equation: $(\nabla^2 + k^2)E = 0$, also known as the Helmholtz equation where $k = \omega/c$. This theorem expresses the solution E of the Helmholtz equation at an arbitrary field point P, in terms of its solution E and its first derivatives $\partial E/\partial n$ at all points on an arbitrary closed surface surrounding P, provided the medium is a homogeneous dielectric:

$$E(P) = -\frac{1}{4\pi}\oint\!\!\!\oint_S \left[E\bar{\nabla}\left(\frac{\mathrm{e}^{-\mathrm{i}ks}}{s}\right) - \frac{\mathrm{e}^{-\mathrm{i}ks}}{s}\bar{\nabla}E\right]\bar{n}\,\mathrm{d}S \tag{30}$$

Here, s is the distance from point P to the point on surface S, n is the outward normal to S, and $k = \omega/c$ is the wave number in vacuum.

When we consider a monochromatic wave, from a point source P_o propagating through an aperture Ω in a plane opaque screen, and P is the point at which the light disturbance has to be calculated, the theorem can be reduced to an approximate but much simpler form (Figure 13a) on condition that we can assume that the linear dimensions of the aperture Ω, although large compared to the wavelength, are small compared to the distances of both P_o and P from the screen.

As a result of Kirchhoff's theorem we obtain:

$$E(P) = \frac{\mathrm{i}A}{2\lambda}\int\!\!\int_\Omega \frac{\mathrm{e}^{-\mathrm{i}k(r+s)}}{rs}[\cos(n,r) - \cos(n,s)]\mathrm{d}S \tag{31}$$

where A is a constant, λ the wavelength, and r and s are the distances from element $\mathrm{d}S$ on Ω to P_o and P, respectively. Equation [31] is known as the Fresnel–Kirchhoff diffraction formula. In case a more general field E_o is incident at the aperture Ω, replacing the point source $A\,\mathrm{e}^{-\mathrm{i}kr}/r$, an equivalent formulation, known as the Huygens integral, can be found:

$$E(P) = \frac{\mathrm{i}}{\lambda}\int\!\!\int_\Omega E_\mathrm{o}(x_\mathrm{o}, y_\mathrm{o}, z_\mathrm{o})\frac{\mathrm{e}^{-\mathrm{i}ks}}{s}\cos(n,s)\mathrm{d}S \tag{32}$$



Figure 13 Geometry for evaluating (a) the Fresnel–Kirchhoff diffraction formula and (b) the Huygens' integral.

In the case of the Huygens integral an alternative Green's function is chosen, namely $G(P) = \exp(-jks)/s - \exp(-jkr)/r$ instead of $G(P) = \exp(-jks)/s$ used in the Fresnel–Kirchhoff diffraction formula. This then results in an obliquity factor $\cos(n,s)$ instead of $\cos(n,s) - \cos(n,r)$. If the distances of the points P_o and P are large compared to the dimensions of the aperture, the factor $[\cos(n,r) - \cos(n,s)]$ in eqn [31] will not vary appreciably over the aperture and may be replaced by 1. In this case, the optical beams are close to the optical axis and this is considered as the paraxial diffraction theory. In the phase factors, we can expand $r(x,y,z)$ and $s(x,y,z)$ as power series. If the quadratic and higher-order terms may be neglected in the series expansion $(r,s \gg \lambda)$, one speaks of Fraunhofer diffraction, when the previous assumption is not fulfilled $(r,s \geq \lambda)$, the quadratic terms cannot be neglected and one speaks of Fresnel diffraction. The regions where the Fresnel and Fraunhofer diffraction integral may be applied are called the near-field (NF) and far-field (FF) diffraction regions respectively. The Rayleigh range z_R marks the boundary between the NF and FF regions for the beam emerging from the aperture (Figure 14).

As an example, we discuss the diffraction of a uniform planewave by a circular aperture of diameter $2a$. The Rayleigh range for this circular aperture is given by

$$z_R = \frac{\pi a^2}{\lambda} \qquad [33]$$

The FF diffraction pattern $(z \gg z_R)$ for a uniformly illuminated circular aperture is the well-known Airy disk pattern and is given by



Figure 14 The Rayleigh range z_R marks the boundary between the NF and FF regions for a beam emerging from the aperture Ω.

$$E(r,z) \sim \frac{2J_1(2\pi a\theta/\lambda)}{(2\pi a\theta/\lambda)} \qquad [34]$$

where J_1 is the first-order Bessel function. This pattern has a single dominant central lobe surrounded by a series of increasingly weaker circular rings. The first zero of this pattern occurs at a half angle θ_1 or a radius r_1 in the FF, given by

$$\theta_1 = \frac{r_1}{z} \approx \frac{1.22\lambda}{2a} \qquad [35]$$

The NF or Fresnel diffraction patterns for a uniformly illuminated circular aperture $(z < z_R)$ consist of a series of circular rings modulating a constant-amplitude background. When moving even closer to the aperture, the beam profile becomes more and more square and the frequency of the Fresnel ripples increases.

We now know that light is diffracted at the apertures of optical elements (lenses) and that this diffraction can affect its performance. Ideally, the focus of a planewave should be infinitely small, being the image of a point source located at infinity. But even in the ideal case, when no geometrical aberrations are introduced, diffraction will limit the lens performance and the focus of such diffraction-limited lenses will have a finite extension.

Quality Criteria for Lens Performance

In this section we discuss some of the most important figures of merit for diffraction-limited lens performance. This survey raises the problems related to this issue. A more detailed overview can be found in the literature.

Diffraction in a Lens System: The Point Spread Function (PSF)

Diffraction at the lens aperture D causes a blur of the focus. The light distribution in the focal plane of an aberration free lens essentially arises from Fraunhofer diffraction at the aperture of the lens. From eqn [34] we know that the diffraction image for an aberration-free lens with a circular aperture D is the scaled Airy disk, given by

$$E(r,z) \sim \frac{\pi J_1(rD/\lambda f)}{(rD/\lambda f)} \qquad [36]$$

where λ denotes the wavelength of the illuminating light beam and f the focal length.

The normalized intensity of this pattern is called the diffraction-limited (PSF) of the lens:

$$\mathrm{PSF}(r,z) = |E(r,z)|^2 \qquad [37]$$

Although irradiance replaces nowadays the word intensity in optics, we will still use intensity to nominate the flow of energy per unit area per unit time. We can define the irradiance as $I \equiv \frac{1}{2}\varepsilon_0 c\langle \mathbf{E}^2\rangle$, with ε_0 and c the electric permittivity in vacuum and the speed of light, respectively. The radius of this pattern is known as the Rayleigh diffraction limit or Rayleigh resolution and is compared to the measured spot size in the image plane.

To include the effects of aberrations in the diffraction computation, we have to include both the phase profile and the amplitude of the real wavefront in the pupil of the lens. The pupil function $T(x,y)$ may be written as:

$$T(x,y) = E(x,y)\mathrm{e}^{\mathrm{i}k\psi(x,y)} \qquad [38]$$

where $E(x,y)$ represents the amplitude distribution over the exit pupil and $\psi(x,y)$ is the wavefront deformation on this pupil. Starting from the Huygens–Fresnel approach, the diffraction integral can be rewritten in the form of a Fourier transform:

$$E(r,z) \sim FT(\mathrm{e}^{\mathrm{i}k\psi(x,y)}) \qquad [39]$$

The PSF at the focal position can then be found by calculating the Fourier transform of the wavefront error ψ or the pupil function $T(x,y)$ of the lens and taking the complex square of the latter. Figure 15 shows the shape of the PSF of an ideal or diffraction-limited lens. When the lens aperture D decreases, the extension of the PSF increases proportionally, which means that it becomes easier to achieve diffraction-limited performance. Since the extension of the diffraction-limited PSF becomes larger, the constraints on the shape of the phase profile become less stringent. This has important consequences on the scaling behavior of lenses. In the extreme case, the microlens diameter becomes so small, that diffraction-limited imaging is possible without any specific phase profile in the lens pupil. This is also one of the reasons why small water droplets often form relatively good lenslets. For systems including micro-optic lenses, we therefore will have to find better criteria than the PSF of a diffraction-limited lens to evaluate or compare these optical components.

The Rayleigh and Maréchal Criterion

The widely used Rayleigh criterion states that a system is diffraction-limited, as long as the maximum wavefront deviation $|\psi_{\max}(x)|$ is less than one quarter of a wavelength (Figure 16). It was shown by Rayleigh that for a system which suffers primarily from SA such that the wavefront deviation is less than a quarter wavelength, the intensity at the Gaussian focus is diminished by less than 20%; a loss of light that can usually be tolerated. Also in the presence of other commonly occurring Seidel aberrations is the quality of the image not seriously affected when the deviation is less than λ/4. This criterion, which determines the amount of aberration that can be tolerated in an image-formation system is, of course, only a rough guideline since the light distribution in the image does not only depend on the maximum deformation but also on the shape of the wavefront, and even more on the type of aberration. Moreover, the loss of light that can be tolerated depends on the particular use to which the optical component is put and more stringent tolerances have to be imposed for certain applications.



Figure 15 The 1D point spread function of an ideal lens.



Figure 16 Illustration of the Rayleigh criterion.

Low-order aberrations merely cause a shift of light from the main lobe of the PSF to the side lobes. Higher-order aberrations additionally cause a broadening of the PSF and the correlation between the image quality and the maximum value of the wavefront aberration is usually lost. In the latter case, it seems more appropriate to formulate tolerance criteria restricting the average amount of aberration. Criteria of this type were considered by Maréchal, who used the relation that exists between the intensity at the center of the reference sphere and the RMS deviation of the wavefront from a spherical form.

This Maréchal criterion uses the following RMS wavefront aberration ψ_{RMS} to define the lens quality:

$$\psi_{\mathrm{RMS}} = \sqrt{\int |\psi(x)|^2\,\mathrm{d}x - \left[\int |\psi(x)|\mathrm{d}x\right]^2} \leq \frac{\lambda}{14} \qquad [40]$$

This criterion is sensitive to statistical noise on the measured phase profile, while a criterion such as the Rayleigh criterion is little affected by it.

Strehl Ratio

For some applications not the imaging quality but the maximum deposited energy is the most essential feature. In such a situation, the Strehl ratio S is a suitable figure of merit. The Strehl ratio is defined as the normalized peak intensity of the PSF of the lens:

$$S = \frac{I_{\mathrm{real}}(0,0)}{I_{\mathrm{ideal}}(0,0)} = \left| \int\int \mathrm{e}^{ik\psi(x,y)}\mathrm{d}x\,\mathrm{d}y \right|^2 \qquad [41]$$

$I_{\mathrm{real}}(0,0)$ and $I_{\mathrm{ideal}}(0,0)$ denote the intensities at the center of the real point image and the ideal PSF without aberrations, respectively. Even for small aberrations, which do not affect the extension of the PSF, the light intensity in the center peak can drop significantly (Figure 17). A Strehl ratio $S \geq 0.8$ is generally considered to correspond to diffraction-limited performance.

By a Taylor expansion of eqn [40], the relation between the Strehl ratio S and the Maréchal criterion can be written as:

$$S = 1 - \left(\frac{2\pi}{\lambda}\psi_{\mathrm{RMS}}\right)^2 \qquad [42]$$

If only low-order aberrations are taken into account, Rayleigh's $\lambda/4$ criterion also results in a Strehl ratio of $S = 0.8$. For large aberrations ($S \leq 0.3$), however, the behavior of the Strehl ratio becomes uncorrelated to the image quality due to interference effects.



Figure 17 Strehl ratio criterion.



Figure 18 Modulation transfer function for a perfect lens and for small amounts of spherical aberration (λ/2 and λ/4).

Transfer Functions

Transfer functions are most commonly used for evaluating the image quality in lens design. As discussed above, the PSF is the Fourier transform of the wavefront error ψ. For simplicity we can assume that the modulus of the pupil function is 1. The PSF then follows from the Fourier transform:

$$PSF(\mu,\nu) = |\mathrm{FT}(\mathrm{e}^{ik\psi(x,y)})|^2 \qquad [43]$$

The optical transfer function (OTF) is calculated from the PSF data by means of an inverse Fourier transformation:

$$\mathrm{OTF}(\vartheta,\rho) = \mathrm{FT}^{-1}[\mathrm{PSF}(\mu,\nu)] \qquad [44]$$

The OTF is a spatial frequency-dependent complex quantity whose modulus is the modulation transfer function (MTF) and whose phase is, of course, the phase transfer function (PTF). The former is a measure for the reduction in contrast from the object to the image over the whole spectrum. Figure 18 shows the normalized MTF for both a perfect lens and a lens subjected to some small amounts of spherical aberration. The PTF is, in most cases, not so conclusive concerning the optical behavior.

Therefore the wave aberrations, the PSF, the MTF, and the Strehl ratio are the characteristics that are usually provided as an output of lens design programs.

Interference

Many of the processes for the manufacturing of microlenses are not fully understood nor perfectly controlled. It occurs that one generates a microlens array and then measures its performance, hoping that by accurately repeating the processing conditions, a consistent result can be achieved. To achieve optimum conditions, it is therefore crucial to measure the geometrical and optical parameters of the microlenses. Most of the microlens measurement instruments are based on two-beam interference, the phenomena where light from a source is divided into two beams which are later on superposed again. The intensity in the region of superposition is found to vary from point to point between maxima which exceed the sum of the beam intensities and minima which may be zero.

Two-Beam Interference

We consider the interference of two waves, a reference and an object wave, represented by $\mathbf{E}_{\text{ref}}$ and $\mathbf{E}_{\text{obj}}$ respectively, where we take into account the vector properties of the electric fields. In the case of interference, both waves typically originate from a single source and recombine after traveling along different paths. For the moment we will consider only monochromatic linearly polarized waves of the form:

$$\mathbf{E}_{\text{ref}} = \mathbf{E}_{0\text{ref}}\, e^{i\Phi_{\text{ref}}(r) - i\omega t}, \quad \mathbf{E}_{\text{obj}} = \mathbf{E}_{0\text{obj}}\, e^{i\Phi_{\text{obj}}(r) - i\omega t} \qquad [45]$$

The total electric field intensity **E** at the output of the interferometer, according to the principle of superposition, is given by:

$$\mathbf{E} = \mathbf{E}_{\text{ref}} + \mathbf{E}_{\text{obj}} \qquad [46]$$

The total intensity at the output, being the time average of the square of the wave amplitude, can be written as

$$I = I_{\text{ref}} + I_{\text{obj}} + I_{\text{ref/obj}} \qquad [47]$$

with $I_{\text{ref}} \sim \langle \mathbf{E}_{\text{ref}}^2 \rangle$; $I_{\text{obj}} \sim \langle \mathbf{E}_{\text{obj}}^2 \rangle$ and $I_{\text{ref/obj}} \sim 2\langle \mathbf{E}_{\text{ref}} \cdot \mathbf{E}_{\text{obj}} \rangle$. Notice that if both **E**-fields are perpendicular to one another, the interference term $I_{\text{ref/obj}}$ vanishes, while if we assume that both fields are parallel, we can restrict our discussion to scalar theory. Under the latter condition we can write the total intensity as:

$$I = I_{\text{ref}} + I_{\text{obj}} + 2\sqrt{I_{\text{ref}} I_{\text{obj}}} \cos(\Phi_{\text{obj}} - \Phi_{\text{ref}}) \qquad [48]$$

where the presence of the third term is indicative of the wave nature of light which can produce enhancement or diminution of the intensity through interference.

We can rewrite eqn [48] in Michelson's manner of writing:

$$I = I_0(1 + V\cos(\Phi_{\text{obj}} - \Phi_{\text{ref}}))$$
$$\text{where } I_0 = I_{\text{ref}} + I_{\text{obj}}, \quad V = \frac{2\sqrt{I_{\text{ref}} I_{\text{obj}}}}{I_{\text{ref}} + I_{\text{obj}}} \qquad [49]$$

with V the visibility or fringe contrast indicating the degree of modulation.

We can conclude that the measured intensity of a two-beam interferogram depends on the mean intensity I_0, the visibility V, and the phase difference $\Phi_{\text{obj}} - \Phi_{\text{ref}}$. There are a number of techniques to measure the three unknowns: the mean intensity, the visibility, and the interesting spatial phase variation. In the optical instrumentation, further discussed in this article, phase shifting interferometry (PSI) is used which requires a measurement of the intensity in each point of the aperture for at least three different reference phase values, in order to obtain three equations for the three unknowns (I_0, V, and $\Phi_{\text{obj}} - \Phi_{\text{ref}}$). In practice, the reference phase values are obtained by a piezodriven transducer (PZT) mirror and should be equally spaced over one phase cycle of 2π. It has been shown that the five-phase algorithm is the optimal choice as the calculation still remains simple and the second-order nonlinear response of the detector is eliminated. A charge coupled device (CCD) sensor then records the intensity of the resulting interference pattern for different relative phase shifts and converts the intensity data to wavefront phase data through integration.

Microlens Testing

In microlens (lens with a diameter lower than several millimeters) testing, it is essential to measure in a first step the shape or the surface profile of the microlenses or in cases where gradient-index lenses are concerned, their refractive index distribution. In addition, the paraxial parameters, such as the focal length, and the more complex properties like the wave aberrations and surface quality have to be characterized. As discussed in the introduction, massive parallelism and miniaturization ask for the fabrication of microlenses and microlens arrays. The most critical features of these lenslet arrays are the uniformity of the microlenses and their mutual positioning accuracy. As a variation of these properties deteriorates the optical performance in most applications, dedicated test instrumentation is needed.

In the following, we discuss different measurement instruments designed to characterize all the geometrical and optical parameters of microlenses. First, we introduce an optical noncontact profiler which can be used to determine the diameter and the sag (the maximum height of the spherical lenscap) of the surface profile microlenses. In addition, it allows us to quantify the surface roughness on the top of the microlenses. With a transmission Mach–Zehnder (MZ) interferometer the wave aberrations and the focal length of the microlenses can be measured, while a Twyman–Green (TG) interferometer can be used for the measurement of the surface deviations of a microlens from an ideal spherical shape and for the measurement of the radius of curvature of the surface.

Surface Profile Measurements

Optical noncontact profiler

Principle. The surface profile of a microlens can be measured with a Wyko NT2000 noncontact optical profiler (Figure 19a). This surface profiler system uses two approaches to measure a wide range of surface heights. The PSI mode allows measuring fairly smooth and continuous surfaces ($0.1\text{ nm} <$ heights $< 160\text{ nm}$) while the vertical scanning interferometry (VSI) mode can measure rough surfaces and heights ranging between 160 nm and 2 mm. We only discuss here the vertical scanning mode because the principle on which PSI is based has been explained above. As shown in Figure 19b, this noncontact profiler is based on a Mirau interference microscope where a white light beam passes through a beamsplitter which reflects half of the incident beam to a reference surface and transmits the other half onto the sample. The light reflected from the sample and from the reference surface then recombine at the beamsplitter to form interference fringes. The system measures the degree of the fringe modulation or the fringe contrast. Because white light has a short coherence length, interference fringes are present only over a very shallow depth for each focus position. The coherence length can be described here as the optical path distance (OPD) between two wavefronts of an interferometric system for which the phase remains correlated. Or in other words it is a measure of the range of heights over which the instrument will be able to obtain measurable interference fringes. Fringe contrast at a single sample point reaches a peak as the sample is translated through focus. During a measurement, the reference arm containing the interferometric objective moves vertically to scan the surface at varying heights. A linearized PZT precisely controls this motion. As the system scans downward, an interference signal for each point on the surface is recorded. Finally, a series of advanced computer algorithms is used to demodulate the envelope of the fringe signal and to extract the surface information.

The vertical resolution is approximately 3 nm RMS for a single measurement. The lateral resolution is a function of the total magnification, of the cursor position accuracy, and of the detector array size.

Measuring the geometrical lens dimensions. This profiler provides us with information on geometrical dimensions of microlenses. For each microlens we can derive from the contour plot (Figure 20) the sag and the diameter of the microlenses along the x and the y direction. As an example, we show in Figure 21, the



Figure 19 (a) Vertical scanning noncontact profiler (WYKO NT2000); (b) Working principle.

profiles of the cross-section of a 200 μm fused silica microlens ($NA = 0.05$; $D = 200$ μm) along the x and y directions.

The surface roughness on top of the microlens can also be derived from measurements with the noncontact profiler. As an example, we show the fringes on the vertex area (65 × 61 μm^2) of a 200 μm diameter lens as well as the average and RMS roughness on the vertex of the lens (Figure 22).

Measurement of the Optical Lens Performance

To investigate the optical properties of discrete microlenses one of the most accurate and reliable techniques is interferometry. It is well known that microlenses can be tested in transmitted light using instruments with a single pass geometry (e.g., MZ interferometer) as well as in reflected light interferometers using a double pass configuration (e.g., TG interferometer). The interferometers proposed in this section have been especially designed and constructed for microlens testing.



Figure 20 Contour plot of a 200 μm fused silica microlens as obtained with the noncontact profiler.

Mach–Zehnder (MZ) interferometer for transmitted light measurements

Principle. A MZ interferometer, constructed at the Erlangen–Nürnberg University, is used in this work for the measurement of microlenses in transmitted light. The interferometer is installed in a commercial Carl Zeiss Jena microscope, while fiber-optics is used for beam delivery. The scheme is shown in Figure 23. A polarizing beamsplitter (PBS) cube splits the beam of a HeNe laser while a halfwave plate at the entrance enables the balancing of the two interfering beams. The fibers are polarization preserving in order to keep the polarization in the two beams of the interferometer. The planewave of the object arm is either focused by an illumination microscope objective so that a spherical wave impinges onto the microlenses (this is the so-called spherical wave illumination) or the first microscope objective is removed so that a planewave illuminates the object (this is the so-called planewave illumination). By using a telescope consisting of the imaging microscope objective and an achromatic doublet, the expanded planewave then enters a second beamsplitter and is superimposed on a reference planewave generated by the second fiber and an expansion lens. This second beamsplitter is a nonpolarizing one. To force the two beams to interfere, the plane of polarization of the reference beam must be rotated by 90° which is achieved by twisting the fiber end accordingly. This solution has been chosen to avoid a polarizer in front of the CCD camera as it has been shown that the latter would decrease the optical quality. In addition one of the mirrors in the object



Figure 21 (a) 2D lens profile of the microlens shown in Figure 20 along the x direction and (b) along the y direction.

Roughness values	(nm)
Average roughness R_1	1.55
RMS roughness R_q	1.94

(a)



Figure 22 (a) Different roughness values on the vertex area of a 200 μm lens; (b) Fringes in this vertex area (65 × 61 μm^2).



Figure 23 (a) Scheme and (b) picture of the Mach–Zehnder interferometer for measurements in transmitted light.

arm of the MZ is mounted on a PZT driver to enable phase shifting interferometry.

Focal length and array uniformity through plane-wave illumination. The MZ interferometer with planar wavefront illumination offers for slow lenses (NA < 0.1) the opportunity to measure also the total phase lag introduced by the lenses, as shown in Figure 24. This makes it possible to determine the focal length and hence the NA of the microlenses.

For certain applications of arrays of microlenses it is also important to know the uniformity of the lens array or at least of a part of the lens array. There are several different test methods (e.g., Smartt test, shearing test) which can provide a measure of the uniformity. One can even obtain the total phase retardation for a subsection of the microlens array (see Figure 25b).

Measuring the aberrations with spherical wave illumination. Wave aberrations of refractive microlenses can be determined with a spherical wavefront illumination (Figure 26). The measurement of the wave aberrations is carried out by using a PSI algorithm. This requires a measurement of the intensity in each point of the aperture for five different reference phase values. The result of a PSI evaluation is the phase distribution $\Phi(x, y)$ in the exit pupil:

$$\Phi(x, y) = \frac{2\pi}{\lambda}\psi(x, y) \qquad [50]$$

where $\psi(x, y)$ are the wave aberrations of the lens under test.

From these data, the software calculates the unwrapped phase distribution and by subtracting the tilt and defocus, the deviation from an ideal wavefront (phase/lambda) can be found. Fitting this deviation to a fourth degree Zernike polynomial then gives the aberrations (phase/lambda). Besides the aberrations we also derive from the measured phase distribution other optical lens characteristics such as the modulation transfer function and the PSF.

Finally, we emphasise that the measurements should preferably be done in a cleanroom environment as the smallest dust particle on the lens surface decreases the optical performance.

Twyman–Green interferometer

Principle. For most applications microlenses have to feature a spherical or nearly spherical shape. The measurement of the deviations of the microlens surface from an ideal sphere is therefore very important. The basic principle comes down to a planewave which is focused by a high NA microscope objective in such a way that the focus coincides with the center of curvature of the microsphere under test. The light rays are reflected, and behind the microscope objective a nearly planewave carrying the surface deviations and misalignment errors, results. The vertex of the test surface is then imaged onto a CCD camera and the nearly plane object wave interferes with the plane reference wave. The evaluation here is also done with phase shifting interferometry by axially shifting the reference mirror with a piezo transducer.



Figure 24 Interferogram of a 200 μm lens with an NA of 0.05 under planewave illumination.

The use of laser illumination allows us to obtain high contrast fringes. However, the high spatial and temporal coherence of the laser light also has important drawbacks, such as speckle noise and spurious fringes across the field. It is convenient to divide coherence into two classifications, temporal and spatial. The former relates directly to the finite bandwidth of the source, the latter to its finite extent in space. Therefore, polarization beamsplitter optics is commonly used to reduce the contribution of spurious reflections. The polarizing beamsplitter group additionally allows balancing the intensity between the object and the reference arm of the interferometer. Even so, the remaining scatter leads to poor and rough interference fringes. To further increase the fringe quality, the spatial coherence has to be reduced while the temporal coherence of the laser is preserved. This can be done by introducing a rotating scatterer in the light beam which gives a smoothing effect of the interference fringes.

Measurement of the deviations from sphericity. To determine the surface deviation of a microlens from a perfect sphere we make use of a TG



Figure 25 (a) Interferogram of an array of 200 μm diameter microlenses with an average NA of 0.05 and illuminated with a plane wavefront; (b) 3D representation of the phase lag (RMS 1.26λ, *PV* 4.37λ) for the same microlens array.

interferometer, constructed by the Erlangen-Nürnberg University (Figure 27). In this interferometer, the light of a HeNe laser is imaged onto a rotating scatterer by a microscope objective and the scattered light is collimated by an achromat. The collimated laser beam then passes a field stop which is sharply imaged by a 4f system onto the lens under test. The image of the field stop can be focused onto the surface under test by moving the field stop along the optical axis. Once the image of the field stop is sharply imaged onto the CCD array, one can translate the reference mirror until the reference image of this stop in its turn becomes sharp onto the CCD camera. Thus, two conditions have to be met to achieve high contrast fringes: the surface under test and the image of the field stop of both arms of the interferometer have to be sharp on the detector. The half wave plate in front of the PBS adjusts the splitting ratio at the PBS while the polarizer after the beamsplitter is necessary to force the two orthogonally polarized beams to interfere. Finally, the optics at the output of the interferometer gives a sharp image of the intermediate image of the lens surface onto the CCD camera. Analogous to the MZ interferometer, five phase images are grabbed and subjected to different algorithms, leading to the desired information.



Figure 26 Interferogram of a microlens under spherical wavefront illumination: the resulting planewave is a measure for the wave aberrations.

A condensor objective transforms the radius of curvature of the spherical wavefront such that it matches the radius of curvature of the microlens. Hence, the wavefront impinges everywhere perpendicularly on the lens surface. This means that the sensitivity to surface deviations is independent on the surface position leading to high accuracy measurements. The TG interferometer allows us to test the sphericity of microlenses with diameters ranging


(a)
(b)
HeNe Laser
Rotating ground glass
4f imaging optics Tessar lenses f = 115 mm
Field stop
Second intermediate image
CCD
Tessar lens f = 155 mm
Zoom objective
f_{mn} = 12.5 mm
f_{mn} = 75 mm
4f imaging optics Achromatic doublets f = 160 mm
Pol
PBS
λ/2
λ/4
PZT
λ4
Microscope objective 100x : 0.8
Microspheres
First intermediate image

Figure 27 (a) Twyman–Green interferometer setup. (b) Detailed schematic overview of this interferometer.



Figure 28 (a) Measured deviation from an ideal sphere (phase/lambda) for a 200 µm lens with an NA of 0.05 as obtained with a Twyman–Green interferometer. (b) Polynomial fitted surface deviation (phase/lambda) of this microlens.



Figure 29 Necessary adjustments of the spherical microlens for radius measurements.

from 50 to 1000 µm and with a maximum radius of curvature of 1960 µm.

An example of a 200 µm fused silica microlens, with an NA of 0.05, is shown in Figure 28. The deviation from an ideal sphere can be derived from the unwrapped phase after subtracting the tilt and defocus. Fitting the deviation to a fourth degree Zernike polynomial then gives the surface deviation.

Measuring the radius of curvature. Using the TG interferometer it is also possible to determine the radius of curvature R of a microlens. To do this, the test object has to be shifted axially from the basic position, where the light rays impinge perpendicularly onto the surface and the focal length of the condensor objective coincides with the center of the sphere under test, to the so-called cat's eye position, where the focus of the impinging spherical wave is at the vertex of the sphere (Figure 29). For both positions straight, parallel, and equidistant interference fringes are obtained, only perturbed by aberrations due to the lens surface and the condensor objective. This forms the criterion for the adjustment of the two positions. The difference between these two positions then gives the radius of the microsphere. It should be mentioned that the cat's eye position causes an inversion of the object wavefront with respect to the reference wavefront, which results in a vanishing contrast with the partially coherent illumination. The latter can only be avoided by providing the necessary coherence. This implies that the rotating scatterer will have to be removed.

Summary of the Interferometric Instrumentation

Figure 30 summarizes the various instruments we discussed in this section: a noncontact optical profiler, a MZ and a TG interferometer. For each of these instruments, we highlight the measurands, the assumptions that are made, and the resulting optical lens characteristics. From this figure, it is clear that one can obtain a measure for the focal length and hence the numerical aperture and the focal number of a refractive microlens, with all three instruments. However, only the focal length obtained with the MZ interferometer is a direct measurement. The focal length obtained with the optical profiler is derived from the sag of the lens under the assumption of an ideal sphere while the radius of curvature measured with the TG interferometer allows to calculate the focal length as well. Nevertheless, the three values make an interesting comparison possible.


Instrumentation
Measurands
Assumptions
Derived optical lens characteristics
Noncontact optical profiler
Sag h
Diameter D
Pitch P
Ideal sphere
Constant n
Radius of curvature R
Focal length f
Numerical aperture NA
Focal number f#
Mach–Zehnder interferometer
5 phase-shifted interferograms
Planewave illumination
Focal length f
Numerical aperture NA
Focal number f#
Spherical wave illumination
Unwrapping subtracting tilt & defocus
Deviation from an ideal wavefront
Polynomial fit
Wave aberrations
MTF, PSF, Strehl ratio
Twyman–Green interferometer
5 phase-shifted interferograms
Unwrapping subtracting tilt & defocus
Deviation from an ideal sphere
Polynomial fit
Surface deviation
Radius of curvature R
Constant n
Focal length f
Numerical aperture NA
Focal number f#
Comparison

Figure 30 Overview of the instruments that we will use to quantitatively characterize the refractive microlenses: the measurands and the resulting optical lens characteristics.

Conclusions

In this article we introduced geometrical optics to discuss the imaging properties and the aberrations of refractive lenses, while wave optics was used to explain the effects of diffraction on the imaging properties of lenses. Next we put forward some commonly used quality criteria to assess lens performance and we pointed out the unique properties of microlenses. Finally, interference was briefly introduced to clarify the working principle of various instruments to quantitatively characterize refractive microlenses and microlens arrays: a noncontact profiler, a transmission MZ interferometer and a TG interferometer.

We can conclude that micro-optics is a key technology with many applications in various areas of tomorrow's information society. It enables new functionalities and applications previously unachievable with conventional optics and improves product performance, stability and robustness while reducing cost, volume, and weight. While in conventional optics discrete lenses are mounted to form optical systems using mechanical alignment equipment, for microlenses new integration approaches are available. For most of the applications, the integration of micro-optical components into fully functional systems is very important.

Thus micro-optics is a generic technology that allows the manipulation of light with micron and submicron scale structures and components. Micro-optics is therefore the technology to help provide the necessary tools to interface the macroscopic world we live in with the microscopic world of opto- and nano-electronic data processing. Micro-optic processing and fabrication technologies can be adapted to a wide variety of specialty optical materials such as plastics, polymers, semiconductors, sol-gels, and doped glasses. The application of these modified materials permits the widening of the field of photonic functionalities to virtually any region of the optical spectrum and beyond, such that a wealth of novel optical and photonic applications can be realized. Micro-optic processing technologies can be made compatible with scalable industrial mass-manufacturing and replication techniques.

Acknowledgment

This research has been made possible through the financial support of the Fund for Scientific Research-Flanders (FWO-Vlaanderen), the IAP Photon

Network, the Bilateral Scientific and Technological Cooperation Flanders-Poland, the Institute for the Promotion of Innovation by Science and Technology in Flanders (IWT), the IWT GBOU project 'Generic Technologies for Plastic Photonics', the Research Council (OZR) of the Vrije Universiteit Brussel and the EC Network of Excellence NEMO.

List of Units and Nomenclature

[AB]	optical path length
c	speed of light
d	lens thickness
D	lens aperture diameter
$\mathbf{E}$	electricfield
f	focal length
f_{BFL}	back focal length
f_{FFL}	front focal length
$f\#$	focal number
F_{i}	image focal point
F_o	object focal point
h_1	position of the first principal point relative to the vertex V1
h_2	position of the second principal point relative to the vertex V2
h'	deviation from the optical axis
H_1	first principal point
H_2	second principal point
I	intensity
k	wave number in vacuum
n	index of refraction
n_{i}	index of refraction of medium i
O	object point
P	arbitrary field point
P	image point
P	lens pitch
$\wp$	spherical surface power
r	aperture of the refracting surface
R	radius of curvature
$R(x, y)$	real wavefront
S	axial object point
S	Strehl ratio
s_0	object distance
s_i	image distance
V	lens vertex
V	visibility or fringe contrast
$W(x, y)$	spherical wavefront in the Gaussian approximation
y_{o}	object height
y_{i}	image height
z_{R}	Rayleigh range
α	angular semi-aperture
θ	symmetry around the optical axis
λ	wavelength of light
σ	standard deviation
φ_1	angle between the incident ray and the normal to the flat surface
φ_2	angle between the refracted ray and the normal to the flat surface
$\Phi_{\mathrm{obj}} - \Phi_{\mathrm{ref}}$	phase difference
$\Phi(x, y)$	phase distribution
$\psi(x, y)$	wavefront aberration
ω	angular frequency
Ω	aperture in a plane opaque screen
BFL	Back focal length
CCD	Charge coupled device
FF	Far-field
FFL	Front focal length
MTF	Modulation transfer function
MZ	Mach–Zehnder
NA	Numerical aperture
NF	Near-field
OPD	Optical path difference
OTF	Optical transfer function
PBS	Polarizing beamsplitter
PP	Principal plane
PSF	Point spread function
PSI	Phase shifting interferometry
PTF	Phase transfer function
PZT	Piezo-electric transducer
RMS	Root mean square
SA	Spherical aberration
VSI	Vertical scanning interferometry

See also

Diffraction: Fraunhofer Diffraction. **Diffractive Systems:** Aberration Correction with Diffractive Elements. **Geometrical Optics:** Aberrations; Lenses and Mirrors. **Interferometry:** Overview; Phase Measurement Interferometry.

Further Reading

Born M and Wolf E (1999) *Principles of Optics*, 7th edn. Cambridge, UK: Cambridge University Press.

Hecht E (1987) *Optics*. San Francisco, CA: Addison-Wesley Publishing Company.

Herzig HP (1997) *Micro-Optics: Elements, Systems and Applications*. London: Taylor & Francis.

Jenkins FA and White HE (1981) *Fundamentals of Optics*, 4th edn. New York: McGraw-Hill.

Malacara D and Malacara Z (1994) *Handbook of Lens Design*. New York: Marcel Dekker.

Malacara D, Servin M and Malacara Z (1998) *Interferogram Analysis for Optical Testing*. New York: Marcel Dekker.

Mouroulis P and Macdonald J (1997) *Geometrical Optics and Optical Design*. New York: Oxford University Press.
Pedrotti FL and Pedrotti LS (1993) *Introduction to Optics*, 2nd edn. Englewood Cliffs: Prentice-Hall International.
Shannon RR (1997) *The Art and Science of Optical Design*. Cambridge, UK: Cambridge University Press.
Siegman AE (1986) *Lasers*. Sausalito: University Science Books.
Sinzinger S and Jahns J (1999) *Microoptics*. Weinheim, Germany: Wiley-VCH GmbH.
Smith WJ (1997) *Practical Optical System Layout and Use of Stock Lenses*. New York: McGraw-Hill.
Smith W (2002) Engineering an optical system. *SPIE OE Magazine* 7: 49–54.
Young HD (1992) *Physics*, 8th edn. San Francisco, CA: Addison-Wesley Publishing Company.

OPTICAL PARAMETRIC DEVICES

Contents

Overview
Optical Parametric Oscillators (Continuous Wave)
Optical Parametric Oscillators (Pulsed)

Overview

B J Orr, Macquarie University, Sydney, Australia

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Many forms of optical parametric device (OPD) play significant roles as three-wave nonlinear-optical sources of tunable coherent light for laser-based science and technology. Any such device will fall into one of three categories, in increasing order of sophistication: optical parametric generator (OPG); optical parametric amplifier (OPA); and optical parametric oscillator (OPO). This article concentrates largely on nanosecond-pulsed OPOs, with particular emphasis on designs that facilitate their wavelength control and their optical power- or energy-efficiency. The two other important temporal manifestations of OPOs (ultra-fast pulsed and continuous-wave) are briefly outlined. OPDs serve as versatile sources of tunable, intense, coherent radiation covering the infrared, visible, or ultraviolet spectral regions. Their most obvious uses are associated with laser wavelength-conversion and/or tunability, resulting in a variety of spectroscopic applications. Four-wave nonlinear-optical parametric contributions, such as those involved in stimulated Raman scattering and highly nonlinear optical fibers, are also briefly considered.

What is an Optical Parametric Device?

An optical parametric device (OPD) is a source of coherent, laser-like radiation that is typically intense and tunable over a wide range of wavelengths. Its mechanism invariably depends on nonlinear optics, usually through a three-wave mixing process mediated by the nonlinear-optical susceptibility $\chi^{(2)}$ in a noncentrosymmetric crystalline medium. Three forms of OPD are illustrated in Figure 1, and also illustrated is a closely related (but distinct) nonlinear-optical device. Coherent light waves are represented by arrows, with their associated optical frequency ω_j and wave vector $\mathbf{k}_j$ (which are defined below). In Figure 1, input and output waves are shown as arrows on the left and right, respectively, with their breadth intended to indicate typical relative intensities.

An optical parametric generator (OPG) is the simplest form of OPD, with a single input wave (pump, P) from a laser generating two coherent output waves (signal, S; idler, I; $\omega_S \geq \omega_I$), as depicted in Figure 1a. The nonlinear-optical process itself is initiated by low-intensity parametric spontaneous emission/noise/fluorescence processes that occur naturally, effectively 'splitting' a pump photon into two new photons. Once a signal and/or idler wave has been generated, it can be coherently amplified by passing it through an optical parametric amplifier (OPA) together with input pump radiation, as depicted in Figure 1b. A further order of sophistication is reached in an optical parametric oscillator (OPO), as depicted in Figure 1c, where the



Figure 1 Schematic diagrams of three forms of optical parametric device (OPD): (a) optical parametric generator (OPG); (b) optical parametric amplifier (OPA); (c) optical parametric oscillator (OPO). Note that, by convention, optical frequencies of the signal (S) and idler (I) output waves are defined such that $\omega_S \geq \omega_I$. Also shown is a fourth closely related device: (d) difference-frequency generator (DFG). Nonlinear-optical media are denoted by their susceptibility $\chi^{(2)}$. Arrows are used to represent input and output waves, together with their optical frequencies ω_j and wave vectors $\mathbf{k}_j$. An OPO requires an optical resonator, comprising at least two aligned reflectors (M_1, M_2).

functions of an OPG and an OPA are combined by multipassing the optical waves involved inside a resonant optical cavity, formed by two or more appropriately aligned reflectors (M_1, M_2).

A difference frequency generator (DFG), as depicted in Figure 1d, is not an OPD, although the DFG source term is central to the nonlinear-optical mechanism of an OPD. In a DFG, two input waves (labeled 1 and 2) are combined coherently to generate a third output wave at the difference frequency of the two input waves: there are now two relatively high-power driving waves, rather than one, and photons are effectively 'joined', rather than 'split' as in the OPD case. Nevertheless, the outcome and utility of a DFG can be similar to that of an OPD. For instance, if coherent radiation is required at a particular infrared (IR) wavelength, it can be generated either as the idler wave of an OPD, with frequency $\omega_I = (\omega_P - \omega_S)$ *or* as the output wave of a DFG, with frequency $\omega_3 = |\omega_1 - \omega_2|$.

Many of the desirable attributes of OPDs in general, and OPOs in particular, arise from the fact that any such instrument is a nonlinear-optical device, not a laser. This allows versatile, flexible design features, such as methods of temporal and wavelength control that are not possible with lasers. The latter generally depend on population inversion of an optical gain medium, with associated optical lifetime and saturation limitations. On the other hand, optical parametric gain, oscillation and amplification are more amenable to modular system design because (as is explained below) they depend on nonlinear-optical coefficients and phase-matching conditions.

Nonlinear-Optical Origins of OPDs

Nonlinear optics involves interaction of a number ($\sigma > 2$) of optical waves in a medium with a nonlinear-optical susceptibility tensor $\chi^{(\sigma-1)}$. For inelastic optical processes, these waves (each with an angular frequency $\omega_1, \omega_2, \ldots, \omega_\sigma$) obey two conservation conditions, one for energy (or frequency):

$$\omega_1 + \omega_2 + \ldots + \omega_\sigma = 0 \qquad [1]$$

The other conservation condition (expressed in terms of wave vectors $\mathbf{k}_i$, with $i = 1, 2, \ldots, \sigma$, that have magnitudes $k_i = n_i\omega_i/c = 2\pi n_i/\lambda_i$, where n_i is the refractive index at vacuum wavelength λ_i and c is the speed of light) is for momentum:

$$\mathbf{k}_1 + \mathbf{k}_2 + \ldots + \mathbf{k}_\sigma + \Delta\mathbf{k} = 0 \qquad [2]$$

where $\Delta\mathbf{k}$ is the phase-mismatch between the σ interacting waves. Each frequency component and wavevector is ascribed a positive or negative sign, according to their phase relationships. Equation [2] defines phase-matching conditions in which $\Delta\mathbf{k}$ must be minimized to optimize the efficiency of the nonlinear-optical process of interest.

We shall consider below the two specific three-wave nonlinear-optical processes that are particularly relevant to this article, namely, those for an OPD (i.e., OPG, OPA, or OPO) or a DFG. Each of these is mediated by the nonlinear-optical susceptibility tensor $\chi^{(2)}$, which is nonzero in a crystalline medium only if it is noncentrosymmetric. Many such crystals are available. For example, lithium niobate ($LiNbO_3$) has been popular since the early days of pulsed tunable OPOs. Subsequent interest and activity in OPD technology have been stimulated by the availability of new nonlinear-optical materials such as BBO (β-barium borate, BaB_2O_4) and KTP (potassium titanyl phosphate, $KTiOPO_4$).

Additional recent impetus has come from quasi-phase-matched (QPM) nonlinear-optical media, such as periodically poled lithium niobate (PPLN) and PPKTP, tailored for specific wavelengths by periodic optical structuring of domains. QPM media offer compact, efficient, low-threshold alternatives to conventional birefringently phase-matched (BPM) media. Characteristics of BPM and QPM nonlinear-optical crystalline media are accessible *via* Arlee Smith's SNLO software package, accessible by internet at www.sandia.gov/imrl/XWEB1128/xxtal.htm.

For a three-wave OPD, which is of principal interest in this article, the energy and momentum conservation conditions of eqns [1] and [2] become:

$$\omega_\mathrm{P} - \omega_\mathrm{S} - \omega_\mathrm{I} = 0, \qquad \mathbf{k}_\mathrm{P} - \mathbf{k}_\mathrm{S} - \mathbf{k}_\mathrm{I} - \Delta\mathbf{k} = 0 \qquad [3]$$

where a laser input wave ('pump', frequency ω_P, wave vector $\mathbf{k}_\mathrm{P}$) yields two coherent output waves ('signal', frequency ω_S, wave vector $\mathbf{k}_\mathrm{S}$; 'idler', frequency ω_I, wave vector $\mathbf{k}_\mathrm{I}$; $\omega_\mathrm{S} \geq \omega_\mathrm{I}$). Note that the idler frequency ω_I equals the difference $|\omega_\mathrm{P} - \omega_\mathrm{S}|$ between pump and signal frequencies. Equation [3] should be viewed in the context of sections (a–c) of Figure 1.

Equation [2] and the second half of eqn [3] apply strictly only to the conventional case of BPM media. In such media, the phase-matching condition $\Delta\mathbf{k} \approx 0$ is achieved by adjusting the angle and/or temperature of a birefringent nonlinear-optical crystal *via* its ordinary- and extraordinary-ray refractive indices. Such adjustments are used to optimize OPD conversion efficiency and thereby control the output signal and idler wavelengths, λ_S and λ_I. If it is assumed that the three waves are collinear and that $\Delta\mathbf{k}$ is exactly zero, then the signal frequency/wavelength is given simply in terms of the pump frequency/wavelength and the refractive indices n_i $(i = P, S, I)$ as:

$$\begin{aligned} \omega_\mathrm{S} &= \omega_\mathrm{P}(n_\mathrm{P} - n_\mathrm{I})/(n_\mathrm{S} - n_\mathrm{I}); \\ \lambda_\mathrm{S} &= \lambda_\mathrm{P}(n_\mathrm{S} - n_\mathrm{I})/(n_\mathrm{P} - n_\mathrm{I}) \end{aligned} \qquad [4]$$

An alternative to birefringent phase matching is the quasi-phase-matching approach first suggested by Nobel Laureate Nicolaas Bloembergen and co-workers in 1962. This approach has been realized experimentally only in the last few years, *via* QPM nonlinear-optical media such as PPLN or PPKTP. Equation [2] and the second half of eqn [3] need to be slightly modified to include QPM grating contributions.

In the corresponding case of a DFG (which, we repeat, is not an OPD), the energy and momentum conservation conditions of eqns [1] and [2] become:

$$\begin{aligned} |\omega_1 - \omega_2| - \omega_\mathrm{diff} &= 0, \\ \mathbf{k}_1 - \mathbf{k}_2 - \mathbf{k}_\mathrm{diff} - \Delta\mathbf{k} &= 0 \end{aligned} \qquad [5]$$

where two laser input waves (frequencies ω_1, ω_2; wave vectors $\mathbf{k}_1$, $\mathbf{k}_2$) yield one coherent output wave at the difference frequency $\omega_\mathrm{diff} = |\omega_1 - \omega_2|$ (with wave vector $\mathbf{k}_\mathrm{diff}$), as depicted in Figure 1d. As above, phase matching is defined by $\Delta\mathbf{k} \approx 0$ for BPM media and, in the case of QPM media, there is an additional grating contribution in the second half of eqn [5].

Finally, we mention briefly two other important forms of nonlinear-optical device arising from four-wave mixing processes that are mediated by the nonlinear-optical susceptibility $\chi^{(3)}$ which can be non-zero, even in isotropic or centrosymmetric media such as gases, liquids, optical fibers, and all classes of crystal. Optical parametric processes of this type contribute to stimulated Raman scattering (SRS), involving an optical medium with Raman-active resonance frequencies ω_R that coincide with the difference between two optical frequencies. This is particularly useful in providing a relatively straightforward source of coherent radiation, Raman-shifted at discrete intervals from the frequency ω_L of an input pump laser (either tunable or fixed-wavelength). Four-wave parametric processes are involved, such as that in eqn [1] with $|\omega_1| = |\omega_3| = \omega_\mathrm{L}, |\omega_2| = \omega_\mathrm{L} - \omega_\mathrm{R}$, and $|\omega_4| = |\omega_1| + |\omega_3| - |\omega_2| = \omega_\mathrm{L} + \omega_\mathrm{R}$, where ω_R is the characteristic Raman frequency of the nonlinear-optical medium used in the Raman shifter (e.g., high-pressure hydrogen, deuterium or methane gas). These Raman-shifted intervals, both added to (anti-Stokes) and subtracted from (Stokes) the laser frequency ω_L, are integer multiples of ω_R. Other nonlinear-optical Raman parametric processes give rise to various forms of nonlinear Raman spectroscopy, such as CARS (coherent anti-Stokes Raman spectroscopy), and to Raman fiber-optical amplifiers, used in optical telecommunications.

Another promising area of developing OPD technology entailing $\chi^{(3)}$ nonlinearities concerns OPGs, OPAs, and OPOs based on highly nonlinear optical fibers, with either pulsed or cw pump lasers. Such processes use two pump waves (P) to generate tunable signal (S) and idler (I) output waves, such that $\omega_\mathrm{I} = 2\omega_\mathrm{P} - \omega_\mathrm{S}$.

Nanosecond-Pulsed OPOs – Design and Wavelength Control

Here we consider pulsed OPOs that operate on nanosecond (ns, 10^{-9} s) time-scales, and design

Table 1 Some elements of OPO applications to spectroscopy

Key properties	*Options*	*Comments on instrument/technique*
Wavelength range: what forms of spectra need to be measured?	UV/visible (0.2–0.7 μm) Near IR (0.7–4.0 μm) Longwave IR (>4.0 μm)	Many nonlinear-optical OPO materials are available, but less well developed for longwave IR applications
OPO phase matching: BPM or QPM?	Birefringent phase matching (BPM) Quasi-phase matching (QPM)	BPM is well established and preferred for high-power operation. Various low-threshold QPM media are now available for both pulsed and cw OPOs
Temporal: continuous-wave (cw) or pulsed?	Pulsed for power and timing Cw for narrowest bandwidth	Ultrafast (ps, fs) OPO output pulses are relatively broadband, owing to the Fourier transform limit
Optical bandwidth: broad or narrow?	Broadband (free-running) Single longitudinal mode	The Fourier transform limit is 44 MHz (0.0015 cm^{-1}) for an ideal 10 ns pulse Cw OPOs offer even lower $\Delta\nu$. Ultrafast-pulsed OPOs are inevitably broadband: e.g., $\Delta\nu \geq 0.44$ THz ($\geq$15 cm^{-1}) for a 1 ps pulse
Mode of recording of spectra: continuous tuning or multiplex?	Scan narrowband signal/idler OPO output wavelength Free-running OPOs operate broadband in multiplex case	Wavelength control yields continuously tuned narrowband spectra. Multiplex spectra use dispersed detection or multi-wavelength spectroscopic tailoring
Wavelength control: intracavity elements or injection seeding?	Intracavity gratings or étalons Injection seeding of signal or idler by a tunable low-power coherent light source	Intracavity-element designs yield broad tunability but can be complicated. Injection seeding facilitates narrowband, mode-hop-free spectra and tailored multi-wavelength experiments

The above options determine ways to use OPOs for spectroscopic applications, such as: (1) linear absorption (e.g., with a multipass cell); (2) cavity ringdown (CRD) absorption spectra; (3) high-resolution spectra ($\Delta\nu \approx$ MHz or kHz); (4) nonlinear-optical (e.g., coherent Raman); (5) atmospheric remote sensing (e.g., DIAL); (6) fast (μs, ns) and ultrafast (ps, fs) processes.



Figure 2 Schematic diagrams of three forms of optical parametric oscillator: (a) free-running OPO (with no active wavelength control), similar to Figure 1c; (b) OPO with an intracavity tuning element (T); (c) injection-seeded OPO.

features that make them fit for one of the principal applications of OPDs, namely, spectroscopy. Options that determine ways to use OPOs for spectroscopic applications are summarized in Table 1. Some design and wavelength-control features used in ns-pulsed OPOs are depicted schematically in Figure 2. Some of these applications and features are shared with other forms of OPO, notably the ultrafast-pulsed OPOs and cw OPOs that are considered much more briefly in later sections.

The first OPO, demonstrated by Giordmaine and Miller in 1965, was ns-pulsed; it was based on $LiNbO_3$, tunable over the range ~0.96–1.16 μm, spanning a signal- and idler-wavelength range of ±0.1 μm on either side of the degeneracy point defined by the 529 nm pump radiation (from a frequency-doubled, Q-switched Nd:$CaWO_4$ laser). This advance occurred soon after lasers were discovered and the potential of nonlinear optics had been realized through harmonic-generation processes such as frequency doubling. Pioneering work by Stephen Harris, Robert Byer and their co-workers at Stanford University soon established ns-pulsed OPOs as practical sources of tunable coherent light for significant applications such as spectroscopic sensing of chemical processes, in industrial or environmental diagnostics and in basic science. Such ns-pulsed OPOs had an impressive impact in the 1970s, followed by sporadic progress in much of the 1980s, and a dramatic resurgence of interest and activity since the late 1980s.

This irregular rate of progress is attributable to the availability of suitable high-quality nonlinear-optical crystals (as mentioned above), as well as high-performance pump lasers and advanced tunable OPO system designs.

In a typical ns-pulsed OPO, the pump laser delivers sufficient optical energy to enable parametric gain to build up from noise during the pump–pulse duration, exceeding the threshold for oscillation. To maximize gain, the parametric (signal and/or idler) waves are amplified by multipassing them during the pump pulse in an optical resonator, as depicted in Figures 1c and 2. Light travels ~3 m during a 10 ns pump pulse, so that the parametric waves can make ~15 round trips of a 10 cm linear OPO cavity.

A simple free-running OPO, comprising an optical cavity with input and output mirrors M_1 and M_2 but with no wavelength-selective elements, is depicted in Figure 2a. The output radiation from such an OPO generally has a relatively broad optical bandwidth – typically ~5 cm^{-1} (~150 GHz) or more – depending on several factors: refractivity, dispersion, and absorption of the OPO medium; wavelengths λ_P, λ_S, and λ_I; type of phase matching (BPM or QPM, whether collinear or not); crystal dimensions and orientation; cavity reflectivity and effective number of passes of the resonated wave; optical bandwidth, divergence, pulse duration and pulse energy of the pump radiation. Free-running pulsed OPOs represent one extreme of operational simplicity, yielding relatively broadband output radiation suitable for low-resolution or multiplex spectroscopy. Additional OPO wavelength-control measures are usually necessary for higher-resolution spectroscopic applications.

At the other extreme of operational complexity, intracavity wavelength-selective elements, such as gratings and/or étalons, provide a traditional way to control OPO output wavelength and to achieve narrow optical bandwidths. One such approach is depicted in Figure 2b, where a tuning element T (in this case, a tilted étalon or filter; in other designs, an intracavity diffraction grating replacing the output cavity mirror M_2) is inserted in the cavity. Such approaches were used in early pulsed $LiNbO_3$ OPO designs that were continuously tunable in the near IR with an optical bandwidth of ~0.1 cm^{-1} (~3 GHz), but these were often difficult to operate and were damage-prone (with intracavity losses from gratings and étalons causing the operating threshold to approach the damage threshold of OPO nonlinear-optical materials such as $LiNbO_3$).

Continuous narrowband tunability, preferably on a single-longitudinal-mode (SLM) basis, is a desirable performance characteristic of pulsed OPOs amenable to high-resolution spectroscopy. A commercially viable approach to this ideal was achieved by Walter Bosenberg and Dean Guyer in their advanced KTP OPO/OPA system, which includes a master OPO stage with a grazing-incidence grating. This is continuously tunable under computer control in the near IR (1.3–4 μm) with narrow optical bandwidth – ~0.02 cm^{-1} (~600 MHz) or better. Such a high-performance tunable coherent IR source has been used for various forms of laser spectroscopy (cavity ringdown, degenerate four-wave mixing, long-path absorption, etc.), including investigations of chemically reactive media, combustion diagnostics, and studies of processes in molecular beams.

A popular alternative approach to OPO wavelength control is injection seeding by a low-power tunable coherent source such as a tunable diode laser (TDL). This approach is depicted in Figure 3; in practice, a ring cavity is often used to avoid



Figure 3 Schematic diagram of an injection-seeded tunable PPLN OPO system with active cavity control, developed in the author's laboratory. Legend: PD = photodetector, PZT = piezoelectric translator, TDL = tunable diode laser, M_{1-3} = cavity reflectors; the inset shows the QPM multi-grating structure of the PPLN nonlinear-optical crystal.

feedback from the OPO to the seed laser. A significant advantage of injection seeding is that OPO construction is simplified by putting the wavelength-control function into a module that is effectively separate from the optical generation and amplification functions. For example, a high-performance, TDL-seeded PPLN OPO system developed in the author's laboratory is illustrated in Figure 3. It features a multigrating QPM gain medium that is temperature-adjustable up to 250°C, and is pumped at a wavelength of 1.064 μm by a ns-pulsed, SLM Nd:YAG laser. An active cavity control scheme devised by Yabai He enables the SLM near-IR signal and idler outputs from this OPO (at ~1.5 μm and ~3.5 μm, respectively) to be tuned continuously without mode hops over optical frequency ranges of ~250 cm^{-1} (~7.5 THz) with a SLM optical bandwidth of <0.004 cm^{-1} (<120 MHz), as has been confirmed in assorted applications to molecular spectroscopy. The PPLN OPO can by itself generate only moderate output pulse energy (~0.1 mJ, approximately 70% of which is signal radiation), since the 1.064 μm Nd:YAG pump laser pulse energy is limited to ~1 mJ to avoid the optical damage threshold of the PPLN crystal. For higher-power applications, a further portion of the Nd:YAG laser energy (~200 mJ/pulse) can be used to pump an OPA stage based on BPM $\mathrm{LiNbO_3}$, thereby generating SLM signal and idler output pulse energies of ~1.3 mJ and ~0.7 mJ, respectively.

An alternative approach to injection-seeded tuning of ns-pulsed OPOs (used extensively by the author's group in the context of BPM media such as BBO and $\mathrm{LiNbO_3}$) entails passive control of the OPO cavity by slightly misaligning one of its reflectors. This facilitates continuous tuning of the injection-seeded OPO signal and idler outputs by decreasing the effective finesse of the OPO cavity, so that it is then not necessary to lock the OPO cavity length to the seed wavelength. This mode of operation is simpler optically and electronically than active control of the OPO cavity. The method depends on the OPO cavity having a series of high-order transverse modes to smooth out the sharp, widely separated resonances that occur when the OPO cavity is well aligned; a resulting disadvantage is that the multiple transverse modes tend to cause some degradation of output beam quality. Nevertheless, this approach has proved useful for many applications of tunable OPOs, with seeding by either pulsed dye lasers or SLM TDLs.

This passive, misaligned-cavity approach to injection seeding of ns-pulsed OPOs is particularly well suited for spectroscopic applications requiring a coherent source that simultaneously generates two or more adjustable output wavelengths. Such a TDL-seeded, dual-wavelength BBO OPO has been used in the author's laboratory for coherent-Raman spectroscopic measurements of nitrogen ($\mathrm{N_2}$) in furnace air; the relative intensity of the two spectroscopic features provides an instantaneous, turbulence-immune estimate of the temperature of gas in the furnace, within a single shot of the OPO's pump laser (i.e., within ~10 ns). This is an example of so-called spectroscopic tailoring, in which an OPO generates a structured set of two or more discrete output wavelengths, each of which is set to be on- or off-resonance with characteristic features in spectra of molecular target species of interest.

Dual-wavelength injection seeding of ns-pulsed OPOs is relevant to atmospheric remote sensing by DIAL (differential absorption lidar), with TDL-seeded OPO output switched between on- and off-resonance IR wavelengths on alternate shots of the pump laser; range-resolved measurements have been made of key atmospheric species such as methane ($\mathrm{CH_4}$) and water vapor ($\mathrm{H_2O}$). Figure 4 illustrates a proposed extension of the spectroscopic tailoring concept, applicable to dual- and multi-wavelength remote sensing applications by long-path absorption or DIAL. This multiplex system comprises a multi-wavelength passive-cavity pulsed OPO, injection-seeded by a set of single-mode TDLs and a computer-controlled fiber-optic switch to code and decode the resulting multiplex spectroscopic signals.

A significant frontier for narrowband pulsed OPOs entails extending the spectral output range beyond the present readily attainable near-IR limit of ~4 μm (as provided by materials such as BBO, KTP, $\mathrm{LiNbO_3}$, PPLN, and PPKTP). This extension yields high-performance tunable coherent spectroscopic sources at longwave-IR wavelengths where many of the strongest molecular fundamental IR absorption bands are located. OPOs that target the longwave IR depend on availability of suitable nonlinear-optical materials and coherent pump sources at sufficiently long wavelengths (typically >2 μm). One of the most promising longwave-IR OPO materials is zinc germanium phosphide ($\mathrm{ZnGeP_2}$), pumped at 2–3 μm by solid-state crystal lasers such as those based on holmium or erbium. An étalon-tuned narrowband (~0.1 cm^{-1}) $\mathrm{ZnGeP_2}$ OPO, itself pumped at 2.55 μm by a broadband (~15 cm^{-1}) Nd:YAG-pumped $\mathrm{LiNbO_3}$ OPO, is able to cover the wavelength range 3.7–8 μm and has been used to record spectra of $\mathrm{H_2O}$ vapor in the 6.2 μm region. Pulsed OPOs based on gallium arsenide (GaAs) also have great potential; they can be pumped at wavelengths as short as 1 μm and


i_1–, T_1–control
TDL Seed set @ λ_1
i_2–, T_2–control
TDL Seed set @ λ_2
i_3–, T_3–control
TDL Seed set @ λ_3
Collimated multi-λ OPO seed radiation λ_{seed}
Fiber-optic switch
Passive-cavity OPO
λ_{idler} or λ_{signal}
Atmospheric target
λ_{pump}
Multiplex control computer
Pulsed SLM pump laser
Multiplex DIAL detector
Timing control
Timing control
Wavelength decoding control
TDL i-, T-MODULES (single-mode λ control)
Injection seeder laser array
Fiber-optic multiplex control
Multi-λ injection-seeded pulsed OPO system
OPO idler or signal outputs used for dial

Figure 4 Schematic diagram of a multi-wavelength pulsed OPO system employing spectroscopically tailored injection seeding. This design has been proposed by the author for atmospheric remote sensing by DIAL (differential absorption lidar) or long-path absorption.

offer (so far unrealized) tunability out to ~16 μm. Despite its cubic structure and lack of birefringence, GaAs serves as a QPM nonlinear-optical medium in the form of orientation-patterned films.

Another approach to operating continuously tunable OPOs is to vary the wavelength of the pump laser, while fixing other phase-matching parameters such as temperature of the gain medium and crystal angle or QPM grating pitch. Suitable tunable pump laser sources that have been used to pump ns-pulsed OPOs include Ti:sapphire and tunable fiber lasers.

The various wavelength-control strategies outlined above illustrate some of the distinctive attributes of OPOs. It should be recognized that the signal and idler wavelengths of an OPO are distinctly different from that of the pump laser itself, thereby opening up fresh regions of the electromagnetic spectrum. Even if an OPO is injection-seeded (e.g., by a cw TDL) at its signal or idler wavelength, it still generates complementary idler or signal radiation at a new wavelength and (in the case of a pulsed OPO) it also pulse-amplifies the original seed light. Moreover, the nonlinear-optical parametric relationships between the pump, signal, and idler waves in an OPO allow various wavelength-control approaches (e.g., spectroscopic tailoring by multi-wavelength injection seeding) that are simply not attainable in tunable lasers.

Ultrafast-Pulsed OPOs

Given the relatively high peak power of very short (sub-ns) pulses of coherent laser light, it might seem quite easy to use such light to pump the gain medium of an OPD and to exceed its OPO threshold. However, such a task is not at all straightforward, because an ultrafast light pulse, on the time-scale of picoseconds (ps, 10^{-12} s) or femtoseconds (fs, 10^{-15} s), does not stay in one place long enough to enable a coherent parametric wave to build up from noise in the nonlinear-optical medium. Light travels a distance of only ~0.3 mm in 1 ps, which does not allow it to make multiple traversals of the nonlinear-optical medium and build up coherent signal and idler waves. This problem is overcome by synchronous pumping (also used in some ultrafast lasers), in which a train of many consecutive ultrafast pulses from a pump laser interact sequentially with a single signal or idler pulse circulating within the OPO cavity. The mode-locking interval of the pump laser (essentially the round-trip transit time in the laser cavity) must therefore equal the round-trip time of the down-converted (signal or idler) pulse in the OPO cavity. The situation is aggravated when sub-ps (e.g., ~100 fs) pump pulses are used, because the pump and signal (or idler) waves have sufficiently different group velocities that they undergo 'temporal walk-off', becoming separated in time after traversing a relatively short length (typically 1–10 mm for 100-fs pulses) of the nonlinear-optical medium.

Practical ultrafast OPOs were introduced around 1990 and their utility grew as improved pump lasers, nonlinear-optical materials (e.g., KTP, PPLN), and OPO cavity designs became available. Research on ps- and fs-OPOs is now a hot topic, and numerous broadly tunable commercial systems are on the market. Ultrafast OPO-based spectroscopy is becoming extremely important in applications to biology and medicine, where many key processes occur on ps- and fs-time-scales.

Continuous-Wave OPOs

The first cw OPO, reported in 1968, operated in the near-IR and was based on barium sodium niobate ($Ba_2NaNb_2O_5$ – known popularly as 'banana'); it was soon followed by visible cw OPOs based on $LiNbO_3$. However, there was not much more substantial progress on practical cw OPOs for another 20 years, until several technological advances had been made: low-threshold QPM nonlinear-optical gain media, such as $MgO:LiNbO_3$ and KTP; efficient, wavelength-selective cavity designs; all-solid-state cw pump lasers (e.g., diode-pumped crystal lasers or MOPA diode systems). More recently, QPM media (such as PPLN and PPKTP) have provided a further stimulus to efficient, compact cw OPOs.

Most ns-pulsed OPOs use singly resonant (SROPO) designs in which the cavity resonates at either the signal or idler wavelength (but not both), doubly resonant (DROPO) schemes in which both signal and idler resonate are often needed to meet the more demanding pump threshold requirements of cw OPOs. Continuous tuning of a DROPO without longitudinal mode hops needs multiparameter approaches, either dual-cavity (with separate signal- and idler-resonant arms) or concerted tuning of pump and signal/idler wavelengths. Efficient cavity designs for cw OPOs include those that are pump-enhanced (i.e., the cavity is resonant at the pump wavelength as well as the signal and/or idler) and intracavity arrangements in which the laser and OPO gain media share a common cavity. Progress is also being made on cw OPOs based on highly nonlinear optical fibers. With such developments, cw OPOs now have great potential as tunable spectroscopic sources, through their narrow optical bandwidth and their compactness.

OPGs and DFGs – Dispensing with the Optical Cavity

Most of this article has focused on OPOs, in which parametric processes are generated by pumping a nonlinear-optical medium in an optically resonant cavity. As already explained, such a cavity is used to enhance the optical parametric gain by multipassing the signal and/or idler radiation. In some cases, the cavity also contributes to wavelength control, temporal characteristics, beam quality, etc. However, not all optical parametric and related devices need a cavity, as is evident from the OPG, OPA, and DFG schematics in Figures 1a, b, and d.

The use of one or more OPA stages, to supplement the intracavity amplification already present in an OPO itself, is widespread in tunable OPO/OPA systems. Moreover, in some applications (e.g., spectroscopic measurements where optical power is not at a premium) of pulsed OPDs, it is found that a single pass of a (relatively long) nonlinear-optical crystal results in a useful OPG (without an OPO cavity). For instance, Scott Bisson, Thomas Kulp, Peter Powers and co-workers have developed and used several OPD systems of this type. A cavity-free OPG/OPA system that is pumped by a 1 kHz Nd:YAG laser, based on 'fan' PPLN (tuned by continuous transverse variation of the QPM grating pitch), and spectrally filtered by a high-finesse étalon, generates ~10 μJ/pulse of idler radiation. This OPG/OPA radiation has been used to measure narrowband ($\Delta\nu < 0.1\ \mathrm{cm}^{-1}$) cavity-ring-down spectra of CH_4 gas.

Likewise, various tunable DFG devices (closely related, but not identical, to OPDs) have been used in many spectroscopic applications. For instance, a DFG system developed by Frank Tittel and colleagues at Rice University took the near-IR output of two room-temperature TDLs (at 1.55 μm and 1.32 μm, respectively), mixed them in a BPM nonlinear-optical medium such as $AgGaSe_2$, and generated 8.7 μm mid-IR radiation for long-path absorption studies of sulfur dioxide (SO_2), an important atmospheric pollutant. The same group has also used QPM media (e.g., PPLN) for DFG mixing of TDL outputs in the 0.8 μm–1.6 μm range, yielding output at ~3.5 μm to monitor gases such as H_2O, CH_4, and formaldehyde (H_2CO); such DFG devices have been used in NASAs Lunar-Mars Life Support Test program.

Relative to OPGs and DFGs, OPOs and OPAs offer higher output power and coherence, both of which are advantageous in some applications (e.g., remote spectroscopic sensing of the atmosphere). Nevertheless, OPGs and DFGs still have a useful role to play, as indicated above.

Concluding Remarks – When to Use an OPD?

Coherent light sources based on optical parametric generation, amplification, and oscillation represent a significant application of nonlinear optics. Such devices can in turn address as many applications as lasers themselves, at least in principle. However, the fact that OPDs need to be pumped by a laser tends to limit their use to situations that take advantage of their wavelength-conversion and tunability capabilities. The most obvious areas of application of an OPO or any other OPD are therefore those in which the wavelength of the output radiation is critical (e.g., spectroscopy, as indicated in various parts of the above text).

From time to time, there have been suggestions that OPOs would largely displace established tunable lasers such as dye and Ti:sapphire lasers. In the early 1990s, one major laser manufacturer ventured to advertise its new OPO-based instrument with the slogan, "Goodbye to Ti: and Dye". However, such a projected monopoly for OPOs has not eventuated and most laser spectroscopy facilities now depend upon a balanced combination of OPOs together with various forms of tunable laser (including semiconductor lasers, which are almost ubiquitous).

See also

Fiber and Guided Wave Optics: Nonlinear Optics. **Nonlinear Optics, Applications:** Phase Matching. **Nonlinear Optics, Basics:** $\chi^{(2)}$-harmonic Generation; $\chi^{(3)}$ – Third-harmonic Generation; Four-wave Mixing. **Optical Parametric Devices:** Optical Parametric Oscillators (Continuous Wave); Optical Parametric Oscillators (Pulsed). **Scattering:** Stimulated Scattering. **Ultrafast Laser Techniques:** Generation of Femtosecond Pulses.

Further Reading

Barnes NP (1995) Optical parametric oscillators. In: Duarte FJ (ed.) *Tunable Lasers Handbook*, pp. 293–348. San Diego, CA: Academic Press.

Byer RL (1975) Optical parametric oscillators. In: Rabin H and Tang CL (eds) *Quantum Electronics: A Treatise*. Nonlinear Optics, part B, chap. 9, vol. 1, pp. 587–702. New York: Academic.

Byer RL and Herbst RL (1977) Parametric oscillation and mixing. In: Shen Y-R (ed.) *Nonlinear Infrared Generation*, pp. 81–137. New York: Springer-Verlag.

Dmitriev VG, Gurzayan GG and Nikogosyan DN (1997) *Handbook of Nonlinear Optical Crystals*, 2nd edn, pp. 339–362.

Dunn MH and Ebrahimzadeh M (1998) Optical parametric oscillators. In: Finlayson DM and Sinclair BD (eds) *Advances in Lasers and Applications*, pp. 61–82. Bristol and Philadelphia: Institute of Physics Publishing.

Ebrahimzadeh M and Dunn MH (2001) Optical parametric oscillators. In: Bass M, Enoch JM, Van Stryland EW and Wolfe WL (eds) *Handbook of Optics, Fiber Optics and Nonlinear Optics*, vol. 4, pp. 22.1–22.73. New York: McGraw-Hill.

Harris SE (1969) Tunable optical parametric oscillators. *Proceedings of the IEEE* 57: 2096–2113.

Orr BJ (2000) IR Lidar applications in air monitoring. In: Myers RA (ed.) *Encyclopedia of Analytical Chemistry: Applications, Theory and Instrumentation, Applications of Instrumental Methods*, vol. 3, pp. 2007–2032. Chichester: Wiley.

Orr BJ, Johnson MJ and Haub JG (1995) Spectroscopic applications of pulsed tunable optical parametric oscillators. In: Duarte FJ (ed.) *Tunable Laser Applications,* chap 2, pp. 11–82. New York: Marcel Dekker.

Sorokina IT and Vodopyanov KL (eds) (2003) *Solid-State Mid-Infrared Sources*. New York: Springer-Verlag.

Sutherland RL (1996) Optical parametric generation, amplification, and oscillation. *Handbook of Nonlinear Optics,* chap. 3, pp. 111–206. New York: Marcel Dekker.

Optical Parametric Oscillators (Continuous Wave)

S Schiller, Heinrich-Heine Universität Düsseldorf, Düsseldorf, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

A continuous-wave optical parametric oscillator (cwOPO) is a frequency conversion device in which a continuous-wave (cw) laser field (pump) of frequency ω_p is partially converted into two cw waves of lower frequencies ω_s, ω_i (historically denoted by signal and idler) inside an optical cavity. The three frequencies are related by $\omega_i + \omega_s = \omega_p$. The cavity contains a nonlinear medium with a second-order susceptibility and the mirror reflectivities are chosen such that at least one of signal and idler resonates in the cavity. The conversion efficiency from pump power to signal or idler power or both can be larger than 10%. The frequencies of signal and idler waves can be tuned by means similar to conventional lasers, i.e., by changing the spectral dependence of the cavity loss and by tuning the cavity length. Additional tuning parameters specific to OPOs are the pump frequency and the refractive indices of the nonlinear medium for pump, signal and idler. CwOPOs provide a unique combination of features that makes them suitable sources for a variety of spectroscopic applications. Today's cwOPOs can exhibit the following features:

- spectral coverage from the near-infrared (0.7 μm) to the mid-infrared (5.2 μm); for a single device two optical octaves can be covered without change of optical components;
- high output power (up to several W);
- high pump power conversion efficiency (>30%) and good wall-plug efficiency;
- nearly diffraction-limited output beams (modes are close to lowest-order transverse electromagnetic (TEM_{00}) modes)
- single-frequency output, absence of frequency jumps (mode hops);
- narrow free-running linewidth (<6 kHz);
- high absolute frequency stability (<100 MHz drift per hour);
- continuous frequency tuning exceeding 10 GHz;
- rapid, stepwise tuning over several THz; and
- transportability.

cwOPOs complement their pulsed relatives (*see* **Optical Parametric Devices:** Optical Parametric Oscillators (Pulsed)) nanosecond and synchronously pumped pulsed parametric oscillators (*see* **Optical Parametric Devices:** Overview).

Basic Principle

The operation of a cwOPO is most simply described for a singly resonant OPO (SRO) (see Figure 1 and Figure 2a).

Without loss of generality we take the signal wave to be the resonant wave. When a higher-frequency pump wave (power P_p, angular frequency ω_p) and a lower-frequency (signal) wave (power P_s, angular frequency ω_s) traverse a $\chi^{(2)}$ medium (*see* **Fiber and Guided Wave Optics:** Nonlinear Optics), a transfer of power from the pump wave to the signal wave occurs, described by a power gain:

$$\Delta P_\mathrm{s} = GP_\mathrm{s} = EP_\mathrm{p}P_\mathrm{s} \qquad [1]$$

This parametric amplification expression is valid as long as $\Delta P_\mathrm{s} \ll P_\mathrm{s}, P_\mathrm{p}$, i.e., in the limit of small gain and small pump depletion. The (unsaturated) gain coefficient E is a function of: the medium's indices of refraction, orientation and length L, the frequencies $\omega_\mathrm{s}, \omega_\mathrm{p}$, and the spatial modes and overlap of the two beams.


Mirror transmits pump wave
Nonlinear crystal d(z)
Mirror transmits pump and idler
Unconverted pump wave
P_p, ω_p
Pump wave
P_s, ω_s
$P_\mathrm{s}+\Delta P_\mathrm{s}$
ω_i, $P_\mathrm{i,out}$
Idler output wave
L
V_s
ω_s
Signal output mirror
T_s
$P_\mathrm{s,out}$
Signal output wave

Figure 1 Schematic of a singly resonant cwOPO (SRO) in ring configuration. The signal wave (ω_s) is resonated, the idler wave (ω_i) is not. In the nonlinear crystal, the pump wave overlaps with the signal and idler waves; here they are shown displaced with respect to each other for clarity. The signal wave's attenuation coefficient per roundtrip, S_s, is the sum of loss inside the nonlinear crystal, V_s (indicated by arrows), and transmission through mirrors, here represented by a single mirror of transmission T_s. Scatter and absorption losses at mirrors (indicated by arrows) are included in V_s.



Figure 2 Common types of cwOPOs. (a) basic SRO. (b) Doubly resonant OPO (DRO). Standing-wave cavities are shown. (c) SRO with enhancement of the pump wave (PR-SRO); a common-cavity configuration is shown.

If the wave ω_s is made to circulate inside a cavity and the power attenuation per roundtrip, $S_\mathrm{s}P_\mathrm{s}$ is smaller than the power gain per roundtrip (eqn [1]), a sustained oscillation is possible. This is satisfied when the input pump power P_p exceeds the threshold:

$$P^\mathrm{th}_\mathrm{p,in} = S_\mathrm{s}/E \qquad [2]$$

As the pump power P_p is increased above $P^\mathrm{th}_\mathrm{p,in}$, conversion of pump power to idler power occurs, implying that the pump power decreases within the medium. Qualitatively, the average pump power $\langle P_\mathrm{p} \rangle$

along the medium remains at the level $P_{\mathrm{p,in}}^{\mathrm{th}}$, so that the roundtrip fractional power gain remains constant, $G \simeq E\langle P_{\mathrm{p}}\rangle \simeq EP_{\mathrm{p}}^{\mathrm{th}} \simeq S_{\mathrm{s}}$. This ensures that the device reaches a stationary state. The circulating signal power P_{s} increases steadily with increasing pump power, and so does the signal power emitted from the OPO, $T_{\mathrm{s}}P_{\mathrm{s}}$, which is equal to the 'useable' fraction of the roundtrip power gain, $(T_{\mathrm{s}}/S_{\mathrm{s}})GP_{\mathrm{s}}$.

The parametric process that allows the signal wave to experience gain (eqn [1]), also generates an idler wave (difference frequency generation). Its power at the end of the medium is given by the Manley–Rowe relation:

$$P_{\mathrm{i}} = \frac{\omega_{\mathrm{i}}}{\omega_{\mathrm{s}}}\Delta P_{\mathrm{s}} \qquad [3]$$

An OPO also requires a process that starts the oscillation. Spontaneous parametric fluorescence provides this trigger. Due to this quantum effect, a pump wave traversing a $\chi^{(2)}$ medium will generate a flux of signal photons even if there is no signal wave present at the crystal input face. In the photon picture, a tiny fraction (on the order 10^{-9} for a 1 W pump) of the pump photons spontaneously annihilate, creating pairs of signal and idler photons (photon splitting). The idler photons have a frequency $\omega_{\mathrm{i}} = \omega_{\mathrm{p}} - \omega_{\mathrm{s}}$, so that photon energy conservation holds. The process may be thought of as being stimulated by the vacuum fluctuations of the electromagnetic field at the signal and idler frequencies. Some of the signal photons are emitted into the cavity mode, so that after a roundtrip they can serve as a seed for further (stimulated) photon splitting. The process repeats, and the signal wave builds up exponentially in time to a macroscopic level if the pump power is above threshold. The spontaneous (as well as the parametric amplification) process is strongest when momentum conservation is essentially fulfilled, $k_{\mathrm{p}} \simeq k_{\mathrm{s}} + k_{\mathrm{i}}$, where $k = \omega n(\omega)/c$.

In the photon picture, the relation (eqn [3]) is a statement that signal and idler photons are always created in pairs.

Types of OPOs

OPO types may be classified according to the number of waves that resonate within cavities. Typically, a realizable roundtrip loss coefficient is on the order of $S_{\mathrm{s}} = 1\%$ (to which the linear absorption of the nonlinear crystal and mirror transmissivities contribute) and the gain coefficient $E \sim 0.1\%/\mathrm{W}-1\%/\mathrm{W}$ for Gaussian waves, depending on the pump wavelength, crystal type, etc. This leads to SRO threshold powers on the order of 1 to 10 W. Until the early 1990s, solid-state pump lasers of this power level and single-frequency output were unavailable. This led to the interest in and development of cwOPOs in which more than one of the three waves is resonated (Figure 2). The corresponding external threshold powers are

$$\begin{aligned} P_{\mathrm{p,in}}^{\mathrm{th}} &\simeq S_{\mathrm{s}}S_{\mathrm{i}}/4E \text{ for a doubly-resonant OPO} \\ &\qquad \text{(DRO, Figure 2b)} \\ P_{\mathrm{p,in}}^{\mathrm{th}} &\simeq S_{\mathrm{s}}S_{\mathrm{p}}/E \text{ for a pump-resonant SRO} \\ &\qquad \text{(PR-SRO, Figure 2c, see eqn [35])} \\ P_{\mathrm{p,in}}^{\mathrm{th}} &\simeq S_{\mathrm{s}}S_{\mathrm{i}}S_{\mathrm{p}}/E \text{ for a triply-resonant OPO (TRO)} \end{aligned} \qquad [4]$$

Here $S = T + V$ is the fractional power attenuation per roundtrip, arising from the mirror transmission T and absorption/scatter loss V. While the mirror transmission maintains power in a given spatial mode, the loss V removes optical power completely and is the fundamental cause for the nonunity efficiency of the frequency conversion process. Typically, each additional resonant enhancement lowers the threshold power by one to two orders.

Examples for threshold values reported in the literature are: 1.9 W for a 920 nm-pumped SRO, 4 mW for a 0.5 μm-pumped DRO, and 140 mW for a 1 μm-pumped common-cavity PR-SRO. DROs can therefore be pumped even by low-power diode lasers. TROs (where pump, signal, and idler are resonated) are not of importance due to their higher complexity.

Output Power

As an example, the signal and idler output powers for a PR-SRO that resonates the signal are (for a derivation, see Appendix B):

$$P_{\mathrm{s,out}} \simeq T_{\mathrm{s}}P_{\mathrm{s}}(0), \qquad P_{\mathrm{i,out}} \simeq (\omega_{\mathrm{i}}/\omega_{\mathrm{s}})S_{\mathrm{s}}P_{\mathrm{s}}(0) \qquad [5]$$

where the circulating signal power is

$$P_{\mathrm{s}}(0) \simeq \frac{\omega_{\mathrm{s}}}{\omega_{\mathrm{p}}}\frac{4T_{\mathrm{p}}}{S_{\mathrm{s}}S_{\mathrm{p}}}P_{\mathrm{p,in}}^{\mathrm{th}}\left(\sqrt{\frac{P_{\mathrm{p,in}}}{P_{\mathrm{p,in}}^{\mathrm{th}}}} - 1\right) \qquad [6]$$

T_{p} is the input mirror transmission for the pump wave, and T_{s} is the output mirror transmission of the signal wave. Signal and idler output powers have the same dependence on pump input power and increase monotonically with $P_{\mathrm{p,in}}$. The conversion efficiencies reach a maximum four times above threshold, i.e., when $P_{\mathrm{p,in}} = 4P_{\mathrm{p,in}}^{\mathrm{th}}$. There, the signal and idler photon (quantum) conversion efficiencies $\omega_{\mathrm{p}}P_{\mathrm{s,out}}/P_{\mathrm{p,in}}\omega_{\mathrm{s}}$ and $\omega_{\mathrm{p}}P_{\mathrm{i,out}}/P_{\mathrm{p,in}}\omega_{\mathrm{i}}$ exceed 25% and 50%, respectively, if the mirror transmissions T_{p}, T_{s} for pump and signal are chosen larger than the respective loss V_p, V_s. This can be achieved in practice, of course, at the expense of a higher threshold.

Nonlinear Materials

While the fundamental developments in cwOPOs were performed using birefringently phase-matched nonlinear crystals ($MgO:LiNbO_3$, LBO, KTP, $KNbO_3$) (*see* **Materials for Nonlinear Optics:** Liquid Crystals for NLO), and substantial spectral coverage is possible with these crystals, most cwOPOs are now operated with quasi-phase-matched (QPM) nonlinear crystals (*see* **Nonlinear Optics, Application:** Phase Matching). The most commonly used material is periodically poled (PP) $LiNbO_3$ (PPLN), other crystals used are PPKTP and $PPLiTaO_3$, crystals. Their use has led to a substantial widening of the spectral coverage, opening in particular the wavelength range $\lambda > 1.6$ μm, a reduction of the required pump powers thanks to their much higher nonlinearities compared to birefringently phase-matched crystals, and a simplification of (gross) tuning through the use of multigrating structures (containing several sections of differing Λ periods side by side within the same crystal). The above PP crystals exhibit a loss of 0.1%/cm at wavelength around 1 μm, and can be coated with broadband dielectric antireflection coatings, in order to maximize the overall transmission. Another important aspect is that the crystals withstand long irradiation times with high-power focused cw light. For PPLN, operation temperature above 100°C is chosen in order to prevent photorefractive effects.

Spectral Coverage

An example of particularly wide spectral coverage reported in the literature is a cwOPO pumped by a frequency-doubled $Nd:YVO_4$ laser ($\lambda_p = 532$ nm) using a multigrating PPLN crystal. With grating periods $\Lambda = 6.5-9.6$ μm, the range 660–1030 nm (signal wave) and 1100–2800 nm (idler wave) was covered. A cwOPO with a Nd:YAG pump source emitting at the fundamental wavelength ($\lambda_p = 1064$ nm) and a multigrating PPLN crystal ($\Lambda = 25.5-31.2$ μm) achieved a range of 1.45–1.99 μm (signal) and 2.3–4.0 μm (idler).

For idler wavelengths beyond 4 μm, idler absorption by the crystals types above becomes relevant, leading to a reduction in the gain G (this effect is not considered in the treatment given in the Appendix) and to an increase of the threshold. To a certain extent, this can be compensated with powerful cw pump lasers. For example, a 1064 nm pumped PPLN-SRO achieved idler emission in the range 3.6–4.7 μm at 11 W pump power. Also, an 850 nm pumped PR-SRO covered an idler range 4.3–5.3 μm when pumped with 750 mW.

In the future, cwOPOs will certainly profit from the development of novel QPM materials with wider IR transparency range.

Frequency Control

The small-signal gain $G(\omega_s)$ of a parametric interaction in a cwOPO is analogous to the homogenously broadened gain in a laser medium. In contrast to it, however, spatial hole-burning cannot occur. Therefore, mode competition is generally strong in a cwOPO, which will oscillate on a single longitudinal mode: the one for which the difference (or ratio) between 'unsaturated' parametric gain G and total loss S is largest (Figure 3). This is equivalent to the condition of minimum threshold.

The functions $G(\omega_s)$ and $S(\omega_s)$ are therefore important characteristics of a cwOPO. Oscillation can only occur for a frequency ω_s that is very close to a cavity mode frequency $\omega_q = 2\pi qc/OPL(\omega_q)$, where q is the integer mode number, and $OPL(\omega_s)$ is the round-trip optical path length at the frequency ω_s.

To tune a cwOPO to a particular signal/idler frequency pair, a coarse tuning is initially performed



Figure 3 Frequency selection and tuning in a SRO (or PR-SRO) containing an etalon. Oscillation occurs on the signal cavity mode (circled) closest to the frequency where the difference between the small-signal gain G and the loss S is largest (dashed line). The frequency of this mode or the mode number q can be changed by changing the parameters indicated near the thick double arrows. The parameter changes shift the line(s) 'attached' to the corresponding double arrow. Changing the temperature leads to a rough setting of the oscillation frequency. Tilting the etalon allows mode-hop tuning of signal and idler frequencies. Fine tuning by a small amount can be done by changing the cavity length. The frequency of the idler is not shown here; it is always given by the difference between pump frequency and the frequency of the oscillating mode. Thus, tuning of the pump frequency generally leads to a tuning of the idler frequency. For modest pump tuning the amount of signal tuning however depends on SRO type: no signal tuning in a basic SRO and in a dual-cavity PR-SRO, while in a common-cavity PR-SRO pump and signal frequencies are correlated and thus pump tuning leads to signal tuning. FSR: free spectral range.

by tuning the corresponding phase mismatch ΔkL (L is the crystal length) approximately to zero. Taking into account a modulation of the nonlinear susceptibility of the crystal with period Λ, the quantity $\Delta k = k_p - k_s - k_i \pm 2\pi/\Lambda$ describes the deviation from momentum conservation in the photon splitting process. When using a multigrating QPM crystal, the first tuning consists in the selection of a grating of appropriate period Λ, which is moved into the pump wavepath. This is followed by tuning the photon momenta via the refractive indices of the nonlinear medium, which is usually accomplished by temperature tuning, or alternatively by angle-tuning of the crystal. These steps place the maximum of $G(\omega_s)$ to the vicinity of the desired frequency. Options for tuning the emission exactly to the desired frequency are described below for the different OPO types.

Because external perturbations change parameters that enter in $G(\omega_s)$, $S(\omega_s)$, and ω_q, the value of the oscillating frequency will also change in time. The change will be continuous over a certain range of the parameters, but if their perturbation is large enough, a mode hop can occur: the oscillation on the initial mode q will eventually cease and another mode q', for which $G(\omega_{q'}) - S(\omega_{q'})$ is larger, will oscillate instead. A variety of parameters is affected by perturbations: pump power, pump beam direction, cavity length, crystal temperature, and pump frequency.

When such perturbations are applied on intentionally, the OPO output frequencies can be tuned, scanned, or adjusted. The tolerable change in the various parameters before a mode-hop occurs, and the sensitivity of the output frequencies to changes in the parameters depends on the particular cwOPO type. One important approach to suppress mode-hops consists in adding elements into the cavity, such as an etalon, that modify the function $S(\omega)$, typically by modulating it spectrally.

SRO

In the following, we assume that the signal wave is resonated. The SRO is the simplest cwOPO type. The oscillation nominally occurs at the cavity frequency that is closest to the gain maximum, as described above. In practice, environmental disturbances will cause mode-hops on a time-scale of minutes. For this reason, an etalon is added to the cavity. Mode-hop-free oscillation, for several hours, is then achieved.

Typical nonlinear crystals exhibit parametric gain with spectral widths of hundreds of GHz. In contrast, the cavity mode spacing (free spectral range, FSR) c/OPL is on the order of 1 GHz. The tuning range achievable by a cavity length change (using, e.g., a piezo translator) is therefore, at most, one free spectral range (equal but opposite for signal and idler); then a mode-hop to the neighboring cavity mode occurs, with a signal/idler frequency jump by one FSR in the opposite direction to the previous tuning. This process repeats itself as the cavity length is tuned further. It is, therefore, not possible to easily and reliably access a large frequency range by using the cavity length as tuning parameter.

As shown in Figure 3, if an etalon of linewidth smaller than the gain bandwidth is added to the cavity, it becomes the dominant influence (etalon FSRs on the order of one hundred to a few hundred GHz have been used). This means that shifting the etalon's transmission maximum (i.e., the cavity loss S) in frequency space (by tilting a solid etalon or changing the spacing of an air-spaced etalon) as indicated by the double-headed arrows in Figure 3, forces the signal to mode-hop to an adjacent mode, with a corresponding idler frequency hop in the opposite direction. As the etalon is tuned further this occurs repeatedly. This discontinuous 'mode-hop tuning' is useful for tuning the SRO output frequencies over a significant range (e.g., 100 GHz) and allows to reach a desired frequency within one cavity free spectral range.

Continuous tuning of both signal and idler waves is obtainable, if the pump laser is not frequency tunable, by changing the cavity length and synchronously tuning the etalon. This can be achieved by a feedback or feedforward system that controls the etalon angle or spacing. Up to 38 GHz tuning for signal and idler were achieved in this way.

When a tunable pump is available, one can tune the pump frequency while keeping the cavity length and the etalon angle fixed. This keeps the signal cavity mode fixed, and thus the nonresonant wave's frequency (usually the idler) is tuned by an amount equal to the pump frequency change. Continuous tuning ranges exceeding 50 GHz have been obtained in this way. For such pump tuning ranges, the shift of the gain curve, indicated by a double-arrow in Figure 3, is usually sufficiently small that it can be neglected. The use of a widely tuneable pump laser is also possible. A (discontinuous) idler tuning of 9 THz around 3.3 μm has been demonstrated, covered in just 0.3 ms thanks to a large pump tuning rate. In such a case of large pump tuning range, the gain shift is important, causing a significant tuning also of the signal.

The advantages of the basic SRO as compared to other cwOPOs are mainly the simpler tuning behavior, the possibility of continuous tuning without necessitating a tunable pump laser, and the possibility to achieve a very wide tuning range without optics change, since only the spectral range covered by one of the two parametric waves must be provided as a high reflectivity coating on the cavity mirrors. Moreover, in the simplest implementation, it is possible to operate without any electronic servo control of cavity elements, at the expense of a reduced power and frequency stability. In terms of spectral properties (linewidth, frequency stability, time between undesired mode-hops) the SRO does not offer particular advantages compared to other cwOPO types, even if actively stabilized (see below). The disadvantage of the basic SROs based on Gaussian modes is the high threshold, necessitating expensive high-power (several W) cw lasers. This disadvantage is likely to disappear with progress in laser development. The alternative of waveguide SROs is mentioned below.

PR-SRO

In a PR-SRO, the pump wave is also resonated, leading to a substantial reduction of threshold. For example, it is possible to generate mid-IR radiation (3 μm range), even with much more affordable 1 W-level Nd:YAG pump lasers.

One implementation is the common-cavity PR-SRO (Figure 4). The cavity length is either locked to the pump laser frequency or vice-versa. If a frequency-stable pump laser is used, the first solution is favorable, since then both signal and idler waves have a stability comparable to that of the pump laser. With an etalon (coated so as to be transparent for the pump wave) inside the cavity, mode-hop-free operation for several hours has been demonstrated.



Figure 4 Schematic of a pump-resonant SRO with a common cavity for pump and signal waves. The inset shows the pump wave fields incident on and leaving the input coupling mirror. The arrow symbolizes pump wave loss during the round trip.

Mode-hop tuning in a PR-SRO with cavity-to-laser lock can be achieved:

(i) by tuning the etalon at constant pump frequency: the signal mode-hops from mode to mode, the idler tunes equally but in opposite direction;
(ii) by tuning the pump frequency at constant etalon position: the cavity length must follow and therefore the signal tunes by $\Delta\omega_s = (\omega_s/\omega_p)\Delta\omega_p$, while the idler frequency tunes by $\Delta\omega_i = (\omega_i/\omega_p)\,\Delta\omega_p$. This continues until the signal must mode-hop back, causing an equal but opposite frequency jump in the idler. The pump tuning is thus completely transferred to the idler.

Continuous signal and idler tuning is performed by tuning the pump frequency and synchronously adjusting the etalon angle. Thus, a limitation of the common-cavity PR-SRO concept is that continuous tunability necessitates a tunable pump laser.

In a dual-cavity, PR-SRO pump and signal waves resonate in separate cavities. The pump cavity is usually stabilized to the pump frequency and an etalon is placed into the signal cavity for better stability against mode-hops. This configuration combines the tuning simplicity of a basic SRO with a low-threshold power. For example, a threshold for a 1 μm-pumped PPLN dual-cavity PR-SRO at the 0.4 W level was obtained.

Mode-hop tuning (in opposite directions) of the frequencies of both parametric waves in steps of the cavity's FSR can be performed by changing the etalon angle (Figure 3). A range exceeding 50 GHz (at constant output power) has been achieved. Continuous signal and idler wave tuning (by equal but opposite amounts) is possible by changing the signal cavity length (Figure 3). However, the range is limited to the FSR of the cavity, typically on the order of 500 MHz, then the frequencies mode-hop back. It is expected that wider continuous tuning should be possible by synchronous etalon and cavity length scan. If a tuneable pump laser is employed, continuous tuning of only the idler frequency is possible by keeping the etalon and signal wave cavity length fixed; the pump tuning range is fully transferred to the idler.

DRO

In contrast to an SRO, this device type requires both parametrically generated waves to be resonant in the cavity. Here we consider only DROs with a common cavity for both signal and idler waves (dual-cavity DROs have also been demonstrated).

Because of the added resonance condition, mode-hops of the oscillating mode pair occur already upon a very small change (~1 nm) in the cavity length. Under normal environmental conditions such changes are unavoidable and therefore a 'free-running' DRO does not produce frequency-stable output. However, by active control of one additional parameter of the OPO system the mode-hops can be effectively suppressed. A practical solution is to actively control the length of the cavity via the position *a* of one of the cavity mirrors so that a particular mode pair, q_s, q_i, continues to oscillate; this is achieved by maximizing the OPO output power or by minimizing the detuning of one of the two resonant waves from its respective cavity mode frequency. This control system ensures that energy conservation and the two resonance conditions are simultaneously satisfied:

$$\begin{aligned} \omega_s + \omega_i &= \omega_p \\ \omega_s &= 2\pi c q_s/\mathrm{OPL}(d, \omega_s, T) \\ \omega_i &= 2\pi c q_i/\mathrm{OPL}(d, \omega_i, T) \end{aligned} \qquad [7]$$

Experimentally, mode-hop-free oscillation exceeding 10 h was achieved by such active stabilization.

Another system parameter may then be used to tune both signal and idler frequencies. The tuning coefficient for the crystal temperature T is small, but tuning the pump frequency is an efficient way. The tuning coefficient is approximately $\Delta\omega_s = (\omega_s/\omega_p)\Delta\omega_p$, and accordingly for ω_i.

Continuous tuning of signal and idler frequencies over 10 GHz by pump tuning was achieved. This range was limited by the available continuous tuning range of the pump laser. Mode-hop tuning can be induced by mechanical perturbations: by tapping on the DRO cavity, mode-hop tuning over 220 GHz has been demonstrated.

Linewidth and Frequency Stability

For high-resolution spectroscopy a narrow linewidth for signal or idler is desirable. One contribution to the linewidth of a cwOPO arises from the unavoidable spontaneous parametric fluorescence, similar to the Schawlow–Townes limit in lasers due to spontaneous emission. This contribution is negligible if the OPO operates at power levels of practical interest. Thus, other sources of classical noise dominate the linewidth of cwOPOs. As discussed above, the frequency of cwOPOs depends (on a fine scale) on pump frequency and cavity optical path length. Both parameters fluctuate: the pump laser has a finite linewidth as well as frequency jitter, and the cavity optical path length fluctuates due to acoustic noise affecting the mirror positions, to air pressure fluctuations, temperature fluctuations of the crystal and of the cavity structure.

With careful construction and shielding, many of these noise sources can be minimized. Furthermore, it is highly favorable to use pump lasers of narrow linewidth and high intrinsic frequency stability (e.g., diode-pumped monolithic solid-state lasers), or actively frequency-stabilized lasers. Note that this special requirement on the pump source does not exist for lasers.

In an SRO, the linewidth and frequency stability of the signal are mostly determined by the stability properties of the cavity. The idler spectral properties then follow entirely from the signal and pump spectral properties through $\omega_i = \omega_p - \omega_s$. Since the idler is usually the wave of interest, this implies that the SRO cavity and the pump laser must both have a stability appropriate to the spectroscopic application.

If the SRO cavity is not sufficiently stable (e.g., because of insufficient temperature stability of the oven containing the nonlinear crystal), the frequency fluctuation/drift of the signal and idler can be substantial, tens to hundreds of MHz within minutes being typical.

To avoid mode-hops also on long time-scales, the cavity length (or the etalon angle) can be actively stabilized so as to maximize the idler's output power. This ensures that the cavity mode position and the frequency of maximum difference between gain and loss are kept equal.

If a frequency-stable pump wave is used, it is possible to transfer these characteristics by stabilizing the SRO cavity length to the pump wave frequency. In an SRO without resonant pump one can make use of the residual reflection of the pump wave by the cavity mirrors that leads to interference with the pump wave reflected from the pump input mirror. This was implemented in a SRO pumped by a high-power diode-pumped internally doubled Nd:YVO$_4$ laser (532 nm) of high intrinsic frequency stability. Signal and idler drifts of less than 50 MHz/h were achieved. At the same time, a very small 20 kHz linewidth of the (resonant) signal radiation was obtained. Similar levels were obtained for a PR-SRO with a common cavity for pump and signal wave.

In a PR-SRO with dual-cavity configuration, the same requirements of minimization of disturbances to the parametric wave's cavity arise as in a basic SRO. Using a highly frequency-stable kHz linewidth monolithic pump laser, together with the above-mentioned idler power maximization control, frequency drift values for both parametric waves at the level of 30 MHz/h were obtained and a short-term linewidth below 6 kHz.

In a single-cavity DRO, the linewidth and frequency stability of the parametric waves are essentially determined by the pump wave properties (see discussion in the section on DRO above). Here, too, the use of narrow-linewidth, high-frequency-stability pump lasers has led to excellent signal/idler characteristics. For example, less than 40 kHz linewidth and <40 MHz per hour drift were obtained with a DRO pumped by an externally doubled monolithic Nd:YAG laser of 10 kHz linewidth.

If further narrowing of linewidth or reduction of frequency drift is desired, the OPO output frequencies can be stabilized to a stable cavity, atomic, or molecular transition. Locking to a cavity has been demonstrated for a DRO.

Applications

CwOPOs are most interesting as sources of radiation in the IR range beyond 2 μm, especially in the 3–5 μm range, where vibrational transitions of many molecules occur. In comparison to other sources of coherent radiation (color center laser, quantum cascade laser, lead-salt diode laser, CO overtone laser, difference frequency generation), cwOPOs provide a unique combination of desirable features.

A simple application of cwOPOs would be as a source providing a power level/output wavelength/mode quality combination not available from other sources. Possible applications are vibrational spectroscopy in the condensed phase, where a narrow linewidth is not required. The excellent beam quality provides a high spatial resolution.

Concerning high-resolution spectroscopy (mostly in the gas phase), methods demonstrated in conjunction with cwOPOs include:

- Absorption spectroscopy;
- Doppler-free saturation spectroscopy;
- Photo-acoustic spectroscopy (PAS);
- Hole-burning spectroscopy;
- Coherent atomic spectroscopy;
- Cw cavity ring down spectroscopy (cw-CRDS).

Trace gas detection using PAS or cw-CRDS is a particular application where cwOPOs have reached excellent sensitivity (minimum detectable concentrations as low as 1 part in 10^{11}). The high output power and/or the narrow linewidth are specific features that make such sensitivity possible.

Quantum-Optical Properties

The pairwise production of signal and idler photons is at the heart of the parametric process. This perfect quantum correlation is to a certain extent also maintained in the output waves of a cwOPO. In particular, the intensity fluctuations of signal and idler waves emitted by a DRO are strongly (albeit never perfectly) quantum correlated if their output coupler transmissions significantly exceed their respective roundtrip losses. For these 'twin beams' the spectral density of the fluctuations of their power difference can be less than the spectral density of the fluctuations of the power of an individual wave (squeezing). Making use of this correlation permits to increase the obtainable sensitivity in spectroscopic measurements for a given power level of the wave interacting with the sample.

Device Development Trends

CwOPOs using solid-state pump lasers have become commercially available. In the near future, some likely developments will be miniaturization and optimization in order to reduce the influence of perturbations, further extension of continuous and mode-hop tuning ranges and the wider use of diode lasers as pump lasers, leading to cost reduction. To access a larger range of molecules in spectroscopy, extension of the emission range well beyond 5 μm is also of significant interest. Novel nonlinear materials and pump lasers of wavelength longer than the often employed Nd:YAG lasers will become of importance in this development.

Two specific lines of development complementary to the bulk cwOPOs described above are waveguide and intracavity cwOPOs (ICSRO). If pump, signal and idler waves are confined in a waveguide (*see* **Photonic Crystals:** Photonic Crystal Lasers, Cavities and Waveguides) the parametric gain coefficient is a few orders higher than for free-space Gaussian waves, due to the small mode cross-section and the scaling with the square of the crystal length, compared with the linear scaling in case of Gaussian beams (see eqn [36]). Values are on the order of $E \sim 1/\mathrm{W}$ at $\lambda_p = 1.5\ \mu\mathrm{m}$ leading to low thresholds even for SROs, with pump lasers of comparatively long wavelength. For example, in a SRO consisting of a 9 cm long titanium:PPLN waveguide, a threshold below 300 mW for a 1.5 μm pump was achieved. The idler emission range was 3.1–3.4 μm. The potential for mass production and, therefore, cost minimization is clear.

An ICSRO consists of an SRO internal to the cavity of a cw laser, where the high circulating laser power is taken advantage of for pumping. An ICSRO is thus similar to a PR-SRO but there is no need to implement a control system for the frequency lock between pump laser and pump cavity nor to mode-match the pump wave to the SRO cavity mode.

Appendix A

Three-Wave Mixing in a $\chi^{(2)}$ Medium with Focused Waves

The wave equation in a nonlinear medium reads

$$\Delta\vec{E} - \mu_0\mu_r \frac{\partial^2}{\partial t^2}\vec{D}_\mathrm{L} = \mu_0\mu_r \frac{\partial^2}{\partial t^2}\vec{P}_\mathrm{NL} \qquad [8]$$

The displacement field $\vec{D}_\mathrm{L}$ is related to the electric field $\vec{E}$ by linear response. $\vec{P}_\mathrm{NL}$ is the nonlinear polarization. We deal with nonmagnetic media ($\mu_r = 1$) and choose the principal axis system as coordinate system. The Fourier transform of, for example, the x-component of the wave equation then reads:

$$\begin{aligned}&\Delta E_x(\omega,\vec{r}) + \mu_0\omega^2\varepsilon_0\varepsilon_x(\omega)E_x(\omega,\vec{r})\\ &\quad = -\mu_0\omega^2 P_{\mathrm{NL},x}(\omega,\vec{r})\end{aligned} \qquad [9]$$

In the following, we take into account only second-order nonlinear effects, so the nonlinear polarization reduces to $P_\mathrm{NL} = P^{(2)}$. The fields to be considered are monochromatic, propagate in the z-direction and are linearly polarized along x. The notation can then be simplified to:

$$E_x(\omega,\vec{r}) = E(\vec{r})\mathrm{e}^{\mathrm{i}kz}, \quad P_{\mathrm{NL},x}(\omega,\vec{r}) = P^{(2)}_\omega(\vec{r}) \qquad [10]$$

with the wavevector $k = \omega n(\omega)/c$ and the refractive index for the polarization under consideration $n_\omega^2 = n(\omega)^2 = E_x(\omega)$. The electric field is obtained as $\vec{E}(t,\vec{r}) = \frac{1}{2}\mathrm{Re}(E(\vec{r})\mathrm{e}^{\mathrm{i}(kz-\omega t)})\hat{x}$.

Since the parametric gains are small in cw conversion, the derivative of the envelope $E(\vec{r})$ changes only little over a propagation distance on the order of a wavelength $2\pi/k$. Inserting eqn [9] into eqns [6] and [8] and neglecting the term $\sim \mathrm{d}^2E(\vec{r})/\mathrm{d}z^2$, yields the paraxial or slowly varying envelope wave equation:

$$\left(\frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2} + 2\mathrm{i}k\frac{\partial}{\partial z}\right)E(\vec{r}) = -\mu_0\omega^2 P^{(2)}_\omega(\vec{r})\mathrm{e}^{-\mathrm{i}kz} \qquad [11]$$

The electric field envelope can be expanded in a complete set of Gaussian TEM$_{mn}$ – mode functions ψ_{mn}:

$$E(\vec{r}) = \sqrt{\frac{\omega}{n_\omega}}\sum_{m,n=0}^{\infty} A_{mn}(z)\psi_{mn}(\vec{r}) \qquad [12]$$

These mode functions are defined to satisfy the paraxial wave equation in absence of nonlinearity (vanishing right-hand side in eqn [11]) and the orthonormality properties

$$\int\!\!\int_{-\infty}^{+\infty} \psi^*_{mn}(\vec{r})\psi_{m'n'}(\vec{r})\mathrm{d}x\,\mathrm{d}y = \delta_{mm'}\delta_{nn'} \qquad [13]$$

A particular mode function set is characterized by position (along z) and size of the waist, which can be chosen arbitrarily. The functions $A_{mn}(z)$ are slowly varying amplitude functions. The power in a particular mode can be calculated from:

$$P_{mn}(z) = \frac{\omega|A_{mn}(z)|^2}{2\mu_0 c} \qquad [14]$$

where c is the speed of light *in vacuo*. Inserting eqn [12] into eqn [11], multiplication with $\psi^*_{m'n'}(\vec{r})$, and integration over x, y yields:

$$\frac{\mathrm{d}A_{m'n'}(z)}{\mathrm{d}z} = \mathrm{i}\frac{\mu_0 c}{2}\sqrt{\frac{\omega}{n_\omega}}\mathrm{e}^{-\mathrm{i}kz}\int\!\!\int_{-\infty}^{\infty} P^{(2)}_\omega(\vec{r})\psi^*_{m'n'}(\vec{r})\mathrm{d}x\,\mathrm{d}y \qquad [15]$$

If all electric fields are linearly polarized, the Fourier amplitudes of the nonlinear polarization can be written as:

$$\begin{aligned}P^{(2)}_{\omega_\mathrm{s}}(\vec{r}) &= 2\varepsilon_0 d(z)E_{\omega_\mathrm{p}}(\vec{r})E^*_{\omega_\mathrm{i}}(\vec{r})\\ P^{(2)}_{\omega_\mathrm{i}}(\vec{r}) &= 2\varepsilon_0 d(z)E_{\omega_\mathrm{p}}(\vec{r})E^*_{\omega_\mathrm{s}}(\vec{r})\\ P^{(2)}_{\omega_\mathrm{p}}(\vec{r}) &= 2\varepsilon_0 d(z)E_{\omega_\mathrm{s}}(\vec{r})E_{\omega_\mathrm{i}}(\vec{r})\end{aligned} \qquad [16]$$

where d is the tensor element appropriate to the particular combination of linear polarizations of the three waves. (In eqn [16], $\omega_\mathrm{i} + \omega_\mathrm{s} = \omega_\mathrm{p}$.)

The mode amplitude equations for the three interacting waves follow from eqns [10], [15], and [16] as:

$$\begin{aligned}\frac{\mathrm{d}A_{mn}^{\left\{\begin{smallmatrix}\mathrm{p}\\ \mathrm{s}\\ \mathrm{i}\end{smallmatrix}\right\}}(z)}{\mathrm{d}z} &= \mathrm{i}\frac{d(z)}{c}\left\{\begin{matrix}\sqrt{\omega_\mathrm{p}/n_\mathrm{p}}\mathrm{e}^{-\mathrm{i}\Delta kz}\\ \sqrt{\omega_\mathrm{s}/n_\mathrm{s}}\mathrm{e}^{+\mathrm{i}\Delta kz}\\ \sqrt{\omega_\mathrm{i}/n_\mathrm{i}}\mathrm{e}^{+\mathrm{i}\Delta kz}\end{matrix}\right\}\int\!\!\int \mathrm{d}x\,\mathrm{d}y\\ &\quad\times\left\{\begin{matrix}\mathrm{E_s}(\vec{r})\mathrm{E_i}(\vec{r})\\ \mathrm{E_p}(\vec{r})\mathrm{E_i}(\vec{r})^*\\ \mathrm{E_p}(\vec{r})\mathrm{E_s}(\vec{r})^*\end{matrix}\right\}\psi_{mn}^{\left\{\begin{smallmatrix}\mathrm{p}\\ \mathrm{s}\\ \mathrm{i}\end{smallmatrix}\right\}}(\vec{r})^{*+\infty}\end{aligned} \qquad [17]$$

The quantity $\Delta k = k_\mathrm{p} - k_\mathrm{s} - k_\mathrm{i}$ is the wavevector mismatch. Here, the envelope of each wave has an expansion of the form in eqn [12] with its respective (independent) set of mode functions.

Appendix B

Steady-State Description of the cwOPO

The general eqns [17] are applicable to any type of cwOPO. Below and at threshold at least two of the three waves have given modes, i.e., the corresponding function $E(\vec{r})$ is known up to a slowly z-dependent amplitude: the resonant parametric wave has a mode defined by the cavity geometry and mirrors, while the pump wave mode is defined by the used focusing optics. This knowledge allows to obtain an analytic expression for the threshold of any OPO type and for an arbitrary cavity.

Above threshold two cases can be distinguished:

(i) in a basic SRO the pump mode itself becomes a function of pump power, due to its depletion by signal and idler wave, and only a numerical solution can be given; and
(ii) if two or more waves resonate in one or more cavities (DRO, PR-SRO, TRO), an analytic solution is possible even above threshold.

In the following, the PR-SRO is treated. Figure 4 shows a schematic of a common cavity PR-SRO and the notation; the treatment below also holds for the dual cavity PR-SRO. Without loss of generality, the signal wave is taken to be the signal. For the sake of simplicity, below a further assumption about the spatial mode of the idler will be made.

The pump and signal waves are given by TEM_{00} modes of the cavity (or cavities):

$$E_{\mathrm{p}}(\vec{r}) = \sqrt{\frac{\omega_{\mathrm{p}}}{n_{\mathrm{p}}}} A_{00\mathrm{p}}(z)\psi_{00\mathrm{p}}(\vec{r})$$
$$E_{\mathrm{s}}(\vec{r}) = \sqrt{\frac{\omega_{\mathrm{s}}}{n_{\mathrm{l}}}} A_{00\mathrm{s}}(z)\psi_{00\mathrm{s}}(\vec{r}) \qquad [18]$$

In the case of a common-cavity PR-SRO, pump and signal resonate in the same cavity and therefore their modes have the same waist position and Rayleigh ranges $z_{\mathrm{R}} = kw^2/2$, (w is the waist). In the case of a dual-cavity PR-SRO the modes are in principle independent.

Although the idler wave is in general not purely TEM_{00}, it may be approximated by a TEM_{00} mode, whose mode parameters are determined by an optimization criterion. We can then introduce the overlap function:

$$O(z) = \int\int \mathrm{d}x\, \mathrm{d}y (\psi_{00\mathrm{p}}(\vec{r}))^* \psi_{00\mathrm{s}}(\vec{r})\psi_{00\mathrm{i}}(\vec{r})_{-\infty}^{+\infty} \qquad [19]$$

Under these assumptions, the infinite set of mode eqns [17] reduces to just three coupled equations ($A \equiv A_{00}$):

$$\frac{\mathrm{d}A_{\mathrm{p}}(z)}{\mathrm{d}z} = -\mathrm{i}\xi(z)A_{\mathrm{s}}(z)A_{\mathrm{i}}(z)\mathrm{e}^{-\mathrm{i}\Delta kz}O(z) \qquad [20]$$

$$\frac{\mathrm{d}A_{\mathrm{s}}(z)}{\mathrm{d}z} = -\mathrm{i}\xi(z)A_{\mathrm{p}}(z)A_{\mathrm{i}}^*(z)\mathrm{e}^{\mathrm{i}\Delta kz}O(z)^* \qquad [21]$$

$$\frac{\mathrm{d}A_{\mathrm{i}}(z)}{\mathrm{d}z} = -\mathrm{i}\xi(z)A_{\mathrm{p}}(z)A_{\mathrm{s}}^*(z)\mathrm{e}^{\mathrm{i}\Delta kz}O(z)^* \qquad [22]$$

where

$$\xi(z) = \frac{d(z)}{c}\sqrt{\frac{\omega_{\mathrm{p}}\omega_{\mathrm{s}}\omega_{\mathrm{i}}}{n_{\mathrm{p}}n_{\mathrm{s}}n_{\mathrm{i}}}} \qquad [23]$$

Two phasematching cases have to be considered: for birefringent phasematching, $d = \mathrm{const}$ and ξ is independent of z. In QPM, the d-coefficient is modulated periodically along z with period Λ. It suffices to consider only the particular term of its Fourier series expansion that gives the smallest wavevector quasi-mismatch. When only the first term is relevant, this is referred to as first-order QPM and $d(z) \simeq \frac{1}{2}\hat{d}(g_1\mathrm{e}^{\mathrm{i}2\pi z/\Lambda} + \mathrm{c.c.})$. This case can be taken into account by replacing $d(z)$ in eqn [23] by $d_{\mathrm{eff}} = \frac{1}{2}\hat{d}g_1$, and in eqns [20]–[22] the relevant wavevector mismatch becomes $\Delta k = k_{\mathrm{p}} - k_{\mathrm{s}} - k_{\mathrm{i}} \pm 2\pi/\Lambda$, where, for usual materials, the minus sign applies.

We solve eqns [20]–[22] by expanding in powers of the nonlinearity ξ. This is appropriate due to the small gain and implies that the resonant pump and signal wave amplitudes do not change substantially (relative to the respective average amplitude) along the crystal length and around the cavity.

Integrating eqn [22] after approximating the amplitudes on the right-hand side by their values at $z = 0$ yields:

$$A_{\mathrm{i}}(z) = -\mathrm{i}\xi z A_{\mathrm{p}}(0)A_{\mathrm{s}}^*(0)I^*(z)$$
$$I(z) = \frac{1}{z}\int_0^z \mathrm{d}z' O(z')\mathrm{e}^{-\mathrm{i}\Delta kz'} \qquad [24]$$

We insert this result into eqns [20] and [21] and approximate $A_{\mathrm{s}}(z)$ and $A_{\mathrm{p}}(z)$ by their values at $z = 0$. The result is

$$A_{\mathrm{p}}(z) = A_{\mathrm{p}}(0) - \frac{1}{2}(\xi z)^2 D^*(z)A_{\mathrm{p}}(0)|A_{\mathrm{s}}(0)|^2 \qquad [25]$$

$$A_{\mathrm{s}}(z) = A_{\mathrm{s}}(0) + \frac{1}{2}(\xi z)^2 D(z)A_{\mathrm{s}}(0)|A_{\mathrm{p}}(0)|^2 \qquad [26]$$

$$D(z) = \frac{2}{z^2}\int_0^z \mathrm{d}z' z' I(z') O(z')^* \, \mathrm{e}^{\mathrm{i}\Delta k z'} \qquad [27]$$

This completes the calculation of the propagation through the nonlinear medium. Now we proceed to calculate the propagation around the cavity.

Since the signal wave is resonant with the cavity, we can immediately write the self-consistency equation for the roundtrip:

$$|A_\mathrm{s}(0)| = \sqrt{R_\mathrm{s}(1 - V_\mathrm{s})}|A_\mathrm{s}(L)| \qquad [28]$$

The roundtrip cavity reflectivity and roundtrip loss for the signal wave are denoted by R_s and V_s. At the input mirror (see lower part of Figure 4), characterized by a transmission $T_\mathrm{p} = 1 - R_\mathrm{p}$, the interference of the injected pump wave $A_\mathrm{p,in}$ and the internally circulating pump wave must be considered:

$$A_\mathrm{p}(0) = \sqrt{T_\mathrm{p}}A_\mathrm{p,in} + \sqrt{R_\mathrm{p}(1 - V_\mathrm{p})}A_\mathrm{p}(L)\mathrm{e}^{\mathrm{i}\phi} \qquad [29]$$

V_p is the pump roundtrip loss. Evaluating eqn [26] at $z = L$ and comparing with eqn [28] yields:

$$|A_\mathrm{p}(0)|^2 = \left[\frac{1}{\sqrt{R_\mathrm{s}(1 - V_\mathrm{s})}} - 1\right]\frac{1}{\frac{1}{2}(\xi L)^2 \mathrm{Re}\, D(L)} \qquad [30]$$

Here the imaginary part of $D(z)$ was neglected since $|\xi L A_\mathrm{p}(0)|^2 \ll 1$. Expression [30] shows that the intracavity pump power is clamped at a fixed value, equal to the value at threshold, independent of the input power.

In eqn [29] we can assume $A_\mathrm{p,in}$ to be real without loss of generality, yielding the relation:

$$\sqrt{T_\mathrm{p}}\frac{A_\mathrm{p,in}}{A_\mathrm{p}(0)} = 1 - \sqrt{R_\mathrm{p}(1 - V_\mathrm{p})}\mathrm{e}^{\mathrm{i}\phi}\frac{A_\mathrm{p}(L)}{A_\mathrm{p}(0)} \qquad [31]$$

where $\phi = \omega_\mathrm{p}\mathrm{OPL}(\omega_\mathrm{p}, T)/c$. The pump wave is assumed to be exactly resonant; this means that $A_\mathrm{p}(0)$ is maximum. The phase ϕ must therefore be such that:

$$\mathrm{e}^{\mathrm{i}\phi}\frac{A_\mathrm{p}(L)}{|A_\mathrm{p}(0)|} \in \mathbb{R} \qquad [32]$$

Together, with eqn [25], we obtain:

$$\left|\frac{A_\mathrm{p}(L)}{A_\mathrm{p}(0)}\right|^2 = \left|1 - \frac{1}{2}(\xi L)^2 D^*(L)|A_\mathrm{s}(0)|^2\right|^2 \qquad [33]$$

The right-hand side is evaluated neglecting the contribution proportional to ξ^4; inserting the result in eqns [31] and [32] gives:

$$\sqrt{T_\mathrm{p}}\frac{A_\mathrm{p,in}}{|A_\mathrm{p}(0)|} = 1 - \sqrt{R_\mathrm{p}(1 - V_\mathrm{p})} + \sqrt{R_\mathrm{p}(1 - V_\mathrm{p})}\frac{1}{2}(\xi L)^2 \mathrm{Re}\, D|A_\mathrm{s}(0)|^2 \qquad [34]$$

Equations [30] and [34] represent the steady-state solution of the PR-SRO: they give the circulating pump and signal powers, from which all desired quantities can be computed.

The external threshold is found by setting $A_\mathrm{s}(0) = 0$ and assuming small losses, T_p, $V_\mathrm{p} \ll 1$

$$P^\mathrm{th}_\mathrm{p,in} \simeq \frac{T_\mathrm{p} + V_\mathrm{p}}{T_\mathrm{p}}\cdot(T_\mathrm{p} + V_\mathrm{p})\cdot\frac{(T_\mathrm{s} + V_\mathrm{s})}{E} \qquad [35]$$

with the nonlinearity

$$E = \frac{2\mu_0 d^2}{\pi c^2}\frac{\omega_\mathrm{s}\omega_\mathrm{i}}{n_\mathrm{p}n_\mathrm{s}n_\mathrm{i}}L^2 \,\mathrm{Re}\, D(L) \qquad [36]$$

Note that $\mathrm{Re}\, D(L) = |I(L)|^2$. The second factor in eqn [35] is responsible for the reduction of threshold due to pump resonance. The last factor is the internal pump threshold and constant circulating pump power level:

$$P_\mathrm{p}(0) \simeq \frac{(T_\mathrm{s} + V_\mathrm{s})}{E} \qquad [37]$$

which is also equal to the threshold of a basic SRO. The nonlinearity may be written as

$$E \simeq \frac{4\mu_0 d^2}{\pi c^2}\frac{\omega_\mathrm{s}^2\omega_\mathrm{i}^2}{n_\mathrm{p}^2\omega_\mathrm{p}}L h_\mathrm{PA} \qquad [38]$$

with the dimensionless focusing function h_PA. A detailed calculation shows that the value of h_PA cannot exceed 1.1 and is close to its maximum when the phase mismatch ΔkL is approximately zero and the pump and signal focusing by the cavity is such that their Rayleigh range $z_\mathrm{R} \simeq L/2$.

The OPO will select the signal cavity mode frequency ω_s and idler spatial mode that minimizes the threshold eqn [35]. Note that this is not necessarily equivalent to a maximization of E, since T_s and V_s may also be dependent on signal frequency, for example, because of the presence of an etalon inside the cavity.

The circulating signal power as derived from eqns [30] and [34], is given in eqn [6].

The signal power extracted from the cavity is $P_\mathrm{s,out} = T_\mathrm{s}P_\mathrm{s}(L) \simeq T_\mathrm{s}P_\mathrm{s}(0)$, while the (fully extracted) idler power is given by:

$$P_\mathrm{i,out} = P_\mathrm{i}(L) = \frac{\omega_\mathrm{i}}{\omega_\mathrm{s}}EP_\mathrm{s}(0)P_\mathrm{p}(0) \qquad [39]$$

See also

Nonlinear Optics, Applications: Phase Matching. **Optical Parametric Devices:** Overview.

Further Reading

Breitenbach G, Schiller S and Mlynek J (1995) 81% conversion efficiency in frequency-stable continuous-wave parametric oscillation. *Journal of the Optical Society of America B* 12: 2095–2101.

Ebrahimzadeh M and Dunn MH (2000) Optical parametric oscillators. In: Bass M, Enoch JM, van Stryland EW and Wolfe WL (eds) *Handbook of Optics IV*, pp. 2201–2272. New York: McGraw-Hill.

Ebrahimzadeh M, Turnbull GA, Edwards TJ, Stothard DJM, Lindsay ID and Dunn MH (1999) *Journal of the Optical Society of America B* 16: 1499–1511.

Gibson GM, Dunn MH and Padgett MJ (1998) Application of a continuously tunable, cw optical parametric oscillator for high-resolution spectroscopy. *Optics Letters* 22: 40–43.

Klein ME, Laue CK, Lee D-H, Boller K-J and Wallenstein R (2000) Diode-pumped singly resonant continuous-wave optical parametric oscillator with wide continuous tuning of the near-infrared idler wave. *Optics Letters* 25: 490–493.

Klein ME, Gross P, Boller K-J, *et al.* (2003) Rapidly tunable continuous-wave optical parametric oscillator pumped by a fiber laser. *Optics Letters* 28: 920–923.

Müller F, Popp A, Kühnemann F and Schiller S (2003) Transportable, highly sensitive photoacoustic spectrometer based on a continuous-wave dual-cavity optical parametric oscillator. *Optics Express* 11: 2820–2825.

Schiller S, Schneider K and Mlynek J (1999) *Journal of the Optical Society of America B* 16: 1512–1524.

Schreiber G, Hofmann D and Grundkötter W, *et al.* (2001) Nonlinear integrated optical frequency converters with periodically poled Ti:LiNbO$_3$ waveguides. *Proceeding SPIE* 4277: 144.

Special issue (1998) Continuous-wave optical parametric oscillators: materials, devices, and applications. *Applied Physics B* 66(6).

Strössner U, Meyn J-P, Wallenstein R, *et al.* (2002) Single-frequency continuous-wave optical parametric oscillator system with an ultrawide tuning range of 550 to 2830 nm. *Journal of the Optical Society of America B* 19: 1419–1424.

Yariv A and Yeh P (2002) *Optical Waves in Crystals*. Hoboken, NJ: Wiley-Interscience.

Optical Parametric Oscillators (Pulsed)

H Giessen and X P Zhang, University of Bonn,
Bonn, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Advantages and Applications of Ultrashort Pulsed OPOs

The advantages of ultrashort pulsed optical parametric oscillators (OPOs) are twofold: on the one hand, it is possible to generate tunable laser radiation with a pulse duration in the femtosecond and picosecond time domain; on the other hand, the short pulses give rise to a high peak intensity of the electric field of the pump wave inside the nonlinear medium. Due to the fact that the OPO single-path gain coefficient reads as:

$$\eta = \frac{P_{\mathrm{Signal}}}{P_{\mathrm{Pump}}} = \frac{8\pi^2 d_{\mathrm{eff}}^2 L^2 I_{\mathrm{P}}}{\varepsilon_0 n_{\mathrm{P}} n_{\mathrm{S}} n_{\mathrm{I}} c \lambda_{\mathrm{S}}^2} \frac{\sin^2(\Delta k L/2)}{(\Delta k L/2)^2} \qquad [1]$$

where I_{P} is the pump intensity, Δk is the phase mismatch between pump, signal, and idler, n_{P}, n_{S}, n_{I}, are the refractive indices at the pump, signal, and idler wavelengths, respectively, and L is the length of the nonlinear medium with an effective nonlinear coefficient d_{eff}, the efficiency grows proportional to the intensity of the pump.

Ultrashort pulsed OPOs can provide widely tunable femtosecond or picosecond pulses, covering the spectral range from the visible to the mid-infrared, which have many applications, such as time-resolved spectroscopy, pump-probe measurements, semiconductor analysis, photochemistry, optical ranging, data transfer, and data processing with high carrier frequency, white-light generation, etc.

Synchronous Pumping

The key issue in operating ultrashort-pulse OPOs is synchronization between the pump pulses and the signal pulses. Consider the following sequence: a pump pulse enters the OPO cavity and generates spontaneously downconverted light at the signal wavelength (see Figure 1, inset). These signal photons travel inside the OPO cavity, entering the nonlinear medium again after exactly one cavity round trip. This light will act as seed light for another downconversion process if a second pump pulse enters the nonlinear medium at exactly the same instance (see Figure 1). The presence of the signal pulse will lead to a much more efficient stimulated downconversion process.



Figure 1 Synchronous pumping of a typical ring-cavity OPO: P, pump pulses; S, signal pulses; OC, output coupler; ω_P, ω_S, ω_I, frequencies of the pump, the signal, and the idler, respectively. Inset: energy level diagram for optical parametric oscillation.

This requires the repetition rate of the pump oscillator and the OPO to be synchronized precisely. Therefore, this pump scheme is called *synchronized pumping*. If the temporal separation between the pump pulses does not exactly equal the roundtrip time of the signal pulses inside the OPO cavity, the generation efficiency will decrease dramatically as the temporal pulse overlap is reduced.

Dispersion in Nonlinear Media and Optical Glasses

Maintaining synchronicity between the pump pulses and the signal pulses is a necessary, but not sufficient prerequisite for successful operation of an ultrashort-pulse OPO. The signal pulses will be temporally broadened during their repeated trip through the nonlinear medium. This will lead to problems, as the newly generated signal pulses are still rather short (as they have been generated by a short pump pulse), but the previously generated signal pulses, which should act as seed pulses and ideally have a similar pulse duration as the pump pulses, have already been broadened temporally, due to dispersion in the nonlinear medium and other intracavity optical elements. Meanwhile, temporal walk-off between the signal (idler) and the pump pulses will take place, resulting in reduced conversion efficiency and broadened signal pulses. Group velocity dispersion (GVD) and group velocity mismatch (GVM) are normally used to characterize the dispersion in nonlinear medium.

The group velocity of the laser pulses propagating in a nonlinear optical medium is defined as:

$$v_G = \frac{c}{n - \lambda \dfrac{dn}{d\lambda}} \qquad [2]$$

where c is the velocity of light in vacuum, n is the refractive index of the nonlinear medium at the center wavelength λ of the laser pulses. Then the GVD can be written as:

$$\frac{dv_G}{d\lambda} = \frac{\lambda v_G^2}{c} \frac{d^2 n}{d\lambda^2} \qquad [3]$$

In most cases, we evaluate the GVD of the optical materials using the group velocity dispersion parameter (k''), which is defined as:

$$k'' = \frac{d^2 k}{d\omega^2} = \frac{\lambda^3}{2\pi c^2} \frac{d^2 n}{d\lambda^2} \qquad [4]$$

where $k = n\omega/c$ is the wave vector, ω is the frequency of the incident wave, and consequently:

$$\frac{dv_G}{d\lambda} = \frac{2\pi c v_G^2}{\lambda^2} \frac{d^2 k}{d\omega^2} \qquad [5]$$

Due to GVD in the nonlinear medium, the spectral components in the broadband spectrum of an ultrashort pulse will travel at different group velocities and will consequently be delayed differently in the crystal, therefore the pulses will become temporally broadened or become chirped. This linear chirp induced pulse broadening effect can be characterized quantitatively by the following formula:

$$\tau_P = \tau_{P0} \sqrt{1 + \left(\frac{z}{z_d} \right)^2} \qquad [6]$$

where τ_{P0} is the incident pulse duration, τ_P is the pulse duration after the pulse propagates in the nonlinear medium over a distance of z, and z_d is called the characteristic length and defined as:

$$z_d = \frac{\tau_{P0}^2}{4 \ln 2 |k''|} \qquad [7]$$

In frequency conversion processes, such as second-harmonic generation (SHG), sum-frequency generation (SFG), difference frequency generation (DFG), optical parametric oscillation (OPO), or optical parametric amplification (OPA), three waves interact with each other while propagating through the nonlinear medium. Due to dispersion of the material, different waves propagate at different group velocities. This effect is generally called group velocity mismatch. In cases of interaction on the femtosecond scale, the interacting pulses may get separated after propagating some distance in the medium, which means that there is a reduced effective interaction length. The GVM is a quantitative evaluation of this effect, which is defined as:

$$\Delta v_{\mathrm{G}} = \left(\frac{1}{v_{\mathrm{G,i}}} - \frac{1}{v_{\mathrm{G,j}}} \right)^{-1} \qquad [8]$$

where $v_{\mathrm{G,i}}$ and $v_{\mathrm{G,j}}$ are the group velocities of the two interacting waves i and j. The effective interaction length L_{eff} for wave i and wave j can thus be calculated by the following formula:

$$L_{\mathrm{eff}} = \tau_{\mathrm{P}} |\Delta v_{\mathrm{G}}| = \tau_{\mathrm{P}} \left| \left(\frac{1}{v_{\mathrm{G,i}}} - \frac{1}{v_{\mathrm{G,j}}} \right)^{-1} \right| \qquad [9]$$

where τ_{P} is the incident pulse duration at full width at half maximum (FWHM). It is assumed that wave i and wave j have a similar pulse duration. This temporal walk-off will lead to two effects. First, the interacting pulses will get separated and the conversion efficiency will be reduced. The second effect is the broadening of the signal pulses. In the case of sub-100 fs operation, to restrict the broadening in pulse length to less than ~10%, the crystal length should be smaller than $L_{\mathrm{eff}}/2$.

Figure 2 shows the GVD of some typical OPO crystals, including KTP, KTA, RTA, CTA, PPLN, PPKTP, and LBO. Their Sellmeier equations are as summarized in Appendix A. In addition to the wavelength of the incident beam, the GVD is also dependent on the polarization of the incident beams and the type of phase matching.

We give the GVM values between the pump and the signal (P–S), the signal and the idler (S–I), and between the pump and the idler (P–I) for a KTP crystal in Figure 3.

Intracavity Dispersion Compensation and Extra Cavity Pulse Compression

In order to tackle the problem of intracavity dispersion, corrective elements have to be placed inside the cavity in order to compensate the chirp. There have been several solutions to this problem, namely the combination of intracavity prism pairs, chirped mirrors, chirped grating periods (for quasi-phase matching) with oppositely chirped pump pulses, and glass plate dispersion compensators. Certainly, a shorter crystal length will yield a smaller GVM and GVD, but will also give a smaller nonlinear conversion efficiency due to the shorter crystal length (see eqn [1]).



Figure 2 Group velocity dispersion characteristics of some typical OPO crystals.



Figure 3 GVM between the interaction waves of a KTP OPO versus pump wavelength (λ_{P}).

Pump Sources

As pump pulses, mode-locked femtosecond or picosecond lasers are used. The requirements on pulse durations are determined by the desired pulse durations of the OPO signal and by the phase-matching bandwidth of the correspondingly used crystal. Shorter pump pulses normally lead to higher pump power thresholds due to shorter temporal overlap between the interacting pulses. It can also lead to higher instability of the OPO operation due to its higher sensitivity to the cavity length fluctuations. Generally, larger pump bandwidth means larger bandwidth of the signal. Consequently, a potentially shorter signal pulse duration can be achieved if the intracavity dispersion is perfectly compensated. Sometimes it is advantageous for stability to operate the OPO in the slightly negative total GVD regime. In a quasi-phase-matched (QPM) OPO, the phase-matching bandwidth is so large that only a narrow pump bandwidth is required to phase-match a large bandwidth of the signal. Therefore, a pump depletion hole can be commonly observed with the oscillation of the OPO.

Design of Ultrashort Pulsed OPOs

Design of an OPO device may involve the design of the cavity length, cavity mirrors, focal length for focusing the pump beam, intracavity dispersion compensation scheme, frequency stabilization module, crystal length, and some other design depending on the special configuration of the OPO, for example, a heating module (an oven) is required for a PPLN OPO and temperature control module is required for a temperature phase-matched LBO OPO. For an ultrashort pulsed OPO, the most important designs include the design of the crystal length, the design of intracavity dispersion compensation components, and the frequency stabilization control.

Crystal Length

Several factors have to be taken into account when designing a crystal length. The design of a crystal length should be a compromise of all of these considerations. What is special for a femtosecond or picosecond OPO is the dispersion and temporal walk-off between the interacting pulses in the crystal:

1. Effective interaction length: Pump pulse duration, estimated signal pulse duration, temporal walk-off between the pump and the signal give a limit of the crystal length that is characterized by eqn [9].
2. Pulse broadening due to GVM and GVD from the OPO crystal and other intracavity optical glass elements should be estimated. It is reasonable that shorter crystal length is always favorable for ultrashort pulse generation. The crystal length should be as short as possible while maintaining an acceptable conversion efficiency. When designing the crystal length, the available dispersion compensation device should be considered simultaneously.

Dispersion Compensation

For a crystal with a given material and length, the intracavity dispersion can be calculated. The compensation device should introduce an amount of negative GVD such that the total intracavity GVD is equal to or slightly smaller than zero at the desired center wavelength of the signal pulses. Meanwhile, the compensation should be relatively uniform (for instance having a GVD fluctuation of $<50\ \mathrm{fs}^2/\mathrm{mm}$) over the bandwidth of the expected signal spectrum. Then a compensation method (as described above) should be chosen and corresponding device should be designed.

Piezo-Driven Mirror and Frequency Stabilization

To achieve fine tuning of the cavity length, one of the cavity mirrors should be mounted onto a piezoelectric translation stage. When feeding back the signal output of the OPO to this piezo-driven mirror, forming a closed loop to compensate for the drift of the cavity length, a stabilization of the OPO repetition rate is achieved. If the signal is dispersed by a grating, a change in cavity length will also lead to a change in the output spectrum. Using a split photodiode, the difference signal of the dispersed spectrum can be utilized as the measured signal in the feedback loop.

Tuning Characteristics and Methods

Tunability is one of the most important advantages of the OPO over other ultrashort pulsed lasers. A large variety of tuning methods make the OPO more practical and versatile in many applications. For birefringently phase-matched OPOs, the tuning of the signal wavelength can be achieved through changing the pump wavelength (pump wavelength tuning), using an intracavity wavelength selection element (such as a birefringent filter), changing the temperature of the crystal when its refractive index is sensitive to the temperature change (temperature tuning), or changing the orientation of the OPO crystal (angle tuning). Some more methods can be utilized for a QPM OPO, for example through changing the poling period of the crystal (grating period tuning). A special method for an ultrashort pulsed OPO is the so-called cavity length tuning.

As has been discussed above, in synchronous pumping, the OPO must have the same cavity length as the pump laser, so that the signal pulse arrives simultaneously with the pump pulse at the crystal to get the most efficient interaction. Because of dispersion of the nonlinear crystal, the signal will be delayed differently at different wavelengths. In other words, signal pulses have different round-trip times in the cavity at different center wavelengths. When the cavity length of the OPO is changed slightly, the signal has to change its wavelength to keep constant optical path length or constant round-trip time. Cavity length tuning can be achieved easily by tuning the voltage on a piezoelectric transducer (PZT), onto which one of the cavity mirrors is mounted. Therefore, this method is the most common and frequently used to tune the signal wavelength of a synchronously pumped OPO. This is also the basis for stabilizing the operation of a synchronously pumped OPO.

High-Repetition-Rate (HRR) Operation

Synchronously pumping an OPO at high repetition rate produces a high-repetition-rate signal pulse train which extends the application fields of the OPO. Using high-repetition-rate laser pulses (e.g., >1 GHz) as the pump is a straightforward method to run the OPO at a high repetition rate. But a high repetition rate means an extremely short cavity length. For instance, the cavity length is about 30 cm at 1 GHz repetition rate. Such a short cavity length leads to a large mode of the signal beam waist in the crystal. Mode matching between the signal and the pump beams requires that the transverse mode of the pump beam should be slightly larger than that of the signal beam within the interaction zone to maintain stable and efficient oscillation of the OPO. Large modes of the signal and the pump beams mean low interacting intensities, increasing the pump threshold significantly. Using smaller curvature radius of the curved mirrors and shorter focal length of the focusing lens might reduce the mode sizes at the focus in the nonlinear medium, but this will introduce extremely serious astigmatism when the signal beam is reflected from a strongly tilted curved mirror with a quite small curvature radius. In addition to exact synchronous pumping, there are at least two methods to realize high-repetition-rate operation of an OPO. First, pumping at low repetition rate while using a shorter cavity length of the OPO (L_{OPO}) than the pump laser (L_{P}) with $L_{\mathrm{OPO}} = L_{\mathrm{P}}m/N$, where m and N are both integers and $m < N$, as demonstrated in Figure 4a, which is called lower-order synchronous pumping. However, applying this technique, the signal pulses experience more round-trip losses, also resulting in a much higher pump threshold and periodically varying intensities of the output pulses. Second, pumping the OPO at high repetition rate while using a much longer cavity length of the OPO than the pump laser with $L_{\mathrm{OPO}} = L_{\mathrm{P}}N/m$, where m and N are both integers and $m < N$, is called higher-order pumping, as demonstrated in Figure 4b. In higher-order synchronous pumping, the signal pulse train has the same repetition rate as the pump, while the mode-matching problem is removed through a long OPO cavity.



Figure 4 (a) 3/7-order synchronous pumping. Three signal pulse trains (S1–S3) are produced, each having a repetition period (Ts) 3/7 that of the pump pulse train (P): Ts = 3/7*T*. The pump repetition rate is multiplied by a factor of 7 in the signal pulse train (S). (b) Fourth-order synchronous pumping at 1 GHz. The signal pulse train (S) is a combination of four pulse trains (S1–S4), each having a repetition period (4*T*) 4 times that of the pump pulse train (P).

See also

Optical Parametric Devices: Optical Parametric Oscillators (Continuous Wave); Overview.

Appendix A

Sellmeier Equations for some Typical Crystals and Optical Glasses

In the equations, n denotes the refractive index; λ is the wavelength of incident light in μm; $A, B, C, D, A_1, A_2, A_3, A_4, A_5, A_6, B_1, B_2, B_3, B_4, \ldots$, are the Sellmeier coefficients; the subscripts X, Y, Z, stand for the directions of the principal axes of the biaxial crystals.

KTP

$$n^2 = A + \frac{B}{1-\left(\frac{C}{\lambda}\right)^2} - D\lambda^2$$

	A	*B*	*C*	*D*
n_X	2.1146	0.89188	0.20861	0.01320
n_Y	2.1518	0.87862	0.21801	0.01327
n_Z	2.3136	1.00012	0.23831	0.01679

KTA

$$n^2 = A + \frac{B}{\lambda^2 - C} - D\lambda^2$$

	A	*B*	*C*	*D*
n_X	3.1413	0.04683	0.04055	0.01023
n_Y	3.1593	0.04828	0.04710	0.01049
n_Z	3.4435	0.06571	0.05435	0.01460

RTA

$$n^2 = A + \frac{B}{1 - \left(\frac{C}{\lambda}\right)^2} - D\lambda^2$$

	A	*B*	*C*	*D*
n_X	2.04207	1.17785	0.20157	0.01035
n_Y	2.14941	1.09267	0.21462	0.01067
n_Z	2.18962	1.30103	0.22809	0.01390

CTA

$$n^2 = A + \frac{B}{1 - \left(\frac{C}{\lambda}\right)^2} - D\lambda^2$$

	A	*B*	*C*	*D*
n_X	2.34498	1.04863	0.22044	0.01483
n_Y	2.74440	0.70733	0.26033	0.01526
n_Z	2.53666	1.10600	0.24988	0.01711

LiNbO$_3$

$$n_e^2 = A_1 + B_1 f + \frac{A_2 + B_2 f}{\lambda^2 - (A_3 + B_3 f)^2} + \frac{A_4 + B_4 f}{\lambda^2 - A_5^2} - A_6\lambda^2$$

$$f = (T - T_0)(T + T_0 + 546) \text{ and } T_0 = 24.5\,°\text{C}$$

Coefficients	*Values*
A_1	5.35583
A_2	0.100473
A_3	0.20692
A_4	100
A_5	11.34927
A_6	1.5334×10^{-2}
B_1	4.629×10^{-7}
B_2	3.862×10^{-8}
B_3	-0.89×10^{-8}
B_4	2.657×10^{-5}

LBO

$$n^2 = A + \frac{B}{\lambda^2 + C} + D\lambda^2$$

	A	*B*	*C*	*D*
n_X	2.4543	1.1413×10^{-2}	-9.4981×10^{-3}	-1.3900×10^{-2}
n_Y	2.5382	1.2830×10^{-2}	-1.1387×10^{-2}	-1.7034×10^{-2}
n_Z	2.5854	1.3065×10^{-2}	-1.1617×10^{-2}	-1.8146×10^{-2}

$$\frac{\mathrm{d}n_X}{\mathrm{d}T} = 2.0342 \times 10^{-7} - 1.9697 \times 10^{-8} T - 1.4415 \times 10^{-11} T^2$$

$$\frac{\mathrm{d}n_Y}{\mathrm{d}T} = -1.0748 \times 10^{-5} - 7.1034 \times 10^{-8} T - 5.7387 \times 10^{-11} T^2$$

$$\frac{\mathrm{d}n_Z}{\mathrm{d}T} = -8.5998 \times 10^{-7} - 1.5476 \times 10^{-7} T + 9.4675 \times 10^{-10} T^2 - 2.2375 \times 10^{-12} T^3$$

BBO

$$n_o^2 = 1.7018379 + \frac{1.0357554\lambda^2}{\lambda^2 - 0.01800344} + \frac{1.2479989\lambda^2}{\lambda^2 - 91}$$

$$n_e^2 = 1.5920433 + \frac{0.7816893\lambda^2}{\lambda^2 - 0.016067891} + \frac{0.8403893\lambda^2}{\lambda^2 - 91}$$

Sapphire

$$n^2 = 1 + \frac{A_1\lambda^2}{\lambda^2 - B_1} + \frac{A_2\lambda^2}{\lambda^2 - B_2} + \frac{A_3\lambda^2}{\lambda^2 - B_3}$$

A_1	A_2	A_3	B_1	B_2	B_3
1.023798	1.058264	5.280792	0.00377588	0.0122544	321.3616

Quartz

$$n_{o,e}^2 = A + \frac{B\lambda^2}{\lambda^2 - C} + \frac{D\lambda^2}{\lambda^2 - E}$$

	A	*B*	*C*	*D*	*E*
n_o	1.28604141	1.07044083	0.0100585997	1.10202242	100
n_e	1.28851804	1.09509924	0.0102101864	1.15662475	100

Fused Silica, BK7, SF2, SF5, SF10, SF11, SF18

$$n^2 = 1 + \frac{A_1\lambda^2}{\lambda^2 - B_1} + \frac{A_2\lambda^2}{\lambda^2 - B_2} + \frac{A_3\lambda^2}{\lambda^2 - B_3}$$

	A_1	A_2	A_3	B_1	B_2	B_3
Fused silica	0.6961663	0.4079426	0.8974794	0.0046791	0.01351206	97.9340025
BK7	1.03961212	0.23179234	1.01046945	0.0060007	0.0200179	103.560653
SF2	1.40301821	0.23176750	0.93905659	0.0105796	0.04932270	112.405955
SF5	1.46141885	0.24771302	0.94999583	0.0118261	0.05085946	112.041888
SF10	1.61625977	0.25922933	1.07762317	0.0127535	0.05819840	116.607680
SF11	1.73848403	0.31116897	1.17490871	0.0136069	0.06159605	121.922711
SF18	1.56441436	0.29141358	0.96030788	0.0121864	0.05355680	111.451201

Further Reading

Agrawal GP (1989) *Nonlinear Fiber Optics*. Boston, San Diego: Academic Press.

Albrecht TF, Sandmann JHH, Feldmann J, Stolz W, Göbel EO, Hillmer H, Lösch R and Schlapp W (1995) Design and application of a femtosecond optical parametric oscillator for time-resolved spectroscopy of semiconductor heterostructures. *Applied Physics* B 60: 459.

Arbore MA, Marco O and Fejer MM (1997) Pulse compression during second-harmonic generation in aperiodic quasi-phase-matching gratings. *Optics Letters* 22: 865–867.

Arigas D and Reid DT (2002) Efficient femtosecond optical parameteric oscillators based on aperiodically poled nonlinear crystals. *Optics Letters* 27: 851–853.

Bass M, Enoch JM, Van Stryland EW and Wolfe WL (2001) *Handbook of Optics: Volume IV, Fiber Optics and Nonlinear Optics*. New York: McGraw-Hill.

Beddard T, Ebrahimzadeh M, Reid TD and Sibbett W (2000) Synchronously pumped optical parametric oscillator driven by a femtosecond mode-locked fiber laser. *Optics Letters* 25: 1052.

Bierlein JD and Vanherzeele H (1997) Potassium titanyl phosphate: properties and new applications. *Journal of the Optical Society of America B* 6: 622.

Burr KC, Tang CL, Arbore MA and Fejer MM (1997) High-repetition-rate femtosecond optical parametric oscillator based on periodically poled lithium niobate. *Applied Physics Letters* 70: 3341.

Diels J-C and Rudolph W (1996) *Ultrashort Laser Pulse Phenomena: Fundamentals, Techniques, and Applications on a Femtosecond Time Scale*. San Diego, CA: Academic Press.

Dmitriev VG, Gurzadyan GG and Nikogosyan DN (1991) *Handbook of Nonlinear Optical Crystals*. New York: Springer-Verlag.

Dunn MH and Ebrahimzadeh M (1999) Parametric generation of tunable light from continuous-wave to femtosecond pulses. *Science* 286: 1513.

Fenimore DL, Schepler KL, Zelmon D, Kuck S, Ramabadran, Von Richter P, and Small D (1996) Rubidium titanyl arsenate difference-frequency generation and validation of new Sellmeier coefficients. *Journal of the Optical Society of America B* 13: 1935.

Ghost G (1995) Temperature dispersion of refractive indices in β-BaB_2O_4 and LiB_3O_5 crystals for nonlinear optical devices. *Journal of Applied Physics* 78: 6752.

Ghost G (1999) Dispersion-equation coefficients for the refractive index and birefringence of calcite and quartz crystals. *Optics Communications* 163: 95.

Hebling J, Giessen H, Linden S and Kuhl J (1997) Mirror-dispersion-compensated femtosecond optical parametric oscillator. *Optical Communications* 141: 229.

Jundt DH (1997) Temperature-dependent Sellmeier equation for the index of refraction, ne, in congruent lithium niobate. *Optics Letters* 22: 1553.

Kato K, Umemura N and Tanaka E (1997) 90° phase-matched mid-infrared parametric oscillation in undoped $KTiOAsO_4$. *Japanese Journal of Applied Physics 2* 36(4A): L403.

Loza-Alvarez P, Reid DT, Faller P, Ebrahimzadeh M and Sibbett W (1999) Simultaneous femtosecond-pulse compression and second-harmonic generation in aperiodically poled KTiOPO4. *Optics Letters* 24: 1071.

Matuschek N, Gallmann L, Sutter DH, Steinmeyer G and Keller U (2000) Back-side-coated chirped mirrors with ultra-smooth broadband dispersion characteristics. *Applied Physics B* 71: 509.

Mokhtari A, Fini L and Chesony J (1987) Efficient frequency mixing of a cw femtosecond laser synchronously pumped by a frequency doubled Nd:YAG laser. *Optics Communications* 61: 421.

Nebel A, Fallnich C, Beigang R and Wallenstein R (1997) Noncritically phase-matched continuous-wave mode-locked singly resonant optical parametric oscillator synchronously pumped by a Ti:sapphire laser. *Journal of the Optical Society of America B* 10: 2195.

Schubert M and Wilhelmi B (1978) *Nonlinear Optics and Quantum Electronics*. New York: John Wiley & Sons.

Seres J and Hebling J (2000) Nonstationary theory of synchronously pumped femtosecond optical parametric oscillators. *Journal of the Optical Society of America B* 17: 741.

Shen YR (1984) *The Principles of Nonlinear Optics*. New York: John Wiley & Sons.

Sutherland RL (1996) *Handbook of Nonlinear Optics*. New York: Marcel Dekker Inc.

Szipöcs R and Kohazi-Kis A (1997) Theory and design of chirped dielectric laser mirrors. *Applied Physics B* 65: 115.

Tang Y, Cui Y and Dunn MH (1995) Thermal dependence of the principal refractive indices of lithium triborate. *Journal of the Optical Society of America B* 12: 638.

Tomaru T and Petek H (2000) Femtosecond Cr4+ YAG laser with an L-fold cavity operating at a 1.2-GHz repetition rate. *Optics Letters* 25: 584.

Tomaru T and Petek H (2000) Thermal dependence of the principal refractive indices of lithium triborate. *Journal of the Optical Society of America B* 18: 388.

Velsko SP, Webb M, Davis L and Huang C (1991) Phase-matched generation in lithium triborate (LBO). *IEEE Journal of Quantum Electronics* 27: 2182.

Yariv A (1984) *Optical Waves in Crystals: Propagation and Control of Laser Radiation*. New York: John Wiley & Sons.

Yariv A (1989) *Quantum Electronics*. New York: John Wiley & Sons.

Zernike F and Midwinter JE (1973) *Applied Nonlinear Optics*. New York: John Wiley & Sons.

Zhang XP, Hebling J, Kuhl J, Rühle WW, Palfalvi L, Giessen H (2002) Femtosecond near-IR optical parametric oscillator with efficient intracavity generation of visible light. *Journal of the Optical Society of America B* 19: 2479.

Zhang XP, Kuhl J, Hebling J, Bartels A, Nau D, Rühle XP, Giessen H (2002) 1-GHz repetition-rate femtosecond optical parametric oscillator. *Applied Physics Letters* 80: 1873.

OPTICAL PROCESSING SYSTEMS

D Arbel and N S Kopeika, Ben-Gurion University of the Negev, Beer Sheva, Israel

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Modern optical systems find many applications in sensing, recording, storage, and transmission of data. These applications stimulate the development of many new optical devices, components, materials, and applied technologies. The basic element of an optical system is the light. The physical implications of the light in optical systems are very analogous to those of electricity, hence, light signals are quite similar to electric signals. High-speed spatial light components are being developed for more stringent applications in coherent optical processing systems, where they may be used in the input plane or in the Fourier transform plane. Research in this area is directed towards the design of robust and compact correlators.

Novel transforms for information processing (also known in electronics) include Fourier and wavelet transforms. Such optical transformations serve as the basic platform for linear optical system processing. Optical devices and systems for information processing include spatial light modulators, which are used to implement optical information processing systems. There are holographic applications in information processing, display systems, memory systems, optical computing systems, and imaging systems. Such devices and systems are based on applications of novel materials for information processing. Optical and digital techniques are used for optical system design, optical computing, image processing, and even for encryption and security systems.

The imaging system is an optical system and integrates hardware as well as software. Figure 1 presents a general model of an extensive imaging system. The starting point of the system is the object (or the light source). An imaging device, such as camera or optical sensor detects the energy radiated in electromagnetic waves from the light source. The image (or series of images – video) formed in the imaging device depends on the received irradiance of the image propagated through the imaging path and is correspondingly diminished from that in the object plane. The properties of the optical medium (transmission path) such as atmospheric properties, background light, motion, and vibration in both the object and the image planes, and the quality of the imaging device, all affect the quality of the images.



Figure 1 General description of an imaging system.

There are atmospheric phenomena that give rise to attenuation of the irradiance of the propagating image, thus reducing the contrast of the final image, as well as atmospheric phenomena that cause blurring of detail. Both types of phenomena degrade image quality.

Image blurring caused by vibration is a factor whose influence on resolution is often significant in imaging systems that involve mechanical motion. In order to obtain a well processed imaged, as similar as possible to the ideal image (the source), image processing techniques such as image enhancement, restoration, and filtering are implemented in an optical processing system which is a combination of software (algorithms) and hardware (electronic and optical components). The processing procedure involves mathematical and especially optical transformations. The output of the processing system is presented by using a display device or hardcopy. The development of imaging systems (imaging devices and displays) which include integrated optical components and processing units, assist in improving image quality at early stages, and as a result reduce the need of unique processing systems and may serve as the standalone device.

The key issues which must be addressed in the design, evaluation, and implementation of practical systems for optical processing, are provided here in a detailed review. Thus, the review is focused on imaging where considerations such as optical transformations, optical computing, effects of diffraction, scatter, absorption, and design on the performance of optical systems, imaging and the optical transfer function (OTF) for image restoration, and filtering, are all discussed in detail.

Digital Processing and Control

The Fourier transform properties of Fraunhofer diffraction permit data processing operations carried out optically that can, in many situations, be more advantageous than digital signal processing. The primary advantages of optical techniques over electronic analog and digital signal processing, are best realized when the information to be processed has two degrees of freedom. Optical systems correspondingly can have two degrees of freedom. Thus, for handling pictorial data, they can be intrinsically superior to electric or electronic systems, which have only time as an independent variable. This two-dimensional (2D) processing property can be particularly valuable in radar applications where previously velocity and position data had to be processed separately in order for sufficient accuracy in the estimation of each set of data to be obtained.

Many of the basic operations that can be performed by optical computers can also be done with electronic systems. However, if large quantities of wideband data are to be processed, the electronic techniques can often be prohibitively expensive and time consuming. The optical computer is faster than a digital computer because it operates on signals that are functions of positions, not time. The input to an optical data processor is a pattern of light irradiance that varies over some area, not light irradiance that varies as a function of time.

Thus, optical data processing can be very appropriate for such lengthy operations as the calculation of complicated Fourier transforms and the processing of side-looking radar signals. In addition to mathematical operations such as differentiation, integration, and producing Fourier transforms, the two classes of applications for which optical signal processing is most often used are filtering and correlation.

Optical Computing

Optical computing (OC) means the use of light as a primary means for carrying out numerical calculations, reasoning, artificial intelligence, etc. The history of OC is linked to that of radar systems. OC systems received a great push from the invention of laser in 1960. In the 1960s, the first schemes for all-optical digital computers were proposed. Since the 1990s, researchers have been pursuing the development of computers based on optical technology, and emphasis has shifted to optical interconnection of arrays of semiconductor smart pixels. OC provides the first in-depth review of the possibilities and limitations of optical data processing. The partial listing of those points that make OC appealing are direct image processing, massive parallelism and connectivity, immunity to electromagnetic interference (EMI), speed, size, and cost. There are three distinct trends in OC: special purpose analog optical systems, general purpose digital optical systems, and hybrid optical/electronic systems.

Innovations such as the electro-optic spatial filter, the 2D spatial light modulator, and the variable electro-optic mirror provide the fundamental building blocks for both analog optical computing (AOC) and digital optical computing (DOC) technologies. Optical techniques can provide solutions and a number of ways of extending the information processing capability of electronics. The optical processors have to be compatible with existing electronic systems. Free space digital optics is one direction that provides some valuable solution. DOC requires the use of nonlinear optics.

All-optical processing refers to optically based processors employed nonlinear optical resources either of liquid crystal spatial light modulators (SLMs) or nonlinear interference filters (NLIFs). Electro-absorption devices are a bridge between all-optical demonstrators and optically interconnected smart pixels (logic and local on-chip interconnection is electrical whereas chip to chip interconnection is optical). Optically interconnected smart pixels have several advantages like faster data acquisition and low power consumption. A major breakthrough in nonlinear optics is essential to increase the use of optics within computing and the manufacture of optical digital computers.

An optically bistable device used for photonic switching is the self electro-optic effect device (SEED). It is the analogous component for the transistor in optical processing. A SEED consists of multiple elements, biased by an external voltage, which creates an external field that shifts the wavelength of the onset of absorption, thus varying the intensity of the transmitted light. SEEDs rely on changes in the optical transmission of a semiconductor induced by an applied electric field. SEEDs can be configured in pairs (connected electrically) so that a beam of light switching one device can cause a complementary switch in the transmission of the other. Hence, a small change in the intensity of one beam can cause a large change in intensity of the other. This kind of configuration is known as symmetric SEEDs, and acts like an electronic flip-flop and permits logic operations NAND and NOR to be carried out on pairs of optical input signals. With symmetric SEEDs, the higher the input optical power, the faster the switching speed. Cellular logic image processor (CLIP) is implemented using the symmetric SEEDs. CLIP computer architecture is designed to permit parallel information processing, in which logic operations are performed on each element of the array simultaneously.

Holography

Holography is a photographic method of recording information (two mutually coherent beams) about an object, in which one beam is the object beam and the other a reference beam, which enables the construction of objects in three dimensions. Holography relies on the encoding of the object formation in a set of complex interference fringes formed by the interaction of a plane coherent reference wave with the wavelets diffusely scattered by the object.

The microscopic interference fringes recorded on a high resolution photographic plate after development and processing become a hologram. Hologram applications assist the study of small deformations of objects, to replace conventional optical elements such as lenses and beamsplitters, for data/information storage, and use of photo-refractive materials in analog computing, object recognition, and correlation, etc.

The purpose of recording a hologram is not optical data processing but rather a lensless method of forming an image. The uniqueness of a hologram as compared to an ordinary photographic image, for example, is that the latter contains amplitude information only. A hologram, because it involves interference of the complex field amplitude (CFA) of a given scene with a reference beam, records both amplitude and phase of the CFA of the given scene as seen within its field of view (FOV) by a square-low photosensitive device such as a film.

The film is exposed within its region of linearity whereby transmission is proportional to irradiance for a given time exposure. The transparency resulting from the film is the hologram. To view the holographic image, the hologram is illuminated with a reference wave, which causes the CFA of the given scene (both amplitude and phase) to be reconstructed. Since hologram reconstruction involves the CFA of the given scene in its entirety, depth information is included as well. Furthermore, it is even possible to view the holographic scene from different physical points of view and to see around objects in the scene. This ability, however, is limited by the solid angle subtended by the object when the hologram is recorded. Hologram reconstruction cannot supply more information than that recorded in the hologram itself.

Image Processing

Figure 1 demonstrates a general behavior of an imaging process. The ‘Processing System’ block in Figure 1 is expanded and presented in more detail by Figure 2. Figure 2 demonstrates in a flow chart, a general process occurring within the processing system. The input to the processing system is a degraded image (or set of images or video signal) such as blurred image, noisy image, image with clutters, multi-spectral image, etc. The input depends on exterior (environmental conditions) and interior (optical, electronic, and mechanical) effects of the imaging system. It may be generated as an analog signal or digital signal. As a result, the output of the imaging system is expected to be a processed (filtered, enhanced, estimated, restored, cleared, etc.) image.


Input – degraded image
Image processing
• Optical transformations
• Optical or digital processing
• Software/hardware as the processing tools
• Linear and nonlinear algorithms and techniques
Output – processed image
Implementations and applications
• Presentation
• Data analysis and storage

Figure 2 Image processing.

Implementations and applications depend on the output obtained by the imaging system. The output can be presented by a display device and/or hardcopy. The output can be stored for future assignments and may also serve for data analysis such as detection, recognition, and identification of patterns and other details of interest (mapping, target acquisition, defects and imperfections in the human body, meteorology, security, intelligence, etc.).

Spatial units are reciprocal to time, and are cycles/seconds or Hz. The spatial units are also reciprocal to the domain of the information being sought. Spatial signals are 2D or even 3D on occasions. 2D spatial transforms may actually exist physically in the spatial plane. Novel transforms for information processing include Fourier and wavelets transforms. Such optical transformations serve as the basic platform for linear optical system processing. Image processing techniques are based on the image spatial frequencies. In most techniques the degraded image is transformed using an optical transformation, as a primary stage before any other process is being conducted. Optical (inverse) transformations also serve as the last processing tool before the output. Practically, optical transformations are involved and integrated in most processes related to image processing.

Image processing refers to both digital and optical image processing, and also considers algorithms and techniques, which are implemented by an integration of software and hardware. Image processing is an extremely broad field. It considers digital image processing, 2D and 3D image processing and pattern recognition, real-time processing, neural networks, image enhancement/improvement, image restoration, estimation, filtering for noise removal, linear and nonlinear filtering techniques for variety of implementations, optimum filtering, etc. Image processing also include varieties of algorithms such as linear and nonlinear algorithms, algorithms for pattern recognition, linear and nonlinear techniques for pattern recognition, neural networks based algorithms, etc. Both optical and electronic implementations (hardware) are still under investigation. Nevertheless, image processing based on software presents reliable results and hence, can be transformed into hardware components, which may become an integrated part of the processing hardware.

Optical Transformations

Mathematical transformations are applied to signals to obtain further information from the signal that is not readily available in the raw signal. Most of the signals, in practice, are time-domain signals in their raw format. That is, whatever that signal is measuring, is a function of time. In many cases, the most important information is hidden in the frequency content of the signal. The frequency spectrum of a signal is basically the frequency components (spectral components) of that signal. The frequency spectrum of a signal shows what frequencies exist in the signal.

There are many transforms that are widely used, often by engineers and mathematicians, in solving problems in science and engineering. Fourier, Laplace, Hilbert, Wigner distributions, Radon, and wavelet transforms, constitute only a small portion of a huge list of transforms that are available. Every transformation technique has its own area of application, with advantages and disadvantages.

Fourier Transform

The Fourier transform (FT) is probably the most popular linear transform being used. The FT, a pervasive and versatile tool, is used in many fields of science as a mathematical or physical tool to alter a problem into one that can be more easily solved. It is used in linear systems analysis, antenna studies, optics, random process modeling, probability theory, quantum physics, and boundary-value problems and has been successfully applied to restoration of astronomical data. Some scientists understand Fourier theory as a physical phenomenon, not simply as a mathematical tool. In some branches of science, the FT of one function may yield another physical function. The FT, in essence, decomposes or separates a waveform or function into sinusoids of different frequency which sum to the original waveform. It identifies or distinguishes the different frequency sinusoids and their respective amplitudes. There are functions for which the Fourier transform does not exist; however, most physical functions have a FT, especially if the transform represents a physical quantity. Other functions can be treated with Fourier theory as limiting cases. Many of the common theoretical functions are actually limiting cases in Fourier theory.

Wavelets

Wavelets were developed independently in the fields of mathematics, quantum physics, electrical engineering, and seismic geology. Interchanges between these fields have led to many new wavelet applications including image processing. Wavelets are mathematical functions that cut up data into different frequency components, and then study each component with a resolution matched to its scale. Wavelet transforms comprise an infinite set. The different wavelet families make different trade-offs between how compactly the basis functions are localized in space and how smooth they are. Within each family of wavelets are wavelet subclasses distinguished by the number of coefficients and by the level of iteration.

The wavelet transform (WT), which is also a linear operation, provides the time-frequency representation. Often a particular spectral component occurring at any instant can be of particular interest. In these cases it may be beneficial to know the time intervals at which these particular spectral components occur. WT is capable of providing the time and frequency information simultaneously, hence giving a time-frequency representation of the signal. The WT was developed as an alternative to the short-time FT (STFT). The WT was developed to overcome some resolution related problems of the STFT. The frequency and time information of a signal at some certain point in the time-frequency plane cannot be known. What spectral component exists at any given time instant is a mystery. Therefore, it is best to investigate what spectral components exist at any given interval of time. This is a problem of resolution, and it is the main reason why researchers have switched to WT from STFT. STFT gives a fixed resolution at all times, whereas WT gives a variable resolution as follows: higher frequencies are better resolved in time, and lower frequencies are better resolved in frequency. This means that a certain high frequency component can be located better in time (with less relative error) than a low frequency component. On the contrary, a low frequency component can be located better in frequency, compared to high frequency component.

Wavelet versus Fourier Transforms

Both transforms are linear and the mathematical properties of the matrices involved in the transforms are similar. The inverse transform matrix for both transforms is the transpose of the original. Wavelets have advantages over traditional Fourier methods in analyzing physical situations where the signal contains discontinuities and sharp spikes. The most interesting dissimilarity is that individual wavelet functions are localized in space, Fourier sine and cosine functions are not. This localization feature, along with wavelets localization of frequency, makes many functions and operators using wavelets ‘sparse’ when transformed into the wavelet domain. This sparseness, in turn, results in a number of useful applications such as data compression, detecting features in images, and removing noise from time series. One way to see the time-frequency resolution differences between the FT and the WT is to look at the basis function coverage of the time-frequency plane. In order to isolate signal discontinuities, some very short basis functions are needed. At the same time, in order to obtain detailed frequency analysis, some very long basis functions are needed. A way to achieve this is to have short high-frequency basis functions and long low-frequency ones. This happy medium is obtained with WT. FT utilizes just the sine and cosine functions (single set of basis functions). Therefore, its new domain contains basis functions that are sines and cosines. On the other hand, WT includes an infinite set of possible basis functions. Hence, its new domain contains more complicated basis functions called wavelets, mother wavelets, or analyzing wavelets. The basis functions are localized in frequency, making mathematical tools such as power spectra and scalegrams useful at picking out frequencies and calculating power distributions. Thus wavelet analysis provides immediate access to information that can be obscured by other time-frequency methods such as Fourier analysis.

Physical Properties and Analog/Digital Mitigation Processing in Nonideal Systems

The weakest link in most imaging systems is time varying distortions, such as the Earth’s atmosphere, motion, or vibrations. To obtain clear imaging through time varying distortions, it is useful to characterize the physical degradation phenomena using an OTF. It is often important to use the appropriate filter based on the OTF magnitude, modulation transfer function (MTF), to correct (restore) the degraded image (using software or hardware). On the other hand, it may be useful to incorporate real-time phase correction into the imaging system such as adaptive optics.

Optical Transfer Function for Incoherent Imaging

In electronics, the transfer function is redefined as the Fourier transform of the impulse response. The OTF is defined similarly, but is normalized to its own maximum value which normally occurs at zero spatial frequency, that is:

$$\begin{aligned}\mathrm{OTF} &= \tau(\omega) = \tau(\omega_x, \omega_y)\\ &= \frac{\iint_{-\infty}^{\infty} s(x', y')\exp[-j(\omega_x x' + \omega_y y')\mathrm{d}x'\,\mathrm{d}y']}{\iint_{-\infty}^{\infty} s(x', y')\mathrm{d}x'\,\mathrm{d}y'}\\ &= \frac{S(\omega_x, \omega_y)}{S(0,0)} = \mathrm{MTF}\ \exp(j\mathrm{PTF}) \qquad [1]\end{aligned}$$

where $S(\omega_x, \omega_y)$ is the FT of the spread function or impulse response $s(x', y')$. Ordinarily, for artificial imaging systems, the OTF is maximum at zero frequency. The magnitude of the OTF is called the MTF. The name refers to spatial modulation of light irradiance. If there is no such modulation, irradiance is uniform and there is no image. Thus, spatial modulation is related to image quality and MTF is a measure of the ability of an imaging component or system to transfer such spatial modulation from input (object plane) to output (image plane).

There is also a phase transfer function (PTF) whose importance in resolution is not nearly as widespread as that of MTF but which, nevertheless, cannot be neglected. Spatial phase determines image position and orientation, rather than amount of detail. If a target is displaced bodily in the image plane such that each part of the target image is displaced by the same amount, the target image is not distorted. However, if portions of the target image are displaced more or less than other portions, then the target image is distorted. This information is contained in the PTF.

The physical implications of the OTF are very analogous to those of electronics transfer functions. Both permit determination of output for any given input. In both cases, since the FT of the delta function is a constant (unity) amplitude, a delta function input permits indication of the frequency response of the system, that is, which frequencies pass through the system unattenuated and which are attenuated and by how much. Perfect fidelity or resemblance between input and output requires infinite bandwidth so that an impulse function is obtained at output for impulse function input. In imaging, an impulse formation at output is a point image. This means that, to obtain a point image for a point object, infinite spatial frequency bandwidth is required of the imaging system. Physically, this means that because of diffraction effects optical elements such as lenses, field stops, and mirrors must be of infinite diameter so as to eliminate diffraction at the edges. This, of course, is not attainable.

Pixel Modulation Transfer Function

To measure the point spread function (PSF), it is important to determine which size object can be considered a point object. This is affected primarily by instrumentation pixel size. The pixel is the smallest element recordable in image space. The brightness value represents average irradiance over that small portion of the image scene. Pixel size is often related to detector size. If only a portion of the detector is illuminated, the output current is equivalent to that obtained for the same total radiant power absorbed by the detector but averaged over the entire detector area. No detail smaller than a pixel can be resolved in the image. In practice, dead space between pixels violates isoplanaticism (spatial stationarity), which is a requirement for linear systems. Nevertheless, dead space is small and such effects are often neglected in image system characterization. However, it is possible to overcome distortions in MTF measurements arising from this lack of isoplanaticism by using a ‘white’ spatial noise random object. This gives rise to a white noise random image. The ratio of the image power spectral density to object power spectral density is equal to the square of the system MTF. In this way the lack of isoplanaticism is overcome by the spatial randomness of the object and image.

Pixel size strongly affects system MTF. If a pixel represents a point image, then pixel size and shape are minimum spread function. A best case OTF for such an imaging system is then a normalized FT of the pixel shape. For example, a square pixel yields a two-dimensional sinc MTF whose width increases as pixel size decreases.

Optical Transfer Functions for Image Motion and Vibration

Image blurring caused by vibrations is a factor whose influence on resolution is often significant in imaging systems that involve mechanical motion. A stabilized system, which obtains image motion corrections by moving optical elements so as to counteract sensor motions, has a residual error typically on the order of 2500 μrad/s involving pitch, roll, yaw, and forward motion compensation errors. The greatest errors usually result from rotational vibration. A stabilized mount-type system has a combined error typically on the order of 100 μrad/s. Even where no motion is involved, as in large fixed-position astronomical telescopes, vibrations deriving from thermal gradients in the walls and other parts of the telescope can be the limiting factor in image resolution.

As a consequence of such image motion, in many high-resolution systems, despite the use of high-quality sensors, resolution is limited by image motion and, as a result, the high-resolution capability of the sensor may be wasted. It can be a significant waste of means to use an expensive high-resolution sensor in such a situation unless the blur can be corrected with image restoration. In imaging system design, a convenient engineering tool is OTF. The overall system OTF is limited by the OTF of the weakest link. The formulation of such image motion blur into an OTF format is thus very convenient for system design and system analysis purposes, as well as for image restoration.

OTFs can describe image quality for many forms of image motion such as linear (uniform) motion, sinusoidal vibrations at high vibration frequencies, sinusoidal vibrations at low vibration frequencies, acceleration, etc. The OTF for any type of image motion can be calculated numerically in real time provided the motion function is known. This is usually determined easily via a gyroscope or microelectronic accelerometer.

In general, the motion of interest is not the actual relative motion between object and imager, but rather the relative motion between imager and image plane. The latter motion is that observed in the image plane. Both of these motions are related to each other by the image system magnification. Hence, image plane relative motion is usually much less than the actual relative motion. However, any motion during an exposure gives rise to blurring of image plane detail. One question to be considered is how much blur can take place as a result of motion and still not be noticeable because of inherent blur deriving from the PSF of the rest of the imaging system. In other words, assuming that image motion and vibration blur cannot be removed completely, how much is tolerable before resolution and target acquisition capability are affected? This depends on focal length and system zoom.

A general method of OTF calculation is obtained by the line spread function (LSF) derived from image motion transverse to the optical axis. The MTF is derived as the modulus of the MTF or FT of the LSF, and the PTF is derived as the phase of the OTF. The LSF is the probability density function (PDF) of the histogram of the relative transverse displacement between object and sensor beginning at time t_s and ending at time $t_s + t_e$ where t_s is measured from the instant the sensor is first exposed and t_e is exposure time.

Recently a method of calculating motion OTF analytically has been developed for any type of motion. Also, methods to calculate motion OTF without a motion sensor have been derived for a sequence of consecutive images and even from a single motion-blurred image. All three methods have been used successfully in image restoration.

Optical Transfer Functions for the Atmosphere

Many properties of the atmosphere affect the quality of images propagating through it. There are atmospheric phenomena that give rise to attenuation of the irradiance of the propagating image, thus reducing the contrast of the final image. There are also atmospheric phenomena that cause blurring of detail. Both types of phenomena prevent small detail from being resolved in the final image, thus degrading image quality.

Electromagnetic (EM) wave absorption and scattering by the constituent gases and particulates of the atmosphere and airborne particulates give rise to attenuation. Scattering of photons by airborne particulates is manifested as deflections of the photons to directions other than that of the original propagation. If such scattering causes the deflected photons to miss the imaging receiver, then the scattering is manifested as attenuation. The received irradiance of the image propagated through the atmosphere is correspondingly diminished from that in the object plane. However, if the light scattering is at very small angles with respect to the original direction of the propagation, and several such small-angle scattering events take place, then forward-scattered radiation can take round-about paths and still be received by the imaging system together with the unscattered radiation. The net effect is image blurring caused by a multitude of angles of arrival at the imaging receiver of radiation emanating from the same point in the object plane. Many multiple-scattering paths give rise to a relatively large blurred-point image rather than a fine sharp-point image. Adjacent image plane points can then appear for a single object plane point, thus degrading image resolution. Such aerosol scatter blur is known as the adjacency effect.

Another effect of light scattering, particularly at large angles, is increased path radiance. The atmospheric background irradiance at wavelengths less than 2–4 μm, consists through the day of scattered background light such as sunlight. This atmospheric background radiation is imaged over the same image space as the received irradiance from the target plane. The result is decreased contrast of the target plane scene. At wavelengths larger than 4 μm, most of the path radiance is not scattered sunlight, but rather thermal emission of the atmospheric constituents, gases in particular. This thermal path radiance decreases contrast in thermal imaging systems, particularly in the longwave infrared (8–13 μm).

Turbulence results from variations in the atmospheric refractive index, which are random in both time and space. These refractive index fluctuations are caused by local fluctuations in atmospheric temperatures, pressure, humidity, etc., all of which are affected by wind speed, which in itself is also random in time and space. Generally, the larger the temperature and humidity gradients, the more serious the image resolution degradation caused by turbulence. The lower the wind speed, the stronger the impact of turbulence. Scattering and turbulence are basically two very different physical mechanisms, each exhibiting quite different properties. Time dynamic properties such as scintillations and image dancing derive from turbulence, while aerosol scatter light changes only slowly with time.

A point that must be strongly emphasized is that there is no such thing as a purely turbulent, purely scattering, or purely absorption atmosphere. All three properties occur simultaneously in the real-world atmosphere. Modeling and interpretation of experimental results must relate to all three processes. Any attempt to pretend otherwise is not realistic. In general, blur is caused by turbulence and small-angle scatter of light by aerosols and particles. Attenuation is caused by large-angle scatter and by absorption.

Generally turbulence blur is dominant for images near the ground, where ground heating gives rise to the turbulence. Aerosol blur is usually dominant at higher elevations, even as little as several meters above ground, depending on weather conditions and wavelength.

The product of both aerosol and turbulence MTFs (in the spatial frequency domain, after FT) yields approximately atmospheric MTF. The atmospheric MTF can be predicted according to atmospheric (meteorological) parameters. Aerosol MTF calculation is based on optical depth, which includes parameters such as scattering and absorption coefficients through the atmosphere over the imaging path. Turbulence MTF calculation is based on the refractive index structure coefficient, which includes parameters such as temperature, humidity, wind speed, etc.

By referring to the edge response in a given scene the atmospheric MTF may be calculated. The edge separating the wide white and black bars is imaged from the scene. The image of the edge is not a step function because of atmospheric blur. The gradient of the edge image is the LSF, from which the overall atmospheric MTF can be obtained after the FT of the LSF is divided by the hardware MTF.

Spatial Filtering

Spatial filtering is a process by which we can alter properties of an optical image by selectively removing certain spatial frequencies that make up an object, for example, filtering video data received from satellite and space probes, or removal of raster from a television picture or scanned image. In digital image processing, the term image refers to a two-dimensional light-intensity function, where amplitude at spatial coordinates (x, y) gives the intensity (brightness) of the image at that point.

Digital image processing techniques are oriented to transform, enhance, restore, or encode an image. Digital image restoration is on the basis of the OTF or even MTF alone describing the image degradation. Resolution is limited usually not by electronics or optics, but by image motion and vibration. For long-range imaging, the image quality may be limited by atmospheric effects.

By image restoration filters we refer primarily to spatial frequency filters placed in the spatial frequency plane in the optical data processor. Although data processing is done optically, the same mathematical concept is usually carried out with a digital computer. It is also possible to do restoration in the spatial domain. The simplest image restoration filter is the inverse filter. When noise becomes a problem, there are often used three classes of minimum mean square error estimations (MMSEE), which are the noncausal Wiener filtering, causal Wiener filtering, and Kalman filtering. Kalman and Wiener filters are proposed to obtain the optimum solution for the MMSEE problem in linear systems. Wiener filters are applied in linear time invariant systems, and Kalman filters in linear systems which may be either time invariant or time variant. A novel area of application for Wiener filtering is image restoration. On the other hand, if the estimation processes are partial and an ideal image is not obtainable, a Kalman filter may present better restoration results than a Wiener filter.



Figure 3 An example for satellite image restoration. (a) Original image of Beer-Sheva, Israel, from Landsat 7 satellite; (b) restored image after Kalman filter using aerosol and turbulence MTFs. Reproduced with permission of the American Society for Photogrammetry and Remote Sensing from Arbel D, Cohen E, Citroen M, Blumberg DG and Kopeika NS (2004) Landsat TM satellite image restoration using Kalman filters. *Photogrammetric Engineering and Remote Sensing* (PE&RS) 70(1): 91–100.

Figure 3 demonstrates the restoration result for a satellite image. Figure 3a presents an original Landsat 7 enhanced thematic mapper plus (ETM+) image of the city of Beer-Sheva, Israel. The image was recorded from 750 km satellite elevation. The image was recorded using an ETM+ sensor with 15 m ground resolution, and its wavelength range is 520–900 nm (Panchromatic band). Figure 3a is of 256 × 256 pixel size, which is a segment defined as a region of interest (ROI) in the original image. The scene was recorded on August 7, 1999 and was degraded (blurred) as a result of the meteorological conditions, which were measured and recorded (as data) at the same time. Figure 3b shows the restored image using the Kalman filter, which was based on the atmospheric MTF, which is obtained by using aerosol MTF with turbulence MTF. The restored image (Figure 3b) is more detailed. For example, roads and buildings were deblurred and became more accurate than in the original image (Figure 3a).

See also

Environmental Measurements: Optical Transmission and Scatter of the Atmosphere. **Fourier Optics**. **Holography, Techniques:** Computer-Generated Holograms. **Quantum Optics:** Quantum Computing with Atoms.

Further Reading

Arbel D, Greenberg S, Hadar O and Kopeika NS (2003) Criteria for satellite image restoration success. *Optical Engineering* 42(9): 2607–2613.

Arbel D, Cohen E, Citroen M, Blumberg DG and Kopeika NS (2004) Landsat TM satellite image restoration using Kalman filters. *Photogrammetric Engineering and Remote Sensing (PE&RS)* 70(1): 91–100.

Daniels A, Boreman GD and Ducharme AD (1995) Random transparency targets for modulation transfer function measurement in the visible and infrared. *Optical Engineering* 34(3): 860–868.

Gabor D (1948) A new microscope principle. *Nature* 161: 777.

Gabor D (1949) Microscopy by reconstructed wavefronts. *Proceeding of the Royal Society A* 197: 454.

Gabor D (1951) Microscopy by reconstructed wavefronts: II. *Proceeding of the Royal Society B* 64: 449.

Hadar O, Dror I and Kopeika NS (1994) Image restoration limits resulting from mechanical vibrations, part IV: real-time numerical calculation of optical transfer functions and experimental verification. *Optical Engineering* 33: 566–578.

Hadar O, Robbins M, Novogrozky Y and Kaplan D (1996) Image motion restoration from a sequence of images. *Optical Engineering* 35: 2898–2904.

Kopeika NS (1998) *A System Engineering Approach to Imaging*. Bellingham, WA: SPIE Press.

O'Donnell E (1987) Image steadiness: a critical factor in system performance. In: Wright R (ed.) *Electron Optical Imaging System Integration. Proceedings SPIE* 762: 51–56.

Stern A and Kopeika NS (1995) Analytical method to calculate optical transfer functions for image motion and vibrations using moments. *Journal of the Optical Society of America A* 14: 388–396.

Yitzhaky Y and Kopeika NS (1997) Identification of blur parameters from motion blurred images. *CVGIP: Graphical Models and Image Processing* 59(5): 321–332.

OPTICAL TWEEZERS

A Gajraj and J C Meiners, University of Michigan, Ann Arbor, MI, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The concept of radiation pressure or pressure from the propagation of light is not new. In the early seventeenth century, Johannes Kepler proposed that radiation pressure from the sun accounted for the fact that tails of comets always point away from the sun. In 1873, James Maxwell, on the basis of electromagnetic theory, showed that pressure should result from the absorption or reflection of a beam of light. However, early studies in the beginning of the twentieth century that attempted to detect and quantify the effects of radiation pressure were unsuccessful, mainly frustrated by thermal forces from temperature gradients that tended to obscure the weak effects of radiation pressure. It was only in the 1960s, that the advent of lasers provided a light source with the power to generate sufficient radiation pressure to overcome forces due to thermal effects.

As lasers became generally available in the early 1970s, Arthur Ashkin from the Bell Labs pioneered the development of optical tweezers. He showed that the forces of radiation pressure from focused laser beams could be used to affect the dynamics of small transparent micrometer-sized particles. According to Ashkin, his early experiments were motivated by simple back of the envelope calculations of the magnitude of the radiation pressure force of light on a totally reflecting mirror. Let us consider such a calculation: a photon of frequency ω has a momentum of $\hbar\omega/c$. For a total power of I, we have a flux of $I/\hbar\omega$ photons per second incident on the mirror. When the photons are reflected, they transfer a momentum of $2I/c$ to the mirror. The force exerted on the mirror for $I = 1$ W, is approximately 10^{-9} N. If the mirror is a 1 μm size particle weighing 10^{-15} kg, this force will induce an acceleration of 10^6 g!

In the following decade, Ashkin demonstrated that by focusing laser light using a high numerical aperture microscope objective, strong intensity gradients could be created to optically trap small dielectric particles such as microspheres. Ashkin named this trapping scheme a 'single-beam gradient force trap', now more commonly called optical tweezers.

Today optical tweezers are well-established and extremely versatile tools for the physical and life sciences. Using optical tweezers, forces up to 200 pN can be applied with a resolution of 100 aN on particles with dimensions on the order of the wavelength of light. Even particles as small as 5 nm can be trapped, rotated, positioned, and arrayed. Optical tweezers have been used in single molecule studies of biopolymers (DNA, RNA), in the manipulation of various types of cells and in cell sorting, in microsurgical procedures, as well as in viscoelastic studies of membranes, and protein. Optical tweezing has also been the key tool in the understanding of the workings of molecular motors such as myosin, kinesin, RNA polymerases, etc.

Theory

Optical tweezers trap dielectric particles using radiation pressure generated by a tightly focused beam of light from a laser. Depending on the size of the particle in relation to the wavelength of the trapping beam, there are two different mechanisms responsible for trapping small particles in a single beam gradient trap. For particles in the Mie regime, where the particle size is large compared to the laser wavelength, a simple geometric-optics model serves best. Figures 1a–c, illustrate possible cases of a Mie particle in an optical trap. Here, the particle is assumed to be a sphere that is transparent with a refractive index higher than that of the surrounding medium. The particle behaves as a convergent lens refracting and deflecting the beam when its center is displaced from the laser focus. In Figure 1a, the sphere is axially displaced from the focus, away from the microscope objective. Ray A is then refracted toward the surface normal as it enters and exits the sphere, causing a change in the momentum of the ray. Due to conservation of momentum, the sphere reacts with a force F_a in the opposite direction. The situation is similar for ray B. The gradient force, F, obtained from the vectorial addition of F_a and F_b, is directed toward the light source. At the same time, the scattering force, arising from back and scattered reflections, is directed away from the light source. It can be seen that above the focal point, the scattering and gradient forces act in the same direction, pushing the particle away from the light source (Figure 1b). For a particle in the focal plane, but transversely displaced from the trap center, the gradient force acts in a restoring direction pushing the bead into the trap focus (Figure 1c). At a location just below the focus, the scattering force balances the gradient force and stable optical trapping is achieved.



Figure 1 Ray diagram sketches showing three cases of particle trapping in the Mie regime. Rays A and B border the cone of light focused by a high numerical aperture microscope objective. The refraction of these rays gives rise to forces F_a and F_b, the resultant force F tends to restore axial and transverse displacements of the particle from the trap focus (at the intersection of dotted rays A and B).

This simple ray optics model can also be used to estimate the trapping force, an example of such a calculation is shown in Box 1.

For dielectric particles in the Rayleigh regime, where the size of the particle is small compared to the wavelength of the incident light, the particle acts as a simple dipole. The electromagnetic light wave polarizes the particle, inducing a set of oscillating dipoles. The dipoles respond to the electric field of the incident light in the direction of the gradient, resulting in the movement of the particle towards the focal point. Additionally, there is also a scattering force, acting in the direction of beam propagation, from light that is scattered or absorbed. While the scattering force is proportional to the electromagnetic field, the gradient force is proportional to the gradient of the electromagnetic field. Therefore, stable optical trapping can be achieved for a field with a gradient large enough to overcome the scattering force. This can be obtained by using a microscope objective with a high numerical aperture.

Stable trapping is achieved when the energy associated with the trapping significantly exceeds the thermal energy of the trapped particle, $\frac{1}{2}k_B T$ per degree of freedom. Since the optical gradient is weakest in the axial direction of the trap, the trap stiffness in this direction limits its stability. Furthermore, the trap is weakened in the axial direction by the scattering force, which pushes the microsphere away from the objective. To overcome this, two counterpropagating laser beams can be used, not only to increase the axial gradient of the trap, but also to provide a compensating scattering force in the opposite direction.

Force Measurement

Optical tweezers can be used as picotensiometers or highly sensitive force sensors. Measuring the displacement of a particle in a trap with known stiffness k, yields the force F given by

$$\mathbf{F} = -k \cdot x \qquad [1]$$

The displacement can be measured in different ways, ranging from video microscopy to light-scattering techniques. Some of these methods are discussed in the instrument design section below.

The trap stiffness is generally not known *a priori* as it depends on the shape and intensity of the trap, as well as the relative refractive index, shape, and position of the object in the trap. Since theoretical approximations are usually not accurate enough, the trap stiffness must be empirically determined and calibrated.

Various force calibration strategies have evolved over the years, however, they can be broadly divided into two types: (i) schemes that rely on the interaction of the optical trap with viscous forces; and (ii) those that exploit the thermal fluctuations of the trapped object.

Force Calibration by Viscous Drag

The conceptual basis for calibration by viscous drag is simple. A known force is exerted on a trapped object and the deviation in its position is measured as a function of the applied force. The trap stiffness can then be calculated from eqn [1]. Force can be exerted by either flowing liquid past the trapped object, translating the microscope stage while keeping the trap fixed, or translating the optical trap while keeping the sample fixed.

In a situation where the Reynolds number is small, inertial forces can be neglected and Stokes' Law gives the viscous drag force on a sphere of known radius r:

$$F_d = (6\pi\eta r)\nu = \beta\nu \qquad [2]$$

Box 1

Optical Tweezers in the Ray Optics Model

In a simple ray optics model, the trapped microsphere acts like a small lens on the incident laser beam. If the microsphere is not centered on the beam axis, the beam will be refracted. The corresponding change in the momentum of the laser beam gives rise to a restoring force on the microsphere.



Figure B1

A photon of frequency ω in a medium of refractive index n_1 that is deflected by an angle θ, as shown in Figure B1, acquires a lateral momentum of

$$\Delta p_x = \frac{\hbar \omega n_1}{c} \sin \theta \qquad [B1]$$

Momentum conservation requires a counteracting force on the microsphere, which is for a laser beam of intensity I

$$F_x = \frac{I n_1}{c} \sin \theta \qquad [B2]$$

Assuming that the deflection angle θ is given by the deflection of a beam that is incident on biconvex lens with curvature R and refractive index n_2 at an off-axis displacement Δx, we find for the restoring force on the microsphere:

$$F_x = \frac{2I}{Rc}(n_2 - n_1)\Delta x \qquad [B3]$$

which describes a linear spring with a stiffness of the optical trap of

$$k = \frac{2I}{Rc}(n_2 - n_1) \qquad [B4]$$

Here, η, the viscosity of the sample fluid, is known and immediately allows the determination of the friction coefficient β of the sphere. The fluid velocity, v, can be measured in the case of external fluid flow by either tracking the trapped object when the trap is switched off or measuring the speed of some other marker in the sample. If the stage is moved to generate the fluid flow, the velocity of the fluid surrounding the trapped object can be estimated from the motion of the stage. In either case, the drag coefficient, from eqn [2] may need to be corrected if the trapped object is close to the walls of the sample cell. This correction is well known as Faxen's Law, which accounts for hydrodynamic interactions between the trapped particle and the wall. These effects are particularly significant when the center of the trapped particle is less than a diameter away from the wall. The advantage of these fluid-flow calibration methods is that the trap stiffness at regions far from the trap center can be measured. The drawback is that, in general, only transverse trapping forces can be measured and the trapped objects have to be approximated as spherical or ellipsoidal.

Thermal Motion Methods

These methods measure the Brownian motion of a trapped particle to deduce the trap stiffness. A trapped particle experiences three forces: (i) the thermal forces due to collisions with surrounding solvent molecules; (ii) forces from viscous drag; and (iii) the restoring force of the trap. For low Reynolds numbers, where the inertial effects can be neglected for the microsphere, the equation of motion is

$$\beta \dot{x} + kx = F(t) \qquad [3]$$

Where β is the viscous drag, k is the trap stiffness, and $F(t)$ is a randomly fluctuating Langevin force due to thermal fluctuations. This motion of the microsphere in the trap at a temperature T is characterized by a Lorentzian power spectrum of the form:

$$x_f^2 = \frac{k_b T}{2\pi^3 \beta (f_0^2 + f^2)} \qquad [4]$$

where $f_0 = k/(2\pi\beta)$ is the corner frequency, above which the motion of the particle is Brownian.

To calibrate the optical trap by the corner frequency method, the motion of a trapped particle is observed and its power spectrum, which is the Fourier transform of the autocorrelation function, is calculated. Fitting the power spectrum to a Lorentzian function will yield the corner frequency f_0, which can be directly related to the trap stiffness k, provided that the drag coefficient β can be estimated.

Alternatively, the trap stiffness can be obtained directly from the time constant of the exponential decay of the autocorrelation function of the particle motion. The spring constant is the ratio of the drag coefficient to the time constant of the trap.

Another approach known as the mean square displacement method does not require the estimation of the drag coefficient but does require a well-calibrated position detector. In this method, the mean square displacement $\langle x^2 \rangle$ of the fluctuations of a trapped particle is computed from position data and then by the Equipartition theorem:

$$\langle x^2 \rangle = k_b T/k \qquad [5]$$

This enables a simple, straightforward calculation of k, the trap stiffness.

Design

Optical tweezing stations broadly fall into three categories: (i) stand-alone systems; (ii) systems incorporating an optical microscope; and (iii) completely configured commercially available systems. Stand-alone systems feature optical tweezers built around a microscope objective and suitable optical components. These systems provide the maximum flexibility and can be easily reconfigured to adapt to different experimental needs. Furthermore, they also tend to provide the best mechanical stability, if configured properly. Figure 2a shows a picture of a stand-alone optical tweezing setup from our laboratory. This system is capable of the basic tasks of trapping, holding, and positioning microscopic objects. The most common optical tweezing stations are integrated into commercial light microscopes as sketched in Figure 3. The advantage of these hybrid systems is that the commercial microscope provides a flexible, optimized optical imaging platform, in which the optical trapping system can be integrated with only moderate difficulty. Figure 2b shows a picture of a typical optical tweezing station built around a commercial inverted microscope and mounted on a vibration–isolation table. This system includes an acousto-optic modulator that enables beam scanning for line-tweezing experiments. At the time of this writing, optical tweezing systems range from less than $10 000 for basic demonstration stations to between $50 000 to $100 000 for more sophisticated hybrid systems.

Commercial fully integrated systems are available from P.A.L.M. Microlaser Technologies AG (Bernried, Germany), Cell Robotics, Inc (Albuquerque, NM, USA), and Arryx (Chicago, IL, USA). Figure 2c shows a commercial optical tweezers set-up available from P.A.L.M. Microlaser Technologies.

When designing an optical tweezing station, the first item to consider is the choice of laser system. A simple single beam tweezing system can be built around a laser with less than 100 mW of power. Even though the minimum power required for trapping is a few milliwatts in the laser focus, there is considerable power loss in the tweezing and microscope optics. Also, the trap stiffness and thus the maximum trapping force decreases linearly with intensity, therefore most optical tweezers typically use lasers with an output power of 1 W. In some special applications, when beam scanning or multiple traps are required, the power requirement can be significantly larger. The wavelength of the laser also affects the capability of the trap in that the optimum wavelength depends on the size of the objects that are to be trapped. In general, the strongest traps occur


Microscope objective
Movable X–Y stage
CCD camera
Focusing lens
Trapping laser beam path
Movable rail
(a)
CCD camera
IR laser
Axiovert S100 TV
Gimbal mirrors
Focusing lens
(b)
(c)



Figure 3 A sketch showing the instrumentation of a typical optical tweezing system incorporated into a commercial microscope.

for particles of size comparable to the wavelength of the laser. Another important concern in the choice of wavelength is possible damage to the sample from absorption and heating. In general, biological material is more transparent to the longer wavelengths of the IR spectrum. Studies on living cells have shown that generally, a range of wavelengths of 700 nm to 1100 nm, termed 'the optical window' of cells and tissue, is most suitable. Importantly, at higher wavelengths there is a reduced possibility of damage from multiphoton effects. DNA (260 nm) and proteins (280 nm) are strong absorbers in the ultraviolet range. Due to multiphoton effects, wavelengths between 700–800 nm have been seen to affect cell metabolism and lead to cell death within seconds. However, at wavelengths greater than 1000 nm, the simultaneous absorption of four photons required is unlikely at typical laser intensities used in trapping experiments.

The beam quality of the laser also restricts the choice of laser system. Diode lasers, in particular, have poor beam quality since the beam is often elliptical in shape and astigmatic, leading to a larger inefficient trap. Over the years, Nd-YAG lasers, at 1064 nm, have emerged as the lasers of choice, providing the best balance between price, power, and quality.

To achieve stable trapping it is essential to create an optical potential in which the gradient forces dominate the scattering force as discussed in the Theory section above. This suggests that the higher the numerical aperture (NA) of the microscope objective the stronger and more stable the trap will be. Oil or water-immersion microscope objectives with NA > 1.2 are commonly used. Further, this requirement also implies that the back aperture (rear entrance) of the microscope objective needs to be completely filled or, in the case of a Gaussian beam, overfilled to a certain degree to achieve optimal trapping efficiency. Since most commercial objectives are corrected for achromatic and spherical aberrations in the visual region of the spectrum, only

---

Figure 2 (a) A stand-alone tweezing station built around a microscope objective mounted on a vibration isolation table. (b) A typical tweezing station incorporated into a standard commercial microscope. This setup features dual-steerable optical traps and includes a CCD camera. Position detecting instrumentation can be mounted on the existing microscope stage. (c) The commercially available PALM® Combisystem utilizes an IR laser (wavelength 1064 nm) and a UV laser (wavelength 377 nm) coupled via the epi-fluorescence path to a research microscope. The system advertises automated and noncontact laser microdissection as well as trapping, sorting, and positioning. (**Figure 2:** (c), courtesy of P.A.L.M. Microlaser Technologies, Bernried, Germany.)

a small fraction of the working distance is usable for viable trapping. Normally this is limited to within 40 μm of the cover slip.

In addition to providing a beam large enough to overfill the back aperture, there are two other criteria that the external optics have to satisfy: first, the optical trap should be parfocal with the specimen plane. This enables the visualization of trapped objects. Second, the laser beam should be able to pivot around the back aperture without moving laterally to maintain the same degree of overfilling. This allows for a stable two-dimensionally movable trap. In practice, these requirements are fulfilled by using a telescopic system of lenses and Gimbal mounted mirrors. The latter are special mounts that enable a mirror to be tilted around its center position without lateral displacement. The telescope expands the incoming beam to fill the back aperture of the microscope objective and also images the back aperture onto the center of the Gimbal mounted mirror. As seen in Figure 4, since the back aperture of the microscope objective and the Gimbal mounted mirror are in conjugate planes, a small tilting of the mirror will only result in a change in the angle of the laser beam entering the microscope objective. The position of the beam will be unchanged, as will the degree of overfilling.

More sophisticated optical tweezer designs use acousto-optic modulators and galvanometer scanning mirrors to create scanning line tweezers and/or multiple traps. The basic approach is to deflect the laser beam to create multiple traps or to scan a single trap to create a one-dimensional potential well. Additionally, a new generation of holographic optical tweezers, capable of creating three-dimensional arrays of trapped particles, has emerged. Computer generated holograms that modify the phase and amplitude of the trapping laser are reverse engineered from the desired two- or three-dimensional optical trapping patterns. Furthermore, constructing such holograms from liquid crystal light modulators allows for dynamic control of the trapping pattern, yielding a fully computerized reconfigurable trapping system. An interesting example of the application of holographic optical tweezers to colloidal transport is shown in Figure 5, the first demonstration of 'kinetically locked-in states' where particles traveling across a potential mesh display a preference for certain paths.

It is to be noted that the optical tweezer is fundamentally a constant-extension technique, that is, it attempts to maintain the extension of a stretched molecule whereas the force is varied. However, it is of interest to study the action of molecular motors under constant force conditions. A basic optical tweezers setup can be modified to include an electronic feedback loop to provide constant force conditions. More recently, scanning-line optical tweezers have been adapted to implement all-optical constant force schemes that dispense with the need for electronic feedback.

An important aspect of any force measurement is the ability to accurately image and measure the position of a trapped particle. Standard digital video microscopy techniques yield a resolution of ~5 nm but have limited bandwidth and thus cannot be used for systems that employ feedback control of laser intensity or trap position. In these systems, the forward- or back-scattered trapping laser light from the trapped particle can be imaged onto a calibrated quadrant photodiode to provide sensitive position detection at high bandwidths (~1 kHz). If the photodiode is fixed in a plane conjugate to the back focal plane of the microscope objective, the trap can



Figure 4 A sketch showing the working of a gimbal mounted mirror in two positions (shown as shaded and as unshaded). For small tilts of the mirror, the beam is seen to 'pivot' about the back aperture of the microscope objective resulting in the displacement of the optical trap in the focal plane. Note that for both beams the degree of overfilling of the back aperture of the microscope objective is unchanged, a crucial requirement for movable traps.



Figure 5 Data showing the superimposed paths of approximately 18 000 micron-sized particles flowing across a 10 × 10 grid of optical traps created by holographic optical tweezers. The particles are deflected laterally assuming a path dictated by the potential energy landscape and display kinetically locked-in states. This technique can be used to sort particles based on size, refractive index or charge. (Picture courtesy of D. Grier.)

be moved without having to move or recalibrate the photodiode detector. Using the quadrant photodiode method 2- and 3-dimensional position sensing is possible. A further improvement is found in schemes that use an additional laser dedicated to position sensing. The most sensitive method, however, for position sensing is interferometry. In this scheme, the trapping laser beam is split into two orthogonally polarized beams that are recombined after passing through the microscope objective and the sample. For a particle perfectly centered in the trap, the resulting combined beam has a circular polarization. In other cases, the bead displacement is sensitively reflected in the ellipticity of the polarization.

Applications

Colloids

Optical tweezers have been widely used to probe the interaction in colloids and other complex fluids. In fact, an optical tweezer apparatus was included in the instrumentation on the International Space Station for use with colloidal crystallization experiments in space. Various aspects of colloidal interactions have been studied using optical tweezers including mutual- and self-diffusion coefficients, the effects of hydrodynamic and electrostatic interactions, and depletion layer effects. More sophisticated scanning-line tweezing setups have been used to probe entropically driven self-assembly and interactions of colloids in polymer suspensions.

Blinking optical tweezers provide an elegant method for positioning colloidal particles in configurations of interest in a solution. When the tweezers are switched off the colloids respond to their environment, reacting to thermal forces and interacting either with other colloids or interfaces. The trajectories of the released colloids can be tracked and analyzed in 2D using digital video microscopy or 3D if combined with an evanescent illumination scheme. Switching on the tweezers again results in a return to the initial configuration, yielding a reproducible and tightly controlled experiment to examine colloidal behavior.

Biopolymers

The study of biopolymers has benefited from the development of optical tweezers. By chemically attaching a trappable latex microsphere to a biopolymer of interest, the molecule can be stretched, positioned, or moved. Measuring the response of the biopolymer to these external forces yields useful information such as elasticity, rigidity, and domain unfolding characteristics. This information obtained at a single molecule level has provided invaluable insight into the relationships between the structure and function of biopolymers. For example, in an early tweezing experiment, characterizing the intrinsic elasticity of λ-phage DNA, it was discovered that the double-stranded DNA undergoes a reversible structural transition when stretched at forces greater than 65 pN, extending to about 1.7 times its crystallographic contour length. These studies complement well-established structural techniques, such as X-ray crystallography and NMR, which provide information in a force-free environment. Furthermore, by anchoring one strand of DNA to a surface and pulling on the other strand, unzipping forces for DNA have been measured. Optical tweezers have also been combined with other mechanical tools, such as a micropipette, and used as sensitive tensiometers. Protein folding and unfolding experiments are generally harder, as their contour length is shorter than that of typical DNA fragments. Nevertheless, the folding and unfolding behavior of single giant muscle protein, titin has been probed by attaching a different latex bead to either end of the molecule. The first bead is held by a movable micropipette and the second bead is optically trapped. As the micropipette is moved, the position of the optically trapped bead provides information about the forces required to unfold the membrane domains of the protein.



Figure 6 Observation of the stepping motion of the molecular motor kinesin. (a) A microsphere attached to a kinesin molecule is optically trapped; as the kinesin steps along a microtubule track which is immobilized onto a glass substrate, it pulls on the microsphere, whose motion is followed by an electronic feedback mechanism. (b) Motion of a single kinesin motor stepping against a 5 pN force. The data shows the discrete 8 nm steps of kinesin. (Figures courtesy of S. Block.)

Molecular Motors

Molecular motors (proteins that transduce chemical potential energy in to mechanical motion) have been the subject of intense attention since the early 1990s. Optical tweezers have played a crucial role in furthering the understanding of the mechanisms of molecular motors. The characteristics of molecular motor systems that have been studied with optical tweezers include speed, step-size, processivity, ATPs consumed per stroke, stall force, and static force. In fact, many of the advances in optical tweezers technology have been motivated by the study of molecular motors and have lead to spectacular results. An impressive example is the observance of the stepping motion of kinesin, as shown in Figure 6. Other experiments on molecular motors with optical tweezers have measured the stall force of motors as they move along their polymer track, or observed the transcription of DNA and RNA polymers, yielding interesting observations of the pauses during the transcription process.

Cells

The application of optical tweezers to cell biology was first demonstrated by Ashkin and co-workers in the late 1980s, by successfully trapping living objects: large viruses and bacteria. Since then, optical tweezers have been widely used to study various aspects of cellular biology. These include cell reproduction, growth, adhesion, mobility, and membrane elasticity. Additionally, the noninvasive nature of optical tweezers enables manipulations in the interior of an unopened object, allowing for the study of intracellular mechanisms by subcellular manipulations.

Optical tweezers have also been combined with various techniques to yield application-oriented tools for cell biologists. For instance, the combination of optical tweezers and state-of-the-art image recognition algorithms has been used to develop microfluidic cell sorters. In reproductive medicine, two of the major problems are penetration of the egg and sperm motility. A promising new solution combines laser zona drilling to pierce the egg envelope and optical tweezing to transport the sperm cells to the egg.

See also

Modulators: Acousto-Optics.

Further Reading

Ashkin A (2000) History of optical trapping and manipulation of small-neutral particle, atoms and molecules. *IEEE Journal of Selected Topics in Quantum Electronics* 6(6): 841–856.

Greulich KO (1999) *Micromanipulation by Light in Biology and Medicine: The Laser Microbeam and Optical Tweezers*. Basel; Boston; Berlin: Birkhauser.

Grier DG (2003) A revolution in optical manipulation. *Nature* 424: 810–816.

Lang MJ and Block SM (2003) Resource letter: LBOT-1: Laser-based optical tweezers. *American Journal of Physics* 71(3).

Sheetz MP (1998) *Methods in Cell Biology. Volume 55: Laser Tweezers in Cell Biology*. San Diego, CA: Academic Press.

Svoboda K and Block SM (1994) Biological applications of optical forces. *Annual Review of Biophysics Biomolecular Structure* 23: 247–285.

P

PHASE CONTROL

Contents

Phase Conjugation and Image Correction
Wavefront Coding

Phase Conjugation and Image Correction

E N Leith, University of Michigan, Ann Arbor, MI, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Phase conjugation of a wave is a process that has long been recognized. However, the technique for producing high-quality phase conjugation is relatively new. Also, the principal use of phase conjugation, the correction of phase errors in waves that have propagated through phase-distorting media, is relatively new, having originated in holography in the 1960s. Today, phase conjugation is an important area of modern optics. This article describes the conjugation of a wavefield by the process of holography and the holographic phase conjugation method of removing phase distortions from a wavefield, thereby permitting high-quality images to be produced from phase-distorted waves.

The basic meaning of a conjugated wave is explained with the aid of Figure 1. Figure 1a shows a wavefield propagating to the right. For simplicity, we show only one wavefront, i.e., one contour of constant phase. It is understood that a wavefield consists of a sequence of such wavefronts, with each wavefront differing in phase by 2π from the adjacent one, and separated by the wavelength λ. Of the two points, A and B, on the wavefront, we say that the wavefront at A lags that at B, since when the wavefront crosses a plane normal to the direction of travel, point A of the wavefront crosses that plane behind point B. The wavefield produces, at the plane P, a field $ae^{i\phi}$, where a is the amplitude and ϕ is the phase of the wavefront at the plane P.

We place a phase conjugator in the path of the wave. The wave passes through the conjugator, emerging as a phase conjugated wave, in which the point B, which formerly led point A in phase, now lags behind it by a corresponding amount. This illustrates the basic meaning of the term ‘phase conjugation’. This device could be considered as a forward phase conjugator, since the phase conjugated wave travels in the same direction as the original wave.

Next (Figure 1b) we describe a backward phase conjugator. The conjugate wave travels in a direction opposite to that of the incident wave. The conjugate wave emitted by the phase conjugator seems to be



Figure 1 A phase conjugator. (a) shows a forward phase conjugator; (b) shows a backward phase conjugator. For clarity, in (b) the conjugated wave is shown with dotted lines. PC is phase conjugator, and P is the entrance plane of the conjugator.



Figure 2 Light reflected from mirrors. (a) Light falling on a conventional mirror and being reflected; (b) light reflected from a conjugating mirror; (c) as in (b), except that illustration is with wavefronts instead of rays.



Figure 3 A ray of light reflected from a retroreflector (or corner cube).

identical to the incident wave; we show the two waves to be in coincidence, or more precisely, for purposes of clarity, almost in coincidence. The points A on the two wavefronts coincide, as do the points B. As before, on the incident wave, point A lags behind point B. On the exiting wave, since the wave is traveling in the opposite direction, point B is now lagging point A, i.e., is lagging in phase. In either case, forward or backward conjugation, the wave emerging from the conjugator has the complex amplitude $a(x,y)e^{-i\phi(x,y)}$.

A phase conjugator (backward variety) is like a mirror, in that it obeys the basic mirror law, that the angle of reflection equals the angle of incidence, but in a rather different way, as Figure 2 shows. In fact, the reflected ray travels back on itself. A simple way to generate a conjugate wave, and one that has been known for a very long time, is with the use of an array of retroreflectors, or corner cubes. As shown in Figure 3, each ray undergoes two reflections and emerges traveling in exactly the opposite direction, although with some displacement. If we considered the third dimension, there could be three reflections. The amount of displacement depends on where the ray strikes; if it strikes near the apex of the corner cube, the ray displacement will be slight; if at the edge, the displacement is greatest. Thus, the image formed in reflection is degraded. This geometrical degradation is greater for larger corner cubes. Thus, why not make the cubes very small? Then, however, the image is degraded by diffraction effects, since each corner cube constitutes a small aperture. Thus, there is an optimum size for the cubes; if too large, geometrical factors degrade the image; if too small, diffraction effects degrade the image.

Phase Conjugation by Holography

With holography, however, came a method of conjugating a wavefront that yields high-resolution imagery. The holographic process inherently produces a phase conjugate image, as was noted by Gabor in his early papers on holography. The holographic process is illustrated in Figure 4. For simplicity, we assume the object to be a planar transparency $s(x,y)$. A coherent light wave, generally a plane or spherical wave, passes through the transparency and a diffracted field u is produced at the recording plane P, as in Figure 4a. The field u is typically the Fresnel diffraction pattern of the object s, but if the propagation distance is sufficiently great, u could be the Fraunhofer pattern of s. Of course, lenses can be placed between the object and recording planes, thus modifying the diffraction pattern.

The field u is combined with a reference wave u_o, which is generally an off-axis planar or spherical wave. The two beams produce an interference pattern with intensity

$$I = |u_o + u|^2 = |u_o|^2 + |u|^2 + 2Re\, u_o^* u \qquad [1]$$

where the final term can be written as $u_o^* u + u_o u^*$; the * denotes complex conjugate. The process of forming the interference of the two beams, i.e., forming the intensity of their sum, has generated the conjugate term u^*. When the intensity is recorded, as on photographic film, for example, both terms are stored on the film. Suppose for simplicity that u_o is a plane wave $a_o e^{i2\pi f_o x}$, where a_o is a constant, and $f_o = (\sin\theta)/\lambda$, where θ is the angle that the reference wave makes with the optic axis and λ is the wavelength of the light. Also, u can be



Figure 4 The holographic process. (a) Making the hologram; (b) reading out the hologram, using a readout beam that duplicates reference beam; (c) reading out with reversal of reference beam.

written as a product of an amplitude term a and a phase term $e^{i\phi}$, or $u = ae^{i\phi}$. Let the photographic plate, after exposure and development, have a transmittance t proportional to the intensity I, or $t = kI$, with k a constant; this is an oversimplification of the recording process, but preserves the essence of the holographic process. Now let the photographic plate, which after development becomes a hologram, be illuminated with a readout wave that, for simplicity, we let be u_o, a duplicate of the reference wave. Then, the field emerging from the hologram is

$$u_e = u_o k\Big[|u_o|^2 + |u|^2 + u_o^* u + u_o u^*\Big] \qquad [2]$$

Only the last two terms are of interest. These can be written as $k|u_o|^2 u$ and $ku_o^2 u^*$, respectively, or alternatively, as $ka_o^2 a e^{i\phi}$ and $ka_o^2 a e^{i(4\pi f_o x - \phi)}$. The term $k|u_o|^2 u$ represents a wave that is, to within a constant, identical to the object wave u; the other term represents a wave that is, to within a constant and a linear phase term, a conjugate of the original wave. The factor $e^{i4\pi f_o x}$ has the physical meaning that the wave is propagating in a direction 2θ given by $\sin 2\theta/\lambda = 2f_o$. The readout waves are shown in Figure 4b.

The so-called true wave u and the conjugate wave u^* thus propagate angularly away from each other and from the direct transmitted beam, which carries the uninteresting components $|u_o|^2$ and $|u|^2$.

However, a more suitable way to form the conjugate wave is to illuminate the hologram with a readout wave that is, again, a duplicate of the original reference wave, but propagating in the opposite direction, as in Figure 4c. The conjugate wave is now propagating along the z axis, along the path of the original object wave. It is readily shown that this counterpropagating wave is identical in shape to the original object wave recorded by the hologram, except that it travels in the opposite direction, exactly the situation portrayed in Figure 2. This wave propagates so as to form an image that is, to within a constant, identical to the original object, except for the counterpropagation, which produces a conjugate image $s^*(x, y)$. The image intensity, however, is $|s|^2$, which is identical to the original image intensity.

This conjugate wave was, in the early days of holography, a detriment, since without the use of the off-axis method (reference wave introduced at an angle to the object wave) the two images were inseparable, and the true image could be observed only against the background of the defocused conjugate image. Thus, an out-of-focus image overlaid the true image, making it noisy.

In 1962, the same year that the off-axis reference wave for separating the two images was introduced, a possible use for the conjugate image was suggested. If the original propagation path of the object wave were aberrated, as would occur if the wave propagated through an irregular medium, then the conjugate wave propagating through the medium would undergo a correction and would arrive at the original object position perfectly corrected, resulting in a sharp image, a process sometimes called wavefront healing. The idea lay dormant for 3 years, until in 1965, experimental demonstration of this idea was reported. In one case, the object was a transparency containing opaque lettering against a transparent background and the inhomogeneity was a piece of frosted glass, which resulted in extremely severe aberrations, so that the object wave, having traversed the diffuser, was no longer capable of forming an image. However, when the distorted wave was recorded holographically, conjugated, and sent back through the same diffuser, the result was a highly legible image.

The principle of wavefront healing is illustrated in Figure 5, when the inhomogeneity is an extended, or three-dimensional, structure. A point object O sends a spherical wave into the inhomogeneity. As the wavefront propagates, it becomes distorted, and loses its sphericity. When it emerges from the inhomogeneity, the wavefront is highly distorted.



Figure 5 The wavefront healing process. C is the conjugator, I is the inhomogeneity, and O is a point object.

The wave is conjugated at the conjugator C and emerges as a back-propagating wave that retraces the original wave path through the inhomogeneity, gradually losing its aberrations and looking more like a spherical wave. When it emerges from the inhomogeneity, it is a perfect spherical wave that converges to a point image that coincides with the original object. At each plane throughout the inhomogeneity, the back-propagating conjugate wave (dashed lines) has the same shape as did the original wave when it crossed that plane (solid line).

This interesting wavefront healing property of holographic phase conjugation was the beginning of a new branch of optics, called phase conjugation, giving rise to a number of applications. However, the holographic method had the problem that it did not occur instantaneously, but had to await the processing of the photographic film on which the hologram was recorded. This delay limited the range of potential applications. Later, in the 1970s, nonlinear crystals became available that did the equivalent of holography, but in real time, or near real time – a process known as four wave mixing. There are yet other types of real-time phase conjugators with nonlinear devices.

Pseudoscopic Image

As long as the object is only two-dimensional, a function of x and y only, with no extent along the axial dimension, z, the intensity distribution of the true and conjugate images is identical. The conjugateness, being a pure phase phenomenon, disappears when the observable is the image intensity $|s|^2$, and not the complex amplitude s. Since the intensity is always the observable, whether the image is viewed by eye, or with a camera, the conjugateness generally is of no significance.

However, when the object for holography is three-dimensional, the situation is different, and the conjugate image exhibits some strange properties. These arise from conflicting cues pertaining to the three-dimensionality of the image. To explain, we review some basics about how a three-dimensional world is perceived by a viewer. First, there is the stereo effect, resulting from the viewer having two eyes, with each eye seeing an object from slightly different positions, a phenomenon called binocular disparity. The mind uses this stereo effect to perceive three-dimensionality. But there are other cues that also contribute to perception of three-dimensionality. Another is parallax; as the viewer moves his head, objects farther from the observer change their angular position more slowly than objects close by. The observer can sense the three-dimensionality of an object, even with only one eye, by moving the head, thereby inducing parallax. Also, there is interposition, whereby near object portions block the viewing of object portions lying behind them, again giving a sense of depth. There are still other cues, more subjective, such as perspective, parallel lines converging toward infinity, shadowing, etc. With these observations in mind, we consider the hologram under illumination and the two images that it forms (Figure 6). As depicted in Figure 6, these two images lie in mirror symmetrical positions relative to the hologram. Both images have the same side facing the hologram. It must be this way, because when the hologram was recorded, it was side **a** that faced the recording plane. And both images must therefore have side **a** closer to the hologram.

When a viewer observes the true image (a virtual image), he views it looking through the hologram, and he sees the image at the position where the original object was when the hologram was recorded, and it is, in its visual properties, indistinguishable from the actual object; it has all of the three-dimensional and the parallax properties that the original object would exhibit. However, when the viewer observes the conjugate image, he must view it


Observation of true image
Photographic plate (hologram)
Incident light
b
a
True image
a
b
Conjugate image
Observation of conjugate image

Figure 6 Formation of the true and conjugate images from a hologram.

from the side of the image opposite from the hologram, i.e., he views the image from the back side. When a viewer observes the conjugate image, he sees it from the back side (side **b**). All of the above cited cues are in agreement about the orientation of the image, viz., that side **b** is closer to the observer than is side **a**. That is, all cues but one. The conjugate image is formed as the hologram recording plate saw it, with side **a** being closer. Thus, all interpositions are formed with the same relation that the object had with respect to the recording plate. The side **a** is the part of the object that was closer to the hologram, so that when interpositions occur, side **a** blocks side **b**. Since the observer thus sees side **a** partially obscuring side **b**, he must conclude that side **a** is closer than is side **b**. However, this observation is in direct conflict with the other cues, especially the stereo and the parallax cues, which are themselves strong cues, as is the interposition cue. The conflict of these cues, with two of them interpreting the image as being formed with one depth orientation, the other with the opposite, gives a number of strange effects. For example, as the viewer moves his head so as to induce parallax, the object appears to rotate. If the image is that of a human head, for example, the observed effect is that as the viewer changes his position, the head appears to rotate in synchronism with the observer, as if the image had its gaze fixed on the viewer, an effect that is often perceived as being eerie.

Similarly, if the object were two flat plates, (Figure 7) in the situation depicted, the planes have no overlap, i.e., no interposition, as seen by the observer. And the observer unequivocally perceives plate A as being closer than plate B. However, if the viewer moves his head to a position where interposition occurs, the conflict of cues arises, A becomes partially blocked by B, which is quite correct as observed at the position of the hologram, but is quite incorrect from the viewer's vantage point. The result of this conflict is that the viewer, who previously perceived the three-dimensionality, now sees the three-dimensionality perception suddenly collapse, and the sense of three-dimensionality is lost. Other strange perception anomalies can also be produced. Such images, with conflicting depth cues, are called pseudoscopic, as opposed to orthoscopic images, where the cues do not conflict.



Figure 7 Pseudoscopic conjugate image formed from an object consisting of two plates. The viewer V perceives plate A as being closer than B and there are no conflicting cues, since there is no interposition. However, if the observer moves his head upward, there is partial interposition, thus conflicting cues, and the sense of three-dimensionality is lost.

One Way Phase Conjugation

A significant limitation of phase conjugation aberration correction is that the image and object are on the same side of the inhomogeneity. One would usually want them to be on opposite sides. In a modified form



Figure 8 One-way phase conjugation. Top: Making the hologram. Bottom: The viewing process. We show three points on the object. The center point forms a well-corrected image, but the other two points produce imperfectly corrected images.

of the phase conjugation process, shown in Figure 8, this result is achieved. The first step of the process is carried out by passing a plane wave, instead of the object wave, through the inhomogeneity. This plane wave originates from a point source located at the focal plane of a collimating lens. The plane wave thus carries information about the inhomogeneity to the recording plate, where it is combined with a reference wave and a hologram of the distorted plane wave is recorded. Thus, information about the phase defect is stored on the hologram.

Next, the hologram is read out, not with a counterpropagating replica of the reference wave as before, but instead with an object-bearing wave that passes through the hologram. This wave emerges from the hologram and now has on it the recorded aberration information. As it counterpropagates along the path of the original object wave, it passes through the inhomogeneity, whereupon the aberration is cancelled and a corrected image forms at the focal plane of the collimating lens, where previously the point source had originated. The goal is achieved; the object and the corrected image are now on opposite sides of the inhomogeneity.

This correction is only approximate. To explain, we think of the object as being a collection of many points. The radiation from each point is converted into a plane wave by the lens, with different object points producing plane waves propagating at different angles. These plane waves then impinge on the hologram and emerge with each one bearing the aberration stored on the hologram. They continue on their paths and enter the inhomogeneity. The plane wave component, whose path direction matches that of the reference wave used in recording the hologram, will emerge from the inhomogeneity as a perfectly corrected wave, thus forming a well-corrected point image at the position of the original point radiator. However, another plane wave component, traveling in an incorrect direction, will be laterally displaced from the proper position for entering the inhomogeneity, and the aberration correction will be imperfect, the degree of imperfection being in direct relation to this displacement error. The displacement error is the product of the angular error and the propagation distance between hologram and inhomogeneity. If the inhomogeneity is slowly varying as a function of x and y, and if the object does not have a large extent, so that the range of angles is small, the image degradation will be small.

If the last two conditions do not apply, two options are available. First, the distance between inhomogeneity and hologram can be reduced, either by bringing the hologram closer to the inhomogeneity, or by imaging the hologram onto the inhomogeneity. The correction is now valid over a wider extent of the image, especially if the inhomogeneity can be treated as planar rather than extending over a volume. Alternatively, a scanning process can be carried out on the object beam falling on the hologram, so that in sequence, each plane wave component assumes the proper angle to counter-propagate along the path for perfect correction, and will form a well-corrected image point. This output spot then falls on a pinhole positioned to separate it from other, imperfectly corrected points. Then, over time, all points of the object will form well-corrected image points, and the entire object will thus be well-imaged. The one way phase conjugation method was first used to correct the spherical aberration of a lens, and the result was quite successful.

Phase conjugation has become an important branch of modern optics. The process is often carried out using photographic materials. More often nowadays, it is carried out using nonlinear crystals. Some of the crystal methods are essentially holography in real time, but others, such as phase conjugation by Brillouin scattering, go beyond holography.

See also

Nonlinear Optics, Basics: Nonlinear Optical Phase Conjugation. **Phase Control:** Wavefront Coding.

Further Reading

Caulfield HJ (ed.) (1979) *Handbook of Optical Holography.* New York: Academic Press.

Goodman JW (1996) *Introduction to Fourier Optics*, 2nd edn. New York: McGraw-Hill, chap. 9. This chapter is devoted to holography, with section 9.12.3 dealing with phase conjugation aberration correction.

Kogelnik H (1965) Holographic image projection through inhomogeneous media. *Bell Systems Technology Journal* 48: 2451–2452.

Leith EN and Upatnieks J (1965) Holograms: their properties and uses. *SPIE Journal* 4: 3–6. This is the earliest publication demonstrating the principle of wavefront healing by holographic phase conjugation.

Smith HM (1975) *Principles of Holography*, 2nd edn. New York: Wiley.

Wavefront Coding

W T Cathey, University of Colorado, Boulder, CO, USA

E R Dowski, CDM Optics, Inc. Boulder, CO, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

We describe a new paradigm for designing imaging systems that have performance that is otherwise unobtainable. These are hybrid systems that use the optics of the system to acquire an 'intermediate' image, which is processed to produce the final image. The optical components of the system are designed jointly with signal processing to optimize overall performance. It is possible to extend the depth of field of an imaging system, for example, by a factor of eight to ten. On the other hand, by concentrating on the increase of the depth of focus in the detector plane, it is possible to use that increase in the depth of focus to make the system invariant to focus-related aberrations. By doing this, it becomes possible to design a single-lens imaging system with small f-number and large field of view. Another example of the sort of new imaging system that can be designed is a two-lens zoom lens that images with a large field and a very short overall length.

First, the term 'Wavefront Coding' is defined as employed with imaging systems, and a description is given of how such coding is achieved. Examples of means of applying Wavefront Coding are given along with the analysis and design tools that are useful in designing hybrid optical/digital imaging systems. Finally, some potential future applications of Wavefront Coding in imaging systems are suggested.

Background and Basic Concepts

Some early suggested modifications to imaging systems can be viewed as wavefront modification, even though they were not described in that manner at the time. These include the work of Ojeda-Castañeda that described masks to block portions of the lens to extend the depth of field. In addition, it has long been known that the depth of field is slightly greater in lenses that have spherical aberration. In both of these cases, the wavefront is modified, in one case by changing the wave amplitude, and in the other by a deviation from the traditional ideal phase front. However, in both cases, the increase in the depth of field was only a few percent. Häusler extended the depth of field by requiring that the focus be continuously changed during the exposure time of the camera. This resulted in a modulation transfer function (MTF) for the imaging system that was the incoherent superposition of a spread of MTFs for the different foci during the exposure. To form an acceptable image, signal processing was used.

The use of Wavefront Coding here refers to new optical systems arrived at by designing the modulation of the wave and signal processing to achieve previously unobtainable imaging modalities. These new imaging systems can have more than an order of magnitude increase in depth of field, for example. The coding of signals so that particular information is optimally conveyed is not new. For example, in radar, coding of the pulses is done to optimally provide information concerning a target's range. At the radar receiver, signal processing is required to extract the range information. In a similar manner, an imaging system can have a coded wavefront in order to provide range or misfocus information in a manner such that signal processing can easily extract the desired information in the scene. Alternatively, the wavefront can be modified so that the imaging system is invariant to object depth or to misfocus of the system, so that, after processing, good resolution can be obtained over a large image depth.

A primary feature of Wavefront Coding in imaging is that the optical image-gathering portion of the system can be designed in combination with the design of the signal processing. This is normally not done in the design of imaging systems. It is done, however, in tomography, coded aperture imaging, and sometimes, interferometric imaging. In 1984, a group pointed out the potential of increasing the performance of imaging systems by jointly designing the optics and the signal processing. Since that time, major advances have been made in doing this. Now, several analysis and design tools are available, and are described in the following section.

Theory and Applications of Wavefront Coding

Wavefront Coding refers to a modification of the imaging system by placing specialized phase plates (or phase and amplitude masks) in the aperture stop, or in an image of the aperture stop, of the imaging system. This could be a phase plate as a separate optical element, or, if a surface of a lens is close to the aperture stop, the Wavefront Coding surface can be superimposed onto the normal lens surface. Processing to decode the image that is formed by the detector array (the intermediate image) is related to the coding that is impressed on the wavefront. The term 'signal processing' also includes the spatial integration provided by the width and height of the pixels. The final image is hence a function of the optics that form the intermediate image and the signal processing that produces the final image.

In the following section, we discuss the Woodward function as used in analysis and design of hybrid imaging systems, and show visualizations of the effect of Wavefront Coding on the image performance of two dramatically different types of systems. Then, other design techniques are discussed for imaging systems using Wavefront Coding and several examples of systems are given where the depth of field of imaging systems is extended by at least an order of magnitude. By concentrating on the increase in the depth of focus, rather than the depth of field, very simple imaging systems can be designed where Wavefront Coding makes the imaging system invariant to focus-related aberrations, and the shape of the lens is used to minimize the other aberrations.

Wavefront Coding Theory

The Woodward function

P. M. Woodward showed that the capability of a radar system to estimate both the range and the velocity of a target can be described by a mathematical function that became known as the Ambiguity Function. The Ambiguity Function shows how well systems that use different types of radar pulses can measure the transit time of the pulse (hence the range to the target) and the Doppler shift in the frequency of the returned pulse (hence the velocity of the target). Because the parameters, range, and Doppler, are measured with different accuracy, there is ambiguity in the measurement, and the Ambiguity Function is a display of the tradeoffs that are possible, Brenner, Lohmann, and Ojeda-Castañeda showed that the same mathematical function, with differently defined variables, can represent the Optical Transfer Function (OTF) of a one-dimensional imaging system.

The Ambiguity Function for a radar system is given by

$$A(u, v) = \int P(x + u/2)P^*(x - u/2)\exp(\mathrm{i}2\pi vx)\mathrm{d}x \quad [1]$$

where $\mathrm{i} = \mathrm{sqrt}(-1)$, * denotes complex conjugate, u is time, v is frequency, x is a dummy variable, and $P(x)$ is a complex function representing the transmitted waveform of the radar system. The OTF of a one-dimensional imaging system for different values of misfocus can be written as

$$H(u,\psi)=\int\Big\{P(x+u/2)\exp(j(x+u/2)^2\psi)\Big\} \times\Big\{P^*(x-u/2)\exp(-j(x-u/2)^2\psi)\Big\}\mathrm{d}x \qquad [2]$$

where $P(x)$ represents the complex pupil function of the imaging system. The misfocus parameter ψ can be shown to be equal to the physical parameters:

$$\psi=(\pi L^2/(4\lambda))(1/f-1/d_\mathrm{o}-1/d_\mathrm{i}) =2\pi W_{20}/\lambda=kW_{20} \qquad [3]$$

where L is the one-dimensional length of the aperture, and λ is the center wavelength of the narrowband illumination. The distance d_o is measured between the object and the first principal plane of the lens, and d_i is the distance between the second principal plane of the lens and the image plane. The focal length of the lens is given by f. The wavenumber is given by k and the traditional misfocus aberration constant is given by W_{20}. A comparison of the form of the ambiguity function and the OTF shows that:

$$H(u,\psi)=A(u,u\psi/\pi) \qquad [4]$$

The mathematics of the Woodward function as used for the Ambiguity Function has been studied extensively. Hence one can apply the theory that was worked out for the Ambiguity Function to the study of imaging systems. This gives a tool that is, in many ways, more powerful than other forms of three-dimensional optical transfer functions. For example, it can be shown that the squared volume under the Woodward function is a constant. This means that whatever one does to modify the Woodward function, there is a constraint on what can be done. Another constant is the power under a vertical cut of the Woodward function at a particular value of spatial frequency. This means that there is constant power for all misfocus values at any given spatial frequency. It can be bunched up about the normal in-focus position, or it can be spread out as shown below, but the squared area does not change.

Examples of the Woodward function for different imaging systems

A display of the Woodward function for a high-quality, one-dimensional lens is shown in Figure 1a. The horizontal line and the slanted line represent in-focus and out-of-focus slices through the Woodward function. A projection onto the horizontal axis gives



Figure 1 (a) The Woodward function for a high-quality one-dimensional lens with slices that represent in-focus and out-of-focus imaging. (b) The corresponding values of the modulation transfer function for those two cases.

the OTFs for those two focal conditions. The magnitudes of those two OTFs, the MTF, is shown in Figure 1b. Note that the out-of-focus MTF goes through a zero, where there is a phase shift, which gives a contrast reversal in the image.

Extended depth of field. Figure 2a shows the corresponding display of the Woodward function for a one-dimensional lens with a cubic phase function, $\phi = \alpha x^3$ added in the aperture stop. The appearance of the Woodward function immediately shows that this imaging system will have an increased depth of field, because the Woodward function shows that the energy is spread over a larger misfocus region. The slices in the Woodward function are taken for the same misfocus values as were used for the images in Figure 1. Notice that the MTFs of Figure 2b are very similar, and that the MTF for the misfocused case does not go through a zero. This implies that the imaging system will have an extended depth of focus.

The analogy to the Ambiguity Function of radar was key in selection of the cubic function for early demonstrations of extending the depth of field of an imaging system. Work in the radar field had shown that a radar pulse, where the carrier frequency increases quadratically with time, has an Ambiguity Function that is identical to the distribution in Figure 2a. Because a quadratic in time is a cubic in phase, the cubic phase function:

$$\phi = \alpha x^3 \qquad [5]$$

was selected as one that will provide the same Woodward function, and hence an increase in the depth of field. Many families of phase distributions have now been found that extend the depth of focus of an imaging system.

Antialiasing. When the resolution of the optics of an imaging system exceeds the resolution of the image detector array, the high spatial frequencies cannot be detected. They are not lost, however. When a spatial frequency is sampled below the Nyquist sampling rate, the high spatial frequency shows up, or aliases, as a lower spatial frequency. This aliased frequency is equal to the sampling frequency (determined by the pixel spacing) less the difference between the high frequency that has been undersampled and the sampling frequency. This results in an image with broad bands (low spatial frequencies) across the image as is often seen in television images of patterns with high spatial frequency content, such as striped shirts. Because the signal power at a given spatial



Figure 2 The Woodward function and the modulation transfer functions for a high-quality one-dimensional lens that has a phase plate with a cubic profile in the aperture stop. (a) The Woodward function showing a broadened pattern that is indicative of an increased depth of field. (b) The MTFs that are associated with the slices that represent in focus and out of focus.

frequency over all misfocus (the squared area under a vertical slice of the Woodward function at that spatial frequency) is constant, these frequency components cannot be removed. They can, however, be reduced at a given focus value by spreading the Woodward function vertically. Figure 3 shows a Woodward function that would be ideal. Below the cutoff spatial frequency, all of the signal power is in the focal plane, and beyond the cutoff frequency, the power is spread as much as possible over a large misfocus region. There is no assurance that a phase distribution can be found to give a desired Woodward function, however. Figure 4 shows the effect of one phase function, given by

$$S(r, \theta) = r^3 \cos(3\theta) \qquad [6]$$

upon the MTF of the imaging system. The dashed vertical line shows the cutoff spatial frequency that is due to the sampling rate of the pixels. Note that in Figure 4, the magnitude of the Wavefront Coded spatial frequencies that are aliased have lower values than do those that are passed by a traditional full aperture F/2.5 system. Stopping the traditional system down to F/25 reduces the aliased MTF to an amount close to that obtained with the wide aperture and Wavefront Coding, but it also reduces the amount of light by a factor of 100.



Figure 3 The Woodward function for an ideal antialiasing filter.

Wavefront Coding in Imaging Systems with Extended Depth of Field or Focus

Figure 2 shows the Woodward function for one phase distribution (cubic in x and y for a two-dimensional imaging system) that increases the depth of field of an imaging system. The cubic function was selected by using analogies to the Ambiguity Function of radar. Even though it is doubtful that this phase distribution could have been found by using conventional lens design techniques, it is instructive to show the ray traces and point spread functions that are obtained when this phase distribution is used in the aperture stop.

Ray trace analysis

Figure 5 shows the ray trace from a point object through a conventional (one-dimensional) lens and through a lens that has been modified with the cubic profile of eqn [5]. Figure 5a shows the rays through a conventional lens coming to a focus, and Figure 5b shows the corresponding rays as they go through a lens with a cubic profile added. In the latter case, the



Figure 4 Normalized MTFs for traditional optics and Wavefront Coding. The full aperture F/2.5 system has a large amount of optical power beyond the detector cutoff frequency of 50 lp/mm. With Wavefront Coding the aliased optical power can be greatly reduced. The traditional system aperture needs to be reduced to F/25 to compare to the antialiasing performance of the Wavefront Coded system. This reduction reduces the light level by a factor of 100 in comparison with the F/2.5 system.

rays cross, but have a relatively constant ray density in the region of what was the focal region. Figure 6 shows experimentally acquired point spread functions (PSF) for both cases. Note that the PSF changes very little over the region of misfocus. After signal processing, the PSF can be brought back to that of the conventional imaging system when in focus. Figure 7 illustrates the effect of the signal processing upon the intermediate image that is acquired by the optics. The object is a tilted bar pattern, so that a portion is in focus, and the remainder of the bar pattern is so far out of focus that there is a contrast reversal in the image. With the system that has a coded wavefront to give an extended depth of field, the entire image appears to have the same blur, no matter which part of the tilted bar pattern is observed. This is because the same PSF is convolved with the object distribution for all regions of misfocus. Signal processing removes the effect of the modified PSF, resulting in the image of Figure 7b. Figure 7c shows a trace through the image of Figure 7b. The amount of the misfocus that can be tolerated is a design parameter, and is discussed in the next section.



Figure 5 Ray traces from a point object through (a) a conventional one-dimensional lens, and (b) a lens that has been modified to have a cubic profile on the surface.

Signal processing requirements

It is necessary to do signal processing when using an imaging system that employs Wavefront Coding; the signal processing is needed to 'decode' the image that is formed by the detector array. This intermediate image is not a clear image. To obtain an intermediate image, the object distribution is convolved with a PSF, or impulse response, that has a shape similar to that



Figure 6 Point spread functions for a conventional lens in focus (a) and with large misfocus (b), and a lens that has been modified to have a cubic profile on the surface when in focus (c) and with a large misfocus (d).

of Figure 6c and d. To obtain the final image, the intermediate image must go through a deconvolution with the PSF. Because of the square law detection that occurs in the detector array, this deconvolution does not simply undo the effects of the convolution with the PSF that describes image formation. A straightforward digital convolution is required in most cases, and has been shown to run at video frame rates in software.

Parameter trade offs in imaging systems with extended depth of field

Depth of field and signal-to-noise ratio. The greater the phase modulation by the phase plate (with a cubic profile in this example), the greater the extension of the depth of field. The greater the phase modulation for extending the depth of field, the larger the PSF, and the greater the drop in the MTF, as seen in Figure 2b, which show the MTF of the imaging system. The use of the phase function to extend the depth of field causes portions of the MTF to sag as compared with the MTF of the in-focus conventional system. This reduces the signal-to-noise ratio. If there is a greater phase alteration, the MTF sags more.



Figure 7 Image of a tilted bar pattern with an extended depth of field imaging system. (a) Image with a conventional imaging system. (b) Final image from the imaging system with Wavefront Coding. (c) Traces through the images to give quantitative comparisons of the image quality.

Focus budget and focus-related aberrations. Another set of trade offs can be seen by considering the imaging systems from the detector plane. Here, we see an increase in the depth of focus of the system. All of this increase in the focal depth can be used to increase the depth of field if the optics of the system are of high quality. Otherwise, the increase in the depth of focus can be used to compensate for focus-related aberrations. For example, chromatic aberration occurs when different colors focus to different planes. Figure 8 shows that if the depth of focus is extended, then there is a region where red, blue, and green, for example, are in focus. Figure 9 shows the red, blue, and green images of a US Air Force test pattern, as formed with a two-element imaging system with severe chromatic aberration, and with the same system when a Wavefront Coding element is used to extend the depth of focus.

Compensation can also be seen for the case of curvature of field, where the image of a plane object falls onto a curved surface. If an extension of the depth of focus causes the focal region to resemble a curved bar instead of a curved line, then it is possible to place a flat detector array in the curved region, and therefore obtain a good image after signal processing. Similar arguments can be made for other focus-related aberrations. This leads to the concept of a focus budget, where a portion of the increased depth of focus can be allocated to extend the depth of field by some amount, and other portions of the depth of focus allocated to provide invariance to focus-related aberrations.



Figure 8 Ray traces showing different focal planes for red, blue, and green, and the effect of extending the depth of focus for each color.


(a)
(b)
2
3
2
3
4
5
6
(c)
RGB
Red
Green
Blue
(d)
RGB
Red
Green
Blue

Figure 9 Color images of a US Air Force test pattern. (a) Images from a two-element lens of the center portion of the test pattern. (b) Images from an extended-depth-of-focus imaging system of the center portion of the test pattern. (c) Images from a two-element lens of a small number ‘three’ on the test pattern. (d) Images from an extended-depth-of-focus imaging system of a small number ‘three’ on the test pattern. Some residual effects remain due to different magnifications at different wavelengths.


Input
Specialized optical surfaces Refractive, Reflective Diffractive, Volume
CodeV, Zemax
Optical system modeling and propagation
Image detection and sampling
Input
Detector layout and noise model
Optimization loop
Signal processing
Input
Electronic processing architecture and models
Output
Optical prescription mechanical and signal processing parameters
Modify system variables through optimization
From optical, digital, image, and task-based figures of merit
Input
System specifications and goals

Figure 10 Schematic of a tool for designing imaging systems with Wavefront Coding. A ray trace determines the distribution in the exit aperture, and software determines the effect of the detector array and the signal processing. Then the ray trace and signal processing can be modified to optimize the entire system.

New design tools for imaging systems with wavefront coding

The Woodward function is a very good tool for analyzing imaging systems with a coded wavefront and is a good guide for someone who is expert in designing such systems. However, another approach is better for those designers who are more familiar with conventional lens design tools. If one combines a conventional ray-tracing tool with custom software, it is possible to jointly design the optical and the signal processing portions of the system. A schematic of such a system is shown in Figure 10. The ray-tracing tool is used to trace the rays and determine the distribution in the exit aperture. Various software tools then are used to take into account the effect of pixel size and spacing, and the signal processing. The criteria for optimizing the design can include the size of the digital filter, acceptable noise gain, and other parameters related to signal processing as well as the parameters of the optical elements.

Example applications of hybrid imaging systems with an extended depth of field or focus

Barcode and label readers. The images of Figure 7 show that image-based bar code reading is a good application for imaging systems that are based on Wavefront Coding. A bar code or label reader need not be positioned nearly as accurately as without the



Figure 11 Images of a 2D bar code as the object position is varied for (a) conventional images and (b) Wavefront Coded images after signal processing for the same object positions as in (a).



Figure 12 Images of an iris taken with infrared illumination. The top row shows images with a traditional CMOS camera. The lower row is taken with a camera using wavefront coding to extend the depth of field. The misfocus distance in the right and left columns is the same.



Figure 13 Images from a digital camera (a) Conventional camera with the lens wide open and focused on the white crayon. (b) Conventional camera with the lens stopped down to increase the depth of field, with the resulting increase in noise due to a lower light level. (c) Intermediate image of a camera that was modified with Wavefront Coding to have an extended depth of field. (d) Final image with the modified camera.

extended depth of field. Images of 2D bar codes imaged with and without Wavefront Coding are shown in Figure 11. Images in Figure 11a show the image of a 2D bar code formed by a conventional imaging system as the position of the object is varied. As with most imaging systems with fast optics and moderate magnification, the depth of field of the system is smaller than the application would prefer. Images in Figure 11b show the Wavefront Coded images of a 2D bar code after signal processing for the same object positions as (Figure 11a). These images are sharp and clear over a very large change in the distance to the bar code.

Biometric imaging systems. Biometric imaging applications, such as fingerprint or iris recognition, provide the means to eliminate passwords, secure E-commerce, and securely identify humans or animals. In traditional imaging technology, quite often the trade-off between light throughput and depth of field makes conventional biometric systems difficult to use or not sufficiently reliable. By using Wavefront Coding, the depth of information gathered can greatly increasing the ease of use and possibly reducing the cost of the systems.

Figures 12a,b, and c shows example images of an iris taken with near IR illumination and a traditional CMOS imaging system at three different planes of focus. At best focus (Figure 12b) the detail of the iris is sharp and clear. This iris detail is used by iris recognition algorithms to accept or reject the person.



Figure 14 A schematic of a fast single-lens imaging system that has good performance over a wide field of view and the full visible range.

With slight movement towards (Figure 12a) or away (Figure 12c) from the imaging system the detail of the iris is lost. Figures 12d,e, and f show example iris images taken with the same near-IR illumination and a CMOS Wavefront Coded imaging system. At best focus (Figure 12e), the iris detail is as high as that from the traditional system. Movement towards (Figure 12d) or away (Figure 12f) from the imaging system results in images with essentially a constant level of iris detail. The size of the iris changes through magnification change. Increasing the range at which clear images can be made extends the useful image capture volume, enabling a more flexible system that is easier to use.

Color images with digital cameras. A conventional digital camera has a small depth of field as shown in Figure 13a, where the camera was focused on the white crayon. In a conventional imaging system, the only way to increase the depth of field is to stop down the lens. As seen in Figure 13b, this reduces the light that is available, and results in a very noisy image. The intermediate image of an imaging system that has an extended depth of field is shown in Figure 13c, where it is seen that the result of convolving the object distribution with the modified PSF is an intermediate image that appears to have the same blur over the entire image. After signal processing of the intermediate image to obtain the final image, a clear image is seen with good signal-to-noise ratio.

Inexpensive imaging systems with high-quality imaging characteristics. By exploiting the extension of the depth of focus that is made possible with Wavefront Coding techniques, one can design imaging systems that have fewer optical elements than traditional designs that do not use Wavefront Coding. In high-volume applications, reduction in the number of optical elements can lead to greatly reduced costs. Figure 14 shows a schematic of a fast, single-lens Wavefront Coded imaging system that is very compact and has the performance of a longer lens that traditionally requires two or more optical elements. In this example, the entire focus budget was used to compensate for focus-related aberrations, and the shape of the lens was used to compensate for distortion and coma. Even zoom systems can be greatly simplified with the new design techniques. Figure 15 shows a fast two-element Wavefront Coded zoom lens that images over a wide field with performance that is traditionally obtained only with three or more optical elements. Both of these imaging systems use non-rotationally symmetric forms of phase functions and are different from the ones of eqns [5] and [6].



Figure 15 A schematic of a fast two-element zoom system with good performance over a 2.5 × zoom and a wide viewing angle.

Large depth of focus microscopes. A microscope can be modified to employ Wavefront Coding by either modifying the surface of one of the lenses in the objective, or by inserting a phase plate into the system at some appropriate position. One easy means of doing the modification is to place a Wavefront Coding phase plate in the slider position of a microscope, as shown in Figure 16. In this case, the optics is of high quality, and the entire focus budget was allocated to increasing the depth of field. A modified Zeiss microscope was used to obtain the images shown in Figure 17. An image of a diatom in Figure 17 shows the comparison with a conventional microscope in (a) and as with a Wavefront Coded microscope in (b). Notice that the greater depth of field gives more of an appearance of depth in the image.



Figure 16 Schematic of a modified Zeiss microscope to employ Wavefront Coding to extend the depth of field.



Figure 17 A 100 × image of diatoms made with (a) conventional and (b) modified Zeiss microscope to give an extended depth of field.



Figure 18 Imaging 0.5 micron diameter fluorescent beads at different sample distances. The images were taken with a 63×, NA = 1.4 imaging system in one micron steps. (a) Three image planes taken using a traditional system. They show that individual beads are sharp only in a single plane. The images in (b), which were taken with a Wavefront Coding system at the same image planes, show all beads are imaged clearly at each plane.

Other modes of microscopy are also possible. In fluorescence microscopy, ultraviolet light illuminates objects that have fluorescing compounds in them. The images are formed using the fluorescence that is excited by the ultraviolet illumination. Figure 18 shows images of fluorescing beads having a 0.5 micron diameter. The beads are at various depths within the sample. The traditional system, operating at 63 × with an immersion objective having a NA of 1.4, has a depth of field that is too small to image all of them. The images in Figure 18a were taken with the same microscope but with a wavefront coding phase element placed in the slider and signal processing of the captured images. All beads are clearly seen at all three of the focus positions.

Potential Future Applications

Wavefront Coding should be useful in many imaging system where signal processing is to be done anyway; in that case, optimizing the optics and the signal processing to the purpose of the imaging system. Examples where an extended depth of field may be desired are endoscopes, video cameras, and lithography. In designing an imaging system to take advantage of a large depth of focus to produce inexpensive digital cameras, high-quality images can be formed with fewer optical elements and much lighter cameras. In lithography, a larger process window is possible.

Because an increase in the depth of focus can permit wide spectral imaging, wide band infrared images can be formed. In systems that are used to provide images for machine interpretation, it is possible to design the optics and signal processing so that the desired process can be optimized globally, with the optics and the signal processing. For example, if the object is to classify cells as cancerous or noncancerous, it may be that the optics should be modified so that the information of primary importance is acquired and transmitted to the detector array. This modification would be done in conjunction with the optimization of the signal processing.

Conclusion

The mathematics and concepts that underlie a new approach to lens design were summarized. The technique has thus far been useful in enhancing the performance of some imaging systems such as microscopes, and in making simpler systems for inexpensive cameras. This new approach requires that some signal processing be done, but in digital cameras, some signal processing is being done already.

List of Units and Nomenclature

Modulation transfer function	The magnitude of the optical transfer function of an imaging system.
Optical transfer function	The response of an imaging system as a function of the spatial frequency of a sinusoidal object distribution.
Spatial frequency	A measure of spatial variation in the form of sinusoids in cycles per millimeter.

See also

Imaging: Wavefront Sensors and Control (Imaging Through Turbulence). **Microscopy:** Imaging Multiple Photon Fluorescence Microscopy; Overview.

Further Reading

Barrett HH and Swindell W (1981) *Radiological Imaging: The Theory of Image Formation, Detection, and Processing*. New York: Academic Press.

Brenner K, Lohmann A and Ojeda-Castañeda J (1983) The ambiguity function as a polar display of the OTF. *Optics Communications* 44: 323–326.

Cathey WT and Dowski ER (2002) New paradigm for imaging systems. *Applied Optics* 41: 6080–6092.

Cathey WT, Frieden BR, Rhodes WT and Rushforth CK (1984) Image gathering and processing for enhanced resolution. *Journal of the Optical Society of America A* 1: 241–249.

Cushman SC (2001) *Finite-Dimensional Matrix Treatment of Partially Coherent Optical Systems*. University of Colorado thesis, Boulder, Colorado.

Dowski ER and Cathey WT (1995) Extended depth of field through wavefront coding. *Applied Optics* 34: 1859–1866.

FitzGerrell AR (1993) *Applications of the Ambiguity Function to Optics*. Thesis, University of Colorado, Boulder, Colorado.

Häusler G (1972) A method to increase the depth of focus by two step image processing. *Optics Communications* 6: 38–42.

Ojeda-Castañeda J, Tepichin E and Diaz A (1989) Arbitrary high focal depth with quasioptimum real and positive transmittance apodizer. *Applied Optics* 28: 2666–2670.

Papoulis A (1974) Ambiguity function in Fourier optics. *Journal of the Optical Society of America* 64: 779–788.

Rihaczek AW (1969) *Principles of High Resolution Radar.* New York: McGraw-Hill.

Van der Gracht J, Dowski ER, Taylor MG and Deaver DM (1996) Broadband behavior of an optical-digital focus-invariant system. *Optics Letters* 21: 919–921.

Wach HB, Dowski ER and Cathey WT (1998) Control of chromatic focal shift through wave-front coding. *Applied Optics* 37: 5359–5367.

Woodward PM (1953) *Probability and Information Theory with Applications to Radar.* New York: Pergamon Press.

PHOTON PICTURE OF LIGHT

S J Bentley, Adelphi University, Garden City, NY, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The photon nature of light is the central topic in the field of quantum optics, which has developed into a leading area of research. The possible technological impacts of this field to many areas, such as imaging, computing, and lithography, have greatly expanded interest into the nature of the photon. A photon description of light goes well beyond the particle nature of light, to include any optical phenomena that cannot be adequately described by classical physical optics. This article will introduce the nature of the photon through a discussion of many such phenomena, covering topics from the beginning of quantum mechanics, including black-body radiation and Compton scattering, to areas of modern interest, such as squeezed light and entangled photons.

The Origins of Quantum Optics

One of the earliest theories in the development of quantum physics was the description of black-body radiation by Max Planck (1858–1947). Using the model of a radiating body as a collection of oscillators, he postulated that the amount of energy emitted or absorbed was proportional to its frequency, ν, and that these oscillators could only have energies corresponding to integer multiples of such a packet of energy, where one unit of energy was given by

$$E = h\nu \qquad [1]$$

where $h = 6.626 \times 10^{-34}$ Js is the universal constant, now known as Planck's constant. He then assumed a Maxwell–Boltzmann distribution to describe the probability of such oscillator states being occupied:

$$P(n) = P_0 e^{-nh\nu/kT} \qquad [2]$$

where $k = 1.381 \times 10^{-23}\,\mathrm{JK}^{-1}$ is Boltzmann's constant and T is the temperature of the blackbody. The energy density in the radiation field, at a given frequency, is given by the oscillator density (at that frequency) times the average energy of the oscillators. Previous models had not only failed to quantize the oscillator energies, but in doing so also assumed equal occupation probabilities that led to a prediction of infinite energy densities at short wavelengths, the so-called ultraviolet catastrophe. The oscillator density is given by

$$n(\nu) = 8\pi\nu^2/c^3 \qquad [3]$$

where $c = 3 \times 10^8\ \mathrm{m\ s}^{-1}$ is the speed of light. This value can be found by a mode density calculation within a box, as is often done in an introductory electromagnetics text. The average energy of the oscillators is found by calculating the sum of the occupation probability times the state energy and dividing by the sum of the occupation probabilities:

$$E_{\mathrm{av}} = \sum_{n=0}^{\infty}[P(n)h\nu n] \Big/ \sum_{n=0}^{\infty} P(n) \qquad [4]$$

Evaluating the above expression for E_{av} and multiplying by $n(\nu)$, one finds the Planck radiation law:

$$I(\nu) = \frac{8h\pi\nu^3}{c^3(e^{h\nu/kT} - 1)} \qquad [5]$$

The black-body curve described by Planck's law is shown in Figure 1. By introducing quantization to solve a problem that classical physics had failed to explain, Planck paved the way for quantum physics.

Albert Einstein (1879–1955) made use of Planck's quantization for two important results that will be described here. The first is the photoelectric effect, a process by which electrons are released from a metal surface when exposed to light. The process has several traits that could not be explained by



Figure 1 The spectral density emitted by a blackbody at a given temperature as given by Planck's law.

classical physics. A given metal will only release electrons if the incident light is above a certain frequency, regardless of the intensity. However, once sufficient frequency components are present, electrons are immediately released, with their number dependent on the intensity of the light and independent of its frequency. Contrarily, the maximum potential energy of the released electrons depends only on the maximum frequency of light present, independent of intensity. Einstein was able to satisfy all of these conditions by saying that the light energy comes in quantized amounts as described by Planck, and that the electrons in the metal require a minimum energy, or work function *W*, to be ejected. Then for each quantum of light, which we now call a photon, with energy greater than *W* that strikes an electron, the electron will be released with kinetic energy given by

$$K = h\nu - W \qquad [6]$$

It is historically important to note that, although Planck introduced the idea of a quantized release of radiation from oscillators, he still believed the light field itself to be continuous and classical. Planck's approach of quantizing energy levels of matter while treating light classically has since become known as the semiclassical method, and is adequate for solving many problems. Thus, it was also in quantizing light itself that Einstein took the next step, and thus can be viewed in many respects as the father of the modern photon, although the term photon was not used until two decades later.

The second area in which Einstein used the idea of energy quantization is in predicting radiative transition probabilities. A radiative transition is a process by which a photon is either absorbed or emitted to satisfy conservation of energy when an atom moves to a higher or lower energy state. Einstein assumed three such processes existed, as shown in Figure 2: absorption of a photon raising the atom to a higher energy level; spontaneous emission of a photon, where the atom emits a photon in going to a lower energy level; and stimulated emission, a process in which a photon interacts with the atom and causes it to emit a second photon (in phase with the first) and thereby go to a lower energy level. For each of these processes he defined a corresponding coefficient, now known as the Einstein *A* and *B* coefficients. They are labeled B_{12} for absorption, A_{21} for spontaneous emission, and B_{21} for stimulated emission. Note that there is no A_{12} as absorption by its very nature is a stimulated process. Einstein further stated that the rate of spontaneous emission was only dependent on his material dependent coefficient and the number of atoms in the upper energy state, with the rate given by



Figure 2 Energy level diagrams representing the processes of absorption, spontaneous emission, and stimulated emission.

$$R_{\mathrm{sp}} = A_{21}N_2$$

However, he said that the rates of the stimulated processes were also dependent upon the strength of the optical field seen by the atoms, $I(\nu)$, and were given by

$$R_{\mathrm{ab}} = I(\nu)B_{12}N_1 \qquad [7]$$

for absorption and

$$R_{\mathrm{st}} = I(\nu)B_{21}N_2 \qquad [8]$$

for stimulated emission. The full absorption rate is given by R_{ab} as defined above, whereas the full emission rate is the sum of the spontaneous and stimulated rates, given by

$$R_{\mathrm{em}} = [A_{21} + B_{21}I(\nu)]N_2 \qquad [9]$$

Einstein was primarily interested in a system in equilibrium, for which $R_{\mathrm{ab}} = R_{\mathrm{em}}$. If one then looks at the limit where the optical field is very large such that spontaneous emission is negligibly small and the population is equally divided between the upper and lower state, the relationship $B_{12} = B_{21}$ is found. Applying the same Maxwell–Boltzmann occupation statistics that Planck used to find his black-body expression, one can find that in thermal equilibrium the ratio of probability of finding an atom in state 1 to finding an atom in state 2 is

$$N_1/N_2 = e^{(E_2-E_1)/kT} = e^{h\nu/kT} \qquad [10]$$

Note that for a two-level system in thermal equilibrium, the population in the upper level can at most equal, never exceed, the population in the lower level, regardless of the strength of the applied field. This is important in showing that the *B* coefficients are equal, and will also be a crucial point when discussing the theory of the laser later in this article.

Appropriately combining the above expressions leads to

$$I(\nu) = A_{21}/[B_{21}(e^{h\nu/kT} - 1)] \qquad [11]$$

Equating this with Planck's radiation law yields the relation:

$$A_{21}/B_{21} = 8\pi h\nu^3/c^3 \qquad [12]$$

Thus, to fully specify the transition probabilities for a given system, one needs only to find A or B. It is rather straightforward using only atomic quantization to calculate B (such a derivation can be found in many introductory quantum mechanics textbooks). Direct calculation of A is more involved, requiring quantization of both the optical field as well as the atomic system.

Arthur Compton (1892–1962) used the idea of quantized radiation to explain the presence of longer wavelength components present when X-rays are scattered from matter, an effect which now bears his name. The amount of scattering is independent of the scattering material and the wavelength of the source, depending only on the angle of scattering, θ. If the scattering is treated as a collision between a particle-like photon and a massive particle (taken to be initially at rest) as shown in Figure 3, the result can then be found simply by applying conservation of energy and momentum, where the photon energy is as given above and the photon momentum is given by

$$p = E/c = h/\lambda \qquad [13]$$

Recalling that the momentum is a vector quantity, the conservation laws provide a set of three coupled equations. Solving them directly one finds that

$$\Delta\lambda = (h/c)(1 - \cos\theta)(2K)/[p^2 - (K/c)^2] \qquad [14]$$

where K and p correspond to the final kinetic energy and momentum of the massive particle. It is important to allow for the possibility of very high velocities for the massive particle, thus implying that relativistic expressions for K and p are needed. In terms of the kinetic energy, the relativistic expression for momentum is

$$p = \sqrt{2Km + (K/c)^2} \qquad [15]$$

where m is the mass of the scattering particle. Using this relation, the above expression can be simplified, giving the wavelength shift to be

$$\Delta\lambda = (1 - \cos\theta)h/mc \qquad [16]$$

The scaling factor is known as the Compton wavelength:

$$\lambda_c = h/mc \qquad [17]$$

For the case of an electron, the Compton wavelength has the value 0.02426 angstroms. For a massive particle, the Compton wavelength is often used when wanting to discuss and analyze wavelike properties. As a final note on this process, if the calculation would have been done nonrelativistically, there would have been an extra factor of $[1 - 0.25(v/c)^2]^{-1}$, where v is the velocity of the particle. The appearance of the factor (v/c) in any result implies the need for a relativistic treatment, though often (as in this case) taking the limit of $v/c = 0$ yields the proper result.

Another area in which the photon nature of light is revealed is a form of inelastic scattering of light now known as the spontaneous Raman effect. Discovered by CV Raman (1888–1970), this is a process in which a material illuminated by a light source scatters light into frequency components not found in the source. The frequency shift is due to the energy difference, ΔE, between two energy states in the material. There are two possible cases, each of which is represented in Figure 4. In the first, known as Stokes scattering, an atom in the lower state absorbs a source photon, raising it to the upper state via a virtual level, during which it emits a photon at the Stokes frequency, ν_s, as represented by the relation

$$h\nu_i = h\nu_s + \Delta E \qquad [18]$$

where ν_i is the frequency of the incident photon from the source. The second case, anti-Stokes scattering, has an atom in the upper state absorb the source photon and simultaneously fall to the lower state, again through the virtual level during which it emits a photon at the higher anti-Stokes frequency, ν_a,



Figure 3 Schematic representation of Compton scattering.


$h\nu_i$
$h\nu_s$
ΔE
Spontaneous Stokes–Raman scattering
$h\nu_i$
$h\nu_a$
ΔE
Spontaneous anti-Stokes–Raman scattering

Figure 4 Energy level diagrams for Stokes and anti-Stokes Raman scattering.

given by

$$h\nu_i = h\nu_a - \Delta E \qquad [19]$$

Since the anti-Stokes scattering requires the atom to be initially in the upper state, the probability of such scattering is generally much less than that for Stokes scattering. This can be quantified by the same occupation statistics used above, giving the ratio of probabilities as

$$P_{\mathrm{as}}/P_s = e^{-h\Delta E/kT} \qquad [20]$$

It is important to note that the energy difference can either be based on the electronic structure of an atomic system as has been discussed thus far, or other energies such as the vibrational energies in a molecular system. The ability to probe a variety of energy structures without having to tune the source to a particular wavelength has led to wide use of Raman scattering for spectroscopy. A related effect, known as stimulated Raman scattering, will be discussed later.

The Photon in Modern Physics

As an indication of the widespread importance of the results discussed thus far, they led to four Nobel prizes in physics: Planck in 1918; Einstein in 1921; Compton in 1927; and Raman in 1930. Our initial understanding of the photon comes from these results, but it was with the development of modern quantum mechanics by Erwin Schrödinger (1887–1961), Werner Heisenberg (1901–1976), and Paul Dirac (1902–1984); quantum electodynamics by Richard Feynman (1918–1988) and others; and the invention of the laser by Charles Townes (1915–) and others, that the field of quantum optics and our modern view of the photon began to fully take shape. In this section, the basics of modern quantum optics will first be introduced. A brief discussion of the theory of the laser as related to photon transitions will then be given, followed finally by examples of important areas of experimental quantum optics that have been made accessible by the laser.

It is now common to treat the photon with a very similar formalism as that originally created for massive particles in the development of quantum mechanics. That is, one describes the photon by a wave function, $|\Psi\rangle$, which contains all the information about the photon and must satisfy the Schrödinger equation

$$i\hbar\frac{\partial}{\partial t}|\Psi\rangle = H|\Psi\rangle \qquad [21]$$

where $\hbar = h/2\pi = 1.054\times10^{-34}$ Js and H is the Hamiltonian for the photon. Just as in classical electromagnetics, the Hamiltonian is related to an electric and magnetic field. Clearly, for this treatment to be in agreement with the well-established classical electromagnetic theory, these fields must satisfy Maxwell's equations. There are several possible representations of the Hamiltonian, but for the purposes of this discussion a convenient choice is

$$H = h\nu(\hat{n} + 0.5) \qquad [22]$$

where $\hat{n}$ is called the number operator as it returns the average number of photons in the state, $\langle\hat{n}\rangle$, represented by the operation

$$\langle\hat{n}\rangle \equiv \langle\Psi|\hat{n}|\Psi\rangle \qquad [23]$$

Explanations of the notation used can be found in any elementary quantum mechanics text. Note that in defining the Hamiltonian, a single frequency ν was used. This implies a single mode field. For a more general case, one would simply sum over the modes corresponding to various frequencies.

In addition to obeying the Schrödinger equation, the photon is also restricted by the Heisenberg uncertainties as for massive matter, given in a general form as

$$\Delta q\Delta p \geq \hbar \qquad [24]$$

where q and p are any set of canonically conjugate variables, such as position and momentum or energy and time. Note that, depending on the exact definitions used for q and p, there can be extra factors such as 0.5, and sometimes normalized variables are used such that the inequality is with respect to 1. However, it is interesting to note that, unlike for massive particles that were considered well localized in classical theory, the idea of uncertainty for light had been accepted in some form long before the development of quantum mechanics. Neglecting the scaling factor $\hbar$, which is purely quantum in origin, an uncertainty principle can be derived for any wavelike phenomena simply using the relationship between Fourier transform pairs.

Using the basic ideas of a photon state and the uncertainty principle, some important properties of light will now be explored. There are several possible forms the wave function can take. It is often convenient to write the wave function in terms of states containing a certain number of photons. Such states are known as Fock or number states and are represented as $|n\rangle$, with n being the number of photons in the state and are said to be eigenstates of the number operator. The energy of a Fock state is given by

$$E_n = h\nu(n + 0.5) \qquad [25]$$

Notice that this predicts a background, or vacuum, energy for the electromagnetic field, even when the average number of photons in the field is zero. This vacuum energy is given by $0.5\ h\nu$. Correspondingly, due to the uncertainty principle, there must be some uncertainty in this energy as well as with any energy. The fluctuations in the vacuum energy are known as vacuum fluctuations. Many processes, such as spontaneous emission that cannot be adequately described by a simple semiclassical approach, where matter is treated quantum mechanically and light is treated classically, can be treated by the addition of vacuum fluctuations, without requiring a full quantum mechanical treatment of the electromagnetic field. Such an approach is used in many texts, but there are several important physical phenomena that do require the fully quantized approach discussed here.

The state most resembling a classical field is known as the coherent state, represented here as a sum of Fock states:

$$|\Psi\rangle = |\alpha\rangle = e^{-|\alpha|^2/2} \sum_{n=0}^{\infty} \frac{\alpha^n}{\sqrt{n!}} |n\rangle \qquad [26]$$

where α is a parameter describing the field, with the average number of photons in the field given by

$$\langle \hat{n} \rangle = |\alpha|^2 \qquad [27]$$

One key property of coherent states is that they exhibit minimal uncertainty. That is, the uncertainty relations become equalities. Also, the uncertainty is equally divided between quadrature components.

Before applying the above principles to explore some of the dramatic results of quantum optics, a brief discussion of the laser will be given due to its importance in the field. The theory of operation of the laser is based directly on Einstein's transition probabilities. For the transition of interest, one wants to generate a large number of coherent photons (that is, photons in phase with one another). Recall that in the process of stimulated emission, one photon leads to two coherent photons, whereas spontaneous emission leads to photons which are not phase referenced to anything else in the system. Also, if a significant number of the photons are to escape the region where they are generated, it is important to minimize the absorption. Thus, a laser requires that the stimulated emission rate exceed both the spontaneous emission rate and the absorption rate. The first condition places a lower limit on the optical field density present at the lasing frequency. This density can be reasonably large, but presents no fundamental difficulties. In practice, mirrors are placed around the emission region to confine the photons and counteract losses, thereby building up the energy density until the above condition is satisfied. The second condition, however, can be written as

$$N_2 > N_1 \qquad [28]$$

and is the more restrictive requirement. Such a condition is referred to as inversion and, as was previously mentioned, cannot be sustained in a two-level system once equilibrium is reached. Therefore, to be able to maintain lasing, additional levels are needed. Two typical laser energy diagrams are shown in Figure 5. In such multilevel systems, it is possible to create an inversion in the levels of interest and thus allow lasing. Further details on lasers (both in theory and practice) are widely available, though it should be noted that the output of a laser is a good approximation of a coherent state described above.

The invention of the laser revolutionized optics, as well as the whole of modern physics, by making readily available electromagnetic fields of a vastly different nature than that from any previous source of light. This quickly led to the birth of a new field known as nonlinear optics. Nonlinear optics describes interactions between light and matter which have properties dependent on the field strength. Although some nonlinear processes can be described adequately without the use of a photon picture, most nonlinear process can be best described as some combination of annihilation (absorption) and creation (emission) of photons. Two such



Figure 5 Energy level diagrams for three-level and four-level lasers.

processes, that are of great interest in quantum optics, are stimulated scattering and parametric down conversion.

Earlier, the process of spontaneous Raman scattering was discussed. For such a process, it is assumed that the incident field driving the process is relatively weak such that the scattering process generates very low photon densities in the various modes of the electromagnetic field. However, just as there are both stimulated and spontaneous emission processes in the radiative transitions discussed previously, in the presence of strong fields there can also be stimulated scattering. The total Raman scattering rate can be expressed as

$$R = \eta I_i(I_\mathrm{R} + 1) \qquad [29]$$

where η is a scaling factor, including the gain of the process for a given material, I_i is the strength of the incident optical field (generally a laser field to be sufficiently strong to cause stimulated scattering), and I_R is the Raman field strength. Note that for I_R, the rate is just linear with the applied field, representing the spontaneous process. However, with a strong pump, the generated field will quickly become large enough such that the stimulated process will dominate. The spontaneous scattering is not directional dependent, but since the stimulated process grows along the length of the scattering material in the path of the incident beam, it will tend to be generated along the path of the incident laser. Due to linear and nonlinear dispersion effects, however, the light will form in a narrow cone about the pumping laser rather than exactly collinear. Unlike the spontaneous scattering, a significant percentage of the incident photons can be converted to the Raman frequencies, making stimulated Raman scattering an extremely powerful spectroscopic tool.

Possibly the most important nonlinear optical process for quantum optics is parametric down conversion. This process is interesting both in the nature of the process itself, as well in the properties of the generated light. In parametric down conversion, shown schematically in Figure 6, one photon (known as a pump photon) of frequency ν_p is annihilated and two new photons (generally referred to as signal and idler) are created with frequencies ν_s and ν_i respectively, given by the conservation of energy relationship:



Figure 6 Schematic representation of parametric down conversion.

$$h\nu_p = h\nu_s + h\nu_i \qquad [30]$$

In the case where $\nu_s = \nu_i$, the process is referred to as degenerate. Down conversion can either be spontaneous, in which only pump photons are externally applied, or stimulated, in which both pump photons and signal photons are applied. In the stimulated case, the signal is amplified and idler photons are generated as a byproduct. Parametric down conversion is one of the leading sources of nonclassical states of light. The term nonclassical is used rather than quantum, because all states of light can be accurately described by a quantum picture, but while most can also be described very well with a classical picture the states referred to as nonclassical cannot. Two of the most common nonclassical states of light are entangled states and squeezed states.

Entangled states are multiphoton states in which the state cannot be written as a product of the states of the individual photons. For simplicity, only two-photon entangled states (commonly referred to as EPR states for Einstein, Podolsky, and Rosen) will be discussed. More extensive and general material, including discussions of higher-order entanglement,



Figure 7 Uncertainty diagrams for squeezed and unsqueezed vacuum and coherent states.

such as the three-photon entangled states (commonly referred to as GHZ states for Greenberger, Horne, and Zeilinger), can be found in a variety of textbooks on modern quantum optics. One of the simplest ways to generate a two-photon entangled state is by the process of spontaneous parametric down conversion described above. If the product of the pumping intensity, generation length, and generation gain is of an appropriate level, individual pairs of photons are emitted. The states of these photon pairs are entangled, with the position, momentum, wavelength, polarization, and all other properties of the photons completely correlated and inseparable. Such states have been a powerful tool for the experimental verification of many of the predictions of quantum mechanics and quantum optics. Entangled states can also act as a source for many of the newer technologies in quantum optics, including cryptography and teleportation.

Another important form of nonclassical light is known as squeezed light. The principle behind squeezed light is that, unlike for coherent states where the uncertainty is equally distributed, the uncertainty in one quadrature can be reduced at the expense of increased uncertainty in the other quadrature. This is shown schematically in Figure 7. As opposed to entangled states which tend to be very weak, containing only a few photons, squeezed states of light can be quite intense. This makes squeezed light more desirable for many applications.

In conclusion, it should be noted that while the photon description of light can explain a wide variety of physical processes and is now leading to many exciting technological developments, much is still unknown about the photon at the fundamental level. Any accurate description of the photon must be in agreement with experimental evidence, including that discussed in this article, but one should be aware that the accepted picture of the photon nature of light is still constantly evolving and growing.

See also

Nonclassical Light. **Nonlinear Optics, Applications:** Raman Lasers. **Optical Amplifiers:** Raman, Brillouin and Parametric Amplifiers. **Quantum Optics:** Entanglement and Quantum Information. **Scattering:** Raman Scattering. **Spectroscopy:** Raman Spectroscopy.

Further Reading

Boyd RW (2002) *Nonlinear Optics*, 2nd edn. San Diego, CA: Academic Press.

Cohen-Tannoudji C, Diu B and Laloë F (1977) *Quantum Mechanics*. New York: Wiley-Interscience Publications.

Hecht E (2001) *Optics*, 4th edn. Reading, MA: Addison-Wesley Publishing.

Heisenberg W (1949) *The Physical Principles of the Quantum Theory*. New York: Dover Publications.

Lipson SG, Lipson H and Tannhauser DS (1995) *Optical Physics*, 3rd edn. Cambridge, UK: Cambridge University Press.

Loudon R (2000) *The Quantum Theory of Light*, 3rd edn. Oxford, UK: Oxford University Press.

Mandel L and Wolf E (1995) *Optical Coherence and Quantum Optics*. Cambridge, UK: Cambridge University Press.

Milonni PW and Eberly JH (1988) *Lasers*. New York: Wiley-Interscience Publications.

Roychoudhuri C and Roy R (eds) (2003) *OPN Trends – The Nature of Light: What is a Photon?* Washington, DC: Optical Society of America.

Schwinger J (ed.) (1958) *Selected Papers on Quantum Electrodynamics*. New York: Dover Publications.

Scully MO and Zubairy MS (1997) *Quantum Optics*. Cambridge, UK: Cambridge University Press.

Yariv A (1989) *Quantum Electronics*, 3rd edn. New York: John Wiley & Sons.

PHOTONIC CRYSTALS

Contents

Atomic Physics
Electromagnetic Theory
Microwave Photonic Crystals
Nonlinear Optics in Photonic Crystal Fibers
Photonic Crystal Lasers, Cavities and Waveguides
Self-Assembled and Functionalized Photonic Crystals

Atomic Physics

G Kurizki and A G Kofman, Weizmann Institute of Science, Rehovot, Israel

D Petrosyan, Institute of Electronic Structure and Laser, Heraklion, Greece

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The fabrication and study of dielectric structures whose refractive index is periodically modulated on a micron or submicron scale, known as photonic crystals (PCs), are attracting considerable interest at present. One-, two-, or three-dimensional (1D-, 2D-, or 3D-) periodic PCs exhibit photonic band gaps (PBGs), analogously to electronic band gaps in ordinary crystals, and can incorporate defects, designed to form localized narrow-linewidth (high-*Q*) modes at PBG frequencies. The advent of such structures opens up new perspectives in atomic physics and quantum optics, since they are expected to allow an unprecedented control over the spectral density of modes (DOM) and the spatial modulation of narrow-linewidth (high-*Q*) modes, in the microwave, infrared, and optical domains. An interesting situation arises when foreign atoms or ions – dopants – with transition frequencies within the PBG, are implanted in the PC. Then light near one of these frequencies resonantly interacts with the dopants and is concurrently affected by the PBG dispersion. Consequently, highly nonlinear processes with a rich variety of unusual PC-related features are anticipated. Such nonlinear optical processes, involving near-resonant transitions in PCs, undergo basic modifications as compared to the corresponding processes in free space, which are attributed to the strong suppression of the DOM within PBGs, to sharp bandedges and to intra-gap narrow lines associated with high-*Q* defect modes.

Results are detailed below for spontaneous emission of radiation in PCs and for the resonant interaction of atoms with the field of a single high-*Q* defect mode. These results stem from the failure of perturbation theory and the onset of strong field-atom coupling near sharp bandedges or narrow defect-mode lines in 2D and 3D PCs. 3D-PBGs are needed, in order to extinguish spontaneous emission in all possible directions of propagation and dipole orientations. If only one polarized atomic transition is involved in the spontaneous emission, 2D-PCs suffice for its suppression. For controlling strictly unidirectional field propagation, it is sufficient to resort to PBGs in 1D-periodic structures (Bragg reflectors or dielectric multi-layer mirrors).

As a further example of field–atom interactions in doped PCs, we will show that two ultraweak electromagnetic fields (or photons), coupled to appropriate transitions of the dopants in a PC, can mutually induce large phase shifts or drastic changes in absorption. Appreciable photon–photon correlations can then be established, which can be utilized in both classical and quantum optical communications.

Radiative Decay and Photon–Atom Binding in a PC

The interaction of a two-level atom with an arbitrary field-mode continuum can be described by the following second-quantized Hamiltonian in the rotating-wave approximation (RWA)

$$\begin{aligned} H = {} & \hbar\omega_{\mathrm{a}}|e\rangle\langle e| + \hbar\sum_{\vec{k}} \omega_{\vec{k}} a_{\vec{k}}^{\dagger} a_{\vec{k}} \\ & + \hbar\sum_{\vec{k}} [\kappa(\omega_{\vec{k}}) a_{\vec{k}}^{\dagger} |g\rangle\langle e| + \text{hermitian constant}] \end{aligned} \qquad [1]$$

Here $|e\rangle$ and $|g\rangle$ are the excited and ground atomic states, respectively, ω_{a} is the atomic transition frequency, $a_{\vec{k}}^{\dagger}$ and $a_{\vec{k}}$ are the creation and annihilation operators of a field mode with wavevector $\vec{k}$, and frequency $\omega_{\vec{k}}$, and $\hbar\kappa(\omega_{\vec{k}})$ is the resonant coupling energy of this mode with the atomic dipole. The $\vec{k}$-summation can be replaced by an integral over the continuum DOM in the frequency domain, $\sum_{\vec{k}} \rightarrow \int_0^{\infty} \mathrm{d}\omega\rho(\omega)$, avoiding, for the sake of simplicity, the study of direction-(angle-)dependent DOM effects.

We consider a two-level atom that is excited at time $t = 0$ in an empty, periodic dielectric structure. The wavefunction of the combined system field + atom can be cast in the general form:

$$|\Psi(t)\rangle = \alpha(t)|e, \{0_{\omega}\}\rangle + \int \beta_{\omega}(t)|g, 1_{\omega}\rangle\rho(\omega)\mathrm{d}\omega \qquad [2]$$

where $\{0_{\omega}\}$ signifies the completeness of field modes in the vacuum state and $|1_{\omega}\rangle$ denotes single-photon occupation of the ω-mode. The corresponding Schrödinger equation can be solved with the initial condition $|\Psi(0)\rangle = |e, \{0_{\omega}\}\rangle$ by means of the continuum spectral response:

$$G(\omega) = |\kappa(\omega)|^2\rho(\omega) \qquad [3]$$

The analysis of eqn [2], with $G(\omega)$ appropriate for photonic bandstructures, is aimed at revealing the prominent features of the atomic excitation decay $\alpha(t)$ and the corresponding emission spectrum.

In what follows, we consider a photonic bandstructure with several PBGs, separated by allowed bands. Each PBG is labeled by index i and has lower and upper cutoff frequencies $\omega_{\mathrm{L}i}$ and $\omega_{\mathrm{U}i}$, respectively. Then $G(\omega) = 0$ for $\omega_{\mathrm{L}i} < \omega < \omega_{\mathrm{U}i}$. Naively, one might expect that an excited atom would either be stable against single-photon decay, if ω_{a} is within a PBG, or decay completely at $t \rightarrow \infty$, if ω_{a} is anywhere in an allowed band. However, both statements turn out to be inaccurate.

Incomplete decay of $\alpha(t \rightarrow \infty)$ occurs if there is a stable eigenvalue (energy level) $\hbar\omega_i$ of the total (field-atom) Hamiltonian eqn [1]. Such an energy level is possible only if $G(\omega_i) = 0$, i.e., for ω_i in a PBG. It must satisfy:

$$\omega_i = \omega_{\mathrm{a}} + \Delta(\omega_i) \qquad [4]$$

$$\Delta(\omega_i) = \int_0^{\omega_{\mathrm{L}i}} \frac{G(\omega')}{\omega_i - \omega'}\mathrm{d}\omega' + \int_{\omega_{\mathrm{L}i}}^{\infty} \frac{G(\omega')}{\omega_i - \omega'}\mathrm{d}\omega' \qquad [5]$$

Here the integrals are the frequency shifts of the atomic resonance $\hbar\omega_{\mathrm{a}}$ induced by the spectral parts of the reservoir situated, respectively, below and above the ith PBG (Figure 1). If eqn [4] holds, then the corresponding term in $\alpha(t)$ is proportional to $\exp(-i\omega_i t)$, and does not decay. Physically, such a stable level can be interpreted as representing the binding of the photon to the atom (photon-dressed atom), without the ability to leave the atomic vicinity, due to Bragg reflection in the PBG.

Assuming that ω_i occurs in the ith PBG, we observe that the first shift is positive whereas the second shift is negative, i.e., each part of the continuum repels the atomic level from its PBG edge. Equation [4] has a solution if ω_{a} falls between the minimum and maximum values assumed by its left-hand side in the ith PBG, i.e., if

$$\omega_{\mathrm{L}i} - \Delta(\omega_{\mathrm{L}i}) < \omega_{\mathrm{a}} < \omega_{\mathrm{U}i} - \Delta(\omega_{\mathrm{U}i}) \qquad [6]$$



Figure 1 Frequency shifts of the atomic resonance ω_{a} (dashed line) due to 'repulsion' (arrows) by asymmetric spectral parts of the continuum below and above the PBG: (a) Incomplete decay for ω_{a} in allowed band. The interaction with the continuum splits the state into a superposition of a stable part in the PBG (solid line) and a decaying part above ω_{a} (shaded peak). (b) Complete decay for same ω_{a}, due to larger shifts that split the state into decaying parts in two allowed bands.

Incomplete decay occurs if this condition holds at least for one PBG. There may be, at most, one stable state in a single PBG (Figure 1). However, a two-level atom in a periodic structure can have several stable dressed states simultaneously, when conditions hold for several PBGs. It is quite extraordinary that the conditions (eqn [6]) for incomplete decay can be fulfilled with ω_a, not only in a PBG, but even in an allowed band, e.g., when $\Delta(\omega_{Ui})$ is negative or when $\Delta(\omega_{Li})$ is positive (Figure 1a,b).

Equally counterintuitive is the converse possibility, of complete decay for ω_a within a PBG. When there is a single PBG and one of the inequalities in eqn [6] is violated, complete decay will occur for $\omega_{Li} < \omega_a < \omega_{Li} - \Delta(\omega_{Li})$, if $\Delta(\omega_{Li}) < 0$, or $\omega_{Ui} - \Delta(\omega_{Ui}) < \omega_a < \omega_{Ui}$, if $\Delta(\omega_{Ui}) > 0$.

The possibility that one or several discrete, stable, states exist yields the corresponding wavefunction in the form:

$$|\Psi(t)\rangle = \sum_i \sqrt{c_i}|\psi_i\rangle e^{-i\omega_i t} + |\Psi_c(t)\rangle \qquad [7]$$

Here the summation is over all discrete atomic photon-dressed states with energies $\hbar\omega_i$, $|\psi_i\rangle$ is a discrete-(dressed-)state eigenfunction of the Hamiltonian (eqn [1]) normalized to unity, and weighted by the amplitude $\sqrt{c_i} = [1 + \int_0^\infty d\omega G(\omega)/(\omega - \omega_i)^2]^{-1/2}$. The dressed state $|\psi_i\rangle$ consists of an excited-state component and a photon-bound ground-state component.

The population of the excited state for long times:

$$|\alpha(t)|^2 = \sum_{i,i'} c_i c_{i'} \cos(\omega_i - \omega_{i'})t \text{ for } t \to \infty \qquad [8]$$

is a nonzero time-constant if there is one discrete stable state, whereas in the case of several such states, it undergoes beats at the frequencies corresponding to their energy differences. The splitting of an excited state $|e\rangle$ into superposed stable states, oscillating at bandgap frequencies ω_i, whose amplitudes c_i, and eigenfrequencies ω_i are controllable by the atomic transition detuning from cutoff, constitutes spontaneous coherence control.

If, however, ω_a is far from the cutoff, then eqn [2] results in an exponentially decaying amplitude:

$$\alpha(t) \approx e^{-(\gamma_a + i\tilde{\omega}_a)t} \qquad [9]$$

where $\tilde{\omega}_a = \omega_a + \Delta_a$, Δ_a, and γ_a being the effective spectral shift and width of the decaying atom. This regime holds for a locally smooth $G(\omega \approx \omega_a)$ such that

$$|\gamma'_a|, |\Delta'_a| \ll 1;\ |\gamma'_a \Delta_a| \ll \gamma_a;\ \gamma_a, |\Delta_a| \ll |\omega_a - \omega_g| \qquad [10]$$

where ω_g is the bandedge frequency nearest to ω_a and the primes denote differentiation with respect to ω_a.

We now apply the foregoing general results to a model DOM distribution. This distribution is derived on keeping the lowest term in the Taylor expansion of the dispersion relation $\omega(\vec{k})$ near a photonic bandedge ω_U (the effects of the further PBG edge are neglected). This yields the effective mass approximation:

$$\omega \approx \omega_U + \sum_{i=x,y,z} (k - k_U)_i^2 / m_i \qquad [11]$$

with $1/m_i = (1/2)(\partial^2 \omega / \partial k_i^2)|_{\omega = \omega_U}$. In a structure with period L, k_U satisfies the Bragg condition $k_U = \pi/L$. The corresponding DOM in a 3D-periodic structure with an allowed symmetry may be approximated as

$$\rho(\omega) \sim (\omega - \omega_U)^{(1-D)/2} \theta(\omega - \omega_U) \qquad [12]$$

where θ is the step function and D is the dimension of the Brillouin-zone surface spanned by bandedge modes with vanishing group velocity. In realistic photonic structures $D \le 2$, $D = 2$ corresponding to completely isotropic dispersion (spherical Brillouin-zone surface) and $D = 0$ corresponding to an anisotropic three-dimensional Brillouin zone. Both cases can be represented, respectively, as the limits $\varepsilon \to 0$ and $\varepsilon \to \infty$ of the function:

$$G(\omega) = \frac{C}{\pi} \frac{\sqrt{\omega - \omega_U}}{\omega - \omega_U + \varepsilon} \theta(\omega - \omega_U) \qquad [13]$$

where ε is the 'cutoff-smoothing' parameter and C is the continuum coupling constant. Depending on whether $C^{2/3}/\varepsilon$ is greater or less than one, the continuum is close to the case $\varepsilon = 0$ ($D = 2$) or $\varepsilon \to \infty$ ($D = 0$), respectively.

Using the properties of the model DOM (eqn [13]), we can infer the criteria for the two regimes discussed above:

(i) The conditions for incomplete decay, eqn [6], are now (Figure 2) $\Delta_c \equiv \omega_a - \omega_U < C\varepsilon^{-1/2}$. Hence, the abrupt, singular cutoff of the DOM with $D = 2$ ($\varepsilon \to 0$) implies the existence of a discrete state for any ω_a, either inside or outside the PBG. The energy of the discrete state, $\hbar\omega_0$, which must lie in the PBG, is found to be a real and positive root of the equation $\omega_a - \omega_0 = C/(\sqrt{\omega_U - \omega_0} + \sqrt{\varepsilon})$.



Figure 2 (a) Incomplete decay of the excited state population as a function of $\gamma_c t$, where $\gamma_c = C\varepsilon^{-1/2}$, for $\varepsilon = 10^{-3}$, at cutoff $\Delta_c = 0$. The beat period is $2\pi/(\omega_U - \omega_0)$ and the nondecaying probability is $c_0^2 = 4/9$. (b) The corresponding spectrum. The frequency is normalized to γ_c.

(ii) The conditions for nearly exponential decay, eqn [10], can be shown to reduce now to the requirement that ω_a be in the allowed zone sufficiently far from cutoff, $\Delta_c \gg \min\{C^{2/3}, C\varepsilon^{-1/2}\}$. Under this condition, the intermediate-time exponential decay of the excited state (Figure 3) is given to first approximation by eqn [9], with $\gamma_a = C\sqrt{\Delta_c}/(\varepsilon + \Delta_c)$ and $\Delta_a = -C\sqrt{\varepsilon}/(\varepsilon + \Delta_c)$.

The resulting atomic frequency shift Δ_a is negative in the present model, vanishing for $\varepsilon \to 0$ $(D = 2)$. The long-time behavior of $\alpha(t)$ can be shown to exhibit a tail decaying as $t^{-3/2}$ (or $t^{-1/2}$ at $\Delta_c = C\varepsilon^{-1/2}$) and oscillating at the cutoff frequency ω_U (Figure 3).

With the increase of ε, the smoothing inhibits the decay more strongly for ω_a at cutoff, $\Delta_c = 0$, because $G(\omega_a \simeq \omega_U)$ is now weaker and the stable-state probability c_0 (eqn [7]) is correspondingly larger. By contrast, at a large detuning from cutoff Δ_c, the large-ε smoothing allows the decay to become complete, and the corresponding spectrum is entirely Lorentzian.



Figure 3 As in Figure 2, for a large detuning from the sharp cutoff, $\varepsilon = 10^{-3}$, $\Delta_c = 0.3$. (a) $\log_{10}|\alpha|t|^2$ is plotted as a function of *i*. The nearly complete decay ($c_0^2 \sim 10^{-3}$) is modulated by beats with frequency Δ_c. A power tail obtains for $t \gg \gamma_a^{-1} \approx \Delta_c^{1/2}/C$, decreasing as $t^{-1/2}$ for $t \ll \Delta_c^2/C^2$ and as $t^{-3/2}$ for $t \gg \Delta_c^2/C^2$. (b) The nearly Lorentzian spectrum, w(ω), has a small peak near ω_U, due to the sharply peaked DOM near the cutoff.

A defect in the periodic structure can produce a narrow-linewidth local mode in the PBG, whose spectral response is describable by a Lorentzian:

$$G_d(\omega) = \frac{\gamma_d}{\pi} \frac{\Gamma_d^2}{\Gamma_d^2 + (\omega - \omega_d)^2} \qquad [14]$$

where γ_d characterizes the coupling strength of the atomic dipole with the defect field, whereas ω_d and Γ_d stand for the line center and width, respectively. The presence of a nonvanishing DOM in the PBG, due to a defect, causes spontaneous emission in the PBG spectral range. This broadens the discrete state ω_0, which becomes metastable (see Figure 4). The oscillator strength of the line at ω_0 is then proportional to c_0.

EIT and Cross-Coupling of Photons in Doped PCs

Nonlinear effects, whereby one light beam influences another, require strong fields or else light confinement in a high-Q cavity. The analysis above has shown that by choosing an appropriate detuning of an atomic transition from the PBG cutoff, the spontaneous coherence is established between the states of an initially excited atom. The ability to control this coherence, by varying the detuning, opens interesting perspectives for optical processes in PCs containing multilevel atoms with a resonant transition near a bandedge. From among such processes, we discuss here electromagnetically induced transparency (EIT) and its applicability to nonlinear photon switching or giant cross-phase modulation.

Let us examine the nonlinear coupling of two weak (single-photon) optical fields E_a and E_b with the frequencies ω_a and ω_b, respectively, propagating along the z-axis in a PC dilutely doped with identical four-level atoms (**Figure 5a**). These fields interact with the atoms via the transitions $|1\rangle \rightarrow |2\rangle$ and $|3\rangle \rightarrow |4\rangle$, respectively, while the transition $|2\rangle \rightarrow |3\rangle$ is coupled to the structured mode-continuum $\rho(\omega)$ in the PC (**Figure 5b**). Initially the atoms are in the ground state $|1\rangle$ and the continuum is in the vacuum state $\{0_\omega\}$. Then the wavefunction of the system at the position z_l of the lth atom reads:

$$|\Psi(z_l,t)\rangle = \alpha_1|1,\{0_\omega\}\rangle + \alpha_2|2,\{0_\omega\}\rangle + \int \beta_{3,\omega}|3,1_\omega\rangle\rho(\omega)\mathrm{d}\omega + \int \beta_{4,\omega}|4,1_\omega\rangle\rho(\omega)\mathrm{d}\omega \qquad [15]$$



Figure 4 Spectrum w(ω)(same units as in **Figures 2** and **3**) for ω_a at cutoff, $\Delta_\mathrm{c} = 0$, in the presence of a defect in the PBG, $\omega_\mathrm{d} = -10$, $\gamma = 0.1$, $\Gamma_\mathrm{d} = 3$, $\varepsilon = 10^{-3}$. The oscillator strength is now roughly equally shared between the distribution above cutoff (same as in **Figure 2b**) and the defect peak at ω_0.

The consecutive terms in eqn [15] denote the atom being in states $|1\rangle$, $|2\rangle$, $|3\rangle$, or $|4\rangle$, with zero $\{0_\omega\}$ or one $|1_\omega\rangle$ photon in mode ω whose DOM is $\rho(\omega)$, and α_1, α_2, $\beta_{3,\omega}$, or $\beta_{4,\omega}$ are the corresponding probability amplitudes. Upon making the weak-field linear-response approximation, we can set $\alpha_1 \simeq 1$ and solve the set of equations for the slowly varying (compared to an optical cycle) probability amplitudes α and β, using the perturbation theory. Under these conditions, we effectively obtain a free-space propagation of the E_b field. By contrast, the evolution of the E_a field in the slowly varying envelope approximation, is given by $E_\mathrm{a}(z,t) = E_\mathrm{a}(0, t - z/v_\mathrm{g})\exp(ipz)$. We thus see that the real part of the macroscopic complex polarizability p is responsible for the phase shift ϕ_a of the E_a field, $\phi_\mathrm{a} = \mathrm{Re}(p)z$, while the probability of the absorption $\mathscr{A}$ of the field depends on the imaginary part of p, $\mathscr{A} = 1 - \exp[-2\mathrm{Im}(p)z]$. The polarizability is expressed by

$$p = a_0 \frac{i\gamma_2/2}{\gamma_2/2 - i\Delta_\mathrm{a} + I(\Delta_\mathrm{a})} \qquad [16]$$

where $a_0 \equiv \sigma_0 N$ is the linear resonant absorption coefficient on the atomic transition $|1\rangle \rightarrow |2\rangle$, with σ_0 the resonant absorption cross-section and N the density of doping atoms, γ_2 is the radiative width of



Figure 5 (a) Photonic crystal dilutely doped with atoms located at black dots. (b) Four-level atom coupled to a structured continuum $\rho(\omega)$ near the band-edge or defect mode frequencies (DOM plotted) via the intermediate transition $|2\rangle \rightarrow |3\rangle$ and interacting with two weak fields E_a and E_b at the sideband transitions $|1\rangle \rightarrow |2\rangle$ and $|3\rangle \rightarrow |4\rangle$, respectively.

state $|2\rangle$, $\Delta_a = \omega_a - \omega_{21}$ is the detuning from the atomic resonance ω_{21}, and $I(\Delta_a)$ is the integral of the saturation factor over the structured DOM. The group velocity v_g is expressed as $v_g = \partial_{k_a}\omega_a = [n_a/c + \partial_{\omega_a}\mathrm{Re}(p)]^{-1}$, where n_a is the (averaged) refraction index at the frequency ω_a.

To calculate $I(\Delta_a)$, we assume the isotropic PBG model, eqn [13] with $\varepsilon \to 0$, with the atoms doped at the positions of the local defects in the PC separated by a distance d from each other. These defect modes in the PBG are localized around each atomic site in a volume $V_d \simeq (rL)^3$ of several $(r)^3$ lattice cells L^3, with $L \simeq \pi c/\omega_{23}$, and serve as effective high-Q cavities, eqn [14] with $\Gamma_d \ll 1$. Assuming $|\Delta_b| \gg |\Delta|, |\Delta_a|, \gamma_4$, where $\Delta_b = \omega_b - \omega_{43}$ and $\Delta = \omega - \omega_{23}$, the integration leads to

$$I(\Delta_a) = \frac{B_d^2}{\gamma_{31} - i(\Delta_a - \Delta_d - s_3)} - \frac{B_U^{3/2}}{\sqrt{i\gamma_{31} + (\Delta_a - \Delta_U - s_3)}} \qquad [17]$$

where $\Delta_{d,U} = \omega_{d,U} - \omega_{23} \ll \omega_{23}$ are the detunings of the defect-mode and PBG-edge frequencies from the atomic resonance ω_{23}, γ_{31} the $|1\rangle \leftrightarrow |3\rangle$ decoherence rate, $s_3 = (\mu_{34}^2/\hbar^2\Delta_b)|E_b|^2$ is the E_b field-induced ac Stark shift of level $|3\rangle$ (μ_{ij} is the atomic dipole matrix element on the transition $|i\rangle \to |j\rangle$), and B_d and B_U are the coupling constants of the atom with the structured reservoir, whose main contributions are near ω_d and ω_U.

To illustrate the results of the foregoing analysis, we plot in Figure 6 the imaginary and real parts of the polarizability (eqn [16]). Consider first the case of one incident field $E_a (E_b = 0)$. Clearly, two frequency regions, $\Delta_a \sim \Delta_d$ and $\Delta_a \sim \Delta_U$, where the absorption vanishes and, at the same time, the dispersion slope is steep, are of particular interest. One can see that there is, however, a substantial difference between the spectra in the foregoing frequency regions, for the following physical reasons. First, in the vicinity of Δ_d, the atom interacts with the defect mode as in a high-Q cavity. This strong interaction 'dresses' the atomic states $|2\rangle$ and $|3\rangle$, thereby splitting the spectrum around $\Delta_a \simeq \Delta_d$ by the amount equal roughly to $2B_d$. Near the two-photon Raman resonance $\Delta_a = \Delta_d$, the two alternative transition paths $|1\rangle \to |2\rangle$ (the direct transition) and $|1\rangle \to |2\rangle \to |3\rangle \to |2\rangle$ (transition via state $|3\rangle$) interfere distractively with each other, cancelling thus the absorption of the E_a field and the medium becomes transparent to the radiation. This effect has been widely studied in atomic vapors, where the transition $|2\rangle \to |3\rangle$ is strongly driven by a coherent laser field, and is called electromagnetically induced transparency (EIT). The transparency window is rather broad and is given by the inverse Lorentzian (see the first term on the right-hand side of eqn [17]). Due to the steepness of the dispersion curve, the corresponding group velocity is much smaller than the speed of light, $v_g \simeq 2B_d^2/(\gamma_2 a_0) \ll c$, which leads to a large delay time $T_{del} = \zeta/v_g$ at the exit $z = \zeta$ from the medium. One has to keep in mind, however, that the absorption-free propagation time is limited by the EIT decoherence time $T_{del} < \gamma_{31}^{-1}$, which imposes a limitation on the length ζ of the active PC medium. Second, in the vicinity of Δ_U, the strong interaction of the atom with the continuum near the bandedge ω_U causes the Autler–Townes splitting of level $|2\rangle$ into a doublet with a separation equal roughly to B_U. One component of this doublet is shifted out of the PBG, while the other one remains



Figure 6 (a) Imaginary and (b) real part of the complex polarizability p as a function of the detuning Δ_a for the case $E_b = 0$ (solid lines) and $E_b \neq 0$ (dashed lines). The parameters (normalized by γ_2) are: $\Delta_d = -1$, $\Delta_U = 1$, $\gamma_{31} = 0.001$, $B_d = B_U = 1$, $s_3 = -0.1$, and $a_0 = 1\ \mathrm{cm}^{-1}$. The insets magnify the important frequency regions.

within the gap and forms the photon–atom bound state. Consequently, there is vanishing absorption and rapid variation of the dispersion at $\Delta_\mathrm{a} \simeq \Delta_\mathrm{U}$. Since the transparency region is very narrow with a width $\delta\omega \sim \gamma_{31}(\ll \gamma_2, B_\mathrm{U})$, for an absorption-free propagation of the E_a pulse, its temporal width τ_a should satisfy the condition $\tau_\mathrm{a} > \pi/\delta\omega$. Simultaneously, a small deviation from the condition $\Delta_\mathrm{a} = \Delta_\mathrm{U}$ will lead to a strong increase in the absorption of the E_a field.

Let us now switch on the E_b field. As seen from eqn [17], its effect is merely to shift the spectrum by the amount equal to s_3 (Figure 6). This shift, however, will have different implications in the two frequency regions distinguished above: if $s_3 \ll B_\mathrm{d}$, i.e., the Stark shift is smaller than the width of the EIT window at Δ_d, the medium will still remain transparent for an E_a field with the detuning $\Delta_\mathrm{a} = \Delta_\mathrm{d}$, but its phase will experience an appreciable nonlinear shift ϕ_a, given by $\phi_\mathrm{a} = Re(p)z \simeq -\gamma_2 a_0 s_3 z/(2B_d^2)$. On the other hand, for an E_a field with the detuning $\Delta_\mathrm{a} = \Delta_\mathrm{U}$, the medium, which is transparent for $E_\mathrm{b} = 0$, $\mathrm{Im}(p) \ll a_0$, will become highly absorptive (opaque) even for such a small frequency shift as s_3 (provided $s_3 < 0$ and $|s_3| > \Delta\omega$), $\mathrm{Im}(p) \simeq \gamma_2 a_0 \sqrt{|s_3|}/(2B_\mathrm{U}^{3/2})$ and thus acting as an ultrasensitive, effective switch.

The remaining question is how to maximize the interaction between the E_a pulse, which propagates with a small group velocity, and the E_b pulse, which propagates with a velocity close to the speed of light. The interaction between the fields is maximized if: they enter the medium simultaneously; the transverse shapes of their envelopes overlap completely; and the pulse length l_b of the E_b field satisfies the condition $(l_\mathrm{b} + \zeta)/c \le \zeta/v_\mathrm{g}$. Then the E_b pulse leaves the medium not later than the E_a pulse. The effective interaction length between the two pulses is, therefore, $z_\mathrm{eff} \sim l_\mathrm{b} v_\mathrm{g}/c \le \zeta$, after which the two pulses slip apart. Thus, the presence of the E_b (control) field induces either strong absorption or a large phase shift of the E_a (signal) field, depending on the frequency region employed.

The effects surveyed above reveal unusual features of spontaneous emission and photon–atom binding in PCs, atomic interaction with the field of a high-Q defect mode, and nonlinear coupling of two fields via four-level dopant atoms in PCs. These effects are of fundamental interest. In addition, they can serve as the basis for highly efficient optical communications and data processing, in either the classical or the quantum domain, by providing two key elements: ultrasensitive nonlinear phase-shifters and photon switches.

List of Units and Nomenclature

Atomic or photonic eigenstates [dimensionless]	$\|\ldots\rangle$
Complex polarizability [cm^{-1}]	p
Coupling constant [s^{-1}]	κ, $C^{2/3}$, B
Decay rate [s^{-1}]	γ
Density of modes [s]	ρ
Frequency [s^{-1}]	ω, Δ, s
Phase [dimensionless]	ϕ
Probability amplitudes [dimensionless]	α, β, c
Reservoir spectral response [s^{-1}]	G
Resonant absorption coefficient [cm^{-1}]	a_0
Spontaneous emission spectrum [s]	W
Wave vector [m^{-1}]	k

See also

Electromagnetically Induced Transparency. **Photonic Crystals:** Photonic Crystal Lasers, Cavities and Waveguides.

Further Reading

Joannopoulos JD, Meade RD and Winn JN (1995) *Photonic Crystals: Molding the Flow of Light*. Princeton, NJ: Princeton University Press.

John S and Wang J (1991) Quantum optics of localized light in a photonic band gap. *Physics Review B* 43: 12772–12789.

Kofman AG, Kurizki G and Sherman B (1994) Spontaneous and induced atomic decay in photonic band structures. *Journal of Modern Optics* 41: 353–384.

Lambropoulos P, Nikolopoulos GM, Nielsen TR and Bay S (2000) Fundamental quantum optics in structured reservoirs. *Reports on Progress in Physics* 63: 455–503.

Loudon R (1983) *The Quantum Theory of Light*. Oxford, UK: Clarendon Press.

Meystre P and Sargent M III (1991) *Elements of Quantum Optics*. Berlin: Springer Verlag.

Petrosyan D and Kurizki G (2001) Photon–photon correlations and entanglement in doped photonic crystals. *Physics Review A* 64: 023810-1-6.

Sakoda K (2001) *Optical Properties of Photonic Crystals*. Springer Series in Optical Sciences, 80. Berlin: Springer Verlag.

Scully MO and Zubairy MS (1997) *Quantum Optics*. Cambridge, UK: Cambridge University Press.

Electromagnetic Theory

S G Johnson and J D Joannopoulos,
Massachusetts Institute of Technology, Cambridge, MA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Photonic crystals are periodically structured electromagnetic media, generally possessing photonic bandgaps: ranges of frequency in which light cannot propagate through the structure. This periodicity, whose lengthscale is proportional to the wavelength of light in the bandgap, is the electromagnetic analog of a crystalline atomic lattice, where the latter acts on the electron wavefunction to produce the familiar band gaps, semiconductors, etc., of solid-state physics. The study of photonic crystals is likewise governed by the Bloch–Floquet theorem, and intentionally introduced defects in the crystal (analogous to electronic dopants) give rise to localized electromagnetic states: linear waveguides and point-like cavities. The crystal can thus form a kind of perfect optical 'insulator', which can confine light around sharp bends, in lower-index media, and within wavelength-scale cavities, among other novel possibilities for control of electromagnetic phenomena. Below is introduced the basic theoretical background of photonic crystals in one, two, and three dimensions (schematically depicted in Figure 1), as well as hybrid structures that combine photonic-crystal effects in some directions with more-conventional index guiding in other directions. (Line and point defects in photonic crystals are discussed in another article.)

Electromagnetic wave propagation in periodic media was first studied by Lord Rayleigh in 1887, in connection with the peculiar reflective properties of a crystalline mineral with periodic 'twinning' planes (across which the dielectric tensor undergoes a mirror flip). These correspond to one-dimensional photonic crystals, and he identified the fact that they have a narrow bandgap prohibiting light propagation through the planes. This bandgap is angle-dependent, due to the differing periodicities experienced by light propagating at non-normal incidences, producing a reflected color that varies sharply with angle. (A similar effect is responsible for many other iridescent colors in nature, such as those of butterfly wings and abalone shells.) Although multilayer films received intensive study over the following century, it was not until 100 years later, when Yablonovitch and John, in 1987, joined the tools of classical electromagnetism and solid-state physics, that the concepts of omnidirectional photonic bandgaps in two and three dimensions was introduced. This generalization, which inspired the name 'photonic crystal', led to many subsequent developments in their fabrication, theory, and application, from integrated optics to negative refraction to optical fibers that guide light in air.


1-D
2-D
3-D
Periodic in one direction
Periodic in two directions
Periodic in three directions

Figure 1 Schematic depiction of photonic crystals periodic in one, two, and three directions, where the periodicity is in the material (typically dielectric) structure of the crystal. Only a 3d periodicity, with a more complex topology than is shown here, can support an omnidirectional photonic bandgap.

Maxwell's Equations in Periodic Media

The study of wave propagation in three-dimensionally periodic media was pioneered by Felix Bloch in 1928, unknowingly extending an 1883 theorem in one dimension by Gaston Floquet. Bloch proved that waves in such a medium can propagate without scattering, their behavior described by a periodic envelope function multiplied by a planewave. Although Bloch studied quantum mechanics, leading to the surprising result that electrons in a conductor scatter only from imperfections and not from the periodic ions, the same techniques can be applied to electromagnetism by casting Maxwell's equations as an eigenproblem in analog with Schrödinger's equation. By combining the source-free Faraday's and Ampere's laws at a fixed (angular) frequency ω, i.e., time dependence $e^{-i\omega t}$, one can obtain an equation in only the magnetic field $\vec{H}$:

$$\vec{\nabla}\times\frac{1}{\varepsilon}\vec{\nabla}\times\vec{H}=\left(\frac{\omega}{c}\right)^2\vec{H} \qquad [1]$$

where ε is the dielectric function $\varepsilon(x,y,z)$ and c is the speed of light. This is an eigenvalue equation, with eigenvalue $(\omega/c)^2$ and an eigen-operator $\vec{\nabla}\times(1/\varepsilon)\vec{\nabla}\times$ that is Hermitian (acts the same to the left and right) under the inner product $\int \vec{H}^* \cdot \vec{H}'$ between two fields $\vec{H}$ and $\vec{H}'$. (The two curls correspond roughly to the 'kinetic energy' and $1/\varepsilon$ to the 'potential' compared to the Schrödinger Hamiltonian $\nabla^2 + V$.) It is sometimes more convenient to write a generalized Hermitian eigenproblem in the electric field $\vec{E}$, $\vec{\nabla} \times \vec{\nabla} \times \vec{E} = (\omega/c)^2 \varepsilon \vec{E}$, which separates the kinetic and potential terms. Electric fields that lie in higher ε, i.e., lower potential, will have lower ω; this is discussed further in the context of the variational theorem of eqn [3].

Thus, the same linear-algebraic theorems as those in quantum mechanics can be applied to the electromagnetic wave solutions. The fact that the eigen-operator is Hermitian and positive-definite (for real $\varepsilon > 0$) implies that the eigenfrequencies ω are real, for example, and also leads to orthogonality, variational formulations, and perturbation–theory relations that are discussed further below. An important difference compared to quantum mechanics is that there is a transversality constraint: one typically excludes $\vec{\nabla} \cdot \vec{H} \neq 0$ (or $\vec{\nabla} \cdot \varepsilon \vec{E} \neq 0$) eigensolutions, which lie at $\omega = 0$; i.e., static-field solutions with free magnetic (or electric) charge are forbidden.

Bloch Waves and Brillouin Zones

A photonic crystal corresponds to a periodic dielectric function $\varepsilon(\vec{x}) = \varepsilon(\vec{x} + \vec{R}_i)$ for some primitive lattice vectors $\vec{R}_i$ ($i = 1, 2, 3$ for a crystal periodic in all three dimensions). In this case, the Bloch–Floquet theorem for periodic eigenproblems states that the solutions to eqn [1] can be chosen of the form $\vec{H}(\vec{x}) = e^{i\vec{k}\cdot\vec{x}} \vec{H}_{n,\vec{k}}(\vec{x})$ with eigenvalues $\omega_n(\vec{k})$, where $\vec{H}_{n,\vec{k}}$ is a periodic envelope function satisfying

$$\left(\vec{\nabla} + i\vec{k}\right) \times \frac{1}{\varepsilon}\left(\vec{\nabla} + i\vec{k}\right) \times \vec{H}_{n,\vec{k}} = \frac{\omega_n(\vec{k})}{c}^2 \vec{H}_{n,\vec{k}} \qquad [2]$$

yielding a different Hermitian eigenproblem over the primitive cell of the lattice at each Bloch wavevector $\vec{k}$. This primitive cell is a finite domain if the structure is periodic in all directions, leading to discrete eigenvalues labeled by $n = 1, 2, \ldots$. These eigenvalues $\omega_n(\vec{k})$ are continuous functions of $\vec{k}$, forming discrete 'bands' when plotted versus the latter, in a 'band structure' or dispersion diagram – both ω and $\vec{k}$ are conserved quantities, meaning that a band diagram maps out all possible interactions in the system. (Note also that $\vec{k}$ is not required to be real; complex $\vec{k}$ gives evanescent modes that can exponentially decay from the boundaries of a finite crystal, but which cannot exist in the bulk.)

Moreover, the eigensolutions are periodic functions of $\vec{k}$ as well: the solution at $\vec{k}$ is the same as the solution at $\vec{k} + \vec{G}_j$, where $\vec{G}_j$ is a primitive reciprocal lattice vector defined by $\vec{R}_i \cdot \vec{G}_j = 2\pi\delta_{i,j}$. Thanks to this periodicity, one need only compute the eigensolutions for $\vec{k}$ within the primitive cell of this reciprocal lattice – or, more conventionally, one considers the set of inequivalent wavevectors closest to the $\vec{k} = 0$ origin, a region called the first Brillouin zone. For example, in a one-dimensional system, where $R_1 = a$ for some periodicity a and $G_1 = 2\pi/a$, the first Brillouin zone is the region $k = -\pi/a \ldots \pi/a$; all other wavevectors are equivalent to some point in this zone under translation by a multiple of G_1. Furthermore, the first Brillouin zone may itself be redundant if the crystal possesses additional symmetries such as mirror planes; by eliminating these redundant regions, one obtains the irreducible Brillouin zone, a convex polyhedron that can be found tabulated for most crystalline structures. In the preceding one-dimensional example, since most systems will have time-reversal symmetry ($k \to -k$), the irreducible Brillouin zone would be $k = 0 \ldots \pi/a$.

The familar dispersion relations of uniform waveguides arise as a special case of the Bloch formalism: such translational symmetry corresponds to a period $a \to 0$. In this case, the Brillouin zone of the wavevector k (also called β) is unbounded, and the envelope function $\vec{H}_{n,k}$ is a function only of the transverse coordinates.

The Origin of the Photonic Bandgap

A complete photonic bandgap is a range of ω in which there are no propagating (real $\vec{k}$) solutions of Maxwell's eqn [2] for any $\vec{k}$, surrounded by propagating states above and below the gap. There are also incomplete gaps, which only exist over a subset of all possible wavevectors, polarizations, and/or symmetries. Both sorts of gaps are discussed in the subsequent sections, but in either case, their origins are the same and can be understood by examining the consequences of periodicity for a simple one-dimensional system.

Consider a one-dimensional system with uniform $\varepsilon = \bar{\varepsilon}$, which has planewave eigensolutions $\omega(k) = ck$, as depicted in Figure 2(left). This ε has trivial periodicity a for any $a \geq 0$, with $a = 0$ giving the usual unbounded dispersion relation. One is free, however, to label the states in terms of Bloch envelope functions and wavevectors for some $a \neq 0$, in which case the bands for $|k| > \pi/a$ are translated (folded) into the first Brillouin zone, as shown by the dashed lines in Figure 2(left). In particular, the $k = -\pi/a$ mode in this description now lies at an equivalent wavevector to the $k = \pi/a$ mode, and at the same frequency; this accidental degeneracy is an artifact of



Figure 2 Left: Dispersion relation (band diagram), frequency ω versus wavenumber k, of a uniform one-dimensional medium, where the dashed lines show the 'folding' effect of applying Bloch's theorem with an artificial periodicity a. Right: Schematic effect on the bands of a physical periodic dielectric variation (inset), where a gap has been opened by splitting the degeneracy at the $k = \pm\pi/a$ Brillouin-zone boundaries (as well as a higher-order gap at $k = 0$).

the 'artificial' period that has been chosen. Instead of writing these wave solutions with electric fields $\vec{E}(x) \sim e^{\pm i\pi x/a}$, one can equivalently write linear combinations $e(x) = \cos(\pi x/a)$ and $o(x) = \sin(\pi x/a)$ as shown in Figure 3, both at $\omega = c\pi/a\sqrt{\varepsilon}$. Now, however, suppose that one perturbs ε so that it is nontrivially periodic with period a; for example, a sinusoid $\varepsilon(x) = \bar{\varepsilon} \cdot [1 + \Delta \cdot \cos(2\pi x/a)]$, or a square wave as in the inset of Figure 2(right). In the presence of such an oscillating 'potential', the accidental degeneracy between $e(x)$ and $o(x)$ is broken: supposing $\Delta > 0$, then the field $e(x)$ is more concentrated in the higher-ε regions than $o(x)$, and so lies at a lower frequency. This opposite shifting of the bands away from the mid-gap frequency $\omega \cong c\pi/a\sqrt{\bar{\varepsilon}}$ creates a bandgap, as depicted in Figure 2(right). (In fact, from the perturbation theory described subsequently, one can show that for $\Delta \ll 1$ the bandgap, as a fraction of mid-gap frequency, is $\Delta\omega/\omega \cong \Delta/2$.) By the same arguments, it follows that any periodic dielectric variation in one dimension will lead to a bandgap, albeit a small gap for a small variation; a similar result was identified by Lord Rayleigh in 1887.

More generally, it follows immediately from the properties of Hermitian eigensystems that the eigenvalues minimize a variational problem:

$$\omega^2_{n,\vec{k}} = \min_{\vec{E}_{n,\vec{k}}} \frac{\int \left|\left(\vec{\nabla} + i\vec{k}\right) \times \vec{E}_{n,\vec{k}}\right|^2}{\int \varepsilon \left|\vec{E}_{n,\vec{k}}\right|^2} c^2 \qquad [3]$$



Figure 3 Schematic origin of the band gap in one dimension. The degenerate $ka = \pm\pi/a$ planewaves of a uniform medium are split into $\cos(\pi x/a)$ and $\sin(\pi x/a)$ standing waves by a dielectric periodicity, forming the lower and upper edges of the bandgap, respectively – the former has electric-field peaks in the high dielectric (n_{high}) and so will lie at a lower frequency than the latter (which peaks in the low dielectric).

in terms of the periodic electric field envelope $\vec{E}_{n,\vec{k}}$, where the numerator minimizes the 'kinetic energy' and the denominator minimizes the 'potential energy' Here, the $n > 1$ bands are additionally constrained to be orthogonal to the lower bands:

$$\int \vec{H}^*_{m,\vec{k}} \cdot \vec{H}_{n,\vec{k}} = \int \varepsilon \vec{E}^*_{m,\vec{k}} \cdot \vec{E}_{n,\vec{k}} = 0 \qquad [4]$$

for $m < n$. Thus, at each $\vec{k}$, there will be a gap between the lower 'dielectric' bands concentrated in the high dielectric (low potential) and the upper 'air' bands that are less concentrated in the high dielectric: the air bands are forced out by the orthogonality condition, or otherwise must have fast oscillations that increase their kinetic energy. (The dielectric/air bands are analogous to the valence/conduction bands in a semiconductor.)

In order for a complete bandgap to arise in two or three dimensions, two additional hurdles must be overcome. First, although in each symmetry direction of the crystal (and each $\vec{k}$ point) there will be a bandgap by the one-dimensional argument, these bandgaps will not necessarily overlap in frequency (or even lie between the same bands). In order that they overlap, the gaps must be sufficiently large, which implies a minimum ε contrast (typically at least 4/1 in 3d). Since the 1d mid-gap frequency $\sim c\pi/a\sqrt{\bar{\varepsilon}}$ varies inversely with the period a, it is also helpful if the periodicity is nearly the same in different directions – thus, the largest gaps typically arise for hexagonal lattices in 2d and fcc lattices in 3d, which have the most nearly circular/spherical Brillouin zones. Second, one must take into account the vectorial boundary conditions on the electric field: moving across a dielectric boundary from ε to some $\varepsilon' < \varepsilon$, the inverse 'potential' $\varepsilon|\vec{E}|^2$ will decrease discontinuously if $\vec{E}$ is parallel to the interface ($\vec{E}_\parallel$ is continuous) and will increase discontinuously if $\vec{E}$ is perpendicular to the interface ($\varepsilon\vec{E}_\perp$ is continuous). This means that, whenever the electric field lines cross a dielectric boundary, it is much harder to strongly contain the field energy within the high dielectric, and the converse is true when the field lines are parallel to a boundary. Thus, in order to obtain a large bandgap, a dielectric structure should consist of thin, continuous veins/membranes along which the electric field lines can run – this way, the lowest band(s) can be strongly confined, while the upper bands are forced to a much higher frequency because the thin veins cannot support multiple modes (except for two orthogonal polarizations). The veins must also run in all directions, so that this confinement can occur for all $\vec{k}$ and polarizations, necessitating a complex topology in the crystal.

Ultimately, however, in two or three dimensions there are only rules of thumb for the existence of a bandgap in a periodic structure, since no rigorous criteria have yet been determined. This made the design of 3d photonic crystals a trial and error process, with the first example by Ho *et al.* of a complete 3d gap coming three years after the initial 1987 concept. As is discussed by the final section below, a small number of families of 3d photonic crystals have since been identified, with many variations thereof explored for fabrication.

Computational Techniques

Because photonic crystals are generally complex, high index-contrast, two- and three-dimensional vectorial systems, numerical computations are a crucial part of most theoretical analyses. Such computations typically fall into three categories: time-domain 'numerical experiments' that model the time-evolution of the fields with arbitrary starting conditions in a discretized system (e.g., finite-difference); definite-frequency transfer matrices wherein the scattering matrices are computed in some basis to extract transmission/reflection through the structure; and frequency-domain methods to directly extract the Bloch fields and frequencies by diagonalizing the eigenoperator. The first two categories intuitively correspond to directly measurable quantities such as transmission (although they can also be used to compute e.g., eigenvalues), whereas the third is more abstract, yielding the band diagrams that provide a guide to interpretation of measurements as well as a starting-point for device design and semi-analytical methods. Moreover, several band diagrams are included in the following sections, and so the frequency-domain method used to compute them is briefly outlined here.

Any frequency–domain method begins by expanding the fields in some complete basis, $\vec{H}_{\vec{k}}(\vec{x}) = \sum_n h_n \vec{b}_n(\vec{x})$, transforming the partial differential eqn [2] into a discrete matrix eigenvalue problem for the coefficients h_n. Truncating the basis to N elements leads to $N \times N$ matrices, which could be diagonalized in $O(N^3)$ time by standard methods. This is impractical for large 3d systems, however, and is also unnecessary – typically, one only wants the few lowest eigenfrequencies, in which case one can use iterative eigensolver methods requiring only $\sim O(N)$ time. Perhaps the simplest such method is based directly on the variational theorem eqn [3]: given some starting coefficients h_n, one iteratively minimizes the variational 'Rayleigh' quotient using e.g., preconditioned conjugate–gradient descent. This yields the lowest band's eigenvalue and field, and upper bands are found by the same minimization while orthogonalizing against the lower bands ('deflation'). There is one additional difficulty, however, and that is that one must at the same time enforce the $(\vec{\nabla} + i\vec{k}) \cdot \vec{H}_{\vec{k}} = 0$ transversality constraint, which is nontrivial in three dimensions. The simplest way to maintain this constraint is to employ a basis that is already transverse, for example planewaves $\vec{h}_{\vec{G}} e^{i\vec{G}\cdot\vec{x}}$ with transverse amplitudes $\vec{h}_{\vec{G}} \cdot (\vec{G} + \vec{k}) = 0$. (In such a planewave basis, the action of the eigen-operator can be computed via a fast Fourier transform in $O(N \log N)$ time.)

Semi-analytical Methods: Perturbation Theory

As in quantum mechanics, the eigenstates can be the starting point for many analytical and semi-analytical studies. One common technique is perturbation theory, applied to small deviations from an ideal system – closely related to the variational eqn [3], perturbation theory can be exploited to consider effects such as nonlinearities, material absorption, fabrication disorder, and external tunability. Not only is perturbation theory useful in its own right, but it also illustrates both old and peculiarly new features that arise in such analyses of electromagnetism compared to scalar problems such as quantum mechanics.

Given an unperturbed eigenfield $\vec{E}_{n,\vec{k}}$ for a structure ε, the lowest-order correction $\Delta\omega_n^{(1)}$ to the eigenfrequency from a small perturbation $\Delta\varepsilon$ is given by

$$\Delta\omega_n^{(1)} = -\frac{\omega_n(\vec{k})}{2} \frac{\int \Delta\varepsilon \left|\vec{E}_{n,\vec{k}}\right|^2}{\int \varepsilon \left|\vec{E}_{n,\vec{k}}\right|^2} \qquad [5]$$

where the integral is over the primitive cell of the lattice. A Kerr nonlinearity would give $\Delta\varepsilon \sim |\vec{E}|^2$, material absorption would produce an imaginary frequency correction (decay coefficient) from a small imaginary $\Delta\varepsilon$, and so on. Similarly, one can compute the shift in frequency from a small $\Delta\vec{k}$ in order to determine the group velocity $\mathrm{d}\omega/\mathrm{d}k$; this variation of perturbation theory is also called $k \cdot p$ theory. All such first-order perturbation corrections are well known from quantum mechanics, and in the limit of infinitesimal perturbations give the exact Hellman–Feynman expression for the derivative of the eigenvalue. However, in the limit where $\Delta\varepsilon$ is a small shift Δh of a dielectric boundary between some ε_1 and ε_2, an important class of geometric perturbation, eqn [5] gives a surface integral of $|\vec{E}|^2$ on the interface, but this is ill-defined because the field there is discontinous. The proper derivation of perturbation theory in the face of such discontinuity requires a more careful limiting process from an anisotropically smoothed system, yielding the surface integral:

$$\Delta\omega_n^{(1)} = -\frac{\omega_n(\vec{k})}{2}\,\frac{\int\int \Delta h\left(\Delta\varepsilon_{12}\left|\vec{E}_{\|}\right|^2 - \Delta\varepsilon_{12}^{-1}\left|D_{\perp}\right|^2\right)}{\int \varepsilon\left|\vec{E}_{n,\vec{k}}\right|^2}$$

where $\Delta\varepsilon_{12} = \varepsilon_1 - \varepsilon_2, \Delta\varepsilon_{12}^{-1} = \varepsilon_1^{-1} - \varepsilon_2^{-1}$, and $\vec{E}_{\|}/D_{\perp}$ denotes the (continuous) interface parallel/perpendicular components of the unperturbed electric/displacement eigenfield. A similar expression is required in high index-contrast systems to employ, e.g., coupled-mode theory for slowly-varying waveguides or Green's functions for interface roughness.

Standard perturbation–theory techniques also provide expressions for higher-order corrections to the eigenvalue and eigenfield, based on an expansion in the basis of the unperturbed eigenfields. This approach, however, runs into immediate difficulty because the eigenfields are also subject to the transversality constraint, $(\vec{\nabla} + i\vec{k}) \cdot \varepsilon\vec{E}_{\vec{k}} = 0$, and this constraint varies with ε and $\vec{k}$ – the eigenfields $\vec{E}_{\vec{k}}$ are not a complete basis for the eigenfields constrained at a different ε or $\vec{k}$. For ε perturbations, this problem can be eliminated by using the $\vec{H}$ or $\vec{D}$ eigenproblems, whose constraints are independent of ε. For $\vec{k}$ perturbations, one can employ a transformation by Sipe to derive a corrected higher-order perturbation theory (for e.g., the group-velocity dispersion), based on the fact that all of the non-transverse fields lie at $\omega = 0$. Such completeness issues also arise applying the variational eqn [3], as was noted in the previous section: in order for a useful variational bound to apply, one must operate in the constrained (transverse) subspace.

Two-Dimensional Photonic Crystals

After the identification of one-dimensional bandgaps, it took a full century to add a second dimension, and three years to add the third. It should therefore come as no surprise that 2d systems exhibit most of the important characteristics of photonic crystals, from nontrivial Brillouin zones to topological sensitivity to a minimum index contrast, and can also be used to demonstrate most proposed photonic–crystal devices. The key to understanding photonic crystals in two dimensions is to realize that the fields in 2d can be divided into two polarizations by symmetry: *TM* (transverse magnetic), in which the magnetic field is in the (xy) plane and the electric field is perpendicular (z); and *TE* (transverse electric), in which the electric field is in the plane and the magnetic field is perpendicular.

Corresponding to the polarizations, there are two basic topologies for 2d photonic crystals, as depicted in Figure 4(top): high index rods surrounded by low index (top) and low-index holes in high index (bottom). Here, a hexagonal lattice is used because, as noted earlier, it gives the largest gaps. Recall that a photonic band gap requires that the electric field lines run along thin veins: thus, the rods are best suited to TM light ($\vec{E}$ parallel to the rods), and the holes are best suited to TE light ($\vec{E}$ running around the holes). This preference is reflected in the band diagrams, shown in Figure 4, in which the rods/holes (top/bottom) have a strong TM/TE band gap. For these diagrams, the rod/hole radius is chosen to be $0.2a/0.3a$, where a is the lattice constant (the nearest-neighbor periodicity) and the high/low ε is 12/1. The TM/TE bandgaps are then 47%/28% as a fraction of mid-gap frequency, but these bandgaps require a minimum ε contrast of 1.7/1 and 1.9/1, respectively. Moreover, it is conventional to give the frequencies ω in units of $2\pi c/a$, which is equivalent to a/λ (λ being the vacuum wavelength) – Maxwell's equations are scale-invariant, and the same solutions can be applied to any wavelength simply by choosing the appropriate a. For example, the TM mid-gap ω in these units is 0.36, so if one wanted this to correspond to $\lambda = 1.55\ \mu\mathrm{m}$ one would use $a = 0.36 \cdot 1.55\ \mu\mathrm{m} = 0.56\ \mu\mathrm{m}$.

The Brillouin zone (a hexagon) is shown at left-center, with the irreducible Brillouin zone shaded (following the sixfold symmetry of the crystal); the corners (high symmetry points) of this zone are given canonical names, where Γ always denotes the origin $\vec{k} = 0$, K is the nearest-neighbor direction,



Figure 4 Band diagrams and photonic band gaps for hexagonal lattices of high dielectric rods ($\varepsilon = 12$, $r = 0.2a$) in air (top), and air holes ($r = 0.3a$) in dielectric (bottom), where a is the center–center periodicity. The frequencies are plotted around the boundary of the irreducible Brillouin zone (shaded triangle, left center), with solid/dashed lines denoting TE/TM polarization (electric field parallel/perpendicular to plane of periodicity). The rods/holes have a gap in the TM/TE bands.

and M is the next-nearest-neighbor direction. The Brillouin zone is a two-dimensional region of wavevectors, so the bands $\omega_n(\vec{k})$ are actually surfaces, but in practice the band extrema almost always occur along the boundaries of the irreducible zone (i.e., the high-symmetry directions). So, it is conventional to plot the bands only along these zone boundaries in order to identify the bandgap, as is done in Figure 4.

Actually, the hole lattice can display not only a TE gap, but a complete photonic bandgap (for both polarizations) if the holes are sufficiently large (nearly touching). In this case, the thin veins between nearest-neighbor holes induce a TE gap, while the interstices between triplets of holes form ‘rod-like’ regions that support a TM gap overlapping the TE gap.

Photonic-Crystal Slabs

In order to realize 2d photonic-crystal phenomena in three dimensions, the most straightforward design is to simply fabricate a 2d-periodic crystal with a finite height: a photonic-crystal slab, as depicted in Figure 5. Such a structure can confine light vertically within the slab via index guiding, a generalization of total internal reflection – this mechanism is the source of several new tradeoffs and behaviors of slab systems compared to their 2d analogs.

The key to index guiding is the fact that the 2d periodicity implies that the 2d Bloch wavevector $\vec{k}_{\|}$ is a conserved quantity, so the projected band structure – all states in the bulk substrate/superstrate (the uniform regions far below/above the slab) versus their in-plane wavevector component (projected wavevector) – creates a map of which states can radiate vertically. If the slab is suspended in air, for example, then the eigensolutions of the bulk air are $\omega = c\sqrt{|\vec{k}_{\|}|^2 + k_{\perp}^2}$, which when plotted versus $\vec{k}_{\|}$ forms the continuous light cone $\omega \geq c|\vec{k}_{\|}|$, shown as a shaded region in Figure 5. Because the slab has a higher ε (12) than the air (1), and frequency goes as $1/\sqrt{\varepsilon}$, discrete guided bands are ‘pulled down’ in frequency from this continuum – these bands, lying beneath the light cone, cannot couple to any vertically



Figure 5 Projected band diagram for a finite-thickness (0.5*a*) slab of air holes in dielectric (cross section as in Figure 4 bottom), with the irreducible Brillouin zone at lower left. The shaded region is the light cone: the projection of all states that can radiate in the air. Solid/dashed lines denote guided modes (confined to the slab) that are even/odd with respect to the horizontal mirror plane of the slab, whose polarization is TE-like/TM-like, respectively. There is a 'bandgap' (region without guided modes) in the TE-like guided modes only.

radiating mode by the conservation law and so are confined to the slab (exponentially decaying away from it). If the horizontal mid-plane of the slab is a mirror symmetry plane, then just as there were TM and TE states in 2d, here there are two categories of modes: even (TE-like) and odd (TM-like) modes under reflections through the mirror plane (which are purely TE/TM in the mirror plane itself). Because the slab here is based on the 2d hole crystal, which had a TE gap, here there is a 26% 'bandgap' in the even modes: a range of frequencies in which there are no guided modes. It is not a complete photonic bandgap, not only because of the odd modes, but also because there are radiating (light cone) modes at every ω. The presence of these radiating modes means that if all in-plane translational symmetry is broken by a localized change in the structure, say a waveguide bend or a resonant cavity, then vertical radiation losses are inevitable; there are various strategies to minimize the losses to tolerable levels, however. On the other hand, if only one direction of translational symmetry is broken, as in a linear-defect waveguide, ideally lossless guiding can be maintained.

Photonic-crystal slabs have two new critical parameters that influence the existence of a gap. First, it must have vertical mirror symmetry in order that the gaps in the even and odd modes be treatable separately – such symmetry is broken by the presence of a substrate that is not the mirror image of the superstrate, but in practice the symmetry breaking can be weak if the index contrast is sufficiently high (so that the modes are strongly confined in the slab). Second, the height of the slab must not be too small (or the modes will be weakly confined) or too large (or higher-order modes will fill the gap); the optimum height is around half a wavelength λ/n_{eff} (relative to an average/effective index n_{eff} that depends on the polarization). In Figure 5, a height of $0.5a$ is used, which is near the optimum (with holes of radius $0.3a$ and $\varepsilon = 12$ as in the previous section).

Three-Dimensional Photonic Crystals

Photonic-crystal slabs are one way of realizing 2d photonic-crystal effects in three dimensions; an example of another way, lifting the sacrifices imposed by the light cone, is depicted in Figure 6. This is a 3d-periodic crystal, formed by an alternating hole-slab/rod-slab sequence in an ABCABC stacking of bilayers – equivalently, it is an fcc (face-centered cubic) lattice of air cylinders in dielectric, stacked and oriented in the 111 direction, where each overlapping layer of cylinders forms a rod/hole bilayer simultaneously. Its band diagram is shown in Figure 6 along the boundaries of its irreducible Brillouin zone (from a truncated octahedron, inset), and this structure has a >21% complete gap ($\Delta\omega$ as a fraction of mid-gap frequency) for $\varepsilon = 12/1$, forbidding light propagation for all wavevectors (directions) and all polarizations. Not only can this crystal confine light perfectly in 3d, but because its layers resemble 2d rod/hole crystals, it turns out that the confined modes created by defects in these layers strongly resemble the TM/TE states created by corresponding defects in two dimensions. One can therefore use this crystal to directly transfer designs from two to three dimensions while retaining omnidirectional confinement. Its fabrication, of



Figure 6 Band diagram (bottom) for 3d-periodic photonic crystal (top) consisting of an alternating stack of rod and hole 2d-periodic slabs (similar to **Figure 4**), with the corners of the irreducible Brillouin zone labeled in the inset. This structure exhibits a $\Delta\omega/\omega_{\text{midgap}} = 21\%$ omnidirectional bandgap.

course, is more complex than that of photonic-crystal slabs (with a minimum ε contrast of 4/1), but this and other 3d photonic crystal structures have been constructed even at micron (infrared) lengthscales, as described below.

There are three general dielectric topologies that have been identified to support complete 3d gaps for $\varepsilon = 12/1$ (e.g., Si:air) contrast: diamond-like arrangements of high dielectric 'atoms' surrounded by low dielectric, which can lead to $>20\%$ gaps between the 2nd and 3rd bands; fcc 'inverse opal' lattices of nearly-touching low dielectric spheres (or similar) surrounded by high dielectric, giving gaps around 10% between the 9th and 10th bands; and cubic 'scaffold' lattices of rods along the cube edges, giving $\sim$7% gaps between the 2nd and 3rd bands. It is notable that the first two topologies correspond to fcc lattices, which have the most nearly spherical Brillouin zones in accordance with the rules of thumb given above. Many variations on these topologies continue to be proposed – for example, the structure of Figure 6 is diamond/graphite-like – mainly in conjunction with different fabrication strategies, such as the following three successful approaches. First, layer-by-layer fabrication, in which individual crystal layers (typically of constant cross-section) are deposited one-by-one and etched with a 2d pattern via standard lithographic methods (giving fine control over placement of defects, etc.); Figure 6 can be constructed in this fashion (as well as other diamond-like structures with large gaps). Second, colloidal self-assembly, in which small dielectric spheres in a fluid automatically arrange themselves into close-packed (fcc) crystals by surface forces – these crystals can be back-filled with a high-index material, out of which the original spheres are dissolved in order to form inverse–opal crystals with a complete gap. Third, holographic lithography, in which a variety of 3d crystals can be formed by an interference pattern of four laser beams to harden a light-sensitive resin (which is then back-filled and dissolved, as with colloids, to achieve the requisite index contrast). The second and third techniques are notable for their ability to construct large-scale 3d crystals (thousands of periods) in a short time.

See also

Photonic Crystals: Atomic Physics; Photonic Crystal Lasers, Cavities and Waveguide.

Further Reading

Ashcroft NW and Mermin ND (1976) *Solid State Physics*. Philadelphia: Holt Saunders.

Cohen-Tannoudji C, Din B and Laloë F (1977) *Quantum Mechanics*. Paris: Hermann.

Joannopoulos JD, Meade RD and Winn JN (1995) *Photonic Crystals: Molding the Flow of Light*. Princeton: Princeton University Press.

Johnson SG and Joannopoulos JD (2002) *Photonic Crystals: The Road from Theory to Practice*. Boston: Kluwer.

Johnson SG, Ibanescu M, Skorobogatiy M, Weisberg O, Joannopoulos JD and Fink Y (2002) Perturbation theory for Maxwell's equations with shifting material boundaries. *Physical Review E* 65: 066611.

Sakoda K (2001) *Optical Properties of Photonic Crystals*. Berlin: Springer.

Sipe JE (2000) Vector $k \cdot p$ approach for photonic band structures. *Physical Review E* 62: 5672–5677.

Microwave Photonic Crystals

D F Sievenpiper, HRL Laboratories LLC, Malibu, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Photonic Crystals

Photonic crystals are materials that have a periodically varying dielectric constant that results in a bandgap, or range of frequencies where electromagnetic waves are unable to propagate. A simple one-dimensional example is the Bragg mirror, or quarter-wave stack, in which periodic layers of alternating dielectrics reflect photons within a frequency band determined by the thickness and refractive index of the layers. Photonic crystals are the extension of this concept into two or three dimensions. They are constructed as a lattice of two different dielectrics, and examples include a triangular lattice of circular rods, or a diamond lattice of spheres. Certain geometries will produce a bandgap, within which propagation is impossible in any direction. These materials are the photonic analog of semiconductors, in that their periodic dielectric function provides a bandgap for photons in much the same way that the periodic atomic potential of a crystal lattice can provide a bandgap for electrons.

While most photonic crystal research has focused on optical wavelength structures, many of the first experimental studies were performed on scale models at microwave frequencies, where fabrication and measurements were simpler. Operating at microwave frequencies also allowed a new class of materials to emerge, based on metals and lumped circuit elements. The nearly infinite dielectric contrast provided by the use of metals, and the ability to make complex subwavelength scale structures at radio frequencies, allows photonic crystals with ultra-wide bandgaps to be produced. Furthermore, the use of lumped circuit elements allows the electromagnetic properties to be easily tuned, resulting in unique microwave structures.

Wire Mesh Photonic Crystals

At optical frequencies, conductive losses preclude the use of metals for many applications. However, at microwave frequencies, metals are nearly ideal materials, since they have low loss and are easily formed into complicated geometries. The simplest metallic photonic crystal is a three-dimensional wire mesh, shown in Figure 1. This example resembles a diamond crystal lattice, in which metal wires have been substituted for atomic bonds. It can be constructed using zig-zag-shaped metal strips that fit together to form a continuous conductive network.

The electromagnetic properties of this wire mesh can be understood by considering a traditional microwave analog: an array of metal waveguides. Open tunnels permeate the mesh in various directions, and it behaves as an interpenetrating fabric of waveguides, whose walls are defined by the wires. Shorter wavelengths, that fit between the wires, can propagate through the crystal, while longer waves see the mesh as a continuous metal surface, and are reflected. As for a conventional waveguide, the cutoff frequency occurs approximately where one half wavelength fits between the rows of wires. Similarly, for a diamond lattice of wires, the cutoff frequency is

$$\omega_{\text{cutoff}} = \frac{\pi c}{na} \qquad [1]$$

where n is the refractive index of the material between the wires, and a is the length of the unit cube of the diamond lattice. Because the cutoff frequency is primarily determined by the diameter of the open tunnels, and it is largely independent of the detailed arrangement of the wires, other mesh geometries can



Figure 1 A wire mesh photonic crystal with diamond geometry. (a) The mesh forms continuous conductive structure that is permeated with open tunnels. (b) A diagram of one of the interlocking metal parts that fit together to form the crystal. (Reproduced with permission from Sievenpiper D, Sickmiller M and Yablonovitch E (1996) 3D wire mesh photonic crystals. *Physics Review Letters* 76: 2480. Copyright (1996) by the American Physical Society.)



Figure 2 The transmission magnitude through a conductive wire mesh photonic crystal as a function of frequency, ω. Shorter wavelengths can propagate through the open tunnels, while longer wavelengths see the mesh as a continuous block of metal. The cutoff frequency is determined largely by the lattice constant, *a*, and the refractive index, *n*, of the material between the wires. A cut wire forms a defect state within the band gap.

be expected to give similar results. However, the cutoff frequency can vary by a constant of order unity, depending on the lattice and the unit cell chosen.

The transmission magnitude, as a function of frequency for such a mesh, is depicted in Figure 2. Experimentally, it is found that a typical wire mesh structure attenuates roughly 6 dB per layer for frequencies below cutoff. However, because the exact transmission magnitude above cutoff depends on details of the measurement, such as impedance matching at the crystal boundary, the vertical scale shown here is arbitrary, and the intent is simply to give the qualitative behavior of these and similar crystal structures. Waves just below the cutoff frequency can penetrate a crystal with finite thickness, as depicted by the finite slope of the transmission edge.

We can better understand the behavior of waves within the crystal by examining the dispersion diagram, shown in Figure 3, in which we plot the allowed frequencies as a function of wave vector $k = 2\pi/\lambda$, the spatial frequency of waves inside the material. A band of allowed frequencies is bounded by upper and lower band edges, corresponding to high and low cutoff frequencies, beyond which propagation is forbidden. The reflective nature of the crystal below cutoff is shown as a bandgap that extends down to zero frequency. The slope of the dispersion curve corresponds to the group velocity of waves within the allowed band, and states at the bandedges represent standing waves. The upper edge of this band occurs where the wavelength matches the periodicity of the crystal, and for a diamond mesh, it is approximately

$$\omega_{\text{lattice}} = \frac{2\pi c}{na} \quad [2]$$



Figure 3 The dispersion diagram for a wire mesh photonic crystal, plotted as frequency, ω, versus wave vector k. The bandgap extends to zero frequency. The lower bandedge of the allowed band is determined largely by the lattice constant. Like other photonic crystals, the wire mesh also supports higher frequency bands, which are not shown. A point defect such as a cut wire creates a mode at a single frequency, which contains all wave vectors.

Like traditional dielectric photonic crystals, these wire mesh structures also have higher order bands and gaps that occur at higher frequencies. The nature of the higher band structure depends on the detailed geometry of the mesh to a much greater extent than the lowest order gap, which is our primary interest for radio frequency materials.

Defect States

As in semiconductor crystals, we can alter the behavior of photonic crystals by adding defects to create localized states within the bandgap. For the wire mesh photonic crystal, a defect may be a cut wire, or a lumped circuit element inserted into the mesh. For example, replacing one of the wires with a capacitor creates a parallel resonant circuit, which acts as a small electromagnetic cavity within the mesh. Its resonance frequency is given by

$$\omega_{\text{defect}} = \frac{1}{\sqrt{LC}} \quad [3]$$

where C is the capacitance of the defect, and L is the inductance of the surrounding wires. The inductance depends logarithmically on the wire diameter, so it is largely fixed for a given mesh lattice. However, the capacitance can be easily changed, since it is a simple lumped circuit element. Thus, by adding capacitive defects we can create tunable local states within the bandgap. The presence of a defect is seen as a narrow transmission band within the bandgap, shown in Figure 2. Because a point defect contains all wave vectors, it is shown as a horizontal line in the dispersion diagram in Figure 3.

If two defects are located in close proximity, their modes overlap, and they interact with each other. For example, two neighboring defects with identical capacitance will exhibit a split pair of resonances, corresponding to a lower frequency symmetric mode, and a higher frequency anti-symmetric mode. The modes are highly localized at the defects, and this interaction is limited to defects that are within one or two lattice constants of each other. If one member of a pair of nearby defects is tuned with respect to the other, the frequencies the two modes exhibit are an avoided crossing behavior, as is typical in many systems of coupled oscillators. The resonance frequencies for more complex arrangements of defects can be calculated by assigning an interaction energy to each neighboring pair, and solving the resulting Hamiltonian matrix to find the energy levels of the complete system. In this way, the interaction among defects in small clusters is analogous to atoms in simple molecules, and the resulting energy level structure is similar.

As more defects are added periodically throughout the mesh, they form a superlattice, and their states merge into an additional band within the original bandgap. The upper frequency of this band depends on the LC resonance frequency of the defects. The lower frequency depends on the density of the remaining wires, since waves at the lower bandedge must be able to fit through the open regions in the mesh. In the extreme case, where every wire is cut and replaced by a capacitor, the mesh is no longer a continuous conductive network. These structures have an allowed band that extends to zero frequency, and they will be explored in greater detail in the next section. Not every wire must be cut to reach this limit, and the conditions for this to occur are the subject of percolation theory.

Capacitive Mesh Photonic Crystals

In a capacitive mesh photonic crystal, small isolated metal islands are distributed on a lattice, and they are capacitively coupled to their neighbors. This represents the extreme case of the wire mesh photonic crystal, where every wire has been cut, and replaced by a capacitor. An example of such a structure, built as a stack of printed circuit boards, is shown in Figure 4. A diamond lattice can be approximated using planar circuit boards, with printed tetrapodal structures consisting of two orthogonal metal strips connected by a metal plated via. Each metallic island couples to its four nearest neighbors through their overlapping capacitor plates.

The capacitive mesh photonic crystal is transmissive at low frequencies because it is not traversed by conducting paths, like the continuous wire mesh version. The crystal supports a lower band that extends from zero frequency, up to an LC resonance frequency:

$$\omega_{\text{lower}} = \frac{1}{\sqrt{LC}} \qquad [4]$$

which marks the lower edge of the bandgap. This is determined by the capacitance between the metal islands, and the inductance associated with each island. At higher frequencies, the capacitors appear as shorts, and the crystal behaves similarly to the conductive wire mesh structure described previously, with an upper edge given by

$$\omega_{\text{upper}} = \frac{\pi c}{na} \qquad [5]$$

At this frequency, the waves can again fit through the open areas between the metallic islands. The transmission magnitude, as a function of frequency for the capacitive mesh photonic crystal, is shown in Figure 5, and the additional band is illustrated in the dispersion diagram in Figure 6. Like the conductive wire mesh, the capacitive mesh also has a rich upper band structure, that is outside the scope of this article.

With these capacitive mesh structures, it is possible to create materials with finite, but arbitrarily large bandgaps, because the upper and lower edges of the bandgap are controlled independently by the lattice constant and the capacitance, respectively. In conventional dielectric photonic crystals, the width of the bandgap depends on the dielectric contrast between the constituent materials. Waves at the upper edge primarily reside in the lower dielectric material, and waves at the lower edge inhabit the higher dielectric material. This reasoning can also be applied to capacitive mesh structures. The lower dielectric is the substrate material that fills the open spaces between the metal islands, and modes at the upper edge of the gap primarily fill these open spaces. However, for modes at the lower edge of the gap, the electric field is primarily concentrated within the capacitors. The metal regions and the capacitors can



Figure 4 A capacitive mesh photonic crystal, built as a diamond lattice of capacitively coupled metallic islands. It can be built by stacking printed circuit boards. (a) One 'atom' of the crystal, which is made of two small orthogonal metal strips connected by a metal-plated via. (b) A side view, showing how the metal strips overlap to form a capacitor. (c) Several periods of the completed crystal structure, shown without the substrate. (Reproduced with permission from Sievenpiper D, Yablonovitch E, Winn J, et al. (1998) 3D metallo-dielectric photonic crystals with strong capacitive coupling between metallic islands. Physics Review Lett. 80: 2829. Copyright (1998) by the American Physical Society.)



Figure 5 The transmission magnitude through a capacitive mesh photonic crystal, as a function of frequency. The crystal is transparent at low frequencies, because the conducting paths are broken by capacitors. At higher frequencies, the capacitors appear as shorts, and crystal behaves like a solid wire mesh.

be considered as an effective medium, or artificial dielectric whose properties depend on the density, arrangement, and values of the capacitors. By using large capacitors, the dielectric contrast can be made arbitrarily large, and the bandgap arbitrarily wide.

Within the bandgap, these materials can support surface waves, which are modes that are bound to the interface between the crystal and free space. Surface waves propagate along the crystal surface, and they have their own band structure. In the following sections, we examine these waves, and we will introduce periodically textured surfaces that suppress them, much like three-dimensional photonic crystals suppress internal plane waves.

Surface Waves

Electromagnetic waves that are bound to the interface between two materials are known as surface waves. They exist on ordinary metals, and at optical frequencies they are often called surface plasmons. They also exist on photonic crystals within the



Figure 6 The dispersion diagram of the capacitive mesh photonic crystal. The two edges of the bandgap can be adjusted independently by varying the lattice constant and the capacitance.

bandgap region, as well as on other impenetrable materials. They cannot propagate into the crystal because of Bragg reflection, yet they are prevented from escaping into free space by total internal reflection. They typically interact strongly with the top layer of the crystal, and they can often be manipulated or suppressed by adjusting the geometry of that layer. At radio and microwave frequencies, these waves are usually called surface currents, because the associated fields are only loosely bound to the surface, and extend a great distance into free space. Their presence can be seen in antenna radiation patterns and other phenomena, and by suppressing them we can make a variety of unique radio frequency devices. However, we must first understand the nature of these waves.

To understand the nature of these surface currents, we begin by examining surface waves on metals, where we assume a wave confined to a dielectric interface, and then insert the complex dielectric constant of a metal. Consider a surface in the YZ plane, where $X < 0$ is filled with dielectric ε, and $X > 0$ is filled with vacuum. A wave propagates in the Z direction with propagation constant k. For transverse magnetic (TM) polarized waves, which are illustrated in Figure 7, the transverse electric field $E_y = 0$. The electric field has the form

$$E_1 = (\hat{x}E_{1x} + \hat{z}E_{1z})e^{i\omega x - ikz - \alpha x} \qquad [6]$$



Figure 7 Surface waves can be classified into two polarizations. (a) A TM wave, shown on a metal surface; (b) A TE wave, shown on a textured surface. TM waves consist of electric charges on the metal surface that oscillate along the direction of propagation. They have nonzero electric field components both perpendicular to the surface, and parallel to the direction of propagation. TE waves are associated with transverse currents in the surface. They are similar to TM waves, but with the electric and magnetic fields exchanged.

for $X > 0$ and

$$E_2 = (\hat{x}E_{2x} + \hat{z}E_{2z})e^{i\omega x - ikz + \gamma x} \qquad [7]$$

for $X < 0$, where α and γ are the attenuation constants into free space and dielectric, respectively. The fields of such a wave are shown in Figure 7. We can solve the wave equation for the electric field:

$$\nabla \times \nabla \times \vec{E} = \varepsilon_r \frac{\omega^2}{c^2} \frac{\partial^2 \vec{E}}{\partial t^2} \qquad [8]$$

by matching E_x and $\varepsilon_r E_z$, at the interface to yield

$$k = \sqrt{\frac{\varepsilon}{1+\varepsilon}} \frac{\omega}{c} \qquad [9]$$

$$\alpha = \sqrt{\frac{-1}{1+\varepsilon}} \frac{\omega}{c} \qquad [10]$$

$$\gamma = \sqrt{\frac{-\varepsilon^2}{1+\varepsilon}} \frac{\omega}{c} \qquad [11]$$

A solution for transverse electric (TE) waves, where $H_y = 0$, can be found by applying the principle of duality, by exchanging the electric and magnetic fields, and substituting μ for ε.

For surface waves on a metal surface, we insert the dielectric constant of a metal, which is

$$\varepsilon = 1 - \frac{i\sigma}{\omega\varepsilon_0} \qquad [12]$$

The conductivity, λ, is

$$\sigma = \frac{nq^2\tau/m}{1 + i\omega\tau} \qquad [13]$$

where τ is the mean electron collision time, q is the electron charge, m and n are the effective mass and the density, respectively, of the conduction electrons. For frequencies much lower than $1/\tau$, which includes microwave and radio frequencies, we can substitute eqns [12] and [13] into eqn [9] to find

$$k \approx \frac{\omega}{c} \qquad [14]$$

Thus, surface waves on metals propagate at nearly the speed of light in vacuum, and they travel for many wavelengths with little attenuation. We can also solve for the decay constants into free space using eqn [10]:

$$\alpha = (1 - i)\frac{\omega}{c}\sqrt{\frac{\omega\varepsilon_0}{2\sigma}} \qquad [15]$$

and into the metal using eqn [11]:

$$\gamma \approx (1 + i)\sqrt{\frac{\omega\mu_0\sigma}{2}} = \frac{(1 + i)}{\delta} \qquad [16]$$

where δ is recognized as the skin depth. Thus, we have derived the skin depth of a metal from the penetration depth of surface waves.

From the skin depth, we can derive the impedance of a metal sheet. Assuming that E_0 is the electric field at the surface, the surface current is given by

$$J_z(x) = \sigma E_z(x) = \sigma E_0 e^{-x(1+i)/\delta} \qquad [17]$$

The magnetic field at the surface is found by integrating along a path that surrounds the surface current:

$$H_0 = \int_0^{-\infty} J_z(x)\mathrm{d}x = \frac{\sigma\delta}{1 + i}E_0 \qquad [18]$$

The surface impedance of the metal is therefore

$$Z_s = \frac{E_z}{H_y} = \frac{1 + i}{\sigma\delta} \qquad [19]$$

We can see that the resistance of a metal surface is accompanied by an equal amount of inductance, because the real and imaginary parts of the surface impedance are equal, and have the same sign.

The part of the wave that extends into vacuum is very loosely bound to the metal surface, but the currents in the metal occur in a well-defined skin depth. For example, copper has a surface impedance of $0.03(1 + i)$ ohms/square at 10 GHz. Using eqns [15] and [16], a surface wave at that frequency extends about 70 meters, or 2300 wavelengths into free space, but less than 1 micron into the metal. For this reason, surface waves are often described simply as surface currents at microwave and radio frequencies, although they are the same phenomenon as the more tightly bound surface plasmons that occur at optical frequencies. Nonetheless, their presence can be seen in a variety of phenomena at RF frequencies, such as antenna radiation patterns.

The above discussion can be generalized to a simple impedance surface, and it can be shown that TM waves are supported on inductive surfaces having an impedance of

$$Z_s(\mathrm{TM}) = \frac{i\alpha}{\omega\varepsilon} \qquad [20]$$

while TE waves are supported on capacitive surfaces, having an impedance of

$$Z_s(\mathrm{TE}) = \frac{-i\omega\mu}{\alpha} \qquad [21]$$

Thus, while ordinary metals, which are inductive, support TM waves, they do not support TE waves, which require a capacitive surface.

Surface waves on metals can be suppressed over a finite frequency band by applying various kinds of periotic textures. For example, at optical frequencies, a lattice of small bumps on a metal surface can create a surface wave bandgap. Surface waves are scattered by the bumps, and form standing waves when one-half wavelength fits between the rows of bumps. Two modes occur, in which the wave nodes lie either on the bumps or between them. These two modes have slightly different frequencies, separated by a narrow bandgap.

At microwave frequencies, more elaborate structures can be built to control the surface properties. One example is a corrugated metal surface, shown in Figure 8. The corrugations can be considered as transmission lines running into the slab, and shorted at the bottom. They are typically one-quarter wavelength deep, so that the short circuit at the bottom is transformed into an open circuit at the top. Because of these resonant structures built into the surface, it has high impedance for waves that are polarized with the electric field transverse to the corrugations, but it has low impedance for waves that are polarized in the orthogonal direction, with the electric field parallel to the metal ridges. For waves propagating transverse to or parallel to the corrugations, the surface can be described as hard or soft, respectively, by analogy to the acoustic surfaces of the same names. Both of these boundary conditions are used in antennas to control scattering properties or



Figure 8 A corrugated metal surface containing quarter-wave resonant grooves presents a soft boundary condition to waves propagating transverse to the grooves, and a hard boundary condition to waves propagating along the grooves.

Table 1 Four basic boundary conditions in electromagnetics, and the surface impedance for each polarization

Boundary condition	$Z_s(TM)$	$Z_s(TE)$
Electric conductor	0	0
Soft surface	∞	0
Hard surface	0	∞
Magnetic conductor	∞	∞

field profiles. These two surfaces, along with the electric and magnetic conductors, describe four basic boundary conditions for electromagnetics, which are summarized in Table 1. Like the soft and hard surfaces, the magnetic conductor does not exist in nature, but it can be produced artificially over a finite frequency band, using a kind of two-dimensional photonic crystal known as a high-impedance surface.

High-Impedance Surfaces

Just as three-dimensional photonic crystals forbid internal plane waves, two-dimensional photonic crystals can be designed to suppress surface waves. Like the capacitive mesh described earlier, they can be constructed with lumped circuit elements. They can be understood as corrugated surfaces, in which the resonant corrugations have been folded up into resonant LC circuits, and distributed on a two-dimensional lattice. An example of such a structure is shown in Figure 9. It can be built using printed circuit boards, in which flat metal patches are connected to a common ground plane by metal plated vias.



Figure 9 A high-impedance surface, constructed as a printed circuit board. (a) The top view shows an array of hexagonal metal patches; (b) the side view shows metal-plated vias that connect the patches to the ground plane; (c) the effective surface impedance can be modeled as a parallel resonant LC circuit.

When the plates are small compared to the wavelength, we may treat the surface as an effective medium, with a surface impedance defined by a parallel resonant LC circuit. The proximity of the neighboring metal plates provides capacitance, while the current paths, through the vias and the ground plane, provide inductance. The surface impedance is given by

$$Z_s = \frac{i\omega L}{1 - \omega^2 LC} \qquad [22]$$

and the resonance frequency is

$$\omega_0 = \frac{1}{\sqrt{LC}} \qquad [23]$$

The sheet capacitance, C, is equal to the value of the individual capacitors, multiplied by a geometrical factor that is related to their arrangement. It can be shown that for nonmagnetic materials, the sheet inductance L is equal to

$$L = \mu_0 t \qquad [24]$$

where t is the total thickness of the high-impedance surface. The surface is inductive for frequencies below resonance, and capacitive for frequencies above resonance. Near the resonance frequency, the magnitude of the surface impedance is very high ($Z_s >> \eta$, where $\eta = 377\Omega$ is the impedance of free space).

For a normally incident wave, the reflection coefficient of the surface is

$$R = \frac{Z_s - \eta}{Z_s + \eta} \qquad [25]$$

The phase $\phi = \mathrm{Im}(Ln(R))$ of the reflection coefficient is plotted as a function of frequency in Figure 10. While a low impedance surface such as a conventional electric conductor reflects with a phase shift of π, a high-impedance surface or artificial magnetic conductor reflects with a phase shift of 0. This can be used to build low-profile antennas, because radiating elements can lie very near to a high-impedance ground plane without being shorted out. For example, a thin wire antenna can be placed within a small fraction of a wavelength of the high-impedance surface, yet retain high radiation efficiency. While image currents in a metal ground plane would normally oppose the antenna current, the currents in a high-impedance ground plane reinforce the antenna current because of the opposite reflection phase. This effect occurs when the reflection phase falls between $\pi/2$ and $-\pi/2$, and the corresponding frequency range defines the practical bandwidth of a low-profile antenna on such a surface. Experimentally this bandwidth is found to be roughly equal to the surface wave bandgap, to be described later.



Figure 10 The reflection phase of a high-impedance surface crosses through 0 at the resonance frequency, where the surface appears as an artificial magnetic conductor. The reflection phase falls between $\pi/2$ and $-\pi/2$ for frequencies corresponding roughly to the edges of the surface wave bandgap.

The reflection phase properties of these materials can also be used to build unique microwave reflectors. Since the phase depends on the resonance frequency, one can vary the local resonance frequency in order to tune the reflection phase as a function of position on the surface. For example, a linear phase gradient can be used for beam steering, or a parabolic phase function can be used for focusing. The resonance frequency can be adjusted by tuning the capacitance of the individual unit cells, using varactors or mechanical motion, to build actively controlled microwave reflectors.

The other important property of these textured ground planes is their surface wave bandgap, which can be used to control the radiation pattern of antennas near the surface. We examine the surface wave properties by considering a wave that decays into free space, as in eqn [6]. From Maxwell's equations, we can obtain

$$k^2 = \mu_0 \varepsilon_0 \omega^2 + \alpha^2 \qquad [26]$$

which can be combined with eqs [20] and [21] to obtain the dispersion relations for TM and TE waves on a general impedance surface, respectively. For TM waves, which occur where $\omega < \omega_0$, we have

$$k(\mathrm{TM}) = \frac{\omega}{c}\sqrt{1 - \frac{Z_s^2}{\eta^2}} \qquad [27]$$

and for TE waves, which occur where $\omega > \omega_0$ we have

$$k(\mathrm{TE}) = \frac{\omega}{c}\sqrt{1 - \frac{\eta^2}{Z_s^2}} \qquad [28]$$

These functions describe, to first order, the dispersion of waves on a high-impedance surface. However, they do not predict the bandgap, which can only be obtained by including the effects of radiation damping.

Consider an oscillating sheet of current that sees the impedance of the textured surface on one side, and the impedance of free space on the other side. At very low, or very high frequencies, the current is shunted through the surface. Near the resonance frequency, where the surface impedance is high, power is delivered to free space through radiation damping. The half power bandwidth of this radiation is defined by the frequencies where the magnitude of the surface impedance is equal to the impedance of free space:

$$\left|\frac{i\omega L}{1-\omega^2 LC}\right| = \eta \qquad [29]$$

We solve for λ to yield the frequencies of the two bandedges:

$$\omega^2 = \frac{1}{LC} + \frac{1}{2\eta^2 C^2} \pm \frac{1}{\eta C}\sqrt{\frac{1}{LC} + \frac{1}{4\eta^2 C^2}} \qquad [30]$$

The terms in $1/\eta^2 C^2$ are typically small compared to the terms in $1/LC$, so we neglect them to obtain

$$\omega \approx \omega_0 \sqrt{1 \pm \frac{Z_0}{\eta}} \qquad [31]$$

where

$$Z_0 = \sqrt{\frac{L}{C}} \qquad [32]$$

is the characteristic impedance of the surface. For structures that are thin compared to the wavelength, the characteristic impedance is small compared to η. We can expand the square root in eqn [31], to approximate the fractional bandwidth of the radiation as

$$\frac{\Delta\omega}{\omega_0} \approx \frac{Z_0}{\eta} = \frac{\sqrt{L/C}}{\sqrt{\mu_0/\varepsilon_0}} \qquad [33]$$

Using eqn [23], this can be rearranged to obtain

$$\frac{\Delta\omega}{\omega_0} \approx t\frac{2\pi}{\lambda_0} \qquad [34]$$

where λ_0 is the free space wavelength at the resonance frequency. This defines a surface wave bandgap that is centered at the resonance frequency, between a lower-frequency TM band and a higher-frequency TE band. From eqn [34], we see that the bandwidth of a high-impedance surface, or of an antenna on that surface, is limited by its thickness with respect to its free space wavelength at resonance. The term $\lambda_0/2\pi$ is recognized as the radian length, described by Wheeler, who showed that the fractional bandwidth limit of a small resonant antenna is given by its volume with respect to a notional sphere of this radius. Equation [34] represents the equivalent bandwidth limit for a two-dimensional resonant surface.

The surface wave bandgap can be measured experimentally with a pair of small probes placed near the surface. A surface wave probe can be constructed from the end of a coaxial cable with a short section of the inner conductor exposed. Fields from the probe excite surface waves when they are placed near the surface, and the transmission magnitude between the probes can be used to analyze the surface wave band structure. For a high impedance surface, the bandgap can be seen as a range of frequencies with a significant reduction in surface wave transmission magnitude, shown in Figure 11. Within the bandgap, waves are not bound to the surface, and currents on the surface readily radiate energy into free space. The upper edge of the bandgap



Figure 11 The surface wave transmission magnitude as a function of frequency for a high-impedance surface. TM waves are supported at low frequencies, and TE waves are supported at high frequencies. Leaky TE waves, which are damped by radiation, can occur within the bandgap.



Figure 12 The dispersion diagram for surface waves on a high-impedance surface. The bandgap spans from the upper edge of the TM band, to the point where the TE band crosses the light line. Within the bandgap, electromagnetic waves are not bound to the surface. Modes to the left of the light line represent leaky waves.

is typically less abrupt than the lower edge, due to the presence of leaky TE waves.

The dispersion diagram for surface waves on a high-impedance surface is illustrated in Figure 12. The TM band begins at zero frequency, and bends over flat below the resonance frequency. The TE band begins at the resonance frequency, and slopes upward through the light line. The bandgap, which is the region where bound surface waves are not supported, extends from the upper edge of the TM band to the point where the TE band crosses the light line. This boundary, where $\omega = ck/n$, represents waves in free space propagating parallel to the surface. TE modes, that lie to the right of the light line, are bound to the surface while those that lie left of the light line lose energy to radiation damping. They are not bound to the surface, and are described as leaky waves. The approximate dispersion functions of eqns [27] and [28] are similar to the curves shown in Figure 12, but because they neglect radiation damping, they do not describe these leaky modes. Furthermore, like other photonic crystals, high-impedance surfaces also have higher-order bands and gaps that are not explained by the effective medium model.

The suppression of propagating surface modes can be used for a variety of applications, such as antennas and other microwave structures. One example is to change the radiation pattern of an antenna by covering its ground plane with a textured surface. Figure 13 shows a simple monopole antenna, along with the radiation patterns produced by the monopole when it is placed on a flat or textured ground plane. These plots show the relative magnitude of radiation from the antenna as a function of angle. TM surface currents on the finite metal ground plane form standing waves, which scatter from the edges and corners of a finite ground plane. This causes ripples in the radiation pattern as radiation from the edges interferes with the direct radiation from the antenna. Scattering of the surface currents from the ground plane edges also allows the antenna to radiate power into the backward hemisphere, which would otherwise be shadowed by the ground plane. On the high-impedance ground plane, the suppression of surface



Figure 13 (a) A monopole antenna on a ground plane, used for testing the effect of a textured surface on the radiation pattern. (b) The E-plane radiation pattern of the monopole on a flat metal ground plane shows ripples due to standing surface waves. (c) On a high-impedance ground plane, within the bandgap, surface waves are forbidden, and the radiation pattern is smooth. (d) Outside the bandgap, in the TM band, there is a high density of surface modes.

currents within the bandgap results in a smooth radiation pattern in the forward hemisphere, and very little power in the backward hemisphere. For frequencies outside the bandgap, such as within the TM band, the high density of TM modes can be seen as fine ripples in the pattern, and significant power in the backward hemisphere.

The monopole is useful for illustrating the suppression of TM surface modes, but many other antenna designs are possible. For example, the suppression of both TM and TE surface waves can be used to build patch antennas or aperture antennas with a high degree of symmetry between the *E* and *H* planes. Because these materials behave as artificial magnetic conductors, they can also be used to design a variety of thin antennas that would be impractical on conventional metal ground planes. Finally, by incorporating active elements into the surface, tunable or steerable antennas are possible.

List of Units and Nomenclature

a	lattice constant	meters
c	speed of light in vacuum	meters/second
C	capacitance	Farads
E	electric field	Volts/meter
H	magnetic field	Amps/meter
i	unit imaginary number	–
J	current density	Amps/meter^2
k	wave vector	1/meters
L	inductance	Henrys
m	effective electron mass	kilograms
n	refractive index	–
n	electron density	number/meter^3
q	electron charge	Coulombs
r	radius	meters
R	reflection coefficient	–
t	thickness	meters
T	transmission coefficient	–
Z	surface impedance	Ohms/square
α	decay constant into free space	1/meters
γ	decay constant into material	1/meters
δ	skin depth	meters
ε	electric permittivity	Farads/meter
η	impedance of free space	Ohms
λ	wavelength	meters
μ	magnetic permeability	Henrys/meter
π	diameter/circumference ratio	–
σ	electrical conductivity	1/Ohms
τ	mean electron collision time	seconds
ω	angular frequency	radians/second
∇	vector differential operator	–
∂	scalar differential operator	–
∞	infinity	–

See also

Babinet's Principle. **Diffractive Systems**: Diffractives in Animals; Microstructure Fibers; Omnidirectional Surfaces and Fibers. **Photonic Crystals:** Atomic Physics; Electromagnetic Theory; Nonlinear Optics in Photonic Crystal Fibers; Photonic Crystal Lasers, Cavities and Waveguide; Self-Assembled and Functionalized Photonic Crystals.

Further Reading

Ashcroft N and Mermin N (1976) *Solid State Physics*. Orlando, FL: Saunders College Publishing.

Brillouin L (1953) *Wave Propagation in Periodic Structures: Electric Filters and Crystal Lattices*, 2nd edn. New York: Dover Publications.

Brown E, Parker C and Yablonovitch E (1993) Radiation properties of a planar antenna on a photonic-crystal substrate. *Journal of the Optical Society of America B* 10: 404.

Collin R (1991) *Field Theory of Guided Waves*, 2nd edn. New York: IEEE Press.

Fan S, Villeneuve P and Joannopoulos J (1996) Large omnidirectional band gaps in metallodielectric photonic crystals. *Physics Review B* 54: 11245.

Feynman R, Leighton R and Sands M (1964) *The Feynman Lectures on Physics*, vol. 3. Reading, MA: Addison-Wesley.

Joannopoulos J, Meade R and Winn J (1995) *Photonic Crystals: Molding the Flow of Light*. Princeton, NJ: Princeton University Press.

Kildal P-S (1990) Artificially soft and hard surfaces in electromagnetics. *IEEE Transactions on Antennas and Propagation* 38: 1537.

Kurizki G and Haus J (eds) (1994) Photonic band structures. *Journal of Modern Optics* 41, special issue.

Lee S, Zarrillo G and Law C (1982) Simple formulas for transmission through periodic metal grids or plates. *IEEE Transactions on Antennas and Propagation* 30: 904.

Pendry J, Holden A, Stewart W and Youngs I (1996) Extremely low frequency plasmons in metallic mesostructures. *Physics Review Letters* 76: 4773.

Ramo S, Whinnery J and Van Duzer T (1984) *Fields and Waves in Communication Electronics*, 2nd edn. New York: John Wiley and Sons.

Sievenpiper D (1999) *High-Impedance Electromagnetic Surfaces*. Ph.D. Thesis, Los Angeles: University of California.

Sievenpiper D, Sickmiller M and Yablonovitch E (1996) 3D wire mesh photonic crystals. *Physics Review Letters* 76: 2480.

Sievenpiper D, Yablonovitch E, Winn J, *et al.* (1998) 3D metallo-dielectric photonic crystals with strong capacitive coupling between metallic islands. *Physics Review Letters* 80: 2829.

Sigalas M, Chan C, Ho K-M and Soukoulis C (1995) Metallic photonic band-gap materials. *Physics Review B* 52: 11744.

Smith D, Schultz S, Kroll N, et al. (1994) Experimental and theoretical results for a two-dimensional metal photonic band-gap cavity. *Applied Physics Letters* 65: 645.

Soukoulis C (ed.) (1996) Photonic band gap materials. *Proceedings of the NATO ASI on Photonic Band Gap Materials, Elounda, Crete, Greece, June 18–30, 1995.* The Netherlands: Kluwer Academic Publishers.

Wheeler H (1947) Fundamental limitations of small antennas. *Proceedings of the Institute of Radio Engineers* 35: 1479.

Yablonovitch E (1987) Inhibited spontaneous emission in solid-state physics and electronics. *Physics Review Letters* 58: 2059.

Nonlinear Optics in Photonic Crystal Fibers

J E Sharping, Cornell University, Ithaca, NY, USA

P Kumar, Northwestern University, Evanston, IL, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Photonic crystal fibers (PCFs) are very similar to normal optical fibers in that they consist of a core surrounded by cladding, such that light is guided within the core of the fiber. The primary difference between PCF and standard optical fibers is that PCFs feature an air–silica cross-section, whereas standard optical fibers have an all-glass cross-section. An electron micrograph of a typical PCF is shown in Figure 1. The air holes extend along the axis of the fiber for its entire length and the core of the fiber is formed by a defect, or missing hole, in the periodic structure. The core is formed of solid glass, whose refractive index is that of pure silica (or whatever other glass is chosen), and the cladding is formed by the air–glass mixture, whose effective refractive index depends on the ratio of air-to-glass, also known as the air-fill fraction, that comprises the structure. The resulting effective-index of the cladding will be lower compared with that of the core and, as such, will provide the refractive index variation necessary to support total internal reflection at the core-cladding boundary, and guide light in a manner similar to that of standard optical fibers. The fiber design (i.e., size, shape, and the air-fill fraction) dictates solutions to Maxwell's equations for light propagating within the fiber. Valid solutions are referred to as 'modes' which propagate along the fiber in a known manner, and have a well-defined shape in the transverse direction (i.e., they have a well-defined transverse mode structure).

Nonlinear-optical effects in fibers result from the interaction of optical fields with the glass via the $\chi^{(3)}$, or Kerr nonlinearity. The phenomenon of nonlinear refractive index is a manifestation of a light–material interaction mediated by $\chi^{(3)}$. The magnitudes of the components of the third-order susceptibility tensor in glass, $\chi^{(3)}$, are generally quite small compared with the analogous second-order ($\chi^{(2)}$) terms for materials exhibiting such nonlinearities (e.g., lithium niobate, beta-barium borate (BBO), etc.). The relatively small $\chi^{(3)}$ nonlinearity in optical fibers makes them ideal for wavelength-division multiplexed optical communication where light propagation subject to a minimum of nonlinear effects is critical. Nonlinearity does, however, eventually become an issue in wavelength-division multiplexed systems as the launched optical power increases and as the channel spacing decreases. On the other hand, one can utilize nonlinear-optical effects in soliton communication systems and to build useful photonic devices. Despite the weak $\chi^{(3)}$



Figure 1 An electron micrograph showing the periodic microstructure of a typical PCF. The core is formed by the 'missing hole' in the center of the microstructure. (Reproduced with permission from Ranka JK, Windeler RS and Stentz AJ (2000) Visible continuum generation in air-silica microstructure optical fibers with anomalous dispersion at 800 nm. *Optical Letters* 25: 25–27. ©2000 Optical Society of America, courtesy of OFS.)

nonlinearity, the net nonlinear-optical effect in fibers can be large due to the ability to tightly confine intense fields within the core of an optical fiber and maintain the interaction over a long distance as the guided fields propagate through the fiber.

The study of nonlinear-fiber optics has benefited from dramatic improvements in optical fiber and fiber-optic device fabrication. The importance of understanding nonlinear-fiber optics is driven by the need to develop fiber-integrated devices, and also by the need to understand and mitigate the problems that these nonlinearities cause in optical communication systems.

This section introduces the unique linear- and nonlinear-optical properties of PCFs in order to understand the reasons why nonlinear-optical effects are often enhanced in such fibers. These discussions pertain to PCFs which are 'highly nonlinear'. It is essential to clarify that 'highly nonlinear' in this context does not mean that the $\chi^{(3)}$ is any larger than that of standard telecommunication fibers, rather that the effect of this nonlinearity is enhanced due to the fiber's very small core.

PCF Properties

Photonic crystal fibers feature a variety of interesting properties. From the standpoint of nonlinear-fiber optics there are four very useful fundamental properties of PCFs:

- a mechanically robust optical fiber can be fabricated with an extremely small core (a few μm^2);
- a fiber can be made to guide in a single transverse mode over an extremely broad wavelength range (370 nm–1600 nm);
- there are new degrees of freedom that allow one to manipulate the fiber's group-velocity dispersion (GVD) properties; and
- many, but not all, PCFs are polarization maintaining as a result of form birefringence present in the core.

The fact that small-core PCFs can be fabricated is clear from Figure 1 by taking note of the fact that the center defect region which comprises the core is about 1.7 μm in diameter. Photonic crystal fibers with even smaller cores have been fabricated.

Transverse Mode Structure

A widely accepted model used to describe the transverse modal behavior of PCFs is called the effective-index model. The effective-index model can be used to understand why some PCFs are 'endlessly single mode', meaning that the fiber guides in a single transverse mode over an exceptionally wide wavelength range (370 nm–1600 nm). In the effective-index model, the refractive index of the core, $n_{co}(\lambda)$, is that of glass, and the refractive index of the cladding, $n_{eff}(\lambda)$, assumes a value in between that of glass and air. In the context of PCFs, one makes a modification to the standard expression describing single-mode behavior in step-index fibers:

$$V_{eff} = \frac{2\pi\Lambda}{\lambda}\sqrt{n_{co}(\lambda)^2 - n_{eff}(\lambda)^2} < V_{cutoff} \qquad [1]$$

where Λ is the spacing between air holes, λ is the wavelength of light, and V_{cutoff} is the cutoff condition for the PCF. A similar expression for the V parameter is commonly used to understand the modal behavior of standard fibers where the larger the V is, the more transverse modes are supported within the fiber. In standard fibers the cutoff condition below which only a single mode can propagate within the core of a fiber is given by $V_{cutoff} < 2.405$. In the case of PCFs, a numerical method should be used to determine V_{cutoff}. Mechanically robust PCFs can be fabricated where the dispersion in $n_{eff}(\lambda)$ (i.e., the variation of n_{eff} with λ) offsets dispersion in $n_{co}(\lambda)$ and compensates for the $2\pi\Lambda/\lambda$ coefficient in eqn [1]. Therefore, the light within the fiber propagates in a single, Gaussian-like mode because for all wavelengths $V_{eff} < V_{cutoff}$. A graph of the variation of V_{eff} with Λ/λ is shown in Figure 2, where d represents the size of an air hole.

Conceptually, the effective index model can be understood by noting that at short wavelengths the mode field is confined well within the all-silica core, but as λ increases the mode field extends further into the air–glass cladding and V_{eff} and $n_{eff}(\lambda)$ both decrease.

Dispersion in PCF

Other critical differences between PCFs and standard optical fibers lie in the dispersion properties. When light propagates through a fiber its behavior depends on the light's optical frequency:

$$E(t,z) = A(t,z)e^{i[\omega t - \beta(\omega)z]} \qquad [2]$$

Equation [2] describes the mode as it propagates through the fiber. It is decomposed into a slowly varying envelope, $A(t,z)$, and a rapidly varying exponential component where ω is the frequency of the mode, t is time, z is the position along the length of the fiber, and $\beta(\omega)$ is called the mode-propagation constant. The general term used in describing the



Figure 2 Variation of V_{eff} for different relative hole diameters d/Λ. The calculation assumes a fiber with an air–glass cross-section where the refractive index of air and glass was taken to be 1 and 1.45, respectively. The dashed line marks $V_{\text{eff}} = 2.405$, the cutoff value for a step-index fiber. (Reproduced with permission from Birks TA, Knight JC and Russell PStJ (1997) Endlessly single-mode photonic crystal fiber. *Optical Letters* 22: 961–963. ©1997 Optical Society of America.)

frequency dependence of β is chromatic dispersion, which includes contributions from the material as well as the waveguide. Other types of dispersion present in optical fibers include multi-modal (arising from multiple guided transverse modes) and polarization-mode dispersion.

One way to understand the chromatic dispersion of a mode propagating through an optical fiber is to study the Taylor series expansion of the mode-propagation constant, β, about the center frequency of the field, ω_0:

$$\beta(\omega) = \beta_0 + \beta_1(\omega - \omega_0) + \frac{1}{2}\beta_2(\omega - \omega_0)^2 + \cdots \qquad [3]$$

where $\beta_i = \mathrm{d}^i\beta/\mathrm{d}\omega^i$. The physical significance of the various β_i in eqn [3] are as follows: the phase-fronts of the electric field move at a speed given by $\omega/\beta_0 = v_p$, and the envelope, $A(t,z)$, moves at a group velocity given by $1/\beta_1$. A GVD term, which governs temporal spreading of the envelope, is given by β_2. Higher-order β terms are usually negligible for propagation of pulses of ≥1 ps duration in optical fibers and are lumped into the category of 'higher-order chromatic dispersion'.

The notation 'β_2', as defined above, is often used in the literature with dimensions of ps^2/km. However, another expression is frequently used because of its direct relationship to measured quantities. It is straightforward to measure the relative delay, T, between two pulses having different center wavelengths. Choosing a particular wavelength as a reference, one can then measure relative delay as a function of an injected pulse's center wavelength. The first derivative with respect to λ of the relative delay curve gives the GVD according to

$$D = \frac{\partial\left(\dfrac{1}{v_g}\right)}{\partial\lambda} = \frac{1}{L}\frac{\mathrm{d}T}{\mathrm{d}\lambda} = -\frac{2\pi c}{\lambda^2}\beta_2 \qquad [4]$$

where v_g is the group velocity, and L is the length of the fiber under test. The dimension commonly used for D is ps/(nm km).

Chromatic dispersion in single-mode optical fibers results from two different wavelength-dependent fiber parameters. The medium itself, glass in this case, has a wavelength-dependent refractive index. This 'material' contribution has the same magnitude regardless of the various parameters associated with the waveguide. A second contribution has to do with the design of the optical fiber. This 'waveguide' contribution to dispersion arises from the fact that the wavelength-dependent mode depends on the properties of the waveguide (i.e., the core size and refractive index contrast between the core and cladding). Empirical models can be used to describe the material, waveguide, and total GVD for standard communication fibers. Such a set of curves is given in Figure 3 where it can be seen that it is possible to have positive, negative, or zero values for D. For historical reasons, the regions where D is negative (β_2 is positive) exhibit 'normal GVD', while those where D is positive (β_2 is negative), exhibit 'anomalous GVD'. The wavelength corresponding to $D = 0$ is referred to as the zero-dispersion wavelength (λ_0), which for most silica glass fibers is about 1,300 nm.

In contrast with standard optical fibers, where the waveguide contribution to D is always less than zero, small-core PCFs can be fabricated where the waveguide contribution to GVD is positive and quite large. As such, in PCFs, λ_0 can be shifted to wavelengths shorter than the intrinsic dispersion zero of glass. Control over the GVD is essential for phase matching certain nonlinear-optical interactions involving light



Figure 3 Plots of the theoretical dispersion coefficient, D, as a function of wavelength for a standard optical communication fiber.

of different colors co-propagating within a fiber. Indeed, several exciting applications of nonlinear optics in PCF require a fiber with a $\lambda_0 \sim 800$ nm. The GVD is also of great importance when working with pulsed light in PCF, because GVD results in temporal pulse broadening. It also governs pulse temporal walkoff effects, limiting the effective interaction length between pulses of different colors. This new flexibility to manipulate the GVD curve, by varying waveguide design parameters, is a key advantage associated with using PCFs for nonlinear optics.

Birefringence in PCF

The core of an optical fiber often exhibits some amount of anisotropy. The core may be elliptical in form (shape) which leads to a phenomenon referred to as form birefringence. Since mode propagation depends on the fiber structure, a fiber with an elliptical core will exhibit mode propagation that depends on the electric field's polarization with respect to the axes of the elliptical core. As a result of birefringence, the polarization of the mode varies as it propagates through the fiber (unless care is taken to align the polarization of the injected light with respect to a principal axis of the birefringence).

Polarization-maintaining (PM) fibers are designed to include birefringence in a particular axis of the fiber. By including a well-defined birefringence throughout the length of a fiber that is larger than that induced by external perturbations, fast and slow axes of the optical fiber are created for all guided wavelengths, giving two orthogonal 'polarization modes'. If light is injected into one of the polarization modes (i.e., with its linear polarization along one of the axes) it remains linearly polarized along that axis as it propagates along the fiber. The two polarization modes generally have different group velocities, so pulsed light in each mode will take a different amount of time to propagate through a given segment of fiber. Most PCFs exhibit strong birefringence due to a slightly elliptical core combined with a large core-cladding index difference, and so they behave similarly to PM fibers. Special care must be taken when working with PCF to be sure that the polarization of the light launched into the fiber is aligned with one of the birefringent axes.

In practice, there are a few other features of PCF that are of importance when discussing nonlinear-optic interactions:

- propagation losses are generally larger in PCFs than in standard optical fibers; and
- free-space coupling and splicing are difficult and can result in large coupling losses.

Nonlinear Phenomena

The basic principles determining nonlinear effects in PCFs are the same as those for standard optical fibers (*see* **Fiber and Guided Wave Optics:** Nonlinear Effects (Basics)). It is the new flexibility in PCFs to obtain transverse-modal and GVD behavior different from that of standard optical fibers that makes PCFs truly interesting for nonlinear optics. The relevant nonlinear-optical effects are: self-phase modulation (SPM); cross-phase modulation (CPM); third-harmonic generation (3HG); four-wave mixing (FWM); Raman scattering; and Brillouin scattering.

Self-phase modulation (also known as the optical Kerr effect) refers to the self-induced phase shift experienced by an optical field as it propagates through a fiber. It becomes particularly important for the case of pulses of light propagating through optical fibers. In small core PCFs, SPM is enhanced due to the high-intensity light propagating within the core. Self-phase modulation can lead to substantial spectral broadening of pulsed light propagating along an optical fiber.

When a pulse of light experiences normal GVD (i.e., $D < 0$) as it propagates, the longer-wavelength components travel faster than the shorter-wavelength components. Anomalous GVD (i.e., $D > 0$) leads to the opposite, short-wavelength components traveling faster than the long-wavelength components. Group-velocity dispersion generally leads to temporal broadening of pulses as they propagate along a fiber. Under ideal conditions, however, SPM in combination with anomalous GVD, leads to pulses which propagate without any temporal or spectral broadening. These self-sustaining pulses are called 'optical solitons'.

When waves of light having different wavelengths co-propagate along a fiber, CPM can occur. It can be understood as a phase shift induced on one wave, due to the presence of the other wave. Cross-phase modulation also leads to spectral broadening and solitonic pulse propagation.

In 3HG and FWM, one or more photons are destroyed and others are created. In 3HG, three 'fundamental' photons are destroyed to create one with three times the energy of the fundamental photons. In FWM, two fundamental photons are destroyed while two others are created. While it is straightforward to conserve energy in 3HG and FWM, these interactions must be 'phase-matched', meaning that the interacting waves must be made to propagate in-phase over a meaningful length. Such phase-matching conditions need to be carefully considered when studying 3HG and FWM. Nevertheless, 3HG and FWM can be used to obtain frequency shifts and all-optical amplification. In comparison with other types of optical fibers, PCFs are particularly useful for 3HG and FWM applications. The small core of the PCF allows interactions to occur at much lower input powers, and the new flexibility associated with the GVD properties permits phase matching in cases which are not possible using standard optical fibers. Finally, the fiber's endlessly single-mode behavior permits very good transverse mode overlap between interacting waves having widely different center wavelengths.

Self-phase modulation, CPM, 3HG, and FWM are photon–photon interactions wherein no energy is exchanged with the medium itself. In contrast, Raman scattering and Brillouin scattering result from photon–phonon interactions. The differences between Raman and Brillouin scatterings lie in the energy of the phonons involved and the direction in which the interactions occur. Raman scattering is an interaction between a photon and an optical–phonon mode of the molecules making up the material. In the case of Raman scattering in glass, the energy shift, associated with molecular vibrational (Raman) modes, corresponds to frequencies of 1–12 THz. Raman scattering occurs in the forward and backward directions. With pulsed light, stimulated Raman scattering can occur when the lower-frequency spectrum of the pulse overlaps with the spectrum of the Raman resonances excited by the higher-frequency spectrum. When this happens, energy can be efficiently shifted in spectrum towards the peak of the Raman resonance. In the forward direction, this 'Raman self-frequency shift' builds up. Additionally, if the Raman self-frequency shift occurs in the presence of anomalous dispersion, a 'Raman soliton self-frequency shift' can result. As the injected power is increased, the spectral shift between the injected pulse and the resulting Raman soliton increases. The principal advantage associated with PCF is the ability to generate Raman solitons for a broader range of wavelengths than was previously possible.

For Brillouin scattering, interaction with the acoustical phonons results in frequency shifts of about 10 GHz and the interaction only occurs in the backward direction. Brillouin scattering is generally a nuisance in fiber-based devices, leading to intensity noise and other problems. The interesting feature of Brillouin scattering in PCFs is that the threshold intensity where problems begin to occur is higher for PCFs than for standard optical fibers. The higher threshold permits further optimization of fiber-based devices wherein Brillouin scattering limits the performance.

Experiment Examples

In the following subsections, a selection of experiments, demonstrating a few of the relevant nonlinear-optical phenomena, are briefly described.

Supercontinuum Generation

One of the most exciting demonstrations of nonlinear optics in PCF is that of supercontinuum generation. In a typical experiment, 100 femtosecond pulses from a mode-locked Ti:Sapphire laser operating at a wavelength of 800 nm were injected into the PCF. As the injected power was increased, a broad continuum of spectrum was generated from wavelengths of 400 nm up to 1,600 nm. Typical data showing the input and output optical spectra are given in Figure 4, where it can be seen that well over an octave of frequency spectrum is generated from an input pulse whose spectral width is only about 10 nm.

It is widely accepted that supercontinuum generation results from a combination of linear and nonlinear optical effects conspiring to generate the broad spectrum. As the pulse propagates through the PCF, SPM, FWM, and Raman scattering are all likely to occur with relative efficiencies depending heavily on the input pulse's spectral and temporal characteristics, as well as the fiber's properties. Indeed, efficient supercontinuum generation can occur in PCFs for pump wavelengths lying near the zero-dispersion point in the normal or anomalous dispersion regime of the PCF, and for fibers as short as a few millimeters in length.

Spectral broadening, due to SPM, is common in standard optical fibers, but what makes this



Figure 4 In supercontinuum generation one observes a broad continuum generated after short pulses of light from a Ti:Sapphire laser propagate through a 75 cm section of PCF. The spectrum of the input pulse is shown as a dashed curve, while the output is a solid curve. (Reproduced with permission from Ranka JK, Windeler RS and Strentz AJ (2000) Visible continuum generation in air-silica microstructure optical fibers with anomalous dispersion at 800 nm. *Optical Letters* 25: 25–27. ©2000 Optical Society of America.)

particular experiment interesting is the remarkable width of spectrum generated with a short piece of fiber (~1 m) and with comparatively small optical powers.

Optical Switching in PCF

Cross-phase modulation can be used to build an all-optical switch. Such a switch can be implemented as a three-port device where the output port for a given optical bit (the signal pulse), is determined by the presence of an optical control (the pump pulse). Switching can then be achieved by dividing the signal pulse equally on two arms of an interferometer and injecting the strong pump pulse only on one arm. Because the pump pulse co-propagates with only one of the two signal pulses, there exists a CPM-induced phase difference $\phi_{\text{NL}} = 2\gamma P_{\text{p}} L$ at the output of the interferometer, where P_{p} is the peak power of the pump pulse and L is the interaction length. By varying the intensity of the pump pulses one can vary the magnitude of this phase difference. If a π-phase shift is achieved, one can switch the interference from destructive to constructive, or vice-versa, thus realizing an all-optical switch.

Figure 5 shows an experimental setup used to observe switching near 1,550 nm (a similar apparatus using bulk-optic rather than fiber-optic components can be used to conduct experiments near 780 nm). The pump and signal are synchronous few-ps-duration pulses with a tunable wavelength separation


Signal
(1546 nm, 2.6 ps)
Pump
(1537 nm, 4.9 ps)
FPC3
FPC2
EDFA
50/50
FPC1
TBPF
BWDM
APC
POL
Detector
PBS
AL
Synchronous pump
and signal input
AL
Sagnac
loop
MF
(5.8 m)

Figure 5 Experimental setup used to demonstrate all-optical switching near 1,550 nm. (EDFA, erbium-doped fiber amplifier; BWDM, bandpass wavelength-division multiplexor; PBS, polarization beamsplitter; FPC, fiber polarization controller) (Reproduced with permission from Sharping JE, Fiorentino M, Kumar P and Windeler RS (2002) All-optical switching based on cross-phase modulation in microstructure fiber. *IEEE Photonics Technology Letters* 14: 77–79. ©2002 IEEE).



Figure 6 Switching curves (open boxes and filled circles), showing the relative power measured in each port of the switch vs. the pump peak power, for experiments conducted near (a) 1,550 nm and (b) 780 nm. The curves accompanying the data are generated from numerical solutions of coupled wave equations for CPM. (Reproduced with permission from Sharping JE, Fiorentino M, Kumar P and Windeler RS (2002) All-optical switching based on cross-phase modulation in microstructure fiber. *IEEE Photonics Technology Letters* 14: 77–79. ©2002 IEEE.)


From
Ti:Sapphire
laser
(150fs)
2ps
λ0+δλ
FPC1
L1
90/10
L2
M1
FPC2
Grating
L3
M3
M2
M4
A
2ps, λ0
Microstructure fiber
λ/2
PBS
Collimator
Optical spectrum
analyzer

Figure 7 A schematic of the experimental setup used to investigate FWM in PCFs. (Reproduced with permission from Sharping JE, Fiorentino M, Coker A, Kumar P and Windeler RS (2001) Four-wave mixing in microstructure fiber. *Optical Letters* 26: 1048–1050. ©2001 Optical Society of America.)



Figure 8 A typical FWM spectrum observed at the output of the microstructure fiber. The inset shows a spectrum where higher-order cascaded mixing is evident. (Reproduced with permission from Sharping JE, Fiorentino M, Coker A, Kumar P and Windeler RS (2001) Four-wave mixing in microstructure fiber. *Optical Letters* 26: 1048–1050. ©2001 Optical Society of America.)

of 5–15 nm. The switching characteristics for this implementation are shown in Figure 6. The apparatus has the advantage of requiring short fiber lengths, low switching powers, and allows switching of weak pulses. It demonstrates the feasibility of using nonlinear optics in PCF to perform essential functions in high-speed all-optical processing.

Parametric (Mixing) Processes

The first set of experiments with controlled FWM in a PCF achieved nondegenerate parametric gains over a 30 nm range of pump wavelengths near the λ_0 of the PCF. The experiments also confirmed the wavelength dependence of the GVD coefficient of the PCF near λ_0. Since the dispersion characteristics of these fibers can be adjusted during the fabrication process, the experiments demonstrate the potential for the use of PCFs in broadband parametric amplifiers, wavelength shifters, and other optical communication devices.

The experimental setup used to demonstrate phase-matched FWM in PCF is shown in Figure 7. The pump and the input signal are two synchronous pulsed beams having 3–5 nm wavelength separation with the center wavelength tunable over a 720–850 nm range. The maximum peak power of the pump pulses is ≃12 W. The two synchronous beams are then combined and injected into the PCF. The pump and signal's optical paths are adjusted to obtain temporal overlap in the PCF and their polarizations are aligned by fiber polarization controllers.

Figure 8 shows a typical FWM optical spectrum at the output of a 6.1 m long PCF. Here the strong pump beam and the weak signal beam have wavelengths of 753 nm and 758 nm, respectively. The spectrum shows the undepleted pump, the amplified signal, and the generated idler at 747 nm. The spectra in Figure 8 show that large gain is achievable for a pump-to-signal spacing of 5 nm. Gain values of more than 20 (13 dB) were obtained.

Conclusion

In summary, the advantages of using photonic crystal fibers for demonstrating nonlinear-fiber optical effects arise from four novel properties:

- the nonlinear coefficient is enhanced in small-core PCFs (core area of a few μm^2);
- PCFs can support a single transverse mode over an extremely broad wavelength range (370 nm–1600 nm);
- PCF design parameters allow one to manipulate the fiber's GVD properties; and
- nonlinear interactions are enhanced due to the polarization maintaining properties of PCFs which result from form birefringence present in the core.

These four properties combine to allow efficient interactions to occur in PCFs which are either inefficient or not possible at all in standard optical fibers.

See also

Optical Amplifiers: Raman, Brillouin and Parametric Amplifiers. **Photonic Crystals:** Electromagnetic Theory. **Scattering:** Raman Scattering.

Further Reading

Agrawal GP (2000) *Nonlinear Fiber Optics*, 3rd edn. San Diego, CA: Academic Press.

Birks TA, Knight JC and Russell PStJ (1997) Endlessly single-mode photonic crystal fiber. *Optical Letters* 22: 961–963.

Hansryd J, Andrekson PK, Westlund M, Li J and Hedekvist P (2002) Fiber-based optical parametric amplifiers and their applications. *IEEE Journal of Selected Topics in Quantum Electronics* 8: 506–520.

Monro TM, Richardson DJ, Broderick NGR and Bennett PJ (2000) Modeling large air fraction holey optical fibers. *Journal of Lightwave Technology* 18: 50–56.

Ranka JK, Windeler RS and Stentz AJ (2000) Visible continuum generation in air-silica microstructure optical fibers with anomalous dispersion at 800 nm. *Optical Letters* 25: 25–27.

Russell PStJ (2003) Photonic crystal fibers. *Science* 299: 358–362.

Sharping JE, Fiorentino M, Coker A, Kumar P and Windeler RS (2001) Four-wave mixing in microstructure fiber. *Optical Letters* 26: 1048–1050.

Sharping JE, Fiorentino M, Kumar P and Windeler RS (2002) All-optical switching based on cross-phase modulation in microstructure fiber. *IEEE Photonics Technology Letters* 14: 77–79.

Photonic Crystal Lasers, Cavities and Waveguides

J O'Brien and W Kuang, University of Southern California, Los Angeles, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Photonic bandstructure engineering, in which the electromagnetic dispersion relations are intentionally modified, can be accomplished by creating one-, two-, and three-dimensionally periodic dielectric materials. These periodic materials, called photonic crystals, can be used to confine and guide light. This article describes the formation of optical resonant cavities and waveguides in these materials. Most of the discussion will focus on two-dimensional photonic crystals. One-dimensionally periodic systems are treated elsewhere in this volume. This article will begin with a short review of the relevant electromagnetic properties of photonic crystals. The formation and properties of resonant cavities will follow this, and the article will conclude with waveguides formed by linear defects in two-dimensional photonic crystals.

Electromagnetics of Photonic Crystals

A two-dimensional photonic crystal consists of a dielectric material in which the dielectric constant is periodic in two dimensions. The period of these materials is on the order of a half-wavelength of the operating optical wavelength. In this section, we briefly review the electromagnetic properties of two-dimensional photonic crystals. For more details, see the article entitled **Spectroscopy:** Raman Spectroscopy in this volume.

There are five Bravais lattices in two dimensions. Most of the research on photonic crystal resonant cavities and waveguides has focused on square and triangular lattices, and in this article we will consider examples based on the triangular lattice. Since these structures are usually defined lithographically however, there is, in principle, no need to confine the investigation to naturally occurring Bravais lattices. Due to the limitations of current nanofabrication technology, much of the research has focused on photonic crystals that have a finite thickness. The important feature of photonic crystals is that the bandgaps in the electromagnetic spectrum opened up by all of the Bragg planes overlap spatially and spectrally, so that a frequency region exists in which no electromagnetic propagation is allowed. These electromagnetic bandgaps can be used to confine optical modes in very small-volume resonant cavities and in waveguides. In high-contrast dielectric systems, such as a semiconductor/air periodic system, only a few lattice periods may be necessary to confine an electromagnetic mode. In the case of finite thickness photonic crystals, this periodicity has the effect of limiting the bandgap formed to the in-plane directions and in the case of a two-dimensional photonic crystal in a high-index dielectric slab to the formation of a bandgap in the guided modes of the slab. In this case there are still radiation modes of the slab.

Consider a two-dimensional photonic crystal that is periodic in the $x-y$ plane. To start, we can consider materials that are uniform and infinitely extended in z. Electromagnetic fields propagating in the $x-y$ plane are Bloch states. These can be written as:

$$\vec{H}_{k_z,k_\parallel}(\vec{\rho},z,t) = \mathrm{e}^{\mathrm{i}(\omega t-(\vec{k}_\parallel\cdot\vec{\rho}+k_z z))}\vec{u}_{k_z,k_\parallel}(\vec{\rho}) \qquad [1]$$

where $\vec{\rho}$ labels the in-plane coordinates and $\vec{k}_\parallel$ labels the in-plane wavevectors. $\vec{u}_{k_z,k_\parallel}$ is a periodic function in the $x-y$ plane. Modes propagating in the $x-y$ plane in such a system can be classified as transverse electric (TE) waves or transverse magnetic (TM) waves. TE waves have nonzero E_x, E_y, and H_z field components, and TM waves have nonzero E_z, H_x, and H_y field components. A triangular lattice of air holes patterned into a high refractive index dielectric can be used to create a bandgap for both the guided TE and TM modes of the membrane for a range of hole radii. The TE and TM bandgaps that are formed can be over different spectral ranges, however. For laser applications this is unimportant since in practice the emission occurs from electron-hole recombination in a semiconductor quantum well, and for unstrained or compressively strained quantum well materials this emission is TE polarized. In most cases, waveguides have also been designed to work for a single optical polarization. It is generally true that a photonic lattice that consists of a connected high dielectric region is likely to exhibit a TE bandgap, while a lattice formed by disconnected high dielectric regions is more likely to exhibit a TM bandgap. The bandgap in the TE modes is formed between the first and second bands. The first band is called the dielectric band because the field at the Brillouin zone boundary is a standing wave with its intensity concentrated in the high dielectric regions. The second band is called the air band because at the Brillouin zone boundary this field is a standing wave with its intensity localized in the low dielectric regions. Over a reasonable range of lattice parameters, the bandwidth of the TE bandgap can be changed by changing *r*/*a* where *r* is the radius of the holes and *a* is the lattice constant of the triangular lattice. As *r*/*a* gets larger the dielectric band moves up in frequency. This can be thought of as being due to the fact that this mode has a decreasing effective index as *r*/*a* increases. The air band frequency increases as *r*/*a* increases. Since more of the electric field of the air band is located in the low dielectric regions than the field of the dielectric band, the air band increases in frequency with increasing *r*/*a* faster than the dielectric band and the bandgap therefore increases with increasing *r*/*a*. This trend holds in photonic crystals of finite thickness as well.

For photonic crystals of a finite thickness, the ability to simply classify modes as either TE or TM is lost. In the most simple finite thickness photonic crystals, that of a high index dielectric slab in which a two-dimensional photonic crystal has been patterned surrounded above and below by the same low index material which may be air of sapphire, or silicon dioxide, the modes can be classified as being either even or odd modes with respect to the mid-plane of the high index slab. In this mid-plane, however, modes can be classified as being either TE or TM, with each containing the same nonzero vector field components as in the infinite case. Away from this mid-plane, however, modes have in general six nonzero electromagnetic field components. The photonic bandgap that is created in this case is in the guided mode spectrum of the high index dielectric slab. There is no gap formed in the radiation modes of the slab. The radiation modes consist of modes with a ray vector that is not totally internally reflected at the high index slab/low index cladding interfaces. **Figure 1** shows the dispersion relation, plotted over the irreducible Brillouin zone, of the even modes for dielectric slab with a refractive index of 3.4 in which a two-dimensional triangular lattice of holes has been patterned. The surrounding material is air. The figure shows an electromagnetic bandgap



Figure 1 The photonic band diagram for a photonic crystal slab with a triangular lattice of air holes perforating a high-index dielectric slab. The slab, which assumes a refractive index $n = 3.4$, is suspended in the air with a thickness of $d/a = 0.6$. The air holes have radii of $r/a = 0.3$, where a is the lattice constant. Only the lowest three eigenmodes are shown in the plot.

formed between the first and the second guided modes of the slab. Radiation modes of the slab have real valued propagation vectors in the *z*-direction. These modes lie above the in-plane dispersion relation for air and exist inside the shaded region in the figure. This dividing line between the guided modes and the radiation modes is referred to as the light line.

If the upper and lower cladding layers of the high index slab are different and therefore have different indices of refraction, then the ability to classify modes as being either even or odd about the mid-plane of the slab disappears and it is possible to lose the bandgap in the guided modes altogether. In cases where the refractive index of the bottom cladding is not significantly different from that of the top cladding, such as a case where air serves as the top cladding layer and a material such as sapphire or silicon dioxide forms the bottom cladding, it is found that the even and odd modes describe the field reasonably accurately. To emphasize the approximation involved in the model, these modes are most often referred to in the literature as even-like or odd-like. Overall, there are three primary effects of having asymmetric cladding layers such as an air top cladding and sapphire bottom cladding case. These are a reduction in the effective bandgap width, an increase in the area of the radiation modes on the dispersion relation, and the loss of a rigorous bandgap in the guided modes of the slab. The first two of these effects are the most serious for device designers.

Photonic Crystal Resonant Cavities and Lasers

Photonic crystal resonant cavities can be formed at frequencies inside the bandgap or at the bandedges. Modes in the bandgap are formed as a result of a defect in the lattice. Modes at the bandedge are also sometimes used because the fields with wavevectors at Brillouin zone boundary are standing waves. These standing waves are analogous to the resonant modes that are formed in distributed feedback (DFB) laser structures. Here we will focus on modes confined in the bandgap. Allowed modes in electromagnetic bandgaps in photonic crystal slabs can be introduced by introducing one or more defects into the lattice. By perturbing a single lattice site, we can permit a localized mode or modes that have a frequency in the gap. This phenomenon is similar to the formation of deep levels in an electronic bandgap of a solid due to impurities and identical to the formation of resonant modes in vertical cavity surface emitting lasers (VCSELs) and phase-shifted DFB lasers. In each of these last cases, a defect in the periodicity of a precise thickness occurs between two one-dimensional distributed Bragg reflectors. Defect modes in photonic crystal resonant cavities can be engineered to radiate in a particular direction by trading-off the in-plane versus out-of-plane losses, and the resonant frequency is determined by the parameters of the lattice. Very small mode optical mode volumes can also be obtained in these resonant cavities leading to the possibility of modifying spontaneous emission.

Simple models exist which illustrate the formation of localized modes inside the bandgap as a result of defects in the otherwise periodic lattice. One of these was applied to the formation of deep levels in solids. This model can also be applied to the electromagnetics of defects in periodic structure. For a simple one-dimensional case, assuming that the defect exists at a single unit cell and that the dispersion of the band is dominated by nearest neighbor interactions, this can be solved exactly. Figure 2 shows the allowed frequencies of a ten unit cell chain with a single defect located at the center unit cell. Notice that one mode, called a donor mode, drops out of the band for positive values of $\Delta\varepsilon$ and one mode, called an acceptor mode, rises out of the band for negative values of $\Delta\varepsilon$. This is true in general. A perturbation of the lattice in which the defect has a higher index than the unperturbed lattice will cause a mode to drop out of the air band while a perturbation that has a lower dielectric constant than the background lattice will cause a mode to rise into the bandgap out of the dielectric band. In practice, resonant modes and frequencies in photonic crystals are modeled numerically.

A great deal of variety exists in resonant modes formed by defects in two-dimensional photonic crystal slabs. The simplest examples consist of a single missing hole in a two-dimensional square or



Figure 2 A one-dimensional Slater–Koster model for a single defect in a 10-unit-cell chain, showing the allowed states as a function of the defect perturbation.

triangular lattice patterned into a high-index dielectric slab. However, the resonant mode size, shape, frequency, and polarization can be engineered by tailoring the local dielectric in the region of the resonant mode. Losses in these cavities can be conceptually separated into losses in-plane through the photonic crystal and radiation losses out-of-plane. The in-plane losses are a result of having only a finite number of lattice periods surrounding the localized mode. A finite number of periods results in a finite loss due to tunneling of the fields through the lattice. This loss can in principle be made arbitrarily small by increasing the number of lattice periods surrounding the resonant mode. For a fixed number of lattice periods, the in-plane radiation loss will be reduced as the bandwidth of the photonic bandgap is increased because the magnitude of the in-plane decay constant increases with increasing bandgap width. A resonant mode formed by a defect in a truly three-dimensional photonic crystal will have losses limited by the number of achievable lattice periods and the bandwidth of the photonic crystal bandgap.

Photonic crystal cavities formed by two-dimensional photonic crystals of finite thickness suffer from an out-of-plane radiation loss. Optical confinement in the direction perpendicular to the two-dimensional photonic crystal is due to total internal reflection of the mode that occurs in the high index photonic crystal slab surrounded by lower index materials. Out-of-plane losses are due to the presence of wavevector components in the resonant mode that lie above the light line inside the radiation cone of the cladding. Figure 3 shows the Fourier transform of the magnetic field at the mid-plane of photonic crystal slab in which the resonant mode is formed by a single missing hole in a two-dimensional triangular lattice. In this cavity geometry, a doubly degenerate pair of modes is introduced into the photonic bandgap. The figure shows the Fourier transform of the field for one mode of this double degenerate pair. The boundary of the radiation cone in the figure is marked by the solid circle. Components of the mode inside this circle are not confined to the slab and contribute to out-of-plane radiation losses. These losses can be reduced by engineering the mode so that it has a smaller overlap with the radiation cone. This can be accomplished by allowing the mode to expand in real space in directions in which the wavevectors of the mode extend into the radiation cone. This reduces the spread of the Fourier transform of the mode and reduces the overlap of the mode with the radiation cone.

Symmetry can also be used to reduce the coupling to the radiation fields of the slab. Reducing the resonant frequency of the mode can also reduce out-of-plane radiation losses. This has the effect of reducing the size of the radiation cone in *k*-space. One way to accomplish this is to reduce *r*/*a* in the photonic crystal lattice. This will generally reduce frequencies of all of the photonic crystal modes. It will also, however, generally be accompanied by a reduction in the bandwidth of the photonic bandgap which will increase the in-plane losses. As a result, care must be taken in designing photonic crystal resonant cavities. Nevertheless, in the smallest mode volume photonic crystal resonant cavities, the optical losses will generally be dominated by out-of-plane radiation loss.



Figure 3 (a) The spatial Fourier transform of the magnetic field component, Hz, of a defect cavity mode at the mid-plane of a triangular-lattice suspended membrane single-defect photonic crystal microcavity. The inner circle indicates the light cone inside which mode components radiate vertically. (b) The spatial Fourier transform of a modified defect cavity mode. The overlap of the mode with light cone has been reduced by modifying the defect cavity.

Quality factors have been predicted to exceed 100 000 in carefully designed photonic crystal resonant cavities in which the optical mode volume is on the order of a few cubic half-wavelengths in the material. Larger resonant cavities formed by introducing multiple defects in the lattice are often less well confined in the real space lattice leading to a reduction in the components overlapping the radiation cone in *k*-space and a reduction in out-of-plane radiation loss. These cavities also are much more likely to support multiple resonant modes for a given index perturbation.

In analyzing resonance modes of photonic crystal resonant cavities, one of the most important parameters is the quality factor Q of the cold cavity. Practically, a theoretical prediction of the quality factor requires the use of numerical methods and finite-difference time-domain and finite element techniques are commonly used. There are basically three numerical approaches that can be used to calculate the quality factor of the cavity modes. Two of these methods calculate the quality factor from the time domain fields while the third is a frequency domain approach. The first method is to calculate the slope of the exponential decay of the energy of a given cavity mode with time. This decay of energy from the cavity is described by $\exp(-t/t_{\mathrm{ph}})$ where t_{ph} is the photon lifetime which is related to the quality factor Q, by $Q = \omega t_{\mathrm{ph}}$. This method is most useful for relatively low Q modes where the slope of energy decay is visibly greater than zero.

Another method is to calculate the ratio of the full width at half magnitude (FWHM) of the cavity resonance in the frequency domain, $\Delta\omega$, to the center frequency, ω_0. However, distortion to the spectrum is often introduced because the numerical simulation terminates before the impulse response is fully evolved. This has the effect of viewing the true time-domain response through a rectangular window, which translates mathematically into the convolution of the true spectrum with a sinc function. This must be accounted for in the determination of the quality factor.

A third method calculates the ratio of cycle-averaged power absorbed in the boundary to the total energy in the cavity mode. This last method has the advantage of by being able to separate the radiation losses into different directions:

$$\begin{aligned} \frac{1}{Q} &= \frac{\omega P}{U} = \frac{\omega(P_\perp + P_\parallel)}{U} \\ &= \frac{1}{Q_\perp} + \frac{1}{Q_\parallel} \end{aligned} \qquad [2]$$

in which, the effective vertical quality factor $Q_\perp$ is given by the ratio of power lost to the absorber at the top and bottom $P_\perp$ to the total cavity energy $U(t)$, and the effective in-plane quality factor $Q_\parallel$ is similarly given by the ratio of in-plane power loss $P_\parallel$ to the total cavity energy.

Photonic crystal lasers and resonant cavities have been demonstrated experimentally. The first demonstration of lasing in a two-dimensional photonic crystal laser occurred in a cavity formed by a single defect in a triangular lattice that was patterned into an InGaAsP membrane. The laser operated under optically pumped conditions at 143 K. Room temperature pulsed operation of photonic crystal defect lasers was reported shortly thereafter. Figure 4 shows an electron micrograph of such a resonant cavity. In the figure, the resonant cavity is formed in a suspended membrane in which a triangular lattice photonic crystal with a defect has been patterned. The fabrication of these devices involves pattern definition by electron beam lithography and pattern transfer by a series of wet and dry etching steps. The observed quality factors are, of course, sensitive to fabrication imperfections. Many other cavity designs and demonstrations have also been reported.

To operate a photonic crystal laser continuously at room temperature, it is necessary to design a high-Q resonant cavity that dissipates heat well. Poor heat dissipation is a major drawback of suspended membrane resonant cavities. One strategy for improving the heat dissipation in photonic crystal laser cavities is to form the two-dimensional photonic crystal membrane cavity on top of a low-index high-thermal-conductivity substrate. Figure 5 shows an electron micrograph of a photonic crystal cavity formed by leaving out 37 holes from a triangular lattice patterned into an InGaAsP membrane. This membrane is bonded to a sapphire substrate, which facilitates heat dissipation. This cavity is capable of room temperature continuous wave operation.

It is believed that these lasers are capable of electrically-pumped room temperature operation. This is based on the fact that large quality factors have been demonstrated in optically-pumped photonic crystal lasers and some quality factor reduction due to free carrier absorption and absorption at metal contacts can be tolerated and still lead to lasing. A reasonable assumption would be that the



Figure 4 The scanning electron micrograph of a triangular-lattice suspended membrane photonic crystal single defect cavity.



Figure 5 The scanning electron micrograph of a triangular-lattice, 37-missing-hole, photonic crystal defect cavity, bonded on sapphire which serves as lower cladding to improve heat dissipation. CW operation of the laser cavity was demonstrated.

performance of these electrically-pumped photonic crystal lasers would have much in common with the performance of VCSELs. Both VCSELs and photonic crystal cavities have small mode volumes with the cavity formed in some directions by distributed Bragg reflection. The emission direction of photonic crystal lasers can be engineered to be vertical or in-plane, but the basic resonant cavities do have important similarities. The free carrier absorption loss in photonic crystal laser cavities may be expected to be larger than in VCSELs since a photonic crystal laser mode lacks the standing wave behavior in the vertical direction that allows doping at the nodes of the standing wave to reduce the absorption loss. If free carrier absorption loss leads to larger internal losses for photonic crystal lasers than for VCSELs, then some reduction in the achievable slope efficiencies will also occur for photonic crystal lasers.

Photonic Crystal Waveguides

Another important optical element for integrated photonic circuitry is a linear waveguide. Conventional dielectric waveguides confine propagating beams by an index of refraction difference between the waveguide core and the waveguide cladding. Photonic crystal waveguides are most often formed by a linear defect, which consists of a row of modified unit cells of the lattice, patterned into a high index dielectric membrane. The guiding in this case is due to a mixture of total internal reflection at the high index membrane/low index cladding interfaces and distributed reflections from the photonic crystal in-plane. Because this confinement does not exclusively dependent on total internal reflection, the transmission loss through small bending radius waveguide branches and bends can be made very small. Predictions and experimental demonstrations exist which show that photonic crystal waveguides are capable of supporting small bending radius waveguide bends with almost total transmission. This makes photonic crystal waveguides a candidate for waveguides in densely integrated photonic circuits.



Figure 6 (a) The top view of a triangular lattice photonic crystal single-line defect waveguide with air hole radius $r/a = 0.3$. (b) The 2D spatial Fourier transform of the waveguide dielectric distribution. (c) The photonic band diagram for a suspended membrane single-line photonic crystal waveguide. The membrane has a refractive index of $n = 3.4$ and its thickness is $d/a = 0.6$. The surrounding material is air. The light gray and dark gray area indicate the regimes where field radiates through the air and photonic crystals, respectively.

Figure 6a shows an illustration of the top view of a two-dimensional photonic crystal waveguide.

This is a triangular lattice in which one row of unit cells has been modified. Shown in Figure 6b is the Fourier transform of index of refraction for the situation in which the photonic crystal consists of low index holes in a high index semiconductor. The presence of the linear defects modifies and broadens the reciprocal lattice from a simple reciprocal triangular lattice, before the creation of linear defect, to the distribution shown in the figure. This Fourier transform has components along the direction of propagation at $(\vec{b}_1 - \vec{b}_2)/2$ as shown in the figure where $\vec{b}_1$ and $\vec{b}_2$ are reciprocal lattice unit vectors. These reciprocal lattice components at $(\vec{b}_1 - \vec{b}_2)/2$ couple a planewave with wavevector β to other planewaves with wavevectors $\beta \pm (\vec{b}_1 - \vec{b}_2)/2$. The result of this coupling is that the electric field of the waveguide mode is a Bloch wave. In a photonic crystal waveguide in which the waveguide axis is the z-direction, the Bloch wavefield in the waveguide can be written in the form:

$$\vec{E}(x,y,z,t) = \sum_n c_n \vec{f}_\beta(x,z) \times \exp\left[\mathrm{i}\left(\omega t - \left[\beta + n\left(\frac{\vec{b}_1 - \vec{b}_2}{2} \right) \right] y \right) \right] \qquad [3]$$

In this expression the periodic function of the Bloch wave has been explicitly expanded as a Fourier series and each term in the Fourier series is called a spatial harmonic. Note that these fields differ from that of a photonic crystal fiber because the cladding of a photonic crystal waveguide has a periodicity along the direction of a waveguide. A photonic crystal fiber does not.

Most of the realizations of photonic crystal waveguides occur in two-dimensional photonic crystals formed in high index dielectric slabs. The membrane is usually located a few microns above a high index substrate. Because the fields of the guided modes decay exponentially outside the membrane, the effect of a substrate several microns away is very nearly negligible. The photonic band structure for $r/a = 0.3$, normalized membrane thickness $d/a = 0.6$ and refractive index of $n = 3.4$ is shown in Figure 6c. Only the modes with even symmetry along the mid-plane of the membrane are shown. A bandgap opens for modes with odd symmetry only for large low index filling factors in the triangular lattice. Filling factors large enough to create a bandgap for the odd modes are often impractical so that the odd modes are rarely considered. The even and odd modes are orthogonal, so that plotting the dispersion relation for the even modes only is justified. In reality, even and odd modes may be weakly coupled as a result of fabrication imperfections. The horizontal axis of the dispersion relation covers the in-plane wavevector β along the propagation direction of the irreducible Brillouin zone. The vertical radiation light cone and transverse radiating region of the photonic crystal are mapped as light gray and dark gray areas, respectively. They correspond to the regimes in which light radiates through the air cladding and photonic crystal cladding, respectively. Waveguide dispersion relations can be calculated using two-dimensional approaches in which case the guiding due to the high index slab is accounted for by using an effective index of refraction for the mode. The effective index is the ratio of the propagation coefficient to the free space wavevector of the guided mode of the slab. The two-dimensional



Figure 7 The photonic band diagram for a triangular-lattice sapphire-bonded single-line photonic crystal defect waveguide. The dielectric membrane has a refractive index of $n = 3.4$ and thickness of $d/a = 1.0$. The index of the sapphire bottom cladding is assumed to be 1.6.



Figure 8 The photonic band diagram for a triangular-lattice deeply etched single-line photonic crystal defect waveguide. The top cladding, guiding membrane, and bottom cladding have an index of refraction of 3.0, 3.4, and 3.0, respectively. Their normalized thicknesses d/a are 1.0, 1.0, and 6.0, respectively.

calculation then uses the effective index of the mode as the high index of material in the photonic crystal. To obtain accurate results, the effective index for each mode calculated separately and the two-dimensional calculation of the photonic crystal waveguide dispersion must be repeated for each waveguide mode.

Examples of photonic crystal waveguide dispersion relations are shown in Figures 7 and 8 for waveguides formed by photonic crystals in dielectric slabs on high index lower cladding layers. Figure 7 is the dispersion relation for an oxide lower cladding layer. The area of the light gray region, which is the projection of the oxide cladding light cone onto waveguide propagation direction, increases as a result of higher index of refraction. Figure 8 shows the dispersion relation for a waveguide with an even larger lower cladding index. In this case the air holes of the two-dimensional photonic crystal are patterned all the



Figure 9 The out-of-plane radiation loss as a function of normalized frequency for the photonic crystal defect slab waveguides illustrated in Figures 6–8. The lattice constant $a = 450$ nm for deeply etched waveguide and 420 nm for the rest of the cases. Points are calculated values and lines are B-spline curve fits.

Table 1 Photonic crystal defect slab waveguides considered in the calculations

Waveguide structures	*Suspended membrane*		*Oxidized lower cladding*		*Deeply etched*
	Deep undercut	*Shallow undercut*	*Thin oxide*	*Thick oxide*	
Layer description: Material (normalized thickness *d*/*a*)	Air (>3.0)				
	–	–	–	–	AlGaAs (1.0)
	GaAs (0.6)	GaAs (0.6)	GaAs (0.6)	GaAs (0.6)	GaAs (1.0)
	Air (3.0)	Air (1.0)	Al_xO_y (2.0)	Al_xO_y (5.0)	AlGaAs (6.0)
			GaAs substrate (>3.0)		

Refractive index of 3.4 is assumed for GaAs, 3.0 for AlGaAs, 1.6 for Al_xO_y, and 1.0 for air.



Figure 10 The scanning electron micrograph of a photonic crystal Y-branch fabricated on InP material system.

way through the lower cladding layer, with an index of 3.0, on a high index substrate. The defect modes lying within the in-plane photonic bandgap are all above the cladding light line in this case. Propagation losses are predicted to increase by over two orders of magnitude from the structure with very low index cladding layers shown in Figure 6 to the high index lower cladding structure of Figure 8.

Figure 9a and b shows the results of a fully three-dimensional calculation for the propagation loss of the three structure shown in Figures 6–8. The details of these structures are shown in Table 1. This calculated loss is due to coupling between the guided mode and the radiation modes of the high index substrate. A wavelength scale is also included using $a = 420$ nm in Figure 9a and 450 nm in Figure 9b. The suspended membrane suffers the least vertical radiation loss among all of the waveguides considered and has a minimum loss around 0.2 cm^{-1}. Low-loss waveguides formed on high index cladding layers may be possible, but care should be taken to eliminate coupling between the guided modes and the radiation modes of the cladding. In this case, the design strategy for reducing the optical loss is to reduce the magnitude of the Fourier component of the electromagnetic field inside the light cone. It should also be noted that deeply-etched waveguides formed by removing multiple rows of holes have been demonstrated with significantly lower radiation loss than is predicted for the single line defect waveguides. However, these waveguides are multi-moded at all frequencies. It is also important to remember that the nanofabricated waveguides will suffer additional losses due to fabrication imperfections that were not included in the numerical model. Figure 10 shows a nanofabricated photonic crystal waveguide. The image is an electron micrograph of a y-branch component of a Mach–Zehnder interferometer formed in a two-dimensional photonic crystal waveguide patterned into a suspended InGaAsP membrane.

Finally, it is worth noting that the group velocity of photonic crystal waveguide modes, where the group velocity is given by the gradient of the dispersion surface:

$$v_g = \nabla_{\vec{\beta}} \omega \qquad [4]$$

is very small near the zone boundary. This can be seen from the dispersion relations shown in Figures 6–8. In fact, the slope of the dispersion relations is likely to be a parameter which can be engineered by careful waveguide design. This property may allow photonic crystal waveguides to find applications in optical processing functions such as delay lines.

See also

Photonic Crystals: Atomic Physics; Electromagnetic Theory.

Further Reading

Baba T (1997) Photonic crystals and microdisk cavities based on GaInAsP–InP system. *IEEE Journal of Selected Topics in Quantum Electronics* 3: 808–830.

Joannopoulos JD, Meade RD and Winn JD (1995) *Photonic Crystals: Molding the Flow of Light*. Princeton: Princeton University Press.

Mekis A, Chen JC, Kurland I, Fan S, Villeneuve PR and Joannopalos JD (1996) High transmission through sharp bends in photonic crystal waveguides. *Physics Review Letters* 77: 3787–3790.

Painter O, Lee RK, Yariv A, *et al.* (1999) Two-dimensional photonic crystal defect laser. *Science* 284: 1819–1821.

Sakoda K (2001) *Optical Properties of Photonic Crystals*. New York: Springer.

Slater JC (1967). *Insulators, Semiconductors, and Metals, Vol. 3*. New York: McGraw-Hill Book Company.

Srinivasan K and Painter O (2002) Momentum space design of high-Q photonic crystal optical cavities. *Optics Express* 10: 670–684.

Villeneuve PR, Fan S and Joannopoulos JD (1996) Microcavities in photonic crystals: mode symmetry, tenability, and coupling efficiency. *Physics Review B* 54: 7837–7842.

Yariv A and Yeh P (1984) *Optical Waves in Crystals: Propagation and Control of Laser Radiation*. New York: John Wiley & Sons.

Self-Assembled and Functionalized Photonic Crystals

S Bhandarkar, Alfred University, Alfred, NY, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Photonic crystals mimic the role of the atomic structure of a semiconductor in manipulating electrons, in this case for light. Hence, called semiconductors of light, these crystals are not generally found in nature and have to be designed and fabricated. Research and development in this field is taking place at a feverish pace to both understand the various nuances of this concept, as well as to evolve new methods to fabricate such crystals in the laboratory and ultimately on a commercial scale. The driving force behind this is the tremendous potential of these systems. They promise to revolutionize the way light can be used for future devices: from forming perfect, omnidirectional mirrors to the smallest ever lasers, and ultimately, complex optical chips with a wide range of functionality arranged in three-dimensional (3D) circuits.

This article seeks to elaborate on a specific technique to make photonic crystals called colloidal self assembly. Here, we will review the fundamental concepts underlying photonic crystals and see how the above process can lead to a versatile platform in making such systems. We will discuss the basic aspects of this method and look at the various innovative manifestations that have been used to fabricate many types of photonic bandgap materials.

Photonic Bandgap

A key attribute of a semiconductor is the formation of a bandgap, a band of energy states that the electrons cannot acquire. They may exist in the so-called valence band where their energy levels are less than that of the bandgap. Or they may be energized to states above the bandgap, i.e., to the conduction band, but the bandgap is the forbidden region. The continuous band of states that constitutes this bandgap is a result of the long-range order imposed by the crystal structure of the semiconductor, where the atomic lattice presents a periodic potential to a propagating electron. The tremendous usefulness of semiconductors comes from their ability to perform switching and logic functions, which in turn is a result of controlling the availability of electrons above and below the bandgap.

The propagation of light as an electromagnetic wave is influenced by the dielectric properties of the medium. For a waveguide aligned in the z direction, the field is the sum of the two propagating transverse modes, each with the form $E(x) = \Phi(x, y)\mathrm{e}^{ik_z z}$, where $\Phi(x, y)$ is the field distribution and k_z is the propagation constant. The wave equation for the transverse mode reduces to

$$\frac{\lambda^2}{4\pi^2}\left(\frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2}\right)\Phi(x, y) + n(x, y)^2\Phi(x, y) = (\bar{n})^2\Phi(x, y) \qquad [1]$$

Here, $\bar{n}$ is referred to as the effective refractive index and is given by $\bar{n} = k_z\lambda/2\pi$.

Equation [1] has the same form as the Schrödinger equation, which describes the wave functions of quantum particles such as electrons. This equivalence helps us to understand the similarity between the attractive potential well structures that bind electrons to the wells created by a local increase in the refractive index that confines light into optical modes.

The creation of a structure with a 3D periodic change in the refractive index (Figure 1) opens a gap, due to Bragg scattering off the dielectric interfaces whereby a set of frequencies of light becomes forbidden to propagate in any direction – a photonic bandgap. To understand the formation of the



Figure 1 Schematic representation of a three-dimensional photonic crystal. The structure formed is a periodic variation in the dielectric properties of the matrix. Here, the two different dielectric regions are represented by □ and ⊞.

bandgap, one needs to consider the complex pattern of overlapping beams that results from the refractions and reflections from the numerous interfaces. This pattern is determined by the characteristics of lightwaves (wavelength and direction of travel) and those of the periodic dielectric variation (pitch and magnitude of the contrast). Thus, for a select band of wavelengths, complete cancellation through destructive interference occurs in all directions.

One way to breach this restriction is by creating a defect or a disturbance in the periodicity, which would allow localized photonic states in the gap. This defect can be a point defect to form a microcavity, or have a 1D trace that behaves as a waveguide or a planar defect. Thus, a photonic crystal with a specific defect structure can be used to manipulate light in unique ways that can be used for a variety of applications, including lasers, filters, switches, waveguides, and for 3D integrated optics circuits. These structures are also interesting because they have been predicted to exhibit enhanced optical nonlinearities.

Photonic Crystals

The lattice constant for the photonic crystal must be comparable to the wavelength of light, typically in the range of 0.5 to 2 μm. This range is three orders of magnitude greater than the lattice constants found in solids and hence photonic crystals need to be synthesized. A common example of such a structure is a diffraction grating in a waveguide, which serves as a 1D photonic crystal. There are also examples of photonics crystal structures found in nature, such as the iridescent colors seen in certain butterflies and opal gemstones. The structure of opal is a 3D photonic crystal consisting of small spherical particles of hydrated silica (SiO_2). These spheres tend to be irregular in size but in rare precious opals, they are monosized. Diffraction from these spheres leads to the remarkable colors seen in opals.

Fabrication of 3D photonic crystal structures, with two materials with sufficiently different dielectric properties, has been extensively investigated over the past several years. Given the requirement of a tightly controlled periodicity, one obvious means of doing this is to use the microlithographic patterning processes that are so well developed for very large-scale integration (VLSI). Since these are planar and not volumetric techniques, several iterations of layer-by-layer deposition, lithography, and etching are necessary. A popular second method is that of colloidal self assembly.

The Self-Assembly Technique

The term ‘self assembly’ is usually used to describe the act of spontaneous and controlled agglomeration of some basic moieties. These basic units could be molecules, supramolecules, nanoclusters, or particles. It is similar to what is seen in living systems, where organic and inorganic materials are assembled into useful configurations mediated by various proteins. Since there is no intrinsic restriction on the number of such building blocks that can spontaneously organize into periodic structures, this process is readily scalable to large dimensions, and is the main attraction of this process.

The self-assembly technique is well suited for making periodic structures such as photonic crystals. Starting with particles of the appropriately uniform size (in the range 0.5 to 2 μm), one can conceive of organizing them into a periodic 3D array. Particles, rather than molecules or nanoclusters, are the preferred starting materials for photonic crystals because their larger size provides periodicity on the length-scale of optical wavelengths. Large block copolymer molecules have also been used instead, but they are limited in their scope.

The following sections will discuss the salient details of using self assembly to form photonic crystals. The sequence of the discussion follows the path increasing process complexity. To begin, we will examine the simplest of photonic crystals made by neatly packing uniform particles called a colloidal lattice. Given the limited range of monosized particles available, such lattices are inadequate as useful photonic crystals but can be used as templates into which other materials can be incorporated. We shall discuss one particularly attractive incorporation technique, namely electrochemical deposition, in more detail. Finally, since the process is dominated by surface interactions, diverse classes of particles can be generated by simply functionalizing the particle surface. Looking ahead to the future, this is an important aspect that can vastly increase the capability of a colloidal assembly.

Formation of Colloidal Lattices

Colloidal crystallization has been studied for several decades but has received renewed attention due to both the availability of more uniform powders as well as new applications such as photonic crystals. Fine particles are unwieldy in their dry state due to high solid–gas interfacial energy and are typically dispersed in a liquid. Particle concentration is kept low to avoid agglomeration. Further stabilization of the particles may be achieved by either charging the particles' surface (electrostatic stabilization) or by adsorbing a neutral shielding molecule (steric stabilization). A preferred approach is to induce monosized spherical particles to settle into a tightly packed lattice. The settling rate, v, of particles of diameter d_p is given by the well-known Stokes equation:

$$v = \frac{d_p^2 a \Delta\rho}{18\mu} \qquad [2]$$

where a is the acceleration due to gravity (or a centrifugal field), $\Delta\rho$ is the density difference between the particle and the liquid, and μ is the viscosity of the liquid. Whereas settling is a popular means of self assembling, other methods such as centrifugation, filtering, pressing, or dip coating can be used (Figure 2). For charged particles, electrophoresis, where an electric field induces flow, is applicable.

The typical lattice types in these domains are hexagonal close-packed planes (hcp) as shown in Figure 3 or face-centered cubic (fcc) structures (Figure 4). In fcc crystals, the layer stacking follows the order ABCABC; in hcp it is ABAB. In both stacking sequences, hard spheres occupy a volume fraction of 0.7404 and can be shown to have little entropic differences. However, it is experimentally observed that the preferred ordering of spheres is the fcc close-packed arrangement, which is also the case in high-quality opals.

This method clearly has the advantage of being a simple, cost-effective platform to make 3D photonic crystals that can be readily scaled to various levels. There are no repetitive steps as would be the case in layer-wise lithographic pattering. However, there are still some outstanding challenges. The primary one is the difficulty in ensuring that the organization of the particles does not incur the formation of unwanted defects and domains. Also, introduction of intentional defects such as waveguides is not trivial, although this is being demonstrated in different laboratories. Another shortcoming is the



Figure 2 Diagram showing some of the techniques to use self assembly of spherical particles to make colloidal lattices. These include settling (a); centrifuging (b); electrophoresis (c); dip-coating (d); and filter-pressing (e).



Figure 3 The arrangement of spheres in a hexagonal closed packed (hcp) arrangement (a). The unit cell is shown in (b) whereas the stacking *abab* sequence can be seen in (c).



Figure 4 The arrangement of spheres in a face centered cubic (fcc) arrangement with spheres of radius *r* (a). The unit cell is shown in (b). The stacking follows an *abcabc* order. The *a* and *c* sites relative to spheres populating the *b* sites are seen in (c).

unavailability of uniformly sized particles of various different chemical compositions.

The formation of monosized spherical particles is a complex problem in its own right. Usually, such particles can be made from specific polymeric materials such as polystyrene or latex, whereas SiO_2 is the best-known inorganic system. These particles are not perfectly uniform but the typical deviations from the mean size of a few percent are acceptable for most applications. Given the attractiveness of photonic crystals for a wide array of applications in optics, research in this field is burgeoning and more breakthroughs are bound to come. Already first-generation photonic bandgap devices, such as fiber gratings or photonic crystal optical fiber, are commercially available.

Colloidal Lattices as Photonic Crystals

Due to the limited range of composition of the particles available, the particle-to-air refractive index contrast provided by straightforward colloidal lattices is small. This results in low diffraction efficiencies and hence colloidal lattices do not have photonic bandgap in all directions. However, these structures can then be used as templates for various additional modifications, as seen later.

On the other hand, a simple colloidal lattice can be more easily modeled. An analytical solution can be achieved for this system using dynamical diffraction theory for a low diffraction efficiency approximation. For a close-packed stacking of spheres in a fcc array, there exists a minimum in the transmission band at a wavelength λ_c which is given by the Bragg–Snell equation:

$$\lambda_c = 2d_s\sqrt{n_{\text{eff}}^2 - \sin^2\theta} \qquad [3]$$

where d_s is the d-spacing between the planes in the $\langle 111\rangle$ direction, n_{eff} is the effective refractive index of the assembly and θ is the angle between the incident beam and normal to the (111) plane. This minimum in the transmission is referred to as the primary stop-band.

Photonic crystals are characterized using a Michelson or Mach Zehnder interferometer to obtain the phase and amplitude of the transmission (or reflection) as a function of the wavelength of light (Figures 5 and 6). Ideally, the whole band structure can be calculated from these data. In addition to λ_c, the close-packed structures also exhibit a transmission threshold at a wavelength λ_t, as seen in Figure 5. Both λ_c and λ_t depend on the particle diameter and increase with particle size. In a close-packed structure,



Figure 5 The typical profiles observed from transmission measurements on a photonic crystal. The stopband wavelength (λ_c) increases with d_p, where $(d_p)_1 > (d_p)_2 > (d_p)_3$. The polarization of light is fixed at *s* or *p* polarized.



Figure 6 The typical profiles of the reflectance peaks corresponding to the transmission plot seen in **Figure 5**.



Figure 7 The transmittance profiles as a function of the angle of incidence of light of a fixed polarization. Typical values of θ would be $\theta_1 = 0$, $\theta_2 = 10°$, $\theta_3 = 30°$, $\theta_4 = 50°$, $\theta_5 = 60°$.

the lattice *d*-spacing d_s is related to the particle diameter d_p as $d_s = d_p\sqrt{2/3}$. So when the incident light is orthogonal to the structure, eqn [3] can be simplified to:

$$\lambda_c = 2\sqrt{2/3}(d_p n_{\text{eff}}) \qquad [4]$$

Thus, n_{eff} can be obtained from the slope of a plot of the stop-band wavelength λ_c as a function of the particle diameter d_p. The angular dependence of the reflectance spectra is illustrated in Figure 7. These results depend upon the polarization state of the incident light and hence need to be obtained separately for *s* and *p* polarized light.

More Complex Colloidal Lattices

While the use of SiO_2 and polymer microspheres is ubiquitous, they are optically passive materials. New methods are being developed for making uniform spherical particles from other more optically active systems. The zinc oxide (ZnO) system is one such example. The higher refractive index (~2.2) and the light emission ability of this system make it particularly interesting. Monosized particles in the size range of 100 to 600 nm can be made using a two-stage reaction method, which allows extra control over the particle formation. Other optically active systems include rare-earth doped SiO_2, dye doped PMMA spheres, or composite spheres comprised of core–shell configuration with SiO_2 or zinc sulfide (ZnS) cores and gold (Au) or SiO_2 shells, respectively.

Whereas the above discussion focuses on monosized particles, binary crystals can be made using spheres of two different sizes. The strategy here is to vary the particle size during the deposition of every alternate layer. For instance, a first layer of closely packed spheres is followed by the deposition of layers of smaller particles. The resultant crystal structure depends primarily on the concentration of the smaller particles in the dispersion. As seen in Figure 8, the second layer can vary from having three to six particles around every underlying larger particle. Thus the large-small (LS) stoichiometry of these binary crystals can be varied from LS to LS_2 to LS_3 by increasing the concentration of the smaller particles in the suspension phase. Such crystals open up interesting new avenues for complex photonic crystals.

Colloidal Lattices as Templates

By using the colloidal lattice as porous host for a second material, a greater range of photonic crystals can be synthesized. Here, the role of the colloidal array



Figure 8 Binary crystals formed using spheres of two different sizes. The large-small (LS) ratio in (a) is 1:1 whereas in (b) it is 1:2.



Figure 9 Schematic representation of the templating process using infiltration (a). Upon removal of the particles, a macroporous photonic crystal is formed (b). This is the inverted opal configuration.

is simply as a scaffolding structure. The second material to be infiltrated may be either a liquid (in the form of a dispersion, a solution, or a molten liquid) or a vapor. Both eventually deposit a solid material inside the template. Subsequent selective removal of the template yields a 3D photonic crystal in the form of an inverted opal (Figure 9). This is one of the best and most versatile means of achieving high index contrast, which is required for true photonic bandgap behavior.

It must be noted that to use self-assembled particle arrays as a template, the whole structure has to be often heat treated to confer greater mechanical strength. As assembled, the particles are normally attached by short-range Van der Waals forces and hydrogen bonding, which in the case of SiO_2 is silanol (Si–OH) mediated. Both of these are relatively weak bonds. By heating the assembly, a greater number of siloxane (Si–O) bonds can be formed which additionally strengthens and stabilizes the particulate network. This is important to retain the periodic structure of the assembly during the exposure to high stresses during the infiltration step, for instance. At temperatures around 750 °C, there is significant generation of siloxane bonds but minimal sintering so that the lattice does not change dimensions and retains its original open porosity. With latex particles, the annealing is done just above the glass transition temperature T_g of the polymer for no more than a critical period of time. Longer treatments can destroy the ordering of the spheres.

A template thus strengthened by heat treatment is now ready for infiltration. For example, a template comprised of polystyrene spheres can be infiltrated with a hydrolyzed sol of titanium alkoxide to ultimately form titania in the interstitial regions. Upon standing, the alkoxide sol gels in the interstitial regions leading to a polymeric network called a xerogel. This entire composite can then be further heated to high temperatures (>300 °C). All organics are removed by decomposition and combustion so as to leave behind a titania matrix with periodic voids (in place of the polystyrene spheres). The templating spheres may also be dissolved, rather than combusted, in solvents such as toluene. The refractive index of titania depends on the crystalline phase that results after heat treatment – anatase is ~2.5 while rutile is ~2.9. High indices can also be achieved with semiconducting materials such as selenium (Se) with an index of ~2.5 or cadmium selenide (CdSe), ~2.9. These chalcogen-derived materials have low absorption in the visible and near infrared, so they are suitable candidates.

When SiO_2 particles are used for templating, they are eventually removed by etching, typically with dilute, buffered hydrofluoric acid at low temperatures. Given the thermal and chemical stability of the SiO_2 particles, molten Se (or other low melting metals) can be used to rapidly fill the interstitial space. Vapor phase deposition has also been used to fill the porous templates. Examples include the backfilling with silicon (Si) using chemical vapor deposition (CVD), or indium phosphide (InP) using metal-organic chemical vapor deposition (MOCVD).

A variety of structured, macroporous carbon matrices has been made with remarkable optical properties. The templates are artificial opals assembled using SiO_2 microspheres, which are filled with carbon by either: (a) infiltrating with phenolic resin followed by anaerobic pyrolysis of the resin to glassy carbon; (b) CVD of graphitic carbon; and (c) growing diamond-seeded CVD graphite from a plasma. The resultant carbonaceous 'inverse opals' are highly conductive, show intense opalescence due to the ordered arrays of holes, and have a photonic bandgap in the infrared region.

Electrochemical Deposition

One particularly effective backfilling technique is electrodeposition, which has been successfully used to deposit most of the different classes of materials – semiconductors, metals, and polymers. Here, a conducting substrate serves as the appropriate electrode where deposition occurs. By placing a colloidal lattice template on this electrode, the electrochemical deposit is used to fill the interstitial voids in the template (Figure 10). This method has been successfully applied for a host of different metals such as gold (Au), nickel (Ni), platinum (Pt), and alloys such as tin–cobalt (Sn–Co). Likewise, conducting polymers can be efficiently deposited by this method. Although these polymers suffer from inherently low indices, they have favorable electro-optic properties that can be tuned by controlling the composition. In the case of II–VI semiconductors, galvanostatic or potentiostatic deposition can be used: for instance, interstitial CdSe has been deposited (Figure 10) using an acidic solution of electrolytes such as cadmium sulfate ($CdSO_4$) and selenium dioxide (SeO_2).



Figure 10 An electrochemical cell for deposition of CdSe from an electrolytic solution on a conducting electrode. The solution contains sulfuric acid (H_2SO_4), $CdSO_4$, and SeO_2. A potentiostat is used to generate the electric fields.

Electrochemically deposited structures have minimal porosity leading to densities close to bulk density. Hence, they have a higher refractive index and are generally more robust than those made by simple infiltration. Also, they exhibit little change in dimensions and a lower tendency toward cracking during the various physicochemical processes such as drying and sintering that occur en route to forming the photonic crystal. Hence, it is a preferred technique in many cases.

Functionalization

The self-assembly process, whether used directly or as a template to synthesize a photonic crystal, is dominated by surface interactions between particles starting from the organization process through to the thermal stabilization step. These interactions can be tailored by specially treating the surface of the particles with functional groups. Functionalized colloidal templates can enhance the infiltration of the high index material and its properties such as smoothness, density, or optical nonlinearity. Latex spheres can be surface functionalized with sulfate and carboxylic acid groups to increase their surface charging capability, which can lead to more robust self-organization. These spheres can also be coated with a layer of SiOH, which gives them a SiO_2-like appearance on the surface and allows them to be used in conjunction with SiO_2 microspheres. The infiltration of metal (such as Au) nanoparticles into a template crystal of SiO_2 microspheres can be significantly enhanced by functionalizing the SiO_2 surface. This can be achieved using long-chain organic molecules with polar groups on one end that bond with silanols on the SiO_2 surface and thiol groups on the other that strongly latch onto the gold nanoparticles. Simulations of light interaction with ordered three-dimensional arrays of these metallodielectric spheres, show that they are promising starting points for the construction of full photonic bandgap materials in the visible part of the optical spectrum. Also, in these systems, the plasmon resonance of the Au shell particles can be controlled over the visible and infrared region by varying the thickness of the Au shell.

The site-selective attachment ability of biological moieties can also be used effectively here by attaching them onto particle surfaces. DNA oligomers are well known to form conjugate specific bonds – adenine to thymine and guanine to cytosine. Thus particles functionalized with these oligomers can be made to organize in specific sequences that are differentiated, depending on the surface group. These particles can have variable sizes or compositions but their surface properties are controlled largely by the attached biomolecules. Likewise, the antigen–antibody attachment ability can be exploited to improve surface bonding.

Positioning Defects in Photonic Crystals

Much of the work on photonic crystals involves the making of a long-range periodic microstructure with high dielectric contrast because the underlying materials engineering aspects are very challenging. However, the usefulness of photonic crystals depends on the successful placement of defects in precise locations within the crystal. The placement of a point defect leads to a photonic microcavity and that of a line defect, a waveguide for propagation of a lightwave (Figure 11). However, there are certain unique advantages to this style of propagation, such as the possibility of bending light around sharp corners. Line defects in the form of air cores have been introduced in a photonic crystal using a combination of lithography and self assembly. First, ridges are defined in a photoresist on top of the substrate by optical lithography (Figure 12). Upon forming a colloidal lattice on top, the ridges are converted to linear voids by removing the photoresist using combustion or etching. Another technique is to infiltrate a photopolymerizable monomer into a colloidal crystal and preferentially polymerize the liquid by focusing a light beam inside the crystal. Thus the locus of the focused beam defines the waveguiding region that is formed upon removal of the unpolymerized liquid.



Figure 11 Two common defects in colloidal lattices.



Figure 12 Formation of intentional defect using a lithographic process to define an air-core. This structure can also be used as a template for backfilling a high dielectric material.

Tunable Photonic Crystals

The holy grail in many photonic devices is tunability, and photonic crystals are no exception. Given the wide spectral range that constitutes the domain of light, the ability of devices to switch or translate their performance to another wavelength through an external stimulus is indeed very attractive. The two parameters that can be externally tuned are the dielectric contrast, which would result in a change in the n_{eff} of the crystal and the periodicity of the grating. One technique to tune the former is to form an interference pattern that organizes liquid crystals dispersed in a polymer matrix into droplets to form the photonic crystal. Applying an electric field that changes the refractive index of the droplets can therefore alter the transmission spectrum of the photonic crystal.

To control the lattice parameter, the size of or the spacing between the spheres need to be varied. This concept has also been demonstrated using self-assembled hydrogel-based nanoparticles, which are made of a thermo-responsive material such as poly-*N*-isopropylacrylamide. These particles are soft and conformable and their sizes can be tuned depending on the water content of the system. This ordered matrix is in the form of a gel that can be made to swell and compress upon changing the temperature as water is exchanged between the gel and the ambient. Wavelength tunability of one nanometer has been achieved this way. Tunability has also been sought using methods such as straining the lattice. Calculations show that a 2 or 3% shear strain ought to create a 52–73% distortion of the bandgap. In one novel approach, SiO_2 or polystyrene microspheres were strongly surface charged and ordered with a less than dense packing within a poly-acrylamide



Figure 13 Tunable photonic crystal. Spherical particles are assembled in a compressible media like a hydrogel, which deforms upon applying a stress. The deformation can be used to tune the lattice parameter and hence the optical properties of the photonic crystal.

hydrogel housing (Figure 13). Due to the strong charging the arrangement tends to be body centered cubic (bcc) with the lattice spacing that depends on the concentration of the particles. When the hydrogel is deformed by applying mechanical stress, the diffraction peaks were shown to be tunable over almost the whole visible light wavelength spectrum.

Photonic crystals made from self-organized hydrogels have been used as sensors. Here, they are functionalized with chemical recognition agents that cause the gels to swell upon binding to the analyte. The resultant change in the lattice parameters causes a measurable change in the color. Specific examples include the detection of the toxic organophosphate, parathion, using acetylcholinesterase or of glucose using boronic acid and polyethylene glycol. Utilizing the same principle, even metal ions such as copper can be detected using a hydroxyquinoline-based hydrogel. These serve as a good illustration of the multifaceted potential of photonic crystals.

Summary

Photonic crystals have aroused tremendous interest with their promise to lift the field of photonics to a new level of capability. These crystals are conceptually analogous to electronic semiconductors in their function and hence are called photonic bandgap materials. The big challenge lies in synthesizing them artificially without defects. One of the few methods to synthesize these crystals is by self assembly of micron-sized building units. Self assembly leads to formation of a uniform array of monodispersed particles, typically silica or latex. This process can be further embellished by permeating a second, high-index material using the particulate assembly as a template. Useful applications of photonic crystal require them to have specifically positioned defects and tunability. These aspects, which currently constitute the state-of-the-art research in this field, promise to deliver unique devices and applications.

List of Units and Nomenclature

a	Acceleration (typically due to gravitational or applied centrifugal force)
d_p	Diameter of the particle
d_s	*d*-spacing or distance between lattice planes
E	Electric field
k_z	Propagation constant for travel in *z* direction
n	Refractive index of the medium
$\bar{n}$	Modal effective refractive index
n_{eff}	Effective refractive index of the colloidal assembly
v	Settling velocity
$\Delta\rho$	Density difference between the particle and the fluid in which it is suspended
θ	Angle between the incident beam and normal to the lattice plane in question
λ	Wavelength of the lightwave
λ_c	Stopband wavelength
λ_t	Threshold wavelength for the photonic crystal
μ	Viscosity of the suspending fluid
Φ	Electric field distribution

See also

Photonic Crystals: Atomic Physics; Electromagnetic Theory; Photonic Crystal Lasers, Cavities and Waveguide.

Further Reading

Born M and Wolf E (1981) *Principles of Optics: Electromagnetic Theory of Propagation Interference and Diffraction of Light*. Oxford, UK: Pergamon Press.

Braun PV and Wiltzius P (2002) Macroporous materials – electrochemically grown photonic crystals. *Current Opinion in Colloid and Interface Science* 7: 116–123.

Graf C and Van Blaaderen A (2002) Metallodielectric colloidal core-shell particles for photonic applications. *Langmuir* 18(2): 524–534.

Iwayama Y, Yamanaka J, Takiguchi Y, *et al.* (2003) Optically tunable gelled photonic crystal covering almost the entire visible light wavelength region. *Langmuir* 19(4): 977–980.

Joannopoulos JD, Meade RD and Winn JN (1995) *Photonic Crystals*. Princeton, NJ: Princeton University Press.

Johnson SG and Joannopoulos JD (2002) *Photonic Crystals: The Road from Theory to Practice*. Dordrecht, The Netherlands: Kluwer Academic Publishers.

Kazuaki S (2001) *Optical Properties of Photonic Crystals*. New York: Springer-Verlag.

Koenderink AF, Johnson PM, Galisteo López JF and Vos WL (2002) Three-dimensional photonic crystals as a cage for light. *Comptes Rendus Physique* 3: 67–77.

Soukoulis CM (ed.) (2001) *Photonic Crystals and Light Localization in the 21st Century*. Dordrecht, The Netherlands: Kluwer Academic Publishers.

Stein A (2001) Sphere templating methods for periodic porous solids. *Macroporous and Mesoporous Materials* 44–45: 227–239.

Velev OD and Lenhoff AM (2000) Colloidal crystals as templates for porous materials. *Current Opinion in Colloid and Interface Science* 5: 56–63.

Xia Y, Gates B, Yin Y and Lu Y (2000) Monodispersed colloidal spheres: old materials with new applications. *Advanced Materials* 12(10): 693–713.

Yablonovitch E (1987) Inhibited spontaneous emission in solid-state physics and electronics. *Physics Review Letters* 58(20): 2059–2062.

PHYSICAL APPLICATIONS OF LASERS

Contents

Free-Electron Lasers in Physics
Industrial Applications
Sum-Frequency Generation at Surfaces

Free-Electron Lasers in Physics

T Dekorsy, Forschungszentrum Rossendorf, Dresden, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The topic of this article is a survey on the main applications of free-electron lasers (FELs) in physical sciences. The merits of FELs are discussed with respect to other available laser sources. For the wavelength ranges, where FELs contributed significantly to advances in physical sciences, specific examples of the research with FELs are given.

The basic physics of FELs, their historic development, and the state of the art of these laser sources are described in detail in this Encyclopedia (*see* **Lasers:** Free Electron Lasers). The present article covers the applications of FELs in physical sciences, but excludes all phenomena involved in the physics of FELs themselves. From the application point of view, one should regard an FEL as any other laser, as a source of coherent electromagnetic radiation with high power, narrow bandwidth, and a diffraction limited beam. Thus, the radiation produced by an FEL significantly differs from that generated by synchrotrons (*see* **Incoherent Sources:** Synchrotrons). The specifications of the FEL, such as wavelength, temporal structure of the output intensity, and peak power, determine the possible applications of the laser. One might now ask, why it is worthwhile to write – and read – an article on its own devoted to the applications of FELs. The answer to this question is the uniqueness of the radiation produced by FELs, which enables certain classes of experiments and applications in specific wavelength ranges not covered by other laser sources, such as gas, solid state, or semiconductor lasers.

Since the construction and operation costs of an FEL facility are usually orders of magnitude higher than those for the equipment of a conventional laser spectroscopy laboratory, FEL facilities have been built, and are planned for the future, in different places all over the world as dedicated-user facilities. These user facilities allow researchers from universities and industry to exploit the unique properties of FEL radiation for their research and provide the basic infrastructure and support for setting up the experiments. Usually potential users apply using a standard procedure for beam time at an FEL by submitting a short proposal to the facility. The proposals are judged by a panel which distributes the available beam time to the different users. So researchers active in the field of optics should keep in mind that these facilities exist and are available to anyone who has specific needs which can be fulfilled by an FEL facility. A list of all major FEL facilities is given in Table 1.

Table 1 FEL user facilities. Facilities marked with an asterisk are under construction at the time of publication

Facility name	*Wavelength ranges*
iFEL (Osaka, Japan)	230 nm–1.2 μm 1–6 μm, 5–22 μm 20–60 μm, 50–100 μm
Duke University Free Electron Laser Laboratory (US)	193–400 nm 2–9 μm
Vanderbilt University Free Electron Laser Center (US)	2.1–9.8 μm
FELIX–FOM (Rijnhuizen, Netherlands)	4.5–250 μm
Stanford Picosecond FEL Center (US)	3–15 μm 15–65 μm
CLIO–LURE (Orsay, France)	3–90 μm
Jefferson Lab (US)	3–6.2 μm
FEL–SUT–Science University of Tokyo (Japan)	5–16 μm
UCSB Center for Terahertz Science and Technology (US)	63–338 μm 338 μm–2.5 mm
ENEA Compact FEL (Frascati, Italy)	2–3.5 mm
FELBE (Dresden, Germany)*	5–150 μm
SCSS SPring-8 Compact SASE Source (Japan)*	X-ray
Institute for Plasma Research (India)*	sub-mm
BESSY FEL (Germany)*	deep UV–X-ray
Brookhaven–NSLS SDL DUV–FEL (US)*	deep UV
University of Maryland–MIRFEL (US)*	far-infrared
University of Hawaii (US)*	UV–far-infrared
SLAC SSRL X-ray FEL–LCLS (US)*	X-ray
TESLA X-ray FEL, DESY (Germany)*	X-ray
Daresbury 4GLS (UK)*	IR, X-ray
MIT Bates Lab X-ray FEL (US)*	X-ray
INFN SPARX X-FEL (Italy)*	X-ray
Tel Aviv University (Israel)*	far-infrared
Center for Advanced Technology (India)*	far-infrared

The basic principles of an FEL are briefly summarized here, while for an in-depth description the reader is referred to the article on free electron lasers (*see* **Lasers:** Free Electron Lasers). As with any other laser, the FEL consists of a laser cavity and a gain medium. The gain media are free electrons, which travel with a velocity close to the speed of light in vacuum through a periodic array of magnets called an undulator or wiggler. The magnets are arranged in a way that the electrons feel an alternating magnetic field. Due to the Lorentz force, the electrons perform an undulating or wiggling motion perpendicular to the magnetic field, which gives rise to spontaneous electromagnetic radiation into the forward direction. The radiation, emitted in due course of the passage of the electrons through the undulator, superposes constructively. The FEL may operate in such a way that the gain from one passage of an electron bunch is high enough to produce a coherent light pulse. This regime is known as self-amplified spontaneous emission (SASE) regime which is especially desirable for short wavelength operation in the UV and X-ray region, where the manufacturing of adequate resonator optics is difficult. At longer wavelengths, a laser cavity provides the feedback for the build-up of the coherent light field. The laser starts lasing when the amplification exceeds the losses of the cavity, including the light intensity coupled out of the cavity.

One of the distinct properties of FELs, in comparison to other laser sources, is their continuous tunability. The emission wavelength of an FEL is given by the following relation (*see* **Lasers:** Free Electron Lasers):

$$\lambda = \frac{d}{2\gamma^2}\left(1 + \frac{K^2}{2}\right) \qquad [1]$$

with d the period of the magnet array, the γ-parameter is the relativistic factor related to the electron velocity u via $\gamma = 1/(1 - u^2/c^2)^{1/2}$, and the K-parameter is given by d, and the magnetic field B as $K = 0.934 \times B[\mathrm{T}] \times d[\mathrm{cm}]$. From eqn [1] it becomes obvious that the emission wavelength of the FEL can be continuously tuned via the electron energy and the magnetic field. This is in distinct contrast to other laser sources, where the emission wavelength is fixed by the energy separation of electronic levels in atoms or by the bandgap energy of semiconductors.

The main advantage of FELs concerns the high power, both average and peak, which can be obtained. In addition, an FEL provides short optical pulses due to the fact that the electron beam passing through the undulator consists of short electron bunches. The temporal width of these electron bunches can be below one picosecond (10^{-12} s), so that optical pulses in the sub-picosecond to picosecond range are obtained. These pulses are extremely adjuvant for performing nonlinear optical experiments (*see* **Spectroscopy:** Nonlinear Laser Spectroscopy) and pump-probe experiments with high temporal resolution (*see* **Chemical Applications of Lasers**: Pump and Probe Studies of Femtosecond Kinetics). Typically the optical pulses are Fourier transform limited, i.e., the product of the spectral bandwidth $\Delta\nu$ times the pulse duration $\Delta\tau$ equals a constant, which depends on the specific shape of the pulse. For a pulse of Gaussian shape in frequency and time, this so called time-bandwidth product is given as $\Delta\nu\,\Delta\tau \geq 0.441$. From this equation the minimum spectral width (temporal duration) can be calculated for a given temporal duration (spectral width) of the laser pulse. When the electron beam driving the FEL is produced by a superconducting radio frequency linear electron accelerator, the repetition rate of the pulses is in the range of some tens of MHz. The energy per optical pulse is obtained by dividing the average power of the FEL through the repetition rate. The peak power within an optical pulse is obtained by dividing the energy per pulse through the pulse duration, which can be in the picosecond to sub-picosecond range. Typical values for FELs are energies per pulse in the μJ to mJ range, pulse lengths from some 100 femtoseconds to a few picoseconds, and accordingly peak powers in the range of kW to GW. Depending on the type of electron accelerator employed, the pulse structure of an FEL may have further peculiarities. Superconducting radio-frequency accelerators provide a quasi continuous-wave (CW) train of electron pulses, thus enabling the FEL to emit a continuous optical pulse train. Electrostatic accelerators provide macropulses of electrons at some Hz repetition rates with a duration of several μs. These macropulses consist of micropulses with MHz repetition rates and picosecond or sub-picosecond duration. Hence the FEL output has the same temporal characteristics with the FEL turning on at the beginning of each macropulse.

Another important development is the synchronization of table-top short-pulse laser systems to FELs. This is accomplished by stabilizing the repetition rate of the table-top laser system via a movable intracavity mirror accurately to the repetition rate (or a higher harmonic of the FEL) of the FEL. Using a high-frequency electronic phase-locked loop, a timing jitter, down to 500 femtoseconds between the FEL pulses and those from a mode-locked titanium-sapphire laser, have been obtained. Nonlinear frequency conversion of the near-infrared pulses from the synchronized titanium-sapphire allows one to perform multi-color pump-probe measurements in a broad spectral range in combination with the FEL.

In the following, FELs will be discussed with respect to the wavelength range which they cover. For each wavelength range alternative laser sources are given and compared to FELs. It should be noted that these alternative sources evolve very rapidly and thus pose challenges on the justification of FELs in certain wavelength and power ranges. For each wavelength region selected scientific achievements obtained from experiments performed with FELs are given.

FELs in the Far Infrared Region

The far infrared region is roughly defined as the wavelength (energy) range from 20 μm to 300 μm (62 meV to 4 meV). At the long wavelength end (wavelengths larger than 220 μm) radiation can be obtained from pure electronic devices, so-called backward wave oscillators (BWO). Furthermore, optically pumped gas lasers operate at certain discrete wavelengths in this range where there exists one fundamental problem for realizing a semiconductor laser based on transitions between the conduction and the valence bands. Auger recombination, where an electron and hole combine by transferring another electron high into the conduction band, becomes increasingly important for smaller bandgaps. Recent advancements in this field are based on quantum cascade lasers, which use inter-sub-band transitions of quantum structures for achieving lasing in the wavelength range from 105 μm to 3.4 μm. Another possibility to generate coherent radiation in this wavelength range is optical rectification or difference frequency mixing of femtosecond laser pulses at near-infrared wavelengths. However, none of these sources outperform FELs in terms of peak or average power, making FELs the most important tunable laser source in this wavelength range.

In the far-infrared, several scientific opportunities exist. In condensed matter many important elementary excitations exist in this frequency range, e.g., phonon-polaritons, plasmons, polarons, and magnons. The quantum confinement in semiconductor heterostructures leads to the formation of discrete electronic levels with energy separation typically in the far-infrared. The associated radiative transitions, so-called inter-sub-band transitions, can be arbitrarily tuned by varying the materials and the dimensions of the confining potential. In surface science, intramolecular vibration of molecules adsorbed to surfaces are of large interest. They can be studied by resonant nonlinear optical experiments such as sum-difference frequency generation or second harmonic generation, giving information about the energy transfer between the molecules and the surface. In biophysics, low-frequency modes of large bio-molecules lie in the far-infrared, whose dynamics can also be studied.

Important scientific results have been obtained with FELs in the following fields, which exclude the important fields of molecular science, chemistry, biology, and medical research.

Scanning Near-Field Optical Microscopy (SNOM)

Increasing the spatial resolution is an important task in spectroscopy. Free-space focusing of a laser beam is diffraction-limited to a spot with the dimensions of the wavelength. Especially in the far-infrared region this would allow to resolve objects larger than 10 μm only. However, the imaging of elementary excitations in solid state or of collective excitation in biomolecules on a sub-μm scale, would be highly desirable. SNOM allows to circumvent the diffraction limit. Several different SNOM techniques have been introduced in recent years, most of them working with apertures smaller than the wavelength. Imaging is performed by scanning the aperture over the sample or vice versa. An evanescent electromagnetic field is present at the aperture which can couple to the specimen brought into the proximity of the aperture. Since the aperture is smaller than the wavelength, the light intensity drops by order of magnitudes. It is here that the high power available from FELs becomes advantageous. Usually, the end of a fiber is tapered and metalized, leaving a small aperture at the tip of the fiber. In the far-infrared region the problem exists in the absorption of the fiber material. Chalcogenide fibers are capable of transmitting in the 2–12 μm range, while hollow glass capillaries coated with metals inside work also at longer wavelengths. Recent approaches try to work without apertures, e.g., by coupling the light locally via a nanometer metal tip to the sample. Another interesting approach is to use the focus of visible laser light to create a small highly reflective spot on a material. By creating free-carriers with the visible laser light in the material, the reflectivity of the far-infrared light of the FEL can be strongly increased, thus a reflecting spot is created which is diffraction-limited by the wavelength of the visible light rather than that of the infrared light. The techniques described here are, of course, not limited to the far-infrared region but may also be applied successfully, for example, in the mid-infrared region.

Rabi Oscillations

Rabi oscillations are a fundamental phenomenon in a quantum mechanical two-level system driven by a light field. The light field promotes electrons from the lower to the upper state and back, depending on the duration and intensity of the light field, i.e., the population oscillates between the lower and upper state of the two-level system with the oscillation period depending on the intensity of the light field. This phenomenon has been studied extensively in atoms. In semiconductors, scattering processes strongly aggravate the observation of Rabi oscillations. By using the Santa Barbara FEL Rabi oscillations between the ground and excited state of a hydrogenic, impurities in GaAs could be observed. From the excited state of the impurity, electrons are transferred to the conduction band, thus changing the photoconductivity of the crystal, which is measured as a function of time delay. Overdamped oscillations with frequencies changing with the laser intensity could be clearly resolved.

Optical Nonlinearities in Semiconductors

An important concept of nonlinear optics is based on the nonlinear susceptibility $\chi^{(n)}$ of a material, where n denotes the order of the nonlinearity. The nonlinear susceptibility has tensorial character and determines, for example, the efficiency of second harmonic generation and difference frequency mixing ($\chi^{(2)}$), third harmonic generation, and the Kerr nonlinearity ($\chi^{(3)}$), etc. Hence the knowledge about the dispersion and the absolute value of $\chi^{(n)}$s is both of fundamental and practical importance. Due to the lack of tunable laser sources, these values are not well known in the far-infrared. Especially close to fundamental lattice resonances in the far-infrared, a strong dispersion is theoretically expected. Here FELs play an important role in the determination of these values. For example, in GaAs, the dispersion of the $\chi^{(2)}$ has been recently determined from second harmonic generation experiments below the fundamental optical phonon resonance at 8 THz, i.e., wavelengths larger than 37 μm, where a resonance enhancement at half the phonon frequency could be observed.

Relaxation Kinetics in Semiconductor Quantum Structures

The investigations of inter-sub-band transitions in semiconductor heterostructures have opened the pathway for the realization of the quantum cascade laser. In these devices, the radiative and nonradiative transition rates between different electronic quantum levels are of prime importance for a working device. The relevant time-scales have been obtained from pump-probe experiments with FELs. In semiconductor quantum dots, the strong coupling of phonons to inter-sublevel transitions could be observed and the polaron lifetime could be determined.

Bloch Oscillations in Semiconductor Superlattices

Bloch oscillations are an intriguing concept of solid state physics. When an electron experiences the force of an electric field in a periodic potential, the resulting dynamics is oscillatory in the absence of scattering events. However, since in real solid state the scattering rates are much higher than the expected oscillation period, such oscillations cannot be observed and the application of an electric field leads to a net electric current. However, in artificial semiconductor superlattices, the Bloch oscillation period can be tailored to be smaller than the scattering rate, leading to the observation of Bloch oscillations and the associated THz emission. The inverse effect of a Bloch oscillator, i.e., the generation of a photocurrent by tuning an FEL to the Bloch oscillation frequency, could be observed.

Cluster Physics

FELs can be an important tool for studying the dynamics of clusters and molecules in the gas phase by infrared resonance enhanced multiphoton ionization (IR-REMPI). In IR-REMPI, the species of interest are irradiated by pulsed, tunable IR radiation from a free electron laser. When the radiation is resonant with a vibrational mode of the molecule or cluster, the absorption of many – up to several hundred – photons can take place. When the internal energy is high enough, the thermal emission of an electron can take place. The resulting ions can be detected mass selectively in a time-of-flight mass spectrometer. Monitoring the mass specific ion yield as a function of IR wavelength then yields the IR spectrum of that species. This technique has given important information on the IR absorption spectra of interstellar dust.

FELs in the Mid-Infrared Region

This wavelength (energy) range extends from 20 μm to 2 μm (62 meV to 0.62 eV). Alternative sources in this wavelength range are nonlinear optical parametric generators and amplifiers (OPGs/OPAs) which compete against FELs in terms of peak power. However, there still exists a large number of interesting phenomena where FELs are better suited, e.g., due to their higher repetition rate in the MHz range as opposed to the kHz repetition rate of OPGs/OPAs and their higher average power exceeding several W up to kW as compared to mW for OPGs/OPAs. These high-power levels find applications in material processing and recently in surgery. Since these applications cover such a wide variety of different materials, we refer the reader to publications from users of the Jefferson Laboratories FEL and the Vanderbilt University FEL (see Table 1). The advantage of FELs in this context is that their wavelength can be tuned exactly to a resonance of the material under preparation. The following significant spectroscopic application was performed with FELs.

Vibrational Relaxation of Defects in Semiconductors

The heat dissipation in submicron electronic devices is of prime importance for the failure behavior of such devices. As the device size shrinks to the nanometer scale, atomic defects play an important role. In silicon, hydrogen passivation of defects is a standard process step in the production of metal-oxide-semiconductor electronic devices. Hence detailed knowledge about the stability and heat dissipation of hydrogen defects is very important. By employing nonlinear optical methods such as four-wave mixing or a transient bleaching technique, the vibrational lifetime of hydrogen vibrational modes in silicon (around a wavelength of 5 μm to 6 μm) could be determined and important information on the dependence of the local atomic arrangement and the vibrational lifetime could be obtained.

FELs in the Near-Infrared to the UV Region

The wavelength (energy) range from 2 μm to 200 nm (0.62 eV to 6.2 eV) is the realm of solid state lasers. Especially diode pumped solid state lasers have made tremendous improvements in terms of power and stability in the past years. Nonlinear frequency conversion of ultrashort optical pulses generated from titanium-sapphire lasers and amplifiers cover almost all of this wavelength range. Hence there is no specific need for operating FELs in this wavelength range for applications in physical sciences.

FELs in the Extended UV to X-ray Region

In the wavelength (energy) range shorter than 200 nm (larger than 6.2 eV) the availability of laser sources is very scarce. In this wavelength range, solid state lasers have the problem of the reabsorption of the laser light by the crystals' hosts. Also nonlinear frequency conversion processes are hampered by the absorption of the nonlinear crystals in this wavelength range. The generation of ultrashort pulses at the wavelength of the Cu K_α line has been obtained on the basis of amplified femtosecond titanium-sapphire pulses, thus enabling the study of the lattice vibrations in the time domain via a modulation of the X-ray diffraction. Since these sources are limited in their wavelength and output power, the development and operation of FELs in this wavelength range is truly important.

Only recently the first experimental verification of the feasibility of a SASE FEL at short wavelengths was obtained at the DESY facility. The lasing wavelength was 110 nm. Since several of these sources are presently under construction worldwide, there are as yet no experimental results published. However, the future development of short-wavelength FELs will enable new types of time-resolved experiments in atoms, solid state physics, chemistry, and biology. One prominent example is protein crystallography with X-ray pulses. The high intensity of FELs in this wavelength range should allow one to obtain a diffraction pattern of a single protein or other important bio-molecules in a single shot on a subpicosecond time-scale, i.e., before the protein is fragmented. The short-pulse duration opens the pathway to study the dynamical behavior of such structures in pump-probe experiments with solid-state lasers synchronized to the FEL. In solid state physics, such experiments could yield important insights into the dynamics of phase transitions.

Other Developments

Beyond the use of an FEL as a light source in the above described wavelength ranges, there exists the possibility of using FEL facilities in a broader way. One example is the development of a high-intensity γ-ray source which can be accomplished by Compton backscattering of FEL photons from the relativistic electrons driving the FEL. This work has been performed at a storage ring FEL (OK-4/Duke University), where 12.2 MeV γ rays were obtained by backscattering 379.4 nm free-electron laser photons from 500 MeV electrons circulating in the storage ring. The advantage of these γ rays is that they are highly monochromatic and linearly polarized, thus making them an ideal source for nuclear spectroscopy and investigations in cancer therapy.

See also

Incoherent Sources: Synchrotrons. **Lasers:** Free Electron Lasers. **Spectroscopy:** Nonlinear Laser Spectroscopy.

Further Reading

Andruszkow J, Aune B, Ayvazyan V, *et al.* (2000) First observation of self-amplified spontaneous emission in a free-electron laser at 109 nm wavelength. *Physical Review Letters* 85: 3825–3828.

Benson SV (2003) Free electron lasers push into new frontiers. *Optics and Photonics News* 14: 20–25.

Budde M, Lupke G, Chen E, *et al.* (2001) Lifetimes of hydrogen and deuterium related vibrational modes in silicon. *Physical Review Letters* 87: 145501–145503.

Cole BE, Williams JB, King BT, Sherwin MS and Stanley CR (2001) Coherent manipulation of semiconductor quantum bits with terahertz radiation. *Nature* 410: 60–62.

Colson WB, Johnson ED, Kelley MJ and Schwettman HA (2002) Putting free-electron lasers to work. *Physics Today* 55: 35–41.

Dekorsy T, Yokovlev VA, Seidel W, Helm M and Keilmann F (2003) Infrared-phonon-polariton resonance of the nonlinear susceptibility in GaAs. *Physical Review Letters* 90: 055508.

Helm M (ed.) (2000) *Long Wavelength Infrared Emitters Based on Quantum Wells and Superlattices*. Amsterdam: Gordon and Breach.

Knippels GMH, van de Pol MJ, Pellemans HPM, *et al.* (1998) Two-color facility based on a broadly tunable infrared free-electron laser and a subpicosecond-synchronized 10-fs-Ti sapphire laser. *Optical Letters* 23: 1754–1756.

Litvinenko VN, Burnham B, Emamian M, *et al.* (1997) Gamma-ray production in a storage ring free-electron laser. *Physical Review Letters* 78: 4569–4572.

Murdin BN, Knippels GMH, Vandermeer AFG, *et al.* (1994) Excite-probe determination of the intersubband lifetime in wide GaAs/AlGaAs quantum wells using a far-infrared free-electron laser. *Sem. Sci. Techn.* 9: 1554–1557.

Palanker DV, Knippels GMH, Smith TI and Schwettman HA (1998) IR microscopy with a transient photo-induced near-field probe. *Opt. Comm.* 148: 215–217.

Sauvage S, Boucaud P, Lobo RPSM, *et al.* (2002) Long polaron lifetime in InAs/GaAs self-assembled quantum dots. *Physical Review Letters* 88: 177402.

Sorokina IT and Vodopyanov KL (eds) (2003) *Solid-State Mid-Infrared Laser Sources*. Berlin: Springer.

Unterrainer K, Keay BJ, Wanke MC, *et al.* (1996) Inverse Bloch oscillator: strong terahertz-photocurrent resonances at the Bloch frequency. *Physical Review Letters* 76: 2973–2976.

von Helden G, Tielens ACGM, van Heijnsbergen D, *et al.* (2000) Titanium carbide nanocrystals in circumstellar environments. *Science* 288: 313–316.

World Wide Web Virtual Library (2004) *Free Electron Laser Research and Applications*. Available online at http://sbfel3.edu/www/UL_fel.html

Industrial Applications

I P Mercer, Imperial College of Science, Technology and Medicine, London, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Lasers are seeing increasing application in industry, driven by emerging market demand and continuing enabling advances in laser technology. Core laser technology advances are based on robustness, performance, and cost. A combination of gas and solid-state lasers currently see application across the spectrum, from the extreme ultraviolet (EUV) to the infrared (IR). Industrial applications continue to emerge across the spectrum and are being extended to the extreme ends of the spectrum at terahertz (THz) and X-ray frequencies (see Figure 1).

Where a step in level of performance is offered by a laser based tool, that is robust enough and cost-effective for industrial application, it can be anticipated that new applications and markets will emerge. For this reason, many established laser manufacturers and new entries in the 1980s and 1990s were driven in part by the exploitation of laser technology advances, as opposed to market application demand. As markets mature for lasers applied to materials processing and diagnostics, so the driver across industry is beginning to shift from being predominantly set by the capability of emerging laser technology, to a combination of laser technology drive and application demand.

Figure 2 shows the current and emerging picture of laser technologies across a core range of wavelengths and pulse durations. Current technologies are shown along with emerging technologies expected to see industrial application in this decade, opening up new applications and markets. Currently established technologies include: CO_2 gas lasers at 10 μm; excimer and KrF gas lasers emitting in the ultraviolet at 248 and 193 nm, respectively; direct diode lasers emitting in the near infrared and visible; and solid state lasers emitting in the near infrared and visible. Current technology developments are centered on extending the range of performance of both gas and solid-state lasers: gas lasers are being extended to the ultraviolet with gases such as F_2; diode lasers are being extended to the ultraviolet with materials such as nitride-based semiconductors and to the infrared with the incorporation of quantum cascade technology; and solid-state diode pumped lasers are being extended to the infrared and ultraviolet via nonlinear conversion. In essence, achievable laser parameter space is seeing continued expansion, not only in terms of pulse duration and wavelength, but also in terms of average power, pulse energy, beam quality, robustness, and cost. Laser technology has now arrived as a major driver for industrial and social change through this decade and into the next.



Figure 1 Industrial laser applications across the spectrum.

Infrared wavelengths directly stimulate nuclear motion, coupling to heat without necessary recourse to electronic excitation. Visible wavelengths couple to electronic transitions and at high laser intensities can ionize via multiphoton absorption. Ultraviolet wavelengths couple to electronic transitions and for wavelengths in the region of or below 200 nm, ultraviolet radiation can directly result in bond breaking. For materials processing applications, ultraviolet radiation can have advantages in reducing the laser threshold required for ablation, translating to reduced thermal load imparted to the material.



Figure 2 Current and emerging laser technologies across the spectrum as a function of laser pulse duration. Currently established technologies (light gray) are shown with technologies expected to emerge during this decade (dark gray).

Nuclear motions in materials cover a range of timescales of dynamics from 100 ps (0.3 cm^{-1}) to 10 fs (3000 cm^{-1}). As the laser pulse duration is reduced below 1 μs, the effects of thermal diffusion are mitigated in solids and as the pulse duration is further reduced below 100 ps, the interaction between radiation and matter is seen to adopt impulsive behavior. Reduction in pulse duration below the microsecond regime can lead to increased efficiency for material ablation combined with improved quality.

Materials Processing – Photochemical

Lithography in Semiconductor Manufacture

Laser technology's role in semiconductor and microelectronics fabrication is growing as manufacturers move towards producing smaller, more powerful devices. The overriding commercial driver for a generation has been to increase the number of integrated components per area of silicon. This has been achieved by reducing the feature size of a transistor on silicon and this trend is anticipated to remain in place through to 2010.

Features on silicon are chemically etched following lithographic exposure. To meet the increasing demand in resolution and throughput, lasers have been applied with a trend in development towards shorter (ultraviolet) wavelengths, with increasing power and reliability.

The semiconductor industry is currently in transition from 248 nm (XeCl gas) to 193 nm (ArF gas) ultraviolet (UV) pulsed laser technology to expose silicon wafers of diameter 30 cm. A typical laser power available at this time at 193 nm, is 40 W at a repetition rate of 4 kHz. To continue the reduction of feature sizes by a factor of two every four to five years, the industry is considering moving to 157 nm (F_2 gas) pulsed laser technology. As wavelengths reach the deep ultraviolet (DUV), transmission through gas is significantly reduced, requiring a move to vacuum-based systems. Associated technologies relating to translation (stepper), mask, and image relay optics also require significant advancement. A technology also being considered at this time is to image the mask to silicon through a medium with refractive index greater than unity, thereby reducing the minimum feature size afforded by diffraction theory, whilst maintaining the same laser wavelength and numerical aperture.

It is estimated that at a feature size of approximately 80 nm, the above technologies will be reaching their resolution limit. This will necessitate a switch to electron beam projection lithography or extreme ultraviolet (EUV, 13 nm) technology. Electron beam projection carries a disadvantage in terms of projected rates of wafer throughput and as such, emphasis has been placed by the industry on the current development of EUV technology. EUV radiation can be produced by laser interaction with a gaseous volume.

Computer to Plate Printing

A common advantage where lasers are replacing current technologies is to reduce the number of associated processes and thereby reduce the cost of process ownership. Computer to plate (CTP) printing involves the laser exposure of a printing plate without the use of a film intermediate. This technology is finding fast traction within the printing industry and is applicable to drum or flat bed platforms. CTP first gained serious attention in the 1990s and has since substantially advanced, with a wide range of technology suppliers (Figure 3).

Traditional methods have involved offset printing plates, imaged used traditional film, and high-power



Figure 3 Moore's Law: continuing growth in computing power, showing a doubling in the number of transistors per unit area of silicon every 2 to 2.5 years. Also shown are 110 nm dense lines on silicon (state of the art in 2002). Source: International Sematech.

UV lamps. In contrast, CTP exposes the plate directly with laser radiation. The major saving reported by users of CTP is a faster turnaround time. For color printers, CTP gives almost instant color register on the press and there is a reduced requirement to stop the press to delete dust marks and scratches, as was the case with film. As the industry sees transition to reduced press run lengths, so the importance of CTP is increasing.

Digital plates generally use a high-quality, grained, and anodized aluminum substrate, as for analog plates (see Figure 4). High tolerance electrochemical graining and anodizing ensure stable ink/water balance and good-quality printed results and translates to predictable press behavior. Multiple coatings are applied for CTP, in contrast to a single coating for offset printing, and these take the form of a photopolymer or silver halide and a thermally responsive layer.

On the press, ink and water rollers are continually rolled over the plate. The grained and anodized aluminum substrate serves as a hydrophyllic surface volume to attract water. Ink is oil based and is repelled from areas of water absorbed into the substrate, but is attracted to the hydrophobic dot material.

Silver halide is rated for runs up to 350 000, proving a popular choice for commercial and newspaper applications. It is straightforward to sensitize for a range of writing wavelengths and is the fastest to write.

Thermal plates offer high resolution, equivalent to silver halide and can be baked to enable the longest application lifetimes. Typically the plates are exposed to 830 nm radiation on the external surface of a drum. This technology has served the industry well, but has struggled to find full application in the newspaper business, due to its disadvantage in writing speed.

The most common CTP technology used for newspapers uses a photopolymer coating, which is fast to write and durable. Resolution has traditionally been limited, with Agfa, for example, rating their N91 photopolymer plate to a maximum of 175 lines per inch (LPI), whilst thermal and silver plates are able to image at 200 LPI and above. However, recent advances in shorter wavelength violet diode lasers and violet sensitive polymers have improved resolution. Launched in 2000, violet technology is seeing widespread takeup. This technology is a spinoff from the DVD industry and with laser lifetimes estimated at 10 to 20 years, cost of ownership is one of the drivers. Both silver halide and photopolymers can be sensitized to violet. Current typical laser parameters are for: silver halide, 2–3 μJ/cm^2 at 405 nm; photopolymer, 0.2 mJ/cm^2 at 488 or 532 nm; and thermal, 0.1 J/cm^2 at 830 nm.

The chemical composition of the CTP surface layers is balanced to determine the response to different laser wavelengths, as well as performance characteristics in different print applications. The plate coatings undergo a photochemical change during laser exposure. This is a critical stage since it is important that the plate surface is not under- or over-exposed.

Chemical post processing after exposure is generally required for CTP to date, with the exception of ablative CTP, to remove unexposed material. After imaging, thermal plates go through a pre-bake step, during which the system heats the plate to 130 °C (266 °F) for about 30 seconds. The energy from this



Figure 4 Three typical polymer dots of a few microns depth on an anodized aluminum substrate. Also shown is a further magnified electron microscope image of the substrate material, with the anodized layer cut away for presentation. The porous structure increases water retention. Oil-based ink is repelled from areas other than the dots. Figure courtesy of Agfa (Tony King, tony.king1@agfa.com).

heating stage completes cross-linking of polymer chains in the exposed portions of the emulsion. Chemical processing consists of processing the plate through an alkaline developer solution where the polymer that is not cross-linked washes away. Following the wash is a rinse and application of a coating. After chemical processing, some plates require baking to 200 °C (392 °F) for 35 minutes. Afterwards, the plate continues on to rinsing.

The machine tools required for these processing steps measure 30 feet long and take up to 7 minutes to process a plate after imaging. For both polymer and thermal plate processing, the temperatures are carefully controlled to prevent the aluminum substrate from deforming during the baking stages.

The effluent from thermal and other photopolymer plate processors is fairly benign and is typically directly disposed without significant environmental concern. Spent photopolymer chemistry can, however, pose problems with waste flow, it being a plastic sludge that can solidify and over time, clog plumbing systems.

Silver diffusion plate processors are relatively compact and tend to process plates in less than a minute. Environmental precautions are required with the disposal of accumulated silver particulates. Relatively simple systems are available, which neutralize the pH of the effluent and filter out silver until concentration levels are below 3 parts per million. Under these circumstances, most jurisdictions allow drain disposal.

Ablative plates do not require post processing, other than a rinse to remove residues. This is an emerging technology that has not taken hold at this time in the printing industry and requires more powerful lasers to ablate a layer from the plate. These plates use layers of ink-repellent silicon on top of an aluminum substrate to provide the non-inking portion of the plate. Variations of this technology use a laser to ablate the silicon from the substrate in the image areas of the plate, or to transfer material from a donor layer to the aluminum substrate. A weakness of this technology has been the limited durability of the plates in press. There is continuing development to produce ablative plates with other surface layers that are more durable on press.

Materials Processing – Heating

One way in which lasers can be applied to materials processing is as a directed source of heating. With material quickly raised in temperature to the point of melting and vaporization, applications lie in drilling, welding, cutting, and scintering.

The exploited characteristics of a laser source are its directionality and discrete color. Directionality enables the formation of a restricted area for heating as well as an extended working distance, whilst a discrete color enables absorption to be optimized for the material being worked. Laser technologies typical in application to materials processing through heating, range from diodes at 808 and 940 nm to flashlamp or diode pumped solid state lasers at 1 μm, and CO_2 gas lasers at 10 μm. A recent entry technology is in diode pumped fiber lasers, reaching output powers in the kilowatt regime at a wavelength of 1 μm and typically being continuous in emission or pulsed with a pulse duration in the millisecond regime.

Direct diode lasers (see Figure 5) have advantages in simplicity and robustness and with the minimum of additional assembled optical components, costs can be expected to continue to reduce, fed by Moore's law for the cost of semiconductor manufacture. Typical powers range from 1 to 10 kW and light can be fiber delivered to the work piece. A disadvantage of direct diode emission is the reduced directionality in comparison with alternative laser sources. For example, a current typical numerical aperture of emission from a diode bar array emitting a power of 60 W, is 10 and 60 degrees in directions parallel and perpendicular, respectively, to the array. These divergences can be reduced to a numerical aperture of approximately one degree with the addition of micro-optics, at a device cost increment of approximately 20%. For an array of diode bars with emitting powers in the kilowatt regime and with emitting dimensions sided 2 cm, a typical optical quality is one thousand time diffraction limited, translating to working distances are on the order of centimeters for a laser spot size at a work piece that is on the order of 1 mm.

CO_2 gas lasers and solid state lasers offer the advantage of reduced divergence and corresponding greater working distance, combined with a smaller laser spot size at the work piece for finer processing.



Figure 5 Diode bar array, with an output power exceeding 500 W. Courtesy of Rofin.

Both laser technologies can operate in the kilowatt regime, for application to sheet metal cutting and welding.

With the interaction process involving high temperatures and the ejection of material, a high-pressure gas bathes the area of illumination to remove smelt and either reduce exothermic chemical reactions, or where process acceleration is required, to utilize an assist gas to increase heating through exothermic reaction. Oxygen is typically used as an assist gas for the processing of low-alloy steels, with the process being typically known as laser flame cutting. The gas is, in general, injected coaxially with the laser beam. Laser flame cutting is used in industry for material up to 4 cm thick, albeit the width of the cut becomes significant at this thickness. Both CO_2 and Nd:YAG lasers are applied for this application, the choice of which is dependant on the cut geometry, the cycle time, and the material. Typical cutting speeds are, for example, in the region of 10 meters per minute for 1 mm, 3 meters per minute for 6 mm, and 1 meter per minute for 15 mm thick material.

In the case of high-alloy steels and aluminum, in particular, the material is bathed with an inert gas such as nitrogen or argon. The material is heated solely by the energy in the laser beam, and is typically referred to as laser fusion cutting (see Figure 6). The laser power required is higher than for laser flame cutting. Laser fusion cutting reduces oxidization to the cut edges, which is particularly important where welding is the next process step after cutting.

Laser fusion cutting is used in industry for material up to 25 mm thick, albeit the width of the cut becomes significant at this thickness.



Figure 6 Laser fusion cutting. Courtesy of Rofin.

As with laser flame cutting, both CO_2 and Nd:YAG lasers are suitable for this application, the choice of which is influenced by the geometry of the cut, the cycle time, and the material. Typical cutting speeds in steel are, for example, in the region of ~8 meters per minute for 1 mm, 4.5 meters per minute for 3 mm and 1.5 meters per minute for 8 mm thick material.

Materials Processing – Localized Heating

As a material is heated in a localized volume to the point of vaporization, so also is the surrounding material, which can melt and experience cracking or changes in phase. Such heating is mainly considered deleterious, reducing process tolerances and reducing the tensile strength of the surrounding material.

As the pulse duration is reduced for a localized laser heating source, so are the dimensions that experience heating around the interaction volume (the heat affected zone), translating to improved part quality, with the length for thermal diffusion, l_{th} given by:

$$l_{th} = \sqrt{Dt} \qquad [1]$$

where D is the thermal diffusivity and t, the time of diffusion. As the pulse duration is reduced, the pulse energy required to ablate material is also reduced, with the laser pulse energy required to raise the material temperature to the point of vaporization being proportional to the volume heated. For an example such as silver, a pulse duration of 200 fs is associated with a diffusion length of 6 nm. Extrapolating, a pulse duration of 100 ps, 100 ns, and 100 μs are associated with diffusion lengths of 0.1, 4, and 130 μm, respectively. For typical metals and dielectrics, the process quality and pulse energy threshold for ablation become decoupled from variation in pulse duration for pulse durations less than a few picoseconds. In this regime, the volume for heating is dictated more by the depth for optical absorption and further, the physical mechanism for absorption changes to that of material breakdown and multiphoton ionization (Figure 7).

Additional advantages of operating in the short-pulse regime are a sharpening of threshold to ablation, enabling the processing of features of dimension less than that of the laser spot size and an increase in the number of materials that can be processed by the same color laser source.

Given the advantages of the short-pulse regime, it should be noted that this is currently juxtaposed with the complexity and cost of the required laser sources. Solid-state laser technology is, however, advancing, significantly reducing the number of optical components required to deliver short pulses at multi-kHz



Figure 7 Pulse duration dependence of threshold damage fluence for fused silica. Reproduced with permission from Stuart BC, Feit MD, Herman S, Rubenchik AM, Shore BW and Perry MD (1996) Nanosecond-to-femtosecond laser-induced breakdown in dielectrics. *Physics Review B* 53: 1749. Copyright (1996) by The American Physical Society.

repetition rates and multi-mJ pulse energies. At this time of evolution in laser technology, solid-state, diode-pumped high repetition rate (>10 kHz), high pulse energy (>40 mJ) nanosecond (1–200 ns) lasers at a wavelength of 1 μm are seeing increasing application. Such laser sources offer a combination of robustness and cost-effectiveness, combined with a process quality improvement over sources with longer pulse duration.

In the nanosecond regime, the nature of light-matter interaction remains dependent on the wavelength of the laser source and the material properties. In particular, wavelengths in the UV exhibit reduced pulse energy threshold and can offer improved process quality. UV wavelengths less than 300 nm are currently produced by excimer and ArF gas lasers, emitting at 248 and 193 nm, respectively, or solid-state sources that are wavelength converted with nonlinear optical parametric materials to emit at 354 or 256 nm. Significant laser development effort is underway to improve optical parametric materials for nonlinear conversion, to enable greater robustness for solid-state UV sources that then offer reduced overall laser tool cost and complexity.

Semiconductor Lithography

The advantage of nanosecond and shorter pulsed lasers for materials processing extends from localization of heating. With heating being localized, a greater temperature can be achieved. This behavior is fundamental to the production of EUV radiation for application to next-generation lithographic processing.

EUV lithography is considered as an attractive candidate to succeed deep DUV-based optical lithography within this decade. EUV wavelengths around 13 nm will allow the reduction of structure sizes to less than 80 nm in semiconductor devices.

For such a high-power light source that emits at a wavelength of 13 nm, solutions are currently being pursued by multiple industry players in electrical plasma discharge and laser produced plasmas (LPP) (Figure 8). Electron beam and synchrotron sources could, in principle, satisfy the application requirements, but suffer from restriction relating to cost, size, and throughput. The choices of technologies remain to be finalized. It is, however, accepted across the industry that Moore's Law should remain intact and that a solution is required that is scalable to high throughput rates for wafer exposure.

For a laser-produced plasma, the peak wavelength of the light emitted from a plasma is determined by its temperature, T, where according to the blackbody formula:

$$T \sim E_{\mathrm{ph}}/3 \qquad [2]$$

where E_{ph} is the photon energy associated with the wavelength of maximum emission. Liner photopolymerization (LPP) schemes use pulsed laser radiation to heat a target to the optimum temperature required for efficient EUV production. For plasma-emitted light which peaks at a wavelength of 13.5 nm, the optimum temperature is approximately 3.5×10^5 Kelvin (30 eV).

A laser is focused onto a target, transferring its energy into the target in such a way that a plasma is formed and heated. A range of targets have been investigated for use in LPP schemes ranging from gaseous and cluster targets, to liquid targets and macroscopic solid targets. The interaction begins with the production of free electrons via multiphoton ionization, which is strongly dependent on the peak intensity of the laser. As heating progresses, there is further ionization from inelastic collisions between heated electrons and ions to reach a pseudo-equilibrium state, where cooling competes with heating on nanosecond timescales. Given this time-scale for cooling and requirements on source size and temperature, the optimum laser pulse duration lies in the regime of nanoseconds and the optimum laser pulse energy is hundreds of millijoules. Laser technology



Figure 8 Light source roadmap to 2010. Courtesy of Intel Corporation.

suited to this application is diode-pumped Nd:YAG, emitting at a wavelength of 1 μm and pulsed at multikilohertz repetition rates.

Fine Control Material Removal

Localized heating afforded with the application of lasers with pulse durations in the nanosecond regime and shorter, is seeing increasing takeup to replace processes ranging from wet etching and electro-discharge machining (EDM) in applications such as scribing, drilling, and differential layer removal. Laser methods are seeing advantage in direct ablation of material, for feature sizes on the order of microns to hundreds of microns. Large areas on the order of 2 m^2 are now becoming cost-effective to process with direct laser ablation, with the advent of high average power laser sources of hundreds of watts of average power, combined with nanosecond regime or shorter pulse durations. Typical sources are gas excimer or diode-pumped solid-state.

The finest processing is advantaged by the application of pulse durations in the picosecond regime. A restriction in application of this technology has been robustness and cost of the laser sources to date; however, such technology is continuing to see rapid improvement and may be expected to see wider takeup in industry by 2010.

Also seeing application, are wavelengths in the UV regime combined with nanosecond pulse durations. UV radiation in general offers a reduced threshold of ablation, translating to reduced heating and improved process quality. High absorption at UV wavelengths in most materials, combined with photon energies that can exceed bond energies of the material, contribute to the removal of material with the minimum of heating. Excimer, KrF, and ArF gas lasers are applied here (Figure 9), but it is expected that solid-state lasers will emerge by 2010 to capture a large part of the UV market. CO$_2$ gas lasers are used for fine processing where the material being ablated is of low thermal diffusivity, which is typical for dielectrics or ceramics. Materials of low thermal diffusivity are associated with a low heat affected zone (see eqn [1]).



Figure 9 KrF laser micromachined microfluidic channels in polyester for application to lab-on-a-chip technologies or sensing devices. Courtesy of Exitech Ltd.

Scribing is required for dicing of wafers such as silicon and other low-*k* materials, both for computing device manufacture and for solar cell manufacture. Nanosecond and shorter pulsed lasers have seen recent application in this area, enabling higher aspect ratio scribing and a reduced material affected zone. This application has seen laser wavelengths applied from the UV to near-infrared. Short pulse laser scribing can see advantages of high throughput yet reduced or eliminated chipping, delamination, and film peeling.

Fine drilling is required for a wide variety of applications and markets ranging from constructing vias for through-layer interconnects in printed circuit board (PCB) fabrication, to ink jet nozzles (Figure 10) and high aspect ratio holes in hard materials, such as steel or alloys for application to combustion engines.



Figure 10 A laser drilled hole in steel and an array of shaped holes in polyamide for inject nozzle application. Courtesy of Exitech Ltd.

Excimer and CO_2 laser drilling has seen industrial application in the drilling of via holes for electronics interconnection packages, since early investigations in the 1980s. More recently, high repetition rate diode-pumped solid-state lasers, nonlinearly converted to emit in the UV, are seeing application. In parallel with the increasing density of transistors in silicon processors, the density of packaging of multichip modules (MCM) and PCB components has also been increasing, requiring the drilling of blind vias on the order of 100 microns in diameter to enable interconnects between multiple conducting layers (Figure 11). Also, as processor power increases, so does the number of connections required to devices. Microvias have enabled the application of two-dimensional grid array connections to the underside of devices, reducing overall package size, including processor electrical connections, by a factor of five.

Laser drilling of microvias in PCBs is expected to increase as packing density increases. PCBs remain cheaper than MCMs and traditionally have been mechanically drilled. As via sizes are reduced below 100 μm, however, it is expected that pulsed CO_2 and Nd:YAG lasers will be applied.

Thin layer ablation is required for applications ranging from surface cleaning to display manufacture and for polymers, dielectrics, and metals. For example, manufacture of plasma displays currently incorporates lithography combined with wet etching, to pattern layers of thin conducting oxide onto a substrate. Multiple process steps can be replaced by application of direct laser ablation and increased laser average power combined with pulse durations in the nanosecond regime are allowing millions of cells to be processed per minute, with the accommodation of process areas currently greater than $2.5\ m^2$ (see Figure 12).



Figure 11 Cross-section of 14-layer copper plated MCM board showing 80 μm diameter microvias drilled by a KrF laser in acrylic resin-polyimide and, fully assembled MCM package. Courtesy of Siemens AG.

Laser-Based Diagnostics

With a continuing increase in reliability, performance, and range of specifications, lasers are seeing growing industrial application for process monitoring and diagnostics, ranging from gas phase detection of molecular specific concentrations to *in vitro* microscopy in the life sciences. Markets are emerging, driven in a large part by advances in laser technology. Chemical sensing with application of lasers is a vast field, which is difficult to cover here completely. Following, are some applications seeing current industrial application and growth.

Microscopy

Confocal microscopy has seen large uptake, in particular, for the application to imaging of cell and membrane function, with more than fifteen manufacturers now supplying confocal microscope tools including Zeiss, Biorad, Leica, Olympus, and Nikon. Confocal microscopy enables increases in resolution and contrast compared to standard microscopy. Techniques such as fluorescence resonant energy transfer (FRET), fluorescence recovery after photobleaching (FRAP), fluorescence loss in photobleaching (FLIP), fluorescence lifetime imaging (FLIM), or fluorescence correlation spectroscopy (FCS), where married with confocal microscopy and, in particular, where relevant molecular structures are known in advance, can offer the additional advantages of specific molecular and structural specificity through the incorporation of tracer fluorophores. This is seen as color coding of the resultant image, with sophisticated microscopes currently offering differential imaging stimulated by three laser colors and with six selectable colors for detection.

The confocal microscope operates with advantage over a standard microscope, by illuminating only a small area in the sample with dimensions of the resolution limit of the objective and re-imaging emission from that area through a pinhole spatial filter (Figures 13 and 14). Structures outside of the illuminated area or at a depth outside that of the focus, are suppressed from detection. Fluorophores (tracers) can be inserted into protein sequences at predetermined locations and are stimulated by either single or two-photon absorption of the stimulating laser light.

Two photon absorption has the additional advantages of increased resolution and detected contrast over single photon absorption. Laser sources applied are generally modelocked oscillators operating near 800 nm, with a pulse duration on the order of 100 fs. This technology is continuing to improve in robustness, with fiber and direct diode pumped solid-state sources available from multiple vendors.

FRAP and FLIP monitor diffusion or transport of fluorescent labeled molecules into or out of the laser focal volume, respectively. FCS monitors the fluctuations in detected signal from emissions within the laser focal volume, to determine the rate of diffusion with sensitivity achievable to the single molecule level (Figure 15).

FRET is seeing application for the probing of protein interactions in cells or at cell membranes. FRET involves the nonradiative transfer of excitation energy from one fluorophore to another, which subsequently emits at a different wavelength. The fluorophores are inserted into molecules, the



Figure 12 Plasma display manufactured by direct laser ablation of thin-film indium tin oxide (ITO). Courtesy of Exitech Ltd.



Figure 13 Confocal microscope principle of operation. Courtesy of Leica Microsystems Heidelberg GmbH.



Figure 14 Image (a): *Drosophila melanogaster*, fluorescence nonconfocal configuration and Image; (b): *Drosophila melanogaster*, fluorescence confocal 3D projection. Courtesy of Leica Microsystems Heidelberg GmbH.

interaction of which is being investigated. FRET effectively enables sensitivity to relative position at fluorophore separations less than 10 nm; a significant advance over the 200 nm resolution provided by a standard optical microscope. Concentrations of binding events can be monitored over time (Figure 16).



Figure 15 Spectral selective imaging with three fluorescence channels showing triple labeled mouse fibroblast: green: actin fibers, red: microtubules, blue: vimentin. Courtesy of Leica Microsystems Heidelberg GmbH.

Raman Methods and Microscopy

Raman spectroscopy sees broad application in chemistry in the analysis of chemical composition and molecular structure, being used, for example, in pharmaceuticals, polymer materials science, bioclinical science, and forensic science.

The history of Raman scattering stems from theoretical predictions in the early 1920s,


CFP
YFP
Energy
λex
FRET
λem
Donor
Acceptor
YFP
Stimulus
Intensity
FRET
CFP
Time (s)

Figure 16 Fluorescence resonant energy transfer mechanism and example relating to cytoplasmic Ca^{2+} concentration. Cyan Fluorescent Protein (CFP) and Yellow Fluorescent Protein (YFP) are acceptor and donor, respectively, for the FRET. Courtesy of Carl Zeiss, Germany.


1960
1970
1980
1990
2000
Weber & Porto - 1st measurements w laser
Cary 81L - with laser
Spex 1401 Double Mono-designed by Sergio Porto and Don Landon
First commercial Holo gratings
First use of Ar+ and Kr+ lasers
Jy Double-Concave Holographic Gratings
Characteristics of Triple Spectrograph are described
MOLE Raman Microscope exhibited @ Raman Conf. at Bowdoin College and NBS system built
Triple Spectrographs with Multichannel Detectors introduced by Dilor, Johin Yvon, and Spex
Demonstration of NIR FTRaman - Chase and Rabolt
Carrabba: Demonstration of Holographic Filter for suppression of Rayleigh light
Dillor introduce first stigmatic benchtop systems
Confocal line-scanning patented for Raman mapping
785 nm laser sources and CCD detectors
UV Raman microscope introduce as commercial product
First FTIR/Raman Microscope - JY and SensIR

Figure 17 Timeline of Raman spectroscopy from the first incorporation of a laser source. Courtesy of Jobin Yvon.

accompanied also in the 1920s by early measurements, notable being those of C.V. Raman for which he was awarded the Nobel prize, soon followed in the 1930s by hundreds of chemistry papers describing this technique. Raman used for his early experiments filtered sunlight, a prism spectrometer, and visual observation. This was followed by application of filtered Hg emission and photographic plates. Lasers first saw application to Raman scattering in the 1960s, shortly after their innovation (see Figure 17).

In the simplest form of application of the Raman effect, UV or visible radiation illuminates a sample, coupling to excite electronic transitions near or on resonance. Spontaneous emission is shifted to a longer wavelength than that of the excitation (Stokes emission) and this is filtered and detected. In general, a broad spectrum of fluorescence is superimposed by weaker, narrow features that originate from vibration-electronic coupling (Raman emission). Inclusion of laser excitation increases the rate of data collection and also enables nonresonant interaction of the stimulating radiation with the sample whilst maintaining data collection rates. Nonresonant interaction preferentially reduces electronic emission of fluorescence relative to that of the narrow featured Raman emission. Lasers applied to spontaneous Raman spectrometers in general emit in the visible or near-infrared running nonpulsed, such as Ar-ion, Nd:YAG or He:Ne.

Further enhancements are made to deliver spatial as well as vibration-specific information, through tight focusing of the stimulating radiation on to the sample in a confocal microscope arrangement, delivering spatial resolution down to 200 nm (Figure 18).

A limitation of standard Raman spectrometers and microscopes is the rate of signal collection, requiring concentrated samples for interrogation. The restricted signal level derives from a typical cross-section for the spontaneous emission of Raman radiation being 10^{-30} cm^2; 10^{10} to 10^{14} times less than that typical for spontaneous electronic fluorescence. Enhancements in the level of signal and the ratio of signal to background noise may be made through coherent laser stimulation of anti-Stokes Raman emission, known as coherent anti-stokes Raman scattering (CARS) (Figures 19 and 20).

It can be anticipated that bond-specific imaging will see wide industrial application in future, employing Raman as well as resonant infrared techniques. Application of CARS to microscopy involves two laser colors. A vibration transition is exited at the beat frequency of the two laser frequencies and the shorter laser wavelength is subsequently scattered from the sample to a yet shorter wavelength of emission. Such a coherent process has the advantage of signal scaling proportional to the square of emitters at the sample, thereby increasing the signal over that of spontaneous Raman scattering. Typical laser pump and Stokes powers range from less than 1 mW to 10s of mW, with laser repetition rates ranging from multi-kHz to greater than 100 MHz and typical pulse durations from 10s of picoseconds to 100 fs.

Infrared Methods

Infrared absorption spectroscopy provides a wealth of information on bond-specific sample concentration



Figure 18 Confocal Raman image of semicrystalline polypropylene film. Two typical Raman spectra are shown. The ratio of the Raman lines at 809 and 841 cm increases with the degree of crystalline order, delivering a two-dimensional image (Hendra *et al.* 1995). Courtesy of Witec GmbH.



Figure 19 CARS image of a NIH 3T3 cell in metaphase, where Raman vibration stimulation is tuned to the PO_2^- symmetric stretching vibrational frequency at 1090 cm^{-1}. Reproduced from Cheng J-X, Kevin JYK, Zheng G and Xie X-S (2002) Laser-scanning coherent anti-Stokes Raman scattering microscopy and applications to cell biology. *Biophysical Journal* 83: 502–509, with permission from The Biophysical Society.



Figure 20 CARS microscope image of an erythrocyte ghost, consisting of a single lipid bilayer, with a Raman shift of 2845 cm^{-1}. The scale bar is of length 2 µm. Reproduced from Potma EO and Xie X-S (2003) Detection of single lipid bilayers with coherent anti-Stokes Raman scattering (CARS) microscopy. *Journal of Raman Spectroscopy* 36: 642–650, with permission from Wiley InterScience.

and has become a standard tool for the chemistry laboratory. Interaction between the radiation and sample is via resonant vibrational absorption and is otherwise analogous to the operation of a standard optical absorption spectrometer. Applied to a microscope arrangement, resolution on the order of 10 µm is standard. One restriction associated with infrared absorption spectroscopy applied to solution, is that absorption lineshapes are broadened and the spectra lose detail at room temperature, hindering identification of the contributing species.

A technique showing early promise for application in bond-specific molecular detection in solution, is coherent resonant infrared wavemixing. Here, cross coupling between vibrational modes are detected, promising information more detailed than that of infrared absorption. Figure 21 shows an example of triply vibrationally enhanced four-wave mixing, where two infrared laser beams mix to deliver cross peaks representing vibration mode coupling. Here, the 2D spectrum contains two sets of cross-peaks corresponding to the couplings of the two strong IR modes at 1943 and 2002 cm^{-1} of $Ni(CO)_2(PPh_3)_2$ and 1996 and 2068 cm^{-1} of $Ni(CO)_3PPh_3$. Concentrations in solution are on the order of 10 mM. Such methods provide a means sensitive to chemical structure without a requirement for fluorophores.

Current application requires complex laser equipment delivering microjoule pulse energies, tunable between 3 and 10 microns, with pulse durations on the order of 1 ps. However, following the example of other laser diagnostic techniques in application



Figure 21 Triply vibrationally enhanced four-wave mixing of $Ni(CO)_2(PPh_3)_2$ and $Ni(CO)_3PPh_3$. Reproduced from Meyer KA, Besemann DM and Wright JC (2003) Coherent two dimensional spectroscopy with triply vibrationally enhanced infrared four-wave mixing. *Chemical Physics Letters* 381: 642–649, with permission of Elsevier.



Figure 22 DIAL trace of sulfur dioxide distribution from Mount Etna. Reproduced with permission from Weibring P, Edner H and Svanberg S (2003) Versatile mobile lidar system for environmental monitoring. *Applied Optics* 42: 3583–3594. © 2003 Optical Society of America.

across industry today, as laser technology advances over this decade, we can expect such methods of probing chemical systems to see significant uptake, in particular in the bio-industries.

Laser Diagnostics and Treatment of Tumors

For clinical medicine, fluorescent detection is applied in the visualization of malignant tumors. Important natural chromophores emitting fluorescence in the blue-green region are elastin, collagen, NADH, and NAD^+, whilst administered agents such as porphyrins and phthalocyanines yield sharp peaks in the dark red.

Excitation is via UV or violet light. Where emission is monitored in both the blue-green and red regions of the spectrum and the ratio taken, an enhanced tumor differentiation is possible from that of normal tissue whilst simultaneously reducing sensitivity to geometry, illumination, and detection efficiency. Fiber optic probes are generally applied for delivery and collection of radiation.

Such detection can be combined with techniques of laser photodynamic therapy (PDT) to preferentially remove cancerous tissues. Typical laser wavelengths for photodynamic therapy are in the visible region of 600 to 700 nm with a pulse fluence of tens of joules/cm^2, a pulse duration in the nanosecond regime and a repetition rate from single shot to 10 Hz. Where combined with diagnostic detection, the PDT can be carried out by exciting the same administered sensitizer, with subsequent transfer of ground-state triplet oxygen to a toxic singlet state.

Remote Chemical Sensing

The atmosphere can be monitored by absorption and laser-induced fluorescence (LIF). Three-dimensional mapping of chemical distribution can be achieved with light detection and ranging (LIDAR), using a pulsed laser as a transmitter and an optical telescope as a receiver. Information collated includes pollution concentration, temperature, humidity, and wind velocity. Strong quenching prohibits LIF at atmospheric pressures; however, it does become practical to monitor for example, Li, Na, K, and Ca layers in the mesosphere. Pollution monitoring in the troposphere is most frequently performed with differential absorption LIDAR (DIAL). Range resolved optical transients are taken as a ratio of two laser wavelengths; on and just off resonance for the species of interest. Typical ranges for detection of SO_2, O_3, NO_2, NO, and Hg are 500 m to 5 km, making this technique suitable for urban and industrial monitoring. Sulfur dioxide is the most common pollutant emitted when fossil fuels are burned or sulfide ores are roasted and this technique sees application for the monitoring of industrial emissions. Figure 22 shows a DIAL trace recorded from Mount Etna, from which emissions of SO_2 are estimated at 75 tonnes/h. Laser wavelengths used are 300.02 and 299.30 nm for on and off resonance for absorption, respectively.

Important to the widespread application of LIDAR and LIF for atmospheric chemical monitoring, has been the advance in robustness and flexibility of the associated laser technologies. The laser technology applied for the above measurement is based on solid-sate Nd:YAG, nonlinearly converted via optical parametric amplification to wavelengths tunable between 220 nm and 4 μm, delivering up to 20 mJ in the mid-infrared at a repetition rate of 20 Hz and with bandwidths of less than 0.2 cm^{-1}, in a pulse duration of 4 ns.

See also

Imaging: Infrared Imaging. **Lasers:** Carbon Dioxide Lasers. **Microscopy:** Confocal Microscopy. **Scattering:** Raman Scattering. **Spectroscopy:** Raman Spectroscopy.

Further Reading

Allen SD, Bass M and Teisniger ML, Comparison of pulsed Nd:YAG and pulsed CO2 lasers for hole drilling in printed circuit board materials. CLEO 1982 Conference Summary.

Cheng J-X, Kevin Jia YK, Zheng G and Xie X-S (2002) Laser-scanning coherent anti-Stokes Raman scattering microscopy and applications to cell biology. *Biophysical Journal* 83: 502–509.

Cymer Inc., http://www.cymer.com

Cymer Inc., ASML, TRW, Xtreme Technologies GmbH, Fraunhoffer Institut fur Lasertechnik, Philips Extreme UV GmbH, Royal Institute of Technology Sweden, PLEX LLC.
Disco Corporation, http://www.disco.co.jp/
Exitech Ltd., http://www.exitech.co.uk/
Lamda Physik, http://www.lambdaphysik.de/
Meyer KA, Besemann DM and Wright JC (2003) Coherent two dimensional spectroscopy with triply vibrationally enhanced infrared four-wave mixing. *Chemical Physics Letters* 381: 642–649.
Perkin Elmer, www.perkinelmer.com
Phillips D (1997) Chemical mechanisms in photodynamic therapy with phthalocyanines. *Progress in Reaction Kinetics* 22(3–4): 175–300.
Potma EO and Xie X-S (2003) Detection of single lipid bilayers with coherent anti-Stokes Raman scattering (CARS) microscopy. *Journal of Raman Spectroscopy* 34: 642–650.
Powerlase Ltd., http://www.powerlase.com
Presstek Inc., Hudson, NH, http://www.presstek.com
Pronko PP, Dutta DK, Squier J, Rudd JV, Du D and Mourou G (1995) Machining of sub-micron holes using a femtosecond laser at 800 nm. *Optics Communications* 114: 106–110.
Reiser A (1989) *Photoreactive Polymers – The Science and Technology of Resists*. John Wiley & Sons.
Silverman PJ (2002) Intel Corporation. Presented at 1st Intl EUV Lithography Symposium, 15–17 October 2002, Dallas, USA.
Stuart BC, Feit MD, Herman S, Rubenchik AM, Shore BW and Perry MD (1996) Nanosecond-to-femtosecond laser-induced breakdown in dielectrics. *Physics Review B* 53(4): 1749.
Svanberg S (1996) Chemical sensing with laser spectroscopy. *Sensors and Actuators B* 33: 1–4.
Wang I, Bendsoe N, Klinteberg CAF, *et al.* (2001) Photodynamic therapy vs. cryosurgery of basal cell carcinomas: results of a phase III clinical trial. *British Journal of Dermatology* 144(4): 832–840.
Watson MN (1984) Laser drilling of printed circuit boards. *Circuit World* 11: 13.
Waynant RW (ed.) (2002) *Lasers in Medicine*. CRC Press.
Weibring P, Edner H and Svanberg S (2003) Versatile mobile lidar system for environmental monitoring. *Applied Optics* 42(18): 3583–3594.
WITEC, WITec Wissenschaftliche, Instrumente und Technologie GmbH, Hörvelsinger Weg 6, D-89081 Ulm, Germany, www.WITec.de
Yvon J, www.jobinyvon.com

Sum-Frequency Generation at Surfaces

M B Raschke and Y R Shen, University of California, Berkeley, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Under sufficiently intense illumination the optical properties of a material system depend nonlinearly on the strength of the electromagnetic field. Related to this nonlinear optical response is a large number of phenomena and fundamental processes which are discussed in various articles of this encyclopedia. This article will focus on second-harmonic generation (SHG) and sum-frequency generation (SFG) for the investigation of surfaces and interfaces. The intrinsic surface sensitivity of these techniques allows for investigations of surface properties not readily accessible by other spectroscopies. Here, the basic principles of these optical processes as well as their experimental implementation are discussed, and a summary of the applications to different material systems is given.

Among the various techniques employed for the characterization of surfaces and interfaces, those using light are particularly attractive. They are applicable *in situ* to all interfaces accessible by light, are nondestructive, and offer unprecedented time resolution. However, the penetration depth of optical radiation in matter is generally of the order of a wavelength, which makes isolation of the surface or interface contribution to the optical response from the bulk contribution difficult. In contrast, for reasons of symmetry, SHG and SFG are intrinsically surface sensitive in media with inversion symmetry, and hence the signal generated mainly originates from the topmost surface layer where the inversion symmetry is broken. By means of electronic or vibrational SHG or SFG spectroscopy, information on surface structure, chemical composition and bond or molecular orientation at solid and liquid interfaces can be deduced. To date, SFG and SHG have been well established as important tools for the investigation of surfaces and interfaces of solids ranging from metals and semiconductors to insulators and magnetic materials, liquids, polymers, biological membranes, and other systems. The studies are motivated by fundamental interests as well as applications in many areas such as heterogeneous catalysis, electrochemistry, device fabrication, epitaxial growth, and environmental science.

Theory

The nonlinear optical response of a material, in the electric-dipole approximation, can often be described by an induced polarization in the form of a power series,

$$\begin{aligned}\boldsymbol{P}(\omega)=\epsilon_0[&\chi^{(1)}(\omega)\boldsymbol{E}(\omega)\\ &+\chi^{(2)}(\omega=\omega_1+\omega_2)\boldsymbol{E}(\omega_1)\boldsymbol{E}(\omega_2)\\ &+\chi^{(3)}(\omega=\omega_1+\omega_2+\omega_3)\boldsymbol{E}(\omega_1)\boldsymbol{E}(\omega_2)\boldsymbol{E}(\omega_3)+\dots]\end{aligned} \qquad [1]$$

where $\boldsymbol{E}(\omega_i)$ is the optical field with frequency ω_i and $\chi^{(n)}$ is the nth-order linear ($n=1$) or nonlinear ($n>1$) susceptibility tensor. The second term, being the lowest-order nonlinear optical response, is responsible for sum-frequency generation and second-harmonic generation (with $\omega_1=\omega_2$). In the electric-dipole approximation, all even-order terms ($\chi^2, \chi^{(4)}$, etc.) are forbidden in media with inversion symmetry. At the surface or interface, however, the inversion symmetry is necessarily broken and hence $\chi^{(2)}\neq 0$. This makes SHG and SFG surface-sensitive and specific. While electric-quadrupole and magnetic-dipole contributions from the bulk may not be totally negligible, in many cases it has been shown that the surface contribution clearly dominates.

Surface SFG and SHG is best described by radiation from a surface polarization $\boldsymbol{P}_s^{(2)}(\omega)$ induced in a thin sheet with dielectric constant ε' sandwiched between two linear media (1) and (2) as shown schematically in Figure 1. This surface polarization has an in-plane wavevector component equal to the sum of the in-plane wavevector components of the incident fields: $\boldsymbol{k}_\parallel(\omega)=\boldsymbol{k}_\parallel(\omega_1)+\boldsymbol{k}_\parallel(\omega_2)$. The ratio of $\boldsymbol{k}_\parallel(\omega)$ to $\boldsymbol{k}(\omega)$ then determines the direction of the sum-frequency output that appears in both transmission and reflection. The reflection geometry is often used in order to minimize the bulk contribution.



Figure 1 Schematic of SHG and SFG geometry in reflection and transmission from an interface.

With $\boldsymbol{P}_s^{(2)}$ as the source term, the sum-frequency output can be obtained from the solution of the wave equation. With the proper boundary conditions the sum frequency (SF) intensity is given by:

$$\begin{aligned}I(\omega)=&\frac{8\pi^3\omega_s^2\sec^2\theta_\omega}{\hbar c^3\sqrt{\epsilon_1(\omega)\epsilon_1(\omega_1)\epsilon_1(\omega_2)}}\\ &\times|\boldsymbol{e}^\dagger(\omega)\cdot\boldsymbol{\chi}_s^{(2)}:\boldsymbol{e}(\omega_1)\boldsymbol{e}(\omega_2)|^2 I_1(\omega_1)I_2(\omega_2)\end{aligned} \qquad [2]$$

In this expression, $\chi_s^{(2)}$ is the surface nonlinear susceptibility defined by $\boldsymbol{P}_s^{(2)}=\varepsilon_0\boldsymbol{\chi}_s^{(2)}:\boldsymbol{E}(\omega_1)\boldsymbol{E}(\omega_2)$; the quantities $\boldsymbol{e}(\omega_i)$ correspond to the unit polarization vectors after the appropriate Fresnel correction, $\boldsymbol{e}(\omega_i)\equiv\boldsymbol{F}(\omega_i)\hat{\boldsymbol{e}}(\omega_i)$, with $\boldsymbol{F}(\omega_i)$ being the transmission Fresnel factor and $\hat{\boldsymbol{e}}(\omega_i)$ the unit polarization vector of $\boldsymbol{E}(\omega_i)$; θ_ω denotes the SF output angle with respect to the surface normal, $\varepsilon(\omega_i)$ is the dielectric constant at frequency ω_i, and I_i is the input pump intensity at ω_i.

The surface nonlinear susceptibility $\chi_s^{(2)}$ is a third-rank tensor. In Cartesian coordinates it has 27 tensor elements ($\chi_{ijk}^{(2)}$), many of which could vanish or depend on others due to the surface structural symmetry. As an example, $\chi_{ijk}^{(2)}(\omega=\omega_1+\omega_2)$ for an isotropic surface, with the z-direction defined by the surface normal, has only four independent nonvanishing elements: $\chi_{xxz}^{(2)}=\chi_{yyz}^{(2)}, \chi_{xzx}^{(2)}=\chi_{yzy}^{(2)}, \chi_{zxx}^{(2)}=\chi_{zyy}^{(2)}$, and $\chi_{zzz}^{(2)}$. Different combinations of input and output beam polarizations in SFG measurements are often used to deduce values for the non-vanishing elements. Such measurements then allow the determination of surface symmetry or surface molecular orientation. Being a third-rank tensor, $\chi_s^{(2)}$ can reflect up to three-fold rotational symmetry. $\chi_{s,ijk}^{(2)}$ is related to the molecular nonlinear polarizability or hyperpolarizability $\alpha_{\xi\eta\zeta}^{(2)}$, where $\hat{\xi}$, $\hat{\eta}$, and $\hat{\zeta}$ define the molecular coordinates, through the coordinate transformation

$$\chi_{s,ijk}^{(2)}=N_s\left\langle(\hat{\boldsymbol{i}}\cdot\hat{\boldsymbol{\xi}})(\hat{\boldsymbol{j}}\cdot\hat{\boldsymbol{\eta}})(\hat{\boldsymbol{k}}\cdot\hat{\boldsymbol{\xi}})\right\rangle\alpha_{\xi\eta\zeta}^{(2)} \qquad [3]$$

The angular brackets denote an average over the molecular orientational distribution, and N_s is the surface molecular density. For simplicity, microscopic local-field correction is neglected in eqn [3]. Knowing $\chi_{s,ijk}^{(2)}$ and $\alpha_{\xi\eta\zeta}^{(2)}$ thus permits deduction of information on the orientational distribution.

An explicit expression for the nonlinear optical polarizability is obtained from a second-order quantum mechanical perturbation calculation:

$$\begin{aligned}\alpha^{(2)}_{s,ijk}(\omega_s) = & -\frac{e^3}{\hbar^2}\sum_{g,n,n'}\left[\frac{\langle g|r_i|n\rangle}{\omega_s-\omega_{ng}+i\Gamma_{ng}}\right. \\ & \times\left(\frac{\langle n|r_j|n'\rangle\langle n'|r_k|g\rangle}{\omega_2-\omega_{n'g}+i\Gamma_{n'g}}\right. \\ & \left.\left.+\frac{\langle n|r_k|n'\rangle\langle n'|r_j|g\rangle}{\omega_1-\omega_{n'g}+i\Gamma_{n'g}}\right)+\cdots\right]\rho_g^{(0)} \qquad [4]\end{aligned}$$

This expression shows how the nonlinear polarizability or susceptibility depends on material parameters such as the dipole transition moments $\langle n|r_i|g\rangle$ and energy levels. It contains a sum over eight resonant terms. The quantities ω_{ng} and Γ_{ng} are the frequencies and half-widths for the transitions between quantum states $|n\rangle$ and $|g\rangle$, and $\rho_g^{(0)}$ denotes the population in $|g\rangle$. It can be seen that $\alpha^{(2)}$, and hence the SF output, should be resonantly enhanced when the pump frequency ω_1 or ω_2 and/or the sum frequency $\omega_1+\omega_2$ approach resonance. The resonant enhancement provides spectral information and makes SHG and SFG effective spectroscopic tools. The resonances could be electronic or vibrational, or more generally, any surface characteristic transition.

Experimental

Here we deal with basic considerations concerning the optical setup for SHG or SFG experiments in reflection from a surface as is shown schematically in Figure 2. In general, the pump radiation from pulsed laser sources is directed onto the surface. High-power tunable light pulses can be obtained from optical parametric generation and amplification (OPG/OPA) together with harmonic, sum- or difference-frequency generation, preferably pumped by picosecond or femtosecond lasers with high repetition rates. By this means radiation tunable from near UV at ~200 nm to mid IR at ~18 μm can be generated. For SFG the input pulses with frequencies ω_1 and ω_2 are directed to overlap spatially and temporally on the sample. The sample could be the surface of a liquid or solid in air, a single crystalline surface in ultrahigh vacuum, buried interfaces, etc. Polarizers and half-wave plates allow for tuning of incident power and polarizations at the sample. Together with the polarizer in the output path, different input/output polarization combinations can be chosen. In the detection system the signal has to be discriminated against reflected and scattered pump light. This is achieved by spatial and spectral filtering with apertures, dielectric mirrors, and interference and color glass filters. An optional monochromator can also be used for additional stray-light suppression. The signal is then detected by a photomultiplier tube and gated electronics are used for signal integration or photon counting.

From eqn [2] the expected signal strength for SHG/SFG can be estimated. With a typical value of $\chi_s^{(2)}$ of 10^{-21} m^2 V^{-1}, a single 1-μm pump pulse, incident at $\theta = 45°$ having pulse energy $E = I\,A\tau = 100$ μJ, beam cross-section $A = 1$ mm^2, and pulse duration $\tau = 10$ ps, can generate about 10^3 photons per pulse of SHG. By means of photon counting a minimal count rate of 10^{-3} photons/pulse



Figure 2 Schematic of experimental setup for second-harmonic and sum-frequency generation.

can be achieved which allows the detection of $\chi_s^{(2)}$ as small as 10^{-24} m^2 V^{-1}. The spectral resolution is limited by the spectral width of the pump pulses. In order to obtain accurate spectral data over a wide tuning range or to obtain absolute values for $\chi_{s,ijk}^{(2)}$ of the material investigated, a reference material such as *z*-cut quartz with known values of χ is to be measured for comparison.

The simplest kind of experiments are SHG at a fixed pump frequency. From the signal variation in response to surface modification one can probe kinetics and dynamics of adsorption, desorption, diffusion, surface melting, phase transitions, etc. By tuning the pump wavelength, second-harmonic spectroscopy can give information on surface electronic states. For surface vibrational spectroscopy, however, IR-vis SFG must be employed. In the latter case, tunable IR input is mixed with visible input to yield a SF signal in the visible region.

Surface Specificity

In many cases, the surface contribution to SFG or SHG from a centrosymmetric medium clearly dominates over the bulk contribution. This generally occurs when the surface or interface is composed of a polar oriented molecular layer. An example is shown in Figure 3, where the vibrational spectra in the C–H stretch region of three buried solid–liquid interfaces are presented. The spectrum for hexadecane ($C_{16}H_{34}$)/fused silica shows no C–H peaks. This is in spite of the fact that liquid hexadecane has strong infrared and Raman activity in this spectral range. The result indicates that the bulk signal contribution is negligible. In contrast, strong resonances are observed from the hexadecane/OTS/silica system, where OTS is a monolayer of octadecyltrichlorosilane ($CH_3(CH_2)_{17}SiCl_3$) chemisorbed on the fused silica plate. A similar spectrum is obtained for the CCl_4/OTS/silica interface. This clearly indicates that it is the contribution from the OTS monolayer that dominates the spectra.

Another example is described in Figure 4 where the SFG spectrum in reflection from a free liquid water surface is shown. The resonant features between 3000 and 3600 cm^{-1} are due to the O–H stretches of hydrogen-bonded OH groups. The sharp peak at 3700 cm^{-1} can be identified with the free OH bonds. Since no dangling OH bonds can exist below the surface its presence indicates that the spectrum must originate from the topmost layer of water molecules. Furthermore it can be shown that the surface water molecules are oriented with one of the OH bonds directed out of the liquid. In addition to the above examples, the surface sensitivity and specificity has been demonstrated and successfully applied to a large number of systems as will be shown below.

A note on the definition of surface or interface is in order. In SHG and SFG, the surface or interface layer refers to a thin layer between two adjacent bulk media that has a different structure from the bulk media and lacks inversion symmetry. If molecules in the surface layer are polar-ordered, then SHG and



Figure 3 SFG spectra of different interfaces obtained with *ssp* polarization combination: hexadecane/silica (dashed), CCl_4/ OTS/silica (solid circles), and hexadecane/OTS/silica (open squares). OTS refers to a monolayer of octadecyltrichlorosilane.



Figure 4 SFG spectrum of the liquid–vapor interface of pure water (*ssp* polarization combination). The mode at 3700 cm^{-1} is due to the dangling OH bonds at the surface.

SFG are often dominated by contributions from the surface layer. However, the bulk contribution is not strictly zero even if the media have inversion symmetry, as $\chi^{(2)}$ can arise from electric-quadrupole and magnetic-dipole contributions. Separation of surface and bulk contributions in SHG and SFG is a subtle problem in general. Experimentally, how surface modification affects the signal can be used to evaluate whether or not the surface contribution dominates.

A special case concerns materials that lack bulk inversion symmetry, for example, III–V and II–VI semiconductors such as GaAs and ZnSe. In this case, the bulk contribution to SHG and SFG is electric-dipole allowed and may be very significant. With an appropriate choice of polarization combinations and surface orientation, it can nevertheless be well suppressed, leaving the surface contribution dominant.

Applications

Both SFG and SHG have been applied to a wide variety of surface and interfacial systems. To illustrate their capabilities and versatility as surface spectroscopic tools, the focus of this summary will be on examples where the information deduced cannot readily be obtained by other techniques. (For details, readers are referred to the review articles cited in Further Reading and the original papers cited therein.)

SFG and SHG have been used for the study of adsorbates at surfaces even under ambient conditions. The adsorbate alters electronic or structural properties of the substrate and the signal is thus related to the surface density of the adsorbate and its orientation.

Elementary surface reactions, in particular adsorption, dissociation, or desorption of simple molecules such as CO, hydrogen, oxygen, or water on metal and semiconductor single-crystal surfaces under ultrahigh-vacuum conditions, have been investigated. Sensitivity into the sub-percent monolayer regime is achieved and allows the identifictation of competing reaction channels and adsorbate dynamics on surfaces. Such studies can help to understand epitaxial growth or heterogeneous catalysis because the techniques are applicable at any gas pressure and surface temperature. Related to this is the study of surface diffusion, which can be probed following the temporal decay of a diffracted SHG signal off a submonolayer adsorbate grating formed by laser-induced desorption.

Making use of the spectroscopic capabilities of SHG, the surface electronic structure of selected metals and semiconductors, in particular silicon, were studied with an emphasis on the effects of temperature, crystallographic orientation and different adsorbates. Among buried interfaces, the Si/SiO$_2$ interface has been the subject of intense investigations and the sensitivity of SHG to static electric fields at the interface and to inhomogeneous strain was also demonstrated.

Different in-plane surface symmetries associated with different crystallographic orientations or surface reconstructions yield different SHG and SFG responses. This allowed for the investigation of surface reconstructions (e.g., Si(111)$2 \times 1 \rightarrow 7 \times 7$), order–disorder transitions (e.g., Si(111)$7 \times 7 \rightarrow 1 \times 1$, Au/Si(111)) and surface melting (e.g., single-crystal ice, Si(111), Ge(111)), providing information on latent heat, superheating, and its dynamics using pump-probe techniques. Magnetization-induced SHG was also used for probing surface and interface magnetism of ferromagnetic metals and bimetallic systems.

Many unique applications of spectroscopic SFG have been developed based on its capability to study large molecules, in particular under ambient conditions. Surface vibrational spectra with different input/output polarization combinations and sample geometries provide information on orientation, conformation and alignment of surface molecules and the composition and structure of the surface layer. The study of self-assembled monolayers (e.g., OTS on quartz) to deduce the orientation and conformation of the alkyl chains in the monolayer is an example. The effect of molecular density and temperature on the spectrum gives information on intermolecular interactions and phase transitions. Another example concerns the adsorption of liquid crystal molecules on nanostructured polymer substrates. Both the chain orientation at the polymer surface and its effect on the alignment of adsorbed liquid crystal molecules can be addressed.

Surface structures of liquids, especially those of pure liquids, are of great interest in science and technology, and SFG is a unique spectroscopic tool for probing liquid surfaces and interfaces. For example, the SFG vibrational spectrum for the water–vapor interface in Figure 4 gives information on the density and orientation of the surface water molecules at the water–vapor interface. The surface layer was found to be more ordered compared to the bulk as was also observed for various other organic liquids studied with SFG. In other cases soluble and insoluble organic molecules at a liquid–vapor, liquid–liquid, or liquid–solid interface have also been studied. They appear as adsorbed monolayer films and their structure and phase behavior are relevant to many applications. Identification of the adsorbed molecular species at solid–liquid interfaces is also important for understanding electrochemical processes. Various studies with SFG have addressed bonding of, e.g., CO, CN^-, and SCN^- at electrodes and its variation with electrode potential.

SFG spectroscopy also finds unique applications in studies of polymer surfaces and interfaces most relevant to modern science and technology. The observed surface vibrational spectra of polymers provide information on surface composition, molecular orientation, and conformation of neat and blended polymers. The effect of environment and surface treatment on the surface structure can also be studied. Investigation of the biological functions of complex molecular systems has attracted increasing interest, and SHG and SFG have been applied successfully to selected systems ranging from the isomerization of retinal – a molecule involved in the vision process – to functional aspects of model membranes.

Both SHG and SFG can be combined with microscopy techniques for surface microscopic studies. Microscopic imaging can be achieved by rastering the probe beam or, preferably, the sample position. Near-field SFG/SHG spectroscopy has recently been developed.

Performing surface SHG and SFG experiments in the time domain can provide information on surface dynamics. Pump-probe experiments allow for measurements of energy relaxation and phase coherence of excitations such as surface electronic states and surface phonons and vibrations.

Outlook

Although SHG and SFG were established as surface analytical tools more than 15 years ago, it is still an active field of research with much potential that has not yet been explored. As an example, it has only recently been demonstrated that doubly resonant infrared–visible SFG, as a two-dimensional spectroscopy, can give access to couplings between vibrational modes and surface electronic transitions. With the commercial availability of suitable laser sources, the techniques can be extended to a much wider range of applications. This includes possible investigations of ultrafast surface dynamics, nanostructures, and biological systems.

Further Reading

Bennemann KH (ed.) (1998) *Nonlinear Optics in Metals*. Oxford, UK: Clarendon Press.

Bloembergen N (1977) *Nonlinear Optics*. New York: Benjamin.

Boyd RW (1993) *Nonlinear Optics,* 2nd edn. San Diego, CA: Academic Press.

Dumas P, Weldon MK, Chabal YJ and Williams GP (1999) Molecules at surfaces and interfaces studied using vibrational spectroscopies and related techniques. *Surface Review & Letters* 6(2): 225–255.

Guyot-Sionnest P and Harris AL (1995) Surface vibrational dynamics probed by sum frequency generation. In: Ho W and Dai HL (eds) *Laser Spectroscopy and Photochemistry of Metal Surfaces*, pp. 405–458. Singapore: World Scientific.

Guyot-Sionnest P, Superfine R, Hunt JH and Shen YR (1988) Vibrational spectroscopy of a silane monolayer at air/solid and liquid/solid interfaces using sum-frequency generation. *Chemical Physics Letter* 144: 1–5.

Heinz TF (1991) Second-order nonlinear optical effects at surfaces and interfaces. In: Stegeman GI and Ponath H-E (eds), *Nonlinear Surface Electromagnetic Phenomena*, pp. 353–416. Amsterdam, The Netherlands: North-Holland.

Matthias E and Träger F (eds) (1999) *Applied Physics B, Special Issue: Nonlinear Optics at Interfaces*, Volume 210.

McGilp JF (1999) Optical second-harmonic generation as a semiconductor surface and interface probe. *Physica Status Solidi (a)* 175: 153–167.

Miranda PB and Shen YR (1999) Liquid interfaces: A study by sum-frequency vibrational spectroscopy. *Journal of Physical Chemistry B* 103: 3292–3307.

Reider GA and Heinz TF (1995) Second-order nonlinear optical effects at surfaces and interfaces: recent advances. In: Halevi P (ed.) *Photonic Probes of Interfaces*, 413. Amsterdam, The Netherlands: Elsevier.

Shen YR (1984) The Principles of Nonlinear Optics. New York: Wiley.

Shen YR (1994) Nonlinear optical studies of polymer interfaces. *International Journal of Nonlinear Optical Physics* 3: 459–468.

Shen YR (1994) Surface spectroscopy by nonlinear optics. In: Ḧansch TW and Inguscio M (eds) *Frontiers in Laser Spectroscopy*, pp. 139–165. Amsterdam, The Netherlands: North-Holland.

Shen YR (2001) Vibrational spectroscopy of water at interfaces. In: Morra M (ed.) *Water in Biomaterials Surface Science*, Chapter 8, pp. 215–244. Chichester, UK: Wiley.

Wei X and Shen YR (2001) Motional effect in surface sum-frequency vibrational spectroscopy. *Physical Review Letter* 86: 4799–4802.

POLARIZATION

Contents

Introduction
Matrix Analysis

Introduction

J M Bennett, Michelson Laboratory, China Lake, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Polarization is one property of light waves and will be defined after a brief overview of the properties of light. Light is part of the electromagnetic spectrum of waves that have both particle-like and wave-like properties. Light waves carry energy in the form of photons which act like particles; the photon energy increases in proportion to the frequency of the wave. The particle-like properties of light and other electromagnetic waves are described by quantum mechanics. Light also acts like transverse waves that travel in straight lines in air and vacuum and can be described by classical electromagnetic theory. Polarization deals with the wave-like properties of light, and is described mathematically by Maxwell's equations, the key relations in electromagnetic theory. Polarization effects occur when light interacts with matter. In order to understand polarization, there will be a brief introduction to the subject of electromagnetic waves.

For a more in-depth treatment of the material in this article, the reader is directed to the Further Reading list at the end of this article and in particular to the two chapters on 'Polarization' and 'Polarizers' written by the author in Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. I, chapter 5 and vol. II, chapter 3. New York: McGraw-Hill Inc.

Electromagnetic waves have both electric and magnetic fields associated with them. These are vibrations in directions perpendicular to the direction the wave is traveling, i.e., the direction of propagation. $\vec{E}$ represents the vector of the electric field and $\vec{H}$, perpendicular to $\vec{E}$, represents the magnetic field vector. Both these vectors are complex and have real and imaginary parts. Polarization effects are always associated with the $\vec{E}$ vector. Specifically, the plane of polarization is defined as the plane in which the $\vec{E}$ vector is vibrating. Waves having different amplitudes, phases, or angular orientations (azimuths) of their electric or magnetic vectors can be combined by conventional vector addition methods. Also the $\vec{E}$ vector of a particular vibration can be resolved into two components in mutually perpendicular directions that are vibrating in phase.

If a light source such as the sun, a candle flame, or an electric light bulb is considered on a microscopic scale, each vibrating atom or molecule emits linearly polarized light (see the definition below). But the individual atoms or molecules do not act together, so their vibrations have no fixed phase relationships to each other and they cannot be added into a single linearly polarized beam. Thus, we call light from these sources unpolarized. In an unpolarized light beam, the $\vec{E}$ vector vibrates in all directions perpendicular to the direction of propagation. If a snapshot is taken at a particular instant of time, different parts of the beam will have $\vec{E}$ vectors vibrating with different amplitudes and phases at different angles to each other, but all in a plane perpendicular to the direction of propagation. In the most common convention used in optics, the wave travels in the $+z$ direction in a right hand coordinate system and the $\vec{E}$ vectors are all vibrating at various angles in the $x-y$ plane. The angle of vibration is measured from the positive x axis in a counterclockwise direction when the observer is looking against the direction of propagation of the light beam.

For linearly polarized or plane polarized light, if a snapshot of a light beam is taken at a particular instant, the $\vec{E}$ vector will be vibrating at a certain angle in the $x-y$ plane. As time (or position on the traveling wave) varies, the amplitude of the $\vec{E}$ vector will vary in a sinusoidal manner, but the vibration will remain at the same angle in the $x-y$ plane. As an example, the real part of the electric vector of a linearly polarized beam that is vibrating in the $+x$ and $-x$ directions and traveling in the $+z$ direction is given by the relation:

$$\vec{E}_x(z,t) = \hat{\imath} E_0 \cos(kz - \omega t) \qquad [1]$$

where t is the time, $\hat{\imath}$ is a unit vector in the $+x$ direction, E_0 is the amplitude of the vibration, $\vec{k}$ is the propagation vector in the direction the wave is traveling, i.e., the z direction (its magnitude is $2\pi/\lambda$), and $\omega = 2\pi f$ where f is the vibration frequency of the wave. In free space, $\omega = 2\pi c/\lambda$ where c is the velocity of light and λ is the wavelength of the vibration.

Light can also be circularly or elliptically polarized. Circularly polarized light is produced by adding the electric vectors of two waves, each having the same amplitude but which are 90° out of phase; the resulting vibration sweeps out a circle in the x–y plane. When the first wave is vibrating in the $+x$ and $-x$ directions (eqn [1]), the second wave is vibrating in the $+y$ and $-y$ directions:

$$\vec{E}_y(z,t) = \hat{\jmath} E_0 \sin(kz - \omega t) \qquad [2]$$

and is added to the first wave. The resultant wave is the sum of eqns [1] and [2]:

$$\vec{E} = E_0[\hat{\imath} \cos(kz - \omega t) + \hat{\jmath} \sin(kz - \omega t)] \qquad [3]$$

The direction of vibration of this wave will rotate in a circle as either the time increases or as the distance along the wave increases, but the amplitude of the vibration will not change. As time increases, the vibration will make a circle in the clockwise direction (to negative angles). This light is defined to be right circularly polarized. If the + sign between the two parts of eqn [3] is changed to a minus sign, as time increases, the vibration will make a circle in the counterclockwise direction (to positive angles) and the light is now defined to be left circularly polarized. These definitions are for conventional (traditional) optics. However, the opposite definitions with right (left) circularly polarized light defining circles in the counterclockwise (clockwise) direction are also in use. In modern physics, there is still another convention that defines right (left) circularly polarized light as having negative (positive) helicity.

Right and left elliptically polarized light beams have the same angle conventions as for circularly polarized beams but are produced by adding two electric vectors that have different amplitudes. In eqns [1] and [2], the amplitude terms will be, for example, E_1 and E_2 instead of E_0 and eqn [3] can no longer be used. There is now a major axis and a minor axis of the ellipse. If $E_1 > E_2$, the major axis will be along the x axis; for $E_1 < E_2$, the major axis will coincide with the y axis.

The preceding discussion has dealt entirely with the electric vector of the electromagnetic field. However, one cannot observe the $\vec{E}$ vector. The irradiance (energy per unit area per unit time), $\vec{E}\vec{E}^*$, is what can be observed visually and measured by electronic detectors. Thus, measurements of the polarization are irradiance measurements. Light transmitted by a polarizer is called the transmittance of the polarizer; similarly, light reflected from a polarizer is called the reflectance of the polarizer.

One of the most important parts of the subject of polarization is how to produce linearly polarized light starting with unpolarized light. This is done by using polarizers, as discussed in the section on polarizers below. Certain materials have special properties that make them able to polarize light. Depending on the application, different kinds of polarizers are preferred. Optics textbooks by Hecht and Guenther discuss the most important polarizers and two articles by Bennett describe many kinds of polarizers including special ones (see the Further Reading at the end of this article for full references). Only the basic principles will be described here.

Sunlight scattered by air molecules in the atmosphere (Rayleigh scattering) is also partially linearly polarized. The air molecules act like tiny dipoles and vibrate when they absorb sunlight. They emit radiation that is polarized in certain directions relative to the vibration direction. When the viewer is at a 90° angle with respect to the sun, the polarization of the skylight is a maximum. Rayleigh scattering is the subject of several books and will not be further discussed here.

Retarders are used to change linearly polarized light into circularly or elliptically polarized light and compensators, which are a form of retarders, can analyze an unknown type of polarized light and determine its composition. They are discussed below.

Polarimetry and ellipsometry are closely related techniques that are used to determine the optical properties of a material by shining a known type of polarized light on the material at non-normal incidence and analyzing the polarization properties of the light after it has been reflected from the material. These subjects are treated in other articles in this encyclopedia and in several references at the end of this article.

Changes can be produced in the optical properties of some materials by applying an electric field, a magnetic field, an acoustic field, or another form of variable pressure. The materials changed in these ways are said to be electro-optic, magneto-optic, or piezo-optic. The changes in the optical properties modify some parameter of a light wave passing through a material or reflecting from it.

The amplitude, phase, frequency, polarization, or direction of the light wave can be modified. In this article, we are only concerned with modifications that produce changes in the polarization; these are discussed towards the end of this article.

Matrix methods have been developed to handle problems involving polarization and there is also a visual representation of the matrix algebra that is based on the Poincaré sphere. Both topics are covered at the end of this article.

Polarizers

Basic Relations for Polarizers

A linear polarizer is anything which, when placed in an incident unpolarized beam, produces a beam of light whose electric vector is vibrating primarily in one direction with only a small component vibrating in the direction perpendicular to it. The transmittance T of the linear polarizer is

$$T = \tfrac{1}{2}(T_1 + T_2) \qquad [4]$$

where T_1, the principal transmittance of the polarizer, is $\gg T_2$, the transmittance of the polarizer at 90° to the principal transmittance. Thus, a perfect polarizer would transmit only 50% of an incident unpolarized beam.

If a linear polarizer is placed in a linearly polarized beam and is rotated about an axis parallel to the beam direction, the transmittance will vary between a maximum value T_1 and a minimum value T_2 according to the law:

$$T = (T_1 - T_2)\cos^2\theta + T_2 \qquad [5]$$

where θ is the angle between the plane of vibration of the principal transmittance and the plane of vibration of the electric vector in the incident beam.

The extinction ratio ρ_P of a polarizer is defined as

$$\rho_P = \frac{T_2}{T_1} \qquad [6]$$

and the degree of polarization of a polarization P is

$$P = \frac{T_1 - T_2}{T_1 + T_2} \qquad [7]$$

When two identical polarizers are placed in an unpolarized beam, and the directions of their principal transmittances, T_A and T_B, are inclined at an angle θ to each other, the transmittance of the pair will be

$$T_\theta = \tfrac{1}{2}(T_1^2 + T_2^2)\cos^2\theta + T_1T_2\sin^2\theta \qquad [8]$$

Thus, when the directions of the principal transmittances are aligned, $T_{\parallel} = \frac{1}{2}(T_1^2 + T_2^2)$, and when they are perpendicular, $T_{\perp} = T_1T_2$.

Birefringent Materials (Calcite)

The majority of high-quality polarizers are made from calcite. This is a birefringent (doubly refracting) crystalline material that is uniaxial (i.e., there is one preferred direction in the crystal). A birefringent material acts differently for light going in different directions through the crystal. For example, if an unpolarized light beam passes through the crystal in a certain direction, it will be split into two spatially separated beams that are parallel but are linearly polarized at right angles to each other. A uniaxial crystal has an optic axis (i.e., a certain direction in the crystal). When light rays travel parallel to the optic axis, they travel at the same velocity and there is no difference between them. When light passes through the crystal in other directions, the ray whose vibration direction is perpendicular to the optic axis is governed by the ordinary laws of geometrical optics (the same as for isotropic materials) and is called the ordinary ray. The ray whose vibration direction is parallel to the optic axis does not follow the normal geometrical optics laws and is called the extraordinary ray. One ray travels faster than the other, so there is a phase retardation for one ray relative to the other. This is the principle of a retarder or retardation plate (see the next section).

Calcite is a negative uniaxial crystal which means that the refractive index for the ordinary ray is larger than the refractive index for the extraordinary ray. When the ordinary ray enters a block of calcite from air at non-normal incidence, it is bent more than the extraordinary ray.

Calcite can be easily cleaved along three distinct planes, making it possible to produce rhombs of the form shown in Figure 1. The optic axis, going in the HI direction, makes equal angles with all three faces at point H. Any plane, such as DBFH, which contains the optic axis and is perpendicular to the two opposite faces of the rhomb ABCD and EFGH is called a principal section. If the plane of incidence of light on the rhomb coincides with a principal section, the light entering the crystal will be split into two components polarized at right angles to each other which travel in slightly different directions and leave the crystal as two beams slightly displaced but parallel to each other.

The large birefringence of calcite and its excellent transmission through the visible spectral region and into the ultraviolet and infrared regions has made it possible to make excellent high extinction ratio polarizers with different designs. Some of these are shown in Figure 2. There are two main types: Glan types with rectangular shapes and Nicol types with rhombohedral shapes. The polarizers are made of two pieces of calcite cemented together. Glan types have their optic axes in the plane of the entrance face. In the Nicol types, the principal section is perpendicular to the entrance face, but the optic axis is neither parallel nor perpendicular to the face. The two halves of conventional polarizing prisms are cemented together with cement that has a refractive index intermediate between the ordinary and extraordinary refractive indices. This enables one ray (generally the extraordinary, or *e* ray) to be transmitted and the other to be reflected at the cut, so that only one ray exits from the prism in the direction of the incoming ray. The Glan types are also used without cement with only an air space between the two halves. They can be used at shorter wavelengths in the ultraviolet where the cement absorbs. The extinction ratio can be very high for air-spaced prisms. For example, for a Glan–Foucault prism (an air-spaced Glan–Thompson prism, Figure 2), the extinction ratio can be better than 1×10^{-5} and the prism is usable from about 0.214 μm in the ultraviolet to 2.3 μm in the infrared. However, air-spaced polarizers have very small field angles, so they are mainly used with laser sources where the beam is parallel.

The extreme paths of light through a cemented Glan–Thompson prism are shown in Figure 3. This prism has a length that is three times the width of the entrance aperture (i.e., an *L*/*A* ratio of 3). The optic axis is perpendicular to the plane of incidence which is in the plane of the paper. In the first half of the polarizer, the paths of the ordinary and extraordinary rays, both of which follow the conventional law of refraction (Snell's Law, eqn [8] above) nearly coincide. Ray A is incident on the entrance face of the polarizer at an angle such that the angle of incidence on the cut is the smallest angle for which the *o* ray is totally internally reflected. Ray B is incident at an angle such that the angle of refraction in the first half of the prism is essentially equal to the cut angle, S, so that the *e* ray just passes through the cut. The field angle of the polarizer is twice the smaller of angles θ_A and θ_B. Thus, all rays having angles of incidence between rays A and B will be polarized



Figure 1 Schematic representation of a rhombohedral calcite crystal showing the angles between faces. The optic axis passes through corner H and point I on side BF. (Reproduced with permission from Bennett JM (1995) Polarizers. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 3. New York: McGraw-Hill, Inc.)



Figure 2 Types of polarizing prisms. Glan types: (a) Glan-Thompson, (b) Lippich, and (c) Frank-Ritter; Nicol types: (d) conventional Nicol, (e) Nicol, Halle form, and (f) Hartnack-Prazmowsky. The optic axes are indicated by the double-pointed arrows. (Reproduced with permission from Bennett JM (1995) Polarizers. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 3. New York: McGraw-Hill, Inc.)

when exiting the prism. The paths of similar rays can be traced through the other prism designs.

In addition to conventional polarizing prisms, there are also polarizing beamsplitter prisms and Feussner prisms. In polarizing beamsplitter prisms, the two beams that are polarized at right angles to each other both emerge from the prism but are separated spatially. Figure 4 shows a diagram of several types of polarizing beamsplitter prisms and Figure 5 shows the paths of rays through side views of these prisms.

A Feussner prism is made of isotropic material but the film separating the two halves is birefringent. These prisms have the advantage that much less birefringent material is required but they have a more limited wavelength range when calcite or sodium nitrite (another birefringent material) is used because the transmitted ordinary ray has a shorter transmission range than the extraordinary ray which is transmitted by the conventional and air-spaced polarizing prisms.



Figure 3 Extreme rays (A and B) that can pass through a cemented Glan-Thompson prism. Both rays change to ordinary and extraordinary rays in the calcite. Both ordinary rays are reflected at the boundary between the two halves of the prism and the extraordinary rays exit in the directions indicated. Rays entering the prism between rays A and B would be transmitted by the prism. The field angle of the prism is twice the smaller of the two angles of incidence (ray A).

Dichroic Absorbers

A dichroic material is one that absorbs light polarized in one direction more strongly than light polarized at right angles to that direction. Dichroic materials are different from birefringent materials because the latter usually have negligible absorption coefficients for both the ordinary and extraordinary rays. Stretched polyvinyl alcohol sheets treated with absorbing dyes or polymeric iodine are the most common type of dichroic absorbers and are primarily sold under the tradename Polaroid. These polarizers do not have as good an extinction ratio as the calcite prism polarizers (see above), but they are inexpensive, come in large sizes, are easily rotated, and produce negligible beam deviation. Also, they are thin, lightweight, and can be made in any desired shape. One of their main advantages is that they are insensitive to the degree of collimation of the beam and can be used in strongly convergent or divergent light.



Figure 4 Three-dimensional views of various types of polarizing beamsplitter prisms: (a) Rochon; (b) Sénarmont; (c) Wollaston; (d) Foster (shaded face is silvered); and (e) beamsplitting Glan-Thompson. (Reproduced with permission from Bennett JM (1995) Polarizers. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 3. New York: McGraw-Hill, Inc.)



Figure 5 Side views of the polarizing beamsplitter prisms in Figure 4. The directions of the optic axes are indicated by the dots and the heavy double-pointed arrows. When the Foster prism is used as a microscope illuminator, the source, specimen, and eyepiece are in the positions indicated. (Reproduced with permission from Bennett JM (1995) Polarizers. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 3. New York: McGraw-Hill, Inc.)

Depending on the density and type of absorbing dye used to make the polarizer, the transmission can be maximized for the visible or near infrared spectrum. The extinction ratio of the Polaroid HN-22 sheet compares favorably with that of the Glan–Thompson prisms throughout the visible spectral region, but the transmission of the Glan–Thompson prism is superior. As the dichroic polarizer transmission increases, the extinction ratio becomes worse. Transmission and extinction ratio curves for various types of dichroic polarizers are shown in Bennett JM (1995) Polarizers. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 3. New York: McGraw-Hill, Inc.

A wire grid polarizer is another kind of dichroic absorber. It is made of a series of equally spaced conducting bars or wires that are either free standing or deposited onto a transparent substrate (backing plate). Energy that is polarized parallel to the length of the bars is absorbed out of the incoming wave by inducing oscillations in the electrons in the metal. Thus, only light polarized perpendicular to the bars will be transmitted. In order to have an appreciable degree of polarization, the wavelength must be at least twice the spacing between grids in the polarizer. Because of the difficulty of making wire grids with small enough spacings, these polarizers are limited to the mid- and long-wavelength infrared spectral region, beyond about 5 μm. The polarizer will have the best extinction ratio if the substrate has a low refractive index; if a high refractive index substrate such as silicon or germanium is used, it must be covered with an antireflection coating before the grid is deposited.

Most of the wire grid polarizers have been used with microwaves, so the theory is in the form for transmission lines. Similar transmission line theory has been applied to infrared polarizers in the form of bars and wires.

Reflection and Transmission

Light can be polarized by reflecting it from the flat surface of a material inclined at non-normal incidence to the light beam or by transmitting it through a transparent plate at non-normal incidence. These polarizers work because light has different reflectances when the electric vector is linearly polarized parallel and perpendicular to the plane of incidence. The plane of incidence contains both the incoming light beam (incident beam) and the reflected light beam. The angles for both the incident and reflected light beams are measured relative to an axis perpendicular to the surface (the surface normal). The reflection coefficients are given by the Fresnel equations and, for nonabsorbing materials, are:

$$R_s = r_s^2 = \frac{\vec{E}_s^2(\text{reflected})}{\vec{E}_s^2(\text{incident})} = \frac{\sin^2(\theta_0 - \theta_1)}{\sin^2(\theta_0 + \theta_1)} \qquad [9]$$

$$R_p = r_p^2 = \frac{\vec{E}_p^2(\text{reflected})}{\vec{E}_p^2(\text{incident})} = \frac{\tan^2(\theta_0 - \theta_1)}{\tan^2(\theta_0 + \theta_1)} \qquad [10]$$

where R_s and R_p are called the reflectances (previously called the intensity reflection coefficients), and r_s and r_p are the amplitude reflection coefficients. $\vec{E}_s$ ($\vec{E}_p$) is the incident or reflected electromagnetic wave vibrating perpendicular (parallel) to the plane of incidence and θ_0 and θ_1 are the angles of incidence and refraction, respectively. The angle of refraction is the angle of the light beam in the material, measured from the surface normal. For a nonabsorbing material, it can be obtained in terms of the refractive index n_1 of the material from Snell's Law:

$$\frac{\sin\theta_0}{\sin\theta_1} = \frac{n_1}{n_0} \tag{11}$$

where n_0 and n_1 are the refractive indexes of the incident medium (usually air with $n_0 = 1$) and the material. Sometimes the refractive index of the material is expressed as a ratio measured relative to the refractive index of the incident medium: $n = n_1/n_0$. The reflectances of absorbing materials are similar to eqns [9]–[11] but involve complex refractive indexes and angles of refraction.

Figure 6 shows curves for R_s and R_p as a function of angle of incidence for four nonabsorbing materials that have different refractive indexes. In all cases the reflectance is higher for the *s* component than for the *p* component except at 0° and 90° angles of incidence where they are the same. At the so-called Brewster angle, θ_B, $R_p = 0$, $\tan\theta_B = n_1/n_0$, and incident unpolarized light is now completely linearly polarized perpendicular to the plane of incidence (s-polarized light). Note that high refractive index materials produce more intense polarized beams (i.e., have higher reflectances) than low refractive index materials.



Figure 6 Reflectance of light polarized parallel R_p and perpendicular R_s to the plane of incidence from materials of different refractive index n as a function of angle of incidence: (a) $n = 1.5$ (alkali halides in the ultraviolet, glass (approximately) in the visible, and sheet plastics in the infrared), (b) $n = 2.0$ (AgCl in the infrared), (c) $n = 2.46$ (Se in the infrared), and (d) $n = 4.0$ (Ge in the infrared). The Brewster angle θ_B (at which R_p goes to 0) and the magnitude of R_s at θ_B are also indicated. (Reproduced with permission from Bennett JM (1995) Polarization. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. I, chap. 5. New York: McGraw-Hill, Inc.)



Figure 7 (a) Reflectance R_s and (b) extinction ratio R_p/R_s for materials of different refractive index at angles near the Brewster angle θ_B. A single surface of the material is assumed. (Reproduced with permission from Bennett JM (1995) Polarization. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. I, chap. 5. New York: McGraw-Hill, Inc.)

Figure 7 shows the reflectances and extinction ratios for materials having different refractive indexes. Each curve is for a single reflection. Since plates have two surfaces, there will be two reflections from an actual reflection polarizer so the reflectance and extinction ratios will increase. If the plates are thick, the reflection from the back surface of the plate will be displaced from the reflection from the front surface of the plate. A reflection polarizer is normally used close to the Brewster angle because a high degree of polarization (i.e., a very small extinction ratio) is desired. Because the extinction ratio changes rapidly for angles of incidence close to the Brewster angle, the incident beam must be well collimated to obtain a high degree of polarization. A main disadvantage of reflection polarizers is that the reflected beam is no longer parallel to the incident beam and two additional reflections are required to align the beam.

Light transmitted through a plate will only be partially linearly polarized at any angle of incidence including the Brewster angle because both s- and p-components are partially transmitted. Transmission polarizers are thus made of several plates to increase the degree of polarization. Figure 8 shows the transmittance and extinction ratio for a stack of four plane parallel plates assuming multiple incoherent reflections within each plate and no reflections between plates. At the Brewster angle the p-transmittance is theoretically 1 (assuming that there is no absorption within the material) but the extinction ratio greatly depends on the refractive index of the material. A stack of low refractive index plates ($n = 1.5$) has a poor extinction ratio, while a pile of high refractive index plates ($n = 4.0$) has a much better extinction ratio. The plates are often inclined at small angles to each other so the light multiply reflected between plates (which decreases the polarization) is removed from the transmitted beam. The sides of each plate are plane parallel to increase the polarization, but the plates are too thick for the amplitudes of the multiple internally reflected beams to add or subtract. If the amplitudes of the beams could be added, there would be interference effects and the transmittance would vary with the thickness of each plate and with the wavelength. These are so-called interference polarizers and are mentioned below.

Transmission polarizers do not have the angle deviation problem of the reflection polarizers, but the transmitted beam may be slightly displaced parallel to the incident beam if the plates are thick. The main problem with transmission polarizers is that the light is not completely polarized even with several plates in a stack. If the plates are slightly absorbing, the transmission of the polarizer is reduced.

Miscellaneous Types

There are numerous other types of polarizers that mostly use thin films. Interference effects in thin films can increase the polarization efficiency at certain wavelengths depending on the thicknesses of the films and the design of the multilayer coating. Many of the applications involve non-normal incidence designs. For example, a single high refractive index film or a multilayer coating evaporated onto a low refractive index substrate increases the degree of polarization of reflection and transmission polarizers. Polarizing beamsplitters also use multilayer dielectric coatings. Free-standing films of different thicknesses were formerly used for infrared polarizers before wire grid polarizers became available.

Dichroic absorbers have been made from two-phase lamelar eutectics of thin needles of a conducting material embedded in a transparent matrix. Thin sheets of pyrolytic graphite material also act



Figure 8 (a) Transmittance and (b) extinction ratio of four plane-parallel plates of refractive index n as a function of angle of incidence, for angles near the Brewster angle. Assumptions are multiple reflections but no interference within each plate and no reflections between plates. (Reproduced with permission from Bennett JM (1995) Polarization. In Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. I, chap. 5. New York: McGraw-Hill, Inc.)

as dichroic absorbers. There are also numerous miniature polarizer designs for fiber optics and nanotechnology applications.

Retarders or Retardation Plates

Retarders, or retardation plates, are devices that can change linearly polarized light into circularly or elliptically polarized light. They can also rotate the plane of polarization of linearly polarized light. A retardation plate is made from a uniaxial crystal that has an optic axis (as discussed above); the light travels in a direction perpendicular to the optic axis, as described below and shown in Figure 9. The ordinary and extraordinary rays travel at different velocities through the crystal depending on their refractive indexes: $n = c/v$, where c is the velocity of light in a vacuum and v is the velocity of light in the material. The larger the refractive index, the slower is the velocity of light in the material. The ordinary ray with a refractive index n_o and the extraordinary ray with a refractive index n_e have mutually perpendicular vibration directions. If the ray has a vibration direction at another azimuth in the crystal, the refractive index is intermediate between n_o and n_e. For a positive uniaxial crystal $n_e > n_o$ so the extraordinary ray travels slower than the ordinary ray through the crystal. Thus, the designation 'fast axis' is often used for the ordinary ray and 'slow axis' is used for the extraordinary ray, as shown in Figure 9. In a negative uniaxial crystal, $n_e < n_o$, i.e., the velocities along the two axes are reversed.

Because there is a velocity difference between the ordinary and extraordinary rays traveling through a uniaxial crystal, they get out of phase. Depending on their velocities and the optical thickness of the material (the refractive index times the physical thickness), the addition of their amplitudes results in a wave whose vibration direction is either: (a) perpendicular to the original vibration direction; (b) rotates in a circle (right or left circularly polarized light); or (c) rotates in an ellipse (right or left elliptically polarized light). The path difference N between two rays in the crystal, measured in terms of the wavelength of the light, is $N\lambda = \pm d(n_e - n_o)$, where d is the physical thickness of the material. The corresponding phase difference δ between the two rays is $\delta = 2\pi N = \pm(2\pi d/\lambda)(n_e - n_o)$. The quantity N is important because if beams of light vibrating along the fast and slow axes of a crystal get out of step by one quarter of the wavelength of the light, the device is called a quarter wave (or $\lambda/4$) retardation plate, or simply a quarter-wave plate. There are also half-wave ($\lambda/2$) plates that rotate the plane of polarization, and full-wave (λ) plates that rotate the plane of polarization through 180°. If light passes through a full-wave plate, theoretically it is indistinguishable from the original beam. However, materials are normally temperature sensitive so that as the temperature changes, the retardation is no longer exactly one wave, but may be slightly less than or greater than one wavelength. Other thicknesses of retardation plates produce elliptically polarized light.


Optic axis and vibration of extraordinary ray (slow axis)
Vibration direction of ordinary ray (fast axis)
Line of sight

Figure 9 Light incident normally on the front surface of a retardation plate showing the vibration directions of the ordinary and extraordinary rays. In a positive uniaxial crystal, the fast and slow axes are as indicated in parentheses; in a negative uniaxial crystal, the two axes are interchanged. (Adapted with permission from Bennett JM (1995) Polarization. In Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. I, chap. 5. New York: McGraw-Hill, Inc.)

Figure 10 shows what happens to a beam of linearly polarized light when the axis of vibration is at 45° to the fast and slow axes of a positive



Figure 10 State of polarization of a light wave after passing through a crystal plate whose retardation is indicated in fractions of a wavelength (phase retardation $2\pi/\lambda$ times these values) and whose fast axis is indicated by the double arrow. In all cases the incident light is linearly polarized at an azimuth of 45° to the direction of the fast axis. (Adapted with permission from Bennett JM (1995) Polarization. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. I, chap. 5. New York: McGraw-Hill, Inc.)



Figure 11 State of polarization of a light wave after passing through a $\lambda/4$ plate (whose fast axis is indicated by the double arrow) for different azimuths of the incident linearly polarized beam. (Adapted with permission from Bennett JM (1995) Polarization. In Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. I, chap. 5. New York: McGraw-Hill, Inc.)

uniaxial crystal. The fast axis is in the horizontal direction, the same as in Figure 9.

The main purpose of a quarter-wave plate is to change linearly polarized light into circularly polarized light. However, as Figure 11 shows, the state of polarization of the light will be quite different depending on the orientation of the plane of polarization of the incident beam relative to the fast axis of the quarter-wave plate.

A half-wave plate is used to rotate the plane of polarization of a linearly polarized beam. The plane of polarization is always rotated through an angle that is twice the angle the initial plane of polarization makes with the fast axis of the uniaxial crystal. A linearly polarized beam always remains linearly polarized.

Retardation plates are often made of mica, stretched polyvinyl alcohol, or crystal quartz, although they can also be made of other stretched plastics, sapphire, magnesium fluoride, and other materials.

Variable Retardation Plates and Compensators

Variable retardation plates are devices whose retardation can be varied in a variety of ways. They can be used to modulate or vary the phase of a beam of linearly polarized light or to analyze a beam of unknown polarization (often elliptically polarized light) such as might be produced by transmission through a birefringent material or by reflection from a metal or film-covered surface. The term compensator is often applied to a variable retardation plate since it can be used to compensate for the phase retardation produced by a material. Common types of compensators include the Babinet and Soleil compensators, in which the total thickness of a birefringent material in the light path is changed, the Sénarmont compensator which consists of a fixed quarter-wave plate and rotatable analyzer to compensate for varying amounts of ellipticity in a light beam, and tilting-plate compensators, which change the thickness of birefringent material in the light beam by changing the angle of incidence. Electro-optic and piezo-optic modulators can also be used as high-frequency variable retardation plates since their birefringence can be changed by varying the electric field or pressure (see next section).

The Babinet compensator, shown schematically in Figure 12 consists of two crystal quartz wedges, each with its axis in the plane of the face but with the axes at right angles to each other. One wedge is stationary, and the other can be moved in the direction indicated by the arrow, so that the total amount of quartz through which the light passes can be varied. The total retardation is proportional to the difference in thickness between the two wedges. This type of compensator was used extensively when the light source was a vertical slit and visual measurements were made of the state of polarization of a beam. However the bands representing different phase retardations were too narrow to be used effectively with a photoelectric detector, so the Babinet compensator was replaced by a Soleil compensator (Figure 13). This device, sometimes called a Babinet–Soleil compensator, is similar to the Babinet compensator except that the field of view has a uniform tint if the compensator is constructed correctly. This is because the ratio of the thicknesses of the two crystal quartz blocks (a movable wedge and a fixed wedge attached to a plate with the two axes perpendicular to each other) is the same over the entire field. The Soleil compensator will produce light of varying ellipticity depending on the position of the movable wedge. It is used in the same way as a Babinet compensator with the uniformly dark field of the Soleil compensator corresponding to the black zero-retardation band in the Babinet compensator.

It is sometimes necessary to accurately measure the azimuth of a beam of linearly polarized light using a photoelectric detector with a rotatable analyzer (i.e., a polarizer) directly in front it. The obvious method is to rotate the analyzer until the detector signal is a minimum and then read the analyzer angle, which equals the extinction angle (perpendicular to the azimuth of the linearly polarized beam). However, the



Figure 12 Arrangement of a Babinet compensator, polarizer, and analyzer for measuring the retardation of a sample. The appearance of the field after the light has passed through the compensator is shown to the left of the sample position. Retardations are indicated for alternate regions. After the beam passes through the analyzer, the field is crossed by a series of dark bands, one of which is shown to the left of the analyzer. (Adapted with permission from Bennett JM (1995) Polarizers. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 3. New York: McGraw-Hill, Inc.)

angle can be determined more precisely if the analyzer is offset by a small angle from the extinction angle and the transmittance noted. Then the analyzer is offset by a small angle on the other side of the extinction angle at the angle where the transmittance is the same. One half the difference between these two azimuthal angles gives a more accurate value of the extinction angle than can be obtained by measuring it directly.

Before the days of photoelectric detectors, half-shade devices were extensively used to determine the azimuth of a linearly polarized beam. The device consisted of two polarizers with their axes inclined at a small angle to each other. As the device was rotated, one part of the field became darker and the other part became lighter. At the match position, both parts of the field appeared equally bright. There were a variety of these devices as well as ellipticity half-shade devices that could detect very small amounts of ellipticity in a nominally linearly polarized beam and hence could verify when a compensator had completely converted elliptically polarized light into linearly polarized light.

Electro-Optic, Magneto-Optic, and Piezo-Optic Devices

The state of polarization of light can be rapidly altered by passing it through a material that has electro-optic, magneto-optic or piezo-optic properties. The voltage, magnetic field, or pressure are varied to make the material birefringent (see above). Some materials are isotropic without the applied field, i.e., the refractive index is the same in all directions. Other materials have an optic axis



Figure 13 Arrangement of a Soleil compensator, polarizer, and analyzer for measuring the retardation of a sample. The appearance of the field after the light has passed through the compensator is shown to the left of the sample position. After the beam passes through the analyzer, the field appears as one of the shades of gray shown to the left of the analyzer. (Adapted with permission from Bennett JM (1995) Polarizers. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 3. New York: McGraw-Hill, Inc.)

(uniaxial materials) or two optic axes (biaxial materials). In these cases, the applied field creates further asymmetries in the material.

The most common electro-optic, magneto-optic and piezo-optic effects are the Pockel's effect (depending on the electric field), the Kerr effect (depending on the square of the electric field), the Faraday effect (depending on the magnetic field), the Cotton–Mouton and Voigt effects (depending on the square of the magnetic field), and stress birefringence or the photoelastic effect (depending on pressure changes). These effects are shown in Table 1 along with order of magnitude strengths needed to produce changes in the refractive index, and materials that most strongly exhibit the effects. The mathematical descriptions of the effects involve tensors and are too involved to present here. However, simple physical descriptions will be given.

If a varying electric field acts on an electro-optic material, electrons, ions, or permanent dipoles in the material are made to reorient, inducing an electric polarization. The induced polarization creates birefringence that modifies the optical polarization of a light beam passing through the material. The electric field strength determines how the polarization is changed (see Figure 10).

Linearly polarized light passing through a magneto-optic material will be rotated in a direction parallel to the direction of the applied magnetic field. This phenomenon, called the Faraday effect, or Faraday rotation, is similar to what happens in optically active materials (see the next paragraph) except that the Faraday effect depends on the direction of the magnetic field, but not on the direction the light is traveling.

There are naturally optically active materials such as camphor, nicotine, sugar solutions, and crystal quartz that can rotate the plane of linearly polarized light passing through the material. For example, the Si–O bonds in crystal quartz form a helical path around the optic axis. This crystal structure interacts with an incoming linearly polarized beam traveling parallel to the optic axis and rotates it in a clockwise direction. A 1 mm-thick piece of quartz will rotate a

Table 1 Electro-optic, magneto-optic, and piezo-optic effects

Effect	*Device*	*Effect proportional to*	*Strength (Δn)*	*Materials*
Pockels (electro-optic)	Pockels cell	E	$10^{-12}E$	$BaTiO_2$, $LiNBO_3$
Kerr	Kerr cell	E^2	$10^{-19}E^2$	Nitrobenzene, Benzonitrile
Faraday (magneto-optic)	Faraday rotation	H	$10^{-14}H$	Zns, GaAs, CS_2
Cotton–Mounton	[a]	H^2	$10^{-25}H^2$	Chloroform, acetone
Photoelastic effect; stress birefringence	[b]	Pressure	–	Fused silica, polystyrene, Ge, KDP, ruby

[a] Too small to be of technological importance.

[b] Depends on the mounting or the processing of the material.

Adapted with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley and Sons.

linearly polarized beam by 21.7°. Other materials have asymmetric structures that have mirror images. A mirror image structure cannot be obtained by simply rotating the group of atoms in space. These materials are also optically active. The amount of rotation produced by an optically active material is proportional to the thickness (optical density) of the material that the light passes through. Dextrose (a form of glucose) and levulose (also known as fructose) rotate the plane of linearly polarized light in clockwise and counterclockwise directions, respectively. Many other organic molecules have D- (right handed, dextro-rotary) and L- (left handed, levo-rotary) mirror image forms.

An isotropic material can become anisotropic when stress or an induced strain is applied because of an elasto-optic interaction known as stress birefringence, or the photoelastic effect. This effect is usually bad because it reduces the performance of optical components and devices by introducing phase distortions caused by improper mounting or unequal thermal expansion between the mounts and components. Another source of distortion is strain that has been frozen into optical components during manufacture. French curves are excellent examples that show colored strain birefringence patterns when viewed between crossed polarizers. In one application, strain birefringence has been used constructively to produce a variable phase retarder made from crystal quartz and fused silica. A block of electro-optic crystal quartz, is cemented to a block of isotropic fused silica. When a variable electric field is applied to the crystal quartz, its length changes at the resonant frequency of the block. This produces strain in the fused silica block which in turn produces a variable retardation of light passing through the strained fused silica. Depending on the magnitude of the varying electric field, the device can act like a variable quarter-wave plate, a variable half-wave plate, or have other applications.

Matrix Methods for Computing Polarization

An optical system containing various polarizing and retarding devices can be modeled using matrices. In general, there is an incident beam (in matrix form), that has some state of polarization. It interacts with a device called an instrument (also in matrix form) that alters the state of polarization, so that the exiting beam (a third matrix, the product of the first and second matrices) has another state of polarization. There can be more than one instrument matrix acting on the same incident matrix to produce the final matrix. The two most common matrix methods are the Mueller calculus and the Jones calculus.

There is also a visual representation of this process, a Poincaré sphere, on which vectors represent different states of polarization. The polarization instrument moves the vector representing the incident polarization around the sphere in a prescribed manner. The vectors are called Stokes vectors and are used in the Mueller calculus. The various states of polarization are represented on the Poincaré sphere as follows: The equator represents various forms of linear polarization, the poles represent right- and left-circular polarization, and other points on the sphere represent elliptically polarized light. Every point on the sphere corresponds to a different polarization form. The radius of the sphere represents the incident irradiance of the light beam (which is usually assumed to be unity). The effects of various polarization instruments are determined by displacements on the sphere. Partially polarized light or absorption may be dealt with approximately by ignoring the irradiance factor, since the state of polarization is generally the quantity desired. The Poincaré sphere is most useful for visualizing problems involving nonabsorbing materials, various polarization instruments including polarizers, retarders, compensators, half-shade devices, and depolarizers, and has also been applied to ellipsometric problems and stress-optical measurements.

The Poincaré sphere is used with Stokes vectors, which are often designated S_0, S_1, S_2, and S_3. S_0 is the incident irradiance of the light beam, corresponding to the radius of the Poincaré sphere. S_1 is the difference in irradiances between the horizontal and vertical polarization components of the beam; for example, when S_1 is positive, the preference is for horizontal polarization. S_2 indicates preference for $+45°$ or $-45°$ polarization depending on whether it is positive or negative, and S_3 gives the preference for right or left circular polarization. Thus, the Stokes vectors S_1, S_2, and S_3 are simply the three Cartesian coordinates of a point on the Poincaré sphere. S_1 and S_2 are perpendicular to each other in the equatorial plane, and S_3 points toward the north pole of the sphere. Any state of polarization of a light beam can be specified by these three vectors. The irradiance vector S_0 is related to the other three by the relation $S_0^2 = S_1^2 + S_2^2 + S_3^2$ when the beam is completely polarized. If the beam is partially polarized, $S_0^2 > S_1^2 + S_2^2 + S_3^2$.

In the Mueller calculus, the incident beam is represented by the four-component Stokes vector, written as a column vector. This vector has all real elements and gives information about irradiance properties of the beam. Thus it is not able to handle problems involving phase changes or combinations of two beams that are coherent. The instrument matrix is a 4×4 matrix with all real elements.

In the Jones calculus, the Jones vector representing the incident beam is a two-component column vector that generally has complex elements. It contains information about the *amplitude* properties of the beam and hence is well suited for handling problems involving the phases of light waves. However, it cannot handle problems involving depolarization, as the Mueller calculus can. The Jones instrument matrix is a 2×2 matrix whose elements are generally complex. The Jones calculus is well suited to problems involving a large number of similar devices arranged in series in a regular manner and makes it possible to obtain a result expressed explicitly in terms of the number of such devices. The Jones instrument matrix of a train of transparent or absorbing nondepolarizing polarizers and retarders contains no redundant information. The matrix contains four elements, each of which has two parts, so that there are a total of eight constants, none of which is a function of any other. The Mueller instrument matrix of such a train contains much redundancy; there are 16 constants but only 7 of them are independent. More information about the Poincaré sphere and the Mueller and Jones calculus is available in other references.

See also

Electromagnetically Induced Transparency. **Magneto-optics:** Faraday Rotation, CARS, ODMR, ODSR, Optical Pumping; Interband Magnetoabsorption, Cyclotron Resonance, Spin Flip Raman Scattering.

Further Reading

Auton JP (1967) Infrared transmission polarizers by photolithography. *Applied Optics* 6: 1023–1027.

Azzam, Rasheed MA and Bashara NM (1977) *Ellipsometry and Polarized Light*, chaps. 1 and 2. Amsterdam: North-Holland Publishing Co.

Azzam, Rasheed MA (1995) Ellipsometry. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 27. New York: McGraw-Hill.

Bennett JM (1995) Polarization. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. I, chap. 5. New York: McGraw-Hill.

Bennett M (1995) Polarizers. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 3. New York: McGraw-Hill.

Bohren CF and Huffman DR (1983) *Absorption and Scattering of Light by Small Particles*. New York: John Wiley.

Born M and Wolf E (1999) *Principles of Optics*, 7th edn, chap. 1. Cambridge: Cambridge University Press.

Chipman RA (1995) Polarimetry. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 22. New York: McGraw-Hill.

Clark JR (1956) New calculus for the treatment of optical systems. VIII. Electromagnetic theory. *Journal of the Optical Society of America* 46: 126–131.

Guenther RD (1990) *Modern Optics*. chaps. 2, 13, and 14. New York: John Wiley and Sons.

Hass M and O'Hara M (1965) Sheet infrared transmission polarizers. *Applied Optics* 4: 1027–1031.

Hecht E and Zajac A (1997) *Optics*, 3rd edn, chap. 8. Reading, MA: Addison-Wesley Publishing Co.

Jackson JD (1999) *Classical Electrodynamics*, 3rd edn, chap. 7. New York: John Wiley and Sons, Inc.

Jasperson SN and Schnatterly SE (1969) An improved method for high reflectivity ellipsometry based on a new polarization modulation technique. *Reviews of Scientific Instruments* 40: 761–767.

Kerker M (1969) *The Scattering of Light and Other Electromagnetic Radiation*. New York: Academic Press.

Kliger DS, Lewis JW and Randall CE (1990) *Polarized Light in Optics and Spectroscopy*, chaps. 1–5. San Diego: Academic Press.

Maldonado TA (1995) Electro-optic modulators. In: Bass M (ed.) *Handbook of Optics*, 2nd edn, vol. II, chap. 13. New York: McGraw-Hill, Inc.

Markuvitz N (ed.) (1951) *Waveguide Handbook*, pp. 218–229, 285–289. New York: McGraw-Hill Book Co.

Shurcliff WA (1962) *Polarized Light, Production and Use*. Cambridge, MA: Harvard University Press.

van de Hulst HC (1957) *Light Scattering by Small Particles*. New York: John Wiley.

Matrix Analysis

B D Guenther, Duke University, Durham, NC, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Hooke postulated, in the seventeenth century, that light waves must be transverse but his idea was forgotten. Young and Fresnel put forward the same idea in the nineteenth century and accompanied their postulation with a theoretical description of light based on transverse waves. Forty years later, Maxwell proved that light must be a transverse wave and that **E** and **H**, for a plane wave in an isotropic medium with no free charge and no currents, are mutually perpendicular and lie in a plane normal to the direction of propagation, **k**.

Convention requires that we use the electric vector to label the direction of the electromagnetic wave's polarization. The direction of the displacement vector is called the direction of polarization and the plane containing the direction of polarization and the propagation vector is called the plane of polarization. The selection of the electric field is not completely arbitrary, except in relativistic situations, when $v \approx c$, the interaction of the electromagnetic wave with matter will be dominated by the electric field.

Assume that a plane wave is propagating in the z-direction. In complex notation, the plane wave is given by

$$\tilde{\mathbf{E}} = \mathbf{E}_0\, e^{i(\omega t - \mathbf{k}\cdot\mathbf{r} + \phi)} = \mathbf{E}_0\, e^{i(\omega t - kz + \phi)} \qquad [1]$$

The procedure used to decompose an arbitrary polarization into components parallel to two axes of a Cartesian coordinate system, is a technique used extensively in vector algebra to simplify mathematical calculations. According to the mathematical formalism associated with this technique, the polarization is described in terms of a set of basis vectors, $\mathbf{e}_i$. An arbitrary polarization would be expressed as

$$\mathbf{E} = \sum_{i=1}^{2} a_i \mathbf{e}_i \qquad [2]$$

The set of basis vectors, $\mathbf{e}_i$, are orthonormal, i.e.:

$$\mathbf{e}_i \mathbf{e}_j^* = \delta_{ij} = \left\{ \begin{matrix} 1 & i = j \\ 0 & i \neq j \end{matrix} \right\} \qquad [3]$$

where we have assumed that the basis vectors could be complex. We mention this mathematical formalism because an identical formalism is encountered in a description of spin.

In a Cartesian coordinate system, the $\mathbf{e}_i$'s are the unit vectors **i**, **j**, **k**. The summation in eqn [2] extends over only two terms because the electromagnetic wave is transverse, confining **E** to a plane normal to the direction of propagation (according to the coordinate convention we have selected, the **E** field is in the x, y plane).

Polarization Ellipse

Following the formalism of eqn [2], a polarized wave can be written in terms of the x and y components of $\mathbf{E}_0$

$$\tilde{\mathbf{E}} = \mathbf{E}_{0x}\, e^{i(\omega t - kz + \phi_1)}\hat{\mathbf{i}} + \mathbf{E}_{0y}\, e^{i(\omega t - kz + \phi_2)}\hat{\mathbf{j}} \qquad [4]$$

We will use only the real part of **E** for manipulation, to prevent errors. We divide each component of the electric field by its maximum value, so that the problem is reduced to one of the following two sinusoidal varying unit vectors:

$$\begin{aligned} \frac{E_x}{E_{0x}} &= \cos(\omega t - kz + \phi_1) \\ &= \cos(\omega t - kz)\cos\phi_1 - \sin(\omega t - kz)\sin\phi_1 \\ \frac{E_y}{E_{0y}} &= \cos(\omega t - kz)\cos\phi_2 - \sin(\omega t - kz)\sin\phi_2 \end{aligned} \qquad [5]$$

When these unit vectors are added together, the resulting equation will describe the path taken by the tip of the resultant vector. The path will create a Lissajous figure.

To obtain the equation for the Lissajous figure, we eliminate the dependence of the unit vectors on $(\omega t - kz)$. First, multiply the equations by $\sin\phi_2$ and $\sin\phi_1$, respectively and then subtract the resulting equations. Second, multiply the two equations by $\cos\phi_2$ and $\cos\phi_1$, respectively and then subtract the new equations. These two operations yield the following pair of equations:

$$\begin{aligned} &\frac{E_x}{E_{0x}}\sin\phi_2 - \frac{E_y}{E_{0y}}\sin\phi_1 \\ &\quad = \cos(\omega t - kz)[\cos\phi_1 \sin\phi_2 - \sin\phi_1 \cos\phi_2] \end{aligned} \qquad [6]$$

$$\frac{E_x}{E_{0x}}\cos\phi_2 - \frac{E_y}{E_{0y}}\cos\phi_1$$

$$= \sin(\omega t - kz)[\cos\phi_1 \sin\phi_2 - \sin\phi_1 \cos\phi_2] \qquad [7]$$

The term in brackets can be simplified using the trig identity

$$\sin\delta = \sin(\phi_2 - \phi_1)$$

$$= \cos\phi_1 \sin\phi_2 - \sin\phi_1 \cos\phi_2 \qquad [8]$$

After replacing the term in brackets by sin δ, the two equations are squared and added yielding the equation for the Lissajous figure:

$$\left(\frac{E_x}{E_{0x}}\right)^2 + \left(\frac{E_y}{E_{0y}}\right)^2 - \left(\frac{2E_xE_y}{E_{0x}E_{0y}}\right)\cos\delta = \sin^2\delta \qquad [9]$$

The trig identity

$$\cos\delta = \cos(\phi_2 - \phi_1) = \cos\phi_1 \cos\phi_2 + \sin\phi_1 \sin\phi_2$$

was also used to further simplify eqn [9].

Equation [9] has the same form as the equation of a conic

$$Ax^2 + Bxy + Cy^2 + Dx + Ey + F = 0$$

Geometry defines the conic as an ellipse because, from eqn [9]

$$B^2 - 4AC = \frac{4}{E_{0x}^2 E_{0y}^2}(\cos^2\delta - 1) < 0$$

This ellipse is called the polarization ellipse. The orientation of the ellipse, with respect to the x-axis, is

$$\tan 2\theta = \frac{B}{A - C} = \frac{2E_{0x}E_{0y}\cos\delta}{E_{0x}^2 - E_{0y}^2} \qquad [10]$$

The tip of the resultant electric field vector obtained from eqn [4] traces out the polarization ellipse in the plane normal to **k**, as predicted by eqn [9]. The ratio of the length of the minor to the major axis of the ellipse is equal to the ellipticity, φ, i.e., the amount of deviation of the ellipse from a circle

$$\tan\varphi = \pm\left(\frac{E_m}{E_M}\right)$$

$$= \frac{E_{0x}\sin\phi_1 \sin\theta - E_{0y}\sin\phi_2 \cos\theta}{E_{0x}\cos\phi_1 \cos\theta + E_{0y}\cos\phi_2 \sin\theta} \qquad [11]$$



Figure 1 General form of the ellipse described by eqn [9]. Reproduced with permission from Guenther RD (1990) *Modern Optics*. New York: John Wiley and Sons.

In particle physics, the light would be said to have a negative helicity if it rotated in a clockwise direction. If we look at the source, the electric vector seems to follow the threads of a left-handed screw, agreeing with the nomenclature that left-handed quantities are negative. However, in optics the light that rotates clockwise, as we view it traveling toward us from the source, is said to be right-circularly polarized. The counterclockwise rotating light is left-circularly polarized. The association of right-circularly polarized light, with 'right-handedness' in optics, came about by looking at the path of the electric vector in space at a fixed time, then $\tan\psi = \tan(\phi - kz)$ (Figure 1).

Stokes Parameters

In the formalism associated with eqn [2], the expansion coefficients, a_i, can be used to form a 2–2 matrix which, in statistical mechanics, is called the density matrix and in optics, the coherency matrix (Table 1). The elements of the matrix are formed by the rule

$$\rho_{ij} = \mathbf{a}_i\mathbf{a}_j^* \qquad [12]$$

The matrix is Hermitian, so that $\rho_{ij} = \rho_{ji}^*$. We will not develop the theory of polarization using the coherency matrix, but simply use the coherency matrix to justify the need for four independent measurements to characterize polarization. There is no unique set of measurements required by the theory, but normally measurements made are of the Stoke's parameters which are directly related to the parameters of the polarization ellipse of eqn [9].

The Stokes parameters of a light wave are measurable quantities, defined as:

$s_0 \Rightarrow$ Total flux density
$s_1 \Rightarrow$ Difference between flux density transmitted by a

Table 1 Typical Stokes vectors

Horizontal polarization	$\begin{bmatrix}1\\1\\0\\0\end{bmatrix}$	Vertical polarization	$\begin{bmatrix}1\\-1\\0\\0\end{bmatrix}$
+45° polarization	$\begin{bmatrix}1\\0\\1\\0\end{bmatrix}$	−45° polarization	$\begin{bmatrix}1\\0\\-1\\0\end{bmatrix}$
Right circular polarization	$\begin{bmatrix}1\\0\\0\\1\end{bmatrix}$	Left circular polarization	$\begin{bmatrix}1\\0\\0\\-1\end{bmatrix}$

linear polarizer oriented parallel to the x-axis and one oriented parallel to the y-axis. The x and y-axes are usually selected to be parallel to the horizontal and vertical directions in the laboratory.

$s_2 \Rightarrow$ Difference between flux density transmitted by a linear polarizer oriented at 45° to the x-axis and one oriented at 135°.

$s_3 \Rightarrow$ Difference between flux density transmitted by a right-circular polarizer and a left-circular polarizer.

If the Stokes parameters are to characterize the polarization of a wave, they must be related to the parameters of the polarization ellipse. It is therefore important to establish that the Stokes parameters are variables of the polarization ellipse (eqn [9]).

In its current form, eqn [9] contains no measurable quantities and thus must be modified if it is to be associated with the Stokes parameters. The time average of the Poynting vector is the quantity observed when measurements are made of light waves. We must, therefore, find the time average of eqn [9] if we wish to relate its parameters to observable quantities.

The time average eqn [9] can now be written as

$$\frac{\langle E_x^2\rangle}{E_{0x}^2} + \frac{\langle E_y^2\rangle}{E_{0y}^2} - 2\frac{\langle E_x E_y\rangle}{E_{0x}E_{0y}}\cos\delta = \sin^2\delta \qquad [13]$$

where time average is denoted by $\langle\ \rangle$

$$\langle E_x^2\rangle = \frac{1}{T}\int_{t_0}^{t_0+T} E_{0x}^2[\cos(\omega t - kz)\cos\phi_1 - \sin(\omega t - kz)\sin\phi_1]^2 \mathrm{d}t \qquad [14]$$

With the time averages, eqn [13] can be written as

$$(E_{0x}^2 + E_{0y}^2)^2 - (E_{0x}^2 - E_{0y}^2)^2 - (2E_{0x}E_{0y}\cos\delta)^2 = (2E_{0x}E_{0y}\sin\delta)^2 \qquad [15]$$

Each term in this equation can be identified with a Stokes parameter:

$$s_0 = \langle E_{0x}^2\rangle + \langle E_{0y}^2\rangle \qquad s_1 = \langle E_{0x}^2\rangle - \langle E_{0y}^2\rangle$$
$$s_2 = \langle 2E_{0x}E_{0y}\cos\delta\rangle \qquad s_3 = \langle 2E_{0x}E_{0y}\sin\delta\rangle \qquad [16]$$

Equation [15] can now be written as

$$s_0^2 - s_1^2 - s_2^2 = s_3^2 \qquad [17]$$

For a polarized wave, only three of the Stokes parameters are independent. This agrees with the requirement placed upon elements of the Hermitian, coherency matrix, introduced above.

With this demonstration of the connection between the Stokes parameters and the polarization ellipse, the Stokes parameters can be written in terms of the parameters of the polarization ellipse.

$$s_1 = s_0\cos 2\varphi\cos 2\theta$$
$$s_2 = s_0\cos 2\varphi\sin 2\theta \qquad [18]$$
$$s_3 = s_0\sin 2\varphi$$

Mueller Calculus

Mueller pointed out that the Stokes parameters can be thought of as elements of a column matrix or a 4-vector (Table 2)

$$\mathcal{S} = \begin{pmatrix} s_0\\ s_1\\ s_2\\ s_3\end{pmatrix} \qquad [19]$$

Each element of the Stokes vector represents a measurable intensity. The vector can represent not only polarized 1ight, but unpolarized or partially polarized light.

In 1929, Soleillet discovered that an optical device performed a linear transformation on the input wave and, in 1942, Perrin put this fact into a matrix formalism involving the Stokes vectors:

$$\mathcal{S}_1 = \mathcal{M}\cdot\mathcal{S}_0 \qquad [20]$$

Mueller used experimentally derived 4 × 4 matrices, the $\mathcal{M}$ in eqn [20], to describe the effect of an optical device on a light wave's polarization. The $\mathcal{S}$'s in eqn [20] are column matrices whose elements

Table 2 Mueller matrices for polarizers

Polarizer	*Transmission axis*	*Mueller matrix*
Linear	Horizontal	$\frac{1}{2}\begin{bmatrix} 1 & 1 & 0 & 0 \\ 1 & 1 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \end{bmatrix}$
	Vertical	$\frac{1}{2}\begin{bmatrix} 1 & -1 & 0 & 0 \\ -1 & 1 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \end{bmatrix}$
	+45°	$\frac{1}{2}\begin{bmatrix} 1 & 0 & 1 & 0 \\ 0 & 0 & 0 & 0 \\ 1 & 0 & 1 & 0 \\ 0 & 0 & 0 & 0 \end{bmatrix}$
	−45°	$\frac{1}{2}\begin{bmatrix} 1 & 0 & -1 & 0 \\ 0 & 0 & 0 & 0 \\ -1 & 0 & 1 & 0 \\ 0 & 0 & 0 & 0 \end{bmatrix}$
Circular	Right	$\frac{1}{2}\begin{bmatrix} 1 & 0 & 0 & 1 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ 1 & 0 & 0 & 1 \end{bmatrix}$
	Left	$\frac{1}{2}\begin{bmatrix} 1 & 0 & 0 & -1 \\ 0 & 0 & 0 & 0 \\ 0 & 0 & 0 & 0 \\ -1 & 0 & 0 & 1 \end{bmatrix}$

Table 3 Mueller matrices for retarders

Retarder	*Transmission axis*	*Mueller matrix*
Quarter-wave plate	Horizontal	$\begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & 1 \\ 0 & 0 & -1 & 0 \end{bmatrix}$
	Vertical	$\begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & 0 & -1 \\ 0 & 0 & 1 & 0 \end{bmatrix}$
	+45°	$\begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 0 & 0 & -1 \\ 0 & 0 & 1 & 0 \\ 0 & 1 & 0 & 0 \end{bmatrix}$
	−45°	$\begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 0 & 0 & 1 \\ 0 & 0 & 1 & 0 \\ 0 & -1 & 0 & 0 \end{bmatrix}$
Half-wave plate	0° or 90°	$\begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & 1 & 0 & 0 \\ 0 & 0 & -1 & 0 \\ 0 & 0 & 0 & -1 \end{bmatrix}$
	±45°	$\begin{bmatrix} 1 & 0 & 0 & 0 \\ 0 & -1 & 0 & 0 \\ 0 & 0 & 1 & 0 \\ 0 & 0 & 0 & -1 \end{bmatrix}$

are the Stokes parameters (eqn [16]). The matrices are based upon an assumed linear relationship between the incident and transmitted beams (Table 3).

The analysis of the effect of a number of polarizers and retarders is made easier by the use of the Mueller–Stokes matrix calculus, coupled with the use of the Stokes vectors. To determine the Mueller matrices, one must measure the effect a device has on unpolarized, horizontally polarized, linearly polarized at + 45°, and right-circularly polarized light. It is then an algebraic exercise to generate the elements of the matrix. A few optical devices and their Mueller matrix are listed in Tables 2 and 3.

The Mueller matrix contains 16 parameters but there are only seven independent parameters. The matrix contains no information about absolute phase but it handles partially polarized and unpolarized light without modification (Table 4).

Jones Vector

There is one other representation of polarized light, complementary to the Stokes vector, developed by Clark Jones in 1941 and called the Jones vector. It is superior to the Stokes vector in that it handles light of a known phase and amplitude with a reduced number of parameters. However, it is inferior to the Stokes vector in that, unlike the Stokes representation, which is experimentally determined, the Jones representation cannot handle unpolarized or partially polarized light. The Jones vector is a theoretical construct that can only describe light with a well-defined phase and frequency. The density matrix formalism can be used to correct the shortcomings of the Jones vector, but then the simplicity of the Jones representation is lost.

Assuming the coordinate system is such that the electromagnetic wave is propagating along the z-axis, it was shown earlier that any polarization could be decomposed into two orthogonal **E** vectors, i.e., parallel to the x and y directions. The Jones vector is defined as a two-row, column matrix consisting of the complex components in the x and y direction:

$$\mathbf{E} = \begin{bmatrix} E_{0x}\, e^{i(\omega t - \mathbf{k}\cdot\mathbf{r} + \phi_1)} \\ E_{0y}\, e^{i(\omega t - \mathbf{k}\cdot\mathbf{r} + \phi_2)} \end{bmatrix} \qquad [21]$$

Table 4 Jones vectors

Horizontal polarization	$\begin{bmatrix} 1 \\ 0 \end{bmatrix}$	Vertical polarization	$\begin{bmatrix} 0 \\ 1 \end{bmatrix}$
+45° polarization	$\frac{1}{\sqrt{2}}\begin{bmatrix} 1 \\ 1 \end{bmatrix}$	−45° polarization	$\frac{1}{\sqrt{2}}\begin{bmatrix} 1 \\ -1 \end{bmatrix}$
Right circular polarization	$\frac{1}{\sqrt{2}}\begin{bmatrix} 1 \\ i \end{bmatrix}$	Left circular polarization	$\frac{1}{\sqrt{2}}\begin{bmatrix} 1 \\ -i \end{bmatrix}$

If absolute phase is not an issue, then we may normalize the vector by dividing by that number (real or complex) that simplifies the components but keeps the sum of the square of the components equal to one. For example, assume that $E_{0x} = E_{0y}$, then

$$\mathbf{E} = E_{0x}\, e^{i(\omega t - \mathbf{k}\cdot\mathbf{r} + \phi_1)} \begin{bmatrix} 1 \\ e^{i\delta} \end{bmatrix} \qquad [22]$$

The normalized vector would be the terms contained within the bracket, each divided by $\frac{1}{\sqrt{2}}$.

The general form of the Jones vector is

$$\mathbf{E} = \begin{bmatrix} \mathrm{A} \\ \mathrm{B} \end{bmatrix} \qquad \mathbf{E}^* = [\mathrm{A}^*\mathrm{B}^*] \qquad [23]$$

Some examples of Jones vectors are shown in Table 4.

Jones Calculus

The Jones calculus is complementary to the Mueller calculus and operates on the Jones vector, (eqn [23]), similar to the way the Mueller matrix operates on the Stokes vector (Table 5).

The Jones matrix contains eight independent parameters with no redundancy, making it simpler than the Mueller calculus. However, the Jones calculus only applies to polarized light. The Jones calculus can be extended, using the density matrix formalism to allow manipulation of unpolarized

Table 5 Jones matrices for retarders

Retarder	*Transmission axis*	*Jones matrix*
Quarter-wave plate	Horizontal	$\begin{bmatrix} e^{i\pi/4} & 0 \\ 0 & e^{-i\pi/4} \end{bmatrix}$
	Vertical	$\begin{bmatrix} e^{-i\pi/4} & 0 \\ 0 & e^{i\pi/4} \end{bmatrix}$
	+45°	$\frac{1}{2}\begin{bmatrix} 1 & i \\ i & 1 \end{bmatrix}$
	−45°	$\frac{1}{2}\begin{bmatrix} 1 & -i \\ -i & 1 \end{bmatrix}$
Half-wave plate	0° or 90°	$\begin{bmatrix} 1 & 0 \\ 1 & -1 \end{bmatrix}$
	±45°	$\begin{bmatrix} 0 & 1 \\ 1 & 0 \end{bmatrix}$

Table 6 Jones matrices for polarizers

Polarizer	*Transmission axis*	*Jones matrix*
Linear	Horizontal	$\begin{bmatrix} 1 & 0 \\ 0 & 0 \end{bmatrix}$
	Vertical	$\begin{bmatrix} 0 & 0 \\ 0 & 1 \end{bmatrix}$
	+45°	$\frac{1}{2}\begin{bmatrix} 1 & 1 \\ 1 & 1 \end{bmatrix}$
	−45°	$\frac{1}{2}\begin{bmatrix} 1 & -1 \\ -1 & 1 \end{bmatrix}$
Circular	Right	$\frac{1}{2}\begin{bmatrix} 1 & -i \\ i & 1 \end{bmatrix}$
	Left	$\frac{1}{2}\begin{bmatrix} 1 & i \\ -i & 1 \end{bmatrix}$

light, but with a loss of simplicity. The matrix equation for Jones calculus is

$$\mathbf{E}_{\mathrm{out}} = \mathcal{W}\mathbf{E}_{\mathrm{in}} \qquad [24]$$

A few optical devices and their Jones matrices, $\mathcal{W}$, are listed in Tables 5 and 6.

For every matrix in Jones calculus, there is a matrix in Mueller calculus, but the converse is not true. For example, it is possible to construct a depolarizer, by using a thick piece of opal glass in the visible or by using gold covered sandpaper in the infrared. Such a device can be described in Mueller calculus, but there is no matrix for such a device in Jones calculus (Tables 5 and 6).

See also

Polarization: Introduction.

Further Reading

Born M and Wolf E (1970) *Principles of Optics*. New York: Pergamon Press.

Clark Jones R (1941) A new calculus for the treatment of optical systems. *Journal of the Optical Society of America* 32: 488–503.

Clark Jones R (1942) A new calculus for the treatment of optical systems. *Journal of the Optical Society of America* 31: 486–493.

Guenther RD (1990) *Modern Optics*. New York: Wiley.

Hecht E (1998) *Optics*, 3rd edn. Reading, MA: Addison-Wesley.

Klein MV (1970) *Optics*. New York: Wiley.

Kliger DS, Lewis JW and Randall CE (1990) *Polarized Light in Optics and Spectroscopy*. Boston, MA: Academic Press.

McMaster WH (1954) Polarization and the Stokes parameters. *American Journal of Physics* 22: 351–362.

Mueller H (1948) The foundation of optics. *Journal of the Optical Society of America* 38: 661.

QUANTUM ELECTRODYNAMICS

Contents

Quantum Theory of the Electromagnetic Field
Cavity QED
Cavity QED in Semiconductors

Quantum Theory of the Electromagnetic Field

I Bialynicki-Birula and Z Bialynicka-Birula,
Polish Academy of Sciences, Warsaw, Poland

© 2005, Elsevier Ltd. All Rights Reserved.

The quantization of the free electromagnetic field is explained by analogy with the quantization of a collection of harmonic oscillators.

Brief History

The first step in the formulation of the quantum theory of the electromagnetic field (EMF) was the 'quantum hypothesis' put forward in 1900 by Planck. According to this hypothesis the exchange of energy between the EMF and the cavity walls occurs in portions $h\nu$, where h – the quantum of action – is a new fundamental constant (the Planck constant) and ν is the frequency of the material oscillator in the wall. With the help of this hypothesis Planck explained the spectrum of the electromagnetic radiation in thermodynamic equilibrium with the cavity walls. The second step was made in 1905 by Einstein, who postulated that the quantum hypothesis of Planck should be applied directly to the EMF. The assumption that the energy of the electromagnetic radiation is carried by light quanta (named photons by Lewis in 1926), each of energy $h\nu$, enabled Einstein to explain the puzzling properties of the photoelectric effect, namely, the gross disparity between the tiny classical energy flux delivered to an electron and the amount of energy needed to eject the photo-electron from the metal. After the formulation of quantum mechanics, it became possible to complete the quantum theory of the EMF (Dirac 1927) by applying the general rules of quantization to the classical Maxwell theory. However, this theory ran into difficulties when it was applied to the interaction of the EMF with charged matter.

The lightest carriers of the electric charge are the electrons and their dynamics determines to a very large extent the electromagnetic properties of ordinary matter. The main principles of quantum electrodynamics (QED) – the theory unifying the quantum theory of the EMF and the relativistic theory of electrons (Dirac 1928) – have been set forth by Heisenberg and Pauli already in 1929 but the proper tool (renormalization theory) to perform highly accurate calculations was developed by Feynman and Schwinger in 1949. In 1967 QED was unified by Weinberg and Salam with the theory of weak interactions. Later, after the unification with the theory of strong interactions, QED became part of the so called 'standard model' – the present day theory of elementary ingredients of matter: quarks, leptons, gluons, intermediate bosons, and photons. Therefore, the modern quantum theory of the EMF is not a self-contained theory but part of a much more encompassing theory. Often it requires some input from a more general theory or from phenomenology. However, the quantum theory of the EMF with only a very crude description of its coupling to the rest of the world (for example, in the form of boundary conditions or constitutive relations) is still not only a good starting point to a more elaborate theory but also a source of important information about the behavior of photons under realistic conditions. The main reason why treating photons as free particles gives a reasonably good approximation is the smallness of the Sommerfeld fine structure constant $\alpha = e^2/4\pi\varepsilon_0\hbar c \approx 1/137$ that measures the strength of the electromagnetic interactions between photons and charged particles.

Electromagnetic Field as a Collection of Harmonic Oscillators

In order to apply the same quantization procedure as in quantum mechanics, it is useful to formulate classical electrodynamics in a way that exhibits its close relationship with mechanical systems. Many properties of the electromagnetic field may be described and understood in the simplest case of the free field. Therefore, in this article we restrict ourselves to the quantum description of the free EMF.

It was discovered by Rayleigh and Jeans that the electromagnetic field may be viewed as a collection of harmonic oscillators. This analogy enables one to apply well-established methods of simple quantum mechanics to describe the much more complicated problem of the quantum field. The dynamics of a single, one-dimensional harmonic oscillator is governed by the Hamiltonian:

$$H(p,q) = \frac{p^2}{2m} + \frac{m\omega^2 q^2}{2}$$

The equations of motion for the position and momentum of a harmonic oscillator have the same form in classical and in quantum theory:

$$\frac{\mathrm{d}q(t)}{\mathrm{d}t} = \frac{p(t)}{m}, \qquad \frac{\mathrm{d}p(t)}{\mathrm{d}t} = -m\omega^2 q(t)$$

The solutions of these equations describe harmonic oscillations with the frequency ω

$$q(t) = q_0 \cos(\omega t) + (p_0/m\omega)\sin(\omega t)$$

$$p(t) = -m\omega q_0 \sin(\omega t) + p_0 \cos(\omega t)$$

A complete description of a multidimensional harmonic oscillator may be obtained in terms of normal modes. The transformation to normal modes leads to a decomposition of the Hamiltonian of the system into the sum, one term for each mode,

$$H = \sum_k \left(\frac{p_k^2}{2m} + \frac{m\omega_k^2 q_k^2}{2} \right)$$

Thus, each mode may be viewed as a separate system – a one-dimensional harmonic oscillator with characteristic frequency ω_k – noninteracting with the remaining oscillators.

The Maxwell equations for the free EMF read

$$\partial_t \mathbf{B}(\mathbf{r},t) = -\nabla \times \mathbf{D}(\mathbf{r},t)/\varepsilon, \ \nabla\cdot\mathbf{B}(\mathbf{r},t) = 0$$

$$\partial_t \mathbf{D}(\mathbf{r},t) = \nabla \times \mathbf{B}(\mathbf{r},t)/\mu, \ \nabla\cdot\mathbf{D}(\mathbf{r},t) = 0$$

In the vacuum, the constants ε and μ must be replaced by ε_0 and μ_0. The Maxwell equations lead to the wave equation for the vector $\mathbf{D}(\mathbf{r},t)$

$$\left(\frac{1}{c^2}\partial_t^2 - \Delta \right) \mathbf{D}(\mathbf{r},t) = 0$$

and to the same equation for the vector $\mathbf{B}(\mathbf{r},t)$. The solution of this equation obtained by the separation of variables has the form

$$\mathbf{D}(\mathbf{r},t) = a(t)\mathbf{u}(\mathbf{r})$$

where $a(t)$ satisfies the harmonic equation

$$\frac{\mathrm{d}^2}{\mathrm{d}t^2} a(t) + \omega^2 a(t) = 0$$

and $\mathbf{u}(\mathbf{r})$ satisfies the Helmholtz equation

$$(\Delta + (\omega/c)^2)\mathbf{u}(\mathbf{r}) = 0$$

Without going into mathematical details we shall assume that there exist a complete set of vector functions $\mathbf{u}_k(\mathbf{r})$, called the mode functions, satisfying the Helmholtz equations

$$(\Delta + (\omega_k/c)^2)\mathbf{u}_k(\mathbf{r}) = 0$$

the divergence condition $\nabla \cdot \mathbf{u}_k(\mathbf{r}) = 0$, the orthonormality conditions

$$\int \mathrm{d}^3 r \mathbf{u}_k(\mathbf{r}) \cdot \mathbf{u}_l(\mathbf{r}) = \delta_{kl}$$

and also the appropriate boundary conditions. In most cases of physical interest such a set does exist.

Given the set of mode functions $\mathbf{u}_k(\mathbf{r})$ one may expand the vector field $\mathbf{D}(\mathbf{r},t)$ at each t into the series

$$\mathbf{D}(\mathbf{r},t) = -\sum_k p_k(t)\mathbf{u}_k(\mathbf{r})$$

The minus sign is purely conventional; it makes the correspondence with the harmonic oscillator a closer one. The same procedure may be repeated for the vector $\mathbf{B}$ with a different complete set of functions $\mathbf{v}_k(\mathbf{r})$, resulting in the decomposition

$$\mathbf{B}(\mathbf{r},t) = \sum_k q_k(t)\mathbf{v}_k(\mathbf{r})$$

The Maxwell equations are satisfied if the coefficient functions $p_k(t)$ and $q_k(t)$ obey the equations of motion for harmonic oscillators

$$\frac{\mathrm{d}q_k(t)}{\mathrm{d}t} = \frac{p_k(t)}{\varepsilon}, \quad \frac{\mathrm{d}p_k(t)}{\mathrm{d}t} = -\varepsilon\omega^2 q_k(t) \qquad [1]$$

and the functions $\mathbf{v}_k(\mathbf{r})$ are related to $\mathbf{u}_k(\mathbf{r})$ by the formulas

$$\mathbf{v}_k(\mathbf{r}) = \nabla \times \mathbf{u}_k(\mathbf{r})$$

Note that the electric constant ε plays the same role as the mass for a mechanical oscillator. The calculation of the Hamiltonian, the total field energy,

$$H = \int \mathrm{d}^3 r\left(\frac{\mathbf{D}^2}{2\varepsilon} + \frac{\mathbf{B}^2}{2\mu}\right)$$

completes the reduction of the electromagnetic field to a collection of harmonic oscillators. Upon inserting the representation of the field vectors in terms of the complete set of functions $\mathbf{u}_k(\mathbf{r})$ into the integral, one obtains the following formula

$$H = \sum_k \left(\frac{p_k^2}{2\varepsilon} + \frac{\varepsilon\omega_k^2 q_k^2}{2}\right)$$

which differs from its mechanical counterpart only by the replacement $m \to \varepsilon$. The time dependence has been omitted here because the Hamiltonian is a constant of motion.

Mode Functions

The simplest example of a complete set of mode functions is that obtained for a rectangular metallic cavity. In this case the functions $\mathbf{u}_k(\mathbf{r})$ may be expressed in terms of trigonometric functions. In order to write them down, it is convenient to replace one label k by a collection of three numbers $\boldsymbol{\kappa} = \{\kappa_x, \kappa_y, \kappa_z\}$ and an additional index λ taking on the values 1 and 2. The mode functions $\mathbf{u}_{\boldsymbol{\kappa}\lambda}(\mathbf{r})$ satisfying the proper boundary conditions have the following components

$$\mathbf{u}_{\boldsymbol{\kappa}\lambda}(\mathbf{r}) = N\begin{pmatrix} a_x^{(\lambda)} \cos(\kappa_x x)\sin(\kappa_y y)\sin(\kappa_z z) \\ a_y^{(\lambda)} \sin(\kappa_x x)\cos(\kappa_y y)\sin(\kappa_z z) \\ a_z^{(\lambda)} \sin(\kappa_x x)\sin(\kappa_y y)\cos(\kappa_z z) \end{pmatrix}$$

where $N = \sqrt{8/(L_x L_y L_z)}$, the coefficients $\{\kappa_x, \kappa_y, \kappa_z\}$ have the form $\{\kappa_x, \kappa_y, \kappa_z\} = \{\pi n_x/L_x, \pi n_y/L_y, \pi n_z/L_z\}$ and all the n's are natural numbers. The components of both vectors $\mathbf{a}^{(\lambda)}$ are subjected to the conditions $\boldsymbol{\kappa}\cdot\mathbf{a}^{(\lambda)} = 0$ (vanishing divergence) and orthonormalization $\mathbf{a}^{(\lambda)}\cdot\mathbf{a}^{(\lambda')} = \delta_{\lambda\lambda'}$. For each set $\{\kappa_x, \kappa_y, \kappa_z\}$ one must choose two independent solutions of these conditions $\mathbf{a}^{(1)}$ and $\mathbf{a}^{(2)}$. These two vectors define two states of linear polarization. The mode function $\mathbf{u}_{\boldsymbol{\kappa}\lambda}(\mathbf{r})$ is a solution of the Helmholtz equation for the value of ω/c equal to the length of the vector $\boldsymbol{\kappa}$. The expansion of the EMF vectors into the mode functions in a rectangular cavity has the form

$$\mathbf{D}(\mathbf{r},t) = -\sum_{\boldsymbol{\kappa}\lambda} p_{\boldsymbol{\kappa}\lambda}(t)\mathbf{u}_{\boldsymbol{\kappa}\lambda}(\mathbf{r})$$

$$\mathbf{B}(\mathbf{r},t) = \sum_{\boldsymbol{\kappa}\lambda} q_{\boldsymbol{\kappa}\lambda}(t)\nabla \times \mathbf{u}_{\boldsymbol{\kappa}\lambda}(\mathbf{r})$$

where the summation extends over all allowed values of $\boldsymbol{\kappa}$ and two values of λ. One may explicitly write down mode functions also for a cylindrical and for a spherical cavity. They involve Bessel functions and are obtained by solving the Helmholtz equation in cylindrical and spherical coordinates, respectively.

One often uses another set of mode functions that does not correspond to any physical boundary conditions but is very helpful in the theoretical analysis. It is obtained by imposing the so-called periodic boundary conditions that were first introduced by Born in the study of crystal lattices. The periodic boundary conditions require that the electromagnetic field is periodic in space; it does not change when the coordinates are displaced by the 'period of the lattice' in all three directions. Assuming, for simplicity, that this period is the same, equal to L, in all directions, one obtains the following conditions for the mode functions

$$\mathbf{u}_k(\mathbf{r}) = \mathbf{u}_k(\mathbf{r} + L\mathbf{i}_x) = \mathbf{u}_k(\mathbf{r} + L\mathbf{i}_y) = \mathbf{u}_k(\mathbf{r} + L\mathbf{i}_z)$$

where $\mathbf{i}_i$ are the unit vectors in the directions of the coordinate axes. The complete set of solutions of the Helmholtz equation satisfying the periodic boundary conditions is labeled by the wavevector $\mathbf{k} = \{2\pi n_x/L, 2\pi n_y/L, 2\pi n_z/L\}$, where all the n's are arbitrary integers, and by the polarization index λ. The value of ω/c in the Helmholtz equation is equal in this case to the length of the vector k. Each member of the set $\mathbf{u}_{\mathbf{k}\lambda}$ has the form

$$\mathbf{u}_{\mathbf{k}\lambda}(\mathbf{r}) = \frac{1}{\sqrt{V}}\mathbf{e}_{\mathbf{k}\lambda}\exp(\mathrm{i}\mathbf{k}\cdot\mathbf{r}) \qquad [2]$$

where $V = L^3$. The polarization vectors $\mathbf{e}_{\mathbf{k}\lambda}$ must be orthogonal to the wave vector $\mathbf{k}$. It is convenient to impose the unitary orthonormality conditions $\mathbf{e}_{\mathbf{k}\lambda}\cdot \mathbf{e}^*_{\mathbf{k}\lambda} = \delta_{\lambda\lambda'}$ and also to assume that $\mathbf{e}^*_{\mathbf{k}\lambda} = \mathbf{e}_{-\mathbf{k}\lambda}$. The expansion of the EMF vectors into the mode functions obeying the periodic boundary conditions has the form

$$\mathbf{D}(\mathbf{r},t) = -\frac{1}{\sqrt{V}}\sum_{\mathbf{k}\lambda} P_{\mathbf{k}\lambda}(t)\mathbf{e}_{\mathbf{k}\lambda}\mathrm{e}^{\mathrm{i}\mathbf{k}\cdot\mathbf{r}}$$

$$\mathbf{B}(\mathbf{r},t) = \frac{1}{\sqrt{V}}\sum_{\mathbf{k}\lambda} Q_{\mathbf{k}\lambda}(t)\mathrm{i}\mathbf{k}\times\mathbf{e}_{\mathbf{k}\lambda}\mathrm{e}^{\mathrm{i}\mathbf{k}\cdot\mathbf{r}} \quad [3]$$

where the sum extends again over all allowed values of the vectors $\mathbf{k}$ and over two values of λ. The expansion coefficients $P_{\mathbf{k}\lambda}$ and $Q_{\mathbf{k}\lambda}$ are now complex. In order to guarantee that the field vectors are real, they must obey the conditions

$$P^*_{\mathbf{k}\lambda} = P_{-\mathbf{k}\lambda},\ Q^*_{\mathbf{k}\lambda} = Q_{-\mathbf{k}\lambda}$$

These conditions are satisfied if $P_{\mathbf{k}\lambda}$ and $Q_{\mathbf{k}\lambda}$ are parametrized by the real (but otherwise arbitrary) variables $p_{\mathbf{k}\lambda}$ and $q_{\mathbf{k}\lambda}$

$$P_{\mathbf{k}\lambda} = \frac{p_{\mathbf{k}\lambda}+p_{-\mathbf{k}\lambda}}{2} + \frac{\varepsilon\omega_{\mathbf{k}}(q_{\mathbf{k}\lambda}-q_{-\mathbf{k}\lambda})}{2i}$$

$$Q_{\mathbf{k}\lambda} = \frac{q_{\mathbf{k}\lambda}+q_{-\mathbf{k}\lambda}}{2} + \frac{\mathrm{i}(p_{\mathbf{k}\lambda}-p_{-\mathbf{k}\lambda})}{2\varepsilon\omega_{\mathbf{k}}}$$

The energy of the EMF splits again into a sum of independent contributions from all the modes

$$H = \sum_{\mathbf{k}\lambda}\omega_{\mathbf{k}}\left(\frac{p_{\mathbf{k}\lambda}p_{\mathbf{k}\lambda}}{2\varepsilon\omega_{\mathbf{k}}} + \frac{\varepsilon\omega_{\mathbf{k}}q_{\mathbf{k}\lambda}q_{\mathbf{k}\lambda}}{2}\right)$$

An important property of the periodic mode functions [2] is that not only the Hamiltonian but also the total momentum of the field splits into a sum of independent contributions. The total momentum $\mathbf{P}$ of the EMF is

$$\mathbf{P} = \int \mathrm{d}^3 r\,\mathbf{D}\times\mathbf{B}$$

Upon substituting into this expression the expansions [3] of the field vectors, one obtains, with the use of the orthonormality conditions,

$$\mathbf{P} = \sum_{\mathbf{k}\lambda}\mathbf{k}\left(\frac{p_{\mathbf{k}\lambda}p_{\mathbf{k}\lambda}}{2\varepsilon\omega_{\mathbf{k}}} + \frac{\varepsilon\omega_{\mathbf{k}}q_{\mathbf{k}\lambda}q_{\mathbf{k}\lambda}}{2}\right)$$

Canonical Quantization

The canonical quantization in quantum mechanics consists in replacing the c-numbers representing the classical canonical variables q_k and p_k by the operators $\hat{q}_k$ and $\hat{p}_k$. These operators are assumed to obey the canonical commutation relations

$$[\hat{q}_k, \hat{p}_l] = \mathrm{i}\hbar\delta_{kl} \quad [4]$$

The canonical quantization of the EMF may proceed along the same lines as in quantum mechanics. All the variables q_k and p_k appearing in the decomposition into normal modes are replaced by the operators. When this is done, the field vectors $\mathbf{B}$ and $\mathbf{D}$ become the field operators $\hat{\mathbf{B}}$ and $\hat{\mathbf{D}}$ and the expression for the energy of the field becomes the Hamiltonian operator $\hat{H}$

$$\hat{H} = \sum_k \frac{\hat{p}_k^2}{2\varepsilon} + \frac{\varepsilon\omega_k^2\hat{q}_k^2}{2}$$

The only difference between quantum mechanics and quantum field theory is that in the second case the number of canonical variables is infinite but this may cause complications only when one wants to give the quantum theory of the EMF a firm mathematical foundation. In physical applications one may think of the number of field oscillators as being very large but finite.

Time evolution of a quantum system is described by associating the time dependence either with the operators (the Heisenberg picture) or with the state vectors (the Schrödinger picture). In both pictures the time dependence is governed by the system Hamiltonian. In the Heisenberg picture the time dependence of the operators is given by the commutators with $\hat{H}$

$$\frac{\mathrm{d}\hat{q}_k(t)}{\mathrm{d}t} = \frac{1}{\mathrm{i}\hbar}[\hat{q}_k(t), \hat{H}] = \frac{\hat{p}_k(t)}{\varepsilon}$$

$$\frac{\mathrm{d}\hat{p}_k(t)}{\mathrm{d}t} = \frac{1}{\mathrm{i}\hbar}[\hat{p}_k(t), \hat{H}] = -\varepsilon\omega_k^2\hat{q}_k(t)$$

These equations have the same form as in the classical theory (cf. eqn [1]). Therefore, in the Heisenberg picture the field operators will also obey the same equations as in the classical theory – the Maxwell equations:

$$\partial_t\hat{\mathbf{B}}(\mathbf{r},t) = -\nabla\times\hat{\mathbf{D}}(\mathbf{r},t)/\varepsilon,\ \ \nabla\cdot\hat{\mathbf{B}}(\mathbf{r},t) = 0$$

$$\partial_t\hat{\mathbf{D}}(\mathbf{r},t) = \nabla\times\hat{\mathbf{B}}(\mathbf{r},t)/\mu,\ \ \nabla\cdot\hat{\mathbf{D}}(\mathbf{r},t) = 0$$

Of course, the average values of the field operators evaluated in both pictures are the same and for every quantum state they obey the classical Maxwell equations.

The commutation relations [4] for the canonical operators and the completeness of the mode functions imply the following equal-time commutation relations for the field operators

$$[\hat{B}_i(\mathbf{r},t),\hat{D}_j(\mathbf{r}',t)] = \mathrm{i}\hbar \sum_k \varepsilon_{ijk}\partial_k \delta^{(3)}(\mathbf{r}-\mathbf{r}')$$

These relations do not depend on the choice of the mode functions. They summarize in a universal manner the canonical properties of the electromagnetic field operators.

Annihilation and Creation Operators

The canonical variables q_k and p_k are convenient for bringing home the analogy between mechanical oscillators and wave fields. However, there exists also a complementary, corpuscular aspect of the quantum theory of the EMF and that is most easily expressed in terms of photons. The best way to describe photons in quantum field theory is in terms of annihilation and creation operators. These operators were introduced by Schrödinger in the context of the quantum-mechanical harmonic oscillator but they have become really indispensable in quantum field theory. Formally, the annihilation $\hat{a}_k$ and the creation $\hat{a}_k^\dagger$ operators are defined as the following complex combinations of canonical operators

$$\begin{aligned} \hat{a}_k &= \sqrt{\frac{\varepsilon\omega}{2\hbar}}\left(\hat{q}_k + \mathrm{i}\frac{\hat{p}_k}{\varepsilon\omega}\right) \\ \hat{a}_k^\dagger &= \sqrt{\frac{\varepsilon\omega}{2\hbar}}\left(\hat{q}_k - \mathrm{i}\frac{\hat{p}_k}{\varepsilon\omega}\right) \end{aligned} \qquad [5]$$

Annihilation and creation operators are dimensionless, one is the Hermitian adjoint of the other, and they obey very simple commutation relations:

$$[\hat{a}_k,\hat{a}_l^\dagger] = \delta_{kl} \qquad [6]$$

The Hamiltonian expressed in terms of annihilation and creation operators reads

$$\hat{H} = \sum_k \hbar\omega_k \hat{a}_k^\dagger \hat{a}_k + \frac{1}{2}\sum_k \hbar\omega_k \qquad [7]$$

This Hamiltonian determines the following time dependence of the annihilation and creation operators

$$\hat{a}_k(t) = \hat{a}_k \exp(-\mathrm{i}\omega_k t),\ \hat{a}_k^\dagger(t) = \hat{a}_k^\dagger \exp(\mathrm{i}\omega_k t)$$

The field operators expressed in terms of annihilation and creation operators corresponding to the periodic boundary conditions are

$$\hat{\mathbf{D}}(\mathbf{r},t) = \mathrm{i}\sum_{\mathbf{k}\lambda}\sqrt{\frac{\hbar\varepsilon\omega_{\mathbf{k}}}{2V}}\hat{a}_{\mathbf{k}\lambda}\mathbf{e}_{\mathbf{k}\lambda}\mathrm{e}^{-\mathrm{i}\omega_{\mathbf{k}}t+\mathrm{i}\mathbf{k}\cdot\mathbf{r}} + \mathrm{H.c.}$$

$$\hat{\mathbf{B}}(\mathbf{r},t) = \mathrm{i}\sum_{\mathbf{k}\lambda}\sqrt{\frac{\hbar}{2V\varepsilon\omega_{\mathbf{k}}}}\hat{a}_{\mathbf{k}\lambda}\mathbf{k}\times\mathbf{e}_{\mathbf{k}\lambda}\mathrm{e}^{-\mathrm{i}\omega_{\mathbf{k}}t+\mathrm{i}\mathbf{k}\cdot\mathbf{r}} + \mathrm{H.c.}$$

where H.c. stands for the Hermitian conjugate of the first term. In the limiting case for infinite empty space, when $V \to \infty$, the Fourier sum becomes the Fourier integral:

$$\begin{aligned} \hat{\mathbf{D}}(\mathbf{r},t) = {} & \mathrm{i}\sum_\lambda \int \mathrm{d}^3k\sqrt{\frac{\hbar\varepsilon\omega_{\mathbf{k}}}{2(2\pi)^3}}\big(\hat{a}_\lambda(\mathbf{k})\mathbf{e}_{\mathbf{k}\lambda}\mathrm{e}^{-\mathrm{i}\omega_{\mathbf{k}}t+\mathrm{i}\mathbf{k}\cdot\mathbf{r}} \\ & - \hat{a}_\lambda^\dagger(\mathbf{k})\mathbf{e}_{\mathbf{k}\lambda}^*\mathrm{e}^{\mathrm{i}\omega_{\mathbf{k}}t-\mathrm{i}\mathbf{k}\cdot\mathbf{r}}\big) \end{aligned}$$

$$\begin{aligned} \hat{\mathbf{B}}(\mathbf{r},t) = {} & \mathrm{i}\sum_\lambda \int \mathrm{d}^3k\sqrt{\frac{\hbar}{2\varepsilon\omega_{\mathbf{k}}(2\pi)^3}}\big(\hat{a}_\lambda(\mathbf{k})\mathbf{k}\mathbf{e}_{\mathbf{k}\lambda}\mathrm{e}^{-\mathrm{i}\omega_{\mathbf{k}}t+\mathrm{i}\mathbf{k}\cdot\mathbf{r}} \\ & - \hat{a}_\lambda^\dagger(\mathbf{k})\mathbf{k}\times\mathbf{e}_{\mathbf{k}\lambda}^*\mathrm{e}^{\mathrm{i}\omega_{\mathbf{k}}t-\mathrm{i}\mathbf{k}\cdot\mathbf{r}}\big) \end{aligned}$$

In this case, the commutation relations involve the (three-dimensional) Dirac delta function

$$[\hat{a}_\lambda(\mathbf{k}),\hat{a}_{\lambda'}^\dagger(\mathbf{k}')] = \delta_{\lambda\lambda'}\delta^{(3)}(\mathbf{k}-\mathbf{k}') \qquad [8]$$

The field operators may also be expressed in terms of the vector potential operator $\hat{\mathbf{A}}(\mathbf{r},t)$

$$\hat{\mathbf{D}}(\mathbf{r},t) = -\varepsilon\partial_t\hat{\mathbf{A}}(\mathbf{r},t),\ \hat{\mathbf{B}}(\mathbf{r},t) = \nabla\times\hat{\mathbf{A}}(\mathbf{r},t)$$

$$\begin{aligned} \hat{\mathbf{A}}(\mathbf{r},t) = {} & \sum_\lambda \int \mathrm{d}^3k\sqrt{\frac{\hbar}{2\varepsilon\omega_{\mathbf{k}}(2\pi)^3}}\big(\hat{a}_\lambda(\mathbf{k})\mathbf{e}_{\mathbf{k}\lambda}\mathrm{e}^{-\mathrm{i}\omega_{\mathbf{k}}t+\mathrm{i}\mathbf{k}\cdot\mathbf{r}} \\ & + \hat{a}_\lambda^\dagger(\mathbf{k})\mathbf{e}_{\mathbf{k}\lambda}^*\mathrm{e}^{\mathrm{i}\omega_{\mathbf{k}}t-\mathrm{i}\mathbf{k}\cdot\mathbf{r}}\big) \end{aligned}$$

The vector potential is needed for the description of the interaction with charged particles.

Space of Quantum States

The standard basis in the space of quantum states consists of the state vectors of stationary states – the eigenvectors of the Hamiltonian.

Vacuum State

The lowest energy state of the EMF – the ground state of the system – is often called the vacuum state. The state vector describing the vacuum state is denoted by $|0\rangle$. The vacuum state is the common ground state of all harmonic oscillators making up the EMF. Since the ground state of a single harmonic oscillator has the energy $\hbar\omega/2$, the energy of the ground state for an infinite number of oscillators is infinite (last term in eqn [7]). This infinity has no physical consequences because only the energy differences are observable. In the presence of obstacles (mirrors, resonators, beamsplitters, etc.), owing to the change in the mode structure, there will be a change in the energy of the new ground state relative to the energy in empty space. The energy differences between various ground states do have physical significance.

Fock Basis

It follows from the commutation relations [6] and from the form [7] of the Hamiltonian that the operator $\hat{a}_k$ decreases the energy of the EMF by the Planck quantum of energy $\hbar\omega_k$. Therefore, all operators $\hat{a}_k$ must annihilate the ground state vector, $\hat{a}_k|0\rangle = 0$, because there is no state with a lower energy. Each creation operator $\hat{a}_k^\dagger$ acting on any state vector adds one excitation with the energy $\hbar\omega_k$. These excitations of the electromagnetic field with characteristic energies $\hbar\omega_k$ are interpreted as photons. The state vectors of the form $\hat{a}_k^\dagger|0\rangle$ describe one-photon states, the state vectors of the form $\hat{a}_k^\dagger\hat{a}_l^\dagger|0\rangle$ describe two-photon states, etc. All the vectors generated from the vacuum state vector by acting with the creation operators form a basis, called the Fock basis. The general state vector of this basis is characterized by a sequence of natural numbers $\{n_1, n_2, \ldots\}$ and is generated from the vacuum state according to the formula

$$|n_1, n_2, \ldots\rangle = (n_1!n_2!\cdots)^{-1/2}(\hat{a}_1^\dagger)^{n_1}(\hat{a}_2^\dagger)^{n_2}\ldots|0\rangle \qquad [9]$$

where the prefactor is needed for normalization. The number n_k tells us how many photons of type k are present in this state. The spatial structure of a field excitation created by $\hat{a}_k^\dagger$ is described by the mode function $\mathbf{u}_k(\mathbf{r})$. Thus, this mode function plays the same role as the wavefunction $\psi(\mathbf{r})$ of a massive particle and the set of indices labeling the mode functions is the analog of quantum numbers for $\psi(\mathbf{r})$. In particular, for the mode function [2], the photons have a definite momentum $\hbar\mathbf{k}$. In a cylindrical waveguide the photons may have a definite momentum only along the axis of the cylinder. In a spherical cavity the photons may have the definite value of square of the total angular momentum and its projection on a given axis. The Fock states are highly nonclassical; all average values of the EMF in these states vanish.

All states of the EMF are either pure or mixed. Pure states are described by all linear superpositions of the basis states. In particular, by superposing photon states with a range of energies, one may form nonmonochromatic photon wavepackets. All superpositions are allowed since photons do not have any absolutely conserved quantum numbers (like, e.g., charge). Mixed states are described by the density operators. Among the mixed states the prominent role is played by the thermal state describing the EMF in equilibrium with a reservoir at temperature T.

Coherent States

The one-mode coherent states $|\alpha\rangle$ are obtained from the vacuum state by the action of the unitary displacement operator $\hat{D}(\alpha, \alpha^*)$

$$|\alpha\rangle = D(\alpha, \alpha^*)|0\rangle = \mathrm{e}^{\alpha\hat{a}^\dagger - \alpha^*\hat{a}}|0\rangle = \mathrm{e}^{-|\alpha|^2/2}\mathrm{e}^{\alpha\hat{a}^\dagger}|0\rangle$$

where $\hat{a}$ and $\hat{a}^\dagger$ are the annihilation and creation operators corresponding to a given mode. Coherent states are superpositions of an infinite number of Fock states. The multimode coherent state is generated by the product of displacement operators

$$|\alpha_1, \alpha_2, \ldots\rangle = \mathrm{e}^{\sum_k (\alpha_k\hat{a}_k^\dagger - \alpha_k^*\hat{a}_k)}|0\rangle$$

In reality, the coherent states are generated by the action of an external (strong) time-dependent electric current. In that case the coefficients α_k are the projections of the current on the mode functions. The average values of the field operators $\langle\hat{B}_i(\mathbf{r}, t)\rangle$ and $\langle\hat{D}_j(\mathbf{r}, t)\rangle$ in coherent states are the solutions of the Maxwell equations in the presence of an external electric current.

Entangled States

The states of the EMF describing photons in different modes may exhibit correlations. The simplest such state is a two-photon state of the form $|\phi\rangle = 2^{-1/2}(\hat{a}_1^\dagger\hat{a}_2^\dagger + \hat{a}_3^\dagger\hat{a}_4^\dagger)|0\rangle$. In this case, when one photon is found, say, in the state 1, the other will be found with the probability 1 in the state 2. The states that exhibit correlations between photons belonging to different modes are called the entangled states.

Correlations occur also in the classical theory, but only for statistical mixtures when there is a loss of information. In quantum theory the correlations may arise even without a loss of information, i.e., for pure states. A striking feature of entangled states is that the decomposition of such a state into a sum of Fock states is not unique. For example, the state vector $|\phi\rangle$ may also be written in the form $|\phi\rangle = 2^{-1/2}(\hat{a}^\dagger_{1'}\hat{a}^\dagger_{2'} + \hat{a}^\dagger_{3'}\hat{a}^\dagger_{4'})|0\rangle$, where $\hat{a}^\dagger_{1'} = 2^{-1/2}(\hat{a}^\dagger_1 - \hat{a}^\dagger_3)$, $\hat{a}^\dagger_{2'} = 2^{-1/2}(\hat{a}^\dagger_2 - \hat{a}^\dagger_4)$, $\hat{a}^\dagger_{3'} = 2^{-1/2}(\hat{a}^\dagger_1 + \hat{a}^\dagger_3)$, $\hat{a}^\dagger_{4'} = 2^{-1/2}(\hat{a}^\dagger_2 + \hat{a}^\dagger_4)$. Entangled states play a crucial role in quantum information theory, especially in quantum cryptography.

Quantum Fluctuations and the Uncertainty Relations

It follows from the basic principles of quantum theory that there are no states of the system for which both canonical variables q and p have sharply defined values. The limits on the quantum fluctuations (variances) of these values are determined by the uncertainty relation. The most stringent form of this relation obtained from the commutation relations [4] (for a single mode) reads

$$(\Delta q)^2(\Delta p)^2 \geq \frac{\hbar^2}{4} + \frac{\langle \delta\hat{q}\delta\hat{p} + \delta\hat{p}\delta\hat{q}\rangle^2}{4} \qquad [10]$$

where $\delta\hat{q} = \hat{q} - \langle\hat{q}\rangle$, $\delta\hat{p} = \hat{p} - \langle\hat{p}\rangle$, $(\Delta q)^2 = \langle(\delta\hat{q})^2\rangle$, and $(\Delta p)^2 = \langle(\delta\hat{p})^2\rangle$. The states for which this inequality is saturated play a distinguished role in quantum theory. Since the uncertainty relation expresses the limitations on the quantum fluctuations of q and p, the best one can do in approaching the classical regime is to achieve equality in the uncertainty relation. That is why the quantum states that saturate [10] are viewed as the counterparts of the classical states. In the quantum theory of the EMF, the uncertainty relations express the complementarity between the magnetic and electric fields. The better one knows the magnetic field, the more uncertain is the electric field, and vice versa. However, the projections of the field operators $\hat{\mathbf{B}}$ and $\hat{\mathbf{D}}$ on the same direction commute (cf. eqn [5]). Therefore, there are no limitations on the magnetic and electric field values in a given direction and only the values in different directions are subjected to the quantum uncertainty relation.

In the vacuum state the variances of q and p for each mode are

$$(\Delta q)^2 = \frac{\hbar}{2\varepsilon\omega}, (\Delta p)^2 = \frac{\hbar\varepsilon\omega}{2} \qquad [11]$$

and they saturate the uncertainty relation. These fluctuations are called the shot noise. Very often one uses dimensionless quadrature operators $\hat{X}_1 = \hat{q}\sqrt{2\varepsilon\omega/\hbar}$ and $\hat{X}_2 = \hat{p}\sqrt{2/\varepsilon\omega\hbar}$, whose fluctuations in the vacuum state are equal to 1. All coherent states have the same fluctuations as the vacuum state. They may be viewed in the phase space as the vacuum state displaced from the origin (corresponding to the vacuum state) by the mean values of q and p.

Coherent states are not the only states that saturate the uncertainty relations. The other states with this property are called the squeezed states. The fluctuations of X_1 and X_2 for squeezed states are different from 1 but their product is still equal to 1, $(\Delta X_1)^2(\Delta X_2)^2 = 1$.

Fock states have well-defined energies and numbers of photons since they are the eigenstates of the Hamiltonian. However, the phases of the EMF are maximally uncertain; they are evenly spread over the whole range from 0 to 2π. That is why the average values of the field vectors vanish in all Fock states.

See also

Photon Picture of Light. **Quantum Electrodynamics:** Cavity QED.

Further Reading

Bialynicki-Birula I (1996) Photon wave function. In: Wolf E (ed.) *Progress in Optics*, vol. 36. Amsterdam, The Netherlands: Elsevier.

Bialynicki-Birula I and Bialynicka-Birula Z (1975) *Quantum Electrodynamics*. London: Pergamon.

Loudon R (1973) *The Quantum Theory of Light*. Oxford, UK: Clarendon Press.

Louisell W (1990) *Quantum Statistical Properties of Radiation*. New York: Wiley.

Mandel L and Wolf E (1995) *Optical Coherence and Quantum Optics*. Cambridge, UK: Cambridge University Press.

Power EA (1964) *Introductory Quantum Electrodynamics*. London: Longman.

Scully MO and Zubairy MS (1997) *Quantum Optics*. Cambridge, UK: Cambridge University Press.

Cavity QED

H Walther, University of Munich and
Max-Planck-Institute for Quantum Optics, Garching,
Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Modification of the Spontaneous Transition Rate in Confined Space

In order to understand the modification of the spontaneous emission rate in an external cavity-like structure, it must be remembered that in quantum electrodynamics this rate is proportional to the density of modes of the electromagnetic field, i.e., the vacuum field fluctuations above the atomic transition frequency ω_0. As a consequence the spontaneous emission rate is increased if the atom is surrounded by a cavity tuned to the transition frequency. Conversely, the decay rate decreases when the cavity is mistuned. This fact was already recognized in the pioneering days of nuclear magnetic resonance by Purcell.

The spontaneous decay rate of the atom in the cavity, γ_c, will then be enhanced in relation to that in free space, γ_f, by a factor given by the ratio of the corresponding mode densities

$$\frac{\gamma_c}{\gamma_f} = \frac{\rho_c(\omega_0)}{\rho_f(\omega_0)} = \frac{2\pi Q}{V_c \omega_0^3} = \frac{Q\lambda_0^3}{4\pi^2 V_c}$$

where V_c is the volume of the cavity and Q is the quality factor of the cavity which expresses the 'sharpness' of the mode. For low-order cavities $V_c \approx \lambda_0^3$ this means that the spontaneous emission rate is increased by roughly a factor of Q. As mentioned already, when the cavity is detuned, the decay rate will decrease. In this case the atom cannot emit a photon, since the cavity is not able to accept it, and the energy will stay with the atom, i.e., its decay is inhibited.

To change the decay rate of an atom, in principle no resonator has to be present; any conducting surface near the radiator affects the mode density and, therefore, the spontaneous radiation rate. Parallel conducting planes can alter the emission rate somewhat but can only reduce the rate by a factor of 2 owing to the existence of modes, independent of the plate separation with an electric field perpendicular to the planes.

In order to demonstrate experimentally the modification of the spontaneous decay rate, it is not necessary to go to single-atom densities. The experiments where the spontaneous emission is inhibited can also be performed with large atom numbers. However, in the opposite case, when the increase of the spontaneous rate is observed, a large number of excited atoms may disturb the experiment by induced transitions. The first experimental work on inhibited spontaneous emission was done by Drexhage, Kuhn and Schäfer in 1974. The fluorescence of a thin dye film near a mirror was investigated. A reduction of the fluorescence decay by up to 25% was observed. Later experiments with microcavities filled with dye solutions were performed by de Martini *et al.* These experiments demonstrated that thresholdless lasing is possible in such systems.

Inhibited spontaneous emission was observed by Gabrielse and Dehmelt. In these neat experiments with a single electron stored in a Penning trap they observed that cyclotron orbits show lifetimes which are up to 10 times longer than that calculated for free space. The electrodes of the trap form a cavity which decouples the cyclotron motion from the vacuum field leading to the longer lifetime.

A new stage in experiments on cavity QED was reached when it was recognized that highly excited alkaline atoms are very suitable for these experiments. The main quantum numbers are in the range $n = 20-60$. Those so-called Rydberg atoms couple very strongly to the radiation field as will be discussed later. The transitions to neighboring states are in the microwave region. The cavities can therefore be built as low-order cavities with dimensions on the order of the wavelength of the transitions being in the mm or cm regions. The spontaneous rate of these transitions in free space is small owing to the low value of their transition frequency, therefore an enhancement is possible. Experiments with Rydberg atoms on the inhibition of spontaneous emission have been performed by Kleppner and coworkers and by Haroche and coworkers. In the latter experiment a 3.4 μm transition of the Cs atom was suppressed.

The first observation of enhanced atomic spontaneous emission in a resonant cavity was published by Haroche *et al.* This experiment was performed with Rydberg atoms of Na excited in the 23s state in a niobium superconducting cavity resonant at 340 GHz. Cavity tuning-dependent shortening of the lifetime was observed. The cooling of the cavity had the advantage of totally suppressing the black-body field. The latter effect is completely absent if optical transitions are observed, however, in this case it is more difficult to obtain low-order cavities. The first experiments on optical transitions were performed by Feld and collaborators. They succeeded in demonstrating the enhancement of spontaneous transitions even in higher-order optical cavities.

In modern semiconductor devices both electronic and optical properties can be tailored with a high degree of precision. Therefore, electron–hole systems producing recombination radiation analogous to radiating atoms can be localized in cavity-like structures, e.g., in quantum wells. Thus optical microcavities of half or full wavelength size are obtained. Both suppression and enhancement of spontaneous emission in semiconductor microcavities were demonstrated in experiments by Yamamoto and collaborators. Yablonovitch *et al.* proposed the use of photonic band gap structures in semiconductors. In those systems spontaneous emission is forbidden in certain frequency regions owing to the special material properties.

Energy Shift in Confined Space

In the previous section we focused on changes of radiation rates of atoms near conducting walls or in cavity-like structures. Next we will discuss the more subtle phenomenon of energy shifts. While radiation rates are modified by the influence of the vacuum field on the real emission of photons the energy shifts are caused by the modification of a virtual photon interaction.

Resonant and nonresonant phenomena have to be distinguished. The resonant self-energy shift of a decaying atomic dipole in the vicinity of a conducting wall can be determined from the average polarization energy produced by the image dipole field. For distances comparable to the wavelength the near-field condition is satisfied, resulting in the z^{-3} dependence of the static dipole–dipole interaction characteristic for the van der Waals energy; under far-field conditions the distance dependence is given by z^{-1}. The polarization of the atom by the nonresonant parts of the broadband electromagnetic field causes energy shifts, of which the Lamb shift is the most prominent. In the sense of the nonrelativistic treatment by Bethe the major contribution of that shift can be described as being a result of the emission and reabsorption of virtual photons. It is plausible that just as the real emission of a photon is modified in confined space, so also is the virtual process. The latter ‘real’ radiation energy shift is thus a consequence of vacuum fluctuations only. It is identical with the energy shift predicted by Casimir and Polder and is analogous to the better-known result of Casimir on the force between two plane neutral conducting plates.

The question of modification of atomic energies in confined space has recently found considerable interest and many calculations of the phenomenon have been performed. Direct application to the energy shift of Rydberg atoms, which are of special interest for experimental studies, was performed by Barton in 1987. He calculated the direct electrostatic interaction with a conducting wall and the radiation induced (retarded) effects. The result is that in the case of two parallel plates the electrostatic effect is dominant when the distance L between the conducting plates is small, $L < n^3 a_0/\alpha$ (n is the principal quantum number of the Rydberg atom, a_0 the Bohr radius, and α the fine-structure constant), and the radiative effect plays the major role when large distances are used, $L > n^3 a_0 \alpha$.

Experiments to measure the van der Waals force of conducting planes have been performed by Hinds and coworkers. They could clearly demonstrate the z^{-3} dependence of the van der Waals force. The retarded effects were not detectable at large distances but at small distances from the wall a deviation from the z^{-3} dependence was found which was attributed to the retarded QED potential.

The energy shift of rubidium Rydberg atoms in confined space has been measured by Marrocco *et al.* in an experiment with extreme high-resolution using the Ramsey experiment two-field method. The atoms are excited in s-Rydberg states ($n \approx 30$) by two-photon transitions using the light of an ultrastable dye laser, the linewidth of which was less than 10 Hz. The laser intensity was enhanced in a folded cavity locked to the laser frequency. Both interaction zones necessary for the Ramsey method were enclosed in this cavity. Between the two interaction regions the atoms pass through a pair of conducting plates, the distance between which can be changed. The shift of the Ramsey interference was measured as a function of the plate distance. Using the Ramsey method has the advantage that the shift can be determined without a direct probing of the atoms in the space between the plates. A level shift on the order of about 150 Hz could be measured, in very good agreement with theory.

Maser Operation

If the rate of atoms crossing a cavity exceeds the cavity damping rate ω/Q, the photon released by each atom is stored long enough to interact with the next atom. Here ω stands for the cavity frequency and Q for the quality factor of the cavity. The atom–field coupling becomes stronger and stronger as the field builds up and evolves to a steady state. Using Rydberg atoms with a large field–atom coupling constant leads to a new kind of maser which operates with exceedingly small numbers of atoms and photons.

The photons corresponding to transitions between neighboring Rydberg atoms are in the microwave region at about 20–100 GHz. Atomic fluxes as small as a few atoms per second have generated maser action, as could be demonstrated by Walther *et al.* of the University of Munich in 1985 using a superconducting cavity. For such a low flux there is never more than a single atom in the resonator – in fact, most of the time the cavity is empty of atoms. It should also be mentioned that in the case of such a setup a single resonant photon is sufficient to saturate the maser transition.

The scheme for this one-atom maser or micromaser is shown in Figure 1. The setup represents the simplest system in radiation–atom interaction: a single atom is interacting with a single mode of the radiation field. This device was used to verify the complex dynamics of a single atom in a quantized field predicted by the Jaynes–Cummings model. All of the features are explicitly a consequence of the quantum nature of the electromagnetic field: the statistical and discrete nature of the photon field leads to new characteristic dynamics such as collapse and revivals in the exchange of a photon between the atom and the cavity mode. The frequency of this exchange is usually called the Rabi flopping frequency. The field in the cavity is measured through the number of atoms in the lower state of the maser transition. Due to the strong coupling between the atom and maser field both are entangled. The strong coupling can also be used to entangle subsequent atoms.

The steady-state field of the micromaser shows sub-Poisson statistics. This is in contrast to regular masers and lasers where coherent fields (Poisson statistics) are observed. The reason for nonclassical radiation being produced is that a fixed interaction time of the atoms is chosen, leading to careful control of the atom–field interaction dynamics.

Under steady-state conditions, the photon statistics $P(n)$ of the field of the micromaser are essentially determined by the pump parameter $\Theta = N_{\mathrm{ex}}^{1/2}\Omega t_{\mathrm{int}}$, denoting the angular rotation of the pseudospin vector of the interacting atom. Here, N_{ex} is the average number of atoms that enter the cavity during the decay time of the cavity τ_{cav}, Ω the vacuum Rabi flopping frequency, and t_{int} is the atom–cavity interaction time. The normalized photon number of the maser $\langle\nu\rangle = \langle n\rangle/N_{\mathrm{ex}}$ shows the following generic behavior


Rubidium oven
Superconducting niobium cavity
Velocity selective angle tuned UV laser
State selective field ionization of Rydberg atoms

Figure 1 Micromaser setup of rubidium Rydberg atoms in the 63p state. The velocity of the atoms is controlled by exciting a velocity subgroup of atoms in the atomic beam. The atoms in the upper and lower maser levels are selectively detected by field ionization. The number of photons deposited in the cavity is determined through the number of atoms in the lower state (61d).



Figure 2 One-atom maser or micromaser characteristics. The upper part of the figure shows the average photon number versus interaction time (solid curve) and the photon number fluctuations represented by the Q-factor (dotted line). Both curves are determined by the photon exchange dynamics between atom and field. The pump parameter gives the angular rotation of the pseudospin vector of the interacting atom (e.g., 2π corresponds to a full rotation, i.e., the atom is again in the upper level). In the lower part of the figure the steady-state photon number distribution $P(n)$ is shown for three values of t_{int}. The distribution on the left side corresponds to the maser threshold, that on the right gives an example of the double-peaked distribution associated with the quantum jump behavior. In this situation, the atom is back in the excited state and can again emit, leading to a higher steady-state photon number n_{h}. With increasing t_{int} this part will grow and n_{l} will decrease and disappear. A new jump occurs in the region 3b.

(see Figure 2). It suddenly increases at the maser threshold value $\Theta = 1$ and reaches a maximum for $\Theta \approx 2$ (denoted by 1 in Figure 2). The behavior at threshold corresponds to the characteristics of a continuous phase transition. As Θ increases further, the normalized averaged photon number $\langle \nu \rangle / N_{\text{ex}}$ decreases to a minimum slightly below $\Theta \approx 2\pi$, and then abruptly increases to a second maximum (3a in Figure 2). This general type of behavior recurs roughly at integer multiples of 2π, but becomes less pronounced with increasing Θ. The reason for the periodic maxima of the average photon number is that for integer multiples of $\Theta = 2\pi$ the pump atoms perform an integer number of full Rabi flopping cycles, and start to flip over at a slightly larger value of Θ, thus leading to enhanced photon emission. The periodic maxima for $\Theta = 2\pi, 4\pi$, and so on may be interpreted as first-order phase transitions.

The photon statistics of the maser radiation is usually characterized by the Q-parameter introduced by Mandel:

$$Q_{\text{field}} = \left\{ \left(\langle n^2 \rangle - \langle n \rangle^2 \right) / \langle n \rangle \right\} - 1$$

It can be seen that $Q_{\text{field}} = 0$ corresponds to a Poissonian photon distribution. Q_{field} for the micromaser is plotted as a dotted line in Figure 2. The value drops below zero in the region 2a, 2b, etc. This shows the highly sub-Poissonian character of the one-atom-maser field being present over a large range of parameters.

The reason for the sub-Poissonian atomic statistics is the following. A changing flux of atoms changes the Rabi frequency via the stored photon number in the cavity. Adjusting the interaction time allows the phase of the Rabi nutation cycle to be chosen such that the probability of the atoms leaving the cavity in the upper maser level increases when the flux, and hence the photon number in the cavity, is raised. This leads to sub-Poissonian atomic statistics since the number of atoms in the lower state decreases with increasing flux and photon number in the cavity. This feedback mechanism can be neatly demonstrated when the anticorrelation of atoms leaving the cavity in the lower state is investigated. Measurements of this anticorrelation phenomenon could be made.

The fact that anticorrelation is observed shows that the atoms in the lower state are more equally spaced than expected for a Poissonian distribution of the atoms in the beam. This means, for example, that when two atoms enter the cavity close to each other, the second one performs a transition to the lower state with reduced probability.

The interaction with the cavity field thus leads to an atomic beam with atoms in the lower maser level showing number fluctuations which are up to 40% below those of a Poissonian distribution found in usual atomic beams. This is interesting because atoms in the lower level have emitted a photon to compensate for cavity losses inevitably present. Although this process is induced by dissipation giving rise to fluctuations, the atoms still obey sub-Poissonian statistics.

Generation of Number States (Fock States) of the Radiation Field

When the micromaser is operated at low temperatures, a very interesting feature is observed in the inversion of the population of the two maser levels called trapping states. They are a steady-state feature of the maser field; they occur in the micromaser as a direct consequence of field quantization in a cavity. At low cavity temperatures the number of black-body photons, n_{th}, in the cavity mode is reduced and trapping states begin to appear; at higher temperatures they are washed out by the thermal photons. The trapping states show up when the atom–field coupling Ω and the interaction time t_{int} are chosen such that in a cavity field with n_{q} photons the atoms undergo an integer number k of Rabi cycles. This is summarized by the condition

$$\Omega t_{\mathrm{int}}\sqrt{n_{\mathrm{q}}+1}=k\pi \qquad [1]$$

for the trapping state, denoted by (n_{q}, k). When eqn [1] is satisfied, the cavity photon number is left unchanged after interaction of an atom and hence the photon number is 'trapped'. This will occur regardless of the atomic pump rate N_{ex}. The trapping state is therefore characterized by the upper-bound photon number n_{q} and the number of integer multiples of full Rabi cycles k. In this situation the field is stabilized. Whenever a photon disappears, e.g., due to dissipation, the next incoming atom experiences a changed Rabi nutation frequency and emits a photon with high probability. At the trapping condition a quantum nondemolition situation is present. Through the dynamics of the Rabi nutation the field is measured, without any net change of the field.

The build-up of the cavity field can be seen in Figure 3, where the emerging atom inversion is plotted against the interaction time and pump rate. At low atomic pump rates (low N_{ex}) the maser field cannot build up and the maser exhibits Rabi oscillations due to the interaction with the vacuum field. At the positions of the trapping states, the field increases until it reaches the trapping-state condition. This is manifested as a reduced emission probability and hence as a dip in the atomic inversion. Once in a trapping state, the maser will remain there regardless of the pump rate.



Figure 3 Behavior of the micromaser at low temperature showing the trapping states, manifested as valleys along the N_{ex} axis. For the designation of the trapping states see text.

Under ideal conditions the micromaser field in a trapping state is a Fock state, but when the micromaser is operated in a continuous wave mode, the field state is very fragile and highly sensitive to external influences and experimental parameters. However, in contrast to continuous-wave operation, in pulsed operation trapping states are more stable and more practical and can be used over a much broader parameter range than in continuous-wave operation.

To demonstrate the principle, Figure 4 shows a simulation of a sequence of 20 pulses of the pumping atoms in which an average of seven excited atoms per pulse are present. Under the trapping condition only a single emission event occurs, producing a single lower state atom which leaves a single photon in the cavity. Since the atom–cavity system is in the trapping condition, the emission probability is reduced to zero and the photon number is stabilized. Consequently, excited state atoms following the emitting atom stay in the upper maser level. The variation of the time when an emission event occurs during the atom pulses in Figure 4 is due to the Poissonian spacing of upper-state atoms entering the cavity and the stochasticity of the quantum process.

The lower part of Figure 4 shows the photon number distribution resulting from this process. It was demonstrated experimentally by Brattke *et al.* that a single photon number state could be generated with a success rate of 85%. By improving the experimental parameters one can expect to prepare single-photon Fock states in 98% of the pulses by this method.

Other Cavity Experiments

Besides the micromaser, there are also other experiments using Rydberg atoms in cavities and the strong interaction of these atoms with cavities which lead to interesting applications. One example is an experiment by S. Haroche, J. M. Raimond *et al.*, who succeeded in realizing a Schrödinger cat state in a cavity. Studies on the decoherence of this state could be conducted. The experiments are quite important in exploring the boundaries between the quantum and classical worlds. Another example is the quantum nondemolition detection of a single photon in a cavity by S. Haroche employing the dispersion level shift of probing atoms.

There is an interesting equivalence between an atom interacting with a single-mode field and a quantum



Figure 4 A simulation of a subset of 20 subsequent atom bunches generated by pulsed laser excitation with the associated probability distribution for photons in the cavity or lower-state atom production (filled circles represent lower-state atoms and open circles represent excited-state atoms). The start and end of each pulse is indicated by the vertical dotted lines marked 0 and τ_{pulse}, respectively. For details, see Battke S, Varcoe BTH and Walther H (2001) Generation of photon number states on demand via cavity, quantum electrodynamics. *Physical Review Letters* 86: 3534–3537.

particle in a harmonic potential, as was first pointed out by D. F. Walls and H. Risken; this connection results from the fact that the radiation field is quantized on the basis of the harmonic oscillator. The Jaynes–Cummings dynamics can therefore also be observed with trapped ions, as recently demonstrated in a series of beautiful experiments by D. Wineland *et al.* They also produced a Schrödinger cat state by preparing a single trapped ion in a superposition of two spatially separated wavepackets which are formed by coupling different vibrational quantum states in the excitation process.

Besides the experiments in the microwave region, a single-atom laser emitting in the visible range has also been realized by M. Feld *et al.* Furthermore, cavity quantum electrodynamic effects have been studied in the optical spectral region by J. L. Kimble *et al.*

Today's technology in microfabrication of semiconductor diode structures allows the realization of low-order cavity structures for diode lasers. In these systems the spontaneous emission is controlled in the same way as in the micromaser. Since spontaneous decay is a source of strong losses, control of this phenomenon leads to highly efficient laser systems. Quantum control of spontaneous decay thus has important consequences for technical applications. This topic will be briefly described in the next section.

Microlasers

The simplest approach to fabricating an optical microcavity is to shrink the spacing between the mirrors of a Fabry–Perot resonator to λ/n (where n stands for the refractive index) while reducing the lateral dimensions to a range of the same order of magnitude. This structure provides a single dominant longitudinal field mode that radiates into a narrow range of angles around the cavity axis.

The first optical microcavity experiments used dye molecules between high-reflectivity dielectric mirrors in the Fabry–Perot configuration. Because spontaneous emission is a major source of energy loss, speed limitations, and noise in lasers, the capability to control spontaneous emission is expected to improve laser performance. If the fraction of spontaneous emission coupled into the lasing mode is made close to one, the 'thresholdless' laser is obtained, in which the light output increases almost linearly with the pump power instead of exhibiting a sharp turn-on at the pump threshold.

Semiconductor microcavities provide high-Q Fabry–Perot cavities for both basic studies and potential applications. Molecular beam epitaxy or organometallic chemical vapor deposition techniques are used to deposit high-reflectivity mirrors consisting of alternating quarter-wavelength layers of lattice-matched semiconductors. For example, 15–20 pairs of quarter-wave layers of $Al_{0.2}Ga_{0.8}As$ and AlAs result in a reflectivity greater than 99% and Q values greater than 500. The optically active layer in such a microcavity is typically a GaAs quantum well located at the midplane of the cavity, where the field strength is maximum.

Since the microcavities have an extremely low threshold, their efficiency will also be high. Low-cost, high-density light source arrays and photonic circuits are made possible by the small size and low power consumption of such resonators. It will be possible to produce entire wafers containing millions of microlasers with a multipole arrangement instead of having to cleave each individual semiconductor laser as at present. This improvement will lead to higher yields and lower cost per element. Another advantage of surface-emitting microcavity sources is the efficient optical coupling of their stable symmetric mode patterns into optical fibers or waveguides. These lasers are thus certain to spark a revolution in optical communication in the future.

Conclusion

This article reviewed experiments in cavity quantum electrodynamics. The experiments shed new light on our understanding of the radiation interaction of atoms. The achievable strong coupling between atoms and radiation leads to the possibility to generate entanglement between the generated radiation field and the atoms, presenting a basis for interesting applications in connection with, e.g., quantum computing and quantum information processing. Furthermore Fock states of the radiation field can be generated. The control of spontaneous decay finally leads to interesting new laser systems offering high efficiency.

See also

Quantum Electrodynamics: Cavity QED in Semiconductors; Quantum Theory of the Electromagnetic Field. **Quantum Optics:** Quantum Computing with Atoms.

Further Reading

Berman PR (1994) Cavity quantum electrodynamics. In: Bederson B and Bates D (eds). *Advances in Atomic, Molecular, and Optical Physics*, Supplement 2. Boston, MA: Academic Press.

Englert B-G, Löffler M, Benson O, *et al.* (1998) Entangled atoms in micromaser physics. *Fortschritte der Physik* 46: 897–926.

Haroche S (1992) Cavity quantum electrodynamics. In: Dalibard J, Raimond J-M and Zinn-Justin J (eds) *Fundamental Systems in Quantum Optics*. pp. 767–935. Amsterdam: North-Holland.

Haroche S and Kleppner D (1989) Cavity quantum electrodynamics. *Physics Today* 42: 24–30.

Kimble HJ, Carnal O, Georgiades N, *et al.* (1995) Quantum optics with strong coupling. In: Wineland DJ, Wieman CE and Smith SJ (eds) *Atomic Physics*, vol. 14, pp. 314–335. New York: American Institute of Physics.

Marrocco M, Weidinger M, Sang RT and Walther H (1998) Quantum electrodynamic shifts of Rydberg energy levels between parallel metal plates. *Physical Review Letters* 81: 5784–5787.

Meschede D (1992) Radiating atoms in confined space: from spontaneous emission to micromasers. *Physics Reports* 211: 201–250.

Meystre P (1992) Cavity quantum optics and the quantum measurement process. In: Wolf E (ed.) *Progress in Optics*, vol. 30. Amsterdam: North-Holland.

Walther H (1992) Experiments on cavity quantum electrodynamics. *Physics Reports* 219: 263–281.

Cavity QED in Semiconductors

M Kira, W Hoyer and S W Koch,
Philipps-University, Marburg, Germany

G Khitrova and H M Gibbs,
University of Arizona, Tucson, AZ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

According to classical electromagnetism, propagating light fields obey Maxwell's equations under which electric and magnetic fields exchange their strength in an oscillatory manner. If a propagating field is followed at a single reference point, it is convenient to represent the electric field as a complex number $|E(t)|\exp(-i\omega t)$ where $|E(t)|$ is the magnitude of the field and the phase of the field $\exp(-i\omega t)$ oscillates in time t with the optical frequency ω. Figure 1 illustrates how the classical field is determined by one single point in the complex plane; consequently, the phase and amplitude of the field are known exactly. According to quantum mechanics, this simple picture has to be altered because the Heisenberg uncertainty relation states that complementary quantities like phase and amplitude cannot be determined precisely at the same time. As a result, the real and imaginary parts of the field can be determined only with accuracy $\Delta\mathrm{Re}[E]$ and $\Delta\mathrm{Im}[E]$, respectively, and the Heisenberg uncertainty principle determines the best possible accuracy $\Delta\mathrm{Re}[E]\,\Delta\mathrm{Im}[E] \geq 1$. To incorporate the fundamental inaccuracy, the electric field has to be defined by using complex-valued distributions or equivalently wavefunctions as shown in Figure 1. This quantization procedure leads to the Schrödinger equation for light analogous to that for particles. The field called quantum optics investigates the quantum electrodynamics (QED) features of light.



Figure 1 (a) The classically described light field $E(t)$ is a single point in the complex XY-plane; the corresponding (X, Y) vector has a definite phase and angle. (b) Quantum mechanically described light is a distribution with fluctuations ΔX and ΔY described by the shaded circle.



Figure 2 (a) A typical vertical-cavity surface-emitting laser (VCSEL) structure; a stack of quarter-wavelength layers with different refractive index provides a mirror such that the light intensity (solid line) is strongly confined inside the cavity. A quantum well (QW) is positioned at the field maximum. (b) In a microdisk laser, light encounters ideal total reflection when the edge of the disk is reached. The so-called whispering gallery mode emits (leaks) light from the edge. (c) A schematic illustration of semiconductor band structure, bandgap, and Coulomb interaction for an electro–hole system.

In general, light does not propagate freely in space, but it interacts strongly with the surrounding matter. For example, light can be absorbed, and its energy can be converted into excitation of the matter. As a result, the light may be slowed down, reflected, scattered, or diffracted. In order to explain the implications of the light–matter interaction in detail, one obviously has to apply a quantum mechanical description also for the matter. This approach determines the so-called eigenstates of the matter, so that the matter may occupy only certain discrete states with discrete energies. The Rydberg series of a hydrogen atom is a typical example. Similar discrete energy levels are also found for the quantized light; these levels are often referred to as photons which heuristically describe the particle properties of the light. The lowest-order light–matter interaction consists of processes where one photon is absorbed (emitted) while the matter is simultaneously excited (de-excited) from one eigenstate to another. This generic type of interaction leads to a microscopic description of the optical effects mentioned above. The magnitude of these effects depends on the strength of the interaction. By implementing different cavity configurations, the reflected light can be forced to travel across the same matter many times. As a result, the light–matter interaction is enhanced by a factor proportional to the multiple passes of the light. Thus, a cavity can be efficiently used to amplify optical phenomena. Figure 2 shows cavity configurations commonly used for semiconductors. Semiconductor cavity QED investigates quantum optical effects in semiconductor systems by enhancing them with cavity mirrors. In general, quantum optical features produce classically unexpected effects which typically stem from: (a) the discrete nature of eigenstates of light and matter; (b) the superposition principle of quantum mechanics; and (c) the Heisenberg uncertainty principle. In this article, we review both theoretical and experimental advances made so far to predict, observe, and control quantum optical effects in semiconductors with respect to effects (a)–(c).

During the last few decades, atomic quantum optics has already developed toward QED investigations, and semiconductor optics is developing rapidly into the same regime. Advanced atomic QED theories have successfully explained and guided intriguing experimental developments like laser cooling, atom condensation, and photon teleportation. However, the atomic approach can mostly be applied to describe dilute and only weakly interacting atomic gases since relatively simple models of few-level systems are used to describe the material. The elementary electronic excitations in semiconductors consist of electrons and holes (missing electrons) lifted into the conduction and valence bands, respectively. The corresponding eigenstates form continuous energy bands with the band-gap energy separation indicated in Figure 2. Since electrons and holes have opposite charges, they experience Coulomb attraction whereas bare electrons or holes repel each other. Under favorable conditions, the attractive Coulomb interaction prevails and atom-like bound electron–hole pairs (excitons) may be formed. However, since the Coulomb force has an infinite range and an electron–hole system is typically dense, excitons cannot be treated as weakly interacting quasiparticles. As a result, the atomic QED approaches cannot be used to describe quantum optics of semiconductors in general. Thus, this article concentrates mostly on semiconductor QED theory which fully includes the interaction of charge carriers, i.e., electrons and holes, as well as quantum features of light.

The development work on quantum devices and processes is vital for advancements in several key technologies such as computers and telecommunications. The continuous decrease in component dimensions leads to a microscopic structure size (less than 1 μm); at the same time, increase in the device performance is accompanied by ultrafast operation time (faster than 1 ps). Due to these development trends, the properties of components and processes are becoming more and more quantum mechanical. Although the description of the quantum processes is complicated, the microscopic behavior offers entirely new operational functionality such as massively parallel quantum computers. These possibilities are based on the controlled manipulation of the quantum mechanical state of the light and matter. Due to rapid recent developments, optically coupled semiconductor devices have a great potential to become technologically successful and commercially viable quantum components.

Quantized States: Observation via Strong Light–Matter Interaction

In order to enhance the light–matter interaction, we choose a system where the semiconductor is placed inside a cavity in the position where the field intensity is maximum. For an empty cavity, the field intensity has a strong dependence upon frequency with a strong resonance at ω_R when the cavity length is an integer number of light wavelengths in the material. The width of the resonance is directly related to the quality of the cavity as determined by the number of back-and-forth reflections of light inside the cavity. If one chooses a vertical-cavity surface-emitting laser (VCSEL) structure, the most efficient coupling is obtained by placing a thin planar semiconductor structure at the field maximum as shown in Figure 2. If the semiconductor is planar and thin, the structure is called a quantum well because electrons and holes are confined in one direction in analogy to the standard particle-in-a-box problem of fundamental quantum mechanics. As a result, the energy levels of a quantum well are discrete in the confinement direction. If the structure is narrow enough, the system dynamics is confined to the lowest quantum-well level such that the carriers are quasi-two-dimensional due to the free in-plane motion. The optical response of such a system to a weak classical probe beam has been successfully analyzed with the so-called semiconductor Bloch equations. For the quantum-well system alone, the absorption spectrum may have a sharp resonance; this is often referred to as an excitonic resonance since it is located below the fundamental bandgap energy at a position corresponding to the exciton binding energy. Obviously, the light–matter coupling becomes large when the exciton and cavity resonances coincide. However, since these resonances are coupled, the optical response is altered; we observe a splitting into two absorption peaks instead of the original degenerate resonances. This phenomenon is commonly referred to as normal-mode coupling; in general, it is a quite common feature in quantum mechanics that degenerate states split due to an additional interaction. Figure 3 shows the first experimental observation of normal-mode coupling in semiconductors.

Since a semiconductor is a strongly interacting many-body system, several effects alter the specific character of an excitonic resonance when electrons and holes are excited. The attractive interaction between electrons and holes becomes weaker for



Figure 3 Probe reflectivity of a seven-quantum-well microcavity structure. The various curves correspond to the energy difference between exciton and cavity resonances. When these resonances become degenerate, the reflectivity shows two resonances corresponding to the normal-mode splitting. From Weisbuch C, Nishioka M, Ishikawa A and Arakawa Y (1992) Observation of the coupled exciton-photon mode splitting in a semiconductor quantum microcavity. *Physical Review Letters* 69: 3314. Copyright (2004) by the American Physical Society.

increased carrier density since the surrounding charges screen the bare Coulomb interaction. A particular exciton may also experience scattering from nearby electrons, holes, or other excitons via the Coulomb interaction. Furthermore, electrons and holes are Fermions, which requires that any given carrier state can only be occupied once. This poses fundamental limits on how many carriers can coexist in a specific volume; above a certain limit, additional occupation is prevented, and so-called Pauli blocking is observed. Since an exciton consists fundamentally of Fermionic constituents, eventually Pauli blocking effects become important even for excitons. Due to a combination of these many-body effects, the excitonic resonance is weakened by an increasing carrier density. Figure 4 shows a comparison between theory and experiment of the excitonic absorption spectrum for different carrier densities. For elevated densities, the exciton resonance is broadened and its height reduced. When the same investigations are repeated in a microcavity, we observe that the normal-mode peaks decrease in height but their separation is roughly unchanged for moderate densities. In general, the normal-mode spitting is proportional to the oscillator strength of the excitonic absorption, i.e., the area under the resonance. Thus, the observed constant splitting suggests an unchanged oscillator strength for moderate densities. The invariant oscillator strength was unexpected and can only be explained by using a theory which includes the Coulomb interaction of carriers microscopically. When the carrier density is increased even further, the exciton resonance is completely bleached, and the microcavity transmission has only a single peak, at the cavity mode energy; this is commonly referred to as the weak-coupling regime, in contrast to the nonperturbative strong coupling with two transmission peaks. The strong coupling regime provides several intriguing phenomena; for example, parametric amplification of emission has been demonstrated by applying simultaneously multiple light beams to the sample.



Figure 4 Left column: (a) microscopically computed bare quantum-well absorption spectrum, i.e., the imaginary part of the susceptibility, as a function of carrier density. (b) Calculated transmission of the quantum-well microcavity for corresponding densities. The right column shows experimentally determined (a) absorption and (b) microcavity transmission for the same conditions as in the calculations. From Jahnke F, Kira M, Koch SW, *et al.* (1996) Excitonic nonlinearities of semiconductor microcavities in the nonperturbative regime. *Physical Review Letters* 77: 5257. Copyright (2004) by the American Physical Society.

The ultimate cavity QED limit of normal-mode coupling follows when the light–matter interaction is so strong that even a single photon leads to splitting (genuine strong coupling). We briefly outline some aspects of the quantum statistical limit known from atomic physics. This situation can be analyzed with the so-called Jaynes–Cummings model where only two states of the atom are included together with a single light mode. In this case, the interaction between a single photon and an atom leads to a normal-mode splitting g_0. If two photons interact with one atom, the splitting increases to $2^{1/2}g_0$; more generally coupling between n photons and an atom leads to a splitting of $n^{1/2}g_0$. In the QED limit, the matter response is very nonlinear because one can detect the quantized nature of light directly from the energy splitting. This limit has already been reached in atomic cavity QED, whereas this regime is hard to approach with semiconductors because they behave more like multi-atom systems. If one has N atoms in a cavity, the first photon excites one atom, but there are N different ways of doing this, so the splitting is $N^{1/2}g_0$. If a second photon arrives, it interacts with the remaining unexcited atoms rather than the excited one, so that the splitting remains $N^{1/2}g_0$ as long as the number of photons is much smaller than N. Thus, in an N-atom system, or equivalently in semiconductors, the quantized light effects are much harder to observe than for a single atom. Currently, the normal-mode splitting in a semiconductor microcavity is explainable by the classical features of light, so that only the quantized nature of the matter is observed. In order to approach the ultimate cavity QED limit, one obviously has to reduce N and increase the light–matter coupling. In the future, this objective might be possible in quantum-dot/nanocavity systems where the semiconductor is confined in all spatial directions.

When an excited semiconductor is not under any influence of external classical light fields, it can still emit light via spontaneous emission resulting from the recombination of electron–hole pairs. The resulting light emission is called photoluminescence. Since the emission process takes place in a strongly interacting many-body system, one has to systematically include the Coulomb interaction and Fermionic features. The emission properties can be consistently described by the so-called semiconductor luminescence equations. When the microcavity photoluminescence spectrum is investigated, one observes a similar normal-mode splitting as for the transmission studies. However, this normal-mode coupling is not in the ultimate cavity QED limit even though the quantum fluctuations of the light field trigger the spontaneous emission. Nevertheless, the luminescence shows an interesting new transition as a function of the excitation level. Figure 5 contains a comparison between theory and experiment of normal-mode peak heights and positions as a function of carrier density. For low densities, the high-energy peak is lower in height but it overtakes the low-energy peak for moderate carrier densities that are still below lasing threshold. This threshold-like overtaking was attributed to Boser action, involving exciton formation, final-state stimulation, and Bose condensation. The inset shows an estimate of just how Bosonic the excitons are, i.e., how much they actually behave as independent atoms; the value unity corresponds to the fully Bosonic situation. The nonlinear luminescence transition takes place at a density regime where the underlying Fermionic electron and hole contributions become important (commutator is roughly 0.5). A more detailed analysis with the semiconductor luminescence equations shows that Fermionic carrier nonlinearities in a detuned cavity are responsible for the experimental observations. This example of a misinterpretation based on a Bosonic analysis stresses how important it is to include the Coulomb interaction and Fermion character of carriers when analyzing the properties of semiconductors.



Figure 5 Measured microcavity luminescence intensities (a) and peak energies (c) versus excitation intensity for the high-energy peak (solid line) and the low-energy peak (dashed line). The results of the microscopic theory are shown in (b) and (d). From Kira M, Jahnke F, Koch SW, *et al.* (1997) Quantum theory of nonlinear semiconductor microcavity luminescence explaining "boser" experiments. *Physical Review Letters* 79: 5170. Copyright (2004) by the American Physical Society.

Superposition Principle: Observation of Quantum Optical Correlations

The above normal-mode-coupling investigations have shown interesting nonlinear effects, but they also revealed that the ultimate QED limit – demonstrating discrete states of light directly – has not yet been reached. Alternatively, a QED investigation may concentrate on other fundamental features of quantum mechanics. One possibility is to study the implications of the superposition principle which states that the joint properties of a light–matter system can always be expressed as a superposition that combines light and matter wavefunctions. The most dramatic consequence can be observed in so-called entangled wavefunctions which cannot be factorized into light and matter parts. In a factorized wavefunction, the light and matter parts are independent whereas entangled wavefunctions conditionally connect light and matter wavefunctions. To elaborate the subtle details of entanglement, we first analyze a simple example. Assume that light can be in two different polarization states, $|\sigma^+\rangle$ or $|\sigma^-\rangle$, and the matter part is either excited $|\mathrm{up}\rangle$ or de-excited $|\mathrm{down}\rangle$. A wavefunction, $[|\mathrm{up}\rangle + |\mathrm{down}\rangle][|\sigma^+\rangle + |\sigma^-\rangle]$, is clearly a superposition of the fundamental states, and at the same time the light and matter parts are completely factorized. However, the wavefunction $[|\mathrm{up}\rangle\ |\sigma^+\rangle + |\mathrm{down}\rangle|\sigma^-\rangle]$ is entangled, since the light and matter parts cannot be separated. In the entangled state, measurement on the light state will conditionally determine a definite state of the matter, whereas the factorized state has no such conditionality. The entanglement has far-reaching consequences which cannot be understood with a classical analysis. For example, the principles of teleportation and quantum computing follow directly from the controlled manipulation of different parts of the entangled wavefunction. For atomic systems, wavefunction entanglement has been demonstrated and utilized in several experiments. For semiconductors, the direct manipulation and detection of the wavefunction seems difficult due to the overwhelming complexity of the many-body wavefunctions. Once again, the entanglement and the wavefunction are simplest for low-dimensional structures; direct entanglement effects have been demonstrated recently in a single quantum dot and between a pair of dots. Also for more complicated semiconductor systems, such as a quantum well in a microcavity, the entanglement can be observed as correlations between light and matter. In this case, the existence of QED correlations basically means that light and matter properties depend conditionally on each other. In general, the direct entanglement and QED correlation investigations have a large development potential for semiconductors.

When a semiconductor is excited with an external light pulse, entanglement-related correlations couple the classical and luminescence emission dynamics. The resulting dynamic interplay between the semiconductor Bloch and luminescence equations is mainly mediated by the correlation between photons and electron–hole densities. In the following, we analyze a microcavity configuration where a strong pump pulse generates large QED correlations. The effect of the correlations is then measured by the response of a weak probe beam. Figure 6 shows a comparison of theory and experiment of probe reflection in a configuration where the pump and probe do not have any spectral overlap. The measured probe reflection displays long-living oscillations as a function of time delay, i.e., phase difference, between the pump and the probe. Only by including the QED correlation in the theory can the oscillatory probe reflection be explained. When the QED contributions are omitted from the theory, the phase difference does not have any effect on the probe reflection. Thus, this experiment–theory example represents a direct observation of the cavity QED effects in semiconductors. Figure 6 also shows more pronounced oscillations when two phase-locked pump pulses provide the excitation; again the full QED theory explains the enhanced oscillation features.

The QED features can also alter the normal-mode coupling characteristic of a weak probe beam. Figure 7 shows a comparison of theory and experiment for a situation where the pump spectrum is



Figure 6 (a) Measured differential reflectivity and (b) computed reflection probability of the probe pulse as function of probe delay with respect to the excitation pulse. For two-pulse excitations, ±130° relative phase shifts are used. The dotted line is computed without the QED correlations. From Lee Y-S, Norris TB, Kira M, *et al.* (1999) Quantum correlations and intraband coherences in semiconductor cavity QED. *Physical Review Letters* 83: 5338. Copyright (2004) by the American Physical Society.



Figure 7 Dependence of probe transmission on probe intensity (nJ cm^{-2}) at a constant pump intensity of 330 nJ cm^{-2} for the microcavity. (a) Experiment, and (b) theory. The shaded regions indicate the pump spectrum. From Ell C, Brick P, Hübner M, *et al.* (2000) Quantum correlations in the nonperturbative regime of semiconductor microcavities. *Physical Review Letters* 85: 5392. Copyright (2004) by the American Physical Society.

located between the two normal-mode coupling resonances. Both the theory and experiment show a new third resonance which follows the energetic position of the pump. The third peak is a direct consequence of the QED correlations. Since the third peak is generated from the QED field–carrier correlations generated by the pump pulse, its magnitude follows the intensity of the pump. As the probe intensity is decreased the relative effect of the QED correlations is increased so that the third peak grows in the probe transmission.

In these QED investigations, the cavity plays an important role since the mirror feedback leads to a significant amplification of the QED effects through the enhanced light–matter coupling. From a practical point of view, normal-mode coupling also provides well-separated spectral features which can be used as classical-emission reference points.

Heisenberg Uncertainty Principle: Squeezing of Light Emission

Quantized light effects can also be investigated by measuring the light fluctuations of the field directly. To maximize the quantum effects, we analyze the field fluctuations in the emission directions where the classical field vanishes. This situation can be realized in planar quantum-well structures which are nearly free of disorder. In such systems, a light pulse propagating perpendicular to the structure leads to transmission and reflection of classical light only along the excitation axis. If the detection is performed at an angle, the so-called secondary emission is purely quantum mechanical. However, the classical and quantum emissions are coupled in the same way as for the QED correlation study. The resulting fluctuations of secondary emission obey the Heisenberg uncertainty principle; in the following, the special quantum features of these fluctuations are investigated.

In the full analysis, we determine the variance ΔX and ΔY of the emission as shown in Figure 8 (see also Figure 1). The Heisenberg uncertainty principle requires that the quadrature fluctuations obey $\Delta X \Delta Y \geq 1$. For a specific quadrature, the minimum uncertainty limit is usually defined to be $\Delta X = 1$ or $\Delta Y = 1$. If ΔX and ΔY are different, the observed light field is squeezed; and if the variance in one quadrature is less than one, the field is squeezed below the minimum uncertainty limit. In both cases, the field has a strong quantum nature; in particular, squeezing below unity suggests that measurements can be more accurate than the standard quantum limit for that quadrature.

To illustrate the behavior of the quantum fluctuations, we excite the quantum well resonantly with a relatively strong pulse. The emission is detected at an angle of 45° away from the excitation axis. Since the excitation pulse is relatively strong, the carrier density starts to oscillate during the pulse because Fermionic carriers can be excited only once; thus, further excitation actually leads to de-excitation. In other words, when these states become almost fully excited, the pulse can no longer excite the system, and we observe periodic de-excitation and excitation analogous to the Rabi-flopping of a strongly excited two-level system. Figure 8 shows the exciting pulse and corresponding quadrature fluctuations during the excitation process. As long as the pulse is present, the squeezing is at the 4% level and oscillates with the Rabi-flopping frequency. The quadrature fluctuations clearly show squeezing below the minimum uncertainty limit. Hence, the field has obvious quantum properties.

Similar squeezing and quantum characteristics statistics have been predicted and observed in the photon statistics of resonance fluorescence from two-level atoms subjected to an intense coherent light beam. The quantum properties of the scattered light



Figure 8 (a) Time-resolved maximum (solid line) and minimum (dashed line) deviations of the mode quadratures from the vacuum value of unity. (b) Corresponding time-resolved carrier density (solid line) and excitation pulse (dashed line). From Kira M, Jahnke F and Koch SW (1999) Quantum theory of secondary emission in optically excited semiconductor quantum wells. *Physical Review Letters* 82: 3544. Copyright (2004) by the American Physical Society.

in both quantum-well and atomic emission are enhanced when the driving field forces the system to oscillate between the excited and de-excited state. Just as described above, when the system becomes de-excited, it can no longer emit an additional photon; this inhibition manifests itself as sub-Poissonian photon statistics and squeezing in the mode quadratures. When the excitation pulse re-excites the system, such restrictions are no longer imposed. Thus, the field properties show quantum features oscillating with the Rabi-flopping frequency. Squeezing effects can also be observed with excitation by an electric current; for example, amplitude squeezing of diode laser emission has been demonstrated by controlling the electron statistics of the current flow.

The squeezing investigations demonstrate that some QED effects are expected to be seen without a cavity. Figure 9 shows the quadrature fluctuations when the cavity is added to the squeezing analysis. We observe qualitatively similar squeezing, but now the level of squeezing is enhanced up to 30% compared to the minimum uncertainty. This is once again a demonstration how QED effects can be amplified by using an increased light–matter coupling provided by the cavity.



Figure 9 Squeezed light from a quantum well inside a microcavity: (a) the time evolution of maximum and minimum of the quadrature fluctuations; (b) the corresponding density and light field intensity at the quantum well.

Summary

This article overviews some of the most intriguing features of cavity quantum electrodynamics in semiconductors. Even though the related research has started only recently, several important quantum phenomena have already been predicted and measured: (a) the discrete quantum mechanical states of light and/or matter can be measured with strong coupling; (b) the consequences of the superposition principle have been detected as light–matter entanglement; and (c) the Heisenberg uncertainty principle has been tested via the squeezing of light. In all cases, the cavity enhances light–matter coupling leading to more pronounced quantum effects. Compared to atomic systems, the semiconductor has strong Coulomb correlation effects due to the relatively high density, which makes the analysis challenging. However, the semiconductor can also provide new mechanisms like the photon/carrier-density correlations which trigger new unexpected quantum phenomena.

The field of semiconductor quantum optics is very active and is developing rapidly. It benefits both from advances in computer capabilities and in semiconductor crystal growth. The increasing computer capacity allows more profound, accurate, and realistic modeling of semiconductor structures. At the same time, advances in crystal growth technology provide us with improved samples which are almost disorderless. In particular, the growth of quantum wells with narrower exciton linewidths and quantum dots with larger dipole moments and reduced dephasing rates may be achieved, which is certain to make quantum features increasingly apparent and unavoidable.

All these research efforts eventually focus on producing devices utilizing quantum mechanical principles. One of the main objectives endeavors to develop quantum logic components for building blocks of quantum computers. Similar expanding possibilities can be expected, e.g., for accuracy of detection, device efficiency, and component design in general. Considering all of this, we are almost guaranteed to see new astonishing advancements; in this bright future, semiconductor cavity QED research will most likely be a pre-eminent element.

See also

Quantum Electrodynamics: Cavity QED.

Further Reading

Allen L and Eberly JH (1987) Optical Resonance and Two-Level Atoms, 1st edn. New York: Dover.

Banyai L and Koch SW (1993) Semiconductor Quantum Dots, 1st edn. Singapore: World Scientific.

Berman PR (ed.) (1994) Several articles in *Cavity Quantum Electrodynamics*, 1st edn. Boston, MA: Academic Press.

Cohen-Tannoudji C, Dupont-Roc J and Grynberg G (1989) Photons and Atoms, 3rd edn. New York: Wiley.

Haug H and Koch SW (2004) Quantum Theory of the Optical and Electronic Properties of Semiconductors, 4th edn. Singapore: World Scientific.

Khitrova G, Gibbs HM, Jahnke F, Kira M and Koch SW (1999) Nonlinear optics of normal-mode-coupling semiconductor microcavities. *Reviews of Modern Physics* 71: 1591–1639.

Kira M, Jahnke F, Hoyer W and Koch SW (1999) Quantum theory of spontaneous emission and coherent effects in semiconductor microstructures. *Progress in Quantum Electronics* 23: 189–279.

Scully MO and Zubairy MS (1999) Quantum Optics, 1st edn. Cambridge, UK: Cambridge University Press.

Walls DF and Milburn GJ (1994) Quantum Optics, 1st edn. New York: Springer-Verlag.

QUANTUM OPTICS

Contents

Atom Optics
Atomic Coherence Effects
Entanglement and Quantum Information
Laser Cooling of Ions
Quantum Computing with Atoms
Squeezed Phonons in Solids

Atom Optics

A D Cronin and D E Pritchard, Massachussetts Institute of Technology, Cambridge, MA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

In 1923 Louis de Broglie suggested that particles of matter propagate as waves with a wavelength

$$\lambda_{dB} = h/p \qquad [1]$$

where h is Planck's constant and p is the particle's momentum. This breakthrough idea motivated Schrödinger's equation, which is the equation of motion of quantum mechanics.

Schrödinger's equation is a wave propagation equation, and therefore implies the existence of a whole new type of optics – matter wave optics – in which electron waves, neutron waves, atom waves, and entire molecule waves can be manipulated coherently. Such optics enable new measurement technologies and devices that depend on matter wave interference.

Guided by a knowledge of light waves, one can understand that the de Broglie wavelength of a particle sets the scale for focusing, diffraction, and interference. However, there are differences between matter and light. For example, the vacuum is tremendously dispersive for matter waves. In other words, the group velocity for a particle depends on its de Broglie wavelength, while for light waves the group velocity is independent of wavelength.

To illuminate the mathematical connection with light optics, we note the wave equation for light is

$$\nabla^2 \vec{E} = \mu \varepsilon \frac{\partial^2 \vec{E}}{\partial t^2} \qquad [2]$$

where $\vec{E} = \vec{E}(\vec{x}, t)$ is the optical electric field, and the parameters μ and ε may vary throughout space, describing an index of refraction. The wave equation for matter waves is Schrödinger's equation:

$$\left(-\frac{\hbar^2 \nabla^2}{2m} + V \right) \psi = i\hbar \frac{\partial}{\partial t} \psi \qquad [3]$$

where $\psi = \psi(\vec{x}, t)$ is the probability amplitude, or wavefunction, for a particle of mass m. Here, the potential energy V can vary throughout space, and thus control the phase and amplitude of propagating atoms. Just as density for photons is proportional to $\vec{E}(\vec{x})^2$, the probability density for particles is given by $|\psi(\vec{x})|^2$.

In a vacuum $V = 0$ and $(\mu_0 \varepsilon_0)^{-1/2} = c$, and if we assume that both ψ and E have a time dependence described by $e^{-ik\omega}$, the wave equations become

$$\left[\nabla^2 + \frac{\omega^2}{c^2} \right] \vec{E} = 0 \qquad [4]$$

and

$$\left[\nabla^2 + \frac{2m\omega}{\hbar} \right] \psi = 0 \qquad [5]$$

which look similar, but have a critical difference stemming from the single time derivative in Schrödinger's equation. To see how this makes the vacuum dispersive for matter waves, but not for light, consider a propagating plane wave of either ψ or $\vec{E}$ described by $e^{i(kx-\omega t)}$ (for either kind of wave, $k \equiv 2\pi(\lambda)^{-1}$). Using the wave equation for light waves, the dispersion relation is

$$\omega = ck \qquad [6]$$

where c is the phase (and group) velocity of light, which is independent of k. The same plane wave substituted into Schrödinger's equation for matter waves yields the dispersion relation

$$\omega = \frac{\hbar k^2}{2m} \qquad [7]$$

This is quadratic for matter waves, which means the group velocity $v_g = d\omega/dk$ is twice the phase velocity $v_p = \omega/k$, and both still depend on k.

From an engineering perspective, matter wave optics consists of lenses, mirrors, beam-splitters, and other components of an optics toolkit. The fact that electrons and neutrons can be transmitted through solid material, and that electrons can be reflected or refracted by static electromagnetic fields, has enabled optical elements to be created for these kinds of matter waves. For atoms, however, finding suitable materials for lenses or mirrors is a daunting task, since with rare exceptions (e.g., cold H on liquid He) atoms thermalize on surfaces rather than elastically bouncing off or passing through them. This was the major obstacle which delayed the blossoming of atom optics until the mid-1980s.

This obstacle has now been circumvented, but only with difficulty. Electromagnetic fields (whose spatial configurations are severely constrained by Maxwell's equations) can change the potential energy of neutral atoms, but since an atom's net charge is zero, provide only a weak and highly dispersive index of refraction based on the atom's polarizability or magnetic moment. However, these effects are tremendously enhanced if the electromagnetic fields oscillate near a transition frequency of the atom. Hence, propagating waves and standing waves of single-frequency laser light have become standard tools in atom optics. Standing light waves are often referred to as a light crystal, because the periodic potential can diffract atom beams.

An alternative source of atom optical components is based on nanofabrication. Thin sheets of material with patterned holes serve as absorptive atom optics by transmitting atom waves only through the nanometer scale openings. A variety of techniques have been used to make physical diffraction gratings, zone plates, and holograms for atom waves. Methods such as electron beam lithography and ultraviolet photolithography both rely on sophistocated etching procedures to make the final free-standing structures. Thus, in either approach – near-resonant light, or miniature physical structures – current technologies such as the tunable laser or nanofabrication techniques have been required for the development of useful atom optics.

While coherent manipulation of atom waves is often the goal, incoherent manipulations are possible also, e.g., if photons are spontaneously scattered. Dissipative processes offer an additional class of possibilities such as increasing the brightness of an atom source, and are therefore an important part of atom optics. This article excludes atom slowing and trapping, and focuses instead on atom diffraction – a coherent process which can be used to make beam splitters for atom interferometers.

Nanofabricated Atom Optics

Because atoms stick to surfaces, mechanical structures are absorptive atom optics. Yet the de Broglie waves transmitted through slots of a mask are nearly unaffected, provided the mask is thin enough. This is because the van der Waals potential energy of interaction with nearby surfaces falls off rapidly for neutral atoms.

Consider, for example, an atom wave packet being diffracted by a mechanical grating made with physical bars and slots as shown in Figure 1. Initially, let the atom wave packet have a slowly varying spatial envelope, $f = f(x, y, z)$, and momentum only in the $\hat{x}$-direction, $\vec{p} = \hbar\vec{k}_0 = h(\lambda_{dB})^{-1}\hat{x}$, so the wavefunction can be written as

$$\psi = fe^{i(k_0x - wt)} \qquad [8]$$

Immediately after the grating, only the portions of the wavefunction passing through slots remain nonzero, as depicted in Figure 2. Here, the wavefunction is now periodic both due to the grating lattice vector $k_g\hat{y}$ and the initial wavevector $k_0\hat{x}$. According to the Schrödinger equation, a periodicity in any direction implies a momentum in that direction. Thus, variation of ψ in the $\hat{y}$ variation gives rise to a new momentum distribution.

The square wave modulating the envelope of the wave packet can be described by a Fourier sum times the incident wavefunction

$$\psi = fe^{i(k_0x - \omega t)} \sum_{n=-\infty}^{\infty} a_n \cos(nk_g y) \qquad [9]$$

where $k_g = 2\pi(d_g)^{-1}$ is the grating lattice vector. The only other physical parameter of the grating is the open fraction, γ, and this determines the Fourier amplitudes a_n

$$a_n = \frac{\sin(n\pi\gamma)}{n\pi} \qquad [10]$$

From the principle of superposition (which is applicable here because the Schrödinger equation is linear) the wavefunction can be written as a sum of traveling waves with wavevectors $\vec{k}_n$:

$$\psi = f \sum_{n=-\infty}^{\infty} a_n e^{(i\vec{k}_n \cdot \vec{r} - wt)} \qquad [11]$$

$$\vec{k}_n = \frac{k_0\hat{x} + nk_g\hat{y}}{N} \qquad [12]$$

where, just as in standard optics, the factor N serves to keep $|\vec{k}_n|$ on a spherical shell, i.e., the grating does not add energy to the atom.

Inserting this expression for the wavefunction into Schrödinger's equation we get the dispersion relation



Figure 1 Scanning electron microscope image of a silicon nitride diffraction grating for atom waves. The bars (light) absorb, and the slots (dark) transmit atom waves. The grating period is 100 nm, the open fraction is 0.67, and the free-standing bars are supported every 5 μm with a thicker strip of silicon nitride material. The grating was fabricated by Tim Savas and Henry I Smith at MIT NanoStructures laboratory.



Figure 2 Schematic diagram of an atom wavepacket passing through an absorbing grating, as seen from above. The atom wavepacket is depicted before and after passing through the grating from left to right.



Figure 3 Diffraction data from a beam of sodium formed by passing atoms through two collimating slits followed by a nanofabricated diffraction grating. The momentum of the atoms determines their de Broglie wavelength, and thus their diffraction angle $\sin(\Theta_D) = \lambda_{dB}/d_{\text{grating}}$. These data were obtained at MIT by the authors.

for matter waves and a different group velocity, v_n, for each k_n

$$\hbar\omega = \frac{\hbar^2 k_n^2}{2m} \qquad [13]$$

$$v_n = \frac{d\omega}{dk_n} = \frac{\hbar k_n}{m} = p_n/m \qquad [14]$$

Thus, diffraction through a grating puts an atom into a coherent superposition of different momenta, each separated by $\sim\hbar k_g \hat{y}$. Some time later, the atom will be in a coherent superposition of multiple locations, and the far-field probability density will be peaked at integer multiples of the diffraction angle

$$\Theta_D = \frac{k_g}{k_0} = \frac{\lambda_{dB}}{d_{\text{grating}}} \qquad [15]$$

where d_{grating} is the lattice spacing of the grating and the small-angle approximation for $\sin(\theta)$ has been used. Exactly as in light optics, these diffraction gratings are good momentum spectrometers, i.e., the diffraction angle is a measure of longitudinal momentum. (Contrary to light optics, group velocity can also be used to measure matter wave momentum.) Coherence between the diffraction orders remains until a perturbation occurs which would (even in principle) be sufficient to determine which path the atom took. This assertion has been tested with atoms in an interferometer (discussed below).

Atom flux in the nth diffraction order is given by

$$I_n = \left(\frac{\sin(n\pi\gamma)}{n\pi}\right)^2 \qquad [16]$$

To resolve the diffracted orders the initial transverse momentum distribution of the atoms must be smaller than k_g, and the time until the far-field observation must be sufficiently large given the beam width. At intermediate times, the atom waves are in the Fresnel diffraction region where the Talbot effect can be observed. This effect causes the atom waves to form a replica of the grating in free space at integer multiples of the Talbot length, $Z_T = 2d^2_{\text{grating}}\,\lambda^{-1}_{dB}$.

Figure 3 shows the far-field diffraction pattern from a beam of sodium (^{23}Na) atoms using a material grating with a period of 100 nm. The atom beam velocity peaked at 1500 ms^{-1} corresponds to a de Broglie wavelength of 0.11 Å; thus, $\Theta_D \approx 10^{-4}$ rad. (The beam of 3000 ms^{-1} atoms diffracts at half this angle.) The spread in longitudinal velocity of $\sigma_v/v \approx 6\%$ can be deduced from the data because it slightly increases the width for higher order diffraction peaks. The open fraction of the grating, $\gamma \approx 60\%$, can also be determined from the diffraction data, because it determines the relative intensity of the orders. Effects of the atoms' finite size and interaction with the grating bars make small corrections to this simple theory.



Figure 4 Diffraction data using a mixed beam of sodium atoms (Na) and sodium dimer molecules (Na_2). From this source molecules have the same speed as atoms, thus twice the momentum. Thus, molecule waves are diffracted at half the diffraction angle compared to atom waves. These data were obtained at MIT by the authors.



Figure 5 Diffraction of helium atoms and helium molecules through a nanofabricated grating. These data, reproduced with permission from Wieland Schoellkopf, were obtained at the Max-Planck-Institute in Göttingen.

Nanofabricated atom optics differ from those based on light forces in a number of ways: they are amplitude structures (with corresponding loss of transmission intensity), they are species-independent, their scale size can be several times smaller than attainable with light, and they can be arbitrarily patterned since they are fabricated by electron beam lithography. Insensitivity to species is demonstrated in Figure 4, where a beam of Na_2 molecules and Na atoms is diffracted and separated by a nanofabricated diffraction grating. The flexibility of electron beam lithography has allowed fabrication not only of diffraction gratings, but also of spherical and cylindrical zone plates, as well as a combination of lens and a hologram that generates a focused atom image. One stunning application laid to rest a long-standing argument concerning whether a stable bound state of the $^4He_2$ dimer exists. For this a diffraction grating was used to separate and resolve $^4He_2$ and more massive clusters (Figure 5). Subsequently a nano-sieve was used to estimate the size of the $^4He_2$ dimers to be 62 ± 10 Å.

Standing Waves of Light

In contrast to nanofabricated structures, standing waves of near-resonant light are phase gratings for atoms. The optical electric field dynamically polarizes the atoms and causes a shift to the ground state energy (the ac-Stark shift). For optical electric fields oscillating above (below) the atomic resonance frequency, the ac-Stark shift increases (decreases) potential energy for atoms and in either case perturbs the de Broglie wave phase.

In many respects, the interaction of an atom with a standing light wave is richer than the more familiar topic of light–atom interactions in a traveling light wave. Part of this richness reflects two ways in which a standing wave can be considered, either as two counter-propagating traveling waves or as a single, stationary standing wave. The standing wave–atom interaction is capable of transferring momentum in well-determined quantities, coherently splitting atomic wave packets, and generating forces much larger than possible with spontaneously scattered light. Not surprisingly, this interaction has many distinct facets that only appear in different regimes of the interaction parameters (intensity, detuning, and pulse duration) and atomic parameters (mass, initial momentum with respect to the standing wave, and excited state natural lifetime).

We begin with the Bragg scattering of atoms from a standing wave light grating. Although it can be difficult to realize the physical conditions that assure its occurrence, pure Bragg scattering is simpler than intermediate cases involving spontaneous decay (from light too close to resonance) or Kapitza–Dirac diffraction (from shorter interaction times).

Consider a standing wave light grating formed by two counter-propagating plane waves (traveling parallel to the z-axis) of equal amplitude, E_0, wavevector, k, frequency, ω, polarization vector, $\hat{e}$, and temporal envelope function, $f(t)$:

$$\vec{E}(z,t) = E_0 f(t)\sin(kz - \omega t)\hat{e} + E_0 f(t)\sin(kz + \omega t)\hat{e} \qquad [17]$$

$$= 2E_0 f(t)\sin(kz)\cos(\omega t)\hat{e} \qquad [18]$$

We would like to work with momentum states as our atomic basis, thus it is easiest to consider the description of the electric field driving the transitions in terms of two counter-propagating traveling waves of definite momentum (eqn [17]), as opposed to the single standing wave they jointly form (eqn [18]).

Momentum is transferred by paired stimulated absorption and emission processes, resulting in a transfer of photons between the traveling waves. An N_B^{th} order diffraction process transfers N_B photons from one traveling wave to the counter-propagating traveling wave and changes the atomic momentum by $2N_B\hbar k\hat{z}$. Furthermore, atomic population is transferred only between $|g, -N_B\hbar k\rangle$ and $|g, +N_B\hbar k\rangle$, where $|g(e), \pm N\hbar k\rangle$ denotes a two-level atom in its ground (excited) state with momentum $\pm N\hbar k$ parallel to the standing wave axis. The excited state remains nominally unpopulated so long as the temporal envelope function, $f(t)$, does not have strong frequency components near the laser detuning

$$\delta = \omega - \omega_0 \qquad [19]$$

where ω_0 is the unperturbed frequency of the atomic transition. Furthermore, for a given initial state ($|g, -N_B\hbar k\rangle$) the uniqueness of the final state ($|g, +N_B\hbar k\rangle$) occurs because of the fundamental assumption that makes Bragg scattering so simple to describe; the uncertainty in the photon energy driving the transitions is small compared to the energy separation between neighboring momentum states. A quantitative discussion of the validity of this assumption will be given later.

We now calculate the probability, $P_1^B(\tau)$, of the first order ($N_B = 1$) Bragg process. Scattering transfers an atom from $|g, -\hbar k\rangle$ to $|g, +\hbar k\rangle$ when the atoms interact with a constant light intensity for a time τ (i.e., in eqns [17] and [18] $f(t)$ is a square wave of unit amplitude and duration τ). The geometry for Bragg diffraction from a standing wave of light is shown in Figure 6, and the energy/momentum states involved in the transition are depicted in Figure 7.

Considering the electronic degree of freedom, we rewrite the Schrödinger equation as

$$(\mathcal{H}_0 + \mathcal{H}_{\text{int}})|\psi\rangle = i\hbar\frac{\partial}{\partial t}|\psi\rangle \qquad [20]$$

where the total Hamiltonian $\mathcal{H} = \mathcal{H}_0 + \mathcal{H}_{\text{int}}$ is a matrix. The wavefunction is a vector of coefficients c_i in the basis $\{|g, -\hbar k\rangle, |e, 0\rangle, |g, +\hbar k\rangle\}$, with normalized population amplitudes for each component:



Figure 6 Two counter-propagating running waves of light superimpose to form a standing wave of light. This 'light crystal' acts as a diffraction grating for atoms, shown here in the configuration for Bragg diffraction.



Figure 7 Energy vs. momentum diagram describing atomic states involved in Bragg diffraction. The total energy is due to the electronic state ($|g\rangle$, $|e\rangle$) plus the kinetic energy associated with the recoil from photon emission (or absorption). In Bragg diffraction, atoms make a coherent transition from $|g, -\hbar k\rangle \leftrightarrow |g, +\hbar k\rangle$. Reprinted from Gupta S, *et al.* (2001) Coherent manipulation of atoms with standing light waves. *Comptes Rendus de L'Academie des Sciences – Series IV – Physics-Astrophysics* 2:479–495, copyright (2001) with permission from Elsevier.

$$|\psi\rangle = \begin{pmatrix} c_{-1}(t) \\ c_0(t) \\ c_{+1}(t) \end{pmatrix} \qquad [21]$$

In the electric dipole approximation, the interaction Hamiltonian is $\mathcal{H}_{\text{int}}(t) = -\vec{\mu}\cdot\vec{E}(t)$, where $\mu = \langle e|q\vec{r}|g\rangle \cdot \hat{e}$ is the electric dipole matrix element connecting the ground ($|g\rangle$) and excited ($|e\rangle$) states of the atom. $\hat{e}$ is the polarization vector of the light and q is the charge of the electron. By momentum conservation, only the plane wave traveling in the $\pm\hat{z}$ direction couples the $|e,0\rangle \leftrightarrow |g,\mp\hbar k\rangle$ transitions. By using this argument, we are effectively viewing the electric field as a quantum mechanical operator. Expanding the sinusoidal variation of the electric field in terms of complex exponentials and treating the spatially dependent complex exponential terms as quantum mechanical momentum translation operators yields the interaction Hamiltonian:

$$\mathcal{H}_{\text{int}} = \frac{\hbar\omega_R}{2}\begin{pmatrix} 0 & ie^{i\omega t} & 0 \\ -ie^{-i\omega t} & 0 & ie^{-i\omega t} \\ 0 & -ie^{i\omega t} & 0 \end{pmatrix} \qquad [22]$$

For example, $e^{\pm ik\hat{z}}|g, n\hbar k\rangle = |e,(n\pm 1)\hbar k\rangle$ describes absorption, and for stimulated emission, $e^{\mp ik\hat{z}}|e, n\hbar k\rangle = |g,(n\pm 1)\hbar k\rangle$. This procedure includes the rotating wave approximation. In addition, we have neglected any frequency components associated with the sudden switch on of the fields and the finite duration of the light–atom interaction. In formulating $\mathcal{H}_{\text{int}}$, the strength of the light–atom interaction is parameterized by the single-photon Rabi frequency:

$$\omega_R = \frac{\mu E_0}{\hbar} \qquad [23]$$

Without loss of generality, we will take μ and hence ω_R to be positive, real-valued quantities.

The total Hamiltonian follows simply by including the electronic and kinetic energy terms:

$$\mathcal{H}_0 = \hbar\begin{pmatrix} \omega_{\text{rec}} & 0 & 0 \\ 0 & \omega_0 & 0 \\ 0 & 0 & \omega_{\text{rec}} \end{pmatrix} \qquad [24]$$

where the single-photon recoil energy, E_{rec}, of an atom of mass m is given by

$$E_{\text{rec}} = \hbar\omega_{\text{rec}} = \frac{\hbar^2 k^2}{2m} \qquad [25]$$

Making the *ansatz* for the solution wavefunction as

$$|\psi\rangle = \begin{pmatrix} c_{-1}(t)e^{-i\omega_{\text{rec}}t} \\ c_0(t)e^{-i\omega_0 t} \\ c_{+1}(t)e^{-i\omega_{\text{rec}}t} \end{pmatrix} \qquad [26]$$

and substituting into the Schrödinger equation yields three coupled first-order differential equations:

$$\dot{c}_{\pm 1}(t) = \mp\frac{\omega_R}{2}e^{i\Delta t}c_0(t), \qquad [27]$$

$$\dot{c}_0(t) = \frac{\omega_R}{2}e^{-i\Delta t}\big(c_{+1}(t) - c_{-1}(t)\big), \qquad [28]$$

where $\Delta = \delta + \omega_{\text{rec}} = (\omega - \omega_0) + \omega_{\text{rec}}$. Differentiating eqn [27] and substituting eqn [28] into the result yields two coupled second-order differential equations:

$$\ddot{c}_{\pm 1}(t) - i\Delta\dot{c}_{\pm 1}(t) + \frac{\omega_R^2}{4}\big(c_{\pm 1}(t) - c_{\mp 1}(t)\big) = 0 \qquad [29]$$

With the initial conditions:

$$c_{-1}(0) = 1 \qquad [30]$$

$$c_0(0) = 0 \Rightarrow \dot{c}_{\pm 1}(0) = 0 \qquad [31]$$

$$c_{+1}(0) = 0 \qquad [32]$$

and the assumption $\Delta^2 \gg \omega_R^2$, the solutions to eqn [29] are

$$c_{-1}(t) = e^{-i\frac{\omega_R^{(2)}}{2}t}\cos\left(\frac{\omega_R^{(2)}}{2}t\right) \qquad [33]$$

$$c_{+1}(t) = ie^{-i\frac{\omega_R^{(2)}}{2}t}\sin\left(\frac{\omega_R^{(2)}}{2}t\right) \qquad [34]$$

where the two-photon Rabi frequency is

$$\omega_R^{(2)} = \frac{\omega_R^2}{2\Delta} \rightarrow \frac{\omega_R^2}{2\delta}, \quad |\delta| \gg \omega_{\text{rec}} \qquad [35]$$

with both transitions driven at equal single-photon Rabi frequencies, ω_R.

Substituting the solution of eqn [33] or [34] into eqn [27] yields an expression for the excited state amplitude:

$$c_0(t) = -i\frac{\omega_R}{2\Delta}e^{-i\Delta t}e^{-i\omega_R^{(2)}t} \qquad [36]$$

This will be important in calculating the rate of spontaneous emission events later.

The solutions for $c_{-1}(t)$ and $c_{+1}(t)$ oscillate with the interaction duration, τ, yielding the result for the $|g,-\hbar k\rangle \rightarrow |g,+\hbar k\rangle$ transition probability:

$$P_1^B(\tau) = |c_{+1}(\tau)|^2 = \sin^2\left(\frac{\omega_R^{(2)}}{2}\tau\right) \qquad [37]$$

Thus, the system oscillates between the two momentum states $|g,-\hbar k\rangle$ and $|g,+\hbar k\rangle$ in a manner analogous to the Rabi oscillation of atomic population between two resonantly coupled states. This solution with oscillatory probabilities for the two Bragg coupled states is known as the Pendellösung and has been observed for atoms, neutrons, and X-rays (Figure 8). The nice feature here is that the strength of the grating can be actually controlled by the intensity of the light.

Viewing Bragg scattering as a two-photon transition from the initial ground state to the final ground state with opposite momentum, illuminates the close connection with a Raman transition between two internal sub-states of the ground state manifold, each with its own external momentum state. The formalism describing the Raman transition is basically the same as that presented here, except the two transitions can be driven at different single-photon Rabi frequencies, ω_{R1} and ω_{R2}, so that the generic two-photon Rabi frequency is given by $\omega_R^{(2)} = \omega_{R1}\omega_{R2}/2\Delta$, where Δ is the detuning from the intermediate state.

An N_B^{th} order Bragg process (similar to a $2N_B$-photon Raman process) is a coherent succession of N_B two-photon transitions from $|g, -N_B\hbar k\rangle$ to $|g, +N_B\hbar k\rangle$ with $2N_B - 1$ intermediate states of the form:

$$|e, (-N_B + 1)\hbar k\rangle, |g, (-N_B + 2)\hbar k\rangle \ldots$$

$$\ldots |g, (N_B - 2)\hbar k\rangle, |e, (N_B - 1)\hbar k\rangle$$

Such a process is characterized by a $2N_B$-photon Rabi frequency given by

$$\omega_R^{(2N_B)} = \frac{[\omega_R]^{2N_B}}{2^{2N_B-1}\Delta_1\Delta_2\cdots\Delta_{2N_B-1}} \qquad [38]$$

where Δ_n is the detuning from the n^{th} intermediate state. Figure 9 shows what this process would look like for an N_B^{th} order Bragg transition where the intermediate state detunings are given by

$$\Delta_n = \left\{ \begin{array}{ll} \delta + (2N_B n - n^2)\omega_{\mathrm{rec}} : & n \text{ odd} \\ (2N_B n - n^2)\omega_{\mathrm{rec}} : & n \text{ even} \end{array} \right\} \qquad [39]$$

Substituting these detunings into eqn [38] yields the N_B^{th} order Bragg transition $2N_B$-photon Rabi frequency, $\omega_R^{(2N_B)}$:

$$\omega_R^{(2N_B)} = \frac{[\omega_R]^{2N_B}}{2^{4N_B-3}[(N_B - 1)!]^2 \delta^{N_B} \omega_{\mathrm{rec}}^{N_B-1}} \qquad [40]$$

where we have assumed $|\delta| \gg N_B^2 \omega_{\mathrm{rec}}$.

To ensure that the system truly undergoes Bragg scattering, and validate the assumption that only states of equal kinetic energy and opposite



Figure 8 Bragg scattering of an atom beam from an optical standing wave. First-order Bragg scattering at (a) lower power, (b) higher power of the laser beams (Pendellösung has set in, increasing the amplitude of the undeflected peak), (c) second-order Bragg scattering. Reprinted with permission from *Physical Review Letters* 60(6): 515–518. Copyright (1998) by the American Physical Society.



Figure 9 Energy vs. momentum diagram describing atomic states involved in higher-order Bragg diffraction. Reprinted from Gupta S, *et al.* (2001) Coherent manipulation of atoms with standing light waves. *Comptes Rendus de L'Academie des Sciences – Series IV – Physics-Astrophysics* 2:479–495, copyright (2001) with permission from Elsevier.

momentum are coupled, the overall exposure time, τ, of the atoms to the fields must be limited both from below and above.

The lower bound on τ is necessary to resolve the final momentum state ($|g, N_B\hbar k\rangle$) from neighboring momentum states ($|g, (N_B \pm 2)\hbar k\rangle$) two photon recoil momenta away. Avoiding population transfer into these states requires that the energy separation be resolvable, or

$$\tau(\delta E) \gg h \qquad [41]$$

For first-order Bragg scattering processes ($N_B = 1$) the nearest lying momentum states that may be mistakenly populated are $|g, \pm 3\hbar k\rangle$, for which

$$\delta E = \frac{p_{n=3}^2}{2m} - \frac{p_{n=1}^2}{2m} = 8\hbar\omega_{\text{rec}} \qquad [42]$$

Therefore

$$\tau \gg \frac{h}{8\hbar\omega_{\text{rec}}} = \frac{\pi}{4\omega_{\text{rec}}} \qquad [43]$$

For sodium atoms (^{23}Na) in 590 nm light, $\tau \gg 6\ \mu\text{s}$ is the lower bound required for first-order Bragg scattering.

For all higher-order ($N_B > 1$) Bragg scattering processes, the nearest momentum states are $|g, \pm(N_B - 2)\hbar k\rangle$, which limits the interaction time to

$$\tau \gg \frac{\pi}{2(N_B - 1)\omega_{\text{rec}}} \qquad [44]$$

which for $N_B \gg 1$ reduces to

$$\tau \gg \frac{\pi}{2N_B\omega_{\text{rec}}} \qquad [45]$$

The upper bound on the interaction duration is necessary to avoid spontaneous emission. The interaction duration must be short enough so that the expected number, N_s, of spontaneous emission events per atom during the time τ is negligible. N_s is simply given by the product of the excited state fraction (eqn [36]) and the probability of spontaneous decay given that the atom is in the excited state:

$$N_s = |c_0(t)|^2\Gamma\tau = \frac{\omega_R^2}{4\Delta^2}\Gamma\tau \qquad [46]$$

where Γ is the natural decay rate of the excited state. Avoiding spontaneous emission ($N_s \ll 1$) while still having a significant probability for transitions ($\omega_R^{(2N_B)}\tau \simeq \pi$) forces one to work in the regime where $\Delta \gg \Gamma$, which is a practical requirement to avoid spontaneous emission and maintain coherence. For sodium atoms on the 590 nm transition, $\Gamma = 6.3 \times 10^7\ \text{s}^{-1}$, and a typical choice in Bragg diffraction experiments is $\Delta = 50\Gamma$, or $\Delta/2\pi = 500$ MHz.

Briefly, to relate Rabi frequency to optical intensity, the transition rate W on resonance with a Lorentzian spectral line is given by Fermi's golden rule:

$$W = \frac{\omega_R^2}{\Gamma} = \frac{\lambda_{\text{photon}}^2}{2\pi}\frac{I}{\hbar\omega} \qquad [47]$$

where the last term can be regarded as the cross section for absorption multiplied by intensity in units of photon flux. Hence

$$\omega_R^2 = \Gamma\frac{\lambda_{\text{photon}}^2}{2\pi}\frac{I}{\hbar\omega} \qquad [48]$$

For Na atoms in 12 mW(cm)$^{-2}$ resonant light, $\omega_R = \Gamma = 6.3 \times 10^7\ \text{s}^{-1}$. Both the probability of Bragg scattering and the spontaneous emission increase linearly with $\omega_R^2\tau\Gamma^{-1}$. However, spontaneous emission decreases as Δ^2 while the Bragg scattering probability decreases as Δ. Thus, as shown in Figure 10, at sufficient detuning and laser power, Bragg scattering occurs with no spontaneous emission. For reference, 12 mW(cm)$^{-2}$ × 10 μs corresponds to $\omega_R^2\tau\Gamma^{-1} = 630$ for sodium atoms.

Bragg scattering of atoms from a standing light wave was first observed at MIT in 1988. A supersonic atomic beam was diffracted from a standing wave of near-resonant laser light as depicted in Figure 6. The angle between the atomic beam (of thermal wavelength λ_{dB}) and the light grating (of periodicity $\lambda_L/2$) was tuned to the appropriate Bragg angle, θ_B, where:

$$\lambda_{dB} = \lambda_L \sin(\theta_B) \qquad [49]$$

Population transfer corresponding to both first- and second-order Bragg scattering was observed (Figure 7). The experiment required a sub-recoil transverse momentum spread of the atomic beam in order to resolve the different momentum states in the far field and limit the final state to only one



Figure 10 The conditions for which $N_s > 0.02(0.10)$ are hashed in light(dark) gray. ω_R^2/Γ is proportional to optical intensity. The line labeled π-pulse indicates the parameters which cause complete first-order Bragg diffraction. The line labeled 2π-pulse indicates conditions where population is completely transferred back to the initial state (Pendellösung oscillation).

diffracted order. The Pendellösung was observed as an oscillation in population transfer as a function of standing wave intensity, $I \propto \omega_R^{(2)}$, for a fixed interaction time, τ.

Atomic beam diffraction from an optical standing wave is a continuous-wave (CW) experiment in which the selectivity needed for the Bragg process is imposed by good angular resolution of the particle beam and a high degree of parallelism between the light crystal planes. This ensures that of the various final Bragg orders allowed by momentum conservation, only one conserves energy (energy conservation is exact in a CW experiment). For atoms scattering from a light crystal, parallelism of the crystal planes requires highly parallel photon momentum that implies a minimum width of the standing wave (the diffraction limit for the collimated photons). The transit time, τ, of the atoms across this width then exceeds the lower bound given in eqn [44].

The excellent collimation required of the atomic beam to ensure resolution of the Bragg scattered atoms reduces the intensity of the source by many orders of magnitude. A Bose–Einstein Condensate (BEC) is an attractive alternative source of atoms because its momentum spread is typically an order of magnitude below a single-photon recoil momentum. To Bragg diffract atoms initially in a stationary BEC, it is easier to move the light crystal than to accelerate the condensate. This is done by simply frequency shifting one of the traveling waves so that the resultant standing wave formed by its interference with the unshifted traveling wave moves with the proper velocity ($N_B\hbar k/m$) relative to the stationary atoms to impart the necessary momentum. The Bragg scattered atoms will then have momentum $2N_B\hbar k$ in the laboratory frame. The resonance condition thus becomes a condition on relative detuning, δ_{N_B}, between the two laser beams forming the diffraction grating. For N_B^{th}-order Bragg diffraction, the relative detuning is given by

$$\delta_{N_B} = \frac{2N_B\hbar k^2}{m} = 4N_B\omega_{\text{rec}} \qquad [50]$$

The first demonstration of Bragg scattering in a BEC was at NIST in 1999. They used Bragg scattering mainly as a tool to manipulate the momentum of the BEC, observing up to sixth-order processes. At MIT the interaction time was lengthened (to ≈100 times the lower bound of eqn [44] for first-order Bragg scattering), creating a new type of spectroscopy called Bragg Spectroscopy. It is a spectroscopic measurement of the shift of the Bragg scattering frequency due to the Doppler shift ($k \cdot v$) from the atoms' motion together with any mean field interaction. (These effects can be separated by going to higher-order Bragg scattering to enhance the Doppler shift.)

Bragg Spectroscopy was used to observe the momentum distribution of a BEC in a magnetic trap. The width of the Bragg resonance curve was primarily due to a 2 kHz Doppler-broadening that yielded the momentum distribution of the condensate. The spread in the corresponding velocity distribution was very small ($\approx 0.5\ \text{mm s}^{-1}$), even smaller than allowed by the Heisenberg uncertainty limit for a particle confined in the ground state of a harmonic trap. This reflects the increase in size of the condensate due to the mean field repulsion (^{23}Na, used in the MIT experiment, has a positive scattering length). The distribution was Heisenberg uncertainty limited at the observed size of the BEC, establishing for the first time that the coherence length of the condensate was equal to its size. In addition, the narrow Bragg resonance was shifted by the repulsive interactions within the condensate, resulting in a spectroscopic measurement of the mean-field energy.

Kapitza–Dirac Scattering

Diffraction of neutral atoms from a standing wave of near-resonant light with a short interaction time ($\tau_{KD} \ll 1/\omega_{\text{rec}}$) has come to be called Kapitza–Dirac scattering, in honor of their pioneering suggestion. In 1933, Kapitza and Dirac predicted that an electron beam propagating in a standing light wave would undergo stimulated Compton scattering and be reflected. This process has a tiny cross-section, equal to the classical electron radius squared: $\sigma_{\text{Compton}} = 8\pi/3(e^2/mc^2)^2 \approx 6 \times 10^{-25}\ \text{cm}^2$, and has only recently been observed using extremely high laser intensities. If the electrons are replaced by atoms, however, the scattering cross-section for resonant light $\sigma_{\text{atom}} = (1/2\pi)\lambda_{\text{photon}}^2 \approx 4 \times 10^{-10}\ \text{cm}^2$ is 15 orders of magnitude larger. This large cross-section, together with the ready availability of tunable lasers, has allowed stimulated scattering, both in the Kapitza–Dirac and Bragg regimes, to become the primary tool for the coherent manipulation of atoms.

In Kapitza–Dirac scattering, atomic motion during the interaction time is small compared to the characteristic dimensions of the interaction potential. This is equivalent to the eikonal approximation for scattering or the thin-lens approximation in optics. The idea is that the phase of the incident particle changes along each classical trajectory, but not the amplitude. Thus, there may be momentum transfer perpendicular to the trajectory, but the trajectory is not significantly displaced (until after the interaction is over). Mathematically, this regime can be treated by neglecting the atomic kinetic energy term in the Hamiltonian (the Raman–Nath approximation).

The standing wave interaction may be treated by considering the standing wave (ac-Stark shift) potential resulting from the applied fields given in eqn [18]:

$$V(z,t) = \frac{\hbar\omega_R^2}{\delta} f^2(t)\sin^2(kz) \qquad [51]$$

where we have assumed $\delta \gg \Gamma$, because the constraint $N_s \ll 1$ (eqn [46]) holds in this regime as well, where N_s is the expected number of spontaneous emission events per atom during the time τ. Although we neglect the kinetic energy term in the Hamiltonian, we continue to will treat z in eqn [51] as an operator.

Given the initial atomic wavefunction in momentum space, $\psi(p_0)$, the atomic wavefunction immediately after the interaction is given by

$$\psi(p) = e^{-\frac{i}{\hbar}\int^{t} dt' U(z,t')}\psi(p_0) \qquad [52]$$

$$= e^{-i\frac{\omega_R^2}{2\delta}\tau} e^{i\frac{\omega_R^2}{2\delta}\tau\cos(2kz)}\psi(p_0) \qquad [53]$$

where $\tau = \int dt' f^2(t')$ and the integral is over the interaction duration. With the use of the identity for Bessel functions of the first kind, $e^{i\alpha\cos(\beta)} = \sum_{n=-\infty}^{\infty} i^n J_n(\alpha)e^{in\beta}$, the atomic wavefunction can be written as

$$\psi(p) = e^{-i\frac{\omega_R^2}{2\delta}\tau}\sum_{n=-\infty}^{\infty} i^n J_n\left(\frac{\omega_R^2}{2\delta}\tau\right)e^{i2nkz}\psi(p_0) \qquad [54]$$

$$= e^{-i\frac{\omega_R^2}{2\delta}\tau}\sum_{n=-\infty}^{\infty} i^n J_n\left(\frac{\omega_R^2}{2\delta}\tau\right)\psi(p_0 + 2n\hbar k) \qquad [55]$$

States with $2N\hbar k$ of momentum are populated with the probability:

$$P_N = J_N^2(\theta), \quad N = 0, \pm1, \pm2, \ldots \qquad [56]$$

where

$$\theta = \frac{\omega_R^2}{2\delta}\tau = \omega_R^{(2)}\tau \qquad [57]$$

is the pulse area. This leads to a transverse rms momentum of the diffracted atoms that is linearly proportional to the pulse area:

$$p_{\mathrm{rms}} = \sum_{n=-\infty}^{\infty} (n\hbar k)^2 P_n = 2^{1/2}\theta\hbar k \qquad [58]$$

The maximum and minimum bounds on the interaction time, τ, and the amount of momentum transfer to the atoms are discussed in the next section.

Kapitza–Dirac diffraction of atoms was first observed at MIT in 1986. Diffraction of a well-collimated (subrecoil) supersonic atomic beam was observed after passage through the tightly focused waist of a near-resonant standing wave (Figure 11). Significant diffraction into momentum states $|g, \pm10\hbar k\rangle$ was observed (Figure 12).



Figure 11 Two counter-propagating running waves of light superimpose to form a standing wave of light. The more narrow beam shown here represents the configuration for Kapitza–Dirac diffraction.



Figure 12 Kapitza–Dirac diffraction of an atomic beam from a standing wavelight grating. The solid lines are experimental data, the dashed lines are theoretical curves. (a) $\theta = 1.69$, (b) $\theta = 2.33$, (c) $\theta = 2.84$. Reprinted with permission from *Physical Review Letters* 56(8): 827–830. Copyright (1986) by the American Physical Society.

Even higher diffracted orders should be observable in the future using laser beams directed at small BECs for somewhat longer times.

Comparison of Atom-Standing Wave Interactions

The atomic motion induced by interaction with a standing light wave varies qualitatively with the interaction parameters. Figure 13 summarizes the various interaction regimes of an atom with a standing wave in terms of the two most basic parameters: the two-photon Rabi frequency, $\omega_R^{(2)} = \omega_R^2/2\delta$, and the duration of the interaction, τ. To render the plot independent of atomic species, $\omega_R^{(2)}$ is given in units of the single-photon recoil frequency, ω_{rec}, and τ is given in units of the inverse single-photon recoil frequency, ω_{rec}^{-1}. Thus, for ^{23}Na the point (1,1) on Figure 13 corresponds to (6.4 μs, $2\pi \times 25$ kHz). The product of the two-photon Rabi frequency and the duration of the interaction is the pulse area, $\theta = \omega_R^{(2)}\tau$ (eqn [57]), which is likewise the product of the pair of coordinates forming a point on the plot.

The lines KD1(KD10) on Figure 13 show where the first maxima of $P_{1,10} = J_{1,10}^2(\theta)$ (eqn [56]) occur, corresponding to the maximum possible population transfer into the first and tenth Kapitza–Dirac diffracted order respectively. Since the momentum distribution of diffracted atoms depends only on the pulse area (θ), all Kapitza–Dirac orders are parallel to each other and further offset from the origin in increasing order number.

The Kapitza–Dirac regime ends at large interaction times where the Raman–Nath approximation fails due to motion of the atoms down the slope of the standing wave potential. We show these lines dashed as the interaction time approaches the beginning of the classical oscillation regime, and terminate these lines where the oscillation produces its first focus, at the first focus line. This line corresponds to the atoms completing a quarter period of oscillation in the standing wave potential, $\tau = \tau_{\text{osc}}/4$, where the oscillation time is derived from the approximation that the potential $\langle V(z,t)\rangle_t$ (eqn [51]) is harmonic



Figure 13 Atomic diffraction from a standing light wave. The vertical axis is the two-photon Rabi frequency, $\omega_R^2/2\delta$, in units of the single-photon recoil frequency, ω_{rec}, and the horizontal axis is the pulse duration, τ, in units of the inverse single-photon recoil frequency, ω_{rec}^{-1}. The scaling is chosen to eliminate the atomic species dependence of the plot. All coherent momentum transfer processes are destroyed by spontaneous decay, which occurs with probability $N_s = 0.1$ along the lines labeled accordingly and parameterized by the given ratio δ/Γ. Lines KD1 and KD10 show conditions for the maximum transfer into the first and tenth Kapitza–Dirac diffracted order respectively. As the interaction time is increased the Raman–Nath approximation is violated (termination of Kapitza–Dirac curves) and the atoms enter the oscillatory regime, executing at least a quarter period of oscillation above the first focus line (shaded area). Cures B1, B2, B3, B10, and B20 correspond to conditions that generate complete Bragg reflection in the first-, second-, third-, tenth-, and twentieth-order respectively. Experimental conditions are shown as points. Filled circles: Kapitza–Dirac diffraction of an atomic beam (Pritchard 1986). Filled squares: Bragg diffraction of an atomic beam (Pritchard 1988). Open squares: Bragg diffraction of a BEC (Phillips 1999). Open circles: transition from Kapitza-Dirac diffraction to oscillation of a BEC in a standing wave light pulse (Phillips 1999). Reprinted from Gupta S, *et al.* (2001) Coherent manipulation of atoms with standing light waves. *Comptes Rendus de L'Academie des Sciences – Series IV – Physics-Astrophysics* 2:479–495, copyright (2001) with permission from Elsevier.

about the minimum:

$$\tau_{\mathrm{osc}} = \frac{\pi}{\omega_R}\left(\frac{|\delta|}{\omega_{\mathrm{rec}}}\right)^{1/2} \qquad [59]$$

In the shaded region of Figure 13, the atoms will oscillate classically about the potential minimum, causing a periodic focusing of the atoms alternately in position and momentum space. However, anharmonicities of the potential away from its minimum will degrade the quality of the focusing effects.

The maximum diffracted order that can be significantly populated by the light–atom interaction is limited by energy conservation. Classically, the maximum momentum transfer to the atoms due to the sudden switch on of the standing wave is delivered to atoms that convert the full height of the standing wave potential ($\hbar\omega_R^2/\delta$), into kinetic energy. This gives

$$\frac{p_{\max}^2}{2m} \simeq \frac{\hbar\omega_R^2}{\delta} \Rightarrow p_{\max} \simeq \omega_R\left(\frac{2\hbar m}{\delta}\right)^{1/2} \qquad [60]$$

Equating the maximum absorbed momentum, $p_{\max}$, to an integer number of two-photon recoil momenta yields the maximum expected diffracted order, $N_{\max}$:

$$p_{\max} = 2N_{\max}\hbar k \Rightarrow N_{\max} \simeq \frac{\omega_R}{2}(\omega_{\mathrm{rec}}\delta)^{-1/2} \qquad [61]$$

This is just half of the square-root of the standing wave potential height measured in units of the single-photon recoil energy:

$$N_{\max} = \frac{1}{2}\left(\frac{\frac{\omega_R^2}{\delta}}{\omega_{\mathrm{rec}}}\right)^{1/2} = \frac{1}{2}\left(\frac{\omega_R^{(2)}}{\omega_{\mathrm{rec}}}\right)^{1/2} \qquad [62]$$

As the two-photon Rabi frequency is reduced, $N_{\max}$ falls below unity. As a result, there is no longer time for the higher-order multi-photon processes to generate significant amplitudes in diffracted orders with $N > 1$ before dephasing due to the kinetic energy term (eqn [24]) becomes significant and the higher-order processes become negligible. Only a small population is ever transferred to the $N = \pm 1$ orders and it does not oscillate at ω_{rec}. Therefore the classical oscillation regime does not extend below $N_{\max} \simeq 1$ where it is terminated on Figure 13.

Classical oscillation would result in atoms with momentum from zero up to the maximum allowed by energy conservation. Therefore, the classical focusing of atoms must be manifest as an atomic population distribution over many of the quantized momentum states (separated by $2\hbar k$) allowed by energy conservation (eqn [61]). However, as the interaction time lengthens and extends into the Bragg regime, the populated momentum states become restricted by energy conservation until only the oscillatory Pendellösung into and back from only one final state remains. Therefore, we have ended the classical oscillation regime where the Bragg condition (eqn [44]) is satisfied. The Bragg regime presupposes a smooth light pulse shape. For a pulse with sharp edges, classically oscillatory behavior can still be observed at longer times than included in the shaded region of Figure 13, which is why we show the large τ boundary of the classical oscillation regime as dashed.

In the Bragg regime, transfer of population is restricted to (and back from) only one final momentum state. The allowable final states are restricted by limiting the frequency bandwidth (i.e., energy uncertainty) of the light fields in the atomic rest frame. This is accomplished by lengthening the interaction time and smoothing the rise and fall of the electromagnetic fields. The parameters for a first-order Bragg transition (Table 1) are typically $\delta/\Gamma \simeq 50$, $\Gamma\tau \simeq 1$, and $\omega_R/\Gamma \simeq 10$ giving $N_s \simeq 10^{-2}$ and $\omega_R^{(2)}\tau \simeq 1$. Obtaining significant population transfer with higher-order Bragg processes requires larger intensities. Various orders (1, 2, 3, 10, and 20) of Bragg diffraction are shown as lines on Figure 13 corresponding to $\omega_R^{(2N_B)}\tau = \pi$, where $\omega_R^{(2N_B)}$ is given in eqn [40]. The lines are terminated at the appropriate interaction time determined from the final momentum state resolution condition (eqn [44]). The Bragg regime extends indefinitely to larger interaction times, which might be termed the region of Bragg spectroscopy. In experiments in this regime with ^{23}Na, atomic velocity resolution below 1 mm s^{-1} was obtained at $\tau = 80\omega_{\mathrm{rec}}^{-1}$. The study of adiabatically expanded BECs would require larger interaction times to resolve their smaller velocity spread and weaker mean field shifts.

The Kaptiza–Dirac and Bragg regimes assume a different initial atomic momentum (in the rest frame of the standing wave) parallel to the standing

Table 1 Natural parameters and typical experimental parameters involved in standing wave diffraction. The relevant frequencies together with the corresponding times ($1/\omega$) are tabulated. The parameters for ^{23}Na have been used for system dependent quantities

ω	$\omega/2\pi$	$1/\omega$
ω_0	500 THz	0.3 fs
δ (Bragg)	500 MHz	0.3 ns
ω_R (Bragg)	100 MHz	1.6 ns
ω_R (K–D)	100 MHz	1.6 ns
Γ	10 MHz	16 ns
ω_{rec}	25 kHz	6.4 μs
ω_{osc}	1 MHz	160 ns

wave axis. Kapitza–Dirac scattering assumes no component of the initial atomic momentum along this axis. The efficiency of Kapitza–Dirac diffraction falls rapidly as the initial momentum in units of the photon momentum approaches $1/\omega_{\text{rec}}\tau$. To observe N_B^{th}-order Bragg scattering, the initial atomic momentum along the standing wave axis must have (nonzero) magnitude $N_B\hbar k$. Without adhering to this constraint, no final momentum state will be energetically degenerate with the initial state and the atomic sample will not respond to the presence of the standing wave, even if the interaction parameters are appropriate ($\omega_R^{(2N_B)}\tau \simeq 1$) for N_B^{th}-order Bragg scattering.

The condition $N_s = 0.1$ (eqn [46]), where N_s is the expected number of spontaneous emission events per atom during the light–atom interaction, is drawn on Figure 13 for two ratios (30 and 1000) of standing wave detuning, δ, to the atomic excited state natural lifetime, Γ. For fixed δ/Γ, we see that $N_s \propto \theta$, thus conditions with an increased pulse area (above and to the right of the $N_s = 0.1$ lines) result in a proportionally increased N_s. These $N_s = 0.1$ lines are extended across all regimes of Figure 13 because restricting spontaneous emission is required for both Kapitza–Dirac and Bragg scattering. As N_s approaches unity, the correct optical potential describing the light–atom interaction no longer is eqn [51], and scattering of atoms becomes an incoherent process which can lead to new possibilities such as a complex valued optical potential. Thus, while the standing wave fields in pure Bragg or Kapitza–Dirac scattering behaved as phase gratings for atoms, light gratings on resonance can effectively become amplitude diffraction gratings.

Atom Interferometry

In the 19th century, Fizeau (1853), Michelson (1881), Rayleigh (1881), and Fabry and Perot (Fabry 1899) exploited the interference properties of light waves to create the light interferometer which has since resulted in many beautiful experiments and precise measurements. Using technologies invented since the Second World War, the initial ideas of de Broglie and Schrödinger have evolved into construction of interferometers for neutrons, electrons, and atoms. These new interferometers are proving to be valuable tools for probing fundamental physics, for studying quantum mechanical phenomena, and for making inertial measurements.

The scientific value of interferometry with atoms and molecules has long been recognized. In fact, the concept of an atom interferometer was patented in 1973 and it has been extensively discussed since. Atom interferometry offers great richness stemming from the varied internal structure of atoms, the wide range of properties possessed by different atoms (e.g., mass, magnetic moment, absorption frequencies, and polarizability), and the great variety of interactions between atoms and their environment (e.g., static E–M fields, radiation, and other atoms).

Light interferometers are generally based either on achromatic beamsplitters such as half-silvered mirrors or on other semi-transparent membranes whose structure is small compared to the wavelength of the wave they are splitting. Lacking material structures that are either transparent to atoms or smaller than their de Broglie wavelength, diffraction gratings have been pressed into service both as beamsplitters and mirrors for atom waves. This means that atom interferometers are constrained to designs which somehow compensate for the dependence of diffraction angle on the wavelength of the individual atoms. In spite of this challenge, a surprising variety of atom and molecule interferometers have been built since 1991. A majority have used the three-grating configuration in which the first grating splits the incident beam, the second reverses the differential momenta given by the first, and the third recombines the two beams at the location where they overlap. Both material gratings and standing waves of light have been used in the Raman–Nath, Bragg, and adiabatic regimes to obtain interference fringes. Some designs render the interference fringes in position space, others in internal state space.

Figure 14 shows the MIT setup for a three-grating atom interferometer which features sufficient separation between interfering paths to accommodate an interposed metal foil. This allows different fields or media to act on atom waves only in one of the two



Figure 14 An interferometer for atoms built with three nanofabricated gratings. Each atom propagates in a superposition of two paths, shown in bold. The beam of atoms is well enough collimated, and the diffraction angle is large enough, that a metal barrier can be inserted between the two paths inside the interferometer. The interference fringes are observed by translating one grating transverse to the atom beam. See for example: Berman PR (ed.) (1997) *Atom Interferometry*. San Diego, CA: Academic Press.

arms of the interferometer. Such an interaction region has been used to measure phase shifts due to an electric field applied to only one of the interfering paths. The phase difference between the two paths is then given by the Feynman path integral:

$$\phi = \frac{-i}{\hbar}\int V(x)dt \qquad [63]$$

where

$$V = -\frac{1}{2}\alpha E^2 \qquad [64]$$

is the potential energy due to the electric filed E, and α is the electric polarizability of the atoms. The resulting phase shift of the interference fringes (Figure 15) has been used to measure the polarizability of sodium atoms to unprecedented accuracy.

Phase shifts have also been measured due a dilute target gas in one arm of the interferometer. In this case there is a complex index of refraction for the forward scattered atoms (some attenuation, and some phase shift) which depends on matter wave wavelength. Recent measurements reveal glory oscillations in the matter wave index of refraction due to passing through a dilute gas, and are a sensitive probe of interatomic potentials.

In the domain of inertial sensing, atom interferometers have been used to the local gravitational acceleration, $\vec{g}$, Newton's constant, G, gravity gradients, $\nabla\vec{g}$, and rotations Ω, each with sensitivity rivaling if not exceeding any other method. The Sagnac phase shift, due to rotations, for a two-path interferometer is

$$\phi_S = \frac{4\pi}{\lambda_{dB} v}\vec{\Omega}\cdot\vec{A} \qquad [65]$$

where v is the velocity of atoms, $\vec{A}$ is the enclosed area of the interferometer, and $\vec{\Omega}$ is the rotation rate. The two factors in the denominator, λ_{dB} and v, are both $\sim 10^5$ times larger for light than for atoms, which is why atom interferometers have the potential to be 10^{11} times more accurate than optical interferometers. In practice, atom interferometers only outperform laser gyros by a small amount because they have dramatically smaller enclosed areas and particle flux than optical interferometers.



Figure 15 Interference fringes from atoms. 2π of grating phase corresponds to translating the grating one grating period, or 100 nm. These data were obtained at MIT.

Since the first atom interferometers for Na and He* began working in 1991, others have been made for Li, Ar*, Ca, Cs, K, Mg, Ne*, Rb, and Li_2, Na_2, I_2, C_{60} and C_{70} molecules, interferometers starting with trapped atoms have been made for Cs, Ca, He*, Mg, and Rb. Interferometers using Bose–Einstein condensates have been demonstrated with Na and Rb. These lists are still growing. Diffraction from a single grating has been observed for molecules as large as C_{70} buckyballs, which may someday be used in a three-grating interferometer.

Conclusion

The manipulation of atoms using light forces from standing light waves is a rich subject. The seminal suggestion of Kapitza and Dirac laid dormant for 50 years due to lack of experimental technology. However, in the 1980s this suggestion was realized with atomic sources and considerably extended both experimentally and theoretically. In the early 1990s, coherent standing wave manipulation and nonofabricated atom optics became the two major routes to making atom interferometers. As the new century begins, these techniques are being refined further with improved sources, new detection schemes, and better atom optics. Replacing thermal atomic beams by Bose–Einstein condensates (BECs), as sources of atoms, will revolutionize the field of atom optics just as lasers did in light optics.

Conversely, stimulated light scattering and nanostructures provide new ways to study atomic and molecular properties, such as Bragg spectroscopy for BEC characterization. As progress continues, exciting developments should be forthcoming, such as definitive measurements of the fine structure constant, α, atom gyroscopes that are far superior to the best laser gyroscope technology, and improved studies of BECs. Another area that is on the brink of spectacular development is the confinement of coherent matter waves in atom waveguides and the development of the scientific and technological opportunities that these represent, in analogy to fiber optic waveguides for light.

While we have described the application of nanofabrication techniques to atom optics, it is possible to imagine technology transfer in the other direction. The fundamental problem of fabricating ever smaller structures might be tremendously advanced by atom optics because the de Broglie wavelength of atoms is so much smaller than that of light, permitting them to be focused to directly deposit much smaller features than possible with photolithography.

See also

Interferometry: Overview. **Scattering:** Scattering Theory.

Further Reading

Cohen-Tannoudji C, Diu B and Laloe F (1977) *Quantum Mechanics*. New York: Wiley and Sons.

Hecht E (1987) *Optics*. Reading, MA: Addison-Wesley.

Berman PR (ed.) (1997) *Atom Interferometry*. San Diego, CA: Academic Press.

Mandel L and Wolf EM (1995) *Optical Coherence and Quantum Optics*. London: Cambridge University Press.

Balykin VI and Letokhov VS (1995) *Atom Optics with Laser Light*. Chur, Switzerland: Harwood Academic Publishers.

Meystre P and Sargent M III (1999) *Elements of Quantum Optics*. Heidelberg, Germany: Springer Verlag.

Rauch H (2000) *Neutron Interferometry*. Oxford, UK: Oxford University Press.

Meystre P (2001) *Atom Optics*. New York: Springer-Verlag.

Campargue R (ed.) (2001) *Atomic and Molecular Beams, the State of the Art 2000*. Berlin: Springer.

Atomic Coherence Effects

A Belyanin, G R Welch and M O Scully,
Texas A&M University, College Station, TX, USA

© 2005, Elsevier Ltd. All Rights Reserved.

History and Perspective

Quantum optics and laser physics have entered a new era. This started with the invention of the laser and the associated theoretical developments such as the theory of photon correlations and statistics, and the quantum theory of the laser. Later, new and novel lasers such as the free electron laser and tunable dye laser fueled many new research directions. With the development of the micromaser, quantum optics became a beautiful new test bed for the study of nonequilibrium statistical physics of photons interacting with matter in a controlled environment. The realization that a deeper understanding was needed to understand the measurement process led to the utilization of the laser as a probe of gravity, and to insight into nonclassical processes such as quantum nondemolition measurements and the production of squeezed states of light.

Effects of atomic coherence in quantum electronics have a long history. One of the first examples was the Hanle effect: excitation by polarized light creates atomic coherence that can evolve in a magnetic field, causing the change of polarization of the resulting fluorescence. Another important example is the interference of decay processes, first suggested by Fano. Modern schemes utilizing quantum coherence in atomic vapors or solid media usually involve strong coupling laser fields (laser drives). In each case, the effect of quantum coherence can be understood as interference of multiple (usually two) transition paths between quantum states of a system.

In the past decade, the concepts of atomic coherence and interference have led to many new and surprising innovations in laser physics such as electromagnetically induced transparency (EIT), refractive index enhancement, lasers without population inversion, ultra-slow light group velocity, storage of the quantum states of light, teleportation of quantum states, and nonlinear optics at an ultra-low intensity level.

Electromagnetically Induced Transparency

One of the most vivid manifestations of quantum coherence effects is the reduction of absorption in a three-level system that is driven by a coherent laser field. This effect is known as electromagnetically induced transparency, or EIT. We consider in more detail the case when the probe and drive fields are in a so-called Λ-configuration (Figure 1a) named after the appearance of the level scheme. In the conventional usage, the two lower levels are coupled to the upper level with two lasers. One of the lasers may be strong and is called the driving or coupling laser, and the other is weak and is called the probe laser.

Consider a quasi-monochromatic laser field E_d (called the ‘driving’ field, or ‘coupling’ field) and probe field E_p interacting with a three-level medium of Figure 1a. This interaction is described by a density matrix ρ_{ij}, where i, j take the values a, b, c. Within the



Figure 1 Real and imaginary parts of the susceptibility as functions of the frequency of the probe laser for (a) three-level Λ-type atoms, and (b) two-level atoms.

density matrix approach, quantum coherence in the system has the precise meaning of an off-diagonal element of the density matrix at the two-photon transition c–b. To have strong quantum coherence in a Λ-system, one must excite a large value of ρ_{cb}.

It is convenient to simplify the equations from the very beginning by using the rotating-wave approximation. We introduce slowly varying complex amplitudes of fields and polarizations and neglect their second derivatives. For example, for the probe field applied at the $a \rightarrow b$ transition we write

$$E_p(z,t) = \frac{1}{2}\varepsilon_p(z,t)\exp(-i\omega_p t + ik_p z) + \text{c.c.} \qquad [1]$$

After introducing the complex Rabi frequency $\Omega_p(z,t) = d_p\varepsilon_p(z,t)/2\hbar$, the wave equation for waves propagating in the z-direction can be written as

$$\frac{\partial\Omega_p}{\partial z} + \frac{n_p}{c}\frac{\partial\Omega_p}{\partial t} + \kappa_p\Omega_p = \frac{2\pi i\nu_p d_p^2 N}{\hbar c n_p^2}\sigma_{ab} \qquad [2]$$

Here d_p is the dipole moment of the probe transition a–b, N the total volume density of atoms in the active region, κ_p represents cavity losses, and $n_p = k_p c/\omega_p$ is the refraction index. The variable σ_{ab} is the slowly varying amplitude of the corresponding off-diagonal element $\rho_{ab} = \sigma_{ab}\exp(-i\nu_p t)$ of the density matrix. The same representation is assumed for the drive field E_d, with parameters n, d, ν, κ having index 'd'.

The functions σ_{ab}, σ_{ac}, and σ_{cb}, which determine the polarization response of the medium at the frequency of the external field, should be found from the density matrix equations

$$\frac{d\sigma_{cb}}{dt} + \Gamma_{cb}\sigma_{cb} = -i\Omega_p\sigma_{ac}^* + i\Omega_d^*\sigma_{ab} \qquad [3]$$

$$\frac{d\sigma_{ab}}{dt} + \Gamma_{ab}\sigma_{ab} = i\Omega_p n_{ba} + i\Omega_d\sigma_{cb} \qquad [4]$$

$$\frac{d\sigma_{ac}}{dt} + \Gamma_{ac}\sigma_{ac} = i\Omega_d n_{ca} + i\Omega_p\sigma_{cb}^* \qquad [5]$$

where

$$\begin{aligned} \Gamma_{cb} &= \gamma_{cb} + i(\nu_{cb} - \nu_p + \nu_d), \\ \Gamma_{ab} &= \gamma_{ab} + i(\nu_{ab} - \nu_p), \\ \Gamma_{ac} &= \gamma_{ac} + i(\nu_{ac} - \nu_d) \end{aligned} \qquad [6]$$

Here the γ's are relaxation rates of the polarizations at the corresponding transitions (the so-called homogeneous broadening). The population differences $n_{ik} = \rho_{ii} - \rho_{kk}$ are defined from eqns [2]–[6] together with the three equations for $\rho_{ii}, i = a, b, c$, with phenomenological rates of population relaxation and pumping:

$$\begin{aligned} \frac{d\rho_{bb}}{dt} &= -2\,\mathrm{Im}[\Omega_p^*\sigma_{ab}] + r_{cb}\rho_{cc} + r_{ab}\rho_{aa} - r_{ba}\rho_{bb} \\ \frac{d\rho_{cc}}{dt} &= -2\,\mathrm{Im}[\Omega_d^*\sigma_{ac}] + r_{ac}\rho_{aa} - r_{cb}\rho_{cc} \\ \frac{d\rho_{aa}}{dt} &= 2\,\mathrm{Im}[\Omega_p^*\sigma_{ab}] + 2\,\mathrm{Im}[\Omega_d^*\sigma_{ac}] + r_{ba}\rho_{bb} \\ &\quad - (r_{ab} + r_{ac})\rho_{aa} \end{aligned} \qquad [7]$$

Here we have included only the pumping term r_{ba} between levels b and a for simplicity. Later, we will consider the effect of incoherent pumping on gain, but in this section we put $r_{ba} = 0$. The sum of populations is evidently conserved in this model. Analysis of open systems with, e.g., flow of atoms through a cavity, leads to qualitatively similar conclusions.

Suppose that the probe field is weak, $|\Omega_p|^2 \ll \gamma_{cb}\gamma_{ac}$, and the drive-field intensity is constant in a sample. The complex susceptibility at the probe-field frequency, which is proportional to $\sigma_{ab}/\varepsilon_p$, is given by

$$\chi = \frac{i d_p^2 N}{\hbar c}\left\{\frac{1}{\Gamma_{ab} + |\Omega_d|^2/\Gamma_{cb}}\left(n_{ba} - \frac{|\Omega_d|^2 n_{ca}}{\Gamma_{cb}\Gamma_{ac}^*}\right)\right\} \qquad [8]$$

This expression can be further simplified if there is no pumping to the states $|c\rangle$ and $|a\rangle$, so that we can assume that $n_{ca} = 0$ and drop the second term in the brackets. The behavior of χ as a function of detuning from resonance $\nu_{\mathrm{p}} = \nu_{ab}$ is shown in Figure 1a. In the absence of the drive field Ω_{d}, we retrieve the usual two-level susceptibility, shown in Figure 1b.

There are two remarkable features in the susceptibility of Figure 1a. The first one is the transparency window at the point of two-photon resonance. The absorption coefficient at resonance is

$$K'' = \frac{2\pi\nu_{\mathrm{p}} d_{\mathrm{p}}^2 N}{\hbar c(\gamma_{ab} + |\Omega_{\mathrm{d}}|^2/\gamma_{cb})} \qquad [9]$$

Clearly, absorption can be arbitrarily small when $\gamma_{cb} \ll \gamma_{ab}$ and $|\Omega_{\mathrm{d}}|^2 \gg \gamma_{cb}\gamma_{ab}$, since it is proportional to $\gamma_{cb}/|\Omega_{\mathrm{d}}|^2$. For any value of $|\Omega_{\mathrm{d}}|^2$, the absorption is much smaller than that resulting from simple Stark splitting of two Lorentzians. Moreover, in the most interesting case

$$\gamma_{cb}\gamma_{ab} \ll |\Omega_{\mathrm{d}}|^2 \ll \gamma_{ab}^2$$

the Stark splitting is negligible while the deep and narrow EIT feature remains, with width $\gamma_{cb} + |\Omega_{\mathrm{d}}|^2/\gamma_{ab}$.

Note that the intensity of the drive field required for the coherent bleaching of the medium is a factor $r_{ab}/\gamma_{cb} \gg 1$ smaller than the intensity needed for usual saturation bleaching.

EIT is closely related to the phenomenon of coherent population trapping (CPT). This can be illustrated by transforming from states $|a\rangle$, $|b\rangle$, $|c\rangle$ to a new set of states $|a\rangle$, $|B\rangle$, $|D\rangle$, where

$$|D\rangle = (\Omega_{\mathrm{d}}|b\rangle - \Omega_{\mathrm{p}}|c\rangle)/\sqrt{|\Omega_{\mathrm{d}}|^2 + |\Omega_{\mathrm{p}}|^2}$$

$$|B\rangle = (\Omega_{\mathrm{d}}|b\rangle + \Omega_{\mathrm{p}}|c\rangle)/\sqrt{|\Omega_{\mathrm{d}}|^2 + |\Omega_{\mathrm{p}}|^2}$$

It can be easily found that under the condition of two-photon resonance $\nu_{\mathrm{p}} - \nu_{\mathrm{d}} = \nu_{cb}$ the dipole matrix element from $|D\rangle$ to $|a\rangle$ goes to zero. This means that the population in state $|D\rangle$ does not interact with the coherent radiation field and does not contribute to absorption. That is why this state is called a non-absorbing or dark state. Under the condition $|\Omega_{\mathrm{d}}|^2/\gamma_{cb}\gamma_{ab} \gg 1$ practically all the population of states $|b\rangle$ and $|c\rangle$ is optically pumped into the dark state, and only a small fraction $\propto \gamma_{cb}$ remains in the absorbing state $|A\rangle$ and contributes to absorption.

The second remarkable feature of a driven Λ-system is sharp variation of the real part of χ near the resonance, which can be used for manipulation of the group velocity of light, as discussed in the next section.

Slow, Ultra-Slow, Stored, and Frozen Light

Introduction

There are five useful definitions for the velocity of a traveling wave:

- the phase velocity, which is the speed at which the zero crossings of the carrier wave move;
- the group velocity, at which the peak of a wave packet moves;
- the energy velocity, at which energy is transported by the wave;
- the signal velocity, at which the half-maximum wave amplitude moves;
- the front velocity, at which the first appearance of a discontinuity moves.

Although these can all be different, in most cases (linear, passive, dispersive media) the last four coincide, and are usually less than the phase velocity. By using the very steep frequency dispersion in the vicinity of the narrow resonance associated with electromagnetically induced transparency (EIT), it has been shown that the group velocity of light can be reduced by approximately 100 million compared with its velocity in vacuum.

In order to understand the concept of group velocity, it is useful to consider the superposition of two waves of the same amplitude E_1 and E_2 where $E_i = E_0\cos(k_i z - \nu_i t)$ with $i = 1, 2$. Addition of these waves gives rise to the modulation shown in Figure 2:

$$\begin{aligned} E &= E_0(\cos(k_1 z - \nu_1 t) + \cos(k_2 z - \nu_2 t)) \\ &= 2E_0\cos(\Delta k z - \Delta\nu t)\cos(kz - \nu t) \end{aligned}$$

where $\Delta k = (k_1 - k_2)/2$, $\Delta\nu = (\nu_1 - \nu_2)/2$, $k = (k_1 + k_2)/2$, and $\nu = (\nu_1 + \nu_2)/2$. This superposition



Figure 2 Interference of two monochromatic waves with different frequencies results in a wave modulated in time and space.

displays an interference pattern consisting of a rapid oscillation propagating with the so-called phase velocity,

$$v_{\text{phase}} = \frac{\nu}{k} \qquad [10]$$

and a slowly varying envelope propagating at the group velocity,

$$v_{\text{g}} = \frac{\Delta\nu}{\Delta k} \qquad [11]$$

Usually, the group velocity of wave packets consisting of more than two harmonics is given by transforming the ratio $\Delta\nu/\Delta k$ into $\mathrm{d}\nu/\mathrm{d}k$.

Slow and Ultra-Slow Light

In ordinary absorption and refraction of light, it is sufficient to consider only two atomic energy levels interacting with the light. However, in multilevel systems, coherent excitation of more than one transition can dramatically alter the dispersion and hence the group velocity. The first experiments of this effect demonstrated a group velocity of $c/13$. However, this was progressively lowered in later experiments as the steepness of the dispersion was increased, culminating in a group velocity as low as $c/300\,000\,000$ (1 m/s) in a Bose–Einstein condensate of ultra-cold sodium atoms. Slow light has been observed in a wide range of systems, from the Bose–Einstein condensates just mentioned, to hot optically dense gases of atoms and molecules, and in solids ranging from rare-earth doped crystals to solid hydrogen.

Most of these experiments occurred in a Λ system. The susceptibility of this medium has very steep dispersion without absorption, as shown in Figure 1.

The minimum possible group velocity slowed by the steep dispersion in EIT is given by

$$v_{\text{g}} = \frac{8\pi\Omega^2}{3\lambda^2 N\gamma} > 0 \qquad [12]$$

where $\gamma = \gamma_{ab} = \gamma_{ac}$. The driving field Ω should be strong enough to meet the condition $\Omega^2 \gg \gamma\gamma_{bc}$ for coherent effects. It can be shown that the group velocity approaches its minimum $v_{\text{g min}} = 8\pi\gamma_{bc}/(3\lambda^2 N)$ when $\Omega^2 \approx \gamma\gamma_{bc}$.

Bringing Light to a Halt: Frozen Light

Consider a laser pulse propagating through a medium with ultra-slow group velocity while the medium itself is moving with some velocity v in the opposite direction to the direction of laser pulse propagation. Let us denote the group velocity of the light in the frame co-moving with the atoms as $\tilde{v}_{\text{g}}$. In this frame, atoms are at rest, and hence, there is no spatial dispersion. The Galilean transformation to the laboratory frame, $k = \tilde{k}$, $\nu = \tilde{\nu} - \tilde{k}v$, where v is the atomic velocity, yields the group velocity $v_{\text{g}} = Re(\mathrm{d}\nu/\mathrm{d}k) = \tilde{v}_{\text{g}} - v$. This simple transformation shows that the light pulse is 'dragged' by the moving atoms. If the velocity of the atoms with respect to the laboratory frame is exactly equal and opposite to the group velocity of light in the frame where atoms are at rest, then we find that the group velocity in the laboratory frame is zero. We refer to this as 'freezing' of light. We may even make the group velocity negative so that the propagation direction is opposite to the wavevector (that is, that $v_{\text{g}} < 0$). The simplest example of spatial dispersion is the so-called drift dispersion corresponding to a mono-velocity atomic beam or moving sample with velocity v.

Slow light experiments in Doppler broadened systems such as warm gases allow group velocities that are much lower than the mean thermal speed (v_{T}) of the atoms in the thermal sample (Figure 3). This means that freezing of light can occur without actually moving the atomic sample. When the experimentally obtained group velocity is less than or about equal to the mean thermal speed of the atoms, a pulse of light can be stopped in a stationary cell. In this case the delay time for a pulse passing through the medium would tend to infinity (contrary to the case of a finite atomic beam) in the sense that this pulse would never leave the cell.

This is accomplished by using a single velocity group from the Maxwellian thermal distribution of atomic velocities, and adjusting the frequency of the driving field to be resonant with that velocity group (see Figure 4). In this case it is mainly the atoms in this single velocity group that support the ultra-slow group velocity as a slow EIT polariton, and the atoms



Figure 3 Ultra-slow and negative group velocity of EIT polariton versus detuning of drive laser; $\Omega = 0.25\gamma$, $k_d v_T = 100\gamma$, $\gamma_{cb} = 0.001\gamma$, (a) $N = 0.6\,N_{cr}$; (b) $N = N_{cr}$; (c) $N = 1.5\,N_{cr}$.



Figure 4 The velocity distribution of atoms in a cell (solid line). Effective drifting beam (dotted) selected by drive laser.

then act as an effective atomic beam. If the driving field is on resonance with the velocity group of atoms moving into the light with speed equal to $\tilde{v}$, we will have $v_g = \tilde{v}'_g - v_d$, where $\tilde{v}'_g$ is the group velocity of the light defined by the effective atom beam if those atoms were at rest. This requires that the intensity of the drive is strong enough to provide EIT for the resonant velocity group of atoms, i.e., $\Omega^2 > \gamma_{bc}\gamma$ (see Figure 4) but at the same time weak enough to avoid interaction with off-resonant atoms moving with the 'wrong' velocities (i.e. $\Omega < kv_T\sqrt{\gamma_{bc}/\gamma}$).

Storing and Retrieving Quantum Information

Photons are potentially the best particles for use in quantum computing and quantum information processing. They are the fastest, and perhaps the simplest and most robust carriers of quantum information, but their storage and manipulation is difficult without destroying their quantum state. However, for application to quantum cryptography, quantum teleportation, and quantum computation it is necessary to achieve a strong coupling between electromagnetic waves and a large nonlinear susceptibility with small losses. For this task, it may be resonant coherent media that offer the promise of success.

Recently, new coherent and reversible methods based on EIT have been found for the transfer and manipulation of photons and their quantum information. Quantum states of photons are trapped in coherently driven atomic media in which the group velocity is reduced adiabatically toward zero. The methods allow for an ideal transfer of quantum correlations between light fields and metastable states of matter. Currently, interesting applications such as quantum state memories and quantum information processing including transporting and time reversing the state of light are being investigated.

Although experiments have not yet been conducted with single quanta, proof-of-principle experiments using classical laser fields have demonstrated the technique. In these experiments control and signal light pulses propagate in a gas of three-level Λ-type atoms and excite a spatial profile of a long-lived coherence of ground spin states. This spin coherence profile contains quantum information about the 'writing' pulses. When the control field is switched back on, the signal pulse is restored via Raman scattering on the atomic coherence. Ideally, the scattered pulse is in the same quantum state as the input signal pulse, preserving entanglement, quantum statistics, etc.

Similar experiments have also shown that different reading pulses (rather than switching back on the same control pulse) can be used to obtain new tools for quantum information storage and processing. Time reversing, teleportation, color switch and multiplexing of the signal pulse of light have all been demonstrated. These new operational possibilities arise as a result of the reading of the stored information with a light pulse that is spatially separated from, has different frequency from, and propagates in the opposite direction to the signal beam.

To demonstrate these effects, one pair of control and signal pulses (the 'writing' fields) prepares a spin coherence of the lower level (Figure 5). A second control pulse (which can be thought of as a 'reading' field) scatters from this coherence resulting in the generation of a new, or 'recovered', field. This recovered field acquires some properties of the reading field because it is a Raman scattered component of the reading pulse. If the reading field pulse is centered about a frequency other than that of the writing fields, and propagates in the opposite direction to the writing fields, then the recovered field propagates in the same direction as the reading field and has a different frequency from the incident writing fields. Even if the writing and reading pulses are separated in space as well as time the scattering effect will persist. This allows the transportation of the coherence grating to another point in the atomic cell via the atomic center-of-mass motion.

In the ideal case the signal pulse profile and quantum statistics are exactly stored by the atomic coherence grating. Thus, reading by a backward propagating pulse results in a generated pulse that is also backward propagating. That is it represents an exactly time-reversed copy of the signal pulse. Similarly, atomic motion in the direction transverse to the light propagation moves the coherence grating to another spatial position. Reading the light by a spatially shifted laser results in the equivalent of


a_2
a_1
Reading
Restored
$\vec{\kappa}_2$
$\vec{\kappa}_2$
$\vec{v}$
$\vec{\kappa}_1$
$\vec{\kappa}_1$
Writing
$\vec{E}_2\ \vec{\kappa}_2$
$\vec{\varepsilon}_2\ \vec{\kappa}_2$
$\vec{\varepsilon}_1\ \vec{\kappa}_1$
$\vec{E}_1\ \vec{\kappa}_1$
c
b
(a)
in
out
Intensity
0
1
10
100
Nonadiabatic
Adiabatic
γT
Time
(b)

Figure 5 (a) Energy level scheme used in experiments for multiplexing, transporting, and time-reversing stored light. (b) 'Storage of light': intensity of the signal field versus time for different switching times (T) of the reading and writing fields.

'teleportation' of light by atoms in the same spirit as the teleportation of the quantum state of light by atoms that has been discussed recently. It is also possible for the frequency of the 'restored' pulse to be easily shifted by switching the frequency of the reading pulse. This means that the use of a frequency comb of reading pulses propagating in different spatial modes should result in multiplexing of the signal light.

Novel Laser Sources Based on Quantum Coherence

Introduction

In the previous sections we have seen how quantum coherence can be used to overcome resonant absorption on a transition of interest, leading to EIT. A natural question arises whether it is possible to achieve gain without population inversion at this transition, i.e. lasing without inversion (LWI). This subject has been intensively investigated since the early 1990s, and the first proof-of-principle experiments have been successful.


$|a\rangle$
E_p
E_d
$|c\rangle$
$|b\rangle$
(a)
$|a\rangle$
E_p
$|c\rangle$
E_d
$|b\rangle$
(b)
$|c\rangle$
E_d
$|a\rangle$
E_p
$|b\rangle$
(c)
$|b\rangle$
E_p
$|a\rangle$
E_d
$|c\rangle$
(d)

Figure 6 LWI schemes in a three-level system coherently driven by a laser field.

Besides the fundamental physical beauty of this phenomenon, the research effort has been motivated by potentially important applications. It is clear that LWI could be particularly useful in situations where a population inversion is difficult to maintain due to, e.g., very fast relaxation or inefficient pumping. The obvious examples are high-frequency UV, X-ray and gamma-ray lasers, or semiconductor mid/far-infrared lasers based on intersub-band transitions. Another promising application of LWI is efficient frequency up- or down-conversion. Furthermore, if resonant absorption can be eliminated, resonant nonlinear optical interactions become a reality. Since all nonlinear coefficients are maximized at resonance, highly efficient nonlinear optical generators of light can be created.

In this section we discuss the simplest possible schemes of inversionless lasing which allow one to clarify the physical origin of LWI and to see the shortcomings which have so far prevented LWI-based schemes from reaching the level of practical laser devices.

Consider a three-level system, coherently driven by a strong quasi-monochromatic field nearly resonant with one transition, and probed by a field that is nearly resonant with an adjacent transition. Some possible configurations are shown in Figure 6. We consider in detail the case when the two fields are in a Λ-configuration (Figure 6a). This is probably the most popular and well-studied scheme since it can provide probe-field gain for a very low pumping rate, when most of the population is at the lowest energy level. However, we will see that the gain condition for the Λ-scheme is actually rather restrictive and does not allow one to realize large frequency up-conversion. For the latter purpose, ladder-type schemes (Figure 6c,d) turn out to be more favorable.

Weak-field gain in the Λ-scheme

From the general formalism presented earlier, it is straightforward to get the amplification condition

$$K'' = \mathrm{Re}\left\{ \eta_{\mathrm{p}} \frac{1}{\Gamma_{ab} + |\Omega_{\mathrm{d}}|^2/\Gamma_{cb}} \left(n_{ba} - \frac{|\Omega_{\mathrm{d}}|^2 n_{ca}}{\Gamma_{cb}\Gamma_{ac}^*} \right) \right\} + \kappa_{\mathrm{p}} < 0 \qquad [13]$$

where

$$\eta_{\mathrm{p}} = \frac{2\pi\omega_{\mathrm{p}} d_{\mathrm{p}}^2 N}{\hbar c n_{\mathrm{p}}^2}$$

The physical meaning of the two terms in brackets in eqn [13], which originate from the two terms on the right-hand side of eqn [4] for σ_{ab}, can be easily understood. The first term is just the resonant one-photon absorption proportional to the population difference n_{ba}. It can be strongly reduced in the presence of a drive field Ω_{d}, as explained earlier. However, it can change sign and give rise to the field amplification only if $n_{ba} < 0$, meaning there is a population inversion!

The second term, originating from the product $\Omega_{\mathrm{d}}\sigma_{cb}$ in eqn [4], is due to the mixing of the drive field Ω_{d} and polarization σ_{cb} where the latter is parametrically excited by a two-photon process: $\sigma_{cb} \propto e_{\mathrm{p}}\sigma_{ac}^* \propto e_{\mathrm{p}}\Omega_{\mathrm{d}}^* n_{ca}$. It is this term that can overcome one-photon absorption to provide amplification without inversion in the Λ-scheme. As we see, the possibility of LWI depends crucially on our ability to excite a sufficiently large polarization σ_{cb} at the transition resonant with the beat frequency of the probe and drive fields. This conclusion is universal for all LWI schemes with a coherent drive. We see that the sometimes loosely defined term 'quantum coherence' has a precise meaning here as the polarization σ_{cb} at a two-photon transition c–b. It is clear that the effects of quantum coherence are maximized when γ_{cb} is small, i.e., the transition c–b is long-lived.

We are of course interested in the case of weak incoherent pumping. The typical dependence of gain on detuning from two-photon resonance is shown in Figure 7. At resonance, where the gain is maximized, the amplification condition $K'' < 0$ yields (in the absence of nonresonant losses):

$$r_{ac} > 2\gamma_{cb}(r_{ab}/r_{ba} - 1) \geq r_{ab} - r_{ba} \simeq r_{ab} \qquad [14]$$



Figure 7 Gain without inversion in Λ-scheme.

because $\gamma_{cb} \geq r_{ba}/2$. Here we assumed that the incoherent pumping is weak, $r_{ba} \ll r_{ab}$, so that it does not produce population inversion at the probe transition.

Equation [14] is a simple and very important result, which is valid for all three-level laser schemes in the absence of inversion at both probe and drive transitions: the relaxation rate at the drive transition should exceed that at the probe transition. This result is an immediate consequence of the fact that the long-lived coherence σ_{cb} is inevitably destroyed by incoherent pumping, and γ_{cb} is now bounded from below. One can follow how the EIT regime is transformed into lasing as follows. With increasing incoherent pumping rate r_{ba}, EIT is actually destroyed due to the growth of $\gamma_{cb} \simeq r_{ba}/2$. In terms of CPT states, this means increase of population of the absorbing state $|B\rangle$. At the same time, the resonant Raman term in [13] also grows since n_{ac} is proportional to r_{ba}. With increase in the incoherent pumping rate, the contribution to gain overcomes the contribution to absorption if $r_{ac} > r_{ab}$.

Propagation effects

Inequality [14] has important implications for the problem of co-propagation of probe and drive fields. Indeed, to provide a significant amplification of the probe field, the absorption length $L_{\mathrm{d}} = \gamma_{ac}/(\eta_{\mathrm{d}} n_{ca})$ of the drive field should be larger than the amplification length $L_{\mathrm{p}} \simeq \gamma_{ac}/(\eta_{\mathrm{p}} n_{ca})$ of the probe. This requirement gives simply

$$\eta_{\mathrm{p}}/\eta_{\mathrm{d}} > 1 \qquad [15]$$

which in the absence of nonradiative relaxation can be rewritten as

$$\frac{r_{ab}}{r_{ac}} \frac{\nu_d^2}{\nu_p^2} > 1$$

In view of the gain condition given in eqn [14], the above requirement can be satisfied only if $\nu_d > \nu_p$, i.e., up-conversion is impossible.

An interesting solution to this problem is to realize population inversion at the driving transition. Then up-conversion can be realized with a lower relaxation rate at the drive transition as compared with probe transition. In this case in the Λ and V-schemes the two-photon term contributes to absorption at resonance, and gain is only possible far off-resonance. At the same time, in the ladder schemes shown in Figure 6c and d the gain is achieved at resonance, as discussed below in more detail.

It should also be noted that to excite laser oscillations in a high-Q cavity, large one-pass gain is not required at all, so that a Λ-scheme could still be employed for up-conversion.

Now, consider a probe field of arbitrary intensity. An important question is where the energy for amplification of the probe field comes from. It is known that for parametric processes in a transparent medium the Manley–Rowe relations are satisfied. Therefore, it might seem that the drive field is also the ultimate energy source for LWI. However, this is the case only for very large detunings of the drive and probe fields from the corresponding transition frequencies. In that case, we can neglect one-photon absorption, and the wave equations take the form typical for stimulated Raman scattering. They possess the first integral

$$\frac{|\varepsilon_d|^2}{\nu_d} + \frac{|\varepsilon_p|^2}{\nu_p} = \text{const} \qquad [16]$$

which expresses the conservation of the total number of quanta in both waves (Manley–Rowe conditions).

However, in the case of exact resonance, one can show that one-photon absorption of the drive field is always important, and the Manley–Rowe-type conservation law does not exist at all. The optimal condition for the probe field amplification is $\eta_p/\eta_d \gg 1$. In this case the stage of exponential amplification of the probe is maintained over a long distance, and the probe field intensity can grow to much larger values than the sum of initial intensities of the drive and probe fields. Apparently, the energy for the probe field amplification comes mainly from the medium, namely from the upper-level population ρ_{aa} supported by incoherent pumping.

V-Scheme

The V-scheme, shown in Figure 6b, is qualitatively similar to the Λ-scheme. An important difference is that there is now no long-lived coherence at the mixing transition c–a. Indeed, even if the transition $a \rightarrow c$ is strongly forbidden, the coherence γ_{ac} is destroyed by fast relaxations at the c–b and a–b transitions. We can immediately suggest that for the V-scheme inversionless lasing takes place at large driving field intensities exceeding the saturation value. However, one must be careful: although it appears that the reduction of absorption in the absence of pumping cannot be greater than a factor of 2, this turns out to be incorrect. Rather, almost complete transparency can be achieved, as confirmed by calculations and recent experiments. Analysis of the laser gain condition shows that the V-scheme shares with Λ-scheme the same negative feature: relaxation at the driving transition should be much faster than at the probe transition.

Schemes with Population Inversion at the Driving Transition

The above analysis illustrates the common problem of LWI schemes: the requirement of rapid relaxation at the driving transition and the resulting strong absorption of the drive field. This difficulty can be overcome in schemes with population inversion at the driving transition. Then, of course, all this makes practical sense only if the relaxation at the drive transition is much slower than that on the probe transition, so that it is easy to provide population inversion for the drive transition as compared with the probe transition. Luckily, such schemes do exist in principle, and seem to have many potential applications. The simplest possibility is the so-called ladder (or cascade) schemes shown in Figure 6c,d. LWI in ladder schemes is usually studied in the regime when there is no inversion at both probe and drive transitions. In this case gain is achieved at large detunings from two-photon resonance and under the same unfortunate condition of fast relaxation at the drive transition as compared with the probe transition. In the opposite case, population inversion at the driving transition is required for LWI at the probe transition. In ladder schemes the maximum gain of the probe field is achieved when both fields are at resonance with atomic transitions, while in V and Λ-schemes the resonance point corresponds to maximum absorption, and the gain is achieved in sidebands.

Note that population inversion at the driving transition means that the drive field can be amplified. This immediately puts forward the possibility to use a drive field which is self-generated in the same active medium. In other words, the system supports lasing with inversion at the drive frequency and LWI at the probe frequency. This situation is especially beneficial for dense gases or solids where the problems of external drive absorption, reflection, and inhomogeneity may become otherwise insurmountable. One specific example considered in the literature is LWI on rapidly decaying UV and soft X-ray transitions in gas lasers in the presence of lasing with inversion on long-lived adjacent transitions in the visible range (as in Figure 6c). Another example is LWI on rapidly decaying mid/far-infrared intersub-band transitions in semiconductor quantum wells in the presence of lasing with inversion on the interband transition, as in Figure 6d. These interband transitions have 10^4 times longer lifetime than the intersub-band transitions.

Experiments

Experimentally, amplification without inversion has been observed in rarefied atomic vapors in the early and mid-1990s. In particular, amplification of a probe beam in the Λ-configuration was realized in atomic samarium, sodium, and cadmium, while the V-scheme was successfully implemented in atomic rubidium. Inversionless laser oscillation was observed in a V-scheme in rubidium vapor and a Λ-scheme in a sodium atomic beam. In all of these proof-of-principle experiments, the frequencies of the probe and drive fields were very close to each other, and the coherence was excited between two hyperfine states or Zeeman sublevels. One-pass gain of a few per cent was observed.

Nonlinear Optical Sources Based on Quantum Coherence

Excitation of a strong coherence has a profound impact on nonlinear optical interactions. Strong scattering on the polarization wave excited at the beat frequency of two or more laser fields allows one to achieve huge nonlinear coefficients and conversion efficiencies. A particularly impressive example is ultra-broadband collinear Raman generation in a resonant Λ-scheme, that has been observed experimentally. A pair of strong laser pulses propagating in molecular deuterium excites a strong polarization wave at a beat frequency close to a vibronic transition in deuterium. As a result, a comb of Raman sidebands from the infrared to the deep-UV region of the spectrum has been observed.

Another example is an extremely efficient simultaneous blue light and mid-infrared generation in a four-wave mixing experiment in rubidium vapor. Here, all four fields are resonant with corresponding transitions.

A final example illustrates the use of self-generated drive fields for nonlinear generation. It has been suggested that one can use two intracavity generated laser modes in a semiconductor quantum-well laser for the difference frequency, sum frequency, and second-harmonic generation in fully resonant three-wave mixing processes. This idea has already been successfully realized in two-wavelength quantum-cascade lasers, and experiments with other types of semiconductor lasers are under way.

The whole field of resonant nonlinear optics, stemming from original ideas of LWI in systems with quantum coherence, is now in explosive development.

Summary

Atomic coherence effects have already found many important applications in metrology and low-intensity nonlinear optics. Novel applications in quantum nonlinear optics, laser physics, and quantum information processing seem to be feasible. The coherence allows the storage of information about the probe light, its transportion in space, time reversing, and multiplexing the light. Moreover, the coherence allows an increase of the coupling between light fields such that it becomes possible to study the interaction between single photons. New coherent radiation sources based on the ideas of LWI and coherent nonlinear optics are at the stage of active research. There are surely many other applications ahead.

See also

Electromagnetically Induced Transparency. **Non-Classical Light**. **Nonlinear Optics, Applications:** Raman Lasers. **Nonlinear Optics, Basics:** Cascading; Four-Wave Mixing. **Quantum Optics:** Entanglement and Quantum Information.

Further Reading

Belyanin AA, Bentley C, Capasso F, *et al.* (2001) Inversionless lasing with self-generated driving field. *Physical Review A* 64: 013814.

Harris SE (1997) Electromagnetically induced transparency. *Physics Today* 50(9): 36–42.

Kocharovskaya O (1992) Amplification and lasing without inversion. *Physics Reports* 219: 175–190.

Mompart J and Corbalán R (2000) Lasing without inversion. *Journal of Optics B: Quantum and Semiclassical Optics* 2: R7–R24.

Rostovtsev Y, Kocharovskaya O, Welch GR and Scully MO (2002) Slow, ultra-slow, stored and frozen light. *Optics Photonics News*, June.

Scully M and Zubairy S (1997) Quantum Optics. Cambridge, UK: Cambridge University Press.

Entanglement and Quantum Information

P G Kwiat, University of Illinois at Urbana-Champaign, Urbana, IL, USA

D F V James, Los Alamos National Laboratory, Los Alamos, NM, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Quantum information is an emerging field of technology that encompasses the application of fundamental quantum mechanical phenomena, such as entanglement, to tasks in information processing and communications. The importance of optical technology in quantum information is not surprising, given the success of quantum optics in the investigation of these fundamental phenomena and the pre-eminent role of optics in modern communications. This article describes some of the important advances in photonic quantum information and discusses the prospects for the future.

Basic Notions: Qubits and Entanglement

Qubits

Quantum information is usually confined to two-level quantum systems, which are referred to as quantum bits, or qubits. The qubits form the register of a quantum computer or carry the information in a quantum communications channel. Physical examples of qubits under active study include the spin degrees of freedom of an electron or spin-1/2 nucleus, two well-isolated energy levels of an atom or trapped ion, and the polarization degrees of freedom of a photon; here we concentrate on the latter.[1] The two states of each qubit are generically denoted by $|0\rangle$ and $|1\rangle$ (although, because of our concentration on optical polarization, we shall use the horizontal and vertical states $|H\rangle$ and $|V\rangle$ interchangeably with $|0\rangle$ and $|1\rangle$ when describing experiments). An arbitrary state of a single qubit, $|\psi\rangle = \alpha|0\rangle + \beta|1\rangle$, is specified by the complex probability amplitudes α and β associated with the two possible states, constrained by $|\alpha|^2 + |\beta|^2 = 1$. States for which α and β are deterministic quantities are referred to as pure states; when they are stochastic, the state is mixed, and must be described by a density matrix, e.g., $\rho = \sum_i p_i|\psi_i\rangle\langle\psi_i|$, where p_i is the probability of the pure state $|\psi_i\rangle$. Pure states are a useful but unattainable ideal, just like a perfectly coherent laser beam; in reality even the best-prepared quantum states have some level of mixedness, which can be quantified by the entropy: $S \equiv -Tr(\rho \ln\rho) = -\sum_i \lambda_i \ln\lambda_i$, where λ_i are the eigenvalues of the matrix ρ.

Multiqubit States and Entanglement

For two qubits, the possible pure states of the system are specified by four probability amplitudes:[2] $|\psi_2\rangle = \alpha|00\rangle + \beta|01\rangle + \gamma|10\rangle + \delta|11\rangle$, with $|\alpha|^2 + |\beta|^2 + |\gamma|^2 + |\delta|^2 = 1$, and, e.g., $|00\rangle \equiv |0\rangle \otimes |0\rangle$ denoting the state in which the first and the second qubits are both in state $|0\rangle$. In general, 2^n amplitudes are needed to characterize a pure state of n qubits. Immediately we can see one advantage of quantum systems for information storage: if each distinct probability amplitude is regarded as a data register, the size of the memory grows exponentially with the number of qubits. Further, if one were to flip just one qubit, for example the second, the state would be transformed into $|\psi_2'\rangle = \beta|00\rangle + \alpha|01\rangle + \delta|10\rangle + \gamma|11\rangle$, where all of the amplitudes have been affected. This simple example demonstrates the notion of quantum parallelism, one of the most powerful properties of quantum information processors.

If the two-particle state can be written as a product of two single-particle states, i.e., if $\alpha|00\rangle + \beta|01\rangle + \gamma|10\rangle + \delta|11\rangle = (A|0\rangle + B|1\rangle) \otimes (C|0\rangle + D|1\rangle)$, then these two particles can be considered as separate, unconnected entities: the state is said to be separable.[3] When the state cannot be written in this form, it is called an entangled state. Entanglement is one of the most fascinating fundamental properties of quantum systems: Erwin Schrödinger described it as '*the* characteristic trait of quantum mechanics … that enforces its entire departure from classical lines of thought.' Consider performing a measurement on the second of the two qubits, to establish which of its two states the particle was in, leaving the first qubit untouched. The result would collapse the state of the first qubit into one of two possibilities: either $|\phi_0\rangle = (\alpha|0\rangle + \gamma|1\rangle)/\sqrt{P_0}$ if the outcome of the measurement were 0 (which occurs with probability $P_0 = |\alpha|^2 + |\gamma|^2$) or $|\phi_1\rangle = (\beta|0\rangle + \delta|1\rangle)/\sqrt{P_1}$ if it were 1 (with probability $P_1 = |\beta|^2 + |\delta|^2$). Thus the state of the first qubit is instantaneously projected into a specific state by performing a measurement on the second qubit, which can be in a completely different location. This example demonstrates the nonlocality of quantum mechanics, which has been confirmed experimentally in some depth by a number of elegant quantum optics experiments over the last 30 years.

---

[1] Recently some attention has been devoted to quantum information based on continuous variables, such as those arising in connection with 'squeezed light'. However, here we will focus on discrete systems, i.e., qubits.

[2] Qubits are assumed to be distinguishable particles, and so the wavefunctions describing their states need not be symmetrized under exchange of particles.

[3] When mixture is also present, the state is separable if it can be written as $\rho = \sum_i p_i \rho_i^A \otimes \rho_i^B$, i.e., as a sum of product states for systems A and B.

The fidelity $F = |\langle\Phi|\Psi\rangle|^2$ characterizes the overlap of two states.[4] The fidelity of $|\phi_0\rangle$ and $|\phi_1\rangle$ is a way to quantify the amount of entanglement in the initial two-qubit state. If the final two states are identical, the fidelity will be unity, and the initial state is separable; conversely if the two final states are orthogonal and occur with equal probability, then in a sense the initial state is maximally entangled, since the largest possible nonlocal influence would occur due to the measurement. Mathematically, the fidelity of the two final states is $|\langle\phi_0|\phi_1\rangle|^2 = 1 - C^2/4P_0P_1$, where $C = 2|\alpha\delta - \beta\gamma|$ is called the concurrence of the state. If $C = 0$, the state is separable; if $C = 1$, the state is maximally entangled.[5]

As discussed below, entanglement forms the heart of a number of quantum information protocols, such as dense coding, teleportation, and one type of quantum key distribution (also known as quantum cryptography), and large-scale entangled states of many qubits seem to be a requirement for the more ambitious goal of practical quantum computing.

Creating Entangled States Experimentally

Entangled states can currently be created in a controlled manner using technologies such as ion traps, cavity quantum electrodynamics, and optical spontaneous parametric down-conversion (SPDC). Down-conversion is a nonlinear optical process by which an incident ‘pump’ photon can be split (or down-converted) into a pair of longer-wavelength daughter photons (historically called ‘signal’ and ‘idler’) in a crystal possessing a $\chi^{(2)}$ nonlinearity, such as beta-barium borate (BBO). Mathematically, the process is described using the creation and annihilation operators of the field modes $(\hat{a}^\dagger_\lambda, \hat{a}_\lambda)$, thus:

$$|\Phi_{\text{out}}\rangle = \exp\left[-i \sum_{p,s,i} c_{p,s,i}(\hat{a}^\dagger_p \hat{a}_s \hat{a}_i + \hat{a}^\dagger_i \hat{a}^\dagger_s \hat{a}_p) \right] |\Phi_{in}\rangle$$

where the triple sum is over all field modes (subscripts p, s, and i refer to pump, signal, and idler modes, respectively) and $c_{p,s,i}$ is a coefficient linearly dependent on the second-order nonlinear susceptibility $\chi^{(2)}_{ijk}$ and also on the birefringent properties of the crystal. Further, $c_{p,s,i}$ will be negligibly small unless both total photon energy and momentum are conserved (i.e., $\omega_p = \omega_s + \omega_i$ and $\vec{\kappa}_p = \vec{\kappa}_s + \vec{\kappa}_i$, where $\vec{\kappa}$ is the intracrystal momentum).

One particularly efficient method for using this phenomenon to create entangled states is as follows. For a specific geometry (type-I phase matching), the daughter photons emerge from the crystal with identical polarizations (perpendicular to the parent polarization and the crystal optic axis) on opposite sides of a cone that is centered about the pump beam (Figure 1a). Because each photon is in a definite state of polarization, the two photons are not in an entangled state. Two crystals, aligned with their axes of symmetry oriented at 90° to each other, as shown in Figure 1b, can then be used to create an entangled state.[6] With crossed crystals, two processes are possible: the parent photon can down-convert in the first crystal to yield two vertically polarized photons, or it can down-convert in the second crystal to yield two horizontally polarized photons. Because it is impossible to distinguish which of these processes has occurred, the state of the daughter photons is a coherent quantum-mechanical superposition of the states that would arise from each crystal alone; the output of the crossed crystals is photons in the maximally entangled state $|\Phi_+\rangle \equiv \frac{1}{\sqrt{2}}(|HH\rangle + |VV\rangle)$.[7]

Figure 2 shows how this basic source can be adapted to produce any pure quantum state of two photons by placing rotatable half- and quarter-wave plates (which can be used to transform the

---

[4] The generalized fidelity between mixed states ρ_A and ρ_B is $F = |Tr\sqrt{\sqrt{\rho_A}\rho_B\sqrt{\rho_A}}|^2$.

[5] The concurrence can also be generalized to mixed states, although it has a much more complicated expression. The quantification of entanglement for mixed states with more than two subsystems is presently an active area of research.

[6] Another widely used method employs type-II phase matching in a single crystal. The down-conversion photons are emitted with perpendicular polarizations along a pair of cones. Pairs emitted along particular directions are in the maximally polarization-entangled state $|\psi_-\rangle = \frac{1}{\sqrt{2}}(|HV\rangle - |HV\rangle)$. Such a source was used in the first demonstrations of superdense coding and quantum teleportation.

[7] Note that in an arbitrary basis $|\theta\rangle \equiv \cos\theta|H\rangle + \sin\theta|V\rangle$ and $|\theta^\perp\rangle \equiv -\sin\theta|H\rangle + \cos\theta|V\rangle$, this maximally entangled state has the form $|\Phi_+\rangle = \frac{1}{\sqrt{2}}(|\theta\theta\rangle + |\theta^\perp\theta^\perp\rangle)$, demonstrating that the nonlocal correlations are present regardless of the bases used to represent the state.



Figure 1 An entangled-photon source. (a) For a given orientation of the nonlinear crystal, a horizontally polarized parent photon produces a pair of vertically polarized daughters. The daughters emerge on opposite sides of an imaginary cone. The cone's axis is parallel to the original direction taken by the parent photon. The two daughter photons are not in an entangled state. Reorienting the BBO crystal by 90° will produce a pair of horizontally polarized daughters if a vertically polarized pump beam is used. (b) Passing a photon polarized at 45° through two crossed BBO crystals can produce two photons in an entangled state. Because of the Heisenberg uncertainty principle, there is no way to tell in which crystal the parent photon 'gave birth,' and so a coherent superposition of two possible outcomes results: a pair of vertically polarized photons or a pair of horizontally polarized photons. (Adapted with permission from James DFV and Kwiat PG (2002) Quantum state entanglement: creation, characterization, and application. *Los Alamos Science* 27: 52–67.)



Figure 2 Creating and measuring two-photon entangled states. The 'pump' photons are created, for example, in an argon ion laser and are linearly polarized with a polarizing beamsplitter (PBS). The half-wave plate (HWP) rotates the polarization state before the photon enters the pair of nonlinear crystals that constitute the entangled-photon source; the initial angle of pump polarization controls the entanglement of the pair produced. Each photon's polarization state can be altered at will by the subsequent HWP and quarter-wave plate (QWP). The decoherers following the state selection allow the production of mixed photon states. The optical elements (QWP, HWP, and PBS) in the tomographic analyzer allow the measurement of each photon in an arbitrary basis. Coincidence measurements of photons allow the quantum state to be determined. (Adapted with permission from James DFV and Kwiat PG (2002) Quantum state entanglement: creation, characterization, and application. *Los Alamos Science* 27: 52–67.)

polarization state of a single photon) before the crystal pair and in the paths of the two daughter photons. To create mixed states, a long birefringent crystal can be used to delay one polarization component with respect to the other. If the delay is longer than the coherence time of the photons, the horizontal and vertical components are effectively decohered; that is, the phase relationship between the different states is destroyed.

The figure also shows schematically the apparatus required for measuring the quantum state. In classical optics, four Stokes parameters are required to specify the polarization of a single beam (i.e., an ensemble of uncorrelated photons); for a pair of photons, 16 projective measurements, each with different wave plate settings, is required. From these 16 measurements, all of the elements of the 4×4 density matrix describing the (in general, mixed) state of the photon pairs can be deduced. This is an example of quantum state tomography, a technique that has found application to a number of quantum optical systems.

Quantum Key Distribution

Two parties, historically known as Alice and Bob, want to have a secret conversation. A generic, classical encryption protocol would begin when Alice and Bob convert their messages to separate binary streams of 0's and 1's, which are then encrypted and decrypted with a set of secret 'keys' known only to the two. Each key is a random string of 0's and 1's that is as long as the binary string comprising each message. To encrypt, Alice (the sender) sequentially adds each bit of the key to each bit of her message, using addition modulo 2. She then sends the encrypted message over a public channel to Bob, who decrypts it by simply repeating the addition modulo 2 of the key to the message. This type of encryption, known as a one-time pad, is currently the only provably secure encryption protocol. But the one-time pad is effective only if Alice and Bob never reuse the key, and more obviously, if the key remains secret. A potential eavesdropper, Eve, cannot be allowed to glean any part of the bit stream that makes up the key. Therein lies a central problem of cryptography – how can secret keys be created and then securely distributed?

Quantum key distribution (QKD) exploits the fundamentally indivisible nature of photons to perform this task. There are a variety of QKD protocols; here we describe one that employs entangled photon pairs (see Figure 3). Alice and Bob use a source such as the one described above to produce maximally entangled photons in the state $|\Phi_+\rangle \equiv \frac{1}{\sqrt{2}}(|HH\rangle + |VV\rangle) = \frac{1}{\sqrt{2}}(|45°,45°\rangle + |-45°,-45°\rangle)$. One photon goes to Alice and the other to Bob. For each pair, Alice and Bob randomly and independently analyze their respective photons (using a polarizing beamsplitter) in the H/V or the 45°/−45° basis. They record a bit value of 0 for all H or 45° results, and a 1 for all V or −45° results. After a sufficient number of measurements (dictated by the length of the key), Alice and Bob have a public discussion, e.g., over the internet. For each detected photon, they announce which basis they used for the measurement, but not the actual measurement result. Whenever they made the same basis choice (50% of the time), the correlations of the entangled state ensure their measured bit values agree. By contrast, they discard the results when they used different bases, because their measurements are completely uncorrelated (see Table 1).

An eavesdropper (Eve) cannot tap the line, as she might with conventional communications, because of the indivisibility of individual photons and the fact


Entangled-photon source
(1) $|\Phi_+\rangle = 1/\sqrt{2}\,(|HH\rangle + |VV\rangle)$
$= 1/\sqrt{2}\,(|45°45°\rangle + |-45°-45°\rangle)$
(2) Pockels cell (on)
(3) $|\Phi_A\rangle = |45°\rangle$
0
Detector
PBS
1
Detector
Alice
(4) $|\Phi_B\rangle = |45°\rangle$
(2′) Pockels cell (off)
Bob
1
0

Figure 3 Quantum cryptography using entangled photons. Entangled photons can be used to create a pair of identical cryptographic keys. One member of an entangled pair (1) is sent to Alice, and the other to Bob. Alice and Bob each randomly and independently analyze their respective photon in one of two linear polarization bases with a polarizing beamsplitter (PBS); the basis can be actively chosen using a Pockels cell before the PBS, as shown, to rotate the polarization (alternatively, the 'choice' could be made by directing the photon onto a nonpolarizing 50/50 beamsplitter; in the transmitted path, one analysis basis is used, in the reflected path, the other is used). In the example shown, Alice used the 45°/−45° basis (2), and measured 45° polarization (3), thus projecting Bob's photon into the identical state (4). Since he chose the H/V analysis basis (2′), he is equally likely to detect a 0 or a 1. By subsequent public discussions Alice and Bob determine the events for which they used the same analysis basis (and discard the other events). For these events Alice and Bob will have obtained identical measurement results, which they may interpret as raw key material. After classical error correction and privacy amplification techniques are applied, the remaining string is the sought-after shared secret key. (Adapted with permission from James DFV and Kwiat PG (2002) Quantum state entanglement: creation, characterization, and application. *Los Alamos Science* 27: 52–67.)

Table 1 Polarization entanglement-based quantum cryptography protocol

Alice's analysis basis	H/V	H/V	45°/−45°	H/V	45°/−45°	45°/−45°	H/V	45°/−45°
Alice's measurement result[a]	*H*	–	*−45°*	*V*	*45°*	*45°*	*V*	*−45°*
Alice's bit value	0	–	1	1	0	0	1	1
Bob's analysis basis	H/V	45°/−45°	45°/−45°	45°/−45°	H/V	45°/−45°	H/V	HV
Bob's measurement result	*H*	*−45°*	*−45°*	*45°*	*H*	–	*V*	*H*
Bob's bit value	0	1	1	0	0	–	1	0
Public discussion: Both photons detected and same basis used?	yes	no	yes	no	no	no	yes	no
Remaining secret key	0		1				1	

[a] In some cases Alice or Bob may not detect a photon due to loss or detector inefficiency. These events simply do not contribute to the key data.

that arbitrary quantum systems cannot be accurately cloned.[8] If Eve steals Bob's photon (a 'denial-of-service' attack), the photon's information never becomes part of the key. Thus, although a wiretap would reduce the rate of the transmission, it would not jeopardize the security of the key. Eve can try to intercept the photon, measure it, and send another one to Bob. But any measurement Eve would make to determine the photon's polarization state would perturb the photon and collapse the entangled state. The photon she sends to Bob would therefore only be 'classically' correlated with Alice's photon. Consequently, Eve's intervention necessarily induces additional errors into Bob's key, which Alice and Bob can detect by publicly revealing a small subset of their actual key. Unfortunately, even with no eavesdropper, the encryption keys created by any real-world quantum cryptography system typically possess a few-percent errors. To make sure their key is secure, Alice and Bob ascribe all errors to Eve and then estimate the maximum amount of information available to the eavesdropper. They then use a classical privacy amplification protocol to reduce Eve's knowledge of the secret key to less than one bit by reducing the length of the key. It has been proven that if the initial error probability per bit is greater than ~15%, no secret bits will remain after error detection and privacy amplification.

Researchers are working to make entanglement-based quantum cryptography more practical. Also, a number of longer distance quantum cryptography demonstrations using weak pulses have been carried out, over tens of kilometers in fibers and in free space. In fact, the first commercially available systems have recently been announced (in Europe and the United States).

Table 2 Method to convert the initial state $|\Phi_+\rangle = \frac{1}{\sqrt{2}}(|00\rangle + |11\rangle)$ into any of the four Bell states

Alice's operation	*Polarization transformation*	*Resultant two-qubit state*
$\hat{I}$, the identity	H → H; V → V	$|\Phi_+\rangle = \frac{1}{\sqrt{2}}(|00\rangle + |11\rangle)$
$\hat{\sigma}_x$	H → V; V → H	$|\Psi_+\rangle = \frac{1}{\sqrt{2}}(|01\rangle + |10\rangle)$
$i\hat{\sigma}_y$	H → V; V → −H	$|\Psi_-\rangle = \frac{1}{\sqrt{2}}(|01\rangle - |10\rangle)$
$\hat{\sigma}_z$	H → H; V → −V	$|\Phi_-\rangle = \frac{1}{\sqrt{2}}(|00\rangle - |11\rangle)$

Quantum Superdense Coding

It is possible for Alice to send Bob two bits of classical information using a single qubit in the quantum superdense coding protocol. Suppose that Alice and Bob share one qubit each of an entangled pair in the maximally entangled state $|\Phi_+\rangle = \frac{1}{\sqrt{2}}(|00\rangle + |11\rangle)$, where we have returned to the generic labeling scheme for the qubit states. Alice has two classical bits of information, which is equivalent to one of four choices. She can encode this information by applying one of four possible transformations on her qubit; a suitable set of transformations are the three Pauli matrices and the identity (i.e., do nothing). This set of operations can be performed experimentally on photon qubits quite easily, e.g., using waveplates, as indicated in Table 2. The four resultant two-qubit states are all maximally entangled and are orthonormal. They form a special basis for the two-qubit states, the Bell basis, which is of particular use in analyzing entanglement.

Alice now sends her qubit to Bob, e.g., through an optical fiber. Bob can then perform a Bell state analysis[9] on his qubit pair, i.e., a projective measurement of the two-qubit state in the Bell basis. The result immediately reveals the choice of operation Alice made, and in effect, two bits of classical information have been encoded on a single qubit.

---

[8] The no-cloning proof is very simple. If we have a copying operation such that $|0\rangle|c\rangle \rightarrow |0\rangle|0\rangle$ and $|1\rangle|c\rangle \rightarrow |1\rangle|1\rangle$ ($|c\rangle$ is the initial state of the copier), then by linearity, a superposition becomes an entangled state, instead of two copies: $\frac{(|0\rangle + |1\rangle)}{\sqrt{2}}|c\rangle \rightarrow \frac{(|0\rangle|0\rangle + |1\rangle|1\rangle)}{\sqrt{2}} \neq \frac{(|0\rangle + |1\rangle)}{\sqrt{2}}\frac{(|0\rangle + |1\rangle)}{\sqrt{2}}$.

[9] Complete discrimination of all four Bell states is presently an unsolved technical problem: for photons one needs either a nonlinear interaction (which is typically very weak) or to exploit so-called 'hyper-entanglement' involving other entangled degrees of freedom of the photons.

Quantum Teleportation

Another application of entanglement is quantum state teleportation (Figure 4), in which the infinite amount of information contained in an arbitrary qubit state $|\psi\rangle = \alpha|0\rangle + \beta|1\rangle$ is transferred by communication of two bits of classical information between Alice and Bob, if they also share two qubits in the maximally entangled state $|\Psi_-\rangle$. The three-photon initial state (i.e., the input photon plus the two entangled photons) is

$$|\psi_0\rangle = (\alpha|H\rangle + \beta|V\rangle) \otimes \frac{1}{\sqrt{2}}(|HV\rangle - |VH\rangle),$$

which can be rewritten with the first two photons (the input plus the first half of the entangled pair) represented by the Bell state basis:

$$\begin{aligned} |\psi_0\rangle = \ & \tfrac{1}{2}\{|\Phi_+\rangle \otimes (-\beta|H\rangle + \alpha|V\rangle) \\ & + |\Phi_-\rangle \otimes (\beta|H\rangle + \alpha|V\rangle) \\ & + |\Psi_+\rangle \otimes (-\alpha|H\rangle + \beta|V\rangle) \\ & + |\Psi_-\rangle \otimes (-\alpha|H\rangle - \beta|V\rangle)\}. \end{aligned}$$

Now suppose that a Bell state measurement is performed on the first two photons. The third photon

(a) Before Bell-state measurement


Entangled-photon source
Charlie's unknown photon
ϕ_+
ϕ_-
ψ_+
ψ_-
Entangled photons
To Bob
Alice's teleporter (Bell state analyzer)

(b) After Bell state measurement


Bob's photon is projected into a pure state
ψ_+
Two bits of classical information
Alice relays results to Bob
To Bob

(c) After classical communication


Delay cavity
Optical elements
Bob's photon assumes the same polarization state as Charlie's
Classical information
Bob applies one of four transformations

Figure 4 Quantum state teleportation. (a) Teleportation requires an entangled photon source, a Bell state analyzer and a classical communications channel. One entangled photon goes to Bob and the other to Alice, who also receives a photon of unknown polarization state. (b) Alice performs a joint polarization measurement of the two photons and relays the result to Bob using two classical bits of information. The photon going to Bob is projected into a pure state as a result of Alice's measurement. (c) Upon receiving Alice's classical information, Bob performs a simple transformation on his photon (which he has been storing), such as a rotation of the polarization vector. The resulting state of his photon is then identical to the unknown state Alice wished to teleport. (Adapted with permission from James DFV and Kwiat PG (2002) Quantum state entanglement: creation, characterization, and application. *Los Alamos Science* 27: 52–67.)

is immediately projected into one of four possible states, which can be transformed back into the state of the original input photon by a simple operation, e.g., with a waveplate. For example, if the Bell state measurement produced the result $|\Psi_+\rangle$, the third photon is immediately 'collapsed' into the pure state $|\psi_3\rangle = -\alpha|H\rangle + \beta|V\rangle$. By applying a π-phase shift to the horizontal polarization (relative to the vertical), $|\psi_3\rangle$ can be transformed into the original input state: $|\psi'_3\rangle = \alpha|H\rangle + \beta|V\rangle$. Alice (who does the Bell state measurement) need only communicate to Bob (who wants to receive the teleported photon) which of the four Bell states she measured. Note that during the entire teleportation procedure, neither Alice nor Bob can obtain any idea of the values of the parameters α and β, which specify the state. Also, because Alice's measurement collapses the unknown state, there is only a single copy at the end of the protocol.

Quantum state teleportation was first demonstrated experimentally by Zeilinger and coworkers (University of Innsbruck, Austria). The group was able to determine two of the four Bell states unambiguously (the other two states gave the same experimental signature) and proved for those cases that the state of the input photon could indeed be transferred to Bob. Other experiments have realized modified forms of quantum teleportation in different systems. For example, Kimble's group (California Institute of Technology) teleported the coherent state of an optical mode using squeezed (rather than polarization-entangled) light. Researchers have recently suggested how teleportation might form the basis of a distributed network of quantum communication channels, and how it might enable quantum computing in all-optical systems.

Other Application of Optical Entanglement

Quantum Computing

The most challenging and powerful application of quantum information is large-scale quantum computing. Two features that make quantum information processing potentially powerful are the exponentially large Hilbert space, which gives quantum registers very large capacities, and quantum parallelism, which means that data processing tasks can be performed very efficiently. One fundamental drawback, which severely constrains useful applications of quantum computers, is that the final measurement can only produce a number of classical bits equal to the number of qubits. Thus, quantum computers are limited to performing tasks in which a small amount of information is meant to be gleaned from processing a large amount of data; examples include searching an unstructured database for a specific entry (Grover's algorithm) or finding the periodicity of a function (the quantum Fourier transform). This second task is central to Shor's factor-finding algorithm, the most famous quantum computing algorithm to date.

A practicable quantum computer technology must have at least the following features, first identified by DiVincenzo:

- A set of well-characterized, distinguishable qubits to form a quantum data storage register.
- The ability to initialize the qubits of the register in a simple fiducial state.
- Decoherence times that are much longer than the time needed to perform logical operations.
- The ability to perform any single qubit operation on any qubit in the register, and the ability to perform two-qubit conditional logic gates (such as the CNOT gate: $\alpha|00\rangle + \beta|01\rangle + \gamma|10\rangle + \delta|11\rangle \rightarrow \alpha|00\rangle + \beta|01\rangle + \gamma|11\rangle + \delta|10\rangle$). Together, these operations constitute a universal set of quantum gates, from which all other gates can be synthesized.
- The ability to measure each qubit.

All-optical schemes have been used to implement small quantum algorithms. However, most of the approaches are not scalable, due to the limitations of non-linear optics to perform a CNOT gate at the single-photon level. Recent proposals have suggested that very high efficiency single-photon detectors, along with sources of single photons 'on-demand,' allow scalable quantum computing with only linear optics; preliminary two-qubit gates have been experimentally demonstrated. A number of other promising candidate technologies that meet DiVincenzo's five requirements are being pursued vigorously. For example, the ability to create multi-qubit entanglement and perform reliable measurements on trapped ions cooled and manipulated by lasers has recently been demonstrated. Solid state systems offer the possibility of scalability, and a number of schemes, such as quantum dots, isolated impurities with nuclear spins, and superconducting quantum interference devices (SQUIDs), are being investigated. It is possible that the final quantum computing technology may take the form of a hybrid between various present approaches.

Lithography

Lithography, in which a pattern is optically imaged onto some photoresistive material, is the primary method of manufacturing microscale or nanoscale electronic devices. An inherent limitation of this process is that details smaller than a wavelength of light cannot be written reliably. However, quantum state entanglement might circumvent this limitation. Under the right circumstances, the interference pattern formed by beams of entangled photons can have half the classical fringe spacing. Quantum lithography requires two beams of photons, a coherent superposition consisting of the state in which two photons are in beam A while none are in B, and the state in which no photon is in beam A while two photons are in B. Such number-entangled states can be made in the laboratory, and the predictions about fringe spacings have been verified. However, other obstacles must be overcome to surpass current classical-lithography techniques.

Two-Photon Imaging and Microscopy

At present, two-photon microscopy is widely used to produce high-resolution images, often of biological systems. However, the classical light sources (lasers) used for the imaging have random spreads in the temporal and spatial distributions of the photons, and the light intensity must be very high if two photons are to intersect within a small enough volume to cause a detectable excitation. Such high intensity can damage the system under investigation. Because the temporal and spatial correlations may be much stronger between members of an entangled photon pair, much weaker light sources could be used, which would be much less damaging to the systems being observed. The development of such systems is currently an active area of research.

List of Units and Nomenclature

Entanglement: a property of quantum systems consisting of two or more distinct subsystems, often separate particles. When transformations on one system do not affect the other, the state is said to be separable; when this is not the case, and the quantum state of the overall system cannot be resolved into separate states of the individual pieces, the system is entangled.

Pure and mixed states: when the probability amplitudes specifying a quantum state are deterministic, the state is said to be pure; when the amplitudes are random quantities, the state is mixed. The distinction is similar to that of coherent and partially coherent optical fields.

Quantum computer: an information processing device that exploits quantum mechanical phenomena to greatly enhance computational power for certain problems. Some mathematical problems thought to be intractable on conventional computers can, in theory, be performed efficiently on a quantum computer.

Quantum crytography (also known as quantum key distribution): a quantum information protocol by which two parties acquire a shared series of random numbers (a cryptographic key) by exploiting the quantum nature of light. Absolute security can be proven by virtue of the indivisibility and uncopy-ability of individual quanta.

Quantum state tomography: a means by which quantum states can be determined experimentally by performing a series of appropriate measurements on multiple identically prepared systems. From such measurements, the elements of the density matrix, which fully specifies the state, may be inferred.

Quantum superdense coding: A quantum information protocol by which two bits of classical information may be communicated by a single quantum bit, initially part of an appropriate entangled quantum state.

Quantum teleportation: a quantum information protocol by which the unknown quantum state of one particle can be transferred to another distant particle, using a pair of entangled particles, a projective measurement, and exchange of two bits of classical information.

Qubit (quantum bit): a two-level quantum mechanical system, which constitutes the building blocks of quantum information processing devices. Examples include a spin-1/2 particle, an atom with two well-isolated levels, or the polarization of a photon.

See also

Nonlinear Optics, Applications: Three-Dimensional Microfabrication. **Quantum Optics:** Quantum Computing with Atoms.

Further Reading

Berman GP, Doolen GD, Mainieri R and Tsifrinovitch V (1998) *Introduction to Quantum Computers*. Singapore: World Scientific.

Bouwmeester D, Ekert AK and Zeilinger A (eds) (2000) *The Physics of Quantum Information*. Berlin: Springer-Verlag.

Braunstein SL and Lo HK (eds) (2001) *Scalable Quantum Computers: Paving the Way to Realization*. Berlin: Wiley-VCH.

DiVincenzo DP (2000) The physical implementation of quantum computation. *Fortschrcitte der Physik* 48: 771–783.

Gisin N, Ribordy G, Tittel W and Zbinden H (2002) Quantum cryptography. *Review of Modern Physics* 74: 145–195.

Kok P, Braunstein SL and Dowling JP (2002) Quantum lithography. *Optics and Photonics News* 13(9): 24–27.

Lo HK, Popescu S and Spiller T (eds) (1998) *Introduction to Quantum Computation and Information*. Singapore: World Scientific.

Macchiavello C, Palma GM and Zeilinger A (eds) (2000) *Quantum Computation and Quantum Information Theory.* Singapore: World Scientific.

Mandel L and Wolf E (1995) *Optical Coherence and Quantum Optics*. Cambridge, UK: Cambridge University Press.

Nielsen MA and Chuang IL (2000) *Quantum Computation and Quantum Information*. Cambridge, UK: Cambridge University Press.

Williams CP and Clearwater SH (1998) *Explorations in Quantum Computing*. Santa Clara: Telos.

Yariv A (1989) *Quantum Electronics*. New York: Wiley.

Laser Cooling of Ions

H Walther, University of Munich and
Max-Planck-Institute for Quantum Optics, Garching,
Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The fact that light can exert a mechanical force on atoms by the transfer of linear momentum was recognized as long ago as the 1930s, when Frisch demonstrated the deflection of an atomic beam using resonant light. With the advent of tunable laser light in the early 1970s, a much larger excitation rate for atoms was achieved, leading to a much stronger deflection. A little earlier it was also observed that in addition to the force resulting from photon recoil, a dipole force is also produced in a focused light beam so that even small solid particles can be trapped and manipulated. The original proposal for laser cooling of atomic gases was put forward in 1975 and later laser cooling of trapped ions was proposed. The principle of laser cooling is very simple. The ion is excited by laser light below a resonance frequency; in order that a transition can be made, the residual energy has to be taken from the kinetic energy of the particle, leading to cooling of the particle. In this article, we will discuss this cooling process in more detail.

Laser Cooling of Ions in a Radiofrequency Trap

Of the various proposed and realized methods for laser cooling of atoms or trapped ions, sideband cooling is conceptually the simplest and most efficient. It allows a trapped particle to be cooled to the quantum-mechanical ground state of a harmonic trap potential. The process can be regarded as anti-Stokes Raman scattering of the pseudomolecule formed by the ion and the trap. If the linewidth of an optical transition in this atom is smaller than the vibrational frequency of the trapped ion, both electronic levels of the transition split into a ladder of resolved vibrational levels. The absorption spectrum consists of a carrier at the resonance of the free atom and sidebands at multiples of the vibrational frequency. With a laser tuned to the m-th lower frequency sideband, each absorption of a photon will reduce the vibrational energy of the atom by m quanta. Since the subsequent spontaneous re-emission will, on average, not change the vibrational excitation, repeated photon scattering processes lead to efficient cooling of the atom. This cooling will continue until the absorption probability for the low-frequency sidebands decreases when approaching the vibrational ground state of the ion in the trap. The final temperature is limited by the heating process caused by photon recoil. However, after the ion is cooled to the vibrational ground state this heating process disappears, when the vibrational energy of the ion is larger than the recoil energy of a photon. In this case, the recoil is taken up by the entire trap setup, as it is the case in the Mössbauer effect.

Despite these obvious advantages of sideband cooling, relatively few experiments have been made using this method. This is because the regime, where the oscillation frequency ω is larger than the natural linewidth Γ of an optical transition (the so-called 'strong binding regime'), is not easily accessible. Vibrational frequencies of ions in standard electromagnetic traps are of the order of 1 MHz, whereas linewidths of electric dipole transitions in positive ions are in the range 20–50 MHz. In this 'weak binding regime' with $\Gamma > \omega$, laser cooling of trapped ions is essentially analogous to Doppler cooling of free atoms. The minimum temperature is given by the Doppler limit $k_B T = \hbar\Gamma/2$, and the mean vibrational quantum number is $\langle n\rangle = \Gamma/2\omega > 1$. The first experiments with cooling on resolved sidebands, therefore, used a strongly forbidden optical transition or stimulated Raman transitions. In these cases, however, sideband cooling is inevitably slow and it was used only to extract a few vibrational quanta from Doppler-precooled ions. In both experiments the vibrational ground state was reached to a very good approximation (mean quantum number $\langle n\rangle \approx 0.05$). Raman sideband cooling has also recently been applied to neutral atoms in optical traps.

Laser cooling of trapped ions was motivated by their possible use for optical frequency standards where the relativistic Doppler shift, as well as the Stark shift due to the trap potential, are eliminated at low temperatures. Cooling to the ground state also opens up the possibility of studying a well-controlled mechanical quantum oscillator experimentally. This led to the realization of nonclassical states of motion, investigation of quantum decoherence phenomena, and the demonstration of a quantum logic gate for quantum computing.

Sideband Cooling

Most theoretical treatments of sideband cooling consider a static harmonic trap, whereby the time dependence of the potential of the radio-frequency (rf) ion trap is neglected. In such a model a running laser wave $\propto \exp(ikr)$ of wave number k induces transitions between the eigenstates $|n\rangle$ and $|n'\rangle$ of a harmonic oscillator. The relevant transition matrix elements are

$$U_{n'n} = \langle n'|\exp(ikr)|n\rangle \qquad [1]$$

$$U_{n'n} = \exp(-\eta^2/2)\sqrt{\frac{n_<!}{(n_< + \Delta n)!}}(i\eta)^{\Delta n} L_{n_<}^{\Delta n}(\eta^2) \qquad [2]$$

Here $\eta = kx_0 = k\sqrt{\hbar/2m\omega}$ is the Lamb–Dicke parameter for the spatial extension x_0 of the ground state, $n_<$ the smaller of the two numbers n and n', $\Delta n = |n - n'|$, and L_n^m denotes the generalized Laguerre polynomial. In the case of high vibrational excitation $n, n' \gg 1$, $U_{n',n}$ can be approximated as

$$U_{n+\Delta n,n} \approx i^{\Delta n} J_{\Delta n}(2\eta\sqrt{n}) \qquad [3]$$

with the Bessel function of n-th order J_n. The argument of the Bessel function is the product of the wave number and the classical vibration amplitude of the highly excited state. This is the result one would expect for the frequency-modulated spectrum of a classical oscillator. For arguments β among the Bessel functions $J_n(\beta)$, those of order $n \approx \beta$ have the largest modulus. Consequently, during the initial stages of cooling it is most efficient to tune the laser so that it induces transitions with $\Delta n \approx 2\eta\sqrt{n} \gg 1$.

For the final stages of cooling one can usually assume that the ion is in the Lamb–Dicke regime, i.e., that it is localized within dimensions of the optical wavelength. A detailed study of the limits of sideband cooling in a static trap was carried out in 1984. The final distribution of population over the vibrational states is thermal and can be characterized by a mean occupation number $\langle n\rangle$ or a temperature $T = \hbar\omega/k_B \ln(1 + 1/\langle n\rangle)$. The number $\langle n\rangle$ is a rational function of the four frequencies involved, i.e., the natural linewidth Γ, the oscillation frequency in the trap ω, the laser detuning δ, and the Rabi frequency ω_R. For certain limiting cases, simple expressions for the mean vibrational excitation $\langle n\rangle$ can be derived from the general result. The lowest vibrational excitation is achieved in the case of well-resolved sidebands ($\omega \gg \Gamma$) and under weak laser excitation ($\omega_R \ll \Gamma$), tuned to the first sideband ($\delta = -\omega$):

$$\langle n\rangle = \left(\alpha + \frac{1}{4}\right)\frac{\Gamma^2}{4\omega^2} \qquad [4]$$

The constant α depends on the geometry of excitation and photon re-emission and is of the order of 1. In the case of strong saturation ($\omega_R \gg \Gamma$) of the first sideband ($\delta = -\omega$), the mean vibrational quantum number is proportional to the laser intensity:

$$\langle n\rangle = \frac{\omega_R^2}{8\omega^2} \qquad [5]$$

This case is of practical relevance if one wants to detect a fluorescence signal on the cooling transition, for example, to measure the internal state of the ion in a double-resonance experiment, while keeping the ion cooled. For the choice of parameters $\omega_R = \omega = -\delta$, the ion is still predominantly in the vibrational ground state ($\langle n\rangle \approx 1/8$), but photons are scattered from the wing of the saturation-broadened carrier at a rate $P = \Gamma\omega_R^2/(\Gamma^2 + 2\omega_R^2 + 4\delta^2) \approx \Gamma/6$, which is already one-third of the maximum scattering rate. Finally, in the case of large laser detuning ($\delta \gg \Gamma, \omega, \omega_R$), the energy is proportional to the detuning because the lower vibrational levels are no longer depleted by the laser:

$$\langle n\rangle \approx \frac{\alpha + 1}{4}\frac{\delta}{\omega} \qquad [6]$$

If the Lamb–Dicke parameter satisfies $\eta \ll 1$, the strength of the sidebands can be calculated from a power series expansion of the matrix elements of eqn [2] and the thermal distribution of population over the oscillator levels. The $U_{n',n}$ are evaluated to first-order in η only. In this approximation, the height of the first lower-frequency sideband in the absorption spectrum relative to the carrier is $\eta^2\langle n\rangle$ and that of the first higher-frequency sideband $\eta^2(\langle n\rangle + 1)$. This information can be used to determine experimentally the vibrational quantum number from the absorption spectrum. The strengths of the higher-order sidebands contain higher powers of η^2 and therefore decrease rapidly.

Let us now briefly review some facts about the motional spectrum of an ion in a Paul trap, which is not just a static system but possesses an explicitly time-dependent potential. The equation of motion for a classical particle of charge e and mass m in the quadrupole potential of the trap $\phi(r,z) = (V_0 - U_0 \cos \Omega t)(r^2 - 2z^2)/2r_0^2$ is given by the Mathieu differential equation:

$$\frac{\delta^2 r}{\delta \tau^2} + (a_r - 2q_r \cos 2\tau)r = 0 \qquad [7]$$

with dimensionless parameters:

$$\tau = \frac{\Omega}{2}t, \qquad a_r = \frac{4eV_0}{m\Omega^2 r_0^2}, \qquad q_r = \frac{2eU_0}{m\Omega^2 r_0^2} \qquad [8]$$

Here a static voltage V_0 and an alternating voltage with amplitude U_0 and frequency Ω are applied to a Paul trap with the radius of the ring electrode r_0. The equation of motion for the z coordinate is obtained by multiplying the parameters a and q by the factor -2. The general solution of the Mathieu equation in the first stability region of the (a,q) parameter space can be written by using the Floquet ansatz:

$$r(\tau) = A\sum_{j=-\infty}^{\infty} c_j \cos(2j+\beta_r)\tau + B\sum_{j=-\infty}^{\infty} c_j \sin(2j+\beta_r)\tau \qquad [9]$$

where A and B are constants determined by the initial conditions, and the c_j and β_r depend on a and q. In the first stability region, where most of the experiments are carried out, the value of β_r is between 0 and 1. According to eqn [9] the motional spectrum of the ion has resonances at

$$\omega_{r,j} = \left(j \pm \frac{\beta_r}{2}\right)\Omega, \qquad j = 0,1,2\ldots \qquad [10]$$

In the adiabatic approximation, which is valid for $a, q^2 \ll 1$, the motion of the ion can be separated into an oscillation at the driving frequency Ω, the so-called micromotion, and a slower oscillation, called the secular motion, describing the oscillation in the time-averaged pseudopotential. This pseudopotential describes the effect of the ponderomotive force of the oscillating trapping field that drives the ion to the field minimum at the center of the trap. Since, in the quadrupole trap the pseudopotential is harmonic, the solution to the equation of motion can be approximated as

$$r(\tau) = r_0 \cos\beta_r\tau\left(1 + \frac{q_r}{2}\cos 2\tau\right) \qquad [11]$$

The approximate expression for β_r is $\beta_r = \sqrt{q_r^2/2 + a_r}$ and the secular frequencies are given by

$$\omega_r = \frac{\Omega}{\sqrt{8}}\sqrt{q_r^2 + 2a_r}, \qquad \omega_z = \frac{\Omega}{\sqrt{2}}\sqrt{q_r^2 - 2a_r} \qquad [12]$$

which are the lowest-order resonances $\omega_{r,z} = \beta_{r,z}\Omega/2$ in the Floquet ansatz, eqn [9]. From eqn [11] it is seen that the amplitude of motion at the resonances $\Omega \pm \omega$ is a factor $q_r/4$ smaller than those at the resonance ω. It is noteworthy that the frequency Ω of the driving field does not appear directly in the motional spectrum, but only in combination with the secular frequency ω. This changes, however, if there is an additional static force acting on the ion, displacing it from the center of the quadrupole. The approximate solution to the equation of motion then becomes:

$$r(\tau) = r_1 + r_0 \cos\beta\tau\left(1 + \frac{q_r}{2}\cos 2\tau\right) \qquad [13]$$

and a resonance at Ω appears. The force that displaces the ion by r_1 may be due to static electric stray fields or the presence of a second ion in the trap. These effects can have a strong influence on sideband laser cooling of the trapped ions. A number of theoretical studies have been published on the quantum-mechanical treatment of the Paul trap. The explicitly time-dependent potential does not allow stationary states with time-independent energy eigenvalues. One can, however, as in the case of the pseudopotential model, distinguish between two time-scales and construct wave functions of the harmonic secular oscillator that show some additional breathing motion at the trap frequency. A quantum-mechanical theory of sideband cooling in the time-dependent potential of the Paul trap thus far exists only for special cases; in 1994 there was a case where the ion was localized in the Lamb–Dicke regime at the node of a standing laser wave and time averaged kinetic energies were calculated. Minima of the energy that agree with the results of the theory for the static harmonic trap to within a factor of 2 were found. The strongest modifications to the predictions of the cooling theory for the static trap arise in the dependence of the energy on the laser detuning. The influence of the micromotion gives rise to heating for certain regions of negative laser detuning (on the high-frequency side of a low-frequency micromotion sideband) and to cooling for some positive detunings (on the low-frequency side of a high-frequency micromotion sideband).

Trapped LASER-cooled ions have a variety of applications in spectroscopy and other fields.

In the following, a phenomenon will be discussed where observations during the cooling process of ions in traps is interpreted as phase transitions between chaotic and ordered ion structures during the cooling process.

Generation of Chaos During the Cooling Process and Phase Transitions to Ordered Configurations

Using a Paul trap, it is possible to study the physics of a few-body phase transition of ions. The ordered state of the trapped ions can be observed directly by monitoring their resonantly scattered light. The transition to an ordered or 'crystalline' configuration is expected when the Coulomb coupling constant which corresponds to the ratio of Coulomb energy to the kinetic energy of a particle, is larger than 1. The ordered structures represent configurations of maximum density for the ions, they are determined by the trap potential pushing the ions towards the trap center, and by the Coulomb repulsion between the ions acting in the opposite direction, so that minimum energy configurations are finally adopted. The system corresponds to an ordered one-component plasma or a strongly coupled plasma.

In the following, computer simulations of the phase transition in the Paul trap will be reviewed. In the trap the ions are subjected to five different forces. These are the force $\mathbf{F}^{(\text{trap})}$, arising from the dynamical rf trapping field, the Coulomb interaction between the ions $\mathbf{F}^{(\text{Coul})}$, the laser cooling force $\mathbf{F}^{(\text{laser})}$, a random force $\mathbf{F}^{(\text{rand})}$ arising from the recoil of the spontaneously emitted photons, and a parasitary force $\mathbf{F}^{(\text{cont})}$, arising from a contact potential, which may be generated unintentionally by locally coating the electrodes with the trapped atoms.

The potential generated by the rf voltage applied to the hyperbolic electrodes of the trap is given by

$$\phi(\mathbf{r},t) = \varphi(t)[x^2 + y^2 - 2z^2]$$
$$\varphi(t) = \frac{U_0 + V_0\cos(\Omega t)}{r_0^2 + 2z_0^2} \qquad [14]$$

where U_0 and V_0 are the dc and ac components of the voltages applied to the trap. From eqn [1] we obtain the trapping force and the resulting equation of motion of a single ion in the trap:

$$\mathbf{F}^{(\text{trap})} = m\ddot{\mathbf{r}} = \mathbf{e}\nabla\phi(\mathbf{r},t) = -2\mathbf{e}\varphi(t)[\mathbf{r} - 3z\mathbf{e}_z] \qquad [15]$$

where m, $\mathbf{r}$, and $z\mathbf{e}_z$ denote the mass of the ion, the position, and the $z\mathbf{e}_z$-component of the position vector, respectively.

The Coulomb interaction between the particles results in the force:

$$\mathbf{F}_i^{(\text{Coul})} = \frac{e^2}{4\pi\varepsilon_0}, \sum_{m\neq 1} \frac{\mathbf{r}_i - \mathbf{r}_m}{[\mathbf{r}_i - \mathbf{r}_m]^3} \qquad [16]$$

In the process of laser cooling, every scattered photon changes the momentum of an ion on the average by an amount $\hbar k$.

The ensemble average of the resulting laser cooling force acting on the i-th ion is thus:

$$\mathbf{F}_i^{(\text{laser})} = \hbar k R[\mathbf{r}_i(t); \dot{\mathbf{r}}_i(t)] \qquad [17]$$

The number $N_i(l)$ of spontaneously emitted photons from the i-th ion during the l-th cycle of period $T = 2\pi/\Omega$ is

$$N_i(l) \int_{(l-1)T}^{lT} R[\mathbf{r}_i(t); \dot{\mathbf{r}}_i(t)]\mathrm{d}t \qquad [18]$$

In the simulations, it is assumed that these N_i spontaneous photons are emitted one by one, at the end of each rf cycle, rather than emitting them one by one, according to the appropriate photon-statistics during the cycle. The orientation of the unit vector $\hat{\mathbf{u}}_j$, which points in the direction of the j-th emitted photon, is chosen at random, but weighted with a $\cos^2$ distribution (dipole characteristic) with respect to the laser polarization axis. This way, only the linearly polarized spontaneously emitted photons have been simulated in the calculations. The circularly polarized ones, which occur with a $\sin^2$ distribution, have been neglected. The random force $\mathbf{F}_i^{(\text{rand})}$, is thus:

$$\mathbf{F}_i^{(\text{rand})}(t) = \hbar k \sum_{l=-\infty}^{\infty} \delta(t - lT) \sum_{j=1}^{N_i} \hat{\mathbf{u}}_j \qquad [19]$$

In some of the calculations, a contact potential has been taken into account which is generated experimentally by a coating of the quadrupole electrodes by the trapped particles. Close to the center of the trap, the contact potential gives rise to an approximately homogeneous electric field. Altogether, the motion of the i-th particle is governed by the sum of the above forces, that is:

$$m\ddot{\mathbf{r}}_i = \mathbf{F}_i^{(\mathrm{trap})} + \mathbf{F}_i^{(\mathrm{Coul})} + \mathbf{F}_i^{(\mathrm{laser})} + \mathbf{F}_i^{(\mathrm{rand})} + \mathbf{F}_i^{(\mathrm{cont})} \qquad [20]$$

Given appropriate initial conditions, the eqns of motion [20] are integrated forward in time to obtain the trajectories of the n-ion system. These trajectories provide all the information necessary to find the quantities of interest, such as the occupation probability density of the i-th ion in phase space (i.e., the probability density of finding the i-th ion at a given position, and with a given velocity), the (total) kinetic energy, and the fluorescence intensity.

Some of the results of the described simulations will be summarized below. Figure 1 shows the excitation spectrum of the ions as a function of laser detuning. The experiment confirms the results of the simulations.

Owing to the Coulomb interaction of the ions at particular phases of the cooling process, chaos in the ion cloud is observed leading to a heating process of the ions by the applied field of the trap. This heating mechanism was investigated in the simulations in detail and the summary of the results is given in Figure 2.

For zero laser power and large r, there is no net heating of the ions. This is confirmed by the experiments, in which, even in the absence of a cooling laser, large clouds of ions can be stored in a Paul trap over several hours without being heated out of the trap. The ions are far apart, the Coulomb force is small, and on short time-scales the ions behave essentially like independent singly stored ions. For this reason, this part of the heating diagram is called the 'Mathieu regime' as it is well described by the Mathieu equation [7]. Turning on a small laser power, the rms radius r reduces drastically due to laser



Figure 1 Excitation spectrum of five ions as a function of laser detuning. When the laser detuning is changed the cooling rate of the ion is varying. Two phase transition points (and bistability) are apparent. Insets show the results of the molecular dynamics calculations shortly before and after the jump, which demonstrates directly the existence of a transition from a cloud phase to a crystalline state. The units given at the insets are μm.



Figure 2 Average heating rate of five ions in a Paul trap versus the rms radius of the ion configuration. The insets show the power spectrum and the corresponding stroboscopic Poincaré sections in the *x*–*z* plane of relative separation for two ions in three characteristic domains: the quasiperiodic regime, the chaotic regime and the Mathieu regime. All length scales are in units of micrometers. Units gives at the *x*–*z* axis of the insets are in μm.

cooling, but comes to a halt at about 14 μm where chaotic rf heating sets in and balances the cooling power of the laser. Increasing the laser power results in an even smaller cloud. The smaller cloud produces more chaotic rf heating, as seen clearly by the negative slope of the heating curve (Figure 2) in the range $8 < r < 14$ μm.

In the range 4 μm $< r <$ 8 μm, there is still chaotic heating, but the slope of the heating curve is positive. As a consequence of the resulting triangular shape of the heating curve, at about 8 μm, the chaotic heating power can no longer balance the cooling power of the laser, and the cloud collapses into the 'crystalline' state located at $r \approx 3.8$ μm; a 'phase transition' has occurred. Due to this collapse, the behavior of the heating rate in the range 3.8 μm $< r <$ 8 μm cannot be studied by equilibrating laser cooling and rf heating. In this case, we start out from the crystal state and slightly displace the ions to explore the 'vicinity' of the crystal. We observe no heating for 3.8 μm $< r <$ 4 μm, but quasiperiodic motion, and thus name this regime the 'quasi-periodic' regime. We call the upper edge of the quasiperiodic regime ($r \approx 4$ μm) the 'chaos threshold'. An initial condition beyond the chaos threshold, i.e., satisfying $r > 4$ μm, leads to heating and expansion of the ion configuration and numerical data relevant for the shape of the heating curve can be taken during this 'explosion phase'. The laser power P is set to zero for this type of experiment. We conjecture that, apart from the trivial case of a single stored ion, the heating curve is 'universal', i.e., its qualitative shape, including the existence of the chaotic regime, does not depend on the number of simultaneously trapped ions.

For the quasiperiodic, the chaotic and the Mathieu-regime, respectively, the corresponding type of power spectrum are shown in the insets above the abscissa of Figure 2. The data were actually taken from the case of two ions, but would look similar in the five-ion case. A discrete spectrum in the quasi-periodic regime and a complicated



Figure 3 Ordered ion configuration of two, three, four, and seven laser-cooled Mg^+ ions confined in a Paul trap and observed using resonantly scattered light. The average ion separation is 20 μm. The structures of four and seven ions are slightly deformed owing to contact potentials in the trap.

noisy spectrum in the chaotic regime is obtained. The spectrum in the Mathieu regime is again quite simple and dominated by the secular motion frequency. Stroboscopic pictures of the locations of two ions in the $x-y$ plane of the trap characterizing the three regions, are shown on the insets below the abscissa of Figure 2.

Some of the ordered ion structures observed experimentally are shown on Figures 3 and 4. The structures in Figure 3 were obtained in a Paul trap; the others are measured in a storage ring leading to quasi-linear structures of the ion configurations, depending on the symmetry of the trap. Ordered ion structures have also been observed in Penning traps. Due to the symmetry of this trap rotationally symmetric structures are observed.

Conclusion

Laser cooling of ions in traps provides an excellent tool for numerous experiments, varying from tests of basic physics to important and new applications in quantum information processing. The linear ion structure shown on Figure 4 is presently investigated in many laboratories in order to realize gates for



Figure 4 Crystalline structures of laser-cooled $^{24}Mg^+$ ions in the quadrupole storage ring. At a low ion density the ions form a string along the field axis (upper). Increasing the ion density transforms the configuration to a zigzag (middle). At still higher ion densities, the ions form ordered helical structures on the surface of a cylinder, e.g., three interwoven helices (lower). As the fluorescent light is projected onto the plane of observation in this case the inner spots are each created by two ions seated on opposite sides of the cylindrical surface, resulting in a single, bright area. (Reproduced by permission of *Nature* from Birkl G, Kassner S and Walther H (1992) Multiple shell structures of laser cooled $^{24}Mg^+$ ions in a quadrupole storage ring. *Nature* 357: 310–313.)

quantum computing. Single trapped ions in cavities may be used as deterministic light sources for secure single photon communication links. Furthermore, in many laboratories single laser-cooled ions are investigated as the basis for new time and frequency standards, being several orders of magnitude more accurate than our present atomic clock.

See also

Chaos in Nonlinear Optics. **Quantum Optics:** Entanglement and Quantum Information; Quantum Computing with Atoms.

Further Reading

Arimondo E, Philips WD and Strumia F (eds) (1992) Laser manipulation of atoms and ions. *Proceedings of the International School of Physics Enrico Fermi, Course CXVIII*. Amsterdam, Oxford, New York, Tokyo: North Holland.

Ashkin A (1970) Atomic-beam deflection by resonance-radiation pressure. *Physical Review Letters* 25: 1321–1324.

Birkl G, Kassner S and Walther H (1992) Multiple shell structures of laser cooled $^{24}Mg^+$ ions in a quadrupole storage ring. *Nature* 357: 310–313.

Blümel R, Chen JM, Peik E, Quint W, Schleich W, Shen YR and Walther H (1988) Phase transitions of stored laser-cooled ions. *Nature* 334: 309–313.

Blümel R, Kappler C, Quint W and Walther H (1989) Chaos and order of laser-cooled ions in a Paul trap. *Physical Review A* 40: 808–823.

Bollinger JJ, Kriesel JM, Mitchell TB, King LB, Jensen MJ, Itano WM and Dubin DHE (2003) Laser-cooled ion plasmas in Penning traps. *Journal of Physics B: Atomic Molecular Optical Physical* 36: 499–510.

Cirac JI, Garay LJ, Blatt R, Parkins AS and Zoller P (1994) Laser cooling of trapped ions: the influence of micromotion. *Physical Review A* 49: 421–432.

Dehmelt H (1967 and 1969) In: Bates DR and Estermann I (eds) *Advances in Atomic and Molecular Physics*, vols. 3 and 5. New York: Academic Press.

Dehmelt HG (1983) Stored ion spectroscopy – three lectures. In: Arecchi FT, Strumia F and Walther H (eds) *Advances in Laser Spectroscopy*. New York: Plenum.

Diedrich F, Peik E, Chen JM, Quint W and Walther H (1987) Observation of a phase transition of stored laser-cooled ions. *Physical Review Letters* 59: 2931–2934.

Glauber R (1991) In: Arimondo E and Phillips W (eds) *Proceedings of the International School of Physics 'Enrico Fermi,'* vol. 118. Amsterdam: North Holland.

Hänsch TW and Schawlow AL (1975) Cooling of gases by laser radiation. *Optics Communications* 13: 68–69.

Javanainen J, Lindberg M and Stenholm S (1984) Laser cooling of trapped ions: dynamics of the final stages. *Journal of Optical Society of America B* 1: 111–115.

Leibfried D, Blatt R, Monroe C and Wineland D (2004) Quantum dynamics of single trapped ions. *Review of Modern Physics* 75: 281–324.

Peik E, Abel A, Becker Th, von Zanthier J and Walther H (1999) Sideband cooling of ions in radio-frequency traps. *Physical Review A* 60: 439–449.

Schieder R, Walther H and Wöste L (1972) Atomic beam detection by the light of a tunable dye laser. *Optics Communications* 5: 337–340.

Wineland D and Dehmelt H (1975) Proposed 10–14 laser fluorescence spectroscopy on Tl^+ mono-ion oscillator. *Bulletin of the American Physical Society* 20: 637.

Quantum Computing with Atoms

S F Huelga, University of Hertfordshire, Hatfield, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

It is a well-known fact that the speed of commercial microprocessors is doubling, roughly, every 18 months (Moore's law). This speedup is achieved mainly at the expense of reducing the size of the microchip. If this tendency is to continue, it seems unavoidable that quantum mechanical effects will eventually become important.

Remarkably, far from being a technological nuisance, the fact that information carriers are truly quantum mechanical systems offers an entirely new paradigm for computation. As opposed to classical bits, with logical values 0 and 1, quantum bits (qubits) can be prepared in arbitrary, normalized superpositions of the logic values. In addition, quantum states of multiqubit systems can be entangled, i.e., cannot be written as tensor products of states of the individual components. The theoretical description of entanglement requires a huge number of parameters which, in fact, grows exponentially with the number of particles that are involved. This exponential number of new degrees of freedom is responsible for the computational potential that quantum systems offer. Recently it has been demonstrated theoretically how we can harness this potential in the form of quantum algorithms, including Shor's factorization algorithm and Grover's protocol for data base search.

From a theoretical point of view, the implementation of quantum computation is greatly simplified by the fact that any unitary transformation involving an arbitrarily large number of qubits can be decomposed into two building blocks: single qubit operations and two-qubit controlled-NOT gates (CNOT-gates). We only need to identify two-level systems whose interaction can be mediated in a way that allows for conditional dynamics, that is, the second system undergoes certain operation (a NOT operation in our case), conditional on the state of the first qubit. However, it is easy to convince ourselves that from the experimental point of view, the challenge is going to be formidable. The following (DiVincenzo)-checklist summarizes the necessary requirements for the potential physical realization of a quantum computer:

- The system needs to provide a well-defined qubit, with two robust levels to represent the logical values 0 and 1. Moreover, the system should be scalable.
- Both the initial preparation and the final readout of the system has to be done with sufficient accuracy.
- The system has to allow the implementation of a universal set of gates (single-qubit rotations and CNOTs gates) with sufficient high fidelity. Implicit in this requirement is the ability to address individual qubits.

From the above list it is clear that the practical realization of a quantum computer relies on the ability to achieve a delicate equilibrium: the system needs to interact strongly with selected external agents, typically laser light, both during the gate operations and the preparation and readout steps, but should be shielded from any unwanted interaction if the desired dynamics is to be preserved. Perfect, selective, shielding from the environment is not possible in practice and unwanted interactions with the surroundings will unavoidably result in some form of decoherence. In this article we will review the fundamentals of the implementation of a universal set of quantum gates using (i) atomic system coupled to a resonant field sustained in a microwave cavity and (ii) trapped ions confined in an electromagnetic trap. Atomic and ionic systems provide a good means for storing quantum information in long-lived electronic states. In addition, both neutral atoms and ions can be selectively detected with high efficiency. While none of the presented schemes is expected to be scalable to a very large number of qubits, they constitute the first prototypes for quantum registers and are expected to play an important role in applications where only a moderate number of qubits are required. These applications range from the development of new frequency standards to quantum communication protocols. We will discuss in the following sections how a set of universal gates can build within these systems and will present the state of the art of the experiments performed to date.

Quantum Computation: Basic Definitions

As stated before, the basic unit of quantum information is a qubit, an arbitrary quantum mechanical two-level system. We will associate logical values 0 and 1 with quantum states $|0\rangle$ and $|1\rangle$, the eigenvectors of an observable such as the energy, and refer to such states as the computational basis. Any unitary operation on a qubit will be called a single qubit gate. Joint operations on more than one qubit will be denoted as multi-qubit gates. Using the fact that any two-level system is isomorphic to a spin-1/2 particle (e.g., an electron), we can always think of a qubit in terms of a certain pseudo-spin whose dynamics can be represented as rotation of the associated Bloch vector within the Bloch sphere.

For instance, as depicted in Figure 1, a qubit initially prepared in state $|1\rangle$, after experiencing a single qubit gate will be represented by certain Bloch vector $\vec{S}$, whose location on the Bloch sphere is a function of the gate parameters. Note that a classical system can only assume two positions (upwards and downwards), while a quantum system can explore the whole surface of the sphere.

It is also quite standard in quantum computation to use a diagramatic representation in terms of quantum circuits. Quantum circuits are built up of wires to denote the quantum bits and boxes to represent the gates, or quantum operations. Figure 2 shows two basics elements of a quantum circuit. The element on the left is the so-called Hadamard transformation, a particular example of single-qubit gate which transform each element of the computational basis as follows:

$$\begin{aligned} |0\rangle &\rightarrow \frac{1}{\sqrt{2}}\left(|0\rangle + |1\rangle\right) \\ |1\rangle &\rightarrow \frac{1}{\sqrt{2}}\left(|0\rangle - |1\rangle\right) \end{aligned} \qquad [1]$$



Figure 1 Geometrical representation of qubit systems using the Bloch sphere formalism. See the text for details.



Figure 2 Examples of single qubit gates (a) Hadamard transformation and two qubit gates (b) CNOT gate as customarily represented in quantum circuits diagrams.

Part (b) of Figure 2 depicts a CNOT-gate. This is now an operation involving two qubits. The first one, the control qubit, remains unaltered after the gate operation while the second qubit, referred to as the target, undergoes a spin flip (logical NOT operation) only when the control is in the state $|1\rangle$. Specifically, the action of a CNOT-gate is defined by the following transformation rule:

$$\begin{aligned} &\text{CNOT} \\ &|00\rangle \rightarrow |00\rangle \\ &|01\rangle \rightarrow |01\rangle \\ &|10\rangle \rightarrow |11\rangle \\ &|11\rangle \rightarrow |10\rangle \end{aligned} \qquad [2]$$

We have already mentioned that single qubit rotations and CNOT gates provide a universal set of gates. Our aim now is to show how such operations can be built when the so far generic qubit are realized in terms of real atomic systems. In the two experimental scenarios we are going to analyze here, the CNOT operation will be achieved by means of a different type of gate, a controlled-phase gate supplemented by two one-qubit Hadamard gates on the target qubit. The arrangement is showed in Figure 3. The controlled-phase gate is again a two-qubit operation defined by the following transformation rule:

$$\begin{aligned} &\text{CNOT} \\ &|00\rangle \rightarrow |00\rangle \\ &|01\rangle \rightarrow |01\rangle \\ &|10\rangle \rightarrow |10\rangle \\ &|11\rangle \rightarrow -|11\rangle, \end{aligned} \qquad [3]$$

i.e., a global phase equal to π is acquired if, and only if, the two basis states are in the logical state 1. It is easy to check that when the target bit is rotated by a Hadamard gate prior and subsequently to the action



Figure 3 Controlled-phase gate with both inputs, control, and target qubits, in state $|1\rangle$. The first Hadamard gate rotates the target to state $(|0\rangle - |1\rangle)/\sqrt{2}$. The action of the controlled-phase gate with $\phi = \pi$ yields the joint state $|1\rangle + (|0\rangle - |1\rangle)/\sqrt{2}$ and a final Hadamard rotation on the target leaves the system in the product state $|1\rangle|0\rangle$.

of the joint phase gate, the resulting state is tantamount to the action of a single CNOT gate. Therefore, to prove that our atomic system allows for the implementation of a universal set of gates, it suffices to show that both single qubit rotations and controlled phase gates can be implemented with sufficient accuracy.

The next section analyzes a typical cavity QED setup and presents the basic physical ideas to understand how single and two-qubit gates can be implemented within atomic systems interacting with radiation fields. Subsequent sections will rely heavily in this analysis.

Quantum Computing with Atoms I: Cavity QED

A simplified cavity-QED arrangement for performing both single- and two-qubit gate operations is depicted in Figure 4. This configuration is well-known to quantum opticians and it is often referred to as a Ramsey interferometric setup. For concreteness, we will focus here in the experimental set up currently in operation at the ENS in Paris. There, the atomic system is a highly excited Rydberg atom initially prepared in a long-lived circular state. The relevant atomic states are represented in Figure 5, with the qubit being stored in levels $|i\rangle$ and $|g\rangle$ which will play the role of the general basis states $|0\rangle$ and $|1\rangle$.



Figure 4 Cavity QED setup for single-qubit and two-qubit operations. Rotations of the atomic pseudo spin are performed via interation with classical radiation (Zone R), while the interaction with a resonant cavity field sustained in C allows the realization of a phase gate where the cavity photon acts as the control qubit.



Figure 5 Circular Rydberg levels involved in the ENS experimental setup. The qubit is stored in levels $|i\rangle$ (logical value 0) and $|g\rangle$ (logical value 1). The radiative lifetime of these levels lies in the millisecond range. Dissipation can then be neglected along the 20 cm path inside the apparatus.

Regions denoted by R represent the interaction of the atomic system with classical microwave radiation. As detailed below, this interaction will allow arbitrary rotations of the atomic pseudo spin. Region C represents the interaction of the atomic system with a single mode cavity field resonant the atomic transition $g - e$. The highest Q value reported to date is of the order of 10^8, which corresponds to a photon storage time of a few milliseconds. Therefore, the relaxation time of the cavity field is much longer than the atom-cavity interaction time, which defines the two-qubit gate operation time and is of the order of a few tens of μs. The cavity field can be prepared in either of the Fock states $|0\rangle_\gamma$ or $|1\rangle_\gamma$ and will play the role of the control qubit for the realization of a phase gate, as detailed below. This set up is completed with a detection scheme (SD in the figure) that allows the selective detection of the atomic electronic state.

We will start our discussion showing how to perform an arbitrary single-qubit gate by means of irradiating the atomic system with classical radiation. We will keep the analysis in very general terms with the aim of using it later in the description of the implementation of quantum logic with trapped ions.

Single-Qubit Rotations

Let our qubit be a two-level atomic system with frequency separation ω_0. We will show that an arbitrary rotation can be achieved by means of irradiating the system with classical light, e.g., microwave radiation or a laser field, with tunable frequency ω_L. The radiation field will be specified by two controllable parameters, its Rabi frequency Ω and its phase ϕ. The atom-field Hamiltonian can be written as

$$\begin{aligned} H = {} & \frac{\hbar\omega_0}{2}\left(|1\rangle\langle 1| - |0\rangle\langle 0|\right) \\ & + \hbar\left(g e^{i\omega_L t}|0\rangle\langle 1| + g^* e^{-i\omega_L t}|1\rangle\langle 0|\right) \end{aligned} \qquad [4]$$

where the first term corresponds to the atomic internal energy and the second describes the coupling with the external field. The coupling constant g can be written in terms of the field parameters as

$$g = \frac{i\Omega}{2} e^{-i\phi} \qquad [5]$$

In order to write down a time-independent Hamiltonian, we will move to an interaction picture with respect to $H_0 = \hbar\omega_L/2(|1\rangle\langle 1| - |0\rangle\langle 0|)$. In this frame,

$$H_{\text{int}} = \frac{\hbar\delta}{2}\Big(|1\rangle\langle 1| - |0\rangle\langle 0|\Big) + \hbar\Big(g|0\rangle\langle 1| + g^*|1\rangle\langle 0|\Big) \qquad [6]$$

The interaction Hamiltonian can be readily expressed in terms of the Pauli spin operators

$$\sigma_x = \begin{pmatrix} 0 & 1 \\ 1 & 0 \end{pmatrix} \quad \sigma_y = \begin{pmatrix} 0 & i \\ -i & 0 \end{pmatrix} \quad \sigma_z = \begin{pmatrix} 1 & 0 \\ 0 & -1 \end{pmatrix} \qquad [7]$$

as

$$H_{\text{int}} = \frac{\hbar\delta}{2}\sigma_z + \frac{\hbar\Omega}{2}(\sin\phi\,\sigma_x - \cos\phi\,\sigma_y) \qquad [8]$$

where $\delta = \omega_L - \omega_0$ denotes the detuning from the atomic transition and we have taken into account the explicit form of g as given by eqn [5]. We can now easily derive the time evolution operator by noting that H_{int} can be written in a compact form as $H_{\text{int}} = \vec{\sigma}\cdot\vec{n}$, where the vector $\vec{n}$ has cartesian coordinates $\vec{n} = (\Omega/2\sin\phi, -\Omega/2\cos\phi, \delta/2)$. Note that $|\vec{n}| \equiv \Omega_g = 1/2\sqrt{\Omega^2 + \delta^2}$. The time evolution operator can then be written as follows:

$$U = e^{-iH_{\text{int}}t} = \cos(|\vec{n}|t)11 - i\sin(|\vec{n}|t)\vec{\sigma}\cdot\vec{n}/|\vec{n}| \qquad [9]$$

In matrix form:

$$U = \begin{pmatrix} \cos\left(\frac{\Omega_g t}{2}\right) - i\frac{\delta}{\Omega_g}\sin\left(\frac{\Omega_g t}{2}\right) & \frac{\Omega}{\Omega_g}\sin\left(\frac{\Omega_g t}{2}\right)e^{-i\phi} \\ -\frac{\Omega}{\Omega_g}\sin\left(\frac{\Omega_g t}{2}\right)e^{i\phi} & \cos\left(\frac{\Omega_g t}{2}\right) + i\frac{\delta}{\Omega_g}\sin\left(\frac{\Omega_g t}{2}\right) \end{pmatrix} \qquad [10]$$

In the limit of large Rabi frequency, where $\Omega \gg \delta$, we can write the following approximate expressions for the time evolution of the computational basis states

$$\begin{aligned} U|0\rangle &= \cos\left(\frac{\Omega_g t}{2}\right)|0\rangle - \sin\left(\frac{\Omega_g t}{2}\right)e^{i\phi}|1\rangle \\ U|1\rangle &= \sin\left(\frac{\Omega_g t}{2}\right)e^{-i\phi}|0\rangle + \cos\left(\frac{\Omega_g t}{2}\right)|1\rangle \end{aligned} \qquad [11]$$

The transformed states by U are eigenstates of the spin operator along the direction $\vec{n}$ which is a function of the external field parameters. Therefore, by adjusting the Rabi frequency and the field's phase, it is possible to transform the basis states into spin eigenstates along any arbitrary direction, and to perform an arbitrary rotation of our qubit, we simply have to tailor appropriately the parameters of the driving field. For example, when the Rabi frequency and the interaction time are chosen such that $\Omega t/2 = \pi/4$, and the field's phase is taken equal to π, we get

$$\begin{aligned} U|0\rangle &= \frac{1}{2}\Big(|0\rangle + |1\rangle\Big) \\ U|1\rangle &= \frac{1}{2}\Big(|0\rangle - |1\rangle\Big) \end{aligned} \qquad [12]$$

This relationship defines the Hadamard transformation H introduced before. Alternatively, using quantum optics jargon, we have performed a $\pi/2$-pulse. Note that using the Bloch sphere representation, we can visualize the action of a Hadamard gate on the computational basis states as a rotations that brings them to the equatorial plane of the Bloch sphere, the transformed states by H now lying in opposite directions along the x-axis.

The next step is to show that our system also allows the implementation of conditional dynamics and, in particular, allows to build a controlled-phase gate.

Conditional Dynamics: Controlled-Phase Gate

The interaction of the atomic system with the cavity field sustained by the microwave cavity is described by the Jaynes–Cummings (JC) Hamiltonian. We can see this Hamilton operator as a generalization of the operator defined by eqn [4], where the radiation field is now quantized and the terms $e^{\pm i\omega_L t}$ are replaced by the operators a and $a^\dagger$ corresponding to the annihilation and creation of a cavity photon of frequency ω. The interaction with the quantized cavity field couples levels $|e\rangle$ and $|g\rangle$, while the far detuned level $|i\rangle$ will now play the role of a passive spectator. Remember that our atomic qubit is stored in levels $|i\rangle$ and $|g\rangle$. To avoid confusion with the notation, we will write the Hamilton operator in terms of the atomic states e and g. Explicitly:

$$\begin{aligned} H_{\text{JC}} = {} & \frac{\hbar\omega_0}{2}\Big(|e\rangle\langle e| - |g\rangle\langle g|\Big) + \hbar\omega a^\dagger a \\ & - i\frac{\hbar\Omega}{2}\Big(a|g\rangle\langle e| - a^\dagger|g\rangle\langle e|\Big) \end{aligned} \qquad [13]$$

where the coupling constant g has been taken to be $g = -i(\hbar\Omega/2)$, proportional to the Rabi frequency averaged over the mode structure, Ω. Using the same techniques employed in the previous section, we can derive the corresponding JC time evolution operator, which yields, for exact resonance, the following transformation rules:

$$\begin{aligned}
&|g\rangle|0\rangle_\gamma \rightarrow |g\rangle|0\rangle_\gamma \\
&|g\rangle|1\rangle_\gamma \rightarrow \cos\frac{\Omega t}{2}|g\rangle|1\rangle_\gamma - \sin\frac{\Omega t}{2}|e\rangle|0\rangle_\gamma \\
&|e\rangle|0\rangle_\gamma \rightarrow \cos\frac{\Omega t}{2}|e\rangle|0\rangle_\gamma + \sin\frac{\Omega t}{2}|g\rangle|1\rangle_\gamma
\end{aligned} \qquad [14]$$

where states $|\rangle_\gamma$ refer to the cavity field. Note that:

- The cavity field will play the role of our control qubit in the performance of a phase gate, the target qubit being the atomic system with computational states defined as before. The computational basis for the photonic qubit is provided by the Fock states $|0\rangle_\gamma$ and $|1\rangle_\gamma$.
- Strictly speaking, the time t entering in the equations above corresponds to an effective interaction time which accounts for the spatial variation of the coupling along the field mode.
- When the atom enters the cavity in state $|i\rangle$, it will acquire a global phase proportional to the ratio Ω^2/δ_i, where δ_i denotes the detuning between the atomic transition $e \leftrightarrow i$ and the mode frequency ω. In conditions of resonance, or quasi-resonance, this factor can be safely neglected, which justifies the term *passive spectator* used before.

We now have all the ingredients to understand how we can perform a controlled phase gate. Consider the situation where $\Omega t = 2\pi$, so the system experiences a full Rabi oscillation. According to the previous discussion, the basis states of two-qubit system atom-cavity field will transform as follows:

$$\begin{aligned}
&|i\rangle|0\rangle_\gamma \rightarrow |i\rangle|0\rangle_\gamma \\
&|i\rangle|1\rangle_\gamma \rightarrow |g\rangle|0\rangle_\gamma \\
&|g\rangle|0\rangle_\gamma \rightarrow |g\rangle|0\rangle_\gamma \\
&|g\rangle|1\rangle_\gamma \rightarrow -|g\rangle|1\rangle_\gamma
\end{aligned} \qquad [15]$$

That is, whenever the atomic system enters the cavity in state $|i\rangle$, it will be left unaffected, irrespective of the photon state. However, if the atom enters the cavity in state $|g\rangle$, the system will undergo a phase shift equal to π conditional to the photon number. And that is precisely the dynamics required for a controlled phase gate as defined earlier.

A detailed account of the experiments in cavity QED, showing coherent gate operation, can be found in Further Reading. These experiments prove the working principle of a universal set of quantum logic gates with neutral atoms and provide the basic elements for the development of a cavity QED quantum register in the near future.

Quantum Computing with Atoms II: Ion Traps

Charged atomic particles, ions, provided the first atomic system where conditional dynamics was demonstrated experimentally. The theoretical proposal in 1995, by Cirac and Zoller, for performing a two-qubit controlled NOT gate between trapped ions cooled to their motional ground state, was followed a few months later by a pioneering experiment at NIST, in Colorado. While the physics involved in the description of laser cooled and trapped ions is conceptually more involved than the dynamics ruled by a purely JC Hamiltonian, we can review the rudiments of the Cirac–Zoller scheme on the basis of the techniques developed in the previous sections. Nevertheless, as discussed briefly at the end of this section, we should point out that the exact procedure followed in the actual experiments departs from the analysis presented here.

Figure 6 depicts a linear ion trap where a string of ions is confined in an essentially 1-D structure. Quantum bits are stored in two long-lived hyperfine states which can be driven with laser light of controllable Rabi frequency Ω and phase ϕ. Ideally, the separation d between ions exceeds the wavelength of the external field so that ions can be addressed individually. Detection of the atomic state relies on the well mastered quantum jump technique which provides an efficiency close to 100%. From our previous discussion, it is clear that we already have all the ingredients for performing arbitrary single qubits gates, but we still need to provide a procedure to achieve two-qubit gate operations. As detailed in the next section, this will be achieved using the motional degrees of freedom of the ions as a bus for information transfer between an arbitrary pair of ions.



Figure 6 Schematic representation of a linear ion trap. Ions are individually addressed by external laser fields to perform single qubit operations, while two-qubit gates are mediated by the coupling to the motional degrees of freedom, depicted here as mechanical strings linking the chain of ions in the trap. The exact duration of a two-qubit gate operation and the characteristic decoherence time depend very much on the trap design, but orientative values are in the range of 50 μs and 100 − 1000 μs respectively.

The Cirac and Zoller Quantum Computer

At sufficiently low temperatures, the process of absorption and emission of photons produces a non-negligible recoil of the atomic system and the ion's motion can no longer be treated classically. In this regime, we can think of the string of ions as a system of coupled quantum harmonic oscillators whose normal mode configurations correspond to the collective motional states of the ions. The lowest energy solution corresponds to an oscillation where all ions are in phase (center of mass (CM) mode) and will be the one considered in our description. Figure 7 depicts the level scheme for ions initially cooled down to the motional ground state, illustrating both internal levels, $|e\rangle$ and $|g\rangle$, and motional (vibrational) states, denoted by $0, 1, \ldots$ Laser radiation can be tuned to be resonant with the $|g\rangle|0\rangle_{cm} \leftrightarrow |e\rangle|0\rangle_{cm}$ transition (carrier transition), but may also be tuned to drive transitions with different vibrational states (sideband transition), as represented by the external arrows in the figure. The realization of single qubit gates simply involves tuning the laser towards the carrier transition. The interaction is ruled by essentially the same Hamiltonian discussed above. Therefore, choosing appropriately the laser parameters, it is possible to induce an arbitrary rotation of the ion pseudo-spin.

To prove that the system allows the implementation of a universal set of gates, we will now show that it is possible to operate a controlled phase gate between two arbitrary ions. For that we need to couple internal and motional degrees of freedom which will be done by means of tuning the laser light to a sideband transition. The corresponding Hamiltonian will not be derived here in detail but it can be understood as describing a Jaynes–Cummings form of dynamics where the quantized electromagnetic field within a cavity is replaced by the quantum mechanical oscillator describing the vibrational states of the ion. Explicitly:

$$H = \frac{\eta\Omega}{2}\left(c|e\rangle\langle g| + c^{\dagger}|g\rangle\langle e|\right) \qquad [16]$$

where c and $c^{\dagger}$ denote the annihilation and creation operators of vibrational quanta and η is the so-called Lamb–Dicke parameter, a measure of the recoil energy. The gate operation involves the following sequence:

- Mapping the internal state of the control ion into the collective motional state of the chain,
- performing an operation on the target ion conditional to the excitation number of the vibrational state and
- reverse the initial operation restoring the vibrational state to its ground state.



Figure 7 Relevant internal and motional atomic levels for the realization of a controlled NOT gate between two arbitrary ions within a chain. See the text for details.

Imagine ion i, which will play the role of the control, and j, the target, initially prepared in arbitrary superpositions of the corresponding internal states, with the whole system cooled down to their motional ground state $|0\rangle_{cm}$. The joint state of the two particles can be written as a product state of the form:

$$\left(\alpha_i|g\rangle_i + \beta_i|e\rangle_i\right) \otimes |0\rangle_{cm} \otimes \left(\alpha_j|g\rangle_j + \beta_j|e\rangle_j\right) \qquad [17]$$

When ion i is irradiated by a laser tuned to the first motional side band $|g\rangle|1\rangle_{cm} \leftrightarrow |e\rangle|0\rangle_{cm}$, and the timing is such that the system undergoes a π-Rabi rotation, the internal state of the ion i is mapped onto the vibrational state (Note the transformation rules given in eqn [14]. As a result, the joint state of the system is still factorizable as

$$\left(|g\rangle_i \otimes \alpha_i|0\rangle_{cm} + \beta_i|1\rangle_{cm}\right) \otimes \left(\alpha_j|g\rangle_j + \beta_j|e\rangle_j\right) \qquad [18]$$

The second step of the protocol consists of applying an operation on ion j conditional on the vibrational state of the joint system. For that we apply a laser pulse resonant with the transition $|e\rangle_j|1\rangle_{cm} \leftrightarrow |a\rangle_j|0\rangle_{cm}$ with an auxiliary level $|a\rangle_j$ so that ion j undergoes a full Rabi oscillation. This results in acquiring a phase shift equal to π only if the system is state $|e\rangle_j|1\rangle_{cm}$ (see eqn [15]). This step entangles the internal and vibrational degrees of freedom of ion j, leading to a joint state of the form:

$$|g\rangle_i \otimes \Big(\alpha_i|0\rangle_{cm}(\alpha_j|g\rangle_j + \beta_j|e\rangle_j) + \beta_i|1\rangle_{cm}(\alpha_j|g\rangle_j - \beta_j|e\rangle_j)\Big) \qquad [19]$$

Applying a final laser pulse on ion i identical to the initial one, the state of the vibrational mode is transferred back to ion i and the atomic systems are left in the, generally, entangled state

$$\alpha_i\alpha_j|g\rangle_i|g\rangle_j + \alpha_i\beta_j|g\rangle_i|e\rangle_i + \beta_i\alpha_j|e\rangle_i|g\rangle_j - \beta_i\beta_j|e\rangle_i|e\rangle_j, \qquad [20]$$

which completes the controlled-phase gate operation.

A simplified version of this scheme shortly followed the theoretical proposal by Cirac and Zoller, proving the working principle of the ions trap quantum processor. Since then, both theoretical and experimental progress have allowed the development of schemes for implementing faster gates as well as protocols which do not require cooling to the motional ground state. We will briefly revise the current state of the art and future prospects of this technology in the last section of this article.

Frequency Estimations as a Quantum Computation: Building Frequency Standards with Entangled States

Recently, it has been proposed to make use of entangled states of trapped ions for performing high-resolution spectroscopy beyond the shot noise limit. This boundary is the ultimate limit achievable when performing a frequency measurement using uncorrelated particles. Consider n atomic two-level systems with frequency separation ω_0 initially prepared in their ground state $|0\rangle$. The aim is to lock a certain oscillator of frequency ω_L to the atomic frequency. To do that, the currently employed protocols use the so-called Ramsey method of separate oscillating fields, where each atomic system undergoes two $\pi/2$-pulses (or Hadamard transformations) separated by a free time evolution of duration t, much larger than the duration of the pulse. Looking at the Hamiltonian describing the interaction between the ion and the field, eqn [1], one can easily see that the free time evolution can be understood as a controlled phase gate in the following sense. If we set $g = 0$ in eqn [1] and for simplicity re-scale the ion internal energies so that $H = \hbar\delta|1\rangle\langle 1|$, the free evolution operator can be written as $U = -\hbar\delta|1\rangle\langle 1|$, so that the atomic basis states evolve as:

$$\begin{aligned} U|0\rangle &= |0\rangle \\ U|1\rangle &= e^{-i\delta t}|1\rangle \end{aligned} \qquad [21]$$

In other words, the ground state remains invariant, whereas the upper levels pick up a phase which is proportional to the detuning from the atomic transition. The state of each particle after the time evolution can then be written as

$$\frac{1}{\sqrt{2}}\Big(|0\rangle + e^{-i\delta t}|1\rangle\Big) \qquad [22]$$

After the second pulse, which again mixes populations of levels $|0\rangle$ and $|1\rangle$, one measures the population of, say, level $|1\rangle$. The signal is therefore a sinusoidal function of the form

$$P_1 = \frac{1}{2}\Big(1 + \cos(\delta t)\Big) \qquad [23]$$

which is symmetrical with respect to $\delta = 0$. This procedure is repeated a number of times to accumulate a sufficient data. Let us call T the total duration of the procedure, so that we accumulate $N = nT/t$ experimental data. Finally, whenever statistics in the populations are different from 50:50 at half maximum are detected, the oscillator frequency is steered to achieve exact resonance. The ultimate resolution $\Delta\omega_0$ achievable with this technique is limited simply by projection noise and can be written as

$$\Delta\omega_0 = \frac{1}{\sqrt{nTt}} \qquad [24]$$

After time T, the oscillator's frequency is steered towards the resonance and new sequence starts. We will now illustrate how the use of entanglement can yield an uncertainty in the measurement beyond the shot noise limit eqn [24]. Consider the quantum network depicted in Figure 8. The n particles are now initially prepared in a maximally entangled state. This is achieved by means of subjecting the first ion to



Figure 8 Quantum circuit representation for an experimental setup for a frequency estimation using maximally entangled states.

a Hadamard transformation followed by a cascade of CNOTs between the first ion, which acts as a control, and each of the remaining $(n-1)$ particles.

The resulting state is of the form

$$\frac{1}{\sqrt{2}}\Big(|0\ldots0\rangle + |1\ldots1\rangle\Big) \qquad [25]$$

The systems now evolve freely for a time t and, in light of the discussion above, we can represent this evolution in terms of a quantum gate which will leave state $|0\rangle$ invariant while introducing a phase factor proportional to the detuning if the system is in state $|1\rangle$. As a result, the joint state of the n particle after the free time evolution is given by

$$\frac{1}{\sqrt{2}}\Big(|0\ldots0\rangle + e^{-in\delta t}|1\ldots1\rangle\Big) \qquad [26]$$

with a phase factor amplified by a factor n as compared with the single particle state given by eqn [22]. The second part of the network disentangles the n particles, leaving the first ion in the state $(1/\sqrt{2})(|0\rangle + e^{-in\delta t}|1\rangle)$. If we now subject it to an additional Hadamard gate, the probability for the ion to be excited is

$$P_{1,ent} = \frac{1}{2}\Big(1 + \cos(n\delta t)\Big) \qquad [27]$$

which oscillates n times faster than the signal eqn [23]. The corresponding uncertainty for the estimation of the atomic frequency is now

$$\Delta\omega_0, ent = \frac{1}{n\sqrt{Tt}} \qquad [28]$$

This corresponds to an increase in the resolution of $\sqrt{n}$ beyond the shot noise bound. In practice, the achievable resolution using entangles states is limited by the decoherence time of the system t_{dec}, which sets the condition $T < t_{\text{dec}}/2$ for the procedure to be valid. Remarkably, entanglement is still advantageous in a situation where T is chosen such that it exceeds the decoherence time. However, maximally entangled states should now be replaced by certain partially entangled ones to overcome the precision achievable with uncorrelated particles.

The application of entangled states in precision spectroscopy is a nice illustration of the potential of the ideas developed in quantum information beyond the ultimate task of building a large-scale quantum computer. The first experimental results showing the enhanced performance of entangled states have been reported by the NIST group in Boulder.

Conclusion and Perspectives

We have revised the fundamental concepts for the practical realization of quantum computation using atomic systems. We have showed how single qubit and two-qubit controlled-phase gates can be implemented using atoms interacting with the cavity field sustained by a microwave resonator and ion traps. We have illustrated how a very simple quantum computation can be used for the development of more precise frequency standards, emphasizing the potential of the ideas developed in quantum information beyond the implementation of large scale quantum computation.

Cavity QED technology has so far allowed the generation of entangled states of two and three particles and has demonstrated coherent gate operation. Ion trap technology has pushed controllable multi-particle entanglement to four particles and has showed the possibility of implementing forms of error correction. The combination of these two technologies offers interesting prospects for the near future. Surrounding traps by optical cavities and networking these devices via optical fibers is expected to allow the construction of the first prototypes for a quantum communication network.

See also

Quantum Optics: Entanglement and Quantum Information.

Further Reading

Cirac JI and Zoller P (1995) Quantum computations with cold trapped ions. *Physical Review Letters* 74: 4091.

Deutsch D, Barenco A and Ekert AK (1995) Universality in quantum computation. *Proc. Roy. Soc. London A MAT* 449: 669–677.

Grover L (1999) Quantum mechanics helps in searching for a needle in a haystack. *Physical Review Letters* 79: 325–328.

Huelga SF, *et al.* (1997) Improvement of frequency standards with quantum entanglement. *Physical Review Letters* 79: 3865.

Jaynes ET and Cummings FW (1963) Comparison of quantum and semiclassical radiation theories with application to the beam maser. *Proc. IEEE* 51: 89.

Kielpinski D, Meyer V, Rowe MA, *et al.* (2001) A decoherence-free quantum memory using trapped ions. *Science* 291: 1013–1015.

Monroe C, Meekhof DM, King BE, *et al.* (1995) Demonstration of a fundamental quantum logic gate. *Physical Review Letters* 75: 4714–4717.

Raimond JM, Brune M and Haroche S (2001) *Colloquium*: manipulating quantum entanglement with atoms and photons in a cavity. *Review Modern Physics* 73: 565 and references therein.

Sackett CA, Kielpinski D, King BE, *et al.* (2000) Experimental entanglement of four particles. *Nature* 404: 256–259.

Shor P (1994) *Proc. of the 35th Annual Symposium on the Foundations of Computer Science, IEEE Computer Society, Los Alamitos*. Santa Fe, NM: IEEE Computer Society Press.

Sorensen A and Molmer K (1999) Quantum computation with ions in thermal motion. *Physical Review Letters* 82: 1971.

Wineland DJ, Monroe C, Itano WM, Leibfried D, King BE and Meekhof DM (1998) Experimental issues in coherent quantum-state manipulation of trapped atomic ions. *J. Res. Natl. Inst. Stand. Tech.* 103: 259 and references therein.

Squeezed Phonons in Solids

A V Bragas, Universidad de Buenos Aires, Buenos Aires, Argentina

R Merlin, University of Michigan, Ann Arbor, MI, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The reduction of noise is crucial for measurements requiring high accuracy and, often, for the observation of new phenomena. Among noise sources, noise inherently related to the quantum nature of an object persists even after all the classical sources of noise are removed. Quantum noise is a fundamental limitation, loosely related to the Heisenberg uncertainty principle, which imposes a lower limit to the fluctuations of any pair of conjugated variables, like position and momentum. For conjugated variables A_1 and A_2 we have

$$\Delta A_1 \Delta A_2 \geq \frac{\hbar}{2} \qquad [1]$$

where

$$\Delta A_i = \sqrt{\langle A_i^2 \rangle - \langle A_i \rangle^2} \qquad i = 1, 2 \qquad [2]$$

While quantum mechanics does not forbid reducing the noise in one of the conjugated observables down to zero, the noise for the other variable will increase according to eqn [1]. Squeezing refers to the reduction of noise of a quantum variable at the expenses of its conjugated variable. The term originates from quantum optics. Nonlinear interactions of the electromagnetic field with passive and active atomic media have been successfully used to generate squeezed photons, opening new possibilities for essentially noiseless optical communications and precision measurements. The electromagnetic field is not the only quantum object that can be squeezed. By performing appropriate manipulations of the internal quantum state of a system, it is, in principle, possible to squeeze an arbitrary variable. In the past few years, vibrational states have also been experimentally squeezed in molecules and solids, by exciting the system with ultrafast optical pulses. The concept of squeezing can also be extended to an ensemble of classical objects for which the fluctuations are of thermal origin.

Squeezing applies in particular to situations where the relevant variables are the position Q and momentum P of a harmonic oscillator. Consider the Hamiltonian of a particle of mass m in a harmonic potential of frequency Ω

$$H_0 = \frac{P^2}{2m} + \frac{m}{2}\Omega^2 Q^2 \qquad [3]$$

The ground state wavefunction is

$$\varphi_0 = \frac{1}{\left[2\langle Q_0^2 \rangle \pi\right]^{1/4}} \exp\left(-\frac{Q^2}{4\langle Q_0^2 \rangle}\right) \qquad [4]$$

where $\langle Q_0^2 \rangle = \hbar/2m\Omega$. The stationary probability, $|\varphi_0|^2$, is represented in Figure 1a. This state is also a minimal uncertainty state in that $\Delta Q \Delta P \equiv \hbar/2$. $\langle Q_0^2 \rangle$ gives a measure of the quantum noise and it is known as the vacuum noise level.

Let us now discuss the behavior of a harmonic oscillator that interacts with an external source. There are two types of quantum states for which the Gaussian shape of the wavefunction is preserved after interacting with an external driving force. These are the coherent state and the squeezed state. If the interaction places the system in a state of the same form as eqn [4] but displaced with respect to the center, the wavepacket will oscillate periodically, with period $\tau = 2\pi/\Omega$, without changing its shape as shown in Figure 1b. This quantum state is known as the coherent state. It has the same uncertainty as the ground state but the expectation value $\langle Q(t) \rangle$ depends on the time following the classical trajectory in the harmonic potential. If, instead, we introduce a sudden change in the spring constant at $t = 0$, the wavepacket will begin to 'breathe' for $t > 0$, so that its width will vary periodically with a period given by $\pi/2$. This is the squeezed state. Here the noise of one of the variables is periodically reduced below the level of the vacuum noise (Figure 1c). A state that is a combination of a coherent and a squeezed state is shown in Figure 1d. The wavepacket follows the classical trajectory and breathes at the same time.

The results in Figure 1 apply only to harmonic oscillators. While the concept of squeezing can be extended to anharmonic potentials, there are additional features to consider such as, for example, wavepacket revivals.

Dynamics of a Parametrically Excited Crystal

Harmonic oscillators describe a wide range of physical systems. In particular, the dynamics of a crystal lattice can be described in terms of a set of independent harmonic oscillators, the quantum nature of which is described in terms of phonons. In this section we discuss interactions of a harmonic oscillator with external sources that produce squeezing.

The normal modes in a crystal obey equations of the form:

$$\ddot{Q}_q + \Omega_q^2 Q_q = 0 \qquad [5]$$

where Q_q and Ω_q are the phonon coordinate and frequency, and q is the wavevector.

As briefly mentioned in the previous section, a sudden change in the spring constant produces a squeeze state. To do this, we need what is known as time-dependent parametric coupling. As in the experiments on phonon squeezing, using ultrashort optical pulses, we consider an impulsive driving force proportional to Q. The relevant equation is:

$$\ddot{Q}_q + \Omega_q^2 Q_q = \lambda_q Q_q \delta(t) \qquad [6]$$

where $\delta(t)$ is the Dirac delta function, and λ accounts for the strength of the external impulsive force. This impulsive excitation induces a sudden change in momentum, proportional to the normal coordinate Q at $t = 0$, as can be shown by integrating eqn [6]. Explicitly, $\Delta\dot{Q}_q = \Delta P_q = \lambda_q Q_q(0)$. $\Delta P_q = P_q(0^+) - P_q(0^-)$, where $0^-(0^+)$ is the time immediately before (after) the excitation. This result is illustrated in Figure 2. The main effect of the interaction is to change the width of the Gaussian packet or variance of the distribution. This leads to a time-dependence of the noise defined in eqn [2], $\Delta Q^2(t) = \langle Q^2(t)\rangle$ reflecting the 'breathing' of the wavepacket. Since P_q is the conjugated variable of Q_q, $\langle P_q^2(t)\rangle$ shows the same time-dependent behavior as $\langle Q_q^2(t)\rangle$ but in quadrature with it, so as to fulfill eqn [2] at all time. Assuming an oscillator initially in its ground state, the solution of eqn [6] is

$$\langle Q_q^2(t)\rangle = \frac{\hbar}{2m\Omega_q}\left[1 + \left(\frac{\lambda_q}{\Omega_q}\right)\sin(2\Omega_q t) + \left(\frac{\lambda_q}{\Omega_q}\right)^2 \sin^2(\Omega_q t)\right] \qquad [7]$$

It is then clear that the fluctuations of Q_q periodically fall below the vacuum quantum noise level, determined by $\langle Q_0^2\rangle$, and that the oscillations have a frequency that is twice the frequency of the oscillator.

The considerations above apply to a quantum harmonic oscillator at temperature $T = 0$. In the classical case, we need to consider an ensemble of oscillators in equilibrium with a thermal bath at temperature T. It can be shown that eqn [7] also applies to the classical case, provided $\hbar/2m\Omega$ is replaced by $k_B T/\Omega^2 m$, where k_B is the Boltzman constant. In classical squeezing, the external perturbation is applied simultaneously to the ensemble, leading to a sudden change of the momentum of all the oscillators. The jump in momentum is proportional to the position of the particle at $t = 0$. After the interaction, the noise of the ensemble will fall periodically below the thermal noise at temperature T given by $k_B T/\Omega^2 m$. A pictorial representation of classical squeezing is shown in Figure 3.

To describe a more realistic situation, it is necessary to take into account effects due to dissipation. Theoretically, this is usually accomplished by considering the coupling with a continuum of external modes simulating a thermal bath. The solution to this type of problem is nontrivial even for the simplest case of linear coupling to the bath.

The impulsive excitation of eqn [6] is a parametric excitation containing all the frequencies. A more common way to parametrically excite an oscillator is to use a monochromatic source, as described by the equation

$$\ddot{Q} + [\Omega^2 + \varepsilon\cos(\Omega_0 t)]Q = 0 \qquad [8]$$

where the parametric excitation is characterized by the amplitude ε and the modulation frequency Ω_0. Notice that the excitation induces a time-dependent frequency $\omega^2(t) = \Omega^2 + \varepsilon\cos(\Omega_0 t)$, and, hence, it



Figure 1 (a) Ground state probability density $|\varphi_0|^2$ for a quantum harmonic oscillator of frequency Ω. Q is the position, P is the momentum and σ is the standard deviation of the Gaussian wavepacket, or the square root of $\langle Q_0^2 \rangle$. The phase-space diagram on the left shows the uncertainty region for the ground state. (b) Coherent state. The uncertainty $\langle Q^2 \rangle$ does not change in time and it is always equal to $\langle Q_0^2 \rangle$, but the wavepacket oscillates with the period τ of the harmonic oscillator. The phase diagram shows the evolution of the uncertainty region, starting from the ground state (dashed line). A sudden constant change in momentum at time $t = 0$ produces a change in the equilibrium position and the wavepacket begins to oscillate. (c) Squeezed state. The wavepacket evolves by changing its width periodically with period $\tau/2$. The uncertainty, $\langle Q^2(t) \rangle$, takes values smaller than $\langle Q_0^2 \rangle$ for a fraction of the cycle. Due to the sudden change on momentum, proportional to Q, at $t = 0$, the distribution becomes ellipsoidal and rotates with frequency 2Ω. (d) Coherent-squeezed state. It is a combination of both (b) and (c). The wavepacket oscillates and breathes at the same time.



Figure 1 *Continued.*



Figure 2 Schematic representation of the effect of an impulsive excitation on the ground state of the harmonic oscillator. At $t = 0$, the pulse induces a change in momentum P, proportional to the position Q. As a result, the wavepacket width in momentum space changes suddenly and starts to oscillate.

shows squeezing effects. The complete set of solutions with and without dissipation has been obtained by Zerbe and Hanggi for the quantum and classical cases.

Physical Interactions Giving Phonon Squeezing

The considerations above are rather general and specific to any physical system that behaves like a set of harmonic oscillators. Here, we consider proposals for phonon squeezing.

Equations [6] and [8] show that we need a driving force proportional to the phonon coordinate Q to achieve squeezing. One way to do this is for the external interaction to produce time-dependent correlations between two modes. Prior to the experimental achievement of phonon squeezing in 1997, using stimulated second-order Raman scattering, models based on (a) three-phonon parametric amplification and (b) polaritons had been proposed.



Figure 3 (a) Classical representation of a coherent phonon. An impulsive horizontal force acts on all members of a thermal distribution of pendula, displacing the group in phase space along the momentum axis. The ensemble precesses with an average position $\langle x \rangle \sim \sin(\Omega t)$. (b) Classical representation of a squeezed phonon. An impulsive vertical force produces an impulse proportional to the pendulum's displacement from equilibrium. Those pendula farthest from equilibrium receive the largest kick. The phase space distribution becomes elliptical and precesses with an ensemble averaged variance $\langle x^2 \rangle \sim \sin(2\Omega t)$.

These proposals have not yet been implemented experimentally.

The scheme proposed in (a) is based on three-phonon parametric amplification, similar to photon squeezed states that are generated by optical parametric amplification. Specifically, the proposal relies on a two-step process. First the generation by external excitation with two lasers of a ‘pump’ longitudinal optical phonon (LO) and, second, the decay of the optical phonon into two longitudinal acoustic phonons (LA), which will be squeezed. This is the kind of parametric oscillator described by eqn [8], for which the parametric control is driven by the coherent optical phonon field.

In case (b) it has been shown that mixed polarization modes known as phonon polaritons are intrinsically squeezed. These hybrid objects, sometimes referred to as dressed photons, are a mixture between phonons and photons that cannot be separated once they are formed.

Squeezing of vibrational states in molecules was confirmed experimentally earlier than in solids. Here, a molecule initially in the ground electronic and vibrational state is excited by an ultrafast optical pulse tuned with an electronic resonance. After the pulse arrives, the molecule is placed in a excited electronic state and the nuclei in a new (excited) potential with a new set of discrete vibrational modes. In Figure 4 we show, as an example of a diatomic molecule, the potential of a sodium dimer. For the sake of simplicity, we consider a single vibrational mode in the excited state and we disregard effects due to anharmonicity. If the optical pulsewidth is much shorter than any vibrational frequency, and the frequencies are different in the ground and excited state, the sudden change in frequency produces a vibrational squeezed state. On the other hand, even if the frequencies in the ground and excited state are equal, but the laser pulse is finite or chirped (frequency sweep on time), the final vibrational state may be squeezed. The formal demonstration of this is not trivial. Analytic solutions for the vibrational wavefunction for an arbitrary external field excitation are known for a very limited number of cases.

Squeezing of a wavepacket in an excited sodium diatomic molecule was achieved by Dunn and coworkers, measuring the time and frequency-resolved spectrum of the spontaneous emission. In this experiment, the molecule can return at any time to its electronic ground state by emitting light, the wavelength of which depends on the internuclear separation at that time. As shown in Figure 4, this is because the equilibrium position for the potential surfaces in the ground and excited states are different. Thus, the time-dependent average wavelength of the emitted light oscillates as the atom vibrates, giving a signature of the dynamics of the wavepacket. Dunn observed oscillations in the signal strength that are consistent with a wavepacket expanding and contracting.



Figure 4 Potential curves for a Na_2 molecule, showing the ground and first excited states. The dashed line represents the ground state wave function. The equilibrium position of both potentials are shifted and the vibrational frequencies are different.

Experimental Generation and Detection of Squeezed Phonons by Second Order Raman Scattering

The first experimental demonstration of phonon squeezing was performed in 1997 by exciting a $KTaO_3$ (potassium tantalate) crystal with an ultrafast pulsed laser and coupling the light to the phonons through second order Raman Scattering. The squeezed phonon field produced by an intense optical pulse, referred to as the ‘pump’, is detected by a second low intensity pulse, known as the ‘probe’. Phonon squeezing was also reported for $SrTiO_3$ (strontium titanate). In addition, correlations between pairs of phonons of different frequencies was reported in a closely related experiment on $KTaO_3$.

The simplest Hamiltonian describing this experiment contains the harmonic contribution from the lattice and a Raman-type interaction term. Raman scattering (RS) refers to light-crystal interaction in which the initial quantum of radiation energy, $\hbar\omega_i$, is divided into a vibrational excitation of the crystal with energy $\hbar\Omega$ and a scattered photon with energy $\hbar\omega_f$. Here, the total energy and momentum are conserved. The interaction energy is proportional to the second-order electronic susceptibility which can be expanded in terms of the atomic displacement Q. The nth term of the Taylor expansion is associated with RS of order n. Two phonons participate in the second order RS process. Although the absence of first-order RS is not required for achieving squeezing, $KTaO_3$ and SrTiO3 (above ~100 K) show no first-order Raman active modes. As a result, the leading contribution is

$$H_{\text{int}} = -\frac{1}{4}|E(t)|^2 \sum_q \chi_2(q) \qquad [9]$$

with $\chi_2(q) = (\partial^2\chi/\partial Q_q^2)Q_q^2$, where $\partial^2\chi/\partial Q_q^2$ is the second order Raman tensor, $E(t)$ is the magnitude of the light electric field, and χ is the linear electronic susceptibility. The Hamiltonian eqn [9], reflecting contributions from pairs of modes at $\pm q$, represents a change in the phonon frequency $\Delta\Omega_q(t) \approx -(1/4\Omega_q)(\partial^2\chi/\partial Q_0^2)|E(t)|^2$ that results in a time-dependent variance $\langle Q_q^2(t)\rangle$ and thus, squeezing. We note that, while individual scattering events produce a two-phonon state, the coherent ensemble of these correlated two-phonon states modulates the variance of Q. Notice that second-order RS excites phonons throughout the whole Brillouin zone instead of just the zone center at $q \approx 0$, as in first-order RS. This means that the light couples to a continuum of modes. The strength of the scattering at any particular frequency is proportional to the number of modes, i.e., the density of states, which is inversely proportional to the gradient $\nabla_q\Omega_q$ and thus, exhibits singularities at points where the gradient vanishes. These so-called critical points lead to associated singularities in the density of states referred to as van Hove singularities. $KTaO_3$ and $SrTiO_3$ show a sharp peak in the density of states at frequencies associated with certain van Hove singularities and, therefore, the continuum of modes becomes quasimonochromatic.

In the experiments, the period of the relevant phonons, $2\pi/\Omega_q$, is large compared with both the pulsewidth and the time the pulse takes for traversing the sample. Then, the time-dependent electric field can be approximated by the delta function $|E(t)|^2 \cong (4\pi I_0/nc)\delta(t)$, where I_0 is the pulse energy density, n the refractive index and c the speed of the light. Within this approximation, the dynamics of the system at $T = 0$ is described by eqn [6]. To lowest order in I_0, we have

$$\Delta Q_q = \langle Q_q^2(t)\rangle^{\frac{1}{2}} \approx \langle Q_q^2(0)\rangle^{\frac{1}{2}}\left[1 + \left(\frac{\lambda}{\Omega_q}\right)\sin(2\Omega_q t)\right] \qquad [10]$$

with $\lambda = 2\pi(I_0/nc)(\partial^2\chi/\partial Q_q^2)$.

As before, the variance drops below the quantum limit $\langle Q_q^2(0)\rangle$ for some fraction of the cycle. This zero-temperature description is only accurate for temperatures such that k_BT is very small compared with the phonon energies. For $T \neq 0$, the conditions overcoming the thermal contribution and produce quantum squeezing at low intensities are

$$n_q \ll 1 \quad \text{and} \quad \left(\frac{\lambda}{\Omega_q}\right) > 2n_q \qquad [11]$$

where $n_q = 1/[\exp(\hbar\Omega_q/k_BT) - 1]$ is the Bose factor.

Next we discuss the detection of the squeezed field. As mentioned earlier, the pump pulse creates the squeezed phonon state and the probe is affected by the changes in the material produced by the pump. The scattering of the probe by the squeezed phonon is also described by the nonlinear polarization of the material $P^{NL} = (2V)^{-1}E'(t)\sum_q\chi_2(q)$, where $E'(t)$ is the probe field, and V is the scattering volume. If the probe pulse is Gaussian-shaped of width τ_0 and centered at $\omega = \omega_0$, the total normalized change in the probe transmission ΔT is

$$\frac{\Delta T}{T}(\omega) \approx -\frac{l\pi\tau_0^2\omega(\omega-\omega_0)}{ncV}\sum_q \frac{\partial^2\chi}{\partial Q_q^2}|E'(t)|^2 \times \lambda\langle Q_q^2(0)\rangle\cos(2\Omega_q\Delta t)\exp(-2\Omega_q^2\tau_0^2) \qquad [12]$$

where l is the length of the sample. Equation [12] can be obtained from well-known results in coherent phonon detection. Comparing eqn [12] with eqn [10] it follows that the change in probe transmission is proportional to the derivative of the total time-dependent variance $\langle Q^2(t)\rangle = \sum_q\langle Q_q^2(t)\rangle$. Accordingly, the integral of $\Delta T/T$ probes $\langle Q^2(t)\rangle$.

$KTaO_3$

The perovskite $KTaO_3$ was the first material for which phonon squeezing was achieved. This compound has no first-order Raman active modes. The time-domain data in Figure 5a shows behavior



Figure 5 (a) The normalized transmitted probe intensity as a function of the probe delay for $KTaO_3$ at $T = 10$ K. Reprinted with permission from Garrett GA, Rojo AG, Sood AK, Whitaker JF and Merlin R (1997) Vacuum squeezing of solids: Macroscopic quantum states driven by light pulses. *Science*, 275(5306): 1638–1640. Copyright 1997 American Association for Advancement of Science. (b) Fourier transform of the time domain data in (a). The narrow peak appears very close to twice the frequency of the TA (transverse acoustic) mode at the X point of the Brillouin zone. (c) Second order Raman cross section.

consistent with eqn [12]. The Fourier transform $\mathcal{F}_{\mathrm{FT}}$ in Figure 5b, is dominated by a narrow peak, strongly dependent on temperature, that appears very close to twice the frequency of the TA (transverse acoustic) mode at the X point of the Brillouin zone. The comparison with the spontaneous Raman scattering data, Figure 5c, indicates that the $\mathcal{F}_{\mathrm{FT}}$ peak is due to the 2TA overtone. The squeezing factor defined as $S = 1 - [\langle Q^2(t)\rangle / \langle Q^2(0)\rangle]^{1/2}$, is depicted in Figure 6. Notice that, whereas the squeezing factor in a quantum optics experiment can reach values as large as 70%, phonons in a solid can be squeezed by no more than, say, 0.01%. This is because larger values may lead to collapse of the solid since, according to the Lindemann criterion, solids melt when the root-mean-square displacement of an atom is a fraction of 0.2–0.25 of the lattice parameter.



Figure 6 Experimental time dependence of the squeezing factor $S = 1 - [\langle Q^2(t)\rangle / \langle Q^2(0)\rangle]^{1/2}$. I_0 is the pulse intensity. Inset: the amplitude of S as a function of the integrated intensity of the pulse, showing the linear behavior predicted by eqn [12]. Reprinted with permission from Garrett GA, Rojo AG, Sood AK, Whitaker JF and Merlin R (1997) Vacuum squeezing of solids: Macroscopic quantum states driven by light pulses. *Science* 275(5306): 1638–1640. Copyright 1997 American Association for the Advancement of Science.



Figure 7 Fourier transform of the time domain data (inset) of the probe differential transmitivity of $KTaO_3$ at room temperature. The excited phonon combinations are indicated in the figure. Reproduced with permission from Bartels A, Dekorsy T and Kurz H (2000) Impulsive excitation of phonon-pair combination states by second-order Raman scattering. *Physical Review Letters* 84(13): 2981–2984. Copyright 2000 by the American Physical Society.

In $KTaO_3$ it was also possible to induce a time-dependent covariance between two different independent modes by using second order RS to couple the two oscillators. In Figure 7 we show



Figure 8 (a) The normalized transmitted probe intensity as a function of the probe delay for $SrTiO_3$ at $T = 7$ K. (b) Fourier transform of the time domain data. The 1.3 THz peak is the soft A_{1g}-phonon (coherent), and the 6.9 THz is the 2 TA overtone (squeezed). The second order feature is dominated by a sharp peak very close to twice the frequency of TA modes at X and M points of the Brillouin zone.

data revealing correlations between transverse optical (TO) and transverse acoustical (TA) modes.

$SrTiO_3$

This material undergoes a structural phase transition, called antiferro-distortive, at $T_C \approx 110$ K. Second-order RS is allowed at all temperatures, but first-order RS is only allowed for temperatures below T_C. Figure 8 shows data at low temperatures, revealing both first and second order features. From the comparison with spontaneous RS, the peak appearing in the $\mathcal{F}_{FT}$ at ~1.3 THz is due to first-order RS, while the peak at ~6.9 THz is due to second order RS (2TA overtone). The quantum state created by the ultrafast pulse is then a mixture of a coherent and a squeezed state. Hence the phonon wavefunction will evolve qualitatively as in the picture shown in Figure 1d.

List of Units and Nomenclature

Gaussian units

I_0	energy density [$\mathrm{Jcm^{-2}}$]
E	electric field [statvolt $\mathrm{cm^{-1}}$]

See also

Scattering: Stimulated Scattering; Raman Scattering. **Semiconductor Physics:** Light Scattering. **Ultrafast Laser Techniques:** Generation of Femtosecond Pulses.

Further Reading

Dunn TJ, Sweetser JN, Walmsley IA and Radzewicz C (1995) Experimental determination of the dynamics of a molecular nuclear wave-packet via the spectra of spontaneous emission. *Physical Review Letters* 74(6): 884–887.

Garraway BM and Suominen KA (1995) Wave-packet dynamics: new physics and chemistry in femto-time. *Reports on Progress in Physics* 58(4): 365–419.

Garrett GA, Rojo AG, Sood AK, Whitaker JF and Merlin R (1997) Vacuum squeezing of solids: Macroscopic quantum states driven by light pulses. *Science* 275(5306): 1638–1640.

Hayes W and Loudon R (1978) *Scattering of Light by Crystals*. New York: John Wiley & Sons, Inc.

Lindemann F (1910) Über die Berechnung molekularer Eigenfrequenzen. *Zeitschrift Für Physik* 11: 609–612.

Walls DF and Milburn GJ (1994) Generation and Applications of Squeezed Light. *Quantum Optics*, pp. 137–174. Berlin Heidelberg: Springer Verlag.

Zerbe C and Hanggi P (1995) Brownian parametric quantum oscillator with dissipation. *Physical Review E* 52(2): 1533–1543.

RELATIVISTIC NONLINEAR OPTICS

D P Umstadter, University of Michigan, Ann Arbor, MI, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Immediately after the invention of the laser in 1960, light could be focused to sufficient intensity to cause nonlinear optical effects in atomic media. In conventional nonlinear optics, where the electric field of a light wave E is much smaller than an atomic field, $E_{\mathrm{at}} = 3 \times 10^9$ V/cm, various nonlinear phenomena, such as self-focusing, harmonic generation, and Raman scattering, arise due to the anharmonic motion of electrons in the combined fields of atom and laser. Approximate analytical solutions can be obtained by means of perturbation expansion methods, using E/E_{at} as the expansion parameter. At higher light fields, when E approaches E_{at}, this method breaks down and the medium becomes photo-ionized, creating a plasma, as illustrated by Figure 1. Further increases in light intensity enabled nonlinear optical effects of even these free plasma electrons (see Figure 2). The nonlinearity arises, in this case, because the electrons oscillate at relativistic velocities in laser fields that exceed 10^{11} V/cm, resulting in relativistic mass changes exceeding the electron rest mass and the light's magnetic field becomes important. The work done by the electromagnetic field (E) on an electron ($eE\lambda$) over the distance of a laser wavelength (λ), then approaches the electron rest mass energy ($m_e c^2$), where e is the elementary charge of an electron, m_e is the electron rest mass, and c is the speed of light. Effects analogous to those studied with conventional nonlinear optics – self-focusing, self-modulation, harmonic generation, and so on – are all found, but based on this entirely different physical mechanism. Thus, a new field of nonlinear optics, that of relativistic electrons, has been launched, as illustrated by Figure 1.

One outcome of accessing this new optical regime is the generation of frequency-shifted light in a spectral region where there are no other compact sources. Another is the acceleration of other types of particles, such as positrons, ions, and neutrons. These novel radiation sources have properties (femtosecond duration, micron source size, MeV energy) that make them suitable for numerous applications in imaging and spectroscopy in basic research, as well as medical diagnostics, cancer therapy, energy production, and space propulsion. Rapid advancement is underway and new research tools, subfields, and commercial products are on the horizon, e.g., compact and ultrashort pulse duration laser-based electron accelerators and X-ray sources.

Another physical regime will be encountered at even higher intensities ($I\lambda^2 \simeq 10^{24}$ W/cm^2), when even protons will quiver relativistically, i.e., the work done on a proton over the distance of a laser wavelength approaches its rest mass energy. This might be called the nuclear regime of laser–plasma interactions, because of the fusion and fission reactions and the generation of pions, muons, and neutrinos that should occur as nuclei collide in such energetic plasmas.

The recent dramatic increase in light intensity was partly made possible by the development, in the last decade, of compact lasers that have the ability to amplify shorter light pulses. For instance, solid-state lasers use the technique of chirped-pulse amplification to generate femtosecond duration pulses. To accomplish this, an ultrashort, low-energy laser pulse is first stretched in time before it is amplified and then recompressed. Gas or dye lasers, using solid-state switches, have produced picosecond duration pulses. Present day advanced laser systems now have multiterawatt peak powers and, when focused to micron spotsizes with adaptive optics, can produce electromagnetic intensities $I\lambda^2 \simeq 10^{21}$ W/cm^2, as illustrated by Figure 3. An example of a modern ultra-high-power (0.9 PW) solid-state (Ti:Sapphire) laser


Intensity (W/cm^3)
Energy (MeV)
10^{25}
10^{20}
10^{15}
10^{10}
10^{5}
10^{3}
10^{0}
10^{-3}
10^{-6}
10^{-9}
Uranium atom fully stripped
Relativistic protons
Pion production
Fusion
Thermal pressure of sun's core
Electron-positron plasma
Relativistic electrons
Chirped-pulse amplification
Coulomb binding energy
Photoionization
Vaporization of molecules
First lasers
room temperature

Figure 1 The various regimes of laser–matter interactions, represented by the ideal laser pulse. As the intensity of laser light increases, so does the energy of electrons accelerated in the light field and the regime of conventional nonlinear optics with electrons bound to atoms is replaced by the regime of relativistic nonlinear optics with free electrons in relativistic plasmas. At the highest intensities, even protons become relativistic, giving rise to what might be called the regime of nuclear optics, in which various nuclear processes, such as fusion, can take place. (Reproduced from Umstadter D (2003) Relativistic laser–plasma interactions. *Journal Physics D: Applied Physics* 36: R151–R165, with permission from IOP Publishing Ltd.)

system, located at the Advanced Photon Research Center, Kansai Research Establishment, Japan Atomic Energy Research Institute (JAERI), can be seen in the photograph shown in Figure 4.

This paper will discuss the fundamental concepts underlying what might be referred to more broadly as the field of high-field science. For more detailed descriptions of recent progress in experiment or theory, several review papers have been published on related topics: (i) relativistic nonlinear optics; (ii) high-intensity laser development; (iii) laser accelerators; (iv) intense laser–plasma interactions; and (v) relativistic scattering.

Definitions

For an infinite plane wave for the light wave propagating in the $\hat{z}$ direction (shown in Figure 5), the fields may be described by

$$\mathbf{E} = \hat{e}_x E_0 \exp[\mathrm{i}(kz - \omega t)] = \hat{e}_x E_0 \, \mathrm{e}^{\mathrm{i}\psi} \qquad [1]$$

and

$$\mathbf{B} = \hat{e}_y B_0 \exp[\mathrm{i}(kz - \omega t)] = \hat{e}_y B_0 \, \mathrm{e}^{\mathrm{i}\psi} \qquad [2]$$

where ω and k are the frequency and wavenumber of the laser light, respectively. For the ultrashort pulse durations of the lasers typically used to produce high fields, it is assumed that the ions do not have time to move because of their greater inertia. In this case, $m(\mathrm{d}v/\mathrm{d}t) \approx -e\mathbf{E}$ and the term v/c can be used as an expansion parameter. At even higher fields, electrons can be accelerated to nearly the speed of light as they quiver in the oscillating fields of the light wave. In this case, the force due to the magnetic field can no longer be ignored and the mass of the electron



Figure 2 History of light sources over the last century. Each advance in laser power enables a new regime of optics. (Reproduced from Umstadter D (2003) Relativistic laser–plasma interactions. *Journal Physics D: Applied Physics* 36: R151–R165, with permission from IOP Publishing Ltd.)

can increase as $m = \gamma m_0$, where m_0 is the electron rest mass and the relativistic gamma factor is given by

$$\gamma = \frac{1}{\sqrt{1 - \left(\frac{v}{c}\right)^2}} \qquad [3]$$

The threshold for the relativistic regime of optics is crossed when the electron momentum p exceeds the product of the electron rest mass m_0 and c.

For problems involving charged particle motion in intense electromagnetic fields, it is often convenient to introduce the vector potential: $\mathbf{A}(\mathbf{r}, t) = \mathrm{Re}\{\mathbf{A}_0\, e^{i\psi}\}$. From Maxwell's equation $\nabla \cdot B = 0$, it can be seen that without loss of generality, the magnetic field can be written as the curl of a potential $B = \nabla \times A$. Further, from Faraday's law in vacuum:

$$\nabla \times E = -\frac{1}{c}\frac{\partial B}{\partial t} = -\frac{1}{c}\frac{\partial(\nabla \times A)}{\partial t} \qquad [4]$$

it is clear that $\mathbf{E} = -(1/c)\partial\mathbf{A}/\partial t$. To include the space–charge field of the plasma, as we will do in the section on collective plasma response below, we introduce the potential Φ, and the definition:

$$\mathbf{E} = -\nabla\Phi - \frac{1}{c}\frac{\partial}{\partial t}\mathbf{A} \qquad [5]$$

Assuming the Coulomb gauge:

$$\nabla \cdot \mathbf{A} = 0 \qquad [6]$$

or $A_z = 0$ in 1D, then $\mathbf{A}_\perp$ represents the laser field.

If we neglect Φ for now, then, by Fourier analysis:

$$\mathbf{E} = \mathrm{Re}\left\{\frac{i\omega}{c}\mathbf{A}_0\, e^{i\psi}\right\} \qquad [7]$$



Figure 3 Laser light has become concentrated to ever-smaller regions of space (r) and time (t), dramatically increasing the peak electric field (E) at the laser focus. Prior to the development of chirped-pulse amplification (CPA), the energy of light was produced in long-duration pulses, as shown in the pulse of the bottom figure. After CPA, the pulse duration decreased dramatically as shown in the pulse in the middle. The latest improvement in laser technology has been the use of deformable mirrors, which has allowed lasers to be focused to a spatial dimension that is as small as the temporal dimension, a few laser wavelengths, as shown in the pulse on top. (Reproduced from Umstadter D (2003) Relativistic laser–plasma interactions. *Journal Physics D: Applied Physics* 36: R151–R165, with permission from IOP Publishing Ltd.)

$$\mathbf{B} = \mathrm{Re}\{ik\hat{z} \times \mathbf{A}_0\, e^{i\psi}\} \qquad [8]$$

The light intensity is given by the time-averaged Poynting's vector, which can be written for linear (LP), $\mathbf{A}_0 = A_0\hat{e}_y$ and circular polarizations (CP), $\mathbf{A}_0 = A_0(\hat{e}_x \pm \hat{e}_y)$ as:

$$I = \langle|\mathbf{S}|\rangle = \left\langle\left|\frac{c\mathbf{E} \times \mathbf{B}}{8\pi}\right|\right\rangle = \frac{\omega k}{16\pi}A_0^2 \qquad [9]$$

It is often the combination $I\lambda^3$ that matters, which has units of power and for linear polarization can be

Figure 4 Photograph of the 33-fs duration 0.9-PW-peak power laser system at JAERI. (Reproduced with permission from Yamakawa K (2004) Table-top lasers create ultrahigh peak powers. *OYOBUTURI* 73: 186–193.)

written as

$$I\lambda^2 = \frac{\omega k \lambda^2}{16\pi} A_0^2 = \frac{\pi}{2} c A_0^2 = \left[1.37 \times 10^{18} \frac{\mathrm{W}}{\mathrm{cm}^2} \mu\mathrm{m}^2\right] a_0^2 \qquad [10]$$

where the normalized vector potential is defined as

$$a_0 = \frac{eA_0}{mc^2} \qquad [11]$$

Relativistic effects become significant when a_0 approaches unity, which, as can be seen from eqn [10] occurs for 1 μm wavelength light at a laser intensity of $\sim 1.37 \times 10^{18}$ W/cm^2, corresponding to a electric field strength of 6×10^9 V/cm, which is four orders of magnitude greater than E_{at}.

Single-Particle Motion

The electron orbit, subject to a linearly polarized electromagnetic wave propagating in the $+z$ direction, is governed by the Lorentz equation:

$$m\frac{\mathrm{d}\mathbf{v}}{\mathrm{d}t} = -e\left(\mathbf{E} + \frac{\mathbf{v}}{c} \times \mathbf{B}\right) \qquad [12]$$

where v is the electron velocity, and E and B are the light's electric and magnetic field.

A zeroth order solution to eqn [12] is found by setting $v/c \ll 1$, which allows the term $(v/c) \times B$ to be neglected and γ from eqn [8] is set to unity. Integrating eqn [12] in this limit once over time (t) yields for the velocity:

$$\mathbf{v} = \mathrm{Re}\left\{\frac{e\mathbf{E}}{im\omega}\right\} = \frac{a_0}{c}\begin{cases} \hat{e}_y \cos\psi, & \mathrm{LP} \\ (\hat{e}_x \cos\varphi \mp \hat{e}_y \sin\psi), & \mathrm{CP} \end{cases} \qquad [13]$$

An electron in low-intensity light oscillates with this velocity in a straight line along the polarization vector ($\hat{e}_y$), which when normalized to c, is the normalized vector potential a_0. Integrating again yields for the



Figure 5 Classical optics versus relativistic optics. (a) In classical optics, the amplitude of the light wave is small, electrons oscillate in the direction of the electric field at the light's frequency, and there is no displacement along the light's propagation direction. Note that only the *E* field acts on the electron and the electron-oscillation velocity is very small compared with the speed of light. (b) In relativistic optics, the amplitude of the light wave is very large, the light's magnetic field becomes important and the combined action of the electric and magnetic fields push the electron forward. In this case, the electron velocity becomes close to the speed of light and its motion is a figure-eight superimposed upon a steady drift. (Reproduced from Umstadter D (2003) Relativistic laser–plasma interactions. *Journal Physics D: Applied Physics* 36: R151–R165, with permission from IOP Publishing Ltd.)



Figure 6 Harmonics driven by relativistic Thomson scattering as the electrons in high-intensity laser fields (a_0^2) undergo figure-eight motion display unique angular distributions. (Reproduced from Umstadter D (2003) Relativistic laser–plasma interactions. *Journal Physics D: Applied Physics* 36: R151–R165, with permission from IOP Publishing Ltd.)

transverse displacement:

$$\mathbf{x} = \mathrm{Re}\left\{\frac{e\mathrm{E}}{m\omega^2}\right\} = \frac{a_0}{\omega c}\begin{cases} \hat{e}_y \sin\psi, & \text{LP} \\ (\hat{e}_y \sin\varphi \mp \hat{e}_z \cos\psi), & \text{CP} \end{cases} \qquad [14]$$

Thus, for the $a_0 \sim 1$, the electron excursion during its oscillation is approximately λ.

A first-order approximation for the electron motion can be found by substituting the zeroth order velocity eqn [13] into the $v/c \times B$ term of eqn [12]. The latter then becomes proportional to

$$E \times B \propto \frac{a_0^2}{2}[1 + \cos(2\omega_0)]\hat{e}_z \qquad [15]$$

In the frame in which the electron is on the average at rest, the relativistic motion of an electron is thus described by a figure eight, oscillating twice in the $\hat{e}_z$ or $\hat{k}$ direction for every once in the polarization direction ($\hat{e}_x$); i.e., a figure of eight motion. This originates from the fact that $v \times B \propto E \times B \propto E^2\hat{k}$, which is a product of two functions that vary sinusoidally at frequency ω and thus varies itself at frequency 2ω. In the lab frame, this transverse motion is superimposed upon a steady drift in the ($\hat{e}_z$) direction (shown in Figure 5), originating from the DC term in eqn [15]. The next order approximation would include the mass shift $m = \gamma m_0$. As the field strength increases ($a_0^2 \gg 1$), the longitudinal motion ($\propto a_0^2$) begins to dominate the transverse motion ($\propto a_0$), as shown in Figure 5. This is described more formally below.

In the regime $a_0 \lesssim 1$, electrons radiate photons at harmonics of a modified laser frequency ω_0, with each harmonic order having its own unique angular distribution, as shown in Figure 6. The radiation at the fundamental is the usual donut pattern, with a maximum in the direction perpendicular, and a minimum along, the polarization vector ($\hat{e}_x$). The second harmonic has two emission lobes with maxima pointing at an angle between $\hat{e}_z$ and $\hat{e}_x$. An additional lobe is added for each additional harmonic order. This is referred to as nonlinear or relativistic Thomson scattering. The unique angular distributions of the second and third harmonics emitted from nonlinear relativistic Thomson scattering were observed experimentally and are shown in Figure 7. As will be shown in detail in the section on radiation from relativistic electrons, below, the situation is more complex for $a_0 \gtrsim 1$, and the scattered light is no longer simply harmonic.

Constants of the Motion

Several constants of the motion can be found from an exact treatment for the motion. The starting point is the relativistically correct Lagrangian, which is written as

$$L(\mathbf{r}, \mathbf{v}, t) = -mc^2\sqrt{1 - \frac{v^2}{c^2}} + \frac{q}{c}\mathbf{v} \cdot \mathbf{A} + q\phi \qquad [16]$$



Figure 7 Angular pattern of higher-order harmonic light. Shown are polar plots of the intensity of the second-harmonic light (top) and third harmonic (bottom) as a function of azimuthal angle. Filled circles, experimental data; solid and dashed lines, theoretical results. (Reproduced with permission from Chen S-Y, Maksimchuk A and Umstadter D (1998) Experimental observation of relativistic nonlinear Thomson scattering. *Nature* 396: 653.)

where ϕ is the scalar potential associated with electrostatic fields. The Lorentz equation, eqn [12], is derived from the Euler–Lagrange equation:

$$\frac{\mathrm{d}}{\mathrm{d}t}\frac{\partial L}{\partial \mathbf{v}} - \frac{\partial L}{\partial \mathbf{r}} = 0 \qquad [17]$$

For an infinite plane wave, in which the Lagrangian is independent of space in the transverse direction, eqn [17] yields the conservation of transverse canonical momentum:

$$\frac{\partial L}{\partial \mathbf{v}_\perp} = \mathbf{p}_\perp + \frac{q}{c}\mathbf{A}_\perp = \text{constant} \qquad [18]$$

The sum of the transverse momentum and field strength remain constant. The next constant follows from $\mathrm{d}H/\mathrm{d}t = -\partial L/\partial t$, yielding the relation:

$$\frac{\mathrm{d}E}{\mathrm{d}t} = -\frac{\partial L}{\partial t} = c\frac{\partial L}{\partial z} = c\frac{\mathrm{d}}{\mathrm{d}t}\frac{\partial L}{\partial v_z} = c\frac{\mathrm{d}p_z}{\mathrm{d}t} \qquad [19]$$

where E is the time-dependent energy of the particle, which yields our second constant of the motion:

$$E - cp_z = \text{constant} \qquad [20]$$

For a particle initially at rest, the kinetic energy E_{kin} becomes

$$E_{\mathrm{kin}} = E - mc^2 = p_z c \qquad [21]$$

which yields

$$E_{\mathrm{kin}} = \frac{p_\perp^2}{2m} = p_x c = mc^2(\gamma - 1) \qquad [22]$$

Thus, the electron scattering angle θ is related to the transverse and longitudinal momenta or the kinetic energy by

$$\tan^2\theta = \left(\frac{p_\perp}{p_z}\right)^2 = \frac{2mE_{\mathrm{kin}}}{(E_{\mathrm{kin}}/c)^2} = \frac{2}{\gamma - 1} \qquad [23]$$

The angle of electrons produced by photo-ionization with intense lasers has been shown experimentally to obey the conservation of canonical momentum, as demonstrated in experiments that studied the angular distribution of relativistic electrons emitted from barrier-suppression ionization of atoms in intense laser fields (shown in Figure 8). The transverse normalized vector potential, $\mathbf{a} = e\mathbf{A}_\perp/mc^2$, is thus equal to the transverse normalized momentum:

$$\hat{\mathbf{p}}_\perp = \frac{\mathbf{p}_\perp}{mc} = \mathbf{a} = (0, a_y, a_x) \qquad [24]$$

The normalized kinetic energy can also be written in terms of a:

$$\hat{E}_{\mathrm{kin}} = \frac{E_{\mathrm{kin}}}{mc^2} = \gamma - 1 = \hat{p}_z = \frac{\hat{p}_\perp^2}{2} = \frac{a^2}{2} \qquad [25]$$

This can be rewritten as

$$\gamma = 1 + \frac{a^2}{2} \qquad [26]$$

From eqn [25], the normalized momenta in each direction can be found:

$$\hat{p}_z = \gamma\beta_z = \frac{\gamma}{c}\frac{\mathrm{d}z}{\mathrm{d}t} = \frac{a^2}{2} \qquad [27]$$

$$\hat{p}_y = \gamma\beta_y = \frac{\gamma}{c}\frac{\mathrm{d}y}{\mathrm{d}t} = a_y \qquad [28]$$

$$\hat{p}_x = \gamma\beta_x = \frac{\gamma}{c}\frac{\mathrm{d}x}{\mathrm{d}t} = a_x \qquad [29]$$

Note that the momentum in the longitudinal ($\hat{e}_z$) direction is proportional to a^2 while in the two



Figure 8 Top: Experiment to measure the angle of electron ejection during photo-ionization. Bottom: Kinetic energy versus angle during the production of 3^+ through 8^+ of neon. (Reproduced with permission from Moore CI, Knauer JP and Meyerhofer DD (1995) Observation of the transition from Thomson to Compton scattering in multiphoton interactions with low-energy electrons. *Physics Review Letters* 74: 2439. Copyright (1995) by the American Physical Society.)

transverse directions it is proportional to a. Equations [26]–[29] indicate that in the limit of large a, the normalized velocities are given by

$$\beta_z = \frac{a^2/2}{1+a^2/2} \rightarrow 1, \qquad \beta_y = \frac{a_y}{1+a^2/2} \rightarrow 0, \qquad \beta_x = \frac{a_x}{1+a^2/2} \rightarrow 0 \qquad [30]$$

This indicates that in the deeply relativistic regime, the electron is accelerated to near c in the longitudinal direction, while in the transverse directions its velocity goes to zero. It follows that, as a increases and the electron moves in phase with the light wave, relativistic Thomson scattering will be significantly reduced. Integrating eqn [29] in the variable $\tau = t - x(t)/c$ gives

$$\begin{aligned}\gamma\frac{\mathrm{d}}{\mathrm{d}t} &= \gamma\frac{\mathrm{d}\tau}{\mathrm{d}t}\frac{\mathrm{d}}{\mathrm{d}\tau} = \gamma\left(1 - \frac{1}{c}\frac{\mathrm{d}z}{\mathrm{d}\tau}\right)\frac{\mathrm{d}}{\mathrm{d}\tau} \\ &= \left(1 + \frac{a^2}{2} - \frac{a^2}{2}\right)\frac{\mathrm{d}}{\mathrm{d}\tau} = \frac{\mathrm{d}}{\mathrm{d}\tau} \qquad [31]\end{aligned}$$

which allows the equations for the displacement to be written simply as

$$\frac{\mathrm{d}z}{\mathrm{d}\tau} = c\frac{a^2}{2} \qquad [32]$$

$$\frac{\mathrm{d}y}{\mathrm{d}\tau} = ca_y \qquad [33]$$

$$\frac{\mathrm{d}x}{\mathrm{d}\tau} = ca_x \qquad [34]$$

For a box-shaped pulse, $a_x = a_0\cos(\omega\tau)$ for $0 < \tau < N(2\pi/\omega)$, $a_z = 0$, $a^2 = a_x^2\cos^2(\omega\tau)$, the trajectory for an electron initially at rest at $x = y = z = 0$ at $\tau = 0$ is then

$$\begin{aligned}x(\tau) &= \frac{ca_0^2}{2}\int_0^\tau \cos^2(\omega\hat{\tau})\mathrm{d}\hat{\tau} \\ &= \frac{ca_0^2}{4}\left[\tau + \frac{1}{2\omega}\sin(2\omega\tau)\right] \qquad [35]\end{aligned}$$

$$y(\tau) = ca_0\int_0^\tau \cos(\omega\hat{\tau})\mathrm{d}\hat{\tau} = \frac{ca_0}{4}\sin(\omega\tau) \qquad [36]$$

Thus, as we saw from the first-order appoximation above, eqn [15], the motion consists of a drift along $\hat{x}$:

$$x_\mathrm{d}(t) = \frac{a_0^2}{a_0^2+4}ct \qquad [37]$$

and a figure-eight motion in the drift frame of reference:

$$\begin{aligned}ky &= a_0\sin(\omega\tau), \\ k(z - z_\mathrm{d}) &= \frac{a_0}{8}\sin(2\omega\tau)\end{aligned} \qquad [38]$$

In the strongly relativistic regime, because the electron is strongly accelerated in the direction of the light wave, the harmonic emission from relativistic Thomson scattering loses its dependence on the laser frequency, ω, but instead depends only on the direction of observation, the amplitude a_0 and the initial phase of the electron, relative to the light wave. Electrons that do not begin their trajectories at zero or π phase with respect to the light wave can drift in the transverse direction. For pulses with finite spatial width, such as a Gaussian pulse with field strength peaked on axis, the ponderomotive force of the light can also act to expel the electrons transversely from the axis.

For circular polarization:

$$\mathbf{a}(\mathbf{r}, t) = \mathrm{Re}\{a_0(\hat{e}_y \pm \mathrm{i}\hat{e}_x)\mathrm{e}^{-\mathrm{i}\omega\tau}\} \qquad [39]$$

the electron drifts as it did in the case of linear polarization and described in eqn [37] but orbits in a helical trajectory:

$$y(\tau) = \frac{ca_0}{\sqrt{2}\omega}\sin(\omega t/\gamma) \qquad [40]$$

$$x(\tau) = \mp\frac{ca_0}{\sqrt{2}\omega}\cos(\omega t/\gamma) \qquad [41]$$

Rather than oscillate in amplitude, the relativistic factor remains constant:

$$\gamma = 1 + \frac{a_0^2}{4} \qquad [42]$$

In either polarization case, the light pulse eventually overtakes the electron, leaving the latter at rest. However, net acceleration in vacuum can be obtained only under special circumstances, described by the Lawson–Woodward criterion, such as in the near field of metallic surfaces; with high-order focusing modes instead of infinite plane waves; or with mixed frequencies, or with optics to terminate the light but not the electrons. Regions of a tightly focused Gaussian pulse, where the accelerating field propagates at sub-luminal velocities also exist, but they are effective for only extremely large values of a and thus only very short acceleration lengths.

Role of Initial Phase

If we wish to understand the role of the electron's initial phase, the relativistic Lorentz equation (eqn [12]) may also be written, for an $\hat{x}$-polarized wave traveling in the $\hat{z}$ direction, as

$$\frac{\mathrm{d}}{\mathrm{d}t}(\gamma\beta) = (\hat{x} - \hat{z}\times\beta)a\cos(t - z) \qquad [43]$$

where we normalize time by $1/\omega_0$, velocity by c, and distance by c/ω_0. In eqn [43], $a = eE_0/m\omega_0 c$ is the dimensionless parameter measuring the electric field strength, $\gamma = (1 - \beta_x^2 - \beta_y^2 - \beta_z^2)^{-1/2}$ is the relativistic mass factor, and $\beta = (\beta_x, \beta_y, \beta_z)$ is the electron velocity (in units of c). The electron orbit, subject to the following general initial conditions at time $t = 0$:

$$x = 0, \qquad y = 0, \qquad z = z_{\mathrm{in}} \qquad [44]$$

$$\beta_x = \beta_{x0}, \qquad \beta_y = \beta_{y0}, \qquad \beta_x = \beta_{z0} \qquad [45]$$

$$\beta_{x0} = \beta_{y0} = 0 \qquad [46]$$

has a closed form solution when it is expressed parametrically: $t = t(\theta)$, $r = r(\theta)$, $\beta = \beta(\theta)$, where θ is the phase of the wave, defined by

$$\theta = t - z \qquad [47]$$

Note that $\beta_0 = (\beta_{x0}, \beta_{y0}, \beta_{z0})$ is the unperturbed velocity of the electron ($a = 0$ limit) and that the initial phase that the electron sees is $\theta_{\mathrm{in}} = -z_{\mathrm{in}}$ according to eqns [44] and [47]. This phase can be important in the ionization of the gas by an intense laser.

For the special case $\beta_{x0} = 0$, $\beta_{y0} = 0$, one finds $\beta_y = 0$, and the orbital equation yields the following closed form solution:

$$\gamma = \gamma_0 + \frac{a^2(\sin\theta - \sin\theta_{\mathrm{in}})^2}{2\gamma_0(1 - \beta_{z0})} \qquad [48]$$

$$\gamma\beta_z = \gamma - \gamma_0(1 - \beta_{z0}) \qquad [49]$$

$$\gamma\beta_x = \frac{1}{\gamma_0(1 - \beta_{z0})}a(\sin\theta - \sin\theta_{\mathrm{in}}) \qquad [50]$$

$$x = \frac{a[(\cos\theta_{\mathrm{in}} - \cos\theta) - (\theta - \theta_{\mathrm{in}})\sin\theta_{\mathrm{in}}]}{\gamma_0(1 - \beta_{z0})} \qquad [51]$$

$$\begin{aligned} t = {} & \frac{(\theta - \theta_{\mathrm{in}})}{1 - \beta_{z0}}\left[1 + \frac{a^2}{2}\left(\frac{1}{2} + \sin^2\theta_{\mathrm{in}}\right)\right] \\ & + \frac{a^2(1 + \beta_{z0})}{2(1 - \beta_{z0})}\left[-\frac{\sin 2\theta}{4} + 2\cos\theta\sin\theta_{\mathrm{in}}\right. \\ & \left. - \frac{3\sin 2\theta_{\mathrm{in}}}{4}\right] \end{aligned} \qquad [52]$$

In eqns [48]–[52], $\gamma_0 = (1 - \beta_{z0}^2)^{-1/2}$ and β_{z0} may either be negative (counter-propagating against the laser), or zero (Thomson scattering), or positive (co-propagating with the laser). Note that the velocity components β_x and β_z are given as explicit functions of θ according to eqns [49] and [50], upon using eqn [48]. They are periodic functions of θ of period 2π. The period, T, of this periodic (Figure 8) motion is thus equal to the increase in t as θ increases by 2π. Thus, we obtain from eqn [53]:

$$T = \frac{2\pi}{1 - \beta_{z0}}\left[1 + \frac{a^2}{2}\left(\frac{1}{2} + \sin^2\theta_{\mathrm{in}}\right)\right] \qquad [53]$$

The parametric solution for the z-coordinate of the electron orbit is given by $z = t - \theta$, in which t is given by eqn [52]. Over one orbital period, T, the electron undergoes a net displacement $r_0 = (x_0, 0, z_0)$ where x_0 is given by the increase in eqn [51] as θ increases by 2π, and z_0 is simply $T - 2\pi$:

$$\begin{aligned} z_0 &= T - 2\pi \\ &= \frac{2\pi}{1-\beta_{z0}}\left[\beta_{z0} + \frac{a^3}{2}\left(\frac{1}{2} + \sin^2\theta_{\mathrm{in}}\right)\right] \end{aligned} \qquad [54]$$

$$x_0 = \frac{-2\pi a \sin\theta_{\mathrm{in}}}{\gamma_0(1-\beta_{z0})} \qquad [55]$$

Note that the electron trajectory depends on a, β_{z0}, and θ_{in} in a rather complicated manner. Accordingly, the fundamental frequency ω_1 of the radiation spectrum depends on these three quantities. For backscattered radiation ($\hat{n} = -\hat{z}$), the dependence on electron beam and on the laser becomes decoupled.

Following is a useful formula relating the change of t with respect to θ:

$$\frac{\mathrm{d}\theta}{\mathrm{d}t} = 1 - \beta_z = \frac{\gamma_0(1-\beta_{z0})}{\gamma} \qquad [56]$$

which may be verified from eqns [47] and [49]. Equation [56] is also valid for arbitrary values of β_{x0}, β_{y0}, β_{z0}, and θ_{in}, in which case γ_0 is the electron's relativistic mass factor in the absence of the laser.

Radiation from Relativistic Electrons

An electron with displacement $r(t)$ and velocity $v(t)$ carries a current density $J(r,t) = ev(t)\delta r - r(t)]$, whose Fourier transform $J_{\mathrm{F}}(k,\omega)$ may easily be obtained. The total work done, W, in ergs, performed by the current $\mathbf{J}(\mathbf{r},t)$ on the electric field $\mathbf{E}(\mathbf{r},t)$ is given by

$$\begin{aligned} W &\equiv \int \mathrm{d}\omega\,\mathrm{d}\Omega \frac{\mathrm{d}^2 W}{\mathrm{d}\omega\,\mathrm{d}\Omega} \\ &= \int \mathrm{d}\omega\,\mathrm{d}\Omega \frac{\omega^2}{c^2}\left[|\mathbf{J}_{\mathrm{F}}(\mathbf{k},\omega)|^2 - |\mathbf{n}\cdot\mathbf{J}_{\mathrm{F}}(\mathbf{k},\omega)|^2\right] \end{aligned} \qquad [57]$$

where the $\mathbf{k}$-space differential volume $\mathrm{d}^3\mathbf{k} = k^2\,\mathrm{d}k\,\mathrm{d}\Omega$ is expressed in terms of the solid angle (Ω) in the direction of the unit vector $\mathbf{n} = c\mathbf{k}/\omega$. We immediately obtain from eqn [56], under the far-field approximation:

$$\frac{\mathrm{d}^2 W}{\mathrm{d}\Omega\,\mathrm{d}\omega} = \frac{e^2\omega^2}{4\pi^2 c}|\mathbf{n}\times[\mathbf{n}\times\mathbf{F}(\omega)]|^2 \qquad [58]$$

$$\mathrm{F}(\omega) = \int_{-\infty}^{\infty} \mathrm{d}t\ \beta(t)\mathrm{e}^{\mathrm{i}\omega[t-\mathbf{n}\cdot\mathbf{r}(t)/c]} \qquad [59]$$

Equation [58] gives the energy radiated by the electron in the direction of the unit vector, per unit solid angle, per unit frequency ω. Radiation damping is ignored throughout.

Let us consider the simplest case where the electron orbit is strictly a periodic function of time with period T and a net displacement $\mathbf{r}_0$ per period. Thus, we have for all integers m (positive, negative, or zero):

$$\beta(t+mT) = \beta(t), \quad \mathbf{r}(t+mT) = m\mathbf{r}_0 + \mathbf{r}(t) \qquad [60]$$

Equation [59] may then be written as, because of Thomson scattering the energy of the scattered photon is much less than the electron rest mass in the average rest frame of the electron, i.e.:

$$\frac{\hbar\omega_{\mathrm{L}}}{mc^3} \ll 1 \qquad [61]$$

$$\begin{aligned} \mathrm{F}(\omega) &= \sum_{m=-\infty}^{\infty}\int_{mT}^{(m+1)T} \mathrm{d}t\ \beta(t)\mathrm{e}^{\mathrm{i}\omega[t-\mathbf{n}\cdot\mathbf{r}(t)/c]} \\ &= \sum_{m=-\infty}^{\infty} f(\omega)\mathrm{e}^{\mathrm{i}m\omega[T-\mathbf{n}\cdot\mathbf{r}_0/c]} \end{aligned} \qquad [62]$$

where

$$f(\omega) = \int_0^T \mathrm{d}t\ \beta(t)\mathrm{e}^{\mathrm{i}\omega[t-\mathbf{n}\cdot\mathbf{r}(t)/c]} \qquad [63]$$

and we have used eqn [60]. Upon using $\sum_m \mathrm{e}^{\mathrm{i}mx} = \sum_m 2\pi\delta(x - 2m\pi)$ in the last infinite sum in eqn [64] and the property of the Dirac delta function, $\delta(ax) = (1/a)\delta(x)$, we obtain from eqns [62] and [63], the following expression for the spectrum:

$$\mathrm{F}(\omega) = \sum_{m=-\infty}^{\infty} \mathrm{F}_m\delta(\omega - m\omega_1) \qquad [64]$$

$$\omega_1 = \frac{2\pi}{T - \mathbf{n}\cdot\mathbf{r}_0/c}, \qquad [65]$$

$$\mathbf{F}_m = \frac{\omega_1}{2\pi}\int_0^T \mathrm{d}t\ \bar{\beta}(t)\mathrm{e}^{\mathrm{i}m\omega_1[t-\mathbf{n}\cdot\mathbf{r}(t)/c]} \qquad [66]$$

Note from eqn [64] that the radiation spectrum is discrete, for strictly periodic motion of the electron. The base frequency of this spectrum, ω_1, depends on the periodicity (T) of the electron, on the electron's net displacement ($\mathbf{r}_0$) in one such period, and on the direction ($\hat{n}$) in which the radiation is observed. Thus, the radiation spectrum is, in general, not at the harmonic frequency of the laser (nor at the harmonics of the electron orbital frequency, $2\pi/T$). It would thus be wrong to simply insert $\omega = n\omega_0$ in eqn [63] and to replace the electron's orbital period T there by the laser's optical period $2\pi/\omega_0$ and consider the resultant value of that integral to give the spectral amplitude of the radiation at the nth harmonic of the laser frequency. Erroneous conclusions regarding generation of high laser harmonics have appeared in the literature based on such an intuitive (but incorrect) substitution.

The power, p_m (in erg/s), radiated at the harmonic frequency $\omega = m\omega_1$ per unit solid angle in the direction of the unit vector $\hat{n}$ is then given by (from eqns [58] and [64]):

$$p_m = \frac{e^2 m^2 \omega_1^2}{4\pi^2 c} |\mathbf{n} \times \mathbf{F}_m|^2 \qquad [67]$$

where the dimensionless spectral amplitude $\mathbf{F}_m$ is given in eqn [66]. It is easy to show from eqns [60] and [65] that the integrand in eqn [66] is a periodic function of t of period T. Integrals of this type are readily evaluated by the Romberg method. The radiation spectrum observed *exactly* in the forward direction of the laser ($\hat{n} = \hat{z}$) always has only one discrete frequency, $\omega = \omega_1 = \omega_0$, which is easily shown from eqn [65] upon using the first equality of eqn [53]. This statement is true regardless of the velocity of the electron or the laser intensity, and may easily be deduced from eqn [66] for this case. However, for an energetic electron beam that is almost co-propagating with the laser, such as that produced by the laser itself, high harmonics at the laser frequency may be observed in the direction just slightly off the laser direction.

In the backscattering direction of the laser ($n = -z$), if we set $\theta_{\text{in}} = 0$, one obtains the following expressions for ω_1 and p_m, the backscatter power at $\omega = m\omega_1$ (from eqn [67]):

$$\begin{aligned} \frac{\omega_1}{\omega_0} &= \left(\frac{2}{2+a^2}\right)\left(\frac{1-\beta_{z0}}{1+\beta_{z0}}\right) \\ &= \left(\frac{2}{2+a^2}\right)\gamma_0^2(1-\beta_{z0})^2 \end{aligned} \qquad [68]$$

$$p_m = \frac{A}{\gamma_0^2(1-\beta_{z0})^2}\left(\frac{\omega_1}{\omega_0}\right)^4 s_m \qquad [69]$$

where $A = e^2\omega_0^2/4\pi^2 c = 0.69[\lambda(1\ \mu\text{m})]^{-2}$ erg/s, $s_m = 0$ for $m = 0, \pm 2, \pm 4, \ldots$, and for $m = \pm 1, \pm 3, \pm 5, \ldots$,

$$s_m = (a\pi)^2 m^2 \left[J_{\frac{(m-1)}{2}}(m\kappa) - J_{\frac{(m+1)}{2}}(m\kappa)\right]^2 \qquad [70]$$

$$\kappa = \frac{a^2}{2(a^2+2)} \qquad [71]$$

The $J_\nu(x)$ above are Bessel functions of the first kind of order ν. They also appear in the quantity '$[JJ]$' or '$F_m(K)$' in the FEL/synchrotron literature, where K is the undulator/wiggler parameter K. Setting $K = a$, one finds $s_m = \pi^2(1 + K^2/2)^2 F_m(K)$. It is easy to show that $s_m = s_{-m}$ for all odd integers m. Note that the relative spectral shape of s_m depends only on a, and is independent of the electron beam energy. The discrete spectrum for small a approaches a continuum for $a^2 \gg 1$.

The maximum values of s_m, occurring at $m = M$ with a value s_M, are shown in Figure 9. Note that the frequency component $\omega = M\omega_1$ contains the highest backscattered power. In terms of the laser frequency, the frequency component $\omega = N\omega_0$ would contain the highest backscatter power, where $N = M\omega_1/\omega_0$. The total backscatter power, P_T (in ergs/s), per unit solid angle in the $\mathbf{n} = -\mathbf{z}$ direction is then given by $P_\text{T} = \Sigma p_m$, where the sum is taken over all odd values of m:

$$P_\text{T} \approx \frac{\gamma_0^6(1-\beta_{z0})^6}{(\lambda/1\ \mu\text{m})^3} \times \begin{cases} 13.7a^3, & (a < 0.3) \\ 11.1/a, & (a \gg 1) \end{cases} \qquad [72]$$

To summarize, due to the rapid acceleration of electrons in the direction of the light wave and decrease of the oscillation frequency in the deeply relativistic regime, the photon energy from relativistic nonlinear scattering scales only linearly with laser field strength, $\sim a$. However, the relativistic motion of the electron results in a reduction in the angle of the scattered light, such that the harmonics are generated in a low-divergence-angle forward-propagating beam. There is also a relativistic Doppler shift ($\sim\gamma^2$). For instance, this mechanism will be used in high-energy physics experiments to cleanly make constituent particles in the gamma–gamma ($\gamma\gamma$) collider, in which gamma rays with energy 200 GeV will be generated by Compton scattering 1 eV photons from 250 GeV energy conventionally accelerated electron beams ($\gamma = 5 \times 10^{11}$).

Using a much smaller, laser-based accelerator (discussed in the following section), a 1 eV photon can be upshifted by this Doppler shift to an energy of 50 keV, corresponding to subatomic spatial resolution and of interest in medical diagnostics, by an electron beam with only $\gamma = 200$ (100 MeV). In this case, the maximum efficiency is obtained for laser fields a of order unity. When compared with conventional light sources based on cm-wavelength magnetostatic wigglers, the electromagnetic wigglers of such all-optical-laser-based EUV sources have ten-thousand times shorter wavelength (micron-scale). Thus, the total length of the wiggler region is correspondingly smaller (only mm in length). Another consequence of this is that the frequency upshift required to reach a given output wavelength is also ten thousand times smaller. Also, given that the required electron energy scales as the square root of the upshift, the required electron energy can be one-hundred-times lower (10–100 MeV). It follows from this, and the fact that the field gradients of these accelerators can be ten thousand times higher (1 GeV/cm) than convention RF-based accelerators, that the size of the accelerating region can, in principle, be a million times smaller (only mm in length). Besides its small size, this EUV source can produce femtosecond duration pulse and be synchronized with a relatively low jitter with another femtosecond light pulse having a different wavelength (by virtue of the possibility of deriving the two pulses from the same laser pulse); this is advantageous for the study of ultrafast pump-and-probe photo-initiated processes. The exceptionally low transverse emittance of laser-accelerated electron beams may even make it possible to generate coherent XUV radiation by means of the self-amplified spontaneous emission (SASE) free-electron lasing (FEL) mechanism.



Figure 9 Normalized spectral distribution of s_m, at frequency $\omega = m\omega_1$. Here, s_m is normalized with respect to the maximum value s_M, occurring at $m = M$. (Reproduced from Lau Y, He F and Umstadter D (2003) Nonlinear Thomson scattering: A tutorial. *Physics Plasmas* 10: 2155, with permission from the American Institute of Physics.)

Collective Plasma Response

The above equations apply to electron motion in vacuum. In the case of electrons in plasmas, the collective plasma electron response needs to be considered. A theory for the 1D nonlinear interaction of intense laser fields with electrons has been developed.

The variables are normalized such that

$$\mathbf{a} = e\mathbf{A}/mc^2, \qquad \phi = e\Phi/mc^2 \qquad [73]$$

$$\mathbf{u} = \mathbf{p}/mc, \qquad \beta = \mathbf{v}/c, \qquad \mathbf{u} = \gamma\beta \qquad [74]$$

$$\gamma = (1 + u^2)^{1/2} = (1 - \beta^2)^{-1/2} \qquad [75]$$

The relativistic force equation (Lorentz equation) is given by

$$\frac{\mathrm{d}}{\mathrm{d}t}\mathbf{u} = \nabla\phi + \frac{\partial}{\partial t}\mathbf{a} - \bar{\beta}\times(\nabla\times a) \qquad [76]$$

The energy equation ($\mathbf{u}\cdot$force equation) is given by

$$\frac{\mathrm{d}}{\mathrm{d}t}\gamma = \beta\cdot\left(\frac{\partial}{\partial z}\phi + \frac{\partial}{\partial t}\mathbf{a}\right) \qquad [77]$$

The transverse force equation (1D) is

$$\frac{\mathrm{d}}{\mathrm{d}t}\mathbf{u}_\perp = \left(\frac{\partial}{\partial t} + \beta_z \frac{\partial}{\partial z}\right)\mathbf{a}_\perp \qquad [78]$$

Since $\mathbf{a} = \mathbf{a}(z, t)$:

$$\frac{\mathrm{d}}{\mathrm{d}t}\mathbf{a}_\perp = \left(\frac{\partial}{\partial t} + \beta_z \frac{\partial}{\partial z}\right)\mathbf{a}_\perp \qquad [79]$$

hence:

$$\frac{\mathrm{d}}{\mathrm{d}t}(\mathbf{u}_\perp - \mathbf{a}_\perp) = 0 \qquad [80]$$

This is just conservation of transverse canonical momentum. Assuming $\mathbf{u}_\perp = 0$ prior to the laser interaction gives

$$\mathbf{u}_\perp = \mathbf{a}_\perp \qquad [81]$$

which is the same as eqn [24].

The electron response to the normalized scaler and vector potentials of the form $\phi = \phi(z - ct)$ and $\mathbf{a} = \mathbf{a}(z - ct)$, which are a function of only $\xi = z - ct$, is completely described by the following constants of the motion:

$$\beta_\perp - a_\perp/\gamma = 0, \qquad [82]$$

$$\gamma(1 - \beta_z) - \phi = 1, \qquad [83]$$

$$n(1 - \beta_z) = n_0, \qquad [84]$$

where $\gamma = (1 - \beta^2)^{-1/2}$ is the relativistic factor and n is the electron density. This allows the various electron quantities to be specified solely in terms of the potentials:

$$\beta_\perp = \frac{2(1+\phi)a_\perp}{(1 + a_\perp^2) + (1+\phi)^2}, \qquad [85]$$

$$\beta_z = \frac{(1 + a_\perp^2) - (1+\phi)^2}{(1 + a_\perp^2) + (1+\phi)^2}, \qquad [86]$$

$$\gamma = \frac{(1 + a_\perp^2) + (1+\phi)^2}{2(1+\phi)}, \qquad [87]$$

$$\frac{n}{n_0} = \frac{(1 + a_\perp^2) + (1+\phi)^2}{2(1+\phi)^2} \qquad [88]$$

In the single particle limit, $\phi \equiv 0$, eqns [26] and [30] are retrieved. For a long pulse interacting with a dense plasma, $\tau_\mathrm{L} \gg \omega_\mathrm{p}^{-1}$ (i.e., neglecting wakefield effects) it can be shown that $(1 + \phi) \simeq (1 + a_0^2)^{1/2}$ for circular polarization and $(1 + \phi) \simeq (1 + a_0^2/2)^{1/2}$ for linear polarization.

Propagation

To understand the propagation of high-intensity light in plasma, we need to understand how the dielectric properties of a plasma medium are affected by the relativistic electron mass change. A wave equation is found by taking the curl of Faraday's law:

$$\nabla \times \mathbf{E} = -\frac{1}{c}\frac{\partial \mathbf{B}}{\partial t} \qquad [89]$$

and using Ampere's law:

$$\nabla \times \mathbf{B} = 4\pi \mathbf{J}/c + \frac{1}{c}\frac{\partial \mathbf{E}}{\partial t} \qquad [90]$$

gives

$$\begin{aligned}\nabla \times \nabla \times \mathbf{E} &= -\nabla^2 \mathbf{E} + \nabla(\nabla \cdot \mathbf{E}) \\ &= \frac{1}{c^2}\left[4\pi \frac{\partial \mathbf{J}}{\partial t} - \frac{\partial^2 \mathbf{E}}{\partial t^2}\right]\end{aligned} \qquad [91]$$

where $\mathbf{J} = \sum n_i q_i v_i$ and the summation over the index i is done over all charged species of electrons and ions. Using Coulomb's law:

$$\nabla \cdot \mathbf{E} = 4\pi\rho \qquad [92]$$

where $\rho = \sum n_i q_i$, and assuming a uniform plasma, the second term on the left vanishes. Substituting eqn [13] for the velocity, we find

$$\left(-\frac{\partial^2}{\partial t^2} + c^2\nabla^2 - \omega_\mathrm{p}^2\right)\mathbf{E} = 0 \qquad [93]$$

where

$$\omega_\mathrm{p} = (4\pi n_i q_i^2/m_i)^{1/2} \qquad [94]$$

is the plasma frequency. Assuming again plane waves and Fourier analyzing, yields the well-known dispersion relation for electromagnetic waves in plasma:

$$\omega^2 = \omega_\mathrm{p}^2 + c^2k^2 \qquad [95]$$

The index of refraction can be written fully relativistically as

$$\eta^2 = \frac{c^2k^2}{\omega^2} = \frac{c^2}{v_\phi^2} = 1 - \frac{\omega_\mathrm{p}^2}{\omega^2} \qquad [96]$$

where v_ϕ is the phase velocity of the light wave. Assuming infinitely massive ions, the plasma frequency can be written as

$$\omega_\mathrm{p} = \frac{\omega_{\mathrm{p}0}}{\gamma^{1/2}} = \left(\frac{4\pi n_\mathrm{e} e^2}{\gamma m_0}\right)^{1/2} \qquad [97]$$

where ω_{p0} is the plasma frequency in a quiescent plasma, e is the electron charge, m_0 is the electron rest mass, and n_e is the plasma electron density. A change in mass changes the plasma frequency, which in turn modifies the index of refraction and the velocity of the light wave. The light's phase velocity then depends on the laser intensity. This can be seen clearly if we expand the phase velocity for small field strength ($a_0 \ll 1$):

$$v_\phi = \frac{c}{\eta} \sim c\left[1 + \frac{\omega_{p0}^2}{2\omega^2}\left(1 - \frac{\langle a_0^2\rangle}{2}\right)\right] \qquad [98]$$

An on-axis minimum of the phase velocity [i.e., $v_\phi(r) > v_\phi(0)$] can be created by a laser beam with an intensity profile peaked on axis, such as with a Gaussian beam, causing the wavefronts to curve inward and the laser beam to focus, as shown in Figure 10. When this focusing effect just balances the defocusing caused by diffraction, the laser pulse can propagate over a longer distance than it could in vacuum, while maintaining a small cross-section. This mechanism is referred to as relativistic self-guiding.



Figure 10 Relativistic self-focusing occurs when an on-axis peak in light intensity (left) produces an on-axis dip in the phase velocity (middle), which acts like a positive lens to cause the phase fronts to curve inward (right). (Reproduced from Umstadter D (2003) Relativistic laser–plasma interactions. *Journal Physics D: Applied Physics* 36: R151–R165, with permission from IOP Publishing Ltd.)

Relativistic Self-Focusing

The threshold for relativistic self-focusing can be obtained using the fully relativistic formalism with the vector potential, as in our previous discussion of electron motion in vacuum. In this case, we can rewrite eqn [91] as

$$\nabla^2 \mathbf{a} - \frac{1}{c^2}\frac{\partial^2 \mathbf{a}}{\partial t^2} = \frac{\omega_p^2}{c^2}\frac{n_e \mathbf{a}}{n_0 \gamma} \qquad [99]$$

where $n_0 = n_i$ is the uniform background density. For a Gaussian beam focused in vacuum, where

$$\mathbf{a}(\mathbf{r}, t) = \operatorname{Re}\{\mathbf{a}_0(\mathbf{r}, t)\exp[i(\mathbf{k}\cdot\mathbf{r} - \omega t)]\} \qquad [100]$$

and the amplitude $\mathbf{a}(\mathbf{r}, t)$ varies much less less in r and t than does the phase:

$$|\partial a_0/\partial t| \ll |\omega a_0|, \qquad |\partial a_0/\partial z| \ll |k a_0| \qquad [101]$$

then

$$a_0(r,z) = \frac{e^{-r^2/(r_0^2(1+z^2/L_r^2))}}{\sqrt{1+z^2/L_R^2}} \exp\left\{ -\mathrm{i}\arctan\left(\frac{z}{L_R}\right) + \mathrm{i}\left(\frac{r}{r_0}\right)^2 \frac{z/L_R}{1+z^2/L_R^2}\right\} \qquad [102]$$

satisfies the envelope equation (assuming second deriviatives are small compared to first derivatives), where L_R is the Rayleigh range and r_0 is the focal radius. In plasma, eqn [99] can then be written in this envelope approximation as

$$\left[\nabla_\perp^2 + 2ik\frac{\partial}{\partial z}\right]a = -\frac{\omega_p^2}{c^2}\frac{|a|^2}{4}a \qquad [103]$$

The power at which the first and last terms of eqn [103] are in balance is

$$P = \frac{\pi R^2 I_0}{2} \qquad [104]$$

An equation for the beam radius R can thus be found:

$$\frac{d^2 R(z)}{dz^2} = \frac{4}{k^2 r_0^2}\left[1 - \frac{1}{22}\frac{\omega_p^2}{c^2}|a_0|^2 r_0^2\right] \qquad [105]$$

Self-focusing occurs when the two terms in the brackets in eqn [105] are equal, which gives for the critical power:

$$P_{\text{crit}} \simeq 17.4 \cdot (\omega/\omega_p)^2 \text{ GW} \qquad [106]$$

This corresponds to 1 TW for 1 μm light focused into a gas with electron density of $10^{19}/\text{cm}^3$. Note that this is a power threshold, not an intensity threshold, because the tighter the focusing, the greater the diffraction (the first term in eqn [103]). Numerous recent experiments have confirmed this focusing mechanism when $P > P_{\text{crit}}$.

Any spatial variation of the laser intensity will act to push an electron to regions of lower intensity through the so-called ponderomotive force:

$$\mathbf{F} = \nabla\gamma = \nabla\sqrt{1 + a^2} = (2\gamma)^{-1}\nabla a^2 \qquad [107]$$

$$\mathbf{F}_{\mathrm{pond}} = -\frac{m_0 c^2}{8\pi} \frac{\nabla a_0^2}{\sqrt{1+\dfrac{a_0^2}{2}}} \cdot \left[\left(\frac{2}{a_0^2} + 1 \right) E(2\pi, \kappa) - \frac{2}{a_0^2} F(2\pi, \kappa) \right] \qquad [108]$$

where

$$\kappa = \frac{a_0^2/2}{1 + a_0^2/2} \qquad [109]$$

and F and E are the elliptic integrals of the first and second kind, respectively. In the low intensity limit, i.e., when $a_0^2 \ll 1$;

$$\mathbf{F}_{\mathrm{pond}} = -\frac{m_0 c^2}{4} \nabla a_0^2 \qquad [110]$$

That is, the laser ponderomotive force is roughly proportional to the gradient of laser intensity.

A Gaussian-shaped laser's ponderomotive force will tend to expel electrons radially from the region of the axis, so called 'electron cavitation.' If the ponderomotive force is high enough for long enough, the charge displacement due to expelled electrons (in either the lateral or longitudinal direction) will eventually cause the ions to move as well through the Coulomb electrostatic force, forming a density channel. Because $n_{\mathrm{e}}(0) < n_{\mathrm{e}}(r)$, and thus $v_\phi(0) < v_\phi(r)$, this enhances the previously-discussed relativistic self-guiding and can itself guide a laser pulse.

For plasmas created by photo-ionization of a gas by a Gaussian laser pulse, the density will be higher on the axis than off the axis. If we instead expand the phase velocity in terms of changes in density:

$$\frac{v_\phi}{c} \sim 1 + \frac{\omega_{\mathrm{p}0}^2}{\omega^2} \frac{\Delta n_{\mathrm{e}}}{n_{\mathrm{e}}} \qquad [111]$$

The phase velocity will thus be higher on axis, which will tend to defocus the light and increase the self-guiding threshold. In order to avoid this, gases with low atomic number and thus fewer available electrons, such as H_3, are commonly used as targets.

Raman Scattering, Plasma Wave Excitation and Electron Acceleration

The local phase velocity, described in eqns [98] and [111], can also vary longitudinally if the intensity and/or electron density does. Local variation in the index of refraction can 'accelerate' photons, i.e., shift their frequency, resulting in photon bunching, which in turn bunches the electron density through the ponderomotive force (F), and so on. When the laser pulse duration is longer than an electron plasma period, $\tau \gg \tau_{\mathrm{p}} = 2\pi/\omega_{\mathrm{p}}$, this photon and electron bunching grows exponentially, leading to the stimulated Raman scattering instability. Energy and momentum must be conserved when the electromagnetic wave $(\omega_0, \mathbf{k}_0)$ decays into a plasma wave $(\omega_{\mathrm{p}}, \mathbf{k}_{\mathrm{p}})$ and another light wave $(\omega_0 - \omega_{\mathrm{p}}, \mathbf{k}_0 - \mathbf{k}_{\mathrm{p}})$.

From an equivalent viewpoint, the process begins with a small density perturbation, Δn_{e}, which, when coupled with the quiver motion, eqn [13], drives a current $J = \Delta n_{\mathrm{e}} e v_{\mathrm{e}}$. This current then becomes the source term for the wave equation (eqn [91]), driving the scattered light wave. The ponderomotive force, due to the beating of the incident and scattered light wave, enhances the density perturbation, creating a plasma wave and the process begins anew. In three dimensions, a plasma wave can be driven when transverse self-focusing and stimulated Raman scattering occur together, a process called the self-modulated wakefield instability.

Two conditions must be satisfied for self-modulation to occur in the plasma. First, the laser pulse must be long compared to the plasma wave, $L \gg \lambda_{\mathrm{p}}$. This allows the Raman instability time to grow, and it allows for feedback from the plasma to the laser pulse to occur. Second, the laser must be intense enough for relativistic self-focusing to occur, $P > P_{\mathrm{c}}$, so that the laser can be locally modified by the plasma. Under these conditions, the laser can form a large plasma wave useful for accelerating electrons.

As the long laser pulse enters the plasma, it will begin to drive a small plasma wave due to either forward Raman scattering or the laser wakefield effect from the front of the laser pulse. This small plasma wave will have regions of higher and lower density with both longitudinal and radial dependence. That is, the plasma wave will be three-dimensional in nature with a modulation along the propagation direction of the laser and a decay in the radial direction to the ambient density (see Figure 11). The importance of this lies with how it affects the index of refraction in the plasma. In the regions of the plasma wave where the plasma density is lower, the radial change in the index of refraction is negative, $\partial n(r)/\partial r < 0$. This means that this part of the plasma acts like a positive lens and focuses the laser. Whereas regions of the plasma wave where the density is higher, $\partial n(r)/\partial r > 0$, the opposite occurs and the laser defocuses. This has the effect of breaking up the laser pulse into a series of shorter pulses of length $\lambda_{\mathrm{p}}/2$ which will be separated by the plasma period. The instability occurs because of how the plasma responds to this. Where the laser is more tightly focused, the ponderomotive force will be



Figure 11 The plasma wave generated by a SMLWFA is three-dimensional in nature. Note that the darker regions correspond to areas of higher plasma density. The graphs to the right represent lineouts of the plasma density longitudinally and radially at the indicated points. (Reproduced with permission from Wagner R (1998) Laser–plasma electron accelerators and nonlinear relativistic optics. PhD thesis, University of Michigan.)

greater and will tend to expel more electrons. This decreases the density in these regions even further, resulting in more focusing of the laser. This feedback rapidly grows, hence the instability.

The phase velocity of the plasma wave in the case of forward scattering is equal to the group velocity of the beat wave, which for low-density plasma is close to the speed of light, as can be seen from the relation:

$$v_\phi = \omega_\mathrm{p}/k_\mathrm{p} = \Delta\omega/\Delta k = v_\mathrm{g} = c\eta \sim c \qquad [112]$$

where eqn [94] and $\omega_\mathrm{p}^2 \ll \omega^2$ were used to show that η is close to unity. Such relativistic plasma waves can also be driven by short pulses ($\tau \sim \tau_\mathrm{p}$). In this case, the process is referred to as laser–wakefield generation, referring to the analogy with the wake driven by the bow of a boat moving through water, but the mechanism is similar (except it has the advantage that the plasma wave is driven linearly instead of as an instability).

In either case, the resulting electrostatic plasma wave can continuously accelerate relativistic electrons with enormous acceleration gradients. The gradient can be estimated from eqn [92] and the fact that because

$$\nabla \cdot \mathbf{E} \sim E\omega_\mathrm{p}/c \propto E\sqrt{n_\mathrm{e}} \qquad [113]$$

then

$$E \sim \sqrt{n_\mathrm{e}}\ \mathrm{eV/cm} \qquad [114]$$

corresponding to 1 GeV/cm for $n_\mathrm{e} = 10^{18}\ \mathrm{cm}^{-3}$. Because this gradient is four orders of magnitude greater than achieved by conventional accelerators (based on fields driven by radio-frequency waves pumped into metal cavities), laser-driven plasma accelerators have received considerable recent attention. They have been shown to accelerate an amount of electron charge (100 nC) comparable to that from conventional accelerators and to have superior transverse geometrical emittance (product of divergence angle and spotsize, similar to the *f*/# in light optics). However, their longitudinal emittance is currently much inferior, energy spreads of 100%. They have been shown to be useful for much of the same applications: radio-isotope production, radiation chemistry, as well as X-ray, proton, and neutron generation. Once the longitudinal emittance can be reduced, they may be advantageous for, among other applications, injectors (especially of short-lived unstable particles) into larger conventional accelerators for high-energy physics research and light sources, and, as discussed in the section on radiation from relativistic electrons about, as stand-alone all-optically driven ultrashort-pulse duration X-ray sources.

The SIMLAC code has been used to study wakefield generation and laser propagation in the limit $a^2 \ll 1$. It draws from nonlinear optics models and treats propagation in the group velocity frame. In this idealized model (which assumes perfect Gaussian beams), the pulse and wake are maintained over long enough propagation distances to accelerate an electron to GeV energy, as shown in Figure 12. A three-dimensional envelope equation for the laser field was derived that includes nonparaxial effects, wakefields, and relativistic nonlinearities.

The resonant wakefield has been characterized experimentally by temporal interferometry, as shown in Figure 13. However, this was done only for the tight-focusing case in which the laser spotsize is much



Figure 12 The ‘standard’ resonant wakefield simulated with SIMLAC, a code that moves at the light pulse’s group velocity. (Reproduced with permission from Umstadter D (2001) Review of physics and applications of relativistic plasmas driver by ultra-intense lasers. *Physics Plasmas* 8: 1774.)



Figure 13 Typical result of a phase shift measurement to study a resonantly excited laser wakefield plasma wave by means of time-domain interferometry. Parts (A) and (B) have different color scales. The bottom graph is a line out of part (B) along the laser axis. (Reproduced with permission from Marquès JR, Dorchies F, Audebert P, Ceindre JP, Amiranoff F, Gauthier JC, Hammoniaux G, Antonetti A, Chessa P, Mora PTM and Antonson J (1997) Frequency increase and damping of nonlinear electron plasma oscillations in cylindrical symmetry. *Physics Review Letters* 78: 3463. Copyright (1995) by the American Physical Society.)



Figure 14 Artistically enhanced photograph of the acceleration of an electron beam by a laser interacting with a gas jet inside a vacuum chamber. The laser crosses the picture from left to right and is focused by a parabolic mirror (right side of the picture). The supersonic nozzle (shown in the middle of the picture) is positioned with micron accuracy with a 3-axis micropositioner. The e-beam makes a small spot on a white flourescent (LANEX) screen, shown in the upper left-hand corner of the picture. (Reproduced with permission from Umstadter D (2001) Review of physics and applications of relativistic plasmas driver by ultra-intense lasers. *Physics Plasmas* 8: 1774, with permission from the American Institute of Physics.)

smaller than the plasma wave wavelength ($r_1 \ll \lambda_p$) and thus the transverse wakefield was much greater than the longitudinal wakefield.

A typical experimental setup, used to study electron acceleration, is shown in Figure 14.

Dramatic reduction of the angular divergence of a laser accelerated electron beam was observed with increasing laser power above the relativistic self-focusing threshold, as shown in Figure 15.

Interactions with Solid-Density Targets

The generation of electrons by high-intensity laser light interacting with solid targets can generate energetic X-rays, accelerate other types of particles and induce nuclear reactions, as illustrated in Figure 16. For instance, high-order harmonics have been generated by the oscillation of the critical density surface, in the so-called moving mirror model. Bright X-rays, originating from Bremstrahlung caused by electron collisions with high-*Z* atoms in solid targets, have created isotopes by means of photofission. Laser-accelerated electron energies and angular distributions have been inferred from analyzing (γ, n) and $(\gamma, 2n)$ reactions in composite Pb/Cu targets and in Ta/Cu targets. Positrons were created by colliding laser-accelerated electrons with a tungsten target.

When electrons are heated to high temperatures or accelerated to high energies, they can separate from plasma ions. Such charge displacement creates an electrostatic sheath, which eventually accelerates the ions. The ions are pulled by the charge of the electrons and pushed by the other ions' unshielded charges (similar to the 'Coulomb explosion' that can occur during the ionization of atoms). When the charge displacement is driven by thermal expansion, as in long-pulse (low-power) laser–plasma experiments, the maximum ion energies are limited to less than 100 keV. However, when the charge displacement is driven by direct laser heating, as in short-pulse high-power laser–plasma experiments, multi-MeV ion energies are possible. This was first shown with gas jet targets, in which case the ions were accelerated radially into 2π, and then later with thin solid-density-films, in which case the ions were accelerated into collimated beams. In the latter case, hydrocarbons and water on the surface of the film can become ionized and provide a source of protons to be accelerated.



Figure 15 Images of the spatial profiles of the electron beam measured by a ccd camera imaging a LANEX screen at a distance of 15 cm from the gas jet for various laser powers. The divergence angle of the beam decreases to a value of $\Delta\theta = 1^\circ$ at a power of 2.9 TW, corresponding to a transverse geomtrical emittance of just $\varepsilon_\perp \lesssim 0.06\pi$ mm-mrad. (Reproduced with permission from Umstadter D (2001) Review of physics and applications of relativistic plasmas driver by ultra-intense lasers. *Physics Plasmas* 8: 1774, with permission from the American Institute of Physics.)

An intense laser can ponderomotively heat electrons. If the laser contrast is high, vacuum heating can occur in the following manner. When light encounters a sharp interface between vacuum and solid density, the electromagnetic field becomes evanescent in the region above the critical density. The instantaneous '$v \times B$' force can push electrons in the direction of the light's propagation vector; it also has a frequency twice that of the pump and a magnitude proportional to the square of the normalized vector potential, a_0^3. Thus, electrons can only complete half of their figure-eight orbits, on the vacuum side, gaining relativistic energies; they move through the overdense region without the electromagnetic field to pull them back. An electrostatic sheath can thus form, which will accelerate the ions left behind. Another important heating mechanism is stochastic heating, which occurs when the light that is reflected from the critical surface beats with the incoming wave to create a standing wave. The motion of electrons in such a wave can become chaotic, resulting in a large increase in electron temperature (>100 keV).

As the heated electrons propagate through a solid, they can instantaneously field-ionize the neutral atoms of the solid. This will both modify the solid's



Figure 16 Illustration of the various mechanisms of particle acceleration and X-ray generation in high-intensity laser interactions with solid-density targets. (Courtesy of R. Sauerbrey.)

conductivity and provide a source of protons on the rear-side of the target. If the film is thin enough, the electrons can pass through, and create a sheath on the rear-side of the target. This latter mechanism has been dubbed the target normal sheath acceleration mechanism. The ions from thin foils have been claimed to originate from both the front and rear-side of the foil.

Several groups have reported the observation of ions originating from thin-film solid-density targets. Unlike previous long-pulse experiments, the ions were accelerated along the direction normal to the side of the target, that is opposite to that upon which the laser was incident. The ions generally originate from water or hydrocarbons on the surface of the material. The acceleration results from several different mechanisms, which may be occurring simultaneously. Charge-displacement is again common to all, with the electrons being heated ponderomotively, such as by Brunel, $J \times B$ or stochastic heating. In one case, the electrostatic sheath is formed at the backside of the ionization layer formed on the side of the target upon which the laser is incident (front side). In another case, the electrostatic sheath is formed by field ionization of the ion layer on the opposite side of the thin film target (back-side), the target normal sheath acceleration (TNSA) hypothesis. Numerical simulations show evidence for both front- and back-side acceleration.

The results of these experiments indicate that a large number of protons (10^{13} p) can be accelerated, corresponding to source current densities (10^8 A/cm^2) that are nine orders of magnitude higher than produced by cyclotrons, but with comparable, or even lower, transverse emittances ($\varepsilon_\perp \leq 1.0\pi$ mm-mrad). Proton energies up to 60 MeV have been observed in experiments at intensities exceeding 10^{20} W/cm^2 (using a petawatt power laser). The high end of the proton spectrum typically has a sharp cut-off, but is a continuum. In one experiment, protons were observed to be emitted in ring patterns, the radii of which depend on the proton energy, which was explained by self-generated magnetic fields.

A typical experimental setup used to observe the acceleration of ions is shown in Figure 17. The production of radionuclides have been used as an ion energy diagnostic. In another example of a nuclear reaction initiated by an intense laser, neutrons



Figure 17 Artistically enhanced photograph of the typical setup used to observe the acceleration of ions. The laser (shown in the foreground) is focused with an off-axis parabola onto a thin-foil, held by a mesh that is positioned by a 3-axis micropositioner. CR-39, a nuclear track detector (shown in the background) is used to detect the ions. An actual proton-produced pattern is shown in red. (Reproduced from Umstadter D (2001) Review of physics and applications of relativistic plasmas driver by ultra-intense lasers. *Physics Plasmas* 8: 1774, with permission from the American Institute of Physics).



Figure 18 Photograph of a laser interacting with a deuterium cluster jet emanating from cooled gas nozzle. Fusion neutrons are produced with relatively low laser intensities. (Reproduced with permission from Ditmire T (2002) Laser fusion on a tabletop. *Optics and Photonics News* 13: 28, with permission from IEEE.)

have been produced by the He fusion reaction in the focus of 200 mJ, 160 fs Ti:sapphire laser pulses on a deuterated polyethylene target. Optimizing the fast electron and ion generation by applying a well-defined prepulse led to an average rate of 140 neutrons per shot. Neutrons have also been generated from cluster plasmas, which were produced by the cooled-nozzle depicted in Figure 18, but with significantly lower laser intensities than required with planar solid targets.

Concluding Remarks

The field of nonlinear optics, with electrons bound to atoms, has over the last forty years given rise to many scientific discoveries and technologies that are now commonplace. The relatively young field of relativistic nonlinear optics has already begun to do the same. Some of the exciting phenomena and applications that have already been identified have been discussed in this article. Others await discovery as ever higher laser intensities are reached, with no foreseeable limit.

See also

Fiber and Guided Wave Optics: Nonlinear Optics. **Scattering:** Raman Scattering.

Further Reading

Chen S-Y, Maksimchuk A and Umstadter D (1998) Experimental observation of relativistic nonlinear Thomson scattering. *Nature* 396: 653.

Cowan TE, Hunt AW, Phillips TW, Wilks SC, Perry MD, Brown C, Fountain W, Hatchett S, Johnson J, Key MH, Parnell T, Pennington DM, Snavely RA and Takahashi Y (2000) Photonuclear fission from high energy electrons from ultraintense laser–solid interactions. *Physics Review Letters* 84: 903.

Ditmire T (2002) Laser fusion on a tabletop. *Optics and Photonics News* 13: 28.

Eberly JH (1986) Fundamentals of laser interactions, vol. 229 of lecture notes in physics. *Journal Optical Society of America B* 3: 1324.

Esarey E, Sprangle P, Krall J and Ting A (1996) Overview of plasma-based accelerator concepts. *IEEE Transactions on Plasma Science* 24: 252.

Gibbon P and Förster E (1996) Short-pulse laser–plasma interactions. *Plasma Phys. Controlled Fusion* 38: 769.

Hartemann F (2001) *High-Field Electrodynamics*. Boca Raton: CRC Press.

Joshi CJ and Corkum PB (1995) Interactions of ultra-intense laser light with matter. *Physics Today* 48: 36.

Lau Y, He F and Umstadter D (2003) Nonlinear Thomson scattering: A tutorial. *Physics Plasmas* 10: 2155.

Ledingham KWD, Spencer I, McCanny T, Singhal RP, Santala MI, Clark E, Watts I, Beg FN, Zepf M, Krushelnick K, Tatarakis M, Dangor AE, Norreys PA, Allott R, Neely D, Clark RJ, Machacock AC, Wark JS, Cresswell AJ, Sanderson DCW and Magill J (2000) Photonuclear physics when a multiterawatt laser pulse interacts with solid targets. *Physics Review Letters* 84: 899.

Luther-Davies B, Gamaly EG, Wang Y, Rode AV and Tikhonchuk V (1992) Matter in ultrastrong laser fields. *Soviet Journal Quantum Electronics* 22: 289.

Marquès JR, Dorchies F, Audebert P, Ceindre JP, Amiranoff F, Gauthier JC, Hammoniaux G, Antonetti A, Chessa P, Mora PTM and Antonson J (1997) Frequency increase and damping of nonlinear electron plasma oscillations in cylindrical symmetry. *Physics Review Letters* 78: 3463.

Meyer-ter-Vehn J, Pukhov A and Sheng Z-M (2001) Relativistic laser plasma interaction. In: Batani D (ed.) *Atoms, Solids and Plasmas in Super-Intense Laser Fields*, pp. 167. New York: Kluwer Academic–Plenum.

Moore CI, Knauer JP and Meyerhofer DD (1995) Observation of the transition from Thomson to Compton scattering in multiphoton interactions with low-energy electrons. *Physics Review Letters* 74: 2439.

Mourou G and Umstadter D (1992) Development and applications of compact high-intensity lasers. *Physics Fluids B* 4: 2315.

Mourou GA and Umstadter D (2002) Extreme light. *Scientific America* 81.

Mourou GA, Barty CPJ and Perry MD (1998) Ultrahigh-intensity lasers: Physics of the extreme on a tabletop. *Physics Today* 22.

Siders CW, Blanc SPL, Fisher D, Tajima T, Downer MC, Babine A, Stepanov A and Sergeev A (1996) Laser wakefield excitation and measurement by femtosecond longitudinal interferometry. *Physics Review Letters* 76: 3570.

Sprangle P, Peñano JR, Hafizi B, Hubbard RF, Ting A, Gordon DF, Zigler A and Antonsen TM (2002) GeV acceleration in tapered plasma channels. *Physics Plasmas* 9: 2364.

Tajima T and Mourou G (2002) Zettawatt-exawatt lasers and their applications in ultrastrong-field physics. *Physics Review STAB* 5: 031301.

Umstadter D (2001) Review of physics and applications of relativistic plasmas driver by ultra-intense lasers. *Physics Plasmas* 8: 1774.

Umstadter D (2003) Relativistic laser–plasma interactions. *Journal Physics D: Applied Physics* 36: R151–R165.

Umstadter D and Norris TB (eds) (1997) Nonlinear optics with relativistic electrons. *IEEE Journal Quantum Electronics* 33: 1878.

Wagner R (1998) Laser–plasma electron accelerators and nonlinear relativistic optics. PhD thesis, University of Michigan.

Wagner R, Chen S-Y, Maksimchuk A and Umstadter D (1997) Electron acceleration by a laser wakefield in a relativistically self-guided channel. *Physics Review Letters* 78: 3125.

Yamakawa K (2004) Table-top lasers create ultrahigh peak powers. *OYOBUTURI* 73: 186–193.

S

SCATTERING

Contents

Raman Scattering
Scattering from Surfaces and Thin Films
Scattering Phenomena in Optical Fibers
Scattering Theory
Stimulated Scattering

Raman Scattering

F Kannari, Keio University, Yokohama, Japan

© 2005, Elsevier Ltd. All Rights Reserved.

When an electromagnetic wave passes over a small elastically bound charged particle, the particle will be set into motion by the electric field. Scattering takes place for frequencies not corresponding to the natural frequencies of the particles. If the particle is bound by a force obeying Hooke's law, this vibration will have the same frequency and spatial direction as that of the electric force in the electromagnetic wave. The phase, on the other hand, of the forced vibration will differ from that of the incident wave, which causes the basis of dispersion. If the charged oscillation is bound by a force which does not obey Hooke's law, but some more complicated law, it will reradiate not only the impressed frequency, but also various combinations of this frequency with the fundamental and overtone frequencies of the oscillator.

The Raman effect was discovered by C.V. Raman (1888–1971). Ordinary Raman spectroscopy is used as a tool for studying the vibrational energy levels of molecules and of lattice optical branch vibration in crystals. A spectroscopic measurement of the scattered light reveals the existence of frequencies shifted down by increments corresponding to vibrational frequencies of the material. This down-shifted scattering is referred to as Stokes scattering. Frequencies shifted up by the vibrational frequencies are also present in the scattered radiation, which are the so-called anti-Stokes scattering.

Stimulated amplification of scattered Stokes radiation occurs through a third-order nonlinear process. To introduce stimulated Raman scattering (SRS), first we describe the steady-state stimulated scattering theory.

In general, nonlinear optical processes are described by the classical Maxwell equation with the nonlinear polarization of a material $\mathbf{P}^{\mathrm{NL}}$:

$$\nabla \times \nabla \times \mathbf{E} + \varepsilon \mu_0 \frac{\partial^2 \mathbf{E}}{\partial t^2} = -\mu_0 \frac{\partial^2 \mathbf{P}^{\mathrm{NL}}}{\partial t^2} \qquad [1]$$

where ε and μ_0 are the linear dielectric constant of the material and the magnetic permeability of the vacuum. We consider a relatively intense excitation radiation $\mathbf{E}_{\mathrm{L}}$ (frequency ω_{L}) and a weak signal radiation $\mathbf{E}_{\mathrm{S}}$, having the carrier frequency ω_{s} corresponding to the scattered light frequency ($\omega_{\mathrm{s}} = \omega_{\mathrm{L}} - n\omega_0$);

$$\mathbf{E}_{\mathrm{L}} = \frac{1}{2}\{\bar{\mathbf{E}}_{\mathrm{L}}(\mathbf{r}, t) \exp \mathrm{i}(\mathbf{k}_{\mathrm{L}} \times \mathbf{r} - \omega_{\mathrm{L}} t) + \mathrm{c.c.}\} \qquad [2]$$

$$\mathbf{E}_{\mathrm{S}} = \frac{1}{2}\{\bar{\mathbf{E}}_{\mathrm{S}}(\mathbf{r}, t) \exp \mathrm{i}(\mathbf{k}_{\mathrm{S}} \times \mathbf{r} - \omega_{\mathrm{S}} t) + \mathrm{c.c.}\} \qquad [3]$$

where $\bar{\mathbf{E}}_L(\mathbf{r},t), \bar{\mathbf{E}}_S(\mathbf{r},t)$ are a slowly varying envelope of the complex electric fields. Assuming that the variation of the electric field during the time-scale shorter than the decay time of the induced oscillation in the material is negligible, nonlinear polarization induced by the excitation radiation is described as follows:

$$\mathbf{P}_S^{NL} = \frac{1}{2}\{\bar{\mathbf{P}}_S^{NL}(\mathbf{r},t)\exp \mathrm{i}(\mathbf{k}_S \times \mathbf{r} - \omega_S t) + \text{c.c.}\} \qquad [4]$$

$$\bar{\mathbf{P}}_S^{NL} = \varepsilon_0 \chi^{NL}(-\omega_S, -\omega_L, \omega_L, \omega_S)\bar{\mathbf{E}}_L^* \bar{\mathbf{E}}_L \bar{\mathbf{E}}_S \qquad [5]$$

where ε_0 is the vacuum dielectric constant and $\chi^{NL}(-\omega_S, -\omega_L, \omega_L, \omega_S)$ is the third-order nonlinear susceptibility, of which the real part corresponds to the variation of the dielectric constant depending on the optical radiation, whereas the imaginary part describes the stimulated scattering. In steady-state approximation, substituting eqns [3]–[5] into [1], we obtain

$$\frac{\mathrm{d}\bar{\mathbf{E}}_S}{\mathrm{d}z} = \frac{1}{2}\left(-a + \mathrm{i}\frac{\omega_S}{cn_S}\chi^{NL}|\bar{\mathbf{E}}_L|^2\right)\bar{\mathbf{E}}_S \qquad [6]$$

where we ignore the higher-order differential of amplitude. n_S is the refractive index at ω_S, and a is the linear absorption coefficient of the signal radiation. When ignoring the decay of the excitation radiation along the z direction in the material, for making the right-hand term of eqn [6] positive, the next condition must be satisfied:

$$I_L = \frac{1}{2}c\varepsilon_0 n_L |\bar{\mathbf{E}}_L|^2 \geq I_L^{th} = \frac{c^2\varepsilon_0 n_S n_L}{2\omega_S}\frac{a}{-\operatorname{Im}\chi^{NL}} \qquad [7]$$

The signal radiation is then amplified along the z direction at an amplification constant of g,

$$G = g(I_L - I_L^{th}) \qquad [8]$$

$$g = \frac{\omega_S}{c^2\varepsilon_0 n_S n_L}(-\operatorname{Im}\chi^{NL}) \qquad [9]$$

Stimulated Raman Scattering

In SRS, the frequency difference $\omega_L - \omega_S$ corresponds to the resonance frequency of vibrational oscillation ω_V. Therefore, the vibrational oscillation mode is excited in the material as well as the generation of scattered radiation. In the following section, we consider the SRS by optical phonon. In general, nonlinear polarization under the optical excitation is described as follows:

$$\mathbf{P}^{NL} = N_0 \alpha' q \mathbf{E}, \qquad [10]$$

$$\ddot{q} = \Gamma_V \dot{q} + \omega_V^2 q = \frac{1}{2}\alpha' \mathbf{E}^2 \qquad [11]$$

where q is the basic coordinate of molecular vibration, Γ_V is the decay rate of the vibrational oscillation, $\alpha' = (\partial\alpha/\partial q)_0$ is the Raman polarizability of a molecule, and N_0 is the molecule density. We can obtain the steady-state nonlinear polarization from eqns [4], [5], [10], and [11] as

$$\begin{aligned}\chi^{NL} &= (-\omega_S, -\omega_L, \omega_L, \omega_S) \\ &= \frac{N_0(\alpha')^2}{4\varepsilon_0}\frac{1}{\omega_V^2 - \omega^2 + \mathrm{i}\omega\Gamma_V}\end{aligned} \qquad [12]$$

where $\omega = \omega_L - \omega_S$. Thus, the gain coefficient can be obtained from eqns [9] and [12] under the assumption of $\omega_V \gg \Gamma_V$, as follows:

$$\begin{aligned} g_R(\omega_S) &= \pm\frac{N_0(\alpha')^2\omega_S}{2c^2\varepsilon_0 n_S n_L \omega_V \Gamma_V} \\ &\quad \times \frac{(\Gamma_V/2)^2}{(\omega_L - \omega_S \mp \omega_V)^2 + (\Gamma_V/2)^2}\end{aligned} \qquad [13]$$

In general, Raman scattering is characterized by the scattering cross-section $\mathrm{d}\sigma/\mathrm{d}\Omega$, which is defined for one of the optical polarization directions in terms of the optical power density:

$$\begin{aligned} & g_R(\omega_L - \omega_V) \\ &\quad = \frac{16\pi^2 c^2 N_0}{\hbar n_S^2 \omega_S^3 \Gamma_V}\frac{\mathrm{d}\sigma}{\mathrm{d}\Omega}\left\{1 - \exp\left(-\frac{\hbar\omega_V}{k_B T}\right)\right\}\end{aligned} \qquad [14]$$

The value of $(\mathrm{d}\sigma/\mathrm{d}\Omega)\Gamma_V^{-1}$ can be characterized as a peak intensity in the measured spontaneous Raman scattering spectrum.

When the conversion to the first Stokes wave is large, we must consider both pump depletion and conversion to higher-order Stokes waves (Figure 1a). Pump depletion in first Stokes generation can be accounted for by solving the following coupling



Figure 1 Energy diagrams of stimulated Raman scattering: (a) first Stokes scattering; (b) cascaded second Stokes scattering; and (c) first anti-Stokes scattering.

equations between pump power and Stokes power:

$$\frac{\partial I_{\mathrm{L}}}{\partial z} + \frac{n_{\mathrm{L}}}{c}\frac{\partial I_{\mathrm{L}}}{\partial t} = -g_{\mathrm{L}} I_{\mathrm{L}} I_{\mathrm{S}} \qquad [15]$$

$$\frac{\partial I_{\mathrm{S}}}{\partial z} + \frac{n_{\mathrm{S}}}{c}\frac{\partial I_{\mathrm{S}}}{\partial t} = g_R I_{\mathrm{L}} I_{\mathrm{S}} \qquad [16]$$

where

$$g_{\mathrm{L}} = \frac{\omega_{\mathrm{L}}}{\omega_{\mathrm{S}}} g_{\mathrm{R}}$$

In SRS the power generated in the first Stokes serves as a pump for a second Stokes wave (Figure 1b). Cascade shifts of this type, in which the Stokes wave of order n serves as a pump for the generation of the Stokes wave order $n+1$, can result in the generation of radiation at several frequencies, each one shifted from the original pump frequency by a multiple of the vibrational mode frequency. In addition to the cascade higher-order Stokes generation, multiple Stokes orders can also be generated by four-wave mixing interactions (Figure 2), of the form:

$$\omega_{\mathrm{S},n+1} = 2\omega_{\mathrm{S},n} - \omega_{\mathrm{S},n-1} \qquad [17]$$

These interactions are important when the wavevector mismatch among the various waves is small. In most media exhibiting positive dispersion, the phase matching of the various interactions involves off-axis components of the generated waves. Thus, these four-wave mixing interactions are stronger for tightly focused beams than for collimated pump beams.



Figure 2 Vector diagram of multiple Stokes generation through four-wave mixing in positively dispersive media.

SRS can be realized in a variety of configurations, including single pass Raman generation, or using a variety of extra-cavity or intra-cavity Raman resonator. Variation of the Raman cross-section for the wavelength is shown in Figure 3 for various gaseous Raman media. The Raman gain coefficient simply increases with decreasing wavelength, as indicted by eqn [13]. Therefore, higher conversion efficiencies are obtainable with UV lasers such as rare-gas halide excimer lasers in a single pass configuration. Note that in some gases, such as H_2, the Raman gain becomes independent of pressure at higher pressures since the increase in linewidth, due to pressure broadening, cancels the increase in gain originated from number density. Typical SRS gains for some gas, liquid, and solid media are listed in Table 1.

Although SRS in high-pressure gases has been widely employed for frequency conversion, SRS in crystals is currently a growing area of research activity. Table 2 lists SRS frequency shifts of various crystals. Since a very high pump laser power ~1 GW/cm², which is already close to the laser damage threshold of many crystals, solid-state Raman lasers are



Figure 3 Variation of the Raman cross-section with pump wavelength for various gases. Source: AIP Conference Proceedings No. 100 (Excimer Laser – 1983), 181.

Table 1 Typical Raman media and their parameters

Materials	*Stokes shift (cm^{-1})*	*Raman linewidth (cm^{-1})*	$N\frac{d\sigma}{d\Omega}$ *(10^{-6} m^{-1} str^{-1})*	*Raman gain (10^{-5} m/MW)*
H_2 (100 atm)	4155	0.20	3.0×10^3	1.5
H_2O	3420	176	0.51	0.07
Acetone CH_3COCH_3	2921	18	5.4	1.2
Cyclohexane C_6H_{12}	2852	11	3.7	1.2
Liquid N_2	2326.5	0.067	0.29 ± 0.09	17.5 ± 5
Liquid O_2	1552	0.117	0.48 ± 0.14	14.5 ± 4
Nitrobenzene $C_6H_5NO_2$	1345	6.6	6.4	2.1
Toluene C_7H_8	1003	1.94	1.1	1.2
C_6H_5Cl	1002	1.6	1.5	1.9
C_6H5Br	1000	1.9	1.5	1.5
C_6H_6	992	2.15	3.06	2.8
CS_2	655.6	0.5	7.55	23.8
CC_{l4}	459	5	2.3	0.85
Diamond	1332	2.04	17	6.9
Calcite	1086	1.1	2.9	4.4
Si	521	0.8	305	190
Quartz	467	6.7	3.1	0.8
Li^7TaO_3	201	22	238	4.4
	215	12	167	10
Li^7NbO_3	256	23	381	8.9
	258	7	262	28.7
	637	20	231	9.4
	643	16	231	12.6
InSb ($n_e \sim 2 \times 10^{22}$ m^{-3})	100	2	30	16.7

designed with an intra-cavity, coupled cavities, or an extra-cavity. Efficient Raman lasers have been demonstrated using external resonator configuration when the pumping pulse is intense enough. For example, ~40% conversion efficiency to S1 was reported with a Q-switched frequency doubled Nd:YAG laser in a $Ba(NO_3)_2$ crystal using a pump fluence of 1.4 J cm^{-1} and a pulse repetition rate of 30 Hz. The resonator mirror characteristics can be designed to enhance the desired Stokes-order radiation by completely confining the lower-order Stokes radiation inside the cavity. For a lower power pump source, such as cw-pumped Q-switch lasers, a Raman crystal is placed inside a pump laser resonator to reduce the effective threshold for SRS. The resonator configuration has a significant influence on the Stokes output performance. The optimum spot size in the resonator and power density in the Raman crystal is a compromise between maximizing the conversion efficiency and avoiding optical damage. It is noteworthy that the thermal lens in the Raman crystal is caused by the energy dissipation of the phonon and thus depends on the power density of the Stokes field.

A fiber Raman laser is an optical fiber with pump light focused into one end and SRS light appearing at the output. By injecting a weak frequency-shifted signal light together with the pump light, the signal light experienced substantial amplification along the length of the fiber. This fiber Raman amplifier has been actively developed to extend the wavelength band for optical fiber communication. The fiber Raman lasers have utilized fused silica (SiO_2), germanosilicate, or phosphosilicate optical fibers for which the Raman frequency shifts are ~440–490 cm^{-1}. In contrast to Erbium-doped fiber amplifier (EDFA), since the single mode fiber itself can act as an amplifier, the Raman amplifier can be distributed over optical transmission lines in lengths of >20 km, which can keep the transmission power always nearly constant and consequently reduce the signal noise. Moreover, by preparing multipumping wavelengths, the number of signal wavelengths can increase without the limitation of an amplification gain bandwidth. High-power light sources around 1480 nm developed for EDFA can be utilized by the fiber Raman amplifier. By tailoring the power levels among multiwavelength pump lights, a flat amplification gain spectral width of ~100 nm is obtainable.

Transient Effects

In the steady-state SRS analysis, we assume that the pump pulse duration is much longer than the vibrational mode dephasing time ($\Delta\nu_p \ll \Gamma_V$). In a transient regime, when the pump pulse duration is shorter than the dephasing time ($\Delta\nu_p \gg \Gamma_V$), the effect of the transient response of the medium reduces the gain and delays the Stokes pulse relative to the pump pulse. With no pump depletion, the analytical expression for the Stokes intensity for large

Table 2 Typical solid-state Raman materials and parameters

Materials	*Stokes shift (cm^{-1})*	*Raman linewidth (cm^{-1})*	*$\frac{d\sigma}{d\Omega}$ (arb.u.)*
Diamond	1332.9	2.7	100
SO_2	464.5	7.0	2.2
Nitrates and calcite			
$Ba(NO_3)_2$	1048.6	0.4	21
$NaNO_3$	1069.2	1.0	23
$CaCO_3$	1086.4	1.2	6.0
Tungstates			
$CaWO_4$	910.7	4.8	47
$SrWO_4$	921.5	3	–
$BaWO_4$	926.5	2.2	–
$NaY(WO_4)_2$	918	15	–
$KGd(WO_4)_2$	901	5.4	54
$KGd(WO_4)_2$	901	5.4	43
$KGd(WO_4)_2$	768	6.4	19
$KGd(WO_4)_2$	768	6.4	65
$KY(WO_4)_2$	905.6	7	50
$KY(WO_4)_2$	905.6	7	45
$KY(WO_4)_2$	767.4	8.4	20
$KY(WO_4)_2$	767.4	8.4	64
$KYb(WO_4)_2$	908	7.4	48
$KYb(WO_4)_2$	908	7.4	48
$KYb(WO_4)_2$	757	15	25
$KYb(WO_4)_2$	757	15	70
Molybdates			
$CaMoO_4$	879.3	5.0	64
$SrMoO_4$	887.7	2.8	55
$BaMoO_4$	892.4	2.1	52
Iodate and niobates			
$LiIO_3$	821.6	5.0	54
$LiNO_3$	872	21.4	44
$LiNbO_3$	632	27	166
$LiNbO_3$	250	28	–
$LaNbO_4$	805	9	22
Phosphates			
$Ca_2(PO_4)_3F$	964.7	2.8	3.4
$Sr_5(PO_4)_3F$	950.3	2.8	3.4

amplification gain is given as

$$I_S(\ell) \propto I_S(0)\exp\left(-\frac{\tau_p}{T_V}\right) \times \exp\left\{2\left[I_L\tau_p\ell\frac{16\pi^2c^2N_0}{\hbar n_S^2\omega_S^3}\left(\frac{d\sigma}{d\Omega}\right)\right]^{1/2}\right\} \qquad [18]$$

Here, T_V is the dephasing time ($T_V = \pi\Gamma_V^{-1}$), and τ_p is the pump pulse width. One can see that the Raman gain is proportional to the square root of the multiplication of the pump pulse energy $I_L \times \tau_p$, the crystal length ℓ, and the total integral Raman scattering cross-section ($d\sigma/d\Omega$), but does not depend on the Raman linewidth Γ_V.

Anti-Stokes Raman Scattering

From eqn [13] the gain coefficient is negative at $\omega = \omega_L + \omega_S$. However, anti-Stokes scattering (Figure 1c) is stimulated through a four-wave mixing interaction of the form:

$$\omega_A = 2\omega_L - \omega_S \qquad [19]$$

The equations describing anti-Stokes Raman scattering in the absence of pump depletion are:

$$\frac{d\bar{E}_S}{dz} + \frac{a}{2}\bar{E}_S = i\frac{\omega_S^2}{2c^2\varepsilon_0 k_{Sz}}\bar{P}_S^{NL} \qquad [20]$$

$$\frac{dE_A^*}{dz} + \frac{a}{2}\bar{E}_A^* = -i\frac{\omega_A^2}{2c^2\varepsilon_0 k_{Az}}\bar{P}_A^{NL*} \qquad [21]$$

$$\bar{P}_S^{NL} = \varepsilon_0\chi^{NL}\left\{|\bar{E}_L|^2\bar{E}_S + \bar{E}_L^2\bar{E}_A^*\exp(i\Delta kz)\right\} \qquad [22]$$

$$\bar{P}_A^{NL*} = \varepsilon_0\chi^{NL}\left\{\bar{E}_L^{*2}\bar{E}_S\exp(-i\Delta kz) + |\bar{E}_L|^2\bar{E}_A^*\right\} \qquad [23]$$

Here, Δk is the wavevector mismatch, given by

$$\Delta k = k_S + k_A - 2k_L \qquad [24]$$

Then, power gain per unit length is obtained to give

$$G \cong -a \pm 2\,\mathrm{Im}\left\{\left(\frac{\Delta k}{2}\right)^2 - \frac{\omega_S}{2cn_S}\chi^{NL}|\bar{E}_L|^2\Delta k\right\}^{1/2} \qquad [25]$$

The interaction of the anti-Stokes wave with the other waves is stronger when the wavevector mismatch is small. The exact value of the phase-matching angle depends on the dispersion of the medium. At the tightly focused pumping condition, strong anti-Stokes radiation is generated so that the wavevector mismatch is minimum. Just as in Stokes scattering, multiple anti-Stokes orders can be generated (Figure 4).

So far, Stokes and anti-Stokes Raman scattering have been used to generate radiation over much of the UV and VUV, ranging from 138 to 400 nm. The shortest wavelength achieved in this manner is at 138 nm, generated by a seventh-order anti-Stokes shift in H_2 using 139 nm radiation of an ArF laser. In general, the pump intensity used in experiments with rare-gas halide excimer lasers was in the range of 100 MW/cm^2 to 5 GW/cm^2. The conversion efficiency and the distribution of power among the various Stokes and anti-Stokes



Figure 4 Vector diagram of anti-Stokes Raman scattering in positively dispersive media.

components depend on the focal geometry, and the extent of the spectrum could be varied by changing the gas pressure.

See also

Magneto-Optics: Cyclotron Resonance, Interband Magnetoabsorption, Spin Flip Raman Scattering. **Nonlinear Optics, Applications:** Raman Lasers.

Further Reading

Basiev TT, Sobol AA, Zverey PG, Ivleva LI, Osiko VV and Powell RC (1999) Raman spectroscopy of crystals for stimulated Raman scattering. *Optical Matters* 11: 307.

Bischel WK and Blach G (1983) New lines in the UV: SRS of excimer laser wavelengths. *AIP Conference Proceedings No. 100 (Excimer Lasers-1983)*, 181.

Loree TR, Sze RC, Barker DL and Scott PB (1979) *IEEE Journal of Quantum Electronics* QE-15: 337.

Reinties JF (1985) Coherent ultraviolet and vacuum ultraviolet sources. In: Laser Bass M and Stitch ML (eds) *Laser Handbook*. Amsterdam: North-Holland Physics Publishing.

Weber MJ (ed.) (2001) Raman, Brillouin and Soliton lasers. In: *Handbook of Laser*, p. 291. Boca Raton, FL: CRC Press.

Scattering from Surfaces and Thin Films

A Duparré, Fraunhofer Institut IOF, Jena, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The quality of optical components can be critically limited by light scattering. The majority of these components, such as lenses, mirrors, beamsplitters, and polarizers are covered with thin film optical coatings. To reduce scattering losses, their main sources and mechanisms must be known and, whenever possible, be controlled. Moreover, light scattering techniques have been widely recognized as a powerful tool for roughness and defect analysis as well as for general quality assessment.

Scattering can be divided into surface/interface scattering (SIS) and volume scattering (VS), attributed to the following scatter sources:

- roughness and surface defects of the substrate: SIS,
- surface/interface roughness and defects of the thin film coating: SIS,
- imperfections in the bulk substrate material: VS,
- intrinsic thin film morphology and defect structures: VS,
- surface contaminations: SIS.

Even though in particular cases and applications, VS can constitute the main scattering source, SIS largely dominates both substrate and thin film scattering losses. Studies into light scattering have widely focused on SIS effects from surface and interface micro-roughness. The theoretical outline given in the next section will also follow this concept in describing scattering from surface and interface roughness. It is emphasized, however, that volume scattering theories are accessible in the literature.

Light Scattering Models

Scattering from Rough Surfaces

A randomly rough surface can be considered as a Fourier series of sinusoidal waves with different amplitudes, periods, and phases. Following the grating equation, a single grating with spacing D causes scatter into the angle Θ according to

$$\sin \Theta = \lambda / D \qquad [1]$$

where λ is the wavelength of light. D represents one spatial wavelength in the Fourier series. Accordingly, $f = 1/D$ represents one single spatial frequency. A randomly rough surface contains many different spatial frequencies. This is quantitatively expressed by the power spectral density (PSD), giving the relative strength of each roughness component of a surface microstructure as a function of spatial frequency:

$$\mathrm{PSD}(\mathbf{f}) = \lim_{A\to\infty} \frac{1}{A} \left| \int_{\mathbf{A}} \zeta(\mathbf{r}) \exp(-2\pi i \mathbf{f}\cdot\mathbf{r}) d\mathbf{r} \right|^2 \qquad [2]$$

where $\zeta(\mathbf{r})$ represents the height of the surface roughness profile, $\mathbf{r}$ is the position vector, and $\mathbf{f}$ is the spatial frequency vector in the x–y plane. A is the area of the measured region $\mathbf{A}$. We confine our discussion to isotropic surfaces, which represent the majority of cases in optical surface and thin film scattering studies. Thus, a $\mathrm{PSD}(f)$ independent of the surface direction Φ of vector $\mathbf{f}$ is obtained by averaging the two-dimensional function $\mathrm{PSD}(\mathbf{f})$ over all surface directions after transformation into polar coordinates:

$$\mathrm{PSD}(f) = \frac{1}{2\pi} \int_0^{2\pi} \mathrm{PSD}(f, \Phi) d\Phi \qquad [3]$$

Well-established vector scattering theories developed, for instance, by Bousquet *et al.* or Elson provide the link between the PSD and the scattering intensity per solid angle of a surface:

$$\frac{\mathrm{d}P}{P_0\,\mathrm{d}\Omega} = F(\lambda, n, \Theta, \Phi)\mathrm{PSD}(f) \qquad [4]$$

This theory is valid for surfaces whose rms roughness is small compared to the wavelength. $\mathrm{d}P/(P_0\,\mathrm{d}\Omega)$ denotes the differential power scattered into the direction (Θ, Φ) per unit solid angle $\mathrm{d}\Omega = \sin\Theta\,\mathrm{d}\Theta\,\mathrm{d}\Phi$ divided by the incident power P_0. Θ and Φ are the polar and azimuthal angles of scattering, respectively. The optical factor F contains all information on the corresponding perfect surface (without the roughness properties), i.e., the refractive index n, wavelength, and the conditions of illumination and observation. Both backscattering and forward scattering can be expressed by eqn [4], according to the illumination and observation conditions chosen. Without loss of generality, all formulas have been written here for normal incidence. The formalism, however, allows consideration of all possible cases, including oblique angles of incidence and arbitrary polarization properties. $\mathrm{d}P/(P_0\,\mathrm{d}\Omega)$ is called angle resolved scattering (ARS) which is related to the well-established term BRDF/BTDF (bidirectional reflectance/transmittance distribution function) by multiplication with $\cos\Theta$:

$$\frac{\mathrm{d}P}{P_0\,\mathrm{d}\Omega} = \mathrm{ARS} = \mathrm{BRDF\ (or\ BTDF)}\cdot\cos\Theta \qquad [5]$$

Total scattering (TS), which is defined as the power P scattered into the backward or forward hemisphere divided by the incident power P_0 (see also section on scattering measurement below), is obtained by integrating eqn [4] over the forward or backward hemisphere:

$$\mathrm{TS} = 2\pi\int_0^{\frac{\pi}{2}}\left(\frac{\mathrm{d}P}{P_0\,\mathrm{d}\Omega}\right)\sin\Theta\,\mathrm{d}\Theta \qquad [6]$$

If the correlation length of surface roughness is much larger than the wavelength, scalar scattering theories like the one from Carniglia can also be employed. Moreover, in this case, the well-known simple approximate formula for total backscattering can be derived from both vector and scalar theories:

$$\mathrm{TS}_{\mathrm{back}} = R_0\left(\frac{4\pi\sigma}{\lambda}\right)^2 \qquad [7]$$

where σ is the rms roughness and R_0 the specular reflectance.

It must be emphasized that this formula is only valid if the above-mentioned condition is met and as long as only single surfaces without coatings are considered.

Scattering from Dielectric Thin Films

For surfaces coated with a dielectric single layer or multilayer, ARS for a system of N layers is given by

$$\frac{\mathrm{d}P}{P_0\,\mathrm{d}\Omega} = \sum_{i=0}^{N}\sum_{j=0}^{N} F_i F_j^* \mathrm{PSD}_{ij}(f) \qquad [8]$$

where F_i is the optical factor at the i-th interface and F_j^* is the conjugate complex number of the optical factor at the j-th interface. The optical factors include both the conditions of illumination and observation and the characteristics of the ideal multilayer (refractive indices, film thickness). PSD_{ij} are the power spectral densities of the corresponding interfaces. For $i \neq j$, they describe the roughness cross-correlation between two interfaces.

From eqn [8] it becomes obvious that the scattering mechanism of coated surfaces is considerably more complex as compared to single surfaces.

The amplitudes of the scattered fields from all individual interfaces add up to the total scatter. In particular, the cross-correlation properties between the interface roughness profiles significantly determine the overall total scatter. So even for coatings having the same statistical roughness, the scatter losses can differ drastically when the cross-correlation between the interfaces is different. An example is demonstrated in a model calculation of total backscattering for $\lambda = 632.8$ nm in Figure 1.



Figure 1 Calculated ratio of the total backscattering of a single high index layer ($n = 2.4$) on BK7 substrate ($n = 1.52$) to the scattering of the bare substrate as a function of optical thickness nd. (QWOT: quarter wave optical thickness). rms roughness was 1 nm, correlation length 1 μm for both the substrate–film and film–air interfaces. Full line: full interface cross-correlation. Dashed line: zero interface cross-correlation. Lower dashed line: bare substrate.

A thin film with refractive index $n = 2.4$ (typical for Titania films), and continuously increasing thickness, was modeled onto a BK 7 substrate ($n = 1.52$). Gaussian autocovariance functions with an rms roughness $\sigma = 1$ nm and a correlation length $\tau = 1$ μm were chosen for both the substrate–film and film–air interfaces. Only the cross-correlation function was varied. The two extreme cases of fully uncorrelated and fully correlated interfaces are depicted in the figure and related to the scattering of the bare substrate (TS_0). As a result of scattering interference effects, in both cases the scattering varies periodically with optical film thickness. The appearance of maxima and minima as well as the total amount of scattering crucially depends on the type of cross-correlation.

These effects have to be taken into careful deliberation whenever scattering in dielectric thin film coatings is considered. Otherwise, misinterpretation of the scatter loss origin is possible and may result in unsuitable technological attempts to minimize scatter losses.

Instrumentation for Light Scattering Measurement

Types of Measurements

Light scattering experiments on optical surfaces and thin films are, in most cases, either performed as ARS measurements using goniophotometers, or the scattering is collected over the backward and forward hemispheres yielding total integrated scattering (TIS) or TS. The latter can be measured either by using a Coblentz sphere or an integrating sphere (see schematic picture in Figure 2).

As Coblentz spheres image the scattered radiation directly onto the detector, they are much less sensitive to scattering by air particles than integrating spheres. So if super-smooth samples with scattering levels in the visible range of 1 ppm and lower shall be measured, integrating spheres require operation in vacuum or He-gas atmosphere whereas Coblentz spheres can still be used under usual clean room conditions.

Angle Resolved Scattering (ARS)

Sophisticated instruments for ARS measurements have been established in a number of laboratories. Most frequently the systems are operated at the He–Ne laser wavelength 632.8 nm, but also at 10.6 μm (CO_2 laser), 325 nm (He–Cd laser), and yet other wavelengths. These techniques are versatile and powerful, but rather unsuitable for routine measurements. For single surfaces, PSD can be calculated from such measurements. A standard procedure for ARS measurements is defined in ASTM standard E 1392 and was successfully verified in various round-robin experiments at different wavelengths. Figure 3 shows the photograph of a typical instrumentation.

The main parts of this setup are the illumination system and a double goniometer. The sample holder and the detector are each mounted on a precision goniometer. The detector head is located on the outer goniometer and can be revolved 360 degrees around the sample with an angular resolution of 0.01°. The performance of a scatterometer depends also considerably on the quality of the illumination system. Laser radiation passes several optical elements, such as a spatial filter, diaphragms, polarizers, and mirrors providing the high beam quality necessary for precision measurement.



Figure 2 Schematic picture of types of scattering measurement. ARS: angle resolved scattering, TIS, TS: total integrated scattering, total scattering.



Figure 3 Instrumentation for angle resolved scattering measurement (courtesy of Fraunhofer Institute for Applied Optics and Precision Engineering, Jena, Germany).

Total Scattering (TS)

TIS measurements collect the light scattered into the backward hemisphere and are defined as the backscattered radiation divided by the total reflectance. The TIS measurement procedure is prescribed in ASTM standard F 1048 which applies to opaque reflective surfaces. Transparent or semi-transparent samples such as substrates, AR coatings, and beamsplitters cannot be measured without ambiguous additional assumption. The new international standard ISO 13696 defines TS as the backscattered and forward scattered radiation P divided by the incident radiation P_0. TS is hence equivalent to the scattering loss of the component. Opaque as well as transparent surfaces and coatings can be measured both in the backward and forward directions. TS and TIS can, however, be converted into one another, if the reflectance of the sample is known. This standard procedure was proved in an international round-robin experiment at 632.8 nm.

An example of a facility for TS measurements, in a wide range of wavelengths, is given in Figure 4. The apparatus for total backscattering and forward scattering measurements is operated from 193 nm to 10.6 μm by using several lasers. The setup is based on a Coblentz sphere imaging the light scattered into the backward or forward hemisphere within an angular range from 2° to 85° onto the detector unit. This angular range complies with the specification given in ISO 13696.

A special arrangement allows easy change from the backscatter to forward scatter operation modus. The detector unit consists of the detector (photomultiplier in the UV, VIS, NIR, and HgCdTe-element in the IR) and a small integrating sphere. The latter is used for homogeneously illuminating the detector. At all wavelengths, the light beam is modulated by a chopper and passes a beam-cleaning element. The incident radiation hits the sample surface at nearly zero degrees and the specular beam is guided back through the entrance/exit aperture of the Coblentz sphere. While performing the measurement, the sample is scanned across its surface by a positioning system, yielding one- or two-dimensional scattering diagrams. Calibration is performed with a commercial diffusing (Lambertian) standard. Filters are used for attenuating the beam during measurement of high-scatter samples and diffuse reflectance standards. Background levels smaller than 0.1 ppm at 632.8 nm were achieved without the necessity of He-gas flow or operation in vacuum.

Whereas in the past the majority of such facilities were designed for the visible, infrared, and near-ultraviolet spectral regions, the increasing demands for low-scatter optical components in the vacuum ultraviolet (VUV) region for application in photolithography has driven the development of scattering facilities for wavelengths as short as 157 nm. Because of the enhanced technical effort needed for the development of VUV scattering measurement instrumentation, only few setups exist that can be operated at 157 nm.

Applications

Fields of Applications

There exists a diversity of purposes for light-scattering investigations of surfaces and thin films, which requires proper selection of the particular method. For a number of purposes, routine measurements without detailed understanding of the scatter sources can be sufficient, while other problems need deeper insight into the scatter mechanisms and hence, require the combination of measurement with theoretical modeling. It is up to the engineer or scientist to decide in each particular case, to which level the


Beam dump
Sample
Sample positioning system
Detector
Coblentz sphere
Signal evaluation
Signal processing
Spatial filter
Beam dump
Radiation sources
Chopper
Attenuator
Incident radiation detector

Figure 4 Schematic picture of an instrument for total scattering measurement (courtesy of Fraunhofer Institute for Applied Optics and Precision Engineering, Jena, Germany).

light-scattering study has to be extended. Examples for typical application tasks arising in industry and institutes are:

- determination of total scattering as an optical loss limiting the performance of a thin film component;
- surface finish assessment (roughness, defects) of optical substrates;
- study into the relation between scattering and the morphology and roughness of optical thin films as a precondition for optimizing deposition processes;
- assessment of cleanliness of coated components;
- detection of degradation effects in coatings and substrate materials;
- separation of interface scattering from the film and substrate;
- distinction of volume scattering from interface scattering in substrates and films.

Scattering measurements are noncontact, do not require sample preparation, enable rapid mapping of large sample areas, and are highly sensitive. This makes them usable for a large variety of applications extending from super-smooth substrates with surface roughness below 0.01 nm, thin film structures in the nanometer range, and small and large defect features up to rough engineering surfaces with micron roughness.



Figure 5 TS measurement (backscattering) on conventionally polished fused silica at 632.8 nm (2D-mapping) for surface quality assessment. Measurement performed with the TS instrument shown in Figure 4.

Examples of Measurements

Surface finish assessment

The result of a scattering measurement (TS, backscattering) at the He–Ne laser wavelength (632.8 nm), on conventionally polished fused silica, is shown in Figure 5. Symmetric defects, as well as scratch-like features, can be recognized in this diagram. The minimum and averaged rms-roughness determined from the minimum (defect-free) and averaged (including defects) scattering levels are 0.51 and 0.72 nm, respectively.

Scattering from thin film components

Figure 6 shows a TS measurement (backscattering) performed on a polished CaF_2 sample. Half of the area of one surface of this sample was coated with a fluoride multilayer mirror system designed for 248 nm. The area mapping of the TS measurement at 248 nm delivers information of both the bare substrate quality and the increase in scattering after coating. According to the explanations in the first section, this increase has to be interpreted as a result of two influences: the increased reflectance (i.e., changed optical factors) and the roughness growth during deposition of the multilayer (i.e., changed PSD).



Figure 6 TS measurement (backscattering) at 248 nm on a CaF_2 substrate half of which was coated with a fluoride multilayer mirror system designed for 248 nm. Measurement performed with the TS instrument shown in Figure 4.

On the basis of such measurements, detailed interpretation can be accomplished by additional roughness analysis using scanning force microscopy, subsequent scattering modeling employing the formulas given above, and comparison of the modeled and measured results.

ARS techniques can, for example, be employed to compare the angular distribution of the scattering of a coating to that of the bare substrate. Figure 7 displays ARS measurements in the backward hemisphere at 325 nm (He–Cd laser) on a fused silica substrate before and after deposition (magnetron sputtering) of a Ta_2O_5/SiO_2 quarterwave multilayer mirror (325 nm design wavelength). As with the example discussed above, the higher scatter of the multilayer is caused by both the optical factors and increased roughness. The slight bump at large scatter angles in particular reveals high spatial frequency roughness attributed to the film morphology.

Figure 8 displays TS measurements at 157 nm. The diagram contains one-dimensional scans of forward scattering from an uncoated CaF_2 substrate and an antireflective (AR) coating on CaF_2. The background signal level is also included.



Figure 7 ARS measurement at 325 nm (backward hemisphere) on a fused silica substrate before (lower curve) and after (upper curve) deposition of a Ta_2O_5/SiO_2 quarterwave multilayer mirror with 325 nm design wavelength. Measurements performed with the ARS instrument shown in Figure 3.



Figure 8 TS measurements at 157 nm (forward scattering): bare CaF$_2$ substrate, AR coating on CaF$_2$ and background scattering level. Measurements performed with the VUV total scattering instrumentation at the Fraunhofer Institute for Applied Optics and Precision Engineering, Jena, Germany.

List of Units and Nomenclature

Angle resolved scattering	[nondimensional]	ARS
Azimuthal scattering angle	[degree]	Φ
Correlation length	[nm]	τ
Differential scattered power	[nondimensional]	$dP/(P_0\, d\Omega)$
Grating spacing	[μm]	D
Height of surface roughness profile	[nm]	ζ
Incident power	[W]	P_0
Optical factor	[nm^{-4}]	F
Polar scattering angle	[degree]	Θ
Power spectral density	[nm^4]	PSD
Refractive index	[nondimensional]	n
Rms roughness	[nm]	σ
Spatial frequency	[μm^{-1}]	f
Specular reflectance	[nondimensional]	R_0
Total integrated scattering	[nondimensional]	TIS
Total scattering	[nondimensional]	TS
Wavelength	[nm]	λ

See also

Optical Coatings: Thin-Film Optical Coatings. **Semiconductor Physics:** Light Scattering.

Further Reading

Baeumer S, Duparré A, Herrmann T, *et al.* (1999) SLIOS – a contribution to standard procedures in stray light measurement. *Proceedings SPIE* 3739: 414–421.

Bennett JM and Mattsson L (1999) *Introduction to Surface Roughness and Scattering*, 2nd edn., pp. 28–35, 62–70. Washington, DC: Optical Society of America.

Bousquet P, Flory F and Roche P (1981) Scattering from multilayer thin films: theory and experiment. *Journal of Optical Society of America* 71: 1115–1123.

Carniglia CK (1979) Scalar scattering theory for multilayer optical coatings. *Optical Engineering* 18: 104–115.

Church L, Jenkinson HA and Zavada JM (1979) Relationship between surface scattering and microtopographic features. *Optical Engineering* 18: 125–136.

Duparré A (1995) Light scattering of thin dielectric films. In: Hummel RE and Günther KH (eds) *Thin Films for Optical Coatings*, pp. 273–303. Boca Raton, FL: CRC Press.

Elson JM (1984) Theory of light scattering from a rough surface with an inhomogeneous dielectric permittivity. *Physical Review B* 30: 5460–5480.

Elson JM and Bennett JM (1979) Vector scattering theory. *Optical Engineering* 18: 116–124.

Herman IP (1996) *Optical Diagnostics for Thin Film Processing*, pp. 522–529. London: Academic Press.

Kadkhoda P, Müller A, Ristau D, *et al.* (2000) International round-robin experiment to test the international organization for standardization total-scattering draft standard. *Applied Optics* 39: 3321–3332.

Kassam S, Duparré A, Hehl K, Bussemer P and Neubert J (1992) Light scattering from the volume of optical thin films: theory and experiment. *Applied Optics* 31: 1304–1313.

Leonhard TA and Rudolph P (1995) BRDF round robin test of ASTME 1392. *Proceedings SPIE* 1995: 285–293.

Macleod HA (2001) *Thin-Film Optical Filters*, 3rd edn., pp. 12–52. Bristol, UK and Philadelphia: Institute of Physics Publishing.

Rönnow D and Veszelei E (1994) Design review of an instrument for spectroscopic total integrated light scattering measurements in the visible wavelength region. *Review of Scientific Instruments* 65: 327–334.

Stover JC (1995) *Optical Scattering, Measurement and Analysis*, 2nd edn., pp. 133–176. Bellingham, CA: SPIE Press.

Van de Hulst HC (1957) *Light Scattering by Small Particles*, pp. 28–31, 63–84. London: Chapman and Hall Ltd.

Whitehouse DJ (1994) *Handbook of Surface Metrology*, pp. 49–60, 512–517. Bristol, UK and Philadelphia: Institute of Physics Publishing.

Scattering Phenomena in Optical Fibers

P Tchofo-Dinda and G Millot, Université de Bourgogne, Dijon, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Nonlinear phenomena that result from interaction of intense light beams with dielectric media can be broadly divided into two main categories: namely, parametric effects and scattering phenomena. Parametric effects arise whenever the state of the matter is left unchanged by the interaction, whereas scattering phenomena imply transitions between vibrational or rotational energy levels in the medium. The two dominant scattering phenomena in optical fibers are stimulated Raman scattering (SRS) and stimulated Brillouin scattering (SBS), which are nonlinear processes in which a part of the energy propagating at a given frequency is converted into one or several down-shifted Stokes beams, through interaction with the vibrational modes of the materials. Although SBS and SRS phenomena are beneficial for developing all-optical fiber lasers and amplifiers for long-haul fiber transmissions, they are detrimental to transmission of ultrashort light pulses in silica fibers. In this article we describe the fundamental aspects of SBS and SRS.

General Features

Three well-known kinds of scattering phenomena in optical fibers are Rayleigh, Raman and Brillouin scattering. Although these three phenomena manifest themselves in qualitatively different ways, all of them originate fundamentally from the effects of a light wave on the atomic and molecular charges of the dielectric medium. The Raman and Brillouin scattering phenomena involve the vibrational modes of the material that are associated with the optical and acoustic branches of the dispersion curve of the material, respectively. Such vibrational modes, called phonons, are schematically represented in Figure 1 with the help of typical dispersion curves of a one-dimensional atomic lattice.

In standard silica fibers (SiO_2), the phonons associated with the optical branch correspond to intramolecular vibrations, which give rise to the Raman scattering phenomenon, whereas those associated with the acoustic branch correspond to intermolecular vibrations, which are responsible for Brillouin scattering. In either of these two scattering processes, part of the energy of the incoming light, which propagates at a given frequency ω, is converted into downshifted (Stokes) or upshifted (anti-Stokes) light waves, at frequencies $\omega - \Omega$ and $\omega + \Omega$, respectively. The frequency shift Ω is determined by the vibrational modes involved in the scattering process. Figure 2 represents schematically



Figure 1 Schematic representation of the dispersion curves for material waves.



Figure 2 Schematic representation of the diagrams of energy transfer between incoming photons with frequency ω and the material, leading to (a) generation of the Stokes radiation ω_s, and (b) generation of the anti-Stokes radiation ω_{as}.

these energy conversion processes with the help of only two vibrational states, to simplify matters.

As Figure 2a shows, the material, which is initially in the ground state, absorbs a fraction $\hbar\Omega$ of the energy $\hbar\omega$ of incoming photons, to move up to the excited state. As a result, the frequency of the photons involved in this process is downshifted to $\omega_s = \omega - \Omega$. Those photons that are generated at frequency ω_s are commonly called 'Stokes radiation'. On the other hand, when a sufficiently large number of molecules is excited, they can interact with the incoming photons and return back to the ground state. As Figure 2b shows, in this process the energy is transferred from the material to the incoming photons, which thereby generates an upshifted anti-Stokes radiation at frequency $\omega_{as} = \omega + \Omega$. The Raman (Brillouin) frequency shift Ω is of the order of $\Omega_R \approx 13\,\text{THz}$ ($\Omega_B \approx 10\,\text{GHz}$).

In fact, the Raman and Brillouin effects may lead to so-called spontaneous processes, which occur in the limit of low-amplitude for all waves other than the incoming wave. For example, when a laser beam is injected in the fiber with a sufficiently low intensity, one can observe a spontaneous scattering process as schematically represented in Figure 3a.

One can clearly identify in Figure 3a the Raman and Brillouin radiation, as well as radiation scattered at the same frequency as the incoming wave, that is, Rayleigh radiation. Now, when the incoming wave propagates together with light waves whose intensity is no longer negligible with respect to that of the incoming wave, the Raman and Brillouin effects can lead to stimulated processes, in which energy is continually converted from higher to lower frequency photons. As a result, the number of Stokes photons is continually amplified at the expense of anti-Stokes photons, as schematically represented in Figure 3b. The stimulated process can be obtained by either launching the incoming wave ω together with a probe wave at frequency $\omega - \Omega$ (which corresponds to the situation represented in Figure 3b), or by using a sufficiently intense incoming light beam. Indeed, above a certain power threshold (which depends strongly on the fiber length and the amount of dopants in the fiber), for which the gain corresponding to the Stokes amplification compensates for the linear fiber losses, the energy conversion from the incoming wave to the scattered waves can become sufficiently important for the scattering process to become stimulated. This process is commonly referred to as a self-stimulated process, as it does not require the use of a probe wave. Although the SRS and SBS exhibit some common general features as those mentioned above, there exist however some major differences between these two phenomena, from a fundamental point of view as well as for their practical applications to optical communication systems. We discuss separately these specific features for SRS and SBS.



Figure 3 (a) Schematic representation of the frequency spectra for spontaneous and stimulated Raman and Brillouin scattering processes. (a) Fluorescence spectrum; (b) gain spectrum for stimulated Raman and Brillouin scattering processes. A pump and a probe waves are injected together in the fiber. δ is the frequency spacing between the pump and the probe wave.

Stimulated Raman Scattering

Under adiabatic following by the electrons of the optical-field-induced nuclear motions, the third-order nonlinear polarization in optical fibers may be



Figure 4 Schematic representation of the Raman susceptibility in an optical fiber. The solid curve represents the imaginary part of the susceptibility, that is, the Raman gain. The dashed curve represents the real part of the susceptibility.



Figure 5 Self-stimulated Raman spectrum (i.e., amplified spontaneous noise), as recorded for a peak pump power $P_0 =$ 150 W and a fiber length $L = 10$ m.

written as

$$P(t) = \sigma|E(t)|^2E(t) + E(t)\int_{-\infty}^{t} \mathrm{d}s\,\sigma_R(t-s)|E(s)|^2 \quad [1]$$

where σ and σ_R represent the instantaneous (Kerr) and noninstantaneous (Raman) parts of the fiber response, respectively. Here, we consider linearly polarized waves, for simplicity. Figure 4 shows schematically the Raman susceptibility of the fused silica, $\chi_R(\Omega) = \sigma_R(\Omega)/2$, which is quite close to that of standard silica fibers.

In Figure 4, the real and imaginary parts of χ_R are represented in solid and dashed curves, respectively. The imaginary part of the Raman susceptibility, which corresponds to the Raman gain $G_R = \mathrm{Im}(\chi_R)$, is an experimentally measurable quantity. For example, at a pump wavelength $\lambda = 1\,\mu$m, the maximum value of the Raman gain in standard silica fibers is $\approx 10^{-13}$ mW^{-1}. In fact the Raman gain $G_R(\Omega)$ depends on the type and amount of dopants used in the fabrication of the fiber. In contrast to crystalline silica where the Raman gain occurs at a well-defined frequency of 13.2 THz, the Raman gain of silica fibers extends over a large frequency range, as can be seen in Figure 4, with a broad prominent peak around 13.2 THz. In the absence of an input signal the broadband noise is amplified within the Raman Stokes components, which are centered about the frequency detuning of 13.2 THz.

If the power of the Stokes wave becomes large enough, the Stokes wave serves as a pump to generate a second-order Stokes wave. This process of cascade SRS can generate multiple Stokes waves whose number depends on the input pump power and fiber length. Figure 5 displays a typical experimental Raman spectrum generated from a Q-switched, frequency-doubled Nd:YAG laser, emitting 5 ns duration (30 GHz spectral width) pulses at 563.63 THz (532.26 nm). The laser output was injected along one birefringence axis of a 14 m length of polarization-maintaining single-mode fiber. At an estimated injected peak power of 200 W, several higher-order Raman Stokes orders S_j $(j = 1, 4)$ (separated by 13.2 THz) are generated between 510 and 550 THz (588 and 545 nm). The spectral profile of each resulting Stokes line is near-Lorentzian with a full width at half maximum ranging from about 2 THz for the first Stokes to about 3.5 THz for the fourth Stokes. The broadening of the Raman Stokes wave, as the Stokes order increases, is due to several competing nonlinear processes.

This broadband gain is due to the amorphous nature of fused silica, in which the molecular vibrational frequencies spread out into bands which overlap and create a continuum. This outstanding feature has been fully exploited to develop wide-band amplifiers for multichannel optical communications. Recent work demonstrated the achievement of a Raman amplifier with a bandwidth of 100 nm, by use of a set of height pumps and an appropriate choice of the frequency separations between the pumps. Another important application of the Raman gain in optical fibers lies in the development of fiber-Raman lasers, which can be tuned over a wide frequency range (≈10THz). Such lasers can be obtained by inserting a piece of single-mode fiber inside a Fabry–Perot cavity formed by two partially reflecting mirrors. A rotating output mirror and an intracavity prism allow one to select the Stokes light that provides the laser wavelength. Another example is that the Raman gain can be used to assist non-phase-matched parametric interactions.

A large power-gain enhancement was recently demonstrated for nonphase-matched waves in a three-wave mixing interaction. The Raman-assisted three-wave mixing can be used to achieve wide-bandwidth frequency conversion processes without having to satisfy the strict conditions imposed by phase-matching conditions. The above discussion clearly illustrates some useful effects of the SRS in optical fibers. On the other hand, the SRS may represent a drawback for some optical communication systems, as we discuss below.

Let us consider a pump wave injected in the fiber at frequency ω_0. The total electric field in the fiber may be written as follows:

$$E = \frac{1}{2}\mathcal{A}(z,t)\exp[\mathrm{i}(k_0 z - \omega_0 t)] \qquad [2]$$

where $\mathcal{A}$ is a slowly varying field envelope. By expanding the wavevector k_0 of the electric field in a Taylor series around ω_0, the amplitude $\mathcal{A}$ of the electric field is found to satisfy the generalized nonlinear Schrödinger equation (NLSE):

$$\begin{aligned}\frac{\partial\mathcal{A}}{\partial z}&+\frac{\mathrm{i}}{2}\beta\frac{\partial^2\mathcal{A}}{\partial t^2}\\ &=\mathrm{i}\gamma(1-\rho)|\mathcal{A}|^2\mathcal{A}+\mathrm{i}\gamma\rho\mathcal{A}\int_0^\infty \chi_R(s)|\mathcal{A}|^2(t-s)\mathrm{d}s\\ &=\mathrm{i}\gamma|\mathcal{A}|^2\mathcal{A}+\mathrm{i}\gamma\rho C_1\mathcal{A}\frac{\partial|\mathcal{A}|^2}{\partial t}+\frac{\mathrm{i}}{2}\gamma\rho C_2\mathcal{A}\frac{\partial^2|\mathcal{A}|^2}{\partial t^2}\\ &\quad+\frac{\mathrm{i}}{6}\gamma\rho C_3\mathcal{A}\frac{\partial^3|\mathcal{A}|^2}{\partial t^3}+\cdots\end{aligned} \qquad [3]$$

In eqn [3], $C_1 \approx -7.9\times10^{-3}$ps, $C_2 \approx -1.28\times10^{-4}$ps^2, $C_3 \approx 9\times10^{-6}$ps^3, and the parameter ρ, which measures the fractional contribution of Raman effects to the total nonlinearity, is ≈ 0.18 for standard silica fibers.

When the wave propagation involves only a relatively small frequency range around the pump frequency (less that 1 THz) then only the term proportional to C_1 in eqn [3], i.e., the leading term of the Raman contribution, plays a significant role. Most high-capacity transmission systems using a single channel fall into this situation, as long as picosecond pulses are used. The term proportional to C_1 induces a continuous frequency shift of the pulse frequency, as a result of a small transfer of energy from higher- to lower-frequency waves. This phenomenon, known as the soliton self-frequency shift, constitutes one of the undesirable effects of SRS in optical communications.

On the other hand, when the wave propagation involves a relatively large frequency region (of the order of a few THz), then higher-order terms that are proportional to C_2 and C_3 begin to play a significant role. In particular, the term proportional to C_3 indicates a strong transfer of energy from higher- to lower-frequency waves. In optical communications, this effect causes higher-wavelength channels of wavelength-division multiplexing systems to be amplified while depleting the lower-wavelength channels. This effect can be reduced by using filters and more amplification to compensate for the depletion at lower wavelengths (but this is achieved at the expense of a degradation of the signal-to-noise ratio).

Stimulated Brillouin Scattering

In optical fibers, the SBS occurs at input power levels that are much lower that those needed for SRS, and manifests itself through the generation of a backward-propagating Stokes wave. Although SBS is not (strictly speaking) a parametric process, the generation of the Brillouin Stokes radiation is commonly described as a parametric interaction between the pump wave, the Stokes wave and an acoustic wave (material wave). Indeed, one assumes that the annihilation of a pump photon creates simultaneously a Stokes photon and an acoustic phonon, with the following conservation laws for the energy and the momentum:

$$\Omega_\mathrm{B} = \omega_0 - \omega_\mathrm{s} \qquad [4]$$

$$K_\mathrm{B} = k_0 - k_\mathrm{s} \qquad [5]$$

where ω_0 and ω_s are the frequencies, and k_0 and k_s are the wavevectors of the incoming and Stokes waves, respectively. Then, assuming $|k_\mathrm{s}| \approx |k_0|$, the acoustic wave is found to satisfy the following dispersion relation

$$\Omega_\mathrm{B} = K_\mathrm{B}v = 2v|k_0|\sin(\theta/2) \qquad [6]$$

where v is the phase velocity of the acoustic wave, and θ is the angle between the pump and Stokes wavevectors. As eqn [6] shows, the frequency shift

Ω_B depends on the scattering angle. Ω_B is a maximum for $\theta = \pi$ (i.e., in the backward direction) and vanishes for $\theta = 0$ (forward direction). Thus, although eqn [6] predicts that Brillouin scattering should not occur in the forward direction, spontaneous Brillouin scattering can occur in the forward direction in optical fibers. But this phenomenon is quite negligible. In optical fibers, SBS occurs mainly in the backward direction with a frequency shift given by

$$\nu_B = \Omega_B/(2\pi) = 2v|k_0| = 2n_0 v/\lambda_0 \qquad [7]$$

where n_0 is the refractive index and λ_0 is the pump wavelength (incoming wave). In silica fibers, $v \approx 6\,\mathrm{km\,s^{-1}}$ and $n_0 \approx 1.45$; which leads to $\nu_B \approx 10\,\mathrm{GHz}$ at $\lambda_0 = 1.55\,\mu\mathrm{m}$. Thus, the Brillouin frequency shift is smaller by three orders of magnitude compared with the Raman frequency shift ($\approx$13 THz). The amorphous nature of fused silica leads to a Brillouin-gain coefficient $G_B(\nu)$ which extends over a frequency range of $\approx$ 10 MHz, with a peak value at $\nu = \nu_B$. The Brillouin gain can be approximated by a Lorentzian profile given by

$$G_B(\nu) = \frac{(\Delta\nu_B/2)^2}{(\nu - \nu_B)^2 + (\Delta\nu_B/2)^2} G_B(\nu_B),$$
$$G_B(\nu_B) = \frac{2\pi n_0^7 p_{12}^2}{c d_0 \lambda_0^2 v \Delta\nu_B} \qquad [8]$$

where $\Delta\nu_B$ is the full width at half maximum, p_{12} is the elasto-optic coefficient and d_0 is the material density.

The Brillouin gain has been exploited to develop fiber-Brillouin lasers. Such lasers are obtained by inserting a piece of fiber inside a (ring or Fabry–Perot) cavity. Another useful application of the Brillouin gain of an optical fiber lies in the amplification of a weak signal. Fiber-Brillouin amplifiers allow one to amplify signals with a frequency shift that corresponds to the Brillouin frequency shift ν_B. Fiber-Brillouin amplifiers can provide up to 40 dB gain at pump powers of a few milliwatts. But the bandwidth of such amplifiers is relatively narrow.

Conclusion

In fact scattering phenomena can be beneficial as well as detrimental for optical communication systems. If signals are transmitted in a communication channel with a power above the threshold of a given scattering phenomenon, this phenomenon will induce a transfer of energy from the signal to the Stokes radiation. The resulting signal depletion would then require more amplification. In multichannel communications, the SBS (SRS) can induce cross-talk between two bidirectional channels if their frequency separation happens to be close to the Brillouin (Raman) shift, $\approx$10 GHz ($\approx$13 THz). However, those undesirable effects can be avoided by in-line control techniques for pulse transmission in fiber-optics communication systems. On the other hand, the Raman and Brillouin effects are useful for generating light at new frequencies as well as for amplifying weak light signals. In particular Raman amplifiers are one of the key devices for high-speed telecommunication systems.

List of Units and Nomenclature

Group velocity dispersion coefficient β_2 [$\mathrm{ps^2\,km^{-1}} = 10^{-27}\mathrm{s^2\,m^{-1}}$]
Nonlinear parameter γ [$\mathrm{W^{-1}\,m^{-1}}$]
NLS (E): nonlinear Schrödinger (equation)
Optical intensity I [$\mathrm{GW\,cm^{-2}} = 10^9\ \mathrm{W\,cm^{-2}}$]
SBS: stimulated Brillouin scattering
SRS: stimulated Raman scattering
WDM: wavelength division multiplexing

See also

Fiber and Guided Wave Optics: Light Propagation; Nonlinear Effects (Basics). **Optical Amplifiers:** Raman, Brillouin and Parametric Amplifiers. **Solitons:** Soliton Communication Systems.

Further Reading

Agrawal GP (2001) Nonlinear Fiber Optics. San Diego, CA: Academic Press.

Agrawal GP (2001) Applications of Nonlinear Fiber Optics. San Diego, CA: Academic Press.

Bloembergen N (1977) Nonlinear Optics. Reading, MA: Benjamin.

Dianov EM, Mamyshev PV, Prokhorov AM and Serkin VN (1989) Nonlinear Effects in Optical Fibres. Switzerland: Harwood Academic Publishers.

Hellwarth R (1977) Third-order optical susceptibilities of liquids and solids. *Progress in Quantum Electronics* 5: 1–68.

Pocholle JP, Papuchon M, Raffy J and Desurvire E (1990) Non linearities and optical amplification in single mode fibres. *Revue Technique Thomson-CSF* 22: 187–268.

Shen YR (1984) Principles of Nonlinear Optics. New York: Wiley.

Scattering Theory

Y A Eremin, Moscow State University, Moscow, Russia

© 2005 Published by Elsevier Ltd.

Lord Rayleigh (John William Strutt) (1842–1916)

In the nineteenth century, Lord Rayleigh offered the first explanation for the sky's blue color (on a clear day!). From Rayleigh's initial theory, representing a simplification of Maxwell's electromagnetic theory for the case of particles very small compared to the wavelength of the incident light, the theory was extended to describe the scattering of light by larger macromolecules in solution.

Scattering theory has played a central role in twentieth-century mathematical physics. From Rayleigh's explanation of why the sky is blue to modern medical application of computerized tomography, has attracted both scientists and mathematicians for over a hundred years. Scattering theory is concerned with the effect an inhomogeneous medium has on an incident wave. In particular, if the total field is viewed as sum of an incident field and a scattered field, then the direct scattering problem is to determine the scattered field from a knowledge of the incident one, obstacle properties, and the equations governing the wave motion. In contrast, the inverse scattering problem consists of reconstruction of the inhomogeneity from the knowledge of asymptotic behavior of the scattered field. An everyday example is human vision: from the measurements of scattered light that reaches our retinas, our brain reconstructs a detailed three-dimensional map of the world around us. In summary, the task of direct scattering theory is to determine the relation between the incident and scattered waves. The task of inverse scattering theory is to determine properties of the obstacle.

Light propagating can be described in terms of an electromagnetic field, which is composed of two related vector fields, the electric and the magnetic fields. This means that the vectors of electric (**E**) and magnetic (**H**) field have values defined at each point in space and time. The vector fields **E** and **H** interact through the material parameters: electric permittivity ε and magnetic permeability μ. The behavior of electromagnetic fields can be described by Maxwell's equations.

Maxwell Equations. James Clerk Maxwell (1831–1879)

Consider the electromagnetic wave (light) propagation in a homogeneous, isotropic medium with electric permittivity $\varepsilon > 0$, electric conductivity $\sigma \geq 0$, and magnetic permeability $\mu > 0$, containing a local obstacle. We assume that $\sigma = 0$ outside an obstacle. If J is a current density, the electric field $\vec{E}(x,t)$ and magnetic field $\vec{H}(x,t)$ satisfy the Maxwell equations:

$$\begin{aligned} \nabla \times \vec{E}(x,t) + \mu \frac{\partial \vec{H}}{\partial t}(x,t) &= 0 \\ \nabla \times \vec{H}(x,t) - \varepsilon \frac{\partial \vec{E}}{\partial t}(x,t) &= \vec{J}(x,t) \end{aligned} \qquad [1]$$

Also, in an isotropic conductor, the electric field satisfies Ohm's law:

$$\sigma \vec{E}(x,t) = \vec{J}(x,t) \qquad [2]$$

The speed of wave propagation for the electric and magnetic fields is $c = 1/\sqrt{\varepsilon\mu}$ and in free space $c = 1/\sqrt{\varepsilon_0\mu_0} = 2.99792458 \times 10^8\ \mathrm{m\ s^{-1}}$. Assume that the electromagnetic field is time-harmonic, i.e., of the form:

$$\begin{aligned} \vec{E}(x,t) &= \frac{1}{\sqrt{\varepsilon_0}} \mathbf{E}(x) e^{-j\omega t} \\ \vec{H}(x,t) &= \frac{1}{\sqrt{\mu_0}} \mathbf{H}(x) e^{-j\omega t} \end{aligned} \qquad [3]$$

where $\omega > 0$ is the frequency. Many phenomenon of light scattering can be described based on monochromatic wave propagation. Let us consider a local obstacle occupying a bounded domain D. Inside the obstacle we introduce relative complex permittivity:

$$\varepsilon = \frac{1}{\varepsilon_0}\left(\varepsilon + j\frac{\sigma}{\omega}\right) \qquad [4]$$

Then $\mathbf{E}(x)$ and $\mathbf{H}(x)$ obey the time-harmonic Maxwell equations:

$$\nabla \times \mathbf{E}(x) = jk\mathbf{H}(x), \quad \nabla \times \mathbf{H}(x) = -jk\varepsilon\mathbf{E}(x) \qquad [5]$$

where $k^2 = \varepsilon_0\mu_0\omega^2$.

Helmholtz Equation. Herman Ludwig von Helmholtz (1821–1894)

A wave equation for vector **E** can be readily derived from the Maxwell equations. We obtain:

$$(\nabla^2 + k^2)\mathbf{E}(x) = 0 \qquad [6]$$

This is known as the homogeneous Helmholtz equation. A general planewave solution of the equation can be written as

$$\mathbf{E}(x) = \mathbf{E}_0\, \mathrm{e}^{\mathrm{j}\vec{k}\cdot\vec{x}} \qquad [7]$$

here $\mathbf{E}_0$ is a constant vector independent of spatial coordinates and $\vec{k}\cdot\vec{x}$ is a scalar product of the vectors $\vec{x} = \{x_1, x_2, x_3\}$ and $\vec{k} = \{k_1, k_2, k_3\}$, the so called wavevector. Equations [6] and [7] yield the dispersion relation:

$$k^2 = \varepsilon_0 \mu_0 \omega^2 = k_1^2 + k_2^2 + k_3^2 \qquad [8]$$

For a given $\vec{k}$ vector, a constant phase front is determined by $\vec{k}\cdot\vec{x} = \text{const}$, which indicates that the front is perpendicular to the wavevector. So, the phase front is a plane and the amplitude of the electric field on the plane is a constant.

The Maxwell equations for the plane wave solution become:

$$\begin{aligned} &\vec{k} \times \mathbf{E}(x) = k\mathbf{H}(x), \quad \vec{k} \times \mathbf{H}(x) = -k\mathbf{E}(x) \\ &\Rightarrow \vec{k}\cdot\mathbf{E} = 0, \quad \vec{k}\cdot\mathbf{H} = 0 \end{aligned} \qquad [9]$$

Therefore, vectors **E** and **H** belong to the constant phase plane perpendicular to vector $\vec{k}$ and are orthogonal each other.

Poynting's Vector. John Henry Poynting (1852–1914)

For time-dependent fields, the Poynting vector is introduced as

$$\vec{S}(x,t) = \vec{E}(x,t) \times \vec{H}(x,t) \qquad [10]$$

It is interpreted as the power flow density with the dimension of watts/m^2. The time-average Poynting's vector power density is given by

$$\langle S \rangle = \frac{1}{T}\int_0^T \vec{S}(x,t)\mathrm{d}t \qquad [11]$$

For the time-dependent planewave fields:

$$\begin{aligned} \vec{E}(x,t) &= \mathbf{E}_0 \cos(\vec{k}\cdot\vec{x} - \omega t) \\ \vec{H}(x,t) &= \mathbf{H}_0 \cos(\vec{k}\cdot\vec{x} - \omega t) \end{aligned} \qquad [12]$$

The vector Poynting's power density shown in eqn [10], accepts the form:

$$\vec{S}(x,t) = |\mathbf{E}_0|^2 \cos^2(\vec{k}\cdot\vec{x} - \omega t) \qquad [13]$$

The time-average vector power density gives

$$\langle \vec{S}(x,t) \rangle = \frac{1}{2}|\mathbf{E}_0|^2 \qquad [14]$$

which shows that Poynting's power density is also propagating in the direction of the wave vector $\vec{k}$.

Boundary Conditions

Let us consider a bound obstacle D_i with a smooth closed surface S. The Maxwell eqn [5] has been written in differential form. It must be supplemented with boundary conditions enforced at the obstacle surface. The boundary conditions can be derived from the integral form of Maxwell equations. The field vectors **E**, **H** are assumed to be finite but may be discontinuous across the obstacle surface S. In cases where there is no surface current density (which is so for a perfect conductor) the boundary conditions accept the following form:

$$\vec{n} \times (\mathbf{E}_\mathrm{i} - \mathbf{E}_\mathrm{e}) = 0, \quad \vec{n} \times (\mathbf{H}_\mathrm{i} - \mathbf{H}_\mathrm{e}) = 0 \qquad [15]$$

where subscripts i and e correspond to the total fields inside and outside the obstacle, respectively, and $\vec{n}$ is unit outward normal to S. Essentially the boundary conditions state that tangential components for electromagnetic fields are continuous across the boundary.

Silver–Müller Radiation Conditions

Analysis of a direct scattering problem on a local obstacle involves Maxwell eqn [10] and boundary conditions as in eqn [15] and some infinity conditions, which provide the uniqueness of the scattering problem solutions. Let us assume that a local obstacle is excited by an incident electromagnetic field $\{\mathbf{E}_0, \mathbf{H}_0\}$, given as entire solution to the Maxwell equations. Total field outside the obstacle can be represented as

$$\mathbf{E}_\mathrm{e} = \mathbf{E}_0 + \mathbf{E}_\mathrm{s}, \quad \mathbf{H}_\mathrm{e} = \mathbf{H}_0 + \mathbf{H}_\mathrm{s} \qquad [16]$$

where scattered field $\{\mathbf{E}_\mathrm{s}, \mathbf{H}_\mathrm{s}\}$ in the exterior domain $D_\mathrm{e} = \mathbb{R}^3/\bar{D}_\mathrm{i}$ satisfies the Silver–Müller radiation conditions:

$$\left.\begin{aligned} &\frac{x}{|x|} \times \mathbf{H}_\mathrm{s} + \mathbf{E}_\mathrm{s} = \mathrm{o}\left(\frac{1}{|x|}\right) \\ &\frac{x}{|x|} \times \mathbf{E}_\mathrm{s} - \mathbf{H}_\mathrm{s} = \mathrm{o}\left(\frac{1}{|x|}\right) \end{aligned}\right\} \quad |x| \to \infty \qquad [17]$$

uniformly for all directions $x/|x|$.

Scattering Amplitude

The following result is valid: every radiating solution $\{\mathbf{E}_s, \mathbf{H}_s\}$ to the Maxwell equations has the following asymptotic form:

$$\mathbf{E}_s(x) = \frac{e^{ik|x|}}{|x|}\left\{\mathbf{E}_\infty(\varpi) + O\left(\frac{1}{|x|^2}\right)\right\}$$

$$|x| \to \infty \qquad [18]$$

$$\mathbf{H}_s(x) = \frac{e^{ik|x|}}{|x|}\left\{\mathbf{H}_\infty(\varpi) + O\left(\frac{1}{|x|^2}\right)\right\}$$

where the vector functions $\mathbf{E}_\infty$ and $\mathbf{H}_\infty$ defined on the unit sphere $\varpi \in \Omega = \{0 \le \vartheta \le \pi; 0 \le \varphi \le 2\pi\}$ are known as the electric far field pattern (scattering amplitude) and magnetic far field pattern, respectively. They satisfy:

$$\mathbf{H}_\infty = \vec{\nu} \times \mathbf{E}_\infty, \quad \vec{\nu} \cdot \mathbf{E}_\infty = \vec{\nu} \cdot \mathbf{H}_\infty = 0 \qquad [19]$$

with the unit outward normal $\vec{\nu}$ on Ω. The latter means that $\mathbf{E}_\infty$ and $\mathbf{H}_\infty$ have only tangential components at the unit sphere.

Far field pattern represents real value analytic functions on a unit sphere. Reillich's lemma establishes one-to-one correspondence between radiating electromagnetic field and their far field pattern. It means that there exists only one scattered field $\{\mathbf{E}_s, \mathbf{H}_s\}$ corresponding to a given far field pattern $\mathbf{E}_\infty$.

Reciprocity Relations

Examine the set of far field pattern corresponding to the scattering problem including: Maxwell eqn [5], boundary conditions in eqn [15], and radiation conditions in eqn [17] at the infinity for the scattered fields. Let the incident electromagnetic field is given by the planewave:

$$\mathbf{E}_0(x) = \vec{e}_0\, e^{jk\vec{x}\cdot\vec{\kappa}}, \quad \mathbf{H}_0(x) = \vec{\kappa} \times \vec{e}_0\, e^{jk\vec{x}\cdot\vec{\kappa}} \qquad [20]$$

where $\vec{\kappa} \in \Omega$ is a unit vector giving the propagation direction and $\vec{e}_0 \in \mathbb{R}^3$ is a constant vector responsible for the polarization. From the previous consideration one can see that:

$$\mathbf{E}_s(x; \vec{\kappa}, \vec{e}_0) = \frac{e^{ik|x|}}{|x|}\left\{\mathbf{E}_\infty(\varpi\vec{\kappa}, \vec{e}_0) + O\left(\frac{1}{|x|^2}\right)\right\},$$

$$|x| \to \infty \qquad [21]$$

Furthermore, the following reciprocity relation for the scattering amplitude holds:

$$\vec{h}_0 \cdot \mathbf{E}_\infty(\varpi; \vec{\kappa}, \vec{e}_0) = \vec{e}_0 \cdot \mathbf{E}_\infty(-\vec{\kappa}; -\varpi, \vec{h}_0)$$

for all vectors $\varpi, \vec{\kappa} \in \Omega$ and $\forall \vec{e}_0, \vec{h}_0 \in \mathbb{R}^3$.

Optical Theorem

Far field pattern enables us to evaluate scattering cross section, which is defined as

$$\sigma_s = \int_\Omega |\mathbf{E}_\infty(\varpi)|^2 d\varpi \qquad [22]$$

For the planewave given by eqn [20] and excitation of nonabsorbing obstacle ($\sigma = 0$), the following relation holds:

$$\sigma_s = \frac{4\pi}{k} \operatorname{Im}\{\mathbf{E}_\infty(\vec{\kappa}) \cdot \vec{e}_0\} \qquad [23]$$

This is so-called optical theorem.

Huygen's Principle (Green's Theorem). Christian Huygens (1629–1695)

The Huygens' principle shows that a wavefield on the surface determines the wavefield off the surface. Let us introduce the scalar Green's function which satisfies the Helmholtz equation:

$$(\nabla^2 + k^2) g(x, y) = -\delta(x - y) \qquad [24]$$

where $\delta(x - y)$ is the Dirac delta function. For three-dimensional problems, the scalar Green's function $g(x, y)$ for isotropic media accepts the form:

$$g(x, y) = \frac{e^{jk|x-y|}}{4\pi |x - y|} \qquad [25]$$

Let electromagnetic fields $\{\mathbf{E}_s, \mathbf{H}_s\}$ be a radiating solution to the Maxwell eqn [5] in D_e. Then for any $x \in D_e$ we have the Stratton–Chu formulas:

$$\begin{aligned}
\mathbf{E}_s(x) &= \nabla \times \int_S g(x, y) \vec{\nu}_y \times \mathbf{E}_s(y) ds_y \\
&\quad + \frac{j}{k} \nabla \times \nabla \times \int_S g(x, y) \vec{\nu}_y \times \mathbf{H}_s(y) ds_y \\
\mathbf{H}_s(x) &= \nabla \times \int_S g(x, y) \vec{\nu}_y \times \mathbf{H}_s(y) ds_y \\
&\quad - \frac{j}{k} \nabla \times \nabla \times \int_S g(x, y) \vec{\nu}_y \times \mathbf{E}_s(y) ds_y
\end{aligned} \qquad [26]$$

here S is a smooth closed surface, and $\vec{\nu}$ is the unit normal vector to S directed into D_e. Similar relations are valid for an electromagnetic field inside a bounded domain D_i. The Stratton–Chu formulas are extensively employed to construct boundary integral equations for scattering problems investigating.

Homogeneous Obstacle

Consider a mathematical statement of the scattering problem by a bound homogeneous obstacle. Let external excitation be a planewave $\{\mathbf{E}_0, \mathbf{H}_0\}$: (eqn [20]). In this case the boundary-value scattering problem can be formulated in the form:

$$\begin{gathered}\nabla \times \mathbf{E}_\tau(x) = \mathrm{j}k\mathbf{H}_\tau(x), \quad \nabla \times \mathbf{H}_\tau(x) = -\mathrm{j}k\varepsilon_\tau \mathbf{E}_\tau(x), \\ x \in D_\tau, \tau = \mathrm{i}, \mathrm{e} \\ \vec{\nu} \times (\mathbf{E}_\mathrm{i} + \mathbf{E}_\mathrm{e}) = \vec{\nu} \times \mathbf{E}_0, \\ \vec{\nu} \times (\mathbf{H}_\mathrm{i} + \mathbf{H}_\mathrm{e}) = \vec{\nu} \times \mathbf{H}_0 \ \text{ on } S \\ \frac{x}{|x|} \times \mathbf{H}_\mathrm{e} + \mathbf{E}_\mathrm{e} = o\left(\frac{1}{|x|}\right), \quad |x| \to \infty\end{gathered} \qquad [27]$$

where $\varepsilon_\mathrm{e} = 1$, $\varepsilon_\mathrm{i} = \varepsilon$ and $\{\mathbf{E}_\mathrm{e}, \mathbf{H}_\mathrm{e}\}$ corresponds to scattered field. For a smooth surface and the case $\operatorname{Im} \varepsilon \geq 0$, the problem has a unique solution.

Lippman–Swinger Integral Equation

Assume we deal with the local inhomogeneous obstacle that can be described by dielectric permittivity $\varepsilon(x)$, which is a continuous complex-valued $(\operatorname{Im} \varepsilon(x) \geq 0)$ function in D_i. The correspondent scattering problem can be formulated as below in eqn [29]. In this case, the boundary-value scattering problem can be reduced to the solution of the Lippman–Swinger integral equation

$$\begin{aligned}\mathbf{E}_\mathrm{i}(x) = {} & \mathbf{E}_0(x) + \nabla \times \nabla \times \int_{D_\mathrm{i}} g(x,y) k^2 (\varepsilon(y) - 1) \\ & \times \mathbf{E}_\mathrm{i}(y) \mathrm{d}\nu_y, \quad x \in D_\mathrm{i}\end{aligned} \qquad [28]$$

Volume integral eqn [28] is equivalent to the corresponding scattering problem. Once the solution is found, the associated scattered field outside the inhomogeneous obstacle can be represented as

$$\begin{aligned}\mathbf{E}_\mathrm{s}(x) = {} & \nabla \times \nabla \times \int_{D_\mathrm{i}} g(x,y) k^2 (\varepsilon(y) - 1) \\ & \times \mathbf{E}_\mathrm{i}(y) \mathrm{d}\nu_y, \quad x \in D_\mathrm{e}\end{aligned} \qquad [29]$$

The Lippman–Swinger integral equation plays an important role under analysis of a wave scattering by local inhomogeneous obstacle.

Born Approximation

In the case where $k^2 |\varepsilon(x) - 1| mes D_\mathrm{i} \ll 1$, or where the second term on the right-hand part of the Lippman–Swinger integral eqn [28] is small compared to the first term, one can write $\mathbf{E}_\mathrm{i}(x) \simeq \mathbf{E}_0(x)$. Then the scattered field can be approximately evaluated as

$$\begin{aligned}\mathbf{E}_\mathrm{s}(x) = {} & \nabla \times \nabla \times \int_{D_\mathrm{i}} g(x,y) k^2 (\varepsilon(y) - 1) \\ & \times \mathbf{E}_0(y) \mathrm{d}\nu_y, \quad x \in D_\mathrm{e}\end{aligned} \qquad [30]$$

The above representation for the scattered field is known as the first-order Born approximation. It is also the first-order approximation in the Neumann series for the integral eqn [28]. The Born approximation plays an important role in diffraction tomography.

Rayleigh Scattering

Rayleigh scattering characterizes the scattering of electromagnetic waves by particles much smaller then an exciting wavelength. Consider a spherical particle with constant permittivity ε and radius a deposited at the origin of a coordinate system. Let linear polarized planewave be incident upon the particle $\mathbf{E}_0(x) = \vec{e}_x \, e^{\mathrm{j}kz}$, and $\vec{e}_x$ be unit vector Cartesian coordinate system. It is polarized in x-direction and propagates along z-axis. In this case, for the scattered intensity, we get:

$$I_\mathrm{s} = \left(\frac{\varepsilon - 1}{\varepsilon + 2}\right)^2 \frac{k^4 a^6}{r^2} \sin^2 \vartheta \qquad [31]$$

where r is distance from the origin and $\vartheta \in [0, \pi]$.

Corresponding scattering cross-section is calculated as

$$\sigma_\mathrm{s} = \frac{8\pi}{3} \left(\frac{\varepsilon - 1}{\varepsilon + 2}\right)^2 k^4 a^6 \qquad [32]$$

Thus the total scattered power is proportional to the fourth power of the wave number (minus fourth power of the wavelength – Rayleigh's Law). The scattered power is also proportional to the sixth power of the radius.

Mie Scattering

The Mie theory is a complete mathematical–physical theory of the scattering of electromagnetic wave by homogeneous spherical particles, developed by Gustav Mie in 1908. In contrast to Rayleigh scattering, the Mie theory embraces all possible ratios of the particle radius to wavelength. It relays upon the exact solution to Maxwell equation for spherical homogeneous obstacle with planewave excitation. In the frame of Mie theory, the scattered field is represented as an infinite series of fields of spherical multipoles, which are orthogonal at a sphere surface. Mie solution plays an important role in light scattering by clouds of particles.

See also

Scattering: Raman Scattering; Scattering from Surfaces and Thin Films; Scattering Phenomena in Optical Fibers; Stimulated Scattering.

Further Reading

Boheren C and Hoffman D (1983) *Absorption and Scattering of Light by Small Particles*. New York: Wiley.

Born M and Wolf E (1970) *Principles of Optics*. New York: Pergamon Press.

Chew WC (1995) *Waves and Fields in Inhomogeneous Media*. New York: IEEE Press.

Colton D and Kress R (1992) *Inverse Acoustic and Electromagnetic Scattering Problems*. New York: Springer-Verlag.

Guenther RD (1990) *Modern Optics*. New York: Wiley.

Kong JA (2000) *Electromagnetic Wave Theory*. Cambridge: EMW Publishing.

Kong JA (2002) *Maxwell Equations*. Cambridge: EMW Publishing.

Stimulated Scattering

M Bashkansky and J Reintjes, Naval Research Laboratory, Washington, DC, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Scattering of light involves conversion of an incoming light wave in one mode to an outgoing wave in a different mode. Scattering can involve changes of wavelength, direction, and polarization, and can occur in all types of materials. Without scattering we would not be able to see objects in the world around us. Scattering processes involving particular physical interactions are often given distinctive names. Familiar examples include Rayleigh scattering from the random distribution of air molecules, which makes the sky blue, and Tyndall scattering from small suspended particles, which makes the sunset red. Other types of scattering, e.g., Raman, Brillouin and Rayleigh-wing scattering, are important spectroscopic tools that provide insight into atomic and molecular properties. In their most commonly encountered form, where the intensity of the scattered light is proportional to the intensity of the incident light, the scattering processes are termed spontaneous. With the intense radiation provided by lasers, however, the intensity of the scattered light can grow exponentially, and the processes are termed stimulated scattering.

Stimulated scattering is a subset of the larger discipline of nonlinear optics. The term was first used to describe nonlinear optical interactions (e.g., Raman, Brillouin, Rayleigh) in which the intensity of the scattered light grows exponentially, in a manner similar to the exponential growth of light intensity associated with lasers. These interactions involve exchange of energy with a second mode that is an internal mode of the scattering medium, and the scattered light wave is at a different wavelength from the incoming light. The use of the term stimulated has subsequently been expanded to include a wider class of nonlinear optical interactions, such as parametric fluorescence or certain aspects of self-focusing, in which the second mode is itself a light wave, with either a different frequency or direction of propagation.

In the wider sense, scattering of light occurs through interaction of the incoming light wave with an 'idler' mode in a material. Stimulated scattering occurs when the idler mode is itself driven by interference of the incoming and scattered light waves. Under these circumstances, exponential growth of the scattered wave results. Depending on the interaction, the idler mode may be an internal mode of the material or another light wave. Most linear scattering processes have stimulated counterparts. However, there are stimulated scattering interactions that have no spontaneous analogs.

The elements of stimulated light scattering can be summarized mathematically as follows. The scattering process is modeled as an incoming laser or pump, an outgoing scattered wave and an idler mode. The interaction of the laser with the idler mode to produce the scattered light wave is described by the equation

$$\frac{\partial}{\partial z}A_S(z,t) + \frac{n}{c}\frac{\partial}{\partial t}A_S(z,t) = \kappa A_L b^* \qquad [1]$$

where A_S and A_L are the slowly varying amplitudes of the scattered and laser light waves whose electric fields are defined as

$$E_{S(L)} = \frac{1}{2}\left\{A_{S(L)}e^{i[\omega_{S(L)}t - k_{S(L)}z]} + cc\right\} \qquad [2]$$

$\omega_{S(L)}$ is the frequency of the scattered (laser) light, $k_{S(L)}$ is the corresponding wavevector, κ is a coupling coefficient, cc denotes complex conjugate, and b is the amplitude of the idler mode given by

$$B = \frac{1}{2}\left\{b e^{i[\omega_b t - k_b z]} + cc\right\} \qquad [3]$$

The interaction of the laser and scattered wave to drive the idler mode is described by the equation

$$\mathcal{L}(b^*) = \kappa' A_L^* A_S \qquad [4]$$

where $\mathcal{L}$ is a differential operator that describes the dynamics of the idler mode, e.g., a damped oscillator or a propagating wave, and κ' is a second coupling coefficient. For the class of stimulated processes that involve excitation of an internal mode of the medium, $\mathcal{L}$ has the form

$$\mathcal{L} = \frac{\partial}{\partial t} + \frac{1}{T_2} - v\frac{\partial}{\partial z} \qquad [5]$$

where T_2 is the damping time of the coherence of the internal mode. When interaction times are long compared to internal response and decay times,

$$b^* \sim \kappa' A_L^* A_S$$

and the scattered wave obeys an equation of the form

$$\frac{\partial}{\partial z} A_S(z,t) = \frac{g}{2} |A_L|^2 A_S(z,t)$$

which has an exponential-gain solution for the scattered wave intensity:

$$I_S(z,t) = I_S(0,t) e^{I_L g z}$$

When the idler mode is a light wave, as in stimulated parametric fluorescence, [4] has the same form as [1] and they can be solved as a coupled pair, leading to transcendental or hyperbolic solutions. Within the framework of nonlinear optics, interactions of these types can be expressed as arising from a nonlinear optical polarization, which forms the right-hand side of [1]. The dynamics of the nonlinear polarization are then described by [4].

Stimulated processes are often associated with pumping thresholds. When these processes are configured with cavity resonators, they possess a threshold in pumping intensity just as with lasers or other oscillators. When they are operated in single or multipass scattering cells, they have no true threshold. However, they still have a practical useful threshold when the growth from quantum noise raises the scattered signal to a level comparable to the pump. By convention, this is taken to be the incident light intensity at which the scattered intensity reaches approximately 1% of the pump intensity, typically involving gains of the order of e^{23}–e^{30}. At this level, a small increase in pump intensity raises the scattered intensity to levels at which the pump starts to be depleted.

Attenuation of the scattered light can be accounted for by replacing $I_L g$ in the above expression by $I_L g - \alpha$, where α is the attenuation coefficient. Exponential gain is now experienced when the pump intensity exceeds the level given by

$$I_L > \frac{\alpha}{g}$$

This value can serve as an estimate of threshold pumping in cavity configurations, although in free propagation situations, net gain must still approach e^{23} to exhibit threshold behavior.

A list of stimulated scattering interactions is given in Table 1.

Stimulated Raman Scattering

Stimulated Raman scattering (SRS) involves conversion of an incoming light wave at one frequency, termed the laser or pump wave, into a scattered wave of different frequency, along with excitation or de-excitation of an internal mode of the medium. The frequency difference between the pump and scattered waves is equal to the frequency of the material mode and is characteristic of the material. When the frequency of the scattered wave is lower than that of the incident wave, the scattered wave is termed a Stokes wave, and the internal mode of the medium is excited in the scattering process. When the frequency of the scattered wave is higher than that of the incident wave, the scattered wave is termed an anti-Stokes wave, and the internal mode of the medium is de-excited in the scattering process.

The internal mode of the medium that is involved in Raman scattering is a nonpropagating collective mode. Many different types of internal modes in all types of materials can be involved in Raman scattering. Examples include molecular vibrations and rotations in gases, liquids, or solids, electronic states that are of the same parity as the ground state in gases or solids, optical phonons or polaritons in solids, and Langmuir waves in plasmas. Raman frequency shifts can range from tens of wavenumbers for lattice vibrations to tens of thousands of wavenumbers for electronic transitions.

Spontaneous Raman scattering was first described theoretically by Smekal in 1923 from a quantum mechanical study of light scattering, and was

Table 1 List of stimulated scattering interactions

Stimulated scattering process	*Internal material mode*	*Light mode change*
Stimulated Raman scattering	Nonpropagating internal energy mode: molecular vibrations and rotations, same parity electronic states, optical phonons and Langmuir waves	Change in wavelength, polarization, direction
Stimulated Brillouin scattering	Propagating sound waves	Change in wavelength, polarization, and direction
Stimulated Rayleigh scattering	Temperature and density fluctuations due to light absorption	Change in direction
Stimulated Rayleigh wing scattering	Molecular distribution and orientation fluctuations	Change in wavelength and direction
Stimulated concentration scattering	Fluctuations of concentration in gas mixtures	Change in direction
Photorefractive stimulated scattering	Diffusion of photo-excited carriers	Change in direction
Stimulated Thomson/Compton scattering	Momentum changes in bunched free electrons	Change in wavelength and direction
Stimulated parametric fluorescence	Nonresonant nonlinear polarization	Change in wavelength and direction
Self-focusing	Nonresonant nonlinear polarization	Change in direction

demonstrated experimentally by Raman, and shortly after by Landsberg and Mandelstamm in 1928. Stimulated Raman scattering was first observed in 1962 by Woodbury and Ng, and Eckhardt *et al.* soon after the development of pulsed lasers.

Stimulated Raman scattering can be observed in many different configurations including cavity resonators, single or multiple-pass generator cells or amplifiers. It can be observed as forward scattering, with the scattered light propagating in the same direction as the pump light, or backward scattering, with the scattered light propagating in the opposite direction to the pump light. Its most widespread use is for generation of coherent light at frequencies different from the pump light. Other applications include phase conjugation, optical gating, beam cleanup, and pulse compression.

The equations describing SRS when depletion of the pump light and diffraction of the optical beams are neglected are:

$$2ik_S\left(\frac{\partial A_S}{\partial z} \pm \frac{1}{v_{gS}}\frac{\partial A_S}{\partial t}\right) = -\frac{N}{2}\frac{\omega_S^2}{c^2}\left(\frac{\partial \alpha}{\partial Q}\right)_S Q^* A_L \quad [6]$$

$$\frac{\partial Q^*}{\partial t} + \Gamma Q^* = -\frac{i}{4\omega_o m}\left(\frac{\partial \alpha}{\partial Q}\right)_S A_L^* A_S \quad [7]$$

Here A_S and A_L are the slowly varying optical field amplitudes of the Stokes and laser waves as given in [2], $\omega_{S(L)}$ are the optical frequencies, $k_{S(L)}$ are the corresponding k vectors, $v_{S(L)}$ are the group velocities, and Q is the amplitude of the idler mode, in this case the normal mode coordinate of the material excitation, defined by:

$$\mathrm{Q}(x,y,z,t) = \frac{1}{2}(Q(x,y,z,t)e^{-i(\omega_o t - k_o z)} + \mathrm{cc}) \quad [8]$$

$(\partial\alpha/\partial Q)_S$ is the Stokes hyperpolarizability, $\omega_0 = \omega_L - \omega_S$ is the Raman transition frequency, and k_0 is the k vector of the material excitation. The phase matching relation $k_S = k_L - k_0$ is automatically satisfied for SRS because the material mode that is involved is nonpropagating. Γ is the half width at half maximum of the Raman linewidth given by $\Gamma = 1/T_2$, where T_2 is the dephasing time. N is the number of molecules in the ground state and m is the effective reduced mass of the material oscillation.

When the fields are constant or vary slowly compared to the response time of the material, the Stokes intensity is given by

$$I_S(z) = I_S(0)e^{I_L g_{ss} Z} \quad [9]$$

where the intensity I is given by

$$I_{S(L)} = \frac{1}{2}(cn_{S(L)}\varepsilon_0)|A_{S(L)}|^2$$

and

$$g_{ss} = \frac{N\omega_s}{4\Gamma n_S n_L m\omega_0 c^2 \varepsilon_0}\left(\frac{\partial \alpha}{\partial Q}\right)^2 \quad [10]$$

where $n_{S(L)}$ is the index of refraction of the Stokes (laser) in the material and ε_0 is the dielectric permittivity of the vacuum.

The Stokes wave grows exponentially with z at a rate that depends on the pump intensity. If the Stokes wave becomes intense enough, its power can become comparable to that of the original pump wave. In that case depletion of the pump wave must be taken into account with an equation for the pump wave amplitude similar to [6]. The Stokes intensity is now given by

$$I_S(z) = \frac{I_S(0)e^{I_L(0)gz}}{1 + \dfrac{\omega_L}{\omega_S}\dfrac{I_S(0)}{I_L(0)}e^{I_L(0)gz}} \qquad [11]$$

which is valid when $I_S(0) \ll I_L(0)$.

In the limit of strong interactions all of the laser energy can be depleted. The maximum Stokes energy is given by $I_S = I_L(\omega_S/\omega_L)$, where ω_S/ω_L is termed the Manly–Rowe ratio. The energy that is removed from the laser but not converted to Stokes radiation is transferred to the material.

For each photon produced in the scattered wave, a corresponding quantum of energy is given to the material mode and a photon is removed from the laser. In principle, 100% of the laser photons can be converted to Stokes photons, but complete conversion is not achieved in practice. Photon conversion efficiencies greater than 90% have been reported in some pulsed laser experiments.

SRS frequency shifts and gains of some materials are shown in Table 2.

When pulses are used with durations comparable to or shorter than the response time of the material, ranging from picoseconds to femtoseconds depending on the material, the interaction is transient and the effects of the time derivatives in [6] and [7] must be accounted for. Under these conditions the Stokes intensity is given as a temporal integral with Bessel function dependence on the laser intensity. When the pulse duration is much shorter than the material dephasing time and the incident Stokes functional form is the same as the pump, the amplified Stokes intensity is given by the expression

$$I_S(z,\tau) = I_S(0,\tau)I_0^2\left(\sqrt{2g_{ss}\Gamma z\int_{-\infty}^{\tau} I_L(\tau')\mathrm{d}\tau'}\right) \qquad [12]$$

where I_0 is a modified Bessel function. In this regime, the Stokes intensity depends only on the integrated pump energy. The Stokes gain is reduced from its steady state value for pulses of constant intensity, but for pulses of constant energy the highest Raman gain is obtained in the limit of transient interactions.

Table 2 List of frequency shifts and gains of selected materials for stimulated Raman scattering

Material, λ_L (nm)	*Shift* (cm^{-1})	*Gain (cm/GW)*
H_2 gas (20 atm), 532	4155	2.5
D_2 gas (60 atm), 532	2987	0.45
CH_4 (115 atm), 532	2913	1.26
H_2O, 694	3290	0.14
CS_2, 694	655.6	24
$LiNbO_3$, 694	637	9.4
$Ba(NO_3)_2$, 532	1047	47

Table compiled in parts from: Kaiser W and Maier M (1972) Stimulated Rayleigh, Brillouin and Raman Spectroscopy. In: Arecchi FT and Schulz-DuBois EO (eds) *Laser Handbook*, vol. 2. pp. 1077–1150. Amsterdam, The Netherlands: North Holland and Reintjes J and Bashkansky M (2001) Stimulated Raman and Brillouin Scattering. In: Bass M (ed.) *Optical Society of America Handbook of Optics*, Ch. 18, 2nd ed., vol. IV, New York: McGraw-Hill.

One of the most important applications of Raman scattering is the generation of new coherent waves at frequencies shifted from the pump. In this case, an incident Stokes wave is not supplied as the starting term in [9] or [12]. Rather, the process is initiated by the vacuum fluctuations in the Stokes and material oscillator fields. Quantum field creation and annihilation operators must replace the classical field amplitudes of [6] and [7]. The intensity of the generated Stokes wave is given by the expectation value of the normally ordered number operator and in the extreme transient regime is given by:

$$\begin{aligned} I_S(z,\mathrm{d}\tau) = {} & \frac{1}{2A}\hbar\omega_S\Gamma g_{ss}I_L(\mathrm{d}\tau)z \\ & \times\left\{I_0^2\left(\sqrt{2\Gamma g_{ss}z\int_{-\infty}^{\tau} I_L(\tau')\tau'}\right)\right. \\ & \left. - I_1^2\left(\sqrt{2\Gamma g_{ss}z\int_{-\infty}^{\tau} I_L(\tau')\tau'}\right)\right\} \end{aligned} \qquad [13]$$

where A is the cross-sectional area of the interaction geometry. The Stokes light generated in this fashion has all the characteristics of amplified spontaneous emission of lasers operated below threshold until the Stokes intensity becomes high enough to deplete the laser.

The stochastic nature of the SRS quantum mechanical source is manifest in the macroscopic Stokes light when the Stokes generator is operated well below pump depletion levels. For a single spatial mode the probability density distribution of



Figure 1 SRS level diagram showing generation of multiple Stokes and anti-Stokes frequencies.

the Stokes energy has the form of a negative exponential:

$$P(W) = \frac{1}{\langle W \rangle} \exp\left[- \frac{W}{\langle W \rangle} \right]$$

Statistical fluctuations in pulse energy, spatial profile, pointing, and in the spectral and temporal structure of the Stokes signal have all been observed.

If the intensity of the generated Stokes light becomes comparable to the pump intensity, it can serve as a pump wave for its own Raman interaction, producing a wave termed the second Stokes wave, shifted from the pump by frequency $2\omega_o$. If the process is driven hard enough third- and higher-order Stokes waves can be produced.

In addition to the interaction between the pump and Stokes beams described above, stimulated Raman scattering can also involve an anti-Stokes wave whose frequency is given by $\omega_{AS} = \omega_L + \omega_o$. The relationship of various Stokes and anti-Stokes waves is depicted in Figure 1. If a population inversion exists between the energy levels of the Raman process, then the anti-Stokes wave experiences exponential gain in a manner similar to that described above for the Stokes gain.



Figure 2 Phase matching diagram for Stokes–anti-Stokes coupling in a medium with positive dispersion.

When all the population is in the ground state, which is usually the case, the anti-Stokes wave has exponential loss. The anti-Stokes wave can still grow without population inversion if the phase-matching condition

$$\Delta k = k_{AS} + k_S - 2k_L = 0$$

is approximately satisfied. Because of normal dispersion in the material this condition is usually not satisfied for collinear beams. However, if the Stokes and anti-Stokes beams propagate at small angles as shown in Figure 2, then the phase-matching condition can be met. For angles near but not exactly at phase matching the anti-Stokes wave grows exponentially as part of a mixed Stokes/anti-Stokes mode with a gain given by:

$$g = \mathrm{Re}\left\{ \tfrac{1}{2}(K_3 - K_1)|A_L|^2 - \tfrac{i}{2}\sqrt{\Delta k^2 + 2i\Delta k(K_3 + K_1)|A_L|^2 - (K_1 - K_3)^2 |A_L|^4} \right\} \quad [14]$$

At exact phase matching the interaction of Stokes and anti-Stokes waves serves to suppress the exponential gain of either wave.

As with Stokes waves, multiple-order anti-Stokes waves can be generated. Stokes and anti-Stokes orders up to at least 13 have been reported.

Stimulated Brillouin and Rayleigh Scattering

Light scattering can also occur through interaction with material density variations. Spontaneous scattering through interaction with this type of internal mode produces a triplet of spectral lines. The up- and down-shifted lines are known as Brillouin anti-Stokes and Stokes lines, respectively, and are due to interaction with acoustic waves. The central peak is termed Rayleigh, or thermal Rayleigh scattering and is due to stationary density fluctuations arising from light absorption. A broad skirt around the central peak, which can be observed in anisotropic media, is due to the fluctuation of molecular distribution and orientation and is termed Rayleigh wing scattering. Each of these processes can give rise to stimulated scattering in the presence of intense radiation.

Density fluctuations are induced directly by light intensity through electrostriction, and indirectly by temperature fluctuations when optical absorption is important. A general classical model of the interaction, including both electrostriction and absorptive heating effects, is described by three equations:

The Navier-Stokes equation:

$$\rho_0 \frac{\partial \mathbf{v}}{\partial t} + \frac{v^2}{\delta}\nabla(\Delta\rho) + \frac{v^2\beta\rho_0}{\delta}\nabla(\Delta T) - \eta\nabla^2\mathbf{v} = 2\gamma\varepsilon_0\nabla(\mathbf{E}_\mathrm{L}\cdot\mathbf{E}^*_\mathrm{R/B}) - 2\varepsilon_0\left(\frac{\partial\varepsilon}{\partial T}\right)_\rho(\mathbf{E}_\mathrm{L}\cdot\mathbf{E}^*_\mathrm{R/B})\nabla(\Delta T) \qquad [15]$$

The continuity equation:

$$\frac{\partial}{\partial t}\Delta\rho + \rho_0\nabla\cdot\mathbf{v} = 0 \qquad [16]$$

The energy transport equation:

$$\left(\rho_0 C_v\frac{\partial}{\partial t} - \lambda_\mathrm{T}\nabla^2\right)\Delta T - \frac{C_v(\delta-1)}{\beta}\frac{\partial}{\partial t}\Delta\rho = 4nc\alpha\varepsilon_0(\mathbf{E}_\mathrm{L}\cdot\mathbf{E}^*_\mathrm{R/B}) + 4\varepsilon_0\left(\frac{\partial\varepsilon}{\partial T}\right)_\rho\left(T_0\mathbf{E}_\mathrm{L}\cdot\frac{\partial}{\partial t}\mathbf{E}^*_\mathrm{R/B}\right) \qquad [17]$$

Here $\rho=\rho_0+\Delta\rho$, $T=T_0+\Delta T$, $\mathbf{v}$ is the volume element, v is the acoustic wave velocity, $\delta=C_p/C_v$ is the ratio of heat capacities at constant pressure and at constant volume, $\eta=(2\eta_\mathrm{s}+\eta_\mathrm{d})$ where η_s is the shear viscosity and η_d is the dilational viscosity, $\gamma=\rho_0(\partial\varepsilon/\partial\rho)_T$, λ_T and β are the thermal conductivity and thermal expansion coefficients, ε is the dielectric constant, and α is the linear absorption coefficient. $\mathbf{E}_\mathrm{L}$ is the pump field and $\mathbf{E}_\mathrm{R/B}$ is either the Rayleigh or Brillouin field.

Equations [15] and [16] can be combined to eliminate the $\mathbf{v}$ dependence:

$$\left[-\frac{\partial^2}{\partial t^2} + \left(\frac{v^2}{\delta} + \frac{\eta}{\rho_0}\frac{\partial}{\partial t}\right)\nabla^2\right]\Delta\rho + \frac{v^2\beta\rho_0}{\delta}\nabla^2(\Delta T) = 2\gamma\varepsilon_0\nabla^2(\mathbf{E}_\mathrm{L}\cdot\mathbf{E}^*_\mathrm{R/B}) - 2\varepsilon_0\left(\frac{\partial\varepsilon}{\partial T}\right)_\rho\nabla\cdot[(\mathbf{E}_\mathrm{L}\cdot\mathbf{E}^*_\mathrm{R/B})\nabla(\Delta T)] \qquad [18]$$

Together with the equations describing the effect of the medium on the optical fields [19a,b], this coupled set of equations describes simultaneously stimulated Brillouin and Rayleigh scattering:

$$\left(\frac{\partial}{\partial z} + \frac{1}{v_\mathrm{g}}\frac{\partial}{\partial t} + \frac{1}{2}\alpha\right)A_\mathrm{L} = \mathrm{i}\frac{\omega_\mathrm{L}}{4cn_\mathrm{L}}\left[\frac{\gamma}{\rho_0}\Delta\rho A_\mathrm{R/B} + \left(\frac{\partial\varepsilon}{\partial T}\right)_\rho A_\mathrm{R/B}\Delta T\right] \qquad [19a]$$

$$\left(\frac{\partial}{\partial z} - \frac{1}{v_\mathrm{g}}\frac{\partial}{\partial t} - \frac{1}{2}\alpha\right)A_\mathrm{R/B} = -\mathrm{i}\frac{\omega_\mathrm{R/B}}{4cn_\mathrm{R/B}}\left[\frac{\gamma}{\rho_0}\Delta\rho^* A_\mathrm{L} + \left(\frac{\partial\varepsilon}{\partial T}\right)_\rho A_\mathrm{L}\Delta T^*\right] \qquad [19b]$$

where the slowly varying envelope approximation [2] is used for the waves described by A_L, $A_\mathrm{R/B}$, $\Delta\rho$, and ΔT. The nonlinear polarization term is related to density and temperature wave amplitudes in the following way:

$$P^\mathrm{NL} = \varepsilon_0 E\left[\left(\frac{\partial\varepsilon}{\partial\rho}\right)_T\rho + \left(\frac{\partial\varepsilon}{\partial T}\right)_\rho T\right] \qquad [20]$$

Without the driving terms involving the optical fields, [17] and [18] describe broadband damped fluctuations in the variables $\Delta\rho$ and ΔT. When the optical driving terms are included, resonant behavior emerges. Steady state solutions can be obtained assuming strongly damped material excitations, allowing neglect of $\Delta\rho$ and ΔT derivatives. Separate contributions of the Rayleigh and Brillouin interactions to $\Delta\rho$ can be identified:

Rayleigh contribution:

$$\Delta\rho_\mathrm{R} = \left[\frac{\gamma(\Omega + \frac{1}{2}\mathrm{i}\delta\Gamma_\mathrm{R}) - \mathrm{i}\gamma_\mathrm{a}\Omega_\mathrm{B}}{\Omega + \frac{1}{2}\mathrm{i}\Gamma_\mathrm{R}}\right]\frac{\varepsilon_0}{4v^2}A_\mathrm{L}A^*_\mathrm{R} \qquad [21]$$

where γ_a is the absorptive coupling constant given by

$$\gamma_\mathrm{a} = \frac{2\alpha n v^2\beta}{C_p\Omega_\mathrm{B}}$$

The Brillouin contribution is:

$$\Delta\rho_B = \left[\frac{-(\gamma - i\gamma_a vq/\Omega)q^2\varepsilon_0}{4(\Omega^2 + i\Omega\Gamma_B - v^2q^2)}\right] A_L A_B^* \qquad [22]$$

In [21] and [22] the frequencies and wavevectors satisfy the following relations:

$$\omega_L = \omega_{R/B} + \Omega \qquad [23a]$$

$$k_L = k_{R/B} + q \qquad [23b]$$

where ω_L is the incident laser frequency, $\omega_{R/B}$ is the frequency of the scattered Rayleigh or Brillouin wave, and k_L, $k_{R/B}$ are the corresponding wavevectors. Ω and q are the frequency and wavevector of the density fluctuation. Equations [23a,b] can also be described as energy and momentum conservation relations among incident and scattered photons and a phonon in the quantum mechanical picture.

The Rayleigh and Brillouin contributions exhibit resonant behavior at different frequency shifts. The Rayleigh contribution has its resonant frequency at $\Omega_R = 0$, resulting in typical diffusion behavior. The Rayleigh linewidth $\Gamma_R = 2\lambda_T q^2/\rho_0 C_p$ is the inverse of the decay time of the isobaric density fluctuations. The Brillouin contribution has its resonance at a frequency shift given by

$$\Omega_B = qv$$

where v is the sound velocity. Thus at resonance the density fluctuations associated with the Brillouin effect correspond to sound waves. The Brillouin linewidth

$$\Gamma_B = \frac{q^2}{\rho_0}\left[\eta + \frac{\kappa}{C_p}\left(\frac{C_p}{C_v} - 1\right)\right]$$

is the inverse of the phonon lifetime τ_B.

In general Brillouin and Rayleigh interactions involve noncollinear scattering with the outgoing wave propagating at an arbitrary angle to the incident wave. In this case [23b] is a vector relation and the interaction geometry can be represented as shown in Figure 3.

The resulting relations among the k-vectors and frequencies of the various waves can place restrictions on the values of frequency shifts that are observed under various circumstances.

The coupled equations for the optical intensities in the steady state take the following form:

$$\frac{dI_L}{dz} = -g_{R/B} I_L I_{R/B} - \alpha I_L \qquad [24a]$$



Figure 3 SBS phase matching diagram depicting relations between laser, k_L, sound wave, q_B, and Stokes and anti-Stokes, k_S, k_A k-vectors.

$$\frac{dI_{R/B}}{d\zeta} = g_{R/B} I_L I_{R/B} - \alpha I_{R/B} \qquad [24b]$$

where z is the direction of propagation of the incoming wave, ζ is the direction of propagation of the scattered wave, and $g_{R/B}$ is the gain coefficient of the Rayleigh or Brillouin effect. Equations [24a,b] describe interactions that have exponential gain. Stimulated Brillouin and Rayleigh scattering can be used in both a self-generator and an amplifier mode, but are used most often in a self-generator mode. Because the frequency shifts are small in these interactions, the starting signals for self-generators are thermal excitations of the internal modes rather than vacuum fluctuations.

Stimulated Brillouin Scattering

Stimulated Brillouin scattering (SBS) occurs through interaction with acoustic waves in solids, liquids, and gases and with ion-acoustic waves in plasmas. The Stokes or anti-Stokes frequency shifts for SBS are much smaller than for SRS, with typical values on the order of 0.1–100 GHz, depending on the excitation wavelength and interaction geometry as well as on material properties. Because the internal mode in SBS is a propagating wave, the phase matching condition shown in Figure 3 places restrictions on the frequency of the sound wave that is involved at various scattering angles. SBS is used most often for pulse compression and for correction of phase distortion in propagating light beams through phase conjugation. Although SBS is normally associated with high-power lasers in laboratory experiments, it is also a major factor in limiting the intensity of low-power lasers that can be used in optical fibers because of the long interaction lengths. SBS is also a prominent source of damage in solids and crystals caused by high-power lasers. It can also be used for generation and study of coherent hypersonic waves.

The SBS gain coefficient has both electrostrictive and absorptive contributions, $g_B = g_B^e + g_B^a$ where

$$g_B^e = \frac{\omega_B \gamma^2 \Omega_B}{2 n_B n_L c^2 v^2 \rho_0 \Gamma_B} \frac{1}{1 + (2(\Omega - \Omega_B)/\Gamma_B)^2} \qquad [25]$$

and

$$g_B^a = \frac{\omega_B \gamma \gamma_a \Omega_B}{4 n_B n_L \rho_0 v^2 c^2 \Gamma_B} \frac{4(\Omega - \Omega_B)/\Gamma_B}{1 + (2(\Omega - \Omega_B)/\Gamma_B)^2} \qquad [26]$$

The SBS gain from electrostriction has a maximum value of

$$g_B^e = \frac{\omega_B \gamma^2 \Omega_B}{2 n_B n_L c^2 v^2 \rho_0 \Gamma_B} \qquad [27]$$

at the resonant frequency shift

$$\Omega = \Omega_B = qv \qquad [28]$$

For this condition the interaction is with a sound wave in the material. The frequency of the sound wave, and the gain, depend on the angle between the incident and scattered light. Using the vector relation

$$\mathbf{k}_B = \mathbf{k}_L - \mathbf{q}$$

depicted in Figure 3 and the approximations $\Omega_B << \omega_B, \omega_L, |k_B| \approx |k_L|$ we obtain

$$q = 2|k_L| \sin(\theta/2) \qquad [29]$$

The Brillouin frequency shift is then given by

$$\Omega_B = 2 n_L \omega_L (v/c) \sin(\theta/2) \qquad [30]$$

and the Brillouin linewidth is given by

$$\Gamma_B = \frac{4}{\rho_0} \left[\eta + \frac{\kappa}{C_p} \left(\frac{C_p}{C_v} - 1 \right) \right] \frac{\omega_L^2 n_L^2}{c^2} \sin^2(\theta/2)$$
$$= \Gamma'' \sin^2(\theta/2) \qquad [31]$$

The peak Brillouin electrostrictive gain is then given by

$$g_B^e = \frac{\omega_B \gamma^2 \omega_L}{n_B c^3 v \rho_0 \Gamma_B} \sin(\theta/2) \qquad [32a]$$

$$g_B^e = \frac{\omega^2 \gamma^2}{n_B c^3 v \rho_0 \Gamma'' \sin(\theta/2)} \qquad [32b]$$

where we have used the approximation $\omega_B \approx \omega_L = \omega$.

The maximum electrostrictive SBS gain is independent of the laser frequency because the Brillouin linewidth is proportional to the square of the laser frequency.

As a function of angle the maximum Brillouin gain is usually observed in the backward direction. This is consistent with the form of the gain coefficient given in [32a], which indicates that the gain is proportional to $\sin(\theta/2)$. However, when the angular variation of the Brillouin linewidth is also accounted for, the gain coefficient is actually minimum in the backward direction [32b]. Typical laboratory experiments involve pencil-like geometries in which the interaction length is significant only in the backward or forward directions. In these situations, the total gain is actually maximum in the backward direction, where the interaction length is longest. Although the formulas appear to indicate that the gain goes to infinity in the forward direction, the damping time, which is proportional to Γ_B^{-1}, also goes to infinity and the interaction becomes transient. Under these conditions the gain parameter is proportional to $\sin(\theta/2)$ and the Brillouin gain goes to zero in the forward direction. Under some geometries Brillouin scattering at 90° to the laser can also be significant. It can be a source of damage to large glass components in high-power lasers.

For thermal Brillouin scattering the gain has a dispersive shape centered on the frequency shift $\Omega = \Omega_B$, with loss occurring on the low-frequency side and gain occurring on the high-frequency side, peaking at a frequency $\Omega = \Omega_B + \Gamma_B/2$. The maximum absorptive SBS gain depends on the laser frequency as ω^{-1}.

Table 3 shows representative values of the Brillouin linewidth and gain coefficients for a selection of substances.

Brillouin-enhanced four-wave mixing is a related effect that involves both a downshifted wave and an upshifted wave in which the coherent interaction is enhanced by the resonance associated with the sound wave. Gains of the order of 10^5 can be realized. Systems based on this effect are often used for phase conjugation.

Stimulated Rayleigh Scattering

Stimulated thermal Rayleigh scattering (R) can be observed in liquids while Stimulated Rayleigh wing scattering (SRWS) is observed in liquids with anisotropic molecules. Additionally, stimulated Rayleigh scattering due to fluctuations of concentration in gas mixtures can also occur. For R the internal mode obeys a diffusion equation. The R gain is given by

$$g_R = g_R^e + g_R^a$$

Table 3 Properties of stimulated Brillouin scattering for selected materials

Substance	*Laser wavelength (nm)*	*Frequency shift (Ghz)*	$\Delta\nu$ *(MHz)*	τ_B (ns)	g_B^e *(cm/GW)*	g_B^a/α (cm/GW)*
Liquid						
Acetone	532	5.93	361	0.44	12.9	22
Benzene	532	8.33	515	0.31	12.3	24
CS_2	532	7.7	120	1.9	130	20
CCl_4	532	5.72	890	0.18	8.77	13
Chloroform	532	5.75	635	0.25	11.7	
Ethanol	532	5.91	546	0.29	12*	10
Methanol	532	5.47	325	0.49	10.6	13
Water	532	7.4	607	0.26	2.94	0.8
Gas						
Xenon (7599 torr)	532	0.654 ± 0.024	98.1 ± 8.9	$0.65\lambda_P^2P$	1.38 ± 0.19	
SF_6(20 bar)	1320	0.2		35		
N_2(100 bar)	1320	0.5		30		
Solid						
BK 7	532	34.65 ± 0.039	165.0 ± 8.6		2.15 ± 0.21	
CaF_2	532	37.164 ± 1.185	45.6 ± 8.8		4.11 ± 0.65	
Plexiglas	532	15.687 ± 0.036	253.7 ± 12.6			
SiO_2	488	35.6	156		4.482	

*Absorptive maximum gain SBS values at 694 nm, with permission from Boyd RW (1992) *Nonlinear Optics*. Academic Press: New York. Reproduced from Reintjes J and Bashkansky M (2001) Stimulated Raman and Brillouin scattering. In: Bass M (ed.) *Optical Society of America Handbook of Optics*, Ch. 18, 2nd ed., vol. IV. New York: McGraw-Hill.

where g_R^e and g_R^a are the electrostrictive and absorptive contributions given by

$$g_R^e = \frac{\omega\gamma^2(\delta - 1)}{4\rho_0 n_L n_R v^2 c^2}\,\frac{4\Omega/\Gamma_R}{1 + (2\Omega/\Gamma_R)^2} \qquad [33]$$

$$g_R^a = \frac{-\omega\gamma\gamma_a\Omega_B}{2\rho_0 n^2 v^2 c^2 \Gamma_R}\,\frac{4\Omega/\Gamma_R}{1 + (2\Omega/\Gamma_R)^2} \qquad [34]$$

Both contributions to the STRS gain have dispersive forms. The electrostrictive contribution is maximum for a down-shifted wave with $\Omega = \frac{1}{2}\Gamma_R$. Its maximum value scales linearly with laser frequency. For the absorptive process the gain depends inversely on the laser frequency, and is maximum for an upshifted wave with $\Omega = -\frac{1}{2}\Gamma_R$. Table 4 shows representative values of the Rayleigh linewidth and gain coefficients for a selection of substances.

Table 4 Properties of stimulated Rayleigh scattering for some materials at a wavelength of 694 nm

Substance	*Calculated maximum steady state gain factor*		*Linewidth* $\delta\nu_R$ *(MHz)*
	g_R^e*(max) (cm/MW)*	g_R*(max)/*α *(cm²/MW)*	
CCl_4	2.6×10^{-4}	0.82	17
Methanol	8.4×10^{-4}	0.32	20
CS_2	6.0×10^{-4}	0.62	36
Benzene	2.2×10^{-4}	0.57	24
Aceton	2.0×10^{-4}	0.47	21
H_2O	0.02×10^{-4}	0.019	27.5
Ethanol		0.38	18

Reproduced from Kaiser W and Maier M (1972) Stimulated Rayleigh, Brillouin and Raman Spectroscopy. In: Arecchi FT and Schulz-DuBois EO (eds) *Laser Handbook*, vol. 2, pp. 1077–1150. Amsterdam, The Netherlands: North Holland.

Parametric Fluorescence

Some types of stimulated interactions do not involve exchange of energy with the material. These include parametric down-conversion and self-focusing. In parametric down-conversion an incident wave at frequency ω_L scatters into two longer-frequency light waves at signal and idler frequencies ω_s and ω_i. They satisfy the frequency and wavevector relations

$$\omega_L = \omega_s + \omega_i$$
$$k_L = k_s + k_i$$

The equations for the waves are:

$$\frac{\partial}{\partial z}A_s = -i\left(\frac{\omega_s}{2n_s c}\right)\chi^{(2)}A_L A_i^*$$

$$\frac{\partial}{\partial z}A_i = -i\frac{\omega_i}{2n_i c}\chi^{(2)}A_L A_s^*$$

where A_s and A_i are called the signal and idler fields. The solution for the signal field takes the following form:

$$A_s(z) = A_s(0)\cosh\left(\sqrt{|\kappa|^2|A_L|^2}z\right) - i\sqrt{\frac{\omega_s n_i}{\omega_i n_s}}A_i^*(0)\sinh\left(\sqrt{|\kappa|^2|A_L|^2}z\right) \quad [35]$$

where

$$|\kappa|^2 = (\omega_s\omega_i/4n_s n_i c^2)|\chi^{(2)}|^2$$

The stimulated parametric interaction provides gain for input signal and idler waves. For large values of $\sqrt{|\kappa|^2 A_L|^2}\ z$ the gain becomes exponential in character, similar to the gain in SRS and SBS. When no incident signals are supplied, the source terms in [35] are the vacuum fluctuations at the signal and idler frequencies. Stimulated parametric fluorescence is the basis for parametric oscillators that provide tunable coherent radiation over a wide wavelength range in the visible and infrared.

Stimulated Photorefractive Scattering

Stimulated light scattering also takes place in photorefractive materials. These materials include crystals such as $LiNbO_3$, $BaTiO_3$, $Bi_{12}SiO_{20}$, and others. They possess a unique property of photo-induced index change with very low light intensities. Some of the potential applications include real-time holography, information recording, phase conjugation, parallel signal processing, and ultrafast optical gating. The nonlinearities leading to stimulated scattering are very large and can produce a significant gain in millimeter thick crystals. In order for amplification of scattered light to take place the nonlinearities have to have a nonlocal character due to diffusion or drift fields. Figure 4 shows a two-beam interaction effect in a photorefractive medium leading to stimulated scattering. Solid lines represent intensity maxima of interfering light beams while dashed lines represent diffused index change maxima. The fact that the two do not overlap allows amplification of the signal beam, with the maximum gain occurring at π/2 phase shift.



Figure 4 Stimulated photorefractive scattering diagram showing incident pump and signal beams, amplified signal beam, and an index grating formed in the photorefractive crystal.

Stimulated Compton and Thomson Scattering

Light scattering from free electrons is described by Thomson scattering in the low-energy limit, with a cross-section of $(8\pi)/(3)((e^2)/(4\pi\varepsilon_0 mc^2)^2)$, and by Compton scattering in the relativistic limit. Stimulated Thomson or Compton scattering is the source of light emitted from free electron lasers. In these interactions, the electron scatters incoming radiation in its rest frame to a backscattered wave. The ponderomotive force resulting from the interaction with the scattered waves increases the periodic electron bunching, which in turn increases the efficiency of scattering. In some cases, the incoming electromagnetic wave is provided by a microwave source, while in others it arises from a static magnetic wiggler, which appears as an incident electromagnetic wave in the electron rest frame because of a relativistic Lorentz transformation. Free electron lasers are a source of tunable coherent radiation from the microwave region to the ultraviolet.

Self-focusing

In the presence of a strong laser field with intensity I, the refractive index of many materials changes according to the relation

$$n = n_0 + n_2 I$$

where n_2 is termed the nonlinear index. This change in refractive index gives rise to several effects, depending on the temporal and spatial properties of the light. In one type of interaction, a strong forward beam couples to two weaker beams that propagate at small forward angles, providing gain for the weaker beams. One of the weak beams interferes with the strong forward beam to form a phase grating through the nonlinear index, providing gain for the second weak beam. The interference of the second weak beam with the forward beam forms a second phase grating, providing gain for the first weak beam, thereby completing the coupling for the stimulated process. This effect is similar to Stoke/anti-Stokes Raman scattering, except that the coupling is between waves propagating in different directions rather than between waves with different frequencies.

For interactions with an instantaneous relaxation time, the gain for waves propagating at a small angle to the forward direction is given by

$$g = \frac{K_\perp}{2k}\sqrt{K_{\max}^2 - K_\perp^2}$$

where $K_\perp = \sqrt{k_x^2 + k_x^2}$ is the transverse wavevector, corresponding to the angle

$$\theta = \frac{K_\perp}{k}$$

and

$$K_{\max} = 4k^2 n^{\mathrm{L}} n_2 I$$

is the largest transverse k-vector for which gain is observed. The maximum gain is given by

$$g_{\max} = \frac{K_{\max}^2}{4k}$$

and occurs for an angle corresponding to

$$K_\perp = \frac{K_{\max}}{\sqrt{2}}$$

When the physical interaction that causes the refractive index to change with light intensity has a nonzero relaxation time, gain can be observed at angles larger than that given by $K_{\max}$.

This stimulated four-photon effect can be interpreted as the initiating stage of self-focusing. In the self-focusing effect, a laser beam with a normal mode profile (more intense in the center than at the edges) creates a positive lens in the material, focusing the beam. As the beam intensifies, the power of the lens increases, causing the beam to focus more tightly and eventually coming to a catastrophic focus if other nonlinear effects do not limit the intensity. The four-photon stimulated effect described above results in the spread of k-vectors of the forward beam, corresponding to a reduction in its diameter.

Self-focusing is responsible for breakdown and damage in many solids. Self-focusing in high-power lasers is commonly suppressed by restricting transverse k-vectors to values well below those of maximum gain.

See also

Nonlinear Optics, Applications: Self-Focusing and Related Effects (Solitons and Multiphoton Absorption). **Nonlinear Optics, Basics:** Photorefraction. **Scattering:** Scattering Theory.

Further Reading

Bloembergen N (1965) *Nonlinear Optics*. New York: Benjamin.

Bloembergen N (1967) The stimulated Raman effect. *American Journal of Physics* 35: 989–1023.

Boyd RW (1992) *Nonlinear Optics*. New York: Academic Press.

Fabellinskii IL (1968) *Molecular Scattering of Light*. New York: Plenum.

Gunter P and Huignard J-P (eds) (1989) *Photorefractive Materials and their Applications II*. Springer-Verlag Topics in Applied Physics, vol. 62. Berlin: Springer-Verlag.

Kaiser W and Maier M (1972) Stimulated Rayleigh, Brillouin and Raman spectroscopy. In: Arecchi FT and Schulz-DuBois EO (eds) *Laser Handbook*, vol. 2, pp. 1077–1150. Amsterdam, The Netherlands: North Holland.

Milanovich F (1986) Stimulated Raman scattering. In: Weber MJ (ed.) *Handbook of Laser Science and Technology. Optical Materials*, vol. III. Boca Raton, FL: CRC Press.

Penzkofer A, Laubereau A and Kaiser W (1979) High intensity Raman interactions. *Progress in Quantum Electronics* 6: 55–140.

Rabin H and Tang CL (eds) (1975) *Quantum Electronics: A Treatise*. Part A, vol. 1. New York: Academic Press.

Raymer MG and Walmsley IA (1990) The quantum coherence properties of stimulated Raman scattering. In: Wolf E (ed.) *Progress in Optics*, vol. XXVIII, p. 183. Amsterdam, The Netherlands: Elsevier.

Reintjes JF (1984) *Nonlinear Optical Parametric Processes in Liquids and Gases*. New York: Academic Press.

Reintjes JF (1995) Stimulated Raman and Brillouin scattering. Handbook of laser science and technology, supplement 2. In: Weber MJ (ed.) *Optical Materials*, pp. 334–364. Boca Raton, FL: CRC Press.

Reintjes J and Bashkansky M (2001) Stimulated Raman and Brillouin scattering. In: Bass M (ed.) *Optical Society of America Handbook of Optics*, Ch. 18, 2nd ed., vol. IV. New York: McGraw-Hill.

Shen YR (1984) *Principles of Nonlinear Optics*. New York: Wiley.

Shen YR and Bloembergen N (1965) Theory of stimulated Brillouin and Raman scattering. *Physical Review* 137: A1787.

SEMICONDUCTOR MATERIALS

Contents

Amorphous Semiconductors
Band Structure Engineering
Dilute Magnetic Semiconductors
GaAs Based Compounds
Group IV Semiconductors, Si/SiGe
III-Nitrides
Large Gap II–VI Semiconductors
Lead Salts
Mercury Cadmium Telluride
Modulation Spectroscopy of Semiconductors and Semiconductor Microstructures
Quantum Dots
Type-II Quantum Wells and Superlattices

Amorphous Semiconductors

J I B Wilson, Heriot-Watt University, Edinburgh, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Amorphous semiconductors comprise several classes of materials having a range of useful properties that have made many of them commercially important. Their special characteristics are derived from the particular techniques used in their synthesis, and include the ability of some to change their structure under the influence of heat or illumination. Many are photoconductive, making them valuable for photodetectors when large area devices are required (e.g., xerography), or photovoltaic, hydrogenated amorphous silicon being widely used in thin-film solar cells.

'Amorphous' means noncrystalline, thus encompassing glassy materials and disordered covalent-bonded materials. Glasses, such as the amorphous chalcogenides (glassy sulfides, selenides, and tellurides), melt to viscous liquids when heated, whereas disordered semiconductors like amorphous silicon are metastable thin films that vaporize or crystallize when heated. Two other groups of glassy semiconductors, the covalent-bonded II–IV–V_2 compounds and ionic-bonded oxides (e.g., $V_2O_5P_2O_5$) will not be discussed here. Amorphous organic semiconductors are receiving much interest now, because of their potential use in low-cost display devices, but are more logically treated as polymer materials.

The following sections explain the main preparation methods and the structures that result, the importance of defects and the influence these have on optical and electrical behavior, and some of the most important applications.

Amorphous Structure

The common property that distinguishes all amorphous materials from crystalline ones is the absence of long-range order in their atomic structure. These disordered solids have no periodic or translational symmetry. The term is sometimes loosely applied, and it should be noted that elements and compounds that are able to form several structures might contain different phases. An example is 'hard carbon' which in thin-film form may contain tetrahedral amorphous carbon and hydrogenated amorphous carbon, as well as microcrystallites of graphite and diamond. Interestingly, the prediction in 1989 by A.Y. Liu and M.L. Cohen, that crystalline cubic-C_3N_4 would be even harder than diamond, has not been confirmed by experiment. Only a hard amorphous C_xN_y has been produced, even by nitrogen ion beam assisted sputtering of graphite, which it was thought would have provided sufficient energy to form the close C–N bonds.

When the common crystalline semiconductors, Si and Ge, melt they become liquid metallic conductors. This is because the solid is formed by directional covalent bonds that produce tetrahedral packing of the atoms. In the liquid the bonds are weakened and a closer packed structure found in metals results. However a less ordered atomic arrangement results from condensing vaporized Si or Ge on to a cold substrate. In this case the atoms cannot move into their preferred positions for either tetrahedral or close packing arrays and instead are frozen almost wherever they land. Nonetheless, the arrangement of atoms is closer to that of the tetrahedral crystalline semiconductor than that of the metallic liquid. The radial distribution function of an amorphous semiconductor provides the numbers of atoms versus distance from an arbitrary atom. It shows that the nearest-neighbor distance is the same as in the equivalent crystalline material, although with some spread of values, but that the separation of atoms further away has a less well-defined value. Thus pure amorphous Si and Ge retain the directional covalent bonds between nearest neighbors but have distorted bond angles that make next nearest neighbors lie in different positions from the equivalent crystalline solid. Consequently there is only short-range order and the atoms form a continuous random network, a concept introduced by W.H. Zachariasen in 1932 for glasses. The deposition conditions generally lead to further disruptive effects that will incorporate small voids where the distortion is too large to allow a bond between atoms. These voids together with broken bonds give a defective network that is far from the ideal random tetrahedral 'lattice'.

Amorphous Semiconductor Energy Bands

A frequently asked question is 'Why can amorphous materials show semiconducting behavior?' since they do not have the periodic structure that leads to the allowed energy band scheme in crystalline semiconductors. However, note that metals do not become insulators when they melt, demonstrating that electrical conductivity does not require a periodic atomic structure. In fact, electron energy levels in solids may also be derived by considering chemical bonds when discrete atoms are brought closer together. The valence band in a semiconductor arises from the electron bonding orbitals and the conduction band from the antibonding electron orbitals. The forbidden energy gap (bandgap) is the separation between these two bands, which are only partially filled in semiconductors at room temperature. Thus amorphous semiconductors will have bonding and antibonding energy bands, and a more or less well-defined bandgap according to the defect content.

In fact, pure amorphous Si and Ge are extremely poor semiconductors due to an ill-defined bandgap and the large concentration of defects. Distorted bonds produce allowed electron energy levels that lie adjacent to the well-defined bands in crystals, producing tails of energy levels extending into the bandgap. Electrons that take up these 'tail state' energies are not entirely free to move through the solid but can only hop from one defective site to another. Additional defects arise from unsatisfied covalent bonds that 'dangle' in the spaces between the atoms. These produce electron energy levels within the forbidden gap (Figure 1). Indeed, their concentration is so high in amorphous silicon produced from a condensed silicon vapor, that they fix the position of the Fermi level at approximately the middle of the bandgap and the semiconductor has a high resistivity. The usual option of reducing a semiconductor's resistivity by adding small amounts of dopants from adjacent columns of the periodic table has little effect in this case. A donor atom from group V (e.g., phosphorus) may have all five valence electrons satisfied by a locally distorted arrangement of silicon atoms, instead of having only four bonded electrons and a loosely bound electron as in crystalline silicon. A similar picture exists for an acceptor atom from group III (e.g., boron).

Semiconductors containing group VI elements, S, Se, or Te, have two-fold coordination instead of the tetrahedral arrangement of the group IV elements, Si and Ge. The bonding between atoms in the solid is formed from four of the six p-electrons, which give



Figure 1 Schematic density of states for hydrogenated amorphous silicon.

rise to the bonding and antibonding energy bands of the solid, and the two remaining p-electrons from each atom form a non-bonding 'lone pair'. The lone pair energy band lies between the bonding and antibonding bands, and is the highest filled band in the solid, thus being the valence band.

Just as in amorphous Si or Ge, dangling bond defects will have energies between the valence and conduction bands, but in lone-pair semiconductors such disturbed energy states will now produce energy levels that fall within the lone pair band instead of within the bandgap. This makes it difficult to dope chalcogenide semiconductors, especially by donors, since the additional energy levels often lie within an existing energy band. Similar considerations apply to ternary chalcogenide alloys: these will have lone-pair bands arising from the group VI element, with additional energy levels from the other components (e.g., from group IV or V). However, amorphous chalcogenides will also contain three-fold coordinated chalcogenide atoms and these defects can associate in pairs or may interact with an adjacent two-fold coordinated atom. Defect centers with two oppositely charged chalcogens may form a 'valence alternation pair' (VAP).

So it may be seen that the semiconducting behavior of solids arises from the nearest-neighbor interactions of the atoms giving rise to allowed electron energy bands, and that long-range order is not necessary to produce the semiconductor's forbidden energy gap. Defects then produce localized energy levels that usually lie within the forbidden gap.

Preparation of Amorphous Silicon

Despite the early use of selenium as a photoconductive semiconductor in xerography, most amorphous semiconductors might have stayed as curious but technologically impractical materials, if an alternative preparation method to physical vapor deposition had not been discovered.

In the 1950s the preparation of high-purity single-crystal silicon was not yet established, and work at Standard Telecommunication Laboratories, UK, was attempting to use radio-frequency heating to produce silicon from low-pressure silane gas (SiH_4). It was noticed that a side effect was a deposit of resistive, noncrystalline material on cool parts of the container, close to unwanted plasma 'glow discharges'. In following up this observation, the technique was developed to produce a variety of other useful compounds from electrical discharges in appropriate gas mixtures, particularly silicon nitrides and oxides. With new scientific interest in amorphous semiconductors, the silicon coatings from silane were examined in more detail, and were shown to be significantly different from amorphous silicon produced by evaporating and condensing silicon. This new form was very photoconductive and could be doped n-type by adding phosphine to the silane. A more detailed study of doping led to the seminal papers by W.E. Spear and P.G. LeComber of Dundee University, UK, and to an explosive growth in the whole subject, once the potential commercial applications became apparent.

Despite many alternative synthesis methods, plasma chemical vapor deposition (CVD) remains the most widely used, and produces material that has not been surpassed in quality. The key features are a vacuum chamber into which a controlled flow of each of the gaseous sources is fed, and a heated plate on which the substrate is placed for coating. The decomposition of the gases is driven by an electrical discharge between two electrodes, which enables the gas temperature to be much lower than in conventional pyrolysis (thermal CVD). An important aspect of the process is the incorporation of hydrogen into the deposited material, which is thus more accurately known as hydrogenated amorphous silicon, a-Si:H. In the best material, hydrogen is mainly bonded singly as Si–H, but if the preparative conditions are not optimum then there may also be large amounts of $Si{-}H_2$ (as may be seen from the infrared absorption spectra). Alternative source gases usually contain hydrogen (e.g., Si_2H_6), and hydrogen may be added as a diluting agent for the doping gases (e.g., B_2H_6 or PH_3). Other precursors include fluorinated gases, but these have failed to give the predicted improvements in performance of the semiconductor in such applications as solar cells, and have greater chemical reactivity.

Since silane is spontaneously flammable in air, and the dopant gases are not only flammable but also very toxic, efforts have been made to produce a-Si:H by other means. Sputtering from undoped or doped silicon targets has been a popular choice, but it is still necessary to incorporate hydrogen into the deposited material, for instance by adding it to the usual argon sputter gas. This is because hydrogen serves to passivate unsatisfied 'dangling' Si bonds and to reduce the stresses that would occur in a pure silicon network. Photo-CVD, using ultraviolet light to drive the reaction without raising the temperature, can produce high-quality material but has the problem of unwanted silicon deposits on the illuminated reaction chamber window. Although conventional silane pyrolysis is not suitable for producing a-Si:H, because the temperatures needed for useful deposition rates also remove much of the hydrogen if the substrate is too hot, it is possible to heat the gas separately from the substrate by means of a hot filament and so produce good-quality films.

Other hydrogenated silicon alloy semiconductors are synthesized by additions to silane of ammonia (giving amorphous silicon nitride, a-Si:N:H), or a hydrocarbon gas such as methane (giving a-Si:C:H), or germane (giving a-Si:Ge:H).

Preparation of Amorphous Chalcogenides

Unlike the tetrahedral group IV elements, useful members of this class of amorphous semiconductors may be produced by vacuum evaporation and condensation on to a relatively cool substrate. Compounds, such as As_2Se_3, do not evaporate congruently and so the deposit will change composition as the evaporation proceeds. More uniform compositions may be obtained by sputtering with argon, and glassy oxides may also be obtained in this way with oxygen added to the inert gas. Chalcogenide glasses may also be prepared by rapid cooling from a melt, or by chemical vapor deposition from heated vapor precursors. Since glasses are thermodynamically unstable, they will tend to transform to a more stable, sometimes crystalline structure. The rate for this process depends on the temperature and may be effectively too slow to observe.

Optical Properties of Amorphous Semiconductors

Optical absorption spectra of amorphous semiconductors clearly show a forbidden energy gap. By plotting a suitable function of the absorption coefficient, α, versus photon energy, $h\nu$, usually that given by J. Tauc, $(\alpha h\nu)^{1/2}$, the 'optical gap' may be determined from the intercept of the linear portion of the plot with the x-axis. Unlike crystalline semiconductors, amorphous ones have no k-selection rules to give indirect and direct transitions across the bandgap, thus a-Si:H behaves as a direct gap material. This 'optical gap' is greater than the bandgap determined from electrical conductivity measurements, since the latter will have contributions from both localized bandtail states (low electrical mobility) and extended states (high electrical mobility) (Figure 2).

The absorption spectra also have a portion at lower photon energies having an exponential dependence on photon energy, known as the Urbach tail. This is related to the structural disorder in the material and the tail states. Transitions involving defect bandgap states lie at even lower photon energy, and the density of defects can be determined from the weak absorption in this region of the spectrum, perhaps by using photothermal deflection spectroscopy to detect the weak optical absorption.

Photoluminescence also provides a probe of the defect content of many materials. Interpretation and identification of the actual defect (e.g., chemical impurity or structural imperfection) is aided by



Figure 2 Typical optical absorption spectra of hydrogenated amorphous silicon and arsenic sulfide.

reference to the crystalline form. Both crystalline and amorphous forms of chalcogenide have a wealth of special effects, including reversible photoinduced bleaching and darkening, and laser-induced crystallization and amorphization. In addition the creation and dispersal of defects by appropriate illumination of some amorphous chalcogenides is accompanied by changes in the electron spin resonance (ESR) signal. Some of these effects have been the basis for applications in optical memories. More prosaically, chalcogenide glasses are important infrared transparent materials and amorphous chalcogenide thin films have had historical importance as the photoconductive layer in xerography, although here they are now being supplanted by less toxic amorphous silicon alloys.

Electrical Properties of Amorphous Semiconductors

The electrical conductivity of amorphous semiconductors is often controlled by the defects that are introduced by impurities or by structural flaws. For a-Si:H this provides alternative conduction mechanisms, via extended state electron and hole conduction (as in crystalline silicon), and via hopping of electrons or holes through localized energy levels within the bandtails or within the bandgap. The relative importance of each route depends on the temperature and on the density of states (DOS) in each energy range, as well as on the mobility of the charge carriers.

These different conduction mechanisms are clearly seen in the temperature dependence of the conductivity of a-Si:H and of many amorphous chalcogenides, since a semilog plot of conductivity versus $1000/T$ K will have portions with different slopes as each mechanism dominates a particular temperature range. Near room temperature, good-quality a-Si:H films in the dark exhibit a well-defined Arrhenius relationship with an activation energy that is the energy separation of the Fermi level from the conduction band extended states, electrons dominating the conductivity. The conduction band extended states do not have the high electron mobility found in crystalline silicon, due to the disruption of long-range order and the consequent increased electron scattering. Typical electron mobilities in a-Si:H are $\sim 1\,\mathrm{cm^2\,v^{-1}\,s^{-1}}$, and hole mobilities are even lower.

The band tail states have even worse carrier mobilities, since movement is by hopping to vacant sites that might lie at some distance, and hopping is unlikely between sites that have a large energy difference. (The process has an inverse exponential dependence on the energy difference between the initial and final states.) Hopping of carriers between states that lie within the bandgap is a significant contribution to the conductivity only at low temperatures, unless the density of such defects is high. In materials having weakly localized states, nearest-neighbor hopping is supplanted by variable range hopping, as carriers prefer to hop to a more distant site if it has a smaller energy difference from the starting site than do the neighboring sites. As the temperature is lowered, this hopping distance will increase and the conductivity has N.F. Mott's characteristic $\exp(-B/T^{1/4})$ dependence on temperature, T. Lower-quality films deposited by plasma CVD on to unheated substrates tend to be p-type due to hopping conductivity through the high density of defect states. The link between substrate deposition temperature and material quality is caused by the way in which hydrogen is incorporated into the growing material: high temperatures allow only singly bonded hydrogen, which passivates dangling bonds thus removing bandgap defect energy levels. Low temperatures also allow hydrogen to be incorporated as $\mathrm{Si{-}H_2}$ and this disrupts the Si–Si lattice bonding, producing more defect levels. Confirmation of this effect is obtained from sputtered amorphous silicon, with and without hydrogen added to the argon.

When a-Si:H is illuminated it may show strong photoconductivity, depending on the preparative conditions. Free carriers are generated by the illumination but may fall into defect states (energies within the band gap) where they can be released or can recombine with the oppositely charged carriers. The detailed response to light (wavelength, intensity, duration) and temperature thus depends on the distribution and concentration of defects. Luminescence effects are similarly influenced. Most amorphous chalcogenides are only weakly photoconductive due to their high density of gap states, those near the middle of the gap (e.g., VAPs) being highly effective recombination centers.

The electrical properties of other hydrogenated amorphous tetrahedral semiconductors based on silicon are determined by their defect populations, and in general they are less well behaved. a-Si:Ge:H and a-Si:Sn:H have reduced bandgaps and a-Si:C:H and a-Si:N:H have increased bandgaps, which offer many possibilities for multilayer device design, provided that their normally high defect contents can be reduced or controlled.

The study of glassy semiconductors was stimulated in the 1960s by the discovery of electrical switching in sputtered multicomponent thin films.

These simple devices changed from a nonconducting to a conducting state when the applied electric field exceeded a certain threshold, and returned to their initial state when the current fell below a certain value. A variety of other switching types was discovered, especially under pulsed operation, including those having a memory effect based on the reversible crystallization and vitrification of a narrow filament between the contacts. A theoretical model of these devices comprises both electronic and thermal effects, which are responsible for initiating the switching event and for memory effects. A practical problem has been the variable jitter in the switching time.

Applications

Amorphous silicon alloy films are valuable as the active layers in thin-film photovoltaic cells, two-dimensional optical position detectors, linear image sensors (optical scanners), and thin-film transistors used in liquid crystal display panels. They also have uses as antireflection coatings and planar optical waveguides. Amorphous chalcogenide films have been used as electrical switches and memory devices, for optical data storage, and as dry photoresists and electron beam resists. Both types of amorphous material have been used in xerography and medical X-ray imaging detectors.

Amorphous silicon solar cells have power conversion efficiencies of ~12% for the most complicated structures. These are tandem cells that use different alloys (including a-Si:C:H) for the various layers, in order to enhance effective absorption of the solar spectrum. A serious drawback of using amorphous semiconductors in electronic devices is their short carrier diffusion length. In solar cells this is circumvented by ensuring that there is a built-in field to separate photogenerated electron–hole pairs before they can recombine. Because doped amorphous silicon alloys have high defect densities, it is difficult to make the effective pn junctions that provide such built-in fields in conventional crystalline silicon cells. Instead, amorphous silicon cells use pin structures, where the i-layer is effectively undoped and provides an extended electric field between the p-i and i-n junctions. Long periods of illumination increase the dark current in these devices, as additional defects are generated. This 'Staebler–Wronski effect' is believed to be associated with hydrogen movement at a passivated dangling bond (Si–H) and a nearby weak Si–Si bond. It is a cause of slow degradation in unstabilized solar cells although the change may be reversed by thermal annealing.

In contrast to 'minority carrier' photovoltaic devices, thin-film transistors necessitate the control of majority carriers alone. To address each pixel in a liquid crystal display, a switching element is needed and simple thin-film transistors fulfill this role. Although low carrier mobilities in amorphous semiconductors restrict the current passed and switching speeds, the requirement for coating large area glass panels at low temperatures make a-Si:H with a-Si:N:H gate dielectric almost the only options. Improved performance is possible by using pulsed laser irradiation to change the amorphous semiconductor to polycrystalline material.

Further Reading

Brodsky MH (ed.) (1985) *Amorphous Semiconductors*, 2nd edn. Berlin: Springer-Verlag.

Elliot SR (1984) *Physics of Amorphous Materials*. London: Longman.

EMIS Datareviews Series No.1 (1989) *Properties of Amorphous Silicon*, 2nd edn. London: INSPEC.

Joannopoulos JD and Lucovsky G (eds) (1984) *The Physics of Hydrogenated Amorphous Silicon*. Topics in Applied Physics, vols 55 and 56. Berlin: Springer-Verlag.

Journal of Non-Crystalline Solids (2000) *Proceedings of the 18th International Conference on Amorphous and Microcrystalline Semiconductors (1999)*, vol. 266–269. This journal has published the proceedings of most of these well-established annual meetings dealing with all aspects of amorphous semiconductors.

Kramer B and MacKinnon A (1993) Localization – theory and experiment. *Reports on Progress in Physics* 56: 1469–1564.

Luft W and Tsuo YS (1993) *Hydrogenated Amorphous Silicon Alloy Deposition Processes*. New York: Marcel Dekker.

Madan A and Shaw MP (1988) *The Physics and Applications of Amorphous Semiconductors*. San Diego, CA: Academic Press.

Mott NF (1985) Electrons in non-crystalline materials – the last twenty five years. *Contemporary Physics* 26: 203–215.

Pankove JI (volume ed.) (1984) Hydrogenated amorphous silicon. In: Willardson RK and Beer AC (series eds) *Semiconductors and Semimetals*, vol. 21, Parts A–D. Florida: Academic Press.

Zallen R (1983) *The Physics of Amorphous Solids*. New York: Wiley.

Band Structure Engineering

C R Pidgeon, Heriot-Watt University, Edinburgh, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Direct gap semiconductors have many unique properties which are advantageous for optical and electronic applications, and in particular for detectors and emitters of infrared radiation associated with interband optical transitions. Gallium arsenide, GaAs, based structures have principally been used in the near-infrared, and so-called narrow gap semiconductors in the mid-infrared (MIR) spectral regions. More recently systems based on intersub-band transitions have shown great promise for MIR devices, with the obvious advantage for some applications that they can be constructed from large gap, better controlled materials (mainly InP- and GaAs-based to date) and have a peak operating frequency which is determined simply by the design of the particular quantum structure. Both approaches have been substantially advanced by band structure engineering techniques, reducing Auger losses and phonon losses, respectively, which is the subject of the present work.

The classic examples of narrow gap materials are the III–V semiconductors (InSb, InAs, and their related alloys), II–VI semiconductors (mainly $Hg_{1-x}Cd_xTe$), and the lead salt alloys. As a direct result of the small energy gap, these materials have a very low electron effective mass, very high electron mobility, even at room temperature, and a high saturation velocity. In addition they have a high ratio of stimulated to spontaneous transition probabilities and a large nonlinear susceptibility. However, they have the disadvantage of a high intrinsic carrier density at room temperature and thermal generation rate, so that a fundamental limitation to the performance of devices at elevated temperatures (preferably room temperature) is nonradiative losses resulting from Auger recombination processes. One solution is to cool these systems to 80 K or below which involves expensive and bulky cooling methods such as Stirling-cycle coolers, negating their advantages over other, otherwise inferior, devices. In the past 10 years there has been an intensive effort to circumvent this limitation by quantum structure and so-called 'band structure engineering' techniques made possible by epitaxial growth techniques, whereby the Auger processes are suppressed. Since the emphasis of the band structure engineering work has been mainly towards the optimization of III–V semiconductor lasers rather than detectors, we reflect that emphasis here. Although developed more recently than the bipolar diode lasers, the unipolar quantum cascade (QC) lasers provide perhaps the best example of systems that can be conveniently optimized by band structure engineering techniques. In this case, phonon processes dominate so that the design is to do with phonon suppression. Thus, we are concerned principally with suppression of Auger processes for interband devices, and phonon processes for intraband devices.

Nonradiative Processes and Band Structure Engineering

Suppression of Auger Recombination

Electron recombination processes are dealt with in detail elsewhere in the Encyclopedia (*see* **Semiconductor Physics:** Recombination Processes) but we briefly summarize the main points here. It is well known that there are three principal interband recombination mechanisms by which thermodynamic equilibrium is established in semiconductors: Shockley–Read recombination, radiative recombination, and Auger recombination. These are shown schematically in Figure 1. The Shockley–Read recombination occurs via extrinsic energy levels produced by lattice defects and impurities, Figure 1a, and can in principle be controlled by the procedure used to grow the material; hence it does not provide a fundamental limit to the



Figure 1 Electronic processes in semiconductors: (a) Shockley–Read recombination; (b) radiative recombination; (c) Auger recombination; (d) impact ionization.

carrier lifetime. The radiative and Auger mechanisms (Figure 1b,c, respectively) are, however, fundamental and are determined by the electronic structure of the material. The former is central to the operation of light-emitting diodes and is approximately inversely proportional to the electron and hole concentration. Optimum detector operation is achieved in materials that are limited by the radiative lifetime mechanism. Thus, in both cases it is desirable to minimize Auger processes.

By contrast with the two-particle radiative recombination process, Auger recombination is a three-particle interaction. For example in one so-called CHCC (or Auger-1) process an electron collides with a second electron; the first electron recombines with a hole in the valence band and the energy produced by the electron–electron collision excites the second electron higher up into the conduction band. This second electron eventually de-excites by phonon emission, and can cause observable heating of carriers by an Auger type of up-conversion. However, for the present article we are only interested in the first part of the process, so we do not consider the heating further here. The Auger process is the inverse of impact ionization where an energetic conduction electron collides with a valence electron, thereby creating an electron–hole pair as shown in Figure 1d. The final state consists of two low-energy electrons and one hole. Analogously, in Auger recombination the initial state has three particles (e.g., two electrons and one hole) and the final state one (e.g., one electron). Due to this three-body nature, the collision probability (or transition rate) per unit volume, R, varies with the cube of the carrier concentration and (if $n = p$) may be written $R = Cn^3$, where n is the electron density and C is referred to as the Auger coefficient. Note that the Auger rate is sometimes defined per carrier as $R' = Cn^2 = 1/\tau_A$, where τ_A is the Auger lifetime.

Narrow gap III–V semiconductors have the familiar three-band (so-called Kane energy band structure – (*see* **Semiconductor Physics:** Band Structure and Optical Properties) consisting of an s-like conduction band separated by a small energy gap from a triply degenerate p-like valence band, part of whose degeneracy is raised by spin–orbit splitting as shown in Figure 2. Thus, a large number of permutations of Auger processes become possible for n- and p-type semiconductors. Those which are initiated by a collision between two electrons are referred to as conduction, or n-n, Auger processes (e.g., the CHCC process), and those by a collision between two holes as valence, or p-p, Auger processes. It can be shown that the n-n process (so-called CHCC or Auger-1) illustrated in Figure 3a is dominant in bulk n-type and the p-p process (so-called CHLH or Auger-7) shown in Figure 3c is dominant in bulk p-type semiconductors, and so these have received the most attention. For larger gap (shorter wavelength) semiconductors there is sometimes a significant resonance between the bandgap and the spin–orbit splitting and the p-p process (CHSH) shown in Figure 3b becomes important. Clearly these simple descriptions require extension when the more complex band structure of strained layer superlattice quantum systems is considered.



Figure 2 Schematic diagram of the conduction and valence band structure of InSb showing the energy bands around the Γ-point ($k = 0$) that are involved in Auger transitions.

With certain approximations, some analytic solutions for the Auger recombination rates are possible. This model is, while not appropriate for higher levels of band structure engineering, very important for giving an insight into how Auger effects should be studied, and how they themselves might be engineered. The approximations generally used are parabolic bands and Boltzmann statistics, but some further analytic results may also be obtained when these restrictions are relaxed. Bloch functions and Fermi's golden rule are utilized (*see* **Semiconductor Physics:** Recombination Processes) to describe the particle states, so obtaining the general expression for the Auger rate per unit volume. Energy and momentum conservation provide strong constraints on the resulting integral, and give rise to a considerable reduction in the Auger transition rate. However if, for example, the momentum conservation constraint is relaxed due to occupied levels existing with a broad range of momenta, such as at some band extremum with a



Figure 3 Important Auger recombination mechanisms for mid-infrared (MIR) semiconductor detectors and lasers: (a) CHCC or Auger-1; (b) CHSH; (c) CHLH or Auger-7.

large effective mass, then the Auger rate will be strongly enhanced. Or to put it the other way round, the Auger rate can be reduced by engineering the band structures such that the heavy hole effective mass is reduced (e.g., by stress – see below) to approach that of the conduction band. Furthermore, since we are concerned with nonradiative recombination across the bandgap with energy E_g, any energy levels (again band extrema in particular) separated from the conduction or valence band edges by E_g are particularly susceptible to the excitation part of the Auger process. The Auger rate may therefore be reduced by designing the structure so that there are no band extrema at energies E_g from the conduction and valence band edges.

Interband (Bipolar) Lasers

The technology of band structure engineering, which includes superlattices, quantum confinement, and intentional incorporation of strain, has now become sufficiently advanced that it can be employed in a routine manner. As originally proposed, the modified band structure of strained III–V quantum-well structures can lead to significant benefits for diode laser performance, including reduced threshold current density, improved efficiency, and enhanced dynamic response and speed. Predicted advantages have been demonstrated, although for near-infrared devices these have not been quite as substantial as originally hoped because of the presence of phonon-assisted Auger processes which are not so susceptible to band structure engineering techniques. Strained layer lasers are now commercially available at a variety of MIR wavelengths, where the dominant nonradiative loss is via the direct interband Auger scattering routes.

From the point of view of the present article the main contribution of 'designed' strain splittings and quantum confinement is in the reduction of the Auger coefficient itself, by removing states that easily satisfy the momentum and energy conservation conditions required for the process to take place. However, in addition to this there can be a substantial reduction in the threshold carrier injection level required for population inversion in a laser. In real III–V semiconductors the heavy hole valence band mass, m_h, is so much greater than the electron mass, m_e, that the usual laser picture of degenerate electron and hole distributions does not apply. At normal carrier injection levels the quasi-Fermi level of the holes is above the top of the valence band resulting in a classical heavy hole distribution. Thus, the lower laser levels are almost completely filled with electrons, by contrast with the ideal situation of two mirror bands. This leads to an injection level for the laser threshold of greater than 2:1 required for the actual case compared to the ideal case. Since the Auger recombination rate per unit volume is approximately proportional to the cube of n, this factor of ~ 2 reduction in injection level can produce a factor of almost an order of magnitude reduction in this loss mechanism. Large biaxial strains, either compressive or tensile, can lead to a considerable reduction in the hole mass and hence in the density of states at the top of the valence band, so that the laser characteristics may then approach those of an ideal semiconductor, with $m_e = m_h$.

A further important loss mechanism is free hole absorption of the heavy holes resulting from intervalence band transitions. This can be effectively eliminated, and other improvements made to laser performance, by the introduction of a strained layer structure which raises the degeneracy of the light and heavy hole at $k = 0$ and reduces the mass of the heavy hole. One example of this comes just from the symmetry of the problem, where clearly the cubic symmetry of the p-like valence band is not matched to the uniaxial symmetry of the laser beam. Application of biaxial or uniaxial strain removes the cubic symmetry, changing the relative energies of the p_x, p_y, and p_z valence states, and making it possible for almost all of the injected holes to be in the states of the correct symmetry to take part in the lasing action. The one parasitic phenomenon in semiconductor lasers which is hardly affected by band structure engineering is spontaneous emission, which will always make some contribution to the current density required at threshold.

The band structure of a bulk unstrained direct gap tetrahedral semiconductor is shown again for comparison in Figure 2. The effect of biaxial tension and compression is shown respectively in Figure 4a,b. In each case the lowest conduction band is approximately parabolic near the zone center, but becomes anisotropic with the electron dispersion at small k. The axial strain breaks the cubic symmetry of the semiconductor, introducing a tetragonal distortion which splits the degeneracy of the light and heavy hole states at the valence maximum, Γ, typically by about 60–80 meV for a 1% lattice mismatch. The resulting valence band structure is highly anisotropic (Figure 4a,b), with the band which is heavy along the strain axis, wavevector $k_\perp$, being comparatively light in the plane, along $k_\|$, and vice versa. The in-plane mass, $m_\|$, determines the density of states, and thus, under compression (Figure 4b), can be reduced according to the principles described above to improve conditions towards those for ideal laser operation: viz, (1) that there is only one band at the valence band maximum; (2) that it has an effective mass as close to that of the electron as possible; and (3) that above the Bernard–Duraffourg transparency condition, the polarization of the gain is anisotropic, with spontaneous emission and gain being suppressed along all directions except along the axis contributing to the laser beam.



(a) (b)

Figure 4 Schematic representation of the band structure of a direct gap tetrahedral semiconductor: (a) under biaxial tension the hydrostatic component of the tension reduces the mean bandgap, while the axial component splits the degeneracy of the valence band maximum and introduces an anisotropic valence band structure (the highest band being light along the strain axis, k_z and comparatively heavy perpendicular to that axis, $k_\perp$); (b) under biaxial compression the mean bandgap increases and the valence splitting is reversed.

Since the Auger recombination involves three carriers, the Auger current J_{NR} in a device with an undoped active region varies approximately as $J_{\mathrm{NR}}(T) \propto C(T)n_{\mathrm{th}}^3$, where $C(T)$ is the temperature-dependent Auger coefficient per unit volume and nth is the threshold carrier density. The influence of strain on Auger recombination has two aspects, as discussed above. First, J_{NR} is very sensitive to any reduction in n_{th} brought about by strain either through a decrease in h (heavy hole) mass or an increase in the optical transition strength. Secondly, strain may change the magnitude of $C(T)$ for the interband Auger processes described earlier (Figure 3). A simple calculation of Auger recombination in a quantum well heterostructure, assuming parabolic bands and Boltzmann statistics, shows that the coefficient increases exponentially with temperature as $C(T) = C_o\exp(-E_a/kT)$, where the activation energy, E_a, is approximately dependent on $(m_h)^{-1}$. Thus, both of these should be reduced by several orders of magnitude due to a reduction in the heavy hole mass, m_h, resulting from the strain effects discussed above.

Phonon Scattering: QWIPs and QC Lasers

Sub-band transitions are useful for MIR detectors and emitters because they make it possible to cover a broad range of MIR wavelengths using the same combination of large gap, InP-based and GaAs-based state of the art semiconductor alloys that are used for high-speed electronics and optical communications. They are the most advanced of the low-dimensional solids from the point of view of demonstrated detector performance. This superior control of materials results in high uniformity and has thus allowed the demonstration of large 128 × 128 arrays with excellent imaging performance. Detectivities $D^* > 10^{10}\ \mathrm{cm\,Hz^{1/2}\,W^{-1}}$, low noise equivalent temperature differences, and excellent infrared video imaging can be achieved at 10 μm for temperatures $T = 10-80$ K.

Although the QWIP (quantum well infrared photodetectors) detectors showed promise for many years as alternatives to HgCdTe systems, the first intersub-band laser was not realized until the demonstration of the quantum cascade (QC) laser. Intersub-band (QC) lasers differ fundamentally from bipolar diode lasers in that they rely on only one type of carrier and on electronic transitions between conduction sub-band states arising from size quantization in semiconductor quantum heterostructures. These in-plane sub-bands have the same curvature (by contrast with the interband devices which have conduction and valence bands of opposite curvature), so that the joint density of states and corresponding gain spectrum (collision limited) is much narrower and approximately symmetric. Thus, the arguments which show that the Kane-type band structure is particularly disadvantageous for the overall Auger loss mechanism in interband diode lasers do not apply; the problems resulting from having $m_e \ll m_h$ are removed and the inversion is much less sensitive to thermal broadening of the electron distribution. In addition, there is no free hole absorption, and, since the component semiconductor materials are of comparatively wide bandgap, there is negligible intrinsic carrier concentration. However, the threshold current density tends to be rather large owing to the rapid nonradiative phonon relaxation of the population inversion.

In the original QC laser structure the electrons streamed down a potential staircase, sequentially emitting photons at the steps, consisting of coupled quantum wells in which the population inversion between discrete conduction band excited states was achieved by control of tunneling. The laser structure was grown with the $Al_{0.48}In_{0.52}As/Ga_{0.47}In_{0.53}As$ heterojunction material system lattice matched to InP. Electrical pumping was achieved by alternating 25 undoped coupled-well active regions with compositionally graded layers. The coupled-well region was essentially a four-level laser system, where a population inversion was achieved between the two excited states, $n = 3$ and $n = 2$. While the nonradiative phonon emission lifetime is short ($\tau_{32} \sim 4.3$ ps at the electric fields used in the tunneling process), strong coupling to an adjacent GaInAs well gives an even shorter lower state lifetime ($\tau_{21} \sim 0.6$ ps) from optical phonons with nearly zero momentum transfer between the strongly overlapped and closely spaced $n = 2$ and $n = 1$ states. This enables the achievement of a population inversion between these states. (Note that the separation between the $n = 2$ and $n = 1$ states, E_{21}, is designed to be approximately equal to the optical phonon energy.)

The radiative efficiency of these QC devices is unavoidably low ($<10^{-3}$) because most of the electrons in the upper sub-band relax within ~1 ps through nonradiative optical phonon emission before radiative transitions with a lifetime in the nanosecond range have a chance to occur. An alternative configuration has been proposed, the type II interband cascade laser (T2ICL), which retains the advantages of cascaded tunneling injection and wavelength tuneability but eliminates the nonradiative phonon path between valence and conduction bands of opposite curvature. In addition, band structure engineering ideas discussed above are incorporated to suppress the unwanted Auger processes; the design results in a light in-plane hole mass and the removal of resonances between the energy gap and intervalence transitions.

See also

Semiconductor Materials: Group IV Semiconductors, Si/SiGe; Type-II Quantum Wells and Superlattices. **Semiconductor Physics:** Band Structure and Optical Properties; Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures; Recombination Processes.

Further Reading

Faist J, Capasso F, Sirtori C, Sivco DL, Hutchinson AL and Cho AL (1994) Quantum cascade laser. *Science* 264: 553–556.

O'Reilly EP and Adams A (1994) Band structure engineering in strained semiconductor lasers. *IEEE Journal of Quantum Electronics* 30: 366–379.

Pidgeon CR, Ciesla CM and Murdin B (1997) Suppression of non-radiative processes in semiconductor mid-infrared emitters and detectors. *Progress in Quantum Electronics* 21: 361–419.

Yablonovitch E and Kane EO (1988) Band structure engineering of semiconductor lasers for optical communications. *Journal of Lightwave Technology* 6: 1292–1299.

Youngdale ER, Meyer JR, Hoffman CA, Bartoli FJ, Grein CH, Young PM, Ehrenreich H, Miles RH and Chow DH (1994) Auger lifetime enhancement in InAs-GaInSb superlattices. *Applied Physics Letter* 64: 3160–3162.

Dilute Magnetic Semiconductors

R R Gałązka, Polish Academy of Sciences, Warsaw, Poland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction, General Remarks

Semimagnetic semiconductors (SMSs) are a group of solids at the interface between semiconductors and magnetic materials. Semimagnetic semiconductors, also referred to as dilute magnetic semiconductors, are semiconductor-based solid solutions where some of the cations are replaced by transition metals or rare earth elements. The crystallographic structure of the semiconductor is conserved; the lattice constant is a function of composition. From a magnetic point of view SMSs are disordered magnetic materials, since magnetic atoms are randomly distributed in the cation sublattice of the semiconductor compound. Table 1 presents the most complete list of bulk ternary SMSs. Quaternary SMSs are also investigated (e.g., PbSnMnTe or CdMnSeTe).

Generally speaking, in SMSs there coexist two interrelated and interacting subsystems: mobile delocalized charge carriers and localized magnetic moments connected with paramagnetic ions. Electronic (mainly optical) properties of SMSs have been the subject of intensive studies since early in 1970. Due to the strong spin exchange interaction between mobile carriers and localized magnetic moments (the exchange constant of the sp-d interaction is of the order of 1 eV for II–VI SMSs) significant changes of the band structure and behavior of the carriers were observed. A number of new physical phenomena were discovered, such as giant Faraday rotation (now important in magnetic field sensors and other applications in, for example, the automobile industry based on this strong magneto-optical effect), the magnetic field induced metal–insulator transition, the bound magnetic polaron and quantum thermomagnetic oscillations. Investigations of the influence of the electron subsystem on the magnetic properties of SMSs are connected with the observation of a ferromagnetic phase in PbSnMnTe induced by carrier concentration.

Molecular beam epitaxy (MBE) grown GaAs with Mn opened a new chapter of III–V SMSs showing ferromagnetic behavior with the highest transition temperature $T_c = 110\,\mathrm{K}$. In 1987 the first paper devoted to layered structure and magnetic properties of low-dimensional (LD) SMSs was published starting intensive studies of superlattices and other LD structures made of SMSs.

Energy Band Structure, Optical and Magneto-optical Properties of SMSs

Replacing cations such as Cd or Hg with a paramagnetic ion such as Mn in the same crystallographic structure does not markedly disturb the semiconductor properties of the material. The energy gap changes (increases) but the conduction and valence bands conserve their symmetry and character as in nonmagnetic semiconductor mixed crystals. The spin momentum of paramagnetic ions is connected with the 3d or 4f shell, for transition metals or rare earth elements, respectively. The energy level of 3d or 4f electrons lies below the top of the valence band and thus has negligible influence on its shape or that of the bottom of the conduction band. Thus all basic semiconductor optical properties connected with the band symmetry and topology are the same as for a typical semiconductor. These are described, for example, in articles on the lead salts (MS641) involving direct optical transitions at the L-point of the Brillouin zone, and on mercury cadmium telluride (MS639) with direct optical transitions at the Γ-point. The only influence of the magnetic subsystems on electrons comes from the spin exchange interaction between mobile carriers and localized magnetic ions. This interaction can be represented by a Heisenberg term

$$H_{\mathrm{ex}} = \bar{\sigma} \sum_i \bar{S}_i J(\mathbf{r} - \mathbf{R}_i) \qquad [1]$$

where $\bar{\sigma}$ and $\bar{S}$ are spin operators of the band electron and magnetic ion, respectively, the summation is over all lattice sites occupied by the magnetic ions, and J is the exchange constant.

Assuming mean field and virtual crystal approximations this term can be rewritten in the form which is periodic with a lattice constant:

$$H_{\mathrm{ex}} = x \langle \bar{S} \rangle_{\mathrm{av}} \bar{\sigma} \sum_R J(\mathbf{r} - \mathbf{R}) \qquad [2]$$

where x is the molar fraction of magnetic ions, $\langle \bar{S} \rangle_{\mathrm{av}}$ is the average over all magnetic ions and is directly related to the magnetization of the sample:

$$M = N_0 g \mu \langle \bar{S} \rangle_{\mathrm{av}} \qquad [3]$$

N_0 is the number of unit cells per unit volume, g is the Lande factor for magnetic ions, and μ is the Bohr magneton.

The Heisenberg term must be added to the effective-mass Hamiltonian to solve the energy eigenvalue problem for SMSs. Realizing this was the turning point in understanding their properties and provided a basis for this group of alloys to be distinguished from other semiconductor mixed crystals. Since that time SMSs have become the subject of intensive studies in Europe and elsewhere.

The exchange interaction depends on the ion spin and the exchange constant. The spin of Mn is the highest for transition metals and equals five Bohr magnetons, and whilst a typical value for the exchange coupling between magnetic ions $J_{\mathrm{d-d}}$ is 10^{-3} eV, the exchange constant for electrons and holes with magnetic ions $J_{\mathrm{sp-d}}$ is about 1 eV in SMSs.

The exchange interaction is also strongly temperature and magnetic field dependent. As the macroscopic magnetization of a sample is proportional to the thermodynamic average value of the magnetic ion spin, to a good approximation we can replace the ion spin operators in the Hamiltonian by their average value, calculated or taken from measurements of the magnetization. From typical magnetic functions we can thus obtain information on the electron behavior.

In semiconductors, an external magnetic field acts on both the orbital motion and the spin of electrons producing Landau quantization and spin splitting, to an extent dependent on the effective mass of the carriers. The exchange interaction acts on their spin only and is, in effect, mass independent. Because of this, and also the large value of $J_{\mathrm{sp-d}}$, the band structure in turn changes drastically under the influence of an external magnetic field and depends strongly on temperature. From Figure 1 we can see that the very typical structure of the degeneracy of the light and heavy hole valence bands disappears in SMS when a magnetic field is applied. The change is accompanied by a drastic increase of hole mobility like that observed in low-dimensional structures. In SMS such as $Hg_{1-x}Mn_xTe$ or $Hg_{1-x}Mn_xSe$ (for $x \le 0.07$) (Figure 2), the magnetic field produces an overlap of the valence and conduction bands, an effect never observed in nonmagnetic semiconductors.

Impurity levels are also influenced by exchange interactions: the ionization energy of an acceptor

Table 1 Composition and crystal structure of ternary bulk SMSs

Material	*Crystal structure*	*Composition range*
II–VI (Mn)		
$Zn_{1-x}Mn_xS$	ZB	$0 < x \le 0.10$
	W	$0.10 < x \le 0.45$
$Zn_{1-x}Mn_xSe$	ZB	$0 < x \le 0.30$
	W	$0.30 < x \le 0.57$
$Zn_{1-x}Mn_xTe$	ZB	$0 < x \le 0.86$
$Cd_{1-x}Mn_xS$	W	$0 < x \le 0.45$
$Cd_{1-x}Mn_xSe$	W	$0 < x \le 0.50$
$Cd_{1-x}Mn_xTe$	ZB	$0 < x \le 0.77$
$Hg_{1-x}Mn_xS$	ZB	$0 < x \le 0.37$
$Hg_{1-x}Mn_xSe$	ZB	$0 < x \le 0.38$
$Hg_{1-x}Mn_xTe$	ZB	$0 < x \le 0.35$
II–V (Mn)		
$(Cd_{1-x}Mn_x)_3As_2$	tetr.	$0 < x \le 0.18$
$(Zn_{1-x}Mn_x)_3As_2$	tetr.	$0 < x \le 0.15$
IV–VI (Mn, Eu, Gd)		
$Pb_{1-x}Mn_xS$	RS	$0 < x \le 0.05$
$Pb_{1-x}Mn_xSe$	RS	$0 < x \le 0.17$
$Pb_{1-x}Mn_xTe$	RS	$0 < x \le 0.12$
$Sn_{1-x}Mn_xTe$	RS	$0 < x \le 0.40$
$Ge_{1-x}Mn_xTe$	RH	$0 < x \le 0.18$
	RS	$0.18 < x \le 0.50$
$Pb_{1-x}Eu_xSe$	RS	$0 < x \le 0.04$*
$Pb_{1-x}Eu_xTe$	RS	$0 < x \le 0.32$*
$Sn_{1-x}Eu_xTe$	RS	$0 < x \le 0.013$
$Pb_{1-x}Gd_xTe$	RS	$0 < x \le 0.11$*
$Sn_{1-x}Gd_xTe$	RS	$0 < x \le 0.09$*
II–VI (Fe, Co, Cr)		
$Zn_{1-x}Fe_xS$	ZB	$0 < x \le 0.26$*
$Zn_{1-x}Fe_xSe$	ZB	$0 < x \le 0.22$*
$Zn_{1-x}Fe_xTe$	ZB	$0 < x \le 0.01$*
$Cd_{1-x}Fe_xS$	W	$0 < x < 0.09$*
$Cd_{1-x}Fe_xSe$	ZB	$0 < x < 0.20$
$Cd_{1-x}Fe_xTe$	ZB	$0 < x \le 0.06$*
$Hg_{1-x}Fe_xS$	ZB	$0 < x \le 0.037$*
$Hg_{1-x}Fe_xSe$	ZB	$0 < x \le 0.20$*
$Hg_{1-x}Fe_xTe$	ZB	$0 < x \le 0.02$*
$Zn_{1-x}Co_xS$	ZB	$0 < x \le 0.15$*
$Zn_{1-x}Co_xSe$	ZB	$0 < x \le 0.10$*
$Zn_{1-x}Co_xTe$	ZB	$0 < x < 0.06$*
$Cd_{1-x}Co_xS$	W	$0 < x \le 0.064$*
$Cd_{1-x}Co_xSe$	W	$0 < x \le 0.082$*
$Cd_{1-x}Co_xTe$	ZB	$0 < x \le 0.04$
$Hg_{1-x}Co_xS$	ZB	$0 < x \le 0.02$
$Hg_{1-x}Co_xSe$	ZB	$0 < x \le 0.047$*
$Zn_{1-x}Cr_xSe$	ZB	$0 < x \le 0.005$*
$Zn_{1-x}Cr_xTe$	ZB	$0 < x \le 0.003$*
$Cd_{1-x}Cr_xS$	W	$0 < x \le 0.002$*

ZB – zinc blende, W – wurtzite, RS – rock salt, RH – rombohedral. Asterisks denote SMSs with the highest reported x value; tetr, tetragonal structure.

Reprinted in part from Gałązka RR (1995) Influence of electron subsystem on magnetic properties of semimagnetic semiconductors. In: Tróc R, Morkowski J and Szymczak M (eds) Proceedings of the International Conference of Magnetism, Warsaw 1994. *Journal of Magnetism and Magnetic Materials*, 113–116. Copyright Elsevier Science.



Figure 1 Conduction and valence band quantization in an external magnetic field for $Cd_{0.95}Mn_{0.05}Te$ and CdTe. Spin splitting, which is very weak in CdTe, is the main effect in CdMnTe. Notice the almost equal splitting of the heavy- and light-hole bands in CdMnTe. The influence of exchange interaction is visible even at 100 K. The picture of CdTe over this range of temperature is practically unchanged. Reproduced from Gałązka RR (1987) Semimagnetic semiconductors. *Europhysics News* 18(6): 90–92.



Figure 2 Energy band structure of $Hg_{1-x}Mn_xTe$, $x = 0.02$, calculated at 14 K (a) and 30 K (b) in a magnetic field of 4 T. After Gałązka RR (1978) Semimagnetic semiconductors based on HgMnTe and CdMnTe. Reproduced from Wilson BLM (ed) ICPS 14th, Edinburgh Institute of Physics, Conference series no. 43, 1978, p.133–140.

decreases and its wavefunction becomes anisotropic under the influence of a magnetic field. Both effects produce a giant negative magnetoresistance and a field-induced insulator–metal transition. Indeed all (particularly optical) properties susceptible to being changed by a magnetic field are very different in SMSs from those of standard semiconductors: the Faraday effect., Shubnikov–de Haas oscillations, interband magnetoabsorption, luminescence and spin flip Raman scattering (see below) become strongly dependent on temperature and magnetic field.

In the absence of a magnetic field, the average value of the ion spins is zero, the magnetization is zero too, and SMSs should behave as typical non-magnetic semiconductors. Whereas this is true for delocalized band electrons, when an electron is localized around an impurity, a bound magnetic polaron can be observed. This concept was first introduced to explain the behavior of magnetic semiconductors (Eu chalcogenides) and then later was applied also to SMSs. A localized electron can produce a spontaneous magnetization within the range of its wavefunction via the exchange interaction. Local ferromagnetic ordering in this range produces a Stokes shift in spin-flip Raman scattering even in the absence of an external magnetic field and other related phenomena. Local fluctuations of magnetization and a detailed knowledge of electronic states are essential for a theoretical description of this effect. The bound magnetic polaron is a subtle example of the feedback between electronic and magnetic subsystems present in SMS.

Magnetic Properties

Magnetic properties of SMS connected with the exchange interaction between paramagnetic ions are similar to those of other dilute magnetic materials. The broad range of possible magnetic ion concentrations (up to $x = 0.80$ in $Zn_{1-x}Mn_xTe$ and $x = 0.70$ for $Cd_{1-x}Mn_xTe$) allows us to observe the evolution of magnetic interactions in the same crystallographic structure as a function of magnetic ion concentration. A continuous transition from diamagnetic behavior (for $x \leq 0.005$) of the host semiconductor, to paramagnetism, spin-glass (for $x \geq 0.02$) and finally antiferromagnetic order has been observed. Type III antiferromagnetic ordering is observed for $x > 0.6$ indicating that the magnetic elementary cell contains two elementary cells of the cation sublattice. From a crystallographic point of view the magnetic subsystem is disordered; the distribution of magnetic atoms on the cation sublattice is random.

A spin-glass-like state is observed in SMSs in the broadest range of paramagnetic ion concentrations ($0.02 \leq x \leq 0.60$) below and above the percolation threshold (Figure 3). Indeed the temperature dependence of the magnetic susceptibility below and above the transition temperature and their dynamic properties at low and high magnetic fields suggest rather the existence of two spin-glass phases arising from the competition between spin-glass and clustering behavior. Below the percolation threshold ($x \leq 0.17$ for fcc lattice) the mechanism responsible for a spin-glass phase is even less clear, although, for such a dilute system it must be long-range to produce freezing of the spins.



Figure 3 Magnetic phase diagram for the listed SMSs. P indicates the paramagnetic region, SG indicates the spin-glass region. Reprinted in part from Gałązka RR (1995) Influence of electron subsystem on magnetic properties of semimagnetic semiconductors. Reproduced with permission from Tróc R, Morkowski J and Szymczak M (eds) Proceedings of the International Conference of Magnetism, Warsaw 1994. *Journal of Magnetism and Magnetic Materials*, 113–116. Copyright Elsevier Science.

The antiferromagnetic order has been inferred from specific heat and magnetic susceptibility measurements, and additional information concerning this phase has come from neutron diffraction studies: only a certain fraction of the total number of magnetic ions (e.g., about 50% for CdMnTe, $x = 0.65$) is well ordered; the rest remain in a disordered spin-glass phase. Thus a mixed phase (antiferromagnetic and spin-glass coexisting together) rather than a truly antiferromagnetic phase is observed.

The influence of carrier concentration on magnetic properties has been extensively investigated in metallic alloys. Several IV–VI semiconductors like SnTe can exhibit quite high metallic-like carrier concentrations. In the quarternary alloy PbSnMnTe, the concentration of holes can be varied by annealing in the range 10^{20} to 5×10^{21} cm^{-3}. In $Pb_{0.25}Sn_{0.72}Mn_{0.03}Te$ an abrupt transition from the paramagnetic to ferromagnetic phase has been found for $p > 3 \times 10^{20}$ cm^{-3}. The Curie temperature is a function of hole concentration, but the Mn ions conserve their magnetic moment of five Bohr magnetons. The magnetic phase diagram for this first ferromagnetic SMS (Figure 4) is thus three dimensional (T,x,n) in contrast to the



Figure 4 Magnetic phase diagram for PbSnMnTe (•) and SnMnTe (▪). The ferromagnetic phase is observed in the region above the critical carrier concentration p_c and the straight line defined by the equation x/p = const. Away from this region a spin-glass state is observed. Calculated phase boundaries between the ferromagnetic and spin-glass state are also shown for two theoretical models: SK: Sherrington–Kirkpatrick model and RMF: random mean field model. Canonical metallic spin-glasses are also shown. Reproduced from de Jonge WJM, Story T, Swagten HJM and Eggerkamp PJT (1992) Carrier-induced breakdown of ferromagnetism. *Europhysics Letters* 17: 631–636.

two-dimensional diagram (T,x) usually presented for magnetic alloys. Even a low concentration of spin polarized carriers when optically pumped can change the magnetization of HgMnTe owing to the strong exchange interaction of carriers with magnetic ions.

Low-Dimensional (LD) SMSs: Magneto-optical and Spintronic Effects

Modern technology such as MBE makes it possible to obtain quasi-3D SMSs in the whole range of x from 0 to 1. It also gives broad possibilities to create different combinations of semiconductor, SMS, and magnetic materials. In addition the dimensionality of LD structures influences the properties of both electronic and magnetic subsystems. Further there is almost always some strain in the system which also influences the properties of superlattices and other LD structures. Studies of LD SMSs not only extend the material base but open a new area of dimension-dependent phenomena and interactions in SMS systems.

Among many effects observed in LD SMS structures we will mention only a few phenomena, where exchange interaction is essential and which cannot be observed in nonmagnetic LD semiconductors. In all cases the giant (magneto-optical) Zeeman splitting caused by the exchange interaction plays a key role.

In superlattices made of ZnSe/ZnMnSe with a small amount of Mn, the band offset of conduction and valence bands is negligible at zero external magnetic field. In the presence of an external field the conduction and valence bands of ZnMnSe split creating a spin-superlattice because the spin-split states allow only one spin configuration. The possibility of the existence of such a spin superlattice was earlier suggested for SMSs and later experimentally observed.

If the superlattice, quantum well or heterostructure is made of SMS and non-SMS material (e.g. ZnTe/CdMnSe or CdTe/CdMnTe) one can exploit the drastic differences in the Zeeman splitting occurring in different layers to pinpoint the localization in space of specific electronic states. If one (hole or electron) or both states involved in optical transitions originate from the SMS layer, this state will show a very strong Zeeman splitting in the external magnetic field. Thus the SMS component can be used as a ‘marker’ in order to bring out the general properties of the wavefunction distribution.

Excitonic Zeeman splitting in non-magnetic quantum wells with SMS barriers can be applied to studies of the shape of interface profile and the influence of the growth conditions on the shape of the interface. If the interface is not completely flat, even a small fraction of magnetic atoms in the well close to the interface can significantly enhance the Zeeman exciton splitting in the quantum well. The sensitivity of this method allows one to detect the sharpness of an interface with one monolayer accuracy.

The MBE technique opens up possibilities of creating hybrid structures with SMSs, useful for spintronic devices such as spin filters, spin transistors and tunneling magnetoresistance sensors. Very importantly, it has been realized that SMSs are highly suitable to form the ferromagnetic spin injecting electrodes in such systems where simple metallic electrodes fail because of the large electrical resistance mismatch between the electrode and the semiconductor in which the spin is being processed. A further possibility is to fabricate hybrid metallic ferromagnetic–SMS structures. In such a case one can make use of the magnetic field exerted by the metallic ferromagnet positioned very close (on an atomic scale) to the SMS layer or quantum structure, thus affecting the spin splitting in the latter. One could use such a fringe field to shape the band edges in such a fashion that an additional localization of the carriers in a two-dimensional quantum well is induced leading to formation of quantum wires or dots. In other applications a spin-coherence storage effect has been obtained for core electron polarization in Mn-doped ZnSe quantum wells. The optically pumped conduction electron spin polarization generates a nonequilibrium spin polarization of the paramagnetic core electron spins(3d in the case of Mn) through the core–conduction-electron coupling. This core electron spin polarization persists long after the conduction electron spin polarization has decayed away and presents an interesting avenue towards information storage.

The physics of SMSs is currently a well-established part of solid state physics. In the investigations of bulk crystals and LD structures many problems are solved and new problems are waiting further research. Particularly important seems to be investigation of layers and LD structures because of the broad technological possibilities and because of the new important factor (i.e., dimensionality) whereby spin-dependent phenomena can be intentionally regulated.

List of Units and Nomenclature

g	Lande factor for paramagnetic ion
H_{ex}	Heisenberg spin exchange Hamiltonian
$J_{\mathrm{d-d}}$	exchange constant for coupling between paramagnetic ions (transition metals)
$J(\bar{r}-\bar{R})$	exchange constant
$J_{\mathrm{sp-d}}$	exchange constant for electron or hole coupling with paramagnetic ions
LD	low dimensional
M	magnetization
MBE	molecular beam epitaxy
N_0	number of unit cells per unit volume
SMS	semimagnetic (diluted magnetic) semiconductor
$\langle\bar{S}\rangle_{\mathrm{av}}$	average value of spin operator
T_{c}	Curie temperature
V_{h}	hybridization energy
x	molar fraction of paramagnetic ions
$\boldsymbol{\mu}$	Bohr magneton
$\bar{\boldsymbol{\sigma}}, \bar{S}$	spin operators

See also

Magneto-Optics: Interband Magnetoabsorption, Cyclotron Resonance, Spin Flip Raman Scattering. **Semiconductor Materials:** Lead Salts; Mercury Cadmium Telluride. **Semiconductor Physics:** Spin Transport and Relaxation in Semiconductors; Spintronics.

Further Reading

Bauer G, Pascher H and Zawadzki W (1992) Magneto-optical properties of semimagnetic lead chalcogenides. *Semiconductor Science and Technology* 7: 703–723.

Dietl T (1994) Magnetic semiconductors. Moss TS (ed.) *Handbook of Semiconductors*, vol. 3b, pp. 1251–1342. Amsterdam, The Netherland: North-Holland.

Dietl T (2002) Ferromagnetic semiconductors. *Semiconductor Science and Technology* 17: 377–392. (Special issue: Semiconductor Spintronics, guest ed Hideo Ohno).

Dobrowolski W, Kossut J and Story T (2003) Magnetic semiconductors–new bulk materials and low-dimensional quantum structures. In: Buschow KHJ (ed.) *Handbook of Magnetic Materials, II–VI and IV–VI.* vol. 15, pp. 289–378. Amsterdam: Elsevier North-Holland.

Furdyna JK (1991) In: Averous M and Balkanski M (eds) *Semimagnetic Semiconductors and Diluted Magnetic Semiconductors*. New York: Plenum.

Furdyna JK and Kossut J (eds) (1988) Semiconductors and Semimetals. *Diluted Magnetic Semiconductors*, vol. 25, 470 pp. San Diego, CA: Academic Press.

Gałązka RR and Kossut J (1980) Narrow-gap semimagnetic semiconductors. In: Zawadzki W (ed.) *Lecture Notes in Physics*, vol. 133, pp. 245–265. Berlin: Springer Verlag.

Gałązka RR and Kossut J (1982) Semimagnetic semiconductors. In: Madelung O, Schulz M and Weiss H (eds) *Landolt-Börnstein New Series*, vol. III/17b, pp. 302–318. Berlin: Springer Verlag.

Gałązka RR, Kossut J and Story T (1999) Semimagnetic semiconductors. In: Rössler U (ed.) *Landolt-Börnstein New Series*, vol. III/41B, pp. 650–721. Berlin: Springer Verlag (Update to chapter 5, Vol. III/17b).

Kossut J and Dobrowolski W (1993) Diluted magnetic semiconductors. In: Buschow KHJ (ed.) *Handbook of Magnetic Materials*, vol. 7, pp. 231–305. Amsterdam, The Netherlands: North Holland.

Kossut J and Dobrowolski W (1997) Properties of diluted magnetic semiconductors. In: Capper P (ed.) *Narrow-Gap II–VI Compounds for Optoelectronics and Electromagnetic Applications*, pp. 401–429. London: Chapman and Hall.

Kossut J (2001) Low dimensional structure of diluted magnetic (semimagnetic) semiconductors – a subjective review. *Acta Physica Polonica, A* 100 (supplement): 111–138.

Ohno H, Matsukura F and Ohno Y (2002) Semiconductor spin electronics. *Japan Society of Applied Physics (JSAP International)* 5: 4–13.

Story T (2003) Optoelectronic properties. In: Monasreh MO (series ed.) *Optoelectronic Properties of Semiconductors and Superlattices* vol. 18, Khokholov D. (volume ed.) *Lead Chalcogenides: Physics and Applications, Semimagnetic Semiconductors Based on Lead Chalcogenides*, pp. 385–425. New York, London: Taylor and Francis Books Inc.

GaAs Based Compounds

J J Finley and J P R David, University of Sheffield, Sheffield, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Background

Gallium Arsenide (GaAs) is an important semiconductor that has come to dominate the field of optoelectronics by virtue of its favorable electro-optical properties and the ease by which it can be controllably modified by extrinsic means; combining it with its large family of related alloys ($Al_xGa_{1-x}As$, $In_xGa_{1-x}As$, $GaAs_xP_{(1-x)}$, $(In_xGa_{(1-x)})_yAsN_{1-y}$) and via the growth of hetero-structures with reduced dimensionality (Quantum Wells-2D, Wires-1D, and Dots-0D). In such low dimensional semiconductor nanostructures, quantum mechanical effects are directly exploited to customize and dramatically enhance electro-optical properties. Such investigations of the fundamental electro-optical properties of GaAs-based compounds has resulted in the emergence of several new device concepts such as the Quantum Cascade laser, led to the discovery of new physical phenomena like the fractional Quantum Hall effect, and may pave the way for an entirely new class of opto-electronic devices with true quantum functionality.

In the following, we explore the fundamental physical and electro-optical properties of GaAs and its related alloys and illustrate the considerable impact this remarkable family of materials has had on modern semiconductor devices.

Fundamental Physical Properties

The crystal structure of GaAs (Figure 1 – inset) consists of two interpenetrating face centred cubic lattices that accommodate the group III and V atoms respectively. The sub-lattices of Ga and As are shifted from each other by $a/4$ along the [111] body diagonal, where a is the lattice constant, forming the well-known zincblende crystal structure. For stochiometric GaAs, the lattice constant is $a = 0.56536(1)$ nm at room temperature which translates to a Ga–As nearest neighbor separation (bond length) of 0.2308 nm.

Figure 1 summarizes the variation of the lattice constant for a number of GaAs related III–V semiconductor alloys, plotted as a function of their fundamental electronic bandgap. Particularly relevant is AlAs, which also crystallizes in the zincblende form and has a lattice constant (a(AlAs) $= 0.5660(2)$ nm) almost identical to that of GaAs ($\Delta a < 1\%$). The sole fact that the $Al_xGa_{(1-x)}As$ alloy can be almost perfectly lattice matched to GaAs over its entire compositional range, whilst exhibiting near continuously variable electronic and optical properties, is the principal reason for the key role GaAs-related materials play in semiconductor opto-electronic devices. We continue by investigating the electronic and optical properties of the $Al_xGa_{(1-x)}As$ family of materials and discover why they are particularly suited to opto-electronic device applications.

Summary of Electronic Properties of GaAs and $Al_xGa_{1-x}As$

The optical properties of semiconductors are determined principally by inter-band radiative transitions involving electronic states in the vicinity of the conduction (CB) and valence band (VB) extrema. Consequently, in the following we focus on electronic properties of GaAs close to these points and substantiate our discussion using experimental data obtained from optical spectroscopy.

GaAs Bandstructure

GaAs is a direct-gap semiconductor ($E_g = 1.42$ eV at 300 K), both the conduction band minimum and



Figure 1 Fundamental bandgap of selected compounds within the III–V semiconductor family plotted as a function of the cubic lattice constant – a. The inset depicts the zincblende crystal structure within the GaAs unit cell. Data obtained from various sources, see for example Brozel MR and Stillman GE (eds) (1996) *Properties of Gallium Arsenide*, INSPEC, emis Datareviews Series No.16 and Loffe Institute, on NSM semiconductor data repository at http://www.ioffe.rssi.ru

valence band maximum occurring at the center of the Brillouin zone (Γ-point). Figure 2 summarizes our discussion of the electronic structure of GaAs, depicting the bandstructure schematically within the first Brillouin zone. The valence electron configurations of Ga and As atoms result in the band edge CB states being two-fold degenerate due to the electron spin and characterized by an almost isotropic effective mass of $m_{\Gamma}^{*} = 0.068\, m_{\mathrm{o}}$. For GaAs heterostructures with reduced dimensionality, the very weak anisotropy of the conduction band states can generally be ignored when calculating the lowest energy confined electron states but has a significant impact on higher quantized levels and must, therefore, be included. In addition to the fundamental CB minimum at the zone center or Γ-point of the Brillouin zone, satellite minima occur at the six equivalent X-points ($k = (1/a, 0, 0)$) and eight equivalent L-points ($k = (1/a, 1/a, 1/a)$). The X-point and L-point minima lie $\Delta E_{\Gamma X} = 0.49$ eV and $\Delta E_{\Gamma L} = 0.32$ eV above the Γ-minimum at low temperatures ($T = 4.2$ K) and are characterized by strongly direction dependent effective masses parallel (||) or perpendicular (⊥) to the principal axes. Electronic states in the vicinity of these minima are termed the X and L-valleys respectively and have a significant impact on high-energy electron transport in devices such as HEMTs and in avalanche carrier multiplication processes, but do not generally play a significant role in the optical properties of the binary – GaAs. However, satellite CB minima can strongly influence the optical properties of GaAs–AlAs superlattices and QWs that can exhibit a type-II band alignment for GaAs layer thicknesses < 6 nm. In this case, the electrons (holes) are localized in the AlAs (GaAs) layer and the nature of the AlAs X-states dominates the optical properties.



Figure 2 Schematic representation of the bandstructure of GaAs showing just a single conduction band over whole Brillouin zone in Γ-L and Γ-X directions only and neglecting the split off band that does not significantly influence electrical or optical properties.

Table 1 Low temperature GaAs effective masses for electrons (upper panel) and holes (lower panel). Values marked with * are inferred from measurements on GaAs based heterostructures and values marked ** are calculated

	Crystallographic axis	*Effective Mass (m_o)*
CB-Γ minimum	*Isotropic*	0.068(2)
CB-X minimum*	|| [100]	1.9
	⊥ [100]	0.19
CB-L minimum**	|| [111]	1.9
	⊥ [111]	0.075
VB-HH	[111]	0.72(3)
	[100]	0.33(6)
VB-LH	[111]	0.08(3)
	[100]	0.09(4)

The valence band (VB) states of GaAs are four-fold degenerate at the bandedge and, characteristic of most zincblende semiconductors the valence bandstructure, is significantly more strongly anisotropic than the CB states discussed above. Away from the Γ-point, the four-fold degeneracy of the valence band states is lifted into 2 doubly degenerate sets of bands termed the heavy (HH) and light hole (LH) bands by virtue of their zone center effective masses (Table 1). The HH band is considerably more strongly anisotropic than the LH band and is characterized by a much larger effective mass along the [100] direction when compared with [001], $m_{\mathrm{h}}^{*}[111] > m_{\mathrm{h}}^{*}[001]$. The anisotropy of the LH states is much weaker than for the HH band, with approximately equivalent effective masses along [100] and [111] crystallographic directions. Typical values for the CB and VB effective masses are summarized in Table 1, obtained using a variety of experimental techniques at low temperature.

Temperature Dependence

Quantitative values given above relate specifically to the bandstructure at liquid helium temperatures ($T = 4.2$ K). Increasing temperature results in a narrowing of many of the conduction–valence band gaps discussed above and lowering of the effective masses. This temperature dependence of the fundamental bandstructure arises from the anharmonic dilation of the lattice and from interactions with phonons, the population of which becomes significant at elevated temperature. In the simplest picture, one can visualize the effect of increasing temperature

Table 2 Varshnii coefficients for the Γ, L, and X CB minima in GaAs relative to the top of the VB. For the Γ minimum a number of experimental works are available and the value cited is the average

	$\alpha (10^{-4}$ eV/K$)$	β (K)
Γ point	5.45	210
X point	7.20	205
L point	6.05	204

as a shrinking of the first Brillouin zone as the lattice constant increases, and with a subsequent increase of the band curvature leading to ~5–10% lighter effective masses at room temperature than at 4.2 K. In addition, the dramatic increase of the phonon population at elevated temperatures results in a narrowing of the fundamental bandgaps. Phenomenologically, the temperature dependence of the fundamental bandgaps can be well described by the well-known Varshnii relation

$$E_{\mathrm{g}}(T) = E_{\mathrm{g}}^{T=0\,\mathrm{K}} - \frac{\alpha T^2}{(T+\beta)} \qquad [1]$$

where α and β are experimentally determined constants which are sensitive to the bandgap of interest (e.g. Γ, X, or L, etc.) as summarized in Table 2.



Figure 3 The absolute energy (at 4.2 K) of the Γ, X and L CB minima for $\mathrm{Al}_x\mathrm{Ga}_{(1-x)}\mathrm{As}$ as a function of aluminum composition up to $x \sim 0.8$. Higher compositions are not given due to the well-known unreliability of experimental data due to instability of high Al content $\mathrm{Al}_x\mathrm{Ga}_{(1-x)}\mathrm{As}$ due to oxidation. Polynominals describing each curve are also plotted. Data taken from the following sources: Γ-minimum, Bosio C, Staehli JL, Guzzi M, Burri G and Logan RA (1988) Direct-energy-gap dependence on Al concentration in $\mathrm{Al}_x\mathrm{Ga}_{1-x}\mathrm{As}$. *Physical Review* 38: 3263–3268, X-minimum, Guzzi M, Grilli E, Oggioni S, Staehli JL, Bosio C and Pavesi L (1992) Indirect-energy-gap dependence on Al concentration in $\mathrm{Al}_x\mathrm{Ga}_{1-x}\mathrm{As}$ alloys. *Physical Review* B45: 10951, and L-minimum, Henning JCM, Ansens JPM and Roksnoer PJ (1986) Spectroscopic determination of L6 conduction-band minima in $\mathrm{Al}_x\mathrm{Ga}_{1-x}\mathrm{As}$. *Journal of Physical Chemistry*, L335.

GaAs/$\mathrm{Al}_x\mathrm{Ga}_{(1-x)}$As – The Most Significant Alloy

Incorporation of aluminum into the GaAs crystal to form $\mathrm{Al}_x\mathrm{Ga}_{(1-x)}\mathrm{As}$ results in a number of profound and important modifications of the electronic properties compared with pure GaAs. Aluminum is more strongly electronegative than Gallium and consequently the electron charge distribution along the Al–As bonds are more strongly localized towards the group-III site than for Ga–As bonds which qualitatively results in a widening of the fundamental bandgap with increasing aluminum composition (x).

The variation of the $\mathrm{Al}_x\mathrm{Ga}_{(1-x)}\mathrm{As}$ energy gaps for the Γ, X, and L conduction band minima at low temperature are summarized in Figure 3 as a function of the alloy composition up to $x \sim 0.8$. The data of Figure 3 reflect the results of optical emission and absorption measurements and are most reliable for more dilute compositions since crystalline AlAs and high Al content $\mathrm{Al}_x\mathrm{Ga}_{(1-x)}\mathrm{As}$ oxidize rapidly under atmospheric conditions.[1] With increasing Al content, the Γ-minimum shifts rapidly to higher energy whilst the shift of the L and X-minima is significantly less pronounced. At $x \sim 0.4$ the Γ and X minima intersect and for $x > 0.4$, the lowest energy conduction band minimum shifts to the X-point and the fundamental bandgap becomes indirect. This effect is responsible for the short wavelength cutoff of $\mathrm{Al}_x\mathrm{Ga}_{(1-x)}\mathrm{As}$/GaAs based multi-quantum well LEDs at $\lambda \sim 630$ nm since the transition to an indirect bandgap is accompanied by a drastic reduction of the radiative efficiency. Shorter wavelength LED operation region of the spectrum is possible by moving to other related alloys in the III–V family such as $(\mathrm{Al}_x\mathrm{Ga}_{1-x})_{0.5}\mathrm{In}_{0.5}\mathrm{P}$ (520–630 nm) and $(\mathrm{GaAs})_{0.6}\mathrm{P}_{0.4}$ (~600 nm). We return to discuss the optical properties of $\mathrm{Al}_x\mathrm{Ga}_{(1-x)}\mathrm{As}$ below in Section 4.

As expected, the pronounced modifications of the bandgap induced by Al incorporation are accompanied by modifications of the carrier effective masses and temperature dependence of the bandgap. These compositional dependence of the Γ, X, and L conduction band and HH and LH valence band effective masses are summarized in Table 3.

It should be stressed that the relationships given in Table 3 should be considered to be accurate at the

---

[1] The ease by which high Al content $\mathrm{Al}_x\mathrm{Ga}_{(1-x)}\mathrm{As}$ can be oxidized is of great technological benefit for device fabrication. Examples include the formation of current apertures in injection lasers, $\mathrm{Al}_x\mathrm{Ga}_{(1-x)}\mathrm{As}$ etch stops etc. For a summary Brozel MR and Stillman GE (eds) (1996) *Properties of Gallium Arsenide*, INSPEC, emis Datareviews Series No.16.

Table 3 Compositional variation of the electron and hole effective masses for $Al_xGa_{(1-x)}As$ taken from various sources: Data drawn from the following sources: Lautenschlager Γ-P, Garriga M, Logothetidis S and Cardona M (1997) *Physical Review* B35: 9174 and Grilli E , Guzzi M and Zamboni R (1992) *Physical Review* B45: 1638. Thurmond CD (1975) L-minimum. *Journal Electrochemical Society*, 122: 1133 and Aspines DE (1976) L-Minimum. *Physical Review* B14: 5331

	Crystallographic Axis	*$Al_xGa_{(1-x)}As$ Effective Mass (m^0)*
CB-Γ minimum	*Isotropic*	$0.0682 + 0.0835x$
CB-X minimum	∥ [100]	$1.9 - 1.02x$
	⊥ [100]	$0.19 + 0.06x$
CB-L minimum	∥ [111]	$1.9 - 0.58x$
	⊥ [111]	$0.075 + 0.075x$
VB-HH	DOS	$0.62 + 0.14x$
VB-LH	DOS	$0.087 + 0.09x$

~5–10% level, since reliable experimental data only exists for the GaAs binary endpoint and more dilute alloy compositions ($x < 0.3$).

The Varshnii coefficients of the temperature dependence of the bandgap vary with $x (0 < x < 0.5)$ according to $\alpha(x) = 5.5 + 3.35x(10^{-4}\ \mathrm{eV/K})$ and $\beta(x) = 225 + 88x(\mathrm{K})$ respectively. Recent photoreflectance measurements have indicated that these simple linear relationships do not hold well over the entire compositional range with evidence for some bowing of $\alpha(x)$ and $\beta(x)$ closer to the AlAs binary endpoint.

GaAs/$Al_xGa_{(1-x)}As$ Hetero-interfaces

Modern epitaxial growth techniques now enable the routine fabrication of semiconductor heterostructures consisting of a well-defined sequence of atomically precise layers of different materials, which together manipulate the opto-electronic properties to suit a particular device or application. Of particular technological relevance is the GaAs/$Al_xGa_{(1-x)}As$ hetero-interface since both materials are lattice matched for $0 < x < 1$ (Figure 1), and multiple layers of GaAs and $Al_xGa_{(1-x)}As$ can be readily deposited without introducing defects into the crystal which seriously degrade optical performance. In this section, we summarize the most salient features of the GaAs/$Al_xGa_{(1-x)}As$ hetero-interface, with particular emphasis on the electronic properties before continuing to discuss the optical properties of $Al_xGa_{(1-x)}As$ in Section 4.

The most important parameters that characterize a semiconductor hetero-interface are the magnitude and sign of the conduction (ΔE_c) and valence band (ΔE_v) offsets. These parameters determine how effectively electrons and hole are localized within specific epilayers and are related to the total difference in the bandgap ($\Delta E_g = E_g^{\mathrm{AlGaAs}} - E_g^{\mathrm{GaAs}}$) via $\Delta E_g = |\Delta E_c + \Delta E_v|$. Taking the mean of 21 separate optical and electrical investigations between 1985 and 1995, the currently accepted value for the band-offset ratio is $\Delta E_c/\Delta E_v \approx 64/36$, with an associated variance over the body of the data of approximately ±8%. It should be stressed that the majority of the experimental investigations of the band offsets at the GaAs–$Al_xGa_{(1-x)}As$ hetero-interface have been performed for alloy compositions $x < 0.4$ and much less experimental data exists regarding the variation of $\Delta E_c : \Delta E_v$ with higher Al composition. A rather old review (*c.* 1992), collating data available, at the time has indicated that the absolute energies of the conduction and valence band offsets vary with composition as $\Delta E_c = (800 \pm 30)x$ meV for ($x < 0.4$) and $\Delta E_c = (510 \pm 40)x\ (0 < x < 1)$. It is widely assumed that the band offsets do not change appreciably with temperature.

Optical Properties of GaAs and Significant Alloys

Optical Absorption

Monochromatic light of energy $E_p = \hbar\omega$ incident on the surface of GaAs may stimulate interband optical transitions in which a photon is absorbed and an electron from the valence band is promoted into the conduction band. In processes involving a single photon, the photon momentum is entirely negligible compared with the electron and optical transitions are vertical in k-space.

Following excitation, the electron–hole (e–h) pairs relax extremely rapidly ($\tau_{LO} \sim 150$ fs) by sequential emission of multiple longitudinal optical (LO) phonons until their energy becomes close to the bandedge and further LO-phonon emission is forbidden by energy conservation requirements. This initial phase of the carrier relaxation can be extremely rapid, the LO-phonon scattering time in GaAs being due to the semi-polar nature of the crystal. After this initial rapid relaxation phase, the electron and hole populations relax principally via acoustic phonon emission ($\Delta E < 2$ meV) over much longer timescales (~ 10–300 ps), which depend upon the lattice temperature, carrier type and density. Finally, the electron and hole populations form thermal distributions via carrier–carrier and Auger scattering over longer timescales up ~ 500 ps. During these final relaxation and thermalization phases, e–h pairs are depleted from the conduction and valence bands by interband radiative recombination.

For energies less than the bandgap, the semiconductor normally appears transparent, although the presence of impurities and defect levels can result in a weak absorption 'tail' below the gap. Optical absorption by impurities results in only electrons in the conduction band or holes in the valence band. The wavelength of light that just causes the creation of an electron–hole pair is given by $\lambda = hc/E_g$, where h is Planck's constant, c the speed of light and E_g the fundamental bandgap. As described in Section 3.1, this corresponds to approximately $\lambda = 870$ nm at room temperature, depending on the type and level of the doping. Light with wavelength much shorter than this, corresponding to energies much larger than E_g, will create electron–hole pairs higher up the band structure with higher energy and be strongly absorbed. These carriers, however, will rapidly lose this excess energy by interacting with the lattice and relax to the minima of the conduction and valence bands.

The optical absorption is usually quantified by the absorption coefficient, α, which is a function of the photon energy or wavelength and is shown for GaAs in Figure 4. The fraction of the light intensity that is absorbed in the semiconductor after passing through a thickness x is given by $f = (1 - \exp(-\alpha x))$ and the fraction of light intensity that is transmitted is then simply $\exp(-\alpha x)$. α is usually expressed in units of cm^{-1} and at energies above the bandgap has values typically between 10^4–$10^5\ \mathrm{cm}^{-1}$. Light with wavelength corresponding to energies above the bandgap is usually absorbed very efficiently (>90%) within a few microns. Increasing the bandgap, say by adding aluminum, would have the effect of making the material more transparent at a given wavelength.



Figure 4 Variation of the absorption coefficient, α, as a function of wavelength in GaAs at room temperature.

Optical absorption is an important process as it allows light to be converted to free carriers, and hence a current in the semiconductor. This forms the basis of optical detection by most types of semiconductor photodetectors.

Refractive Index

The speed (more precisely the phase velocity) of light, of all wavelengths, in a vacuum is constant at $\sim 3.10^8\ \mathrm{m\,s}^{-1}$. The speed of light in a medium such as a semiconductor is slower due to the microscopic interaction of the electromagnetic wave with the crystal. The refractive index, R_I, is defined as the ratio of the speed in a vacuum to the speed in the semiconductor. Increasing the density of the medium decreases the speed. Changing the semiconductor, for example by adding aluminum, not only increases the bandgap as discussed above, but also decreases R_I for a given wavelength.

At wavelengths corresponding to an energy just below the bandgap of the semiconductor, the material is essentially transparent, i.e., the absorption coefficient is low.

Light can be made to travel in a waveguide comprising this semiconductor, provided that it was surrounded by semiconductor material of a lower R_I. Light is totally internally refracted at the interface between the GaAs and $\mathrm{Al}_x\mathrm{Ga}_{1-x}\mathrm{As}$ and so cannot escape. The semiconductors with a smaller R_I usually have a larger bandgap, so are even more transparent at the operating wavelength and help to physically confine the electrons and holes within the GaAs.

The R_I can be changed by injecting charge (electrons or holes) into the semiconductor, by changing the temperature (which changes the bandgap), and by applying an electric field. This forms the basis of operation of devices such as optical modulators. Unfortunately it also can cause 'chirping', i.e., the unwanted change in light intensity or wavelength as the charge or temperature changes.

The R_I which is a function of the wavelength, is sometimes expressed as a complex number:

$$R_I = n + ik \qquad [2]$$

where n is the real part and k is the imaginary part called the extinction coefficient, which is related to the absorption coefficient. Typical room temperature values of n for GaAs vary from about 3.37 at ~1.55 μm to 3.87 at 620 nm.

Common GaAs Based Alloys for Novel Technological Applications

GaInP/AlGaInP – 'Red, Orange and Green Emission'

The alloy $(Al_xGa_{1-x})_{0.52}In_{0.48}P$ is becoming technologically important as it has the same lattice parameter as GaAs for all values of x, so can grow lattice matched on GaAs. This alloy system offers the largest direct bandgap of virtually any III–V (excluding the Nitride family), so has attracted considerable interest for visible lasers and LEDs in the wavelength range 530 nm–670 nm. At room temperature the direct Γ bandgap increases almost linearly from ~1.85 eV for $Ga_{0.52}In_{0.48}P$ to ~2.3 for $(Al_{0.5}Ga_{0.5})_{0.52}In_{0.48}P$. For values of $x > 0.5$, the bandgap becomes indirect as in $Al_xGa_{1-x}As$ ($x > 0.4$) when the X-level indirect bandgap becomes lower than the Γ-level direct bandgap. Earlier work in this alloy suggested that the point at which it became indirect was at $x = 0.66$. The X-level bandgap appears to be relatively insensitive to the aluminum composition and has a value of ~2.3 eV at room temperature.

GaAs/GaInAsN – '1.3 μm and 1.55 μm for telecommunication applications'

One limitation of GaAs is that most of the compounds that are lattice matched to it, such as $Al_xGa_{1-x}As$ or $(Al_xGa_{1-x})_{0.52}In_{0.48}P$, have bandgap energies that are large, making them unsuitable for telecommunication applications which require narrow bandgap materials capable of operating in the range 1.3 μm to 1.55 μm. Adding indium (In) to GaAs can decrease the bandgap but also causes strain as the lattice parameter increases, which limits the amount of indium and total thickness of the structure.

Recently, it has been shown that while adding In to GaAs increases the lattice parameter, adding N to GaAs decreases it. Consequently GaInAsN can be made to be lattice matched to GaAs by controlling the In and N content. Unlike conventional alloy semiconductors, adding In or N both result in a reduction of the bandgap energy. Furthermore, GaInAsN is found to be a direct bandgap material with a type I band lineup when combined with $Al_xGa_{1-x}As$, which is a wide bandgap material also lattice matched to GaAs. These properties make GaInAsN ideally suited for lasers and there have been several reports of devices operating at 1.3 μm in the literature.

See also

Semiconductor Physics: Quantum Wells and GaAs-based Structures.

References

Bosio C, Staehli JL, Guzzi M, Burri G and Logan RA (1988) Direct-energy-gap dependence on Al concentration in $Al_xGa_{1-x}As$. *Physical Review* 38: 3263–3268.

Brozel MR and Stillman GE (eds) (1996) *Properties of Gallium Arsenide*, INSPEC, emis Datareviews Series No.16.

Data drawn from the following sources: Lautenschlager Γ-P, Garriga M, Logothetidis S and Cardona M (1997) *Physical Review* B35: 9174 and Grilli E, Guzzi M and Zamboni R (1992) *Physical Review* B45: 1638. Thurmond CD (1975) L-minimum. *Journal Electrochemical Society*, 122: 1133 and Aspines DE (1976) L-Minimum. *Physical Review* B14: 5331.

Guzzi M, Grilli E, Oggioni S, Staehli JL, Bosio C and Pavesi L (1992) Indirect-energy-gap dependence on Al concentration in $Al_xGa_{1-x}As$ alloys. *Physical Review* B45: 10951.

Henning JCM, Ansens JPM and Roksnoer PJ (1986) Spectroscopic determination of L6 conduction-band minima in $Al_xGa_{1-x}As$. *Journal of Physical Chemistry*, L335.

Ioffe Institute, on NSM semiconductor data repository at http://www.ioffe.rssi.ru/SVA/NSM/Semicond/index.html

Landolt-Börnstein (1986) *Numerical data and functional relationships in science and technology.* In: Madelung O (ed.) *Semiconductors*, vol 22. Berlin: Springer Verlag.

Nakwaski W (1995) InAs, AlAs and their ternary compounds. *Physica* B210: 1–25.

Varshni YP (1967) Temperature dependence of the energy gap in semiconductors. *Physica* B34: 149.

Group IV Semiconductors, Si/SiGe

D J Paul, University of Cambridge, Cambridge, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

SiGe is now a mature materials system with electronic circuits on the market place. While no optical devices are available yet, there is a substantial amount of research in the field. In this article, the fundamental materials properties will be reviewed. As SiGe is a strained system, we shall start with the basic material properties as this determines the Ge content and layer thicknesses which are available for use. The band structure and electronic behavior will then be reviewed before the optical properties of the material.

The main drive for SiGe research in optical systems is the ability to use the extensive Si processing knowledge and to integrate a number of components onto a Si chip. Conventional Si transistors may also be used as driver circuits for the optical components, reducing chip counts in systems and therefore reducing costs. As Si processing is substantially cheaper than other semiconductor materials, if SiGe devices can be made on Si processing lines, they have the potential to be substantially cheaper than comparable III–V or II–VI devices. The SiGe material properties that will be reviewed in this article should be considered as an expansion of bulk silicon.

Material Properties and Strain

Ge has a 4.2% larger lattice constant that Si (Table 1). When growing epitaxial films of germanium or the alloy $Si_{1-x}Ge_x$ $(0 < x < 1)$ on a silicon substrate, there exists a maximum thickness called the critical thickness above which it costs too much energy to strain additional layers of material into coherence with the substrate. Instead defects appear, in this case misfit dislocations, which act to relieve the strain in the epitaxial film. Relaxed Si, Ge or SiGe films form diamond, diamond and zincblende lattices respectively while strained heterolayers below the critical thickness form a tetragonal symmetry arrangement. The strain therefore will substantially modify the electronic and optical properties of the material as will be discussed later.

Most SiGe films are produced by either chemical vapor deposition or molecular beam epitaxy. Both these techniques allow the deposition of films at low temperatures (typically 670–970 K) which is essential to prevent strained layers relaxing and forming defects. Chemical vapor deposition uses a number of different gases such as silane, disilane, dichlorosilane, and germane (occasionally with a hydrogen carrier gas) as the main species, while phosphine or arsine are used as n-type dopants and diborane is the typical p-type dopant. With the high melting point of both silicon and germanium, molecular beam epitaxy requires electron beam evaporators for the host materials silicon and germanium while effusion cells of antimony (occasionally phosphorus) and boron are used for n- and p-type dopants, respectively.

There are a number of models used to calculate the equilibrium critical thickness. The most often quoted is the Matthews and Blakeslee model (Figure 1). Experimentally it has been shown that defect-free films with thicknesses above the critical thickness may be grown (Figure 1) although these layers are metastable and will relax if temperatures above the

Table 1 Materials properties of Si, Ge and relaxed $Si_{1-x}Ge_x$

Element		*Si*	*Ge*	*Bulk relaxed $Si_{1-x}Ge_x$*
Lattice		Diamond	Diamond	Zincblende
Lattice constant	a_o (nm)	0.5431	0.5657	$0.5431 + 0.0226x$
Lattice mismatch	η_o (%)	0	4.17	$0.04115x - 0.02500x^2 + 0.05826x^3 - 0.03379x^4$
Density	(kg m^{-3})	2329	5323	$2329 + 2994x$
Sound velocity	m s^{-1} (300 K)	8440	4900	$8440 - 3540x$
Poisson s ratio	ν	0.280	0.273	$0.280 - 0.007x$
Melting point	(K)	1685	1210	
Elastic moduli	c_{11} (GPa)	165.8	128.5	
Elastic moduli	c_{12} (GPa)	63.9	48.3	
Elastic moduli	c_{44} (GPa)	79.6	66.8	
Thermal conductivity	κ (W m^{-1} K^{-1}) (300 K)	140	60	
Dielectric constant	ε	11.9	16.2	$11.9 + 4.1x$



Figure 1 The critical thicknesses for growing a strained $Si_{1-x}Ge_x$ epitaxial layer on a bulk silicon substrate. The white area corresponds to the region below the equilibrium critical thickness as calculated with the Matthews and Blakeslee model while the gray region corresponds to a metastable layer which may relax after thermal treatments. The black area will have dislocations and strain relaxation using any growth technique or temperature.

growth temperature are applied to the heterolayers. For any manufacture, the layers cannot be metastable as high-temperature processes are normally employed in processing. The Matthews and Blakeslee equilibrium critical thickness, h_c for strained-$Si_{1-x}Ge_x$ on bulk Si is given by

$$h_c = \frac{0.55}{x} \ln[10 h_c] \qquad [1]$$

while an approximate value can be obtained from

$$h_c \approx 1.7793 x^{-1.2371} (\mathrm{nm}) \qquad [2]$$

Figure 1 clearly demonstrates that for thick SiGe films, low Ge contents must be used.

There is also a substantial interest in producing low-defect relaxed $Si_{1-y}Ge_y$ films or strained-Si on a relaxed $Si_{1-y}Ge_y$ substrate which can provide bandgaps and band discontinuities not available to pseudomorphically grown alloy layers. Ideally the relaxed $Si_{1-y}Ge_y$ substrate is grown on a Si substrate as this allows integration with conventional complementary metal oxide semiconductor (CMOS) electronics. To date no high-quality bulk single-crystal $Si_{1-y}Ge_y$ substrates are available due to the strong segregation of Si and Ge phases as liquid SiGe crystallizes. Growing a thick $Si_{1-x}Ge_x$ layer on Si well above the critical thickness so that it relaxes produces a threading dislocation density of about 10^{12} cm^{-2} which is far too large to produce device-quality material for electronics or optics. By growing a linearly graded $Si_{1-y}Ge_y$ with the grading rate sufficiently low (typically 10% per μm), the strain relaxation mechanism changes from a nucleation relaxation mechanism to a glide relaxation mechanism resulting in dislocations with comparatively long misfit segments. The defect densities are typically 10^5–10^6 cm^{-2} (Figure 2) although recent thermal processes and other techniques have now reduced this to 100 cm^{-2}.

Substantial work has appeared in the literature on self-organized growth of islands. Such islands are of interest in many materials systems as the quantum confinement they may offer can potentially enhance luminescence properties in numerous opto-electronic devices. The dots are formed by the Stranski–Kranstanow growth mode in a strained system. Planar epitaxial layers grown under stress conditions can lower their elastic energy by morphological changes. For the growth of strained-Ge or $Si_{1-x}Ge_x$ on bulk Si, this corresponds to the formation of islands when the growth parameters in the system are correctly set. While the islands may have well-defined shapes, the formation of the dots relies on random nucleation followed by ripening and coalescence. These mechanisms have produced large distribution of sizes (up to 30% of the mean size), densities and positions. It is quite common to have distributions of two or more sizes of islands and the densities are typically of order of 10^8–10^9 islands per cm^2. While the heights of these islands may be as low as 3 nm, the



Figure 2 A transmission electron micrograph of a strain relaxation buffer grown by DERA, Malvern. The dense region of dislocations corresponds to an approximately 4 μm thick $Si_{1-y}Ge_y$ layer which is graded from $y = 0$ to $y = 0.23$. Above this is a 1 μm thick $Si_{0.77}Ge_{0.23}$ buffer which has no dislocation segments threading to the surface.

widths of the islands are typically 20 nm or greater, which is not yet small enough to produce the quantum confinement properties useful for significant improvements in opto-electronic devices.

Electronic Properties and Band Structure

As many of the optical properties and responses are derived or result from the band structure of materials, this section will concentrate on the band structure and electronic properties of SiGe layers. The bandgap of SiGe whether strained or unstrained is always below that of bulk Si. This potentially allows applications at longer wavelengths than comparable Si devices. Figure 3 shows the appropriate bandgaps for both the unstrained and strained $Si_{1-x}Ge_x$ grown on relaxed Si. For the unstrained case with a Ge fraction $x < 0.85$, the band structure is Si-like with six Δ-valleys forming the conduction band (Figure 4a). For $x > 0.85$ the band structure is Ge-like with four L-valleys. When strain is applied, both the conduction band and the valence band are split. Figure 4b shows the splitting of the conduction band with the Δ_4 valleys lower in energy and the Δ_2 valleys higher. In addition the valence band is split with the heavy-hole band being higher in energy than the light-hole band (Figure 3). The split-off band is also moved further away from the light and heavy hole bands as the strain in the system is increased. The indirect energy gap for the strained $Si_{1-x}Ge_x$ at 4.2 K as measured by photoluminescence is given by

$$E_g = 1.155 - 0.43x + 0.0206x^2\,[\text{eV}] \text{ for } x < 0.85 \qquad [3]$$

$$E_g = 2.010 - 1.27x\,[\text{eV}] \text{ for } x > 0.85 \qquad [4]$$

while the direct bandgap is given by

$$E_g = 3.395 - 1.287x + 0.153x(1-x)\,[\text{eV}]\,(300\,\text{K}) \qquad [5]$$

Due to the critical thickness, measurements of the bandgap of strained $Si_{1-x}Ge_x$ grown pseudomorphically on bulk Si substrates has been limited to low Ge concentrations. Using photoluminescence measurements at 4.2 K, Robbins has obtained a value for the exciton bandgap for strained $Si_{1-x}Ge_x$ layers for $x < 0.25$ to be

$$E_g = 1.155 - 0.874x + 0.376x^2\,[\text{eV}] \qquad [6]$$

The bandgap for any strained $Si_{1-x}Ge_x$ layer grown on a relaxed $Si_{1-y}Ge_y$ substrate is shown in Figure 5. If the active strained $Si_{1-x}Ge_x$ layer is compressively strained then the conduction band is split into Δ_4 valleys being lower in energy and the Δ_2 valleys being higher (Figure 4b). For tensile strain (such as strained Si on a relaxed $Si_{1-y}Ge_y$ substrate), the Δ_2 valleys are lower in energy and the Δ_4 valleys are higher (Figure 4b).

The band alignments for typical heterolayer structures are shown in Figure 6. Pseudomorphically grown strained $Si_{1-x}Ge_x$ layers are only useful for forming quantum wells in the valence band (Figure 6a). Photoluminescence measurements do suggest a type I band alignment for these structures (quantum wells in both the conduction and valence bands) although it was later shown that the material is type II but due to charges producing band bending, the photoluminescence wrongly suggests a type I transition. For a quantum well for electrons, strained Si layers are grown on a relaxed $Si_{1-y}Ge_y$ substrate. In addition, quantum wells in the valence band can be produced for strained $Si_{1-x}Ge_x$ layers with high Ge content grown on relaxed $Si_{1-y}Ge_y$ substrates for $x > y$. In almost all cases the band alignments are type II although a small region exists where theory suggests type I is possible but this has not been demonstrated experimentally at present.



Figure 3 The bandgap energy for strained $Si_{1-x}Ge_x$ on a relaxed Si substrate and unstrained $Si_{1-x}Ge_x$. For the unstrained there is a discontinuity at $x \sim 0.85$ where the band structure changes from Si-like with Δ-valleys to Ge-like with L valleys (see Figure 4).


[001]
[010]
[100]
[$\bar{1}\bar{1}\bar{1}$]
(a)
bulk-Ge and
Strained Si$_{1-x}$Ge$_x$ ($x > 0.85$)
[001]
[010]
[100]
bulk-Si
[001]
[010]
[100]
Energy
E_c
Δ_6
Δ_4
Δ_2
Δ_2
Δ_4
(b)
Relaxed Si$_{1-y}$Ge$_y$ ($y > 0.85$)
Strained Si on relaxed Si$_{1-y}$Ge$_y$
Strained Si$_{1-x}$Ge$_x$ on relaxed Si$_{1-y}$Ge$_y$ ($x > y$)

Figure 4 (a) A schematic diagram of the valleys for Ge-like and Si-like material. (b) A schematic diagram of the valley structures and energy levels of the conduction bands for relaxed, tensile strained (strained Si on relaxed Si$_{1-y}$Ge$_y$) and compressively strained (strained Si$_{1-x}$Ge$_x$ on relaxed Si$_{1-y}$Ge$_y$ ($x > y$)) material.

The valence band discontinuity is given by

$$\Delta E_v = (0.74 - 0.06y)(x - y)\,[\text{eV}] \qquad [7]$$

while the conduction band discontinuity for strained Si on a relaxed Si$_{1-y}$Ge$_y$ substrate is

$$\Delta E_c = 0.6y\,[\text{eV}] \qquad \text{for } x < 0.6 \qquad [8]$$

The complete set of ΔE_c and ΔE_v values for all x and y are shown in Figures 7 and 8 respectively. Table 2 gives some of the electronic data on Si, Ge, and relaxed Si$_{1-x}$Ge$_x$ including mobilities, bandgaps, and effective masses.

The mobilities for electrons and holes in relaxed Si$_{1-x}$Ge$_x$ layers are below the bulk Si and Ge layers due to alloy scattering (Table 2). For strained layers, mobility enhancements have been demonstrated in a number of different systems. Electron mobility enhancements result from the splitting of the valleys reducing intervalley scattering. Hole mobility enhancements result from the splitting of the valence band and reduction of effective masses. The hole mobilities for pseudomorphically grown strained Si$_{1-x}$Ge$_x$ quantum wells have shown values as high as 17 000 cm^2 V^{-1} s^{-1} at a carrier density of 2×10^{11} cm^{-2} for Si$_{0.87}$Ge$_{0.13}$ layers. Higher Ge contents reduce the mobility due to alloy scattering. At room temperature, only modest mobility improvements of about 20% have been observed giving 220 cm^2 V^{-1} s^{-1} at the high carrier



Figure 5 The bandgap energy (in meV) for strained $Si_{1-x}Ge_x$ grown on a relaxed $Si_{1-y}Ge_y$ substrate. Theoretical curves from Riger and Vogl have been calibrated to the experimental data from pseudomorphic layers.

densities required for electronic devices of about 2×10^{12} cm^{-2}. To remove alloy scattering, pure strained Ge channels grown on relaxed $Si_{1-y}Ge_y$ substrates have shown low-temperature mobilities of 55 000 cm^2 V^{-1} s^{-1} for densities of 5×10^{11} cm^{-2} with the room-temperature values reaching 1665 cm^2 V^{-1} s^{-1}. For electrons, a strained Si layer on relaxed $Si_{1-y}Ge_y$ substrates ($0.2 < y < 0.3$) also reduces the alloy scattering in the channel and produces much higher low-temperature mobilities of 390 000 cm^2 V^{-1} s^{-1} for densities of 4×10^{11} cm^{-2} while room-temperature values have peaked at 2830 cm^2 V^{-1} s^{-1}. All these values correspond to electrons or holes at heterointerfaces. Enhanced mobilities have also been observed for strained Si metal oxide semiconductor field effect transistors (MOSFET) where electron mobility enhancements of 75% compared to the bulk Si devices has been reported on relaxed $Si_{0.8}Ge_{0.2}$ although intrinsic transconductances are only increased by 60%. For holes, a strained Si layer on a $Si_{0.8}Ge_{0.2}$ relaxed substrate has demonstrated a 50% mobility enhancement over a bulk Si MOSFET.


(a)
$\Delta E_c < 20$ meV
E_c
bulk Si
$E_g = 1.17$ eV
strained
$Si_{0.8}Ge_{0.2}$
$E_g \approx 1.04$ eV
E_v
$\Delta E_v \approx 150$ meV
(b)
$\Delta E_c \approx 180$ meV
E_c
relaxed $Si_{0.7}Ge_{0.3}$
$E_g \approx 1.08$ eV
strained Si
$E_g \approx 0.955$ eV
$\Delta E_v \approx 55$ meV
E_v
(c)
$\Delta E_c \approx 110$ meV
E_c
relaxed $Si_{0.7}Ge_{0.3}$
$E_g \approx 1.08$ eV
strained
$Si_{0.2}Ge_{0.8}$
$E_g \approx 0.83$ eV
E_v
$\Delta E_v \approx 360$ meV

Figure 6 A schematic diagram of some typical SiGe heterolayer structures showing the bandgap, conduction band discontinuity, ΔE_c, and the valence band discontinuity, ΔE_v. (a) shows a quantum well in the valence band using a pseudomorphic strained $Si_{0.8}Ge_{0.2}$ layer; (b) shows a quantum well in the conduction band using a strained Si layer on a relaxed $Si_{0.7}Ge_{0.3}$ substrate; and (c) shows a quantum well in the valence band using a high Ge content layer on a relaxed substrate with lower Ge content.

The effective mass for electrons in strained Si layers on relaxed $Si_{1-y}Ge_y$ substrates for $0.1 < y < 0.4$ has produced a very small spread of effective masses with values of 0.19 m_0 (where m_0 is the free electron mass) for the longitudinal mass as measured by cyclotron resonance and the temperature dependence of Shubnikov–de Haas oscillations. The electron effective masses are very similar to the bulk values for strained Si quantum wells. Hole effective masses in pseudomorphically strained $Si_{1-x}Ge_x$ layers have produced a large spread of data even for similar alloy and strain values mainly due to the large nonparabolicity of the valence band (Table 3) and many of the measured samples having metastable $Si_{1-x}Ge_x$ quantum wells. The in-plane hole mass is theoretically expected to decrease as the strain in the system is increased but to date the experimental values have been much lower than theoretically calculated values. Experimental data (Table 3)



Figure 7 The conduction band discontinuity (in meV) for strained $Si_{1-x}Ge_x$ grown on a relaxed $Si_{1-y}Ge_y$ substrate. Positive numbers correspond to potential barriers to electrons while negative values represent quantum wells. The general trends and unknown experimental regimes are from the theoretical work of Rieger and Vogl while the quantum well data for $0.1 < y < 0.4$ and $x = 0$ has been recalibrated from experimental work. No experimental data are known to allow calibration of the barrier regime.



Figure 8 The valence band discontinuity (in meV) for strained $Si_{1-x}Ge_x$ grown on a relaxed $Si_{1-y}Ge_y$ substrate. Positive numbers correspond to quantum wells for holes while negative values represent potential barriers. The values from theory in the quantum well region agree well with experimental values but little experimental data exist to compare the barrier data from the theorertical values (plot from Rieger and Vogl) with experiment.

suggests that strained $Si_{0.88}Ge_{0.12}$ layers have a heavy effective mass of about $0.3\,m_0$ compared to the bulk value of $0.55\,m_0$.

Optical Properties

Due to the problems of producing high-quality single crystals of $Si_{1-x}Ge_x$, there are relatively little data on the optical properties of relaxed $Si_{1-x}Ge_x$ in the literature. The situation is even worse for strained $Si_{1-x}Ge_x$ as the layer thicknesses are limited to below 30 nm for Ge contents above 0.1, a value much smaller than the penetration depths in the system at most optical frequencies. There is, however, substantial interest in the optical properties, particularly the refractive index, as they suggest that SiGe can be used as a waveguide on Si substrates.

For the relaxed $Si_{1-x}Ge_x$ layers, most of the published work in the field has been from crystals grown by liquid phase epitaxy using melts of indium or tin. The samples had free hole concentrations of $10^{17}\,cm^{-3}$ along with indium or tin impurities and details can be found in the reviews by Humlícek. Some of the data are also from thick epitaxial layers grown well above the critical thickness where the threading dislocation density is likely to be about $10^{12}\,cm^{-2}$. The data below 2 eV were obtained by absorption measurements, those between 2 and 5.6 eV have been obtained using ellipsometry and the values between 6 and 12 eV were obtained by reflectance measurements.

Figures 9 and 10 show the real and imaginary parts of the complex dielectric function defined as $\varepsilon = \varepsilon_1 + i\varepsilon_2$ where $i = \sqrt{-1}$ for a number of different Ge contents. Figures 11 and 12 show the real and imaginary parts of the complex refractive index defined by $N = n + ik = \sqrt{\varepsilon}$. The peak starting at 3.395 eV and decreasing as the Ge content is increased corresponds to the E_1 transition across the direct gap and may be used to find the Ge content using the expression

$$x = 4.707 - \sqrt{6.538E_1 - 0.0397} \qquad [9]$$

The refractive index is high owing to the strong electronic interband absorption in the visible and ultraviolet regions of the spectrum.

The other important optical property of the material is the absorption. The absorption coefficient is defined as $K = 4\pi k/\lambda$ where k is the extinction coefficient for a wavelength λ. The intensity of a wave traversing a distance d in a homogeneous medium of extinction coefficient, k, is attenuated by a factor $\exp(-Kd)$. Therefore $1/K$ is the penetration depth. The absorption coefficient is shown in Figure 13.

Table 2 Electronic properties of Si, Ge and relaxed $Si_{1-x}Ge_x$

Element		*Si*	*Ge*	*Bulk unstrained* $Si_{1-x}Ge_x$
Direct bandgap	(eV) at 300 K	3.4	0.80	$3.395 - 1.287x + 0.153x(1 - x)$
Indirect bandgap	(eV) at 300 K	1.11 (D)	0.664 (L)	$1.155 - 0.43x + 0.0206x^2$ $(x < 0.85)$ $2.010 - 1.27x$ $(x > 0.85)$
Spin-orbit splitting	Δ_{so} (meV)	44	290	Discontinuity at $x \sim 0.85$
Electron mobility	μ_e ($cm^2\ V^{-1}\ s^{-1}$) at 300 K	1450	3900	$\mu_e = 1466.2 - 6425.9x + 6601.8x^2 + 7716.5x^3 - 10944x^4 (x < 0.6)$ $\mu_e = 2.9235 \times 10^{-28} e^{71.105x} + 4790.1 - 14246x + 11117x^2 (x > 0.6)$
Hole mobility	μ_h ($cm^2\ V^{-1}\ s^1$) at 300 K	505	1800	$\mu_h = 188.42 - 935.7x + 5455.5x^2 - 8553.7x^3 + 5751.7x^4$(all x) ($N_A = 1 - 50 \times 10^{16}\ cm^{-3}$)
Longitudinal electron mass	m_l^*	0.1905	0.082	Discontinuity at $x \sim 0.85$
Transverse electron mass	m_t^*	0.9163	1.58	Discontinuity at $x \sim 0.85$
Heavy-hole mass	m_{hh}^*	0.537	0.284	Discontinuity at $x \sim 0.85$
Light-hole mass	m_{lh}^*	0.153	0.044	Discontinuity at $x \sim 0.85$
Spin–orbit mass	m_{so}^*	0.234	0.095	Discontinuity at $x \sim 0.85$

Table 3 A comparison of effective masses in modulation-doped samples as measured by the temperature dependence of the Shubnikov–de Haas oscillations (SdH) or by cyclotron resonance (CR) at liquid helium temperatures. All samples have strained $Si_{0.88}Ge_{0.12}$ or $Si_{0.87}Ge_{0.13}$ quantum wells grown on bulk Si substrates. Therefore only the heavy-hole band should be populated at these low temperatures and strain values. ℓ is the mean free path which is the mean scattering distance of a hole in the system and is a quantitative measure of disorder

	Mobility ($cm^2\ V^{-1}\ s^{-1}$)	p ($\times 10^{11}\ cm^{-2}$)	ℓ (nm)	m^* (m_0) *SdH*	m^* (m_0) *CR*
DERA	6560	4.4	71	0.304	0.26
NRC	6800	5.9	86	0.31	–
IBM	6000	3.7	60	0.34	0.18
Warwick	9600	2.5	78	0.27	0.23, 0.29
Warwick	10500	2.1	78	0.27	0.24, 0.30



Figure 9 The real part (ε_1) of the complex dielectric function $\varepsilon = \varepsilon_1 + i\varepsilon_2$.



Figure 10 The imaginary part (ε_2) of the complex dielectric function $\varepsilon = \varepsilon_1 + i\varepsilon_2$.



Figure 11 The real part (n) of the complex refractive index $N = n + ik$.



Figure 12 The imaginary part (k) of the complex refractive index $N = n + ik$.

Determining the optical properties of strained $Si_{1-x}Ge_x$ layers has been substantially more difficult. The major problem is that the absorption coefficient is about $10-20\,\text{cm}^{-1}$ around the fundamental bandgap (Figure 6) and therefore any shift due to strain effects becomes very difficult to observe using absorption techniques in thin SiGe layers. Additional complexity results as the substrate material has a fundamental bandgap close to the strained layer. Therefore photoluminescence is one of the few methods for extracting experimentally the optical changes due to strain.



Figure 13 The absorption coefficient K.

The splitting of the conduction (Figure 8) and valence bands (Figure 9) has already been discussed. The photoluminescence signals will also shift with strain for the lowest lying bandgap energy. Almost all the experimental data for strained layers have been obtained for pseudomorphically grown strained $Si_{1-x}Ge_x$ alloys on bulk Si substrates and the data agree well with the bandgaps shown in Figures 3 and 5. The quantum well photoluminescence signal is found to shift by −1.4 meV per kbar of pressure. After removal of nonhydrostatic components, a value of −1.52 meV per kbar for the pure hydrostatic shift has been reported.

Conclusions

A review has been presented of the fundamental properties of relaxed and strained $Si_{1-x}Ge_x$ alloys. The materials properties were first reviewed and demonstrate the limitations imposed by the critical thickness. The electronic properties including the bandstructure were then discussed and demonstrate the lowered bandgap for $Si_{1-x}Ge_x$ alloy compositions compared to bulk Si. This property has been used in $Si_{1-x}Ge_x$ p-i-n photodetectors to move the absorption to longer wavelengths in an attempt to compete with III–V photodetectors for the important 1.3 μm and 1.55 μm fiber optic frequencies. In the final section the optical properties of relaxed and strained $Si_{1-x}Ge_x$ material were reviewed. The difference in refractive indices has opened research into SiGe on Si waveguides.

List of Units and Nomenclature

Absorption coefficient (K)	[cm^{-1}]
Band gap energy (E_g)	[eV]
Conduction band discontinuity (ΔE_c)	[meV]
Critical thickness	[nm]
Density	[kg m^{-3}]
Dielectric constant (ε)	
Effective mass [m_0 where $m_0 = 9.11 \times 10^{-31}$ *kg*]	
Elastic moduli (c_{ij})	[GPa]
Extinction coefficient (k)	[cm^{-1}]
Lattice constant (a_0)	[nm]
Mean free path (l)	[nm]
Melting point	[K]
Mobility (μ)	[cm^2 V^{-1} s^{-1}]
Pressure	[kbar]
Refractive index (N)	
Sheet carrier densities	[cm^{-2}]
Sound velocity	[m s^{-1}]
Temperature	[K]
Thermal conductivity (κ)	[W m^{-1} K^{-1}]
Valence band discontinuity (ΔE_v)	[meV]
Wavelength (λ)	[nm]

See also

Semiconductor Physics: Band Structure and Optical Properties; Outline of Basic Electronic Properties; Recombination Processes.

Further Reading

Humlícek J, Garriga M, Alonso MI and Cardona M (1989) Optical spectra of $Si_{1-x}Ge_x$ alloys. *Journal of Applied Physics* 65(7): 2827–2832.

Humlícek J, Lukes F and Schmidt E (1991) Silicon-germanium alloys (Si_xGe_{1-x}). In: Palik ED (ed.) *Handbook of Optical Constants of Solids*, vol. II, pp. 607–636. San Diego, CA: Academic Press.

Kasper E and Lyutovich K (eds) *Properties of Silicon Germanium and SiGe:Carbon*. London: INSPEC IEE.

Paul DJ (1999) Silicon-germanium strained layer materials in microelectronics. *Advanced Materials* 11(3): 191–204.

Rieger MM and Vogl P (1993) Electronic-band parameters in strained $Si_{1-x}Ge_x$ alloys on $Si_{1-y}Ge_y$ substrates. *Physical Review B* 48(19): 14276–14287.

Robbins DJ, Canham LT, Barnett SJ, Pitt AD and Calcott P (1992) Near band gap photoluminescence from pseudomorphic $Si_{1-x}Ge_x$ single layers on silicon. *Journal of Applied Physics* 71(3): 1407–1414.

III-Nitrides

K P O'Donnell, University of Strathclyde, Glasgow, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction to InGaN

The optical properties of wurtzite GaN are of interest mainly to band-structure theorists. Luminescence from pure InN has probably never been detected. It is therefore surprising that the combination of these binary III–N compounds produces a solid solution, InGaN, which has revolutionized blue–green optoelectronics in the last 10 years, and may form the basis of a new lighting technology to replace the tungsten lamp in the first half of the twenty-first century.

InGaN is also the material basis of the blue laser diode, which will be used for future generations of optical data storage and for many other applications that require a compact source of short-wavelength coherent light. The market for nitride light emitters has been growing at a rate of ~20% a year since the introduction of the first blue nitride light-emitting diode (LED) by Nichia Chemical in 1993. The first commercial lasers, with lifetimes in excess of 10 000 hours, were released in 1998.

So what is InGaN? The naïve response–that it is a semiconductor alloy–ignores the theoretical demonstration, based on simple equilibrium thermodynamics, that InN is insoluble in GaN at the temperatures usual for growth (using metalorganic vapor phase epitaxy, MOVPE). If we imagine a cation lattice, on which we distribute Ga and In atoms, in a fixed numerical proportion, in order to form a solid solution of given composition, it is thermodynamically probable that the In atoms will associate to form agglomerations in certain regions of the lattice. The size, shape, and properties of the resulting concentration fluctuations have been a topic of intense speculation.

Practically speaking, InGaN layers are grown either as rather thin (<3 nm) quantum wells (QWs) immersed in GaN or AlGaN or as thicker epilayers (10–500 nm) on top of thick GaN templates. Only the QWs are of use in devices, whereas the composition and structure of the thick epilayers are easier to measure in research applications. It is dangerous to suppose that the material retains the same properties when grown in thicker layers. Recently, a third class of sample has emerged, in the form of self-organized ‘quantum boxes’ (originally French *bôites*), which we shall call QBs. These samples, grown at low temperatures by molecular beam epitaxy (MBE) comprise pancake-shaped disks of uncertain composition, about 50 nm across and 3–5 nm high.

Optical Spectra of Devices

There have been several ‘generations’ of nitride LED. We refer here to the Nichia Blue, Extrablue (actually turquoise) and Green diodes which set the scene in 1996, and the Amber diode which first appeared in 1998, although not yet available commercially. The spectral properties of these devices have been stable while their efficiencies have improved in the intervening years. The basic design appears to incorporate a single quantum well. Up to a point, the wavelength tuning depends upon the incorporation of different amounts of indium in the well. (Green and amber devices may have the same amount.)

In what follows, we prefer to specify composition by quoting the indium nitride content, x, according to the formula unit

$$\mathrm{In}_x\mathrm{Ga}_{1-x}\mathrm{N} = x\mathrm{InN} + (1-x)\mathrm{GaN} \qquad [1]$$

Electroluminescence (EL) spectra of blue and green diodes are shown in Figure 1. Spectra are broad (compared to k_BT at room temperature) with exponential tails to high and low photon energies. The linewidth tends to increase as the device peak wavelength shifts further to the red.

Whereas it is difficult to measure directly the optical absorption spectrum of an ultrathin layer of material, an equivalent measurement can be made on an LED by monitoring the photocurrent (PC) generated by incident monochromatic light. PC spectra of the blue and green diode are shown in Figure 1, together with the absorption and photoluminescence (PL) spectra of a thick violet-light-emitting epilayer.

The spectra of Figure 1 transform into each other by ‘stretching’ the x-axis, using the bandgap energy of GaN as an anchor point. Comparison of many pairs of spectra produces evidence of a *universal scaling behavior*, which relates the details of each spectrum to a single controlling parameter. In the case of epilayers, this is undoubtedly the InN fraction, as we shall see later.



Figure 1 EL and PC (quasi-absorption) spectra of nitride LEDs, compared to PL and absorption spectra of a thick InGaN epilayer.

In order to describe the form of the absorption/excitation curve, we introduce the formal expression

$$\alpha = \frac{\alpha_0}{1 + \exp\left(\dfrac{E_g - E}{\Delta E}\right)} \qquad [2]$$

where α_0 is the plateau absorption, observed experimentally, but not yet theoretically explained, E_g is the (effective) bandgap energy of the sample, E is the photon energy, and ΔE is an energy broadening term, similar to the well-known Urbach parameter.

Optical Energy Relationships

The spectral universality pointed out in the previous section requires the existence of certain relationships between the optical energies. We list the defining energies as the bandgap, E_g, the peak energy of EL or PL, E_p, and the difference between these energies, measured for a particular sample, which we call the Stokes shift:

$$\mathrm{SS} = E_g - E_p \qquad [3]$$

(While the energy broadening tends to increase in a regular fashion with the Stokes shift, there are irregularities in both ΔE and the PL linewidths of samples from different sources. Hence ΔE and PL



Figure 2 Linear dependence of luminescence peak energy on effective bandgap.

linewidth appear to be local rather than universal parameters.)

The relationship between E_g and E_p for a wide range of emitters is found to be linear (Figure 2):

$$E_p = 1.45E_g - 1.54 \qquad [4]$$

The bandgap energy and luminescence peak energy coincide at 1.54/(1.45 − 1) = 3.42 eV, which corresponds to the energy bandgap of pure GaN. The simple linear dependence of E_p upon E_g implies a linear increase of the Stokes shift energy with increasing detuning from the GaN band edge.

Dependence of Optical Energies on *x*, the InN Fraction, for Thick Epilayers

As stated above, it is usual to measure the composition of thick layers, rather than quantum wells, for reasons of experimental convenience. Several techniques can be used to this end, including measurement of the lattice constants by X-ray diffraction (XRD) (one asymmetric and one symmetric reflections are required to take into account the strain state of the layer), Rutherford backscattering spectrometry (RBS), wavelength-dispersive (preferable) or energy-dispersive X-ray fluorescence (XRF), sputtered ion mass spectroscopy (SIMS), and extended X-ray absorption fine structure (EXAFS).

All usable techniques provide comparable results if carried out with sufficient care. We plot the peak energy of PL emission against the measured indium nitride fraction for a range of epilayer samples in Figure 3. Once more, the dependence appears to be linear in a restricted composition range. The best-fit line to a linear function $E_p(x)$ has an x-intercept which is close to the bandgap of GaN. The dependence of the optical energies on the indium nitride fraction can now be summarized by three interdependent linear relations, which are valid in the composition range $0 < x < 0.4$:



Figure 3 Linear dependence of the PL peak energy on the InN content of InGaN epilayers.

$$E_p = 3.4 - 4.4x$$

$$E_g = 3.4 - 3.0x \qquad [5]$$

$$SS = 1.4x$$

The measurements described above rely on separate determinations of composition and an optical energy for each sample. Since all samples are to some extent inhomogeneous, it would be preferable to make such measurements at one and the same time. This can be done by using an electron probe microanalyzer, modified to allow simultaneous cathodoluminescence (CL) spectroscopy. CL is analogous to PL. A recent study of samples with $0.05 < x < 0.25$ has yielded the result:

$$E_c = 3.40(1) - 3.91(5)x \qquad [6]$$

with error bars (shown) that are about ten times smaller than those of the previous work.

Bandgap of InN

It is dangerous to extrapolate experimentally determined relationships beyond the range of measurements used to derive them.

The bandgap of an alloy is best represented by a quadratic function of x, with the deviation from linearity described by a bowing parameter. The above measurements suggest a small bowing parameter for the InGaN alloy system. If we ignore bowing and equate E_p with E_c, the InN bandgap obtained by setting $x = 1$ is calculated to be 0.71 eV. This is certainly an underestimate, but is similar to recent values obtained experimentally for layers of pure InN grown by Molecular Beam Epitaxy. Before the year 2000, the generally accepted value of the InN bandgap was close to 2 eV.

Origin of the Stokes Shift

Stokes shifts originate in systematic energy loss during the excitation–luminescence cycle. While the bandgap, as defined above, is the mean energy of electron–hole pairs across the bandgap, the PL peak is the modal energy of electron–hole recombination. The large Stokes shift in the InGaN system is probably due to the influence of giant internal electric fields that separate the carriers prior to recombination.

In the absence of a microscopic model, it is difficult to provide a quantitative description of energy loss in the excitation–emission cycle. Experiment shows that the shift can be as large as ~ 0.6 eV in an epilayer with $x = 0.4$. If such a layer were 100 nm thick and uniform in composition, it would be strained by about 4% when pseudomorphic to a GaN template, with an estimated vertical electric field of 6×10^6 V m^{-1}. Unit strain would correspond to a 15-eV shift (equivalent to a piezoelectric deformation potential). While these numbers are large, they seem reasonable in the light of sophisticated theoretical calculations of the magnitude of the piezoelectric effect in InGaN. But it is an unfortunate experimental fact that layers grown with different thicknesses, and presumably under different states of strain, may show the same value of the Stokes shift.

If the material has composition fluctuations, accompanied by strain variations, the recombination energy will be much more sensitive to the local environment. One can imagine a situation in which recombination always takes place at the lowest available energy, as carriers diffuse under the action of local strain/electric fields. This situation would be rather similar to that which pertains in quantum wells with spatial energy disorder, caused by well width fluctuations. A theoretical treatment of localization in three dimensions would be very difficult.

In any case, the physical situation of excitation and recombination in the presence of an electric field is that sketched in Figure 4.



Figure 4 Excitation–emission cycle in the presence of an electric field. CB and VB are conduction band and valence band, respectively.

Quantum Wells and Quantum Boxes

The incorporation of quantum wells has several advantages for light-emitting devices. In nitrides, the expected increase of oscillator strength for radiative transitions, due to the reduced dimensionality, is mitigated to some extent by the opposing effect of the internal electric fields, but the quantum well still acts as an energy sink for mobile excitations and as a site for carrier localization.

Quantum confinement can also act as a wavelength tuning mechanism in QW devices. The effect in blue-emitting nitride devices is rather small until the QW width falls below 3 nm. It should be clear that a reduction in the photon energy of recombination with increasing well width will accompany vertical separation of carriers in a piezoelectric model. Usually, as mentioned above, wavelength tuning in nitride devices is accomplished by changing the composition. What should we make of the fact that amber and green diodes apparently have the same composition? It would appear that the well widths are different. On the other hand, the amber emitters have anomalously narrow linewidths, which may imply that some other mechanism is in force. Here, we must let the matter rest, in the absence of detailed structural information.

Quantum boxes should be distinguished from quantum dots (QDs). The former are mesoscopic objects that form spontaneously under certain growth conditions, which usually involve the influence of strain. The best-characterized example in semiconductor physics is the Stranski–Krastanow growth of InGaAs structures on GaAs. While GaN in AlGaN forms recognizable nanocrystals, InGaN forms less well-defined structures of indeterminate shape, some 30–50 nm in lateral extent and 3–10 nm high. QDs, on the other hand, are truly zero-dimensional objects, in the sense that carrier motion is quantized simultaneously in three spatial dimensions. The utilization of reduced dimensionality to enhance recombination probabilities in active devices is only valid when QB structures meet the criteria of low dimensionality: the carrier motion must be restricted to a distance smaller than the appropriate Bohr radius.

Structure of InGaN Epilayers

The state of strain of InGaN epilayers is usually determined by XRD. Both symmetric and asymmetric reflections are required to calculate the actual values of the out-of-plane and in-plane lattice constants, c and a, respectively. These can then be compared with those predicted for a relaxed alloy by Vegard's law, for example:

$$c(\mathrm{In}_x\mathrm{Ga}_{1-x}\mathrm{N}) = xc_{\mathrm{InGaN}} + (1-x)c_{\mathrm{GaN}} \qquad [7]$$

The composition itself, as well as the state of strain, can be determined from measurements of c and a with one additional assumption: that the Poisson ratio of the alloy also obeys Vegard's law. If the composition is known from an independent chemical measurement, this assumption can be tested.



Figure 5 EXAFS-determined local structure parameters of thick InGan films.

InGaN epilayers are usually grown on thick GaN formers. In pseudomorphic growth, the constraint, $a(\text{layer}) = a_{\text{GaN}}$ applies. This is sometimes assumed to be the case when layers are thinner than about 50 nm, but nothing should be taken for granted when dealing with this material. Each layer is different. A similar warning applies to the assumption that thick InGaN layers will be relaxed. It has recently been shown that partially relaxed and pseudomorphic regions may actually coexist within the same InGaN film, which nevertheless has a composition that is uniform throughout. Other films may show a concentration gradient due to compositional pulling during growth.

The local structure of InGaN films has been measured using In-edge EXAFS. Using a tetrahedral two-shell model that does not distinguish the wurtzite and cubic crystal structures, we find that the In–N1 bond length is more or less independent of the alloy composition in the range $0.17 < x < 0.38$ of samples measured, having a value of 2.11(1) Å (compared to 2.16 Å in pure InN). The M1 shell of mixed In and Ga atoms is located on average at about 3.28 Å, as shown in Figure 5.

The straight line on the figure connects the values of the a lattice parameters (of GaN at $x = 0$ and InN at $x = 1$) and hence represents the predictions of Vegard's law for a relaxed or bulk alloy. The measured In–M1 separations are less dependent on x than Vegard predicts.



Figure 6 Fourier transform of the EXAFS spectrum yields the radial distribution function of an InGaN QB sample.

Local Structure of InGaN QW and QB

There has been a great deal of speculation in the literature concerning the local structure of InGaN alloys in the active layers of light-emitting devices. Much of this discussion paddles in the shallows of invalid comparison, as researchers extrapolate their findings from the results of measurements and calculations that can be made to those that cannot. One example is the large theoretical effort devoted to the defect physics of GaN, which is supposed somehow to 'explain' the optical properties of InGaN. ('Let us first suppose that all the horses in the race are spherical.')

We will try to avoid invalid comparisons in the brief discussion that follows. Recently, a Strathclyde University/Daresbury Laboratories/CHEA-CNRS Valbonne collaboration has succeeded in measuring the local structure of an InGaN QB sample, grown on a thick GaN template by MBE. The radial distribution function (RDF) around the target In probe atom is shown in Figure 6, together with a three-shell fit to the data.

The first shell of neighbors comprises four N atoms at 2.10(2) Å, the second shell is pure Ga at 3.22(3) Å, and the third shell pure In at 3.56(3) Å. These results suggest that there are two distinct In environments in such samples. One resembles the InGaN alloy, encountered in the epilayer samples, while the other is an environment of pure InN.

On the basis of these results, it is extremely likely that InGaN phase-separates in QB growth to form a two-component mixture comprising an In-poor and an In-rich phase. The manner in which these phases interpenetrate is a matter for speculation.

See also

Semiconductor Materials: Quantum Dots. **Semiconductor Physics:** Infrared Lattice Properties; Light Scattering; Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures.

Further Reading

Gil B (ed.) (1998) *Group III Nitride Semiconductor Compounds, Physics and Applications*. Series on Semiconductor Science and Technology 6. Oxford, UK: Oxford Science Publications.

Gil B (ed.) (2002) *Low Dimensional Nitride Semiconductors*. Oxford, UK: Oxford Science Publications.

Nakamura S and Fasol G (2000) *The Blue Laser Diode*, 2nd edn. Berlin: Springer-Verlag.

Large Gap II–VI Semiconductors

J F Donegan, Trinity College Dublin, Dublin, Ireland

© 2005, Elsevier Ltd. All Rights Reserved.

Background

The chemical reaction of group IIA (Be, Mg), IIB(Zn, Cd) and group VI (O, S, Se, Te) atoms produces solid crystalline materials which are classified as semiconductors. The archetypal compound is ZnSe and this material will be used as the main example in this article. These are termed II–VI binary (involving two elements) compounds. It is also possible to grow alloy materials where more than one atom from each group is used; an example is $Zn_xCd_{1-x}Se$ where x is the proportion of Zn in the material. In general, there is a random arrangement of the Zn and Cd atoms within the crystal structure. Both binary and alloy semiconductor materials are single crystals so that the atoms are arranged in a periodic three-dimensional system called a lattice. The lattice may be represented by a unit cell; simply by repeating the pattern of the unit cell, we can generate the entire crystal lattice.

At the atomic level, the zinc (selenium) atom is bonded to 4 selenium (zinc) atoms which are arranged at the corners of a tetrahedron. The unit cell formed by this tetrahedral arrangement is termed the zincblende structure and is illustrated in Figure 1a. The dimension shown is called the lattice constant a and is characteristic of a particular II–VI semiconductor material. Some II–VI materials crystallize with a different unit cell which is termed the wurtzite structure, though again the atoms are bonded to four others in a tetrahedral arrangement as shown in Figure 1b. In this case, two lattice constants denoted a and c are required to characterize the unit cell. Some of the II–VI materials can occur in either of these two structures depending on how they were grown. The lattice constants of several II–VI compounds are given in Table 1.

II–VI Materials Growth

All of the II–VI family of semiconductors have high melting points due to the strong bonding that exists between the atomic species; values are given in



Figure 1 (a) Zincblende lattice; (b) wurtzite lattice. *a* and *c* are the lattice constants as given in Table 1.

Table 1. The crystals can be grown either by cooling a liquid (often called a melt) or by condensation from a gas (vapor). Crystal growth is a very precise and difficult process requiring the control of a large number of variables most notably temperature and pressure. As many of the II–VI materials can exist in either the zincblende or wurtzite structures, producing single crystals with only one structure is often quite difficult. Many of the crystals are 'twinned'; in a zincblende structure, a twin produces a wurtzite structure in one plane. The photograph in Figure 2 shows a ZnSe single crystal. This crystal took several days to grow indicating that very stable growth conditions must be maintained over long periods of time. The vapor phase technique takes advantage of the high vapor pressure of the II–VI compounds that allows for the growth of large single crystals at temperatures much below the melting point of these materials. Vapor growth is helped also by the congruent evaporation of the two constituents into the vapor state in a dissociated form. These two vapor constituents also recombine stoichiometrically into the solid crystal. The melting points and vapor pressures at the melting points of some II–VI semiconductors are given in Table 1.

It is also possible to grow materials in a layer-by-layer fashion onto an existing substrate; this is termed epitaxial growth. Recent developments have allowed the growth to proceed one atomic layer after the other. As a result, materials can be grown that are less than 100 Å in size. At these small sizes, the fundamental electronic and optical behavior of these materials is altered due to quantum mechanical effects. These materials are termed quantum wells. Growth temperatures in these cases are much below the melting point of these materials and allow for uniform single crystals without any 'twin' formation. In molecular beam epitaxy (MBE), atomic beams of the constituents impinge onto a heated substrate where they combine to form the crystalline material. Growth of ZnSe onto III–V substrates such as GaAs is well developed. The quality or purity of the single crystals can often be deduced from their optical properties as we will see later.

The addition of small amounts of other atoms into the crystal during the growth procedure is called doping. Semiconductors are materials whose electrical conductivity can be drastically altered by the addition of small amounts of dopants. This ability to control the electrical conductivity is the key to their use in the high-speed devices used in modern optical communications systems (*see* **Semiconductor Physics:** Impurities and Defects). In ZnSe, doping with Cl produces n-type material while doping with N produces p-type material. The ability to form a pn junction (a thin region between n and p type material) is the precursor for the production of optical devices such as light-emitting diodes (LEDs) or laser diodes (LDs) based on II–VI semiconductors. Doping also changes the optical properties of II–VI materials.

All materials are defective to some degree, and these II–VI materials are no exception. The number and type of defects are determined by thermodynamic and purity considerations during the growth process. There are native defects such as vacancies (missing atoms) and dislocations (extra or missing layers of atoms). There are also impurities present; foreign atoms due to the impurities in the starting growth materials. These impurities have an important effect on the ability of the material to emit light. Dopants and impurities may help to increase the amount of light emitted while dislocations usually reduce the emission efficiency in II–VI materials.

Optical Properties of II–VI Semiconductors: Basic Concepts

Introduction

When light is incident on a solid material, its electric field interacts with the electric field within the atoms comprising the solid. This interaction leads to a

Table 1 Structural, thermodynamic and optical properties of II–VI compound semiconductors

Material	*Lattice constant (Å)*	*Crystal structure*	*Melting point (mp) (°C)*	*Vapor pressure at mp (atm)*	*Refractive index*	*Bandgap (0 K)*	*Bandgap (300 K)*
ZnO	*a* 3.250 *c* 5.207	W	1975	22	2.0	3.44	3.37
ZnS	*a* 3.820 *c* 6.260	W	1718–1850	3.7	2.8	3.91	3.80
	a 5.410	Z			2.4	3.83	3.66
ZnSe	*a* 5.668	Z	1520	1.0	2.8	2.82	2.67
ZnTe	*a* 6.104	Z	1300	0.6	3.1	2.39	2.25
CdS	*a* 4.133 *c* 6.710	W	1405–1475	3.8	2.5	2.58	2.42
	a 5.832	Z			–	–	–
CdSe	*a* 4.299 *c* 7.015	W	1239–1264	0.4	2.6	1.84	1.74
	a 6.057	Z			–	1.77	–
CdTe	*a* 6.477	Z	–	–	2.75	1.60	1.49
MgS	*a* 5.89	Z	–	–	2.6	–	4.5
MgSe	*a* 5.62	Z	–	–	2.6	–	3.6
BeTe	*a* 5.627	Z	–	–	–	–	2.8

Data taken from many sources mentioned in the bibliography but primarily from Bhargava, R. (1997) (ed.) *Wide Bandgap II–VI Semiconductors*, The Institute of Electrical Engineers, London, Table 1 of Chapter 5.4 with permission.



Figure 2 ZnSe single crystal grown by vapor transport. Photograph courtesy of NASA.

number of effects that we can observe. The light will be reflected or scattered from the surface of the solid, depending on whether the surface is smooth or rough on a length-scale similar to the wavelength of light. The materials of interest here are high-quality crystals with a smooth reflective surface. When light enters a material, it is refracted, i.e., it changes direction within the material. The simplest example of this is when a stick is placed in a jug of water, it appears to be bent. It is of course the light that is bent due to its different interaction with the air and with water. Snell's law states that:

$$\frac{\sin \alpha_i}{\sin \alpha_{tr}} = n \qquad [1]$$

where α_i is the angle of incidence of the light and α_{tr} is the angle of refraction. n is known as the refractive index of the material and is characteristic of it. As well as being refracted, any light that enters the crystal is either absorbed within the material or transmitted through the material to emerge on the other side. If the light is absorbed the material will look colored if the absorption takes place in the visible region where our eyes are sensitive. The ZnSe crystal in Figure 2 is such a material; the orange color is due to the absorption of blue light from the white light shining on the material. Other materials look transparent; ZnO is such an example. Following absorption, some materials produce light of their own; the color of the light is characteristic of the material and this process is termed luminescence. Light may also be scattered within a crystal by imperfections and by vibrations of the atoms in the crystal.

When light enters a solid material, the electric field polarizes the atoms within the structure. The positive and negative charges within the atoms move slightly from the equilibrium positions. All of the optical effects mentioned above are related to the induced polarization. As the constituent atoms in the structure are unique, the induced polarization and the resulting optical properties are specific to particular materials, and this makes optical characterization a very important tool for the investigation of semiconductor materials.

Reflection at the Air-to-Material Interface

Our experience of looking at reflection from glass tells us that these are weakly reflecting materials; the same is true of single crystal II–VI materials such as that in Figure 2. The interface between air and an optical material is a fundamental aspect of optical physics. The amount of light reflected can be determined from Maxwell's equations. The simplest equation is found where light is incident perpendicular to the surface of the material:

$$R = \frac{(n-1)^2}{(n+1)^2} \qquad [2]$$

where R is the reflection coefficient and n is the refractive index of the material. The value of n is characteristic of the particular material. Values of n for several II–VI materials are given in Table 1. The refractive index n for all these II–VI materials is not constant but varies slowly with the wavelength of the light impinging on the material. In Figure 3, we show the wavelength dependence of the refractive index of ZnSe.

Transmission and Absorption of Light within II–VI Materials

Once the light has passed through the interface with the air, it can either be transmitted through the material to emerge on the other side at a second material–air interface or be gradually absorbed within the body of the material. The ZnSe sample in Figure 2 is illuminated with white light, but it appears orange in color to our eyes, i.e., the orange component within the white light is transmitted through the material to our eye. The other components in the light, mostly green and blue, are absorbed within the material. To obtain more quantitative information, we take a spectrum of the absorption within the material. We illuminate the sample with light of different wavelengths and determine how much is transmitted or absorbed at each wavelength. The transmission spectrum of ZnSe is shown in Figure 4.

The visible spectral region extends from 0.4 to 0.7 microns and we see that there is a large change in transmission around 0.5 microns that is responsible for the color of the ZnSe crystal as seen in Figure 2. This spectral region around the onset of a large reduction in transmission at 0.5 microns is termed the bandgap of the material. As in the case of the refractive index, the value is unique to the material. II–VI materials are termed wide bandgap materials as they possess larger values of the bandgap energy than for Si, Ge and the III–V semiconductor materials. If we shine light of wavelength 0.5 microns onto ZnSe material, the transmission is very low. Under these conditions, the material would look black to our eyes. Once the light has been



Figure 3 Refractive index n of ZnSe versus wavelength and photon energy at $T = 300\,K$. Adapted from Madelung E (ed.) (1982) *Numerical Data and Functional Relationships in Science and Technology, New Series, Group III: Crystal and Solid State Physics, vol. 17b: Physics of II–VI and II–VII Compounds, Semimagnetic Semiconductors*, Berlin: Springer-Verlag, Figure 52, with permission.



Figure 4 ZnSe transmission spectrum versus wavelength. Courtesy of II–VI Incorporated.



Figure 5 A seven-segment II–VI LED with blue emission taken at room temperature. Reproduced with permission from Hagerott M, Jeon H, Nurmikko AV, *et al.* (1992) Indium tin oxide as transparent electrode material for ZnSe-based blue quantum well light emitters. *Applied Physics Letters* 60: 2825–2827.

absorbed by the II–VI semiconductor, it can in turn produce light of its own. This light, known as luminescence, is again characteristic of the particular material and is the basis for the use of such materials in light-emitting diodes (LEDs) and laser diodes (LDs). In Figure 5 we show the luminescence from a II–VI LED. We see also from Figure 4 that at very long wavelengths, the ZnSe material also exhibits a large reduction in light transmission. This spectral region is termed the far infrared and the light absorbed at this spectral region produces vibrations of the atoms within the material, referred to as lattice absorption.

Light Scattering

Within the bulk of the material, small areas may have a different arrangement of atoms or may contain a substantial number of foreign atoms known as impurities. A large grouping of these impurities is known as an inclusion. In these regions, the optical properties will be different from the bulk of the material. Differences in both absorption coefficients and refractive indices can be found. These different refractive indices cause the light passing through the material to be scattered. Poor-quality material will often contain many inclusions. Even to the eye, these crystals will not look highly transparent. Changes in the refractive indices can also occur in highly pure materials due to vibrations of the atoms in the crystals. The lattice vibrations change the distance between the atoms in the material which alters the electric fields within the material and thereby changes the optical properties. Light can also be scattered due to these vibrations; experimental measurements of light scattering can provide useful information on the vibrations in these materials.

Optical Properties of II–VI Semiconductors: More Advanced Concepts

Light–Semiconductor Interactions

Light is an oscillating electromagnetic field whose interaction with semiconductor materials is in terms of the complex dielectric constant $\varepsilon_c = n_c^2$ where n_c is the complex refractive index defined as $n_c = n - ik$. k is known as the extinction coefficient and the value of k determines the amount of absorption in a material. The optical processes of reflection and absorption in semiconductors are governed by this complex dielectric constant. It turns out that there is a strong relationship between these processes. If the absorption spectrum is determined at all frequencies, then we can determine the refractive index spectrum at all frequencies by what is known as the Kramers–Kronig relations. From this description, we can now refine eqn [2] presented above:

$$R = \frac{(n-1)^2 + k^2}{(n+1)^2 + k^2} \qquad [3]$$

If the material is transparent at a particular wavelength, then $k = 0$ and we can determine the refractive index n. This is the case for values given in the table. The technique of spectroscopic ellipsometry can be used to determine the optical response of materials over a large wavelength range. This technique relies upon the change from linear polarization to elliptical polarization for light reflected from a material. From these measurements, the dielectric response can be determined.

If we look again at Figure 3, we see that there is a strong change in sample transmission around 0.5 μm. This corresponds to an energy of 2.18 eV and is the bandgap energy of ZnSe. According to the details presented above, transitions are now being made from the full valence to the empty conduction bands of the semiconductor material. Once we have exceeded the bandgap energy, we can make further transitions between the bands. The spectrum shown in the figure is a broad band, reflecting the change from sharp atomic transitions to broad transitions in the solid state. Light with a wavelength greater than 0.5 μm does not have sufficient energy to effect the transitions between the bands. These wavelengths are not absorbed in the material. The material is transparent and the value of the extinction coefficient k is zero. The orange color of the crystal in Figure 2 corresponds to this transparent spectral region.

Cooling samples to low temperatures close to absolute zero has a profound effect on the optical properties of materials, particularly the absorption spectrum. In Figure 6, we show the absorption spectrum of a ZnSe sample at a temperature of 2 K. The absorption spectrum is determined from the measured transmission by the following equation

$$\alpha = \frac{1}{L}\ln\frac{I_0}{I_t} \qquad [4]$$

where α is the absorption coefficient, L the length of the sample, I_0 the light intensity incident on the sample and I_t the light intensity transmitted through the sample. In addition to the broad band spectrum there are now a number of sharp spectral lines near the bandgap energy.



Figure 6 Low-temperature optical absorption spectrum of a ZnSe layer showing the 1S and 2S exciton features, the 1S + 1LO-phonon transition and the split-off (SO) exciton. Reproduced with permission from Bhargava R (ed.) (1997) *Wide Bandgap II–VI Semiconductors*, The Institute of Electrical Engineers: London, Figure 2 of Chapter 4.1.

These lines are due to exciton formation. An exciton is an electron–hole pair bound together by their mutual Coulomb interaction. It is the solid state equivalent of the Hydrogen atom (*see* **Semiconductor Physics:** Excitons). The bandgap energy at 2 K has increased from its value at 300 K. This is due to the thermal changes in the interatomic distance and the vibrational properties of the materials. Values of the bandgap energies determined from the position of the exciton lines in absorption spectra at low and at room temperatures are given in Table 1. At low temperatures, the luminescence is dominated by excitons, and we observe sharp line transitions. The width of the exciton transition is an excellent indicator of the quality of the material, and is often used by crystal growers to determine the quantity of defects in their materials.

It is possible for excitons and for free carriers (those that are not bound together) to recombine without giving out light. This nonradiative process usually involves the creation of local vibrations of the crystal lattice in the vicinity of defects in the material. We can define the radiative efficiency η_r as follows

$$\eta_r = \frac{R_r}{R_r + R_{nr}} \qquad [5]$$

where R_r is the radiative transition rate and R_{nr} is the nonradiative transition rate. In order to develop new optical devices based on II–VI semiconductors, it is essential that the value of R_{nr} be as small as possible. As R_{nr} is directly related to the concentration of defects in these materials, one can see why it is essential to make semiconductors with as few defects as possible. We can study these effects using a pulsed light source. Carriers are created during the pulse of light and recombine after the pulse has stopped. If we measure the luminescence intensity versus time, we can deduce the lifetime, which is given as

$$\frac{1}{\tau} = \frac{1}{\tau_r} + \frac{1}{\tau_{nr}} \qquad [6]$$

where τ_r is the radiative and τ_{nr} the nonradiative lifetime, respectively. By varying the carrier density we can separately determine the contribution to the lifetime from radiative and nonradiative effects. In II–VI materials at room temperature, lifetimes are of the order of 1 ns.

Quantum Wells, High Carrier Density Effects, and Lasers

Recent developments in the growth of semiconductor materials has allowed the production of samples with monolayer accuracy (3–5 Å). If we grow a layered structure with materials of high bandgap on either side of a material of lower bandgap, we can observe quantum mechanical effects. These materials are called quantum wells (*see* **Semiconductor Physics:** Quantum Wells and GaAs-Based Structures). As an example, a 75 Å ZnSe quantum well can be grown between layers of ZnSSe. Due to the small size of the active material, quantum mechanical effects come into play, most notably an increase in the bandgap energy as the width of the quantum well decreases. The effect of placing this material between ZnSSe layers that have a larger bandgap is to confine the electrons and holes to the small region of the well. In this small region, they are less likely to encounter defects and so quantum well materials usually have a higher radiative efficiency than bulk II–VI materials which are grown by standard techniques. In Figure 7, we show the exciton absorption and luminescence from a ZnSe quantum well at low temperature.

If we increase the excitation level in these materials, we can eventually cause them to operate as lasers. At high carrier densities, nonradiative transitions become saturated and radiative efficiency increases. As the refractive indices in II–VI materials are quite large, the reflectivity of the two ends of the sample are usually sufficient to act as the mirrors for the laser cavity. All the II–VI semiconductor materials have exhibited laser action due to their direct bandgap. Most of the early studies of lasing were carried out at low temperature. In recent times, lasing action has been observed at room temperature in CdZnSe quantum well materials and there are attempts at present to develop commercial II–VI lasers for use in optical storage devices and flat panel displays. In Figure 8 we show the transition from luminescence through gain and into lasing action for a CdZnSe quantum well material.



Figure 7 (a) Absorption and (b) luminescence from a single ZnSe quantum well at $T = 10\,\mathrm{K}$ in the vicinity of the $n = 1$ quantum well exciton transition. Reprinted from Nurmikko AV, Jeon H, Gunshor RL and Han J (1996) II–VI lasers – directions. *Journal of Crystal Growth*, 159: 644–651 with permission from Excerpta Media Inc.



Figure 8 Emission spectra above and below lasing for a 40 Å $Cd_{0.28}/Zn_{0.72}Se/ZnSe$ system at room temperature. 100% corresponds to 1.1 times lasing threshold. Reprinted from Donegan JF, Jordan C, Rees P, Logue F, Heffernan JF and Hegarty J (1996) A study of internal loss in CdZnSe/ZnSe multiple quantum well materials. *Journal of Crystal Growth*, 159: 653–656 with permission from Excerpta Media Inc.

Dopants and Impurities

The key to the large-scale use of semiconductor materials is the large change in the electrical conductivity of the materials with the incorporation of small amounts of other elements. This process is known as doping and the foreign elements are known as dopants. The recent development of II–VI laser diodes in ZnSe materials is based on the p-n diode junction. Electrons injected into the n-type material recombine with holes injected into the p-type material at the junction between these two materials. A particular type of luminescence transition unique to semiconductor materials is the donor–acceptor pair (DAP) recombination. As donor and acceptor atoms are located in specific crystalline sites with respect to one another, we observe that the recombination energy is dependent on separation. Pairs that are close together often exhibit sharp lines while those far apart merge into a broad band. In Figure 9 we show the DAP recombination in ZnSe at 1.6 K.

It is also possible to incorporate foreign atoms in II–VI materials that have a small effect on the electrical properties but significantly change the optical properties. Such foreign atoms are termed impurities to distinguish them from dopants. An example is Mn^{2+} in ZnS. The Mn ions take the place of a small number of Zn atoms in the lattice. The luminescence from such a material is a broad emission in the visible region due to optical transitions on the Mn ions. ZnS:Mn materials are used as phosphors in flat-panel displays.



Figure 9 DAP recombination spectra of In-Li pairs in ZnSe showing pair lines, pair band (Q_0) and LO-phonon replicas (Q_1 and Q_2) at two different intensities (a) and (b). Adapted with permission from Merz JL, Nassan K and Shiever JW (1973) Pair spectra and the shallow acceptors in ZnSe. *Physical Review B* 8: 1444–1452.

Effects of Temperature, Pressure, Electric, and Magnetic Fields

The optical properties of II–VI materials are subject to variation due to temperature changes, external pressure and fields. Increasing temperature is found to lead to a decrease in the bandgap of II–VI materials. This decrease is due to the combined effects of an increase in the lattice spacing with temperature and the electron–phonon interaction. As the population of phonons is temperature dependent, this effect increases strongly as temperature increases and is the major contributor to the change in bandgap with temperature. A second effect of increasing the temperature is the change in the luminescence properties. In particular, it is found that the luminescence efficiency decreases and this is reflected in a reduced luminescence lifetime at room temperature compared with low-temperature values. Looking again at eqn [6], it is the nonradiative lifetime that changes rapidly with temperature and results in the decrease in the luminescence efficiency.

Pressure changes may be hydrostatic or uniaxial. In the hydrostatic case, the atoms are all brought closer together, and for the II–VI materials, this results in an increase in the bandgap energy. On the other hand, a uniaxial stress results in a decrease in the bandgap in the direction of the stress and an increase in the transverse directions. In II–VI materials with a wurtzite structure, the situation is more complex with two longitudinal and four transverse deformations possible.

External electric and magnetic fields can also be applied to II–VI semiconductors and thereby the optical properties can be changed. Electric fields polarize the materials and can lead to a reduction in the optical strength of transitions due to this polarization-induced carrier separation. Magnetic fields, on the other hand, lead to a splitting of the conduction and valence bands into Landau levels due to the circular motion of the carriers around the direction of the field.

See also

Semiconductor Physics: Band Structure and Optical Properties; Excitons; Impurities and Defects; Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures.

Further Reading

Adachi S and Taguchi T (1991) Optical Properties of ZnSe. *Physical Review B* 43: 9569–9577.

Bhargava R (ed.) (1997) *Wide Bandgap II-VI Semiconductors*. London: Institute of Electrical Engineers.

Madelung E (ed.) (1982) *Numerical Data and Functional Relationships in Science and Technology, New Series, Group III: Crystal and Solid State Physics, vol. 17b: Physics of II-VI and I-VII Compounds, Semimagnetic Semiconductors*. Berlin: Springer-Verlag.

Madelung E (ed.) (1987) *Numerical Data and Functional Relationships in Science and Technology, New Series, Group III: Crystal and Solid State Physics, vol. 22a: Intrinsic Properties of Group IV Elements and III-V, II-VI and I-VII Compounds*. Berlin: Springer-Verlag.

Mar H (1992) Optical properties of wide bandgap II-VI semiconductors. In: Ruda HE (ed.) *Widegap II-VI Compounds for Opto-electronic Applications*, pp. 167–188. London: Chapman and Hall.

Nurmikko AV and Gunshor RL (1993) Physics and application of II-VI quantum confined structures. In: Henneberger F, Schmitt-Rink S and Göbel EO (eds) *Optics of Semiconductor Nanostructures*, pp. 229–262. Berlin: Akademie Verlag.

Pankove J (1975) *Optical Processes in Semiconductors*, 1st edn. New York: Dover Publications.

Stanley RP and Hegarty J (1993) Physics of excitons in wide bandgap II-VI quantum wells. In: Henneberger F, Schmitt-Rink S and Göbel EO (eds) *Optics of Semiconductor Nanostructures*, pp. 263–290. Berlin: Akademie Verlag.

Yu PY and Cadona M (1996) *Fundamentals of Semiconductors*. Berlin: Springer Verlag.

II–VI Compounds 1999. Ninth International Conference. Elsevier, Netherlands. *Journal of Crystal Growth* vol. 214–215, 2000.

II–VI Compounds 1997. Eighth International Conference. Elsevier, Netherlands. *Journal of Crystal Growth* vol. 184–185, 1998.

II–VI Compounds 1995. Seventh International Conference. Elsevier, Netherlands. *Journal of Crystal Growth* vol. 159, 1996.

Lead Salts

G Bauer and G Springholz, Johannes Kepler Universität, Linz, Austria

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The binary IV–VI compounds formed from Pb and group-VI elements like S, Se, and Te are among the oldest known semiconducting materials, and have been used for many years for electronic and optoelectronic device applications. The first ever reported solid state diode was made from single crystalline PbS and its rectifying properties were exploited in early radio receivers. Later on, interest in IV–VI semiconductors shifted to mid-infrared opto-electronic device applications such as photon detectors operating in the 3–14 μm wavelength range, taking advantage of the narrow energy gap between the valence and conduction band of the IV–VI compounds. Soon after the demonstration of lasing in III–V semiconductor diode structures, the first mid-infrared p-n junction laser was reported using $Pb_{1-x}Sn_xTe$, and since then efficient mid- and far-infrared IV–VI compound diode lasers have been fabricated, finding their main applications for remote sensing of gaseous pollutants in trace gas sensing devices, for toxic gas analysis systems, for human breath analysis in medical diagnostics, and for fabrication process control. Recently, IV–VI multiquantum-well structures have also attracted a lot of attention for their potential as efficient thermoelectric devices.

Basic Properties

In lead salt compounds, both the valence band maximum and the conduction band minimum occur at the L-points of the Brillouin zone. Thus these many-valley semiconductors have a direct gap, but not in the center of the Brillouin zone. In addition the small values of the energy gaps ($E_g < 410$ meV at $T = 300$ K) lead to a strong $\mathbf{k} \cdot \mathbf{p}$ interaction which in turn results in a strong nonparabolicity of the $E(k)$ dispersion relations. The small energy gaps also lead to small effective masses of electrons and holes, and the strong spin–orbit interaction (Pb is a very heavy element) leads to large values of the g-factors.

The bandgaps of the lead compounds have a positive temperature coefficient ($\mathrm{d}E_g/\mathrm{d}T > 0$) and a negative pressure coefficient ($\mathrm{d}E_g/\mathrm{d}p < 0$), i.e., the gaps increase with temperature and decrease with hydrostatic pressure. These anomalous properties are related to peculiarities of the band structure, among them the fact that in the lead compounds the Pb 6s levels are below the top of the valence band, and thus are occupied, in contrast to the group IV, III–V and II–VI compounds.

Almost all optical device applications of the IV–VI semiconductors are based on the materials subgroup of cubic lead chalcogenides PbTe, PbSe, and PbS, and their quasibinary alloys with other chalcogenide such as compounds, like PbSnTe, PbSnSe, or ternary alloys like PbEuTe, PbSrTe, PbEuSe, PbSrSe, etc. These compounds all crystallize in the rocksalt structure with sixfold coordination and lattice constants in the 5.9 to 6.5 Å range. Mechanically, the lead salt compounds are much softer than the tetrahedrally bonded semiconductors, which has significant implications for device fabrication processes.

A further unusual property of the lead compounds is their huge static dielectric constant ε_0. In particular PbTe is close to a structural phase transition from the NaCl structure to a rhombohedral modification with ferroelectric properties. GeTe and SnTe are indeed ferroelectric with Curie temperatures of about 700 K and 145 K respectively, and also PbGeTe and PbSnTe become ferroelectric when the Ge or Sn content exceeds 1% or 20%, respectively. PbTe exhibits a softening of the transverse optic phonon mode with decreasing temperature. Although PbTe remains cubic, the temperature dependence of the static dielectric constant $\varepsilon_0 \propto C/(T-\theta)$ can be associated with an extrapolated negative Curie temperature θ of -75 K. As a consequence, the static dielectric constant increases strongly with decreasing temperature, reaching a value of $\varepsilon_0 = 1350$ at 4 K. This is the reason for the strong increase of the static dielectric constant at low temperatures as shown in Table 1, in which important properties of PbTe, PbSe, and PbS are summarized.

Also, the high-frequency dielectric constants ε_∞ of the lead salts are extremely high, which leads to refractive indices of about 4.4 for PbS, to 5.0 for PbSe and to about 6.0 for PbTe at $T = 300$ K, for photon energies just below the respective energy gaps.

As a result of the huge static dielectric constants, the hydrogen-like impurity binding energies are in the range of μeV, and the carrier scattering at ionized impurities is effectively screened. Consequently, the low-temperature carrier mobilities are high, exceeding 10^6 cm^2/Vs in PbTe. For doping of the lead salts two alternative methods are used, namely (1) adjustment of the stoichiometry of the compounds, or (2) doping with various kinds of impurities. Because the electronic states of these vacancies are resonant within the conduction or valence bands, each metal (Pb or Sn) vacancy acts as a doubly charged acceptor, and each chalcogen (Te, Se, or S) vacancy acts as a doubly charged donor. As a result, background doping levels below 10^{17} cm^{-3} are difficult. For doping with impurities, atoms from group IIIa (In, Ga, Tl), group Va (As, Sb, Bi), as well as group Ib elements (Cu, Ag) are used. These dopants are amphoteric p- or n-type, depending on whether they are incorporated substitutionally on metal or chalcogen lattice sites.

Table 1 Physical properties of some of binary IV–VI semiconductors

Parameter	*PbTe*	*PbSe*	*PbS*
Lattice constant a_0 (Å)	6.462	6.124	5.936
Melting point (°C)	930	1080	1113
Energy gap E_g			
at 300 K (meV)	319	278	410
at 77 K (meV)	217	176	307
at 4 K (meV)	190	147	286
Static dielectric constant ε_0			
at 300 K	414	210	169
at 77 K	1000	227	181
at 4 K	1350	280	–
High-frequency dielectric constant ε_∞	34	21	17
TO phonon mode frequency	18 (4 K) 33 (300 K)	37	65

Table 2 Expansion coefficients (10^{-6} K^{-1})

Compound	*Expansion coefficient*
PbS	20.3
PbSe	19.4
PbTe	19.8
GaAs	6
Si	2.6
BaF$_2$	18.8

Other important aspects of the lead salts are their rather large linear thermal expansion coefficients of around 20×10^{-6} K^{-1} which are about a factor of three larger than that of GaAs, and six times larger than that of Si as shown in Table 2. The thermal conductivity is much lower than that of other semiconductors, which is favorable for their use in thermoelectric devices but causes problems in the removal of the dissipated heat in IV–VI compound diode lasers.

Band Structure

A main property of the electronic band structure of the lead salt compounds is the small and direct energy gap of less than 410 meV (see Table 1). Since the maxima of the valence band and the minima of the conduction band are located at the same wavevector in reciprocal space, optical photons can be directly absorbed or emitted at the band edges. This makes the lead salts very well suited for opto-electronic applications such as infrared photon detectors or emitters. The band extrema are located at the edges in the <111> direction of the Brillouin zone (L-points). In contrast to most other semiconductors, the conduction and valence bands are nearly mirror symmetric with almost equal effective masses for the electrons and holes. Because of the narrow energy gaps, the energy bands are strongly nonparabolic and the effective masses of electrons as well as holes are rather small (0.02–0.08 m_0 for the transverse masses,

Table 3 Band edge values of effective masses (in units of m_0) and g-factors (absolute values), $T = 2$ K

Parameter	*PbTe*	*PbSe*	*PbS*
m_t^{CB}	0.0207	0.037	0.081
m_l^{CB}	0.0213	0.0687	0.108
m_t^{VB}	0.0241	0.036	0.076
m_l^{VB}	0.263	0.066	0.108
g_t^{CB}	16.7	32.5	–
g_l^{CB}	66.1	44.1	12
g_t^{VB}	13.5	30.6	–
g_l^{VB}	65.6	–	13

Table 4 Pressure and temperature coefficients of the energy gaps

	PbTe	*PbSe*	*PbS*
dE_g/dp(eV Pa^{-1})	-7.5×10^{-11}	-9.1×10^{-11}	-9.1×10^{-11}
dE_g/dT (meV K^{-1})	0.457	0.457	0.462

see Table 3). In addition, the bands are anisotropic, i.e., the Fermi surfaces are elongated ellipsoids of revolution around the $<111>$ axes, characterized by a longitudinal and transverse effective mass m_l and m_t parallel and perpendicular to the four-fold $<111>$ directions.

For PbTe the effective mass anisotropy is very large with a ratio of about 10 between longitudinal and transverse masses, whereas for PbSe and PbS this ratio is only 1.8 and 1.2, respectively (Table 2). Furthermore, in the alloy system $PbSe_{1-x}Te_x$ the energy gap shows a bowing, but not with a minimum value but rather a maximum gap for x at about 0.7. This is in contrast to the behavior found in direct-gap zincblende semiconductors: the bandgap $E_g(x)$ of an $A_{1-x}B_x$ alloy can generally be represented by $E_g(x) = (1-x)E_g(A) + xE_g(B) - bx(1-x)$ where b denotes the bowing coefficient. For III–V and II–VI compounds $b > 0$; whereas, for PbSeTe alloys $b < 0$.

Apart from the above-mentioned negative pressure coefficients of the direct gaps and their positive temperature coefficient which are tabulated in Table 4, there is a further intriguing anomaly in the chemical trends of the fundamental gap at the L-points: it decreases from PbS to PbSe, but increases from PbSe to PbTe, i.e., the direct gaps do not decrease monotonically with increasing atomic number of the anions. This decrease of the energy bandgap with decreasing temperature is substantial: i.e. it decreases from room temperature to 4 K by about 130 meV (see Table 1). This represents a large relative change with respect to the absolute value of the bandgap, and thus the emission of lead salt based diode lasers can be tuned over a broad wavelength range just by changing the operation temperature. This effect is actually utilized for spectroscopic applications of these lasers.



Figure 1 Energy bandgap versus lattice constant for several IV–VI compounds and alloys.

For adjustment of the fundamental absorption edge of infrared detectors as well as the adjustment of the wavelength emission of lead salt diode lasers, alloying of the lead salt compounds with other chalcogenide compounds is used. As illustrated in Figure 1, for this purpose many different ternary and quaternary alloys have been used. Important alloy systems for far-infrared applications are the lead–tin chalcogenide alloys. The tin chalcogenides (SnS, SnSe, SnTe) form single-phase pseudobinary alloy systems with the lead salts for all compositions. They have similar band structures as compared to the lead salt compounds; however, the arrangement of valence and conduction bands is exchanged. As a result, with increasing Sn content the energy bandgap of the ternary lead–tin chalcogenide alloys decreases and a zero bandgap semiconductor is reached for a certain ternary composition. For an operation temperature of 77 K, the bandgap is zero for a Sn content of $x_{Sn} \sim 40\%$ in the case of $Pb_{1-x}Sn_xTe$, and of $x_{Sn} \sim 20\%$ in the $Pb_{1-x}Sn_xSe$ case.

Optical Properties

The strong fundamental absorption in the lead salt compounds reflects the particularly high joint density of states at the direct gap at the L-points of the Brillouin zone. The main advantage of the lead compounds with respect to other direct narrow-gap semiconductors like InSb, or HgCdTe alloys, with band extremes at the center, i.e., the Γ-point of the Brillouin zone, is related to the differences in the effective masses. Whereas the transverse effective masses of the IV–VI compounds have comparable values to the effective masses of the narrow-gap III–V and II–VI compounds, the longitudinal effective masses of the lead compounds are much larger. Thus the mass anisotropy together with the fourfold valley degeneracy at the L-point of the Brillouin zone leads to the substantially higher joint density of states and corresponding large absorption constants. Due to the rapid change of $\alpha(\omega)$ in the fundamental absorption range, a peak appears in the refractive index, $n(\omega)$, as shown in Figure 2 for PbTe, PbSe and for PbS. The shift of the peak with increasing temperature to higher photon energies reflects the increasing energy gaps.

In two-dimensional structures the changes of the absorption constant with frequency are particularly steep for energies which correspond to the onset of absorption between quantum confined electric subbands in the valence and conduction band. Such step-like features have indeed been observed in the absorption of PbTe/PbEuTe multiquantum-well (MQW) structures by Yuan *et al.* In Figure 3 the absorption constants and refractive indices are shown for a series of three MQW samples with different PbTe well widths. The steps in the absorption coefficients for the interband transitions associated to the longitudinal valleys with their main axis parallel to the [111] growth direction, denoted by 'l' as well as those associated by the oblique valleys, denoted by 'o' are accompanied by corresponding cusp-like enhancements of the refractive index. These cusps are of importance for the proper design of MQW laser structures.



Figure 2 Refractive indices of PbTe, PbSe, and PbS as a function of photon energy at 77, 300, and 373 K. Reproduced with permission from Zemel JN, Jensen JD and Schoolar RB (1965) Electrical and optical properties of epitaxial films of PbS, PbSe, PbTe and SnTe. *Physical Review* 140: A330–A337. Copyright 1965, American Physical Society.

Because of the extremely high values of the refractive indices, the lead salts can easily be combined with materials of much lower refractive indices like EuTe, EuSe, or BaF_2 for efficient multilayer Bragg mirror structures. The high reflectivity of Bragg mirrors is caused by constructive interference of electromagnetic waves reflected at the subsequent interfaces of a multilayer structure. To obtain constructive interference, all interfaces have to be parallel, and, depending on the refractive indices of the media inside the Bragg mirror, the distance between subsequent interfaces should be an even or odd multiple of one quarter of the optical wavelength λ. In practice, stacks of two alternating layers with different refractive indices n_1 and n_2 and with a thickness equal to a quarter optical wavelength are used.

If for these $\lambda/4$ layers $Pb_{0.93}Eu_{0.07}Te$ and EuTe are used, a high index contrast of 68% is obtained and therefore very high reflectivities can be achieved already by a very small number of layer pairs. It was shown that a Bragg mirror with 3.5 periods of EuTe/$Pb_{0.93}Eu_{0.07}Te$ layer pairs for a target wavelength of 3.8 μm has only a total thickness as small as 2.55 μm. For comparison with results obtained for other material combinations it is useful to relate the stop bandwidth $\Delta\lambda$ to the center wavelength λ_T of the Bragg mirror. For EuTe/$Pb_{0.93}Eu_{0.07}Te$ this relative stop bandwidth $\Delta\lambda/\lambda_T$ is as large as 50%. An even wider stop bandwidth of 59% was demonstrated for a mirror with PbTe and EuTe $\lambda/4$ layers. This value represents, to the best of our knowledge, the highest relative stop bandwidth obtained for molecular beam epitaxy (MBE) grown Bragg reflectors.

Infrared Lasers

Among the infrared diode lasers, those based on IV–VI compounds play a particularly important role. They cover a wavelength range from 2.5 μm to about 30 μm. In fact, up to now most commercially



Figure 3 Left panel: (a) transmission versus energy for a PbTe/Pb$_{1-x}$Eu$_x$Te multiquantum-well sample A (6.2 nm/62.1 nm, $x = 0.026$, 46 periods). Dots: experimental data; full line: calculation based on an envelope function model. (b) Frequency dependence of the absorption constant (full line) and of the refractive index (dotted lines). The arrows indicate interband transitions between electric sub-bands associated with valleys with main axis parallel to the [111] growth direction (l) and oblique to it (o). Right panel: (a) Comparison of the absorption constant of three PbTe/PbEuTe MQW samples (B: 9.3 nm/55.4 nm, $x = 0.03$, 30 periods; C: 11.8 nm/48.6 nm, $x = 0.024$, 30 periods). (b) Refractive index versus energy. Steps in the absorption constant due to onset of interband transitions are associated with cusps in the refractive index. Reproduced with permission from Yuan S, Springholz G, Bauer G and Kriechbaum M (1994) Electronic and optical properties of PbTe/Pb$_{1-x}$Eu$_x$Te multiple-quantum-well structures. *Physical Review B* 49: 5476–5489, Copyright 1994, American Physical Society.

available mid- and far-infrared laser diodes are made from IV–VI compounds. The main material properties which are advantageous in this respect are (i) the electronic band structure with mirror-like bands at the L-point of the Brillouin zone and the resulting high joint density of states; (ii) the lower nonradiative Auger recombination rate in IV–VI compounds as compared to III–V and II–VI materials, and (iii) the high dielectric constant and the resulting weak detrimental influence of defects on nonradiative recombination losses. At wavelengths longer than 3 μm, IV–VI interband diode lasers are superior to their III–V counterparts for reaching high operating temperatures. So far IV–VI compound lasers hold extreme high cw operating temperature at wavelengths larger than 3 μm. With PbSe/PbSrSe diode lasers pulsed operation up to 60 °C was reported, whereas cw operation up to 223 K was achieved with separate confinement buried PbTe/PbEuSeTe heterostructure laser. Embedding PbTe quantum wells as the active medium in PbEuTe barriers between two dielectric Bragg mirrors optically pumped pulsed lasing was observed up to 65 °C. The recently developed III–V based quantum cascade lasers are rapidly improving and are becoming important competitors for IV–VI lasers. The commercial IV–VI lasers, however, are still based on conventional designs like homojunction, heterojunction, or single and multiple heterojunction lasers.

A unique property of lead salt laser diodes is the ease of tuning of the emission wavelength due to the strong change of bandgap of the IV–VI materials with increasing temperature. This, together with their narrow linewidths, makes these lasers ideally suited for spectroscopic applications, including research in molecular spectroscopy of ions or radicals in heterodyne and acoustic spectroscopy, or Doppler spectroscopy of molecular beams. So far the main applications are in time resolved combustion analysis in the automotive industry, in the monitoring of emissions of power plants, in exact monitoring of gas compositions in chemical plants, and spatially and time resolved *in situ* analysis.

Apart from the significant advances with IV–VI edge emitting diode lasers, vertical cavity surface


(a)
513 nm EuTe λ/4 layer
253 nm PbEuTe λ/4 layer
PbSe quantum dots
48 nm PbEuTe spacer
2 μm PbEuTe buffer layer
513 nm EuTe λ/4 layer
253 nm PbEuTe λ/4 layer
(111) BaF2 substrate
(b) SEM
3 period top Bragg mirror
PbSe/PbEuTe dot superlattice 140 periods
10.3 μm Cavity
PbEuTe buffer
3 period bottom Bragg mirror
2 μm
(111) BaF2
(c) TEM
cross section
plan view
150 nm
100 nm

Figure 4 (a) Schematic cross-section of a PbSe quantum-dot VCSEL structure; (b) corresponding cross-sectional scanning electron micrograph; and (c) cross-sectional and plan-view transmission electron micrographs of a PbSe/PbEuTe dot superlattice sample reference sample. Reproduced with permission from Springholz G, Schwarzl T, Heiss W, *et al.* (2001) Midinfrared surface emitting PbSe/PbEuTe quantum dot lasers. *Applied Physics Letters* 79: 1225–1227. Copyright 2001, American Institute of Physics.

emitting lasers (VCSELs) have been successfully produced with optically pumped pulsed mode operation up to 50 °C. These lasers have attractive features like low-divergence circular output beam, low active volumes, and low thresholds.

High-finesse vertical cavity structures have also made it possible to realize mid-infrared surface-emitting PbSe/PbEuTe quantum dot lasers. As shown in Figure 4 in this case a self-organized PbSe/PbEuTe quantum dot superlattice was introduced into the active cavity region between Bragg mirrors consisting of three $\lambda/4$ layer pairs of 513 nm EuTe alternating with 253 nm $Pb_{0.94}Eu_{006}Te$. Optically pumped VCSEL emission at $\lambda = 4.2–3.9$ μm was achieved up to 150 K. The PbSe dots exhibit a face-centered cubic three-dimensional stacking in the superlattice. Lasing occurs simultaneously at the $m = 28^{\text{th}}$ and 29^{th} order cavity modes, which shifts with increasing temperature to the $m = 29^{\text{th}}$ and $m = 30^{\text{th}}$ mode as shown in Figure 5. This simultaneous stimulated two-mode laser operation is a result of the inhomogeneously broadened quantum-dot gain spectrum, due to PbSe dot size fluctuations.



Figure 5 PbSe dot VCSEL emission spectra at various temperatures between 1.5 and 100 K for a pump power twice the threshold, showing the switching of the laser emission to higher cavity modes as the temperature increases. The arrows and the dashed line indicate the low-energy edge of the quantum-dot gain spectrum given by $E_{g,\text{PbSe}}(T) + \Delta E_{\text{QD}}$, where $\Delta E_{\text{QD}} = 141$ meV. Reproduced with permission from Springholz G, Schwarzl T, Heiss W, *et al.* (2001) Midinfrared surface emitting PbSe/PbEuTe quantum dot lasers. *Applied Physics Letters* 79: 1225–1227. Copyright 2001, American Institute of Physics.

Infrared Detectors

The photoconductive properties of PbS and PbSe have been used for the detection of infrared radiation already since about 1930. These detectors are still mass produced either by vacuum deposition or precipitation from aqueous solution in the presence of an oxidizing agent. The polycrystalline films deposited on glass or similar substrates are usually about 1 μm thick with grain sizes of about 1 μm.

Apart from polycrystalline thin-film detectors also single crystalline films have been used for infrared detection. In particular, the photoconductive response of a sequence of n- and p-doped PbTe multilayers (so-called nipi structures) was shown to come close to that for the theoretical limit for the detectivity D^* of an ideal photodetector at temperatures between 77 and 90 K. Recently, lead selenide detectors have been used in advanced focal plane array (FPA) detectors and are commercially available as linear or bilinear FPAs with up to 526 detector elements. These elements are coupled to CMOS multiplexer readout circuits. The PbSe detector elements are thermoelectrically cooled, with entire power requirement for the FPAs and the cooler of less than 5 W. These structures are a low-cost alternative to the more elaborate FPAs based on HgCdTe technology.

The importance of thermal imaging by using focal plane arrays of many detector elements has recently stimulated further work with IV–VI epitaxial layers. In particular, the possibility of using Si substrates, as first shown by Zogg *et al.*, has brought a new impetus to the field of IV–VI infrared devices. With the use of Si wafers it is possible to integrate the detector of an infrared camera which consists of thousands of pixels to the read-out electronics which is usually based on standard silicon CMOS devices. In this case, the active lead salt infrared detector elements are grown by molecular beam epitaxy on CaF_2/BaF_2 buffer layers deposited on the Si (111) substrates after the fabrication of the electronic circuitry for the read-out. Conventional HgCdTe focal plane technology relies on hybrid structures with In bump bonds between the infrared devices and the Si substrate for each of the pixels. Due to the rather high dielectric constants of the IV–VI compounds as compared to HgCdTe, the high-frequency operation of IV–VI detector structures is limited to about 100 MHz. This upper frequency limit is, however, sufficient for infrared focal plane arrays. With IV–VI active epilayer thicknesses of few μm internal quantum efficiencies close to 100% and external efficiencies of about 60% have been achieved. Using materials like PbS, PbTe, PbEuSe, PbEuTe, or PbSnSe, the cutoff wavelength of the detector array can be varied from 4 to 14 μm at $T = 77$ K. The sensitivity of these detector structures is limited by generation-recombination noise for $T < 100$ K, whereas for higher temperatures these sensors are diffusion limited. The variation of quantum efficiencies between different pixels was shown to be less than about 3% for a 256 pixel device. Since all growth steps for these infrared sensors are performed at temperatures below 450 °C, a processing compatibility exists with standard Si-VLSI technology.

Summary

The peculiar structural, electronic, and optical properties of IV–VI semiconductors as compared to other semiconductor materials are a consequence of the ten valence electrons per atomic pair instead of the eight valence electrons typical for the tetrahedrally bonded group IV, III–V, and II–VI semiconductors. The most important group of IV–VI materials is the so-called lead chalcogenide (lead salt) compounds and their ternary and quaternary alloys. Their electronic band structure with the narrow direct minimum gap not at the center but at the edges of the Brillouin zone (L-points) exhibits a number of unique properties. The minimum energy gap increases with increasing temperature and decreases with hydrostatic pressure. The refractive indices are particularly large. As compared to narrow-gap III–V or II–VI semiconductors the Auger recombination rates are by two orders of magnitude smaller. All these properties provide the lead salts with great advantages for achieving infrared p-n junction lasing operation at comparatively high temperatures. Furthermore, efficient microcavity designs with extremely high reflectivities of 99% were realized with only three layer periods of combination like $PbSrTe/BaF_2$ or PbEuTe/EuTe due to their extremely high refractive index contrast. Further applications of the lead compounds are high sensitive infrared detectors, including focal plane array detectors which can be fabricated with comparatively low cost technologies, as well as thermoelectric devices.

List of Units and Nomenclature

Absorption *constant*	α
Absorption index	κ
Composition	x
Damping parameter	Γ_D
Detectivity	D^*
Dielectric function	ε
Energy	E
Energy gap	E_g
Free electron mass	m_0
High frequency dielectric constant	ε_∞
Kramers Kronig relations	KKR
Longitudinal effective mass	m_l
Longitudinal g-factor	g_l
Pressure	p
Refractive index	n
Static dielectric constant	ε_0
Temperature	T
Transverse effective mass	m_t
Transverse g-factor	g_t

See also

Nonlinear Optics, Basics: Kramers–Krönig Relations in Nonlinear Optics.

Further Reading

Bauer G (1980) Magnetooptical properties of IV–VI compounds. In: Zawadzki W (ed.) *Narrow Gap Semiconductors Physics and Applications*, pp. 470–494. Berlin: Springer Verlag.

Bauer G and Krenn H (1985) Lead selenide, lead telluride. In: Palik ED (ed.) *Handbook of Optical Constants*, pp. 517–523 and 535–546. New York: Academic Press.

Felix CL, Bewley WW, Vurgaftman I, *et al.* (2001) Low-threshold optically pumped $\lambda = 4.4\ \mu m$ vertical cavity surface emitting laser with a PbS quantum well active region. *Applied Physics Letters* 78: 3770–3772.

Holloway G (1980) Thin film IV–VI semiconductor photodiodes. In: Hass G and Francombe MF (eds) *Physics of Thin Films*, vol. 11, pp. 105–203. New York: Academic Press.

Jantsch W (1983) Dielectric properties and soft modes in semiconducting (PbSnGe)Te. *Springer Tracts in Modern Physics* 99: 1–50.

Katzir A, Rosman R, Shani Y, *et al.* (1989) Tuneable lead salt lasers. In: Cheo PK (ed.) *Handbook of Solid State Lasers*, pp. 227–347. New York: Marcel Dekker.

Khoklov D (2003) Lead chalcogenioles: Physics and applications. In: Manasreh MO (ed.) *Optoelectronic Properties of Semiconductors and Superlattices*, vol. 18. New York: Taylor and Francis.

Lucovsky G, Martin RM and Burstein E (1974) Structure, bonding and lattice dynamical properties of the IV–VI compounds. In: Rabii S (ed.) *Physics of IV–VI Compounds and Alloys*, pp. 93–102. New York: Gordon and Breach.

Nimtz G (1993) IV–VI compounds. In: Hellwege K and Madelung O (eds) *Numerical Data and Functional Relationships in Science and Technology.* Landolt-Börnstein, new series, group III, vol. 17, Part F, pp. 152–180. Berlin: Springer Verlag.

Partin DL and Heremans J (1994) Growth of narrow bandgap semiconductors. In: Moss TS and Mahajan S (eds) *Handbook on Semiconductors*, vol. 3A, pp. 369–450. Amsterdam: North-Holland.

Preier H (1990) Physics and applications of IV–VI compound semiconductor lasers. *Semiconductor Science and Technology* 5: S12–S20.

Ravich YI, Efimova BA and Smirnov IA (1970) Semiconducting Lead Chalcogenides. New York: Plenum.

Schwarzl T, Heiss W and Springholz G (1999) Ultra-high-finesse IV–VI microcavities for the midinfared. *Applied Physics Letters* 75: 1246–1248.

Springholz G, Shi Z and Zogg H (1998) Molecular beam epitaxy of IV–VI semiconductors. In: Liu AWK and Santos MB (eds) *Heteroepitaxial Thin Film Systems*, pp. 621–688. Singapore: World Scientific.

Springholz G, Schwarzl T, Heiss W, *et al.* (2001) Mid-infrared surface-emitting PbSe/PbEuTe quantum dot-lasers. *Applied Physics Letters* 79–81: 1225.

Tacke M (1995) New developments and applications of tunable IR lead salt lasers. *Infrared Physics and Technology* 36: 447–463.

Yuan S, Springholz G, Bauer G and Kriechbaum M (1994) Electronic and optical properties of PBTe/$PB_{1-x}Eu_xTe$ multiple quantum well structures. *Physical Review* B49: 5476–5489.

Zemel JN, Jensen JD and Schoolar RB (1965) Electrical and optical properties of epitaxial films of PbS, PbSe, PbTe and SnTe. *Physical Review* 140: A330–A337.

Zogg H, Fach A, John J, *et al.* (1995) Photovoltaic IV–VI on Si infrared sensor arrrays for thermal imaging. *Optical Engineering* 34: 1964–1969.

Mercury Cadmium Telluride

M B Reine, BAE SYSTEMS, Lexington, MA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Mercury-cadmium telluride (HgCdTe or $Hg_{1-x}Cd_x$ Te) is a pseudobinary alloy semiconductor that crystallizes in the zincblende structure. The energy bandgap $E_G(x,T)$ varies continuously, and nearly linearly, with alloy composition parameter x, ranging from 1.6 eV for the wide-gap semiconductor CdTe to −0.3 eV for the semimetal HgTe. The bandgap passes through zero at an alloy composition of $x = 0.16$ (for $T = 0$ K). This broad range of energy bandgap provides a continuum of materials whose absorption edge can be tailored to provide high-performance quantum detectors for wavelengths over the 1–30 μm spectral range. Direct allowed valence-to-conduction band transitions are responsible for large values of the optical absorption coefficient, which enable quantum efficiencies approaching 100% to be achieved in practical device designs. Long minority carrier lifetimes result in low thermal noise, and permit high performance to be achieved at operating temperatures that are the highest reported among infrared detectors of comparable cutoff wavelengths. HgCdTe is well-established today as the most broadly applicable high-performance infrared detector material.

This article summarizes the fundamental properties of this versatile alloy semiconductor, and relates the material properties to its success as an infrared photoconductive and photovoltaic detector material.

Historical Background

It is noteworthy that HgCdTe is probably the first example of a semiconductor material that was intentionally created to satisfy well-defined theoretical device requirements. The importance of the infrared atmospheric transmission window at 8–12 μm was well known for thermal imaging systems, which enable night vision by imaging emitted infrared radiation from the scene rather than reflected visible radiation. The only available infrared detectors with the required sensitivity at 8–12 μm were extrinsic photoconductors such as copper-doped germanium, in which the photoinduced transitions were between a donor or acceptor level and the adjacent band extremum. However, such extrinsic detectors required cooling to prohibitively low temperatures, such as 10–15 K, which made thermal imaging systems bulky and impractical.

Theory showed that the reasons for such a low operating temperature were fundamental to the extrinsic detector material itself – essentially a short carrier lifetime that resulted in a large thermal generation rate and a correspondingly large thermal noise. Theory also showed that an intrinsic detector, in which the photoinduced transitions were direct (vertical) transitions between the valence band and the conduction band, could have significantly longer carrier lifetimes. This meant that an intrinsic detector, with a bandgap of 0.1 eV that matched the 8–12 μm band, could achieve the required sensitivity at much higher operating temperatures, as high as 77 K, that of liquid nitrogen. These theoretical and practical considerations motivated the search in the late 1950s for a semiconductor with a direct bandgap of 0.1 eV.

The first report of the synthesis of the semimetal HgTe and the wide-bandgap semiconductor CdTe to form the semiconductor alloy HgCdTe was published in 1959 by the Royal Radar Establishment in Malvern, England. This seminal paper reported both photoconductive and photovoltaic response at wavelengths extending to 12 μm, and made the understated observation that this material showed promise for intrinsic infrared detectors.

Soon thereafter, working under a US Air Force contract with the objective of devising an 8–12 μm background-limited semiconductor infrared detector that would operate at temperatures as high as 77 K, the group led by Paul Kruse at the Honeywell Corporate Research Center in Hopkins, Minnesota developed a modified Bridgman crystal growth technique for HgCdTe. In 1962 they reported both photoconductive and photovoltaic detection in rudimentary HgCdTe devices.

Fundamental Material Properties

Three fundamental properties determine the degree to which a semiconductor will make a successful infrared detector. First, the energy bandgap must be approximately equal to the smallest photon energy to be detected. There can be severe cooling penalties if the bandgap is significantly smaller than the smallest photon energy of interest. Second, the optical absorption coefficient must be large enough so that nearly all incident photons of interest are converted to electron–hole pairs for practical values of device thickness. Third, the inherent recombination mechanisms must allow long carrier lifetimes to be realized so that thermal generation rates, and hence thermal noise, can be minimized for practical devices and operating conditions.

The three key features that make HgCdTe the nearly ideal infrared detector material – tailorable energy band gap over the 1–30 μm range, large optical absorption coefficients that enable high quantum efficiency, and favorable inherent recombination mechanisms that lead to high operating temperature – are direct consequences of the energy band structure of this zincblende semiconductor. They apply no matter whether the device embodiment is a photoconductor, a photodiode or a metal–insulator–semiconductor detector. In addition, HgCdTe has many other favorable material properties, summarized in this article, that are technologically important for realizing practical infrared detectors. Tables 1 and 2 summarize various material properties for $Hg_{1-x}Cd_xTe$. **Table 1** summarizes material properties for $Hg_{1-x}Cd_xTe$ that vary with alloy composition x and temperature T: lattice constant a, energy band gap E_G, cutoff wavelength λ_{CO} (= 1.24/E_G), intrinsic carrier concentration n_i, conduction band effective mass ratio m_C/m_0, conduction band g-factor g_C, static and high frequency dielectric constants $\varepsilon_S/\varepsilon_0$ and $\varepsilon_\infty/\varepsilon_0$, index of refraction $n_R = (\varepsilon_\infty/\varepsilon_0)^{1/2}$, electron and heavy hole mobilities μ_e and μ_{hh}, mobility ratio b, radiative and Auger-1 lifetimes τ_{RAD} and $\tau_{Auger\text{-}1}$, and typical lifetimes $\tau_{typical}$ observed in n-type HgCdTe of low carrier concentration ($<1\times10^{15}cm^{-3}$).

Table 1 Material properties for selected compositions of $Hg_{1-x}Cd_xTe$, including the binary components HgTe and CdTe, and several technologically important alloy compositions. The radiative and Auger-1 lifetimes τ_{RAD} and $\tau_{Auger\text{-}1}$ are calculated for n-type HgCdTe with $N_D = 1 \times 10^{15}$ cm^{-3}

Property	*HgTe*	*$Hg_{1-x}Cd_xTe$*						*CdTe*
x	0	0.194	0.205	0.225	0.31	0.44	0.62	1.0
a (Å)	6.461	6.464	6.464	6.464	6.465	6.468	6.472	6.481
T (K)	77	77	77	77	140	200	250	300
E_G (eV)	−0.261	0.073	0.091	0.123	0.272	0.474	0.749	1.490
λ_{CO} (μm)		16.9	13.6	10.1	4.6	2.6	1.7	0.8
n_i (cm^{-3})		1.9×10^{14}	5.8×10^{13}	6.3×10^{12}	3.7×10^{12}	7.1×10^{11}	3.1×10^{10}	4.1×10^{5}
m_C/m_0		0.006	0.007	0.010	0.021	0.035	0.053	0.102
g_C		−150	−118	−84	−33	−15	−7	−1.2
$\varepsilon_S/\varepsilon_0$	20.0	18.2	18.1	17.9	17.1	15.9	14.2	10.6
$\varepsilon_\infty/\varepsilon_0$	14.4	12.8	12.7	12.5	11.9	10.8	9.3	6.2
n_R	3.79	3.58	3.57	3.54	3.44	3.29	3.06	2.50
μ_e (cm^2/V-s)		4.5×10^5	3.0×10^5	1.0×10^5				
μ_{hh} (cm^2/V-s)		450	450	450				
$b = \mu_e/\mu_{hh}$		1000	667	222				
τ_{RAD} (μs)		16.5	13.9	10.4	11.3	11.2	10.6	
$\tau_{Auger\text{-}1}$ (μs)		0.45	0.85	1.8	40	450	4.8×10^3	
$\tau_{typical}$ (μs)		0.4	0.8	1	7			

Table 2 Material properties for $Hg_{1-x}Cd_xTe$ that are independent of or relatively insensitive to alloy composition

Property	*Symbol*	*Value*
Kane matrix element	E_P	19 eV
Split-off band energy	Δ	0.93 eV
Heavy-hole effective mass ratio	m_{hh}/m_0	0.40–0.53
Valence band offset	E_v(HgTe) − E_v(CdTe)	0.35–0.55 eV

Energy Band Gap and Band Structure

The energy band gap $E_G(x, T)$ of $Hg_{1-x}Cd_xTe$ varies continuously, and nearly linearly, with alloy composition parameter x, ranging from 1.6 eV for the wide-gap semiconductor CdTe to -0.3 eV for the semimetal HgTe, as shown in Figure 1a. Also plotted in Figure 1a is the cutoff wavelength $\lambda_{CO}(x, T)$ ($\approx hc/E_G(x, T)$, where h is Planck's constant and c is the speed of light), defined as that wavelength at which the photoresponse falls to 50% of its peak value. The energy bandgap $E_G(x, T)$, defined at the difference between the Γ_6 and Γ_8 band extrema at $\Gamma = 0$, passes through zero at an alloy composition of $x = 0.16$ (for $T = 0$ K), as illustrated in Figure 1b. This broad range of energy bandgap provides a continuum of materials whose absorption edge can be tailored to provide high-performance quantum detectors for wavelengths over the 1–30 μm spectral range.

Optical Absorption Coefficient

Optical absorption coefficient data for several alloy compositions of $Hg_{1-x}Cd_xTe$ are plotted versus wavelength in Figure 2. Several trends are evident. The absorption strength generally decreases as the gap becomes smaller due both to the decrease in the conduction band effective mass and to the $\lambda^{-1/2}$ dependence of the absorption coefficient on wavelength λ. There is an exponential tail at energies just below the bandgap energy.

Carrier Lifetime Mechanisms

There are two fundamental mechanisms that determine the minority carrier lifetime in defect-free HgCdTe: radiative recombination and Auger recombination (Auger-1 in n-type and Auger-7 in p-type). Because they involve only interactions among electrons and holes in the valence and conduction bands, and do not require the intermediary of defect states, these mechanisms are regarded as inherent to the material itself, depending only on the band structure, the donor or acceptor concentration, and the temperature. The important advantage that HgCdTe enjoys as a high-performance detector material is that these fundamental mechanisms provide, for practically achievable



Figure 1 (a) Energy bandgap $E_G(x,T)$ and cutoff wavelength $\lambda_{CO}(x,T)$ for $Hg_{1-x}Cd_xTe$, plotted versus alloy composition parameter x, for temperatures of 77 K (solid curves) and 300 K (dashed curves). Horizontal bars indicate important cutoff wavelengths for HgCdTe detector technology. (b) Band diagrams near the Γ point calculated for HgTe, for two compositions of $Hg_{1-x}Cd_xTe$, and for CdTe, illustrating the transition from negative to positive energy bandgap. The energy bandgap is defined at the difference between the Γ_6 and Γ_8 band extrema at $\Gamma = 0$. Part (b) reproduced with permission from Chadi DJ and Cohen ML (1973) Electronic structure of $Hg_{1-x}Cd_xTe$ alloys and charge-density calculations using representative K points. *Physical Review B* 7: 692–699.

carrier concentrations, lifetimes that are long enough (and hence thermal generation rates that are low enough) that background-limited sensitivity is achieved at temperatures substantially higher than for other classes of infrared detectors, such as extrinsic detectors (As-doped Si, Cu-doped Ge) and quantum-well infrared photodetectors (QWIPs).



Figure 2 Optical absorption coefficient data for several $Hg_{1-x}Cd_xTe$ alloy compositions, for photon energies near the fundamental absorption edge, plotted versus wavelength.



Figure 3 Calculated detectivity (D^*) for $Hg_{1-x}Cd_xTe$ infrared detectors for four technologically important wavelength regions, plotted versus operating temperature.

Figure 3 illustrates the sensitivities and operating temperatures that can be achieved for HgCdTe infrared detectors for four important wavelength regions. Detectivity, D^*, is the normalized signal-to-noise ratio that is the key figure of merit for the sensitivity of an infrared detector. At lower temperatures, detector thermal noise is negligible, and D^* is limited by detector noise due to fluctuations in the arrival rate of photons from the thermal room-background radiation. This limit is referred to as the BLIP (background-limited infrared photodetector) limit, and is indicated in Figure 3 by the horizontal dashed lines. As detector temperature increases, the detector thermal noise increases exponentially, and eventually overcomes the background noise, causing D^* to decrease exponentially for further increases in temperature. Detector thermal noise is proportional to the thermal generation rate, which is inversely proportional to the carrier lifetime.

n-Type and p-Type Doping

HgCdTe can be made n-type or p-type by a number of relatively convenient methods, at carrier concentrations required for high-performance n-type photoconductor and p-n junction photodiode architectures. Common donors are indium and iodine. Arsenic has become the most commonly used acceptor dopant, although copper and gold are used in some cases. Some HgCdTe photodiode designs still employ native metal-vacancy point defects as acceptors, although the clear trend is toward the use of extrinsic acceptor doping to avoid the strong Shockley–Read recombination associated with the Hg vacancy. Residual electrically active impurity concentrations are generally less than $1 \times 10^{14}\,\mathrm{cm}^{-3}$, which allows controllable doping at low-$10^{14}\,\mathrm{cm}^{-3}$ concentrations.

Crystal Growth Methods

The first growth methods for HgCdTe were bulk growth. Liquid phase epitaxy (LPE) began to be developed around 1975, followed by metalorganic chemical vapor deposition (MOCVD) and molecular beam epitaxy (MBE) in the early 1980s. Bulk growth, LPE, MOCVD, and MBE techniques have been refined through the years, and each is still in use today. Each technique has found application for certain types of HgCdTe devices. Bulk growth methods are used for production quantities of n-type wafers, with diameters of 12–20 mm, for LW and VLW photoconductive arrays, which are more tolerant of dislocations. LPE is in use today for production quantities of photovoltaic (PV) HgCdTe arrays, and has also been used for certain photoconductive HgCdTe arrays. Vapor-phase epitaxy (VPE) methods such as MBE and MOVPE are in use for engineering and prototype quantities. Both run-to-run reproducibility and control as well as intra-wafer uniformity of HgCdTe alloy composition are well in hand, meeting or exceeding requirements.

LPE-based one-layer and two-layer photodiode technology is well established today, offering the lowest defect densities and highest operabilities for production quantities of high performance FPAs. The VPE methods, MBE and MOVPE, will probably not entirely replace LPE in the near future, but will continue to improve, particularly with respect to lower defect densities, offering *in situ* growth of advanced bandgap-engineered detector designs that are unwieldy or impossible with LPE, such as dual-band detectors, avalanche photodiodes, and planar buried junctions with *in situ* CdTe passivation. MBE has shown the potential for rapidly switching from growth of one HgCdTe alloy composition to another in successive growth runs, without the necessity of preparatory calibration growth runs. This compositional agility, important for the rapid and cost-effective adjustment from product to product, will be further enhanced by the ongoing efforts to implement and improve *in situ* real-time monitors and feedback controls.

Substrates for Epitaxial Growth

The lattice mismatch between HgTe and CdTe is small, approximately 0.3%. This allows epitaxial growth of high-quality HgCdTe films on IR-transparent CdTe or nearly-lattice-matched IR-transparent $\mathrm{Cd}_{1-z}\mathrm{Zn}_z\mathrm{Te}$ ($z \approx 0.04$) substrates, with dislocation densities in the mid-$10^4\,\mathrm{cm}^{-2}$ range. It also allows the *in situ* growth of various isotype and anisotype heterojunctions with tolerably low or negligible densities of misfit dislocations. This has led to an increasing number of bandgap-engineered HgCdTe photodiode structures, such as dual-band or two-color detector arrays and Auger-suppressed photodiodes with the potential for greatly increased operating temperature.

Sapphire and silicon are IR-transparent substrates that are less costly, that are available in much larger areas, and that are more rugged than CdTe and CdZnTe. Both sapphire and silicon can be used for epitaxial growth of HgCdTe films with dislocation densities that are acceptably low (mid-$10^6\,\mathrm{cm}^{-2}$) for many important photodiode applications, such as for the MW and SW spectral ranges, and for the LW spectral range for high background photon fluxes. LPE growth of HgCdTe($x = 0.4$) is done on 3-inch diameter sapphire substrates with MOCVD-grown CdTe buffer layers. MBE growth of HgCdTe($x = 0.3$) on 4-inch diameter (211) silicon substrates, with ZnTe/CdTe buffer layers, has recently been reported.

Dielectric Constant

The relatively low dielectric constant ($\varepsilon_S = 18\varepsilon_0$) of HgCdTe, in contrast to those of PbTe and PbSnTe, permits low junction capacitance. This is important for fast response in laser pulse detectors where small $R-C$ time constants are needed. It is also important for suppressing preamplifier noise below the detector noise, and thereby achieving high detectivity (D^*), in photodiodes operating at low temperature and low background fluxes, where the junction resistance is sufficiently high that the junction capacitance becomes an important contribution to the junction impedance at frequencies of interest.

Surface Passivation

Passivation of the exposed HgCdTe surfaces is critical for both device performance and long-term stability. The favorable surface properties of HgCdTe have enabled practical surface passivation schemes to be developed for both n-type photoconductors and p-n junction photodiodes of both planar and mesa configurations.

n-type HgCdTe photoconductors are commonly passivated with a native oxide that accumulates the surface, resulting in surface recombination velocities as low as 50 cm s^{-1}, along with low 1/*f* noise (knee frequencies less than 50 Hz). The surface accumulation layer also provides a layer of surface electrons with high mobility, though lower than the bulk electron mobility, such that the shunt conductance of this layer is tolerably low compared to the bulk conductance of the detector itself. Several methods have been used for growing this native oxide, including plasma deposition and electrochemical (anodic) oxidation.

HgCdTe photovoltaic detectors require quite different passivation because usually both n-type and p-type surfaces are exposed as well as the depletion region. The CdTe/HgCdTe heterostructure is an important passivation for HgCdTe photovoltaic detectors and arrays. CdTe passivation has enabled arrays of HgCdTe photodiodes with negligible 1/*f* noise (knee frequencies less than 1 Hz), radiation hardness well in excess of the 20–40 kRad(Si) usually encountered in Earth-resource space missions, and excellent stability to thermal bake and to exposure to moisture.

CdTe has a number of important advantages as a passivant for HgCdTe junctions. It is a 'native' passivant that is chemically compatible with HgCdTe. Adhesion is excellent. The valence band edge of CdTe is approximately 0.4 eV below that of HgTe, thereby allowing repulsive barriers to form in the underlying HgCdTe for both electrons in the conduction band and holes in the valence band. Both mesa and planar photodiodes have been successfully passivated with CdTe. A wide variety of methods has been reported for deposition of CdTe passivating layers, including MBE, MOVPE, e-beam evaporation, sputtering, and hot wall epitaxy.

Electron-to-Hole Mobility Ratio

The small values for the conduction band effective mass ratio lead to large values for the electron mobility, as large as 4.5×10^5 cm^2/V-s for $x = 0.195$ at 77 K. The heavy hole effective mass ratio is quite large, approximately 0.5 for all alloy compositions, leading to low values for the heavy hole mobility, on the order of 500 cm^2/V-s. This gives large values for the electron-to-heavy hole mobility ratio, b, as high as 1000 for $x = 0.194$ at 77 K.

These large values of b were of great benefit to n-type HgCdTe photoconductors. Most such devices have small active areas, on the order of 50×50 μm^2, and the drift length for minority carriers (holes) becomes comparable to the interelectrode spacing at modest bias voltages. In this case, when the contacts have a high recombination velocity, the photoconductive gain saturates to the value $b/2$. High values of b in HgCdTe allowed sufficiently high photoconductive gains to be achieved to raise the detector noise above the preamp noise, an essential condition for achieving BLIP sensitivity.

HgCdTe Infrared Detector Configurations

Three different types of infrared detectors can be realized in the $Hg_{1-x}Cd_xTe$ alloy semiconductor: the photoconductive (PC) detector, the photodiode, also referred to as the photovoltaic (PV) detector, and the metal–insulator–semiconductor (MIS) detector. These are illustrated in Figure 4.

In all three types of HgCdTe detector – PC, PV, and MIS – excess electron–hole pairs are photogenerated by the same mechanism: valence-to-conduction band absorption of infrared radiation with photon energy greater than the bandgap energy E_G. All three types can achieve high quantum efficiencies, approaching 100% for well-designed devices. All three types have the same fundamental recombination mechanisms (Auger-1 and radiative) that determine the highest possible operating temperature to achieve a given sensitivity (signal-to-noise ratio).



Figure 4 Three different types of infrared detectors have been realized in the $Hg_{1-x}Cd_xTe$ alloy semiconductor: the photoconductive (PC) detector, the photodiode or the photovoltaic (PV) detector, and the metal–insulator–semiconductor (MIS) detector. HgCdTe PC and PV detector arrays are being manufactured for a wide variety of applications. The MIS detector was abandoned in the mid-1980s because it placed unachievable demands on material quality.

The differences among PC, PV, and MIS HgCdTe detectors are due to the way in which the photogenerated electron–hole pairs are manifested electrically in the terminal characteristics of the device. In the PC detector, the excess electron–hole pairs are sensed as a small increase in the conductivity of what is basically a two-terminal resistor. In the PV detector, the excess electron–hole pairs are sensed as a photocurrent in a short-circuited p-n junction photodiode. In the MIS detector, the excess electron–hole pairs are sensed as a small change in the voltage due to minority photocarriers filling a transient charge storage well that has been biased to deep depletion.

PC HgCdTe Detectors

The HgCdTe PC detector is a low-resistance two-terminal device. Resistances are typically 25–100 ohms per square. A dc bias current is applied to convert the conductivity change to an observable voltage change. The device operates under near-equilibrium conditions, with small dc bias voltages typically on the order of 0.1 V. The dc bias electric field within the photoconductor is quite small, generally in the 20–50 $\mathrm{V\,cm^{-1}}$ range. The low-resistance device requires a low-noise bipolar preamplifier, usually external to the dewar. Each PC detector element requires one lead through the dewar wall, thus limiting the practical number of PC elements in an array to about 200–300.

The basic HgCdTe photoconductor is a rectangular area, photolithographically defined in an n-type HgCdTe layer approximately 8–15 μm thick, with two ohmic contacts on opposite edges. Surface passivation is straightforward: a thin native oxide strongly accumulates the surface of n-type HgCdTe, thereby reducing the surface recombination velocity to negligibly small values.

Many useful variations on the simple rectangular geometry are possible because of the favorable material properties of HgCdTe. Several contact geometries have been devised to minimize the recombination of photocarriers at the contacts. Serpentine designs have been used to increase detector resistance and reduce bias power dissipation, especially important issues for large-area and very long-wavelength detectors. The SPRITE (signal processing in the element) design reduces the number of electrical connections and dewar leads for scanned arrays by performing both detection and integration within an elongated HgCdTe bar.

PV HgCdTe Detectors

The HgCdTe photodiode is a more complicated device than the photoconductor, requiring both n-type and p-type layers, and having a surface depletion region that makes stringent demands on surface passivation technology.

The PV detector is a high-resistance p-n junction device. The photodiode is operated very close to equilibrium conditions, either at zero bias voltage or at a small reverse bias voltage whose magnitude is several *kT*, typically 20–30 mV. The absorber layer is usually n-type HgCdTe about 5–15 μm thick, with the thicker values required for longer-wavelength radiation. A p-n junction is formed by a thin p-type layer. A wide variety of junction formation methods are used. Wide-gap-p on narrow-gap-n heterojunctions are formed by two-layer LPE. Planar p-on-n or n-on-p junctions are formed by arsenic or boron implantation into n-type or p-type layers grown by LPE or MBE. Vertical-geometry p-on-n junctions are formed by a damage mechanism during ion beam milling. Both single-junction and multijunction devices are grown *in situ* by vapor phase epitaxial methods such as MBE and MOVPE. Surface passivation is generally accomplished by CdTe. The high-resistance PV device can match well with low-noise silicon CMOS preamplifiers that can be integrated with two-dimensional arrays to form large back-illuminated hybrid focal plane arrays (FPAs). Typical array formats for HgCdTe FPAs are 256 × 256 and 480 × 640, and can be as large as 1024 × 1024 and 2048 × 2048.

MIS HgCdTe Detectors

The metal–insulator–semiconductor (MIS) detector, also referred to as a photocapacitor, is usually formed on an n-type HgCdTe absorber layer. The insulator of choice is a thin native oxide. The gate electrode is a thin semitransparent metal film.

In contrast to the PC and PV detectors, the MIS detector operates in a strongly nonequilibrium mode.


Infrared radiation
N x N HgCdTe array
Output leads
Indium interconnects
CMOS silicon multiplexer chip with N x N unit cells
Indium interconnects
Substrate
N-type HgCdTe
P-type HgCdTe
Silicon
Unit cell
15KV 424X 50U 0731

Figure 5a Back-illuminated bump-interconnected HgCdTe FPA architecture. The SEM photo shows an LPE P-on-n HgCdTe mesa photodiode array with 60 × 60 μm^2 unit cells and 33 × 33 μm^2 mesa (junction) areas.

A bias voltage pulse of several volts is applied across the capacitor to drive the HgCdTe surface into deep depletion. Excess electron–hole pairs are photogenerated in the absorber layer and diffuse to the edge of the depletion region, where the holes are collected in the charge well. After a period of time, called the integration time, the voltage across the capacitor is sensed, giving a measure of how much charge was collected, and the cycle is repeated.

Because of the nonequilibrium operation of the MIS detector, much larger electric fields are set up in the depletion region than in the p-n junction, resulting in defect-related tunneling dark current that is orders of magnitude larger than the fundamental dark current. The MIS detector requires much higher material quality than PV or PC detectors, which still has not been achieved. For this reason, all development of the HgCdTe MIS detector was abandoned in the mid-1980s.

Two-Dimensional HgCdTe Infrared Focal Plane Arrays

Among the most important applications of HgCdTe are large two-dimensional electronically scanned hybrid arrays, referred to as focal plane arrays (FPAs). A hybrid HgCdTe FPA consists of a two-dimensional HgCdTe photovoltaic detector array that is interfaced electrically, thermally and mechanically with a matching two-dimensional array of input circuits in a silicon CMOS ROIC chip. Each HgCdTe detector element in the array has one electrical connection to its matching input circuit node in the silicon ROIC.

The thermal expansion coefficient of HgCdTe is sufficiently close to that of silicon to allow several technologically viable hybrid arrangements of HgCdTe detector arrays and silicon multiplexer chips.

There are two main types of hybrid HgCdTe FPAs being developed and manufactured today: the back-illuminated bump-interconnected configuration, shown in Figure 5a, and the front-illuminated or ‘loophole’ configuration shown in Figure 5b. Each configuration successfully solves the problem of the thermal expansion mismatch between silicon and HgCdTe in different ways, and each requires fundamentally different HgCdTe photodiode designs and processing.

In the back-illuminated configuration, illustrated in Figure 5a, the HgCdTe detector array is bump-mounted onto the silicon ROIC by cold-welded or thermally reflowed indium interconnects. Incident radiation reaches the detectors through an infrared-transparent substrate such as CdTe, CdZnTe, sapphire, or silicon.

In the front-illuminated (or ‘loophole’) FPA architecture, shown in Figure 5b, the thin HgCdTe layer is epoxied to the silicon ROIC chip, and undergoes elastic deformation when the FPA is cooled. This allows large arrays to be made without need for engineering the thermal expansion of the silicon ROIC chip. Low-temperature processing techniques



Figure 5b Front-illuminated loophole HgCdTe FPA architecture. The SEM photo shows one corner of a FPA. The metalized via holes are on 20 μm centers.

for junction formation and passivation are required because of the presence of the epoxy.

Conclusions and Trends

There has been enormous progress in HgCdTe material science and device technology over the past 45 years. This progress has been fueled by the many military and space applications for which HgCdTe PC and PV infrared detectors provide nearly ideal solutions. It is important to recognize that the progress so far in HgCdTe detector technology has been possible only through advances in basic materials growth and processing technology.

Further progress can be expected. The fundamental performance limits of HgCdTe photodiodes have not yet been reached. Continued reduction of material defects, both grown-in and process-induced, will reduce thermal generation rates, increase junction impedance, and allow higher operating temperatures for a number of important applications. Continued development of the *in situ* VPE growth methods – MBE and MOVPE – will allow bandgap-engineered heterojunction devices of increasing quality and complexity. Continued development of VPE growth on alternative substrates such as silicon will reduce the cost of two-dimensional arrays, and will make larger arrays practical.

List of Units and Nomenclature

BLIP	Background limited infrared photodetector
CdTe	Cadmium telluride
CdZnTe	Cadmium zinc telluride
CMOS	Complementary metal-oxide-semiconductor
FPA	Focal plane array
HgCdTe	Mercury cadmium telluride
$Hg_{1-x}Cd_xTe$	Mercury cadmium telluride
IR	Infrared
LPE	Liquid phase epitaxy
LW	Long wavelength
LWIR	Long wavelength infrared
MBE	Molecular beam epitaxy
MCT	Mercury cadmium telluride
MIS	Metal-insulator-semiconductor
MOCVD	Metal-organic chemical vapor epitaxy
MOVPE	Metal-organic vapor phase epitaxy
MW	Medium wavelength
MWIR	Medium wavelength infrared
PC	Photoconductive
PV	Photovoltaic
QWIP	Quantum well infrared photodetector
ROIC	Readout integrated circuit
SPRITE	Signal processing in the element
SW	Short wavelength
SWIR	Short wavelength infrared
VLW	Very long wavelength
VLWIR	Very long wavelength infrared
VPE	Vapor phase epitaxy

See also

Semiconductor Physics: Band Structure and Optical Properties; Impurities and Defects; Outline of Basic Electronic Properties.

Further Reading

Capper P (ed.) (1994) *Properties of Narrow Gap Cadmium-based Compounds*. EMIS Datareviews Series No. 10. London: INSPEC, Institution of Electrical Engineers. Reviews and compilations of fundamental and technological properties of HgCdTe and CdTe/CdZnTe/CdTeSe.

Capper P (ed.) (1997) *Narrow-Gap II–VI Compounds for Optoelectronic and Electromagnetic Applications*. London: Chapman and Hall. Twenty review chapters on growth techniques, materials characterization, and device applications of HgCdTe.

Capper P and Elliott CT (eds) (2000) *Infrared Detectors and Emitters: Materials and Devices*. Boston, MA: Kluwer Academic Publishers. Review chapters on HgCdTe materials, photoconductive and nonequilibrium HgCdTe detectors, photovoltaic HgCdTe detectors, and HgTe-CdTe superlattice detectors.

Rogalski A, Adamiec K and Rutkowski J (2000) *Narrow Gap Semiconductor Photodiodes*. Washington, DC: SPIE Press.

Willardson RK and Beer AC (eds) (1981) *Defects, (Hg,Cd)Se, (Hg,Cd)Te*. Semiconductors and Semimetals, vol. 16. New York: Academic Press. Review chapters on magneto-optical properties of HgCdTe and nonlinear optical effects in HgCdTe.

Willardson RK and Beer AC (eds) (1981) *Mercury Cadmium Telluride*. Semiconductors and Semimetals, vol. 18. New York: Academic Press. Seven review chapters: history of HgCdTe, preparation of high-purity Hg, Cd and Te, crystal growth of HgCdTe, Auger recombination in HgCdTe, and photoconductive, photovoltaic and metal-insulator-semiconductor HgCdTe detectors.

Modulation Spectroscopy of Semiconductors and Semiconductor Microstructures

Y-S Huang, National Taiwan University of Science and Engineering, Taipei, Taiwan

F H Pollak, Brooklyn College of the City University of New York, Brooklyn, NY, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Modulation spectroscopy is a versatile and powerful optical technique for obtaining valuable information relevant to a large variety of semiconductor systems including bulk/thin films, surfaces/interfaces [semiconductor/air (vacuum), semiconductor/electrolyte, semiconductor/metal, semiconductor/semiconductor (homo- and heterojunctions)], micro- and nanostructures (quantum wells, multiple quantum wells, superlattices, quantum wires, quantum dots), the effects of growth/processing, as well as the characterization of actual device structures [heterojunction bipolar transistors (HBTs), pseudomorphic high electron mobility transistors (PHEMTs), edge-emitting and vertical-cavity surface-emitting (VCSEL) quantum well lasers, etc.].

Modulation spectroscopy deals with the measurement and interpretation of changes in the optical response of a sample which are effected by the modification of the measurement conditions. This can easily be accomplished by periodically modulating either (1) the measurement conditions themselves ('internal' modulation) or (2) some parameters applied to the sample ('external' modulation). The observed normalized changes are usually small so that the difference signals are closely related to a derivative of the absolute spectrum with respect to the modifying parameters. The derivative nature of modulation spectroscopy emphasizes structure localized in the photon energy region of the interband (intersub-band) transitions of semiconductors (semiconductor microstructures) and suppresses uninteresting background effects. As a result, weak features that may not be detected in the absolute spectra are often enhanced. Because of this derivative-like nature a large number of sharp spectral features may be observed, even at room temperature.

The ability to perform a lineshape fit is one of the great advantages of modulation spectroscopy. Since for the modulated signal the features are localized in photon energy it is possible to account for the lineshapes to yield accurate values of energies and broadening parameters of the associated interband transitions. For example, the energies of various interband (intersub-band) transitions may be evaluated to within a few meV, even at room temperature. Thus, the effects of static external perturbations such as electric and magnetic fields, temperature, hydrostatic pressure, uniaxial stress, etc., can be conveniently studied.

A particularly useful form of modulation spectroscopy is electromodulation (EM) since it is sensitive to surface/interface electric fields and can be performed in contactless modes that require no special mounting of the sample. Under appropriate conditions the EM spectrum may exhibit above bandgap oscillatory features, called Franz–Keldysh oscillations (FKOs), which are a direct measure of the relevant electric field (built-in and/or applied).

Two of the most widely used forms of EM are photoreflectance (PR) and contactless electroreflectance (CER). In PR, modulation of the built-in electric field is caused by photo-excited electron–hole pairs created by a pump source of ~3–5 mW power of either (1) an internally modulated laser diode or (2) a mechanically chopped dc laser. The modulating frequency is typically ~100–200 Hz. CER utilizes a condenser-like system consisting of a front wire grid electrode with a second metal electrode separated from the first electrode by insulating spacers, which are ~0.1 mm larger than the sample thickness. The sample is placed between these two capacitor plates. Thus, there is nothing in direct contact with the front surface of the sample. The probe beam is incident through the front wire grid. EM is achieved by apply an ac voltage (~1 kV peak to peak at ~200 Hz) across the electrodes.

Instrumentation

Shown in Figure 1 is a schematic drawing of the experimental arrangement for a general 'external' modulated reflectance experiment (except for PR). Light from an appropriate light source (xenon arc or tungsten halogen lamp) passes through a monochromator. The exit intensity at wavelength λ, $I_o(\lambda)$, is focused onto the sample by means of a lens (or mirror). The modulation (electric field, stress, temperature) is applied to the sample at frequency Ω_m. The reflected light is collected by a second lens (mirror) and is focused onto an appropriate detector



Figure 1 Schematic representation of external modulation experimental apparatus.

(photomultiplier or photodiode). For the sake of simplicity the two lenses (mirrors) are not shown.

The light striking the detector contains two signals: the dc is given by $I_o(\lambda)R(\lambda)$, where $R(\lambda)$ is the dc reflectance of the material while the modulated value (at frequency Ω_m) is $I_o(\lambda)\Delta R(\lambda)$, where $\Delta R(\lambda)$ is the change in reflectance produced by the modulation source. The ac signal from the detector, proportional to $I_o(\lambda)\Delta R(\lambda)$, is measured by a lock-in amplifier. Typically $I_o\Delta R$ is 10^{-4}–10^{-6} of I_oR. In order to evaluate the quantity of interest, i.e., the relative change in reflectance $\Delta R/R$, a normalization procedure must be used to eliminate the uninteresting common feature $I_o(\lambda)$. This can be done in several ways, one of which is shown in Figure 1, where the normalization is performed by a variable neutral density filter (VNDF) connected to a servo mechanism. The dc signal from the detector, which is proportional to $I_o(\lambda)R(\lambda)$, is fed into the servo which moves the VNDF in such a manner as to maintain a constant $I_o(\lambda)R(\lambda)$, i.e., $I_o(\lambda)R(\lambda) = C$. Under these conditions the ac signal $I_o(\lambda)\Delta R(\lambda) = C\Delta R(\lambda)/R(\lambda)$. Subsequently, the signal to the lock-in amplifier is proportional to the quantity of interest, i.e., $\Delta R(\lambda)/R(\lambda)$.

Bulk/Thin-Film Material

Modulation spectroscopy has been used to study the properties of bulk/epitaxial layered semiconductors such as ordering in $GaInP_2$, piezoelectric fields in strained GaN, the influence of isotopes, the properties of low-temperature grown GaAs, the space charge region, carrier concentration, the nature of the band bending (carrier type), impurity effects, deep levels, alloy composition, the influence of static external or internal perturbations such as temperature, external uniaxial stress, lattice-mismatch strain, hydrostatic pressure, the effects of crystal growth/processing/annealing procedures, and amorphous and microcrystalline materials.

The dashed lines in Figure 2 are the piezoreflectance (PZR) spectra in the region of the direct gap of ReS_2 in the temperature range $25\,K < T < 450\,K$. The data at low temperatures exhibit two well-resolved features labeled E_1^{ex} and E_2^{ex}. The solid lines are lineshape fits to the first derivative of a Lorentzian profile which yields the energies indicated by arrows and also the related broadening parameters. The solid/open squares and circles in Figure 3 are the temperature dependence of E_1^{ex}/E_2^{ex} of ReS_2 and $ReSe_2$, respectively. The solid, dot-dashed, and dashed lines in the figure are fits to the Varshni, O'Donnel–Chen, and Bose–Einstein expressions, respectively. The Varshni equation is:

$$E_i^{ex}(T) = \frac{E_i^{ex}(0) - \alpha_i T^2}{\beta_i + T} \quad [1]$$

where $i = 1$ or 2, $E_i^{ex}(0)$ is the excitonic transition energy at 0 K and α, β are the Varshni coefficients. The O'Donnel–Chen expression is:

$$E_i^{ex}(T) = E_{i0} - S_i\langle\hbar\Omega_i\rangle\left(\frac{\coth\langle\hbar\Omega_i\rangle}{2kT} - 1\right) \quad [2]$$



Figure 2 The PZR spectra (dashed lines) in the region of the direct gap of ReS2 in the temperature range $25\,K < T < 450\,K$. The solid lines are lineshape fits yielding the energies indicated by the arrows.



Figure 3 The temperature dependence of the excitonic transition energies of ReS_2 and $ReSe_2$. The solid, dot-dashed, and dashed lines in the figure are fits to the Varshni, O'Donnel–Chen, and Bose–Einstein expressions, respectively.



Figure 4 The solid/open squares and circles are the temperature dependence of the broadening parameters of E_1^{ex}/E_2^{ex} of ReS_2 and $ReSe_2$, respectively. The solid lines are fits to the Bose–Einstein-type expression.

where E_{i0} is the excitonic transition energy at 0 K, S_i is a dimensionless coupling constant related to the strength of the electron–phonon interaction, and $\langle \hbar\Omega_i \rangle$ is the average phonon energy. The Bose–Einstein-type expression can be written as

$$E_i^{ex}(T) = E_{iB} - a_{iB}\left[1 + \frac{2}{\exp(E_{ap}/kT) - 1}\right] \qquad [3]$$

where a_{iB} represents the strength of the electron (exciton)–phonon interaction, and E_{ap} corresponds to the average phonon energy.

The temperature dependence of the broadening parameters, $\Gamma(T)$, is due only to the electron–phonon interaction and can also be described by a Bose–Einstein-type equation. For the lowest lying direct gap only the longitudinal optic (LO) phonon is involved. In Figure 4 the solid/open squares and circles are the temperature dependence of the broadening parameters of E_1^{ex}/E_2^{ex} of ReS_2 and $ReSe_2$, respectively. The solid lines are fits to the Bose–Einstein-type expression:

$$\Gamma_i(T) = \frac{\Gamma_i(0) + \Gamma_{i,ep}}{\exp(E_{i,LO}/kT) - 1} \qquad [4]$$

where $i = 1$ or 2. The first term of eqn [4] corresponds to broadening mechanisms due to intrinsic lifetime, electron–electron interaction, impurity, dislocation, and alloy scattering effects. The parameter Γ_{ep} is an electron (exciton)–phonon coupling coefficient and E_{LO} is the zone-center LO phonon energy. The obtained values of Γ_{ep} for these materials have been compared with those for the direct gap in GaAs and ZnSe.

Surfaces/Interfaces

Almost since the inception of modulation spectroscopy it has been recognized that EM could be used as an effective probe of surfaces and interfaces. For EM this is true not only because of the sharp, derivative-like spectral features but also due to its sensitivity to electric fields, i.e., FKOs. In addition, PR and CER are of considerable interest and usefulness since they are contactless, employ low light levels, require no special mounting of the sample, and can be performed in any transparent ambient including ultrahigh vacuum (UHV).

Of particular usefulness in the study of Fermi level pinning at surfaces are UN(SIN)/UP(SIP) and δ-doping configurations. The UN(SIN)/UP(SIP) structures are made by fabricating an undoped layer of thickness $L\,(\sim 1000\,\text{Å})$ on a buried doped $n^+(p^+)$ buffer on a doped $n^+(p^+)$ substrate. In the $n^+(p^+)$ buffer/substrate the Fermi level occurs near the conduction (valence) band edge. At the surface the Fermi level is pinned at some value, V_F. Therefore, there exists in the undoped region, which has a small broadening parameter, a large, almost constant electric field, F. A similar constant field can be created by placing a δ-doping layer a distance L from the surface.

The relation between F, as observed from the FKOs, and V_F is given by:

$$FL = V_F - (kT/q) - \text{SCC} - V_p(T) \qquad [5]$$

where the second, third, and fourth terms on the right-hand side are the Debye length, space charge layer, and temperature dependent photovoltaic effect corrections, respectively.

The properties of the metal–semiconductor interface have been reported by a number of investigators using PR and/or ER. Jonker *et al.* have demonstrated that an epitaxial Fe film on GaAs (UN structure) provides a ferromagnetic contact, suppresses midgap state formation, and does not pin the Fermi level. Four samples were investigated: a native oxide reference sample, the same sample after sulfur passivation, Al/GaAs-(2 × 4), and Fe/GaAs-(2 × 4). The width of the undoped GaAs layer was 1070 Å for the first three samples and 1500 Å for the last sample. These results are shown in Figure 5a–d, respectively. The fields obtained from the FKOs are 58 kV/cm, 61 kV/cm, 55 kV/cm and 60 kV/cm. For the first three samples the measured barrier height is about 0.64 eV (not corrected for the photovoltaic effect) while for the Fe/GaAs material it is about 40% higher (~0.9 eV). Another significant feature of the Fe/GaAs spectrum is the large number of FKOs (in relation to the other samples) extending to about 2 eV. The significant reduction in damping indicates a substantial increase in carrier lifetimes.

Micro- and Nanostructures

Modulation spectroscopy is a very powerful tool for investigating many of the fundamental aspects of compositional single quantum wells (SQWs)/multiple quantum wells (MQWs), superlattices (SLs), quantum wires, and quantum dots (QDs). Various phenomena can be studied, including band offset, well and barrier widths, excitons, strain, coupling and decoupling between wells, miniband formation, two-dimensional electron gas (2DEG) effects, zone-folding in short-period SLs, built-in electric fields, etc. Work on a large variety of GeSi, III–V and II–VI systems has been reported, including both lattice-matched and strain-layer configurations. In addition the effects of various external perturbations can be evaluated.

The properties of a vertically coupled InAs/GaAs QD-based laser structure fabricated by a self-assembled technique have been investigated by CER (300 K and 20 K). Signals have been observed from all the relevant regions of the sample. The dotted lines are the CER spectra at 300 K and 20 K in Figure 6a,b, respectively. The solid lines are lineshape fits which yield the energies indicated by arrows. The low-energy features, labeled QD_0 (lateral coupling), QD_1 (vertical coupling) and QD_2 (vertical coupling), originate from the QDs while the resonances designated W_1 and W_2, correspond to the first conduction to first heavy- (1C-1H) and light-hole (1C-1L) transitions, respectively, in the QW (approximately one monolayer) formed by the



Figure 5 The PR spectra at 300 K for (a) a native oxide reference sample, $F = 58$ kV/cm; (b) the same sample following sulfur passivation, $F = 61$ kV/cm; (c) Al/GaAs-(4 × 2) sample, $F = 55$ kV/cm, and (d) Fe/GaAs-(2 × 4) sample, $F = 60$ kV/cm. The thickness of the undoped spacer region is 1070 Å for (a)–(c) and 1500 Å for (d).



Figure 6 CER spectra (dotted lines) of an InAs/GaAs quantum dot-based laser structure at (a) 300 K and (b) 20 K. The solid lines are a lineshape fit to a first derivative Gaussian.



Figure 7 Room-temperature CER spectra (dashed lines) for a GaInP/GaAs HBT sample fabricated by metalorganic chemical vapor deposition for incident light polarized (a) $\boldsymbol{E}\|[110]$ and (b) $\boldsymbol{E}\|[1\bar{1}0]$. The solid lines are a lineshape fit which yields the bandgap energies denoted by arrows.

wetting layer (WL). Although the oscillator strength of the QD features is small compared to the WL resonances, they are clearly visible even at 300 K. The GaAs$_1$ and GaAs$_2$ features are attributed to GaAs-related transitions. The former at both 300 K and 20 K corresponds to the bandgap energy of GaAs and probably comes from the undoped 400 Å-thick GaAs layers which envelop the QD region. The GaAs$_2$ feature is most likely related to the p-doped 6000 Å-thick GaAs cap layer. The heavy doping of this layer induces a Burstein–Moss blue shift of the bandgap.

Device Structures

The methods of PR and CER are valuable tools in the evaluation of important device parameters for structures such as heterojunction bipolar transistors (HBTs), pseudomorphic high electron mobility transistors (PHEMTs), edge-emitting and vertical cavity surface-emitting (VCSEL) quantum well lasers, multiple quantum well infrared detectors, solar cells, superlattice optical mirrors, resonant tunneling structures, metal-oxide-semiconductor (MOS) configurations, among others.

The dashed lines in Figure 7a,b are the 300 K CER spectra of a GaInP$_2$(emitter)/GaAs(collector) HBT (fabricated by metalorganic chemical vapor deposition) for incident light with electric field vector $E\|[110]$ (polarization A) and $E\|[1\bar{1}0]$ (polarization B), respectively. Both collector and emitter signals exhibit well-pronounced FKOs. The solid lines are least-squares fits to a function which contains Lorentzian broadened electro-optic functions, yielding 1.873 ± 0.001 eV and 1.885 ± 0.001 eV for the GaInP$_2$ bandgaps for polarizations A and B, respectively, as indicated by the arrows. The ordering parameter of 0.3 deduced from the differences in the measured bandgaps for the two polarizations was consistent with transmission electron microscope measurements. The electric fields evaluated from the emitter and collector region FKOs were compared with a computer simulation of the field profiles using a comprehensive, self-consistent model, including the photovoltaic effect. The deduced emitter and collector doping densities were in good agreement with the intended growth conditions.

Summary

Modulation spectroscopy is a very powerful tool for investigating many of the fundamental and applied aspects of a wide variety of semiconductors and semiconductor micro- and nanostructures, including bulk/thin films, surfaces/interfaces, single quantum wells, multiple quantum wells, superlattices, quantum wires, quantum dots, etc. In addition the effects of various perturbations such as alloy composition, temperature, electric and magnetic fields, hydrostatic pressure, internal and/or external stain, processing, etc., can be evaluated. Recently these methods have also been applied for the characterization of actual device structures such as HBTs, PHEMTs, quantum well lasers, etc.

See also

Semiconductor Materials: Quantum Dots. **Semiconductor Physics:** Band Structure and Optical Properties; Impurities and Defects; Outline of Basic Electronic Properties; Quantum Wells and GaAs-based Structures; Surface Photovoltage Spectroscopy of Semiconductors.

Further Reading

Aspnes DE (1980) Modulation spectroscopy/electric field effects on the dielectric properties of semiconductors. In: Balkanski M (ed.) *Handbook on Semiconductors*, vol. 2, pp. 109–154. Amsterdam, The Netherlands: North-Holland.

Glembocki OJ and Shanabrook BV (1992) Photoreflectance spectroscopy of microstructures. In: Seiler DG and Littler CL (eds) *Semiconductors and Semimetals*, vol. 36, pp. 222–289. New York: Academic Press.

Pollak FH (1994) Modulation spectroscopy of semiconductors and semiconductor microstructures. In: Balkanski M (ed.) *Handbook on Semiconductors*, vol. 2, pp. 527–635. Amsterdam, The Netherlands: North Holland.

Pollak FH (1995) Electromodulation spectroscopy of semiconductor surfaces and interfaces. In: Halevi P (ed.) *Photonic Probes of Surfaces*, pp. 175–209. Amsterdam, The Netherlands: North-Holland.

Pollak FH (1996) Modulation spectroscopy of quantum wells and superlattices. In: Bhattacharya P (ed.) *Properties of III–V Quantum Wells and Superlattices*: *EMIS Data Reviews Series #15*, pp. 232–240. London: INSPEC.

Pollak FH (1998) Modulation spectroscopy of the group III-nitrides. In: Gil B (ed.) *Group III Nitride Semiconductor Compounds*, pp. 158–181. Oxford, UK: Clarendon.

Pollak FH (2001) Modulation spectroscopy characterization of semiconductors and semiconductor microstructures. In: Buschow KH, Cahn W, Flemmings MC, *et al.* (eds) *Encyclopedia of Materials: Science and Technology*, vol. 6, pp. 5743–5748. Amsterdam, The Netherlands: Elsevier.

Ramdas AK and Rodriguez S (1992) Piezospectroscopy of semiconductors. In: Seiler DG and Littler CL (eds) *Semiconductors and Semimetals*, vol. 36, pp. 137–220. New York: Academic Press.

Quantum Dots

R J Warburton, Heriot-Watt University,
Edinburgh, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Quantum dots are nanometer-sized clusters of semiconductor material. An island of low-bandgap material is embedded in a sea of high-bandgap material so that both electrons and holes are spatially confined in all three directions. In an unstructured semiconductor, the electron energy levels of the individual atoms hybridize to form energy bands. In a quantum dot, however, there are discrete energy levels. This can be understood from the band structure of the unstructured material where there is a so-called dispersion relation connecting the energy, E, and the momentum, k. The confinement potential of a quantum dot quantizes the k-values, giving rise to discrete energy levels. If the energy levels of a quantum dot are separated by more than the typical energy level broadenings and by more than the thermal energy then the quantum dot will behave quite differently to the bulk material. The quantum dot will exhibit atom-like properties – discrete energy levels with small degeneracies – despite the fact that it is embedded in a semiconductor matrix. It is this ability to prepare a variety of atom-like systems in a semiconductor environment which has driven the research into semiconductor quantum dots.

In some sense, nanosized quantum dots have been the subject of research for quite some time. Color filters, for instance, consist of nanosized particles dispersed in a glass matrix, and this is a very mature technology. Also, lithography of layered semiconductor systems already possessing confinement in one dimension has been pursued for at least 15 years. However, developments in the past few years have been rapid, all based on the discovery of self-assembly of quantum dots directly in the growth of semiconductor heterostructures. These quantum dots can be produced with standard materials in standard growth systems, and this allows an easy integration of quantum dots into devices such as diode lasers. Furthermore, the self-assembled quantum dots are of extremely high quality and this is of great value not just for devices but also for fundamental physics experiments, aimed at studying or exploiting the coherence of excitons confined in the quantum dots. For these reasons, this short review concentrates on the properties of self-assembled quantum dots, giving just brief descriptions of other systems. It should be noted that the bibliography is extremely limited and in no way does justice to the large number of research groups which have made valuable contributions to this field. Instead, the bibliography is simply a list of suggestions for finding out more about this fascinating research area.

Quantization in Quantum Dots

Quantum dots are on the one hand large enough that the bulk band structure of the host material can be used to describe the material's electronic properties. In the effective mass approximation, this amounts to giving both electrons and holes a quadratic dispersion on momentum, just as for a free electron, but with an effective mass, typically about 0.1 for the electrons, and 0.3 for the holes. On the other hand, quantum dots are small enough that confinement effects are important. For instance, the energy of an exciton in a nanometer-sized quantum dot is a strong function of the quantum dot size. As the dots become smaller, confinement effects become larger, and the energy separating electron and hole levels increases. This does not increase indefinitely, however. There is a finite-size energy barrier to the matrix surrounding the dot such that in the limit of small dot sizes, the wavefunction spreads out into the barrier region and confinement effects become very weak. Ideally, an electron in a quantum dot has a confinement energy of at least several meV, and an energy barrier to the surrounding matrix of several 100 meV so that confinement effects are visible even at room temperature.

The motivation for the study of quantum dots is to combine the atom-like properties with the flexibility of a solid-state environment. This is perfectly illustrated by considering a quantum dot as the gain medium for a laser. In a conventional semiconductor diode, a band of levels has to be inverted in order to achieve population inversion. This is costly in terms of the threshold current and the temperature stability. In a quantum dot, inversion can be achieved simply by inverting the population of the two-fold degenerate ground state, which is clearly trivial. Furthermore, a strong confinement energy and a large barrier to the surrounding matrix imply that this population inversion is stable against rises in temperature, implying better room-temperature performance. This example also exemplifies the motivation for investigating quantum dots using well-developed inorganic semiconductor technology as in this case the dots can be integrated into established device geometries. Generally speaking, the important concept in quantum dot physics is spatial confinement of electrons in all three directions, giving rise to discrete energy levels.

Lithography for Quantum Dots

Developments in semiconductor growth technology, largely during the 1970s and 1980s, enabled thin layers of different semiconductors to be grown on top of each other. There are two principal growth techniques, molecular beam epitaxy (MBE), in which a heated substrate is bombarded with pure species in a high vacuum, and metal organic chemical vapor deposition (MOCVD), in which chemical precursors flow over a heated substrate and react. In the simplest structure, termed a quantum well, a thin layer of low-bandgap material is sandwiched between high-bandgap material. The discontinuities in the potentials at the interface give rise to confined electronic states for both carrier types, electrons and holes. The quantum well is an example of a two-dimensional system: there is confinement in one direction, the growth direction, but free dispersion in the other two directions. To make a quantum dot, it is necessary to confine the electron and hole in all three directions. An obvious approach is to take a quantum well, with perfect confinement in one direction, and process it laterally with lithographic techniques to complete the quantization. Note that an analogy can be made to the physics of the quantum Hall effect, where a two-dimensional electron gas is subjected to a very high magnetic field. The magnetic field quantizes the lateral motion in a similar way to the electrostatic potential in a quantum dot.

This approach to the formation of optically active quantum dots obviously has some advantages, notably that the shape and position of the quantum dots can be chosen in the lithography. However, there are some significant problems associated with these techniques. As most of these problems do not plague the properties of self-assembled quantum dots, self-assembled quantum dots are more suitable for advanced photonic devices.

A number of different lithographic techniques has been used to process quantum-well heterostructures into quantum dots. For research applications, electron-beam lithography is the method of choice. The sample is coated with a resist, for instance PMMA, and exposed with electrons in an area with nanometer size. A protective layer, either a metal or insulator, is transferred to the exposed area by developing the resist, by depositing the protective layer material, and by removing the unwanted material with a lift-off step. The wafer is then etched, typically in a dry environment, to produce a free-standing column.

The photoluminescence of these quantum dots has been measured by various research groups, and although the results vary quite widely there are some systematic trends. The photoluminescence efficiency decreases rapidly for pillars smaller than a few microns. This is somewhat improved at low temperature, where reasonably strong emission can be observed down to 100-nm diameter pillars. For pillars with micron diameters, the lateral confinement effects are weak, and it is debatable if true quantum dots have been achieved. There are a number of effects which degrade the emission. First, pinning of the Fermi energy by surface states generates large electric fields near the surface, which can ionize electron–hole pairs. This is well known for quantum wells: if a GaAs quantum well for example is placed less than about 25 nm from the surface, the photoluminescence is very weak because of the surface electric field. In an etched pillar, these effects are clearly magnified by the new surface area generated. Secondly, the etching process damages the material to a greater or lesser degree, and the damaged region contains centers for nonradiative recombination.

Other lithography techniques have also been used to generate semiconductor quantum dots for optical experiments. An elegant idea is to deposit small regions of a highly strained film onto the sample surface. In this way, a laterally varying strain film in an underlying quantum well can be set up, generating quantum dots through the effect of strain on the band gap. (This idea has also been married with self-assembly, by using Stranski–Krastanow-grown InP stressors on a GaAs surface, generating lateral confinement in an underlying InGaAs quantum well.) A further idea is to generate a quantum dot by deliberately growing a quantum well with rough interfaces. In such a system, there will inevitably be regions which confine an electron–hole pair through localization. Both of these approaches clearly circumvent the problems generated by the exposed surface in an etched quantum dot. However, they generate small lateral confinement potentials, typically a few meV. This is of value in a research environment where fundamental experiments can be carried out at low temperature, but in a possible device at room temperature, where the thermal energy is 25 meV, quantization effects will not be discernible.

Self-Assembled Quantum Dots

A solution to the difficulties inherent in quantum dots made by lithographic techniques began to emerge in the early 1990s. It was discovered that quantum dots can be produced directly in the semiconductor growth by depositing a material onto a substrate with a substantially smaller lattice constant. The most well-known example is the growth of InAs (lattice constant 6.05 Å) on GaAs (lattice constant 5.65 Å) where In-rich quantum dots form. Because billions of dots form spontaneously in this process, the dots are referred to as self-assembled quantum dots. Since the early experiments, considerable progress has been made, such that the state-of-the-art quantum dots possess many of the hoped-for properties: they are coherent (meaning that they contain no dislocations), highly homogeneous (meaning that fluctuations in shape and composition from dot to dot are small), and have large quantum efficiencies for the emission of light.

Growth of Self-Assembled Quantum Dots

When growing one material on top of another, three principal growth mechanisms have been identified: Frank–van der Merwe, Volmer–Weber, and Stranski–Krastanov. In the Frank–van der Merwe mode, material is deposited layer by layer, as in the growth of the lattice-matched pair GaAs and AlAs. In the Volmer–Weber mode, island formation occurs: the material does not wet the surface because it is energetically unfavorable. Another possibility arises if there is a lattice mismatch. In this case, the epilayer is strained, and the strain energy obviously increases with increasing epilayer thickness. In the Stranski–Krastanow mode, the initial growth is layer by layer, as in Frank–van der Merwe, but beyond a certain thickness, islands form, as shown schematically in Figure 1. On the one hand, the islands limit the strain energy, because some strain relaxation is allowed, which is not possible in a thin film. On the other hand, island formation results in an increase of the



Figure 1 A schematic of the Stranski–Krastanow mode. The material deposited has a substantially larger lattice constant than the substrate, for example InAs on GaAs. Initially, a thin and uniform layer is deposited. At the critical thickness (1.5 monolayers for InAs on GaAs), islands spontaneously form. Further growth results in an increase in the number of islands. At large coverages, large and dislocated islands appear.



Figure 2 An atomic force micrograph of InAs quantum dots on a GaAs substrate. The InAs dots were grown by MBE at a growth temperature of 530 °C. The image was taken by Axel Lorke.

surface energy. This means that there is a size at which the total energy is minimized.

It is now well established that many combinations of semiconductors grow in the Stranski–Krastanow mode, and this can be utilized for self-assembly of quantum dots. The most studied example is InAs on GaAs where high-quality quantum dots can be grown with both MBE and MOCVD. Dots form at the so-called critical thickness of 1.5 monolayers, corresponding to just 4 Å of material. For thicknesses less than the critical thickness, the covering is not completely uniform; there are island-like structures, elongated along the $[0\bar{1}1]$ direction. At the critical thickness dots form, leaving a thin InAs layer (the wetting layer) between the dots. As more InAs is added, the density of dots increases with only small changes in the dot size. As an example, Figure 2 shows InAs dots on a GaAs substrate.

The dots grown in this Stranski–Krastanow mode are free of dislocations, which is an essential prerequisite in III–V compounds for a high quantum efficiency for optical emission. Furthermore, the dots are remarkably homogeneous. Statistical fluctuations during growth will always give rise to a distribution in dot size and height. Nevertheless, the fluctuations in dot size can be as small as ~10%. The dots are randomly arranged in the lateral plane if the growth proceeds on a flat substrate, and densities are between 10^9 and 10^{11} cm^{-2}. The shape and composition of the dots depend on the growth parameters. For instance, InAs/GaAs dots can have facets along particular crystal directions, or they can be lens-shaped without facets, depending on the growth technique, and in particular the growth temperature. In fact, measuring the shape and composition is a very challenging task, particularly for buried dots.

Stranski–Krastanow growth has turned out to be a robust phenomenon for III–V materials; quantum dots have been produced in this way for a number of material combinations. The most important condition is that the deposited material has a substantially larger lattice constant than the substrate. InAs forms dots not just on GaAs but also on InP. The InAs/InP dots are particularly interesting because they emit at the technologically important 1.5 µm wavelength. InP can also form the dot material by using GaInP substrates where the bandgap is pushed up into the red region of the spectrum. Dots can also be grown with II–VI materials; the growth of CdSe on ZnSe is analogous to the growth of InAs on GaAs. These II–VI dots emit in the green. Finally, dots can also be formed in the nitrides, for instance by depositing InGaN on an AlGaN surface. In fact, the high emission efficiency of GaN, despite the large defect density, has been attributed to the formation of quantum dot-like structures in the active layers.

It is a challenge to arrange the dots in the plane of the substrate. An easy route with self-assembly has not been found to accomplish this. Nevertheless, dots can be encouraged to grow at particular positions by pre-patterning the substrate. This obviously limits the separation of the dots in any such array to the limits set by lithography. However, self-assembly does provide a means to order the dots in the growth direction: if the separation between successive layers is small enough (less than 15 nm for InAs/GaAs) then the dots grow directly above one another, as shown in Figure 3. In a new layer, the residual strain field from the dots in the layer below is sufficient to seed the dots. In this way, vertical stacks of dots can be built up. In fact, it has been argued that the dots tend to become more laterally ordered with each layer. The point is that if two dots are close together in one layer, their strain fields overlap, and provide only one seeding center in the subsequent layer.

Optical Properties

The main interest in quantum dot physics is the quantization in all three spatial directions, giving rise to atomic-like energy levels. For a system of self-assembled quantum dots, it is important to measure the fundamental bandgap, the energetic separation between the confined states both for electrons and for holes, the barriers to the electron continuum and hole continuum, and the oscillator strengths for the various interband transitions. All this information can be gleaned with optical spectroscopy.

Perhaps the simplest experiment to perform, if not to understand, is photoluminescence in which electron–hole pairs are excited with a laser beam.



Figure 3 A transmission electron micrograph of two layers of InAs quantum dots in GaAs showing how the dots in the upper layer lie directly above the dots in the first. The image was taken by Gio Medeiros-Ribeiro.

The laser energy can be tuned to lie just above the bandgap of the wetting layer in which case the electron–hole pairs are excited in the wetting layer itself. Alternatively, if the laser energy is larger than the bandgap of the barrier material, electron–hole pairs are excited in the barrier. In both cases, the carriers relax into the dots, and then down the ladder of states in the dot, so that the dot electron and hole ground states are occupied. Emission is detected when an electron and a hole recombine. As such, the experiment measures only the energy of the ground-state exciton. However, if the pump intensity is increased such that electron–hole pairs are generated faster than they can recombine, the excited states of the dots are also occupied and recombination can also occur from excited states. An example of such an experiment is shown in Figure 4. At low pump powers, only the ground state emission is detected; at higher pump powers, the first excited state emerges, and at higher powers still, the second excited state also emerges, and so on. The spectra are broadened by the inhomogeneous broadening, i.e., from fluctuations from dot to dot, but the broadening is small enough that the excited state emission can be easily distinguished from the ground state emission. For these particular quantum dots, the energetic separation between the ground and excited state emission is 15 meV, and this corresponds to the sum of the electron and hole confinement energies. The separation between the other emissions is also about 15 meV, implying that the states are approximately equally spaced, implying in turn that the confining potential is approximately parabolic. Furthermore, in this experiment, emission from the wetting layer can also be made out, and this enables the electron and hole confining potentials to be estimated.



Figure 4 Photoluminescence from an ensemble of quantum dots as a function of laser excitation power. The measurement temperature was 12 K. The quantum dots are induced in an InGaAs/GaAs quantum well by a strain field generated by InP stressors on the sample surface. The stressors are grown in the Stranski–Krastanow mode, and are 1 nm away from the quantum well. At low excitation power, only the ground state emission is observed. As the power increases, emission from excited states is also observed through state filling. Reprinted with permission from Lipsanen H, Sopanen M and Ahopelto J (1995) Luminescence from excited states in strain-induced $In_xGa_{1-x}As$ quantum dots. *Physical Review* 51: 13868. Copyright 1995 American Physical Society.

Photoluminescence invariably yields the sum of electron and hole energies. In order to measure just the electronic properties, it is possible to occupy the dots with, say, two electrons (so that in each dot the two-fold degenerate ground state is fully occupied) and to excite electric dipole transitions between the electron levels. This has been accomplished with so-called charge-tunable heterostructures, with which electrons can be controllably loaded into the dots from an electron reservoir. The interlevel absorption lies in the far-infrared region of the spectrum; for InAs/GaAs quantum dots for instance, the transition is at a wavelength of 25 μm (an energy of 50 meV), as shown in Figure 5. The results of this experiment also point to an approximately parabolic confining potential from the fact that as electrons are added to the dots, the energy of the far-infrared absorption does not change much. (In the limit of a perfect parabolic potential, a famous result known as Kohn's theorem states that the long-wavelength absorption should show no energy dependence on the electron occupation.)

In self-assembled quantum dots, the confining potential can be thought of as very steep in the growth direction, and relatively shallow in the lateral plane. In other words, the dots are essentially two-dimensional disks. The electron ground state is, in analogy with atomic physics, s-like, and the excited state p-like. However, because of the disk-like nature of the dots, the p-state is four-fold degenerate, and not six-fold degenerate as in a conventional atom. One way to demonstrate this is to perform interband absorption experiments on charge-tunable structures, as shown in Figure 6. The first transition corresponds to the transition from the hole s-state to the electron s-state, and disappears when the dots are occupied with two electrons. This is simply because the Pauli principle forbids the transition once the final level is fully occupied. The second transition corresponds to the transition from the hole p-state to the electron p-state, and disappears when the dots are occupied with four electrons, confirming the degeneracies of



Figure 5 Transmission in the far infrared of an ensemble of InAs/GaAs quantum dots where each quantum dot is occupied with two electrons. The data were taken at a temperature of 4.2 K. The shaded transmission minima correspond to absorption from the quantum dots. The transitions are between the electron ground state and the first excited state. Two peaks are observed even at zero magnetic field, suggesting that the dots are slightly oval in shape. In a magnetic field, the two peaks move apart, which is a consequence of the Zeeman effect. The strong feature at 45 meV arises from an electronic interaction with an interface phonon. Reprinted with permission from Fricke M, Lorke A, Kotthaus JP, Medeiros-Ribeiro G and Petroff PM (1996) Shell structure and electron-electron interaction in self-assembled InAs quantum dots. *Europhysics Letters* 36: 197. Copyright 1996 European Physical Society.



Figure 6 Transmission in the near infrared of an ensemble of InAs/GaAs quantum dots at 4.2 K. Spectra are shown for different values of N, the electron occupation. At $N = 0$, there are three transitions corresponding to transitions from a valence state to an electron state. These are the s–s, p–p and d–d transitions, where the states are labeled in analogy to atomic physics. At $N = 2$, the electron ground state is fully occupied, and the s–s transition disappears because it is blocked, a consequence of the Pauli principle. Similarly, the p–p transition is blocked at $N = 6$ when both the electronic s and p states are fully occupied. Reprinted with permission from Warburton RJ, Dürr CS, Karrai K *et al.* (1997) Charged excitons in self-assembled semiconductor quantum dots. *Physical Review Letters* 79: 5282. Copyright 1997 American Physical Society.

the confined states. This experiment, unlike a photoluminescence experiment, also yields a value for the oscillator strength. The result can be understood simply in terms of the overlap integral between the hole and electron states. In other words, these dots are in the strong confinement regime where the confinement energies are larger than the exciton binding energy. In the other limit, the weak confinement regime, the exciton binding energy dominates over the confinement energies, and it makes sense only in this limit to think of an exciton moving as a coherent entity throughout the dot. In the weak confinement regime, the oscillator strength is actually larger than in the strong confinement regime.

An important issue in interpreting photoluminescence experiments is the rate at which a highly excited electron–hole pair can relax to the ground state of a quantum dot. Relaxation in the continuum is known to occur on a picosecond time-scale: electrons and holes relax by emitting LO-phonons if possible; and if not, acoustic phonons. Capture by a dot also occurs quickly (apart from in low-density samples where capture may take a few hundred picoseconds). It was initially thought that relaxation of carriers once captured by a quantum dot would be hindered by the discrete nature of the density of states. The argument is that the energy separation between the levels is too large for acoustic phonon emission; and there is no reason why the separation between the levels should match the LO-phonon energy (which has a very weak dispersion). Nonetheless, experiments have shown that relaxation from excited dot states to the ground state is rapid, occurring on a picosecond time-scale, pretty much as for quantum wells. Auger processes can be important, whereby an electron in a dot loses energy by promoting an electron in the continuum to a higher energy. But relaxation can also be fast without a large population of mobile carriers in the wetting layer, and this is thought to arise through multiphonon processes. The radiative lifetime is typically 1 ns for self-assembled quantum dots, depending to some extent on the size and material system. As for quantum wells, relaxation occurs much faster than recombination.

Lasers and Self-Assembled Quantum Dots

The motivation for using quantum dots as the gain medium for semiconductor lasers is that they should have advantageous properties over quantum wells. These include a lower threshold current, better temperature stability, and a higher modulation frequency. All of these possible advantages stem from the quantization. In a quantum dot, there are discrete levels each with low degeneracy so that population inversion is easy to achieve. Also, there are large potential barriers to the continuum of states in the surrounding matrix, and an energy separation between levels in the dot at least comparable to the thermal energy at room temperature. This should make a quantum dot device relatively insensitive to temperature. The threshold current of a semiconductor laser usually behaves as $I = I_0 e^{T/T_0}$ where T is the temperature, T_0 is the characteristic temperature, and I_0 the low-temperature threshold current. Generally speaking, lasers are desirable with a small I_0 and a large T_0.

The main obstacle to realizing the benefits of full spatial confinement in self-assembled quantum dots is the inhomogeneity. For a particular lasing wavelength only a fraction of the dots can contribute to the lasing signal. Additionally, the dot densities are typically about 10^{11} cm^{-2} for these applications, implying that in the layer plane there is more unoccupied space than dot material. All in all, the gain at a particular wavelength is limited. Nevertheless, it would appear that even with inhomogeneous dot ensembles the advantages inherent in zero-dimensional states can be exploited.

In addition to the density of states, there is an important difference in the nature of the gain spectrum between quantum well and quantum dot lasers. In a quantum well, gain exists over a range of energies through band filling. If an electron–hole pair is stimulated to emit by the lasing field, then the vacancies will be quickly filled by carrier–carrier scattering in the bands, maintaining a quasi-thermal equilibrium in the conduction and valence bands. In quantum dots at low temperature, capture into a particular dot is a random process, and given the rapid relaxation and the high barriers to the continuum, an electron–hole pair is very likely to emit from the dot where it was created. In other words, the system is not in thermal equilibrium. At higher temperatures, thermal escape out of the dots becomes likely, enabling the system to come into thermal equilibrium. The transition into thermal equilibrium will depend critically on the barrier height, and with appropriate design may take place close to, or even above, room temperature.

Quantum dot lasers have now been realized, and emit continuous wave at room temperature. Progress has been rapid in the past few years. In fact the best quantum dot lasers now have the lowest I_0 and the highest T_0 of any semiconductor laser diode.

Even if the intrinsic advantages of quantum dots are largely offset by the inhomogeneous broadening for laser applications, there are some other advantages. The InAs/GaAs quantum dot emission wavelength is significantly higher than that of InGaAs/GaAs quantum wells, and with subtle changes in the growth can be increased to 1.3 μm, corresponding to one of the low-loss windows in optical fiber. Also, much higher powers have been realized with quantum dot lasers than with quantum well lasers. In quantum well lasers, device failure occurs at high current, often due to degradation of the end mirrors. It would appear that the carrier localization in quantum dots is sufficiently strong to prevent diffusion to the end facets, allowing the devices to withstand higher currents.

Colloidal Quantum Dots

Progress has been made recently in making inorganic quantum dots with techniques from organic chemistry. Organometallic precursors are employed. The growth temperature is typically below 200 °C which has been found to give material with quite high crystalline quality. A crucial development has been the use of various organic groups to passivate the surface so that the quantum dots have bright photoluminescence. The II–VIs, being more polar than the III–Vs, are easier to produce with these techniques, and most work has concentrated on CdS and CdSe quantum dots which emit in the visible. Nevertheless, it is also possible to produce III–V quantum dots with this technology, and although the bulk GaAs bandgap lies in the near-infrared, the quantum confinement effects can be so high as to push the photoluminescence into the visible. Furthermore, HgCdTe has also been developed as a material system for quantum dots, and the emission can be tuned to the all-important 1.5 μm.

The spectral width of emission from these colloidal quantum dots tends to be very large because of a large spread in particle size. However, techniques are being developed to isolate a specific size. With a selective precipitation technique for instance, the spectral width can be reduced considerably to the extent that a fine structure can be observed in the optical response.

The advantage of these quantum dots lies in the possibility of mass-production for applications such as solar cells. The ease with which one material system can be used to cover a large spectral bandwidth is already attracting a lot of interest, for instance in using passivated and water-soluble quantum dots as biological labels. By using different materials, a huge spectral range can be covered with this technology, as illustrated in Figure 7. Of course, there are still challenges to be met in this field. The quantum dots tend to degrade in the course of time, losing their high quantum efficiency for emission, presumably as a result of changes to the surface structure. Improvements have been made recently by capping the dots with a high-bandgap semiconductor, such as ZnS, which hinders interactions of the exciton with the surface states. The emission from organic-based dots also tends to show temporal fluctuations in wavelength, revealed experimentally from the emission of a single dot. This is thought to come about through the charging and discharging of traps in the vicinity of the quantum dot. Fundamentally, there are difficulties injecting carriers across an interface into the colloidal dots. However, progress can be expected in all these areas, and these quantum dots may well find applications in novel photonic devices.



Figure 7 Room temperature emission spectra of surfactant-coated colloidal quantum dots. The quantum dots consist of InAs (left), InP (middle), and CdSe (right). Selection of the size has been used to give a particular wavelength in each band. Reprinted (abstracted/excerpted) with permission from Bruchez M Jr, Moronne M, Gin P, Weiss S and Alivisatos AP (1998) Semiconductor nanocrystals as fluorescent biological labels. *Science* 281: 2013. Copyright 1998 American Association for the Advancement of Science.

Single-Dot Spectroscopy

No matter how quantum dots are prepared, there is always a distribution in emission energy. This constitutes an inhomogeneous broadening mechanism. For self-assembled InAs dots on GaAs, the lowest emission width from an ensemble of dots is about 20 meV. This energy is large compared to several other energies in the system. For example, the binding energy of a charged exciton, or of an exciton–exciton complex (a biexciton), is about 2 meV in this system. Also, the width of single dot emission is two to three orders of magnitude smaller than the ensemble width at low temperature. The width of single-dot emission is inversely related to the time over which the exciton maintains its coherence, and this should be as long as possible for future applications of quantum dots which manipulate the phase of the excitonic wavefunction. In order to investigate the properties of quantum dots in detail it is clearly necessary to measure the optical response of a single quantum dot rather than the response of a large ensemble of dots. The development of this field has been aided by the techniques developed for single-molecule spectroscopy which was first reported in the late 1980s and has subsequently become almost a standard experimental technique.

Typical densities of self-assembled quantum dots correspond to 100 per μm^2. Given that the emission wavelength is around 1 μm, it is clear that an optical technique with subwavelength spatial resolution is required to excite and detect a signal from just one quantum dot. The techniques employed include cathodoluminescence, where a focused electron beam provides the spatial resolution, and near-field optics where a subwavelength-sized aperture in a metal mask determines the spatial resolution. In the latter case, the aperture is either permanently connected to the sample surface, or it is formed on a tapered optical fiber positioned just a few nanometers away from the sample surface. An example is shown in Figure 8: with a confocal microscope the spatial resolution is not high enough to isolate spectroscopically a single dot. With increased spectral resolution, however, just a small number of peaks remain, each corresponding to the emission from a single dot. A further technique is to etch nanometer-sized mesas in the sample such that each mesa contains on average just one quantum dot. In some cases, single quantum dot emission has been detected with a conventional optical microscope (usually a confocal microscope) by adjusting the growth conditions to give particularly low dot densities. This can be achieved with colloidal nanocrystals by spinning a dilute suspension of the dots onto a substrate, a technique which has been frequently used in single-molecule spectroscopy. In each case, the photoluminescence signal from a single quantum dot is not large, and a detector capable of counting individual photons with a high quantum efficiency is required. A cooled silicon CCD camera is very convenient, giving not only a very low dark count and high quantum efficiency, but also a huge multiplexing advantage. However, the response of a Si detector tails off in the visible, and decreases rapidly at about 1050 nm in the near infrared, so it is by no means a universal solution.

The most striking feature of the emission from a single inorganic quantum dot is its spectral purity. Linewidths as small as a few μeV (a few hundred MHz) have been reported at low temperature for



Figure 8 Emission from quantum rings from a 1 μm^2 area of the sample, and from a 0.07 μm^2 area of the sample, both taken at 4.2 K. The quantum rings are generated with a Stranski–Krastanow growth procedure using InAs and GaAs. The first spectrum was taken with a low-temperature confocal microscope; the second with a near-field technique. It can be seen how large statistical fluctuations arise in the first spectrum, because the number of rings probed is not sufficient to give a smooth distribution function. In the second spectrum, just a few peaks can be discerned above the noise level, each arising from the emission from an individual quantum ring.

quantum dots formed in a localizing potential in a quantum well. These linewidths can be interpreted as de-phasing times of the excitons. The maximum possible de-phasing time is obviously the radiative lifetime, in which case the line is homogeneously broadened. This limit has been observed at low temperature on natural quantum dots, but not at elevated temperature: as the temperature increases, scattering of the excitons by phonons decreases the coherence time, observed through a broadening of the emission.

The sharp lines observed in single-dot spectroscopy give access to fine structure on a meV energy scale. Most of this fine structure arises through Coulomb interactions between the electrons and holes. For example, two recent experiments have explored the emission as a function of electron occupation, and exciton population. In both cases, new lines emerge when a single dot is populated by more than one electron–hole pair.

Perspectives

The field of semiconductor quantum dots has made rapid advances in the past decade largely through the discovery of self-assembly in the growth of lattice-mismatched inorganic semiconductors. The most immediate application of these defect-free nanostructures is as the gain medium for semiconductor laser diodes, the aim being to reduce the threshold currents beyond those achievable with quantum wells. This approach is already proving highly successful. However, there are also other possibilities for novel photonic applications of quantum dots. These include memory elements for image processing, detectors and sources for single photons, and perhaps even elements for the coherent manipulation of wavefunctions.

See also

Semiconductor Materials: Band Structure Engineering; GaAs Based Compounds. **Semiconductor Physics:** Band Structure and Optical Properties; Excitons; Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures; Recombination Processes.

Further Reading

Bayer M, Stern O, Hawrylak P, Fafard S and Forchel A (2000) Hidden symmetries in the energy levels of excitonic artificial atoms. *Nature* 405: 923.

Bimberg D, Grundmann M and Ledentsov NN (1998) *Quantum Dot Heterostructures*. Chichester, UK: Wiley.

Bruchez M, Jr, Moronne M, Gin P, Weiss S and Alivisatos AP (1998) Semiconductor nanocrystals as fluorescent biological labels. *Science* 281: 2013.

Empedocles SA and Bawendi MG (1997) Quantum-confined Stark effect in single CdSe nanocrystalline quantum dots. *Science* 278: 2114.

Fricke M, Lorke A, Kotthaus JP, Medeiros-Ribeiro G and Petroff PM (1996) Shell structure and electron–electron interaction in self-assembled InAs quantum dots. *Europhysics Letters* 36: 197.

Gaponenko SV (1998) *Optical Properties of Semiconductor Nanocrystals*. Cambridge, UK: Cambridge University Press.

Leonard D, Pond K and Petroff PM (1994) Critical layer thickness for self-assembled InAs islands on GaAs. *Physical Review B* 50: 11687.

Lipsanen H, Sopanen M and Ahopelto J (1995) Luminescence from excited states in strain-induced $In_xGa_{1-x}As$ quantum dots. *Physical Review B* 51: 13868.

Tersoff J, Teichert C and Lagally MG (1996) Self-organization in growth of quantum dot superlattices. *Physical Review Letters* 76: 1675.

Warburton RJ, Dürr CS, Karrai K, *et al.* (1997) Charged excitons in self-assembled semiconductor quantum dots. *Physical Review Letters* 79: 5282.

Warburton RJ, Schäflein C, Haft D, *et al.* (2000) Optical emission from a charge-tunable quantum ring. *Nature* 405: 926.

Weisbuch C and Vinter B (1991) *Quantum Semiconductor Structures*. San Diego, CA: Academic Press.

Xie Q, Madhukar A, Chen P and Kobayashi NP (1995) Vertically self-organized InAs quantum box islands on GaAs(100). *Physical Review Letters* 75: 2542.

Type-II Quantum Wells and Superlattices

I Vurgaftman and J R Meyer, Naval Research Laboratory, Washington, DC, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

When thin layers of two semiconductor materials are combined to form a heterojunction, quantum well (QW), or superlattice, the properties of the resulting 'quantum heterostructure' are to a large extent governed by the alignment of the conduction and valence bands at the interfaces. Usually the overall conduction-band (CB) minimum lies in the same material as the overall valence-band (VB) maximum, as for example in the $GaAs/Al_{0.3}Ga_{0.7}As$ QW illustrated in Figure 1a. In such a type-I structure,



Figure 1 Conduction band (CB) and valence band (VB) profiles along with selected sub-band energies and wavefunctions for: (a) 50 Å $GaAs/Al_{0.3}Ga_{0.7}As$ type-I quantum well (GaAs substrate); (b) 50 Å/50 Å $Ga_{0.47}In_{0.53}As/GaAs_{0.5}Sb$ type-II staggered-gap superlattice (InP substrate); (c) 100 Å/100 Å InAs/GaSb type-II broken-gap semimetallic superlattice (GaSb substrate); (d) 50 Å/50 Å GaAs/AlAs type-I superlattice (GaAs substrate); (e) 20 Å/50 Å GaAs/AlAs type-II superlattice with indirect band alignment both in real and momentum spaces; and (f) 30 Å/30 Å InAs/GaSb type-II semiconducting superlattice. E1, H1, and X1 represent the first sub-band in the Γ-valley conduction band, Γ-valley valence band, and X-valley conduction band, respectively. The overlap between the electron and hole wavefunctions is shown in gray.

the electrons and holes both reside mostly in the GaAs and their wavefunctions overlap almost perfectly as shown in the figure.

There are cases, however, when the CB minimum is in one layer while the VB maximum is in the other. For this so-called type-II alignment, which is exemplified by the $Ga_{0.47}In_{0.53}As/GaAs_{0.5}Sb_{0.5}$ superlattice of Figure 1b, the electrons and holes tend to separate spatially. It should not be surprising that this significantly influences many of the basic optical and electronic properties. Just one example is the band-edge absorption, whose strength is proportional to the square of the wavefunction overlap integral.

In contrast to the staggered type-II heterostructure of Figure 1b, another possibility is the broken-gap type-II alignment of the InAs/GaSb superlattice shown in Figure 1c. Since the CB minimum in InAs actually lies below the VB maximum in GaSb, this combination becomes a semimetal even though the bulk constituents are both semiconductors.

The nature of the band alignment can also be strongly influenced by shifts of the electron and hole energy levels induced by quantum confinement. Figure 1d illustrates a type-I GaAs/AlAs superlattice with relatively thick GaAs layers. Notice that the same superlattice becomes type-II if, as in Figure 1e, the GaAs layers are thin enough that the GaAs Γ-valley electron level (center of the Brillouin zone) is pushed to a higher energy than the AlAs X-valley level (boundary of the Brillouin zone). Similarly, quantum confinement can turn the broken-gap (semimetallic) type-II InAs/GaSb superlattice of Figure 1c into a staggered (semiconducting) type-II superlattice as in Figure 1f.

Although many different type-II heterostructures have been identified over the last three decades, only a few are likely to have long-term technological importance for optics or electronics. The system that has received the most attention in terms of both fundamental scientific studies and opto-electronic device development is InAs/GaSb and related alloy combinations such as InAs/GaInSb. Following a brief overview of wider-gap type-II heterostructures, this article will concentrate primarily on that interesting narrow-gap system.

Wide-Gap Type-II Heterostructures

The best-known wide-gap type-II heterostructure is the GaAs/AlAs superlattice of Figure 1e. The band lineup is type-II provided the GaAs thickness is no greater than ≈10 monolayers (28 Å) and the AlAs layer is no thinner than the GaAs layer. Since the CB minimum is in the AlAs X-valley and the VB maximum is in the GaAs Γ-valley, this structure has an indirect energy gap in both real space and momentum space. In type-II GaAs/AlAs, the X-valley states at the CB minimum form one or more superlattice minibands, which display relatively low resistance at small biases, negative differential velocity, etc. A related structure is the GaAs/AlAs/GaAs/AlAs/GaAs double-barrier intervalley resonant tunneling diode, in which resonant or sequential phonon-assisted tunneling proceeds via intervalley transitions whenever the Fermi level in the GaAs emitter lines up with the X-valley minimum in AlAs. Structures containing AlGaAs do not necessarily need quantum confinement to establish a type-II alignment, since it occurs naturally in $Al_xGa_{1-x}As$/AlAs heterojunctions with $x > 0.3$.

The device potential of wide-gap type-II heterostructures is rather limited, owing to their low luminescence efficiencies (due in large part to the doubly indirect band alignment) and low mobilities (due to the heavy X-valley effective mass). A few proposals have focused on modulation of the band alignment between the type-I and type-II regimes. The $Ga_{0.47}In_{0.53}As/GaAs_{0.5}Sb_{0.5}$ superlattices of Figure 1b and related structures have been investigated as alternative active regions for semiconductor lasers emitting in the important 1.3–2 μm wavelength range.

InAs/GaSb/AlSb-Based Type-II Superlattices and Quantum Wells

Molecular beam epitaxy (MBE) was used to fabricate the first InAs/GaSb-based superlattices in 1977, only a few years after the initial GaAs/AlGaAs superlattice growths. It was quickly demonstrated that for relatively thick layers the band alignment is broken-gap type-II, with 100–150 meV overlap between the conduction band minimum in InAs and the valence band maximum in GaSb. In this semimetallic superlattice, GaSb valence-band electrons spill over into the InAs and leave behind holes (see Figure 1c). It was also observed that at equal layer thicknesses of ≈90 Å quantum confinement induces a semimetal-to-semiconductor transition (Figure 1f), and that the gap becomes increasingly positive when the thickness is reduced further. This is no mere scientific curiosity, since being able to tune in a wide range of energy gaps spanning 0 to >0.5 eV has enormous practical consequences for infrared (IR) emitters and detectors. Such a capability cannot be replicated by any other III–V heterostructure system.

Another happy accident is that the lattice constants of InAs (6.058 Å) and GaSb (6.096 Å) are matched closely enough to allow them to be grown together by MBE or metalorganic chemical vapor deposition (MOCVD). A third binary member of the 'antimonide' or '6.1-Å' family of growth-compatible heterostructures is AlSb (6.136 Å), which is valuable in that it serves as a quantum barrier to both InAs conduction states and GaSb valence states. The extended family includes a variety of ternary alloys (GaInSb, GaAlSb, InAsSb, AlAsSb, etc.), whose energy gaps as a function of lattice constant are given by the curves in Figure 2, and also at least three quaternary alloys: GaInAsSb, AlGaAsSb, and InAlAsSb. Taken together, this menagerie of materials



Figure 2 Direct energy gaps at zero temperature for III–V compound semiconductors and their ternary alloys with lattice constants in the vicinity of 6.1 Å.

provides the type-II IR device designer with an exceptional degree of configurational flexibility.

Type-II IR structures are typically grown on either a GaSb or InAs substrate. Since even a small amount of strain build-up can produce dislocation defects that seriously degrade the performance, one usually balances the net tensile strain (associated with layers having a lattice constant slightly larger than that of the substrate) with a compensating amount of net compressive strain (from layers whose lattice constant is slightly smaller than that of the substrate).

Band structures for complicated type-II layering configurations have been calculated by a variety of methods, including $k{\cdot}p$, tight-binding, and empirical pseudopotentials. While all reproduce the main features of the electron and hole sub-bands and dispersion relations near the center of the Brillouin zone, the relative merits of the different approaches remain controversial. Due to the small energy gaps, band-mixing effects are especially important in this system.

One consequence of the small type-II antimonide energy gap is that the electron and hole bands repel each other and both effective masses can be lighter than in any other III–V semiconductor (e.g., smaller than in the bulk constituents). This leads to high mobilities at room temperature, and promising possibilities for high-electron-mobility transistors (HEMTs). Also of interest are resonant tunneling diodes (RTDs) based on InAs/AlSb/GaSb/AlSb/InAs and related structures, in which interband tunneling via the GaSb valence states results in negative differential resistance with a very high peak-to-valley ratio. Since these devices are primarily electronic rather than optical, we will not discuss them further here.

While interfaces play an important role in any semiconductor heterostructure, they are especially crucial in InAs/GaSb and related type-II systems because the two materials on opposite sides of the interface have neither a common cation nor a common anion (unlike GaAs/AlGaAs, for example, in which both wells and barriers have As anions). By timing the shutter sequences in the growth, one can in principle end the InAs on an In layer and begin the GaSb on Sb, to produce InSb-like interface bonds. Alternatively, one can end the InAs on As and begin the GaSb on Ga to form GaAs-like bonds. Detailed characterizations by a variety of methods have shown that the device properties and even the band structure can be relatively sensitive to whether the interface bonds are InSb-like or GaAs-like.

With regard to opto-electronic devices, a potential limitation of InAs/GaSb superlattices is that in order to reach a long wavelength (small energy gap), the layers must be rather thick (e.g., ≈90 Å for zero gap). In such a structure the overlap between the electron and hole wavefunctions becomes quite small (see Figures 1c and 1f), and consequently the interband optical interactions are weak. However, Mailhiot and Smith pointed out that this issue can be circumvented to a large extent by employing $Ga_{1-x}In_xSb$ (with $x \leq 0.4$) rather than GaSb for the hole QWs. Compressive strain in the GaInSb produces a large splitting of the heavy and light hole sub-bands, along with a substantial increase of the type-II offset energy. The result is that much thinner layers (with large wavefunction overlaps) may be employed in conjunction with energy gaps corresponding to long IR wavelengths. In fact, the overlap for a short-period InAs/GaInSb superlattice such as that illustrated schematically in Figure 3 can be large enough to yield interband optical interaction strengths comparable to those in bulk materials and type-I superlattices.

While practical constraints on the minimum reproducible layer thickness set a lower wavelength limit on the order of 2 μm, the upper limit governed by uniformity considerations is quite high, perhaps in the $\lambda = 25-100$ μm range. This makes type-II antimonide quantum heterostructures a natural choice for mid-IR to far-IR photodetectors and lasers.

Type-II IR Photodetectors

Because IR detectors sense the radiant black-body emission from warm objects rather than relying on reflected visible light, they can be used for 'night vision.' Both photoconductive (PC) and



Figure 3 Conduction and valence band profiles along with electron (E1) and hole (H1) sub-band energies and wavefunctions for a 19 Å/19 Å InAs/$Ga_{0.7}In_{0.3}Sb$ type-II superlattice (GaSb substrate) with an energy gap equal to that of the InAs/GaSb superlattice in Figure 1d.



Figure 4 Temperature dependence of the dynamic impedance at zero bias R_0A for two different InAs/GaInSb superlattice diodes with cutoff wavelengths of 8.7 μm. The generation-recombination (G-R) and diffusion-limited R_0A values are indicated by the dashed lines. Reproduced with permission from Bürkle *et al.* (2000) *MRS Symp. Proc.*, 607, pp. 77–82.

photovoltaic (PV) IR detectors are now being developed with type-II active regions, usually consisting of simple InAs/GaInSb superlattices. The PV geometry, in which a reverse bias is applied to a p–n junction, is ultimately preferred since it is easily adaptable to pixelation in a 2D array with many discrete detector elements. That allows an IR camera to construct a detailed thermal picture of any given scene.

An optimized PV photodetector must have high absorption in the active region, unimpeded vertical transport to assure collection of the photogenerated carriers, and a low dark current. The thin layers of a type-II InAs/GaInSb active region help to satisfy the first two criteria, since they assure both a large wavefunction overlap (Figure 3) and rapid electron and hole tunneling through the superlattice minibands.

The dark current in a high-quality diode tends to be dominated by generation-recombination currents at low temperatures and diffusion currents at higher *T*. However, trap-assisted tunneling via dislocations and other macroscopic defects can significantly increase the dark current. Figure 4 plots the resistance–area product (R_0A) for diodes with and without macroscopic defects. Surface leakage resulting from inadequate sidewall passivation can also lead to a substantial contribution that is proportional to the perimeter of the mesa. The diffusion current scales as $1/\tau^{1/2}$, where τ is the recombination lifetime. To date, the defect-mediated Shockley–Read lifetimes of <100 ns have been significantly shorter than in competing HgCdTe IR materials (>1 μs). However, Auger lifetimes are substantially enhanced, as will be discussed further in the context of type-II IR lasers. In an Auger event, the energy and momentum of the recombining electron–hole pair is transferred to a third carrier, which scatters to a higher-lying state in either the same or a different band. Because three different carriers must interact simultaneously, the recombination rate scales with the cube of the carrier density. Usually Shockley–Read recombination dominates at lower temperatures and Auger processes at higher *T*.

Typically the n-side of a type-II diode is heavily doped (10^{18} cm^{-3} range) and relatively thin, while most of the absorption occurs on the lightly doped (10^{16} cm^{-3} range) p-side. A standard figure of merit is the detectivity (D^*), which is essentially the signal-to-noise ratio in a device of standard size. For 77 K operation, type-II PV detectors with cutoff wavelengths of 7.5 μm and 12 μm achieved D^* of 1×10^{12} cm Hz$^{1/2}$/W and 5×10^{10} cm Hz$^{1/2}$/W, respectively. Those values are nearly as high as typical results for the much more mature HgCdTe FPA technology.

It is anticipated that type-II detectors will be particularly attractive at very long wave IR (VLWIR), at which it becomes increasingly difficult to maintain adequate control over the HgCdTe compositional uniformity. Recent PC detectors operated out to 22 μm, and PV devices to 16 μm. Due in part to the strong suppression of Auger recombination, type-II detectors are also expected to be advantageous at noncryogenic temperatures where future systems will increasingly operate.

Type-II IR Lasers

At visible and near-IR wavelengths out to ≈2 μm, the QW diode laser is by now a mature technology that dominates the commercial marketplace due to its low cost (<$1 per laser in some cases), compactness, and reliability. However, the technical challenges become much more severe in the mid-IR spectral region (3–5 μm). Before the advent of the type-II laser, no interband III–V semiconductor device emitting at $\lambda \geq 3$ μm had ever operated at room temperature. Alternatives are the lead salt laser, which is limited to very low-output powers, and the quantum cascade laser (QCL) that is based on optical transitions between two electron QW sub-bands rather than interband electron–hole processes. Mid-IR lasers are needed for high-power military applications such as IR countermeasures against heat-seeking missiles and for the sensitive detection of trace chemicals using the spectroscopic 'fingerprint' that distinguishes each species from any other.

From the 1960s to the late 1990s, conventional III–V double heterostructure (DH) and type-I QW lasers for the mid-IR never achieved the desired levels of performance because they failed to overcome certain fundamental limitations. Those included:

1. inadequate band offsets, which at higher temperatures made it difficult for the QW or DH active regions to retain the injected electrons and holes;
2. rapid Auger nonradiative decay, which led to excessive threshold current densities at higher temperatures; and
3. restricted spectral range, limited to wavelengths shorter than the cutoff for bulk $InAs_{1-x}Sb_x$.

However, it has more recently become apparent that all of these limitations can be either minimized or removed by employing a type-II InAs/GaSb-based active region.

For example, electrical confinement is far more effective because the GaSb conduction band confines InAs electrons and the InAs valence band confines GaSb holes (see Figure 1f). Auger recombination is also significantly suppressed, in part because the holes are nearly as light in the plane as the electrons, making it much more difficult to conserve both momentum and energy in the three-carrier process. Nearly an order-of-magnitude suppression of the room-temperature Auger rate has been reported, which translates directly into a similar reduction of the threshold current density. And as was discussed above in connection with IR photodetectors, very long wavelengths are readily attainable because the energy gap in a type-II active region can be arbitrarily small. Type-II lasers have already operated cw at $\lambda > 7$ μm, and cryogenic operation out to wavelengths as long as 100 μm has been projected theoretically.

In 1986 the first type-II semiconductor laser, which emitted at $\lambda = 1.86$ μm from single liquid-phase epitaxy (LPE)-grown heterojunctions, was demonstrated. Since the mid-1990s, 3–4 μm GaInAsSb/InAs-based single-interface type-II diodes have been developed that operate up to 205 K in pulsed mode.

In 1995, lasing at $\lambda = 3.2$–3.5 μm was reported from type-II $InAs/Ga_{0.75}In_{0.25}Sb$ superlattice diodes grown by MBE. Subsequent work on these devices extended the temperature range to 255 K in pulsed mode and 180 K for cw operation, and the emission wavelength to 4.3 μm.

While the wavefunction overlap and hence the gain for a two-constituent type-II superlattice active region can be quite favorable, penetration of the electron wavefunctions into the thin GaInSb layers is in fact so great that a wide miniband forms along the growth axis. The electrons then have strong energy dispersion in all three dimensions, whereas present-generation near-IR and visible semiconductor lasers nearly always have QW active regions with 2D carriers. The stepped quasi-2D density of states yields a much higher differential gain per injected carrier at threshold, and also narrower spectral emission lines than are attainable with a 3D electron population. The most straightforward approach to blocking the formation of a miniband in the superlattice is to add a high electron barrier between the periods, e.g., InAs/GaInSb/AlSb. However, the drawback of that approach is that the wavefunction overlap becomes much smaller than in the simple superlattice, resulting in significantly lower gain.

On the other hand, if a second electron well is added on the other side of the hole well, the resulting structure with four constituents per period (e.g., InAs/GaInSb/InAs/AlSb) combines the large wavefunction overlap of the two-constituent superlattice with 2D electron and hole confinement. Figure 5 illustrates band profiles, energy levels, and wavefunctions for the 'W' laser, which takes its name from the shape of the conduction-band profile.

Optically pumped type-II W lasers display high-power pulsed operation at temperatures well above ambient. Wavelengths have spanned the range 2.6–7.3 μm, and mid-IR vertical-cavity surface-emitting lasers (VCSELs) were also fabricated. Optical pumping is viewed primarily as a means of achieving high cw or quasi-cw output powers in the mid-IR, and in that regard W lasers have exceeded all other semiconductor approaches with 1.5 W peak output power being obtained at 71 K for 100 μs



Figure 5 Conduction and valence band profiles along with selected sub-band energies and wavefunctions for InAs/$Ga_{0.7}In_{0.3}Sb$/InAs/AlSb type-II 'W' structure (GaSb substrate). Electron (E1), heavy hole (H1, H2, H3), light hole (L1), and barrier heavy hole (HB) sub-bands are indicated.

pulses with a 10% duty cycle. The average output at 82 K for that device was up to 360 mW for 20 μs pulses and a 50% duty cycle.

Cw operation at $\lambda = 3.0$ μm was observed nearly to room temperature (290 K), and even a 6.1 μm emitter operated cw to 210 K. The cw output power of 540 mW/facet from a device with 80 W QW periods was the highest ever reported for 78 K operation in the mid-IR. Despite the rather high output power, however, the differential power conversion efficiency was only 2.5% at 78 K and fell to 1% at 140 K. Much higher efficiencies were obtained using the optical pumping injection cavity (OPIC) approach, in which the active region was surrounded by semiconductor quarter-wave mirror stacks that formed an etalon cavity resonant at the 2.1 μm pump wavelength. For pulsed operation, OPIC devices with uncoated facets and only 10 active QWs yielded lower thresholds, lower internal losses, and higher power conversion efficiencies than any previous results at $T \geq 200$ K. Figure 6 illustrates that the efficiencies were 7.1% at 220 K for one device and 4% at 275 K for another.



Figure 6 Power conversion efficiency per uncoated facet as a function of temperature for two different W-OPIC lasers emitting in the wavelength ranges of 3.1–3.4 μm (filled circles) and 3.4–3.7 μm (filled squares), respectively. For comparison, conversion efficiencies for a typical 'W' laser without an OPIC emitting in the same spectral range (open circles) are also shown. All of the lasers were optically pumped in pulsed mode by a 2.1 μm Ho:YAG laser, and the cavity length for all three devices was 0.5 mm.

An alternative approach to maximizing the pump absorbance despite a small number of QWs is the 'integrated absorber' (IA) concept. In this approach, the W QWs are separated by intermediate-gap GaInAsSb absorbing layers which donate optically generated electrons and holes to the active wells. At 80 K with 35 μs pulses at 2.5% duty cycle, an IA laser with only five QWs separated by ≈1600-Å-thick absorber layers had a power conversion efficiency of 9.8% and peak output power of 2.1 W. Thus far the IA has not done as well as the OPIC at high temperatures, due mostly to an inadequate valence band offset between the absorber layers and the active QWs.

The beam quality for optically pumped type-II lasers was substantially improved by using the angled-grating distributed-feedback (α-DFB) approach pioneered at shorter wavelengths. Since both the grating and the facets are needed to produce optical feedback, only a narrow angular cone is fed back into the tilted cavity. For a pump-stripe width of 50 μm, the near-diffraction-limited output beam had 15 times narrower angular divergence (1.4° full width at half-maximum (FWHM)) than the double-lobed beam emitted from a conventional Fabry–Perot laser occupying an unpatterned portion of the same bar. Even more promising results have been reported using the photonic-crystal distributed-feedback (PCDFB) laser, in which the grating is defined on a two-dimensional rectangular lattice that is tilted with respect to the facets as in the α-DFB. For a pump-stripe width of 200 μm, the beam quality for the direction along the laser stripe was four times the diffraction limit.

Although optical pumping is the simplest way to inject electrons and holes into the active region, type-II diode lasers will ultimately be much more inexpensive, convenient, compact, and energy efficient. However, generalization of the W configuration to electrical pumping is not entirely straightforward. This is because holes injected from the p-type cladding layer may have poor growth-axis transport, and hence hole populations in the various GaInSb QWs could be highly nonuniform. Whereas the holes in a superlattice are required to tunnel through only one InAs electron well at a time (see Figure 3), the barrier for the structure in Figure 5 consists of two InAs layers in addition to the AlSb barrier. To overcome this problem the AlSb was replaced with a specially designed quaternary $Al_{0.15}Ga_{0.85}As_{0.05}Sb_{0.95}$ barrier, which raised the L1 light-hole sub-band to within ≈100 meV of the H1 heavy-hole valence band maximum. That permitted thermally excited light holes to provide the needed tunneling transport to all of the QWs. Another key design element was the insertion of relatively thick (0.6 μm) undoped $Al_{0.35}Ga_{0.65}As_{0.03}Sb_{0.97}$ 'broadened-waveguide' layers on each side of the active region, in order to minimize free-carrier absorption in the doped $Al_{0.9}Ga_{0.1}As_{0.07}Sb_{0.93}$ cladding layers. Some of the devices also contained InAs/AlSb 'hole-blocking' layers, which prevented hole leakage into the n-type broadened waveguide layer.

A pulsed $\lambda = 3.27$ μm W-diode of this type with 10 active QW periods achieved the first room temperature operation (to 310 K) of an electrically pumped III–V interband laser in the mid-IR. Another device with five QWs operated in cw mode to 200 K, the highest $T_{\max}$ to date for any interband III–V laser beyond 3 μm. The threshold at 78 K was 63 A/cm^2, and Figure 7 shows that the cw output was 140 mW at 78 K and 20 mW at 180 K. Following optimization of the turn-on voltages, series resistances, and internal losses, cw diodes with one–three QWs are projected to operate in the thermo-electric cooler range and ultimately at room temperature.

A more exotic variation on the type-II diode emitter is the interband cascade laser (ICL) that was first proposed by RQ Yang. Like the intersub-band QCL, the ICL generates multiple photons per injected electron by making an optical transition at each step of a staircase-like QW structure. While the threshold current density for the QCL is high because of the inherently short lifetimes associated with intersub-band phonon scattering, the interband configuration of the ICL eliminates that nonradiative relaxation path. Early projections that the ICL should display low thresholds, high cw operating temperatures, high output powers, and high differential quantum efficiencies (well above the conventional limit of one photon/electron) have all been confirmed experimentally.



Figure 7 Cw output power as a function of injection current at temperatures between 78 K and 180 K for a 'W' diode laser with a 2-mm-long cavity and 100-μm-wide stripe emitting at a wavelength of 3.3 μm.

Figure 8 illustrates conduction and valence band profiles for a typical single stage of the ICL staircase. While this example employs a W configuration, in which two InAs electron QWs (19 Å and 13 Å) surround the active GaInSb hole QW (32 Å), some designs employ only a single InAs active well. Electrons tunneling into the InAs QWs from the preceding injection region at left emit a photon by making spatially indirect radiative transitions to the GaInSb valence band. They next tunnel into the valence states of the adjacent GaSb and GaInSb hole wells, whose function is to provide a thick barrier to prevent electron leakage from the active InAs QWs directly to the 70 Å InAs well that begins the next injection region. From the final GaInSb hole QW (40 Å), the carriers undergo near-elastic interband scattering into conduction states of the 70 Å InAs QW. Electrons traversing the superlattice miniband of the injection region, which in this case consists of eight digitally graded InAs wells, finally tunnel into the active electron QWs of the next period. This series of events is repeated at each step of the ICL staircase.

Following the first ICL demonstration in 1997, there have been reports of threshold current densities 13 A/cm^2 at 80 K, maximum operating temperatures of up to 300 K for pulsed operation and 150 K for cw (with epitaxial-side-up mounting), pulsed output powers of 6 W/facet and slope quantum efficiencies exceeding 600%. A cw wall plug efficiency of 22%



Figure 8 Conduction and valence band profiles for one period of an interband cascade laser with a W active region and three hole wells. Sub-band energy levels are also indicated.

at 80 K was recently reported. While substantial further improvements are expected, the primary disadvantage of the ICL is its complexity.

Despite numerous dramatic advances by type-II mid-IR lasers since their first demonstration in 1995, the performance has not yet progressed to the level that will be required to support a robust commercial technology. One key issue is the cw operating temperature, which must increase to at least the thermo-electric cooler range if the potential market is to extend beyond niche applications. Higher-temperature operation will result automatically once the number of QWs, and hence the threshold current density, can be reduced. Further suppression of the Auger decay rate would also be highly beneficial if it is proven possible.

The laser output power and efficiency are governed by the internal loss, which in type-II QWs tends to be dominated by resonant free-hole intersub-band transitions. The details of the valence sub-band structure are not well known at present, although recent experiments have apparently identified a number of the transition energies. As in the case of the threshold, reducing the number of QWs is highly beneficial since it reduces the number of free carriers that can absorb the lasing photons. The optically pumped OPIC and IA structures discussed above achieved dramatic reductions in the internal losses by following that strategy.

The beam quality attainable from a semiconductor laser is governed by the linewidth enhancement factor (LEF), which is proportional to the variation in the refractive index induced by a small change in the carrier density. A large positive value of the LEF leads to filamentation in broad-area lasers as tiny peaks in the optical intensity cause carrier depletion and a local increase in the refractive index, which in turn stimulates further focusing of the output beam. The output then consists of an incoherent superposition of many rapidly diverging filaments, resulting in a beam quality that is several orders of magnitude worse than the diffraction limit. While theoretical LEFs for optimized type-II W structures can be in the 1.5–2 range even at room temperature, recent Hakki–Paoli measurements have yielded values in the 2.5–5 range. This is possibly due to additional inhomogeneous broadening of the gain spectrum induced by interface roughness.

See also

Semiconductor Materials: Band Structure Engineering; Quantum Dots. **Semiconductor Physics:** Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures; Recombination Processes.

Further Reading

Mailhiot C and Smith DL (1989) Long-wavelength infrared detectors based on strained InAs-GaInSb type-II superlattices. *Journal of Vacuum Science and Technology* A7: 445–449.

Meyer JR, Malin JI, Vurgaftman I, Hoffman CA and Ram-Mohan LR (1997) Antimonide-based quantum heterostructure devices. In: Manasreh MO (ed.) *Strained*

Quantum Wells and Their Applications, pp. 235–272. Amsterdam, The Netherlands: Gordon and Breach.

Olafsen LJ, Vurgaftman I and Meyer JR (in press) Antimonide mid-IR lasers. In: Choi HK (ed.) *Long-Wavelength Semiconductor Lasers*. New York: Wiley.

Ram-Mohan LR, Vurgaftman I, Meyer JR and Dossa D (2000) Wavefunction engineering: a new paradigm in quantum nanostructure modeling. In: Nalwa HS (ed.) *Handbook of Nanostructured Materials and Nanotechnology*, vol. 2, pp. 707–739. New York: Academic Press.

Razeghi M (1998) Current status and future trends of infrared detectors. *Optoelectronics Review* 6: 155–194.

Vurgaftman I, Felix CL, Aifer EH and Meyer JR (2000) Interband III–V mid-IR semiconductor lasers. In: Perera AGU and Liu HU (eds) *Handbook of Thin Film Devices*, vol. 2, pp. 171–193. San Diego, CA: Academic Press.

Vurgaftman I, Felix CL, Bewley WW, *et al.* (2001) Mid-IR "W" lasers. *Philosophical Transactions of the Royal Society A* 359: 489–504.

Vurgaftman I, Meyer JR and Ram-Mohan LR (2001) Band structure parameters for III–V compound semiconductors and their alloys. *Applied Physics Reviews, Journal of Applied Physics* 89: 5815–5875.

Wilson BA (1988) Carrier dynamics and recombination mechanisms in staggered-alignment heterostructures. *IEEE Journal of Quantum Electronics* 24: 1763–1777.

Yang RQ, Bradshaw JL, Bruno JD, Pham JT and Wortman DE (2002) Mid-IR type-II interband cascade lasers. *IEEE Journal of Quantum Electronics* (Feature Section on Mid-IR Quantum Cascade Lasers) 38: 559–568.

SEMICONDUCTOR PHYSICS

Contents

Outline of Basic Electronic Properties
Band Structure and Optical Properties
Excitons
Impurities and Defects
Infrared Lattice Properties
Light Scattering
Polarons
Quantum Wells and GaAs-Based Structures
Recombination Processes
Spin Transport and Relaxation in Semiconductors; Spintronics
Surface Photovoltage Spectroscopy of Semiconductors

Outline of Basic Electronic Properties

C R Pidgeon, Heriot-Watt University, Edinburgh, UK

© 2005, Elsevier Ltd. All Rights Reserved.

We briefly introduce the main concepts underlying the detailed treatment of specialist aspects of semiconductor physics in ensuing sections, viz: the free electron model, density of states, Fermi-Dirac statistics, energy bands and energy gaps, effective mass, electrons and holes, intrinsic and extrinsic conductivity, direct and indirect interband optical transitions, excitons and low-dimensional systems.

Introduction

A proper treatment of optoelectronic devices needs to include the physical properties of the materials from which the devices are made, and this subject is covered under the section of the Encyclopedia entitled 'Semiconductor Fundamentals'. This includes sections on the basic physics common to all semiconductors useful in optoelectronic applications, the experimental techniques used to investigate the optical properties of these semiconductors and the more detailed properties of the most widely used semiconductors, and semiconductor systems. The properties of greatest importance here are those of electrons in crystalline solids, but the interaction between the electrons and the atoms of the crystal lattice is also significant. The combination of these microscopic effects is responsible for determining the macroscopic optical and electrical properties of semiconductors, and in this section we give the necessary background to these topics.

The classical treatment is extremely useful in describing the electrical conductivity of solids; the electrons are regarded as charged particles obeying Newton's laws of motion, and electrical resistance is assumed to arise from collisions with the vibrating lattice and/or impurities. However, the classical theory does not give a method of predicting the natural frequencies, or energies, of these electronic oscillators. To do this we need to use quantum mechanics, and the elements of this are reviewed here. We start with the free electron theory of metals, where the electrons are treated as particles constrained to move in a potential box. For convenience we begin by considering the situation in one dimension (1D).

Free Electron Theory of Metals

Free electrons in a 1D potential box of length L in the x-direction are described by a plane wave function that is normalized within the box, $\psi = (1/L)e^{ikx}$, and satisfies the Schrödinger equation in the x-direction:

$$\frac{\hbar^2}{2m}\frac{d^2\psi}{dx^2} + E\psi = 0 \qquad [1]$$

where E is the electron energy. This gives the familiar parabolic $E-k$ dispersion relation (see Figure 1), $E = \hbar^2 k^2/2m$ (with electron momentum $p = \hbar k$). In order to evaluate physical problems it is necessary to define the boundary conditions for the wave function. We assume fixed boundary conditions (i.e., $\psi = 0$ at $x = 0, L$) leading to the quantization condition $k = n\pi/L$ where n is a positive integer.

Density of States

Physical properties of solids depend on the number of allowed k-values per unit range of k (or E-values per unit range of E), a quantity referred to as the density of states, D(k) or D(E) – for example, the number of allowed states between k and $k + dk = D(k)dk$. From the fixed boundary condition ($k = n\pi/L$, the number of allowed values of k per unit range of k in 1D is just $D(k) = L/\pi$. In terms of energy, using the $E-k$ dispersion relation, we can write (including the factor 2 for two possible spin states):



Figure 1 Schematic representation of energy bands in one dimension, characterized by gaps at the high symmetry points of the Brillouin zone.

$$\begin{aligned} D(E)dE &= D(k)(dk/dE)dk \\ &= (L/2\pi)(2m/\hbar^2)^{1/2}E^{-1/2}dE \qquad [2] \end{aligned}$$

i.e., the density of states depends on $E^{-1/2}$ for the 1D situation.

For a cube of side L, in three dimensions we generalize the identity for fixed boundary conditions:

$$\frac{L^2k^2}{\pi^2} = n_x^2 + n_y^2 + n_z^2 = R^2 \qquad [3]$$

where $k_x = n_x\pi/L$ etc., and the states fill up the positive quadrant of a sphere of radius ($R = Lk/\pi$) in k-space. Thus, the number of states in a given volume of k-space is numerically equal to that volume, so that the number of states between R and $R + dR$ in the positive quadrant (hence 1/8th) of a spherical shell of radius R in k-space is

$$D(R)dR = 4\pi R^2 dR(1/8) \qquad [4]$$

i.e., (1/8)th of the surface area of the shell multiplied by the thickness of the element. Changing the variable to k, the number of states between k and $k + dk$ is

$$D(k)dk = D(R)\frac{dR}{dk}dk = \frac{V}{2\pi^2}2k^2dk \qquad [5]$$

where the volume $V = L^3$, and a factor of 2 has again been included to account for the two possible spin states of the electron. This in turn, through the relation between E and k, can be expressed in terms of the density of states per unit energy so that the number of states between E and $E + \mathrm{d}E$ is given by:

$$D(E)\mathrm{d}E = D(k)\frac{\mathrm{d}E}{\mathrm{d}k}\mathrm{d}E = \frac{2V}{2\pi^2}\left(\frac{2m^*}{\hbar^2}\right)^{\frac{3}{2}} E^{\frac{1}{2}}\mathrm{d}E \qquad [6]$$

In two dimensions, by the same argument:

$$\frac{L^2k^2}{(\pi)^2} = n_x^2 + n_y^2 = R^2 \qquad [7]$$

Therefore $D(R)\mathrm{d}R = (2\pi R/4)\,\mathrm{d}R$, where the factor 1/4 implies the positive quarter of the 2D ring between R and $R + \mathrm{d}R$ in k-space, $A = L^2$ and

$$D(k)\mathrm{d}k = D(R)\frac{\mathrm{d}R}{\mathrm{d}k}\mathrm{d}k = \frac{A}{\pi}k\mathrm{d}k \qquad [8]$$

From the E–k relation we have the number of states between E and $E + \mathrm{d}E$ as:

$$D(E)\mathrm{d}E = D(k)\frac{\mathrm{d}E}{\mathrm{d}k}\mathrm{d}E = \frac{A}{\pi}\left(\frac{m}{\hbar^2}\right)\mathrm{d}E \qquad [9]$$

Thus, in 2D systems we have the important result that $D(E)$ is a constant.

Fermi-Dirac Distribution of Electrons

At zero temperature an atom exists in what is known as the ground state. All the electrons rest in the lowest energy states allowed to them by the Pauli principle, and fill the allowed states up to an energy known as the Fermi energy, E_F. Above absolute zero of temperature this is no longer the case, and thermal energy allows some electrons to exist in higher energy states. The probability $f(E)$ that a state of energy E will be occupied for an ideal electron gas in thermal equilibrium (thermal energy kT) is governed by Fermi-Dirac statistics:

$$f(E) = \frac{1}{1 + \exp\left(\frac{E - E_\mathrm{F}}{kT}\right)} \qquad [10]$$

For a metal at room temperature the difference between the Fermi energy and the energy of the conduction band minimum is much greater than the thermal energy, $(E_\mathrm{F} - E_\mathrm{co}) \gg kT$; this is also true for a strongly n-type semiconductor (see below) and the distribution is said to be degenerate.

Energy Bands and Energy Gaps: Semiconductors

In the presence of the (perturbing) periodic crystal potential, $V(r)$, the above simplicity is lost: this is the so-called 'nearly free electron model', and the perturbed Schrödinger equation is now:

$$-\frac{\hbar^2}{2m}\frac{\mathrm{d}^2\psi}{\mathrm{d}x^2} + V(x)\psi = E\psi \qquad [11]$$

for the x-direction. This topic is discussed in all undergraduate texts on solid state physics, but we list the main results of the model as follows:

1. The electrons that we are concerned with are confined within a periodic lattice. Consequently the wave function ψ is modulated with the periodicity of the lattice. By symmetry arguments the correct wave function can be shown to be:

   $$\psi_k(x) = \frac{1}{\sqrt{L}}\mathrm{e}^{ikx}u_k(x) \qquad [12]$$

   where $u_k(x)$ is a function that has the symmetry of the lattice. $\psi_k(x)$ is known as the Bloch function and is a satisfactory solution to the Schrödinger equation. Because of the periodic nature of the Bloch equation, it is always possible to select the wavevector index k of any Bloch function to lie within the range $\pi/\mathrm{a} < k < \pi/a$. This region is referred to as the first Brillouin zone, and the representation where the E–k dispersion is mapped back entirely into the first Brillouin zone is called the 'reduced zone scheme' (Figure 1).
2. Regions of E appear where solutions $\psi_k(x)$ are not allowed, corresponding to Bragg reflections of the electron waves by the lattice; these are the so-called energy gaps (forbidden energy regions) which separate energy bands (allowed energy regions). In 3D these discrete bands of energy form the conduction and valence bands within materials. The forbidden energy gap separates these bands. An additional quantum number n is required to label the individual energy bands corresponding to successive Brillouin zones in the wavevector, $2n\pi/a$ (where $n = 0, 1\ldots$). The position of the Fermi level determines the electron population of the energy bands, and the character of the solid (see below).
3. The parabolic E–k dispersion relation is retained near $k = 0$, and at other symmetry points of the Brillouin zone, but with the substitution of an effective mass, m^* (see below) for the free electron mass, i.e., $E = \hbar^2k^2/2m^*$ for $k \ll \pi/a$. This is referred to as the effective mass approximation.

The nearly free electron model is one limit for the description of the formation of energy bands and energy gaps in a solid. In real crystals the energy bands derive from, and retain the symmetry of, the parent atomic states of the host atoms. In this limit, the model that starts out from the wave functions of the free atoms is known as the tight binding model or the LCAO (linear combination of atomic orbitals) approximation. As neutral separated atoms are brought together to form a crystal, their wave functions overlap and the Coulomb interaction between the atom cores and the electrons splits the atomic energy levels, spreading them into bands. Each state of given quantum number of the free atom is spread in the crystal into a band of energies; a given s, p, d-state in N separate atoms will produce the corresponding N-orbital s, p, d-energy band in the solid. Including the factor of 2 for spin, a full s-band would contain 2N electrons, a full p-band 6N electrons and so on. The width of the band is proportional to the strength of the overlap interaction between neighboring atoms. Each energy band will not have the same energy as any other band over any substantial range of the wavevector.

Metals, Insulators and Semiconductors

The position of the Fermi level distinguishes whether the solid is a metal, insulator or semiconductor. Generally those bands that derive from full atomic orbital states will be fully occupied with electrons, those that derive from empty atomic states lead to empty energy bands, and those from partially full atomic states lead to partially full energy bands. The highest band of those that are filled with electrons is called the valence band; the next highest band is called the conduction band (the fundamental energy gap, E_G, is the valence/conduction band separation, referred to from now on as simply the energy gap). For a metal, E_F is in the conduction band at all temperatures; for an insulator, E_F is close to the middle of the energy gap. Semiconductors are a class of crystals with small energy gaps; they are insulators at $T = 0\,K$, but are conductors at finite temperatures due to either thermal excitation of electrons across the gap or doping, n- or p-type (see below).

Effective Mass

Consider what happens to an electron when an external electric field F is applied. Suppose the electron is initially in a state k. When the field has acted on the electron for a small time dt, it has gained an energy:

$$dE = eFv dt = (eF/\hbar)(dE/dk)dt \qquad [13]$$

since the group velocity of the de Broglie wave (energy, $E = \hbar\omega$) is $v = \hbar^{-1}(dE/dk)$. Or simplifying we have: $dk/dt = eF/\hbar$. This gives for the resulting acceleration:

$$\begin{aligned} a &= dv/dt = (1/\hbar)(d^2k/dt^2)(dk/dt) \\ &= (eF/\hbar^2)(d^2E/dk^2) \qquad [14] \end{aligned}$$

Comparing this result for the acceleration of a free electron of mass m under the influence of F, $a = eF/m$, it follows that the electron behaves as if it had an effective mass, m^*, given by

$$\frac{1}{m^*} = \frac{1}{\hbar^2}\frac{d^2E}{dk^2} \qquad [15]$$

Thus, the electron effective mass m^* gives a measure of the conduction band curvature near the minimum at $k = 0$. We note that the same result is achieved by differentiating twice the 'nearly free electron' $E-k$ relation, $E = \hbar^2k^2/2m^*$.

Electrons and Holes

Consider the situation where a single electron is excited either optically or thermally from the top of the filled valence band to the bottom of the conduction band of a 1D lattice, and consider the collective behavior of the valence band when an external electric field is applied. Denoting the charge of an electron by $-e$ and the velocities of the electrons by v_i, we may write for the current associated with all electrons in the completely filled valence band in the absence of an external field:

$$I = -e\sum_i v_i = -e[v_j + \sum_{i\neq j} v_i] = 0 \qquad [16]$$

Thus, if the electron j were missing, we should have current

$$I' = -e\sum_{i\neq j} v_i = ev_j \qquad [17]$$

Applying an external field F, the rate of change of the current due to the field is:

$$dI'/dt = e(dv_j/dt) = -e^2F/m_j^* \qquad [18]$$

Since the holes are at the top of the valence band, m_j^* is negative and the right hand side of the equation is positive – i.e., a positive external field F gives a positive change of current at the top of the valence band. Thus, a band in which an electron is missing behaves as a 'positive hole' with an effective mass $m_h = -m_e$, and positive charge $+e$. Since m_e is negative near the top of the valence band, m_h is positive.

Impurities, Intrinsic and Extrinsic Conductivity

The key point about semiconductors from a device point of view is that one can control their conductivity. The basic method is by doping the host crystal with impurities either of valence greater than the host (donors giving excess electrons, called n-type) or of valence less than the host (acceptors giving excess holes, called p-type). The conductivity is referred to as intrinsic conductivity (from intrinsic carrier concentration, N_i) and extrinsic conductivity (from extrinsic carrier concentration, N_e) for undoped and doped material, respectively.

The impurities are chosen to have very low binding energies, so that the electrons (holes) are substantially ionized at room temperature to provide n-type (or p-type) conductivity. These shallow impurities can be treated using the simple Bohr theory of the hydrogen atom, substituting the electron orbiting around the proton in the hydrogen atom under the Coulomb potential e/r, by the electron in the crystal (electron effective mass m^*) orbiting round the ionized (donor/acceptor) impurity atom under the Coulomb potential $e/\varepsilon r$ in the crystal – where ε is the static dielectric constant of the crystal. As with the hydrogen atom, this gives a set of discrete energy levels:

$$E = \frac{m^*/m_o}{\varepsilon^2}\frac{13.6}{n^2}\,\mathrm{eV} \qquad [19]$$

where 13.6 eV is the binding energy of the H-atom and n is the principal (Bohr) quantum number. The binding energy is then

$$E_B = \frac{m^*/m_o}{\varepsilon^2} \times 13.6\ \mathrm{eV} \qquad [20]$$

For typical semiconductors (Ge, Si...) we have $m^*/m_o \sim 0.05$, $\varepsilon \sim 16$. Thus, E_B is in the range of a few meV (i.e., much less than E_G, and kT at room temperature). The energy level scheme for a doped semiconductor is shown schematically in real space (at room temperature) in Figure 2.

The total conductivity will be $\sigma = \sigma_i + \sigma_e$, where the intrinsic conductivity $\sigma_i = n_i e^2 \tau / m^*$ and the extrinsic conductivity $\sigma_e = n_e e^2 \tau / m^*$. τ is the so-called carrier scattering time. The intrinsic carrier concentration is related to temperature by $n_i = n_0 \times \exp(-E_G/2kT)$, where n_0 is a constant. In the extrinsic regime ($n_e \gg n_i$), at temperatures such that $kT \gg E_d$ (so that the impurities are all ionized), the conduction (valence) carrier concentration $n_e \to n_d$ (or n_a), the donor (or acceptor) concentration.



Figure 2 Doping in semiconductors. In n-type material (a), carriers are excited thermally from the donor states to the conduction band where they can contribute to the conductivity. In p-type material (b), electrons are effectively 'captured' by the acceptor states, leaving behind holes in the valence band which can also contribute to conduction. N_D and N_A are the concentration of donor and acceptor impurities, respectively.

Infrared Absorption – Interband Optical Transitions, Excitons

Apart from thermal promotion of electrons and holes via interband (valence to conduction band) transitions responsible for intrinsic conductivity, it is possible to directly excite such transitions optically by subjecting the sample to radiation with $\hbar\omega > E_G$. If the lowest conduction band minimum is situated vertically above the valence band maximum (usually at $k = 0$), then the optical transition process is referred to as a direct transition. If the lowest conduction band minimum is situated at some other point in k-space than that of the valence band maximum, the process is referred to as an indirect transition; this requires the participation of optical phonons (i.e., quantized lattice vibrations) to satisfy momentum conservation, and is therefore a weaker (higher order) process. The semiconductors are respectively referred to as Direct Gap and Indirect Gap Semiconductors. Simplified energy band diagrams for direct and indirect transitions are shown in Figure 3.

The optical spectrum corresponding to the onset of interband electric dipole transitions is referred to as the absorption edge. The most widely used indirect gap materials are the group IV semiconductors Si and Ge. The best known direct gap materials are the III–V's (InSb, GaAs, GaP, etc.), II–VI's (HgTe, CdTe, ZnSe, etc.) and IV–VI's (lead salts PbTe, PnSe, SnTe) and alloy combinations of all these. An important additional effect, which becomes progressively stronger as the energy gap becomes larger in a semiconductor is the Coulomb interaction between the electrons and holes created by interband optical transitions. The electron is raised into an excited state but remains bound in a hydrogen-like orbit around the positive hole creating a two particle excitation called an exciton. The composite particle can then move throughout the crystal. In an ideal crystal, therefore, the absorption spectrum should consist of a series of discrete lines corresponding to the ground and excited exciton states, followed at somewhat high energies by the continuum associated with interband electronic transitions. The energy levels of the exciton spectrum measured from the beginning of the ionization continuum will be given by the Bohr formula:

$$E_{ex} = \frac{\mu}{\varepsilon^2}\frac{13.6}{n^2}\text{eV} \qquad [21]$$

where μ is the reduced mass given by: $1/\mu = 1/m_e + 1/m_h$ (m_e, m_h are electron and hole effective masses). A schematic diagram of the absorption edge is shown in Figure 4 (dashed line – in the absence of excitons; solid line – in the presence of excitons).



Figure 3 (a) Direct and (b) indirect gap semiconductors. Direct gap transitions involve only the absorption or emission of a single photon and are therefore very nearly 'vertical' transitions in k-space. On the other hand, indirect transitions have a 'two-stage' nature, involving the participation of both a photon and an optical phonon that carries sufficient momentum $\hbar q$ to allow the conduction band electron created in the absorption process to have a large non-zero wavevector.



Figure 4 Absorption edge spectra without (dashed curve) and with (solid curve) the excitonic effect.

Conduction and Valence Band Parameters in Typical Semiconductors

As has been described earlier in real semiconductors the conduction and valence bands retain the symmetry of the parent atomic states from which they derive. For example, the conduction and valence bands of silicon can be regarded as deriving from 3s and 3p electrons, and it is generally true that for all group IV, III–V and II–VI semiconductors commonly used in electronic applications the conduction band has s-like symmetry and the valence band has p-like symmetry. This means that the valence band has the additional complication that it is triply degenerate (c.f. the p_x, p_y, p_z components of the hydrogen atom p-orbital); and further, in the presence of spin-orbit coupling (familiar from atomic physics) part of this degeneracy is raised, resulting in doubly degenerate (at $k = 0$) so-called heavy hole (hh) and light hole (lh) bands, and a band split-off by the spin-orbit splitting, Δ:

$$E_{hh} = -\hbar^2k^2/2m_{hh}\ ;\ E_{lh} = -\hbar^2k^2/2m_{lh}\ ;$$
$$E_{so} = -\Delta - \hbar^2k^2/2m_{so} \qquad [22]$$

The resulting conduction and valence bands near $k = 0$ are shown in Figure 5.

Low Dimensional Systems: Quantum Wells

So far we have been concerned almost entirely with the bulk properties of crystalline solids. Such properties can normally be specified in terms of coefficients that are independent of the shape and size of a particular specimen. Thus, for example the electrical



Figure 5 Energy bands (s-like conduction and p-like valence bands) of a direct gap semiconductor near the Brillouin zone center.

conductivity and resistivity, or the optical absorption coefficient and refractive index are properties only of the material and not of the sample dimensions. When one or more dimensions of a solid are reduced sufficiently, the properties are no longer given by these bulk coefficients. The sample is then described as a low-dimensional system (LDS). Such systems form the basis of many optoelectronic devices. LD systems can be classified according to the number of dimensions that are small: thin films (and heterojunctions) are two-dimensional since only the thickness is reduced, and these form so-called quantum wells; fine wires are one-dimensional since two dimensions are reduced, forming quantum wires; dots or specks are zero-dimensional, forming quantum dots.

From an optoelectronic point of view, the most important example is that of electrons confined to a semiconductor film or junction; this system is called the two-dimensional electron gas (2-DEG) and the structure a quantum well. Thus, it is possible to create a narrow electric potential junction region so that the electrons are restricted in 1D (say z) according to the quantum mechanics of a particle in an infinite potential well (described earlier), but 'free' within the xy junction plane.

See also

Semiconductor Materials: Band Structure Engineering; Quantum Dots. **Semiconductor Physics:** Band Structure and Optical Properties; Impurities and Defects; Infrared Lattice Properties; Quantum Wells and GaAs-Based Structures; Recombination Processes.

Further Reading

Hook JR and Hall HE (1991) *Solid State Physics*, 2nd edn. Chichester, UK: John Wiley and Sons, Inc.
Kittel C (1996) *Introduction to Solid State Physics*, 7th edn. Chichester, UK: John Wiley and Sons, Inc.
Seeger K (1989) *Semiconductor Physics: an Introduction*, 4th edn. Berlin: Springer.

Band Structure and Optical Properties

W Zawadzki, Polish Academy of Sciences, Warsaw, Poland

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The purpose of this article is to describe the influence of the electronic energy band structure of semiconductors on their optical properties. By the band structure one understands the energy–wavevector dispersion relation $\varepsilon(\mathbf{k})$ for the electron energy bands and the relative positions of band maxima and minima in the Brillouin zone.

The main problem in calculating the band structure of a semiconductor is that of the periodic potential of the lattice in which the electrons move. It is, in fact, a self-consistent problem since the moving electrons partly screen the potential. Different approximations have been developed to deal with the question, and in all of them the symmetry of the lattice is of fundamental importance. Thus, in the so-called empty-lattice approximation one deals exclusively with the symmetry and periodicity of the lattice without specifying the potential. This can give qualitative ordering and symmetry of the bands but no quantitative results. In the opposite limit one uses the tight binding approximation, in which the bands are constructed from the atomic states of separate atoms. This method gives quite a good description of lower (valence) bands but poor results for higher (conduction) bands. A powerful way to describe real energy bands is obtained by various forms of pseudopotential calculation, where one approximates the potential near actual atoms by simple parametrized forms and then adjusts the parameters to fit experimental (mostly optical) data. The pseudopotential methods give a good overall description of various bands in the entire Brillouin zone, but they do not provide sufficiently precise results near the band extrema. A semi-empirical way to serve the latter purpose is called $\mathbf{k}\cdot\mathbf{p}$ theory which we describe below. Various methods of band structure calculation are reviewed in books on solid state physics as outlined in the suggestions for Further Reading at the end of this article.

In the majority of important semiconductor materials (Si, Ge, many III–V and II–VI compounds) the maxima of the valence bands are at the center of the Brillouin zone (Γ point). The minima of the conduction bands in Si and Ge are not at the Γ point. This means that the fundamental optical interband transitions in these materials are indirect (in the ε–$\mathbf{k}$ diagram), i.e., they require phonon assistance. On the other hand, the minima of conduction bands in important III–V and II–VI compounds are at the Γ point, so that the interband optical transitions are direct and they do not require phonon assistance.

Both systems are utilized in opto-electronic devices, particularly for detectors. However, for emitters (light-emitting diodes and lasers) we are mostly concerned with the second case, on which we concentrate here.

Bloch States

The Bloch theorem states that if the potential $V(\mathbf{r})$ in which the electron moves is periodic with the periodicity of the lattice, then the solutions $\Psi(\mathbf{r})$ of the Schrödinger wave equation

$$\left[\frac{\mathbf{p}^2}{2m_0}+V(\mathbf{r})\right]\Psi(\mathbf{r})=\varepsilon\Psi(\mathbf{r}) \qquad [1]$$

are of the form $\Psi(\mathbf{r})=\exp(\mathrm{i}\mathbf{k}\cdot\mathbf{r})u_k(\mathbf{r})$, where $u_\mathrm{k}(\mathbf{r})$ is periodic with the periodicity of the direct lattice, and $\mathbf{k}$ is the wavevector ($\hbar\mathbf{k}$ is the pseudomomentum). The proof of this theorem can be found, for example, in undergraduate textbooks on solid state physics.

k·p Theory

The underlying idea of semi-empirical **k·p** theory is to describe the energy bands in the vicinity of a given point of the Brillouin zone (usually near a band extremum). Symmetry properties are used to minimize the number of unknown band parameters (effective mass, energy gap, etc.) which are then determined by experiment. The initial Schrödinger equation for an electron in the periodic potential $V(\mathbf{r})$ of the crystal lattice reads

$$[\mathbf{p}^2/2m_0+V(r)+H_\mathrm{so}]\Psi=\varepsilon\Psi \qquad [2]$$

where m_0 is the free electron mass and H_so is the spin–orbit interaction. Since $H_\mathrm{so}(\mathbf{r})$ is also periodic with the lattice periodicity, the solutions of eqn [2] are given by the Bloch states above.

We use **k·p** perturbation theory, as follows, to describe the energy bands near $\mathbf{k}=0$ (i.e., the so-called Γ point of the Brillouin zone). Since we are interested in small values of $\mathbf{k}$, we expand our unknown cell periodic functions, $u_{l\mathbf{k}}(\mathbf{r})$, in terms of the set of Γ-point functions, $u_{lo}(\mathbf{r})$, whose symmetry we know. One defines a representation $\Phi_{l\mathbf{k}}=\exp(\mathrm{i}\mathbf{k}\cdot\mathbf{r})u_{lo}(r)$, where $u_{lo}(\mathbf{r})$ is the periodic $\mathbf{k}$-independent function satisfying the equation

$$[\mathbf{p}^2/2m_0+V+\mathrm{H}_\mathrm{so}]u_{lo}=\varepsilon_{lo}u_{lo} \qquad [3]$$

whose solution we know in terms of the band-edge energies, ε_{lo}. This representation is sometimes referred to as the Luttinger and Kohn (LK) representation. The u_{lo} functions are in general mixtures of spin up and spin down states because of the spin–orbit interaction. One looks for the solutions of eqn [2] in the form

$$\Phi_{n\mathbf{k}}=\exp(\mathrm{i}\mathbf{k}\cdot\mathbf{r})\sum_l c_l^{(n)}(\mathbf{k})u_{lo}(\mathbf{r}) \qquad [4]$$

where the sum is over all bands and $c_l^{(n)}(\mathbf{k})$ are the coefficients to be determined. Inserting the above form into eqn [2], performing the operation $\mathbf{p}^2$ (i.e., operating twice on the Bloch product function with the operator $\mathrm{p}=-\mathrm{i}\hbar\nabla$) and using the property [3] one eliminates the unknown potential $V(\mathbf{r})$. Multiplying the resulting equation from the left by $u^*_{l'o}$, integrating over the unit cell Ω and using the orthonormality of u_{lo}, one finally obtains

$$\sum_l\left[(\varepsilon_{lo}-\varepsilon')\delta_{l'l}+\frac{\hbar}{m_0}\mathbf{k}\cdot\mathbf{p}_{l'l}\right]c_l^{(n)}(\mathbf{k})=0 \qquad [5]$$

for $l'=1,2,3,\ldots$ Here $\delta_{l'l}$ is the Kronecker delta function, $\varepsilon'=\varepsilon-\hbar^2k^2/2m_0$, and $\mathbf{p}_{l'l}$ is the so-called matrix element of the momentum given by $\mathbf{p}_{l'l}=(1/\Omega)\int_\Omega u^*_{l'o}\mathbf{p}u_{lo}\,\mathrm{d}\mathbf{r}$. The index l' runs over all energy bands.

Equation [5] formulates the famous **k·p** theory. The nondiagonal part $\mathbf{k}\cdot\mathbf{p}_{l'l}$ can be eliminated by the perturbation procedure, and the method is referred to as **k·p** perturbation theory. In the second order of perturbation the bands are separated and in each band the carriers are described by a dispersion relation $\varepsilon_l=(\hbar^2/2)\mathbf{k}(\widehat{1/m^*_{lo}})\mathbf{k}$ where $(\widehat{1/m^*_{lo}})$ is an inverse effective mass tensor at the band edge in question. The inverse mass is generally a 3×3 tensor, but for cubic materials in the center of the Brillouin zone it is a scalar, so that $\varepsilon_l(\mathrm{k})=\hbar^2\mathrm{k}^2/2\mathrm{m}^*_{lo}$ (where $1/\mathrm{m}^*_{lo}\equiv1/\mathrm{m}_0+(2/\mathrm{m}_0^2)\sum_{l\neq l'}(\mathrm{p}^2_{ll'})/[\varepsilon_{l0}-\varepsilon_{l'0}]$). We then say that the band is spherical and parabolic. The second order of perturbation is a good approximation if the energy ε (as counted from a nondegenerate band edge) is small compared to forbidden energy gaps. For the triply degenerate p-like valence band one has to do degenerate perturbation theory and treat the bands together as a 3×3 matrix equation.

In the same approximation the wavefunction for a given band is: $\Psi_{l\mathbf{k}}(\mathbf{r})=\exp(\mathrm{i}\mathbf{k}\cdot\mathbf{r})\,u_{lo}(\mathbf{r})$. In the absence of spin–orbit coupling, H_so, the u_{lo} function would just have the symmetry of the parent band (i.e., labeled S for the s-like conduction band, and X, Y or Z for the triply degenerate p-like valence band – each with a single spin up or spin down component). In the presence of H_so, the triply degenerate valence band states become mixtures of X, Y and Z with mixed spin character and part of the degeneracy is raised.

In atomic notation the presence of H_{so} has transformed the basis from the (l, s) to the (J, m_J) representation. This results in the well-known light and heavy hole bands (degenerate at $k = 0$) and the spin–orbit split-off band.

Under the influence of a radiation field, of vector potential $\mathbf{A}'$ and frequency ω, the optical transition probability for an electron to be raised from state Ψ_i (initial) to Ψ_f (final) is proportional to the square of $M = (e/mc)\langle\Psi_f|\mathbf{A}'\cdot\mathbf{p}|\Psi_i\rangle$ i.e., it is determined by the same momentum matrix element, p_{fi}, which governs the effective mass. For interband transitions one immediately gets the selection rule $\Delta k = 0$ (i.e., direct transitions). The polarization selection rules are determined by the $u_{l0}(r)$ components of the initial and final states, through the momentum matrix elements.

Narrow-Gap Semiconductors

Semiconductors such as InSb and $Hg_{1-x}Cd_xTe$ (with $x < 0.3$) have small energy gaps and are referred to as narrow gap semiconductors (NGSs). They are commonly used in opto-electronic applications which may be accessing energies in the conduction or valence band which are a significant fraction of the energy gap. Under these circumstances it is not valid to cut off the expansion to order k^2, and one has to deal with so-called nonparabolic bands. Thus, in NGSs (or indeed in any situation where the energy becomes an appreciable fraction of ε_g) the above procedure is not valid and an alternative approximation is in order. Following semidegenerate perturbation theory one includes exactly in eqn [5] a finite number of bands (near each other in energy) and neglects distant bands. This is referred to as the Kane model, and the energy bands near $k = 0$ are shown for InSb-type III–V compounds and for HgTe-type II–VI compounds in Figure 1. In this case we include only the conduction and valence band in our set of states (eqn [5]). Including spin and degeneracy of the Γ_8 symmetry the set [5] then has eight equations. They can be solved analytically and the resulting energies are given by

$$\varepsilon'(\varepsilon'+\varepsilon'_g)(\varepsilon'+\varepsilon'_g+\Delta)-\left(\varepsilon'+\varepsilon'_g+\frac{2\Delta}{3}\right)\kappa^2k^2=0 \quad [6]$$

where $\varepsilon' = \varepsilon - \hbar^2k^2/2m_0$. We see that for this restricted set of states the only unknown parameters are the energy gap, ε_g, the spin–orbit splitting energy, Δ, and $\kappa = -i(\hbar/m_0)\langle S|p_z|Z\rangle$ (note that this is the only non-vanishing matrix element of the momentum). The fourth energy is $\varepsilon' = -\varepsilon_g$. All four energies are spin degenerate. In NGSs one may neglect the free electron term, i.e., set $\varepsilon' \approx \varepsilon$. For $\varepsilon \ll \varepsilon_g + (2/3)\Delta$ the resulting quadratic equation for the conduction and the light-hole bands is



Figure 1 Three-level model of band structure near the Γ point of the Brillouin zone: (a) InSb-type semiconductors; (b) HgTe-type semiconductors.

$$\varepsilon(1+\varepsilon/\varepsilon_g) = \hbar^2k^2/2m_0^* \quad [7]$$

where $1/m_0^* = (4\kappa^2/3\hbar^2\varepsilon_g)(\varepsilon_g + 2\Delta/3)/(\varepsilon_g + \Delta)$ defines the effective mass at the band edge. The root for the heavy holes is $\varepsilon = -\varepsilon_g$ i.e., this band is not correctly described within the three-level model. The bands given by eqn [6] are spherical but nonparabolic. For $\varepsilon \ll \varepsilon_g$ one recovers the standard dispersion, $\varepsilon = \hbar^2k^2/2m_0^*$.

For HgTe-type materials, setting the zero of energy at the Γ_8 edge and replacing ε_g by $-\varepsilon_0$ (cf. Figure 1), one obtains

$$\varepsilon'(\varepsilon'+\varepsilon_0)(\varepsilon'+\Delta)-\left(\varepsilon'+\frac{2\Delta}{3}\right)\kappa^2k^2=0 \quad [8]$$

For $\varepsilon' \ll (2/3)\Delta$ the dispersion [7] is valid with $1/m_0^* = 4\kappa^2/3\hbar^2\varepsilon_0$. In this case the conduction and the heavy hole bands ($\varepsilon \equiv 0$) are degenerate at $k = 0$, i.e., the thermal gap is zero.

The important property of the above model is that it holds also in the limit of $\varepsilon_g \to 0$ (i.e., for mixed $Hg_{1-x}Cd_xTe$ crystals). The effective mass in eqn [7] tends to zero, but the dispersion described by eqn [6] is valid and it gives $\varepsilon = (2/3)\kappa k$, i.e., a linear band.

The electron and hole wavefunctions in NGSs resulting from semidegenerate perturbation theory are given by eqn [4], in which the sum runs over all the included states. Thus they involve truly **k**-dependent amplitudes of the Bloch states, cf. eqn [1]. In addition, these functions are mixtures of spin-up and spin-down states. These features have important consequences for optical and dc transport phenomena.

If the conduction band minimum is not at the Γ point (Ge and Si), there are at least two different matrix elements of momentum and the resulting band is ellipsoidal.

Effective Mass

The nonparabolic dispersions $\varepsilon(k)$ in NGSs require generalizations of important relations. The momentum mass $\widehat{m}^*$ is introduced as a connection between the psuedomomentum and the velocity: $\hbar\mathbf{k} = \widehat{m}^*\mathbf{v}$. Since $v_i = \delta\varepsilon/\delta(\hbar k_i)$, one obtains for a spherical band

$$\frac{1}{m^*} = \frac{1}{\hbar^2 k}\frac{\mathrm{d}\varepsilon}{\mathrm{d}k} \qquad [9]$$

The above mass is a scalar, but it depends on the energy (or momentum). This mass is more useful than the one usually defined in textbooks, relating force to acceleration. The latter is not a scalar even for a spherical band. However, for the standard parabolic band, $\varepsilon = \hbar^2k^2/2m_0^*$, both masses are the same and are equal to m_0^*. The mass [9] is related via velocity to the electric current, so that it enters naturally in transport phenomena (also free carrier optics). In particular, this mass enters the definition of mobility $\mu = q\tau/m^*$, where q is the charge and τ is the relaxation time. It enters the density of states (see below). Finally, it is the momentum mass [9] which is measured in cyclotron resonance.

For the dispersion [7] (the so-called two-level model), the mass [9] in the conduction band is

$$m^*(\varepsilon) = m_0^*\left(1 + \frac{2\varepsilon}{\varepsilon_\mathrm{g}}\right) \qquad [10]$$

Again, for $\varepsilon/\varepsilon_\mathrm{g} \ll 1$ the energy dependence of the mass is negligible, which represents the standard regime. Figures 2 and 3 illustrate energy dependences of the electron masses in InSb and HgSe, as measured by various optical and transport methods. The increase of the mass with energy is very strong in both cases.

Density of States

The density of states in energy space is calculated beginning with pseudomomentum space. For the spherical band one obtains

$$\rho(\varepsilon) = \frac{k^2}{\pi^2}\frac{\mathrm{d}k}{\mathrm{d}\varepsilon} = \frac{m^*k}{\pi^2\hbar^2} \qquad [11]$$



Figure 2 Electron effective mass in InSb at room temperature versus free electron concentration. The solid line, calculated for the two-level model, represents the mass value at the Fermi energy, as indicated on the upper abscissa. The experimental results of various authors are also indicated. Reproduced from Zawadzki W (1974) Electron transport phenomena in Sm all-gap semiconductors. *Advances in Physics* 23: 435–512.



Figure 3 Electron effective mass in zero-gap material HgSe versus free electron concentration. The solid line is calculated for the three-level model. Experimental results of various authors are also indicated. Reproduced from Zawadzki W (1974) Electron transport phenomena in Sm all-gap semiconductors. *Advances in Physics* 23: 435–512.

The momentum mass [9] enters naturally into this important quantity. For the parabolic case $m^* = \text{const.}$ and $k \sim \varepsilon^{1/2}$, so that the standard result is recovered. In the general case one should use eqn [10] for $m^*(\varepsilon)$ and determine k from eqns [6] or [7].

Electron–photon Interaction

The electron–photon interaction can be introduced into the theory on two levels. If one replaces in the initial equation [2] the momentum $\mathbf{p}$ by $\mathbf{p} + (e/c)\mathbf{A}'$, the interaction term is obtained in the scalar form $H_{\text{int}} = (e/m_0c)\mathbf{A}'\cdot\mathbf{p}$, where $\mathbf{A}'$ is the vector potential of radiation. The wavefunctions to be used for the calculation of matrix elements are of the form [4], i.e., they include the periodic LK amplitudes. In fact, the matrix elements of momentum for optical transitions are identical to those of the $\mathbf{k}\cdot\mathbf{p}$ theory, as pointed out earlier. Since (as noted above) the wavefunctions for all bands have the same form [4], differing only by the coefficients $c_l^{(n)}(\mathbf{k})$, the matrix elements for interband and intraband optical transitions have the same form.

The electron–photon interaction can also be introduced directly to the $\mathbf{k}\cdot\mathbf{p}$ theory of eqn [5] replacing $\hbar\mathbf{k}$ by $\hbar\mathbf{k} + (e/c)\mathbf{A}'$. If the free electron term $\hbar^2k^2/2m_0$ is neglected, the interaction matrix involving $\mathbf{A}'$ terms is a number matrix. In this procedure the wavefunctions for initial and final states are simply columns and rows of $c_l^{(n)}$ coefficients and LK amplitudes no longer come into play. Here the $\mathbf{p}_{l'l}$ elements of $\mathbf{k}\cdot\mathbf{p}$ theory determine directly the electron–photon interaction. Both procedures described above give the same results.

Quantum Wells

If charge carriers are placed in a quantum well described by a potential $U(z)$, the motion in the z-direction is quantized while the motion in the x–y plane remains free. One takes the same LK basis (cf. eqn [3]), but the general form of solution is given by

$$\Psi = \sum_l f_l(\mathbf{r}) u_{l0}(\mathbf{r}) \qquad [12]$$

since, in the presence of an external potential, $\mathbf{k}$ is not a good quantum number and the envelope functions $f_l(\mathbf{r})$ are unknown. If $U(z)$ is a slowly varying function within the unit cell the potential appears only on the diagonal of the set [5] and $\hbar\mathbf{k}$ is replaced by $\mathbf{p}$. One obtains

$$\sum_l \left[\left(\varepsilon_{l0} + \frac{\mathbf{p}^2}{2m_0} + U - \varepsilon \right) \delta_{l'l} + \frac{\mathbf{p}_{l'l}\cdot\mathbf{p}}{m_0} \right] f_l(\mathbf{r}) = 0 \qquad [13]$$

One can now eliminate the nondiagonal terms applying the standard Luttinger and Kohn scheme of second-order perturbation theory and arrive at the decoupled band equations with effective masses. This results in the standard quantization due to electric (and magnetic, if present) fields, and wavefunctions are of the form $\Psi_{lm} = f_m u_{l0}$ for the m-th sub-band of the l-th band.

For NGSs this procedure is a poor approximation and one should proceed as before including exactly a finite number of bands (cf. eqn [12]). This results in a set of coupled differential equations for the envelope functions $f_l(\mathbf{r})$. In some important cases one can find the eigenenergies without finding the functions by using the semiclassical approximation (the so-called WKB method).

We shall omit the calculations with coupled differential equations by using a semiclassical procedure also in another sense. Namely, we shall generalize the nonparabolic dispersion relation [7] to include the presence of external fields. To this end we observe that, including the potential $U(\mathbf{r})$ on the diagonal of eqn [13], one replaces $-\varepsilon$ by $-\varepsilon + U$. Further, if a magnetic field is introduced to the $\mathbf{k}\cdot\mathbf{p}$ theory one replaces $\hbar\mathbf{k}$ by $\mathbf{P} = \mathbf{p} + (e/c)\mathbf{A}$, where $\mathbf{A}$ is the vector potential of the magnetic field. Thus the semiclassical equation resulting from eqn [7] is

$$\left[\frac{\mathbf{P}^2}{2m_0^*} - (\varepsilon - U)\left(1 + \frac{\varepsilon - U}{\varepsilon_g} \right) \right] \Psi = 0 \qquad [14]$$

It can be seen that for $\varepsilon - U \ll \varepsilon_g$ one recovers the standard one-band approximation mentioned above. However, below we consider the general situation described by eqn [14].

Let us first consider the case of no magnetic field, i.e., $\mathbf{P} = \mathbf{p}$. For $U(\mathbf{r}) = U(z)$ one can separate the variables by looking for solutions in the form $\Psi = \exp(\mathrm{i}k_x x + \mathrm{i}k_y y)\Phi(z)$. One can now transform eqn [14] into

$$\left[\frac{1}{2m_0^*}p_z^2 - \frac{1}{\varepsilon_g}(\varepsilon - \varepsilon_\perp - U)(\varepsilon_g + \varepsilon + \varepsilon_\perp - U)\right]\Phi(z) = 0 \qquad [15]$$

where

$$\varepsilon_\perp = \frac{\varepsilon_g}{2} + \left[\left(\frac{\varepsilon_g}{2}\right)^2 + \varepsilon_g \frac{\hbar^2 k_\perp^2}{2m_0^*}\right]^{1/2} \qquad [16]$$

in which $k_\perp^2 = k_x^2 + k_y^2$. Equation (15) is suitable for the WKB semiclassical quantization with which one determines the eigenenergies ε by one integration.

For a magnetic field applied along the z-direction (parallel electric and magnetic fields) the effects of both fields are separated and the form of eqn [15] is valid, with $\hbar^2 k_\perp^2/2m_0^*$ in eqn [18] replaced by $\hbar\omega_c(n + 1/2) \pm (1/2)|g_0^*|\mu_B B$. Here $\omega_c = eB/m_0^* c$ is the cyclotron frequency, $n = 0, 1, 2, \ldots$ is the Landau quantum number, g_0^* is the spin splitting factor, and μ_B is the Bohr magneton. This results in nonequal spacing of Landau levels for a fixed value of B and in nonlinear B dependence of the Landau energies as functions of B (similarly but not identically to the bulk case). These features are illustrated by the cyclotron resonance experiment and theory shown in Figure 4.



Figure 4 Electron effective mass versus two-dimensional electron density in GaAs/GaAlAs heterostructures, as measured by far infrared cyclotron resonance. The solid lines are calculated using the effective two-level model for GaAs. Reproduced from Zawadzki W, *et al.* (1994) Cyclotron emission study of electron masses in GaAs-GaAlAs heterostructures. *Semiconductor Science and Technology* 9: 320–328.

Selection Rules for Intersub-band Optical Transitions

For the one-band effective mass approximation the electron–photon interaction is $H_{\text{int}} \sim \mathbf{A}' \cdot \mathbf{p}$ (cf. above), and the wavefunctions for the initial and final sub-bands are $\Psi_m = \exp(\mathrm{i}k_x x + \mathrm{i}k_y y)\Phi_m(z)$, in which the $\Phi_m(z)$ must be orthogonal to each other since they describe different energies. It is then clear that the matrix element $\langle fn|\mathbf{A}' \cdot \mathbf{p}|in\rangle$ is finite only if $\mathbf{A}'$ is polarized along the z-direction (also called the growth direction) since for $\mathbf{A}'$ parallel to x or y the integral over z is $\langle \Phi_{m'}|\Phi_m\rangle = 0$ giving a vanishing matrix element. Experimentally this is a serious problem for spectroscopic applications involving intraband (i.e., intersub-band) transitions in n-type semiconductors, since it is not possible to access these using normal incidence radiation.

This selection rule is somewhat relaxed for p-type semiconductors as a result of the mixed spin states of the complex valence band. In addition the narrow-gap band structure introduces interesting new possibilities into the selection rules. The wavefunctions have the form [12] and for the light polarizations A'_x or A'_y the momentum operators p_x or p_y act also on the periodic amplitudes $u_{l0}(\mathbf{r})$, which leads to a nonvanishing transition probability for intersub-band transitions. This has indeed been observed in narrow-gap materials.

See also

Magneto-Optics: Interband Magnetoabsorption, Cyclotron Resonance, Spin Flip Raman Scattering. **Semiconductor Materials:** Mercury Cadmium Telluride; Quantum Dots. **Semiconductor Physics:** Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures.

Further Reading

Ashcroft NW and Mermin ND (1976) *Solid State Physics*. Holt, Rinehart and Winston.

Kane EO (1980) Band structure of narrow gap semiconductors. In: Zawadzki W (ed.) *Narrow Gap Semiconductors. Physics and Applications*, pp. 13–31. Berlin: Springer.

Luttinger JM and Kohn W (1955) Motion of electrons and holes in perturbed periodic fields. *Physical Review* 97: 869–883.

Zawadzki W (1974) Electron transport phenomena in Sm all-gap semiconductors. *Advances in Physics* 23: 435–512.

Zawadzki W (1984) Electric and magnetic quantisation of two-dimensional systems – elementary theory. In: Bauer G, *et al.* (eds) *Two-Dimensional Systems, Heterostructures, and Superlattices*, pp. 2–11. Berlin: Springer.

Zawadzki W (1991) Intraband and interband magneto-optical transitions in semiconductors. In: Landwehr G and Rashba EI (eds) *Landau Level Spectroscopy*, pp. 483–512. Amsterdam: North-Holland.

Excitons

I Galbraith, Heriot-Watt University, Edinburgh, UK

© 2005, Elsevier Ltd. All Rights Reserved.

In semiconductors electron–hole pairs can lower their energy by correlating their motion in an exciton state. Such states dominate the bandedge optical properties of direct-gap semiconductors. The resultant absorption peaks are affected by quantum confinement, electric, and magnetic fields and carrier scattering.

Introduction

In the simplest, single-particle picture, the ground state of a semiconductor consists of a full valence band and an empty conduction band. The lowest lying excitation above the ground state in such a scheme is produced by excitation of one electron from the valence band to the conduction band. To achieve this optically requires a photon energy greater than the bandgap, E_g. However in many semiconductor materials this simple picture is unable to explain the observed absorption spectrum in the neighborhood of the fundamental bandgap. The origin of the discrepancy lies in the neglect of the Coulomb interaction between the negatively charged excited electron and the hole which is left in the valence band.

The term exciton refers to a two-particle excitation, consisting of a bound electron and hole. Such excitations dominate the bandedge optical spectra of most direct gap semiconductors, especially at low temperatures. In particular there exists a series of hydrogen-like bound states lying below the bandedge. These states are bound by energies

$$E_b^{3D} = \frac{\mu e^4}{8\mathrm{h}^2 \varepsilon_r^2 \varepsilon_0^2} \frac{1}{n^2} \qquad [1]$$

where $\mu = m_e m_h/(m_e + m_h)$, is the reduced mass, $m_{e(h)}$ the electron (hole) effective mass, e is the electronic charge, h is Planck's constant, ε_0 is the permittivity of free space, ε_r the relative permittivity of the material and $n = 1, 2, 3, \ldots\infty$ is the principal quantum number.

The binding energy of the lowest lying exciton state varies considerably from one semiconductor to another being, e.g., 0.5 meV in InSb and over 60 meV in Zn0. Similarly the spatial extent of the 1 s electron-hole relative wave function or effective Bohr radius is given by

$$a_0^{3D} = \frac{\hbar}{\sqrt{2\mu E_b^{3D}}} \qquad [2]$$

and ranges from 750 μm in InSb to ≈2 nm in Zn0. Typically, in semiconductors the exciton spatial extent is much larger than the lattice constant of around 0.6 nm, and such excitons are classed Wannier excitons. At the opposite limit, which occurs in many molecular materials, the exciton is localized around a particular atomic site and is termed a Frenkel exciton. Wannier excitons are characterized by the hydrogen-like quantum numbers of their relative motion and an overall center of mass momentum which describes the wave-like motion of the bound entity through the crystal.

Another type of exciton is often referred to as a bound exciton. This consists of an electron–hole pair bound to a neutral impurity center. Such excitons are localized around the impurity and cannot move through the crystal in the same way as a free exciton.

Optical Properties

Excitons manifest themselves primarily as strong modifications to the bandedge optical properties of semiconductors. In particular the bound states give rise to discrete absorption lines at lower energy than the bandgap energy. Several peaks corresponding to the different hydrogen-like bound states

(1s, 2s, etc.) can be seen provided the lines are sufficiently narrow. A theoretical calculation of this is shown in Figure 1.

Associated with these absorption changes are concomitant changes in the refractive index. Contributions to the spectral width of the absorption peaks are characterized as either homogeneous or inhomogeneous. Homogeneous broadening refers to broadening associated with the finite lifetime of a particular state, e.g., due to phonon scattering. Inhomogeneous broadening is due to non-uniformity in the system, e.g., in a sample having a spatially non-uniform strain field.

There is also enhancement of the absorption at photon energies above the bandgap due to the residual influence of the Coulomb attraction on the electron-hole scattering states. Although not bound, electrons and holes in these states still have an enhanced probability of being found close together. This is called the Sommerfeld Enhancement Factor (see Figure 1).

It is important to note that although there may be an excitonic peak in the absorption spectrum this does not imply that excitons form a stable population in such a sample. Often, especially at room temperature, the lifetime of an optically generated exciton is determined by the scattering time with optical phonons which may be very short (<1 ps). In this case the excitons are quickly ionized and the quasi-thermal equilibrium which is formed is dominated by essentially plasma-like behavior. In photoluminescence experiments, where carriers are generated high in the band and the spectrum of the resulting emitted luminescence is measured, peaks associated with the free exciton are often observed and taken as a signature of the presence of excitons. This view has been challenged recently by theoretical calculations which show that a photoluminescence peak at the exciton energy can be also be produced from an uncorrelated plasma if proper account of the Coulomb interaction is taken. This issue remains controversial.



Figure 1 Calculated bulk absorption spectra including (solid-line) and neglecting (dashed line) the Coulomb interaction. The Sommerfeld enhancement is seen as photon energies above the bandgap. Also shown is the spectrum with an applied electric field of one exciton Rydberg per Bohr radius.

In bulk samples, experiments such as absorption and reflectivity are complicated by the existence of polariton effects. An exciton-polariton is a quantum mixture of the propagating photon inside the semiconductor sample and the material excitation. Where the photon dispersion and the exciton energy dispersion meet there is an anti-crossing and this is manifested in, for example, the appearance of two lines in the reflectivity spectrum.

It was hoped during the 1970s that laser action in wide bandgap material such as ZnSe would be possible based on excitonic lasing. In this process a quasi-equilibrium exciton population would form the injected excitation and stimulated recombination would occur with the associated emission of a scattering partner which would take up the necessary momentum to ensure overall momentum conservation. This leads to a light emission wavelength below the absorption edge which is advantageous for minimizing losses. In fact, this process has only been seen at low temperature for scattering with LO-phonons, electrons and other excitons. Each mechanism has its own characteristic lasing threshold and temperature dependence.

Influence of Quantum Confinement

The advent of Molecular Beam Epitaxy enabled the growth of semiconductor layers of thickness similar to the electronic de Broglie wavelength. By sandwiching a low bandgap semiconductor between two high bandgap layers, one can make quantum well structures in which the electronic motion is effectively confined to the plane of the layer. In such structures the excitonic properties are also radically altered by this confinement. An example of the absorption spectrum of a ZnCdSe quantum well embedded in ZnSe is shown in Figure 2. The heavy and light hole excitons correspond to different spin quantum numbers for the electron and hole making up the exciton.

The exciton binding energy is enhanced by a factor of 4 compared to the bulk case and the spatial extent of the 1s wavefunction is also reduced by half:

$$E_b^{2D} = \frac{\mu e^4}{8\mathrm{h}^2\varepsilon_r^2\varepsilon_0^2}\,\frac{1}{(n-\frac{1}{2})^2} \qquad n = 1, 2, 3\ldots \qquad [3]$$



Figure 2 Heavy and light hole exciton absorption spectrum for ZnCdSe quantum wells embedded between ZnSe barriers. Also shown is the bulk exciton of the ZnSe barriers.

This enhancement can be understood since the particles are confined to lie in the plane and are hence closer together on average than in the three-dimensional case. In practice, a four-fold enhancement in the binding energy is never observed since the quantum wells are neither infinitely deep nor infinitely thin. Both these limitations lead to a reduction in the actual enhancement from 4 to about 2, depending on the structure. For example, the binding energy in a realistic quantum well corresponds to the bulk value of the well material for very wide wells and to the bulk value of the barrier material for very narrow wells. In between the value is enhanced by the quantum confinement. The maximum enhancement typically occurs when the well width is around half the bulk Bohr radius for the well material.

Accurate calculation of the exciton binding energy is complicated by the fact that the quantum confinement influences the band structure, making it strongly anisotropic and splitting heavy and light holes. A complete inclusion of these effects is at the limit of current computational power due to the need to calculate the electron-hole interaction matrix elements. Approximate schemes, including variational approaches, have proved successful in fitting a variety of samples, including GaAs and ZnSe based quantum wells. The limitation to such calculations is often the requirement for accurate values of the material parameters such as effective masses and energy band offsets.

The Sommerfeld enhancement of the absorption into the continuum states of quantum wells leads to a doubling of the absorption at the bandedge. This enhancement reduces only slowly as the photon energy is increased.

If multiple quantum wells with very thin barrier layers are used, the electronic states in the neighboring wells couple together to form a superlattice. The superlattice dispersion in the growth direction behaves like a heavy mass and the resulting exciton is three-dimensional but strongly anisotropic.

More extreme quantum confinement is possible making quantum wires, by etching or selective growth of quantum well samples. In these quasi-one dimensional structures, as in quantum wells, the exciton binding energy is again increased further. The Coulomb problem in one-dimension is pathological in that the ground-state binding energy diverges logarithmically, and higher states are pairwise degenerate. However, accounting for the finite cross-section of realistic wires eliminates this problem and recovers a finite binding energy. One consequence of this is that there is no simple enhancement factor which corresponds to the four-fold enhancement in going from bulk to two-dimensional excitons. The density of states in one-dimensional systems diverges at the bandedge, implying the existence of an infinite absorption in a perfect quantum wire. However, the influence of excitonic correlations cancels this divergence, resulting in an enhanced, but not divergent, bandedge absorption feature.

The ultimate limit in quantum confinement can be achieved in quantum dots, where the carriers are confined in all three directions. In this case the term exciton should be used with some care as there are no bandedge states to compare with. The discrete energy levels dictated by the confinement are affected by the Coulomb interaction and the energy is renormalized – in some cases substantially. The absorption spectrum should consist of a series of sharp atomic-like transitions corresponding to s-s, p-p, d-d,... transitions and indeed luminescence spectra obtained from single quantum dots do display such fine structure. Even in the best controlled material systems, such as InAs quantum dots, the spectra are strongly inhomogeneously broadened due to variations in the dot size, shape, and alloy composition.

In large quantum wells, where the width is larger than the exciton Bohr radius the center-of-mass part of the wavefunction can be confined by the barriers. This leads to a quantized motion for the exciton as a whole, rather than for the individual electron and hole separately. One implication of this is that for such excitons the center-of-mass momentum is no longer a good quantum number.

The above effects are a controlled case of disorder induced effects in semiconductors. This is an area which is only now beginning to be understood. The presence of local potential fluctuations will influence the energy spectrum of excitons in that vicinity. Clearly both the depth and spatial extent of these fluctuations will be important – very short range (less than Bohr radius), shallow potential fluctuations will not have any influence on the exciton. While deep potentials can lead to the center of mass confinement above.

Influence of Electric and Magnetic Fields

Just as an externally applied electric field affects the absorption edge via the Franz–Keldysh Effect, broadening the edge itself and inducing oscillations in the continuum part of the spectrum, so, in the case of an excitonic bandedge, there is substantial modification due to the presence of the field. At low fields, when the Coulomb interaction is strong compared to the potential drop across the exciton diameter, the exciton will be little affected by the applied field. At higher fields the exciton will become gradually more polarized by the field until the exciton is field ionized. This ionization process is manifested in the field broadening of the exciton line (see Figure 1).

Of more technological importance is the influence of an electric field applied perpendicular to the plane of a quantum well. The field forces the electron and hole in opposite directions leading to a reduction in the exciton binding energy. This would lead to a blue shift in the exciton absorption peak were it not for an even larger reduction in the single particle electron and hole energy levels within the quantum wells. Overall a strong red-shift of the excitonic absorption peak is observed with increasing field. This is accompanied by a reduction in the oscillator strength due to the reduced electron-hole overlap. This is termed the Quantum Confined Stark Effect and is the basis for the operation of some semiconductor electro-optic modulators. An electric field applied in the plane of the quantum well gives rise to Franz–Keldysh oscillations analogous to the bulk case.

The influence of magnetic fields on excitons is more subtle and richer than the electric field. This is because the magnetic field seeks to induce a circular cyclotron orbit motion on the carriers, but this is influenced by their mutual Coulomb interaction. Two regimes exist where either the cyclotron energy:

$$\hbar\omega_c = \hbar(eB/\mu) \qquad [4]$$

or the exciton binding energy dominates. In the former strong field case, one can treat the Coulomb interaction as a small perturbation on the electron and hole states in the presence of the magnetic field. In exciton states, which have a finite magnetic moment at zero field, we find a linear Zeeman shift in the magneto-exciton energy. In the other case we must use the magnetic field as the perturbation which produces a mixing of the zero-field exciton states. For example, for the ground state the magnetic field induces an admixture of the p-like excited state with the s-like ground state. The total angular momentum of the mixed state is proportional to B and as the energy of a magnetic dipole in a magnetic field is also proportional to B the shift of the magneto-exciton is proportional to B^2. This distinction between linear and quadratic shifts has been used to identify the nature of carrier populations (excitons or unbound free carriers) in a variety of samples. Clearly there exists an intermediate regime where both the magnetic and Coulomb energies are comparable and in this case the precise energy shifts need to be evaluated numerically.

In quantum well samples the orientation of the magnetic field with respect to the confinement direction is crucial in determining the physics. When the field is perpendicular to the confinement plane the cyclotron orbits exist as before and essentially the same phenomenon as in the bulk emerge. For other orientations, the behavior is much more complex and beyond the scope of this article.

Exciton Scattering

An electron and hole in an excitonic bound state execute a correlated motion which can be disturbed by scattering of either partner. This may lead to the ionization of the exciton and the destruction of the correlation or, alternatively, it may change the center of mass momentum of the exciton as a whole. Almost all of the important scattering mechanisms for excitons arise from the charged nature of the electron and hole. Via the Coulomb interaction, excitons can scatter with lattice phonons, other excitons, free carriers, and impurities. Each of these scattering processes has its own regime of dominance, dependent on, for example, temperature or material quality.

When the scattering rate with other particles is much larger than the recombination rate for electrons and holes, a quasi-equilibrium state is reached. The detailed nature of such an interacting electron/hole plasma remains a a long-standing open question. The reasons for this can be traced to interplay between the intrinsic Coulomb interactions within the plasma, which give rise to both bound and scattering states, and Pauli exclusion arising from the fermionic nature of the electrons and holes. This leads to a complex phase diagram which encompasses, e.g., electron-hole droplets, the ionized electron-hole plasma, biexciton phase, and the exciton gas which, some suggest, may undergo Bose–Einstein condensation. The parameters of this phase diagram are carrier density, temperature, and the semiconductor material parameters. Interest in this essentially fundamental question has remained high, stimulated by the stream of technological benefits that even partial answers have brought.

In this context it is worth mentioning that there have been two theoretical approaches to exciton physics which each have their advantages and problems. One approach is to treat excitons as bosonic quasi-particles and derive results from Hamiltonians formulated using bosonic operators. This approach has the appeal of simplicity and produces acceptable results in the low-density regime. It does, however, omit a key feature of the constituent particles making up an exciton namely the fermionic nature of electrons and holes. A more rigorous approach based around electron and hole operators has been followed but this is considerably more complex and numerically involved.

Excitonic Molecules

Just as two hydrogen atoms can lower their total energy by forming a bound hydrogen molecule, so two excitons can make a bound complex which has lower energy than the two isolated excitons. Such complexes are called biexcitons and are mostly important in high quality material and at low temperatures. Their binding energy is less than that of the exciton by a factor of about 0.1–0.3, depending on the ratio of electron to hole effective masses.

Three particle complexes have also been observed consisting of two electrons bound to a hole. These are termed trions or charged excitons. Their binding energy lies intermediate between excitons and biexcitons.

See also

Semiconductor Materials: GaAs Based Compounds; Large Gap II–VI Semiconductors; Type-II Quantum Wells and Superlattices. **Semiconductor Physics:** Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures.

Further Reading

Bastard G (1998) Wave Mechanics Applied to Semiconductor Heterostructures. New York: Halstead John Wiley.

Haug H and Koch SW (1993) *Quantum Theory of the Optical and Electronic Properties of Semiconductors*. Singapore: World Scientific.

Klingshirn CF (1997) *Semiconductor Optics*. Berlin: Springer.

Rashba EI and Sturge MD (eds) (1982) *Excitons*. Amsterdam: North Holland.

Schmitt-Rink S, Chemla DS and Miller DAB (1989) Linear and nonlinear optical properties of semiconductor quantum wells. *Advances in Physics* 38: 89–188.

Ueta M, Kanzaki H, Kobayashi K, Toyozawa Y and Hanamura E (1986) *Excitonic Processes in Solids*. Berlin: Springer.

Yu PY and Cardona M (1999) *Fundamentals of Semiconductors*. Berlin: Springer.

Impurities and Defects

K A Prior, Heriot-Watt University, Edinburgh, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

A simple definition of a defect is any feature that disturbs the periodicity of the perfect lattice. This definition is sufficiently broad to encompass a whole range of different entities, which are normally divided into three categories based on their dimensionality, or extent in real space.

0D defects are those which have an extent of the order of only a few atomic spacings at most in any direction. They include all cases where one, or at most a few, atoms are removed or displaced, or are replaced by atoms of a different type.

1D defects are linear features within the crystal that extend over many atomic dimensions. The most important type of 1D defect is the dislocation and in a single crystal it is possible for a dislocation to extend from one side of the crystal to the other.

2D defects include a variety of different features that occur primarily in one plane. Any junction between two different types of crystal in an epitaxially grown layer (a heterointerface) fits this description, as of course does the sample surface. There are also crystal defects which exist in two dimensions of which the most important is the stacking fault.

Finally, there are also 3D defects. This category includes voids and inclusions, which are both major perturbations in a crystal structure. In most pure crystals grown by modern techniques these are eliminated and they will not be discussed further.

In the sections below the main types of defect will be discussed according to the scheme described above. Despite the substantial research effort to understand the basic properties of many semiconductors, and of course the huge effort devoted to producing semiconductor devices, it remains true that the defect structure of most semiconductors is still poorly understood, with the exceptions of silicon and gallium arsenide. This is especially true in the case of the nitride semiconductors with the wurtzite structure which have recently been the subject of much commercial interest. In the following sections examples will mainly be taken from gallium arsenide.

Lastly, it is important to note that defects of different dimensionality interact. Several possible interactions are discussed in the last section.

0D Defects

Dopants

There are two basic types of 0D defects to consider: chemical defects, or impurities, and native or point defects caused by missing or misplaced atoms. Table 1 gives the major types of 0D defect found in compound semiconductors together with the symbol used in the common notation for point defects and impurities.

Impurity atoms are those which are introduced either accidentally during the production of the bulk crystal or epitaxial layer, or deliberately by the crystal grower in precisely controlled amounts to modify some property of the material. Usually, this means that the material added is a dopant, and has been added to create a surplus of either free electrons or holes in the semiconductor. Typically, the amounts of dopants added are between 10^{-6} and 10^{-3} mole fraction, giving doping levels between $10^{22}\ \mathrm{m}^{-3}$ and $10^{25}\ \mathrm{m}^{-3}$.

Table 1 Impurities and point defects in a compound *AB* with the zincblende lattice structure

Symbol	*Description*
X_A^n, X_B^n	Impurity atom, *X*, on *A* or *B* site with charge *n*
X_i^n	Interstitial impurity atom with charge *n*
V_A^n, V_B^n	Vacancy on *A* or *B* site with charge *n*
A_i^n, B_i^n	Interstitial *A* or *B* atom with charge *n*
A_B, B_A	*A* atom on *B* site or *B* atom on *A* site (antisite)

In general, any atom added to a material will introduce a localized state into the band structure of the semiconductor. This state may rarely occur in either the conduction or valence band, but is more likely to be located in the bandgap. If the localized energy level is within a few kT of the valance or conduction band edge, then the state is an electron acceptor or donor. If it is much further from the band edge then it is usually known as a deep level. In this case its main effect on the electrical properties will be to act as a trap for electrons or holes, and introduce noise into the current flow. Its effect on the optical properties of the material will be to reduce the radiative recombination rate for band-to-band transitions by acting as an alternate recombination pathway for either radiative or nonradiative transitions.

It is generally assumed that dopant atoms occur only on the site of the appropriate sublattice and are well behaved. While it is true that some elements are well behaved substitutional dopants, such as sulfur in gallium arsenide, which can be denoted $\mathrm{S}_{\mathrm{As}}^{+}$ when acting as a singly charged donor, the behavior of other species is more complex. In many III–V compounds, silicon is an amphoteric dopant, occupying sites on both the metal and nonmetal sublattices which ionize as shown:

$$\mathrm{Si}_{\mathrm{Ga}}^{0} = \mathrm{Si}_{\mathrm{Ga}}^{+} + \mathrm{e}^{-}$$

$$\mathrm{Si}_{\mathrm{As}}^{0} = \mathrm{Si}_{\mathrm{As}}^{-} + \mathrm{h}^{+}$$

In molecular beam epitaxy (MBE) growth on GaAs(100) the ratio between the donor $\mathrm{Si}_{\mathrm{Ga}}^{+}$ and the acceptor $\mathrm{Si}_{\mathrm{As}}^{-}$ varies as the concentration of doping is increased. At low levels silicon is a donor, while at high concentrations the fraction which is an acceptor increases rapidly. The semiconductor is therefore compensated, effectively limiting the maximum concentration of free carriers.

Another type of behavior occurs with beryllium in III–V semiconductors and lithium in II–VI semiconductors. Here, the dopant atom is so small that it can easily be displaced from the lattice site. Thus, for example, in InGaAs, it is energetically favorable for the acceptor $\mathrm{Be}_{\mathrm{In}}^{-}$ atom to move from the lattice site to an interstitial position:

$$\mathrm{Be}_{\mathrm{In}}^{-} = \mathrm{V}_{\mathrm{In}}^{-} + \mathrm{Be}_{\mathrm{i}}^{+} + \mathrm{e}^{-}$$

The interstitial Be ion is a donor and causes some compensation, but even worse, is highly mobile. It can move a substantial fraction of a micron in an epitaxial device and in so doing completely destroys a carefully engineered abrupt p-n junction. It can be seen therefore that dopant interactions with the host lattice are important in determining device performance.

Native Defects

A large variety of native defect species are possible in semiconductors. Interstitial atoms and vacancies are found in both the diamond structure (silicon) and the zincblende structure (most III–V and II–VI semiconductors). In zincblende structures there is also the possibility of placing an atom on the wrong atomic site, or sublattice; for example in GaAs a Ga atom may be found on an As site. This type of defect is known as an antisite.

Bulk semiconductor crystals are grown under conditions close to equilibrium. In the long periods of time needed to grow the crystals, equilibrium concentrations of point defects are established. Epitaxial growth techniques (in particular molecular beam epitaxy, MBE and metalorganic chemical vapor deposition, MOCVD) operate under conditions far from equilibrium and the point defect concentrations may differ markedly from the equilibrium values. Some semiconductor processing operations can also increase point defect concentrations. Etching semiconductors with ion beams or energetic plasmas is a very efficient way of creating in the subsurface region high concentrations of point defects well above the equilibrium values.

It is possible to anneal crystals in the vapor of one of the constituent elements to alter the point defect concentrations. Interstitial and vacancy concentrations can be changed relatively rapidly over the course of several hours (interstitials) or days (vacancies) as these species are much more mobile than dopant atoms. Usually, annealing is done to reduce point defect concentrations, but on occasions, for example with the alloy HgCdTe, it is done to increase the concentration of a type of defect, in this case mercury vacancies which are used to dope the material.

Like dopant atoms, point defects can also introduce defect levels into the band structure of the semiconductor, and some defects, for example the gallium vacancy $\mathrm{V}_{\mathrm{Ga}}^{n-}$, exist in multiple charge states. In some materials, the native defects act either as dopants or as compensating traps, and are present in concentrations that can severely limit the maximum obtainable doping levels. The gallium vacancy, for example, is believed to limit the maximum doping level obtainable in n-type GaAs, and its concentration increases dramatically as the concentration of n-type dopant is increased.

It should be noted that the concentrations of the various types of defect are not independent of one another, and at any given growth (or annealing) temperature and applied partial pressures of the constituent elements, the equilibrium concentrations of the defects are fixed. Examples of the interactions between the types of defect may be seen by considering the displacement of a gallium atom from its lattice site to create a vacancy and an interstitial (the Frenkel reaction):

$$\mathrm{Ga}_{\mathrm{Ga}}^{0} = \mathrm{Ga}_{\mathrm{i}}^{0} + \mathrm{V}_{\mathrm{Ga}}^{0}$$

and the interaction of an arsenic interstitial with a gallium vacancy to create an arsenic antisite:

$$\mathrm{As}_{\mathrm{i}}^{0} + \mathrm{V}_{\mathrm{Ga}}^{0} = \mathrm{As}_{\mathrm{Ga}}^{0}$$

The relative importance of the types of defect varies between semiconductors. In compounds where one of the elements is very volatile, then high concentrations of vacancies on that particular sublattice are to be expected. Antisites occur only at very low concentrations in the ionic II–VI compounds, as the energy involved in placing an atom on the wrong sublattice is very high. However, in the more covalent III–V compounds, there is not such a large energy penalty, and it has been suggested that in GaAs the $\mathrm{As}_{\mathrm{Ga}}$ antisite may be the most common point defect.

In addition to the simple defect types described above, there are other possibilities. One of these is that complexes of defects may form. The best known are the complexes that occur between dopant atoms and vacancies, for example the $[\mathrm{Te}_{\mathrm{As}}\mathrm{V}_{\mathrm{Ga}}]^{-}$ complex found in Te doped GaAs (Figure 1). In this material, partial compensation of the n-type dopant occurs with the formation of gallium vacancies, as described above:

$$\frac{1}{2}\mathrm{As}_2(\nu) = \mathrm{V}_{\mathrm{Ga}}^{0} + \mathrm{As}_{\mathrm{As}}$$

$$\mathrm{V}_{\mathrm{Ga}}^{0} = \mathrm{V}_{\mathrm{Ga}}^{2-} + 2\mathrm{h}^{+}$$

These vacancies are mobile and diffuse in the material. In the vicinity of $\mathrm{Te}_{\mathrm{As}}^{+}$ they experience a strong Coulombic attraction and the complex forms when the vacancy and dopant atom are on nearest neighbor sites:

$$\mathrm{V}_{\mathrm{Ga}}^{2-} + \mathrm{Te}_{\mathrm{As}}^{+} = [\mathrm{V}_{\mathrm{Ga}}\mathrm{Te}_{\mathrm{As}}]^{-}$$



Figure 1 Diagram of the tellurium atom–vacancy complex in GaAs. Gallium and arsenic atoms are shown in mid-gray and white, respectively, while the tellurium atom is shown in dark gray.



Figure 2 Diagram of the silicon atom–vacancy complex in GaAs. Gallium and arsenic atoms are shown in mid-gray and white, respectively, while the silicon atom is shown in dark gray.

A similar complex also forms in Si doped GaAs: $[\mathrm{Si_{Ga}V_{Ga}}]^-$ (Figure 2), although here both species exist on the same sublattice, and consequently occur as next nearest neighbors in the complex.

In the description above it is assumed that all atoms which are located on a particular site are centered on that site. However, it is possible for a dopant atom to replace an atom of the host semiconductor, but not occupy the lattice site. *Ab initio* calculations of the bonding around the dopant atom suggest that it can be displaced away from one of its nearest neighbors towards the other three atoms (Figure 3). The dopant can be considered as having one bond weaker than the other three.

In the case of n- and p-type doped semiconductors the corresponding defects are known as DX and AX centers respectively. DX centers occur in many semiconductors but are particularly important in AlGaAs, where Si (or other n-type dopant) atoms form DX centers that partially compensate the material and reduce the electron mobility. However, irradiation with white light excites the DX center and converts it back to a normal dopant centered on the lattice site. In AlGaAs the DX center is the stable species and the dopant atom is a higher energy state. Conversion back to the DX center requires surmounting an energy barrier and thus the normal dopant is metastable. The irradiated semiconductor has a lower concentration of DX and a higher doping concentration than before, and consequently has a higher conductivity than the unirradiated material. This results in persistent photoconductivity in the irradiated material, which is a characteristic feature of semiconductors containing DX centers. At low temperatures, this effect can persist for many hours.



Figure 3 A GaAs crystal shown with [111] oriented vertically. Two Ga atoms have been substituted by silicon atoms which are shown in dark gray. One Si atom is on a substitutional site (top atom) and the other is displaced along [111] away from one of its nearest neighbors (bottom atom). This is one of the structures suggested for the DX center.

1D Defects

Within any crystal, there must exist a set of planes where the interplanar bonding is weakest. In both the diamond and zincblende crystal structures these are the {111} planes. When a crystal is subjected to a shear stress above its elastic limit, then the material accommodates that stress by changing shape, alternately breaking and reforming bonds across these planes where the bonding is weakest. The resulting movement is easily observable under a microscope in many materials and is known as slip or glide; the planes on which this happens are known as slip or glide planes.

Movement on a slip plane does not happen over the whole crystal at once, and there is always a boundary between the material in which slip has occurred and material where it has not. This boundary is the dislocation. A section through a piece of material where slip has occurred is shown in Figure 4. The curved line DD′ marks the dislocation and slip has occurred in the region marked DQD′. Because it marks a boundary, the dislocation may not end within the crystal and the only permitted ways that a dislocation may terminate are to finish at the surface of the crystal (as shown) or to meet another dislocation, forming either a closed loop or a junction.

Across the slip plane, the material has moved by a certain amount, which is, typically, a lattice vector within the crystal. The direction of slip is known as the Burgers vector of the dislocation, and it is a constant for any one dislocation. The Burgers vector at any point may be determined by describing a simple loop in the crystal passing through adjacent lattice points lying in one plane. If a dislocation lies within the loop then the ends will not close, and the displacement needed to close the loop is the Burgers vector. This can be seen in Figure 4 on the left-hand face of the crystal around point D, where the Burgers vector is parallel to the line of the dislocation. It can also be seen on the right hand face of the crystal at point D′, where the Burgers vector, which has not changed direction, now lies perpendicular to the dislocation line. Dislocations where the Burgers vector is parallel or perpendicular to the dislocation line are known as screw and edge dislocations, respectively.



Figure 4 Diagram of a crystal showing a region where slip has occurred. For clarity only the lattice points are shown. The slip plane is PQRT and the slipped region is DQD′. The curve DD′ is the line of the dislocation and has a Burgers vector **b**.

Examples of edge and screw dislocations are shown in Figures 5 and 6, respectively. Edge and screw dislocations are considered to be 'pure' types of dislocations. If the Burgers vector makes any other angle to the dislocation line, the dislocation is referred to as a mixed dislocation. In semiconductors mixed dislocations are the most common type. There are many different ways of describing dislocations; however, the most common one is to give the angle between the dislocation line and the Burgers vector. In this system screw and edge dislocations are referred to as 0° and 90° dislocations.

At the core of the dislocation there is a small region, typically only one or two atoms wide, where the atoms have highly distorted bonding. Around this



Figure 5 A schematic diagram of an edge dislocation. Only the lattice points are shown for clarity. The slip plane is PQRT and contains the Burgers vector denoted **b**. The line of the edge dislocation is EE′, which can be thought of as terminating a half-plane of atoms denoted ABEE′.



Figure 6 A schematic diagram of a screw dislocation. Only the lattice points are shown for clarity. The slip plane is PQRT and contains the Burgers vector denoted **b**. The line of the screw dislocation is SS′.

core the atoms adopt the normal (tetrahedral) bonding, although they are strained for many nanometers around the dislocation. The strain field around the dislocation means that low dislocation densities are very easy to detect using a technique such as X-ray topography, which images the strain introduced locally in a set of crystal planes by a dislocation. Using this technique, individual dislocations may be determined within crystals. Currently, it is possible to obtain silicon crystals which are essentially dislocation free, while the best GaAs crystals have dislocation densities of $<10^5$–$10^6\,\mathrm{m}^{-2}$. In other materials the densities may be 100–1000 times higher.

The highly distorted bonding at the core of the dislocation inhibits dislocation motion. Under the action of an external stress, dislocations normally move on their glide plane to relieve the stress and deform the material plastically. This is dislocation glide. In covalent semiconductors, such movement means breaking and reforming strong bonds, and does not occur in silicon below the crystal growth temperature. Dislocations are also immobile in GaAs at room temperature, although they can be induced to move in softer, more ionic II–VI semiconductors. Dislocation densities are therefore usually considered 'frozen in' at room temperature.

In addition to macroscopic shear forces, each dislocation experiences the stresses introduced by other dislocations and point defects present in the crystal, and is either attracted or repelled by them. At high densities, therefore, the motion of dislocations is inhibited by the presence of the surrounding defects – the dislocations are said to be pinned.

Generation and movement of dislocations occurs in most semiconductors easily at their growth temperature, and is important in the relief of strain introduced in growing a material on a substrate with a different lattice constant. Edge dislocations always introduce, or remove, extra planes of atoms (Figure 5), and so an array of dislocations can add or remove atoms to accommodate the strain between two semiconductor layers of different lattice constant. These are known as mismatch dislocations and they occur frequently in epitaxial growth when strain relief has occurred.

Typically, growth in MBE or MOCVD occurs on the (001) surface. Mismatch dislocations lie on the {111} planes, which intersect this plane, and at low densities occur in crystals regularly spaced along [110] and $[1\bar{1}0]$ directions. The Burgers vectors are also of ⟨110⟩ type and are typically at 60° to the dislocation line. The edge component of this vector, projected on to the (001) plane, gives the amount of strain relief to be expected.

Despite the distorted bonding that exists around the dislocation core, there are thought to be remarkably few broken bonds there. An exception to this is thought to be when the dislocation line is not straight, but kinked, the atoms at the kinks having broken bonds. As a result, nonradiative transitions involving dislocations are not strong. They are important, however, during operation of lasers and LEDs. Dislocations can be seen in electroluminescence of light-emitting devices as dark lines. These so-called dark-line defects (DLDs) are the result of nonradiative recombination occurring at dislocations. Not only do they reduce the efficiency of the device, but the energy released by the recombination of the electron and hole is deposited at the dislocation core as thermal energy. Under these conditions, dislocation movement becomes easy and DLDs propagate, eventually destroying the device.

2D Defects

In a simple description of metallic structures, the hexagonal close packed structure is described as a sequence of hexagonal sheets with the stacking pattern *ABABABAB*..., while that of the face centered cubic structure is *ABCABCA*... In a similar manner, we can describe the wurtzite crystal structure by the stacking sequence *ABABABAB*..., although the layers are no longer close packed and the stacking units comprise one metal and one nonmetal atom. The corresponding stacking sequence for the zincblende structure then becomes *ABCABCA*... These structures are shown in Figures 7a and b, respectively. It can be seen that the two atom units are oriented perpendicular to the stacking sequence, and it is possible to rotate the structure about the vertically oriented bonds between any two given planes. A rotation of 180° would place all the atoms back in registry but on the wrong site. For example, in a zincblende crystal, a rotation after the third layer in the sequence *ABCABCA*... would result in *ABCBCAB*... This means that the top part of the crystal is related to the bottom half by a rotation of 180°, and the two parts are said to be twinned. The twin plane extends throughout the crystal, and is a two-dimensional defect. Both above and below the twin plane, the stacking sequence is the usual *ABC*... found in the zincblende structure; however, at the junction there is a region denoted *BCB*. This region is three planes of the wurtzite stacking sequence, and is an example of what is called a stacking fault. In zincblende crystals, stacking faults introduce small regions of the wurtzite structure, while the reverse happens in wurtzite crystals.



Figure 7 Diagrams of the stacking sequence of layers for two different semiconductor structures. In both cases the metal atoms are small and dark while the larger pale ones are the nonmetal atoms. The structures are: (a). The wurtzite crystal structure. The atoms which occupy the A, B and C sites are marked. Here the vertical direction in which the planes stack is the [0001] direction. (b). The zincblende crystal structure. The atoms which occupy the A and B sites are marked and the vertical direction corresponds to one of the ⟨111⟩ directions in the crystal.

The density of stacking faults in a material is primarily a function of the ease of placing the crystal planes in the wrong order. Under nonequilibrium growth conditions, this can occur easily for many different materials, but for slow growth near equilibrium, the prevalence of stacking faults is governed by the stacking fault energy. This is a measure of the wrong stacking sequence occurring and is also related to the energy of transformation between the zincblende and wurtzite crystal structures. For GaAs, the energy is high and stacking faults are rare, while for II–VI semiconductors the stacking fault energies are low and stacking faults are relatively common.

Typically, stacking faults are observed in TEM planar view micrographs, and on (001) oriented epitaxial samples are clearly visible as triangular regions lying on {111} planes, as described above, nucleated at the interface between the substrate and epitaxial layer.

While stacking faults are accidental introductions in a crystal structure, other 2D defects are introduced deliberately. Heterojunctions between different semiconductor alloys are an obvious example and are responsible for most of the useful properties of advanced semiconductor devices. However, by far the most important 2D crystal defect is the surface of the crystal. This creates a high density of broken bonds, each of which can introduce a defect level in the band structure. Surfaces usually lower their free energy by moving atoms from the bulk equilibrium positions to new sites and forming extra bonds in the plane of the surface. This removes some of the defect levels, but it is still possible to have surface defect densities as large as $10^{18}\,\mathrm{m}^{-2}$ which are associated with enhanced rates of nonradiative recombination of electrons and holes.

Interactions of Defects

Earlier it was assumed that the Burgers vector associated with a dislocation is a lattice vector. The energy of a dislocation per unit length is proportional to the magnitude of the Burgers vector squared:

$$E \propto b^2$$

In some crystals, however, it is possible for the displacement to be composed of two smaller steps, neither of which is a complete lattice vector:

$$\mathbf{b} = \mathbf{b}_1 + \mathbf{b}_2$$

where $\mathbf{b}$ is a lattice vector and $\mathbf{b}_1$ and $\mathbf{b}_2$ are the smaller displacements. In this case, the total energy



Figure 8 An example of a close packed structure where a region with a stacking fault lies between two partial dislocations.

can be reduced if the dislocation splits into two:

$$E_1 + E_2 \propto b_1^2 + b_2^2 < E$$

These dislocations are known as *partial* dislocations. A normal dislocation splits into two partial dislocations if it is energetically favorable to do so. Figure 8 shows an example in a close packed structure, which illustrates the point without the problem of introducing two different types of atoms. Two partial dislocations run through the top layer. The material lying between them has a different stacking sequence (AC) from the material around it (AB) and must contain a stacking fault. This shows that a 2D defect, such as a stacking fault, is bounded by two 1D defects, in this case partial dislocations.

There also exists an intimate relationship between point defects and dislocations, which may be seen by examining the edge dislocation shown in Figure 5. The edge dislocation may be considered as an extra half-plane of atoms, ABEE′ which terminates along line EE′. The last row of atoms in the plane can be removed from the sheet by one of two processes. Firstly, the atoms at the dislocation core can become interstitials and diffuse away from the dislocation. Alternatively, vacancies can diffuse towards the dislocation. In either case the result is the same; the dislocation line EE′ moves upwards towards AB. The opposite sequence of events (diffusion of interstitials towards the dislocation or vacancies away from it) is also possible and results in a movement of line EE′ downwards. Such processes are known as dislocation climb. Climb is not as common as glide, but it is important as the dislocation acts as a source or sink for point defects. This process contributes to the reduction in radiative efficiency in LEDs and lasers, particularly as the devices age.

See also

Semiconductor Physics: Outline of Basic Electronic Properties; Quantum Wells and GaAs-based Structures.

Further Reading

Beanland R, Kiely CJ and Pond RC (1992) Dislocations in heteroepitaxial films. In: Mahajan S (ed.) *Handbook on Semiconductors. Materials, Properties and Preparation*, vol. 3a, pp. 1149–1225. Amsterdam: North-Holland.

Fukuda M (1991) Reliability and Degradation of Semiconductor Lasers and LEDs. Boston, MA: Artech House.

Hirth JP and Lothe J (1982) Theory of Dislocations. New York: Wiley.

Hull D (1965) Introduction to Dislocations. Oxford, UK: Pergamon Press.

Hurle DTJ (1999) A comprehensive thermodynamic analysis of native point defect and dopant solubilities in gallium arsenide. *Journal of Applied Physics* 85: 6957–7022.

Kelly A, Groves GW and Kidd P (2000) Crystallography and Crystal Defects, revised edn. Chichester, UK: Wiley.

Kossevich AM (1999) The Crystal Lattice. Berlin: Wiley-VCH.

Malloy KJ and Khachaturyan K (1993) DX and related defects in semiconductors. In: Willardson RK and Beer AC (eds) *Semiconductors and Semimetals*, pp. 235–291. New York: Academic Press.

Schubert EF (1993) Doping in III–V semiconductors. In: Ahmed H (ed.) *Cambridge Studies in Semiconductor Physics and Microelectronic Engineering*, vol. 1. Cambridge, UK: Cambridge University Press.

Skowronski M (1992) Impurity- and defect-centres in compound semiconductors. In: Mahajan S (ed.) *Handbook on Semiconductors. Materials, Properties and Preparation*, vol. 3a, pp. 1343–1398. Amsterdam: North-Holland.

Infrared Lattice Properties

T J Parker and S R P Smith, University of Essex, Colchester, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The vibrations of atoms in solids were first studied theoretically at the beginning of the twentieth century to explain the observed temperature dependence of the heat capacity. Following earlier work by Einstein and Debye, Born and von Karman showed in 1912 that the vibrational properties of a linear chain of alternate light and heavy atoms connected by springs account very well for the observed thermal behavior of solids. It was shown many years later that, if the atoms are alternately positively and negatively charged, the model also gives a good description of the optical properties.

In this article the vibrational properties of a linear diatomic chain of atoms are first described. The model gives a good description of the basic vibrational properties of solids with two atoms per unit cell, such as Si, Ge, and the binary III–V (e.g., GaAs) and II–VI (e.g. CdTe) semiconductors, and explains the origin of optic and acoustic branches of the phonon dispersion curves. This leads naturally to an understanding of the basic far-infrared reflectivity of binary semiconductors. The model is then further developed to account for the effects of impurities and the optical properties of alloys.

The far-infrared properties of semiconductors are then reviewed. We begin with the group IV semiconductors Si and Ge in which there is no first-order interaction with infrared radiation, and explain the origins of second-order interactions, and the effects of disorder and impurities. Examples of the first-order reflection spectra of bulk single crystal binary semiconductors and their alloys are then presented. Localized vibrational modes and phonon combination bands are discussed next. We finish with a brief review of more exotic excitations that occur in layered semiconductors: confined optic modes, surface phonon polaritons, guided waves, and interface modes.

Background Theory of Phonons in Semiconductor Materials

Phonons in a Diatomic Linear Chain Lattice

Consider a line of atoms of alternating type A and B, separated by a distance a, as shown in Figure 1. Suppose that the nth A atom is displaced by a small amount $u_{A,n}$ from its equilibrium position. The forces attempting to return it to its equilibrium position will be proportional to the distance it has moved relative to the neighboring atoms. If we assume that the only significant force involves the nearest neighbor B atoms n and $n+1$, the equation of motion for the nth A atom is

$$M_A \frac{d^2 u_{A,n}}{dt^2} = C(u_{B,n} + u_{B,n+1} - 2u_{A,n}) \qquad [1]$$



Figure 1 Atomic displacements in a diatomic linear chain.

where M_A is the mass of the atom, and C is the Hooke's law nearest-neighbor force constant. There is a similar equation

$$M_B \frac{d^2 u_{B,n}}{dt^2} = C(u_{A,n-1} + u_{A,n} - 2u_{B,n}) \qquad [2]$$

for the motion of the nth B atom. We assume that the solution of the equations of motion has the wavelike form

$$\begin{aligned} u_{A,n} &= U_A \exp\{i(qan - \omega t\} \\ u_{B,n} &= U_B \exp\{i(qan - \omega t\} \end{aligned} \qquad [3]$$

in which U_A and U_B are amplitude factors, ω is the angular frequency, and q is the wavevector, so that qa is the phase factor by which the phase of the wave changes from one site n to the next site $n+1$. The equations of motion are satisfied so long as the angular frequency ω is given by

$$\begin{aligned} \omega^2 = \frac{C}{M_A M_B}\Big[& M_A + M_B \\ & \pm \sqrt{(M_A + M_B)^2 - 4M_A M_B \sin^2(qa/2)}\Big] \end{aligned} \qquad [4]$$

There are two possible solutions here because there are two ions in the unit cell. A plot of ω as a function of q is shown in Figure 2a, with q in the range $-\pi/a$ to $+\pi/a$. In the lower branch, the *acoustic* phonon branch, the vibrations at long wavelength (equivalent to small q) are essentially the same as ordinary sound waves. The A and B atoms vibrate in phase, and at long wavelength there is a linear relation between ω and q:

$$\omega \approx v_s q \qquad [5]$$



Figure 2 (a) Phonon frequency ω versus wavevector, q, in a one-dimensional diatomic lattice; (b) three-dimensional density of states $D(\omega)$.

where $v_s = \omega_0 a/2$ is the velocity of sound of the acoustic phonons.

The upper branch in Figure 2a, which is of more interest in the present context, is called the *optic* phonon branch. Here the A and B atoms vibrate in antiphase, and because the A and B atoms have equal but opposite charges there is an electric field associated with the vibration. The optic phonon vibrations will consequently affect the propagation of electromagnetic waves through the medium – hence the name – although the vibration frequencies (around 10 THz) are in the far infrared rather than the visible part of the electromagnetic spectrum. At this frequency, the infrared wavelength λ is about 30 μm. The propagation of the infrared will be affected only by phonons whose wavevector q matches the infrared wavevector $k = 2\pi/\lambda$. Since λ is around 10^4 times larger than the typical lattice spacing a in semiconductor materials, it follows that the optical properties of the material may be largely understood merely by considering the long-wavelength phonons with wavevector $q \approx 0$. Thus, in the diatomic case, only the optic phonon of wavevector $q \approx 0$ and frequency

$$\omega_0 = \sqrt{\frac{2C(M_A + M_B)}{M_A M_B}} \qquad [6]$$

is of importance to the propagation of electromagnetic radiation.

Many semiconductor materials are of the diatomic AB type – for example group III–V materials such as GaAs, and II–VI semiconductors such as CdTe. Their phonons are described in detail by three-dimensional versions of the simple linear chain model discussed above. The most basic semiconductor materials, Si and Ge, are clearly monatomic, but their crystal structure is identical to the zincblende structure of GaAs, and they show two phonon bands as in Figure 2a. However, because there is only one type of atom, these materials differ from the diatomic materials in that the optic phonon branch has no electric dipole moment. In Si and Ge, there is no dielectric anomaly around the frequency ω_0 of the type discussed in the following section. In these materials, the only significant optic effects occur when phonons combine in pairs with equal but opposite wavevector q, so that the resultant has very small wavevector that can match the infrared wavevector $k = 2\pi/\lambda$. The significant factor here is the density of states $D(\omega)$, representing the number of phonon states per unit frequency range. In Figure 2b, we show $D(\omega)$ for the diatomic lattice. This is obtained as

$$D(\omega) = D(q)\frac{\mathrm{d}q}{\mathrm{d}\omega} \qquad [7]$$

where $D(q)$ is the density of states with respect to the wavevector, which is proportional to q^2 for a three-dimensional lattice. Note that $D(\omega)$ has peaks at frequencies corresponding to the zone boundary phonon frequencies because the dispersion curves are flat in these regions. These features are known as critical points, and they have well-defined shapes. Their spectroscopic importance is discussed later.

In bulk three-dimensional crystals, both transverse and longitudinal optic and acoustic phonons occur, each represented by different branches of the phonon dispersion curves, and the transverse branches in cubic materials are doubly degenerate. In three dimensions, more elaborate theoretical models are required, such as the rigid ion model and the shell model, and improved results can sometimes be achieved by including next-nearest-neighbor atoms in the model. As an example, the phonon dispersion curves of GaAs are shown in Figure 3.

It should be noted that the dispersion curves, and hence the associated optical properties, differ for propagation in different crystallographic directions, e.g., [100], [110], and [111].

Born–Huang Optic Phonon Model

The infrared lattice properties of materials at long wavelength are usually described by using the relative permittivity ε (often called the 'dielectric constant'), which is defined through the relation

$$D = \varepsilon\varepsilon_0 E \qquad [8]$$

between the electric field E in a medium and the displacement field D (here, ε_0 is the permittivity of free space). D is the sum of the field E and the polarization P of the medium:

$$D = P + \varepsilon_0 E \qquad [9]$$

P has contributions from lattice displacements (phonons), free electrons (plasmons), and the basic atomic polarizabilities. Since these quantities depend on frequency, ε is also a function $\varepsilon(\omega)$ of angular frequency ω. The charges of the A and B sites are taken as $+Q$ and $-Q$ respectively, and their equations of motion [1] and [2] are extended to include the electric forces $\pm EQ$. As a result of these considerations, the dielectric function can be written in the form

$$\varepsilon(\omega) = \varepsilon_\infty\left[1 + \frac{\omega_\mathrm{L}^2 - \omega_\mathrm{T}^2}{\omega_\mathrm{T}^2 - \omega^2}\right] = \varepsilon_\infty\frac{\omega_\mathrm{L}^2 - \omega^2}{\omega_\mathrm{T}^2 - \omega^2} \qquad [10]$$

Here, ε_∞ is the high-frequency dielectric constant due to the atomic polarizabilities, and ω_L and ω_T are frequencies that are close to the natural vibrational frequency ω_0 that occurs in the absence of electric field effects; the difference $(\omega_\mathrm{L}^2 - \omega_\mathrm{T}^2)$ is of order $\omega_0^2 Q^2/(Ca^3\varepsilon_0)$.

Figure 4 shows a plot of $\varepsilon(\omega)$ as a function of ω. Note that $\varepsilon(\omega)$ diverges at $\omega = \omega_\mathrm{T}$, and that $\omega = 0$ at $\omega = \omega_\mathrm{L}$ ($\omega_\mathrm{L}/\omega_\mathrm{T} = 1.25$ in Figure 4). ω_T is called the transverse optic (TO) phonon frequency: it is the resonance frequency of propagation of transverse



Figure 3 Phonon dispersion curves of GaAs determined by neutron spectrometry (points) compared with calculation (dotted and solid lines). Reproduced with permission from Waugh JLT and Dolling G (1963) Crystal dynamics of gallium arsenide. *Physical Review* 132: 2410.



Figure 4 Dielectric function $\varepsilon(\omega)$ as a function of angular frequency, ω.



Figure 5 The dispersion curves for phonon polariton modes (solid lines) for a diatomic linear chain of atoms showing the gap in bulk phonon modes between the frequencies ω_T and ω_L.

electromagnetic waves in the material. ω_L is called the longitudinal optic (LO) phonon frequency: it is the frequency of the longitudinal electrostatic wave. Physically, the dielectric constant determines the velocity v of propagation of electromagnetic waves in the material

$$v^2 = \frac{\omega^2}{q^2} = \frac{c^2}{\varepsilon(\omega)} \qquad [11]$$

where c is the velocity of light. Equation [11] has two solutions for ω as a function of wavevector: the two solutions are shown in Figure 5. Note that there is no solution with ω in the range between ω_T and ω_L. The excitations in the region where the graphs are curved are called 'polaritons' – a combination of polar phonon and photon.

The refractive index n of the material is the ratio of v, the velocity of light in the medium, to c, the velocity in free space; thus $n = \sqrt{\varepsilon}$. n is often found from a measurement of the optical reflectivity R. At normal incidence



Figure 6 Calculated reflectivity plotted versus angular frequency for a diatomic linear chain of atoms for the case of zero damping.

$$R = \left|\frac{1-n}{1+n}\right|^2 \qquad [12]$$

A graph of R is shown in Figure 6; note that the reflectivity is 100% for ω in the range $\omega_T < \omega < \omega_L$.

Impurity Phonon Modes

Impurity atoms in crystal lattices can significantly affect the infrared properties. The simplest case is when an impurity atom has the same binding but a different mass. Consider the monatomic, one-dimensional case, in which the impurity atom has a mass $M + \delta M$, where M is the normal mass. Let the impurity be at the site $n = 0$. The equations of motion are

$$-M\omega^2 u_n = C(u_{n-1} + u_{n+1} - 2u_n) \text{ for } n \neq 0$$

$$-(M + \delta M)\omega^2 u_0 = C(u_{-1} + u_1 - 2u_0) \text{ for } n = 0 \qquad [13]$$

These equations have a solution provided that ω satisfies the equation

$$N^{-1}\frac{\delta M}{M}\sum_q \frac{\omega^2}{\omega_q^2 - \omega^2} = 1 \qquad [14]$$

where N is the number of atoms in the linear chain, and ω_q the unperturbed normal mode frequencies. This equation has solutions ω that lie close to the bulk phonon frequencies ω_q. However, if $\delta M < 0$ (i.e. the impurity atom is lighter than the bulk atoms), one additional mode is possible at a frequency ω that is higher than the maximum frequency $\omega_0 = \sqrt{C/M}$ of the bulk phonons. This is the so-called impurity or localized vibrational mode (LVM – see Figure 7).



Figure 7 Representation of TO and LO phonon frequencies in a mixed crystal $A_xB_{1-x}C$ plotted versus composition x.

The impurity atom, being lighter than the material atoms, vibrates at a higher frequency than the bulk frequencies; the amplitude of the vibration is greatest at the impurity site, and decreases the further away one goes from the impurity site. If the impurity atom is heavier than the bulk atoms ($\delta M > 0$), there is no distinguishable local mode. In the case of diatomic lattices, an analogous situation pertains: if the impurity is lighter than the bulk atoms, an impurity mode is distinguishable above the top of the optic phonon band; if the impurity is heavier, there is the possibility that a distinct impurity mode may appear in the gap between the acoustic and optic phonon branches.

Mixed Crystals

Mixed compound semiconductor crystals are in widespread use because the bandgap can be adjusted by varying the composition. For example, the ternary material $A_xB_{1-x}C$ is an alloy of a fraction x of the material AC with a fraction $1-x$ of the material BC. A typical example is $Al_xGa_{1-x}As$. The infrared lattice properties of these materials are classified as 'one-mode' or 'two-mode' depending on how many distinct optic phonon frequencies are observed. The distinction can easily be understood in the context of the discussion above of impurity modes. If an A atom in the bulk material BC has a distinct local impurity optic phonon mode frequency, and similarly for a B impurity in AC, then there will usually be two distinct optic phonon modes throughout the whole composition range $0 < x < 1$: one mode is AC-like, and the other BC-like, as shown in Figure 7. On the other hand, if neither A in BC, nor B in AC, provide distinct optic phonons, there is only one distinguishable optic phonon in the alloy $A_xB_{1-x}C$.

Review of Far-Infrared Properties of Semiconductors

Group IV Semiconductors

We begin with Si and Ge, both of which crystallize in the diamond structure. As mentioned earlier, there is no first-order interaction between far infrared radiation and the TO mode. However, there are several other mechanisms that result in absorption. The dipole moment of the zone center TO phonon in an ionic solid is an example of a symmetry property that, in group theory, is described by a set of selection rules for each different crystal lattice. Other mechanisms that can lead to the creation of a dipole moment are:

Disorder

Disorder destroys the translational symmetry, and hence the selection rules. Consequently, phonon modes that, in a perfect lattice, are not infrared active will become active. The most general case occurs if the crystal becomes completely disordered, in which case all phonon modes become dipole-active and the far-infrared absorption spectrum resembles the phonon density of states. This is illustrated in Figure 8, in



Figure 8 Top: infrared absorption coefficient (solid line) and Raman spectrum (dashed line) of amorphous Si. Bottom: calculated density of states (solid line), and broadened density of states (dashed line). Reproduced with permission from Bradskyn H and Lunio (1974) Infrared vibrational spectra of amorphous Si and Ge. *Physical Review B* 9: 1646, ADS.

which measured infrared and Raman spectra of amorphous Si are compared with the calculated one-phonon density of states.

Phonon combination bands

A combination of the lattice distortions due to two phonons excited simultaneously can produce a resultant displacement of the ions in the lattice with a dipole moment. Such phonon combinations can be excited simultaneously by a far-infrared photon, and they are observed as weak bands in the infrared absorption spectrum. Apart from the dipole moment selection rule, it is also necessary for wavevector conservation to occur. Since $q \sim 0$ for the photon, the two phonons must either be at the zone center, or have equal and opposite wavevectors. An additional consideration is that, if the process is to lead to observable absorption, it should have a high probability as determined by the density of states, so observable absorption features usually arise from critical-point phonon combinations. An example of phonon combination bands in Si is shown in Figure 9. Assignment of the features in the spectrum is usually possible by inspection of the phonon dispersion curves at the zone boundaries, a procedure known as critical-point analysis. Alternatively, the two-phonon density of states can be calculated, taking into account the selection rules, and then compared with the measured spectrum. Similar considerations apply to higher-order phonon combination bands, e.g., three or four phonons, etc., but the strength of the combination bands usually decreases rapidly as the order of interaction increases.

The presence of impurities

As mentioned above, dipole-active localized vibrational modes (LVMs) can occur if the sample is doped with lighter elements as this destroys the local translational symmetry. For instance, an LVM occurs if Si is doped with B, as shown in Figure 10. The LVM frequency is proportional to the ratio $(C/M)^{1/2}$ as seen earlier where C is the force constant and M is the isotopic mass of the substituted atom. As such modes have narrow linewidths, the features in the spectrum due to different isotopes of the same element are easily distinguished, as shown in Figure 10.

Group III–V and II–VI Semiconductors: Bulk Crystals

The group III–V and group II–VI semiconductors crystallize in either the cubic (zincblende) structure, or the hexagonal (wurtzite) structure. Many mixed crystal materials, such as $Al_xGa_{1-x}As$, are grown for



Figure 9 Measured lattice combination bands in a single crystal of silicon at 290 K (top), 77 K (middle), and 20 K (bottom). (Note that 100 mm^{-1} = 1000 cm^{-1}.) Reproduced with permission from Johnson FA (1959) Lattice absorption bands in silicon. *Proceedings of the Physical Society* 73: 265.

electronic applications that require materials with bandgaps not found naturally. Furthermore, a host of low-dimensional structures, such as epilayers, multiple quantum wells (MQWs) and superlattices, are fabricated by molecular beam epitaxy (MBE) or metalorganic vapor phase epitaxy (MOVPE) to create devices that exploit the novel properties which occur when one or more of the physical dimensions are small.

Reflectivity from a bulk single crystal

In the reststrahl frequency range bulk phonon modes cannot propagate and incident radiation is perfectly reflected, i.e., $R = 1$, as shown in the calculated spectrum in Figure 6. Figures 4 and 6 represent the ideal case of a harmonic crystal, in which there is no interaction between the phonon modes, so that all modes have infinite lifetime or, equivalently, spectral features have zero linewidth, corresponding to zero damping. This is close to the behavior of a crystal at absolute zero but, in practice, the phonon modes are coupled, so each mode will decay into combinations of other phonon modes. This leads to finite phonon lifetimes and finite linewidths of all features in the measured spectra. This damping has the effect of



Figure 10 The far-infrared absorption spectrum of Si doped with B (^{10}B + ^{11}B). Reproduced with permission from Angress JF, Goodwin AR and Smith SD (1965) A study of the vibrations of boron and phosphorus in silicon by infrared-red absorption. *Proceedings of the Royal Society A* 287: 64.



Figure 11 The reststrahlen band reflectivity of GaP, measured (points) and calculated from a damped simple harmonic oscillator (line). Reproduced with permission from Kleinman DA and Spitzer WG (1960) Infrared lattice absorption of GaP. *Physical Review* 118: 110.



Figure 12 (a) Reflection spectra for GaAs, AlAs, and five Ga$_{1-x}$Al$_x$As mixed crystals. The curves have been displaced for clarity. (b) TO and LO mode frequencies obtained analytically from the spectra, plotted versus alloy composition. Reproduced with permission from Ilegens M and Pearson GL (1970) Infrared reflection spectra of Ga$_{1-x}$AL$_x$As mixed crystals. *Physical Review B* 1: 1576.

rounding off features in the reflectivity compared with Figure 6, and it can be represented analytically by the equation:

$$\varepsilon(\omega) = \varepsilon_\infty + \frac{(\varepsilon(0) - \varepsilon_\infty)\omega_T^2}{\omega_T^2 - \omega^2 - i\gamma\omega} \qquad [15]$$

This differs from eqn [10] only by the addition of the damping coefficient, γ, which takes account in a phenomenological way of the interactions between the phonon modes. Here $\varepsilon(0)$ is the dielectric function at zero frequency, and $\varepsilon(0) - \varepsilon_\infty$ is the oscillator strength (i.e., the dipole strength) of the mode. We shall consider γ again later.

The reflectivity of GaP is shown in Figure 11, and this should be compared with Figure 6. In pure diatomic crystals like the simple ionic solids, e.g., NaCl and KCl, or the binary semiconductors, e.g., GaAs and CdTe, this is the only region of high reflectivity at frequencies below the visible or ultraviolet, and it is often described as the reststrahlen band, from the German term for residual ray.

Reflectivity from mixed crystals of binary semiconductors

The spectra of mixed crystals were discussed above and an example is shown in Figure 12a, which shows the reflection spectra of GaAs, AlAs and five $Ga_{1-x}Al_xAs$ mixed crystals. The TO and LO phonon frequencies were obtained from the spectra using a Kramers–Kronig analysis and classical dispersion theory. Changes in the mode frequencies with composition are interpreted using the so-called random element isodisplacement (REI) model. In Figure 12b, the TO and LO frequencies are plotted versus composition, x, and it can be seen that this system displays typical two-mode behavior, following closely the behavior shown in Figure 7.

Localized vibrational modes due to impurities

LVMs have been widely investigated in binary semiconductors because they offer a useful diagnostic tool for the investigation of impurities. In addition to the identification of isotopic species, high-resolution transmission spectroscopy can be used to determine the sites of the impurity atoms in the lattice. In Figure 13 the LVM absorption band for ^{12}C in GaAs is shown at different resolutions. The ^{12}C atoms are substitutional impurities on the As sites and the different components of the band arise from the different nearest-neighbor isotopic arrangements



Figure 13 Localized vibrational mode (LVM) absorption band for ^{12}C in GaAs measured at 80 K. The numbers in brackets are estimated band strengths. Reproduced with permission from Theis WM, Bajaj KK, Litton CW and Spitzer WG (1982) Direct evidence for the site of substitutional carbon impurity in GaAs. *Applied Physics Letters* 41: 70.



Figure 14 High-resolution far-infrared absorption spectra of GaP and InP with the frequency scale normalized in each case to the reststrahl frequency ($\nu/\nu_R = 1$ corresponds to $\omega = \omega_T$). Reproduced with permission from Koteles ES and Datars WR (1976) Two-phonon absorption in InP and GaP. *Solid State Communications* 19: 221.

surrounding the different ^{12}C atoms in the lattice. Note that ^{12}C is much lighter than either of the host lattice atoms, Ga or As, as required theoretically.

Phonon combination bands

Weak features due to the simultaneous excitation of two or more phonons are observed in the spectra of all semiconductors, and there are two excitation mechanisms. The first is direct excitation of two or more phonons by an incident photon via nonlinear terms in the dipole moment. The second process is indirect: the incident photon first excites a zone center TO phonon and the TO phonon then decays into a combination of phonons elsewhere in the Brillouin zone, a process described as anharmonic decay of the TO phonon. Mathematically, it is described by a complex frequency-dependent damping coefficient, $\gamma(\omega)$, in the oscillator equation [15]. Clearly, the latter mechanism is not available in Si and Ge as the TO phonons are not dipole-active. Anharmonicity is very important in strongly ionic crystals like the alkali halides (i.e., group I–VII compounds like NaCl), leading to prominent phonon combination bands, but it becomes progressively less important in semiconductors as the interatomic bonding becomes less ionic and more covalent, which is the case in the sequence through group II–VI (e.g., semiconductors like CdTe or ZnSe), group III–V (e.g., GaAs or InP), and group IV (Ge and Si), which are entirely covalent. Nearly all two-phonon combinations are dipole-active in zinc-blende structure crystals with the result that the transmission spectrum either side of the reststrahlen band is very rich in weak phonon combination bands, as shown in Figure 14 for GaP and InP.

Layered Semiconductor Structures

Confined optical phonons

Semiconductor superlattices are fabricated for a variety of electronic and optical applications, and the



Figure 15 Measured (solid lines) and calculated (dashed lines) oblique incidence (45°) reflectivity spectra at 77 K of three short-period (GaAs)$_n$/(AlAs)$_n$ superlattices on GaAs substrates: n denotes the number of monolayers. Left curves: s-polarization, right curves: p-polarization. Note that the strong reststrahl reflectivity is from the GaAs substrates and the fine structure is due to confined modes. The subscripts 1, 2, and 3 denote the orders of the confined modes. Reproduced with permission from Dumelow T, Hamilton AA, Parker TJ, Tilley DR, Foxon CT, Hilton D and Moore KJ (1990) Far infrared measurements of bulk and surface phonons in GaAs/AlAs superlattices. *International Journal of Infrared and Millimeter Waves* 11: 901.

quality of the interfaces in such structures is important as it determines the amount of electronic scattering at the interfaces. Some structures are fabricated from alternate layers of materials such as GaAs and AlAs, in which there is no overlap between the frequencies of the optical branches of the phonon dispersion curves. This has the effect that optical phonons excited in one type of layer, e.g., in GaAs, cannot propagate into the other type of layer, i.e., AlAs, and vice versa, so that the optical phonon modes are confined in their respective layers. The confined modes behave like standing waves, with frequencies determined by the thicknesses of the layers and the bulk optical phonon dispersion curves. Thus, if the superlattice structure is of poor quality, and the interfaces are broad due to alloying, rather than abrupt, there will be a change in the effective widths of the layers. This leads to small shifts in the frequencies of the confined phonons which can be measured and used to obtain a quantitative estimate of the amount of interface broadening. An example is shown in Figure 15. The degree of interface broadening determined from these spectra was 1.4 atomic spacings, in agreement with estimates using other techniques.

Surface phonon polaritons and guided waves

The reststrahl reflection band (Figure 6) occurs because there is a gap between ω_T and ω_L in the polariton dispersion curves (Figures 4 and 5), with no solutions for bulk phonon modes. Surface phonon polaritons can, however, propagate in this frequency band, but they have wavevectors that are larger than those, ω/c, of far-infrared radiation, so special techniques are required to observe them. The necessary wavevector enhancement can be obtained in two ways. Prism coupling can be used, as shown in Figure 16. When the angle of incidence of the incident beam at the base of the prism exceeds the critical angle for total internal reflection an evanescent wave with advanced wave vector, $q > \omega/c$, is set up at the base of the prism. This wave can couple to a surface polariton, and the energy used to excite the polariton results in a dip in the reflectivity at the frequency of the surface polariton, hence the name of the technique: attenuated total reflection (ATR). An example is shown in Figure 16. Alternatively, wavevector enhancement can be achieved by placing a grating on the surface of the sample. The incident photon wavevector is then enhanced by $+2m\pi/d$, where d is the grating period and m is an integer.

Interface phonons

Under certain conditions phonons can propagate along the interface between two different media that are in intimate contact, as for instance, in the case of thin epilayers on substrates, or in multilayered



Figure 16 ATR reflection spectrum with dips due to surface phonon polaritons (S) and guided waves (G) in a GaAs/$Al_{0.38}Ga_{0.65}As$ MQW. Inset: schematic diagram of the ATR stage. Reproduced with permission from Dumelow T, Hamilton AA, Parker TJ, Tilley DR, Foxon CT, Hilton D and Moore KJ (1990) Far infrared measurements of bulk and surface phonons in GaAs/AlAs superlattices. *International Journal of Infrared and Millimeter Waves* 11: 901.



Figure 17 Far-infrared reflectivity of a GaN epilayer on a GaAs substrate at 290 K with dips due to a Brewster mode at C and a Berreman mode at D. Reproduced with permission from Mirjalili G, Parker TJ, Farjami Shayesteh S, Bulbul MM, Smith SRP, Cheng TS and Foxon CT (1998) Far infrared and Raman analysis of phonons and phonon interface modes in GaN epilayers on GaAs and GaP substrates. *Physical Review B* 57: 4656.

structures. There are two common sets of criteria for the existence of such interface modes. The first, leading to so-called Brewster modes, is when the numerator of the Fresnel reflection coefficient passes through zero due to impedance matching in the two media. The second, leading to a Berreman mode, is when the real part of the dielectric constant has a zero crossing in one of the media at a frequency where it is negative in the other medium. Both modes are observed as dips in the reflectivity. A reflection spectrum for a GaN epilayer on a GaAs substrate is shown in Figure 17. The two interface modes occur at frequencies close to the frequencies of GaN LO phonons; the Berreman mode is close to the GaN LO phonon frequency at the base of the GaN epilayer, which is shifted down by about 50 cm^{-1} from the bulk GaN value (735 cm^{-1}) due to disorder arising from the large lattice mismatch between the epilayer and the substrate. Both interface modes couple strongly to free carriers (i.e., plasmons) propagating normal to the interface, and thus act as useful probes of the structural and electronic properties of the epilayer. No other technique is available for probing the electronic properties of the epilayer for propagation normal to the layer.

See also

Semiconductor Materials: GaAs Based Compounds. **Semiconductor Physics:** Band Structure and Optical Properties; Light Scattering; Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures.

Further Reading

Angress JF, Goodwin AR and Smith SD (1965) A study of the vibrations of boron and phosphorus in silicon by infrared-red absorption. *Proceedings of the Royal Society A* 287: 64.

Barker AS Jr and Sievers AJ (1975) Optical studies of the vibrational properties of disordered solids. *Reviews of Modern Physics* 47 (Suppl. 2): S1.

Berreman DW (1963) Infrared absorption at longitudinal optic frequency in cubic crystal films. *Physical Review* 130: 2193.

Born M and Huang K (1954) *Dynamical Theory of Crystal Lattices*. Oxford: Clarendon Press.

Dumelow T and Tilley DR (1993) Optical properties of semiconductor superlattices in the far infrared. *Journal of the Optical Society of America* 10: 633.

Dumelow T, Hamilton AA, Parker TJ, Tilley DR, Foxon CT, Hilton D and Moore KJ (1990) Far infrared measurements of bulk and surface phonons in GaAs/AlAs superlattices. *International Journal of Infrared and Millimeter Waves* 11: 901.

Johnson FA (1959) Lattice absorption bands in silicon. *Proceedings of the Physical Society* 73: 265.

Kittel C (1996) *Introduction to Solid State Physics*, 7th edn. New York: John Wiley.

Kleinman DA and Spitzer WG (1960) Infrared lattice absorption of GaP. *Physical Review* 118: 110.

Koteles ES and Datars WR (1976) Two-phonon absorption in InP and GaP. *Solid State Communications* 19: 221.

Mirjalili G, Parker TJ, Farjami Shayesteh S, Bulbul MM, Smith SRP, Cheng TS and Foxon CT (1998) Far infrared and Raman analysis of phonons and phonon interface modes in GaN epilayers on GaAs and GaP substrates. *Physical Review B* 57: 4656.

Newman RC (1974) *Studies of Crystal Defects*. London: Taylor and Francis.

Theis WM, Bajaj KK, Litton CW and Spitzer WG (1982) Direct evidence for the site of substitutional carbon impurity in GaAs. *Applied Physics Letters* 41: 70.

Waugh JLT and Dolling G (1963) Crystal dynamics of gallium arsenide. *Physical Review* 132: 2410.

Light Scattering

M Balkanski, Université Pierre et Marie Curie, Paris, France

© 2005, Elsevier Ltd. All Rights Reserved.

When a monochromatic light beam passes through a transparent medium, a small part of the light is scattered out of the incident direction with a change in frequency. The scattering processes are usually classified into three groups. The light scattering is named:

Brillouin scattering when the light is scattered with a small frequency shift that varies continuously with scattering angle.

Raman scattering when the light is scattered with a relatively large frequency shift that is independent of scattering angle. The possibility of observing a given transition, however, depends on the orientation of the crystal relative to the polarization of the incident light.

Rayleigh scattering when the light is scattered without frequency shift. In this case the scattering is elastic with the incident and scattered frequencies equal: $\omega_\mathrm{i} = \omega_\mathrm{s}$. Rayleigh scattering is particularly useful in the study of critical phenomena or aspects related to the size and polarizability of particles.

Brillouin Scattering

Brillouin scattering is caused by the interaction of light with the acoustic modes of vibration of the crystal. Consider an acoustic wave of frequency ω_a propagating with velocity $\pm v$ as shown in Figure 1. Light with incident frequency ω_i interacts strongly with acoustic waves satisfying the Bragg condition $\omega_a = 2\omega_i(v/c)n\sin(\theta/2)$, where n is the refractive index of the material and θ is the angle of deviation of the scattered beam. Since the acoustic waves are moving with velocity $\pm v$ the scattered light suffers a Doppler shift in frequency and exhibits a frequency doublet at the angle θ given by the Brillouin equation

$$\omega_i \pm \omega_a = \omega_i \pm 2\omega_i(v/c)n\sin(\theta/2)$$

In terms of the quantum picture, Brillouin scattering corresponds to scattering of incident photons of frequency ω_i and wavevector $\mathbf{k}_i$ into scattered photons of frequency ω_s and wavevector $\mathbf{k}_s$ with the emission or absorption of an acoustic phonon of frequency ω_a and wavevector $\mathbf{q}$. The predicted Brillouin spectrum is shown in Figure 2. It consists of Stokes $(\omega_s = \omega_i - \omega_a)$ and anti-Stokes $(\omega_s = \omega_i + \omega_a)$ components corresponding to phonon emission and absorption, respectively.

The frequency shift $|\omega_i - \omega_s|$ for a well-defined scattering angle θ directly gives the acoustic phonon frequency and velocity. The width Γ of the Brillouin component of the spectrum is a measure of the damping or attenuation of the wave.



Figure 1 Light scattering at angle ϕ and Bragg reflection at angle θ by moving thermal waves.



Figure 2 Schematic diagram of a Brillouin spectrum.

Raman Scattering

The essential difference between Brillouin and Raman scattering is that in Raman scattering the incident light beam is scattered with relatively large frequency shift independent of the scattering angle. The same basic considerations apply to Raman scattering that apply to Brillouin scattering. The Raman spectrum has Stokes and anti-Stokes branches corresponding to the emission and absorption, respectively, of an elementary excitation. A variety of elementary excitations are important. They include optical phonons and, in the case of magnetic materials, magnons. Also of interest are electronic excitations such as intraband single-particle excitations, interband excitations, and collective excitations (plasmons).

Raman Scattering by Phonons

An inelastic light scattering event involves the destruction of a photon of frequency ω_i incident from a light source, the creation of a scattered photon of frequency ω_s and the creation or destruction of an optical phonon of frequency ω_o.

Destruction of a photon involves interaction of the radiation field with matter by which a pair of free carriers is created in the semiconductor corresponding to a virtual transition between the valence and conduction bands. The excited state, free electron in the conduction band, interacts with the lattice via the optical deformation potential. This interaction results in the creation or annihilation of an optical phonon of frequency ω_s. When the resulting process corresponds to the creation emission of a phonon, the frequency of the scattered photon is $\omega_s = \omega_i - \omega_a$ and is referred to as the Stokes component of the spectrum. When the process is the annihilation or absorption of a phonon the scattered frequency is $\omega_s = \omega_i + \omega_a$, referred to as the anti-Stokes component.

These two first-order scattering events can be described in terms of Feynman diagrams as shown in Figure 3.

Considering these elementary processes one can calculate, using time-dependent perturbation theory, the Raman amplitude and hence the differential scattering cross-section. The remarkable feature here is that for incident frequencies approaching the frequencies of an electronic excited state of the material the Raman amplitude diverges. This leads to the phenomenon of resonant Raman scattering.



Figure 3 Feynman diagrams for two first-order scattering events.

The Raman scattering efficiency, which is the scattering cross-section per illuminated area can be calculated numerically. Numerical estimates give efficiencies typically of order 10^{-6} or 10^{-7}.

In polar semiconductors the macroscopic electric field leads to an additional contribution to the scattering cross-section for the longitudinal optical (LO) phonon modes. The macroscopic field is a consequence of the Coulomb field of the ionic charges and gives rise to an electron–phonon interaction.

There is no simple relationship between the scattering intensities for transverse optical (TO) and LO phonons in polar semiconductors.

When the probing frequency coincides with the transverse optical mode frequency, i.e., for the regime $cq \cong \omega_{\mathrm{TO}}$ (where c is the light velocity, q the photon wavevector and ω_{TO} the transverse optical phonon frequency) in polar semiconductors it is necessary to take into account the polariton nature of the coupled photon–TO-phonon modes and their associated macroscopic electrical field. The dispersion relation of the coupled photon–TO mode, called a polariton, consists of two branches: an upper branch ω_+, in which the electro-optical contribution dominates, and the lower branch ω_-, which contains essentially the mechanical contribution. This leads to a contribution to the Raman amplitude from both mechanical and electro-optical origins. An exception occurs for the lower polariton branch with $\omega = \omega_{\mathrm{TO}}$; then the electro-optic contribution is very small compared to the mechanical contribution. If $cq \gg \omega_{\mathrm{TO}}$ as in the upper polariton branch, destructive interference between the mechanical and electro-optic contributions can occur.

Selection Rules in Raman Scattering

Not all elementary excitations in semiconductors scatter light. The Raman active modes are determined by selection rules established using group-theoretical methods. The various normal modes in a given crystal correspond to various symmetries of the vibrations of the atoms in the crystal and are characterized by the irreducible representations of the space group of the crystal lattice. One can show that a normal mode can participate in a first-order Raman transition if and only if its irreducible representation is the same as one of the irreducible representations that occur in the reduction of the representation of the Raman tensor.

An important result of group theory is the rule of mutual exclusion which states that, in crystals with a center of inversion, excitations that are active in the first-order infrared spectrum are inactive in the first-order Raman spectrum, and conversely, excitations that are active in the first-order Raman spectrum are inactive in the first-order infrared spectrum. In particular, the first-order spectra due to optical phonons in NaCI are infrared active, but Raman inactive, whereas in Si they are infrared inactive, but Raman active. This difference is related to the fact that each atomic site in NaCI is a center of inversion and the active optical phonons have odd parity whereas each midpoint between two nearest-neighbor atomic sites in Si is a center of inversion and the active optical phonons have even parity.

In a crystal with the zinc blend structure, there is no center of inversion, and the crystal is both infrared and Raman active. The only non-vanishing elements of the Raman tensor $R(\hat{e})$ with $\hat{e} \| z$ are the xy and yx elements. To observe the Raman effect of an LO phonon propagating in the z-direction, one can arrange the polarization of the incident light parallel to the x-axis and observe the scattered light with its polarization parallel to the y-axis or vice versa. An analogous set of constraints applies to TO phonons. A typical spectrum is illustrated in Figure 4.

For higher-order Raman processes in which several phonons participate, it is the product of the irreducible representations of the phonons involved that must be the same as the irreducible representation of the Raman tensor.



Figure 4 Raman spectrum for optical phonons.

Geometrical Aspects of First-Order Raman Scattering

The observation of light scattering by optical phonons in transparent crystals is usually done in a geometry in which the linearly polarized incident light beam is directed along, say, the x-axis and the scattered beam is observed along the y-axis (see Figure 5). When the crystal is not transparent, as is often the case in semiconductors, the observation is made in the backscattering geometry in which the scattered beam is observed in the opposite direction to the incident beam.

The scattering geometry affects the range of phonon wavevectors that is accessible in first-order Raman scattering. The condition of wavevector conservation is

$$\mathbf{K}_{\mathrm{i}} - \mathbf{K}_{\mathrm{s}} = \pm\mathbf{q}$$

where $\mathbf{q}$ is the phonon wavevector and the plus (minus) sign refers to the Stokes (anti-Stokes) process. The Stokes geometry is shown in Figure 6 and satisfies the following relation:

$$q^2 = k_{\mathrm{i}}^2 + k_{\mathrm{s}}^2 - 2k_{\mathrm{i}}\, k_{\mathrm{s}} \cos\theta$$

Forward scattering is characterized by $\theta = 0$ and a minimum value of q given, for isotropic media, by

$$q_{\min} = \frac{n(\omega_{\mathrm{i}})\ \omega_{\mathrm{i}} - n(\omega_{\mathrm{s}})\omega_{\mathrm{s}}}{c}$$

where $n(\omega_{\mathrm{i}})$ and $n(\omega_{\mathrm{s}})$ are the refractive indices of the crystal for the incident and scattered light, respectively, and $k_{\mathrm{i(s)}} = n(\omega_{\mathrm{i(s)}})\omega_{\mathrm{i(s)}}/c$.

Back scattering is characterized by the maximum value of q when $\theta = 180°$ and is given by

$$q_{\max} = \frac{n(\omega_{\mathrm{i}})\omega_{\mathrm{i}} - n(\omega_{\mathrm{s}})\omega_{\mathrm{s}}}{c}$$



Figure 5 Geometry for light-scattering experiments in transparent crystals.



Figure 6 Diagram for Stokes processes.

For typical light-scattering experiments in the visible region the range of the incident wavevector is $0 < k_{\mathrm{i}} < 10^6\ \mathrm{cm}^{-1}$. This implies that for first-order scattering processes the accessible range of $\mathbf{q}$ under conditions of wavevector conservation is small compared to a nonzero reciprocal lattice wavevector. Light-scattering experiments yield the frequencies of optical modes at essentially the center of the Brillouin zone.

The energy and momentum conservation rules have to be modified when the lifetime of the crystal excitations are strongly limited by their decay into other crystal excitations. Momentum conservation breaks down in imperfect crystals, in solids lacking translational symmetry like amorphous materials, and in crystals which are opaque to incident and scattered light.

In those cases where the incident and scattered waves are damped inside the scattering volume, such as occur in small-gap semiconductors that are opaque at the light frequencies involved, $\mathbf{k}_{\mathrm{i}}$ and $\mathbf{k}_{\mathrm{s}}$ are complex. The inelastic scattering is due to excitations having a range of wavevector

$$\Delta q = |\mathrm{Im}\ \mathbf{k}_{\mathrm{i}}| + |\mathrm{Im}\ \mathbf{k}_{\mathrm{s}}|$$

about $\mathbf{q} = \mathrm{Re}(\mathbf{k}_{\mathrm{i}} - \mathbf{k}_{\mathrm{s}})$. Effects associated with such a wavevector uncertainty have been reported in

Raman scattering spectra of III–V semiconductor compounds.

Second-Order Raman Scattering

Second-order Raman scattering involves two phonons rather than a single phonon as in first-order scattering. The possible second-order processes are the following: two phonons may be created, giving a Stokes component in the scattered light, or one is created and the other destroyed, giving a Stokes or anti-Stokes component, or both may be destroyed giving an anti-Stokes component. For each of these cases there are the possibilities of a pair of first-order electron–phonon interactions or a single second-order electron–phonon interaction.

In the case of second-order Raman scattering the wavevector conservation condition is $\mathbf{q}_1 \pm \mathbf{q}_2 \cong 0$, where $\mathbf{q}_1$ and $\mathbf{q}_2$ are the wavevectors of the phonons involved. This condition places no restriction on the magnitudes of the individual wavevectors, other than $|q_1| \cong |q_2|$, which is in contrast to first-order scattering where $q \cong 0$.

The possible phonon frequency pairings associated with second-order processes are $\omega_1 + \omega_2$ (combination band), $\omega_1 - \omega_2$ (difference band), and $2\omega_1$, (overtone band). The second-order scattering spectrum covers a broad range of frequencies. The overtone spectrum provides a measure of the phonon density of states.

Resonant Light Scattering

General Formulation

Resonant Raman scattering occurs when the incident or scattered photon energy is close to the energy of an intermediate electronic state relative to the ground electronic state. Certain terms in the Raman amplitude then diverge leading to a very large scattering cross-section. Divergences occur in the Stokes spectrum when $\hbar\omega_\mathrm{i} = \hbar\omega_\mathrm{a}$, and $\hbar\omega_\mathrm{s} = \hbar\omega_\mathrm{b}$: the photon energies *resonate* with the excitation energies of the intermediate states *a* or *b*. If *a* and *b* are the same state, resonance occurs nearly simultaneously for both ω_i and ω_s, and gives rise to a particularly strong enhancement of the scattering efficiency. It is thus clear that the resonance phenomenon is specific to the nature of the intermediate state, and its investigation leads to basic information concerning the electronic states of the system. We shall now examine the resonance behavior in several cases where the intermediate states are carrier Bloch states, free excitons, or bound excitons.

Resonance at the Fundamental Bandgap

The divergent behavior of the Raman amplitude is associated with the factor $(\hbar\omega_\mathrm{i} - E_\mathrm{g})^{-1}$ where E_g is the lowest direct bandgap of the material.

Resonance at Free Exciton States

The Raman intensity as a function of the incident photon energy has a Lorentzian line shape in the range of a single intermediate state. It is centered at the resonance frequency and has a width determined by the lifetime of the intermediate state. The distinction between scattering at resonance and scattering off resonance in the wings of the Lorentzian is that at resonance the intensity is determined by the exciton lifetime, whereas off resonance it is determined by the frequency separation from resonance. Since in many instances excitons have very long lifetimes, they can lead to a very large Raman cross-section at resonance.

Resonance at Bound Exciton States

Scattering induced by the presence of impurities involving bound exciton states has the following essential features: (a) observation of sharp resonance at the energies of the bound exciton which form discrete levels below the free exciton resonance; (b) dependence upon impurity concentration; (c) involvement of LO phonons of wavevector of the order of the inverse of the impurity state radius. Resonance at bound exciton energies has been observed in impurity-induced resonant Raman scattering by LO phonons in CdS. The resonance is centered at the absorption peak for the impurity state and has approximately Lorentzian shape. If the impurity gives rise to a localized vibrational mode, bound exciton resonance in Raman scattering due to the local mode can occur.

Anharmonic Effects on Raman Spectra

In a perfect crystal whose vibrations are harmonic and which is transparent to the incident and scattered light, the Raman lineshape is a delta function centered on the optical phonon frequency. Experimentally one finds that even in crystals of very high quality, the Raman line is broadened into a roughly Lorentzian shape with a width that increases with increasing temperature. This width can be attributed to anharmonic terms in the vibrational Hamiltonian.

The temperature dependence of the line width is determined by the phonon occupation factors. As the temperature approaches zero, the phonon occupation factor approaches zero also, and the width approaches the value due to the zero-point motion of the nuclei. At temperatures above the Debye temperature, the width due to cubic anharmonicity becomes proportional to T. Quartic anharmonicity imparts a T^2 dependence to the width which becomes significant at very high temperatures.

In addition to line broadening, anharmonicity causes a shift of the frequency of peak intensity to lower values as the temperature increases. Contributions to the shift proportional to T and T^2 arise in the high-temperature regime from cubic and quartic anharmonicity, respectively.

Light Scattering due to Electronic Excitations

Light Scattering by Plasmons

Plasmons are similar to LO phonons in that they have a macroscopic electric field associated with them. The field modulates the electric susceptibility and gives rise to Raman scattering. The difference in frequency of the incident and scattered light is equal to the plasma frequency ω_p specified by $\omega_p = e^2 n/\varepsilon_0 \varepsilon_\infty m^*$, where n is the electron concentration, m^* is their effective mass, and ε^∞ is the high-frequency dielectric constant.

When the plasma frequency is close to the LO phonon frequency, there is a plasmon–phonon interaction via the macroscopic electric fields that leads to coupled modes and forces the frequencies apart.

Light Scattering Associated with Interband Transitions

The plasmons dealt with in the preceding section are an intraband type of excitation. Also of interest are interband transitions in which a carrier undergoes a transition from one band to a different band during the scattering process. An example is provided by p-type silicon in which an electron makes a transition from an occupied state in the light-hole band to an unoccupied state in the heavy-hole band via the conduction band as shown in Figure 7.

For the case of isotropic bands the scattering efficiency spectrum at 0 K has sharp edges. If the anisotropy of the valence bands is taken into account, the sharp edges of the spectrum are smoothed out.

The experimental Raman spectrum for p-type Si exhibits a broad continuum due to the electronic transitions but in the same spectral range there are also Raman active optical phonons which superpose on the electronic continuum and distort it. The resulting distortion of the spectrum is associated with resonant interference that occurs between the discrete phonon line and the electronic continuum.



Figure 7 Electronic transitions occurring in intervalence band scattering.

See also

Scattering: Raman Scattering. **Semiconductor Physics:** Outline of Basic Electronic Properties.

Further Reading

Balkanski M (1972) In: Abeles F (ed.) *Optical Properties of Solids*. Amsterdam: North-Holland.

Balkanski M, Jain KP, Beserman R and Jouanne M (1975) *Phys. Rev.* B12: 4328.

Birman JL (1974) *Encyclopedia of Physics*, vol XXV 12b. Berlin: Springer-Verlag.

Born M and Huang K (1954) *Dynamical Theory of Crystal Lattice*. Oxford, UK: Oxford University Press.

Brillouin L (1922) *Ann. Physique* 17: 88.

Buchler S and Burstein E (1974) *Phys. Rev. Letter* 33: 908.

Daman TC and Shah J (1971) *Phys. Rev. Letter* 27: 1506.

Hayes W and Loudon R (1978) Scattering of Light by Crystals. New York: John Wiley.

Haro E, Balkanski M, Wallis RF and Wanser KH (1986) *Phys. Rev.* B34: 5358.

Kanehisa MA, Wallis RF and Balkanski M (1982) *Phys. Rev.* B25: 7619.

Wallis RF and Balkanski M (1986) Many-Body Aspects of Solid Spectroscopy. Amsterdam: North-Holland.

Yu PY, Pilkhun MH and Evangelisti F (1978) *Solid State Communications*, vol. 25, p. 371.

SEMICONDUCTOR PHYSICS

Polarons

J T Devreese, Universiteit Antwerpen, Antwerp, Belgium

© 2005, Elsevier Ltd. All Rights Reserved.

The Polaron Concept

If an electron (or hole) is placed in a polarizable medium (like an ionic crystal or a polar semiconductor), it induces a deformation of polarization field around itself. On the other hand, the electron is attracted to the potential well of this disturbed polarization field. Thus, a feedback loop between the electron and the polarization field arises, which leads to a highly correlated state of the charge carrier and the polarization field. A conduction electron (or hole) together with its self-induced polarization in an ionic crystal or in a polar semiconductor forms a quasiparticle, which is called a polaron. The polaron concept was introduced by Landau in 1933.

The physical properties of the polaron differ from those of the band carrier. In particular, the polaron is characterized by its binding (or self-) energy E_0, effective mass m^* and by its response to external electric and magnetic fields (e.g., dc mobility and optical absorption coefficient).

If the spatial extension of the polaron is large compared to the lattice parameters of the solid, the latter can be treated as a polarizable continuum. This is the case of a 'large polaron', to which most of this article is confined.

The polaron characteristics are determined by the coupling between an electron and the long-wavelength longitudinal optical (LO) phonons. The strength of this coupling is expressed in terms of the constant introduced by Fröhlich:

$$\alpha = \frac{e^2}{\hbar c}\sqrt{\frac{m_b c^2}{2\hbar\omega_{LO}}}\left(\frac{1}{\varepsilon_\infty} - \frac{1}{\varepsilon_0}\right) \qquad [1]$$

In this definition, ω_{LO} is the frequency of LO phonons, c is the velocity of light, and ε_∞ and ε_0 are, respectively, the electronic and the static dielectric constant of the polar crystal.

In order to find the coupling constant according to eqn [1], it is crucial to know the electron (hole) band mass m_b. This unknown parameter can, in principle, be determined from experiment. However, in ionic crystals and polar semiconductors, experiment measures the polaron effective mass m^* rather than the band mass, because of the polaron effect. The problem of determining the band mass is therefore far from trivial and should be tackled on the basis of the results of polaron theory. In Table 1 the coupling constants are indicated for a number of crystals.

Landau and Pekar were the first to investigate the self-energy and the effective mass of the strong-coupling polaron, when $\alpha \gg 1$. As seen from Table 1, in substances with large values of the electron–phonon coupling constant (like alkali halides, TlBr, CdF_2, $SrTiO_3$) α ranges between 2.5 and 4.5. Though, strictly speaking, polarons in such materials are of intermediate coupling, their properties can be approached within the strong-coupling approximation.

The cases when $\alpha \ll 1$ (like InSb, InAs, GaAs) are referred to as the weak-coupling regime. Polarons in many other substances with $\alpha < 1$ (e.g., GaP, CdTe, ZnSe, CdSe, CdS, CdO) are well described in the weak-coupling approximation.

In the weak-coupling regime, the states of the polaron can be imagined as those of a band carrier perturbed by the electron–phonon interaction. Fröhlich provided in 1954 the first weak-coupling perturbation theory results for the polaron characteristics:

$$E_0 = -\alpha\hbar\omega_{LO} \qquad [2]$$

$$m^* = \frac{m_b}{1 - \alpha/6} \qquad [3]$$

Feynman formulated the polaron problem in the Lagrangian (path integral) form of quantum mechanics and obtained an upper bound for the polaron self-energy at all values of the α, which at weak and strong coupling gave accurate limits. Over the years the Feynman all-coupling model

Table 1 Electron–phonon coupling constants

Material	α	*Material*	α
InSb	0.02	AgCl	1.8
InAs	0.052	KI	2.5
GaAs	0.068	TlBr	2.55
GaP	0.201	KBr	3.05
CdTe	0.286	RbI	3.16
ZnSe	0.43	CdF_2	3.2
CdSe	0.49	KCl	3.5
CdS	0.52	CsI	3.67
CdO	0.74	RbCl	3.81
AgBr	1.6	$SrTiO_3$	4.5

for the polaron has been proven to be in many respects the most successful approach to the polaron problem.

Optical Properties and Internal Structure of Polarons

Optical Absorption of Polarons at Weak Coupling

At zero temperature and in the weak-coupling limit, the optical absorption is due to the following elementary polaron scattering process, schematically shown in Figure 1. An incoming photon is absorbed by a polaron. The polaron emits a phonon during the absorption process and takes recoil energy from the incident light. At zero temperature, the absorption coefficient for absorption of light with frequency Ω can be expressed in terms of elementary functions in two limiting cases: in the region of comparatively low frequencies $(\hbar(\Omega-\omega_{\mathrm{LO}})/\zeta \leqslant 1)$

$$\Gamma(\omega)=\frac{1}{\varepsilon_0 nc}\frac{2^{1/2}N^{2/3}\alpha}{(3\pi^2)^{1/3}}\frac{e^2}{(\hbar m_{\mathrm{b}}\omega_{\mathrm{LO}})^{1/2}}\frac{\omega-1}{\omega^3}\Theta(\omega-1) \qquad [4]$$

and in the high-frequency region $(\hbar(\Omega-\omega_{\mathrm{LO}})/\zeta \geqslant 1)$

$$\Gamma(\omega)=\frac{1}{\varepsilon_0 nc}\frac{2Ne^2\alpha}{3m_{\mathrm{b}}\omega_{\mathrm{LO}}}\frac{(\omega-1)^{1/2}}{\omega^3}\Theta(\omega-1) \qquad [5]$$

Here $\omega=\Omega/\omega_{\mathrm{LO}}$, ε_0 is the dielectric permittivity of the vacuum, n is the refractive index of the medium, N is the concentration of polarons, and ζ is the Fermi level for electrons. The step function

$$\Theta(\omega-1)=\begin{cases}1 & \text{if } \omega>1\\ 0 & \text{if } \omega<1\end{cases} \qquad [6]$$

reflects the fact that at zero temperature absorption of light accompanied by emission of a phonon can occur only if the energy of a photon is larger than that of a phonon ($\omega>1$). In the weak-coupling limit, according to eqn [4], the absorption spectrum consists of a one-phonon line.

Experimentally, the one-phonon line has been clearly seen for free polarons in the infrared absorption spectra of CdO-films (see Figure 2). In CdO, which is a weakly polar material with $\alpha \approx 0.74$, the optical absorption band is observed in the spectral region between 6 and 20 μm (above the LO phonon frequency). As seen from Figure 2, this optical absorption band can be attributed to the weak-coupling polaron absorption as described by eqn [4].



Figure 1 The elementary polaron scattering process leading to absorption of an incoming photon and to generation of an outgoing phonon.



Figure 2 Optical absorption spectrum of a CdO film with the carrier concentration $N=5.9\times10^{19}$ cm^{-3} at $T=300$ K. The theoretical results are shown with (solid curves) and without (dashed curves) the polaron contribution of eqn [4], and compared to the experimental data (solid dots). (Reproduced with permission from Finkenrath H, Uhle N and Waidelich W (1969) The influence of phonons and polarons on the infrared absorption of cadmium oxide*1. *Solid State Communications* 7: 11–14.)

With strengthening coupling, it becomes possible that absorption of a photon is accompanied by emission of two, three, ..., K phonons, thus giving rise to two-, three-, ..., K-phonon sub-bands in the optical absorption spectra. At high temperatures, absorption of a photon can be accompanied not only by emission, but also by absorption of one or more phonons.

Optical Absorption of Polarons at Arbitrary Coupling

The theoretical absorption spectrum of a single large polaron (at all electron–phonon coupling strengths) is given by the expression

$$\Gamma(\omega) = \frac{1}{n\varepsilon_0 c}\frac{\mathrm{Im}\Sigma(\omega)}{[\omega - \mathrm{Re}\Sigma(\omega)]^2 + [\mathrm{Im}\Sigma(\omega)]^2} \qquad [7]$$

The so-called memory function $\Sigma(\omega)$ contains the dynamics of the polaron and depends on α and ω. This function is related to the impedance function $Z(\omega)$ of the polaron through $-\mathrm{i}Z(\omega) = \omega - \Sigma(\omega)$.

Optical Absorption of Polarons at Strong Coupling

The absorption of light by free large polarons was treated by Kartheuser, Evrard and Devreese using the adiabatic strong-coupling method by Landau and Pekar. The polaron ground state in this scheme has the energy

$$E_0 = -\frac{\alpha^2}{3\pi}\hbar\omega_{\mathrm{LO}} = -0.106\alpha^2\hbar\omega_{\mathrm{LO}} \qquad [8]$$

If the lattice polarization is allowed to relax or adapt to the electronic distribution of the excited electron (which itself then adapts its wavefunction to the new potential, etc., leading to a self-consistent final state), the so-called relaxed excited state (RES) results. Its energy is

$$E_{\mathrm{RES}} = -0.041\alpha^2\hbar\omega_{\mathrm{LO}} \qquad [9]$$

It was argued by Kartheuser, Evrard and Devreese, that for a sufficiently large α ($\alpha > 3$), the (first) RES of a polaron is a stable state, which can participate in optical absorption transitions. This idea was important in order to understand the optical absorption spectrum in the strong-coupling regime. In particular, the following scenario of a transition, which leads to a zero-phonon peak in the absorption by strong-coupling polaron, can be suggested. If the frequency of a photon is equal to

$$\Omega_{\mathrm{RES}} \equiv \frac{E_{\mathrm{RES}} - E_0}{\hbar} = 0.065\alpha^2\omega_{\mathrm{LO}} \qquad [10]$$

then the electron goes from the ground state (following the analogy with the hydrogen atom, let us call it '1s') to an excited state ('2p'), while the lattice polarization in the final state is adapted to the '2p' state of the polaron.

Each RES of the polaron can be accompanied by 1, 2, 3, ... free optical phonons in the lattice. Such states are called scattering states (ScS). They are shown in Figure 3. Starting with the photon energy

$$\Omega_{\mathrm{RES}} + \omega_{\mathrm{LO}} \qquad [11]$$

a transition of the polaron towards the first ScS, belonging to the RES, becomes possible. In the course of this transition, while absorbing a photon, the polaron goes from the ground state to the RES with emission of one extra phonon. This process is called one-phonon sideband absorption.

The one-, two-, ..., K-phonon sidebands give rise to the broad structure of the absorption coefficient. These transitions occur without lattice relaxation. The (unstable) polaron state, in which the lattice polarization corresponds to the electron ground state, while the electron is excited ('a frozen lattice'), is referred to as the *Franck–Condon* (FC) state of a polaron. Within the adiabatic approach, the energy of the lowest FC state is

$$E_{\mathrm{FC}} = \frac{\alpha^2}{9\pi}\hbar\omega_{\mathrm{LO}} = 0.035\alpha^2\hbar\omega_{\mathrm{LO}} \qquad [12]$$

The superposition of the one-, two-, ..., K-phonon sidebands is centered at the FC transition frequency

$$\Omega_{\mathrm{FC}} \equiv \frac{E_{\mathrm{FC}} - E_0}{\hbar} = 0.141\alpha^2\omega_{\mathrm{LO}} \qquad [13]$$



Figure 3 Internal excitations of a polaron at strong coupling: E_0 – the ground state, E_{RES} – the (first) relaxed excited state; the Franck–Condon states (E_{FC}) are shown with a set of horizontal lines above the zero energy. In fact, both the Franck–Condon states and the relaxed excited states lie in the continuum and, strictly speaking, are resonances.

The optical absorption spectrum at strong coupling is, thus, characterized by the following features.

(a) There is an intense absorption peak ('zero-phonon line'), which corresponds to a transition from the ground state to the first RES at Ω_{RES}.
(b) At $\Omega_{\mathrm{RES}} + 1$, a phonon sideband structure appears (namely, a K-phonon sideband at $\Omega_{\mathrm{RES}} + K$). The maximum of this structure occurs at the FC transition frequency Ω_{FC}.

The qualitative behavior predicted by Kartheuser, Evrard and Devreese, namely, an intense zero-phonon (RES) line with a broader sideband at the high-frequency side, was revealed using a general all-coupling expression for the optical absorption coefficient [7] at $\alpha = 5, 6, 7$.

Internal Structure of Polarons at Arbitrary Coupling

The optical absorption spectra calculated according to the theory of Devreese *et al.* are displayed in Figure 4 for values of α in the range from 1 to 6.

The absorption spectrum for $\alpha = 1$ consists of a one-phonon line, similar to the weak-coupling result. The absorption peak for $\alpha = 3$ might correspond to a one-phonon peak at this intermediate coupling. It was also argued that part of the oscillator strength in the absorption for $\alpha = 3$ is due to lattice relaxation in the final states, be it to a smaller extent than for $\alpha = 5$.



Figure 4 Polaron optical absorption spectra at zero temperature, calculated within the path integral method (according to eqns [11a], [12], [13] of the paper (Devreese JT, De Sitter J and Goovaerts M (1972) Optical absorption of polarons in the Feynman–Hellwarth–Iddings–Platzman approximation. *Physical Review B* 5: 2367–2381)) for different values of the electron–phonon coupling constant α. The peaks are labeled in the picture according to their physical origin as discussed in the text. A δ-like central peak is schematically shown by a vertical line.

It is remarkable that from [7] the three different kinds of polaron excitations appear in the calculated optical absorption spectra for polarons at $\alpha \geq 5$:

- scattering states where, e.g., one real phonon is excited (the structure starting at $\omega = 1$);
- relaxed excited state (RES);
- Franck–Condon (FC) states.

Besides that, at zero temperature, the optical absorption spectrum for one polaron contains a central peak [$\sim\delta(\omega)$] at the origin. For nonzero temperature, this central peak smears out and the optical absorption spectrum consists of both a broad envelope and an anomalous Drude-type low-frequency component.

For example, in Figure 4 the main peak of optical absorption for $\alpha = 5$ at $\omega = 3.51$ is interpreted as due to transitions to RES. The shoulder at the low-frequency side of the main peak is attributed to one-phonon transitions to scattering states. The structure centered at about $\omega = 6.3$ is attributed to a FC band. As seen from Figure 4, when increasing the electron–phonon coupling constant to $\alpha = 6$, the RES peak at $\omega = 4.3$ becomes very intense compared with the FC peak centered at $\omega = 7.5$.

The free-carrier polaron effects were revealed through measurements of optical constants, of cyclotron resonance and of mobility in semiconductors and insulating photoconductors. Experimentally, only the scattering states have been seen for free polarons. However, the full structure of eqn [7] has been revealed through cyclotron resonance measurements.

Magneto-absorption of Polarons

Polaron Cyclotron Resonance

A polaron in a magnetic field is referred to as a *magnetopolaron*. The most powerful technique to study the electron–phonon coupling in semiconductors is cyclotron resonance. Changing the magnetic field B allows one to vary the cyclotron frequency $\omega_c = eB/m_b c$. When it is brought closer to resonance with the phonon frequency ω_{LO}, a strongly renormalized magnetopolaron state is formed. This results in a splitting of the cyclotron resonance, which is a measure of the electron–phonon (polaron) coupling constant α.

A theory of the polaron effects in cyclotron resonance was proposed by Larsen. In particular, the variational approach of Larsen is based on an intermediate-coupling theory to calculate the energy levels (modified Landau levels) of a polaron in a magnetic field. The polaron mass is then defined from the energy differences between the polaron (Landau-) energy levels.

A rigorous way to find the polaron cyclotron mass is to calculate the magneto-optical absorption spectrum of the polaron (the quantity which is actually measured) and to define the polaron mass, in the same way as the experimentalists do, from the peak positions in the spectrum. The magneto-optical absorption of polarons for all α and ω_c at $T = 0$ was calculated by Peeters and Devreese. They extended the memory-function formalism described above to study the response of a polaron in a magnetic field. The magneto-absorption was then obtained from

$$\lim_{\varepsilon \to 0} \mathrm{Re} \frac{1}{z - \omega_c - \Sigma(z)} \qquad z = \omega + \mathrm{i}\varepsilon \qquad [14]$$

where $\omega_c = eB/m_b$ is the cyclotron frequency for a rigid-lattice band mass m_b, and $\Sigma(z)$ is the memory function, which takes into account all the polaron internal states as well as all the Landau levels and depends on the coupling constant α and on the magnetic field. The explicit results for $\Sigma(z)$ depend on the optimal parameters of the anisotropic Feynman polaron model, which are found by a variational calculation of the polaron ground-state energy.

At $T = 0$ and when $\omega < 1$, it follows that $\mathrm{Im}\Sigma(\omega) = 0$. According to eqn [14], the position of the cyclotron resonance line is determined by the equation $\omega - \omega_c - \Sigma(\omega) = 0$. If solutions of this equation are denoted as $\omega = \omega_c^*$ then the polaron cyclotron mass m_p^* is calculated from the relation $\omega_c^* = eB/m_p^*$.

Cyclotron Resonance of Polarons in Silver Halides

In pioneering experimental studies, Brown and coworkers have combined mobility experiments and cyclotron resonance measurements to clearly demonstrate the polaron effect in AgBr. From a theoretical plot of polaron mobility versus band mass compared to experimental Hall mobility data at a given temperature, they estimate the band mass. This allows them to calculate α and the polaron mass m^*. This value of m^* can then be compared to the measured cyclotron mass in order to test the polaron theory. For AgBr, the experimental value $m^*/m_e = 0.27 \pm 0.01$ obtained from the cyclotron resonance at millimeter wave frequencies and at 18 K is shown to agree well with the value $m^*/m_e = 0.27 \pm 0.05$ determined by comparison of mobility experiment and theory.

Precise cyclotron mass measurements in AgBr and AgCl covered the range from zero magnetic field to 16 T (see Figure 5). Several polaron theories were compared in analyzing these experimental data. It should be pointed out that the weak-coupling theories (Rayleigh–Schrödinger perturbation theory, Wigner–Brillouin and its improvements) fail (and are all off by at least 20% at 16 T) to describe the



Figure 5 The polaron cyclotron mass in AgBr (a) and in AgCl (b): comparison of experiment and theory. Larsen: (Larsen D (1974) *Journal of Physics C* 7: 2877–2889); PD: (Peeters FM and Devreese JT (1986) *Physical Review B* 34: 7246–7259) (P) – with parabolic band, (NP) – with corrections of the two-band Kane model. In each case the band mass was adjusted to fit the experimental point at 525 GHz. (Reproduced with permission from Hodby JW, Russell G, Peeters F, Devreese JT and Larsen DM (1987) Cyclotron resonance of polarons in the silver halides. *Physical Review Letters* 58: 1471–1474). ©(1987) American Physical Society.

experimental data for the silver halides. The variational approach by Larsen underestimates the polaron cyclotron mass by 2% at 15.3 T. It turns out that the magneto-absorption calculated by Peeters and Devreese leads to the best quantitative agreement between theory and experiment as was analyzed for AgBr and AgCl. This analysis provides a clear confirmation of the Fröhlich description of the polaron in the case where weak-coupling approximations are adequate.

Cyclotron Resonance of Polarons in CdTe

The early infrared transmission study of hydrogen-like shallow donor impurity states in *n*-CdTe was reported by Cohn, Larsen and Lax (see Figure 6). By studying the Zeeman splitting of the ($1s \rightarrow 2p, m = \pm 1$) transition in the Faraday configuration at magnetic fields up to ~160 kOe, they performed the first quantitative determination of polaron shifts of the energy levels of a bound electron. The experimental data were shown to be in good agreement with the weak-coupling theory of the polaron Zeeman effect. In this comparison, however, the value $\alpha = 0.4$ was used instead of $\alpha = 0.286$, which comes from the definition [1]. Similarly, the value $\alpha \sim 0.4$ was suggested to explain the measured variation of the cyclotron mass with magnetic field in CdTe. This discrepancy gave rise to a discussion where important contributions have been, in particular, due to Harper and Zawadzki.



Figure 6 Plot of the experimentally determined magnetic field dependence of the ($1s \rightarrow 2p, m = \pm 1$) transition frequencies in n-CdTe. The solid lines represent the theoretical results for the effects of the electron–LO-phonon interaction upon the shallow donor impurity levels. α treated as a fitting parameter is taken to be 0.4. (Reproduced with permission from Cohn DR, Larsen DM and Lax B (1972) Polaron Zeeman effect in CdTe. *Physical Review B* 6: 1367–1374). ©(1972) American Physical Society.

Grynberg *et al.* applied the far-infrared photoconductivity technique to study the energy spectrum of shallow In donors in CdTe layers and obtained experimental data over the energy range relevant to study the magnetopolaron effect, as shown in Figure 7. An overall good agreement is found between experiment and the theoretical approach, where the electron–phonon interaction is treated within a second-order improved Wigner–Brillouin perturbation theory and a variational calculation is performed for the lowest-lying donor states ($1s$, $2p^{\pm}$, $2s$, $2p_z$, $3d^{-2}$, $4f^{-3}$). It is to be stressed that this agreement is achieved with the coupling constant $\alpha = 0.286$ as follows from eqn [1] with the known material parameters of CdTe.



Figure 7 Plot of the experimentally determined magnetic field dependence of the $1s \rightarrow 2p^{\pm 1}$ transition energies in CdTe layers grown by molecular beam epitaxy. The solid lines represent the results of the calculation described in the text without any fitting parameters. The solid dots are the experimental data of the present work and the open circles represent the data of Cohn, Larsen and Lax. (Reproduced with permission from Grynberg M, Huant S, Martinez G, *et al.* (1996) Magnetopolaron effect on shadow indium donors in CdTe. *Physical Review B* 54: 1467–1470). ©(1996) American Physical Society.



Figure 8 The cyclotron resonance position plotted as a function of magnetic field for InSe. (Reproduced with permission from Nicholas RJ, Watts M, Howell DF, *et al.* (1992) Cyclotron resonance of both magnetopolaron branches for polar and neutral. *Physical Review B* 45: 12144–12147). ©(1992) American Physical Society.

Polarons in the Layered Compound InSe and in Superlattices

Nicholas *et al.* provided a clear demonstration of the polaron coupling by the cyclotron resonance in a two-dimensional electron gas (2DEG), which naturally occurs in the polar semiconductor InSe. One clearly sees, over a wide range of magnetic fields ($B = 18-34$ T), the two distinct magnetopolaron branches separated by as much as 11 meV ($\sim 0.4\omega_{\mathrm{LO}}$) at resonance (Figure 8). The lines show the results of theoretical calculations for coupling to the LO phonon in bulk (3D), sheet (2D) and after correction for the quasi-2D systems at $\alpha = 0.29$ (for motion perpendicular to the *c*-axis). The agreement is reasonable for the 3D case, and is better for the quasi-2D system, where the finite spatial extent of the 2D electron gas in the symmetric planar layer is taken into account.

For GaAs/Al$_x$Ga$_{1-x}$As quantum wells and superlattices, the polaron effect is found to decrease the energy of the shallow donor states at low magnetic fields and to lead to a resonant splitting of the energies at high magnetic fields. The results are in very good agreement with available experimental far-infrared optical data in the whole magnetic-field range.



Figure 9 Fluorescence spectra of CdSe quantum dots with wurtzite structure at the average radius $\langle R \rangle = 1.25$ nm. The dashed line represents the experimental data of Nirmal M, Murray CB, Norris DJ and Bawendi MG (1993) *Z. Phys. D* 26: 361–363, the dot-dashed line displays a Franck–Condon progression with the Huang–Rhys parameter $S = 0.06$ calculated using the adiabatic approximation, the dotted line shows another Franck–Condon progression with the Huang–Rhys parameter $S = 1.7$, which is obtained by fitting the ratio of one-phonon and zero-phonon peak heights to the experimental value, and the solid line results from the nonadiabatic theory. (Reproduced with permission from Fomin VM, Gladilin VN, Devreese JT, *et al.* (1988) Photoluminescence of spherical quantum dots. *Physical Reviews B* 57: 2415–2425). ©(1998) American Physical Society.

Optical Properties of Quantum Dots: Effects of the Polaron Interaction

In order to interpret the phonon-assisted optical transitions in semiconductor quantum dots, a theory was developed by Fomin, Gladilin, Devreese *et al.* comprising the exciton interaction with both adiabatic and Jahn–Teller phonons, and also the external nonadiabaticity (pseudo-Jahn–Teller effect). The effects of nonadiabaticity of the exciton–phonon system are shown to lead to a significant enhancement of phonon-assisted transition probabilities and to multiphonon optical spectra which are considerably different from the Franck–Condon progression (see Figure 9). The calculated relative intensity of the phonon satellites and its temperature dependence compare well with the experimental data on the photoluminescence of CdSe quantum dots, both colloidal and embedded in glass. These results clearly demonstrate a breakdown of the adiabatic approximation when describing the polaron interaction in quantum dots.



Figure 10 Experimental and theoretical conductivity data at 250 K for $Pr_2NiO_{4.22}$ and four contributions to the theoretical curves resulting from the transitions between the following polaron states: σ_1 – small → small; σ_2 – large → small; σ_3 – small → large; σ_4 – large → large. (Reproduced with permission from Eagles DM, Lobo RPSM and Gervais F (1995) Infrared absorption in oxides in the presence of both large and small polarons. *Physical Review B* 52: 6440–6450). ©(1995) American Physical Society.

Small Polarons

An electron or a hole trapped by its self-induced atomic (ionic) displacement field in a region of linear dimension, which is of the order of the lattice constant, is called a 'small polaron'. As distinct from large polarons, small polarons appear due to short-range forces.

Experimentally small-polaron effects have been analyzed, e.g., in KCl, LiF, NiO, MnO, TiO_2, $BaTiO_3$, $SrTiO_3$, $LaCoO_3$. More recently, Alexandrov and Mott (1996) surveyed both the principles and the main results of the small-polaron theory in the context of the (bi)polaronic approach to describe the physics of high-T_c superconductors.

Spectroscopic manifestations of both large and small polarons have been found by Eagles *et al.* in the infrared optical absorption spectra of $Pr_2NiO_{4.22}$. The infrared reflectivity spectra on a crystal of this material were measured between 30 and 20 000 cm^{-1}. Mid-infrared conductivity data for frequencies between 1000 and 16 000 cm^{-1} were obtained by Kramers–Kronig transformation of those reflectivity spectra. The resulting optical absorption spectrum was quantitatively interpreted (see Figure 10) using the assumption that in $Pr_2NiO_{4.22}$ two types of polarons, small and large, coexist but do not mix with each other. The contribution due to the transitions between the large-polaron states, which dominates the absorption in the low-frequency region, was calculated using the arbitrary coupling theory by Devreese *et al.* for the coupling constant $\alpha = 3$.

In summary, the polaron concept has been proven to be one of the corner-stones of modern solid-state optics.

Acknowledgments

This work has been supported by the BOF NOI (UA-UIA), GOA BOF UA 2000, IUAP, FWO-V projects G.0287.95, 9.0193.97, G.0274.01 and the W.O.G. WO.025.99N (Belgium).

See also

Semiconductor Materials: Quantum Dots.

Further Reading

Alexandrov AS and Mott N (1996) *Polarons and Bipolarons*. Singapore: World Scientific.

Devreese JT (ed.) (1972) *Polarons in Ionic Crystals and Polar Semiconductors*. Amsterdam: The Netherlands North-Holland.

Devreese JT (1996) Polarons. In: Trigg GL (ed.) *Encyclopedia of Applied Physics*, vol. 14, pp. 383–413. Weinheim: VCH.

Devreese JT, De Sitter J and Goovaerts M (1972) Optical absorption of polarons in the Feynman–Hellwarth–Iddings–Platzman approximation. *Physical Review B* 5: 2367–2381.

Feynman RP (1955) Slow electrons in a polar crystal. *Physical Review* 97: 660–665.

Kartheuser E, Evrard R and Devreese J (1969) Mechanism of absorption of light by free continuum polarons. *Physical Review Letters* 22: 94–97.

Kuper CG and Whitfield GD (eds) (1963) *Polarons and Excitons*. Edinburgh, UK: Oliver and Boyd.

Landwehr G and Rashba EI (eds) (1991) *Landau Level Spectroscopy*, 2 vols. Amsterdam, The Netherlands: North-Holland.

Peeters FM and Devreese JT (1986) Magneto-optical absorption of polarons. *Physical Review B* 34: 7246–7259.

Pekar SI (1951) *Issledovanija po Ekektronnoj Teorii Kristallov*. Moscow: Gostekhizdat (in Russian); German translation: (1954) *Untersuchungen über die Elektronentheorie der Kristalle*. Berlin: Akademie Verlag.

Quantum Wells and GaAs-Based Structures

P Blood, Cardiff University, Cardiff, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

A quantum well is a potential minimum within a semiconductor structure which is sufficiently thin to localize charge carriers on a length-scale similar to their de Broglie wavelength which, for an electron in GaAs at room temperature, is about 30 nm. When electrons are localized in this way their electronic and optical properties are determined by quantum mechanical aspects of their behavior which are not apparent in larger-scale structures. The potential well is usually formed by a sandwich of a thin layer of narrow-gap semiconductor between two layers of a wider gap material as depicted in Figure 1. Typical quantum wells have widths of about 5 nm and the key to their routine production has been the development of advanced epitaxial semiconductor crystal growth techniques such as metalorganic vapor phase epitaxy (MOVPE) and molecular beam epitaxy (MBE). The most significant application of these structures has been in opto-electronic devices, especially laser diodes, and in this article I describe how electrons behave in quantum wells with particular reference to optical properties.



Figure 1 Electron energy diagram illustrating the formation of a potential well by sandwiching a layer of narrow gap semiconductor material (B) between two wider gap layers (A).

The optical properties of semiconductors are usually considered in terms of transitions of electrons between quantum mechanical energy levels, as in the Bohr atom. An alternative description is to consider the spatial displacement of electrons in the oscillating electric field of the electromagnetic radiation. These two descriptions are linked through Schrödinger's equation. For each energy state there is an associated wavefunction which determines the spatial probability distribution of electrons in the state. Consequently, a change in quantum state implies a change in spatial distribution and energy of the electron system. Both approaches are used: here I adopt the viewpoint of transitions between energy states.

We begin with a quantum mechanical description of electrons in a 'bulk' material, as appears in many textbooks. Here electrons are constrained by a three-dimensional potential well of extent given by the sample dimensions, typically millimeters or centimeters and therefore large compared with the de Broglie wavelength. Then we examine what happens when the size of the sample is reduced in one direction: in the limiting case of a quantum well electrons are able to move in only two directions. Quantum confinement is also possible in two or three dimensions to produce a quantum wire or quantum dot, respectively, and it is easy to use the concepts developed in this article to determine the properties of such systems.

Electron States in Bulk Material

We first consider the behavior of an electron in one direction (the x-direction) within a potential well with large dimensions (side length L), then generalize this to three directions (see Figure 2). The wavefunction ψ_n and energy E_n (measured with respect to the bottom of the well) are given by solutions of Schrödinger's equation, which within the well is:

$$\frac{\hbar^2}{2m}\frac{\mathrm{d}^2\psi_n}{\mathrm{d}x^2} = E_n \qquad [1]$$

It is assumed that the potential is infinitely deep compared with the energy of the electrons.



Figure 2 The properties of electrons in a large cubic sample (a) can be obtained by solving Schrödinger's equation for the potential well formed by the sample in each direction (b). This potential well keeps the electrons within the material. The wavefunctions $\psi(x)$ shown in part (c) satisfy cyclic boundary conditions as described in the text, leading to a series of electron energy levels, E_n, given by eqn [3], shown in (b) of the figure.

Within the sample the electrons are described by plane waves of the form $\psi_n = A_n \sin(k_n x)$, where k_n is a wavevector ($= 2\pi/\lambda_n$, where λ_n is the wavelength), and substitution into eqn [1] gives the corresponding energy eigenvalues as

$$E_n = \frac{\hbar^2 k_n^2}{2m} \qquad [2]$$

where m is the mass of the electron. [Substituting $E_n = k_B T$ at room temperature (0.025 eV) and using an effective mass of $0.067m_0$ (for GaAs) in eqn [2] gives $k_n = 2.1 \times 10^8\ \mathrm{m}^{-1}$ and $\lambda = 30$ nm.] Applying cyclic boundary conditions which permit traveling-wave solutions of eqn [1] the wavelength must satisfy the condition $\lambda_n = nL$, i.e., $k_n = 2\pi n/L$, as illustrated in Figure 2, where n is an integer. The dimensions of a typical sample are much greater than the 'size' of an electron so n can be a very large number. The energy eigenvalues are therefore given by

$$E_n = \frac{\hbar^2}{2m}\left(\frac{2\pi n}{L}\right)^2 \qquad [3]$$

This treatment can be extended by solving eqn [1] for motion in three orthogonal directions, x, y, and z. In this case electron motion is described by a wavevector $\mathbf{k}$ comprising components k_x, k_y, k_z, each of which satisfies the cyclic boundary condition in the respective direction. We take the sample to be of dimension L in each direction with no loss of generality. Thus (representing unit vectors by $\langle \mathbf{x} \rangle$, etc.)

$$\begin{aligned}\mathbf{k} &= k_x\langle \mathbf{x}\rangle + k_y\langle \mathbf{y}\rangle + k_z\langle \mathbf{z}\rangle \\ &= \frac{2\pi n_x}{L}\langle \mathbf{x}\rangle + \frac{2\pi n_y}{L}\langle \mathbf{y}\rangle + \frac{2\pi n_z}{L}\langle \mathbf{z}\rangle \end{aligned} \qquad [4]$$

the energy is

$$E = \frac{\hbar^2}{2m}\left\{k_x^2 + k_y^2 + k_z^2\right\} \qquad [5]$$

and the wavefunction takes the vector form

$$\psi_k(\mathbf{r}) = A_k \sin(\mathbf{k}\cdot\mathbf{r}) \qquad [6]$$

$\psi_n^2(\mathbf{r})$ represents the probability of an electron being at the location $\mathbf{r}$. Each allowed electron state obtained by solution of Schrödinger's equation is specified by a unique combination of the numbers $(n_x\, n_y\, n_z)$, which take both positive and negative values corresponding to plane waves traveling in positive and negative directions. The Pauli exclusion principle states that only one electron of each spin can occupy a given quantum state so the amplitude of each wavefunction is normalized such that

$$\int \psi_k^2(\mathbf{r})\,\mathrm{d}\mathbf{r} = \int [A_k \sin(\mathbf{k}\cdot\mathbf{r})]^2\,\mathrm{d}\mathbf{r} = 1 \qquad [7]$$

where the integrals are evaluated over the volume of the sample. Since the amplitude of these solutions is constant throughout the sample electrons may be anywhere in the sample with equal probability. The motion of an *individual* electron of momentum $\hbar\mathbf{k}$ is represented by a wavepacket formed by combination of a number of wavefunctions having similar values of $\mathbf{k}$.

Because the sample dimensions are large the energies of the states allowed by Schrödinger's equation take a series of very closely spaced values for increasing integer values of n as shown in Figure 2b. Substituting a typical sample size of $L = 1$ mm into eqn [3], the $n = 1$ and 2 states are separated by only 7×10^{-11} eV in GaAs and these values are very small compared with thermal energies: at room temperature, $k_\mathrm{B}T = 0.025$ eV. The allowed values of $\mathbf{k}$ and E are discrete and there is a finite but very large number of allowed states in the sample. Since these are very closely spaced we can regard $\mathbf{k}$ and E as continuous variables and the allowed energy states form a continuum. We can calculate the number of allowed energy states dN in a small energy interval, dE, and hence determine the density of states in energy $g = (\mathrm{d}N/\mathrm{d}E)$ (the number per unit energy interval) at any value of energy.

Electron States in Quantum Wells

Now imagine a sample where the length of one side is reduced in the z-direction (L_z), as illustrated in Figure 3. Gradually the allowed values of k_z become more widely spaced as a consequence of the boundary conditions (eqn [4]). Eventually the width of the potential well becomes similar to the wavelength of the plane-wave state corresponding to the lowest energy level in the well. In these circumstances electron motion is not possible in the z-direction and the wavefunctions become standing waves with boundary conditions $n(\lambda_n/2) = L_z$ in an infinitely deep potential (where n_z takes only positive values) and the amplitude of the wavefunction outside the well must be zero. The lowest energy state, given by eqn [5] with $n_x = n_y = n_z = 1$, no longer lies near the bottom of the potential well. Since the energies associated with motion in the x and y directions remain very small (of order 10^{-10} eV derived earlier) because L_x and L_y are large, the energy of the lowest state is effectively determined by the z-dimension because it is very small, so eqn [5] gives

$$E_{n_z} = \frac{\hbar^2}{2m}\left(\frac{n_z\pi}{L_z}\right)^2 \qquad [8]$$

for the lowest energy state in the well. For $L_z = 5$ nm (and $m = 0.067$) E_1 is 0.22 eV above the bottom of the well. Equation [8] shows that this energy can be changed by choice of the well thickness. A simple interpretation of this behavior is as follows. When L_z becomes very small it is no longer possible for the z-component of the wavefunction of the lowest energy state to satisfy the boundary condition of zero amplitude at opposite sides of the sample. The condition can only be satisfied by wavefunctions which have a smaller wavelength, and consequently a higher energy.

Electrons can occupy states defined by all values of $(n_x\, n_y\, n_z)$, thus for $n_z = 1$ there is a continuum of allowed states at increasing energies corresponding to increasing values of $(n_x\, n_y)$ and corresponding to motion in the (x, y) plane (Figure 4a). Since L_x and L_y are both large these states are closely spaced and form a continuum. There is a similar continuum of energy


L_z
L
L
(a)
Electron energy
$n_z = 2$
E_2
$n_z = 1$
E_1
L_z
Distance, z
(b)

Figure 3 Electron energy diagram (b) for a sample (a) in which one dimension, L_z, is very small. The electron motion in the z-direction is constrained and the associated energy levels become widely spaced, defined by the integers $n_z = 1, 2, \ldots$ in eqn [8]. The wavefunctions in the z-direction, $\psi(z)$, are also illustrated for the first two electron levels.


Electron energy
E_1
E_2
E_3
$n_z = 1$
$n_z = 2$
$n_z = 3$
Sub-band
(a)
Electron energy
$\frac{m}{\pi\hbar^2}$
$g_{2D}(E)$
Density of states
(b)

Figure 4 (a) Electron energy diagram showing the energy states associated with unconstrained motion in the (x, y) plane for each sub-band formed by localizing the electrons in the z-direction, defined by $n_z = 1, 2, 3$, etc. When all these allowed states are summed at any energy and expressed as a number of states per unit energy interval we obtain the density of states function $g_{2D}(E)$ shown in (b). This has a series of steps corresponding to each sub-band edge.

states above the energy levels for $n_z = 2, 3$, etc. Thus the energy level diagram is a series of sub-bands, each defined by n_z and with a continuum of states associated with motion in two dimensions in the (x, y) plane, as shown in Figure 4. The number of continuum energy states in a given sub-band in a small energy interval gives the density of states for both spin directions

$$g_{2D}(E) = \frac{m}{\pi\hbar^2} \qquad [9]$$

per unit energy interval per unit sample area.

The density of states is independent of n_z and therefore the same for all sub-bands, and is independent of energy. The density of states function is therefore a series of steps of height given by eqn [9] at each sub-band energy as illustrated in Figure 4b. The density of states per unit area within a given sub-band is independent of L_z as a consequence of dealing with a two-dimensional system.

In real samples the quantum well is not infinitely deep: typically the well depth is in the range 100–400 meV, consequently electrons are not totally confined to the well but are able to penetrate into the barrier material by quantum mechanical tunneling. Solution of Schrödinger's equation for a finite well (treated in many quantum mechanics textbooks) again yields a series of sub-bands, finite in number and with an energy spacing smaller than that given by eqn [8]. In a typical GaAs well the lowest energy state may be about 100 meV from the bottom of the well. The density of states in each sub-band, which is due to the (x, y) motion, remains unchanged. The wavefunction in the z-direction $F(z)$ comprises a sine wave-like standing wave within the well and an exponentially decaying wave in the barrier representing tunneling (Figure 5). The wavefunction is therefore made up of (x, y) plane-wave components and the localized z component and is of the form

$$\Psi_k(\mathbf{r}) = A_k \sin(\mathbf{k}_{xy} \cdot \mathbf{r}_{xy}) F(z) \qquad [10]$$

where $\mathbf{k}_{xy}$ and $\mathbf{r}_{xy}$ are the wavevector and position vector in the (x, y) plane. This wavefunction is again normalized according to eqn [7] such that each state is occupied by one electron of a given spin direction. We see from Figure 5 that we cannot regard the electron as being localized in the well: the electron distribution in the z-direction is specified by the probability distribution $F^2(z)$.



Figure 5 Illustration of the envelope wavefunction $F(z)$ in the z-direction for an electron localized in the $n_z = 1$ sub-band of a well of finite depth. The electron is able to penetrate the barrier by tunneling and this is represented by the decaying part of the wavefunction outside the well.

Occupancy of States in Quantum Wells

The density of states function describes the energy distribution of allowed states in the quantum well. Whether or not particular states are occupied by electrons is determined by the electron concentration and the temperature through the thermodynamic properties of the system. In most cases electron–electron scattering is sufficiently rapid to bring the electron population into an internal equilibrium. Furthermore the interaction between the electrons and the crystal lattice is able to redistribute energy between the two systems so that the lattice and the electron distribution have the same temperature. The electron distribution can therefore be described by Fermi–Dirac statistics for which the probability of a state at energy E being occupied with an electron is

$$f(E) = \frac{1}{1 + \exp\left\{\dfrac{E - E_f}{k_B T}\right\}} \qquad [11]$$

where E_f is the chemical potential (which can be equated with the Fermi level for electrons), T is the lattice temperature and all energies are positive quantities measured with respect to the same arbitrary zero. The energy distribution of electrons in the well, $n(E)$, is then the product of the density of states function, $g_{2D}(E)$, and the occupation probability, $f(E)$, as depicted in Figure 6. The total number of electrons, n, is the integral over energy. Combining eqns [9] and [11], for a single sub-band gives:

$$n_a = \frac{mk_B T}{\pi\hbar^2} \ell n\left\{1 + \exp\left(-\frac{E_n - E_f}{k_B T}\right)\right\} \qquad [12]$$

per unit area, single sub-band.

We cannot specify the carrier density in the well 'per unit volume' since the extent of the distribution in the z-direction is not defined because electrons



Figure 6 (a) The density of states function for a quantum well, with the value of $g_{2D}(E)$ on the horizontal axis indicating how the density of states varies with increasing electron energy. (b) is an illustration of the probability that a state is occupied by an electron, showing how $f(E)$ varies with increasing electron energy, given by eqn [11]. The actual density of electrons in a given energy interval at any energy $n(E)$ is given by the product of the density of available states and the probability that the state is occupied as shown in (c). The integral of $n(E)$ over energy gives the total density of electrons given for each sub-band by eqn [12].

may tunnel into the barrier material. The electron distribution is properly specified as a number per unit area having a probability distribution in the z-direction given by the function $F(z)$. Where more than one sub-band is populated the total electron density is obtained by adding the contributions from each sub-band each given by eqn [12] with the same Fermi energy and the appropriate sub-band energy. We always use Fermi factors to specify the probability of occupation of a state by an *electron*. The probability that a state is empty is $(1 - f)$.

Formation of Quantum Wells

A quantum well is formed by sandwiching a narrow gap semiconductor layer (E_{g1}) between two layers of wider gap material (E_{g2}). To avoid the formation of defects and dislocations, which have a deleterious effect on many properties of the structure, the constituent materials must have the same lattice parameter. Figure 7a is an energy band diagram for an n-type double heterostructure with layers of micron dimensions. At each interface there are discontinuities in the conduction and valence bands, ΔE_c and ΔE_v, respectively, which account for the difference in the band gaps of the two materials, ΔE_g. While the value of ΔE_g is known for any system, the manner in which this difference is apportioned between the two band edges is not known a priori and the values of ΔE_c and ΔE_v must be obtained from experiment. The discontinuities are often expressed as fractions Q_c, Q_v of the band gap difference:

$$\Delta E_c = Q_c \Delta E_g, \qquad \Delta E_v = Q_v \Delta E_g \qquad [13]$$

In equilibrium the Fermi energy is constant across the diagram and there is a band-bending region on each side of the discontinuity such that the conduction band edges return to their equilibrium energy values at large distances from the interface. The extent of these regions is determined by the discontinuity and the doping level and is typically 200–1000 nm. At each single interface a triangular well is formed which localizes electrons and whose precise shape is determined by the doping density, the carrier distribution and discontinuity through simultaneous solution of Schrödinger's equation and Poisson's equation. Single heterointerfaces only localize the majority carrier. Quantum confinement of both types of carrier can be achieved by a very thin narrow gap semiconductor layer.

When the layer of narrow gap material is made thinner than the band-bending regions, the



Figure 7 Electron energy diagrams showing the formation of a quantum well as a very thin double heterostructure made up of materials of band gaps E_{g1} and E_{g2}. When the layers are thick the energy diagram is influenced by band bending at the interfaces as shown in (a). When the narrow gap layer is made thinner than the band-bending distances a rectangular well is formed in the conduction and valence bands with depths determined by the respective band offset as shown in (b). On the small distance scale of the well the bands are flat in each region of the structure.

conduction band edge in this layer is not able to regain its bulk equilibrium position and the two triangular wells coalesce as illustrated in Figure 7b. When the well is sufficiently thin, say L_z less than 20 nm, the band-bending across this layer is negligibly small and the well becomes effectively rectangular. This well accumulates electrons from the surrounding barrier material and its potential relative to the Fermi level rises such that there is band bending in the barrier material on each side of the well inhibiting further accumulation. Since the band bending in the barrier occurs on a distance of hundreds of nanometers (being determined by the doping density) it is not apparent over the distance scale of the diagram of the quantum well, which is on the order of 10 nm. Consequently, as shown in Figure 7b, the well can be drawn as a rectangle to a good degree of approximation. This thin, narrow gap layer localizes both electrons and holes. The form of the well is determined by the respective band discontinuities, ΔE_c and ΔE_v, and the thickness of the layer.

Potential wells formed in this way are the basis for most quantum-confined device structures.

Other forms are possible. In certain material combinations ΔE_c or ΔE_v may be negative, meaning that, at the interface, both discontinuities are in the same sense and only one carrier type is confined in the thin narrow gap material. These are known as 'type II' structures. If there is an electric field across the well due to doping or strain (piezoelectric) effects the well becomes triangular. Wells can also be engineered with steps in the potential profile and multiple well systems can be grown in which the states are quantum mechanically coupled. All these variants provide opportunities to engineer the properties of the structure.

One important development of the rectangular quantum well deserves mention. It is possible for the well material to have a different lattice parameter to that of the surrounding barrier material provided that the strain energy can be accommodated elastically within the structure. This means that the strain energy in the layer must be below the energy necessary for formation of dislocations and this translates into an upper limit on the layer thickness (the critical thickness) for a given mismatch. Incorporation of elastic strain is significant because relaxing the lattice match requirement widens the choice of well and barrier materials and because strain modifies the properties of the electronic states in the quantum well and these effects can be used to advantage in the design of devices.

Here we concentrate on the rectangular potential well. Such wells are widely used, particularly in opto-electronic devices, and this structure provides the basic concepts which lie at the heart of all quantum-confined systems. We consider the 'model' lattice-matched quantum well system: a GaAs well bounded by AlGaAs barriers.

GaAs/AlGaAs Quantum Well Structures

As Al is substituted for Ga in the $Al_xGa_{1-x}As$ alloy system the direct band gap increases from 1.424 eV in GaAs ($x = 0$) to 3.018 eV in AlAs ($x = 1$) (Figure 8) while the lattice parameter remains unchanged. A quantum well is formed using a narrow GaAs layer sandwiched between barrier layers of $Al_xGa_{1-x}As$ having a composition chosen to give the desired well depth. The whole structure is grown on a GaAs substrate. The band discontinuity ratio between GaAs and $Al_xGa_{1-x}As$ is independent of alloy composition (ΔE_c and ΔE_v are constant fractions of ΔE_g as x is varied) with $Q_c = 0.66$ and $Q_v = 0.33$. For a typical barrier composition of $x = 0.3, \Delta E_g = 0.374$ eV and ΔE_c and ΔE_v are 0.247 eV and 0.127 eV, respectively.



Figure 8 Variation of the direct band gap of $Al_xGa_{(1-x)}As$ with Al content (x).

Optical Properties of AlGaAs/GaAs Quantum Wells

General Principles

Figure 9 illustrates a transition of an electron between an occupied state at E_1 in the $n_z = 1$ sub-band in the conduction band and an empty state (i.e., a hole) at E_2 in the $n_z = 1$ sub-band in the valence band, resulting in emission of a photon of energy $h\nu = E_1 - E_2$ as required by energy conservation. This is the process of luminescence (or spontaneous emission), which requires external excitation such as illumination (photoluminescence) or biasing a p-n junction (electroluminescence, as in a light-emitting diode). Alternatively, incident light may promote an electron from an occupied state in the valence band to an empty state in the conduction band with the consumption of the energy of a photon. This is the process of optical absorption.

At typical temperatures the electrons and holes are at energies near to their respective band edges so the photon energy $h\nu$ is close to the separation of the $n_z = 1$ sub-bands. Since these energies are determined by the well width it is possible to change the photon energy for emission or absorption by changing the well width. As the well width is reduced the energy separation increases and the wavelength of light emitted by the structure is reduced. This ability to engineer the emission wavelength by simply adjusting



Figure 9 Illustration of a downward optical transition of an electron from a state in the $n_z = 1$ conduction sub-band to an empty state (hole) in the $n_z = 1$ valence sub-band resulting in emission of a photon of energy $h\nu = E_1 - E_2$. The spatial probability distribution of the electron and hole is specified by their respective envelope functions $F_c(z)$ and $F_v(z)$ and the probability of the transition occurring is proportional to their overlap integral, eqn [14].

the well width, without changing the chemical composition of the constituent materials, is one of the major attractions of quantum-confined structures. The shortest wavelength possible for a given material combination is determined by the band gap of the wide gap barrier material alongside the well.

The strength of the luminescence signal or the absorption is determined by the rates at which the electronic transitions occur. In general these rates are determined by the following intrinsic factors.

1. *The quantum mechanical probability of an electron making a transition between a full and an empty state*. This depends upon the 'matrix element' for the transition, which is a fundamental property of the well material and the overlap of the envelope functions. The electron and hole in the initial and final states must be in the same region of space and if the spatial distributions of electrons and holes, determined by F_c and F_v, do not overlap the probability for an electron to make a transition to the hole state is very low. The overlap is almost complete in a rectangular well (see Figure 9), but is only partial in a triangular well. The transition probability is proportional to

$$I_{\text{overlap}} = \left\{ \int F_v(z) F_c(z)\,dz \right\}^2 \qquad [14]$$

2. *The probability of occupation of initial and final states by electrons, specified by the Fermi factors* (eqn [11]). The initial state must be occupied and the Pauli exclusion principle prohibits an electron entering a final state which is already occupied. Thus for a downward transition resulting in emission of light the rate is proportional to $f_c(1 - f_v)$.
3. *The density of initial and final states* (eqn [9]). The more states there are within a given small energy interval, the greater the emission rate per unit energy.
4. *Photon distribution*. For processes such as optical absorption, which are 'induced' by the presence of a photon, the transition rate is also proportional to the photon density in the region of the well. Because the electrons are not wholly localized in the well, and because the spatial extent of the optical field is larger than that of the carriers, the coupling between the photon field (intensity $I_{\text{ph}}(z)$) and the carrier probability distributions is expressed as

$$I_{\text{coupling}} = \frac{\left\{ \int F_v(z) [I_{\text{ph}}(z)]^{1/2} F_c(z)\,dz \right\}^2}{\int I(z)\,dz} \qquad [15]$$

5. *Optical mode density*. The emission rate also depends upon the density of optical modes

available to receive the recombination radiation. In most situations the emission occurs into the cavity of free space which is very large compared with the wavelength of the radiation so the modes are very closely spaced and the cavity can accept radiation at any transition energy (this is the well-known Raleigh–Jeans theory of cavity radiation). However, in some special situations the cavity has dimensions comparable with the wavelength of the radiation (microcavities) and then the modes are widely spaced. In such a microcavity, the optical cavity effectively controls the electronic transitions.

Optical Absorption

Figure 10 is an optical absorption spectrum for a GaAs quantum well measured with light incident normal to the plane of the quantum wells. A series of steps can be seen which correspond to absorption at increasing photon energy between increasing orders of sub-bands, $E_{1e} \rightarrow E_{1h}$, $E_{2e} \rightarrow E_{2h}$, etc. Normally $n_z = 1$ to $n_z = 2$ transitions are forbidden in rectangular wells. At each step there is a pair of peaks (not always resolved) and above each step the absorption is roughly constant, following the step-like density of states function sketched in Figure 4. The peaks are due to the formation of excitons which are weakly bound electron–hole pairs. In bulk materials excitons are only observed at low temperatures whereas in quantum wells the localization increases the binding energy (E_{bX}, typically 6–8 meV) such that they are observed at room temperature. The excitonic peak is at an energy E_{bX} below the sub-band separation. There are in fact two different kinds of electrons in the valence band with different masses so there are pairs of $n_z = 1, 2, 3, \ldots$ sub-bands due to the different confinement energies for the different valence electrons. Spectra of this kind provided the first evidence for the distinctive sub-band structure of quantum well systems produced by carrier confinement. Absorption measurements provide data on the energy spacing of the sub-bands in the well, and it is possible to determine the well width and depths, from which the band offsets can also be determined.



Figure 10 Absorption spectrum of a multiple quantum well structure having 10 nm GaAs wells measured at room temperature. The absorption edges corresponding to transitions between $n_z = 1, 2$, and 3 pairs of sub-bands can be identified. The peaks are due to absorption by formation of excitons.

The strength of the absorption is also of interest because it provides a measure of the optical matrix element if the Fermi factors f_c and f_v are known. If the incident optical beam is very weak such that the absorption process excites very few electrons then the system remains close to thermal equilibrium so the upper states are empty ($f_c = 0$) and the lower states are full ($f_v = 1$).

In *bulk material* the change in photon flux over a small distance Δx is proportional to the flux Φ and the distance traveled

$$\Delta\Phi = -\Phi\alpha\Delta x \qquad [16]$$

where α is the absorption coefficient which has units L^{-1}. This results in an exponential decrease of photon flux with distance traveled through the material

$$\Phi(x) = \Phi_0 \exp(-\alpha x) \qquad [17]$$

For a quantum well structure with light incident in the z-direction perpendicular to the plane of the quantum well, the fraction of light absorbed by a single well by transitions between a single sub-band pair (e.g., transitions between the $n_z = 1$ conduction and valence sub-bands) is independent of the thickness of the well because the density of states for a single sub-band is independent of well thickness. The strength of the absorption cannot be expressed by an absorption coefficient but by the fraction of light absorbed per well:

$$\Delta\Phi = -\gamma_w\Phi \qquad [18]$$

This arises because the quantum well is effectively a sheet in the z-direction: changing its thickness does not change the density of states per unit area (eqn [9]) and we cannot specify the electron concentration along the z-direction. This behavior also occurs because the well is much thinner than the wavelength of the light and it is not possible to specify the variation of photon flux on a distance scale smaller than the wavelength. The barrier material surrounding the well has a wider band gap and does not absorb at the photon energies absorbed by the well. The well thickness does affect the sub-band spacing and at a fixed photon energy the absorption increases as the well width is decreased as light is absorbed by transitions between more sub-bands. Equation [18] applies individually to each sub-band because the density of states is the same for each sub-band.

In a multiple well system, the fraction of light transmitted through N independent wells is

$$T_N = \{1 - \gamma_{\mathrm{w}}\}^N \qquad [19]$$

so the fraction of light absorbed by such a system is

$$\frac{\Delta\Phi}{\Phi} = -\left[1 - \{1 - \gamma_{\mathrm{w}}\}^N\right] = -N\gamma_{\mathrm{w}} \qquad [20]$$

which is proportional to the number of wells when $\gamma_{\mathrm{w}} << 1$.

The fraction of light absorbed by transitions between a single pair of sub-bands for a rectangular GaAs quantum well is predicted to be about 0.01, and a similar value has been obtained from absorption measurements. In a rectangular well the envelope function overlap is complete; however, in a triangular well of the same material the absorption is reduced by the smaller overlap of the envelope functions.

Photoluminescence and Spontaneous Emission

We turn now to discuss the optical emission from quantum wells as a result of external excitation. An external light source with photon energy above the effective band gap produces excess electron–hole pairs by excitation of electrons from the valence band. These rapidly lose their excess energy and thermalize to the sub-band edges to take up Fermi energy distributions. The electrons subsequently recombine to vacant valence band states by spontaneous emission. The low energy edge of this spectrum corresponds to the sub-band separation and the shape of the spectrum at higher energies corresponds to the thermal distribution of carriers in the bands. At very low excitation intensities where the excess electron population is small the luminescence may be due to recombination of electrons within an exciton and occur at an energy E_{bX} below the sub-band separation. Generally the sub-band separation is several $k_{\mathrm{B}}T$ so only the lowest sub-band is populated and photoluminescence is not seen from higher sub-bands. In this respect absorption measurements provide a more complete characterization of the structure.

While the energy position of features in the photoluminescence spectrum provides useful information, it is difficult to use the strength of the photoluminescence signal to provide quantitative information about the rate of optical transitions within the material because the excitation power and volume within the sample must be known and a known fraction of emitted light must be collected and measured with a calibrated detector. The relative intensity of photoluminescence under standard conditions does provide comparative information and the linewidth of the spectrum at low intensity provides a qualitative indication of ‘quality’ (e.g., well width variations in the structure). A quantitative determination of the internal recombination rate can be obtained by measuring the decay of the luminescence signal following short-pulse excitation. Fuller discussion can be found in books dealing with the characterization of semiconductor structures.

Concluding Remarks

We have shown that an understanding of the electronic structure of quantum wells follows naturally from quantum mechanical treatments of electrons in bulk materials. When one of the dimensions of the structure is reduced to be similar to the de Broglie wavelength, quantization of the electron motion in this direction becomes apparent. The sub-bands which are formed have a profound effect on the electronic and optical properties when their spacing exceeds thermal energies such that only one band is significantly populated with carriers. The density of states function is a series of steps, each corresponding to a sub-band, and this produces characteristic step features in the optical absorption spectrum. The effective band gap of the structure is controlled by the width of the well. Quantum confinement also increases the binding energy of excitons compared with bulk materials and under low excitation conditions absorption and luminescence spectra are dominated by excitonic features even at room temperature.

One of the most successful application areas of quantum well structures has been in laser diodes. Figure 11 shows experimental data for laser emission wavelengths as a function of well width, showing the dramatic reduction which can be achieved simply by changing the width of the quantum well. Furthermore the step density of



Figure 11 Measured values of the emission wavelength of GaAs/AlGaAs quantum well lasers as a function of well width, showing how the wavelength can be engineered by choice of the well width. Data from: squares: Woodbridge K, Blood P, Fletcher ED and Hulyer PJ (1984) Short wavelength (visible) GaAs quantum well lasers grown by molecular beam epitaxy. *Applied Physics Letters* 45: 16–18; and triangles: Chen HZ, Ghaffari A, Morkoç H and Yariv A (1987) Effect of substrate tilting on molecular beam epitaxial grown AlGaAs/GaAs lasers having very low threshold current densities. *Applied Physics Letters* 51: 2094–2096.

states function, characteristic of quantum wells, is one of the fundamental reasons for the reduction in threshold current of quantum well lasers relative to bulk GaAs devices.

We have considered GaAs because it is a model material system for production of quantum well structures. The concepts developed in this chapter are, however, quite general and can be applied to other material systems, other forms of quantum well and quantum wires and dots.

List of Units and Nomenclature

E	energy
E_f	Fermi energy
E_g	bandgap
F	envelope wavefunction
$f(E)$	Fermi–Dirac distribution function
g_{2D}	two-dimensional density of states $[\text{energy}]^{-1}$ $[\text{area}]^{-1}$
$\hbar$	Planck's constant divided by 2π
I_{ph}	optical field intensity
$\mathbf{k}$	wavevector
k_B	Boltzmann's constant
m	electron mass
n	carrier density, expressed per unit area in quantum well structures
Q_c, Q_v	heterostructure band offset ratios
$\mathbf{r}$	position vector
t	time
T_N	fraction of light transmitted at normal incidence through N quantum wells
$\langle \mathbf{x} \rangle$	unit vector along x-direction, similarly for y, z directions
α	optical absorption coefficient in a bulk material, per unit length
γ	fraction of light absorbed by a quantum well at normal incidence to the plane of the well
λ	wavelength
Φ	photon flux (photons per unit time crossing unit area)
Ψ	electronic wavefunction
ν	light frequency

See also

Semiconductor Materials: Band Structure Engineering; Quantum dots; Type-II Quantum Wells and Superlattices. **Semiconductor Physics:** Excitons; Outline of Basic Electronic Properties.

Further Reading

Bastard G (1988) *Wave Mechanics Applied to Semiconductor Heterostructures*. New York: Les Editions de Physique, Halstead Press.

Bimberg D, Grundmann M and Ledentsov NN (1999) *Quantum Dot Heterostructures*. Chichester, UK: Academic Press.

Blood P (1991) Heterostructures in lasers. In: Morgan DV and Williams RH (eds) *Physics and Technology of Heterojunction Devices*. Stevenage, UK: Peter Peregrinus.

Blood P (2000) On the dimensionality of optical absorption, gain and recombination in quantum-confined structures. *Journal of Quantum Electronics* 36: 354–362.

Blood P and Orton JW (1992) *The Electrical Characterisation of Semiconductors: Majority Carriers and Electron States*. London: Academic Press.

Casey HC Jr and Panish MB (1978) *Heterostructure Lasers*. San Diego, CA: Academic Press.

Dingle R, Gossard AC and Weigmann W (1975) Direct observation of superlattice formation in semiconductor heterostructures. *Physical Review Letters* 34: 1327–1330.

Eisberg R and Resnick R (1985) *Quantum Physics of Atoms, Molecules, Solids, Nuclei and Particles*, 2nd edn. New York: John Wiley.

Hook JR and Hall HE (1991) *Solid State Physics*. Chichester, UK: John Wiley.

Kelly MJ (1995) *Low-Dimensional Semiconductors*. Oxford, UK: Clarendon Press.
Orton JW and Blood P (1990) *The Electrical Characterisation of Semiconductors: Measurement of Minority Carrier Properties*. London: Academic Press.
Perkowitz S (1993) *Optical Characterisation of Semiconductors*. London: Academic Press.
Wolfe CM, Holonyak N Jr and Stillman GE (1989) *Physical Properties of Semiconductors*. Englewood Cliffs, NJ: Prentice Hall.

Recombination Processes

P T Landsberg, The University of Southampton, Southampton, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In studies of recombination there occur considerable complications; many are associated with interactions between electrons, electrons and phonons, excitons, bi-excitons, impurity centers, etc. Most of these are not required in the present exposition. Modern work normally assumes that the basics of recombination physics are understood and the present exposition offers an appropriate outline.

Basic Assumptions

Electron–Electron Interactions for Electrons in Bands

The recombination problem in semiconductors is greatly complicated by the interaction of the electrons with each other. This allows one to speak only of the quantum states of the semiconductor crystal as a whole. However, as in metals, so also in semiconductors, a simplified picture is successful. In this, the electron interactions, and other interactions, are first neglected, but are later taken into account as a perturbation. Thus, the electrons are first treated as if they can move through each other; the fact that they collide and deflect each other by virtue of their Coulomb interaction is treated as a perturbation. The transitions are still described within the framework of the single-particle states of the unperturbed problem.

The Effect of Electron–Boson Interactions

Our first approximation is to neglect most (but not all) electron interactions. Later we take into account the two-electron transitions that arise. This two-particle recombination process is referred to as Auger recombination and its inverse as the generation of current carriers by impact ionization. In addition, electrons interact with the radiation and lattice fields and emit or absorb photons or phonons. These electron–boson interactions result in transitions of single electrons in an energy band scheme. We shall attach a superfix ‘S’ (for single-electron) to the recombination coefficients for such processes. These are then denoted by B^{S} or T^{S} depending whether only bands are involved or whether traps are also involved. They are illustrated in Figure 1, where the solid horizontal lines represent the conduction and valence band edges and the dashed line refers to traps. Note that the two-electron transitions do not have the superfix ‘S’, while n and p refer to the electron and hole concentrations; N_0 and N_1 are the concentration of unoccupied and occupied trap states, respectively.

Electron–Electron Interaction in Traps

Electron–electron interactions can at least formally be taken into account in connection with electrons trapped in a center: the spectrum is a function of the number, $r\,(=1,2,3,\ldots,M)$, of electrons captured. The ‘irremovable’ electrons can be included with the ion core. Given that the center captured r electrons (say), it can still be in a variety of quantum states, and they will be denoted by the symbol ℓ, yielding a set of quantum states (ℓ, r) for a center. The energy of such a state, divided by kT to make it dimensionless, is denoted by $\eta(\ell, r)$, yielding the canonical partition function

$$Z_r = \sum_{\ell} \exp[-\eta(\ell, r)] \qquad [1]$$

The location of a center in space will here be considered to be of no significance.

Centers can capture several electrons. This brings in a need for the chemical potentials (or Fermi levels) for r-electron centers. They are here denoted by γ (when divided by kT) and the suffix ‘eq’ denotes an equilibrium value. Thus, the equilibrium probability of finding an r-electron center in state ℓ is given by:

$$P(\ell, r)_{\mathrm{eq}} = \frac{\exp[r\gamma_{\mathrm{eq}} - \eta(\ell, r)]}{\sum_{s=0}^{M} (\exp s\gamma_{\mathrm{eq}}) Z_S} \qquad [2]$$



Figure 1 Definition of recombination coefficients. Transition rates per unit volume are stated with each process, and, in brackets, for the reverse process. Thus B_1, B_2, T_1–T_4 refer to Auger processes; B^s, T_1^s, T_2^s refer to single-electron recombination; Y^s, X_1^s, X_2^s refer to carrier generation processes; Y_1, Y_2, X_1–X_4 refer to impact ionization processes. Arrows indicate transitions made by electrons.

One can identify the dominant energies from optical or electrical experiments.

To understand the properties of these centers, suppose we can arrange for the equilibrium Fermi level to rise from the valence band to the conduction band. At first practically no electrons are captured ($r = 0$). As the Fermi level rises the states corresponding to $r = 1$ begin to appear. The states ℓ of the center which correspond to the ground states in equilibrium are always more highly populated than the states ℓ corresponding to excited states, so that we can often confine attention to them. As the Fermi level rises, the ground states for $r = 2$ become more important, and there may now be hardly any centers which have captured fewer electrons. If a larger number of electrons cannot be captured, by the time the Fermi level reaches the conduction band, then states of the center with $r > 2$ can (normally) be neglected as unstable. That this is a satisfactory picture is our second approximation.

Assumptions for Nonequilibrium Statistics

The now much simplified recombination problem is still complex because of the many states available to electrons in bands and centers. A key simplification arises from the fact that it is often possible to talk about a small number of groups of quantum states: let $I\,(= 1, 2, \ldots)$ label quantum states in a group i, let $J\,(= 1, 2, \ldots)$ label quantum states in a group j, etc. Within each group it is supposed that the transitions are much more rapid than they are between groups. In that sense electrons in each group are in equilibrium among themselves. Their quasi-equilibrium is then characterized by what is called a quasi-Fermi level. The dimensionless version, obtained by dividing it by kT, is denoted by γ_i, γ_j, etc., for groups i, j, etc. That this is reasonable is our third assumption. Thus γ_c, γ_v are quasi-Fermi levels which refer to the quasi-equilibrium of the conduction and valence band, respectively, and γ_I to an I-electron center. Groups of states with different quasi-Fermi levels are not in equilibrium with each other.

Recombination problems can now be discussed by neglecting transitions within one (quasi-equilibrium) group, because they proceed at exactly the same rate as their reverse transitions. The number of transition types to be considered is thereby greatly reduced. Away from equilibrium we shall adopt eqn [3] instead of [2] in order to allow for distinct quasi-Fermi levels:

$$P(\ell, r) = \frac{\exp[r\gamma_r - \eta(\ell, r)]}{\sum_{s=0}^{M} (\exp s\gamma_S) Z_S} \qquad [3]$$

Equation [3] is not always correct, but is an approximation arising from the quasi-Fermi level assumption. Among the improved theories are, for example, the 'cascade' theories.

The assumption of a quasi-Fermi level for each state of charge of a center implies that all the excited states of an *r*-electron center are populated according to eqn [2].

The Main Recombination Rates

General Results and The Two-Band Case

Recombination and its converse, generation, consist of a transition of an electron from one state to another. The observed rate is the net rate of recombination and is the algebraic sum of the recombination and generation processes. During these processes both total energy and total momentum must be conserved. This is achieved by creation or absorption of photons, or phonons, excitation of secondary electrons, etc.

The transition probability per unit time, S_{IJ}, for a single-electron transition from state I in a band to state J requires that state I should be occupied, with probability p_I say, and state J should be vacant with probability q_J say. The general expression for the average rate of the transition from I to J then takes the form $p_I S_{IJ} q_J$. For the reverse process electron state J has to be occupied and state I vacant. Thus the rate of this reverse process is $p_J S_{JI} q_I$. The net recombination rate per unit volume of the process I to J can then be written as:

$$u_{IJ} = (p_I S_{IJ} q_J - p_J S_{JI} q_I) V^{-1} \qquad [4]$$

By the principle of detailed balance, this expression vanishes at equilibrium. If one puts $X_{JI} \equiv S_{IJ} p_I q_J / S_{JI} p_J q_I$, one has $u_{IJ} = p_J S_{JI} q_I (X_{JI} - 1) V^{-1}$. In equilibrium $X_{JI} \to (X_{JI})_{\mathrm{eq}} = 1$, and the recombination rate is zero.

One can say a little more if one assumes that states I and J are in conduction or valence bands, each with a quasi-Fermi level (divided by kT to make it dimensionless). If these are denoted by γ_{e} and γ_{h}, then $p_I = [1 + \exp(\eta_I - \gamma_{\mathrm{e}})]^{-1}$ for a conduction band. For the total recombination rate per unit volume between the bands i and j one finds:

$$u_{ij} \equiv \left[\sum_{I \in i} \sum_{J \in j} p_J S_{JI} q_I \right] \left[\exp\left(\frac{|e|\phi}{kT} \right) - 1 \right] V^{-1} \qquad [5]$$

where ϕ is essentially the difference between the quasi-Fermi levels: $\gamma_{\mathrm{e}} - \gamma_{\mathrm{h}}$. The first factor depends on the bands involved and it has been assumed that the transition probability ratio S_{IJ}/S_{JI} is independent of the excitation.

A transition rate, when multiplied by the charge of current carriers, is a current, and when divided by the area of the surface involved, is a current density. If i and j denote the states of the conduction and valence bands of a semiconductor, excitation independence may often be assumed, and one then expects a current density proportional to $\exp(|e|\phi/kT) - 1$. This is characteristic of the current through pn junctions, metal semiconductor junctions, etc. In these configurations the Fermi level difference between the ends of the device determines the voltage across it. When radiation is involved, however, excitation dependence of some of the parameters introduced above (e.g. S_{JI}) tends to spoil this simple story.

The Case of Defects

So far we have considered only two bands. When a trap is involved matters are rather different. Because of the interactions among the electrons on a center it is not possible to talk of the same level being occupied or vacant. Consequently, identification of forward and reverse processes in terms of levels becomes impossible. Instead one deals with a center, say an *r*-electron center, as a whole; we then need the probability that a given center is an *r*-electron center. For example, the capture of an electron converts an $(r-1)$-electron center into an *r*-electron center. Thus the *p*'s and *q*'s must be replaced by more complicated expressions. It is convenient to denote u_{ij} by u_{cv} in the simple two-band case and its structure is given (with a sign change) by a recombination coefficient:

$$u_{\mathrm{cv}} = B^{\mathrm{S}} np[1 - \exp(\gamma_{\mathrm{h}} - \gamma_{\mathrm{e}})] \equiv B^{\mathrm{S}} np - Y^{\mathrm{S}} \qquad [6]$$

using Figure 1a. Here, n and p are the electron and hole concentrations. Auger effects in Figures 1b and 1c can also be included, at least formally. Then B^{S} has to be replaced in eqn [6] by $B^{\mathrm{S}} + B_1 n + B_2 p$. Analogous replacements are found for recombination processes involving defects.

In the simplest case of one type of localized defect one finds a steady-state recombination rate per unit volume of the form:

$$u = \frac{np - (np)_0}{\tau_{n0}(p + p_1) + \tau_{p0}(n + n_1)} \qquad [7]$$

Here τ_{n0}, τ_{p0} are parameters with the dimension of time and p_1, n_1 are parameters with the dimension of concentration. The recombination increases with the defect concentration, which is actually in the denominators of τ_{n0} and τ_{p0}. This is an old and much used result associated with the names of W Shockley and W T Read.

Radiative Transitions

Spontaneous and Stimulated Emission

Quantum theory was initiated by Planck's law for black-body radiation at temperature T. This gives the spatial energy density as a function of frequency ν in this system as

$$f(\nu, T) = \frac{8\pi\nu^2}{c^3} \frac{h\nu}{\exp(h\nu/kT) - 1} \qquad [8]$$

For low frequencies one finds the Rayleigh–Jeans law which makes [8] proportional to kT in agreement with the classical equipartition theorem. For high temperatures [8] diverges, as required.

The result [8] may also be obtained by writing

$$N = [A + Bf(\nu, T)]N_{\mathrm{u}} \qquad [9]$$

for the emission rate of photons by atoms, where N_{u} is the number of atoms in the upper of two states which are separated by the energy $h\nu$. The first term on the right-hand side is due to the normal decay of an excited state ('spontaneous emission'). The second term refers to additional emission ('stimulated emission') induced by the radiation of frequency $h\nu$ itself.

The first factor in [8] is due to the density of states and the second factor is due to the fact that the energy is considered. If one considers the number of photons of energy $h\nu$ at temperature T one comes up with

$$N_\nu = \left[\exp\frac{h\nu - \mu}{kT} - 1\right]^{-1} \qquad [10]$$

(Bose–Einstein distribution)

Here μ is a possible chemical potential of the radiation which is non-zero only in nonequilibrium situations such as in a semiconductor laser.

In a pn junction the two bulk materials several diffusion lengths away from the junction are approximately in equilibrium even if a modest current is flowing. On one side one has then just one quasi-Fermi level, say μ_I, and on the other side one has just one quasi-Fermi level, say μ_J. Then the difference

$$\mu \equiv \mu_I - \mu_J = q\varphi \qquad [11]$$

corresponds to the applied voltage φ. This is in agreement with eqn [10], in that $\varphi = 0$ implies no current and hence thermal equilibrium is possible.

Statistical mechanics teaches one the rule that, in equilibrium, occupation probabilities of individual quantum states are always less for states of higher energies. This ensures that the total energy of a quantum system converges, the occupation probability p being a kind of convergence factor. However, if one is away from equilibrium, the above rule can be suspended and one can have population inversion.

For $h\nu = \mu$ there is trouble with [10] because the steady-state photon occupation diverges. This does not correspond to a 'death ray', but is the result of imperfect modeling; for example, the leakage of photons from the cavity may have been neglected. A formula of type [10] is also needed in connection with solar cells.

Donor–Acceptor Pair Recombination

A striking demonstration of radiative donor–acceptor transitions in GaP at low temperature (1.6 K) was revealed by sharp lines (Figure 2) at photon energies $h\nu_i$ given by

$$h\nu_i = E_{\mathrm{G}} - E_{\mathrm{A}} - E_{\mathrm{D}} + e^2/\varepsilon R_i\,[-E] \qquad [12]$$

where R_i is the distance between the ith-order nearest neighbors.

The discrete nature of the peaks is due to the fact that the impurities involved settle in general on lattice sites so that only definite separations R_i are possible. The energy gap is E_{G}; the value of $E_{\mathrm{A}} + E_{\mathrm{D}}$ can be inferred from the experimental lines by extrapolation to $R_i \to \infty$. The energy term E is sometimes neglected.

The ZnS phosphors were the first materials in which donor–acceptor radiation was hypothesized. However, it is hard to control its stoichiometry and its impurity content, and it has relatively large carrier mass and hence relatively large impurity activation energies. In such cases spectra such as those shown in Figure 2 are hard or impossible to obtain. This applies in general to many II–VI compounds.

Quantum Efficiency

The quantum efficiency is the radiative recombination as a fraction of the total recombination. It can also be regarded as the average number of electrons produced per incident photon. Consider an intrinsic semiconductor, i.e., one in which the electron and hole concentrations are equal. Then with the notation of Figure 1 the radiative band–band recombination rate is $B^{\mathrm{s}}n^2$. The nonradiative rate is $(B_1 + B_2)n^3$. We shall add another nonradiative rate, An say, proportional to the injected carrier density $n \sim p$. The quantum efficiency is then

$$\eta = \frac{B^{\mathrm{s}}n^2}{An + (B_1 + B_2)n^3 + B^{\mathrm{s}}n^2} \qquad [13]$$



Figure 2 Comparison of the positions and intensities of the sharp line spectra at 1.6 K corresponding to both ZnS and CdS acceptor–donor pairs with the predicted pair distribution. The lower scales show the pair separation (*R*) and the Coulombic energy derived from *R*. The emission energy scales for the two measured spectra are shown at the top. Reproduced with Gershenzon M, Logan RA, Nelson DF, *et al.* (1968) *Proceedings of the International Conference on Luminescence*. Budapest, Hungary: Akademia Kiada.

Traps are here neglected, and one finds a maximum

$$\eta_{\max} = \left\{1 + \frac{2}{B^{s}} A^{1/2} (B_1 + B_2)^{1/2}\right\}^{-1} \qquad [14]$$

For a high-quality epitaxial AlGaAs/GaAs double heterostructure of great purity we may take

$$A \sim 0.5 \times 10^{6}\ \mathrm{s}^{-1},\ \ B \sim 10^{-10}\ \mathrm{cm}^{3}\ \mathrm{s}^{-1},$$
$$B_1 + B_2 \sim 10^{-29}\ \mathrm{cm}^{6}\ \mathrm{s}^{-1} \qquad [15]$$

whence $n_1 \sim 2 \times 10^{17}\ \mathrm{cm}^{-3}$, $\eta_{\max} \sim 0.96$.

Detailed Balance

It is clear that the radiative recombination rate from a material should be obtainable in terms of its optical ‘constants’, the absorption coefficient $\alpha(\lambda)$ and the refractive index $\mu(\lambda)$. Both are functions of the wavelength. This connection can be formalized by comparing the optical absorption process with the emission process and this can be done by using the principle of detailed balance. This equates the rate of disappearance by absorption of photons with the rate of production of photons by radiative recombination. The radiative recombination rate can thus be obtained as an integral over the optical functions. This relationship, pioneered by van Roosbroeck and Shockley in 1954, has been used a great deal because the optical quantities are often known with some accuracy.

This result corresponds to balancing the rate $B^{s}np$ and the rate Y^{s} in Figure 1a. Analogous detailed balance results are obtainable for the other pairs of processes in Figure 1. Thus, the Auger recombination rate can be related to an integral over the impact ionization rate. However, this connection is less useful since impact ionization data are generally less well known than the optical absorption information.

Nonradiative Processes

Auger Effects

The Auger effect was discovered in 1925 in gases by Pierre Auger. An atom is ionized in an inner shell. An electron drops into the vacancy from a higher orbit and a second electron takes up the energy which is used to eject it from the atom. In solids the effect is roughly analogous. One of its characteristics is that it is not radiative. Since radiation is what is seen in many experiments, the Auger effect is suspected if and when there is less radiation than expected in the first place. It is rather harder to investigate than radiative transitions.

The effect has proved to be important as it limits the performance of semiconductor lasers, light-emitting diodes and solar cells, and it can be crucial in transistors and similar devices whose performance is governed by lifetimes. When heavy doping is required, as it is in the drive towards microminiaturization, its importance tends to increase, since the Auger recombination rate behaves roughly as n^2p or p^2n (see Figure 1) compared with the radiative rate which behaves more like np. The inverse process is impact ionization, and is important in the photodiode, the impact avalanche transit time (IMPATT) diode, and hot electron devices.

Impact ionization can be regarded as an autocatalytic reaction of order one:

$$\mathrm{e} \rightarrow 2\mathrm{e} + \mathrm{h} \quad \text{or} \quad \mathrm{h} \rightarrow 2\mathrm{h} + \mathrm{e} \qquad [16]$$

i.e., one extra particle is produced of the type present in the first place. This is a key feature for impact-induced nonequilibrium phase transitions in semiconductors.

In the theory one needs wavefunctions for four states of two electrons which are relevant after the many-electron problem has been reduced to a two-electron problem. In a matrix element calculation the four wavevectors imply a 12-fold integration in $\boldsymbol{k}$-space to cover all possible states of the two electrons. However, momentum and energy conservation usually reduce this to an eight-fold integration. Such a calculation is hard, for it requires (1) good wavefunctions and (2) accurate integrations.

Here we shall merely concentrate on the broad principles. In addition, the many-electron nature of the problem implies that another approximation is often inherent in the treatment apart from the use of perturbation theory. This is clear if one considers that the electron interactions are screened twice: once by an exponential screening factor and a second time by the dielectric constant. So there is some double counting, and the treatment of the effect as uncorrelated electronic transitions mediated by screened Coulomb interactions is another approximation. The collective effects that enter require more sophisticated field theoretic methods which take care of electron–hole correlations, plasmon effects and the effect of free excitons, the so-called excitonic Auger effect. These calculations broadly confirm the results obtained by the simpler methods used for energy gaps large compared with the plasmon energies, provided the high-frequency dielectric constant is used and doping is not too heavy. Significant corrections are required for the narrow gap lead compounds, for example, and a considerable computational effort is required.

Let us now consider lifetimes for high carrier concentrations, as limited by band–band processes. They are best studied by looking at the emitted radiation. In this connection we recall the striking rise of the threshold current density J in a semiconductor laser as the material is changed from a direct material like GaAs to an indirect material, by mixing it with a compound such as GaP. Figure 3 shows this spectacular rise for $\mathrm{GaAs}_{1-x}P_x$ at 77 K near $x = 0.38$. It is due to the drop in the radiative transition probabilities, as the substance becomes indirect, thus requiring a higher current density for threshold. So we should start with band–band processes in direct materials as most favorable for the experimentally accessible radiative transitions.

The essential point here is that the injected carrier density behaves as:

$$n_{\mathrm{inj}} = \frac{J\tau}{qd} \sim \frac{(5\times 10^{3}\ \mathrm{A\ cm^{-2}})(10^{-9}\ \mathrm{s})}{(1.6\times 10^{-19}\ \mathrm{C})(10^{-4}\ \mathrm{cm})} \sim 10^{17}\ \mathrm{cm^{-3}} \qquad [17]$$

where J/q is the particle current density at threshold, τ is the lifetime of the carriers, and d is the thickness of the active layer. As active layers are made thinner n_{inj} increases to $10^{19}\ \mathrm{cm^{-3}}$ or so, far in excess of the defect concentration in the (undoped) material. This brings in band–band Auger effects. These have also been invoked to explain the undesirable increase in J with temperature. Thus the interest in direct band–band Auger effects in III–V compounds is fuelled by the need for better and smaller opto-electronic devices which work at long wavelengths (1.3–1.5 μm). It matches the interest in indirect band–band Auger and impurity Auger effects in silicon due to the importance of heavy doping in VLSI (very large scale integration) and transistor technology. Figure 4 shows a typical Auger process, called CHHS, as the conduction band (C) and the split-off band (S) are involved. Two relevant states are in the heavy hole band (H). State 2′ is referred to as the Auger carrier, as it has more kinetic energy than the others.



Figure 3 Lowest values of laser threshold current density at 77 K as a function of mole fraction of GaP for $\mathrm{Ga(As}_{1-x}P_x)$ junction lasers. Reproduced from Neill CJ, Stillman GE, Sirkis MD, *et al.* (1966) Gallium arsenide-phosphide: Crystal, diffusion and laser properties. *Solid-State Electronics* 9: 735–742, with permission from Elsevier.



Figure 4 Conduction band, heavy hole and split-off valence bands of GaAs, all treated as parabolic with $\hbar^2 k_0^2/2m_h \equiv E_G - \Delta$. *x* denotes a quadruplet of states for a most probable transition. The two states in the heavy hole band are not shown separately. The arrows indicate electron transitions. Reproduced from Neill CJ, Stillman GE, Sirkis MD, *et al.* (1966) Gallium arsenide-phosphide: Crystal, diffusion and laser properties. Solid-State Electronics 9: 735–742, with permission from Elsevier.

Impact Ionization

The CHHS and CHCC processes and their inverses can be written as

$$\mathrm{e_C + 2h_H \leftrightarrow h_s \quad 2e_C + h_H \leftrightarrow e_C} \qquad [18]$$

where the suffix refers to the band. Viewed from left to right these are Auger processes. Viewed from right to left they are autocatalytic and impact ionizations.

Such processes are important for the impact-induced nonequilibrium phase transition in semiconductors. Also reaction rates with autocatalytic elements imply nonlinear equations in the concentrations and this gives rise to much interesting behavior as regards stability and bifurcation phenomena.

Momentum and energy conservation are very restrictive conditions on the four states involved in [18], and it is easily seen that they cannot normally be satisfied if in a direct band semiconductor the recombining electron drops from the band minimum to the valence band maximum. This effect raises all the kinetic energies of possible processes. The Auger electron (on the right-hand sides of [18]) must also have a minimum energy in order that the impact-ionization process can proceed. This leads to an activation energy for the process. For Figure 4, for example, and in the case of nondegeneracy, the energetic hole has a kinetic energy at threshold of

$$E_{\mathrm{th}} = \frac{m_{\mathrm{e}} + 2m_{\mathrm{h}}}{m_{\mathrm{e}} + 2m_{\mathrm{h}} - m_{\mathrm{s}}}(E_{\mathrm{G}} - \Delta) \quad \text{(CHSS)} \qquad [19]$$

As the band gap increases we see that E_{th} goes up and so the Auger rate for simple parabolic bands decreases. Values of E_{th} for other transitions can be obtained from equation [19].

The total kinetic or threshold energy E_{th} can be converted to an activation energy by subtracting the basic energy which must under all conditions be part of the Auger particle energy. In the case of eqn [19] one finds for $E_G > \Delta$:

$$\begin{aligned} E_{\mathrm{a}} &= E_{\mathrm{th}} - (E_{\mathrm{G}} - \Delta) \\ &= \frac{m_{\mathrm{s}}}{m_{\mathrm{e}} + 2m_{\mathrm{h}} - m_{\mathrm{s}}}(E_{\mathrm{G}} - \Delta) \end{aligned} \qquad [20]$$

This can result in a strong temperature dependence in accordance with an Arrhenius factor $\exp(-E_{\mathrm{th}}/kT)$. However, this is again lost, and the direct band–band Auger effect will certainly be important and only weakly temperature dependent, if $E_{\mathrm{G}} \sim \Delta$. This can occur, for example, for InAs, GaSh and their solid solutions.

The connection between Auger processes and impact ionization has also been formalized. Of all Auger quadruplets of states in a set of nondegenerate bands, the most probable Auger transition involves the quadruplet, which yields the threshold for impact ionization. The three crosses in Figure 4 indicate such a quadruplet (the central cross represents two states).

Identification of Auger Effects

How does one know that an Auger effect has occurred? In pure but highly excited materials there is the original solid-state Auger effect which leads to a lifetime broadening of the electronic states at the band edge. For a semiconductor this effect causes fuzziness in the band edge which is a contributory factor to the overall bandgap shrinkage. The mechanism is illustrated in Figure 5, which shows how the lifetime of a vacant electron state near the band edge is shortened by the Auger processes within this band. Under normal conditions this effect is small in a semiconductor. But under degenerate conditions the effect leads by lifetime broadening to a low-energy tail in emission.

The blanket term ‘Auger effect’ for all Coulombically excited two-particle transitions has been used here. In semiconductor device work the ‘Auger effect’ has become associated with transitions in which one electron bridges an energy gap. But there is no need to limit the concept in this way. Its competition with radiative effects means that it is often detrimental and a full discussion of means of suppressing it has recently been given by Pidgeon *et al.*

More spectacular and more convincing is the *detection* of the energetic Auger electron or hole. For this purpose one may look for the weak luminescence emitted when this carrier recombines radiatively. This has been done for the band–band process in Si and for the band–impurity process



Figure 5 The filling of a state *k* by the Auger effect. The arrows indicate electron transitions.

in GaAs. It leads to so-called $2E_G$-emission. Its rate-limiting step is the rate of the Auger process per unit volume, $B_1 n^2 p$, which populates the high-energy level. The radiative process then proceeds at a rate $B'_1 n^2 p^2$ per unit volume with $B'_1 \sim 10^{-54}$–10^{-51} cm^9 s^{-1}.

More usual is the identification of the band–band Auger recombination mechanism from the minority carrier lifetime τ, which behaves as

$$\frac{1}{\tau_p} = B_1 n^2 \quad \text{or} \quad \frac{1}{\tau_n} = B_2 P^2 \qquad [21]$$

where B_1 and B_2 are Auger coefficients when the Auger particle is an electron or hole, respectively. A more complete expression allows also for trapping processes.

The departure from parabolic bands plays an important part for the energetic Auger particle (in state 2′). Theory shows that when this effect is taken into account, it tends to lower the band–band Auger coefficient. In fact in GaAs the CHCC process is ruled out altogether at 0 K for nonparabolic bands, suggesting that it should be an ideal material for radiative transitions. However, the possibility of phonon participation brings the effect back again, though it is still comparatively weak. The difficulty of conserving electron energy and momentum, which gives rise to the activation energies (eqn [20]) is greatly alleviated if phonons can take up some of the momentum in a direct gap semiconductor.

We have seen that the activation energy barrier against the band–band Auger effect can be overcome by a suitable disposition ($E_G = \Delta$) of the three direct bands and by phonon participation. It can also be overcome if there is an indirect minimum near a Brillouin zone edge at about half the direct energy gap.

Acknowledgments

The author wishes to acknowledge support from NATO under their grant PST.CLG 975758.

See also

Semiconductor Physics: Band Structure and Optical Properties; Excitons; Impurities and Defects; Infrared Lattice Properties; Outline of Basic Properties; Quantum Wells and GaAs-Based Structures.

Further Reading

Fraser DA (1986) *The Physics of Semiconductor Devices*, 4th edn. Oxford, UK: Clarendon Press.

Hangleiter A (1985) Experimental proof of impurity Auger recombination in silicon. *Physical Review Letter* 55: 2976–2978.

Harrison D, Abram RA and Brand S (1999) Characteristics of impact ionization rates in direct and indirect gap semiconductors. *Journal of Applied Physics* 85: 8186.

Landsberg PT (1991) (paperback edn., 2003) *Recombination in Semiconductors*. Cambridge, UK: Cambridge University Press.

Nimtz G (1980) Recombination in narrow gap semiconductors. *Physics Reports* 63: 265.

Pidgeon CR, Ciesla CM and Murdin BN (1997) Suppression of non-radiative processes in semiconductor mid-infrared emitters and detectors. *Progress in Quantum Electronics* 21: 361–419.

Spin Transport and Relaxation in Semiconductors; Spintronics

M E Flatté, University of Iowa, Iowa City, IA, USA

D D Awschalom, University of California,
Santa Barbara, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Control of the generation and transport of coherent electron spin in semiconductors suggests new ways to probe the fundamentals of quantum decoherence in solids and to explore device applications that rely on coherence, including quantum computation. The focus here will be on the physical phenomena that govern spin transport and relaxation, with a particular emphasis on those phenomena that are amenable to direct manipulation. Manipulation of material properties in general has been taken to its most advanced level in the design of semiconductor electronic devices, in which operations are performed by perturbing the motion of electrons through their electric charge; hence, ‘spintronics’ is a term introduced to describe both the manipulation of electrons by their spin and control of their spin properties, such as *g*-factors.

The study of the evolution of spin coherence first requires the generation and detection of spin coherence. Here the ultrafast optical technique for generating and detecting spin-polarized populations will be emphasized. The next logical component to treat will be the persistence of spin coherence, followed by the transport of spin coherence from one region of a material to another. Finally the direct ultrafast manipulation of spin-polarized populations will be described. These components are likely to play a prominent role in any attempt to apply the fundamental physical phenomena of spin coherence to specific device technologies.

Optical Generation of Spin-Polarized Distributions

Optical pulses with definite circular polarization can be used to generate spin-polarized distributions of excited electrons in crystals. In order for this process to work one of the energy bands involved in the optical transition must be characterized by a substantial spin–orbit interaction. The selection rules for circularly polarized photons require a change in the orbital angular momentum of the electron projected along the propagation direction of the photon. For the optical transitions of an atom in free space this azimuthal orbital angular momentum l_z must increase or decrease by $\hbar$, permitting the coupling of the p-state with $l_z = 1$ to an s-state for left circular polarization, and of the p-state with $l_z = -1$ to that s-state for right circular polarization. Thus the optical selection rules pick out a particular orbital angular momentum projection.

These selection rules by themselves do not explain how spin-polarized populations are generated, for both spin directions are possible for each value of l_z. In the presence of spin–orbit interaction, however, the energy of a state with a particular l_z is correlated with the spin orientation. The six p-states, which are degenerate in the absence of spin–orbit interaction, split into two groups: one of four degenerate states and the other of two degenerate states. The higher-energy group of four degenerate states consists of two states with **L** and **S** parallel and two states with a one-third probability for **L** and **S** to be antiparallel and a two-thirds probability for **L** and **S** to be perpendicular. Thus for a transition involving the four degenerate states, a circularly polarized photon (that selects a particular initial l_z) is three times more likely to generate a carrier with spin parallel to the initial l_z than antiparallel to it.

In a solid, although full rotational symmetry is lost, the band symmetries preserve some of these selection rules. In crystals of tetrahedral symmetry, such as zincblende semiconductors, the selection rules for transitions from the valence to the conduction band are identical to the selection rules between p and s states for the atom in free space. For example, the valence heavy-hole states are those for which **L** and **S** are parallel. Thus by setting the optical photon energy to the fundamental gap, the resulting excited conduction electrons and valence holes will be spin polarized. In quantum wells, where the energy of the heavy hole is split from that of the light hole by quantum confinement (and, sometimes, strain), fully spin-polarized carrier distributions are possible. Commonly used group IV, III–V, and II–VI semiconductors have a sufficient spin–orbit interaction to permit the straightforward optical generation of spin-polarized distributions. Shown in Figure 1 are the selection rules



Figure 1 Selection rules for bulk zincblende crystals. Circularly polarized light changes the azimuthal orbital quantum number l_z by $+1$ or -1. Here $\Delta l_z = -1$ is shown. The orbital and spin quantum numbers for the two degenerate conduction band edge states and the four degenerate valence band edge states are shown – unshaded areas correspond to spin up and shaded to spin down. A transition with $\Delta l_z = -1$ couples one heavy-hole state to the conduction band up-spin state, and one light-hole state to the conduction band down-spin state. The orbital angular momentum of the heavy-hole state is entirely parallel to its spin angular momentum. In contrast only one-third of the light-hole state has antiparallel orbital and spin angular momentum. The rest of the light-hole state has perpendicular orbital and spin angular momentum. Thus the oscillator strength of the transition creating the conduction up-spin state is three times larger than that of the transition creating the conduction down-spin state, yielding a 50% spin polarized distribution. In quantum wells for which the heavy–light splitting is larger than the linewidth of the light source driving the transition, only the heavy-hole transition is excited and the spin polarization approaches 100%.



Figure 2 Diagram of the experimental geometry for time-resolved Faraday rotation. A pulse of circularly polarized light illuminates the sample, followed by a probe of linearly polarized light. The linearly polarized light can be considered as a sum of equal parts left and right circularly polarized light. The spin-polarization of the electron population (along the photon propagation direction) induces a difference in index of refraction for left and right circularly polarized light (circular dichroism). This produces a phase change between the left and right polarized components of the probe, which is measured as a rotation (θ_F) of the linear polarization direction. Monitoring the angle of rotation of the probe as a function of time directly indicates the spin polarization along the propagation axis of the photon as a function of time. Reproduced with permission from Awschalom DD, Samarth N and Loss D (eds) (2002) *Semiconductor Spintronics and Quantum Computation*. New York: Springer

which permit circularly polarized optical pulses to generate spin-polarized carriers in the conduction and valence band.

The evolution of a coherent spin-polarized population can be monitored through optical means as well. If the optical transitions used to generate the spin-polarized population are pumped hard enough, the transitions will be bleached. By measuring the polarization dependence of this bleaching the decay of the spin-polarized population can be determined. This can be done either by monitoring the transmission of time-delayed probe pulses of circularly polarized light, or by monitoring the rotation angle (Faraday rotation) of a pulse of linearly polarized light. The first of these depends directly on the imaginary component of the spin-polarized dielectric function, whereas the second depends directly on the real components. Shown in Figure 2 is the geometry for observing Faraday rotation from a spin-polarized distribution in the presence of an applied magnetic field perpendicular to the spin polarization.



Figure 3 Time-resolved Faraday rotation measurements on bulk GaAs at several doping levels, indicating a sensitive doping dependence of the transverse spin coherence time T_2. T_2 for ideal doping densities can exceed 150 ns at 5 K. The magnetic field is 4 T, and the sample is 50 μm thick. Reproduced with permission from Kikkawa JM and Awschalom DD (1998) Resonant spin amplification in *n*-type GaAs. *Physical Review Letters* 80: 4313–4316.

Mobile Electron Spin Time Evolution: Decoherence and Precession

Two natural phenomena in the time evolution of a coherent spin-polarized population are decay of that population (decoherence) and rotation of the macroscopic magnetization in the presence of an applied magnetic field (precession). The time-scale of decay of the spin coherence can be very much longer than time-scales for the decay of other coherent phenomena in solids. Typical orbital coherence times, for example, are 100 fs, whereas spin coherence times can exceed microseconds. In Figure 3 are shown time-resolved Faraday rotation data for three bulk GaAs crystals with different doping levels. The oscillations are characteristic of the spin precession, and the oscillation frequency is the Larmor frequency of the electron spin in this crystal. The crystal with the middle doping level, $10^{16}\ \mathrm{cm}^{-3}$, has oscillations that persist for the longest time, and therefore this material has the longest spin coherence time.

The dominant mechanism for the decay of these spin polarized distributions works via the same spin–orbit interaction that permits the generation and detection of these spin-polarized distributions. For mobile electrons in homogeneous environments, the mechanisms of spin coherence relate to the crystal momentum-dependence of the eigenstates of the electronic system. Because of time reversal invariance the electronic states with zero momentum (at the Γ point in the Brillouin zone) are doubly degenerate. The electronic states for momentum $\mathbf{k}$ near the Γ point occur in nearly degenerate pairs. Although it is common usage to refer to these eigenstates as degenerate spin eigenstates (correct in the absence of spin–orbit interaction), with spin–orbit interaction the states are not spin eigenstates and are not necessarily degenerate. As a consequence, when a spin-polarized carrier is scattered by ordinary, non-spin-dependent scattering from one momentum state $\mathbf{k}$ to another $\mathbf{k}'$, and then back again to $\mathbf{k}$, the effective orientation of the carrier spin will have rotated by an angle dependent on the intermediate momentum state $\mathbf{k}'$. For a population of carriers in thermal equilibrium this process will lead to misorientation of the individual spin moments from the mean, and thus a decoherence of the spin population. This process is characterized by an increasing decoherence rate with increasing orbital scattering. Thus the dirtier a material is made, the faster the spin orientations decohere.

In crystals with inversion symmetry the pairs of nearly degenerate states are precisely degenerate. Lack of inversion symmetry, and the consequential energy splitting, can be viewed as an effective (crystal) magnetic field, in which the approximate spin eigenstates precess. The magnitude and direction of this effective field depends on the orbital momentum $\mathbf{k}$, and because of time reversal invariance, the effective fields for $\mathbf{k}$ and $-\mathbf{k}$ are opposite. Thus an initially spin-polarized population will dephase due to experiencing different effective magnetic fields. Ordinary spin-independent scattering can now be seen as randomly changing the precession axis for the spin in this effective field. Once the information about the precession axis orientation has been lost the dephasing is not reversible and the spin orientations have decohered. As the precession angle increases linearly between scattering events, the longer the time between such scattering events the faster the spin population decoheres. Thus for this process the cleaner a material is made, the faster the spin orientations decohere. This precessional decoherence process dominates for mobile conduction electrons in bulk and quantum-well III–V semiconductors near room temperature.

The influence of the spin–orbit interaction is far stronger for the valence electrons than the conduction electrons for two reasons. First, as the effective magnetic fields come from relativistic transformations of internal electric fields, and the electric fields are largest near the nucleus, the valence electrons, which are closer to the nucleus than the conduction electrons, experience a stronger spin–orbit interaction. Second, the valence electrons have a dominant p-like character, whereas the conduction electrons have dominant s-like character (and thus lack orbital angular momentum to be coupled to the spin). Thus the spin coherence times of valence electrons (or holes) are commonly much shorter than the coherence times of the conduction electrons. Spin-flip exchange between conduction electrons and valence holes can therefore be the dominant source of decoherence for conduction electrons. This process can dominate at low temperatures in clean III–V semiconductors, and even up to room temperature in III–V quantum wells grown along the unusual (110) growth direction.

As a consequence one would expect the spin coherence times of electrons in n-doped semiconductors to be longer than those of electrons in p-doped or undoped semiconductors (in which excess holes must also be optically generated). This expected trend is present in Figure 3, for the n-doped materials have longer spin coherence times than the semi-insulating material. However, as the effect of the spin–orbit interaction increases with increasing momentum $\mathbf{k}$, the spin coherence times of the more heavily doped material are shorter than those of the lightly doped material. The doping corresponding to the longest spin coherence times may lie near the metal–insulator transition, although the theory of spin coherence times on the insulating side of that transition is not as well developed as on the metallic side.

Transport and Manipulation of Spin Coherence

An essential component of the motion of spin coherence in semiconductors is the response of carriers to electric fields. Outside of very unusual electronic states in semiconductors, such as the quantum Hall state, there is no spin–charge separation of elementary carriers. The carriers in the semiconductors will move under the influence of an electric field, and if they happen to be spin-polarized, then a spin current will exist. Although there are numerous possible regimes of spin transport (at least as many as there are regimes of charge transport), only two will be presented here, both in the low-field diffusive limit.

Mobilities and diffusion constants are the material properties that describe the low-field charge transport in a homogeneous material. Spin transport can be described similarly, and the spin mobility and diffusion constant can be related to those of charge motion. The relationship between the two emerges from the nature of carrier packets that can be maintained under low-field conditions. Deviations from local charge neutrality cause very large space-charge fields in the semiconductor, and thus under low-field conditions approximate local charge neutrality must be maintained. Shown in Figure 4 are charge and spin packets in an n-doped semiconductor. The charge polarization packet, incorporating extra conduction electrons and valence holes, is shown in Figure 4a. The electron spin polarization packet shown in Figure 4b is qualitatively different from the charge packet as well as the hole spin polarization packet (shown in Figure 4c). Only the electron spin polarization packet does not incorporate both conduction electrons and valence holes.

The difference in packet structure profoundly changes the mobility and diffusion properties of the packet. For packets consisting of both electrons and holes the low-conductivity carrier species dominates the packet motion (in this case, the holes). For the electron spin packet, however, majority carriers dominate the packet motion. Thus motion of this spin packet is very rapid, and also sensitive to the higher Fermi temperature of electrons relative to holes. Experimentally this has been seen by optically creating a local spin-polarized packet of conduction electrons (an electron spin packet) in a thin sample of n-doped GaAs. The application of a lateral electric field drags that spin packet, and an optical probe measures the transport distance (thus the mobility) and the packet spread (yielding the diffusion constant). Such an approach is very similar in concept to the electrical probe of charge packet motion developed by Shockley and Haynes to measure minority hole mobility and diffusion in n-doped Ge.



Figure 4 Inhomogeneous carrier packets in n-doped semiconductors in the low-field regime. The charge polarization packet (a) is constructed of approximately equal numbers of electrons and holes. The electron spin polarization packet (b) can be constructed without any excess holes, whereas the hole spin polarization packet (c) requires both excess electrons and excess holes. The presence of minority carriers in a packet significantly alters the mobility and diffusion properties of the packet.

The picture of approximately charge-neutral packets is very helpful for describing spin motion in homogeneous materials, but most semiconductor devices are based on inhomogeneous configurations of semiconducting material. For example, the most ubiquitous charge-based semiconductor device is the p–n diode, whose nonlinear current–voltage characteristics have been used as building blocks for numerous other devices. Such devices rely on the ability of a current to traverse an interface between two dissimilar materials – either different in doping density or different in host structure. Experiments in metallic ferromagnetic systems indicated that, whereas charge current was easily passed from one ferromagnetic metal to another through an interface, the same was not always true for the spin current. Differences in band structure or interface roughness are usually expected in such systems to strongly diminish the efficiency of spin current transfer across the interface.

Semiconductors, however, offer a possible new regime. The bulk band structures of most III–V semiconductors are very compatible – the variations in bandgap may be substantial, but the orbital wavefunctions are very similar. Current growth techniques permit the fabrication of atomically smooth interfaces between two semiconductors, so long as the lattice constants are almost identical. Thus one might expect the spin current to be transferred across such interfaces without tremendous degradation.

The transfer process for spin current across the GaAs/ZnSe interface has been investigated in detail. Here the ZnSe material was n-doped, and GaAs layers that were n-doped, p-doped, and semi-insulating were investigated. Electron spin polarization was generated optically in the GaAs layer. For n-doped GaAs in the absence of an electric field only a small signal for spin-polarized electrons in the ZnSe was detected. An applied electric field, however, which drove the electrons within the GaAs towards the interface, produced a substantial spin-polarized population in the ZnSe. This indicates that spin-polarized packets can be created in one semiconductor, and then controllably moved into a second semiconductor with an applied electric field. This ability may become a key component of manipulating spin in semiconductors.

One reason the p–n diode is a paradigm of charge-based semiconducting electronics is that it exhibits the crucial phenomenon of minority spin injection. Manipulation of minority spin injection permits great control of charge current, for its amplitude is very sensitive to barriers (such as those introduced by gates). Spin-polarized minority carrier injection has not been shown yet experimentally, however the complementary process of minority carrier extraction has. This process corresponds to optically generating spin-polarized electrons in p-doped GaAs, where the electrons are minority carriers. The built-in electric field of the p–n junction drives these electrons out of the GaAs into the n-doped ZnSe with great efficiency. Thus one may imagine that spin-polarized minority carrier injection is plausible in these systems.

A hybrid of these two situations is the spin-polarized light-emitting diode. Here spin-polarized carriers (either electrons or holes) are electrically injected into the insulating region of p–i–n structure. In the insulating region they recombine with unpolarized carriers of the other species and emit light. Due to the selection rules described before, the emitted light is circularly polarized, and the degree of circular polarization is an indication of the spin-polarization of the recombining carriers. This device demonstrates that large numbers of spin-polarized carriers can be accumulated in the insulating region, although the spin-polarized carriers are not minority carriers.

Methods of manipulating electron spin coherence externally without electric fields are also under investigation. One demonstrated technique relies on the shift of energy levels in a semiconductor under illumination by laser light with frequencies below the fundamental bandgap. When the laser light is circularly polarized this ‘ac Stark effect’ shifts the energy levels of spin-up states and spin-down states differently, generating an effective magnetic field. Rotations of electron spin by angles greater than $\pi/2$ have been demonstrated in this ultrafast effective magnetic field in semiconductor quantum wells.

Transfer of Spin Coherence from Mobile Electrons to Other Spin Systems

Another fundamental phenomenon in spin coherence is the transfer of spin coherence from one system to another. If one spin system has an extremely long coherence time, this transfer can be viewed as establishing a reservoir of spin coherence that can be drawn on at later times. Explorations of transfer phenomena have focused on establishing spin coherence in a system that is coupled to the conduction electrons, such as core electron polarization or nuclear polarization. The polarization of these other spin systems can be detected because, when polarized, they exert an effective field on the conduction electrons. For example, when the nuclear system is polarized it exerts an effective field on the electrons through the hyperfine coupling.

It is also possible to polarize these other systems indirectly through their interaction with the conduction electron system. When the conduction electron system is driven far from equilibrium by optically pumping the spin polarization, the coupled spin systems also become spin polarized. In the case of the nuclear spin system this effect is the Overhauser effect. While continually generating conduction electron spin polarization with optical pumping the polarization of the nuclear system begins to rise with a time-scale characterized by the coupling between the nuclear spins and the conduction electron spins (hyperfine coupling). Because of the substantial difference between the nuclear spin coherence times parallel to and perpendicular to the applied magnetic field, the effective nuclear polarization is generated parallel to the applied magnetic field independent of the orientation of the conduction electron spin polarization. In bulk GaAs at 5 K the percentage polarization achieved was a few per cent, yielding an effective field through the hyperfine interaction of ~ 0.4 T. These nuclear polarizations and effective fields are increased over an order of magnitude in certain quantum wells, suggesting that nanostructure design can be used to control the effective fields. The induced nuclear polarization persists for time-scales characteristic of the nuclear longitudinal spin coherence time, on the order of minutes. If the optical pumping is turned off, the conduction electron spin polarization decays away rapidly, whereas the nuclear spin polarization persists for time-scales characteristic of the nuclear longitudinal spin coherence time, on the order of minutes. This nuclear hyper-polarization, and its manipulation through an optically pumped time-dependent conduction electron spin polarization, suggests a possible general technique of ultrafast all-optical nuclear magnetic resonance in solids.

A similar spin-coherence storage effect has been obtained for core electron polarization in Mn-doped ZnSe quantum wells. Again, the optically pumped conduction electron spin polarization generates a nonequilibrium spin polarization of the paramagnetic core electron spins (3d in the case of Mn) through the core-conduction electron coupling. This core electron spin polarization persists long after the conduction electron spin polarization (and, in undoped systems, long after the conduction electron density) has decayed away. The magnetic polarization of the paramagnetic Mn spins dephases over the very long time-scales determined by spin–lattice relaxation, and thus is an interesting avenue towards information storage.

The above systems are not ferromagnetic – the spin systems involved in the process are paramagnetic spin systems coupled to the conduction electrons, which are 'super-polarized' through the conduction electron spin polarization. An alternative approach to manipulating the conduction electrons has recently been demonstrated using a thin layer of a ferromagnetic material placed on top of n-doped GaAs. Here the presence of this ferromagnetic material, even if only a few nanometers thick, leads to a remarkable enhancement of the nuclear spin polarization in the GaAs. For example in the presence of a mere 1000 G applied magnetic field, the ferromagnetic layer generates an effective field on the electrons from the nuclei of up to 9000 G. This effective field also depends on the orientation of the magnetism in the ferromagnetic layer. This intriguing effect has yet to be fully explored, but may yield a new type of magnetic 'gate' on the mobile electrons in a semiconductor without a direct form of electrical spin injection.

The Future of Semiconductor Spintronic Devices

Semiconductor charge-based electronics (e.g., transistors and integrated circuit chips) and magnetoelectronics (e.g., hard disk read heads) are two of the most successful electronic technologies of the twentieth century. A union of elements of these two technologies is anticipated in the area of semiconductor spintronics. Immediate approaches involve placing hybrid magnetic elements within known semiconductor devices. Semiconductor spintronic devices, however, are unlikely to compete with the most successful devices from each of these two areas – the semiconductor transistor is an extremely effective and efficient device, as is the magnetoelectronic hard disk read head. As has occurred with many other new technologies perhaps the most important applications of semiconductor spintronics have not even been envisaged yet.

Despite this, one significant application without a dominant technology suggests itself – that of quantum computation. Recent advances in the theoretical understanding of quantum information technology, including novel algorithms, error-correcting codes, and plausible scalable device architectures, suggest that calculations involving quantum mechanical coherent states are possible. Here the extremely long spin coherence times in semiconductor systems, and the demonstrated ability to manipulate that coherence on ultrafast optical times, indicate that spins in semiconductors (whether electron or nuclear) may constitute a good basis for a physical realization of a quantum computer.

See also

Quantum Optics: Quantum Computing with Atoms. **Semiconductor Physics:** Outline of Basic Electronic Properties.

Further Reading

Abragam A (1961) *Principles of Nuclear Magnetism*. Oxford, UK: Oxford University Press.

Awschalom DD and Kikkawa JM (1999) Electron spin and optical coherence in semiconductors. *Physics Today* 52: 33–38.

Awschalom DD, Samarth N and Loss D (eds) (2002) *Semiconductor Spintronics and Quantum Computation*. New York: Springer.

Ivchenko EL and Pikus GE (1997) *Superlattices and Other Heterostructures*, 2nd edn. New York: Springer.

Jeffries CD (1963) *Dynamic Nuclear Orientation*. New York: Wiley.

Meier F and Zachachrenya BP (eds) (1984) *Optical Orientation*. Amsterdam, The Netherlands: North-Holland.

Slichter CP (1992) *Principles of Magnetic Resonance*, 3rd edn. New York: Springer.

Wolf SA, Awschalom DD, Buhrman RA, *et al.* (2001) Spintronics: a spin-based electronics vision for the future. *Science* 294: 1488–1495.

Yafet Y (1963) g factors and spin-lattice relaxation of conduction electrons. In: *Solid State Physics*, vol. 14. New York: Academic Press.

Surface Photovoltage Spectroscopy of Semiconductors

L Kronik, Weizmann Institute of Science, Rehovot, Israel

Y Shapira, Tel-Aviv University, Tel-Aviv, Israel

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Surface photovoltage spectroscopy (SPS) is a well-established contactless technique for semiconductor characterization, which relies on analyzing illumination-induced changes in the surface voltage. SPS traces its origins to the pioneering work of Brattain and Bardeen in the early 1950s, and was extended into a powerful spectroscopic tool by Gatos, Lagowski and Balestra in the early 1970s. It has been used as an extensive source of surface and bulk information on various semiconductors and semiconductor interfaces. In the following, we present the basic theory behind SPS, its experimental setup, and a range of its applications.

Principles of Operation

In general, a surface is defined as a boundary of media with different physical properties. The periodic structure of an ideal crystalline semiconductor results in the appearance of allowed energy bands separated by forbidden energy gaps. In particular, semiconductors are characterized by a nearly full 'valence band', separated by a forbidden bandgap from a higher lying, nearly empty 'conduction band.' Electron transport takes place within the latter and hole transport takes place within the former. The mere termination of this periodic structure at the surface, as well as the chemical changes in the surface associated with this termination, allow for the formation of surface-localized electronic states within the semiconductor bandgap. Electrons or holes in these local states are referred to as 'trapped carriers', as opposed to the 'free carriers' in the conduction and valence bands.

The appearance of surface-localized states induces charge transfer between bulk and surface in order to establish thermal equilibrium between the two. The free carrier density in the vicinity of the surface therefore deviates from its equilibrium value in the bulk. This results in a surface space charge region (SCR), which is electrically non-neutral, implying a nonzero electric field in it and therefore a potential drop across it. Thus, even under equilibrium conditions the surface potential, V_s, is different from the electric potential far away in the bulk. As a specific example which illustrates these concepts, consider an n-type semiconductor with a depleted surface. The majority carriers are electrons and some of them have been trapped in surface states, such that their concentration in the vicinity of the surface is smaller than its equilibrium value but larger than that of the holes (see Figure 1a). The potential drop across the SCR is manifested by the bending of the semiconductor bands, which is such that electrons are repelled from the surface and holes are attracted to it, due to the trapped surface electrons. We note that, by definition, the energy band edge is lower the higher the electrical potential, so that a positive V_s corresponds to downward-bent bands.

Generally, the photovoltaic effect comprises an illumination-induced change in the equilibrium potential distribution and is typically the result of some charge transfer and/or redistribution within the device due to the incident illumination. This is the basic principle behind devices ranging from photodiode detectors to photovoltaic solar panels. A specific variant of the photovoltaic effect is the *surface* photovoltaic effect, which is at the center of this text. It is important to note that the formation of a surface photovoltage (SPV) occurs only if carrier photogeneration *per se* is followed by net charge redistribution. Usually, no significant driving force for such redistribution is found beyond the SCR and the underlying bulk remains quasineutral. Thus, we are interested primarily in the surface SCR.

The SPV mechanism depends strongly on whether the incident photon energy is larger or smaller than the semiconductor bandgap (denoted below as the super-bandgap and sub-bandgap, respectively). Dominant SPV mechanisms are demonstrated below for a depleted n-type surface. The dominant mechanism by which super-bandgap illumination results in surface photovoltage generation is shown in Figure 1b. The electric field in the SCR causes excess electrons to be swept away from the surface and excess holes to be swept towards it. This serves to reduce the density of surface-trapped electrons and decreases the band-bending. In a second mechanism, shown in Figure 1c, either electrons or holes are preferentially trapped at surface defects. This effectively charges the surface and thus modifies the



Figure 1 Schematic band diagrams of the surface space charge region at a depleted n-type semiconductor surface under different conditions: (a) thermal equilibrium; (b) super-bandgap illumination with carrier separation under an electric field; (c) super-bandgap illumination with preferential trapping of: (i) electrons, (ii) holes; (d) sub-bandgap illumination with excitation of trapped: (i) electrons, (ii) holes. In all diagrams, solid and dashed lines indicate band positions in the dark and under illumination, respectively. Straight arrows denote carrier generation and curved arrows denote carrier trapping. Adapted from Gal D, Mastai Y, Hodes G and Kronik L (1999) Bandgap determination of semiconductor powders via surface photovoltage spectroscopy. *Journal of Applied Physics* 86: 5573. Reproduced by permission of the American Institute of Physics.

surface potential. This second mechanism is usually apparent in bulk samples only if the equilibrium surface band-bending is fairly small, but increases in importance in polycrystalline materials with decreasing crystallite size, because of the increasing surface to volume ratio.

The most common mechanism for sub-bandgap SPV involves the direct modification of the surface charge, and hence potential, by excitation of trapped carriers, as shown in Figure 1d. Illumination by photons with energy $h\nu > E_c - E_t$ may produce electron transitions from a surface state at an energy E_t into the conduction band, where they are quickly swept to the semiconductor bulk by means of the surface electric field. Hence, the negative surface charge is reduced and the band-bending decreases. Conversely, illumination by photons with energy $h\nu > E_t - E_v$ may produce electron transitions from the valence band into a surface state situated at an energy E_t above the valence band maximum, E_v (which are equivalent to hole transitions from the surface state to the valence band). Such transitions increase the surface negative charge and therefore the surface band-bending. For a SPV to develop in this case, it is necessary to have a significant diffusion of the excess holes into the bulk and/or a significant recombination of electrons and holes inside the SCR, as there is no field-assisted driving force of holes into the bulk.

A typical SPV spectrum shows the SPV as a function of incident photon energy. Its most important features – the ones to watch for when attempting to interpret an SPV spectrum – are the sharp slope changes ('knees') associated with an abrupt onset of an additional carrier excitation mechanism. Consider, as an illustrative example, the top SPV curve in the right-hand part of Figure 2 (the rest of the figure is discussed below). In this curve, two 'knees' are shown. The first 'knee' (marked by an arrow) occurs at sub-bandgap photon energies and corresponds to the onset of carrier excitation from surface states (as in Figure 1d). The second 'knee' occurs in the vicinity of the bandgap energy and corresponds to the onset of band-to-band carrier excitation (as in Figure 1b,c). The proper interpretation of the energy position of these 'knees', their sign (negative or positive SPV change), and the relation of both to the SPV mechanism at work, is elaborated below in the 'Applications' sections.

So far, our discussion has been devoted solely to a study of semi-infinite, uniform bulk samples. However, actual semiconductor samples may be thin, i.e., not much larger than the diffusion length and/or the absorption length, so that excess carriers may be present near their back part as well. Many optically and electronically interesting structures (advanced detectors, transistors, lasers) consist of a multilayer structure, which has several buried interfaces.

Any change in the potential drop across a buried surface will also be measurable at the front surface, because potential drops are additive. For example, the photo-induced potential drop across a photodiode is measured at its contacts, which can be many microns away from its active region. Thus, the sensitivity of SPV measurements to a certain region in the semiconductor is limited only by the



Figure 2 SPV spectra of: (a) an n-type GaAs(110) surface, UHV cleaved (top curve) and with an Al overlayer (bottom curve); (b) a p-type InP(110) surface, UHV cleaved (top curve) and with an Au overlayer (bottom curve). Arrows denote the onset of optically induced transitions and labels denote the corresponding defect level. Adapted from Burstein L, Bregman J and Shapira Y (1991) Characterization of interface states at III–V compound semiconductor–metal interfaces. *Journal of Applied Physics* 69: 2312. Reproduced by permission of the American Institute of Physics.

absorption length of the photons, i.e., by the possibility of introducing an excess of free carriers in the region of interest.

Experimental Details

SPV measurements are nontrivial because the surface potential is a *built-in* potential, rather than an external potential. In other words, the surface potential is not equal to the difference in Fermi levels between the front and back surfaces. Therefore, it cannot be simply measured using some form of voltmeter. Moreover, in the case of a free surface, the application of any contact to indirect electrical measurements of the built-in voltage (e.g., current–voltage or capacitance–voltage analyses) will invariably alter the surface properties and hence the quantity under measurement. Consequently, most of the prevalent techniques for measuring the surface potential (or at least changes of it upon illumination) are based on capacitive coupling schemes that do not require a direct electrical contact.

The two most commonly used methods rely on bringing a metallic probe close to the free surface, but never touching it, thus forming a parallel-plate capacitor. An alternating current, from which surface potential changes can be calculated, is then excited by (a) vibrating the metallic probe, which results in alternating capacitance, or (b) using 'chopped' illumination. The two approaches are known as the Kelvin probe and the ac-SPV schemes, respectively. In principle, they provide similar information, but their somewhat different physical principles result in several relative strengths and weaknesses, which make the method of choice application-dependent. In a nutshell, the Kelvin probe is more suitable for following phenomena with large time constants (in particular surface states with long relaxation times) and does not perturb the true band-bending of the free surface. The ac-SPV technique is more suitable for following fast relaxation phenomena, allows for a systematic modification of the surface band-bending in the dark as an extra degree of freedom, and does not require an ohmic back-contact.

Both Kelvin probe and ac-SPV measurements may also be employed in a scanning mode, which allows for recording lateral variations in the SPV, by scanning a small probe or a well-focused light beam, respectively, across the surface. Both approaches are typically limited to a lateral resolution roughly of the order of ~1 μm. SPV measurements can also be performed by a limited modification of two high-resolution techniques for topographic mapping of surfaces that have emerged in the 1980s: scanning tunneling microscopy (STM) and atomic force microscopy (AFM). This opens new horizons for SPV mapping with a resolution on the nanometer scale or even the atomic scale.

A schematic view of a complete, generic SPS setup is given in Figure 3. The sample under study is typically placed inside a metallic box, which serves as both a dark box and a Faraday cage. This box must be such that it effectively includes the probe.

Clearly, for spectroscopic purposes one needs to generate the SPV signal using a broadly tunable light source. The default choice would therefore be the use of a 'white-light' source in conjunction with a monochromator. Because the typical super-bandgap absorption coefficient is typically orders of magnitude larger than the sub-bandgap coefficient, SPS is vulnerable to the spurious contribution of high-order diffraction peaks and stray light. Use of a monochromator where these effects are as small as possible is therefore highly recommended. For some applications, use of an auxiliary light source (e.g., white light, laser light, ultraviolet light, etc.) allows for a 'photobias' of the system and/or for additional quantitative analysis.

The actual recording of an SPV spectrum is coordinated by a real-time computer program. This program controls the monochromator motor and thus wavelength changes, operates the control electronics of the probe, reads the measurement results by interfacing with the probe read-out electronics via an analog-to-digital converter, and finally stores the obtained spectrum for subsequent display and analysis.



Figure 3 Schematic block diagram of a generic SPS setup. Adapted from Kronik L and Shapira Y (2001) Surface photovoltage spectroscopy of semiconductor structures: at the cross-roads of physics, chemistry and electrical engineering. *Surface and Interface Analysis* 21: 954. New York: John Wiley and Sons, Inc.

Applications I: Uniform Semiconductors

An elementary application of SPS is the approximate determination of the semiconductor bandgap. This determination is based on the large increase in absorption coefficient near the bandgap energy, E_g, found in most semiconductors. This increase brings about a significant change of the SPV signal, which is easily identified as a sharp change in slope of the SPV curve and is often the most significant one in a given spectrum. An example is shown in Figure 2, where the slope changes related to the bandgaps of GaAs and InP are clearly identified. Indeed, the bandgaps of most known semiconductors have been analyzed using this approach.

The use of SPS for extraction of E_g is at heart nothing more than an emulation of an absorption spectrum. However, as opposed to, e.g., transmission spectroscopy, SPS does not require light collection. It can therefore be performed on arbitrarily thick samples (or on layers sandwiched within a heterostructure – see below) and does not require the sample to be removed from the substrate or grown on a transparent one. It is also inherently insensitive to reflection and scattering and is thus eminently useful for micro- and nanocrystallites.

One must bear in mind that the value of E_g obtained from an SPS plot by inspection is only approximate. Indeed, detailed experimental comparisons between SPV and absorption spectra reveal that the two are often similar, but never identical. Thus, the nominal bandgap is nearly always found within the onset of the largest SPV signal, but is usually relatively broad, the exact position of E_g within it is by no means obvious, and the error in E_g is often ~0.1 eV. However, it has been shown that this error can be reduced significantly – often by one to two orders of magnitude – by a careful quantitative analysis of the experimental data.

We now turn our attention to determining the type (p or n) of the semiconductor. This may be achieved with the help of the sign of the knee associated with the onset of the super-bandgap SPV. Most semiconductor surfaces are depleted, which means that the bands of p-type semiconductors are bent downwards towards the surface, whereas the bands of n-type semiconductors are bent upwards. Since super-bandgap illumination typically tends to decrease the surface band-bending, this would result in a positive SPV in n-type semiconductors and a negative SPV in p-type semiconductors. For example, the SPV spectra of n-type GaAs and p-type InP, shown in Figure 2, clearly feature opposite onset signs which obey the above rules.

While in many cases the type of the semiconductor is known a priori, this is not always the case and SPS can become very useful in determining the semiconductor type. For example, SPS was used for fast and nondestructive verification of the semiconductor type in GaN films, where the p-doping is known to be nontrivial and subject to compensation by its native n-type doping.

We note that under conditions where the SPV is dominated by trapping of carriers, as shown in Figure 1c, the sign convention described above clearly does not apply. For example, etched CdSe quantum dot films were found to exhibit a p-type response in a humid ambient and an n-type response in a dry ambient, on account of preferential trapping of holes or electrons in a dry or humid ambient, respectively.

A key strength of SPS is in the determination of the energy position and type of surface states. Because photons of sufficient energy may excite charge carriers from a surface state to a band or vice versa, we expect a knee in the SPV spectrum whenever the photon energy exceeds the threshold energy of a certain transition. If the latter involves excitation of electrons from the surface state to the conduction band (Figure 1d(i)),a positive change in the surface charge is induced, and hence a positive SPV is expected. Conversely, excitation of holes to the valence band (Figure 1d(ii)) makes the surface charge more negative and a negative SPV is expected. Thus, the combination of the SPV threshold energy and slope sign makes the determination of the approximate position of the surface state within the bandgap possible.

As an illustrative example, consider how SPS can be used to monitor metal-induced surface states, as shown in Figure 2. After cleaving in ultrahigh vacuum, neither GaAs nor InP surfaces display any knees associated with deep surface states, as expected for these surfaces. However, upon deposition of a very thin metallic overlayer, distinct sub-bandgap knees emerge. These knees, associated with positive and negative SPV changes at the Al/GaAs and Au/InP interfaces, respectively, indicate the formation of surface states situated ~0.8 eV below the conduction band edge and ~0.92 eV above the valence band edge, respectively.

Because SPS is contactless and nondestructive, it can be applied not only to clean surfaces, but also to real ones, in practically any ambient. This makes SPS highly suitable for a direct correlation of surface electronic structure with chemical treatments. One such area of active research is the study of surface passivation treatments. An illustrative example, in which the passivating effects of various liquids on a specific p-InP surface (denoted as (100)) was studied *in situ*, is shown in Figure 4. The negative SPV change at ~1.3 eV found in all spectra shown is clearly due to the onset of band-to-band transitions in the InP sample, with its sign indicating a p-type sample, as appropriate. The SPV spectrum of the water-exposed sample (which is similar to that obtained in air (not shown)) features two surface states: the negative SPV slope change, at ~1 eV, is due to a photo-induced population of a surface state situated ~1 eV above the valence band edge. The positive SPV slope change at ~1.2 eV is due to a photo-induced depopulation of a surface state situated ~1.2 eV below the conduction band edge. Interestingly, exposure to HF eliminates the latter state, but not the former. The opposite is true for exposure to H_2O_2. Finally, exposure to a Na_2S solution results in removal of both surface states, in agreement with the known passivating action of this solution. This is just one example of many illustrating the strength of SPS for revealing the link between chemical/physical treatments and device-affecting electronic properties, already at the material level.



Figure 4 SPV spectra of the p-InP(100) surface in air and after successive immersion in (from top to bottom in the lower energy part): A – 18 MΩ H_2O; B – 0.4% HF; C – 30% H_2O_2; D – a 1.3 M Na_2S solution. Arrows denote the onset of optically induced transitions and labels denote the corresponding defect level. Adapted from Bastide S, Gal D, Cahen D and Kronik L (1999) Surface photovoltage measurements in liquids. *Review of Scientific Instruments* 70: 4032. Reproduced by permission of the American Institute of Physics.

While we have so far considered only surface states, SPS is sensitive to bulk states too, as long as charge excited from or trapped in them can be separated (typically under the electric field of a space charge region). Accordingly, SPS has been used for studying, e.g., Cr-related defects in GaAs or Fe-related defects in InP. The simplest distinction between surface and bulk states in SPS is obtained by examining whether the pertinent spectral feature disappears after surface (e.g., etching) or bulk (e.g., doping) treatment, respectively.

We note that in recent years, SPS has also been applied successfully along the lines outlined here for the study of bandgaps, doping type, and surface and bulk defects in the emerging field of organic semiconductors and organic treatments of semiconductors, as well as for nanostructures, such as fullerenes and nanotubes.

Additional, quantitative analyses of the SPV spectra allow for a determination of densities, thermal and optical transition rates, and the spatial site of gap states. Such analyses are usually based on the SPV response to a systematic modification of one or more external parameters, e.g., time (for transient responses), illumination intensity, temperature, etc.

Applications II: Multilayer Structures

Beyond the study of surface properties, the application of SPS to heterojunctions, multilayer structures, and actual device structures has been most rewarding in recent years. The SPS of multilayer structures is illustrated by Figure 5. This figure features the SPV spectra of a ZnO:Al/ZnO/CdS/Cu(In,Ga)Se_2 layered structure, used for the fabrication of thin-film solar cells. Distinct spectral knees at ~1 eV, ~2.4 eV, and ~3.1 eV, corresponding to the bandgaps of Cu(In,Ga)Se_2, CdS, and ZnO, respectively, are clearly observed. The unequivocal identification of all three bandgaps confirms the above-mentioned theoretical prediction of SPS sensitivity to buried interfaces. Interestingly, the magnitude of the SPV signal is seen to increase with increasing annealing time (in air, at 200 °C), in agreement with the increase in overall solar cell efficiency with such annealing.



Figure 5 SPV spectra of ZnO:Al/ZnO/CdS/CIGS structures for various annealing times, in air, at 200 °C. Adapted from Gal D, Beier J, Moons E, *et al.* (1995) Band diagram and band line-up of the polycrystalline Cds/Cu(In,Ga)se_2 heterojunction and its response to air annealing. *AIP Conference Proceedings* 353: 453. Reproduced by permission of the American Institute of Physics.

Another feature of growing importance in SPS is that it allows for the characterization of quantum wells and other low-dimensional heterostructures. An illustrative example of the SPS of a multiple-quantum-well (MQW) GaAs/AlGaAs structure is shown in Figure 6a. The spectral knees at ~1.4 eV and 1.78 eV correspond to the onset of band-to-band absorption in the GaAs epilayer and the AlGaAs cap layer, respectively. In between these two knees, the shape of the SPV spectrum resembles typical absorption spectra of MQW structures and the observed MQW-related maxima agree well with calculated energy values of the hole level-electron level transitions denoted as 1HH-1E and 2HH-2E transitions. Note that before etching, a nonnegligible sub-bandgap SPV signal was apparent at photon energies below 1.38 eV, indicating the presence of optically active gap states. Since no such signal was observed after etching, these states were located at the external AlGaAs surface and were not associated with the MQW region. Moreover, the SPV spectrum in the MQW absorption energy range has not changed at all (other than undergoing a uniform shift) after etching, showing that the signal SPV in the MQW absorption range is not interfered by surface effects. Thus, all allowed hole–electron transitions have been resolved, at room temperature.

As SPV analyses of multilayer structures offer the possibility of performing contactless and nondestructive electrical and optical characterization of buried interfaces, they have found significant uses in the field of process monitoring and quality control of actual device structures. This is because the possibility of assessing the quality of a layered structure before any actual device processing takes place presents an opportunity for significant savings in time and money. Recent applications include the identification of defective batches and prediction of ultimate performance of solar cells and x-ray detectors, the prediction of energy levels and lasing wavelength in modern laser heterostructures, the assessment of bandgap narrowing and ultimate gain of heterojunction bipolar transistors, and the



Figure 6 (a) SPV spectra of a GaAs/AlGaAs MQW sample before (solid curve) and after (dashed curve) etching. Adapted from Bachrach-Ashkenasy N, Kronik L, Shapira Y, *et al.* (1996). Surface photovoltage spectroscopy of quantum welts and superlattices. *Applied Physics Letters* 68: 879. Reproduced by permission of the American Institute of Physics. (b) Room temperature experimental SPV spectra (i) and calculated photo-excited carrier spectra (ii) of an InGaAs/GaAs/AlGaAs vertical-cavity surface-emitting laser structure. Adapted from Huang YS, Malikova L, Pollak FH, *et al.* (2000). Surface photovoltage spectroscopy, photoreflectance, and reflectivity characterization of an InGaAs/GaAs/GaAlAs vertical-cavity surface-emitting laser including temperature dependence. *Applied Physics Letters* 77: 37. Reproduced by permission of the American Institute of Physics.

characterization of the electronic structure of high electron mobility transistors and vertical cavity surface emitting lasers.

As an example of such studies, consider the recent characterization of an In-GaAs/GaAs/AlGaAs vertical-cavity surface-emitting laser, shown in Figure 6b. It is readily observed that SPS resolves both the gain providing 1C-1H transition and the lasing-wavelength-related cavity mode, as well as a rich oscillatory structure above ~1.37 eV due to interference effects from the distributed Bragg reflector stacks. The measured SPV spectrum is also in very good agreement with the calculated dependence of the photo-excited carrier density on photon energy, also shown in Figure 6b. In fact, SPS is the first contact-less technique to resolve all of these features in one measurement, and it also allows for a temperature-resolved determination of these quantities.

Summary

SPS features a theory that is relatively straightforward (at least at the qualitative level), and offers typical experimental setups that make the method contactless, nondestructive, ambient insensitive, and capable of any lateral resolution. It can provide a detailed picture of the electronic structure at surfaces, interfaces, heterojunctions, and even complicated multilayer structures. The wide range of SPS applicability also makes it easy to compare and link changes in electronic structure to changes in chemical/physical properties on the one hand, and electrical/optical device properties and performance on the other.

See also

Semiconductor Materials: Modulation Spectroscopy of Semiconductors and Semiconductor Microstructures. **Semiconductor Physics:** Band Structure and Optical Properties; Impurities and Defects; Outline of Basic Electronic Properties; Quantum Wells and GaAs-Based Structures.

Further Reading

Brattain WH and Bardeen J (1953) Surface properties of germanium. *Bell System Technical Journal* 32: 1–41.

Brillson LJ (1982) The structure and properties of metal–semiconductor interfaces. *Surface Science Reports* 2: 123–326.

Gatos HC and Lagowski J (1973) Surface photovoltage spectroscopy – a new approach to the study of high-gap

semiconductor surfaces. *Journal of Vacuum Science and Technology* 10: 130–135.
Kronik L and Shapira Y (1999) Surface photovoltage phenomena: theory, experiment, and applications. *Surface Science Reports* 37: 1–206.
Kronik L and Shapira Y (2001) Surface photovoltage spectroscopy of semiconductor structures: at the crossroads of physics, chemistry and electrical engineering. *Surface and Interface Analysis (special issue on Optical Techniques)* 21: 954–965 (main source for the present text).
Lüth H (1993) *Surfaces and Interfaces of Solids*, 2nd edn. Berlin: Springer-Verlag.
Many A, Goldstein Y and Grover NB (1971) *Semiconductor Surfaces*, 2nd edn. Amsterdam, The Netherlands: North-Holland.
Pollak FH (2000) Modulated electric fields produce semiconductor spectra. *Laser Focus World* 36: S9.

SOLITONS

Contents

Bright Spatial Solitons
Optical Fiber Solitons, Physical Origin and Properties
Soliton Communication Systems
Temporal Solitons

Bright Spatial Solitons

C Conti and G Assanto, University ‘Roma Tre’, Rome, Italy

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical spatial solitons, once considered an exotic and rather abstract concept belonging to the realm of mathematics or mathematical physics, nowadays are pursued both experimentally and theoretically in terms of their rich dynamics and variegated features, with important perspectives in applications to signal processing and switching, routing, filtering and – generally – light-by-light controlling. In an intuitive description of a bright spatial soliton, a self-focusing response balances natural diffraction of a light beam, allowing for its invariant propagation in transverse size and intensity. Spatial solitons can be regarded as the stationary or time-independent self-guided ‘eigenwaves’ of Maxwell equations in a material system with a nonlinear optical response. Basically, ‘bright’ spatial solitons (we will not address ‘dark’ cases here, i.e., a dip on an illuminated background) bear the same relationship to nonlinear optics in space as temporal, or fiber, solitons do in time. While both temporal and spatial solitons are special cases of light localization in the $(3+1)$ dimensions (light bullets) encompassing time and two transverse coordinates in space in addition to propagation; the spatial case requires particular attention compared to the fiber inasmuch as, in general, two transverse coordinates (2D) complement the direction of propagation. In other words, the scenario is potentially one-dimension richer than for ‘standard’ temporal solitons, where light confinement, i.e., the effect of the nonlinearity, takes place along a single coordinate. In this respect, the latter case finds a direct counterpart with spatial solitons in planar waveguides, i.e., $(1+1)$D solitons, where light confinement occurs linearly in one spatial dimension, providing group-velocity dispersion in time is replaced by beam diffraction in space, respectively.

When both transverse dimensions are involved, i.e. when a light beam propagates in bulk, in the simplest case of Kerr self-focusing, the nonlinearity can become overcritical and cause filamentation and catastrophic collapse. Additional mechanisms (such as saturation, nonlocality, or higher-order effects) or inherently different nonlinear responses (parametric or molecular), need therefore to be involved in the description of spatial solitons. In several instances, the mathematics differs from the nonlinear Schrödinger equation originally invoked to define a 1D bright optical soliton, leading to nonintegrable systems and to a wider class of solutions, called solitary waves. Since solitary waves constitute the vast majority of the observed spatial light-localization phenomena, we will refer to spatial solitons even in those cases when their model is nonintegrable, defining them as non-diffracting beams in a self-focusing material. While retaining the distinction between 1D and 2D cases, in the following sections we will discuss bright spatial solitons and their features, grouping them on the basis of the underlying nonlinear mechanism and corresponding model, trying to provide a direct link with experimental observations. In doing so, we will leave out discussions on dark solitons and modulationally unstable phenomena, as well as more involved subjects ranging from higher-order to vector, vortex, photonic-crystal, and incoherent spatial solitons.

The General Model of Bright Spatial Solitons

Assuming the paraxial approximation to be valid, the general structure of the evolution equations which lead to spatial solitons propagating along z takes the so-called Foch–Leontovich form:

$$2\mathrm{i}k\frac{\partial A}{\partial z} + \nabla_\perp^2 A = -2k^2\frac{\Delta n}{n_0}A \qquad [1]$$

where A is the complex amplitude of the linearly polarized electric field, $k = \omega/c = 2\pi n_0/\lambda$, with λ the wavelength, $\omega = 2\pi\nu$ the pulsation, n_0 the bulk refractive index, and $\Delta n(\mathbf{r})$ the index change induced by the nonlinear effect. In anisotropic materials, both n_0 and Δn may depend on the polarization of the envelope A. The latter is normalized such that the optical intensity is $I = |A|^2$. Hence the whole optical field is

$$E_{\mathrm{opt}} = \mathrm{Re}\left[\sqrt{\frac{2Z_0}{n_0}}A\mathrm{e}^{-\mathrm{i}\omega t+\mathrm{i}kz}\right] \qquad [2]$$

with Z_0 being the vacuum impedance.

Hereafter we will neglect material losses and assume $\Delta n(\mathbf{r})$ to be real-valued. In the simplest case it is a function of the field intensity I calculated in $\mathbf{r}$. Typical models are the Kerr medium with $\Delta n = n_2 I$, or the saturable Kerr with $\Delta n = n_2 I/(1 + I/I_s)$ and I_s a saturation value; they are particular cases of local nonlinear media defined by a relation of the type $F[\Delta n(\mathbf{r}), I(\mathbf{r})] = 0$, with F a 'well-behaved' function.

There is also the possibility that the refractive index modification depends on the electromagnetic perturbation (e.g. the intensity) in a finite region, as happens with nonlocal solitons. In the latter case, F needs to be substituted by an integro-differential system of equations, i.e., it represents a functional between $\Delta n(\mathbf{r})$ and $I(\mathbf{r})$.

Relevant exceptions to eqn [1] are spatial solitons due to a quadratic nonlinearity, where a system of two coupled equations must be taken into consideration, and a description in terms of a refractive index change only holds in an approximate, and by no means physical, sense. Quadratic solitons will be discussed later. Here, instead of embarking into a general classification, we will describe the relationships to some representative cases. In this simple framework, spatial solitons are defined as solutions of the type $A = a\exp(\mathrm{i}\beta z)$, with a real-valued and satisfying the equation:

$$\frac{1}{2k^2}\nabla_\perp^2 a + \frac{\Delta n(I)}{n_0}a = \frac{\beta}{k}a \qquad [3]$$

Equation [3] is the z-independent counterpart of eqn [1]. It has the form of the stationary Schrödinger equation (with a field-dependent Hamiltonian operator), where the kinetic energy and the potential are given by the diffraction term and by the nonlinear correction to the refractive index, respectively. Its solutions correspond to solutions of eqn [1] due to the balance between diffraction and nonlinearity. β is the nonlinear correction to the dispersion relation $k = n_0\omega/c$, i.e., it yields the resulting longitudinal wavevector $K = k + \beta$. Solitary solutions are often classified in terms of their dimensionality. Solutions of eqn [3], which depend on either 1 or 2 transverse coordinates, define 1D or 2D solitons, respectively. 1D solitons refer to situations in which a bulk nonlinear medium is illuminated with a highly elliptic beam (such that the diffraction along a transversal dimension, denoted by y, is negligible), or a planar waveguide is excited with a linear mode fixing the transverse profile in one of the dimensions (denoted by y). The nonlinear dynamics and the corresponding steady-state solutions are then described by eqns [1] and [3], with $\partial_y = 0$.

Spatial Solitons in Kerr Media

1D Kerr Spatial Solitons and the Nonlinear Schrödinger Equation

The simplest example of a spatial soliton is an optical beam diffracting in one transverse dimension in the presence of the so-called Kerr effect, i.e., a refractive index that increases linearly with the local intensity I:

$$n = n_0 + n_2 I \qquad [4]$$

where $n_2(>0)$ is measured in $\mathrm{m}^2\,\mathrm{W}^{-1}$ and has typical values of 10^{-20} for silica and 10^{-17} for semiconductors at photon energies below half-bandgap, i.e., leaving aside two photon absorption and higher-order effects. For 1D Kerr spatial solitons, eqn [1] becomes

$$2ik\frac{\partial A}{\partial z} + \frac{\partial^2 A}{\partial x^2} = -2k^2\frac{n_2}{n_0}|A|^2 A \qquad [5]$$

Equation [5] is known as the nonlinear Schrödinger equation (NLS), and is the basic model in describing temporal soliton, i.e., nondispersing pulses propagating in optical fibers, provided the variable x is intended as the temporal coordinate. The importance of eqn [5] is due to several remarkable, in some sense unique, mathematical properties, and to the fact that it can be considered a fundamental model for diverse nonlinear phenomena. This circumstance is often referred to as the 'universality of the NLS'.

In the framework of optical spatial solitons, the NLS relevance is moderated by the fact that most experimentally explored environments involve processes significantly more complicated than the Kerr effect. Nevertheless, it settles the basic principles and constitutes a reference point in optical soliton assessment.

Trying to gain some physical insight, the starting point is the beam spreading when $n_2 = 0$ in eqn [5], i.e., the linear regime corresponding to low intensities. The diffraction is inherent to the spectrum of plane waves in a finite beam (along x). To underline the role of the nonlinear response, one can consider the NLS without the diffraction term (the second derivative with respect to x), obtaining:

$$A(x,z) = \sqrt{I(x)}\,\exp\left[ik\frac{n_2}{n_0}I(x)z\right] \qquad [6]$$

Equation [6] shows how the nonlinearity yields a phase-front curvature related to the sign of n_2: the medium is self-focusing (a converging beam) for $n_2 > 0$ or self-defocusing (a diverging beam) for $n_2 < 0$ (see **Figure 1**). In the absence of diffraction, i.e., for a plane wave, the Kerr effect modifies the field phase by increasing ($n_2 > 0$) or decreasing ($n_2 < 0$) the local refractive index (and hence the effective optical path) proportional to the intensity. For a beam of finite transverse extent, nonlinearity and diffraction act together. In a self-focusing medium, the concave phase-front due to diffraction can be balanced by the nonlinearity, and the natural tendency of a beam to spread can therefore be compensated. For this to happen, the length-scales associated to the diffraction, i.e., the Rayleigh range $L_R = kw_0^2$, and the Kerr effect must be comparable. A characteristic length $L_N = n_0/(kn_2I_0)$, over which the nonlinear phase shift equals 1, can be associated



Figure 1 Kerr spatial solitons. Top: sketch of the mechanism leading to Kerr soliton formation. In the absence of diffraction, self-focusing of a Gaussian beam provides a converging phase-front (dashed lines). Conversely, diffraction by itself causes beam divergence. When these two effects act jointly, they can balance each other and soliton generation can be observed, with a flat phase-front. (Adapted with permission from Stegeman GI, Christodoulides DN and Segev M (2000) Optical spatial solitons: historical perspectives. *IEEE Journal of Selected Topics in Quantum Electronics* 6:1419–1426). Bottom: beam propagation method used to simulate the propagation of a one-dimensional Gaussian beam by integrating the nonlinear Schrödinger equation, for (a) low-power input, (b) input high enough to generate a self-trapped solitary wave. The transverse coordinate x is expressed in units of the beam waist, the propagation coordinate z in Rayleigh lengths.

to the nonlinearity, with I_0 the peak intensity across the beam profile. When the two lengths L_R and L_N are nearly equal, i.e., $w_0^2 I_0 \approx n_0/(k^2 n_2)$, the balance between the phase-front curvatures, due to diffraction and nonlinearity, yields a self-localized nondiffracting beam. Such a situation is described by the exact solutions of eqns [1] and [3], which takes the form:

$$A(x,z)=a(x)e^{i\beta z} \quad \text{with} \quad a(x)=\sqrt{I_0}\,\mathrm{sech}\left(x\sqrt{\frac{k^2 n_2}{n_0}I_0}\right) \qquad [7]$$

and $\beta = n_2 I_0/2n_0$ is determined by the peak intensity or, equivalently, by the power P_1 carried by the soliton per unit of transverse wavefront along y:

$$P_1=\int_{-\infty}^{\infty}|A|^2\,dx=\sqrt{\frac{4n_0 I_0}{k^2 n_2}}$$

Note that the overall phase-front is flat, and the spatial extension in width yields $1/(n_2 k^2 I_0)^{1/2}$, as anticipated. The relationship between the soliton width – which determines the strength of diffraction – and the intensity – responsible for the nonlinear phase shift – is known as the existence curve, and is characteristic of the specific nonlinear mechanism.

Equation [7] is the fundamental soliton of the NLS and the paradigmatic 1D spatial soliton. Its sech shape specifically results from the type of nonlinearity; as discussed below, other effects (including parametric generation) can yield different profiles.

Figure 1 shows the simulation of a 1D Kerr soliton generated from a Gaussian input. Self-trapping is attained when the peak intensity or, equivalently, the power, reaches a threshold value depending on experimental details, the size of the nonlinear response, and the beam profile.

Figure 2 shows experimental results on the formation of a 1D Kerr soliton in a semiconductor (AlGaAs, $n_0 \approx 3.5$) waveguide. At low power (center panel) the output beam exhibits diffraction, whereas the soliton (bottom) reproduces the input beam profile (top panel) at the end facet of the sample. These results were obtained at $\lambda = 1.55$ μm, using pulsed laser beams, with temporal pulse durations of about 1 ps and peak powers of about 500 W; the generated 1D solitons had waists of tens of microns.

In a physically intuitive sense, self-trapping is due to the refractive index increase across the beam profile. Such an increase gives rise to a graded index optical waveguide able to confine all the plane wave components with angles of propagation within the numerical aperture of the input beam. Large spatial-frequency components k_x cannot be trapped and are emitted as radiation during soliton formation. It is possible to experimentally verify that this self-induced waveguide is also able to guide a weak probe uncorrelated to the soliton, provided it is above the cutoff for dielectric confinement. The use of spatial solitons for intensity-controlled or all-optical lightwave circuitry can therefore be envisaged. The first experiments on optical 1D Kerr spatial solitons date back to 1985, and were performed in carbon disulfide. Since then, 1D Kerr spatial solitons have been reported in glasses, semiconductors, and organic materials.



Figure 2 1D Kerr soliton in a planar AlGaAs waveguide. Transverse beam profiles at the input (top) and output facets of a planar waveguide in AlGaAs, at low (center) and high (bottom) power, showing diffraction and soliton formation, respectively. (Adapted with permission from Aitchison JS, Al-hemyari K, Ironside CN, Grant RS and Sibbett W (1992) Observation of spatial solitons in AlGaAs waveguides. *Electronic Letters* 28: 1879.)

Kerr Spatial Solitons in Two Transverse Dimensions: Saturable and Nonlocal Media

When the dynamics of the optical beam encompasses two transverse dimensions, the idealized discussion above no longer applies. As long as the medium is described by the simple Kerr law (eqn [4]), 2D propagation does not admit stable self-trapped stationary beams. Because of this, two alternatives are available: (i) the beam diffracts; or (ii) the beam progressively self-focuses until it undergoes catastrophic collapse: in the absence of additional limiting phenomena, such as plasma formation or nonparaxial/vectorial coupling, its waist keeps shrinking with a corresponding unbound increase in peak intensity (beam power is conserved). Which regime actually applies, depends on whether the excitation is lower or higher than a self-focusing critical power $P_c = (0.61\lambda)^2/8n_0n_2$. The latter corresponds to a diffraction-driven divergence equal to the critical angle for total internal reflection in the induced waveguide. The self-focusing instability, first predicted by Kelly in 1965, is related to the so-called Derrick's theorem: particularly related to spatial solitons in a positive ($n_2 > 0$) Kerr medium, it states that the equilibrium between diffraction and nonlinearity in 2D is unstable.

The situation is markedly different when saturation is present: self-focusing arrests at the maximum value of the nonlinear refractive index increase, and stable self-trapped beams are allowed. The simplest model for a saturating nonlinearity yields the following stationary-state equation:

$$\frac{1}{2k^2}\nabla_\perp^2 a + \frac{n_2}{n_0}\frac{I}{1+I/I_s}a = \frac{\beta}{k}a \qquad [8]$$

Its solutions, while retaining a bell-shaped profile, depart from the purely Kerr model corresponding to $I_s \to \infty$, and can only be obtained numerically.

Gases, and specifically sodium vapors, were the first media in which spatial solitons of a saturable Kerr-like nonlinearity were observed in 1974. Historically, these were the first 2D optical spatial solitons.

Most recent developments on optical spatial solitons involve more complicated environments and nonlinear responses. In the next sections we will consider those most investigated experimentally: photorefractive solitons, nonlocal solitons in liquid crystals and parametric solitons.

Spatial Solitons in Photorefractive Media

In recent years, research on spatial optical solitons in photorefractives has been among the most active. Self-trapping in photorefractive materials was first predicted in 1992 and observed in 1993. However, a clear assessment of this result came with the demonstration of the so-called steady-state screening photorefractive solitons in 1994.

The principle underlying the photorefractive response can be described as a feedback mechanism relating to the optical induction of a static electric field **E**. In specific materials, such as semiconductors or ferroelectrics, a light beam generates free charges which diffuse and drift under an externally applied voltage. Owing to free carriers and donor/acceptor sites, the resulting net spatial charge produces a static electric field which, in turn, modifies the refractive index n_0 via the electro-optic effect, phenomenologically described by

$$\Delta n_{ij} = -\frac{1}{2}n_0^3 r_{ijk}E_k - \frac{1}{2}n_0^3\varepsilon_0^2(\varepsilon_r - 1)^2 g_{ijkl}E_kE_l \qquad [9]$$

Equation [9] is a series expansion of the index change in powers of the static electric field: all terms are present if the medium is noncentrosymmetric, otherwise only even-powered terms need be included. In essence, eqn [9] entails the feedback mediated by the static electric field on the optical wave.

The feedback leads to stable solutions under appropriate conditions. These are steady-state solitons if the inhomogeneous light-induced index change makes a suitable waveguide for the beam. The three main types of such self-localized beams are screening, photovoltaic, and centrosymmetric photorefractive solitons. Boundary conditions determine the induced static field to be inserted in eqn [9] and in the propagation eqn [1]. In the simplest cases we consider, the light-wave is linearly polarized and the tensorial nature of the index perturbation in eqn [9] can be neglected.

The equations encompassing most of the physics of the photorefractive effect constitute the Kukhtarev model and can be shown as:

$$\begin{aligned} &s(I + I_b + I_{dark})(N_d - N_d^i) - \gamma_r\rho N_d^i = 0 \\ &\nabla\cdot\mathbf{J} = \nabla\cdot[q\mu\rho\mathbf{E} + k_BT\mu\nabla\rho + \beta_{ph}(N_d - N_d^i)I\mathbf{c}_{opt}] = 0 \\ &\nabla\cdot\mathbf{E} + \frac{q}{\varepsilon_S}(\rho + N_A - N_d^i) = 0 \end{aligned} \qquad [10]$$

The relevant quantities in eqns [10] are: the current density **J**; the free charges (electrons) density ρ; the density of ionized (total) donors N_d^i (N_d), the density of negatively charged sites N_A, the photo-ionization cross-section s, the background density I_b (due to background laser light), the dark irradiance I_{dark} (sI_{dark} is the dark generation rate, typically $I_b \gg I_{dark}$), the recombination rate γ_r, the electron mobility μ, the low frequency dielectric constant $\varepsilon_S = \varepsilon_0\varepsilon_r$, the Boltzmann constant k_B, the versor $\mathbf{c}_{opt}$ of the optic axis, and the temperature T. In the second of eqn [10], the pertinent element β_{ph} of the photovoltaic tensor needs be taken into account only for the photovoltaic solitons described below. The above must be completed by boundary conditions for the bias V – the line integral of

E – and the geometry of the metal contacts. Typically, $N_\mathrm{d} \approx 10^{18}\ \mathrm{cm}^{-3} \gg N_\mathrm{a}$, $I_\mathrm{dark} \approx 10^{-3}–10^{-6}\ \mathrm{W/cm}^2$, $I_\mathrm{b} \approx 10\ \mathrm{W/cm}^2$, $\varepsilon_\mathrm{r} \approx 10^3$ and solitons are observed in the visible.

Equations [10] determine the field **E** in terms of the optical intensity I in steady-state, and **E** is inserted in eqn [9] to yield the optically induced index change. A major signature of photorefractive solitons is the cumulative process they rely on: the space-charge field **E** builds up in time along with the distribution of carriers, until equilibrium is reached. Hence the phenomenon does not require high optical intensities but, conversely, a sufficiently long time (of the order of minutes or hours). Photorefractive solitons are typically observed at modest excitations, as low as a few microwatts, with typical waists of tens of microns.

Screening and Photovoltaic Solitons

When an externally applied bias lowers the refractive index of a crystal through its electro-optic response, a light beam can screen this effect, defining a self-waveguide supporting a spatial soliton. In a noncentrosymmetric photorefractive, the beam raises the conductivity in the illuminated region, locally lowering the voltage drop compared to dark regions. The induced space-charge screens the applied static field, and it may bring the refractive index back to its unbiased value. This can be seen as a voltage divider formed by a small optically controlled resistance and two large ones corresponding to the dark regions. The resulting solitary waves are called screening photorefractive solitons. For them to be stable (in time), additional illumination of intensity I_b at the same wavelength is required on the crystal in order to increase the conductivity of the (dark) regions surrounding the soliton. The charge accumulation in the beam-tails would otherwise flatten the induced index distribution and destroy the soliton.

The simplest description of screening solitons is provided by the saturating relationship between the electric field E and the light intensity I:

$$E = -\frac{V}{L}\frac{1}{1 + I/I_\mathrm{b}} \qquad [11]$$

to be used in eqn [9] to get the index perturbation via the electro-optic effect. L is the width across which the voltage is applied. Since the quadratic term in eqn [9] (weighed by the tensor g_{ijkl}) can be neglected in noncentrosymmetric crystals:

$$\Delta n \approx -\frac{1}{2} n_0^3 r_\mathrm{eff} E \qquad [12]$$

where r_eff is the relevant component of the electro-optics tensor; typically $n_0 \approx 2$, $r_\mathrm{eff} \approx$ tens or hundreds of pm/V, and the overall index perturbation is of the order of $10^{-4}–10^{-3}$, with $V/L \approx 10^3$ V/cm. This description applies to 1D solitons; for 2D solitons, sometimes referred to as 'needle' solitons, the whole set of constitutive equations must be solved numerically. Nevertheless, in most cases the saturating model, even if not rigorous, describes well solitons and related phenomena both theoretically and experimentally, especially when nonlocal effects can be ignored.

Figure 3 shows the propagation of a 2D spatial screening soliton (top) compared to the linear case (bottom). The diffractive regime is realized by artificially 'turning off' the nonlinearity acting on the applied voltage (when $V = 0$ in eqn [11] then $\Delta n = 0$, corresponding to no induced perturbation).

Another class of photorefractive spatial solitary waves is that of photovoltaic solitons. In this case the electric field in the crystal has an additional component through the photovoltaic effect, the latter being relevant in materials such as $\mathrm{LiNbO_3}$. To sustain bright solitons the index perturbation due to the photovoltaic current, which induces the space-charge field, must be positive. This is the case for Cu:KNSBN, where 2D photovoltaic solitons were first observed.

The space-charge field, due to the photovoltaic effect, can be derived from the Kukhtarev model:

$$E = -E_\mathrm{ph}\frac{I/I_\mathrm{b}}{1 + I/I_\mathrm{b}} \qquad [13]$$

with E_ph is a constant depending on the material ($E_\mathrm{ph} \approx 10^3$ V/cm) and I_b is the dark-irradiance controlled by the background laser light. Typical



Figure 3 2D photorefractive soliton. Top view photograph of a 10 mm wide spatial soliton propagating in strontium barium niobate (top), and for comparison, the same beam diffracting when the nonlinearity if 'turned off' (bottom). (Adapted with permission from Stegeman GI, Christodoulides DN and Segev M (2000) Optical spatial solitons: historical perspectives. *IEEE Journal of Selected Topics in Quantum Electronics* 6: 1419–1426).

geometries account for the tensorial nature of the effect, and are arranged to make I_b of the same magnitude of the beam intensity I. If $E_{ph} > 0$, as in Cu:KNSBN, eqn [13] in eqn [12] shows that a positive index change of the saturating type can be induced and support bright solitons. This model is successfully used for both 1D and 2D bright photovoltaic spatial solitons.

Photorefractive Solitons in Centrosymmetric Media

Most experiments on screening solitons were performed in ferroelectric noncentrosymmetric crystals. When brought above the Curie temperature T_c, such materials exhibit a phase-transition to a centrosymmetric paraelectric state. Crystals such as Potassium Lithium Tantalate Niobate have room-temperature phase-transitions, conveniently enabling experimental investigations. In paraelectrics, the second-order electro-optic tensor r_{ijk} is zero because of symmetry, but the photorefractive effect is still available through the third-order coefficient g_{ijkl} in eqn [9]. By properly choosing the orientation, eqn [12] can then be replaced by

$$\Delta n = \frac{1}{2} n_0^3 \varepsilon_0^2 (\varepsilon_r - 1)^2 g_{\text{eff}} E^2 \qquad [14]$$

Operation near T_c greatly enhances the relevant electro-optic coefficient $g_{\text{eff}} > 0$ ($g_{\text{eff}} \approx 0.1\ \text{m}^4\ \text{C}^{-2}$), making the observation of photorefractive screening solitons possible. Using eqn [11] in eqn [14] the model is saturating and works for both 1D and 2D bright solitons.

Thanks to the low powers involved and a mature crystal technology, the photorefractive effect and related soliton phenomena have contributed several impressive results in optical morphology of nonlinear light propagation, including incoherent and white light excitations.

Spatial Solitons in Nonlocal Media, Liquid Crystalline Media

A link, such as the Kerr law (eqn [4]), between the index perturbation and the optical intensity is 'local', because Δn at a given point (x, y, z) only depends on the intensity at the same location. Otherwise the medium is said to be 'nonlocal', e.g., one of those described by the general Kukhtarev model (eqn [10]) although, sometimes well approximated by eqns [11] or [13].

There are various mechanisms yielding nonlocality, mainly through spatial diffusion of the index perturbation far from the excitation. Remarkable nonlocal effects are expected when the spatial features of the beam, e.g., its waist, are significantly smaller than those of the induced polarization.

One of the most important effects of nonlocality is the stabilization against the catastrophic self-focusing in 2D, as experimentally investigated by Suter and Blasberg in 1992. Evidence of a highly nonlocal behavior has been very recently reported in liquid crystals, where the nonlinearity can be thermal or re-orientational. In the former case the index perturbation is much wider than the beam waist due to thermal diffusion associated to (absorption mediated) heat transfer. In the latter case the elastic properties of the medium produce a widening of the self-waveguide far from the beam axis. In nematic liquid crystal (NLC), the re-orientational response stems from the optically induced tilt of the elongated molecules towards the linearly polarized field versor. The light forced re-orientation increases the refractive index, thus creating the self-guiding conditions for spatial solitons. However, since in the nematic phase the molecules are linked together in a wide-scale order, the region (kernel) affected by this process is determined by the elastic properties of the medium and can extend to tens of microns.

An effective approach to describe spatial solitons in a highly nonlocal medium (where the kernel is much larger than the beam) postulates that the punctual relationship between Δn and I is replaced by a link between Δn and the beam power P. In such a way the transverse integral of the intensity is fully embedded in the index perturbation.

Assuming $n = n(P, r)$ with the beam mainly subject to the refractive perturbation near its axis, one can write:

$$n^2(r, P) = n_0^2(P) - r^2 \gamma(P) \qquad [15]$$

with $n_0^2(P) \cong n_0^2$ the on-axis value. $\gamma(P)$ depends on the specific geometry and determines the wavefront convexity at the origin. The overall profile is basically determined by the constitutive relationships of the medium. The propagation equation can be shown as

$$2ik \frac{\partial A}{\partial z} + \nabla_\perp^2 A = \frac{k^2}{n_0^2} \gamma^2(P) r^2 A \qquad [16]$$

Equations like [16] also describe the transverse profile of a beam linearly propagating in optical fibers, as well as the quantum harmonic oscillator (interpreting z as time). The soliton is its nondiffracting solution, a particular stationary case of a more general Gaussian beam with waist variable in propagation.

For intensities:

$$I(z) = \frac{P}{\pi w^2(z)} \mathrm{e}^{-r^2/w^2(z)} \quad [17]$$

the spot-size obeys:

$$\frac{w^2(z)}{w_0^2} = 1 + \left[\frac{1}{k_0^2 w_0^4 \gamma^2(P)} - 1 \right] \sin^2 \left[\frac{n_0 z}{\gamma(P)} \right] \quad [18]$$

Therefore, for a Gaussian excitation, the waist oscillates along z between the values w_0 – in general determined by the launch conditions – and $w_m = w_0 \gamma(P_S)/\gamma(P)$. P_s is the 'soliton power' for which $w_m = w_0$ and $k^{02} w_0^4 \gamma^2(P_S) = 1$, hence for $P < P_s$ or $P > P_s$ the beam pulsates cyclically with z (breathes). Such a dynamic balance between diffraction and nonlinearity stems from the spectral broadening associated to an increased beam shrinking: when the spectrum widens sufficiently, diffraction starts to prevail and the beam spreads again. This process repeats itself in propagation.

The stationary solution for $P = P_s$ corresponds to a point in the existence curve of waist versus power, i.e.:

$$k_0 w_0^2 \gamma(P_S) = 1 \quad [19]$$

Such exact balance is critical, and experimentally observed solitary waves in highly nonlocal media appear as breathers.

Figure 4 displays the intensity profile of a soliton propagating in nematic liquid crystals, as acquired by a digital camera placed on the top of the cell and retrieving the scattered light (see Figure 5). The waist oscillation in the self-trapped beam and the dependence of the period on excitation are apparent.



Figure 4 Nonlocal breather. (Top) top view photograph of a spatial soliton in NLC. Beam waist oscillations are apparent in propagation, as graphed (bottom panels) versus z for various excitations.



Figure 5 Sketch of a liquid crystal cell for the observation of nonlocal solitons. $\theta(x)$ is the orientation of the main axis of the ellipsoidal molecules, fixed by an external bias. The alignment is planar, with molecules parallel to the cell facets. The optical beam propagates in the center of the cell, where $\theta(x) = \theta_0$, and induces an additional re-orientation ψ. (Adapted from Conti C, Peccianti M and Assanto G (2003) Route to nonlocality and observation of accessible solitons. *Physics Review Letters* 91: 073901).

A specific highly nonlocal nonlinear system is formed by a linearly polarized beam in NLC with molecules pre-tilted (by an external electric or magnetic field) at $\theta_0 = \pi/4$ with respect to the input polarization. As sketched in Figure 5, the light wave induces an additional tilt Ψ. At the lowest order of approximation, the relevant set of equations can be shown as:

$$\begin{aligned} 2ik\frac{\partial A}{\partial z} + \nabla_\perp^2 A &= -k^2 \frac{n_a^2}{n_0^2} \Psi A \\ K\nabla_\perp^2 \Psi - G\Psi + \frac{n_a^2}{2cn_0} |A|^2 &= 0 \end{aligned} \quad [20]$$

with K the NLC elastic constant ($K \approx 10^{-11}$ N, for NLC of the E7 type), $n_0 \approx 1.5$, n_a^2 the optical anisotropy ($n_a \approx 1$), i.e., the difference between relative permittivities along the two principal axes, G a constant determined by the specific geometry of the NLC cell and the pre-tilt angle θ_0. Since, for $K = 0$, eqn [20] represents a Kerr medium, it can be considered one of the simplest nonlocal generalizations of local models for spatial solitons. The length $R_c = \sqrt{K/G}$ quantifies the diffusion of the index perturbation away from the beam axis, such that Ψ decays according to the modified Bessel function $K_0(r/R_c)$. Typically, $R_c \approx 20\ \mu$m and solitons are observed in the visible and near-infrared.

Solitary wave profiles are found with the ansatz $A = a\exp(\mathrm{i}\beta z)$, obtaining:

$$\begin{aligned} &\frac{\nabla_\perp^2 a}{2k^2} + \frac{n_\mathrm{a}^2}{2n_0^2}\Psi a = \frac{\beta}{k}a \\ &R_\mathrm{c}^2\nabla_\perp^2\Psi + \frac{R_\mathrm{c}^2 n_\mathrm{a}^2}{2Kcn_0}a^2 = \Psi \end{aligned} \qquad [21]$$

No analytical solutions of eqns [21] are known in 2D, hence the profiles have to be derived numerically. Conversely, it can be shown that 1D sech^2 solutions exist (see next section on parametric solitons). From eqn [21], the whole family can be parameterized by a dimensionless $\alpha = 1/(2k\beta R_\mathrm{c}^2)$. Since $(1/2k\beta)^{1/2}$ measures the soliton waist (see eqn [7]), α relates the beam size and the extension of the induced perturbation. Small α solutions access the highly nonlocal regime, as shown in Figure 6, where the ratio R between the index perturbation and the soliton waist is graphed. The insets show sample profiles of a and ψ in two limits, respectively. On the other hand, when $K = 0$, $R_\mathrm{c} = 0$, and $\alpha \to \infty$, the local limit yields an index perturbation comparable in size to the beam waist.

It is worth pointing out that a model such as eqn [16], also derived in the framework of plasma physics, predicts unconditionally stable self-trapped beams. Nonlocal solitons realize an energy minimum, thus preventing beam collapse such as in saturable (Kerr) media. The oscillations observed in experiments can be regarded as fluctuations around the lowest energy state.



Figure 6 Spatial solitons versus nonlocality. Graph of the ratio *R* between the waist of the induced index perturbation in a nonlocal medium and the soliton waist versus parameter α. The insets show (in normalized units) soliton (solid line) and perturbation profiles (dashed line) for two different α, i.e., in the local ($\alpha = 100$) and highly nonlocal ($\alpha = 0.01$) regimes. (Adapted from Conti C, Peccianti M and Assanto G (2003) Route to nonlocality and observation of accessible solitons. *Physics Review Letters* 91: 073901).

Parametric Spatial Solitons in Quadratic Media

Solitons due to parametric processes, such as second-harmonic generation, belong to a different class with respect to previous sections. In fact, no refractive index modification can be physically associated to parametric effects. Parametric solitons are characterized by a power spectral density peaked around at least two carrier harmonic frequencies. It is the interaction between these components which provides the diffraction beating mechanism. Their existence was predicted in the early 1970s by Sukhorukov and Karamzin, while the first experimental evidence was reported in 1995.

The simplest process to address is second-harmonic generation (SHG): a fundamental frequency (FF) wave at ω interacts with a component at 2ω. The latter can be spontaneously generated in noncentrosymmetric crystals (e.g., $\mathrm{LiNbO_3}$, $\mathrm{KNbO_3}$, BBO, KTP, etc.) or externally seeded.

For plane waves, this process is ruled by:

$$\begin{aligned} &\mathrm{i}\frac{\mathrm{d}A_1}{\mathrm{d}z} + \frac{\omega d_\mathrm{eff}}{c}A_1^* A_2\,\mathrm{e}^{-\mathrm{i}\Delta kz} = 0 \\ &\mathrm{i}\frac{\mathrm{d}A_2}{\mathrm{d}z} + \frac{\omega d_\mathrm{eff}}{c}A_1^2\,\mathrm{e}^{\mathrm{i}\Delta kz} = 0 \end{aligned} \qquad [22]$$

with $\Delta k = k_1 - 2k_2 = 2\omega/c(n_1 - n_2)$ the phase mismatch, d_eff the nonlinear coefficient, n_2 and n_1 the indices at SH and FF, respectively, and

$$E_\mathrm{opt} = \mathrm{Re}\left[\sqrt{\frac{2Z_0}{n_1}}A_1\mathrm{e}^{-\mathrm{i}\omega t + \mathrm{i}k_1 z} + \sqrt{\frac{2Z_0}{n_2}}A_2\mathrm{e}^{-2\mathrm{i}\omega t + \mathrm{i}k_2 z}\right]$$

the overall electric field. d_eff relates to the quadratic susceptibility $d_\mathrm{eff}^{(2)}$ (measured in $\mathrm{mV^{-1}}$) through to $d_\mathrm{eff} = d_\mathrm{eff}^{(2)}\sqrt{2Z_0}/(n_1\sqrt{n_2})$, and typically $d_\mathrm{eff} \approx 10^{-10}\,\mathrm{m^2\,W^{-1/2}}$.

Equations [22] show that, in general, the harmonics with amplitudes A_1 and A_2 affect each other's phase and intensity during propagation. The solution with constant moduli, i.e.:

$$\begin{aligned} A_1 &= \sqrt{I_1}\exp\left[\mathrm{i}\frac{\omega}{c}\Delta n_1 z\right] \\ A_2 &= \sqrt{I_2}\exp\left[\mathrm{i}\frac{2\omega}{c}\Delta n_2 z\right] \end{aligned} \qquad [23]$$

with I_1 and I_2 the respective intensities, provides a 'pure' phase variation and 'apparent' index changes Δn_1 and Δn_2 on either wave. The latter satisfy:

$$\Delta n_1 = d_{\text{eff}}^2 \frac{I_2 - I_1/2}{n_1 - n_2}$$
$$\Delta n_2 = d_{\text{eff}}^2 \frac{I_1}{2I_2} \frac{I_2 - I_1/2}{n_1 - n_2} \qquad [24]$$

with the constraint (for plane waves to exist):

$$I_1 = 2I_2 - 2\frac{n_1 - n_2}{d_{\text{eff}}}\sqrt{I_2} \qquad [25]$$

Equations [24] encompass a great deal of the physics in self-trapping via SHG. When eqn [25] is satisfied (at least approximately), the effect of SHG is exclusively on the phase. Assuming eqn [24] is valid for (wide) beams, the propagation in the presence of diffraction can be described by two coupled equations of the type [1] with relevant perturbations (eqn [24]). This shows that the sign of the term $(2I_2 - I_1)/(n_1 - n_2)$ is crucial, because focusing at both harmonics ($\Delta n_{1,2} > 0$) requires $(2I_2 - I_1)/(n_1 - n_2) > 0$.

When just a fundamental frequency (ω) is launched, solitons are generated for $\Delta k > 0$: a small 2ω component is provided via SHG and $I_1 > 2I_2$. In fact, since SHG ($\omega + \omega = 2\omega$) is followed by difference frequency generation ($2\omega - \omega = \omega$, DFG), for any finite mismatch $\Delta k > 0$, a portion of the FF travels for a while at 2ω before it is back-converted: this is commonly named 'cascading' and, as a consequence, part of the FF undergoes a positive phase shift. The converse happens in the DFG + SHG process. Finally, if an SH beam with a small FF seed is input, solitons form for $\Delta k < 0$ being $2I_2 > I_1$. From a physical point of view, these mechanisms create the phase-front distortion required to counteract diffraction. Figure 7 is an artist's sketch on the formation of an SHG soliton.

Equations [24] are approximately valid and rely on a plane-wave insight, but they point out the wealth of possibilities offered by three-wave interactions for light transverse localization via parametric processes. The full set of coupled equations describing parametric solitons from SHG differs from eqn [1]:

$$\mathrm{i}\frac{\mathrm{d}A_1}{\mathrm{d}z} + \frac{1}{2k_0 n_1}\nabla_\perp^2 A_1 + \frac{\omega d_{\text{eff}}}{c} A_1^* A_2 \mathrm{e}^{-\mathrm{i}\Delta kz} = 0$$
$$\mathrm{i}\frac{\mathrm{d}A_2}{\mathrm{d}z} + \frac{1}{4k_0 n_2}\nabla_\perp^2 A_2 + \frac{\omega d_{\text{eff}}}{c} A_1^2 \mathrm{e}^{\mathrm{i}\Delta kz} = 0 \qquad [26]$$

as it includes diffraction terms added to eqn [22].


$I \ll I_{\text{Threshold}}$
FF
$I < I_{\text{Threshold}}$
FF>> SH
$I > I_{\text{Threshold}}$
FF + SH

Figure 7 Parametric solitons via SHG. Intuitive description of soliton formation with an FF Gaussian input. At low powers (top) and for a small amount of generated SH (center) linear diffraction dominates. Above threshold parametric gain efficiently counteracts diffraction, originating a spatial soliton via quadratic cascading.

The self-trapped solutions are found as in eqn [23], with

$$A_1 = a_1(x, y)\exp(\mathrm{i}\beta z)$$
$$A_2 = a_2(x, y)\exp(\mathrm{i}\Delta kz)\exp(2\mathrm{i}\beta z), \quad \text{and} \qquad [27]$$
$$a_{1,2}(x, y) = \sqrt{I_{1,2}(x, y)}$$

These show that, even in the presence of diffraction, SHG can give rise to pure phase effect if the profiles satisfy:

$$\frac{1}{2k_0 n_1}\nabla_\perp^2 a_1 + \frac{\omega d_{\text{eff}}}{c} a_1 a_2 = \beta a_1$$
$$\frac{1}{8k_0 n_2}\nabla_\perp^2 a_2 + \frac{\omega d_{\text{eff}}}{2c} a_1^2 = \beta + \frac{\Delta k}{2} a_2 \qquad [28]$$

which are the space-dependent counterpart of eqn [25]. Again, β is a nonlinear contribution to the FF wavevector, and determines the corresponding correction $\beta_2 = 2\beta + \Delta k$ at SH. β is univocally determined by the power of the two harmonics in the solutions of eqn [28].

In the particular case:

$$\Delta k = \beta\frac{n_1 - 4n_2}{2n_2} \qquad [29]$$

1D parametric solitons exhibit profiles

$$a_1 = \sqrt{\frac{n_1}{n_2}}\frac{3c}{4\omega d_{\text{eff}}}\beta\,\mathrm{sech}\left(\sqrt{\frac{\beta k_0 n_1}{2}}x\right)^2$$
$$a_2 = \frac{3c}{4\omega d_{\text{eff}}}\beta\,\mathrm{sech}\left(\sqrt{\frac{\beta k_0 n_1}{2}}x\right)^2 \qquad [30]$$

and the powers per unit of transverse wavefront along y at the two components are:

$$P_1 = \int_{-\infty}^{\infty} a_1^2(x)\mathrm{d}x = \frac{n_1}{n_2}\frac{3\sqrt{2}c^2}{4\omega^2 d_{\mathrm{eff}}^2\sqrt{k_0 n_1}}\beta^{3/2}$$
$$P_2 = \int_{-\infty}^{\infty} a_2^2(x)\mathrm{d}x = \frac{3\sqrt{2}c^2}{4\omega^2 d_{\mathrm{eff}}^2\sqrt{k_0 n_1}}\beta^{3/2} \qquad [31]$$

with the total soliton power $P_1 + P_2$, directly related to β.

Equation [29] implies that, for $n_1 > 4n_2$ and therefore $\Delta k > 0$, 1D parametric solitons exhibit the sech^2 profile. Otherwise, no analytical solutions are known even in 1D, and numerical techniques need to be employed. The same applies to 2D soliton profiles in all instances.

Notably, eqns [28] are essentially identical to eqns [21] for solitons in NLC. Therefore, Figure 4 provides the features of 2D parametric solitons as well, with 'a' replaced by 'a_1', and 'Ψ' by 'a_2'. For parametric solitons $\alpha = 4n_2(1 + \Delta k/2\beta)/n_1$, showing that at phase-matching ($n_2 = n_1$, $\Delta k = 0$) $\alpha = 4$, while large α's correspond to large Δk or small β's, e.g., low power and very wide solitons. The sech^2 profile for 1D solitons corresponds to $\alpha = 1$. 1D and 2D soliton solutions exist for any $\alpha > 0$.

The model for SHG solitons is more complicated than the previously discussed Kerr or saturable cases. The stability question can be formulated as the constrained-minimum problem of a specific functional, the Hamiltonian H. In general, for a given soliton power (the sum of the powers at the two harmonics) two branches exist for H. They correspond to two solitary solutions, differing in the ratio between the two powers. The solution with $P_2 > P_1$ corresponds to higher H, and is unstable via parametric amplification. When a harmonic field propagates in the presence of energy at a subharmonic (e.g., a small amount of FF), it tends to break up and transfer energy to it. Looking at Figure 4, this corresponds to small α's, only attainable when $\Delta k < 0$. As a result, quadratic solitons with a relevant SH content are unstable and thus, more difficult to observe.

The generation of a parametric soliton with a Gaussian input at FF, has a threshold (see Figure 7). This is because the input has to generate sufficient SH in order to produce and 'feel' the nonlinear phase-shift. A numerical simulation of eqn [26] shows the formation of a parametric spatial soliton, as displayed in Figure 8. As shown in (a), if only a small second-harmonic is generated by an FF excitation, diffraction dominates. Above threshold, as in (b), a stable self-trapped two-color beam is generated.

Two significant experimental results are reproduced in Figures 9 and 10. The photograph in Figure 10 shows a soliton propagating in periodically poled KTP (PPKTP) over five Rayleigh ranges, obtained by imaging the out-of-plane scattered light. Parametric solitons are typically observed with the FF in the near-infrared and the SH in the visible.

Figure 10 shows the output spots at FF and SH of a beam propagating in PPKTP for various FF excitations, until a soliton is generated (right end).

We close this section by observing that more general models must be considered to describe the whole physics of solitons in media with a quadratic



Figure 8 Parametric solitons via SHG. 1D numerical simulations using the beam propagation method. (a) An FF Gaussian excitation diffracts at low powers; (b) at high FF powers, after a transient both harmonics propagate undiffracted as a parametric spatial soliton. (Adapted with permission from Assanto G and Stegeman GI (2002) Simple physics of quadratic spatial solitons. *Optics Express* 10: 388–396).



Figure 9 2D parametric solitons via SHG. Top view photograph of a soliton in PPKTP (20 ps pulses at $\lambda \approx 983$ nm and pulse energy of about 0.3 μJ). The dashed lines illustrate the diffractive behavior in the absence of nonlinear effects. (Adapted with permission from Malendevich R, Jankovic L, Polyakov S, Fuerst R, Stegeman G, Bosshard C and Gunter P (2002) Two-dimensional type I quadratic spatial solitons in KNbO3 near non-critical phase-matching. *Optics Letters* 27: 631–673.)



Figure 10 2D parametric solitons via SHG. Beam spots at FF (top row) and SH (bottom) for various input intensities in a PPKTP crystal. (Adapted with permission from Stegeman GI, Jankovic L, Kim H, *et al.* (2003) Generation of, and interactions between quadratic spatial solitons in non-critically-phase-matched crystals. *Journal of Nonlinear Optical Physics and Materials*. 12: 1–20).

response. We mention, for example, the subtleties associated to anisotropy (walk-off), nondegenerate three wave interactions, additional Kerr and higher-order effects.

Conclusions

Bright spatial solitons are widespread, and have been reported in several materials using various wavelengths and geometries. The brief overview presented above was intended to introduce the variety of basic mechanisms underlying their generation and propagation, but could not even touch upon the wealth of additional properties and potential applications of individual and multiple spatial solitons, their interactions and collisional properties, their stability and their control with other linear and nonlinear light waves, as well as with additional nonoptical effects (temperature, voltage, acoustic, and magnetic fields, etc.). Fascinating phenomena involve bright spatial solitons and are the subject of current research. Among them we like to mention all-optical logic and signal readdressing, beam shaping and filtering, limiting, sub-wavelength spatial compression, and digital imaging. To learn more on the subject, we encourage the interested readers to look up the vast literature covering both fundamental and applied aspects of optical spatial solitons.

List of Units and Nomenclature

Angular frequency [s^{-1}]	ω
Beam waist [m]	w
Boltzmann constant [$\mathrm{J\,K}^{-1}$]	k_B
Current density vector [$\mathrm{A\,m}^{-2}$]	$\mathbf{J}$
Density of ionized donors [m^{-3}]	N_d^i
Dielectric constant of vacuum [$\mathrm{F\,m}^{-1}$]	ε_0
Director angle perturbation [rad]	ψ
Director orientation angle [rad]	θ_0
Electric field amplitude, normalized [$\mathrm{W}^{1/2}\,\mathrm{m}^{-1}$]	a, A
Electric field amplitude, optical frequency [Vm^{-1}]	E_opt
Electric field vector, low frequency [$\mathrm{V\,m}^{-1}$]	$\mathbf{E}$
Electron charge [C]	q
Electron density [m^{-3}]	ρ
Electron mobility [$\mathrm{m}^2\,\mathrm{V}^{-1}\,\mathrm{s}^{-1}$]	μ
Electro-optic second-order tensor [$\mathrm{m\,V}^{-1}$]	r, r_{ijk}

Electro-optic third-order tensor $[\mathrm{m^4\,C^{-2}}]$	$g_{\mathrm{eff}}, g_{ijkl}$
Element of the photovoltaic tensor $[\mathrm{C\,m^3\,J^{-1}}]$	β_{ph}
Kerr nonlinear coefficient $[\mathrm{m^2W^{-1}}]$	n_2
Low frequency permittivity $[\mathrm{F\,m^{-1}}]$	ε_{S}
Medium elastic constant [N]	K
Medium forcing constant $[\mathrm{N\,m^{-2}}]$	G
Non local decay distance [m]	R_{c}
Nonlinear length [m]	L_N
Nonlinear wavevector correction $[\mathrm{m^{-1}}]$	β, β_2
Optic axis versor	$\mathbf{c}_{\mathrm{opt}}$
Optical background intensity $[\mathrm{Wm^{-2}}]$	I_{b}
Optical dark intensity $[\mathrm{Wm^{-2}}]$	I_{dark}
Optical index anisotropy	n_{a}
Optical intensity $[\mathrm{Wm^{-2}}]$	I
Optical saturation intensity $[\mathrm{Wm^{-2}}]$	I_{S}
Photo-ionization cross-section $[\mathrm{m^2\,J^{-1}}]$	s
Photovoltaic index perturbation constant $[\mathrm{V\,m^{-1}}]$	E_{ph}
Power [W]	P
Power per wavefront unit $[\mathrm{W\,m^{-1}}]$	P_1, P_2
Propagation coordinate [m]	z
Rayleigh length [m]	L_{R}
Recombination rate $[\mathrm{m^3\,s^{-1}}]$	γ_{r}
Refractive index	n
Refractive index perturbation	Δn
Relative dielectric constant	ε_{r}
Sample width [m]	L
Second order effective susceptibility $[\mathrm{m\,V^{-1}}]$	$d^{(2)}_{\mathrm{eff}}$
Second order nonlinear coefficient $[\mathrm{m\,W^{-1/2}}]$	d_{eff}
Self-focusing power [W]	P_{c}
Soliton power [W]	P_{S}
Speed of light in vacuum $[\mathrm{ms^{-1}}]$	c
Static dielectric constant $[\mathrm{F\,m^{-1}}]$	ε_{s}
Temperature [K]	T
Total density of negatively charged sites $[\mathrm{m^{-3}}]$	N_{A}
Total donor density $[\mathrm{m^{-3}}]$	N_{d}
Transverse coordinates [m]	x, y, r
Transverse wave-vector $[\mathrm{m^{-1}}]$	k_x
Vacuum impedance $[\Omega]$	Z_0
Wavelength [m]	$\lambda = 2\pi n/k = 2\pi/k_0$
Wavevector in medium $[\mathrm{m^{-1}}]$	$k = n\omega/c$
Wavevector in vacuum $[\mathrm{m^{-1}}]$	$k_0 = \omega/c$

See also

Babinet's Principle. **Fiber and Guided Wave Optics:** Nonlinear Optics. **Nonlinear Optics, Applications:** Self-focusing and Related Effects (Solitons and Multiphoton Absorption). **Nonlinear Optics, Basics:** Cascading; Photorefraction.

Further Reading

Assanto G and Peccianti M (2003) Spatial solitons in nematic liquid crystals. *IEEE Journal of Quantum Electronics* 39: 13–21.

Assanto G and Stegeman GI (2002) Simple physics of quadratic spatial solitons. *Optics Express* 10: 388–396.

Assanto G, Peccianti M and Conti C (2003) Nematicons: optical spatial solitons in nematic liquid crystals. *Optics and Photonics News* 14: 44–48.

Buriak AV, Di Trapani P, Skryabin DV and Trillo S (2002) Optical solitons due to quadratic nonlinearities: from basic physics to futuristic applications. *Physics Reports* 370: 63–235.

Chiao RY, Garmire E and Townes CH (1964) Self-trapping of optical beams. *Physics Review Letters* 13: 479–482.

Conti C, Peccianti M and Assanto G (2003) Route to nonlocality and observation of accessible solitons. *Physics Review Letters* 91: 073901.

Conti C, Peccianti M and Assanto G (2004) Observation of optical spatial solitons in a highly nonlocal medium. *Physics Review Letters* 92: 113902.

Crosignani B and Salamo G (2002) Photorefractive solitons. *Optics and Photonics News* 13: 38–41.

Kivshar Y and Agrawal G (2003) *Optical Solitons: From Fibers to Photonic Crystals*. New York: Academic Press.

Stegeman GI, Christodoulides DN and Segev M (2000) Optical spatial solitons: historical perspectives. *IEEE Journal of Selected Topics in Quantum Electronics* 6: 1419–1426.

Torner L and Sukhorukov AP (2002) Quadratic solitons. *Optics and Photonics News* 13: 42–47.

Various Authors (1998) In: Kajzar F and Reinisch R (eds) *Beam Shaping and Control with Nonlinear Optics*. New York: Plenum Press.

Various Authors (2001) In: Boardman AD and Sukhorukov AP (eds). *Soliton-driven Photonics*. London: Kluwer Academic.

Various Authors (2002) In: Trillo S and Torruellas WE (eds) *Spatial Solitons*. Berlin: Springer-Verlag.

Optical Fiber Solitons, Physical Origin and Properties

G Millot and P Tchofo-Dinda, Université de Bourgogne, Dijon, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In the last few decades there has been considerable effort made in understanding energy-localization phenomena in many areas of physics. Optical fibers constitute excellent media where such phenomena are routinely observed by means of relatively simple experimental setups. A well-known example of those energy-localization phenomena is the optical soliton, which corresponds to a light pulse that can propagate in optical fibers over relatively long distance without experiencing significant degradations. From a fundamental point of view, the high stability of the optical soliton results from a delicate balance between the fiber chromatic dispersion and the nonlinear refractive (or Kerr) index. The idea of using optical solitons as information bits in high-speed communication systems was first proposed in 1973, and then demonstrated experimentally in 1980. After these discoveries, interest in optical soliton transmission started to increase. In an ideal fiber, optical solitons can be modeled approximately by the nonlinear Schrödinger equation, whose solutions are well known. In this article we present the main types of soliton behavior and the fundamental physical processes that are involved in soliton stability.

The Nonlinear Schrödinger Equation

In optical fibers, there are many nonlinear phenomena that are difficult to understand by direct analysis of the nonlinear polarization (e.g., the soliton effect) but that can be readily understood by use of the nonlinear Schrödinger equation (NLSE). Let us consider an optical pulse that propagates in the z-direction, in a dielectric Kerr medium such as an optical fiber, with frequency ω_0, wavenumber k_0, and an envelope $\mathcal{A}$:

$$E = \mathcal{A}\exp[\mathrm{i}(\mathbf{k}_0\cdot\mathbf{r} - \omega_0 t)] \qquad [1]$$

We assume that the wave envelope $\mathcal{A}$ varies slowly in time and space compared with the fast variations of the carrier wave ω_0. In this situation, the Fourier spectrum of the wave is restricted to frequencies and wavenumbers close to $\omega = \omega_0$ and $k = k_0$, respectively. Then, the wavenumber k can be expanded in a Taylor series around k_0, as follows:

$$k(\omega) = k_0 + \left(\frac{\partial k}{\partial \omega}\right)_{\omega_0}(\omega - \omega_0) + \frac{1}{2}\left(\frac{\partial^2 k}{\partial \omega^2}\right)_{\omega_0}(\omega - \omega_0)^2 + \left(\frac{\partial k}{\partial |\mathcal{A}|^2}\right)_{\mathcal{A}_0 = 0}|\mathcal{A}|^2 + \cdots \qquad [2]$$

The nonlinear term $Q = \left(\partial k/\partial|\mathcal{A}|^2\right)_{\mathcal{A}_0=0}$ arises from the optical Kerr effect, as $k = n\omega/c = k(\omega, |\mathcal{A}|^2)$.

Setting $K = k - k_0$, $\Omega = \omega - \omega_0$, $\beta_1 = (\partial k/\partial\omega)_{\omega_0}$ and $\beta_2 = \left(\partial^2 k/\partial\omega^2\right)_{\omega_0}$, one can rewrite eqn [2] as

$$K = \beta_1\Omega + \frac{1}{2}\beta_2\Omega^2 + Q|\mathcal{A}|^2 \qquad [3]$$

where β_1 is the inverse of the group velocity and β_2 is the group velocity dispersion (GVD) coefficient. Equation [3] represents the nonlinear dispersion relation for the envelope. Using a Fourier transform method in which K is replaced by a spatial operator $-\mathrm{i}\,\partial/\partial z$, and Ω by a temporal operator $\mathrm{i}\,\partial/\partial T$, one can apply eqn [3] on the envelope $\mathcal{A}$ to obtain the following equation:

$$\mathrm{i}\frac{\partial \mathcal{A}}{\partial z} + \mathrm{i}\beta_1\frac{\partial \mathcal{A}}{\partial T} - \frac{1}{2}\beta_2\frac{\partial^2 \mathcal{A}}{\partial T^2} + Q|\mathcal{A}|^2\mathcal{A} = 0 \qquad [4]$$

In practice it is more convenient to make use of the quantity $A = (\alpha A_{\mathrm{eff}})^{1/2}\mathcal{A}$, for which $|A|^2$ represents the wave power. The parameter A_{eff} is the effective core area, which takes into account the variation of the light intensity across the transverse section of the fiber. The value of A_{eff} strongly depends on the mode distribution. Using a system of coordinates that moves at the group velocity v_{g}, i.e., replacing T by $t = T - z/v_{\mathrm{g}}$, eqn [4] reduces to the basic NLSE:

$$\mathrm{i}\frac{\partial A}{\partial z} - \frac{1}{2}\beta_2\frac{\partial^2 A}{\partial t^2} + \gamma|A|^2 A = 0 \qquad [5]$$

where γ is the nonlinear coefficient defined by $\gamma = Q/(\alpha A_{\mathrm{eff}}) = \omega_0 n_2/(cA_{\mathrm{eff}})$ and expressed in $\mathrm{W}^{-1}\mathrm{m}^{-1}$. This equation is formally analogous to the Schrödinger equation in quantum mechanics but with a nonlinear potential. Furthermore, in this basic NLSE, all higher-order terms that describe effects such as the fiber losses, third-order dispersion, or stimulated Raman scattering, are neglected. The NLSE for pulse propagation in optical fibers was first derived in 1973 by Hasegawa and Tappert. It has also found applications in other areas of physics, such as in plasma physics, fluid dynamics and electrical transmission lines. From a fundamental point of view, the basic NLSE involves the combined effects of the group velocity dispersion (GVD) and self-phase modulation (SPM), which are described by the second and third terms in eqn [5], respectively. Each of these two effects is analyzed below.

Group Velocity Dispersion

The individual effect of the GVD on pulse propagation can be obtained by setting the nonlinear coefficient to zero ($\gamma = 0$). In this case, eqn [5] reduces to

$$\mathrm{i}\frac{\partial A}{\partial z} = \frac{1}{2}\beta_2 \frac{\partial^2 A}{\partial t^2} \qquad [6]$$

In the frequency domain, eqn [6] becomes

$$\mathrm{i}\frac{\partial \tilde{A}}{\partial z} = -\frac{1}{2}\beta_2 \omega^2 \tilde{A} \qquad [7]$$

where $\tilde{A}$ represents the Fourier transform of A. The solution of eqn [7] is given by

$$\tilde{A}(z, \omega) = \tilde{A}(0, \omega)\exp(\mathrm{i}\beta_2 \omega^2 z/2) \qquad [8]$$

As eqn [8] shows, the GVD changes the phase of each spectral component of the pulse by an amount that depends on the propagated distance and the frequency of the spectral component. But this effect does not modify the power spectrum: ($|\tilde{A}(z, \omega)|^2 = |\tilde{A}(0, \omega)|^2$). This phase change can modify the shape of the pulse envelope. For example, a Gaussian pulse with a width of δ_0 at $z = 0$, $A(z = 0, t) = \exp\{(-t^2/(2\delta_0^2)\}$, will transform into

$$A(z,t) = [\delta_0^2/(\delta_0^2 - \mathrm{i}\beta_2 z)]^{1/2} \exp[-t^2/2(\delta_0^2 - \mathrm{i}\beta_2 z)] \qquad [9]$$

at a distance z. In other words, the pulse width increases from δ_0 to $\delta_0[1+(z/L_\mathrm{D})^2]^{1/2}$. The parameter $L_\mathrm{D} = \delta_0^2/|\beta_2|$ defines a dispersion length, that is, a length scale over which the dispersive effects become important. At $z = L_\mathrm{D}$ the Gaussian pulse broadens by a factor of $\sqrt{2}$. Thus, the GVD causes the spectral components of the pulse to move at different velocities, which broadens the pulse, as shown by Figure 1.



Figure 1 Temporal evolution of the power of a Gaussian pulse, as a function of the propagation distance. The simulation parameters are the following: input peak power $P_0 = 1$ mW, $\beta_2 = -20$ ps^2 km^{-1}, $\gamma = 3 \times 10^{-3}$ m^{-1} W^{-1} and $\delta_0 = 10$ ps. The dispersion length is $L_\mathrm{D} = 1.8$ km.

Another important effect of the GVD comes from the time dependence of the pulse phase, which one can easily obtain by rewriting eqn [9] as $A(z,t) = |A(z,t)| \exp[\mathrm{i}\phi(z,t)]$. It turns out that the GVD induces an instantaneous variation of the frequency across the pulse, called a frequency chirp. For the initially unchirped Gaussian pulse, the GVD induces a chirp given by

$$\delta\omega = -\frac{\partial \phi}{\partial t} = \frac{t\beta_2(z/L_\mathrm{D})}{|\beta_2|\delta_0^2[1 + (z/L_\mathrm{D})^2]} \qquad [10]$$

As eqn [10] illustrates, the GVD-induced frequency chirp depends on the sign of β_2, and varies linearly across the pulse.

Self-Phase Modulation

Similarly to dispersion effects, nonlinear effects in optical fibers require a minimum propagation distance to develop significantly. The distance over which nonlinear effects become important is defined as the nonlinear length L_NL, given by $L_\mathrm{NL} = 1/(\gamma P_0)$, where P_0 is the peak power.

Let us consider the propagation of a light pulse in a fiber of length L, such that $L_\mathrm{NL} < L \ll L_\mathrm{D}$. In this particular case, the effects of dispersion can be neglected, and then the NLS equation becomes

$$\mathrm{i}\frac{\partial A}{\partial z} + \gamma |A|^2 A = 0 \qquad [11]$$

It results from this equation that $|A(z,t)|^2 = |A(z = 0,t)|^2$. This means that the pulse shape remains unchanged during propagation. The solution of eqn [11] is given by

$$A(z,t) = A(0,t)\exp[\mathrm{i}\Phi_\mathrm{NL}(z,t)] \qquad [12]$$

where $\Phi_{\mathrm{NL}}(z,t) = \gamma|A(0,t)|^2 z$. Thus, the Kerr effect causes the phase of the wave envelope to vary during the propagation. The nonlinear phase shift Φ_{NL} increases with the propagated distance z. The maximum phase shift $\Phi_{\mathrm{NL}}^{\max}$ occurs at the pulse center and is given by $\Phi_{\mathrm{NL}}^{\max} = \gamma|A(0,0)|^2 z = \gamma P_0 z$. One can see that the nonlinear length represents the propagation distance at which $\Phi_{\mathrm{NL}}^{\max} = 1$. Since the nonlinear phase shift Φ_{NL} depends on the initial pulse shape, it varies nonlinearly with time t. This implies that the instantaneous optical frequency differs across the pulse from its central value ω_0. The frequency chirp is given by

$$\delta\omega(t) = \omega(t) - \omega_0 = -\frac{\partial \Phi_{\mathrm{NL}}}{\partial t} = -\frac{\partial |A(0,t)|^2}{\partial t}\gamma z \qquad [13]$$

The modification of the phase of the wave envelope by itself is called self-phase modulation. The frequency chirp increases with the propagated distance, thus implying that new frequencies are continuously generated as the pulse propagates through the fiber. This spectral broadening depends on the initial pulse shape. Figure 2 shows the variation of Φ_{NL} and the corresponding induced frequency chirp across the pulse at $z = L_{\mathrm{NL}}$ for the case of an initial Gaussian pulse.

The SPM-induced chirp exhibits several interesting features. $\delta\omega$ is negative near the leading edge (red shift) and is positive near the trailing edge (blue shift). The chirp is linear (and increases) in the central region of the pulse. In fact, the chirp $\delta\omega$ at a given propagation distance z depends on the initial chirp. As Figure 3 shows, at a sufficiently long propagated distance, the SPM-induced spectrum exhibits several peaks due to interference effects across the pulse. Indeed as Figure 2 shows, the same frequency chirp occurs at two distinct times associated with two distinct nonlinear phase shifts.

The spectrum width can be estimated by calculating the maximum value $\delta\omega_{\max}$ of the frequency chirp. For an initial unchirped Gaussian pulse one obtains

$$\delta\omega_{\max} \approx \frac{0.86\gamma P_0 z}{\delta_0} \qquad [14]$$

Thus, the spectral width increases linearly with the propagated distance z and the input peak power P_0, and is inversely proportional to the initial pulse width δ_0. The SPM can be detrimental for optical communication systems. The SPM broadens the spectrum of the signal and makes it then more susceptible to GVD effects. Note that in wavelength division multiplexing (WDM) systems, the phase modulation of a given channel can come not only from the power in the considered channel itself (SPM) but also from the power in a different channel of the WDM system (CPM, i.e., cross-phase modulation). By appropriate dispersion compensation, the impact of SPM and CPM can be significantly reduced. On the other hand, the SPM, combined with dispersive effects, leads to very useful effects such as pulse compression, or the generation of optical solitons (described below).



Figure 2 Temporal variation of the nonlinear phase shift (a) and the corresponding frequency chirp induced by SPM (b), for a Gaussian pulse.



Figure 3 Evolution of the SPM-induced spectral broadening of an initially unchirped Gaussian pulse, as a function of the propagation distance. Here the normalized distance is z/L_{NL}.

Optical Solitons

Bright Solitons

Soliton propagation results fundamentally from a delicate balance between two phenomena: GVD and SPM. As we mentioned above, the GVD causes the spectral components of the pump to move at different velocities, thus leading to a temporal broadening of the pulse as shown in Figure 1 in the case of a Gaussian input pulse. Moreover, eqn [10] shows that the effect of GVD on a propagating Gaussian pulse is associated with a linear frequency chirp $\delta\omega$ and a parabolic temporal phase, proportional to β_2. On the other hand, eqn [12] shows that the SPM induces a frequency chirp across the pulse proportional to the temporal derivative of the pulse intensity. The chirp induced by SPM is then linear only in the central region of the pulse as long as the initial pulse shape is nonparabolic. As a consequence a Gaussian input pulse cannot propagate in a distortion-free manner since the GVD for anomalous dispersion ($\beta_2 < 0$) is able to completely cancel the intensity-dependent phase shift from SPM only over the central region of the pulse. On the other hand we show below that, in the anomalous dispersion regime, the exact cancellation of the nonlinear and dispersive temporal phase components (and corresponding chirps) is obtained in the case of the propagation of a hyperbolic secant pulse, which corresponds to the fundamental bright optical fiber soliton.

We consider the propagation of an unchirped hyperbolic secant pulse at a wavelength of 1.55 μm in a standard telecommunications fiber with $\beta_2 = -21 \times 10^{-3}\ \text{ps}^2\ \text{m}^{-1}$ and $\gamma = 1.2 \times 10^{-3}\ \text{W}^{-1}\ \text{m}^{-1}$. The input pulse at $z = 0$ is given by $A(0,t) = \sqrt{P_0}\ \text{sech}\,(t/\delta_0)$ with $\delta_0 = 10$ ps and $P_0 = 175$ mW. With this choice of parameters the dispersion length is equal to the nonlinear length, i.e. $L_D = L_{NL} = 4.76$ km. In fact, these conditions correspond to those which would support a propagating soliton. However, let us consider first how SPM and GVD modify the incident pulse when acting independently. Figure 4 shows numerically computed results from the solutions of eqns [12] and [8] to illustrate the effects of nonlinear and dispersive evolution over a range of propagation distances. The figure shows the pulse intensity as well as the time-dependent phase and the corresponding frequency chirp. The evolution is clearly very different in the presence of only nonlinear or dispersive effects. Nonlinear SPM alone induces no change in the temporal intensity of the pulse, but the magnitudes of the SPM-induced phase and chirp increase with propagation distance. In contrast, GVD induces changes in both the intensity and the phase of the pulse as it propagates, and the temporal broadening with propagation is associated with a significant change in the functional forms of the phase and frequency chirp. In particular, whilst for large propagation distances it can be seen that GVD induces a parabolic temporal phase and corresponding linear chirp, this is clearly not the case for small propagation distances. This result strongly differs from that obtained for a propagating Gaussian pulse for which the temporal phase is always parabolic. In the context of soliton propagation, the results in Figure 4b are of particular significance, since they clearly show that at $z = L_D/10$ where neither SPM nor GVD noticeably modify the pulse intensity profile, the SPM and GVD-induced phases and frequency chirps have qualitatively similar forms, yet opposite sign. The split-step Fourier method demonstrates that over a sufficiently small propagation distance (e.g., $\delta z = L_D/10$) the effects of nonlinearity and dispersion can be considered to act independently on a propagating pulse. This suggests that, over the propagation segment ($0 < z < \Delta z$), the phases are capable of cancelling each other across the entire pulse profile. It is obvious that, if the effects cancel over this distance, then the propagation in the following segment will begin from the same initial condition of an unchirped pulse which was the case at $z = 0$. The nonlinear and dispersive phase components will therefore continue to cancel over successive iterations for an arbitrary length of fiber, and we thus obtain a simple physical interpretation to explain the distortion-free propagation of an optical soliton. Thus, the combined effects of GVD and SPM can prevent the occurrence of a frequency chirp across the pulse. In this situation the pulse propagates with a constant temporal profile. Such light pulses are called optical solitons.

Mathematically, the basic NLSE, eqn [5], belongs to a remarkable class of integrable nonlinear equations, which can be solved exactly for an arbitrary initial condition by means of the inverse scattering method. The solutions depend strongly on the sign of dispersion, and the relative importance of dispersive and nonlinear effects, measured by a dimensionless parameter N:

$$N^2 = \frac{L_D}{L_{NL}} = \frac{\gamma P_0 \delta_0^2}{|\beta_2|} \qquad [15]$$

In the anomalous dispersion regime ($\beta_2 < 0$) the NLS equation admits envelope-soliton solutions. The soliton order is given by the parameter N. Only the fundamental soliton, defined by $N = 1$, can propagate in the fiber with a constant profile, as schematically represented in Figure 5.



Figure 4 Numerical results showing nonlinear (left column) and dispersive (right column) propagation in an optical fiber, with parameters as described in the text, and for propagation distances as indicated. The solid lines show the pulse intensity (left axis) whilst the dashed lines show the calculated phase (right axis, top) and chirp (right axis, bottom). Constant phase offsets have been removed for clarity.



Figure 5 Temporal evolution of the power of a fundamental bright soliton, as a function of the propagation distance. The simulation parameters are the following: input peak power $P_0 = 67$ mW, $\beta_2 = -20\ \mathrm{ps^2\,km^{-1}}$, $\gamma = 3 \times 10^{-3}\ \mathrm{m^{-1}\,W^{-1}}$ and $\delta_0 = 10$ ps. The nonlinear length is $L_{NL} = 5$ km.

For the fundamental soliton, dispersion and nonlinearity exactly balance each other in a way such that neither the pulse shape nor the pulse spectrum change during the pulse propagation. The fundamental soliton ($N = 1$) is given by

$$A(z, t) = \sqrt{P_0}\,\mathrm{sech}(t/\delta_0)\,\exp(\mathrm{i}\gamma P_0 z/2) \qquad [16]$$

where the peak power required to generate this soliton is determined by $L_D = L_{NL}$, and given by

$$P_0 = \frac{|\beta_2|}{\gamma\delta_0^2} \qquad [17]$$

Note that the phase of this bright soliton remains constant across the entire pulse. For a standard single-mode fiber (SMF), at 1.55 μm wavelength, typical values of the dispersion and nonlinear parameters are $\beta_2 = -21\ \mathrm{ps^2\,km^{-1}}$ and $\gamma = 1.2 \times 10^{-3}\ \mathrm{W^{-1}\,m^{-1}}$, respectively.

So, the peak power required to propagate a fundamental soliton with pulse width $\delta_0 = 10$ ps, is $P_0 = 175$ mW. This soliton is represented in Figure 5. A further reduction of P_0 can be obtained by using dispersion-shifted fibers (DSF), for which the dispersion can be significantly reduced to values of the order of 1 $\mathrm{ps}^2\,\mathrm{km}^{-1}$. In this situation, the power required to create a soliton reduces to $P_0 = 8.3$ mW. Thus, fundamental solitons can be generated at power levels that are easily obtainable from conventional laser diodes. The first experimental observation of soliton propagation in optical fibers was reported in 1980 by Mollenauer, Stolen and Gordon.

Note that all the higher-order solitons ($N > 1$) execute a recurrent deformation during their propagation, as illustrated in Figure 6 in the case of the second-order soliton ($N = 2$).

Dark Solitons

In the normal dispersion regime ($\beta_2 > 0$) the chirps induced by GVD and SPM reinforce each other and thus make the hyperbolic secant pulse more susceptible to temporal broadening. Thus, in the normal dispersion regime bright solitons cannot propagate. However, in this case the NLS equation, eqn [5], admits a hole-soliton solution. In other words, the intensity profile of this soliton exhibits a dip in a uniform background, as represented in Figure 7.

Mathematically, this hole-soliton, commonly called a dark soliton, takes the following form:

$$A(z,t) = \pm\sqrt{P_0}\,\tanh(t/\delta_0)\,\exp(\mathrm{i}\gamma P_0 z) \qquad [18]$$



Figure 6 Temporal evolution of the power of a second-order soliton, as a function of the propagation distance. The simulation parameters are the following: input peak power $P_0 = 267$ mW. The fiber parameters are the same as in Figure 5. The nonlinear length is $L_{\mathrm{NL}} = 1.25$ km.



Figure 7 Temporal evolution of the power of a dark soliton, as a function of the propagation distance, for an input peak power $P_0 = 67$ mW.

As eqn [18] shows, the amplitude of the dark soliton is given by an odd function of time. Thus its phase exhibits an abrupt π jump at the dip center, thus implying that dark solitons are chirped. The phase between each jump is constant. Note that there exist other soliton solutions that are similar to the dark soliton, but for which the intensity at the dip center does not fall to zero and the phase variation is more gradual and smaller. These solutions are often called gray solitons.

A common feature of bright and dark solitons is their robustness. This property is very important for ensuring practical applications in optical communications. Moreover, optical solitons emerge unchanged from collision processes. However, dissipative perturbations such as material loss or Raman scattering can destroy such solitons.

Dispersion-Managed Solitons

As we mentioned above, the fundamental soliton is based on a delicate balance between dispersion and nonlinearity, through the relation $L_{\mathrm{D}} = L_{\mathrm{NL}}$. In addition, the existence of this soliton requires that only these two effects are present in the fiber. But in practice, additional linear and nonlinear effects such as fiber losses, Raman scattering, or third-order dispersion, are always present in the fiber. In particular, the fiber losses cause the soliton power to continually decrease during the propagation. The use of lumped amplifiers along the transmission line allows one to compensate for the power loss, but does not prevent the occurrence of chirp. As a consequence, the fundamental soliton does not survive over long distances (a few tens of kilometers), without in-line control. Moreover, this soliton is not stable against phenomena such as CPM and FWM processes that occur unavoidably in WDM systems. The CPM between the pulses in a given channel and the pulses in other channels induce a frequency chirp (in the considered channel), which is converted into amplitude variations by the fiber dispersion. The FWM induces energy-exchange processes between different channels, which lead to pulse distortions.

A new transmission scheme, called *dispersion management*, was recently proposed to resolve the above-mentioned limitations. Basically, the dispersion-management technique utilizes a transmission line with a periodic dispersion map, such that each period is built up by two types of fibers, generally with different lengths and opposite group-velocity dispersion. Whereas the fundamental soliton requires total cancellation of the chirp at each propagation distance, the dispersion-managed (DM) soliton induces a small variation of the chirp, with a zero mean value over each period of dispersion management.

The DM soliton exhibits major differences with respect to the fundamental bright soliton. First, whereas the fundamental bright soliton possesses a smooth profile (as Figure 5 shows), the profile of the DM soliton exhibits an internal oscillatory structure, with several side-lobes on each side of the soliton's center. A typical representation of a DM-soliton profile is shown in Figure 8, at the free-chirp point of the dispersion map. Another outstanding difference is the following: whereas the fundamental soliton propagates with a constant profile, the DM soliton executes a periodic deformation, with a period that coincides with that of the dispersion map. The minimum value of the soliton's width occurs at the free-chirp point. From this point, the soliton's width can execute several oscillations within one dispersion map, with a peak value that can be quite large compared with the width at the free-chirp point. Figure 9 illustrates the propagation of a DM soliton within one dispersion map of a lossless DM line.



Figure 8 Plot showing the profile of a DM soliton at the free-chirp point of a typical DM line made up of 20.5 km of anomalous-dispersion fiber [$\beta_2 = -1.5\times10^{-3}\ \mathrm{ps^2\,m^{-1}}$, $\gamma = 1.4\times10^{-3}\ \mathrm{W^{-1}\,m^{-1}}$], and 19.5 km of normal-dispersion fiber [$\beta_2 = 1.5\times10^{-3}\ \mathrm{ps^2\,m^{-1}}$, $\gamma = 1.4\times10^{-3}\ \mathrm{W^{-1}\,m^{-1}}$].



Figure 9 Plot showing the evolution of the DM soliton's profile as a function of the propagation coordinate *z*.

Recent experiments have demonstrated that in this new transmission scheme the pulse propagation becomes much more stable than fundamental solitons against linear and nonlinear effects such that SPM, FWM, CPM, or third-order dispersion. The DM transmission lines are currently subject to intense research with a view both to upgrade the capacity of existing terrestrial networks, and to design submarine fiber systems with ultrahigh capacity.

Modulational Instability

In optical fibers, the interaction between nonlinear and dispersive effects may lead to modulational instability (MI), a phenomenon in which a continuous or quasicontinuous wave undergoes a modulation of its amplitude or phase in the presence of noise or any other small perturbation. The perturbation can originate from quantum noise (spontaneous-MI) or from a frequency shifted signal wave (induced-MI). MI was observed for the first time by Tai, Hasegawa and Tomita in 1986 for a single pump wave propagating in a standard nonbirefringent fiber (scalar MI). Scalar MI occurs only when the group velocity dispersion (GVD) is negative (anomalous dispersion regime). Modulational instability in eqn [5] is examined through a linear stability analysis (LSA) of its steady state solution

$$A = \sqrt{P_0}\exp[\mathrm{i}\gamma P_0 z] \tag{19}$$

Equation [19] shows that the power remains constant through propagation along the fiber. The linear stability of the steady state solution is examined by looking into the system in the presence of small amplitude and phase perturbations a; that is, we consider

$$A = (\sqrt{P_0} + a)\exp[\mathrm{i}\gamma P_0 z] \tag{20}$$

Then, the linearization of the NLSE with respect to a yields

$$\frac{\partial a}{\partial z} + \frac{\mathrm{i}}{2}\beta_2\frac{\partial^2 a}{\partial t^2} = \mathrm{i}\gamma P_0(a + a^*) \tag{21}$$

Then one can assume for the perturbation a modulational ansatz with wavenumber K and frequency Ω, of the form

$$a(z,t) = u\cos(Kz - \Omega t) + \mathrm{i}v\sin(Kz - \Omega t) \tag{22}$$

Substitution of eqn [22] into eqn [21] leads to the following dispersion relation for the perturbation

$$K^2 = \frac{\beta_2^2\Omega^2}{4}\left[\Omega^2 + \frac{4\gamma P_0}{\beta_2}\right] \tag{23}$$

The MI phenomenon manifests itself by an exponential growth of the amplitude of the perturbation. This behavior occurs when the wavenumber K possesses a nonzero imaginary part. The dispersion relation [23] clearly shows that MI strongly depends on the sign of the dispersion. For normal dispersion ($\beta_2 > 0$), K is always real and the steady state is stable, whereas in the anomalous dispersion regime, MI appears for $\Omega < \Omega_c = \sqrt{4\gamma P_0/|\beta_2|}$. The importance of the phenomenon is measured by a power gain defined by

$$g(\Omega) = 2|\mathrm{Im}(K)| = |\beta_2|\Omega\sqrt{\Omega_c^2 - \Omega^2} \tag{24}$$

Figure 10 shows the MI-gain spectra at three power levels with fiber parameters appropriate for standard silica fibers at $\lambda_0 = 1.319\ \mu\mathrm{m}$.

The peak value of the gain, $g_{\max} = 2\gamma P_0$, occurs at a frequency

$$\Omega_{\mathrm{opt}} = \sqrt{\frac{2\gamma P_0}{|\beta_2|}} \tag{25}$$

called the optimal modulational frequency. In practice, when the perturbation corresponds to quantum noise, the spectral components that are amplified by the MI-process are close to Ω_{opt}. Here, as shown by Figure 11, the MI phenomenon leads to two sidebands that are situated symmetrically with respect to the pump, at frequency detunings of $\approx \pm\Omega_{\mathrm{opt}}$ (see Figure 10 for a pump peak power $P_0 = 3$ W).

In the time domain, induced-MI leads to the break-up of the quasi-cw pump wave into a train of ultrashort pulses. The repetition rate of the pulses is determined by the frequency detuning between the signal and the pump (i.e. the modulational frequency). The temporal shape of these ultrashort pulses depends not only on the powers



Figure 10 Spectral profiles of MI gain g for a pump peak power $P_0 = 1$ W (solid), 3 W (dashed) and 10 W (dot-dashed). The fiber parameters are $\beta_2 = -3.5\ \mathrm{ps^2\ km^{-1}}$ and $\gamma = 1.9 \times 10^{-3}\ \mathrm{m^{-1}W^{-1}}$.



Figure 11 Spontaneous modulational instability spectrum (i.e., parametrically amplified spontaneous noise), as obtained for a peak pump power $P_0 = 3$ W and a fiber length $L = 1$ km. The fiber parameters are the same as in Figure 10.



Figure 12 (a) Theoretical temporal evolution of the power for induced-MI, as a function of the propagation distance. (b) Output power spectrum in logarithmic intensity scale. The pump (signal) power is 3 W (0.5 mW), the pump-signal frequency detuning is 0.34 THz, and the fiber length is 1 km. The fiber parameters are the same as in Figure 10.

of the input waves but also on the modulational frequency. In particular, trains of bright and dark solitons with a terahertz repetition rate have been generated by MI in optical fibers. Figure 12a shows theoretically the evolution of a small initial modulation.

As Figure 12a shows, MI causes a small initial perturbation to evolve into a periodic pulse train, whose period is inversely proportional to the frequency spacing Δf between the pump and signal waves. Thus the technique of induced-MI can be exploited for generating high-repetition-rate ultrashort pulse trains. As shown in Figure 12b, such pulse train generation manifests itself in the frequency domain by the growth of a cascade of sidebands. The number of harmonics ($n\Delta f$) is determined by the temporal shape of the generated pulses and the initial conditions at the fiber input.

Cross-phase modulation (CPM) between two modes can be used to extend the instability domain to the normal dispersion regime (positive GVD). This is achieved by using orthogonally polarized pump waves. This CPM-induced MI is called vector modulational instability. The optical field evolutions are described by two coupled NLS equations. Several experiments involving two polarization modes, or two spatial modes, have been done in order to observe MI in the normal GVD regime.

Conclusion

The invention of soliton transmission, predicted in 1973 and experimentally demonstrated in 1980, is one of the major discoveries made in the area of optical telecommunication. Although from the period of invention of optical solitons up to very recent years the main line of research activities was based on the concept of the ‘classical soliton’, which represents an exact balance between the fiber group-velocity dispersion and its intensity-dependent refractive index, most recent experimental and theoretical developments focus on dispersion-managed solitons. It is now widely recognized that DM solitons in fiber-optic links are the most promising way both to upgrade the capacity of existing terrestrial telecommunication networks and to design submarine fiber systems. Most of the current research and development activities in this context aim to develop a non-empirical methodology of designing ultrahigh-speed DM fiber systems.

List of Units and Nomenclature

Dispersion length L_D [m]
Group velocity dispersion coefficient β_2 [$\mathrm{ps^2\,km^{-1}} = 10^{-27}\,\mathrm{s^2\,m^{-1}}$]
Nonlinear length L_{NL} [m]
Nonlinear parameter γ [$\mathrm{W^{-1}\,m^{-1}}$]
Nonlinear refractive index n_2 [$\mathrm{m^2\,W^{-1}}$]
Optical intensity I [$\mathrm{GW\,cm^{-2}} = 10^9\,\mathrm{W\,cm^{-2}}$]

CPM: cross-phase modulation
DM Soliton: dispersion-managed soliton
FWM: four-wave mixing
GVD: group velocity dispersion
LSA: linear stability analysis
MI: modulational instability
NLS (E): nonlinear Schrödinger (equation)
SPM: self-phase modulation
WDM: wavelength division multiplexing

See also

Fiber and Guided Wave Optics: Dispersion; Light Propagation; Nonlinear Effects (Basics). **Lasers:** Optical Fiber Lasers. **Scattering:** Scattering Theory. **Solitons:** Soliton Communication Systems.

Further Reading

Ablowitz MJ and Clarkson PA (1991) *Solitons, Evolution Equations and Inverse Scattering*. Cambridge, UK: Cambridge University Press.
Agrawal GP (1997) *Fiber-Optic Communication Systems*. New-York: Wiley-Interscience.
Agrawal GP (2001) *Nonlinear Fiber Optics*. San Diego, CA: Academic Press.
Agrawal GP (2001) *Applications of Nonlinear Fiber Optics*. San Diego, CA: Academic Press.
Hasegawa A (1989) *Solitons in Optical Fibers*. New-York: Springer Verlag.
Hasegawa A and Kodama Y (1995) *Solitons in Optical Communications*. Oxford, UK: Clarendon Press.
Remoissenet M (1999) *Waves Called Solitons, Concepts and Experiments*, 3rd edn. Berlin: Springer.
Taylor JR (ed.) (1992) *Optical Solitons – Theory and Experiment*. Cambridge, UK: Cambridge University Press.
Zakharov VE and Wabnitz S (eds) (1999) *Optical Solitons: Theoretical Challenges and Industrial Perspectives*. Les Ulis (France) and Berlin (Germany): EDP Sciences and Springer.

Soliton Communication Systems

M Karlsson and P Andrekson, Chalmers University of Technology, Gothenburg, Sweden

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In 1973 Hasegawa and Tappert proposed that optical soliton pulses in fibers could exist. A soliton is a propagating wave packet that is localized in the sense that it does not spread its energy during propagation, and with the additional property that it is so stable that it can collide with other solitons and emerge unaffected with respect to energy, shape, and momentum after the collision. Solitons are based on some kind of nonlinearity in the system, and for optical fibers the weak Kerr nonlinearity (which makes the refractive index increase in proportion to the optical intensity) can counteract the pulse broadening induced by group-velocity dispersion (GVD). The two effects can form a stable balance in the form of a soliton pulse, which then propagates without changing shape.

Due to the lack of short-pulse laser sources at wavelengths above 1.3 μm, and low-loss silica fibers, it took another seven years for optical soliton pulses to be experimentally verified. In an experiment by Mollenauer, Stolen, and Gordon in 1980, soliton pulse transmission over 700 m fiber was demonstrated. During the 1980s soliton research aimed towards the use of solitons as information carriers in optical communications, and in 1990 the first data transmission experiment using solitons (2.8 Gb/s over 23 km of fiber) were reported by Iwatsuki *et al.*

During the 1990s, soliton-based communication systems have matured, an important reason being the development of the erbium-doped fiber amplifier (EDFA), which made high power levels commercially available. The most recent developments have been towards the use of solitons in alternating dispersion maps (so-called dispersion management), and such systems have reached performance levels near commercialization.

It should be stressed that fiber soliton research has been almost exclusively devoted to single-mode fibers at a wavelength of 1550 nm. In principle, solitons can also be used to counteract mode dispersion in multimode fibres, but that generally requires unrealistically high peak powers, and is therefore regarded to be of less interest. Similarly, solitons with wavelengths around 1300 nm in single-mode fibers have been considered, but found to be of less interest due to the lack of low-noise optical amplifiers in this spectral range. Another kind of soliton, the so-called dark soliton, can also be generated in single-mode fibers. However, dark solitons have only been used as information carriers in a very limited number of experiments, and will also be omitted from this discussion.

In the present review we will discuss both theoretical and experimental aspects of soliton transmission. We will distinguish between conventional solitons, which have constant dispersion during transmission, and dispersion-managed solitons (although solitary waves would be the proper mathematical name) for which the dispersion varies periodically during transmission.

Conventional Fiber Solitons

Group-velocity dispersion means that the group velocity of the light changes with the optical frequency, and it is usually defined as the second derivative of the propagation constant β with respect to the angular frequency ω, and denoted β_0'' [ps^2 km^{-1}]. Standard single-mode fibers have a $\beta_0'' \approx -20$ [ps^2 km^{-1}] around a wavelength of 1550 nm, whereas dispersion-shifted fibers (DSFs) have β_0'' close to zero in the 1550 nm region. The dispersion is defined with respect to sign, so that the GVD is said to be normal if the group velocity decreases with frequency (i.e., $\beta_0'' > 0$), and anomalous if the group velocity increases with frequency (i.e., $\beta_0'' < 0$). A pulse propagating in a dispersive fiber will broaden with propagation distance at a rate proportional to the product of β_0'' and the spectral width of the pulse. In a communication system such a broadening is devastating, since neighboring pulses will interfere and disperse power into adjacent bit slots. The problem is increased for high data rates (as this requires short pulses with broad spectra) and/or long transmission distances.

The nonlinearity in optical fibers manifests itself as a dependence of the refractive index with power, and is known as the optical Kerr effect. For pulse propagation the Kerr effect will give rise to self-phase modulation (SPM), which means that the pulse will get a phase modulation proportional to its own intensity. Mathematically speaking, the amplitude of an optical pulse $u(0, t)$ [W$^{1/2}$] launched at $z = 0$ will evolve according to $u(z,t) = u(0,t) \exp(-\mathrm{i}\gamma z|u(0,t)|^2)$, where γ [W^{-1} km^{-1}] is the nonlinear coefficient of the fiber, z [km] is the propagation distance along the fiber, t [ps] is the time coordinate, and $|u(z, t)|^2$ [W] is the power level of the light. The value of γ varies between different fiber types due to the dependence on the core area of the fiber, but for standard single-mode fibers, in the 1550 nm region, it is approximately 2.2 km^{-1} W^{-1}.

Taking both self-phase modulation and dispersion into account, one can derive a propagation equation for light, known as the nonlinear Schrödinger (NLS) equation. Of particular importance for the solution to the NLS equation is solitons, which is a solution that propagates without dispersive broadening. The soliton solution arises as a result of a cancellation of the dispersion and the self-phase modulation effects, and it can only be formed when the dispersion is anomalous. For normal dispersion the nonlinearity and the dispersion will instead act together to increase the spectral broadening of the pulse. The soliton solution of duration t_0 and dispersion β_0'' reads

$$u_{\mathrm{sol}}(z,t) = \sqrt{\frac{1}{\gamma L_{\mathrm{D}}}}\,\mathrm{sech}\left(\frac{t}{t_0}\right)\exp\left(-\mathrm{i}\frac{z}{2L_{\mathrm{D}}}\right) \qquad [1]$$

where the dispersive length is $L_{\mathrm{D}} = t_0^2/|\beta_0''|$ [km]. The soliton peak power P_{s} [W] and energy E_{s} [J] can be expressed as $P_{\mathrm{s}} = |u_{\mathrm{sol}}(z,0)|^2 = |\beta_0''|/\gamma t_0^2$ and $E_{\mathrm{s}} = 2P_{\mathrm{s}}t_0 = 2|\beta_0''|/\gamma t_0$.

The fact that solitons are not broadened by dispersion will make them ideally suited as information carriers in a communication system. However, the solitons are affected by various perturbations that will affect the balance by dispersion and nonlinearity. Unless proper care is taken in the design of the system, those perturbations can destroy the performance of the communication system. Next, we will review the most important perturbations and design issues of soliton-based communication systems.

Solitons in the Presence of Third-Order Dispersion

The third-order dispersion (TOD), or the dispersion slope, is modeled with the derivative of the GVD, β_0'' [ps^3 km^{-1}], which is typically 0.1 ps^3 km^{-1} in standard and dispersion-shifted fibers. For solitons in dispersion-shifted fibers the effect of the dispersion slope is increasingly important the closer the solitons are to the zero dispersion wavelength.

When a soliton is placed close to the zero-dispersion wavelength, it will emit radiation in the normal dispersion regime of the spectrum, lose energy, and recoil further into the anomalous dispersion region so that the radiation stops and a stable soliton is formed. As a design criterion $\beta_0'''/(|\beta_0''|t_0) < 0.24$ have been suggested for this phenomenon to provide negligible energy loss.

Solitons in the Presence of Amplification and Loss

The most important property that has been neglected in the derivation of the NLS equation for optical pulses is the effect of loss. The loss will decrease the power and hence the nonlinearity so that the balance sustaining the soliton is no longer maintained. As a result of the loss (which is of the order of 0.2 dBkm^{-1} in standard transmission fibers) the soliton pulse will be broadened. Partly, this can be circumvented by requiring the launched peak power of the soliton after each amplifier to be such that the path-average power between the amplifiers equals the soliton power, P_s. The peak power P_{peak} falls off as $\exp(-\alpha z)$, where $\alpha = 0.042\ \text{km}^{-1}$ is the fiber loss coefficient, and the average peak power over one amplifier span is then $P_{\text{peak}}\ (1 - \exp(-\alpha L_a))/\alpha L_a = P_{\text{peak}}(G - 1)/G\ \ln(G) = P_s$, where $G = \exp(\alpha L_a)$ is the gain of each amplifier and L_a [km] is the amplifier spacing.

Nevertheless the periodic fluctuation of power and width over each amplifier length may cause the solitons to become unstable and lose power to dispersive wave radiation. To minimize this loss a useful design criterion is that the amplifier length L_a should be smaller than the dispersive length, L_D.

Sources of Timing Jitter

Another transmission obstacle is the various sources of random movement of the pulse in the bit slot, i.e., timing jitter of the pulses in the data transmission link. There are various sources of timing jitter, e.g., soliton interaction, Gordon–Haus, acoustic, and wavelength division multiplexing collision induced jitter.

Soliton interactions

Solitons, being nonlinear pulses, will interact with adjacent pulses in the pulse train. The interaction between solitons of the same polarization state and wavelength is phase sensitive so that in-phase solitons will attract each other whereas out-of-phase solitons will repel each other. To reduce this effect the solitons must be sufficiently spaced in the data stream. A typical design condition is that the pulse width of the solitons are one fifth of the bit slot, or one fifth of the inverse bit rate. A straightforward way of reducing the interaction is to have alternating amplitudes of the soliton in the pulse train, and the solitons can then be packed more densely.

Orthogonally polarized solitons interact substantially less, since it is the intensity overlap that causes the interaction, rather than the amplitude overlap as for copolarized solitons. In polarization multiplexed systems where adjacent pulse have orthogonal polarization it is usually enough with half the above separation, i.e., a pulse duration of 2.5 less than the bit separation.

Gordon–Haus jitter

Noise from the in-line amplifiers will give rise to a small jitter in the carrier frequency of each soliton, which, via the dispersion, will alter the group velocity and hence affect the arrival time of each pulse. This is known as the Gordon–Haus effect, and it has to be accounted for in long-distance systems. The variance of the timing jitter is proportional to the ratio of the power spectral density of the noise to the energy of the soliton, and also proportional to the transmission distance cubed. The fact that Gordon–Haus jitter grows cubically with distance makes it particularly important at transoceanic lengths, typically exceeding 1 Mm.

Acoustic jitter

The electrostriction nonlinearity in the fiber gives rise to a mechanical pressure proportional to the optical intensity, which in turn modifies the refractive index of the fiber. In particular, an intense optical pulse like a soliton will give rise to a pressure (acoustic) wave moving radially outwards from the fiber center. The pulses in the wake of this wave will experience a randomly changing local refractive index, and hence (just as for Gordon–Haus jitter) a randomly changing carrier frequency that transforms into a timing jitter. The variance of this jitter will grow as the transmission distance to the power of four.

WDM Considerations

Wavelength division multiplexing (WDM) is another way of increasing the bit-rate of soliton systems. That is, several frequency channels are used for solitons transmission. The problem with WDM transmission using solitons stems mainly from collisions between solitons in the different wavelength channels. In a perfectly ideal NLS equation solitons would collide elastically without changing carrier wavelength. However, the presence of losses and amplification may cause the collisions to be asymmetric if they occur around an amplifier, and the result will be a frequency displacement and a concomitant timing jitter.

Soliton Control

Soliton control is the common name for methods to control the soliton parameters such as wavelength and position, mainly in order to reduce the deleterious timing jitter effects. There are two different approaches: passive and active control.

Passive soliton control has been suggested in the form of filters that are inserted along the transmission path. This helps to keep the soliton wavelength fixed. In this way not only Gordon–Haus and acoustic jitter can be remedied, but also interaction jitter and

WDM-collision-induced jitter. A problem with this kind of filtering is that it defines a spectral region with excess gain, in which amplifier noise will grow excessively. A way around that problem is to slightly shift the center wavelength of the filters along the transmission path. In that way the solitons will follow the frequency shift, but the linear noise will not. Such sliding filter experiments have demonstrated 8 × 10 Gb/s WDM soliton transmission over 10 Mm.

Active control usually acts in the time domain by using phase or amplitude modulators to retime and reshape the solitons. Using this technique, 10 Gbit/s over unlimited distances has been demonstrated. However, this kind of active reshaping of the pulses suffers from the same drawbacks as conventional electronic regeneration, i.e., incompatibility with WDM, complexity, and high cost.

Dispersion-Managed Solitons

Introduction

In the last years of the 1990s, solitons have become substantially more attractive through the rapidly emerging strategy of improving the performance of soliton transmission with dispersion management (DM). While the DM strategy, which involves altering the local dispersion between a large positive and a large negative GVD such that the average GVD is small, has long been used in linear systems, it was only relatively recently appreciated that the same technique, if properly implemented, gives rise to several very striking improvements over conventional soliton transmission systems. While DM-solitons are clearly nonlinear pulses they are by no means classical solitons.

From a commercial viewpoint, however, the most important benefit with using DM-solitons is that they, in principle, can use the already installed conventional fibers (with zero dispersion at 1300 nm) allowing a much more cost-effective upgrade together with dispersion-compensating fibers (DCF) or chirped fiber gratings, which can be located together with in-line amplifiers at certain intervals in the link.

In Figure 1, an example of breathing in spectral and temporal widths of a DM-soliton can be seen, together with its dispersion map at the bottom.



Figure 1 Plot of the spectral width (top), temporal width (middle), dispersion map (bottom) of a dispersion-managed soliton in the lossless case (left column) and the lossy case that is periodically amplified (right column). The positions of the amplifiers are denoted by the small triangles in the plot of the dispersion map.

Two cases are shown; one without fiber attenuation (left column) and one including fiber losses and periodic, lumped amplification every 60 km. One may note the strictly periodic behavior of both the spectral and temporal widths in both cases, and that the evolution of the spectral width is significantly different in the lossy case. This is because a change of the pulse spectrum requires nonlinearities and high power, and the spectral broadening is therefore highest directly after the amplifiers.

Properties

DM-solitons emerged from extensive simulation work, and it was quite surprising to many researchers that the simulations revealed such stable and strictly periodic pulses. The periodicity follows that of the dispersion variation of the system. Usually the system under study has a dispersion map, i.e., a plot of how the GVD varies along the transmission path. The map has a characteristic period (typically 10–100 km) and an average GVD which is significantly lower than the local GVD in the map.

As a result of the massive simulation work done by many groups the following properties of DM-solitons have been found:

- The pulse width, chirp, and spectral width oscillates periodically in the dispersion map. There are two points within the period at which the pulse is chirp-free, and those correspond to local minima of the pulse width. One of those points is the global minimum width, referred to as the 'shortest pulse' below.
- A central parameter that is useful for the characterization of DM-solitons is the map strength, $S = (L_1|\beta_1''| + L_2|\beta_2''|)T_{\mathrm{FWHM}}^2$, where L is the length, β'' is the dispersion, T_{FWHM} is the minimum pulse width in the full width half maximum sense, and the subscripts 1 and 2 refer to the two fibers in the dispersion map. In this example we thus assume the map to consist of two fibers, one with normal and one with anomalous dispersion. Physically the map strength is the number of dispersive lengths the pulse propagates in one period. DM-solitons have been found for map strengths ranging from $S = 0$ (which is the same as conventional solitons) to $S \approx 12$, although this upper limit is a transition regime in which the pulses radiate and perfect periodic evolution never arises.
- DM-solitons have been found for anomalous, normal, and zero average dispersion β'', defined as $\beta_0'' = (L_1\beta_1'' + L_2\beta_2'')/(L_1 + L_2)$. Normal average dispersion is only possible for map strengths above 3.9.
- The shortest pulse shape ranges from hyperbolic secant at $S = 0$ to Gaussian for higher map strengths, and this is also evident from the time-bandwidth product, which increases with S from 0.32 (sech-shape) at $S = 0$ to 0.44 (Gaussian shape) and even higher for large values of S. In addition, the shortest pulse has oscillating tails in the wings.
- The energy of a DM-soliton pulse is enhanced relative to a soliton with the same average dispersion and pulse width.
- The interaction between DM-solitons is less than that of conventional solitons, and an optimum map strength exists that minimizes the interaction.

The fact that DM solitons can work for an average net zero GVD and even for normal dispersion, was a striking and unexpected difference from conventional solitons. This can be understood by the fact that the spectrum is widest in the anomalous dispersion regime (i.e. positive values of the dispersion parameter D, cf. Figure 1), and it has been conjectured that the average dispersion, weighted by the spectral width of the DM-soliton, should always be anomalous. This is then a generalization of the fact that conventional solitons must always have a constant anomalous dispersion.

The technical improvements with DM solitons over conventional ones are numerous. The signal-to-noise ratio is improved since the DM-solitons have a larger peak power than the corresponding conventional solitons. DM-solitons have less Gordon–Haus and acoustic timing jitter, since the system average GVD is much smaller in these systems. A very important added benefit appears in WDM systems. Due to the alteration between large positive and negative GVD along the path, the jitter induced from WDM-soliton collisions is greatly reduced. This, in turn, allows for very dense WDM which will improve the spectral efficiency substantially.

An important practical consequence of using DM-solitons is that they reduce (or eliminate) the need for in-line soliton control such as synchronous modulation or sliding filters. Yet soliton control methods are still applicable and will give improvement in terms of signal-to-noise ratio for DM-solitons as well.

Quite impressive circulating loop experiments including WDM have been reported. For example, 51 densely packed WDM channels each operating at 20 Gb/s were transmitted over 1000 km with 100 km sections of standard fiber, clearly demonstrating the strength of the DM soliton technique.

Quasi-linear Transmission Intrachannel Impairments

As a rule, map strengths in the range 1–8 make best use of the unique features of DM-solitons. This means that the use of installed standard fiber becomes difficult at very high bit-rates (say beyond 30–40 Gb/s) as shorter pulses require a more rapidly (sub-km) varying dispersion map to maintain a proper S-value. If this cannot be maintained, i.e. for S values significantly above 10, one reaches the quasi-linear regime, in which the dispersion significantly dominates the transmission.

In the quasi-linear regime, there are a couple of nonlinear transmission impairments that need to be accounted for and analyzed in more detail. They are the so-called intra-channel effects; intra-channel four-wave mixing (ICFWM), and intra-channel cross-phase modulation (ICXPM), and arise due to the nonlinear interaction between two neighboring pulses. Four-wave mixing (FWM) and cross-phase modulation (XPM) are usually effects associated with WDM transmission. However, the fact that the pulses are chirped and broadened, will cause different frequency components from neighboring pulses within the same wavelength channel to overlap in time, thereby causing FWM and/or XPM within the same channel.

ICFWM arises for two neighboring pulses that, via four-wave mixing (FWM), creates new frequency components that in the time domain will give rise to a new pulse (commonly referred to as a ghost pulse), next to the two. The ghost pulse will then give rise to intersymbol interference and reduction of the eye opening. ICFWM is most prominent for large map strengths and high power.

ICXPM can be viewed as pulse-to-pulse interaction, and physically, it manifests as the frequency shift of one pulse induced by the presence of a neighboring pulse, which, by the dispersion transforms into a timing jitter. The effect can be minimized by selecting proper map strength and pre-chirp of the pulses.

Finally it should be emphasized that these intra-channel impairments will affect also non-soliton systems (e.g., non-return-to-zero (NRZ) modulated systems) if the nonlinearities are significant.

Experiments and Field Trials

Soliton Pulse Sources

When doing soliton experiments, be it conventional or DM-solitons, particular importance is placed on the properties of the pulse source, as it sets the lower limit of the system performance. A high bit-rate soliton pulse source needs to produce low-chirp, low timing-jitter pulses with proper duration (in the ps regime), repetition rate (10–40 GHz), and shape.

One possible choice is gain-switched (GS) laser diodes, possibly with an external cavity for tunability. However, they suffer the drawback of producing pulses that are strongly chirped, asymmetric and often too wide.

For laboratory experiments, fiber ring lasers (FRL) are very attractive, as they provide wavelength and pulse width tunability, besides meeting the above demands. Their drawback is that they are bulky, need active stabilization, and sometimes also temperature control to achieve long-term stability.

Finally it appears quite clear that electro-absorption modulators (EAM), which can be integrated or not with a distributed feedback (DFB) laser, are very useful and simple sources for soliton transmission. While such sources were developed for linear NRZ systems, they have now proven to be near ideal in soliton systems as well. Although EAMs are not commercially available at 40 GHz yet, they are likely to be so soon.

Special considerations need to be taken in DM-soliton systems, however, as the launch condition is different from that for conventional solitons. The pulses should have a linear chirp such that it fits seamlessly in the periodically induced chirp variation along the link. This can be achieved by incorporating a proper length of fiber (or chirped fiber grating) in the transmitter once the overall dispersion map is known.

Loop Experiments

In order to investigate really long distances (megameters) of transmission, loop experiments were developed in the early 1990s. This means that the data pulses are injected in a loop consisting of transmission fiber and amplifier, and then left to propagate a number of laps corresponding to a certain transmission distance. Acousto-optic switches are used to switch the pulse train in and out from the loop at proper time intervals. The drawback of loop experiments is that they may be poor models of reality when it comes to things like dispersion variation along the fiber, polarization mode dispersion (PMD), or various kinds of drift that may arise. In addition, a real system has more options to fine tune, e.g., amplifiers along the transmission line. However, as long as these drawbacks are recognized, loop experiments are very powerful indeed, and invaluable in laboratory evaluations of long-distance transmission.

Field Trials

In the field, there are many transmission link design restrictions and fiber properties which make the systems far from optimal. The actual fiber parameters are nonperiodic with propagation distance as the systems are straight lines rather than relatively short loops. Both loss (in particular when including many contacts and splices along the link) and dispersion might vary significantly along a fiber span. In addition, it may not be possible to tailor the dispersion map and amplifier locations to reach an optimal state. All these examples of nonidealities justify the need for field experiments.

Several soliton field experiments have been conducted over the past few years in Japan by NTT, in the US by MCI/Pirelli, as well as in Europe by ACTS projects, and the results from those experiments are discussed below. It is a good indication that solitons are indeed foreseen as very interesting candidates in commercial systems. Again, it is not very easy to compare the results as the situation in each case differs. All of the systems operated in the 1550 nm range, used optical time division demultiplexing with a 10 Gb/s electronic base rate, and the average loss/km ranged from 0.24 to 0.33 dB/km. Dispersion-shifted fiber was always used, apart from in two cases, where standard fiber was used. One field trial has used DCF for dispersion compensation, which makes this the only DM-soliton field experiment to date.

Polarization multiplexing, for which adjacent pulses have orthogonal polarization, have been used in a few experiments and this serves mainly to allow the use of relatively wide pulses, which in turn allows for larger amplifier spans. Polarization-multiplexing, however, is not as useful if the PMD of the system is high, as then the orthogonally polarized pulses would start to drift statistically in time relative to each other, thereby creating intersymbol interference and increasing the soliton interaction. In the 40 Gb/s cases and above, PMD was found to be the main capacity limiting factor.

Most of the recent experiments used a mode-locked fiber ring laser as a source, mainly because these provide excellent pulse quality as well as tunability in terms of wavelength and pulse width. Other experiments used either gain-switched lasers or electro-absorption modulators.

Future soliton field trials are expected to (1) take advantage of the now well-known strategy of improving soliton transmission performance with dispersion-management, this being very attractive for upgrading existing fiber plants, (2) implement dense WDM (in fiber lines that do not contain dispersion-shifted fibers) to boost aggregate capacity, (3) utilize different forms of in-line control, particularly at high bit rates, and (4) further address the implications of PMD and techniques to combat it. The interesting trade-off between wavelength and time division multiplexing (WDM–TDM) for optimization of overall aggregate capacity will depend on the details of the fiber line parameters.

Future Outlook

To conclude, we note that the motivation for using solitons as information carriers has changed over the years. The property of being resistant to dispersive broadening was originally the main feature, but this was considered less important when dispersion-compensating fibers became commercially available. Instead, this led to the development of the dispersion-managed soliton. The advantages of the DM-soliton over linear transmission are features like the large power which gives a high signal-to-noise ratio. On the other hand, the difference between linear and nonlinear pulses is becoming increasingly fuzzy, and perhaps the distinction should be made between return-to-zero (RZ) and NRZ modulation rather than between linear and nonlinear transmission.

It is nevertheless interesting to note that solitons are now not only considered for oceanic systems but also for shorter terrestrial systems. There are still several challenges and opportunities remaining in order to take full advantage of solitons and to reach a better understanding. Further work is also needed on WDM soliton- and very high-speed TDM soliton-systems. The use of DM-solitons is a very recently established technique and there are thus many issues to consider. These include studies of robustness to deviations of optimum conditions, e.g., improper pulse launch conditions, the impact of nonperiodic dispersion maps and of PMD (both of which are difficult to study in loop experiments), and intrachannel effects. Nevertheless, solitons have now reached a level of maturity such that commercialization seems very near.

List of Units and Nomenclature

Amplifier gain	G	[−]
Amplifier separation	L_a	[km]
Average dispersion	β_0''	[ps^2 km^{-1}]
Dispersive length	L_D	[km]
Fiber loss coefficient	α	[km^{-1}]
Fiber nonlinear coefficient	γ	[W^{-1} km − 1]
Group velocity dispersion (GVD)	β_0''	[ps^2 km^{-1}]

Map strength	S	$[-]$
Optical field amplitude	$u(z, t)$	$[\mathrm{W}^{1/2}]$
Pulse duration	t_0	[ps]
Soliton energy	E_s	[J]
Soliton peak power	P_s	[W]
Third-order dispersion	β_0'''	$[\mathrm{ps}^3\ \mathrm{km}^{-1}]$
Time	t	[ps]
Transmission distance	z	[km]

See also

Fiber and Guided Wave Optics: Nonlinear Effects (Basics). **Solitons:** Temporal Solitons.

Further Reading

Agarwal GP (1995) *Nonlinear Fiber Optics*, 2nd edn. San Diego: Academic Press.

Agarwal GP (2001) *Nonlinear Fiber Optics*, 3rd edn. San Diego: Academic Press.

Agarwal GP (2001) *Applications of Nonlinear Fiber Optics*. San Diego: Academic Press.

Hasegawa A and Kodama Y (1995) *Solitons in Optical Communications*. Oxford: Clarendon Press.

Iannone E, Matera F, Mecozzi A and Settembre M (1998) *Nonlinear Optical Communication Networks*. New York: Wiley.

Mollenauer LF, Gordon JP and Mamyshev PV (1997) Solitons in high bit-rate long-distance transmission. In: Kaminow IP and Koch TL (eds). *Optical Fiber Telecommunications III A*. San Diego: Academic Press.

Smith NJ and Doran NJ (1995) Evaluating the capacity of phase modular-controlled long-haul soliton transmission. *Optical Fiber Technology* 1: 218–235.

Suzuki K and Nakazawa M (1995) Recent progress in optical soliton communication. *Optical Fiber Technology* 1: 289–308.

Taylor JR (ed) (1992) *Optical Solitons–Theory and Experiment*. Cambridge: Cambridge University Press.

The final report of the ACTS-MIDAS project, Jan 1999, can be downloaded at *www.infowin.org/ACTS/RUS/PROJECTS/FINAL-REPORTS/fr-053.pdf*.

Turitsyn SK, Mezentsev VK and Shapiro EG (1998) Dispersion-managed solitons and optimization of the dispersion management. *Optical Fiber Technology* 4: 384–452.

Temporal Solitons

S Trillo, University of Ferrara, Ferrara, Italy

A Tonello, Université de Bourgogne, Dijon, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The fact that wave propagation phenomena are intrinsically dispersive, that is localized disturbances tend to spread, is part of our experience. Less well known is the fact that the spreading of wavepackets can be counteracted by the nonlinear response of the host medium. Solitons are wavepackets that exploit this principle, realizing a perfect balance of dispersion and nonlinearity that allows them to self-trap and travel undistorded, or at least to recover their shape periodically, for long (virtually unlimited) distances. More specifically, here we deal with optical temporal solitons constituted by envelopes, or pulses with relatively narrow bandwidths around a carrier optical frequency, whose temporal profile remains unchanged (either strictly or on average) upon propagation. In contrast with spatial solitons predicted earlier and such that nonlinearities are exploited to compensate for diffractive beam spreading even in the two transverse dimensions (i.e., in bulk samples, for details the reader is referred to **Solitons:** Bright Spatial Solitons), temporal soliton trapping is intrinsically a one-dimensional phenomenon typically observed in optical fibers where diffraction is compensated by the standard fiber guidance mechanism. Temporal solitons were first predicted and observed in single-mode fibers (SMFs). Their applications in digital optical communications have increased due to their capability to behave as nearly ideal bits. Meanwhile, however, the concept of temporal soliton has been considerably generalized by investigating new settings and effects such as polarization, parametric amplification (*see* **Nonlinear Optics, Basics:** $\chi^{(2)}$-Harmonic Generation), gratings (*see* **Fiber Gratings**), stimulated scattering (*see* **Scattering:** Scattering Phenomena in Optical Fibers), and fiber lasers (*see* **Lasers**: Optical Fiber Lasers), etc. Here we briefly review the essential features of these different families of temporal solitons. In particular, in the section on Fiber Temporal Solitons below, we introduce the basic model for fiber solitons, whereas we discuss their application to optical communications in the section on Solitons in Optical Communications below. In the sections on Multi-component Temporal Solitons, and Temporal Solitons in Bragg Gratings below, we introduce significant generalizations of the concept involving multicomponent and slow-light grating solitons, respectively. Finally, in the section on Solitons on Dissipative nonlinear optics we discuss issues related to solitons in strongly dissipative systems. Note that, throughout the paper, the word soliton is used in the aforementioned general sense, which does not necessarily require the underlying model to be integrable (*see* the section on Fiber Temporal Solitons below,), as implied by the more restrictive and rigorous mathematical meaning of soliton. We further focus our discussion to bell-shaped solitons (for dark solitons, holes on a continuous-wave background, *see* **Solitons:** Optical Fiber Solitons, Physical Origin and Properties), which can be excited by means of standard laser pulses.

Fiber Temporal Solitons

An optical pulse is described by the complex electric-field envelope $E(z, t)$ that modulates the carrier frequency ω_0. Its evolution along the z axis of a silica SMF is described with good approximation by the following universal model for dispersive and weakly nonlinear systems, known as the nonlinear Schrödinger equation (NLSE),

$$\mathrm{i}\frac{\partial E}{\partial z} - \frac{k''}{2}\frac{\partial^2 E}{\partial t^2} + \gamma|E|^2 E = 0 \qquad [1]$$

In eqn [1] the second term is responsible for dispersive spreading of pulses ruled by the group-velocity dispersion

$$k' = \left.\frac{\mathrm{d}^2 k}{\mathrm{d}\omega}\right|_{\omega_0}$$

(GVD, known also as chromatic or second-order dispersion), while the first-order dispersion

$$k' = \left.\frac{\mathrm{d}k}{\mathrm{d}\omega}\right|_{\omega_0}$$

has been removed in eqn [1] by introducing the retarded time $t = T - k'z$ measured in the pulse frame traveling at the natural group-velocity $V \equiv k'^{-1}$ of light, T being the physical time in the laboratory frame. The cubic term in eqn [1] is responsible for self-phase modulation (SPM) that stems from the instantaneous optical Kerr effect characterized by the effective coefficient $\gamma = k_0 n_{2I}/A_{\mathrm{eff}} = (\omega_0/cA_{\mathrm{eff}})n_{2I}$, where n_{2I} is the nonlinear index of silica, i.e., the nonlinear refractive index change divided by the intensity which has produced it. The real-world total electric field can be recovered as $\mathcal{E}(z, r, t) = \mathrm{Re}[f(r)E(z, t)\exp(\mathrm{i}k_0 z - \mathrm{i}\omega_0 T)]$, where the transverse modal profile $f(r)$ has been averaged out in eqn [1] to yield an effective fiber area A_{eff}.

The mechanism behind soliton formation can be understood as due to the instantaneous frequency changes along the pulse caused by the Kerr SPM, compensating those due to the group velocity dispersion (GVD) in the anomalous case ($k'' < 0$, at carrier wavelengths longer than 1.3 μm in standard SMFs) where the GVD induces a blue-shift on the pulse leading edge and a red-shift on the pulse trailing edge (in the absence of such compensation the pulse broadens because anomalous GVD means that blue-shifted frequencies travel faster than red-shifted frequencies). Such mechanism of compensation becomes ideal in the case of a soliton waveform. This concept finds its mathematical support in the fact that eqn [1] is a conservative (Hamiltonian) model with the remarkable property to possess infinite conserved quantities, a rather exceptional feature which makes it exactly integrable. Among the solutions, the following fundamental (so-called $N = 1$, see below) bright temporal soliton exists whenever $k'' < 0$:

$$\begin{aligned} E(z, t) = {} & \frac{1}{\sqrt{\gamma L_{\mathrm{d}}}}\operatorname{sech}[\eta(t - \mathrm{d}k'z - t_0)] \\ & \times \exp\left[-\,\mathrm{i}\delta\omega t + \frac{\mathrm{i}}{2}\left(\frac{1}{L_{\mathrm{d}}} + k''\delta\omega^2\right)z + \mathrm{i}\phi_0\right] \end{aligned} \qquad [2]$$

where t_0 and ϕ_0 are arbitrary initial position and phase, and $L_{\mathrm{d}} = (k''|\eta^2)^{-1}$ is the characteristic distance after which the GVD causes a significant pulse broadening, the so-called dispersion length. Temporal solitons [2] are characterized by two independent parameters, namely the duration $1/\eta$ and the frequency detuning $\delta\omega$, and possess several remarkable features:

(i) they travel with invariant shape by realizing the condition $N \equiv L_{\mathrm{d}}/L_{\mathrm{nl}} = 1$, i.e., exact balance between the two length scales associated with eqn [1], namely L_{d} and the nonlinear length $L_{\mathrm{nl}} = (\gamma P_1)^{-1}$ associated with the peak power $P_1 = (\gamma L_{\mathrm{d}})^{-1} = |k''|\eta^2/\gamma$ needed for the input pulse [2] to be a soliton;
(ii) in any given fiber with fixed GVD k'' and nonlinearity γ, a larger soliton power P_1 is required for a shorter duration, i.e., narrower solitons are taller;
(iii) solitons experience a phase retardation as a whole (particle), which increases with P_1, i.e., taller solitons have larger shifts;

(iv) as a consequence of Galileian invariance, a frequency shift $\delta\omega$ from ω_0 induces the soliton velocity to change from k'^{-1} to $(k' + \mathrm{d}k')^{-1}$, with $\mathrm{d}k' = \mathrm{d}k''\delta\omega$;

(v) unlike other waves in nonlinear media, collisions between solitons with different velocities are strictly elastic, as shown in the example of Figure 1a; and

(vi) solitons are extremely robust: for instance they can be excited with input peak powers differing from P_1, whereas a weak attenuation α ($\alpha L_\mathrm{d} \ll 1$) induces the soliton to reshape adiabatically, i.e., the peak power decreases, yet the pulse remains locally a soliton by adjusting its width, as displayed in Figure 1b.

More general (and cumbersome) solutions of eqn [1] describe periodic soliton evolutions, such as the interaction of in-phase adjacent input pulses at the same frequency (see Figure 1c), or a single input pulse with sech-shape but peak powers corresponding to higher integer values of N, so-called breathers because of their ability to recover periodically the initial shape after ‘breathing’ (see Figure 1d for $N = 3$) over the distance $\pi L_\mathrm{d}/2$.

Solitons [2] describe stable propagation-invariant pulses under ideal conditions (lossless case, relatively long pulses and short SMFs). In practical settings, the importance of solitons stems from their robustness against real-world perturbing phenomena described by terms that in turn break the integrability of the underlying model [1]. Situations of this kind arise, for instance, when one accounts for stimulated Raman scattering whose effect is to down-shift continuously the central frequency of ultra-short solitons, or in optical communication systems treated below.

Solitons in Optical Communications

Solitons [2] represent ideal bits for RZ (return-to-zero) optical data sequences. However, fibers have unavoidable losses of about 0.2 dB/km at the usual operating wavelength $\lambda_0 = 1550$ nm. To ensure long-haul connections, the optical signal must be periodically amplified, commonly using erbium-doped fiber amplifiers (EDFAs). The pulse peak power hence



Figure 1 Fundamental features of fiber (NLSE) solitons: (a) elastic collision of two $N = 1$ solitons with different values of parameter pairs (frequency–velocity and amplitude–width); (b) adiabatic soliton damping in the presence of losses; (c) two-soliton bound state (in-phase interacting solitons of equal amplitudes); (d) evolution of a $N = 3$ soliton breather along one period of its evolution. Here the power $|E|^2$ is scaled in units of fundamental soliton power P_1, while distance z and time t are reported in units of L_d and initial pulse-width $1/\eta$, respectively.

undergoes both large exponential decay, because of distributed losses and abrupt lumped amplification under the action of EDFAs. Therefore, the stable local balance between GVD and nonlinearity cannot be rigorously sustained in the fiber. If both losses and amplifiers are accounted for, the mathematical model for pulse envelope propagation along M spans becomes:

$$\mathrm{i}\frac{\partial E}{\partial z} - \frac{k''}{2}\frac{\partial^2 E}{\partial t^2} + \chi|E|^2 E = -\mathrm{i}\alpha E + \mathrm{i}[\exp(\alpha Z_\mathrm{A}) - 1] \times \sum_{n=1}^{M} \delta(z - nZ_\mathrm{A})E(nZ_\mathrm{A}, t) \qquad [3]$$

where the RHS contains the perturbing terms arising form distributed losses (α) and lumped amplifications (described by the comb with spacing Z_A).

The analysis of nonintegrable systems, such as eqn [3], can be carried out by appropriate transformations that allow the recovery of a reduced integrable model. The key result is that, under the limitations set by an appropriate length scale, the solitons of the reduced system can be close to those of the original problem. For temporal solitons, such transformation was first called 'the guiding center soliton', envisaging a similarity with the guiding center motion of a charged particle in a magnetic field. The main outcome is that eqn [3] can be reduced to the standard NLSE [1], clearly showing that soliton-like propagation still occurs in the presence of losses (even large, $\alpha L_\mathrm{d} \gg 1$) and rapid periodic amplification. The appropriate scale for these systems is the amplifier spacing Z_A, that must be much shorter than L_d. To reproduce an average behavior similar to the lossless case, it is sufficient to multiply the input condition for an enhancement factor that counteracts the effect of fiber losses. Therefore soliton-like solutions do exist even in fiber systems with loss management, though on average (over several fiber spans) rather than locally.

Another issue that makes solitons suitable as optical bits, lies in their intrinsic aptness to be controlled either through passive or through active systems. Solitons tend to follow their relative center of mass in the temporal or spectral domain. For instance, a powerful technique to overcome one of the major problems, i.e., the growth of noise due to amplified spontaneous emission, may be obtained by deploying periodically along the line optical passband filters. Mollenauer and co-workers have demonstrated that, by sliding the filters progressively (i.e., changing slightly the central peak from filter to filter), one can guide a shape-invariant soliton which adapts its carrier frequency while effectively suppressing the noise. Similar control techniques involve amplitude or phase modulators and a consistent amount of work has focused on the problem of all optical soliton regeneration.

To exploit the idea of soliton in optical communications, however, we should consider the fact that ultra-short optical pulses, suitable for high transmission rates, require extremely low fiber GVD to accomplish the stable balance between dispersion and nonlinearity for a fixed pulse-width and available power. For instance, in order to transmit at 40 Gbit/s, we should achieve a fixed GVD coefficient $D = -(2\pi c/\lambda_0^2)k'' \simeq 0.25$ ps/(km nm) for the whole link.

On the other hand, in many optical systems the fiber nonlinearity is not exploited at all but rather considered as a perturbing effect and a source of penalty that limits the maximum transmission distance. In such an approach the desired cumulated GVD should be as close as possible to zero to avoid errors coming from inter-symbol interference caused by dispersive broadening. Dispersion-shifted fibers may ensure low GVD only in a narrow spectral region, thus limiting the transmission bandwidth. Conversely GVD can be reduced to zero on average, simply combining fiber spans with opposite GVD. The periodic alternance of fiber types may also carry several benefits, e.g., limiting the impact of resonant nonlinear interactions such as four-wave mixing (*see* **Fiber and Guided Wave Optics:** Nonlinear Effects (Basics) for its definition). The different architectures of dispersion management proposed with the twofold scope of limiting nonlinear effects and reducing the cumulated GVD, have immediately stimulated the investigation of their impact on soliton propagation. In the early schemes, the attention was focused on the so-called adiabatic dispersion management, where the GVD was changed proportionally to the soliton power to improve soliton system performances. In contrast with previous works, nonadiabatic map profiles were introduced in the experiments by Suzuki and co-workers to compensate the cumulated dispersion by locating periodically dispersion compensating fibers (DCFs). In net contrast, Doran and co-workers have suggested the use of a combination of fibers with alternate normal and anomalous GVD (i.e., a periodic stepwise variation of GVD), predicting the existence of solitons with a peak power larger than the equivalent classical soliton power, i.e., dispersion-managed solitons (DMSs) The periodic stepwise GVD map is not only conceptually different from earlier designs (with exponentially decaying GVD), but has opened the field to real application due to its simplicity of implementation. The innovative discovery that special pulse waveforms may propagate in periodically dispersion managed fiber links has triggered the interest of several groups, leading to a complete characterization of the problem, both theoretically and experimentally.

Similar to the case of guiding center solitons, a DMS usually shows a solitonic behavior. However, the DMS has a Gaussian shape surrounded by oscillating tails (see Figure 8 in **Solitons:** Optical Fiber Solitons, Physical Origin and Properties), thus being more suitable, due to its faster decaying tails, to be closely packed in a bit sequence in comparison with a sech-soliton (eqn [2]) of the same FWHM. We show an example of DMS transmission line in the top frame of Figure 2, where we sketched the variation of the GVD of a standard SMF periodically balanced by shorter segments of DCFs with opposite GVD. We report, in the middle frame, the DMS pulsewidth and chirp and in the bottom frame the pulse peak power. As shown, the macroscopic soliton parameters are characterized by large fluctuations: the local minima of pulsewidth correspond to chirp-free points and at such points one observes either a minimum or a maximum of the pulse spectral bandwidth. Nonetheless, all these pulse parameters have periodical evolutions that are fingerprints of an invariant and soliton-like pulse when observed at integer multiples of Z_A. The exact periodicity preserves the pulse waveform and hence the carried information. In DMS transmission we assist at the threefold compensation of energy, GVD and nonlinearity. Similarly to the guiding center solitons, the threefold compensation has an average, rather than pointwise, connotation. However, unlike guiding center solitons, for DMSs the definition of average should take into account the different relevance of pulse peak power in the map. Consequently the nonlinearity is compensated in a weighted manner, and it is not surprising in this context (though astonishing if placed back in the context of the NLSE [1] which requires anomalous GVD), that DMSs have been observed even when the uniform average GVD is weakly normal.



Figure 2 Evolution of soliton parameters along three periods of a fiber link with lumped amplifiers and dispersion management. Top frame: GVD map D(z) [ps/(nm km)] and EDFAs (triangles) location; Middle frame: soliton chirp (in units of 1000 ps^{-2}, dashed line), and pulse-width (in ps, solid line) vs. distance. Bottom frame: DMS peak power (dBm) vs. distance.

The net difference between the local and average GVD allows simultaneous control of different detrimental phenomena: for instance four-wave mixing is reduced by the large local GVD, whereas a small average GVD limits the impact of timing jitter due to amplified spontaneous emission (Gordon–Haus effect). As a result, DMSs perform better than conventional solitons.

Figure 3 shows a typical high-speed (20 Gb/s) single-channel experiment, and the achieved performance in terms of quality factor Q versus propagation distance, with the output after 8100 km. We recall that the Q factor measures the bit-error-rate (an error rate lower than 10^{-9} corresponds to a Q higher than $\sim$ 16 dB). DMSs also allow the control of collisions between solitons that pertain to different channels (we recall that solitons at different carrier frequencies go at different velocities, and hence collide), thus enhancing performances of standard or dense WDM systems.

Multi-Component Temporal Solitons

So far we have discussed temporal solitons described by a single envelope. However, the same mechanism of mutual balance between nonlinearity and dispersion can also be effective for multiple pulses, leading to trap simultaneously multicomponent (or so-called vector) solitons. Solitons of this type are, for instance, those due to the interaction of polarization modes in isotropic or birefringent Kerr media, higher-order modes in large-core (multimode) fibers, or mixing of pulses at different carrier frequencies that interact parametrically (i.e., without net exchange of energy with the medium). The latter case entails a broad class of solitons since virtually any parametric four-photon mixing process in cubic media (e.g., nondegenerate or partially degenerate four-wave mixing, third harmonic generation, ...), or three-photon mixing process in quadratic media (sum- and difference-frequency generation, second-harmonic generation (SHG), optical rectification, etc.) is allowed to sustain them. This opens up the field to an entirely new class of materials, namely noncentrosymmetric (quadratic) materials which usually have stronger nonlinear responses if compared with silica fibers. SHG can be taken as a paradigm to



Figure 3 (a) Schematic diagram of the straight-line experiment with optical time-division multiplexing (OTDM) of soliton at 20 Gbit/s; (b) Measured *Q* factor vs. distance comparing experimental results obtained in the straight-line and loop configuration (loop length of 1000 km), respectively. The waveform received after 8100 km is also shown. With permission from Suzuki M and Edagawa N (2003) Dispersion-managed high-capacity ultra-long-haul transmission. *Journal of Lightwave Technology* 21: 916–929. © 2003 IEEE.

understand the main features of these multicomponent solitons. In this case, the evolution of the interacting envelopes E_j at carrier frequencies $j\omega_0$, $j = 1, 2$, is ruled by the coupled equations:

$$\begin{gathered}\left(\mathrm{i}\frac{\partial}{\partial z} - \frac{k_1''}{2}\frac{\partial^2}{\partial t^2}\right)E_1 + \chi E_2 E_1^* \exp(\mathrm{i}\Delta k z) = 0, \\ \left(\mathrm{i}\frac{\partial}{\partial z} + \mathrm{i}\delta k'\frac{\partial}{\partial t} - \frac{k_2''}{2}\frac{\partial^2}{\partial t^2}\right)E_2 + \chi E_1^2 \exp(-\mathrm{i}\Delta k z) = 0,\end{gathered} \tag{4}$$

where the subscript $j = 1, 2$ indicates that the relative quantities evaluated at frequency $j\omega_0$, $t = T - k'_1 z$, $k''_{1,2}$ are GVD coefficients, $\delta k' \equiv k'_2 - k'_1$ is the group-delay, χ is the effective nonlinear coefficient, and $\Delta k = k_2 - 2k_1$ is the wave-number (or phase) mismatch. In spite of the fact that eqns [4] are not integrable, their stable soliton solutions can be found (numerically) in a wide range of parameters as symbiotic phase-locked pulses $E_{1,2}(z,t)$ that travel undistorted. For instance, SHG solitons exist either in phase-matching ($\Delta k = 0$) or far-off phase-matching (with some limitations for $\Delta k > 0$), and, unlike fiber solitons, also in normally dispersive media ($k''_{1,2} > 0$). As for fiber solitons, their width is related to their peak power, since the basic mechanism is the mutual balance between the dispersive broadening (that depend on the pulsewidth) and nonlinear phase-shifts (that depend on power), which occur due to repeated up-conversion and down-conversion processes, often referred to as cascading. A SHG soliton is robust enough to permit the observation of trapping, even from an input that differs considerably from the soliton (e.g., from the fundamental only), or in the presence of a relatively strong group-delay which tends to rip apart the two-component soliton, inducing walk-off between the two envelopes.

In contrast with fibers, in this case, experiments are necessarily made in relatively short bulk samples, thus resulting in a limited number of dispersion lengths. Usually broad (quasi-planewave) beams are conveniently employed in order to make diffraction ineffective.

The main experimental problem is that, in crystals commonly employed for SHG, the dynamics of typical laser pulses (duration above 100 fs) is fully dominated by the group-delay $\delta k'$. In other words, the material GVD becomes relevant only for pulses as short as a few fs. Therefore, the observation of solitons with longer pulses has been required to tailor the dispersion, which can be accomplished by means of pulses with tilted phase front. As displayed in Figure 4, successful compression of 200 fs (FWHM) tilted pulses was observed at relatively large negative Δk in a BBO bulk crystal with effective zero group-delay and enhanced (anomalous) GVD.



Figure 4 Soliton fomation via SHG: the circles show the output pulse duration (full width at half maximum (FWHM) of autocorrelation τ_{corr}) vs. mismatch Δk, measured after propagation of an input 200 fs tilted pulse (input $\tau_{corr} = 284$ fs) with 13.4 GW/cm^2 peak intensity, in a 7 mm BBO crystal (inset: same with 10.4 GW/cm^2). Superimposed (dotted line) is the corresponding theoretical value obtained from eqn [4]. The solid curve that fits better the data accounts for the additional effect of the material Kerr effect. With permission from Di Trapani P, Caironi D, Valiulis G, Dubietis A, Danielius R and Piskarskas A (1998) Observation of temporal solitons in second-harmonic generation with tilted pulses. *Physical Review Letters* 81: 570–573. © 1998 APS.



Figure 5 Dynamics of temporal soliton formation ruled by eqn [4]. A compressed soliton is formed via strongly mismatched ($\Delta k = -100$ cm^{-1}) SHG from a 200 fs (FWHM) input pulse at fundamental carrier frequency, in a crystal with $\chi = 1.4 \times 10^{-4}$ W$^{-1/2}$, effective dispersion $\delta k' = 0$ (group–velocity matching) and $k_1'' = -1.8$ ps^2/m, $k_2'' = -0.75$ ps^2/m.

The measured compression is a signature of soliton formation, as clearly indicated by the example of simulated pulse dynamics reported in Figure 5: the pulse at second-harmonic is generated and then trapped with the input one as a two-component bound state. Radiation and oscillations occur, in this case, because the launching conditions (single envelope) are far enough from the two-component soliton.

Temporal Solitons in Bragg Gratings

A linear periodic structure, such as a Bragg grating with pitch Λ, couples counter-propagating waves when their frequency lies close to the Bragg frequency ω_B (vacuum wavelength $\lambda_B = 2n_0\Lambda$) defined by the resonance condition $k(\omega_B) = \pi/\Lambda$. Such a type of structure supports a different type of temporal solitons, so-called gap solitons (GSs) since they originate from a linear dispersion relationship of the type shown in Figure 6a, characterized by a stop-band (gap) centered around ωB. The gap is characterized by a unitary grating reflectivity, as shown in Figure 6b, and the forward linear propagation is therefore forbidden. However, if the incoming wave is intense enough to induce the refractive index to increase through the optical Kerr effect, the Bragg resonance (and the whole gap) is shifted downwards (in frequency) allowing for self-transparency at the operating frequency. GSs can be understood as bell-shaped envelopes which are allowed to travel along the grating due to a high-intensity core that bleaches the reflectivity, while the high reflectivity seen by the tails takes the pulse together. GSs are expected to be slow because the slope of the dispersion curve tends to zero when approaching the gap, while its curvature results in the grating GVD (huge if compared with material GVD in real-world units), which is exactly balanced by the nonlinearity when the GS is formed. This naive portrait is supported by a more thorough analysis starting from the coupled-mode equations obeyed by the forward $E_+(z, T)$ and backward $E_-(z, T)$ envelopes at frequency ω_B, propagating along a (e.g., fiber) Bragg grating with Kerr effect (inducing SPM and



Figure 6 (a) Bragg linear dispersion relationship in normalized (dimensionless) units: wave-number shift $\delta k = (k(\omega) - \pi/\Lambda)/\Gamma$ vs. frequency detuning $\delta\omega = k'(\omega - \omega_B)/\Gamma$; (b) linear grating reflectivity vs. $\delta\omega$ for a grating figure of merit $\Gamma L = 4$; (c) existence domain (whole shaded area) of GSs in the normalized detuning–velocity plane ($\delta\omega, v \equiv k V_{sol}$). The light shaded area corresponds to the stop-band $|\delta\omega| < 1$ (inner region between dashed lines in a–b). The insets show samples of GS intensity profiles vs. the moving frame coordinate $\zeta = (1 - v^2)(z - V_{sol}T)$. Zero-velocity GSs have symmetric envelopes ($|E_+| = |E_-|$) and range from high-amplitude (HA) to low-amplitude (LA) across the gap. The third inset shows a moving GS in the experimentally accessible region, where it retains LA but has a stronger component in the direction of motion.

cross-phase modulation):

$$\mathrm{i}\left(k'\frac{\partial E_\pm}{\partial T} \pm \frac{\partial E_\pm}{\partial z}\right) + \Gamma E_\mp + \gamma\left(|E_\pm|^2 + 2|E_\mp|^2\right)E_\pm = 0 \qquad [5]$$

The linear dispersion associated with eqn [5] is as in Figure 6a, with a stop-band $|\omega - \omega_B| \le \Gamma/k'$ proportional to the index corrugation depth through the Bragg coupling coefficient Γ. In the nonlinear regime, GS solutions of eqn [5] differ qualitatively from conventional fiber solitons [2]:

(i) first, GSs are indeed slow since the two envelopes can travel locked with any soliton velocity V_{sol} such that $|v| \equiv |k'V_{sol}| \le 1$, i.e., lower than the natural group velocity k'^{-1};



Figure 7 Gap solitons in a fiber Bragg grating: (a) measured pulse spectrum compared with the linear grating transmission, (b) compressed (15 ps) and delayed pulse transmitted at high intensity (dashed line), compared with the pulse transmitted at frequency far from the Bragg resonance (solid line) where it retains its input width of 80 ps. With permission from Eggleton BJ, Slusher RE, de Sterke CM, Krug PA and Sipe JE (1996) Bragg grating solitons. *Physical Review Letters* 76: 1627–1630. ©1996 APS.

(ii) GSs exist only in a narrow bandwidth, i.e., the shaded area in Figure 6c, which corresponds to the gap seen in the soliton frame (it reduces to the conventional stop-band for still solitons and gets wider for faster GSs); and

(iii) the gap is strongly asymmetric since lower intensity is required to induce transparency close to the high-frequency band-edge where, as a consequence, GSs have low amplitudes and are stable (the amplitude grows moving towards the low-frequency bandedge, where GSs become unstable).

Experimentally, GSs have been typically observed with pulses at frequency close to the blue bandedge of fibers (see Figure 7a) and AlGaAs waveguides with built-in Bragg gratings of a few centimeters. The typical signature of GSs, illustrated in Figure 7b, is the enhanced pulse transmission observed under the operating conditions of Figure 7a when the input intensity is sufficiently high. The transmitted pulse experiences pulse compression and a significant group-delay (measured with respect to the transit-time at frequency far off the stop-band), witnessing its nature of slow-light solitons.

Finally, we emphasize that grating solitons can also be supported in the case where the two modal envelopes propagate in the forward direction along a grating whose period Λ is long enough to be resonant with the modal phase slippage, thus inducing efficient linear coupling between them. In this case, the structure has a gap in wave-number, and solitons are slow in the frame traveling at the average modal group-velocity. Soliton formation is expected to lead to grating-induced compensation of the group-delay between the modes. Experiments on such types of structures have been carried out only recently.

Solitons in Dissipative Nonlinear Optics

Temporal solitons can also be observed in nonlinear optical interactions that involve changes of the state (energy level) of matter as in inverted media or scattering phenomena. For instance, early studies in the 1960s have demonstrated that coherent pulses with energy above a critical level can pass through resonant (two-level) atoms without being absorbed, a phenomenon denoted as self-induced transparency. Such pulses are temporal solitons solutions of the Maxwell–Bloch model which describes the atom–light interaction.

Also scattering phenomena occurring in optical fibers, such as Raman and Brilluoin scattering, possess three-wave solitons, in which the pump and scattered (Stokes) light waves are coupled to a phonon field of the acoustic or optical branch (for Brillouin or Raman, respectively).

Perhaps more important from the point of view of the modern applications, are fiber lasers composed by spans of active and/or passive fiber closed to form a recirculating loop. These types of structures can often be described by distributed (averaged over several round-trips) models, which take the form of a dissipative perturbed NLSE, known as the Ginzburg–Landau equation (GLE):

$$\mathrm{i}\frac{\partial E}{\partial z} - \frac{k''}{2}\frac{\partial^2 E}{\partial t^2} + \chi|E|^2 E = \mathrm{i}gE + \mathrm{i}g_{\mathrm{nl}}|E|^2 E + \mathrm{i}q|E|^4 E + \frac{\mathrm{i}}{\Omega_{\mathrm{f}}^2}\frac{\partial^2 E}{\partial t^2} \qquad [6]$$

where g is the excess (net) gain ($g > 0$) or loss ($g < 0$), g_{nl} and q describe the nonlinear gain mechanism and its saturation (usually introduced to control the mode-locking), and Ω_{f} is linked to spectral filtering. Several soliton (pulse) solutions of the GLE [6] can be found even when the parameters (g, g_{nl}, q, Ω_{f}) are such as to constitute a strong perturbation of the NLSE. Unlike NLSE solitons [2], pulse solutions of the GLE [6] are usually chirped (i.e., possess a nonlinear phase profile), and have fixed amplitude for a given value of the parameters. The set of soliton waveforms is generally richer and includes, for instance, flat-top stationary pulses, two-pulse bound-states, solitons moving at fixed velocity, etc. Although instabilities of the background (for $g > 0$) or of the pulse itself can affect their observability, large islands of stability in the parameter space can be found. The relevant role of stable solitons in mode-locking and intra-cavity pulse formation mechanisms has been demonstrated in many different fiber laser geometries, for which we refer the reader to the more specialized papers listed as Further Reading at the end of this article. We point out that some schemes, for instance the stretched pulse-fiber laser developed at MIT, involve a basic configuration (alternating GVD within the cavity length) which is quite similar to that seen in the framework of DMSs, thus exhibiting the same basic physical mechanism (strong compression and stretching of the pulse along each round-trip which play the role of the map period for a DMS).

List of Units and Nomenclature

BBO	β-barium borate
DCF	dispersion compensating fiber
DMS	disperion managed soliton
EDFA	Erbium doped fiber amplifier
GLE	Ginzburg–Landau equation
GS	gap soliton
GVD	group-velocity dispersion
NLSE	nonlinear Schrödinger equation
OTDM	optical time-division multiplexing
SHG	second-harmonic generation

SPM self-phase modulation
WDM wavelength division multiplexing
Amplifier spacing L_{A} [m]
Bragg frequency ω_{B} [Hz]
Bragg period Λ [m]
Central wavelength λ_0 [nm]
Coupling coefficient Γ [m^{-1}]
Dispersion coefficient D [ps nm^{-1} km^{-1}]
Dispersion length L_{d} [m]
Effective area A_{eff} [m^2]
First-order dispersion k' [s/m]
Fundamental soliton power P_1 [W]
Gain (linear) g [m^{-1}]
Gain (nonlinear) g_{nl} [m^{-1}]
Group-delay δ [s/m]
Group-velocity $V = k'^{-1}$ [m/s]
Group velocity dispersion k'' [ps^2 m^{-1}]
Inverse pulse-width η [s^{-1}]
Light velocity in vacuum c [m/s]
Loss coefficient α [m^{-1}]
Nonlinear coefficient (fiber) γ [m^{-1} W^{-1}]
Nonlinear coefficient (quadratic bulk materials) χ [W$^{-1/2}$]
Nonlinear refractive index n_{2I} [m^2 W^{-1}]
Nonlinear length L_{nl} [m]
Refractive index (linear) n_0
Retarded time (in the moving frame) t [s]
Spectral filtering coefficient Ω_{f} [Hz m$^{1/2}$]
Time in the laboratory frame T [s]
Wave-number mismatch Δk [m^{-1}]

See also

Fiber and Guided Wave Optics: Nonlinear Effects (Basics); Nonlinear Optics. **Fiber Gratings**. **Lasers:** Optical Fiber Lasers. **Nonlinear Optics, Basics:** $\chi^{(2)}$–Harmonic Generation. **Optical Communication Systems:** Wavelength Division Multiplexing. **Scattering:** Scattering Phenomena in Optical Fibers. **Solitons:** Bright Spatial Solitons; Optical Fiber Solitons, Physical Origin and Properties.

Further Reading

Ablowitz MJ, Biondini G and Ostrovsky LA (eds) (2000) Focus issue: optical solitons: perspectives and applications. *Chaos* 10: 471–640.

Agrawal GP (1995) *Nonlinear Fiber Optics*, 2nd edn. London: Academic Press.

Agrawal GP and Kivshar YS (2003) *Optical Solitons*. London: Academic Press.

Akhmediev NN and Ankiewicz A (1997) *Solitons: Nonlinear Pulses and Beams*. London: Chapman and Hall.

Buryak AV, Di Trapani P, Skryabin D and Trillo S (2002) Optical solitons due to quadratic nonlinearities: from basic physics to futuristic applications. *Physics Reports* 370: 63–235.

De Sterke CM, Eggleton BJ and Sipe JE (2001) In: Trillo S and Torruellas W (eds) *Spatial Solitons*. Berlin: Springer-Verlag.

Di Trapani P, Caironi D, Valiulis G, Dubietis A, Danielius R and Piskarskas A (1998) Observation of temporal solitons in second-harmonic generation with tilted pulses. *Physics Review Letters* 81: 570–573.

Eggleton BJ, Slusher RE, de Sterke CM, Krug PA and Sipe JE (1996) Bragg grating solitons. *Physics Review Letters* 76: 1627–1630.

Forysiak W, Knox FM and Doran NJ (1994) Average soliton propagation in periodically amplified systems with stepwise dispersion-profiled fiber. *Optics Letters* 19: 174–176.

Hasegawa A (2000) Soliton-based optical communications: An overview. *IEEE Journal of Selected Topics in Quantum Electronics* 6: 1161–1172.

Hasegawa A and Kodama Y (1995) *Solitons in Optical Communications*. London: Oxford University Press.

Hasegawa A and Matsumoto M (2002) *Optical Solitons in Fibers*. Berlin: Springer-Verlag.

Haus HA (2000) Mode-locking of lasers. *IEEE Journal of Selected Topics in Quantum Electronics* 6: 1173–1185.

Mollenauer LF and Mamyshev PV (1998) Massive wavelength-division multiplexing with solitons. *IEEE Journal of Quantum Electronics* 34: 2102.

Nakazawa N, Kubota H, Sahara A, Suzuki K and Yamada E (2000) Ultrahigh-speed long-distance TDM and WDM soliton transmission technologies. *IEEE Journal of Selected Topics in Quantum Electronics* 6: 363.

Porsezian K and Kuriakose VC (2003) *Optical Solitons: Theoretical and Experimental Challenges*. Berlin: Springer-Verlag.

Slusher RE and Eggleton BJ (eds) (2003) *Nonlinear Photonics Crystals*. Berlin: Springer-Verlag.

Suzuki M and Edagawa N (2003) Dispersion-managed high-capacity ultra-long-haul transmission. *Journal of Lightwave Technology* 21: 916–929.

Suzuki M, Morita I, Edagawa N, Yamamoto S, Toga H and Akiba S (1995) Reduction of Gordon-Haus jitter by periodic dispersion compensation in soliton transmission. *Electronic Letters* 31: 2027–2028.

Turitsyn SK, Aceves AB, Jones CKRT, Zharnitsky V and Mezentsev VK (1999) Hamiltonian averaging in soliton-bearing systems with a periodically varying dispersion. *Physics Review E* 59: 3843–3846.

Wabnitz S, Kodama Y and Aceves AB (1995) Control of optical soliton interactions. *Optics and Fiber Technology* 1: 187–217.

Zakharov VE and Wabnitz S (1999) *Optical Solitons: Theoretical Challenges and Industrial Perspectives*. Berlin: Springer-Verlag.

SPECTROSCOPY

Contents

Absolute Optical Frequency Metrology
Fourier Transform Sepctroscopy
Hadamard Spectroscopy and Imaging
Nonlinear Laser Spectroscopy
Raman Spectroscopy
Second-Harmonic Spectroscopy
Single Molecule Spectroscopy

Absolute Optical Frequency Metrology

S T Cundiff, National Institute of Standards and Technology and University of Colorado, Boulder, CO, USA

L Hollberg, National Institute of Standards and Technology, Boulder, CO, USA

Published by Elsevier Ltd.

Introduction

Visible light occupies a portion of the electromagnetic spectrum between frequencies of approximately 400 terahertz (THz) to 750 THz, where 1 THz is 10^{12} oscillations per second. Optical radiation, which includes adjacent infrared and ultraviolet portions of the spectrum, covers a frequency range of approximately 15–1500 THz. The techniques required for measuring frequencies in this range are qualitatively different from those currently employed in the radio frequency (RF) and microwave portions of the spectrum, where high-speed electronic counters make a direct measurement possible.

The frequency of an oscillatory phenomenon is the number of oscillations that occurs in unit time, or alternatively, the inverse of the period of one oscillation. Thus, to understand frequency, we must understand time, which is intrinsically related to phase. Only a time interval, the time elapsed between two events, has fundamental physical meaning. The 'time' that we are most familiar with, the time of day (including the date), is based on an arbitrarily chosen starting point. The starting point chosen in current international agreements can be traced to noon on December 31st, 1899. Furthermore, the time defined by those agreements, Universal Coordinated Time (UTC), is periodically adjusted relative to atomic time (discussed below) to compensate for irregularities in the rotation of the Earth.

Knowledge of the transition frequencies (energies) in simple atoms gives detailed information on the structure of the atoms. This can be used to test our understanding of the fundamental interactions in nature by comparing the measured frequencies with predictions of fundamental physical theories, in this case quantum electrodynamics (QED). Beautiful results along these lines are exemplified by precision measurements of transition frequencies in hydrogen and helium. In addition, the ability to measure and precisely control laser frequencies promises tremendous advances in the performance of the next generation of atomic clocks and frequency standards. These have potential applications to navigation and communication systems.

The measurement of frequency and time intervals also involves a choice, that of the unit of time, i.e., the definition of the second. The original definition of the second was based on the rotation of the Earth. However, not only is it irregular, but it is slowing down. Both of these facts limit its utility as a frequency standard. Once atomic clocks were highly developed, the second was redefined in 1967 to be the time it takes for the $F = 4$, $m_F = 0 \rightarrow F = 3$, $m_F = 0$ transition in the hyperfine structure of the ground state of ^{133}Cs to undergo 9192 631 770 oscillations. Thus an 'absolute' measurement of time interval, and hence frequency, must be directly connected to this defining frequency. The basic structure of an atomic clock is shown in Figure 1.


Atomic
Control system locks LO to atomic resonance
f_{Atom}
Local
E.g. quartz crystal, synthesizer, or laser
Counter
456 986 240 494

Figure 1 An atomic clock has three basic components: an atomic resonance, an oscillator to probe and lock to the atomic resonance, and a counter that records the number of oscillations and thus displays the time interval since some chosen starting time.

Frequency standards (or clocks) are characterized by three properties: accuracy, stability, and reproducibility. Accuracy describes how well the natural and fundamental atomic frequency is produced by the atomic frequency standard. Stability describes the frequency fluctuations on short timescales (an accurate but unstable standard produces a frequency that fluctuates around a constant mean that is the atomic frequency). Reproducibility between standards addresses whether or not two implementations of the standard produce exactly the same frequency. Atomic clocks are intrinsically accurate because the frequency of the transitions they are based on is determined by identical atoms in nature. The largest inaccuracies are usually due to environmental perturbations such as tiny variations in the local magnetic field.

A careful analysis of all of these issues, together with technical considerations, yielded the choice of cesium for the current definition of the second. Other common frequency standards include quartz crystal oscillators, hydrogen masers, and rubidium vapor cell standards. Quartz oscillators are inexpensive and have good stability, but in comparison to atomic standards they suffer from accuracy and reproducibility issues. Hydrogen masers have the best stability, but also poor accuracy and reproducibility compared to cesium. Vapor cell rubidium standards can be small and inexpensive but have poorer accuracy than cesium beam standards due to cell and buffer gas effects.

There are several motivations for using optical sources rather than RF or microwaves to measure time intervals and frequencies. Obviously, a higher oscillation frequency can divide time into smaller units and this can provide higher measurement precision. It is thus natural to use the highest oscillation frequency that can be precisely counted to measure time and frequency. Not long after lasers were invented, suggestions were made that it would be possible to make optical frequency standards using lasers locked to narrow atomic resonances.

A basic feature of optical transitions is that they have a very high *Q* factor (the ratio of the center frequency to the linewidth). This allows them to be measured to very high precision (current measurements are good to a few parts in 10^{15}). It may be possible to use this high precision to build improved atomic clocks that use optical transitions instead of the microwave transition currently being used. Candidates for optical standards include both trapped ions (Hg^+, Yb^+, Sr^+, and In^+ are under investigation) and laser-cooled neutral atoms (Ca, Sr, Mg, Ba, and Ag). The high precision is also utilized for fundamental tests of quantum electrodynamics by comparing transition frequencies (usually of hydrogen or helium atoms) to first-principle calculations. For comparison Figure 2 shows the relevant transitions and energy levels in the Cs microwave standard and the Hg^+ optical frequency. It is even possible to use the precision of atomic clocks for high-sensitivity tests of variation in the fundamental constants with time. Finally, because the speed of light is constant length measurements based on the wavelength of light with a known frequency, the precision of length metrology ultimately rests on optical frequency metrology.

An obvious question, which might occur to many in the field of optics, is why a standard spectrometer does not provide absolute frequency measurements. All spectrometers measure wavelength, not frequency, based on interference between light traveling two different path lengths. Thus, knowledge of the path length is needed to determine the wavelength. However, since length is now defined using the speed of light, the definitions become circular unless a source of light with known absolute frequency is available. In addition, frequency measurement is intrinsically more precise and reliable than mechanical length measurement.

Recently, there has been a significant breakthrough in optical-frequency metrology and optical clocks by using mode-locked lasers that generate optical pulses with durations of a few femtoseconds. Before discussing optical frequency metrology based on mode-locked lasers, we will review earlier techniques to provide the necessary background. After describing



Figure 2 Simplified energy level diagram of Hg^+ and Cs.

methods that use mode-locked lasers, we will then provide a summary of current measurements and standards. Finally we will briefly describe the outlook for the future of absolute optical frequency metrology.

Background

To imagine being able to measure the frequency of light we need to have laser sources with high coherence, like that of radio waves, where the phase is stable enough to be measured. Even though the first beat-note between two lasers was demonstrated in the 1960s, most lasers were not coherent (stable) enough that the optical phase could be tracked for much longer than about 10 to 100 ns. After many years of research and inspiring technological achievements, Hall, Chebotayev, Bergquist and others were able to stabilize the frequency of tunable laser sources to the point that lasers could indeed be considered coherent sources, with the phase continuously measurable and even predictable for times as long as seconds. Once the lasers were stable enough to be counted, there was still the essential problem that no counter was fast enough to actually count optical frequencies.

With spectrally pure laser sources it was possible to conceive of measuring optical frequencies by extending the nonlinear methods that are used to generate and measure RF and microwave frequencies. By using simple nonlinear components such as diodes, it is easy to generate high harmonics of an input frequency in the RF and microwave regions of the spectrum. At least in principle, and by direct analogy, it seemed that it should be possible to multiply coherent sine waves from radio frequencies up through the microwave region to reach the THz frequencies of far-infrared lasers, and then to use nonlinear optical methods to multiply on up to the infrared (IR) and eventually to the visible region of the spectrum. The concept is simple enough, $f \rightarrow 100 \times f \rightarrow 1000 \times f \rightarrow 2000 \times f \rightarrow 4000 \times f\ldots$ until you reach an optical frequency. Multiplication up to the microwave region works quite well, but unfortunately the nonlinear optical processes in the far-infrared, IR, and optical regions are typically quite inefficient; the power at the second harmonic is typically only 10^{-5} times the square of the fundamental power in watts. Just multiplying a single-frequency laser by a factor of two can be a technological challenge. After reaching a microwave frequency of about 50 GHz we still require a multiplication factor of 10^4 to reach the visible at 500 THz. Since we are usually forced to multiply in the IR and optical by factors of 2, we have $2^N = 10^4$, which means we require $N \approx 13$ multiplication stages. This is approximately the number of stabilized laser oscillators that are required to span the frequency gap from the microwave to the visible. Notwithstanding these technological limitations, Evenson and collaborators did a groundbreaking demonstration of a harmonic frequency chain in 1972 that connected a microwave atomic frequency standard and a stabilized HeNe laser in the IR at 88 THz. With a concerted multiperson effort, more lasers, and 10 years of research, Jennings and co-workers finally succeeded in extending the harmonic optical frequency chain to the visible. That original optical frequency chain from the RF to the visible is diagramed in Figure 3. In the succeeding 18 years, only three other harmonic frequency chains were built world-wide that connected the microwave standards to optical frequencies.

An alternative scheme for measuring optical frequencies is the optical bisection method, a conceptually simple technique proposed by Telle, Meschede and Hänsch, for dividing down from


$\nu_{10}/2$ (HeNe) 1.15 μm
X2 XTAL
ν_{10} $^{127}I_2$
CHARTREUSE
ν_{10}= 520.206837 THz
$\nu_{10} = 2\nu_9+\nu_{10B}$
ν_9 = 260.103264 Ne(^{20}Ne)
$^{13}C^{16}O_2$ 9 μm R(20)
$C^{16}O_2$ 9 μm R(22)
Xtal
Xtal
SA
$\nu_9 = \nu_8 + \nu'_{CO2} + \nu''_{CO2} + \nu_{9B}$
ν_8 = 196.780372 HeNe(1.52 μm)
$\nu_8 = \nu_7 + \nu_{CO} + \nu_{8B}$
ν = 48.862 075 CO (6.1 μm)
ν_7 = 147.915857 Xe(2.03 μm)
CO_2 9 μm P(36)
CO_2 9 μm P(8)
$\nu_7 = \nu_6 + \nu'_{CO2} + \nu''_{CO2} + \nu_{7B}$
ν_6 = 88.376 181 627 HeNe(3.39 μm): CH_4P(7)
$\nu_6 = 3\nu_5 + 0.049 + \nu_{6B}$
ν_5 = 29.442 483 315 CO_2 νR[30] (10.2 μm)
$\nu_5 = \nu_4 - 3\nu_2 - 0.020 + \nu_{5B}$
Laser frequency synthesis chain (all frequencies in THz)
ν_4 = 32.134 266 891 CO_2 νR[10] (9.3 μm)
$\nu_4 = 3\nu_3 - 0.020 + \nu_{4B}$
ν_3 = 10.718 068 6 H_2O (28 μm)
$\nu_3 = 12\nu_2 + 0.029 + \nu_{3B}$
ν_2 = 0.890 760 550 HCN (337 μm)
$\nu_2 = 12\nu_1 + \nu_{2B}$
ν_1 = 0.074 232 545 83 Klystron
$\nu_1 = 7\nu_0 + \nu_{1B}$
ν_0 = 0.010 600 363 69 Klystron
Counter
Cs Freq. standard
Diode
Klystron
SA Spectrum analyzer

Figure 3 Schematic of the first frequency chain used to measure optical frequencies relative to the Cs standard.

optical frequencies to microwaves. In fact, the bisection method divides an arbitrary optical frequency interval in half by utilizing second-harmonic generation and sum-frequency-mixing, and forcing the condition that $2f_3 = f_1 + f_2$. Thus, the laser at frequency $f_3 = (f_1 + f_2)/2$ bisects the frequency interval between the lasers at f_1 and f_2. The optical bisection method has the following two significant advantages over the multiplication method: the phase noise is decreased in successive divisions (rather than increased by multiplications), and the system could be constructed out of one convenient and reproducible laser technology, say diode lasers in the near-visible. In principle, any optical frequency could be measured by successive operations of the optical bisector. Optical frequency intervals as large as 8 THz have been measured with this method, but even though it is feasible, no bisection system has been built to date that connects the optical region all the way to countable microwave frequencies. The main limitation is the same as that facing the multiplication scheme: it still requires lots of stabilized laser sources to divide by factors of 2 from 10^{15} to 5×10^{10} Hz. The problem can be reduced somewhat by taking advantage of an optical-frequency comb generator based on an electro-optic modulator inside a resonant optical cavity. These systems, developed by Korougi and others, generate many coherent microwave sidebands on a laser so that optical frequency intervals on the order of 5 THz can be measured.

Even combining all of these ideas and techniques, a convenient system to count optical frequencies remained elusive. This has now changed with the revolutionary new optical frequency combs based on mode-locked femtosecond lasers.

Optical Frequency Metrology with Femtosecond Combs

Recently, the introduction of mode-locked lasers into the field of absolute optical frequency metrology has resulted in an important advance. The extremely complex frequency chains described above can be replaced by a single mode-locked laser if it produces pulses with sufficiently large bandwidth. Although the underlying ideas are not new (they were originally discussed by Hänsch and Chebotayaev in the 1970s) it is only recently that mode-locked lasers with the required characteristics were developed and the concept carefully tested.

The dramatic simplification of a frequency chain that uses a mode-locked laser means that absolute optical-frequency measurements can now be made by a single person as compared to the team of approximately 10 highly trained scientists required to run the previous chains. This has resulted in a large number of measurements being reported in the last 2 years. The simplicity also allows longer averaging times and a greater number of measurements to be used in determining the final reported frequency. In addition, since a simpler system has fewer sources of error, it has improved the quality of measurements made in a given amount of time.

Mode-locked lasers produce ultrashort pulses of light. For a typical modern high-quality mode-locked laser, the pulse duration is around 10 fs (1 fs = 10^{-15} second), corresponding to three or four optical cycles in the near-infrared, where these lasers typically operate. The current best mode-locked lasers can produce pulses that are shorter than two optical cycles in duration (5–6 fs). Since the spectrum of these lasers is complicated, the bandwidth is significantly larger than it would be for a smooth pulse such as one with a Gaussian or hyperbolic-secant temporal intensity profile.

At first sight, using mode-locked lasers for optical-frequency metrology seems counter-intuitive, because optical-frequency metrology clearly requires very well-defined frequencies in contrast to the broad frequency spectrum of ultrashort pulses. This apparent conundrum is resolved by the fact that a mode-locked laser actually produces a very regularly spaced train of ultrashort pulses. The ultrashort pulses emitted by a mode-locked laser are replicas of a steady-state pulse that circulates inside the cavity of the laser. Every time the internal pulse impinges on the output coupler, which is a partially reflective mirror, a portion of it is transmitted, producing the output. The timing between these output pulses is determined purely by the time, τ_c, for the intracavity pulse to make one round trip, which is typically between 1 and 20 ns. The spectrum of a train of pulses is a regularly spaced 'comb' of frequencies spaced by the repetition rate of the train, $f_{\text{rep}} = 1/\tau_c$. If all of the pulses are identical, then these comb lines are just integer multiples of f_{rep}. However, due to dispersion, the group and phase velocities are different inside the cavity of a mode-locked laser. This leads to a pulse-to-pulse shift in the phase between the carrier and envelope (which we call the carrier–envelope phase; ϕ_{ce}, the pulse-to-pulse shift of ϕ_{ce} is designated by $\Delta\phi_{\text{ce}}$). The presence of $\Delta\phi_{\text{ce}}$ results in a rigid shift of all the comb lines by an amount $\delta = 2\pi\Delta\phi_{\text{ce}}/f_{\text{rep}}$. Thus the frequencies of the comb lines are given by $\nu_n = nf_{\text{rep}} + \delta$, where n is a large integer of order 10^6. The essential point of this equation is that it gives optical frequencies in terms of RF frequencies (f_{rep} and δ) that can easily be measured with conventional electronics and



Figure 4 Time–frequency correspondence and relationship between $\Delta\phi$ and δ. (a) In the time domain, the relative phase between the carrier and the envelope evolves from pulse to pulse by the amount $\Delta\phi$. (b) In the frequency domain, the elements of the frequency comb of a mode-locked pulse train are spaced by f_{rep}. The entire comb is offset from integer multiples of f_{rep} by an offset frequency $\delta = \Delta\phi f_{\mathrm{rep}}/2\pi$.



Figure 5 Schematic of the self-referencing technique for determining the offset frequency of the frequency comb produced by a femtosecond mode-locked laser. The frequency difference between the fundamental comb and its second harmonic is the offset frequency. In the region where overlap occurs, this is easily detected as a heterodyne beat.

compared to the microwave cesium frequency standard. The relationship between the time and frequency domains is shown in Figure 4.

Given such a comb of frequencies, a heterodyne measurement readily yields the frequency difference between the unknown optical frequency of a narrow-band source (typically a single frequency laser) and the optical frequency of a nearby comb line. Thus, the absolute unknown frequency can be determined if the absolute frequencies of the comb lines are known. This requires measurement of f_{rep} and δ. The repetition rate, f_{rep}, is easily measured with a fast photodiode. Measurement of δ requires somewhat greater effort.

The development of a 'self-referencing' method to easily measure δ is the key enabling breakthrough that has brought about the recent revolution in optical-frequency metrology. It is called self-referencing because it provides a direct measure of δ with no other optical frequencies as input. It works by comparing frequencies that differ by a factor of two (typically these lie in the wings of the spectrum) using second-harmonic generation. Specifically, the frequency difference between the second harmonic of a comb line n and the comb line $2n$ is given by $2f_n - f_{2n} = 2(nf_{\mathrm{rep}} - \delta) - (2nf_{\mathrm{rep}} - \delta) = \delta$. Such a frequency difference is easily measured using a heterodyne beat. This technique is shown schematically in Figure 5. Other variations on this basic idea are possible; for example, rather than frequency doubling the comb itself, it is also possible to extract the same information by comparing the comb lines to a single-frequency laser and its second harmonic.

Implementation of the self-referencing technique requires a pulse spectrum that spans a factor of two in frequency (an optical octave). Although a laser has recently been demonstrated that produces such a broad spectrum, they are not commonly available. However, the development of microstructured fiber has made it easy to broaden the spectrum of ordinary mode-locked lasers so that it spans an octave, as was first demonstrated by Ranka and co-workers at Bell Labs. The broadening occurs because optical nonlinearity in the fiber results in self-phase modulation of the laser pulse. Microstructure fiber achieves guiding by surrounding the core region with microscopic air holes, as compared to regular fiber that uses doping to produce a difference in the index of refraction. The much larger difference in the index of refraction in microstructure fiber allows a smaller core region to be used, which increases the effective nonlinearity. It also makes it possible to modify the dispersion such that the group velocity dispersion goes through zero for light with a wavelength close to 800 nm. This is crucial because group-velocity dispersion in ordinary fiber causes ultrashort pulses to temporally spread, which lowers the peak power and hence nonlinearity. It is possible to implement self-referencing techniques using less bandwidth if higher orders of nonlinearity are used; for example, if the difference between the second harmonic of the high-frequency end and third harmonic of the low-frequency end of the comb are used, only a half-octave bandwidth is required.

Given the ability to measure both f_{rep} and δ, and as long as its frequency lies within the comb spectrum, it is possible to measure the optical frequency of any optical source by measuring the heterodyne beat with a nearby comb line. Thus, an absolute optical frequency measurement comes down to measuring three RF frequencies. It is often advantageous to actively control either one or both of f_{rep} and δ to hold them to a fixed frequency. This requires real-time adjustment of some parameters of the mode-locked laser to affect the necessary feedback. Controlling f_{rep} is straightforward; it is achieved by simply changing the cavity length of the laser, typically by mounting a mirror on a piezoelectric transducer. Controlling δ is more challenging, as it requires a differential change between the cavity group delay and phase delay. This has been achieved by adjusting the pump power, which in turn controls the energy of the intracavity pulse, and/or by tilting the end mirror of the cavity in lasers that employ prism dispersion compensators. Since the optical spectrum is spread out across this mirror, tilting it can be thought of as a frequency-dependent change in the cavity length, with the optical frequency corresponding to the pivot point of the tilt experiencing no length change, while those on opposite sides of the pivot point see changes with opposite signs.

In addition to the three RF frequencies, it is necessary to know the large integer n that describes the comb line that is beat against the unknown source. If a priori knowledge about the unknown source is available with precision somewhat better than $f_{\mathrm{rep}}/2$ or better, n can readily be determined. For typical mode-locked lasers, standard commercial wavemeters can provide this level of precision. In the absence of additional outside information, n can also be determined with some effort and precision measurements by changing f_{rep} and δ in a systematic fashion. In the end, the simple formula $f_n = nf_{\mathrm{rep}} + \delta$ gives the optical frequency of any arbitrary nth mode of the femtosecond optical comb. With this established, the frequency of any single-mode laser within the octave span of the comb can be determined simply by measuring the frequency of the beat-note generated in a photodiode between the cw laser and the known frequencies of the comb.

The diagram in Figure 6 shows how a femtosecond comb acts as an optical frequency synthesizer, which provides frequencies that are known relative to the input frequency (provided by a hydrogen maser in the figure). A typical series of measurements is shown in Figure 7 for the NIST Hg^+ single ion standard. The inset shows the results of numerous measurements for the frequency of Hg^+ relative to the NIST primary cesium standard.



Figure 6 Schematic example of how the femtosecond comb is configured to make optical frequency measurements relative to the reference frequency provided by a hydrogen maser (Maser) that is in turn calibrated to a cesium atomic frequency standard. The repetition rate of the pulses from the Ti:Sapphire laser are detected in a photodiode and are controlled using a piezoelectric transducer (PZT) that changes the length of the laser cavity. The microstructure fiber and second harmonic crystal (SHC), provide the 'self-referencing' beat-note signal that is used to control the offset frequency, δ, by changing the power of the pump laser with an electro-optic modulator (EOM). This 'self-referenced' system then provides a set of modes with known frequencies spanning the visible. An unknown laser frequency can then be measured by making a beat-note with one of the modes of the comb.



Figure 7 Actual frequency measurements of the beat-note between a hydrogen maser stabilized optical frequency comb (as shown in Figure 6) and the NIST Hg^+ optical frequency standard. The scatter in the data for counter gate time of 10 seconds corresponds to a fractional frequency uncertainty of about 4×10^{-14}, consistent within the instability in the maser. The inset shows the results from numerous datasets of measurement of the frequency of the Hg^+ optical standard relative to the cesium primary standard at NIST. The frequency data are plotted relative to 1064 721 609 899 142.6 Hz. The dotted lines give estimates of systematic uncertainties in lieu of a complete accuracy evaluation.

Table 1 Summary of optical frequency measurements of a selection of molecular, atomic, and ionic transitions. Recent measurements listed for all and additional measurements are given for a few to indicate the level of agreement

Atom/molecule/ion	*Wavelength (nm)*	*Frequency (THz)*	*Uncertainty*		*Year*	*First author and institution*
			± *Hz*	*Frac.*		
O_sO_4	10318.0	29.054 057 446 660	50	2×10^{-12}	1985	Clarion, LPTF
		29.054 057 446 579	10	3×10^{-13}	1999	Ducos, LPTF
CH_4	3392.2	88.376 181 627 000	50 000	6×10^{-10}	1972	Evenson, NBS
		88.373 149 028 553	200	2×10^{-11}	1998	Ering, PTB
Rb−2 photon	778.11	385.285 142 367 000	8000	2×10^{-11}	1993	Nez, ENS
		385.285 142 374 800	3000	8×10^{-12}	2000	Diddams, JILA
Sr^+	674.03	444.779 904 409 540	200	4×10^{-13}	1999	Bernard, NRC
Ca	657.45	455.986 240 495 150	8	10×10^{-14}	2003	Helmcke, PTB
		455.986 240 494 158	26	6×10^{-14}	2000	Udem, NIST
I_2 a_{15} of $R(127)$ 11-5	632.99	473.612 340 492 000	74 000	2×10^{-10}	1983	Jennings, NBS
I_2 a_{16} of $R(127)$ 11-5	632.99	473.612 353 604 800	1200	3×10^{-12}	2000	Ye, JILA
I_2 a_{10} of $R(56)$ 32-0	532.24	563.260 223 480 000	70 000	1×10^{-10}	1995	Jungner, JILA
		563.260 223 514 000	5000	9×10^{-12}	2000	Diddams, JILA
Yb^+	435.51	688.358 979 230 931	6	9×10^{-15}	2001	Stenger, PTB
H 2*S*-8*S*	389.01	770.649 561 581 100	5900	8×10^{-12}	1997	de Bouroir, ENS
Hg^+	281.57	1064.721 609 899 140	10	9×10^{-15}	2000	Udem, NIST
In^+	236.54	1267.402 452 899 920	230	2×10^{-13}	2000	von Zanthier, MPQ
H 1*S*-2*S*	121.57	2466.061 413 187 100	46	2×10^{-14}	2000	Holzwarth, MPQ

Summary of Measurements/Standards

Starting with the first measurement of the frequency of the methane-stabilized HeNe laser in 1972, a new laser frequency measurement was reported every year or so using harmonic frequency chains. These are summarized in Table 1. An indication of the history of frequency measurements of stable laser references is given in Figure 8. The accuracy, in terms of fractional frequency uncertainty, improved from 10^{-10} in 1972 to 10^{-12} in 1999, at which time the femtosecond optical frequency combs came on line and there was a dramatic improvement in the precision as well as the number of measurements that were completed. It is impossible to predict with certainty but some have projected that optical standards can ultimately reach uncertainties as small as 10^{-18}.



Figure 8 Progress in the accuracy of optical frequency measurements.

Outlook

Three separate technologies have now reached a level of maturity that it is possible to build high-performance optical-frequency standards and clocks. The essential achievements are: laser cooling and trapping of atoms (first proposed by Wineland and Dehmelt, and Hänsch and Schawlow), highly stabilized narrow-linewidth cw lasers, and femtosecond optical frequency combs. Combining these key ingredients, we can construct an optical atomic clock as shown schematically in Figure 9.

Here, for comparison with Figure 1, the cold atoms or single ion provide the narrow atomic resonance, the cw laser serves as the local oscillator to probe the resonance, and the femto-comb serves as the counter. Optical frequency standards of the future are expected to provide orders of magnitude better stability and improved accuracy over the existing atomic frequency standards that now use microwave transitions in atoms. As described in the previous section, frequency combs produced by femtosecond lasers can directly measure the frequency of a stable laser locked to an atomic transition relative to a known microwave frequency standard. This gives fundamental information about the atomic energy levels, and structure, and allows comparisons between different elements. However, to take


Self-referencing of comb offset
f_o
$I(f)$
Femtosecond laser + microstructure fiber
f
f_m
f_b
f_r
Clock output
$f_r = f_A/m$
counter
Optical frequency standard (f_A)

Figure 9 Simplified schematic of an optical clock.

advantage of the high stability of the optical references we run the system as an optical clock (Figure 9) where the stable laser and the femto-comb are locked to the atomic resonance, and the clock output comes as pulses at the repetition rate (e.g., 1 GHz) of the femtosecond mode-locked laser. With a judicious choice of control parameters it is possible to have the pulse repetition frequency, i.e., the clock output, at an exact subharmonic of the optical transition frequency. It is intriguing to note that a portable optical clock could measure time and length at the same time.

See also

Instrumentation: Spectrometers. **Quantum Electrodynamics:** Quantum Theory of the Electromagnetic Field.

Further Reading

Barnett JE (1998) Time's Pendulum. New York: Plenum.

Bergquist JC, Jefferts SR and Wineland DJ (2001) Time measurement at the millennium. *Physics Today* March: 37–42.

Cundiff ST, Ye J and Hall JL (2001) Optical frequency synthesis based on mode-locked lasers. *Reviews of Scientific Instruments* 72: 3749–3771.

Diddams SA, Jones DJ, Ye J, *et al.* (2000) Towards the ultimate control of light. *Optics and Photonics News* October: 16–22.

Diddams SA, Udem T, Bergquist JC, *et al.* (2001) An optical clock based on a single trapped ^{199}Hg^{+} ion. *Science* 293: 825–828.

Diels JC and Rudolph W (1996) Ultrashort Laser Pulse Phenomena. San Diego, CA: Academic Press.

Hall JL (2000) Optical frequency measurement: 40 years of technology revolutions. *IEEE Journal of Selected Topics in Quantum Electronics* 6: 1136–1144.

Hall JL and Ye J (2001) A new era of frequency standards and optical frequency measurements. *Optics and Photonics News* February: 45–50.

Hänsch TW and Walther H (1999) Laser spectroscopy and quantum optics. *Reviews of Modern Physics* 71: S242–S252.

Hollberg L, Diddams SA, Curtis EA, Oates CW and Fox RW (2001) Optical frequency standards for clocks of the future. In: The International Society for Optical Engineering. *Harnessing Light: Optical Science and Metrology at NIST.* Bellingham, DC. *Proceedings of SPIE* 4450: 54–59.

Jennings DA, Evenson KE and Knight DJE (1986) Optical frequency measurements. *Proceedings of the IEEE* 74: 168–179.

Jespersen J and Fitz-Randolph J (1977) From Sundials to Atomic Clocks. New York: Dover.

Jones T (2000) Splitting the Second: The Story of Atomic Time. Bristol, UK: Institute of Physics.

Luiten AN (2001) Frequency Measurement and Control: Advanced Techniques and Future Trends. Berlin: Springer-Verlag.

Menoni CS (ed.) (2001) Feature section on optical frequency synthesis: a new tool for precision optical frequency metrology. *IEEE Journal of Quantum Electronics* 37: 1481–1513.

Quinn TJ (1999) Practical realization of the definition of the metre. *Metrologia* 36: 211–244.

Fourier Transform Spectroscopy

T Fromherz, Johannes Kepler Universität, Linz, Austria

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Fourier transform spectroscopy (FTS) has emerged as one of the most powerful spectroscopic techniques since the first instruments became commercially available in the late 1960s. With this method, high spectral resolution, high wavenumber accuracy, broad spectral range, high optical throughput, and high signal to noise ratio can be achieved simultaneously. Because of these combined advantages that will be discussed in more detail throughout this article, especially in the far- (10–500 cm^{-1}) and mid-infrared (FIR and MIR) spectral region (500–5000 cm^{-1}), FTS has become the method of choice for the most sensitive spectral investigations. In this article, an overview of the setup, the working principle, and the computation of spectra from the measured interferograms will be given. Finally, by comparing FTS to dispersive spectroscopic methods, the conditions under which FTS can be exploited to advantage, will be discussed.

Spectrometer Setup

Almost all commercially available Fourier transform (FT) spectrometers are based on a Michelson interferometer. A typical layout of this interferometer is sketched in Figure 1. A collimated beam with spectral density $S(\sigma)$ entering the spectrometer is divided into two beams by a beamsplitter. Here, σ denotes the wavenumber that is related to the wavelength (λ) of the radiation by $\sigma = 1/\lambda$. As shown in Figure 1, one part of the radiation is reflected by the beamsplitter and propagates through the compensator plate to a fixed mirror. The mirror reflects the beam through the compensator plate back onto the beamsplitter. The other part of the radiation beam is transmitted through the beamsplitter and its substrate, and hits a moveable mirror from which it is reflected back onto the beamsplitter. At the beamsplitter, both beams are divided again. As shown in Figure 1, two beams, one propagating to the source, the other propagating to the detector, finally result. Both beams contain a contribution that was reflected by the fixed mirror and a second contribution that was reflected by the moveable mirror. In Figure 1, lines indicate the paths of the beams schematically. In the case of a reflection on the beamsplitter, the line type is changed in Figure 1, whereas for a transmission, the line type remains unchanged. The widths of the lines in Figure 1 indicate the size of the field amplitudes and, therefore, are reduced for each reflection/transmission on the beamsplitter. For clarity, the lines indicating the beams reflected into themselves by the fixed and moveable mirrors in Figure 1 are offset laterally.



Figure 1 Schematic sketch of the layout of a Michelson interferometer. The paths of the rays are indicated by lines and arrows. At a reflection on the beamsplitter, the line type is changed, whereas for a transmission it remains unchanged. The widths of the lines indicate the size of the field amplitudes. For clarity, the lines indicating the beams reflected into themselves by the fixed and moveable mirrors, are offset laterally. The inset shows a magnified cross-section of the beamsplitter. In the inset, the geometrical details used for calculating the phase difference between *R* and *T* are defined.

By changing the position of the moveable mirror along the beam axis, a difference between the optical paths from the beamsplitter to the fixed and moveable mirror is generated. The compensator consists of the same material and has the same thickness as the beamsplitter substrate and, therefore, minimizes the influence of the dispersion of the beamsplitter substrate on the optical path difference.

Fourier Analysis and Interferometry

To calculate the intensities of the combined beams falling on the detector and on the source, we start by considering the phase difference between the reflected and transmitted beams leaving the beamsplitter. For simplicity, we ignore the compensator and beamsplitter substrate, since ideally, they generate the same phases in both arms of the interferometer, and therefore, do not contribute to the phase difference. Thus the beamsplitter is regarded as a freestanding, dielectric slab with thickness d. The complex reflection (R) and transmission (T) coefficients, including the effect of multiple internal reflections within the beamsplitter layer, are given by:

$$\begin{aligned} R &= r(1 - e^{i2\gamma})/(1 - r^2 e^{i2\gamma}) \\ T &= e^{i\gamma}(1 - r^2)/(1 - r^2 e^{i2\gamma}) \end{aligned} \qquad [1]$$

Here, r is the Fresnel reflection coefficient that describes the ratio of the moduli and the phase difference between incoming and reflected electrical field for a electromagnetic wave incident under a angle Θ_1 on the surface of a dielectric with dielectric constant n, and $\gamma = 2\pi\sigma n d \cos(\Theta_2)$ is the phase difference evaluated at P_1 and P_2 in Figure 1 for a single pass of the electromagnetic wave through the dielectric slab under the angle Θ_2 (by Snellius law, $\sin(\Theta_1) = n \sin(\Theta_2)$). Since n is real, so is r and, therefore, the phase difference $\Delta\varphi$ between R and T is calculated from eqn [1] according to:

$$\begin{aligned} \frac{R}{T} &= \frac{|R|}{|T|} e^{i\Delta\varphi_{RT}} = \frac{r}{1 - r^2}(e^{-i\gamma} - e^{i\gamma}) \\ &= -2i \frac{r}{1 - r^2} \sin(\gamma) \end{aligned} \qquad [2]$$

i.e., $\Delta\varphi_{RT} = -\pi/2$. With this result, we are able to calculate the phase difference between the two rays falling on the detector and the two rays falling back on the source. The geometry considered in the following is sketched in Figure 1. The coefficients R and T connect the phases and magnitudes of reflected and transmitted electric field amplitudes at the points P_1 and P_2. From these points, the radiation beams travel back and forth to the fixed and moveable mirrors, thereby accumulating phases according to: $\varphi_f = 2\pi 2x_f\sigma$ and $\varphi_m = 2\pi 2(x_f + \Delta x)\sigma$, where we have defined $\Delta x = x_m - x_f$ and x_m, x_f denote the distances of moveable and fixed mirrors from the points P_1 and P_2. The two planewaves falling on the detector interact twice with the beamsplitter. Each planewave is once reflected at and once transmitted through the beamsplitter. Therefore, the beamsplitter adds no additional phase difference to the two planewaves and the total phase difference is given by $\Delta\varphi = \varphi_m - \varphi_f$. The situation is different for the two beams falling back on the source. Here, one beam is reflected at both interactions with the beamsplitter, whereas the other is transmitted at both interactions. According to eqn [2], between these two beams an additional phase shift of π results. Quantitatively, the total field amplitude at the detector, neglecting an arbitrary phase, is given by $E_D = E_0RT(e^{i\varphi_m} + e^{i\varphi_f})$, and the corresponding intensity is:

$$\begin{aligned} I_D \propto E_D E_D^* &= 2|E_0|^2|R|^2|T|^2\{1 + \mathrm{Re}[e^{i(\varphi_m - \varphi_f)}]\} \\ &= 2|E_0|^2|R|^2|T|^2\{1 + \cos(4\pi\sigma\Delta x)\} \end{aligned} \quad [3]$$

The sum of the field amplitudes falling back on the source is $E_S = E_0(R^2e^{i\varphi_m} + T^2e^{i\varphi_f})$. For the intensity one gets:

$$I_S \propto E_S E_S^* = |E_0|^2\{|R|^4 + |T|^4 + 2\mathrm{Re}[R^2T^{*2}e^{i(\varphi_m - \varphi_f)}]\} \quad [4]$$

Denoting the complex coefficients R and T by their modulus and their phase $R = |R|e^{i\varphi_R}$, $T = |T|e^{i\varphi_T}$ and using eqn [2], one gets:

$$I_S \propto |E_0|^2\{|R|^4 + |T|^4 + 2|R|^2|T|^2\cos(4\pi\sigma\Delta x + \pi)\} \quad [5]$$

Both intensities, I_D and I_S contain a constant component and a component that varies with $\cos(4\pi\sigma\Delta x)$. The varying parts have the same amplitude $2|E_0|^2|R|^2|T^2|$ but are out of phase by π. Consequently, a maximum in I_D corresponds to a minimum in I_S and the sum of both intensities is independent of the mirror displacement Δx.

In most of the commercially available spectrometers, only I_D is used for spectral measurements. Usually, the detector signal is amplified by an AC coupled electronics. Therefore, in a measurement of $I_D(\Delta x)$, the constant part of the signal is suppressed. Assuming a spectral density $S(\sigma)$ of the source and an ideal detector with a responsivity R_D linear in the intensity and independent of the wavenumber σ, the detector signal $D(\Delta x)$ is given by:

$$D(\Delta x) = R_D \int_0^\infty S(\sigma)\cos(4\pi\sigma\Delta x)d\sigma \quad [6]$$

The information about the spectrum is contained in $S(\sigma)$ and can be extracted from the interferogram $D(\Delta x)$ by a cosine Fourier transformation. The transformation has to be done numerically and, therefore, it is more convenient to use a complex, fast Fourier transform algorithm. For that purpose, eqn [6] is modified by using the complex expansion of the cosine $\cos(x) = (e^{ix} + e^{-ix})/2$:

$$\begin{aligned} D(\Delta x) &= \frac{R_D}{2}\left(\int_0^\infty S(\sigma)e^{i4\pi\sigma\Delta x}d\sigma + \int_0^\infty S(\sigma)e^{-i4\pi\sigma\Delta x}d\sigma\right) \\ &= \frac{R_D}{2}\left(\int_0^\infty S(\sigma)e^{i4\pi\sigma\Delta x}d\sigma + \int_{-\infty}^0 S(-\sigma)e^{i4\pi\sigma\Delta x}d\sigma\right) \end{aligned} \quad [7]$$

Extending $S(\sigma)$ to negative wavenumbers according to:

$$S'(\sigma) = \begin{cases} S(\sigma) & \text{for } \sigma \geq 0 \\ S(-\sigma) & \text{for } \sigma < 0 \end{cases} \quad [8]$$

leads to the following expression for the interferogram:

$$D(\Delta x) = \frac{R_D}{2}\int_{-\infty}^\infty S'(\sigma)e^{i4\pi\sigma\Delta x}d\sigma \quad [9]$$

and the spectral density $S'(s)$ can be obtained by the complex Fourier transform according to:

$$S'(\sigma) = \frac{4}{R_D}\int_{-\infty}^\infty D(\Delta x)e^{-i4\pi\sigma\Delta x}d(\Delta x) \quad [10]$$

In the following, we will skip the prime and S will refer to the spectral density extended to negative values of σ.

To calculate the spectral density according to eqn [10], one has to use an interferogram extending from $-\infty$ to $+\infty$ measured at infinitely small sampling distances $d(\Delta x)$. In practise, of course, the interferogram is measured only between finite mirror displacements $-\Delta x_{max}$ and Δx_{max}, at sampling points equally spaced by ξ.

The effect of the finite mirror displacement on the resulting spectral density S can be included into eqn [10] by multiplying the interferogram $D(\Delta x)$ with a function that vanishes for $|\Delta x| > \Delta x_{max}$. As an example, we use the boxcar function

$\theta(\Delta x + \Delta x_{\max})\theta(\Delta x_{\max} - \Delta x)$, where $\theta(x)$ is the Heavyside step function with values 0 and 1 for $x < 0$ and $x > 0$, respectively, and calculate the output spectrum for a spectral density $S_1(\sigma)$ consisting of a single line at wavenumber $\sigma_0 : S_1(\sigma) = (\delta(\sigma - \sigma_0) + \delta(\sigma + \sigma_0))/2$ (note that the spectral density is extended to negative wavenumbers according to the definitions given above). According to eqn [9], the interferogram is $D_1(\Delta x) = (R_D/2)\cos(4\pi\sigma_0\Delta x)$. Multiplying the interferogram with the boxcar function and Fourier transforming the product back using eqn [10], the resulting spectral density S_1^{box} is:

$$S_1^{\text{box}} = 2\Delta x_{\max}\left\{\frac{\sin[4\pi(\sigma_0 - \sigma)\Delta x_{\max}]}{4\pi(\sigma_0 - \sigma)\Delta x_{\max}} + \frac{\sin[4\pi(\sigma_0 + \sigma)\Delta x_{\max}]}{4\pi(\sigma_0 + \sigma)\Delta x_{\max}}\right\} \qquad [11]$$

Therefore, the approximation to a monochromatic spectrum is a sum of $\text{sinc}(z_\pm)$ ($= \sin(z_\pm)/z_\pm$) functions where $z_\pm = 4\pi(\sigma_0 \pm \sigma)\Delta x_{\max}$. The lineshape function S_1^{box} is plotted around σ_0 in Figure 2 by the full line. Compared to the monochromatic spectrum S_1, the lines of S_1^{box} have a finite linewidth with a fullwidth at half maximum (FWHM) of approximately $0.3/\Delta x_{\max}$. As a general rule in spectroscopy, two spectral lines of equal intensity and linewidth have to be separated at least by their FWHM, in order to be clearly distinguishable. According to this definition, the limit of resolution of a FT spectrometer $\Delta\sigma_{\min}$ is inversely proportional to the maximum mirror displacement and given by $\Delta\sigma_{\min} = 0.3/\Delta x_{\max}$.

A less precise, but more intuitive definition of the resolution refers to the difference of the phases of the interferograms corresponding to two monochromatic lines separated by $\Delta\sigma$. The two lines are defined to be resolvable if the phases of their interferograms differ by more than 2π between the mirror positions $-\Delta x_{\max}$ and $\Delta x_{\max}$, i.e., the beating in the superposition of the interferograms shows at least one period. It is easily seen that, according to this definition $\Delta\sigma_{\min} = 1/(2\Delta x_{\max})$, a result in good agreement but slightly larger than that obtained by the more precise definition given above.



Figure 2 Normalized lineshape functions for boxcar (full line) and triangular apodization (broken line). In the inset, the corresponding apodization functions are shown.

As shown in Figure 2 by the full line, the sinc function has negative side-lobes with magnitudes of up to 22% of the maximum value. For some spectroscopic applications this side lobes are unwanted since they lead to a suppression of smaller peaks separated by approximately the resolution limit of the spectrometer. Thus, in these cases, it appears to be reasonable to multiply the interferogram by a (apodization) function different from the natural boxcar function. Usually, triangular or trapezoidal functions vanishing for $|\Delta x| > \Delta x_{\max}$ are used. By Fourier transformation of these functions, it can be shown that no negative side lobes are generated. However, these functions have a larger (up to ~50%) peak FWHM than the sinc function. For comparison, in Figure 2, also the lineshape of a monochromatic spectrum using a triangular apodization function $A(\Delta x) = \theta(\Delta x + \Delta x_{\max})\theta(\Delta x_{\max} - \Delta x)(1 - |\Delta x/\Delta x_{\max}|)$ is shown by the broken line. In this case, the negative sidelobes are strongly suppressed but the FWHM is increased.

Generally, the output spectrum $S^{\text{A}}(\sigma)$ corresponding to an arbitrary spectral density $S(\sigma)$ and an apodization function $A(\Delta x)$ is given by the convolution $S^{\text{A}}(\sigma) = 2[S \otimes A^{\text{FT}}](\sigma)$, where the lineshape function A^{FT} is the Fourier transform of $A(\Delta x)$:

$$A^{\text{FT}}(\sigma) = \int_{-\infty}^{\infty} A(\Delta x)\text{e}^{-4\pi\sigma\Delta x}\text{d}(\Delta x) \qquad [12]$$

and

$$[f \otimes g](t) \equiv \int_{-\infty}^{\infty} f(\tau)g(t - \tau)\text{d}\tau \qquad [13]$$

Discrete Sampling

In order to discuss the effect of the discrete, equally spaced sampling points with a mutual distance of ξ on the output spectrum, Δx is replaced by $x_n = n\xi$ in eqn [10], where n is an integer and runs from $-N_{\max}$ to $N_{\max}$ and $N_{\max}\xi = \Delta x_{\max}$. Instead of the continuous interferogram $D(\Delta x)$, a discrete interferogram:

$$D_n = \frac{R_D}{2}\int_{-\infty}^{\infty} S(\sigma)\text{e}^{\text{i}4\pi n\xi\sigma}\text{d}\sigma \qquad [14]$$

results. From eqn [14], it is readily seen (by shifting the integration variable) that replacing $S(\sigma)$ with $S[\sigma + m/(2\xi)]$, where m is an integer, does not change the discrete interferogram D_n. Keeping in mind that according to our definition $S(-\sigma) = S(\sigma)$, it is clear that $S[-\sigma + m/(2\xi)]$ also leads to the same interferogram as $S(\sigma)$. Therefore, to be able to transform the interferogram to the spectral density $S(\sigma)$ for a wavenumber band $[0, \sigma_{\max}]$ unambiguously, one has to make sure, by electronically and/or optical filtering, that no wavenumbers outside this range contribute to the interferogram and that the sampling interval ξ is small enough so that $\sigma_{\max} < -\sigma_{\max} + 1/(2\xi)$, i.e., $\sigma_{\max} < 1/(4\xi)$. In Figure 3, a schematic sketch of a spectral density $S(\sigma)$, consisting of two spectral bands shown by the full and dashed lines, is plotted. For the spectral band shown by the full line, the sampling interval ξ is small enough so that in the interval $[0, 1/(4\xi)]$ no ambiguity arises. For the spectral band shown by the dashed line, the interferogram appears to be under-sampled: ξ is too large, and, therefore, the part of the spectral band at negative wavenumbers shifted by $+1/(2\xi)$ falls into the interval $[0, 1/(4\xi)]$ (shown by the dotted line in Figure 3). Thus, for the sampling interval ξ, the interferogram for the sum of spectral bands, shown by the full and the dashed lines in Figure 3, is the same as for the sum of the spectral bands shown by the full and dotted lines. Since the interferograms are the same, the two spectra are indistinguishable at sampling intervals ξ. This ambiguity of spectra for an under-sampled interferogram is called aliasing. Comparing the correct sampling interval $\xi < 1/(4\sigma_{\max})$ with the period of the interferogram D_n corresponding to a spectrum consisting of a single line at $\sigma_{\max}$ ($D_n = R_D\cos(4\pi n\xi\sigma_{\max})$), it follows that the interferogram has to be sampled more than two times per period in order to obtain an unambiguous result (Nyquist Theorem).



Figure 3 Schematic sketch of aliasing for under-sampled interferograms. For spectral density shown by the full line, the sampling interval ξ is chosen correctly and the $1/(2\xi)$ wavenumber ambiguity indicated by the arrows in the plot does not result in erroneous features in the spectral range $[0, 1/(4\xi)]$. The situation is different for the spectral band sketched by the dashed line: For this band, the sampling interval ξ is too large, and consequently, the $1/(2\xi)$ wavenumber ambiguity maps the line from the negative wavenumber region into the range $[0, 1/(4\xi)]$. The mapped spectral band is indicated by the dotted line.

Mathematically, the spectral density is calculated from the discrete interferogram D_n by a discrete Fourier transformation:

$$S_m = \frac{2}{R_D N}\sum_{n}^{N} D_n e^{-2\pi i nm/N} \qquad [15]$$

where N is the number of sampling points ($N = 2N_{\max} + 1$) and the wavenumbers corresponding to S_m are given by $\sigma_m = m/2\xi N$.

In order to obtain a high accuracy in the sampling intervals ξ, usually a reference interferogram of a monochromatic laser line (for example from a HeNe laser) is measured simultaneously with the interferogram of the actual experiment. By counting, for example, the zeros with positive slope in the interferogram of the laser line, uniformly spaced sampling points can be achieved with high accuracy. If, in an experiment many interferograms have to be averaged, the absolute position of the sampling points is important, in order to ensure that only points of equal mirror displacement are averaged. Therefore, in some spectrometers, the interferogram of a broadband source is measured simultaneously with the interferograms of the laser and the experiment and the maximum of the interferogram of the broadband source is taken as the origin for counting the zeros of the laser interferogram.

Phase Correction

Ideally, the interferogram is expected to be symmetrically around the position of equal optical path in the two arms of the interferometer. However, in practise this is seldom the case. Many reasons can lead to an asymmetric interferogram, the most obvious being that none of the discrete sampling points of the interferogram coincides with the mirror position for equal optical path in the two interferometer arms. Let Δx_m be the measured mirror displacement that differs from the real mirror displacement Δx by x_0, i.e., $\Delta x = \Delta x_m + x_0$. In that case the measured interferogram is:

$$D(\Delta x_m) = \frac{R_D}{2}\int_{-\infty}^{\infty} S(\sigma) e^{i[4\pi\sigma(\Delta x_m + x_0)]} d\sigma \qquad [16]$$

and the Fourier transformation, according to eqn [10] with Δx_m as the integration variable, results in

$S(\sigma)e^{i4\pi x_0\sigma}$, that is, in a spectrum with both real and imaginary parts. Also, mirror or compensator misalignment can result in a wavenumber-dependent optical path at a fixed mirror position. Finally, for rapid-scan interferometers, in that the movable mirror is scanned at a constant velocity v, the electronic filtering and amplification of the detector signal will also add different phases, depending on the signal frequency ν that is correlated to the wavenumber σ by $\nu = 2\sigma v$. In general, as long as the phase φ depends only on the wavenumber and not on the mirror displacement, the measured interferogram is:

$$D(\Delta x_m) = \frac{R_D}{2} \int_{-\infty}^{\infty} S(\sigma) e^{i[4\pi\sigma\Delta x_m + \varphi(\sigma)]} d\sigma \qquad [17]$$

and by the Fourier transformation, according to eqn [10], one obtains $S(\sigma)e^{i\varphi(\sigma)}$. There are several methods implemented in the software of commercially available Fourier spectrometers to eliminate the phase from the Fourier transform. In most experimental cases, in that the measured interferograms correspond to spectra with $S(\sigma) \geq 0$ for all $\sigma \in [0, \sigma_{max}]$, these methods usually give the correct results. However, care has to be taken if spectra contain positive and negative components. This can be the case, for example, if the transmission of a sample is periodically modulated by externally applied voltage or a laser light and the detector signal is amplified by a lock-in technique before it is fed into the electronics of the Fourier transform spectrometer. If the modulation increases the sample absorbance in one part of the spectral range and decreases it in a different part, then the measured interferogram corresponds to a spectrum with both negative and positive regions. In the following, first the phase correction methods for spectra with positive values only are discussed before it is argued, why these methods might fail for spectra with positive and negative parts.

For spectra with only positive values, the most simple method to eliminate the unknown phase is to measure the interferogram symmetrically around $\Delta x_m = 0$ and calculate $S(\sigma)e^{i\varphi(\sigma)}$ according to eqn [10]. Including the effect of finite scan length, the output spectrum becomes $S^A = 2[S(\sigma)e^{i\varphi(\sigma)}] \otimes A(\sigma)^{FT}$. Under normal experimental conditions, the phase $\varphi(\sigma)$ does not vary over the peak FWHM of $A(\sigma)^{FT}$ and, therefore, the phase term can be put outside the integral of the convolution and $S^A = 2e^{i\varphi(\sigma)}[S(\sigma) \otimes A(\sigma)^{FT}]$ results. Since $A(\Delta x_m) \geq 0$, and chosen to be symmetric around $\Delta x_m = 0$, the convolution is real and positive and the true spectrum with instrumental resolution $2[S(\sigma) \otimes A(\sigma)^{FT}]$ can be obtained by calculating the modulus of S^A without any knowledge about $\varphi(\sigma)$. However, for several reasons this method for phase correction is not ideal. First of all, since the maximum spectral resolution of a Fourier transform spectrometer is inversely proportional to the maximum mirror displacement, for a given spectrometer layout with a fixed maximal mirror scan length L, the maximal achievable spectral resolution is reduced by a factor of two if scans symmetric around $\Delta x = 0$ have to be performed. Secondly, for signals closer to or smaller than the noise level of the spectrometer, the random noise will be entirely positive by taking the modulus. Hence, for small signals, the noise level will be increased relative to the signal level by taking the modulus.

Therefore, usually the 'Mertz phase correction method' is used. This method is based on the assumption that the phase $\varphi(\sigma)$ is a slowly varying function of σ. In this case, $\varphi(\sigma)$ can be determined with low spectral resolution, i.e., by a short, symmetric scan of length $2L_1$ around $\Delta x = 0$. It can be shown that from this scan the phase can be obtained according to:

$$\varphi(\sigma) = \arctan\left\{ \frac{\mathrm{Im}[S(\sigma)e^{i\varphi(\sigma)} \otimes A^{FT}(\sigma)]}{\mathrm{Re}[S(\sigma)e^{i\varphi(\sigma)} \otimes A^{FT}(\sigma)]} \right\} + \pi \,(\text{if denominator is negative}) \qquad [18]$$

Here, $S(\sigma)e^{i\varphi(\sigma)} \otimes A(\sigma)^{FT}$ results from the Fourier transformation of the short interferogram measured between $-L_1$ and L_1 and the apodization function $A(\Delta x_m)$ is adjusted to $-L_1$ and L_1. The addition of π for negative denominators is a consequence of the assumption that $S(\sigma)$ is positive everywhere. Under this assumption, a negative denominator in eqn [18] corresponds to a phase angle $|\varphi(\sigma)| > \pi/2$, that is mapped into $[-\pi/2, \pi/2]$ by the arctan-function. To get the correct phase angle, π has to be added to the phase angle, thereby extending the range of $\varphi(\sigma)$ to $[0, 2\pi]$.

With $\varphi(\sigma)$ known, the interferogram has to be recorded only for mirror displacements $\Delta x_m \geq 0$, since the information about the interferogram for $\Delta x_m < 0$ is contained in the phase spectrum and the interferogram for $\Delta x_m \geq 0$. Therefore, with this method, the totally available mirror displacement length can be used for increasing the spectral resolution.

However, for spectra containing positive and negative spectral bands, the Mertz phase correction usually fails, due to the addition of π if the denominator in eqn [18] becomes negative. For spectra with positive and negative bands, the sign of the denominator is determined by both $S(\sigma)$ and $\varphi(\sigma)$. Applying the Mertz algorithm in a negative region of the spectrum with a vanishing physical phase angle, results in a calculated phase angle of $\varphi = \pi$. As a consequence, the negative spectral band appears as a positive band in the output spectrum calculated according to the Mertz algorithm.

To avoid erroneous phase-flips, the addition of π in eqn [18] for negative denominators can be omitted and the allowed values for $\varphi(\sigma)$ are reduced to $[-\pi/2, \pi/2]$. The corresponding phase correction method is usually referred to as the 'Mertz signed method'. However, it is immediately clear from the discussion above, that in this case any physical phase angle outside the range $[-\pi/2, \pi/2]$ results to an erroneous π-jump of the phase. According to eqn [16], a physical phase shift larger than $\pi/2$ can, for example, be the consequence of a large offset x_0, i.e., of an inaccurate alignment of Δx_m and Δx. At $\Delta x = 0$, all contributions to the interferogram add constructively and the height of the interferogram is proportional to the area under the spectral curve $S(\sigma)$, as can be readily seen by setting $\Delta x = 0$ in eqn [10]. Therefore, for $S(\sigma) > 0$ the position $\Delta x_m = 0$ is usually estimated by the global maximum of the measured interferogram. However, for spectra with both positive and negative bands, in most cases the interferogram does not exhibit a maximum at $\Delta x = 0$ (for positive and negative bands of equal height and width, the interferogram vanishes at $\Delta x = 0$), and estimating $\Delta x_m = 0$ by an extremum of the interferogram results, therefore, in a large offset x_0. Thus, in order to be able to use the 'Mertz signed' algorithm, $\Delta x_m = 0$ has to be determined separately in a calibration experiment in that the condition $S(\sigma) > 0$ is fulfilled. However, even for accurately determined $\Delta x_m = 0$, erroneous phase jumps can appear if lines of different intensity and opposite sign are spaced approximately equal to the resolution used for determining the phase spectrum $\varphi(\sigma)$.

In conclusion, there are no general strategies to completely exclude phase jumps in the Fourier transformation of interferograms corresponding to spectra with positive and negative bands. The experimentalist has to check from case to case if lines with strange shapes appear in the output spectra, and modify the phase correction accordingly. More elaborate strategies for phase correction, that are beyond the scope of this article, are reported in literature.

Example of Experimental Results

To illustrate the features of FTS discussed in the previous paragraphs by a practical example, in Figure 4 the results of a typical measurement in the MIR between 500 cm^{-1} and 5000 cm^{-1} are shown. The experiments were performed with a BRUKER IFS113 spectrometer using a silicon carbide glowbar as a source for the infrared radiation, a potassium bromide beamsplitter, and a liquid-nitrogen cooled mercury cadmium telluride detector. The spectrometer used for the experiments is set up in a vacuum chamber. The two interferograms shown in Figure 4a were measured at two different pressures (broken line: 10 mbar; full line: 300 mbar), i.e., at two different levels of absorption of the atmospheric gas in the interferometer chamber (for clarity, the interferograms are offset vertically). The abscissa axis is broken in Figure 4a and shows portions of the interferograms around zero mirror displacement and around the maximum mirror displacement of 2.5 cm (chosen for 0.2 cm^{-1} spectral resolution). For higher chamber pressures, the increased absorption of the atmospheric gas results in an increased amplitude of the wiggles of the interferogram apparent for large mirror displacements in Figure 4a. The amplitude of these wiggles is approximately three orders of magnitude smaller than the detector signal observed at the center-burst of the interferogram around zero mirror displacement. However, in the corresponding spectra (Figure 4b) calculated from the interferograms after phase correction, the absorption of the atmospheric gas is clearly evident by a strong increase of the dense and narrow absorption lines in the spectral regions 1200 cm^{-1}–2200 cm^{-1}, 2300 cm^{-1}–2400 cm^{-1}, and 3200 cm^{-1}–4000 cm^{-1} (note that in Figure 4b the spectra are offset vertically by 0.1 for clarity). The lines observed between 2300 cm^{-1}–2400 cm^{-1} are due to absorption of the CO_2 molecule and are shown in more detail in Figure 4c from 2335 cm^{-1} to 2345 cm^{-1}. In order to simulate the contribution of the CO_2 lines to the interferogram shown in Figure 4a, two neighboring lines in Figure 4c were fitted to a doublet of Lorentz-absorption lines (indicated by the symbols in Figure 4c). The corresponding interferogram was calculated by Fourier transformation of the Lorentz lines and is shown in Figure 4d. It consists of a rapid oscillating, cosine-like signal (see inset for an expanded plot between 0.6 and 0.602 cm) with an amplitude modulation corresponding to the difference of the resonance wavenumbers of the two Lorentz lines. The ordinate axes of Figures 4a,d have the same arbitrary units and, therefore, the amplitudes of the interferograms shown in these two panels can be directly compared. From Figure 4a, d we conclude that the two CO_2 lines contribute approximately with only one in 10^5 parts to the center-burst of the measured interferogram, i.e., theses lines absorb only a fraction of 10^{-5} of the integrated (over the wavenumbers) intensity of



Figure 4 Measurement of the absorption of atmospheric gas for different pressures in the interferometer chamber (broken lines: 10 mbar, full lines: 300 mbar). (a) Interferograms (note the break in the axis of the mirror displacement). For clarity, the interferograms are offset vertically by 0.1 and 0.0002 on the left and right side of the axis break. On the right side of the axis break, the interferograms are amplified by a factor 500. (b) Spectra corresponding to the interferograms shown in (a). The spectra are offset vertically by 0.1 for clarity. (c) Part of the CO_2 absorption lines on an expanded wavenumber axis. The symbols indicate a fit of two Lorentz lines to neighbouring CO_2 absorption lines. The fit is used for calculating the interferogram shown in (d). (d) Simulated interferogram corresponding to the two CO_2 lines shown by the symbols in (c). The arbitrary units of the ordinate axis are the same as those used in (a) but the interferogram is amplified by a factor 10^5. In the inset, the interferogram is shown on an enlarged scale between 0.6 and 0.602 cm mirror displacement.

the incident radiation. Despite this small fraction, they are extremely well resolved with a large signal-to-noise ratio in Figures 4b,c, thus demonstrating the ability of FTS to measure spectra simultaneously with high resolution and over a large spectral range. This ability is one of the advantages (the so-called multiplex advantage) inherent in FTS and will be discussed in more detail in the following paragraph.

Advantage of FTS Over Dispersive Spectrometer

The two main advantages of FTS over dispersive spectroscopic methods, using, for example, a grating for the spectral decomposition of an incoming radiation, are directly connected with the working principle of FT spectrometers; high optical throughput and multiplexed measurement over the whole spectral range of interest. These advantages are discussed in the following, in more detail.

For a fair comparison of the optical throughput, spectrometers with equal spectral resolving power ρ have to be compared. Here, $\rho = \sigma_{\max}/\Delta\sigma$, where $\sigma_{\max}$ is the maximum wavenumber analyzed and $\Delta\sigma$ is the spectral resolution. For an ideal Fourier transform spectrometer, the limit for $\sigma_{\max}$ depends on the divergence angle of the beams propagating in the spectrometer. As sketched in Figure 5, the divergence angle α is determined by the radius r_a of the entrance aperture and the focal length f of the collimating lens by $\alpha \approx r_a/f$. This angle causes a phase shift between the rays propagating parallel to and those propagating under the angle of α inclined to the optical axis



Figure 5 Entrance aperture and collimating element for an interferometer. For simplicity, the beamsplitter and fixed mirror are omitted in the sketch. The extreme rays entering the interferometer are indicated by the full and broken lines. Due to divergence α, a monochromatic light with wavenumber σ_0 produces all periods in the range $[4\pi\sigma_0, 4\pi\sigma_0/\cos(\alpha)]$ in the interferogram.

through the interferometer. The phase difference φ_{div} depends on the mirror displacement according to $\varphi_{\text{div}} = 4\pi\sigma\Delta x((1/\cos(\alpha)) - 1)$ and can be approximated for small α by $\varphi_{\text{div}} \approx 2\pi\sigma\Delta x\alpha^2$. It can be shown, that as long as φ_{div} does not exceed approximately π, the influence of the divergence on the interferogram can be tolerated, i.e., $\sigma_{\max} \approx 1/(2\Delta x_{\max}\alpha^2)$. Using $\Delta\sigma \approx 1/(2\Delta x_{\max})$ for the resolution, one obtains for the resolving power of a FT spectrometer, $\rho = (f/r_a)^2$.

The optical throughput Θ describes the allowable energy per unit time that the system can let through and is related to area πr_a^2 of the aperture and the solid angle Ω of the collimating (or focusing) optics by $\Theta = \pi r_a^2\Omega$. Using $\Omega = A_{\text{FTS}}/f^2$, where A_{FTS} is the clear area of the collimating lens (for a collimating mirror, A_{FTS} is the area of the mirror projected on a plane perpendicular to the beam direction), results in $\Theta_{\text{FTS}} = \pi A_{\text{FTS}} r_a^2/f^2 = \pi A_{\text{FTS}}/\rho$. For a grating spectrometer, $\Theta_{\text{grating}} = hA_{\text{G}}/f\rho$. (see respective chapter of this encyclopedia) where h is the height of the slit, f the focal length of the collimating optics, and A_{G} the projected area of the grating. Generally, h/f is smaller than 1/20 in up-to-date grating spectrometers. Thus, for the same resolving power ρ and similar instrument size, FT spectrometer can offer a more than $\pi f/h \approx 60$ times larger energy gathering capability. Therefore, for measurements with weak signals in that the detector noise is the dominant noise source, the large throughput of a FTS greatly increases the spectral signal to noise ratio that can be achieved for a fixed measuring time.

The other major principal advantage compared to dispersive methods relies on the simultaneous (multiplexed) gathering of information about all spectral bands $\Delta\sigma$ over a broad spectral range from $\sigma_{\min}$ and $\sigma_{\max}$. For a grating spectrometer using a single detector element, the measurement time T_{m} available for recording the spectrum in that range has to be distributed between the $M = (\sigma_{\max} - \sigma_{\min})/\Delta\sigma$ spectral bands so that for a single spectral band the available integration time is T_{m}/M and the integrated signal increases proportional to T_{m}/M. If the dominant noise source is the detector noise which is independent of the signal level, then the noise will be proportional to $(T_{\text{m}}/M)^{1/2}$ and, therefore, the signal to noise ratio for the grating spectrometer $(S/N)_{\text{G}}$ is:

$$(S/N)_{\text{G}} \propto (T_{\text{m}}/M)^{1/2} \qquad [19]$$

For a FTS the situation is different, since it detects in the band $[\sigma_{\min}, \sigma_{\max}]$ all M small bands over the whole measurement time T_{m} via their contribution to the interferogram. So the integrated signal in a small band $\Delta\sigma$ is proportional to T_{m}. If the noise is again assumed to be random and independent of the signal level, for the FTS:

$$(S/N)_{\text{FTS}} \propto T_{\text{m}}^{1/2} \qquad [20]$$

results. For the same detector, assumed in the grating spectrometer and in the FTS, the proportionality constants are the same in eqns [19] and [20] and, therefore

$$\frac{(S/N)_{\text{FTS}}}{(S/N)_{\text{G}}} = M^{1/2} \qquad [21]$$

Equation [21] shows that the multiplex advantage becomes increasingly important for measurements of broad spectral bands with high resolution. In this case, an enhancement of the $(S/N)_{\text{FTS}}$ over $(S/N)_{\text{G}}$ by 2–3 orders of magnitude can be achieved. However, it has to be noted that the multiplex advantage of a FTS can be exploited only in cases where the detector noise is the dominant source of noise. In the visible and near infrared spectral region, low noise detectors, that allow single photon detection, are available. With these detectors, the spectral noise is dominated by the photon noise that is proportional to the square root of the intensity. It is evident that in this case the multiplexed detection is not an advantage, since for M spectral bands of width $\Delta\sigma$ contributing to the interferogram at a given mirror position, the noise is enhanced by $M^{1/2}$ compared to the noise that would be measured for a single band (here, it is assumed that all M bands contribute with the same intensity to the interferogram). Consequently, in this case, the noise enhancement by $M^{1/2}$ cancels the beneficial factor $M^{1/2}$ in eqn [21] and with single-detector grating and FT spectrometers, the same S/N ratio is achieved for a given measurement time T_{m}. In addition, using linear detector arrays with dispersive spectrometers, the multiplex advantage increases the S/N ratio for the dispersive spectrometer. However, detector arrays and low-noise detectors are mainly available for spectral regions with $\sigma > 6000\ \text{cm}^{-1}$, i.e., in the near-infrared and visible spectral region. In the FIR and MIR region ($\sigma < 6000\ \text{cm}^{-1}$) in that such detectors are absent, the multiplexing inherent in FTS makes it the method of choice if low-noise, broadband, and high-resolution spectroscopic data are required.

List of Units and Nomenclature

Angle of incidence for radiation on beamsplitter	Θ_1
Angle of propagation of radiation in the beamsplitter layer	Θ_2
Beam divergence angle	α
Beam splitter thickness (cm)	d
Complex reflection coefficient	R, r
Complex transmission coefficient	T, t
Detector Signal normalized to detector area (A cm^{-2})	D
Difference between real and measured mirror displacement (cm)	x_0
Dirac delta-function	δ
Discrete interferogram (A cm^{-2})	D_n
Discrete spectral density (W cm^{-1})	S_m
Distance from beamsplitter to fixed mirror (cm)	x_f
Distance from beamsplitter to movable mirror (cm)	x_m
Electric field amplitude of incident radiation (V/m)	E_0
Electric field amplitude of radiation falling back on source (V/m)	E_S
Electric field amplitude of radiation reaching detector (V/m)	E_D
Focal length (cm)	f
Fourier transform of apodization function A (cm)	A^FT
General apodization function	A
Heavyside step function	θ
Intensity falling back on source (W cm^{-2})	I_S
Intensity on detector (W cm^{-2})	I_D
Maximum mirror displacement (cm)	Δx_max
Maximum wavenumber (cm^{-1})	σ_max
Measured mirror displacement (cm)	Δx_m
Measured single line spectral density for a finite scan length (W cm^{-1})	S_1^box
Measured single line spectral density for a finite scan length using the apodization function A (W cm^{-1})	S^A
Measurement time for complete spectrum (s)	T_m
Minimum wavenumber (cm^{-1})	σ_min
Mirror displacement	Δx
Mirror velocity (cm s^{-1})	v
Modulation frequency (s^{-1})	ν
Number of sampling points of the interferogram	N
Number of spectral bands	M
Optical throughput (cm^2)	Θ
Optical throughput for FTS (cm^2)	Θ_FTS
Optical throughput for grating spectrometer (cm^2)	Θ_grating
Phase accumulation due to optical path to fixed mirror	φ_f
Phase accumulation due to optical path to moveable mirror	φ_m
Phase angle	γ
Phase angle	φ
Phase difference	$\Delta\varphi$
Phase difference between beams reflected at and transmitted through beamsplitter	$\Delta\varphi_\text{RT}$
Phase difference due to beam divergence	φ_div
Phase jump for reflection at beamsplitter	φ_R
Phase jump for transmission through beamsplitter	φ_T
Projected area of collimating element of FTS (cm^2)	A_FTS
Projected area of grating (cm^2)	A_G
Radius of entrance aperture (cm)	r_a
Refractive index	n
Responsivity (A W^{-1})	R_D
Sampling interval (cm)	ξ
Signal to noise ratio for FTS	$(\text{S/N})_\text{FTS}$
Signal to noise ratio for grating spectrometer	$(\text{S/N})_\text{G}$
Single line spectral density (W cm^{-1})	S_1
Solid angle	Ω
Spectral bandwidth (cm^{-1})	$\Delta\sigma$
Spectral density (W cm^{-1})	S
Spectral resolving power	ρ
Wave length (μm)	λ
Wave number (cm^{-1})	σ, σ_0
Wave number resolution (cm^{-1})	$\Delta\sigma_\text{min}$

See also

Interferometry: Overview; Phase Measurement Interferometry.

Further Reading

Bell RJ (1972) *Introductory Fourier Transform Spectroscopy.* New York, London: Academic Press.

Born M and Wolf E (1970) *Principles of Optics.* New York: Pergamon Press.

Griffiths PR (1975) *Chemical Infrared Fourier Transform Spectroscopy*. New York, London, Sydney, Toronto: John Wiley & Sons.
Hecht E (1987) *Optics*. Reading, MA: Addison-Wesley.
Mertz L (1965) *Transformations in Optics*. New York, London, Sydney: John Wiley & Sons.
Saptari V (2004) *Fourier-Transform Spectroscopy Instrumentation Engineering*. Bellingham: SPIE Press.

Hadamard Spectroscopy and Imaging

R A DeVerse, Plain Sight Systems, Inc., Kailua-Kona, HI, USA

R M Hammaker, Kansas State University, Manhattan, KS, USA

W G Fateley, Plain Sight Systems, Inc., Manhattan, KS, USA

F B Geshwind and A C Coppi, Plain Sight Systems, Inc., Hamden, CT, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Consider the task of measuring the spectra of a source, the spectra of an array of contiguous sources, or simply the broadband irradiance of an array of sources. These measures are commonly known as spectrometry, spectral imaging, and imaging, respectively. The sensitivity at which spectrometric, spectral imaging, and imaging systems can be operated is often dominated by noise associated with the detection system and the ability of the optics employed to deliver sufficient photonic flux to the detector subsystem to overcome this noise limitation. The ideal case is where the optical system can be fashioned in such a way as to deliver greater signal to the detector in order to maximize the signal-to-noise ratio (SNR) for a given finite source irradiance and detector noise.

Let us consider the number of discrete spectral resolution elements of spectrometers, spatio-spectral resolution elements of spectral imagers, and spatial resolution elements of imaging systems as being the N quantities of interest we would like to measure. We wish to measure these N quantities in time T with the greatest accuracy and precision as determined by the maximum SNR possible given a finite source flux and a fixed detector noise floor. One option might be to use a multi-element detection system (multi-channel detection system) with N detectors, so each detector is measuring one of the N quantities for the full time T in order to maximize the available integration time. However, in practice, these detectors can be problematic or simply not available for many applications when compared to single-element detectors. When a single-element detector is employed in spectrometry, spectral imaging, or imaging, the measurement methodology required becomes N measurements, each for a time T/N, so that each of the N quantities is measured separately or alternatively, one can record N measurements, each for time T/N, for various groups of the N quantities. The measurement procedure for various groups of the N quantities requires an encoding procedure to choose which of the N quantities to include in each of the N measurements and a decoding procedure to recover the values for each of the N individual quantities. When combinations of N quantities are measured, the signal at the single detector element is increased and the procedure is called multiplexing. Multiplexing may be defined as measuring the sum of groups of quantities rather than measuring each quantity separately with the primary goal of increasing SNR. Multiplexing can and does increase SNR when the detection system of the measuring device is operating in the detector noise limit. The detector noise limit is defined as the noise of the detector output that is independent of the amplitude of the signal. Photon-noise-limited detector systems can benefit from multiplexing strategies, however, one must be careful not to realize a multiplex disadvantage when the source of noise is not detector noise limited.

Fourier Transform Multiplexing

In optical spectrometry a common multiplexing method employs the Michelson interferometer in a Fourier transform (FT) spectrometer where, in the best case, as much as half of the spectral energy of the source entering the aperture is incident upon the single detector element for the duration of the measurement. The output of the detector is recorded as an interferogram, which is the detector response as a function of optical retardation (twice the path difference between the arms of the Michelson interferometer). The recorded interferogram is decoded using a Fourier transform algorithm to yield the desired spectrum. FT spectrometers are routinely employed in near-infrared, mid-infrared, and far-infrared spectrometry. In Raman spectrometry, FT spectrometers are used in the near-infrared spectral region typically using an Nd:YAG laser providing an excitation wavelength of 1064 nm. FT techniques are also employed in nuclear magnetic resonance (NMR) spectrometry and mass spectrometry.

Hadamard Transform Multiplexing

Hadamard transform multiplexing in dispersive optical spectrometry can be accomplished by use of an encoding mask at the focal plane of a dispersive spectrometer, that is operable to select different combinations of spectral resolution elements that are allowed to pass to the single detector element for each of the *N* required measurements. The specification of which ones of the *N* quantities are included in each of the *N* measurements of groups of the *N* quantities is called a weighing design. The term weighing design originally referred to a procedure for accurately determining the mass of a number of objects by weighing them in groups rather than one at a time. The optimal weighing designs and corresponding optimal encoding masks are specified by Hadamard mathematics. The Hadamard matrix or **H** matrix has all elements of +1 and −1 and provides the optimal weighing design for a two-pan balance or an optical instrument having two detector elements for the +1 and −1 measures. The Hadamard matrices specify which quantities go to each balance pan or detector element.



Figure 1 Simple schematic of a conventional and a Hadamard transform spectrometer. The top shows a conventional spectrometer where only one of seven spectral resolution elements ($N = 7$) impinge upon the single element detector for each of *N* measurements. The bottom shows a Hadamard transform spectrometer where $N = 7$. One more than half of the spectral resolution elements impinge upon the single element detector for each of the *N* measurements.

One and Two Detector Hadamard Encodement Matrices

In the case of a dispersive spectrometer with a single detector element, the optimal weighing designs and corresponding optimal encoding masks are provided by the simplex matrix or **S** matrix derived from the **H** matrix. The type of **S** matrix that is most convenient for optical applications is the cyclic or left circulant **S** matrix where only the first row needs to be known to generate the complete cyclic **S** matrix of N columns and N rows. Each row is obtained by shifting the previous row by a left-shift registration in which the element in the far left column moves to the far right column of the next row and each of the other $N-1$ elements moves one column to the left. Each of the N rows of the cyclic **S** matrix specifies one of the N encodements and each of the N columns specifies one of the N spectral resolution elements. The elements of the cyclic **S** matrix are 1 and 0 instead of the +1 and −1 found in the **H** matrix implementation. Spectral resolution elements allowed and not allowed to reach the single detector element are given as 1's and 0's, respectively. Each row and each column of the cyclic **S** matrix is a different sequence of $(N+1)/2$ elements of 1's and $(N-1)/2$ elements 0's so that each encodement in the row of the cyclic **S** matrix has a different combination of $(N+1)/2$ spectral resolution elements that are incident upon the single detector element. Just as the positions of the 1's in a row show which spectral resolution elements are included in a particular encodement, the positions of the 1's in a column show which encodements include that particular spectral resolution element. The result is that provided the detector noise is independent of its output signal, the SNR is increased by a factor of $(N+1)/(2\sqrt{N})$, approximately $(\sqrt{N})/2$, when compared to the method of measuring each spectral resolution element separately as in a raster scan performed by a classical scanning dispersive spectrometer.

Multiplexing in dispersive optical spectrometry as introduced in the previous paragraph is called Hadamard transform spectrometry (HTS) (see Figure 1). It is a unique combination of dispersive and multiplexing spectrometries. The choice of transparent or opaque for the elements of a multislit array or Hadamard encoding mask provides an encoding of spectral information that may be decoded into a conventional spectrum by Hadamard mathematics. In a typical dispersive spectrometer, the source energy is collected and separated into its individual spectral resolution elements by a spectral separator and then collected and focused for spatial presentation on a focal plane. Unlike a scanning dispersive spectrometer, which possesses a single exit slit, the Hadamard transform (HT) spectrometer employs a multislit array as a Hadamard encoding mask. This arrangement allows for the simultaneous measurement of a multitude of spectral resolution elements at a single-element detector and produces a multiplexing spectrometer.

Theory of Hadamard Multiplexing

The operation of the HT spectrometer can be described using matrix algebra with column vectors [**D**] and [**I**] and the N-order square matrices $\mathbf{S}_N$, $\mathbf{S}_N^{-1}$, $\mathbf{S}_N^{\mathrm{T}}$, and $\mathbf{T}_N$. [**D**] is a column vector of N rows containing the detector responses for the N encodements. [**I**] is a column vector of N rows containing the N spectral resolution elements to be determined. $\mathbf{S}_N$ is the cyclic **S** matrix of order N that is the basis for construction and design of the Hadamard encoding mask. $\mathbf{S}_N^{-1}$ is the inverse of $\mathbf{S}_N$ and is given by $(2/(N+1))\mathbf{T}_N$. $\mathbf{T}_N$ is a matrix of +1 and −1



Figure 2 An encodegram (top plot) and the corresponding single-beam spectrum (bottom plot) as a result of decoding the encodegram using Hadamard mathematics.

elements obtained from S_N^T, the transpose of S_N, with T_N having +1's and −1's where S_N^T has 1's and 0's, respectively. A cyclic matrix is required to be symmetric so that an interchange of columns and rows can recover the original matrix and S_N^T then becomes equal to S_N. The encoding of the radiation by the HT spectrometer is given by $[D] = S_N[I]$ and the resulting primary data are a record of detector response versus encodement number. The plot of detector response versus encodement number is called an encodegram (analogous to the interferogram produced by an FT spectrometer). The decoding of the encodegram to recover the conventional spectrum using a Hadamard transform can be described by $[I] = S_N^{-1}[D]$, obtained by left multiplying $[D] = S_N[I]$ by S_N^{-1}. In practice, it is not necessary to invert S_N because there is a fast Hadamard transform (FHT) algorithm available when N is of the form $N = 2^w - 1$, w being an integer. There are three known methods for generating the first row of cyclic **S** matrices of order $N = 2^w - 1$. Consider the example of $N = 7$ for $w = 3$ where the first row of S_7 is 1 1 1 0 1 0 0. Figure 2 shows an encodegram and the result of decoding using Hadamard mathematics. Figure 3 contains the matrices and matrix equations for $N = 7$.

Hadamard Encoding Masks

The key component of any HT spectrometer is the Hadamard encoding mask (Figure 4). Two choices for the Hadamard encoding mask are the moving mechanical mask and the stationary electro-optical mask. The moving mask for N spectral resolution elements requires $2N - 1$ mask elements that are either completely open with a transmittance of 1 or completely closed with a transmittance of 0. The stationary mask for N spectral resolution elements requires only N mask elements that are selected to be either transparent: transmittance $T_t = 1$ or <1 or opaque: transmittance $T_o = 0$ or >0. The resulting SNR is dependent upon $\Delta T = T_t - T_o$, which has its optimal value of unity only for an ideal mask which is $T_t = 1$, $T_o = 0$. The advantage of the moving mask is

$$[D] = \begin{matrix} D_1 \\ D_2 \\ D_3 \\ D_4 \\ D_5 \\ D_6 \\ D_7 \end{matrix} = \begin{matrix} I_1 + I_2 + I_3 + I_5 \\ I_1 + I_2 + I_4 + I_7 \\ I_1 + I_3 + I_6 + I_7 \\ I_2 + I_5 + I_6 + I_7 \\ I_1 + I_4 + I_5 + I_6 \\ I_3 + I_4 + I_5 + I_7 \\ I_2 + I_3 + I_4 + I_6 \end{matrix} \qquad S_7 = \begin{matrix} 1\,1\,1\,0\,1\,0\,0 \\ 1\,1\,0\,1\,0\,0\,1 \\ 1\,0\,1\,0\,0\,1\,1 \\ 0\,1\,0\,0\,1\,1\,1 \\ 1\,0\,0\,1\,1\,1\,0 \\ 0\,0\,1\,1\,1\,0\,1 \\ 0\,1\,1\,1\,0\,1\,0 \end{matrix} \qquad [I] = \begin{matrix} I_1 \\ I_2 \\ I_3 \\ I_4 \\ I_5 \\ I_6 \\ I_7 \end{matrix}$$

$$T_7 = \begin{matrix} 1 & 1 & 1 & -1 & 1 & -1 & -1 \\ 1 & 1 & -1 & 1 & -1 & -1 & 1 \\ 1 & -1 & 1 & -1 & -1 & 1 & 1 \\ -1 & 1 & -1 & -1 & 1 & 1 & 1 \\ 1 & -1 & -1 & 1 & 1 & 1 & -1 \\ -1 & -1 & 1 & 1 & 1 & -1 & 1 \\ -1 & 1 & 1 & 1 & -1 & 1 & -1 \end{matrix} \qquad S_7^{-1} = (1/4)T_7 = \begin{matrix} (1/4)(1\ 1\ 1\ -1\ 1\ -1\ -1) \\ (1/4)(1\ 1\ -1\ 1\ -1\ -1\ 1) \\ (1/4)(1\ -1\ 1\ -1\ -1\ 1\ 1) \\ (1/4)(-1\ 1\ -1\ -1\ 1\ 1\ 1) \\ (1/4)(1\ -1\ -1\ 1\ 1\ 1\ -1) \\ (1/4)(-1\ -1\ 1\ 1\ 1\ -1\ 1) \\ (1/4)(-1\ 1\ 1\ 1\ -1\ 1\ -1) \end{matrix}$$

$$[I] = \begin{matrix} I_1 \\ I_2 \\ I_3 \\ I_4 \\ I_5 \\ I_6 \\ I_7 \end{matrix} = S_7^{-1}[D] = \begin{matrix} (1/4)(D_1 + D_2 + D_3 - D_4 + D_5 - D_6 - D_7) \\ (1/4)(D_1 + D_2 - D_3 + D_4 - D_5 - D_6 + D_7) \\ (1/4)(D_1 - D_2 + D_3 - D_4 - D_5 + D_6 + D_7) \\ (1/4)(-D_1 + D_2 - D_3 - D_4 + D_5 + D_6 + D_7) \\ (1/4)(D_1 - D_2 - D_3 + D_4 + D_5 + D_6 - D_7) \\ (1/4)(-D_1 - D_2 + D_3 + D_4 + D_5 - D_6 + D_7) \\ (1/4)(-D_1 + D_2 + D_3 + D_4 - D_5 + D_6 - D_7) \end{matrix}$$

For example: Note $I_1 = (1/4)\,[\,(D_1 + D_2 + D_3 + D_5) - (D_4 + D_6 + D_7)\,]$ so

$$I_1 = (1/4)\{[(I_1 + I_2 + I_3 + I_5) + (I_1 + I_2 + I_4 + I_7) + (I_1 + I_3 + I_6 + I_7) + (I_1 + I_4 + I_5 + I_6)] - [(I_2 + I_5 + I_6 + I_7) + (I_3 + I_4 + I_5 + I_7) + (I_2 + I_3 + I_4 + I_6)]\} = (1/4)\{4I_1\} = I_1$$

Figure 3 Matrices and matrix equations (note since $\mathbf{S}_7$ is symmetric $\mathbf{S}_7^T = \mathbf{S}_7$).



Figure 4 A linear encodement of length $N = 43$ generated by using a quadratic residue construction.

no optical transmission problems. However, it suffers the disadvantage of having moving parts and position repeatability problems. For the case of the stationary mask, it has the advantage that it has no moving parts and no positioning repeatability problems. The disadvantage of the stationary mask is the optical transmission problem where $T_t < 1$ and $T_o > 0$. The moving Hadamard encoding mask of $2N - 1$ mask elements is changed to the next encodement by translation of the Hadamard encoding mask to the left past the aperture by a single mask element. For $N = 7$ and $2N - 1 = 13$, the assignment of 1 and 0 to positions 1 through 13 is [1 1 1 0 1 0 0 1 1 1 0 1 0]. For example, the first encodement corresponding to the first row of S_7 in Figure 3 is from positions 1 through 7 as [1 1 1 0 1 0 0] and the fourth encodement corresponding to the fourth row of S_7 in Figure 3 is from positions 4 through 10 as [0 1 0 0 1 1 1].

2D Encoding Masks for Multiplexing in Spectral Imaging and Imaging

If the conventional one-dimensional (1D) Hadamard encoding mask is folded in some manner, the result is the generation of a two-dimensional (2D) Hadamard encoding mask (Figure 5). Similar to the 1D Hadamard encoding masks that are used for spectral mutiplexing, 2D Hadamard encoding masks can be used for the spatial multiplexing done in Hadamard transform spectral imaging (HTSI) and Hadamard transform imaging (HTI). It is important to note that spectrometry as HTS, spectral imaging as HTSI, and imaging as HTI all realize the same theoretical SNR improvement based on the number of spectral, spatio-spectral, or spatial resolution elements (N), respectively. Consider the folding of a 1D Hadamard encoding mask for $N = 15$ into a 2D Hadamard encoding mask of three rows and five columns (Figure 6). A cyclic S_{15} has a first row of [0 0 0 1 0 0 1 1 0 1 × 0 1 1 1 1] so the 2D Hadamard encoding mask has a first row of [0 0 0 1 0], a second row of [0 1 1 0 1], and a third row of [0 1 1 1 1] from columns 1 through 5, 6 through 10 and 11 through 15, respectively, from S_{15}.



Figure 5 A two dimensional encodement of length $N = 10{,}007$ in a 100 × 100 format generated by quadratic residue construction. The remaining 7 elements are shown as the last 7 elements in the bottom row on the right. In practice these 'extra' data points can be masked off and used as a measure of system noise characteristics.



Figure 6 Spectrometry to imagery: The folding of a ID encoding mask that can be used for spectrometry is used to generate a 2D encoding mask that can be used for imaging. Note that using a symmetric aperture window where only 3 × 2 elements are used, the mask element that is not included in the windowed aperture can be used as a measure of the dark noise of the system, however, a more conventional encodement matrix might be one that can be divided into an integer number of rows and columns such as $N = 15$ where one can construct a 5 × 3 2D encodement mask for imagery and use a symmetric aperture that uses the entire length of the encodement matrix.

Hadamard Mathematics

Consider a general multiplexing problem where one seeks to measure N quantities, $X = \{x_0, x_1, \ldots, x_{N-1}\}$, in the presence of noise, and wishes to determine a vector function $F(X)$, such that the measurement of $F(X)$ yields the best estimate of X. Conservation of energy and superposition principles dictate a restriction to linear functions. The principle of rank suggests that we restrict our measurements to N-dimensional linear combinations. Determining the best linear combination is the challenge. In the case of constant error for each measurement, an answer is provided by Hotelling's theorem, which proves Hadamard matrices are optimal for such measurements. Hadamard matrices uniquely achieve the optimal bound for root-mean-square measurement error. A Hadamard matrix is a matrix $\mathbf{H}$ for which $\mathbf{H}_{i,j} = \pm 1$, and $\mathbf{H}^{-1} = \frac{1}{N}\mathbf{H}^{\mathrm{T}}$. The definitions of matrix inverse, transpose, and multiplication dictate that the rows of the matrix $\mathbf{H}$ form an orthogonal basis with each basis element having norm $\sqrt{N}$. The norms of the rows of $\mathbf{H}$ follow from the entries of the matrix that are ± 1, and place no additional restriction on $\mathbf{H}$. The columns of $\mathbf{H}$ are also an orthogonal basis with these same norms. The rows (columns) of the matrix $\frac{1}{\sqrt{N}}\mathbf{H}$ form an orthonormal basis. From these few statements and definitions, one can already derive estimates of the multiplex advantage. For example, one seeks to measure X and in one case measures $Y_1 = X + \varepsilon$, where ε is a random noise or error that has a Gaussian distribution with a mean of 0 and variance σ^2. In another case, suppose that one measures $Y_2 = HX + \varepsilon$. In this second case, one would estimate

$$X_2 = \frac{1}{N}\mathbf{H}^{\mathrm{T}}(\mathbf{H}X + \varepsilon) = X + \left(\frac{1}{\sqrt{N}}\right)^2 \mathbf{H}^{\mathrm{T}}\varepsilon$$
$$= X + \frac{1}{\sqrt{N}}\varepsilon_1$$

where ε_1 is random noise with the same characteristics as ε. It follows that the measurement error in the second case has a standard deviation σ that is less than in the former case, with an improvement by the factor $\frac{1}{\sqrt{N}}$.

Hadamard Computations

The ± 1 Hadamard matrices can be applied to two detector optical systems, and 0,1 matrices can be applied to single detector systems. In a two detector system $\mathbf{H}^{\mathrm{T}}$ is proportional to $\mathbf{H}^{-1}$ and one can invert these transforms. Suppose that one has chosen a particular Hadamard matrix $\mathbf{H}$, with which to conduct a multiplexed measurement. One can show that multiplication of any row or any column by -1 does not affect the efficacy of $\mathbf{H}$ in improving SNR. Hence one may assume that the first row and first column of $\mathbf{H}$ are all $+1$. From $\mathbf{H}$, we can form a new $(N-1)\times(N-1)$ matrix $\mathbf{S}$ by deleting the first row and column of $\mathbf{H}$, and then changing each 1 to a 0, and each -1 to a 1. This new matrix $\mathbf{S}$, an $\mathbf{S}$-matrix, is the one corresponding to $\mathbf{H}$ that is to be used for single-element detector optical systems. It is known that $\mathbf{S}$ matrices are optimal for 0,1 matrices just as Hadamard matrices are optimal for ± 1 matrices, with signal to noise improvement by a factor $\frac{\sqrt{N-1}}{2}$, where here N is the dimension of $\mathbf{H}$.

Letting $\mathbf{I}$ be the identity matrix, and $\mathbf{J}$ be the matrix whose entries are all 1, it follows that $\mathbf{S}^{\mathrm{T}}\mathbf{S} = \frac{N}{4}(\mathbf{I} + \mathbf{J})$, where N is the dimension of $\mathbf{H}$. From this we can ascertain that a multiplexed system using the matrix $\mathbf{S}$, multiplied by the encoded parameters of $\mathbf{S}^{\mathrm{T}}$ recovers the original signal to within the addition of an offset. In practice this is what is done to recover the original X. In certain cases, there is also a fast algorithm for computing $\mathbf{S}^{\mathrm{T}}Y$, without ever explicitly computing $\mathbf{S}^{\mathrm{T}}$.

Constructions for Hadamard Matrices

It is known that if $\mathbf{H}$ is an $N \times N$ Hadamard matrix, then N must be 1, 2, or a multiple of 4 and so nontrivial S-matrices must be of size one less than a multiple of 4. It is conjectured that Hadamard matrices exist for each N which is a multiple of 4. Some constructions of Hadamard matrices are enumerated below.

Walsh–Hadamard Construction

A Hadamard matrix of size $N = 2^K$ can be constructed by sampling the first N Walsh functions at $0, 1/N, 2/N, 3/N, \ldots, (N-1)/N$, where the Walsh functions are defined by $W_0(x) = 1$, for $0 \le x < 1$, $W_0(x) = 0$ otherwise, and the recurrence relations, for each non-negative integer n:

$$\begin{aligned} W_{2n}(x) &= W_n(2x) + W_n(2x-1), \text{ and} \\ W_{2n+1}(x) &= W_n(2x) - W_n(2x-1) \end{aligned} \qquad [1]$$

Tensor Product Construction

Walsh is a special case of iterating this construction, starting with the matrix $\mathbf{H}_1 = [1]$. In general, if $\mathbf{H}_{\mathrm{N}}$ is a Hadamard matrix of size $N \times N$, then:

$$\mathbf{H}_{2N} = \begin{bmatrix} H_N & H_N \\ H_N & -H_N \end{bmatrix} \qquad [2]$$

is a Hadamard matrix of size $2N \times 2N$.

Quadratic Residue Construction

This construction is an example of a cyclic S-matrix: one for which each row is a cyclic shift of the previous row. Given a prime number $p = 4n + 3$, define, for $i = 0, \ldots, p-1$, the values $S_{1,i} = 1$ if there is some integer k, such that the remainder of dividing k^2 by p is i, and $S_{1,i} = 0$ otherwise. Taking the cyclic matrix with the first row given by $S_{1,i}$, yields a Hadamard S-matrix.

Other constructions are possible. Maximal length shift register codes, and a construction involving quadratic residues of twin primes are two examples.

Fast Hadamard Transforms

The fast Walsh transform can be deduced from eqn [1]. The basic idea is that, in eqn [1], the function W_n is specified by $\log_2 n$ recurrence relations. For this reason, a Walsh transform (or its transpose) can be computed in $O(n \log_2 n)$ steps. The algorithm goes as follows, for a sequence of length $N = 2^n$:

(i) begin with $Y_{0,0}, Y_{0,1}, \ldots, Y_{0,N-1} = Y_0, Y_1, \ldots, Y_{N-1}$
(ii) for $i = 1, \ldots, n-1$, let $Y_{i,k} = Y_{i-1,2k} + Y_{i-1,2k+1}$, and $Y_{i,n/2+k} = Y_{i-1,2k} - Y_{i-1,2k+1}$, for $k = 0, \ldots, N/2$
(iii) output $X_i = Y_{n-1,i}$

Then the resulting X_i is the inverse Walsh transform of Y_i.

Note that cyclic S matrices that come from maximal length shift registers are known to be permutations of the Wzalsh–Hadamard S matrices, and hence there is also a fast algorithm for inverting these, albeit involving some tedious permutations.

Optics for Hadamard Encoded Apertures

Hadamard optical systems utilize spatially encoded apertures that can be employed either at the entrance aperture of the optical system, the exit aperture or both. They have the common attribute that they encode the available aperture spatially where the spatial resolution elements that make up the encodement dictate the spectral, spatio-spectral, or spatial resolution elements that propagate through the optical system, including diffractive optical elements and on to the sensor or exit aperture. These masks have some spatial extent that places special requirements on the optics of the system. As the encodement mask grows either by longer length encodements with fixed subapertures or as the subaperture dimension grows for a fixed encodement length, the spatial resolution elements making up the subapertures in the encodement mask depart from the optical axis. When the resolution elements depart from the optical axis or paraxial condition, it becomes important to employ optics that can image the off-axis resolution elements without inducing excessive aberrations that degrade the performance and cripple the advantages gained by HT multiplexing.

Typically the optical path for conventional monochromators begins with a source that is focused onto an aperture plane that has a large aspect ratio aperture know as a slit. This slit is often very small in extent in the dispersion plane compared to the other extent in the spatial plane. However, it is not required that this aspect ratio is large. If the aspect ratio is close to 1 then simple spherical optics can be employed that perform well as long as the departure from the optical axis is kept to a minimum. However, most monochromators have a large aspect ratio in order to increase the opportunity to maximize throughput, and detectors must be able to ‘see’ the large extent of the slit aperture. The light entering the slit aperture is then dispersed and focused onto an exit slit aperture. Monochromators are only required to perform well on the optical axis and do not typically employ optics that can manage rays that depart from the optical axis in the plane of dispersion as required by HT multiplexing instruments. To employ encoding techniques the optical system is required to utilize optical performance attributes normally found only in imaging and spectral imaging systems. This requirement is driven by the extent of the encoding mask. The extent of the encoding mask is governed by the diffraction limit of the wavelengths within the bandpass, the encodement length N, and the attributes of the optical system.

In a conventional dispersive spectrometer the radiation from a source is collected and separated into its individual spectral resolution elements by a spectral separator such as a diffraction grating or prism and then is collected and focused for spatial



Figure 7 Example implementation of a Hadamard transform spectrometer with reflective optics. Light from a source passes through a sample, is transferred into an entrance aperture, bounced off of a concave grating, and then a reflective mask, and finally transferred to a detector.

presentation on a focal plane. The dispersive spectrometer uses a single exit slit to select one spectral resolution element at any given time, out of N possible spectral resolution elements for measurement by the detector. The Hadamard transform spectrometer (HTS, Figure 7) uses an array of slits (i.e., a mask) at the focal plane to select one more than half, $(N+1)/2$, of the spectral resolution elements at the focal plane for measurement by the detection system. The optical challenge to effect an HT multiplexing spectrometer is to collect all of the spatially distributed individual bandpass images of the entrance slit and transfer them to as small a detector as possible. One desires to keep the area of the detector at a minimum as the noise of many detectors increases with the square of the area. If the optics are able to illuminate a single detector element with all of the available light impinging upon the focal plane containing the spatially distributed images of the slit for each of the N bandpass resolution elements, a multitude of spectral resolution elements can be measured simultaneously using a single detector element. This arrangement results in a multiplexing spectrometer. The recovery of N spectral resolution elements requires measuring the detector response for N different encodements of $(N+1)/2$ open mask elements. The raw data are recorded as the detector response versus encodement number and is called an encodegram. Hadamard transformation of the encodegram yields the spectrum.

The History of Applied Hadamard Multiplexing

The Hadamard transform instruments developed in the 1960s and 1970s employed moving masks. Significant problems such as misalignment and jamming associated with a moving mask led to a reputation of poor reliability and contributed to a dormant period in the development of HTS and HTI. Interest was rekindled in the 1980s using stationary Hadamard encoding masks based on liquid crystal (LC) technology. The first generation 1D stationary Hadamard encoding mask was a cholesteric LC with $N=127$ mask elements and used polarization as its operating phenomenon. Two parallel polarizers and rotation or lack of rotation of the polarized radiation generated the opaque and transparent states, respectively. The second generation 1D stationary Hadamard encoding mask was fabricated using a polymer dispersed liquid crystal (PDLC) material with $N=255$ mask elements and used light scattering as its operating phenomenon. The PDLC contained LC droplets dispersed in a polymer matrix whose index of refraction matched the index of refraction in one direction in the birefringent LC droplet. Alignment of the LC droplets optical axis under an applied voltage removed discontinuities in index of refraction at the polymer matrix/LC interface to generate a good transparent state while random orientation of LC droplets in the polymer matrix generated the opaque state from light scattering by the discontinuities in index of refraction at the polymer matrix/LC droplet interface. A 2D stationary Hadamard encoding mask was also based on LC technology. A ferro-electric liquid crystal positioned between a pair of polarizers with perpendicular orientation operated as an electro-optic half-wave plate when a +value of applied voltage rotated the plane of polarization by 90 degrees to produce the transparent state and a −value of applied voltage left the plane of polarization unaltered to produce the opaque state.

Development based on stationary Hadamard encoding masks continued in the 1990s and a 2D moving Hadamard encoding mask was also fabricated and used to perform imaging in the near-infrared and mid-infrared spectral regions. Note that the mid-infrared spectral region is not generally accessible via Hadamard encoding masks based on

LC technology, since any LC material is expected to have strong absorption bands in the mid-infrared spectral region. From the mid-1990s to the present, the stationary Hadamard encoding mask of choice for the visible and near-infrared spectral regions has been the digital micromirror device (DMD), a device based on micro-optoelectromechanical systems (MOEMS) technology and developed by Texas Instruments for projector display applications. One DMD format incorporates 508 800 micromirrors in an 848 column by 600 row array that is 14.4 mm wide by 10.2 mm high. Each individual micromirror is 16 μm square and adjacent micromirrors are separated by a 1 μm gap. The micromirrors are individually addressable and rotate by +10 or −10 degrees about the diagonal axis to produce binary 'on' and 'off' states. The on state has T_t determined by the mirror reflectivity and approaches 1 while the off state approaches $T_o = 0$. The ideal condition of on and off is not realized due to diffraction of the light off of the small and periodic features of the micromirror device. The DMD is an array of spatial resolution elements that may be selected as groups of super-resolution elements or as individual resolution elements consisting of a single micromirror. The DMD resolution elements are realized as spectral resolution elements in the spectrometer with the columns attributed to the frequency or wavelength dimension and the rows attributed to the slit height dimension. The DMD resolution elements are utilized as spatio-spectral resolution elements in the imaging spectrograph with the columns as the frequency or wavelength dimension and the rows as a vertical spatial dimension with the horizontal spatial dimension being accessed, if desired, by translating the sample relative to the imaging spectrograph. The DMD resolution elements are spatial resolution elements in the imager with the columns for the horizontal dimension and the rows for the vertical dimension and the frequency or wavelength dimension provided by other instrumentation. If a photo-acoustic detection system is present then the depth dimension of the sample may also be accessed by changing the modulation frequency used in the photo-acoustic detection system.

Some important features of HTS to keep in mind are:

(i) it is a dispersive technique using a spectral separator;
(ii) it is a multiplexing technique using a single-element detector;
(iii) it uses a Hadamard encoding mask (multislit array) in a focal plane;
(iv) it sends one more than half the resolution elements to the single-element detector in each encodement;
(v) it uses a number of encodements equal to the number of resolution elements desired and the number of mask elements (pixels) in the stationary Hadamard encoding mask (a moving Hadamard encoding mask has $2N - 1$ mask elements);
(vi) it has each encodement containing a different combination of one more than half the resolution elements;
(vii) it has as its primary data the encodegram, a record of detector response versus encodement number; and
(viii) it uses a FHT of the encodegram to decode the encodegram and generate the spectrum or image.

Note that all of these, except for item (i), also apply to HTSI and HTI. The DMD promises to be the best Hadamard encoding mask yet developed for the visible and near-infrared spectral regions. However, its potential applications in spectrometry and imaging are by no means limited to HT techniques since the information corresponding to any micromirror in the DMD may be included in or excluded from any measurement as desired by the investigator. An instrument with no moving parts, other than the micromirrors in the DMD, promises to provide a compact and robust instrument for operation in potentially hostile environments ranging from process control to outer space. It is our belief that the combination of a DMD with a single-element detector may provide an important advance in spectroscopic instrumentation and that instrumentation based on the DMD may lead to a host of environmental, industrial, medical, and military applications.

See also

Fourier Optics. **Imaging:** Multiplex Imaging. **Optical Communication Systems:** Optical Time Division Multiplexing. **Spectroscopy:** Fourier Transform Spectroscopy.

Further Reading

Bellamy MK, Mortensen AN, Hammaker RM and Fateley WG (1997) Chemical mapping in the mid- and near-IR spectral regions by Hadamard transform/FT-IR spectrometry. *Applied Spectroscopy* 51: 477–486.

Fateley WG, Hammaker RM, Paukstelis JV, *et al.* (1993) Application of a two-dimensional Hadamard encoding mask for the imaging of thin-layer chromatography plates by laser-induced fluorescence or surface-enhanced Raman scattering and for use with a photoacoustic detector to generate three-dimensional photoacoustic images. *Applied Spectroscopy* 47: 1464–1470.

Fateley WG, Hammaker RM, DeVerse RA, Coifman RR and Geshwind FB (2002) The other spectroscopy: demonstration of a new de-dispersion imaging spectrograph. *Vibrational Spectroscopy* 29: 163–170.

Hammaker RM, Bohlke AP, Freeman RD, *et al.* (1996) Hadamard transform Raman spectrometry. In: Laserna JJ (ed.) *Modern Techniques in Raman Spectroscopy*, pp. 143–226. Chichester: Wiley.

Hammaker RM, DeVerse RA, Asunskis DJ and Fateley WG (2002) Hadamard transform near-infrared spectrometers. In: Chalmers JM and Griffiths PR (eds) *Handbook of Vibrational Spectroscopy*, vol. 1, pp. 453–460. Chichester: Wiley.

Harwit M and Sloane NJA (1979) *Hadamard Transform Optics*. New York: Academic Press.

Nonlinear Laser Spectroscopy

P Ewart, University of Oxford, Oxford, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction: Linear and Nonlinear Spectroscopy

Light propagates in transparent or weakly absorbing media by inducing the atoms or molecules in the material to oscillate in response to the electromagnetic field of the light. The induced dipole oscillations set up a polarization field **P** which radiates the wave in the propagation direction. The induced polarization **P** is proportional to the amplitude of the electric field **E** in the incident light:

$$\mathbf{P} = \varepsilon_0 \chi^{(1)}(\omega)\mathbf{E} \qquad [1]$$

where ε_0 is the permittivity of free space and $\chi^{(1)}(\omega)$ is the first-order, frequency-dependent, susceptibility of the material. This interaction of the light with the medium generally results in some absorption of energy from the field and a shift in the phase of the propagating light. Both the phase delay and the absorption depend on the frequency ω (and wavelength λ) of the light. The phase shifting is responsible for dispersion – the variation, as a function of frequency, of the speed (phase velocity) of light in the medium. The dispersion and absorption effects are described by the real and imaginary parts, respectively, of the complex susceptibility:

$$\chi(\omega) = \chi_{\mathrm{Re}}(\omega) + \mathrm{i}\chi_{\mathrm{Im}}(\omega) \qquad [2]$$

This susceptibility parameter describes the optical properties of the medium. Linear spectroscopy uses the frequency-dependent property of the $\chi(\omega)$ to create spectra by absorption or dispersion of specific frequencies that are resonant with transitions between internal energy states of the molecules. The electric field in the incident light is considered to be weak when it leaves the atomic and molecular properties essentially unaffected. Nonlinear optical spectroscopy, however, is based on the ability of intense laser light to modify the optical properties of the medium through which it propagates. These effects are also frequency dependent and so can be used to generate spectra. When the strength of the electric field becomes comparable with the electric fields within the atoms or molecules (typically $\sim 10^{11}\ \mathrm{V\,m^{-1}}$) then the induced polarization becomes nonlinear and is described by a power series expansion:

$$\mathbf{P} = \varepsilon_0[\chi^{(1)}(\omega)\mathbf{E}_1 + \chi^{(2)}(\omega)\mathbf{E}_1\mathbf{E}_2 + \chi^{(3)}(\omega)\mathbf{E}_1\mathbf{E}_2\mathbf{E}_3 + \text{higher-order terms}] \qquad [3]$$

$\chi^{(2)}(\omega)$ and $\chi^{(3)}(\omega)$ are the second- and third-order susceptibilities respectively. The real and imaginary parts of these susceptibilities (and of the higher-order terms) describe observable effects arising from absorption and dispersion. The associated interactions involve two and three photon processes, respectively. In general, nonlinear interactions involve multiphoton processes and will be described by the appropriate term in the expansion of the induced polarization.

Broadly speaking, nonlinear spectroscopy is based on detection of these multiphoton interactions by either incoherent or coherent processes. Incoherent processes include fluorescence and ionization where, following the multiphoton interaction, photons or electrons respectively are emitted spontaneously in all directions. Coherent processes, on the other hand, arise from the coupling of the input driving fields via the nonlinear polarization of the medium.

The waveform of the polarization oscillations is a distorted form of the driving field. Fourier analysis of these nonlinear oscillations would reveal extra frequencies not present in the incident field. When a suitably phased array of dipoles is established, the nonlinear optical process is detected by emission of coherent directional light. The efficiency with which this coherent signal beam is generated is crucially dependent upon the correct phasing of the radiating molecules. This process is known as phase matching and is achieved by geometrical arrangements of the input beams or by modifying the refractive index to counteract dispersion between the generating polarization wave and the radiated signal wave.

Apart from the general division of nonlinear spectroscopy according to whether the detection uses incoherent or coherent emission, the techniques are characterized as frequency or time domain methods, according to how the signal is generated and detected. In most cases the signals recorded in either domain may be related by a Fourier transformation to an equivalent signal in the other.

The advantages of nonlinear spectroscopic techniques lie in their ability to provide high spectral, temporal, and spatial resolution. In particular, it is possible, using a variety of nonlinear optical processes, to eliminate inhomogeneous broadening of the spectral lines recorded. Second, when coherent signal beams are generated they can be readily distinguished from incoherent background emissions, thus permitting high signal-to-noise ratios. Third, the use of short laser pulses, down to the order of 10^{-15} s, allows high temporal resolution. High spatial resolution is achieved by generating signals from interaction regions defined by crossed and focused beams. Although the coefficients of successive terms in the power series expansion of the nonlinear polarization decrease by many orders of magnitude with increasing order, signal strengths may be made comparable to those of linear spectroscopy. Strong signals are obtained by the use of resonant enhancement of the nonlinear susceptibility, high field strengths from laser sources, and the use of sensitive photodetectors.

Second-Order Nonlinear Effects

Weak light fields leave unaffected the optical properties of the medium through which they propagate. When, however, the second-order susceptibility $\chi^{(2)}$ contributes significantly to the induced polarization, the complex refractive index includes a field-dependent term:

$$\mathbf{P} = \varepsilon_0[\chi^{(1)}(\omega) + \chi^{(2)}(\omega)\mathbf{E}_1]\mathbf{E}_2 \qquad [4]$$

Owing to the symmetry properties of $\chi^{(2)}$, second-order nonlinear effects are absent in isotropic media or those possessing a center of inversion symmetry. They may, however, be observed in anisotropic materials such as crystalline solids where they are the basis of frequency mixing schemes leading to second-harmonic generation, sum- and difference-frequency generation, and optical parametric amplification and oscillation. The symmetry of gas phase media, such as atomic vapors, may be broken by application of an external electric or magnetic field. Resonantly enhanced second-harmonic generation has been achieved in alkali metal vapors in the presence of a magnetic field giving potential for spectroscopy. Symmetry breaking is achieved also on solid surfaces where sum-frequency generation has been used to study surface morphology, monatomic layers, and catalytic effects of adsorbed materials.

Third-Order Nonlinear Spectroscopy

In gas phase or isotropic solid and liquid media, the first nonlinear term is of third order and leads to a refractive index that is dependent on the field intensity $|\mathbf{E}|^2$:

$$\mathbf{P} = \varepsilon_0[\chi^{(1)}(\omega) + \chi^{(3)}(\omega)\mathbf{E}^2]\mathbf{E} \qquad [5]$$

Intensity-dependent refractive index effects lead to a wide range of nonlinear optical phenomena. In general, the polarization contains terms that are the product of three input fields generating Fourier components at sum and difference frequencies. Phase matching constraints will generally determine which of the possible interactions will be observed. A wide range of physical effects contribute to $\chi^{(3)}(\omega)$. The simplest of these nonlinear effects is saturation of the absorption.

Linear absorption is defined by the situation where the intensity decays exponentially with propagation distance x, according to Beer's Law:

$$I(x) = I(0)\exp\{-\alpha_0(\omega)x\} \qquad [6]$$

where $I(0)$ and $I(x)$ are the intensity values at $x = 0$ and x, respectively, and $\alpha_0(\omega)$ is the weak field absorption coefficient. The fractional power absorbed in this case is, therefore:

$$[I(0) - I(x)]/I(0) = \alpha_0(\omega)x \qquad [7]$$

and is independent of the intensity. When the incident intensity increases, until the rate of stimulated absorption from the lower level equals the spontaneous emission rate out of the upper level, the medium is said to be saturated. The intensity is then I_{sat}. A simple rate-equation analysis shows that the absorption coefficient in the presence of a strong light field is:

$$\alpha(\omega) = \frac{\alpha_0(\omega)}{[1 + I/I_{sat}]} \quad [8]$$

The absorption is then no longer independent of the light intensity.

Saturation Spectroscopy

In the case of a homogeneously broadened transition the effect of a saturating monochromatic light field is to reduce the absorption across the entire line profile. This is shown in Figure 1a where the frequency of the incident light w_L is detuned from line center ω_0. The degree of saturation and the effect on the absorption coefficient depends on the intensity I and the detuning $\Delta\omega = \omega_L - \omega_0$.

For a transition dominated by inhomogeneous broadening a monochromatic light field interacts strongly only with a sub-group of atoms. This sub-group is determined by those having a resonance frequency within the spectral range covered by the homogeneous width and centered on the incident frequency. Saturation in this case results in ‘hole burning’ as shown in Figure 1b. A dip in the absorption coefficient $\alpha(\omega)$ is produced centered on ω_L of width given by the homogeneous width.



Figure 1 Absorption lineshapes for (a) homogeneously broadened and (b) inhomogeneously broadened lines centered at ω_0. Dashed lines in both figures show lineshape measured by weak probe. Solid lines show lineshape measured by weak probe in presence of a monochromatic, saturating beam at frequency $\omega_L \neq \omega_0$.

Saturation affects the population of both upper and lower levels involved in an optical transition and so affects both absorption and amplification (gain). The phenomenon shows itself as a narrow dip in the spectral profile of lasers operating on an inhomogeneously broadened gain line (e.g., a HeNe gas laser). These ‘Lamb dips’, as they are called, are the result of saturation by the laser mode which has a very narrow spectral width. Only those atoms in the Maxwell–Boltzmann velocity distribution are saturated, whose velocity results in a Doppler shift of the light that brings it into resonance, i.e., to within the atom’s homogeneous linewidth of the resonance frequency. When the laser mode frequency is detuned from atomic line center two velocity subgroups of atoms, within the distribution, are saturated corresponding to positive and negative Doppler shifts for counter-propagating fields of the mode. When the mode frequency is tuned to atomic line center, the counter-propagating fields interact with the same (zero) velocity subgroup. The saturation effect is thereby enhanced, reducing the gain by depletion of the population inversion, leading to a dip in output intensity at line center. The width of the dip is the homogeneous width of the transition (Figure 2).

The variation of output intensity around the Lamb dip is used to provide an error signal in one scheme for laser frequency stabilization. A feedback system is employed to adjust the cavity length, L, in order to maintain the mode frequency, ν, exactly on atomic line-center ($\nu = mc/2L$ where m is an integer). This scheme uses gain saturation of the amplifying medium, whereas an alternative uses saturated absorption. In this scheme, a cell of gas having a narrow absorption line, within the gain profile of the laser, is placed inside the cavity. When the laser mode is tuned to absorption, line-center saturation reduces the absorption loss, resulting in a narrow peak in the laser emission. Drifting off this peak can be used as an error signal, as before, to stabilize the mode frequency.

Saturated absorption spectroscopy uses the same mechanism by placing the absorbing specimen outside the laser cavity. The effect is detected by monitoring the transmission of a weak probe beam in the presence of a strong counter-propagating ‘pump’ beam. Both probe and pump beams are



Figure 2 (a) Holes burned in gain profile by two counter-propagating monochromatic waves at $\omega_L \neq \omega_0$. (b) 'Lamb dip' in gain profile $g(\omega)$ (or absorption profile $\alpha(\omega)$) when $\omega_L = \omega_0$.



Figure 3 Schematic diagram of saturated absorption spectroscopy experiment. The saturating pump beam is chopped or modulated and the signal is processed using phase-sensitive detection to improve the signal-to-noise ratio.

derived from the same laser using a suitable beamsplitter and, thus, have identical frequency. When tuned to line-center of the absorbing sample, the transmission of the probe increases owing to saturation by the strong pump beam interacting with the same subgroup of the inhomogeneously broadened medium (Figure 3).

The elimination of the first-order Doppler effect, in gaseous media, using this technique results in very high-resolution spectra. The residual linewidth is determined by homogeneous processes such as lifetime broadening, collisional (or pressure) broadening and power (or saturation) broadening. The latter effect is inevitable, as saturation is necessary, but may be controlled so as to contribute very little to the overall broadening. Power broadening becomes significant only when the laser intensity is appreciably in excess of the saturation intensity. Another limiting effect is transit time broadening: moving atoms spend only a limited time interacting with the narrow beams as they pass through. The consequent limit on the interaction time leads to conjugate broadening of the frequency of the transition as a result of the uncertainty principle.

The general problem of the spectral lineshape of signals in saturation spectroscopy is complex. Apart from the effects mentioned above, the lineshape will be affected by relativistic effects (second-order Doppler shifts), velocity-changing collisions, recoil effects from photon absorption and emission, velocity-dependent transit time broadening, optical pumping and laser lineshape effects.

Saturation spectroscopy is widely used in high-resolution spectroscopy for measurement of atomic and molecular transition frequencies, time and frequency standards using stabilized lasers, measurement of fundamental constants such as the Rydberg constant and the fine structure constant. Dynamical effects such as atomic collisions are also studied using saturation, whereby the relaxation of hole burning is measured in the time or frequency domain.

Polarization Spectroscopy

An important variation of saturation spectroscopy uses the change induced by a saturating beam in the real part of the complex refractive index, i.e., dispersion rather than absorption. Specifically, the technique of polarization spectroscopy employs a saturating beam that is circularly polarized to effect optical pumping on the degenerate lower level of a transition. The degenerate states may be identified, for example, with magnetic substates based on orientation of the intrinsic atomic or molecular angular momentum and labeled by the quantum numbers m_J. In equilibrium, the populations of all these degenerate substates will be equal and the optical properties of the system will then be isotropic. In particular, the polarization state of a linearly polarized probe beam will be unaffected by passage through the medium. This probe is totally rejected by an analyzer (a linear polarizer set to transmit only light in an orthogonal plane). The linear polarized beam is a linear combination of two oppositely circular polarization states, σ^+ and σ^-, and both components experience the same complex refractive index. In the presence of a circularly polarized saturating pump beam, the distribution of population amongst the degenerate substates is disturbed from its equilibrium by optical pumping. The result will be an excess of population in higher or lower m_J states (a condition known as orientation) and this leads to optical anisotropy in the medium. The refractive index for σ^+ light is now different from that for σ^- light and a relative phase shift is introduced between these components of the linearly polarized probe resulting in elliptical polarization. A component of this elliptically polarized light will then be transmitted by the analyzer and is detected. When the strong pump beam is closely counter-propagating to the probe, then both beams interact with the same velocity subgroup as in Doppler-free saturation spectroscopy. The inhomogeneous (Doppler) broadening is thus significantly reduced. The technique provides a signal above an essentially 'zero' background and is thus capable of a higher signal-to-noise ratio than saturated absorption spectroscopy. How close to 'zero' the background is depends crucially on the degree of extinction by the analyzer. High-quality polarizer/analyzer devices can achieve extinction ratios of 1:10^{-8}. Stress-induced birefringence in the windows of the cell containing the sample is a common limiting factor (Figure 4).



Figure 4 Schematic diagram of polarization spectroscopy experiment. Circularly polarized pump beam may be modulated for phase-sensitive detection of transmitted probe beam.

A probe laser of intensity I_{probe} is transmitted through a sample of length l with an intensity $I_{\text{PS}}(\omega)$ given by the following expression, that takes account of different contributions to the detected signal:

$$I_{\text{PS}}(\omega) = I_{\text{probe}}\left[\xi + \varphi^2 + b^2 + \frac{1}{2}\frac{b\Delta\alpha_{\pm}l}{(1+x^2)} + \frac{1}{2}\varphi\Delta\alpha_{\pm}l\frac{x}{(1+x^2)} + \left(\frac{1}{4}\Delta\alpha_{\pm}l\right)^2\frac{1}{(1+x)^2}\right] \qquad [9]$$

where $x = 2(\omega_0 - \omega)/\gamma$ is the detuning from the resonance frequency ω_0 normalized by the halfwidth γ of the collision broadened line. The frequency-dependent terms provide absorptive (Lorentzian) and dispersive contributions to the total lineshape. The first three, frequency independent, terms in eqn [9] are responsible for a constant background signal. They originate from residual transmission of the polarizers (ξ), their accidental uncrossing (φ), and a possible residual birefringence (b) from optical elements between both polarizers in the probe beam path. ($\xi + b^2$), normally is in the range 10^{-6}. The differential absorption coefficient for left and right circularly polarized light, $\Delta\alpha_{\pm}$, at resonance ($x = 0$), is given by:

$$\Delta\alpha_{\pm}(x=0) = \Delta\alpha_{\pm}^0 = \alpha^+ - \alpha^- = \alpha_0 S_0 \Delta C_{JJ_1} \qquad [10]$$

where α_0 is the unsaturated absorption coefficient, S_0 is the saturation parameter for the pump wave ($I_{\text{pump}}/I_{\text{sat}}$), and ΔC_{JJ_1} are Clebsch–Gordan coefficients for the respective transition and coupling case.

The dispersion-shaped component may be made to dominate by deliberately uncrossing the polarizer/analyzer combination to a small extent. This technique enhances the resolution of the transition frequency. Linewidths are limited by residual Doppler broadening owing to finite crossing angles of pump and probe beams, collisional broadening, transit time broadening, etc.

Applications of the technique have included Doppler-free spectroscopy of atomic transitions for precision measurements of fundamental constants, molecular spectroscopy and detection of atomic, molecular, and radical species in flames. By employing a different laser to accomplish the induced optical anisotropy from that used to probe the medium, molecular spectra can be simplified by the technique of 'polarization labeling'. Signals are obtained only when the probe and pump excite transitions sharing a common level and the particular transitions observed are sensitive to the selection rules for ΔJ, governing both pump and probe transitions. In this way P- and R-branch transitions can be distinguished.

Advantages of polarization spectroscopy include high sensitivity (10^2–10^3 times that of saturation spectroscopy), high signal-to-noise, simplification of molecular spectra by polarization labeling, dispersion profiles for enhanced resolution, and for frequency stabilization techniques.

Multiphoton Absorption Spectroscopy

Multiphoton absorption is the term used to describe a process in which an atom or molecule makes a single transition between two of its allowed energy levels by absorbing the energy from more than a single photon. Sequential transitions, by which successive photons are absorbed via single-photon transitions between stationary energy levels, take place provided photons arrive within the lifetime of the intermediate state. Multiphoton transitions take place via 'virtual' energy levels. The lifetime of a virtual level is determined by the uncertainty principle to be the inverse frequency detuning from the nearest stationary energy level. Thus a high photon flux is usually required for multiphoton effects to be observed (Figure 5).

The simplest multiphoton effect, two-photon absorption, may be observed using strong atomic or molecular electronic transitions, even with modest laser power. The absorption is detected by observing the fluorescence from the spontaneous, radiative decay of the excited state. Two-photon absorption spectroscopy may be made Doppler-free by arranging absorption of one photon from each of two counter-propagating beams. The moving atoms experience opposite Doppler shifts **k**·**v** from each beam. The transition energy is thus:

$$E = (\hbar\omega + \mathbf{k}\cdot\mathbf{v}) + (\hbar\omega - \mathbf{k}\cdot\mathbf{v}) = 2\hbar\omega \qquad [11]$$



Figure 5 Multiphoton absorption spectroscopy. (a) Two-photon absorption using fluorescence detection of radiative decay at ω_F. (b)Three-photon absorption spectroscopy using fluorescence detection of radiative decay at ω_F. (c) Three-photon absorption spectroscopy using ionization detection following photoionization, collisional or field ionization. (d) Two-photon resonant multiphoton ionization spectroscopy; laser at frequency ω_1 is fixed and laser at ω_2 is tuned over transitions to high-lying levels.

Absorption of two photons from a single beam is prevented by choosing a transition between levels of the same parity and angular momentum quantum number, i.e., $\Delta J = 0$ and using circularly polarized light. Absorption of two σ^+ or σ^- photons gives $\Delta J = \pm 2$, which would be forbidden, e.g., on a $n^2S - n'^2S$ transition in an alkali metal. This method of Doppler-free spectroscopy has the advantage that it involves all the atoms and not just the zero-velocity subgroup, as in saturation or polarization spectroscopy. In principle, it is also possible to use three-photon absorption, with the momentum of the wavevectors arranged to sum to zero, to achieve Doppler-free absorption on a transition between opposite parity states.

Instead of observing fluorescence following multiphoton absorption, the excited atom or molecule may be ionized by atomic collisions or by applying a d.c. electric field. Excitation of Rydberg levels (i.e., having high value of the principal quantum number n) by two- or three-photon absorption is readily accomplished. The sensitivity of this technique is enhanced by using two lasers. One laser at frequency ω_1 is tuned to a two-photon transition (energy $= 2\hbar\omega_1$) and the second laser ω_2 is tunable to excite transitions from the two-photon intermediate state to higher-lying levels (energy $= 2\hbar\omega_1 + \hbar\omega_2$). Thus, energy levels normally requiring excitation in the vacuum UV may be reached using visible frequency lasers. In such cases ionization detection may be more efficient than fluorescence since the nonradiative decay rate of these highly excited levels may exceed the fluorescence decay rate. The ion signal produced may be significantly amplified by the process of space charge amplification. A weak discharge established in the atomic vapor creates a space charge around the cathode. A single ion moving slowly through the space charge cloud acts to cancel the local field allowing many (up to 10^6) electrons to escape to the anode with a resulting amplification of 10^6 in the 'photoionization current'.

Multiphoton ionization spectroscopy is a sensitive method of recording highly excited energy levels. The sensitivity is enhanced in the technique of resonance ionization spectroscopy (RIS): two lasers are used such that the frequency of one laser is fixed close to a two-photon allowed transition and the second is tuned to excite a range of higher excited states. Absorption of an even number of photons allows excitation of levels having the same parity as the ground state and thus not accessible to normal absorption spectroscopy. In combination with a mass spectrometer to detect the ions produced by the multiphoton absorption resonance ionization mass spectrometry (RIMS), affords additional species selectivity and sensitivity. RIMS finds application in high-resolution spectroscopy of rare isotopic species and is the basis for a scheme for isotope separation.

Coherent Third-Order Processes

An important class of spectroscopic techniques exploits the coherent interaction of three input waves via the nonlinear response of the medium. Specifically, the third-order term has the form:

$$P_i^{(3)}(\omega_4,\vec{r}) = \chi_{ijkl}^{(3)}(\omega_1,\omega_2,\omega_3,\omega_4)E_j(\omega_1,\vec{r}) \times E_k(\omega_2,\vec{r})E_l(\omega_3,\vec{r}) \qquad [12]$$

where $E_m(\omega_n)$ are complex field amplitudes and the subscript $m = i, j, k, l$ refers to each of the Cartesian coordinates x, y, z of the electric vector. $\chi_{ijkl}^{(3)}$ is a fourth-rank tensor. In condensed phase media, the third-order nonlinearity is readily observed, even with modest laser intensities. In the gas phase, although $\chi_{ijkl}^{(3)}(\omega)$ is small relative to $\chi^{(1)}$, its effect is enhanced when the incident fields are resonant and this nonlinear response may be used for spectroscopy. Equation [12] shows that the induced polarization couples three waves to radiate a fourth and describes a class of interactions known collectively as four-wave mixing.

The physics of four-wave mixing interactions may be visualized as the formation and read-out of a volume hologram. The three input beams are denoted as two pumps and one probe. The process involves the interference of one pump with the probe to form a spatially periodic grating pattern in the electric field distribution. The nonlinear response of the medium via $\chi^{(3)}$ leads to a spatial modulation of the refractive index – a laser-induced grating. The second pump beam generates a signal by scattering off this grating in a manner analogous to Bragg scattering of X-rays from regular crystal planes. The condition for generating a coherent scattered beam is equivalent to matching the momentum (or wavevectors) of the interacting photons, i.e., phase matching.

Degenerate Four-Wave Mixing (DFWM) Spectroscopy

The simplest case of four-wave mixing spectroscopy involves pump and probe beams of identical (i.e., degenerate) frequency to generate a signal at the same frequency. Spectra are generated as the frequency is tuned through atomic or molecular resonances where the interaction is strongly enhanced. In this degenerate case, the pump and probe interference pattern is stationary and the remaining pump beam scatters off this grating with the same frequency. As with all parametric processes, the interaction is phase matched by a suitable geometrical arrangement of the beams. A probe intersecting with counter-propagating pump beams leads to a signal that counter-propagates with the probe. This arrangement provides 'Doppler-free' lineshapes, since only those atoms with essentially zero velocity along the line of intersection of the beams contribute to the signal. Alternatively, pump and probe beams may be arranged to cross at an angle (usually small) in the forward direction – the 'forward geometry', with the resulting signal propagating at the same small angle to the incoming beams. Signals in this case are stronger, since all velocity classes may contribute but the lineshape is Doppler broadened (Figure 6).

An additional feature of the counter-propagating pump geometry is that the phase-matched signal arises from terms that involve products of fields with the complex conjugate of the incident



Figure 6 Degenerate four-wave mixing: (a) all input frequencies are degenerate, $\omega_1 = \omega_2 = \omega_3$ and give signal at the same frequency, ω_4. Phase matching geometries are shown in (b) counter-propagating pump (phase conjugate) and (c) forward geometry. (d) and (e) show the grating formation and read-out respectively.

probe field. The induced polarization radiating the signal wave has a component given by:

$$\mathbf{P}^{(3)}_{\text{signal}}(\omega) = \chi^{(3)}(\omega)\mathbf{E}_{\text{pump}}(\omega)\mathbf{E}_{\text{pump}}(\omega)\mathbf{E}^{*}_{\text{probe}}(\omega) \qquad [13]$$

The backward propagating signal appears as a phase conjugated reflection of the incident probe wave. A probe wave that has propagated through a phase-distorting medium thus generates a signal with an initial phase distortion that will be undone as it retraces the path through the distorting medium. This phase conjugating property finds application in adaptive optics but also lends an advantage when DFWM is used as a spectroscopic probe in hostile or distorting environments, such as flames or plasmas. The counter-propagating pump geometry is often referred to as the phase conjugating geometry.

The intensity of the DFWM signal beam may be calculated using perturbation theory to derive $\chi^{(3)}(\omega)$ arising from saturated absorption. In the perturbation approximation, the probe beam is assumed to be weak and interacts with stationary atoms in the presence of counter-propagating, saturating pump fields. The signal is found from the phase-matched terms in the wave radiated from the induced polarization. When integrated over the atomic resonance line, the signal intensity, $I^{\text{int}}_{\text{sig}}$, is given by analytic expressions in the two limiting regimes of weak and strong saturation by the pump:

$$I^{\text{int}}_{\text{sig}} = \frac{|\mu_{12}|^8 N^2 k^2 T_1^2 T_2^3}{[1 + 4I_{\text{pump}}/I_{\text{sat}}(0)]^{5/2}} I^2_{\text{pump}} I_{\text{probe}} \qquad [14]$$

when $I_{\text{pump}} \ll I_{\text{sat}}(0)$ and

$$I^{\text{int}}_{\text{sig}} \propto |\mu_{12}|^3 N^2 k^2 T_1^{-1/2} T_2^{1/2} I^{-1/2}_{\text{pump}} I_{\text{probe}} \qquad [15]$$

when $I_{\text{pump}} \gg I_{\text{sat}}(0)$.

In these relations μ_{12} is the atomic dipole moment, N the atomic number density, $I_S(0) = \hbar^2/T_1 T_2 |\mu_{12}|^2$ is the line-center saturation intensity, and T_1 and T_2 are the longitudinal and transverse relaxation times, respectively. Extensions of the basic theory accommodate the effects of moving absorbers (Doppler effect) in both the phase-conjugate and forward phase matching geometry.

These results are derived using perturbation theory, by assuming that the probe field is weak. In practice the signal is optimized when pump and probe are of equal intensity and approximately equal to the saturation intensity. This situation violates the perturbation theory assumption but the signal intensity may be derived using nonperturbative analytical methods, although the resulting expression is more complicated. Alternatively, the quantum mechanical equations for the nonlinear susceptibility can be solved numerically to find the signal level for arbitrary intensity of the incident fields. Optimum signal-to-noise ratio in the spectra is achieved using approximately saturating intensities.

The sensitivity of resonant DFWM and the coherent nature of the signal beam suits the process to spectroscopy of nonfluorescing or trace molecular species, such as radicals created in chemical reactions. Equation [15] shows that the DFWM signal becomes relatively insensitive to collisional effects when the incident lasers saturate the transition. This feature of DFWM gives it an additional advantage over laser-induced fluorescence in optical diagnostic applications where quantitative evaluation of fluorescence intensity is hampered by collisional quenching. The state and species selectivity afforded by resonant DFWM is exploited in diagnostics of combustion and plasma processes, where the reduction of Doppler broadening allows high-resolution spectra from high-temperature gases. The relative intensity of spectral lines is used to derive temperature and concentration information with time and space resolution.

Additional selectivity is provided by using two input frequencies in two-color four-wave mixing (TC-FWM), to probe molecular excited state dynamics. The TC-FWM process uses resonant enhancement on two coupled transitions, i.e., the pump beams excite one transition and the probe and signal are generated on another transition having a common level with that excited by the pumps.

Coherent Raman Spectroscopy

The classical theory of spontaneous Raman scattering shows that a nonresonant pump of frequency ω_{p} wave can excite a resonance ω_{m} in a molecule with a nonlinear polarizability $\beta(x)$. (x is the spatial coordinate of the internuclear potential.) The wave resulting from this inelastic scattering is a Stokes wave of frequency $\omega_{\text{S}} = \omega_{\text{p}} - \omega_{\text{m}}$. The propagation of the Stokes wave is governed by the complex Raman susceptibility (Figure 7a):

$$\chi_{\text{Raman}}(\omega_{\text{s}}) = \chi'_{\text{Raman}}(\omega_{\text{s}}) + i\chi''_{\text{Raman}}(\omega_{\text{s}}) \qquad [16]$$

This generated Stokes wave may then couple with the pump to drive the molecular resonance coherently leading to amplification of the Stokes wave at the expense of the pump. This process of stimulated Raman scattering (SRS), provides gain if the amplification exceeds the loss due to absorption, scattering, etc. There is, therefore, a definite threshold intensity that the pump must satisfy to observe SRS. The SRS



Figure 7 Coherent Raman spectroscopy. (a) Spontaneous Raman scattering of input pump ω_L producing Stokes wave ω_S in inelastic scattering. (b) Coherent anti-Stokes Raman scattering (CARS). Phase matching geometries for CARS is shown for a nondispersive medium in (c) and dispersive media in (d) and (e). The planar boxcars geometry in (e) may be folded along the dotted line (folded boxcars geometry) to separate the signal into an orthogonal plane from the pump beams to reduce scattered pump light reaching the detector.

gain $g(\omega_s)$ at the Stokes frequency ω_s is given by:

$$g(\omega_s) = -\frac{k_s}{2n_s^2}|E(\omega_L)|^2\chi''_{\mathrm{Raman}}(\omega_s) \qquad [17]$$

where k_s and n_s are the wavevector and refractive index for the Stokes wave, $E(\omega_L)$ is the field amplitude at the pump laser frequency ω_L, and $\chi''_{\mathrm{Raman}}(\omega_s)$ is the imaginary part of the complex Raman susceptibility:

$$\chi''_{\mathrm{Raman}}(\omega_s) = \frac{-\varepsilon_0 N\left(\frac{\partial\beta}{\partial x}\right)^2\gamma}{32m_e\omega_v\left\{(\omega_m-(\omega_L-\omega_S))^2+\frac{\gamma^2}{4}\right\}} \qquad [18]$$

In this expression $\partial\beta/\partial x$ is the variation of polarizability β with internuclear displacement x, N is the molecular population density, and γ is the linewidth due to damping. Spectroscopy based on SRS provides signals that are many orders of magnitude stronger than those from spontaneous Raman scattering, and is widely used to study spectra of complex molecules having no absorption spectra in the visible region.

A four-wave mixing interaction, involving a pump and probe beam of different frequencies, generates a nonstationary grating. The signal generated by scattering of a second pump beam off this moving grating is Doppler-shifted to lower or higher frequency. These signal beams correspond respectively to Stokes or anti-Stokes waves in Raman scattering. A probe beam at the Stokes frequency will thus interact with a pump beam to generate a coherent signal at the anti-Stokes frequency; a process known as coherent anti-Stokes Raman scattering (Figure 7b). A probe at the anti-Stokes frequency correspondingly gives the process of coherent Stokes Raman scattering (CSRS). Phase matching is necessary for both CARS and CSRS and is satisfied by an appropriate arrangement of the incident wavevectors (Figure 7c,d and e).

CARS has proven to be a valuable spectroscopic technique in a wide variety of applications. A CARS spectrum is generated by scanning the frequency of the probe, i.e., the Stokes laser. The signal strength is given by

$$I_4 = I_{\mathrm{CARS}} = \frac{\omega_4^2}{n_1^2 n_2 n_4 c^4 \varepsilon_0^2} I_1^2 I_2 |\chi_{\mathrm{CARS}}|^2 l^2 \times\left(\frac{\sin(\Delta k l/2)}{\Delta k l/2}\right)^2 \qquad [19]$$

where I_1 and I_2 are the intensity of the pump and Stokes beams, respectively, l is the interaction length, and n_i are the refractive indices at frequency ω_i. The maximum signal is generated when the phase mismatch $\Delta k = 0$. The third-order susceptibility, $\chi^{(3)} = \chi_{\mathrm{CARS}}$, in general consists of a nonresonant part $\chi_{\mathrm{nr}}^{(3)}$, which is independent of the frequency of the exciting beams, and a Raman-resonant contribution $\chi_{\mathrm{r}}^{(3)}$:

$$\chi^{(3)} = \chi_{\mathrm{nr}}^{(3)} + \chi_{\mathrm{r}}^{(3)} \qquad [20]$$

The lineshape in coherent Raman spectroscopy is affected by interference between resonant and nonresonant contributions. This effect is exploited to derive the concentration of the resonant (Raman active) species relative to that of the background of known density. A more common application of CARS, however, is for temperature measurement. The dependence of the signal intensity on $|\chi_{\mathrm{CARS}}|^2$, and therefore on the square of the molecular population of the initial state, yields a spectrum from which the temperature may be derived by assuming a Maxwell–Boltzmann distribution over the state populations.

A particularly useful application of CARS employs a narrow linewidth pump laser and a broad bandwidth Stokes laser. CARS signals are generated simultaneously on all frequencies such that the corresponding Stokes frequency is available from the broadband probe. The spectrum recorded with a single laser pulse can thus provide population information on a wide range of molecular states, giving time- and space-resolved measurement of temperature and concentration.

CARS and CSRS spectroscopy is applied to both gas and condensed phase media. Owing to the higher density in the latter, signals may be strong in spite of the two-photon nature of the resonant interaction.

Time Domain Four-Wave Mixing Spectroscopy

Four-wave mixing spectroscopy may also be executed in the time domain. The three incident waves may arrive as pulses separated in time by variable delays. The interaction is, therefore, mediated by the atom or molecule's induced polarization or coherence. DFWM, CARS, and CSRS processes may thus be used to study ultrafast relaxation since the signal intensity gives a measure of the coherence decay in the intervening delay between the pulses. These processes are intimately related to coherent transient spectroscopy using measurements of free induction decay, photon echoes, and stimulated photon echoes.

Laser-Induced Grating Spectroscopy

The four-wave mixing processes discussed above involve a spatial modulation of the molecular population and a consequent modulation of the refractive index for resonantly interacting waves. The signals are radiated by the coherent oscillations of the molecular populations that decay rapidly. Relaxation processes result in transfer of energy from the excited molecular states, leading to a temperature and density grating in the bulk medium with a period Λ, given by:

$$\Lambda = \lambda_{\text{pump}}/(2 \sin \theta_1) \qquad [21]$$

where θ_1 is the angle between the interfering beams of wavelength λ_{pump}. A nonresonant wave of wavelength λ_{probe} may be scattered by this laser-induced grating provided it is incident on the grating at the angle θ_2 satisfying the Bragg condition:

$$\theta_2 = \sin^{-1}(\lambda_{\text{probe}}/2\Lambda) \qquad [22]$$

The periodic temperature/density grating, when induced by a short duration laser pulse, is accompanied by two oppositely propagating acoustic waves. The reflectivity of Bragg scattering is temporally modulated as the acoustic waves traverse the stationary grating at the local sound speed. Measurement of the period of these oscillations yields the sound speed from which the temperature may be derived. The stationary grating and acoustic waves decay by diffusive and damping processes, dependent upon the bulk medium properties. Measurement of the decay time of the grating induced in gas phase media yields the gas pressure if the gas dynamic parameters are known (Figure 8).

Laser-induced grating spectroscopy (LIGS), has been widely employed for studies of condensed phase relaxation processes. Applications have also been developed for gas phase studies using resonant absorption to enhance the thermal grating component. A grating may, however, also be induced in response to the electrostrictive effect of the high electric field in the interference pattern of two intense pump waves. Such electrostrictive gratings do not require resonant absorption and their spectroscopic utility centers on the study of relaxation effects in the molecular medium.



Figure 8 Laser-induced thermal grating spectroscopy. (a) Absorption of energy from pump lasers creates excited molecular population in grating pattern shown in (b). Spacing of laser induced grating Λ is set by angle of intersection of pumps. Quenching, *Q*, of excited population by collisions transfers heat to bulk medium and forms thermal grating. (c) Probe incident at Bragg angle θ_2 is scattered to form signal.

List of Units and Nomenclature

Formulae are expressed in SI units

c	Speed of electromagnetic wave *in vacuo*
$\mathbf{E}$	Electric field amplitude
$g_0(\omega)$, $g(\omega)$	Gain coefficient at line center, at frequency ω
h	Planck's constant
I	Intensity of electromagnetic wave
I_{sat}	Saturation intensity of medium
$\mathbf{k}$, k	Wave vector, scalar value of wave vector ω/c
m_{e}	Mass of electron
n_{m}	Refractive index of medium for mth beam
N	Atomic or molecular population density
$\mathbf{P}$	Polarization field amplitude
T_1	Longitudinal relaxation time
T_2	Transverse relaxation time
α_0, $\alpha(\omega)$	Absorption coefficient at line center, at frequency ω
$\beta(x)$	Molecular polarizability as function of internuclear separation x
ε_0	Permittivity of free space
μ_{12}	Dipole moment for transition between energy levels 1 and 2
ν	Frequency of electromagnetic wave
$\chi^{(n)}$	nth order susceptibility
ω	Angular frequency of electromagnetic wave

See also

Coherent Transients: Coherent Transient Spectroscopy in Atomic and Molecular Vapours; Foundations of Coherent Transients in Semiconductors; Ultrafast Studies of Semiconductors. **Fiber and Guided Wave Optics:** Nonlinear Optics. **Imaging:** Adaptive Optics. **Nonlinear Optics, Applications:** Phase Matching. **Nonlinear Optics, Basics:** $\chi^{(2)}$–Harmonic Generation; Four-Wave Mixing; Kramers–Kronig Relations in Nonlinear Optics. **Phase Control:** Phase Conjugation and Image Correction. **Physical Applications of Lasers:** Sum-Frequency Generation at Surfaces. **Scattering:** Raman Scattering; Stimulated Scattering. **Spectroscopy:** Raman Spectroscopy; Second-Harmonic Spectroscopy.

Further Reading

Clark RJH and Hester RE (eds) (1988) Quantitative CARS spectroscopy. In: *Advances in Non-Linear Spectroscopy*, pp. 193–251. New York: John Wiley.

Corney A (1986) *Atomic and Laser Spectroscopy*. Oxford, UK: Oxford University Press.

Demtröder W (1996) *Laser Spectroscopy*, 2nd edn. Berlin: Springer-Verlag.

Dreier T and Ewart P (2002) Coherent techniques for measurements with intermediate concentrations. In: Kohse-Höinghaus K and Jeffries JB (eds) *Applied Combustion Diagnostics*. London: Taylor and Francis.

Eesley GL (1981) *Coherent Raman Spectroscopy*. London: Pergamon.

Eichler HJ, Günter P and Pohl DW (1986) *Laser Induced Dynamic Gratings*. Berlin: Springer-Verlag.

Feld MS and Letokhov VS (eds) (1980) *Coherent Nonlinear Optics, Recent Advances*. Berlin: Springer-Verlag.

Fisher RA (ed.) (1983) *Optical Phase Conjugation*. San Diego, CA: Academic Press.

Levenson MD and Kano SS (1987) *Introduction to Nonlinear Laser Spectroscopy*. Revised edn. San Diego, CA: Academic Press.

Raman Spectroscopy

R Withnall, University of Greenwich, Chatham, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Inelastic light scattering, the optical analogue of Compton scattering, had been predicted to occur by Smekal in 1923, but it was Chandresekar Venkataraman Raman who provided the first experimental demonstration of the phenomenon in February 1928. Only a few months later in 1928 the Russian scientists, Landsberg and Mandelstam observed inelastic light scattering from a quartz crystal. In spite of initial claims to the contrary, this was the same effect that had been observed by Raman, although the Russian scientists did not acknowledge this, preferring to call the effect 'combinatorial scattering'. It was not until the 1970s that the effect became known as Raman scattering everywhere, including Russia.

As typically practised, Raman spectroscopy involves laser excitation of a sample and measurement of the wavelength and intensity distribution of the scattered Raman light. When a microscope is used for delivering laser excitation and/or collecting the inelastically scattered light, the technique is referred to as Raman microscopy. However, it is important to recognize that, apart from the differences in sampling configuration, there are no fundamental differences between Raman microscopy and Raman spectroscopy; the terms merely identify the different sampling techniques.

Since its invention in 1960, major advances in the technology of the laser have occurred, resulting in the wide variety of laser light sources that are currently available for Raman spectroscopy. Characteristic properties of laser systems for Raman microscopy will be described in this chapter, following an introduction to the technique and its applications in the next section below. Then, the commonly used laser sources for Raman microscopy are categorized according to the wavelength regions of their emissions, along with their merits and drawbacks for each application. The chapter will consider mainly continuous wave laser sources, because pulsed laser beams that are tightly focused with microscope optics give very high irradiance that would destroy most samples.

Raman Microscopy

The first experimental Raman microscopes were developed in the mid-1970s by two independent groups, and it was not long before the first generation of Raman microscopes were subsequently commercialized. Many of these early instruments simply consisted of commercial optical microscopes coupled to Raman spectrometers, as shown in Figure 1. It was recognized that the use of a microscope for sampling in this way can facilitate the Raman examination of tiny particles of micrometer dimensions.

The optical lay-out in Figure 1 shows an infinity corrected microscope. The advantage of using this, rather than a standard tube length microscope, is that its length can be extended in order to incorporate additional optical elements that are required for coupling to the Raman excitation and collection optics. In the optical layout, the incident laser beam is spatially filtered by a pinhole, D_1, in order to remove the diffraction rings and give a point source. The laser light is then partially reflected by beamsplitter, B_1, and focused on to the sample by the microscope objective. The back-scattered Raman radiation is collected by the same microscope objective, partially transmitted by the beamsplitter, and directed into the entrance slit of the Raman spectrometer by means of coupling optics. The accurate location of an aperture, D_2, at the focal point improves the spatial resolution and allows depth profiling of transparent samples. The two pinholes, D_1 and D_2, act as spatial filters and are referred to as confocal diaphragms. The Raman microscope is described as being confocal, because out-of-focus light, collected from outside the focal volume, is rejected.

The use of the beamsplitter, in the optical path of early Raman microscope designs, gives rise to significant losses of the precious Raman



Figure 1 Diagram of the optical layout of a visible Raman microscope (Reproduced from Turrell G, Delhaye M and Dhamelincourt P (1996) Characteristics of Raman microscopy. In: Turrell G and Corset J (eds) *Raman Microscopy. Development and Applications*, 2. London: Academic Press).

scattered light. If a 50:50 beamsplitter is used then half of the incoming laser light is lost by transmission at B_1 and, more significantly, half of the Raman scattered light is lost by reflection at B_1. As long as a higher laser power can be employed, it is better to use a 90:10 beamsplitter that transmits 90% of the light and reflects 10%; then, only 10% of the incoming laser light is directed by B_1 on to the sample, but 90% of the Raman scattered light is transmitted by B_1 towards the detector and only 10% of the Raman light is lost by reflection at B_1. The efficiency of a beamsplitter can be defined as the product of the reflectivity at the laser wavelength and the transmission at the Raman-shifted wavelength. Thus, conventional 50:50 and 90:10 beamsplitters would have efficiencies of 25% and 9%, respectively. Recently, however, holographic notch filters have been developed which can be used as higher efficiency beamsplitters. These typically have a laser rejection contrast ratio of better than 10^4, reflecting ca. 90% of the laser excitation and transmitting ca. 90% of the Raman scattered light, thus giving an efficiency of ca. 81%. Due to these considerations, higher throughput, commercial Raman microscope designs usually incorporate a holographic notch filter.

The importance of Raman microscopy stems from the fact that it is the only microanalytic method available today, by use of which it is possible to identify, or characterize, small particles of micrometer dimensions *in situ*. It is also advantageous that no sample preparation is required when performing Raman microscopy.

The fundamental limit of the lateral spatial resolution (i.e., for a diffraction limited focus) is the separation at which the maximum of one Airy disc function just touches the first minimum of an adjacent Airy disc, given by:

$$\text{Lateral spatial resolution} = \frac{1.22\lambda}{2\text{NA}} \qquad [1]$$

where λ is the wavelength of the light and NA is the numerical aperture of the microscope objective.

The axial Airy disc function determines the resolution in the longitudinal direction. A good estimate of the axial resolution limit for low numerical aperture is given by:

$$\text{Axial spatial resolution} = \frac{2\lambda}{(\text{NA})^2} \qquad [2]$$

When the sample is heterogeneous and exhibits fluorescence that is not evenly distributed within the sample, a region of the sample can be selected with the microscope that shows the minimum amount of fluorescence. If the fluorescence is intrinsic to the sample itself, then it is possible to use the shift subtract technique and/or temporal discrimination between the fluorescence and the Raman scattering. The latter can be achieved by Kerr gate fluorescence rejection, in which a pulse of light is used to close a Kerr gate shutter. The problem with this approach, however, is that it uses a laser pulse, and even pulses of modest energy will have extremely high irradiance when focused to a tiny spot by a microscope objective. Such laser pulses would inevitably destroy the sample under a microscope.

Another approach for reducing fluorescence is to use near infrared excitation, which is low enough in energy so that absorption cannot occur to promote electronic transitions. The technique of Fourier Transform Raman (FTR) spectroscopy often offers the best chance of obtaining Raman spectra from fluorescent samples for this reason. Low energy excitation of wavelength equal to 1064 nm, provided by a Nd:YAG laser, is normally used for FTR. Disadvantages are that the Raman scattering efficiency is low relative to that obtained with visible excitation, due to the ν^4 dependency (ν^4 refers to Rayleigh scattering of the Raman light). This is compensated to some extent by employing a high throughput (Jacquinot advantage) interferometer. However, this works better for macro rather than micro samples. This is because the coupling of a microscope to an FT Raman spectrometer has a fundamental drawback; the microscope is throughput limited, so the high throughput advantage of the FTR spectrometer cannot be realized in FTR microscopy. The image of the Jacquinot stop (the large circular aperture which is the entrance to the interferometer) at the sample plane typically has a diameter of a few hundred μm, which is much larger than particles with diameters of ca. 1 μm having similar dimensions to the waist diameter of the 1064 nm light excitation at its diffraction-limited focus. Consequently the throughput advantage of the interferometer is not fully exploited and there is a trade-off of spatial resolution with signal-to-noise at the detector. For this reason, the typical spatial resolution that is achieved is in the range of 15–100 μm rather than 4 μm, as claimed in the literature. Bruker has commercialized an FTR microscope by coupling an optical microscope to an FTR spectrometer with near infrared optical fibers.

An approach that offers more promise for reducing fluorescence and achieving spatial resolution close to the diffraction limit is to use near infrared excitation in conjunction with dispersive Raman microscopy. For example, semiconductor lasers operating from 785 to 852 nm can be used in conjunction with sensitive multichannel silicon-based CCD arrays. If longer excitation wavelengths are necessary, in order to overcome the problems with fluorescence, then diode lasers can be used that emit at longer wavelengths in conjunction with dispersive Raman spectrometers equipped with multichannel near infrared (NIR) detectors, e.g., Ge- or InGaAs-array detectors.

The applications of Raman microscopy cover many areas, including material science, the earth sciences, environmental science, biology and medicine, forensic science, and even the analysis of artworks. These areas are too wide ranging to be described in detail here, but the interested reader is referred to the Further Reading section at the end of this article.

Characteristics of Laser Sources

The laser is an excellent light source for Raman spectroscopy to such an extent that the terms 'Raman spectroscopy' and 'laser Raman spectroscopy' are synonymous for all but the most esoteric experiments, for example, with synchotron sources. Indeed, the advent of the laser was the stimulation for the renaissance of Raman spectroscopy in the 1960s, given its special properties, such as monochromaticity, high intensity, beam collimation, and coherence.

The characteristics of laser light and the advantages it offers to Raman microscopy are now considered.

Beam Quality

The light inside a laser tube is formed from a number of standing waves having distinct vibrational modes. There are a limited number of these modes transverse to the beam and these are characterized by the TEM$_{pq}$ number (where p and q can be 0, 1, 2,...) where TEM is an acronym for 'transverse electromagnetic'. When a laser is operating in its fundamental TEM$_{00}$ mode, light rays are reflected on axes between the end mirrors of the laser cavity. The '00' indicates that there are no nodes in the beam profile (Figure 2a), and the laser beam has a Gaussian intensity profile in the radial direction:

$$I(r) = I_0 \exp\left(- \frac{2r^2}{w^2} \right) \qquad [3]$$

where $I(r)$ is the irradiance at a radial distance r from the axis of the beam, I_0 is the axial irradiance, and w is the beam radius.

For higher-order modes, a number of nodes are observed in the beam profile, which arise from off-axis light rays being reflected between the end mirrors, for example, the TEM$_{11}$ mode has two nodes which are mutually perpendicular (Figure 2b).

The propagation characteristics of a Gaussian beam can be fully defined, either by the diameter of the beam waist or by the far-field divergence. Consequently, it is only necessary to know the diameter of the beam waist ($2w_0$), or the diameter of the beam ($2w_z$) at a longitudinal distance z from the waist, in order to determine the propagation characteristics of the beam:



Figure 2 Transverse electromagnetic modes formed with confocal concave mirrors, (a) TEM$_{00}$, and (b) TEM$_{11}$. (Reproduced with permission from Young M (1977) *Optics and Lasers: an Engineering Approach*. Berlin, Heidelberg: Springer-Verlag

$$w(z) = w_0 \sqrt{1 + \left(\frac{z}{z_R} \right)^2} \qquad [4]$$

$$R(z) = z\left[1 + \left(\frac{z_R}{z} \right)^2 \right] \qquad [5]$$

where the quantity $z_R = \pi w_0^2/\lambda$ is known as the Rayleigh range of the beam, λ is the wavelength of the laser radiation, and $R(z)$ is the radius of curvature of the wavefront at a distance z from the beam waist.

The wavefront is planar at the minimum beam waist and the Rayleigh range is the distance from the beam waist to the location at which the wavefront is most curved (Figure 3), the region from the waist to



Figure 3 The Rayleigh range and embedded Gaussian (adapted from http://beammeasurement.mellesgriot.com/tut_m2.asp).

the Rayleigh range being the near field. Beyond approximately ten times the Rayleigh range, in the far field, the beam diverges as a cone with approximately straight sides. It can be seen by substituting $z = z_R$ into eqn [4] that the beam diameter at the Rayleigh range is $\sqrt{2}$ times the waist diameter.

Unfortunately laser beams do not conform to pure Gaussian functions and therefore they do not propagate according to the above equations. As a result, a dimensionless beam propagation parameter was devised in the early 1970s. This parameter, known as the M^2 factor or the 'times diffraction limit', is based on the brightness theorem, which states that for any laser beam the product of the beam diameter and the far-field divergence is a constant. Thus, M^2 is defined as the ratio of the laser beam's multimode diameter-divergence product to the ideal diffraction-limited (TEM_{00}) beam diameter-divergence product:

$$M^2 = \left(\frac{2w_m \Theta_m}{2w_0 \theta_0}\right) \qquad [6]$$

where Θ_m is the laser beam's multimode divergence, θ_0 is the theoretical diffraction-limited divergence, $2w_m$ is the laser beam's multimode waist diameter, and $2w_0$ is the ideal diffraction-limited beam waist diameter.

Alternatively, M^2 can be defined as the square of the ratio of the multimode beam diameter ($2w_m$) to the diffraction-limited beam diameter ($2w_0$):

$$M^2 = \left(\frac{2w_m}{2w_0}\right)^2 \qquad [7]$$

The intensity of the beam has a Gaussian distribution in the radial direction, but the accepted definition of beam diameter is the distance at which the intensity has fallen to $1/e^2$ (i.e., ca. 13.5%) of its axial intensity, as can be seen by setting $r = w$ in eqn [3] above. This definition only applies properly to Gaussian beams; for other beam profiles the diameter can be calculated using a second moment measurement of the entire beam.

The real beam, then, can be treated as Gaussian by substituting an artificial wavelength $M^2\lambda$ into the equations that apply to an ideal diffraction-limited TEM_{00} beam. The ideal TEM_{00} Gaussian can be superimposed as an 'embedded Gaussian' on the optical diagram of the real multimode beam (Figure 3). It can be seen that the multimode beam has a waist diameter and a divergence that are both M times larger than those of the embedded Gaussian.

The M^2 factor has a value of unity for an ideal diffraction-limited TEM_{00} beam, and values of greater than unity for all other beams; it can be as high as several hundred for a distorted beam of poor quality. This is an important parameter where a tightly focused laser spot (e.g., confocal Raman microscopy) or low divergence (e.g., remote sensing) are required.

Polarization

Although polarization is not an inherent property of laser light, lasers provide plane polarized light when the end windows of the laser tube are mounted at Brewster's angle (θ_B):

$$\theta_B = \tan^{-1} n \qquad [8]$$

where n is the refractive index of the window material for the appropriate wavelength of laser light. For this angle, reflected light is completely plane polarized and consequently the laser light that is generated is also plane polarized. Brewster windows are often used inside the laser cavity in order to reduce reflection losses. This is important in low-gain lasers such as HeNe lasers where laser action could be prevented by reflection losses. Air-cooled ionic gas lasers typically deliver highly linearly polarised output with ratios exceeding 1000:1.

The polarization property of the exciting light is used a great deal in Raman spectroscopy. In combination with the polarization properties of the Raman scattered light, it can be used to determine the depolarization ratios, ρ, of Raman bands in the solution state. In solid state studies it can be used to determine the degree of orientation, for example, in polymeric fibers or films, and in single crystal studies it can be used to determine the symmetry classes of the Raman active vibrations. In such studies a linear polarizer is used to improve the degree of plane polarization of the laser light, and a half-wave plate is used to rotate the plane of polarization by 90°.

Plane polarized laser light can be converted to circularly polarized laser light which is required for Raman optical activity (ROA) studies. For example, plane polarized 514.5 nm laser light provided by an argon ion laser can be converted to circularly polarized light by an electro-optic modulator. As CCD detectors are usually employed in present-day ROA experiments and they have relatively long sampling times, slow polarization modulation is required which can be achieved by periodically rotating a quarter-wave plate or by applying a square quarter-wave voltage to a Pockels cell.

Whereas optical isomers or enantiomers give identical Raman spectra, they are distinguished in the ROA experiment by the sign of the ROA signal. Indeed, the sign can be used to determine the absolute configuration of a chiral molecule. Also the enantiomeric excess of mixtures of enantiomers can be determined in such experiments, with obvious applications in the pharmaceutical industry, and the conformations of biological molecules, for example, proteins, nucleic acids, sugars, and viruses, can be determined.

Up until now, the ROA technique has been practised by no more than a handful of research groups world-wide, but it is expected that this situation will change in the near future, since the first commercial ROA spectrometer (the ChiralRAMAN spectrometer) has recently been launched by Biotools Inc. This spectrometer makes use of a solid state laser as the source of the polarized laser light.

Beam Divergence

Referring to Figure 3, the full divergence angle, Θ, for the fundamental TEM_{00} Gaussian beam is given by:

$$\Theta = \lim_{z\to\infty} \frac{2w(z)}{z} = \frac{2\lambda}{\pi w_0} \qquad [9]$$

From eqn [4] it can be seen that the spot size increases linearly with the longitudinal distance z and, from eqn [9], that it diverges at a constant cone angle, Θ. It can also be seen from eqn [9] that the smaller the spot size, w_0, the greater the beam divergence angle, Θ.

Indeed, a highly divergent beam is a problem with edge-emitting laser diodes due to the small dimensions of the light source. Furthermore, it is much smaller in the vertical direction than in the horizontal, giving rise to an elliptical output beam that diverges much more rapidly in the vertical direction than in the horizontal. The highly divergent, elliptical beam can be corrected, to an extent, with a cylindrical lens, but the inherent problem of a small, elliptical source can never be completely corrected.

In contrast, vertical-cavity surface-emitting semiconductor lasers (VCSELs) do not have the same limitations on beam divergence because the cavity is in the vertical direction and the light emission occurs from the surface, which has a much larger area than the light source of an edge emitter. Indeed, frequency-doubled green and blue semiconductor lasers are now available, having beams with M^2 values of less than 1.1 and beam divergences of a few milliradians. In terms of these beam characteristics, it appears that these lasers are beginning to challenge the argon ion laser.

Emission Linewidth

The laser linewidth limit, $\Delta\nu_{\mathrm{L}}$, is given by the Schawlow–Townes expression:

$$\Delta\nu_{\mathrm{L}} = \frac{2\pi h\nu(\Delta\nu_{\mathrm{c}})^2}{P_{\mathrm{out}}} \qquad [10]$$

where $\Delta\nu_{\mathrm{c}}$ is the linewidth of the passive resonator, $h\nu$ is the photon energy, and P_{out} is the laser power output.

The power output, P_{out}, is equal to the number of photons, N_{p}, in the resonator times the energy per photon, $h\nu$, divided by the photon lifetime, τ_{c}:

$$P_{\mathrm{out}} = \frac{N_{\mathrm{p}}h\nu}{\tau_{\mathrm{c}}} \qquad [11]$$

Furthermore, the width $\Delta\nu$ of the resonance curve, at which the intensity has fallen off to half the maximum value, is given by:

$$\Delta\nu_c = (2\pi\tau_c)^{-1} \quad [12]$$

Substituting for P_{out} and $\Delta\nu_c$ from eqns [8] and [9] into eqn [10] gives the limit for the linewidth, $\Delta\nu_L$:

$$\Delta\nu_L = \frac{\Delta\nu_c}{N_p} \quad [13]$$

The linewidth of a laser is characterized by its *Q* factor:

$$Q = \frac{\nu}{\Delta\nu} \quad [14]$$

where ν is the frequency of the laser line and $\Delta\nu$ is the linewidth.

Other useful relationships involving linewidth parameters are:

$$Q = \frac{\lambda}{\Delta\lambda} \quad [15]$$

and

$$\Delta\tilde{\nu} = -\frac{\Delta\lambda}{\lambda^2} \quad [16]$$

where λ and $\Delta\lambda$ are the wavelength and linewidth (in units of metres), respectively, and $\Delta\tilde{\nu}$ is the linewidth expressed as a wavenumber (in units of cm^{-1}).

The *Q* factor can be as high as 10^8 which is of great use in high resolution spectroscopy.

Visible Lasers

Helium-Neon Laser

The helium-neon laser is continuously pumped electrically using a high dc voltage of up to 1 kV. The gain medium consists of a gas mixture of about 10 parts helium to each part of neon at a pressure of about 3 Torr. The gain of this medium is extremely low, hence the requirement for Brewster-angle windows to eliminate reflection loss of the light polarized in the plane that includes the axis of the laser and the normal to the Brewster window. Due to this requirement, the light output is necessarily plane polarized.

The pumping excites helium atoms by electron impact, and resonant energy transfer to neon atoms then occurs via collisions of the gaseous atoms (Figure 4). This creates a population inversion in the neon atoms, enabling the laser transition to occur at 632.8 nm. Following emission, the neon atoms decay nonradiatively down to their metastable $2p^5 3s^1$ level from which they decay back down to the ground state via collisional de-excitation with the walls of the tube. This mechanism restricts the maximum achievable power output to ca. 50 mW, because of the need to depopulate the metastable neon atoms by wall collisions.



Figure 4 Energy levels of the He-Ne laser.

An advantage of using helium-neon lasers for Raman spectroscopy is that they generally operate in the fundamental TEM_{00} mode, which is critically dependent on the ratio of the length of the tube to its diameter. For this reason they are designed to have small tube diameters of around a few millimetres and lengths of 0.15–0.50 m, the small diameter also aiding collisional de-activation with the walls due to the relatively large surface to volume ratio of the tube. Another advantage of this laser for Raman spectroscopy is that the linewidth of the 632.8 nm emission line is ca. 1.5 GHz.

A disadvantage of the helium-neon laser is that it emits a large number of spontaneous emission lines originating from the excited neon atoms. These plasma emissions are observed in the Raman spectrum as sharp lines unless they are filtered out, for example, by a pre-monochromator or an interference filter. It should be mentioned, in passing, that these plasma lines are not always unwanted, because they can be very useful for wavenumber calibration of the Raman spectrometer.

The low output power of <50 mW is not generally a disadvantage for Raman microscopy since higher laser powers can often cause photolytic or thermal degradation of the sample. This is due to the high irradiance at the sample when the laser light is focused to a tight spot by the microscope objective. The excitation wavelength of 632.8 nm is suitable for combined use of the laser with a silicon-based CCD detector in Raman spectroscopy, because large Stokes shifts in the 3000–4000 cm^{-1} region lie well within the quantum efficiency curve of this detector. It is also possible, though less common, to operate the helium-neon laser on weaker transitions that include the green 543.5 nm line.

Argon Ion Laser

The argon ion laser was one of the first lasers to be discovered following the invention of the laser and up until now it has been used extensively for Raman spectroscopy, among many other applications. Excitation is provided by a continuous electrical discharge, and because of the high energy required to ionize the argon atoms and then promote the ions to an excited state, the efficiency of the laser is very small (ca. 0.1%). In spite of this, once population inversion has been achieved, the gain of the laser is very high and output powers of up to 25 W can be obtained for the strong lines at 488.0 and 514.5 nm and up to 50 W for multiline operation.

An advantage of the argon ion laser is that it can provide emission at more than 35 discrete wavelengths, the strongest of which are listed in Table 1. These lie in the green, blue, and near ultraviolet regions of the spectrum, a number of the ultraviolet lines only being obtained on the larger frame argon ion lasers. Discrete laser emission lines are selected by tuning a prism or grating inside the cavity. The argon ion laser can also be operated in multiline mode, for example, for pumping dye or Ti:sapphire lasers.

Table 1 Continuous wave argon ion laser wavelengths and output powers for the Coherent Inc. Innova 300 argon ion laser system

Wavelength (nm)	*Power (mW)*
228.9	30
238.3	100
244.0	400
248.3	180
257.3	750
275.4	5
300–305.5	20
333.4	40
333.8	30
335.8	20
351.1	200
351.4	60
363.8	240
454.5	140
457.9	420
465.8	180
472.7	240
476.5	720
488.0	1800
496.5	720
501.7	480
514.5	2400
528.7	420

The five lines below 260 nm are frequency doubled.

The linewidths of the argon ion emission lines at 488.0 and 514.5 nm are around 4.0 GHz. The high temperature laser tube has a diameter of approximately 12 mm and a length in the range of 0.1 to 1.8 m. A 240 V three phase power supply and ca. 35 A are required for pumping a medium power 5 W argon ion laser. The tube also requires water cooling at a flow rate of ca. 10 L/min and a pressure of 25 psi because of the large amount of heat dissipation.

For Raman microscopy smaller, air-cooled argon ion lasers, which only require a 240 V single phase power supply, can be used to provide output of a few hundred milliwatts on the 488.0 and 514.5 nm lines. For this application, the excitation is provided by argon ion lasers, which are designed to operate in the TEM_{00} mode.

Until recently, the argon ion laser has been a workhorse as the most common excitation source for Raman spectroscopy, but it is now losing ground to solid state lasers. The principle reasons for this are that the latter are much more efficient and consequently do not in general have three phase power and water-cooling requirements. Nevertheless, argon ion lasers still have a niche when high excitation powers on the order of watts are required in conjunction with a good beam quality ($M^2 < 1.1$), for example, for Raman spectroscopy of gaseous samples. Another advantage of argon ion lasers over solid state lasers is their multiline capability.

Krypton Ion Laser

The krypton ion laser has useful discrete emission lines in the near ultraviolet, blue, yellow, red, and near infrared regions of the electromagnetic spectrum; the strongest lines of a Coherent Inc. Innova 400 krypton ion laser are listed in Table 2.

The argon ion and krypton ion lasers are close relatives, thus the large frame krypton ion laser has similar power and water-cooling requirements to those mentioned above for the argon ion laser. Also, like the argon ion laser, air-cooled models with lower power output are available. The characteristics of the two lasers are also similar; for example, the linewidths of the krypton ion transitions at 530.9, 568.2, and 647.1 nm are about 4.0 GHz, the laser tube has similar dimensions (0.1–2.0 m in length) and the laser can be operated in either TEM_{00} or multimode.

The krypton ion laser is even less efficient than the argon ion laser, consequently lower-power outputs of

Table 2 Continuous wave krypton ion laser wavelengths and output powers for the Coherent Inc. Innova 400 krypton ion laser system

Wavelength (nm)	*Power (mW)*
206.5	4
234	8
337.5–356.4	2000
406.7	900
413.1	1800
415.4	280
468.0	500
476.2	400
482.5	400
520.8	700
530.9	1500
568.2	1100
647.1	3500
676.4	900
720.8	45
752.5	1200
793.1–799.3	300

The 206.5 and 234 nm lines are frequency doubled.

up to about 20 W can be achieved when operated in multiline mode.

Mixed argon and krypton ion laser tubes are also commonly used that provide laser lines originating from both argon ion and krypton ion transitions. As with the individual argon ion and krypton ion lasers, sharp plasma lines, due to spontaneous emission from the rare gas ions, are observed in the Raman spectrum unless they are filtered out. If interference filters are used for this, each laser line requires its own filter that is tailored to the specific emission wavelength.

HeCd Laser

Laser lines at 325 and 442 nm, both capable of providing milliwatts of output power, can be obtained from the helium-cadmium laser. These emission lines result from electronic transitions in free cadmium atoms.

It is obviously advantageous to use blue, rather than longer wavelength, excitation (e.g., provided by the 442 nm line of the HeCd laser) for off-resonance Raman spectroscopy, due to the ν^4 dependence of the Raman light scattering efficiency, provided that the efficiencies of the illumination/collection optics and Raman spectrometer throughput are optimized in the blue region of the spectrum. Unfortunately, far more samples fluoresce when excited with blue light than with red or near infrared radiation, which explains why red or near infrared lasers (e.g., HeNe, semiconductor lasers) are more commonly used for general Raman applications.

Near Infrared Lasers

Although the traditional laser systems for Raman spectroscopy have been the argon ion, krypton ion, and helium-neon lasers for discrete excitation wavelengths, the diode laser has gained popularity over recent years.

The principal advantage of near infrared semiconductor lasers for Raman microscopy is that they generally excite less fluorescence in the Raman spectrum than visible lasers due to their longer wavelength. Commonly available wavelengths are 670, 785, 830, and 852 nm and, of these, the first two can be used in conjunction with silicon-based CCD detectors to give Stokes Raman shifts over the whole range of fundamental vibrations, up to 4000 cm^{-1}. However, for excitation wavelengths of 830 and 852 nm, only Stokes Raman bands in the fingerprint region can be detected with a silicon-based CCD detector because higher wavenumber Raman shifts approach the bandgap of the silicon semiconductor ($\lambda >$ ca. 1050 nm).

The disadvantages of diode lasers are that they cannot supply high power of narrow linewidth in single-mode and they are susceptible to mode hopping which gives rise to a shift in the excitation wavelength. This latter drawback is particularly disadvantageous for Raman spectroscopy because it results in a shift in the wavenumber positions of the Raman bands. When good beam quality is not required, broad stripe, high power laser diodes can be used; these can have output powers that are greater than 1 W but their emission linewidths are equal to ca. 2 nm, which is far too wide for Raman spectroscopic applications. These laser diodes find applications as pumps of solid state lasers, for example, Nd:YAG, Nd:YVO_4 lasers, however. Additionally, amplified stimulated emission (ASE) gives an unwanted background signal that can be very broad (ca. 20–30 nm) and 0.1–1% of the intensity of the laser line. This necessitates the use of bandpass filters in order to reduce this unwanted background.

Although laser diodes having an output of less than 200 mW can operate in TEM_{00} and in single longitudinal modes, mode hopping can occur due to optical feedback or fluctuations in environmental factors and this causes severe broadening of the linewidth. The sensitivity to optical feedback can be greatly reduced, hence the laser linewidth can be narrowed appreciably, by confining the frequency of the photons either in an internal cavity containing a small diffraction grating or in an external cavity. The former types of laser are sometimes called ‘distributed feedback’ (DFB) lasers because the feedback is distributed over the length of the grating, rather than occurring all at once at a mirror. The wavelength that is fed back is determined by the period of the grating. Usually, a DFB laser has a grating fabricated into the entire length of the laser. A variation referred to as a distributed Bragg reflector (DBR) laser has a distinct grating fabricated into the substrate on each side of the active area. The external cavity semiconductor laser (ECSL) is fabricated by placing the laser diode in a separate resonator like a conventional gas or solid-state laser. The DBR and ECSL lasers are now discussed.

Distributed Bragg Reflector Lasers

The DBR laser consists of a grating on each side of the active region (Figure 5); these gratings act as mirrors having a reflectivity that is optimized at one particular wavelength, in addition to narrowing the laser linewidth. At present, DBR lasers are only commercially available having an excitation wavelength of 852 nm.

The emission linewidth is less than 4 MHz, which is suitable for the vast majority of Raman spectroscopic applications and the laser operates in single TEM_{00} mode. The disadvantages of DBR lasers are that the maximum output power is restricted to around 150 mW, so an optical isolator is usually necessary in order to prevent external facet damage caused by external optical feedback, and only an excitation wavelength of 852 nm is currently available.

External-Cavity Semiconductor Lasers (ECSL)

ECSLs provide higher output power (up to ca. 1 W) and a wider range of excitation wavelengths (630 nm to around 850 nm), as well as being less expensive than DBR lasers. They use the semiconductor chip only as the gain medium and employ an external grating, both as the frequency selector and the reflective mirror. Specific excitation wavelengths are becoming widely adopted in Raman microscopy employing single grating spectrograph in conjunction with CCD detection, such as 670, 785, 830, and 852 nm. The ECSLs have emission linewidths as low as a few MHz, but in general they span the range 2 MHz–30 GHz, and can operate in a nearly diffraction-limited transverse mode.



Figure 5 Diagram of the cavity of the DBR laser (adapted from Pan M-W, Benner RE and Smith LM (2002) Continuous lasers for Raman spectrometry. In: Chalmers JM and Griffiths PR (eds) *Handbook of Vibrational Spectroscopy*, 1. Chichester, UK: Wiley).

Three different cavity designs employing a diffraction grating have been discussed in the literature: Littrow type-I, Littrow type-II, and Littman configurations. In the Littrow type-I design, the laser diode light is incident on the grating at an angle of incidence equal to θ_{Littrow} (Figure 6a). The diffracted light in first order is re-directed back to the laser diode to provide feedback and the output is the zeroth order (i.e., specularly reflected) light. A disadvantage of this design is that the bandwidth of the grating is relatively large because a single pass geometry is used. In the Littrow type-II design, light from the rear facet of the laser diode is collimated by a lens and directed on to a grating at an angle of incidence equal to θ_{Littrow} (Figure 6b). The diffracted light in first order is re-directed back to the laser diode, in a similar fashion to the Littrow type-I design, in order to provide optical feedback, and the output is the laser light emitted from the front facet. Disadvantages of the Littrow type-II design are the requirement for



Figure 6 Diagrams of the cavities of (a) Littrow type-I, (b) Littrow type-II, and (c) Littman external cavity diode lasers (adapted from Pan M-W, Benner RE and Smith LM (2002) Continuous lasers for Raman spectrometry. In: Chalmers JM and Griffiths PR (eds) *Handbook of Vibrational Spectroscopy*, 1. Chichester, UK: Wiley).

custom fabrication of antireflection coatings on both facets and the sensitivity to external optical feedback. In the Littman design, the laser diode light is collimated by a lens and directed on to a grating at a grazing angle of incidence. The diffracted light is reflected by a mirror and diffracted back to the laser diode by the grating in order to provide optical feedback (Figure 6c). An advantage of this design is that the grating bandwidth is less than half that of the Littrow designs due to the double pass geometry, but a disadvantage is that the external cavity length is longer, resulting in a narrower spacing of the cavity modes. Another advantage of this design is that the tuning is accomplished by rotating the mirror instead of the grating, thus the alignment of the output beam is not altered when tuning. For Littrow type I and II and Littman ECSL designs, filtering of the ASE is required, as it can have an intensity of ca. 0.1 to 1% of the intensity of the laser line. Thus, these designs necessitate the incorporation of a bandpass filter (having a rejection of better than 10^{-4} at the ASE).

Nd:YAG Laser

Under normal conditions, the Nd:YAG laser oscillates on a transition in the near infrared at 1064 nm, and this is the excitation line that is used in most commercial Fourier Transform Raman spectrometers. The gain medium is a crystal of yttrium aluminium garnet ($Y_3Al_5O_{12}$, YAG) doped with ca. 1.0 mol% Nd^{3+} cations that substitute Y^{3+} ions in the cubic YAG lattice.

The Nd:YAG laser is a four-level system (Figure 7), which has high gain and low threshold due to the narrow fluorescent linewidth of the laser transition. Absorption bands of the Nd^{3+}ions around 808 nm conveniently match the energy of commercially available high-power multimode diode lasers that serve as the pump. The Nd^{3+} ions decay nonradiatively to the upper laser level, the $^4F_{3/2}$ state, thereby creating a population inversion. This is because the lower laser level, the $^4I_{11/2}$ state, has no appreciable thermal population at room temperature, since it is $>2000\,cm^{-1}$ above the $^4I_{9/2}$ ground state, and the $^4F_{3/2}$ excited state has a relatively long lifetime of 230 μs.



Figure 7 Energy levels of the Nd:YAG laser.

The high thermal conductivity of Nd:YAG enables the laser to operate at high power in either continuous wave (CW) or *Q*-switched modes, and the diode pumped solid state (DPSS) variety of the cw Nd:YAG laser can currently achieve an output power in excess of 20 W on the 1064 nm line. The laser can be designed to operate in the fundamental TEM_{00} mode and the full width at half maximum (FWHM) linewidth of the spontaneous emission of the 1064 nm laser transition is 120 GHz (ca. 0.45 nm). Advantages of the diode pumped Nd:YAG laser are that it is air-cooled and can be operated at 240 V single phase. Also, being all solid state and having a small footprint, it is robust and portable. The lifetime of the laser is dependent on the laser diodes used for pumping, but some Nd:YAG laser designs enable these to be replaced in the field.

The frequency-doubled Nd:YAG laser emitting green light, having a wavelength of 532 nm, is also commonly used nowadays for dispersive Raman spectroscopy, and an output power of 10 W on the 532 nm laser line is provided by commercially available frequency-doubled diode-pumped Nd:YAG lasers.

It is worth mentioning that Nd:YAG lasers have also been fabricated that emit either at 946 or 1330 nm, by suppressing the strong emission at 1064 nm and optimising the optics for the desired wavelength.

Nd:YVO$_4$ and Nd:YLF Lasers

An intracavity, frequency-doubled DPSS Nd:YVO_4 laser has recently become commercially available, and it has some advantages over the Nd:YAG laser including a larger stimulated emission cross-section and a higher absorption coefficient (along the extraordinary direction of the birefringent crystal). It has the same emission wavelength as the frequency-doubled Nd:YAG laser, i.e., 532 nm, and Nd:YVO_4 is the material of choice for cw end-pumped lasers having around 5 W output power. This is because the diode laser pump beam is tightly focused in the end-pumped system, but a small waist diameter cannot be retained over a distance of more than a few millimeters, consequently a high absorption coefficient and gain are very beneficial.

The gain medium of the Nd:YLF laser consists of a crystal of yttrium lithium fluoride (YLF) that is doped with Nd^{3+} ions on the Y^{3+} cation sites. Unlike the Nd:YAG and $Nd:YVO_4$ lasers, the emission does not occur at 1064 nm; instead the $^4F_{3/2}$–$^4I_{11/2}$ emission occurs at wavelengths of either 1047 or 1053 nm, depending on the polarization that is selected. The former is due to extraordinary polarized light, whereas the latter is due to ordinary polarization, and either of these emission wavelengths can be selected using an intracavity polarizer. The Nd:YLF laser can offer benefits in *Q*-switched operation when the longer fluorescence lifetime (480 μs) of Nd^{3+} ions in the $^4F_{3/2}$ state enables a higher energy to be stored for the same number of pump laser diodes.

Ti:Sapphire Laser

The Ti:sapphire laser is tunable over the approximate range of 670–1070 nm with the peak of the gain curve at ca. 800 nm. In the gain medium, ca. 0.1% by weight Ti^{3+} is doped into a crystal of sapphire grown by the Czochralski method. The Ti^{3+} ions substitute for Al^{3+} ions in the Al_2O_3 of the sapphire and the laser emission is due to the ^2E–$^2T_2$ transition of the Ti^{3+} cation, which has a $3d^1$ valence electronic configuration (Figure 8). The laser has a large stimulated emission cross-section but the fluorescence lifetime of the upper laser level (^2E state) is quite short (3.2 μs), thus the laser is usually laser (e.g., by argon ion or frequency-doubled Nd:YAG or $Nd:YVO_4$ lasers) rather than flashlamp pumped because a very high pump flux is required.



Figure 8 Energy levels of the Ti:sapphire laser (adapted from Pan M-W, Benner RE and Smith LM (2002) Continuous lasers for Raman Spectrometry. In: Chalmers JM and Griffiths PR (eds) *Handbook of Vibrational Spectroscopy*, 1. Chichester, UK: Wiley).



Figure 9 Absorption and emission spectra of the Ti^{3+} ion in sapphire. Al_2O_3 (adapted from Pan M-W, Benner RE and Smith LM (2002) Continuous lasers for Raman Spectrometry. In: Chalmers JM and Griffiths PR (eds) *Handbook of Vibrational Spectroscopy*, 1. Chichester, UK: Wiley).

The absorption and emission bands are broad and widely separated, due to the vibronic coupling between the Ti^{3+} host and the Al_2O_3 lattice (Figure 9). The lower laser level is any one of the vibronic levels of the $^2T_2$ state. Following the laser transition, the Ti^{3+} ions decay from the upper vibronic levels of the $^2T_2$ state down to the lower vibronic levels. Hence, this is a four-level laser.

The broad spontaneous emission linewidth of the ^2E–$^2T_2$ laser transition is around 100 THz, the ouput power can be as high as 50 W, and the laser can be operated in either TEM_{00} or multimodes.

UV Lasers

UV laser sources offer numerous advantages over visible laser sources for Raman spectroscopy. A major consideration is that many analytes have absorptions in the near UV, making them amenable to resonance Raman spectroscopic studies. The signal enhancement (up to 10^6), that can be achieved in resonance Raman spectra, results in a large increase in detection sensitivity. Furthermore, some vibrational modes, which normally give rise to weak bands in the off resonance Raman spectrum, can show strong enhancement in the UV excited resonance Raman spectrum. A good example of this is the amide II band of peptides and proteins, which is due to a combination of N–H in plane bending and C–N stretching modes of the peptide linkage. This band is normally weak in the Raman spectrum but strong in the infrared spectrum; however, the amide II band can show strong enhancement in the UV excited resonance Raman spectrum and this can be useful for determining secondary structure in proteins. A further benefit of UV excited Raman spectroscopy is that fluorescence can often be avoided as it tends to occur at a lower energy, outside the Stokes Raman spectral window.

It can be advantageous to use cw rather than pulsed excitation for UV resonance Raman spectroscopy, if the analyte has a long excited state lifetime relative to the pulsewidth of the pulsed laser. This is because the concentration of analyte molecules in the ground state is significantly depleted during pulsed excitation, due to Raman saturation giving a lower signal to noise ratio in the Raman spectrum than for the case of cw excitation. It has been found that pulse energy flux densities should be less than 1 mJ/cm^2 and flowing or spinning samples should be used, in order to ensure that nonlinear phenomena and saturation effects do not occur.

For UV Raman microscopy, where the laser beam is focused into a small spot of micrometer dimensions on the sample, it is essential to avoid using pulsed lasers delivering high peak powers. This is because such pulsed lasers can cause dielectric breakdown, and even at lower peak powers they can cause nonlinear effects and Raman saturation phenomena. Consequently, with UV Raman microscopy, one is restricted to the use of cw or quasicontinuous laser excitation.

It is only recently that high thoughput UV Raman microspectrometers have been developed. It has been demonstrated for visible Raman spectroscopy that a significantly higher throughput can be achieved by employing a single stage spectrograph with a notch filter instead of a double or triple monochromator. In the UV region, blocking the Rayleigh scattering is a problem because notch filters are not currently available. However, it has been discovered that this can be overcome by introducing two modifications to the design of the optical layout of a visible Raman microscope. First, two novel dielectric longpass filters were used instead of a notch filter in order to reject the elastically scattered light. Second, an all-reflecting Cassegrain microscope objective was used, instead of a lens, in order to block the specular reflection, and thereby further reduce the Rayleigh scattering background. These design modifications have enabled a single stage spectrograph with a holographic grating to be used to disperse the Stokes Raman radiation in a UV Raman microspectrometer (Figure 10).

In the optical layout of Figure 10 it can be seen that the laser excitation is not focused by the Cassegrain microscope objective because an epi-illumination configuration is not employed. Instead the laser is focused by a separate lens and directed on to the sample with a turning prism located directly underneath the Cassegrain objective. This minimizes loss of laser beam throughput or scattered light throughput to the spectrometer at the expense of spatial resolution, since the laser light is focused by a longer focal length lens than the microscope objective. An additional difference between the optical layouts of the visible and UV Raman microscopes shown in Figures 1 and 10, respectively, is that pinhole spatial filters are not shown in the latter. However, better axial spatial resolution could be achieved if this UV Raman microscope was made confocal by introducing a pinhole and lens.


Eye-piece
CCD camera
Diode array detector
Monochromator
Reflected light illuminator
Dichroic beamsplitter
Dielectric long-pass filter
All-reflecting microscope objective
Turning prism
CW UV laser
Micropositionable sample stage

Figure 10 Diagram of the optical layout of a UV Raman microscope (adapted from Pajcini V, Munro CH, Bormett RW, Witkowski RE and Asher SA (1997) UV Raman microspectroscopy: Spectral and spatial selectivity and simplicity. *Applied Spectroscopy* 51: 81–86).

Frequency-Doubled Argon Ion Laser

The frequency doubled argon ion laser is a popular choice among UV laser sources. The cw UV laser contains a nonlinear optical beta-barium borate (BBO) crystal, which is located within the laser cavity; this crystal frequency doubles the strong Ar$^+$ lines to give five UV lines below 260 nm which are listed in Table 1 for the Coherent Inc. Innova 300 Ar$^+$ ion laser system. Of these UV lines, the 228.9 nm line is almost ideal for resonance Raman enhancement of tyrosine and trpytophan residues in proteins and the 244.0 nm line is well suited for studying tyrosinate groups. The 244.0 nm line has also been used to excite selectively UV resonance Raman spectra from spatially resolved areas of biological samples within the nucleus of a single cell, from DNA in particular, using low laser powers and short acquisition times to keep sample damage to a minimum under the microscope.

Frequency-Doubled Krypton Ion Laser

Like the cw frequency-doubled argon ion laser mentioned above, the cw frequency-doubled krypton ion laser contains a nonlinear optical BBO crystal, which is located within the laser cavity; this crystal frequency doubles the strong Kr^+ lines to give 206.5 and 234 nm UV lines which are listed in Table 2 for the Coherent Inc. Innova 400 Kr^+ ion laser system. The 206.5 nm laser line is useful for exciting resonance Raman spectra within the $\pi-\pi^*$ amide transition of the peptide backbone of proteins, and the enhanced protein amide vibrational bands can be used to determine the protein secondary structure.

HeCd Laser

The 325 nm HeCd excitation line, in the near ultraviolet, can be used for combined micro-Raman/photoluminescence studies of, for example, semiconductors. These lasers are suitable for low-power applications, typically having output powers in the 1–100 mW range, and they can be designed to operate in TEM_{00} single-mode or multimode.

Quasi-CW Mode-Locked Ti:Sapphire Laser

The second harmonic of the mode-locked Ti:sapphire laser (ca. 350–500 nm), third harmonic (ca. 233–333 nm), and fourth harmonic (ca. 200–250 nm), are all available with conventional nonlinear crystals.

Typically, the Ti:sapphire crystal is pumped by a cw argon ion laser, for example, as the excitation source for a UV Raman microscope. This quasicontinuous laser system produces 2–3 ps pulses at a 76 MHz repetition rate and is continuously tunable over the 200–300 nm range. The typical power output is ca. 50 mW at 250 nm, ca. 10 mW at 240 nm, and 1 mW at 230 nm. In future, it is anticipated that a frequency-doubled Nd:YAG laser will be increasingly favored as the pump, creating an all-solid-state laser source.

Conclusions

Laser systems for Raman microscopy have been described in this article. Although the differences in the terms ‘Raman spectroscopy’ and ‘Raman microscopy’ only refer to whether a macro or micro sampling configuration is used, this does have a bearing on the types of laser systems that are employed. This is because the latter imposes a restriction on using low duty pulsed lasers with high pulse peak power, as both spatial and temporal confinement of the laser excitation can lead to dielectric breakdown of the sample, nonlinear phenomena, or Raman saturation. Thus, for this reason, one is limited to cw lasers or quasi-cw lasers for Raman microscopy whereas there is no such restriction for Raman spectroscopy.

The quality of the laser beam, measured by the M^2 value or ‘times diffraction limit’ influences the ultimate spatial resolution that can be achieved in Raman microscopy.

In the visible region, argon ion, krypton ion, and frequency-doubled Nd:YAG lasers have good beam quality and high power, with helium-neon and helium-cadmium lasers also having good beam quality but lower power; this makes these lasers good light sources for visible Raman microscopy.

For FT Raman microscopy using Nd:YAG excitation, there is a lack of fluorescence interference from a wide variety of samples, but sensitivity and spatial resolution are compromised in comparison to visible dispersive Raman microscopy.

Red and near infrared semiconductor lasers operating in TEM_{00} single mode can have good beam quality, approaching that of gas lasers, but they are power limited. Obviously, when good beam quality is not necessary, for example, for optically pumping other laser sources, high-power diode lasers can be used in multimode operation. Solid state red and near infrared laser sources are becoming very popular for routine Raman microscopic analysis due to their compactness, robustness, and economical power consumption.

Another reason for the popularity of the red and near infrared diode laser sources for Raman microscopy is that fluorescence is less of a problem due to the lower energy of the light, compared to conventional green 514.5 nm excitation. Although there is a penalty, due to the dependency of the scattering efficiency on the ν^4 term, present day silicon-based CCD arrays can exhibit excellent detection quantum efficiency of Stokes shifted Raman radiation, across the whole vibrational spectrum, when using standard 670 and 785 nm diode lasers and, at least across the fingerprint region, when using 830 and 852 nm diode lasers.

For ultimate spatial resolution in the Raman microscopic experiment, short wavelength excitation is advantageous because it is fundamentally possible to focus to a smaller diffraction-limited laser spot. In this regard, it would be preferable to use UV Raman microscopy where fluorescence is also not as problematic as it is in the visible region. However, in spite of recent improvements in UV laser sources such as the intracavity frequency-doubled argon and krypton ion cw lasers, there are current instrumental limitations on the throughput efficiency of the UV Raman microscope imposed by the lack of availability of suitable notch filters and low stray light and high throughput optics.

It is anticipated that in the future all-solid-state, quasi-cw, diode pumped, mode-locked Ti:sapphire lasers operating on their third or fourth harmonics will become increasingly popular for providing tunable UV excitation affording good beam quality. It is now also possible to fabricate hollow cathode metal ion deep UV lasers, 10–15 cm in length, 2–4 cm in diameter, weighing 50–100 g and requiring only 2–3 W of electrical power. These lasers have low beam quality (M^2 equal to ca. 18), but they make possible the development of portable UV fluorescence imaging and Raman microprobes for geobiological exploration of terrestrial and extraterrestrial environments.

See also

Fourier Optics. **Imaging:** Infrared Imaging. **Introductory Article:** Early Development of the He-Ne Laser (Title TBC). **Lasers:** Noble Gas Ion Lasers; Semiconductor Lasers. **Nonlinear Optics, Applications:** Raman Lasers. **Scattering:** Raman Scattering.

Further Reading

Andrews DL (1990) *Lasers in Chemistry* (2nd edition). Berlin, Heidelberg: Springer-Verlag.

Asher SA, Bormett RW, Chen XG, *et al.* (1993) UV resonance Raman spectroscopy using a new cw laser source: Convenience and experimental simplicity. *Applied Spectroscopy* 47: 628–633.

Bell SEJ, Bourguignon ESO, O'Grady A, Villaumie J and Dennis AC (2002) Extracting Raman spectra from highly fluorescent samples with "Scissors" (SSRS, Shifted-Subtracted Raman Spectroscopy). *Spectroscopy Europe* 14: 17.

Best SP, Clark RJH and Withnall R (1992) Non-destructive pigment analysis of artefacts by Raman microscopy. *Endeavour* 16: 66.

Boustany NN, Manoharan R, Dasari RR and Feld MS (2000) Ultraviolet resonance Raman spectroscopy of bulk and microscopic human colon tissue. *Applied Spectroscopy* 54: 24–30.

Delhaye M, Barbillat J, Aubard J, Bridoux M and Da Silva E (1996) Instrumentation. In: Turrell G and Corset J (eds) *Raman Microscopy: Developments and Applications*, chap. 3. London: Academic Press.

Delhaye M and Dhamelincourt P (1975) Raman microprobe and microscope with laser excitation. *Journal of Raman Spectroscopy* 3: 33.

Derbyshire A and Withnall R (1999) Pigment analysis of portrait miniatures using Raman microscopy. *Journal of Raman Sprectroscopy* 30: 185.

Gordeyev SA, Nikolaeva GYu, Prokhorov KA, Withnall R, Dunkin IR and Shilton SJ (2001) Super-selective polysulfone hollow fiber membranes for gas separation: assessment of molecular orientation by Raman spectroscopy. *Laser Physics* 11: 82–85.

Hayward CL, Best SP, Clark RJH, Ross NL and Withnall R (1994) Polarised single crystal Raman spectroscopy of sinhalite, $MgAlBO_4$. *Spectrochimica Acta* 50A: 1287–1294.

Hendra P, Jones C and Warnes G (1991) *Fourier Transform Raman Spectroscopy*. London: Ellis Horwood.

Hitz B (2003) Solid state lasers are gunning for argon ion's place. *Photonics Spectra* 54–58.

Holtz JSW, Bormett RW, Chi Z, *et al.* (1996) Applications of a new 206.5 nm continuous wave laser source: UV Raman determination of protein secondary structure and CVD diamond material properties. *Applied Spectroscopy* 50: 1459–1468.

http://www.btools.com

Koechner W and Bass M (2003) *Solid-State Lasers*. New York: Springer-Verlag.

Landsberg G and Mandelstam L (1928) Eine neue Erschienung bei der Lichtzerstreaung in Krystallen. *Naturwiss* 16: 557.

Matousek P, Towrie M, Stanley A and Parker AW (1999) Efficient rejection of fluorescence from Raman spectra using picosecond Kerr gating. *Applied Spectroscopy* 53: 1485.

Nakashima S, Okumura H, Yamamoto T and Shimidzu R (2004) Deep-ultraviolet Raman microspectroscopy: Characterization of wide-gap semiconductors. *Applied Spectroscopy* 58: 224–229.

Pajcini V, Munro CH, Bormett RW, Witkowski RE and Asher SA (1997) UV Raman microspectroscopy: Spectral and spatial selectivity and simplicity. *Applied Spectroscopy* 51: 81–86.

Pallister DM and Morris MD (1993) In: Morris MD (ed.) *Microscopic and Spectroscopic Imaging of the Chemical State*, chap. 1. New York: Marcel Dekker.

Pan M-W, Benner RE and Smith LM (2002) Continuous lasers for Raman spectrometry. In: Chalmers JM and Griffiths PR (eds) *Handbook of Vibrational Spectroscopy,* 1. Chichester, UK: Wiley.

Pan M-W, Benner RE, Johnson CW and Smith LM (2000) Near-IR lasers rejuvenate Raman spectroscopy. *Optoelectronics World* S5–S10.

Raman CV and Krishnan KS (1928) A new type of secondary radiation. *Nature* 121: 501.

Rosasco GJ (1980) Raman microprobe spectroscopy. In: Clark RJH and Hester RE (eds) *Advances in Infrared and Raman Spectroscopy*, vol. 7. Chichester: Wiley.

Rosasco J, Etz ES and Cassatt WA (1975) The analysis of discrete fine particles by Raman spectroscopy. *Applied Spectroscopy* 29: 396.

Schawlow AL and Townes CH (1958) Infrared and optical masers. *Physics Review* 112: 1940.

Smekal A (1923) Sur Quantentheorie der Dispersion. *Naturwiss* 11: 873.

Storrie-Lombardi MC, Hug WF, McDonald GD, Tsapin AI and Nealson KH (2001) Hollow cathode ion lasers for deep ultraviolet Raman spectroscopy and fluorescence imaging. *Review of Scientific Instruments* 72: 4452–4459.

Turrell G, Delhaye M and Dhamelincourt P (1996) Characteristics of Raman microscopy. In: Turrell G and Corset J (eds) *Raman Microscopy: Development and Applications*, 2. London: Academic Press.

Young M (1977) *Optics and Laser: An Engineering Approach*. Berlin, Heidelberg: Springer-Verlag.

Yu Y-M, Nam S, Byungsung O, *et al.* (2002) Resonant Raman scattering in ZnS epilayers. *Materials Chemistry and Physics* 78: 149–153.

Second-Harmonic Spectroscopy

J I Dadap and T F Heinz, Columbia University, New York, NY, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The demonstration of second-harmonic generation (SHG), one of the early experiments with pulsed lasers, is considered to have marked the birth of the field of nonlinear optics. The importance of second-harmonic generation, and the related phenomena of sum- and difference-frequency generation, as methods for producing new frequencies of coherent radiation was recognized immediately and has in no way diminished over the years. Associated with these applications came an interest in the fundamental nature of the second-order nonlinear response, and some spectroscopic studies were undertaken with this motivation. These investigations were of rather limited scope and were not developed as a general probe of materials. In contrast, the third-order nonlinear optical interactions have given rise to a panoply of significant spectroscopic measurement techniques, including, to name a few, coherent Raman spectroscopy, pump-probe and other four-wave mixing measurements, two-photon absorption and hole burning measurements, photon echoes, and Doppler-free spectroscopy.

A central factor in the lack of spectroscopic applications of the second-order nonlinear response lies in a fundamental symmetry constraint. Unlike the third-order nonlinearity, which is present in all materials, only materials lacking a center of inversion give rise to an (electric-dipole) allowed second-order nonlinear response. As we demonstrate in this article, however, it is this property that makes SHG, as well as the sum-frequency generation process discussed elsewhere in this encyclopedia, such a remarkable probe of surfaces and interfaces. For centrosymmetric materials, the second-order nonlinear response is strong only at interfaces, where only a monolayer or so of material contributes to the response. This yields a purely optical probe (with incident and emitted photons) that gives an inherent surface sensitivity comparable to the best electron spectroscopies, such as electron diffraction, Auger-electron spectroscopy, photoemission spectroscopy, and scanning tunneling microscopy, the workhorses of surface science. Neither linear nor third-order nonlinear optical measurements provide this inherent interface sensitivity. The possibility of probing interfaces by purely optical means permits one to take advantage of several important features of optical radiation. Perhaps most noteworthy is the possibility of probing buried interfaces of every sort, from solid/solid to liquid/liquid, as well as the more conventional cases of solid/vapor, liquid/vapor, and liquid/solid. In addition, laser-based techniques offer unequalled capabilities for spectral or temporal resolution.

In this article, we present a brief overview of SH spectroscopy for the study of surfaces and interfaces. The article is divided into two principal sections: an introductory section that presents some of the fundamentals of SHG and the behavior at interfaces; and a discussion of the different types of information that the method can yield, as illustrated by some representative examples. A brief section on the experimental technique links these two parts.

Fundamentals of Surface SHG

Basic Notions

Within the domain of classical optics, the response of a material to electromagnetic radiation is described by an induced polarization **P** that varies linearly with the electric field strength, **E**. This situation reflects the fact that the strength of electric fields for light encountered under conventional conditions is minute compared to that of the electric fields binding atoms and solids together. The electric field binding an atom may be estimated as $E_a \sim 1\ \text{V/Å} = 10^{10}$ V/m. To reproduce this field strength by an electromagnetic wave requires an irradiance of $I_a \sim 10^{17}\ \text{W/m}^2$, so the validity of this linear approximation in classical optics is clear. The advent of the laser, with its capability for producing light beams with very high optical power and irradiance, has permitted us to probe and exploit the nonlinear response of materials, giving rise to the field of nonlinear optics.

The next-order material response beyond the linear approximation consists of an induced nonlinear source polarization $\mathbf{P}^{(2)} = \varepsilon_0 \boldsymbol{\chi}^{(2)} : \mathbf{EE}$ that depends quadratically on the driving electric field $\mathbf{E}$, described by a second-order nonlinear susceptibility $\boldsymbol{\chi}^{(2)}$. For excitation by a single laser at a frequency ω, this response gives rise to SHG at a frequency of 2ω, as well as optical rectification with a dc induced-polarization. For beams at two distinct frequencies of ω_1 and ω_2, the processes of sum- or difference-frequency generation (SFG or DFG) become operative with the production of the new frequencies of $|\omega_1 \pm \omega_2|$. For a relationship of the given form, which assumes only a spatially local quadratic dependence of the polarization on the driving electric field, one can show that $\boldsymbol{\chi}^{(2)}$ must vanish within any centrosymmetric medium. This is a direct consequence of the fact that $\boldsymbol{\chi}^{(2)}$ as a quantity describing a centrosymmetric medium should not change under an inversion operation, while the quantities $\mathbf{P}^{(2)}$ and $\mathbf{E}$ as polar vectors will change sign. The interface specificity of the SHG technique for centrosymmetric media follows from this general observation: only at interfaces is the bulk symmetry broken and the SHG process allowed.

Anharmonic Oscillator Model

Before we embark on our discussion of surface SHG, we first briefly consider a simple classical model of SHG based on an anharmonic oscillator. Although this is not a realistic treatment of the response of materials, it helps to illustrate the characteristic features of the surface SHG process and its spectroscopic attributes. In the anharmonic oscillator model, the medium is treated as a collection of electrons bound to fixed ion cores. While the usual Lorentz model only includes the effect of a linear restoring force, to describe second-order response, we generalize this description to include a leading-order anharmonic restoring force. For simplicity, we consider motion of the anharmonic oscillator in one spatial dimension, in which case the classical equation of motion for the displacement, x, of the electron can then be written as

$$\frac{\mathrm{d}^2x}{\mathrm{d}t^2} + 2\gamma\frac{\mathrm{d}x}{\mathrm{d}t} + \omega_0^2 x - bx^2 = -\frac{e}{m}E(t) \qquad [1]$$

Here $-e$ and m denote, respectively, the electron charge and mass, and $E(t)$ is the optical driving field. The (angular) frequency ω_0 defines the resonance of the harmonic component of the response, and γ represents a phenomenological damping rate for the oscillator. The nonlinear restoring force corresponds to the term containing the parameter b, a material-dependent constant. We are interested in the solution of this equation for a monochromatic driving field at frequency ω with amplitude $E(\omega)$ which we write as

$$E(t) = E(\omega)\exp(-\mathrm{i}\omega t) + \mathrm{c.c.} \qquad [2]$$

An exact solution to eqn [1] in the presence of this electric field is not possible. Let us, however, consider a regime in which we do not excite the oscillator too strongly, and the effect of the anharmonic term remains relatively small compared to the harmonic one. In this case, we may solve the problem perturbatively in powers of the driving field. We find a linear response at the fundamental frequency and a nonlinear response at the SH frequency, which we can write in terms of the corresponding induced dipole moments $p = -ex$:

$$p(t) = p^{(1)}(\omega)\exp(-\mathrm{i}\omega t) + p^{(2)}(2\omega)\exp(-\mathrm{i}2\omega t) + \mathrm{c.c.} \qquad [3]$$

We can then write the amplitudes for the harmonically varying dipole moments as

$$p^{(1)}(\omega) = \alpha^{(1)}(\omega)E(\omega) \qquad [4]$$

$$p^{(2)}(2\omega) = \alpha^{(2)}(2\omega = \omega + \omega)E(\omega)E(\omega) \qquad [5]$$

where $\alpha^{(1)}$, the linear polarizability, and $\alpha^{(2)}$, the second-order polarizability (or first hyperpolarizability) for SHG are given, respectively, by

$$\alpha^{(1)}(\omega) = \frac{e^2}{m}\frac{1}{D(\omega)} \qquad [6]$$

$$\alpha^{(2)}(2\omega = \omega + \omega) = \frac{(e^3/m^2)b}{D(2\omega)D^2(\omega)} \qquad [7]$$

Here we have introduced the resonant response at the fundamental frequency by $D(\omega) \equiv \omega_0^2 - \omega^2 - 2\mathrm{i}\gamma\omega$, with a corresponding relation for the response $D(2\omega)$ at the SH frequency. A similar derivation can, of course, be applied to obtain the corresponding material response for the SFG or DFG processes.

The spectral dependence of the polarizabilities $\alpha^{(1)}$ and $\alpha^{(2)}$ is illustrated in Figure 1 for the anharmonic oscillator model with a resonance frequency of ω_0. In the linear case, one sees the expected behavior of the loss, associated with the $\mathrm{Im}[\alpha^{(1)}]$, and dispersion associated with $\mathrm{Re}[\alpha^{(1)}]$. A single resonance in the linear response is seen for the driving frequency ω near the oscillator frequency ω_0. For the case of SHG, on the other hand, we observe both resonances when the fundamental frequency $\omega \approx \omega_0$ and when the SH



Figure 1 Real and imaginary components of the linear polarizability $\alpha^{(1)}(\omega)$ (top panel) and the second-order nonlinear polarizability $\alpha^{(2)}(2\omega = \omega + \omega)$ (bottom panel) plotted versus frequency according for the anharmonic oscillator model. For the SH response, the resonance features at $\omega = \omega_0$ and $\omega = \omega_0/2$ correspond, respectively, to single-photon and two-photon resonances.

frequency $2\omega \approx \omega_0$. In quantum mechanical language introduced below, these peaks can be considered as arising, respectively, from matching of the fundamental and second-harmonic photon energies with the transition energy in the material.

In SHG spectroscopy, one normally measures the SH power as a function of the laser frequency. The SH field will scale with the nonlinear material response, i.e., with $\alpha^{(2)}(2\omega = \omega + \omega)$, so that the SH power will be proportional to $|\alpha^{(2)}(2\omega = \omega + \omega)|^2$. Figure 2 shows the corresponding spectra in the vicinity of the second-harmonic resonance. An important aspect of this type of spectroscopy, which is also present in other nonlinear spectroscopies, such as coherent Raman measurements, is the role that may be played by a nonresonant background. This may arise either from the off-resonant response of the system under study or from a coherent background from another material. In either case, the effect can be described by adding a spectral flat background response to the nonlinearity. Now when we detect the optical power, we then measure a quantity proportional to $|\alpha^2(2\omega = \omega + \omega) + k|^2$, where k represents the nonresonant background. The presence of k obviously elevates the baseline response near a resonance. In addition, however, depending on the relative phase of k, this extra term can introduce significant changes in the observed lineshapes. Figure 2 illustrates this effect, which must always be borne in mind in the interpretation of experimental spectra.



Figure 2 SH spectra $I(2\omega)$ versus pump laser frequency ω corresponding to Figure 1 in the vicinity of the two-photon resonance, with and without the presence of a nonresonant (frequency-independent) background: $I(2\omega) \sim |\alpha^{(2)}(2\omega = \omega + \omega) + k|^2$, where k represents a constant background and parametrized through $k = m|\alpha^{(2)}(2\omega = \omega_0)|$ and m is constant factor. Top panel: $m = 0$, 0.5, 1 (bottom to top curves). Bottom panel: $m = 0$, $0.5i$, i (bottom to top curves). In the top panel, the upper two lineshapes were displaced vertically to distinguish the three curves.

For the purposes of studies of surfaces and interfaces, the key property of second-order nonlinear processes is the fact that they exhibit, for centrosymmetric bulk media, an inherent interface specificity. This feature can be readily understood in the context of the nonlinear oscillator model in which the SH polarization scales with the material parameter b. Since this term is associated with a potential that varies as x^3, it is clear that the value of the b parameter can be taken as a measure of the material's departure from inversion symmetry. At the interface, such a term can be present, reflecting the inherent asymmetry at a boundary, while it must necessarily be absent in the bulk of a centrosymmetric material.

Quantum-Mechanical Description of SHG

A correct description of SHG naturally requires a quantum mechanical treatment of the material response to the optical field. For our present purposes, we consider a localized entity with a nonlinear response, such as a non-centrosymmetric molecule at a surface. We consider below how these individual units can be added together to yield the surface nonlinear response of the material. Within this picture, we write the induced nonlinear dipole moment $\mathbf{p}^{(2)}$ of each molecule in terms of the driving electric field $\mathbf{E}$ as

$$\mathbf{p}^{(2)}(2\omega) = \boldsymbol{\alpha}^{(2)}(2\omega = \omega + \omega) : \mathbf{E}(\omega)\mathbf{E}(\omega) \qquad [8]$$

This relation is simply the generalization of eqn [5] to include a full 3-dimensional description, where $\mathbf{p}^{(2)}$ and $\mathbf{E}$ are vectors and the second-order nonlinear polarizability $\boldsymbol{\alpha}^{(2)}$ is a third-rank tensor. The quantum mechanical description enters in how we relate the response function $\boldsymbol{\alpha}^{(2)}(2\omega = \omega + \omega)$ to the underlying properties of the material.

We can obtain an expression for the second-order nonlinear polarizability by application of second-order perturbation theory with the light–matter interaction treated as the perturbation. Within the electric-dipole approximation, the interaction Hamiltonian can be taken as $H_{\text{int}} = -\boldsymbol{\mu}\cdot\mathbf{E}(t)$, where $\boldsymbol{\mu} = -e\mathbf{r}$ denotes the electric-dipole operator and $\mathbf{E}(t)$ the electric field of the driving laser beam. Using the standard density-matrix formalism for second-order perturbation theory, one calculates for the Cartesian components $\alpha^{(2)}_{ijk}$ of the tensor $\boldsymbol{\alpha}^{(2)}$ as

$$\alpha^{(2)}_{ijk}(2\omega = \omega + \omega) = -\frac{1}{\hbar^2}\sum_{g,n,n'}\left[\frac{(\mu_i)_{gn}(\mu_j)_{nn'}(\mu_k)_{n'g}}{(2\omega - \omega_{ng} + \mathrm{i}\Gamma_{ng})(\omega - \omega_{n'g} + \mathrm{i}\Gamma_{n'g})} + \cdots\right]\rho_g^{(0)} \qquad [9]$$

In this expression, the letters g, n', and n represent energy eigenstates $|g\rangle$, $|n'\rangle$, and $|n\rangle$ of the system, with $\rho_g^{(0)}$ corresponding to the thermal population for differing available ground states g. As illustrated in Figure 3, the SHG process can be regarded as involving a series of three transitions: two transitions associated with the absorption of two pump photons, each of energy $\hbar\omega$, and a transition associated with emission of a second-harmonic photon of energy $2\hbar\omega$. These transitions occur through the electric-dipole operator $\boldsymbol{\mu}$ and are characterized by the matrix elements $(\mu_i)_{gn}$. In eqn [9], the energy denominators involve the energy differences $\hbar\omega_{ng} \equiv E_n - E_g$ and widths $\hbar\Gamma_{ng}$ for transitions between eigenstates $|n\rangle$ and $|g\rangle$, and similarly for other combinations of states. In addition to the term indicated explicitly in eqn [9], there are seven additional terms with different Cartesian coordinates in the matrix elements and/or frequency denominators.



Figure 3 Quantum mechanical description of SHG process for the situations of (a) nonresonant, (b) single-photon resonant, and (c) two-photon resonant interactions. SHG occurs through transition from the initial state electronic state $|g\rangle$ and a first intermediate state $|n'\rangle$, then to a second intermediate state $|n\rangle$, followed by a return to the initial state. The process is just a parametric conversion of two photons at frequency ω into one photon at frequency 2ω.

The frequency denominators in the eight terms of eqn [9] introduce a resonant enhancement in the nonlinearity when either the fundamental frequency ω or the SH frequency 2ω coincides with a transition from a ground state $|g\rangle$ to one of the intermediate states $|n'\rangle$ or $|n\rangle$. Figure 3a shows the situation for a nonresonant nonlinear response, while Figures 3b,c illustrate, respectively, single- and two-photon resonances. The numerator in the perturbation theory expression consists of products of the three dipole matrix elements of the form $(\mu_i)_{gn}(\mu_j)_{nn'}(\mu_k)_{n'g}$. These terms reflect the structure and symmetry of the material that is built into the third-rank tensor $\alpha^{(2)}_{ijk}(2\omega = \omega + \omega)$.

The Surface Nonlinear Response

As a model of the surface nonlinearity, let us consider a monolayer of oriented molecules. The surface nonlinear response accessible to a macroscopic measurement is given, under the neglect of local-field effects, simply by summing the response of the individual molecules. The resulting surface nonlinear susceptibility tensor $\chi^{(2)}_{\mathrm{s},ijk}$ connecting the induced nonlinear sheet polarization to the driving electric field can then be expressed as

$$\chi^{(2)}_{\mathrm{s},ijk} = \frac{N_{\mathrm{s}}}{\varepsilon_0}\langle T_{i\lambda}T_{j\mu}T_{k\nu}\rangle\alpha^{(2)}_{\lambda\mu\nu} \qquad [10]$$

Here N_s denotes the adsorbate surface density, $\alpha^{(2)}_{\lambda\mu\nu}$ the nonlinear polarizability of the molecule expressed in its own coordinate system, $T_{i\lambda}$ the transformation tensor from the molecule's coordinate system to the laboratory frame, $\langle\,\rangle$ an ensemble average over the orientation of the different molecules in the monolayer, and $\varepsilon_0 = 8.85 \times 10^{-12}$ F/m the permittivity of free space. This expression for the surface nonlinear susceptibility has been successful in describing properties of adsorbed molecules, including their coverage, orientation, and spectroscopic features.

For the surfaces of materials such as semiconductors or metals with delocalized electronic states, a somewhat different formulation of the nonlinear response is appropriate. A modified version of eqn [9] can be obtained using the relevant band states. The underlying concepts involved in the surface nonlinear response are, however, similar to those presented for the molecular case.

Regardless of the details of the model describing the surface nonlinear susceptibility, its tensor properties must reflect the symmetry of the interface. In that respect $\chi^{(2)}_{s,ijk}$ is quite analogous to the bulk nonlinear response, $\chi^{(2)}_{ijk}$, in a non-centrosymmetric medium. In the absence of any symmetry constraints, $\boldsymbol{\chi}^{(2)}_s$ will exhibit $3 \times 3 \times 3 = 27$ independent elements for SFG and DFG. For SHG, the order of the last two indices has no significance, and the number of independent elements is reduced to 18. If the surface exhibits a certain in-plane symmetry, then the form of $\boldsymbol{\chi}^{(2)}_s$ will be simplified correspondingly. For the common situation of an isotropic surface, for example, SHG possesses three allowed elements of $\boldsymbol{\chi}^{(2)}_s$ and may be denoted as $\chi^{(2)}_{s,\perp\perp\perp}$, $\chi^{(2)}_{s,\perp\|\|}$, $\chi^{(2)}_{s,\|\perp\|} = \chi^{(2)}_{s,\|\|\perp}$, where $\perp$ corresponds to the direction of the surface normal and $\|$ to an in-plane direction. The nonvanishing elements of $\boldsymbol{\chi}^{(2)}_s$ for other commonly encountered surface symmetries are summarized in several textbooks and reviews listed below.

Radiation Properties for Surface SHG

In order to probe and extract information from interfaces through surface SHG, it is necessary to understand how radiation interacts with the relevant media and gives rise to the experimentally observable signals. Here we present the principal results for the usual case of a spatially homogeneous planar interface. Nonplanar and inhomogeneous geometries, which are also of considerable interest, will be considered briefly under the heading of applications of the SHG technique below.



Figure 4 Schematic representation of SHG at the interface between two centrosymmetric media. The pump field $\mathbf{E}(\omega)$ at frequency ω with corresponding wavevector $\mathbf{k}_\omega$ is incident on the interface from medium 1. The SH field $\mathbf{E}(2\omega)$ at frequency 2ω is emitted in directions described by the wavevectors $\mathbf{k}^R_{2\omega}$ (reflected in medium 1) and $\mathbf{k}^T_{2\omega}$ (transmitted in medium 2). The linear dielectric constants of media 1, 2, and the interface are denoted, respectively, by ε_1, ε_2, and ε'. The nonlinear response of the interface ($z = 0$) is given by the surface nonlinear susceptibility tensor $\boldsymbol{\chi}^{(2)}_s$.

The SHG process is coherent in nature. Thus, for the planar geometry, a pump beam impinging on the interface will give rise to a well-collimated SH radiation emerging in distinct reflected and transmitted directions. To describe this situation in a more detailed fashion and provide formulas for the radiation efficiency, we introduce a general description of SHG by a planar interface excited by a plane wave, as shown in Figure 4. The nonlinear response of the interface described by the surface nonlinear susceptibility tensor $\boldsymbol{\chi}^{(2)}_s$ is incorporated through a nonlinear source polarization $\mathbf{P}^{(2)}$ of

$$\begin{aligned}\mathbf{P}^{(2)}(2\omega) &= \mathbf{P}^{(2)}_s(2\omega)\delta(z)\\ &= \varepsilon_0\boldsymbol{\chi}^{(2)}_s(2\omega = \omega + \omega) : \mathbf{E}(\omega)\mathbf{E}(\omega)\delta(z)\end{aligned} \qquad [11]$$

localized at the interface ($z = 0$). In addition to the strong nonlinear response at the interface, one must also generally consider the nonlocal nonlinear response of the bulk media. This response is much weaker than the symmetry-allowed interfacial response, but is permitted even in centrosymmetric materials. Since it is present in a much larger volume, however, its cumulative effect, while generally weaker than the surface response, may be of comparable magnitude. For simplicity, however, we neglect this constant background response in our discussion in this article, but a complete discussion can be found in the referenced works. The overall SH response is naturally also influenced by the linear optical properties of the surrounding media. The two bulk media and the interfacial region are characterized, respectively, by frequency-dependent dielectric functions ε_1, ε_2, and ε', as shown in Figure 4. Again for simplicity, and in accordance with most applications, we take the linear response to be isotropic.

Figure 4 shows the incoming pump radiation and the reflected and transmitted SH beams. The directions of these beams are determined by conservation of the component of the momentum parallel to the interface in the SHG process, i.e., $2\mathbf{k}_{\omega,\parallel} = \mathbf{k}^{\mathrm{R}}_{2\omega,\parallel} = \mathbf{k}^{\mathrm{T}}_{2\omega,\parallel}$. Thus the reflected and transmitted beams both remain in the plane of incidence, with directions governed by the so-called nonlinear Snell's law. For bulk media without dispersion between the frequencies of ω and 2ω, the reflected and transmitted beams simply maintain the same angle of incidence as the pump beam. However, for dispersive bulk media, the directions of the beams are, however, altered, as can be understood immediately from the expression $2k_\omega/k_{2\omega} = n_\omega/n_{2\omega}$, where n denotes the refractive index of the medium. The surface SHG process does, nonetheless, differ in an important respect. In contrast to the situation for bulk media, the interfacial region is of negligible thickness, so phase shifts can obviously be disregarded. The issue of phase matching, which is of great significance for SHG from bulk media, consequently does not enter into the surface SHG problem.

By application of the Maxwell equations with the indicated nonlinear source polarization, one can derive explicit expressions for the SH radiation in terms of the linear and nonlinear response of the materials and the excitation conditions. For the case of the nonlinear reflection, the irradiance for the SH radiation can be written as

$$I(2\omega) = \frac{\omega^2 \sec^2\theta |\mathbf{e}'(2\omega)\cdot\boldsymbol{\chi}_s^{(2)} : \mathbf{e}'(\omega)\mathbf{e}'(\omega)|^2 [I(\omega)]^2}{2\varepsilon_0 c^3 [\varepsilon_1(2\omega)]^{1/2} \varepsilon_1(\omega)} \qquad [12]$$

where $I(\omega)$ denotes the irradiance of the pump beam at the fundamental frequency; c is the speed of light in vacuum; θ is the angle of emission of the SH beam with respect to the surface normal. The vectors $\mathbf{e}'(\omega)$ and $\mathbf{e}'(2\omega)$ represent the polarization vectors $\hat{\mathbf{e}}_1(\omega)$, and $\hat{\mathbf{e}}_1(2\omega)$, respectively, after they have been adjusted to account for the linear propagation of the waves to the interface. More specifically, we may write $\mathbf{e}'(\omega) = \mathbf{F}_{1\to 2}\hat{\mathbf{e}}_1(\omega)$. Here the $\mathbf{F}_{1\to 2}$ describes the relationship between the electric field $E\hat{\mathbf{e}}_1$ in medium 1 (propagating towards medium 2), which yields a field $E\mathbf{e}'$ at the interface. For light incident in the x–z plane as shown in Figure 4, $\mathbf{F}_{1\to 2}$ is a diagonal matrix whose elements are $F^{xx}_{1\to 2} = 2\varepsilon_1 k_{2,z}/(\varepsilon_2 k_{1,z} + \varepsilon_1 k_{2,z})$, $F^{yy}_{1\to 2} = 2k_{1,z}/(k_{1,z} + k_{2,z})$, and $F^{zz}_{1\to 2} = 2(\varepsilon_1\varepsilon_2/\varepsilon')k_{1,z}/(\varepsilon_2 k_{1,z} + \varepsilon_1 k_{2,z})$, where the quantity $k_{i,z}$ denotes the magnitude of the z-component of the wavevector in medium i at the relevant wavelength (ω or 2ω) (Figure 4).

A few observations may be made about eqn [12], which describes the relationship between the typical experimental observables of the pump irradiance, $I(\omega)$, and the irradiance of the emitted SH reflection, $I(2\omega)$, from the interface. First, one can immediately recognize the quadratic relationship between the pump irradiance and the SH irradiance that is expected for a second-order nonlinear optical effect. Second, the SH radiation is determined not only by the nonlinear optical response, but by the linear optical properties of the relevant media. Consequently, obtaining the surface nonlinear susceptibility tensor $\boldsymbol{\chi}_s^{(2)}$ from experiment requires knowledge or measurement of the linear response. (It should be noted, however, that the interfacial linear properties always enter into the response in a fixed manner and can be incorporated into an effective surface nonlinear response.) The linear response can significantly enhance or reduce the efficiency of the SHG process. The use of a total-internal reflection geometry, for example, provides a significant enhancement in the SH radiation through the linear optical response of the media. Third, while full knowledge of the linear and nonlinear response will obviously allow one to predict the strength of the SH radiation for any set of conditions, a simple measurement of the SH response does not permit one to determine $\boldsymbol{\chi}_s^{(2)}$, even if the linear optical properties are known. The determination of the tensor $\boldsymbol{\chi}_s^{(2)}$ requires probing the material with different polarization states and/or angles of incidence. Protocols for making these measurements have been discussed extensively in the literature. For the general case of a material with in-plane anisotropy, such as the surface of a crystal, measurements of the response as the crystal is rotated about its surface normal are also very useful in a complete determination of $\boldsymbol{\chi}_s^{(2)}$. Fourth, the simple measurement of the SH intensity as assumed here obviously eliminates information about the overall phase of the $\boldsymbol{\chi}_s^{(2)}$. This phase information is often of considerable interest and importance. For example, if the response of the interface is dominated by an oriented molecular monolayer, the sign of $\boldsymbol{\chi}_s^{(2)}$ will be inverted if the monolayer is reflected through the plane of the surface, i.e., the phase of $\boldsymbol{\chi}_s^{(2)}$ yields information on the polar ordering of the layer. To obtain such phase information, one must employ a scheme using interference with a known SH reference. This approach, which is sketched briefly in the next section, is implemented quite commonly in experiment.

Experimental Considerations

The merits of the SHG technique for selective probing of interfaces are clear. On the other hand, one needs to be able to detect the optical signal associated with a second-order nonlinear response of a material that arises from an effective thickness of just a monolayer or so. Consequently, it is important to consider various factors that aid in optimizing the strength and detectability of the SH radiation. To discuss how best to achieve this end, let us recast eqn [12] in terms of more convenient experimental parameters. We express the SH signal, S, in units of photons/s and describe the laser excitation by its pulse energy E_p, pulse width τ, and repetition rate R. For irradiation of an area A of the sample, we then obtain

$$S = \frac{\omega \sec^2 \theta E_p^2 R |\chi_{\text{eff}}^{(2)}|^2}{4\hbar \varepsilon_0 c^3 \tau A} \qquad [13]$$

where $|\chi_{\text{eff}}^{(2)}| \equiv |\mathbf{e}'(2\omega)\cdot\boldsymbol{\chi}_s^{(2)} : \mathbf{e}'(\omega)\mathbf{e}'(\omega)|/[\varepsilon_1^{1/2}(2\omega)\,\varepsilon_1(\omega)]^{\frac{1}{2}}$, whose typical value is of the order of 10^{-21} m^2/V. From this relation, we see that increasing either the pulse energy or repetition rate of the laser will enhance our SH count rate. These parameters are, however, often limited by the characteristics of the available laser, as well as possible damage of the sample. For a given pulse energy and repetition rate, the SH signal is also seen to increase as the laser pulse duration or sample area is decreased. In practice, adequate SH signals can generally be obtained from high-power Q-switched lasers (with nanosecond pulses) with a fairly large focal spot. A preferred solution in most cases is, however, provided by modelocked lasers with high repetition rate and pulses of sub-picosecond duration. Surface SH signals obtained, for example, using a femtosecond mode-locked Ti:sapphire oscillator, are typically in the range of 10^2–10^6 photons/s. Although these signals are relatively weak, they are easily detectable with photomultiplier tubes (PMT) and appropriate electronics.

The basic arrangement for surface SHG measurements is shown in Figure 5. It makes use of the directionality and frequency selectivity of the SHG process not only to detect the desired signal with high efficiency, but to discriminate strongly against background signals, including the reflected laser beam. In the setup, irradiation of the sample involves a pulsed laser source, LS; a halfwave plate, λ, and polarizer, P, for controlling the input polarization. Spectral control is achieved with a filter F1 that passes the fundamental radiation in the pump beam, but rejects other wavelengths, particularly spurious SH radiation arising from other optical components; and a color filter F2 that passes SH, but rejects the reflected fundamental radiation. In addition, a spectrometer is commonly employed to limit the detection bandwidth further. An analyzer A serves to select the desired SH polarization. The SH signal is then measured by a high-quantum efficiency detector and the signal is monitored by processing electronics, typically a photon counter, a gated integrator, or a lock-in amplifier, depending on the strength of the signal and the repetition rate of the laser. The laser source may be either of fixed wavelength or tunable for spectroscopic measurements.



Figure 5 Schematic representation of a basic surface experimental setup for surface SHG. It is comprised of laser source (LS), halfwave plate (λ), polarizer (P), lenses (L), spectral filters (F1, F2), analyzer (A), and detector (D).

There are other important experimental configurations for surface SHG that extend beyond the basic SH reflection geometry, shown schematically in Figure 6a. A common improvement (Figure 6b) is the implementation of a SH reference in which a small fraction of the pump radiation is directed into a crystal with a bulk second-order nonlinear response. This approach provides a reference against which to compare the measured signal, thus compensating appropriately for pulse-to-pulse variation in duration,



Figure 6 Various schematic representations of different experimental schemes for surface SH measurements. Panel (a) represents the basic scheme as in Figure 5. Panel (b) describes use of a separate SH source as a reference for normalizing the surface SH signals against laser fluctuation and drift. Panel (c) represents the arrangement for a measurement of the phase of the surface SH signal by mixing the fields from the surface and an external source SH radiation. Panel (d) describes the configuration for a time-resolved measurement using the pump-probe scheme.

energy, and spatial profile, as well as for long-term drifts. This type of normalization (against a material with a suitably flat spectral response) is essential for spectroscopy measurements in which the laser frequency is scanned. In addition, use of a calibrated reference is the best way of determining the surface nonlinear response in absolute terms.

It may also be desirable to measure the phase of the signal. For this type of an experiment, a reference field, $\mathbf{E}_{\mathrm{ref}}(2\omega)$, of similar amplitude and known phase response is generated along the path of the surface SH signal $\mathbf{E}(2\omega)$ (Figure 6c). The two collinear SH beams of the same polarization interfere at the detector. The SH power scales as $|\mathbf{E}_{\mathrm{ref}}(2\omega)+\mathbf{E}(2\omega)|^2 = |\mathbf{E}_{\mathrm{ref}}|^2 + 2E_{\mathrm{ref}}E\cos\varphi + |\mathbf{E}|^2$, where φ is the relative phase of the two fields. The relative phase φ may be varied by translating a reference plate along the path of the beam and making use of the dispersion of the ambient air or by inserting another control phase-shifting element. A variant of this phase measurement method is the homodyne scheme in which the reference electric field amplitude $\mathbf{E}_{\mathrm{ref}}(2\omega)$ is significantly stronger than that of the signal amplitude $\mathbf{E}(2\omega)$. The measured SH power then scales as $|\mathbf{E}_{\mathrm{ref}}|^2 + 2E_{\mathrm{ref}}E\cos\varphi$, which yields a signal that varies linearly with the desired SH field strength from the sample.

In the SHG technique, a short-pulse laser is used to interrogate the sample and thus the measurement provides high time-resolution. To make use of this capability, we can add a pump pulse to excite the sample away from equilibrium. This provides the opportunity to examine ultrafast surface dynamics induced by excitation of the sample with a suitable pump laser pulse. For such measurements (Figure 6d), the pump pulse is generally derived from the same laser source as the probe for the SHG measurement, although one or both of these pulses may undergo frequency conversion before being applied to the surface. The critical element is that time synchronism is maintained. The dynamics can then be followed by repeating the SHG measurement at various time delays relative to pump excitation, as controlled by an optical delay line. The ultimate time resolution of this technique is limited only by the duration of the laser pulses and may be as short as a few femtoseconds with state-of-the-art modelocked lasers.

Applications of Surface SHG

The technique of surface SHG is extremely flexible in application, since it relies only on basic symmetry properties for its remarkable surface or interface specificity. SHG measurements can provide quite varied information about the interface, depending on the mode of application of the technique and the material system under study. In this section, we attempt to illustrate the principal types of measurements that can be performed with SHG and the information that can be obtained thereby. For systems with molecular adsorbates, SHG studies can yield information on the density and orientation of molecular species, and can typically do so in real time. For crystalline surfaces, the symmetry and order of the surface can be examined through studies of tensor properties of the surface nonlinear susceptibility. Spectroscopic studies of electronic transitions are also of great value. These can be accomplished for both solids and molecular systems through the same experimental approach of tuning the frequency of the laser source. In all of these investigations, one can achieve very high time resolution, down into the femtosecond range, by the use of pump-probe techniques. In addition, as we discuss below, SHG provides interesting additional capabilities for systems with applied electric and magnetic fields. Finally, the method permits one to probe spatially inhomogeneous systems.

In addition to this diverse range of information that can be provided by surface SHG measurements, the technique is unique in the extremely wide range of material and chemical systems to which it can be – and, indeed, has been – applied. These span the gamut from solids under ultrahigh vacuum to solid/solid, solid/liquid, liquid/vapor, and even liquid/liquid interfaces. Since our examples were drawn to illustrate the type of information obtainable, rather than the range of material systems investigated, the reader is unfortunately obliged to refer to other more detailed treatments of surface SHG measurements to appreciate fully this important facet of the technique.

Adsorbate Density

The remarkably high sensitivity of the SHG technique to the nature of the surface is illustrated by the data in Figure 7, which shows the dramatic change in the SH response from a clean Si(111)-7 × 7 surface upon adsorption of atomic hydrogen. Indeed, it is possible to detect well below 1% of a monolayer (ML) of adsorbed hydrogen. A useful point to note is that the change in $\chi_{\mathrm{s}}^{(2)}$ is linear with adsorbate density for modest values of the coverage, θ. Thus, it is quite easy to obtain a relative gauge of the adsorbate coverage in this regime.

The behavior of the SH response to adsorbates at low coverages can often be described by a simple linearized model of the surface nonlinear susceptibility of $\chi_{\mathrm{s}}^{(2)} = (1-a\theta)\chi_{\mathrm{s},1}^{(2)} + \theta\chi_{\mathrm{s},2}^{(2)}$, where



Figure 7 Dependence of the magnitude (full circles) and the phase (open squares) of the nonlinear susceptibility $\chi_s^{(2)}$ for a Si(111)-7 × 7 surface as a function of the coverage of adsorbed atomic hydrogen using a fundamental photon energy 1.17 eV. Reproduced with permission from Höfer U (1996) Nonlinear optical investigations of the dynamics of hydrogen interaction with silicon surfaces. *Applied Physics A* 63: 533.

$\chi_{s,i}^{(2)}$ $(i = 1, 2)$ are complex quantities and a is a constant. This relation describes the surface nonlinear susceptibility as arising from a contribution $\chi_{s,1}^{(2)}$ from the clean surface and a contribution $\chi_{s,2}^{(2)}$ from a saturated monolayer $(\theta = 1)$ of the adsorbate. The term $-a\theta\chi_{s,1}^{(2)}$ then represents the modification of the surface nonlinearity arising from interaction with the adsorbate. For the case of hydrogen adsorption of Figure 7, this is the dominant term, since hydrogen atoms would have no nonlinearity on their own. In other systems, however, the response can be considered as arising essentially from the nonlinear response of aligned adsorbed molecules. The simple linearity of this relation of $\chi_s^{(2)}$ with adsorbate coverage obviously neglects important effects such as adsorbate–adsorbate chemical interactions, as well as local-field effects and the possible influence of differing adsorption sites. All of these factors have been considered in the literature. Nonetheless, the linearity of response with adsorbate coverage is often found to be a good approximation, even for fairly high adsorbate coverages. From the point of view of simply following adsorption dynamics with SHG, it is not, we note, necessary to have any a priori knowledge of the relation between the adsorbate coverage and the SH response. This relation can be established empirically in static measurements and then used advantageously to follow the dynamics of surface processes.

Surface Symmetry and Molecular Orientation

The surface SHG process is described by the third-rank tensor $\boldsymbol{\chi}_s^{(2)}$. The tensorial properties of this response reflect the symmetry of the surface. Other than for a few cases of high symmetry, such a third-rank tensor gives a distinct signature of surfaces with crystalline order compared to surfaces, such as disordered ones, exhibiting effective in-plane isotropy. The form of the $\boldsymbol{\chi}_s^{(2)}$ tensor can be probed both by measurements that vary the polarization of the fundamental and second-harmonic beams and by measurements in which the plane of incidence is changed with respect to the orientation of the surface, generally by rotating the sample about its normal with a fixed experimental geometry.



Figure 8 Polarization dependence of SHG for normal incidence excitation of the cleaved Si(111)-2 × 1 surface. The polar plot of the SH signal versus the pump polarization orientation is shown for the case of no polarization analysis (top panel), for the SH analyzer along the $[2\bar{1}\bar{1}]$ crystallographic direction of the surface (middle panel), and along the $[01\bar{1}]$ direction (bottom panel). The solid curves are fits to theory assuming that the surface has *m* symmetry. Reproduced with permission from Heinz TF, Log MMT and Thomson WA (1985) Study of Si(111) surfaces by optical second-harmonic generation: reconstruction and surface phase-transformation. *Physical Review Letters* 54: 63.

Figure 8 illustrates the capability of surface SHG measurements to probe surface symmetry. The figure shows SHG polarization dependence for a Si(111) surface cleaved in ultrahigh vacuum. While the underlying bulk symmetry suggests that the surface might exhibit 3m symmetry, the analysis of data indicates that only a single mirror *m* plane is present. This lowered symmetry corresponds to the metastable 2×1 reconstruction induced by the crystal cleavage. By heating the sample, one can observe a phase transformation to the equilibrium 7×7 reconstruction and the emergence of the corresponding 3m surface symmetry.

The analysis of surface or interface symmetry by SHG relies only on the form of the nonlinear susceptibility tensor, i.e., which elements are independent and nonvanishing. Within the context of a microscopic model of the surface response, however, the relative values of the tensor elements of $\boldsymbol{\chi}_{\mathrm{s}}^{(2)}$ can also yield valuable information about the nature of the surface. This approach has been developed extensively in the context of the analysis of molecular orientation at surfaces. The basic notion behind this treatment relies on the knowledge of the microscopic molecular nonlinear polarizability $\alpha_{\lambda\mu\nu}^{(2)}$ and the measured surface nonlinear susceptibility $\chi_{\mathrm{s},ijk}^{(2)}$ to infer information about the orientational average that relates these quantities. As discussed above in conjunction with eqn [10], under the neglect of local-field corrections, the relationship between these two quantities involves the ensemble average of the coordinate transformation tensor from the molecular to the laboratory coordinate systems $\langle T_{i\lambda} T_{j\mu} T_{k\nu} \rangle$. Hence a knowledge of the quantities $\alpha_{\lambda\mu\nu}^{(2)}$, N_{s}, and $\chi_{\mathrm{s},ijk}^{(2)}$ allows us to infer information about the orientational distribution of the molecules as described by the quantity $\langle T_{i\lambda} T_{j\mu} T_{k\nu} \rangle$. Even in the absence of knowledge of the magnitudes of the nonlinear polarizabilities and the adsorbate density, one may still obtain useful information for molecules with a simple form of $\alpha_{\lambda\mu\nu}^{(2)}$.

An important example of this analysis of molecular orientation concerns the case of molecules with a dominant nonlinear polarizability along a single axis, i.e., $\boldsymbol{\alpha}^{(2)} = \alpha_{z'z'z'}^{(2)} \hat{\mathbf{z}}' \hat{\mathbf{z}}' \hat{\mathbf{z}}'$. For the usual situation of in-plane isotropy, one can then show that the nonlinear susceptibility elements are given by $\chi_{\mathrm{s},\perp\perp\perp}^{(2)} = N_{\mathrm{s}} \langle \cos^3 \theta \rangle \alpha_{z'z'z'}^{(2)} / \varepsilon_0$ and $\chi_{\mathrm{s},\|\perp\|}^{(2)} = \chi_{\mathrm{s},\|\|\perp}^{(2)} = \frac{1}{2} N_{\mathrm{s}} \langle \cos \theta \times \sin^2 \theta \rangle \, \alpha_{z'z'z'}^{(2)} / \varepsilon_0$, where θ denotes the angle between the surface normal and the z' molecular axis. It should be noted that these orientational moments, reflecting their origin in a third-rank tensor, give a signature of the polar ordering, since a sign change in the elements of $\boldsymbol{\chi}_{\mathrm{s}}^{(2)}$ follows if the molecular orientation is inverted. Also, when only one element of $\boldsymbol{\alpha}^{(2)}$ is present, we can form ratios of the experimentally measurable ratio of tensor elements that depend only on the molecular orientational factors, such as $R \equiv (2\chi_{\mathrm{s},\|\perp\|}^{(2)} + \chi_{\mathrm{s},\perp\perp\perp}^{(2)}) / \chi_{\mathrm{s},\perp\perp\perp}^{(2)} = \langle \cos \theta \rangle / \langle \cos^3 \theta \rangle$. For a narrow distribution of the orientations centered at θ_0, this ratio yields directly the molecular orientation angle through $R \approx \sec^2 \theta_0$.

This type of molecular orientation analysis has been applied to a wide range of material systems. The method, while powerful, relies on several assumptions, including an adequate knowledge of the molecular nonlinear polarizability, the lack of significant local field corrections, the availability of information about the effective linear dielectric constant in the interfacial region, and a suitable method of eliminating any substrate nonlinear response in the measurement. The method is, consequently, best suited for adsorbed layer of molecules with strong and well-defined nonlinear response, present at relatively modest coverages. The use of resonant excitation is a valuable adjunct in these studies, since it generally simplifies the form and strengthens the molecular nonlinear response. An analogous approach to the analysis of molecular orientation can be accomplished with infrared–visible sum-frequency generation. These measurements often provide a superior method of analysis, since the molecular response and its symmetry are better defined by resonant excitation of a molecular vibration.

Surface and Interface Spectroscopy

Surface SHG can be readily adapted to yield spectroscopic information on surface transitions. As indicated above, both resonances at the fundamental and second-harmonic frequencies are manifested in the SHG response. The examination of resonances at the SH frequency is often convenient, since it permits the application of a relatively intense pump radiation at a frequency well separated from that of the resonance. Such SHG spectroscopy measurements have been widely applied to examine electronic transitions at surfaces and interfaces of solids, as well as in adsorbed molecules under a wide variety of conditions.

An example of SHG spectroscopy of electronic transitions at a buried solid/solid interface is presented in Figure 9. For the epitaxial CaF_2/Si(111) interface, distinctive new electronic transitions, associated with interface states, are observed that are absent from the response of either of the bulk materials. These excitations occur in a spectral range where the bulk silicon sample is highly absorbing, which would render the identification of the new interface transitions very difficult using conventional linear optics. The buried nature of the interface naturally also constrains application of conventional surface probing techniques involving electron



Figure 9 SHG spectrum (solid dots) for the CaF_2/Si(111) interface. For comparison, the open circles represent the corresponding signals for the SiO_2/Si(111) interface, which is seen to give a very weak signal in this frequency range. The solid line is a theoretical fit based on a two-dimensional direct transition of the interface states, together with an excitonic feature slightly below the band gap. Reproduced with permission from Heinz TF, Himpsel FJ, Palange E and Burstein E (1989) Electronic transitions at the CaF_2/Si(111) interface probed by resonant three-wave-mixing spectroscopy. *Physical Review Letters* 63: 644.



Figure 10 Rotational relaxation of Coumarin 314 molecules at the air–water interface subsequent to photoexcitation. The initial anisotropy in the molecular orientational distribution is created by linearly polarized pump radiation in two orthogonal directions in the surface. Reproduced with permission from Zimdars D, Dadap JI, Eilsenthal KB and Heinz TF (1999) Anisotropic orientational motion of molecular adsorbates at the air–water interface. *Journal of Physical Chemistry B* 103: 3425–3433.

irradiation or emission. Two additional general observations are appropriate. First, the lineshape analysis for such measurements must take into account the fact that the SHG response derives from both the real and imaginary parts of $\chi_s^{(2)}$, as we discussed above. Second, in the absence of any other knowledge, SHG spectroscopic data contain an ambiguity about whether the resonances correspond to the fundamental or SH photon energy. This ambiguity, however, can be resolved in a straightforward fashion by complementing the SHG measurement with a sum-frequency measurement in which one frequency is scanned and one is held fixed, as was demonstrated in the study associated with Figure 9.

Time-Resolved Measurements

One of the fascinating frontiers that can be addressed by SHG measurements is probing the ultrafast dynamics of surfaces and interfaces by the pump-probe method. This possibility is exemplified by a variety of studies ranging from the dynamics of laser-driven phase transitions, charge-transfer, solvation, phonon dynamics, and orientational and torsional dynamics.

An example of applying time-resolved SHG to examine ultrafast molecular dynamics at the liquid/vapor interface of water is presented in Figure 10. In these studies, the rotational motion of dye molecules at the interface, which probes the local environment, is followed in real time. This is accomplished by photo-exciting the dye molecules at the interface. Because polarized pump radiation is used, an anisotropic orientational distribution of excited-state molecules is established. Since the excited molecules have a different SHG response, a change in the signal is observed immediately. Subsequently, the anisotropic orientational distribution relaxes to the equilibrium configuration. The time evolution of the rotational anisotropy is followed by detecting the SH of a probe laser pulse as a function of the delay time. Through a comparison of the results for different initial anisotropic distributions (produced by pump beams with differing polarizations), one may deduce rates for both in-plane and out-of-plane orientational relaxation. This example illustrates the possibilities of time-resolved SHG measurements for probing the detailed dynamics of molecules at an interface on the ultrafast timescale.

Spatially Resolved Measurements

Up to this point, our discussions have centered on spatially homogenous surfaces and interfaces. Surface SHG has also been exploited to probe the lateral variation of inhomogeneous surfaces with the micron to sub-micron resolution characteristic of optical microscopy techniques. Spatial resolution may be achieved simply by detecting the nonlinear response with a focused laser beam that is scanned across the surface. A large area of the surface may also be illuminated and the emitted nonlinear radiation imaged. A wide range of applications of this imaging capability has emerged, including the probing of biological materials, such as cells and tissues, to probing spatially varying electric fields and magnetic domains. Within the biological context, SH microscopy has recently become an active research direction. In these applications, while probing with SHG typically senses non-centrosymmetric structures in bulk samples as opposed to interfaces, most of the aspects of SHG presented in this article still apply. To further improve the spatial resolution of SHG microscopy, researchers have also employed near-field techniques for spatial resolutions below the diffraction limit.

Complementary approaches to the real-space imaging just described have also been developed based on SH diffraction. In this scheme, periodically modulated surfaces are established holographically on a surface by utilizing two interfering laser beams. In addition to the reflected and transmitted SH beams, additional beams are then generated at well-defined angles as dictated by the grating period. This approach has been used to monitor the relaxation of a monolayer grating of adsorbates in time, which yields precise information on the rate of adsorbate surface diffusion.

Probing Electric Fields at Interfaces

For centrosymmetric media, the SHG process shows a high degree of sensitivity to the presence of electric fields. This property follows from the fact that an applied electric field can break the inversion symmetry, just as an interface does. The resulting process, termed electric-field induced SHG (or EFISH), has been known for many years. From a phenomenological standpoint, it can usually be described as a nonlinear response of the form $\mathbf{P}^{(3)}(2\omega) = \varepsilon_0 \boldsymbol{\chi}^{(3)} : \mathbf{E}(\omega)\mathbf{E}(\omega)\mathbf{E}$, where **E** is the electric field being probed and $\mathbf{E}(\omega)$ is the laser pump field. Within the context of surfaces and interfaces, there are many circumstances where probing such electric fields is of interest and importance. The SHG technique provides high sensitivity, good spatial resolution, accessibility to buried interfaces, and, in the pump-probe implementation, extremely high time resolution. In addition, with appropriate measurements of the polarization dependence and homodyne detection, the full vector character of the electric field can be determined.

The behavior of electric-field induced SHG is similar to that arising from the asymmetry of an interface. Indeed, it is formally equivalent to the response of an interface provided that the electric field is present in (or radiates from) a region of less than a wavelength's thickness. The applications of this measurement capability are quite diverse, ranging from studies of charging and acid/base reactions at liquid/solid interfaces to probing fields in metal-oxide-semiconductor structures and Schottky barriers to the measurement of freely-propagating terahertz radiation. In Figure 11, SHG with appropriate polarization control and homodyne detection scheme has been applied to the measurement of the vector character of electric fields present in a dc-biased dipole structure on silicon. By spatially scanning the laser beam, a two-dimensional electric field map can be produced. In a pump/probe scheme, the same measurements can be made with femtosecond time resolution.



Figure 11 Vector map of the electric field in Si-on-sapphire substrate as deduced by SHG measurements. A voltage is imposed on the rectangular metallic electrodes, which are separated by 80 μm. Reproduced with permission from Dadap JI, Shan J, Weling AS, Misewich JA, Nahata A and Heinz TF (1999) Measurement of the vector character of electric fields by optical second-harmonic generation. *Optics Letters* 24: 1059–1061.

Probing Magnetization at Interfaces

In contrast to the application of an external electric field (a polar vector), the presence of an external magnetic field (an axial vector) does not break the inversion symmetry of a material. Thus, SHG retains its interface selectivity for magnetic effects. SHG measurements, as an interface-specific probe, thus provide an excellent complement to the linear magneto-optical Kerr effect (MOKE), which is sensitive to magnetic effects within the penetration depth of the light.

The ability of the SHG technique to sense the magnetization at a surface is illustrated in Figure 12 for a film of epitaxially-grown magnetic Co on nonmagnetic substrate Cu. A hysteresis loop of the magnetization versus the strength of an applied magnetic field is shown, where the magnetization is gauged from the SHG response. Through measurements of the response as a function of the thickness of



Figure 12 SH response of a Co film on a Cu(001) substrate as a function of the applied magnetic field. A hysteresis loop corresponding to the surface response is observed. Reproduced with permission from Wierenga HA, de Jong W, Prins MWJ *et al.* (1995) Interface magnetism and possible quantum-well oscillations in ultrathin Co/Cu films observed by magnetization induced second harmonic generation. *Physical Review Letters* 74: 1462–1465.

the magnetic film, the researchers demonstrated that the SH response reflected the interface properties, rather than those of the bulk film.

Probing Micro- and Nanoscale Structures

In addition to the microscopy studies described above that probe spatially inhomogeneous surfaces, there has been considerable interest in SHG from a variety of strongly textured surfaces and small particles. From the standpoint of the optical response of materials, particular interest has been attached to studies of metallic surfaces with surface roughness. For appropriate roughness of low-loss materials, such as silver, very significant local-field enhancements can be achieved. Since these field enhancements enter into the strength of the SH emission nonlinearly, overall enhancements in the SH power by several orders of magnitude have been demonstrated. This provides both a useful method of study of such surface enhancement effects and a scheme for amplifying the relatively weak surface nonlinear response.

Beyond these problems associated with roughened surfaces, considerable attention has recently been directed towards the application of the SHG technique for probing micro- and nano-scale particles. The fundamental principle of the interface selectivity of the SHG process for such systems comprised of centrosymmetric materials remains unaltered. The interaction of these particles with the radiation fields is, however, significantly modified. For the case of particles with dimensions of several optical wavelengths, the overall SHG signal strength may be comparable to that from a corresponding area of a planar surface. The radiation pattern will, of course, be strongly modified and will generally be diffuse in character. While this makes detection (and background discrimination) somewhat more difficult than for the planar geometry, many SHG measurements of surface and interface properties have been carried out in this regime. As the particle size becomes progressively smaller, particles with overall inversion symmetry begin to exhibit appreciable cancellation of the SH emission. Indeed, in the limit of vanishing size, full cancellation is expected. This tendency is, however, offset by the increasing surface-to-bulk ratio and the possibility of increasing the number of particles probed. It has been demonstrated experimentally that the surfaces of particles in the nanometer length scale can indeed be probed by SHG.

From the point of view of applications, this extension of the SHG technique to probe micro- and nano-structured materials opens up a rich variety of new possibilities. Results have been reported on metal and semiconductor nanoparticles in suspension, as well as on colloids of minerals. In addition, liquid droplets have been investigated. Self-assembling structures such as liposomes and vesicles have been examined. For these structures, many of the same capabilities of SHG as demonstrated for the planar geometry, such as probing of adsorption and charging effects, have been demonstrated. More uniquely, molecular transport *through* the liposome membrane could also be observed and characterized. The possibility of extension of these measurements to biological systems is of obvious interest and promise.

Concluding Remarks

In this article, we provided a brief review of surface SHG as a technique for interface-specific probing of materials. In addition to discussing some of the fundamental ideas underlying the method, we outlined the wide variety of information that may be obtained from such measurements, ranging from surface symmetry and molecular ordering to interface spectroscopy and ultrafast dynamics. While several aspects of the method have now become quite well established, developments in widely available mode-locked lasers with excellent performance characteristics have greatly enhanced the ease of making surface SHG measurements in a wide class of material systems. In addition, new developments and applications of the method have continued to emerge apace. Of particular note in this regard are applications to probe electric fields and magnetization at interfaces, as well as advances in the use of the method for interface-specific probing of micro- and nanoscale structures. The sharp increase in applications of SHG for probing systems of biological importance constitutes another important development, and one with much promise for the future.

See also

Materials for Nonlinear Optics: Organic Nonlinear Materials. **Nonlinear Optics, Basics:** $\chi^{(2)}$–Harmonic Generation. **Physical Applications of Lasers:** Sum-Frequency Generation at Surfaces.

Further Reading

Bennemann KH (ed.) (1998) *Nonlinear Optics in Metals*. Oxford, UK: Clarendon.

Bloembergen N (1965) *Nonlinear Optics*. New York: WA Benjamin.

Boyd RW (1992) *Nonlinear Optics*. New York: Academic.

Brevet PF (1997) *Surface Second Harmonic Generation*. Lausanne, Switzerland: Presses Polytechniques et Universitaires Romandes.

Butcher PN and Cotter D (1990) *The Elements of Nonlinear Optics*. Cambridge, UK: Cambridge.

Corn RM and Higgins DA (1994) Optical second-harmonic generation as a probe of surface-chemistry. *Chemical Review* 94: 107–125.

Dadap JI and Heinz TF (2001) Nonlinear optical spectroscopy of surfaces and interfaces. In: Moore JH and Spencer ND (eds) *Encyclopedia of Chemical Physics and Physical Chemistry*, pp. 1089–1125. Bristol, UK: IOP.

Eisenthal KB (1996) Liquid interfaces probed by second-harmonic and sum-frequency spectroscopy. *Chemical Review* 96: 1343–1360.

Heinz TF (1991) Second-order nonlinear optical effects at surfaces and interfaces. In: Ponath H-E and Stegeman GI (eds) *Nonlinear Surface Electromagnetic Phenomena*, pp. 353–416. Amsterdam: North Holland.

Liebsch A (1995) Electronic excitations at metal surfaces. In: Halevi P (ed.) *Photonic Probes of Surfaces*, pp. 479–532. Amsterdam: Elsevier.

Lüpke G (1999) Characterization of semiconductor interfaces by second-harmonic generation. *Surface Science Report* 35: 75–161.

McGilp JF (1995) Optical characterisation of semiconductor surfaces and interfaces. *Progress in Surface Science* 49: 1–106.

McGilp JF (1999) Second-harmonic generation at semiconductor and metal surfaces. *Surface Review Letters* 6: 529–558.

McGilp JF, Patterson CH and Weaire DL (eds) (1995) *Epioptics: Linear and Nonlinear Optical Spectroscopy of Surfaces and Interfaces*. Berlin, New York: Springer.

Prasad PN and Williams DJ (1991) *Introduction to Nonlinear Optical Effects in Molecules and Polymers*. New York: Wiley.

Reider GA and Heinz TF (1995) Second-order nonlinear optical effects at surfaces and interfaces: recent advances. In: Halevi P (ed.) *Photonic Probes of Surfaces*, pp. 413–478. Amsterdam: Elsevier.

Richmond GL (1997) Vibrational spectroscopy of molecules at liquid/liquid interfaces. *Analytical Chemistry* 69: A536–A543.

Richmond GL, Robinson JM and Shannon VL (1988) Second harmonic generation studies of interfacial structure and dynamics. *Progress in Surface Science* 28: 1–70.

Shen YR (1984) *The Principles of Nonlinear Optics*. New York: Wiley.

Shen YR (1989) Optical second harmonic-generation at interfaces. *Annual Review of Physical Chemistry* 40: 327–350.

Single Molecule Spectroscopy

X Michalet and S Weiss, University of California, Los Angeles, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Textbooks in physics, chemistry, and biology abound in diagrams depicting single-particle, single-molecule or single-enzyme properties, reactions or interactions with their environment. Such pictures and the numbers associated with them, however, were, until recently, extrapolated from measurements performed on large ensembles of molecules, which only yield quantities averaged out over time, space, conformations and/or the local environment. Advances in detector sensitivity and improvements in instrument design do now provide scientists with tools to probe single molecules with light, and monitor their photophysical properties with exquisite sensitivity and time resolution. This spectroscopic information is used to explore the molecular structure, conformational dynamics, local environment, and intermolecular interactions. The collected data generate a wealth of new information on single-molecule physical chemistry or biomechanics, but also in polymer gel physics or glass dynamics and other domains of solid state physics.

This article reviews the field of single-molecule spectroscopy. First, the principles underlying single-molecule spectroscopy approaches are introduced, and this is followed by a discussion of the different spectroscopic techniques available to the experimentalist and what kind of information can be extracted with each of them. It also discusses important photophysical properties of molecules that influence the outcome of single-molecule spectroscopic measurements. The next section presents some applications of these techniques, focusing on physical properties of materials and biological applications of single-molecule spectroscopy. The last part briefly reviews recent developments and outlines the future prospects of single-molecule spectroscopy.

Principles of Single-Molecule Spectroscopy

Motivation

Measurements performed on ensembles of molecules only yield averaged-out information. This averaging process is of several kinds: average over molecular heterogeneity (e.g., chemical composition, oxidation state, or spatial conformation) and average over different or changing local environments. Moreover, dynamic processes studied by ensemble measurements cannot sort out molecules exhibiting fast or slow reaction times, although such differences are expected from the stochastic nature of any chemical kinetics. The interest in single-molecule analysis is for these reasons manifold. At low temperature, being able to study a single molecule and its evolution under the influence of various external parameters allows for precise tests of molecular quantum electrodynamics. At higher temperature, it gives access to the temporal evolution of different nanodomains of a bulk material in which single molecules are embedded as reporters of their environment. In biology and biochemistry, the building blocks of any process are individual molecules (genes, enzymes, motors, filaments, etc.); the ability to fully understand their kinetic behavior at the single-molecule level is thus of utmost importance. Finally, reliable observation of single molecules is a prerequisite of the full development of nanotechnology and quantum computing.

Historical Outlook

Single-molecule experiments were first performed on isolated ion channels by the patch clamp technique, which allows the recording of single-ion translocation through a pore-like protein embedded in a fluid membrane. Scanning tunneling and atomic force microscope observations later opened the way to investigations of nanometer-scale objects on surfaces. Only recently have optical methods reached the sensitivity required to detect, image, manipulate, and follow the spectroscopic evolution of single molecules on surfaces, in solids, liquids, and biological membranes as well as inside live cells.

Single-molecule spectroscopy (SMS) was initially demonstrated in a system of pentacene molecules embedded in a *p*-terphenyl host crystal at liquid helium temperature. Absorption (leading to fluorescence excitation) spectroscopy in this system takes advantage of the very narrow zero-phonon absorption line (ZPL) of the rigid pentacene molecule (Figure 1). The position in laser-frequency space of each molecule's ZPL indeed depends on the local fields, allowing for precise molecular selectivity. However this approach is limited to a few molecule–host pairs and requires cryogenic techniques, due to broadening of the ZPL above 10 K.

Room temperature studies started with total internal reflection (TIR) microscopy and standard flow-cytometry methods in the mid-1980s. In the latter case, single molecules randomly passing through the excitation volume gave rise to sudden bursts of photons emitted during their brief transit. Initially developed for rapid DNA sequencing, this simple approach is now widely used for more sophisticated studies in its confocal version (Figure 2), which will be detailed in the following.

The first image of a single molecule at room temperature was later obtained using scanning near-field optical microscopy (Figure 3), rapidly followed by similar achievements using far-field confocal microscopy, at the expense of a lower spatial resolution, but with much more ease of use. TIR and wide-field fluorescence imaging are now used to image and study the two-dimensional and three-dimensional diffusion trajectories of single fluorescent molecules (Figure 4), making a come-back after the pioneering studies of the early 1980s.



Figure 1 Fluorescence excitation spectra of pentacene in *p*-terphenyl at 1.5 K. (a) Schematic of the cryogenic setup used. A laser beam is focused onto the sample through a lens into the cryogenic chamber. The sample can be moved in the *XY* plane, with a magnet and coil pair. A beam block rejects the incident laser light (black arrow). A paraboloidal mirror collects the emitted fluorescence (dashed arrows) and redirects it towards the detector (photomultiplier tube). The laser frequency (linewidth 3 MHz) is tuned around the absorption line center at 592.321 nm. (b) Broad scan showing the inhomogeneously broadened line shape of pentacene molecules embedded in a *p*-terphenyl crystal at 1.5 K. The sharp lines correspond to spectra of individual molecules (see panel c) (cps: counts per second). (c) Detail of the previous spectrum showing spectra of several individual molecules. The variability of intensities is due to the different positions of the molecule in the excitation beam. (d) Individual molecule spectrum obtained at lower excitation power exhibiting a Lorentzian shape (solid line) centered at 592.407 nm with a lifetime-limited width of 7.8 MHz (intensity is measured in counts-per-second for all three spectra). (a): adapted from Ambrose WP, Basché T and Moerner WE (1991) Detection and spectroscopy of single pentacene molecules in a *p*-terphenyl crystal by means of fluorescence excitation. *Journal of Chemical Physics* 95: 7150–7163. (b)–(d): after Moerner WE (1994) Examined nanoenvironments in solids on the scale of a single, isolated impurity molecule. *Science* 265: 46–53. Copyright 1994, The American Association for the Advancement of Science.

Requirements for Single-Molecule Sensitivity

Observing single molecules may be as easy as finding a needle in a haystack if background, signal and noise are not carefully optimized. Simple considerations illustrated in Figure 5a help measure the technical challenge bearing on single-molecule optical detection. Whatever the type of detected signal (fluorescence, Raman scattering, or others), it is characterized by an absorption cross-section σ (probability of photon absorption) and a quantum yield Q (number of emitted photons per absorbed photon). The optical setup transmits an excitation power P at a frequency ν, resulting in a signal rate $s = EQ\sigma P/(Ah\nu)$ expressed in counts per second (or Hz). This rate is proportional to P/A where A is the cross-section of the excitation beam in the plane of the molecule. E is the collection efficiency of the setup. The environment adds a background rate b per unit volume and unit power, and the detector contributes a dark count rate D. Neglecting noise from the readout electronics, a measurement of duration τ will yield the following signal-to-noise ratio (SNR):

$$\mathrm{SNR} = \frac{s\tau}{\sqrt{(s + bVP + D)\tau}} \qquad [1]$$

where V is the excited volume. The denominator is the root mean square of all contributions to the measured count rate, considered shot-noise limited. The SNR obviously increases at larger integration time τ. Another important quantity is the signal-to-background ratio (SBR):

$$\mathrm{SBR} = \frac{EQ\sigma}{bVAh\nu} \qquad [2]$$

These ratios can be increased by improving the collection efficiency E or decreasing the excitation volume V. A larger excitation power or a longer integration time will improve the SNR without affecting the SBR. Typical values for the above



Figure 2 Single-molecule fluorescence burst detection. (a) Schematic of the confocal setup used for single-molecule fluorescence detection. A collimated laser beam is focused through a high numerical aperture (NA) objective in a liquid cell. Molecules diffusing through the diffraction-limited excitation volume (~ 1 fl) emit photons during their passage, which are collected by the same objective. A dichroic mirror (D1) separates excitation and emission wavelengths. The emitted light is focused on a pinhole (ph) in order to reject out-of-focus background light, and finally recollimated onto two different avalanche photodiodes (APDs) after spectral separation by a dichroic mirror (D2). Filters specific for each channel (F_a: acceptor channel, F_d: donor channel) may be used to improve spectral separation. (b) 5 s time trace of recorded bursts for a 30 pM solution of doubly labeled DNA in 20 mM sodium phosphate buffer. The DNA constructs are used for distance measurement (detailed in **Figure 9**) and have a TMR fluorophore attached to one end of the DNA molecule and a CY5 fluorophore attached to the *n*th base from the end. The time traces correspond to $n = 12$. Gray: TMR fluorescence (donor); black: CY5 fluorescence (acceptor). The laser excitation (0.6 mW, 514 nm) is focused 10 μm within the solution through an oil immersion objective (numerical aperture: 1.4). For each detected photon, the APD generates a pulse, which is recorded by a computer-embedded acquisition board. Counting these events into 200 μs bins, the resulting time trace exhibits distinct bursts distributed randomly in time, with duration and amplitude corresponding to a Brownian diffusion of individual molecules through the excitation volume. (b): is adapted from Deniz AA, Dahan M, Grunwell JR, *et al*. (1999) Single-pair fluorescence resonance energy transfer on freely diffusing molecules: Observation of Förster distance dependence and subpopulations. *Proceedings of the National Academy Sciences USA* 96: 3670–3675. Copyright 1999, The National Academy of Sciences.



Figure 3 Scanning near-field imaging of single molecules at room temperature. (a) Schematic of a scanning near-field optical microscope setup used for single-molecule imaging. An aluminum-coated tapered optical fiber (raster-scanned at nanometer distance from the sample) serves as a waveguide for laser excitation. Shear-force feedback keeps the tip at a constant distance from the sample, resulting in a signal used for nanometer-resolution topographic reconstruction of the scanned area. The excitation volume and the corresponding local evanescent electric field are detailed in the expanded view. Fluorescence light emitted by individual molecules is collected by an oil immersion, high NA objective and recorded by an avalanche photodiode. (b) $4 \times 4\ \mu m^2$ area of a polymethylmethacrylate (PMMA) coated coverslip on which a diluted methanol solution of a lipophilic carbocyanine dye, $diIC_{12}$, has been deposited. Scanning was performed with randomly polarized light. (c) Orientation of the corresponding individual emitting dipole determined by modeling the field distribution (expanded view in a), simulation of the absorption intensity with polarized excitation and comparison with data obtained at two different excitation polarizations. (a): Adapted and (b), (c) reprinted with permission from Betzig E and Chichester RJ (1993) Single molecules observed by near-field scanning optical microscopy. *Science* 262: 1422–1425. Copyright the American Association for the Advancement of Science.



Figure 4 Single molecule diffusion in two dimensions. (a) 6.8×6.8 µm^2 images of fluorescently labeled lipids (tetramethylrhodamineinthiocarbamoyl, linked to 1,2-dihexadecanoyl-*sn*-glycero-3-phospho-ethanolamine, DHPE) in a lipid double layer membrane (palmitoyloleoylphosphocholine, POPC) at different concentration. From left to right: 10^3 dyes/µm^2, 10 dyes/µm^2, 10^{-2} dyes/µm^2. Each image was obtained with an epifluorescence microscope, illuminated by a defocused 514 nm Ar laser line (~60 kW/cm^2), and 5 ms integration on a nitrogen cooled CCD camera. Color scale: blue = 0, $d = 60$ counts). Image intensity at 10^3 dyes/µm^2 was divided by 60. (b) Sequence of three 5.4×5.4 µm^2 images of two labeled lipids observed at 105 ms intervals (actual acquisition rate was one frame every 35 ms, integration time: 5 ms). (c) Subregion of a 2.4×2.4 µm^2 membrane area showing the peak marked by a star in B. The nonlinear least-square fit of a two-dimensional Gaussian profile to the peak yields values of the fluorescence intensity $I = 168 \pm 25$ counts, width $r = 480 \pm 80$ nm and two-dimensional position with 40 nm resolution. Adapted from Schmidt T, Schutz GJ, Baumgartner W, *et al.* (1996) Imaging of single molecule diffusion. *Proceedings of the National Academy of Sciences USA* 93: 2926–2929. Copyright 1996, The Academy of Sciences.

parameters in the case of a confocal microscopy study of freely diffusing fluorescein isothiocyanate (FITC) in water, using avalanche photodiode detectors (APD) are: $E = 10^{-2}$, $Q = 0.85$, $\sigma = 2.8 \times 10^{-16}\,\text{cm}^2$, $A = 0.1\,\mu\text{m}^2$, $\lambda = c/\nu = 525\,\text{nm}$, $bV = 10\,\text{Hz}/\mu\text{W}$, $D = 100\,\text{Hz}$. With an excitation power of 100 µW and a 1 ms integration time, a count rate of 629 counts/ms can be obtained, of which 1 comes from the background sources, leading to a SNR ~25 and SBR ~629. Although these are acceptable figures, they have to be balanced by the fact that single molecules have a finite lifespan. Single molecules in an oxygen-rich environment typically emit on the order of 10^6 photons before irreversible degradation (photobleaching). With the above parameters, this amounts to a total emission of ~3.2 ms. This is enough to observe freely diffusing molecules during their transit time of a few hundred microseconds. For a fixed molecule, however, it sets a stringent limit on the total duration of a single-molecule observation, and all efforts are put on reducing the excitation volume and intensity, as well as background sources. Similar considerations hold on the detector side, where a trade-off has to be found between time-resolution and quantum efficiency.

In addition to SNR and SBR issues, care has to be taken to ensure that the collected signal originates from a single molecule. Two different strategies can be envisioned:

(i) work at low concentration, such that at most one molecule is present in the excitation volume (Figure 5b), or equivalently, minimize the excitation volume;
(ii) use a selective excitation or emission detection protocol, such that only one molecule is excited or detected within the sampled volume (Figure 5c).

The first case has already been illustrated in Figure 2, in which a solution of fluorophores at low concentration yields separate bursts corresponding most of the time to transits of individual molecules. The second strategy can be adopted for the example illustrated in Figure 1, in which the ZPL of individual molecules lying in the wings of the ensemble spectrum are well separated. Tuning the laser to the peak absorption frequency of a molecule will excite this molecule only, allowing for a separate study of this molecule.

In summary, a set of six criteria can be defined for SMS:

1. The observed density of emitter is compatible with the known concentration of individual molecules and scales with the original concentration.
2. The observed intensity level is consistent with that of a single emitting molecule.
3. Each immobilized emitter has a well-defined absorption or emission dipole (for organic dyes usually linear, but for other emitters such as a fluorescent semiconductor nanocrystal, possibly circular).



Figure 5 Signal, background and noise issues in single-molecule detection. (a) In a single-molecule spectroscopic experiment, excitation light (power P, frequency ν) is focused on the sample through an optical element O_1 (objective lens, fiber tip), exciting a diffraction-limited volume of section A, represented by an ellipsoid in the expanded view. The absorption process is characterized by an absorption cross-section σ and the emission by a quantum yield Q. The background contribution per watt of incident power is B, whereas the detector will have a dark count rate D. The signal is collected by an optical element O_2 (possibly confounded with O_1), and further guided to the detector, with an overall efficiency E. (b) The signal of a single molecule can be separated from that of other molecules if the probability of finding two or more molecules in the probed volume is negligible. This can be obtained either by a low concentration, or by reducing the excitation volume. (c) If each molecule in the excited volume can be characterized by a different spectral property (which may or may not depend on its exact environment), it is possible to use very selective excitation or detection techniques to probe just one molecule in the sampled volume (the black sphere in the ellipsoid).

4. Fluorescence emission exhibits only two levels (on/off) exemplified in blinking or photobleaching.
5. If there are more emission levels due to spectral jumps (see the section on fluorescence), blinking and spectral jumps are correlated.
6. Antibunching of the emitted photons permits us to test whether the detected signal comes from a single quantum emitter or more (see the section on biological studies below).

Types of Spectroscopy

Fluorophores

A variety of fluorescence emitters (or fluorophores) have been investigated with single-molecule spectroscopy techniques. Fluorescent organic molecules, green fluorescent proteins (GFP) and other biological fluorescent proteins, conjugated polymers (J-aggregates), light-harvesting complexes (e.g., B-phycoerythrin) comprising several fluorophores acting effectively as a single quantum emitter, or semiconductor nanocrystals, are but a few examples of systems which have been extensively studied. Each of these systems exhibits fluorescence based on specific processes, which cannot be described in detail here. A simple picture valid for single fluorescent dyes will be presented instead. It captures, however, the essential ingredients needed to describe the different parameters accessible with single-molecule spectroscopy.

Fluorescence Emission

Most single-molecule experiments use one-photon fluorescence excitation because of its relatively large cross-section ($\sim 10^{-16}\,\mathrm{cm}^2$). It also allows for a simple rejection of the excitation light: the emitted photons have a lower energy because of losses in intramolecular relaxation processes (the so-called Stokes shift). Excitation and emission processes are conveniently represented by a Jablonski diagram (Figure 6a) depicting the initial, final, and intermediate electronic and vibrational states of the molecule. Upon excitation to the first excited state, the molecule has a certain probability to be shelved in a nonemitting triplet state for up to milliseconds, resulting in 'dark' or off-states (Figure 6b,c). This results in a saturation of the emitted count rate R (Figure 6d) according to:

$$R = R_s \frac{I/I_s}{1 + I/I_s}, \qquad [3]$$

where the saturation intensity $I_s \sim 10$–$100\,\mathrm{kW/cm^2}$ and $R_s \sim 1$–$20\,\mathrm{MHz}$ for typical fluorophores. Incidentally, this puts a limit in SNR enhancement due to saturation of the emitted signal (triplet bottleneck). Other fluorescence emitting 'single molecules' like semiconductor nanocrystals exhibit similar dark state intervals, although for different reasons (Auger ionization or surface trapping of carriers). Finally, spectral jumps are also observed at room temperature (**Figure 6e**). This phenomenon results in a shift of absorption and emission maxima due to the changing environment of the molecule, or a sudden conformational change. The corresponding changes in excitation and emission spectra are noticed by sudden fluctuations in the emitted intensity



Figure 6 Single-molecule fluorescence. (a) Jablonski diagram for fluorescence (at room temperature). Upon absorption of a photon of energy $h\nu_a$ close to the resonance energy $E_{S_1} - E_{S_0}$, a molecule in a vibronic sublevel of the ground singlet state S_0 is promoted to a vibronic sublevel of the lowest excited singlet state S_1. Nonradiative, fast relaxation brings the molecule down to the lowest sublevel in picoseconds. Emission of a photon of energy $h\nu_e < h\nu_a$ (radiative rate k_r) can take place within nanoseconds and bring the molecule back to one of the vibronic sublevels of the ground state. Alternatively, collisional quenching may bring the molecule back to its ground state without photon emission (nonradiative rate k_{nr}). A third type of process present in organic dye molecules is intersystem crossing to the first excited triplet state T_1 (rate k_{ISC}). Relaxation from this excited state back to the ground state is spin-forbidden and thus the lifetime of this state is in the order of microseconds to milliseconds. Relaxation to the ground state takes place either by photon emission (phosphorescence) or nonradiative relaxation. The fluorescence lifetime is defined by $\tau = 1/\Gamma = (k_r + k_{nr})^{-1}$. (b) Fluorescence time trace (40 ms excerpt) of a Texas Red (TR) molecule attached to a 20-nucleotides-long single-stranded DNA molecule immobilized on a silanized glass coverslip. The confocal setup is similar to that depicted in **Figure 2**. Excitation: 514 nm, circularly polarized, 6 kW cm^{-2}, binning: 200 µs. On- and off-states (the latter corresponding to the molecule being in the triplet state) alternate stochastically. (c) Histograms of on-state count (left) and off-state duration (right) for the time trace partly shown in (b). The decay parameters of the exponential fits (solid line) are indicated. $t_{off} = 1.2$ ms is the triplet state lifetime. $N_{on}^{-1} = k_{ISC} = 1.7\%$. (d) Intensity dependence of the emission rate of a single Texas Red molecule. The data departs from a linear dependence because of saturation due to intersystem crossing. The fitted curve yields a saturation rate of $R_S = 6.5$ MHz and a triplet lifetime $t_{off} = (k_{ISC}\ R_S)^{-1} = 10$ µs. The difference between this value and the value obtained in (c) illustrates the heterogeneity uncovered by single-molecule measurements. (e) Spectral jumps of a single Texas Red molecule attached to a single-stranded DNA molecule. ds: dark state, sj: spectral jump, no sj: dark state not followed by a spectral jump. Cases where spectral jumps are observed without noticeable dark states may still correspond to dark states with durations shorter than the time resolution of the experiment. (b)–(d) Adapted from Ha T, Enderle T, Chemla DS, *et al.* (1997) Quantum jumps of single molecules at room temperature. *Chemical Physics Letters* 271: 1–5. Copyright 1997, Elsevier Science B. V. (e) Adapted from Ha T, Enderle T, Chemla DS and Weiss S (1996) Dual-molecule spectroscopy: molecular rules for the study of biological macromolecules. *IEEE Journal of Selected Topics in Quantum Electronics* 2: 1115–1127. Copyright 1996 IEEE.

(due to wavelength dependence of the absorption cross-section).

Fluorescence Lifetime

A fluorescence photon is emitted within nanoseconds after absorption of the excitation photon. The decay law is usually mono-exponential, characterized by a lifetime $\tau = \Gamma^{-1}$ (Figure 6a). However, the lifetime depends on the emission spectrum (which can change due to spectral shifts) and the local environment. For instance, the proximity to a dielectric or metallic surface markedly changes it via perturbations of the intramolecular transition matrix elements. Thus, fluorescence lifetime is a sensitive probe of the environment of the molecule (Figure 7). Lifetime measurements require a pulsed laser source and time-correlated single-photon detection and analysis techniques.

Fluorescence Polarization

The efficiency of photon absorption by a fluorescent molecule is proportional to $(\boldsymbol{E}\cdot\boldsymbol{\mu})^2$ where $\boldsymbol{E}$ represents the local electric field and μ the molecule's absorption dipole moment. For a fixed fluorophore, modulation of the excitation polarization thus allows the determination of the absorption dipole orientation (the emission dipole being generally nearly parallel to it). This information in turn allows the determination of the spatial orientation of the molecule. For a mobile molecule, however, more information is needed, since the emission dipole has time to tumble significantly during the few nanoseconds between absorption and emission. The emission polarization is needed to fully recover the relevant information, as illustrated in Figure 8. Different experimental schemes can be used, besides the near-field optical one described in Figure 3 and the confocal one described in Figure 8. In particular, it is important to recover the projection of the polarization on more than two orthogonal axes. Approaches taking advantage of aberrations induced by index mismatch in high numerical aperture (NA) objectives, or using TIR excitation with alternating polarizations, or using amplitude or phase masks, allow a complete determination of this orientation.

Fluorescence Resonance Energy Transfer

A special case of the local influence of the environment on fluorescence is encountered in fluorescence resonance energy transfer (FRET, see Figure 9a), first theoretically explained by Förster in the late 1940s. In case of the presence of a nearby molecule (acceptor) having an absorption spectrum overlapping that of the donor emission, there is a possibility that the energy absorbed by the donor is transferred nonradiatively to the acceptor. The efficiency E of this transfer is given by:

$$E = \left(1 + \left(\frac{r}{R_0}\right)^6\right)^{-1} \qquad [4]$$

where r is the distance between the two emitting centers and R_0 is the Förster radius (in Å):

$$R_0 = a(\kappa^2 n^{-4} Q_D J(\lambda))^{1/6} \qquad [5]$$

In this complex expression, $a = 9.78 \times 10^3$, n is the medium refractive index, Q_D the donor fluorescence quantum yield in the absence of the acceptor and $J(\lambda)$ is a spectral overlap integral (in $M^{-1}\ cm^3$). κ^2 is a geometric factor, which averages out to 2/3 in the case of freely rotating dyes. A typical order of magnitude for R_0 is a few nanometers, which gives the range of the energy transfer. FRET is thus very sensitive to the donor–acceptor distance, which makes it a useful molecular ruler. Experimentally, the efficiency is measured as a function of the recorded donor (F_D) and acceptor (F_A) emissions (dual-channel measurement) via:

$$E = \left(1 + \alpha \frac{F_D}{F_A} \frac{Q_A}{Q_D}\right)^{-1} \qquad [6]$$

where Q_A and Q_D are the fluorescence quantum efficiencies of the donor and acceptor, respectively, and α is the ratio of the acceptor and donor channel detection efficiencies. An illustration of this utilization is given in Figure 9b–d, where different predefined distances between donors and acceptors are set by rigid double-stranded DNA molecules. The corresponding donor–acceptor distances are readily measured on diffusing molecules, with subnanometer precision.

Alternatively, the transfer efficiency can be measured via the fluorescence lifetimes as:

$$E = 1 - \frac{\tau_{D(A)}}{\tau_{D(0)}} \qquad [7]$$

where $\tau_{D(A)}$ and $\tau_{D(0)}$ are the donor lifetimes in the presence or absence of an acceptor, respectively.

Other Spectroscopies

Other types of spectroscopic techniques can be used at the single-molecule level. Fluorescence can for instance be excited via a two-photon absorption process, whereby a laser excitation with half the photon energy needed to attain the excited state



Figure 7 Lifetime measurements. (a) Schematic of a lifetime measurement setup. BS: beamsplitter used to deflect part of the incident pulse towards a fast photodiode (FPD); DBS: dichroic beam splitter used to spectrally separate incident from emitted light; BP: bandpass filter further rejecting stray light; APD: avalanche photodiode. For each detected photon, the APD emits a pulse, which is fed to the start input of a time-to-amplitude converter (TAC). A stop pulse from the laser immediately follows it (regularly emitted at a rate of τ_L^{-1}), allowing the measurement of the separation between both pulses. A multichannel analyzer (MCA) histograms the arrival times, resulting in the curves shown in the right part of Figure 2b–d. (b) and (c) Fluorescence images (left panels), corresponding spectra (middle), and fluorescence decays (right) for two molecules located at a PMMA–air interface. The peak emission wavelength λ_p was 560 nm in (b) and 578 nm in (c). Lifetimes were fitted to a single exponential (dotted curves), with decay times of $\tau = 2.56$ ns (b) and 3.20 ns (c). A ensemble measurement of spectrum and fluorescence decay averaged over several hundred of molecules is shown in (d). The ensemble values are $\lambda_p = 565$ nm and $\tau = 2.70$ ns. (b)–(d): Adapted from Macklin JJ, Trautman JK, Harris TD and Brus LE (1996) Imaging and time-resolved spectroscopy of single molecules at an interface. *Science* 272: 255–258. Copyright 1996, The American Association for the Advancement of Science.

is used. However, due to the very low cross-section and quadratic dependence in the incident energy (two simultaneous photons are needed for excitation), an excitation power several orders of magnitude larger than that for one-photon excitation is needed. In compensation, excitation takes place in a much more reduced volume of the sample, reducing the out-of-focus background contribution. The higher power required increases the probability of photobleaching due to the increased probability of



Figure 8 Polarization Measurements. (a) Experiment schematic. **E** is the electric field, making an angle θ with the p polarization axis. The excitation propagates along the z axis, which is also the collection axis. $\boldsymbol{\mu}_a$ and $\boldsymbol{\mu}_e$ are the absorption and emission dipole moments, initially aligned. ν represents the rotational diffusion of the emission dipole during the excited lifetime. The dipole is supposed to be confined in a cone positioned at an angle ϕ_0 projected on the (s, p) plane, and having a half-angle $\Delta\phi_{max}$. A polarizing beam-splitter (PBS) splits the collected emission into two signals I_s and I_p, which are simultaneously recorded by APDs. (b) Simultaneously recorded I_s (black) and I_p (gray) of a molecule rapidly rotating in a liquid. (c) Same data as in (b), but averaged over 11 on-periods. The fit corresponds to a $\Delta\phi_{max}$ close to 90° (freely rotating molecule) and permits the determination of the constrained rotational diffusion parameters. Adapted from Ha T, Glass J, Enderle T, *et al.* (1998) Hindered rotational diffusion and rotational jumps of single molecules. *Physical Review Letters* 80: 2093–2096. Copyright 1998, The American Physical Society.



Figure 9 Single pair fluorescence resonance energy transfer. (a) Jablonski diagram for FRET. Fluorescence energy transfer involves two molecules: a donor D and an acceptor A whose absorption spectrum overlaps the emission spectrum of the donor. Excitation of the acceptor to the lowest singlet excited state is a process identical to that previously described for single-molecule fluorescence (**Figure 6a**). In the presence (within a few nm) of a nearby acceptor molecule, donor fluorescence emission is largely prevented by energy transfer to the acceptor by dipole–dipole interaction. The donor exhibits fluorescent emission following the rules outlined in **Figure 6a**. (b) DNA n constructs used for the FRET distance study. Tetramethylrhodamine (TMR) is attached to one end of the DNA and CY5 is attached to the nth base from the end ($n = 7$, 12, 14, 16, 19, 24 and 27). (c) FRET histograms extracted from time traces for DNAs 7, 12, and 19, as shown in **Figure 2b**. Double Gaussian fits extract numbers for the mean (width) of the higher efficiency peak of 0.95 ± 0.05, 0.75 ± 0.13, and 0.38 ± 0.21, respectively. The peak around 0 efficiency corresponds to bleached or inactive acceptor molecules. (d) Mean FRET efficiencies extracted from FRET histograms plotted as a function of distance for DNA 7, 12, 14, 16, 19, 24, and 27. Distances are calculated using the known B-DNA double helix structure. The solid line corresponds to the expected Förster transfer curve with $R_0 = 65$ Å. (b)–(c) Adapted from Deniz AA, Dahan M, Grunwell JR, *et al.* (1999) Single-pair fluorescence resonance energy transfer on freely diffusing, molecules: Observation of Förster distance dependence and subpopulations. *Proceedings of the National Academy of Sciences USA* 96: 3670–3675. Copyright 1999, The National Academy of Sciences.

photochemical degradation in the long-lived triplet state and the interplay of multiphoton ionization processes.

Although Raman scattering cross-sections ($\sim 10^{-30}$ cm^2) are orders of magnitude lower than the fluorescence cross-section, they can be enormously amplified if the single molecule is trapped in a 'hot spot' of a metallic nanoparticle, giving rise to surface-enhanced Raman scattering (SERS). Highly resolved vibrational information can be recovered, exhibiting much more stable emission than fluorescence. Moreover, this technique can be applied to nonfluorescent molecules. Similarly to fluorescence, the technique can be extended to nonlinear (two-photon) regimes, as in surface-enhanced hyper-Raman scattering and surface-enhanced anti-Stokes Raman scattering. However, since they require the single molecule to be located on rare sites of a metallic particle, these methods have only been applied to fundamental chemical studies of molecular species.

Finally, extending the range of the FRET 'molecular ruler', electron transfer allows measuring distances between an electron donor and an acceptor within a few ångströms (Å), via opening of a nonradiative channel for the relaxation of the electron in the excited state. Lifetime measurements ($\tau = 1/\Gamma = (k_r + k_{nr})^{-1}$ as defined in Figure 6) yield distance information via the electron transfer rate E_{ET}:

$$E_{ET} = k_0 e^{-\beta r}, \qquad [8]$$

where β^{-1} is of the order of one Å and k_0 of the order of 10^{15} s^{-1} are constants characterizing the donor–acceptor pair.

Applications of Single-Molecule Spectroscopy

Single-molecule spectroscopy has already proven to be a useful tool in various domains. The following examples are but a few of an expanding number of applications of SMS.

Molecular Physics

The realization that the fluorescence of a single molecule could be detected with a good SNR over extended periods of time, especially embedded in a crystalline matrix at cryogenic temperature, has led to high-resolution experiments aimed at determining molecular energy levels and transitions. In particular, studies of transitions between sublevels of the triplet state by electron spin resonance (ESR) using superimposed radio-frequency pulses have permitted a precise test of the quantum description of such systems. The dc and ac Stark effect (the shift of a transition energy in the presence of a fixed or alternating electric field) has also been studied in several systems, allowing the symmetry and deformations of the molecule to be determined. The method has been extended to study the photophysics of luminescent polymers (J-aggregates), light-harvesting complexes, green fluorescent proteins (GFP) or semiconductor nanocrystals, and other fundamental systems.

Material Science Studies

Single-molecule photophysical properties are extremely sensitive to their local (nanometer-sized) environment (Figure 1). A precise knowledge of these properties allows using single molecules as sensitive probes of their environment, as illustrated by experiments designed to study the local dynamics of a polymer matrix at the onset of the glass transition (Figure 10).

Molecules of the organic fluorophore Rhodamine 6G (R6G) dispersed within a thin (250 nm) poly(methacrylate) film were observed at temperatures slightly above the melting temperature of the polymer, using a confocal microscope detecting the *s* and *p* polarization of the emitted fluorescence (Figure 8a). Observations are performed under nitrogen atmosphere and at low excitation power (20 nW) in order to prevent oxidation, thus allowing long (several hours) observation time. Each observed R6G molecule exhibits a slow rotational diffusion, sometimes accompanied by lateral or transverse diffusion on a much longer time-scale (Figure 10a). Computation of the autocorrelation function of the emission polarization shows a multi-exponential decay, pointing to a distribution of time-scales of rotational diffusion. A closer look at subwindows of the time trace reveals, however, that the decay comes closer to mono-exponential behavior at shorter time-scales (Figure 10b,c). This study demonstrates that an individual molecule probes an increasing number of different environments over time. At long time-scales, the observable characteristics (such as the autocorrelation function) are similar to those measured on an ensemble of molecules, as expected from the ergodicity hypothesis. At short time-scale, the molecule reveals the local homogeneous and stable characteristic of its nanoenvironment.

Biophysical and Biological Studies

SMS has allowed a reassessment of long-standing questions in biophysics, biochemistry, and biology, by giving scientists the possibility to look at individual building blocks of biological processes: DNA, RNA, proteins and other biomolecules or biomolecular



Figure 10 Polymer dynamics near the glass transition. (a) Fluorescence intensity of a single long-lived Rhodamine 6G molecule in poly(methylacrylate) (PMA) at 291 K detected at orthogonal polarizations (gray: *s* and black: *p* polarizations). The melting temperature of PMA is $T_g = 281$ K. The time trace integration is 1 s. This time trace shows the anticorrelation of both polarizations, characteristic of rotational diffusion of the molecule. Different regimes are observed along the time trace (1–4), which could be due to either a modification of the local 'cage' in which the molecule rotates, or escape of the molecule to another nearby nano-environment. The autocorrelation function of polarization computed over the whole trace (not shown) is well fitted by a model adapted to the nonexponential relaxation of polymers, the Kohlrausch–Williams–Watt (KWW) model:

$$\mathrm{KWW}(t) \propto e^{-(t/\tau)^{\beta}}.$$

with $\tau = 88$ s, $\beta = 0.46$. (b) Correlation functions of subsets 1–4 of the full trace. 1 (squares): $\tau = 15$ s, $\beta = 1.0$. 2 (triangles): $\tau = 112$ s, $\beta = 0.77$. 3 (open circles): $\tau = 90$ s, $\beta = 0.59$. 4 (diamonds): $\tau = 64$ s, $\beta = 0.59$. The β exponent is closer to 1, showing that the rotational diffusion is an unhindered one at short time-scales, converging to the bulk exponent at larger time-scale due to ergodicity. This experiment illustrates changes of environment as the observed molecule diffuses and rotates through the polymer mesh, changes that are hidden in ensemble measurements. (c) Values of β as a function of photochemical survival time in PMA at $T_g + 5$ K. Adapted from Deschenes L and Vanden Bout DA (2001) Single-molecule studies of heterogeneous dynamics in polymer melts near the glass transition. *Science* 292: 255–258. Copyright 2001, The American Association for the Advancement of Science.

complexes formed by association of a few of these molecules.

To simplify the task, some biological molecules are intrinsically fluorescent in their active state, as the cholesterol oxidase (COx) enzyme of Brevibacterium sp., an enzyme that catalyzes the oxidation of cholesterol by oxygen. As a result, it is relatively easy to study the dynamics of this enzyme at the single-molecule level using a confocal setup with enzymes immobilized in an agarose gel (Figure 11). The intervals during which the enzyme is active ('on' state) are followed by intervals during which it is inactive ('off' states). The fluorescence recording of a single enzyme thus appears as a 'blinking' time trace, as shown in Figure 11b. Relevant kinetic parameters can be extracted from the distribution of 'on' and 'off' times. Apart from the usual heterogeneity between enzymes of the same batch characterized by different kinetic parameters for the catalysis reaction, this experiment reveals a dynamic heterogeneity, which shows up for each individually studied enzyme as a tendency for short 'on' times to follow short 'on' times, and for long 'on' times to follow long 'on' times (Figure 11c). This variable behavior of a single enzyme is reminiscent of the variable rotational dynamics of Rhodamine 6G molecules in a polymer matrix (see the previous section), and can be studied only thanks to single-molecule techniques.

Not all biological molecules can be studied in such a convenient way using their intrinsic fluorescence. Several labeling schemes are currently available, which allow quantitative, site-specific labeling of proteins, nucleic acid or lipid molecules with few biochemical side effects.



Figure 11 Single-enzyme dynamics. (a) Fluorescence image of single $\mathrm{CO_x}$ molecules immobilized in a 10-μm-thick film of agarose gel of 99% pH 7.4 buffer solution (8 μm × 8 μm, 4 min scan, 500 nW excitation at 442 nm). The emission is from the fluorescent active site, FAD, which is tightly bound to the center of $\mathrm{CO_x}$. Each individual peak is attributed to a single $\mathrm{CO_x}$ molecule. The intensity variation between the molecules is due to different vertical positions in the excitation volume. (b) Real-time observation of enzymatic turnovers of a single $\mathrm{CO_x}$ molecule catalyzing oxidation of cholesterol molecules. This panel shows a portion of an emission intensity trajectory recorded in 13.1 ms per channel. The trajectory was recorded with a cholesterol concentration of 0.2 mM and saturated oxygen concentration of 0.25 mM. The emission exhibits stochastic blinking behavior as the flavin adenine dinucleotide (FAD), the $\mathrm{CO_x}$ fluorescent active site toggles between oxidized (fluorescent) and reduced (nonfluorescent) states, each on–off cycle corresponding to an enzymatic turnover. More than 500 on–off cycles are recorded in this trajectory. (c) The 2D conditional probability distribution for on-times (x and y) of two adjacent turnovers as derived from the trajectories of 33 $\mathrm{CO_x}$ molecules with 2 mM 5-pregene-3β-20α diol substrate, a derivative of cholesterol. The scales of the x- and y-axes are from 0 to 1 s. A subtle diagonal feature is present, indicative of a memory effect. (d) The 2D conditional histogram for two on-times separated by 10 turnovers for the $\mathrm{CO_x}$ molecules in (c). The diagonal feature vanishes because the two on-times become independent of each other at the 10-turnover separation. The color code in (c) and (d) represents the occurrence (z-axis from 350 (red) to 0 (purple). Adapted from Lu HP, Xun L and Xie XS (1998) Single-molecule enzymatic dynamics. *Science* 282: 1877–1882. Copyright 1998, The American Association for the Advancement of Science.

An example of this versatility has been provided by the labeling of the central part of a rotary protein, $\mathrm{F_1}$-ATPase. In this experiment (not shown), the molecular rotor was labeled with a single fluorophore whose orientation, detected by emission polarization measurements, directly reported the angle of the rotor with respect to the shaft. The small size of the fluorophore guaranteed that the protein motion would not be hindered, contrary to previous experiments, which used much larger reporters (micron-size latex beads or fluorescent actin filaments). This experiment reproduced the previous results, showing that the rotor performed 120° steps (recent work hints at substeps of 90° and 30°).

One of the most promising domains where SMS can be of great importance is the study of protein folding. Doubly labeled proteins can be monitored as they undergo conformational changes, taking advantage of the distance dependence of fluorescence energy transfer (demonstrated for a model DNA system in the section on FRET, Figure 9).

Figure 12 shows one of many examples of such a study, performed on diffusing molecules in solution, a configuration that suppresses uncontrolled effects of nearby surfaces. The enzyme chymotrypsin inhibitor 2 (CI2) is a model system for protein folding, believed to have two clearly distinct folding states, which can be controlled by the concentration of denaturant guanidinium chloride. Using single-pair FRET (spFRET) techniques, it is possible to sort out the proportion of folded and unfolded molecules present at different denaturant concentration (Figure 12b). These measurements yield the same titration curve as obtained by ensemble measurements (Figure 12b) and can give access, under some simplifying assumptions, to the energy landscape of the folding reaction. The additional information provided by spFRET is



Figure 12 Protein folding. (a) Energy landscape for a protein folding reaction represented as a cartoon of the free energy as a function of distance *r* between donor and acceptor. The rugged energy landscape has a funnel shape with three extrema: U (unfolded state), I (intermediate state) and N (folded or native state). In this labeling scheme, donor and acceptor are close to one another in the native, folded state (N), resulting in a high FRET efficiency. There is reduced energy transfer (larger distance) in the denatured, unfolded state (U). (b) Single-molecule protein folding data. Single-pair FRET (spFRET) histograms of the pseudo-wild type enzyme chymotrypsin inhibitor 2 (PWT CI2) at 3, 4, and 6M denaturant (guanidinium chloride). The FRET efficiency exhibits two peaks, one for folded molecules (high FRET) and one for unfolded molecules (low FRET). Population is transferred from folded to unfolded at higher denaturant concentration, as expected from the protein labeling schematically depicted in (a). (c) Ensemble and single molecule denaturation curves for PWT and K17G mutant CI2. Symbols correspond to data; lines showing sigmoidal fits. PWT CI2: ensemble tryptophan fluorescence experiment (circles), ensemble FRET (squares), spFRET (diamonds); K17G mutant CI2 spFRET (triangles). (d) Free energy functions for PWT CI2 at 3, 4, and 6M denaturant. The solid lines represent a smoothing of the data and are only meant to guide the eye. (a) Adapted from Weiss S (2000) Measuring conformational dynamics of biomolecules by single-molecule fluorescence spectroscopy. *Nature Structural Biology* 7: 724–729. Copyright 2000, Nature Structural Biology. (b)–(d) Adapted from Deniz AA, Laurence TA, Beligere GS, *et al.* (2000) Single-molecule protein folding: diffusion fluorescence resonance energy transfer studies of the denaturation of chymotrypsin inhibitor 2. *Proceedings of the National Academy of Sciences USA* 97: 5179–5184. Copyright 2000, The National Academy of Sciences.

the number of molecules in the two different states, providing direct evidence of the two-states model hypothesized from ensemble measurements.

Other biological systems have been addressed using the spFRET approach. Intramolecular spFRET (used in the CI2 study) allows monitoring conformational changes, whereas by labeling two different molecules, intermolecular spFRET permits the detection of association and dissociation events. For instance, spFRET has revealed transient intermediate states in



Figure 13 Single-photon source at room temperature. (a) Antibunching measurement setup. The basic elements are similar to those of a lifetime measurement setup (**Figure 7a**) except that the emitted filtered signal (BP: bandpass filter) is split in two with a 50/50 beamsplitter (BS). Two avalanche photodiodes (APD) detect the arrival of photons. One APD pulse is used as the start signal for a time-to-amplitude converter (TAC), which is stopped by the pulse coming from the second APD. Since the TAC response time is finite, it cannot detect simultaneously arriving pulses. A delay time δ is thus added to the stop signal, such that two photons impinging simultaneously on the two APDs will generate pulses with a separation of δ. If the start APD detects a photon from the previous excitation, the measured delay will be 160 ns $+ \delta$, whereas if the opposite happens, the delay will be $\delta - 160$ ns. (b) Results of measurements on a terrylene molecule (upper chemical structure) embedded in a p-terphenyl (lower chemical structure) at room temperature. Upper panel: histogram of delay measurements shifted by an amount δ. The histogram corresponds to 120 s of recording on an isolated emitting spot. The residual central peak corresponding to coincidence of photon arrival at APD 1 and 2 is the result of background contamination. Lower panel: histogram acquired over 300 s on a background spot. In both measurements, the laser pulse width was 35 ps, each pulse being separated by 160 ns. The lifetime of terrylene is measured to be 3.8 ns, which sets the width of the observed peaks. Excitation is performed at 532 nm. (b): Adapted with permission from Lounis B and Moerner WE (2000) Single photons on demand from a single molecule at room temperature. *Nature* 407: 491–493. Copyright 2000, Nature Publishing Group.

the Tetrahymena ribozyme, which had remained unnoticed in ensemble studies.

Quantum Optics

Low-temperature spectroscopic studies of single molecules have turned into a benchmark for testing predictions of quantum mechanics. In particular, one effect expected for a single quantum emitter is the absence of simultaneous emission of two photons: a fluorescent system which is excited at time t_0 has to emit a photon before it can return to the ground state, and be re-excited at a later time t_1. In conditions where the excitation takes place immediately as the electron returns to the ground state, the time difference $t_1 - t_0$ is of the order of the excited state lifetime, of the order of a few nanoseconds. This antibunching phenomenon was first observed in atoms and ions, and rapidly confirmed by low-temperature SMS. This observation is possible either using continuous wave or using pulsed excitation. In fact, nothing prevents this effect from occurring at room temperature, as demonstrated in Figure 13 for pulsed excitation in which excitation photons are provided as well-separated bunches of a few hundred femtoseconds duration.

In this experiment, a system originally used at low temperature (terrylene in a crystal of p-terphenyl) is excited with a repetition rate of 6.25 MHz. The fluorescence emitted by a single molecule is detected in a confocal setup, split in two and directed to two different detectors (Figure 13a). In this way, the time interval between each pair of photons detected by the two detectors can be precisely measured and histogrammed. The result of this time-correlated single-photon counting approach is the absence of coincidence of two photons (Figure 13b), besides the residual counts due to background contamination.

Since the quantum efficiency of this system is high, the experimental setup can be seen as a periodic single-photon source, with an extremely low probability for the simultaneous emission of two photons. This is precisely the kind of device that is needed for quantum cryptography, in which information encoded in the polarization of a beam should not be sensitive to a 'beamsplitter' attack. Future efforts will undoubtedly build on such 'turnstile' photon sources to move forward into optical quantum computing applications.

Perspectives

SMS is a mature discipline, which will certainly prove to be most useful in domains beyond those previously mentioned. Its relative ease of implementation will certainly attract more scientists of other disciplines to this methodology, each of them having specific goals in mind that are difficult to foresee. The principal advantages of SMS outlined at the beginning of this article will remain, but improvements, especially towards simultaneous acquisition of all the fluorescence parameters described earlier are promising. New detectors will permit the combination of the high time resolution of single-photon counting devices with the large field of view and spectral resolution allowed by two-dimensional detectors. SMS will be associated with single molecule manipulation techniques, to correlate applied forces and molecular conformations. New ways of controlling local fields (electric, magnetic, or others) would take advantage of the non-invasiveness, high-temporal and spatial resolution of SMS to get a direct feedback of events at the nanometer scale. Undoubtedly, SMS will be a major tool in the future of nanotechnology.

List of Units and Nomenclature

Å	Ångström
cm^2	square centimeter
fl	femtoliter
K	kelvin
ms	millisecond
MHz	megahertz
μW	microwatt
nm	nanometer

APD	Avalanche photodiode
DNA	Deoxyribonucleic acid
FRET	Fluorescence resonance energy transfer
NA	Numerical aperture
PMMA	Polymethylmethacrylate
SERS	Surface-enhanced Raman scattering
SMS	Single-molecule spectroscopy
SNR	Signal-to-noise ratio
SNE	Signal-to-background ratio
TIR	Total internal reflection
ZPL	Zero phonon line

See also

Scattering: Raman Scattering.

Further Reading

Basché T, Moerner WE, Orrit M and Wild UP (1997) Single-Molecule Optical Detection, Imaging and Spectroscopy. Weinheim: VCH.

Craig DP and Thirunamachandran T (1998) Molecular Quantum Electrondynamics. An Introduction to Radiation Molecule Interactions. Mineola: Dovers.

Forkey JN, Quinlan ME and Goldman YE (2000) Protein structural dynamics by single-molecule fluorescence polarization. *Progress in Biophysics and Molecular Biology* 74: 1–35.

Kneipp K, Katrun H, Kneipp I, *et al.* (1999) Surface-enhanced non-linear Raman scattering at the single-molecule level. *Chemical Physics* 247: 155–162.

Marcus RA and Sutin N (1985) Electron transfers in chemistry and biology. *Biochimica et Biophysica Acta* 811: 265–322.

Mehta AD, Rief M, Spudich JA, Smith DA and Simmons RM (1999) Single-molecule biomechanics with optical method. *Science* 283: 1689–1695.

Moerner WE and Orrit M (1999) Illuminating single molecules in condensed matter. *Science* 283: 1670–1676.

Nie S and Zare RN (1997) Optical detection of single molecules. *Annual Review of Biophysics and Biomolecular Structure* 26: 567–596.

Plakhotnik T, Donley EA and Wild UP (1997) Single-molecule spectroscopy. *Annual Review of Physical Chemistry* 48: 181–212.

Tamarat P, Maali A, Lounis B and Orrit M (2000) Ten years of single-molecule spectroscopy. *Journal of Physical Chemistry A* 104: 1–16.

Weiss S (1999) Fluorescence spectroscopy of single biomolecules. *Science* 283: 1676–1683.

Xie XS and Trautman JK (1988) Optical studies of single molecules at room temperature. *Annual Review of Physical Chemistry* 49: 441–480.

T

TERAHERTZ TECHNOLOGY

Contents

Coherent Terahertz Sources
Terahertz Physics of Semiconductor Heterostructures

Coherent Terahertz Sources

L Wang, Chinese Academy of Sciences, Beijing, China

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Terahertz (THz) radiation is usually referred to as an electromagnetic wave with frequencies ranging from 1 to a few terahertz ($1\,\mathrm{THz} = 10^{12}\,\mathrm{Hz}$). In the electromagnetic spectrum, terahertz radiation lies between the infrared and microwave, as shown in Figure 1. The techniques for generation and detection of THz radiation bridge photonics and electronics in the sense of the concepts and the techniques discussed below.

Physical quantities corresponding to 1 THz are listed as follows;

- Frequency, 1 THz
- Wavelength, 300 μm
- Wavenumber, 33 cm^{-1}
- Energy, 4.1 meV
- Temperature, 48 K

In this spectral region, there exist many rich physical, chemical, and biological phenomena. For example, many phonon resonance and other elementary excitations in condensed matter fall in this region; many molecular vibrations and rotations occur at THz frequency; conformation-related collective vibrational modes in macromolecules, especially in bio-molecules such as proteins and DNA, also lie in THz frequency. However, the development of THz technique lags far behind that of photonics and electronics, due to lack of feasible, reliable, and economic coherent THz sources. The situation has been rapidly changing since the 1990s. Benefiting from advanced material science and the ultrafast laser techniques, various coherent THz sources are being developed and commercialization is soon to follow. We will introduce these coherent THz sources and their main features, and discuss their generation mechanisms. More details can be found in the listed books and articles in the Further Reading section at the end of this article.



Figure 1 The electromagnetic spectrum with THz radiation sitting between the microwave and the infrared.

Coherent THz Radiation

When a time varying polarization, $\mathbf{P}(\mathbf{r},t)$, is generated in a medium and oscillates at THz frequency, it will radiate a THz wave, $\mathbf{E}(\mathbf{r},t)$, according to Maxwell's equation:

$$\nabla \times \nabla \times \mathbf{E}(\mathbf{r},t) + \frac{1}{c^2}\frac{\partial^2}{\partial t^2}\mathbf{E}(\mathbf{r},t) = -\mu_0 \frac{\partial^2}{\partial t^2}\mathbf{P}(\mathbf{r},t) \qquad [1]$$

or

$$\nabla \times \nabla \times \mathbf{E}(\omega) - \frac{\omega^2}{c^2}\mathbf{E}(\omega) = \omega^2 \mu_0 \mathbf{P}(\omega) \qquad [2]$$

in frequency domain, for a monochromatic wave or a Fourier component of a wave with a finite bandwidth. The properties of THz radiation are determined by the polarization source $\mathbf{P}(\mathbf{r},t)$. Incoherent THz sources exist in blackbody radiation, and are also detected in astronomy observations. If the phase evolution of the THz wave keeps in step, both spatially and temporally, it is called coherent radiation. A coherent THz source is more powerful and useful in spectroscopy, material characterization, imaging, and many other applications. It is clear that a coherent polarization source is first required for generation of a coherent THz wave. In practice, the working media for THz emitting can be free electrons, quasi-free electrons in solids, or bound electrons and other charge oscillations, such as plasmon oscillation, lattice vibration, etc. Classified by the excitation properties, the emitting process can be of resonance or nonresonance. Coherent polarization sources with different features can be created using various excitation techniques under different principles and device configurations, which lead to different coherent THz sources. Here we focus on coherent THz sources, primarily based on photonic techniques, and working in the spectral range from 1 THz to a few THz.

Gas THz Laser

Molecules have many rotational and vibrational energy levels spaced at THz frequency. For polar molecules, the radiative transition between these levels can radiate THz wave. Following the standard laser technology, molecules pumped either optically or electronically can be used as laser gain media for coherent THz wave generation. For THz gas lasers, the very low THz photon energy poses a problem for lasing, because the coherent radiative transition can be disrupted by thermal depopulation and dephasing. An effective population inversion is difficult to set up and maintain. Therefore, it is important to carefully choose working medium and energy levels, as well as the way to excite the molecules. A number of media has been used for THz laser, such as methanol and HCN vapor, working in both continuous wave (CW) and pulsed modes. For example, methanol lasers operate under excitation of the rocking and asymmetric deformation modes of methanol excited by a CO_2 infrared laser. HCN laser is pumped electrically, which needs a large voltage and current to excite the molecules, a long cavity to obtain sufficient gain, and dedicated control of the temperature in the cavity for stable operation.

In general, THz gas lasers can be tuned discretely in thousands of lasing lines, ranging from a few tens to a few hundreds of micrometers, with power output from μW to mW. THz gas lasers have existed since the early 1970s, and are the only commercialized THz lasers to date. They are still subject to development, for less bulky volume, enhanced tunability and efficiency, and reduced costs.

Free Electron THz Laser

A free electron laser (FEL) uses free electrons as working medium, rather than bound atomic or molecular states in a conventional laser. A typical FEL consists of three parts: (i) an electron source that generates an electron beam with high current; (ii) an accelerator to raise the electron energy; and (iii) a lasing cavity. After the electron beam is generated, electrons are first accelerated to a relativistic velocity, typically with energy of hundreds of MeV, and then enter the cavity consisting of end mirrors and a spatially periodic magnets array called a wiggler (Figure 2). Due to the Lorentzean force imposed by the periodic magnetic field, the high-energy electrons move in the cavity along a sinusoidal path, and emit coherent radiation with a wavelength determined by the spacing between magnets and the electron velocity, as well as the magnetic induction. With the feedback provided by the cavity mirrors, electrons are accelerated or decelerated continuously by the optical field, and are bunched via the resonant interaction. The collective motion of the electron bunches radiates powerful coherent synchrotron radiation. In a standard configuration, the wavelength of the radiation can be expressed as:

$$\lambda = \frac{\Lambda}{2\gamma^2}[1 + (k\Lambda B_0)^2/2] \qquad [3]$$

where Λ is the spatial period of the wiggler magnets, γ the Lorentz factor of the electron beam, B_0 the peak magnetic induction, and k a constant. With a suitable



Figure 2 A schematic of THz generation in a free electron laser.

arrangement of the magnet array, as well as other related factors, the facility can work in THz spectral region.

An FEL generates tunable, coherent, high-power THz radiation. It is the most powerful coherent source of THz radiation available. Up to 50 W of average THz power has been generated in the Jefferson Lab recently. The free electron THz laser is becoming an important tools for studying THz radiation and its interactions with condensed matter and biological materials. On the other hand, the FEL is a complicated and expensive facility, and needs dedicated maintenance.

Semiconductor THz Laser

In the twentieth century, semiconductor devices have achieved tremendous success, both in electronic and photonic regime, such as transistors and diode lasers. The semiconductor industry has resulted in revolutionary changes to our world and everyday life. To fill the THz gap between electronics and photonics, great efforts have been made to meet the demand in compact, economic, tunable, and highly efficient THz sources. Encouraging advances have been made since we stepped into the new millennium.

In a semiconductor quantum well, the energy difference between a pair of sublevels can be artificially designed at THz frequency. As early as 1971, the concept of far infrared lasers based on intersub-band transition in semiconductor superlattices was proposed. Although the sublevels can be populated by electrical or optical pumping, the low photon energy at THz frequency causes serious difficulties for lasing, because the two levels sit so close to each other that many thermal processes could destroy the population inversion. Various designs and configurations have been proposed to tackle the problem. An attractive idea is so-called quantum cascade heterostructure. In this kind of device, the electrons are injected into a series of coupled quantum wells electrically. When the electrons are driven by the biased voltage, they can make radiative transition between a pair of sub-bands in a well. Subsequently, electrons enter the next well through resonant tunneling, and so on. However, this kind of device needs the materials of very high quality and suffers severely from fast depopulation of the excited states, even at very low temperatures.

As the advance in material science and unremitting efforts in pursuing the dedicated design of the device structures continued, the real breakthrough came in 2001, when Köhler *et al.* at Pisa demonstrated THz lasing in a quantum cascade heterostructure. Many improvements have been made since then; for example, the idea of using phonon resonance to selectively deplete the population of the lower sub-band has been successful, so that much stabler and robuster population inversion can be set up. The operation temperature has been raised to 136 K, well above the liquid nitrogen temperature, which opens the way for semiconductor THz lasers stepping into many more daily applications. These semiconductor devices are pumped with low voltages and currents at mA levels, and generate narrow bandwidth radiation with mW output at a frequency of a few THz. It is also probable that a four-level lasing system could even working at room temperature.

Another promising device is the p-germanium (Ge) laser developed recently. The Ge laser operates through the electrical excitation of hot holes in p-doped Ge. The laser cavity is formed by polishing the surfaces of the Ge crystal. These lasers could run at 5% duty cycles, with several mW output power. The output wavelength can be continuously tuned from 1 to 4 THz. At the moment, the devices have to operate at 20–30 K and consume about 10–20 W for refrigeration.

It is safe to predict that the feasibility, low cost, and compact semiconductor THz laser will emerge in the near future.

Beside the THz lasers, coherent THz radiation can also be generated by coherently exciting suitable media in other ways. Since the mid-1990s, the development of ultrafast laser techniques has led to two important pulsed coherent THz sources, i.e., photoconductive antenna and optical rectification THz sources. A unique feature of the pulsed coherent sources is broad bandwidth, which is useful in spectroscopic applications. Figure 3 is a typical setup for pulsed THz generation and spectroscopic study, using photoconductive antenna or optical rectification as THz sources.

THz Photoconductive Antenna (PCA)

Different from a conventional antenna working in radio and microwave frequency that are driven directly by electrical current, a photoconductive antenna for THz wave generation works with ultrafast pulsed lasers. When the photoconductive gap is irradiated by an ultrafast laser pulse, photocarriers are generated in the semiconductor. These photocarriers are driven by a DC voltage bias and form a current transient. The antenna couples the electromagnetic field associated with the time varying current into free space, and produces a THz pulse. The THz pulse usually has a duration of a few picoseconds, with a broad frequency bandwidth centered at THz frequency. The output THz power scales with both the optical pulse power and the DC bias field:

$$E_{\mathrm{THz}} \propto \frac{\partial J}{\partial t} \propto \frac{\partial^2 n_{\mathrm{e}}}{\partial t^2} E_{\mathrm{bias}} \qquad [4]$$

The output power, frequency bandwidth, and polarization of the THz radiation depend on the photoconductive features of the semiconductor layer and the geometric structure of the antenna. For an optimal performance, the substrate should have a suitable bandgap for optical interband excitation, a high electron mobility and short carrier lifetime to support an ultrafast current transient, and high dielectric breakdown threshold and to sustain high bias voltage. High-power PCAs have been demonstrated with semi-insulating GaAs, ion-implanted GaAs, and In-GaAs. In the aspects of antenna structures, coplanar strip lines and large aperture emitters are the most effective. Average output power from a good system can reach 30–40 μW.

A broad bandwidth is a special characteristic of a THz source, which is particularly desirable in the spectroscopic study as a coherent probe source. From the property of Fourier transform, we know that the shorter the THz pulse duration, the broader the spectral band. PCAs made of GaAs typically have a useful bandwidth extending from ~100 GHz to 3 THz, which can be extended to 4 THz by tuning the pumping laser wavelength close to the bandedge. Up to 6 THz bandwidths have been reported for PCAs. The pulse duration and, therefore the achievable bandwidth, are ultimately limited by carrier mobility and TO phonon resonant absorption which is around 8.3 THz in GaAs.

In many applications, THz radiation is coupled to free space from the antenna using a closely attached silicon hemispherical lens. This practice increases the system's output and also provides control of the radiation pattern. The radiation pattern for the common dipole antenna is essentially dipolar, with a weak quadrupole component perpendicular to the bias field. In the far-field, the THz beam has a Gaussian cross-section with high-frequency components concentrated in the center.

As the first practical pulsed coherent THz source, PCA has been widely used for many applications in



Figure 3 A typical setup for broadband pulsed THz generation and spectroscopic study with a femtosecond laser as excitation source.

scientific research and material characterization. Combined with commercial ultrafast optical fiber lasers, full functional and self-contained THz spectroscopy systems with PCAs as emitters, have been demonstrated and are under commercialization.

Optical Rectification

Optical rectification is a second-order nonlinear optical effect originating from susceptibility $\chi^{(2)}$, and was first observed in 1962 using two intense monochromatic nanosecond laser pulses. In this process, the interaction between laser and nonlinear optical crystal produces a frequency difference polarization:

$$P(0) = \chi^{(2)} E(\omega_1) E(-\omega_1) \qquad [5]$$

When a nonlinear optical crystal is irradiated by an ultrafast laser pulse, the different frequency components in the laser pulse will be coupled with each other by $\chi^{(2)}$, to induce frequency difference polarizations as:

$$P(\Omega) = \chi^{(2)}(\omega_1 - \omega_2 = \Omega) E(\omega_1) E(-\omega_2) \qquad [6]$$

A femtosecond laser pulse usually has a spectral linewidth of at least a few nm, the induced polarization $P(\Omega)$ has a finite frequency distribution centered at THz frequency in the far field, and results in THz radiation $E_{\mathrm{THz}} \propto \partial^2 P(t)/\partial t^2$.

THz radiation in free space by optical rectification was obtained in the early 1990s. One of the differences from a PCA device is that the THz output by optical rectification scales with both the optical pulse power and the DC bias field, while the THz radiation generated by optical rectification solely results from the incident laser. The optimal performance depends on several factors. The generation efficiency first depends on the magnitude of the $\chi^{(2)}$ and phase-matching condition between the optical and THz pulses. The effective magnitude of the $\chi^{(2)}$ coefficient varies with the crystal cut and orientation. Up to now, the most popular material is ZnTe, for its physical durability and excellent phase matching, when a Ti:sapphire femtosecond laser is used as the excitation source. With a moderately focused optical pump beam and a ZnTe crystal, nW T-ray average power can be generated by optical rectification. In general, the generation efficiency may be increased by increasing the laser power, but there are two factors limiting the effect. First, the incident laser power cannot exceed the damage threshold. Second, other second-order nonlinear processes may compete with the optical rectification, such as second-harmonic generation of the pump beam at high optical flux.

For THz radiation generated by optical rectification, the ultimate bandwidth is primarily determined only by the linewidth of the pump laser pulse. Because it is a nonresonance process in most cases, optical rectification can reach broader bandwidths than PCA. Using ultrashort optical pulses and thin nonlinear crystal, THz pulses have been generated with spectra extending to the mid-infrared, well beyond the phonon band of the materials. Like the photoconductive antenna, optical rectification has become a popular technique to generate coherent broadband THz radiation in various applications. Beside the conventional bulk inorganic crystals, many different media have been used for THz generation, such as organic crystal DAST, biased quantum wells, periodically poled LiNbO3 (PPLN), poled polymers, super-conducting thin films, etc.

Other Coherent THz Sources

When two light sources with slightly different wavelengths interact together with a nonlinear optical crystal, a beating polarization will be generated and will radiate a THz wave. It is called difference frequency generation, or three-wave mixing. Optical parametric processing is another way to generate a THz wave. In this process, a near-infrared pump beam generates a second NIR idler beam in a nonlinear crystal, and THz radiation can be generated from the beating of the pump and the idler. The merit of this technique is the continuous frequency tunability of the THz output, which is valuable in spectroscopic applications, and relatively cheaper nanosecond lasers can be used. If the nonlinear crystal is further placed in a cavity and the idler beam is amplified by feedback from end mirrors, a THz optical parametric oscillator is formed. A number of improvements have been made since the mid-1990s with this kind of device. More recently, THz parametric generation with an injection seeded idler beam has shown a reduced linewidth ($\Delta v/v \approx 10^{-4}$) and a peak THz power of over 100 mW for 3.4 ns pulses. A narrow linewidth combined with reasonable tunability make this kind of THz source attractive in spectroscopic studies.

Besides using photonic techniques, coherent THz radiation can also be generated by electronic techniques through increasing the output frequency of the microwave devices. For example, an electrically driven microwave generator, backward wave oscillator, can generate CW THz radiation up to 2 THz. A backward wave oscillator, running under optimal conditions, can provide up to 300 mW of polarized, narrowband radiation with a limited tunability about 30% of its central frequency.

See also

Imaging: Infrared Imaging. **Lasers:** Free Electron Lasers. **Optical Parametric Devices:** Overview. **Semiconductor Physics:** Infrared Lattice Properties. **Terahertz Technology:** Terahertz Physics of Semiconductor Heterostructures.

Further Reading

Grüner G (1998) *Millimeter and Submillimeter Wave Spectroscopy of Solids*, *Vol. 74 of Topics in Applied Physics*. Berlin: Springer-Verlag.

Kaiser W (1988) *Ultrashort Laser Pulses and Applications*, *Vol. 60 of Topics in Applied Physics*. Berlin: Springer-Verlag.

Khurgin JB (1994) Optical rectification and terahertz emission in semiconductors excited above the bandgap. *Journal of the Optical Society of America B* 11: 2492–2501.

Rullière C (1998) *Femtosecond Laser Pulses*. Berlin: Springer-Verlag.

Saldin EL, Schneidmiller EA and Yurkov MV (2000) *The Physics of Free Electron Lasers*. *Advanced Texts in Physics*. Berlin: Springer-Verlag.

Siegel PH (2002) Terahertz technology. *IEEE Transactions on Microwave Theory and Techniques* 50: 910–928.

Tredicucci A, Gmachl C, Capasso F, *et al.* (2001) Novel quantum cascade devices for long wavelength IR emission. *Optics Materials* 17: 211–217.

Tsen KT (2001) *Ultrafast Physical Processes in Semiconductors*, *Vol. 67 of Semiconductors and Semimetals*. New York: Academic Press.

Terahertz Physics of Semiconductor Heterostructures

R Bratschitsch and K Unterrainer, Technische Universität Wien, Vienna, Austria

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

The terahertz (THz) regime of the electromagnetic spectrum holds promise for a large number of important applications in areas like environmental sensing, quality control, medicine, military applications, astronomy, etc. The development of THz devices has been mainly hindered by the lack of compact sources. In this article we overview the types of tabletop semiconductor sources that are available right now. We focus on the use of pulsed THz sources that are optically excited by femtosecond laser pulses. The generated bursts of THz radiation are extremely useful for time-resolved THz spectroscopy of semiconductor heterostructures.

THz Generation from Semiconductors

The first freely propagating THz pulses using femtosecond lasers were generated in 1984 when Auston *et al.* fabricated a Hertzian dipole antenna. It mainly consists of an electrically biased transmission line structure mounted on a semiconductor, i.e. a photoconductive switch that is triggered by a femtosecond laser pulse (Figure 1). The generated transient photocurrent $J(t)$ emits radiation according to $E(t) \propto \partial J(t)/\partial t$. Since 1989, sapphire half-spheres or refractive silicon lenses have been attached to these dipole antennas, which made it possible to produce collimated THz beams for use in everyday spectroscopic experiments. Today generation and detection of THz radiation by semiconductor photoconductive antennas is widely used. However, most of the antennas are limited to the low-frequency regime of the THz spectrum since they usually have a high-frequency cutoff of about 1–2 THz.

THz generation from semiconductor surfaces was introduced by Zhang in 1990. There are three different physical mechanisms that are responsible for the surface emission of THz radiation. One is the transient current, i.e., the acceleration of photo-generated carriers in the semiconductor surface electric field. This process is accompanied by field induced optical rectification which is often called instantaneous polarization, where the electron–hole pairs are polarized in the dc electric field. Finally, bulk optical rectification as a source of THz radiation can be observed in noncentrosymmetric crystals.

The surface emission intensity can be enhanced by using an externally applied electric field instead of the intrinsic electric field. Until recently, the use of laser amplifiers that optically pump these so-called large-aperture antennas has led to the brightest ultrafast tabletop THz emitters.

Recently, Sarukura and co-workers found that the application of a magnetic field dramatically increases the THz emission from bulk InAs. This led to a re-examination of Zhang's work, in which he reported the magnetic field enhancement in bulk GaAs,



Figure 1 Photoconducting dipole antenna. Reproduced with permission from Gornik E and Kersting R (2001) Coherent THz emission in semiconductors. In: Tsen KT (ed.) *Ultrafast Physical Processes in Semiconductors*, vol. 25, pp. 396. New York: Academic Press.

and to a large number of studies of different types of other semiconductors in various magnetic field geometries. Currently, there is no unified model of the enhancement mechanism(s).

The use of a semiconductor heterostructure by Roskos *et al.* in 1992 (a coupled double quantum well) marked the advent of a new class of semiconductor THz emitters that can be deliberately designed using bandgap engineering. In these devices the quantum nature of electrons in coupled potential wells is used to generate electron wavepackets that tunnel back and forth between different potential wells (Figure 2). The coherent charge oscillation is triggered by a femtosecond laser pulse that has a spectral width that is larger than the separation between the quantized states in the well. In this way a coherent superposition of these levels is created. THz emission from these quantum beats has also been observed from charge oscillations due to light and heavy hole excitons in a quantum well by Planken and co-workers. The concept of quantum beats can even be transferred to the high-THz regime (tens of THz) which was successfully demonstrated by Bonvalet and co-workers. By using an InAs step quantum well they generated THz radiation at a frequency of 30 THz.

Bloch oscillations, one of the fundamental concepts of solid state physics, were predicted in 1934 by Zener. He stated that electrons in a periodic potential under an applied electric field should perform oscillations. Using a quantum mechanical picture, Bloch oscillations can be described as a quantum beat of Wannier–Stark states and in 1993 Waschke *et al.* detected THz emission from these oscillations.



Figure 2 Schematic band diagram of an asymmetric double quantum well structure. A short laser pulse with a spectral width larger than the intersub-band splitting can excite an electronic wavepacket which tunnels back and forth between both wells. Reproduced with permission from Roskos H, Nuss M, Shah J, Leo K, Miller D, Fox A, Schmitt-Rink S and Köhler K (1992) Coherent submillimeter-wave emission from charge oscillations in a double-well potential. *Physical Review Letters* 68: 2216. Copyright (1992) by the American Physical Society.

These heterostructure THz sources are inherently frequency tunable since the energy level spacing can be altered by an applied electric field that tilts the quantum wells. The Bloch frequency is given by:

$$\omega_{\mathrm{Bloch}} = \frac{eFd}{\hbar} \qquad [1]$$

where F is the applied electric field and d is the superlattice period. Unfortunately, these devices suffer from their low emission power.

An alternative concept is the use of collective excitations in semiconductor bulk material or heterostructures. Dekorsy and co-workers showed in 1995 that coherent phonons emit THz radiation when excited by femtosecond laser pulses. In the same year Sha and co-workers studied the absorption changes within an electrically biased GaAs p-i-n structure and found distinct oscillations which they ascribed to another collective phenomenon, namely coherent plasma oscillations of the photogenerated carriers (Figure 3). This explanation was supported by the square-root dependence of the observed frequencies on the photogenerated carrier density which is predicted by a simple oscillator model:

$$\omega_{\mathrm{p}} = \sqrt{\frac{ne^2}{\varepsilon\varepsilon_0 m^*}} \qquad [2]$$

where n is the carrier density, ε the dielectric constant, and m^* the effective mass of the carriers. Fischler and co-workers confirmed this finding and in particular investigated the damping behavior of the plasmons. In 1997, Kersting *et al.* detected THz radiation from



Figure 3 (a) Time-derivative of the charge in electro-absorption versus pump-probe time delay for decreasing fluences (top to bottom respectively); (b) the frequency of the oscillations as a function of fluence. The dashed curve is a square-root function fit. Reproduced with permission from Sha W, Smirl A and Tseng W (1995) Coherent plasma oscillations in bulk semiconductors. *Physical Review Letters* 74: 4273. Copyright (1995) by the American Physical Society.



Figure 4 (a) THz autocorrelation traces for three different doping densities; (b) THz spectra; lines denote the frequencies calculated by formula [2]. Reproduced with permission from Kersting R, Heyman J, Strasser G and Unterrainer K (1998) Coherent plasmas in n-doped GaAs. *Physical Review B* 58: 4553. Copyright (1998) by the American Physical Society.

these p-i-n structures and identified heating of the photogenerated carriers as the origin for the strong damping of the plasma oscillations resulting in a low emission intensity.

This problem can be circumvented by using coherent plasma oscillations of extrinsic charge carriers. These electrons are cold compared to the photo-excited carriers and should undergo less scattering. Kersting *et al.* showed that THz pulses are indeed emitted from coherent three-dimensional (3D) plasma oscillations in n-doped GaAs epilayers. The THz pulses are temporally and spatially coherent with intensities up to 100 nW.

Figure 4 shows the THz emission from three GaAs epilayer samples which have been doped with densities 1.9×10^{15}, 1.7×10^{16}, and $1.1 \times 10^{17}\ \mathrm{cm}^{-3}$. The curves are recorded using an autocorrelation technique: 13 nJ, 100 fs laser pulses at a repetition rate of 80 MHz and a central wavelength of 800 nm are split into two pulses with a Michelson interferometer. Every visible pulse generates a THz pulse in the transmission or pseudo-reflection direction. After collimating and focusing of the THz radiation by parabolic mirrors, the interference of the two THz pulses can be recorded by changing the time delay between the visible pulses (Figure 5). Assuming negligible nonlinear interactions between the two excitation processes, the linear autocorrelation function can be recorded. The spectrum is calculated by simply Fourier transforming (Figure 4b). The experiments are performed at room temperature, and the whole setup is purged with dry nitrogen gas to prevent



Figure 5 THz autocorrelation setup. Reproduced with permission from Kersting R, Heyman J, Strasser G and Unterrainer K (1998) Coherent plasmons in n-doped GaAs. *Physical Reviews B* 58: 4553. Copyright (1998) by the American Physical Society.

water vapor absorption. Although the autocorrelation traces are recorded at the same optical excitation density of $n_{\text{ex}} = 2 \times 10^{16}\ \text{cm}^{-3}$, the emission frequency changes significantly. In addition, the autocorrelation trace of the highly doped structure ($1.1 \times 10^{17}\ \text{cm}^{-3}$) shows multiple oscillations while in the case of the sample with the lowest doping ($1.9 \times 10^{15}\ \text{cm}^{-3}$) the slow oscillation is damped out rather quickly. The frequency behavior of the three different samples can be analyzed from the spectra shown in Figure 4b. The bars indicate the frequency calculated with [2] and setting n equal to the doping density determined by standard Hall measurements. Obviously, the calculated frequencies match very well the experimentally determined ones. This indicates that the THz emission results from a collective oscillation of the extrinsic electrons within the epilayer. This is also supported by the observation that a variation of the excitation density of the photogenerated carriers over two orders of magnitude does not change the THz emission frequency. This is in clear contrast to the experiments with undoped semiconductors where the emission frequency shows a square-root dependence on the optically excited carrier density.

Excitation of the coherent plasma oscillation results from the ultrafast screening of the surface electric field by the femtosecond laser pulse. Before excitation, the doping electrons are confined between the surface electric field and the undoped GaAs substrate (Figure 6). A short laser pulse with an energy above the bandgap of the semiconductor generates electron–hole pairs that screen this surface electric field for a short time. The doping electrons inside the material respond to the change in potential at the surface of the sample leading to the oscillation behavior. A detailed model calculation of the excitation mechanism can be found in Kersting *et al.* (1998). The oscillation frequency – the eigenfrequency of the electron system – is simply the plasma frequency given by the simple formula [2].



Figure 6 Schematic drawing of the 3D plasmon excitation. After Kersting R, Bratschitsch R, Heyman JN and Unterrainer K (1999) Unpublished.

There are two mechanisms that are responsible for the damping of the plasma oscillations. If the doping density is lower than $10^{16}\ \text{cm}^{-3}$ the coherence time of the 3D plasmon is mainly limited by optical phonon scattering. This can be verified by measuring the plasmon damping times at different temperatures and comparing the results with mobility data which show the same tendency. Since optical phonon scattering is suppressed at low temperatures, the THz emission intensity can be substantially increased by cooling the sample. In the high-doping-density regime $>10^{16}\ \text{cm}^{-3}$ the observed damping times are shorter than those expected due to the optical phonon scattering mechanism alone. This is because in this regime impurity scattering is the dominant scattering mechanism.

One way around this problem is the use of a remotely doped structure. In this case the scatterers are not in the same region as the electrons that perform the plasma oscillation (Figure 7). The higher mobility should lead to a longer decoherence time.



Figure 7 Schematic drawing of a modulation-doped PQW. The doped layers are outside the quantum well.



Figure 8 THz autocorrelation signal of a 1400 Å PQW excited by 780 nm laser pulses ($T = 5$ K). Inset: Fourier transform of the recorded autocorrelation. Reproduced with permission from Bratschitsch R, Müller T, Kersting R, Strasser G and Unterrainer K (2000) Coherent THz emission from optically pumped intersubband plasmons in parabolic quantum wells. In: *Ultrafast phenomena XII*. Springer series in Chemical Physics, vol. 66, pp. 204. New York: Springer-Verlag.

For this purpose Bratschitsch *et al.* used modulation doped GaAs/AlGaAs parabolic quantum wells (PQWs), with widths L in the range of 1200–2000 Å and carrier sheet densities n_s of 1.7×10^{11}–5×10^{11} cm^{-2}. The electrons confined within the parabolic potential form a so-called quasi-3D electron system. Figure 8 shows the THz autocorrelation trace of a modulation doped PQW ($L = 1400$ Å, $n_s = 5 \times 10^{11}$ cm^{-2}) excited by 780 nm laser pulses. The density of the optically generated carriers is kept well below the carrier density due to the modulation doping inside the PQW.

The spectrum of the emitted THz radiation (inset of Figure 8) consists of two components: a broad background and a narrow line (FWHM: 0.3 THz) with a center frequency of 2.55 THz. The low-frequency broadband component is found for all the different PQW samples and is independent of the PQW sample structure. It can also be observed at room temperature while the narrowband component completely vanishes. The origin of the broadband component is due to THz generation at the surface of the sample.

The THz emission at 2.55 THz can be observed within a wide range of excitation wavelengths (815–760 nm) above the 819 nm GaAs bandgap ($T = 5$ K). When varying the excitation density over one order of magnitude ($5.6 \times 10^{10} - 6.2 \times 10^{11}$ cm^{-2}), the emission frequency does not change. The narrowband emission results from the oscillation of the carriers inside the PQW. The observed frequency corresponds to the intersub-band plasmon of the PQW. The expected frequency of the intersub-band plasmon is given by

$$\omega_0 = \sqrt{\frac{8\Delta}{L^2 m^*}} \qquad [3]$$

where Δ is the energetic depth of the well, L is the well width, and m^* the effective mass. For the 1400 Å wide PQW the formula yields 2.2 THz for the intersubband plasmon frequency.

The excitation mechanism for the intersub-band plasmon is due to screening of the surface depletion field by the electron–hole pairs injected by the ultrafast laser pulse. In this way the electrons inside the quantum well experience a kick and begin to oscillate with their eigenfrequency (Figure 9). This is supported by the fact that the oscillation can be excited over a large wavelength range of the femtosecond pulses. The onset of intersub-band plasmon emission appears at 815 nm near the 819 nm GaAs bandgap ($T = 5$ K) and can be observed to up to 760 nm. This large range implies that the excitation mechanism is clearly a nonresonant phenomenon, in contrast to the THz quantum beat experiments. Due to ultrafast field screening, a symmetric nanostructure can emit optically driven THz radiation.

The width of the intersub-band plasmon emission line is 0.3 THz (full width at half maximum; FWHM) for the 1400 Å PQW and even 0.2 THz for the 2000 Å PQW sample. The linewidth is a factor of 5 smaller than the smallest linewidth measured for a 3D plasmon emitter. The width of the intersub-band emission is nearly unaffected when increasing the excitation wavelength from near bandgap to approximately 60 nm above bandgap. However, it shows a linear dependence ($5.6 \times 10^{10} - 6.2 \times 10^{11}$ cm^{-2}) on



Figure 9 Symbolic drawing of the excitation mechanism: an oscillation of the carriers in the parabolic potential is initiated by ultrafast field screening. Reproduced from Bratschitsch R, Müller T, Kersting R, Strasser G and Unterrainer K (2000) Coherent terahertz emission from optically pumped intersubband plasmons in parabolic quantum wells. *Applied Physics Letters* 76: 3501, with permission from the American Institute of Physics.

the number of optically excited carriers. These optically injected carriers are added to those from the modulation doping and cause a faster dephasing of the intersubband plasmon oscillation. This linear dependence due to carrier–carrier scattering has also been observed in Wolter's experiments dealing with the dephasing of Bloch oscillations in semiconductor superlattices. The linewidth stays constant up to about 50 K (0.33 THz = 1.36 meV) and then starts to broaden until the sample temperature reaches 150 K where the PQW emission is buried by the surface-generated THz emission. The broadening of the line between $T = 50$ K and $T = 150$ K can be explained by the onset of optical phonon scattering in addition to interface roughness scattering which is the dominant scattering mechanism at low temperatures. The onset and linear increase of the line broadening has also been observed with Fourier Transform Infrared (FTIR) absorption and THz time-domain cross-correlation spectroscopy measurements by Kersting and co-workers.

The combination of the designability of the transition frequency, the narrowband emission, and the absence of any processing of the sample make modulation-doped PQWs attractive and easy-to-use THz emitters.

Other THz emission experiments of heterostructures include the optically pumped emission of THz radiation from grating-coupled intrasub-band (2D) plasmons in a doped single quantum well observed by Sekine and co-workers or optically excited THz emission from coherent plasmons in doped superlattices detected by Bratschitsch and co-workers.

Few-Cycle THz Spectroscopy of Semiconductor Quantum Structures

There are a large number of studies that use few-cycle THz radiation for the investigation of semiconductor bulk materials. The complex index of refraction in the THz regime gives insight into the conductivity (i.e., carrier mobility) of the material. The free carriers that change the index of refraction by Drude absorption can be provided either by doping (n-doped silicon or GaAs) or by photo-excitation. An optical pump-THz probe experiment with undoped GaAs reveals the different intervalley scattering times.

There are compelling reasons to use THz radiation to excite and probe carriers in semiconductor quantum structures. The photon energies are comparable to the sub-band spacings, carrier kinetic energies, and phonon energies. In addition, THz radiation does not generate minority carriers so that the experiments directly probe free carriers rather than excitons.

Heyman *et al.* investigated a modulation-doped GaAs/AlGaAs multiple quantum well ($d = 510$ Å, 10×) with a transition energy between the two lowest sub-bands of 1.5 THz and a carrier density of $n_s = 2.75 \times 10^{10}\ \mathrm{cm}^{-2}$. On top of the sample an aluminum Schottky gate is evaporated and the well is contacted with AuGe alloyed ohmic contacts. The wells can be depleted of carriers by applying a negative gate voltage to the Schottky gate (−10 V gate bias). By modulating the voltage between 0 V and −10 V the response of the 2D electron system can be measured. Otherwise, the recorded signal is dominated by the contribution of the bulk GaAs substrate that dramatically chirps the THz pulse due to its frequency-dependent index of refraction. The THz pulses are coupled into the cleaved edge of the quantum well sample so that the electric field is parallel to the growth direction in order to excite the intersub-band transition. The electrons' response is measured with a cross-correlation technique. Here the THz radiation transmitted through the quantum well is mixed with a short THz pulse emitted from low-temperature grown GaAs to get the desired time resolution in the experiment. This allows the detection of the transmitted signal in amplitude and phase. Figure 10 shows the cross-correlation signal of the QW. The signal from the carriers rises during the first 2 ps in response to the THz field and then continues to oscillate at a constant frequency of 1.5 THz. Due to the femtosecond time resolution in this experiment it is possible to observe the phase of the electrons even during the process of excitation. Initially, the incident THz pulse generates a coherent superposition of states in the first and second sub-band. After the THz driving pulse is over

(>2 ps) the carriers continue to radiate at the intersub-band transition frequency, and the signal is damped out by the free induction decay. Since the amplitude and phase of the radiated electric field is recorded, not only the absorption due to the QW electrons but also the phase shift associated with the absorption can be extracted (Figure 11).

This experiment showed the response of the QW electrons to radiation which is resonant to the intersub-band transition. Using the same experimental technique Kersting *et al.* investigated the response of electrons to a non-resonant excitation of the intersub-band transition. Instead of a square QW, a modulation-doped parabolic quantum well is used in this experiment which has the advantage that the transition frequency is independent of the carrier concentration (Kohn's theorem) and the applied electric field. Furthermore the THz radiation is coupled to the intersub-band transition via a metallic Schottky grating. Figure 12 shows the response of the QW electrons to resonant THz radiation. The electrons follow the driving pulse and continue to radiate at the intersub-band transition frequency. The response to a nonresonant THz pulse is shown in Figure 13. Initially, the electrons inside the QW follow the driving pulse but when the driving pulse has ended a phase jump occurs and the electrons lock to their eigenfrequency and slowly lose their coherence. This behavior can be understood by using time-dependent perturbation theory to solve Schrödinger's



Figure 10 Cross-correlation signal obtained by electrically modulating the charge density in a 510 Å wide quantum well. The THz pulse generates a coherent superposition of the $n = 1$ and $n = 2$ sub-band states. The resulting oscillating polarization radiates and is damped out by the free induction decay. The upper trace shows the incident THz pulse. Reprinted from Unterrainer K, Kersting R, Bratschitsch R, *et al.* (2001) Few-cycle THz spectroscopy of semiconductor quantum structures. *Physica E* 9: 76, with permission from Elsevier.



Figure 11 Change in the absorption coefficient and index of refraction in the quantum well due to the quantum well electrons. Solid points are calculated from the time-domain data. Reproduced from Heyman J, Kersting R and Unterrainer K (1998) Time-domain measurement of intersubband oscillations in a quantum well. *Applied Physics Letters* 72: 644, with permission from the American Institute of Physics.



Figure 12 Resonant excitation: (a) band diagram of an intersub-band transition of 2.2 THz and driving THz field at 2.0 THz; (b) exciting THz pulse (upper curve) and cross-correlation signal (lower curve). Reproduced from Kersting R, Bratschitsch R, Strasser G, Unterrainer K and Heyman J (2000) Sampling a THz dipole transition with sub-cycle time-resolution. *Optics Letters* 25: 272, with permission from the Optical Society of America.



Figure 13 Nonresonant excitation: (a) band diagram of an intersub-band transition of 3.0 THz and driving THz field at 1.6 THz; the oscillation frequency changes from T_1 to T_2; (b) exciting THz pulse (upper curve) and cross-correlation signal (lower curve); (c) spectra of the exciting THz pulse (dotted curve) and cross-correlation signal (solid curve). Reproduced from Kersting R, Bratschitsch R, Strasser G, Unterrainer K and Heyman J (2000) Sampling a THz dipole transition with sub-cycle time-resolution. *Optics Letters* 25: 272, with permission from the Optical Society of America.

equation for a two-level system with an electromagnetic driving field. While the two-level system is treated quantummechanically, the dipole Hamiltonian is used for the incoming THz radiation: $H = H^0 + H'(t)$ and $H'(t) = \mu E(t)$. Making the ansatz $\Psi(t) = a_1(t)\Psi_1 + a_2(t)\Psi_2$ one gets a system of two coupled equations for $a_1(t)$ and $a_2(t)$. They can be decoupled by the condition that the population in the lower level is close to one ($\left\| a_1^2 \right\| \approx 1$) since the THz radiation field is not very strong. Figure 14 shows the result of the model calculation that reproduces the change in frequency as well as the observed phase jump after the driving pulse is over.



Figure 14 Model calculation of the polarization (dotted curve) and experimental data (solid line). Reproduced from Kersting R, Bratschitsch R, Strasser G, Unterrainer K and Heyman J (2000) Sampling a THz dipole transition with sub-cycle time-resolution. *Optics Letters* 25: 272, with permission from the Optical Society of America.

These experiments are all performed in the linear regime but with nonadiabatic excitation conditions (half-cycle THz pulses). The excellent time resolution together with sufficiently high THz intensities can open up a previously unexplored field of quantum optics beyond the slowly varying envelope approximation.

Conclusions

The recent progress in the development of semiconductor sources together with room temperature THz detection techniques (free-space electro-optic sampling) paves the way for the commercialization of THz technology. In particular, spectrally sensitive THz imaging seems to have great potential in medicine and quality control of products.

See also

Semiconductor Materials: GaAs Based Compounds. **Semiconductor Physics:** Outline of Basic Electronic Properties; Quantum Wells and GaAs-based Structures.

Further Reading

Auston DH, Cheung KP and Smith PR (1984) Picosecond photoconducting Hertzian dipoles. *Applied Physics Letters* 45: 284.

Bonvalet A, Nagle J, Berger V, Migus A, Martin J-L and Joffre M (1996) Femtosecond infrared emission resulting from coherent charge oscillations in quantum wells. *Physical Review Letters* 76: 4392.

Bratschitsch R, Kersting R, Müller T, Strasser G, Unterrainer K, Fischler W and Höpfel RA (1999) Coherent THz plasmons in GaAs/AlGaAs superlattices. *Physica B* 272/1-4: 375.

Bratschitsch R, Müller T, Kersting R, Strasser G and Unterrainer K (2000) Coherent terahertz emission from optically pumped intersubband plasmons in parabolic quantum wells. *Applied Physics Letters* 76: 3501.

Chamberlain M (ed.) (1999) *Terahertz Spectroscopy and Applications*, SPIE Proceedings (Europto Series), vol. 3828, pp. 1–454.

Dekorsy T, Auer H, Waschke C, Bakker H, Roskos H, Kurz H, Wagner V and Grosse P (1995) Emission of submillimeter electromagnetic waves by coherent phonons. *Physical Review Letters* 74: 738.

Gornik E and Kersting R (2001) Coherent THz emission in semiconductors. In: Tsen KT (ed.) *Ultrafast Physical Processes in Semiconductors*, vol. 25, pp. 396. New York: Academic Press.

Heyman J, Kersting R and Unterrainer K (1998) Time-domain measurement of intersubband oscillations in a quantum well. *Applied Physics Letters* 72: 644.

Kersting R, Unterrainer K, Strasser G, Kauffmann H and Gornik E (1997) Few-cycle thz emission from cold plasma oscillations. *Physical Review Letters* 79: 3038.

Kersting R, Heyman J, Strasser G and Unterrainer K (1998) Coherent plasmons in n-doped GaAs. *Physical Reviews B* 58: 4553.

Kersting R, Bratschitsch R, Strasser G, Unterrainer K and Heyman J (2000) Sampling a THz dipole transition with sub-cycle time-resolution. *Optics Letters* 25: 272.

Nun MC and Orenstein J (1997) Terahertz time-domain spectroscopy. In: Gruener G (ed.) *Millimeter Wave Spectroscopy of Solids*. Berlin: Springer.

Roskos H, Nuss M, Shah J, Leo K, Miller D, Fox A, Schmitt-Rink S and Köhler K (1992) Coherent submillimeter-wave emission from charge oscillations in a double-well potential. *Physical Review Letters* 68: 2216.

Sarukura N, Ohtake H, Izumida S and Liu Z (1998) High average power radiation from femtosecond laser-irradiated InAs in a magnetic field and its elliptical polarization characteristics. *Journal of Applied Physics* 84: 654.

Sekine N, Yamanaka K, Hirakawa K, Voßebürger M, Haring-Bolivar P and Kurz H (1999) Observation of terahertz radiation from higher-order two-dimensional plasmon models in GaAs/AlGaAs single quantum wells. *Applied Physics Letters* 74: 1006.

Sha W, Smirl A and Tseng W (1995) Coherent plasma oscillations in bulk semiconductors. *Physical Review Letters* 74: 4273.

Shah J (1999) *Ultrafast Spectroscopy of Semiconductors and Semiconductor Nanostructures*. Springer Series in Solid-State Sciences, vol. 115. Berlin: Springer.

Waschke C, Roskos H, Schwedler R, Leo K, Kurz H and Köhler K (1993) Coherent submillimeter-wave emission from bloch oscillations in a semiconductor superlattice. *Physical Review Letters* 70: 3319.

Wolter F, Martini R, Tolk S, *et al.* (1999) Influence of carrier–carrier scattering on intraband dephasing. *Superlattice and Microstructure* 26: 93.

Zhang X-C, Hu B, Darrow J and Auston D (1990) Generation of femtosecond electromagnetic pulses from semiconductor surfaces. *Applied Physics Letters* 56: 1011.

TIME-RESOLVED FLUORESCENCE

Contents

Laser Applications
Measurements in Polymer Science

Laser Applications

B Valeur, Conservatoire National des Arts et Métiers, Paris, France

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Fluorescence is extensively used in physical, chemical, material, biological, and medical sciences, for investigating the structure and dynamics of matter or living systems. After excitation of a fluorescent sample by a short pulse of light, the fluorescence decay is, in the simplest case, a single exponential whose time constant is the lifetime of the excited state of the fluorescent species (i.e., the average time during which these species stay in the excited state). However, interactions of a fluorescent species with its micro-environment often perturb the fluorescence decay so that information on this micro-environment can be obtained. More specifically, when intermolecular photophysical processes (such as electron transfer, proton transfer, energy transfer, excimer, or exciplex formation) occur during the lifetime of the excited state, competition with normal de-excitation results in a fluorescence decay that contains the rate constants for those processes. Consequently, the fluorescence decay is generally a sum of discrete exponentials, or a more complicated function; for example, sometimes the system is characterized by a distribution of decay times. Thus it is of major interest to recover the parameters characterizing the δ-pulse response of a fluorescent sample (i.e., the response to an iznfinitely short pulse of light expressed as the Dirac function δ). With this aim, two time-resolved techniques, pulse fluorometry and phase-modulation fluorometry, are usually employed.

In pulse fluorometry, the sample is excited by a short pulse of light, and the fluorescence response is the δ-pulse response of the sample convoluted by the instrument response. In phase-modulation fluorometry, the sample is excited by modulated light at variable frequency, and the harmonic response of the sample obtained is the Fourier transform of the δ-pulse response. The first technique works in the time domain, and the second technique in the frequency domain. Pulse fluorometry and phase-modulation fluorometry are theoretically equivalent, but the principles of instrumentation are different. In both techniques, lasers are currently used as sources of pulsed or modulated light.

It is the aim of this article to explain the principles of pulse and phase fluorometries using lasers as light sources, and to compare these techniques.

General Principles of Time-Resolved Fluorometry

The principles of time-resolved fluorometry are illustrated in Figure 1. For any excitation function $E(t)$, the fluorescence response $R(t)$ of the sample is the convolution product of this function by the δ-pulse response $I(t)$:

$$R(t) = E(t) \otimes I(t) = \int_{-\infty}^{t} E(t')I(t - t')\,\mathrm{d}t' \qquad [1]$$

In pulse fluorometry, the sample is excited by a short pulse of light and the fluorescence response is recorded as a function of time. If the duration of the pulse is not short with respect to the time constants of the fluorescence decay, the fluorescence response is the convolution product given by eqn [1]: the fluorescence intensity increases, goes through a maximum, and becomes identical to the true δ-pulse response $i(t)$ as soon as the intensity of the light pulse becomes negligible. In this case, data analysis for the determination of the parameters characterizing the δ-pulse response requires deconvolution of the fluorescence response.


Excitation
Response
Dirac
δ(t)
I(t) δ-pulse response e.g. I(t) = Σ_i α_i exp(−t/τ_i)
Pulse fluorometry
Pulse response
E(t), R(t)
R(t) = E(t) ⊗ I(t)
Convolution product of the excitation pulse and the δ-pulse response
0
Time
Variations in intensity as a function of time
Deconvolution and curve fitting in the time domain
Phase fluorometry
A + B cos ωt
a + b cos (ωt − Φ)
Harmonic response characterized by : Φ, M
phase shift : Φ
Modulation ratio : M = m/m0
m0 = B/A m = a/b
Modulation
Phase
1
90°
M
Φ
0
0
Frequency
Variations in Φ and M as a function of frequency
No deconvolution.
Curve fitting in the frequency domain
Recovery of the parameters characterizing the δ-pulse response, e.g: α_i, τ_i
δ-Pulse response
Fourier transform
Harmonic response

Figure 1 Principles of time-resolved fluorometry.

In phase fluorometry, the sample is excited by a sinusoidally modulated light at high frequency. The fluorescence response, which is the convolution product (eqn [1]) of the δ-pulse response by the excitation function, is sinusoidally modulated at the same frequency, but delayed in phase and partially demodulated with respect to the excitation. The modulation ratio M is defined as the ratio of the modulation depth m (AC/DC ratio) of the fluorescence and the modulation depth of the excitation m_0 (see Figure 1). The phase shift Φ and the modulation ratio M characterize the harmonic response of the system. These parameters are measured as a function of the modulation frequency. No deconvolution is necessary because the data are directly analyzed in the frequency domain.

The relationship between the harmonic response and the δ-pulse response can be obtained as follows. When the excitation function is sinusoidal, i.e., of the following form:

$$E(t) = E_0[1 + m_0 \exp(i\omega t)] \qquad [2]$$

where ω is the angular frequency $(= 2\pi f)$, the response of the system can be calculated using eqn [1]. It can then be shown that

$$M \exp(-j\Phi) = \int_0^\infty i(t) \exp(-i\omega t)\, dt \qquad [3]$$

where $i(t)$ is the normalized δ-pulse response according to

$$\int_0^\infty i(t)\, dt = 1 \qquad [4]$$

This important expression shows that the harmonic response expressed as $M \exp(-j\Phi)$ is the Fourier transform of the δ-pulse response.

It is convenient to introduce the sine and cosine transforms P and Q of the δ-pulse response:

$$P = \int_0^\infty i(t) \sin(\omega t)\, dt \qquad [5]$$

$$Q = \int_0^\infty i(t) \cos(\omega t)\, dt \qquad [6]$$

If the δ-pulse response is not normalized according to eqn [4], then eqns [5] and [6] should be replaced by

$$P = \frac{\int_0^\infty I(t) \sin(\omega t)\, dt}{\int_0^\infty I(t)\, dt} \qquad [7]$$

$$Q = \frac{\int_0^\infty I(t) \cos(\omega t)\, dt}{\int_0^\infty I(t)\, dt} \qquad [8]$$

Since eqn [3] can be rewritten as $M \cos\Phi - iM \times \sin\Phi = Q - iP$, it is easy to show that the phase shift and the modulation ratio are given by

$$\Phi = \tan^{-1}\left(\frac{P}{Q}\right) \qquad [9]$$

$$M = [P^2 + Q^2]^{1/2} \qquad [10]$$

For a single exponential decay, the δ-pulse response is

$$I(t) = \alpha \exp(-t/\tau) \qquad [11]$$

where τ is the decay time and α is the pre-exponential factor or amplitude. The phase shift and relative modulation are related to the decay time by

$$\tan\Phi = \omega\tau \qquad [12]$$

$$M = \frac{1}{(1 + \omega^2\tau^2)^{1/2}} \qquad [13]$$

For a multi-exponential decay with n components, the δ-pulse response is

$$I(t) = \sum_{i=1}^{n} \alpha_i \exp(-t/\tau_i) \qquad [14]$$

Note that the fractional intensity of component i, i.e., the fractional contribution of component i to the total steady-state intensity, is

$$f_i = \frac{\int_0^\infty I_i(t)\, dt}{\int_0^\infty I(t)\, dt} = \frac{\alpha_i\tau_i}{\sum_{i=1}^{n} \alpha_i\tau_i} \qquad [15]$$

with, of course, $\sum_{i=1}^{n} f_i = 1$.

Using eqns [7] and [8], the sine and cosine Fourier transforms, P and Q, are given by

$$P = \frac{\omega \sum_{i=1}^{n} \frac{\alpha_i\tau_i^2}{1 + \omega^2\tau_i^2}}{\sum_{i=1}^{n} \alpha_i\tau_i} = \omega \sum_{i=1}^{n} \frac{f_i\tau_i}{1 + \omega^2\tau_i^2} \qquad [16]$$

$$Q = \frac{\sum_{i=1}^{n} \frac{\alpha_i\tau_i}{1 + \omega^2\tau_i^2}}{\sum_{i=1}^{n} \alpha_i\tau_i} = \sum_{i=1}^{n} \frac{f_i}{1 + \omega^2\tau_i^2} \qquad [17]$$

It should be noted that the optimum frequency for decay time measurements using either the phase shift or the modulation ratio is, according to eqns [12] and [13], such that $\omega\tau$ is close to 1, i.e., $f \approx 1/(2\pi\tau)$. Therefore, for decay times of 10 ps, 1 ns and 100 ns, the optimum frequencies are about 16 GHz, 160 MHz and 1.6 MHz, respectively.

In the case of a single exponential decay, eqns [12] and [13] provide two independent ways of measuring the decay time:

– by phase measurements:

$$\tau_{\Phi} = \frac{1}{\omega} \tan \Phi \qquad [18]$$

– by modulation measurements:

$$\tau_{\mathrm{M}} = \frac{1}{\omega}\left(\frac{1}{M^2} - 1\right)^{1/2} \qquad [19]$$

The values measured in these two ways should, of course, be identical and independent of the modulation frequency. This provides two criteria to check whether an instrument is correctly calibrated, by using a lifetime standard whose fluorescence decay is known to be a single exponential.

It should be noted that the measurement of a decay time is fast (a fraction of a second) for a single exponential decay since a single frequency suffices. It is also of interest that a significant difference between values obtained by means of eqns [18] and [19] is compelling evidence for nonexponentiality of the fluorescence decay.

Pulse Fluorometers

The most widely used technique in time domain is the time-correlated single-photon counting technique, preferably called single-photon timing technique (SPT). Time-gated systems are less popular. Streak cameras offer a very good time resolution (a few picoseconds or less) but the dynamic range is smaller than that of the single photon-timing technique. The instruments that provide the best time resolution (a few tens of femtoseconds) are based on fluorescence up-conversion, but they are very expensive and not commercially available. Because of space limitations, only the single-photon timing technique will be presented below.

Principle of the Single-Photon Timing Technique

The basic principle of this technique relies on the fact that the probability to detect a single photon at time t, after an exciting pulse, is proportional to the fluorescence intensity at that time. After timing and recording the single photons following a large number of exciting pulses, the decay of the fluorescence intensity is reconstructed.

Figure 2 shows a schematic diagram of a conventional single-photon counting instrument using a pulsed laser as an excitation source. An electrical pulse associated to the optical pulse is generated (e.g. by a photodiode or the electronics associated to the excitation source) and routed – through a constant-fraction discriminator – to the start input of the time-to-amplitude converter (TAC). Meanwhile, the sample is excited by the optical pulse and emits fluorescence. The optics is tuned (e.g., by means of a neutral density filter) so that the photomultiplier detects no more than one fluorescence photon for each exciting pulse. The corresponding electrical pulse is routed – through a constant-fraction discriminator – to the stop input of the TAC. The latter generates an output pulse whose amplitude is directly proportional to the delay time between the start and the stop pulses. The height analysis of this pulse is achieved by an analog-to-digital converter and a multichannel



Figure 2 Schematic diagram of a single-photon timing fluorometer.

analyzer (MCA), which increases by one the contents of the memory channel corresponding to the digital value of the pulse. After a large number of excitation and detection events, the histogram of pulse heights represents the fluorescence decay curve.

Obviously, the larger the number of events, the better the accuracy of the decay curve. The required accuracy depends on the complexity of the δ-pulse response of the system; for instance, a high accuracy is, of course, necessary for recovering a distribution of decay times.

When deconvolution is required, the time profile of the exciting pulse is recorded under the same conditions by replacing the sample with a scattering solution (e.g., a suspension of colloidal silica (Ludox)).

It is important to note that the number of detected fluorescence photons must be kept much smaller than the number of exciting pulses ($<0.01-0.05$ stops per pulse), so that the probability of detecting two fluorescence photons per exciting photon is negligible. Otherwise, the TAC will take into account only the first fluorescence pulse and the counting statistics will be distorted: the decay will appear shorter than it is in reality. This effect is called the 'pile-up effect'.

Laser Sources for the Single-Photon Timing Technique

Mode-locked dye lasers and titanium-doped sapphire lasers are well suited to the single-photon timing technique: in fact, they can generate pulses over broad wavelength ranges, and the pulse widths are in the femtosecond and picosecond ranges with a high repetition rate. Flash lamps running in air, or filled with gas, can also be used, but the range of excitation wavelengths is limited; they deliver nanosecond pulses, and the repetition rate is not high (10^4–10^5 Hz). Dye lasers require the handling of large volumes of dye solutions which must be replaced when the dye is bleached. In contrast, the Ti:sapphire laser is a solid-state laser that does not have this drawback and delivers shorter light pulses. Moreover, long operational lifetime, operational simplicity, reliability, and broad tunability are distinct advantages. For these reasons, Ti:sapphire lasers have become more popular, and are described below.

Ti:sapphire lasers

Titanium-doped sapphire crystals are obtained by replacing a small fraction of the Al atoms of the host (Al_2O_3) with Ti atoms. When the concentration of Ti is low, the optical quality and the mechanical properties of Ti:sapphire crystals are comparable to those of ruby crystals in ruby lasers. The absorption spectrum of Ti:sapphire crystals exhibits a maximum at 490 nm and a shoulder at 540 nm. Therefore, pumping can be achieved by an Argon ion laser or a green solid-state laser. The emission spectrum ranges from 600 to 1,100 nm. Such a broad emission spectrum results from electronic coupling between the electronic levels of the 3d electrons with the lattice vibrations. Since excited-state absorption is not possible in the spectral region of the pump and the fluorescence spectrum, the tuning range is broad: it extends from 680 to 1,100 nm, i.e., almost over the entire fluorescence spectrum.

The width of the pulses that can be generated by Ti:sapphire lasers ranges from a few tens of femtoseconds to about 100 picoseconds. Commercially available Ti:sapphire lasers can operate either in the femtosecond configuration or in the picosecond configuration. In time-resolved fluorescence experiments using the single-photon timing technique, the instrument response is limited by the time response of the photomultiplier; the shortest width of this response that can be measured with the faster detectors (i.e., microchannel plate photomultipliers) is about 30–40 ps (see below). Therefore, there is no reason to operate the Ti:sapphire laser in the femtosecond configuration. In the picosecond configuration, the pulse width is <2–100 ps.

Figure 3 shows the six-mirror folded cavity design for the picosecond configuration in a Tsunami



Figure 3 Beam path of the laser cavity of the Tsunami Ti:sapphire laser (Spectra Physics) operating in the picosecond configuration (Adapted from the Tsunami brochure with permission of Spectra Physics).


Frequency tripler and doubler
Pulse picker
up to 4 MHz
Ti:sapphire laser
~80 MHz
Argon ion laser or green solid-state laser
240
360
550
720
1,100
λ/nm

Figure 4 Schematics of the excitation system in time-resolved fluorescence experiments.

Ti:sapphire laser (Spectra Physics). A Brewster's angle acousto-optic modulator, driven by a low-power rf source, insures an 80 MHz repetition rate. Consequently, in contrast to standard passive mode-locking systems, the laser can operate for long periods without dropouts or shut-downs. Gires–Tournois Interferometer (GTI) mirror spacing is used for tuning the laser cavity. Wavelength tuning is achieved by means of a two-plate birefringent filter placed within the laser cavity at Brewster's angle. The tuning range depends on the mirror sets that are used. With broadband cavity mirrors, the entire tuning range of Ti:sapphire is covered, i.e., from below 700 nm to greater than 1,000 nm, and changes in wavelength can be made in a matter of minutes.

When pumping with a 10 W argon ion laser, the average output power is about 1.5 W at 800 nm and the pulse energy is about 15 nJ. Argon ion lasers can now be advantageously replaced by cw green solid-state lasers (532 nm) in which the gain medium ($Nd{:}YVO_4$) is pumped by diodes, and a LBO crystal placed inside the cavity ensures frequency doubling. These lasers offer several advantages: the head is compact and does not require external cooling water; it is insensitive to temperature, and thermal equilibration is very rapid.

Since the excited-state lifetime of fluorescent compounds can be as long as several hundreds of nanoseconds, the repetition rate of 80 MHz is too high to let the fluorescence of long lifetime samples vanish before a new exciting pulse is generated. Therefore, it must be limited to a few MHz, thanks to a pulse picker using a Bragg-angle acousto-optic modulator synchronized to the mode-locked 80 MHz pulse train. Selection of pulses from the train can thus be achieved at a maximum pulse selection rate of 8 MHz.

For excitation of fluorescent samples, wavelengths in the visible and UV regions are desirable. Frequency doublers and triplers using LBO and BBO crystals, respectively, have been designed with this aim. The possible tuning ranges are shown in Figure 4. When pumping with a 10 W argon ion laser, the average output powers are about 300 mW and 120 mW for frequency doubling and tripling, respectively.



Figure 5 Example of data obtained by the single-photon timing technique using a Spectra-Physics setup composed of a titanium-sapphire Tsunami laser pumped by an argon ion laser, a pulse selector, and doubling (LBO) and tripling (BBO) crystals. The detector is a Hamamatsu MCP photomultiplier R3809U. The sample is a solution of DANS1 (a derivative of dansylamide) in a mixture CH_3CN/H_2O (60:40 v/v) at pH 0.8. Excitation wavelength: 286 nm. Channel width: 9.8 ps. A: Observation through a bandpass filter (300–370 nm) of the protonated form that undergoes photoinduced deprotonation. B: Observation through a cut-off filter ($\lambda > 400$ nm) of the neutral form; the observed risetime corresponds to the formation of the neutral form from the protonated form. Global analysis of the two curves leads to two time constants: 183 ± 9 ps and 3.01 ± 0.03 ns (Global $\chi^2_R = 1.26$) (Métivier R, Leray I and Valeur B, unpublished results. Métivier R, doctoral thesis, Ecole Normale Supérieure de Cachan, 2003).

With Ti-sapphire lasers and microchannel plate photomultipliers, decay times as short as 10 ps can be measured.

The results of an experiment are shown in Figure 5.

Pulsed diode lasers

Picosecond diode laser heads offer an interesting alternative to mode-locked lasers and are much less expensive. They can produce light pulses as short as 50–90 ps with repetition rates from single shot to 40–80 MHz. Peak powers up to 500 mW can be obtained. However, the main disadvantage is the absence of tunability, and the number of wavelengths is limited: 375, 400, 440, 635 to 1,550 nm. No wavelength below 375 nm is presently available.

Phase-Modulation Fluorometers

In the frequency domain, the phase and modulation measurements can be taken by using either a cw laser and an optical modulator, or the harmonic content of a pulsed laser.

Phase Fluorometers Using a cw Laser and an Optical Modulator

The optical modulator is generally a Pockels cell. Low-power cw lasers are sufficient and not as expensive as pulsed lasers, so that one can afford several lasers of this type in order to get various excitation wavelengths. Available wavelengths from cw lasers are given in Table 1. A Xenon lamp can also be used; however, the optical modulator works better with a cw laser.

Figure 6 shows the schematic diagram of a multifrequency phase-modulation fluorometer using a cw laser and a Pockels cell. A beamsplitter reflects a few percent of the incident light towards a reference photomultiplier (via, or not, a cuvette containing a reference scattering solution). The fluorescent sample and a reference solution (containing either a scatter or a reference fluorescent compound) are placed in a rotating turret. The emitted fluorescence or scattered light is detected by a photomultiplier through a monochromator or an optical filter. The Pockels cell is driven by a frequency synthesizer and the photomultiplier response is modulated by varying the voltage at the second dynode by means of another frequency synthesizer locked in phase with the first one. The two synthesizers provide modulated signals that differ in frequency by a few tens of Hz in order to achieve cross-correlation (heterodyne detection). This procedure offers excellent accuracy because the phase and modulation information contained in the signal is transposed to the low-frequency domain, where phase shifts and modulation depths can be measured with a much better accuracy than in the high-frequency domain.

Table 1 Examples of available wavelengths from low-power cw lasers

Laser	*Wavelength (nm)*
He–Cd	325; 442.5
He–Ne	543.3; 594; 611.9; 632.8
Ar^{+a}	457.9; 476.5; 488.0; 514.5

[a] High-power argon ion lasers can also provide wavelengths of 351.1 and 363.8 nm.



Figure 6 Schematic diagram of a multifrequency phase-modulation fluorometer using a cw laser and a Pockels cell (S: sample; R: reference; PM: photomultiplier).

Practically, the phase delay ϕ_R and the modulation ratio m_R of the light emitted by the scattering solution are measured with respect to the signal detected by the reference photomultiplier. Then, after rotation of the turret, the phase delay ϕ_F and the modulation ratio m_F for the sample fluorescence are measured with respect to the signal detected by the reference photomultiplier. The absolute phase shift and modulation ratio of the sample are then $\Phi = \phi_F - \phi_R$ and $M = m_F/m_R$, respectively.

Figure 7 shows an example of an experiment.

Phase Fluorometers Using the Harmonic Content of a Pulsed Laser

The type of laser source that can be used is exactly the same as that for single-photon timing pulse fluorometry (see above). Such a laser system that delivers pulses in the picosecond range, with a repetition rate of a few MHz, can be considered as an intrinsically modulated source. The harmonic content of the pulse train – which depends on the



Figure 7 Example of data obtained by the phase and modulation technique using a fluorometer is equipped with a cw Omnichrome He–Cd laser (442 nm) and a Pockels cell operating at frequencies ranging from 0.1 to 200 MHz. The sample is a solution of a calcium complex of a crowned merocyanine (DCM-crown) in acetonitrile (observation through a Balzers bandpass filter centered at 581 nm). The solid line corresponds to the best fit with a biexponential decay. Weighted residuals are shown for the best fit with one and two exponentials. The time constants are 1.87 ± 0.04 and 0.35 ± 0.09 ns with fractional intensities of 0.85 and 0.15, respectively. The value of χ_r^2 is 1.01. (Redrawn from Martin MM, Plaza P, Meyer YH, *et al.* (1996) Steady-state and picosecond spectroscopy of Li^+ or Ca^{2+} complexes with a crowned merocyanine. Reversible photorelease of cations. *Journal of Physical Chemistry* 100: 6879–6888, with permission from the American Chemical Society).



Figure 8 Harmonic content of a pulse train. Example of numerical values: $\Delta f = 4$ MHz; $\Delta t = 4$ Ps; $f_L = 44$ GHz.

pulse width (as illustrated in Figure 8) – extends to several gigahertz.

For high-frequency measurements, normal photomultipliers are too slow, and microchannel plate photomultipliers are required. However, internal cross-correlation is not possible with the latter and an external mixing circuit must be used.

The time resolution of a phase fluorometer, using the harmonic content of a pulsed laser and a microchannel plate photomultiplier, is comparable to that of a single-photon timing instrument using the same kind of laser and detector.

Data Analysis

In both pulse and phase fluorometries, the most widely used method of data analysis is based on a nonlinear least-squares method. The basic principle of this method is to minimize a quantity which expresses the mismatch between data and fitted function. This quantity is the reduced chi-square χ_r^2, defined as the weighted sum of the squares of the deviations of the experimental response $R(t_i)$ from the calculated responses $R_c(t_i)$:

$$\chi_r^2 = \frac{1}{\nu}\sum_{i=1}^{N}\left[\frac{R(t_i) - R_c(t_i)}{\sigma(i)}\right]^2 \qquad [20]$$

where N is the total number of data points and $\sigma(i)$ is the standard deviation of the ith data point, i.e., the uncertainty expected from statistical considerations (noise). ν is the number of degrees of freedom ($\nu = N - p$, where p is the number of fitted parameters). The value of χ_r^2 should be close to 1 for a good fit.

In the single-photon timing technique, the statistics obey the Poisson distribution and the expected deviation $\sigma(i)$ is approximated to $[R(t_i)]^{1/2}$ so that eqn [20] becomes

$$\chi_r^2 = \frac{1}{\nu}\sum_{i=1}^{N}\frac{[R(t_i) - R_c(t_i)]^2}{R(t_i)} \qquad [21]$$

In phase fluorometry, no deconvolution is required: curve fitting is performed in the frequency domain, directly using the variations of the phase shift Φ and the modulation ratio M as functions of the modulation frequency. Phase data and modulation data can be analyzed separately, or simultaneously. In the latter case the reduced chi-squared is given by

$$\chi_r^2 = \frac{1}{\nu}\left[\sum_{i=1}^{N}\left[\frac{\Phi(\omega_i) - \Phi_c(\omega_i)}{\sigma_\Phi(\omega_i)}\right]^2 + \sum_{i=1}^{N}\left[\frac{M(\omega_i) - M_c(\omega_i)}{\sigma_M(\omega_i)}\right]^2\right] \qquad [22]$$

where N is the total number of frequencies. In this case, the number of data points is twice the number of frequencies, so that the number of degrees of freedom is $\nu = 2N - p$.

In addition to the value of χ_r^2, it is useful to display graphical tests. The most important of them is the plot of the weighted residuals defined as

$$W(t_i) = \frac{R(t_i) - R_c(t_i)}{\sigma(i)} \qquad [23]$$

where $\sigma(i) = [R(t_i)]^{1/2}$ for single-photon counting data. The fit is satisfactory when the weighted residuals are randomly distributed around zero.

Concluding Remarks

From the instrumental point of view, the latest generations of pulse and phase fluorometers both use pulsed lasers (usually Ti:sapphire lasers) and microchannel plate detectors; only the electronics is different. Since the instrument response is mainly limited by the time response of the detector, the time resolution is the same for both techniques. Moreover, the optical module is identical so that the total cost of instrumentation is similar.

There are, however, significant differences between pulse and phase fluorometers from the methodological point of view. In pulse fluorometry, the single-photon timing technique offers various advantages: direct visualization of the fluorescence decay; high sensitivity; outstanding dynamic range and linearity; and well-defined statistics (Poisson distribution) allowing the accurate weighing of each point in data analysis. In phase-modulation fluorometry, the main advantage is that no deconvolution is necessary, while this operation is often necessary in pulse fluorometry and requires great care in recording the instrument response, especially for very short decay times. Moreover, the short acquisition time for phase shift and modulation ratio measurements at a given frequency is a distinct advantage.

See also

Ultrafast Laser Techniques: Pulse Characterization Techniques.

Further Reading

Alcala JR, Gratton E and Jameson DM (1985) A multifrequency phase fluorometer using the harmonic content of a mode-locked laser. *Analytical Instrumentation* 14: 225–250.

Demas JN (1983) *Excited-State Lifetime Measurements*. New York: Academic Press.

Jameson DM, Gratton E and Hall RD (1984) The measurement and analysis of heterogeneous emissions by multifrequency phase and modulation fluorometry. *Applied Spectroscopy Reviews* 20: 55–106.

Lakowicz JR (ed.) (1991) *Topics in Fluorescence Spectroscopy, Vol. 1: Techniques*. New York: Plenum Press.

Lakowicz JR, Laczko G and Gryczynski I (1986) 2 GHz frequency-domain fluorometer. *Review of Scientific Instruments* 57: 2499–2506.

O'Connor DV and Phillips D (1984) *Time-Correlated Single Photon Counting*. London: Academic Press.

Valeur B (2002) *Molecular Fluorescence. Principles and Applications*, chap. 6. Weinheim, Germany: Wiley-VCH.

Measurements in Polymer Science

T A Smith, University of Melbourne, Melbourne, Australia

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

In this article we explore the use of ultrashort pulsed lasers in time-resolved fluorescence measurements for the study of the dynamics of excimer formation and energy transfer/migration in synthetic aromatic polymers. The temporal profile of monomer and excimer emission, and the use of time-resolved fluorescence polarization approaches are discussed.

The use of lasers in chemistry has most often exploited the high degree of spectral purity achievable with these devices, in both photochemical and high-resolution spectroscopic applications. Through the use of lasers, we also have the ability to generate pulses of light of ultrashort duration (a few femtoseconds) and of incredibly high peak powers (petawatts), characteristics significantly beyond those achievable with conventional (incoherent) light sources. This enables the kinetics of the many photophysical and photochemical processes that occur on ultrafast time-scales with high efficiency within polymers, to be determined through various time-resolved measurements.

These processes are dealt with in detail in specialist photochemistry textbooks and so knowledge of the terms associated with photochemistry and photophysics is assumed (e.g., electronic configurations, orbitals, spin, multiplicity, etc.).

Following the absorption of light, an isolated chromophore will be in one of its excited electronic and vibrational states. Once formed, the excited state of a molecule will only survive for a limited time, with the molecule losing its excess energy to return to a preferred lower energy state (electronic configuration). It can do this through a number of spontaneous, radiative, and nonradiative deactivation processes, each with its own characteristic rate constant k_{ij}. Nonradiative pathways include internal conversion (IC), such as intramolecular vibrational redistribution, and vibrational coupling to the bath, and inter-system crossing (ISC) between singlet and triplet manifolds. Radiative pathways involve the emission of a photon of light, in the form of fluorescence or phosphorescence.

The time the molecule spends in the excited state is determined by the rates of all the pathways that contribute to the overall deactivation of that state. The lifetime, τ, of a singlet state is therefore defined as:

$$\tau = \frac{1}{k_{\mathrm{ISC}} + k_{\mathrm{IC}} + k_{\mathrm{Rad}} + \cdots} = \frac{1}{\sum k_{ij}} \qquad [1]$$

In systems of higher chromophore concentration, such as aromatic-containing polymers, additional, bimolecular pathways are available through which the excess excited state energy may be dissipated, making it rare that a single fluorescence 'lifetime' is observed from polymer systems. The observation of complex (multi- or nonexponential) fluorescence decay profiles sometimes invokes the use of the terms 'average lifetimes' or 'lifetime distributions'.

The complex nonexponential fluorescence decay behavior observed, particularly from polymer systems, has been variously attributed to one or more of the following factors: molecular aggregation (e.g., excimer/exciplex equilibria); acid–base equilibria (e.g., proton transfer); one-, two-, or three-dimensional energy transfer and energy migration (and variations in the singlet energy migration length); electron transfer; molecular motion (translational diffusion, rotational relaxation); vibrational or solvent relaxation; concentration quenching; fluorescent impurities, etc. The kinetics of excimer formation are further complicated by heterogeneity of kinetically distinct monomer and/or excimer species, configurational and conformational influences upon excimer formation, and the time dependence of energy trapping (excimer formation) through nonequilibrium diffusion-controlled processes. Here, we will concentrate on excimer formation and energy migration in synthetic aromatic polymers, as shown schematically in Figure 1.



Figure 1 Schematic representation of some of the photophysical processes in polymers.

Ultrafast Laser Spectroscopic Techniques

A wide range of experimental techniques and instrumentation is available for the study of time-resolved processes in polymers. The most widely used methods rely on the detection of emission from the polymer. Fluorescence-based techniques are popular for investigating time-dependent processes in polymers, since the time-scales involved in many of the photochemical and photophysical processes discussed correspond with the time-scales on which fluorescence occurs (normally on the subpicosecond to nanosecond time-scales). Phosphorescence usually occurs on significantly longer time-scales and therefore is less likely to be competitive with fluorescence or other radiative or nonradiative deactivation pathways under normal conditions. Fluorescence-based techniques are attractive for reporting on a number of time-dependent processes since fluorescence is inherently multidimensional, it can be readily resolved temporally, and fluorescence detection can be extremely sensitive, achieving single photon and single molecule detection levels.

Amongst the most commonly used fluorescence-based techniques are: time-correlated single photon counting (TCSPC, or single photon timing), fluorescence transient digitization, and ultrafast streak cameras. Methods such as transient absorption (flash photolysis) can also provide some details regarding the identity of short-lived species formed following photo-excitation. Other ultrafast laser techniques have been applied to the study of time-dependent processes in polymers in order to achieve higher temporal resolution. So-called pump–probe methods provide the ultimate in time-resolution and can be combined with fluorescence detection through the use of Kerr shutters or ultrafast fluorescence upconversion techniques. Other, more complex pump–probe methods, such as transient grating and multiple pulse photon echo measurements, are potentially very powerful tools in the study of time-resolved processes in polymers.

The generation of short pulses of light can be achieved through numerous mechanisms, including active or passive mode-locking and Q-switching techniques, and superradiance processes (e.g., in nitrogen lasers). Lasers capable of producing short (~ns) pulses of light by Q-switching are usually characterized by high energies per pulse (from μJ up to many hundreds of mJ/pulse) at low (~Hz–kHz) pulse repetition rates. Lasers producing pulses of ultrashort duration (often in the picosecond or femtosecond region) through mode-locking techniques, characteristically operate at high pulse repetition rates (~MHz) and with lower energies per pulse (~nJ/pulse). It should be noted that even pulses of a few nJ energy delivered in ~100 fs, still have peak powers of tens of kW. These high peak powers enable the generation of a range of excitation wavelengths suitable for the study of polymer systems through nonlinear optical wavelength conversion processes, such as second-harmonic generation (SHG) and optical parametric oscillation (OPO) devices.

Excimer Formation

Excimers (or *exci*ted-state di*mers*) are formed when an aromatic molecule, while in its excited electronic state, $^1M^*$, interacts with a second molecule of the same chemical type in its ground electronic state, ^1M. Excimer formation is often observed in concentrated molecular systems such as concentrated solutions and molecular crystals; however, it can also occur in dilute solutions of polymers containing aromatic chromophores, or in the confined environment of solid polymer systems such as homopolymer films.

The structure of excimers in solution is generally thought to be a face-to-face, coplanar, sandwiched, or in some cases, partially eclipsed arrangement of the two constituent aromatic moieties, which attempt to adopt the lowest possible energy configuration, with a separation of 3–4 Å, as depicted in Figure 2. A range of possible excimer configurations may exist rather than just the two extremes.

A feature of excimers is that they have a dissociative ground state (Figure 3), i.e., they do not exist prior to the absorption of light by one monomer chromophore and thus cannot be formed directly without the coming together of the two constituent chromophores within the lifetime of the $^1M^*$. Excimers, being of lower energy than the corresponding excited monomer species and with this dissociative ground state, usually exhibit characteristically



Figure 2 (a) Sandwiched and (b) partially eclipsed excimer configurations.



Figure 3 Schematic potential energy diagram for excimer formation and decay. *r* represents the monomer–monomer separation.

broad, structureless emission to the red of the monomer emission (Figure 4). Upon the emission of fluorescence from an excimer, the complex loses its excess energy and dissociates back to two ground state monomer units (i.e., 2 ^{1}M). Excimers may also dissociate back to a noninteracting pair of ^{1}M* and ^{1}M.

Excimer formation of simple aromatic molecules in solution is often modeled on the kinetic scheme proposed by Birks and co-workers (Figure 5). From Figure 5, if a δ-pulse excitation, represented by $h\nu_{abs}$, is used to produce an initial concentration of excited singlet monomer molecules, $[{}^1M^*]_o$, then such a scheme results in the following rate equations:

$$\frac{d[{}^1M^*]}{dt} = k_{MD}[{}^1(MM)^*] - X[{}^1M^*] \qquad [2]$$

$$\frac{d[{}^1(MM)^*]}{dt} = k_{DM}[{}^1M][{}^1M^*] - Y[{}^1(MM)^*] \qquad [3]$$

where $X = k_{FM} + k_{NM} + k_{DM}[{}^1M^*] = k_M + k_{DM}[{}^1M]$, $Y = k_{FD} + k_{ND} + k_{MD} = k_D + k_{MD}$.



Figure 4 Schematic representation of monomer and excimer emission.



Figure 5 Kinetic scheme for excimer formation where $h\nu_M$ and $h\nu_D$ represent the emission of photons by the monomer and excimer species respectively, k_M and k_D comprise the sum of the various rate constants for all deactivation pathways for the monomer and excimer respectively (excluding k_{MD} and k_{DM}) (e.g., $k_M = k_{FM} + k_{NM}$ where k_{FM} and k_{NM} are the radiative (fluorescence) and nonradiative deactivation rate constants respectively of the monomer).

Solving these rate equations and applying the initial conditions $[{}^1M^*]_t = [{}^1M^*]_o$ and $[{}^1(MM)^*]_o = 0$ at $t = 0$, yields expressions given below for the decay of monomer and excimer fluorescence intensity with time. The emission intensity (monitored in a spectral region in which only the monomer $[{}^1M^*]$ species emits), will have the temporal form given by eqn [4]:

$$\begin{aligned} i_M(t) &= k_{FM}\frac{[{}^1M^*]}{[{}^1M^*]_o} \\ &= \left[k_{FM}\frac{(\lambda_2 - X)}{(\lambda_2 - \lambda_1)}\right]\left[\exp(-\lambda_1 t) + A\exp(-\lambda_2 t)\right] \end{aligned} \qquad [4]$$

where

$$A = \frac{(X - \lambda_1)}{(\lambda_2 - X)},$$

$$\lambda_{1,2} = \frac{1}{2}\left[X + Y \mp \left\{(Y - X)^2 + 4k_{MD}k_{DM}[{}^1M^*]\right\}^{1/2}\right]$$

The emission intensity collected from a spectral region in which the excimer $({}^1[MM]^*)$ species only emits, will have the temporal form given by eqn [5]:

$$\begin{aligned} i_D(t) &= k_{FD}k_{DM}\frac{[{}^1D^*]}{[{}^1M^*]_o} \\ &= \left[\frac{k_{FD}k_{DM}[{}^1M]}{(\lambda_2 - \lambda_1)}\right]\left[\exp(-\lambda_1 t) - \exp(-\lambda_2 t)\right] \end{aligned} \qquad [5]$$

If excimer formation follows Birks' scheme, then the decay profile of the monomer fluorescence should therefore be described by the sum of two exponential decay terms, and the excimer emission by an exponential growth term and a decay term (Figure 6). Only two decay constants, λ_1 and λ_2, should be required to fit both the monomer and excimer fluorescence profiles successfully. This is often not observed, which has led to the introduction of more complex interpretations.

In synthetic aromatic polymers, the effective local concentration of the aromatic molecules can be high while the concentration of polymer chains in solution may be very low. This means that excimer formation can be significant in such polymers, even in dilute solution. In fact, in some polymers the emission is dominated by excimers over monomers. The fact that the excimers are of lower energy than the corresponding excited monomer species also means that they can act as effective traps of excitation energy that might be migrating/relocating within a polymer chain as discussed below.



Figure 6 Examples of (a) monomer and (b) excimer fluorescence decays.

Excimer formation in solutions of aromatic polymers is generally thought to proceed via a complicated route that may involve a combination of electronic energy transfer and migration, segmental rotation, and chromophore diffusion. It is believed that energy migrates along a polymer chain until sites suitable for excimer formation are encountered, at which point the energy is trapped. A number of mechanisms for the formation of suitable excimer sites in polymers are then conceivable. These include:

(i) interactions between chromophores belonging to different chains (this *inter*molecular excimer formation is highly concentration dependent);
(ii) interactions between two chromophores far removed from each other, but on the same chain. This necessitates mainchain conformational changes and side group motions during the excited state lifetime, so as to bring both molecules together;
(iii) near neighbor interactions (c.f. Hirayama's '$n = 3$' rule). The configuration required for excimer formation need not exist prior to excitation provided that the two constituent groups can attain the required geometry within the lifetime of the excited chromophore; or
(iv) preformed sites, suitable for excimer formation, present in the polymer before the initial absorption of light occurs. These may be formed by interactions between nearest neighbor chromophores or between two chromophores on loops of the same, or different chains in cases where chain motion is restricted.

The first two of these mechanisms depend upon segmental motion of the polymer chain and the third mechanism may depend upon rotation of the chromophore/s to adopt the close proximity and optimum orientational configuration required for excimer formation. In solution, this may be, at least partially, diffusion-controlled, causing a dominant complicating factor in the kinetics of excimer formation in polymeric systems. One approach is therefore to substitute a time-dependent expression for the rate coefficient of excimer formation, $k_{\mathrm{DM}}(t) = A + B/\sqrt{t}$, (based on the Einstein–Smoluchowski diffusion theory), for k_{DM}, into the rate equations. Such an approach produces the following expression for the time dependence of the monomer fluorescence, $I_{\mathrm{M}}(t)$ in the presence of diffusion-controlled excimer formation and the absence of excimer back dissociation:

$$I_{\mathrm{M}}(t) = A \exp\left\{ -at - b\sqrt{t} \right\} \qquad [6]$$

In some cases, such as when excimer back dissociation cannot be neglected, more complex functional forms have been derived, such as:

$$I_{\mathrm{M}}(t) = A \exp\left\{ -at - b\sqrt{t} \right\} + B \exp\left\{ -t/\tau \right\} \qquad [7]$$

Similar expressions can be derived for the time dependence of the excimer fluorescence, $I_{\mathrm{E}}(t)$. More detailed expressions for the term $k(t)_{\mathrm{DM}}$, involving the complete form of the diffusion rate coefficient, have also been used in such approaches.

A related approach is the concept of 'convolution kinetics', in which the intimate dependence of excimer formation upon the monomer decay is emphasized. Once formed, the excimer is assumed to decay exponentially. The excimer fluorescence temporal profile is predicted to take the form:

$$I_{\mathrm{E}}(t) = k_1(t) I_{\mathrm{M}}(t) \otimes \exp\left(\frac{-t}{\tau} \right) \qquad [8]$$

where $\otimes$ represents the convolution integral and $I_{\mathrm{E}}(t)$ and $I_{\mathrm{M}}(t)$ are the measured decay profiles in the excimer and monomer emission regions respectively.

Electronic Energy Transfer, Energy Migration and Trapping

In polymers the high local concentration of chromophores makes additional deactivation pathways competitive with the other photophysical processes.The excess energy may transfer from the excited fluorophore of interest to a lower energy chromophore. Three of the more common possible mechanisms, through which energy transfer can occur, are:

(i) *Radiative* ('*trivial*') – involves the reabsorption of donor emission by an acceptor chromophore.

(ii) *Resonance* (*Dipole–Dipole*, *Förster*) – long-range (15–100 Å), nonradiative, single-step energy transfer process arising from Coulombic (dipole–dipole) interactions between an excited-state donor chromophore, D*, and an initially unexcited acceptor, *A*. Förster derived a statistical expression for the (first-order) rate constant, for such a process, considering three-dimensional, dipole–dipole interactions between stationary molecules:

$$k(R)_{\mathrm{D}^*\to\mathrm{A}} = \frac{9000\kappa^2\phi_\mathrm{o}\ln 10}{128\pi^5\eta^4 N\tau_\mathrm{D}R^6}\int_0^\infty \frac{f_\mathrm{D}(\bar{\nu})\varepsilon_\mathrm{A}(\bar{\nu})}{\bar{\nu}}\mathrm{d}\bar{\nu} = \frac{1}{\tau_\mathrm{D}}\left(\frac{R_\mathrm{o}}{r_\mathrm{D}}\right)^6 \quad [9]$$

where R is the donor–acceptor distance, ϕ_o is the quantum yield for emission from the donor in the absence of acceptor molecules, η is the refractive index of the solvent, τ_D is the lifetime of the donor excited state (reduced by the onset of electronic energy transfer), N is Avogadro's number, κ is a constant dependent on the mutual orientation of the donor and acceptor molecules, and the integral term is a measure of the spectral overlap between the donor emission profile, $f_\mathrm{D}(\bar{\nu})$ (in quanta cm^{-1} and normalized to unit area) and the acceptor absorption profile, $\varepsilon_\mathrm{A}(\bar{\nu})$ (converted to molar extinction coefficients and measured on a wavenumber scale). R_o is the critical transfer distance, at which the probability of resonance transfer, $k(R)_{\mathrm{D}^*\to\mathrm{A}}$, is equal to the probability of spontaneous decay, $1/\tau_\mathrm{D}$.

(iii) *Exchange mechanism* – also a nonradiative, single-step process but involves the exchange of electronic excitation when the donor and acceptor are close enough so that their electron clouds overlap. Consequently it only operates over small distances. Dexter has derived a rate expression for exchange energy transfer, again assuming that the donor and acceptor molecules are stationary:

$$k_{\mathrm{D}^*\to\mathrm{A}} = \left(\frac{2\pi}{\hbar}\right)Z^2\int f_{\mathrm{D}^*}(\bar{\nu})\varepsilon_\mathrm{A}(\bar{\nu})\mathrm{d}\bar{\nu} \quad [10]$$

where $Z^2 = K^2\exp(-2R/L)$ and K and L are simply constants.

It has been clearly demonstrated that energy transfer, from pendant aromatic monomer units to chemically bound acceptor chromophores, can occur with high efficiency and is influenced significantly by polymer structure and conformation.

In addition to energy transfer between D* and A (being different chemical species), more than one exchange of excitation energy between chemically and spectroscopically identical chromophores, attached by covalent bonds to a polymer chain, can occur. A single step between identical units is still termed energy transfer, while more than one such step in a sequence would constitute intramolecular energy migration.

Energy migration is a long-range process, thought to occur via a series of energy transfer steps occurring between chromophores, either: (i) along the polymer chain (often the adjacent groups); (ii) across loops in a single polymer chain; or (iii) across different polymer chains. The migration continues until either a trap site is encountered or one of the chromophores excited in the migration process deactivates spontaneously. Each step is believed to occur with a probability defined by the exchange or Förster mechanisms, but since the energy transfer occurs between donor and acceptor groups, which are of the same type, the spectral overlap integral involved in both mechanisms will usually be small. The distances over which such energy transfer can occur therefore cannot be large and typically takes values of <10–20 Å. It is worth noting that many authors consider the energy to migrate as an incoherent exciton (where the term exciton is used in a much looser sense than is customary among solid-state physicists).

Long-range energy migration can only occur by energy transfer from the initially excited chromophore to ground state chromophores of the same, or lower, energy. If energy transfer is favorable between one chromophore and another of the same energy, then back transfer to the initially excited chromophore is also highly probable. When there is a change in the emission and absorption dipole orientations, caused by rotation of the chromophores relative to one another on the time-scale of the energy transfer step, or the transfer is to a chromophore of significantly lower energy, then the probability of energy transfer back to the original chromophore might be reduced. The lower energy chromophores on the polymer chain may therefore act as 'traps' of the excitation originally absorbed by a higher energy chromophore, even in the absence of excimer energy trap sites.

Various approaches have been proposed for modeling the kinetics of energy migration. One can consider the time-dependent nature of each energy transfer step of the migration process, and introduce a time-dependent rate coefficient for each step of the energy migration process, $k_\mathrm{DD}(t)$. The form for $k_\mathrm{DD}(t)$ by Sienicki *et al.*, is given by eqn [11], which leads to nonexponential functions predicted for the ensemble averaged probability that an originally excited donor molecule is still excited at time t:

$$k_{\mathrm{DD}}(t) = \left(\frac{\Delta}{n}\right)\gamma_{\Delta} c_{\mathrm{D}} \Gamma(1 - \Delta/n)\left(\frac{t}{\tau_{\mathrm{OD}}}\right)^{\Delta/n - 1} \qquad [11]$$

where $\Delta(=1,\ 2,\ 3)$ is the dimensionality of the medium, $n(=6,\ 8,\ 10,\ldots)$ is the order of the interaction, τ_{OD} is the lifetime of the donor fluorescence, $\Gamma(x)$ is the gamma function, γ_{Δ} is a constant dependent upon Δ and c_{D} is the donor concentration.

Energy migration has also been considered as a diffusion-like process, and the Smoluchowski diffusion theory adopted. The rate coefficient for energy migration, $k(t)_{\mathrm{EM}}$, is then expressed in a form similar to the time-dependent rate coefficient for partially diffusion-controlled reactions (eqn [12]). In this type of treatment, the rate of change of the concentration of excited monomer chromophores, $^1\mathrm{M}^*$, is assumed to be given by eqn [13]:

$$k(t)_{\mathrm{EM}} = 4\pi N'_{\mathrm{A}} R D \rho\left[1 + R\rho(\pi D t)^{-1/2}\right] \qquad [12]$$

$$\frac{\mathrm{d}[^1\mathrm{M}^*]}{\mathrm{d}t} = I_{\mathrm{o}} - \left(\frac{1}{\tau_{\mathrm{o}}} + k(t)_{\mathrm{EM}}\right)[^1\mathrm{M}^*] \qquad [13]$$

In these expressions, τ_{o} is the reciprocal of the sum of the rate constants for radiative and nonradiative deactivation, ρ is the reaction probability per collision, R is the interaction distance, and N'_{A} is the number density of the energy acceptors or traps ($N'_{\mathrm{A}} = NC_{\mathrm{A}}$, with the concentration of acceptors, C_{A}, in mol cm^{-3}). D is the mutual diffusion coefficient which can be replaced by a migration coefficient, Λ, R can be replaced by the Förster critical transfer distance, R_{o}, and the reaction probability, ρ, can be set to 0.5 (since R_{o} is the distance at which the probability of energy transfer is 0.5). This leads to a simplified expression for $k(t)_{\mathrm{EM}}$, which can be substituted into eqn [13], to produce an expression (eqn [14]) for the monomer decay:

$$I(t) = A\exp\left(-\left(\frac{1}{\tau_{\mathrm{o}}} + 2\pi N'_{\mathrm{A}} R_{\mathrm{o}} \Lambda[^1\mathrm{M}^*]\right)t - 2N'_{\mathrm{A}} R_{\mathrm{o}}^2 (\pi\Lambda)^{1/2}[^1\mathrm{M}^*]\sqrt{t}\right) \qquad [14]$$

Yokota and Tanimoto have also developed a statistical representation of Förster's theory and derived an expression for dipole–dipole transfer in a fluid medium in which the distribution of excited-state donor and acceptor molecules is determined, both by diffusion and by the decay and transfer of the donor excited state. According to the Yokota and Tanimoto approach, the decay law is approximated by the expression:

$$I(t) = A\exp\left\{\frac{-t}{\tau_{\mathrm{o}}} - 2B\delta\left(\frac{-t}{\tau_{\mathrm{o}}}\right)^{1/2}\right\} \qquad [15]$$

where $\delta = [\mathrm{C}]/[\mathrm{C}]_{\mathrm{o}}$ (C_{o} is the critical molar concentration of acceptor molecules given by: $[\mathrm{C}_{\mathrm{o}}] = 3000/2\pi^{3/2} N R_{\mathrm{o}}^3$, and B is a complex, time-dependent function given by: $B = (1 + 10.87x + 15.5x^2/1 + 8.743x)^{3/4}$ with $x = D\alpha^{-1/3} t^{2/3}$, $\alpha = R_{\mathrm{o}}^6/\tau_{\mathrm{o}}$ and D is the 'diffusion coefficient' representing energy migration.

Emission depolarization is often exploited in the study of energy migration in polymers. Only molecules with some vector component of their absorption transition dipole lying parallel to the plane of polarization of the incident radiation, will absorb incoming radiation. In the absence of angular motion of the absorbing chromophore within the lifetime of the excited state, emission from the same chromophore will also be highly polarized; however, upon each step in the energy migration process, some loss of polarization will be incurred (Figure 7). The extent of depolarization of emission is usually referred to by the term fluorescence anisotropy, $r(t)$ (eqn [16]):

$$r(t) = \frac{I_{\parallel}(t) - I_{\perp}(t)}{I_{\parallel}(t) + 2I_{\perp}(t)} \qquad [16]$$

The rate of energy migration can be estimated directly through observation of the time-dependent decay of $r(t)$ in the absence of other fluorescence depolarizing processes, such as molecule rotation (Figure 8).

One of the important properties which characterizes excitation energy transport in a system of n identical molecules, which are distributed randomly in space, is the Green function, $G(r, t)$. The Green function can be thought of as the time-dependent probability of finding an excitation at position r on the polymer chain at time t. It has been shown that the overwhelming contribution to fluorescence polarization is due to fluorescence from the sites that were initially excited. Thus, $G^{\mathrm{s}}(r, t)$ is directly related to the fluorescence anisotropy if the polarization memory of secondary excited molecules can be neglected. The $r(t)$ for donor–donor energy transfer is then given by:

$$r(t) = \alpha r_{\mathrm{rot}}(t) G^{\mathrm{s}}(t) \qquad [17]$$

in which r_{rot} describes the anisotropy in the absence of energy transfer, i.e., in the presence of chromophore



Figure 7 Schematic representation of energy migration. θ is the inherent angle between the donor emission (dotted arrow) and acceptor absorption (solid arrow) transition dipoles of the chromophore (a) orthogonal donor emission and acceptor absorption dipoles – no energy transfer/migration, emission depolarized only due to θ. (b) some vector component of the absorption dipole of the acceptor is parallel with that of the donor emission dipole – this and subsequent energy transfer steps can occur resulting in loss of emission polarization.



Figure 8 Temporal decays of $r(t)$ from (a) a polymer in which emission depolarization due to energy migration is complete on ultrafast time-scales, and (b) a polymer in which the rate of energy migration has been inhibited. Emission collected from polymers in frozen glass to exclude polymer motion contributions to emission depolarization.

rotation only, and α is the anisotropy from time-independent sources of depolarization.

The determination of the functional form of $G^s(r,t)$, resulting from excitation energy migration in polymer systems, is a challenging theoretical problem to which a number of approaches have been applied. The Gochanour, Anderson and Fayer approach has had some success in arriving at an expression for $G^s(r,t)$, represented as the time decay of emission polarization curves.

Polymeric systems that undergo energy migration, yet contain no excimer forming or other nonmonomeric, energy-trapping sites, are rare. In the presence of singlet energy traps, the problem can be treated as being analogous to energy transfer (via the Förster mechanism), following a diffusive process in a similar manner to that described above.

Fredrickson and Frank have derived expressions for the temporal decays of the monomer and excimer fluorescence when one-dimensional electronic singlet energy migration is the major excimer-forming path, and segmental rotation and chromophore diffusion are considered. The Fredrickson and Frank model assumes inherently that excimers are formed predominantly via a nearest-neighbor mechanism, where rapid energy migration is at least an order of magnitude faster than any competing rotationally sampled pathways. The expressions for the fluorescence decay of both the monomer, $I_M(t)$, and excimer species, $I_E(t)$, are highly nonexponential, with the expression for $I_M(t)$ being given by eqn [18]:

$$I_M(t) = Q_{fm} k_m (1-q)^2 \times \exp[(4q^2 W - k_m - k_{rot})t] \operatorname{erfc}[2q(Wt)^{1/2}] \quad [18]$$

In eqn [18], Q_{fm} is the quantum efficiency for monomer fluorescence and k_m is a rate constant, which encompasses the total rate of monomer decay by radiative and nonradiative pathways in the absence of energy migration and rotational sampling. Similarly, k_{rot} represents the rate at which an excited monomer is transformed into an excimer by segmental rotation. The parameter W represents the rate constant for nearest-neighbor electronic energy transport between the donor (monomer) chromophores, averaged over both the transition moment orientation and the interchromophore separation associated with each dyad.

Energy transfer from pendant aromatic monomer units to a specific chemically bound acceptor chromophore can occur in some polymers following energy migration. This phenomenon is known as the ‘antenna effect’, which has commercial applications such as in the sensitization of photo-oxidation–reduction, i.e. reactions, in the stabilization of polymers against photodegradation or in the modeling of photosynthesis by light harvesting. The kinetic behavior of such processes is yet to be modeled definitively, but the approaches discussed above (and others) have been used with varying degrees of success to date.

List of Units and Nomenclature

Ångstrom (Å)	10^{-10} m
chromophore	An aromatic molecule that absorbs (and may emit) light
exciton	An excited state localized on a particular chromophore at any given time
femtoseconds	10^{-15} s
intermolecular	Occurring between molecules or polymer chains
intramolecular	Occurring within a single molecule or polymer chain
petawatts	10^{15} W
δ-pulse excitation	Excitation by an infinitely short laser pulse

See also

Chemical applications of lasers: Non-linear spectroscopies. **Lasers:** Excimer Laser. **Optical Parametric Devices:** Optical Parametric Oscillators (Pulsed). **Spectroscopy:** Second Harmonic Spectroscopy.

Further Reading

Andrews DL and Demidov AA (1999) *Resonance Energy Transfer*. New York: Wiley.

Birks JB (1970) *Photophysics of Aromatic Molecules*. London: Wiley-Interscience.

Fleming GR (1986). *Chemical Applications of Ultrafast Spectroscopy*, vol. 13. New York: Oxford University Press.

Fredrickson GH and Frank CW (1983) Nonexponential transient behavior in fluorescent polymeric systems. *Macromolecules* 16: 572–577.

Ghiggino KP and Smith TA (1993) Dynamics of energy migration and trapping in photoirradiated polymers. *Progress in Reaction Kinetics* 18: 375–436.

Gochanour CR, Andersen HC and Fayer MD (1979) Electronic excited state transport in solution. *Journal of Chemical Physics* 70: 4254–4271.

Guillet JE (1985) *Polymer Photophysics and Photochemistry: An Introduction to the Study of Photoprocesses in Macromolecules*. New York: Cambridge University Press.

Lakowicz JR (1999) *Principles of Fluorescence Spectroscopy*, 2nd edn. New York: Plenum.

O’Connor DV and Phillips D (1984) *Time-Correlated Single Photon Counting*. London: Academic Press.

Sienicki K, Itagaki H and Mattice WL (1989) On the theory of concentration depolarization of fluorescence in one- and two-component systems for multipole interactions in one, two, and three dimensional medium. *Journal of Chemical Physics* 91: 4515–4521.

Van der Meer BW, Coker G and Chen S-YS (1994) *Resonance Energy Transfer: Theory and Data*. New York: VCH.

Van Hecke GR and Karukstis KK (1998) *A Guide to Lasers in Chemistry*. Boston, MA: Jones and Bartlett.

Yokota M and Tanimoto O (1967) Effects of diffusion on energy transfer by resonance. *Journal of the Physics Society of Japan* 22: 779–784.

TOMOGRAPHY

Contents

Optical Coherence Tomography
Tomography and Optical Imaging

Optical Coherence Tomography

S A Boppart, University of Illinois, Urbana, IL, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical coherence tomography (OCT) is an emerging imaging technique for a wide range of biological, medical, and material investigations. OCT was initially developed for imaging biological tissue because it permits the imaging of tissue microstructure *in situ*, yielding micron-scale image resolution without the need for excision of a specimen and tissue processing. OCT is analogous to ultrasound B-mode imaging except that it uses low-coherence light rather than sound and performs cross-sectional imaging by measuring the backscattered intensity of light from structures in tissue. The OCT image is a gray-scale or false-color two-dimensional representation of backscattered light intensity in a cross-sectional plane. The OCT image represents the differential backscattering contrast between different tissue types on a micron scale. Because OCT performs imaging using light, it has a one to two order-of-magnitude higher spatial resolution than ultrasound and does not require contact with the specimen or sample.

OCT was originally developed and demonstrated in ophthalmology for high-resolution tomographic imaging of the retina and anterior eye. Because the eye is transparent and is optically accessible, it is well suited for diagnostic OCT imaging. OCT is promising for the diagnosis of retinal disease because it can provide images of retinal pathology with 10 micron resolution, almost one order-of-magnitude higher than previously possible using ultrasound. Recently, OCT has been applied for imaging in a wide range of nontransparent tissues. In tissues other than the eye, the imaging depth is limited by optical attenuation due to scattering and absorption. Ophthalmic imaging is typically performed at 800 nm wavelengths. However, because optical scattering decreases with increasing wavelength, OCT imaging in nontransparent tissues is possible using longer near-infrared wavelengths. In most tissues, imaging depths of 2–3 mm can be achieved using a system detection sensitivity of 100 to 110 dB. Imaging studies have been performed in a wide range of biological, medical, and surgical specialties including developmental biology, cardiology, gastroenterology, urology, and neurosurgery. High-resolution OCT using short coherence length, short pulsed light sources has also been demonstrated and axial resolutions less than 2 μm have been achieved. High-speed real-time OCT at image acquisition rates of 4 to 8 frames per second have also been demonstrated. OCT has been extended to perform Doppler imaging of blood flow and birefringence imaging to investigate tissue injury. Different imaging delivery systems including transverse imaging catheters and forward imaging devices have been developed to enable internal body OCT imaging. Most recently, an OCT catheter has been combined with endoscope-based delivery to perform *in vivo* imaging in animal models and human patients.

This chapter will provide an overview of the OCT technology, beginning with the basic principles of operation. Technological advancements over the last decade have enabled OCT to transition from laboratory- to clinical-based imaging. These enabling advancements will be discussed, followed by representative applications in biology, medicine, surgery, and materials.

Principles of Operation

OCT is based on optical ranging, the high-resolution, high dynamic range detection of backscattered light. In contrast to ultrasound, the velocity of light is extremely high. Therefore, the echo time delay of reflected light cannot be measured directly and interferometric detection techniques must be used. One method for measuring echo time delay is to use low coherence interferometry or optical coherence domain reflectometry. Low-coherence interferometry was first developed for measuring reflections in fiber optics and optoelectronic devices.

The echo time delay of reflected light is measured by using a Michelson-type interferometer (Figure 1). The light reflected from the specimen or sample is interfered with light that is reflected from a reference path of known path length. Interference of the light reflected from the sample arm and reference arm of the interferometer can occur only when the optical path lengths of the two arms match to within the coherence length of the optical source. As the reference arm optical path length is scanned, different echo delays of backscattered light from within the sample are measured. The interference signal is detected at the output port of the interferometer, electronically band-pass filtered, demodulated, digitized, and stored on a computer. The position of the incident beam on the specimen is typically scanned in the transverse direction and multiple axial measurements are performed. This generates a two-dimensional data array that represents the optical backscattering through a cross-sectional plane in the specimen (Figure 2). The logarithm of the backscatter intensity is then mapped to false-color or gray-scale and displayed as an OCT image. The interferometer in an OCT instrument can be implemented using a fiber optic coupler and beam-scanning can be performed with small mechanical galvanometers in order to yield a compact and robust system (Figure 3).



Figure 1 Schematic illustrating the concept of low-coherence interferometry. Using a short coherence-length light source and a Michelson-type interferometer, interference fringes are observed only when the path lengths of the two interferometer arms are matched to within the coherence length of the optical source. Abbreviations: BS, beam splitter; Δl_c, coherence length.

In contrast to conventional microscopy, the axial resolution in OCT images is determined by the coherence length of the light source. The axial point spread function of the OCT measurement as defined by the signal detected at the output of the



Figure 2 OCT image generation. The OCT image is typically acquired by performing axial measurements of optical backscatter at different transverse positions on the specimen and displaying the resulting two-dimensional data set as a gray-scale (or false-color) image.



Figure 3 Schematic representation of an OCT system implemented using fiber optics. The Michelson interferometer is implemented using a fiber-optic coupler (beam splitter). The sample arm contains a beam-delivery instrument and the reference arm contains a mechanism for rapidly scanning the optical pathlength. The output of the interferometer is detected with a photodiode, filtered, demodulated, analog-to-digital (A–D) converted, and processed by a computer.

interferometer is the electric-field autocorrelation of the source. The coherence length of the light is the spatial width of the field autocorrelation and the envelope of the field autocorrelation is equivalent to the Fourier transform of its power spectrum. Thus, the width of the autocorrelation function, or the axial resolution, is inversely proportional to the width of the power spectrum. For a source with a Gaussian spectral distribution, the axial resolution Δz is given:

$$\Delta z = \frac{2\ln 2}{\pi} \cdot \frac{\lambda^2}{\Delta\lambda}$$

where Δz and $\Delta\lambda$ are the full-widths-at-half-maximum of the autocorrelation function and power spectrum respectively and λ is the source central wavelength. Figure 4 illustrates the dependence of the coherence length (axial resolution) on the bandwidth of the optical source. To achieve high axial resolution requires broad bandwidth optical sources. Resolution is also improved by using shorter wavelengths, however, shorter wavelengths are scattered and absorbed more in biological tissue.

The transverse resolution in an OCT imaging system is determined by the focused spot size in analogy with conventional microscopy and is given by:

$$\Delta x = \frac{4\lambda}{\pi} \cdot \frac{f}{d}$$

Where d is the spot size on the objective lens and f is its focal length. High transverse resolution can be obtained by using a large numerical aperture and focusing the beam to a small spot size. The transverse resolution is also related to the depth of focus or the confocal parameter $2z_R$ (two times the Raleigh range).



Figure 4 Dependence of coherence length (axial resolution) on the bandwidth of the optical source. Curves are shown for imaging wavelengths of 800 nm, 1300 nm, and 1500 nm. To achieve micron-scale resolution imaging, broad spectral bandwidths are necessary.

$$2z_R = \frac{\pi \Delta x^2}{2\lambda}$$

Thus, increasing the transverse resolution results in a reduced depth of field. Typically, the confocal parameter or depth of focus is chosen to match the desired depth of imaging. Increased resolution may also be obtained by using a higher numerical aperture lens or objective and spatially tracking the focus through the specimen.

Finally, the detection signal-to-noise is given by the optical power backscattered from the sample divided by the noise equivalent bandwidth:

$$\mathrm{SNR} = 10 \log\left(\frac{\eta}{\hbar\omega} \frac{P_{\mathrm{SAM}}}{\mathrm{NEB}} \right)$$

Depending upon the desired signal to noise performance, incident powers of 5–10 mW are typically required for OCT imaging of 250–500 square pixel images at several frames per second. If lower data acquisition speeds or signal-to-noise can be tolerated, power requirements can be reduced accordingly.

Technological Developments

Since the inception of OCT in the early 1990s, there has been rapid technological developments aimed at improving the imaging resolution, acquisition rate, and methods for beam delivery to the tissue or sample. Investigators have also explored other imaging methods using the principles of OCT to extract information from the tissue or sample. Some of these methods have included acquiring optical Doppler signals from moving scatterers or structures, obtaining images based on the polarization state of the returned light, and extracting spectroscopic information based on the local absorption or scattering properties of the tissue.

Optical Sources / High-Resolution Imaging

The majority of OCT imaging systems to date have used superluminescent diodes (SLDs) as low coherence light sources. SLDs are manufactured with a similar structure to that of laser diodes, but commonly end facets are angle-cleaved to suppress lasing. These device structures do not support oscillation modes and generate output based on amplified spontaneous emission, resulting in emission spectra that are broader than laser diodes. SLDs are commercially available at a range of wavelengths including 800 nm, 1.3 μm, and 1.5 μm and are attractive because they are compact, have high efficiency, and low noise. However, output powers are typically limited to only a few milliwatts which limits fast real-time acquisition rates, and the available bandwidths are relatively narrow, permitting imaging with 10–15 micron resolution. Recent advances in short-pulse solid-state laser technology make these sources attractive for OCT imaging in research applications. Femtosecond solid-state lasers can generate tunable, low-coherence light at powers sufficient to permit high-speed OCT imaging. Short pulse generation has been achieved across the full wavelength range in titanium:sapphire ($Ti:Al_2O_3$) from 0.7 μm to 1.1 μm and over more limited tuning ranges near 1.3 μm and 1.5 μm in chromium: forsterite ($Cr^{4+}:Mg_2SiO_4$) and chromium:yttrium-aluminum-garnet (Cr^{4+}:YAG) lasers, respectively. OCT imaging with resolutions of 1 μm and 5 μm has been demonstrated at 800 nm and 1.3 μm respectively using $Ti:Al_2O_3$ and $Cr^{4+}:Mg_2SiO_4$ sources. More compact and convenient sources such as superluminescent fiber sources, are currently under investigation. The titanium:sapphire laser technology is routinely used in multi-photon microscopy applications for its high peak intensities to enable multi-photon absorption and subsequent emission of fluorescence from exogenous fluorescent contrast agents. Combined OCT and multi-photon microscopy has been used to provide complementary image data using a single optical source.

Fast Scanning

The short-pulse solid-state laser technology not only provides broad spectral bandwidths for high-resolution OCT imaging, but also higher output powers to enable fast real-time OCT imaging. Higher incident powers are required to maintain equivalent signal-to-noise ratios when scanning at a faster rate. Linearly translating a reference arm mirror is problematic at high rates and provides axial scan frequencies of approximately 100 Hz, depending on the mirror size and the translating galvanometer. Several investigators have utilized rotating glass cubes, piezoelectric modulators, and multi-pass optical cavities to increase axial scan rates while maintaining scan ranges of 1–2 mm. An optical delay based on the principles used in femtosecond pulse shaping has been demonstrated for OCT. This delay line spectrally disperses the reference arm beam with a grating. The dispersed beam is then focused by a lens on to a rotating mirror mounted on a galvanometer. The mirror, located in the Fourier-transform plane of the lens, imparts a wavelength-dependent phase shift on the light. Subsequently, when re-coupled back into the interferometer, this phase-shift is equivalent to a time-delay in the time domain. The use of high-speed resonant galvanometers has permitted axial scan rates as high as 8 kHz over scan ranges of several millimeters. Depending on the image pixel size (number of axial scans within each image), this scan rate can provide video-rate OCT imaging (30 frames per second). An example of high-speed *functional* OCT imaging is shown in Figure 5. Images of a



Figure 5 Comparison of slow and fast OCT imaging of a beating *Xenopus* (African frog) tadpole heart. The OCT image in (a) was acquired in 30 seconds and shows oscillations and blurring from the beating heart. The image on the right (b) was acquired in 250 ms (4 frames per second), fast enough to capture the anatomy of the heart with minimal motion artifacts. Abbreviations: a, atrium; ba, bulbous arteriosus; v, ventricle. (Images reprinted with permission from Boppart SA, Tearney GJ, Bouma BE, *et al.* (1997) Noninvasive assessment of the developing *Xenopus* cardiovascular system using optical coherence tomography. *Proceedings of the National Academy of Sciences* 94: 4256–4261.)

beating *Xenopus laevis* (African frog) tadpole were compared at slow (30 s per image) and at fast (250 ms per image) acquisition rates. Artifacts due to cardiac motion were present at slow acquisition rates, but were minimized with acquisition rates of 4 frames per second. Functional cardiac parameters could be measured and high-speed processes such as chamber and valve function could be visualized in real-time.

Depth-priority scanning, as described above, is performed by rapidly varying the optical delay in the reference arm and collecting a single axial scan before translating the beam laterally and repeating this depth-scanning. An alternative method for generating OCT images is with transverse-priority scanning. This is equivalent to optical sectioning in confocal and multi-photon microscopy. Three-dimensional OCT imaging using transverse-priority scanning can be obtained by stepping the position of the reference arm mirror after each *en face* image is acquired. The OCT images produced from transverse-priority scanning can be correlated with confocal or multi-photon microscopy images, which are acquired with the same scanning method. This method can also utilize higher numerical aperture objective lenses to provide high transverse resolutions since a large depth of focus is not needed as in depth-priority OCT scanning. The combination of OCT with high-numerical aperture objectives has been termed optical coherence microscopy.

Doppler Optical Coherence Tomography

Conventional OCT detects the amplitude of the optical backscatter versus position within the sample. Doppler OCT is a technique which has been applied to measuring fluid flow within small capillary tubes and *in vivo* vessels in the skin, retina, and heart of small animal models and humans. This technique is based on digitally sampling the interference fringes that are produced from a moving scatterer within the sample or specimen and determining the Doppler frequency shift in the signal due to the moving scatterer. Figure 6 illustrates two- and three-dimensional optical Doppler data for fluid flow through a cylindrical tube. A two-dimensional cross-sectional profile of fluid flow through a silicon tube with a 600 μm inner-diameter is plotted in Figure 6. The acquired data (points) closely match the predicted profile (line) for these tube dimensions. Below the plot, one method of obtaining a three-dimensional fluid flow profile is illustrated. While imaging the tube in cross-section, the fluid flow velocity was altered with a perfusion pump. The detection filter bandwidth of the OCT electronics served a windowing function, detecting only flow velocities with frequencies within the detection bandwidth. For an unknown flow profile, the center frequency of the detection filter can be shifted to map the flow velocities present within the sample.

Beam Delivery

The OCT imaging technology is modular in design and a variety of optical instruments can be used to deliver the OCT beam to the tissue or sample. Because OCT is fiber-optic based, single optical fibers can be used to deliver the OCT beam and collect the reflected light. The OCT technology can readily be integrated into existing optical instruments such as research and surgical microscopes, ophthalmic slit-lamp biomicroscopes, and hand-held imaging probes.

Imaging penetration is determined by the optical absorption and scattering properties of the tissue or specimen. The imaging penetration for OCT ranges from tens of millimeters for transparent tissues such as the eye to less than 3 mm in highly-scattering tissues such as skin. To image highly-scattering tissues deep within the body, novel beam-delivery



Figure 6 Doppler OCT. A two-dimensional plot of the fluid-flow velocity profile of flowing blood through a 600 μm inner-diameter tube is shown. Data points acquired using OCT closely follow the theoretical laminar flow profile (line). Two-dimensional Doppler OCT images of blood flow through the tube are shown below the plot. As fluid flow increases, only fluid-flow velocities within the bandwidth of the detection electronics are detected. This represents one method by which 3-D fluid flow can be imaged.

instruments have been developed to relay the OCT beam to the site of the tissue to be imaged. An OCT catheter has been developed for insertion into biological lumens such as the gastrointestinal tract. Used in conjunction with endoscopy, the 1 mm diameter catheter can be inserted through the working channel of the endoscope for simultaneous OCT and video imaging. Minimally-invasive surgical procedures utilize laparoscopes, which are long, thin, rigid optical instruments that permit video-based imaging within the abdominal cavity. Laparoscopic OCT imaging has been demonstrated by passing the OCT beam through the optical elements of a laparoscope. Deep solid-tissue imaging is possible with the use of fiber-needle probes. Small (400 μm diameter) needles housing a single optical fiber and micro-optic elements can be inserted into solid tissues and rotated to acquire OCT images. Recently, microfabricated micro-electro-optical-mechanical systems (MEOMS) technology has been used to miniaturize the OCT beam scan mechanism.

Applications

Developmental Biology

OCT has been demonstrated in the field of developmental biology as a method to perform high-resolution, high-speed imaging of developing morphology and function. Cellular-level imaging is possible, providing a non-invasive technique for visualizing cellular processes such as mitosis and migration. Imaging studies have been performed on several standard biological animal models commonly employed in developmental biology investigations including *Rana pipiens* (Leopard frog), *Xenopus laevis*



Figure 7 OCT images and corresponding histology of a Stage 49 (12 day) *Rana pipiens* (Leopard frog) tadpole. OCT images in the left and middle columns were acquired with the OCT beam incident from the dorsal and ventral sides of the specimen, respectively. The corresponding histology in the right column illustrates strong correlations between OCT images and the actual tissue morphology. Abbreviations: ey, eye; g, gills; h, heart; i, intestines; rt, respiratory tract. (Images reprinted with permission from Boppart SA, Brezinski ME, Bouma BE, *et al.* (1996) Investigation of developing embryonic morphology using optical coherence tomography. *Dev. Biol.* 177: 54–64.)

(African frog), and *Brachydanio rerio* (zebrafish) embryos and eggs, and the murine (mouse) model.

A series of cross-sectional images acquired *in vitro* from the dorsal and ventral sides of a Stage 49 (12 day) *Rana pipiens* (Leopard frog) tadpole is shown in Figure 7. Features of internal architectural morphology are clearly visible in the images. The image of the eye differentiates structures corresponding to the cornea, lens, and iris. Internal morphology not accessible in one orientation due to the specimen size or shadowing effects can be imaged by reorienting the specimen and scanning in the same cross sectional image plane. With the OCT beam incident on the ventral side, images of the respiratory tract, ventricle of the heart, internal gills, and gastrointestinal tract were acquired.

These images can be compared with corresponding histology (Figure 7). Histological images are acquired by euthanizing the specimen, immersing the specimen in a chemical fixative, and physically sectioning thin (2–5 micron-thick) slices using a microtome. The slices are placed on a microscope slide, selectively stained to highlight particular features, and viewed with light microscopy. The correlations between OCT and histology images are strong, suggesting that OCT images can accurately represent the *in vivo* specimen morphology. The potential exists to repeatedly image specimens to quantify organo- and morphogenesis throughout development. Technologies such as OCT are likely to become increasingly important in functional genomics, relating genetic features to the morphology and function in living specimens.

OCT images represent the optical backscatter intensity from regions within the tissue or sample. Because OCT relies on the inherent optical scattering changes to produce imaging contrast, no exogenous contrast agents or fluorophores are necessary. This permits long-term sequential imaging of development *in vivo* without loss of specimen viability. Repeated images of a developing zebrafish embryo within its egg beginning immediately after fertilization and up until hatching have been demonstrated without loss of specimen viability or without developmental abnormalities. In this example, the zebrafish egg and embryo were semi-transparent and the use of OCT significantly complemented observations made using light microscopy. By imaging subtle differences in backscattering intensity, interfacial structural layers millimeters deep within specimens can be clearly delineated.

Previous OCT images have characterized morphological features within biological specimens. These structures are static even though they may have been acquired from *in vivo* specimens. *In vivo* imaging in living specimens, particularly in larger organisms and for medical diagnostic applications, must be performed at high speeds to eliminate motion artifacts within the images. Functional OCT imaging is the quantification of *in vivo* images which yield information characterizing the functional properties of the organ system or organism. High speed OCT permits both the positioning and manipulation of specimens as well as imaging in real time and is a powerful technology for functional imaging in developmental biology animal models.

Studies investigating normal and abnormal cardiac development have been frequently limited by an inability to access cardiovascular function within the intact organism. OCT has been demonstrated for the high-resolution assessment of structure and function in the developing *Xenopus laevis* (African frog) cardiovascular system (Figure 5). The morphology of the *in vivo* cardiac chambers is clearly delineated. Image acquisition rates are fast enough to capture the cardiac chambers in mid-cycle. With this capability, images can be acquired at various times during the cardiac cycle. These frames can be displayed in real-time to produce a movie illustrating the dynamic, functional behavior of the developing heart. OCT, unlike technologies such as computed tomography and magnetic resonance imaging, provides high-speed *in vivo* imaging, allowing quantitative dynamic activity, such as ventricular ejection fraction, to be assessed.

Cellular Imaging

Although previous studies have demonstrated *in vivo* OCT imaging of tissue morphology, most have imaged tissue at ~10–15 μm resolutions, which does not allow differentiation of cellular structure. The ability of OCT to identify the mitotic activity, the nuclear-to-cytoplasmic ratio, and the migration of cells has the potential to not only impact the fields of cell and developmental biology, but also impact medical and surgical disciplines for the early diagnostics of disease such as cancer.

The *Xenopus laevis* (African frog) tadpole has been used to demonstrate the feasibility of OCT for high-resolution *in vivo* cellular and subcellular imaging. Many of the cells in this common developmental biology animal model are rapidly dividing and migrating during the early growth stages of the tadpole, providing an opportunity to image dynamic cellular processes. Three-dimensional volumes of high-resolution OCT data have been acquired from these specimens throughout development. From this 3-D data set, cells undergoing division were identified and tracked in three dimensions. In a similar manner, 3-D data sets were acquired to track single melanocytes (neural crest cells) as they migrated through the living specimens. The ability of OCT to characterize cellular processes such as mitosis and migration not only are of interest in cell and developmental biology, but also have relevance for cancer diagnostics and tumor metastasis.

An example of cellular-level OCT imaging in these specimens is shown in Figure 8. This composite image (0.83 × 1 mm, 1800 × 1000 pixels) was acquired using a titanium:sapphire laser with a broad bandwidth (~260 nm). The axial and transverse resolution in this image is 1 μm and 5 μm, respectively (see Figure 4). Because the high transverse resolution reduced the depth-of-focus to 49 μm, separate OCT images were first acquired with the focus at different depths within the specimen. These images were then assembled to produce the composite image shown in Figure 8. This type of image construction is similar to C-mode ultrasound. Cellular features including cell membranes, nuclei, and nuclear morphology are clearly observed.

Medicine – Imaging Barrett's Esophagus

OCT performs *in situ* imaging and has the potential to be used as a screening technique of early pathological changes in patients. OCT imaging has the potential to be a general diagnostic in many organ systems,



Figure 8 Cellular-level OCT imaging using a broad bandwidth titanium:sapphire laser. Axial and transverse image resolutions are 1 μm and 5 μm, respectively, enabling the visualization of cell membranes, nuclear morphology, and sub-cellular organelles. Cellular processes such as mitosis and migration can be visualized in real-time in living specimens. (Image reprinted with permission from Drexler W, Morgner U, Kartner FX, *et al.* (1999) *In vivo* ultrahigh resolution optical coherence tomography. *Optics Letters* 24: 1221–1223.)

particularly where current methods of screening by excisional biopsy are limited. Barrett's esophagus is a condition where the cells of the distal esophagus undergo a metaplastic change, resembling cells of the lower gastrointestinal tract. This condition is believed to be caused by chronic gastroesophageal reflux. Several studies have demonstrated that Barrett's esophagus is associated with a 30–125 times increased risk of developing adenocarcinoma. For this reason, endoscopic surveillance of Barrett's epithelium every 12–18 months is recommended. Endoscopic screening currently involves random four-quadrant biopsies every 1–2 cm along the length of suspect mucosa. However, excisional biopsy is prone to sampling errors and small foci of carcinoma or dysplasia may be missed. Because of the imprecision and high cost associated with screening, new methods are being developed to assess patients at increased risk. Endoscopic ultrasound catheters have been used for imaging the gastrointestinal tract with 50–100 μm resolution. However, these resolutions are insufficient to resolve early epithelial changes that occur in Barrett's esophagus and the pre-malignant changes that lead to adenocarcinoma of the esophagus.

The ability of OCT to differentiate normal and pathologic tissue is a central question being addressed by many research groups. Comparisons with histology show good correlations between OCT images and histological findings. The image resolution of conventional OCT (10–15 μm) is sufficient to differentiate architectural but not cellular morphology. Still, endoscopic OCT resolution can differentiate normal from Barrett's epithelium in real-time based on differences in epithelial architecture. Crypt- and gland-like structures that disrupt the relatively uniform layers of squamous epithelium can be readily identified, enabling differentiation between normal and Barrett's epithelium (Figure 9). The ability to differentiate normal from Barrett's epithelium suggests that the OCT technology could be used for screening applications.

Oncology – Identifying Tumors and Tumor Margins

OCT has been used to differentiate between the morphological structure of normal and cancerous tissue for a wide-range of tumors. The use of OCT to identify tumors and tumor margins *in situ* will represent a significant advancement for medical or image-guided surgical applications. OCT has been demonstrated for the detection of brain tumors and their margins with normal brain parenchyma, suggesting a role for guiding surgical resection. A hand-held surgical imaging probe was constructed for this application. The compact and portable probe permits OCT imaging within the surgical field while



Figure 9 Endoscopic OCT imaging in humans. An OCT catheter was inserted down the working channel of an endoscope. Guided by video imaging, regions of normal and Barrett's esophagus were imaged. Corresponding biopsy histology is shown. OCT can identify Barrett's esophagus by the presence of gland- and crypt-like structures (arrows). (Images reprinted with permission from Li XD, Boppart SA, Van Dam J, *et al.* (2000) Optical coherence tomography: advanced technology for the endoscopic imaging of Barrett's esophagus. *Endoscopy* 32: 921–930.)

the OCT instrument can be remotely located in the surgical suite.

Figure 10 shows a specimen of outer human cerebral cortex with metastatic melanoma. The OCT images in Figure 10a,b were acquired through the tumor. These original images were threshold segmented to identify regions of high backscatter within the tumor. The original images were then overlaid with the segmented data and are shown in Figure 10c,d. The OCT images show increased optical backscattering in the region of the larger tumor (arrows). Smaller tumor lesions also appear within the image (arrows). A shadowing effect is observed below each tumor site due to the increased optical backscatter and the subsequent loss of optical power penetrating beneath the tumor. In Figure 10a,c, the boundary of the tumor can be identified. In Figure 10b,d, the tumor is identified below the surface of normal cortex. The histology in Figure 10e,f confirms the presence and relative size of the tumor.



Figure 10 Cancer diagnostics. OCT imaging was used to image metastatic melanoma in an *ex vivo* specimen of human cortex (brain). Raw OCT images (a,b) were threshold-segmented (c,d) to highlight regions of increased optical backscatter and to identify tumor margins. OCT images correlate well with histological findings (e,f). (Images reprinted from Boppart SA, Brezinski ME, Pitris C and Fujimoto JG (1998) Optical coherence tomography for neurosurgical imaging of human intracortical melanoma. *Neurosurgery* 43: 834–841, with permission from Lippincott Williams and Wilkins.)

The image resolutions used to acquire the images in Figure 10 were as high as 16 μm, higher than any current ultrasound, CT, or MRI intraoperative imaging technique. This allowed the tumor-cortex interface and the extent of tumor below the surface to be defined with high resolution. At higher imaging resolutions, it may be possible to image individual tumor cells which have migrated away from the central tumor. OCT represents a new high-resolution optical imaging technology that has the potential for identifying tumors and tumor margins on the micron scale and in real-time. OCT offers imaging performance not achievable with current imaging modalities and may contribute significantly toward the surgical resection of neoplasms.

Image-Guided Surgery

The repair of vessels and nerves is necessary to restore function following traumatic injury. Although the repair of these sensitive structures is performed with the aid of surgical microscopes and loupes to magnify the surgical field, surgeons are limited to the *en face* view that they provide. A technique capable of subsurface, three-dimensional, micron-scale imaging in real-time would permit the intraoperative monitoring of microsurgical procedures. The capabilities of OCT for the intraoperative assessment of microsurgical procedures have been demonstrated. High-speed OCT imaging was integrated with a surgical microscope to performed micron-scale three-dimensional imaging on microsurgical specimens.

OCT has been used to image *in vitro* peripheral nerves and identify individual fascicles. Longitudinal tracking of the spatial orientation of rabbit peripheral nerve fascicles is demonstrated in Figure 11. Representative cross-sectional images of the peripheral nerve are shown in Figure 11a–d. For each slice, one fascicle was manually segmented, colored white, and tracked through the acquired volume of data. Forty images at 100 μm spacing were assembled for the 3-D projections shown in Figure 11e,f. The horizontally- and vertically-rotated projections of the peripheral nerve dramatically reveal the twisted path of the segmented fascicle along the longitudinal axis of the nerve. In addition, a branch in an unsegmented fascicle is observed in Figure 11f. The use of OCT to acquire multiple cross-sectional images and three-dimensionally reconstruct the peripheral nerve offers the opportunity to determine the relative diameters of individual fascicles and to longitudinally track their spatial orientation. OCT may also be useful at identifying and grading the degree of injury in nerves during surgical repair. These results have shown how 2-D OCT images and 3-D OCT projections can



Figure 11 OCT image-guided microsurgery. Multiple cross-sectional OCT images were acquired through a resected rabbit peripheral nerve (a–d). A single nerve fascicle (f) was identified and segmented longitudinally along the length of the nerve. Three-dimensional reconstruction projections of the nerve in (e,f) reveal the tortuous path of the segmented fascicle as well as reveal a bifurcation (b). Intraoperative OCT can guide surgical repair and potentially identify regions of damaged tissue. (Images reprinted from Boppart SA, Bouma BE, Pitris C, *et al.* (1998) Intraoperative assessment of microsurgery with three-dimensional optical coherence tomography. *Radiology* 208: 81–86, with permission from the Radiology Society of North America.)

provide diagnostic feedback to assess microsurgical anastomoses. This previously unavailable diagnostic ability offers the potential to directly impact and improve patient outcome by incorporating high-speed, high-resolution intraoperative image-guidance during microsurgical procedures.

Surgical intervention requires visualization to identify tissue morphology, precision to avoid sensitive tissue structures, and continuous feedback to monitor the extent of the intervention. OCT may provide the technological advancements to improve the operative procedure. The feasibility of OCT to perform image-guided surgical intervention has been investigated. OCT has been used to monitor laser ablation therapy in real-time and may enable more precise control of laser delivery. An argon-laser ablation sequence of fresh *ex vivo* rat rectus abdominis muscle is shown in Figure 12. A pair of blood-filled vessels were located 1.5 mm below the tissue surface and centered within the OCT image. Because blood has a higher absorption coefficient than muscle at the 514 nm argon laser wavelength, coagulation and thermal heating of the blood occurred prior to thermal damage to the overlying tissue. The accompanying histology reveals both the thermally-damaged overlying tissue and coagulated blood present within the vessel pair.

These examples demonstrate the use of OCT for guiding and monitoring surgical intervention. The laser is only a representative interventional surgical technique for a wide range of instruments and techniques including scalpels, electrosurgery, radiofrequency, microwaves, and ultrasound ablation. OCT imaging was performed at 8 frames per second, fast enough to capture dynamic changes in the optical properties of the tissue during thermal ablation. These image sequences provided interesting insight into ablation mechanisms for a variety of tissue types. OCT can monitor the extent of thermal injury below the surface of the tissue by imaging the changes in optical backscatter. OCT imaging can therefore provide empiric information for dosimetry to minimize the extent of collateral injury. The use of OCT for guiding surgical interventions has the potential to improve intraoperative monitoring and more effectively control interventional procedures.

Materials

While the majority of OCT applications have been in the fields of biology and medicine. OCT has also been demonstrated in the non-biological areas of materials investigation, optical data storage, and microfluidic devices. The highly-scattering or reflecting optical properties of many materials prohibits deep imaging penetration using OCT. Many material defects, however, originate near the surface or at interfacial boundaries, making the use of OCT a possibility for inspection and quality control. OCT has been used to identify subsurface defects in ceramics and polymer composites. The optical ranging capabilities of OCT through scattering materials has been utilized for increasing the data storage capacity by assembling multiple layers of optically-accessible data.

The advancement of microfabrication techniques has led to increasingly complex microfluidic and bioMEM (biological micro-electro-mechanical) systems. Microstructures within microfluidic systems range from 10–1000 µm, within both the imaging depth and resolution of OCT. In addition, microfluidic systems are typically fabricated from transparent or semi-transparent substrates, facilitating imaging penetration to deeper three-dimensional features.



Figure 12 OCT image-guided laser ablation. High-speed OCT image sequence of argon-laser ablation of blood vessels in *ex vivo* rat muscle tissue. Thermal heating within the blood vessels (arrows, 0.0–0.5 s) induces coagulation prior to injury to superficial muscle tissue (0.6–1.0 s). Accompanying histology shows coagulated blood within the vessels.

OCT is not only capable of imaging three-dimensional microstructures at micron-scale resolutions, but is also capable of obtaining dynamic functional data from microfluidic systems. Microfluidic devices made from polymeric materials are attractive since they provide flexibility in the design of the channels, can be manufactured in large volumes, and are mostly bio-compatible. A three-dimensional imaging technique, such as OCT, will be instrumental in the analysis of these devices and the monitoring of device performance.

Conclusions

The capabilities of OCT offer a unique and informative means of imaging biological specimens and non-biological samples. The non-contact nature of OCT and the use of low-power near-infrared radiation for imaging causes few harmful effects on living cells or damage to materials. OCT imaging does not require the addition of fluorophores, dyes, or stains in order to improve contrast in images. Instead, OCT relies on the inherent optical contrast generated from variations in optical scattering and index of refraction. These factors permit the use of OCT for extended imaging over the course of hours, days, or weeks. OCT permits the cross-sectional imaging of tissue and samples and enables *in vivo* structure to be visualized in opaque specimens or in specimens too large for high-resolution confocal or light microscopy.

Imaging at cellular and subcellular resolutions with OCT is an important area of ongoing research. The *Xenopus* (African frog) developmental animal model has been commonly used because its care and handling are relatively simple while allowing cells with a high mitotic index to be assessed. Many of the cells observed were as large as 100 μm in diameter, but ranged in size down to a few microns, below the resolution of most OCT systems. Imaging human cells *in vivo* remains a challenge since differentiated human cells are 10 to 20 microns in size, too small for most OCT systems. With further advances in OCT technology, improved discrimination and imaging of more detailed structures should be possible. New laser sources at other wavelengths in the near-infrared can enhance tissue contrast as well as potentially provide functional information since tissue scattering and absorbance properties in specimens are wavelength dependent. Short coherence length short pulse laser sources have been used to achieve higher axial resolutions on the order of 1 to 3 microns. Unfortunately, unlike superluminescent diode source, these high-speed and high-resolution systems utilize femtosecond lasers that are relatively complex and costly. Developing compact and portable optical sources at near-infrared wavelengths, broad spectral bandwidths, and high output powers is an area of active research.

Optical coherence tomography provides high-resolution morphological, functional, and cellular information of biological, medical, and material specimens and samples. OCT represents a multifunctional investigative tool that not only complements many of the existing imaging technologies available today, but also is poised to become a major optical imaging modality.

List of Units and Nomenclature

Cr^{4+}:Mg_2SiO_4	chromium:forsterite
Cr^{4+}:YAG	chromium:yttrium-aluminum-garnet
CT	computed tomography
d	beam diameter
f	focal length
MRI	magnetic resonance imaging
NEB	noise equivalent bandwidth
OCT	optical coherence tomography
P_{SAM}	power from sample
SNR	signal-to-noise ratio
SLD	superluminescent diode
Ti:Al_2O_3	titanium:sapphire
z_R	Rayleigh range
3-D	three-dimensional
Δx	transverse resolution
$\Delta\lambda$	spectral bandwidth
Δz	axial resolution
η	quantum efficiency
λ	center wavelength

See also

Coherence: Coherence and Imaging; Overview. **Coherent Lightwave Systems**. **Interferometry:** Overview. **Fiber and Guided Wave Optics:** Optical Fiber Cables. **Imaging:** Imaging Through Scattering Media; Interferometric Imaging. **Terahertz Technology:** Coherent Terahertz Sources. **Tomography:** Tomography and Optical Imaging. **Microscopy:** Confocal Microscopy; Imaging multiple Photon Fluorescence Microscopy; Overview.

Further Reading

Boppart SA, Tearney GJ, Bouma BE, *et al.* (1997) Noninvasive assessment of the developing *Xenopus* cardiovascular system using optical coherence tomography. *Proceedings of the National Academy of Sciences* 94: 4256–4261.

Boppart SA, Bouma BE, Pitris C, *et al.* (1998) *In vivo* cellular optical coherence tomography imaging. *Nature Medicine* 4: 861–864.

Boppart SA, Deutsch TF and Rattner DW (1999) Optical imaging technology in minimally invasive surgery. *Surgical Endoscopy* 13: 718–722.

Boppart SA, Brezinski ME and Fujimoto JG (2000) Optical Coherence Tomography Imaging. In: Tuan RS and Lo CW (eds) *Methods in Molecular Biology, Vol. 135: Developmental Biology Protocols*, vol. 1, pp. 217–233. Totowa, NJ: Humana Press, Inc.

Bouma BE and Tearney GJ (eds) (2001) *The Optical Coherence Tomography Handbook*. New York: Marcel Dekker Inc.

Chen Z, Zhao Y, Srinivas SM, *et al.* (1999) Optical Doppler tomography. *IEEE Journal of Selected Topics in Quantum Electronics* 5(4): 1134–1142.

Fujimoto JG, Brezinski ME, Tearney GJ, *et al.* (1995) Biomedical imaging and optical biopsy using optical coherence tomography. *Nature Medicine* 1: 970–972.

Fujimoto JG, Pitris C, Boppart SA and Brezinski ME (2000) Optical coherence tomography: An emerging technology for biomedical imaging and optical biopsy. *Neoplasia* 2(1–2): 9–25.

Huang D, Swanson EA, Lin CP, *et al.* (1991) Optical coherence tomography. *Science* 254: 1178–1181.

Masters BR (ed.) (2001) *Selected Papers on Optical Low-Coherence Reflectometry & Tomography*. SPIE Milestone Series, Vol. MS 165, Thompson BJ (general ed.) Bellingham, WA: SPIE Optical Engineering Press.

Puliafito CA, Hee MR, Schuman JS and Fujimoto JG (1995) Optical Coherence Tomography of Ocular Diseases. Thorofare, NJ: Slack, Inc.

Schmitt M (1999) Optical coherence tomography (OCT): A review. *IEEE Journal of Selected Topics in Quantum Electronics* 5(4): 1205–1215.

Tadrous PJ (2000) Methods for imaging the structure and function of living tissues and cells: 1. Optical coherence tomography. *Journal of Pathology* 191(2): 115–119.

Tearney GJ, Brezinski ME, Bouma BE, *et al.* (1997) *In vivo* endoscopic optical biopsy with optical coherence tomography. *Science* 276: 2037–2039.

Welzel J (2001) Optical coherence tomography in dermatology: a review. *Skin Research and Technology* 7(1): 1–9.

Tomography and Optical Imaging

Z Chen, University of California, Irvine, CA, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

'Tomos' means section, in Greek. A tomogram is a sectional image of the internal structure of a three-dimensional object. One of the challenges for tomographic imaging of biological tissue using visible or near-infrared light is tissue optical scattering. When photons propagate inside a tissue, they undergo multiple scattering. The mean free path of photons in the skin, for example, is 5 μm. If one focuses the light 1 mm below the skin surface, most photons undergo multiple scattering and never reach the target point. Less than one out of a million photons will be able to reach the target, undergo a single backscattering, and return to the detector (Figure 1). Most photons that are backscattered and reach the detector are multiple scattered photons that carry little information on the target point. The challenge for tomographic imaging of tissues is to separate the single backscattered photons, that carry information about the target point, from multiple scattered photons.

Several optical tomography techniques have been developed. Each uses different techniques to discriminate the multiple scattering photons from the minimally scattered photons for imaging constructions. The confocal microscope, for example, uses a spatial filtering technique to reject multiple scattering photons because multiple scattered photons are more spread out in their angular distribution than the minimally scattered photons. Time-of-flight imaging uses a time gating technique to discriminate diffuse photons because single backscattered photons arrive earlier than diffuse photons. Optical coherence tomography (OCT) uses coherent gating to discriminate single scattered photons from multiple scattered photons. These gating techniques provide good discrimination of minimally scattered photons from multiple scattered photons and can form high-resolution sectional images, albeit with a limited imaging depth. Diffuse photons can propagate deep into the tissue and these photons can also be used for optical tomography. If a modulated photon density wave is propagated inside the tissue, the scattering and absorption properties of the tissue will modulate the phase and amplitude of the photon density wave. However, the resolution of optical tomography, based on diffuse photons, is usually much lower than that of the tomography constructed from single or minimally scattered photons. Three of the most important parameters for optical tomography are contrast, spatial resolution, and image depth.

Most optical tomography uses absorption, scattering, and fluorescent properties of materials as contrast. OCT, for example, uses variations in tissue scattering as contrast for tomographic imaging. However, in many instances, and especially during the early stages of disease, the change in tissue scattering properties between normal and diseased tissues is small and difficult to measure. One of the great challenges for extending applications of OCT is to find more contrast mechanisms that can provide physiological information in addition to morphological structure. This article will focus on optical tomography technologies that use nonconventional contrast mechanisms to obtain tomographic images. These include optical Doppler tomography (ODT), optical polarization tomography, and optical second-harmonic tomography. These optical tomography technologies are extensions of OCT with contrast mechanisms that can provide physiological information, in addition to morphological structure. ODT, also known as Doppler OCT, combines the Doppler principle with OCT to obtain high-resolution tomographic images of tissue structure and blood flow simultaneously. Optical polarization tomography, also known as polarization sensitive OCT (PS-OCT), combines polarization sensitive



Figure 1 Optical imaging in scattering media.

detection with OCT, to determine tissue birefringence. Optical second-harmonic tomography, also known as second-harmonic optical coherence tomography (SH-OCT), combines second-harmonic generation (SHG) with coherence gating to obtain images with molecular contrast. These functional extensions of OCT provide clinically important information on tissue physiology, such as tissue blood perfusion, oxygen saturation, hemodynamics, and structural remodeling. Each provides several potential clinical applications, such as vasoactive drug screening, tissue viability and burn depth determination, tumor angiogenesis studies, tumor diagnosis, bleeding ulcer management, and ocular pathology evaluation.

Optical Doppler Tomography

ODT combines the Doppler principle with OCT to obtain high-resolution tomographic images of static and moving constituents in high scattering media. When light backscattered from a moving particle interferes with the reference beam, a Doppler frequency shift (f_D) occurs in the interference fringe:

$$f_D = \frac{1}{2\pi}(\mathbf{k}_s - \mathbf{k}_i)\cdot\mathbf{v} \qquad [1]$$

where $\mathbf{k}_i$ and $\mathbf{k}_s$ are wavevectors of incoming and scattered light, respectively, and $\mathbf{v}$ is the velocity vector of the moving particle (Figure 2). Since ODT measures the backscattered light, assuming the angle between flow and sampling beam is θ, the Doppler shift equation is simplified to:

$$f_D = \frac{2V\cos\theta}{\lambda_0} \qquad [2]$$

where λ_0 is the vacuum center wavelength of the light source.



Figure 2 Schematic of flow direction and probe beam angle.

The optical system of ODT is similar to that of OCT. The primary difference is in signal processing. Figure 3 illustrates an ODT instrument that uses a fiber optic Michelson interferometer with a broadband light source. Light from a broadband partial coherence source is coupled into a fiber interferometer by a 2 × 2 fiber coupler and then split equally into reference and target arms of the interferometer. Light backscattered from the turbid sample is coupled back into the fiber and forms interference fringes with the light reflected from the reference arm. A rapid-scanning optical delay line is used for group delay and axial scanning. Because this delay line can decouple the group delay from the phase delay, an electro-optical phase modulator is introduced to produce a stable carrier frequency. The interference fringe intensity signal is amplified, bandpass filtered, and digitized with a high-speed analog-to-digital converter. The signal processing is carried out at the same time as data are transferred to the computer, and real-time display can be accomplished with the use of a digital signal processing board.

To understand the signal processing of ODT, let us look at the fringe signal due to the moving particles.



Figure 3 Schematic of ODT system consists of a fiber-based Michelson interferometer with a partially coherent light source.

If we denote $U(t)$ as a complex-valued analytic signal of a stochastic process representing the field amplitude emitted by a low coherent light source and $\bar{U}(\nu)$ as the corresponding spectral amplitude at optical frequency ν, the amplitude of a partially coherent source light coupled into the interferometer at time t, is written as a harmonic superposition:

$$U(t) = \int_0^\infty \bar{U}(\nu)\mathrm{e}^{2\pi i \nu t}\,\mathrm{d}\nu \qquad [3]$$

Because the stochastic process of a partially coherent light source is stationary, the cross spectral density of $\bar{U}(\nu)$ satisfies:

$$\langle \bar{U}^*(\nu)\bar{U}(\nu')\rangle = S_0(\nu)\delta(\nu - \nu') \qquad [4]$$

where $S_0(\nu)$ is the source power spectral density, and $\delta(\nu - \nu')$ is the Dirac delta function. Assuming that light couples equally into the reference arm and sample arm with spectral amplitude of $\bar{U}_0(\nu)$, the light coupled back to the detector from the reference, $\bar{U}_{\mathrm{r}}(\nu)$, and sample, $\bar{U}_{\mathrm{s}}(\nu)$, are:

$$\bar{U}_{\mathrm{r}}(\nu) = \mathrm{e}^{2\pi i\nu(2L_{\mathrm{r}}+L_{\mathrm{d}})/c}K_{\mathrm{r}}(\nu)\mathrm{e}^{i\alpha_{\mathrm{r}}}\bar{U}_0(\nu) \qquad [5]$$

$$\bar{U}_{\mathrm{s}}(\nu) = \mathrm{e}^{2\pi i\nu(2L_{\mathrm{s}}+L_{\mathrm{d}})/c}K_{\mathrm{s}}(\nu)\mathrm{e}^{i\alpha_{\mathrm{s}}}\bar{U}_0(\nu) \qquad [6]$$

where L_{r} and L_{s} are the optical pathlengths from the beamsplitter to the reference mirror and sample, respectively; L_{d} is the optical pathlength from the beamsplitter to the detector; and $K_{\mathrm{r}}(\nu)\mathrm{e}^{i\alpha_{\mathrm{r}}(\nu)}$ and $K_{\mathrm{s}}(\nu)\mathrm{e}^{i\alpha_{\mathrm{s}}(\nu)}$ are the amplitude reflection coefficients of light backscattered from the reference mirror and turbid sample, respectively.

The total power detected at the interferometer output is given by a time-average of the squared light amplitude:

$$P_{\mathrm{d}}(\tau) = \langle |U_{\mathrm{s}}(t) + U_{\mathrm{r}}(t+\tau)|^2\rangle \qquad [7]$$

where τ is the depth scan time delay. Combining harmonic expansions for $U_{\mathrm{s}}(t)$ and $U_{\mathrm{r}}(t)$ and applying eqn [4] when calculating the time-average, the total power detected is a sum of three terms representing reference (I_{r}), sample (I_{s}), and the interference fringe intensity ($\Gamma_{\mathrm{ODT}}(\tau)$):

$$\begin{aligned} P_{\mathrm{d}}(\tau) &= \int_0^\infty (P_{\mathrm{r}}(\nu) + P_{\mathrm{s}}(\nu) + P_{\mathrm{ODT}}(\nu))\mathrm{d}\nu \\ &= I_{\mathrm{r}} + I_{\mathrm{s}} + \Gamma_{\mathrm{ODT}}(\tau) \end{aligned} \qquad [8]$$

with

$$P_{\mathrm{r}}(\nu) = S_0(\nu)|K_{\mathrm{r}}(\nu)|^2 \qquad [9]$$

$$P_{\mathrm{s}}(\nu) = S_0(\nu)|K_{\mathrm{s}}(\nu)|^2 \qquad [10]$$

$$\begin{aligned} P_{\mathrm{ODT}}(\nu) &= 2S_0(\nu)K_{\mathrm{r}}(\nu)K_{\mathrm{s}}(\nu) \\ &\quad \times\cos[2\pi\nu(\Delta_{\mathrm{d}}/c+\tau)+\alpha_{\mathrm{s}}(\nu)-\alpha_{\mathrm{r}}(\nu)] \end{aligned} \qquad [11]$$

and

$$I_{\mathrm{r}} = \int_0^\infty P_{\mathrm{r}}(\nu)\mathrm{d}\nu \qquad [12]$$

$$I_{\mathrm{s}} = \int_0^\infty P_{\mathrm{s}}(\nu)\mathrm{d}\nu \qquad [13]$$

$$\Gamma_{\mathrm{ODT}}(\tau) = \int_0^\infty P_{\mathrm{ODT}}(\nu)\mathrm{d}\nu \qquad [14]$$

When there is a moving particle, light scattered from this particle is equivalent to a moving phase front; therefore, Δ_{d} in eqn [11] can be written as:

$$\Delta_{\mathrm{d}} = \Delta + 2\bar{n}V_{\mathrm{z}}t \qquad [15]$$

where Δ is the optical pathlength difference between light in the sampling and reference arms; V_{z} is the velocity of a moving particle parallel to the probe beam; and $\bar{n}$ is the refractive index of flow media.

To simplify the computation, we assume α_{s} and α_{r} are constants over the source spectrum and can be neglected. The spectral domain fringe signal, $P_{\mathrm{ODT}}(\nu)$, is simplified to:

$$\begin{aligned} P_{\mathrm{ODT}}(\nu) = {} & 2S_0(\nu)K_{\mathrm{r}}(\nu)K_{\mathrm{s}}(\nu) \\ & \times\cos[2\pi\nu((\Delta + 2\bar{n}V_{\mathrm{z}}t)/c + \tau)] \end{aligned} \qquad [16]$$

The corresponding time domain signal, $\Gamma_{\mathrm{ODT}}(\tau)$, is given by:

$$\begin{aligned} \Gamma_{\mathrm{ODT}}(\tau) = {} & 2\int_0^\infty S_0(\nu)K_{\mathrm{r}}(\nu)K_{\mathrm{s}}(\nu) \\ & \times\cos[2\pi\nu((\Delta + 2\bar{n}V_{\mathrm{z}}t)/c + \tau)]\mathrm{d}\nu \end{aligned} \qquad [17]$$

A comparison of eqns [16] and [17] shows that there is a Fourier transformation relation between spectral domain and time domain signals. Consequently, there are two methods to acquire the ODT signal: the time domain method and the spectral domain method.

In the time domain method, a delay line is incorporated in the reference arm to generate a delay. A spectrogram analysis or phase-resolved algorithm is then used to determine the Doppler frequency shift. In the spectral domain method, the reference mirror is fixed, and there is no depth scan ($\tau = 0$). The spectral domain fringe signal, $P_{\mathrm{ODT}}(\nu)$, is obtained either by a spectrometer at the detection arm, or by a frequency sweeping light source. The time domain signal, $\Gamma_{\mathrm{ODT}}(\tau)$, is determined from the spectral domain signal by a Fourier transformation.

Spectrogram Method

The spectrogram method uses time–frequency analysis to calculate the Doppler shift. Signal processing algorithms to obtain structural and velocity images from recorded temporal interference fringe intensity using the spectrogram method, are illustrated in Figure 4.

The spectrogram is an estimate of the power spectrum of the temporal interference fringe intensity ($\Gamma_{\mathrm{ODT}}(\tau_i, f_j)$) in the ith time delay window. The power spectrum of the temporal interference fringe at the ith pixel, corresponding to time delay τ_i in the structural and velocity images, is calculated by a short-time fast Fourier transformation (STFFT) or a wavelet transformation:

$$\hat{\Gamma}_{\mathrm{ODT}}(\tau_i, f_m) = |\mathrm{STFFT}(f_m; \Gamma_{\mathrm{ODT}}(\tau))|^2 \qquad [18]$$

where f_m is the discrete frequency value. A tomographic structural image is obtained by calculating the value of the power spectrum at the phase modulation frequency (f_0). Fluid flow velocity is determined from the Doppler frequency shift (f_{D}), which is the difference between the carrier frequency established by the optical phase modulation (f_0) and the centroid (f_{c}) of the measured power spectrum at the ith pixel:

$$V_{\mathrm{ODT}}(i) = \frac{\lambda_0 f_{\mathrm{D}}}{2\bar{n}\cos\theta} = \frac{\lambda_0 (f_{\mathrm{c}} - f_0)}{2\bar{n}\cos\theta} \qquad [19]$$

where we have assumed, $\mathbf{k}_{\mathrm{s}} = -\mathbf{k}_{\mathrm{i}}$ and θ is the angle between $\mathbf{k}_{\mathrm{i}}$ and $\mathbf{v}$. The centroid of the measured power spectrum is determined by:

$$f_{\mathrm{c}} = \sum_m f_m \hat{\Gamma}_{\mathrm{ODT}}(\tau_i, f_m) \Big/ \sum_m \hat{\Gamma}_{\mathrm{ODT}}(\tau_i, f_m) \qquad [20]$$

Figure 5 shows the *in vivo* structural and blood flow images from a chick chorioallantoic membrane. The lumen wall, chorion membrane, and yolk sac membrane are observed in structural image (a). In the velocity image (b), static regions ($V = 0$) appear dark, while blood flowing at different velocities appears as different brightnesses on the gray scale. The velocity profile taken from a horizontal cross-section passing through the center of the vessel is shown in (c).

Phase-Resolved ODT Method

Although spectrogram methods allow simultaneous imaging of *in vivo* tissue structure and flow velocity, the velocity sensitivity is limited for high-speed imaging. When STFFT or wavelet transformation is used to calculate flow velocity, the resolution is determined by the window size of the Fourier transformation for each pixel. The minimum detectable Doppler frequency shift, f_{D}, varies inversely with the STFFT window size. Because pixel acquisition time is proportional to the STFFT window size, the image frame rate is limited by velocity resolution. Furthermore, spatial resolution is also proportional to the STFFT window size. Therefore, a large STFFT window size increases velocity resolution while decreasing imaging speed and spatial resolution. This coupling between velocity sensitivity, spatial resolution, and imaging speed prevents the spectrogram method from achieving simultaneously both high imaging speed and high velocity sensitivity, which are essential for measuring flow in small blood vessels where flow velocity is low.

Phase-resolved ODT overcomes the compromise between velocity sensitivity and imaging speed by using the phase change between sequential scans to construct flow velocity images. The phase information of the fringe signal can be determined from the complex analytical signal $\tilde{\Gamma}(t)$, which is determined through analytic continuation of the measured interference fringe function, $\Gamma(t)$, using a Hilbert transformation:

$$\tilde{\Gamma}(t) = \Gamma(t) + \frac{i}{\pi} P \int_{-\infty}^{\infty} \frac{\Gamma(\tau)}{\tau - t}\, \mathrm{d}\tau = A(t)\mathrm{e}^{i\phi(t)} \qquad [21]$$

where P denotes the Cauchy principle value, i is the complex number, and $A(t)$ and $\phi(t)$ are amplitude and phase of $\tilde{\Gamma}(t)$, respectively. Because the interference signal $\Gamma(t)$ is quasi-monochromatic, the complex


$\Gamma_{\mathrm{ODT}}(\tau_i, t)$
$|\mathrm{STFFT}|^2$
$\hat{\Gamma}_{\mathrm{ODT}}(\tau_i, f_m)$
Frequency filter
$\hat{\Gamma}_{\mathrm{ODT}}(\tau_i, f_0)$
ODT structural image
Centroid
Doppler shift
ODT velocity image

Figure 4 Signal processing algorithms for ODT structural and velocity images.



Figure 5 ODT images of *in vivo* blood flow in a CAM vein. (a) Structural image, (b) velocity image, and (c) velocity profile taken from a horizontal cross-section passing through the center of the vein, where the open circles are experimental data and the solid line is a parabolic fit. Reproduced with permission from Chen Z, MilnerTE, Srinivas S, Wang XJ, Malekafzali A, van Gemert MJC and Nelson JS (1997) Noninvasive imaging of *in vivo* blood flow velocity using optical doppler tomography. *Optics Letters* 22: 1119–1121.

analytical signal can be determined by:

$$\tilde{\Gamma}(t) = 2\int_0^\infty \int_0^\tau \Gamma(t')\exp(-2\pi i v t')\mathrm{d}t' \times \exp(2\pi i v t)\mathrm{d}v \qquad [22]$$

where τ is the time duration of the fringe signal in each axial scan.

The Doppler frequency shift (f_n) at nth pixel in the axial direction is determined from the average phase shift between sequential A-scans. This can be accomplished by calculating the phase change of sequential scans from the individual analytical fringe signal:

$$f_n = \frac{\Delta\phi}{2\pi T} = \frac{1}{2\pi T}\sum_{m=(n-1)M}^{nM}\sum_{j=1}^{N}\left[\tan^{-1}\left(\frac{\mathrm{Im}\tilde{\Gamma}_{j+1}(t_m)}{\mathrm{Re}\tilde{\Gamma}_{j+1}(t_m)}\right) - \tan^{-1}\left(\frac{\mathrm{Im}\tilde{\Gamma}_{j}(t_m)}{\mathrm{Re}\tilde{\Gamma}_{j}(t_m)}\right)\right] \qquad [23]$$

Alternatively, the phase change can also be calculated by the cross-correlation method:

$$f_n = \frac{1}{2\pi T}\tan^{-1}\left(\frac{\mathrm{Im}\left[\sum_{m=(n-1)M}^{nM}\sum_{j=1}^{N}\tilde{\Gamma}_j(t_m)\cdot\tilde{\Gamma}^*_{j+1}(t_m)\right]}{\mathrm{Re}\left[\sum_{m=(n-1)M}^{nM}\sum_{j=1}^{N}\tilde{\Gamma}_j(t_m)\cdot\tilde{\Gamma}^*_{j+1}(t_m)\right]}\right) \qquad [24]$$

where $\tilde{\Gamma}_j(t_m)$ and $\tilde{\Gamma}^*_j(t_m)$ are the complex signals at axial time t_m corresponding to the jth A-scan and its respective conjugate; $\tilde{\Gamma}_{j+1}(t_m)$ and $\tilde{\Gamma}^*_{j+1}(t_m)$ are the complex signals at axial time t_m corresponding to the next A-scan and its respective conjugate; M is an even number that denotes the window size in the axial direction for each pixel; N is the number of sequential scans used to calculate the cross correlation; and T is the time duration between A-scans. Because T is much longer than the pixel time window within each scan used in the spectrogram method, high-velocity sensitivity can be achieved.

Phase-resolved ODT decouples spatial resolution and velocity sensitivity in flow images and increases imaging speed by more than two orders of magnitude, without compromising spatial resolution and velocity sensitivity. In addition, because two sequential A-line scans are compared at the same location, speckle modulations in the fringe signals cancel each other and, therefore, will not affect the phase difference calculation. Consequently, the phase-resolved method reduces the speckle noise in the velocity image. Furthermore, if the phase difference between sequential frames is used, the velocity sensitivity can be further increased. Real-time imaging with velocity sensitivity on the order of 10 μm/s has been demonstrated.

In addition to digital processing of the fringe signal using Hilbert transformation, the complex analytical signal can also be achieved through hardware implementation. Optical Hilbert transformation using polarization optics has been implemented for real-time phase-resolved ODT imaging. Real-time ODT imaging using hardware demodulation of the ODT signal has also been demonstrated.

Spectral Domain Phase-Resolved ODT Method

A schematic diagram of a spectral domain ODT system is shown in Figure 6. The signal from the Michelson interferometer is directly coupled to a


Broadband partial coherence source
2x2 coupler
Reference arm
Reference mirror
Optical spectrometer
Sample arm
Lateral scan
CCD or linear array detector
Signal processing and display
Sample

Figure 6 Schematic diagram of a spectral domain ODT instrument.

spectrometer that records the spectral fringe pattern, $P_{\mathrm{ODT}}(\nu)$. The temporal interference fringe can be calculated by a Fourier transformation of the spectral fringe pattern (eqn [17]). The Doppler shift can then be determined from the phase shift between sequential scans using the phase-resolved ODT algorithm (eqns [23] and [24]).

Spectral domain phase-resolved ODT has the advantage that no optical delay line is required. In addition, the spectral domain method can achieve high signal to noise ratio over time domain ODT. Since parallel detection can be implemented with a high-speed spectrometer, high-speed imaging acquisition is possible. Finally, because the dynamic range of the phase-resolved ODT depends on the speed of the line scans, spectral domain ODT has the advantage in terms of imaging speed and velocity dynamic range.



Figure 7 Effect of numerical aperture and transverse flow velocity on Doppler bandwidth.

Transverse Flow Velocity and Doppler Angle Determination

One of the limitations of using the Doppler shift to determine the flow is that the technique is only sensitive to longitudinal flow velocity (Figure 2). If one knows the flow direction, Doppler shift measurement can fully quantify the flow. However, in many biological cases, where flow direction is not known, Doppler shift measurement alone is not enough to fully quantify the flow. Furthermore, there are many clinical cases, such as ocular bloodflow, where vessels are in the plane perpendicular to the probing beam. When flow direction is perpendicular to the probing beam, the Doppler shift is not sensitive to transverse bloodflow (V_{T}). Therefore, a method to measure transverse flow velocity is essential.

Standard deviation of the Doppler spectra can be used to determine the transverse flow. The technique is based on the fact that ODT imaging uses a relatively large numeric aperture lens in the sampling arm. The beam from different sides of the edges will produce different Doppler shifts, f_1 and f_2, as indicated in Figure 7. Consequently, the Doppler spectra will be broadened by the transverse flow. If the incident beam has a Gaussian spectral profile and contributions from Brownian motion and other sources that are independent of the macroscopic flow velocity are included, a linear relation between standard deviation of the Doppler spectra and transverse flow velocity, $V_{\mathrm{T}} = V \sin\theta$, can be derived:

$$\sigma = \frac{\pi V \sin\theta NA_{\mathrm{eff}}}{8\lambda} + b \qquad [25]$$

where b is a constant, and NA_{eff} is the effective numeric aperture. The standard deviation can be determined from the measured analytical fringe signal:

$$\sigma^2 = \frac{1}{2\pi^2 T^2} \times \left(1 - \frac{\left| \sum_{m=(n-1)M}^{nM} \sum_{j=1}^{N} \tilde{\Gamma}_j(t_m) \cdot \tilde{\Gamma}^*_{j+1}(t_m) \right|}{\frac{1}{2} \sum_{m=(n-1)M}^{nM} \sum_{j=1}^{N} [\tilde{\Gamma}_j(t_m) \cdot \tilde{\Gamma}^*_j(t_m) + \tilde{\Gamma}_{j+1}(t_m) \cdot \tilde{\Gamma}^*_{j+1}(t_m)]} \right) \qquad [26]$$



Figure 8 Standard deviation as a function of flow velocity for two different numeric apertures. Reproduced with permission from Ren *et al.* (2002) *Optics Letters* 27: 409–411.

The measured standard deviation as a function of transverse flow velocity is shown in Figure 8. As predicted, the Doppler bandwidth is a linear function of transverse flow velocity above a certain threshold level. The effective numerical aperture of the optical objective in the sample arm determines the slope of this dependence. This result indicates that standard deviation can be used to determine the transverse flow velocity. Since both longitudinal and transverse flow velocity (V_L and V_T) can be measured by the Doppler shift and standard deviation, respectively, flow direction can be determined from a single measurement of the Doppler fringe signal.

Applications

Due to its exceptionally high spatial resolution and velocity sensitivity, several clinical applications of ODT have been demonstrated, including screening vasoactive drugs, monitoring changes in image tissue morphology and hemodynamics following pharmacological intervention and photodynamic therapy, evaluating the efficacy of laser treatment in port wine stain (PWS) patients, assessing the depth of burn wounds, mapping cortical hemodynamics for brain research, imaging ocular bloodflow, and



Figure 9 ODT images taken *in situ* from PWS human skin. (a) Structural image, (b) histological section, (c) image before laser treatment, and (d) image after laser treatment (scale bar 100 μm). Reproduced with permission from Nelson *et al.* (2001) *Archives of Dermatology* 137: 741–744. Copyright © 2001, American Medical Association. All rights reserved.

mapping bloodflow in gastrointestinal tracts. Figure 9 shows ODT structural and flow velocity images of a patient with PWS before and after laser treatment, respectively. For comparison, a histology picture taken at the same site is included. The vessel location from the ODT measurement and histology agree very well. Furthermore, the destruction of the vessel by laser can be identified, since no flow appears on the Doppler flow image after laser treatment.

Three-dimensional images of a microvascular network can be obtained by stacking 2D scans together. It is known that the microvasculature of mammary tumors has several distinct differences from normal tissues. Mapping of a 3D cancer microvascular network could provide additional information for cancer diagnosis. Figure 10 shows multiple blood vessels imaged from a patient with an abnormal microvascular network. Different colors represent different signs of the Doppler shift, which depends on the angle between the direction of flow and probing beam.

ODT is also a powerful tool to study flow dynamics in microfluidic channels. In addition to imaging flow velocity profile, ODT can also be used to measure osmotic mobility, quantify size of the scattering particle, and study flow dynamics of microfluids in microchannels of different materials, geometry, and surface treatment.



Figure 10 Three-dimensional ODT images of multiple blood vessels in human skin from a patient with a PWS birthmark. Reproduced with permission from Zhao *et al.* (2001) *IEEE J. Select Topics Quantum Electro.* 7: 931–935. © 2001, IEEE.

Polarization Sensitive OCT

PS-OCT combines polarization sensitive detection with OCT to determine tissue birefringence. PS-OCT can obtain enhanced image contrast and additional physiological information by studying polarization properties of biological tissues. Many biological tissues, such as tendon, muscle, nerve, bone, cartilage, and skin, exhibit birefringence properties. Consequently, PS-OCT can provide contrast mechanisms that are directly related to the physiological conditions of these tissues.

The polarization state of a light beam can be described by a Stokes vector **S** as:

$$\mathbf{S} = \begin{bmatrix} I \\ Q \\ U \\ V \end{bmatrix} = \begin{bmatrix} a_x^2 + a_y^2 \\ a_x^2 - a_y^2 \\ 2a_x a_y \cos\varphi \\ 2a_x a_y \sin\varphi \end{bmatrix} \qquad [27]$$

where I, Q, U, V are Stokes parameters, a_x and a_y are amplitudes of two orthogonal components of the electric vector, and φ represents the phase difference between the two components.

The effect of an optical device on the polarization of light can be characterized by a 4×4 Mueller matrix. The matrix acts on the input state, $\mathbf{S}_1$, to give the output state, $\mathbf{S}_2$:

$$\mathbf{S}_2 = \begin{bmatrix} I_2 \\ Q_2 \\ U_2 \\ V_2 \end{bmatrix} = \mathbf{MS}_1$$

$$= \begin{bmatrix} M_{00} & M_{01} & M_{02} & M_{03} \\ M_{10} & M_{11} & M_{12} & M_{13} \\ M_{20} & M_{21} & M_{22} & M_{23} \\ M_{30} & M_{31} & M_{32} & M_{33} \end{bmatrix} \begin{bmatrix} I_1 \\ Q_1 \\ U_1 \\ V_1 \end{bmatrix} \qquad [28]$$

In the Poincaré sphere representation, a polarization state, **S**, can be represented by a point (Q, U, V). The Poincaré sphere representation provides a convenient method to evaluate changes of Stokes vectors. Determination of either the Stokes vector or the Mueller matrix allows full quantification of birefringence properties of the biological sample.

A fiber-based, high-speed PS-OCT system is shown in Figure 11. The system is similar to the ODT system, except a polarization modulator and two orthogonal detection channels are included. Due to the coherence detection intrinsic to OCT, backscattered light that



Figure 11 Fiber-based PS-OCT system. DSP: digital signal processing.

originates from incident light in different polarization states can be determined by controlling polarization states in the reference arm. Modulating the reference light in four orthogonal polarization states allows coherent detection of backscattered light from the sample under equivalent illumination in four different polarization states. The choice of orthogonal polarization states in the Poincaré sphere is important because it ensures that the birefringence measurements will be independent of the orientation of the optical axis in the sample.

For every polarization state controlled by the polarization modulator, the A-scan signals corresponding to the two orthogonal polarization diversity channels are digitized. The coherence matrix can be calculated from the complex electrical field vector from these two channels:

$$J = \begin{bmatrix} \langle E_{\mathrm{H}}^*(t)E_{\mathrm{H}}(t)\rangle & \langle E_{\mathrm{H}}^*(t)E_{\mathrm{V}}(t)\rangle \\ \langle E_{\mathrm{V}}^*(t)E_{\mathrm{H}}(t)\rangle & \langle E_{\mathrm{V}}^*(t)E_{\mathrm{V}}(t)\rangle \end{bmatrix} = \begin{bmatrix} J_{\mathrm{HH}} & J_{\mathrm{HV}} \\ J_{\mathrm{VH}} & J_{\mathrm{VV}} \end{bmatrix} \qquad [29]$$

where E_{H}, E_{V} are the components of the complex electric field vector corresponding to horizontal and vertical polarization channels, respectively, and E_{H}^*, E_{V}^* are their conjugates, respectively. The Stokes vector can be derived from the coherence matrix:

$$\begin{aligned} S_0 &= J_{\mathrm{HH}} + J_{\mathrm{VV}} & \qquad S_2 &= S_0^{-1}(J_{\mathrm{HV}} + J_{\mathrm{VH}}) \\ S_1 &= S_0^{-1}(J_{\mathrm{HH}} - J_{\mathrm{VV}}) & \qquad S_3 &= iS_0^{-1}(J_{\mathrm{VH}} - J_{\mathrm{HV}}) \end{aligned} \qquad [30]$$

where S_1, S_2, and S_3 are the normalized coordinates of the Stokes vector in the Poincaré sphere, characterizing the polarization state of the backscattered light, and S_0 is the module of the Stokes vector characterizing light intensity. The Stokes vector, corresponding to each of the input polarization states for the *n*th pixel in the *j*th A-scan, can be calculated as:

$$S_{0,n} = \sum_{m=(n-1)M}^{nM} [\tilde{\Gamma}_j^{\mathrm{H}}(t_m)\tilde{\Gamma}_j^{\mathrm{H}^*}(t_m) + \tilde{\Gamma}_j^{\mathrm{V}}(t_m)\tilde{\Gamma}_j^{\mathrm{V}^*}(t_m)]$$

$$S_{1,n} = S_{0,n}^{-1} \sum_{m=(n-1)M}^{nM} [\tilde{\Gamma}_j^{\mathrm{H}}(t_m)\tilde{\Gamma}_j^{\mathrm{H}^*}(t_m) - \tilde{\Gamma}_j^{\mathrm{V}}(t_m)\tilde{\Gamma}_j^{\mathrm{V}^*}(t_m)]$$

$$S_{2,n} = S_{0,n}^{-1} \sum_{m=(n-1)M}^{nM} 2\,\mathrm{Re}(\tilde{\Gamma}_j^{\mathrm{H}^*}(t_m)\tilde{\Gamma}_j^{\mathrm{V}}(t_m))$$

$$S_{3,n} = S_{0,n}^{-1} \sum_{m=(n-1)M}^{nM} 2\,\mathrm{Im}(\tilde{\Gamma}_j^{\mathrm{H}^*}(t_m)\tilde{\Gamma}_j^{V}(t_m)) \qquad [31]$$

where M is an integer number that determines the size of the average in the axial direction for each pixel; $\tilde{\Gamma}_j^{\mathrm{H}}(t_m)$ and $\tilde{\Gamma}_j^{\mathrm{V}}(t_m)$ are complex signals detected from the two orthogonal polarization channels at axial time t_m, for the *j*th A-scan; and $\tilde{\Gamma}_j^{\mathrm{H}^*}(t_m)$ and $\tilde{\Gamma}_j^{\mathrm{V}^*}(t_m)$ are their conjugates, respectively.

In order to measure the birefringence properties of the sample accurately, four states of light polarization are generated for each lateral pixel. For each polarization state, one A-line scan is performed. Therefore, a total of four A-line scans are used to calculate the Stokes vector and phase retardation images simultaneously.

For a sample with an assumed linear birefringence, there exists two eigenwaves that are polarized along the projected fast and slow axes of the sample normal to the propagation direction of incident light. The Stokes vectors of these eigenwaves determine a rotation axis in the equator plane of a Poincaré sphere.

The effect of birefringence is to rotate the Stokes vector about this axis through an angle that is equal to the phase retardation of the sample. Conversely, the rotation axis can be determined from the known polarization states of incident and backscattered light at the sample location. The phase retardation image, which characterizes the accumulated birefringence distribution in the sample, is calculated by the rotation of the Stokes vectors in the Poincaré sphere.

The simultaneous Stokes vectors and phase retardation images of a rat muscle are shown in Figure 12. Stokes vectors, corresponding to four different polarization states, are shown in the top figure. From Stokes vector images, the phase retardation image can be calculated as shown in the bottom figure. The banded structure in the phase retardation image indicates the accumulated tissue birefringence distribution in the rat muscle. In addition, differential optical axis and birefringence images can also be calculated.



Figure 12 Stokes vectors images (top) and phase retardation image (bottom) in fresh rat muscle. The image area is 2 mm × 5 mm. Reproduced with permission from Ren *et al.* (2003) *SPIE Proceedings* 4956: 320–327.

There are a number of clinical applications for PS-OCT, including burn depth determination and retinal fiber nerve layer thickness evaluation. Figure 13 shows *in vivo* structural and phase retardation images from rat skin burned at 100°C for 10 seconds. Although the structure image shows very little contrast, the phase retardation image clearly shows the contrast between the normal and burned regions. As light propagates into the tissue, the retardation increases due to tissue birefringence. For normal tissue, it only takes less than 20 μm to cause a phase retardation of 90°. However, for the burned tissue, it takes much thicker tissue to cause the same phase retardation. The decrease of birefringence in thermally damaged tissue can clearly be seen in PS-OCT scans in comparison to normal rat skin.

Second Harmonic OCT

SH-OCT combines SHG with coherence gating for high-resolution tomographic imaging of tissue structures with molecular contrast. SHG is the lowest-order nonlinear optical process where the second-order nonlinear optical susceptibility is



Figure 13 *In vivo* structure (top) and phase retardation image (bottom) from rat skin burned at 100°C for 10 seconds. The black contour line in the phase retardation image demarcates the depth at which 90° phase retardation has been reached with respect to the incident polarization (image size 2 mm × 10 mm).

responsible for the generation of light at second-harmonic frequency. Because second-order nonlinear optical susceptibility is very sensitive to electronic configurations, molecular structure and symmetry, local morphology, and ultrastructures, SHG provides molecular contrast for the coherence image.

The schematic diagram for SH-OCT is shown in Figure 14. A broadband short pulse laser is used as a light source in a Michelson interferometer. The light is split into the reference arm and the sample arm. In the reference arm, a thin nonlinear crystal is used to convert the input radiation to SH photons. Both SH and fundamental waves are then reflected by a metal mirror (M1) mounted on a motorized translation stage, which acts as the delay line in this SH-OCT system. A backscattered SH wave from the sample recombines with the SH wave from the reference arms to form interference fringe. The SH interference fringe signal is detected by a photomultiplier tube (PMT) after passing through a short-pass filter (F1). The fundamental interference fringe signal is detected by a photodiode (PD) after passing through a long-pass filter (F2).

A SH-OCT image of a rat tendon is shown in Figure 15. Compared with conventional OCT performed at fundamental wavelengths, SH-OCT offers enhanced molecular contrast and spatial resolution. It is also an improvement over existing SHG scanning microscopy technology as the intrinsic coherence gating mechanism enables the detection and discrimination of SH signals generated at deeper locations. The enhanced molecular contrast of SH-OCT extends conventional OCT's capability for detecting small changes in molecular structure. SH-OCT is promising for the diagnosis of cancers and other diseases at an early stage when changes in tissue and molecular structure are small.



Figure 14 Schematic of experiment set-up for SH-OCT. M1, mirror; NLC, nonlinear crystal; BS, broadband nonpolarization beamsplitter; DBS, dichroic beamsplitter; L1, lens; F1–F2, filters; PD, photo diode; PMT, photomultiplier tube.



Figure 15 SH-OCT image of a rat tendon; image size 250 μm × 250 μm. Scale bar 100 μm. Image reprinted with permission from Jiang Y *et al.* (2004) Proceedings of the 26th Annual International Conference of the IEEE Engineering in Medicine and Biology Society.

Conclusions

Optical tomography is a rapidly developing imaging technology with many potential applications. Through different contrast enhancement mechanisms, ODT, PS-OCT, and SH-OCT provide clinically important physiological information that is not available in the structure image. Given the noninvasive nature and exceptionally high spatial resolution, optical tomography can simultaneously provide tissue structure, blood perfusion, birefringence, and other physiological information and have great potential for basic biomedical research and clinical medicine.

Acknowledgments

I would like to thank many of my colleagues who have contributed to the functional OCT project at the Beckman Laser Institute and Center for Biomedical Engineering at UCI, particularly the students and postdoctoral fellows. I also want to acknowledge the research grants awarded from the National Institutes of Health (EB-00293, NCI-91717, RR-01192 and EB-00255), the National Science Foundation (BES-86924), the Whitaker

Foundation (WF-23281) and the Defense Advanced Research Program Agency (Bioflip program). Institutional support from the Air Force Office of Scientific Research (F49620-00-1-0371), and the Beckman Laser Institute Endowment are also gratefully acknowledged. Dr Chen's e-mail address is zchen@bli.uci.edu.

List of Units and Nomenclature

OCT	Optical coherence tomography
ODT	Optical Doppler tomography
PS-OCT	Polarization sensitive OCT
SH-OCT	Second harmonic OCT
STFFT	Short time fast Fourier transformation

See also

Coherence: Coherence and Imaging; Overview. **Fiber and Guided Wave Optics:** Nonlinear Optics; Optical Fiber Cables. **Imaging:** Imaging Through Scattering Media; Interferometric Imaging; Photon Density Wave Imaging. **Interferometry:** Overview. **Microscopy:** Confocal Microscopy; Imaging Multiple Photon Fluorescence Microscopy. **Polarization:** Introduction; Matrix Analysis. **Tomography:** Optical Coherence Tomography; Tomography and Optical Imaging.

Further Reading

Bouma BE and Tearney GJ (eds) (2001) *The Optical Coherence Tomography Handbook*. New York: Marcel Dekker, Inc.

Chen Z (2003) Functional optical coherence tomograpy. In: Hwang NHC and Woo LY (eds) *Frontiers in Biomedical Engineering*, pp. 345–364. New York: Kluwer Academic Publishers.

Chen Z, Milner TE, Srinivas S, Wang XJ, Malekafzali A, van Gemert MJC and Nelson JS (1997) Noninvasive imaging of *in vivo* blood flow velocity using optical doppler tomography. *Optics Letters* 22: 1119–1121.

Chen Z, Zhao Y, Srinivas SM, Nelson S, Prakash N and Frostig RD (1999) Optical Doppler tomography. *IEEE Journal of Selected Topics in Quantum Electronics* 5(4): 1134–1142.

de Boer JF and Milner TE (2002) Review of polarization sensitive optical coherence tomography and Stokes vector determination. *Journal of Biomedical Optics* 7: 359–371.

Fercher AF and Hizenberger CK (2002) Optical coherence tomography. *Progress in Optics* 44: 215–296.

Huang D, Swanson EA, Lin CP, *et al.* (1991) Optical coherence tomography. *Science* 254: 1178–1181.

Izatt JA, Kulkarni MD, Yazdanfar S, Barton JK and Welch AJ (1997) *In vivo* bidirectional color Doppler flow imaging of picoliter blood volumes using optical coherence tomography. *Optics Letters* 22: 1439–1441.

Jiang Y, Tomov I, Wang Y and Chen Z (2004) Second harmonic optical coherence tomography. *Optics Letters* 29: 1090–1092.

Jiao S and Wang LV (2002) Jones-matrix imaging of biological tissues with quadruple-channel optical coherence tomography. *Journal of Biomedical Optics* 7: 350–358.

Masters BR and Thompson BJ (eds) (2001) *Selected Papers on Optical Low-Coherence Reflectometry & Tomography*. SPIE Milestone Series, vol. MS 165. Bellingham, WA: SPIE Optical Engineering Press.

Tuchin VV (ed.) (2004) *Coherent-Domain Optical Methods for Biomedical Diagnostics, Environmental and Material Science*, vol. 2. Boston, MA: Kluwer Academic Publishers.

Vo-Dinh T (ed.) (2003) *Biomedical Photonics Handbook*. New York: CRC Press.

U

ULTRAFAST LASER TECHNIQUES

Contents

Generation of Femtosecond Pulses
Pulse Characterization Techniques

Generation of Femtosecond Pulses

D T Reid, Heriot-Watt University, Edinburgh, UK

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Optical pulses from femtosecond lasers represent some of the shortest physical events ever observed and their high instantaneous powers allow them to be focused to intensities that can heat and compress matter to resemble the extreme conditions found in a nuclear explosion. The extreme units of time and power needed to describe this area of physics can easily distract from the simple and elegant techniques by which femtosecond pulses can be generated. The review presented here is divided into two main sections. The first explains the theory of pulse generation and shaping and the second concentrates on actual femtosecond laser sources in common use today.

Theory of Femtosecond Pulse Generation

Active Mode-locking

In an inhomogeneously broadened laser system, optical frequencies within the emission bandwidth of the material can experience gain simultaneously at discrete frequencies corresponding to the longitudinal modes of the laser resonator. In the absence of any mechanism to coherently couple energy between these modes, the laser will operate with a continuous-wave (cw) output containing a narrow band of frequencies whose roundtrip cavity gain is highest. An alternative operating regime exists in which each mode is related to its neighbor by a fixed phase relationship and it is this mode-locked condition that is used to generate a periodic sequence of ultrashort optical pulses.

To understand how mode-locking works, consider the frequency separation between adjacent longitudinal resonator modes which can be expressed as

$$\Delta\omega = 2\pi c/l \qquad [1]$$

where l is the optical roundtrip length of the resonator and c is the speed of light. If the nth longitudinal mode has an amplitude E_n then the total optical field can be denoted in complex notation as

$$E(t) = \sum_n E_n \exp \mathrm{i}[(\omega_0 + n\Delta\omega)t + n\Delta\varphi] \qquad [2]$$

with ω_0 being the center frequency of the output and $\Delta\varphi$ being the phase difference between adjacent modes. Figure 1 illustrates how a simple pulse can be produced by coherently adding together adjacent modes. In Figure 1a, three modes with equal amplitudes and the same initial phase ($\Delta\varphi = 0$) are interfered to give a pulse. As further modes are added (Figure 1b) the pulse duration decreases.

Coupling of energy between adjacent cavity modes can be achieved in practice by modulating either the



Figure 1 The principles of mode-locking: (a) three adjacent modes add coherently to produce a pulse; (b) shorter pulses require a larger number of *n* coupled modes.

intracavity loss (amplitude modulation (AM) mode-locking) or the intracavity phase (frequency modulation (FM) mode-locking). A common practical amplitude modulator is an acousto-optic modulator and for operation in the visible and near-infrared, fused silica is a common acousto-optic modulator material. Lithium-niobate devices based on the Pockels effect are the most commonly used phase modulators and are attractive for mode-locked fiber-laser applications because fiber-pigtailed waveguide devices are readily available.

Active mode-locking has been employed in a wide variety of laser systems including argon ion, dye, erbium-doped fiber, semiconductor, and solid-state lasers. Unlike passive mode-locking, no optical nonlinearity is required which means that actively mode-locked lasers can be operated with low intracavity powers. The technique is particularly suitable for mode-locked sources which require active synchronization to an external clock source.

A form of 'optical' active mode-locking exists in which gain modulation resulting from optical pumping using another mode-locked laser is the mode-locking mechanism. Known as synchronously pumped mode-locking, this technique has been used to obtain ultrashort pulses from oscillators incorporating gain media of laser or nonlinear optical materials. The technique is most appropriate to laser gain materials which have a short-lived fluorescence lifetime and whose gain therefore exhibits a significant change when the pump light is modulated at high frequencies. Synchronous pumping has been used to generate mode-locked pulses from color-center lasers, dye lasers, and optical parametric oscillators.

Passive Mode-locking

To produce the shortest optical pulses, passive mode-locking, a technique based on exploiting intracavity optical nonlinearities, must be employed. Unlike the active technique, the strength of the mode-locking action increases as the propagating pulses shorten and their peak intensities rise. One consequence of this nonlinear behavior is that the passive technique commonly generates and mode-locks entirely new cavity frequencies which were not originally present during cw operation.

Passive mode-locking has been implemented using a wide range of different nonlinear effects, but in every technique the mode-locking process can be described in terms of dynamic loss saturation combined, in certain systems, with dynamic gain saturation. The principal mode-locking element is a saturable absorber whose loss decreases as the incident pulse intensity increases. A saturable absorber can take the form either of a resonant component such as a solid-state semiconductor device or a dye jet with a fixed absorption wavelength, or a nonresonant component that replicates a saturable-absorber-like action using self-focusing or self-phase-modulation effects. Saturable absorbers can be categorized as either slow saturable absorbers or fast saturable absorbers, depending on whether their recovery time is longer or shorter than the pulse duration, respectively. The pulse-shaping mechanisms are different in each case and will be described separately.

Slow saturable absorbers are physical devices, commonly dye molecules in solution or semiconductor-doped glass, which rely on resonant excitation to produce an excited electronic state whose transmission is greater than that of the ground state. When an optical pulse is incident on a slow absorber, its leading edge is absorbed and creates an excited state which is relatively transparent to the trailing edge. In a laser medium whose gain is readily saturated, a pulse propagating first through the absorber and then through the gain medium experiences a 'gain window' with a finite duration which strongly shapes the pulse (see Figure 2a,b).

A fast saturable absorber is required to realize mode-locking in laser media which are not easily saturated. The time-dependent gain and loss profiles of the absorber and the gain medium are again depicted in Figure 2c,d and refer to an absorber with both a rapid response and recovery time. In this system, the dynamics of the absorber and gain medium no longer represent the limiting factor influencing the pulse duration, and other effects such as linear and nonlinear dispersion become the dominant pulse-shaping mechanisms.

Pulse Shaping by Material Dispersion

Intense pulses propagating in a mode-locked laser experience strong linear and nonlinear shaping effects associated, respectively, with group-velocity dispersion and self-phase-modulation. Contributions to the net intracavity dispersion arise from the gain medium, the cavity mirrors, other elements such as intracavity prisms, even the air in the beam path. Dispersive effects in materials originate as a result of a frequency-dependent dielectric susceptibility:

$$P(\omega) = \varepsilon_0 \chi^{(1)}(\omega)E(\omega) + \varepsilon_0 \chi^{(2)}(\omega)E(\omega)^2 + \varepsilon_0 \chi^{(3)}(\omega)E(\omega)^3 + \cdots \quad [3]$$

which is due to physical resonances (poles) in the electronic response to an applied E-field.

Linear dispersion

Linear dispersion refers to the variation of the refractive index associated with the real part of the $\chi^{(1)}$ term, namely,

$$n_0 = \sqrt{1 + \mathrm{Re}\{\chi^{(1)}\}} \quad [4]$$

and leads to a wavelength-dependent group velocity which is responsible for pulse broadening and break-up in optical systems. Dispersive effects are best analyzed in terms of optical phase which is related to the refractive index by

$$\varphi(\omega) = \frac{n_0(\omega)\omega L}{c} \quad [5]$$

where L is the medium length and c is the vacuum speed of light. The local variation of the spectral



Figure 2 Saturable absorber action: (a) intracavity gain and loss profiles for a laser comprising a slow saturable absorber and a rapid relaxation time gain medium, and (b) the net gain (gain − loss) for this system; (c) gain and loss profiles for a laser comprising a near-instantaneous saturable absorber and a slow relaxation time gain medium, and (d) the net gain for this system.

phase due to an optical medium can be represented as the Taylor series

$$\varphi(\omega) = \varphi(\omega_0) + (\omega - \omega_0)\frac{\mathrm{d}\varphi}{\mathrm{d}\omega}\bigg|_{\omega_0} + \frac{1}{2}(\omega - \omega_0)^2 \frac{\mathrm{d}^2\varphi}{\mathrm{d}\omega^2}\bigg|_{\omega_0} + \left|\frac{1}{6}(\omega - \omega_0)^3 \frac{\mathrm{d}^3\varphi}{\mathrm{d}\omega^3}\right\|_{\omega_0} + \cdots \qquad [6]$$

where ω_0 is the center frequency of the incident light. When an ultrashort pulse propagates through the medium, only the quadratic and higher-order terms in [6] have a direct influence on the shape of the pulse in time. The $(\omega - \omega_0)^2$ term is responsible for adding linear chirp which refers to a time-varying linear increase or decrease in the instantaneous optical frequency across the pulse. Obtaining the shortest pulses from a mode-locked laser requires the quadratic and higher-order terms in the roundtrip intracavity spectral phase to be zero. In practice this means minimizing the material group-velocity dispersion of the gain medium by using a short but highly doped laser crystal and then identifying additional optical elements whose group-velocity dispersion is equal in magnitude but opposite in sign to that of the crystal. Optical components for compensating group-velocity dispersion fall into two categories: those which use bulk optics and geometry to achieve a wavelength-dependent path length, and others based on interference effects within a dielectric optical coating.

Geometrical methods of dispersion compensation are commonly based on pairs of diffraction gratings or prisms and in both cases the geometry of the systems means that the group delay is wavelength dependent and can be made greater for longer wavelengths than for shorter ones. Analytic expressions describing the quadratic and cubic spectral phase of prism and diffraction grating pairs are summarized in Table 1. Dispersion compensation using prisms has been extremely successful and 11-fs pulses were reported using this approach. The simultaneous compensation of arbitrary second- and third-order spectral phase is, however, difficult and involves identifying a suitable prism material, apex spacing, and tip insertion. The expressions listed in Table 1 indicate that the form of the spectral phase depends on the refractive index of the prism material and its wavelength derivatives, while the apex separation, l, also contributes to a large extent. A further contribution to the spectral phase comes from the glass encountered by the beam passing through the prism tips which contributes a positive dispersion described by the equations for a bulk material given in Table 1. In general, an iterative solution of the equations given in Table 1 is needed to determine the geometry of a prism pair suitable for producing a desired spectral phase profile.

Laser cavity mirrors can be designed with chirped multilayer dielectric coatings which possess a chosen group-velocity dispersion profile. A Bragg mirror with smaller layer periods at the surface and larger periods deeper in the coating provides negative group-velocity dispersion because the longer wavelengths experience larger group delays within the coating than the shorter ones. These chirped mirrors provide constant reflectivity across their stopband and therefore only modify the spectral phase of a pulse, leaving the intensity unchanged. The design of chirped mirrors has been refined in recent years to enhance their operating bandwidth and to reduce undesirable modulations in the group-delay response. The technique has been used to obtain 6.5-fs pulses directly from a Ti:sapphire oscillator and to achieve compression of amplified pulses to below 5 fs.

Nonlinear dispersion

Nonlinear effects arise in all materials due to the $\chi^{(3)}$ term in [3]. In a transparent medium the refractive index due to this net susceptibility is approximately

$$n \approx n_0 + \frac{\chi^{(3)} E^2}{2n_0} = n_0 + n_2 I \qquad [7]$$

where I is the optical intensity. The importance of the $\chi^{(3)}$ susceptibility is therefore that it causes the refractive index to become intensity-dependent, and significant changes in the refractive index can be induced by the high peak intensities of ultrashort pulses.

Self-phase-modulation (SPM) resulting from the nonlinear refractive index is essential in generating the shortest pulses from modern ultrafast lasers and is caused by the time-varying intensity profile of the pulse. The higher-intensity components induce a larger nonlinear refractive index change and therefore experience a greater phase shift than the weaker components. The resulting frequency shift across the pulse can be shown to be

$$\Omega(t) = -\frac{\mathrm{d}\phi(t)}{\mathrm{d}t} = -\frac{\omega n_2 L}{c}\frac{\mathrm{d}I(t)}{\mathrm{d}t} \qquad [8]$$

which describes a redshift of the pulse leading edge and a blueshift of the trailing edge. Only the pulse center frequency remains unchanged and SPM therefore broadens the pulse spectrum by redistributing energy from the center to the wings. Across the center of the pulse, SPM leads to an approximately linear positive chirp that, with appropriate optics, can be

Table 1 Expressions for the second and third-order dispersion of common optical systems

Bulk material, thickness *t* 	$\frac{d^2\varphi}{d\omega^2} = t\frac{\lambda^3}{2\pi c^2}\frac{d^2n}{d\lambda^2}$ $\frac{d^3\varphi}{d\omega^3} = -t\frac{\lambda^4}{4\pi^2c^3}\left(3\frac{d^2n}{d\lambda^2} + \lambda\frac{d^3n}{d\lambda^3}\right)$
Double-pass prism-pair, apex separation *l*, angular deviation within ray of *β* 	$\frac{d^2\varphi}{d\omega^2} = \frac{\lambda^3}{2\pi c^2}\frac{d^2P}{d\lambda^2}$ $\frac{d^3\varphi}{d\omega^3} = -\frac{\lambda^4}{4\pi^2c^3}\left(3\frac{d^2P}{d\lambda^2} + \lambda\frac{d^3P}{d\lambda^3}\right)$ $\frac{d^2P}{d\lambda^2} = 4l\sin\beta\left[\frac{d^2n}{d\lambda^2} + (2n - 1/n^3)\left(\frac{dn}{d\lambda}\right)^2\right] - 8l\cos\beta\left(\frac{dn}{d\lambda}\right)^2$ $\frac{d^2P}{d\lambda^3} = l\cos\beta\left[\left(24/n^3 - 48n\right)\left(\frac{dn}{d\lambda}\right)^3 - 24\frac{dn}{d\lambda}\frac{d^2n}{d\lambda^2}\right] + l\sin\beta\left[\begin{matrix}\left(\frac{dn}{d\lambda}\right)^3\left(12/n^6 + 12/n^4 + 8/n^3 - 16/n^2 + 32n\right)\\ +\left(24n - 12/n^3\right)\frac{dn}{d\lambda}\frac{d^2n}{d\lambda^2} + 4\frac{d^3n}{d\lambda^3}\end{matrix}\right]$
Double-pass grating-pair, separation *l*, angle of incidence *γ*, line spacing *d* 	$\frac{d^2\varphi}{d\omega^2} = l\frac{\lambda^3}{\pi c^2d^2}\left[1 - \left(\frac{\lambda}{d} - \sin\gamma\right)^2\right]^{-3/2}$ $\frac{d^3\varphi}{d\omega^3} = -6l\frac{\lambda^4}{c^3d^2}\left(1 + \frac{\lambda}{d}\sin\gamma - \sin^2\gamma\right)\left[1 - \left(\frac{\lambda}{d} - \sin\gamma\right)^2\right]^{-5/2}$

corrected using an equal but opposite amount of negative second-order dispersion. The combination of spectral broadening using SPM and subsequent chirp-removal using linear dispersion is the basis for optical pulse compression techniques that have been applied effectively to create pulses which exist for only a few carrier-wave periods.

When the pulse propagates in an environment where SPM and linear dispersion are well balanced and evenly distributed, a soliton will evolve which, in the absence of loss, can propagate indefinitely without changing shape. The nonlinear Schrödinger equation predicts that lasers in which the dominant pulse-shaping mechanisms are negative group-velocity dispersion and self-phase-modulation will produce soliton-like pulses with a $\mathrm{sech}^2(t)$ intensity profile. In experimental measurements of ultrafast lasers the pulse shape is commonly assumed to be $\mathrm{sech}^2(t)$ and the chirp of the pulses is then estimated by measuring their duration–bandwidth product, $\Delta\nu\Delta\tau$, which is a dimensionless quantity that can be treated as a figure-of-merit for ultrashort pulses. For unchirped pulses the duration–bandwidth product is independent of their duration or spectral bandwidth but is sensitive to their shape: chirp-free Gaussian pulses have $\Delta\nu\Delta\tau = 0.441$ while $\mathrm{sech}^2(t)$ pulses have $\Delta\nu\Delta\tau = 0.315$.

Sources of Femtosecond Pulses

Dye Lasers

The first practical passively mode-locked ultrafast lasers were those based on a gain medium of a thin (~10 μm) organic dye jet and incorporating a slow saturable absorber jet at a separate cavity focus. The most common combination was Rhodamine 6G in ethylene glycol (gain jet) and 3,3-diethyloxadicarbocyanine iodide in ethylene glycol (absorber jet) which produced pulses at a wavelength of 620 nm. The most successful approach was colliding-pulse mode-locking in which two counter-propagating pulses within a ring cavity are synchronized to arrive simultaneously at the absorber jet, so achieving greater saturation of the absorber and allowing the pulses to be transmitted with a loss significantly smaller than in the single-pulse case. The first sub-100-fs optical pulses were reported in 1981 from a colliding-pulse mode-locking dye laser and later work reported pulse durations as low as 27 fs but the configuration was inefficient and produced low average output powers. Other approaches such as synchronous pumping and hybrid mode-locking produced higher output powers but the maintenance-intensive nature of dye lasers and the hazardous nature of many of the chemicals used led to their gradual replacement by more convenient solid-state alternatives, based principally on Ti:sapphire.

Color-Center Lasers

A new source of femtosecond pulses in the near-infrared was reported in 1984. Coined the soliton laser the system was a synchronously pumped KCl:Tl color-center laser tunable from 1.4 to 1.6 μm and modified to allow direct generation of pulses as short as 50 fs, substantially shorter than the 8 ps achieved in synchronously pumped operation alone. Femtosecond operation was achieved by coupling a length of polarization-preserving anomalously dispersive fiber to the main laser cavity using a beamsplitter and retroreflector arrangement. This coupled-cavity arrangement later became known as additive pulse mode-locking (APM) and produced short pulses when the optical length of the fiber was adjusted to be an integral multiple of the main cavity length. The long upper-state lifetime of the laser-active centers in the KCl:Tl gain medium allowed particularly stable APM operation, but mode-locking of this kind was also successfully employed in an actively stabilized NaCl:OH$^-$ color-center laser to produce 110-fs pulses. The need to maintain color-center crystals at liquid-nitrogen temperatures limited the convenience of these lasers but until the advent of Ti:sapphire they remained the only solid-state sources capable of femtosecond operation.

Ti:sapphire Lasers

The creation in 1986 of a new broadband laser material – titanium-doped sapphire or Ti:sapphire – began a revolution in ultrafast laser sources that still continues today. Unlike other contemporary solid-state materials for mode-locked lasers such as Nd:YAG, Ti:sapphire is a vibronic gain medium which exhibits a strong electron-phonon coupling between the titanium ion transition and the host lattice. This vibronic coupling leads to a broad continuum of possible transition energies and results in a fluorescence bandwidth covering 670–1050 nm, making Ti:sapphire capable of supporting extremely short femtosecond pulses. The long fluorescence lifetime of Ti:sapphire means that, unlike dye lasers, femtosecond mode-locking requires a passive method using a fast saturable absorber and two methods have prevailed and are discussed below.

The first passively mode-locked Ti:sapphire lasers were based on the APM technique in which mode-locking is achieved by a fast-saturable absorber action due to interference between the intracavity pulse and a self-phase-modulated replica propagating in an auxiliary cavity. An important breakthrough was made in 1990 when it was reported that an APM Ti:sapphire laser continued to operate even when the auxiliary cavity was blocked. This discovery was attributed to an entirely new mode-locking effect known as Kerr-lens mode-locking (KLM) or self-mode-locking in which the presence of a Kerr lens within the gain medium during mode-locked operation changes the mode focusing within the cavity so that, compared to cw operation, mode-locked pulses experience higher gain. Two configurations of KLM exist and are known as soft aperture mode-locking, where the presence of the Kerr lens increases the gain by improving the overlap between the pump and laser modes, and hard-aperture mode-locking, in which a physical aperture such as a slit or the edge of a prism is adjusted to introduce greater loss for cw operation. Because KLM is based on a nonresonant nonlinearity, Ti:sapphire lasers can be mode-locked at any wavelength in their gain bandwidth using this technique. Recent advances in controlling the intracavity group-velocity dispersion characteristics have led to the generation of sub-5-fs pulses directly from a Ti:sapphire oscillator. The principal drawback of the KLM method is that it is not self-starting because mode-locked operation must be seeded by an intense noise spike or other short fluctuation. Different starting methods have been applied successfully including mirror tapping, acousto-optic modulation, and mode-dragging, and once mode-locking has been initiated it is generally stable until some external perturbation disturbs the intracavity beam.

An alternative method for obtaining femtosecond pulses has been pioneered largely in parallel with the KLM efforts and is based on using resonant nonlinearities in semiconductors as fast saturable absorbers. The approach is to fabricate a semiconductor multiple-quantum-well (MQW) device whose bandgap has been chosen to match the laser wavelength and whose absorption can be saturated at high fluences. Initially these devices were utilized in an APM geometry in which the MQW device was situated in an auxiliary cavity but it was later realized that an equivalent monolithic configuration could be obtained by sandwiching the MQW layer between two high-reflectivity mirrors (see Figure 3, inset) to form a Fabry–Perot structure and the resulting element was known as an antiresonant Fabry–Perot saturable absorber. The first application of a such a semiconductor saturable absorber mirror (SESAM) for mode-locking Ti:sapphire was reported in 1995 where self-starting operation was demonstrated. A typical modern Ti:sapphire laser design is shown in Figure 3 and illustrates how a saturable absorber mirror can be integrated into the cavity. Further design enhancements such as reducing the finesse of the Fabry–Perot cavity resulted in SESAMs with a broader wavelength response which enabled sub-10-fs self-starting operation.

Fiber Lasers

Ultrafast fiber lasers, particularly those based on silica doped with rare earth Er^{3+}, Nd^{3+}, or Yb^{3+}ions, have enjoyed renewed attention in recent years as efforts to scale their average output powers and pulse energies to practical levels have proved successful. Four main mode-locking strategies have been applied to these systems: active mode-locking which is generally restricted to picosecond generation; intensity-dependent feedback using a nonlinear amplifying loop mirror; polarization APM; and semiconductor saturable absorber mode-locking. The upper-state lifetime of rare-earth-doped fibers is long and therefore a fast saturable absorber mechanism is necessary for passive mode-locking, limiting the choice of mode-locking elements to those based on Kerr or semiconductor nonlinearities.



Figure 3 Typical configuration of a modern femtosecond Ti:sapphire laser. PL, pump laser; M1, pump focusing mirror; M2, high-reflectivity cavity mirror (800 nm); TS, Ti:sapphire crystal, typically, 2–10 mm long; M3, SESAM mirror; P, dispersion-compensating prisms; OC, output coupler. Inset: a simplified schematic of a saturable-absorber Bragg mirror.

The development of mode-locked fiber sources has concentrated on Er-doped lasers because of the compatibility of their output wavelengths with the 1.5 μm optical communication window in standard silica fiber. Passively mode-locked designs based on the nonlinear loop mirror work by exploiting the Kerr effect in an intracavity fiber Sagnac interferometer containing a gain section. With suitable control of the intracavity polarization, such a nonlinear amplifying loop mirror (NALM) can be set up to transmit light of high intensities but reflect low intensities because of the differential phase shift induced between the two interferometer arms. By adding the loop mirror to a unidirectional ring cavity a figure-of-eight laser is formed (Figure 4) which is capable of producing femtosecond soliton pulses with average powers of around 1 mW. Drawbacks of the figure-of-eight laser include the presence of spectral sidebands at the shortest pulse durations and a tendency for multiple pulse operation. Mode-locking can also be achieved



Figure 4 Schematic of a figure-of-eight femtosecond fiber laser. EDFA, erbium-doped fiber amplifier gain section; OC, output coupler; PC, polarization controller.

using a variation on the APM technique and significant average output powers have been demonstrated from stretched-pulse-APM lasers, with up to 90 mW being reported at pulse energies of 2.25 nJ.

Semiconductor saturable absorber mode-locking has been demonstrated in fiber lasers using a variety of configurations including bulk InGaAsP on InP and saturable Bragg reflectors based on InGaAs/InP MQWs on a AlAs/GaAs mirror structure. Fiber lasers mode-locked using semiconductor saturable absorbers are self-starting and exhibit stable mode-locking, normally at the fundamental cavity frequency. The narrow bandwidth of saturable absorber devices at near-infrared wavelengths makes the generation of sub-100-fs pulses difficult.

Semiconductor Sources

Diode lasers and external-cavity lasers based on semiconductor optical amplifiers (SOAs) are of importance because of their ability to produce ultrashort pulses from a compact system at wavelengths of relevance to optical fiber communications. The two principal methods used to generate ultrashort pulses from such devices are mode-locking with an external cavity or gain-switching (equivalently known as *Q*-switching) in a bow-tie waveguide structure. Subpicosecond pulse durations are now routinely produced using dispersion compensation and/or nonlinear pulse compression techniques and, by combining these strategies with Er:fiber amplification, 20-fs pulses have been produced. The mode-locking and gain-switching techniques each have their individual advantages. Gain-switching provides a simple and compact approach offering high average output power, but significant timing jitter and poor spectral quality can accompany pulses produced in this way. Mode-locked systems are physically larger than gain-switched devices because they require an external cavity and additional optical components, but shorter and higher quality pulses are achievable.

Other Common Solid-State Laser Sources

Certain solid-state gain media offer the potential for direct diode pumping, miniaturization and operation at wavelengths or average powers not accessible with other sources. Systems based on Nd or Cr ion transitions have been shown to be capable of ultrashort picosecond or femtosecond operation. Femtosecond mode-locking (175 fs) has been reported in Nd:glass which has one of the broadest fluorescence spectra of the Nd materials. Crystals with active ions of Cr^{2+}, Cr^{3+}, and Cr^{4+} have broad transitions covering wavelengths in the 2.0 μm, 800 nm and 1.4 μm regions and femtosecond operation has been demonstrated in Cr^{4+}:YAG at 1.52 μm, Cr^{4+}:Mg_2SiO_4 (Cr:forsterite) at 1.25 μm, Cr^{3+}:$LiSrAlF_4$ (Cr:LiSAF) at 850 nm, and Cr^{3+}:$LiSrGaF_6$ (Cr:LiSGAF). Direct diode pumping of Cr-ion-based lasers is attractive because of the opportunities for producing low-noise, compact, and efficient femtosecond sources, but the limited power available from high-quality pump diodes results in low intracavity powers which make KLM operation difficult. As a result, stable operation is better achieved using a physical saturable absorber, and SESAM mode-locking has been applied successfully to many of these lasers.

Sources Based on Nonlinear Frequency Conversion

Laser sources alone are unable to provide ultrashort pulses continuously tunable from the ultraviolet to the mid-infrared, and large gaps exist at wavelengths where no broadband laser materials are available. Harmonic generation using Ti:sapphire can be used to access some parts of the visible and ultraviolet regions, but infrared and certain visible wavelengths cannot be generated in this way and coverage is limited by the ability to tune the source itself. The nonlinear production of infrared wavelengths requires parametric down-conversion using a synchronously pumped optical parametric oscillator. Ti:sapphire pumped synchronously pumped optical parametric oscillators have produced, either directly or using harmonic generation, outputs from the green to beyond 7 μm.

Sources of Amplified Ultrashort Pulses

Modern ultrafast oscillators can produce pulses with peak powers of >1 MW, average powers of several watts, and cavity frequencies from 4 MHz to 2 GHz, but many applications require pulses with higher intensities or lower pulse repetition frequencies. Additional amplification stages can be used to satisfy these requirements and these are commonly implemented in Nd:glass for picosecond pulses and Ti:sapphire for femtosecond pulses. In order to avoid damage and unwanted nonlinear effects caused by high pulse intensities within the amplifier system, most practical sources now apply the chirped-pulse amplification (CPA) approach in which a low-energy femtosecond seed pulse is stretched to subnanosecond durations to reduce its peak power then amplified and finally compressed to its original duration. Using the chirped-pulse amplification technique, pulses with peak powers as high as 1.5 petawatt have been generated.

Two possible amplifier geometries are used which are categorized either as multipass or regenerative amplifiers. In the multipass configuration the injected pulse is refocused many times through the same gain crystal using a system of mirrors. The gain crystal is pumped above the saturation fluence in order to extract the maximum stored energy from the medium per pass. The multipass geometry is more commonly used for high-average-power operation and critical alignment is required to maximize the overlap between the pump mode profile and the multiple beams intersecting the gain medium. The alternative regenerative amplifier is essentially a stable laser resonator which includes a Pockel cell and a polarizing beamsplitter to enable pulses to be switched into and out of the cavity. The gain per pass is considerably lower than in the multipass configuration but regenerative systems produce superior beam quality and their performance can be optimized without affecting the beam pointing of the output. Commercially available Ti:sapphire amplifiers commonly use the regenerative method and are available with pulse energies of up to 1 mJ at repetition frequencies in the 1–300 kHz range.

Further Reading

Agrawal GP (1995) *Nonlinear Fiber Optics*. San Diego, CA: Academic Press.

Duling IN (1995) *Compact Sources of Ultrashort Pulses*. Cambridge University Press.

Fork RL, Martinez OE and Gordon JP (1984) Negative dispersion using pairs of prisms. *Optics Letters* 9: 150–152.

Keller U, Weingarten KJ, Kartner FX, *et al.* (1996) Semiconductor saturable absorber mirrors for femtosecond to nanosecond pulse generation. *Solid-State Lasers, IEEE Selected Topics in Quantum Electronics* 2: 435–453.

Siegman AE (1986) *Lasers*. University Science Books.

Spence DE, Kean PN and Sibbett W (1991) 60-fsec pulse generation from a self-mode-locked Ti-sapphire laser. *Optics Letters* 16: 42–44.

Szipocs R, Ferencz K, Spielmann C and Krausz F (1994) Chirped multilayer coatings for broad-band dispersion control in femtosecond lasers. *Optics Letters* 9: 201–203.

Yariv A (1989) *Quantum Electronics*. New York: Wiley.

Pulse Characterization Techniques

D J Kane, Southwest Sciences, Inc., Santa Fe, NM, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Ultrashort optical pulses have very short time durations, typically less than a few tens of picoseconds. As a result, these pulses are spectrally broad. Because the index of refraction of materials is a function of wavelength, different wavelengths of light travel at different speeds in optical materials, causing the properties of ultrashort optical pulses to change as they propagate. However, the shape of the pulse can influence how the pulse itself interacts with materials. Thus, the goal of ultrafast laser pulse measurement is to obtain not only the intensity profile of the pulse, but also the actual variation of the frequencies that make up the pulse. This is called measuring the intensity and phase of the pulse, respectively.

Even though the development of techniques to characterize ultrashort optical pulses has not been easy, a myriad of pulse measurement techniques have been developed. In this chapter, we will confine our discussion to the most well-known pulse and generally accepted pulse characterization methods in an effort to provide a basic working knowledge of pulse measurement techniques and a fundamental understanding of the principles behind pulse measurement. After a brief discussion of the mathematical representation of ultrashort optical pulses, we will discuss pulse measurement in (roughly) chronological order, starting with autocorrelation methods. The next section introduces a useful method for the measurement of the relative phase between two pulses called spectral interferometry (SI). Following SI, we introduce the notion of the time-frequency representation of ultrashort optical pulses where techniques such as frequency-resolved optical gating (FROG) are discussed. Following the time-frequency section, a relatively new technique known as spectral phase interferometry for direct electric field reconstruction (SPIDER) is discussed.

Mathematical Representation of an Optical Pulse

The time-dependent variations of the pulse are embodied in the pulse electric field, $A(t)$, which can be written:

$$A(t) = \mathrm{Re}[E(t)\mathrm{e}^{\mathrm{i}\omega_0 t}] \qquad [1]$$

where ω_0 is the carrier frequency and Re refers to the real part. While we can use $A(t)$ as it stands for calculations, it is much easier to remove the rapidly varying ω_0 part, $\mathrm{e}^{\mathrm{i}\omega_0 t}$, and use a slowly varying envelope together with a phase term that contains only the frequency variations, not the rapidly varying carrier frequency:

$$E(t) = [I(t)]^{1/2}\mathrm{e}^{\mathrm{i}\varphi(t)} \qquad [2]$$

where $I(t)$ and $\varphi(t)$ are the time-dependent intensity and phase of the pulse. (Note that $E(t)$ is complex.) The frequency variation, $\Omega(t)$, is the derivative of $\varphi(t)$ with respect to time:

$$\Omega(t) = -\mathrm{d}\varphi(t)/\mathrm{d}t \qquad [3]$$

The pulse field can be written equally well in the frequency domain by taking the Fourier transform of eqn [2]:

$$\tilde{E}(\omega) = [\tilde{I}(\omega)]^{1/2}\mathrm{e}^{-\mathrm{i}\phi(\omega)} \qquad [4]$$

where $\tilde{I}(\omega)$ is the spectrum of the pulse, and $\phi(\omega)$ is its phase in the frequency domain. The spectral phase contains time versus frequency information; that is, the derivative of the spectral phase with respect to frequency yields the time arrival of the frequency – the group delay.

Obtaining the intensity and phase, $I(t)$ and $\varphi(t)$ (or $\tilde{I}(\omega)$ and $\phi(\omega)$) is called full characterization of the pulse. Common phase distortions include linear chirp, where the phase (either the time domain or frequency domain) is parabolic. When the frequency is increasing in time, the pulse is said to have positive linear chirp; negative linear chirp is when the high frequencies lead the lower frequencies. Higher-order chirps are common, but for these, differentiation between spectral and temporal chirp is required because spectral phase and temporal phase are not interchangeable.

Autocorrelation

Traditionally, we measure events using shorter events. Unfortunately, for the ultrafast researcher, shorter events do not exist and modern electronics are not fast enough. Therefore, because the shortest event we have is the event we wish to measure, traditional pulse measurement methods use the pulse itself to determine the approximate duration of the pulse in question giving birth to the ubiquitous intensity autocorrelation (see Figure 1). While autocorrelations cannot be used to fully characterize ultrashort optical pulses, the methods used in autocorrelations are fundamental to all pulse measurement schemes.

The intensity autocorrelation is measured by combining a pulse and a delayed replica of a pulse in a nonlinear medium such as a second harmonic generation (SHG) crystal. A pulse is sent onto a beamsplitter to produce the two replicas. One pulse is delayed relative to the other and both are focused together into a SHG crystal. As the delay of one pulse relative to the other is varied, the intensity of the second-harmonic signal is recorded. The intensity autocorrelation is not limited to using SHG; any nonlinearity may be utilized. Indeed, two-photon absorption in a semiconductor LED or photodiode often acts as a convenient nonlinearity. Sometimes a third-order nonlinearity is used to provide some direction of time information about the pulse. When the generation of the signal involves phase matching, such as second harmonic generation, care must be taken to use a thin crystal. Typically, 10 μm to 1 mm thick SHG crystals are used, depending on the bandwidth of the pulse to be measured. The exact thickness depends on the SHG crystal, the pulse width, and the requirements of the measurement.

Regardless of the nonlinearity used, an autocorrelation yields only the approximate duration and



Figure 1 An intensity autocorrelator used to determine the approximate duration of a pulse. The pulse is split into two replicas that are sent into delay lines. The outputs from both delay lines are focused into a doubling crystal. The second harmonic output is monitored as a function of delay between the two pulses. A plot of the signal versus time is the intensity autocorrelation of the pulse.

shape of the pulse. The structure of the pulse is smeared, producing a smooth, featureless profile for even a complex pulse. Thus, the intensity autocorrelation alone does not determine the intensity profile of the pulse, $I(t)$. Only the interaction of the intensity of the pulse is recorded, producing no phase information for the pulse. Some qualitative information can be gleaned from the spectrum and the autocorrelation, but usually only that the pulse is chirped, and higher-order chirps and complex pulse structures elude such an analysis.

Another useful form of intensity autocorrelation is the single-shot autocorrelator. In this case, fairly large beams are used, and these beams are set to intersect at an angle of 2Φ, tilting the pulse fronts, so that delay is mapped onto a spatial coordinate (see Figure 2). The beams are then focused into a nonlinear medium using a cylindrical lens. The interaction region in the SHG crystal is imaged onto a linear array or CCD camera. Typically, when second-harmonic generation is used, the SHG crystal is oriented for Type I phase matching. The time window is proportional to $\Delta w(\sin \Phi)/\Delta v_g$, where Δw is the beam waist at the SHG crystal, and v_g is the group velocity of the pulse in the crystal. Like all SHG interactions, care must be exercised to insure that the phase matching is sufficient to mix the entire bandwidth of the pulse.

Jean-Claude Diels improved the intensity autocorrelation by the development of the interferometric autocorrelation. In this configuration, a Michelson interferometer is typically used so that the beams are collinear when arriving at the SHG crystal, which allows the beams to interfere. As a result, fringes appear on the autocorrelation. By examining the shape and extent of the fringes, some information about the pulse chirp can be obtained. While this does add to the information provided by an intensity autocorrelation, the added information is only the spectrum of the second harmonic. Unfortunately the addition of the second harmonic spectrum does not provide enough information for full retrieval of the intensity and phase.

Even though autocorrelation alone does not completely determine pulse intensity and phase, it is a very simple and useful technique to determine approximate pulse duration. Sometimes, cross-correlation can be used to determine the duration of a long pulse, if a shorter one is available, or a pulse too weak (or at an inappropriate wavelength) to measure with autocorrelation. The addition of the spectrum and/or the second harmonic spectrum can provide more,



Figure 2 A single shot intensity autocorrelator. For this type of autocorrelator, the beam size is large, on the order of 1 cm in diameter, and the pulse fronts are tilted with respect to each other in order to map relative delay to position. The two beams are focused using a cylindrical lens and the output is recorded using an array detector. The inset shows how delay is mapped into position. Inset: the tilted pulse fronts cause time delay to be mapped spatially.

albeit, incomplete information about pulse chirp. More importantly, the experimental techniques used by correlation methods are fundamental to all pulse measurement methods.

Spectral Interferometry – Relative Phase Measurements

While determination of the absolute intensity and phase of an ultrashort laser pulse is difficult, determination of the relative phase is not. Invented in the late 1800s, spectral interferometry (SI), measures the relative phase between two pulses. SI, a linear technique, can also be modified (albeit, a some-what complex modification) to be self-referencing for full characterization of the ultrashort optical pulse (See the section on SPIDER below). In addition, when combined with a full pulse characterization technique, SI, because it is a linear technique, provides a method by which very weak optical pulses can be characterized (see below).

Typically, an SI apparatus uses a Mach–Zender interferometer (see Figure 3). A pulse is split into two replicas; one is sent through a region or medium to measure and the other through a known path. The two pulses remain separated by some known time and are sent, collinearly, into a spectrometer; no time scanning is required. An analysis of the fringe pattern yields the relative phase between the two pulses. In other words, SI provides $\phi_{\text{unk}}(\omega) - \phi_{\text{ref}}(\omega)$, where $\phi_{\text{unk}}(\omega)$ is the unknown pulse phase versus frequency. The spectrum of the two pulses in the frequency domain is

$$\tilde{I}_{\text{SI}}(\omega) = |\tilde{E}_0(\omega) + \tilde{E}_{\text{unk}}(\omega)|^2$$

$$\tilde{I}_{\text{SI}}(\omega) = \tilde{I}_0(\omega) + \tilde{I}_{\text{unk}}(\omega) + 2\sqrt{\tilde{I}_0(\omega)}\sqrt{\tilde{I}_{\text{unk}}(\omega)} \times \cos(\phi_{\text{unk}}(\omega) - \phi_0(\omega) - \omega\tau) \quad [5]$$



Figure 3 A Mach–Zender interferometer is the typical arrangement for spectral interferometry. One path acts as the reference arm and the sample to be measured is placed in the other arm. Unlike standard interferometry, the delay is fixed in a spectral interferometry experiment.

where $\tilde{I}_{\text{SI}}(\omega)$ is the output spectrum, $\tilde{E}_0(\omega)$ is the reference pulse electric field, $\tilde{E}_{\text{unk}}(\omega)$ is the unknown pulse electric field, $\tilde{I}_0(\omega)$ is the reference pulse spectrum, $\tilde{I}_{\text{unk}}(\omega)$ is the unknown pulse spectrum, $\phi_{\text{unk}}(\omega)$ is the unknown pulse phase, $\phi_0(\omega)$ is the reference pulse phase, and τ is the delay between the two pulses. To facilitate extracting the phase difference from the SI output, τ is chosen to yield fringes in the sum spectrum. The spectral fringes, which have a period inversely proportional to the optical path difference between the two beams (see Figure 4), contain all of the phase difference information.

Figure 4 shows the steps required to obtain the phase difference between the two pulses. The first step is to subtract out the spectra of the individual pulses in order to isolate the spectral interferogram, $S(\omega)$ (Figure 4a), where

$$S(\omega) = 2\sqrt{\tilde{I}_0(\omega)}\sqrt{\tilde{I}_{\text{unk}}(\omega)}\cos(\phi_{\text{unk}}(\omega) - \phi_0(\omega) - \omega\tau) \quad [6]$$

By Fourier transforming $S(\omega)$, we obtain

$$\Im^{-1}[S(\omega)] = f(t-\tau) + f(-t-\tau) \quad [7]$$

where $f(t)$ is the correlation product between the reference and the unknown electric field (see Figure 4b). The Fourier transform of eqn [7] multiplied by a Heaviside function, $\Theta(t)$ (to remove $f(-t-\tau)$), recovers the amplitude and phase of $f(\omega)$, the Fourier transform of $f(t-\tau)$, which contains the relative spectral phase between the unknown pulse and the unmodified pulse. Some care, however, needs to be taken to correctly remove the linear phase due to the time delay between the two pulses, $\omega\tau$. Also, for best results, the spectrometer should be well calibrated and care should be taken to properly window the spectrum before taking the Fourier transform.

Spectral interferometry is a straightforward and simple technique that always provides a relative phase. For this very reason, care must be taken to make sure the beams are mode-matched as well as collinear; also, interferometric stability must be maintained over the course of the measurement. Furthermore, SI is nongating; that is, CW background in the laser can add to the interferogram, masking transient effects. Nevertheless, spectral interferometry is a useful technique that has been applied to the measurement of the linear and nonlinear spectral phase introduced by optical fibers. More recently, SI has been applied to phase-locking and to phase-resolved pump probe experiments.



Figure 4 The steps required for the analysis of spectral interferograms. Part (a) shows a sample SI interferogram. The dominant frequency of the fringes is the delay multiplied by the speed of light. The actual phase differences of interest are the perturbations on this frequency. Part (b) is the Fourier transform of the SI interferogram in Part (a). (Note that this is not the true time domain.) The central peak contains only spectral information. All of the phase information is contained in the satellite peaks. The next step is to mask out the central peak and one of the satellite peaks (Part (c)). The phase of the inverse Fourier transform of Part (c) yields the relative phase between the two pulses (Part (d)).

Time-Frequency Representation

In 1971, E.B. Treacy laid the foundations for a revolution in pulse measurement by introducing the idea of measuring the intensity versus time for different spectral splices of a pulse. Because his measurements provided both time and frequency information simultaneously, these measurements could be thought of as applying in a hybrid time-frequency domain. At first, this may seem confusing, but similar methods have been used to visualize sounds patterns (a musical score, for example) and speech. A time-frequency plot of this type, where spectral slices of a pulse are plotted versus time, is called a sonogram. The mathematical formalism of a sonogram is:

$$S_{\mathrm{E}}(\Omega, T) = \left| \int_{-\infty}^{\infty} \tilde{E}(\omega) h(\omega - \Omega) \mathrm{e}^{-\mathrm{i}\omega T} \mathrm{d}\omega \right|^2 \qquad [8]$$

where $\tilde{E}(\omega)$ is the electric field of the pulse to be measured in the frequency domain and $h(\omega - \Omega)$ is a frequency gate that varies with frequency. The magnitude squared of the inverse Fourier transform of spectral slices yields the sonogram.

In 1991, Chilla and Martinez showed that the sonogram could be used to reconstruct the full intensity and phase of the pulse. That is, under certain conditions, the approximate group delay could be determined as a function of frequency from the sonogram by finding the peak time arrival of each spectral slice; integration of the group delay yields the spectral phase, which together, with the pulse spectrum, provides the intensity and phase of the pulse in the frequency domain. They labelled this technique as frequency domain phase measurement (FDPM).

An experimental diagram of an FDPM apparatus is shown in Figure 5. The pulse is split into two replicas, and one of the pulse replicas is spectrally filtered. The spectrally filtered pulse is cross-correlated with the original pulse to find the ‘time arrival’ of the spectrally filtered pulse – defined as the peak of the cross-correlated pulse. Because the spectrally filtered pulse has a much longer time duration than the original pulse, the small perturbation caused by the finite length of the original pulse is neglected.

The main difficulty of the Chilla–Martinez method is that the frequency gate must be very narrow, reducing the filtered pulse energy significantly, which greatly reduces the measured signal strength. If the spectral phase is not well behaved, the filtered pulse may not be much longer than the original pulse. In addition, for a given frequency, the sonogram may have two or more peaks in time, that is, the group delay may not be a function. However, a method called 2D phase retrieval, discussed in the next section, can alleviate many of these issues.

A spectrogram is a relative of the sonogram. Rather than determining the time arrival of spectral slices of a pulse, a spectrogram is obtained when the spectrum of time slices of the pulse are measured. The spectrogram is experimentally much easier to obtain than the sonogram; however, the measured quantity is not


Pulse to be measured
Beamsplitter
Variable-frequency filter $g(\omega-\omega')$
$g(\omega-\omega')\ E(\omega)$
$E(t-\tau)$
SHG crystal
Variable delay

Figure 5 Measuring a sonogram requires determining the time arrival of spectral slices of the pulse. The pulse is split into two replicas using a beamsplitter. One replica is spectrally filtered using a tunable filter. The other pulse is cross-correlated with the spectrally filtered pulse to determine the time arrival.

quite as mathematically useful as the sonogram because the time slicing of the pulse occurs in the time domain. Thus, if a narrow time gate is used, the time domain phase is obtained. The time domain phase together with the intensity of the pulse, $I(t)$, provides the full intensity and phase of the pulse. Unfortunately, the intensity profile is not as readily measurable as the pulse spectrum. Consequently, to obtain the full intensity and phase of a pulse from its spectrogram requires an iterative 2D phase retrieval algorithm. This is the basis of a pulse measurement technique called frequency-resolved optical gating (FROG).

Frequency-Resolved Optical Gating

Frequency-resolved optical gating (FROG), developed by Kane and Trebino, measures the spectrum of a particular temporal component of the pulse (see Figures 6 and 7) by spectrally resolving the signal pulse in an autocorrelation-type experiment using an instantaneously responding nonlinear medium. As shown in Figure 6, FROG involves splitting a pulse and then overlapping the two resulting pulses in an instantaneously responding $\chi^{(3)}$ or $\chi^{(2)}$ medium. Even though any instantaneous nonlinear interaction may be used to implement FROG, perhaps the most intuitive is the polarization-gating configuration. In this case, induced birefringence, due to the electronic Kerr effect, is used as the nonlinear-optical process. In other words, the 'gate' pulse causes the $\chi^{(3)}$ medium, which is placed between two crossed polarizers, to become slightly birefringent. The polarization of the 'gated' probe pulse (which is cleaned up by the first polarizer) is rotated slightly by the induced birefringence allowing some of the 'gated' pulse to leak through the second polarizer. This is referred to as the signal. Because most of the signal emanates from the region of temporal overlap between the gate pulse and the probe pulse, the signal pulse contains the frequencies of the 'gated' probe pulse within this overlap region. The signal is then spectrally resolved, and the signal intensity is measured as a function of wavelength and delay time τ. The resulting trace of intensity versus delay and frequency is a spectrogram, a time- and frequency-resolved transform that intuitively displays time-dependent spectral information of a waveform.

The spectrogram can be expressed as:

$$S_{\mathrm{E}}(\omega,\tau) = \left| \int_{-\infty}^{\infty} E(t) g(t-\tau) \mathrm{e}^{-\mathrm{i}\omega t} \mathrm{d}t \right|^2 \qquad [9]$$

where $E(t)$ is the measured pulse's electric field, $g(t-\tau)$ is the variable-delay gate pulse, and the subscript E on S_{E} indicates the spectrogram's dependence on $E(t)$. The gate pulse $g(t)$ is usually somewhat shorter in length than the pulse to be measured, but not infinitely short. This is an important point: an infinitely short gate pulse yields only the intensity $I(t)$ and conversely, a CW gate yields only the spectrum $I(\omega)$. On the other hand,


Single-shot Polarization-Gate FROG
Input pulse
Polarization-rotating out-of-plane path
Beamsplitter
• Use large beam angle and line focus at nonlinear optical medium to map delay onto position
• Output at camera: Intensity versus frequency (ω) and delay (τ)
Gate pulse $E(t-\tau)$ 45° polarization
Probe pulse $E(t)$
Imaging spectrometer
Cylindrical lens
Nonlinear-optical medium
Polarizer
Camera
Polarizer
Beam dump
ω
Delay
τ
Spherical imaging lens
Beam dump

Figure 6 Measuring the spectrogram of a pulse is easier than measuring its sonogram – a spectrogram is a spectrally resolved autocorrelation. In this figure, the optical Kerr–effect is used (polarization-gate) as the nonlinearity. (Adapted with permission from Kane DJ and Trebino R (1993) Single shot measurement of the intensity and phase of an arbitrary ultrashort pulse by using frequency-resolved optical gating. *Optics Letters* 18(10): 823–825.)


Pulse to be measured
$I_{\mathrm{FROG}}(\omega,\tau) = |\int E_{\mathrm{sig}}(t,\tau)\, e^{-i\omega t}\, dt|^2$
Beamsplitter
Second-harmonic-generation crystal
Camera
Spectrometer
$E(t-\tau)$
$E(t)$
Variable delay
$E_{\mathrm{sig}}(t,\tau) \propto E(t)\, E(t-\tau)$

Figure 7 This figure shows a schematic of an SHG FROG device. The SHG signal from the autocorrelation is spectrally resolved. SHG FROG is very simple and sensitive, but it has a direction-of-time ambiguity. For example, if the pulse has chirp, only the magnitude of the chirp is determined – the sign of the chirp remains unknown.

a finite-length gate pulse yields the spectrum of all of the finite pulse segments with duration equal to that of the gate. While the phase information remains lacking in each of these short-time spectra, having spectra of an infinitely large set of pulse segments compensates for this loss. The spectrogram has been shown to nearly uniquely determine both the intensity $I(t)$ and phase $\varphi(t)$ of the pulse, even if the gate pulse is longer than the pulse to be measured (although if the gate is too long, sensitivity to noise and other practical problems arise).

In FROG, when using optically induced birefringence as the nonlinear effect, the signal pulse is given by:

$$E_{\text{sig}}(t,\tau) \propto E(t)|E(t-\tau)|^2 \qquad [10]$$

So the measured signal intensity $I_{\text{FROG}}(\omega,\tau)$, after the spectrometer is:

$$I_{\text{FROG}}(\omega,\tau) = \left| \int_{-\infty}^{\infty} E(t)|E(t-\tau)|^2 \mathrm{e}^{-\mathrm{i}\omega t}\,\mathrm{d}t \right|^2 \qquad [11]$$

We see that the FROG trace is a spectrogram of the pulse $E(t)$ although the gate, $|E(t-\tau)|^2$, is a function of the pulse itself.

To see that the FROG trace essentially uniquely determines $E(t)$ for an arbitrary pulse, it is first necessary to observe that $E(t)$ is easily obtained from $E_{\text{sig}}(t,\tau)$. Then it is simply necessary to write eqn [11] in terms of $E_{\text{sig}}(t,\Omega)$, the Fourier transform of the signal field $E_{\text{sig}}(t,\tau)$, with respect to delay variable τ. We then have what appears to be a more complex expression, but one that will give us better insight into the problem:

$$I_{\text{FROG}}(\omega,\tau) = \left| \iint_{-\infty}^{\infty} E_{\text{sig}}(t,\Omega) \mathrm{e}^{-\mathrm{i}\omega t - \mathrm{i}\Omega\tau}\,\mathrm{d}t\,\mathrm{d}\Omega \right|^2 \qquad [12]$$

Equation [12] indicates that the problem of inverting the FROG trace $I_{\text{FROG}}(\omega,\tau)$, to find the desired quantity $E_{\text{sig}}(t,\Omega)$, is that of inverting the squared magnitude of the two-dimensional (2D) Fourier transform of $E_{\text{sig}}(t,\Omega)$. This problem, which is called the 2D phase-retrieval problem, is well known in many fields, especially in astronomy, where the squared magnitude of the Fourier transform of a 2D image is often measured. At first glance, this problem appears unsolvable; after all, much information is lost when the magnitude is taken. It is well known that the one-dimensional (1D) phase retrieval problem is unsolvable (for example, infinitely many pulse fields give rise to the same spectrum). Intuition fails in this case, however; two- and higher-dimensional phase retrieval essentially always yields unique results.

The Simplified FROG – GRENOUILLE

A simplified version of the FROG device, known as grating eliminated no-nonsense observation of ultrafast incident laser light e-fields (GRENOUILLE), can be constructed using the doubling crystal as both the gating medium and the spectrometer (see Figure 8). In this case, the phase matching condition in certain thick doubling crystals causes a wavelength dependent output from the doubling crystal. A cylindrical lens is used in a Fourier transform configuration to image the wavelength variation onto a CCD camera. A cylindrical lens set at 90 degrees to the Fourier transform lens images the time axis onto the CCD camera. A Fresnel biprism replaces the traditionally used Mach–Zender interferometer to produce two pulses propagating at an angle with respect to each other. Presently, the GRENOUILLE technique works with BBO, in the wavelength region around 500 nm–1200 nm, and with proustite in the wavelength region around 1200 nm–2000 nm.



Figure 8 Figure showing a schematic of a GRENOUILLE FROG device which uses a thick doubling crystal as both the gating nonlinearity and the spectrometer. Like single-shot autocorrelators, a cylindrical lens focuses a spatially large input beam into an SHG crystal in only one dimension. Unlike most autocorrelators, the Mach–Zender interferometer is replaced with a Fresnel biprism that forces each half of the input beam to propagate, at an angle, toward the SHG crystal. An imaging cylindrical lens images the spatial dependence of the delay onto a CCD camera. A Fourier transform cylindrical lens maps the angular dependence of wavelength from the SHG crystal to a spatial coordinate on the CCD camera. (Adapted with permission from O'Shea P, Kimmel M, Xun G and Trebino R (2001) Highly simplified device for ultrashort-pulse measurement. *Optics Letters* 26(12): 932–934.)

FROG Inversion Algorithms

An iterative 2D phase retrieval algorithm is required to extract the pulse information from the measured FROG trace (see Figures 9 and 10). This algorithm converges to a pulse that minimizes the difference



Figure 9 Example FROG traces and sonograms are shown for four different pulses: a transform limited pulse, a positively chirped pulse, and a negatively chirped pulse. The top series of plots are the time domain representation of the pulse intensity (solid line) and phase (dashed line). The second row of four plots is the frequency domain representation of the sample pulse's intensity and phase. The next four plots show the instantaneous frequency and the group delay. The vertical axis is frequency and the horizontal axis is time. The remaining rows show the PG FROG traces, the SHG FROG traces and sonograms of the pulse shown in the first two rows.


$E_{sig}(t, \tau)$
Generate new $E(t)$
Generate new $E_{sig}(t, \tau)$ (Apply mathematical form constraint)
1D Fourier transform w.r.t. t
$E_{sig}(\omega, \tau)$
Replace the magnitude of $E_{sig}(\omega, \tau)$ with $(I_{FROG}(\omega, \tau))^{1/2}$
$E_{sig}(\omega, \tau)$
Inverse Fourier transform w.r.t. ω

Figure 10 Phase retrieval algorithm for the inversion of FROG spectrograms. Start with an initial guess for the pulse to generate an initial $E_{sig}(t,\tau)$. A 1D Fourier transform generates the FROG trace. The next step is to replace the magnitude of the calculated FROG trace with the square root of the measured FROG trace. Inverse Fourier transform with respect to ω to produce the new signal field and generate a new guess for $E(t)$. Interestingly, it is only the step that produces $E(t)$ from $E_{sig}(t,\tau)$ that differentiates all the FROG algorithms.

between the measured and the calculated FROG trace. While this aspect of FROG has been its Achilles heel in the past, in reality, new generalized projections algorithms (together with faster computers) converge quickly and can track pulse changes at rates up to 30 Hz and beyond, making FROG a true, real-time pulse measurement technique. Indeed, excellent algorithms for the analysis of FROG traces in real-time are commercially available.

The original FROG inversion algorithm, commonly referred to as the vanilla algorithm, is simple and iterates quickly, but tends to stagnate, giving erroneous results, especially for geometries that use a complex gate function such as SHG or self-diffraction. An improved algorithm, incorporating several different algorithms including brute force minimization, was developed to alleviate stagnation programs at the expense of both speed and convergence time. By the mid-1990s, a significant advance in both speed and stability was made by the addition of a numerical method called generalized projections. This algorithm determines the next guess by constructing a projection – minimizing the error (distance) between the FROG electric field, $E_{\text{sig}}(t, \tau)$, obtained immediately after the application of the intensity constraint, and the FROG electric field calculated from the mathematical form constraint.

The first generalized projections algorithm used a standard minimization procedure to find the electric field for the next iteration, which can still be slow. For the most common FROG geometries, PG and SHG, a different algorithm that determines the next iteration directly has been developed. This algorithm, called the principal components generalized projections (PCGP) algorithm, converts the generalized projections algorithm into an eigenvector problem. Using this algorithm, pulse measurement rates of at least 30 Hz have been achieved.

The goal of the phase retrieval algorithm is to find the $E(t)$ that satisfies two constraints. The first is the FROG trace itself which is the magnitude squared of the 1D Fourier transform of $E_{\text{sig}}(t, \tau)$:

$$I_{\text{FROG}}(\omega, \tau) = \left| \int_{-\infty}^{\infty} E_{\text{sig}}(t, \tau) e^{-i\omega t} dt \right|^2 \qquad [13]$$

The other constraint is the mathematical form of the signal field, $E_{\text{sig}}(t, \tau)$, for the nonlinear interaction used. The signal forms for a variety of FROG beam geometries are:

$$E_{\text{sig}}(t, \tau) \propto \left\{ \begin{array}{ll} E(t)|E(t-\tau)|^2 & \text{PG FROG} \\ E(t)^2 E^*(t-\tau) & \text{SD FROG} \\ E(t)E(t-\tau) & \text{SHG FROG} \\ E(t)^2 E(t-\tau) & \text{THG FROG} \end{array} \right\} \qquad [14]$$

where PG is polarization gate, SD is self-diffraction, SHG is second harmonic generation, and THG is third harmonic generation FROG.

All FROG algorithms work by iterating between two different data sets: the set of all signal fields that satisfy the data constraint, $I_{\text{FROG}}(\omega, \tau)$, and the set of all signal fields that satisfy eqn [14]. The difference between the FROG algorithms is how the iteration between the two sets is completed. In the case of generalized projections, the $E(t)'$s are chosen such that the distance between the $E(t)$ on the magnitude set and the $E(t)$ on the mathematical form set is minimized. This is accomplished by minimizing the following equation:

$$Z = \sum_{i,j=1}^{N} \left| E^{(k)}_{\text{sig(DC)}}(t_i, \tau_j) - E^{(k+1)}_{\text{sig(MF)}}(t_i, \tau_j) \right|^2 \qquad [15]$$

where $E^{(k)}_{\text{sig(DC)}}(t_i, \tau_j)$ is the signal field generated by the data constraint, and $E^{(k+1)}_{\text{sig(MF)}}(t_i, \tau_j)$ is the signal field produced from one of the beam geometry equations in eqn [14]. For the normal generalized projection, the minimization of Z is completed using a standard steepest descent algorithm; the derivative of Z with respect to the signal field is computed to determine the direction of the minimum. The computation of the derivatives are tedious; they are tabulated elsewhere.

An alternative to an algorithm that minimizes eqn [15] is the PCGP algorithm. This algorithm converts the computation of the next guess into an eigenvector problem, reducing the computation of the next guess to simple matrix–vector multiplications. This algorithm works for both the PG and SHG beam geometries, it is robust and the fastest FROG algorithm. Indeed, the PCGP algorithm was used in the original real-time FROG work by D.J. Kane.

Self Checks in FROG Measurements

Unlike any other pulse measurement techniques, FROG can provide a great deal of feedback about both the quality of the measurement (systematic errors) and the quality of the algorithm's performance. The most common check for convergence is the FROG trace error together with a visual comparison between the retrieved FROG trace and the measured FROG trace. The FROG trace error is given by:

$$G = \sqrt{\frac{1}{N^2} \sum_{i,j=1}^{N} \left| I_{\text{FROG}}(\omega_i, \tau_j) - \alpha I^{(k)}_{\text{FROG}}(\omega_i, \tau_j) \right|^2} \qquad [16]$$

where α is a renormalization constant, I_{FROG} is the measured trace, and $I^{(k)}_{\text{FROG}}(\omega, \tau)$ is computed from the retrieved electric field. Typically, the FROG trace error of a PG measurement should be less than 2% for a 64 × 64 pixel trace, while the FROG trace error of a 64 × 64 pixel SHG FROG trace should be about 1% or less. Acceptable FROG trace errors decrease as FROG trace size increase for smaller FROG traces. These values are only rules of thumb only;

for example, acceptable retrievals of large and very complicated FROG traces can produce larger FROG trace errors.

In a good FROG measurement, the spectrum of the retrieved pulse should faithfully reproduce the salient features of the pulse's measured spectrum. SHG FROG even provides an additional check called the frequency marginal. The sum of an SHG FROG trace along the time axis yields the autoconvolution of the pulse's spectrum, providing two ways the FROG measurement can be checked. First, the autoconvolution of an independently measured spectrum can be compared to the sum of the FROG trace along the time axis, providing an indication of how well the measurement was made. For example, if the doubling crystal was too thick in the pulse measurement, the FROG trace's frequency marginal will be narrower than the autoconvolution of the measured spectrum. Second, comparing the autoconvolution of the retrieval pulse spectrum with the FROG trace marginal can provide a test of algorithm convergence in addition to a test of the measurement. Phase matching problems appear as a mismatch between the FROG trace frequency marginal and the autoconvolution of the retrieved spectrum.

Because FROG is a spectrally resolved autocorrelation, summing any FROG trace along the frequency axis yields the autocorrelation of the measured pulse. This autocorrelation can be compared to an independently measured autocorrelation, or a comparison can be made between the frequency sum of the FROG trace and the autocorrelation calculated from the retrieved pulse to determine algorithm convergence and the quality of the measurement.

Measuring Pulses Directly – SPIDER

SPIDER is a novel technique that measures the pulse directly – no iterative phase retrieval method is required. To accomplish this feat, spectral interferometry is conducted on two pulse replicas that are shifted in frequency with respect to one another. The original pulse is split into two replicas. The two pulse replicas are sent into a phase modulator that shifts the center frequency of each pulse slightly. The frequency-shifted pulses are sent into a spectrometer and a standard spectral interferometry analysis yields the derivative of the phase. Integration of the phase derivative, together with the spectrum of pulse, provides the full intensity and phase.

Thus, analysis of the spectral interferogram gives:

$$\Delta\phi = (\phi(\omega_1) - \phi(\omega_2))\Delta\omega \qquad [17]$$

where $\Delta\phi$ is the measured phase difference from the spectral interferogram, $\Delta\omega$ is the difference in the center frequency between the two pulses, and $\phi(\omega)$ is the pulse phase as a function of frequency. Consequently, the phase difference must be divided by the frequency difference between the two pulses to determine the true derivative. It is also important to subtract out the linear phase difference resulting from the delay between the two pulses (the delay produces the fringes in the resulting interferogram) as this integrates to a linear chirp.

Because phase modulators are too slow to be used in the femtosecond region, a different method is used to shift the frequency of the two pulses – they are mixed with a highly chirped pulse (see Figure 11).



Figure 11 Figure showing how a SPIDER device works. The highly chirped pulse has a frequency that varies with time. Mixing the chirped pulse with two time delayed replicas produces two pulses, separated in time, that have slightly different frequencies, but are otherwise identical. By interfering the two pulses in a spectrometer, the relative phase between $\omega_0 + \delta\omega$ portions of the pulse and ω_0 portions of the pulse are determined.



Figure 12 SPIDER apparatus. The input pulse is first split into two pulses. One pulse is stretched in a pulse stretcher. The other pulse is sent into a Michelson interferometer to produce two time-delayed pulses. The two time-delayed pulses are mixed with the stretched pulse to produce two pulses at a slightly different center frequency. The two pulses are sent into a spectrometer to produce a spectral interferogram. Analysis of the spectral interferogram yields the derivative of the pulse phase.

Because the pulses are slightly time delayed, each one aligns with a slightly different frequency in the chirped pulse. The chirped pulse must be so highly chirped that the pulse frequency does not change significantly over the duration of the pulse to be measured.

A schematic of a SPIDER device for the measurement of femtosecond laser pulses is shown in Figure 12. The input pulse is first split into two replicas. The first replica is sent to a pulse stretcher to produce to highly chirped pulse. The other replica is sent into a Michelson interferometer (or a simple étalon may sometimes suffice) to create two time-delayed replicas. The time-delayed replicas are mixed with the chirped pulse. Because each replica is mixed with a slightly different frequency in the chirped pulse, each replica produces a pulse with a slightly different center frequency. When the time-delayed replicas are spectrally resolved, each frequency of the pulse interferes with a frequency-shifted portion of the same pulse. Thus, the measured phase difference is proportional to the derivative of the phase of the original pulse.

Measuring Weak Pulses

Because virtually all the pulse measurement techniques, that do not require a reference pulse, use a nonlinearity, measuring weak ultrafast pulses directly is difficult. Fortunately, because most weak pulses are generated from a stronger pulse, spectral interferometry can be used to determine the relative phase between the weaker pulse and the stronger pulse (for regions where there is spectral overlap between the two pulses). If the stronger pulse is characterized using another pulse measurement technique, then the weaker pulse phase can be determined from the relative phase measurement and the known phase of the stronger pulse. For example, the Trebino group termed the combination of FROG and SI as TADPOLE (Temporal Analysis by Dispersing a Pair Of Light E-fields).

Which Pulse Measurement Method Should I Use?

Choosing a pulse measurement method depends on the required measurement as well as the precision and accuracy required. All the pulse measurement techniques have advantages and disadvantages, but excellent measurements have been made with all of them. Autocorrelation is adequate when all that is required is the approximate pulse duration without any phase information. Spectral interferometry is quite useful for measuring transient changes in a sample in pump-probe experiments. FROG is perhaps the most commonly used and general-purpose pulse measurement technique, providing a great deal of feedback about the quality of the pulse measurement. Inexpensive and convenient FROG devices, together with software, are available commercially, adding to their acceptance. While SPIDER is experimentally complex and does not have the cross checks that FROG has, it provides the quickest answer, requiring no iterative phase retrieval algorithm to obtain pulse intensity and phase.

Acknowledgments

This material is based in part upon work supported by the National Science Foundation under Grant numbers DMI-9801116 and DMI-0091454. The author would also like to acknowledge Rick Trebino for the use of figures from his lectures.

List of Units and Nomenclature

$A(t)$	Full electric field
$E(t)$	Complex electric field without carrier frequency
$E_{\text{sig}}(t, \tau)$	Complex electric field of the FROG trace versus time and time delay
$E_{\text{sig}}(t, \Omega)$	Fourier transform of $E_{\text{sig}}(t, \tau)$ with respect to τ
$\tilde{E}(\omega)$	Complex electric field in the frequency domain
$f(t)$	Correlation product
$f(\omega)$	Fourier transform of the correlation product
$g(t - \tau)$	time gate or filter
G	FROG trace error
$h(\omega - \Omega)$	frequency gate or filter
$I(t)$	Intensity profile of the electric field in the time domain
$\tilde{I}(\omega)$	spectral intensity
$I_{\text{FROG}}(\omega, \tau)$	Intensity of the FROG trace
$\Theta(t)$	Heaviside function $= 0 \;\; t < 0, \;\; = 1 \;\; t \geqq 0$
$\phi(\omega)$	Frequency domain phase
$S_{\text{E}}(\omega, \tau)$	Spectrogram
$S_{\text{E}}(\Omega, T)$	Sonogram
$S(\omega)$	Spectral interferogram
t, T	variables for time
τ	Fourier transform
v_{g}	group velocity
$\varphi(t)$	Time domain phase
Δw	Beam waist
Z	Distance metric between the FROG signal field generated by the data constraint and the FROG signal field generated by the mathematical form constraint
Φ	Geometric angle between two beams
$\Delta\phi$	Phase difference
$\Pi^{(n)}$	nth order nonlinear susceptibility
ω	Primary variable for frequency
$\Delta\omega$	Difference in center frequency between two pulses
Ω	Secondary variable for frequency
$\Omega(t)$	Instantaneous frequency

See also

Coherent Transients: Ultrafast Studies of Semiconductors. **Nonlinear Optics, Basics:** Ultrafast and Intense-Field Nonlinear Optics. **Ultrafast Laser Techniques:** Generation of Femtosecond Pulses. **Ultrafast Technology:** Femtosecond Chemical Dynamics: Gas-Phase; Femtosecond Condensed Phase Spectroscopy: Structural Dynamics; Ultrafast Illumination and Processing.

Further Reading

Diels JC and Rudolph W (1996) *Ultrashort Laser Pulse Phenomena*. San Diego, CA: Academic Press Inc.

Dorrer C, Belabas N, Likforman J-P and Joffre M (2000) Spectral resolution and sampling issues in Fourier-transform spectral interferometry. *Journal of the Optical Society B* 17: 1795.

Kane DJ, Weston J and Chu K-CJ (2003) Real-time inversion of polarization gate frequency-resolved optical gating spectrograms. *Applied Optics* 42: 1140–1144.

Iaconis C and Walmsley IA (1999) Self-referencing spectral interferometry for measuring ultrashort optical pulses. *IEEE Journal of Quantum Electronics* 35: 501–509.

Lepetit L, Cheriaux G and Joffre M (1995) Linear techniques of phase measurement by femtosecond spectral interferometry for applications in spectroscopy. *Journal of the Optical Society of America B* 12: 2467–2474.

Rulliere C (ed.) (2000) *Femtosecond Laser Pulses*. New York: Springer Verlag.

Shuman TM, Anderson ME, Bromage J, Iaconis C, Waxer L and Walmsley IA (1999) Real-time SPIDER: ultrashort pulse characterization at 20 Hz. *Optics Express* 5: 134–143.

Treacy EB (1971) Measurement and interpretation of dynamic spectrograms of picosecond light pulses. *Journal of Applied Physics* 42: 3848–3858.

Trebino R (2000) *Frequency Resolved Optical Gating: The Measurement of Ultrashort Laser Pulses*. Boston, MA: Kluwer Academic Publisher.

Trebino R, DeLong KW, Fittingholf DN, Sweetser JN, Krunbugel MA, Richman BA and Kane DJ (1997) Measuring ultrashort laser pulses in the time-frequency domain using frequency-resolved optical gating. *Review of Scientific Instruments* 68: 3277–3295.

Various authors (1999) Feature issue on ultrashort-laser-pulse measurement and applications. *IEEE Journal of Quantum Electronics* 35: 4.

ULTRAFAST TECHNOLOGY

Contents

Femtosecond Chemical Dynamics: Gas-Phase
Femtosecond Condensed Phase Spectroscopy: Structural Dynamics
Ultrafast Illumination and Processing

Femtosecond Chemical Dynamics: Gas-Phase

M Dantus, Michigan State University, East Lansing, MI, USA

E J Brown, McDaniel College, Westminster, MD, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Chemical reactions are at the heart of chemistry; the quest to understand them has sparked research and study along many different avenues. The fundamental dynamics involved in bond breakage, bond formation, and transition states take place on a very fast time-scale, usually in the tens to hundreds of femtoseconds, where a femtosecond (fs) is equal to 10^{-15} seconds. Therefore, ultrashort laser pulses are required to measure these fundamental processes as well as the rotational and vibrational motion before and after the reaction. The whole set of measurements can then be used for mapping a potential energy surface for the reaction. As a result of these studies, one learns the key details that are required to develop a picture of how chemical reactions occur. The measurement of these fundamental dynamics, using ultrashort laser pulses, is the subject of this article.

To illustrate how long it takes to form or break a chemical bond, one needs to consider the following analogy. The time it takes to break a chemical bond is approximately a tenth of a trillionth of a second (10^{-13} s). During such a short time, light can travel only 0.03 mm in vacuum. This time is so short that it cannot be measured electronically. Its measurement requires the use of ultrashort laser pulses, with pulse durations of 50 femtoseconds or shorter. The development of methods aimed at measuring the fundamental steps involved in chemical reactions culminated in the development of femtosecond transition state spectroscopy (FTS), a method developed in the 1980s by Zewail and co-workers at Caltech. This work allows researchers to observe bond breakage and formation, vibrational and rotational dynamics, and transition state configurations, as the reaction occurs. The Nobel Prize in Chemistry was awarded in 1999 to Ahmed Zewail for this development. Since the 1980s, femtosecond lasers have been used to study molecular dynamics and chemical dynamics on very fast time-scales. The field, known as femtochemistry, has grown quickly and diversified to involve hundreds of scientists around the world. This article discusses the measurement of ultrafast dynamics measured in gas-phase samples. The presentation encompasses some of the measurement techniques and the fundamental values to be measured and concludes with an outlook towards the future.

From Nanosecond to Picosecond to Femtosecond Reaction Kinetics

The quest for shorter light pulses to study chemical reactions predates the invention of the laser. In the early days, electric discharges were used to measure fast dynamics in the millisecond (10^{-3} s) and then the microsecond (10^{-6} s) time-scales. With the invention of the laser, measurements improved drastically with temporal resolution going from the nanosecond (10^{-9} s) to the picosecond (10^{-12} s) time-scales. Since the early days, it was recognized that the best time resolution was obtained when pairs of light pulses were used – one to initiate the reaction and the second to probe it. These pump-probe measurements have progressed with the laser technology almost to the single femtosecond level.

The measurements being considered here go beyond the measurement of fast reaction kinetics. When a chemical reaction occurs in a beaker, one usually measures a statistical rate of reaction that involves diffusion of reagents in a solvent. These kinetic measurements, which involve an ensemble of molecules, are much slower and do not reveal the fundamental steps of the reaction such as bond formation. The introduction of ultrafast pulses allowed, for the first time, the measurement of the motion of the atoms in real time, as if the motion was frozen by ultrafast flash photography. Capturing this motion helps to reveal the internal forces, described by a potential energy surface, that act on the atoms in the molecule during the chemical reaction. This concept is illustrated in Figure 1, where we see the reagents and the products for the reaction. Typically, the starting and ending point of a chemical reaction are very well known and the compounds are very well characterized. However, how the reagents become the products is not always known. Chemists typically deduce a reaction mechanism based on a large body of experiments where different parameters including the structure of the reagents are modified to evaluate their effect on the outcome of the reaction. Unfortunately in most cases, reaction mechanisms, even when consistent with all available experimental evidence, may not accurately reflect how a particular chemical reaction takes place.


Determination of the reaction mechanism
?
hv
+
(a)
(b)
(c)
+
Reactants
Products

Figure 1 A sketch of a chemical reaction, AB + CD → A + BCD. The reactants and products are well known, but it is not known how they change from reactants to products. This mechanism may involve a transition state which is (a) a linear complex with vibrational motion, (b) a nonlinear complex, (c) a bent complex with rotational motion, or many other possibilities and combinations. The elucidation of the mechanism and transition state dynamics are the goals of femtosecond time-resolved studies.

The ideal method to make the determination involves direct observation. As mentioned earlier, direct observation requires femtosecond laser pulses, just like a fast camera shutter is required to take pictures of fast-moving objects. The concept of a femtosecond pump-probe measurement is illustrated in Figure 2. The chemical reaction is initiated at time $t = 0$ fs by the pump laser. The pump laser provides the energy required for initiating the chemical transformation. The probe laser, delayed in time, probes the formation of the product. Figure 2 illustrates a number of pump-probe measurements


Probing the progress of a reaction using the pump-probe method
Energy
λ_{probe}
λ_{probe}
λ_{probe}
λ_{probe}
λ_{probe}
λ_{probe}
λ_{pump}
+
+
Signal
Formation of product
Transition state dynamics
$t = 0$
t_1
t_2
t_3
t_4
t_∞
Time delay between pump and probe pulses

Figure 2 Energy schematic of the reaction of AB + CD → A + BCD assuming vibrational motion in a linear transition state. The pump pulse provides enough energy to excite the reactants to the transition state at $t = 0$. This transition state is probed by the second pulse. This pulse arrives at different time delays, from no delay ($t = 0$), to increasing delays (t_1, t_2,…), to infinite delay (t_∞). The signal varies depending on the time delay between the two pulses and these changes in signal intensity correspond to vibrational and rotational information about the transition state. To obtain a transient as shown at the bottom, the time delay between the pump and probe pulses is scanned. The dashed line shows the transient that would be obtained when the transition state is monitored; the solid line shows the transient that would be obtained when the product is monitored.

each obtained at a different time delay between the pump and probe laser pulses. When a series of pump-probe measurements are gathered as a function of time delay, one obtains a transient that contains a record for the evolution of the reagents to product as a function of time.

The Formation of Coherent Wave Packets and their Motion

The illustration shown in Figure 2 shows atoms in a molecule moving as classical particles. Because of their small size, atoms behave quantum mechanically and this has some implications on the observed motion. A prototypical pump-probe measurement is illustrated for this purpose in Figure 3. For resonant excitation, a photon is absorbed by a molecular system, originally in the ground electronic state (V_0). This absorption causes a vertical transition to an excited electronic state (V_1). Consistent with Heisenberg's uncertainty principle, a pulse that has a short temporal duration has a large spectral bandwidth; for most molecular systems and ultrashort pulses, the frequency spread of the pulse is wider than the vibrational energy spacing in the excited state. Thus, a number of quantum vibrational states are populated on V_1 by the absorption of a short laser pulse. When a short pulse excites a number of states, a coherent superposition of states is formed. One can understand the formation of a wave packet by simply realizing that in the short time the laser pulse excites the system there is no opportunity for the atoms in the molecule to move. For this reason the initial wave packet is very similar to the ground state atomic arrangement.



Figure 3 Pump-probe experiment. The pump pulses excite the molecular system from the ground state V_0 to excited state V_1. The large spectral bandwidth of femtosecond pulses allows for a number of vibrational levels in V_1 to be populated. A wave packet is formed that vibrates on V_1; the classical motion of the particle is shown as well at the top. In this case the energy of the probe pulse will excite the molecules to V_2 when the bond is stretched (right side of oscillation); however, when the bond is compressed, the energy is not resonant with any excitation and the probe pulse will not be absorbed.

When a short laser pulse excites a molecule to a bound electronic state, the resulting wave packet, $\Psi(t)$, is a sum of all the possible states φ_n in V_1 with amplitudes, a_n, $\Psi = \sum_n a_n \varphi_n$. The amplitudes, a_n, depend on the overlap between the initial (ground state) and final (excited state) spatial overlap. This overlap indicates that the excitation process is faster than the motion of atoms in a molecule. Based on this approximation for the overlap integral, the amplitudes are replaced by the Franck–Condon overlaps to obtain $\Psi = C\sum_n \langle \varphi_n | \varphi_0^{(0)} \rangle \varphi_n$. The wave packet on V_1 evolves in time according to $\Psi(t) = \sum_n a_n \exp[-\mathrm{i}E_n t/\hbar]\varphi_n$, where E_n is the energy that corresponds to the state φ_n and $\hbar$ is Planck's constant divided by 2π. When a pulse is very short in time, the coherent superposition of states closely resembles the initial distribution of atoms in the molecule. The motion from inner to outer turning point of the quantum mechanical wave packet is illustrated in Figure 3. One can imagine this wave packet as a classical particle oscillating on the excited potential energy curve with the periodic nature of the molecular vibrations. When the pulse is very long and only one state is populated, the dynamics can no longer be observed, as is the case with conventional frequency-resolved spectroscopy.

Molecular dynamics can be inferred from high-resolution frequency-resolved spectroscopy; however, the spectra can become congested and the data analysis becomes more complicated for large molecules, for high temperatures, or in solutions. Molecular dynamics are obtained from frequency-resolved spectra by taking the Fourier transform of the data. It seems more intuitive to consider these dynamics in the time domain where the dynamics can be observed directly as 'snapshot' taken by the femtosecond pulses. Ultrafast time-resolved spectroscopy has other advantages – high peak intensities allow for multiphoton excitation and other nonlinear processes, the selection of the detection wavelength discriminates between different species and results in an increased signal-to-noise ratio for intermediate short-lived species, collisions take place on a longer time-scale and do not affect these measurements, and the characteristics of the ultrafast laser pulse (such as phase, frequency components, and chirp) can be manipulated to control the dynamics and the yield of chemical reactions.

Methods for Measuring Femtosecond Dynamics

Pump-Probe Method

Pump-probe techniques use a pair of pulses separated in time, one to initiate the reaction and the second to determine its progress. The first femtosecond pulse with wavelength λ_{pump} excites a molecule from its (bound) ground electronic state (V_0) to an excited (V_1) state. After a variable time delay, a second femtosecond pulse with wavelength λ_{probe} causes a transition to another excited state (V_2) as shown in Figures 3 and 4.

The progress of the reaction dynamics is followed through the measurement of signal resulting from the absorption of the probe pulse by the system. There are different detection modes depending on the potential energy surfaces reached by the pump and probe pulses. In one case (Figure 4a), the first excited state (V_1) is nonfluorescent but the second one (V_2) fluoresces and this fluorescence is measured. In another case (Figure 4b), state V_1 is fluorescent but state V_2 is not; in this case the depletion of the fluorescence by the probe is measured. Finally (Figure 4c), excited states V_1 and V_2 may be dissociative; therefore, the fluorescence detected is emitted by the products. In any of these cases, as the wave packet on the intermediate state propagates (e.g., vibrates, dissociates), the transition probability varies (i.e., the ability of the probe pulse to be absorbed by the molecule changes). Therefore, the amount of laser-induced fluorescence (LIF) emitted varies with the pump-probe time delay. In some cases, the probe pulse produces ions and there are a number of methods to detect the electrons or the ions with great sensitivity.

Measurement of rotational dynamics

Measurement of rotational dynamics requires a vectorial frame of reference and this is achieved with linearly polarized laser beams. Excitation by the pump pulse selects an initial population distribution described by $\cos^2\theta$ where θ is the angle between the transition dipole and the pump laser polarization vector. As the rotational wave packet dephases due to the distribution of the population in different rotational levels, the probe pulse probes the transient alignment of the molecules in space. As the molecules rotate away from the initial alignment, the signal decreases. In Figure 5 rotational dynamics are depicted schematically. First, a single (classical) molecule is considered (top panel). As the molecule rotates, its dipole changes from being aligned with the polarization vector of the laser field



Figure 4 Different pump-probe experiments.(a) Bound-to-bound transitions from $V_0 \rightarrow V_1$ and from $V_1 \rightarrow V_2$. The V_2 state fluoresces and this increase in LIF from V_2 is measured as signal. (b) Bound-to-bound transition from $V_0 \rightarrow V_1$ where V_1 fluoresces. When the probe pulse causes an excitation from $V_1 \rightarrow V_2$, a loss of LIF signal is observed. The depletion of fluorescence is measured in this case. (c) Bound-to-repulsive surface transition from $V_0 \rightarrow V_1$. The energy of the probe causes an excitation to V_2 at a particular molecular distance. Fluorescence of a product fragment is measured.



Figure 5 Rotational motion of molecules. Excitation by a linearly polarized laser pulse initially selects molecules that are well aligned ($\cos^2\theta$) with its polarization. Considering only one molecule evolving in time (top), the rotational motion in the molecule causes it to move away from the initial alignments and then eventually return to it. The signal will decrease when the molecule is not aligned with the polarization of the probe laser and will increase when aligned well. The signal looks like a cosine function that depends on the rotational frequency of the molecule (ω_j). For a rotational wave packet, the rotational dynamics are similar except that a number of rotational levels are populated; thus, the signal depends on the summation of many cosine functions and the features in the data become sharper.

(assumed vertical) to being perpendicular. The rotational motion can be described by a cosine function. The rotational frequency ω_j is proportional to the rotational level and the rotational constant of the molecule. Because the rotational constant is inversely proportional to the angular momentum, larger molecules rotate slower than smaller molecules. When several rotational levels are contained in a rotational wave packet the motion produces sharper features (bottom panel). The sharp features are called rotational recurrences or revivals. Note that the opposite trend is observed if the probe pulse is polarized perpendicular to the pump pulse; the signal increases as the molecules rotate away from the initial alignment and decreases as the alignment recurs. The time-resolved data for each polarization arrangement (parallel and perpendicular) contain both an isotropic component (vibrational motion) and an anisotropic component (rotational motion). In rotational anisotropy measurements, data from these two polarization arrangements are manipulated mathematically to yield just the rotational motion; rotational dynamics and rotational information such as the spectroscopic rotational constants and the rotational energy partitioning in the reactants and products can be extracted from these measurements.

Three-Pulse Four-Wave Mixing Method

Some methods are more complicated than pump-probe technique but they are more powerful. Three-pulse four-wave mixing (FWM) is one such method and is briefly presented here. Time-resolved four-wave mixing techniques can be understood based on the formation of transient gratings by two of the incident lasers. When two laser beams cross, the spatial modulation of their electric fields varies due to constructive and destructive interference as shown in Figure 6. The molecules in the interaction region experience varying electric field intensities according to their position and this leads to the formation of a transient grating of polarized molecules in space. The transient grating formation can be probed easily by the detection of Bragg scattering of a third laser beam, also known as homodyne detection; here, the signal beam is scattered in the phase-matching direction $\mathbf{k}_{\text{signal}}$ as indicated in Figure 6a. Alternatively, probing can be achieved by detection of changes in the intensity of a fourth beam that propagates in the



Figure 6 (a) FWM experimental configuration. Two of the beams cross which forms a grating and the third beam scatters off the grating to generate a fourth beam (the signal). The three laser pulses are noted as electric fields E_a, E_b, and E_c. These three laser pulses can be delayed or advanced in time relative to each other giving rise to a number of different pulse sequences. (b) Pulse sequence with fields E_a and E_b overlapped in time ($\tau_{ab} = 0$). Field E_c follows at a time delay τ. (c) Pulse sequence in which E_c precedes E_a and E_b by time delay τ. For both of these cases, τ is scanned in time to obtain the transients. (d) Pulse sequence in which no pulses are overlapped in time and are applied in the order E_a, E_b, and E_c. Time delay τ_{ab} can be set to specific values while τ is scanned in time.

same direction as the signal; this is called heterodyne detection. The medium that constitutes the gratings is composed of the sample molecules, which in the gas phase move freely. Therefore as time evolves, the molecular dynamics (rotation and vibration) modulate the transient grating and hence the signal.

Three-pulse four-wave mixing is a nonlinear spectroscopic method that combines the interaction of three laser pulses in a phase-matched geometry with a well-defined time sequence of the pulses. The signal from these measurements arises from a third-order polarization resulting from the interaction of the three electric fields. Three-pulse FWM is similar to the pump-probe technique in that a preparation step is followed, after some variable time delay, by a probing step. However, three-pulse FWM allows for a greater degree of control over the preparation and probing processes.

When the lasers are in resonance with an electronic state, FWM measurements can provide dynamic information from the ground and excited electronic states. When two pulses are incident on the sample at $t = 0$ and a third pulse probes the dynamics at a later time τ (as in Figure 6b), the measurements provide information that is very similar to that from a pump-probe measurement. However, having three pulses allows for other different setups. For example, when one pulse arrives at the sample first and the other two pulses follow after a time delay (as in Figure 6c), the resulting signal provides dynamic information from the excited state. This type of measurement also provides a measurement of the electronic coherence of the sample, i.e., for how long the molecules remember the phase of the incident laser pulses. This information is important if one wants to take advantage of the phase of laser pulses to cause quantum mechanical interference in the molecular sample. These measurements are known as photon echo and are much more common in condensed-phase samples. There are numerous pulse sequences possible; only three examples are shown in Figure 6.

FWM measurements do not depend on resonance excitation to an electronic excited state. In the absence of such resonance, the grating is formed in the ground state and ground state vibrational and rotational dynamics are observed. These measurements, also known as transient grating (TG), depend on the impulsive Raman scattering process. By changing the time delay (in Figure 6b) between the electric fields that generate the grating and the third (probe) beam, the signal is modulated by the molecular dynamics. Analysis of the time-dependent signal yields the rotational and vibrational spectroscopic values from the sample being studied.

Studies of Reaction Dynamics

Dissociation on a Repulsive Surface

In 1987, Zewail and co-workers studied the photodissociation of cyanogen iodide (ICN) using femtosecond lasers; the first direct observation of a chemical reaction from reactants to products was conducted. The excitation and decay of the reactants (ICN), the formation and decay of the intermediates (I–CN), and the formation of the products (I + CN) were observed in this experiment.

The pump pulse (306 nm) excited ground state cyanogen iodide to a repulsive excited state of ICN which dissociated into I and CN fragments (both in the ground state). The probe pulse when set to 388.5 nm was resonant with an excitation of the CN fragment; therefore, the reaction was monitored by detecting the laser-induced fluorescence (LIF) of this CN^* fragment using a probe pulse at different time delays (as shown in Figure 4c). The wavelength of the probe pulse could be detuned to different wavelengths for making observations at different lengths of the I–C bond. The results of these experimental studies showed that ICN dissociated in about 200 fs and that the transition state lived for only about 50 fs. The data from the wavelength detuning studies were used to map the excited state potential of ICN both in time and in space; this data analysis is called inversion to the potential.

A schematic representation of the ICN experiment is shown in Figure 7. The potential energy curves are shown in Figure 7a. The pump laser initiates the chemical reaction. Three different probe wavelengths are depicted, the first probing early in the reaction, the second at an intermediate distance, and the final one probing the free products. Notice that the wavelength of the probe determines the location in the potential energy curve that is probed. This concept allows one to study reagents as they are transformed into products. The signals obtained from the three different probe wavelengths are shown in Figure 7b.

Reactions Involving Crossing of Potential Energy Surfaces

For many chemical reactions, the progress of the reaction requires changes of the electronic state. This can take place where potential energy surfaces cross. The best-known example of reaction dynamics involves the experiment on the photodissociation of NaI by Zewail and co-workers. This experiment is depicted in Figure 8. The pump pulse excites the wave packet from ground state (ionic) to an excited state (covalent) where it begins to oscillate. The ground and excited states overlap with an avoided crossing in this molecule (ionic versus covalent nature, as shown in Figure 8a); when the wave packet approaches this avoided crossing, it splits into two partial waves. One wave stays on the excited state while the other 'escapes' onto the dissociative surface and separates into Na and I. The partial wave on the excited state again oscillates and then splits at the avoided crossing and the pattern continues. The time delay of the probe pulse shows the oscillations of the wave packet on the excited surface when detecting the activated complex $[NaI]^{*\ddagger}$ (thin line), while the data of the product fragments (free Na atoms detected by using the D-line absorption) (thick line) show a step-wise accumulation in the signal corresponding to the sequential formation of products during each oscillation near the avoided crossing region of the surfaces (see Figure 8b).



Figure 7 Photodissociation of ICN. (a) Potential energy surface schematic showing the initial excitation by the pump laser to a dissociative surface. The reaction could be monitored at different I–CN distances by using different probe wavelengths as shown by three examples here, (i), (ii) and (iii), from shorter to longer distances. (b) At short distances (long probe wavelengths), the signal is observed at shorter time delays only. The signal decreases at later time delays because the internuclear distance continues to lengthen as the dissociation occurs over time. When the distance increases as monitored by shorter probe wavelengths, the signal rises to a maximum at longer time delays reflecting the dissociation of the reaction in progress. At 'infinite' I–CN distance (i.e., the molecule is dissociated and only free I atoms and CN fragments remain), the signal reaches a maximum and remains there because the reaction is complete.

Chemical Dynamics with Multiple Pathways

The pump-probe concept can be used to probe more complex reactions. To date, a great number of different chemical reactions have been studied (see Further Reading). Among the most important reactions we list ring opening, isomerization, proton transfer, and concerted chemical reactions. We illustrate these measurements with experiments on the photodissociation of dihalogenated alkanes. Upon high-energy excitation (12 eV), the methylene iodide (CH_2I_2) molecule dissociates and forms molecular iodine in excited states D′ and f as well as producing I atoms (main channel). The detection wavelength used in the experiment can distinguish between these products; D′ fluorescence can be collected at 342 nm and f fluorescence is collected at 272 nm. The Dantus group has studied the dynamics of this type of concerted molecular elimination reaction extensively. The photodissociation reaction occurs by a multiphoton excitation (three-photons from the pump beam at 310 nm) reaching a dissociative state where the CH_2 fragment and excited molecular iodine are formed. The 620 nm probe pulse depletes the fluorescence from the excited I_2 molecule (either D′ or f state) as shown in Figure 4b; this fluorescence depletion is measured and analyzed to determine the dynamics of the reaction. The object of this experimental work was to determine if the photodissociation mechanism for forming molecular iodine followed a step-wise, synchronous concerted, or asynchronous concerted mechanism as shown in Figure 9.

The time transients reveal coherent vibrational motion of the I_2 product. Analysis of the transition state dynamics shows that the breaking of the carbon–halogen bond and the formation of the halogen–halogen bond occurs within 50 fs. Further, the iodine molecule is formed with a very hot rotational distribution indicating that the symmetry of the molecule is broken during the process; the torque imparts a large amount of rotational motion. Overall, the results of these studies show that the photodissociation process of CH_2I_2 follows an asynchronous concerted reaction mechanism and corresponds to a symmetry barrier that exists in C_{2v} molecules preventing the formation of the interhalogen bond. The existence of this symmetry barrier was explored by using CH_2ICl, a molecule that does not have C_{2v} symmetry; as expected, the halogen molecule (ICl) was formed with a cold rotational distribution indicating that it was able to follow a synchronous concerted mechanism. The dissociation times were also studied on the family of compounds CX_2Y_2 and $R-CHI_2$ to investigate the influence of thermodynamics and reduced mass changes on the reaction.

The Dynamics of Bond Formation

Most chemical reactions that are studied with femtosecond spectroscopy are unimolecular reactions (photodissociation); however, bimolecular reactions (photo-association) are interesting and chemically relevant in trying to understand how chemical reactions occur. In the photo-association process, a pair of atoms or molecules cooperatively absorbs the photon undergoing a free-to-bound transition and forming a bond. When the ultrashort pulse initiates the reaction in femtosecond photo-association spectroscopy, a clearly defined initial time for the reaction is given



Figure 8 Photodissociation of sodium iodide. (a) Potential energy curve schematic showing the curve-crossing between the ground (ionic) and excited (covalent) states. As the wave packet oscillates on the excited curve, it splits into two wave packets at the curve crossing. (b) The thin line shows the vibrations of the excited complex as it oscillates on the excited surface. The signal intensity decreases because some of the molecules have dissociated to form Na and I atoms when the wave packet splits. The thick line shows the stepwise increase in free Na atom signal each time the wave packet oscillates and splits.



Figure 9 Possible mechanisms for the photodissociation of CH_2I_2 following multiphoton excitation. The molecule could break both C–I bonds and form an I–I bond all at the same time (synchronous concerted mechanism); this would result in very little rotational motion in the products. The molecule could begin to break one C–I bond slightly before breaking the second one and forming the I–I bond, but all three events still occur within the duration of the laser pulse (asynchronous concerted mechanism). This would result in significant rotational motion in the products. The molecule could also lose one I atom and at some later time lose the other I atom; these I atoms could collide later to form I_2 (stepwise mechanism).



Figure 10 Photo-association of mercury dimers. The pump (bind) pulse is absorbed by two ground-state Hg atoms to form Hg_2^* on the excited state which is fluorescent. The probe pulse depletes this fluorescence causing the LIF signal to decrease at $t = 0$. Analysis of the transient reveals that the time of association is <60 fs. Parallel and perpendicular pump-probe data were examined to obtain the rotational distribution of this reaction.

and the alignment conditions of the reaction can be examined by taking advantage of the polarization of the lasers. The femtosecond photo-association spectroscopy technique was used by the Dantus group to study the formation of an excited mercury dimer. Their experiment is depicted in Figure 10. Two ground-state mercury atoms absorbed the pump (bind) pulse (at 312 nm) forming a wave packet in the excited D state. The probe pulse depleted the fluorescence from the newly formed molecules. The time of association was determined to be within the laser pulse duration (<60 fs). The dimers were found to have a narrow rotational distribution which together with the wavelength of the binding pulse reflects the impact parameter (geometry) of the collision. Calculations reveal that the 'optimal'



Figure 11 Molecular dynamics of iodine using two different pump laser wavelengths. (a) The pump laser, either at 550 or 622 nm, causes an excitation from the ground state to the B excited state. The choice of wavelength determines the vibrational levels which are excited on the B state. In either case, the probe at 311 nm causes an excitation to the f excited state which fluoresces around 340 nm. (b) Parallel and perpendicular pump-probe transients were obtained using each pump wavelength. At higher pump energies (550 nm), the molecule vibrates more slowly (higher vibrational level) and is reflected by the 410 fs vibrational period observed in the data. At lower pump energies (622 nm), the molecule vibrates faster and corresponds to the 300 fs vibrational period observed in the data.

binding pulse for this association reaction is 10 fs; such short pulses would overlap the entire absorption band from the repulsive ground state to the bound D state.

Bimolecular reactions can also be studied by preparing a low-temperature cluster that contains the reagents of interest. For example, a cluster containing one HI and one CO_2 molecule can be used to study the reaction $H + CO_2 \rightarrow OH + CO$. Initiation of the reaction takes place when the pump laser cleaves the H–I bond and the H atom attacks the CO_2 molecule present in the cluster. The reaction dynamics are probed as a function of time delay between pump and probe pulses as for other pump-probe experiments. The femtosecond dynamics of this reaction have been studied independently by Wittig's and Zewail's research groups.

Studies of Molecular Dynamics

I_2-Pump-Probe, Rotation and Vibration (Bound Surface)

Aside from observing chemical reactions, using ultrafast spectroscopy allows for studying the motion of isolated molecules to elucidate the internal motions of molecules themselves and to extract spectroscopic parameters. Iodine is one of the most frequently used molecules in femtosecond spectroscopy. Here we highlight only a small subset of the femtosecond studies on I_2 that have been conducted by Zewail's and other research groups. Using a pump beam at 550 nm, ground state I_2 is excited to the B state; probing with 310 nm excites the molecule to an even higher bound potential (f state) from which fluorescence at 340 nm can be obtained (as shown in Figure 11). By changing the pump-probe time delay, oscillations on the B excited state are clearly visible and show a vibrational period of approximately 410 fs. Excitation at 622 nm produces a wave packet lower in the potential well, with a vibrational period of approximately 300 fs. The differences observed for parallel and perpendicular probing correspond to the early rotational motion of the molecules. Fourier transfer analysis of the data yields the energy of each vibrational state that forms part of the vibrational wave packet. Different pump wavelengths can be used to access different vibrational levels such that vibrational frequencies and rotational constants can be obtained for a wide range of vibrational levels of the potential. This information can then be used to refine the B excited state potential energy curve of iodine.

Different Measurements Possible with Three-Pulse FWM

Ground and excited state molecular dynamics

Molecular dynamics can also be examined with four-wave mixing techniques. Once again we use iodine as a model system to illustrate that unlike the previous experimental transients of iodine obtained with pump-probe measurements, both excited and ground state dynamics of I_2 are revealed with FWM. Materny, Kiefer, and co-workers have carried out coherent anti-Stokes Raman spectroscopy and degenerate four-wave mixing measurements on this molecule using two pulses overlapped in time followed by a third pulse after a time delay; both ground and excited state dynamic are observed in the Fourier transform of data. Dantus and co-workers explored all the pulse sequences possible with three-pulse FWM using molecular iodine as a model system (see below).

Double-sided Feynman diagrams and third-order response functions can be used to describe the interaction of the three pulses with the molecular system in three-pulse four-wave mixing. These mathematical tools are described in several books on nonlinear optical spectroscopy (see Further Reading). Figure 12 illustrates how different pulse sequences reveal different molecular dynamics. The transient grating method (Figure 12a) shows both ground (160 fs oscillations) and excited state (310 fs oscillations) wave packet dynamics. When data collection occurs over long time delays, the transient grating signal persists with a similar time constant to that of the lifetime of the excited state. The photon echo pulse sequence (shown in Figure 12b) reveals only excited state dynamics (310 fs oscillations). Note that at longer time delays, the signal decays exponentially with a time constant that reflects the rate of electronic coherence dephasing. This fundamental decay parameter indicates how long molecules remember the phase of the electric field that acted on them.

Off-resonance transient grating molecular dynamics

Off-resonance transient grating can be used to study the molecular motion of molecules in the ground state. The pulse sequence used is shown in Figure 6b. With this method it is possible to examine the rotational and vibrational dynamics of diatomic and polyatomic molecules. The vibrational dynamics belong to the Raman-active modes. From the rotational recurrences, one can obtain rotational constants with great accuracy. Dantus and co-workers have studied carbon dioxide at room temperature and in flames. At high temperatures, rotational recurrences narrow because more rotational levels are populated and the rotational recurrence moves towards longer times because of centrifugal distortion. Further studies on carbon dioxide and carbon disulfide have shown that strong fields can impart an increase in initial alignment (due to torque along the polarization vector of the laser) as well as molecular deformation such as bending (due to electronic state mixing). Heterodyne detected off-resonance transient grating data for CO_2 at room temperature are shown in Figure 13. The data closely resemble the schematic illustration in Figure 5 where rotational dynamics were introduced. The data in Figure 13 have been analyzed to yield the B and D rotational constants which give the structural parameters of the molecules and the centrifugal distortions, respectively. The type of analysis given here for CO_2 can be done on molecules



Figure 12 FWM signal in molecular iodine using two pulse sequences at short and long delay times. (a) Transient grating – E_a and E_b overlapped in time followed by E_c. Similar amounts of ground (208 cm^{-1}) and excited (105 cm^{-1}) state dynamics are observed with short delay times. In the transients, these correspond to oscillations of 160 fs and 307 fs respectively. (b) Photon echo – E_a and E_c overlapped in time but preceded by E_b. Excited state dynamics are observed in the transient with short delay times. At long time delays, the decrease in the signal reflects (a) the lifetime of the excited state or (b) the rate of the electronic coherence dephasing.



Figure 13 Heterodyne detected off-resonance transient grating on carbon dioxide at room temperature. The experimental data (dots) reflect the rotational motion of the CO_2 molecule. The data have been analyzed (the fit is shown as a line that goes through the experimental data points) to obtain the rotational constant (B) and the centrifugal distortion constant (D).

and molecular fragments resulting from chemical reactions. This method can also be used for molecular identification.

Perspectives for the Future

Most of this article has focused on the observation of ultrafast dynamics involved in chemical reactions. Presently, it is possible to generate pulses with durations as short as 5 fs. Such short pulses are capable of observing motion involving frequencies near 3000 cm^{-1}. This implies that one can observe the dynamics of most chemical bonds. The availability of shorter pulses will allow one to observe electronic dynamics. Advances in laser technology have also produced ultrashort pulses in the infrared region as well as in the vacuum ultraviolet and X-ray region. The wide spectrum available permits experiments that follow specific chemical bonds or specific transitions in elements. This in turn gives a wide range of possibilities for probing ultrafast chemical reaction dynamics.

Having pulses that are shorter than the duration of the dynamics they probe allows one to consider influencing the evolution of a chemical reaction as it is taking place. Controlling chemical reactions with lasers is not a new theme; however, the availability of ultrashort laser pulses has given new power to these efforts. Here we present a brief sample of some of the current efforts.

Control Using Three-Pulse Four-Wave Mixing

Coherent control of chemical reactions depends on the relative phase of two different laser pulses that interact with the sample in order to optimize the transfer of population between electronic states. The three-pulse four-wave mixing technique can be utilized to attain coherent control; the specific timing between the pulses can be used to achieve near-unity or near-zero values of the transfer of population for molecules that interacted with the two electric fields. The Dantus group has also used three-pulse FWM to demonstrate control over optimizing the population transfer between two electronic states in iodine. The populations of the ground and excited states are controlled based on the time delay between the first two pulses τ_{ab} in the pulse sequence shown in Figure 6d. The transient is obtained as a function of the time delay between the second and third pulses, which probes the vibrational dynamics of the population; this experiment is illustrated in Figure 14. For Figure 14a using $\tau_{ab} = 460$ fs, only excited-state dynamics are observed; while for Figure 14b using $\tau_{ab} = 614$ fs, primarily ground-state dynamics are observed. This observation is confirmed by the Fourier transform of the time-resolved transient. The top transient has a vibrational frequency of 108 cm^{-1}, corresponding to the vibrational frequency of the excited B state. The bottom transient has a vibrational



Figure 14 FWM signal in molecular iodine demonstrating control over observation of molecular dynamics. By using the pulse sequence shown, τ_{ab} was defined to be either (a) 460 fs or (b) 614 fs while τ was scanned in time. As is clearly evident in the data and the FFT, excited-state dynamics alone (307 fs oscillations) are observed with $\tau_{ab} = 460$ fs and ground-state dynamics (160 fs oscillations) are observed with $\tau_{ab} = 614$ fs.

frequency of $208\,\mathrm{cm}^{-1}$, corresponding to the vibrational frequency of the ground state of iodine molecules.

Control Using Feedback and Evolutionary Algorithm

For complex molecules, one seldom knows the precise sequence of pulses or phase modulation of a given pulse that can optimize the yield of a chemical reaction. In these cases, a pulse-shaping device which manipulates the phase and amplitude of frequencies within an ultrashort pulse can be used. The device is part of a learning loop that includes a computer and an experimental setup. The learning algorithm running in the computer generates different pulses to be evaluated experimentally. Signal from the experiments is sent back to the computer for further refinement. The learning algorithm iteratively arrives at the optimum pulse. This method, first introduced by Rabitz, was first tested by Wilson. Gerber and co-workers have demonstrated automated control over the photodissociation reaction of organometallic compounds using an evolutionary algorithm with feedback. The organometallic compounds chosen were iron pentacarbonyl ($Fe(CO)_5$) and dicarbonylchloro(η^5-cyclopentadienyl)iron ($CpFe(CO)_2Cl$). For the first molecule, multiphoton absorption of femtosecond pulses at 800 nm caused ionization and fragmentation resulting in numerous ionic species – Fe^+, $Fe(CO)^+$, $Fe(CO)_2^+$, $Fe(CO)_3^+$, $Fe(CO)_4^+$, and $Fe(CO)_5^+$. These species were detected by mass spectrometry; the measured signal was used as feedback for the evolutionary algorithm that adjusts the phase of the femtosecond laser pulse. The $Fe^+$and $Fe(CO)_5^+$ exit channels were used to demonstrate the control available over branching ratios with this automated control method. Maximization (5.0) of the $Fe(CO)_5^+/Fe^+$ ratio was achieved with very short laser pulses while minimization (0.057) of this ratio was achieved with long (ps) pulses. These results were found to correspond well to changing the pulse duration of bandwidth-limited pulses. The optimization procedure did not attempt to control the other ionic species. This same automated optimization procedure was used to control the branching ratio of $CpFeCOCl^+/FeCl^+$ for the second organometallic compound. The maximum branching ratio was 4.9; the minimum was 1.2; and bandwidth-limited pulses yielded 2.4. Unlike the simpler carbonyl compound, simple changes to the pulse duration of a laser pulse could not optimize this branching ratio. The evolutionary algorithm with the feedback from the mass spectrometer allowed for these tailored pulses to be obtained and optimized the desired exit channel without any knowledge of the specific molecular system. The full potential of shaped femtosecond pulses has yet to be realized. It is possible that shaped femtosecond pulses will play an important role in future time-resolved experiments where they will be used to improve time resolution or to access potential energies that could not be reached with simpler pulses. Pulse shapers will also play a role in the preparation of ultrashort pulses with single femtosecond or attosecond duration.

List of Units and Nomenclature

Å	angstrom (10^{10} Å = 1 meter)
Attosecond	10^{18} as = 1 second
B	rotational constant
cm^{-1}	wavenumbers
D	centrifugal distortion constant
electron volts	1 eV = 8065 cm^{-1}
fs	femtosecond (10^{15} fs = 1 second)
FTS	femtosecond transition state spectroscopy
FWM	four-wave mixing
$\mathbf{k}$	wavevector
LIF	laser-induced fluorescence
nm	nanometer (10^9 nm = 1 meter)
ps	picosecond (10^{12} ps = 1 second)
R(Å)	internuclear distance (given in angstroms)
$t = 0$	initiation of reaction (pump and probe are overlapped in time)
τ	time delay between pump and probe pulses being applied
TG	transient grating
ω_j	rotational frequency

See also

Chemical Applications of Lasers: Non-Linear Spectroscopies; Pump and Probe Studies of Femtosecond Kinetics. **Coherent Control:** Experimental; Theory. **Nonlinear Optics, Applications:** Phase Matching. **Nonlinear Optics, Basics:** Four-Wave Mixing; Ultrafast and Intense-Field Nonlinear Optics; $\chi^{(3)}$ – Third-Harmonic Generation. **Spectroscopy:** Nonlinear Laser Spectroscopy; Raman Spectroscopy. **Ultrafast Laser Techniques:** Generation of Femtosecond Pulses. **Ultrafast Technology**: Femtosecond Condensed Phase Spectroscopy: Structural Dynamics.

Further Reading

Bandrauk AD, Fujimura Y and Gordon RJ (eds) (2002) *Laser Control and Manipulation of Molecules*, vol. 821 Washington, DC: ACS Press.

Chergui M (ed.) (1996) *Femtochemistry: Ultrafast Chemical and Physical Processes in Molecular Systems*. Singapore: World Scientific.

Dantus M (2001) Coherent nonlinear spectroscopy: from femtosecond dynamics to control. *Annual Reviews of Physical Chemistry* 52: 639–679.

De Schriber FC, De Feyter S and Schweitzer G (eds) (2001) *Femtochemistry: With the Nobel Lecture of A. Zewail*. Weinheim, Germany: Wiley-VCH.

Douhal A and Santamaria J (eds) (2002) *Femtochemistry and Femtobiology*. Singapore: World Scientific.

Goswami D (2003) Optical pulse shaping approaches to coherent control. *Physics Reports* 374: 385–481.

Grimberg I, Lozovoy VV, Dantus M and Mukamel S (2002) Femtosecond three pulse spectrocopies in the gas phase: density matrix representation. *Journal of Physical Chemistry* 106: 697–718.

Manz J and Woste L (eds) (1995) *Femtosecond Chemistry*, vols. I and II. Heidelberg, Germany: Verlag Chemie.

Mukamel S (1995) Principles of Nonlinear Optical Spectroscopy. New York: Oxford University Press.

Sundstrom V (ed.) (1997) *Femtochemistry and Femtobiology*. Singapore: World Scientific.

Zewail AH (ed.) (1994) *Femtochemistry – Ultrafast Dynamics of the Chemical Bond*, vols. I and II. Singapore: World Scientific.

Femtosecond Condensed Phase Spectroscopy: Structural Dynamics

E T J Nibbering, Max Born Institut, Berlin, Germany

© 2005, Elsevier Ltd. All Rights Reserved.

Ultrafast Chemistry

Chemistry means rearrangement of atoms in/between molecules. Chemical bonds are broken and/or formed, leading to a change in chemical composition, from reactants to products, during a reaction. Following the temporal behavior of the reaction all the way from reactant – via possible intermediates – towards the product state(s), amounts to deciphering the molecular processes that lead to these chemical reaction dynamics. Molecular rearrangements from reactant to product may encompass many orders of magnitude in time (see Figure 1). Typically the larger and more involved the rearrangements are, the more time it takes for a molecular species to reach the final state. Rearrangements of biomolecular structure occur in micro- to milliseconds (spontaneous folding of small proteins consisting of several hundreds of amino acid units), or longer (DNA multiplication, protein synthesis in ribosomes). In these conformational dynamics, hundreds to thousands of chemical bonds change their nature. Bimolecular reaction dynamics in liquid solution occur on time-scales of nanoseconds or longer, being controlled by the relatively slow diffusional motions of the reaction partners to each other. Many elementary processes in chemistry, however, occur on much faster time-scales. In fact, when one considers the dynamical event of a single-bond rearrangement, the relocation of the (relatively few) atoms appears to take place as an ultrafast event. Bond fission, hydrogen and proton transfer, electron transfer, and cis/trans-isomerizations have been found to occur on femto- to picosecond time-scales ('femtochemistry'). The dynamics of these elementary processes are not only determined by the energy landscapes of the reacting partners. The energy landscapes (potential energy surfaces) are determined by molecular parameters such as relative orientation (distances, angles) of the reaction partners, the energy levels of the reactant, intermediate and product species, and – very important – the energy barriers represented by transition states. When considering condensed phase reaction dynamics, the important role of the surrounding solvent has been recognized. The solvent shells modulate energy levels of the reactant, intermediate and product states, through electrostatic interactions. In the liquid phase the solvent fluctuations lead through these interactions to fluctuating energy levels of the reaction partners. In addition, the solvent may facilitate chemical reactions through energy exchange with the reaction partners, leading to efficient dissipation of excess energy, making chemical reactions often irreversible. The processes that are extremely dominated by these solvent interactions (such as molecular collisions, electronic and vibrational dephasing, vibrational relaxation) are also often found to occur on femto- to picosecond time-scales. The outcome of a bond fission may be a null effect, when the dissociating fragments are forced by the surrounding solvent to recombine and relax ('cage effect').

Spectroscopy has been a prime tool to obtain insight into these key molecular processes. Reactant, intermediate, and products contribute to the spectra with their respective molecular resonances. With spectral domain spectroscopy one may, in principle, obtain a precise determination of structural information. Fluctuations of energy levels of these species by the solvent interactions, and finite lifetimes, contribute to a broadening of these molecular resonances. Using steady-state spectroscopy one


Physics
Collision time in liquids
Molecular rotation
Solvent relaxation
Electronic dephasing
Vibrational dephasing
Radiative decay
Intramolecular vibrational redistribution
Vibrational cooling
Vibrational motion
Internal conversion intersystem crossing
10^{-15}
10^{-14}
10^{-13}
10^{-12}
10^{-11}
10^{-10}
10^{-9}
10^{-8}
10^{-7}
10^{-6}
10^{-5}
10^{-4}
10^{-3}
femto
pico
nano
micro
milli
Electron transfer
Enzyme catalysis
Hydrogen and proton transfer
Ion pumping through membranes
Photochemical isomerization
Chemistry and biology
Photodissociation
Protein internal motions
Cage recombination
Helix coil transition
Electron transfer in photosynthesis
Torsional dynamics of DNA
Protein folding tertiary structure

Figure 1 Chart showing the ultrafast time-scales of fundamental physical and chemical processes (inspired by charts of Fleming GR (1986) *Chemical Applications of Ultrafast Spectroscopy*. Oxford, UK: Clarendon Press and Zewail AH (2000) Femtochemistry: atomic-scale dynamics of the chemical bond. Nobel lecture as appeared in *Journal of Physical Chemistry A* 104(24): 5660–5694).

could try to determine these effects through a lineshape analysis. Using this approach, the results have to be analyzed with an a priori defined model representing the dynamics. The disadvantage lies in the averaging over all time-scales inherent in spectral domain spectroscopy, where details of transient states may be lost in this averaging procedure. In contrast, in experiments designed to grasp the molecular dynamics in real time, the temporal resolution is the prerequisite quantity in observation of these processes. In time-resolved experiments one can trigger a chemical reaction at a well-defined point in time, after which one can follow the conformational changes from reactant – via possible intermediates – to the product, and identify any possible transition states along the reaction pathways.

During the last century the technological advances in time-resolved spectroscopy have prompted significant breakthroughs in the study of chemical reaction dynamics. Initially the temporal resolution was given by the duration of flashes from light bulbs (‘flash’ spectroscopy) or by rapid mixing of reaction partners (stopped-flow technique), as developed by Nobel Laureates Eigen, Norrish, and Porter, and many others. These techniques allow a temporal resolution of at best milliseconds. Already, up to the early 1960s, it was understood that elementary reaction dynamics occur on much faster time-scales. Fourier spectroscopy may improve time resolution down to microseconds or slightly less. With the advent of pulsed laser sources with ever-increasing temporal resolution, a wide arena of time-resolved spectroscopic techniques has emerged. Nanosecond laser systems are known since the early 1960s, picosecond pulses can be generated since the 1970s, the first femtosecond laser system was reported in 1981, and currently laser engineering groups are breaking into the attosecond domain. The majority of pulsed laser systems operate at visible and near-infrared wavelengths. This means that usually chemical events in ultrafast time-resolved spectroscopy are initiated by electronic excitation (‘photochemistry’). Subsequent molecular rearrangements have then to be followed by probing the electronic states through electronic resonances (UV/VIS pump–UV/VIS probe or UV/VIS four-wave mixing


A-S$_n$
B-S$_n$
UV-VIS probe
UV-VIS probe
UV-VIS pump
A-S$_0$
A-S$_1$
B-S$_1$
UV-VIS probe
Energy
B-S$_n$
A-S$_n$
UV/VIS probe
UV/VIS probe
B-S$_1$
A-S$_1$
Reaction coordinate
UV-VIS pump
UV/VIS probe
A-S$_0$
Nuclear coordinate of spectator mode

Figure 2 Ultrafast time-resolved electronic spectroscopy. A UV/VIS pump pulse excited an electronic resonance, and a probe pulse determines, depending on the tuning in the UV/VIS population changes in the reactant ground or excited states or in the product state.


A-S$_n$
B-S$_n$
UV-VIS pump
A-S$_0$
A-S$_1$
B-S$_1$
Mid-IR probe
Mid-IR probe
Mid-IR probe
Energy
B-S$_n$
A-S$_n$
B-S$_1$
A-S$_1$
Mid-IR probe
Mid-IR probe
Reaction coordinate
UV-VIS pump
A-S$_0$
Mid-IR probe
Nuclear coordinate of spectator mode

Figure 3 Ultrafast time-resolved infrared spectroscopy. A UV/VIS pump pulse excites an electronic resonance, after which the populations are followed with an infrared probe pulse by inspection of marker modes in the different electronic states.

spectroscopy) (Figure 2), or via vibrational resonances (UV/VIS pump–IR/Raman probe spectroscopy) (see Figures 3 and 4).

Laser Technology

Since the beginning of the 1990s, a major advancement in femtosecond laser technology has emerged by the discovery of Kerr lens mode locking in laser oscillators with Ti:sapphire as lasing material. Ultrastable and ultrashort laser pulses tunable between 700 and 1,000 nm can be generated with durations as short as 6 fs. The second advancement is due to the ability of Ti:sapphire as laser amplifying material, using the method of chirped pulse amplification. Pulses with output powers up to several W, with repetition rates in the kHz-regime, are now routinely generated. These developments facilitate the efficient generation of ultrashort pulses tunable from the UV to the mid-infrared, and even beyond to the THz-regime using schemes based on nonlinear optics. Frequency conversion of the fundamental output of an amplified Ti:sapphire laser system is then achieved with nonlinear processes such as self-phase modulation and supercontinuum generation, n^{th}-order harmonic generation ($n = 2, 3, 4, \ldots$), sum and difference frequency generation, or parametric generation and amplification. As a result, one can now almost arbitrarily tune the excitation and probe wavelengths of the applied laser pulses. Additional parameters, that one may alter, are pulse duration (from less than 10 fs up to several ps) and pulse energy (in the mJ range or less; typically one uses for



Figure 4 Ultrafast time-resolved Raman spectroscopy. A UV/VIS pump pulse excites an electronic resonance, after which the populations are followed with (resonance) Raman probe pulse by inspection of marker modes in the different electronic states.

condensed phase spectroscopy pulse energies in the range of nJ to μJ). More advanced pulse manipulation schemes use amplitude and phase masks. The latter aspect holds the promise of amplitude and phase control of molecular excitation, feeding the ultrafast chemist's dream of laser control of molecular reaction dynamics.

Ultrafast Electronic Spectroscopic Techniques

Pulsed laser sources enable a variety of experimental approaches to determine transient states. Already, since the development of nanosecond laser sources, time-resolved pump–probe and four-wave mixing spectroscopy have been widely used. In a first approach, often one uses these forms of spectroscopy to probe in real-time populations of reactant, transient, and product states as function of pulse delay. With the advent of pico- and femtosecond laser sources, coherence properties of the material response have been investigated as well.



Figure 5 Pump–probe technique: A pump pulse induces an absorbance change in a sample, that is subsequently measured by a time delayed probe pulse, either spectrally integrated (a) or spectrally resolved (b).

The following techniques have been widely used in ultrafast electronic condensed phase spectroscopy.

UV/VIS Pump–UV/VIS Probe Spectroscopy

In this technique a 'pump' pulse resonant to a transition promotes the molecules to an electronic excited state, and the time-dependent populations are determined by measurement of the transmission of a time-delayed 'probe' pulse (Figure 5). The absorbance change $\Delta A(\tau) = -^{10}\log[T(\tau)/T(\tau = 0)]$ (with T for transmission change and τ the pulse delay) is a direct indication of populations of states. Here one can tune the probe pulse to the same transition as the pump pulse, and one measures an absorbance decrease due to a bleach of ground state population (i.e., fraction of molecules being excited), and due to molecules in the excited state stimulated back to the ground state. One could also tune the probe pulse to transitions between the transient state and higher lying states. For electronic spectroscopy, often transitions between the ground and first excited state ($S_0 \rightarrow S_1$) overlap with excited state absorptions ($S_1 \rightarrow S_n$). One has to rely then on numerical analysis procedures such as singular value decomposition and decay associated spectra, that correlate spectral features with temporal behavior.

The time resolution of the experiment is given by the cross-correlation between pump and probe pulses. In the case of extremely short pulses one has to consider the effects of group velocity dispersion between different frequency components due to different travel times through the samples, leading to pulse temporal broadening. For the case of pump and probe tuned to different wavelengths, the time-resolution is usually dominated by group velocity mismatch between pump and probe pulses.

When ultrashort laser pulses are used, often the applied spectral bandwidth enables simultaneous excitation of several vibrational sublevels in vibronic transitions. Due to the phase-relationship of the applied laser pulses, these vibrational sublevels are prepared in states that are well-defined in temporal phase with respect to each other. Such a coherent superposition of vibrational eigenstates is nothing less than a vibrational wavepacket, that will evolve in time. The occurrence of vibrational wavepacket motions leads to oscillatory modulations of the pump–probe signals.

Time-Resolved Fluorescence Spectroscopy

Here again a ‘pump’ pulse excites an electronic resonance. The transient excited states are now probed through their spontaneous fluorescence emission, either by use of time-correlated single photon counting or by fluorescence upconversion with a gating pulse in a nonlinear medium (Figure 6). Single-photon counting has a time resolution of at best a few picoseconds. Fluorescence upconversion can be performed with a time resolution of 100–200 fs. The advantage lies in the fact that the measured signals are more likely due to the specific excited states only, and not corrupted by other contributions.



Figure 6 Time-resolved emission detection: The fluorescence emission is either temporally resolved by time-correlated single photon counting (a) or by up-conversion with a gating pulse (b).

Electronic Four-Wave Mixing Spectroscopy

In time-resolved degenerate electronic four-wave mixing spectroscopy, where all the three applied laser pulses (with wavevectors $\mathbf{k}_1$, $\mathbf{k}_2$, and $\mathbf{k}_3$) are tuned to the same electronic resonance, one can detect a nonlinear signal in the phase-matched direction $\mathbf{k}_S = \mathbf{k}_3 + \mathbf{k}_2 - \mathbf{k}_1$ (Figure 7). The first laser pulse generates a coherent superposition between the electronic ground and excited states. This electronic coherence evolves in time during the period (denoted as coherence time τ), until the second pulse converts this coherence in a population frequency grating in the electronic ground and excited states. After a second time period of free evolution (denoted as population or waiting time T), this frequency grating is again transformed into an electronic coherence, which after some time evolution generates a macroscopic polarization in the phase-matched directions. This macroscopic polarization is either directly measured by a time-integrating detector (in which case one measures the intensity signal proportional to the absolute square of the nonlinear polarization), or one uses another light pulse that mixes as local oscillator with the nonlinear polarization (and the signal is proportional to the amplitude of the polarization). The time resolution is determined by the third-order autocorrelation of the applied pulses.

Depending on the delay between the three input pulses, and which delay one varies, different dynamics can be measured. When one performs an experiment with τ scanned and T set at zero, one measures the electronic coherence decay (due to electronic dephasing) time in a two-pulse photon echo experiment. When, on the other hand, τ is set to zero, and T is scanned, one measures the evolution of a population grating, and electronic lifetimes can be deduced. In a three-pulse photon echo experiment both pulse delays are scanned, and the signals give insight into both electronic coherence and frequency grating decay (due to electronic dephasing and spectral diffusion, respectively). A novel extension of four-wave mixing technique is the three-pulse echo peak shift (3PEPS). In a 3PEPS measurement, the delay time $\tau_{\max}$ is



Figure 7 Beam geometry for time-resolved four-wave mixing (grating/photon echo) spectroscopy: The nonlinear signal is transmitted by the sample in a phase-matched direction and its intensity signal (a) or its amplitude by interference with a local oscillator field (b) is detected by a time-integrating detector.

determined, where the echo signal has a maximum along the coherence delay τ, as a function of the population delay T. This method provides direct insight into the frequency fluctuation correlation function that governs the linear and nonlinear signals. Extension of the method to multi-color four-wave mixing spectroscopy has been demonstrated.

Electronic Condensed Phase Spectroscopy: Femtochemistry and Solvation Dynamics

In the narrow sense of meaning, 'femtochemistry' deals with the real-time observation of nuclear motions during chemical reactions. Quantum mechanics teaches us that this is only possible when molecular systems are prepared in vibrational superpositions. Only in the case of quantum states describing vibrational wavepackets evolving in time the narrow-defined positions of nuclei allow for a real-time description of molecular rearrangements, or in other words: dynamics. This has been demonstrated in the gas-phase landmark experiments by Nobel Laureate Zewail (Figure 8).

In the condensed phase at room temperature, however, often such well-defined quantum states are hard to prepare, since the ensembles of molecular systems exist in mixed states. Coherent laser excitation on an ensemble will then prepare mixed states as well, and then information that one obtains from the experiments is less explicit. In addition, room temperature liquid solutions induce extremely fast fluctuations in the states of the molecules under study and as a consequence the electronic and vibrational coherences show ultrafast decaying behavior. This limits the temporal window with which one can follow the evolution of vibrational wavepackets.

Most of the ultrafast spectroscopic experimental work performed on photochemistry in the condensed phase, being described as 'femtochemistry', only deals with the time-scales of changes in electronic states (usually indicated with reaction rates typified with exponentially decaying or rising functions). In this regard it is better to speak of 'kinetics' rather than 'dynamics', although both terms are used in condensed phase spectroscopy. Due to the relative broad electronic spectra of condensed phase molecules masking any structural detail, it is hard to derive nuclear motions in real time, and as such it is difficult to make any statements about dynamics of molecular structures during chemical reactions.

Electronic resonances have also been used to probe the dynamical interactions between a nonreactive solute and the surrounding fluctuating solvent. The idea behind these experiments is to achieve information about the time-scales of solvent fluctuations on (and solvent motions due to a change in) the electronic charge distribution in a molecule (as induced by an electronic excitation). Usually the solvent motions are characterized with a frequency fluctuation correlation function (Figure 9). This information is highly relevant for the case of reacting molecules, where electronic motions accompany the relocations of nuclei, even in electron transfer reactions, where the nucleic rearrangements are modest. Solvent motions have been shown to often control reaction rates. Solvent rearrangement, as a response to a change in electronic charge distribution, is known as solvation dynamics. Experimental probes for solvent motional fluctuations are electronic coherence decay (electronic dephasing) and population frequency grating decay (spectral diffusion) that can be measured in two- and three-pulse photon echoes. Solvent adaptation to new charge distributions can be followed with the time-dependent Stokes-shift in fluorescence emission, as well as in three-pulse photon echoes (in so-called three-pulse echo peak shift measurements described above). Ultimately these experiments resolve the temporal characteristics of the frequency fluctuation correlation function.



Figure 8 Ultrafast excitation with broadband pulses creates coherent superpositions of vibrational eigenstates, i.e., vibrational wavepackets. These wavepackets are generated in electronic excited and ground states (a), and their time-dependence can be determined in pump–probe and four-wave mixing experiments. When level crossing occurs to another electronic state, the vibrational wavepacket may be observed to evolve along the reaction coordinate (b).

Ultrafast Vibrational Spectroscopy in Photochemistry: Structural Dynamics

Vibrational spectroscopy has, despite a smaller signal sensitivity due to smaller transition cross-sections, several advantages over electronic spectroscopy. Vibrational transitions have typically smaller bandwidths than electronic transitions, due to longer dephasing times (the exception to the rule: O–H/O–D stretching bands of hydrogen bonded hydroxyl groups). Specific signal contributions are thus easier tractable in vibrational spectroscopy than in electronic spectroscopy. Vibrational bands can often be correlated to specific vibrational motions by inspection of the transition frequencies, (e.g., O–H, N–H, and C–H stretching bands can be found in the 3000 cm^{-1} range, C=O and C=N stretching modes are located near 1,600–1,750 cm^{-1}, O–H, N–H, and C–H bending vibrations between 1,500–1,650 cm^{-1}, C–O stretching mode around 1,200–1,300 cm^{-1} etc.), and, in particular, the frequency range between 1,000 and 1,800 cm^{-1} is called the fingerprint region because of this reason. Measurement of vibrational bands thus leads to identification of particular vibrational motions, and conclusions can be drawn on specific structural motifs in the molecules. Vibrational bands can be infrared (IR) or Raman active, sometimes both, and both IR and Raman techniques have been widely applied in structural determination studies ranging from small molecules to larger biomolecular systems. In ultrafast photochemistry one thus excites the molecules with a UV/VIS pump pulse, and an IR/Raman probe pulse follows the outcome of the chemical reaction by inspection of vibrational bands of reactant, transients, and products.

Vibrational spectroscopy has the potential of revealing site-specific information if the marker modes are due to nuclear motions of specific molecular side-groups. For instance, hydrogen bonding induces marked shifts of O–H, N–H, C=O, and C=N bands. Observation of changes in spectral shifts reveals important information on hydrogen bond interactions (weakening/strengthening or even hydrogen bond cleavage). Infrared spectroscopy is able to probe small molecular species in solution that typically have their electronic resonances in the far-UV (making electronic spectroscopy impossible, since normally the solvent would absorb this radiation) (Figure 10). For instance, in acid–base neutralization reactions, where the acidity of a so-called photoacid is switched on by use of a UV pulse, a VIS probe pulse would only be able to probe the photoacid (or its conjugate photobase), thus revealing only when a proton leaves the photoacid. An infrared pulse can, besides probing vibrational resonances of the photoacid, also probe bands of a small base (or its conjugated acid) indicating when a proton arrives at the base.

In the case where the vibrational normal modes do not allow such a structural insight into site-specific groups, one can make a comparison of the



Figure 9 Solute–solvent interactions as characterized by the transition frequency fluctuation correlation function $C(t)$. This quantity can be measured in photon echo and time-resolved fluorescence experiments. In a three-pulse photon echo experiment phase information as given by the excited state frequency grating created with the first two interactions, is washed out due to solvent fluctuations and Stokes shifts to lower frequencies due to solvent rearrangement. A similar plot can be drawn for the ground state frequency grating.

experimentally observed vibrational bands with predictions made by quantum chemical calculations. When a full correspondence between experiment and theory is possible, one can make statements about the three-dimensional structure. With current quantum chemical calculational routines, such as density functional theory, medium-sized molecules are routinely calculated for electronic ground-state conformations. Reliable results of transient and product states in electronic excited states can be obtained with the routine *ab initio* complete active space self-consistent field (CASSCF), albeit for mid-size molecules of at most on the order of about 20 atoms. New developments in numerical procedures, such as time-dependent density functional theory (TD-DFT) may prove fruitful in the calculation of larger molecular systems in electronic excited states.

During recent years, femtosecond IR spectroscopy has been used in photo-induced chemical reactions ranging from excited state hydrogen and proton transfer, transformations of photochromic switches, excited state charge transfer, and cis–trans isomerizations. Here an ultrashort UV/VIS ‘pump’ pulse promotes the molecule to an electronic excited state, and the reaction is followed by a measurement of the absorbance change of a ‘probe’ pulse tuned in the mid-IR region where the vibrational marker modes sensitive to structural changes have their resonances. Experimentally, one performs spectrally resolved transient IR spectroscopy. Femtosecond IR parametric devices deliver pulses with bandwidths of 150 cm^{-1} or more. In order to be able to observe shifts as small as the linewidths of IR-active vibrations, one usually measures the IR absorbance change with a detector after spectral dispersion with a monochromator. As a side-effect of this spectral dispersion ground-state bleach signals often appear to grow in at negative pulse delay with the dephasing time of the transition. This effect, known as ‘perturbed free induction decay’ is a common feature of spectrally resolved nonlinear pump–probe spectroscopy of bleached transitions with dephasing times much longer than the time resolution of the experiment. The time resolution of the experiment is given by the cross-correlation between the UV/VIS-pump and IR-probe pulse (about 100–200 fs), and is typically dominated by group velocity mismatch in samples with thicknesses of about 100 μm.

In principle, the same approach can be followed by probing Raman-active vibrations. In this case the spectral resolution is not only determined by the monochromator through which the spontaneous Raman emission dispersed, but also by the bandwidth of the gating pulse by which the Raman effect is induced. As a result, UV/VIS pump–Raman probe



Figure 10 In excited state acid–base neutralization experiments, the proton dissociation can be followed on two sides with ultrafast infrared spectroscopy. Vibrational marker modes of photoacid and conjugated photobase indicate when the proton leaves the acid. The marker mode of acid formed by proton pick-up by the accepting base is a direct measure of the arrival time of the proton at the base. Depending on relative concentrations, either the indirect proton transfer via the solvent or direct scavenging of the proton by the base dominates the dynamics.

spectroscopy has a temporal resolution of around 1 ps (a compromise between spectral and time resolution). Due to the even weaker cross-sections of Raman transitions, one often uses resonance enhancement by tuning the gating pulse close to or resonant with an electronic transition of the state that is probed. The advantage is that one usually only observes Raman bands of the state under inspection. The drawback is that fluorescence resulting from the resonant electronic excitation often inhibits detection of Raman bands in extended spectral ranges.

Raman spectroscopy offers an additional insight into how chemical reactions evolve. By comparison of the intensities of anti-Stokes and Stokes lines of a particular vibration, it is possible to derive time-dependent changes in the excitation level of this vibration. One can draw conclusions on whether particular modes initially drive a chemical reaction ('state transition promoting modes'), or only get excited after the transition is made, by taking up the excess energy released by the reaction ('accepting modes'). In such a way, insight is obtained on the energy flow inside a molecular system (intramolecular vibrational redistribution, abbreviated as IVR) and vibrational energy dissipation to the surrounding solvent (vibrational cooling). Infrared spectroscopy is less powerful in revealing this, since red-shifted transient absorption of vibrational bands may either mean that the particular mode is highly excited (the red-shift is a consequence of the diagonal anharmonicity of the vibration), or it may mean that other modes are highly excited and these cause a red-shift of the marker mode under inspection (the red-shift is then due to off-diagonal anharmonic coupling with other modes).

Equilibrium Structural Dynamics in the Electronic Ground State

Existence of anharmonic coupling between vibrational modes means that the vibrational motions are not decoupled from each other. These couplings always exist, since otherwise no IVR and vibrational cooling (no relaxation) would occur. When the couplings are significantly large, excitation of one specific mode will induce a significant instantaneous shift of other vibrations anharmonically coupled to this particular mode. Estimation of the magnitude of these couplings should lead to a determination of the curvatures of potential energy surfaces along the respective coordinates. With current state-of-the-art femtosecond infrared technology (with time resolution of about 150 fs or less) it is possible to excite



Figure 11 In hydrogen-bonded hydroxyl groups a strong anharmonic coupling exists between the hydroxyl stretching and modes modulating the hydrogen-bond distance. A Born–Oppenheimer-like separation of time-scales of vibrational motion between the high-frequency O–H/O–D stretching and the low-frequency hydrogen bond modes enables a description with potential energy surfaces for the low-frequency mode as a function of the quantum state of the hydroxyl stretching vibration. The formation of low-frequency vibrational wavepackets in ultrafast IR spectroscopy of O–H/O–D stretching modes is then fully analogous to wavepacket formation in ultrafast electronic spectroscopy.

infrared-active vibrations and to probe the same or other vibrations (either in the IR or by the Raman process), enabling insight into the anharmonic couplings between these vibrational modes.

Direct anharmonic couplings are probed in IR-pump–IR-probe and IR photon echo spectroscopy (Figure 11). In the case of peptides, the excitonic (Davydov) couplings between amide I vibrations of the amino acid units have been the subject of extensive study since these lead to spatial information of the relative orientations of the different amide I modes, and thus, of the spatial orientation of the amino acid units inside the peptide. Exploring the effects of the delay between the IR pulses on the observed signals, give insight into the fluctuations of these orientational features, or in other words, into structural dynamics of peptides. In the case of hydrogen bonded O–H/O–D stretching vibrations, the anharmonic couplings with underdamped low-frequency modes modulating the hydrogen bond distance, lead to marked modulations of observed pump–probe and echo signals as function of pulse delay. These experiments reveal which modes couple strongly to the hydrogen stretching oscillator.

Fluctuations in couplings between vibrational modes (in particular with those of the solvent) induce dephasing of the vibrational coherences. The dephasing and spectral diffusion dynamics of vibrational transitions, e.g., the O–H stretch vibration of HOD dissolved in D_2O, have been determined by IR photon echo spectroscopy. From these studies the time-scales of structural memory decay of hydrogen bond networks can be derived. Couplings between vibrational modes ultimately lead to population relaxation through intramolecular vibrational redistribution effects and vibrational cooling. Ultrafast two-color IR-pump–IR-probe reveals whether excitation of one IR-active vibration is followed by population transfer into another IR-active mode.

With IR-pump–Raman-probe, one can estimate whether Raman-active vibrations are transiently excited. In the case of hydrogen-bonded O–H/O–D stretching bands, an extremely short population relaxation time T_1 (below 1 ps) is observed, as well as an ultrarapid dephasing time T_2 (200 fs or less). These values are definitely longer for other vibrations, from which it has been concluded that the strong anharmonicities in hydrogen-bonded vibrational systems enable dephasing and relaxation processes to have such a rapid impact.

Future Developments

Future activities in the determination of dynamically evolving molecular structures in the condensed phase, may involve the aforementioned application of amplitude and phase controlled excitation pulses in optimal control of chemical reactions. Vibrational spectroscopy may be used as a tool in determination of evolving structures after electronic excitation by a shaped pulse tuned in the UV/VIS. Infrared pulses could also be shaped in amplitude and phase, and may be used in the exploration of steering of chemical reactions in the electronic ground state. Multidimensional vibrational spectroscopy is an object of extensive research. Extension of the method to determination of structure of transient states will lead to new results on molecular rearrangements, e.g., polypeptides reaching a new equilibrium after inducing a UV-excitation induced geometric change of a photochromic switch incorporated in the peptide structure. Much activity is currently also being put in the development of ultrafast structure resolving techniques such as electron diffraction, X-ray diffraction, and X-ray spectroscopy. While still extremely demanding at a technological level, final implementation of these latter techniques will open up new areas of ultrafast chemical dynamics.

See also

Chemical Applications of Lasers: Pump and Probe Studies of Femtosecond Kinetics.

Further Reading

Cerullo G and De Silvestri S (2003) Ultrafast optical parametric amplifiers. *Review of Scientific Instruments* 74(1): 1–18.

de Boeij WP, Pshenichnikov MS and Wiersma DA (1998) Ultrafast solvation dynamics explored by femtosecond photon echo spectroscopies. *Annual Review of Physical Chemistry* 49: 99–123.

Elsaesser T and Bakker HJ (eds) (2002) *Ultrafast Hydrogen Bonding Dynamics and Proton Transfer in the Condensed Phase*. Dordrecht, Germany: Kluwer.

Elsaesser T and Kaiser W (1991) Vibrational and vibronic relaxation of large polyatomic molecules. *Annual Review of Physical Chemistry* 42: 83–107.

Fayer MD (ed.) (2001) *Ultrafast Infrared and Raman Spectroscopy*. New York: Marcel Dekker.

Fleming GR (1986) *Chemical Applications of Ultrafast Spectroscopy*. Oxford, UK: Clarendon Press.

Fleming GR and Cho M (1996) Chromophore-solvent dynamics. *Annual Review of Physical Chemistry* 47: 109–134.

Fleming GR and Hänggi P (eds) (1993) *Activated Barrier Crossing: Applications in Physics, Chemistry and Biology*. Singapore: World Scientific.

Kaiser W (ed.) (1988) *Ultrashort Laser Pulses and Applications*. Berlin: Springer.

Mukamel S (1995) *Principles of Nonlinear Optical Spectroscopy*. Oxford, UK: Oxford University Press.

Nibbering ETJ and Elsaesser T (2004) Ultrafast vibrational dynamics of hydrogen bonds in the condensed phase. *Chemical Reviews* 104: 1887–1914.

Owrutsky JC, Raftery D and Hochstrasser RM (1994) Vibrational relaxation dynamics in solutions. *Annual Review of Physical Chemistry* 45: 519–555.

Sundström V (ed.) (1996) *Nobel Symposium: Femtochemistry and Femtobiology: Ultrafast Reaction Dynamics at Atomic-Scale Resolution*. Singapore: World Scientific.

Wiersma DA (ed.) (1994) *Femtosecond Reaction Dynamics*. Amsterdam: North-Holland.

Zewail AH (2000) Femtochemistry: atomic-scale dynamics of the chemical bond. Nobel lecture as appeared in *Journal of Physical Chemistry A* 104(24): 5660–5694.

Web-information: http://www.nobel.se
Nobel web-site showing information on Nobel Laureates M Eigen, RGW Norrish and G Porter (The Nobel Prize in Chemistry 1967: ‘for their studies of extremely fast chemical reactions, effected by disturbing the equilibrium by means of very short pulses of energy’) and AH Zewail (The Nobel Prize in Chemistry 1999: ‘for his studies of the transition states of chemical reactions using femtosecond spectroscopy’).

Ultrafast Illumination and Processing

Y Fainman, University of California, San Diego, CA, USA

D M Marom, Bell Laboratories, Holmdel, NJ, USA

© 2005, Elsevier Ltd. All Rights Reserved.

Introduction

Mode-locked lasers emitting ultrashort pulses have expanded the range of available instruments and techniques to the scientific community. The unique properties of these ultrashort pulses – their high peak powers and short duration – enable such diverse applications as multiphoton microscopy, pump-probe experiments, and coherent control of molecular and atomic wavepackets, to name a few. Ultrashort pulses can also be used as a basis for ultrahigh data rate optical communications using time division multiplexing (TDM) in a fiber communication application. These ultrafast applications often require complementary real-time optical processors based on instantaneous nonlinear phenomena, since conventional electronic means are limited by the response time of electronic devices.

During the last few years, we have developed real-time optical processors utilizing nonlinear three- and four-wave mixing of signals originating from spatial or temporal channels for synthesizing, processing, and detecting ultrafast waveforms. We perform real-time optical signal processing that can be applied to data conversion between slow parallel channels in space and an ultrafast serial signal. A time-to-space mapping processor has been built for detection of ultrafast waveforms. It mixes two spatially inverted temporal frequency information waves in a three-wave mixing arrangement, generating a quasi-monochromatic spatial signal carrying the temporal image for detection by slower electronic means. A space-to-time mapping processor was constructed for generation of arbitrary ultrafast waveforms from an input ultrashort pulse. The waveform is a time-scaled replica of the employed input spatial image, converted by a four-wave mixing arrangement. By introducing only temporal information channels to our four-wave mixing processors, real-time optical processing of temporal waveforms was enabled. We have demonstrated time reversal experiments based on performing spectral phase conjugation and spectral inversion operations, achieving time reversal of the electrical field and of the complex amplitude waveform, respectively. The three- and four-wave mixing arrangements are performed within a spectral processing device – a free-space optical setup consisting of diffraction gratings and lenses – utilizing a $\chi^{(2)}$ nonlinear crystal. A cascaded second-order nonlinearity technique is used for four-wave mixing within the $\chi^{(2)}$ crystal (a frequency-sum generation process followed by a frequency-difference generation process satisfying the type-II noncollinear phase matching condition). However, a $\chi^{(3)}$ nonlinear crystal may be readily substituted without loss of generality (albeit with a likely smaller conversion efficiency).

This article reviews the spatial/temporal processing techniques for synthesizing, processing, and detecting ultrafast waveforms. The generation of spectrally decomposed waves within a spectral processing device is described in the following section. The subsequent section articulates on the employed nonlinear wave mixing processes, and the ensuing sections express the synthesis, processing, and detection of ultrafast waveforms.

Generation and Characteristics of Spectrally Decomposed Waves

Our wave mixing experiments are performed with spectrally decomposed waves, in which the spectral frequency content is spatially dispersed. When the pulse is decomposed with high resolution, the signal at every spatial location can be treated as quasi-monochromatic. This allows for increased interaction length within a nonlinear crystal, allowing us to use long crystals, whereas typically the interaction length is limited by temporal walkoff. In this section we analyze the creation of spectrally decomposed waves.

We introduce an ultrashort optical waveform, with a temporal envelope of $s(t/\tau)$, into the spectral processing device, where τ parameterized the waveform's duration. The waveform is propagating in free space towards a diffraction grating, at an incidence angle θ (see Figure 1). The input ultrashort waveform is characterized in its coordinate system (x_1, z_1) as:

$$E_{\text{pulse}}(x_1, z_1; t) = w\left(\frac{x_1}{L_1}\right) s\left(\frac{t - t_0 - z_1/c}{\tau}\right) \times \exp\left(\mathrm{i}\left(\omega_0 t - \frac{\omega_0}{c} z_1\right)\right) \qquad [1]$$

where $w(\cdot)$ defines the transversal field distribution with a scale size parameter L_1, t_0 is a time delay parameter, c is the speed of light in vacuum, and ω_0 is the center optical frequency. The waveform is



Figure 1 An ultrashort optical waveform, $s(t/\tau)$, propagating in free-space is incident upon a diffraction grating at angle θ. The transverse spatial mode of the pulse is stretched due to the projection onto the grating.

propagating in the z_1 direction at a group velocity and phase velocity of the speed of light in vacuum. The spatial confinement in the y_1 direction is omitted for brevity. We perform a time-domain Fourier transform (TFT) on eqn [1] to perform a frequency decomposition of the ultrafast waveform, yielding:

$$\begin{aligned}\tilde{E}_{\text{pulse}}(x_1, z_1; \omega) = {} & \tau w\left(\frac{x_1}{L_1}\right) \\ & \times \exp\left(-\mathrm{i}\frac{\omega}{c}z_1\right)\tilde{s}(\tau(\omega-\omega_0)) \\ & \times \exp(-\mathrm{i}(\omega-\omega_0)t_0)\end{aligned} \qquad [2]$$

where the tilde over the script denotes a FT relationship, defined for the TFT as $\tilde{s}(\omega)A\int s(t)\exp(-\mathrm{i}\omega t)\mathrm{d}t$. Next we perform a rotation of the coordinate system from (x_1, z_1) to (x, z), for compatibility with the coordinate system of the spectral processing device, yielding:

$$\begin{aligned}\tilde{E}_{\text{pulse}}(x, z; \omega) = {} & \tau w\left(\frac{x\cos\theta - z\sin\theta}{L_1}\right) \\ & \times \exp\left(-\mathrm{i}\frac{\omega}{c}(x\sin\theta + z\cos\theta)\right) \\ & \times \tilde{s}(\tau(\omega-\omega_0))\exp(-\mathrm{i}(\omega-\omega_0)t_0)\end{aligned} \qquad [3]$$

To find the incident field on the input grating of the spectral processing device, the field of eqn [3] is evaluated at $z = 0$. The effect of the grating diffraction can be modeled by adding the grating momentum, k_{g}, in the x direction to the k-vector that characterizes the propagation direction of the wave, resulting in:

$$\begin{aligned}\tilde{E}_{\text{input}}(x, 0; \omega) = {} & \tau w\left(\frac{x\cos\theta}{L_1}\right) \\ & \times \exp\left(-\mathrm{i}\left(\frac{\omega}{c}\sin\theta - k_{\text{g}}\right)x\right) \\ & \times \tilde{s}(\tau(\omega-\omega_0))\exp(-\mathrm{i}(\omega-\omega_0)t_0)\end{aligned} \qquad [4]$$

The grating momentum, k_{g}, and the incidence angle, θ, are chosen such that the center frequency ω_0 will diffract in the direction of the optical axis of the system. Setting $\omega_0/c\cdot\sin\theta = k_{\text{g}}$ and substituting the grating's k-vector, $k_{\text{g}} = 2\pi/\Lambda$, where Λ is the grating period, yields $\sin\theta = \lambda_0/\Lambda \equiv \alpha$, where λ_0 is the optical wavelength corresponding to the center carrier frequency. To further simplify the notation, we define a new spatial width scaling parameter $L = L_1/\cos(\theta)$, accounting for the aperture size increase due to the projection onto the diffraction grating. With these substitutions, the expression takes on the more familiar form, given by

$$\begin{aligned}\tilde{E}_{\text{input}}(x; \omega) = {} & \tau w\left(\frac{x}{L}\right)\exp\left(-\mathrm{i}\frac{(\omega-\omega_0)\alpha x}{c}\right) \\ & \times \tilde{s}(\tau(\omega-\omega_0))\exp(-\mathrm{i}(\omega-\omega_0)t_0)\end{aligned} \qquad [5]$$

We may perform an inverse TFT on eqn [5] to characterize the input signal in the time domain, yielding:

$$E_{\text{input}}(x; t) = w\left(\frac{x}{L}\right)s\left(\frac{t - t_0 - \alpha x/c}{\tau}\right)\exp(\mathrm{i}\omega_0 t) \qquad [6]$$

Equation [6] describes the input waveform scanning across the fixed aperture at velocity of c/α in the x-direction.

The spectrally decomposed wave is generated by performing a spatial Fourier transform (SFT) employing a lens of focal length f on the input wave (either frequency domain representation, eqn [4], or time domain representation, eqn [6]). Using the frequency domain representation, the spectrally decomposed wave U_{SDW} of the input waveform is given by

$$\begin{aligned}U_{\text{SDW}}(x'; \omega) = {} & \tau\tilde{s}(\tau(\omega-\omega_0)) \\ & \times \exp(-\mathrm{i}(\omega-\omega_0)t_0)\int_{-\infty}^{\infty} w\left(\frac{x}{L}\right) \\ & \times \exp\left(-\,\mathrm{i}(\omega-\omega_0)\frac{\alpha x}{c}\right) \\ & \times \exp\left(-\mathrm{i}2\pi\frac{xx'}{\lambda_0 f}\right)\mathrm{d}x\end{aligned} \qquad [7]$$

where we use the central wavelength in the Fourier transform kernel. Evaluating the integration of eqn [7], yields:

$$U_{\mathrm{SDW}}(x';\omega) = L\tau\tilde{s}(\tau(\omega-\omega_0))\exp(-\mathrm{i}(\omega-\omega_0)t_0) \times \tilde{w}\left(\frac{\alpha L}{2\pi c}\left[\frac{\omega_0 x'}{\alpha f}+(\omega-\omega_0)\right]\right) \quad [8]$$

where the SFT of the input pupil function, $\tilde{w}(f_x) A \int w(x)\exp(-\mathrm{i}2\pi x f_x)\mathrm{d}x$, has mixed space-domain and time-domain frequency variables in its argument, characterizing the dispersion. A spectral component shifted away from the center frequency, $\Delta\omega = \omega - \omega_0$, will be centered at a displaced location $\Delta x' = -\Delta\omega\cdot\alpha f/\omega_0$, defining the spatial dispersion term $\partial x'/\partial\omega = -\alpha f/\omega_0$. One can see that in order to get fine localization of each spectral component, the spatial extent of the function $\tilde{w}(\cdot)$ must be minimized. This can be readily achieved by increasing the size of the input aperture, or the parameter L, as well as increasing α (grating's angular dispersion). Let us make the following observation on system resolution: The ultrafast pulse's spectral width is proportional to $1/\tau$, and its spatial extent is therefore proportional to $\alpha f/\omega_0\tau$ (multiplying by the spatial dispersion term). The spatial width of each spectral component is proportional to $cf/\omega_0\tau$. The dimensionless ratio of these two spatial widths, which is indicative of the number of resolvable spectral components, is $N \sim \alpha L/c\tau$, where N is defined as the system spectral resolution. When the spectral processing device is designed to satisfy the requirement of $N \gg 1$, then the spectrally decomposed wave can be considered quasi-monochromatic at every spatial position. In our experiments, we use $\lambda_0 = 800$ nm, gratings of 600 lines/mm frequency ($\Lambda = 1666$ nm), $L \approx 1$ cm, and $\tau \approx 100$ femtoseconds, yielding $\alpha \cong 0.5$ and $N \sim 160$, easily satisfying the high spectral resolution requirement. Let us make a second observation on system resolution using the time domain representation of eqn [6]: The spatial extent of the input aperture is proportional to L, whereas the instantaneous spatial extent of the scanning waveform is proportional to $\tau c/\alpha$ (see Figure 2). The dimensionless ratio of these two spatial widths is again $N \sim \alpha L/c\tau$, exemplifying the concept of resolvable positions and demonstrating the conservation of the space-bandwidth product.



Figure 2 The input short pulse scans across the diffraction grating at velocity of *c/α*. The ratio of the width of the spatial mode of the beam to the instantaneous spatial width of the scanning waveform determines the system resolution. © 2001 Optical Society of America.

To further facilitate the ensuing analysis, let us assume that we operate in the high-resolution regime (satisfied with the values given above), and we seek to simplify the expressions defining the spectrally decomposed wave. The spectrally decomposed wave can be defined in the time domain by performing a SFT on eqn [6], yielding:

$$\begin{aligned} U_{\mathrm{SDW}}(x';t) &= \int w\left(\frac{x}{L}\right)s\left(\frac{t-t_0-\alpha x/c}{\tau}\right)\exp(\mathrm{i}\omega_0 t) \\ &\quad\times\exp\left(-\mathrm{i}\frac{2\pi}{\lambda_0 f}xx'\right)\mathrm{d}x \\ &\approx w\left(\frac{c(t-t_0)}{\alpha L}\right)\exp\left(-\mathrm{i}\frac{\omega_0(t-t_0)x'}{\alpha f}\right) \\ &\quad\times\tilde{s}\left(-\frac{\omega_0\tau x'}{\alpha f}\right)\exp(\mathrm{i}\omega_0 t) \end{aligned} \quad [9]$$

where by account of the high-resolution approximation, the instantaneous location of the traveling signal waveform samples the value of the aperture function and removes the aperture dependence from the Fourier integral. This approximation decouples the aperture function from the temporal waveform, and illustrates that the duration of the spectrally decomposed wave is defined by the aperture function (time of flight through aperture of size L), and that the spatial dependence is a mapping of the incident waveform spectrum. A rotating wavevector in time is also present, on account of the traveling (moving) waveform on the input plane. Again, we may perform a TFT on eqn [9], defining the high-resolution limit of the spectrally decomposed wave, yielding:

$$U_{\mathrm{SDW}}(x';\omega) = \tilde{s}\left(-\frac{\omega_0\tau x'}{\alpha f}\right)\exp(-\mathrm{i}(\omega-\omega_0)t_0) \times\tilde{w}\left(\frac{\alpha L}{2\pi c}\left[\frac{\omega_0 x'}{\alpha f}+(\omega-\omega_0)\right]\right) \quad [10]$$

One can compare eqns [8] and [10], as both characterize the spectrally decomposed wave in the



(a) Three-wave mixing in a $\chi^{(2)}$ crystal



(b) Four-wave mixing by cascaded $\chi^{(2)}$ processes

Figure 3 (a) Three-wave mixing interaction: two input waves U_1 and U_2, generate a third wave U_3. (b) Four-wave mixing by cascaded second order nonlinearities: three input waves, U_1, U_2, and U_3, generate a fourth wave U_4. The first two waves generate an intermediate wave U_{int}, by a frequency-sum process, followed by a frequency-difference process between the intermediate wave and the third input wave.

temporal frequency domain, and observe that the difference lies with the argument of the spectral term. If we apply the high-resolution approximation to eqn [8], then each spectral component would occupy a small region in space, as defined by the extent of the aperture function's SFT. Substituting for $\omega - \omega_0$ by $-\omega_0 x'/\alpha f$ for the spectral argument of eqn [8], corresponding to the high-resolution limit, equates the two expressions (essentially the same approximation as was performed in deriving eqn [9]).

Nonlinear Wave Mixing With Nondepleting Pumps

A nonlinear crystal exhibiting a large nonlinear susceptibility $\chi^{(2)}$ is placed at the Fourier plane of the spectral processing device. We employ noncollinear phase matching in our experiments. Either type-I or type-II phase matching conditions can be used in three-wave mixing experiments, with the resultant frequency-sum wave propagating along the bi-sector direction (see Figure 3a). Since both input waveforms are at ω_0 frequency, the generated field will be at a doubled carrier frequency, $2\omega_0$, due to the frequency-sum process. Four-wave mixing experiments use type-II phase matching in the $\chi^{(2)}$ crystal, involving a frequency-sum process generating an intermediate wave followed by a frequency-difference process between the intermediate wave and the third input wave. The resultant wave will co-propagate with one of the input waves and at the same temporal carrier frequency (propagation direction and frequency ω_0), albeit at an orthogonal polarization state (see Figure 3b). The output signal can be extracted using a polarizer or a polarizing beam splitter. The interacting input waves propagate noncollinearly at the Fourier transform plane by offsetting the signals from each other at the input plane of the spectral processing device.

While it is possible, though often difficult, to obtain a precise analytic solution to the coupled mode equations governing the wave-mixing processes for the generated waves, it is beyond the scope of this article whose focus is on the signal processing functionality. We therefore limit the analysis to weak interactions with nondepleting input waves. Using the nondepleted input waves approximation, the nonlinear polarization term, which drives the generation of new waves, is constant and an ordinary differential equation characterizes the generation process.

The nonlinear polarization for the frequency-sum process is proportional to the product of the input waves, when expressed in the time domain: $P_{\text{NL}}^{\text{sum}}(x';t) = \chi_{\text{eff}}^{(2)} U_1(x';t) U_2(x';t)$. The nonlinear polarization for the frequency-difference process is proportional to the product of an input waves and a conjugated input wave: $P_{\text{NL}}^{\text{diff}}(x';t) = \chi_{\text{eff}}^{(2)} U_1(x';t) U_2^*(x';t)$.

The solution of the ordinary differential equation driving the generation of the new wave, takes into account the possible phase mismatch between the propagation of the nonlinear polarization and the generated wave within the nonlinear crystal medium. Since we are interested in the signal processing functionality only, we approximate the generated waves as being directly proportional to the driving nonlinear polarization. This approach is valid for obtaining the generated signal forms in the case of short nonlinear crystals (limited interaction length) satisfying the phase matching condition. In practice, the temporal and spatial bandwidths, as well as the crystal length, will introduce filtering effects which will slightly modify the output signals. However, it can be shown that when wave mixing with spectrally decomposed waves, especially mutually inverted waves, the phase matching requirement is well satisfied and the filtering effects are negligible for the employed crystal lengths. In our experiments, we typically used 2 mm long β-barium borate (BBO) crystals. Using the simplified method for obtaining the form of the generated waves, arrangements for synthesizing, processing, and detecting ultrafast waveforms can be explored.

Detection of Ultrafast Waveforms

Ultrafast optical waveforms are too rapid for acquisition by opto-electronic means alone, due to the latter's finite response time. An optical processor is usually required to convert a finite time window (typically in the tens to hundreds of ps range) to a stationary signal in space for detection by slower means. We mix two mutually inverted spectrally decomposed waves in the Fourier plane of a spectral processing device, and spatially Fourier transform the resultant wave to the output plane. As will be shown below, when one of the spectrally decomposed waves is generated by a transform limited short pulse, the output spatial signal carries the temporal information of the input waveform. We call this process a time-to-space converter.

Let two ultrafast waveforms, $s((t-t_0)/\tau)$ and $r(t/\tau)$, enter the spectral processing device from opposite directions (one strikes the grating at angle θ and the other at $-\theta$, see Figure 4). Each waveform will generate a spectrally decomposed wave in the spatial Fourier transform plane. The spectrally decomposed wave of the signal $s(t)$, as defined by eqn [9], yields the first input field:

$$U_1(x';t) \approx w\left(\frac{c(t-t_0)}{\alpha L}\right)\exp\left(-\mathrm{i}\frac{\omega_0(t-t_0)x'}{\alpha f}\right) \times \tilde{s}\left(-\frac{\omega_0\tau x'}{\alpha f}\right)\exp(\mathrm{i}\omega_0 t) \qquad [11a]$$

whereas the inverted spectrally decomposed wave for $r(t/\tau)$ is given by

$$U_2(x';t) \approx w\left(-\frac{ct}{\alpha L}\right)\exp\left(\mathrm{i}\frac{\omega_0 t x'}{\alpha f}\right)\tilde{r}\left(\frac{\omega_0\tau x'}{\alpha f}\right)\exp(\mathrm{i}\omega_0 t) \qquad [11b]$$

Without loss of generality, we set the time delay parameter in eqn [11b] to zero, such that the parameter t_0 in the spectrally decomposed wave of the signal waveform is a measure of the relative time delay of the two waveforms. With full knowledge of the two input waves, U_1 and U_2, we can express the resultant waveform of the three-wave mixing process as:

$$U_3(x';t) \propto P_{\mathrm{NL}}^{\mathrm{sum}}(x';t) = w\left(\frac{c(t-t_0)}{\alpha L}\right)w\left(-\frac{ct}{\alpha L}\right) \times \exp\left(\mathrm{i}\frac{\omega_0 t_0 x'}{\alpha f}\right)\tilde{s}\left(-\frac{\omega_0\tau x'}{\alpha f}\right)\tilde{r}\left(\frac{\omega_0\tau x'}{\alpha f}\right) \times \exp(\mathrm{i}2\omega_0 t) \qquad [12]$$

Next we apply a SFT to propagate the wave U_3 to the output plane, yielding:

$$U_{\mathrm{out}}(x'';t) = \int U_3(x';t)\exp\left(-\mathrm{i}\frac{2\pi}{\lambda_0 f/2}x'x''\right)\mathrm{d}x' = y\left(\frac{2\alpha x''}{c}-t_0\right)w\left(\frac{c(t-t_0)}{\alpha L}\right)w\left(-\frac{ct}{\alpha L}\right) \times \exp(\mathrm{i}2\omega_0 t_0) \qquad [13]$$

where $y(t) = s(t/\tau)\otimes r(-t/\tau)$, as the Fourier transform of a product is the convolution of their Fourier transforms (the $\otimes$-symbol denotes the convolution operation), and we use the spatial Fourier transform kernel at the doubled carrier frequency. The stationary spatial signal, $y(\cdot)$, is proportional to the convolution of the two input waveforms, where



Figure 4 Arrangement for imaging ultrafast waveforms using a time-to-space conversion. The mutually inverted, spectrally decomposed waves of a signal waveform and that of a reference pulse are mixed in a nonlinear crystal placed at the Fourier plane. The generated wave is spatially Fourier transformed to the output plane, yielding a stationary image that carries the signal waveform information. © 2001 Optical Society of America.



Figure 5 Output of a time-to-space converter. Top: image acquired by a CCD camera of the stationary image of a pulse sequence. Botttom: extracted time domain data from the image, showing inter-pulse time separation of 1.25 ps.

one of them is reversed in time. This mixing process was developed for time-to-space conversion by using a reference transform limited pulse for the reversed waveform. The resulting spatial image will be that of the signal waveform, albeit smoothed out due to the convolution operation with the reference pulse. The spatial signal is centered at $x'' = ct_0/2\alpha$, illustrating that the relative time delay between the two waveforms shifts the location of the output signal. The temporal characteristic is determined by the product of the time-scaled input apertures. The relative time delay, t_0, serves as an attenuation mechanism when the time windows are not perfectly aligned. When the time delay between the signal pulse and the reference pulse is too large, no output signal will emerge as the two signals do not overlap for the wave mixing process. Therefore, the time window of the spectral processing device is determined by the input aperture size, not the physical dimension of the nonlinear crystal. Consequently, we have been able to demonstrate high-resolution temporal imaging with time windows in the range of tens of picoseconds (see Figure 5). Additionally, as mentioned earlier, one of the significant advantages of this technique is the favorable phase matching condition with the spectrally decomposed wave and its inverted counterpart.

Processing of Ultrafast Waveforms

The simplest form of ultrafast waveform processing uses linear filtering, or placement of an element with transmittance characteristics that are frequency selective. However, a linear filter is a time invariant process and cannot perform more advanced processing operations of ultrafast waveforms such as interaction between ultrafast waveforms. For such processing applications, we mix three spectrally decomposed waves in the Fourier plane of a spectral processing device to generate a resultant output ultrafast waveform in real time. We illustrate advanced processing by performing a time reversal experiment using the spectral phase conjugation and spectral inversion techniques in four-wave mixing experiments.

Consider three ultrafast waveforms, $s_1(t - t_0/\tau)$, $s_2((t - t_1)/\tau)$ and $s_3(t/\tau)$, which enter a spectral processing device for generation of their respective spectrally decomposed waves. Let all three waves enter the spectral processing device from the same direction, such that the spatial dispersion is in the same direction for each signal (as defined by eqn [11a]), and generate the spectrally decomposed waves $U_1(x';t)$, $U_2(x';t)$, and $U_3(x';t)$, respectively (see Figure 6a). Since we utilize a cascaded second-order nonlinearity process, we let the first two waves interact first in a frequency-sum process, generating the intermediate field:

$$\begin{aligned} U_{\mathrm{int}}(x';t) \propto P_{\mathrm{NL}}^{\mathrm{sum}}(x';t) &= w\left(\frac{c(t-t_0)}{\alpha L}\right) w\left(\frac{c(t-t_1)}{\alpha L}\right) \\ &\times \exp\left(-\mathrm{i}\frac{\omega_0(2t-t_0-t_1)x'}{\alpha f}\right)\tilde{s}_1\left(-\frac{\omega_0\tau x'}{\alpha f}\right) \\ &\times \tilde{s}_2\left(-\frac{\omega_0\tau x'}{\alpha f}\right)\exp(\mathrm{i}2\omega_0 t) \end{aligned} \qquad [14]$$

It should be noted that upon a more rigorous analysis of the generated frequency-sum wave, phase matching is not well met across the temporal bandwidth of the waveform, as is the case when wave mixing mutually inverted spectrally decomposed waves. This will introduce time domain spectra filtering effects, but for simplicity these effects are ignored below. The generated frequency-sum wave interacts with the third input wave in a frequency-difference process, giving rise to the fourth wave:

$$\begin{aligned} U_4(x';t) \propto P_{\mathrm{NL}}^{\mathrm{diff}}(x';t) &= w\left(\frac{c(t-t_0)}{\alpha L}\right) w\left(\frac{c(t-t_1)}{\alpha L}\right) \\ &\times w\left(\frac{ct}{\alpha L}\right)\exp\left(-\mathrm{i}\frac{\omega_0(t-t_0-t_1)x'}{\alpha f}\right) \\ &\times \tilde{s}_1\left(-\frac{\omega_0\tau x'}{\alpha f}\right)\tilde{s}_2\left(-\frac{\omega_0\tau x'}{\alpha f}\right)\tilde{s}_3^*\left(-\frac{\omega_0\tau x'}{\alpha f}\right)\exp(\mathrm{i}\omega_0 t) \end{aligned} \qquad [15]$$


Reference pulse
Complex amplitude information
Reference pulse
Spectral phase conjugation
Nonlinear $\chi^{(2)}$ crystal with type II phase matching
PBS
PBS
x'
$w[x]$
θ
D
$w[x]$
U_1
$U_2 \odot + U_3$
U_{int}
$U_4 \odot + U_1$
Polarized to crystal's ordinary axis
Polarized to crystal's extraordinary axis
(a)
Reference pulse
Spectral information inversion
Nonlinear $\chi^{(2)}$ crystal with type II phase matching
PBS
x'
$w[x]$
θ
D
U_1
$U_2 \odot + U_3$
U_{int}
$U_4 \odot + U_1$
$w[x]$
θ
PBS
Reference pulse
Complex amplitude information
Polarized to crystal's ordinary axis
Polarized to crystal's extraordinary axis
(b)

Figure 6 Arrangements of processing ultrafast waveforms within a spectral processing device. (a) Three input waveforms are introduced from the same direction, and their spectrally decomposed waves interact via four-wave mixing. (b) The three input waveforms are introduced from opposite directions, giving rise to mutually inverted spectrally decomposed waves. These two arrangements can perform time reversal, the first by spectral phase conjugation and the second by spectral information inversion. © 2001 IEEE.

where we assume that the window function $w(\cdot)$ is real. Next we apply a SFT to propagate the wave U_4 to the output plane, yielding:

$$\begin{aligned} U_{\text{out}}(x'';t) &= \int U_4(x';t)\exp\left(-\mathrm{i}\frac{2\pi}{\lambda_0 f}x'x''\right)\mathrm{d}x' \\ &= y\left(\frac{\alpha x''}{c}+t-t_0-t_1\right)w\left(\frac{c(t-t_0)}{\alpha L}\right) \\ &\quad\times w\left(\frac{c(t-t_1)}{\alpha L}\right)w\left(\frac{ct}{\alpha L}\right)\exp(\mathrm{i}\omega_0 t_0) \qquad [16] \end{aligned}$$

where $y(t) = s_1(t/\tau)\otimes s_2(t/\tau)\otimes s_3^*(-t/\tau)$. The new ultrafast waveform $y(\cdot)$ scans along the output plane at a velocity of $-c/\alpha$ in the x-direction (compare to the input signals scanning in the opposite direction along the input plane, eqn [6]). By placing another diffraction grating at this plane, the new ultrafast waveform can be recomposed and made to propagate once more in free space. The waveform information consists of a convolution between the first and second signals, followed by a convolution with the third signal, which is both conjugated and reversed. If we set the first and second signals to be transform limited pulses, then the resultant waveform will carry the reversed and conjugated information of the third signal. Such capability can be very important for dispersion compensation in optical fiber communication links.

Let us now consider an alternate arrangement, where the second and third input signals are introduced to the spectral processing device from the opposite direction, and consequently have reversed spatial dispersion direction (see Figure 6b). Therefore, the first signal will generate a spectral decomposed wave $U_1(x';t)$, as defined by eqn [11a], whereas the second and third signals will give rise to the spectrally decomposed waves $U_2(x';t)$ and $U_3(x';t)$, with inverted spectra relative to that of U_1, as defined by eqn [11b]. The interaction of the first two waves gives rise to:

$$\begin{aligned} U_{\text{int}}(x';t) \propto P_{\text{NL}}^{\text{sum}}(x';t) &= w\left(\frac{c(t-t_0)}{\alpha L}\right) \\ &\quad\times w\left(-\frac{c(t-t_1)}{\alpha L}\right)\exp\left(\mathrm{i}\frac{\omega_0(t_0+t_1)x'}{\alpha f}\right) \\ &\quad\times \tilde{s}_1\left(-\frac{\omega_0\tau x'}{\alpha f}\right)\tilde{s}_2\left(\frac{\omega_0\tau x'}{\alpha f}\right)\exp(\mathrm{i}2\omega_0 t) \end{aligned} \qquad [17]$$

which is identical to the wave mixing process of the time-to-space converter (see eqn [12]). However, in this case, we follow the first wave mixing process by a frequency-difference process, generating:

$$U_4(x';t) \propto P_{\mathrm{NL}}^{\mathrm{diff}}(x';t) = w\left(\frac{c(t-t_0)}{\alpha L}\right) w\left(-\frac{c(t-t_1)}{\alpha L}\right) \times w\left(-\frac{ct}{\alpha L}\right) \exp\left(-\mathrm{i}\frac{\omega_0(t-t_0-t_1)x'}{\alpha f}\right) \tilde{s}_1\left(-\frac{\omega_0 \tau x'}{\alpha f}\right) \times \tilde{s}_2\left(\frac{\omega_0 \tau x'}{\alpha f}\right) \tilde{s}_3^*\left(\frac{\omega_0 \tau x'}{\alpha f}\right) \exp(\mathrm{i}\omega_0 t) \qquad [18]$$

Next we apply a SFT to propagate the wave U_4 to the output plane, yielding the output waveform:

$$\begin{aligned} U_{\mathrm{out}}(x'';t) &= \int U_4(x';t) \exp\left(-\mathrm{i}\frac{2\pi}{\lambda_0 f} x' x''\right) \mathrm{d}x' \\ &= y\left(\frac{\alpha x''}{c} + t - t_0 - t_1\right) w\left(\frac{c(t-t_0)}{\alpha L}\right) \\ &\quad \times w\left(-\frac{c(t-t_1)}{\alpha L}\right) w\left(-\frac{ct}{\alpha L}\right) \exp(\mathrm{i}\omega_0 t_0) \qquad [19] \end{aligned}$$

where $y(t) = s_1(t/\tau) \otimes s_2(-t/\tau) \otimes s_3^*(t/\tau)$. As before, the new ultrafast waveform $y(\cdot)$ scans along the output plane at a velocity of $-c/\alpha$ in the x-direction, and will propagate in free-space upon another grating diffraction. This time, however, the waveform information consists of a convolution between the first signal and a time-reversed second signal, followed by a convolution with the conjugated third signal. If we set the first and second signals to be transform limited pulses, then the resultant waveform will carry the conjugated information of the third signal. If we set the first and third signals to be transform limited pulses, then the resultant waveform will carry the reversed information of the second signal.

We have experimentally demonstrated the two time-reversal techniques: the first technique whereby the resultant signal is both reversed and conjugated is labeled ‘spectral phase conjugation’, as the signal’s spectrum is conjugated by the frequency difference process, and the second technique, where the signal is purely reversed in time, is named ‘spectral information inversion’, as the spectrum is flipped about the carrier frequency (see Figure 7). By proper selection of the input waveforms, one can also obtain higher-level operations and functionality such as convolutions and correlations among the different signals. All these operations are time-variant, and cannot be performed by passive filtering alone.



Figure 7 Time reversal experimental results. (a) Input pulse pair consisting of a transform limited pulse followed by a chirped pulse. (b) Time reversal by spectral information inversion technique. Chirped pulse leads transform limited pulse and maintains the sign of the chirp. (c) Time reversal by spectral phase conjugation technique. Chirped pulse leads transform limited pulse and flips the sign of the chirp. Data acquired with time-to-space imaging technique and sign of quadratic term (dashed line) determined by translating output plane.

Synthesis of Ultrafast Waveforms

Shaping of ultrafast waveforms is usually performed by filtering an input transform limited pulse by a fixed filter. Adaptive filtering can be performed by various means incorporating opto-electronic modulators such as liquid-crystal-based or acousto-optic-based spatial light moduloators, however the response time required for changing the waveform is typically limited to the ms and μs regime, respectively. For ultrafast reconfigurability, we utilize our spectral processing device and wave mixing, to achieve pulse shaping controlled by light, or a second optical signal.

Let the three input signals entering the spectral processing device be an ultrashort waveform, $s(t/\tau)$, and two additional spatial domain signals; one carrying spatial information $m(x/\chi)$, where χ is a scaling factor, and the second a point source (see Figure 8). Both spatial domain signals are illuminated


x_1
z_1
Temporal reference pulse
θ
x
z
D
Spatial reference point
PBS
Spatial image channel
U_1
U_2+U_3
x'
z'
U_1+U_4
U_{int}
Residual of temporal pulse
Nonlinear $\chi^{(2)}$ crystal with type II phase matching
PBS
x_2
z_2
x''
z''
Real-time synthesized waveform
Polarization parallel to crystal's ordinary axis
Polarization parallel to crystal's extraordinary axis

Figure 8 Arrangement for ultrafast waveform synthesis by wave mixing temporal and spatial information channels. Three input channels consist of a temporal channel, a spatial channel carrying information, and a second spatial channel consisting of a point source. The information from the spatial channel is transferred to the temporal channel via the wave mixing process. © 2001 IEEE.

by a monochromatic light source at frequency ω_0. The input ultrashort waveform gives rise to a spectrally decomposed wave $U_1(x';t)$, as described by eqn [11a]. The spatial information channel is SFT by a lens, generating the wave:

$$U_2(x';t) \propto \tilde{m}\left(\frac{\omega_0 \chi x'}{2\pi c f}\right)\exp(\mathrm{i}\omega_0 t) \qquad [20]$$

The signal from the point source (or $\delta(x)$) gives rise to a wave $U_3(x';t)$ with no spatial information (plane wave). As before, we utilize cascaded second-order nonlinearities for the wave mixing process. The interaction of the first two waves gives rise to the intermediate frequency-sum wave:

$$\begin{aligned} U_{\mathrm{int}}(x';t) &\propto P_{\mathrm{NL}}^{\mathrm{sum}}(x';t) \\ &= w\left(\frac{ct}{\alpha L}\right)\tilde{s}\left(-\frac{\omega_0 \tau x'}{\alpha f}\right)\tilde{m}\left(\frac{\omega_0 \chi x'}{cf}\right)\exp(\mathrm{i}2\omega_0 t) \end{aligned} \qquad [21]$$

The frequency-difference process with an informationless waveform serves to reduce the carrier frequency of resultant waveform back to ω_0. The down-converted wave U_4 is SFT to the output plane, yielding:

$$U_{\mathrm{out}}(x'';t) = y\left(\frac{\alpha x''}{c}+t\right)w\left(\frac{ct}{\alpha L}\right)\exp(\mathrm{i}\omega_0 t_0) \qquad [22]$$

where $y(t) = s(t/\tau) \otimes m(-ct/\alpha\chi)$. As in the processing of ultrafast waveforms section above, the new ultrafast waveform $y(\cdot)$ scans along the output plane at a velocity of $-c/\alpha$ in the x-direction. The synthesized ultrafast waveform can propagate in freespace after an additional grating diffraction. The waveform information, in this case, consists of a convolution between the input temporal signal and a time-scaled and reversed version of the spatial information channel. Since the input temporal channel is typically a transform limited pulse, the output waveform carries the spatial information image, mapped to the time domain. In analogy to the imaging of ultrafast waveforms section, we call this technique space-to-time conversion. We have generated experimentally numerous waveforms that are controlled by a space domain image, or mask (flat-top waveforms, Figure 9, and pulse sequences of Figure 5 were generated by a cylindrical lens array in the spatial information channel).



Figure 9 Synthesized flat-top waveforms via space-to-time conversion utilizing a variable slit in the spatial information channel. Increasing the width of the slit results in broader square-shaped pulses in real-time. Solid line: 2 ps pulse, dot-dash line: ~1 ps pulse, dashed line: ~300 fs pulse.

Conclusions

To properly utilize ultrafast waveforms in scientific and advanced technology applications requires instantaneous techniques from generation to processing and imaging of the waveforms. We have studied the nonlinear wave-mixing approach within a spectral processing device, and demonstrated the ability to perform all of these tasks. The wave mixing was performed in a second-order nonlinear crystal, using three-wave mixing for detection and four-wave mixing for synthesis and processing of ultrafast waveforms. The three-wave mixing process results in a second-harmonic output image, suitable for acquisition by silicon-based CCD imagers. The four-wave mixing processes result in an output waveform of an identical carrier frequency, as typically required in processing and synthesis applications. The high nonlinear coefficient of $\chi^{(2)}$ crystals enabled us to demonstrate these techniques with ultrashort pulse energies ranging from nJ to mJ levels. Further advantages afforded by the techniques are expanded time windows and favorable phase matching.

This review of the instantaneous optical signal processing capabilities with optical nonlinearities and interaction with ultrafast waveforms introduced and demonstrated the basic signal processing capabilities to manipulate optical signals in amplitude and phase. The same techniques can be used and expanded upon to achieve different signal processing abilities, which are beyond the scope of this article.

See also

Coherent Transients: Ultrafast Studies of Semiconductors. **Nonlinear Optics, Basics:** Ultrafast and Intense-Field Nonlinear Optics. **Ultrafast Laser Techniques:** Pulse Characterization Techniques. **Ultrafast Technology:** Femtosecond Chemical Dynamics: Gas-Phase; Femtosecond Condensed Phase Spectroscopy: Structural Dynamics; Ultrafast Illumination and Processing.

Further Reading

Diels J-C and Rudolph W (1996) *Ultrashort Laser Pulse Phenomena: Fundamentals, Techniques, and Applications on a Femtosecond Time Scale*. San Diego: Academic Press.

Marom DM, Panasenko D, Sun P-C and Fainman Y (2000) Femtosecond-rate space-to-time conversion. *Journal of the Optical Society of America B* 17: 1759–1773.

Marom DM, Panasenko D, Sun P-C, Mazurenko YY and Fainman Y (2001) Real-time spatial-temporal signal processing with optical nonlinearities. *IEEE Journal of Selected Topics in Quantum Electronics* 7: 683–693.

Miller DR, Murnane MM, Scherer NF, Weiner AM (eds) (2003) *Ultrafast Phenomena XIII, Proceeding of the 13th International Conference*. Berlin: Springer-Verlag.

Weiner AM (1995) Femtosecond optical pulse shaping and processing. *Progress in Quantum Electronics* 19: 161–238.

Weiner AM and Kanan M (1998) Femtosecond pulse shaping for synthesis, processing, and time-to-space conversion of ultrafast optical waveforms. *IEEE Journal of Selected Topics in Quantum Electronics* 4: 317–331.

EARLY HISTORY OF QUANTUM ELECTRONICS

C H Townes, University of California, Berkeley, CA, USA

© 2005, C H Townes. Published by Elsevier Ltd. All rights reserved.

All the ideas essential to making a laser were known before 1930, but there was no operating laser before 1960. So why didn't the laser come sooner? There are several reasons. One important impediment to the laser invention was that a combination of ideas from quantum mechanics and from electrical engineering was needed, and these two fields were not well mixed in the early days. Another is that, while some physicists recognized that amplification could occur if there was a population inversion of states, they did not consider the coherence of such amplifications and did not recognize its importance or usefulness. It was just something that in principle could happen, but was not very interesting. What was required was a combination of physics and electrical engineering thinking and recognition of the coherence of such amplification. In addition the importance of such a development had to be visualized and recognized in a way that it led to very devoted work towards its achievement.

It is striking that lasers grew out of the study of microwave spectra of molecules, for which engineering and quantum mechanics were both important and which helped orient thinking in the appropriate direction. That this origin was not accidental is convincingly demonstrated by the fact that three independent ideas for amplification by stimulated emission were generated about 1950. They were from Joe Weber, at the University of Maryland, from Nikolai Basov and Alexander Prokhovov at the Soviet Academy, and myself at Columbia University. Weber primarily wanted to point out the possibility, but didn't try to do it. In addition, his numbers were a bit off and no practical system was suggested. Basov and Prokhovov actually worked towards microwave amplification using a beam of molecules, as did I.

That stimulated amplification was recognized early, but not thought through, is illustrated by the fact that Prof. Richard Tolman, a theoretical physicist, wrote a discussion in 1924 of the net absorption of light by molecules, pointing out in particular that induced emission counteracted absorption and noting that if there were more molecules in the upper than in the lower state there could be 'negative absorption'. But, he wrote, 'This would usually be very small'. The Russian physicist Vitaly Ginsburg wrote me, after the maser and laser had appeared, that his professor, S.M. Levi, had been well aware of such effects back in the 1930s and had told him 'create an overpopulation at higher atomic levels and you will obtain an amplifier; the whole trouble is that it is difficult to create a substantial overpopulation of levels'.

The German physicist F.G. Houtermans said to me that in 1932, when told by a colleague of an unusual light intensity in a gaseous discharge, he had thought it might be a 'photon avalanche', i.e. multiplication of photons by stimulated emission.

Another Russian physicist, V.A. Fabricant, wrote a thesis in 1939 in which he discussed absorption and emission of light radiation in a gas and looked for 'negative absorption', or amplification. He did not discuss coherence or a resonant cavity, and was not able to achieve any amplification so his work was quickly forgotten. None of these early mentions of stimulated emission proposed how to actually get amplification, that it would be useful, nor clearly noted its coherence. Tolman did, however, write in 1927 that, 'We should expect radiation induced by an external field to be coherent with the radiation associated with that field'. I know of no proposal to actually make use of such amplification, until those made by microwave spectroscopists in the early 1950s.

Another clear indicator that even in the 1950s physicists and engineers did not think amplification by stimulated emission was particularly interesting nor useful is that during the $2\frac{1}{2}$ years when Jim Gordon, Herb Zeiger, and I were working on trying to obtain microwave amplification (the maser), a large number of scientists visited my laboratory, saw what we were doing, but no one bothered to also try to obtain such amplification. After the maser worked, it hit the newspapers and then very quickly became a popular and intense field of interest for a number of physicists.

My own drive to produce oscillators by stimulated emission came from my strong interest in obtaining sources of waves shorter than the few millimeters wavelength which could be produced by electronic devices, in order to extend the high resolution study of molecular spectra to wavelengths shorter than microwaves, down into the far infrared. My students and I worked on several possible schemes for producing waves shorter than those produced by klystrons or magnetrons – frequency multiplication by nonlinearities, electronic beams passing over surfaces of solid materials with resonances, and anything else I could think of. None worked very well.

In early 1950, I was asked by the Office of Naval Research to form and chair a committee which would examine possible research towards obtaining wavelengths down to one millimeter and shorter. I chose outstanding scientists and engineers in a variety of fields which might touch on this problem. We met together, and visited many pertinent laboratories and individuals interested in such research. Nothing very promising seemed to turn up. But we wanted, of course, to at least provide a report summarizing the situation as we saw it. Our last meeting was April 26, 1951, in Washington, D.C. Worrying over our lack of success, I woke up early before the meeting. Breakfast was not ready, so I walked over to nearby Franklin Park, sat on a bench in front of beautiful blooming azaleas, and puzzled over why neither I nor the Committee had found any promising solutions.

I went over all the ideas I had had previously. Molecules, of course, can produce high frequencies. But I had previously concluded, I thought wisely and rigorously, that one could not obtain intense radiation from them because radiation intensity was a function of temperature, and the temperature could not be very high without destroying the molecules. Suddenly I realized that they did not need to have a temperature in the usual sense – they need not be in temperature equilibrium. There could be more molecules in an upper than a lower excitation state, which could in principle produce indefinitely intense radiation. I pulled a piece of paper out of my pocket and wrote down the equations and numbers for such a case, using a molecule beam sent into a resonant cavity and ammonia molecules with which I was very familiar. My equations said one could get enough excited molecules, low enough loss in a resonant cavity, and it would work! Why hadn't I thought of it before?!

Back at Columbia, where I worked, and about 4 months later, the graduate student Jim Gordon agreed to work on trying to obtain such an oscillator using a beam of ammonia. I assured him that if it didn't work he could modify the experiment to do interesting spectroscopy and thus complete a thesis. But we both thought he had a good chance of making it work. And a young post doc working with me, Herb Zeiger, joined the effort.

Actually, I had first thought of obtaining stimulated emission from a molecular beam back in 1948, but simply as a demonstration of physical principles rather than as a useful amplification. Also, about a year later a young post doc, J.W. Trischka, working on molecular beams with Professors Rabi and Kusch, had also thought of demonstrating stimulated emission. We talked about it together, and he decided it wasn't worthwhile just demonstrating the effect because it wouldn't really prove any new physics. Neither of us at that time had recognized the real point and the possibility of useful amplification, which is one of the reasons mentioned above that the idea was delayed as long as it was.

It is perhaps important to emphasize again and to illustrate how out-of-the-way the use of stimulated emission was at that time for physicists, and how distant stimulated emission was from engineers. While we were working on the ammonia beam maser, Prof. L.H. Thomas, an outstanding physicist known for the 'Thomas Effect', frequently would run into me in the hallway at Columbia University and say that I didn't understand, and that my proposed ammonia oscillator could not work. However, I never got a clear explanation from him of what it was I didn't understand. And after we had been working on the ammonia maser system for about 2 years (a more-or-less normal time for a student thesis project), the Physics Department Chairman, Prof. Polycarp Kusch, and the previous chairman, Prof. I.I. Rabi, came into my office to object. They were excellent physicists, both received Nobel Prizes, and both were experts on molecular beams. They sat down in my office and said 'Look, Charlie, that is not going to work. We know it won't work and you know it won't work. You are wasting departmental money, and must stop!' Other people had also questioned what I was doing, frequently in particular whether the stimulated radiation would be coherent. So I had already thought over the situation many times. I had full notes from the quantum mechanics course I took as a student back in 1938, and could derive from them a proof of coherence. I felt also that I knew the quantitative numbers, such as the molecular beam intensity and the possible 'Q', or loss, in the cavity resonator, very well. I was also by then an Associate Professor, and the department chairman could not fire me simply because of stupidity. I replied to Rabi and Kusch 'No, I believe it has a reasonable chance of working and I'm going to continue!' Annoyed, they stomped out of the room.

About 2 months after the Rabi/Kusch incident, Jim Gordon dashed into the classroom where I was lecturing and said loudly 'It's working!' Most of the class then went up to the lab to see the new device. Rabi and Kusch were not against me; even though they were outstanding physicists, they probably just didn't quite comprehend the device. A couple of months after its successful operation, Kusch more or less apologized by saying 'Well, I should have realized that you probably know more about what you are doing than I do.'

After the maser successfully operated, there were other incidences showing the lack of appropriate focus of physicists on stimulated emission. I was a friend of Aage Bohr, the son of Niels Bohr, and in that connection was visiting him in Denmark. Niels Bohr asked me what research I was presently doing, so I told him about our new oscillator, the maser, and its remarkably pure frequency. He looked at me and said 'Oh no, that's not possible. You must be misunderstanding something.' I emphasized again what it was really doing, but he still seemed not to believe it could function that way. I presumed he was thinking in terms of the uncertainty principle and the finite time of passage of a molecule through the cavity, though I never was quite sure just why he felt it impossible. A similar thing happened shortly after that at a cocktail party in Princeton, where John Von Neumann asked the same question – what was my research at the moment? After telling him about the maser oscillator and the purity of frequency he reacted very similarly 'Oh no,' he said, 'That can't be right. You must be misunderstanding something.' After arguing a little more, he left to get another drink. Fifteen minutes later he came back, saying 'Hey, you are right!' He had understood, and wanted to talk much more about the maser and of possibly using excited semiconductors. Only after his death did I learn from his notebooks that he had considered exciting electrons in semiconductors with neutrons from a reactor, and had written Edward Teller about whether some experiments might be done with this to obtain intense light. However, he had not considered coherence, and Teller was apparently not interested enough to respond, so the matter was dropped.

The above account reminds me a bit of the amusing comments of Arthur Clark on 'Change'. He writes:

'People go through four states before any revolutionary development:

1. It's nonsense, don't waste my time
2. It's interesting, but not important
3. I always said it was a good idea
4. I thought of it first'.

It's clear that the world of physics was thinking very little in the direction of masers or lasers, and that many preconceptions as well as lack of interest stood in the way. My own experience with engineering at Bell Telephone Labs during World War II, in designing radar and electronic systems, plus my intense interest in obtaining short-wave oscillators, were clearly important in bringing me to the right ideas.

As masers became very interesting to the physics community and the field grew rapidly, my engineering experiences continued to be of help. I was well acquainted with the theoretical examination of noise in vacuum tube amplifiers by various individuals at Bell Labs, and recognized that the maser could provide much more sensitive amplification than could common electronic amplifiers, where discrete electronic charges produce the basic noise. On sabbatical in France, I worked on electron spin masers with Jean Combrisson and Arnold Honig who had the appropriate equipment. And then in Japan, Koichi Shimoda, Hidetoshi Takahashi, and I wrote a theoretical paper on the basic quantum noise of maser (or laser) amplification. The theory showed that maser amplifiers of microwaves should be about 100 times more sensitive than the existing electronic ones.

After 2–3 years of maser experiments and development I felt I wanted to move on to the shorter wavelengths for which I had generated the maser idea. Although I had first tried the idea at microwave frequencies because that seemed the easiest way to test out the general idea and the result had been exciting, I still wanted those shorter wavelengths. I had not come up with any great ideas of just how to get to much shorter wavelengths, which is why I waited several years after the maser worked before moving on. However, in 1957, 3 years after the first successful operation of the maser, I decided it was high time to simply figure out what was the best way I could imagine to move on into the infrared region and do it. A number of physicists had concluded that of course one couldn't make masers work at much shorter wavelengths, certainly not in the visible region, because spontaneous emission becomes so much faster as the wavelength is shortened and adequate inversion of population was not practical. But that was intuition, not quantitative science. As I wrote down equations for what might be done to move towards shorter wavelengths using a model of atomic or molecular excitation by radiation and a reasonably high Q resonator, it became clear that it was quite practical to move on even into the visible region. That was exciting! Why hadn't I, or someone else, looked at it carefully and quantitatively before that time?

I was at the time consulting at Bell Labs, with the assignment to spend a day there every 2 weeks and just talk with the Lab's scientific personnel. Since my former post doc and now brother-in-law Arthur Schawlow was then at Bell Labs, I of course talked with him. On telling him of my ideas for an 'optical maser', using a resonant cavity and excitation of atoms with optical radiation, he said he too was interested in that, and we decided to work together to optimize a system. It was Art who then suggested use of a Fabry–Perot resonator rather than the cavity with large holes I had used for a model, and that was an excellent addition. Why I did not think of that is a mystery, but Art had done his thesis at the University of Toronto in Fabry–Perot spectroscopy, and that might have been why the thought came to him.

Since Art Schawlow was participating, I decided the patent for the new 'optical maser' should belong to the Bell Labs (I already claimed ownership of the basic maser patent, which covered all wavelengths). Hence we recognized that the new idea must be kept confidential until Bell Labs lawyers had worked out and applied for an appropriate patent. This delay in public information sheds some additional light on how the scientific and technical world was thinking at the time. I had written down my original ideas for an 'optical maser' in my notebook and had it witnessed by my student Joe Giordmaine at Columbia University. I had also talked with a Columbia student Gordon Gould because he had been doing research with an intense light source and I wanted to know how much intensity he had in order to be sure I could get enough excited atoms and provide an oscillator at these short wavelengths. Except for these two persons, neither Art Schawlow nor I told anyone outside of Bell Labs about the 'optical maser', or laser idea until after Bell Labs had properly prepared its patent, which was about 11 months after my first notebook entry. For that entire time, no one has produced a record of any thoughts about extending the maser to optical wavelengths except Gordon Gould, who entered some ideas in his notebook about 1 month after I talked with him about the possibility of an optical maser, and 2 months after my original notebook entry. His notes were later to be the source of a long patent case.

The striking observation is that no one outside of Bell Labs except Gordon Gould, to whom I had explained my ideas, seems to have written or noted down anything about extending masers to these shorter wavelengths during the 11 months from my recognition that it could well be done until after the Schawlow and Townes paper on how to do it became available. After that there was considerable excitement and a number of ideas.

It is also noteworthy that, because of low general interest and competition, I did not publish a paper on how a maser might be made, but waited for publication until we demonstrated its operation, about 3 years after the idea had arrived. But after the maser worked the field became exciting and competitive. Hence, Schawlow and I thought we surely should publish a theoretical paper establishing the idea before taking the time to make a laser work. And indeed, there was much competition to build the first laser.

I myself helped a couple of my graduate students start work on trying to build an 'optical maser' or laser. But at about that time (1958), I was urged to undertake a job in Washington as Vice President and Director of Research of the Institute for Defense Analysis, an organization put together largely by the presidents of several universities to try to help advise the government on matters of science and technology. Sputnik had gone up the year before, and everyone was worried about the position of the U.S. with respect to Communist Russia, which seemed to be ahead particularly in some areas important to defense. I decided I should try to help, and accepted a two-year appointment in Washington. I recognized that this seriously distracted my attention from developing a laser quickly, but knew there were many others working towards lasers and so such devices would certainly be developed and our doing it just at Columbia University was neither critically important nor highly probable.

The field of masers and 'optical masers' or lasers was becoming so exciting and a bit scrambled that The Office of Naval Research asked me if I would organize a meeting on the subject. I did, with the help of a committee of many distinguished people in the field or closely related science and technology. And it was in a meeting of the Committee that we christened the field with the name 'Quantum Electronics'. This first international meeting on the subject was at Shawanga Lodge in New York State in September 1959. It made an occasion for the Russians Basov and Prokhorov to visit the United States (and my lab and home), and was about 6 months before Ted Maiman made the first working laser. There were many interesting discussions of masers and their coming operation at optical wavelengths.

It is significant to note that, while the maser grew out of basic research in universities (with Russian work at the Russian Academy) and industry had little to do with early masers, all the first lasers were made in industrial laboratories. This illustrates the sociology and the strengths and weaknesses of industrial and of academic laboratories. While masers (and from them lasers) originated from research on microwave spectroscopy of molecules, industrial laboratories believed the field of microwave spectroscopy had little to offer in the way of commercial results. Because of equipment available and the interest of physicists in industry, the field was initiated and pursued immediately after World War II in commercial laboratories – by myself at Bell Labs, my friends at the RCA Labs, at Westinghouse, and at General Electric. For lack of interest in industry, such work was soon shut down, except at Bell Labs, and it moved to universities. Bell Labs generously allowed me to continue such work, although they wanted me to do some 'more useful' engineering. Once the field had obvious commercial possibilities, commercial laboratories began to support it well and the clear importance of masers and lasers made industry very interested. Really interested industry can more easily put strong new resources and push harder on a field than can academic laboratories, where money has to be granted and professors have a variety of other assignments. The first laser was made to work, of course, by Ted Maiman at Hughes Research Laboratories. Ted had been a student of Willis Lamb at Stanford, and there worked on radio spectroscopy. The second type of laser, rather similar to Maiman's but using a different material, was made to work at the General Electric Laboratories by Peter Sorokin and Mirek Stevenson. Sorokin had been a student of Bloembergen at Harvard in microwave or radio spectroscopy and Stevenson was one of my students in microwave spectroscopy at Columbia University. The next type of laser, and one I particularly admire, was made by Ali Javan, William Bennett, and Don Herriott. Javan had been a student with me in microwave spectroscopy at Columbia University, Bill Bennett a student in the molecular beam group at Columbia working on radio spectroscopy, and Don Harriott was an optics specialist. All of these originators, with the exception of Herriott, had been working at universities in the field which originated the idea and were recently hired by industry. The next important laser, involving semiconductors, was invented by Robert Hall and collaborators at General Electric Labs. Note that every one of these early lasers was created in industry.

After the first laser was operated, my own students at Columbia quickly turned from trying to make a laser to using lasers to explore more physics, the normal university function. And I am delighted that masers and lasers have provided such excellent tools for research, as well as for commercial and medical applications.

After a few years of exploring new physics with lasers, I decided that since there were many excellent scientists doing such work, I should move into fields which it seemed to me were being relatively neglected. I moved to the University of California at Berkeley to look for molecules in interstellar space by microwave spectroscopy, and to do infrared astronomy. Very soon after initiating work at Berkeley, one of my students, Albert Cheung, not only discovered the first polyatomic molecules in space, he found powerful water masers. A while before our discovery of water and identification of its radiation as due to maser action, it had been deduced that some microwave radiation of OH must be due to maser action. And since then, many, many masers due to a wide variety of molecules have been found in astronomical sources as well as a few powerful lasers. Since deviations from thermal equilibrium are common in the very thin gases excited by powerful sources in space, we should have expected this, but didn't. And these masers in space could have been easily detected with radio technology available back in the 1930s if anyone had searched the microwave spectrum carefully.

Clearly, masers and lasers could have been discovered and used much sooner than they actually were. We simply were neither thinking nor looking in the right directions. And this raises the natural question – what important and more-or-less obvious ideas are we missing now because of our lack of imaginative exploration?

Further Reading

Basov N and Prokhorov A (1954) Application of molecular beams to radio spectroscopic studies of rotation spectra of molecules. *J. Experimental. Theoretical Physics U.S.S.R.* 27: 431–438.

Bloembergen N (1956) Proposal for a new type of solid state maser. *Physical Review* 104: 324–327.

Cheung A, Rank D, Townes C, Thornton D and Welch J (1969) Detection of water in interstellar regions by its microwave radiation. *Nature* 121: 626–628.

Combrisson J, Honig A and Townes C (1956) Utilization de la resonance de spins electroniques pour realiser un oscillateur ou un amplificateur en hyperfrequencies. *Comptes Rendues* 242: 2451–2453.

Gordon J, Zeiger H and Townes C (1954) Molecular microwave oscillator and new hyperfine spectrum of NH_3. *The Physical Review* 95: 282–284.

Hall R, Fenner G, Kingsley G, Soltys J and Carlson R (1962) Coherent light emission from GaAs junction. *Physical Review Letters* 9: 366–368.

Javan A, Bennett W and Herriot D (1961) Population inversion and continuous optical maser oscillation in a gas discharge containing a He–Ne mixture. *Physical Review Letters* 6: 106–110.

Knowles S, Mayer C, Cheung A, Rank D and Townes C (1969) Spectra, variability, size, and polarization of H_2O microwave emission sources in the galaxy. *Science* 163: 1055–1057.

Maiman T (1960) Stimulated optical radiation in ruby. *Nature* 187: 493–494.

Perkins F, Gold T and Salpeter E (1966) Maser action in interstellar OH. *Ap. J.* 145: 361–366.

Schawlow A and Townes C (1958) Infrared and optical masers. *Physical Review* 112: 1940–1949.

Shimoda K, Takahashi H and Townes C (1957) Fluctuations in amplification of quanta with application to maser amplifiers. *Journal of the Physical Society of Japan* 12: 686–700.

Sorokin P and Stevenson M (1960) Stimulated infrared emission from trivalent uranium. *Physical Review Letters* 5: 557–559.

Tolman R (1924) Weak quantization. *The Physical Review* 24: 287–295.

Tolman R (1927) Statistical mechanics with applications to physics and chemistry. The Chemical Catalog Co., New York, pp. 169.

Weber J (1953) Amplification of microwave radiation by substances not in thermal equilibrium. *Trans. Inst. Radio Engineers Professional Group on Electron Devices* 3: 1–4.

LET THERE BE COHERENT LIGHT: THE DISCOVERY OF THE LASER

T H Maiman, Vancouver, BC, Canada

© 2005, T H Maiman. Published by Elsevier Ltd. All rights reserved.

Editor's Note

The discovery of the first laser was a remarkable culmination of human creativity and ingenuity. However the achievement was finally made by one individual young scientist, Theodore Maiman, working independently of the mainstream and without the benefit of strong government or private financial support. With persuasive arguments, he convinced his management at the Hughes Research Laboratories to allow him to continue his work, albeit with limited resources. And then, working alone with his assistant he saw the light that now illuminates the world of laser science and engineering. This is the story of how thinking outside the box created a new field of science, whose developing technology has advanced the state of medicine and engineering and the quality of life in general.

Introduction

I am frequently asked how it was that I discovered the laser. Many assume that the concept evolved from some sudden, inspirational thought. It didn't happen that way.

It is dramatic and exciting to have a scientific discovery emerge from a dream or a vision that comes out of nowhere, but it seldom does. In reality, almost all scientific discoveries come from building on other, prior, scientific developments.

So it was with the laser. In 1916, Albert Einstein laid the foundation and conceived the basic underlying principles on which lasers are based. He formulated and explained the relations that govern the way that atoms and molecules absorb and emit radiation. He introduced the key concept of stimulated emission. Then, in the 1920s, physicists C.H. Füchtbauer and Rudolph Ladenburg added formulations that used the Einstein theory to go further, and tie the absorption of light in a material medium to the fundamental properties of its constituent atoms. But it was the Russian physicist A.V. Fabricant who first had the vision to propose the concept of a laser in 1940.

Unlike the Sun and other incoherent light sources, the laser produces light of one precise color. Its waves are emitted in phase with each other, and its radiation can be efficiently focused to a precise spot. In short, the laser produces coherent light, with the properties we were already used to with radio, television and microwave sources.

Fabricant specified the conditions needed for amplification of light via stimulated emission. He appreciated the concept of an inverted population and the concept of coupling such an inverted population medium to a resonant structure (resonator). He proposed using a gaseous electrical discharge to achieve laser action as one possibility. Later, he proposed the use of a helium discharge lamp to optically pump the gaseous form of cesium.

Scientists Purcell and Pound were the first to report evidence of net stimulated emission in 1951. Their observation, in the radio part of the spectrum, was a by-product of their pioneering developments in the techniques of nuclear induction, the foundation for magnetic resonance imaging.

The first achievement of a working device that utilized stimulated emission as its operating principle was a microwave oscillator/amplifier. That device used a beam of ammonia molecules as the working medium. The design details were worked out independently by groups at the Lebedev Institute in the Soviet Union and Columbia University in the USA. The device was dubbed a *maser*, which is an acronym for *microwave amplification by stimulated emission of radiation*.

In 1955, the year after I was awarded my Ph.D., I joined the Hughes Research Laboratory in Culver City, California. One of my major assignments was to head a project developing a miniature, liquid-nitrogen ruby maser for the US Army Signal Corps.

Race to the Light

Before starting work on the maser I had begun to germinate some ideas about the possibility of a laser. My concept so far was to try to use a solid material for the lasing medium, and to fabricate the potential laser material into a rod shape. In microwave thinking this configuration would be called a *dielectric wave-guide*. In optics it is known as a *light pipe*.

Abridged from "The Laser Odyssey" by Theodore H. Maiman. Copyright © 2000 Theodore H. Maiman. Reproduced with the permission of the author and Laser Press, Blaine, WA, USA.

I planned to put mirrors on each end of the rod to form a resonator.

Despite the advances in physics it represents, the maser does not in any way extend the coherent electromagnetic spectrum. Furthermore, its use as an amplifier turned out to be impractical because cryogenic temperatures were required for proper operation. There was strong motivation to push the frontiers of coherent electromagnetic radiation to higher frequencies, principally the promise of higher energies and greater concentrations. The reduction in wavelength from microwave to visible is a factor of about 10^4. This would lead to a consequent 10^4-fold reduction in the minimum achievable focal size, and a 10^8-fold increase in energy concentration delivered by the laser.

Work on the maser project therefore proved something of a distraction, and it was not until August 1959 that I was able to devote full effort to the consideration and analysis of my concepts for a laser.

Why would I be willing to enter such a race? There was rather formidable global competition already in play, well-funded and very competently manned. The answer lies in my knowledge of the proposals that had been floated about. Generally, the scientists who pursued these notions were not particularly secretive about what they were working on. They published and gave talks at conferences. On the whole, however, I found that the authors and conference presenters were only offering vague proposals. To be sure, this served as an exchange of information and stimulated ideas. But it didn't appear to me that anyone was close to the answer. In short, no viable laser concept was yet in existence.

As I look back, I was a little brash. I would be thrusting myself, in a sense, into a technological Olympics. The competition was of the best quality and of international scope. But my competitive spirit won out. The challenge of working in the top league of such an exciting project, that had so many questions and problems to resolve, was very compelling to me.

We know *now* that many kinds of lasers can be made. But back then, in 1959, we didn't know. We didn't even know with any confidence if it was really possible to make a laser at all. My strategy was to limit myself to potential solutions to the making of a laser that did not have appreciable distractions in the design. That way I could focus strictly on just the laser problem itself.

For various reasons I was reluctant to work on alkali-vapor or gas discharge systems. I chose to work with solid-state crystals. The main appeal that solids held for me was simplicity. By that, I mean simple in analysis and understanding, and simple in device conception.

In contrast to a gas discharge, the energy level diagram in an appropriate crystal is very limited. There are relatively few possibilities for the energy states, and by and large, the pertinent parameters for a potential laser candidate are amenable to a combination of calculations and relatively straightforward direct measurements.

Another advantage, in principle, to a solid crystal is its relatively high gain coefficient. By that, I mean the amplification in a given length of material is of reasonable proportions. This meant that the laser medium could be relatively small in size and short in extent, and I would not have the problem of developing or depending on the use of special mirrors. Indeed, my first laser used a crystal that was only 2 cm long.

I was also intrigued with the concept of a solid medium since I would not have to deal with vacuum pumps, impurity problems and gas handling apparatus, or complex mirror mechanisms. I could put simple silver mirror coatings directly on the crystal as I had done with my small ruby maser. In principle, a solid crystal laser could be designed to be very simple, compact and rugged.

My first choice to study and contemplate was that of a ruby crystal. Ruby is the result when a water-clear cast of aluminum oxide is doped with a small amount of chromium oxide impurity. It is the chromium that is responsible for the red color. The rubies used for devices are usually not natural gemstones, which have a chromium impurity level of about 0.5%. The chromium concentration in device rubies is around ten times less than this, and hence they display a lighter red color than gemstone ruby and are referred to as *pink ruby*.

Why choose ruby as a potential laser candidate? Most importantly, I was quite familiar with and fascinated by the interesting optical properties of the crystal. Ruby is a fluorescent mineral; if ultraviolet light is shone on a ruby, it will glow with deep red fluorescence. Furthermore, ruby also gives off a red glow when either blue or green light is shone upon it. It is these blue and green absorption bands that give ruby its red color. When a green photon impinges on and is absorbed by the ruby, a chromium impurity ion is raised from its ground state into a broad, excited band. Although the chromium ion has the possibility of radiating by spontaneous emission from that excited level, another process comes into play. The competing process uses the thermal vibrations of the crystal lattice to interact with the excited ion and deposit most of the excitation energy to another slightly lower excited level of the ruby chromium where it stays for a while. This latter process is much more probable and dominates.

The energy from this third level is radiated as spontaneous incoherent emission. This spontaneous emission is made up of red photons and is the observed fluorescence. The level where the fluorescence emanates is sometimes called a metastable level, since the chromium ions linger in that energy state for a comparatively long time before they radiate red photons.

I developed a model that could be mathematically analyzed and I set up kinetic equations to take into account the various mechanisms taking place in the fluorescent process. I also set up simple intuitive criteria for establishing the condition for laser action. This model and these equations have subsequently become a standard way for others to analyze crystal lasers.

I was able to determine which material parameters were important and relevant to a laser by getting the solution to the equations describing the model. Using known and estimated values for the pertinent parameters in ruby, I found that ruby would require a very bright pump lamp to excite the crystal sufficiently to allow laser action to take place. The brightness of a lamp is an important parameter for lasers. It is a measure not of the total power radiated by the lamp, but rather the power per unit area.

Obstacles and Solutions

Ruby has many desirable qualities. It is a very stable, very rugged crystal to work with. It has some broad pumping bands that make it helpful to get a reasonable energy transfer from an incoherent pumping lamp, and compared to some other crystals I considered (e.g., gadolinium-doped crystals), a working ruby laser would produce visible light.

However, there was some uncertainty over the crystal's measured quantum efficiency. The quantum efficiency for a fluorescent crystal is the number of fluorescent photons emitted, divided by the number of pumping photons. In the case of ruby, this is the number of red photons radiated out compared to the number of green photons absorbed. A report in November 1959 had suggested that ruby's quantum efficiency was only 1%. This would effectively mean that it would be impossible for ruby to achieve laser action. However, I was able to make my own measurements of ruby's fluorescent efficiency, and these showed that it was nearer 75%.

I now had enough information that I could proceed to work out an actual laser design. But how would I pump the ruby? What would be the ruby's shape and size?

I knew that I needed a very bright lamp. Among the brightest around was a high-pressure mercury arc lamp manufactured by General Electric. In addition to being one of the brightest available laboratory lamps, it had the advantage of radiating most of its energy in the green and blue-violet parts of the spectrum. This was a good match to what I needed for the ruby.

I drew up a paper design with the mercury arc lamp at the focus of an elliptic cylinder. A small ruby rod was to be mounted on the other focus of the elliptic cylinder. It is a property of an elliptically shaped reflector that a point of light placed at one focus of the ellipse will be imaged at the other focus. The elliptic cylinder that I had in mind would be highly polished on its inner surface to a mirror finish.

But I had a problem. My paper analysis of the design showed that although it should work, it would only do so by a slim margin. I studied the design in more detail, looking for ways to optimize and improve it, but I couldn't convince myself that it was anything but marginal.

I stewed over the problem at hand. I started to think about other ways to look at the problem. I was frustrated: I felt that, on the one hand I was very close to an answer, but on the other hand it was eluding me.

I went back to my analytical model. I pondered my options and decided to put the pumping lamp requirement for the ruby in a different form. I calculated the equivalent black-body temperature of a suitable pumping lamp. The temperature I calculated to have enough brightness capable of driving a ruby into laser action was close to 5000 K. By contrast an ordinary tungsten light bulb has a brightness temperature of about 2800 K.

Once I put the pumping requirement in terms of brightness temperature, I began to think in a different way. I remembered reading an article about photographic strobe lamps, a camera's flash mechanism. The article said that strobe lamps could reach brightness temperatures of 8000 K or more.

I now had my 'aha'!

Most scientists had been thinking in terms of a continuous laser, and that was certainly my thinking to start with. But why should I place such restrictions on myself? At this juncture I was only trying to demonstrate that coherent light could be made at all. Besides, a pulsed source is not only acceptable in many applications, it may even be preferable.

I went back to my analytical model, modified the equations to account for a pulsed light source, and then analyzed the results to guide me in the actual laser design. I had already determined that the most important parameter of the light source would be its brightness, that is, a lamp that maximized the power per unit area into the useful pump bands of the ruby.

My calculations also instructed me that this lamp brightness requirement is largely independent of the ruby crystal dimensions and its chromium concentration over a reasonably wide range. The model assumption was that of a three-level system (appropriate to ruby) where the lower laser-energy level is the ground state.

Next, I scoured every flashlamp catalogue that I could find. I calculated the luminous intensity for promising candidates and found that the highest intensity came from three General Electric spiral-shaped flashlamps. My calculations showed that I would have an adequate margin of safety, in terms of excess brightness intensity for the laser, of some two to three times, even with the smallest lamp.

Let there be 'Coherent' Light

Based on my most current calculations and measurements, I was becoming optimistic about the possibility of creating a laser. The tension was building and I started to have dreams that I actually did it. It was a wildly exciting thought!

Still, I was worried that I might be missing something. Instead of proceeding directly to the actual design, I decided to do an experiment that would check the validity of my model.

I made up a cube of pink ruby with each dimension equal to one centimeter in length, about the size and shape of a sugar cube. The crystal axis was perpendicular to one set of faces of the cube. I then placed the cube between two parallel plates, thus forming a microwave cavity. The cavity resonance was designed to be equal to the natural ground-state splitting of the ruby. These are the ground-state sublevels used in a ruby maser.

The purpose of this arrangement and the subsequent experiment was to monitor the ground state population of the ruby. My calculations had shown that it would be possible to substantially reduce the ruby ground state ion population necessary to make a laser, but I wanted tangible evidence to confirm and justify my optimism.

I was still harassed by the thought that no one had yet ever made a laser, although by now several teams of scientists had been diligently working away for nearly two years. Was there a fundamental insurmountable problem that I had missed?

I proceeded with the experiment using the ruby cube. As described above, one set of parallel faces of the cube served as the resonant microwave cavity. I connected one of the open (second set of) faces of the cube to one end of a polished quartz rod called a light pipe. The other end of the light pipe was connected to the flashlamp. The third set of faces of the cube was used to probe with selected wavelengths of light. I used the 'loading' on the parallel-plate microwave cavity to monitor the ground state population of the ruby, making use of the microwave properties of ruby that I had learned from my work on the ruby maser.

When I flashed the lamp, the cavity loading did indeed change. It decreased because, as expected, there were fewer chromium ions in the ground state. More important, the *magnitude* of the population change, 3%, was very close to the value I had predicted from my analysis of the experimental parameters. This was an extremely gratifying result since it gave further confirmation to my model and its analysis.

Now I was getting more excited. Since I couldn't think of anything else to check, it was time to proceed with the definitive design of a laser.

The Laser Design

My first thought was to use some modification of the elliptic-cylinder configuration that I considered for the mercury arc lamp as discussed in the previous section. The problem was, I would need a straight, rod-shaped flashlamp, but the straight lamps in the catalogues that I checked didn't have high enough intensity. Therefore, I resorted to a different design and stuck with what was available – the spiral-shaped lamps. I didn't want to get sidetracked at this time into the development of a special lamp.

It dawned on me that I would not have to devise a focusing arrangement, since the brightness of the radiation that is attainable at the focus of a mirror or lens can only approach, but not exceed, the brightness of the source. So, why not just place the crystal in close proximity to the lamp? That is, why not place the crystal *inside* the lamp helix?

To help gather the light, I placed a polished aluminum cylinder around the outside of the spiral. To fit the lamp, I used a pink ruby crystal in the shape of a right circular cylinder rod, about 1 × 2 cm. The ends of the ruby cylinder were polished flat, parallel to each other and perpendicular to the axis of the cylinder. For mirrors, I used evaporated silver.

I chose silver for the mirrors because it has the highest reflectivity of any metal at the deep red ruby laser wavelength. However, silver tarnishes quickly, and so with time, the thin output layer will change its transmission characteristics; it is not stable. To solve this problem, I had a thick layer of silver evaporated on both ends of the crystal and I scraped a tiny hole in the coating at one end. The laser beam would emanate from that coupling hole.

The Crucial Test

As I neared completion of my laser design, Bob Hellwarth, one of my colleagues in the Atomic Physics Department, asked, 'How will you know if it's working?'

At first, I was concerned that if I were stuck with a ruby crystal that deviated too much from optical perfection, these imperfections could prevent measurable laser behavior.

To get a better understanding of the processes, I elaborated on my existing analysis to account for an imperfect crystal. I found that if I were able to drive the ruby crystal reasonably far above the point of inverted population, or laser threshold, that I would see very substantial evidence of an inverted population and impressive laser behavior even with a poor crystal.

Just exactly what would I see?

I planned to monitor the red light emitted from the ruby through the hole in the output silver coating and expected to observe three kinds of laser behavior evidence: a reduction in the decay time of the fluorescent level; the bunching of the radiation into a beam; and a significant reduction of the spectral width of the red light.

The Laser Process

Laser action can be understood by following through the operational details in the above-mentioned ruby laser design. The process starts when the ruby crystal is excited by the flashlamp and chromium ions are excited into the metastable fluorescent level. The ions lose energy by radiating randomly red photons. This is the familiar red fluorescence (spontaneous radiation).

When the excitation level is great enough, that revered 'inverted population' condition is reached. In that case, more chromium ions are in the ruby's metastable upper fluorescent level than are in the ground state. Therefore, chromium ions can radiate by *stimulated* emission as well as by the normal spontaneous emission process.

Because the metastable level now empties much faster than it normally would, the fluorescent lifetime is reduced. That decreased lifetime can be observed by monitoring the red ruby glow with a photoelectric cell connected to an oscilloscope when the ruby is flashlamp-excited.

When the ruby is in the inverted population condition, as explained previously, it becomes an amplifier. The red photons are amplified as they progress through the crystal.

An important selection process starts to take place. The red photons are initially emitted in random directions. But the fluorescent photons that happen to be radiated at large angles to the mechanical axis of the ruby cylinder are lost through the sides of the crystal. On the other hand, photons radiated along the crystal axis, or at small angles with respect to the crystal axis, are in effect, trapped. They are reflected when they strike either one of the end mirrors and move back and forth through the crystal. As these axial photons move through the ruby they are amplified and consequently generate more photons in the same direction. They quickly become the dominant stimulated radiation from the excited metastable level.

Keep in mind that photons moving through the crystal are responsible for the stimulated emission. The axial photons pick up a following and march down that crystal axis. Consequently, the photons that emerge from the coupling hole in the output silver mirror are concentrated in a direction along, or nearly along, the crystal axis.

The red ruby fluorescent (spontaneous) emission extends over a distribution of frequencies in a curve that resembles a bell shape. The fluorescent photons are most concentrated at the center of that curve. When the inverted population condition exists, the top of the curve has the highest amplification. The consequence is (as with the discussion of beam angle) that photons near the center of the distribution are favored, since it is these photons that get amplified most in the back and forth transits, through the crystal from the multiple mirror reflections. It is this last process that explains why the frequency distribution, the linewidth of a laser, is so small.

I planned to vary the excitation to the flashlamp. In doing so, as explained above, I would expect to see a reduction of the fluorescent lifetime giving evidence of stimulated emission. As I varied the ruby excitation level, the fluorescent intensity should increase proportionately, as long as I was below threshold. But, when above threshold, small increases in excitation should make much bigger changes in the output since the detector and monochromator combination are more responsive to the smaller beam and narrower linewidth.

Do it!

It was the afternoon of May 16, 1960; it was time to confirm or deny all the fears of why 'ruby can't work' or why 'lasers can't be made to work.' No more new calculations, no more diversionary experiments. This was the moment of truth!

The laser head was mounted on a workbench. The flashlamp was connected to the power supply. The trigger electrode was connected to the spark coil (the mechanism that initiates the flash from the strobe lamp). The light output from the coupling hole in the end of the ruby was directed through the monochromator to a photomultiplier tube. The electrical signal from the photomultiplier was connected to an oscilloscope.

Irnee D'Haenens, my laboratory assistant, and I were the only ones performing and observing the experiment. We first took a test shot so that we could adjust the monitoring equipment. We turned the power supply up to about 500 volts. We fired the flashtube. Indeed, we observed a trace on the oscilloscope!

The trace was a recording of the red ruby fluorescence. The decay in the trace was about three milliseconds, the lifetime of the upper possible laser level. We made the appropriate adjustments to optimize the monitor display.

We continued. We progressively increased the supply voltage, each time monitoring and recording the light output trace. As we did so, the peak output increased proportionately to the energy input, the decay time remained the same. So far, so good.

But, when we got past 950 volts on the power supply, everything changed! The output trace started to shoot up in peak intensity and the initial decay time rapidly decreased.

Voilà. This was it! The laser was born!

The Light Fantastic

When Irnee and I observed the first laser go into action, Irnee was smiling and jumping up and down with glee. I was numb and emotionally drained from all the tension and excitement.

Imagine: in the 10 years prior to the laser, the coherent electromagnetic spectrum had been extended by perhaps a factor of five. Now, with the advent of the laser, there was a quantum jump in that spectrum of ten thousand!

The significance of my historic accomplishment didn't sink in right away. I'm not sure that it has yet.

THE HELIUM–NEON LASER

A Javan, Massachusetts Institute of Technology, Cambridge, MA, USA

© 2005, A Javan. Published by Elsevier Ltd. All rights reserved.

> The date, twelve of December nineteen sixty, and the time, 4:20 PM, are the date and the time of an event that triggered such an imortant segment of what has now evolved in modern optics. Here is how:

It had snowed heavily on that day. The laboratory at Murray Hill, New Jersey, the Bell Telephone Laboratory, BTL, had been closed at 4. What occurred was a triumph of our depth of understanding of the atomic spectra, the physics of the inter-atom collisions and electron impacts and exchange effects, the fascinating sequence of what takes place in a *gas discharge plasma* when the discharge is switched on. The triumph was also that of the art in spectroscopy, this time that of the colorful glow of a gas discharge plasma in a controlled mixture of helium and neon. Performing the spectroscopy, one could *effectively* watch and follow a set of fascinating physics effects in the discharge plasma, that would lead to an *inversion* to set-in in a specific transition between a high-lying pair of energy levels in neon, by the now well-known transition at 1.15 μm wavelength in neon. Helium atoms in a metastable state in the discharge plasma played the key role.

On that day: The laser had already been de-gassed for 5 days and nights at 600 °C under the high vacuum, to drive off the impurities prior to introducing the gas mixture in the laser-plasma quartz tubing and sealing it off. We had a way to optimize the mixture, at the exact mixture ratio for the optimum inversion and the laser gain at the 1.15 μm neon transition wavelength. The laser design had a *daring* interferometer length *one meter long*. Why *daring* at *one meter long*, I will have a chance to explain why below. The laser-mirrors at each end of the one-meter-long interferometer were situated internally in the laser, exposed to the gas mixture. Two fine micrometers at each end of the laser provided the fine control for the laser–mirror alignment control externally.

To convey the scene, we had known already, that the inversion and the laser gain at the 1.15 μm neon transition will be *higher* in the discharge '*afterglow*', the afterglow following *rapidly switching-off the discharge*. The inversion and the laser gain at the 1.15 μm wavelength, we knew, would last for as long as a millisecond in the afterglow. Certain that the inversion and the gain will be higher in the afterglow, we had set-up the electronics to switch on the discharge for about 10 milliseconds, and switching it off fast at a one microsecond switch-off time, and leaving it off for the same 10 milliseconds time interval, and repeating it at a low rep-rate, about 20 times a second on that day. Expecting that while searching for the laser signal, the laser will first break into oscillation in the afterglow where the laser-gain will be higher, knowing that pulling it into the glow afterward will be easy.

With me on that day I had two of the three good people who worked with me on the experiment. One of the two, Donald Herriott, was about to miss his car pool. He had his hand at the time on the laser–mirror tuning-alignment, the fine micrometer at one end of the laser interferometer on his side. I had my back towards the oscilloscope that would display the laser signal, aligning the detection system. My journey had begun over two years previously. I was *certain* on that day, and at that time, that possibly right then, or no later than hours later or by midnight, the moment would come for me and others that I had with me, to witness the onset of the event sought after so hard. And then … .

I had my back towards Don Herriott, urging him to stay a bit longer. I heard Don's voice, saying '*What is that*?'. I turned and looked. The laser signals in the discharge afterglow on the oscilloscope screen, synchronized to the gas discharge rep rate. I reached the laser interferometer fine-tuning micrometer on my end … a gentle tuning, in a mere few seconds time, optimized the afterglow signal, and then pulled the laser signal right into the glow. I loudly called on 'Ed' to switch on to CW. He, Edward Ballick, jumped over the equipment and the electronics on the floor in the lab, reached the switching electronics, switched it on to CW:

> The laser signal on the oscilloscope … switched to CW … a coherent light beam … CW … continuous … and at a degree of coherence … that as it proved later and I know then … to the limits that the laws of nature will permit. I looked at my watch, 4:20 PM.

The year 1960 was the beginning. Some months earlier, in the summer of that year, Theodore Maiman at Hughes Laboratories, in Malibu, CA, succeeded to operate an optically pumped laser, operating in short-duration laser pulses, the Ruby laser at 0.694 μm. That approach to the laser differed fundamentally from the discharge plasma approach. The two were different inventions and served different purposes. One, the *optically pumped*, converts the *optical energy* in the pump, to the laser light output. The other, *electrically pumped,* converts the *electrical energy* in the *electrical current* that excites the laser plasma, to the laser light output. The rest on how things evolved is history.

The Scene Before Lasers

Before lasers, optics had long passed its peaks. The last words had been written by Born and Wolf in 1957, in an impressive volume on Physical Optics. When I went through my graduate studies at Columbia University in the early fifties, there were no graduate courses offered in optics. The subject was dealt with incidentally in courses in electricity and magnetism. Action was all on the microwaves at the time. Optical spectroscopy had reached its peaks much earlier yet, before World War II. Condon and Shortly had written the last words on Theory of Atomic Spectra in 1935, amazingly, as it seems, in *hardly a decade* after the discoveries in quantum mechanics. As events had it, optics gave way to the microwaves after the war, and optical spectroscopy to the RF and microwave spectroscopy – and all this, a result of the discoveries in Radar at the microwave frequencies in World War II.

We owed everything we knew of the atomic spectra to the *gas discharges* used as spectroscopic light sources at the time, from the high-resolution spectra of the hydrogen atoms at one end of the periodic table, to that of the trans-uranium elements on the other. We need not be reminded, everyone knows, how much we owed then and do now, to the high-resolution spectra of the hydrogen atoms, all because of the early hydrogen discharge light sources and then at the beginning, what led to the discovery of the quantum mechanics, and the wave nature of the atoms. The excitement that followed has remained unparalleled in physics since. Within hardly a decade after as a result, the cleverly designed spectroscopic gas-discharge sources, of different makes and designs, exhaustively revealed every feature predicted by the quantum mechanics in the high-resolution spectra of every element we know in nature. Gas discharge light sources set the course at the time, as did the lasers after the events in 1960.

Optics had given way to the microwaves in the fifties after the war. The physics of the gas discharges, however, continued as an active research field after the war, although of short duration. Bell Telephone Laboratory had a most distinguished research department in gas discharges in the early fifties. Towards the late fifties, as it seemed, the gas discharges as a field in research, also seemed to have been exhausted. The payoff at the time had evolved in the colorful neon light sources and fluorescence lamps, a thriving industry all over the country.

In the summer of 1958, Bell Telephone Laboratory had dissolved their research department in gas discharges. They had transferred every one of their distinguished research people to the other research areas in the laboratory. Some good people had left earlier, already.

As the fate in gas discharge physics had it, I joined the Laboratory in September 1958 – with ZERO backgrounds in gas discharge physics. I knew physics.

How Things Evolved

It has been said that when time is ripe for a new idea, if one person misses it, the next one will not. Time was ripe in the late fifties for the optically pumped idea for the laser, but far from it for the *electrically pumped*. Optical pumping was an active field in research at the time. The French had introduced the ‘pompage optic’, the optical pumping. With the French pompage optic, one would by optical pumping, resonantly excite an atomic species from its ground into its excited electronic state, and perform a double-resonance at an RF frequency on a fine or hyperfine structure of the excited electronic state. There were other versions of the French pompage optic. Each version used the optical pumping to induce resonantly, an atomic species into an excited electronic state.

Important, and more so, in the fifties, in the second half, the discoveries of the three-level masers at the microwave frequencies had attracted much attention. The three-level masers are the counterparts at the microwaves of our now optically pumped lasers. In three-level masers, one drives to saturation a pair of energy levels at microwave energy-spacing in a paramagnetic solid, and allows the inversion and the gain to set-in in a transition to a low-lying third energy level at the microwave frequencies. Nicholas Blumbergen at Harvard had proposed the three-level maser idea in an important publication in 1956. I had my own original three-level maser ideas, and had them published in 1957. In my work I had discovered a fascinating new effect, and for the first time, that in the transition to a third level in a three-level maser, it will be possible to drive the maser into its self-oscillation, *without* requiring the inversion. The effect had led me to the idea of the Raman masers, requiring a ‘*pumping*’ microwave field, followed by a Raman transition across a pair of energy levels at microwave energy-spacing. In my publication of the effect, I had also considered the pumping field at an optical frequency, instead of at the microwave.

The ideas were 'in the air' at the time, to extend the three-level maser approach into the optical frequencies. Yet, in the summer of 1958, on an occasion in June of that year, I think on the first Monday in June, *flashed* through my mind a far different approach, all because of the *helium metastables*. Ideas always come to mind in a *flash*, the rest follows.

Summer of 1958: A Bit of History

I think it was on the first Monday in June 1958. I had been on an occasion visiting the Bell Telephone Laboratory (BTL) on that day. They had approached me that I join their research staff at Bell. My work on masers – I had done as a part of my post-doctoral research position in physics at Columbia University in New York City – had in part overlapped the then ongoing work at Bell. They knew me, and I knew Bell.

At the visit meeting with Arthur Schawlow, whom I knew well, he gave me his news on that day, that he and Charles Townes, had submitted to the *Physical Review* a paper for publication proposing an optically pumped counterpart of a three-level maser at the optical frequencies – by-now, the well-known Schawlow–Townes optically pumped laser publication. Specially, I was attracted to Schawlow's idea on a two-mirror Perot–Fabry-type interferometer as a resonator at the optical frequencies for the laser. The use of it in that publication was Schawlow's idea.

My thoughts, it may seem paradoxical, right there and then moved far away from an optically pumped laser as a possibility. The helium atoms in a *metastable state* flashed through my mind. I will avoid explaining why or how, other than, of a three-level atom, two of the levels were now to belong to a *different* atomic species, the helium atom, and that there will be no optical pumping … and so much '*electrical energy*' could be converted to and stored in the energetic metastable helium. A new possibility presented itself, with no resemblance to the optical pumping – an energy-exchange effect taking place resonantly, between the highly energetic helium metastables, and – as it evolved – another inert gas, the neon atoms in a helium–neon gas mixture. The resonant nature of the effect embodied everything we know of the wave nature of the atoms. I will have a chance to explain the effect shortly below.

Driving home at the end of the day on that day, a two hour drive from Murray Hill, New Jersey to uptown New York City, the thought of the metastable helium had crystallized before me the task to examine the effect in a helium-plasma in a gas discharge, in a gas mixture with the other *four* well-behaved *inert gases*, from neon through xenon. There are four.

Within weeks in June, searching through the literature I learned, that over the years, and mostly in the early fifties, the helium plasmas in a gas discharge in mixtures with *every other* inert gases had been the subject of most extensive research, *except in a mixture with neon*. The mixture with neon, for the reason that the reader will find below, had been thought of as *uninteresting*. The matter was left for me.

I had accepted in June already, to join the Bell research staff at Murray-Hill, and I did on September. From my work that entire summer, unfolded the entire theory for the helium–neon gas laser. There was also another far-reaching offshoot.

The Physics Effect

Next to the hydrogen atom, the helium is the most fundamental of all atoms in physics. Hydrogen has one electron. Its spectrum, detached from the complexities of the multi-electron atoms, carries the entire signature of the wave nature of the atom, in ways that are subject to accurate predictions and the measurements. The helium atom has two electrons. Its spectrum carries the entire signature of the physics effect of the entire multi-electron atoms, also in ways that are subject to accurate predictions and the measurements. In its metastable states, it carries special *dynamic features*, deeply fundamental, and special *only* to the helium metastables.

In a gas discharge in pure helium at a moderate gas pressure, the discharge color takes on a grayish-white with a tint of blue. Over 500 excited electronic states in helium have been identified – their excitation by the energetic electrons in the discharge, followed by their spontaneous radiative decays, the emissions of photons, accounts for the high-resolution spectra of the discharge grayish-white with a tint of blue in color. Of these 500, all of them, high lying in energy, are short-lived radiatively, with the exception, however, of two amongst them. The two have the lowest excitation energy. Their radiative decays to the ground electronic state are deeply forbidden; they cannot decay radiatively. The two form the well-known helium metastables, identified by their spectroscopic designations: $^3S_{1/2}$, the triplet S one half, and $^1S_0$, the singlet S zero – generally referred to in the literature as, the triplet S and the singlet S metastables. Of the two, the triplet S metastable has the lowest excitation energy. It lies at 19.8 electron volts (eV), above the helium ground state. The singlet S metastable lies higher, at 20.2 eV.

Helium atoms in their ground electronic state are chemically inert. A helium atom's two electrons form a closed shell. It cannot enter in a chemical reaction, neither with its own species, nor with any other, as we all know. The situation is, however, far different with every one of the 500 excited electronic states in a helium gas discharge. They are energetically high-reactive, except, and with the exception of the two metastables, they are all *short-lived*, and cannot play an important role.

The effect manifests itself differently in the long-lived metastables, and accounts for their *special dynamic features,* special only to the helium metastables. What follows outlines the effect.

Dynamic Features: Why so Special

By far the majority of the atoms in the helium gas discharge are in their inert, ground electronic states. Once in its energetic metastable state, a helium metastable in the gas discharge encounters in an impact – in a collision – with a helium atom in its ground electronic state. The encounter in the impact is of a short duration in our scale of time, but long in the atomic time-scale, of about 2×10^{-13} second, a fifth of a picosecond. What occurs is strictly wave-mechanical, dictated by the wave nature of the electrons in the atoms. During the encounter, the electron wave functions in the encountering atoms overlap momentarily. A momentary binding occurs. In no ways can one tell during the encounter which electron is which: Electrons are the properties of their wave functions – once overlapped, individual electrons lose their identity, in no way can one tell which is which. As the atoms fly apart, caused by the kinematics of the impact, an *electron exchange* occurs, *wave-mechanically.* The helium atom initially in its ground electronic state, will fly away from the encounter with one of its two electrons now in the *highly excited* energetic *metastable* state. The other, the one initially in the excited metastable state, emerges from the encounter in the *unexcited* ground electronic state.

At a gas pressure in the discharge of about one torr, a millimeter, the mean free-time between two impacts is about one microsecond, a very long time in the scale of the atoms. The helium atom that flew away from the encounter in the metastable state remains in its now metastable state, during the entire mean-free collision time. Once it encounters the next helium atom in its ground electronic state, the act repeats again, a momentary binding occurs, an electron exchange takes place, and a new metastable flying away. The effect repeats over and over again, at about every microsecond. A *diffusion* of the metastability through the helium in the discharge sets in. Depending on the diameter of the discharge tubing, it takes about a millisecond until the helium that emerges from the encounter in the metastable state reaches the walls of the discharge tubing. The act will then *terminate*, in a *most violent* collision effect with the wall. The energetic metastable helium *knocks out* an electron off the wall, as itself emerges from the collision in its ground electronic state – all intact.

With one exception, the encounter between a helium metastable with any species other than of its own kind, a helium, is energetically *highly violent.* The exception is the neon atoms. In encounters with all atomic species other than neon, the metastable helium *knocks out* an electron off the species, ionizes the species, and itself emerges from the encounter in its ground electronic state, intact. The ionizing impacts had attracted so much attentions in the early fifties, the effect in the helium gas discharge in mixtures specially with every other inert gases, had been exhaustively investigated, except with neon. Neon has its ionization potential higher than the two metastable excitation energies. It can not undergo an ionizing impact with either of the two metastables. The mixture with neon had thus been considered uninteresting, and was discarded.

What emerged by the end of the summer of 1958 was the entire theory for the helium neon laser – and the recognition of a deeply wave-mechanical effect, the resonant energy exchange taking place between the energetic helium metastable and an inert neon atom in the discharge gas mixture. In the mixture, a momentary binding occurs between the helium metastable encountering an inert neon atom in the gas discharge. Wave-function overlaps occur for the electrons in the encountering atoms. A *resonant* energy exchange takes place during the encounter. Helium metastable will fly away from the impact in its now ground electronic state, while neon emerges in one of its high-lying excited energy states, at the near-resonant with the helium metastable.

A special effect sets in in the energy exchange, as well. The kinetics of the impact in the encounter enters in satisfying the exact resonance in the energy exchange. The singlet S metastable flying away from the encounter after the energy exchange, will be slightly 'cooler' kinetically, and the triplet S flying away from the encounter after the energy-exchange, will be slightly 'hotter'. The kinetic energy of the impact enters in the energy exchange.

Optical Gain and Amplification Effect

Within weeks, early in the summer of 1958, investigating the energy transfer effect led to the prediction that there can be inversion and optical gain in two sets of transitions in neon, one as a result of the excitation transfer from the triplet S metastables, and the other a result of the transfer from the singlet S. By far the more challenging task that summer, however, was to estimate theoretically the *values* for the *gain and amplification factors* obtainable for the predicted inverted transitions, and more specifically, for the inverted transitions that will have the highest gain and amplification factors. There followed the theoretical estimates on which relied the entire experimental phase of the work, the planning of it commenced within weeks after my joining the Bell Telephone Laboratory on September of that year.

The set of transitions originating from the triplet S energy transfer to neon, occur in the near-red region of the spectrum, the 1 μm wavelength region. The strongest inverted transition at the highest predicted gain value, lies at 1.15 μm transition wavelength, the spectral laser line that first broke into self-oscillation (see the opening page in this article). The set of transitions originating from the singlet S energy transfer to neon occur in the red-yellow region of the spectrum. The strongest, although at less gain-value than 1.15 μm, occurs at the 0.633 μm in the red.

In the early phase of the investigation, it came to light also that the achievement of the inverted transitions with optical gains, was, interestingly, a *commune occurrence* in gaseous discharges in a variety of the atomic species, including in pure neon. However, the complexities in the excitations by the hot electrons of the high-lying energy levels, and in particular in the presence of the secondary excitation mechanism, and a list of other similar effects, in no way would allow a quantitative estimate of the gain and amplification factors in the inverted transitions obtainable in the gas discharge.

The reliance on the excitations of the high-lying energy levels in neon via the resonant energy transfer from the helium metastables, as per the physics effect I have outlined above, placed at my disposal the one gas discharge system that lent itself to the theoretical estimates of the predicted optical gains and the amplification factor for the inverted transitions.

Without a knowledge of the predicted values for the optical gain and the amplification factor, it would have been in no way possible to perform the experiment.

Experimental Phase

The Bell Telephone Laboratory, considered as a foremost research institution in the country at the time, operated at a $250 million yearly budget – in 1960s' dollars. Transistors had been invented at Bell in the forties. With the awareness at the time at Bell, that a light beam at the degree of frequency-purity and the coherence expected of the laser, will have far-reaching consequences on the telecommunication technology, without hesitation I received from Bell an open ticket to do what it takes – one key person in the administration understood in-depth my approach to the laser – via the gas discharge and the physics effects I had invoked. Within weeks following joining Bell in September, I had my planning underway for what came to be known in a short while later, as a most aggressive research in gas discharges – and at a time when Bell had already, in the summer of 1958, dismantled the entire research activities in gas discharges at Bell. That speaks a great deal for Bell at the time … at the time before the AT&T break up.

In lasers, the knowledge of the full length of the amplifying medium across which the optical gain obtainable at the laser transition will suffice to drive the laser into its self-oscillation, will dictate the full length of the laser interferometer resonator. The spacing between the two high-reflectance interferometer end-mirrors will have to accommodate the full length of the amplifying medium, thus dictating the interferometer full length. With respect to the mirror reflectivity obtainable at the time, one had to be content with the values at the highest close to 98%. The highest gain transition from my theoretical estimates, that of the neon transition at the 1.15 μm wavelength in the near-red, indicated an interferometer length of no less than 50 centimeters, or possibly as long as one meter – and there lay the challenge, achieving the required degree of parallelism needed for the interferometer end-mirrors at such spacing. One could show, from simple inspection, that the parallelism needed for the mirrors had to be at values better than one part in several-hundredths of a wavelength. This value applied to the use of the flat interferometer mirrors known to me at that time.

An alignment to such a degree of accuracy could well be obtainable at the time for Perot–Fabry-type interferometer mirrors at the mirror-spacing not exceeding about eight or ten centimeters at the most – where one would rely on the observation of the interference fringes using the available spectroscopic light sources to observe the fringes, a principle well known in physical optics. At longer mirror spacing, the spectroscopic light sources lacked the degree of coherence, the color purity, needed to observe fringes for the mirror alignment. The fringes will get wiped out.

These days, using a helium–neon laser light source available at every laboratory in optics, one can align a two-mirror interferometer at tens of meters mirror-spacing, or hundreds, or even as far apart as several miles in some experiments. Ideas are floating around now of the possibility, using gas lasers, to align mirrors placed on satellites in orbit, with the mirror on two different satellites at controlled spacing as far apart as thousands of miles – the experiment thought of is that of the detection of the gravity waves. Without a laser operating and available at the time, in no ways would it have been possible to align an interferometer at a *daring* mirror-spacing as far apart as one meter, or even half as long. One had to rely on an auto-collimator, an optical instrument that at the best would provide an alignment to within one or two wavelengths, nowhere sufficient to drive the laser into its self oscillation.

The challenge mapped the entire course for the experimental phase, foremost aimed at showing every feature of the predicted effects experimentally, from the energy transfer effect, to observing and measuring the gain and amplification effect in the predicted inverted transitions in neon. The feat was that of the art in spectroscopy. The observation of gain and amplification effect was a highlight in the course of the experiment. Up to that point, in optical spectroscopy, one always measured the spectral lines in either emission or in absorption. The feat was the first in spectroscopy, observing the spectral line of an atomic species not in absorption, but in amplification – the amplification of an external light source transmitted through the gas discharge in the experiment. The feat, yet, lay in the art in spectroscopy, throughout the experiments.

The event at 4:20 PM in December two years later, speaks for itself.

> It may seem now, as if one needed an operating helium–neon laser at the time, to align the laser mirrors for the first operating helium–neon laser. It seemed evident from the beginning, that the presence in the very first helium–neon laser, of the optical-gain at the predicted value in the predicted inverted transition, will guide achieving the alignment of its own mirrors, to the exact optical degree of the alignment accuracy needed for the self-oscillation. Driving the laser into its self-oscillation signaled the feat. The feat, however, was that of the power in spectroscopy, making it possible to predetermine the presence in the first helium–neon laser, of the optical gain, at the predicted optimum value needed for self oscillation.
>
> There were doubters and doubters, in the technical staff and the administration at Bell. Donald Herriott, William Bennett and Edward Ballick collaborated with me in the experiment.

The Impact

Within months of the publication of the work in January 1961 in the *Physical Review Letters*, walking through the long hallways at BTL where the laboratories were situated, one could see through the open doors in many laboratories down the long halways, the pink colors of long helium–neon gas discharges plasma tubing, with people in the labs searching for new laser transitions. BTL had revived the gas discharge research activities they had dismantled in the summer of 1958. Not surprisingly, the second set of new laser transitions driven into self-oscillation took place at Bell in 1962, that of the set of transitions in neon originating from the energy transfer from the helium singlet S metastable – with the most intense in the series, that of the by now well-known 0.6328 μm neon transition in the red. There followed the discoveries of the argon–ion gas laser and shortly thereafter the CO_2 gas laser, the two amongst the foremost in the many new gas lasers driven to self-oscillation at Bell.

Every gas laser discovered since the December 12 event, has enjoyed the use of a '*no-longer*' a '*daring*' '*long*' interferometer resonator, merely because one would use a He–Ne laser to *pre-align* the laser mirrors to within a small fraction of the wavelength needed, prior to searching for a new laser line in the gas discharge chosen for the search. The already aligned resonator removed the need to *predetermine* the presence of the gain and the amplification effect at the values needed for self-oscillation. Within a span of about a decade, virtually hundreds of different gases were driven to self-oscillation with this method, operating literally at thousands of different wavelengths, ranging from the far infrared, the 100 100ηn region, to the near-UV.

The helium–neon laser triggered so many of the key discoveries that followed. Within months, in the spring of 1961, one of the distinguished engineers at BTL, Rudolf Komphner, the discoverer of the backward tube oscillators at the microwave frequencies, began experimenting with the transmission through the improvised thin fiberoptic, of the output beam of a helium–neon laser at the 1.15 μm transition in the near-red, the near-IR, having his eyes on the potential someday in communication on the use of a continuously operating laser light beam at the near-IR frequencies. I recollect the very first ad that appeared on lasers nationally was a BTL ad in the spring of 1961, showing a cross-section of a beam of light, underneath it saying: '*Someday a Beam of Light This Size Will Carry Millions of Telephone Conversations Simultaneously*'. The ad speaks for itself.

In every gas laser, the active laser medium – being a gas – is highly homogeneous. As a result, with a reasonably good optics, one can obtain a nearly perfect Gaussian output beam. For this reason, the helium–neon lasers available commercially since the mid-sixties, have served as the indispensable tools for the alignment of the complex optics in every research laboratory in lasers, or in every manufacturer of the lasers in the country, or the manufacturers of the precise optical components, or the medical uses and so on.

In the applied areas, the helium–neon laser triggered so many of the key experiments in the early days. Philips at Eindhoven can be considered as the first discoverer of a video disc recorder. The model used a helium–neon red laser, at a most impressive fidelity and color resolution, in recording and in reading for the display. I recollect, in an exhibit shown to me at a Philips Lab, one groove on the recorder was that of a horse in a prairie, and the next groove, one '*micrometer away*' on the recorder, was that of a crowd in a park – so impressive at the time, with no cross talks. They had it packaged in a compact unit already. In other areas, all bar-code readings were done using a helium–neon laser, and some still do.

In the scientific area, from high-resolution spectroscopy at unprecedented accuracy, to the accurate clocks operating at optical frequencies, or in the measurements of the absolute frequencies of the accurate laser clocks, or the early experiments in relativity and so on, all are owed to the precision gas lasers. Helium–neon laser has played the key role, in the early days throughout, and continues today.

A note to the reader

In the early publications on laser, the device was generally known and referred to at the time as the 'Optical Maser'. The word laser became an accepted designation for the device in the late 1960s and the early 1970s.

Suggested Readings

Javan A (1961) In: Singer J (ed.) *Advances in Quantum Electronics*, pp. 18. Columbia University Press.

Javan A, Bennett WR, Jr. and Herriott DR (1961) Publications reporting operation of the first helium–neon laser. *Physical Review Letters* 6: 106.



Field Guide to

Microscopy

Tomasz S. Tkaczyk

Field Guide to

Microscopy

Tomasz S. Tkaczyk

SPIE Field Guides
Volume FG13

John E. Greivenkamp, Series Editor

SPIE PRESS
Bellingham, Washington USA

Library of Congress Cataloging-in-Publication Data

Tkaczyk, Tomasz S.
Field guide to microscopy / Tomasz S. Tkaczyk.
p. cm. -- (The field guide series)
Includes bibliographical references and index.
ISBN 978-0-8194-7246-5
1. Microscopy--Handbooks, manuals, etc. I. Title.
QH205.2.T53 2009
502.8'2--dc22
2009049648

Published by

SPIE
P.O. Box 10
Bellingham, Washington 98227-0010 USA
Phone: +1 360.676.3290
Fax: +1 360.647.1445
Email: spie@spie.org
Web: http://spie.org

Copyright © 2010 The Society of Photo-Optical Instrumentation Engineers (SPIE)

All rights reserved. No part of this publication may be reproduced or distributed in any form or by any means without written permission of the publisher.

The content of this book reflects the work and thought of the author. Every effort has been made to publish reliable and accurate information herein, but the publisher is not responsible for the validity of the information or for any outcomes resulting from reliance thereon.

Printed in the United States of America.

Introduction to the Series

Welcome to the *SPIE Field Guides*—a series of publications written directly for the practicing engineer or scientist. Many textbooks and professional reference books cover optical principles and techniques in depth. The aim of the *SPIE Field Guides* is to distill this information, providing readers with a handy desk or briefcase reference that provides basic, essential information about optical principles, techniques, or phenomena, including definitions and descriptions, key equations, illustrations, application examples, design considerations, and additional resources. A significant effort will be made to provide a consistent notation and style between volumes in the series.

Each *SPIE Field Guide* addresses a major field of optical science and technology. The concept of these *Field Guides* is a format-intensive presentation based on figures and equations supplemented by concise explanations. In most cases, this modular approach places a single topic on a page, and provides full coverage of that topic on that page. Highlights, insights, and rules of thumb are displayed in sidebars to the main text. The appendices at the end of each *Field Guide* provide additional information such as related material outside the main scope of the volume, key mathematical relationships, and alternative methods. While complete in their coverage, the concise presentation may not be appropriate for those new to the field.

The *SPIE Field Guides* are intended to be living documents. The modular page-based presentation format allows them to be easily updated and expanded. We are interested in your suggestions for new *Field Guide* topics as well as what material should be added to an individual volume to make these *Field Guides* more useful to you. Please contact us at **fieldguides@SPIE.org.**

John E. Greivenkamp, *Series Editor*
College of Optical Sciences
The University of Arizona

The Field Guide Series

Keep information at your fingertips with all of the titles in the *Field Guide* series:

Field Guide to Geometrical Optics, John E. Greivenkamp (FG01)

Field Guide to Atmospheric Optics, Larry C. Andrews (FG02)

Field Guide to Adaptive Optics, Robert K. Tyson & Benjamin W. Frazier (FG03)

Field Guide to Visual and Ophthalmic Optics, Jim Schwiegerling (FG04)

Field Guide to Polarization, Edward Collett (FG05)

Field Guide to Optical Lithography, Chris A. Mack (FG06)

Field Guide to Optical Thin Films, Ronald R. Willey (FG07)

Field Guide to Spectroscopy, David W. Ball (FG08)

Field Guide to Infrared Systems, Arnold Daniels (FG09)

Field Guide to Interferometric Optical Testing, Eric P. Goodwin & James C. Wyant (FG10)

Field Guide to Illumination, Angelo V. Arecchi; Tahar Messadi; R. John Koshel (FG11)

Field Guide to Lasers, Rüdiger Paschotta (FG12)

Field Guide to Microscopy, Tomasz Tkaczyk (FG13)

Field Guide to Laser Pulse Generation, Rüdiger Paschotta (FG14)

Field Guide to Infrared Systems, Detectors, and FPAs, Second Edition, Arnold Daniels (FG15)

Field Guide to Optical Fiber Technology, Rüdiger Paschotta (FG16)

Preface to the Field Guide to Microscopy

In the 17th century Robert Hooke developed a compound microscope, launching a wonderful journey. The impact of his invention was immediate; in the same century microscopy gave name to "cells" and imaged living bacteria. Since then microscopy has been the witness and subject of numerous scientific discoveries, serving as a constant companion in humans' quest to understand life and the world at the small end of the universe's scale.

Microscopy is one of the most exciting fields in optics, as its variety applies principles of interference, diffraction, and polarization. It persists in pushing the boundaries of imaging limits. For example, life sciences in need of nanometer resolution recently broke the diffraction limit. These new super-resolution techniques helped name microscopy the method of the year by *Nature Methods* in 2008.

Microscopy will critically change over the next few decades. Historically, microscopy was designed for visual imaging; however, enormous recent progress (in detectors, light sources, actuators, etc.) allows the easing of visual constrains, providing new opportunities. I am excited to witness microscopy's path toward both integrated, digital systems and nanoscopy.

This Field Guide has three major aims: (1) to give a brief overview of concepts used in microscopy; (2) to present major microscopy principles and implementations; and (3) to point to some recent microscopy trends. While many presented topics deserve a much broader description, the hope is that this Field Guide will be a useful reference in everyday microscopy work and a starting point for further study.

I would like to express my special thanks to my colleague here at Rice University, Mark Pierce, for his crucial advice throughout the writing process and his tremendous help in acquiring microscopy images.

This Field Guide is dedicated to my family: my wife, Dorota, and my daughters, Antonina and Karolina.

Tomasz Tkaczyk
Rice University

Table of Contents

Glossary of Symbols xi

Basics Concepts 1
- Nature of Light 1
- The Spectrum of Microscopy 2
- Wave Equations 3
- Wavefront Propagation 4
- Optical Path Length (OPL) 5
- Laws of Reflection and Refraction 6
- Total Internal Reflection 7
- Evanescent Wave in Total Internal Reflection 8
- Propagation of Light in Anisotropic Media 9
- Polarization of Light and Polarization States 10
- Coherence and Monochromatic Light 11
- Interference 12
- Contrast vs Spatial and Temporal Coherence 13
- Contrast of Fringes (Polarization and Amplitude Ratio) 15
- Multiple Wave Interference 16
- Interferometers 17
- Diffraction 18
- Diffraction Grating 19
- Useful Definitions from Geometrical Optics 21
- Image Formation 22
- Magnification 23
- Stops and Rays in an Optical System 24
- Aberrations 25
- Chromatic Aberrations 26
- Spherical Aberration and Coma 27
- Astigmatism, Field Curvature, and Distortion 28
- Performance Metrics 29

Microscope Construction 31
- The Compound Microscope 31
- The Eye 32
- Upright and Inverted Microscopes 33
- The Finite Tube Length Microscope 34

Infinity-Corrected Systems 35
Telecentricity of a Microscope 36
Magnification of a Microscope 37
Numerical Aperture 38
Resolution Limit 39
Useful Magnification 40
Depth of Field and Depth of Focus 41
Magnification and Frequency vs Depth of Field 42
Köhler Illumination 43
Alignment of Köhler Illumination 45
Critical Illumination 46
Stereo Microscopes 47
Eyepieces 48
Nomenclature and Marking of Objectives 50
Objective Designs 51
Special Objectives and Features 53
Special Lens Components 55
Cover Glass and Immersion 56
Common Light Sources for Microscopy 58
LED Light Sources 59
Filters 60
Polarizers and Polarization Prisms 61

Specialized Techniques 63
Amplitude and Phase Objects 63
The Selection of a Microscopy Technique 64
Image Comparison 65
Phase Contrast 66
Visibility in Phase Contrast 69
The Phase Contrast Microscope 70
Characteristic Features of Phase Contrast 71
Amplitude Contrast 72
Oblique Illumination 73
Modulation Contrast 74
Hoffman Contrast 75
Dark Field Microscopy 76
Optical Staining: Rheinberg Illumination 77

Optical Staining: Dispersion Staining 78
Shearing Interferometry: The Basis for DIC 79
DIC Microscope Design 80
Appearance of DIC Images 81
Reflectance DIC 82
Polarization Microscopy 83
Images Obtained with Polarization Microscopes 84
Compensators 85
Confocal Microscopy 86
Scanning Approaches 87
Images from a Confocal Microscope 89
Fluorescence 90
Configuration of a Fluorescence Microscope 91
Images from Fluorescence Microscopy 93
Properties of Fluorophores 94
Single vs Multi-Photon Excitation 95
Light Sources for Scanning Microscopy 96
Practical Considerations in LSM 97
Interference Microscopy 98
Optical Coherence Tomography/Microscopy 99
Optical Profiling Techniques 100
Optical Profilometry: System Design 101
Phase-Shifting Algorithms 102

Resolution Enhancement Techniques 103
Structured Illumination: Axial Sectioning 103
Structured Illumination: Resolution Enhancement 104
TIRF Microscopy 105
Solid Immersion 106
Stimulated Emission Depletion 107
STORM 108
4Pi Microscopy 109
The Limits of Light Microscopy 110

Other Special Techniques 111
Raman and CARS Microscopy 111
SPIM 112

Array Microscopy 113

Digital Microscopy and CCD Detectors 114
Digital Microscopy 114
Principles of CCD Operation 115
CCD Architectures 116
CCD Noise 118
Signal-to-Noise Ratio and the Digitization of CCD 119
CCD Sampling 120

Equation Summary 122

Bibliography 128

Index 133

Glossary of Symbols

$a(x, y)$, $b(x, y)$	Background and fringe amplitude
AO	Vector of light passing through amplitude Object
A_R, A_S	Amplitudes of reference and sample beams
b	Fringe period
c	Velocity of light
C	Contrast, visibility
C_{ac}	Visibility of amplitude contrast
C_{ph}	Visibility of phase contrast
$C_{ph\text{-}min}$	Minimum detectable visibility of phase contrast
d	Airy disk dimension
d	Decay distance of evanescent wave
d	Diameter of the diffractive object
d	Grating constant
d	Resolution limit
D	Diopters
D	Number of pixels in the x and y directions (N_x and N_y, respectively)
DA	Vector of light diffracted at the amplitude object
DOF	Depth of focus
DP	Vector of light diffracted at phase object
$\mathrm{D}_{\mathrm{pinhole}}$	Pinhole diameter
d_{xy}, d_z	Spatial and axial resolution of confocal microscope
E	Electric field
E	Energy gap
E_x and E_y	Components of electric field
F	Coefficient of finesse
F	Fluorescent emission
f	Focal length
f_C, f_F	Focal length for lines C and F
f_e	Effective focal length
FOV	Field of view
FWHM	Full width at half maximum
h	Planck's constant
h, h'	Object and image height
H	Magnetic field
I	Intensity of light
i, j	Pixel coordinates
I_o	Intensity of incident light

Glossary of Symbols (cont.)

$I_{\max}$, $I_{\min}$	Maximum and minimum intensity in the image
I, I_t, I_r	Irradiances of incident, transmitted, and reflected light
I_1, I_2, I_3 …	Intensity of successive images
I_0 , $I_{2\pi/3}$, $I_{4\pi/3}$	Intensities for the image point and three consecutive grid positions
k	Number of events
k	Wave number
L	Distance
l_c	Coherence length
m	Diffraction order
M	Magnification
$M_{\min}$	Minimum microscope magnification
MP	Magnifying power
MTF	Modulation transfer function
M_u	Angular magnification
n	Refractive index of the dielectric media
n	Step number
N	Expected value
N	Intensity decrease coefficient
N	Total number of grating lines
n_a	Probability of two-photon excitation
NA	Numerical aperture
n_e	Refractive index for propagation velocity of extraordinary wave
n_m, n_r	Refractive indices of the media surrounding the phase ring and the ring itself
n_o	Refractive index for propagation velocity of ordinary wave
n_1	Refractive index of media 1
n_2	Refractive index of media 2
o, e	Ordinary and extraordinary beams
OD	Optical density
OPD	Optical path difference
OPL	Optical path length
OTF	Optical transfer function
OTL	Optical tube length
P	Probability
P_{avg}	Average power
PO	Vector of light passing through phase object

Glossary of Symbols (cont.)

PSF	Point spread function
Q	Fluorophore quantum yield
r	Radius
r	Reflection coefficients
r, m, and o	Relative, media, or vacuum
r_{AS}	Radius of aperture stop
r_{PR}	Radius of phase ring
r_λ	Radius of filter for wavelength λ
s, s'	Shear between wavefront object and image space
S	Pinhole/slit separation
$s_\perp$	Lateral shift in TIR perpendicular component of electromagnetic vector
$s_\parallel$	Lateral shift in TIR for parallel component of electromagnetic vector
S_{FD}	Factor depending on specific Fraunhofer approximation
SM	Vector of light passing through surrounding media
SNR	Signal-to-noise ratio
SR	Strehl ratio
t	Lens separation
t	Thickness
t	Time
t	Transmission coefficient
T	Time required to pass the distance between wave oscillations
T	Throughput of a confocal microscope
t_{c}	Coherence time
u, u'	Object, image aperture angle
V_{d}, V_{e}	Abbe number as defined for lines d, F, C or e, F′, C′
V_{m}	Velocity of light in media
w	Width of the slit
x, y	Coordinates
z	Distance along the direction of propagation
z	Fraunhofer diffraction distance
z, z'	Object and image distances
z_{m}, z_{o}	Imaged sample depth, length of reference path

Glossary of Symbols (cont.)

α	Angle between vectors of interfering waves
α	Birefringent prism angle
α	Grating incidence angle in plane perpendicular to grating plane
α_s	Visual stereo resolving power
β	Grating diffraction angle in plane perpendicular to grating plane
γ	Angle of fringe localization plane
γ	Convergence angle of a stereo microscope
γ	Incidence / diffraction angle from the plane perpendicular to grating plane
Γ	Retardation
δ	Birefringence
δ	Excitation cross section of dye
δz	Depth perception
Δ_b	Axial phase delay
Δf	Variation in focal length
$\Delta\mathbf{k}$	Phase mismatch
Δz, $\Delta z'$	Object and image separations
$\Delta\lambda$	Wavelength bandwidth
$\Delta\nu$	Frequency bandwidth
$\Delta\varphi$	Phase delay
$\Delta\varphi$	Phase difference
$\Delta\varphi$	Phase shift
$\Delta\varphi_{min}$	Minimum perceived phase difference
ε	Angle between interfering beams
ε	Dielectric constant, i.e., medium permittivity
η	Quantum efficiency
θ'	Refraction angle
θ_{cr}	Critical angle
θ_i	Incidence angle
θ_r	Reflection angle
λ	Wavelength of light
λ_p	Peak wavelength for the m^{th} interference order
μ	Magnetic permeability
ν	Frequency of light
ν	Repetition frequency
ξ	Propagation direction
ρ	Spatial frequency
σ	Molecular absorption cross section

Glossary of Symbols (cont.)

σ_{dark}	Dark noise
σ_{photon}	Photon noise
σ_{read}	Read noise
τ	Integration time
τ	Length of a pulse
τ	Transmittance
φ	Incident photon flux
φ	Optical power
φ	Phase difference generated by a thin film
φ_o	Initial phase
φ_o	Phase delay through the object
φ_p	Phase delay in a phase plate
φ_{TF}	Phase difference generated by a thin film
ω	Angular frequency
ω	Bandgap frequency
$\perp$ and $\parallel$	Perpendicular and parallel components of the light vector

Nature of Light

Optics uses two approaches, termed the **particle** and **wave models,** to describe the nature of light. The former arises from atomic structure, where the transitions between energy levels are quantized. Electrons can be excited into higher energy levels via external processes with the release of a discrete quantum of energy (a photon) upon their decay to a lower level.

The wave model complements this corpuscular theory and explains optical effects involving diffraction and interference. The wave and particle models can be related through the frequency of oscillations, with the relationship between quanta of energy and frequency given by

$$E = h\nu \text{ [in eV or J]},$$

where $h = 4.135667\times10^{-15}$ [eV·s] $= 6.626068\times10^{-34}$ [J·s] is **Planck's constant**, and ν is the **frequency of light** [Hz]. The frequency ν of a wave is the reciprocal of its period T [s]:

$$\nu = \frac{1}{T}\,.$$



The period T [s] corresponds to one cycle of a wave or, if defined in terms of the distance required to perform one full oscillation, describes the **wavelength of light** λ [m]. The **velocity of light** in free space is 2.99792×10^8 m/s and is defined as the distance traveled in one period (λ) divided by the time taken (T):

$$c = \frac{\lambda}{T}\,.$$

Note that wavelength is often measured indirectly as time T required to pass the distance between wave oscillations.

The relationship for the velocity of light c can be rewritten in terms of wavelength and frequency as

$$c = \lambda\nu\,.$$

The Spectrum of Microscopy

The range of electromagnetic radiation is called the **electromagnetic spectrum**. Various microscopy techniques employ wavelengths spanning from **x-ray radiation** and **ultraviolet radiation** (UV) through the **visible spectrum** (VIS) to **infrared radiation** (IR). The wavelength in combination with the microscope parameters determines the resolution limit of the microscope (0.61λ/NA). The smallest feature resolved using light microscopy and determined by diffraction is approximately 200 nm for UV light with a high numerical aperture (for more details, see *Resolution Limit* on page 39). However, recently emerging super-resolution techniques overcome this barrier, and features are observable in the 20–50 nm range.


Frequency / Wavelength / Object Type
100.0 μm
Resolution Limit of Human Eye
Ephithelial Cells
Infrared
(ν ~ 3x10^12 Hz)
10.0 μm
Red Blood Cells
Bacteria
1.0 μm
750.0 nm
Visible
(ν ~ 6x10^14 Hz)
380.0 nm
Limit of Classical Light Microscopy
100.0 nm
Ultraviolet
(ν ~ 8x10^14 Hz)
Viruses
Limit of Light Microscopy with superresolution techniques
10.0 nm
Proteins
X rays
(ν ~ 3x10^16 Hz)
DNA / RNA
1.0 nm
gamma rays
(ν ~ 3x10^24 Hz)
Atoms
Limit of Electron Microscopy
0.1 nm

Wave Equations

Maxwell's equations describe the propagation of an electromagnetic wave. For homogenous and isotropic media, magnetic (*H*) and electric (*E*) components of an electromagnetic field can be described by the wave equations derived from Maxwell's equations:

$$\nabla^2 \vec{E} - \varepsilon_\mathrm{m}\mu_\mathrm{m}\frac{\partial^2 \vec{E}}{\partial t^2} = 0$$

$$\nabla^2 \vec{H} - \varepsilon_\mathrm{m}\mu_\mathrm{m}\frac{\partial^2 \vec{H}}{\partial t^2} = 0\,,$$

where ε is a **dielectric constant,** i.e., **medium permittivity** while μ is a **magnetic permeability**:

$$\varepsilon_\mathrm{m} = \varepsilon_\mathrm{o}\varepsilon_\mathrm{r} \qquad \mu_\mathrm{m} = \mu_\mathrm{o}\mu_\mathrm{r}$$

Indices r, m, and o stand for relative, media, or vacuum, respectively.

The above equations indicate that the time variation of the electric field and the current density creates a time-varying magnetic field. Variations in the magnetic field induce a time-varying electric field. Both fields depend on each other and compose an electromagnetic wave. Magnetic and electric components can be separated.



The electric component of an electromagnetic wave has primary significance for the phenomenon of light. This is because the magnetic component cannot be measured with optical detectors. Therefore, the magnetic component is most often neglected, and the electric vector $\vec{E}$ is called a light vector.

Wavefront Propagation

Light propagating through isotropic media conforms to the equation

$$E = A\sin\left(\omega t - kz + \varphi_{\mathrm{o}}\right),$$

where t is time, z is distance along the direction of propagation, and ω is an **angular frequency** given by

$$\omega = \frac{2\pi}{T} = \frac{2\pi V_{\mathrm{m}}}{\lambda}.$$

The term kz is called the **phase of light**, while φ_{o} is an initial phase. In addition, k represents the **wave number** (equal to $2\pi/\lambda$) and V_{m} is the velocity of light in media:

$$kz = \frac{2\pi}{\lambda} nz$$

The above propagation equation pertains to the special case when the electric field vector varies only in one plane.

The **refractive index** of the dielectric media n describes the relationship between the speed of light in a vacuum and in media. It is

$$n = \frac{c}{V_{\mathrm{m}}},$$

where c is the speed of light in vacuum.

An alternative way to describe the propagation of an electric field is with an exponential (complex) representation:

$$E = A\exp\left[-i\left(\omega t - kz + \varphi_{\mathrm{o}}\right)\right].$$

This form allows the easy separation of phase components of an electromagnetic wave.



Optical Path Length (OPL)

Fermat's principle states that "The path traveled by a light wave from a point to another point is stationary with respect to variations of this path." In practical terms, this means that light travels along the minimum time path.

Optical path length (OPL) is related to the time required for light to travel from point P1 to point P2. It accounts for the media density through the refractive index:

$$t = \frac{1}{c}\int_{P1}^{P2} n\,ds$$

or

$$OPL = \int_{P1}^{P2} n\,ds\ ,$$

where

$$ds^2 = dx^2 + dy^2 + dz^2\ .$$

Optical path length can also be discussed in the context of the number of periods required to propagate a certain distance *L*. In a medium with refractive index *n*, light slows down and more wave cycles are needed. Therefore, OPL is an equivalent path for light traveling with the same number of periods in a vacuum:

$$OPL = nL\ .$$

Optical path difference (OPD) is the difference between optical path lengths traversed by two light waves:

$$OPD = n_1 L_1 - n_2 L_2\ .$$

OPD can also be expressed as a phase difference:

$$\Delta\varphi = 2\pi\frac{OPD}{\lambda}\ .$$



Laws of Reflection and Refraction

Light rays incident on an interface between different dielectric media experience reflection and refraction as shown.



Reflection Law: Angles of **incidence** and **reflection** are related by

$$\theta_i = -\theta_r \,.$$

Refraction Law (**Snell's Law**): Incident and refracted angles are related to each other and to the refractive indices of the two media by Snell's Law:

$$n \sin\theta_i = n' \sin\theta' \,.$$

Fresnel reflection: The division of light at a dielectric boundary into transmitted and reflected rays is described for nonlossy, nonmagnetic media by the Fresnel equations:

Reflectance coefficients	**Transmission Coefficients**
$r_\perp = \frac{I_{r\perp}}{I_\perp} = \frac{\sin^2(\theta_i - \theta')}{\sin^2(\theta_i + \theta')}$ $r_\parallel = \frac{I_{r\parallel}}{I_\parallel} = \frac{\tan^2(\theta_i - \theta')}{\tan^2(\theta_i + \theta')}$	$t_\perp = \frac{I_{t\perp}}{I_\perp} = \frac{4\sin^2\theta' \cos^2\theta_i}{\sin^2(\theta_i + \theta')}$ $t_\parallel = \frac{I_{t\parallel}}{I_\parallel} = \frac{4\sin^2\theta' \cos^2\theta_i}{\sin^2(\theta_i + \theta')\cos^2(\theta_i - \theta')}$

t and r are transmission and reflection coefficients, respectively. I, I_t, and I_r are the irradiances of incident, transmitted, and reflected light, respectively. ⊥ and ‖ denote perpendicular and parallel components of the light vector with respect to the plane of incidence. θ_i and θ' in the table are the angles of incidence and reflection/refraction, respectively. At a normal incidence ($\theta' = \theta_i = 0$ deg), the Fresnel equations reduce to

$$r = r_\perp = r_\parallel = \frac{(n'-n)^2}{(n'+n)^2} \quad \text{and} \quad t = t_\perp = t_\parallel = \frac{4nn'}{(n'+n)^2} \,.$$

Total Internal Reflection

When light passes from one medium to a medium with a higher refractive index, the angle of the light in the medium bends toward the normal, according to Snell's Law. Conversely, when light passes from one medium to a medium with a lower refractive index, the angle of the light in the second medium bends away from the normal. If the angle of refraction is greater than 90 deg, the light cannot escape the denser medium, and it reflects instead of refracting. This effect is known as **total internal reflection** (TIR). TIR occurs only for illumination with an angle larger than the **critical angle**, defined as



$$\theta_{cr} = \arcsin\left(\frac{n_1}{n_2}\right).$$

It appears, however, that light can propagate through (at a limited range) to the lower-density material as an **evanescent wave** (a nearly standing wave occurring at the material boundary), even if illuminated under an angle larger than θ_{cr}. Such a phenomenon is called **frustrated total internal reflection**. Frustrated TIR is used, for example, with thin films (TF) to build beam splitters. The proper selection of the film thickness provides the desired beam ratio (see the figure below for various split ratios). Note that the maximum film thickness must be approximately a single wavelength or less, otherwise light decays entirely. The effect of an evanescent wave propagating in the lower-density material under TIR conditions is also used in total internal reflection fluorescence (**TIRF**) microscopy.



Evanescent Wave in Total Internal Reflection



A beam reflected at the dielectric interface during **total internal reflection** is subject to a small lateral shift, also known as the **Goos-Hänchen effect**. The shift is different for the parallel and perpendicular components of the electromagnetic vector.

	Lateral shift in TIR
Parallel* component of e/m vector	$s_{\parallel} = \frac{\lambda n_1}{\pi n_2^2} \frac{\tan\theta}{\sqrt{\sin^2\theta - \sin^2\theta_c}}$
Perpendicular* component of e/m vector	$s_{\perp} = \frac{\lambda}{\pi n_1} \frac{\tan\theta}{\sqrt{\sin^2\theta - \sin^2\theta_c}}$
* to the plane of incidence	

The intensity of the illuminating beam decays exponentially with distance *y* in the direction perpendicular to the material boundary:

$$I = I_o \exp(-y/d).$$

Note that *d* denotes the distance at which the intensity of the illuminating light I_o drops by *e*. The decay distance is smaller than a wavelength. It is also inversely proportional to the illumination angle.

Decay distance (*d*) of evanescent wave	
Decay distance as a function of incidence and critical angles	$d = \frac{\lambda}{4\pi n_1} \frac{1}{\sqrt{\sin^2\theta - \sin^2\theta_c}}$
Decay distance as a function of incidence angle and refractive indices of media	$d = \frac{\lambda}{4\pi} \frac{1}{\sqrt{n_1^2 \sin^2\theta - n_2^2}}$

Propagation of Light in Anisotropic Media

In anisotropic media the velocity of light depends on the direction of propagation. Common anisotropic and optically transparent materials include **uniaxial crystals**. Such crystals exhibit one direction of travel with a single propagation velocity. The single velocity direction is called the **optic axis** of the crystal. For any other direction, there are two velocities of propagation.

The wave in birefringent crystals can be divided into two components: ordinary and extraordinary. An **ordinary wave** has a uniform velocity in all directions, while the velocity of an **extraordinary wave** varies with orientation. The extreme value of an extraordinary wave's velocity is perpendicular to the optic axis. Both waves are linearly polarized, which means that the electric vector oscillates in one plane. The vibration planes of extraordinary and ordinary vectors are perpendicular. Refractive indices corresponding to the direction of the optic axis and perpendicular to the optic axis are $n_o = c/V_o$ and $n_e = c/V_e$ respectively.



Uniaxial crystals can be positive or negative (see table). The **refractive index** $n(\xi)$ for velocities between the two extreme (n_o and n_e) values is

$$\frac{1}{n^2(\xi)} = \frac{\cos^2\xi}{n_o^2} + \frac{\sin^2\xi}{n_e^2}.$$

Positive Birefringence	$V_e \le V_o$
Negative Birefringence	$V_e \ge V_o$

Note that the propagation direction ξ (with regard to the optic axis) is slightly off from the ray direction, which is defined by the Poynting (energy) vector.

Uniaxial Crystal	**Refractive index**	**Abbe Number**	**Wavelength Range** [μm]
Quartz	$n_o = 1.54424$ $n_e = 1.55335$	70 69	0.18–4.0
Calcite	$n_o = 1.65835$ $n_e = 1.48640$	50 68	0.2–2.0
The refractive index is given for the *D* spectral line (589.2 nm).			

(Adapted from Pluta, 1988)

Polarization of Light and Polarization States

The orientation characteristic of a light vector vibrating in time and space is called the **polarization of light**. For example, if the vector of an electric wave vibrates in one plane, the state of polarization is linear. A vector vibrating with a random orientation represents unpolarized light.

The wave vector E consists of two components E_x and E_y.

$$E(z,t) = E_x + E_y$$
$$E_x = A_x \exp\left[-i\left(\omega t - kz + \varphi_x\right)\right]$$
$$E_y = A_y \exp\left[-i\left(\omega t - kz + \varphi_y\right)\right].$$

The **electric vector** rotates periodically (the periodicity corresponds to wavelength λ) in the plane perpendicular to the propagation axis (z) and generally forms an elliptical shape. The specific shape depends on the A_x and A_y ratios and the phase delay between the E_x and E_y components, defined as $\Delta\varphi = \varphi_x - \varphi_y$.

Linearly polarized light is obtained when one of the components E_x or E_y is zero, or when $\Delta\varphi$ is zero or π. **Circularly polarized light** is obtained when $E_x = E_y$ and $\Delta\varphi = \pm\pi/2$. The light is called right circularly polarized (RCP) if it rotates in a clockwise direction or left circularly polarized (LCP) if it rotates counterclockwise when looking at the oncoming beam.



Polarization	Circular	Linear	Linear	Elliptical
Amplitudes	1 1	1 1	0 1	1 1
Δφ	π/2	0	0	π/4

Coherence and Monochromatic Light

An ideal light wave that extends in space at any instance to $\pm\infty$ and has only one wavelength λ (or frequency ν) is said to be **monochromatic**. If the range of wavelengths λ or frequencies ν is very small (around λ_o or ν_o, respectively), the wave is **quasi-monochromatic**. Such a wave packet is usually called a **wave group**.

Note that for monochromatic and quasi-monochromatic waves, no phase relationship is required, and the intensity of light can be calculated as a simple summation of intensities from different waves; phase changes are very fast and random, so only the average intensity can be recorded.

If multiple waves have a common phase relation dependence, they are **coherent** or **partially coherent**. These cases correspond to full- and partial-phase correlation respectively. A common source of a coherent wave is a laser where waves must be in resonance and therefore in phase. The average length of the wave packet (group) is called the **coherence length**, while the time required to pass this length is called **coherence time**. Both values are linked by the equations

$$\Delta\nu = \frac{1}{t_c} = \frac{V}{l_c}$$

where coherence length is

$$l_c = \frac{\lambda^2}{\Delta\lambda}.$$

The coherence length l_c and **temporal coherence** t_c are inversely proportional to the bandwidth $\Delta\lambda$ of the light source.

Spatial coherence is a term related to the coherence of light with regard to the extent of the light source. The fringe contrast varies for interference of any two spatially different source points. Light is **partially coherent** if its coherence is limited by the source bandwidth, dimension, temperature, or other effects.

Interference

Interference is a process of superposition of two coherent (correlated) or partially coherent waves. Waves interact with each other, and the resulting intensity is described by summing the **complex amplitudes** (**electric fields**) E_1 and E_2 of both wavefronts:

$$E_1 = A_1 \exp\left[-i\left(\omega t - kz + \varphi_1\right)\right]$$

and

$$E_2 = A_2 \exp\left[-i\left(\omega t - kz + \varphi_2\right)\right].$$

The resultant field is

$$E = E_1 + E_2 .$$

Therefore, the **interference** of the two beams can be written as

$$I = EE^*,$$

$$I = A_1^2 + A_2^2 + 2A_1A_2\cos\left(\Delta\varphi\right),$$

$$I = I_1 + I_2 + 2\sqrt{I_1I_2}\cos\left(\Delta\varphi\right),$$

$$I_1 = E_1E_1^*,\ \ I_2 = E_2E_2^*,\ \text{and}$$

$$\Delta\varphi = \varphi_2 - \varphi_1,$$



Propagating Wavefronts

where * denotes a conjugate function, I is the **intensity of light**, A is an amplitude of an electric field, and $\Delta\varphi$ is the phase difference between the two interfering beams. **Contrast** C (called also **visibility**) of the interference fringes can be expressed as

$$C = \frac{I_{\max} - I_{\min}}{I_{\max} + I_{\min}}.$$

The fringe existence and visibility depends on several conditions. To obtain the interference effect,

- Interfering beams must originate from the same light source and be temporally and spatially coherent;
- The polarization of interfering beams must be aligned;
- To maximize the contrast, interfering beams should have equal or similar amplitudes.

Conversely, if two noncorrelated, random waves are in the same region of space, the sum of intensities (irradiances) of these waves gives a total intensity in that region: $I = I_1 + I_2$.

Contrast vs Spatial and Temporal Coherence

The result of interference is a periodic intensity change in space, which creates fringes when incident on a screen or detector. **Spatial coherence** relates to the contrast of these fringes depending on the extent of the source and is not a function of the phase difference (or OPD) between beams. The intensity of interfering fringes is given by

$$I = I_1 + I_2 + 2C\left(\text{Source Extent}\right)\sqrt{I_1 I_2}\cos\left(\Delta\varphi\right),$$

where C is a constant, depending on the extent of the source.





The spatial coherence can be improved through spatial filtering. For example, light can be focused on the pinhole (or coupled into the fiber) by using a microscope objective. In microscopy, spatial coherence can be adjusted by changing the diaphragm size in the conjugate plane of the light source.

Contrast vs Spatial and Temporal Coherence (cont.)

The intensity of the fringes depends on the OPD and the **temporal coherence** of the source. The fringe contrast trends toward zero as the OPD increases beyond the coherence length:

$$I = I_1 + I_2 + 2\sqrt{I_1 I_2}\,C(OPD)\cos(\Delta\varphi).$$





The spatial width of a fringe pattern envelope decreases with shorter temporal coherence. The location of the envelope's peak (with respect to the reference) and narrow width can be efficiently used as a gating mechanism in both imaging and metrology. For example, it is used in interference microscopy for optical profiling (white light interferometry) and for imaging using optical coherence tomography. Examples of short coherence sources include white light sources, luminescent diodes, and broadband lasers.

Long coherence length is beneficial in applications that do not naturally provide near-zero OPD, e.g., in surface measurements with a Fizeau interferometer.

Contrast of Fringes (Polarization and Amplitude Ratio)



The contrast of fringes depends on the polarization orientation of the electric vectors. For linearly polarized beams, it can be described as $C = |\cos\alpha|$, where α represents the angle between polarization states.

Angle between Electric Vectors of Interfering Beams			
0	π/6	π/3	π/2
Interference Fringes			
			

Fringe contrast also depends on the interfering beams' amplitude ratio. The intensity of the fringes is simply calculated by using the main interference equation. The contrast is maximum for equal beam intensities and for the interference pattern, defined as

$$I = I_1 + I_2 + 2\sqrt{I_1 I_2}\cos(\Delta\varphi),$$

it is

$$C = \frac{2\sqrt{I_1 I_2}}{I_1 + I_2}.$$



Ratio between Amplitudes of Interfering Beams			
1	0.5	0.25	0.1
Interference Fringes			
			

Multiple Wave Interference

If light reflects inside a thin film, its intensity gradually decreases and **multiple beam interference** occurs.

The intensity of reflected light is

$$I_r = I_i \frac{F\sin^2(\varphi/2)}{1+F\sin^2(\varphi/2)} \ ,$$

and for transmitted light is

$$I_t = I_i \frac{1}{1+F\sin^2(\varphi/2)} \ .$$



The coefficient of finesse F of such a resonator is

$$F = \frac{4r}{(1-r)^2} \ .$$

Because phase depends on the wavelength, it is possible to design selective **interference filters**. In this case, a dielectric thin film is coated with metallic layers. The peak wavelength for the m^{th} interference order of the filter can be defined as

$$\lambda_p = \frac{2nt\cos\theta'}{m - \left(\frac{\varphi_{TF}}{2\pi}\right)} \ ,$$

where φ_{TF} is the phase difference generated by a thin film of thickness t and a specific incidence angle. The **interference order** relates to the phase difference in multiples of 2π.

Interference filters usually operate for illumination with flat wavefronts at a normal incidence angle. Therefore, the equation simplifies as

$$\lambda_p = \frac{2nt}{m} \ .$$

The **half bandwidth** (HBW) of the filter for normal incidence is

$$HBW = \frac{1-r}{m\pi}\lambda_p \ [\mathrm{m}] \ .$$



The peak intensity transmission is usually at 20% to 50%, or up to 90% of the incident light for metal-dielectric or multi-dielectric filters respectively.

Interferometers

Due to the high frequency of light, it is not possible to detect the phase of the light wave directly. To acquire the phase, interferometry techniques may be used. There are two major classes of interferometers, based on **amplitude splitting** and **wavefront splitting**.


Amplitude Split


Wavefront Split

From the point of view of fringe pattern interpretation, interferometers can also be divided into those that deliver fringes, which directly correspond to the phase distribution, and those providing a derivative of the phase map (also called shearing interferometers). The first type is realized by obtaining the interference between the test beam and a reference beam. An example of such a system is the **Michelson interferometer**. **Shearing interferometers** provide the intereference of two shifted object wavefronts.

Michelson Interferometer


Reference Mirror
Beam Splitter
Object

There are numerous ways of introducing shear (linear, radial, etc.). Examples of shearing interferometers include the parallel or wedge plate, the grating interferometer, the **Sagnac**, and polarization interferometers (commonly used in microscopy). The **Mach-Zehnder interferometer** can be configured for direct and differential fringes, depending on the position of the sample.


Shearing Plate
Tested Wavefront

Mach Zehnder Interferometer (Direct Fringes)


Beam Splitter
Mirror
Mirror
Beam Splitter
Object

Mach Zehnder Interferometer (Differential Fringes)


Beam Splitter
Mirror
Mirror
Object
Beam Splitter

Diffraction

The bending of waves by apertures and objects is called **diffraction of light**. Waves diffracted inside the optical system interfere (for path differences within the coherence length of the source) with each other and create diffraction patterns in the image of an object.


Constructive Interference
Large Aperture Stop
Destructive Interference
Destructive Interference
Point Object
Small Aperture Stop
Constructive Interference

There are two common approximations of diffraction phenomena: **Fresnel diffraction** (near-field) and **Fraunhofer diffraction** (far-field). Both diffraction types complement each other but are not sharply divided due to various definitions of their regions. Fraunhofer diffraction occurs when one can assume that propagating wavefronts are flat (collimated), while the Fresnel diffraction is the near-field case. Thus, Fraunhofer diffraction (distance z) for a free-space case is infinity, but in practice it can be defined for a region

$$z > S_{\mathrm{FD}} \frac{d^2}{\lambda},$$

where d is the diameter of the diffractive object, and S_{FD} is a factor depending on approximation. A conservative definition of the Fraunhofer region is $S_{\mathrm{FD}} = 1$, while for most practical cases it can be assumed to be 10 times smaller ($S_{\mathrm{FD}} = 0.1$).

Diffraction effects influence the resolution of an imaging system and are a reason for fringes (ring patterns) in the image of a point. Specifically, Fraunhofer fringes appear in the conjugate image plane. This is due to the fact that the image is located in the Fraunhofer diffracting region of an optical system's aperture stop.

Diffraction Grating

Diffraction gratings are optical components consisting of periodic linear structures that provide "organized" diffraction of light. In practical terms, this means that for specific angles (depending on illumination and grating parameters), it is possible to obtain constructive (2π phase difference) and destructive (π phase difference) interference at specific directions. The angles of constructive interference are defined by the diffraction grating equation and called **diffraction orders** (m).

Gratings can be classified as transmission or reflection (mode of operation), amplitude (periodic amplitude changes) or phase (periodic phase changes), or ruled or holographic (method of fabrication). Ruled gratings are mechanically cut and usually have a triangular profile (each facet can thereby promote select diffraction angles). Holographic gratings are made using interference (sinusoidal profiles).

Diffraction angles depend on the ratio between the grating constant and wavelength so various wavelengths can be separated. This makes them applicable for spectroscopic detection or spectral imaging. The **grating equation** is

$$m\lambda = d \cos\gamma\,(\sin\beta \pm \sin\alpha)$$



Diffraction Grating (cont.)

The sign in the diffraction grating equation defines the type of grating: A **transmission grating** is identified with a minus sign (–), and a **reflective grating** is identified with a plus sign (+).

For a grating illuminated in the plane perpendicular to the grating, its equation simplifies and is

$$m\lambda = d\left(\sin\beta \pm \sin\alpha\right).$$


Reflective Grating g = 0
Incident Light
+
-
0th order
(Specular Reflection)
+2nd
+1st
+3rd
-1st
-2nd
+4th
-3rd
Grating
Normal


Transmission Grating
Incident Light
+
-
Grating
Normal
-3rd
+4th
-2nd
+3rd
-1st
+2nd
+1st
0th order
(non-diffracted light)
+
-

For normal illumination, the grating equation becomes

$$m\lambda = d\sin\beta.$$

The **chromatic resolving power** of a grating depends on its size (total number of lines *N*). If the grating has more lines, the diffraction orders are narrower, and the resolving power increases:

$$\frac{\lambda}{\Delta\lambda} = mN.$$

The **free spectral range** $\Delta\lambda$ of the grating is the bandwidth in the m^{th} order without overlapping other orders. It defines useful bandwidth for spectroscopic detection as


Overlapping Orders
m = 0
$\lambda = \lambda_1$
m = -1
$\lambda = \lambda_1$
m = -2
$\lambda = 2\lambda_1$
m = -1
$\lambda = \lambda_1$
m = -3
$\lambda = 3\lambda_1$
m = -1
+
-
Incident Light
Grating
Normal

$$\Delta\lambda = \frac{m+1}{m}\lambda_1 - \lambda_1 = \frac{\lambda_1}{m}.$$

Useful Definitions from Geometrical Optics

All optical systems consist of refractive or reflective interfaces (surfaces) changing the propagation angles of **optical rays**.



Rays define the propagation trajectory and always travel perpendicular to the wavefronts. They are used to describe imaging in the regime of geometrical optics and to perform optical design.

There are two **optical spaces** corresponding to each optical system: **object space** and **image space**. Both spaces extend from –∞ to +∞ and are divided into real and virtual parts. Ability to access the image or object defines the real part of the optical space.

Paraxial optics is an approximation assuming small ray angles and is used to determine first-order parameters of the optical system (image location, magnification etc.).

Thin lenses are optical components reduced to zero thickness and are used to perform first-order optical designs (see next page).

The **focal point** of an optical system is a location that collimated beams converge to or diverge from. Planes perpendicular to the optical axis at the focal points are called **focal planes**. **Focal length** is the distance between the lens (specifically, its principal plane) and the focal plane. For thin lenses, principal planes overlap with the lens.

Sign Convention: The common sign convention assigns positive values to distances traced from left to right (the direction of propagation) and to the top. Angles are positive if they are measured counterclockwise from normal to the surface or optical axis. If light travels from right to left, the refractive index is negative. The surface radius is measured from its vertex to its center of curvature.



Image Formation

A simple model describing imaging through an optical system is based on thin lens relationships. A **real image** is formed at the point where rays converge.


Object Plane
Image Plane
Object
h
n
n′
F
F′
h′
Real Image
x
f
f′
x′
z
z′

A **virtual image** is formed at the point from which rays appear to diverge.

For a lens made of glass, surrounded on both sides by air ($n = n' = 1$), the imaging relationship is described by the **Newtonian equation**

$$xx' = ff' \qquad \text{or} \qquad xx' = -f'^2 .$$

Note that Newtonian equations refer to the distance from the focal planes so, in practice, they are used with thin lenses.

Imaging can also be described by the **Gaussian imaging equation**

$$\frac{f}{z} + \frac{f'}{z'} = 1 .$$

The **effective focal length** of the system is

$$f_e = \frac{1}{\varphi} = -\frac{f}{n} = \frac{f'}{n'} ,$$


Image Plane
n
Object Plane
n′
Virtual Image
F
F′
f
f′
z
z′

where φ is the **optical power** expressed in diopters D [m^{-1}].

Therefore,

$$\frac{n'}{z'} = \frac{n}{z} + \frac{1}{f_e} .$$

For air, when n and n' are equal to 1, the imaging relation is

$$\frac{1}{z'} = \frac{1}{z} + \frac{1}{f_e} .$$

Magnification

Transverse magnification (also called **lateral magnification**) of an optical system is defined as the ratio of the image and object size measured in the direction perpendicular to the optical axis:

$$M = \frac{h'}{h} = -\frac{x'}{f'} = -\frac{f}{x} = \frac{z'}{z} = \frac{-f}{z-f} = \frac{-(z'-f')}{f'}.$$

Longitudinal magnification defines the ratio of distances for a pair of conjugate planes:

$$\frac{\Delta z'}{\Delta z} = \left(-\frac{f'}{f}\right) M_1 M_2,$$

where

$$\Delta z = z_2 - z_1$$
$$\Delta z' = z_2' - z_1'$$

and

$$M_1 = \frac{h_1'}{h_1}$$
$$M_2 = \frac{h_2'}{h_2}.$$

Angular magnification is the ratio of angular image size to angular object size and can be calculated with

$$M_u = \frac{u'}{u} = \frac{z}{z'}.$$



Stops and Rays in an Optical System

The primary stops in any optical system are the **aperture stop** (which limits light) and **field stop** (which limits the extent of the imaged object or the field of view). The aperture stop also defines the resolution of the optical system. To determine the aperture stop, all system diaphragms including the lens mounts should be imaged to either the image or the object space of the system. The aperture stop is determined as the smallest diaphragm or diaphragm image (in terms of angle) as seen from the on-axis object/image point in the same optical space.

Note that there are two important conjugates of the aperture stop in object and image space. They are called the **entrance pupil** and **exit pupil**, respectively.

The physical stop limiting the extent of the field is called the **field stop**. To find a field stop, all of the diaphragms should be imaged to the object or image space, with the smallest diaphragm defining the actual field stop, as seen from the entrance/exit pupil. Conjugates of the field stop in the object and image space are called the **entrance window** and **exit window**, respectively.

Two major rays that pass through the system are the **marginal ray** and the **chief ray**. The marginal ray crosses the optical axis at the conjugate of the field stop (and object) and the edge of the aperture stop. The chief ray goes through the edge of the field and crosses the optical axis at the aperture stop plane.



Aberrations

Individual spherical lenses cannot deliver perfect imaging because they exhibit errors called aberrations. All aberrations can be considered either **chromatic** or **monochromatic**. To correct for aberrations, optical systems use multiple elements, aspherical surfaces, and a variety of optical materials.

Chromatic aberrations are a consequence of the **dispersion** of optical materials, which is a change in the refractive index as a function of wavelength. The parameter-characterizing dispersion of any material is called the **Abbe number** and is defined as

$$V_{\mathrm{d}} = \frac{n_{\mathrm{d}} - 1}{n_{\mathrm{F}} - n_{\mathrm{C}}}.$$

Alternatively, the following equation might be used for other wavelengths:

$$V_{\mathrm{e}} = \frac{n_{\mathrm{e}} - 1}{n_{\mathrm{F'}} - n_{\mathrm{C'}}}.$$

λ [nm]	Symbol	Spectral Line
656	C	red hydrogen
644	C′	red cadmium
588	d	yellow helium
546	e	green mercury
486	F	blue hydrogen
480	F′	blue cadmium

In general, V can be defined by using refractive indices at any three wavelengths, which should be specified for material characteristics. Indices in the equations denote spectral lines. If V does not have an index, V_{d} is assumed.

Geometrical aberrations occur when optical rays do not meet at a single point. There are longitudinal and transverse ray aberrations describing the axial and lateral deviations from the paraxial image of a point (along the axis and perpendicular to the axis in the image plane), respectively.

Wave aberrations describe a deviation of the wavefront from a perfect sphere. They are defined as a distance (the optical path difference) between the wavefront and the reference sphere along the optical ray.

Chromatic Aberrations

Chromatic aberrations occur due to the dispersion of optical materials used for lens fabrication. This means that the refractive index is different for different wavelengths; consequently, various wavelengths are refracted differently.



Chromatic aberrations include axial (longitudinal) or transverse (lateral) aberrations. **Axial chromatic aberration** arises from the fact that various wavelengths are focused at different distances behind the optical system. It is described as a variation in focal length:

$$\frac{\Delta f}{f} = \frac{f_F - f_C}{f} = \frac{1}{V} .$$



Transverse chromatic aberration is an off-axis imaging of colors at different locations on the image plane.

To compensate for chromatic aberrations, materials with low and high Abbe numbers are used (such as flint and crown glass). Correcting chromatic aberrations is crucial for most microscopy applications, but it is especially important for multi-photon microscopy. Obtaining multi-photon excitation requires high laser power and is most effective using short pulse lasers. Such a light source has a broad spectrum, and chromatic aberrations may cause pulse broadening.

Spherical Aberration and Coma

The most important wave aberrations are spherical, coma, astigmatism, field curvature, and distortion.

Spherical aberration (on-axis) is a consequence of building an optical system with components with spherical surfaces. It occurs when rays from different heights in the pupil are focused at different planes along the optical axis. This results in an axial blur. The most common approach for correcting spherical aberration uses a combination of negative and positive lenses. Systems that correct spherical aberration heavily depend on imaging conditions. For example, in microscopy a cover glass must be of an appropriate thickness and refractive index in order to work with an objective. Also, the media between the objective and the sample (such as air, oil, or water) must be taken into account.



Coma (off-axis) can be defined as a variation of magnification with aperture location. This means that rays passing through a different azimuth of the lens are magnified differently. The name "coma" was inspired by the aberration's appearance, because it resembles a comet's tail as it emanates from the focus spot. It is usually stronger for lenses with a larger field, and its correction requires accommodation of the field diameter.



Astigmatism, Field Curvature, and Distortion

Astigmatism (off-axis) is responsible for different magnifications along orthogonal meridians in an optical system. It manifests as elliptical, elongated spots for the horizontal and vertical directions on opposite sides of the best focal plane. It is more pronounced for an object farther from the axis and is a direct consequence of improper lens mounting or an asymmetric fabrication process.





Field curvature (off-axis) results in a non-flat image plane. The image plane created is a concave surface as seen from the objective; therefore, various zones of the image can be seen in focus after moving the object along the optical axis. This aberration is corrected by an objective design combined with a tube lens or eyepiece.

Barrel Distortion



Pincushion Distortion



Distortion is a radial variation of magnification that will image a square as a pincushion or barrel. It is corrected in the same manner as field curvature. If preceded with system calibration, it can also be corrected numerically after image acquisition.

Performance Metrics

The major metrics describing the performance of an optical system are the **modulation transfer function** (MTF), the **point spread function** (PSF), and the **Strehl ratio** (SR).

The MTF is the modulus of the **optical transfer function** described by

$$OTF(\rho) = MTF(\rho)\exp\left[i\varphi(\rho)\right],$$

where the complex term in the equation relates to the phase transfer function. The MTF is a contrast distribution in the image in relation to contrast in the object as a function of spatial frequency ρ (for sinusoidal object harmonics) and can be defined as

$$MTF(\rho) = \frac{C(\rho)_{\text{image}}}{C(\rho)_{\text{object}}}.$$

The PSF is the intensity distribution at the image of a point object. This means that the PSF is a metric directly related to the image, while the MTF corresponds to spatial frequency distributions in the pupil. The MTF and PSF are closely related and comprehensively describe the quality of the optical system. In fact, the amplitude of the Fourier transform of the PSF results in the MTF.



The MTF can be calculated as the autocorrelation of the **pupil function**. The pupil function describes the field distribution of an optical wave in the pupil plane of the optical system. In the case of a uniform pupil's transmission, it directly relates to the field overlap of two mutually shifted pupils where the shift corresponds to spatial frequency.

Performance Metrics (cont.)

The **modulation transfer function** has different results for coherent and incoherent illumination. For incoherent illumination, the phase component of the field is neglected since it is an average of random fields propagating under random angles.

For coherent illumination, the contrast of transferring harmonics of the field is constant and equal to 1 until the location of the spatial frequency in the pupil reaches its edge. For higher frequencies, the contrast sharply drops to zero since they cannot pass the optical system. Note that contrast for the coherent case is equal to 1 for the entire MTF range.

The **cutoff frequency** for an incoherent system is two times the cutoff frequency of the equivalent aperture coherent system and defines the **Sparrow resolution limit**.



The **Strehl ratio** is a parametric measurement that defines the quality of the optical system in a single number. It is defined as the ratio of irradiance within the theoretical dimension of a diffraction-limited spot to the entire irradiance in the image of the point. One simple method to estimate the Strehl ratio is to divide the field below the MTF curve of a tested system by the field of the diffraction-limited system of the same numerical aperture. For practical optical design consideration it is usually assumed that the system is diffraction limited if the Strehl ratio is equal to or larger than 0.8.

The Compound Microscope

The primary goal of microscopy is to provide the ability to resolve the small details of an object. Historically, microscopy was developed for visual observation and, therefore, was set up to work in conjunction with the human eye. An effective high-resolution optical system must have resolving ability and be able to deliver proper magnification for the detector. In the case of visual observations, the detectors are the cones and rods of the retina.



A basic microscope can be built with a single-element, short-focal-length lens (**magnifier**). The object is located in the focal plane of the lens and is imaged to infinity. The eye creates a final image of the object on the retina. The system stop is the eye's pupil.

To obtain higher resolution for visual observation, the **compound microscope** was first built in the 17th century by Robert Hooke. It consists of two major components: the **objective** and the **eyepiece**. The short-focal-length lens (objective) is placed close to the object under examination and creates a real image of an object at the focal plane of the second lens. The eyepiece (similar to the magnifier) throws an image to infinity, and the human eye creates the final image. An important function of the eyepiece is to match the eye's pupil with the system stop, which is located in the back focal plane of the microscope objective.



The Eye



The **eye** was the first—and for a long time, the only—real-time detector used in microscopy. Therefore, the design of the microscope had to incorporate parameters responding to the needs of visual observation.

Cornea—the transparent portion of the sclera (the white portion of the human eye), which is a rigid tissue that gives the eyeball its shape. The cornea is responsible for two thirds of the eye's refractive power.

Lens—the lens is responsible for one third of the eye's power. Ciliary muscles can change the lens's power (accommodation) within the range of 15–30 diopters.

Iris—controls the diameter of the pupil (1.5–8 mm).

Retina—a layer with two types of photoreceptors: rods and cones. **Cones** (about 7 million) are in the area of the **macula** (~3 mm in diameter) and **fovea** (~1.5 mm in diameter, with the highest cone density), and they are designed for bright vision and color detection. There are three types of cones (red, green, and blue sensitive), and the spectral range of the eye is approximately 400–750 nm. **Rods** are responsible for night/low-light vision, and there are about 130 million located outside the fovea region.

It is arbitrarily assumed that the eye can provide sharp images for objects between 250 mm and infinity. A 250-mm distance is called the **minimum focus distance** or **near point**. The maximum eye resolution for bright illumination is 1 arc minute.

Upright and Inverted Microscopes

The two major microscope geometries are **upright** and **inverted.** Both systems can operate in reflectance and transmittance modes.


Upright
CCD Camera
Binocular and Optical Path Split Tube
Eye
Field Diaphragm
Aperture Diaphragm
Eyepiece (Ocular)
Light Source - Epi-illumination
Revolving Nosepiece
Filter Holders
Objective
Sample Stage
Condenser and Condenser's Diaphragm
Stand
Condenser's Focusing Knob
Fine and Coarse Focusing Knobs
Source Position Adjustment
Base
Light Source - Trans-illumination
Field Diaphragm

The inverted microscope is primarily designed to work with samples in cell culture dishes and to provide space (with a long-working distance condenser) for sample manipulation (for example, with patch pipettes in electrophysiology).


Trans-illumination
Inverted
Binocular and Optical Path Split Tube
Sample Stage
Eye
Eyepiece (Ocular)
Epi-illumination
CCD Camera
Objective
Revolving Nosepiece
Filter and Beam Splitter Cube

The Finite Tube Length Microscope


Eye's Pupil
Exit Pupil
Eye Relief
Eyepiece
Field Stop
Field Number [mm]
Optical Tube Length
Mechanical Tube Length
Back Focal Plane
M, NA, WD Type
Microscope Objective
Parfocal Distance
Aperture Angle
u
Refractive Index - n
WD - Working Distance
Glass Cover Slip
Microscope Slide

Historically, microscopes were built with a **finite tube length**. With this geometry, the microscope objective images the object into the tube end. This intermediate image is then relayed to the observer by an eyepiece. Depending on the manufacturer, different **optical tube lengths** are possible (for example, the standard tube length for Zeiss is 160 mm). The use of a standard tube length by each manufacturer unifies the optomechanical design of the microscope.

A constant **parfocal distance** for microscope objectives enables switching between different magnifications without defocusing. The **field number**, corresponding to the physical dimension (in millimeters) of the **field stop** inside the eyepiece, allows the microscope's field of view (FOV) to be determined according to

$$FOV = \frac{FieldNumber}{M_{\text{objective}}} \ [\text{mm}].$$

Infinity-Corrected Systems


Eye's Pupil
Exit Pupil
Eye Relief
Eyepiece
Field Stop
Field Number [mm]
Tube Lens' Focal Length
Tube Lens
Mechanical Tube Length
Back Focal Plane
M, NA, WD Type
Microscope Objective
Parfocal Distance
Aperture Angle
u
Refractive Index - n
WD - Working Distance
Glass Cover Slip
Microscope Slide

Microscope objectives can be corrected for a conjugate located at infinity, which means that the microscope objective images an object into infinity. An infinite conjugate is useful for introducing beam splitters or filters that should work with small incidence angles. Also, an infinity-corrected system accommodates additional components like DIC prisms, polarizers. etc. The collimated beam is focused to create an intermediate image with additional optics, called a **tube lens**. The tube lens either creates an image directly onto a CCD chip or an intermediate image, which is further reimaged with an eyepiece. Additionally, the tube lens might be used for system correction. For example, Zeiss corrects aberrations in its microscopes with a combination objective-tube lens.

In the case of an **infinity-corrected objective**, the transverse magnification can only be defined in the presence of a tube lens that will form a real image. It is given by the ratio between the tube lens's focal length and the focal length of the microscope objective.

Manufacturer	Focal Length of Tube Lens
Zeiss	164.5 mm
Olympus	180.0 mm
Nikon	200.0 mm
Leica	200.0 mm

Telecentricity of a Microscope

Telecentricity is a feature of an optical system where the principal ray in object, image, or both spaces is parallel to the optical axis. This means that the object or image does not shift laterally, even with defocus; the distance between two object or image points is constant along the optical axis.

An optical system can be **telecentric** in

- Object space, where the entrance pupil is at infinity, and the aperture stop is in the back focal plane;
- Image space, where the exit pupil is at infinity, and the aperture stop is in the front focal plane; or
- Both (doubly telecentric), where the entrance and exit pupils are at infinity, and the aperture stop is at the center of the system, in the back focal plane of the element before the stop and front focal length of the element after the stop (afocal system).


System Telecentric in Object Space
Focused Object Plane
Image Plane
Aperture Stop
Defocused Object Plane
f '


System Telecentric in Image Space
Object Plane
Focused Image Plane
Aperture Stop
Defocused Image Plane
f


System Doubly Telecentric
Focused Object Plane
Focused Image Plane
Aperture Stop
f₁'
f₂

The aperture stop in a microscope is located at the back focal plane of the microscope objective. This makes the microscope objective telecentric in object space. Therefore, in microscopy, the object is observed with constant magnification, even for defocused object planes. This feature of microscopy systems significantly simplifies their operation and increases the reliability of image analysis.

Magnification of a Microscope

Magnifying power (MP) is defined as the ratio between the angles subtended by an object with and without magnification. The magnifying power (as defined for a single lens) creates an enlarged virtual image of an object. The angle of an object observed with magnification is

$$u' = \frac{h'}{z'-l} = \frac{h(f-z')}{f(z'-l)}.$$


h
u
d_O = 250 mm
h′
u′
F
f
f′
F′
z′
l

Therefore,

$$MP = \frac{u'}{u} = \frac{d_o(f-z')}{f(z'-l)}.$$

The angle for an unaided eye is defined for the **minimum focus distance** (d_o) of 10 inches or 250 mm, which is the distance that the object (real or virtual) may be examined without discomfort for the average population. A distance l between the lens and the eye is often small and can be assumed to equal zero:

$$MP \approx \frac{250\text{mm}}{f} - \frac{250\text{mm}}{z'}.$$

If the virtual image is at infinity (observed with a relaxed eye), $z' = -\infty$, and

$$MP \approx \frac{250\text{mm}}{f}.$$

The total magnifying power of the microscope results from the magnification of the microscope objective and the magnifying power of the eyepiece (usually 10×):

$$M_{\text{objective}} = \frac{OTL}{f_{\text{objective}}}$$

$$MP_{\text{microscope}} = M_{\text{objective}} MP_{\text{eyepiece}} = -\frac{OTL}{f_{\text{objective}}} \frac{250\text{mm}}{f_{\text{eyepiece}}}.$$


Objective
$F_{\text{object ve}}$
$F'_{\text{object ve}}$
F_{eyepiece}
F'_{eyepiece}
OTL = Optical Tube Length
Eyepiece

Numerical Aperture

The aperture diaphragm of the optical system determines the angle at which rays emerge from the axial object point and, after refraction, pass through the optical system. This acceptance angle is called the object space aperture angle. The parameter describing system throughput and this acceptance angle is called the **numerical aperture** (NA):

$$NA = n \sin u \, .$$



As seen from the equation, throughput of the optical system may be increased by using media with a high refractive index *n*, e.g., oil or water. This effectively decreases the refraction angles at the interfaces.

The dependence between the numerical aperture in the object space NA and the numerical aperture in the image space between the objective and the eyepiece NA′ is calculated using the objective magnification:

$$NA = NA' M_{\text{objective}} \, .$$



As a result of diffraction at the aperture of the optical system, self-luminous points of the object are not imaged as points but as so-called Airy disks. An **Airy disk** is a bright disk surrounded by concentric rings with gradually decreasing intensities. The disk diameter (where the intensity reaches the first zero) is

$$d = \frac{1.22\lambda}{n \sin u} = \frac{1.22\lambda}{NA} \, .$$

Note that the refractive index in the equation is for media between the object and the optical system.

Media	Refractive Index
Air	1
Water	1.33
Oil	1.45–1.6 (1.515 is typical)

Resolution Limit



The lateral resolution of an optical system can be defined in terms of its ability to resolve images of two adjacent, self-luminous points. When two **Airy disks** are too close, they form a continuous intensity distribution and cannot be distinguished. The **Rayleigh resolution limit** is defined as occurring when the peak of the Airy pattern arising from one point coincides with the first minimum of the Airy pattern arising from a second point object. Such a distribution gives an intensity dip of 26%. The distance between the two points in this case is

$$d = \frac{0.61\lambda}{n \sin u} = \frac{0.61\lambda}{NA}.$$

The equation indicates that the resolution of an optical system improves with an increase in NA and decreases with increasing wavelength λ. For example, for $\lambda = 450$ nm (blue) and oil immersion $NA = 1.4$, the microscope objective can optically resolve points separated by less than 200 nm.

The situation in which the intensity dip between two adjacent self-luminous points becomes zero defines the **Sparrow resolution limit**. In this case $d = 0.5\lambda/NA$.



The **Abbe resolution limit** considers both the diffraction caused by the object and the NA of the optical system. It assumes that if at least two adjacent diffraction orders for points with spacing d are accepted by the objective, these two points can be resolved. Therefore, the resolution depends on both imaging and illumination apertures and is

$$d = \frac{\lambda}{NA_{\text{objective}} + NA_{\text{condenser}}}.$$

Useful Magnification

For visual observation, the **angular resolving power** can be defined as 1.5 arc minutes. For unmagnified objects at a distance of 250 mm (the eye's minimum focus distance), 1.5 arc minutes converts to d_{eye} = 0.1 mm. Since microscope objectives by themselves do not usually provide sufficient magnification, they are combined with oculars or eyepieces. The resolving power of the microscope is then

$$d_{\text{mic}} = \frac{d_{\text{eye}}}{M_{\text{min}}} = \frac{d_{\text{eye}}}{M_{\text{obj}} M_{\text{eyepiece}}} .$$

In the Sparrow resolution limit, the minimum microscope magnification is

$$M_{\text{min}} = 2 d_{\text{eye}} NA / \lambda .$$

Therefore, a total minimum magnification M_{min} can be defined as approximately 250–500 NA (depending on wavelength). For lower magnification the image will appear brighter, but imaging is performed below the overall resolution limit of the microscope. For larger magnification, the contrast decreases and resolution does not improve. While a theoretically higher magnification should not provide additional information, it is useful to increase it to approximately 1000 NA to provide comfortable sampling of the object. Therefore, it is assumed that the **useful magnification** of a microscope is between 500 NA and 1000 NA. Usually, any magnification above 1000 NA is called **empty magnification**. The image size in such cases is enlarged, but no additional useful information is provided. The highest useful magnification of a microscope is approximately 1500 for an oil-immersion microscope objective with $NA = 1.5$.

Similar analysis can be performed for digital microscopy, which uses CCD or CMOS cameras as image sensors. Camera pixels are usually small (between 2 and 30 microns), and useful magnification must be estimated for a particular image sensor rather than the eye. Therefore, digital microscopy can work at lower magnification, and magnification of the microscope objective alone is usually sufficient.

Depth of Field and Depth of Focus



Two important terms are used to define axial resolution: **depth of field** and **depth of focus**. Depth of field refers to the object thickness for which an image is in focus, while depth of focus is the corresponding thickness of the image plane. In the case of a diffraction-limited optical system, the depth of focus is determined for an intensity drop along the optical axis to 80%, defined as

$$DOF = 2\Delta z' = \frac{n'\lambda}{NA'^2}.$$



The relation between depth of field ($2\Delta z$) and depth of focus ($2\Delta z'$) incorporates the objective magnification:

$$2\Delta z' = M_{\text{objective}}^2 \, 2\Delta z \frac{n'}{n},$$

where n' and n are medium refractive indexes in the object and image space, respectively.

To quickly measure the depth of field for a particular microscope objective, the grid amplitude structure can be placed on the microscope stage and tilted with the known angle α. The depth of field is determined after measuring the grid zone w while in focus:

$$2\Delta z = nw\tan\alpha .$$

Magnification and Frequency vs Depth of Field

Depth of field for visual observation is a function of the total microscope magnification and the NA of the objective, approximated as

$$2\Delta z = n\frac{0.5\lambda}{NA^2} + n\frac{340}{M_{\text{microscope}}NA}\,.$$

Note that estimated values do not include eye accommodation. The graph below presents depth of field for visual observation. Refractive index *n* of the object space was assumed to equal 1. For other media, values from the graph must be multiplied by an appropriate *n*.



Depth of field can also be defined for a specific frequency present in the object because imaging contrast changes for a particular object frequency, as described by the modulation transfer function. The approximated equation is

$$2\Delta z = \frac{0.4}{\rho NA},$$

where ρ is the frequency in cycles per millimeter.



Köhler Illumination

One of the most critical elements in efficient microscope operation is proper set up of the illumination system. To assist with this, August Köhler introduced a solution that provides uniform and bright illumination over the field of view, even for light sources that are not uniform (e.g., a lamp filament). This system consists of a light source, a field-stop diaphragm, a condenser aperture, and collective and condenser lenses. This solution is now called **Köhler illumination** and is commonly used for a variety of imaging modes.


Sample Conjugate
Eye
Eye's Pupil
Source Conjugate
Eyepiece
Intermediate Image Plane
Sample Conjugate
Field Diaphragm
Aperture Stop
Source Conjugate
Microscope Objective
Sample Conjugate
Sample
Condenser Lens
Condenser's Diaphragm
Source Conjugate
Sample Conjugate
Field Diaphragm
Collective Lens
Light Source
Source Conjugate
Sample Path
Illumination Path

Köhler Illumination (cont.)

The illumination system is configured such that an image of the light source completely fills the condenser aperture.

Köhler illumination requires setting up the microscope system so that the field diaphragm, object plane, and intermediate image in the eyepiece's field stop, retina, or CCD are in conjugate planes. Similarly, the lamp filament, front aperture of the condenser, microscope objective's back focal plane (aperture stop), exit pupil of the eyepiece, and the eye's pupil are also at conjugate planes. Köhler illumination can be set up for both the transmission mode (also called **DIA**) and the reflectance mode (also called **EPI**).

The uniformity of the illumination is the result of having the light source at infinity with respect to the illuminated sample.

EPI illumination is especially useful for the biological and metallurgical imaging of thick or opaque samples.


Eye
Eye's Pupil
Eyepiece
Intermediate Image Plane
Field Diaphragm
Beam Splitter
Light Source
Aperture Stop
Microscope Objective
Sample Path
Illumination Path
Sample

Alignment of Köhler Illumination

The procedure for **Köhler illumination** alignment consists of the following steps:

1. Place the sample on the microscope stage and move it so that the front surface of the condenser lens is 1–2 mm from the microscope slide. The condenser and collective diaphragms should be wide open.
2. Adjust the location of the source so illumination fills the condenser's diaphragm. The sharp image of the lamp filament should be visible at the condenser's diaphragm plane and at the back focal plane of the microscope objective. To see the filament at the back focal plane of the objective, a **Bertrand lens** can be applied (also see *Special Lens Components* on page 55). The filament should be centered in the aperture stop using the bulb's adjustment knobs on the illuminator.
3. For a low-power objective, bring the sample into focus. Since a microscope objective works at a parfocal distance, switching to a higher magnification later is easy and requires few adjustments.
4. Focus and center the condenser lens. Close down the field diaphragm, focus down the outline of the diaphragm, and adjust the condenser's position. After adjusting the x-, y-, and z-axis, open the field diaphragm so it accommodates the entire field of view.
5. Adjust the position of the condenser's diaphragm by observing the back focal objective plane through the Bertrand lens. When the edges of the aperture are sharply seen, the condenser's diaphragm should be closed to approximately three quarters of the objective's aperture.
6. Tune the brightness of the lamp. This adjustment should be performed by regulating the voltage of the lamp's power supply or, preferably, through the neutral density filters in the beam path. Do not adjust the brightness by closing the condenser's diaphragm because it affects the illumination setup and the overall microscope resolution.

Note that while three quarters of the aperture stop is recommended for initial illumination, adjusting the aperture of the illumination system affects the resolution of the microscope. Therefore, the final setting should be adjusted after examining the images.

Critical Illumination

An alternative to Köhler illumination is **critical illumination**, which is based on imaging the light source directly onto the sample. This type of illumination requires a highly uniform light source. Any source non-uniformities will result in intensity variations across the image. Its major advantage is high efficiency, since it can collect a larger solid angle than Köhler illumination and therefore provides a higher energy density at the sample. For parabolic or elliptical reflective collectors, critical illumination can utilize up to 85% of the light emitted by the source.


Sample Conjugate
Eye
Eye's Pupil
Eyepiece
Intermediate Image Plane
Sample Conjugate
Field Diaphragm
Aperture Stop
Microscope Objective
Sample Conjugate
Sample
Condenser Lens
Condenser's Diaphragm
Sample Conjugate

Stereo Microscopes

Stereo microscopes are built to provide depth perception, which is important for applications like micro-assembly and biological and surgical imaging. Two primary stereo-microscope approaches involve building two separate tilted systems, or using a common objective combined with a binocular system.


Right Eye
Left Eye
Eyepiece
Eyepiece
Entrance Pupil
Entrance Pupil
Image Inverting Prisms
Image Inverting Prisms
Telescope Objectives
d
Microscope Objective
γ
F_{ob}

In the latter, the angle of convergence γ of a stereo microscope depends on the focal length of a microscope objective and a distance d between the microscope objective and telescope objectives. The entrance pupils of the microscope are images of the stops (located at the plane of the telescope objectives) through the microscope objective.

Depth perception δz can be defined as

$$\delta z = \frac{250\alpha_s}{M_{\text{microscope}} \tan\gamma}[\text{mm}],$$

where α_s is a **visual stereo resolving power**, which for daylight vision is approximately 5–10 arc seconds.

Stereo microscopes have a convergence angle γ in the range of 10–15 deg. Note that γ is 15 deg for visual observation and 0 for a standard microscope. For example, depth perception for the human eye is approximately 0.05 mm (at 250 mm), while for a stereo microscope of $M_{\text{microscope}} = 100$ and $\gamma = 15$ deg, it is $\delta z = 0.5$ μm.

Eyepieces

The eyepiece relays an intermediate image into the eye, corrects for some remaining objective aberrations, and provides measurement capabilities. It also needs to relay an exit pupil of a microscope objective onto the entrance pupil of the eye. The location of the relayed exit pupil is called the **eye point** and needs to be in a comfortable observation distance behind the eyepiece. The clearance between the mechanical mounting of the eyepiece and the eye point is called **eye relief**. Typical eye relief is 7–12 mm.

An eyepiece usually consists of two lenses: one (closer to the eye) which magnifies the image, and a second working as a collective lens and also responsible for the location of the exit pupil of the microscope. An eyepiece contains a field stop that provides a sharp image edge.

Parameters like **magnifying power** of an eyepiece and **field number** (FN), i.e., field of view of an eyepiece, are engraved on an eyepiece's barrel: M × / FN. Field number and magnification of a microscope objective allow quick calculation of the imaged area of a sample (see also *The Finite Tube Length Microscope* on p. 34). Field number varies with microscopy vendors and eyepiece magnification. For 10× or lower magnification eyepieces, it is usually 20–28 mm while for higher magnification, wide-angle oculars can get down to approximately 5 mm.

The majority of eyepieces are **Huygens**, **Ramsden**, or derivations of them. The Huygens eyepiece consists of two plano-convex lenses with convex surfaces facing the microscope objective:



Eyepieces (cont.)

Both lenses are usually made with crown glass and allow for some correction of lateral color, coma, and astigmatism. To correct for color, the following conditions should be met:

$$f_1 \approx f_2 \quad \text{and} \quad t \approx 1.5 f_2 \,.$$

For higher magnifications, the exit pupil moves toward the ocular, making observation less convenient, and so this eyepiece is used only for low magnifications (≤10×). In addition, Huygens oculars effectively correct for chromatic aberrations, and therefore can be more effectively used with lower-end microscope objectives (e.g., achromatic).

The Ramsden eyepiece consists of two plano-convex lenses with convex surfaces facing each other. Both focal lengths are very similar, and the distance between lenses is smaller than f_2:



The field stop is placed in the front focal plane of the eyepiece. A collective lens does not participate in creating an intermediate image, so the Ramsden eyepiece works as a simple magnifier:

$$f_1 = f_2 \quad \text{and} \quad t < f_2 \,.$$

Compensating eyepieces work in conjunction with microscope objectives to correct for lateral color (apochromatic).

High-eye point oculars provide an extended distance between the last mechanical surface and the exit pupil of the eyepiece. They allow users with glasses to comfortably use a microscope. The convenient high eye-point location should be 20–25 mm behind the eyepiece.

Nomenclature and Marking of Objectives

Objective parameters include:

Objective correction—such as Achromat, Plan Achromat, Fluor, Plan Fluor, Apochromat (Apo), and Plan Apochromat.

Magnification	Zeiss Code
1×, 1.25×	Black
2.5×	Khaki
4×, 5×	Red
6.3×	Orange
10×	Yellow
16×, 20×, 25×, 32×	Green
25×, 32×	Green
40×, 50×	Light Blue
63×	Dark Blue
> 100×	White

Magnification—the lens magnification for a finite tube length, or for a microscope objective in combination with a tube lens. In infinity-corrected systems, magnification depends on the ratio between the focal lengths of a tube lens and a microscope objective. A particular objective type should be used only in combination with the proper tube lens.

Application—specialized use or design of an objective, e.g., H (bright field), D (dark field), DIC (differential interference contrast), RL (reflected light), PH (phase contrast), or P (polarization).


Magnification
Application
Optical Tube Length (mm)
Coverslip Thickness (mm)
MAKER
PLAN Fluor
40x / 1.3 Oil
DIC H
160/0 17 WD 0 20
Objective Maker
Objective Type
Numerical Aperture and Medium
Working Distance (mm)
Magnification Color-Coded Ring

Tube length—an infinity corrected (∞) or finite tube length in mm.

Cover slip—the thickness of the cover slip used (in mm). “0” or “–” means no cover glass or the cover slip is optional, respectively.

Numerical aperture (NA) and medium—defines system throughput and resolution. It depends on the media between the sample and objective. The most common media are air (no marking), oil (Oil), water (W), or Glycerine.

Working distance (WD)—the distance in millimeters between the surface of the front objective lens and the object.

Objective Designs

Achromatic objectives (also called **achromats)** are corrected at two wavelengths: 656 nm and 486 nm. Also, spherical aberration and coma are corrected for green (546 nm), while astigmatism is very low. Their major problems are a secondary spectrum and field curvature.

Achromatic objectives are usually built with a lower NA (below 0.5) and magnification (below 40×). They work well for white light illumination or single wavelength use. When corrected for field curvature, they are called plan-achromats.

Achromatic Objectives



Fluorites or **semi-apochromats** have similar color correction as **achromats**; however, they correct for spherical aberration for two or three colors. The name “fluorites” was assigned to this type of objective due to the materials originally used to build this type of objective. They can be applied for higher NA (e.g., 1.3) and magnifications, and used for applications like immunofluorescence, polarization, or differential interference contrast microscopy.

The most advanced microscope objectives are **apochromats**, which are usually chromatically corrected for three colors, with spherical aberration correction for at least two colors. They are similar in construction to fluorites but with different thicknesses and surface figures. With the correction of field curvature, they are called plan-apochromats. They are used in fluorescence microscopy with multiple dyes and can provide very high NA (1.4). Therefore, they are suitable for low-light applications.

Objective Designs (cont.)


Apochromatic Objectives
Low NA
Low M
NA = 0.3
10x
NA = 0.95
50x
NA = 1.4
100x
Fluorite Glass
Immersion Liquid
Object Plane
Amici Lens

Type	Number of wavelengths for spherical correction	Number of colors for chromatic correction
Achromat	1	2
Fluorite	2–3	2–3
Plan-Fluorite	2–4	2–4
Plan-Apochromat	2–4	3–5

(Adapted from Murphy, 2001 and http://www.microscopyu.com/)

Examples of typical objective parameters are shown in the table below:

M	Type	Medium	*WD*	NA	*d*	DOF
10	Achromat	Air	4.4	0.25	1.34	8.80
20	Achromat	Air	0.53	0.45	0.75	2.72
40	Fluorite	Air	0.50	0.75	0.45	0.98
40	Fluorite	Oil	0.20	1.30	0.26	0.49
60	Apochromat	Air	0.15	0.95	0.35	0.61
60	Apochromat	Oil	0.09	1.40	0.24	0.43
100	Apochromat	Oil	0.09	1.40	0.24	0.43
Refractive index of oil is $n = 1.515$						

(Adapted from Murphy, 2001)

Special Objectives and Features

Special types of objectives include long working distance objectives, ultra-low-magnification objectives, water-immersion objectives, and UV lenses.

Long working distance objectives allow imaging through thick substrates like culture dishes. They are also developed for interferometric applications in Michelson and Mirau configurations. Alternatively, they can allow for the placement of instrumentation (e.g., micropipettes) between a sample and an objective. To provide a long working distance and high NA, a common solution is to use reflective objectives, or extend the working distance of a standard microscope objective by using a reflective attachment. While reflective objectives have the advantage of being free of chromatic aberrations, their serious drawback is a smaller field of view relative to refractive objectives. The central obscuration also decreases throughput by 15%–20%.

LWD Reflective Objective



Special Objectives and Features (cont.)

Low magnification objectives can achieve magnifications as low as 0.5. However, in some cases they are not fully compatible with microscopy systems, and may not be telecentric in the image space. They also often require special tube lenses and special condensers to provide Köhler illumination.

Water immersion objectives are increasingly common, especially for biological imaging, because they provide a high NA and avoid toxic immersion oils. They usually work without a cover slip.

UV objectives are made using UV transparent, low-dispersion materials such as quartz. These objectives enable imaging at wavelengths from the near-UV through the visible spectrum, e.g., 240–700 nm. Reflective objectives can also be used for the IR bands.



Reflective Adapter to extend working distance WD

Special Lens Components

The **Bertrand lens** is a focusable eyepiece telescope that can be easily placed in the light path of the microscope. This lens is used to view the back aperture of the objective, which simplifies microscope alignment, specifically when setting up Köhler illumination.

To construct a high-numerical-aperture microscope objective with good correction, numerous optical designs implement the **Amici lens** as a first component of the objective. It is a thick lens placed in close proximity to the sample. An Amici lens usually has a plane (or nearly plane) first surface and a large-curvature spherical second surface. To ensure good chromatic aberration correction, an achromatic lens is located closely behind the Amici lens. In such configurations, microscope objectives usually reach an NA of 0.5–0.7.

To further increase the NA, an Amici lens is improved by either cementing a high-refractive-index meniscus lens to it or placing a meniscus lens closely behind the Amici lens. This makes it possible to construct well-corrected high magnification (100×) and high numerical aperture (NA > 1.0) oil-immersion objective lenses.


Amici-Type microscope objective
NA = 0.50-0.80
20x - 40x
Amici Lens
Achromatic Lens 1
Achromatic Lens 2


Amici Lens with cemented meniscus lens
Amici Lens with Meniscus Lens closely behind

Cover Glass and Immersion

The **cover slip** is located between the object and the microscope objective. It protects the imaged sample and is an important element in the optical path of the microscope. Cover glass can reduce imaging performance and cause spherical aberration, while different imaging angles experience movement of the object point along the optical axis toward the microscope objective. The object point moves closer to the objective with an increase in angle.



The importance of the cover glass increases in proportion to the objective's NA, especially in high-NA dry lenses. For lenses with an NA smaller than 0.5, the type of cover glass may not be a critical parameter, but should always be properly used to optimize imaging quality. Cover glasses are likely to be encountered when imaging biological samples. Note that the presence of a standard-thickness cover glass is accounted for in the design of high-NA objectives. The important parameters that define a cover glass are its thickness, index of refraction, and Abbe number. The ISO standards for refractive index and Abbe number are $n = 1.5255 \pm 0.0015$ and $V = 56 \pm 2$, respectively.

Microscope objectives are available that can accommodate a range of cover-slip thicknesses. An adjustable collar allows the user to adjust for cover slip thickness in the range from 100 microns to over 200 microns.

Cover Glass Grade Number	Thickness (in microns)
0	83–130
1	130–160
1.5	160–190
2	190–250

Cover Glass and Immersion (cont.)

The table below presents a summary of acceptable cover glass thickness deviations from 0.17 mm and the allowed thicknesses for Zeiss air objectives with different NAs.

NA of the Objective	Allowed Thickness Deviations (from 0.17 mm)	Allowed Thickness Range
<0.3	–	0.000–0.300
0.30–0.45	0.07	0.100–0.240
0.45–0.55	0.05	0.120–0.220
0.55–0.65	0.03	0.140–0.200
0.65–0.75	0.02	0.150–0.190
0.75–0.85	0.01	0.160–0.180
0.85–0.95	0.005	0.165–0.175

(Adapted from Pluta, 1988)

To increase both the microscope's resolution and system throughput, immersion liquids are used between the cover-slip glass and the microscope objective, or directly between the sample and objective. An **immersion liquid** effectively increases the NA and decreases the angle of refraction at the interface between the medium and the microscope objective. Common immersion liquids include oil ($n = 1.515$), water ($n = 1.34$), and glycerin ($n = 1.48$).



Water, which is more common, or glycerin immersion objectives are mainly used for biological samples, such as living cells or a tissue culture. They provide a slightly lower NA than oil objectives but are free of the toxicity associated with immersion oils. Water immersion is usually applied without a cover slip. For fluorescent applications it is also critical to use non-fluorescent oil.

Common Light Sources for Microscopy

Common light sources for microscopy include **incandescent lamps**, such as tungsten-argon and tungsten (e.g., quartz halogen) lamps. A **tungsten-argon lamp** is primarily used for bright-field, phase-contrast, and some polarization imaging. **Halogen lamps** are inexpensive and a convenient choice for a variety of applications that require a continuous and bright spectrum.

Arc lamps are usually brighter than incandescent lamps. The most common examples include xenon (XBO) and mercury (HBO) arc lamps. Arc lamps provide high-quality monochromatic illumination if combined with the appropriate filter. Arc lamps are more difficult to align, are more expensive, and have a shorter lifetime. Their spectral range starts in the UV range and continuously extends through visible to the infrared. About 20% of the output is in the visible spectrum, while the majority is in the UV and IR. The usual lifetime is 100–200 hours.

Common Mercury Lines	
Wavelength [nm]	**Color**
254	Far UV
366	Near UV
405	Violet
435	Deep Blue
546	Yellow-green
578	Yellow doublet

Another light source is the **gas-arc discharge lamp**, which includes mercury, xenon, and halide lamps. The **mercury lamp** has several strong lines, which might be 100 times brighter than the average output. About 50% is located in the UV range, and should be used with protective glasses. For imaging biological samples, the proper selection of filters is necessary to protect living cell samples and micro-organisms (e.g., UV-blocking filters/cold mirrors). The xenon arc lamp has a uniform spectrum, can provide an output power greater than 100 W, and is often used for fluorescence imaging. However, over 50% of its power falls into the IR; therefore, IR-blocking filters (hot mirrors) are necessary to prevent the overheating of samples.

Metal halide lamps were recently introduced as high-power sources (over 150 W) with lifetimes several times longer than arc lamps. While in general the metal-halide lamp has a spectral output similar to that of a mercury arc lamp, it extends further into longer wavelengths.

LED Light Sources

Light-emitting diodes (LEDs) are a new, alternative light source for microscopy applications. The LED is a semiconductor diode that emits photons when in forward-biased mode. Electrons pass through the depletion region of a p-n junction and lose an amount of energy equivalent to the bandgap of the semiconductor. The characteristic features of LEDs include a long lifetime, a compact design, and high efficiency. They also emit narrowband light with relatively high energy.

Wavelengths [nm] of High-power LEDs Commonly Used in Microscopy		**Total Beam Power [mW] (approximate)**
455	Royal Blue	225–450
470	Blue	200–400
505	Cyan	150–250
530	Green	100–175
590	Amber	15–25
633	Red	25–50
435–675	White Light	200–300

An important feature of LEDs is the ability to combine them into arrays and custom geometries. Also, LEDs operate at lower temperatures than arc lamps, and due to their compact design they can be cooled easily with simple heat sinks and fans.

The radiance of currently available LEDs is still significantly lower than that possible with arc lamps; however, LEDs can produce an acceptable fluorescent signal in bright microscopy applications. Also, the pulsed mode can be used to increase the radiance by 20 times or more.

LED Spectral Range [nm]	**Semiconductor**
350–400	GaN
400–550	$In_{1-x}Ga_xN$
550–650	$Al_{1-x-y}In_yGa_xP$
650–750	$Al_{1-x}Ga_xAs$
750–1000	$GaAs_{1-x}P_x$

Filters

Neutral density (ND) filters are neutral (wavelength wise) gray filters scaled in units of **optical density** (OD):

$$OD = \log_{10}\left(\frac{1}{\tau}\right),$$

where τ is the transmittance. ND filters can be combined to provide OD as a sum of the ODs of the individual filters. ND filters are used to change light intensity without tuning the light source, which can result in a spectral shift.



Color **absorption filters** and **interference filters** (also see *Multiple Wave Interference* on page 16) isolate the desired range of wavelengths: e.g. bandpass and edge filters.

Edge filters include short-pass and long-pass filters. Short-pass filters allow short wavelengths to pass and stop long wavelengths, and long-pass filters allow long wavelengths to pass while stopping short wavelengths. Edge filters are defined for wavelengths with a 50% drop in transmission.

Bandpass filters allow only a selected spectral bandwidth to pass and are characterized with a central wavelength and full-width-half-maximum (FWHM) defining the spectral range for transmission of at least 50%.

Color absorption glass filters usually serve as broad bandpass filters. They are less costly and less susceptible to damage than interference filters.

Interference filters are based on multiple beam interference in thin films. They combine between three to over 20 dielectric layers of $\lambda/2$ and $\lambda/4$, separated by metallic coatings. They can provide a sharp bandpass transmission down to the sub-nm range and full-width-half-maximum of 10–20 nm.

Polarizers and Polarization Prisms

Polarizers are built with birefringent crystals using polarization at multiple reflections, selective absorption (dichroism), form birefringance, or scattering.

For example, polarizers built with birefringent crystals (Glan-Thompson prisms) use the principle of total internal reflection to eliminate ordinary or extraordinary components (for positive or negative crystals).


Glan-Thompson Prism
Extraordinary Ray
Optic Axis
Optic Axis
Ordinary Ray under TIR

Birefringent prisms are crucial components for numerous microscopy techniques, e.g., differential interference contrast. The most common birefringent prism is a **Wollaston prism**. It splits light into two beams with orthogonal polarization and propagates under different angles.

The angle between propagating beams is

$$\varepsilon = 2\left|n_e - n_o\right|\tan\alpha \,.$$

Both beams produce interference with fringe period *b*:

$$b = \frac{\lambda}{\varepsilon} = \frac{\lambda}{2\left|n_e - n_o\right|\tan\alpha} \,.$$

The localization plane of fringes is

$$\gamma = \frac{1}{2}\left(\frac{1}{n_e} + \frac{1}{n_o}\right)\alpha \,.$$


Wollaston Prism
ε
ε
α
γ
Optic Axis
Optic Axis
Illumination Light
Linearly Polarized at 45°

Polarizers and Polarization Prisms (cont.)

The fringe localization plane tilt can be compensated by using two symmetrical Wollaston prisms.


Two Wollaston Prisms
compensate for tilt of fringe
localization plane
Incident
Light

Wollaston prisms have a fringe localization plane inside the prism. One example of a modified Wollaston prism is the **Nomarski prism**, which simplifies the DIC microscope setup by shifting the plane outside the prism, i.e., the prism does not need to be physically located at the condenser front focal plane or the objective's back focal plane.


Nomarski Prism
α
β
α
Fringe Localization
Plane
Incident
Light

Amplitude and Phase Objects

The major object types encountered on the microscope are **amplitude** and **phase** objects. The type of object often determines the microscopy technique selected for imaging.



The amplitude object is defined as one that changes the amplitude and therefore the intensity of transmitted or reflected light. Such objects are usually imaged with bright-field microscopes. A stained tissue slice is a common amplitude object.

Phase objects do not affect the optical intensity; instead, they generate a phase shift in the transmitted or reflected light. This phase shift usually arises from an inhomogeneous refractive index distribution throughout the sample, causing differences in optical path length (OPL). Mixed amplitude-phase objects are also possible (e.g., biological media), which affect the amplitude and phase of illumination in different proportions.

Classifying objects as **self-luminous** and **non-self-luminous** is another way to categorize samples. Self-luminous objects generally do not directly relate their amplitude and phase to the illuminating light. This means that while the observed intensity may be proportional to the illumination intensity, its amplitude and phase are described by a statistical distribution (e.g., fluorescent samples). In such cases, one can treat discrete object points as secondary light sources, each with their own amplitude, phase, coherence, and wavelength properties.

Non-self-luminous objects are those that affect the illuminated beam in such a manner that discrete object points cannot be considered as entirely independent. In such cases, the wavelength and temporal coherence of the illuminating source needs to be considered in imaging. A diffusive or absorptive sample is an example of such an object.

The Selection of a Microscopy Technique

Microscopy provides several imaging principles. Below is a list of the most common techniques and object types:

Technique	Type of sample
Bright-field	Amplitude specimens, reflecting specimens, diffuse objects
Dark-field	Light-scattering objects
Phase contrast	Phase objects, light-scattering objects, light-refracting objects, reflective specimens
Differential interference contrast (DIC)	Phase objects, light-scattering objects, light-refracting objects, reflective specimens
Polarization microscopy	Birefringent specimens
Fluorescence microscopy	Fluorescent specimens
Laser scanning, Confocal microscopy, and Multi-photon microscopy	3D samples requiring optical sectioning, fluorescent and scattering samples
Super-resolution microscopy (**RESOLFT**, **4Pi**, **I^{5}M**, **SI**, **STORM**, **PALM**, and others)	Imaging at the molecular level; imaging primarily focuses on fluorescent samples where the sample is a part of an imaging system
Raman microscopy, **CARS**	Contrast-free chemical imaging
Array microscopy	Imaging of large FOVs
SPIM	Imaging of large 3D samples
Interference Microscopy	Topography, refractive index measurements, 3D coherence imaging

All of these techniques can be considered for transmitted or reflected light. Below are examples of different sample types:

Sample type	Sample Example
Amplitude specimens	Naturally colored specimens, stained tissue
Specular specimens	Mirrors, thin films, metallurgical samples, integrated circuits
Diffuse objects	Diatoms, fibers, hairs, micro-organisms, minerals, insects
Phase objects	Bacteria, cells, fibers, mites, protozoa
Light-refracting samples	Colloidal suspensions, minerals, powders
Birefringent specimens	Mineral sections, crystallized chemicals, liquid crystals, fibers, single crystals
Fluorescent specimens	Cells in tissue culture, fluorochrome-stained sections, smears and spreads

(Adapted from www.microscopyu.com)

Image Comparison

The images below display four important microscope modalities: **bright field**, **dark field**, **phase contrast**, and **differential interference contrast**. They also demonstrate the characteristic features of these methods. The images are of a blood specimen viewed with the Zeiss upright Axiovert Observer Z1 microscope. The microscope was set with an objective at 40×, NA = 0.6, Ph2, LD Plan Neofluor, and a cover slip glass of 0.17 mm. The pictures were taken with a monochromatic CCD camera.

 Bright Field	 Dark Field
 Phase Contrast	 Differential Interference Contrast (DIC)

The bright-field image relies on absorption and shows the sample features with decreasing amounts of passing light. The dark-field image only shows the scattering sample components. Both the phase contrast and the differential interference contrast demonstrate the optical thickness of the sample. The characteristic halo effect is visible in the phase-contrast image. The 3D effect of the DIC image arises from the differential character of images; they are formed as a derivative of the phase changes in the beam as it passes through the sample.

Phase Contrast

Phase contrast is a technique used to visualize phase objects by phase and amplitude modifications between the direct beam propagating through the microscope and the beam diffracted at the phase object. An object is illuminated with monochromatic light, and a phase-delaying (or advancing) element in the aperture stop of the objective introduces a phase shift, which provides interference contrast. Changing the amplitude ratio of the diffracted and non-diffracted light can also increase the contrast of the object features.


Image Plane
Direct Beam
Diffracted Beam
Phase Plate
F'_{ob}
Aperture Stop
Microscope Objective
Surrounding Media (n_m)
Phase Object (n_{po})
Condenser Lens
Diaphragm
Light Source

Phase Contrast (cont.)

Phase contrast is primarily used for imaging living biological samples (immersed in a solution), unstained samples (e.g., cells), thin film samples, and mild phase changes from mineral objects. In that regard, it provides qualitative information about the optical thickness of the sample. Phase contrast can also be used for some quantitative measurements, like an estimation of the refractive index or the thickness of thin layers. Its phase detection limit is similar to the **differential interference contrast** and is approximately $\lambda/100$. On the other hand, phase contrast (contrary to DIC) is limited to thin specimens, and phase delay should not exceed the depth of field of an objective. Other drawbacks compared to DIC involve its limited optical sectioning ability and undesired effects like halos or shading-off. (See also *Characteristic Features of Phase Contrast Microscopy* on page 71).

The most important advantages of phase contrast (over DIC) include its ability to image birefringent samples and its simple and inexpensive implementation into standard microscopy systems.

Presented below is a mathematical description of the phase contrast technique based on a vector approach. The phase shift in the figure (See page 68) is represented by the orientation of the vector. The length of the vector is proportional to amplitude of the beam. When using standard imaging on a transparent sample, the length of the light vectors passing through sample PO and surrounding media SM is the same, which makes the sample invisible. Additionally, vector PO can be considered as a sum of the vectors passing through surrounding media SM and diffracted at the object DP.

$$PO = SM + DP$$

If the wavefront propagating through the surrounding media can be the subject of an exclusive phase change (diffracted light DP is not affected), the vector SM is rotated by an angle corresponding to the phase change. This exclusive phase shift is obtained with a small circular or ring phase plate located in the plane of the aperture stop of a microscope.

Phase Contrast (cont.)

Consequently, vector PO, which represents light passing through a phase sample, will change its value to PO' and provide contrast in the image:

$$PO' = SM' + DP,$$

where SM' represents the rotated vector SM.


DP
SM′
PO′
PO
φp
φ
DP
SM
Phase Shift to Direct Light
Introduced by
Advancing Phase Plate
Phase Advancing Object
DP
SM′
PO′
φp
SM
φ
DP
PO
Vector for light passing through
Surrounding Media (SM)
Vector for Light Diffracted
at the Phase Object (DP)
Vector for light passing through
Phase Object (PO)
Phase Retardation Introduced
by Phase Object
Phase Retarding Object

Phase samples are considered to be **phase retarding objects** or **phase advancing objects** when their refractive index is greater or less than the refractive index of the surrounding media, respectively.

Phase plate	Object Type	Object Appearance
$\varphi_p = +\pi/2$ ($+90^{o}$)	phase-retarding	brighter
$\varphi_p = +\pi/2$ ($+90^{o}$)	phase-advancing	darker
$\varphi_p = -\pi/2$ (-90^{o})	phase-retarding	darker
$\varphi_p = -\pi/2$ (-90^{o})	phase-advancing	brighter

Visibility in Phase Contrast

Visibility of features in **phase contrast** can be expressed as

$$C_{\text{ph}} = \frac{I_{\text{media}} - I_{\text{object}}}{I_{\text{media}}} = \frac{|SM'|^2 - |PO'|^2}{|SM'|^2}.$$



This equation defines the phase object's visibility as a ratio between the intensity change due to phase features and the intensity of surrounding media $|SM'|^2$. It defines the negative and positive contrast for an object appearing brighter or darker than the media, respectively. Depending on the introduced phase shift (positive or negative), the same object feature may appear with a **negative** or **positive contrast**. Note that C_{ph} relates to classical contrast C as

$$C = \frac{I_{\max} - I_{\min}}{I_{\max} + I_{\min}} = \frac{|I_1 - I_2|}{I_1 + I_2} = |C_{\text{ph}}| \frac{|SM'|^2}{|SM'|^2 + |PO'|^2}.$$

Contrast	Phase Plate
-2φ	$\varphi_p = +\pi/2$ (+90°)
$+2\varphi$	$\varphi_p = -\pi/2$ (–90°)

For phase changes in the 0–2π range, intensity in the image can be found using vector relations; small phase changes in the object $\varphi << 90$ deg can be approximated as $\pm 2\varphi$.

To increase the contrast of images, the intensity in the direct beam is additionally changed with beam attenuation τ in the phase ring. τ is defined as a transmittance, $\tau = 1/N$, where N is a dividing coefficient of intensity in a direct beam (intensity is decreased N times). The contrast in this case is

$$C_{\text{ph}} = -2\varphi / \sqrt{\tau} = -2\varphi\sqrt{N}$$

for a +π/2 phase plate, and

$$C_{\text{ph}} = +2\varphi / \sqrt{\tau} = +2\varphi\sqrt{N}$$

for –π/2 phase plate. The minimum perceived phase difference with phase contrast is

$$\Delta\varphi_{\min} = \frac{C_{\text{ph}-\min}\lambda}{4\pi\sqrt{N}}.$$

$C_{\text{ph}-\min}$ is usually accepted at the contrast value of 0.02.

The Phase Contrast Microscope


Intermediate Image Plane
Direct Beams
Diffracted Beam
Phase Ring
Aperture Stop
F_{ob}
Microscope Objective
Surrounding Media (n_m)
Phase Object (n_{po})
Condenser Lens
Annular Aperture
Field Diaphragm
Collective Lens
Bulb

The common phase-contrast system is similar to the bright-field microscope but with two modifications:

1. The condenser diaphragm is replaced with an annular aperture diaphragm.
2. A ring-shaped phase plate is introduced at the back focal plane of the microscope objective. The ring may include metallic coatings, typically providing 75% to 90% attenuattion of the direct beam.

Both components are in conjugate planes and are aligned such that the image of the annular condenser diaphragm overlaps with the objective phase ring. While there is no direct access to the objective phase ring, the anular aperture in front of the condenser is easily accessible.

The phase shift introduced by the ring is given by

$$\varphi_{\mathrm{p}} = 2\pi\frac{OPD}{\lambda} = \frac{2\pi}{\lambda}\left(n_{\mathrm{m}} - n_{\mathrm{r}}\right)t\,,$$

where n_{m} and n_{r} are refractive indices of the media surrounding the phase ring and the ring itself, respectively. t is the physical thickness of the phase ring.


Phase Contrast Objectives
NA = 0.25
10x
NA = 0.4
20x
NA = 1.25 oil
100x
Phase Rings
Object Plane

Characteristic Features of Phase Contrast



Images in phase contrast are dark or bright features on a background (positive and negative contrast, respectively). They contain undesired image effects called halo and shading-off, which are a result of the incomplete separation of direct and diffracted light. The **halo effect** is a phase contrast feature that increases light intensity around sharp changes in the phase gradient.


Object
Top View
Cross Section
n
n1 > n
Positive Phase Contrast
Image
Negative Phase Contrast
Intensity in cross section of an image
Image with Halo and Shading-off
Ideal Image
Halo Effect
Shading-off Effect

The **shading-off effect** is an increase or decrease (for dark or bright images, respectively) of the intensity of the phase sample feature.


NA and Magnification Increase

Both effects strongly increase with an increase in numerical aperture and magnification. They can be reduced by surrounding the sides of a phase ring with ND filters.

Lateral resolution of the phase contrast technique is affected by the annular aperture (the radius of phase ring r_{PR}) and the aperture stop of the objective (the radius of aperture stop is r_{AS}). It is

$$d = f'_{\text{objective}} \frac{\lambda}{(r_{\text{AS}} + r_{\text{PR}})},$$

compared to the resolution limit for a standard microscope:

$$d = f'_{\text{objective}} \frac{\lambda}{r_{\text{AS}}}.$$


Aperture Stop
Phase Ring
r_{PR}
r_{AS}

Amplitude Contrast

Amplitude contrast changes the contrast in the images of absorbing samples. It has a layout similar to phase contrast; however, there is no phase change introduced by the object. In fact, in many cases a phase-contrast microscope can increase contrast based on the principle of amplitude contrast. The visibility of images is modified by changing the intensity ratio between the direct and diffracted beams.


Intermediate Image Plane
Direct Beams
Diffracted Beam
Attenuating Ring
Aperture Stop
F_ob
Microscope Objective
Amplitude or Scattering Object
Condenser Lens
Annular Aperture
Field Diaphragm
Collective Lens
Bulb

A vector schematic of the technique is as follows:


Vector for light passing through **S**urrounding **M**edia (**SM**)
SM
DA
AO
Object
Vector for Light **D**iffracted at the **A**mplitude Object (**DA**)
Vector for light passing through **A**mplitude **O**bject (**AO**)

Similar to visibility in phase contrast, image contrast can be described as a ratio of the intensity change due to amplitude features surrounding the media's intensity:

$$C_{\mathrm{ac}} = \frac{I_{\mathrm{media}} - I_{\mathrm{object}}}{I_{\mathrm{media}}} = \frac{2|SM||DA| - |DA|^2}{|SM|^2}.$$

Since the intensity of diffraction for amplitude objects is usually small, the contrast equation can be approximated with $C_{\mathrm{ac}} = 2|DA|/|SM|$. If a direct beam is further attenuated, contrast C_{ac} will increase by factor of $N^{-1} = 1/\tau^{-1}$.

Oblique Illumination

Oblique illumination (also called **anaxial illumination**) is used to visualize phase objects. It creates pseudo-profile images of transparent samples. These reliefs, however, do not directly correspond to the actual surface profile.

The principle of oblique illumination can be explained by using either refraction or diffraction and is based on the fact that sample features of various spatial frequencies will have different intensities in the image due to a nonsymmetrical system layout and the filtration of spatial frequencies.



In practice, oblique illumination can be achieved by obscuring light exiting a condenser; translating the sub-stage diaphragm of the condenser lens does this easily.

The advantage of oblique illumination is that it improves spatial resolution over Köhler illumination (up to two times). This is based on the fact that there is a larger angle possible between the 0th and 1st orders diffracted at the sample for oblique illumination. In Köhler illumination, due to symmetry, the 0th and –1st orders at one edge of the stop will overlap with the 0th and +1st order on the other side. However, the gain in resolution is only for one sample direction; to examine the object features in two directions, a sample stage should be rotated.

Modulation Contrast

Modulation contrast microscopy (MCM) is based on the fact that phase changes in the object can be visualized with the application of multilevel gray filters.

The intensities of light refracted at the object are displayed with different values since they pass through different zones of the filter located in the stop of the microscope. MCM is often configured for oblique illumination since it already provides some intensity variations for phase objects. Therefore, the resolution of the MCM changes between normal and oblique illumination.

MCM can be obtained through a simple modification of a bright-field microscope by adding a slit diaphragm in front of the condenser and amplitude filter (also called the modulator) in the aperture stop of the microscope objective. The modulator filter consists of three areas: 100% (bright), 15% (gray), and 1% (dark). This filter acts in a similar way to the knife-edge in the Schlieren imaging techniques.


1%
15%
100%
Modulator Filter
F_{ob}
Aperture Stop
Microscope Objective
Phase Object
Condenser Lens
Slit Diaphragm

Hoffman Contrast

A specific implementation of MCM is **Hoffman modulation contrast**, which uses two additional polarizers located in front of the slit aperture. One polarizer is attached to the slit and obscures 50% of its width. A second can be rotated, which provides two intensity zones in the slit (for crossed polarizers, half of the slit is dark and half is bright; the entire slit is bright for the parallel position).

The major advantages of this technique include imaging at a full spatial resolution and a minimum depth of field, which allows optical sectioning. The method is inexpensive and easy to implement. The main drawback is that the images deliver a pseudo-relief image, which cannot be directly correlated with the object's form.


Intermediate Image Plane
Modulator Filter
Aperture Stop
F_{ob}
Microscope Objective
Phase Object
Condenser Lens
Slit Diaphragm
Polarizers

Dark Field Microscopy

In **dark-field microscopy**, the specimen is illuminated at such angles that direct light is not collected by the microscope objective. Only diffracted and scattered light are used to form the image.

The key component of the dark-field system is the condenser. The simplest approach uses an annular condenser stop and a microscope objective with an NA below that of the illumination cone. This approach can be used for objectives with NA < 0.65. Higher-NA objectives may incorporate an adjustable iris to reduce their NA below 0.65 for dark-field imaging. To image at a higher NA, specialized reflective dark-field condensers are necessary. Examples of such condensers include the **cardioid** and **paraboloid** designs, which enable dark-field imaging at an NA up to 0.9–1.0 (with oil immersion).

For dark-field imaging in epi-illumination, objective designs consist of external illumination, and internal imaging paths are used.


PLAN Fluor
40x / 0.65
D
/0 17 WD 0 50
Illumination
Scattered Light
Dark Field
Condenser


Scattered Light
Illumination
Cardioid
Condenser


Scattered Light
Illumination
Paraboloid
Condenser


Illumination
Scattered Light

Optical Staining: Rheinberg Illumination

Optical staining is a class of techniques that uses optical methods to provide color differentiation between different areas of a sample**.**

Common Color Combinations	
Inner Filter	Annular Filter
Violet	Red
Blue	Yellow-Orange
Green	Red

Rheinberg illumination is a modification of dark-field illumination. Instead of an annular aperture, it uses two-zone color filters located in the front focal plane of the condenser. The overall diameter of the outer annular color filter is slightly greater than that corresponding to the NA of the system:

$$2r_{\lambda 2} > 2NAf'_{\text{condenser}} \, .$$

To provide good contrast between scattered and direct light, the inner filter is darker. Rheinberg illumination provides images that are a combination of two colors. Scattering features in one color are visible on the background of the other color.


Direct Light for λ2
Direct Light for λ1 and Scattered Light for λ2
λ1 Illumination
Condenser
λ2 Illumination
Full Spectrum
Interference Filter - λ1
Interference Filter - λ2
$r_{\lambda 1}$
$r_{\lambda 2}$

Color-stained images can also be obtained in a simplified setup where only one (inner) filter is used. For such an arrangement, images will present white-light scattering features on the colored background. Other deviations from the above technique include double illumination where transmittance and reflectance are separated into two different colors.

Optical Staining: Dispersion Staining



Dispersion staining is based on using highly dispersive media that matches the refractive index of the phase sample for a single wavelength λ_m (the matching wavelength). The system is configured in a setup similar to dark-field or oblique illumination. Wavelengths close to the matching wavelength will miss the microscope objective, while the other will refract at the object and create a colored dark-field image. Various configurations include illumination with a dark-field condenser and an annular aperture or central stop at the back focal plane of the microscope objective.

Color	λ Range [nm]	λ Mean [nm]
Violet	400–450	440
Blue	450–480	470
Blue-Green	480–510	495
Green	510–550	530
Green-Yellow	550–570	560
Yellow	570–590	580
Orange	590–630	605
Red	630–700	650

(Adapted from Pluta, 1989)

The annular-stop technique uses low-magnification (10×) objectives with a stop built as an opaque screen with a central opening, and is used for bright-field dispersion staining. The annular stop absorbs red and blue wavelengths and allows yellow through the system. A sample appears as white with yellow borders. The image background is also white.

The central-stop system absorbs unrefracted yellow light and direct white light. Sample features show up as purple (a mixture of red and blue) borders on a dark background. Different media and sample types will modify the color's appearance.


Direct Light for λ_m
Sample Particles
Scattered Light for $\lambda > \lambda_m$ and $\lambda < \lambda_m$
Condenser
High Dispersion Liquid
Full Spectrum

Shearing Interferometry: The Basis for DIC

Differential interference contrast (DIC) microscopy is based on the principles of shearing interferometry. Two wavefronts propagating through an optical system containing identical phase distributions (introduced by the sample) are slightly shifted to create an interference pattern. The phase of the resulting fringes is directly proportional to the derivative of the phase distribution in the object, hence the name "differential." Specifically, the intensity of the fringes relates to the derivative of the phase delay through the object (φ_o) and the local delay between wavefronts (Δ_b):

$$I \propto I_{\max} \cos^2\left(\Delta_b \pm \Delta\varphi_o\right)$$

or

$$I \propto I_{\max} \cos^2\left(\Delta_b \pm s\frac{d\varphi_o}{dx}\right),$$

where s denotes the shear between wavefronts, and Δ_b is the axial delay.


Sheared Wavefronts

Sheared and Delayed

Sheared and Tilted



Wavefront shear is commonly introduced in DIC microscopy by incorporating a Mach-Zehnder interferometer into the system (e.g., Zeiss) or by the use of birefringent prisms. The appearance of DIC images depends on the sample orientation with respect to the shear direction.

DIC Microscope Design

The most common **differential interference contrast** (**Nomarski DIC**) design uses two **Wollaston** or **Nomarski birefringent prisms**. The first prism splits the wavefront into ordinary and extraordinary components to produce interference between these beams. Fringe localization planes for both prisms are in conjugate planes. Additionally, the system uses a crossed polarizer and analyzer. The polarizer is located in front of prism I, and the analyzer is behind prism II. The polarizer is rotated by 45 deg with regard to the shear axes of the prisms.

If prism II is centrally located, the intensity in the image is

$$I \propto \sin^2\left(\frac{\pi s \dfrac{d\varphi_o}{dx}}{\lambda}\right).$$

For a translated prism, phase **bias** Δ_b is introduced, and the intensity is proportional to

$$I \propto \sin^2 \frac{\pi\left(\Delta_b \pm s\dfrac{d\varphi_o}{dx}\right)}{\lambda}.$$

The sign in the equation depends on the direction of the shift. Shear s is

$$s = \frac{s'}{M_{\text{objective}}} = \varepsilon\frac{OTL}{M_{\text{objective}}},$$



where ε is the angular shear provided by the birefringent prisms, s' is the shear in the image space, and OTL is the optical tube length. The high spatial coherence of the source is obtained by the slit located in front of the condenser and oriented perpendicularly to the shear direction. To assure good interference contrast, the width of the slit w should be

$$w = \frac{\lambda f'_{\text{condenser}}}{4s}.$$

Low-strain (low-birefringence) objectives are crucial for high-quality DIC.

Appearance of DIC Images

In practice, shear between wavefronts in **differential interference contrast** is small and accounts for a fraction of a fringe period. This provides the differential character of the phase difference between interfering beams introduced to the interference equation.


Shear Direction
Shear Direction
Shear Direction
Shear Direction
Intensity
Intensity
Intensity
Intensity
Bias + dOPL/dx
Bias + dOPL/dx
Bias + dOPL/dx
Bias + dOPL/dx
Interfering Wavefronts
OPL = π
Bias = 0
s
Bias = π
s
Bias = π/2
s
Bias = π/2
0.5s
Object
Object
Object
Object

Increased shear makes the edges of the object less sharp, while increased bias introduces some background intensity. Shear direction determines the appearance of the object.


Shear Direction
Shear Direction
Shear Direction

Compared to phase contrast, DIC allows for larger phase differences throughout the object and operates in full resolution of the microscope (i.e., it uses the entire aperture). The depth of field is minimized, so DIC allows optical sectioning.

Reflectance DIC

A **Nomarski interference microscope** (also called a polarization interference contrast microscope) is a reflectance DIC system developed to evaluate roughness and the surface profile of specular samples. Its applications include metallography, microelectronics, biology, and medical imaging. It uses one Wollaston or Nomarski prism, a polarizer, and an analyzer. The information about the sample is obtained for one direction parallel to the gradient in the object. To acquire information for all directions, the sample should be rotated.

If white light is used, different colors in the image correspond to different sample slopes. It is possible to adjust the color by rotating the polarizer.


Image
Analyzer (-45)
From White Light Source
Beam Splitter
Polarizer (+45)
Wollaston Prism
Microscope Objective
Sample

Phase delay (**bias**) can be introduced by translating the birefringent prism. For imaging under monochromatic illumination, the brightness in the image corresponds to the slope in the sample. Images with no bias will appear as bright features on a dark background; with bias they will have an average background level, and slopes will vary between dark and bright. This way, it is possible to interpret the direction of the slope. Similar analysis can be performed for the colors from white-light illumination.


Brightness in image

Illumination with no bias


Brightness in image

Illumination with bias

Polarization Microscopy

Polarization microscopy provides images containing information about the properties of anisotropic samples. A polarization microscope is a modified compound microscope with three unique components: the **polarizer**, **analyzer**, and **compensator**. A linear polarizer is located between the light source and the specimen, close to the condenser's diaphragm. The analyzer is a linear polarizer with its transmission axis perpendicular to the polarizer. It is placed between the sample and the eye/camera, at or near the microscope objective's aperture stop. If no sample is present, the image should appear uniformly dark. The compensator (a type of retarder) is a birefringent plate of known parameters used for quantitative sample analysis and contrast adjustment.

Quantitative information can be obtained by introducing known retardation. Rotation of the analyzer correlates the analyzer's angular position with the retardation required to minimize the light intensity for object features at selected wavelengths. **Retardation** introduced by the compensator plate can be described as

$$\Gamma = \left(n_e - n_o\right)t\ ,$$

where t is the sample thickness, and subscripts e and o denote the extraordinary and ordinary beams. Retardation in concept is similar to the optical path difference for beams propagating through two different materials:

$$OPD = \left(n_1 - n_2\right)t = \left(n_e - n_o\right)t\ .$$

The phase delay caused by sample birefringence is therefore

$$\delta = \frac{2\pi OPD}{\lambda} = \frac{2\pi\Gamma}{\lambda}\ .$$

A polarization microscope can also be used to determine the orientation of the optic axis.


Image Plane
Analyzer
(Rotating Mount)
Compensator
Aperture
Stop
Microscope
Objective
Anisotropic
Sample
Condenser Lens
Condenser
Diaphragm
Polarizer
(Rotating Mount)
Collective Lens
Light Source

Images Obtained with Polarization Microscopes

Anisotropic samples observed under a **polarization microscope** contain dark and bright features and will strongly depend on the geometry of the sample. Objects can have characteristic elongated, linear, or circular structures:

- linear structures appear as dark or bright, depending on the orientation of the analyzer.
- circular structures have a “Maltese Cross” pattern with four quadrants of different intensities.

While polarization microscopy uses monochromatic light, it can also use white-light illumination. For broadband light, different wavelengths will be subject to different retardation; as a result, samples can provide different output colors. In practical terms, this means that color encodes information about retardation introduced by the object. The specific retardation is related to the image color. Therefore, the color allows for determination of sample thickness (for known retardation) or its retardation (for known sample thickness). If the polarizer and the analyzer are crossed, the color visible through the microscope is a complementary color to that having full wavelength retardation (a multiple of 2π, and the intensity is minimized for this color). Note that the two complementary colors combine into white light. If the analyzer could be rotated to be parallel to the analyzer, the two complementary colors will be switched (the one previously displayed will be minimized, while the other color will be maximized).

Polarization microscopy can provide quantitative information about the sample with the application of compensators (with known retardation). Estimating retardation might be performed visually or by integrating with an image acquisition system and CCD. This latter method requires one to obtain a series of images for different retarder orientations and calculate sample parameters based on saved images.



Compensators

Compensators are components that can be used to provide quantitative data about a sample's retardation. They introduce known retardation for a specific wavelength and can act as nulling devices to eliminate any phase delay introduced by the specimen. Compensators can also be used to control the background intensity level.

A **wave plate compensator** (also called a first-order red or red-I plate) is oriented at a 45-deg angle with respect to the analyzer and polarizer. It provides retardation equal to an even number of waves for 551 nm (green), which is the wavelength eliminated after passing the analyzer. All other wavelengths are retarded with a fraction of the wavelength and can partially pass the analyzer and appear as a bright red magenta. The sample provides additional retardation and shifts the colors towards blue and yellow. Color tables determine the retardation introduced by the object.

The **de Sénarmont compensator** is a quarter-wave plate (for 546 nm or 589 nm). It is used with monochromatic light for samples with retardation in the range of $\lambda/20$ to λ. A quarter-wave plate is placed between the analyzer and the polarizer with its slow ellipsoid axis parallel to the transmission axis of the analyzer. Retardation of the sample is measured in a two-step process. First, the sample is rotated until the maximum brightness is obtained. Next, the analyzer is rotated until the intensity maximally drops (the extinction position). The analyzer's rotation angle θ finds the phase delay related to retardation: $\Gamma_{\text{sample}} = 2\theta$.

A **Brace Köhler** rotating **compensator** is used for small retardations and monochromatic illumination. It is a thin birefringent plate with an optic axis in its plane. The analyzer and polarizer remain fixed while the compensator is rotated between the maximum and minimum intensities in the sample's image. Zero position (the maximum intensity) is determined for a slow axis being parallel to the transmission axis of the analyzer, and retardation is

$$\Gamma_{\text{sample}} = \Gamma_{\text{compensator}} \sin 2\theta .$$

Confocal Microscopy

Confocal microscopy is a scanning technique that employs pinholes at the illumination and detection planes so that only in-focus light reaches the detector. This means that the intensity for each sample point must be obtained in sequence through scanning in the x and y directions. An illumination pinhole is used in conjunction with the imaged sample plane and only illuminates the point of interest. The detection pinhole rejects the majority of out-of-focus light.

Confocal microscopy has the advantage of lowering the background light from out-of-focus layers, increasing spatial resolution, and providing the capability of imaging thick 3D samples, if combined with z scanning. Due to detection of only the in-focus light, confocal microscopy can provide images of thin sample sections. The system usually employs a photo-multiplier tube (PMT), avalanche photodiodes (APD), or a charge-coupled device (CCD) camera as a detector. For point detectors, recorded data is processed to assemble x-y images. This makes it capable of quantitative studies of an imaged sample's properties. Systems can be built for both reflectance and fluorescence imaging.



Spatial resolution of a confocal microscope can be defined as

$$d_{xy} \approx \frac{0.4\lambda}{NA},$$

and is slightly better than wide-field (bright-field) microscopy resolution. For pinholes larger than an Airy disk, the spatial resolution is the same as in a wide-field microscope. The **axial resolution** of a confocal system is

$$d_z \approx \frac{1.4n\lambda}{NA^2}.$$

The optimum pinhole value is at the full width at half maximum (FWHM) of the Airy disk intensity. This corresponds to ~75% of its intensity passing through the system, minimally smaller than the Airy disk's first ring:

$$D_{\text{pinhole}} = \frac{0.5\lambda M}{NA}.$$

Scanning Approaches

A scanning approach is directly connected with the temporal resolution of confocal microscopes. The number of points in the image, scanning technique, and the frame rate are related to the signal-to-noise ratio SNR (through time dedicated to detection of a single point). To balance these parameters, three major approaches were developed: point scanning, line scanning, and disk scanning.

A **point-scanning confocal microscope** is based on point-by-point scanning using, for example, two mirror galvanometers or resonant scanners. Scanning mirrors should be located in pupil conjugates (or close to them) to avoid light fluctuations. Maximum spatial resolution and maximum background rejection are achieved with this technique.



A **line-scanning confocal microscope** uses a slit aperture that scans in a direction perpendicular to the slit. It uses a cylindrical lens to focus light onto the slit to maximize throughput. Scanning in one direction makes this technique significantly faster than a point approach. However, the drawbacks are a loss of resolution and sectioning performance for the direction parallel to the slit.

Feature	**Point Scanning**	**Slit Slit Scanning**	**Disk Spinning**
z resolution	High	Depends on slit spacing	Depends on pinhole distribution
x,*y* resolution	High	Lower for one direction	Depends on pinhole spacing
Speed	Low to moderate	High	High
Light sources	Lasers	Lasers	Laser and other
Photobleaching	High	High	Low
QE of detectors	Low (PMT) Good (APD)	Good (CCD)	Good (CCD)
Cost	High	High	Moderate

Scanning Approaches (cont.)

Spinning-disk confocal imaging is a parallel-imaging method that maximizes the scanning rate and can achieve a 100–1000 speed gain over point scanning. It uses an array of pinholes/slits (e.g., Nipkow disk, Yokogawa, Olympus DSU approach). To minimize light loss, it can be combined (e.g., with the Yokogawa approach) with an array of lenses, so each pinhole has a dedicated focusing component. Pinhole disks contain several thousand pinholes, but only a portion is illuminated at one time.

<table>
<tr><th></th><th>Throughput of a confocal microscope T [%]</th></tr>
<tr><td>Array of pinholes</td><td>$T_{\text{pinhole}} = 100 \times (D/S)^2$</td></tr>
<tr><td>Multiple slits</td><td>$T_{\text{slit}} = 100 \times (D/S)$</td></tr>
<tr><td colspan="2">Equations are for a uniformly illuminated mask of pinholes/slits (array of microlenses not considered). D is the pinhole's diameter or slit's width respectively, while S is the pinhole/slit separation.</td></tr>
</table>

Crosstalk between pinholes and slits will reduce the background rejection. Therefore a common pinhole/slit separation S is 5−10 times larger than the pinhole's diameter or the slit's width.


Spinning Disk with Microlenses
Laser Beam
Beam Splitter
To Re imaging system on a CCD
Spinning Disk with Pinholes
Objective Lens
Sample

Spinning-disk and slit-scanning confocal microscopes require high-sensitivity array image sensors (CCD cameras) instead of point detectors. They can use lower excitation intensity for fluorescence confocal systems; therefore, they are less susceptible to photobleaching.

Images from a Confocal Microscope

Laser-scanning confocal microscopy rejects out-of-focus light and enables optical sectioning. It can be assembled in reflectance and fluorescent modes. A 1483 cell line, stained with membrane anti-EGFR antibodies labeled with fluorecent Alexa488 dye, is presented here. The top image shows the bright-field illumination mode. The middle image is taken by a confocal microscope with a pinhole corresponding to approximately 2.5 Airy disks. In the bottom image, the pinhole was entirely open. Clear cell boundaries are visible in the confocal image, while all out-of-focus features were removed.

Images were taken with a Zeiss LSM 510 microscope using a 63× Zeiss oil-immersion objective. Samples were excited with a 488-nm laser source.



Another example of 1483 cells labeled with EGF-Alexa647 and proflavine obtained on a Zeiss LSM 510 confocal at 63× / 1.4 oil is shown below. The proflavine (staining nuclei) was excited at 488 nm, with emission collected after a 505-nm long-pass filter. The EGF-Alexa647 (cell membrane) was excited at 633 nm, with emission collected after a 650−710 nm bandpass filter. The sectioning ability of a confocal system is nicely demonstrated by the channel with the membrane labeling.



Fluorescence

Specimens can absorb and re-emit light through **fluorescence**. The specific wavelength of light absorbed or emitted depends on the energy level structure of each molecule. When a molecule absorbs the energy of light, it briefly enters an excited state before releasing part of the energy as fluorescence. Since the emitted energy must be lower than the absorbed energy, fluorescent light is always at longer wavelengths than the excitation light. Absorption and emission take place between multiple sub-levels within the ground and excited states, resulting in absorption and emission spectra covering a range of wavelengths. The loss of energy during the fluorescence process causes the **Stokes shift** (a shift of wavelength peak from that of excitation to that of emission). Larger Stokes shifts make it easier to separate excitation and fluorescent light in the microscope. Note that energy quanta and wavelength are related by $E = hc/\lambda$.


Step 2
- Fluorophore loses energy to environment (non-radiative decay)
- Fluorophore drops to lowest singlet state
Excited Singlet State Levels
10^{11} sec
Step 3
- Fluorophore drops from lowest singlet state to a ground state
- Lower energy photon is emitted
$\lambda_{\text{Excitation}}$
$\lambda_{\text{Emission}} > \lambda_{\text{Excitation}}$
10^{15} sec
10^{9} sec
Ground Levels
Step 1
- High energy photon is absorbed
- Fluorophore is excited from ground to singlet state

The fluorescence principle is widely used in fluorescence microscopy for both organic and inorganic substances. While it is most common for biological imaging, it is also possible to examine samples like drugs and vitamins.

Due to the application of filter sets, the fluorescence technique has a characteristically low background and provides high-quality images. It is used in combination with techniques like wide-field microscopy and scanning confocal-imaging approaches.

Configuration of a Fluorescence Microscope

A fluorescence microscope includes a set of three **filters**: an **excitation filter**, **emission filter**, and a **dichroic mirror** (also called a **dichroic beam splitter**). These filters separate weak emission signals from strong excitation illumination. The most common fluorescence microscopes are configured in epi-illumination mode. The dichroic mirror reflects incoming light from the lamp (at short wavelengths) onto the specimen. Fluorescent light (at longer wavelengths) collected by the objective lens is transmitted through the dichroic mirror to the eyepieces or camera. The transmission and reflection properties of the dichroic mirror must be matched to the excitation and emission spectra of the fluorophore being used.





Configuration of a Fluorescence Microscope (cont.)

A sample must be illuminated with light at wavelengths within the excitation spectrum of the fluorescent dye. Fluorescence-emitted light must be collected at the longer wavelengths within the emission spectrum. Multiple fluorescent dyes can be used simultaneously, with each designed to localize or target a particular component in the specimen.

The **filter turret** of the microscope can hold several cubes that contain filters and dichroic mirrors for various dye types. Images are then reconstructed from CCD frames captured with each filter cube in place. Simultanous acquisition of emission for multiple dyes requires application of multiband dichroic filters.


Emission Filter
Filter Cube
From Light Source
Dichroic Beam Splitter
Excitation Filter
Aperture Stop
Microscope Objective
Fluorescent Sample

Images from Fluorescence Microscopy

Fluorescent images of cells labeled with three different fluorescent dyes, each targeting a different cellular component, demonstrate fluorescence microscopy's ability to target sample components and specific functions of biological systems. Such images can be obtained with individual filter sets for each fluorescent dye, or with a multiband (a triple-band in this example) filter set, which matches all dyes.



Triple-band Filter



BODIPY FL phallacidin (F-actin)

MitoTracker Red CMXRos (mitochondria)



DAPI (nuclei)

Sample: Bovine pulmonary artery epithelial cells (Invitrogen FluoCells No. 1)			
Components: Plan-apochromat 40×/0.95, MRm Zeiss CCD (1388×1040 mono)			
Fluorescent labels:	Peak Excitation		Peak Emission
DAPI	358 nm		461 nm
BODIPY FL	505 nm		512 nm
MitoTracker Red CMXRos	579 nm		599 nm
Filter:	Excitation	Dichroic	Emission
Triple-band	395–415	435	448–472
	480–510	510	510–550
	560–590	600	600–650
DAPI	325–375	395	420–470
GFP	450–490	495	500–550
Texas Red	530–585	600	615LP

Properties of Fluorophores

Fluorescent emission F [photons/s] depends on the intensity of excitation light I [photons/s] and fluorophore parameters like the **fluorophore quantum yield** Q and **molecular absorption cross section** σ:

$$F = \sigma Q I \ ,$$

where the molecular absorption cross section is the probability that illumination photons will be absorbed by fluorescent dye. The intensity of excitation light depends on the power of the light source and throughput of the optical system. The detected fluorescent emission is further reduced by the quantum efficiency of the detector.

Quenching is a partially reversible process that decreases fluorescent emission. It is a non-emissive process of electrons moving from an excited state to a ground state.

Fluorescence emission and excitation parameters are bound through a photobleaching effect that reduces the ability of fluorescent dye to fluoresce. **Photobleaching** is an irreversible phenomenon that is a result of damage caused by illuminating photons. It is most likely caused by the generation of long-living (in triplet states) molecules of singlet oxygen and oxygen free radicals generated during its decay process. There is usually a finite number of photons that can be generated for a fluorescent molecule. This number can be defined as the ratio of emission quantum efficiency to bleaching quantum efficiency, and it limits the time a sample can be imaged before entirely bleaching. Photobleaching causes problems in many imaging techniques, but it can be especially critical in time-lapse imaging. To slow down this effect, optimizing collection efficiency (together with working at lower power at the steady-state condition) is crucial.



Photobleaching effect as seen in consecutive images

Single vs Multi-Photon Excitation

Multi-photon fluorescence is based on the fact that two or more low-energy photons match the energy gap of the fluorophore to excite and generate a single high-energy photon. For example, the energy of two 700-nm photons can excite an energy transition approximately equal to that of a 350-nm photon (it is not an exact value due to thermal losses). This is contrary to traditional fluorescence, where a high-energy photon (e.g., 400 nm) generates a slightly lower-energy (longer wavelength) photon. Therefore, one big advantage of multi-photon fluorescence is that it can obtain a significant difference between excitation and emission.

Fluorescence is based on stochastic behavior, and for single-photon excitation fluorescence, it is obtained with a high probability. However, multi-photon excitation requires at least two photons delivered in a very short time, and the probability is quite low:

$$n_a \propto \delta \left(\frac{P_{\text{avg}}^2}{\tau \nu^2} \right) \left(\pi \frac{NA^2}{hc\lambda} \right)^2 .$$

δ is the excitation cross section of dye, P_{avg} is the average power, τ is the length of a pulse, and ν is the repetition frequency. Therefore, multi-photon fluorescence must be used with high-power laser sources to obtain favorable probability. Short-pulse operation will have a similar effect, as τ will be minimized.


Single Photon Excitation
Multi photon Excitation
Fluorescing Region


10^{11} sec
$\lambda_{\text{Excitation}}$
10^{15} sec
10^{9} sec
$\lambda_{\text{Emission}} > \lambda_{\text{Excitation}}$
$\lambda_{\text{Excitation}}$
$\lambda_{\text{Emission}} < \lambda_{\text{Excitation}}$

Due to low probability, fluorescence occurs only in the focal point. Multi-photon imaging does not require scanning through a pinhole and therefore has a high signal-to-noise ratio and can provide deeper imaging. This is also because near-IR excitation light penetrates more deeply due to lower scattering, and near-IR light avoids the excitation of several autofluorescent tissue components.

Light Sources for Scanning Microscopy

Lasers are an important light source for scanning microscopy systems due to their high energy density, which can increase the detection of both reflectance and fluorescence light. For laser-scanning confocal systems, a general requirement is a single-mode TEM_{00} laser with a short coherence length. Lasers are used primarily for point-and-slit scanning modalities. There are a great variety of laser sources, but certain features are useful depending on their specific application:

- Short-excitation wavelengths are preferred for fluorescence confocal systems because many fluorescent probes must be excited in the blue or ultraviolet range.
- Near-IR wavelengths are useful for reflectance confocal microscopy and multi-photon excitation. Longer wavelengths are less suseptible to scattering in diffused objects (like tissue) and can provide a deeper penetration depth.
- Broadband short-pulse lasers (like a Ti-Sapphire mode-locked laser) are particularily important for multi-photon generation, while shorter pulses increase the probability of excitation.

Laser Type	Wavelength [nm]
Argon-Ion	351, 364, 458, 488, 514
HeCd	325, 442
HeNe	543, 594, 633, 1152
Diode lasers	405, 408, 440, 488, 630, 635, 750, 810
DPSS (diode pumped, solid state)	430, 532, 561
Krypton-Argon	488, 568, 647
Dye	630
Ti-Sapphire*	710–920, 720–930, 750–850, 690–100, 680–1050

*High-power (1000mW or less), pulses between 1 ps and 100 fs

Non-laser sources are particularly useful for disk-scanning systems. They include arc lamps, metal-halide lamps, and high-power photo-luminescent diodes (See also pages 58 and 59).

Practical Considerations in LSM

A light source in laser-scanning microscopy must provide enough energy to obtain a sufficient number of photons to perform successful detection and a statistically significant signal. This is especially critical for non-laser sources (e.g., arc lamps) used in disk-scanning systems. While laser sources can provide enough power, they can cause fast photobleaching or photo-damage to the biological sample.

Detection conditions change with the type of sample. For example, fluorescent objects are subject to photobleaching and saturation. On the other hand, back-scattered light can be easily rejected with filter sets. In reflectance mode, out-of-focus light can cause background comparable or stronger than the signal itself. This background depends on the size of the pinhole, scattering in the sample, and overall system reflections.

Light losses in the optical system are critical for the signal level. Collection efficiency is limited by the NA of the objective; for example, a NA of 1.4 gathers approximately 30% of the fluorescent/scattered light. Other system losses will occur at all optical interfaces, mirrors, filters, and at the pinhole. For example, a pinhole matching the Airy disk allows approximately 75% of the light from the focused image point.

Quantum efficiency (QE) of a detector is another important system parameter. The most common photodetector used in scanning microscopy is the photomultiplier tube (PMT). Its quantum efficiency is often limited to the range of 10–15% (550–580 nm). In practical terms, this means that only 15% of the photons are used to produce a signal. The advantages of PMTs for laser-scanning microscopy are high speed and high signal gain. Better QE can be obtained for CCD cameras, which is 40–60% for standard designs and 90–95% for thinned, back-illuminated cameras. However, CCD image sensors operate at lower rates.

Spatial and temporal sampling of laser-scanning microscopy images imposes very important limitations on image quality. The image size and frame rate are often determined by the number of photons sufficient to form high-quality images.

Interference Microscopy



Interference microscopy includes a broad family of techniques for quantitative sample characterization (thickness, refractive index, etc.). Systems are based on microscopic implementation of interferometers (like the Michelson and Mach-Zehnder geometries), or polarization interferometers.

In interference microscopy, short coherence systems are particularly interesting and can be divided into two groups: **optical profilometry** and **optical coherence tomography** (OCT) [including **optical coherence microscopy** (OCM)]. The primary goal of these techniques is to add a third (*z*) dimension to the acquired data.

Optical profilers use interference fringes as a primary source of object height. Two important measurement approaches include **vertical scanning interferometry** (VSI) (also called **scanning white light interferometry** or **coherence scanning interferometry**) and **phase-shifting interferometry**. Profilometry techniques are capable of achieving nanometer-level resolution in the *z* direction while *x* and *y* are defined by standard microscope limitations.

Profilometry is used for characterizing the sample surface (roughness, structure, microtopography, and in some cases film thickness) while OCT/OCM is dedicated to 3D imaging, primarily of biological samples.

Both types of systems are usually configured using the geometry of the Michelson or its derivatives (e.g., Mirau).



Optical Coherence Tomography/Microscopy

In early 3D coherence imaging, information about the sample was gated by the coherence length of the light source (**time-domain OCT**). This means that the maximum fringe contrast is obtained at a zero optical path difference, while the entire fringe envelope has a width related to the coherence length. In fact, this width defines the axial resolution (usually a few microns) and images are created from the magnitude of the fringe pattern envelope. **Optical coherence microscopy** is a combination of OCT and confocal microscopy. It merges the advantages of out-of-focus background rejection provided by the confocal principle and applies the coherence gating of OCT to improve optical sectioning over confocal reflectance systems.

In the mid-2000s, time-domain OCT transitioned to **Fourier-domain OCT** (FDOCT), which can acquire an entire depth profile in a single capture event. Similar to Fourier Transform Spectroscopy, the image is acquired by calculating the Fourier transform of the obtained interference pattern. The measured signal can be described as

$$I\left(k,z_{\mathrm{o}}\right)=\int A_{\mathrm{R}}A_{\mathrm{S}}\left(z\right)\cos\left[k\left(z_{\mathrm{m}}-z_{\mathrm{o}}\right)\right]dz\ ,$$

where A_R and A_S are amplitudes of the reference and sample light, respectively, and z_m is the imaged sample depth (z_o is the reference length delay, and k is the wave number).



The fringe frequency is a function of wave number k and relates to the OPD in the sample. Within the Fourier-domain techniques, two primary methods exist: **spectral-domain OCT** (SDOCT) and **swept-source OCT** (SSOCT). Both can reach detection sensitivity and signal-to-noise ratios over 150 times higher than time-domain OCT approaches. SDOCT achieves this through the use of a broadband source and spectrometer for detection. SSOCT uses a single photodetector but rapidly tunes a narrow linewidth over a broad spectral profile. Fourier-domain systems can image at hundreds of frames per second with sensitivities over 100 dB.

Optical Profiling Techniques

There are two primary techniques used to obtain a surface profile using white-light profilometry: **vertical scanning interferomtry** (VSI) and **phase-shifting interferometry** (PSI).

VSI is based on the fact that a reference mirror is moved by a piezoelectric or other actuator, and a sequence of several images (in some cases hundreds or thousands) is acquired along the scan. During post-processing, algorithms look for a maximum fringe modulation and correlate it with the actuator's position. This position is usually determined with capacitance gauges; however, more advanced systems use optical encoders or an additional Michelson interferometer. The important advantage of VSI is its ability to ambiguously measure heights that are greater than a fringe.



The PSI technique requires the object of interest to be within the coherence length and provides one order of magnitude or greater z resolution compared to VSI. To extend coherence length, an optical filter is introduced to limit the light source's bandwidth. With PSI, a phase-shifting component is located in one arm of the interferometer. The reference mirror can also provide the role of the phase shifter. A series of images (usually three to five) is acquired with appropriate phase differences to be used later in phase reconstruction. Introduced phase shifts change the location of the fringes. An important PSI drawback is the fact that phase maps are subject to 2π discontinuities. Phase maps are first obtained in the form of so-called phase fringes and must be unwrapped (a procedure of removing discontinuities) to obtain a continuous phase map.



Note that modern short-coherence interference microscopes combine phase information from PSI with a long range of VSI methods.

Optical Profilometry: System Design


CCD Camera
Beam Splitter
From Light Source
Michelson Microscope Objective
Beam Splitter
Reference Mirror
Sample

Optical profilometry systems are based on implementing a Michelson interferometer or its derivatives into their design. There are three primary implementations: classical **Michelson** geometry, **Mirau**, and **Linnik**. The first approach incorporates a Michelson inside a microscope objective using a classical interferometer layout. Consequently, it can work only for low magnifications and short working distances. The Mireau objective uses two plates perpendicular to the optical axis inside the objective. One is a beam-splitting plate, while the other acts as a reference mirror. Such a solution extends the working distance and increases the possible magnifications.

Design	**Magnification**
Michelson	1× to 5×
Mireau	10× to 100×
Linnik	50× to 100×

The Linnik design utilizes two matching objectives. It does not suffer from NA limitation, but it is quite expensive and susceptible to vibrations.


CCD Camera
Beam Splitter
From Light Source
Mireau Microscope Objective
Reference Mirror
Beam Splitting Plate
Sample


Linnik Microscope
CCD Camera
Beam Splitter
Microscope Objective
From Light Source
Reference Mirror
Microscope Objective
Sample

Phase-Shifting Algorithms

Phase-shifting techniques find the phase distribution from interference images given by

$$I(x,y) = a(x,y) + b(x,y)\cos(\varphi + n\Delta\varphi),$$

where $a(x, y)$ and $b(x, y)$ correspond to background and fringe amplitude, respectively. Since this equation has three unknowns, at least three measurements (images) are required. For image acquisition with a discrete CCD camera, spatial (x, y) coordinates can be replaced by (i, j) pixel coordinates.

The most basic PSF algorithms include the **three-**, **four-**, and **five-image** techniques.

I denotes the intensity for a specific image (1st, 2nd, 3rd, etc.) in the selected i, j pixel of a CCD camera. The phase shift for a three-image algorithm is π/2. Four- and five-image algorithms also acquire images with π/2 phase shifts.

$$\varphi = \arctan\left(\frac{I_3 - I_2}{I_1 - I_2}\right)$$

$$\varphi = \arctan\left(\frac{I_4 - I_2}{I_1 - I_3}\right)$$

$$\varphi = \arctan\left(\frac{2[I_2 - I_4]}{I_1 - I_3 + I_5}\right)$$

A reconstructed phase depends on the accuracy of the phase shifts. π/2 steps were selected to minimize the systematic errors of the above techniques. Accuracy progressively improves between the three- and five-point techniques. Note that modern PSI algorithms often use seven images or more, in some cases reaching thirteen.

After the calculations, the wrapped phase maps (modulo 2π) are obtained (arctan function). Therefore, unwrapping procedures have to be applied to provide continuous phase maps.

Common unwrapping methods include the line by line algorithm, least square integration, regularized phase tracking, minimum spanning tree, temporal unwrapping, frequency multiplexing, and others.

Structured Illumination: Axial Sectioning

A simple and inexpensive alternative to confocal microscopy is the **structured-illumination technique**. This method uses the principle that all but the zero (DC) spatial frequencies are attenuated with defocus. This observation provides the basis for obtaining the **optical sectioning** of images from a conventional wide-field microscope. A modified illumination system of the microscope projects a single spatial-frequency grid pattern onto the object. The microscope then faithfully images only that portion of the object where the grid pattern is in focus. The structured-illumination technique requires the acquisition of at least three images to remove the illumination structure and reconstruct an image of the layer. The reconstruction relation is described by

$$I = \sqrt{\left(I_0 - I_{2\pi/3}\right)^2 + \left(I_0 - I_{4\pi/3}\right)^2 + \left(I_{2\pi/3} - I_{4\pi/3}\right)^2}\ ,$$

where I denotes the intensity in the reconstructed image point, while I_0, $I_{2\pi/3}$, and $I_{4\pi/3}$ are intensities for the image point and the three consecutive positions of the sinusoidal illuminating grid (zero, 1/3 and 2/3 of the structure period).



Note that the maximum sectioning is obtained for 0.5 of the objective's cut-off frequency. This sectioning ability is comparable to that obtained in confocal microscopy.

Structured Illumination: Resolution Enhancement

Structured illumination can be used to enhance the spatial resolution of a microscope. It is based on the fact that if a sample is illuminated with a periodic structure, it will create a low-frequency beating effect (Moiré fringes) with the features of the object. This new low-frequency structure will be capable of aliasing high spatial frequencies through the optical system. Therefore, the sample can be illuminated with a pattern of several orientations to accommodate the different directions of the object features. In practical terms, this means that system apertures will be doubled (in diameter), creating a new synthetic aperture.



To produce a high-frequency structure, the interference of two beams with large illumination angles can be used. Note that the blue dots in the figure represent aliased spatial frequencies.


Pupil of diffraction-limited system
Pupil of structured illumination system with eight directions
Filtered Spacial Frequencies
Increased Synthetic Aperture

To reconstruct distribution, at least three images are required for one grid direction. In practice, obtaining a high-resolution image is possible with seven to nine images and a grid rotation, while a larger number can provide a more efficient reconstruction.

The linear-structured illumination approach is capable of obtaining two-fold resolution improvement over the diffraction limit. The application of nonlinear gain in fluorescence imaging improves resolution several times while working with higher harmonics. Sample features of 50 nm and smaller can be successfully resolved.

TIRF Microscopy



Total internal reflection fluorescence (TIRF) **microscopy** (also called evanescent wave microscopy) excites a limited width of the sample close to a solid interface. In TIRF, a thin layer of the sample is excited by a wavefront undergoing total internal reflection in the dielectric substrate, producing an **evanescent wave** propagating along the interface between the substrate and object.

The thickness of the excited section is limited to less than 100–200 nm. Very low background fluorescence is an important feature of this technique, since only a very limited volume of the sample in contact with the evanescent wave is excited.

This technique can be used for imaging cells, cytoplasmic filament structures, single molecules, proteins at cell membranes, micro-morphological structures in living cells, the adsorption of liquids at interfaces, or Brownian motion at the surfaces. It is also a suitable technique for recording long-term fluorescence movies.







While an evanescent wave can be created without any layers between the dielectric substrate and sample, it appears that a thin layer (e.g., metal) improves image quality. For example, it can quench fluorescence in the first 10 nm and therefore provide selective fluorescence for the 10–200 nm region. TIRF can be easily combined with other modalities like optical trapping, multi-photon excitation, or interference. The most common configurations include oblique illumination through a high-NA objective or condenser and TIRF with a prism.

Solid Immersion

Optical resolution can be enhanced using **solid immersion** imaging. In the classical definition, the diffraction limit depends on the NA of the optical system and the wavelength of light. It can be improved by increasing the refractive index of the media between the sample and optical system or by decreasing the light's wavelength. The solid immersion principle is based on improving the first parameter by applying **solid immersion lenses** (SILs). To maximize performance, SILs are made with a high refractive index glass (usually greater than 2). The most basic setup for a SIL application involves a hemispherical lens. The sample is placed at the center of the hemisphere so the rays propagating through the system are not refracted (they intersect the SIL surface direction) and enter the microscope objective. The SIL is practically in contact with the object, but has a small sub-wavelength gap (<100 nm) between the sample and optical system; therefore, an object is always in an evanescent field and can be imaged with high resolution. Therefore, the technique is confined to a very thin sample volume (up to 100 nm) and can provide optical sectioning. Systems based on solid immersion can reach sub-100-nm lateral resolutions.

The most common solid-immersion applications are in microscopy, including fluorescence, optical data storage, and lithography. Compared to classical oil-immersion techniques, this technique is dedicated to imaging thin samples only (sub-100 nm), but provides much better resolution depending on the configuration and refractive index of the SIL.



Stimulated Emission Depletion

Stimulated emission depletion (STED) microscopy is a fluorescence super-resolution technique that allows imaging with a spatial resolution at the molecular level. The technique has shown an improvement 5–10 times beyond the possible diffraction-resolution limit.

The STED technique is based on the fact that the area around the excited object point can be treated with a pulse (depletion pulse or STED pulse) that depletes high-energy states and brings fluorescent dye to the ground state. Consequently, an actual excitation pulse excites only the small sub-diffraction resolved area. The depletion pulse must have high intensity and be significantly shorter than the lifetime of the excited states. The pulse must be shaped, for example, with a half-wave phase plate and imaging optics to create a 3D doughnut-like structure around the point of interest. The STED pulse is shifted toward red with regard to the fluorescence excitation pulse and follows it by a few picoseconds. To obtain the complete image, the system scans in the *x*, *y*, and *z* directions.


Detection Plane
Excitation
STED
Fluorescent Emission
Half-wave Phase Plate
Red-Shifted STED Pulse
Dichroic Beam Splitter
Dichroic Beam Splitter
Excitation Pulse
Pulse Delay
High-NA Microscope Objective
Depleted Region
Sample
x, y sample scanning
Excited Region

STORM

Stochastic optical reconstruction microscopy (STORM) is based on the application of multiple photo-switchable fluorescent probes that can be easily distinguished in the spectral domain. The system is configured in **TIRF** geometry. Multiple fluorophores label a sample, and each is built as a dye pair where one component acts as a fluorescence activator. The activator can be switched on or deactivated using a different illumination laser (a longer wavelength is used for deactivation—usually red). In the case of applying several dual-pair dyes, different lasers can be used for activation and only one for deactivation.

A sample can be sequentially illuminated with activation lasers, which generate fluorescent light at different wavelengths for slightly different locations on the object (each dye is sparsely distributed over the sample and activation is stochastic in nature). Activation for a different color can also be shifted in time. After performing several sequences of activation/deactivation, it is possible to acquire data for the centroid localization of various diffraction-limited spots. This localization can be performed with precision to about 1 nm. The spectral separation of dyes detects closely located object points encoded with a different color.

The STORM process requires 1000+ activation/deactivation cycles to produce high-resolution images. Therefore, final images combine the spots corresponding to individual molecules of DNA or an antibody used for labeling. STORM images can reach a lateral resolution of about 25 nm and an axial resolution of 50 nm.


Time Diagram
Activation Pulses (violet)
Activation Pulses (blue)
Activation Pulses (green)
De Activation Pulses (red)
Time
Conceptual Resolving Principle
Violet Activated Dye
Blue Activated Dye
Green Activated Dye
Diffraction Limited Spot

4Pi Microscopy

4Pi microscopy is a fluorescence technique that significantly reduces the thickness of an imaged section. The 4Pi principle is based on coherent illumination of a sample from two directions. Two constructively interfering beams improve the axial resolution by three to seven times. The possible values of z resolution using 4Pi microscopy are 50–100 nm and 30–50 nm when combined with STED.

The undesired effect of the technique is the appearance of side lobes located above and below the plane of the imaged section. They are located about λ/2 from the object. To eliminate side lobes, three primary techniques can be used:

- Combine 4Pi with confocal detection. A pinhole rejects some of the out-of-focus light.
- Detect in multi-photon mode, which quickly diminishes the excitation of fluorescence.
- Apply a modified 4Pi system, which creates interference at both the object and detection planes (two imaging systems are required).

It is also possible to remove side lobes through numerical processing, if they are smaller than 50% of the maximum intensity. However, side lobes increase with the NA of the objective; for an NA of 1.4, they are about 60–70% of the maximum intensity. Numerical correction is not effective in this case.

4Pi microscopy improves resolution only in the z direction; however, the perception of details in the thin layers is a useful benefit of the technique.


Interference at object Plane
Incoherent detection
Interference at object Plane
Interference at detection Plane
Interference Plane
Excitation
Detection
Excitation
Excitation
Detection
Detection
Excitation

The Limits of Light Microscopy

Classical light microscopy is limited by diffraction and depends on the wavelength of light and the parameters of an optical system (NA). However, recent developments in super-resolution methods and enhancement techniques overcome these barriers and provide resolution at a molecular level. They often use a sample as a component of the optical train [resolvable saturable optical fluorescence transitions (**RESOLFT**), saturated structured-illumination microscopy (**SSIM**), photoactivated localization microscopy (**PALM**) and **STORM**] or combine near-field effects (**4Pi, TIRF, solid immersion**) with far-field imaging. The table below summarizes these methods.

		Demonstrated Values	
Method	**Principles**	**Lateral**	**Axial**
Bright field	Diffraction	200 nm	500 nm
Confocal	Diffraction (slightly better than bright field)	200 nm	500 nm
Solid immersion	Diffraction / evanescent field decay	< 100 nm	< 100 nm
TIRF	Diffraction / evanescent field decay	200 nm	< 100 nm
4Pi / I5	Diffraction/ interference	200 nm	50 nm
RESOLFT (e.g.,STED)	Depletion, molecular structure of sample–fluorescent probes	20 nm	20 nm
Structured illumination (SSIM)	Aliasing, nonlinear gain in fluorescent probes (molecular structure)	25–50 nm	50–100 nm
Stochastic techniques (PALM, STORM)	Fluorescent probes (molecular structure), centroid localization, time-dependant fluorophore activation	25 nm	50 nm

Raman and CARS Microscopy

Raman microscopy (also called chemical imaging) is a technique based on inelastic **Raman scattering** and evaluates the vibrational properties of samples (minerals, polymers, and biological objects).



Raman microscopy uses a laser beam focused on a solid object. Most of the illuminating light is scattered, reflected, and transmitted, and preserves the parameters of the illumination beam (the frequency is the same as the illumination). However, a small portion of the light is subject to a shift in frequency: $\omega_{\mathrm{Raman}} = \omega_{\mathrm{laser}} \pm \Delta\omega$. This frequency shift between illumination and scattering bears information about the molecular composition of the sample. Raman scattering is weak and requires high-power sources and sensitive detectors. It is examined with spectroscopy techniques.



Coherent Anti-Stokes Raman Scattering (**CARS**) overcomes the problem of weak signals associated with Raman imaging. It uses a pump laser and a tunable Stokes laser to stimulate a sample with a four-wave mixing process. The fields of both lasers [pump field $E(\omega_p)$, Stokes field $E(\omega_s)$, and probe field $E'(\omega_p')$] interact with the sample and produce an anti-Stokes field [$E(\omega_{as})$] with frequency ω_{as}, so $\omega_{as} = 2\omega_p - \omega_s$.

CARS works as a resonant process, only providing a signal if the vibrational structure of the sample specifically matches $\omega_p - \omega_s$. It also must assure phase matching so that l_c (the coherence length) is greater than $\pi/\Delta\mathbf{k} = \pi/\left|\mathbf{k}_{as} - (2\mathbf{k}_p - \mathbf{k}_s)\right|$, where $\Delta\mathbf{k}$ is a phase mismatch. CARS is orders of magnitude stronger than Raman scattering, does not require any exogenous contrast, provides good sectioning ability, and can be set up in both transmission and reflectance modes.

SPIM

Selective plane illumination microscopy (SPIM) is dedicated to the high-resolution imaging of large 3D samples. It is based on three principles:

- The sample is illuminated with a **light sheet**, which is obtained with cylindrical optics. The light sheet is a beam focused in one direction and collimated in another. This way, the thin and wide light sheet can pass through the object of interest (see figure).
- The sample is imaged in the direction perpendicular to the illumination.
- The sample is rotated around its axis of gravity and linearly translated into axial and lateral directions.

Data is recorded by a CCD camera for multiple object orientations and can be reconstructed into a single 3D distribution. Both scattered and fluorescent light can be used for imaging.

The maximum resolution of the technique is limited by the longitudinal resolution of the optical system (for a high numerical aperture, objectives can obtain micron-level values). The maximum volume imaged is limited by the working distance of a microscope and can be as small as tens of microns or exceed several millimeters. The object is placed in an air, oil, or water chamber.

The technique is primarily used for bio-imaging, ranging from small organisms to individual cells.


Microscope Objective
3D Object
Sample Chamber
Laser Light
Thickness of light sheet
Cylindrical Lens
Objective's FOV
Width of light sheet
Rotation and Translations

Array Microscopy

An **array microscope** is a solution to the trade-off between field of view and lateral resolution. In the array microscope, a miniature microscope objective is replicated tens of times. The result is an imaging system with a field of view that can be increased in steps of an individual objective's field of view, independent of numerical aperture and resolution. An array microscope is useful for applications that require fast imaging of large areas at a high level of detail. Compared to conventional microscope optics for the same purpose, an array microscope can complete the same task several times faster due to its parallel imaging format.

An example implementation of the array-microscope optics is shown. This array microscope is used for imaging glass slides containing tissue (histology) or cells (cytology). For this case, there are a total of 80 identical miniature 7×/0.6 microscope objectives. The summed field of view measures 18 mm. Each objective consists of three lens elements. The lens surfaces are patterned on three plates that are stacked to form the final array of microscopes. The plates measure 25 mm in diameter. Plate 1 is near the object at a working distance of 400 μm. Between plates 2 and 3 is a baffle plate. A second baffle is located between the third lens and the image plane. The purpose of the baffles is to eliminate cross talk and image overlap between objectives in the array.

The small size of each microscope objective and the need to avoid image overlap jointly dictate a low magnification. Therefore, the array microscope works best in combination with an image sensor divided into small pixels (e.g., 3.3 μm).

Focusing the array microscope is achieved by an up/down translation and two rotations: a pitch and a roll.



Digital Microscopy

Digital microscopy emerged with the development of electronic array image sensors and replaced the microphotography techniques previously used in microscopy. It can also work with point detectors when images are recombined in post or real-time processing. Digital microscopy is based on acquiring, storing, and processing images taken with various microscopy techniques. It supports applications that require:

- Combining data sets acquired for one object with different microscopy modalities or different imaging conditions. Data can be used for further analysis and processing in techniques like hyperspectral and polarization imaging.
- Image correction (e.g., distortion, white balance correction, or background subtraction). Digital microscopy is used in deconvolution methods that perform numerical rejection of out-of-focus light and iteratively reconstruct an object's estimate.
- Image acquisition with a high temporal resolution. This includes short integration times or high frame rates.
- Long time experiments and remote image recording.
- Scanning techniques where the image is reconstructed after point-by-point scanning and displayed on the monitor in real time.
- Low light, especially fluorescence. Using high-sensitivity detectors reduces both the excitation intensity and excitation time, which mitigates photobleaching effects.
- Contrast enhancement techniques and an improvement in spatial resolution. Digital microscopy can detect signal changes smaller than possible with visual observation.
- Super-resolution techniques that may require the acquisition of many images under different conditions.
- High throughput scanning techniques (e.g., imaging large sample areas).
- UV and IR applications not possible with visual observation.

The primary detector used for digital microscopy is a CCD camera. For scanning techniques, a photomultiplier or photodiodes are used.

Principles of CCD Operation

Charge-coupled device (CCD) sensors are a collection of individual photodiodes arranged in a 2D grid pattern. Incident photons produce electron-hole pairs in each pixel in proportion to the amount of light on each pixel. By collecting the signal from each pixel, an image corresponding to the incident light intensity can be reconstructed.

Here are the step-by-step processes in a CCD:

1. The CCD array is illuminated for integration time τ.
2. Incident photons produce mobile charge carriers.
3. Charge carriers are collected within the p-n structure.
4. The illumination is blocked after time τ (full-frame only).
5. The collected charge is transferred from each pixel to an amplifier at the edge of the array.
6. The amplifier converts the charge signal into voltage.
7. The analog voltage is converted to a digital level for computer processing and image display.

Each pixel (**photodiode**) is reverse biased, causing photoelectrons to move towards the positively charged electrode. Voltages applied to the electrodes produce a potential well within the semiconductor structure. During the integration time, electrons accumulate in the potential well, up to the full-well capacity. The full-well capacity is reached when the repulsive force between electrons exceeds the attractive force of the well. At the end of the exposure time, each pixel has stored a number of electrons in proportion to the amount of light received. These charge packets must be transferred from the sensor, from each pixel to a single amplifier without loss. This is accomplished by a series of parallel and serial shift registers. The charge stored by each pixel is transferred across the array by sequences of gating voltages applied to the electrodes. The packet of electrons follows the positive clocking waveform voltage from pixel-to-pixel or row-to-row. A potential barrier is always maintained between adjacent pixel charge packets.



CCD Architectures

In a **full-frame architecture**, individual pixel charge packets are transferred by a parallel row shift to the serial register, then one-by-one to the amplifier. The advantage of this approach is a 100% photosensitive area, while the disadvantage is that a shutter must block the sensor area during readout, and consequently limits the frame rate.


Frame-Transfer Architecture
Interline Architecture
Full-Frame Architecture
Sensing Area
Readout - Serial Register
Amplifier
Sensing Area
Storage Area (Shielded)
Readout - Serial Register
Amplifier
Sensing Register
Storage Register (Shielded)
Sensing Register
Storage Register (Shielded)
Sensing Register
Storage Register (Shielded)
Sensing Register
Storage Register (Shielded)
Readout - Serial Register
Amplifier

The **frame-transfer architecture** has the advantage of not needing to block an imaging area during readout. It is faster than full-frame, since readout can take place during the integration time. The significant drawback is that only 50% of the sensor area is used for imaging.

The **interline transfer architecture** uses columns with exposed imaging pixels interleaved with columns of masked storage pixels. A charge is transferred into an adjacent storage column for readout. The advantage of such an approach is a high frame rate due to a rapid transfer time (< 1 ms), while again the disadvantage is that 50% of the sensor area is used for light collection. However, recent interleaved CCDs have an increased fill factor due to the application of microlens arrays.

CCD Architectures (cont.)



Quantum efficiency (QE) is the percentage of incident photons at each wavelength that produce an electron in a photodiode. CCDs have a lower QE than individual silicon photodiodes due to the charge-transfer channels on the sensor surface, which reduces the effective light-collection area. A typical CCD QE is 40–60%. This can be improved for back-thinned CCDs, which are illuminated from behind; this avoids the surface electrode channels and improves QE to approximately 90–95%.

Recently, **electron-multiplying CCDs** (EM-CCD), primarily used for biological imaging, have become more common. They are equipped with a gain register placed between the shift register and output amplifier. A multi-stage gain register allows high gains. As a result, single electrons can generate thousands of output electrons. While the read noise is usually low, it is therefore negligible in the context of thousands of signal electrons.



CCD pixels are not color sensitive, but use color filters to separately measure red, green, and blue light intensity. The most common method is to cover the sensor with an array of **RGB** (red, green, blue) filters, which combine four individual pixels to generate a single color pixel. The **Bayer mask** uses two green pixels for every red and blue pixel, which simulates human visual sensitivity.



Blue	Green	Blue	Green	Blue	Green		
Green	Red	Green	Red	Green	Red		
Blue	Green	Blue	Green				
Green	Red	Green	Red				
Blue	Green						
Green	Red						

CCD Noise

The three main types of noise that affect CCD imaging are **dark noise**, **read noise**, and **photon noise**.

Dark noise arises from random variations in the number of thermally generated electrons in each photodiode. More electrons can reach the conduction band as the temperature increases, but this number follows a statistical distribution. These random fluctuations in the number of conduction band electrons results in a **dark current** that is not due to light. To reduce the influence of dark current for long time exposures, CCD cameras are cooled (which is crucial for the exposure of weak signals, like fluorescence, with times of a few seconds and more).

Read noise describes the random fluctuation in electrons contributing to measurement, due to electronic processes on the CCD sensor. This noise arises during the charge transfer, the charge-to-voltage conversion, and the analog-to-digital conversion. Every pixel on the sensor is subject to the same level of read noise, most of which is added by the amplifier.

Dark noise and read noise are due to the properties of the CCD sensor itself.

Photon noise (or **shot noise**) is inherent in any measurement of light, due to the fact that photons arrive at the detector randomly in time. This process is described by **Poisson statistics**. The probability P of measuring k events, given an expected value N is

$$P\left(k,N\right)=\frac{N^{k}e^{-N}}{k!}.$$

The standard deviation of the Poisson distribution is $N^{1/2}$. Therefore, if the average number of photons arriving at the detector is N, then the noise is $N^{1/2}$. Since the average number of photons is proportional to incident power, shot noise increases with $P^{1/2}$.

Signal-to-Noise Ratio and the Digitization of CCD

Total **noise** as a function of the number of electrons from all three contributing noises is given by

$$Noise\left[N_{\text{electrons}}\right] = \sqrt{\sigma^2_{\text{Photon}} + \sigma^2_{\text{Dark}} + \sigma^2_{\text{Read}}}\ ,$$

where

$\sigma_{\text{Photon}} = \sqrt{\varphi\eta\tau}$, $\sigma_{\text{Dark}} = \sqrt{I_{\text{Dark}}\tau}$, and $\sigma_{\text{Read}} = N_{\text{R}}$, I_{Dark} is dark current (electrons per second), and N_{R} is read noise (electrons, rms).

The quality of an image is determined by the **signal-to-noise ratio** (SNR). The signal can be defined as

$$Signal\left[N_{\text{electrons}}\right] = \varphi\eta\tau\ ,$$

where φ is the incident photon flux at the CCD (photons per second), η is the quantum efficiency of the CCD (electrons per photon), and τ is the integration time (in seconds). Therefore, SNR can be defined as:

$$SNR = \frac{\varphi\eta\tau}{\sqrt{\varphi\eta\tau + I_{\text{dark}}\tau + N^2_{\text{R}}}}\ .$$

It is best to use a CCD under photon-noise-limited conditions. If possible, it would be optimal to increase the integration time to increase the SNR and work in photon-noise-limited conditions. However, an increase in integration time is possible until reaching full-well capacity (saturation level):

$$SNR = \frac{\varphi\eta\tau}{\sqrt{\varphi\eta\tau}} = \sqrt{\varphi\eta\tau}.$$

The **dynamic range** can be derived as a ratio of full-well capacity and read noise. Digitization of the CCD output should be performed to maintain the dynamic range of the camera. Therefore, an analog-to-digital converter should support (at least) the same number of gray levels calculated by the CCD's dynamic range. Note that a high bit depth extends readout time, which is especially critical for large-format cameras.

CCD Sampling

The maximum spatial frequency passed by the CCD is one half of the sampling frequency—the **Nyquist frequency**. Any frequency higher than Nyquist will be aliased at lower frequencies.

Undersampling refers to a frequency where the sampling rate is not sufficient for the application. To assure maximum resolution of the microscope, the system should be optics limited, and the CCD should provide sampling that reaches the diffraction resolution limit. In practice, this means that at least two pixels should be dedicated to a distance of the resolution. Therefore, the maximum pixel spacing that provides the diffraction limit can be estimated as

$$d_{\text{pix}} = M\frac{0.61\lambda}{2NA},$$

where M is the magnification between the object and the CCD's plane. A graph representing how sampling influences the MTF of the system, including the CCD, is presented below.



CCD Sampling (cont.)

Oversampling means that more than the minimum number of pixels, according to the Nyquist criteria, are available for detection, which does not imply excessive sampling of the image. However, excessive sampling decreases the available field of view of a microscope. The relation between the extent of field D, the number of pixels in the x and y directions (N_x and N_y, respectively), and the pixel spacing d_{pix} can be calculated from

$$D_x = \frac{N_x d_{\text{pix}-x}}{M}$$

and

$$D_y = \frac{N_y d_{\text{pix}-y}}{M}.$$

This assumes that the object area imaged by the microscope is equal to or larger than D. Therefore, the size of the microscope's field of view and the size of the CCD chip should be matched.



Equation Summary

Quantized Energy:

$$E = h\nu = hc/\lambda$$

Propagation of an electric field and wave vector:

$$E = A\sin\left(\omega t - kz + \varphi_o\right) = A\exp\left[-i\left(\omega t - kz + \varphi_o\right)\right]$$

$$\omega = \frac{2\pi}{T} = \frac{2\pi V_m}{\lambda} \qquad E(z,t) = E_x + E_y$$

$$E_x = A_x \exp\left[-i\left(\omega t - kz + \varphi_x\right)\right] \qquad E_y = A_y \exp\left[-i\left(\omega t - kz + \varphi_y\right)\right]$$

Refractive index:

$$n = \frac{c}{V_m}$$

Optical path length:

$$\mathrm{OPL} = nL$$

$$\mathrm{OPL} = \int_{P1}^{P2} n\,ds$$

$$ds^2 = dx^2 + dy^2 + dz^2$$

Optical path difference and phase difference:

$$\mathrm{OPD} = n_1 L_1 - n_2 L_2$$

$$\Delta\varphi = 2\pi \frac{\mathrm{OPD}}{\lambda}$$

TIR:

$$\theta_{cr} = \arcsin\left(\frac{n_1}{n_2}\right)$$

$$I = I_o \exp\left(-y/d\right)$$

$$d = \frac{\lambda}{4\pi n_1} \frac{1}{\sqrt{\sin^2\theta - \sin^2\theta_c}}$$

Coherence length:

$$l_c = \frac{\lambda^2}{\Delta\lambda}$$

Equation Summary (cont'd)

Two-beam interference:

$$I = EE^*$$

$$I = I_1 + I_2 + 2\sqrt{I_1 I_2}\cos(\Delta\varphi)$$

$$\Delta\varphi = \varphi_2 - \varphi_1.$$

Contrast:

$$C = \frac{I_{\max} - I_{\min}}{I_{\max} + I_{\min}}$$

Diffraction grating equation:

$$m\lambda = d(\sin\beta \pm \sin\alpha)$$

Resolving power of diffraction grating:

$$\frac{\lambda}{\Delta\lambda} = mN$$

Free spectral range:

$$\Delta\lambda = \frac{m+1}{m}\lambda_1 - \lambda_1 = \frac{\lambda_1}{m}.$$

Newtonian equation:

$$xx' = ff'$$

$$xx' = -f'^2$$

Gaussian imaging equation:

$$\frac{n'}{z'} = \frac{n}{z} + \frac{1}{f_e}$$

$$\frac{1}{z'} = \frac{1}{z} + \frac{1}{f_e}$$

$$f_e = \frac{1}{\varphi} = -\frac{f}{n} = \frac{f'}{n'}$$

Transverse magnification:

$$M = \frac{h'}{h} = -\frac{x'}{f'} = -\frac{f}{x} = \frac{z'}{z} = \frac{-f}{z-f} = \frac{-(z'-f')}{f'}$$

Longitudinal magnification:

$$\frac{\Delta z'}{\Delta z} = \left(-\frac{f'}{f}\right) M_1 M_2$$

Equation Summary (cont'd)

Optical transfer function:

$$\mathrm{OTF}(\rho) = \mathrm{MTF}(\rho)\exp\left[i\varphi(\rho)\right]$$

Modulation transfer function:

$$\mathrm{MTF}(\rho) = \frac{C(\rho)_{\mathrm{image}}}{C(\rho)_{\mathrm{object}}}$$

Field of view of microscope:

$$\mathrm{FOV} = \frac{FieldNumber}{M_{\mathrm{objective}}}[\mathrm{mm}]$$

Magnifying power:

$$\mathrm{MP} = \frac{u'}{u} = \frac{d_o(f - z')}{f(z' - l)}$$

$$MP \approx \frac{250\ \mathrm{mm}}{f}$$

Magnification of the microscope objective:

$$M_{\mathrm{objective}} = \frac{OTL}{f_{\mathrm{objective}}}$$

Magnifying power of the microscope:

$$\mathrm{MP}_{\mathrm{microscope}} = M_{\mathrm{objective}}\mathrm{MP}_{\mathrm{eyepiece}} = -\frac{\mathrm{OTL}}{f_{\mathrm{objective}}}\frac{250\,\mathrm{mm}}{f_{\mathrm{eyepiece}}}$$

Numerical aperture:

$$NA = n\sin u$$

$$NA = NA'M_{\mathrm{objective}}$$

Airy disk:

$$d = \frac{1.22\lambda}{n\sin u} = \frac{1.22\lambda}{NA}$$

Rayleigh resolution limit:

$$d = \frac{0.61\lambda}{n\sin u} = \frac{0.61\lambda}{NA}$$

Sparrow resolution limit:

$$d = 0.5\lambda/NA$$

Equation Summary (cont'd)

Abbe resolution limit:

$$d = \frac{\lambda}{NA_{\text{objective}} + NA_{\text{condenser}}}$$

Resolving power of the microscope:

$$d_{\text{mic}} = \frac{d_{\text{eye}}}{M_{\text{min}}} = \frac{d_{\text{eye}}}{M_{\text{obj}} M_{\text{eyepiece}}}$$

Depth of focus and depth of field:

$$DOF = 2\Delta z' = \frac{n'\lambda}{\text{NA}'^2}$$

$$2\Delta z' = M^2_{\text{objective}} 2\Delta z \frac{n'}{n}$$

Depth perception of stereoscopic microscope:

$$\delta z = \frac{250\alpha_s}{M_{\text{microscope}} \tan\gamma} [\text{mm}]$$

Minimum perceived phase in phase contrast:

$$\Delta\varphi_{\text{min}} = \frac{C_{\text{ph-min}}\lambda}{4\pi\sqrt{N}}$$

Lateral resolution of the phase contrast:

$$d = f'_{\text{objective}} \frac{\lambda}{\left(r_{\text{AS}} + r_{\text{PR}}\right)}$$

Intensity in DIC:

$$I \propto \sin^2\left(\frac{\pi s \frac{d\varphi_o}{dx}}{\lambda}\right)$$

$$I \propto \sin^2 \frac{\pi\left(\Delta_b \pm s \frac{d\varphi_o}{dx}\right)}{\lambda}$$

Retardation:

$$\Gamma = \left(n_e - n_o\right)t$$

Equation Summary (cont'd)

Birefringence:

$$\delta = \frac{2\pi OPD}{\lambda} = \frac{2\pi\Gamma}{\lambda}$$

Resolution of a confocal microscope:

$$d_{xy} \approx \frac{0.4\lambda}{NA},$$

$$d_z \approx \frac{1.4n\lambda}{NA^2}$$

Confocal pinhole width:

$$D_{\text{pinhole}} = \frac{0.5\lambda M}{NA}$$

Fluorescent emission:

$$F = \sigma Q I$$

Probability of two-photon excitation:

$$n_{\text{a}} \propto \delta \left(\frac{P_{\text{avg}}^2}{\tau \nu^2} \right) \left(\pi \frac{NA^2}{hc\lambda} \right)^2$$

Intensity in FD-OCT:

$$I(k, z_{\text{o}}) = \int A_{\text{R}} A_{\text{S}}(z) \cos\left[k(z_{\text{m}} - z_{\text{o}}) \right] dz$$

Phase-shifting equation:

$$I(x,y) = a(x,y) + b(x,y)\cos(\varphi + n\Delta\varphi)$$

Three-image algorithm (π/2 shifts):

$$\varphi = \arctan\left(\frac{I_3 - I_2}{I_1 - I_2} \right)$$

Four-image algorithm:

$$\varphi = \arctan\left(\frac{I_4 - I_2}{I_1 - I_3} \right)$$

Five-image algorithm:

$$\varphi = \arctan\left(\frac{2[I_2 - I_4]}{I_1 - I_3 + I_5} \right)$$

Equation Summary (cont'd)

Image reconstruction structure illumination (sectioning):

$$I = \sqrt{\left(I_0 - I_{2\pi/3}\right)^2 + \left(I_0 - I_{4\pi/3}\right)^2 + \left(I_{2\pi/3} - I_{4\pi/3}\right)^2}$$

Poisson statistics:

$$P\left(k, N\right) = \frac{N^k e^{-N}}{k!}$$

Noise:

$$Noise\left[N_{\text{electrons}}\right] = \sqrt{\sigma^2_{\text{Photon}} + \sigma^2_{\text{Dark}} + \sigma^2_{\text{Read}}}$$

$$\sigma_{\text{Photon}} = \sqrt{\varphi\eta\tau}\ ,\ \ \sigma_{\text{Dark}} = \sqrt{I_{\text{Dark}}\tau}\ ,\ \ \sigma_{\text{Read}} = N_{\text{R}}\ ,\ I_{\text{Dark}}$$

Signal-to-noise ratio (SNR):

$$\text{Signal}\left[N_{\text{electrons}}\right] = \varphi\eta\tau$$

$$\text{SNR} = \frac{\varphi\eta\tau}{\sqrt{\varphi\eta\tau + I_{\text{dark}}\tau + N_{\text{R}}^2}}$$

$$\text{SNR} = \frac{\varphi\eta\tau}{\sqrt{\varphi\eta\tau}} = \sqrt{\varphi\eta\tau}$$

Bibliography

M. Bates, B. Huang, G.T. Dempsey, and X. Zhuang, "Multicolor Super-Resolution Imaging with Photo-Switchable Fluorescent Probes." *Science* **317**, 1749 (2007).

J. R. Benford, Microscope objectives, Chapter 4 (p. 178), in *Applied Optics and Optical Engineering, Vol. III,* R. Kingslake, ed., Academic Press, New York, NY (1965).

M. Born and E. Wolf, *Principles of Optics*, Sixth Edition, Cambridge University Press, Cambridge, UK (1997).

S. Bradbury and P. J. Evennett, *Contrast Techniques in Light Microscopy*, BIOS Scientific Publishers, Oxford, UK (1996).

T. Chen, T. Milster, S. K. Park, B. McCarthy, D. Sarid, C. Poweleit, and J. Menendez, "Near-field solid immersion lens microscope with advanced compact mechanical design." *Optical Engineering* **45**(10), 103002 (2006).

T. Chen, T. D. Milster, S. H. Yang, and D. Hansen, "Evanescent imaging with induced polarization by using a solid immersion lens." *Optics Letters* **32**(2), 124–126 (2007).

J.-X. Cheng and X. S. Xie, "Coherent anti-stokes raman scattering microscopy: instrumentation, theory, and applications." *J. Phys. Chem. B* **108***,* 827-840 (2004).

M. A. Choma, M. V. Sarunic, C. Yang, and J. A. Izatt, "Sensitivity advantage of swept source and Fourier domain optical coherence tomography." *Opt. Express* **11**, 2183–2189 (2003).

J. F. de Boer, B. Cense, B. H. Park, M.C. Pierce, G. J. Tearney, and B. E. Bouma, "Improved signal-to-noise ratio in spectral-domain compared with time-domain optical coherence tomography." *Opt Lett* **28**, 2067–2069 (2003).

E. Dereniak, materials for SPIE Short Course on Imaging Spectrometers, SPIE, Bellingham, WA (2005).

E. Dereniak, *Geometrical Optics*, Cambridge University Press, Cambridge, UK (2008).

M. Descour, materials for OPTI 412, "Optical Instrumentation," University of Arizona (2000).

Bibliography

D. Goldstein, *Polarized Light*, Second Edition, Marcel Dekker, New York, NY (1993).

D. S. Goodman, Basic optical instruments, Chapter 4, in Geometrical and Instrumental Optics, D. Malacara, ed., Academic Press, New York, NY (1988).

J. Goodman, *Introduction to Fourier Optics*, 3rd Edition, Roberts and Company Publishers, Greenwood Village, CO (2004).

E. P. Goodwin and J. C. Wyant, *Field Guide to Interferometric Optical Testing*, SPIE Press, Bellingham, WA (2006).

J. E. Greivenkamp, *Field Guide to Geometrical Optics*, SPIE Press, Bellingham, WA (2004).

H. Gross, F. Blechinger, and B. Achtner, *Handbook of Optical Systems*, *Vol. 4*: *Survey of Optical Instruments*, Wiley-VCH, Germany (2008).

M. G. L. Gustafsson, "Nonlinear structured-illumination microscopy: Wide-field fluorescence imaging with theoretically unlimited resolution." *PNAS*, **102**(37) 13081–13086 (2005).

M. G. L. Gustafsson, "Surpassing the lateral resolution limit by a factor of two using structured illumination microscopy." *Journal of Microscopy*, **198**(2), 82-87 (2000).

Gerd Häusler and Michael Walter Lindner, ""Coherence Radar" and "Spectral Radar"—New tools for dermatological diagnosis." *Journal of Biomedical Optics* **3**(1), 21–31 (1998).

E. Hecht, *Optics*, Fourth Edition, Addison-Wesley, Upper Saddle River, New Jersey (2002).

S. W. Hell, "Far-field optical nanoscopy." *Science* **316**, 1153 (2007).

B. Herman and J. Lemasters, *Optical Microscopy: Emerging Methods and Applications*, Academic Press, New York, NY (1993).

P. Hobbs, *Building Electro-Optical Systems: Making It All Work*, Wiley and Sons, New York, NY (2000).

Bibliography

G. Holst and T. Lomheim, *CMOS/CCD Sensors and Camera Systems*, JCD Publishing, Winter Park, FL (2007).

B. Huang, W. Wang, M. Bates, and X. Zhuang, "Three-dimensional super-resolution imaging by stochastic optical reconstruction microscopy." *Science* **319**, 810 (2008).

R. Huber, M. Wojtkowski, and J. G. Fujimoto, "Fourier domain mode locking (FDML): A new laser operating regime and applications for optical coherence tomography." *Opt. Express* **14**, 3225–3237 (2006).

Invitrogen, http://www.invitrogen.com

R. Jozwicki, *Teoria Odwzorowania Optycznego* (in Polish), PWN (1988).

R. Jozwicki, *Optyka Instrumentalna* (in Polish), WNT (1970).

R. Leitgeb, C. K. Hitzenberger, and A. F. Fercher, "Performance of Fourier-domain versus time-domain optical coherence tomography." *Opt. Express* **11**, 889–894 (2003).

D. Malacara and B. Thompson, Eds., *Handbook of Optical Engineering*, Marcel Dekker, New York, NY (2001).

D. Malacara and Z. Malacara, *Handbook of Optical Design*, Marcel Dekker, New York, NY (1994).

D. Malacara, M. Servin, and Z. Malacara, *Interferogram Analysis for Optical Testing*, Marcel Dekker, New York, NY (1998).

D. Murphy, *Fundamentals of Light Microscopy and Electronic Imaging*, Wiley-Liss, Wilmington, DE (2001).

P. Mouroulis and J. Macdonald, *Geometrical Optics and Optical Design*, Oxford University Press, New York, NY (1997).

M. A. A. Neil, R. Juškaitis, and T. Wilson, "Method of obtaining optical sectioning by using structured light in a conventional microscope." *Optics Letters*, **22**(24), 1905–1907 (1997).

Nikon Microscopy U, http://www.microscopyu.com/

Bibliography

C. Palmer (Erwin Loewen, First Edition), *Diffraction Grating Handbook*, Newport Corp. (2005).

K. Patorski, *Handbook of the Moiré Fringe Technique*, Elsevier, Oxford, UK(1993).

J. Pawley, Ed., *Biological Confocal Microscopy*, Third Edition, Springer, New York, NY (2006).

M. C. Pierce, D. J. Javier and R. Richards-Kortum, "Optical contrast agents and imaging systems for detection and diagnosis of cancer." *Int. J. Cancer* **123**, 1979–1990 (2008).

M. Pluta, *Advanced Light Microscopy, Volume One: Principle and Basic Properties*, PWN and Elsevier, New York, NY (1988).

M. Pluta, *Advanced Light Microscopy Volume Two: Specialized Methods*, PWN and Elsevier, New York, NY (1989).

M. Pluta, *Advanced Light Microscopy, Volume Three: Measuring Techniques*, PWN, Warsaw, Poland; and North Holland, Amsterdam, Holland (1993).

E. O. Potma, C. L. Evans, and X. S. Xie, "Heterodyne coherent anti-Stokes Raman scattering (CARS) imaging." *Optics Letters*, **31**(2), 241–243 (2006).

D. W. Robinson, G. T.Reed,, Eds., *Interferogram Analysis*, IOP Publishing, Bristol, UK (1993).

M. J. Rust, M. Bates, and X. Zhuang, "Sub-diffraction-limit imaging by stochastic optical reconstruction microscopy (STORM)." *Nature Methods*, **3**, 793–796 (2006).

B. Saleh and M. C. Teich, *Fundamentals of Photonics*, SecondEdition, Wiley, New York, NY (2007).

J. Schwiegerling, *Field Guide to Visual and Ophthalmic Optics*, SPIE Press, Bellingham, WA (2004).

W. Smith, *Modern Optical Engineering,* Third Edition, McGraw-Hill, New York, NY (2000).

D. Spector and R. Goldman, Eds., *Basic Methods in Microscopy*, Cold Spring Harbor Laboratory Press, Woodbury, NY (2006).

Bibliography

Thorlabs website resources: http://www.thorlabs.com/

P. Török and F. J. Kao, Eds., *Optical Imaging and Microscopy*, Springer, New York, NY (2007).

Veeco Optical Library entry, http://www.veeco.com/pdf/Optical_Library/Challenges_in_White_Light.pdf

R. Wayne, *Light and Video Microscopy*, Elsevier (reprinted by Academic Press), New York, NY (2009).

H. Yu, P. C. Cheng, P. C. Li, F. J. Kao, Eds., *Multi Modality Microscopy*, World Scientific, Hackensack, NJ (2006).

S. H. Yun, G. J. Tearney, B. J. Vakoc, M. Shishkov, W. Y. Oh, A. E. Desjardins, M. J. Suter, R. C. Chan, J. A. Evans, I. K. Jang, N. S. Nishioka, J. F. de Boer, and B. E. Bouma, "Comprehensive volumetric optical microscopy *in vivo*." *Nature Med* **12**, 1429–1433 (2006).

Zeiss Corporation, http://www.zeiss.com

Index

4Pi, 64, 109, 110
4Pi microscopy, 109

Abbe number, 25
Abbe resolution limit, 39
absorption filter, 60
achromatic objectives, 51
achromats, 51
Airy disk, 38
Amici lens, 55
amplitude contrast, 72
amplitude object, 63
amplitude ratio, 15
amplitude splitting, 17
analyzer, 83
anaxial illumination, 73
angular frequency, 4
angular magnification, 23
angular resolving power, 40
anisotropic media,
  propagation of light in, 9
aperture stop, 24
apochromats, 51
arc lamp, 58
array microscope, 113
array microscopy, 64, 113
astigmatism, 28
axial chromatic aberration, 26
axial resolution, 86

bandpass filter, 60
Bayer mask, 117
Bertrand lens, 45, 55
bias, 80
Brace Köhler compensator, 85
bright field, 64, 65, 76

charge-coupled device (CCD), 115
chief ray, 24
chromatic aberration, 26
chromatic resolving power, 20
circularly polarized light, 10
coherence length, 11
coherence scanning interferometry, 98
coherence time, 11
coherent, 11
coherent anti-Stokes Raman scattering (CARS), 64, 111
coma, 27
compensators, 83, 85
complex amplitudes, 12
compound microscope, 31
condenser's diaphragm, 46
cones, 32
confocal microscopy, 64, 86
contrast, 12
contrast of fringes, 15
cornea, 32
cover glass, 56
cover slip, 56
critical angle, 7
critical illumination, 46
cutoff frequency, 30

dark current, 118
dark field, 64, 65
dark noise, 118
de Sénarmont compensator, 85
depth of field, 41
depth of focus, 41
depth perception, 47
destructive interference, 19

Index

DIA, 44
DIC microscope design, 80
dichroic beam splitter, 91
dichroic mirror, 91
dielectric constant, 3
differential interference contrast (DIC), 64–65, 67, 79
diffraction, 18
diffraction grating, 19
diffraction orders, 19
digital microscopy, 114
digitiziation of CCD, 119
dispersion, 25
dispersion staining, 78
distortion, 28
dynamic range, 119

edge filter, 60
effective focal length, 22
electric fields, 12
electric vector, 10
electromagnetic spectrum, 2
electron-multiplying CCDs, 117
emission filter, 91
empty magnification, 40
entrance pupil, 24
entrance window, 24
epi-illumination, 44
epithelial cells, 2
evanescent wave microscopy, 105
excitation filter, 91
exit pupil, 24
exit window, 24
extraordinary wave, 9
eye, 32, 46
eye point, 48
eye relief, 48
eye's pupil, 46
eyepiece, 48

Fermat's principle, 5
field curvature, 28
field diaphragm, 46
field number (FN), 34, 48
field stop, 24, 34
filter turret, 92
filters, 91
finite tube length, 34
five-image technique, 102
fluorescence, 90
fluorescence microscopy, 64
fluorescent emission, 94
fluorites, 51
fluorophore quantum yield, 94
focal length, 21
focal plane, 21
focal point, 21
Fourier-domain OCT (FDOCT), 99
four-image technique, 102
fovea, 32
frame-transfer architecture, 116
Fraunhofer diffraction, 18
frequency of light, 1
Fresnel diffraction, 18
Fresnel reflection, 6
frustrated total internal reflection, 7
full-frame architecture, 116

gas-arc discharge lamp, 58
Gaussian imaging equation, 22
geometrical aberrations, 25

Index

geometrical optics, 21
Goos-Hänchen effect, 8
grating equation, 19–20

half bandwidth (HBW), 16
halo effect, 65, 71
halogen lamp, 58
high-eye point, 49
Hoffman modulation contrast, 75
Huygens, 48–49

I^5M, 64
image comparison, 65
image formation, 22
image space, 21
immersion liquid, 57
incandescent lamp, 58
incidence, 6
infinity-corrected objective, 35
infinity-corrected systems, 35
infrared radiation (IR), 2
intensity of light, 12
interference, 12
interference filter, 16, 60
interference microscopy, 64, 98
interference order, 16
interfering beams, 15
interferometers, 17
interline transfer architecture, 116
intermediate image plane, 46
inverted microscope, 33
iris, 32

Köhler illumination, 43–45

laser scanning, 64
lasers, 96
laser-scanning microscopy (LSM), 97
lateral magnification, 23
lateral resolution, 71
laws of reflection and refraction, 6
lens, 32
light sheet, 112
light sources for microscopy, common, 58
light-emitting diodes (LEDs), 59
limits of light microscopy, 110
linearly polarized light, 10
line-scanning confocal microscope, 87
Linnik, 101
long working distance objectives, 53
longitudinal magnification, 23
low magnification objectives, 54

Mach-Zehnder interferometer, 17
macula, 32
magnetic permeability, 3
magnification, 21, 23
magnifier, 31
magnifying power (MP), 37
marginal ray, 24
Maxwell's equations, 3
medium permittivity, 3
mercury lamp, 58
metal halide lamp, 58
Michelson, 17, 53, 98, 100, 101

Index

minimum focus distance, 32
Mirau, 53, 98, 101
modulation contrast microscopy (MCM), 74
modulation transfer function (MTF), 29
molecular absorption cross section, 94
monochromatic light, 11
multi-photon fluorescence, 95
multi-photon microscopy, 64
multiple beam interference, 16

nature of light, 1
near point, 32
negative birefringence, 9
negative contrast, 69
neutral density (ND), 60
Newtonian equation, 22
Nomarski interference microscope, 82
Nomarski prism, 62, 80
non-self-luminous, 63
numerical aperture (NA), 38, 50
Nyquist frequency, 120

object space, 21
objective, 31
objective correction, 50
oblique illumination, 73
optic axis, 9
optical coherence microscopy (OCM), 98
optical coherence tomography (OCT), 98
optical density (OD), 60
optical path difference (OPD), 5
optical path length (OPL), 5
optical power, 22
optical profilometry, 98, 101
optical rays, 21
optical sectioning, 103
optical spaces, 21
optical staining, 77
optical transfer function, 29
optical tube length, 34
ordinary wave, 9
oversampling, 121

PALM, 64, 110
paraxial optics, 21
parfocal distance, 34
partially coherent, 11
particle model, 1
performance metrics, 29
phase-advancing objects, 68
phase contrast microscope, 70
phase contrast, 64, 65, 66
phase object, 63
phase of light, 4
phase retarding objects, 68
phase-shifting algorithms, 102
phase-shifting interferometry (PSI), 98, 100
photobleaching, 94
photodiode, 115
photon noise, 118
Planck's constant, 1

Index

point spread function (PSF), 29
point-scanning confocal microscope, 87
Poisson statistics, 118
polarization microscope, 84
polarization microscopy, 64, 83
polarization of light, 10
polarization prisms, 61
polarization states, 10
polarizers, 61–62
positive birefringence, 9
positive contrast, 69
pupil function, 29

quantum efficiency (QE), 97, 117
quasi-monochromatic, 11
quenching, 94

Raman microscopy, 64, 111
Raman scattering, 111
Ramsden eyepiece, 48
Rayleigh resolution limit, 39
read noise, 118
real image, 22
red blood cells, 2
reflectance coefficients, 6
reflected light, 6, 16
reflection law, 6
reflective grating, 20
refracted light, 6
refraction law, 6
refractive index, 4
RESOLFT, 64, 110

resolution limit, 39
retardation, 83
retina, 32
RGB filters, 117
Rheinberg illumination, 77
rods, 32

Sagnac interferometer, 17
sample conjugate, 46
sample path, 44
scanning approaches, 87
scanning white light interferometry, 98
Selective plane illumination microscopy (SPIM), 64, 112
self-luminous, 63
semi-apochromats, 51
shading-off effect, 71
shearing interferometer, 17
shearing interferometry, 79
shot noise, 118
SI, 64
sign convention, 21
signal-to-noise ratio (SNR), 119
Snell's law, 6
solid immersion, 106
solid immersion lenses (SILs), 106
Sparrow resolution limit, 30
spatial coherence, 11
spatial resolution, 86
spectral-domain OCT (SDOCT), 99
spectrum of microscopy, 2
spherical aberration, 27
spinning-disc confocal imaging, 88
stereo microscopes, 47

Index

stimulated emission depletion (STED), 107
stochastic optical reconstruction microscopy (STORM), 64, 108, 110
Stokes shift, 90
Strehl ratio, 29, 30
structured illumination, 103
super-resolution microscopy, 64
swept-source OCT (SSOCT), 99

telecentricity, 36
temporal coherence, 11, 13–14
thin lenses, 21
three-image technique, 102
total internal reflection (TIR), 7
total internal reflection fluorescence (TIRF) microscopy, 105
transmission coefficients, 6
transmission grating, 20
transmitted light, 16
transverse chromatic aberration, 26
transverse magnification, 23
tube length, 34
tube lens, 35
tungsten-argon lamp, 58

ultraviolet radiation (UV), 2
undersampling, 120
uniaxial crystals, 9
upright microscope, 33
useful magnification, 40
UV objectives, 54

velocity of light, 1
vertical scanning interferometry (VSI), 98, 100
virtual image, 22
visibility, 12
visibility in phase contrast, 69
visible spectrum (VIS), 2
visual stereo resolving power, 47

water immersion objectives, 54
wave aberrations, 25
wave equations, 3
wave group, 11
wave model, 1
wave number, 4
wave plate compensator, 85
wavefront propagation, 4
wavefront splitting, 17
wavelength of light, 1
Wollaston prism, 61, 80
working distance (WD), 50

x-ray radiation, 2

Tomasz S. Tkaczyk is an Assistant Professor of Bioengineering and Electrical and Computer Engineering at Rice University, Houston, Texas, where he develops modern optical instrumentation for biological and medical applications. His primary research is in microscopy, including endo-microscopy, cost-effective high-performance optics for diagnostics, and multi-dimensional imaging (snapshot hyperspectral microscopy and spectro-polarimetry).

Professor Tkaczyk received his M.S. and Ph.D. from the Institute of Micromechanics and Photonics, Department of Mechatronics, Warsaw University of Technology, Poland. Beginning in 2003, after his postdoctoral training, he worked as a research professor at the College of Optical Sciences, University of Arizona. He joined Rice University in the summer of 2007.

Fundamental Optics

1



Introduction **1.2**
Paraxial Formulas **1.3**
Imaging Properties of Lens Systems **1.6**
Lens Combination Formulas **1.8**
Performance Factors **1.11**
Lens Shape **1.17**
Lens Combinations **1.18**
Diffraction Effects **1.20**
Lens Selection **1.23**
Spot Size **1.26**
Aberration Balancing **1.27**
Definition of Terms **1.29**
Paraxial Lens Formulas **1.32**
Principal-Point Locations **1.36**
Prisms **1.37**
Polarization **1.41**
Waveplates **1.46**
Etalons **1.49**
Ultrafast Theory **1.52**

Introduction

The process of solving virtually any optical engineering problem can be broken down into two main steps. First, paraxial calculations (first order) are made to determine critical parameters such as magnification, focal length(s), clear aperture (diameter), and object and image position. These paraxial calculations are covered in the next section of this chapter.

Second, actual components are chosen based on these paraxial values, and their actual performance is evaluated with special attention paid to the effects of aberrations. A truly rigorous performance analysis for all but the simplest optical systems generally requires computer ray tracing, but simple generalizations can be used, especially when the lens selection process is confined to a limited range of component shapes.

In practice, the second step may reveal conflicts with design constraints, such as component size, cost, or product availability. System parameters may therefore require modification.

Because some of the terms used in this chapter may not be familiar to all readers, a glossary of terms is provided in *Definition of Terms*.

Finally, it should be noted that the discussion in this chapter relates only to systems with uniform illumination; optical systems for Gaussian beams are covered in *Gaussian Beam Optics*.

Engineering Support

CVI Melles Griot maintains a staff of knowledgeable, experienced applications engineers at each of our facilities worldwide. The information given in this chapter is sufficient to enable the user to select the most appropriate catalog lenses for the most commonly encountered applications. However, when additional optical engineering support is required, our applications engineers are available to provide assistance. Do not hesitate to contact us for help in product selection or to obtain more detailed specifications on CVI Melles Griot products.

THE OPTICAL ENGINEERING PROCESS


Determine basic system parameters, such as magnification and object/image distances
Using paraxial formulas and known parameters, solve for remaining values
Pick lens components based on paraxially derived values
Determine if chosen component values conflict with any basic system constraints
Estimate performance characteristics of system
Determine if performance characteristics meet original design goals

Fundamental Optics
Gaussian Beam Optics
Optical Specifications
Material Properties
Optical Coatings

Paraxial Formulas

Sign Conventions

The validity of the paraxial lens formulas is dependent on adherence to the following sign conventions:

For lenses: (refer to figure 1.1)

s is + for object to left of H (the first principal point)

s is − for object to right of H

s'' is + for image to right of H″ (the second principal point)

s'' is − for image to left of H″

m is + for an inverted image

m is − for an upright image

For mirrors:

f is + for convex (diverging) mirrors

f is − for concave (converging) mirrors

s is + for object to left of H

s is − for object to right of H

s'' is − for image to right of H″

s'' is + for image to left of H″

m is + for an inverted image

m is − for an upright image

When using the thin-lens approximation, simply refer to the left and right of the lens.



Note location of object and image relative to front and rear focal points.

ϕ = lens diameter

CA = clear aperture (typically 90% of ϕ)

f = effective focal length (EFL) which may be positive (as shown) or negative. f represents both FH and H″F″, assuming lens is surrounded by medium of index 1.0

m = $s''/s = h''/h$ = magnification or conjugate ratio, said to be infinite if either s'' or s is infinite

θ = arcsin (CA/2s)

s = object distance, positive for object (whether real or virtual) to the left of principal point H

s'' = image distance (s and s'' are collectively called conjugate distances, with object and image in conjugate planes), positive for image (whether real or virtual) to the right of principal point H″

h = object height

h'' = image height

Figure 1.1 **Sign conventions**

Typically, the first step in optical problem solving is to select a system focal length based on constraints such as magnification or conjugate distances (object and image distance). The relationship among focal length, object position, and image position is given by

$$\frac{1}{f}=\frac{1}{s}+\frac{1}{s''} \tag{1.1}$$

This formula is referenced to figure 1.1 and the sign conventions given in *Sign Conventions*.

By definition, magnification is the ratio of image size to object size or

$$m=\frac{s''}{s}=\frac{h''}{h}. \tag{1.2}$$

This relationship can be used to recast the first formula into the following forms:

$$f=m\frac{(s+s'')}{(m+1)^2} \tag{1.3}$$

$$f=\frac{sm}{m+1} \tag{1.4}$$

$$f=\frac{s+s''}{m+2+\frac{1}{m}} \tag{1.5}$$

$$s(m+1)=s+s'' \tag{1.6}$$

where $(s+s'')$ is the approximate object-to-image distance.

With a real lens of finite thickness, the image distance, object distance, and focal length are all referenced to the principal points, not to the physical center of the lens. By neglecting the distance between the lens' principal points, known as the hiatus, $s+s''$ becomes the object-to-image distance. This simplification, called the thin-lens approximation, can speed up calculation when dealing with simple optical systems.

Example 1: Object outside Focal Point

A 1-mm-high object is placed on the optical axis, 200 mm left of the left principal point of a LDX-25.0-51.0-C ($f=50$ mm). Where is the image formed, and what is the magnification? (See figure 1.2.)

$$\frac{1}{s''}=\frac{1}{f}-\frac{1}{s}$$

$$\frac{1}{s''}=\frac{1}{50}-\frac{1}{200}$$

$$s''=66.7\text{ mm}$$

$$m=\frac{s''}{s}=\frac{66.7}{200}=0.33$$

or real image is 0.33 mm high and inverted.



Figure 1.2 **Example 1** ($f=50$ mm, $s=200$ mm, $s''=66.7$ mm)

Example 2: Object inside Focal Point

The same object is placed 30 mm left of the left principal point of the same lens. Where is the image formed, and what is the magnification? (See figure 1.3.)

$$\frac{1}{s''}=\frac{1}{50}-\frac{1}{30}$$

$$s''=-75\text{ mm}$$

$$m=\frac{s''}{s}=\frac{-75}{30}=-2.5$$

or virtual image is 2.5 mm high and upright.

In this case, the lens is being used as a magnifier, and the image can be viewed only back through the lens.



Figure 1.3 **Example 2** ($f=50$ mm, $s=30$ mm, $s''=-75$ mm)

Example 3: Object at Focal Point

A 1-mm-high object is placed on the optical axis, 50 mm left of the first principal point of an LDK-50.0-52.2-C ($f=-50$ mm). Where is the image formed, and what is the magnification? (See figure 1.4.)

$$\frac{1}{s''}=\frac{1}{-50}-\frac{1}{50}$$

$$s''=-25\text{ mm}$$

$$m=\frac{s''}{s}=\frac{-25}{50}=-0.5$$

or virtual image is 0.5 mm high and upright.



Figure 1.4 **Example 3** ($f = -50$ mm, $s = 50$ mm, $s'' = -25$ mm)



Figure 1.5 **F-number and numerical aperture**

A simple graphical method can also be used to determine paraxial image location and magnification. This graphical approach relies on two simple properties of an optical system. First, a ray that enters the system parallel to the optical axis crosses the optical axis at the focal point. Second, a ray that enters the first principal point of the system exits the system from the second principal point parallel to its original direction (i.e., its exit angle with the optical axis is the same as its entrance angle). This method has been applied to the three previous examples illustrated in figures 1.2 through 1.4. Note that by using the thin-lens approximation, this second property reduces to the statement that a ray passing through the center of the lens is undeviated.

F-NUMBER AND NUMERICAL APERTURE

The paraxial calculations used to determine the necessary element diameter are based on the concepts of focal ratio (f-number or f/#) and numerical aperture (NA). The f-number is the ratio of the focal length of the lens to its "effective" diameter, the clear aperture (CA).

$$\text{f-number} = \frac{f}{\text{CA}} . \tag{1.7}$$

To visualize the f-number, consider a lens with a positive focal length illuminated uniformly with collimated light. The f-number defines the angle of the cone of light leaving the lens which ultimately forms the image. This is an important concept when the throughput or light-gathering power of an optical system is critical, such as when focusing light into a monochromator or projecting a high-power image.

The other term used commonly in defining this cone angle is numerical aperture. The NA is the sine of the angle made by the marginal ray with the optical axis. By referring to figure 1.5 and using simple trigonometry, it can be seen that

$$\text{NA} = \sin\theta = \frac{\text{CA}}{2f} \tag{1.8}$$

and

$$\text{NA} = \frac{1}{2(\text{f-number})} . \tag{1.9}$$

Ray f-numbers can also be defined for any arbitrary ray if its conjugate distance and the diameter at which it intersects the principal surface of the optical system are known.

NOTE

Because the sign convention given previously is not used universally in all optics texts, the reader may notice differences in the paraxial formulas. However, results will be correct as long as a consistent set of formulas and sign conventions is used.

Imaging Properties of Lens Systems

THE OPTICAL INVARIANT

To understand the importance of the NA, consider its relation to magnification. Referring to figure 1.6,

$$\text{NA (object side)} = \sin\theta = \frac{\text{CA}}{2s} \tag{1.10}$$

$$\text{NA}'' \text{ (image side)} = \sin\theta'' = \frac{\text{CA}}{2s''} \tag{1.11}$$

which can be rearranged to show

$$\text{CA} = 2s\ \sin\theta \tag{1.12}$$

and

$$\text{CA} = 2s''\sin\theta'' \tag{1.13}$$

leading to

$$\frac{s''}{s} = \frac{\sin\theta}{\sin\theta''} = \frac{\text{NA}}{\text{NA}''}. \tag{1.14}$$

Since $\frac{s''}{s}$ is simply the magnification of the system,

we arrive at

$$m = \frac{\text{NA}}{\text{NA}''}. \tag{1.15}$$

The magnification of the system is therefore equal to the ratio of the NAs on the object and image sides of the system. This powerful and useful result is completely independent of the specifics of the optical system, and it can often be used to determine the optimum lens diameter in situations involving aperture constraints.

When a lens or optical system is used to create an image of a source, it is natural to assume that, by increasing the diameter (ϕ) of the lens, thereby increasing its CA, we will be able to collect more light and thereby produce a brighter image. However, because of the relationship between magnification and NA, there can be a theoretical limit beyond which increasing the diameter has no effect on light-collection efficiency or image brightness.

Since the NA of a ray is given by CA/2s, once a focal length and magnification have been selected, the value of NA sets the value of CA. Thus, if one is dealing with a system in which the NA is constrained on either the object or image side, increasing the lens diameter beyond this value will increase system size and cost but will not improve performance (i.e., throughput or image brightness). This concept is sometimes referred to as the optical invariant.

SAMPLE CALCULATION

To understand how to use this relationship between magnification and NA, consider the following example.

Example: System with Fixed Input NA

Two very common applications of simple optics involve coupling light into an optical fiber or into the entrance slit of a monochromator. Although these problems appear to be quite different, they both have the same limitation — they have a fixed NA. For monochromators, this limit is usually expressed in terms of the f-number. In addition to the fixed NA, they both have a fixed entrance pupil (image) size.

Suppose it is necessary, using a singlet lens, to couple the output of an incandescent bulb with a filament 1 mm in diameter into an optical fiber as shown in figure 1.7. Assume that the fiber has a core diameter of 100 μm and an NA of 0.25, and that the design requires that the total distance from the source to the fiber be 110 mm. Which lenses are appropriate?

By definition, the magnification must be 0.1. Letting $s+s''$ total 110 mm (using the thin-lens approximation), we can use equation 1.3,

$$f = m\frac{(s+s'')}{(m+1)^2}, \tag*{(see eq. 1.3)}$$

to determine that the focal length is 9.1 mm. To determine the conjugate distances, s and s'', we utilize equation 1.6,

$$s(m+1) = s+s'', \tag*{(see eq. 1.6)}$$

and find that $s = 100$ mm and $s'' = 10$ mm.

We can now use the relationship NA = CA/2s or NA″ = CA/2s'' to derive CA, the optimum clear aperture (effective diameter) of the lens.

With an image NA of 0.25 and an image distance (s'') of 10 mm,

$$0.25 = \frac{\text{CA}}{20}$$

and

$$\text{CA} = 5\text{ mm}.$$

Accomplishing this imaging task with a single lens therefore requires an optic with a 9.1-mm focal length and a 5-mm diameter. Using a larger diameter lens will not result in any greater system throughput because of the limited input NA of the optical fiber. The singlet lenses in this catalog that meet these criteria are LPX-5.0-5.2-C, which is plano-convex, and LDX-6.0-7.7-C and LDX-5.0-9.9-C, which are biconvex.

Making some simple calculations has reduced our choice of lenses to just three. The following chapter, *Gaussian Beam Optics*, discusses how to make a final choice of lenses based on various performance criteria.

1ch_FundamentalOptics_Final_a.qxd 6/15/2009 2:28 PM Page 1.7


CA
2
s
s″
θ
θ″
CA
image side
object side

Figure 1.6 **Numerical aperture and magnification**


magnification = $\frac{h''}{h}$ = $\frac{0.1}{1.0}$ = 0.1×
optical system
f = 9.1 mm
filament
h = 1 mm
NA = $\frac{CA}{2s}$ = 0.025
NA″ = $\frac{CA}{2s''}$ = 0.25
CA = 5 mm
fiber core
h'' = 0.1 mm
s = 100 mm
s'' = 10 mm
$s + s''$ = 110 mm

Figure 1.7 **Optical system geometry for focusing the output of an incandescent bulb into an optical fiber**

1ch_FundamentalOptics_Final_a.qxd 6/15/2009 2:28 PM Page 1.8

Lens Combination Formulas

Many optical tasks require several lenses in order to achieve an acceptable level of performance. One possible approach to lens combinations is to consider each image formed by each lens as the object for the next lens and so on. This is a valid approach, but it is time consuming and unnecessary.

It is much simpler to calculate the effective (combined) focal length and principal-point locations and then use these results in any subsequent paraxial calculations (see figure 1.8). They can even be used in the optical invariant calculations described in the preceding section.

EFFECTIVE FOCAL LENGTH

The following formulas show how to calculate the effective focal length and principal-point locations for a combination of any two arbitrary components. The approach for more than two lenses is very simple: Calculate the values for the first two elements, then perform the same calculation for this combination with the next lens. This is continued until all lenses in the system are accounted for.

The expression for the combination focal length is the same whether lens separation distances are large or small and whether f_1 and f_2 are positive or negative:

$$f = \frac{f_1 f_2}{f_1 + f_2 - d}. \qquad (1.16)$$

This may be more familiar in the form

$$\frac{1}{f} = \frac{1}{f_1} + \frac{1}{f_2} - \frac{d}{f_1 f_2}. \qquad (1.17)$$

Notice that the formula is symmetric with respect to the interchange of the lenses (end-for-end rotation of the combination) at constant *d*. The next two formulas are not.

COMBINATION FOCAL-POINT LOCATION

For all values of f_1, f_2, and d, the location of the focal point of the combined system (s_2''), measured from the secondary principal point of the second lens (H_2''), is given by

$$s_2'' = \frac{f_2(f_1 - d)}{f_1 + f_2 - d}. \qquad (1.18)$$

This can be shown by setting $s_1 = d - f_1$ (see figure 1.8a), and solving

$$\frac{1}{f_2} = \frac{1}{s_1} + \frac{1}{s_2''}$$

for s_2''.

Symbols

f_c = combination focal length (EFL), positive if combination final focal point falls to the right of the combination secondary principal point, negative otherwise (see figure 1.8c).

f_1 = focal length of the first element (see figure 1.8a).

f_2 = focal length of the second element.

d = distance from the secondary principal point of the first element to the primary principal point of the second element, positive if the primary principal point is to the right of the secondary principal point, negative otherwise (see figure 1.8b).

s_1'' = distance from the primary principal point of the first element to the final combination focal point (location of the final image for an object at infinity to the right of both lenses), positive if the focal point is to left of the first element's primary principal point (see figure 1.8d).

s_2'' = distance from the secondary principal point of the second element to the final combination focal point (location of the final image for an object at infinity to the left of both lenses), positive if the focal point is to the right of the second element's secondary principal point (see figure 1.8b).

z_H = distance to the combination primary principal point measured from the primary principal point of the first element, positive if the combination secondary principal point is to the right of secondary principal point of second element (see figure 1.8d).

z_H'' = distance to the combination secondary principal point measured from the secondary principal point of the second element, positive if the combination secondary principal point is to the right of the secondary principal point of the second element (see figure 1.8c).

Note: *These paraxial formulas apply to* ***coaxial*** *combinations of both thick and thin lenses immersed in air or any other fluid with refractive index independent of position. They assume that light propagates from left to right through an optical system.*

COMBINATION SECONDARY PRINCIPAL-POINT LOCATION

Because the thin-lens approximation is obviously highly invalid for most combinations, the ability to determine the location of the secondary principal point is vital for accurate determination of d when another element is added. The simplest formula for this calculates the distance from the secondary principal point of the final (second) element to the secondary principal point of the combination (see figure 1.8b):

$$z = s_2'' - f \; . \qquad (1.19)$$

COMBINATION EXAMPLES

It is possible for a lens combination or system to exhibit principal planes that are far removed from the system. When such systems are themselves combined, negative values of d may occur. Probably the simplest example of a negative d-value situation is shown in figure 1.9. Meniscus lenses with steep surfaces have external principal planes. When two of these lenses are brought into contact, a negative value of d can occur. Other combined-lens examples are shown in figures 1.10 through 1.13.



Figure 1.9 **"Extreme" meniscus-form lenses with external principal planes** (drawing not to scale)



Figure 1.8 **Lens combination focal length and principal planes**

Fundamental Optics
Gaussian Beam Optics
Optical Specifications
Material Properties
Optical Coatings



Figure 1.10 **Positive lenses separated by distance greater than $f_1 + f_2$:** f is negative and both s_2'' and z are positive. Lens symmetry is not required.



Figure 1.11 **Achromatic combinations:** Air-spaced lens combinations can be made nearly achromatic, even though both elements are made from the same material. Achieving achromatism requires that, in the thin-lens approximation,

$$d=\frac{(f_1+f_2)}{2}.$$

This is the basis for Huygens and Ramsden eyepieces.

This approximation is adequate for most thick-lens situations. The signs of f_1, f_2, and d are unrestricted, but d must have a value that guarantees the existence of an air space. Element shapes are unrestricted and can be chosen to compensate for other aberrations.



Figure 1.12 **Telephoto combination:** The most important characteristic of the telephoto lens is that the EFL, and hence the image size, can be made much larger than the distance from the first lens surface to the image would suggest by using a positive lens followed by a negative lens (but not necessarily the lens shapes shown in the figure). For example, f_1 is positive and $f_2 = -f_1/2$. Then f is negative for d less than $f_1/2$, infinite for $d = f_1/2$ (Galilean telescope or beam expander), and positive for d larger than $f_1/2$. To make the example even more specific, catalog lenses LDX-50.8-130.4-C and LDK-42.0-52.2-C, with $d = 78.2$ mm, will yield $s_2'' = 2.0$ m, $f = 5.2$ m, and $z = 43.2$ m.



Figure 1.13 **Condenser configuration:** The convex vertices of a pair of identical plano-convex lenses are on contact. (The lenses could also be plano aspheres.) Because $d = 0$, $f = f_1/2 = f_2/2$, $f_1/2 = s_2''$, and $z = 0$. The secondary principal point of the second element and the secondary principal point of the combination coincide at H″, at depth t_c/n beneath the vertex of the plano surface of the second element, where t_c is the element center thickness and n is the refractive index of the element. By symmetry, the primary principal point of the combination is similarly located in the first element. Combination conjugate distances must be measured from these points.

Performance Factors

After paraxial formulas have been used to select values for component focal length(s) and diameter(s), the final step is to select actual lenses. As in any engineering problem, this selection process involves a number of tradeoffs, including performance, cost, weight, and environmental factors.

The performance of real optical systems is limited by several factors, including lens aberrations and light diffraction. The magnitude of these effects can be calculated with relative ease.

Numerous other factors, such as lens manufacturing tolerances and component alignment, impact the performance of an optical system. Although these are not considered explicitly in the following discussion, it should be kept in mind that if calculations indicate that a lens system only just meets the desired performance criteria, in practice it may fall short of this performance as a result of other factors. In critical applications, it is generally better to select a lens whose calculated performance is significantly better than needed.

DIFFRACTION

Diffraction, a natural property of light arising from its wave nature, poses a fundamental limitation on any optical system. Diffraction is always present, although its effects may be masked if the system has significant aberrations. When an optical system is essentially free from aberrations, its performance is limited solely by diffraction, and it is referred to as diffraction limited.

In calculating diffraction, we simply need to know the focal length(s) and aperture diameter(s); we do not consider other lens-related factors such as shape or index of refraction.

Since diffraction increases with increasing f-number, and aberrations decrease with increasing f-number, determining optimum system performance often involves finding a point where the combination of these factors has a minimum effect.

ABERRATIONS

To determine the precise performance of a lens system, we can trace the path of light rays through it, using Snell's law at each optical interface to determine the subsequent ray direction. This process, called ray tracing, is usually accomplished on a computer. When this process is completed, it is typically found that not all the rays pass through the points or positions predicted by paraxial theory. These deviations from ideal imaging are called lens aberrations.

The direction of a light ray after refraction at the interface between two homogeneous, isotropic media of differing index of refraction is given by Snell's law:

$$n_1 \sin\theta_1 = n_2 \sin\theta_2 \qquad (1.20)$$

where θ_1 is the angle of incidence, θ_2 is the angle of refraction, and both angles are measured from the surface normal as shown in figure 1.14.



Figure 1.14 **Refraction of light at a dielectric boundary**

APPLICATION NOTE

Technical Assistance

Detailed performance analysis of an optical system is accomplished by using computerized ray-tracing software. CVI Melles Griot applications engineers are able to provide a ray-tracing analysis of simple catalog-component systems. If you need assistance in determining the performance of your optical system, or in selecting optimum components for your particular application, please contact your nearest CVI Melles Griot office.

Even though tools for the precise analysis of an optical system are becoming easier to use and are readily available, it is still quite useful to have a method for quickly estimating lens performance. This not only saves time in the initial stages of system specification, but can also help achieve a better starting point for any further computer optimization.

The first step in developing these rough guidelines is to realize that the sine functions in Snell's law can be expanded in an infinite Taylor series:

$$\sin\theta_1 = \theta_1 - \theta_1^3/3! + \theta_1^5/5! - \theta_1^7/7! + \theta_1^9/9! - \ldots \qquad (1.21)$$

The first approximation we can make is to replace all the sine functions with their arguments (i.e., replace $\sin\theta_1$ with θ_1 itself and so on). This is called first-order or paraxial theory because only the first terms of the sine expansions are used. Design of any optical system generally starts with this approximation using the paraxial formulas.

The assumption that $\sin\theta = \theta$ is reasonably valid for θ close to zero (i.e., high f-number lenses). With more highly curved surfaces (and particularly marginal rays), paraxial theory yields increasingly large deviations from real performance because $\sin\theta \neq \theta$. These deviations are known as aberrations. Because a perfect optical system (one without any aberrations) would form its image at the point and to the size indicated by paraxial theory, aberrations are really a measure of how the image differs from the paraxial prediction.

As already stated, exact ray tracing is the only rigorous way to analyze real lens surfaces. Before the advent of electronic computers, this was excessively tedious and time consuming. Seidel* addressed this issue by developing a method of calculating aberrations resulting from the $\theta_1^3/3!$ term. The resultant third-order lens aberrations are therefore called Seidel aberrations.

To simplify these calculations, Seidel put the aberrations of an optical system into several different classifications. In monochromatic light they are spherical aberration, astigmatism, field curvature, coma, and distortion. In polychromatic light there are also chromatic aberration and lateral color. Seidel developed methods to approximate each of these aberrations without actually tracing large numbers of rays using all the terms in the sine expansions.

In actual practice, aberrations occur in combinations rather than alone. This system of classifying them, which makes analysis much simpler, gives a good description of optical system image quality. In fact, even in the era of powerful ray-tracing software, Seidel's formula for spherical aberration is still widely used.

SPHERICAL ABERRATION

Figure 1.15 illustrates how an aberration-free lens focuses incoming collimated light. All rays pass through the focal point F″. The lower figure shows the situation more typically encountered in single lenses. The farther from the optical axis the ray enters the lens, the nearer to the lens it focuses (crosses the optical axis). The distance along the optical axis between the intercept of the rays that are nearly on the optical axis (paraxial rays) and the rays that go through the edge of the lens (marginal rays) is called longitudinal spherical aberration (LSA). The height at which these rays intercept the paraxial focal plane is called transverse spherical aberration (TSA). These quantities are related by

$$\mathrm{TSA} = \mathrm{LSA} \times \tan(u''). \qquad (1.22)$$

Spherical aberration is dependent on lens shape, orientation, and conjugate ratio, as well as on the index of refraction of the materials present. Parameters for choosing the best lens shape and orientation for a given task are presented later in this chapter. However, the third-


F″
aberration-free lens
paraxial focal plane
u″
F″
TSA
LSA
longitudinal spherical aberration
transverse spherical aberration

Figure 1.15 **Spherical aberration of a plano-convex lens**

order, monochromatic, spherical aberration of a plano-convex lens used at infinite conjugate ratio can be estimated by

---

* *Ludwig von Seidel, 1857.*

$$\text{spot size due to spherical aberration} = \frac{0.067\,f}{f/\#^3}. \tag{1.23}$$

Theoretically, the simplest way to eliminate or reduce spherical aberration is to make the lens surface(s) with a varying radius of curvature (i.e., an aspheric surface) designed to exactly compensate for the fact that sin $\theta \neq \theta$ at larger angles. In practice, however, most lenses with high surface accuracy are manufactured by grinding and polishing techniques that naturally produce spherical or cylindrical surfaces. The manufacture of aspheric surfaces is more complex, and it is difficult to produce a lens of sufficient surface accuracy to eliminate spherical aberration completely. Fortunately, these aberrations can be virtually eliminated, for a chosen set of conditions, by combining the effects of two or more spherical (or cylindrical) surfaces.

In general, simple positive lenses have undercorrected spherical aberration, and negative lenses usually have overcorrected spherical aberration. By combining a positive lens made from low-index glass with a negative lens made from high-index glass, it is possible to produce a combination in which the spherical aberrations cancel but the focusing powers do not. The simplest examples of this are cemented doublets, such as the LAO series which produce minimal spherical aberration when properly used.

ASTIGMATISM

When an off-axis object is focused by a spherical lens, the natural asymmetry leads to astigmatism. The system appears to have two different focal lengths.

As shown in figure 1.16, the plane containing both optical axis and object point is called the tangential plane. Rays that lie in this plane are called tangential, or meridional, rays. Rays not in this plane are referred to as skew rays. The chief, or principal, ray goes from the object point through the center of the aperture of the lens system. The plane perpendicular to the tangential plane that contains the principal ray is called the sagittal or radial plane.

The figure illustrates that tangential rays from the object come to a focus closer to the lens than do rays in the sagittal plane. When the image is evaluated at the tangential conjugate, we see a line in the sagittal direction. A line in the tangential direction is formed at the sagittal conjugate. Between these conjugates, the image is either an elliptical or a circular blur. Astigmatism is defined as the separation of these conjugates.

The amount of astigmatism in a lens depends on lens shape only when there is an aperture in the system that is not in contact with the lens itself. (In all optical systems there is an aperture or stop, although in many cases it is simply the clear aperture of the lens element itself.) Astigmatism strongly depends on the conjugate ratio.



Figure 1.16 **Astigmatism represented by sectional views**

1ch_FundamentalOptics_Final_a.qxd 6/15/2009 2:28 PM Page 1.14

COMA

In spherical lenses, different parts of the lens surface exhibit different degrees of magnification. This gives rise to an aberration known as coma. As shown in figure 1.17, each concentric zone of a lens forms a ring-shaped image called a comatic circle. This causes blurring in the image plane (surface) of off-axis object points. An off-axis object point is not a sharp image point, but it appears as a characteristic comet-like flare. Even if spherical aberration is corrected and the lens brings all rays to a sharp focus on axis, a lens may still exhibit coma off axis. See figure 1.18.

As with spherical aberration, correction can be achieved by using multiple surfaces. Alternatively, a sharper image may be produced by judiciously placing an aperture, or stop, in an optical system to eliminate the more marginal rays.

FIELD CURVATURE

Even in the absence of astigmatism, there is a tendency of optical systems to image better on curved surfaces than on flat planes. This effect is called field curvature (see figure 1.19). In the presence of astigmatism, this problem is compounded because two separate astigmatic focal surfaces correspond to the tangential and sagittal conjugates.

Field curvature varies with the square of field angle or the square of image height. Therefore, by reducing the field angle by one-half, it is possible to reduce the blur from field curvature to a value of 0.25 of its original size.

Positive lens elements usually have inward curving fields, and negative lenses have outward curving fields. Field curvature can thus be corrected to some extent by combining positive and negative lens elements.



Figure 1.18 **Positive transverse coma**



Figure 1.19 **Field curvature**



Figure 1.17 **Imaging an off-axis point source by a lens with positive transverse coma**

DISTORTION

The image field not only may have curvature but may also be distorted. The image of an off-axis point may be formed at a location on this surface other than that predicted by the simple paraxial equations. This distortion is different from coma (where rays from an off-axis point fail to meet perfectly in the image plane). Distortion means that even if a perfect off-axis point image is formed, its location on the image plane is not correct. Furthermore, the amount of distortion usually increases with increasing image height. The effect of this can be seen as two different kinds of distortion: pincushion and barrel (see figure 1.20). Distortion does not lower system resolution; it simply means that the image shape does not correspond exactly to the shape of the object. Distortion is a separation of the actual image point from the paraxially predicted location on the image plane and can be expressed either as an absolute value or as a percentage of the paraxial image height.

It should be apparent that a lens or lens system has opposite types of distortion depending on whether it is used forward or backward. This means that if a lens were used to make a photograph, and then used in reverse to project it, there would be no distortion in the final screen image. Also, perfectly symmetrical optical systems at 1:1 magnification have no distortion or coma.



Figure 1.20 **Pincushion and barrel distortion**

CHROMATIC ABERRATION

The aberrations previously described are purely a function of the shape of the lens surfaces, and they can be observed with monochromatic light. Other aberrations, however, arise when these optics are used to transform light containing multiple wavelengths. The index of refraction of a material is a function of wavelength. Known as dispersion, this is discussed in *Material Properties*. From Snell's law (see equation 1.20), it can be seen that light rays of different wavelengths or colors will be refracted at different angles since the index is not a constant. Figure 1.21 shows the result when polychromatic collimated light is incident on a positive lens element. Because the index of refraction is higher for shorter wavelengths, these are focused closer to the lens than the longer wavelengths. Longitudinal chromatic aberration is defined as the axial distance from the nearest to the farthest focal point. As in the case of spherical aberration, positive and negative elements have opposite signs of chromatic aberration. Once again, by combining elements of nearly opposite aberration to form a doublet, chromatic aberration can be partially corrected. It is necessary to use two glasses with different dispersion characteristics, so that the weaker negative element can balance the aberration of the stronger, positive element.



Figure 1.21 **Longitudinal chromatic aberration**

Variations of Aberrations with Aperture, Field Angle, and Image Height

Aberration	Aperture (ϕ)	Field Angle (θ)	Image Height (y)
Lateral Spherical	ϕ^3	—	—
Longitudinal Spherical	ϕ^2	—	—
Coma	ϕ^2	θ	y
Astigmatism	ϕ	θ^2	y^2
Field Curvature	ϕ	θ^2	y^2
Distortion	—	θ^3	y^3
Chromatic	—	—	—

LATERAL COLOR

Lateral color is the difference in image height between blue and red rays. Figure 1.22 shows the chief ray of an optical system consisting of a simple positive lens and a separate aperture. Because of the change in index with wavelength, blue light is refracted more strongly than red light, which is why rays intercept the image plane at different heights. Stated simply, magnification depends on color. Lateral color is very dependent on system stop location.

For many optical systems, the third-order term is all that may be needed to quantify aberrations. However, in highly corrected systems or in those having large apertures or a large angular field of view, third-order theory is inadequate. In these cases, exact ray tracing is absolutely essential.



Figure 1.22 **Lateral Color**

APPLICATION NOTE

Achromatic Doublets Are Superior to Simple Lenses

Because achromatic doublets correct for spherical as well as chromatic aberration, they are often superior to simple lenses for focusing collimated light or collimating point sources, even in purely monochromatic light.

Although there is no simple formula that can be used to estimate the spot size of a doublet, the tables in *Spot Size* give sample values that can be used to estimate the performance of catalog achromatic doublets.



Lens Shape

Aberrations described in the preceding section are highly dependent on application, lens shape, and material of the lens (or, more exactly, its index of refraction). The singlet shape that minimizes spherical aberration at a given conjugate ratio is called best-form. The criterion for best-form at any conjugate ratio is that the marginal rays are equally refracted at each of the lens/air interfaces. This minimizes the effect of $\sin\theta \neq \theta$. It is also the criterion for minimum surface-reflectance loss. Another benefit is that absolute coma is nearly minimized for best-form shape, at both infinite and unit conjugate ratios.

To further explore the dependence of aberrations on lens shape, it is helpful to make use of the Coddington shape factor, q, defined as

$$q = \frac{(r_2 + r_1)}{(r_2 - r_1)}. \tag{1.24}$$

Figure 1.23 shows the transverse and longitudinal spherical aberrations of a singlet lens as a function of the shape factor, q. In this particular instance, the lens has a focal length of 100 mm, operates at f/5, has an index of refraction of 1.518722 (BK7 at the mercury green line, 546.1 nm), and is being operated at the infinite conjugate ratio. It is also assumed that the lens itself is the aperture stop. An asymmetric shape that corresponds to a q-value of about 0.7426 for this material and wavelength is the best singlet shape for on-axis imaging. It is important to note that the best-form shape is dependent on refractive index. For example, with a high-index material, such as silicon, the best-form lens for the infinite conjugate ratio is a meniscus shape.

At infinite conjugate with a typical glass singlet, the plano-convex shape ($q = 1$), with convex side toward the infinite conjugate, performs nearly as well as the best-form lens. Because a plano-convex lens costs much less to manufacture than an asymmetric biconvex singlet, these lenses are quite popular. Furthermore, this lens shape exhibits near-minimum total transverse aberration and near-zero coma when used off axis, thus enhancing its utility.

For imaging at unit magnification ($s = s'' = 2f$), a similar analysis would show that a symmetric biconvex lens is the best shape. Not only is spherical aberration minimized, but coma, distortion, and lateral chromatic aberration exactly cancel each other out. These results are true regardless of material index or wavelength, which explains the utility of symmetric convex lenses, as well as symmetrical optical systems in general. However, if a remote stop is present, these aberrations may not cancel each other quite as well.

For wide-field applications, the best-form shape is definitely not the optimum singlet shape, especially at the infinite conjugate ratio, since it yields maximum field curvature. The ideal shape is determined by the situation and may require rigorous ray-tracing analysis. It is possible to achieve much better correction in an optical system by using more than one element. The cases of an infinite conjugate ratio system and a unit conjugate ratio system are discussed in the following section.



Figure 1.23 **Aberrations of positive singlets at infinite conjugate ratio as a function of shape**

Lens Combinations

INFINITE CONJUGATE RATIO

As shown in the previous discussion, the best-form singlet lens for use at infinite conjugate ratios is generally nearly plano-convex. Figure 1.24 shows a plano-convex lens (LPX-15.0-10.9-C) with incoming collimated light at a wavelength of 546.1 nm. This drawing, including the rays traced through it, is shown to exact scale. The marginal ray (ray f-number 1.5) strikes the paraxial focal plane significantly off the optical axis.

This situation can be improved by using a two-element system. The second part of the figure shows a precision achromat (LAO-21.0-14.0), which consists of a positive low-index (crown glass) element cemented to a negative meniscus high-index (flint glass) element. This is drawn to the same scale as the plano-convex lens. No spherical aberration can be discerned in the lens. Of course, not all of the rays pass exactly through the paraxial focal point; however, in this case, the departure is measured in micrometers, rather than in millimeters, as in the case of the plano-convex lens. Additionally, chromatic aberration (not shown) is much better corrected in the doublet. Even though these lenses are known as achromatic doublets, it is important to remember that even with monochromatic light the doublet's performance is superior.

Figure 1.24 also shows the f-number at which singlet performance becomes unacceptable. The ray with f-number 7.5 practically intercepts the paraxial focal point, and the f/3.8 ray is fairly close. This useful drawing, which can be scaled to fit a plano-convex lens of any focal length, can be used to estimate the magnitude of its spherical aberration, although lens thickness affects results slightly.

UNIT CONJUGATE RATIO

Figure 1.25 shows three possible systems for use at the unit conjugate ratio. All are shown to the same scale and using the same ray f-numbers with a light wavelength of 546.1 nm. The first system is a symmetric biconvex lens (LDX-21.0-19.2-C), the best-form singlet in this application. Clearly, significant spherical aberration is present in this lens at f/2.7. Not until f/13.3 does the ray closely approach the paraxial focus.

A dramatic improvement in performance is gained by using two identical plano-convex lenses with convex surfaces facing and nearly in contact. Those shown in figure 1.25 are both LPX-20.0-20.7-C. The combination of these two lenses yields almost exactly the same focal length as the biconvex lens. To understand why this configuration improves performance so dramatically, consider that if the biconvex lens were split down the middle, we would have two identical plano-convex lenses, each working at an infinite conjugate ratio, but with the convex surface toward the focus. This orientation is opposite to that shown to be optimum for this shape lens. On the other hand, if these lenses are reversed, we have the system just described but with a better correction of the spherical aberration.



Figure 1.24 **Single-element plano-convex lens compared with a two-element achromat**

Previous examples indicate that an achromat is superior in performance to a singlet when used at the infinite conjugate ratio and at low f-numbers. Since the unit conjugate case can be thought of as two lenses, each working at the infinite conjugate ratio, the next step is to replace the plano-convex singlets with achromats, yielding a four-element system. The third part of figure 1.25 shows a system composed of two LAO-40.0-18.0 lenses. Once again, spherical aberration is not evident, even in the f/2.7 ray.


SYMMETRIC BICONVEX LENS
ray f-numbers
2.7
3.3
4.4
6.7
13.3
paraxial image plane
LDX-21.0-19.2-C
IDENTICAL PLANO-CONVEX LENSES
2.7
3.3
4.4
6.7
13.3
LPX-20.0-20.7-C
IDENTICAL ACHROMATS
2.7
3.3
4.4
6.7
13.3
LAO-40.0-18.0

Figure 1.25 **Three possible systems for use at the unit conjugate ratio**

Fundamental Optics
Gaussian Beam Optics
Optical Specifications
Material Properties
Optical Coatings

Diffraction Effects

In all light beams, some energy is spread outside the region predicted by geometric propagation. This effect, known as diffraction, is a fundamental and inescapable physical phenomenon. Diffraction can be understood by considering the wave nature of light. Huygens' principle (figure 1.26) states that each point on a propagating wavefront is an emitter of secondary wavelets. The propagating wave is then the envelope of these expanding wavelets. Interference between the secondary wavelets gives rise to a fringe pattern that rapidly decreases in intensity with increasing angle from the initial direction of propagation. Huygens' principle nicely describes diffraction, but rigorous explanation demands a detailed study of wave theory.

Diffraction effects are traditionally classified into either Fresnel or Fraunhofer types. Fresnel diffraction is primarily concerned with what happens to light in the immediate neighborhood of a diffracting object or aperture. It is thus only of concern when the illumination source is close to this aperture or object, known as the near field. Consequently, Fresnel diffraction is rarely important in most classical optical setups, but it becomes very important in such applications as digital optics, fiber optics, and near-field microscopy.

Fraunhofer diffraction, however, is often important even in simple optical systems. This is the light-spreading effect of an aperture when the aperture (or object) is illuminated with an infinite source (plane-wave illumination) and the light is sensed at an infinite distance (far-field) from this aperture.

From these overly simple definitions, one might assume that Fraunhofer diffraction is important only in optical systems with infinite conjugate, whereas Fresnel diffraction equations should be considered at finite conjugate ratios. Not so. A lens or lens system of finite positive focal length with plane-wave input maps the far-field diffraction pattern of its aperture onto the focal plane; therefore, it is Fraunhofer diffraction that determines the limiting performance of optical systems. More generally, at any conjugate ratio, far-field angles are transformed into spatial displacements in the image plane.



Figure 1.26 **Huygens' principle**

CIRCULAR APERTURE

Fraunhofer diffraction at a circular aperture dictates the fundamental limits of performance for circular lenses. It is important to remember that the spot size, caused by diffraction, of a circular lens is

$$d = 2.44\lambda(\text{f/\#}) \tag{1.25}$$

where d is the diameter of the focused spot produced from plane-wave illumination and λ is the wavelength of light being focused. Notice that it is the f-number of the lens, not its absolute diameter, that determines this limiting spot size.

The diffraction pattern resulting from a uniformly illuminated circular aperture actually consists of a central bright region, known as the Airy disc (see figure 1.27), which is surrounded by a number of much fainter rings. Each ring is separated by a circle of zero intensity. The irradiance distribution in this pattern can be described by

$$I_x = I_0\left[\frac{2J_1(x)}{x}\right]^2 \tag{1.26}$$

where

I_0 = peak irradiance in the image

$J_1(x)$ = Bessel function of the first kind of order unity

$$= x\sum_{n=1}^{\infty}(-1)^{n+1}\frac{x^{2n-2}}{(n-1)!\,n!\,2^{2n-1}}$$



Figure 1.27 **Center of a typical diffraction pattern for a circular aperture**

and

$$x = \frac{\pi D}{\lambda}\sin\theta$$

where

$\lambda =$ wavelength

$D =$ aperture diameter

$\theta =$ angular radius from the pattern maximum.

This useful formula shows the far-field irradiance distribution from a uniformly illuminated circular aperture of diameter D.

SLIT APERTURE

A slit aperture, which is mathematically simpler, is useful in relation to cylindrical optical elements. The irradiance distribution in the diffraction pattern of a uniformly illuminated slit aperture is described by

$$I_x = I_0\left[\frac{\sin x}{x}\right]^2 \qquad (1.27)$$

where $I_0 =$ peak irradiance in image

$$x = \frac{\pi w \sin\theta}{\lambda}$$

where $\lambda =$ wavelength

$w =$ slit width

$\theta =$ angular deviation from pattern maximum.

APPLICATION NOTE

Rayleigh Criterion

In imaging applications, spatial resolution is ultimately limited by diffraction. Calculating the maximum possible spatial resolution of an optical system requires an arbitrary definition of what is meant by resolving two features. In the Rayleigh criterion, it is assumed that two separate point sources can be resolved when the center of the Airy disc from one overlaps the first dark ring in the diffraction pattern of the second. In this case, the smallest resolvable distance, d, is

$$d = \frac{0.61\lambda}{\text{NA}} = 1.22\lambda(\text{f/\#})$$

ENERGY DISTRIBUTION TABLE

The accompanying table shows the major features of pure (unaberrated) Fraunhofer diffraction patterns of circular and slit apertures. The table shows the position, relative intensity, and percentage of total pattern energy corresponding to each ring or band. It is especially convenient to characterize positions in either pattern with the same variable x. This variable is related to field angle in the circular aperture case by

$$\sin\theta = \frac{\lambda x}{\pi D} \qquad (1.28)$$

where D is the aperture diameter. For a slit aperture, this relationship is given by

$$\sin\theta = \frac{\lambda x}{\pi w} \qquad (1.29)$$

where w is the slit width, π has its usual meaning, and D, w, and λ are all in the same units (preferably millimeters). Linear instead of angular field positions are simply found from $r{=}s''\tan\theta$ where s'' is the secondary conjugate distance. This last result is often seen in a different form, namely the diffraction-limited spot-size equation, which, for a circular lens is

$$d = 2.44\,\lambda(\text{f}\,/\#) \qquad \textit{(see eq. 1.25)}$$

This value represents the smallest spot size that can be achieved by an optical system with a circular aperture of a given f-number, and it is the diameter of the first dark ring, where the intensity has dropped to zero.

The graph in figure 1.28 shows the form of both circular and slit aperture diffraction patterns when plotted on the same normalized scale. Aperture diameter is equal to slit width so that patterns between x-values and angular deviations in the far-field are the same.

GAUSSIAN BEAMS

Apodization, or nonuniformity of aperture irradiance, alters diffraction patterns. If pupil irradiance is nonuniform, the formulas and results given previously do not apply. This is important to remember because most laser-based optical systems do not have uniform pupil irradiance. The output beam of a laser operating in the TEM_{00} mode has a smooth Gaussian irradiance profile. Formulas used to determine the focused spot size from such a beam are discussed in *Gaussian Beam Optics*. Furthermore, when dealing with Gaussian beams, the location of the focused spot also departs from that predicted by the paraxial equations given in this chapter. This is also detailed in *Gaussian Beam Optics*.

Energy Distribution in the Diffraction Pattern of a Circular or Slit Aperture

	Circular Aperture			Slit Aperture		
Ring or Band	Position (x)	Relative Intensity (I_x/I_0)	Energy in Ring (%)	Position (x)	Relative Intensity (I_x/I_0)	Energy in Band (%)
Central Maximum	0.0	1.0	83.8	0.0	1.0	90.3
First Dark	1.22π	0.0		1.00π	0.0	
First Bright	1.64π	0.0175	7.2	1.43π	0.0472	4.7
Second Dark	2.23π	0.0		2.00π	0.0	
Second Bright	2.68π	0.0042	2.8	2.46π	0.0165	1.7
Third Dark	3.24π	0.0		3.00π	0.0	
Third Bright	3.70π	0.0016	1.5	3.47π	0.0083	0.8
Fourth Dark	4.24π	0.0		4.00π	0.0	
Fourth Bright	4.71π	0.0008	1.0	4.48π	0.0050	0.5
Fifth Dark	5.24π	0.0		5.00π	0.0	

Note: Position variable (x) is defined in the text.



Figure 1.28 **Fraunhofer diffraction pattern of a singlet slit superimposed on the Fraunhofer diffraction pattern of a circular aperture**

Lens Selection

Having discussed the most important factors that affect the performance of a lens or a lens system, we will now address the practical matter of selecting the optimum catalog components for a particular task. The following useful relationships are important to keep in mind throughout the selection process:

- Diffraction-limited spot size = 2.44 λ f/#
- Approximate on-axis spot size of a plano-convex lens at the infinite conjugate resulting from spherical aberration = $\dfrac{0.067\,f}{\mathrm{f}/\#^3}$
- Optical invariant = $m = \dfrac{\mathrm{NA}}{\mathrm{NA}''}$.

Example 1: Collimating an Incandescent Source

Produce a collimated beam from a quartz halogen bulb having a 1-mm-square filament. Collect the maximum amount of light possible and produce a beam with the lowest possible divergence angle.

This problem, illustrated in figure 1.29, involves the typical tradeoff between light-collection efficiency and resolution (where a beam is being collimated rather than focused, resolution is defined by beam divergence). To collect more light, it is necessary to work at a low f-number, but because of aberrations, higher resolution (lower divergence angle) will be achieved by working at a higher f-number.

In terms of resolution, the first thing to realize is that the minimum divergence angle (in radians) that can be achieved using any lens system is the source size divided by system focal length. An off-axis ray (from the edge of the source) entering the first principal point of the system exits the second principal point at the same angle. Therefore, increasing the system focal length improves this limiting divergence because the source appears smaller.

An optic that can produce a spot size of 1 mm when focusing a perfectly collimated beam is therefore required. Since source size is inherently limited, it is pointless to strive for better resolution. This level of resolution can be achieved easily with a plano-convex lens.

While angular divergence decreases with increasing focal length, spherical aberration of a plano-convex lens increases with increasing focal length. To determine the appropriate focal length, set the spherical aberration formula for a plano-convex lens equal to the source (spot) size:

$$\frac{0.067\,f}{\mathrm{f}/\#^3} = 1\ \mathrm{mm}.$$

This ensures a lens that meets the minimum performance needed. To select a focal length, make an arbitrary f-number choice. As can be seen from the relationship, as we lower the f-number (increase collection efficiency), we decrease the focal length, which will worsen the resultant divergence angle (minimum divergence = 1 mm/f).

In this example, we will accept f/2 collection efficiency, which gives us a focal length of about 120 mm. For f/2 operation we would need a minimum diameter of 60 mm. The LPX-60.0-62.2-C fits this specification exactly. Beam divergence would be about 8 mrad.

Finally, we need to verify that we are not operating below the theoretical diffraction limit. In this example, the numbers (1-mm spot size) indicate that we are not, since

diffraction-limited spot size = 2.44 × 0.5 μm × 2 = 2.44 μm.

Example 2: Coupling an Incandescent Source into a Fiber

In *Imaging Properties of Lens Systems* we considered a system in which the output of an incandescent bulb with a filament of 1 mm in diameter was to be coupled into an optical fiber with a core diameter of 100 µm and a numerical aperture of 0.25. From the optical invariant and other constraints given in the problem, we determined that $f = 9.1$ mm, CA = 5 mm, $s = 100$ mm, $s'' = 10$ mm, NA″ = 0.25, and NA = 0.025 (or f/2 and f/20). The singlet lenses that match these specifications are the plano-convex LPX-5.0-5.2-C or biconvex lenses LDX-6.0-7.7-C and LDX-5.0-9.9-C. The closest achromat would be the LAO-10.0-6.0.



Figure 1.29 **Collimating an incandescent source**

We can immediately reject the biconvex lenses because of spherical aberration. We can estimate the performance of the LPX-5.0-5.2-C on the focusing side by using our spherical aberration formula:

$$\text{spot size} = \frac{0.067\ (10)}{2^3} = 84\ \mu\text{m}.$$

We will ignore, for the moment, that we are not working at the infinite conjugate.

This is slightly smaller than the 100-µm spot size we are trying to achieve. However, since we are not working at infinite conjugate, the spot size will be larger than that given by our simple calculation. This lens is therefore likely to be marginal in this situation, especially if we consider chromatic aberration. A better choice is the achromat. Although a computer ray trace would be required to determine its exact performance, it is virtually certain to provide adequate performance.

Example 3: Symmetric Fiber-to-Fiber Coupling

Couple an optical fiber with an 8-µm core and a 0.15 numerical aperture into another fiber with the same characteristics. Assume a wavelength of 0.5 µm.

This problem, illustrated in figure 1.30, is essentially a 1:1 imaging situation. We want to collect and focus at a numerical aperture of 0.15 or f/3.3, and we need a lens with an 8-µm spot size at this f-number. Based on the lens combination discussion in *Lens Combination Formulas*, our most likely setup is either a pair of identical plano-convex lenses or achromats, faced front to front. To determine the necessary focal length for a plano-convex lens, we again use the spherical aberration estimate formula:

$$\frac{0.067\ f}{3.3^3} = 0.008\ \text{mm}.$$

This formula yields a focal length of 4.3 mm and a minimum diameter of 1.3 mm. The LPX-4.2-2.3-BAK1 meets these criteria. The biggest problem with utilizing these tiny, short focal length lenses is the practical considerations of handling, mounting, and positioning them. Because using a pair of longer focal length singlets would result in unacceptable performance, the next step might be to use a pair of the slightly longer focal length, larger achromats, such as the LAO-10.0-6.0. The performance data, given in *Spot Size*, show that this combination does provide the required 8-μm spot diameter.

Because fairly small spot sizes are being considered here, it is important to make sure that the system is not being asked to work below the diffraction limit:

$$2.44 \times 0.5\ \mu\text{m} \times 3.3 = 4\ \ \mu\text{m}\,.$$

Since this is half the spot size caused by aberrations, it can be safely assumed that diffraction will not play a significant role here.

An entirely different approach to a fiber-coupling task such as this would be to use a pair of spherical ball lenses (LMS-LSFN series) or one of the gradient-index lenses (LGT series).



Figure 1.30 **Symmetric fiber-to-fiber coupling**

Example 4: Diffraction-Limited Performance

Determine at what f-number a plano-convex lens being used at an infinite conjugate ratio with 0.5-μm wavelength light becomes diffraction limited (i.e., the effects of diffraction exceed those caused by aberration).

To solve this problem, set the equations for diffraction-limited spot size and third-order spherical aberration equal to each other. The result depends upon focal length, since aberrations scale with focal length, while diffraction is solely dependent upon f-number. By substituting some common focal lengths into this formula, we get f/8.6 at $f = 100$ mm, f/7.2 at $f = 50$ mm, and f/4.8 at $f = 10$ mm.

$$2.44 \times 0.5\ \mu\text{m} \times \text{f}/\# = \frac{0.067 \times f}{\text{f}/\#^3}$$

or

$$\text{f}/\# = (54.9 \times f)^{1/4}.$$

When working with these focal lengths (and under the conditions previously stated), we can assume essentially diffraction-limited performance above these f-numbers. Keep in mind, however, that this treatment does not take into account manufacturing tolerances or chromatic aberration, which will be present in polychromatic applications.

APPLICATION NOTE

Spherical Ball Lenses for Fiber Coupling



Spheres are arranged so that the fiber end is located at the focal point. The output from the first sphere is then collimated. If two spheres are aligned axially to each other, the beam will be transferred from one focal point to the other. Translational alignment sensitivity can be reduced by enlarging the beam. Slight negative defocusing of the ball can reduce the spherical aberration third-order contribution common to all coupling systems. Additional information can be found in "Lens Coupling in Fiber Optic Devices: Efficiency Limits," by A. Nicia, *Applied Optics*, vol. 20, no. 18, pp 3136–45, 1981. Off-axis aberrations are absent since the fiber diameters are so much smaller than the coupler focal length.

Spot Size

In general, the performance of a lens or lens system in a specific circumstance should be determined by an exact trigonometric ray trace. CVI Melles Griot applications engineers can supply ray-tracing data for particular lenses and systems of catalog components on request. In certain situations, however, some simple guidelines can be used for lens selection. The optimum working conditions for some of the lenses in this catalog have already been presented. The following tables give some quantitative results for a variety of simple and compound lens systems, which can be constructed from standard catalog optics.

In interpreting these tables, remember that these theoretical values obtained from computer ray tracing consider only the effects of ideal geometric optics. Effects of manufacturing tolerances have not been considered. Furthermore, remember that using more than one element provides a higher degree of correction but makes alignment more difficult. When actually choosing a lens or a lens system, it is important to note the tolerances and specifications clearly described for each CVI Melles Griot lens in the product listings.

The tables give the diameter of the spot for a variety of lenses used at several different f-numbers. All the tables are for on-axis, uniformly illuminated, collimated input light at 546.1 nm. They assume that the lens is facing in the direction that produces a minimum spot size. When the spot size caused by aberrations is smaller or equal to the diffraction-limited spot size, the notation "DL" appears next to the entry. The shorter focal length lenses produce smaller spot sizes because aberrations increase linearly as a lens is scaled up.

The effect on spot size caused by spherical aberration is strongly dependent on f-number. For a plano-convex singlet, spherical aberration is inversely dependent on the cube of the f-number. For doublets, this relationship can be even higher. On the other hand, the spot size caused by diffraction increases linearly with f-number. Thus, for some lens types, spot size at first decreases and then increases with f-number, meaning that there is some optimum performance point at which both aberrations and diffraction combine to form a minimum.

Unfortunately, these results cannot be generalized to situations in which the lenses are used off axis. This is particularly true of the achromat/aplanatic meniscus lens combinations because their performance degrades rapidly off axis.

Focal Length = 10 mm

	Spot Size (μm)*		
f/#	LDX-5.0-9.9-C	LPX-8.0-5.2-C	LAO-10.0-6.0
f/2	—	94	11
f/3	36	25	7
f/5	8	6.7 (DL)	6.7 (DL)
f/10	13.3 (DL)	13.3 (DL)	13.3 (DL)

**Diffraction-limited performance is indicated by DL.*

Focal Length = 30 mm

	Spot Size (μm)*		
f/#	LPX-18.5-15.6-C	LAO-30.0-12.5	LAO-50.0-18.0 & MENP-18.0-4.0-73.5-NSF8
f/2	295	—	3
f/3	79	7	4 (DL)
f/5	17	6.7 (DL)	6.9 (DL)
f/10	13.3 (DL)	13.3 (DL)	13.8 (DL)

**Diffraction-limited performance is indicated by DL.*

Focal Length = 60 mm

	Spot Size (μm)*			
f/#	LDX-50.0-60.0-C	LPX-30.0-31.1-C	LAO-60.0-30.0	LAO-100.0-31.5 & MENP-31.5-6.0-146.4-NSF8
f/2	816	600	—	—
f/3	217	160	34	4 (DL)
f/5	45	33	10	6.7 (DL)
f/10	13.3 (DL)	13.3 (DL)	13.3 (DL)	13.3 (DL)

**Diffraction-limited performance is indicated by DL.*

Aberration Balancing

To improve system performance, optical designers make sure that the total aberration contribution from all surfaces taken together sums to nearly zero. Normally, such a process requires computerized analysis and optimization. However, there are some simple guidelines that can be used to achieve this with lenses available in this catalog. This approach can yield systems that operate at a much lower f-number than can usually be achieved with simple lenses.

Specifically, we will examine how to null the spherical aberration from two or more lenses in collimated, monochromatic light. This technique will thus be most useful for laser beam focusing and expanding.

Figure 1.31 shows the third-order longitudinal spherical aberration coefficients for six of the most common positive and negative lens shapes when used with parallel, monochromatic incident light. The plano-convex and plano-concave lenses both show minimum spherical aberration when oriented with their curved surface facing the incident parallel beam. All other configurations exhibit larger amounts of spherical aberration. With these lens types, it is now possible to show how various systems can be corrected for spherical aberration.

A two-element laser beam expander is a good starting example. In this case, two lenses are separated by a distance that is the sum of their focal lengths, so that the overall system focal length is infinite. This system will not focus incoming collimated light, but it will change the beam diameter. By definition, each of the lenses is operating at the same f-number.

The equation for longitudinal spherical aberration shows that, for two lenses with the same f-number, aberration varies directly with the focal lengths of the lenses. The sign of the aberration is the same as focal length. Thus, it should be possible to correct the spherical aberration of this Galilean-type beam expander, which consists of a positive focal length objective and a negative diverging lens.

If a plano-convex lens of focal length f_1 oriented in the normal direction is combined with a plano-concave lens of focal length f_2 oriented in its reverse direction, the total spherical aberration of the system is

$$\text{LSA} = \frac{0.272\, f_1}{\text{f/\#}^2} + \frac{1.069\, f_2}{\text{f/\#}^2}.$$

After setting this equation to zero, we obtain

$$\frac{f_1}{f_2} = -\frac{1.069}{0.272} = -3.93.$$

To make the magnitude of aberration contributions of the two elements equal so they will cancel out, and thus correct the system, select the focal length of the positive element to be 3.93 times that of the negative element.

Figure 1.32(a) shows a beam-expander system made up of catalog elements, in which the focal length ratio is 4:1. This simple system is corrected to about 1/6 wavelength at 632.8 nm, even though the objective is operating at f/4 with a 20-mm aperture diameter. This is remarkably good wavefront correction for such a simple system; one would normally assume that a doublet objective would be needed and a complex diverging lens as well. This analysis does not take into account manufacturing tolerances.

A beam expander of lower magnification can also be derived from this information. If a symmetric-convex objective is used together] with a reversed plano-concave diverging lens, the aberration coefficients are in the ratio of 1.069/0.403 = 2.65. Figure 1.32(b) shows a system of catalog lenses that provides a magnification of 2.7 (the closest possible given the available focal lengths). The maximum wavefront error in this case is only a quarter-wave, even though the objective is working at f/3.3.



Figure 1.31 **Third-order longitudinal spherical aberration of typical lens shapes**

1ch_FundamentalOptics_Final_a.qxd 6/15/2009 2:29 PM Page 1.28

a) CORRECTED 4 × BEAM EXPANDER


f = – 20 mm
10-mm diameter
plano-concave
f = 80 mm
22.4-mm diameter
plano-convex

b) CORRECTED 2.7 × BEAM EXPANDER


f = – 20 mm
10-mm diameter
plano-concave
f = 54 mm
32-mm diameter
symmetric-convex

c) SPHERICALLY CORRECTED 25-mm EFL f/2.0 OBJECTIVE


f = – 25 mm
25-mm diameter
plano-concave
f = 50 mm (2)
27-mm diameter
plano-convex

Figure 1.32 **Combining catalog lenses for aberration balancing**

The relatively low *f* numbers of these objectives is a great advantage in minimizing the length of these beam expanders. They would be particularly useful with Nd:YAG and argon-ion lasers, which tend to have large output beam diameters.

These same principles can be utilized to create high numerical aperture objectives that might be used as laser focusing lenses. Figure 1.32(c) shows an objective consisting of an initial negative element, followed by two identical plano-convex positive elements. Again, all of the elements operate at the same f-number, so that their aberration contributions are proportional to their focal lengths. To obtain zero total spherical aberration from this configuration, we must satisfy

$$1.069\, f_1 + 0.272\, f_2 + 0.272\, f_2 = 0$$

or

$$\frac{f_1}{f_2} = -0.51.$$

Therefore, a corrected system should result if the focal length of the negative element is just about half that of each of the positive lenses. In this case, $f_1 = 425$ mm and $f_2 = 50$ mm yield a total system focal length of about 25 mm and an f-number of approximately f/2. This objective, corrected to 1/6 wave, has the additional advantage of a very long working distance.

Definition of Terms

FOCAL LENGTH (*f*)

Two distinct terms describe the focal lengths associated with every lens or lens system. The effective focal length (EFL) or equivalent focal length (denoted *f* in figure 1.33) determines magnification and hence the image size. The term *f* appears frequently in lens formulas and in the tables of standard lenses. Unfortunately, because *f* is measured with reference to principal points which are usually inside the lens, the meaning of *f* is not immediately apparent when a lens is visually inspected.

The second type of focal length relates the focal plane positions directly to landmarks on the lens surfaces (namely the vertices) which are immediately recognizable. It is not simply related to image size but is especially convenient for use when one is concerned about correct lens positioning or mechanical clearances. Examples of this second type of focal length are the front focal length (FFL, denoted f_f in figure 1.33) and the back focal length (BFL, denoted f_b).

The convention in all of the figures (with the exception of a single deliberately reversed ray) is that light travels from left to right.

FOCAL POINT (F OR F″)

Rays that pass through or originate at either focal point must be, on the opposite side of the lens, parallel to the optical axis. This fact is the basis for locating both focal points.

PRIMARY PRINCIPAL SURFACE

Let us imagine that rays originating at the front focal point F (and therefore parallel to the optical axis after emergence from the opposite side of the lens) are singly refracted at some imaginary surface, instead of twice refracted (once at each lens surface) as actually happens. There is a unique imaginary surface, called the principal surface, at which this can happen.

To locate this unique surface, consider a single ray traced from the air on one side of the lens, through the lens and into the air on the other side. The ray is broken into three segments by the lens. Two of these are external (in the air), and the third is internal (in the glass). The external segments can be extended to a common point of intersection (certainly near, and usually within, the lens). The principal surface is the locus of all such


t_c
t_e
primary principal point
primary principal surface
secondary principal surface
secondary principal point
ray from object at infinity
ray from object at infinity
back focal point
optical axis
F
primary vertex A_1
r_2
H
H″
A_2 secondary vertex
F″
front focal point
r_1
reversed ray locates front focal point or primary principal surface
f_f
f_b
A
B
f
f

A = front focus to front edge distance

B = rear edge to rear focus distance

f = effective focal length; may be positive (as shown) or negative

f_f = front focal length

f_b = back focal length

t_e = edge thickness

t_c = center thickness

r_1 = radius of curvature of first surface (positive if center of curvature is to right)

r_2 = radius of curvature of second surface (negative if center of curvature is to left)

Figure 1.33 **Focal length and focal points**

points of intersection of extended external ray segments. The principal surface of a perfectly corrected optical system is a sphere centered on the focal point.

Near the optical axis, the principal surface is nearly flat, and for this reason, it is sometimes referred to as the principal plane.

SECONDARY PRINCIPAL SURFACE

This term is defined analogously to the primary principal surface, but it is used for a collimated beam incident from the left and focused to the back focal point F″ on the right. Rays in that part of the beam nearest the axis can be thought of as once refracted at the secondary principal surface, instead of being refracted by both lens surfaces.

PRIMARY PRINCIPAL POINT (H) OR FIRST NODAL POINT

This point is the intersection of the primary principal surface with the optical axis.

SECONDARY PRINCIPAL POINT (H″) OR SECONDARY NODAL POINT

This point is the intersection of the secondary principal surface with the optical axis.

CONJUGATE DISTANCES (s AND s'')

The conjugate distances are the object distance, s, and image distance, s''. Specifically, s is the distance from the object to H, and s'' is the distance from H″ to the image location. The term infinite conjugate ratio refers to the situation in which a lens is either focusing incoming collimated light or is being used to collimate a source (therefore, either s or s'' is infinity).

PRIMARY VERTEX (A_1)

The primary vertex is the intersection of the primary lens surface with the optical axis.

SECONDARY VERTEX (A_2)

The secondary vertex is the intersection of the secondary lens surface with the optical axis.

EFFECTIVE FOCAL LENGTH (EFL, f)

Assuming that the lens is surrounded by air or vacuum (refractive index 1.0), this is both the distance from the front focal point (F) to the primary principal point (H) and the distance from the secondary principal point (H″) to the rear focal point (F″). Later we use f to designate the paraxial EFL for the design wavelength (λ_0).

FRONT FOCAL LENGTH (f_f)

This length is the distance from the front focal point (F) to the primary vertex (A_1).

BACK FOCAL LENGTH (f_b)

This length is the distance from the secondary vertex (A_2) to the rear focal point (F″).

EDGE-TO-FOCUS DISTANCES (A AND B)

A is the distance from the front focal point to the primary vertex of the lens. B is the distance from the secondary vertex of the lens to the rear focal point. Both distances are presumed always to be positive.

REAL IMAGE

A real image is one in which the light rays actually converge; if a screen were placed at the point of focus, an image would be formed on it.

VIRTUAL IMAGE

A virtual image does not represent an actual convergence of light rays. A virtual image can be viewed only by looking back through the optical system, such as in the case of a magnifying glass.

F-NUMBER (f/#)

The f-number (also known as the focal ratio, relative aperture, or speed) of a lens system is defined to be the effective focal length divided by system clear aperture. Ray f-number is the conjugate distance for that ray divided by the height at which it intercepts the principal surface.

$$\mathrm{f/\#} = \frac{f}{\mathrm{CA}}. \qquad \text{(see eq. 1.7)}$$

NUMERICAL APERTURE (NA)

The NA of a lens system is defined to be the sine of the angle, θ_1, that the marginal ray (the ray that exits the lens system at its outer edge) makes with the optical axis multiplied by the index of refraction (n) of the medium. The NA can be defined for any ray as the sine of the angle made by that ray with the optical axis multiplied by the index of refraction:

$$\mathrm{NA} = n\sin\theta. \qquad (1.30)$$

MAGNIFICATION POWER

Often, positive lenses intended for use as simple magnifiers are rated with a single magnification, such as 4 × . To create a virtual image for viewing with the human eye, in principle, any positive lens can be used at an infinite number of possible magnifications. However, there is usually a narrow range of magnifications that will be comfortable for the viewer. Typically, when the viewer adjusts the object distance so that the image appears to be essentially at infinity (which is a comfortable viewing distance for most individuals), magnification is given by the relationship

$$\text{magnification} = \frac{254\ \text{mm}}{f} \qquad (f \text{ in mm}). \tag{1.31}$$

Thus, a 25.4-mm focal length positive lens would be a 10 × magnifier.

DIOPTERS

The term diopter is used to define the reciprocal of the focal length, which is commonly used for ophthalmic lenses. The inverse focal length of a lens expressed in diopters is

$$\text{diopters} = \frac{1000}{f} \qquad (f \text{ in mm}). \tag{1.32}$$

Thus, the smaller the focal length is, the larger the power in diopters will be.

DEPTH OF FIELD AND DEPTH OF FOCUS

In an imaging system, depth of field refers to the distance in object space over which the system delivers an acceptably sharp image. The criteria for what is acceptably sharp is arbitrarily chosen by the user; depth of field increases with increasing f-number.

For an imaging system, depth of focus is the range in image space over which the system delivers an acceptably sharp image. In other words, this is the amount that the image surface (such as a screen or piece of photographic film) could be moved while maintaining acceptable focus. Again, criteria for acceptability are defined arbitrarily.

In nonimaging applications, such as laser focusing, depth of focus refers to the range in image space over which the focused spot diameter remains below an arbitrary limit.

APPLICATION NOTE

Technical Reference

For further reading about the definitions and formulas presented here, refer to the following publications:

Rudolph Kingslake, *Lens Design Fundamentals*
(Academic Press)

Rudolph Kingslake, System Design
(Academic Press)

Warren Smith, *Modern Optical Engineering*
(McGraw Hill).

Donald C. O'Shea, *Elements of Modern Optical Design*
(John Wiley & Sons)

Eugene Hecht, *Optics* (Addison Wesley)

Max Born, Emil Wolf, *Principles of Optics*
(Cambridge University Press)

If you need help with the use of definitions and formulas presented in this guide, our applications engineers will be pleased to assist you.

Paraxial Lens Formulas

PARAXIAL FORMULAS FOR LENSES IN AIR

The following formulas are based on the behavior of paraxial rays, which are always very close and nearly parallel to the optical axis. In this region, lens surfaces are always very nearly normal to the optical axis, and hence all angles of incidence and refraction are small. As a result, the sines of the angles of incidence and refraction are small (as used in Snell's law) and can be approximated by the angles themselves (measured in radians).

The paraxial formulas do not include effects of spherical aberration experienced by a marginal ray — a ray passing through the lens near its edge or margin. All EFL values (f) tabulated in this catalog are paraxial values which correspond to the paraxial formulas. The following paraxial formulas are valid for both thick and thin lenses unless otherwise noted. The refractive index of the lens glass, n, is the ratio of the speed of light in vacuum to the speed of light in the lens glass. All other variables are defined in figure 1.33.

Focal Length

$$\frac{1}{f} = (n-1)\left(\frac{1}{r_1} - \frac{1}{r_2}\right) + \frac{(n-1)^2}{n}\,\frac{t_c}{r_1 r_2} \qquad (1.33)$$

where n is the refractive index, t_c is the center thickness, and the sign convention previously given for the radii r_1 and r_2 applies. For thin lenses, $t_c \cong 0$, and for plano lenses either r_1 or r_2 is infinite. In either case the second term of the above equation vanishes, and we are left with the familiar lens maker's formula:

$$\frac{1}{f} = (n-1)\left(\frac{1}{r_1} - \frac{1}{r_2}\right). \qquad (1.34)$$

Surface Sagitta and Radius of Curvature

(refer to figure 1.34)

$$r^2 = (r-s)^2 + \left(\frac{d}{2}\right)^2 \qquad (1.35)$$

$$s = r - \sqrt{r^2 - \left(\frac{d}{2}\right)^2} > 0 \qquad (1.36)$$

$$r = \frac{s}{2} + \frac{d^2}{8s}. \qquad (1.37)$$

An often useful approximation is to neglect $s/2$.

Symmetric Lens Radii ($r_2 = -r_1$)

With center thickness constrained,

$$r_1 = (n-1)\left[f \pm \sqrt{f^2 - \left(\frac{f t_c}{n}\right)}\right] \qquad (1.38)$$

$$= (n-1)\,f\left[1 + \sqrt{1 - \left(\frac{t_c}{nf}\right)}\right]$$

where, in the first form, the + sign is chosen for the square root if f is positive, but the − sign must be used if f is negative. In the second form, the + sign must be used regardless of the sign of f.

Plano Lens Radius

Since r_2 is infinite,

$$r_1 = (n-1)\,f. \qquad (1.39)$$

Principal-Point Locations (signed distances from vertices)

$$A_2H'' = \frac{-r_2 t_c}{n(r_2 - r_1) + t_c(n-1)} \qquad (1.40)$$

$$A_1H = \frac{-r_1 t_c}{n(r_2 - r_1) + t_c(n-1)} \qquad (1.41)$$

where the above sign convention applies.

For symmetric lenses ($r_2 = -r_1$),

$$A_1H = -A_2H''$$

$$= \frac{r_1 t_c}{2nr_1 - t_c(n-1)}. \qquad (1.42)$$



Figure 1.34 **Surface sagitta and radius of curvature**

If either r_1 or r_2 is infinite, l'Hôpital's rule from calculus must be used. Thus, referring to *Aberration Balancing*, for plano-convex lenses in the correct orientation,

$$A_1H = 0$$

and

$$A_2H'' = -\frac{t_c}{n}. \qquad (1.43)$$

For flat plates, by letting $r_1 \to \infty$ in a symmetric lens, we obtain $A_1H = A_2H'' = t_c/2_n$. These results are useful in connection with the following paraxial lens combination formulas.

Hiatus or Interstitium (principal-point separation)

$$HH'' = t_c \left\{ 1 - \frac{f}{n} \left[\frac{1}{f} - \frac{(n-1)^2}{n} \frac{t_c}{r_1 r_2} \right] \right\} \qquad (1.44)$$

which, in the thin-lens approximation (exact for plano lenses), becomes

$$HH'' = t_c \left(1 - \frac{1}{n} \right). \qquad (1.45)$$

Solid Angle

The solid angle subtended by a lens, for an observer situated at an on-axis image point, is

$$\begin{aligned} \Omega &= 2\pi(1-\cos\theta) \\ &= 4\pi \sin^2\left(\frac{\theta}{2}\right) \end{aligned} \qquad (1.46)$$

where this result is in steradians, and where

$$\theta = \arctan\left(\frac{CA}{2s}\right) \qquad (1.47)$$

is the apparent angular radius of the lens clear aperture. For an observer at an on-axis object point, use s instead of s''. To convert from steradians to the more intuitive sphere units, simply divide Ω by 4π. If the Abbé sine condition is known to apply, θ may be calculated using the arc sine function instead of the arctangent.

Back Focal Length

$$\begin{aligned} f_b &= f'' + A_2H'' \\ &= f'' - \frac{r_2 t_c}{n(r_2 - r_1) + t_c(n-1)} \end{aligned} \qquad (1.48)$$

where the sign convention presented above applies to A_2H'' and to the radii. If r_2 is infinite, l'Hôpital's rule from calculus must be used, whereby

$$f_b = f'' - \frac{t_c}{n}. \qquad (1.49)$$

Front Focal Length

$$\begin{aligned} f_f &= f - A_1H \\ &= f + \frac{r_1 t_c}{n(r_2 - r_1) + t_c(n-1)} \end{aligned} \qquad (1.50)$$

where the sign convention presented above applies to A_1H and to the radii. If r_1 is infinite, l'Hôpital's rule from calculus must be used, whereby

$$f_f = f - \frac{t_c}{n}. \qquad (1.51)$$

Edge-to-Focus Distances

For positive lenses,

$$A = f_f + s_1 \qquad (1.52)$$

and

$$B = f_b + s_2 \qquad (1.53)$$

where s_1 and s_2 are the sagittas of the first and second surfaces. Bevel is neglected.

Magnification or Conjugate Ratio

$$\begin{aligned} m &= \frac{s''}{s} \\ &= \frac{f}{s-f} \\ &= \frac{s''-f}{f}. \end{aligned} \qquad (1.54)$$

PARAXIAL FORMULAS FOR LENSES IN ARBITRARY MEDIA

These formulas allow for the possibility of distinct and completely arbitrary refractive indices for the object space medium (refractive index n'), lens (refractive index n''), and image space medium (refractive index n). In this situation, the EFL assumes two distinct values, namely f in object space and f'' in image space. It is also necessary to distinguish the principal points from the nodal points. The lens serves both as a lens and as a window separating the object space and image space media.

The situation of a lens immersed in a homogenous fluid (figure 1.35) is included as a special case ($n = n''$). This case is of considerable practical importance. The two values f and f'' are again equal, so that the lens combination formulas are applicable to systems immersed in a common fluid. The general case (two different fluids) is more difficult, and it must be approached by ray tracing on a surface-by-surface basis.

Lens Constant (k)

This number appears frequently in the following formulas. It is an explicit function of the complete lens prescription (both radii, t_c and n') and both media indices (n and n''). This dependence is implicit anywhere that k appears.

$$k=\frac{n'-n}{r_1}+\frac{n''-n'}{r_2}-\frac{t_c(n'-n)(n''-n')}{n'r_1r_2}. \qquad (1.55)$$

Effective Focal Lengths

$$f=\frac{n}{k} \qquad f''=\frac{n''}{k}. \qquad (1.56)$$

Lens Formula (Gaussian form)

$$\frac{n}{s}+\frac{n''}{s''}=k. \qquad (1.57)$$

Lens Formula (Newtonian form)

$$xx''=f''f=\frac{nn''}{k^2}. \qquad (1.58)$$

Principal-Point Locations

$$\mathrm{A_1H}=\frac{nt_c}{k}\left(\frac{n''-n'}{n'r_2}\right) \qquad (1.59)$$

$$\mathrm{A_2H''}=\frac{-n''t_c}{k}\left(\frac{n'-n}{n'r_1}\right). \qquad (1.60)$$

Object-to-First-Principal-Point Distance

$$s=\frac{ns''}{ks''-n''}. \qquad (1.61)$$

Second Principal-Point-to-Image Distance

$$s''=\frac{n''s}{ks-n}. \qquad (1.62)$$

Magnification

$$m=\frac{ns''}{n''s}. \qquad (1.63)$$

Lens Maker's Formula

$$\frac{n}{f}=\frac{n''}{f''}=k. \qquad (1.64)$$

Nodal-Point Locations

$$\mathrm{A_1N}=\mathrm{A_1H}+\mathrm{HN} \qquad (1.65)$$

$$\mathrm{A_2N''}=\mathrm{A_2H''}+\mathrm{H''N''}. \qquad (1.66)$$

Separation of Nodal Point from Corresponding Principal Point

HN = H″N″ = $(n''-n)/k$, positive for N to right of H and N″ to right of H″.


index n = 1 (air or vacuum)
index n''= 1.333 (water)
f
f_f
f''
f_b
A₁
A₂
F
H H″
N N″
F″
index n = 1.51872 (BK7)

Figure 1.35 **Symmetric lens with disparate object and image space indexes**

Back Focal Length

$$f_b = f'' + A_2H''. \qquad \text{(see eq. 1.48)}$$

Front Focal Length

$$f_f = f - A_1H. \qquad \text{(see eq. 1.50)}$$

Focal Ratios

The focal ratios are *f*/CA and *f*″/CA, where CA is the diameter of the clear aperture of the lens.

Numerical Apertures

$$n \sin\theta$$

$$\text{where } \theta = \arcsin\left(\frac{CA}{2s}\right)$$

and

$$n'' \sin\theta''$$

$$\text{where } \theta'' = \arcsin\left(\frac{CA}{2s''}\right).$$

Solid Angles (in steradians)

$$\Omega = 2\pi\,(1 - \cos\theta) \qquad \text{(see eq. 1.46)}$$

$$= 4\pi \sin^2\left(\frac{\theta}{2}\right)$$

$$\text{where } \theta = \arctan\left(\frac{CA}{2s}\right)$$

$$\Omega = 2\pi(1 - \cos\theta'')$$

$$= 4\pi \sin^2\left(\frac{\theta}{2}\right)$$

$$\text{where } \theta'' = \arctan\left(\frac{CA}{2s''}\right).$$

To convert from steradians to spheres, simply divide by 4π.

APPLICATION NOTE

For Quick Approximations

Much time and effort can be saved by ignoring the differences among f, f_b, and f_f in these formulas by assuming that $f = f_b = f_f$. Then s becomes the lens-to-object distance; s'' becomes the lens-to-image distance; and the sum of conjugate distances $s + s''$ becomes the object-to-image distance. This is known as the thin-lens approximation.

APPLICATION NOTE

Physical Significance of the Nodal Points

A ray directed at the primary nodal point N of a lens appears to emerge from the secondary nodal point N″ without change of direction. Conversely, a ray directed at N″ appears to emerge from N without change of direction. At the infinite conjugate ratio, if a lens is rotated about a rotational axis orthogonal to the optical axis at the secondary nodal point (i.e., if N″ is the center of rotation), the image remains stationary during the rotation. This fact is the basis for the nodal slide method for measuring nodal-point location and the EFL of a lens. The nodal points coincide with their corresponding principal points when the image space and object space refractive indices are equal ($n = n''$). This makes the nodal slide method the most precise method of principal-point location.

Principal-Point Locations

Figure 1.36 indicates approximately where the principal points fall in relation to the lens surfaces for various standard lens shapes. The exact positions depend on the index of refraction of the lens material, and on the lens radii, and can be found by formula. in extreme meniscus lens shapes (short radii or steep curves), it is possible that both principal points will fall outside the lens boundaries. For symmetric lenses, the principal points divide that part of the optical axis between the vertices into three approximately equal segments. For plano lenses, one principal point is at the curved vertex, and the other is approximately one-third of the way to the plane vertex.



Figure 1.36 **Principal points of common lenses**

1ch_FundamentalOptics_Final_a.qxd 7/6/2009 1:54 PM Page 1.37



Prisms

Prisms are blocks of optical material whose flat, polished sides are arranged at precisely controlled angles to each other. Prisms may be used in an optical system to deflect or deviate a beam of light. They can invert or rotate an image, disperse light into its component wavelengths, and be used to separate states of polarization.

PRISM ORIENTATION

The orientation of a prism determines its effect on a beam of light or an image.

A viewer looks through a prism at an object and sees a virtual image (see Figure 1.37). This image may be displaced from the original object, or, if a dove prism is used, it may coincide with the object. Furthermore, image orientation may differ from the object; in the case of a right-angle prism, the image is reversed.

A real image (see Figure 1.38) can be formed only if imaging optics are present in the system. Without imaging optics, the image is virtual. A virtual image has the same orientation as the real image shown, but it can be viewed by the observer only by looking back through the prism system.

TOTAL INTERNAL REFLECTION

Rays incident upon a glass/air boundary (i.e., an internal reflection) at angles that exceed the critical angle are reflected with 100-percent efficiency regardless of their initial polarization state. The critical angle is given by

$$\theta_c(\lambda) = \arcsin\frac{1}{n_\lambda} \qquad (1.67)$$

and depends on the refractive index, which is a function of wavelength. If, at some wavelength, the refractive index should fall to less than $\sqrt{2} = 1.414$, the critical angle will exceed 45 degrees, and total internal reflection (TIR) will fail for a collimated beam internally incident at 45 degrees on the hypotenuse face of a right-angle prism. Reflectance decreases rapidly at angles of incidence smaller than the critical angle.

The index of BK7 is sufficiently high to guarantee the TIR of a collimated beam at 45 degrees internal incidence over the visible and near-infrared region. The possibility of significant TIR failure with convergent or divergent beams should be kept in mind if polarization is important. TIR can also fail if the hypotenuse face is not kept extremely clean. Even an almost invisible fingerprint can lead to TIR failure. An aluminum- or silver-coated hypotenuse is recommended for applications where the right-angle prism is frequently handled, or where convergent or divergent beams are used. There is a slight loss of reflectance at all internal angles with the coating, and no critical angle exists.



Figure 1.37 **Virtual imaging using a prism**



Figure 1.38 **Real imaging using a prism**

ABERRATIONS FOR PRISMS

Prisms will introduce aberrations when they are used with convergent or divergent beams of light. Using prisms with collimated or nearly collimated light will help minimize aberrations. Conjugate distances that include prisms should be long.

DISPERSING PRISMS

Dispersing prisms are used to separate a beam of white light into its component colors. Generally, the light is first collimated and then dispersed by the prism. A spectrum is then formed at the focal plane of a lens or curved mirror. In laser work, dispersing prisms are used to separate two wavelengths following the same beam path. Typically, the dispersed beams are permitted to travel far enough so the beams separate spatially.

A prism exhibits magnification in the plane of dispersion if the entrance and exit angles for a beam differ. This is useful in anamorphic (one-dimensional) beam expansion or compression, and may be used to correct or create asymmetric beam profiles.

As shown in Figure 1.39, a beam of width W_1 is incident at an angle α on the surface of a dispersing prism of apex angle A. The angle of refraction at the first surface, β, the angle of incidence at the second surface, γ, and the angle of refraction exiting the prism, δ, are easily calculated:

$$\beta = \sin^{-1}((\sin\alpha) / \eta)$$
$$\gamma = A - \beta$$
$$\delta = \sin^{-1}(\eta\sin\gamma)$$



Figure 1.39 **Diagram of dispersing prism**

The beam deviation, ϵ, is of greatest importance. It is the angle the exit beam makes with its original direction.

$$\epsilon = \alpha + \delta - A \qquad (1.68)$$

The magnification W_2/W_1 is given by:

$$M = \frac{\cos\delta\cos\beta}{\cos\alpha\cos\gamma} \qquad (1.69)$$

The resolving power of a prism spectrometer angle α, the angular dispersion of the prism is given by:

$$\frac{d\delta}{d\lambda} = \left(\frac{\sin A}{\cos\delta\cos\beta}\right)\left(\frac{d\eta}{d\lambda}\right) \qquad (1.70)$$

If the spectrum is formed by a diffraction limited focal system of focal length f, the minimum spot size is $dx \sim f\lambda/W$. This corresponds to a minimum angular resolution $d\delta \sim \lambda/w$ for a beam of diameter w. The diffraction limited angular resolution at a given beam diameter sets the limit on the spectral resolving power of a prism. Setting the expression for $d\delta$ equal to the minimum angular resolution, we obtain:

$$RP = \frac{\lambda}{d\lambda} = \left(\frac{w_2\sin A}{\cos\delta\cos\beta}\right)\left(\frac{d\eta}{d\lambda}\right) \qquad (1.71)$$

where RP is the resolving power of the prism.

At a given wavelength, the beam deviation ϵ is a minimum at an angle of incidence:

$$\alpha_{\text{min dev}} = \sin^{-1}[\eta\sin(A/2)] \qquad (1.72)$$

where η is the prism index of refraction at that wavelength. At this angle, the incident and exit angles are equal, the prism magnification is one, and the internal rays are perpendicular to the bisector of the apex angle.

By measuring the angle of incidence for minimum deviation, the index of refraction of a prism can be determined. Also, by proper choice of apex angle, the equal incident and exit angles may be made Brewster's angle, eliminating losses for p-polarized beams. The apex angle to choose is:

$$A = \pi - 2\theta_B \qquad (1.73)$$

If, in addition, the base angles of the prism are chosen as Brewster's angle, an isosceles Brewster prism results.

Another use is illustrated next.



Figure 1.40 **Translation of a prism at minimum deviation**

At minimum deviation, translating a prism along the bisector of the apex angle does not disturb the direction of the output rays. See Figure 1.40. This is important in femtosecond laser design where intracavity prisms are used to compensate for group velocity dispersion. By aligning a prism for minimum deviation and translating it along its apex bisector, the optical path length in material may be varied with no misalignment, thus varying the contribution of the material to overall group velocity dispersion. Finally, it is possible to show that at minimum deviation

$$\mathrm{RP} = \left(b_2 - b_1\right)\frac{d\eta}{d\lambda} \qquad (1.74)$$

where the relevant quantities are defined in Figure 1.41.



Figure 1.41 **Ray path lengths of a prism at minimum deviation**

If the beam is made to fill the prism completely, $b_1 = 0$, and $b_2 = b$, the base of the prism. So, we have the classical result that the resolving power of a prism spectrometer is equal to the base of the prism times the dispersion of the prism material.

As an example, consider CVI Melles Griot EDP-25-F2 prism, operating in minimum deviation at 590 nm. The angle of incidence and emergence are both then 54.09° and $d\eta/d\lambda$ is $-0.0854\ \mu\mathrm{m}^{-1}$ for F2 glass at 590 nm. If the 25-mm prism is completely filled, the resolving power, $\lambda/d\lambda$, is 2135. This is sufficient to resolve the Sodium D lines.

PELLIN BROCA PRISMS

In a Pellin Broca prism, an ordinary dispersing prism is split in half along the bisector of the apex angle. Using a right angle prism, the two halves are joined to create a dispersing prism with an internal right angle bend obtained by total internal reflection, as shown in Figure 1.42.

In principle, one can split any type of dispersing prism to create a Pellin Broca prism. Typically the Pellin Broca prism is based on an Isosceles Brewster prism. Provided the light is *p*-polarized, the prism will be essentially lossless.



Figure 1.42 **One of the wavelengths deviates at exactly 90° to its initial direction**

Suppose wavelengths λ_1 and λ_2 are superimposed in a collimated beam, as at the output of a harmonic generating crystal, the diagram in Figure 1.42 suggests that it is always possible to find a rotation of the prism in its plane that ensures that one of the two wavelengths will operate at minimum deviation when refracting at the input face of the first of the half-dispersing prisms. This means that it will enter the right angle prism normal to one of its faces, be turned exactly 90°, be presented to the second half-dispersing prism in minimum deviation, and hence exit the Pellin Broca prism deviated at exactly 90° to its initial direction.

A simple dispersing prism always deviates the longer wavelength less than the shorter wavelength. In a Pellin Broca prism, whether the longer wavelength is deviated more or less depends on the orientation of the prism. This is an important consideration when designing a high power Pellin Broca beam separator, as shown in Figures 1.43 and 1.44.



Figure 1.43 **Longer wavelength is deviated more than the shorter wavelength**



Figure 1.44 **Longer wavelength is deviated less than the shorter wavelength**

CVI Melles Griot offers Brewster angle Pellin Brocca prisms in a number of sizes and materials. BK7 prisms are used in the visible and near IR, and is the least expensive. UV-grade fused silica Pellin Broca prisms are used from 240 nm to 2000 nm. Excimer-grade prisms are used in the 180-nm to 240-nm region. Crystal-quartz Pellin Broca prisms are specifically designed for high-power Q-switched 266-nm laser pulses at fluence levels of 50 mJ/cm^2. Fused silica prisms track (i.e., suffer internal catastrophic damage) above this fluence, probably due to self-focusing.

PORRO PRISMS

A Porro prism, named for its inventor Ignazio Porro, is a type of reflection prism used to alter the orientation of an image. In operation, light enters the large face of the prism, undergoes total internal reflection twice from the 45° sloped faces, and exits again through the large face. An image traveling through a Porro prism is rotated by 180° and exits in the opposite direction offset from its entrance point, as shown in Figure 1.45. Since the image is reflected twice, the handedness of the image is unchanged. Porro prisms have rounded edges to minimize breakage and facilitate assembly.



Figure 1.45 **Porro prisms retroreflect and invert the image**

Porro prisms are most often used in pairs, forming a double Porro prism, as shown in Figure 1.46. A second prism, rotated 90° with respect to the first, is placed such that the beam will traverse both prisms. The net effect of the prism system is a beam parallel to but displaced from its original direction, with the image rotated 180°. As before, the handedness of the image is unchanged.

Double Porro prism systems are used in small optical telescopes to reorient an inverted image and in many binoculars to both re-orient the image and provide a longer, folded distance between the objective lenses and the eyepieces.



Figure 1.46 **Double porro prism results in a beam parallel to but displaced from its original direction, with the image rotated 180°**

MELLES GRIOT
GLAN THOMPSON
03 PTO
GLAN TAYLOR
03 PTY
LES GRIOT
N LASER
PRISM
PLS 301

Polarization

Polarization States

Four numbers are required to describe a single plane wave Fourier component traveling in the $+z$ direction. These can be thought of as the amplitude and phase shift of the field along two orthogonal directions.

1. CARTESIAN REPRESENTATION

In Cartesian coordinates, the propagation equation for an electric field is given by the formula

$$E(x,y,z)=(xE_x e^{i\phi_x}+yE_y e^{i\phi_y})e^{i(kz-\omega t)} \qquad (1.75)$$

where E_x, E_y, ϕ_x, and ϕ_y are real numbers defining the magnitude and the phase of the field components in the orthogonal unit vectors x and y. If the origin of time is irrelevant, only the relative phase shift

$$\phi=\phi_x-\phi_y \qquad (1.76)$$

need be specified.

2. CIRCULAR REPRESENTATION

In the circular representation, we resolve the field into circularly polarized components. The basic states are represented by the complex unit vectors

$$e_+=\left(1/\sqrt{2}\right)\left(x+iy\right) \text{ and} \qquad (1.77)$$

$$e_-=\left(1/\sqrt{2}\right)\left(x-iy\right) \qquad (1.78)$$

where e_+ is the unit vector for left circularly polarized light; for positive helicity light; for light that rotates counterclockwise in a fixed plane as viewed facing into the light wave; and for light whose electric field rotation obeys the right hand rule with thumb pointing in the direction of propagation.

APPLICATION NOTE

Polarization Convention

Historically, the orientation of a polarized electromagnetic wave has been defined in the optical regime by the orientation of the electric vector. This is the convention used by CVI Melles Griot.

e_- is the unit vector for right circularly polarized light; for negative helicity light; for light that rotates clockwise in a fixed plane as viewed facing into the light wave; and for light whose electric field rotation disobeys the right hand rule with thumb pointing in the direction of propagation.



Figure 1.47 **Linearly polarized light. E_x and E_y are in phase**



Figure 1.48 **Circularly polarized light. E_x and E_y are out of phase by angular frequency ω**

Fundamental Optics
Gaussian Beam Optics
Optical Specifications
Material Properties
Optical Coatings

As in the case of the Cartesian representation, we write

$$E=(e_{+}E_{+}\mathrm{e}^{\mathrm{i}\phi+} + e_{-}E_{-}\mathrm{e}^{\mathrm{i}\phi-})\,e^{\mathrm{i(kz-\omega t)}} \tag{1.79}$$

where E_{+}, E_{-}, ϕ_{+}, and ϕ_{-} are four real numbers describing the magnitudes and phases of the field components of the left and right circularly polarized components. Note that

$$E_{+}=e_{-}\bullet E \tag{1.80}$$

$$E_{-}=e_{+}\bullet E \tag{1.81}$$

3. ELLIPTICAL REPRESENTATION

An arbitrary polarization state is generally elliptically polarized. This means that the tip of the electric field vector will describe an ellipse, rotating once per optical cycle.

Let a be the semimajor and b be the semiminor axis of the polarization ellipse. Let ψ be the angle that the semimajor axis makes with the x axis.

Let ξ and $\boldsymbol{\eta}$ be the axes of a right-handed coordinate system rotated by an angle $+\psi$ with respect to the x axis and aligned with the polarization ellipse as shown in Figure 1.49.



Figure 1.49 **The polarization ellipse**

The elliptical representation is:

$$E=\left(a\hat{\xi}+b\hat{\eta}\right)e^{i\delta_0}e^{i(kz-\omega t)} \tag{1.82}$$

Note that the phase shift δ_o above is required to adjust the time origin, and the parameter ψ is implicit in the rotation of the ξ and $\boldsymbol{\eta}$ axes with respect to the x and y axes.

CONVERSIONS BETWEEN REPRESENTATIONS

For brevity, we will provide only the Cartesian to circular and Cartesian to elliptical transformations. The inverse transformations are straightforward. We define the following quantities:

$$g_1=E_x\cos\phi_x-E_y\sin\phi_y \tag{1.83}$$

$$g_2=E_x\sin\phi_x+E_y\cos\phi_y \tag{1.84}$$

$$g_3=E_x\cos\phi_x+E_y\sin\phi_y \tag{1.85}$$

$$g_4=E_x\sin\phi_x-E_y\cos\phi_y \tag{1.86}$$

$$u=\left(g_1^2+g_2^2\right)^{1/2} \tag{1.87}$$

$$v=\left(g_3^2+g_4^2\right)^{1/2} \tag{1.88}$$

$$\phi_{12}=\operatorname{atan}(g_1,g_2) \tag{1.89}$$

$$\phi_{34}=\operatorname{atan}(g_3,g_4) \tag{1.90}$$

In the above, atan(x,y) is the four quadrant arc tangent function. This means that atan$(x,y)=$ atan(y/x) with the provision that the quadrant of the angle returned by the function is controlled by the signs of both x and y, not just the sign of their quotient; for example, if $g_2=g_1=-1$, then ϕ_{12} above is $5\pi/4$ or $-3\pi/4$, not $\pi/4$.

A. CARTESIAN TO CIRCULAR TRANSFORMATION

$$E_{+}=v/\sqrt{2} \tag{1.91}$$

$$E_{-}=u/\sqrt{2} \tag{1.92}$$

$$\phi_{+}=\phi_{34} \tag{1.93}$$

$$\phi_{-}=\phi_{12} \tag{1.94}$$

B. CARTESIAN TO ELLIPTICAL TRANSFORMATION

$$a=(v+u)/2 \tag{1.95}$$

$$b=(v-u)/2 \tag{1.96}$$

$$\psi=(\phi_{12}-\phi_{34})/2 \tag{1.97}$$

$$\delta_0=(\phi_{12}+\phi_{34})/2 \tag{1.98}$$

LINEAR POLARIZERS

A linear polarizer is a device that creates a linear polarization state from an arbitrary input. It does this by removing the component orthogonal to the selected state. Unlike plastic sheet polarizers which absorb the rejected beam (which turns into heat), cube polarizers and thin-film plate polarizers reflect the rejected beam, creating two usable beams. Still others may refract the two polarized beams at different angles, thereby separating them. Examples are Wollaston and Rochon prism polarizers.

Suppose the pass direction of the polarizer is determined by unit vector p. Then the transmitted field E_2, in terms of the incident field E_1, is given by

$$E_2 = p(p \bullet E_1) \qquad (1.99)$$

where the phase shift of the transmitted field has been ignored.

A real polarizer has a pass transmission, $T_\|$, less than 1. The transmission of the rejected beam, $T_\perp$, may not be 0. If r is a unit vector along the rejected direction, then

$$E_2 = (T_\|)^{1/2} p(p \bullet E_1)e^{i\phi_\|} + (T_\perp)^{1/2} r(r \bullet E_1)e^{i\phi_\perp} \qquad (1.100)$$

In the above, the phase shifts along the two directions must be retained. Similar expressions could be arrived at for the rejected beam. If θ is the angle between the field E_1 and the polarizer pass direction p, the above equation predicts that

$$T = T_\| \cos^2\theta + T_\perp \sin^2\theta \qquad (1.101)$$

The above equation shows that, when the polarizer is aligned so that $\theta = 0$, $T = T_\|$. When it is "crossed", $\theta = \pi/2$, and $T = T_\perp$. The extinction ratio is $\epsilon = T_\| / T_\perp$. A polarizer with perfect extinction has $T_\perp = 0$, and thus $T = T_\| \cos^2\theta$ is a familiar result. Because $\cos^2\theta$ has a broad maximum as a function of orientation angle, setting a polarizer at a maximum of transmission is generally not very accurate. One has to either map the $\cos^2\theta$ with sufficient accuracy to find the $\theta = 0$ point, or do a null measurement at $\theta = \pm\pi/2$.



Figure 1.50 **At CVI Melles Griot, the DOT marks preferred input face. This is the tested direction for transmitted wavefront. Damage threshold is also higher for this orientation as well.**

Polarization Definitions

BIREFRINGENCE

A birefringent crystal, such as calcite, will divide an entering beam of monochromatic light into two beams having opposite polarization. The beams usually propagate in different directions and will have different speeds. There will be only one or two optical axis directions within the crystal in which the beam will remain collinear and continue at the same speed, depending on whether the birefringent crystal is uniaxial or biaxial.

If the crystal is a plane-parallel plate, and the optical axis directions are not collinear with the beam, radiation will emerge as two separate, orthogonally polarized beams (see Figure 1.51). The beam will be unpolarized where the beams overlap upon emergence. The two new beams within the material are distinguished from each other by more than just polarization and velocity. The rays are referred to as extraordinary (E) and ordinary (O). These rays need not be confined to the plane of incidence. Furthermore, the velocity of these rays changes with direction. Thus, the index of refraction for extraordinary rays is also a continuous function of direction. The index of refraction for the ordinary ray is constant and is independent of direction.

The two indexes of refraction are equal only in the direction of an optical axis within the crystal. The dispersion curve for ordinary rays is a single, unique curve when the index of refraction is plotted against wavelength. The dispersion curve for the extraordinary ray is a family of curves with different curves for different directions. Unless it is in a particular polarization state, or the crystalline surface is perpendicular to an optical axis, a ray normally incident on a birefringent surface will be divided in two at the boundary. The extraordinary ray will be deviated; the ordinary ray will not. The ordinary ray index n, and the most extreme (whether greater or smaller) extraordinary ray index n_e, are together known as the principal indices of refraction of the material.



Figure 1.51 **Double refraction in a birefringent crystal**

If a beam of linearly polarized monochromatic light enters a birefringent crystal along a direction not parallel to the optical axis of the crystal, the beam will be divided into two separate beams. Each will be polarized at right angles to the other and will travel in different directions. The original beam energy, which will be divided between the new beams, depends on the original orientation of the vector to the crystal.

The energy ratio between the two orthogonally polarized beams can be any value. It is also possible that all energy will go into one of the new beams. If the crystal is cut as a plane-parallel plate, these beams will recombine upon emergence to form an elliptically polarized beam.

The difference between the ordinary and extraordinary ray may be used to create birefringent crystal polarization devices. In some cases, the difference in refractive index is used primarily to separate rays and eliminate one of the polarization planes, for example, in Glan-type polarizers. In other cases, such as Wollaston and Thompson beamsplitting prisms, changes in propagation direction are optimized to separate an incoming beam into two orthogonally polarized beams.

DICHROISM

Dichroism is selective absorption of one polarization plane over the other during transmission through a material. Sheet-type polarizers are manufactured with organic materials imbedded into a plastic sheet. The sheet is stretched, aligning molecules and causing them to be birefringent, and then dyed. The dye molecules selectively attach themselves to aligned polymer molecules, so that absorption is high in one plane and weak in the other. The transmitted beam is linearly polarized. Polarizers made of such material are very useful for low-power and visual applications. The usable field of view is large (up to grazing incidence), and diameters in excess of 100 mm are available.

POLARIZATION BY REFLECTION

When a beam of ordinary light is incident at the polarizing angle on a transmissive dielectric such as glass, the emerging refracted ray is partially linearly polarized. For a single surface (with n=1.50) at Brewster's angle, 100 percent of the light whose electric vector oscillates parallel to the plane of incidence is transmitted. Only 85 percent of the perpendicular light is transmitted (the other 15 percent is reflected). The degree of polarization from a single-surface reflection is small.

If a number of plates are stacked parallel and oriented at the polarizing angle, some vibrations perpendicular to the plane of incidence will be reflected at each surface, and all those parallel to it will be refracted. By making the number of plates within the stack large (more than 25), high degrees of linear polarization may be achieved. This polarization method is utilized in CVI Melles Griot polarizing beamsplitter cubes which are coated with many layers of quarter-wave dielectric thin films on the interior prism angle. This beamsplitter separates an incident laser beam into two perpendicular and orthogonally polarized beams.

THIN METAL FILM POLARIZERS

Optical radiation incident on small, elongated metal particles will be preferentially absorbed when the polarization vector is aligned with the long axis of the particle. CVI Melles Griot infrared polarizers utilize this effect to make polarizers for the near-infrared. These polarizers are considerably more effective than dichroic polarizers.

Polarizing thin films are formed by using the patented Slocum process to deposit multiple layers of microscopic silver prolate spheroids onto a polished glass substrate. The exact dimensions of these spheroids determine the optical properties of the film. Peak absorption can be selected for any wavelength from 400 to 3000 nm by controlling the deposition process. Contrast ratios up to 10,000:1 can be achieved with this method. Other CVI Melles Griot high-contrast polarizers exhibit contrasts as high as 100,000:1.

CALCITE

Calcite, a rhombohedral crystalline form of calcium carbonate, is found in various forms such as limestone and marble. Since calcite is a naturally occurring material, imperfections are not unusual. The highest quality materials, those that exhibit no optical defects, are difficult to find and are more expensive than those with some defects. Applications for calcite components typically fall into laser applications or optical research. CVI Melles Griot offers calcite components in two quality grades to meet those various needs.

There are three main areas of importance in defining calcite quality.

Spectral Properties

Trace amounts of chemical impurities, as well as lattice defects, can cause calcite to be colored, which changes absorption. For visible light applications, it is essential to use colorless calcite. For near-infrared applications, material with a trace of yellow is acceptable. This yellow coloration results in a 15-percent to 20-percent decrease in transmission below 420 nm.

Wavefront Distortion (Striae)

Striae, or streaked fluctuations in the refractive index of calcite, are caused by dislocations in the crystal lattice. They can cause distortion of a light wavefront passing through the crystal. This is particularly troublesome for interferometric applications.

Scatter

Small inclusions within the calcite crystal account for the main source of scatter. They may appear as small cracks or bubbles. In general, scatter presents a significant problem only when the polarizer is being used with a laser. The amount of scatter centers that can be tolerated is partially determined by beam size and power.

CVI MELLES GRIOT CALCITE GRADES

CVI Melles Griot has selected the most applicable calcite qualities, grouped into two grades:

Laser Grade

Calcite with a wavefront deformation of $\lambda/4$ at 633 nm or better due to striae only.

Optical Grade

Calcite with a wavefront deformation of 1λ to $\lambda/4$ at 633 nm due to striae only.

Waveplates

Waveplates use birefringence to impart unequal phase shifts to the orthogonally polarized field components of an incident wave, causing the conversion of one polarization state into another.

There are two types of birefringence. With linear birefringence, the index of refraction (and hence the phase shift) differs for two orthogonally polarized linear polarization states. This is the operation mode of standard waveplates. With circular birefringence, the index of refraction and hence phase shift differs for left and right circularly polarized components. This is the operation mode of polarization rotators.

STANDARD WAVEPLATES: LINEAR BIREFRINGENCE

Suppose a waveplate made from a uniaxial material has light propagating perpendicular to the optic axis. This makes the field component parallel to the optic axis an extraordinary wave and the component perpendicular to the optic axis an ordinary wave. If the crystal is positive uniaxial, $\eta_e > \eta_o$, then the optic axis is called the slow axis, which is the case for crystal quartz. For negative uniaxial crystals $\eta_e < \eta_o$, the optic axis is called the fast axis.

The equation for the transmitted field E_2, in terms of the incident field E_1 is:

$$E_2 = \mathrm{s}(\mathrm{s} \bullet E_1)e^{i\phi_s} + \mathrm{f}(\mathrm{f} \bullet E_1)e^{i\phi_f} \qquad (1.102)$$

where s and f are unit vectors along the slow and fast axes. This equation shows explicity how the waveplate acts on the field. Reading from left to right, the waveplate takes the component of the input field along its slow axis and appends the slow axis phase shift to it. It does a similar operation to the fast component.

The slow and fast axis phase shifts are given by:

$$\phi_s = \eta_s(\omega)\omega t/c = 2\pi\eta_s(\lambda)t/\lambda \qquad (1.103)$$

$$\phi_f = \eta_f(\omega)\omega t/c = 2\pi\eta_f(\lambda)t/\lambda \qquad (1.104)$$

where η_s and η_f are, respectively, the indices of refraction along the slow and fast axes, and t is the thickness of the waveplate.

To further analyze the effect of a waveplate, we throw away a phase factor lost in measuring intensity, and assign the entire phase delay to the slow axis:

$$E_2 = \mathrm{s}(\mathrm{s} \bullet E_1)e^{i\phi} + \mathrm{f}(\mathrm{f} \bullet E1) \qquad (1.105)$$

$$\phi = \phi_s - \phi_f = 2\pi\left[\eta_s(\lambda) - \eta_f(\lambda)\right]t/\lambda \qquad (1.106)$$

$$\phi = 2\,\pi\,\Delta\eta(\lambda)t/\lambda \qquad (1.107)$$

In the above, $\Delta\eta(\lambda)$ is the birefringence $\eta_s(\lambda)$ - $\eta_f(\lambda)$. The dispersion of the birefringence is very important in waveplate design; a quarter waveplate at a given wavelength is never exactly a half waveplate at half that wavelength.

Let E_1 be initially polarized along x, and let the waveplate slow axis make an angle θ with the x axis. This orientation is shown in Figure 1.52.



Figure 1.52. Orientation of the slow and fast axes of a waveplate with respect to an x-polarized input field

When the waveplate is placed between parallel and perpendicular polarizers the transmissions are given by:

$$T_{\|} \propto |E_2 x|^2 = 1 - \sin^2 2\theta \sin^2 \phi/2 \qquad (1.108)$$

$$T_{\perp} \propto |E_2 y|^2 = \sin^2 2\theta \sin^2 \phi/2 \qquad (1.109)$$

Note that θ is only a function of the waveplate orientation, and ϕ is only a function of the wavelength, the birefringence is a function of wavelength and the plate thickness.

For a full-wave waveplate:

$\phi = 2m\pi$, $T_{\|} = 1$, and $T_{\perp} = 0$, regardless of waveplate orientation.

For a half-wave waveplate:

$$\phi = (2m + 1)\pi,\ T_{\|} = \cos^2 2\theta, \text{ and } T_{\perp} = \sin^2 2\theta. \qquad (1.110)$$

This transmission result is the same as if an initial linearly polarized wave were rotated through an angle of 2θ. Thus, a half-wave waveplate finds use as a polarization rotator.

For a quarter waveplate,

$$\phi = (2m + 1)\pi/2 \text{ (i.e., an odd multiple of } \pi/2). \qquad (1.111)$$

To analyze this, we have to go back to the field equation. Assume that the slow and fast axis unit vectors s and f form a right handed coordinate system such that s x f = +z, the direction of propagation. To obtain circularly polarized light, linearly polarized light must be aligned midway between the slow and fast axes. There are four possibilities listed in the table below.

Phase Shift	Input Field Along $(\mathbf{s} + \mathbf{f})/\sqrt{2}$	Input Field Along $(\mathbf{s} - \mathbf{f})/\sqrt{2}$
$\phi = \pi/2 + 2m\pi$	RCP	LCP
$\phi = 3\pi/2 + 2m\pi$	LCP	RCP

Sometimes, waveplates described by the second line above are called 3/4 waveplates. For multiple order waveplates, CVI Melles Griot permits the use of either of the above classes of waveplates to satisfy the requirements of a quarter-wave waveplate.

MULTIPLE-ORDER WAVEPLATES

For the full-, half-, and quarter-wave waveplate examples given in standard waveplates, the order of the waveplate is given by the integer m. For $m > 0$, the waveplate is termed a multiple-order waveplate. For $m = 0$, we have a zero order waveplate.

The birefringence of crystal quartz near 500 nm is approximately 0.00925. Consider a 0.5-mm-thick crystal quartz waveplate. A simple calculation shows that this is useful as a quarter waveplate for 500 nm; in fact, it is a $37\,\lambda/4$ waveplate at 500 nm with $m = 18$. Multiple-order waveplates are inexpensive, high-damage-threshold retarders. Further analysis shows that this same 0.5mm plate is a $19\,\lambda/2$ half waveplate at 488.2 nm and a 10λ full-wave waveplate at 466.5 nm. The transmission of this plate between parallel polarizers is shown in Figure 1.53 as a function of wavelength. The retardance of the plate at various key points is also shown. Note how quickly the retardance changes with wavelength. Because of this, multiple-order waveplates are generally useful only at their design wavelength.



Figure 1.53 **Transmission of a 0.5-mm-thick crystal quartz waveplate between parallel polarizers**

ZERO-ORDER WAVEPLATES

As discussed above, multiple-order waveplates are not useful with tunable or broad bandwidth sources (e.g., femtosecond lasers). A zero-order waveplate can greatly improve the useful bandwidth in a compact, high-damage-threshold device.

As an example, consider the design of a broadband half-wave waveplate centered at 800 nm. Maximum tuning range is obtained if the plate has a single π phase shift at 800 nm. If made from a single plate of crystal quartz, the waveplate would be about 45 μm thick, which is too thin for easy fabrication and handling. The solution is to take two crystal quartz plates differing in thickness by 45 μm and align them with the slow axis of one against the fast axis of the other. The net phase shift of this zero-order waveplate is π. The two plates may be either air-spaced or optically contacted. The transmission of an 800-nm zero-order half-wave waveplate between parallel polarizers is shown in Figure 1.54 using a 0-10% scale. Its extinction is better than 100:1 over a bandwidth of about 95 nm centered at 800 nm.

CVI Melles Griot produces multiple order and zero order crystal quartz waveplates at any wavelength between 193 nm and 2100 nm. Virtually all popular laser wavelengths are kept in stock, and custom wavelength parts are available with short delivery time.

Mica waveplates are an inexpensive zero-order waveplate solution for low-power applications and in detection schemes.



Figure 1.54 **Zero-order crystal quartz half-wave waveplate for 800 nm**

POLYMER WAVEPLATES

Polymer waveplates offer excellent angular field of view since they are true zero-order waveplates. Figure 1.55 compares the change in retardance as function of incidence angle for polymer and quartz waveplates. A polymer waveplate changes by less than 1% over a ±10° incidence angle.

Retardance accuracy with wavelength change is often of key concern. For example, an off-the-shelf diode laser has a center wavelength tolerance of ±10 nm. Changes with temperature and drive conditions cause wavelength shifts which may alter performance. These polymer waveplates maintain excellent waveplate performance even with minor shifts in the source wavelength. The temperature sensitivity of laminated polymer waveplates is about 0.15 nm/°C, allowing operation over moderate temperature ranges without significantly degrading retardance accuracy. A comparison of different waveplate types and their dependence on wavelength is shown in figure 1.56.



Figure 1.55 **Retardance vs incidence angle for quartz and polymer waveplates**



Figure 1.56 **Wavelength performance of common quarter wave retarders.**

ACHROMATIC WAVEPLATES

At 500 nm, a crystal quartz zero-order half-wave waveplate has a retardation tolerance of λ/50 over a bandwidth of about 50 nm. This increases to about 100 nm at a center wavelength of 800 nm. A different design which corrects for dispersion differences over the wavelength range is required for bandwidths up to 300 nm.

If two different materials are used to create a zero-order or low-order waveplate, cancellation can occur between the dispersions of the two materials. Thus, the net birefringent phase shift can be held constant over a much wider range than in waveplates made from one material. ACWP-series achromatic waveplates from CVI Melles Griot (see Figure 1.57) are comprised of crystal quartz and magnesium fluoride to achieve achromatic performance.

Three wavelength ranges are available in both quarter and half wave retardances. Retardation tolerance is better than λ/100 over the entire wavelength range.



Figure 1.57 **ACWP-400-700-10-2**

For quarter-wave waveplates, perfect retardance is a multiple of 0.25 waves, and transmission through a linear polarizer must be between 33% and 67%. (In all but the shortest wavelength design, quarter-wave retardation tolerance is better than λ/100.) For half-wave waveplates, perfect retardance is 0.5 waves, while perfect transmission through a linear polarizer parallel to the initial polarization state should be zero. A high degree of achromatization is achievable by the dual material design. In addition, we manage low group velocity dispersion for ultrashort pulse applications through the use of thin plates.

DUAL-WAVELENGTH WAVEPLATES

Dual-wavelength waveplates are used in a number of applications. One common application is separation of different wavelengths with a polarizing beamsplitter by rotating the polarization of one wavelength by 90°, and leaving the other unchanged. This frequently occurs in nonlinear doubling or tripling laser sources such as Nd:YAG (1064/532/355/266).

One way to achieve the multiple retardation specifications is through careful selection of multiple-order waveplates which meet both wavelength and retardation conditions. This often results in the selection of a relatively high order waveplate. Therefore, these dual-wavelength waveplates operate best over a narrow bandwidth and temperature range.

Another approach is to combine two quartz waveplates with their optical axes orthogonal to one another, effectively creating a zero-order waveplate. In this configuration, the temperature dependence is a function of the thickness difference between the waveplates, resulting in excellent temperature stability. The retardation of the compound waveplate is also a function of the thickness difference enabling wide bandwidth performance.

Etalons

Etalons are most commonly used as line-narrowing elements in narrow-band laser cavities or as bandwidth-limiting and coarse-tuning elements in broadband and picosecond lasers. Further applications are laser line profile monitoring, diagnosis.

The etalons described in this section are all of the planar Fabry-Perot type. Typical transmission characteristics for this type etalon are shown in Figure 1.58.



Figure 1.58 **Transmission characteristics of a Fabry-Perot etalon**

Air-Spaced Etalons consist of pairs of very flat plano-plano plates separated by optically contacted spacers. The inner surfaces of the plates are coated with partially reflecting coatings, the outer surfaces are coated with antireflection coatings.

Solid Etalons are made from a single plate with parallel sides. Partially reflecting coatings are then deposited on both sides. The cavity is formed by the plate thickness between the coatings.

Deposited Solid Etalons are a special type of solid etalon in which the cavity is formed by a deposited layer of coating material. The thickness of this deposited layer depends on the free spectral range required and can range from a few nanometers up to 15 micrometers. The cavity is sandwiched between the etalon reflector coatings and the whole assembly is supported on a fused-silica base plate.

Etalon plates need excellent surface flatness and plate parallelism. To avoid peak transmission losses due to scatter or absorption, the optical coatings also have to meet the highest standards.

For a plane wave incident on the etalon, the transmission of the etalon is given by:

$$T = \frac{I_{\text{trans}}}{I_{\text{inc}}} = \frac{1}{1 + \dfrac{4R}{(1-R)^2}\sin^2(\delta/2)} \qquad (1.112)$$

Here, R is the reflectance of each surface; δ is the phase shift

$$\delta = \frac{2\pi}{\lambda}\eta d\cos\theta \qquad (1.113)$$

where,

η is the refractive index (e.g., 1 for air-spaced etalons)

d is the etalon spacing or thickness

θ is the angle of incidence

The free spectral range (FSR) of the etalon is given by

$$\begin{aligned}\text{FSR} &= \frac{c}{2\eta d} \text{ in Hz} \qquad (1.114)\\ &= \frac{1}{2\eta d} \text{ in cm}^{-1}\\ &= \frac{\lambda^2}{2\eta d} \text{ in nm}\end{aligned}$$

The reflectivity finesse, $\mathcal{F}_R$ is given by

$$\mathcal{F}_R = \frac{\pi\sqrt{R}}{1-R} \qquad (1.115)$$

Figure 1.59 shows the reflectivity finesse as a function of the coating reflectivity.

The bandwidth (FWHM) is given by

$$\text{FWHM} = \frac{\text{FSR}}{\mathcal{F}_R} \qquad (1.116)$$

However, the above applies to theoretical etalons which are assumed to be perfect. In reality, even the best etalon will show defects that limit theoretically expected performance. Therefore, in a real etalon, the actual finesse will usually be lower than the reflectivity finesse.



Figure 1.59 **Reflectivity finesse vs. coating reflectance of each surface**

$$\mathcal{F}_{\mathrm{R}} = \frac{\pi\sqrt{R}}{1-R} \tag{1.117}$$

$$\mathcal{F}_{\mathrm{S}} = \frac{M}{2}\,\frac{\lambda}{633\ \mathrm{nm}} \tag{1.118}$$

$$\mathcal{F}_{\theta} = \frac{\lambda}{d\tan^2\theta} \tag{1.119}$$

$$\mathcal{F}_{\mathrm{D}} = \frac{\mathrm{CA}^2}{2d\lambda} \tag{1.120}$$

where $\mathcal{F}_{\mathrm{R}}$ is the reflectivity finesse, $\mathcal{F}_{\mathrm{s}}$ is the plate spherical deviation finesse coefficient, $\mathcal{F}_{\theta}$ is the incident beam divergence finesse coefficient, and $\mathcal{F}_{\mathrm{d}}$ is the diffraction-limited finesse coefficient.

The defects that contribute to this reduction are as shown in Figure 1.60 (graphical representations are exagerated for clarification).


a.
Spherical Defects ($\mathcal{F}_{\mathrm{s}}$)
b.
Spherical Irregularities ($\mathcal{F}_{\mathrm{dg}}$)
c.
Parallelism Defects ($\mathcal{F}_{\mathrm{dp}}$)

Figure 1.60 **Three types of defects contributing to the total defect finesse**

All three types of defects contribute to the total defect finesse $\mathcal{F}_{\mathrm{d}}$:

$$\frac{1}{\mathcal{F}_{\mathrm{d}}{}^2} = \frac{1}{\mathcal{F}_{\mathrm{S}}{}^2} + \frac{1}{\mathcal{F}_{\mathrm{dg}}{}^2} + \frac{1}{\mathcal{F}_{\mathrm{dp}}{}^2} \tag{1.121}$$

The beam divergence also influences the actual finesse of an etalon.

Taking into account all these contributions, the effective finesse ($\mathcal{F}_{\mathrm{e}}$) of an etalon (with $\mathcal{F}_{\mathrm{R}}$ being the reflectivity finesse and $\mathcal{F}_{\theta}$ the divergence finesse) is:

$$\frac{1}{\mathcal{F}_{\mathrm{e}}} = \sqrt{\frac{1}{\mathcal{F}_{\mathrm{R}}{}^2} + \frac{1}{\mathcal{F}_{\mathrm{D}}{}^2} + \frac{1}{\mathcal{F}_{\theta}{}^2} + \frac{1}{\mathcal{F}_{\mathrm{S}}{}^2}} \tag{1.122}$$

The effective finesse a user sees when using the etalon depends not only on the absolute clear aperture, but also on the used aperture of the etalon, especially when a high finesse is required.

The examples below show how the effective finesse varies with plate flatness and clear aperture.

Example 1: Air-spaced etalon,

$R = 95\%$ ($\pm 1\%$) at 633 nm

CA = 25 mm

Used aperture = 20 mm

Spacer (air gap) = 1 mm

Spherical / parallelism defects = <λ/20

Plate rms = 0.80 nm

Beam divergence = 0.1 mRad

$\mathcal{F}_{\mathrm{R}} = 61$, $\mathcal{F}_{\mathrm{e}} = 10$

Example 2: Air-spaced etalon,

Same parameters as example 1 except:

Used aperture = 5 mm

$\mathcal{F}_{\mathrm{R}} = 61$, $\mathcal{F}_{\mathrm{e}} = 40$ (± 4)

Example 3: Air-spaced etalon,

Same parameters as example 1 except:

Spherical / parallelism defects = λ/100

Plate rms = 0.40 nm

Beam divergence: 0.1mRad

$\mathcal{F}_{\mathrm{R}} = 61$, $\mathcal{F}_{\mathrm{e}} = 40$ (± 8)

These examples illustrate that, for large-aperture applications, it is important to use very high-quality plates to ensure a high finesse and good transmission values.

TUNING AN ETALON

Etalons can be tuned over a limited range to alter their peak transmission wavelengths. These techniques are:

Angle tuning or tilting the etalon: As the angle of incidence is increased, the center wavelength of the etalon can be tuned down the spectrum.

Temperature tuning: Primarily used for solid etalons, temperature-tuning changes both the actual spacing of the reflective surfaces via expansion and the index of refraction of the material, which changes the optical spacing. The tuning result can be given by

$$\frac{\partial(\mathrm{FSR})}{\partial T} = -(\mathrm{FSR})\left[\frac{1}{\mathrm{n}}\frac{\partial \eta}{\partial T} + \frac{1}{d}\frac{\partial d}{\partial T}\right] \qquad (1.123)$$

Pressure tuning: Air-spaced etalons can be tuned by increasing the pressure in the cavity between the optics, thereby increasing the effective index of refraction, and thus the effective spacing.

The above examples illustrate how critical the optical surface flatness, plate parallelism and surface quality are to the overall performance of an etalon. At CVI Melles Griot we have developed sophisticated software that allows us to simulate all effects that influence the performance of an etalon. To order an etalon, FSR, finesse and used aperture are required.

Ultrafast Theory

The distinguishing aspect of femtosecond laser optics design is the need to control the phase characteristic of the optical system over the requisite wide pulse bandwidth. CVI Melles Griot has made an intensive theoretical study of these effects. Certain coating designs have been modified with control of the phase characteristics in mind. New proprietary designs have been created with desirable characteristics for femtosecond researchers. All optics in this section have been tested by researchers in the field and we are constantly fielding new requests.

Assume that the power, reflectivity, and polarization characteristics of a laser mirror are acceptable over the bandwidth of a femtosecond pulse. This means that, over the entire pulse bandwidth, a cavity mirror may have a reflectivity greater than 99.8%; a 50% beamsplitter may have a fairly constant reflection; a polarizer may maintain its rejection of one polarization with an acceptable transmission of the other. It is not enough, however, to simply preserve the power spectrum $S(\omega) = |E(\omega)|^2$ when dealing with femtosecond pulses. The phase relationship among the Fourier components of the pulse must also be preserved in order that the pulse not be broadened or distorted. What constraint on the performance of a mirror or transmissive optic does this imply?

Consider a general initial pulse shape $E_0(t)$. As a function of its Fourier components, it may be expressed as:

$$E_0(t) = \int E(\omega)^{-i\omega t}\, d\omega \qquad (1.124)$$

Suppose this pulse reflects off of a mirror. For this example, we assume the mirror is "ideal", and use the Fourier transform of its complex amplitude reflectance:

$$r(\omega) = re^{+i\Phi(\omega)} = re^{+i\omega t_\mathrm{d}} \qquad (1.125)$$

For this "ideal" mirror, r is a real constant equal to the amplitude reflectivity that is assumed constant over the pulse bandwidth. All phase effects have been assumed to be describable by a single phase shift $\phi(\omega)$ that is linearly proportional to frequency with proportionality constant t_d. The reflected pulse is then:

$$\begin{aligned} E_\mathrm{r}(t) &= r\int E(\omega)^{-i\omega(t-t_\mathrm{d})}\, d\omega \\ &= rE(t-t_\mathrm{d}) \end{aligned} \qquad (1.126)$$

Thus, provided the phase shift is linear in frequency over the pulse bandwidth, the reflected pulse is scaled by the amplitude reflectance r, and delayed in time by the constant group delay t_d. It is, otherwise, an undistorted replica of the original pulse.

Examined over a large enough bandwidth, no optical system will exhibit the constant group delay over frequency needed for perfect fidelity. In general, the phase shift near some center frequency ω_0 may be expanded in a Taylor series for frequencies near ω_0:

$$\begin{aligned} \Phi(\omega) = {} & \Phi(\omega_0) + \Phi'(\omega_0)(\omega-\omega_0) + \\ & \Phi''(\omega_0)(\omega-\omega_0)^2/2! + \\ & \Phi'''(\omega_0)(\omega-\omega_0)^3/3! \ldots \end{aligned} \qquad (1.127)$$

These derivatives are, respectively, the group delay $\Phi'(\omega_0)$, the group velocity dispersion $\Phi''(\omega_0)$, and the cubic term $\Phi'''(\omega_0)$, evaluated at a center frequency ω_0. This expansion is heuristically useful, in an exactly soluble model, for the propagation of a transform-limited Gaussian pulse. Note, however, that for extremely short pulses the expansion above may be insufficient. A full numerical calculation may have to be performed using the actual phase shift function $\Phi(\omega)$. CVI Melles Griot will be happy to assist those interested in the modeling of real optical elements.

To illustrate pulse distortion due to the dependence of the group delay on frequency, consider what happens when an unchirped, transform-limited Gaussian pulse passes through a medium, or is incident on a mirror whose dominating contribution to phase distortion is non-zero group velocity dispersion. The field envelope of the pulse is assumed to be of the form:

$$E(t) = \exp\left[-\left(2\ \ln 2t^2/\tau_0^2\right)\right] \qquad (1.128)$$

where τ_0 is the initial pulse duration (FWHM of the pulse intensity). Let the pulse enter a medium or reflect off of a mirror with non-zero $\Phi''(\omega)$, measured in fsec^2 radians. (For a continuous medium-like glass, $\Phi''(\omega) = \beta''(\omega) \times z$ where $\beta''(\omega)$ is the group velocity dispersion (GVD) per centimeter of material, and z is the physical path length, in centimeters, traveled through the material.) The Gaussian pulse will be both chirped and temporally broadened by its encounter with group velocity dispersion. The power envelope will remain Gaussian; the result for the broadened FWHM is:

$$\tau_1 = \tau_0\left[1+\left(4\ln 2\Phi''(\omega)/\tau_0^2\right)^2\right]^{1/2} \qquad (1.129)$$

This result, valid only for initially unchirped, transform-limited Gaussian pulses, is nevertheless an excellent model to study the effects of dispersion on pulse propagation. The graphs shown in Figure 1.61 represent the theoretical broadening from dispersion for initial pulse widths ranging from 10 to 100 femtoseconds.



Figure 1.61 **Output pulse width vs. GVD**

GROUP-VELOCITY & CUBIC DISPERSION FOR VARIOUS OPTICAL MATERIALS

Figures 1.62 and 1.63 show the GVD and cubic dispersion respectively for some common used glasses. Some of the glasses can be used in the UV region. They should be useful in estimating material dispersion and pulse distortion effects. Please check these calculations independently before using them in a final design.



Figure 1.62 **GVD for common glasses**



Figure 1.63 **Cubic dispersion for common glasses**

DISPERSIVE PROPERTIES OF MIRRORS

CVI Melles Griot uses three basic designs; TLM1 mirrors for energy fluence greater than 100 mJ/cm^2, TLM2 mirrors for cw oscillators and low-fluence pulses, and TLMB mirrors which are a hybrid of the two. The reflectivity, GVD parameter, and cubic dispersion parameter for TLM2 high reflectors are shown in Figure 1.64. In these examples, the mirrors are centered at 800 nm and are designed for use at normal incidence and at 45 degrees. Note that, at the design wavelength, (a) GVD is zero, (b) the cubic term is minimized, and (c) at 45° incidence, the GVD of the p-polarization component is very sensitive to wavelength, while the GVD for s-polarization component is nearly zero over a broad wavelength range. Thus one should avoid using mirrors at 45° incidence with the p-polarization. On the other hand, at 45° incidence, s-polarization provides very broad bandwidth and minimizes pulse distortion problems and should be used whenever possible.



Figure 1.64 **Dispersion and reflectivity for mirrors TLM2-800-0 and TLM2-800-45**

Ti:Sapphire and other femtosecond laser systems need prismless compensation of the built-in positive chirp encountered in the laser optical circuit. This becomes mandatory in industrial and biomedical applications where the laser must provide a compact, stable, and reliable solution.

Negative Group Velocity Dispersion Mirrors (TNM2) meet these needs with off-the-shelf availability, and can be employed both intracavity and extracavity to satisfy chirp control requirements.

In experiments using CVI Melles Griot TNM2 negative group velocity dispersion mirrors, 200-mW, 80-fsec pulses centered at 785 nm were achieved in a simple, prismless, Ti:Sapphire oscillator. The configuration is shown in Figure 1.65.



Figure 1.65 **Typical optical setup incorporating low GVD and Negative GVD mirrors in an ultrafast application**



Figure 1.66 **Typical optical set-up of negative GVD mirrors**

OUTPUT COUPLERS AND BEAMSPLITTERS

Output-coupler partial reflectors and beamsplitters behave similarly; however, here is an additional consideration in their analysis. The behavior of the transmitted phase of the coating and the effect of material dispersion within the substrate on the transmitted beam have to be taken into account in a detailed analysis. In general, the coating transmitted phase has similar properties and magnitudes of GVD and cubic to the reflected phase. As usual, centering is important. As a beamsplitter, we recommend the 1.5 mm thick fused silica substrate PW-1006-UV. As an output coupler substrate, we recommend the 3.0 mm thick, 30 minute wedge fused silica substrate IF-1012-UV.

CVI Melles Griot has developed the TFPK Series Broadband Low Dispersion Polarizing Beamsplitters to satisfy requirements for very-high-power, short-pulse lasers. These optics are ideal for intracavity use in femtosecond regenerative amplifiers. The main emphasis is on linear phase characteristics. See Chapter 9 of Lasers, A. E. Siegman (University Science Books, Mill Valley, California, 1986), for a good discussion of linear pulse propagation.

In chirped pulse regenerative amplification, the pulse may have to pass through one or two polarizers twice per round trip. There can be 10 to 20 round trips before the gain is saturated and the pulse is ejected. At this stage the pulse is long (100–1000 psec); however the phase shift at each frequency must still be maintained to minimize the recompressed pulse width. The many round trips of the pulse in the regenerative amplifier put stringent requirements on the phase characteristics of the coatings.

Figure 1.67 shows the power transmission curves for both s- and p-polarization and the transmitted phase characteristics of the p component for a TFPK optimized at 800 nm. (Users may specify any wavelength



Figure 1.67 **Properties for one coated side of a TFPK polarizing beamsplitter optimized for 800 nm. Both sides are coated for these properties.**

from 250 nm to 1550 nm.) The phase characteristics shown are the GVD and the cubic phase term. Not shown are the reflected phase characteristics for *s*-polarization; they are similar to the *p*-polarization transmission curves, and have the same low nonlinearity and broad bandwidth. Note that both sides of the optic have the coating whose properties are described in Figure 1.67. Therefore, the *s*- and *p*-polarization transmissions per surface should be squared in determining the specifications. The phase characteristics show that in all modes of operation, the TFPK polarizer performance is dominated by the substrate.

There are some subtleties associated with the TFPK. The near 72° angle has to be set properly and optimized. Some thought has to be given to mechanical clearances of the laser beam at such a steep incidence angle. The reflectivity for *s*-polarization is limited to 75%. Variant designs can increase this at a slight loss in bandwidth, increase in incidence angle, and increase in insertion loss for the transmitted *p*-polarized component.

The FABS autocorrelator beamsplitters from CVI Melles Griot are broadband, 50% all-dielectric beamsplitters. They are useful in many types of pump-probe experiments and in the construction of antiresonant ring configurations. They are essentially lossless and extremely durable. Both have advantages over partially reflecting metal coatings.

Power transmission curves for the *s*- and *p*-polarized versions of the FABS, along with the corresponding reflected phase characteristics for beamsplitters optimized at 800 nm, are shown in Figures 1.68 and 1.69. The linear pulse propagation properties of these beamsplitters are dominated by the substrate material dispersion. As with virtually all dielectric coated optics, the *s*-polarized version is broader than *p*-polarized version. CVI Melles Griot can produce FABS in other than 50:50 with excellent phase characteristics.



Figure 1.68 **Transmission characteristics for FABS series polarizers with *p*-polarized light**



Figure 1.69 **Transmission characteristics for FABS series polarizers with *s*-polarized light**

ANTIREFLECTION COATINGS

All CVI Melles Griot antireflection coating designs work well in femtosecond operation as the forward-going phasor is the dominant contribution to the phase shift; the AR coating is very thin and simply "fixes" the small Fresnel reflection of the substrate.

PRISMS



Figure 1.70 **Brewster prism**

Very-high-quality isosceles Brewster's angle prisms for intra and extracavity use are available from CVI Melles Griot. The design of these prisms satisfies the condition of minimum loss due to entrance and exit at Brewster's angle. To calculate GVD at Brewsters angle, refer to Figure 1.70 and use the following equation:

$$\mathrm{GVD} = \frac{d^2}{d\omega^2}\psi\bigg|_{\omega-\omega_l} \approx \frac{\lambda_l^3}{2\pi c^2}\left[L\frac{d^2\eta}{d\lambda^2}\bigg|_{\lambda_l} - 4l\left(\frac{d\eta}{d\lambda}\bigg|_{\lambda_l}\right)^2\right] \qquad (1.130)$$

where

η = refractive index of the prisms (assuming the same material)
l = tip to tip distance ($\overline{AB}$)
L = total avg. glass path
ψ = spectral phase of the electric field
$\omega_l \lambda_l = 2\pi_c$ (assumes Brewster prism at minimum deviation).

For more on the Ultrafast phenomena, see J.C. Diels and W. Rudolph, Ultrashort Laser Pulse Phenomena, Academic Press, 1996.

CVI MELLES GRIOT. YOUR SOURCE FOR

BUILD-YOUR-OWN, RAPID DELIVERY SOLUTIONS.



CVI Melles Griot offers two-week delivery of optics at catalog prices.

- 4000 uncoated substrates
- 2500 coating options
- A wide variety of in-stock substrates available (curves, flats, prisms, waveplates)
- Coatings from 193 nm to 2300 nm
- Your order ships in two weeks or less

How can we help you make your project a success?



Lasers | Lenses | Mirrors | Assemblies | Windows | Shutters | Waveplates | Mounts

03W-8605-5.qxd 12/10/09 10:23 AM Page 1


Edit
Vertical
Digital
Horiz/Acq
Trig
Display
B1
0x3
0x3
0x3
0x1
0x2
D0
D1
D2
C1 3.75V/div
C2 3.75V/div
BW:2.0G
BW:2.0G

XYZs of Oscilloscopes

Primer

Tektronix®

Table of Contents

Introduction 4

Signal Integrity . . . . 5 - 6

The Significance of Signal Integrity 5
Why is Signal Integrity a Problem? 5
Viewing the Analog Origins of Digital Signals 6

The Oscilloscope . . . . 7 - 12

Understanding Waveforms & Waveform Measurements . .7
Types of Waves 8
Sine Waves 9
Square and Rectangular Waves 9
Sawtooth and Triangle Waves 9
Step and Pulse Shapes 9
Periodic and Non-periodic Signals 9
Synchronous and Asynchronous Signals 9
Complex Waves 10
Waveform Measurements 11
Frequency and Period 11
Voltage 11
Amplitude 11
Phase 11
Waveform Measurements with Digital Oscilloscopes 12

Types of Oscilloscopes .13 - 17
Digital Storage Oscilloscopes 13
Digital Phosphor Oscilloscopes 15
Mixed Signal Oscilloscopes 16
Digital Sampling Oscilloscopes 17

The Systems and Controls of an Oscilloscope .18 - 31
Vertical System and Controls 19
Position and Volts per Division 19
Input Coupling 19
Bandwidth Limit 19
Bandwidth Enhancement 20
Horizontal System and Controls 20
Acquisition Controls 20
Acquisition Modes 20
Types of Acquisition Modes 21
Starting and Stopping the Acquisition System 21
Sampling 22
Sampling Controls 22
Real-time Sampling Method 22
Equivalent-time Sampling Method 24
Position and Seconds per Division 26
Time Base Selections 26
Zoom/Pan 26
Search 26
XY Mode 26
Z Axis 26
XYZ Mode 26
Trigger System and Controls 27
Trigger Position 29
Trigger Level and Slope 29
Trigger Sources 29
Trigger Modes 30
Trigger Coupling 30
Trigger Holdoff 30
Display System and Controls 31
Other Oscilloscope Controls 31
Math and Measurement Operations 31
Digital Timing and State Acquisitions 31

The Complete Measurement System . . . . 32 - 34
Probes 32
Passive Probes 33
Active and Differential Probes 34
Logicl Probes 34
Specialty Probes 35
Probe Accessories 35

Performance Terms and Considerations . . . . . 35 - 42
Bandwidth 35
Rise Time 36
Sample Rate 37
Waveform Capture Rate 38
Record Length 38
Triggering Capabilities 39
Effective Bits 39
Frequency Response 39
Vertical Sensitivity 39
Sweep Speed 39
Gain Accuracy 39
Horizontal Accuracy (Time Base) 39
Vertical Resolution (Analog-to-Digital Converter) 39
Timing Resolution (MSO) 40
Connectivity 40
Expandability 40
Ease-of-use 42

Operating the Oscilloscope . . . . 43 - 45
Proper Grounding 43
Setting the Controls 43
Calibrating the Instrument 44
Connecting the Probes 44
Compensating the Probes 44

Oscilloscope Measurement Techniques . . . . . . 46 - 48
Voltage Measurements 46
Time and Frequency Measurements 47
Pulse Width and Rise Time Measurements 47
Phase Shift Measurements 48
Other Measurement Techniques 48

Written Exercises . . . . 49 - 54
Part I
A. Vocabulary Exercises 49
B. Application Exercises 50
Part II
A. Vocabulary Exercises 51
B. Application Exercises 52

Answer Key 54

Glossary . . . . 55 - 58

Introduction

Nature moves in the form of a sine wave, be it an ocean wave, earthquake, sonic boom, explosion, sound through air, or the natural frequency of a body in motion. Energy, vibrating particles and other invisible forces pervade our physical universe. Even light – part particle, part wave – has a fundamental frequency, which can be observed as color.

Sensors can convert these forces into electrical signals that you can observe and study with an oscilloscope. Oscilloscopes enable scientists, engineers, technicians, educators and others to “see” events that change over time.

Oscilloscopes are indispensable tools for anyone designing, manufacturing or repairing electronic equipment. In today’s fast-paced world, engineers need the best tools available to solve their measurement challenges quickly and accurately. As the eyes of the engineer, oscilloscopes are the key to meeting today’s demanding measurement challenges.

The usefulness of an oscilloscope is not limited to the world of electronics. With the proper sensor, an oscilloscope can measure all kinds of phenomena. A sensor is a device that creates an electrical signal in response to physical stimuli, such as sound, mechanical stress, pressure, light, or heat. A microphone is a sensor that converts sound into an electrical signal. Figure 1 shows an example of scientific data that can be gathered by an oscilloscope.

Oscilloscopes are used by everyone from physicists to repair technicians. An automotive engineer uses an oscilloscope to correlate analog data from sensors with serial data from the engine control unit. A medical researcher uses an oscillscope to measure brain waves. The possibilities are endless.

The concepts presented in this primer will provide you with a good starting point in understanding oscilloscope basics and operation.



Figure 1. An example of scientific data gathered by an oscilloscope.

The glossary in the back of this primer will give you definitions of unfamiliar terms. The vocabulary and multiple-choice written exercises on oscilloscope theory and controls make this primer a useful classroom aid. No mathematical or electronics knowledge is necessary.

After reading this primer, you will be able to:

- Describe how oscilloscopes work
- Describe the differences between various oscilloscopes
- Describe electrical waveform types
- Understand basic oscilloscope controls
- Take simple measurements

The manual provided with your oscilloscope will give you more specific information about how to use the oscilloscope in your work. Some oscilloscope manufacturers also provide a multitude of application notes to help you optimize the oscilloscope for your application-specific measurements.

Should you need additional assistance, or have any comments or questions about the material in this primer, simply contact your Tektronix representative, or visit **www.tektronix.com**.

Signal Integrity

The Significance of Signal Integrity

The key to any good oscilloscope system is its ability to accurately reconstruct a waveform – referred to as signal integrity. An oscilloscope is analogous to a camera that captures signal images that we can then observe and interpret. Two key issues lie at the heart of signal integrity.

- When you take a picture, is it an accurate picture of what actually happened?
- Is the picture clear or fuzzy?
- How many of those accurate pictures can you take per second?

Taken together, the different systems and performance capabilities of an oscilloscope contribute to its ability to deliver the highest signal integrity possible. Probes also affect the signal integrity of a measurement system.

Signal integrity impacts many electronic design disciplines. But until a few years ago, it wasn't much of a problem for digital designers. They could rely on their logic designs to act like the Boolean circuits they were. Noisy, indeterminate signals were something that occurred in high-speed designs – something for RF designers to worry about. Digital systems switched slowly and signals stabilized predictably.

Processor clock rates have since multiplied by orders of magnitude. Computer applications such as 3D graphics, video and server I/O demand vast bandwidth. Much of today's telecommunications equipment is digitally based, and similarly requires massive bandwidth. So too does digital high-definition TV. The current crop of microprocessor devices handles data at rates up to 2, 3 and even 5 GS/s (gigasamples per second), while some DDR3 memory devices use clocks in excess of 2 GHz as well as data signals with 35 ps rise times.

Importantly, speed increases have trickled down to the common IC devices used in automobiles, consumer electronics, and machine controllers, to name just a few applications.

A processor running at a 20 MHz clock rate may well have signals with rise times similar to those of an 800 MHz processor. Designers have crossed a performance threshold that means, in effect, almost every design is a high-speed design.

Without some precautionary measures, high-speed problems can creep into otherwise conventional digital designs. If a circuit is experiencing intermittent failures, or if it encounters errors at voltage and temperature extremes, chances are there are some hidden signal integrity problems. These can affect time-to-market, product reliability, EMI compliance, and more. These high-speed problems can also impact the integrity of a serial data stream in a system, requiring some method of correlating specific patterns in the data with the observed characteristics of high-speed waveforms.

Why is Signal Integrity a Problem?

Let's look at some of the specific causes of signal degradation in today's digital designs. Why are these problems so much more prevalent today than in years past?

The answer is speed. In the "slow old days," maintaining acceptable digital signal integrity meant paying attention to details like clock distribution, signal path design, noise margins, loading effects, transmission line effects, bus termination, decoupling and power distribution. All of these rules still apply, but…

Bus cycle times are up to a thousand times faster than they were 20 years ago! Transactions that once took microseconds are now measured in nanoseconds. To achieve this improvement, edge speeds too have accelerated: they are up to 100 times faster than those of two decades ago.

This is all well and good; however, certain physical realities have kept circuit board technology from keeping up the pace. The propagation time of inter-chip buses has remained almost unchanged over the decades. Geometries have shrunk, certainly, but there is still a need to provide circuit board real estate for IC devices, connectors, passive components, and of course, the bus traces themselves. This real estate adds up to distance, and distance means time – the enemy of speed.

It's important to remember that the edge speed – rise time – of a digital signal can carry much higher frequency components than its repetition rate might imply. For this reason, some designers deliberately seek IC devices with relatively "slow" rise times.

The lumped circuit model has always been the basis of most calculations used to predict signal behavior in a circuit. But when edge speeds are more than four to six times faster than the signal path delay, the simple lumped model no longer applies.

Circuit board traces just six inches long become transmission lines when driven with signals exhibiting edge rates below four to six nanoseconds, irrespective of the cycle rate. In effect, new signal paths are created. These intangible connections aren't on the schematics, but nevertheless provide a means for signals to influence one another in unpredictable ways.

Sometimes even the errors introduced by the probe/instrument combination can provide a significant contribution to the signal being measured. However, by applying the "square root of the sum of the squares" formula to the measured value, it is possible to determine whether the device under test is approaching a rise/fall time failure. In addition, recent oscilloscope tools use special filtering techniques to de-embed the measurement system's effects on the signal, displaying edge times and other signal characteristics.

At the same time, the intended signal paths don't work the way they are supposed to. Ground planes and power planes, like the signal traces described above, become inductive and act like transmission lines; power supply decoupling is far less effective. EMI goes up as faster edge speeds produce shorter wavelengths relative to the bus length. Crosstalk increases.

In addition, fast edge speeds require generally higher currents to produce them. Higher currents tend to cause ground bounce, especially on wide buses in which many signals switch at once. Moreover, higher current increases the amount of radiated magnetic energy and with it, crosstalk.

Viewing the Analog Origins of Digital Signals

What do all these characteristics have in common? They are classic analog phenomena. To solve signal integrity problems, digital designers need to step into the analog domain. And to take that step, they need tools that can show them how digital and analog signals interact.

Digital errors often have their roots in analog signal integrity problems. To track down the cause of the digital fault, it's often necessary to turn to an oscilloscope, which can display waveform details, edges and noise; can detect and display transients; and can help you precisely measure timing relationships such as setup and hold times. Modern oscilloscopes can help to simplify the troubleshooting process by triggering on specific patterns in parallel or serial data streams and displaying the analog signal that corresponds in time with a specified event.

Understanding each of the systems within your oscilloscope and how to apply them will contribute to the effective application of the oscilloscope to tackle your specific measurement challenge.



Figure 2. X, Y, and Z components of a displayed waveform.

The Oscilloscope

What is an oscilloscope and how does it work? This section answers these fundamental questions.

The oscilloscope is basically a graph-displaying device – it draws a graph of an electrical signal. In most applications, the graph shows how signals change over time: the vertical (Y) axis represents voltage and the horizontal (X) axis represents time. The intensity or brightness of the display is sometimes called the Z axis, as shown in Figure 2. In DPO oscilloscopes, the Z axis can be represented by color grading of the display, as seen in Figure 3.

This simple graph can tell you many things about a signal, such as:

- The time and voltage values of a signal
- The frequency of an oscillating signal
- The "moving parts" of a circuit represented by the signal
- The frequency with which a particular portion of the signal is occurring relative to other portions
- Whether or not a malfunctioning component is distorting the signal
- How much of a signal is direct current (DC) or alternating current (AC)
- How much of the signal is noise and whether the noise is changing with time



C1 200mV/div 50Ω B_W:18.0G
C2 200mV/div 50Ω B_W:18.0G
C3 200mV/div 50Ω B_W:18.0G
A C1 ∫ 0.0V
10.0ns/div 50.0GS/s IT 10.0ps/pt
Stopped
59 acqs RL:10.0k
Cons February 04, 2009 10:30:03

Figure 3. Two offset clock patterns with Z axis intensity grading.

Understanding Waveforms and Waveform Measurements

The generic term for a pattern that repeats over time is a wave – sound waves, brain waves, ocean waves, and voltage waves are all repetitive patterns. An oscilloscope measures voltage waves. Remember as mentioned earlier, that physical phenomena such as vibrations or temperature or electrical phenomena such as current or power can be converted to a voltage by a sensor. One cycle of a wave is the portion of the wave that repeats. A waveform is a graphic representation of a wave. A voltage waveform shows time on the horizontal axis and voltage on the vertical axis.


Sine Wave
Damped Sine Wave
Square Wave
Rectangular Wave
Sawtooth Wave
Triangle Wave
Step
Pulse
Complex

Figure 4. Common waveforms.



Figure 5. Sources of common waveforms.

Waveform shapes reveal a great deal about a signal. Any time you see a change in the height of the waveform, you know the voltage has changed. Any time there is a flat horizontal line, you know that there is no change for that length of time. Straight, diagonal lines mean a linear change – rise or fall of voltage at a steady rate. Sharp angles on a waveform indicate sudden change. Figure 4 shows common waveforms and Figure 5 displays sources of common waveforms.

Types of Waves

You can classify most waves into these types:

- Sine waves
- Square and rectangular waves
- Sawtooth and triangle waves
- Step and pulse shapes
- Periodic and non-periodic signals
- Synchronous and asynchronous signals
- Complex waves

Sine Waves

The sine wave is the fundamental wave shape for several reasons. It has harmonious mathematical properties – it is the same sine shape you may have studied in trigonometry class. The voltage in your wall outlet varies as a sine wave. Test signals produced by the oscillator circuit of a signal generator are often sine waves. Most AC power sources produce sine waves. (AC signifies alternating current, although the voltage alternates too. DC stands for direct current, which means a steady current and voltage, such as a battery produces.)

The damped sine wave is a special case you may see in a circuit that oscillates, but winds down over time.

Square and Rectangular Waves

The square wave is another common wave shape. Basically, a square wave is a voltage that turns on and off (or goes high and low) at regular intervals. It is a standard wave for testing amplifiers – good amplifiers increase the amplitude of a square wave with minimum distortion. Television, radio and computer circuitry often use square waves for timing signals.

The rectangular wave is like the square wave except that the high and low time intervals are not of equal length. It is particularly important when analyzing digital circuitry.

Sawtooth and Triangle Waves

Sawtooth and triangle waves result from circuits designed to control voltages linearly, such as the horizontal sweep of an analog oscilloscope or the raster scan of a television. The transitions between voltage levels of these waves change at a constant rate. These transitions are called ramps.

Step and Pulse Shapes

Signals such as steps and pulses that occur rarely, or non-periodically, are called single-shot or transient signals. A step indicates a sudden change in voltage, similar to the voltage change you would see if you turned on a power switch.

A pulse indicates sudden changes in voltage, similar to the voltage changes you would see if you turned a power switch on and then off again. A pulse might represent one bit of information traveling through a computer circuit or it might be a glitch, or defect, in a circuit. A collection of pulses traveling together creates a pulse train. Digital components in a computer communicate with each other using pulses. These pulses may be in the form of serial data stream or multiple signal lines may be used to represent a value in a parallel data bus. Pulses are also common in x-ray, radar, and communications equipment.

Periodic and Non-periodic Signals

Repetitive signals are referred to as periodic signals, while signals that constantly change are known as non-periodic signals. A still picture is analogous to a periodic signal, while a moving picture can be equated to a non-periodic signal.

Synchronous and Asynchronous Signals

When a timing relationship exists between two signals, those signals are referred to as synchronous. Clock, data and address signals inside a computer are an example of synchronous signals.

Asynchronous is a term used to describe those signals between which no timing relationship exists. Because no time correlation exists between the act of touching a key on a computer keyboard and the clock inside the computer, these are considered asynchronous.


Run
Trig'd
1 120mV
10.0µs
35.2200µs
1.00GS/s
100k points
1 525/NTSC
All Lines
Type
Video
Standard
525/NTSC
Source
1
Trigger On
All Lines
Mode
Auto
& Holdoff

Figure 6. An NTSC composite video signal is an example of a complex wave.


File
Edit
Vertical
Horiz/Acq
Trig
Display
Cursor
Measure
Mask
Math
MyScope
Analyze
Utilities
Help
Tek
C1 94.0mV Offset:560mV 50Ω
t1 -32.5ps
t2 1.575ns
Δt 1.608ns
1/Δt 622.1MHz
C1 Comm 966mV
250ps 400GS/s ET 2.5ps/pt
FastAcq Sample
1 008 960 acqs RL:1.0k
February 06, 2006 14:02:54

	Value	Mean	Min	Max	St Dev	Count	Info
C1 Ext Ratio	1.776	1.775566	1.776	1.776	8.107µ	909.0	
C1 EyeHgt	435.4mV	435.45176m	435.4m	435.5m	5.346µ	909.0	
C1 EyeWid	1.462ns	1.4617506n	1.461n	1.462n	14.66f	909.0	
C1 High	1.241V	1.24056	1.241	1.241	0.0	700.0	
C1 Rise	265.0ps	243.20313p	242.5p	265.0p	3.946p	909.0	
C1 Pk-Pk	661.8mV	661.76003m	661.8m	661.8m	0.0	622.0	
C1 Cross %	49.18%	49.179632	49.18	49.18	156.3µ	165.0	
C1 Pos Wid	1.6ns	1.5999897n	1.6n	1.6n	7.573f	519.0	

Figure 7. 622 Mb/s serial data eye pattern.

Complex Waves

Some waveforms combine the characteristics of sines, squares, steps, and pulses to produce complex waveshapes. The signal information may be embedded in the form of amplitude, phase, and/or frequency variations. For example, although the signal in Figure 6 is an ordinary composite video signal, it is composed of many cycles of higher-frequency waveforms embedded in a lower-frequency envelope.

In this example, it is usually most important to understand the relative levels and timing relationships of the steps. To view this signal, you need an oscilloscope that captures the low-frequency envelope and blends in the higher-frequency waves in an intensity-graded fashion so that you can see their overall combination as an image that can be visually interpreted. Digital phosphor oscilloscopes are most suited to viewing complex waves, such as video signals, illustrated in Figure 6. Their displays provide the necessary frequency-of-occurrence information, or intensity grading, that is essential to understanding what the waveform is really doing.

Some oscilloscopes allow for displaying certain types of complex waveforms in special ways. For example, telecommunications data may be displayed as an eye pattern or a constellation diagram.

Telecommunications digital data signals can be displayed on an oscilloscope as a special type of waveform referred to as an eye pattern. The name comes from the similarity of the waveform to a series of eyes, as seen in Figure 7. Eye patterns are produced when digital data from a receiver is sampled and applied to the vertical input, while the data rate is used to trigger the horizontal sweep. The eye pattern displays one bit or unit interval of data with all possible edge transitions and states superimposed in one comprehensive view.

A constellation diagram is a representation of a signal modulated by a digital modulation scheme such as quadrature amplitude modulation or phase-shift keying.



Figure 8. Frequency and period of a sine wave.



Figure 9. Amplitude and degrees of a sine wave.

Waveform Measurements

Many terms are used to describe the types of measurements that you make with your oscilloscope. This section describes some of the most common measurements and terms.

Frequency and Period

If a signal repeats, it has a frequency. The frequency is measured in Hertz (Hz) and equals the number of times the signal repeats itself in one second, referred to as cycles per second. A repetitive signal also has a period, which is the amount of time it takes the signal to complete one cycle. Period and frequency are reciprocals of each other, so that 1/period equals the frequency and 1/frequency equals the period. For example, the sine wave in Figure 8 has a frequency of 3 Hz and a period of 1/3 second.

Voltage

Voltage is the amount of electric potential, or signal strength, between two points in a circuit. Usually, one of these points is ground, or zero volts, but not always. You may want to measure the voltage from the maximum peak to the minimum peak of a waveform, referred to as the peak-to-peak voltage.

Amplitude

Amplitude refers to the amount of voltage between two points in a circuit. Amplitude commonly refers to the maximum voltage of a signal measured from ground, or zero volts. The waveform shown in Figure 9 has an amplitude of 1 V and a peak-to-peak voltage of 2 V.



Figure 10. Phase shift.

Phase

Phase is best explained by looking at a sine wave. The voltage level of sine waves is based on circular motion. Given that a circle has 360°, one cycle of a sine wave has 360°, as shown in Figure 9. Using degrees, you can refer to the phase angle of a sine wave when you want to describe how much of the period has elapsed.

Phase shift describes the difference in timing between two otherwise similar signals. The waveform in Figure 10 labeled "current" is said to be 90° out of phase with the waveform labeled "voltage," since the waves reach similar points in their cycles exactly 1/4 of a cycle apart (360°/4 = 90°). Phase shifts are common in electronics.

Waveform Measurements with Digital Oscilloscopes

Modern digital oscilloscopes have functions that make waveform measurements easier. They have front-panel buttons and/or screen-based menus from which you can select fully automated measurements. These include amplitude, period, rise/fall time, and many more. Many digital instruments also provide mean and RMS calculations, duty cycle, and other math operations. Automated measurements appear as on-screen alphanumeric readouts. Typically these readings are more accurate than is possible to obtain with direct graticule interpretation.

Examples of fully automated waveform measurements:

- Period
- Frequency
- Width +
- Width -
- Rise time
- Fall time
- Amplitude
- Extinction ratio
- Mean optical power
- Duty Cycle +
- Duty Cycle -
- Delay
- Phase
- Burst width
- Peak-to-peak
- Mean
- Cycle mean
- Cycle area
- High
- Low
- Minimum
- Maximum
- Overshoot +
- Overshoot -
- RMS
- Cycle RMS
- Jitter


1010
0001
0010
0101
ADC
Analog Oscilloscopes Trace Signals
Digital Oscilloscopes Samples Signals and Construct Displays

Figure 11. Analog oscilloscopes trace signals, while digital oscilloscopes sample signals and construct displays.

The Types of Oscilloscopes

Electronic equipment can be classified into two categories: analog and digital. Analog equipment works with continuously variable voltages, while digital equipment works with discrete binary numbers that represent voltage samples. A conventional phonograph is an analog device, while a compact disc player is a digital device.

Oscilloscopes can be classified similarly – as analog and digital types. In contrast to an analog oscilloscope, a digital oscilloscope uses an analog-to-digital converter (ADC) to convert the measured voltage into digital information. It acquires the waveform as a series of samples, and stores these samples until it accumulates enough samples to describe a waveform. The digital oscilloscope then re-assembles the waveform for display on the screen, as seen in Figure 11.

Digital oscilloscopes can be classified into digital storage oscilloscopes (DSOs), digital phosphor oscilloscopes (DPOs), mixed signal oscilloscopes (MSOs), and digital sampling oscilloscopes.

The digital approach means that the oscilloscope can display any frequency within its range with stability, brightness, and clarity. For repetitive signals, the bandwidth of the digital oscilloscope is a function of the analog bandwidth of the front-end components of the oscilloscope, commonly referred to as the –3 dB point. For single-shot and transient events, such as pulses and steps, the bandwidth can be limited by the oscilloscope's sample rate. Please refer to the Sample Rate section under Performance Terms and Considerations for a more detailed discussion.

Digital Storage Oscilloscopes

A conventional digital oscilloscope is known as a digital storage oscilloscope (DSO). Its display typically relies on a raster-type screen rather than the luminous phosphor found in an older analog oscilloscope.

Digital storage oscilloscopes (DSOs) allow you to capture and view events that may happen only once – known as transients. Because the waveform information exists in digital form as a series of stored binary values, it can be analyzed, archived, printed, and otherwise processed, within the oscilloscope itself or by an external computer. The waveform need not be continuous; it can be displayed even when the signal disappears. Unlike analog oscilloscopes, digital storage oscilloscopes provide permanent signal storage and extensive waveform processing. However, DSOs typically have no real-time intensity grading; therefore, they cannot express varying levels of intensity in the live signal.



Figure 12. The serial-processing architecture of a digital storage oscilloscope (DSO).

Some of the subsystems that comprise DSOs are similar to those in analog oscilloscopes. However, DSOs contain additional data-processing subsystems that are used to collect and display data for the entire waveform. A DSO employs a serial-processing architecture to capture and display a signal on its screen, as shown in Figure 12. A description of this serial-processing architecture follows.

Serial-processing Architecture

Like an analog oscilloscope, a DSO's first (input) stage is a vertical amplifier. Vertical controls allow you to adjust the amplitude and position range at this stage. Next, the analog-to-digital converter (ADC) in the horizontal system samples the signal at discrete points in time and converts the signal's voltage at these points into digital values called sample points. This process is referred to as digitizing a signal.

The horizontal system's sample clock determines how often the ADC takes a sample. This rate is referred to as the sample rate and is expressed in samples per second (S/s).

The sample points from the ADC are stored in acquisition memory as waveform points. Several sample points may comprise one waveform point. Together, the waveform points comprise one waveform record. The number of waveform points used to create a waveform record is called the record length. The trigger system determines the start and stop points of the record.

The DSO's signal path includes a microprocessor through which the measured signal passes on its way to the display. This microprocessor processes the signal, coordinates display activities, manages the front panel controls, and more. The signal then passes through the display memory and is displayed on the oscilloscope screen.



Figure 13. The digital storage oscilloscope delivers high-speed, single-shot acquisition across multiple channels, increasing the likelihood of capturing elusive glitches and transient events.

Depending on the capabilities of your oscilloscope, additional processing of the sample points may take place, which enhances the display. Pre-trigger may also be available, enabling you to see events before the trigger point. Most of today's digital oscilloscopes also provide a selection of automatic parametric measurements, simplifying the measurement process.

As shown in Figure 13, a DSO provides high performance in a single-shot, multi-channel instrument. DSOs are ideal for low-repetition-rate or single-shot, high-speed, multi-channel design applications. In the real world of digital design, an engineer usually examines four or more signals simultaneously, making the DSO a critical companion.


Snapshots of the Digital Phosphor contents are periodically sent directly to the display without stopping the acquisition.
Amp
A/D
Digital Phosphor
Display
µP
Waveform math, measurements, and front panel control are executed by the microprocessor parallel to the integrated acquisition/display system.

Figure 14. The parallel-processing architecture of a digital phosphor oscilloscope (DPO).

Digital Phosphor Oscilloscopes

The digital phosphor oscilloscope (DPO) offers a new approach to oscilloscope architecture. This architecture enables a DPO to deliver unique acquisition and display capabilities to accurately reconstruct a signal.

While a DSO uses a serial-processing architecture to capture, display and analyze signals, a DPO employs a parallel-processing architecture to perform these functions, as shown in Figure 14. The DPO architecture dedicates unique ASIC hardware to acquire waveform images, delivering high waveform capture rates that result in a higher level of signal visualization. This performance increases the probability of witnessing transient events that occur in digital systems, such as runt pulses, glitches and transition errors, and enables additional analysis capability. A description of this parallel-processing architecture follows.

Parallel-processing Architecture

A DPO's first (input) stage is similar to that of an analog oscilloscope – a vertical amplifier – and its second stage is similar to that of a DSO – an ADC. But, the DPO differs significantly from its predecessors following the analog-to-digital conversion.

For any oscilloscope – analog, DSO or DPO – there is always a holdoff time during which the instrument processes the most recently acquired data, resets the system, and waits for the next trigger event. During this time, the oscilloscope is blind to all signal activity. The probability of seeing an infrequent or low-repetition event decreases as the holdoff time increases.

It should be noted that it is impossible to determine the probability of capture by simply looking at the display update rate. If you rely solely on the update rate, it is easy to make the mistake of believing that the oscilloscope is capturing all pertinent information about the waveform when, in fact, it is not.

The digital storage oscilloscope processes captured waveforms serially. The speed of its microprocessor is a bottleneck in this process because it limits the waveform capture rate.

The DPO rasterizes the digitized waveform data into a digital phosphor database. Every 1/30th of a second – about as fast as the human eye can perceive it – a snapshot of the signal image that is stored in the database is pipelined directly to the display system. This direct rasterization of waveform data, and direct copy to display memory from the database, removes the data-processing bottleneck inherent in other architectures. The result is an enhanced "real-time" and lively display update. Signal details, intermittent events, and dynamic characteristics of the signal are captured in real-time. The DPO's microprocessor works in parallel with this integrated acquisition system for display management, measurement automation and instrument control, so that it does not affect the oscilloscope's acquisition speed.

A DPO faithfully emulates the best display attributes of an analog oscilloscope, displaying the signal in three dimensions: time, amplitude and the distribution of amplitude over time, all in real-time.



Figure 15. Some DPOs can acquire millions of waveform in just seconds, significantly increasing the probability of capturing intermittent and elusive events and revealing dynamic signal behavior.



Figure 16. The MSO provides 16 integrated digital channels, enabling the ability to view and analyze time-correlated analog and digital signals.

Unlike an analog oscilloscope's reliance on chemical phosphor, a DPO uses a purely electronic digital phosphor that's actually a continuously updated database. This database has a separate "cell" of information for every single pixel in the oscilloscope's display. Each time a waveform is captured – in other words, every time the oscilloscope triggers – it is mapped into the digital phosphor database's cells. Each cell that represents a screen location and is touched by the waveform is reinforced with intensity information, while other cells are not. Thus, intensity information builds up in cells where the waveform passes most often.

When the digital phosphor database is fed to the oscilloscope's display, the display reveals intensified waveform areas, in proportion to the signal's frequency of occurrence at each point – much like the intensity grading characteristics of an analog oscilloscope. The DPO also allows the display of the varying frequency-of-occurrence information on the display as contrasting colors, unlike an analog oscilloscope. With a DPO, it is easy to see the difference between a waveform that occurs on almost every trigger and one that occurs, say, every 100th trigger.

Digital phosphor oscilloscopes (DPOs) break down the barrier between analog and digital oscilloscope technologies. They are equally suitable for viewing high and low frequencies, repetitive waveforms, transients, and signal variations in real-time. Only a DPO provides the Z (intensity) axis in real-time that is missing from conventional DSOs.

A DPO is ideal for those who need the best general-purpose design and troubleshooting tool for a wide range of applications, as seen in Figure 15. A DPO is exemplary for advanced analysis, communication mask testing, digital debug of intermittent signals, repetitive digital design and timing applications.

Mixed Signal Oscilloscopes

The mixed signal oscilloscope (MSO) combines the performance of a DPO with the basic functionality of a 16-channel logic analyzer, including parallel/serial bus protocol decoding and triggering. The MSO's digital channels view a digital signal as either a logic high or logic low, just like a digital circuit views the signal. This means as long as ringing, overshoot and ground bounce do not cause logic transitions, these analog characteristics are not of concern to the MSO. Just like a logic analyzer, a MSO uses a threshold voltage to determine if the signal is logic high or logic low.

The MSO is the tool of choice for quickly debugging digital circuits using its powerful digital triggering, high resolution acquisition capability, and analysis tools. The root cause of many digital problems is quicker to pinpoint by analyzing both the analog and digital representations of the signal, as shown in Figure 16, making a MSO ideal for verifying and debugging digital circuits.



Figure 17. The architecture of a digital sampling oscilloscope.

Digital Sampling Oscilloscopes

In contrast to the digital storage and digital phosphor oscilloscope architectures, the architecture of the digital sampling oscilloscope reverses the position of the attenuator/amplifier and the sampling bridge, as shown in Figure 17. The input signal is sampled before any attenuation or amplification is performed. A low bandwidth amplifier can then be utilized after the sampling bridge because the signal has already been converted to a lower frequency by the sampling gate, resulting in a much higher bandwidth instrument.

The tradeoff for this high bandwidth, however, is that the sampling oscilloscope's dynamic range is limited. Since there is no attenuator/amplifier in front of the sampling gate, there is no facility to scale the input. The sampling bridge must be able to handle the full dynamic range of the input at all times. Therefore, the dynamic range of most sampling oscilloscopes is limited to about 1 V peak-to-peak. Digital storage and digital phosphor oscilloscopes, on the other hand, can handle 50 to 100 volts.

In addition, protection diodes cannot be placed in front of the sampling bridge as this would limit the bandwidth. This reduces the safe input voltage for a sampling oscilloscope to about 3 V, as compared to 500 V available on other oscilloscopes.



Triggered Waveforms= 0

Acq Mode Average

Trig Internal Clock

C3 500.0mp/div

C4 500.0mp/div

v1 1.000p

v2 -1.000p

Δv -2.000p

C3 500.0mp/ 0.0p

100.0ps/di 24.000n

9:13 AM 10/27/00

Figure 18. Time domain reflectometry (TDR) display from a digital sampling oscilloscope.

When measuring high-frequency signals, the DSO or DPO may not be able to collect enough samples in one sweep. A digital sampling oscilloscope is an ideal tool for accurately capturing signals whose frequency components are much higher than the oscilloscope's sample rate, as seen in Figure 18. This oscilloscope is capable of measuring signals of up to an order of magnitude faster than any other oscilloscope. It can achieve bandwidth and high-speed timing ten times higher than other oscilloscopes for repetitive signals. Sequential equivalent-time sampling oscilloscopes are available with bandwidths to 80 GHz.

The Systems and Controls of an Oscilloscope

This section briefly describes the basic systems and controls found on analog and digital oscilloscopes. Some controls differ between analog and digital oscilloscopes; your oscilloscope probably has additional controls not discussed here.

A basic oscilloscope consists of four different systems – the vertical system, horizontal system, trigger system, and display system. Understanding each of these systems will enable you to effectively apply the oscilloscope to tackle your specific measurement challenges. Recall that each system contributes to the oscilloscope's ability to accurately reconstruct a signal.

The front panel of an oscilloscope is divided into three main sections labeled vertical, horizontal, and trigger. Your oscilloscope may have other sections, depending on the model and type. See if you can locate these front-panel sections in Figure 19, and on your oscilloscope, as you read through this section.

When using an oscilloscope, you need to adjust three basic settings to accommodate an incoming signal:

- Vertical: The attenuation or amplification of the signal. Use the volts/div control to adjust the amplitude of the signal to the desired measurement range.
- Horizontal: The time base. Use the sec/div control to set the amount of time per division represented horizontally across the screen.
- Trigger: The triggering of the oscilloscope. Use the trigger level to stabilize a repeating signal, or to trigger on a single event.


DVD
RW
Autoset
Default Setup
Print
Run/Stop
Single
Clear
FastAcq
DPX
Intensity
Horizontal
Trigger
Push - Fine
Multiview Zoom™
Position
Edge
Advanced
Source
Ch 1
Ch 2
Arm
Ch 3
Ch 4
Ready
Aux
Line
Trig'd
Delay
Multipurpose
Cursors
Resolution
Level
More Samples
Search
Mark
Scale
Push Set 50%
Slope
Pos
Neg
Mode
Norm
Auto
Set/Clear
Touch Screen
Off
Vertical
Ch 1
Ch 2
Ch 3
Ch 4
Position
Offset
Push-Select
Scale

Figure 19. Front-panel control section of an oscilloscope.

Common vertical controls include:

- Termination
  - 1M ohm
  - 50 ohm
- Coupling
  - DC
  - AC
  - GND
- Bandwidth
  - Limit
  - Enhancement
- Position
- Offset
- Invert – On/Off
- Scale
  - Fixed steps
  - Variable



DC Coupling of a $V_{p\text{-}p}$ Sine Wave with a 2 V DC Component

AC Coupling of the Same Signal

Figure 20. AC and DC input coupling.

Vertical System and Controls

Vertical controls can be used to position and scale the waveform vertically, set the input coupling, and adjust other signal conditioning.

Position and Volts per Division

The vertical position control allows you to move the waveform up and down exactly where you want it on the screen.

The volts-per-division setting (usually written as volts/div) is a scaling factor that varies the size of the waveform on the screen. If the volts/div setting is 5 volts, then each of the eight vertical divisions represents 5 volts and the entire screen can display 40 volts from bottom to top, assuming a graticule with eight major divisions. If the setting is 0.5 volts/div, the screen can display 4 volts from bottom to top, and so on. The maximum voltage you can display on the screen is the volts/div setting multiplied by the number of vertical divisions. Note that the probe you use, 1X or 10X, also influences the scale factor. You must divide the volts/div scale by the attenuation factor of the probe if the oscilloscope does not do it for you.

Often the volts/div scale has either a variable gain or a fine gain control for scaling a displayed signal to a certain number of divisions. Use this control to assist in taking rise time measurements.

Input Coupling

Coupling refers to the method used to connect an electrical signal from one circuit to another. In this case, the input coupling is the connection from your test circuit to the oscilloscope. The coupling can be set to DC, AC, or ground. DC coupling shows all of an input signal. AC coupling blocks the DC component of a signal so that you see the waveform centered around zero volts. Figure 20 illustrates this difference. The AC coupling setting is useful when the entire signal (alternating current + direct current) is too large for the volts/div setting.

The ground setting disconnects the input signal from the vertical system, which lets you see where zero volts is located on the screen. With grounded input coupling and auto trigger mode, you see a horizontal line on the screen that represents zero volts. Switching from DC to ground and back again is a handy way of measuring signal voltage levels with respect to ground.

Bandwidth Limit

Most oscilloscopes have a circuit that limits the bandwidth of the oscilloscope. By limiting the bandwidth, you reduce the noise that sometimes appears on the displayed waveform, resulting in a cleaner signal display. Note that, while eliminating noise, the bandwidth limit can also reduce or eliminate high-frequency signal content.

Bandwidth Enhancement

Some oscilloscopes may provide a DSP arbitrary equalization filter which can be used to improve the oscilloscope channel response. This filter extends the bandwidth, flattens the oscilloscope channel frequency response, improves phase linearity, and provides a better match between channels. It also decreases rise time and improves the time domain step response.

Horizontal System and Controls

An oscilloscope's horizontal system is most closely associated with its acquisition of an input signal – sample rate and record length are among the considerations here. Horizontal controls are used to position and scale the waveform horizontally.

Acquisition Controls

Digital oscilloscopes have settings that let you control how the acquisition system processes a signal. Look over the acquisition options on your digital oscilloscope while you read this description. Figure 21 shows you an example of an acquisition menu.

Acquisition Modes

Acquisition modes control how waveform points are produced from sample points. Sample points are the digital values derived directly from the analog-to-digital converter (ADC). The sample interval refers to the time between these sample points. Waveform points are the digital values that are stored in memory and displayed to construct the waveform. The time value difference between waveform points is referred to as the waveform interval.

Common horizontal controls include:

- Time Base
- XY
- Scale
- Trace Separation
- Record Length
- Resolution
- Sample Rate
- Trigger Position
- Zoom/Pan
- Search


File
Edit
Vertical
Horiz/Acq
Trig
Display
Cursor
Measure
Mask
Math
MyScope
Analyze
Utilities
Help
Tek
C1 68.0mV Offset:820mV 50Ω
C1 Comm 967mV
250ps 400GS/s ET 2.5ps/pt
Run WfmDB:1000000
325 973 acqs RL:1.0k
February 06, 2006 13:54:20
Horizontal
Acquisition
Acquisition
Acquisition Mode
Sample
Pk Detect
Hi Res
Envelope
Average
WfmDB
Fast Acq
Off
Fast Acq Inhibited
Roll Mode
Auto
Off
Sampling Modes
Real Time
RT
Interpolated
IT
Equivalent
ET
Ext Ref

Figure 21. Example of an acquisition menu.

The sample interval and the waveform interval may, or may not, be the same. This fact leads to the existence of several different acquisition modes in which one waveform point is comprised of several sequentially acquired sample points.

Additionally, waveform points can be created from a composite of sample points taken from multiple acquisitions, which provides another set of acquisition modes. A description of the most commonly used acquisition modes follows.


Sampled point displayed by the DSO
The glitch you will not see

Figure 22. Sample rate varies with time base settings - the slower the time based setting, the slower the sample rate. Some digital oscilloscopes provide peak detect mode to capture fast transients at slow sweep speeds.

Types of Acquisition Modes

- Sample Mode: This is the simplest acquisition mode. The oscilloscope creates a waveform point by saving one sample point during each waveform interval.
- Peak Detect Mode: The oscilloscope saves the minimum and maximum value sample points taken during two waveform intervals and uses these samples as the two corresponding waveform points. Digital oscilloscopes with peak detect mode run the ADC at a fast sample rate, even at very slow time base settings (slow time base settings translate into long waveform intervals) and are able to capture fast signal changes that would occur between the waveform points if in sample mode, as shown in Figure 22. Peak detect mode is particularly useful for seeing narrow pulses spaced far apart in time, as demonstrated in Figure 23.
- Hi-Res Mode: Like peak detect, hi res mode is a way of getting more information in cases when the ADC can sample faster than the time base setting requires. In this case, multiple samples taken within one waveform interval are averaged together to produce one waveform point. The result is a decrease in noise and an improvement in resolution for low-speed signals. The advantage of Hi Res Mode over Average is that Hi-Res Mode can be used even on a single shot event.
- Envelope Mode: Envelope mode is similar to peak detect mode. However, in envelope mode, the minimum and maximum waveform points from multiple acquisitions are combined to form a waveform that shows min/max accumulation over time. Peak detect mode is usually used to acquire the records that are combined to form the envelope waveform.



Figure 23. Peak detect mode enables the oscilloscope to capture extremely brief transient anomalies.

- Average Mode: In average mode, the oscilloscope saves one sample point during each waveform interval as in sample mode. However, waveform points from consecutive acquisitions are then averaged together to produce the final displayed waveform. Average mode reduces noise without loss of bandwidth, but requires a repeating signal.
- Waveform Database Mode: In waveform database mode, the oscillocope accumulates a waveform database that provides a three-dimensional array of amplitude, time, and counts.

Starting and Stopping the Acquisition System

One of the greatest advantages of digital oscilloscopes is their ability to store waveforms for later viewing. To this end, there are usually one or more buttons on the front panel that allow you to start and stop the acquisition system so you can analyze waveforms at your leisure. Additionally, you may want the oscilloscope to automatically stop acquiring after one acquisition is complete or after one set of records has been turned into an envelope or average waveform. This feature is commonly called single sweep or single sequence and its controls are usually found either with the other acquisition controls or with the trigger controls.



Figure 24. Basic sampling, showing sample points are connected by interpolation to produce a continuous waveform.

Sampling

Sampling is the process of converting a portion of an input signal into a number of discrete electrical values for the purpose of storage, processing and/or display. The magnitude of each sampled point is equal to the amplitude of the input signal at the instant in time in which the signal is sampled.

Sampling is like taking snapshots. Each snapshot corresponds to a specific point in time on the waveform. These snapshots can then be arranged in the appropriate order in time so as to reconstruct the input signal.

In a digital oscilloscope, an array of sampled points is reconstructed on a display with the measured amplitude on the vertical axis and time on the horizontal axis, as illustrated in Figure 24.

The input waveform in Figure 24 appears as a series of dots on the screen. If the dots are widely spaced and difficult to interpret as a waveform, the dots can be connected using a process called interpolation. Interpolation connects the dots with lines, or vectors. A number of interpolation methods are available that can be used to produce an accurate representation of a continuous input signal.

Sampling Controls

Some digital oscilloscopes provide you with a choice in sampling method – either real-time sampling or equivalent-time sampling. The acquisition controls available with these oscilloscopes will allow you to select a sample method to acquire signals. Note that this choice makes no difference for slow time base settings and only has an effect when the ADC cannot sample fast enough to fill the record with waveform points in one pass. Each sampling method has distinct advantages, depending on the kind of measurements being made.

Controls are typically available on modern oscilloscopes to give you the choice of three horizontal time base modes of operations. If you are simply doing signal exploration and want to interact with a lively signal, you will use the Automatic or interactive default mode that provides you with the liveliest display update rate. If you want a precise measurement and the highest real-time sample rate that will give you the most measurement accuracy, then the Constant Sample Rate mode is for you. It will maintain the highest sample rate and provide the best real-time resolution. The last mode is called the Manual mode because it ensures direct and independent control of the sample rate and record length.

Real-time Sampling Method

Real-time sampling is ideal for signals whose frequency range is less than half the oscilloscope's maximum sample rate. Here, the oscilloscope can acquire more than enough points in one "sweep" of the waveform to construct an accurate picture, as shown in Figure 25. Real-time sampling is the only way to capture fast, single-shot, transient signals with a digital oscilloscope.



Figure 25. Real-time sampling method.



Figure 26. In order to capture this 10 ns pulse in real-time, the sample rate must be high enough to accurately define the edges.

Real-time sampling presents the greatest challenge for digital oscilloscopes because of the sample rate needed to accurately digitize high-frequency transient events, as shown in Figure 26. These events occur only once, and must be sampled in the same time frame that they occur.

If the sample rate isn't fast enough, high-frequency components can "fold down" into a lower frequency, causing aliasing in the display, as demonstrated in Figure 27. In addition, real-time sampling is further complicated by the high-speed memory required to store the waveform once it is digitized. Please refer to the Sample Rate and Record Length sections under Performance Terms and Considerations for additional detail regarding the sample rate and record length needed to accurately characterize high-frequency components.



C1 200mV/div 50Ω 16.0G

A C1 -20.0mV

40.0ns/div 125MS/s 8.0ns/pt
Stopped
898 acqs RL:50.0
Mon February 04, 2009 11:27:50

	Value	Mean	Min	Max	St Dev	Count	Info
C1 Freq*	10.96MHz	11.007596M	2.965M	62.5M	121.5k	860.0	

Figure 27. Undersampling of a 100 MHz sine wave introduces aliasing effects.

Real-time sampling with interpolation, dgital oscilloscopes take discrete samples of the signal that can be displayed. However, it can be difficult to visualize the signal represented as dots, especially because there can be only a few dots representing high-frequency portions of the signal. To aid in the visualization of signals, digital oscilloscopes typically have interpolation display modes.

In simple terms, interpolation "connects the dots" so that a signal that is sampled only a few times in each cycle can be accurately displayed. Using real-time sampling with interpolation, the oscilloscope collects a few sample points of the signal in a single pass in real-time mode and uses interpolation to fill in the gaps. Interpolation is a processing technique used to estimate what the waveform looks like based on a few points.



Figure 28. Linear and sin x/x interpolation.

Linear interpolation connects sample points with straight lines. This approach is limited to reconstructing straight-edged signals, as illustrated in Figure 28, which better lends itself to square waves.

The more versatile sin x/x interpolation connects sample points with curves, as shown in Figure 28. Sin x/x interpolation is a mathematical process in which points are calculated to fill in the time between the real samples. This form of interpolation lends itself to curved and irregular signal shapes, which are far more common in the real world than pure square waves and pulses. Consequently, sin x/x interpolation is the preferred method for applications where the sample rate is 3 to 5 times the system bandwidth.

Equivalent-time Sampling Method

When measuring high-frequency signals, the oscilloscope may not be able to collect enough samples in one sweep. Equivalent-time sampling can be used to accurately acquire signals whose frequency exceeds half the oscilloscope's sample rate, as illustrated in Figure 29. Equivalent-time digitizers (samplers) take advantage of the fact that most naturally occurring and man-made events are repetitive. Equivalent-time sampling constructs a picture of a repetitive signal by capturing a little bit of information from each repetition. The waveform slowly builds up like a string of lights, illuminating one-by-one. This allows the oscilloscope to accurately capture signals whose frequency components are much higher than the oscilloscope's sample rate.



Figure 29. Some oscilloscopes use equivalent-time sampling to capture and display very fast, repetitive signals.

There are two types of equivalent-time sampling methods: random and sequential. Each has its advantages. Random equivalent-time sampling allows display of the input signal prior to the trigger point, without the use of a delay line. Sequential equivalent-time sampling provides much greater time resolution and accuracy. Both require that the input signal be repetitive.



Figure 30. In random equivalent-time sampling, the sampling clock runs asynchronously with the input signal and the trigger.

Random Equivalent-time Sampling

Random equivalent-time digitizers (samplers) utilize an internal clock that runs asynchronously with respect to the input signal and the signal trigger, as illustrated in Figure 30. Samples are taken continuously, independent of the trigger position, and are displayed based on the time difference between the sample and the trigger. Although samples are taken sequentially in time, they are random with respect to the trigger – hence the name "random" equivalent-time sampling. Sample points appear randomly along the waveform when displayed on the oscilloscope screen.

The ability to acquire and display samples prior to the trigger point is the key advantage of this sampling technique, eliminating the need for external pretrigger signals or delay lines. Depending on the sample rate and the time window of the display, random sampling may also allow more than one sample to be acquired per triggered event. However, at faster sweep speeds, the acquisition window narrows until the digitizer cannot sample on every trigger. It is at these faster sweep speeds that very precise timing measurements are often made, and where the extraordinary time resolution of the sequential equivalent-time sampler is most beneficial. The bandwidth limit for random equivalent-time sampling is less than for sequential-time sampling.



Figure 31. In sequential equivalent-time sampling, the single sample is taken for each recognized trigger after a time delay which is incremented after each cycle.

Sequential Equivalent-time Sampling

The sequential equivalent-time sampler acquires one sample per trigger, independent of the time/div setting, or sweep speed, as illustrated in Figure 31. When a trigger is detected, a sample is taken after a very short, but well-defined, delay. When the next trigger occurs, a small time increment – delta t – is added to this delay and the digitizer takes another sample. This process is repeated many times, with "delta t" added to each previous acquisition, until the time window is filled. Sample points appear from left to right in sequence along the waveform when displayed on the oscilloscope screen.

Technologically speaking, it is easier to generate a very short, very precise "delta t" than it is to accurately measure the vertical and horizontal positions of a sample relative to the trigger point, as required by random samplers. This precisely measured delay is what gives sequential samplers their unmatched time resolution. Since, with sequential sampling, the sample is taken after the trigger level is detected, the trigger point cannot be displayed without an analog delay line, which may, in turn, reduce the bandwidth of the instrument. If an external pretrigger can be supplied, bandwidth will not be affected.

Position and Seconds per Division

The horizontal position control moves the waveform left and right to exactly where you want it on the screen.

The seconds-per-division setting (usually written as sec/div) lets you select the rate at which the waveform is drawn across the screen (also known as the time base setting or sweep speed). This setting is a scale factor. If the setting is 1 ms, each horizontal division represents 1 ms and the total screen width represents 10 ms, or ten divisions. Changing the sec/div setting enables you to look at longer and shorter time intervals of the input signal.

As with the vertical volts/div scale, the horizontal sec/div scale may have variable timing, allowing you to set the horizontal time scale between the discrete settings.

Time Base Selections

Your oscilloscope has a time base, which is usually referred to as the main time base. Many oscilloscopes also have what is called a delayed time base – a time base with a sweep that can start (or be triggered to start) relative to a pre-determined time on the main time base sweep. Using a delayed time base sweep allows you to see events more clearly and to see events that are not visible solely with the main time base sweep.

The delayed time base requires the setting of a time delay and the possible use of delayed trigger modes and other settings not described in this primer. Refer to the manual supplied with your oscilloscope for information on how to use these features.

Zoom/Pan

Your oscilloscope may have special horizontal magnification settings that let you display a magnified section of the waveform on-screen. Some oscilloscopes add pan functions to the zoom capability. Knobs are used to adjust zoom factor or scale and the pan of the zoom box across the waveform.

Search

Some oscilloscopes offer search and mark capabilities, enabling you to quickly navigate through long acquisitions looking for user-defined events.

XY Mode

Most oscilloscopes have an XY mode that lets you display an input signal, rather than the time base, on the horizontal axis. This mode of operation opens up a whole new area of phase shift measurement techniques, explained in the Measurement Techniques section of this primer.

Z Axis

A digital phosphor oscilloscope (DPO) has a high display sample density and an innate ability to capture intensity information. With its intensity axis (Z axis), the DPO is able to provide a three-dimensional, real-time display similar to that of an analog oscilloscope. As you look at the waveform trace on a DPO, you can see brightened areas – the areas where a signal occurs most often. This display makes it easy to distinguish the basic signal shape from a transient that occurs only once in a while – the basic signal would appear much brighter. One application of the Z axis is to feed special timed signals into the separate Z input to create highlighted "marker" dots at known intervals in the waveform.

XYZ Mode with DPO and XYZ Record Display

Some DPOs can use the Z input to create an XY display with intensity grading. In this case, the DPO samples the instantaneous data value at the Z input and uses that value to qualify a specific part of the waveform. Once you have qualified samples, these samples can accumulate, resulting in an intensity-graded XYZ display. XYZ mode is especially useful for displaying the polar patterns commonly used in testing wireless communication devices – a constellation diagram, for example. Another method of displaying XYZ data is XYZ record display. In this mode the data from the acquisition memory is used rather than the DPO database.



Figure 32. Untriggered display.

Trigger System and Controls

An oscilloscope's trigger function synchronizes the horizontal sweep at the correct point of the signal, essential for clear signal characterization. Trigger controls allow you to stabilize repetitive waveforms and capture single-shot waveforms.

The trigger makes repetitive waveforms appear static on the oscilloscope display by repeatedly displaying the same portion of the input signal. Imagine the jumble on the screen that would result if each sweep started at a different place on the signal, as illustrated in Figure 32.

Edge triggering, available in analog and digital oscilloscopes, is the basic and most common type. In addition to threshold triggering offered by both analog and digital oscilloscopes, many digital oscilloscopes offer numerous specialized trigger settings not offered by analog instruments. These triggers respond to specific conditions in the incoming signal, making it easy to detect, for example, a pulse that is narrower than it should be. Such a condition would be impossible to detect with a voltage threshold trigger alone.

Advanced trigger controls enable you to isolate specific events of interest to optimize the oscilloscope's sample rate and record length. Advanced triggering capabilities in some oscilloscopes give you highly selective control. You can trigger on pulses defined by amplitude (such as runt pulses), qualified by time (pulse width, glitch, slew rate, setup-and-hold, and time-out), and delineated by logic state or pattern (logic triggering).

Other advanced trigger functions include:

- **Pattern Lock Triggering:** Pattern lock triggering adds a new dimension to NRZ serial pattern triggering by enabling the oscilloscope to take synchronized acquisitions of a long serial test pattern with outstanding time base accuracy. Pattern lock triggering can be used to remove random jitter from long serial data patterns. Effects of specific bit transitions can be investigated, and averaging can be used with mask testing.
- **Serial Pattern Triggering:** Serial pattern triggering can be used to debug serial architectures. It provides a trigger on the serial pattern of an NRZ serial data stream with built-in clock recovery and correlates events across the physical and link layer. The instrument can recover the clock signal, identify transitions, and allow you to set the desired encoded words for the serial pattern trigger to capture.
- **A & B Triggering:** Some trigger systems offer multiple trigger types only on a single event (A event), with delayed trigger (B event) selection limited to edge type triggering and often do not provide a way to reset the trigger sequence if the B event doesn't occur. Modern oscilloscopes can provide the full suite of advanced trigger types on both A and B triggers, logic qualification to control when to look for these events, and reset triggering to begin the trigger sequence again after a specified time, state, or transition so that even events in the most complex signals can be captured.
- **Search & Mark Triggering:** Hardware triggers watch for one event type at a time, but Search can scan for multiple event types simultaneously. For example, scan for setup or hold time violations on multiple channels. Individual marks can be placed by Search indicating events that meet search criteria.
- **Trigger Correction:** Since the trigger and data acquisition systems share different paths there is some inherent time delay between the trigger position and the data acquired. This results in skew and trigger jitter. With a trigger correction system the instrument adjusts the trigger position and compensates for the difference of delay there is between the trigger path and the data acquisition path. This will eliminate virtually any trigger jitter at the trigger point. In this mode, the trigger point can be used as a measurement reference.



Slew Rate Triggering. High frequency signals with slew rates faster than expected or needed can radiate troublesome energy. Slew rate triggering surpasses conventional edge triggering by adding the element of time and allowing you to selectively trigger on fast or slow edges.



Runt Pulse Triggering. Runt triggering allows you to capture and examine pulses that cross one logic threshold, but not both.



Glitch Triggering. Glitch triggering allows you to trigger on digital pulses when they are shorter or longer than a user-defined time limit. This trigger control enables you to examine the causes of even rare glitches and their effects on other signals



Logic Triggering. Logic triggering allows you to trigger on any logical combination of available input channels – especially useful in verifying the operation of digital logic.



Pulse Width Triggering. Using pulse width triggering, you can monitor a signal indefinitely and trigger on the first occurrence of a pulse whose duration (pulse width) is outside the allowable limits.



Setup-and-Hold Triggering. Only setup-and-hold triggering lets you deterministically trap a single violation of setup-and-hold time that would almost certainly be missed by using other trigger modes. This trigger mode makes it easy to capture specific signal quality and timing details when a synchronous data signal fails to meet setup-and-hold specifications.



Time-out Triggering. Time-out triggering lets you trigger on an event without waiting for the trigger pulse to end, by triggering based on a specified time lapse.



Communication Triggering. Optionally available on certain oscilloscope models, these trigger modes address the need to acquire a wide variety of Alternate-Mark Inversion (AMI), Code-Mark Inversion (CMI), and Non-Return to Zero (NRZ) communication signals.

Figure 33. Common trigger types.

- **Serial Triggering on Specific Standard Signals I²C, CAN, LIN, etc.)** - Some oscilloscopes provide the ability to trigger on specific signal types for standard serial data signals such as CAN, LIN, I²C, SPI, and others. The decode of these signal types is also available on many oscilloscopes today.
- **Parallel Bus Triggering** - Multiple parallel buses can be defined and displayed at one time to easily view decoded parallel bus data over time. By specifying which channels are the clock and data lines, you can create a parallel bus display on some oscilloscopes that automatically decodes bus content. Countless hours can be saved by using parallel bus triggers to simplify capture and analysis.

Optional trigger controls in some oscilloscopes are designed specifically to examine communications signals as well. Figure 33 highlights a few of these common trigger types in more detail. The intuitive user interface available in some oscilloscopes also allows rapid setup of trigger parameters with wide flexibility in the test setup to maximize your productivity.

Trigger Position

Horizontal trigger position control is only available on digital oscilloscopes. The trigger position control may be located in the horizontal control section of your oscilloscope. It actually represents the horizontal position of the trigger in the waveform record.

Varying the horizontal trigger position allows you to capture what a signal did before a trigger event, known as pre-trigger viewing. Thus, it determines the length of viewable signal both preceding and following a trigger point.

Digital oscilloscopes can provide pre-trigger viewing because they constantly process the input signal, whether or not a trigger has been received. A steady stream of data flows through the oscilloscope; the trigger merely tells the oscilloscope to save the present data in memory.
In contrast, analog oscilloscopes only display the signal – that is, write it on the CRT – after receiving the trigger. Thus, pre-trigger viewing is not available in analog oscilloscopes, with the exception of a small amount of pre-trigger provided by a delay line in the vertical system.

Pre-trigger viewing is a valuable troubleshooting aid. If a problem occurs intermittently, you can trigger on the problem, record the events that led up to it and, possibly, find the cause.

Trigger Level and Slope

The trigger level and slope controls provide the basic trigger point definition and determine how a waveform is displayed, as illustrated in Figure 34.

The trigger circuit acts as a comparator. You select the slope and voltage level on one input of the comparator. When the trigger signal on the other comparator input matches your settings, the oscilloscope generates a trigger.

The slope control determines whether the trigger point is on the rising or the falling edge of a signal. A rising edge is a positive slope and a falling edge is a negative slope. The level control determines where on the edge the trigger point occurs.


Triggering on the Negative Slope with the Level Set to 3 V
Positive Slope
Negative Slope
Zero Volts
Input Signal
3 V
Triggering on the Positive Slope with the Level Set to 3 V
3 V

Figure 34. Positive and negative slope triggering.

Trigger Sources

The oscilloscope does not necessarily need to trigger on the signal being displayed. Several sources can trigger the sweep:

- Any input channel
- An external source other than the signal applied to an input channel
- The power source signal
- A signal internally defined by the oscilloscope, from one or more input channels

Most of the time, you can leave the oscilloscope set to trigger on the channel displayed. Some oscilloscopes provide a trigger output that delivers the trigger signal to another instrument.

The oscilloscope can use an alternate trigger source, whether or not it is displayed, so you should be careful not to unwittingly trigger on channel 1 while displaying channel 2, for example.



Figure 35. Trigger holdoff.

Trigger Modes

The trigger mode determines whether or not the oscilloscope draws a waveform based on a signal condition. Common trigger modes include normal and auto.

In normal mode the oscilloscope only sweeps if the input signal reaches the set trigger point; otherwise (on an analog oscilloscope) the screen is blank or (on a digital oscilloscope) frozen on the last acquired waveform. Normal mode can be disorienting since you may not see the signal at first if the level control is not adjusted correctly.

Auto mode causes the oscilloscope to sweep, even without a trigger. If no signal is present, a timer in the oscilloscope triggers the sweep. This ensures that the display will not disappear if the signal does not cause a trigger.

In practice, you will probably use both modes: normal mode because it lets you see just the signal of interest, even when triggers occur at a slow rate, and auto mode because it requires less adjustment.

Many oscilloscopes also include special modes for single sweeps, triggering on video signals, or automatically setting the trigger level.

Trigger Coupling

Just as you can select either AC or DC coupling for the vertical system, you can choose the kind of coupling for the trigger signal.

Besides AC and DC coupling, your oscilloscope may also have high frequency rejection, low frequency rejection, and noise rejection trigger coupling. These special settings are useful for eliminating noise from the trigger signal to prevent false triggering.

Trigger Holdoff

Sometimes getting an oscilloscope to trigger on the correct part of a signal requires great skill. Many oscilloscopes have special features to make this task easier.

Trigger holdoff is an adjustable period of time after a valid trigger during which the oscilloscope cannot trigger. This feature is useful when you are triggering on complex waveform shapes, so that the oscilloscope only triggers on an eligible trigger point. Figure 35 shows how using trigger holdoff helps create a usable display.



Figure 36. An oscilloscope graticule.



Figure 37. Adding channels.

Display System and Controls

An oscilloscope's front panel includes a display screen and the knobs, buttons, switches, and indicators used to control signal acquisition and display. As mentioned at the front of this section, front-panel controls are usually divided into vertical, horizontal and trigger sections. The front panel also includes input connectors.

Take a look at the oscilloscope display. Notice the grid markings on the screen – these markings create the graticule. Each vertical and horizontal line constitutes a major division. The graticule is usually laid out in an 8-by-10 or 10-by-10 division pattern. Labeling on the oscilloscope controls (such as volts/div and sec/div) always refers to major divisions. The tick marks on the center horizontal and vertical graticule lines, as shown in Figure 36, are called minor divisions. Many oscilloscopes display on the screen how many volts each vertical division represents and how many seconds each horizontal division represents.

Other Oscilloscope Controls

Math and Measurement Operations

Your oscilloscope may also have operations that allow you to add waveforms together, creating a new waveform display. Analog oscilloscopes combine the signals while digital oscilloscopes create new waveforms mathematically. Subtracting waveforms is another math operation. Subtraction with analog oscilloscopes is possible by using the channel invert function on one signal and then using the add operation. Digital oscilloscopes typically have a subtraction operation available. Figure 37 illustrates a third waveform created by combining two different signals.

Using the power of their internal processors, digital oscilloscopes offer many advanced math operations: multiplication, division, integration, Fast Fourier Transform, and more. This advanced signal processing capability can also perform functions such as the insertion of a filter block which can be used de-embed the characteristics of the fixture on the device under test or implement a filter block with desired frequency response such as a low pass filter. The processing block is flexible – not dedicated; it can perform as an arbitrary filter instead, for example for simulation of pre-emphasis/de-emphasis schemes.

Digital Timing and State Acquisitions

Digital channels provided by a mixed signal oscilloscope enable acquisition capabilities similar to those found on logic analyzers. There are two major digital acquisition techniques. The first technique is timing acquisition in which the MSO samples the digital signal at uniformly spaced times determined by the MSO's sample rate. At each sample point, the MSO stores the signal's logic state and creates a timing diagram of the signal. The second digital acquisition technique is state acquisition. State acquisition defines special times that the digital signal's logic state is valid and stable. This is common in synchronous and clocked digital circuits. A clock signal defines the time when the signal state is valid. For example, the input signal stable time is around the rising clock edge for a D-Flip-Flop with rising edge clocking. The output signal stable time is around the falling clock edge for a D-Flip-Flop with rising edge clocking. Since the clock period of a synchronous circuit may not be fixed, the time between state acquisitions may not be uniform as it is in a timing acquisition.

A mixed signal oscilloscope's digital channels acquire signals similar to how a logic analyzer acquires signals in timing acquisition mode. The MSO then decodes the timing acquisition into a clocked bus display, and event table which is similar to the logic analyzer's state acquisition display, providing you with important information during debug.

We have described the basic oscilloscope controls that a beginner needs to know about. Your oscilloscope may have other controls for various functions. Some of these may include:

- Automatic parametric measurements
- Measurement cursors
- Keypads for mathematical operations or data entry
- Printing capabilities
- Interfaces for connecting your oscilloscope to a computer or directly to the Internet

Look over the other options available to you and read your oscilloscope’s manual to find out more about these other controls.

The Complete Measurement System

Probes

Even the most advanced instrument can only be as precise as the data that goes into it. A probe functions in conjunction with an oscilloscope as part of the measurement system. Precision measurements start at the probe tip. The right probes matched to the oscilloscope and the device-under-test (DUT) not only allow the signal to be brought to the oscilloscope cleanly, they also amplify and preserve the signal for the greatest signal integrity and measurement accuracy.



Figure 38. Dense devices and systems require small form factor probes.

To ensure accurate reconstruction of your signal, try to choose a probe that, when paired with your oscilloscope, exceeds the signal bandwidth by 5 times.

Probes actually become part of the circuit, introducing resistive, capacitive and inductive loading that inevitably alters the measurement. For the most accurate results, the goal is to select a probe with minimal loading. An ideal pairing of the probe with the oscilloscope will minimize this loading, and enable you to access all of the power, features and capabilities of your oscilloscope.

Another connectivity consideration is the probe’s form factor. Small form factor probes provide easier access to today’s densely packed circuitry, as shown in Figure 38.

A brief description of the types of probes follows. Please refer to the Tektronix ABCs of Probes primer for more information about this essential component of the overall measurement system.



Figure 39. A typical passive probe with accessories.

Passive Probes

For measuring typical signal and voltage levels, passive probes provide ease-of-use and a wide range of measurement capabilities at an affordable price. The pairing of a passive voltage probe with a current probe will provide you with an ideal solution for measuring power.

Most passive probes have some attenuation factor, such as 10X, 100X, and so on. By convention, attenuation factors, such as for the 10X attenuator probe, have the X after the factor. In contrast, magnification factors like X10 have the X first.

The 10X (read as “ten times”) attenuator probe reduces circuit loading in comparison to a 1X probe and is an excellent general-purpose passive probe. Circuit loading becomes more pronounced for higher frequency and/or higher impedance signal sources, so be sure to analyze these signal/probe loading interactions before selecting a probe. The 10X attenuator probe improves the accuracy of your measurements, but also reduces the signal’s amplitude at the oscilloscope input by a factor of 10.

Because it attenuates the signal, the 10X attenuator probe makes it difficult to look at signals less than 10 millivolts peak-to-peak. The 1X probe is similar to the 10X attenuator probe but lacks the attenuation circuitry. Without this circuitry, more interference is introduced to the circuit being tested.

Use the 10X attenuator probe as your general-purpose probe, but keep the 1X probe accessible to measure slow-speed, low-amplitude signals. Some probes have a convenient feature for switching between 1X and 10X attenuation at the probe tip. If your probe has this feature, make sure you are using the correct setting before taking measurements.

Many oscilloscopes can automatically detect whether you are using a 1X or 10X probe and adjust their screen readouts accordingly. However with some oscilloscopes, you must set the type of probe you are using or read from the proper 1X or 10X marking on the volts/div control.

The 10X attenuator probe works by balancing the probe’s electrical properties against the oscilloscope’s electrical properties. Before using a 10X attenuator probe you need to adjust this balance for your particular oscilloscope. This adjustment is known as compensating the probe and is described in more detail in the Operating the Oscilloscope section of this primer.

Passive probes, such as the one shown in Figure 39, provide excellent general-purpose probing solutions. However, general-purpose passive probes cannot accurately measure signals with extremely fast rise times, and may excessively load sensitive circuits. The steady increase in signal clock rates and edge speeds demands higher speed probes with less loading effects. High-speed active and differential probes provide ideal solutions when measuring high-speed and/or differential signals.



Figure 40. High-performance probes are critical when measuring the fast clocks and edges found in today's computer buses and data transmission lines.


File
Edit
Vertical
Horiz/Acq
Trig
Display
Cursors
Measure
Mask
Math
MyScope
Analyze
Utilities
Help
Tek
C1 400mV/div 50Ω B_W:16.0G
C2 400mV/div 50Ω B_W:16.0G
C3 400mV/div 50Ω B_W:16.0G
A C1 424mV
10.0ns/div 50.0GS/s 20.0ps/pt
Run Sample
359 acqs RL:5.0k
Auto February 04, 2009 12:20:31

Figure 41 Differential probes can separate common-mode noise from the signal content of interest in today's fast, low-voltage applications - especially important as digital signals continue to fall below typical noise thresholds found in integrated circuits.

Active and Differential Probes

Increasing signal speeds and lower-voltage logic families make accurate measurement results difficult to achieve. Signal fidelity and device loading are critical issues. A complete measurement solution at these high speeds includes high-speed, high-fidelity probing solutions to match the performance of the oscilloscope, as shown in Figure 40.

Active and differential probes use specially developed integrated circuits to preserve the signal during access and transmission to the oscilloscope, ensuring signal integrity. For measuring signals with fast rise times, a high-speed active or differential probe will provide more accurate results, as highlighted in Figure 41.

Newer probe types provide the advantage of being able to use one setup, and get three types of measurements without adjusting probe tip connections. These probes can make differential, single-ended and common mode measurements from the same probe setup.

Logic Probes



Figure 42. Logic probes for a mixed signal oscilloscope (MSO) simplify digital connectivity to your device.

The logic probe shown in Figure 42 offers two eight-channel pods. Each channel ends with a probe tip featuring a recessed ground for simplified connection to the device-under-test. The coax on the first channel of each pod is colored blue making it easy to identify. The common ground uses an automotive style connector making it easy to create custom grounds for connecting to the device-under-test. When connecting to square pins, you can use an adapter that attaches to the probe head extending the probe ground flush with the probe tip so you can attach to a header. These probes offer outstanding electrical characteristics with minimal capacitive loading.

Specialty Probes

In addition to the previously mentioned probe types, there are also a variety of other specialty probes and probing systems. These include current, high-voltage, and optical probes, just to name a few.

Probe Accessories

Many modern oscilloscopes provide special automated features built into the input and mating probe connectors. In the case of intelligent probe interfaces, the act of connecting the probe to the instrument notifies the oscilloscope about the probe's attenuation factor, which in turn scales the display so that the probe's attenuation is figured into the readout on the screen. Some probe interfaces also recognize the type of probe – that is, passive, active or current. The interface may act as a DC power source for probes. Active probes have their own amplifier and buffer circuitry that requires DC power.

Ground lead and probe tip accessories are also available to improve signal integrity when measuring high-speed signals. Ground lead adapters provide spacing flexibility between probe tip and ground lead connections to the DUT, while maintaining very short lead lengths from probe tip to DUT.

Please refer to the Tektronix ABCs of Probes primer for more information about probes and probe accessories.

Performance Terms and Considerations

As previously mentioned, an oscilloscope is analogous to a camera that captures signal images that we can observe and interpret. Shutter speed, lighting conditions, aperture and the ASA rating of the film all affect the camera's ability to capture an image clearly and accurately.

Like the basic systems of an oscilloscope, the performance considerations of an oscilloscope significantly affect its ability to achieve the required signal integrity.



Figure 43. Oscilloscope bandwidth is the frequency at which a sinusoidal input signal is attenuated to 70.7% of the signal's true amplitude, known as the -3 dB point.

Learning a new skill often involves learning a new vocabulary. This idea holds true for learning how to use an oscilloscope. This section describes some useful measurement and oscilloscope performance terms. These terms are used to describe the criteria essential to choosing the right oscilloscope for your application. Understanding these terms will help you to evaluate and compare your oscilloscope with other models.

Bandwidth

Bandwidth determines an oscilloscope's fundamental ability to measure a signal. As signal frequency increases, the capability of the oscilloscope to accurately display the signal decreases. This specification indicates the frequency range that the oscilloscope can accurately measure.

Oscilloscope bandwidth is specified as the frequency at which a sinusoidal input signal is attenuated to 70.7% of the signal's true amplitude, known as the –3 dB point, a term based on a logarithmic scale, as seen in Figure 43.

Without adequate bandwidth, your oscilloscope will not be able to resolve high-frequency changes. Amplitude will be distorted. Edges will vanish. Details will be lost. Without adequate bandwidth, all the features, bells and whistles in your oscilloscope will mean nothing.

To determine the oscilloscope bandwidth needed to accurately characterize signal amplitude in your specific application, apply the "5 Times Rule."

$$\text{Oscilloscope Bandwidth} \geq \begin{array}{c}\text{Highest Frequency}\\ \text{Component of Signal}\end{array} x \;\, 5$$


File Edit Vertical Horiz/Acq Trig Display Cursors Measure Mask Math MyScope Analyze Utilities Help
Tek
4GHz
2GHz
500MHz
R1 100mV 1.0ns
R2 100mV 1.0ns
R3 100mV 1.0ns
C1 0.0V
4.0ns/div 25.0GS/s 40.0ps/pt
Preview Sample
0 acqs RL:1.0k
Auto February 04, 2009 09:15:09

Figure 44. The higher the bandwidth, the more accurate the reproduction of your signal, as illustrated with a signal captured at 250 MHz, 1 GHz and 4 GHz bandwidth levels.

An oscilloscope selected using the 5 Times Rule will give you less than ±2% error in your measurements – typically sufficient for today's applications. However, as signal speeds increase, it may not be possible to achieve this rule of thumb. Always keep in mind that higher bandwidth will likely provide more accurate reproduction of your signal, as demonstrated in Figure 44.

Some oscilloscopes provide a method of enhancing the bandwidth through digital signal processing. A DSP arbitrary equalization filter can be used to improve the oscilloscope channel response. This filter extends the bandwidth, flattens the oscilloscope's channel frequency response, improves phase linearity, and provides a better match between channels. It also decreases rise time and improves the time-domain step response.

Rise Time

In the digital world, rise time measurements are critical. Rise time may be a more appropriate performance consideration when you expect to measure digital signals, such as pulses and steps. As shown in Figure 45, your oscilloscope must have sufficient rise time to accurately capture the details of rapid transitions.


File Edit Vertical Horiz/Acq Trig Display Cursors Measure Mask Math MyScope Analyze Utilities Help
Tek
C1 60.0mV/div 50Ω BW:8.0G
Z1C1 60.0mV 200ps -1000ps 1.0ns
C1 0.0V
10.0ns/div 25.0GS/s IT 200fs/pt
Preview Single Seq
0 acqs RL:500k
Auto February 04, 2009 09:28:07

Figure 45. Rise time characterization of a high-speed digital signal.

Rise time describes the useful frequency range of an oscilloscope. To calculate the oscilloscope rise time required for your signal type, use the following equation:

$$\text{Oscilloscope Rise Time} \leq \text{Fastest Rise Time of Signal} \; x \; \frac{1}{5}$$

Note that this basis for oscilloscope rise time selection is similar to that for bandwidth. As in the case of bandwidth, achieving this rule of thumb may not always be possible given the extreme speeds of today's signals. Always remember that an oscilloscope with faster rise time will more accurately capture the critical details of fast transitions.

In some applications, you may know only the rise time of a signal. A constant allows you to relate the bandwidth and rise time of the oscilloscope, using the equation:

$$\text{Bandwidth} = \frac{k}{\text{Rise Time}}$$

where k is a value between 0.35 and 0.45, depending on the shape of the oscilloscope's frequency response curve and pulse rise time response. Oscilloscopes with a bandwidth of <1 GHz typically have a 0.35 value, while oscilloscopes with a bandwidth of > 1 GHz usually have a value between 0.40 and 0.45.

Logic Family	Typical Signal Rise Time	Calculated Signal Bandwidth
TTL	2 ns	175 MHz
CMOS	1.5 ns	230 MHz
GTL	1 ns	350 MHz
LVDS	400 ps	875 MHz
ECL	100 ps	3.5 GHz
GaAs	40 ps	8.75 GHz

Figure 46. Some logic families produce inherently faster rise times than others.

Some logic families produce inherently faster rise times than others, as illustrated in Figure 46.

Sample Rate

Sample rate – specified in samples per second (S/s) – refers to how frequently a digital oscilloscope takes a snapshot or sample of the signal, analogous to the frames on a movie camera. The faster an oscilloscope samples (i.e., the higher the sample rate), the greater the resolution and detail of the displayed waveform and the less likely that critical information or events will be lost, as shown in Figure 47. The minimum sample rate may also be important if you need to look at slowly changing signals over longer periods of time. Typically, the displayed sample rate changes with changes made to the horizontal scale control to maintain a constant number of waveform points in the displayed waveform record.

How do you calculate your sample rate requirements? The method differs based on the type of waveform you are measuring, and the method of signal reconstruction used by the oscilloscope.



Figure 47. A higher sample rate provides greater signal resolution, ensuring that you'll see intermittent events.

In order to accurately reconstruct a signal and avoid aliasing, the Nyquist theorem states that the signal must be sampled at least twice as fast as its highest frequency component. This theorem, however, assumes an infinite record length and a continuous signal. Since no oscilloscope offers infinite record length and, by definition, glitches are not continuous, sampling at only twice the rate of highest frequency component is usually insufficient.

In reality, accurate reconstruction of a signal depends on both the sample rate and the interpolation method used to fill in the spaces between the samples. Some oscilloscopes let you select either sin (x)/x interpolation for measuring sinusoidal signals, or linear interpolation for square waves, pulses and other signal types.

> For accurate reconstruction using sin(x)/x interpolation, your oscilloscope should have a sample rate at least 2.5 times the highest frequency component of your signal. Using linear interpolation, the sample rate should be at least 10 times the highest frequency signal component.

Some measurement systems with sample rates to 50 GS/s and bandwidths to 20 GHz have been optimized for capturing very fast, single-shot and transient events by oversampling up to 5 times the bandwidth.


File | Edit | Vertical | Horiz/Acq | Trig | Display | Cursors | Measure | Mask | Math | MyScope | Analyze | Utilities | Help
Tek
A Event
A->B Seq
B Event
Mode
Select
Edit
Data Level
R Clk

C1 200mV/div 50Ω B_W:8.0G
C2 200mV/div 50Ω B_W:8.0G
A C1 Serial
1.0ns/div 25.0GS/s IT 2.0ps/pt
Run Sample
308 acqs RL:5.0k
Auto February 04, 2009 12:27:01

Trigger - Serial Pattern A:Serial → Acquire
Trigger Type: Serial
Clk Src: R Clk
Data Src: Ch 1
Standard: SATA 3.0G
Coding: S8b10b
Bit Rate: 3.0Gb/s
Data Level: -146mV
Trigger On: Pattern
Settings: Shared
0011111010
Format: Binary

Figure 48. A DPO provides an ideal solution for non-repetitive, high-speed, multi-channel digital design applications.


File | Edit | Vertical | Horiz/Acq | Trig | Display | Cursor | Measure | Mask | Math | MyScope | Analyze | Utilities | Help
Tek

Intensity:99.99%
C1 1.0V/div
C1 2.48V
200ns 500MS/s 2.0ns/pt
FastAcq Sample
30 019 465 acqs RL:1.0k
December 09, 2005 11:09:33

Figure 49. A DPO enables a superior level of insight into signal behavior by delivering vastly greater waveform capture rates and three-dimensional display, making it the best general-purpose design and troubleshooting tool for a wide range of applications.

Waveform Capture Rate

All oscilloscopes blink. That is, they open their eyes a given number of times per second to capture the signal, and close their eyes in between. This is the waveform capture rate, expressed as waveforms per second (wfms/s). While the sample rate indicates how frequently the oscilloscope samples the input signal within one waveform, or cycle, the waveform capture rate refers to how quickly an oscilloscope acquires waveforms.

Waveform capture rates vary greatly, depending on the type and performance level of the oscilloscope. Oscilloscopes with high waveform capture rates provide significantly more visual insight into signal behavior, and dramatically increase the probability that the oscilloscope will quickly capture transient anomalies such as jitter, runt pulses, glitches and transition errors.

Digital storage oscilloscopes (DSOs) employ a serial-processing architecture to capture from 10 to 5,000 wfms/s. Some DSOs provide a special mode that bursts multiple captures into long memory, temporarily delivering higher waveform capture rates followed by long processing dead times that reduce the probability of capturing rare, intermittent events.

Most digital phosphor oscilloscopes (DPOs) employ a parallel-processing architecture to deliver vastly greater waveform capture rates. As seen in Figure 48, some DPOs can acquire millions of waveforms in just seconds, significantly increasing the probability of capturing intermittent and elusive events and allowing you to see the problems in your signal more quickly. Moreover, the DPO's ability to acquire and display three dimensions of signal behavior in real time – amplitude, time and distribution of amplitude over time – results in a superior level of insight into signal behavior, as shown in Figure 49.

Record Length

Record length, expressed as the number of points that comprise a complete waveform record, determines the amount of data that can be captured with each channel. Since an oscilloscope can store only a limited number of samples, the waveform duration (time) will be inversely proportional to the oscilloscope's sample rate.

$$\text{Time Interval} = \frac{\text{Record Length}}{\text{Sample Rate}}$$

Modern oscilloscopes allow you to select record length to optimize the level of detail needed for your application. If you are analyzing an extremely stable sinusoidal signal, you may need only a 500 point record length, but if you are isolating the causes of timing anomalies in a complex digital data stream, you may need a million points or more for a given record length, as demonstrated in Figure 50.

Triggering Capabilities

An oscilloscope's trigger function synchronizes the horizontal sweep at the correct point of the signal, essential for clear signal characterization. Trigger controls allow you to stabilize repetitive waveforms and capture single-shot waveforms.

Please refer to the Trigger section under Performance Terms and Considerations for more information regarding triggering capabilities.

Effective Bits

Effective bits represent a measure of a digital oscilloscope's ability to accurately reconstruct a sinewave signal's shape. This measurement compares the oscilloscope's actual error to that of a theoretical "ideal" digitizer. Because the actual errors include noise and distortion, the frequency and amplitude of the signal must be specified.

Frequency Response

Bandwidth alone is not enough to ensure that an oscilloscope can accurately capture a high frequency signal. The goal of oscilloscope design is a specific type of frequency response: Maximally Flat Envelope Delay (MFED). A frequency response of this type delivers excellent pulse fidelity with minimum overshoot and ringing. Since a digital oscilloscope is composed of real amplifiers, attenuators, ADCs, interconnects, and relays, MFED response is a goal that can only be approached. Pulse fidelity varies considerably with model and manufacturer.

Vertical Sensitivity

Vertical sensitivity indicates how much the vertical amplifier can amplify a weak signal – usually measured in millivolts (mV) per division. The smallest voltage detected by a general-purpose oscilloscope is typically about 1 mV per vertical screen division.



Position 54.0%

Scale 5000

Duration 1.0ms

Sample Rate 10.0GS/s

Resolution 100.0ps

Rec Length 10000000

Figure 50. Capturing the high frequency detail of this modulated 85 MHz carrier requires high resolution sampling (100 ps). Seeing the signal's complete modulation envelope requires a long time duration (1 ms). Using long record length (10 MB), the oscilloscope can display both.

Sweep Speed

Sweep speed indicates how fast the trace can sweep across the oscilloscope screen, enabling you to see fine details. The sweep speed of an oscilloscope is represented by time (seconds) per division.

Gain Accuracy

Gain accuracy indicates how accurately the vertical system attenuates or amplifies a signal, usually represented as a percentage error.

Horizontal Accuracy (Time Base)

Horizontal, or time base, accuracy indicates how accurately the horizontal system displays the timing of a signal, usually represented as a percentage error.

Vertical Resolution (Analog-to-Digital Converter)

Vertical resolution of the ADC, and therefore, the digital oscilloscope, indicates how precisely it can convert input voltages into digital values. Vertical resolution is measured in bits. Calculation techniques can improve the effective resolution, as exemplified with hi-res acquisition mode.



	Value	Mean	Min	Max	Std Dev
D0 +Width	1.091ns	1.152n	909.1p	1.636n	264.9p

Figure 51. The MSO provides 16 integrated digital channels, enabling the ability to view and analyze time-correlated analog and digital signals. A high speed timing acquisition provides more resolution to reveal narrow events such as glitches.

Timing Resolution (MSO)

An important MSO acquisition specification is the timing resolution used for capturing digital signals. Acquiring a signal with better timing resolution provides a more accurate timing measurement of when the signal changes. For example, a 500 MS/s acquisition rate has 2 ns timing resolution and the acquired signal edge uncertainty is 2 ns. A smaller timing resolution of 60.6 ps (16.5 GS/s) decreases the signal edge uncertainty to 60.6 ps and captures faster changing signals.

Some MSOs internally acquire digital signals with two types of acquisitions at the same time. The first acquisition is with standard timing resolution, and the second acquisition uses a high speed resolution. The standard resolution is used over a longer record length while the high speed timing acquisition offers more resolution around a narrow point of interest, as shown in Figure 51.

Connectivity

The need to analyze measurement results remains of utmost importance. The need to document and share information and measurement results easily and frequently has also grown in importance. The connectivity of an oscilloscope delivers advanced analysis capabilities and simplifies the documentation and sharing of results. As shown in Figure 52, standard interfaces (GPIB, RS-232, USB, Ethernet) and network communication modules enable some oscilloscopes to deliver a vast array of functionality and control.



Figure 52. Today's oscilloscopes provide a wide array of communications interfaces, such as a standard Centronics port and optional Ethernet/RS-232, GPIB/RS-232, and VGA/RS-232 modules. There is even a USB port (not shown) on the front panel.



Description	Mean	Std Dev	Max	Min	p-p	Population	Max-cc	Min-cc
Width1, Math4, Mat...	153.54ps	0.0000s	153.54ps	153.54ps	0.0000s	1	0.0000s	0.0000s
Height1, Math4, Ma...	162.44mV	0.0000V	162.44mV	162.44mV	0.0000V	1	0.0000V	0.0000V
Height2, Math4, Ma...	597.20mV	0.0000V	597.20mV	597.20mV	0.0000V	1	0.0000V	0.0000V
Width@BER1, Math...	146.49ps	0.0000s	146.49ps	146.49ps	0.0000s	1	0.0000s	0.0000s
Period1, Math4	200.49ps	3.1675ps	216.23ps	187.22ps	29.008ps	997576	26.240ps	-22.564ps
Freq1, Math4	4.9891GHz	78.381MHz	5.3413GHz	4.6247GHz	716.55MHz	997576	555.94MHz	-649.32MHz
TIE1, Math4, Math3	57.582ps	4.8895ps	78.376ps	31.428ps	46.949ps	639056	15.257ps	-12.978ps
RJ-δδ1, Math4, Ma...	3.2652ps	0.0000s	3.2652ps	3.2652ps	0.0000s	1	0.0000s	0.0000s
DJ-δδ1, Math4, Ma...	14.339ps	0.0000s	14.339ps	14.339ps	0.0000s	1	0.0000s	0.0000s
Rise Time1, Math4, ...	161.80ps	3.8452ps	177.95ps	149.81ps	28.147ps	22063	18.555ps	-19.978ps

Figure 53. Analysis software packages are specifically designed to meet jitter and eye measurement needs of today's high-speed digital designers.

Some advanced oscilloscopes also let you:

- Create, edit and share documents on the oscilloscope – all while working with the instrument in your particular environment
- Access network printing and file sharing resources
- Access the Windows® desktop
- Run third-party analysis and documentation software
- Link to networks
- Access the Internet
- Send and receive e-mail

Expandability

An oscilloscope should be able to accommodate your needs as they change. Some oscilloscopes allow you to:


Stop
I2C
[W]: 00
[R]: 50
D: 2E
D: 30
D: 32
D: 34
100µs
0.00000 s
10.0MS/s
10k points
2.00 V
2.00 V
D15–D0
Timing Resolution: 100ns
Address/Data
Type Bus
Source Bus B1 (I2C)
Trigger On Address/Data
Address 50h
Data 2Eh
Direction Read
Mode Normal & Holdoff

Figure 54. Serial bus analysis is accelerated with automated trigger, decode, and search on serial packet context.


Stop
CLOCK
COUNT6
COUNT5
COUNT4
COUNT3
COUNT2
COUNT1
COUNT0
Parallel
00
01
02
03
04
05
06
07
08
200ns
0.00000 s
5.00GS/s
1M points
2.00 V
D15–D0
Timing Resolution: 2.00ns
Data
Type Bus
Source Bus B1 (Parallel)
Data 04
Mode Auto & Holdoff

Figure 55. Automatically trigger, decode, and search on clocked or unclocked parallel bus data.

- Add memory to channels to analyze longer record lengths
- Add application-specific measurement capabilities
- Complement the power of the oscilloscope with a full range of probes and modules
- Work with popular third-party analysis and productivity Windows-compatible software
- Add accessories, such as battery packs and rackmounts

Application modules and software may enable you to transform your oscilloscope into a highly specialized analysis tool capable of performing functions such as jitter and timing analysis, microprocessor memory system verification, communications standards testing, disk drive measurements, video measurements, power measurements and much more. Figures 53 - 58 highlight a few of these examples.


File
Edit
Vertical
Horiz/Acq
Trig
Display
Cursors
Measure
Mask
Math
MyScope
Analyze
Utilities
Help
Tek
DDR Analysis
Setup
Results
Plots
Reports
Generation, Rate and Levels
Measurements
Sources
Burst Detection
Thresholds and Scaling
Detect Levels
Auto
Manual
Strobe
High
Mid
Low
Bursts Table
Advanced
Data
Clear
Recalc
Single
Run
Show Plots
Advanced Setup
DPOJET
Prev
Next

Figure 56. Advanced DDR analysis tools automate complex memory tasks like separating read/write bursts and performing JEDEC measurements.


Tek Run
Trig'd
0.8
0.7
0.6
0.5
0.4
0.3
0.2
0.1
-.1
-.3
Ch1 143mV
M 10.0µs
525/NTSC Ch1
All Lines
40.2000µs
TRIGGER
Format
SDTV
HDTV
Standard
525/NTSC
625/PAL
SECAM
Holdoff
Time
Fields
0.0
Source
Ch: 1 2 3 4
Alt
Field/Line
Even Odd
All Fields
All Lines
0 Line 1
MENU
Video
SUBMENU
SDTV/HDTV
AUTOSET
Lines
Fields
ACQUIRE
Fast Trig
Normal
DISPLAY
Waveform
mV
Vectorscope
75% 100%
Picture
On Off

Figure 57. Video application modules make the oscilloscope a fast, tell-all tool for video troubleshooting.


ScopeMath
File
Tools
Help
Raw Data
Amplitude [V]
Time [sec]
0
100
200
300
400
500
Data source: Simulation
Data channel:
simChan1
Analyzed Data
Plot type:
2D Plot
Analysis model:
highpassfilter
Filter data using highpass Chebyshev filtering
Start
Status
Ready
Elapsed Time: 00:27:41

Figure 58. Advanced analysis and productivity software, such as MATLAB®, can be installed in Windows-based oscilloscopes to accomplish local signal analysis.


Multipurpose
Push - Fine
Cursors
Delay
Resolution
Search
Mark
Scale
Set/Clear
Touch Screen
Off
Ch 3
Ch 4
Ready
Aux
Line
Trig'd
Level
Push Set 50%
Slope
Pos
Neg
Mode
Norm
Auto
Vertical
Ch 1
Ch 2
Ch 3
Ch 4
Position
Offset
Push-Select
Scale

Figure 59. Traditional, analog-style knobs control position, scale, intensity, etc. – precisely as you would expect.


Horizontal
Acquisition
Mode
Automatic
Constant Sample Rate
Manual
Sample Rate
Scale
Record Length Limit
Resolution
Duration
Record Length
Delay Mode
Horizontal Zoom
Ext Ref
Ref Pt
Position

Figure 60. Use graphical control windows to access even the most sophisiticated functions with confidence and ease.


MyScope Setup
Choose From These Controls
Click and Drag Controls onto the Tab below
New Tab
Rename Tab
Delete
Save
Save As
Help
Close
Glitch
Width
Runt
Timeout
Pattern
State
Setup/Hold
Transition
Comm
Serial
Video
Window
CAN Bus
SPI
I2C
RS232
B - TriggerType
A - TriggerType
Edge
Runt
Setup/Hold
Serial
Video
Setup
Untitled
Tab1
Label
Source
Termination
Zoom
Controls
Autoset
Bandwidth
20 MHz
250 MHz
Full
Spectral Analysis
Basic
Advanced

Figure 61. Touch-sensitive display naturally solves issues with cluttered benches and carts, while providing access to clear, on-screen buttons.

Ease-of-Use

Oscilloscopes should be easy to learn and easy to use, helping you work at peak efficiency and productivity. Allowing you to focus on your design, rather than the measurement tools. Just as there is no one typical car driver, there is no one typical oscilloscope user. Regardless of whether you prefer a traditional instrument interface, or that of a Windows® interface, it is important to have flexibility in your oscilloscope's operation.

Many oscilloscopes offer a balance between performance and simplicity by providing the user with many ways to operate the instrument. A front-panel layout, in Figure 59, provides dedicated vertical, horizontal and trigger controls. An icon-rich graphical user interface, as shown in Figure 60, helps you understand and intuitively use advanced capabilities. Touch-sensitive displays solve issues with cluttered benches and carts, while providing access to clear, on-screen buttons, as seen in Figure 61. Online help provides a convenient, built-in reference manual. Intuitive controls allow even occasional oscilloscope users to feel as comfortable driving the oscilloscope as they do driving a car, while giving full-time users easy access to the oscilloscope's most advanced features. In addition, many oscilloscopes are portable, such as the one shown in Figure 62, making the oscilloscope efficient in many different operating environments – in the lab or in the field.

Figure 62. The portability of many oscilloscopes makes the instrument efficient in many operating environments.



Figure 63. Typical wrist-type grounding strap.

Operating the Oscilloscope

This section briefly describes how to set up and start using an oscilloscope – specifically, how to properly ground the oscilloscope and yourself, set the oscilloscope controls, calibrate the oscilloscope, connect the probes, and compensate the probes.

Proper grounding is an important step when setting up to take measurements or work on a circuit. Proper grounding of the oscilloscope protects you from a hazardous shock and grounding yourself protects your circuits from damage.

Proper Grounding

To ground the oscilloscope means to connect it to an electrically neutral reference point, such as earth ground. Ground your oscilloscope by plugging its three-pronged power cord into an outlet grounded to earth ground.

Grounding the oscilloscope is necessary for safety. If a high voltage contacts the case of an ungrounded oscilloscope – any part of the case, including knobs that appear insulated – it can give you a shock. However, with a properly grounded oscilloscope, the current travels through the grounding path to earth ground rather than through you to earth ground.

Grounding is also necessary for taking accurate measurements with your oscilloscope. The oscilloscope needs to share the same ground as any circuits you are testing.

Some oscilloscopes do not require separate connection to earth ground. These oscilloscopes have insulated cases and controls, which keeps any possible shock hazard away from the user.

If you are working with integrated circuits (ICs), you also need to ground yourself. Integrated circuits have tiny conduction paths that can be damaged by static electricity that builds up on your body. You can ruin an expensive IC simply by walking across a carpet or taking off a sweater and then touching the leads of the IC. To solve this problem, wear a grounding strap, as shows in Figure 63. This strap safely sends static charges on your body to earth ground.

Setting the Controls

After plugging in the oscilloscope, take a look at the front panel. As described previously, the front panel is typically divided into three main sections labeled vertical, horizontal, and trigger. Your oscilloscope may have other sections, depending on the model and type.

Notice the input connectors on your oscilloscope – this is where you attach the probes. Most oscilloscopes have at least two input channels and each channel can display a waveform on the screen. Multiple channels are useful for comparing waveforms. As mentioned earlier, MSOs also have digital inputs as well.

Some oscilloscopes have AUTOSET and/or DEFAULT buttons that can set up the controls in one step to accommodate a signal. If your oscilloscope does not have this capability, it is helpful to set the controls to standard positions before taking measurements.

General instructions to manually set up the oscilloscope in standard positions are as follows:

- Set the oscilloscope to display channel 1
- Set the vertical volts/division scale and position controls to mid–range positions
- Turn off the variable volts/division
- Turn off all magnification settings
- Set the channel 1 input coupling to DC
- Set the trigger mode to auto
- Set the trigger source to channel 1
- Turn trigger holdoff to minimum or off
- Set the horizontal time/division and position controls to mid-range positions
- Adjust channel 1 volts/division such that the signal occupies as much of the 10 vertical divisions as possible without clipping or signal distortion

Calibrating the Instrument

In addition to proper oscilloscope setup, periodic instrument self-calibration is recommended for accurate measurements. Calibration is needed if the ambient temperature has changed more than 5° C (9° F) since the last self-calibration or once a week. In the oscilloscope menu this can sometimes be initiated as “Signal Path Compensation”. Refer to the manual that accompanied your oscilloscope for more detailed instructions.

Connecting the Probes

Now you are ready to connect a probe to your oscilloscope. A probe, if well-matched to the oscilloscope, will enable you to access all of the power and performance in the oscilloscope and will ensure the integrity of the signal you are measuring.

Measuring a signal requires two connections: the probe tip connection and the ground connection. Probes often come with a clip attachment for grounding the probe to the circuit under test. In practice, you attach the grounding clip to a known ground in the circuit, such as the metal chassis of a product you are repairing, and touch the probe tip to a test point in the circuit

Compensating the Probes

Passive attenuation voltage probes must be compensated to the oscilloscope. Before using a passive probe, you need to compensate it – to balance its electrical properties to a particular oscilloscope.

You should get into the habit of compensating the probe every time you set up your oscilloscope. A poorly adjusted probe can make your measurements less accurate. Figure 64 illustrates the effects on a 1 MHz test signal when using a probe that is not properly compensated.

Most oscilloscopes have a square wave reference signal available at a terminal on the front panel used to compensate the probe. General instructions to compensate the probe are as follows:

- Attach the probe to a vertical channel
- Connect the probe tip to the probe compensation, i.e. square wave reference signal
- Attach the ground clip of the probe to ground
- View the square wave reference signal
- Make the proper adjustments on the probe so that the corners of the square wave are square

Probe Undercompensated.



Probe Adjustment Signal

Note Reduced Amplitude

Probe Compensated Correctly.



Probe Adjustment Signal

Note Proper Amplitude

Probe Overcompensated.



Probe Adjustment Signal

Note Increased Amplitude

Figure 64. The effects of improper probe compensation.

When you compensate the probe, always attach any accessory tips you will use and connect the probe to the vertical channel you plan to use. This will ensure that the oscilloscope has the same electrical properties as it does when you take measurements.

Oscilloscope Measurement Techniques

This section reviews basic measurement techniques. The two most basic measurements you can make are voltage and time measurements. Just about every other measurement is based on one of these two fundamental techniques.

This section discusses methods for taking measurements visually with the oscilloscope screen. This is a common technique with analog instruments, and also may be useful for "at-a-glance" interpretation of digital oscilloscope displays.

Note that most digital oscilloscopes include automated measurement tools that simplify and accelerate common analysis tasks, thus improving the reliability and confidence of your measurements. However, knowing how to make measurements manually as described here will help you understand and check the automatic measurements.

Voltage Measurements

Voltage is the amount of electric potential, expressed in volts, between two points in a circuit. Usually one of these points is ground (zero volts), but not always. Voltages can also be measured from peak-to-peak – from the maximum point of a signal to its minimum point. You must be careful to specify which voltage you mean.

The oscilloscope is primarily a voltage-measuring device. Once you have measured the voltage, other quantities are just a calculation away. For example, Ohm's law states that voltage between two points in a circuit equals the current times the resistance. From any two of these quantities you can calculate the third using the following formula:

$$\text{Voltage} = \text{Current} \; x \; \text{Resistance}$$

$$\text{Current} = \frac{\text{Voltage}}{\text{Resistance}}$$

$$\text{Resistance} = \frac{\text{Voltage}}{\text{Current}}$$



Figure 65. Voltage peak (V_p) and peak-to-peak voltage (V_{p-p})



Figure 66. Measure voltage on the center vertical graticule line.

Another handy formula is the power law, which states that the power of a DC signal equals the voltage times the current. Calculations are more complicated for AC signals, but the point here is that measuring the voltage is the first step toward calculating other quantities. Figure 65 shows the voltage of one peak (V_p) and the peak-to-peak voltage (V_{p-p}).

The most basic method of taking voltage measurements is to count the number of divisions a waveform spans on the oscilloscope's vertical scale. Adjusting the signal to cover most of the display vertically makes for the best voltage measurements, as shown in Figure 66. The more display area you use, the more accurately you can read the measurement.

Many oscilloscopes have cursors that let you make waveform measurements automatically, without having to count graticule marks. A cursor is simply a line that you can move across the display. Two horizontal cursor lines can be moved up and down to bracket a waveform's amplitude for voltage measurements, and two vertical lines move right and left for time measurements. A readout shows the voltage or time at their positions.



Figure 67. Measure time on the center horizontal graticule line.



Figure 68. Rise time and pulse width measurement points.

Time and Frequency Measurements

You can make time measurements using the horizontal scale of the oscilloscope. Time measurements include measuring the period and pulse width of pulses. Frequency is the reciprocal of the period, so once you know the period, the frequency is one divided by the period. Like voltage measurements, time measurements are more accurate when you adjust the portion of the signal to be measured to cover a large area of the display, as illustrated in Figure 67.

Pulse Width and Rise Time Measurements

In many applications, the details of a pulse's shape are important. Pulses can become distorted and cause a digital circuit to malfunction, and the timing of pulses in a pulse train is often significant.

Standard pulse measurements are pulse rise time and pulse width. Rise time is the amount of time a pulse takes to go from a low to high voltage. By convention, the rise time is measured from 10% to 90% of the full voltage of the pulse. This eliminates any irregularities at the pulse's transition corners. Pulse width is the amount of time the pulse takes to go from low to high and back to low again. By convention, the pulse width is measured at 50% of full voltage. Figure 68 illustrates these measurement points.

Pulse measurements often require fine-tuning the triggering. To become an expert at capturing pulses, you should learn how to use trigger holdoff and how to set the digital oscilloscope to capture pretrigger data, as described in the Systems and Controls of an Oscilloscope section. Horizontal magnification is another useful feature for measuring pulses, since it allows you to see fine details of a fast pulse.



Figure 69. Lissajous patterns.

Phase Shift Measurements

One method for measuring phase shift – the difference in timing between two otherwise identical periodic signals – is to use XY mode. This measurement technique involves inputting one signal into the vertical system as usual and then another signal into the horizontal system – called an XY measurement because both the X and Y axis are tracing voltages. The waveform that results from this arrangement is called a Lissajous pattern (named for French physicist Jules Antoine Lissajous and pronounced LEE–sa–zhoo). From the shape of the Lissajous pattern, you can tell the phase difference between the two signals. You can also tell their frequency ratio. Figure 69 shows Lissajous patterns for various frequency ratios and phase shifts.

The XY measurement technique originated with analog oscilloscopes. DSOs may have difficulty creating real-time XY displays. Some DSOs create an XY image by accumulating triggered data points over time, then displaying two channels as an XY display.

DPOs, on the other hand, are able to acquire and display a genuine XY mode image in real-time, using a continuous stream of digitized data. DPOs can also display an XYZ image with intensified areas. Unlike XY displays on DSOs and DPOs, these displays on analog oscilloscopes are typically limited to a few megahertz of bandwidth.

Other Measurement Techniques

This section has covered basic measurement techniques. Other measurement techniques involve setting up the oscilloscope to test electrical components on an assembly line, capturing elusive transient signals, and many others. The measurement techniques you will use will depend on your application, but you have learned enough to get started. Practice using your oscilloscope and read more about it. Soon its operation will be second nature to you.

Written Exercises

This section contains written exercises that cover information in this primer. These are divided into two parts, Part I and Part II, with vocabulary and application exercises for each.

Check how well you have absorbed the information in these sections by verifying your responses against the answer key at the end of this section on page 54.

Part I covers information presented in these sections:

- The Oscilloscope
- Performance Terms and Considerations

Part II covers information presented in sections:

- The Systems and Controls of an Oscilloscope
- Operating the Oscilloscope
- Measurement Techniques

Part I A: Vocabulary Exercise

Write the letter of the definitions in the right column next to the correct words in the left column.

	Term		Definition
1. ___	Acquisition	**A**	The unit of electric potential difference.
2. ___	Analog	**B**	A performance measurement indicating the precision of an ADC, measured in bits.
3. ___	Bandwidth	**C**	Term used when referring to degree points of a signal's period.
4. ___	Digital Phosphor	**D**	The number of times a signal repeats in one second.
5. ___	Frequency	**E**	The amount of time it takes a wave to complete one cycle.
6. ___	Glitch	**F**	A stored digital value that represents the voltage of a signal at a specific point in time on the display.
7. ___	Period	**G**	A common waveform shape that has a rising edge, a width, and a falling edge.
8. ___	Phase	**H**	A performance measurement indicating the rising edge speed of a pulse.
9. ___	Pulse	**I**	Oscilloscope circuitry that controls the timing of the sweep.
10. ___	Waveform Point	**J**	An intermittent spike in a circuit.
11. ___	Rise Time	**K**	A signal measured by an oscilloscope that only occurs once.
12. ___	Sample Point	**L**	The oscilloscope's process of collecting sample points from the ADC, processing them, and storing them in memory.
13. ___	Digital Storage	**M**	Something that operates with continuously changing values.
14. ___	Time Base	**N**	Digital oscilloscope that captures 3 dimensions of signal information in real-time.
15. ___	Transient	**O**	Digital oscilloscope with serial processing.
16. ___	ADC Resolution	**P**	A sine wave frequency range, defined by the – 3 dB point.
17. ___	Volt	**Q**	The raw data from an ADC used to calculate and display waveform points.

Part I B: Application Exercise

Circle the best answers for each statement. Some statements have more than one right answer.

1. With an oscilloscope you can:
- a. Calculate the frequency of a signal.
- b. Find malfunctioning electrical components.
- c. Analyze signal details.
- d. All the above.

2. The difference between analog and digitizing oscilloscopes is:
- a. Analog oscilloscopes do not have on-screen menus.
- b. Analog oscilloscopes apply a measurement voltage directly to the display system, while digital oscilloscopes first convert the voltage into digital values.
- c. Analog oscilloscopes measure analogs, whereas digitizing oscilloscopes measure digits.
- d. Analog oscilloscopes do not have an acquisition system.

3. An oscilloscope's vertical section does the following:
- a. Acquires sample points with an ADC.
- b. Starts a horizontal sweep.
- c. Lets you adjust the brightness of the display.
- d. Attenuates or amplifies the input signal.

4. The time base control of the oscilloscope does the following:
- a. Adjusts the vertical scale.
- b. Shows you the current time of day.
- c. Sets the amount of time represented by the horizontal width of the screen.
- d. Sends a clock pulse to the probe.

5. On an oscilloscope display:
- a. Voltage is on the vertical axis and time is on the horizontal axis.
- b. A straight diagonal trace means voltage is changing at a steady rate.
- c. A flat horizontal trace means voltage is constant.
- d. All the above.

6. All repeating waves have the following properties:
- a. A frequency measured in Hertz.
- b. A period measured in seconds.
- c. A bandwidth measured in Hertz.
- d. All the above.

7. If you probe inside a computer with an oscilloscope, you are likely to find the following types of signals:
- a. Pulse trains.
- b. Ramp waves.
- c. Sine waves.
- d. All the above.

8. When evaluating the performance of an analog oscilloscope, some things you might consider are:
- a. The bandwidth.
- b. The vertical sensitivity.
- c. The ADC resolution.
- d. The sweep speed.

9. The difference between digital storage oscilloscopes (DSO) and digital phosphor oscilloscopes (DPO) is:
- a. The DSO has a higher bandwidth.
- b. The DPO captures three dimensions of waveform information in real-time.
- c. The DSO has a color display.
- d. The DSO captures more signal details.

Part II A: Vocabulary Exercise

Write the letter of the definitions in the right column next to the correct words in the left column.

	Term		**Definition**
1. ___	Averaging Mode	**A**	The unintentional interaction of the probe and oscilloscope with the circuit being tested which distorts a signal.
2. ___	Circuit Loading	**B**	A conductor that connects electrical currents to the Earth.
3. ___	Compensation	**C**	A sampling mode in which the digital oscilloscope collects as many samples as it can as the signal occurs, then constructs a display, using interpolation if necessary.
4. ___	Coupling	**D**	A sampling mode in which the digital oscilloscope constructs a picture of a repetitive signal by capturing a little bit of information from each repetition.
5. ___	Earth Ground	**E**	A device that converts a specific physical quantity such as sound, pressure, strain, or light intensity into an electrical signal.
6. ___	Equivalent-Time	**F**	A test device for injecting a signal into a circuit input.
7. ___	Graticule	**G**	A processing technique used by digital oscilloscopes to eliminate noise in a displayed signal.
8. ___	Interpolation	**H**	The method of connecting two circuits together.
9. ___	Real Time	**I**	A “connect-the-dots” processing technique to estimate what a fast waveform looks like based on only a few sampled points.
10. ___	Signal Generator	**J**	The grid lines on a screen for measuring oscilloscope traces.
11. ___	Single Sweep	**K**	A trigger mode that triggers the sweep once, must be reset to accept another trigger event.
12. ___	Sensor	**L**	A probe adjustment for 10X attenuator probes that balances the electrical properties of the probe with the electrical properties of the oscilloscope.

Part II B: Application Exercise

Circle the best answers for each statement. Some statements have more than one right answer.

1. To operate an oscilloscope safely, you should:

a. Ground the oscilloscope with the proper three-pronged power cord.

b. Learn to recognize potentially dangerous electrical components.

c. Avoid touching exposed connections in a circuit being tested even if the power is off.

d. All the above.

2. Grounding an oscilloscope is necessary:

a. For safety reasons.

b. To provide a reference point for making measurements.

c. To align the trace with the screen's horizontal axis.

d. All the above.

3. Circuit loading is caused by:

a. An input signal having too large a voltage.

b. The probe and oscilloscope interacting with the circuit being tested.

c. A 10X attenuator probe being uncompensated.

d. Putting too much weight on a circuit.

4. Compensating a probe is necessary to:

a. Balance the electrical properties of the 10X attenuator probe with the oscilloscope.

b. Prevent damaging the circuit being tested.

c. Improve the accuracy of your measurements.

d. All the above.

5. The trace rotation control is useful for:

a. Scaling waveforms on the screen.

b. Detecting sine wave signals.

c. Aligning the waveform trace with the screen's horizontal axis on an analog oscilloscope.

d. Measuring pulse width.

6. The volts per division control is used to:

a. Scale a waveform vertically.

b. Position a waveform vertically.

c. Attenuate or amplify an input signal.

d. Set the numbers of volts each division represents.

7. Setting the vertical input coupling to ground does the following:

a. Disconnects the input signal from the oscilloscope.

b. Causes a horizontal line to appear with auto trigger.

c. Lets you see where zero volts is on the screen.

d. All the above.

8. The trigger is necessary to:

a. Stabilize repeating waveforms on the screen.

b. Capture single-shot waveforms.

c. Mark a particular point of an acquisition.

d. All the above.

9. The difference between auto and normal trigger mode is:

a. In normal mode the oscilloscope only sweeps once and then stops.

b. In normal mode the oscilloscope only sweeps if the input signal reaches the trigger point; otherwise the screen is blank.

c. Auto mode makes the oscilloscope sweep continuously even without being triggered.

d. All the above.

10. The acquisition mode that best reduces noise in a repeating signal is:

a. Sample mode.

b. Peak detect mode.

c. Envelope mode.

d. Averaging mode.

11. The two most basic measurements you can make with an oscilloscope are:

a. Time and frequency measurements.

b. Time and voltage measurements.

c. Voltage and pulse width measurements.

d. Pulse width and phase shift measurements.

12. If the volts/division is set at 0.5, the largest signal that can fit on the screen (assuming an 8 x 10 division screen) is:

a. 62.5 millivolts peak-to-peak.

b. 8 volts peak-to-peak.

c. 4 volts peak-to-peak.

d. 0.5 volts peak-to-peak.

13. If the seconds/division is set at 0.1 ms, the amount of time represented by the width of the screen is:

a. 0.1 ms.

b. 1 ms.

c. 1 second.

d. 0.1 kHz.

14. By convention, pulse width is measured:

a. At 10% of the pulse's peak-to-peak (pk-pk) voltage.

b. At 50% of the pulse's peak-to-peak (pk-pk) voltage.

c. At 90% of the pulse's peak-to-peak (pk-pk) voltage.

d. At 10% and 90% of the pulse's peak-to-peak (pk-pk) voltage.

15. You attach a probe to your test circuit but the screen is blank. You should:

a. Check that the screen intensity is turned up.

b. Check that the oscilloscope is set to display the channel that the probe is connected to.

c. Set the trigger mode to auto since norm mode blanks the screen.

d. Set the vertical input coupling to AC and set the volts/division to its largest value since a large DC signal may go off the top or bottom of the screen.

e. Check that the probe isn't shorted and make sure it is properly grounded.

f. Check that the oscilloscope is set to trigger on the input channel you are using.

g. All of the above.

Answer Key

This section provides the answers to all written exercises in the previous section.

Part IA: Vocabulary Exercise Answers

1. L	5. D	9. G	13. O
2. M	6. J	10. F	14. I
3. P	7. E	11. H	15. K
4. N	8. C	12. Q	16. B
			17. A

Part IB: Application Exercise Answers

1. D	3. D	5. D	7. A
2. B,D	4. C	6. A,B	8. A,B,D
			9. B

Part IIA: Vocabulary Exercise Answers

1. G	4. H	7. J	10. F
2. A	5. B	8. I	11. K
3. L	6. D	9. C	12. E

Part IIB: Application Exercise Answers

1. D	5. C	9. B,C	13. B
2. A,B	6. A,C,D	10. D	14. B
3. B	7. D	11. B	15. G
4. A,C	8. D	12. C	

Glossary

A

Acquisition Mode – Modes that control how waveform points are produced from sample points. Some types include sample, peak detect, hi res, envelope, average, and waveform data base.

Alternating Current (AC) – A signal in which the current and voltage vary in a repeating pattern over time. Also used to indicate signal coupling type.

Amplification – An increase in signal amplitude during its transmission from one point to another.

Amplitude – The magnitude of a quantity or strength of a signal. In electronics, amplitude usually refers to either voltage or power.

Analog-to-Digital Converter (ADC) – A digital electronic component that converts an electrical signal into discrete binary values.

Analog Oscilloscope – An instrument that creates a waveform display by applying the input signal (conditioned and amplified) to the vertical axis of an electron beam moving across a cathode-ray tube (CRT) screen horizontally from left to right. A chemical phosphor coated on the CRT creates a glowing trace wherever the beam hits.

Analog Signal – A signal with continuously variable voltages.

Attenuation – A decrease in signal amplitude during its transmission from one point to another.

Averaging – A processing technique used by digital oscilloscopes to reduce noise in a displayed signal.

B

Bandwidth – A frequency range, usually limited by –3 dB.

C

Circuit Loading – The unintentional interaction of the probe and oscilloscope with the circuit being tested, distorting the signal.

Compensation – A probe adjustment for passive attenuation probes that balances the capacitance of the probe with the capacitance of the oscilloscope.

Coupling – The method of connecting two circuits together. Circuits connected with a wire are directly coupled (DC); circuits connected through a capacitor or transformer are indirectly (AC) coupled.

Cursor – An on–screen marker that you can align with a waveform to make more accurate measurements.

D

Delayed Time Base – A time base with a sweep that can start (or be triggered to start) relative to a pre-determined time on the main time base sweep. Allows you to see events more clearly and to see events that are not visible solely with the main time base sweep.

Digital Signal – A signal whose voltage samples are represented by discrete binary numbers.

Digital Oscilloscope – A type of oscilloscope that uses an analog-to-digital converter (ADC) to convert the measured voltage into digital information. Types include: digital storage, digital phosphor, mixed signal, and digital sampling oscilloscopes.

Digital Phosphor Oscilloscope (DPO) – A type of digital oscilloscope that closely models the display characteristics of an analog oscilloscope while providing traditional digital oscilloscope benefits (waveform storage, automated measurements, etc.) The DPO uses a parallel-processing architecture to pass the signal to the raster-type display, which provides intensity-graded viewing of signal characteristics in real time. The DPO displays signals in three dimensions: amplitude, time and the distribution of amplitude over time.

Digital Sampling Oscilloscope – A type of digital oscilloscope that employs equivalent-time sampling method to capture and display samples of a signal, ideal for accurately capturing signals whose frequency components are much higher than the oscilloscope's sample rate.

Digital Signal Processing – The application of algorithms to improve the accuracy of measured signals.

Digital Storage Oscilloscope (DSO) – A digital oscilloscope that acquires signals via digital sampling (using an analog-to-digital converter). It uses a serial-processing architecture to control acquisition, user interface, and the raster display.

Digitize – The process by which an analog-to-digital converter (ADC) in the horizontal system samples a signal at discrete points in time and converts the signal's voltage at these points into digital values called sample points.

Direct Current (DC) – A signal with a constant voltage and/or current. Also used to indicate signal coupling type.

Division – Measurement markings on the oscilloscope graticule indicating major and minor marks.

E

Earth Ground – A conductor that will connect electrical currents to the Earth.

Effective Bits – A measure of a digital oscilloscope's ability to accurately reconstruct a sine wave signal's shape. This measurement compares the oscilloscope's actual error to that of a theoretical "ideal" digitizer.

Envelope – The outline of a signal's highest and lowest points acquired over many displayed waveform repetitions.

Equivalent-time Sampling – A sampling mode in which the oscilloscope constructs a picture of a repetitive signal by capturing a little bit of information from each repetition. Two types of equivalent-time sampling: random and sequential.

F

Focus – The analog oscilloscope control that adjusts the cathode-ray tube (CRT) electron beam to control the sharpness of the display.

Frequency – The number of times a signal repeats in one second, measured in Hertz (cycles per second). The frequency equals 1/period.

Frequency Response – Frequency response curves of an oscilloscope define the accuracy in amplitude representation of the input signal in function of the signals frequency. In order to obtain maximum signal fidelity, it is important that the oscilloscope has a flat (stable) frequency response across the entire specified oscilloscopes bandwidth.

G

Gain Accuracy – An indication of how accurately the vertical system attenuates or amplifies a signal, usually represented as a percentage error.

Gigahertz (GHz) – 1,000,000,000 Hertz; a unit of frequency.

Glitch – An intermittent, high-speed error in a circuit.

Graticule – The grid lines on a display for measuring oscilloscope traces.

Ground –

1. A conducting connection by which an electric circuit or equipment is connected to the earth to establish and maintain a reference voltage level.
2. The voltage reference point in a circuit.

H

Hertz (Hz) – One cycle per second; the unit of frequency.

Horizontal Accuracy (Time Base) – An indication of how accurately the horizontal system displays the timing of a signal, usually represented as a percentage error.

Horizontal Sweep – The action of the horizontal system that causes a waveform to be drawn.

I

Intensity Grading – Frequency-of-occurrence information that is essential to understanding what the waveform is really doing.

Interpolation – A "connect-the-dots" processing technique to estimate what a fast waveform looks like based on only a few sampled points. Two types: linear and sin x/x.

K

Kilohertz (kHz) – 1,000 Hertz; a unit of frequency.

L

Loading – The unintentional interaction of the probe and oscilloscope with the circuit being tested which distorts a signal.

Logic Analyzer – An instrument used to make the logic states of many digital signals visible over time. It analyzes the digital data and can represent the data as real-time software execution, data flow values, state sequences, etc.

M

Megahertz (MHz) – 1,000,000 Hertz; a unit of frequency.

Megasamples per second (MS/s) – A sample rate unit equal to one million samples per second.

Microsecond (µs) – A unit of time equivalent to 0.000001 seconds.

Millisecond (ms) – A unit of time equivalent to 0.001 seconds.

Mixed Signal Oscilloscope (MSO) – A type of digital oscilloscope that combines the basic functionality of a 16-channel logic analyzer with the trusted performance of a 4-channel digital phosphor oscilloscope.

N

Nanosecond (ns) – A unit of time equivalent to 0.000000001 seconds.

Noise – An unwanted voltage or current in an electrical circuit.

O

Oscilloscope – An instrument used to make voltage changes visible over time. The word oscilloscope comes from “oscillate,” since oscilloscopes are often used to measure oscillating voltages.

P

Peak (V_p) – The maximum voltage level measured from a zero reference point.

Peak Detection – An acquisition mode available with digital oscilloscopes that enables you to observe signal details that may otherwise be missed, particularly useful for seeing narrow pulses spaced far apart in time.

Peak-to-peak (V_{p-p}) – The voltage measured from the maximum point of a signal to its minimum point.

Period – The amount of time it takes a wave to complete one cycle. The period equals 1/frequency.

Phase – The amount of time that passes from the beginning of a cycle to the beginning of the next cycle, measured in degrees.

Phase Shift – The difference in timing between two otherwise similar signals.

Pre-trigger Viewing – The ability of a digital oscilloscope to capture what a signal did before a trigger event. Determines the length of viewable signal both preceding and following a trigger point.

Probe – An oscilloscope input device, usually having a pointed metal tip for making electrical contact with a circuit element, a lead to connect to the circuit’s ground reference, and a flexible cable for transmitting the signal and ground to the oscilloscope.

Pulse – A common waveform shape that has a fast rising edge, a width, and a fast falling edge.

Pulse Train – A collection of pulses traveling together.

Pulse Width – The amount of time the pulse takes to go from low to high and back to low again, conventionally measured at 50% of full voltage.

R

Ramps – Transitions between voltage levels of sine waves that change at a constant rate.

Raster – A type of display.

Real-time Sampling – A sampling mode in which the oscilloscope collects as many samples as possible from one triggered acquisition. Ideal for signals whose frequency range is less than half the oscilloscope’s maximum sample rate.

Record Length – The number of waveform points used to create a record of a signal.

Rise Time – The time taken for the leading edge of a pulse to rise from its low to its high values, typically measured from 10% to 90%.

S

Sampling – The conversion of a portion of an input signal into a number of discrete electrical values for the purpose of storage, processing and/or display by an oscilloscope. Two types: real-time sampling and equivalent-time sampling.

Sample Point – The raw data from an ADC used to calculate waveform points.

Sample Rate – Refers to how frequently a digital oscilloscope takes a sample of the signal, specified in samples per second (S/s).

Sensor – A device that converts a specific physical quantity such as sound, pressure, strain, or light intensity into an electrical signal.

Signal Integrity – The accurate reconstruction of a signal, determined by the systems and performance considerations of an oscilloscope, in addition to the probe used to acquire the signal.

Signal Source – A test device used to inject a signal into a circuit input; the circuit’s output is then read by an oscilloscope. Also known as a signal generator.

Sine Wave – A common curved wave shape that is mathematically defined.

Single Shot – A signal measured by an oscilloscope that only occurs once (also called a transient event).

Single Sweep – A trigger mode to display one triggered screen of a signal and then stop.

Slope – On a graph or an oscilloscope display, the ratio of a vertical distance to a horizontal distance. A positive slope increases from left to right, while a negative slope decreases from left to right.

Square Wave – A common wave shape consisting of repeating square pulses.

Sweep – One horizontal pass of an anlog oscilloscope's electron beam from left to right across the CRT screen.

Sweep Speed – Same as the time base.

T

Time Base – Oscilloscope circuitry that controls the timing of the sweep. The time base is set by the seconds/division control.

Trace – The visible shapes drawn on a CRT by the movement of the electron beam.

Transient – A signal measured by an oscilloscope that only occurs once (also called a single–shot event).

Trigger – The circuit that references a horizontal sweep on an oscilloscope.

Trigger Holdoff – A control that allows you to adjust the period of time after a valid trigger during which the oscilloscope cannot trigger.

Trigger Level – The voltage level that a trigger source signal must reach before the trigger circuit initiates a sweep.

Trigger Mode – A mode that determines whether or not the oscilloscope draws a waveform if it does not detect a trigger. Common trigger modes include normal and auto.

Trigger Slope – The slope that a trigger source signal must reach before the trigger circuit initiates a sweep.

V

Vertical Resolution (Analog-to-Digital Converter) – An indication of how precisely an analog-to-digital converter (ADC) in a digital oscilloscope can convert input voltages into digital values, measured in bits. Calculation techniques, such as hi res acquisition mode, can improve the effective resolution.

Vertical Sensitivity – An indication of how much the vertical amplifier can amplify a weak signal – usually measured in millivolts (mV) per division.

Volt – The unit of electric potential difference.

Voltage – The difference in electric potential, expressed in volts, between two points.

W

Wave – The generic term for a pattern that repeats over time. Common types include: sine, square, rectangular, sawtooth, triangle, step, pulse, periodic, non-periodic, synchronous, asynchronous.

Waveform – A graphic representation of a voltage varying over time.

Waveform Capture Rate – Refers to how quickly an oscilloscope acquires waveforms, expressed as waveforms per second (wfms/s).

Waveform Point – A digital value that represents the voltage of a signal at a specific point in time. Waveform points are calculated from sample points and stored in memory.

Writing Speed – The ability of an analog oscilloscope to provide a visible trace of the movement of a signal from one point to another. This ability is restrictive for low-repetition signals that have fast-moving details, such as digital logic signals.

XY Mode – A measuremenbt technique that involves inputting one signal into the vertical system, as usual, and one into the horizontal system to trace voltages on both the X and Y axis.

Z

Z Axis – The display attribute on an oscilloscope that shows brightness variations as the trace is formed.

Contact Tektronix:

ASEAN / Australasia	(65) 6356 3900
Austria	00800 2255 4835*
Balkans, Israel, South Africa and other ISE Countries	+41 52 675 3777
Belgium	00800 2255 4835*
Brazil	+55 (11) 3759 7600
Canada	1 (800) 833-9200
Central East Europe, Ukraine and the Baltics	+41 52 675 3777
Central Europe & Greece	+41 52 675 3777
Denmark	+45 80 88 1401
Finland	+41 52 675 3777
France	00800 2255 4835*
Germany	00800 2255 4835*
Hong Kong	400-820-5835
India	(91) 80-42922600
Italy	00800 2255 4835*
Japan	81 (3) 6714-3010
Luxembourg	+41 52 675 3777
Mexico, Central/South America & Caribbean	52 (55) 53 35 10 85
Middle East, Asia and North Africa	+41 52 675 3777
The Netherlands	00800 2255 4835*
Norway	800 16098
People's Republic of China	400-820-5835
Poland	+41 52 675 3777
Portugal	80 08 12370
Republic of Korea	82 (2) 6917-5000
Russia & CIS	+7 (495) 7484900
South Africa	+27 11 206 8360
Spain	00800 2255 4835*
Sweden	00800 2255 4835*
Switzerland	00800 2255 4835*
Taiwan	886 (2) 2722-9622
United Kingdom & Ireland	00800 2255 4835*
USA	1 (800) 833-9200

* European toll-free number. If not accessible, call: +41 52 675 3777

Contact List Updated 09 December 2009

For Further Information

Tektronix maintains a comprehensive, constantly expanding collection of application notes, technical briefs and other resources to help engineers working on the cutting edge of technology. Please visit **www.tektronix.com**

Copyright © 2009, Tektronix. All rights reserved. Tektronix products are covered by U.S. and foreign patents, issued and pending. Information in this publication supersedes that in all previously published material. Specification and price change privileges reserved. TEKTRONIX and TEK are registered trademarks of Tektronix, Inc. All other trade names referenced are the service marks, trademarks or registered trademarks of their respective companies.

12/09 JS 03W-8605-5
TEK1511

Tektronix®

Copyrighted Material



OXFORD DICTIONARY OF
BIOCHEMISTRY AND MOLECULAR BIOLOGY

Second Edition

EDITORS Richard Cammack · Teresa K. Attwood · Peter N. Campbell
J. Howard Parish · Anthony D. Smith · John L. Stirling · Francis Vella

Copyrighted Material

OXFORD DICTIONARY OF

Biochemistry and Molecular Biology

REVISED EDITION

Managing Editor
Professor R. Cammack King's College London
General Editors
Professor T.K. Attwood University of Manchester
Professor P.N. Campbell University College London
Dr J.H. Parish University of Leeds
Dr A.D. Smith University College London
Dr J.L. Stirling King's College London
Professor F. Vella University of Saskatchewan

OXFORD
UNIVERSITY PRESS

Editors

Teresa K. Attwood Professor of Bioinformatics, Faculty of Life Sciences & School of Computer Science, University of Manchester

Richard Cammack (Managing Editor) Professor of Biochemistry, King's College London

Peter N. Campbell (deceased) Emeritus Professor of Biochemistry and Honorary Research Fellow, University College London

J. Howard Parish Life Fellow, University of Leeds

Anthony D. Smith Emeritus Reader in Biochemistry, University College London

John L. Stirling Senior Lecture in Molecular Genetics, King's College London

Francis Vella Former Professor of Biochemistry, Faculty of Medicine, University of Saskatchewan, Saskatoon, Canada

OXFORD DICTIONARY OF

Biochemistry and Molecular Biology

OXFORD
UNIVERSITY PRESS

Great Clarendon Street, Oxford OX2 6DP

Oxford University Press is a department of the University of Oxford.
It furthers the University's objective of excellence in research, scholarship,
and education by publishing worldwide in

Oxford New York

Auckland Cape Town Dar es Salaam Hong Kong Karachi
Kuala Lumpur Madrid Melbourne Mexico City Nairobi
New Delhi Shanghai Taipei Toronto

With offices in

Argentina Austria Brazil Chile Czech Republic France Greece
Guatemala Hungary Italy Japan Poland Portugal Singapore
South Korea Switzerland Thailand Turkey Ukraine Vietnam

Oxford is a registered trade mark of Oxford University Press
in the UK and in certain other countries

Published in the United States
by Oxford University Press Inc., New York

© The General Editors. 1997, 2000, 2006

The moral rights of the authors have been asserted
Database right Oxford University Press (maker)

First edition published 1997
Revised edition 2000
Reprinted 2001, 2003
Second edition published 2006

All rights reserved. No part of this publication may be reproduced,
stored in a retrieval system, or transmitted, in any form or by any means,
without the prior permission in writing of Oxford University Press,
or as expressly permitted by law, or under terms agreed with the appropriate
reprographics rights organization. Enquiries concerning reproduction
outside the scope of the above should be sent to the Rights Department,
Oxford University Press, at the address above

You must not circulate this book in any other binding or cover
and you must impose the same condition on any acquirer

British Library Cataloguing in Publication Data
Data available

Library of Congress Cataloging in Publication Data
Data available

Typeset by Market House Books Ltd.
Printed on acid-free paper

ISBN 0-19-852917-1   978–0–19–852917-0

10 9 8 7 6 5 4 3 2 1

In memory of Peter Nelson Campbell (1921–2005)

Peter Campbell was the first person to synthesize a protein using components of the cell rather than complete cells. He was one of the group who first showed the importance of autoimmunity in human disease. Peter was Head of the Biochemistry Department in the University of Leeds from 1967 until 1975. He was a founder of the Federation of European Biochemical Societies (FEBS) and, among many international commitments, chaired the Education Committee of the International Union of Biochemistry and Molecular Biology (IUB). A great advocate of biochemistry teaching, he started the journal *Biochemical Education*. His books included *Biochemistry Illustrated*, with Tony Smith. He was also one of the main driving forces behind the creation of the first edition of the *Oxford Dictionary of Biochemistry and Molecular Biology*.

Preface

Preface to this edition

It is a decade since the first edition of the *Oxford Dictionary of Biochemistry and Molecular Biology*. It was a remarkable work of scholarship, arising from the work of journal editors and scientific writers. Since then the landscape of biochemistry has changed immeasurably. The genome sequences have laid out the blueprints of whole organisms, especially Man. They have revealed the diversity of gene expression, and the complex systems by which cellular molecules organize themselves. The molecular basis of many diseases has been revealed, and vital cellular components discovered.

The literature is more diverse than ten years ago. The identification of the genes has rushed ahead of the biochemical characterization of their functions. Many protein and nucleic acid factors have been discovered. While their functions are incompletely understood, they are referred to by laboratory shorthand abbreviations. These are well understood by the investigators who work on them, but the mass of them becomes very confusing to the student, or to those viewing biochemistry from the outside. New methods of bioinformatics have been developed to bridge the gap. Meanwhile the '-omics' projects have introduced new layers of complexity as we see the interactions between macromolecules leading to new emergent properties.

As predicted in the first edition, the influence of the Internet has expanded. Instead of searching for information in libraries, students now usually go first to a search engine. So, does such a dictionary have a role in the age of Google? In fact it has gained in sales and popularity. Evidently it fills a need for a source of reliable information that is not always so easy to find.

A revised version of the dictionary, with some additions and corrections was printed in 2000. At that time, the need for a complete revision was apparent. The work continued with a new team, recruited by the ever-enthusiastic Peter Campbell. We deeply regret that he did not live to see the completion of this task, having died on February 8th 2005 from complications after an accident.

In order to keep the dictionary as a handy reference volume, we have endeavoured to avoid it becoming much heavier. It is only by being selective that there are only about 20% more entries than the first edition. Most of the appendices have been removed, or their useful parts transferred. The listed Nobel prizewinners in biochemistry and molecular biology have been omitted except for eponymous entries, when they have lent their names to compounds or procedures. There has been a judicious removal of some older terms, though we found that surprisingly few have disappeared from the literature to such an extent that they are obsolete.

The literature abounds with laboratory shorthand names, database identifiers; TLA's (three-letter abbreviations) and other acronyms are extremely common, and a notorious source of ambiguity. We have cited these selectively, sometimes to indicate that a word or phrase has two meanings in different contexts. In the printed form we can show the full range of printed characters – boldface, italic, sub- and superscripts, Greek letters – that make up the syntax of many of the names, and that are difficult to find with search engines.

The dictionary is not intended to be a nomenclature document, and the terms that are in the entries are generally those that are in common use. We continue the practice of pointing the reader in the direction of recommended terminology and nomenclature. Nomenclature rules are applied less prescriptively these days; 'recommended' chemical nomenclature has become 'preferred'; 'recommended names' for enzymes have given way to 'common names'.

A great many of the new entries, on inherited diseases and much else besides are provided by Frank Vella, drawing on the eclectic collection of topical papers that he assembled for his columns in journals such as IUBMB Life. The entries on bioinformatics and genetics, which have assumed greater importance in BMB over the past decade, have been bolstered by the work of Terri Attwood and John Stirling. Finally it has been a pleasure to work with John Daintith and Robert Hine of Market House Books, whose expertise in chemistry and biology meant that their assembly of the book was an expert job.

The content of such a dictionary is necessarily selective. We have tried to ensure that the entries in the dictionary reflect current usage in biochemistry and molecular biology. As always, we are grateful to readers who point out errors in the present text.

Richard Cammack
March 2006

Preface to the revised first edition

It must be inevitable with any work of this nature that a number of imperfections and errors occur. So the opportunity provided by the need to reprint this dictionary has been taken to effect some improvements within the limitation imposed by retention of the original pagination. As well as the correction of a variety of minor misprints and other minor defects, over four hundred entries been either revised or completely rewritten, and fifty or so new entries have been provided, some to remedy deficiencies and others to provide additional terms that have become of topical interest. To help make way for the new ones, about half as many original entries have been deleted. In addition, Appendices B, C, and D have been updated, and Appendix B has been expanded and provided with all the relevant Internet addresses available at the time of writing.

Valuable comments on the original edition by a number of readers are gratefully acknowledged, and thanks are again due to Dr. H. B. F. Dixon for advice on aspects of nomenclature as well as to Oxford University Press and Market House Books for their much appreciated cooperation.

September 1999 A. D. S.

Preface to the first edition

Nearly twenty years ago one of us (S. P. D., soon joined by G. H. S.), began a distillation of the elements of biochemistry into an alphabetical arrangement. The task was formidable and eventually other editors were recruited, an editorial board was established, and now the work is offered as the *Oxford Dictionary of Biochemistry and Molecular Biology*. It is hoped that the dictionary will serve the needs of the research biochemist or molecular biologist, as well as teachers of the subject and their students. In addition, it should prove of value to practitioners of other fields of study or work seeking the meaning of a biochemical term.

An important function of a dictionary is to provide guidance on current usage in the field within its scope. The original 12-volume *Oxford English Dictionary* was compiled from about five million slips of paper bearing sentences or phrases extracted by some thousands of 'readers' from classical works of literature and those of the best contemporary authors. It was thus firmly based on good usage. In scientific subjects, specialist terminology is often codified in sets of recommendations regarding nomenclature, meaning, abbreviations, symbols, and so on. These have been agreed by international commissions (e.g. those of The International Union of Pure and Applied Chemistry and The International Union of Biochemistry and Molecular Biology) as a means of preserving order and facilitating communication between scientists. We have striven to conform as far as possible to the relevant international recommendations, but in some cases, where usage so frequently diverges from a recommendation that adherence to it would seriously detract from ease of use of the dictionary, we have kept to the principle that the dictionary should reflect usage (see the definitions of *lexicographer*). This does not extend, of course, to cases where usage, however widespread, contradicts sound scientific principles. The internationally agreed recommendation is always also listed. The various compilations of these recommendations that have been drawn upon are listed in Appendix B, together with a number of other sources of information on nomenclature.

Biochemistry is the discipline that embraces the study of the structure and function of life-forms at the molecular level. Molecular biology is a closely related discipline that originates in the study of DNA and its metabolism, and now embraces all those investigations that exploit the technology that has resulted from this work. Both disciplines aim to explain the behaviour of life-forms in molecular terms, and are so closely interrelated that separation is barely possible. It is inevitable that the content of this dictionary is to a degree arbitrary, but it is hoped that all important aspects of these subjects have received consideration. The compilers have attempted to offer a broad coverage of terms encountered in the literature of biochemistry and molecular biology by including an appreciable number from cognate sciences. Although the compilation is designed primarily to serve readers of contemporary material, the needs of those who turn to older literature have also been borne in mind. Some of the entries thus have a historical flavour, some obsolete terms are included (e.g. zymase), and in some cases a historical approach has been used as the best means of presenting an explanation of a term, as for example in the case of the entry for *gene*. The value of a scientific dictionary is enhanced by inclusion of contextual information as well as mere explanations of meaning or terminology. This dictionary will be found to have some of the attributes of an encyclopedia, although the extent to which it veers in this direction has varied with the whim of its compilers. It is our hope that in a single volume the reader has easy access to basic definitions as well as a generous helping of other information.

In the present-day world, we are assailed by floods of 'information'. It has been suggested that the average weekday edition of a newspaper of record (e.g. *The New York Times*) provides more information than Shakespeare and his contemporaries would have acquired in a lifetime. With the availability of much information through the Internet, it may be asked whether a dictionary in paper form is actually necessary. In answer, we note that the Internet can be slow, and is not readily accessible in some parts of the world; the databases may be inadequate, and although usually very up-to-date, the high cost of their maintenance restricts them to specialized knowledge in a limited number of fields. Moreover, books have a quality of their own, which is enabling them to maintain their popularity. It appears that the increasing use of the Internet is actually paralleled by the rate of publication of printed dictionaries; in an information-hungry age, there cannot be too many sources of good-quality information.

We are deeply indebted to the Leverhulme Trust for the award of an emeritus fellowship to one of us (A. D. S.), to University College London, which has provided us with friends and expert colleagues, and to Dr O. Theodor Benfey, Dr Mary Ellen Bowden, and Professor Arnold Thackray, The Beckman Center for History of Chemistry, Chemical Heritage Foundation, Philadelphia, and Dr John Edsall, Harvard University for assistance with biographical data.

Particular thanks are due to Dr H. B. F. Dixon for much advice on nomenclature and related matters. Help on questions of nomenclature from Dr G. P. Moss and Dr A. D. McNaught is also acknowledged. We are grateful to Dr D. H. Jenkinson for his help with the recommendations of the International Committee on Nomenclature in Pharmacology. We are also grateful for the valuable advice of Professor K. W. Taylor and Dr J. L. Crammer, on clinical topics, and Professor M. C. W. Evans, on plant biochemistry, and to Dr Margaret McKenzie, for reading the proofs.

During the earlier stages of the project, Mrs S. Gove gave much valuable assistance and Miss A. Straker was most helpful in suggesting terms for inclusion. We also wish to thank all those other friends and colleagues, in addition to those separately listed, who have unstintingly given us help and advice.

We are pleased to acknowledge the collaboration and material support given to us by Oxford University Press. We also acknowledge the very friendly cooperation of Market House Books, especially the patience and good humour of Dr John Daintith through all the complications of the production. The copy editors, Robert Hine and Jane Cavell, made a number of helpful suggestions.

The compilers offer no apology for their failure to include many deserving terms in the dictionary, but would be pleased to have their attention drawn to errors and to receive suggestions for additional entries in any future edition.

January 1997

A. D. Smith, S. P. Datta, G. H. Smith, P. N. Campbell, R. Bentley, H. A. McKenzie

> *This whole book is but a draught—nay, but the draught of a draught. Oh, Time, Strength, Cash, and Patience.*
>
> Herman Melville (1851) *Moby Dick, or The Whale*
> (ed. T. Tanner, 1988, p. 147, Oxford University Press).

Note on proprietary status

This dictionary includes some words which are, or are asserted to be, proprietary names or trade marks. Their inclusion does not imply that they have acquired for legal purposes a non-proprietary or general significance, nor is any other judgement implied concerning their legal status. In cases where the editor has some evidence that a word is used as a proprietary name or trade mark this is indicated by the designation *proprietary name*, but no judgement concerning the legal status of such words is made or implied thereby.

Guide to the Dictionary

1. Alphabetical order

1.1 Main order of headwords

Alphabetical order is determined on a letter-by-letter basis, not word by word; spaces are disregarded:

acid
acid anhydride
acid–base balance
acid–base catalysis
acid dissociation constant
acid dye
acidemia

1.2 Nonalphabetic characters

Numbers, hyphens, primes, and subscript/superscript text are ignored for the purpose of indexing; an example is the following sequence of entries:

FSH-RH
F1 sphere
F′ strain
F-type pentose phosphate pathway
ftz

1.3 Locants and modifiers

In chemical names, any locants and other hyphenated modifiers such as *cis*-, *trans*-, *p*-, and alphabetic Greek characters are not used to determine primary alphabetical order; hence the following entries all appear under the letter A:

***N*-acetylgalactosamine**
***p*-aminobenzoic acid**
***γ*-aminobutyrate shunt**
6-aminohexanoic acid

However, the unhyphenated letters ‘c’ in ‘cDNA’ and ‘d’ in ‘dCTP’, for example, are treated as integral parts of the word and *are* used to determine alphabetical order.

1.4 Secondary order involving locants

When such modifiers constitute the only difference between two headwords, they determine the alphabetical order of the entries:

benzodiazepine
***o*-benzoquinone**
***p*-benzoquinone**
benzoyl

encephalitis
3′-end
5′-end
end+

1.5 Format differences in headwords

The order for entries where the headword is identical except for format is

b, *b*, b-, *b*-, -b, -*b*, B, *B*, B-, *B*-, -B, -*B*

1.6 Subscripts and superscripts

Single letters with subscripts or superscripts are treated as single letters for the purposes of indexing, so entries for $\boldsymbol{k}_{\mathbf{cat}}$ and $\boldsymbol{K}_{\mathbf{m}}$ will both be found in the list of single-letter entries at the beginning of the letter K. The primary order of these single-letter entries is determined by their format (*see* section 1.5); where there is more than one entry with a given format (e.g. italic, lower case ***k***), these are arranged by alphabetical order of their subscripts/superscripts.

1.7 Greek letters

- Where Greek letters form part of a chemical name, they are not used to determine alphabetical order (*see* section 1.3). Otherwise they are written out in full in the headword, e.g. **nu body, beta strand.**
- The names of the letters of the Greek alphabet, together with their English transliterations used in etymologies, are listed in Appendix A. The meanings assigned to Greek alphabetic characters used as symbols are also given in Appendix A.
- Greek characters are set in italic type when the character represents a variable or locant and in roman type when it represents a unit or subtype e.g. of a protein or particle.

2. Format of entries

2.1 Summary of typefaces

- The following distinguishing typefaces are employed in addition to the text light serif typeface used for definitions:

large bold sans serif	headwords
text bold serif	alternative terms for and variant spellings of headwords; hidden entries; run-ons
text bold sans serif	cross-references
text italic serif	usage notes and field labels; parts of speech; foreign language terms (including scientific and medical Latin); symbols for physical quantities and fundamental physical constants; stereochemical prefixes and alphabetical locants

2.2 Headwords

- For each entry, the headword is in bold, sans serif type.
- Upper-case (capital) initial letters are used only for proper names (or terms derived from them) and for proprietary names. Abbreviations and symbols are printed in upper and/or lower case as appropriate.
- If a term would normally be set in bold type, this is indicated in the entry:

  B *symbol for* **1** Napierian absorbance (*see* **absorbance**). **2** magnetic flux density (bold italic).
- Where the same basic term is used in different typefaces, such as roman/italic, or upper case/lower case, or as a prefix or suffix, each usage is given as a separate headword. For example, **h**, ***h***, **H**, and ***H*** each have a separate entry.
- The order in which such entries are given is listed in section 1.5.

2.3 Alternative terms and variant spellings

2.3.1 Choice of headword

Where alternative terms for a headword, or variant spellings of it, exist (*see* section 1.3), the headword selected for the main entry is generally the recommended or preferred term, or the one judged to be the commonest. Exceptions to this generalization are those instances where the name of a Greek alphabetic character is written out for convenience of indexing:

> **beta globulin** *or* **β globulin**....

2.3.2 General

- Any alternative terms and alternative spellings are listed following the headword in bold, serif type:

  retrovirus *or* **ribodeoxyvirus** *or* **RNA–DNA virus** any virus belonging to the family Retroviridae....
- Notes regarding the usage of these alternatives may be given in brackets and in italics; for example

  DNA glycosylase *or (sometimes)* **DNA glycosidase** any of a group of enzymes....

  bacteremia *or (esp. Brit.)* **bacteraemia** the presence of live bacteria in the blood.

  bilirubin *or (formerly)* **bilirubin IXα** *the recommended trivial name for* the linear tetrapyrrole....
- These alternative terms and spellings also appear as entries in the alphabetical sequence, with a cross-reference to the main entry where the term is defined, unless the variant would appear close to the main entry. Additional information is given where appropriate:

  demoxytocin *an alternative name for* **deaminooxytocin**.

  fructose-1,6-diphosphatase *a former name for* **fructose-bisphosphatase**.

  lipide *a variant spelling of* **lipid**.

  molecular exclusion chromatography *a less common name for* **gel-permeation chromatography**.

  oleomargarine *an alternative name (esp. US) for* **margarine**.

  penatin *an obsolete name for* **glucose oxidase**.

2.3.3 Chemical names

- Synonyms may be given following the headword, in the order: other trivial names (if any); the semi-systematic or semi-trivial name(s); older systematic name in style, if still in widespread use; the systematic name in currently recommended style.
- The headword used to represent a chemical compound that can exist in ionized form(s) is in most cases the name of its physiologically predominant form. So, for example, an entry is headed ‘succinate’ rather that ‘succinic acid’.

2.3.4 Enzyme names

Alternative names may be listed following the headword, which is normally the recommended name; otherwise alternative names include the recommended name (if the headword is the common name), the systematic name, and other names. The EC number is also given.

2.4 Multiple definitions

- Where a term has more than one meaning, the different senses are numbered with bold Arabic numerals.

  blockade **1** *(in pharmacology)* the saturation of a specific type of receptor with an antagonist to its normal agonist. **2** *(in immunology)* the overloading or saturation of the **reticuloendothelial system** with inert particles, such as carbon particles. **3** to impose any such blockade.
- The order of the numbered entries is generally determined by their biochemical significance.
- The different senses may be further subdivided into def. 1a, def. 1b, etc.

  di+ *comb. form* **1** *(in chemical nomenclature)* (*distinguish from* **bis+** (def. 2)) **a** indicating the presence in a molecule of two identical unsubstituted groups, e.g. diethylsulfide, 1,3-dihydroxyacetone. **b** indicating the presence in a molecule of two identical inorganic oxoacid residues in anhydride linkage, e.g. adenosine 5′-diphosphate. **2** *or* **bis+** (def. 1) denoting two, twofold, twice, doubled.

- Homographs are not distinguished.

2.5 Hidden entries

Hidden entries are terms that are not defined at their normal headword position. Instead, they are treated (implicitly or explicitly) at some other headword. They are set in bold serif type. In the following example, 'bentonite flocculation test' is the hidden entry:

bentonite a colloidal, native hydrated aluminium silicate clay consisting principally of montmorillonite, a complex aluminosilicate, $Al_2O_3{\cdot}4SiO_2{\cdot}H_2O$, which has marked adsorptive properties. It is used as an inhibitor of nucleases and also in the **bentonite flocculation test**, a passive agglutination test in which antigen-coated bentonite particles are used to detect specific antibody.

2.6 Other information

2.6.1 Plurals

The plural form (or forms) of a headword is (are) given in parenthesis following the headword if its formation is non-standard, e.g. for Latin headwords, or where there is more than one form of the plural.

medulla (*pl.* **medullas** *or* **medullae**) the innermost part of an organ, tissue, or structure; marrow, pith. — **medullary** *adj.*

2.6.2 Affixes and combining forms

- In common with other dictionaries, this Dictionary lists and defines many word elements that are used to compose terms or to modify existing terms. These are either combining forms (which are derived from parent words) or affixes (infixes, prefixes, and suffixes, none of which have parents).
- The usual lexicographical convention is to add a hyphen to suffixes and combining forms when listing them as headwords, although generally the hyphen is omitted in formation of composite terms. However, chemical and biochemical terminology also includes a considerable number of specialized affixes that retain the hyphen in the formation of composite terms (e.g. '*meso*-' in '*meso*-cystine').

  In order to make an explicit distinction between these alternatives, this Dictionary departs from the common convention by adding a hyphen to an affix in a headword only when a linking hyphen is retained in a combination:

  ***meso*-** *abbr.*: *ms*-; *prefix* (*in chemical nomenclature*) designating a substance whose individual molecules contain....

  By contrast, combining forms (e.g., 'meso' in 'mesoderm') together with affixes producing unhyphenated composite terms, are listed with an added plus sign, placed after and/or before the word-element as appropriate:

  meso+ *or (sometimes before a vowel)* **mes+** *comb. form* denoting middle, or intermediate.

  +agogue *or (US)* **+agog** *suffix* denoting an agent that elicits or enhances the secretion of....

2.6.3 Abbreviations and symbols

- Where a term may be abbreviated or indicated with a symbol, this is noted after the headword.

  nuclear magnetic resonance *abbr.*: NMR *or* nmr; the phenomenon that occurs when atomic nuclei....

  electric potential *or* **potential** *symbol*: V *or* ϕ; the work done in bringing unit electric charge....

- The distinction between an abbreviation and a symbol is a little blurred, since some abbreviations (e.g. lg) also may be used as symbols. In general, the term 'symbol' is used here for

  units and their decimal prefixes (e.g. m, mol; μ, M)

  physical quantities and constants (e.g. a, H; k, R)

  mathematical functions (e.g. exp, ln)

  chemical elements (e.g. K, Mg)

  groups of letters that can be used in place of a chemical group or compound in an equation or formula (e.g. CoA, Me)

  recommended abbreviations for nucleotides, bases, or amino acids.

- The symbols for SI base and derived units and their decimal prefixes are mandatory; all other symbols are recommendations of IUBMB or IUPAC. In conformity with these recommendations, symbols for physical quantities and fundamental physical constants are printed in a sloping (italic) typeface.
- No distinction is made between acronyms, contractions, abbreviations, etc. All are classed as abbreviations. Abbreviations formed from the initial letters of two or more words are printed without periods (full-stops), in line with contemporary practice, but abbreviations that are shortened forms of single words have a terminal period.
- In addition to recommended abbreviations, the Dictionary lists a selection of others commonly encountered in the scientific literature.

2.6.4 Derived terms

Derived terms not meriting separate definition are listed at the end of the entry for the parent term, preceded by a bold em dash and followed by an abbreviation indicating the part of speech.

bactericide *or* **bacteriocide** any agent (biological, chemical, or physical) that destroys bacteria. **—bactericidal** *or* **bacteriocidal** *adj.*

2.6.5 Etymology

- Generally, the derivation of words is not explained in entries. The exceptions are for eponymous terms and other entries of particular etymological interest.
- The etymology is given within square brackets at the end of the entry.

  ångström *or* **Ångstrom** *symbol*: Å; a unit of length equal to 10^{-10} metres. ... [After Anders Jonas Ångström (1814–74), Swedish physicist noted for his work on spectroscopy.]

- Greek elements of etymologies are transliterated:

  chirality topological handedness; the property of nonidentity of an object with its mirror image. ... [From Greek *kheir*, hand.]

2.6.6 Usage

- The field within which the term is used may be specified in italics and in parenthesis before the definition.

malonyl **1** *(in biochemistry)* the univalent acyl group, HOOC–CH_2–CO–, derived from malonic acid by loss of one hydroxyl group. **2** *(in chemistry)* the bivalent acyl group, –CO–CH_2–CO–, derived from malonic acid by loss of both hydroxyl groups.

- Notes may also be given regarding the use of alternative terms and variant spellings: *see* section 2.3.2.

2.7 Cross-references

2.7.1 Format

- Cross-references are set in bold sans serif type, e.g. **thiouridine**.
- Where a cross-reference refers to only one sense of a word with multiple definitions, this is indicated as in the following example:

siderophage *an alternative name for* **siderophore** (def. 1).

2.7.2 Types of cross-reference

- There are cross-references from a variant spelling, or a less commonly used term, etc., to the entry where the term is defined. For examples, *see* section 2.3.2.
- Some cross-references are to related entries giving more information. These may be either embedded in the text:

octulose any **ketose** having a chain of eight carbon atoms in the molecule.

or listed at the end of the entry:

vacuum evaporation a technique for .... *See also* **shadow casting**.

- Cross-references may also be used to draw attention to contrasting terms:

heterochromatin ... *Compare* **euchromatin**.

or to pairs of easily confused terms:

prolidase *another name for* **X-Pro dipeptidase**. *Distinguish from* **prolinase**.

prolinase *the recommended name for* **Pro-X dipeptidase**. *Distinguish from* **prolidase**.

3. Abbreviations

abbr.	abbreviation
adj.	adjective
adv.	adverb
Brit.	British
comb. form	combining form (*see* section 2.6.2)
3-D	three-dimensional
def.	definition
e.g.	[Latin, *exempli gratia*] for example
esp.	especially
etc.	etcetera
Fr.	French
i.e.	[Latin, *id est*] that is
max.	maximum
n.	noun
pl.	plural
sing.	singular
sp. or spp.	species (singular and plural respectively)
US	United States
vb.	verb

Other abbreviations are defined in the text itself.

4. Other conventions

4.1 Spelling and hyphenation

4.1.1 Spelling

- For chemical and biochemical terms, recommended international usage is followed; thus, for example, 'heme' is used rather than 'haem', 'estrogen' rather than 'oestrogen', 'sulfur' rather than 'sulphur', and 'oxytocin' rather than 'ocytocin'. All variants are listed as headwords, however, with cross-references to the corresponding main entries.
- For common terms, e.g. 'colour', British spelling is used.

4.1.2 Hyphenation

- Hyphens are used attributively:

'T cell' but 'T-cell receptor'

'amino acid' but 'amino-acid residues'

- This also applies to enzyme names; thus for example, there is no hyphen following the 'glucose' in 'glucose 6-phosphate', but where this substrate forms part of an enzyme name, it is hyphenated, e.g. in 'glucose-6-phosphatase' or 'glucose-6-phosphate isomerase'.

4.2 Nomenclature

In most cases, headwords conform with the recommendations of the various nomenclature bodies of IUB, IUBMB, and IUPAC. The phrase 'not recommended' has been used to indicate that certain forms are not the recommendation of one of these nomenclature bodies.

4.2.1 Drug names

The recommended international nonproprietary names are used (*International nonproprietary names (INN) for pharmaceutical substances*. World Health Organization, Geneva, 1992); hence, for example, main entries are found under epinephrine and norepinephrine rather than under adrenaline and noradrenaline.

4.2.2 Proprietary names

A few commonly used proprietary names are included; these may be listed at the end of an entry if considered to be of particular interest, especially to non-scientists:

acetaminophen *or* **paracetamol** ... *Proprietary names*: Tylenol, Panadol. It inhibits ....

or may be the main headword:

Sephadex.

4.2.3 Other substances

The main entry is under the name used most widely in the scientific literature. Where this is not the recommended name, a cross-reference is given from the recommended name to the main entry. For example, the name 'follicle-stimulating hormone (FSH)' is widely employed instead of the recommended name 'follitropin', hence the former name has been used as the main headword. In such cases there is a cross-reference from the recommended name back to the entry where the substance is defined:

> **follitropin** *the recommended name for* **follicle-stimulating hormone**.

4.3 Representation of chemical structures

4.3.1 Typeset formulae

In conformity with IUPAC nomenclature recommendations for typeset chemical formulae, parentheses (round brackets) indicate a side chain:

$CH_3–CH(NH_2)–COOH$,
$HO–C(CH_2–COO^-)_2–COO^-$

and square brackets indicate a condensed chain:

$CH_3–[CH_2]_8–COOH$

4.3.2 Carbohydrates

- The cyclic forms of monosaccharides are depicted by Haworth representations as are some other compounds; for clarity, the carbon atoms of the heterocyclic ring, and their attached hydrogen atoms, are not shown. *See* the **Haworth representation** entry for more detail.
- Where an abbreviated terminology is included for oligosaccharide chains, the extended or condensed forms described in the publication entitled *Nomenclature of carbohydrates (recommendations 1996)*) are variously used.
- Wherever possible, structure diagrams show absolute configurations.

4.4 Periodic table of the elements

The group numbers used in the text are those of the 18-column format of the table given in the 1990 edition of the IUPAC 'Red Book'. The correspondence between this and other versions of the table is described in the **periodic table** entry and shown below the table displayed on the endpapers.

4.5 Amino-acid sequences

- For peptide sequences of up to 15 amino-acid residues, the three-letter code is used; longer sequences are given in the one-letter code.
- Motifs are given in the one-letter code.
- The full sequences of many proteins can be found in protein sequence databases, and database codes are given to facilitate access to these. The database codes relate to a number of different databases. The style of the code gives an indication of the database from which the data originate, but if the user does not recognize the code, it is necessary to search for it in a composite database that integrates data from all the major databases.

4.6 Genes

- The accepted format of gene names (i.e., whether lower case or upper case or a mixture) varies between different organisms. Where an entry covers genes from various species, the convention for human genes is generally followed in the headword, i.e. all letters are given in upper case, e.g. '*JUN*'.
- However, when an entry refers only to a gene from a specified organism, the accepted convention for that organism is followed.

4.7 Names of organisms

- Where a binomial Latin name is repeated within an entry, the genus name is abbreviated after the first occurrence of the name; for example, the full form '*Escherichia coli*' is used when first mentioned in any entry, but subsequent references to this organism in the same entry are abbreviated to '*E. coli*'.

5. Appendices

Two appendices have been included after the main alphabetical text:

- Appendix A – The Greek alphabet and Greek characters used as symbols
- Appendix B – Sequence-rule priorities of some common ligands in molecular entities.

Aa

a **1** *abbr. for* adsorbed. **2** *symbol for* atto+ (SI prefix denoting 10^{-18}). **3** axial. **4** year.

a′ *symbol for* pseudoaxial.

a *symbol for* **1** absorption coefficient. **2** acceleration (in vector equations it is printed in bold italic (***a***)). **3** activity (def. 3). **4** van der Waals coefficient. **5** *as subscript*, denotes affinity.

a_0 *symbol for* Bohr radius.

A *symbol for* **1** acid-catalysed (of a reaction mechanism). **2** a residue of the *α*-amino acid L-alanine (alternative to Ala). **3** a residue of the base adenine in a nucleic-acid sequence. **4** a residue of the ribonucleoside adenosine (alternative to Ado). **5** uronic acid. **6** ampere.

A *symbol for* **1** absorbance. **2** activity (def. 2). **3** affinity. **4** Helmholtz function. **5** mass number/nucleon number.

A_r *symbol for* relative atomic mass.

A_s *symbol for* area.

$[A]_{0.5}$ *or* $[A]_{½}$ *symbol (in enzyme kinetics) for* the value of the concentration of a substrate, A, in mol dm^{-3}, at which the velocity of the reaction, *v*, is half the maximum velocity, *V*; i.e. when $v = 0.5V$.

$[A]_{50}$ *symbol for* the molar concentration of an agonist that produces 50% of the maximal possible effect of that agonist. Other percentage values ($[A]_{20}$, $[A]_{40}$, etc.) can be specified. The action of the agonist may be stimulatory or inhibitory. *Compare* **EC_{50}**.

2′-5′A *symbol for* any member of a series of oligonucleotides of the general formula p_a A[2′p5′A]$_n$, where p and A are phosphoric and adenosine residues, respectively, and *a* and *n* are small integers (*a* = 1, 2, or 3 and *n* commonly = 2, 3, or 4). Potent inhibitors of protein biosynthesis *in vivo* and *in vitro*, they are believed to mediate the action of interferon on virus-induced cells.

A23187 *or* **calcimycin** a toxic and weakly antibiotic substance isolated from cultures of *Streptomyces chartreusensis*. It is a lipophilic 523 Da monocarboxylic acid of complex structure, two molecules of which form stable lipid-soluble complexes at pH 7.4 with one atom of certain divalent metal cations, especially Mn^{2+}, Ca^{2+}, and Mg^{2+}; monovalent cations are bound only weakly. It also forms lipid-soluble complexes with certain amino acids. It is used experimentally as a calcium **ionophore**.



Å *symbol for* ångström (unit of length equal to 10^{-10} m).

aa **1** *symbol for* an unknown or unspecified aminoacyl group when acting as a substituent on a base or internal sugar in a (poly)nucleotide. **2** *abbr. for* amino acid.

AA *(formerly) symbol for* an unknown or unspecified amino-acid residue. *See* **Xaa**.

AAA **1** a codon in mRNA for L-lysine. **2** *abbr. for* ATPase associated with varied activities. *See* **AAA protease**.

AAA protease *abbr. for* ATPase associated with varied activities; any member of a family of conserved ATP-dependent proteases that mediate degradation of nonintegrated membrane proteins in bacteria, mitochondria, and chloroplasts. They form large complexes composed of identical or homologous subunits. Each subunit contains two transmembrane segments, an ATP-binding domain, and a metal-dependent catalytic domain. Mitochondria contain a matrix-facing AAA protease (m-AAA protease) and an intermembrane space-facing AAA protease (i-AAA protease). The m-AAA protease is regulated by prohibitins. Paraplegin belongs to the AAA protease family.

AAC a codon in mRNA for L-asparagine.

Aad *symbol for* a residue of the *α*-amino acid L-*α*-aminoadipic acid, L-2-aminohexanedioic acid.

***β*Aad** *symbol for* a residue of the *β*-amino acid L-*β*-aminoadipic acid, L-3-aminohexanedioic acid.

AAG a codon in mRNA for L-lysine.

A antigen the antigen defining the A blood group. *See also* **blood-group substance**, **ABH antigens**.

aardvark a *Dictyostelium* orthologue of β-catenin with cytoskeletal and signal transduction roles. *See* **catenin**.

Aarskog–Scott syndrome *or* **Aarskog syndrome** *or* **faciogenital dysplasia** an extremely rare genetically heterogeneous developmental disorder in which individuals have widely spaced eyes, anteverted nostrils, a broad upper lip and a ‘saddlebag’ or ‘shawl scrotum’. The X-linked form has been ascribed to mutations in the **FGD1** gene. [After Dagfinn Aarskog (1928–), Norwegian paediatrician, and Charles I. Scott Jr (1934–), US paediatrician.]

AAT *abbr. for* **amino acid transporter**.

***Aat*II** a type 2 **restriction endonuclease**; recognition sequence: GACGT↑C.

AAU a codon in mRNA for L-asparagine.

Ab *abbr. for* antibody.

abamectin *or* **avermectin B_1** a metabolite of *Streptomyces avermitilis* used as an acaricide, insecticide, and a veterinary anthelmintic.

A-band an anisotropic band in a **sarcomere**.

Abbe refractometer a **refractometer** in which the critical angle for total reflection at the interface of a film of liquid between two similar glass prisms is used in determining the refractive index of the liquid. [After Ernst Abbe (1840–1905), German physicist famous for his researches in optics.]

ABC *abbr. for* **1** antigen-binding capacity. **2** ATP-binding cassette (*see* **ABC transporter**).

ABC model a model for specification of floral organs especially in *Arabidopsis thaliana*. It views the floral primordium as comprising four whorls whose developmental fate is determined by the concentric and combinatorial activity of three classes of gene, denoted A, B, and C, which encode transcription factors. Class A determines the fate of whorls 1 and 2 (sepals and petals, respectively) and requires the *APETALA2* gene (*AP2*); class B determines whorls 2 and 3 (petals and stamens, respectively) and requires the *PISTILLATA* (*PI*) and *APETALA3* (*AP3*) genes; class C determines whorl 4 (carpels) and requires the *AGAMOUS* gene (*AG*). These genes are described as ‘homeotic’ even though they encode transcription factors that contain a **MADS box** instead of homeobox domains. Homologues of these genes occur in other plants.

ABCR *abbr. for* ATP-binding cassette transporter retina; *other name*: rim protein. A protein found in the disc membrane of the outer segment of photoreceptor cells of the retina. It consists of 2273 amino acids, and is presumed to function in the transport of retinoids. Mutations in the ABCR gene, at 1p21-p23, are associated with Stargardt and age-related macular dystrophies. *See* **Stargardt macular dystrophy**.

ABC transporter a membrane transport protein having the ABC molecular domain, named after ATP-binding cassette, characteristic of all members of a large superfamily of membrane transport proteins that hydrolyse ATP and transfer a diverse array of small molecules across membranes. *See also* **CFTR**, **MDR protein**, **sugar transporter**.

ABC transporter retina *see* **ABCR**; *see also* **Stargardt macular dystrophy**.

abductin an insoluble, rubber-like protein from the internal triangular hinge ligament of scallops.

Abe *symbol for* abequose.

abequose *symbol*: Abe; 3,6-dideoxy-D-*xylo*-hexose; 3,6-dideoxy-D-galactose; a deoxysugar that occurs, e.g., in O-specific chains of lipopolysaccharides in certain serotypes of *Salmonella*. For the L enantiomer *see* **colitose**.

abetalipoproteinemia *or (Brit.)* **abetalipoproteinaemia** an autosomal recessive disorder in which plasma lipoproteins lack **apolipoprotein B**. There is defective assembly and secretion both of chylomicrons in intestinal mucosa and of very-low-density lipoproteins in the liver. The cause is a deficiency of the 88 kDa subunit of **microsomal triglyceride transfer protein**.

ABH antigens one of the systems of **blood group** antigens having determinants associated with oligosaccharide structures. It is the basis of the **ABO system**, which was the first human blood group antigen system to be detected, by Austrian-born US pathologist Karl Landsteiner (1868–1943) in 1901, and it remains the most important in blood transfusion. Individuals having neither A nor B antigen express the H antigen, the product of an independent gene belonging to the Hh system. Antigens of the ABH system are oligosaccharide chains, in the erythrocyte carried on band 3 (the anion transporter) and band 4.5 (the glucose transporter), or on ceramide. A highly branched *N*-glycan, consisting of a trimannosyl-di-*N*-acetyl-chitobiosyl core with Gal(*β*1-4)GlcNAc(*β*1-3) repeats, forms the basis of ABH antigens. The H determinant is the precursor; antigen A is formed by addition of *N*-acetyl-D-galactosamine by fucosylgalactose *α*-*N*-acetylgalactosaminyltransferase (EC 2.4.1.40); antigen B is formed by addition of D-galactose by fucosylglycoprotein 3-*α*-galactosyltransferase (EC 2.4.1.37). The terminal sugar residues of importance are: H determinant, Fuc(*α*1-2)Gal*β*-R; A determinant, GalNAc(*α*1-3)(Fuc*α*1-2)Gal*β*-R; B determinant, Gal(*α*1-3)(Fuc*α*1-2)Gal*β*-R. The enzyme responsible for adding the terminal fucosyl residue of the H determinant is galactoside 2-*α*-L-fucosyltransferase (EC 2.4.1.69). *See also* **A-transferase, B-transferase**.

abietic acid a plant terpene acid present in the nonvolatile residue of pine oil.

ab initio *Latin* from first principles; literally it means 'from the beginning'.

***ab initio* gene prediction** the prediction of genes in uncharacterized nucleotide sequences using only characteristics of the sequence (codon usage, compositional bias, etc.) – that is, without direct reference to other sequences.

***ab initio* protein structure prediction** the prediction of the structure of proteins using only properties of the amino-acid sequence (solvation potentials, secondary structure propensities, etc.) – that is, without direct reference to the structure of known homologues.

abiogenesis *or* **spontaneous generation** the discredited doctrine that living organisms can arise from nonliving materials under current conditions. *Compare* **biogenesis** (def. 2).

abiotic characterized by the absence of life.

abl an oncogene from murine Abelson leukemia virus. The human equivalent is *ABL* (locus at 9q34), which encodes a tyrosine protein kinase. In humans, inappropriate activation of *ABL* occurs via a reciprocal translocation between chromosomes 9 and 22 in which *ABL* is joined at the **breakpoint cluster region** (bcr) of the *ph1* gene on chromosome 22(q11), resulting in an altered chromosome 22, referred to as the **Philadelphia chromosome** (Ph^1). The protein product of the spliced genes in the Ph^1 chromosome is a molecule of 210 kDa, which has increased tyrosine kinase activity. The Ph^1 chromosome occurs in most patients with chronic myelogenous leukemia. c-Abl can potentially regulate cell growth and may participate in growth regulation at multiple cellular locations, interacting with different cell components. It contains SH2 and SH3 domains (*see* **SH domains**) and also domains involved in binding to F-actin and DNA, and occurs in both cytoplasmic and nuclear locations. Its DNA-binding activity appears to be cell-cycle-regulated by Cdc2-mediated phosphorylation; it binds the **retinoblastoma protein** indicating involvement in transcriptional regulation.

ablation 1 *(in surgery)* the removal or destruction of tissue by a surgical procedure. **2** *(in genetics)* a technique for the removal of a tissue or a particular cell type during development. It depends on the tissue-specific expression of a toxin gene such as diphtheria A (*dipA*) in a transgenic organism.

ABM *abbr. for* 2-aminobenzyloxymethyl, a group used for derivatizing cellulose or paper. It is converted by diazotization into **DBM**.

abortive complex *or* **dead-end complex** *or* **nonproductive complex** any enzyme–substrate complex in which the substrate is bound to the enzyme in a manner that renders catalysis impossible so that products cannot be formed.

abortive infection infection of a bacterium by phage lacking phage DNA, e.g. in generalized **transduction**.

abortive transconjugate *see* **transconjugate**.

abortive transduction a type of **transduction** in which the donor DNA is not integrated with the recipient chromosome but persists as a nonreplicating fragment that can function physiologically and can be transmitted to one daughter cell at each cell division.

ABO system one of the systems of human **blood groups**, of great importance in blood transfusion because human plasma contains natural antibodies against A and B blood group antigens of the ABH system (*see* **ABH antigens**). The antigens on the red blood cells and the plasma antibodies corresponding to the various phenotypes are shown in the table. *See also* **A-transferase**, **B-transferase**, **O antigen** (def. 2).

Phenotype (blood group)	Antigen on red cells	Antibody in plasma
A	A	anti-B
B	B	anti-A
AB	A and B	neither
O	H	anti-A + anti-B

ABP1 *abbr. for* **auxin-binding protein 1**.

Abri a neurotoxic 34-residue polypeptide, derived from a mutant putative transmembrane precursor, that forms amyloid fibrils in the brain in familial British dementia.

abrin a highly toxic ~65 kDa glycoprotein obtained from the seeds of jequirity, or Indian liquorice (*Abrus precatorius* L.), a tropical Asian vine that also occurs in Florida. It consists of an ~30 kDa acidic A chain, and an ~35 kDa neutral B chain, held together by disulfide bonds. The A chain is a powerful inhibitor of protein synthesis, while the B chain functions as a carrier to bind abrin to the membrane, and perhaps to assist penetration of the A chain into the cell. One well-chewed seed can be fatal. The A and B chains are derived from a common 528 amino acid 59.24 kDa precursor. *Compare* **abrine**, **ricin**. *See also* **ribosome-inactivating protein**.

abrine *trivial name for* N^{α}-methyl-L-tryptophan, *α*-methylamino-amino-*β*-(3-indole)propionic acid; an imino acid obtained from seeds of jequirity (*Abrus precatorius*). Not to be confused with **abrin**.

abscisic acid *or (formerly)* **abscisin II** *or* **dormin** *abbr*.: ABA; 5-(1-hydroxy-2,6,6-trimethyl-4-oxocyclohex-2-en-1-yl)-3-methylpenta-2,4-dienoic acid; a chiral sesquiterpene. The naturally occurring form, the 2*Z*,4*E*,*S* isomer, also designated (*S*)-abscisic acid, is a phytohormone formed by the degradation of carotenoids. It controls abscission in flowers and fruit but probably not in leaves, and is also implicated in geotropism, stomatal closure, bud dormancy, dormancy of seeds requiring stratification (i.e. those that will only germinate after exposure to low temperatures), and possibly tuberization.



abscissa the horizontal or *x* coordinate in a plane rectangular (Cartesian) coordinate system. *Compare* **ordinate**.

abscission the natural shedding of leaves, fruits, and other parts by a plant.

absolute **1** pure, unmixed; e.g. absolute alcohol. **2** not relative; e.g. absolute configuration. **3** describing a measurement defined in fundamental units of mass, length, and time that does not depend on the characteristics of the measuring apparatus; e.g. absolute temperature.

absolute alcohol *the common name for* pure ethanol, i.e. ethanol that has been freed of water. It may contain small amounts of benzene that have been added to aid in removing water. Substances may be added to absolute alcohol to render it unfit for human consumption and hence free of excise duty: **industrial spirit** contains 5% v/v methanol, while **methylated spirit** also contains pyridine, petroleum oil, and methyl violet dye, and **surgical spirit** also contains castor oil, diethyl phthalate, and methyl salicylate.

absolute configuration the actual three-dimensional arrangement of the atoms in a chiral molecule.

absolute reaction rate theory a theory that sets out to predict the absolute reaction rate of a chemical reaction from the quantum mechanical description of the potential energy changes during the interaction between chemical species. It is most widely drawn upon in applying thermodynamic reasoning to equilibria between reactants in the ground state and chemical species in the activated state or transition state.

absolute temperature *see* **thermodynamic temperature**.

absolute zero zero **thermodynamic temperature**, i.e. 0 K or –273.15 °C.

absorb *see* **absorption**.

absorbance *symbol*: *A*; a measure of the ability of a substance or a solution to absorb electromagnetic radiation incident upon it. It equals the logarithm of the ratio of the radiant power of the incident radiation, Φ_0, to the radiant power of the transmitted radiation, Φ. For a solution, absorbance is expressed as the logarithm of the ratio of the radiant power of light transmitted through the reference sample to that of the light transmitted through the solution, the observations being made using identical cells. (Traditionally, radiant intensity was measured instead of radiant power, which is now the accepted form.) Two quantities are defined: **(decadic) absorbance** (*symbol*: A_{10} *or* A), and **napierian absorbance** (*symbol*: A_e *or* B).

$$A_{10} = \lg(\Phi_0/\Phi) = \lg T^{-1} = -\lg(1-\alpha), \text{ and}$$

$$A_e = \ln(\Phi_0/\Phi) = \ln T^{-1} = -\ln(1-\alpha),$$

where T is the (internal) **transmittance** and α is the **absorptance**. These definitions suppose that all the light incident upon the sample is either transmitted or absorbed, reflection and scattering being negligible. The more general term attenuance should be used when scattering is considerable, as when the quantity $\lg(\Phi_0/\Phi)$ is measured to estimate the cell density of a culture. The older terms **absorbancy**, **extinction**, and **optical density** should no longer be used. *Compare* **absorption coefficient**.

absorbancy *or* **absorbency** *(formerly) an alternative term (no longer recommended) for* **absorbance**.

absorbate a substance that is absorbed into another substance.

absorbed dose *(in radiation physics)* a measure of the energy deposition produced by **ionizing radiation** in any (specified) medium as a result of **ion-pair** formation. The CGS unit of absorbed dose is the **rad**; the SI derived unit is the **gray** (*symbol*: Gy); *compare* **exposure** (def. 3). *See also* **dose equivalent**, **dose rate**.

absorbence *a variant spelling of* **absorbance**.

absorbent **1** a substance that absorbs another substance. **2** having the capacity to absorb another substance.

absorptance *or* **absorption factor** *symbol*: α; the ratio of absorbed to incident radiant or luminous flux. A dimensionless physical quantity given by $\alpha = \Phi_{abs}/\Phi_0$, where Φ_0 and Φ_{abs} are the incident and absorbed radiant powers, respectively.

absorptiometer **1** an apparatus, frequently a photoelectric device, for measuring light **absorption** by solids, liquids, or gases. **2** an apparatus for measuring the amount of gas absorbed by a liquid.

absorption **1** the act or process whereby one substance, such as a gas or liquid, is taken up by or permeates another liquid or solid. *Compare* **adsorption**. **2** the retention by a material of energy removed from electromagnetic radiation passing through the material. **3** the removal of any form of radiation, or the reduction of its energy, on passing through matter. **4** the process whereby a neutron or other particle is captured by an atomic nucleus. **5 a** *(in cellular physiology)* the uptake of fluids by living cells or tissues. **b** *(in animal physiology)* the totality of the processes involved in causing water, the products of digestion, and exogenous substances of low molecular mass such as drugs, salts, vitamins, etc. to pass from the lumen of the gastrointestinal tract into the blood and lymph. **c** *(in plant physiology)* the uptake of water and dissolved salts through the roots. **6** *(in immunology)* the process of removing a particular antibody (or antigen) from a mixture by adding the complementary antigen (or antibody) and discarding the antigen–antibody complex so formed. *Compare* **immunosorption**.

absorption band *or* **absorption line** a region of darkness or absorption of radiation in the spectrum of heterochromatic radiation that has passed through an absorbing material.

absorption coefficient four different coefficients are defined. The **(linear) decadic absorption coefficient** (*symbol*: a) is defined by $a = A_{10}/l$; units m^{-1}. The **(linear) napierian absorption coefficient** (*symbol*: α) is defined by $\alpha = A_e/l$; units m^{-1}. The **molar (decadic) absorption coefficient** (*symbol*: ε) is defined by $\varepsilon = a/c = A_{10}/cl$; units m^2 mol^{-1}. The **molar napierian absorption coefficient** (*symbol*: κ) is defined by $\kappa = \alpha/c = A_e/l$. A_{10} and A_e are the decadic and napierian absorbances respectively (*see* **absorbance**), l = path length, and c = amount-of-substance concentration.

absorption cross-section the probability that a photon passing through a molecule will be absorbed by that molecule multiplied by the average cross-sectional area of the molecule. The **net absorption cross-section** (*symbol*: σ_{net}) is defined by $\sigma_{net} = \kappa/N_A$, where κ is the molar napierian **absorption coefficient** and N_A is the Avogadro constant.

absorption, distribution, metabolism, elimination, and toxicity *abbr.*: ADME/Tox; procedures for assessing how pharmaceutical entities are taken up by the body, where they go in the body, the chemical changes they undergo during these processes, how they are excreted, and the toxicological effects they might have. ADME/Tox is an essential component of drug-safety testing.

absorption factor *an alternative name for* **absorptance**.

absorption index *symbol*: k; it is given by $k = \alpha/4\pi\tilde{\nu}$, where α is the (linear) napierian **absorption coefficient** and $\tilde{\nu}$ the wavenumber in vacuum of the radiation.

absorption line *an alternative name for* **absorption band**.

absorption spectrometry the process of measuring an absorption spectrum with a **spectrometer**. **Absorption spectrophotometry** is a related process employing a spectrophotometer. *See also* **absorbance**, **absorptivity**.

absorption spectroscopy the **spectroscopy** of an absorption spectrum.

absorption spectrum a **spectrum** produced when electromagnetic radiation is absorbed by a sample. The frequencies of the radiation absorbed are those able to excite the atoms or molecules of the sample from their ground states to excited states. The frequency, ν, at which a particular absorption line occurs depends on the energy difference, ΔE, between that of a particular ground state and that of the corresponding excited state. It is given by $\nu = \Delta E/h$, where h is the Planck constant. *Compare* **emission spectrum**.

absorptivity a measure of the ability of a material to absorb electromagnetic radiation. It equals the absorptance of a sample of the material divided by the optical path-length. For very low attenuance, it approximates the absorption coefficient. Use of the term is not recommended.

Abu *symbol for* a residue of the α-amino acid L-2-aminobutanoic acid L-α-aminobutyric acid.

A$_2$bu *or* **Dab** *symbol for* a residue of the α,γ-diamino acid L-α,γ-diaminobutyric acid, L-2,4-diaminobutanoic acid.

abzyme *abbr. for* antibody enzyme (an antibody with enzyme activity; also known as catalytic monoclonal antibody).

a.c. *or* **AC** *or* ***ac*** *abbr. for* alternating current.

Ac *symbol for* **1** actinium. **2** the acetyl group, CH_3CO–.

ACA a codon in mRNA for L-threonine.

acanthosome an organelle of fibroblasts isolated from the dermis of hairless mice after chronic UV irradiation. It exists as a spinous membranous vesicle.

acarbose a pseudotetrasaccharide, *O*-4,6-dideoxy-4-[[[1*S*-(1*α*,4*α*,5*β*,6*α*)]-4,5,6-trihydroxy-3-(hydroxymethyl)-2-cyclohexen-1-yl]amino]-*α*-D-glucopyranosyl-(1→4)-*O*-*α*-D-glucopyranosyl-(1→4)-glucose, that inhibits *α*-glucosidase, thereby reducing gastrointestinal absorption of glucose. It is a putative antidiabetic agent.



acaricide a substance or mixture of substances intended to destroy or prevent infestation with mites and ticks.

acatalasemia *or (Brit.)* **acatalasaemia** *or* **Takahara disease** a rare, generally benign condition in which erythrocyte catalase activity is less than 1% of normal. It is sometimes associated with ulcerating lesions in the mouth. It is caused by a splice junction mutation in the catalase gene locus at 11p13.

ACC **1** a codon in mRNA for L-threonine. **2** *abbr. for* 1-aminocyclopropane-1-carboxylic acid.

***Acc*I** a type 2 **restriction endonuclease**; recognition sequence: GT↑[AC][GT]AC.

***Acc*II** a type 2 **restriction endonuclease**; recognition sequence: CG↑CG. *Fnu*DII is an **isoschizomer**.

***Acc*III** a type 2 **restriction endonuclease**; recognition sequence: T↑CCGGA. *Bsp*MII is an **isoschizomer**.

a.c. calorimetry a technique in which the thermal response of a sample to an oscillating heat signal is measured in the form of a temperature wave propagating through the sample. The technique allows the measurement of the heat capacity of the sample on both cooling and heating and the monitoring of its isothermal time-dependence. It is useful in the study of phase transitions in solids and in gel to liquid-crystal systems.

accelerator **1** *(in chemistry)* **catalyst**, especially one that increases the rate of a polymerization reaction. **2** *(in physics)* a device or machine used for imparting high kinetic energy to charged subatomic particles, e.g. electrons, protons, or alpha particles, by means of electric and/or magnetic fields.

accelerator globulin *an alternative name for* factor V. *See* **blood coagulation**.

accelerin *an alternative name for* factor Va. *See* **blood coagulation**.

acceptor **1** *(in chemistry)* a chemical entity that in a chemical reaction receives an electron, atom, or group of atoms. *Compare* **donor**, **donor atom**. *See also* **electron acceptor**. **2** *(in physiology)* a receptor that binds a hormone without a biological response being demonstrable. **3** *(in pharmacology)* a receptor that binds a drug but has no identified endogenous ligand.

accession number a systematic (computer-readable) number or code that uniquely identifies an entry in a particular database. Accession numbers are assigned when entries are first added to a database and should remain static between updates, providing a reliable means of locating them in subsequent releases. For example, P02699 identifies bovine rhodopsin in the **Swiss-Prot** database, and IPR000276 identifies the rhodopsin-like G protein-coupled receptor superfamily in InterPro.

accessory cell any one of various types of cell that assist in the immune response. The term includes **antigen-presenting cell**, **basophil**, **eosinophil**, **mast cell**, and **platelet**.

accessory chromosome *an alternative name for* **1** a **B chromosome**. **2** a **sex chromosome**.

accessory DNA surplus DNA present in certain cells or during certain stages of cell development owing, for example, to **gene amplification**.

accessory food factor *or* **accessory growth factor** a term originally used to describe any unknown substance – subsequently called **vitamin** – found in small amounts in some foods, such as milk, that was necessary for the normal growth of animals fed on diets of purified carbohydrates, fats, proteins, and salts.

accessory pigment any of the pigments, such as the yellow, red, or purple **carotenoids** and the red or blue **phycobiliproteins** in photosynthetic cells. The carotenoids are always present, whereas the phycobiliproteins occur only in algae belonging to the Rhodophyceae, the Cyanophyceae, and the Cryptophyceae. Strictly speaking, chlorophyll b is also an accessory pigment.

ACC oxidase an enzyme present in plant tissues that catalyses the Fe^{2+}- and ascorbate-dependent oxidation of **1-aminocyclopropane-1-carboxylic acid** (ACC) to ethylene, CO_2, HCN, and H_2O. It is a highly unstable monomer (35 kDa) that is inhibited by Co^{2+}. Its activity increases under conditions of stress and at certain developmental stages (e.g. during fruit ripening).

ACC synthase EC 4.4.1.14; *systematic name: S*-adenosyl-L-methionine methylthioadenosine lyase; an enzyme present in plant tissues that catalyses the pyridoxal phosphate-dependent conversion of *S*-adenosylmethionine to **1-aminocyclopropane-1-carboxylic acid** (ACC) and 5′-methylthioadenosine. It has been cloned from various fruits – zucchini (courgette), tomato, apple – and has 48–97% sequence identity in different plants. Tomato contains several genes for the enzyme that are differentially regulated and expressed in response to wounding, ripening, or various stresses.

accuracy a measure of the proximity of a measured value to a true value. *Compare* **precision**.

ACE *abbr. for* **1** amplification control element (a DNA sequence in vertebrates that functions as the origin for **amplification**). **2** **angiotensin converting enzyme**.

ACeDB *or* **acedb** *abbr. for* a *Caenorhabditis elegans* database; *see* **genome database**.

A cell *or (formerly)* **alpha cell** *or* ***α*** **cell** one of the three main histological cell types found in the islets of Langerhans of the pancreas, also found in the gastric oxyntic mucosa. A cells produce, store, and secrete the hormone **glucagon**.

A_1 cell *(formerly) an alternative name for* **D cell**.

aceruloplasminemia *or (Brit.)* **acaeruloplasminaemia** a rare autosomal recessive disorder in which plasma **ceruloplasmin** is severely deficient, characterized by neurological abnormalities and systemic hemosiderosis. Any of at least six mutations in a locus at 3q21-q24 can cause the disease.

Aces *or* **ACES** *abbr. for N*-(2-acetamido)-2-aminoethane sulfonic acid; 2-[(2-amino-2-oxoethyl)amino]ethane sulfonic acid; a **Good buffer substance**, pK_a (20°C) = 6.9.



acesulfame 6-methyl-1,2,3-oxathiazin-4(3*H*)-one 2,2′-dioxide; a sweet-tasting material that, as the potassium salt, has been used in foods and cosmetics.



acetal any member of a class of organic compounds having the general formula $R^1HC(OR^3)OR^4$ or $R^1R^2C(OR^3)OR^4$ – in a **thioacetal** the corresponding formulae are $R^1HC(SR^3)SR^4$ or $R^1R^2C(SR^3)SR^4$ – where R^3 and R^4 are alkyl groups (or R^4 is H in a **hemiacetal** or **hemithioacetal**). An acetal molecule is formed by the acid-catalysed combination of the carbonyl group of an aldehyde or ketone molecule with either one or two alcohol (or mercaptan) molecules (which may be the same or different), or with a diol (or dithiol), by a reaction of the following general type, where X is O (or S in a mercaptan or dithiol):

$$R^1R^2C{=}O + R^3XH = R^1R^2C(XR^3)OH.$$

The hemiacetal (or hemithioacetal) so formed may then undergo a further reaction:

$$R^1R^2C(XR^3)OH + R^3XH = R^1R^2C(XR^3)_2 + H_2O$$

or

$$R^1R^2C(XR^3)OH + R^4XH = R^1R^2C(XR^3)XR^4 + H_2O.$$

In carbohydrates such compounds are formed at the carbonyl group of the acyclic form of a saccharide or saccharide derivative. The terms ‘ketal’ (or ‘thioketal’) and ‘hemiketal’ (or ‘thiohemiketal’), may be applied respectively to any acetal of general formula $R^1R^2C(XR^3)XR^4$ or $R^1R^2C(OH)XR^3$, i.e. to those derived from ketones. These terms, at one time abandoned, have recently been reintroduced as the respective names of subclasses of acetals and hemiacetals and as functional class names.

acetaminophen *or* **paracetamol** 4-acetamidophenol; *N*-acetyl-*p*-aminophenol; *N*-(4-hydroxyphenyl)acetamide; a drug widely used as an analgesic and antipyretic. It inhibits formation of prostaglandins within, but not outside the brain. It is metabolized within the liver mostly to glucuronide and sulfate conjugates. A small amount is oxidized to a highly reactive intermediate, *N*-acetylbenzoquinoneimine, that is normally detoxified by conjugation with glutathione. If it is produced in excess of the capacity of the liver to detoxify it, hepatic necrosis can result. It can be administered with methionine, which increases glutathione in the liver. *N*-Acetylcysteine is administered in cases of poisoning to act as a glutathione substitute. *Proprietary names include*: Panadol, Tylenol.

acetate **1** the traditional name for ethanoate; the anion, CH_3COO^-, derived from acetic acid (ethanoic acid). **2** any salt or ester of acetic acid.

acetate–CoA ligase EC 6.2.1.1; *systematic name*: acetate:CoA ligase (AMP-forming); *other names*: acetyl–CoA synthetase; acyl-activating enzyme; acetate thiokinase; acetyl-activating enzyme. An enzyme that catalyses a reaction between ATP, acetate, and CoA to form AMP, pyrophosphate, and acetyl-CoA. It is an important enzyme in organisms (e.g. *Escherichia coli*, many fungi, protozoans, algae) that utilize acetate as a carbon source. Distinguish from acetate–CoA ligase (ADP-forming), EC 6.2.1.13.

acetate thiokinase *see* **acetate–CoA ligase**.

acetazolamide an inhibitor of carbonic anhydrase that is useful as a diuretic. It acts by preventing bicarbonate reabsorption in the proximal tubules of the kidney.



(+)aceto+ *comb. form* denoting the acyl group derived from acetic acid.

acetoacetate–CoA ligase EC 6.2.1.16; *other name*: acetoacetyl-CoA synthetase; an enzyme that catalyses the formation of acetoacetyl-CoA from ATP, acetoacetate, and CoA with release of AMP and pyrophosphate. In bacteria that carboxylate acetone to acetoacetate, it activates the latter for further metabolism. It is also present in animals, but utilization of blood acetoacetate after its entry into tissues involves **3-oxoacid CoA-transferase**.

acetoacetyl acetyltransferase *see* **acetyl-CoA *C*-acetyltransferase**.

acetoacetyl-CoA synthetase *see* **acetoacetate–CoA ligase**.

acetoacetyl-CoA thiolase *see* **acetyl-CoA *C*-acetyltransferase**.

acetogenin any substance built up of two-carbon units that may formally be considered to derive from a polyacetyl chain intermediate; the carbon atoms derived from the carboxyl carbon atoms of acetic acid frequently remain oxidized. It is not a recommended term. *See* **polyketide**.

acetoin 3-hydroxy-2-butanone; a compound formed by action of acetolactate decarboxylase (EC 4.1.1.5) and, under some conditions, pyruvate decarboxylase (EC 4.1.1.1).



acetone body *see* **ketone body**.

acetone powder any preparation of ruptured cells obtained from a tissue or single-celled organisms that involves dehydration with acetone to form a powder. It is relatively stable, and is used in the preparation of some enzymes.

acetyl the acyl group ethanoyl, $CH_3CO–$, derived from acetic acid (= ethanoic acid).

1-*O*-acetyl-ADPribose *abbr.* OAADPr; a metabolite produced by SIRT2-like or other enzymes from acetylated histone and NAD with release of nicotinamide. Its function is not known. *See* **Sir**.

***N*-acetylaspartate** *abbr.*: NAA; a derivative of aspartic acid, synthesized by *N*-acetyl transferase and degraded by aspartoacylase, present at high concentration in brain grey matter. Its function is enigmatic but its distribution is similar to that of *N*-acetylaspartylglutamate, which is a putative neurotransmitter. Canavan disease results from mutations that decrease aspartoacylase activity and hence increase concentrations of NAA in cerebrospinal fluid and urine.

***N*-acetylaspartylglutamate** *see* ***N*-acetylaspartate**.

acetylation an **acylation** reaction in which an acetyl group, $CH_3CO–$, is introduced into an organic compound. **—acetylated** *adj.*

acetylation coenzyme *the original name for* **coenzyme A**.

acetylcholine *abbr.*: ACh; the acetyl ester of choline; it is a chemical transmitter in both the peripheral and central nervous system. *See* **neurotransmitters**.



acetylcholine binding protein *abbr.*: AChBP; a soluble protein that binds acetylcholine (ACh). It is homologous with, and has similar ligand-binding characteristics to, the extracellular domain of the alpha subunit of the acetylcholine receptor. It forms a homopentamer.

acetylcholine receptor *see* **cholinoceptor**.

acetylcholinesterase *abbr.*: AChE; EC 3.1.1.7; *systematic name*: acetylcholine acetylhydrolase; *other names*: true cholinesterase; cholinesterase I; an esterase enzyme that catalyses the hydrolysis of acetylcholine to choline and acetate; it also acts on a variety of acetic esters and catalyses transacetylations. It is found in or attached to cellular or basement membranes of presynaptic cholinergic neurons and postsynaptic cholinoceptive cells. A soluble form occurs in cerebrospinal fluid and within cholinergic neurons. It is inhibited by a number of drugs, e.g. physostigmine, and by several **organophosphates**. The 3-D structure is known for fragments obtained from the electric ray (fish).

acetylcholine transporter protein an integral membrane protein of synaptic vesicles of cholinergic neurons. It transports newly synthesized acetylcholine molecules into the synaptic vesicles in exchange for protons, thereby replenishing vesicular stores of the neurotransmitter.

acetyl-coA *abbr. for* **acetyl coenzyme A**.

acetyl-CoA *C*-acetyltransferase EC 2.3.1.9; *other names*: acetoacetyl acetyltransferase; acetoacetyl-CoA thiolase; an enzyme that catalyses the formation of two molecules of acetyl-CoA from CoA and acetoacetyl-CoA. During beta oxidation it catalyses the formation of acetyl-CoA from acetoacetyl-CoA, whereas it acts in the reverse direction to form acetoacetyl-CoA during ketogenesis.

It is important in regulating the metabolic pathways for the production of acids, i.e. acetate, butyrate, or solvents, i.e. acetone, butanol, ethanol, during the growth of *Clostridium acetobutylicum*. Reduced activity of the enzyme favours production of acetate and ethanol, while increased activity favours production of butyric acid, butanol, and acetone.

acetyl-CoA C-acyltransferase EC 2.3.1.16; *systematic name*: acyl-CoA:acetyl-CoA *C*-acyltransferase; *other names*: 3-ketoacyl-CoA thiolase; *β*-ketothiolase; an enzyme that catalyses the formation of acyl-CoA and acetyl-CoA from CoA and 3-oxoacyl-CoA. This is the concluding reaction of each cycle of the fatty acid oxidation pathway (**beta oxidation**). Different enzymes exist in the mitochondrion and peroxisome, both being included in the **thiolase** family.

acetyl-CoA carboxylase EC 6.4.1.2; *systematic name*: acetyl-CoA:carbon-dioxide ligase (ADP-forming); a multienzyme complex involved in the formation of **malonyl-CoA**, the first step in fatty-acid biosynthesis. It catalyses a reaction between ATP, acetyl-CoA, and HCO_3^- to form ADP, orthophosphate, and malonyl-CoA. Biotin is a cofactor. In bacteria it is a heterohexamer of biotin-carboxyl-carrier-protein, biotin carboxylase, and a 2:2 complex of the two subunits of carboxyl transferase. Biotin carboxylase (EC 6.3.4.14) catalyses the reaction between ATP, biotin-carboxyl-carrier-protein, and CO_2 to form ADP, orthophosphate, and carboxybiotin-carboxyl-carrier-protein. The carbonyl group of the latter is then transferred to acetyl-CoA by carboxyl transferase, thus forming malonyl-CoA. In mammals the activity is part of a trifunctional polypeptide that contains carboxyl carrier protein, biotin carboxylase (EC 6.3.4.14), and acetyl-CoA carboxylase (EC 6.4.1.2) domains.

[acetyl-CoA carboxylase] kinase EC 2.7.1.128; an enzyme that catalyses the phosphorylation by ATP of [acetyl-CoA carboxylase] with release of ADP. This phosphorylation step is one of the regulatory mechanisms for acetyl-CoA carboxylase, causing that enzyme to dissociate from an active polymeric form to an inactive monomeric form.

[acetyl-CoA carboxylase] phosphatase EC 3.1.3.44; an enzyme that catalyses the hydrolysis of phosphate from [acetyl-CoA carboxylase] phosphate. It reverses the phosphorylation catalysed by [acetyl-CoA carboxylase] kinase.

acetyl coenzyme A *abbr.*: acetyl-CoA; a derivative of **coenzyme A** in which the sulfhydryl group is acetylated. Originally termed 'active acetate', it is an important metabolite, derived from pathways such as glycolysis, fatty-acid oxidation, and degradative metabolism of some amino acids. It is further metabolized by the **tricarboxylic-acid cycle** and represents a key intermediate in lipid and terpenoid biosynthesis and other anabolic reactions.



***N*-acetylcysteine** *or* ***N*-acetyl-L-cysteine** a thiol-protecting agent used intravenously as an antidote in acetaminophen poisoning. It acts by enhancing glutathione synthesis, thereby increasing the capacity for detoxification and excretion of acetaminophen as a **mercapturic acid**. Methionine can be similarly used. It also has **mucolytic** properties, and is used in aiding the isolation of mycobacteria from sputum.

acetylene *the nonsystematic name for* **ethyne**.

***N*-acetylgalactosamine** *symbol*: D-Gal*p*NAc; *abbr.*: NAGA; the D isomer, 2-acetamido-2-deoxy-D-galactopyranose, is a common structural unit of oligosaccharides, such as the blood-group substances and *O*-linked glycoproteins, in which the sugar is in glycosidic linkage to a protein or serine residue, or, in the case of the blood-group substances, to a lipid hydroxyl group. The reactant in synthetic reactions is UDP-*N*-acetylgalactosamine, which is formed by epimerization of *N*-acetylglucosamine.



β-D-anomer

***N*-acetylgalactosamine-4-sulfatase** EC 3.1.6.12; *other names*: arylsulfatase B; chondroitinsulfatase; chondroitinase; an enzyme that hydrolyses the 4-sulfate groups of the *N*-acetyl-D-galactosamine 4-sulfate units of chondroitin sulfate and dermatan sulfate. It is a lysosomal enzyme involved in the degradation of proteoglycans, which accumulate in Maroteaux–Lamy syndrome (**mucopolysaccharidosis VI**), a storage disease resulting from a deficiency of the enzyme.

***N*-acetylgalactosamine-6-sulfatase** EC 3.1.6.4; *other names*: chondroitinsulfatase; chondroitinase; galactose-6-sulfate sulfatase; an enzyme that hydrolyses the 6-sulfate groups of the *N*-acetyl-D-galactosamine 6-sulfate units of chondroitin sulfate, and also the D-galactose 6-sulfate units of keratan sulfate. It is a lysosomal enzyme involved in the degradation of proteoglycans. Keratan sulfate and chondroitin 6-sulfate accumulate in Morquio A syndrome, a storage disease resulting from a deficiency of the enzyme.

***N*-acetylgalactosaminidase** EC 3.2.1.53; either of two lysosomal enzymes that catalyse the hydrolysis of respectively *α*- and *β*-linked terminal nonreducing *N*-acetyl-D-galactosamine residues. Deficiency of *α*-*N*-acetylgalactosaminidase is associated with a storage disease (Schindler disease) in which sialyloligosaccharides are found in urine.

***N*-acetylglucosamine** *symbol*: D-Glc*p*NAc; *abbr.*: NAG; the D isomer, 2-acetamido-2-deoxy-D-glucopyranose, is a common structural unit of plant glycoproteins and of many animal and bacterial glycoproteins. It is often the terminal sugar of an oligosaccharide moiety of a glycoprotein, linked glycosidically to the amide nitrogen of a protein asparagine residue. The acetyl group is introduced in a reaction between acetyl-CoA and glucosamine 6-phosphate to give *N*-acetylglucosamine 6-phosphate, which undergoes a mutase reaction to form *N*-acetylglucosamine 1-phosphate, from which UDP-*N*-acetylglucosamine is formed. The latter is the reactant in pathways of oligosaccharide synthesis and is also a precursor of *N*-acetylneuraminic acid (*see* **sialic acid**).

***N*-acetylglucosamine phosphotransferase** EC 2.7.1.69; *systematic name*: protein-N^{π}-phosphohistidine: sugar *N-pros*-phosphotransferase; *other name*: enzyme II of the phosphotransferase system; an enzyme that catalyses the reaction:

protein N^{π}-phosphohistidine + sugar =
protein histidine + sugar phosphate.

It is a component of the phospho*enol*pyruvate-dependent sugar phosphotransferase system, a major carbohydrate active-transport system; the phosphoryl group from phospho*enol*pyruvate is transferred to phosphoryl carrier protein **HPR** by enzyme I, and from



β-D-anomer

phospho-HPR to the sugar by enzyme II. It is an integral membrane protein.

***N*-acetylglucosamine-6-sulfatase** EC 3.1.6.14; an enzyme that catalyses the hydrolysis of sulfate groups of *N*-acetyl-D-glucosamine 6-sulfate units of heparan sulfate and keratan sulfate. It is a lysosomal glycoprotein. A deficiency is associated with the storage disease **mucopolysaccharidosis III**.

N*-acetylglucosaminidase** *abbr*.: NAG *(in clinical chemistry) an alternative name for β-N-acetylhexosaminidase**.

***N*⁴-(*β*-*N*-acetylglucosaminyl)-L-asparaginase** EC 3.5.1.26; *other names*: aspartylglucosylamine deaspartylase; aspartylglucosylaminase; glycosylasparaginase; an enzyme that catalyses the hydrolysis of N^4-(*β*-*N*-acetyl-D-glucosaminyl)-L-asparagine, released from glycoproteins, to *N*-acetyl-*β*-glucosaminylamine and L-aspartate. A deficiency of the enzyme results in the lysosomal storage disease, **aspartylglucosaminuria**, in which there is an accumulation of the enzyme's substrate.

***N*-acetylglucosaminyl transferase** any of various glycosyltransferase enzymes within the subclass EC 2.4.1 that transfer an *N*-acetylglucosaminyl residue from UDP-*N*-acetyl-glucosamine to an oligosaccharide, and which are important in oligosaccharide synthesis. An example is EC 2.4.1.144, *β*-1,4-mannosyl-glycoprotein *β*-1,4-*N*-acetylglucosaminyltransferase; *other name*: *N*-glycosyl-oligosaccharide-glycoprotein *N*-acetylglucosaminyltransferase III. It catalyses the addition of *N*-acetylglucosamine in *β*(1-4) linkage to the *β*-linked mannose of the trimannosyl core of *N*-linked sugar chains. It is a type II membrane protein of the Golgi stack. *See also* ***N*-acetyllactosamine synthase**, **lipopolysaccharide**, ***N*-acetylglucosaminyltransferase**, **UDP-*N*-acetylglucosamine-dolichyl phosphate-*N*-acetylglucosamine phosphotransferase**.

***β*⁶-*N*-acetylglucosaminyltransferase** *see* ***β*-1,3-galactosyl-*O*-glycosyl-glycoprotein *β*-1,6-*N*-acetylglucosaminyltransferase.**

***N*-acetylglutamate synthase** (*abbr.* AGS) *see* **amino-acid *N*-acetyltransferase.**

acetylglutamic acid the L isomer, *N*-acetyl-L-glutamic acid, is a key intermediate in ornithine formation in bacteria and plants. It is converted to *N*-acetyl-L-glutamic *c*-semialdehyde, from which *N*-acetyl-L-ornithine is formed in a transamination reaction. It activates **carbamoyl-phosphate synthase**, which catalyzes the synthesis of carbamoyl phosphate from ammonia and carbon dioxide, the first committed step in the urea cycle. It is formed from acetyl-CoA and glutamate by the action of amino acid *N*-acetyltransferase, EC 2.3.1.1.

***β*-*N*-acetylhexosaminidase** EC 3.2.1.52; *other names*: *β*-hexosaminidase; hexosaminidase; an enzyme that catalyses the hydrolysis of terminal nonreducing *N*-acetyl-D-hexosamine residues in *N*-acetyl-*β*-D-hexosaminides.

***N*-acetyllactosamine synthase** EC 2.4.1.90; *systematic name*: UDPgalactose:*N*-acetyl-D-glucosamine 4-*β*-D-galactosyltransferase; *other names*: *N*-acetylglucosamine *β*-(1→4)-galactosyltransferase; UDPgalactose-*N*-acetyl-glucosamine *β*-D-galactosyltransferase. An enzyme, located in the rough endoplasmic reticulum, that catalyses a reaction between UDPgalactose and *N*-acetyl-D-glucosamine to form UDP and *N*-acetyllactosamine. In humans the enzyme also has the activity of *β*-*N*-acetylglucosaminylglycopeptide *β*-1,4-galactosyltransferase (EC 2.4.1.38); *other names*: glycoprotein 4-*β*-galactosyltransferase;thyroidgalactosyltransferase; UDPgalactose– glycoprotein galactosyltransferase. It catalyses a reaction between UDPgalactose and *N*-acetyl-*β*-D-glucosaminylglycopeptide to form UDP and *β*-D-galactosyl-1,4-*N*-acetyl-*β*-D-glucosaminylglycopeptide. ***α*-Lactalbumin** is an allosteric regulator and converts this activity to **lactose synthase**.

***N*-acetylmuramoyl-L-alanine amidase** *see* **autolysin**.

***N*-acetylneuraminic acid** *see* **sialic acid**.

acetyloleoylglycerol *see* **oleoylacetylglycerol**.

acetylsalicylic acid *see* **aspirin**.

***N*-acetyl transferase** EC 2.3.1.2; acetyl-CoA–L-aspartate *N*-acetyl hydrolase; an enzyme that catalyses the synthesis of *N*-acetylaspartate.

ACF *abbr. for* **1** ATP-utilizing chromatin assembly and remodeling factor of ***Drosophila***. **2** APOBEC-1 complementation factor; a 65 kDa protein that contains three RNA-recognition motifs and is required for APOBEC-1 to edit apolipoprotein B pre-mRNA. *See* **apoB editing enzyme**.

ACG **1** a codon in mRNA for L-threonine. **2** *abbr. for* acycloguanosine (*see* **acyclovir**).

Ach *symbol for* the arachidoyl (i.e. eicosanoyl) group.

Δ_2Ach *symbol for* the (*all-Z*)-eicosa-8,11-dienoyl group; *see* **eicosadienoic acid**.

Δ_3Ach *symbol for* the (*all-Z*)-eicosa-5,8,11-trienoyl group; *see* **eicosatrienoic acid**.

Δ_4Ach *symbol for* the arachidonoyl (i.e.(*all-Z*)-eicosa-5,8,11,14-tetraenoyl) group; *see* **arachidonoyl**.

ACh *abbr. for* acetylcholine.

Achaete–Scute complex *see* **AS-C protein**.

achatin-1 an endogenous neuroexcitatory tetrapeptide, Gly-DPhe-Ala-Asp, isolated from the ganglia of the giant African snail, *Achatina fulica*.

AchBP *abbr. for* **acetylcholine binding protein**.

AChE *abbr. for* acetylcholinesterase.

achiral not **chiral**. **—achirality** *n.*

achlorhydria an inability to secrete gastric acid. It is a disorder, probably autoimmune, that is linked with pernicious anemia.

achondroplasia the most common form of dwarfism, inherited as an autosomal disorder. It is due mostly to one of two missense mutations in the fibroblast growth factor receptor-3 gene (***FGFR3***) locus at 4p16.3, which affect the transmembrane region of the receptor, causing activation of the receptor. Homozygosity is lethal in the neonatal period. Milder forms, called **hypochondroplasia**, are due to any of several missense mutations that affect the tyrosine kinase domain of this receptor and also activate it. **Pseudoachondroplasia** is caused by over 70 mutations at 19p13.1, within the gene for cartilage oligomeric matrix protein (COMP). These lead to accumulation of the mutant protein within chondrocytes.

achromic point the point in time during the action of amylase on starch at which the reaction mixture no longer gives a colour with iodine, i.e. the reaction has proceeded to the point when the starch has all been degraded at least as far as **achröodextrins**.

achröodextrin any **dextrin** that is small enough not to give a colour with iodine.

acid **1** in the Brønsted–Lowry concept, a molecular species having a tendency to lose a hydron forming a conjugate base, e.g.

$$\mathrm{A} \rightleftharpoons \mathrm{H}^+ + \mathrm{B};$$

$$\mathrm{HCl} \rightleftharpoons \mathrm{H}^+ + \mathrm{Cl}^-;$$

$$\mathrm{RCOOH} \rightleftharpoons \mathrm{H}^+ + \mathrm{RCOO}^-;$$

$$\mathrm{RNH_3}^+ \rightleftharpoons \mathrm{H}^+ + \mathrm{RNH_2}.$$

2 in the Lewis concept, a substance capable of accepting from a base an unshared pair of electrons, which then form a covalent chemical bond, e.g.

$$\mathrm{F_3B} + :\mathrm{NH_3} \leftrightarrow \mathrm{F_3B}^-\text{–}^+\mathrm{NH_3}.$$

acid anhydride any compound formed by the elimination of the elements of water from the acidic groups of two acids, e.g. acetic anhydride (two acetic acid molecules) or acetyl phosphate (one molecule each of acetic and phosphoric acids).

acid–base balance term descriptive of the hydrogen-ion status of the blood, the mechanisms that regulate it, and the causes of its deviation from normal.

acid–base catalysis catalysis of a chemical reaction in which either an acid or a base mediates the formation of a reactive intermediate.

acid–base titration a **titration** in which either acid or base is added to a solution and the progress of the titration is followed by pH measurements, either electrometrically or with the use of pH indicators.

acid box a peptide sequence that contains 4–8 acidic amino acid residues in a protein.

acid carboxypeptidase *see* **cysteine-type carboxypeptidase**.

acid ceramidase EC 3.5.1.23; *other name: N*-acylsphingosine deacylase; a lysosomal enzyme that catalyses the hydrolyis of ceramide to sphingosine and a fatty acid. Its activity requires sphingolipid activator proteins (i.e. saposins B and C) and negatively charged phospholipids. A genetic locus at 8p21.3-22 encodes a precursor that contains 395 amino acids and is proteolytically cleaved into an α subunit (≈13 kDa) and a β subunit (≈40 kDa) linked by a disulphide bridge. The β subunit is probably glycosylated. At least nine mutations in the gene are associated with various forms of a deficiency disease called Farber lipogranulomatosis. This is characterized by granuloma formation and lipid-laden macrophages in joints, subcutaneous tissue, larynx, and frequently also in liver, spleen, lungs, heart, and nervous system. *See* **saposin**.

acid dissociation constant *or* **acidity constant** *symbol*: K_a; the thermodynamic equilibrium constant for the dissociation of an **acid**. For a dilute solution of a weak acid, HA, dissociating in water according to the equilibrium:

$$\mathrm{HA} + \mathrm{H_2O} \rightleftharpoons \mathrm{H_3O^+} + \mathrm{A^-},$$

$$K_a = (a_{\mathrm{H_3O^+}} \times a_{\mathrm{A^-}})/a_{\mathrm{HA}}$$

where *a* is the **activity** of the species designated by the subscripts. The activity of the water has been omitted from the equation since it may be taken as unity for a dilute aqueous solution. K_a is a measure of the strength of the acid, i.e. of its ability to donate hydrons to water. *Compare* **basic dissociation constant**. *See also* **p*K***.

acid dye a **dye** containing an anionic acidic organic group that binds to and stains positively charged macromolecules.

acidemia *or (esp. Brit.)* **acidaemia** (*archaic*) a condition in which there is excessive acidity (i.e. increased hydrogen-ion concentration, lowered pH) of the blood. *Compare* **acidosis**, **alkalemia**.

acid-fast bacillus any bacterium able to resist decolorization by mineral acids after the application of specific basic aniline dyes; this property is possible due to the presence in these organisms of **mycolic acid**, together with a semipermeable membrane that allows the passage of the stain but not of the decolorizing acid.

acid *β*-glucosidase *see* **glucosylceramidase**.

α_1-acid glycoprotein *an alternative name for* **orosomucoid**.

acid-growth hypothesis the proposal that auxin-dependent acidification of plant cell walls promotes wall extensibility and cell growth. It is based on the demonstration that auxin causes acidification of the medium and that acid substitutes for auxin in causing the changes in th cell wall.

acid hydrolase any **hydrolase** enzyme that is active in mildly acidic conditions (pH 5–6); often found in **lysosomes**.

acidic 1 of, relating to, containing, or characteristic of an **acid**. *Compare* **basic** (def. 1). **2** having an acid reaction in water; of or relating to an aqueous solution having a pH < 7.0. *Compare* **basic** (def. 2).

acidic amino acid any amino acid containing more potentially anionic groups than potentially cationic groups. All such amino acids have a net negative charge at neutral pH: *e.g.*, aspartic acid and glutamic acid.

acidic-epididymal glycoprotein *abbr*.: AEG; *see* **CRISP**.

acid-labile sulfide a sulfido ligand, e.g. any of the **bridging ligands** in **iron–sulfur proteins**, that is released as H_2S at acid pH.

acid lipase a lysosomal acid triacylglycerol (triglyceride) and cholesterol esterase. It shows ≈60% sequence identity with human gastric and rat lingual lipase, and with them shares the Gly–X–Ser–X–Gly motif associated with esterase activity. Decreased activity is associated with Wolman disease and **cholesterol ester storage disease**, and is due to mutations in a locus at 10q23.2-q23.3.

acid mucopolysaccharide any of a group of related heteropolysaccharides, found widely distributed in animal connective tissues, that contain *N*-acetylated hexosamine in its characteristic repeating disaccharide unit. They include chondroitin, **chondroitin sulfates**, **dermatan sulfates**, hyaluronic acid (*see* **hyaluronate**), and **keratan sulfates**.

acid number *or* **acid value** the mass, in milligrams, of potassium hydroxide required to neutralize the free fatty acid in one gram of fat; a measure of the mass of free acid in the sample.

acidophilic 1 staining readily with **acid dyes**. **2** (of organisms) preferring or thriving in a relatively acid environment.

acidosis a clinical condition in which excess acid or a base deficit tends to cause increased hydrogen-ion concentration (i.e. lowered pH) in the blood.

acidosome a non-lysosomal vesicle found in the ciliate protozoan *Paramecium*. The organelle is involved in acidification of digestive phagocytic particles through fusion.

acidotropic seeking an acid environment. The term is used e.g. in connection with Ser/Thr protein kinases that require Glu or Asp as part of the recognition site. The resulting Ser(P) or Thr(P) then acts as an acidic residue, extending the site with the result that further Ser or Thr residues are phosphorylated.

acid phosphatase *abbr. (in clinical biochemistry)*: ACP; EC 3.1.3.2; *systematic name*: orthophosphoric monoester phosphohydrolase (acid optimum); *other names*: alkaline phosphomonoesterase; phosphomonoesterase; glycerophosphatase; a lysosomal enzyme (except in red cells). It catalyses the hydrolysis of orthophosphoric monoester to an alcohol and orthophosphate. Zinc and magnesium are cofactors. It is present in high concentrations in the prostate gland, and is also present in red cells, platelets, bone, liver, and spleen. Its measurement in blood may be of use clinically in monitoring progress in cases where prostatic cancer has metastasized, but not where cancer is confined to the prostate, being elevated in only about 30% of cases. Normal range in human plasma 4–11 IU L^{-1}.

acid proteinase *an older name for* enzymes of the sub-subclass **aspartic endopeptidase**, EC 3.4.23. It was suggested by their characteristic low optimum pH.

acid sphingomyelinase *see* **sphingomyelin phosphodiesterase**.

acinus (*pl.* **acini**) **1** a saclike structure that forms the terminal part of a gland. It comprises a cluster of cells surrounding a small duct. **2** one of the collection of small drupes making up an aggregate fruit such as a raspberry. —**acinar** *adj.*

Acinus a nuclear protein that is cleaved by caspase-3 and is required for chromatin condensation during **apoptosis**. It contains an N-terminal **SAP domain** and an RNA-recognition domain. Orthologues are present in vertebrates and in plants.

ackee *or* **akee** a tree, *Blighia sapida*, native to tropical Africa and widely cultivated in the West Indies, especially Jamaica, for its fruit, the fleshy aril of which is edible when cooked and forms an important item of local diet. Unripe fruits contain toxic amounts of **hypoglycin** and can cause **Jamaican vomiting sickness**.

Acm *abbr. for* acetamidomethyl-.

AcNeu *(formerly) symbol for N*-acetylneuraminic acid (*see* **sialic acid**).

acofriose 6-deoxy-3-*O*-methylmannose; the L enantiomer is a component of some **cardiac glycosides**.



α-L-anomer

aconitase EC 4.2.1.3; *other name*: aconitate hydratase; *systematic name*: citrate (isocitrate) hydro-lyase. A hydrolase enzyme that catalyses the reaction:

citrate = *cis*-aconitate + H_2O;

it also reversibly converts isocitrate into *cis*-aconitate + H_2O. An iron–sulfur protein, it removes H_R from the *pro-R*-CH_2–COOH group of citrate (*see* **citrate** for structure). Under kinetic conditions in which it forms isocitrate from citrate the product is (1*R*,2*S*)-1-hydroxypropane-1,2,3-tricarboxylate ((2*R*,3*S*)-isocitrate). The 3-D structure is known.

aconitate the *cis* isomer, (*Z*)-prop-1-ene-1,2,3-tricarboxylate, is an intermediate in the conversion of citrate to isocitrate in the tricarboxylic-acid cycle, by the action of **aconitase**.



cis-aconitate

aconitate hydratase *see* **aconitase**.

aconitate Δ-isomerase EC 5.3.3.7; *systematic name*: aconitate Δ^2–Δ^3-isomerase. An enzyme that catalyses the reaction:

trans-aconitate = *cis*-aconitate.

acoustic gene transfer a method of transforming (typically plant) cells by using ultrasound.

ACP *abbr. for* **1** acyl carrier protein. **2** *(in clinical biochemistry)* acid phosphatase.

εAcp *(formerly) symbol for* a residue of the ε-amino acid ε-caproic acid, now known as 6-aminohexanoic acid. εAhx is the preferred symbol.

acquired immune deficiency syndrome *abbr.*: AIDS; a collection of symptoms resulting from infection by a retrovirus (HIV-1 or HIV-2) that specifically attacks and destroys helper T lymphocytes, thereby impairing immunity and leading to a variety of other diseases (infections or neoplasms). Transmission is intrauterine, or by sexual contact, breast feeding, intimate contact with infected body fluids or tissues, and contaminated needles or syringes.The condition has reached epidemic proportions around the world. Treatment involves combinations of inhibitors of reverse transcriptase and HIV protease, and drugs to prevent microbial infections of brain, respiratory and alimentary tracts and vagina. *See* **HIV**.

acquired immunity *or* **adaptive immunity** immunity (active or passive, humoral or cellular) that is established during the life of an individual, as contrasted with innate or natural immunity. Such immunity is specific for the inducing agent and is marked by an enhanced response on repeated encounters with that agent. The key features are memory (*see* **memory cell**) and specificity.

acquired tolerance **1** *(in immunology)* tolerance to an antigen that is established during the life of an individual. Immunological tolerance can (rarely) be produced in an adult animal by prolonged injection of massive doses of antigen. The tolerance persists as long as antigen persists in the animal. *See also* **self tolerance**. **2** *(in pharmacology)* tolerance (generally to psychoactive compounds) that develops on prolonged or repeated drug administration. It can be either **pharmacokinetic** usually by increased drug metabolism, or **pharmacodynamic**. *See* **tachyphylaxis**, **tolerance**.

acrasin a chemotactic substance produced by the myxamoebae of the cellular slime mould *Dictyostelium discoideum*, now identified as cyclic AMP.

acridine the parent compound of a series of derivatives, e.g. 3,6-diaminoacridine (proflavin), that are potent mutagens. Some acridines are found in coal tar. They induce **frameshift mutations** during the replication of DNA by binding to DNA and distorting the double helix, causing additional bases to be incorporated or bases to be omitted. They are used as topical antiseptics and antimalarial agents.



acridine

Acridine Orange 3,6-bis(dimethylamino)acridine; a dye used as a probe of nucleic acids in microscopy and related techniques. When illuminated under UV light it yields a green (DNA) or reddish-orange (RNA) fluorescence.



Acridine Orange

acridinium esters esters of acridine-9-carboxylic acid. They have a quaternary nitrogen centre and are derivatized at the 9 position to give a labile phenyl ester moiety. Acridinium esters such as 2′,6′-dimethyl-4′-[*N*-succinimidyloxy carbonyl]phenyl-10-methyl-acridinium-9-carboxylate can be used as chemiluminescent labels for antibodies. Light emission is activated by adding hydrogen peroxide under alkaline conditions. In hybridization protection assays, single-stranded DNA probes labelled with acridinium esters are protected against rapid hydrolysis when hybridized with a target DNA molecule but not when they are in free solution.

acriflavin a mixture of the **acridine** derivatives 3,6-diamino-10-methylacridinium chloride (about 65%) and **proflavin**.

acrocentric describing a chromosome in which the **centromere** is very close to one end.

acrolein 3-propenal; CH_2=CH–CHO; an unstable flammable liquid with a pungent odour that irritates the eyes and mucosae. It polymerizes (especially under light) to form a plastic solid.

acrolein test a qualitative test for the presence of glycerol, either free or esterified, based upon its oxidative dehydration to acrolein when heated with solid potassium hydrogen sulfate.

acromegaly a chronic disease marked by the gradual enlargement of the bones of the hands, feet, head, and chest with thickening of the skin, lips, and vocal chords. It is caused by excessive secretion of, or increased sensitivity to, **somatotropin**, and is often due to a tumour of the somatotrope cells of the pituitary.

acrosin EC 3.4.21.10; a trypsin-like serine endopeptidase. A major proteinase of mammalian spermatozoa, synthesized in a zymogen form, proacrosin, and stored in the **acrosome**. It comprises a heavy chain (catalytic) and a light chain linked by two disulfide bonds; it is not inhibited by α_1-antitrypsin. It catalyses the hydrolysis of Arg-|-Xaa and Lys-|-Xaa bonds, with preferential cleavage in the order Arg-|-Xaa >> Lys-|-Lys >> Lys-|-Xaa.

acrosomal process a long thin actin-containing spike produced from the head of certain types of sperm when they make contact with the egg at fertilization. It is seen in sea urchins and other marine invertebrates having eggs surrounded by a thick gelatinous coat.

acrosome a modified lysosome in the head of a spermatozoon that contains acid hydrolases concerned in the breakdown of the outer membrane of the ovum during fertilization. It lies anterior to the nucleus just beneath the plasma membrane. *See also* **acrosin**.

ACRP30 *abbr. for* adipocyte complement-related protein of 30 kDa; *other names*: adipo-Q; adiponectin. An abundant serum protein that is synthesized and secreted by adipocytes (an adipokine) in response to insulin but is downregulated in obese mice and in human obesity. The mouse protein contains a globular domain similar to that of complement protein C1q. This domain, when injected into mice, induces weight loss via activation of fatty acid catabolism in muscle.

acrylamide *or* **acrylamide monomer** *the trivial name for* propenamide, $CH_2{=}CH{-}CONH_2$; a water-soluble solid that is highly toxic and irritant, and readily polymerizes under the action of UV light or chemical catalysts into **polyacrylamide**.

ActA a bacterial actin-binding protein. The human pathogen *Listeria monocytogenes* uses actin filaments to transport itself within the host cell cytoplasm.

ACTH *abbr. for* adrenocorticotrop(h)ic hormone (**corticotropin**).

1–24 ACTH *abbr. for* tetracosactrin.

actidione *see* **cycloheximide**.

actin a major protein constituent of the thin filaments of muscle and of the **microfilaments** found in practically all eukaryotic cells – it comprises 5–10% of the protein of such cells (*see* **actin filament**). In solutions of low ionic strength, actin is a globular 42 kDa monomer, termed **G-actin**. At physiological ionic strengths, G-actin polymerizes into a fibrous form, termed **F-actin**, which resembles two strings of beads wound round each other. F-actin is a helix of actin monomers, with a helix diameter of about 7 nm, the structure repeating at intervals of 36 nm along the helix axis. When a solution of actin is mixed with a solution of the muscle protein myosin, a complex called **actomyosin** is formed, and the viscosity of the solution increases markedly. This increase in viscosity is reversed by the addition of ATP, which acts to dissociate the actomyosin complex. It is thought that the force of muscle contraction arises from an interaction of actin, myosin, and ATP.

actin-binding protein any of several proteins that associate with either actin monomers or actin filaments in cells and modify their properties. Many of these proteins are found in the cell cortex, an actin-rich layer just below the plasma membrane. Examples include **dystropin**, **profilin**, **spectrin** and **ankyrin**, **fimbrin** and α-actinin (*see* **actinin**), **filamin**, **gelsolin**, and the **myosins**. The term is sometimes applied specifically to filamin.

actin depolymerizing factor *see* **destrin**.

actin filament a two-stranded helical polymer of the protein **actin**. Actin filaments form the thin filaments of muscle and also the **microfilaments** of the cytoskeleton of eukaryotic cells. Hence they are a major component of the contractile apparatus of skeletal muscle, and one of the three types of protein filament that form the cytoskeleton, the others being **microtubules** and **intermediate filaments**. The filaments, comprising polymerized globular actin molecules, appear as flexible structures with a diameter of 5–9 nm. They are organized into a variety of linear bundles, two-dimensional networks, and three-dimensional gels. In the cytoskeleton they are most highly concentrated in the cortex of the cell just beneath the plasma membrane.

actinic describing electromagnetic radiation, especially higher frequencies of visible light and UV radiation, capable of initiating photochemical reactions.

actinidine a monoterpenoid alkaloid occurring in *Actinidia polygama*.

actinin a minor protein constituent of muscle, found to be concentrated in both the Z line and the I band. Two components of actinin have been identified: **α-actinin**, F-actin cross-linking protein, a dimer of ~200 kDa with an action similar to that of **actinogelin**.; and **β-actinin**, a dimer of ~70 kDa, similar in action to **gelsolin**.

actinogelin a protein factor that effects Ca^{2+}-sensitive gelation of actin filaments. It was first obtained from Ehrlich ascites tumour cells, and has a molecular mass of 100–120 kDa. α- Actinin (*see* **actinin**) has a similar action.

actinoid *or* **actinide** any member of the series of 15 metallic elements with proton numbers 89 (actinium) to 103 (lawrencium) inclusive that occur together in group 3 and period 7 of the IUPAC **periodic table**; sometimes the term is restricted to the 14 elements following actinium. Actinoid is now the preferred name. All actinoids are radioactive, and those of proton number 93 or greater are artificial. They are all electropositive, and their chemical properties are similar, due usually to the filling of an inner electron subshell (5f) progressively across the series. Like the **lanthanoids**, they thus represent a series of inner transition elements.

actinomycin any of a large group of antibiotics isolated from various species of *Streptomyces* bacteria and characterized by having a substituted phenoxazine ring linked to two cyclic **heterodetic** peptides. The principal member of the group is **actinomycin D** (also called actinomycin C_1, actinomycin IV), which, at low concentrations, inhibits transcription without appreciably affecting DNA replication in both prokaryotic and eukaryotic cells. Actinomycin D binds tightly to duplex DNA thereby preventing it from being an effective template for RNA synthesis. Spectroscopic and hydrodynamic studies of complexes of actinomycin D and DNA suggest that the phenoxazine ring of actinomycin is intercalated between neighbouring base pairs in DNA. Other conformational studies indicate that actinomycin D recognizes the base sequence GpC in DNA.



actinomycin D

actinomyosin *(formerly)* the contractile system in muscle comprising **actin** and **myosin**. *Compare* **actomyosin**.

actin-related protein *see* **Arp**.

action potential the localized change of electrical potential across a nerve fibre or muscle membrane that marks the position of an impulse as it is propagated. It is caused by sodium ion fluxes across the membrane resulting from transitory opening of **sodium channels**.

action spectrum a graph or table showing the relative efficiencies of different frequencies of radiation in causing a chemical or biochemical reaction, e.g. in photosynthesis or gas exchange. Efficiency, or **quantum yield**, is given by the measurable effect divided by the intensity of the (monochromatic) incident radiation.

activate 1 to make or render active, reactive, or capable of action. **2** to make radioactive. **—activated** *adj.*; **activation** *n.*

activated alumina particles of alumina, aluminium oxide, that have been rendered more adsorbent by heating strongly.

activated amino acid an amino-acid residue in an aminoacyladenylate molecule. The amino acid reacts with ATP to form aminoacyl-AMP in a reaction catalysed by an aminoacyl-tRNA synthetase. It is the first metabolic step in the biosynthesis of a polypeptide. The same enzyme catalyses the transfer of the amino acid to an ester link with the 3′-terminal hydroxyl of tRNA.

activated complex term that may be used to denote the assembly of atoms at the transition state of a chemical reaction.

activation 1 the action or process of rendering an atom, molecule, or other substance reactive or more reactive, whether physicochemically, chemically, or biochemically. **2** the process of rendering material artificially radioactive: radioactivation. *See* **radioactivation analysis**. **3** the initial changes in an ovum during fertilization, covering the period from first contact with a sperm to dissolution of the nuclear membranes. **4** the initial changes in the conversion of a spore to a vegetative cell. This can be effected by various agents or processes and may involve alteration of one of the spore's outer layers.

activation analysis *an alternative term for* **radioactivation analysis**.

activation energy *see* **Arrhenius equation**.

activation hormone a polypeptide hormone synthesized in the neurosecretory brain cells of insects. It regulates the functioning of the whole endocrine system, stimulating the secretory activity of other glands.

activation-induced cytidine deaminase a putative RNA-editing enzyme, related to APOTEC-1, that is specific to antigen-activated B lymphocytes in germinal centres of lymph nodes. It is required for immunoglobulin (Ig) class switch recombination, somatic hypermutation, and gene conversion of immunoglobulin genes. Mutations are associated with an autosomal recessive form of hyper-IgM syndrome.

activator any substance that activates a chemical or enzymic reaction. The term was formerly used in biochemistry especially to describe metal-ion **cofactors** for enzymes.

activator constant *symbol*: K_A; the equilibrium **dissociation constant** of the reaction of an enzyme with an activator. For example, in the reaction:

$$E + A \rightleftharpoons EA,$$

$$K_A = [EA]/[E][A],$$

where [EA], [E], and [A] are the concentrations of enzyme– activator adduct, free enzyme, and free activator respectively.

active acetaldehyde *(sometimes)* the α-hydroxyethyl derivative, on C-2 of the thiazolidine ring, of thiamine diphosphate.

active acetate *(formerly) an alternative name for* **acetyl coenzyme A**.

active C_1 *abbr. for* active one-carbon.

active centre all the features of primary, tertiary, and quaternary structure of an enzyme – including the **active site** – that are required for substrate binding, specificity, and catalysis.

active-enzyme centrifugation a technique for determining the sedimentation and diffusion coefficients of an enzyme– substrate complex. A thin lamella of an enzyme solution is layered onto a substrate solution in an ultracentrifuge cell and, on rotation, as the enzyme molecules sediment in a band through the substrate solution they catalyse the enzymic reaction, the progress of which is observed optically (e.g. by spectrophotometry). The required coefficients are then calculated from either the rate of appearance of the product of the reaction or the rate of disappearance of the substrate. The centrifugation may be performed on impure enzyme preparations and at the very low concentrations of enzyme used in kinetic studies.

active fatty acid *(formerly) an alternative term for* an **acyl-CoA** derivative.

active formaldehyde *(formerly) an alternative term for* N^5,N^{10}-methylenetetrahydrofolate.

active immunity *or* **adaptive immunity** a type of immunity resulting from the stimulation of the immune response by an immunogen.

active immunization stimulation of the reactivity of the immune system of an individual towards an immunogen by administration of the immunogen, thereby producing a state of active immunity.

active methionine *or* **active methyl** *name sometimes used for* ***S*-adenosylmethionine**.

active methyl **1** *an alternative name for* **active methionine**. **2** one form of **active one-carbon** (e.g. 5-methyltetrahydrofolate).

active one-carbon any of the one-carbon units carried on tetrahydrofolate and concerned in a wide variety of biosynthetic reactions. They include the methyl-, methylene-, formimino-, formyl-, and methenyl- substituents.

active site **1** the general region of an enzyme molecule containing the **catalytic residues** identified with the binding and reaction of substrate(s). It includes those amino-acid residues that are, in the enzyme–substrate complex, either **contact amino acids**, i.e. those that at some point are only one bond distance removed from some point of the substrate molecule, or **auxiliary amino acids**, i.e. those that are not in such intimate physical contact with the substrate but nonetheless play a definite role in the action of the enzyme. *See also* **contributing amino acid**. **2** *(sometimes)* the portion of a peptide hormone responsible for its biological activity. Isolated fragments containing the active site may show some activity, but may function less efficiently than the intact hormone. *See also* **message sequence**.

active site-directed irreversible inhibitor a custom-made inhibitor of a given enzyme. Such inhibitors are typically trifunctional molecules containing: (1) a functional group able to bind to the enzyme's active site; (2) a nonpolar part that can interact with a nonpolar region on the enzyme, serving to align the inhibitor; and (3) an alkylating group capable of reacting with a susceptible group on the enzyme and irreversibly forming a covalent bond with it.

active sulfate *an alternative name for* **1 adenosine-5′-phosphosulfate**. **2 3′-phosphoadenosine-5′-phosphosulfate**.

active transport any energy-dependent process by which molecules or ions are transported across membranes against a chemical potential gradient. *Compare* **facilitated diffusion**, **simple diffusion**.

activicin a structural analogue of glutamine that inhibits glutamine-PRPP amidotransferase (of purine biosynthesis) and carbomyl phosphate synthetase II (of pyrimidine biosynthesis) and is therefore a potential anticancer agent.

activin one of two gonadal glycoproteins related to **transforming growth factor-β** (the other is **inhibin**); present in two forms in human gonads, it exists as a dimer of inhibin β_A or β_B chains, linked by disulfide bonds. Activin A is a dimer of β_A chains; activin AB is a dimer of β_A and β_B chains. A potent selective stimulator of FSH secretion by the anterior pituitary gland, not via GnRH receptors, it modulates induction of hemoglobin accumulation and proliferation of erythroid progenitor cells in human bone marrow culture, and is important in embryonic axial development.

activin receptor-like kinase 1 *abbr.*: ALK1; a cell-surface receptor kinase of the transforming growth factor β (TGFβ) superfamily of ligands. It is expressed primarily in endothelial cells and highly vascularized tissues. It forms heterodimers with endoglin and signals through R-Smad (*see* **Smad**), which enters the nucleus to affect transcription. Mutations in the ALK1 gene at 12q11-q14 are associated with hereditary hemorrhagic telangiectasia.

activity **1** the natural or normal functioning of an enzyme, hormone, inhibitor, or other agent; or the intensity with which such an agent functions. *See also* **enzymic activity**. **2** the number of nuclear **transformations** (def. 5) that occur or that can be detected in a given quantity of radioactive material in unit time (*see also* **becquerel**, **curie**). This term is also often used in this sense for **radioactivity** and, loosely, for the radioactive material itself or its emitted radiation; see also **specific activity**. **3** *or* **relative activity** *symbol*: *a*; the apparent or effective concentration of a chemical substance as judged by the behaviour of the substance in a standard state. The activity of an entity B is defined by

$$a_B = \exp[(\mu_B - \mu_B^o)/RT]$$

where μ_B and μ_B^o are respectively the chemical potential and standard chemical potential of entity B, *R* is the gas constant, and *T* the thermodynamic temperature. **4 absolute activity** *symbol*: λ; the absolute activity of an entity B is defined by

$$\lambda_B = \exp(\mu_B/RT),$$

where μ_B is the chemical potential of entity B, *R* is the gas constant, and *T* is the thermodynamic temperature. *See also* **activity coefficient**.

activity coefficient *symbol*: γ; the ratio of the **activity** (def. 3) of a component of a solution to its concentration. When expressed on an amount concentration basis it is denoted γ_c, when on a molality basis γ_m, and when on a mole fraction basis γ_x. *See also* **mean ionic activity coefficient**.

activity stain any reagent that develops a colour when acted on by a particular enzyme. Such a reagent is used to detect the presence of an enzyme in a gel or paper electrophoresis strip, in which it differentially stains the enzyme protein in question but not other proteins.

actobindin a monomeric protein capable of binding two molecules of monomeric (i.e., G-) actin.

actomyosin *see* **actin**.

ACU a codon in mRNA for L-threonine.

acumentin a Ca^{2+}-insensitive, actin-modulating protein, isolated from rabbit alveolar macrophages.

acute intermittent porphyria the commonest form of acute hepatic porphyria, which is caused by any of numerous mutations in **hydroxymethylbilane synthase** (porphobilinogen deaminase). It usually develops after puberty and is exacerbated by certain steroid hormones or drugs, or a diet that induces 5-aminolevulinic acid synthase in liver thus increasing formation of the porphobilinogen substrate. *See* **porphyria**.

acute myeloid leukemia *or (esp. Brit.)* **acute myeloid leukaemia** the most common form of acute **leukemia**, occurring within the first four weeks of life. Almost half of the cases have a translocation involving a chromosomal segment at 11q23 (the MLL gene – mixed lineage leukemia) and a segment of another chromosome, frequently 19p13.1 (for ELL), resulting in the production of a **fusion protein** that interferes with the normal control of cell division. The MLL gene encodes a protein of 3968 amino acids, which contains: in the N-terminal region, three A–T hooks for binding A–T base pairs in the minor groove of DNA; a segment homologous with the noncatalytic regions of DNA methyltransferase; in the central region, two zinc finger regions; and in the C-terminal region a 210-amino acid segment that, like the zinc finger regions, has significant homology to *Drosophila* trithorax. The resulting MLL-ELL fusion protein contains the N-terminal 1300 residues (up to but not including the zinc fingers) of MLL, and most of the sequence of ELL.

acute myeloid leukemia 1 *see* **AML1**.

acute-phase protein any of the non-antibody proteins that show raised plasma concentrations soon after the onset of infection, chemical or physical tissue injury, or malignant neoplasia. They include **complement** (def. 3) proteins, **C-reactive protein**, **fibrinogen** and other coagulation proteins, and **interferon**. Levels of some proteins (e.g. albumin) usually decrease. These responses in liver protein synthesis may have complex origins.

acute transfection the short-term infection of cells with DNA.

acyclic describing an organic compound devoid of a ring of atoms.

acycloguanosine *an alternative name for* **acyclovir**.

acyclovir *or* **acycloguanosine** 9-(2-hydroxyethoxymethyl)guanine; an antiviral agent widely used in the treatment of human herpes infections. It is selectively phosphorylated by herpesvirus-induced thymidine kinase and the phosphorylated compound is a potent inhibitor of herpesvirus-induced DNA polymerase. One proprietary name is Zovirax.



acyclovir

acyl *generic name for* any group formally derived by removal of a hydroxyl group from the acid function of an organic acid. Examples include any group of general structure R–CO– derived from a carboxylic acid; R–SO$_2$– from a sulfonic acid; and R–PO(OH)– from a phosphonic acid. However, unless the context indicates otherwise the term refers to such groups derived from carboxylic acids.

acyl-ACP dehydrogenase *see* **enoyl-[acyl-carrier protein] reductase (NADPH, A-specific)**.

acyl-activating enzyme *see* **long-chain-fatty-acid–CoA ligase**.

acylation the process of introducing an acyl group into a compound by substitution for a hydrogen atom. **—acylated** *adj.*

acyl carrier protein *abbr.*: ACP; any of the relatively small acidic proteins that are associated with the fatty acid synthase system of many organisms, from bacteria to plants. They contain one 4′-phosphopantetheine prosthetic group bound covalently by a phosphate ester bond to the hydroxyl group of a serine residue. The sulfhydryl group of the 4′-phosphopantetheine moiety serves as an anchor to which acyl intermediates are (thio)esterified during fatty-acid synthesis. In animals, the fatty acid synthase system is a 500 kDa polyfunctional enzyme containing two identical chains, each with one ACP unit. *Escherichia coli* ACP, a separate single protein, contains 77 amino-acid residues (8.85 kDa); the phosphopantetheine group is linked to serine 36.

acyl-CoA *generic name for* any derivative of **coenzyme A** in which the sulfhydryl group is in thioester linkage with a fatty-acyl group.

acyl-CoA dehydrogenase the first enzyme of fatty acid oxidation, responsible for catalysing an FAD-dependent alpha-beta dehydrogenation of a fatty acyl-CoA substrate. Four enzymes are recognized in humans. **Very-long-chain acyl-CoA dehydrogenase** (EC 1.3.99, *abbr.*: VLCAD) is a homodimer attached to the inner mitochondrial membrane in liver, and acts on fatty acids of chain length 14–20 carbon atoms. Its gene locus at 17p13 encodes a sequence of 655 amino acids. **Long-chain acyl-CoA dehydrogenase** (EC 1.3.99.13, *abbr.*: LCAD) is a homotetramer bound to the inner mitochondrial membrane that acts on fatty acids 12–18 carbon atoms long; it also has 2-enoyl-CoA hydratase activity and constitutes the α subunits of mitochondrial trifunctional protein (an $\alpha_4\beta_4$ octamer). The β subunits of the trifunctional protein have 3-ketoacyl-CoA thiolase activity. Genetic loci for both subunits are at 2p23. **Medium-chain acyl-CoA dehydrogenase** (EC 1.3.99.3, *abbr.*: MCAD) is a homotetramer present in the mitochondrial matrix and acts on fatty acids of chain length 4–12 carbon atoms. Its gene locus is at 1p31. **Short-chain acyl-CoA dehydrogenase** (butgryl-CoA dehydrogenase, EC1.3.99.2, *abbr.*: SCAD), also a homotetramer, acts on fatty acids of 4–6 carbon atoms chain length. Its locus at 12q22-qter encodes a mature protein of 388 amino acids. Disease-causing mutations are known in all four enzymes.

acyl-CoA reductase EC 1.2.1.50; *recommended name*: long-chain-fatty-acyl-CoA reductase; *systematic name*: long-chain-aldehyde: NADP$^+$ oxidoreductase (acyl-CoA-forming). An enzyme that catalyses a reaction between a long-chain aldehyde, CoA, and NADP$^+$ to form long-chain acyl-CoA and NADPH. It is part of the bacterial **luciferase** system. Example: *see* **Lux proteins**.

acyl-CoA synthetase *see* **long-chain-fatty-acid–CoA ligase**.

acyl enzyme any intermediate formed in an enzymic acyl-transfer reaction in which a group at the active site of the enzyme is acylated.

acylglycerol **1** any mono-, di-, or triester of glycerol with (one or more) fatty acids (termed respectively monoacylglycerol, diacylglycerol, or triacylglycerol); formerly known as mono-, di-, or triglyceride. **2** acylglycerols (*plural*), also denotes any mixture of mono-, di-, and/or triacylglycerols whatever its degree of complexity, including any comprising a **neutral fat**.

2-acylglycerol *O*-acyltransferase EC 2.3.1.22; *other names*: acylglycerol palmitoyltransferase; monoglyceride acyltransferase; an enzyme that catalyses the acylation by acyl-CoA of 2-acylglycerol to form diacylglycerol and CoA. It is an enzyme involved in the **monoacylglycerol pathway** of triacylglycerol biosynthesis.

1-acylglycerol-3-phosphate *O*-acyltransferase EC 2.3.1.51; *systematic name*: acyl-CoA:1-acyl-*sn*-glycerol-3-phosphate 2-*O*-acyltransferase. An enzyme that catalyses the acylation by acyl-CoA of 1-acyl-*sn*-glycerol 3-phosphate (lysophosphatidic acid) to form 1,2-diacyl-*sn*-glycerol 3-phosphate (phosphatidic acid) with release of CoA. Acylated acyl carrier protein can also act as substrate. In animals, the enzyme specifically transfers unsaturated fatty acyl groups, a preference that contributes to the high proportion of unsaturated fatty acids on the 2-position of phosphoglycerides.

1-acylglycerophosphocholine *O*-acyltransferase EC 2.3.1.23; *other name*: lysolecithin acyltransferase; an enzyme that catalyses the acylation by acyl-CoA of 1-acyl-*sn*-glycero-3-phosphocholine to form 1,2-diacyl-*sn*-glycero-3-phosphocholine and CoA. It is involved in the resynthesis of phosphatidylcholine in situations where the latter has been degraded to lysophosphatidylcholine.

acylhomoserine *see* ***O*-succinylhomoserine**.

acyl migration any intramolecular rearrangement reaction in which, under certain conditions, an acyl group moves from one functional group to another, which may be of the same or of a different kind. **N → O acyl migration** (*also termed* N → O acyl shift, N → O acyl transfer, *or* N → O peptidyl shift) is a reaction that can occur in polypeptides and proteins subjected to hydrolysis by concentrated acid at room temperature or in the presence of an acid chloride (e.g. POCl$_3$), whereby the *β*-hydroxyl group of a serine or threonine residue displaces the amino group of the same residue from its amide (= peptide) linkage with the carboxyl group of the adjacent residue, thus forming an acid-sensitive *β*-ester linkage. The reaction may be used to advantage in partial acid hydrolysis of polypeptides and proteins. In the presence of alkali the ester reverts to the original amide by **O → N acyl migration**, a reaction that can also occur during the **Edman degradation** of a peptide. An acyl group, e.g. acetyl or maleyl, that happens to be present on the *β*-hydroxyl group of a serine or threonine residue, moves to the free amino group of such a residue when it becomes N-terminal, so preventing the next cycle of the degradation.

***N*-acylneuraminate glycohydrolase** *see* **sialidase**.

acylphosphatase EC 3.6.1.7; *systematic name*: acylphosphate phosphohydrolase. An enzyme that catalyses the hydrolysis of acyl phosphate to fatty-acid anion and orthophosphate.

acyl-protein synthase *see* **myelin-proteolipid *O*-palmitoyltransferase**.

acyl shift *see* **acyl migration**.

acylsphingosine deacylase *see* **ceramidase**.

***N*-acylsphingosine galactosyltransferase** EC 2.4.1.47; an enzyme that catalyses the formation of the cerebroside D-galactosylceramide from UDPgalactose and *N*-acylsphingosine with release of UDP.

acyltransferase any enzyme of sub-subclass EC 2.3.1. Such enzymes transfer acyl groups, forming either esters or amides, by catalysing reactions of the type:

acyl-carrier + reactant = acyl-reactant + carrier.

For example if acyl = acetyl, carrier = CoA, and reactant = choline, the reaction is that of **choline acetyltransferase**.

AD *(in clinical biochemistry) abbr. for* alcohol dehydrogenase (preferred to ADH because of possible confusion with antidiuretic hormone).

Ada *or* **ADA** *abbr. for* *N*-(2-acetamido)iminodiacetic acid; [(carbamoylmethyl)imino]diacetic acid; a **Good buffer substance**, pK_a (20 °C) = 6.6.

Adair equation an equation describing the oxygen saturation curve of hemoglobin:

$$\frac{R = K_1[p_{O_2}] + 2K_1K_2[p_{O_2}]^2 + 3K_1K_2K_3[p_{O_2}]^3 + 4K_1K_2K_3K_4[p_{O_2}]^4}{4(1+K_1[p_{O_2}] + K_1K_2[p_{O_2}]^2 + K_1K_2K_3[p_{O_2}]^3 + K_1K_2K_3K_4[p_{O_2}]^4)}$$

where R is the fractional saturation of hemoglobin with oxygen, K_1, K_2, K_3, and K_4 are the stepwise intrinsic association constants for the four oxygen-binding sites, and p_{O_2} is the partial pressure of oxygen. For a generalized form of this equation *see* **Bjerrum formation function**. [Defined by Gilbert Smithson Adair (1896–1979), British biophysicist, in 1925.]

ADAM *abbr. for* a disintegrin and metalloproteinase; any of a large family of zinc-binding cell-surface transmembrane proteins that contain a **disintegrin** and a **metalloproteinase** domain. Such proteins are presumed to have roles in cell fusion, cell adhesion, and cell signaling.

ADAM-10 an α-secretase involved in amyloid peptide precursor proteolysis. It is an endopeptidase, EC 3.4.24.81. *See* **ADAM**.

ADAM-17 *an alternative term for* **TNF-α converting enzyme**. *See also* **ADAM**.

ADAM-33 a protein belonging to the **ADAM** family that is abundant in lung fibroblasts and bronchial smooth muscle cells. Mutations of its gene are associated with asthma.

adamalysin EC 3.4.24.46; *other name*: proteinase II; a metalloendopeptidase that catalyses the cleavage of Phe^1-|-Val^2, His^5-|-Leu^6, His^{10}-|-Leu^{11}, Ala^{14}-|-Leu^{15}, Leu^{15}-|-Tyr^{16}, and Tyr^{16}-|-Leu^{17} in the insulin B-chain. Zn^{2+} and Ca^{2+} are cofactors. It is a snake venom proteinase whose natural substrate(s) are protease inhibitor(s), such as the **serpins**.

1-adamantanamine *or* ***α*-adamantanamine** *see* **amantadine**.

adamantane tricyclo[3.3.1.1^{3,7}]decane; a substance isolated from petroleum and said to have virostatic activity. *See also* **amantadine**.



ADAMTS *abbr. for* a disintegrin and metalloproteinase with a thrombospondin domain; any of a family of proteins that are related to the **ADAM** family of metalloproteinases but are distinguished by having a thrombospondin domain and by being secreted.

ADAMTS-2 a protein belonging to the **ADAMTS** family, deficiency of which is associated with a form of **Ehlers–Danlos syndrome**.

ADAMTS-13 a protein belonging to the **ADAMTS** family that cleaves **von Willebrand factor**. Deficiency leads to microvascular thrombus formation. Mutations in its gene are associated with a form of congenital purpura.

Adapt any of a family of proteins encoded by oxidant stress-inducible genes that provide partial protection against such stress. The genes are also inducible by calcium ionophores or by inceased intracellular calcium. **Adapt78** (*also called* DSCR1 *or* Down syndrome critical region 1) is a 25 kDa protein that specifically binds and inhibits calcineurin, which has a role in stress-induced apoptosis. Adapt78 gene is the most responsive to calcium of the various adapts; its gene is highly expressed in neurons of cerebral cortex and hippocampus, and is overexpressed in brains of Down syndrome sufferers.

adaptation *(in biology)* **1** any change in an organism's structure or function that allows it better to deal with its environmental conditions. **2** the mechanism whereby bacterial cells that approach cells of the opposite mating type, but fail to mate, can recover and continue dividing.

adapted gradient in **gradient elution**, a form of gradient in which the composition of the eluate is adjusted, on the basis of information obtained in a trial separation, to be optimal at each moment of the elution, so that the optimum resolution between the desired components of the sample is obtained.

adaptin a major coat protein of clathrin-coated vesicles. It functions as a component of the adaptor complexes that link clathrin to the receptors being taken into the cell in the coated vesicles, recognizing a motif of four amino acids (FRxY) in the cytoplasmic domain of the receptor.

adaptive describing changes in an organism, induced by environmental factors, that tend to increase its viability.

adaptive enzyme *see* **inducible enzyme**.

adaptive immunity *an alternative name for* **active immunity**.

adaptor **1** any of various devices useful for joining together two or more parts, otherwise incompatible, such as electrical connectors or pieces of glassware. **2** any synthetic single- or double-stranded oligodeoxynucleotide useful in recombinant DNA technology for joining two incompatible cohesive ends of restriction fragments. *Compare* **linker**. **3** *or* **adaptor molecule** the molecule that was postulated as carrying the amino acid to the (messenger) RNA in the **adaptor hypothesis** of protein synthesis, now known to be a tRNA molecule.

adaptor hypothesis the hypothesis, first postulated by the British molecular biologist Francis **Crick** (1916–), that during protein biosynthesis each amino-acid residue is carried to the RNA template by its appropriate small adaptor RNA molecule, and that the adaptor is the part that fits on to the messenger RNA. The hypothesis was subsequently confirmed by the discovery of **transfer RNA**.

adaptor protein *abbr.*: AP **1.** a protein that links together active signal components but is not itself catalytic. **2.** a component of protein complexes associated with clathrin in **clathrin-coated vesicles**.

ADAR *abbr. for* adenosine deaminase acting on RNA; any member of a family of enzymes that deaminate adenosine to inosine in RNA and share a common modular organization. This consists of a variable N-terminal region, one or several double-standed RNA-binding domains, and a zinc-containing catalytic domain. In vertebrates, ADAR 1 and ADAR 2 are expressed in most tissues and are involved in editing of pre-mRNA for mammalian ionotropic glutamate receptors and a subtype of serotonin receptors, whereas ADAR 3 is brain-specific but appears to lack catalytic activity. *See also* **adenosine deaminase**.

ADAT *abbr. for* adenosine deaminase acting on tRNA; *other name*: tRNA-specific adenosine deaminase; any member of a family of RNA-dependent adenosine deaminases that act on the anticodon in several tRNAs in higher eukaryotes, prokaryotes, and plant chloroplasts. The catalytic domain binds zinc and contains an essential glutamate residue.

ADCC *abbr. for* antibody-dependent cell-mediated cytotoxicity.

Addison's disease a disease due to deficiency of production of cortisol and other cortical steroids. It results from atrophy of the adrenal cortex, a condition having a variety of causes. [Described by Thomas Addison (1793–1860), British physician and endocrinologist, in 1849.]

addition 1 *(in chemistry)* the formation of an **adduct**. **2** an **addition reaction**.

addition compound *see* **adduct**.

addition reaction *or* **addition** any organic chemical reaction involving the combination of two or more substances to form a single product in which there are more groups attached to carbon atoms than there were in the original reactants. Such reactions thus involve a net reduction of bond multiplicity in one of the reactants, as in the example:

$$H_2C{=}CH_2 + Br_2 \rightarrow H_2BrC{-}CBrH_2.$$

address 1 that part of the information contained within the amino-acid sequence of a hormonal polypeptide, or its biosynthetic precursors, that determines the receptor-specific affinity of the hormone. *Compare* **message** (def. 4). **2** *(in computer technology)* a label, name, or number, identifying a device or a location in a memory.

addressin any of a group of glycoproteins, expressed specifically in a region of the vascular endothelium in peripheral and mucosal lymph nodes, that are involved in the homing of T lymphocytes to these sites.

address sequence *or* **address region** that segment of the amino-acid sequence of a polypeptide hormone, or prohormonal polypeptide, in which the address of the hormone resides, and through which the hormone is considered to bind to its specific receptor. *Compare* **message sequence**.

adducin a membrane skeleton protein (heterodimer) that interacts with a junctional complex that links **spectrin** assemblies. The complex in the red blood cell consists of **tropomyosin** and **actin** with band 4.1 (*see* **band**). Adducin probably binds to band 4.1.

adduct 1 any new chemical species, AB, formed by direct combination of two separate chemical species, A and B, in such a way that there is no change in **connectivity** of atoms within the moieties A and B. This term is preferred to **complex**, which is less explicit. **2** *(formerly)* the product of a reaction between molecules occurring in such a way that the original molecules or their residues have their long axes parallel to one another.

Ade *symbol for* a residue of the purine base adenine (alternative to A).

ADE2 a gene that encodes a multifunctional protein with activities for **phosphoribosylaminoimidazole carboxylase** and **phosphoribosylaminoimidazolesuccinocarboxamide synthase**. It has been studied as a model of position effect in gene expression. The gene is expressed in all cells if in its normal position near the middle of the chromosome, but if moved experimentally to the end of the chromosome it is silenced. The lack of the enzyme produces a red pigmentation in these colonies.

adenine *symbol*: A *or* Ade; 6-aminopurine; 1*H*-purin-6-amine; a purine base. It is one of the five main bases found in nucleic acids and a component of numerous important derivatives of its corresponding ribonucleoside, adenosine. It can exist in a tautomeric imino form.



adenine arabinoside *other names*: vidarabine, ara-A; 9-β-D-arabinofuranosyladenine; an antibiotic produced by *Streptomyces* bacteria that acts as an antiviral agent, causing mispairing of purines and pyrimidines in nucleic-acid synthesis.

adenine nucleotide translocase *see* **ADP,ATP carrier protein**.

adenine phosphoribosyltransferase *abbr*.: APRT; EC 2.4.2.7; *other names*: AMP pyrophosphorylase; transphosphoribosidase; an enzyme that catalyses the formation of AMP from 5-phospho-α-D-ribose 1-diphosphate and adenine with release of pyrophosphate. It is an enzyme of purine metabolism that salvages adenine released by degradative enzymes, converting it back to a nucleotide. Several mutations in a locus at 16q24 produce **APRT deficiency type 1**, in which no activity is detectable in erythrocytes and the excess adenine forms the poorly soluble 2,8-dihydroxyadenine and leads to crystalluria. Other mutations produce **APRT deficiency type 2**, in which activity amounts to 10–25% of the wild type.



9-β-D-form

adeno+ *or (before a vowel)* **aden+** *comb. form* meaning of, pertaining to, or like a gland; glandular; found in glands.

adenohypophysis the glandular anterior lobe of the hypophysis (or **pituitary gland**). It produces corticotropin, gonadotropin, lipotropin, somatotropin, thyrotropin, and other hormones. *Compare* **neurohypophysis**. **—adenohypophyseal** *or* **adenohypophysial** *adj.*

adenoma any benign tumour formed by the multiplication of the epithelial cells that form the ducts and acini of glandular organs. The meaning has been broadened to include the benign tumours that arise from the solid masses of epithelium that form some of the endocrine glands. Adenomas often accurately reproduce the tissues from which they are derived and produce a secretion identical with or similar to that produced by the normal glandular tissue.

adenosine *symbol*: A *or* Ado; adenine riboside; 9-β-D-ribofuranosyladenine; a ribonucleoside found widely distributed in cells of every type as the free nucleoside and in combination in nucleic acids and various nucleoside coenzymes. It is a potent regulator of physiological transmission in both central and peripheral nervous systems, where it activates specific receptors (*see* **adenosine receptor**). It can inhibit or stimulate the release of a number of neurotransmitters, including acetylcholine, β-aminobutyrate, catecholamines, excitatory amino acids, and 5-hydroxytryptamine. The effect depends on whether the receptor involved inhibits adenylate cyclase (and thus inhibits release) or stimulates it.



adenosine aminohydrolase *see* **adenosine deaminase**.

adenosine 2′,3′-(cyclic)phosphate *see* **adenosine phosphate**.

adenosine 3′,5′-(cyclic)phosphate *see* **adenosine 3′,5′-phosphate**.

adenosine deaminase EC 3.5.4.4; *systematic name*: adenosine aminohydrolase; an enzyme that catalyses the hydrolysis of adenosine to inosine and NH_3. It is involved in the degradation of adenosine, the inosine thereby formed being then converted to hypoxanthine and thence to uric acid. The enzyme is also found on the outer surface of T cells, and a form that acts on double-stranded RNA (dsRNA) converts adenosines to inosines within dsRNA.

adenosine deaminase acting on RNA *see* **ADAR**.

adenosine deaminase acting on tRNA *see* **ADAT**.

adenosine deaminase deficiency an autosomal recessive disease in which deficiency of adenosine deaminase (ADA) causes a form of severe combined immunodeficiency (SCID). ADA activity is very low or undetectable in all tissues, and both cell-mediated (T-lymphocyte) and humoral (B-lymphocyte) forms of immunity are lacking. Successful therapy involves bone marrow transplantation. Numerous mutations of a locus at 20q13.11 lead to the deficiency. In partial ADA deficiency, ADA activity is absent in erythrocytes and partial in all other tissues, although immune function is essentially normal.

adenosine diphosphatase *see* **apyrase**.

adenosine 5′-diphosphate *symbol*: Ado5′*PP* *or* ppA; *the recommended name for* adenosine diphosphate (*abbr.*: ADP); 5′-diphosphoadenosine; 5′-adenylyl phosphate; adenosine 5′-trihydrogen diphosphate; a universally distributed nucleotide that occurs both in the free state and as a component of certain **nucleotide coenzymes**. It is a metabolic precursor of adenosine 5′-triphosphate, ATP, and is the product of many enzyme reactions in which ATP is hydrolysed by an **adenosine triphosphatase** or in which the terminal phosphoric residue of ATP is transferred to another organic compound by a **kinase** (including **adenylate kinase**).

adenosinediphosphoglucose *or* **adenosine (5′)diphospho(1)-α-D-glucose** *symbol*: Ado*PP*Glc *or* Ado-5′*PP*-Glc *or* A5′pp1Glc; the alternative recommended names for adenosine diphosphate glucose (*abbr.*: ADPG *or* ADP-Glc *or* ADPglucose); adenosine 5′-(α-D-glucopuranosyl diphosphate); α-D-glucopyranosyl 5′-adenylyl phosphate; a **nucleosidediphosphosugar** in which the distal phosphoric residue of adenosine 5′-diphosphate is in glycosidic linkage with glucose. ADPglucose is synthesized from glucose 1-phosphate and adenosine 5′-triphosphate, ATP, through the action of glucose 1-phosphate adenylyltransferase (EC 2.7.7.27). It is an intermediate in the incorporation of glucosyl groups into starch in plants and into storage glucans in bacteria.

adenosinediphosphoribose *or* **adenosine(5′)diphospho(5)-β-D-ribose** *symbol*: Ado*PP*Rib *or* A5′pp5Rib *or* (Rib5)ppA; *the alternative recommended names for* adenosine diphosphate ribose *(abbr.*: ADP-Rib *or* ADPribose); adenosine 5′-(β-D-ribofuranose 5-diphosphate); a **nucleoside diphosphosugar** in which the explicit sugar moiety is a second residue of D-ribose and is in ester linkage with the distal phosphoric residue of adenosine 5′-diphosphate atypically at C-5 instead of at C-1. ADPribose is synthesized from D-ribose 5-phosphate and ADP through the action of ribose-5-phosphate adenylyltransferase (EC 2.7.7.35), releasing orthophosphate. In addition, free ADPribose is released from nicotinamide-adenine dinucleotide, NAD$^+$, on hydrolytic cleavage of the glycosylamine bond to nicotinamide through the action of NAD$^+$ nucleosidase (EC 3.2.2.5). *See also* **cyclic adenosinediphosphoribose**.

adenosinediphosphoribosyl *abbr.*: ADPribosyl; the glycosyl group formally derivable from adenosinediphosphoribose by loss of the anomeric (i.e. C-1) hydroxyl group from its distal ribose moiety. The ADPribosyl group of nicotinamide-adenine dinucleotide may be utilized for **ADP-ribosylation**.

adenosine 5′-[β,γ-imido]triphosphate *symbol*: Ado*PP*[NH]*P* *or* p[NH]ppA; *the recommended name for* β,γ-imidoadenosine 5′-triphosphate (*abbr.*: ATP[β,γ-NH]); 5′-adenylyl imidodiphosphate; 5′-adenylyl iminodiphosphonate (*abbr.*: AMP-PNP); adenosine (5′$\rightarrow O^3$)-1,2-μ-imidotriphosphate; a synthetic analogue of adenosine triphosphate, in which the oxy group between the latter's intermediate and terminal phosphorus atoms is replaced by an imido group. It competitively inhibits ATP-dependent enzymes, including mitochondrial ATPase.



adenosine 5′-[β,γ-imido]triphosphate

adenosine kinase EC 2.7.1.20; an enzyme that catalyses the reaction:

$$\text{ATP} + \text{adenosine} = \text{ADP} + \text{AMP}.$$

adenosine 5′-[α,β-methylene]diphosphate *symbol*: Ado*P*[CH$_2$]*P* *or* p[CH$_2$]pA; *the recommended name for* α,β-methyleneadenosine 5′-diphosphate (*abbr.*: ADP[α,β-CH$_2$]); 5′-adenylyl methylenephosphonate (*abbr.*: AMP-CP); adenosine (5′$\rightarrow O^1$)-1,2-μ-methylenediphosphate; a synthetic analogue of adenosine 5′-diphosphate, ADP, in which the oxy group between the latter's two phosphorus atoms is replaced by a methylene group. It inhibits 5′-nucleotidase obtained from rat-heart membranes.



adenosine5′-[α,β-methylene]triphosphate *symbol*: Ado*P*[CH$_2$]*PP* *or* pp[CH$_2$]pA; *the recommended name for* α,β-methyleneadenosine 5′-triphosphate (*abbr.*: ATP[α,β-CH$_2$]); 5′-adenylyl methylenediphosphate (*abbr.*: AMP-CPP); adenosine (5′$\rightarrow O^1$)-1,2,-μ-methylenetriphosphate; a synthetic analogue of adenosine 5′-triphosphate, ATP, in which the oxy group between the latter's innermost and intermediate phosphorus atoms is replaced by a methylene group. It competitively inhibits rat-liver adenylate cyclase.



adenosine 5′-[β,γ-methylene]triphosphate *symbol*: Ado*PP*[CH$_2$]*P* *or* p[CH$_2$]ppA; *the recommended name for* β, γ-methyleneadenosine 5′-triphosphate (*abbr.*: ATP[β,γ-CH$_2$]); 5′-adenylyl methylenediphosphonate (*abbr.*: AMP-PCP); adenosine (5′$\rightarrow O^1$)-1,2-μ-methylenetriphosphate; a synthetic analogue of adenosine 5′-triphosphate, ATP, in which the oxy group between the latter's intermediate and terminal phosphorus atoms is replaced by a methylene group. It inhibits the binding of ouabain to Na$^+$/K$^+$-transporting ATPase, the sodium pump.



adenosine monophosphate *abbr.*: AMP; *an alternative name for* any **adenosine phosphate**, but in particular for adenosine 5′-phosphate, especially when its distinction from adenosine (5′-) diphosphate and adenosine (5′-)triphosphate requires emphasis.

adenosine phosphate *symbol*: Ado*P*; adenosine monophosphate (*abbr.*: AMP); any phosphoric monoester or diester of adenosine. There are three monoesters – adenosine 2′-phosphate, adenosine 3′-phosphate, and **adenosine 5′-phosphate** – and two diesters – adenosine 2′,3′-phosphate and **adenosine 3′,5′-phosphate** – although adenosine 5′-phosphate is the ester commonly denoted (the locant being omitted if no ambiguity may arise). Adenosine 2′-phosphate (*symbol*: Ado2′*P*) is also named adenosine 2′-monophosphate (*abbr.*: 2′AMP) *or* 2′-adenylic acid *or* adenylic acid a, and adenosine 3′-phosphate (*symbol*: Ado3′*P*) is also named adenosine 3′-monophosphate (*abbr.*: 3′AMP) *or* 3′-adenylic acid *or* adenylic acid b *or* (*formerly*) yeast adenylic acid.

adenosine 2′-phosphate *see* **adenosine phosphate**.

adenosine 2′,3′-phosphate *see* **adenosine phosphate**.

adenosine 3′-phosphate *see* **adenosine phosphate**.

adenosine 3′,5′-phosphate *symbol*: Ado-3′,5′-*P*; *the recommended name for* cyclic adenosine 3′,5′-monophosphate (*abbr.*: cyclic AMP *or* cAMP); adenosine 3′,5′-cyclophosphate; adenosine 3′,5′-(cyclic)phosphate; a monophosphoric diester of adenosine. It is a universally distributed key metabolite, produced by the action of **adenylate cyclase** on adenosine 5′-triphosphate, ATP. The first compound to be named a **second messenger**, it mediates many effects in signal transduction pathways. It was first identified as a heat-stable activator of glycogen phosphorylase kinase, and is now known also to activate cyclic-AMP-dependent protein kinase and to regulate numerous other enzymic activities or physiological processes.



adenosine 5′-phosphate *or* **5′-adenylic acid** *or* **5′-phosphoadenosine** *or* **5′-*O*-phosphonoadenosine** *symbol*: Ado5′*P*; *alternative recommended names for* adenosine 5′-monophosphate (*abbr.*: 5′AMP); adenosine 5′-(dihydrogen phosphate); adenine (mono)ribonucleotide *or* (*formerly*) muscle adenylic acid. (The locant is commonly omitted if there is no ambiguity as to the position of phosphorylation.) It is a metabolic regulator, biosynthesized from inosine 5′-phosphate, 5′-inosinic acid; it is formed also by pyrophosphatase-catalysed cleavage of (inorganic) diphosphate from ATP.

adenosine 3′-phosphate 5′-phosphosulfate *or* **3′-phosphoadenosine 5′-phosphosulfate** *symbol*: *P*Ado*PS*; *abbr.*: PAPS; *alternative recommended names for* active sulfate; 3′-phospho-5′-adenylyl sulfate; adenosine 3′-phosphate 5′-*P*-phosphatosulfate; 3′-phospho-5′-adenylic sulfuric monoanhydride; a naturally occurring mixed anhydride. It is synthesized from **adenosine 5′-phosphosulfate** by phosphorylation with ATP through the action of adenylylsulfate kinase (EC 2.7.1.25). It is an intermediate in the formation of a variety of sulfo compounds in biological systems. For example, in animals it is involved in sulfate transfer in the formation of sulfatides and in the synthesis of chondroitin sulfate and other sulfated polysaccharides, while in bacteria, by a process analogous to that involving adenosine 5′-phosphosulfate in plants, adenosine 3′-phosphate 5′-phosphosulfate interacts with reduced thioredoxin to yield adenosine 3′,5′-bis(phosphate) and sulfite; the latter can then undergo further reduction to sulfide, from which cysteine may be synthesized.



adenosine 5′-phosphosulfate *symbol*: Ado*PS*; *abbr.*: APS; *the recommended name for* 5′-adenylyl sulfate; adenosine 5′-*P*-phosphatosulfate; 5′-adenylic sulfuric monoanhydride; a naturally occurring mixed anhydride. It is synthesized from ATP and (inorganic) sulfate by the action of sulfurylase, sulfate adenylyltransferase (EC 2.7.7.4), and is an intermediate in the formation of **adenosine 3′-phosphate 5′-phosphosulfate**. In plants, by a process analogous to that involving adenosine 3′-phosphate 5′-phosphosulfate in bacteria, adenosine 5′-phosphosulfate can undergo reduction to yield sulfide, which may then be utilized for cysteine synthesis.



adenosine receptor *or* **P_1 purinoceptor** one of three types, A_1, A_2, and A_3, of membrane protein that bind adenosine or its analogues; they are **7TM proteins**. The selective agonist for A_1 is N^6-cyclopentyladenosine; that for A_2 is (2-*p*-carboxyethyl)phenylamino-5 -*N*-carboxamidoadenosine. Binding of agonist to A_1 causes inhibition of **adenylate cyclase**, opening of K^+ channels, and inhibition of Ca^{2+} channels. Activation of A_2 brings about stimulation of adenylate cyclase. Activation of A_3 causes stimulation of adenylate cyclase. In some cases, particularly where A_1 receptors are involved, inositolphospholipid turnover may be stimulated. *See also* **purinoceptor**.

adenosine 5′-β-thiodiphosphate *symbol*: Ado*PP*[S] *or* [S]ppA; *abbr.*: ADP[S] *or* ADP-*β*-S; *the recommended name for* adenosine 5′-[*β*-thio]diphosphate; adenosine 5′-(2-thiodiphosphate); adenosine (5′→*O*²)-1-thiodiphosphate; a synthetic analogue of adenosine 5′-diphosphate, ADP, in which an oxygen atom of its terminal phosphoric residue is replaced by a sulfur atom. It acts variously as a substrate or an inhibitor of ADP-dependent systems.



adenosine 5′-thiophosphate *symbol*: Ado*P*[S] *or* [S]pA; *the recommended name for* adenosine 5′-[*α*-thio]monophosphate (*abbr.*: AMP-S); a synthetic analogue of adenosine 5′-phosphate, AMP, in which an oxygen atom of its phosphoric residue is replaced by a sulfur atom. It acts variously as a substrate or an inhibitor of AMP-dependent systems.



adenosine 5′-γ-thiotriphosphate *symbol*: Ado*PPP*[S] *or* [S]pppA; *abbr.*: ATP[S] *or* ATP-*γ*-S; *the recommended name for* adenosine 5′-[*γ*-thio]triphosphate; adenosine (5′→*O*³)-1-thiotriphosphate; a synthetic analogue of adenosine 5′-triphosphate, ATP, in which an oxygen atom of its terminal phosphoric residue is replaced by a sulfur atom. It can variously substitute for ATP or act as an inhibitor of ATP-dependent systems.



adenosinetriphosphatase *or* **ATP phosphohydrolase** *or* **ATPase** any of several hundred enzymes catalyzing hydrolysis of ATP to ADP plus orthophosphate. Several types of ATPase are recognized.

1 ATPases functioning in the active transport of substances across membranes. These can be classified as: (a) P-type ATPases, which undergo phosphorylation at an aspartate residue during the transport cycle and transport mostly cations (H^+, Na^+, K^+, Ag^+, Ca^{2+}, Cd^{2+}, Cu^{2+}, Mg^{2+}), but also Cl^- and aminophospholipids (EC 3.6.3.1–3.6.3.13, 3.6.3.53 or TC 3.A.3.1.1–3.A.3.9.3); (b) ATPase exporting arsenite anions from bacteria (EC 3.6.3.16 or TC 3.A.4.1.1); (c) the multisubunit or two-sector ATPases transporting H^+ and Na^+ ions (EC 3.6.3.14–3.6.3.15 or TC 3.A.2.1.1–3.A.2.3.1); (d) the ABC-type ATPases (see also **ABC transporter**) transporting a variety of substances, from nutrient molecules in bacteria to xenobiotics in eukaryotic organisms (EC 3.6.3.17–3.6.3.49 or TC 3.A.1.1.1–3.A.1.210.5); (e) enzymes or enzyme complexes participating in the transport of macromolecules (EC 3.6.3.50–3.6.3.52 or TC families 3.A.5–3.A.11).

2 ATPases functioning in cellular and subcellular movement, such as myosin (EC 3.6.4.1), dynein (EC 3.6.4.2), and others (EC 3.6.4.3–3.6.4.11).

adenosine 5′-triphosphate *symbol*: Ado5′*PPP or* pppA; *the recommended name for* adenosine triphosphate (*abbr.*: ATP); 5′-triphosphoadenosine; 5′-adenylyl diphosphate; adenosine 5′-(tetrahydrogen triphosphate); a universally important coenzyme and enzyme regulator. It is formed from adenosine 5′-diphosphate by oxidative phosphorylation in coupled mitochondria, by photophosphorylation in plants, and by substrate-level phosphorylation. Reactions in which it participates are often driven in the direction leading to hydrolysis of ATP. The chemical energy so released may be utilized in active transport; it may be converted to mechanical energy (e.g. for muscular contraction, movement of cilia, etc.), to light energy (for bioluminescence), or to electrical energy (in electric fish); or it may be released as heat. ATP also participates in numerous synthetic reactions by the transfer to other metabolites of a phosphoric or a diphosphoric residue, of an adenosyl residue, or of an adenylyl residue.



adenosyl any chemical group formed by the loss of a 2′-, a 3′-, or a 5′-hydroxyl group from the ribose moiety of adenosine. *Compare* **adenylyl**.

***S*-adenosylhomocysteine** the L enantiomer, *S*-(5′-adenosyl)-L-homocysteine (*symbol*: AdoHcy; *abbr.*: SAH), *S*-(5′-deoxyadenosine-5′-yl)-L-homocysteine, is formed from ***S*-adenosylmethionine**. It is a strong inhibitor of *S*-adenosylmethionine-mediated methylation reactions and is cleaved to adenosine and homocysteine.

***S*-adenosylmethionine** the L enantiomer, active methionine, *S*-(5′-adenosyl)-L-methionine (*symbol*: AdoMet; *abbr.*: SAM), *S*-(5′-deoxyadenosine-5′-yl)-L-methionine, is an important intermediate in one-carbon metabolism, the methionine's methyl group (activated by the adenosyl moiety bonded through sulfonium) being donated to an acceptor molecule by transmethylation and *S*-adenosylhomocysteine being produced. It is important also as an intermediate in the production of ethylene from L-methionine in plants, being cleaved to 5′-methylthioadenosine and 1-aminocyclopropane-1-carboxylate. The latter compound is then fragmented under aerobic conditions to ethylene, formate, ammonium, and carbon dioxide.



S-adenosylhomocysteine

adenosylmethionine decarboxylase EC 4.1.1.50; *systematic name*: *S*-adenosyl-L-methionine carboxy-lyase. An enzyme of polyamine (and hence **trypanothione**) biosynthesis that catalyses the decarboxylation of *S*-adenosyl-L-methionine to (5′-deoxyadenosin-5′-yl)(3-aminopropyl)methylsulfonium salt; pyruvate acts as a cofactor. The product participates in reactions in which its 3-aminopropyl group is transferred to **putrescine** to form **spermidine**, and a second 3-aminopropyl group is then transferred to spermidine to form **spermine**. In most cases its subunits (α and β) are derived from a single proenzyme.

***S*-adenosylmethionine synthetase** *see* **methionine adenosyltransferase**.

adenovirus any of a group of non-enveloped icosahedral viruses, the Adenoviridae, containing linear double-stranded DNA. They affect mammals or birds (usually being specific to one or a few closely related host species) and are often associated with disease of the respiratory tract.

adenyl *a misnomer for* **adenylyl** or **adenylate**.

adenylate **1** either the monoanion or the dianion of adenylic acid. **2** any mixture of the acid and its anions. **3** any salt or ester of adenylic acid.

adenylate cyclase *or* **adenylylcyclase** *or (incorrectly)* **adenyl cyclase** EC 4.6.1.1; *systematic name*: ATP pyrophosphate-lyase (cyclizing); a phosphorus–oxygen lyase enzyme that catalyses the elimination of diphosphate from adenosine 5′-triphosphate (ATP) to form **adenosine 3′,5′-phosphate** (cyclic AMP). It is an effector of signal transduction and other fundamental regulatory mechanisms, being regulated by some G$_\alpha$ subunits of G-proteins. In mammals it is a widely distributed membrane-bound glycoprotein with various isoforms (115–180 kDa). These are six-loop-six structures, the intracellular loop and the C-terminal domain being homologous to the guanylate cyclase catalytic domain. One of them bears an ATP-binding site. Type I, 1134 amino acids, is brain-specific, Ca^{2+}/calmodulin activated, and inhibited by G-protein βγ subunits. Types II (1088 amino acids) and IV (1064 amino acids) are **calmodulin** insensitive and activated by βγ subunits; type II is found in brain and olfactory tissue, type IV is widely distributed except in testis. Type III, from olfactory sensory neurons, is calmodulin sensitive and not regulated by βγ subunits. Types V and VI form a subgroup that is widely distributed and not stimulated by βγ subunits. *Saccharomyces cerevisiae* enzyme (2026 amino acids) has a weak structural relationship with the mammalian enzyme. It is positively regulated by the *RAS1* and *RAS2* gene products, but this property is not shared by a recombinant enzyme from *Schizosaccharomyces pombe*. A plant gene has been cloned, the deduced protein sequence having no similarity to prokaryotic counterparts, but showing striking similarity to the catalytic region of *S. cerevisiae* adenylate cyclase, and with the cytoplasmic domains of bovine adenylate cyclase and two mammalian guanylate cyclases. Soluble adenylate cyclases (*abbr*.: sAC) are not affected by G proteins but are activated by bicarbonate in kidney and choroid plexus. Some sACs are found in bacterial toxins.

adenylate deaminase EC 3.5.4.6; *other names*: AMP aminohydrolase; AMP deaminase; an enzyme that converts adenosine monophosphate (AMP) to inosine monophosphate and ammonia. There are four isozymes in humans. The **M isozyme** (*also called* myoadenylate kinase) is specific to skeletal muscle where it is closely associated with the contractile proteins. It is encoded by the *AMPD1* gene at 1p13-p21. The **L isozyme** predominates in liver and brain. It is encoded by the *AMPD2* gene at 1p13.3. **E1** and **E2** are isoforms in erythrocytes, produced by differential splicing of the pre-mRNA encoded by the *AMPD3* gene at 11p13-pter. Myoadenylate deaminase deficiency can be inherited as an autosomal recessive trait and is associated with exercise-induced cramp or myalgia; alternatively it can be acquired, being associated with a variety of neuromuscular disorders.

adenylate energy charge (*or* **energy charge**) a measure of the phosphorylating power of an adenylate pool, equal to one half the average number of anhydride-bound phosphoric groups per adenosine moiety present in the pool. It may be defined in terms of the concentrations of AMP, ADP, and ATP in the pool and expressed by the quotient:

$$([\mathrm{ATP}] + 0.5[\mathrm{ADP}])/([\mathrm{ATP}] + [\mathrm{ADP}] + [\mathrm{AMP}]).$$

Compare **phosphorylation state ratio**.

adenylate isopentenyltransferase EC 2.5.1.27; *other name*: cytokinin synthase; an enzyme that catalyses the reaction between Δ^2-isopentenyl diphosphate and AMP to form (N^6-Δ^2-isopentenyl)adenosine 5′-monophosphate, an intermediate in the formation of **zeatin** riboside, and pyrophosphate.

adenylate kinase *abbr. (in clinical biochemistry)*: AK; EC 2.7.4.3; *systematic name*: ATP:AMP phosphotransferase; *other name*: myokinase. An enzyme that catalyses the reaction:

$$\mathrm{ATP} + \mathrm{AMP} = \mathrm{ADP} + \mathrm{ADP}.$$

adenylate pool *or* **adenylate system** the total amount of AMP, ADP, and ATP in a cell, tissue, or organism.

adenyl cyclase *a misnomer for* **adenylate cyclase**.

adenylic acid *the trivial name for* any phosphoric monoester of adenosine. The position of the phosphoric residue on the ribose moiety of a given ester may be specified by a prefixed locant; *see* **adenosine phosphate**, **adenosine**. However, 5′-adenylic acid is the ester commonly denoted, its locant usually being omitted if no ambiguity may arise. 5′-Adenylic acid is also an alternative recommended name for **adenosine 5′-phosphate**.

adenylosuccinate lyase EC 4.3.2.2; *other name*: adenylosuccinate adenosine 5′-monophosphate lyase; an enzyme that catalyses the nonhydrolytic cleavage of fumarate from the succinyl moiety of 5-aminoimidazole-4-[*n*-succinyl carboxamide ribotide] (SAICAR) and of succinyl-adenosine 5′-monophosphate, in the synthesis of adenosine 5′-phosphate and of purines, respectively. Its gene locus, at 22q13.1-q13.2, encodes a protein of 484 amino acids, which forms a homotetramer that is widely distributed in tissues and organisms. Deficiency, associated with some 20 mutations, is inherited as an autosomal recessive disorder characterized by psychomotor retardation and often with epileptic seizures or autistic features.

adenylyl the adenosine[mono]phospho group; the acyl group derived from adenylic acid (*see* **adenosine 5′-monophosphate**). *Compare* **adenosyl**.

adenylylate to introduce adenylyl groups into a compound generally through the action of an adenylyltransferase. —**adenylylated** *adj.*; **adenylylation** *n.*

adenylyl cyclase *a misnomer for* **adenylate cyclase**.

adenylyl sulfate *see* **adenosine 5′-phosphosulfate**

adenylylsulfate kinase EC 2.7.1.25; *other name*: APS kinase; an enzyme that synthesizes 3′-phosphoadenosine-5′-phosphosulfate from ATP and adenylylsulfate with release of ADP. See **phosphoadenosine-5′-phosphosulfate**.

adenylyltransferase *generic name for* any of a number of enzymes within sub-subclass EC 2.7.7, nucleotidyltransferases, that are specific for the transfer of an adenylyl group from a donor (usually adenosine triphosphate, ATP) to an acceptor (such as a nucleotide, a polynucleotide, a protein, a sugar phosphate, or sulfate); e.g. FMN adenylyltransferase (EC 2.7.7.2), ribose-5-phosphate adenylyltransferase (EC 2.7.7.35).

ADH *abbr. for*: **1** antidiuretic hormone. **2** *(in clinical biochemistry)* alcohol dehydrogenase (preferred form: AD).

adhalin *or* **DAG2** a dystrophin-associated glycoprotein of skeletal muscle sarcolemma that is specifically deficient in severe childhood autosomal recessive muscular dystrophy. It has a 17-residue signal sequence and one transmembrane domain, and contains two sites for N-linked glycosylation.

adherens junction a **cell junction** in which the cytoplasmic face of the plasma membrane is attached to actin filaments.

adhesion *(in pathology)* the abnormal union of surfaces or parts, usually due to the formation of fibrous tissue following inflammation.

adhesion molecules molecules expressed on the surface of a cell that mediate the adhesion of the cell to other cells, or to the extracellular matrix. They bind to receptors, classed collectively as **integrins**. Adhesion molecules are grouped into classes: these include **selectins**; the immunoglobulin superfamily, containing **ICAM**, **MadCAM**, **NCAM**, **PECAM**, and **VCAM**; the **cadherins**; and **CD44**. Adhesion molecules play a part in morphogenesis (e.g., cadherins), and in the treatment of inflammation and wounds (e.g., selectins and the immunoglobulin superfamily).

adiabatic describing any thermodynamic process that occurs with neither gain nor loss of heat between the system and its surroundings. —**adiabatically** *adv.*

adiabatic calorimeter a calorimeter in which the temperature of the outer jacket is kept as close as possible to that of the inner compartment so that heat losses from the latter are minimized.

adiabatic system *(in thermodynamics)* any geometrically defined volume that does not exchange thermal energy with its surroundings. *Compare* **closed system**, **open system**.

adipocyte a cell of adipose tissue; a fat cell or lipocyte of an animal.

adipogenesis the formation of fat or adipose tissue.

adipokine any adipose tissue-derived protein hormone, such as **ACRP30** or leptin.

adipokinetic fat-mobilizing; lipotropic.

adipokinetic hormone *abbr.*: AKH; *an alternative name for* **lipotropin**.

adiponectin *an alternative name for* **ACRP30**.

adipo-Q *an alternative name for* **ACRP30**.

adipose tissue fat or fatty tissue. *See also* **brown adipose tissue**, **white adipose tissue**.

adipsin **1** *another name for* complement factor D. **2** a protein of the serine endopeptidase family secreted into serum by adipocytes. It is expressed abundantly in adipocytes and sciatic nerve. There are two forms, M_r 37 000 and 44 000.

adiuretin *(sometimes) an alternative name for* **antidiuretic hormone**.

adjuvant **1** *(in immunology)* any substance or mixture of substances that increases or diversifies the immune response to an antigen. *See also* **Freund's adjuvant**. **2** *(in pharmacology)* any remedy or drug that assists or modifies the action of other remedies or drugs.

adjuvant peptide *an alternative name for* **muramyl-dipeptide**.

ad lib without restraint. Short for the Latin *ad libitum*, meaning literally 'at pleasure'.

ADME/Tox *abbr. for* **absorption, distribution, metabolism, elimination, and toxicity**.

A-DNA *abbr. for* A-form of DNA.

Ado *symbol for* a residue of the ribonucleoside adenosine (alternative to A).

AdoHcy *symbol for S*-adenosylhomocysteine.

AdoMet *symbol for S*-adenosylmethionine.

adonitol *a former name for* **ribitol**.

adonose *a former name for* **ribulose**.

Ado*P* *symbol for* any adenosine phosphate.

Ado2′*P* *symbol for* adenosine 2′-phosphate.

Ado-2′,3′-*P* *symbol for* adenosine 2′,3′-phosphate.

Ado3′*P* *symbol for* adenosine 3′-phosphate.

Ado-3′,5′-*P* *symbol for* adenosine 3′,5′-phosphate.

Ado5′*P* *symbol for* adenosine 5′-diphosphate *(alternative to* pAdo).

Ado*P*[CH$_2$]*P* *symbol for* adenosine 5′-[α,β-methylene]diphosphate (alternative to p[CH$_2$]pA).

Ado*P*[CH$_2$]*PP* *symbol for* adenosine 5′-[α,β-methylene]triphosphate (alternative to pp[CH$_2$]pA).

Ado5′*PP* *symbol for* adenosine 5′-diphosphate (alternative to ppA).

Ado*PP*[CH$_2$]*P* *symbol for* adenosine 5′-[β,γ-methylene]triphosphate (alternative to p[CH$_2$]ppA).

Ado*PP*Glc *or* **Ado-5′*PP*-Glc** *symbol for* adenosinediphosphoglucose (alternatives to A5′pp1Glc).

Ado*PP*[NH]*P* *symbol for* adenosine 5′-[β,γ-imido]triphosphate (alternative to p[N]ppA).

Ado5′*PPP* *symbol for* adenosine 5′-triphosphate (alternative to pppA).

Ado*PP*[S] *symbol for* adenosine 5′-β-thiodiphosphate (alternative to [S]ppA).

Ado*P*[S] *symbol for* adenosine 5′-thiophosphate (alternative to [S]pA).

Ado*PPP*[S] *symbol for* adenosine 5′-γ-thiotriphosphate (alternative to [S]pppA).

Ado*PP*Rib *symbol for* adenosine diphosphoribose (alternative to A5′pp5Rib *or* (Rib5)ppA).

Ado*PS* *symbol for* adenosine 3′-phosphate 5′-phosphosulfate.

adopted orphan receptor *see* **nuclear receptor**.

adoptive immunity immunity conferred by transfer of immunologically active cells from one individual to another.

ADP *abbr. for* adenosine 5′-diphosphate.

ADPase *abbr. for* adenosine diphosphatase (*see* **apyrase**).

ADP,ATP carrier protein *or* **adenine nucleotide translocase** an integral membrane protein of the inner mitochondrial membrane, responsible for the transport of ADP and ATP across the membrane. It exchanges one molecule of ADP^{3-} for one molecule of ATP^{4-}, and is thought to be driven by the proton gradient established across the inner membrane. It is a homodimer, each chain having three homologous domains. Different types occur in different mammalian tissues, but all are related.

ADP[α,β-CH$_2$] *abbr. for* α,β-methyleneadenosine 5′-diphosphate; i.e. adenosine 5′-[α,β-methylene]diphosphate.

ADPG *abbr. for* adenosinediphosphoglucose; ADP-Glc is preferred.

ADP-Glc *or* **ADPglucose** (*preferred*) *abbr. for* adenosinediphosphoglucose; *see also* **ADPG**.

ADPKD *abbr. for* autosomal dominant polycystic kidney disease.

ADP-Rib *or* **ADPribose** *abbr. for* adenosinediphosphoribose.

ADP-ribose (cyclic) *see* **cyclic adenosine 5′-diphosphoribose**.

ADPribosyl *abbr. for* the adenosinediphosphoribosyl group.

ADP-ribosylation the transfer of one or more **adenosinediphosphoribosyl** (*abbr.* ADPribosyl) groups from nicotinamide-adenine dinucleotide, NAD^+, to a protein through the action of an **ADP-ribosyltransferase**. In eukaryotic cells the transfer occurs particularly to the α subunits of **G proteins**, and then is stimulated by treatment with certain bacterial toxins such as **cholera toxin** or **pertussis toxin**. Linear poly(ADPribosyl) attachments, which may consist of up to 50 ADPribose units, are found on nuclear proteins and also on some cytoplasmic proteins. In the stepwise generation of such attachments an incoming ADPribosyl group forms a (1→2′) glycosidic bond to the nucleosidic ribose moiety of the most recently attached ADPribose unit. ADP-ribosylation occurs also in cells of *Escherichia coli* infected with bacteriophage T4, where single ADPribosyl groups become attached to the host's RNA polymerase. —**ADP-ribosylated** *adj. See also* **ADP-ribosyltransferase**, **NAD(P)$^+$–arginine ADP-ribosyltransferase**.

ADP-ribosylation factor a protein that acts as activator for **ADP-ribosyltransferase**.

ADP-ribosyl cyclase *abbr.*: ARC; an enzyme that catalyses the reactions:

(1) $NAD^+ \rightarrow$ cADP-ribose + nicotinamide;
(2) $NADP^+ \rightarrow$ 2′-phospho-cADP ribose + nicotinamide;
(3) NAD^+ + nicotinate → NAAD + nicotinamide;
(4) $NADP^+$ + nicotinate → NAADP + nicotinamide.

A physiological role has been assigned to cADP-ribose and NAADP (nicotinic acid adenine dinucleotide phosphate), but not to 2′-phospho-cADP ribose (also called cADPRP) or NAAD (nicotinic acid adenine dinucleotide). The enzyme from *Aplysia* has been cloned and is stimulated by the NO-CGMP pathway. In mammals the homologue is the lymphocyte antigen CD38 and the bone marrow stromal cell-surface molecule BST-1.

ADP-ribosyltransferase EC 2.4.2.30; *recommended name*: NAD^+ ADP-ribosyltransferase; *systematic name*: NAD^+: poly(adenine-diphosphate-D-ribosyl)-acceptor ADP-D-ribosyl-transferase; *other names*: poly(ADP) polymerase; poly(adenosine diphosphate ribose) polymerase; NAD^+ ADP-ribosyltransferase (polymerizing); poly(ADP-ribose) synthetase; *abbr.*: PARP *or* ADPRT. An enzyme that catalyses a reaction between NAD^+ and (ADP-D-ribosyl)$_n$-acceptor to form nicotinamide and (ADP-D-ribosyl)$_{n+1}$-acceptor. The enzyme acts on a number of nuclear proteins and thereby regulates events in differentiation and cell proliferation. The presence of DNA is necessary, and zinc is a cofactor.

ADP[S] *or* **ADP-*β*-S** *abbr. for* adenosine 5′-*β*-thiodiphosphate.

adren+ *or* **adreno+** *comb. form* denoting **1** the **adrenal gland(s)**. **2 epinephrine** or a related catecholamine.

adrenal **1** pertaining to or produced by the **adrenal glands**. **2** the adrenal gland itself.

adrenal androgen any of the C_{19} steroid hormones produced in the cortex of the adrenal gland, including androstenedione and testosterone.

adrenal cortex *see* **adrenal gland**.

adrenal cortical hormone *or* **adrenocortical hormone** any (cortico)steroid hormone elaborated and secreted by the cortex of the **adrenal gland**.

adrenalectomize *or* **adrenalectomise** to carry out adrenalectomy. —**adrenalectomized** *or* **adrenalectomised** *adj.*

adrenalectomy surgical removal of one or (usually) both adrenal glands.

adrenal gland *or* (less commonly) **suprarenal gland** an endocrine organ in vertebrates. There is a single pair in mammals, one near each kidney; in other vertebrates there may be multiple adrenal glands. The gland has two components: an inner medulla, derived from the neural crest, that biosynthesizes and secretes epinephrine and norepinephrine; and an outer cortex, derived from the coelom, that is concerned in the biosynthesis and secretion of steroid hormones. The cortex consists in turn of three histologically defined zones: an outer **zona glomerulosa**, the cells of which are responsible for the biosynthesis of aldosterone and deoxycorticosterone; an intermediate **zona fasciculata**; and an inner **zona reticularis**. The cells of the zona fasciculata and zona reticularis are responsible for the biosynthesis of the glucocorticoid cortisol and the androgens dehydroepiandrosterone and androstenedione.

adrenaline *see* **epinephrine**.

adrenal medulla *see* **adrenal gland**.

adrenal medullary hormone any catecholamine hormone elaborated and secreted by the adrenal medulla. *See* **adrenal gland**.

adrenergic **1** describing a nerve or other cell, or cell receptor (*see* **adrenoceptor**) that is activated by epinephrine, norepinephrine, or an epinephrine-like substance. **2** any nerve that acts by releasing epinephrine, norepinephrine, or an epinephrine-like substance from its nerve ending. *See also* **cholinergic**, **GABAergic**, **noradrenergic**, **peptidergic**, **purinergic**, **serotonergic**. —**adrenergically** *adv.*

adrenergic receptor *an alternative term for* **adrenoceptor**.

β-adrenergic-receptor kinase *abbr.*: βARK, βAR kinase *or* BARK; EC 2.7.1.126; an enzyme that phosphorylates specifically only the agonist-occupied form of the β-adrenoceptor and closely related receptors at the C terminus. It appears to be important in mediating rapid agonist-specific (homologous) desensitization. Its cDNA codes for a precursor protein of 689 amino acids. The purified protein migrates as a single band of 80 kDa on electrophoresis. It has a protein kinase catalytic domain that has sequence similarity to protein kinase C and cyclic AMP-dependent protein kinase.

adrenic acid *see* **docosatetraenoic acid**

adreno+ *see* **adren+**.

adrenoceptor *or* **adrenergic receptor** *or* **adrenoreceptor** *or* **adrenotropic receptor** any receptor on an effector cell that is activated by epinephrine or related catecholamines. Structurally, they are all of the **7TM** type. Adrenoceptors may be classified phenomenologically into different types according to their sensitivities to agonists and antagonists.

α Adrenoceptors have a relative order of agonist potency: epinephrine > norepinephrine > isoprenaline (isoproterenol), and a relative order of antagonist potency: phentolamine >> propranolol. They are associated with stimulatory effects, such as vasoconstriction and contraction of the iris, nictitating membrane, urinary bladder, seminal vesicles, and vas deferens, and with relaxation of propulsive smooth muscle in the gut. In some species, they mediate stimulation of gluconeogenesis and hepatic glycogenolysis. There are two groups, α_1 and α_2. α_1 receptors act through the phosphoinositide/Ca^{2+} second messenger system and are of four subtypes: α_{1A}, norepinephrine > epinephrine; α_{1B}, norepinephrine = epinephrine; α_{1C}, norepinephrine = epinephrine (different antagonist sensitivity from α_{1B}); α_{1D}. α_{2A} receptors all inhibit the formation of cyclic AMP; they also open K^+ channels and inhibit Ca^{2+} channels. α_{2B} receptors inhibit Ca^{2+} channels. α_{2C} receptors have no effect on ion channels.

β Adrenoceptors have actions that can be ascribed to the activation of adenylate cyclase. They may be divided phenomenologically into three classes: (1) β_1 adrenoceptors, in which the relative order of agonist potency is isoprenaline > norepinephrine > epinephrine, and the relative order of antagonist potency is practolol > propranolol. They are associated with cardiac stimulation and glycogenolysis, lipolysis in white adipose tissue, and calorigenesis in brown adipose tissue; (2) β_2 adrenoceptors, in which the relative order of agonist potency is isoprenaline > epinephrine > norepinephrine, and the relative order of antagonist potency is propranolol > practolol; they are associated with skeletal muscle glycogenolysis, promotion of secretion of glucagon and insulin, vasodepression and bronchodilation; and (3) β_3 adrenoceptors, with agonist potency norepinephrine > epinephrine. *See also* **β-adrenergic receptor kinase**, **β-arrestin**.

adrenoceptor kinase *see* **β-adrenergic receptor kinase**.

adrenochrome an oxidation product of epinephrine that polymerizes at alkaline pH to form brown melanin-like pigments.

adrenocortical of, pertaining to, or derived from the cortex of the **adrenal gland**, e.g. adrenocortical hormone. *See* **adrenal androgen**, **corticosteroid**.

adrenocorticotropic hormone *or* **adrenocorticotrophic hormone** *abbr.*: ACTH; *an alternative name for* **corticotropin**.

adrenocorticotropic hormone-releasing factor *an alternative name for* **corticotropin releasing hormone**.

adrenocorticotropin *or* **adrenocorticotrophin** *an alternative name for* **corticotropin**.

adrenodoxin *or (sometimes)* **adrenoredoxin** a **ferredoxin** isolated from adrenal-cortex mitochondria that acts as an electron carrier in hydroxylase systems acting on steroids. It transfers electrons from adrenodoxin reductase to **cholesterol monooxygenase**. *See also* **NADPH:adrenodoxin oxidoreductase precursor**. *Compare* **putidaredoxin**.

adrenodoxin reductase *see* **NADPH:adrenodoxin oxidoreductase precursor**.

adrenoleukodystrophy protein *see* **ALDP**.

adrenomedullary of, pertaining to, or derived from the medulla of the **adrenal gland**.

adrenomedullin a hypotensive peptide that may function as a hormone in circulation control.

adrenoreceptor *a variant spelling of* **adrenoceptor**.

adrenosterone androst-4-ene-3,11,17-trione; a hormone with weak androgenic effect, originally called Reichstein's substance G.

adrenotropic receptor *an alternative name for* **adrenoceptor**.

adrex *or* **adx** *abbr. for* adrenalectomized.

adriamycin *former (generic) name for* **doxorubicin**.

adseverin *another name for* **scinderin**.

adsorb to undergo or elicit **adsorption**. —**adsorbable** *adj.*; **adsorbability** *n.*

adsorbate a substance that is adsorbed to the surface of another substance from either a gas or a liquid phase.

adsorbent **1** capable of **adsorption**. **2** a solid that adsorbs another substance from either a gas phase or a liquid phase.

adsorptiochromism the colour change that sometimes accompanies adsorption of organic compounds onto inorganic substances, e.g. onto alumina.

adsorption **1** any process in which a gas, liquid, or solute adheres to the exposed surfaces of a material, especially a solid, with which it is in contact. In **physical adsorption** the adhesion is through van der Waals forces of interaction, whereas in **chemisorption** (*or* chemical absorption) the adhesion is through formation of weak chemical bonds. *Compare* **absorption**. **2** *(in immunology)* the nonspecific attachment of an antigen (or antibody) onto the surfaces of red cells or inert particles so that the antibody (or antigen) to it may be detected by agglutination of the cells or particles. *Compare* **immunosorption**. **3** *(in microbiology)* the process of attachment of a phage or other virus to a cell.

adsorption chromatography any form of **chromatography** in which separation of the components of a mixture is based mainly on differences between the adsorption affinities of the components for the surface of an active solid.

adsorption coefficient in any adsorption equilibrium (of a substance from a solution), the mass of adsorbed substance per unit mass of adsorbent divided by the concentration of the substance in solution. It has the dimensions of reciprocal concentration. *Compare* **distribution coefficient**, **partition coefficient**.

adsorption isotherm any plot of the amount of solute adsorbed by an adsorbent (or of ligand bound by, e.g., a macromolecule, often expressed as the **saturation fraction**) versus the concentration of the free solute (or ligand), at constant temperature. *Compare* **Langmuir adsorption isotherm**.

advanced glycation end product *abbr.*: AGE; a product of the nonenzymatic glycation by glucose, fructose, or glyceraldehyde-3-phosphate, of extra- or intracellular proteins. High-affinity AGE receptors are present on monocytes, macrophages, liver, renal glomeruli and endothelial cells. AGEs contribute to age-dependent modification and crosslinking of tissue proteins, as in cataract formation, nephropathy, and vascular complications of diabetes mellitus.

adverse drug response *abbr.* ADR; any harmful or unintended effect of a medication, diagnostic test, or therapeutic intervention that occurs at a dose normally used for prophylaxis, disease diagnosis or therapy, or for the modification of physiological function. ADRs are one of the leading causes of hospitalization and death in the USA.

adx *see* **adrex**.

AEBSF *abbr. for* aminoethylbenzenesulfonyl fluoride.

AEG *abbr. for* acidic-epididymal glycoprotein. *See* **CRISP**.

+aemia *see* **+emia**.

aequorin a Ca^{2+}-dependent **photoprotein** responsible for luminescence by oxidation of the chromophore coelenterazine. It is obtainable from the hydrozoan jellyfish, *Aequorea forskaolea*. In the absence of any other cofactors or oxygen, it emits light on the addition of calcium ions, making it useful for the determination of free calcium ions.

aerate **1** to supply with or expose to air. **2** to pass air through a liquid. **—aeration** *n.*

aerenchyma plant tissue containing large, continuous extracellular air spaces. It is found in root cortical tissues of some plants (e.g. maize and rice) to transport oxygen from aerial structures to submerged roots.The spaces may form by the destruction of cells (lysigeny) or separation of cells (schizogeny), or a combination of both, and their formation is promoted by ethylene. **–aerenchymatous** *adj.*

aerobe any organism or class of organisms that can grow in the presence of dioxygen. **Facultative aerobes** are also capable of growing in the absence of dioxygen, whereas **obligate** (or strict) **aerobes** have an absolute requirement for dioxygen. *Compare* **anaerobe**.

aerobic **1** describing conditions in which gaseous or dissolved dioxygen is present. **2** describing an organism or process that requires or is able to use dioxygen. **3** of or produced by an aerobe. *Compare* **anaerobic**.

aerobiosis life in the presence of dioxygen. **–aerobiotic** *adj.*

aerolysin a channel-forming protein secreted by the human pathogen *Aeromonas hydrophila*. The cytolytic toxin is a dimer, but forms stable heptameric structures that insert into lipid bilayers to produce well-defined channels, leading to destruction of the membrane permeability barrier, and osmotic lysis.

aerosol a colloidal dispersion of solid particles or liquid droplets in air or another gas.

Aet *symbol for* the aminoethyl group, $–CH_2–CH_2–NH_2$.

aetiology *see* **etiology**.

***Afa*I** a type 2 **restriction endonuclease**; recognition sequence: GT↑AC. *Rsa*I is an **isoschizomer**.

afamin a mammalian serum protein similar to albumin, α-fetoprotein, and vitamin D-binding protein.

afferent **1** conveying inwards to a part, organ, or centre, as of a blood vessel, nerve, or duct. **2** an afferent part, e.g. an afferent blood vessel or afferent nerve. *Compare* **efferent**.

affine the quality of having affinity.

affine gap penalty *see* **gap penalty**.

affinity **1** chemical attraction; the tendency of a chemical substance to combine with, bind to, or dissolve in other chemical substances. **2** any measure of such chemical attraction. **3** denoting biomolecular interaction that exhibits specificity.

affinity adsorbent any biospecific adsorbent used in affinity chromatography.

affinity chromatography a general chromatographic method that may, in principle, be used to isolate either of the components of a reversibly reacting chemical system provided that one component can be coupled to an insoluble matrix through a covalent linkage. The other component can then be bound to the immobilized component and the system eluted with a buffer that liberates the bound component. The technique has been applied to the separation of various substances, including enzymes, substrates, antigens, antibodies, nucleic acids, and even whole living cells. Pure antibodies can be prepared by this means: the antigen is covalently coupled to the dextran beads in the chromatography column, the antibody-containing solution is run into the column in neutral buffer, the specific antibody binds to the antigen, and the antibody is subsequently released with a buffer of high or low pH or with a denaturing reagent. The technique can also be used to isolate antigen. *See also* **affinity-elution chromatography**, **dye-ligand chromatography**. **—affinity-chromatographic** *adj.*

affinity constant *or* **binding constant** *an alternative name for* **association constant** (especially in relation to the binding of and/or to macromolecules, as in antigen–antibody, hormone– receptor, and enzyme–inhibitor reactions).

affinity cytochemistry a technique for detecting the distribution of specific cell-surface receptors. An easily visible (or electron-dense) material conjugated with a reagent specific for a particular cell-surface receptor is allowed to react with the cells in question and is then detected by light or electron microscopy.

affinity electrode a type of electrode useful for assaying specific proteins. It comprises a metal (e.g. titanium) wire whose surface has been oxidized and then covalently attached to a ligand capable of interacting biospecifically and reversibly with the protein in question. Binding of the complementary protein to the electrode results in a measurable change in electric potential relative to that given by a reference electrode. The latter is prepared in a similar way but lacks the specific ligand.

affinity electrophoresis *or* **affinoelectrophoresis** a type of **electrophoresis** in which the support medium contains an agent, immobilized by entrapment or by covalent linkage, that interacts specifically and selectively with certain of the components of the mixture to be analysed, thereby altering the electrophoretic mobility of those components.

affinity-elution chromatography a technique in which a compound that is nonspecifically bound to the matrix of a chromatographic column is specifically eluted by binding to a ligand in the eluting solvent. **Biospecific-elution chromatography** is a variant of this technique.

affinity gel any gel that serves as an **affinity matrix**.

affinity-isolated *an alternative term for* **affinity-purified**.

affinity label an active-site-directed irreversible inhibitor of an enzyme, antibody, or other protein. It is a chemically reactive compound that resembles a substrate or other specific ligand and bonds covalently to the active site or specific site on the protein. The affinity labelled groups can then be identified by **fingerprinting** and thus reveal the composition at the active site. It is sometimes termed **Trojan horse inhibitor**.

affinity matrix *or* **affinity support** any supporting material to which the biospecific reagent is attached in **affinity chromatography**.

affinity precipitation the precipitation of an enzyme by a homo- or hetero-bifunctional derivative of its coenzyme or/and a substrate or inhibitor. An example is the precipitation of **lactate dehydrogenase** by $N^{2\prime}$-adipodihydrazido-bis-(N^6-carbonylmethyl-NAD), a reactive derivative of its coenzyme, NAD.

affinity-purified *or* **affinity-isolated** describing a specified substance, usually a biological macromolecule such as an antigen or antibody, that has been purified (or isolated) by a technique such as **affinity chromatography** or **affinity electrophoresis**, thus implying high purity.

affinity support *an alternative term for* **affinity matrix**.

affinoelectrophoresis *an alternative term for* **affinity electrophoresis**.

afibrinogenemia *or (esp. Brit.)* **afibrinogenaemia** *see* **fibrinogen**.

aflatoxin any of a group of related and highly toxic secondary metabolites (**mycotoxins**) produced by strains of the moulds *Aspergillus flavus* or *A. parasiticus,* together with further metabolites of these mycotoxins. Their main structural feature is a fused coumarin–bis(dihydrofuran) ring system. The most important are aflatoxins B_1, B_2, G_1, and G_2 – so designated from the colour of their fluorescence (B, blue; G, green). The mycotoxins are produced naturally by the moulds growing on various seed crops, especially groundnuts (peanuts), and certain cereals (e.g. maize) during storage under moist conditions. They are acutely toxic and highly carcinogenic to many species of animals (including humans), and are responsible for turkey X disease. The main organ affected is the liver; aflatoxin B_1 is the most potent hepatocarcinogen known. **Aflatoxicosis** is a form of human hepatitis with jaundice, ascites and other signs of hepatic failure and has a high mortality. The term is derived as a contraction of *A. flavus* toxin.



aflatoxin B_1

***Afl*II** a type 2 **restriction endonuclease**; recognition sequence: C↑TTAAG.

AFLP *abbr. for* amplification fragment length polymorphism. The use of the **polymerase chain reaction** to amplify DNA in the study of **restriction fragment length polymorphism**.

A form 1 A form of DNA (*abbr.*: A-DNA *or* DNA-A); the molecular conformation adopted by fibres of the sodium salt of duplex DNA at a relative humidity of 75% or less. It consists of a right-handed double helix containing about 11 nucleotide residues per turn, with the planes of the base pairs inclined at about 70° to the axis of the helix. Unlike the **B form** of DNA it has a large hole (≈0.8 nm diameter) at the axis and a very deep major groove. *See also* **C form**, **Z form**. **2** A form of RNA (*abbr.*: A-RNA); the molecular conformation of double-stranded regions of RNA that is favoured at low-salt concentrations and moderate temperatures; it resembles the A form of DNA. (*see* def. 1).

AFP *abbr. for* α-fetoprotein.

African pygmyism a type of dwarfism, similar in appearance to the pituitary variety, due mainly to failure of the growth acceleration that is normal at puberty. It results from absence of the normal increase in levels of insulin-like growth factor-I (IGF-I) characteristic of this growth phase. Plasma somatotropin level is normal and there is a lack of responsiveness to exogenous somatotropin. *See* **insulin-like growth factor**.

Ag 1 *abbr. for* antigen. **2** *symbol for* silver.

AGA 1 a codon in non-mitochondrial mRNA for L-arginine. **2** a codon in human mitochondrial mRNA for chain termination. **3** *abbr. for N*-acetylglutamic acid.

agamic reproduction *see* **asexual reproduction**.

agammaglobulinemia *or (esp. Brit.)* **agammaglobulinaemia** a disease characterized by early onset of recurrent infections, profound hypogammaglobulinemia (of IgM, IgA, and IgG) and almost total absence of B lymphocytes in the peripheral circulation. An X-linked form is associated with over 400 mutations in a locus for Bruton's tyrosine protein kinase at Xq22. An autosomal recessive form is associated with at least four mutations in a locus at 14q32.3 encoding the mu heavy chain.

agamogeny the development of a new individual from a single cell. *Compare* **vegetative reproduction**.

agar *or* **agar-agar** a complex sulfated galactan extracted from certain seaweeds, especially *Gelidium* and related genera. The two main components are **agarose** and **agaropectin**. Agar forms an aqueous gel suitable for the solidification of microbiological culture media and for use as a support medium in zone electrophoresis or (immuno)diffusion techniques. It is not metabolized by most organisms. The gelling temperature varies from about 25 to 35 °C for different types of preparation. The gel is then stable to about 90 °C.

agar-diffusion method a method for determining the sensitivity of a microorganism to an antimicrobial drug. The zone of growth inhibition is measured around a ditch, hole, or a filter-paper disk containing the drug and located on an agar culture medium seeded with the microorganism in question.

agarobiose 4-*O*-*β*-D-galactopyranosyl-3,6-anhydro-L-galactose; a **disaccharide** that forms the basic unit of **agarose**.



agarabiose

agaropectin a charged component of **agar** consisting of a mixture of polysaccharides containing D-galactose, 3,6-anhydro-L-galactose, and monoesterified sulfuric acid units. Samples from some algae may contain other components such as pyruvate, L-arabinose, and D-glucuronate units.

agarose an essentially uncharged component of **agar** comprising a ≈120 kDa alternating carbohydrate polymer. It consists of -3)D-Gal*p*-(*β*1-4)-3,6An-L-Gal*p*(*α*1 repeating units, containing small amounts of ionized sulfate and pyruvate groups. It is widely used as a matrix in zone and immunoelectrophoresis, immunodiffusion, and gel filtration and affinity chromatography. *See also* **agarobiose**.

AGC a codon in mRNA for L-serine.

AGE *abbr. for* **advanced glycation product**.

age-1 a gene encoding a phosphatidylinositol 3-kinase in *Caenorhabditis elegans* that functions downstream of the *daf-2* gene product (a receptor like that for insulin). Partial loss-of-function mutations in *age-1* and *daf-2* result in a long-lived phenotype with resistance to killing by several pathogenic bacteria.

agenized flour *see* **methionine sulfoximine**.

AGE receptors *see* **advanced glycation product**.

AGG 1 a codon in non-mitochondrial mRNA for L-arginine. **2** a codon in human mitochondrial mRNA for chain termination.

agglutinate 1 to adhere or cause to adhere. **2** to cause the clumping of cells, particles, etc., or to undergo such clumping.

agglutination 1 the act or process of adhering. **2** the process in which suspended cells or other **antigen** coated particles clump together when **antibody** is added due to an antigen–antibody reaction. **3** the result of such a process. *See also* **agglutinin**.

agglutinin an **antibody** that has the ability to agglutinate the corresponding antigen, e.g. when the antigen is present on the surface of a suspended cell or other particle.

agglutinogen an **antigen**, usually particulate, that stimulates the production of **agglutinin**.

aggrecan the major proteoglycan of cartilage. It has approximately one **glycosaminoglycan** chain for every 20 amino-acid residues, and a total mass of about 3 MDa. It assembles with glycosaminoglycans, especially hyaluronan, into aggregates several micrometres in diameter. *See also* **versican**.

aggregate 1 formed of separate units or particles collected into a whole or into larger units. **2** an assemblage or sum of many separate units or particles. **3** to form or be formed into a single body or larger body.

aggregation 1 the process of forming an **aggregate** (def. 2). **2** a cluster or group of particles held together into larger units.

aggregation number the number of monomers of an amphipathic substance that form a micelle under any particular conditions.

aggresome an inclusion body within cells that is formed in response to excessive misfolded protein.

aggressin a diffusible nontoxic substance produced by a microorganism that promotes the invasive power of the microorganism in the host.

aglucon *or (formerly)* **aglucone** an **aglycon** derived from a glucoside (i.e. where the sugar moiety was a glucose residue).

aglycon *or* **aglucon** *or (formerly)* **aglycone** *or* **aglucone** the part of any **glycoside** that remains after the sugar moiety has been chemically or enzymically removed.

agmatine 1-amino-4-guanidobutane; a putative endogenous ligand for **imidazoline receptors**, synthesized from arginine by the enzyme arginine decarboxylase (EC 4.1.1.19). In some invertebrates, e.g. the sponge *Geodia gigas,* and some cephalopods, the guanidine group can undergo phosphorylation to phosphoagmatine, which acts as a **phosphagen**.

agnotobiotic pertaining to the growth of organisms of a single species in the presence of one or more other species of which at least one is unknown. *Compare* **synxenic**.

+agogue *or (US)* **+agog** *suffix* denoting an agent that elicits or enhances the secretion of the indicated substance. [From the Greek *ag* + *gos*, leading, drawing forth.] **—+agogic** *adj.*

agonist any ligand, especially a drug or hormone, that binds to receptors and thereby alters the proportion of them that are in an active form, resulting in a biological response. A conventional agonist increases this proportion, whereas an **inverse agonist** reduces it. *See also* **full agonist**, **partial agonist**. *Compare* **antagonist**. **—agonistic** *adj.*

agouti signal protein *abbr.*: ASP; a protein (131 amino acids) encoded at 20q11.2 that stimulates pheomelanogenesis. It is an antagonist of melanocyte-stimulating hormone (MSH) at the latter's G-protein coupled receptor. *See* **pheomelanin**.

AGP *abbr. for* **arabinogalactan protein**.

Agranoff's turtle a zoomorphic mnemonic for avoiding the confusion that has tended to occur over the numbering of the carbon atoms of *myo*-inositol and its chiral derivatives, especially when their Haworth projections are converted into diagrams representing their normal chair conformations. The chair conformation of the parent compound is likened to a turtle, with its body corresponding to the C_6 ring, its coplanar limbs and tail representing the five equatorial hydroxyl groups, and its erect head the axial hydroxyl group. The turtle is viewed from above; then, for derivatives named as members of the d series, numbering of the turtle's appendages proceeds counterclockwise, commencing with its right front paw (i.e. its *dextro* 'hand'), which is designated 1d; its head becomes 2d, its left front paw is 3d, and so on around its body. Conversely, numbering of the l series of derivatives commences with the left front paw (the *laevo* 'hand'), designated 1l, and then proceeds clockwise, the head becoming 2l, and so on. [After its originator Bernard William Agranoff (1926–), who devised it in 1978.]

agrin a component of the synaptic basal lamina that causes aggregation of acetylcholine receptors and acetylcholinesterase on the surface of muscle fibres of the neuromuscular junction. It occurs in embryonic nervous tissue and muscle, especially during early development. At least five different forms arise by alternative splicing; they differ in their acetylcholine receptor clustering activity. They contain **EGF**-like domains.

Agrobacterium a genus of Gram-negative aerobic rod-shaped soil bacteria. Most strains can initiate formation of galls in plants (*see* **crown-gall disease**). A feature of the infection of plants by *Agrobacterium* species is that the bacterium can subvert the host plant tissue to produce amino acids known as **opines**, which the bacterium can use as an energy, carbon, and nitrogen source. The type of opine produced is determined by the bacterial strain. Continued presence of the bacteria is not necessary for transformation of the cells of the host plant. Transformation by *Agrobacterium tumefaciens* has been shown to be due to large plasmids (140 – 235 kb). These are known as tumour-inducing, or Ti plasmids, and they have been exploited in the production of **transgenic** plants.

agrochemical a chemical that is used in agriculture or horticulture, especially as a biocide, fertilizer, etc.

agroclavine 8,9-didehydro-6,8-dimethylergoline; a nonpeptide **ergot** alkaloid.

agropine an **opine**; a rare amino-acid derivative that is produced by a certain type of crown-gall tumour. The genes responsible for its synthesis are part of the T-DNA from a **Ti plasmid**. *See also* **crown-gall disease**.



AGU a codon in mRNA for L-serine.

Ah *abbr. for* aromatic hydrocarbon; the name of a genetic locus in higher organisms that governs biological responses to some aromatic hydrocarbons. The proteins it encodes include cytochrome P450 1A1, a liver microsomal monooxygenase that oxidizes a variety of unrelated compounds, including xenobiotics such as the environmental carcinogens, benzo[a]pyrene and 3-methylcholanthrene. This enzyme is induced by these compounds and, more potently, by polychlorinated biphenyls such as 2,3,7,8-tetrachlorodibenzo-*p*-dioxin (TCDD), acting through the **Ah receptor**. The 5′-flanking region of the gene for this enzyme contains several short sequence motifs known as **xenobiotic response elements** (XREs). *See* **ARNT**.

ahnak a human gene that encodes a giant protein of ≈700 kDa with a large internal domain (≈4300 amino acids) of highly conserved repeated sequences, much of which are 128 amino-acid residues in length and contain a heptad repeat. The ahnak protein is found in human nuclei and is of unknown function. [From Hebrew *Ahnak,* giant.]

Ah receptor *abbr. for* aryl hydrocarbon receptor; a protein, encoded by the **Ah** gene, that binds a number of aryl hydrocarbons and mediates their biochemical and toxic effects. It is activated when it binds a ligand, and then translocates from the cytoplasm to the nucleus, where it is believed to enhance gene transcription by binding to the **xenobiotic-response element** sequence. It contains a basic helix-turn-helix motif; the DNA-binding form is a heterodimer of this protein and **ARNT**.

εAhx *or (formerly)* **εAcp** *symbol for* a residue of the ε-amino acid 6-aminohexanoic acid (formerly known as ε-aminocaproic acid).

aHyl *symbol for* a residue of the α-amino acid L-allohydroxylysine; *threo*-5-hydroxy-L$_s$-lysine.

AIB *abbr. for* 2-aminoisobutyric acid.

AICAR *abbr. for* 5-amino-4-imidazolecarboxamide ribonucleotide (an intermediate in **purine biosynthesis**).

AICAR transformylase *see* **phosphoribosylaminoimidazolecarboxamide formyltransferase**.

AIDS *abbr. for* acquired immunodeficiency syndrome.

AIF *abbr. for* **apoptosis inducing factor**.

aIle (AIle) *symbol for* a residue of the α-amino acid L-alloisoleucine, (2*S*,3*R*)-2-amino-3-methylpentanoic acid.

AIR *abbr. for*. for 5-aminoimidazole ribonucleotide, an intermediate in **purine biosynthesis**.



AIR carboxylase *see* **phosphoribosylaminoimidazole carboxylase**.

AIRE *abbr. for* **autoimmune regulator**.

air-lift bioreactor a bioreactor in which the reaction medium is kept mixed and gassed by the introduction of air or another gas at the base of a column-like reactor.

***Air* RNA** a noncoding RNA required for silencing *Igf2r*/*Slc22a*/*Slc22a3* genes on the paternally imprinted mouse chromosome 17.

ajmaline ajmalan-17,20-diol; an alkaloid from the roots of *Rauwolfia serpentina*. It is used clinically as an antihypertensive and antiarrhythmic, having the effect of normalizing heart rhythm.



AK *(in clinical biochemistry) abbr. for* adenylate kinase.

AKAP *abbr. for* A-kinase anchor protein *or* cAMP-dependent protein kinase anchor protein; a protein that anchors the kinase to cytoskeletal and/or organelle-associated proteins, targeting the signal carried by cyclic AMP to specific intracellular effectors. The N-terminal region, which is highly basic, is required for interaction with **calmodulin**.

akaryotic describing a cell without a nucleus.

akee *a variant spelling of* **ackee**.

AKH *abbr. for* adipokinetic hormone.

A-kinase an enzyme that phosphorylates target proteins in response to a rise in intracellular **cyclic AMP**. *See* **cyclic AMP-dependent protein kinase**.

Akt *see* **protein kinase B**.

Akt the mouse or human homologue of v-*akt*, the oncogene of the transforming retrovirus AKT8. v-*akt* encodes a serine/threonine protein kinase that contains an SH2 domain.

AKT1 a protein that serves as an inward rectifier channel for K^+ ions in root cells of *Arabidopsis thaliana*. It is a member of the **shaker** superfamily of voltage-gated ion channels, and is a homotetramer in which each subunit contains six transmembrane segments.

al+ *prefix* denoting an acyclic monosaccharide or monosaccharide derivative. *See also* **aldehydo-**.

+al *suffix* denoting an unbranched acyclic mono- or dialdehyde.

Al *symbol for* aluminium.

Ala *symbol for* a residue of the α-amino acid L-alanine, 2-aminopropanoic acid (alternative to A).

βAla *symbol for* a residue of the β-amino acid β-alanine, 3-aminopropanoic acid.

ALA *or* **dALA** *abbr. for* δ-aminolevulinate.

Ala AT *or* **ALAT** *(in clinical biochemistry) (formerly) abbr. for* alanine aminotransferase. ALT is preferred.

ALA dehydratase *see* **porphobilinogen synthase**.

Alagille syndrome a rare autosomal recessive disorder characterized by intrahepatic cholestasis and developmental abnormalities in many structures including liver, skeleton, heart, eyes, and face. It is associated with over 35 microdeletions or other mutations in a locus at 20p12 for Jagged-1, a one-pass transmembrane protein that contains 16 EGF repeats in the extracellular region. Jagged-1 is a ligand for Notch receptor, which is crucial for cell fate development in *Drosophila* and mammals. *See* **Notch**. [After Daniel Alagille (1925–), French physician.]

alamethicin a linear ionophorous antibiotic polypeptide containing a high proportion of 2-methylalanine residues and blocked at both ends. *See also* **peptaibophols**.

Ac-2-MeAla-L-Pro-2-MeAla-L-Ala-2-MeAla-L-Ala-
L-Gln-2-MeAla-L-Val-2-MeAla-Gly-L-Leu-
2-MeAla-L-Pro-LVal-2-MeAla-2-MeAla-L-Glu-
L-Gln-L-phenylalaninol

alaninal the aldehyde obtained by reduction of the carboxyl group of alanine.

alaninate **1** alanine anion, the anion $CH_3–CH(NH_2)–COO^–$. **2** any salt containing alanine anion. **3** any ester of alanine.

alanine *the trivial name for* α-aminopropionic acid; 2-aminopropanoic acid; $CH_3–CH(NH_2)–COOH$; a chiral α-amino acid. L-alanine *(symbol*: A *or* Ala), (*S*)-2-aminopropanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: GCA, GCC, GCG or GCU. In mammals, it is a non-essential dietary amino acid, and is glucogenic. Residues of D-alanine *(symbol*: D-Ala *or* DAla), (*R*)-2-aminopropanoic acid, are found in cell-wall peptidoglycans of various bacterial species, and in other materials, e.g. **cyclosporin**.



L-alanine

β-alanine *symbol*: βAla; *the trivial name for* β-aminopropionic acid; 3-aminopropanoic acid; $H_2N–CH_2–CH_2–COOH$; an achiral β-amino acid. It occurs free in brain, and in combination in pantothenate (and hence in coenzyme A), and in the isopeptides anserine and carnosine, but it is not a constituent of proteins. It has an inhibitory effect on the central nervous system.

alanine cycle *see* **glucose–alanine cycle**.

alanine–glyoxylate aminotransferase EC 2.6.1.44; a hepatic peroxisomal pyridoxal phosphate-dependent enzyme that catalyses the reaction:

alanine + glyoxylate = pyruvate + glycine.

Examples from six mammalian species show 78–89% sequence identity. Inactivating mutations in the gene for the human enzyme (392 amino acids) lead to hyperoxaluria type 1.

β-alanine–oxoglutarate aminotransferase *see* **4-aminobutyrate transaminase**.

alanine scanning mutagenesis a strategy for **site-directed mutagenesis** in which the amino acid alanine is substituted in each position that a change is desired.

alanine transaminase *abbr. (in clinical biochemistry)*: ALT; EC 2.6.1.2; *systematic name*: L-alanine:2-oxoglutarate aminotransferase; *other names*: glutamic–pyruvic transaminase; glutamic–alanine transaminase. An enzyme that catalyses the reversible reaction:

L-alanine + 2-oxoglutarate = pyruvate + L-glutamate.

Widely distributed in all tissues and organisms, it is a pyridoxal-phosphate enzyme. In clinical chemistry its assay alongside aspartate transaminase (AST), normally present in plasma in higher concentrations, may be useful as an indicator of liver damage, as levels of ALT are higher in liver than those of AST, in contrast to other tissues. In hepatitis, plasma levels of ALT may exceed those of AST.

alaninium alanine cation, $CH_3–CH(NH_3^+)–COOH$.

alanino the alkylamino group, CH_3–CH(COOH)–NH–, derived from alanine.

alaninol the alcohol obtained by the successive reduction of the carboxyl group of alanine.

alanyl the acyl group, CH_3–CH(NH_2)–CO–, derived from alanine.

alarmone any signal molecule that serves to reorient a cell's economy in response to stress. Such molecules include ppGpp, which is produced, e.g., in microorganisms, in response to growth-rate limitation caused by amino-acid stress and acts to correct this in various ways, and diadenosine tetraphosphate (ApppppA), which stimulates proliferation when DNA replication is halted at a replication fork.

ALA synthetase *see* **5-aminolevulinate synthase**.

ALAT *See* **Ala AT**.

albinism a heterogeneous group of disorders in which there is congenital reduction in the synthesis of **melanin** from tyrosine. It was first listed in 1908 by the British physician Archibald Garrod (1857–1936) in his lecture entitled 'Inborn Errors of Metabolism'. Melanism involving the melanocytes of the skin, hair and eyes is called **oculocutaneous albinism** (OCA), whereas melanism affecting primarily the retinal pigment epithelium is termed **ocular albinism** (OA). Three major types of OCA have been characterized. OCA1 (tyrosine-negative) results from numerous mutations in the locus for tyrosinase (**monophenol monooxygenase**) at 11q14-q21. The degree of pigmentation varies with the amount of residual enzyme activity. OCA2 (tyrosine-positive, P-related) results from many mutations in P protein (838 amino acids), a putative transmembrane protein of melanosomes, encoded at 15q11.12. OCA3, reported only in persons of African origin, is due to mutation in tyrosinase-related protein 1 (537 amino acids, encoded at 9p23), which is important for stabilizing tyrosinase in melanocytes. OC1, the major form of ocular albinism, is associated with many mutations of a locus at Xp22 encoding a glycoprotein of the melanosomal membrane.

Albright syndrome *or* **hereditary osteoarthropathy** an uncommon autosomal dominant disorder. Type 1a is characterized by short stature, obesity, skeletal defects, and rounded facies. There is resistance to parathyroid hormone, thyrotropin, and gonadotropins, the activity of which is coupled to stimulation of adenylate cyclase in target cells. The alpha subunit of G-protein S ($G_{S\alpha}$) in affected persons is present at half the normal levels in tissues. This is due to any of some 30 mutations in a locus at 20q13.11, which encodes for the $G_{S\alpha}$ subunit (comprising 394 residues). In type 1b, the physical appearance is normal and hormone resistance is limited to the effect on kidneys of parathyroid hormone. *See* **G-protein**. [After Fuller Albright (1900–1969), US physician.]

albumin any of a group of globular proteins that are soluble in distilled water and solutions of half-saturated ammonium sulfate, but insoluble in fully saturated ammonium sulfate solutions. **Serum albumin**, the major protein of serum, has a good binding capacity for water, Ca^{2+}, Na^+, K^+, fatty acids, hormones, bilirubin, and drugs. Its main function is to regulate the colloidal osmotic pressure of blood; it has structural similarity to **α-fetoprotein** and **vitamin D binding protein**. *See also* **endosperm albumin**, **lactalbumin**, **ovalbumin**, **serum albumin**. [The name originates from Latin *albus,* white, as it exists in nearly pure form in egg-white, from which it was easily obtained by the ancients.]

albuminoid 1 of, or relating to, an **albumin**. **2** *an alternative name for* **scleroprotein**.

albuminuria the presence of excessive amounts of protein in the urine. It is usually a sign of renal disease.

albuterol *see* **salbutamol**.

Alcalase *the proprietary name for* a proteolytic enzyme preparation obtained by fermentation of a strain of *Bacillus subtilis*. It is characterized by stability and activity at high temperatures and alkaline pH values, and is used in enzymic laundering and various industrial processes.

alcapton 2,5-dihydroxyphenylacetic acid. *See* **alcaptonuria**, **homogentisate**.

alcaptonuria *or* **alkaptonuria** a rare autosomal recessive disorder, first studied by the British physician Archibald Garrod (1857–1936), caused by virtual absence of **homogentisate 1,2-dioxygenase** and characterized by ochronosis and arthritis. There is inability to metabolize further the homogentisate produced by the normal metabolism of phenylalanine and tyrosine. Homogentisate therefore accumulates in the body and is excreted in the urine, which gradually turns dark as homogentisate is oxidized to a melanin-like product – a process speeded up at an alkaline pH. The deficiency is associated with more than 20 mutations of the gene locus at 3q21-q23.

alcohol 1 any of a class of alkyl compounds containing a hydroxyl group. An alcohol is called primary, secondary, or tertiary according to whether the carbon atom bearing the hydroxyl group is itself attached to one, two, or three other carbon atoms. **2** specifically, ethyl alcohol, ethanol. *See also* **absolute alcohol**. **—alcoholic** *adj., n.*

alcohol dehydrogenase any of the nicotinamide-nucleotide-linked dehydrogenase enzymes of groups EC 1.1.1.1 (NAD^+) or EC 1.1.1.2 ($NADP^+$) that catalyse the oxidation of alcohols to aldehydes. These are zinc proteins. Also EC 1.1.1.71, alcohol dehydrogenase [$NAD(P)^+$]; *other name*: retinal reductase; EC 1.1.99.8, alcohol dehydrogenase (acceptor), a quinoprotein.

alcoholic fermentation the conversion of glucose to ethanol by a group of reactions that are characteristic of yeast.

alcoholism a common disease caused by prolonged abuse of alcoholic (i.e. ethanol-containing) beverages. A genetic predisposition can be demonstrated in some individuals. Fatty liver develops rapidly after an episode of acute abuse, and chronic abuse leads to hepatic cirrhosis, cardiomegaly, premature atherosclerosis, and brain atrophy. Ethanol is metabolized by alcohol dehydrogenase (ADH) to acetaldehyde, which is then oxidized to acetate by aldehyde dehydrogenase (ALDH). An inactive form of an isozyme of ADH (ADH20) is transmitted as an autosomal dominant trait in a high percentage of Orientals and is caused by an inactivating polymorphism. The mitochondrial isozyme of ALDH (ALDH20) is also common in Orientals. Both defects increase the vulnerability to alcoholism of those who carry them.

alcohol oxidase *abbr.*: AOX *or* **methanol oxidase** *abbr.*: MOX; EC 1.1.3.13; a flavoprotein (FAD) enzyme that catalyses the oxidation by dioxygen of a primary alcohol to the corresponding aldehyde. It is important in methylotrophic yeasts, in which it is the first enzyme in the pathway for utilization of methanol, converting this to formaldehyde, thence to CO_2.

alcoholysis the solvolysis of a covalent derivative of an acid by a reaction in which one of the products combines with the H atom of an alcohol's hydroxy group and the other product with the alcohol's alkoxy group.

aldaric acid any dicarboxylic acid formed by oxidation of both terminal groups of an **aldose** to carboxyl groups. There are three tetraric acids (D-, L-, and *meso*-tartaric acids), four pentaric acids (D- and L-arabinaric acids, xylaric acid [*meso*], and ribaric acid [*meso*]), and ten hexaric acids (D- and L-glucaric acids, D- and L-idaric acids, D- and L-mannaric acids, D- and L-talaric acids, allaric acid [*meso*], and galactaric acid [*meso*]).

aldehyde 1 *an alternative name for* the **formyl** group, –CHO. **2** any organic compound with the formula R–CH=O. *Compare* **ketone**. **—aldehydic** *adj.*

aldehyde dehydrogenase any enzyme that catalyses the oxidation of an aldehyde group to a carboxylic acid. Many examples are known, acting specifically on a wide range of substrates. Those acting on aliphatic aldehydes are divided into four classes. Class 1, or Ald C, are tetrameric cytosolic enzymes, and include aldehyde dehydrogenase (NAD^+), EC 1.2.1.3; *systematic name*: aldehyde:NAD^+ oxidoreductase; an enzyme of wide specificity that contains molybdenum cofactor. This EC designation also includes Class 2 enzymes, or Ald M, which are tetrameric mitochondrial enzymes. Class 3, or Ald D, are dimeric cytosolic enzymes, and include aldehyde dehydrogenase [$NAD(P)^+$], EC 1.2.1.5; *systematic name*: aldehyde:$NAD(P)^+$ oxidoreductase.

aldehyde ferredoxin oxidoreductase an enzyme that catalyses the reversible oxidation of aldehydes to the corresponding carboxylic acid, using ferredoxin as an electron acceptor. Containing tungsten-pyranopterin and 4[Fe-45] clusters, the enzyme has remarkable thermostability.

aldehydo- *abbr.*: al-; *prefix* designating an uncyclized monosaccharide or monosaccharide derivative. It is used in (semi)systematic nomenclature to stress the acyclic nature of such compounds. *Compare* **keto-**.

aldimine any **imine** that is an analogue of an aldehyde; the general structure is RCH=NR where R may be any organyl group or H. *Compare* **ketimine**.

alditol any polyhydric alcohol derived from the acyclic form of a **monosaccharide** by reduction of its aldehyde or keto group to an alcoholic group. Older names for these compounds include glycitol and sugar alcohol.

aldo+ *prefix* indicating aldehydic; e.g. aldohexose.

aldoketose any monosaccharide derivative containing both a (potential) aldehydic carbonyl group and a (potential) ketonic carbonyl group.

aldol **1** any organic compound that is both an aldehyde and an alcohol, especially where the two functions are separated by two linked carbon atoms in accordance with the general structure: HO–C–C–CH=O. **2** *the trivial name for* acetaldol (3-hydroxybutanal), a compound formed by the self-condensation of two acetaldehyde molecules.

aldolase **1** *a generic name for* nearly every enzyme of the sub-subclass EC 4.1.2, the aldehyde-lyases, enzymes catalysing aldol condensations and their reversal. **2** *abbr. (in clinical biochemistry)*: ALS; *common name for* the enzyme fructose-bisphosphate aldolase; EC 4.1.2.13; *systematic name*: D-fructose-1,6-bisphosphate D-glyceraldehyde-3-phosphate-lyase; *other name*: fructose-1,6-bisphosphate triosephosphate-lyase. An enzyme that catalyses the reversible fission of D-fructose 1,6-bisphosphate to glycerone phosphate and D-glyceraldehyde 3-phosphate. It acts also on (3*S*,4*R*)-ketose 1-phosphates. In humans, aldolase A (genetic locus at 16q22-q24) occurs in erythrocytes, muscle, and fibroblasts; aldolase B (9q22.3) occurs in liver, kidney, and small intestine; and aldolase C (chromosome 17) occurs in brain. All three have homologous sequences, form homotetramers, and cleave D-fructose 1,6-bisphosphate and D-fructose 1-phosphate but at different rates. A and C are constitutive whereas B is under dietary control (low during fasting, increased by carbohydrate intake). Deficiency of aldolase A results in a nonspherocytic anemia or in a largely myopathic condition. Deficiency of aldolase B results in **hereditary fructose intolerance**.

aldol condensation the base-catalysed addition reaction of two aldehydes or an aldehyde and a ketone to form an **aldol** (def. 1).

aldonic acid a monocarboxylic acid having a chain of three or more carbon atoms and formally derived from an **aldose** by oxidation of the aldehydic group.

aldopentose any of the eight possible five-carbon-atom **aldoses**.

aldopyranose any **aldose** in the **pyranose** form.

aldose a monosaccharide in which the (potential) carbonyl group is terminal (i.e. aldehydic). The term is frequently modified to indicate the number of carbon atoms in the chain, as in aldotriose, aldotetrose, etc.

aldosterone 11*β*,21-dihydroxy-3,20-dioxopregn-4-en-18-al; the most powerful naturally occurring mineralocorticoid hormone, originally named **electrocortin** by its discoverers Sylvia Simpson and James Tait in 1954. The name was changed to aldosterone after its structure had been determined by **Reichstein** in 1953. It exists in solution as an equilibrium mixture of the aldehyde and the hemiacetal formed with the hydroxyl at position 11. Produced by the cells of the zona glomerulosa of the adrenal cortex, its main action is to increase reabsorption of sodium ions by the distal renal tubules and thus to regulate water and electrolyte metabolism. The biosynthesis of aldosterone is stimulated by angiotensin II (*see* **angiotensin**, **renin–angiotensin system**), **corticotropin**, and increased potassium-ion concentrations. 11-Deoxycorticosterone is converted into aldosterone by **aldosterone synthase**. Aldosterone exerts its effects through binding to cytosolic receptors. The resulting complex is transferred to the nucleus, where it acts to stimulate production of mRNA for sodium transport proteins. The action is thus on a timescale of many minutes.



aldehyde form



hemiacetal form

aldosterone synthase EC 1.14.15.4; *recommended name*: steroid 11*β*-monooxygenase; *other names*: cytochrome P450 11B2; steroid 18-hydroxylase; P450C18. A heme–thiolate enzyme that converts 11-deoxycorticosterone to aldosterone, by successive hydroxylations at the 11*β* and 18 positions. Reduced adrenodoxin is a reactant, being converted to oxidized adrenodoxin. The enzyme is normally expressed in the glomerulosa region of the adrenal cortex. Mutations in the CYP11B2 gene at 8q22 are associated with an autosomal recessive disorder that is potentially fatal in infants or may be asymptomatic in adults. ?

aldotetrose any of the four possible four-carbon-atom **aldoses**.

aldotriose either D- or L-glyceraldehyde; *see* **aldose**.

ALDP *abbr. for* adrenoleukodystrophy protein; a half-transporter of the ABC transporter superfamily that is encoded by a locus at Xp28 (gene product contains 745 amino acids) and is believed to function in transporting very-long-chain fatty acids across peroxisomal membranes. Over 300 mutations are associated with X-linked adrenoleukodystrophy, a condition in which tissues and body fluids have high levels of these fatty acids, particularly hexacosanoic acid (26:0).

aldrin 1,2,3,4,10,10-hexachloro-1,4,4a,5,8,8a-hexahydro-1,4:5,8-dimethanonaphthalene; an organochlorine compound formerly used as an insecticide, but now banned in certain countries on account of its toxicity.



aleurain a protease synthesized during seed germination in barley. It is a homologue of *γ*-oryzain and of human lysosomal cathepsin H, and localizes in a lysosome-like vacuole in aleurone cells. The active mature protein (362 amino acids) is derived by proteolytic cleavge from a larger inactive precursor.

aleuron *or* **aleurone** **1** granules of insoluble protein found in plant cells, especially in the seeds of cereals, where they appear to act as storage material. **2** the single layer of cells on the outside of the endosperm of cereal seeds containing such granules. Translocated **gibberellins** stimulate the cells to synthesize α-amylase, which is secreted into the endosperm to hydrolyse the stored starch.

aleuroplast any colourless **plastid** or **leukoplast** storing protein. Aleuroplasts are found in plant cells, particularly seeds.

Alexander disease a degenerative neurological disease of infantile, juvenile, or adult onset in which there is lack of myelin in the central nervous system and enlarged astrocytes rich in cytoplasmic granules that consist mainly of αB-**crystallin**. The gene at 11q13 corresponds to that for flavoprotein 1 of complex I (i.e. NADH dehydrogenase (ubiquinone)) of the electron transport chain.

alexin *or* **alexine** *former term for* **complement**; hence **alexinated** means treated with complement.

ALG *abbr. for* anti-lymphocyte globulin.

alga (*pl.* **algae**) any of a group of simple eukaryotic photosynthetic protists. They may be unicellular or multicellular, and are generally aquatic. The prokaryotes formerly called blue-green algae are now known as **cyanobacteria**. **—algal** *adj.*

algicide any chemical agent that selectively kills algae.

algin the sodium salt of **alginic acid**

alginate lyase EC 4.2.2.3; *recommended name*: poly(*β*-D-mannuronate) lyase; *systematic name*: poly(*β*-D-1,4-mannuronide) lyase. An enzyme that catalyses a reaction resulting in eliminative cleavage of polysaccharides containing *β*-D-mannuronate residues to give oligosaccharides with 4-deoxy-*α*-L-*erythro*-hex-4-enopyranuronosyl groups at their ends.

alginic acid a hydrophilic polysaccharide (≈240 kDa) occurring in brown algae (brown seaweeds), especially the Californian giant kelp (*Macrocystis pyrifera*) and horsetail kelp (*Laminaria digitata*). Sodium alginate is used commercially as an emulsifier and thickener in foodstuffs, pharmaceuticals, etc. It has an interrupted structure of stretches of *α*1-4-linked *α*-L-gulopyranosyluronic acid residues, stretches of *β*1-4-linked *β*-D-mannopyranosyluronic acid residues, and stretches where both uronic acids occur in alternating sequence. Similar glycans are secreted by some bacteria.

algorithm any systematic mathematical procedure that allows a problem to be solved in a finite number of steps. *Compare* **heuristic**, **stochastic**.

alicyclic describing an organic compound derived from a saturated cyclic hydrocarbon. *Compare* **aliphatic**, **aromatic**.

alignment 1 the process of comparing (aligning) linear sequences of amino acid residues or of nucleotide bases by sliding the sequences horizontally with respect to each other, often inserting gaps to bring equivalent regions into register. Sequences are usually aligned (manually or automatically) to assess their degree of similarity and their likely evolutionary relationships. **2** a horizontal stack of sequences, often including gaps, used to highlight regions of structural or functional similarity. Pairwise alignments compare two sequences, multiple alignments three or more. Alignments may be global (i.e. extend over the full length of the sequences) or local (i.e. extend only over short regions or domains); they underpin many sequence analysis methods.

alignment algorithm a method for automatically obtaining **alignments (def. 2)** of pairs of protein or nucleotide sequences. Alignment algorithms are generally either global or local – BLAST (basic local alignment search tool) and FastA are probably the best known implementations of local alignment algorithms, and are routinely used for database searching.

alignment editor software for manually creating and editing sequence **alignments** (e.g. to correct errors of multiple **alignment algorithms**). Such software typically includes options to add and remove gaps and/or sequences, to change the colour scheme, to select motifs, plot property profiles, view structures, etc. Examples include CINEMA (colour interactive editor for multiple alignments) and JalView.

aliphatic describing organic compounds in which the carbon atoms form open (noncyclic) chains. *Compare* **alicyclic**, **aromatic**.

aliquant one of a number of unequal parts of a whole.

aliquot one of number of equal parts of a whole; often used loosely, and erroneously, for a sample.

alizarin 1,2-dihydroxyanthraquinone; the **aglycon** of **ruberythric acid**.

ALK1 *abbr. for* **activin receptor-like kinase 1**.

alkalemia *or (esp. Brit)* **alkalaemia** a condition in which there is increased alkalinity (i.e. lowered hydrogen-ion concentration and hence raised pH) of the blood. *Compare* **acidemia**, **alkalosis**.

alkali any of a class of bases that neutralize acids and are themselves neutralized by acids, and form caustic and/or corrosive aqueous solutions. The term is applied in particular to hydroxides of the **alkali metals**, though the term is often extended to other substances with similar though weaker properties.

alkali metal any element of group 1 of the IUPAC **periodic table**; the group comprises lithium (Li), sodium (Na), potassium (K), rubidium (Rb), cesium (Cs), and francium (Fr).

alkaline 1 having the properties of an **alkali**; basic. **2** describing an aqueous solution having a pH > 7.

alkaline earth any metallic element belonging to group 2 of the IUPAC **periodic table**; the group comprises beryllium (Be), magnesium (Mg), calcium (Ca), strontium (Sr), barium (Ba), and radium (Ra).

alkaline lysis method a procedure for the recovery of plasmid DNA in which the alkaline conditions chosen for lysis of bacterial cells result in the denaturation of genomic DNA and proteins, which are precipitated when the lysate is neutralized with potassium acetate leaving a solution containing plasmid DNA.

alkaline phosphatase *abbr.*: AP; EC 3.1.3.1; *systematic name*: orthophosphoric monoester phosphohydrolase (alkaline optimum); *other names*: alkaline phosphomonoesterase; phosphomonoesterase; glycerophosphatase. A homodimeric or tetrameric zinc glycoprotein that is anchored to the plasma membrane by phosphatidylinositol glycan. Catalytic activity also requires magnesium. In human plasma the level is raised in the last trimester of pregnancy. Plasma levels may also be greatly elevated in cases of Paget's disease of bone, osteomalacia, and cirrhosis or biliary obstruction; levels may become moderately elevated in other types of bone disease. There are four genes for the enzyme in humans. That located at 1p36.1-p34 is for tissue-nonspecific AP, which occurs in liver, bone, and kidney. Three tissue-specific AP genes are located at 2q34-q37 and are expressed into placental AP (*also called* Regan isozyme), intestinal AP, and germ-cell AP. All four isozymes can be distinguished electrophoretically. **Hypophosphatasia**, a hereditary generalized deficiency of tissue-nonspecific AP, presents as rickets in infants and children and as osteomalacia in adults. Numerous mutations associated with this disorder have been reported.

alkaline tide the slight increase in plasma and urine pH that occurs after meals. It is believed to be due to withdrawal of hydrogen ions from the blood during the formation of gastric HCl.

alkali reserve *or* **alkaline reserve** *a term formerly used to denote* the bicarbonate-CO_2 extractable from blood plasma.

alkaloid any member of a broad group of nitrogen-containing basic organic compounds present in various dicotyledonous plants and some fungi. Although only about 5% of the world's plant species have so far been examined, they have yielded over 2000 different alkaloids. Heterocyclic alkaloids derived from amino acids are termed **true alkaloids**. Alkaloids with and without heterocyclic rings and not derived from amino acids are termed **pseudoalkaloids**; in these the carbon skeleton is usually isoprenoid derived. Alkaloids often have marked and specific pharmacological activity.

alkalosis a clinical condition in which total base excess or total acid deficit has the potential to cause decreased hydrogen-ion concentration (i.e. raised pH) in the blood, in the absence of compensating biochemical and physiological changes.

alkane any saturated aliphatic hydrocarbon compound.

alkanet the plant, *Alkanna tinctoria*, and its root, which contains the pigment **alkannin**.

alkannin (*S*)-5,8,-dihydroxy-2-(1-hydroxy-4-methyl-3-pentenyl)-1,4-naphthalenedione; a red pigment derived from the root of the alkanet plant, and used as a dye in cosmetics and food. The (+)(*R*) enantiomer is also a natural product, **shikonin**, and the racemate is known as shikalkin.



alkannin

alkaptonuria *a variant spelling of* **alcaptonuria**.

alkatriene any unsaturated aliphatic hydrocarbon containing two (conjugated or unconjugated) double bonds.

alkatrienyl any group derived from an alkatriene by removal of a hydrogen atom.

alkB a gene of *E.coli* that protects it against cell-killing by SN$_2$-alkylating agents. Its product is a nonheme-iron protein that catalyzes oxidative demethylation of N^1-methyladenine and N^3-methylcytosine in DNA. The reaction requires O$_2$ and 2-oxoglutarate and produces CO$_2$, formaldehyde, succinate, and demethylated substrate.

alkenyl any group derived from an alkene by removal of a hydrogen atom.

1-alkenyl-2-acylglycerol cholinephosphotransferase EC 2.7.8.22; an enzyme that catalyses the formation of the plasmalogen, plasmenylcholine (i.e. 1-alkenyl-2-acylglycerophosphocholine), from CDPcholine and 1-alkenyl-2-acylglycerol with release of CMP.

1-alkenylglycerophosphocholine *O*-acyltransferase EC 2.3.1.104; an enzyme that catalyses the formation of the plasmalogen, plasmenylcholine (i.e. 1-alkenyl-2-acylglycerophosphocholine) from acyl-CoA and 1-alkenylglycerophosphocholine with release of CoA.

alkenylglycerophosphocholine hydrolase EC 3.3.2.2; *other name*: lysoplasmalogenase; a phospholipase involved in the turnover of **plasmalogens**. It catalyses the hydrolysis of 1-(1-alkenyl)-*sn*-glycero-3-phosphocholine to an aldehyde and *sn*-glycero-3-phosphocholine.

1-alkenylglycerophosphoethanolamine *O*-acyltransferase EC 2.3.1.121; an enzyme that catalyses the formation of the **plasmalogen**, 1-alkenyl-2-acyl-glycerophosphoethanolamine, from acyl-CoA and 1-alkenylglycerophosphoethanolamine with release of CoA.

alkenylglycerophosphoethanolamine hydrolase EC 3.3.2.5; a phospholipase enzyme involved in the turnover of **plasmalogens**. It catalyses the hydrolysis of 1-(1-alkenyl)-*sn*-glycero-3-phosphoethanolamine to an aldehyde and *sn*-glycero-3-phosphoethanolamine.

alkyl any group derived from an alkane by the removal of one hydrogen atom. Alkyl groups are often designated by the symbol R.

alkylating agent any of a group of compounds that react with another compound so as to introduce an alkyl group into the second compound.

alkylation the process of replacing a hydrogen atom in a compound by an alkyl group.

1-alkylglycerophosphocholine *O*-acetyltransferase EC 2.3.1.67; an enzyme that catalyses the formation of 1-alkyl-2-acetyl-*sn*-glycero-3-phosphocholine (*see* **platelet-activating factor**) from acetyl-CoA and 1-alkyl-*sn*-glycero-3-phosphocholine with release of CoA. *See also* **1-alkylglycerophosphocholine *O*-acyltransferase**.

1-alkylglycerophosphocholine *O*-acyltransferase EC 2.3.1.63; an enzyme that catalyses the formation of the **ether lipid**, 1-alkyl-2-acyl-*sn*-glycero-3-phosphocholine, from acyl-CoA and 1-alkyl-*sn*-glycero-3-phosphocholine with release of CoA.

O^6-alkylguanine alkyltransferase *see* **O^6-methylguanine**.

alkyne any unsaturated aliphatic hydrocarbon compound containing one or more triple bonds.

alkynyl any group derived from an **alkyne** by the removal of one hydrogen atom.

All *symbol for* allose.

all+ *see* **allo+**.

all-alpha protein *or* **all-α protein** a member of a class of proteins whose predominant core secondary structure elements are alpha helical (*see* **alpha helix**), often packed into bundle-, folded-leaf- or hairpin-array-type folds. For example, DNA/RNA-binding proteins contain a core three-helical bundle with a right-handed twist; anti-sigma factor Asia contains a core of five helices in an orthogonal array; and members of the globin family contain a core of six alpha helices, with a partly opened folded-leaf topology. *Compare* **all-beta protein**.

allantoic acid *or* **diureidoacetate** the end product of **purine** metabolism in mammals and some fish, formed from **allantoin** by a hydrolytic reaction. Most fish metabolize allantoic acid further to urea and glyoxalate. It is widely distributed in plants as an important source of stored nitrogen.



allantoin (2,5-dioxo-4-imidazolidinyl)urea; 5-ureidohydantoin; an intermediate or end product of purine catabolism, formed from uric acid by urate oxidase. In certain animal groups it is converted to allantoic acid.



all-beta protein *or* **all-β protein** a member of a class of proteins whose predominant core secondary structure elements are beta strands or sheets, often packed into sandwich- or barrel-type folds (sandwiches comprise two aligned, twisted beta sheets; barrels comprise a single beta sheet folded back upon itself such that the first strand usually hydrogen-bonds to the last). For example, members of the immunoglobulin family have a sandwich-like fold, with seven strands in two sheets, whereas trypsin-like serine proteases have a duplicated eight-stranded closed barrel fold. *See* **beta configuration**. *Compare* **all-alpha protein**.

allele *or* **allelomorph** any of the forms of the same **gene** that occur at the same **locus** on a homologous chromosome but differ in base sequence. Two or more alleles are said to be **allelic** or **allelomorphic** to each other, and if more than two alleles exist in a population, the locus is said to show **multiple allelism**.

allele-specific oligonucleotide *abbr*.: ASO; an oligonucleotide that is constructed with a DNA sequence homologous to a specific allele. Two ASOs can be made so that they differ in sequence at only one nucleotide base, thereby distinguishing a mutant allele with a point mutation from its corresponding wild-type allele.

allelic exclusion the process by which a cell uses either the gene from its maternal chromosome or the one from the paternal chromosome, but not both. It seems to occur only in genes that encode antibodies and T-cell receptors. Individual B-lymphocytes display allelic exclusion of their heavy and light IgG genes.

allelomorph *another term for* **allele**.

allelopathic agent any plant excretory product that may be autotoxic or affect neighbouring plants, such as salicylate in *Quercus falcata*.

allelozyme any of two or more variants of a particular enzyme (with similar catalytic properties) whose amino-acid sequences are encoded in allelic structural genes (*see* **allele**); a class of **isoenzyme**. *Compare* **multilocus enzyme**.

allergen any **antigen** that stimulates an allergic reaction, inducing a type I hypersensitive reaction. *See* **allergy**, **hypersensitivity**.

allergic of, relating to, or involving **allergy**.

allergy *or* **allergic reaction 1** a state of altered (usually increased) reactivity of the body to foreign material. **2 hypersensitivity**.

allicin 2-propene-1-sulfinothioic acid *S*-2-propenyl ester; an antibacterial compound derived from garlic (*Allium sativum*) and having an odour of garlic.



alliin 3-(2-propenylsulfinyl)-L-alanine; *S*-allyl-L-cysteine sulfoxide; a component of garlic (*Allium sativum*) and other plants that develops an odour of garlic following the action of alliinase (alliin lyase; EC 4.4.1.4).



allitol a *meso*-hexitol; derived formally by reduction of the aldehyde group of either D- or L-allose.

allo+ *or (before a vowel)* **all+** *comb. form* **1** denoting other, dissimilar, different. *Compare* **hetero+** (def. 1), **homo+** (def. 1), **iso+** (def. 1), **xeno+** (def. 1). **2** referring to a dissimilar genome. *Compare* **homo+** (def. 2), **hetero+** (def. 2), **iso+** (def. 2), **xeno+** (def. 2). **3** referring to an isomeric form of an enantiomer of a compound that has more than one pair of enantiomers. *Compare* **iso+** (def. 3), **nor+** (def. 1).

allo+ *prefix* denoting the configuration of a set of four (usually) contiguous >CHOH groups, as in D- or L-allose. *See* **monosaccharide**.

alloalbumin an electrophoretic variant for serum albumin that gives a bisalbuminemia pattern. It is produced by one of various sense mutations in the gene.

alloantigen an antigen that is part of an animal's self-recognition system, e.g. **major histocompatability complex** molecules. When injected into another animal, they trigger an immune response aimed at eliminating them. *Compare* **alloreactivity**.

allocystathionine *see* **cystathionine**.

alloenzyme *an alternative name for* **allozyme**.

allogeneic *or* **allogenic** describing cells, tissues, organisms, etc. that are of different genetic constitution. *Compare* **heterogenic**, **homologous**.

allograft any tissue graft between allogeneic individuals; i.e. from a donor of one genotype to a host of another genotype.

allohydroxylysine *see* **hydroxylysine**.

alloisoleucine *trivial name for* α-amino-β-methylvaleric acid; (2*R**,3*S**)-2-amino-3-methylpentanoic acid, $CH_3–CH_2–CH–(CH_3)–CH(NH_2)–COOH$; an α-amino acid with two chiral centres. Because molecules of alloisoleucine possess a second chiral centre, at C-3, in addition to the chiral centre at C-2 common to molecules of all α-amino acids other than glycine, the enantiomers L-alloisoleucine (*symbol*: aIle), (2*S*,3*R*)-2- amino-3-methylpentanoic acid, and D-alloisoleucine (*symbol*: D-aIle), (2*R*,3*S*)-2-amino-3-methylpentanoic acid, are diastereoisomeric with those of **isoleucine**, (2*R**, 3*R**)-2-amino-3-methylpentanoic acid. L-Alloisoleucine does not occur in peptide linkage in proteins. Residues of D-alloisoleucine are found in the peptidolipid of the actinomycete, *Nocardia esteroides*, and various members of the actinomycin group of antibiotics contain (usually) two residues per molecule.



L-alloisoleucine pic



D-alloisoleucine

allolactose *trivial name for* β-D-galactopyranosyl-(1→6)-D-glucopyranose; an isomer of lactose and the natural intracellular inducer of the ***lac*** **operon** in *Escherichia coli*.



allomerism a state of similarity in the crystalline structures of substances of different chemical composition. —**allomerous** *adj.*

allometric 1 differing in relative growth rates. **2** of or relating to allometry.

allometry 1 the study of the growth of parts of an organism relative to the growth of the whole organism. **2** change in the proportion of any part of an organism occurring during growth.

allomone any chemical substance produced or acquired by an organism that, when it contacts an individual of another species in the natural context, evokes in the receiver a behavioural or developmental reaction adaptively favourable to the transmitter. *Compare* **kairomone**, **pheromone**.

allomorphism variability in the crystalline structure of certain substances having the same chemical composition.

allophycocyanin a **phycobiliprotein** present in small amounts in red algae and cyanobacteria.

allopurinol 4-hydroxypyrazolo[3,4-*d*]pyrimidine; a constitutional isomer of hypoxanthine and a competitive inhibitor of xanthine oxidase (EC 1.2.3.2). It is a synthetic drug used in the treatment of gout and other conditions characterized by raised blood urate content. Patients with gout excrete less urate and more xanthine and hypoxanthine than normal.



alloreactivity the T-cell response to non-self MHC molecules.

all-or-none describing a chemical reaction, or a pharmacological or physiological response, that either occurs to the fullest extent or not at all, depending on the conditions.

allose *symbol*: All; *allo*-hexose; an aldohexose that differs from glucose only in the configuration of the hydroxyl on C-3.

allosteric describing protein molecules that are assumed to possess two or more stereospecifically different, non-overlapping receptor sites. One of these, the **active site**, binds the substrate; the other, the **allosteric site**, is complementary to the structure of another, or the same, metabolite, the **allosteric effector**, which binds specifically and reversibly. The formation of the enzyme–allosteric effector complex does not activate or deactivate a reaction involving the effector itself; it is assumed only to bring about a discrete reversible alteration of the molecular structure of the protein, called **allosteric transition**. This modifies the properties of the active site, changing one or several of the kinetic parameters that characterize the biological activity of the protein. *See also* **Monod–Wyman–Changeux model**.

allosteric activation any activation of an enzyme by a positive **allosteric effector**.

allosteric constant *symbol*: L; the equilibrium constant for the transition between two forms of an **allosteric** protein in the absence of ligand: $L = T_0/R_0$, where T_0 and R_0 are the concentrations of the less affine T-form and the more affine R-form of the protein, respectively. *See* **Monod–Wyman–Changeux model**.

allosteric effect an effect that arises when the reaction of ligands with one site of any polyvalent molecule affects the reaction of ligand(s) at one or more other sites as a result of conformational changes. The reactions may or may not both be reversible; when they are, and represent equilibria, they are **reciprocal effects** or **linked functions**.

allosteric effector a specific ligand that binds to the allosteric site of a protein with different affinities in the two states of the protein (R and T) in the **Monod–Wyman–Changeux model** of allosteric transition. An effector may be described as positive if it has an activating effect, or as negative if it is inhibitory. *See* **allosteric**. *Compare* **autosteric effector**.

allosteric enzyme designating any enzyme that: (1) contains a site topologically distinct from the active site; (2) has multiple subunits with active sites that interact cooperatively; (3) shows sigmoid kinetics; and (4) obeys the concerted model for allosteric proteins. Since all these properties may sometimes, but not always, go together, the term is somewhat imprecise.

allosteric inhibition any inhibition of an enzyme by a negative **allosteric effector**.

allosteric protein a protein that exhibits **allosterism**. *See also* **allosteric**.

allosteric regulation control of the rate of an enzyme or metabolic system by means of **allosteric activation** or **allosteric inhibition**.

allosteric site *see* **allosteric**.

allosteric transition *see* **allosteric**, **Monod–Wyman–Changeux model**.

allosterism *or* **allostery** a property of an enzyme or other macromolecule by which its principal biological reactivity is modified by the binding of an effector to a site other than the binding site of the principal reactant, thereby bringing about a conformational change in the macromolecule such as to alter its principal reactivity. *See* **allosteric**.

allothreonine *trivial name for* α-amino-β-hydroxybutyric acid; (2R*,3R*)-2-amino-3-hydroxybutanoic acid; $CH_3–CH(OH)–CH(NH_2)–COOH$; an α-amino acid with two chiral centres. Because molecules of allothreonine possess a second chiral centre, at C-3, in addition to the chiral centre at C-2 common to all α-amino acids other than glycine, the enantiomers L-allothreonine (*symbol*: aThr), (2S,3S)-2-amino-3-hydroxybutanoic acid, and D-allothreonine (*symbol*: D-aThr), (2R,3R)-2-amino-3-hydroxybutanoic acid, are diastereoisomeric with those of **threonine**, (2R*,3R*)-2-amino-3-hydroxybutanoic acid. [*Note*: the enantiomers of allothreonine may also be named semi-systematically as derivatives of erythrose: L_s-allothreonine in amino-acid nomenclature is synonymous with 2-amino-2,4-dideoxy-L_g-erythronic acid in carbohydrate nomenclature, and D_s-allothreonine with 2-amino-2,4-dideoxy-D_g-erythronic acid (the subscript letters d or g being added to the configurational prefixes where there might be uncertainty regarding the reference centre of chirality; *see* **D/L convention**).] L-Allothreonine does not occur in peptide linkage in proteins; however, one residue per molecule is present in the peptide antibiotic telomycin. Residues of D-allothreonine have been found in the glycolipid and peptidolipid of actinomycetes, and in mycobacteria.



L-allothreonine



D-allothreonine

allotopic **1** of, relating to, or having the property of **allotopy**. **2** *(in genetics)* describing a mutation that imparts to one tissue a particular metabolic characteristic normally found in another tissue.

allotopy the phenomenon of the formation of a membrane– enzyme complex resulting in alteration of the properties of both enzyme and membrane. For example, a change in enzymatic activity is sometimes observed when a soluble enzyme is adsorbed on an interface.

allotrope any of the different physical forms in which a chemical element can exist; e.g. diamond, graphite, and fullerenes are allotropes of carbon.

allotropy *or* **allotrophy** *or* **allotropism** the phenomenon of a substance, especially an element, existing in more than one physical form (**allotrope**), usually in the same phase; e.g. the different crystalline forms of carbon or phosphorus, or the different molecular forms of dioxygen and ozone. *Compare* **polymorphism** (def. 2). **—allotropic** *adj.*

allotype an antigenically distinct variant of a protein or other antigen arising from intraspecies genetic differences. Each individual has a particular variant at each immunoglobulin gene locus, which will often differ from those in other individuals of the same species.

allotypic specificity an antigenic specificity that is not the same in a given protein in all normal individuals of a species.

allotypy the property, possessed by certain proteins and other antigens, of existing in antigenically distinct forms or **allotypes**. Thus allotypes of the same protein, although not distinguished by usual physicochemical and chemical criteria, can elicit specific antibodies in some other members of the same species. They are those **idiotypes** that behave as **xenotypes** in other individuals of the same species.

alloxan mesoxalylurea; 2,4,5,6-(1H,3H)-pyrimidinetetrone; a compound used experimentally to induce diabetes through its action in selectively destroying pancreatic B-cells.



allozyme *or* **alloenzyme** any enzyme variant produced by a particular **allele**.

all-α protein *an alternative term for* **all-alpha protein**.

all-β protein *an alternative term for* **all-beta protein**.

allulose *trivial name (not recommended) for* **psicose**.

allurin a cysteine-rich secretory protein (CRISP) and sperm attractant from the egg jelly of *Xenopus* eggs.

allysine 6-oxonorleucine; 2-aminoadipaldehydic acid; an α-amino acid not normally found in proteins, but enzymically formed from lysine *in situ* as an intermediate in the creation of covalent crosslinks between adjacent polypeptide strands during the maturation of certain connective-tissue proteins (e.g., collagen, elastin). The enzyme **lysyl oxidase** oxidizes the terminal amino-methylene groups of residues of either lysine or 5-hydroxylysine to aldehyde groups, forming residues of allysine or **hydroxyallysine** respectively. *See also* **desmosine**, **isodesmosine**, **lathyrism**, **noncoded amino acid**, **syndesine**.



L-allysine



D-allysine

almond emulsin *see* **1,3-*α*-L-fucosidase**.

alopecia human hair loss, of which the most common is male pattern baldness (**androgenetic alopecia**). A rare complete loss of scalp and body hair (**alopecia universalis**) is associated with a recessive missense mutation in the hairless gene at 8p12. This encodes a putative single zinc finger transcription factor (of 1189 amino acids) that is expressed only in brain and skin, and shows 80% sequence identity with the equivalent mouse gene.

ALP *(in clinical biochemistry) abbr. for* alkaline phosphatase.

alpha *symbol*: α (lower case) *or* A (upper case); the first letter of the Greek alphabet. For uses *see* **Appendix A**.

α+β protein *or* **alpha+beta protein** member of a class of proteins that comprises both α- and β-secondary structures, in which the helical and strand components are segregated, the strand components mainly forming anti-parallel β-sheets: e.g., members of the lysozyme family have discrete α- and β-components, with a common α+β domain in the active site region; microbial ribonucleases have a single helix packed against an anti-parallel β-sheet.

α/β protein *or* **alpha/beta protein** member of a class of proteins that comprises both α- and β-secondary structures that alternate in closely-coupled α–β units, the strand components forming mainly parallel β-sheets or β-barrels: e.g., **TIM** barrels have a closed 8-stranded parallel β-sheet barrel topology; NAD(P)-binding **Rossmann folds** have a 3-layered α–β–α topology, with a core 6-stranded parallel β-sheet.

alpha carbon atom *or* **C-alpha** (*symbol*: Cα) the central tetrahedral carbon atom of an amino acid, to which is attached a hydrogen atom, an amino group, a carboxyl group and a side chain. *Compare* **beta carbon atom**.

alpha cell *an alternative term for* **A cell**.

alpha-1 cell *an alternative term for* **D cell**.

alpha chain *or* **α chain 1** the **heavy chain** of IgA **immunoglobulin** molecules. **2** one of the two types of polypeptide chain present in normal adult hemoglobin (Hb A) molecules.

alpha complementation a phenomenon in which the N-terminal sequence 1–56 of *β*-galactosidase from *Escherichia coli*, the α-peptide, is able to restore enzyme activity to a mutant form of the enzyme such as lacZΔM15 that has the sequence deleted.

alpha effect the enhancement of nucleophilicity that occurs when the atom adjacent to a nucleophilic site bears a lone pair of electrons. It has been invoked to explain the high toxicity of, e.g., hydroxylamine and the cyanide ion.

alpha-fetoprotein *see* **α-fetoprotein**.

alpha globulin *or* **α-globulin** any of a group of **plasma proteins** that migrate most anodically among the globulins in electrophoresis at pH values slightly above 7.

alpha-helical channels a subclass of transport proteins of the TC system, designated 1.A. It contains nearly 40 families, including voltage-gated ion channels, ATP-gated cation channels, **aquaporins**, **ligand-gated ion channels**, **connexins**, and **heat-shock proteins 70**. They are found in all domains of organisms.

alpha helix *or* **α-helix** a helical, or spiral, conformation of a polypeptide chain in which successive turns of the helix are held together by hydrogen bonds between the amide (peptide) links, the carbonyl group of any given residue being hydrogen- bonded to the imino group of the third residue behind it in the chain. This is the case for all of the carbonyl and amide groups of the peptide bonds of the main chain. The α-helix has 3.6 residues per turn, and the **translation** (def. 2), or pitch, along the helical axis is 1.5 Å per residue, 5.4 Å per turn. The helix may be left- or right-handed, the latter being much more common. It is one of the two basic elements of the **secondary structure** adopted by polypeptide chains (the other being **beta strand**). The α-helix was first described by Pauling and Corey in 1951, based on model building. *See also* **gamma helix**.

alpha-hemolysin a bacterial peptide creating pores in eukaryotic cell membranes; its structure is $(2)_2$ β-strands. It is classified in the TC system under number 1.C.3.

alpha hemolysis *or* **α-hemolysis** a type of hemolysis, characterizing certain strains of streptococci, in which a greenish tinge occurs around the bacterial colonies in a blood-agar plate. *Compare* **beta hemolysis**.

alpha MEM a modification of Minimal Essential Medium, used for the culture of a wide range of mammalian cells.

alphanumeric describing any coding system or data set that provides for letters, numbers, and other symbols such as punctuation. [From 'alphabetic' and 'numeric'.]

alpha oxidation *or* ***α*-oxidation 1** a series of reactions occurring in plant tissue by which a free fatty acid of chain length ranging from C_{18} to C_{13} is oxidatively degraded with the simultaneous release of a molecule of CO_2 from the carboxyl group and the formation of a free fatty acid containing one carbon atom fewer. NAD^+ is the only cofactor required. **2** In animals, the first reaction in the oxidation of phytanic acid in peroxisomes. It is catalysed by phytanoyl-CoA hydroxylase, deficiency of which produces Refsum disease (classical or adult).

alpha particle *or* **α particle** a fast-moving positively charged helium nucleus, $^4He^{2+}$, emitted in the decay of certain **radionuclides**.

alpha-peptide the N-terminal peptide (1–58 or longer) of *E. coli β*-galactosidase. *See* **galactosidase**.

alpha radiation radiation consisting of fast-moving alpha particles.

alpha ray a directed stream of alpha particles.

alpha receptor *see* **adrenoceptor**.

Alport syndrome a progressive hereditary disease of renal glomerular membranes, sometimes also involving hearing loss and ocular lesions. The more common X-linked form is associated with over 300 mutations (mostly small deletions or insertions, splicing or missense mutations) in the gene at Xq22.3 for the type IV collagen α-5 chain. The less common autosomal form is associated with several mutations in the gene at 2q35 for the type IV collagen α-4 chain. Each of these chains is normally ≈1650 residues long and is highly glycosylated. [After Arthur Cecil Alport (1880–1959), South African physician.]

ALS *abbr. for* **1** antilymphocyte serum. **2** *(in clinical biochemistry)* (fructose-bisphosphate) aldolase, EC 4.1.2.13. **3 amyotrophic lateral sclerosis**.

Alt *symbol for* altrose.

ALT *(in clinical biochemistry) abbr. for* alanine transaminase.

alternate pathway *see* **alternative pathway** (def. 2).

alternating axis of symmetry *see* **symmetry**.

alternating current *abbr*.: a.c. *or* AC; an electric current that varies with time in a sinusoidal manner. The abbreviation a.c. may also be applied to a voltage of varying polarity.

alternatively spliced form *an alternative name for* **splice variant**.

alternative oxidase *or* **cyanide-resistant oxidase** an enzyme of plants, many algae and fungi, and some protozoa that is associated with the inner mitochondrial membrane and transfers electrons from ubiquinol to oxygen, bypassing cytochrome *c* oxidase of the electron transport chain without generating a proton gradient or ATP. It is encoded in the nucleus, is insensitive to CO, cyanide and azide (inhibitors of cytochrome *c* oxidase), and to antimycin A and myxothiazol (inhibitors of complex III) but is inhibited by salicylhydroxamic acid and *n*-pyrogallate. Each subunit (32 kDa) of the dimer contains a central hydrophobic region that is membrane-intrusive and flanked by hydrophilic regions, the C-terminal region containing a di-iron centre. It is active in the thermogenesis associated with flowering in the voodoo lily and the skunk cabbage.

alternative pathway 1 a misleading term sometimes applied to any of the metabolic pathways by which glucose is broken down in animals, especially the **pentose (phosphate) pathway**. **2** (*or* **alternate pathway**) a pathway by which **complement** components C3–C9 are activated without a requirement for C1, C2, or C4.

alternative splicing the occurrence of alternative patterns of **splicing** of a primary RNA transcript of DNA to produce different mRNAs. After excision of **introns**, selection may determine which **exons** are spliced together to form the mRNA. An example is the production of mRNA for 19S IgM, which is secreted, and 7S IgM, which is inserted into the lymphocyte membrane, both products being coded for by the same gene, but the mRNA for 7S IgM having fewer of the original exons. Up to 50% of structural gene products in humans may be alternatively spliced.

altro+ *prefix* denoting a particular configuration of a set of four (usually) contiguous >CHOH groups, as in D- or L-altrose. *See* **monosaccharide**.

altrose *symbol*: Alt; *altro*-hexose; an aldohexose that differs from glucose in the configuration of the hydroxyl groups on C-2 and C-3.

***Alu*I** a type 2 **restriction endonuclease**; recognition sequence: AG↑CT. The M.*Alu*I modification site is C3.

alum-precipitated toxoid any preparation in which a toxoid is adsorbed onto an adjuvant containing an aluminium compound, e.g. aluminium hydroxide gel or an alum. The term is applied especially to diphtheria toxoid.

alum precipitation a technique in which a soluble immunogen is converted into particulate form by mixing with a solution of an alum (e.g. aluminium potassium sulfate) and adjusting the pH to near 6.5. The antigen is adsorbed on the aluminium hydroxide precipitate so formed, which acts as an adjuvant in immunization.

Alu sequence *or* ***Alu*I sequence** *or* **Alu repeat** *or* ***Alu*I repeat** any of various base sequences dispersed in human, rat, and mouse (and perhaps other) genomes of ≈0.3 kbp and spaced at approximately 5 kbp. Each Alu sequence comprises two similar 130 bp sequences (**Alu left** and **Alu right**) separated by a short A-rich region. Alu sequences are the major **SINE** in the human genome, being present ≈10^6 times. They are responsible for Alu-mediated deletions in several genes in which they occur (e.g. that for C1 inhibitor). These sequences may be sites for attachment of cohesin complexes that bind newly replicated chromosomes before they segregate into daughter cells. The name derives from the presence in such sequences of sites for the restriction enzyme *Alu*I. *See* **hereditary angioedema**.

alveolus (*pl.* **alveoli**) any small pit, cavity, or saclike dilatation, such as an air cell of the lungs, an **acinus** of a compound gland, or a tooth socket. —**alveolar** *adj.*

Alzheimer's disease *or* **Alzheimer's dementia** *or* **Alzheimer sclerosis** a genetically and phenotypically heterogeneous syndrome of progressive cognitive failure. It is the most common cause of late-life dementia (senile dementia) in developed nations, but early onset before the age of 65 (presenile dementia) is common in familial cases. All cases develop numerous extracellular deposits of the **β-amyloid peptide** in the brain, and almost all have intraneuronal bundles of abnormal filaments composed of highly phosphorylated forms of the microtubule-associated **tau protein**. Numerous mutations associated with early-onset forms occur at various loci, including: 21q21, which encodes the β-amyloid peptide precursor (a single-pass transmembrane glycoprotein of which an isoform containing 695 amino acids is expressed predominantly in brain); 14q21.3, which encodes presenilin 1 (a membrane protein with 5–10 putative transmembrane segments); and 1q42.1, which encodes presenilin 2 (a protein of 448 amino acids that has 60% overall sequence identity with presenilin 1). Inheritance of the E4 allele of the gene for **apolipoprotein E** (locus at 19q13) is associated with a dose-dependent increased risk for late-onset Alzheimer's disease. [After Alois Alzheimer (1864–1915), German neurologist who in 1907 described the condition of a patient referred to as Auguste D.]

Am *symbol for* americium.

Amadori rearrangement an acid- or base-catalysed chemical rearrangement reaction in which an *N*-substituted aldosylamine is converted into the corresponding *N*-substituted 1-amino-1-deoxy-2-ketose. It occurs, e.g., in the **Maillard reaction**, in the reaction of carbohydrates with phenylhydrazine, in the formation of hemoglobin A1_c, and in a step in tryptophan biosynthesis – isomerization of *N*-(5′-phosphoribosyl)-anthranilic acid into 1-(*α*-carboxyphenylamino)-1′-deoxyribulose-5′-phosphate.

***Amanita* toxin** *see* **amatoxin**.

amanitin any of various **amatoxins**, especially α-, β-, γ-, and ε-amanitin. These occur, together with other **amatoxins**, in the highly poisonous agaric commonly called the death-cap fungus or deadly agaric (*Amanita phalloides*), and in some related species.



α-amanitin

α-amanitin

amantadine *trivial name for* 1-adamantanamine; 1-aminoadamantane; $C_{10}H_{17}N$; a polycyclic antiviral agent that is especially effective as a prophylactic against influenza A virus. It appears not to affect viral attachment to cells but to block penetration or uncoating. *See also* **adamantane**.



amatoxin any member of a family of closely related bicyclic octapeptides present in the highly poisonous agaric commonly called the death-cap fungus or deadly agaric (*Amanita phalloides*), and in some related species. α-**Amanitin** is the best known member and the chief toxic constituent of *A. phalloides*. The majority of amatoxins are highly toxic, though much slower in action than the congeneric and less potent phallotoxins. For example, the ingestion by an adult man of 10 mg α-amanitin (the quantity in a single fruit body of *A. phalloides*) leads over the course of several days to death in the absence of treatment. The common elements of the molecular structure of amatoxins include residues of *trans*-4-hydroxy-L-proline, (usually mono- or dihydroxy-)L-isoleucine, and the bisfunctional amino acid (usually 6′-hydroxy-)L,L-tryptathionine *S*-oxide (which forms a sulfoxide bridge across the molecule; *see* structure at **amanitin**), together with two residues of glycine. *α*-Amanitin binds very tightly ($K_{\text{diss}} = 10^{-8}$ M) to eukaryotic RNA polymerase II, thereby blocking the formation of mRNA precursors and hnRNA. It also binds, but rather less tightly ($K_{\text{diss}} = 10^{-6}$ M), to eukaryotic RNA polymerase III, thereby blocking the formation of tRNA and 5S RNA. It has little action on RNA polymerase I. Hence the synthesis of RNA and protein is markedly inhibited in eukaryotic cells but not in prokaryotic cells.

amber 1 a fossil resin. **2** *see* **amber mutant**.

amber codon *or* **amber triplet** *symbol*: UAG; one of the three terminator codons or **nonsense codons** in an mRNA molecule.

Amberlite *proprietary name for* various cation- and anion-exchange resins.

amber mutant *or* **amber** a T4 bacteriophage carrying an **amber mutation**. *See also* **ochre mutant**, **opal mutant**.

amber mutation a temperature-sensitive conditionally lethal mutation, capable of occurring in almost any gene of a bacterial virus, that causes the synthesis of a particular polypeptide chain to terminate prematurely. It is due to the alteration of one codon in the corresponding messenger RNA to an **amber codon**, i.e. a termination codon.

amber suppressor any of a number of mutations in *Escherichia coli* that suppress an **amber codon** in mRNA thereby allowing insertion of one of several alternative amino acids into a polypeptide at that site. The best known are *supD* (Ser), *supE* (Gln), and *supF* (Tyr). The mutations result in changed anticodons of the tRNA molecules, consequent on single base substitutions in their DNA coding sequences.

ambi+ *or* **ambo+** *comb. form* denoting on both sides, both. *Compare* **amphi+**. [From Latin *ambo*, both.]

ambidentate describing ligands, especially metal ions, that can bond through either of two or more donor atoms; for example $(NCS)^-$.

ambient of or relating to the immediate environment.

ambiquitous describing an enzyme that has reversibly convertible soluble and membrane-bound forms. —**ambiquity** *n.*

ambo+ *a variant form of* **ambi+**.

ambo- *prefix* designating chiral compounds in which both of the possible molecular configurations are present at an indicated chiral centre or residue but not necessarily in equimolar proportions. Such situations may arise especially with chiral compounds obtained by partial chemical synthesis from chiral precursors in asymmetric reactions. Examples: the amino-acid sequence Phe-*ambo*-Ala-Leu, representing a mixture of Phe-Ala-Leu and Phe-D-Ala-Leu; and the trivial name 4′-*ambo*-8′-*ambo*-α-tocopherol, representing a synthetic α-tocopherol in which C-2 has the natural, (*R*)-, configuration and C-4′ and C-8′ have both (*R*)- and (*S*)-configurations though not necessarily in equimolar proportions. *Compare* **DL-**, ***RAC-***.

amboceptor *(formerly) an alternative term for* hemolytic antibody. [Named by German biochemist Paul Ehrlich (1854–1915), who pictured hemolysin as an antibody having specific receptors both for erythrocytes and for complement, thereby serving to link the two together.]

AMCA *abbr. for* 7-amino-4-methylcoumarin-3-acetic acid; a **fluorophor** (def. 2) that can be coupled to proteins or other molecules through the carboxylic acid group while retaining its fluorescence property of emitting light in the blue region of the spectrum.



ameba *an alternative US spelling of* **amoeba**.

amelogenin the predominant protein in dental enamel during early development.

amicyanin a bacterial **electron transfer protein** containing a **type 1 copper** site.

amidorphin an opioid peptide corresponding to residues 104–129 of bovine proenkephalin A, but which is amidated at its C terminus.

Ames test *see* ***Salmonella* mutagenesis test**.

amethopterin *another name for* **methotrexate**.

amidase **1.** any enzyme that catalyses the hydrolysis of an ester. **2.** EC 3.5.1.4; acylamide amidohydrolase; an enzyme that catalyses the hydrolysis of a monocarboxylic acid amide to monocarboxylate and NH_3.

ω-amidase EC 3.5.1.3; ω-aminodicarboxylate amidohydrolase; an enzyme that catalyses the hydrolysis of an ω-amidodicarboxylic acid to dicarboxylate and NH_3.

amidate to convert any oxy acid into its corresponding amide. —**amidated** *adj.*; **amidation** *n.*

amide any compound containing one, two, or three acyl groups attached to a nitrogen atom. An amide may be derived formally or actually by condensation of an oxy acid with ammonia or a primary or secondary amine. Amides derived from carbon acids may be termed **carboxamides**, those from sulfonic acids **sulfonamides**, etc. Examples include: acetamide, methanamide, $CH_3–CO–NH_2$; sulfanilamide, 4-aminobenzenesulfonamide, $H_2N–C_6H_4–SO_2–NH_2$; and diethylformamide, formdiethylamide, $H–CO–N(C_2H_5)_2$. The term includes **imide** and **peptide**.

amidination the process or reaction of introducing an amidino group into a chemical entity.

amidine any compound of the type $R–C(=NH)–NH_2$.

amidino the monovalent group $–C(=NH)–NH_2$.

amidino+ *comb. form* denoting the presence of an **amidino** group.

***N*-amidinoglycine** *see* **glycocyamine**.

amido+ *comb. form* denoting the presence of an amide group.

Amido Black *see* **Naphthalene Black**.

amidolysis any cleavage of an amide (including a peptide) to the parent oxy acid and ammonia or an amine.

amidophosphoribosyltransferase EC 2.4.2.14; *systematic name*: 5-phosphoribosylamine:pyrophosphate phospho-α-D-ribosyltransferase (glutamate-amidating); *other names*: glutamine phosphoribosylpyrophosphate amidotransferase; phosphoribosyldiphosphate 5-amidotransferase. An enzyme that catalyses the formation of 5-phospho-β-D-ribosylamine from L-glutamine, 5-phospho-α-D-ribose 1-diphosphate, and H_2O with release of L-glutamate and pyrophosphate. This is an early reaction in purine biosynthesis.

amidorphin an opioid peptide corresponding to residues 104–129 of bovine **proenkephalin** A, but which is amidated at its C terminus.

amidotransferase *see* **amidophosphoribosyltransferase**, **glutamine amidotransferase**.

amiloride *N*-amidino-3,5-diamino-6-chloropyrazinecarboxamide; a potent and specific inhibitor of Na^+ entry into cells. It inhibits Na^+,K^+-ATPase at low concentrations. It is used as a potassium-sparing diuretic.



amiloride-binding protein *see* **amine oxidase (copper-containing)**.

amine any organic compound that is weakly basic in character and contains an **amino** or a substituted amino group. Amines are called primary, secondary, or tertiary according to whether one, two, or three carbon atoms are attached to the nitrogen atom. *See also* **quaternary ammonium compound**.

amine oxidase (copper-containing) EC 1.4.3.6; *other names*: diamine oxidase; diamino oxhydrase; histaminase; an enzyme that catalyses the oxidation by dioxygen of an amino group to an aldehyde, with release of ammonium and hydrogen peroxide. 6-Hydroxydopa and copper are cofactors. Example, human amiloride-sensitive amine oxidase (copper-containing) precursor (amiloride-binding protein; *abbr.*: ABP), an 85.27 kDa enzyme that binds **amiloride**.

amine oxidase (flavin-containing) *see* **monoamine oxidase**.

aminergic describing a receptor that is activated by a specific (biogenic) amine. The term is usually applied to nerves that act by releasing a monoamine (norepinephrine, dopamine, or 5-hydroxytryptamine) from their nerve endings. *Compare* **adrenergic**, **cholinergic**, **dopaminergic**, **peptidergic**, **purinergic**, **serotonergic**.

amino the chemical group $–NH_2$ in an organic molecule. It is basic in character and formally derived by the removal of a hydrogen atom from ammonia.

amino+ *comb. form* denoting the presence of an amino group.

amino acid any organic acid containing one or more amino substituents. The term is usually restricted to amino, especially α-amino, derivatives of aliphatic carboxylic acids, but it can also include β-amino derivatives.

amino-acid accepting RNA *see* **transfer RNA**.

amino-acid *N*-acetyltransferase EC 2.3.1.1; *other name*: *N*-acetylglutamate synthase (*abbr.*: AGS); an enzyme that catalyses the formation of *N*-acetyl-L-glutamate (*abbr.*: AGA) from acetyl-CoA and L-glutamate with the release of CoA. It is responsible for the formation of AGA, an obligate activator of **carbamoyl-phosphate synthase** (def. 1), the first step in the **ornithine–urea cycle**. The mammalian enzyme is present in mitochondrial matrix in liver, intestine, kidney, and spleen.

amino-acid analyser any instrument or apparatus for the automated analysis of mixtures of amino acids. The amino acids are separated individually and quantified spectrophotometrically.

amino-acid arm the base-paired segment of **transfer RNA** containing both the 3′ and the 5′ ends of the RNA molecule, on which the specific amino acid is attached to the 3′-hydroxyl at the 3′ end.

amino acid exchange matrix *an alternative name for* **substitution matrix**.

amino acid index a numerical scale that quantifies particular amino acid properties (e.g. size, polarity, weight, hydrophobicity). For example, the **aliphatic index** gives a measure of the relative volume of a protein occupied by aliphatic side chains. Amino acid indices are often used to predict the properties of the proteins in which they occur.

amino-acid oxidase any enzyme that catalyses the oxidation by dioxygen of the amino group of an *α*-amino acid to an oxo acid with release of ammonium and hydrogen peroxide. L-Amino-acid oxidase, EC 1.4.3.2, is specific for L enantiomers, and D-amino-acid oxidase, EC 1.4.3.3, is specific for D enantiomers. Both enzymes have FAD as coenzyme.

amino-acid residue that part of any amino-acid molecule that is present when the amino acid is combined in a (poly)peptide, i.e. the amino acid less the atoms (a hydrogen atom and/or a hydroxyl group) that have been removed during the formation of a peptide bond or bonds.

amino-acid sequence *or* **primary structure** the sequential order of amino-acid residues in a polypeptide or protein. It is usually given from the end carrying an *α*-amino group not in peptide linkage, i.e. from the N-terminal end.

***α*amino-acid site** *a less correct term for* **aminoacyl site**.

amino acid transporter *abbr*.: AAT; any of numerous membrane proteins involved in amino acid transport into cells or into membranous organelles such as mitochondria, chloroplasts, and vesicles. The human genome contains 46 genes for AATs, that of *Arabidopsis* has 53, and that of yeast 24. AATs fall into five superfamilies: amino acid-polyamine-choline (in bacteria, yeasts, plants, and animals); sodium-dicarboxylate symporter (only in animals); neurotransmitter (only in animals), amino acid transfer; and AATs within the major facilitator superfamily. These proteins are presumed to contain 10, 12, or 14 transmembrane segments. Mitochondrial AATs are presumed to contain six transmembrane segments.

amino acid–tRNA ligase *other name*: aminoacyl-tRNA synthetase. Any of the sub-subclass EC 6.1.1 of enzymes that catalyse the formation of aminoacyl-tRNA from ATP, amino acid, and tRNA with release of pyrophosphate and AMP. Each amino acid has its cognate amino acid–tRNA ligase and tRNA acceptor species; e.g. in the case of glutamate–tRNA ligase (EC 6.1.1.17), the tRNA is tRNA$^{\text{Glu}}$ and the product is Glu-tRNA$^{\text{Glu}}$. Many contain zinc or putative zinc-binding motifs. Aminoacyl adenylate is normally an intermediate and the initial aminoacyl-tRNA product usually involves 2′-substitution with subsequent rearrangement. Specificity is not perfect but the enzymes have one or more mechanisms for correcting mischarged aminoacyl-tRNAs, which occur with structurally similar amino acids (e.g. Ile-tRNA$^{\text{Val}}$). Structurally the enzymes of *E. coli* belong to two classes. Class I are mostly monomeric, aminoacylate the tRNA on the 2′ –OH of the terminal ribose of the acceptor stem, require anticodon recognition for catalysis, and share two homologous sequences that are components of a nucleotide-binding fold. Class II are mostly dimeric or tetrameric, aminoacylate the 3′ –OH of the terminal ribose, do not require recognition of the anticodon for catalysis, and lack the homologous sequences of class I but share three sequences in the core of their catalytic domains.

amino aciduria a condition in which, on a normal dietary intake, amino acids appear in the urine. It may be restricted to one or a few amino acids, or be more generalized, and result from increased amounts in plasma (usually as a feature of an inherited disease of amino-acid metabolism) or from acquired damage or a hereditary reabsorption defect in the proximal renal tubules. *See* **Hartnup disease**, **maple syrup urine disease**.

aminoacyl the acyl group, R–CH(NH_2)–CO–, formed by removal of the hydroxyl group from the *α*-carboxyl group of an (unknown or unspecified) *α*-amino acid.

aminoacylase **1** EC 3.5.1.14; an *N*-acyl amino-acid aminohydrolase; an enzyme that catalyses any reaction of the general type:

$$N\text{-acyl-L-amino acid (except } N\text{-acetylaspartate)} + H_2O \rightarrow \text{fatty acid (anion)} + \text{amino acid.}$$

2 EC 3.5.1.15; *recommended name*: aspartoacylase; an enzyme that hydrolyses *N*-acetylaspartate to acetate and aspartate. Mutations in a locus at 17p13-pter, which decrease the enzyme's catalytic activity, are associated with Canavan disease.

aminoacyl site *or* **A site** *or (correctly)* **aminoacyl-tRNA site** the site on a **ribosome** to which the incoming aminoacyl-tRNA is bound during protein synthesis. In bacteria this involves **ribosomal proteins** L1, L5, L7/L12, L20, L30, L33, both 16S and 23S rRNA (L7 and L12 differ in acetylation only).

aminoacyltransferase any enzyme of sub-subclass EC 2.3.2 that transfers aminoacyl groups, forming either an ester or an amide.

aminoacyl-tRNA the form in which amino acids are transported to the ribosomes during protein synthesis. The amino acid is esterified through its carboxyl group to the 3′-hydroxyl group of the 3′-terminal adenosine of a molecule of **transfer RNA**.

aminoacyl-tRNA synthetase *an alternative name for* **amino acid–tRNA ligase**.

***α*-aminoadipate** 2-aminohexanedioate; an intermediate in the synthesis of lysine (*see* **aminoadipic pathway**). It is a competitive inhibitor of **glutamate receptors**.

aminoadipic pathway a metabolic pathway for the biosynthesis of lysine that occurs in some algae, *Euglena*, and fungi. It involves a two-carbon extension of 2-oxoglutarate to 2-oxoadipate (acetyl-CoA addition to form homocitrate, thence *cis*-homoaconitate, homoisocitrate, and oxidation to 2-oxoadipate), transamination to 2-aminoadipate, reaction of the latter with ATP to yield 5-adenylyl-2-aminoadipate, and further reductive reactions to 2-aminoadipic-5-semialdehyde, saccharopine, and finally L-lysine. Aminoadipate is also involved in lysine catabolism in mammals.

***α*-aminoadipic semialdehyde synthase** a homotetrameric enzyme that takes part in the degradation of lysine. It catalyses the reactions:

(1) L-lysine + 2-ketoglutarate + NADPH = saccharopine + NADP$^+$;

(2) saccharopine = NAD$^+$ + H_2O = *α*-aminoadipic semialdehyde + glutamate + NADH.

In mammals it is bifunctional (human, 927 amino acids), but in bacteria and fungi it is represented by the separate enzymes lysine-ketoglutarate reductase (reaction 1) and saccharopine dehydrogenase (reaction 2). Deficiency of both activities leads to familial hyperlysinemia.

amino alcohol any aliphatic organic molecule or moiety containing both an amino and a hydroxyl substituent.

***p*-aminobenzoic acid** *abbr*.: PABA; 4-aminobenzoic acid; a compound present in yeast as a factor in the B complex of vitamins, and a structural component of folic acid and related compounds. It is a substrate for the bacterial enzyme dihydropteroate synthase, EC 2.5.1.15, competitive inhibitors of which (e.g. **sulfonamides**) are effective antibacterial agents. It is used in sunscreen preparations. *De novo* synthesis is through the intermediate chorismate formed by the **shikimate pathway**. It is formed in a test of pancreatic function, the **PABA test**.

***γ*-aminobutyrate receptor** *see* **GABA receptor**.

***γ*-aminobutyrate shunt** *or* **GABA shunt** a variation of the **tricarboxylic-acid cycle** in which *α*-oxoglutarate is converted to L-glutamate either by transamination or by reductive amination. The glutamate is decarboxylated to form *γ*-aminobutyrate, which can re-enter the tricarboxylic acid cycle after being deaminated and oxidized to succinate. This pathway occurs in brain tissue, presumably to form and catabolize *γ*-aminobutyric acid, and is also prominent in green plants.

4-aminobutyrate transaminase *abbr*.: GABA-T; EC 2.6.1.19; *other names*: *γ*-amino-*N*-butyrate transaminase; GABA transaminase; *β*-alanine–oxoglutarate aminotransferase; an aminotransferase enzyme important in the catabolism of *γ-amino-n*-butyric acid (*abbr*.: GABA). It catalyses the reaction:

$$\text{4-aminobutanoate (GABA)} + \text{2-oxoglutarate} = \text{succinate semialdehyde} + \text{L-glutamate.}$$

Pyridoxal phosphate is the coenzyme. The human enzyme is a homodimer present in the mitochondrial matrix. Deficiency of the enzyme results from a rare missense mutation and is accompanied by seizures and psychomotor retardation and elevated levels of GABA, *β*-alanine, and homocarnosine in plasma and cerebrospinal fluid.

α-amino-*n*-butyric acid 2-aminobutanoic acid; a component of **ophthalmic acid**.

γ-amino-*n*-butyric acid *abbr*.: GABA; 4-aminobutanoic acid, $H_2N–CH_2–CH_2–CH_2–COOH$; an amino acid not found in proteins, but occurring principally in the central nervous system, where it is an important inhibitory **neurotransmitter**. It is also found in some plants. *See also* **GABA receptor**.

ε-aminocaproic acid *symbol*: εAcp; *(formerly) an alternative name for* **6-aminohexanoic acid**.

7-aminocephalosporanic acid a compound obtained by the acid hydrolysis of **cephalosporin** C and used in the manufacture of semi-synthetic cephalosporins.

4-amino-4′-chlorodiphenyl *abbr*.: pCPA; an irreversible inhibitor of **tryptophan 5-hydroxylase,** an enzyme in the pathway for synthesis of 5-hydroxytryptamine.



1-aminocyclopropane-1-carboxylic acid *abbr*.: ACC; a cyclic *α*-amino acid that is the immediate precursor of the plant hormone ethylene. ACC is produced by ACC synthase in the reaction:

$$S\text{-adenosylmethionine} = \text{ACC} + 5'\text{-methylthioadenosine}.$$

ACC produces ethylene in the reaction catalysed by ACC oxidase:

$$\text{ACC} + {}^1/_2O_2 = \text{ethylene} + CO_2 + HCN + H_2O.$$

ACC is also a potent and selective ligand for the glycine modulatory site of the NMDA receptor (*see* **glutamate receptor**).



aminodeoxysugar *or* **amino sugar** *or* **amino-saccharide** *or* **aminomonosaccharide** any monosaccharide or monosaccharide derivative in which an alcoholic hydroxyl group has been replaced by an amino group.

aminoethoxyvinylglycine *abbr*.: AVG; an inhibitor of ethylene formation in higher plants. It is produced by *Streptomyces* spp. It acts at the level of 1-aminocyclopropane-1-carboxylate synthase (*see* **1-aminocyclopropane-1-carboxylic acid**).

aminoethyl *symbol*: Aet; the $–CH_2–CH_2–NH_2$ group.

aminoethylbenzenesulfonyl fluoride *abbr*.: AEBSF; an inhibitor of serine endopeptidases. It is both soluble and stable in aqueous solutions, and is less toxic (LD_{50} 2.8 g kg^{-1}) than **phenylmethylsulfonyl fluoride**, but with the same action and similar potency. *Compare* **organophosphate**.



***N*-(2-aminoethyl)isoquinoline-5-sulfonamide** *or* **H9** a selective inhibitor of casein kinase I, protein kinase A, and, less potently, protein kinase C.



aminoglycoside antibiotic any member of a group of broad-spectrum antibiotics, of similar toxicity and pharmacology, that contain an aminodeoxysugar, an amino- or guanidino-substituted inositol ring, and one or more residues of other sugars. The group includes **streptomycin**, **neomycin**, framycetin, **kanamycin**, paromomycin, and **gentamicin**. An isolated form of deafness is induced by aminoglycosides in persons who carry one of two point mutations in the mtDNA for 12S rRNA.

aminoglycoside phosphotransferase a bacterial enzyme whose gene is carried on the transposon sequence Tn5. Expression of the enzyme in eukaryotic cells confers resistance to the **aminoglycoside antibiotics**. It is used as a **dominant selectable marker** in cells transfected with plasmids, where the presence of the gene is indicated by *neo* or *neo*^{R} (denoting resistance to neomycin).

6-aminohexanoic acid *symbol*: εAhx; a compound that acts as an inhibitor of **streptokinase** and **urokinase** and prevents the synthesis of **plasmin**.

***para*-aminohippuric acid** *abbr*.: PAH; *N*-(4-aminobenzoyl)-glycine; it is used in renal clearance tests. Its clearance exceeds that of inulin, indicating that it is actively secreted by renal tubular cells. It shares this transport system with penicillin and competitively inhibits penicillin secretion. PAH clearance is taken as a measure of effective renal plasma flow and the inulin:PAH clearance ratio as the filtration fraction, normally about 18%.



α-amino 3-hydroxy-5-methylisoazolepropionic acid receptor *see* **AMPA repector**.

aminoimidazole carboxamide ribonucleotide *see* **AICAR**.

aminoimidazole ribonucleotide *see* **AIR**.

amino–imino tautomerism a form of **tautomerism** in which the amino and the imino forms of a compound are in equilibrium, the change corresponding to the migration of a hydrogen atom. *Compare* **keto–enol tautomerism**.

α-aminoisobutyric acid *α*-methylalanine, 2-amino-2-methyl-propanoic acid, $(CH_3)_2C(NH_2)COOH$; a non-metabolizable amino-acid analogue used in metabolic and other studies.

β-aminoisobutyric acid *or* **3-amino-2-methylpropanoic acid** a non-protein amino acid, the (*R*)-isomer of which is an intermediate in the degradation of thymine, and the (*S*)-isomer in the degradation of L-valine – both to the glycogenic succinyl-CoA. The (*R*)-isomer is formed in liver, and further utilization requires *β*-aminoisobutyrate–pyruvate aminotransferase (EC 2.6.1.40). When activity of this enzyme falls to below 10% of normal, the result is hyperbeta-aminoisobutyricaciduria, a benign condition that is inherited as an autosomal recessive trait. This polymorphism is found in about 10% of Caucasians and in 40–95% of Orientals.

δ-aminolevulinate *or (esp. Brit.)* **δ-aminolaevulinate** *abbr*.: ALA, δALA, *or* DALA; 5-amino-4-oxopentanoate; $H_2N–CH_2–CO–[CH_2]_2–COO^–$; a compound formed in animals and bacteria from glycine and succinyl-CoA (*see* **5-aminolevulinate synthase**); in plant chloroplasts it is formed from glutamate (*see* **glutamate-1-semialdehyde 2,1-aminomutase**). It is an intermediate in **tetrapyrrole** biosynthesis.

5-aminolevulinate synthase EC 2.3.1.37; *systematic name*: succinyl-CoA:glycine *C*-succinyltransferase (decarboxylating); *other names*: *δ*-aminolevulinate synthase; δALA synthetase. The first and regulatory enzyme in the porphyrin biosynthetic pathway. It catalyses a reaction in mitochondria between succinyl-CoA and glycine to form 5-aminolevulinate, CoA, and CO_2. There are two isozymes: housekeeping or ALAS1 (locus at 3p21.1, which encodes 640 amino acids, and is induced by certain drugs and repressed by hemin); and erythroid or ALAS2 (locus at Xp11.21, which encodes 587 amino acids, and is neither induced nor repressed). Both contain bound pyridoxal phosphate. Deficiency of ALAS2 is associated with over 20 inactivating mutations in congenital sideroblastic anemia.

***δ*-aminolevulinic acid dehydratase** *an alternative name for* **porphobilinogen synthase**.

aminolysis **1** any chemical reaction in which an amine reacts analogously to ammonia in **ammonolysis**. **2** any hydrolytic deamination reaction in which an amino group is replaced by a hydroxyl group.

2-amino-4-methylhex-4-enoic acid a non-protein amino acid found in plants, e.g. *Aesculus californica* (California buckeye).

amino-monosaccharide *an alternative name for* **aminodeoxysugar**.

6-aminopenicillanic acid *abbr*.: 6-APA; a compound formally derived by the removal of the acyl side chain from **penicillin**. It is obtained industrially from fermentations in the absence of side-chain precursors but more usually by removal of the side chain using an amidase from *Escherichia coli* as an immobilized support. It is a very important intermediate for the manufacture of semisynthetic penicillins.

aminopeptidase any enzyme of sub-subclass EC 3.4.11, *α*-aminoacylpeptide hydrolases, that hydrolyse N-terminal amino-acid residues from oligopeptides or polypeptides.

4-aminophthalhydrazide *see* **luminol**.

aminopterin 4-aminofolic acid; a potent inhibitor of dihydrofolate reductase ($K_i < 10^{–9}$ M). It is used as an antineoplastic agent in the treatment of acute leukemia and choriocarcinoma. Aminopterin blocks nucleotide biosynthesis and thus also DNA biosynthesis, and has a similar action to **amethopterin**. It is a component of **HAT**, a selective medium used in tissue culture.



amino-saccharide *an alternative name for* **aminodeoxysugar**.

amino-terminal determination the analysis of a peptide or a protein to determine the nature of the amino-acid residue at the N terminus. The free terminal *α*-amino group is substituted with a reagent such as 2,4-dinitrofluorobenzene (Sanger's reagent), dansyl chloride, or phenylisothiocyanate (Edman's reagent). The substituted terminal residue is then removed by hydrolysis and identified by, e.g., chromatography.

amino terminus *or* **amino terminal** *an alternative name for* **N terminus**. *Compare* **carboxyl terminus**.

aminotransferase *or* **transaminase** any enzyme, of the large sub-subclass EC 2.6.1, that catalyses the reversible transfer of a nitrogenous group, usually an amino group, to an acceptor, generally a 2-oxo acid. Pyridoxal phosphate is a coenzyme, the intermediate pyridoxamine phosphate being formed in the reaction. *See also* **transamination**.

amitosis division of a cell nucleus by a process other than **mitosis**.

AML1 *symbol for* acute myeloid leukemia 1 gene; *also called* Runt-related transcription factor 1 (*RUNX1*); a gene, at 21q22.3, that encodes the α subunit of transcription factor PEBP2. The protein contains a DNA-binding domain that shows 70% homology with that of Runt and Lozenge (both of *Drosophila*). Chromosomal translocations t(8;21) that involve the *AML*1 gene result in oncogenic hybrid fusion proteins that are frequent in acute myeloid leukemia of children and young adults.

ammonification of nitrate *see* **nitrate reduction**.

ammonium **1** the NH_4^+ ion, formed by hydronation of a molecule of ammonia. It is formed from N_2 by root-nodule bac teria (*Rhizobium* spp.) in leguminous plants, and is an excretory product in **ammonotelic** animals. In higher animals it is toxic in elevated concentrations, and for excretion is converted to uric acid in **uricotelic** animals, and to urea in **ureotelic** animals. **2** the chemical group $–NH_3^+$.

ammonium sulfate $(NH_4)_2SO_4$; a salt much used in the purification of proteins, which vary in their solubility in ammonium sulfate solutions. An early step in the purification of a protein is thus often an ammonium sulfate precipitation.

ammonolysis any chemical reaction in which a covalent bond is cleaved by the action of ammonia, one or more of the hydrogen atoms of the ammonia being replaced by other atoms or groups; e.g.

$$2NH_3 + CH_3CO–O–COCH_3 \rightarrow$$
$$CH_3CONH_2 + CH_3COO^–NH_4^+.$$

ammonotelic describing animal groups (e.g. crustaceans, marine mussels, octopods) in which ammonium is the principal end-product of the degradation of nitrogen-containing compounds.

amniocentesis the process of withdrawing a sample of amniotic fluid from the **amnion** by means of a hollow needle. It is particularly useful in the diagnosis of the status of a fetus with respect to proteins or DNA but, in the human, sampling can only be carried out during the second trimester of pregnancy.

amnion a membranous sac, filled with amniotic fluid, that surrounds and protects the embryo in higher animals. It is developed in reptiles, birds, and mammals but not in amphibians or fish.

amoeba *or (US)* **ameba** (*pl.* **amoebae** *or* **amebae**) any of a genus (*Amoeba*) of naked rhizopod protozoans in the order Amoebida, characterized by a thin pellicle and frequent alterations in shape due to the constant formation and retraction of pseudopodia. —**amoebic** *or (US)* **amebic** *adj.*

amoebapore any of a family of pore-forming peptidic toxins with about 100 amino acid residues, permitting passage of small solutes, including water. The amoebapores are produced by *Entamoeba histolytica*. They are classified in the TC system under number 1.A.35.

amoeboid *or* (*US*) **ameboid** **1** of, pertaining to, or reminiscent of an amoeba or amoebae. **2** describing cells, etc. that move by forming pseudopodia.

amorph a mutant allele that is inactive and fails to produce a measurable effect. It may act as a genetic block to normal biosynthesis.

amorphous **1** lacking definite shape or form. **2** noncrystalline; devoid of real or apparent crystalline form.

amount concentration *see* **concentration**.

amount of substance *or* **chemical amount** *symbol*: *n*; a fundamental physical quantity – one of the seven SI base physical quantities – proportional to the number of specified elementary entities of a substance (i.e. atoms, molecules, ions, radicals, electrons, etc., or any specified group(s) of such particles). The SI base unit of the amount of substance is the **mole**. The proportionality factor is the same for all substances, and is the reciprocal of the **Avogadro constant**, N_A. It is given by: $n_B = N_B/N_A$, where n_B and N_B are the amount of substance B and the number of entities of substance B, respectively. The terms 'amount of substance' and 'chemical amount' may often usefully be abbreviated to 'amount'.

amount-of-substance concentration *see* **concentration**.

amp *abbr. for* ampere.

AMP *abbr. for* adenosine monophosphate; i.e. adenosine phosphate.

2′AMP *abbr. for* adenosine 2′-monophosphate; i.e. adenosine 2′-phosphate.

3′AMP *abbr. for* adenosine 3′-monophosphate; i.e. adenosine 3′-phosphate.

5′AMP *abbr. for* adenosine 5′-monophosphate; i.e. adenosine 5′-phosphate.

ampakine a drug that increases the efficiency of glutamate transmission at **α-amino-3-hydroxy-5-methylisoxazolepropionic acid receptors** (AMPA receptors) thereby allowing weaker stimuli to activate the receptors.

AMPA receptor *abbr. for* α-amino-3-hydroxy-5-methylisoxazolepropionic acid receptor; *former name*: quisqualate receptor. An excitatory amino acid receptor coupled directly to a transmembrane cation channel. It is expressed ubiquitously in neurons and glial cells and mediates the majority of fast excitatory synaptic transmission in the CNS. The receptor also has an excitatory glycine-binding site. It is a type of **glutamate receptor**.

AMP-CP *abbr. for* 5′-adenylyl methylenephosphonate; i.e. adenosine 5′-[α,β-methylene]diphosphate.

AMP-CPP *abbr. for* 5′-adenylyl methylenediphosphate; i.e. adenosine 5′-[α,β-methylene]triphosphate.

AMP deaminase *an alternative name for* **adenylate deaminase**.

ampere *symbol*: A; *abbr.*: amp; the SI base unit of electric current. It is defined as that constant current, which if maintained in two straight parallel conductors of infinite length, of negligible circular cross-section, and placed 1 metre apart in a vacuum, would produce between these conductors a force equal to 2×10^{-7} newton per metre of length. [After André Marie Ampère (1775–1836), French physicist.]

amperometric titration any titration in which the end point is detected by measuring the electric current flowing when a potential is applied between two electrodes in a solution.

AMPGD *abbr. for* 3-(4-methoxyspiro)-1,2-dioxetane-3,2′-tricyclo[3.3.1.1]decan-(4-yl)phenyl-β-D-galactopyranoside; a chemiluminescent substrate for β-galactosidase (*see* **chemiluminescence**). It is used to detect the activity of the β-galactosidase gene when the latter is employed as a reporter gene in transgenic plants, etc.



amphetamine (*R*,*S*)1-phenyl-2-aminopropane; (±)-α-methylphenethylamine; racemic desoxynorephedrine; a drug that has potent effects by stimulating the release of monoamines, inhibiting **monoamine oxidase**, and blocking neuronal reuptake of monoamines from the synapse. It is noted for its marked CNS stimulant actions. *See also* **dextroamphetamine**.



amphi+ *or (before a vowel)* **amph+** *prefix* **1** denoting on both sides of, of both kinds. **2** denoting around.

Amphibia a class of anamniote vertebrate animals in the superclass Tetrapoda. They are characterized by having gills during the larval stage; these are typically replaced by lungs in the adults. The skin is moist, glandular, and scaleless.

amphibian **1** a member of the class Amphibia. **2** adapted for life both on land and in water; amphibious.

amphibolic describing an enzyme or metabolic pathway that is concerned in both **anabolism** and **catabolism**. —**amphibolism** *n.*

amphile *an alternative name for* **amphiphile**.

amphion *or* **amphoion** any molecule that contains ionic groups of opposite charge, not necessarily in equal numbers; an ionized **ampholyte**. *Compare* **dipolar ion**. —**amphionic** *or* **amphoionic** *adj.*

amphipath *an alternative name for* **amphiphile**.

amphipathic *or* **amphiphilic** describing a molecule, such as a glycolipid or phospholipid, that contains both hydrophobic (i.e. lipophilic, nonpolar) and hydrophilic (i.e. aquaphilic, polar) parts; displaying **amphipathy**; being an **amphiphile**.

amphipathic helix an **alpha helix** with a specific topography consisting of opposite polar and non-polar forces, and a regular charge distribution. It is proposed as a basic structural element of the lipid-associating domains of apolipoproteins in very-low-density lipoproteins and high-density lipoproteins.

amphipathy *or* **amphiphilicity** the property (of a molecule, substance, etc.) of having affinity for both lipoidal and aqueous media; the extent or the degree to which a substance is amphipathic.

amphiphile *or* **amphile** *or* **amphipath** a substance whose molecules have an affinity for both aqueous and nonaqueous media; an **amphipathic** substance. [From Greek *amphi*-, of both kinds, + *philos*, loving.]

amphiphilic *an alternative term for* **amphipathic**.

amphiphysin an acidic protein that is localized in many synapses of avian and mammalian nervous systems, and also expressed in adrenal gland and anterior and posterior pituitary tissues. It is an autoantigen in paraneoplastic stiff-man syndrome, a generalized progressive muscular hypertonia.

amphipol a synthetic linear amphiphilic polymer that contains alternating hydrophilic and hydrophobic side chains. It solubilizes integral membrane proteins by wrapping around their hydrophobic segments.

amphiprotic describing a substance that can either gain or lose one or more protons.

amphiregulin a bifunctional transmembrane glycoprotein with a C-terminal EGF-like domain. It inhibits growth of several human carcinoma cells in culture, and stimulates proliferation of human fibroblasts and certain other tumour cells. It is induced by phorbol acetate.

amphitropism the property of proteins that allows them to interconvert between an inactive form in the cell cytosol and an active membrane-lipid-bound form, commonly in response to signals generated on the membrane. Their membrane affinity can be modulated in various ways including by phosphorylation, palmitoylation, prenylation, calcium, and nucleotides. –**amphitropic** *adj.*; **amphitropically** *adv.*

amphoion *a variant spelling of* **amphion**.

Ampholine *the proprietary name for* a series of mixtures of **carrier ampholytes**, which between them span the pH range 2.5–11. They consist of polyamino-polycarboxylic acids formed by reaction between acrylic acid and various polyethylene-polyamines. Each mixture contains a large number of ampholyte species of slightly differing isoelectric points. The mean and maximum apparent molecular masses are approximately 400 and 500 respectively. They are used in **isoelectric focusing**. They set up a pH gradient through the electrophoretic medium, and components being separated equilibrate to a point in the medium corrresponding to their isoelectric point.

ampholyte any amphoteric electrolyte; *see also* **carrier ampholyte**, **amphion**.

ampholyte-displacement chromatography a technique for the fractionation of protein mixtures by displacement chromatography on an ion exchanger using a mobile phase containing a mixture of amphoteric substances of closely spaced isoelectric points (i.e. carrier ampholytes). Separation of the components is thought to involve specific interaction between the proteins and the carrier ampholytes as well as competition between them for sites on the ion exchanger.

amphoteric describing a molecule that can react as acidic towards strong bases and as basic towards strong acids, e.g. an amino acid.

amphotericin B Fungizone; a polyene macrolide antifungal antibiotic produced by *Streptomyces* spp. It is useful against many mycotic infections, acting as a membrane-active lytic agent. At appropriate concentrations it permeabilizes cells, creating pores formed of five to ten molecules of antibiotic in association with cholesterol. These pores allow the passage of low M_r substances. Because it is active only against sterol-containing membranes, mitochondria are not affected. It interacts preferentially with ergosterol, giving it a high affinity for plant membranes; hence its value as a fungicide. *See also* **polyene antibiotic**.

ampicillin a semisynthetic antibiotic of the **penicillin** type, and having a $C_6H_5CH(NH_2)$– side chain.

ampicillin-resistant *symbol*: Ap^r; describing a cell, culture, organism, etc. that shows resistance to the lethal effects of the antibiotic **ampicillin**. This is a *β*-lactam antibiotic and resistance is often mediated by a class of enzymes called ***β*-lactamases**, which are secreted either into the periplasmic space of Gram-negative bacteria or into the medium of Gram-positive bacteria. The cloning vector pBR322 contains an ampicillin-resistance gene.

ampicillin-sensitive *symbol*: Ap^s; describing a cell, culture, organism, etc. that shows sensitivity to the antibiotic ampicillin.

AMPK *abbr. for* adenosine monophosphate-activated protein kinase; a protein serine/threonine kinase that consists of a catalytic α subunit, and regulatory β and γ subunits. Its substrates include glycogen synthase, acetyl-CoA carboxylase, and 3-hydroxy-3-methylglutaryl-CoA reductase. Mutation in a muscle isoform of the γ subunit (**PRKAG3**) in pig muscle results in a glycogen storage abnormality that is present in a high proportion of purebred Hampshire pigs.

amplicon a segment of chromosomal DNA that undergoes amplification or contains multiple copies of a gene.

amplification 1 the act, process, or result of amplifying. **2** the increase in the strength of an electromagnetic, chemical, or acoustic signal effected by an amplifier. **3** the production of additional copies of a stretch of genomic DNA, as a result of DNA either added to cells or originating in the chromosomes. These copies may result in tandem arrays in either an extrachromosomal or chromosomal location. This can result during selection of cells for resistance to certain agents; e.g. methotrexate blocks folate metabolism and may lead to amplification of dihydrofolate reductase genes. **4** the increase in the amount of a DNA with a specific sequence resulting from the **polymerase chain reaction**.

amplification refractory mutation system *abbr*.: ARMS; *a proprietary name for* a method for detection of mutations caused by single nucleotide changes. A pair of oligonucleotide primers are designed in which the 3′ end of one is complementary to the normal nucleotide at the position of the mutation and the other upstream or downstream from it to give a PCR product of a known size when normal DNA is amplified. Another pair of primers are designed in which one primer is complementary to the mutant nucleotide at its 3′ end and the other is placed upstream or downstream to give a PCR product that differs in size from the normal product when the mutant allele is amplified. The mismatch at the 3′ end of the normal primer with the mutant sequence makes it refractory to amplification, and vice versa. By electrophoretic separation of products obtained with both primer pairs it is possible to ascertain whether the individual is homozygous normal, heterozygous, or homozygous for the mutant allele.

amplifier 1 an electronic device used to increase the strength of an electromagnetic signal; especially such a device used to increase the strength of an acoustic signal. **2** a combination of a receptor and various enzymes used to increase the strength of a chemical signal, as in a **cascade sequence**.

amplify to enlarge or to increase in strength or effect, especially an electromagnetic, acoustic, or chemical signal.

amplimer the amplified product of a **polymerase chain reaction**.

amplitude 1 magnitude; greatness of extent. **2** *symbol*: *a*; the maximal displacement from zero or from a mean position of an oscillation or a curve.

AMP-PCP *abbr. for* 5′-adenylyl methylenediphosphonate; i.e. adenosine 5′-[*β*,*γ*-methylene]triphosphate.

AMPPD *abbr. for* adamantyl-1,2-dioxetane phosphate *or* 3-(4-methoxyspiro[1,2-dioxetane-3,2′-tricyclo-[3.3.1.$1^{3,7}$]decan]-4yl)-phenylphosphate. A chemilumigenic substrate for alkaline phosphatase forming the basis of sensitive nonradioactive labelling systems used in association with Northern, Southern, and Western blotting.

AMP-PNP *abbr. for* 5′-adenylyl imidodiphosphonate; i.e. adenosine 5′-[*β*,*γ*-imido]triphosphate.

AMP-S *abbr. for* adenosine 5′-[*α*-thio]monophosphate; i.e. adenosine 5′-thiophosphate.

amrinone 5-amino-(3,4′-bipyridin)-6(1*H*)-one; an inhibitor of cardiac (type III) phosphodiesterase, resulting in increased cardiac contractility and vasodilatation. It is useful in the treatment of heart failure.



AMS *(in clinical biochemistry) abbr. for* α-amylase.

amu *or* AMU *symbol for* atomic mass unit. *See also* **unified atomic mass unit**.

amunine *another name for* **corticotropin-releasing factor**.

amygdalin (–)-D-mandelonitrile *β*-D-gentiobioside; a **cyanogenic** glycoside derived biogenically from phenylalanine and found principally in oil of bitter almonds, although it is present in other plants belonging to the Rosaceae.



amygdalin

amygdalose *former name for* **gentiobiose**.

amyl *former name for* the **pentyl** group.

amyl+ *see* **amylo+**.

amylase any enzyme able to hydrolyse *O*-glucosyl linkages in starch, glycogen, and related polysaccharides (*see* **α-amylase**, **β-amylase**).

α-amylase EC 3.2.1.1; *systematic name*: 1,4-*α*-D-glucan glucohydrolase. An enzyme that catalyses the endohydrolysis of 1,4-*α*-D-glucosidic linkages with the production of mainly *α*-maltose from amylose, but also limit dextrins from **glycogen** and **amylopectin** since it cannot catalyse hydrolysis of 1,6 linkages. It is typical of animal cells (especially pancreas), and saliva. It has five motifs. The plasma level of α-amylase is raised in acute pancreatitis, and assay of the pancreas-specific isoenzyme aids diagnosis. Normal levels in human plasma are <300 IU l^{-1} (this is very method-dependent). The α/β-amylase precursor from *Bacillus polymyxa* is cleaved proteolytically to form the α (551 amino acids) and β (419 amino acids) enzymes.

β-amylase EC 3.2.1.2; *systematic name*: 1,4-*α*-D-glucan maltohydrolase; *other names*: saccharogen amylase; glycogenase. An enzyme that removes successive maltose units from the nonreducing ends of carbohydrate chains; the anomeric group undergoes inversion so that the major product is *β*-maltose. In some organisms it shares the same biosynthetic precursor as α-amylase. β-Amylases are characterized by their formation as insoluble zymogens during the process of seed maturation, and are also found in bacteria.

amylin *or* **islet amyloid polypeptide** (*abbr*.: IAPP) a 37-residue peptide, sequence KCNTATCATQRLANFLVHSSNNFGAILSST-NVGSNTY–NH_2, isolated from pancreatic islet amyloid deposits of an insulinoma and from amyloid-rich pancreases of type 2 diabetic patients; it is found in pancreatic cells and secreted with insulin. Structurally, it closely resembles **calcitonin gene-related peptide** (CGRP), and has 43% and 46% amino-acid sequence similarity with human α- and β-CGRP respectively. Like CGRP, it is C-terminally amidated, and has an N-terminal disulfide bridge linking cysteines 2 and 7. It opposes the action of glycogen synthase in skeletal muscle, and may modulate insulin action. The peptide inhibits insulin-stimulated glucose metabolism in muscle, but not in adipocytes.

amylo+ *or (before a vowel)* **amyl+** *comb. form* denoting starch.

amylo-1,6-glucosidase EC 3.2.1.33; *other name*: dextrin 6-*α*-D-glucosidase; an enzyme that catalyses the endohydrolysis of 1,6-*α*-D-glucoside linkages at points of branching in chains of 1,4-linked *α*-D-glucose residues. The human enzyme also has glycogen debranching (4-*α*-glucanotransferase) activity.

amyloid **1** a waxy eosinophilic translucent material deposited in tissues in **amyloidosis**. Originally thought to be polysaccharide, it is now known to comprise proteinaceous fibrils with a twisted β-pleated sheet structure. It is insoluble, and exhibits a green fluorescence when stained with Congo Red and viewed through crossed Nicol prisms. Amyloid fibres are relatively inert, being resistant to solution in physiological solvents and to proteolytic enzymes. **2** pertaining to or characterized by the production of amyloid. **3** any non-nitrogenous substance resembling starch. **4** like or containing starch.

amyloid A protein *or* **serum amyloid A** (*abbr*.: SAA *or* AA) any of various plasma proteins synthesized by liver, and induced by **cytokine** stimulation. The extracellular accumulation in various tissues of amyloid proteins results in secondary amyloidosis in human and other species. These deposits are highly insoluble and resistant to proteolysis. They disrupt tissue structure and compromise function.

amyloidogenic describing a protein that contains or can form an antiparallel beta-sheet structure that aggregates to form non-branching fibrils of **amyloid**. These fibrils stain with Congo Red and occur in extracellular spaces. Such proteins are associated with amyloidosis, and include amyloid peptide precursor, immunoglobulin light chain, transthyretin, and prion protein. **–amyloidogenically** *adv*.

amyloidosis any of various pathological states in which the deposition of **amyloid** (def. 1) occurs in tissues. It is often associated with chronic infections and immunocyte dyscrasias. In the absence of medical intervention amyloid accumulates implacably, causing pressure atrophy of the affected tissue(s). Death subsequently results from interference with the normal physiological processes of affected vital organs. The descriptive term β-fibrillosis has been suggested for amyloidosis, after the beta-pleated sheet structure of the amyloid fibrils. Amyloidosis may be systemic, with major organ systems involved, or localized and restricted to a single organ. Many cases have a hereditary basis. It is now classified in terms of the protein that accumulates. *See also* **amyloid A protein**.

β-amyloid peptide a glycoprotein associated with Alzheimer's disease, and derived from a precursor, A4, capable of several forms through alternative splicing.

β-amyloid peptide precursor *abbr*.: APP; a type 1 single-pass transmembrane protein that is largely extracellular and binds collagen, laminin, and heparan sulfate side chains of proteoglycans. Several isoforms result from alternative splicing of the pre-mRNA. APP695 predominates in brain, while APP751 and APP770 occur mainly in non-neuronal tissues. All contain the β-amyloid peptide sequence as part of the transmembrane segment. Cleavage by α-secretase (*see* **ADAM-10**) occurs within the β-amyloid peptide sequence, while cleavage by β- and γ-secretases releases this peptide. Several mutations in APP are associated with familial (autosomal dominant, early-onset) forms of Alzheimer's disease.

amyloid precursor-like protein *abbr*.: APLP; either of two proteins belonging to the amyloid peptide precursor family but lacking the amyloid peptide domain. Human APLP1 maps to chromosome 19 and APLP2 to chromosome 11.

amylolysis the process of converting starch into soluble oligo- and monosaccharides, especially by enzymic action. **—amylolytic** *adj.*

amylopectin a polydisperse highly branched **glucan** composed of chains of D-glucopyranose residues in *α*(1→4) glycosidic linkage. The chains are joined together by *α*(1→6) glycosidic linkages. A small number of *α*(1→3) glycosidic linkages and some 6-phosphate ester groups also may occur. The chains are of similar structure to those of glycogen but with fewer and longer branches. Those in amylopectin have been found variously to contain 24 to 30 glucose residues per nonreducing end-group. The size of the molecule varies greatly according to source and method of measurement, with average M_r values of 10^6 to 10^8 reported. Amylopectin occurs in starch, commonly as a mixture with about one-third its mass of **amylose**. However, some starches, notably the so-called waxy starch of maize (*Zea mays*), are almost pure amylopectin. Starch granules serve as the principal cellular store of glucose in most plants.

amylopectin 6-glucanohydrolase *see* ***α*-dextrin endo-1,6-*α*-glucosidase**.

amylopectinosis *see* **glycogen disease**.

amyloplast a colourless **plastid** or **leukoplast** in which starch is stored. It occurs in various plant tissues, e.g. cotyledons, endosperm, and storage organs such as potato tubers.

amylopsin *former term for* **pancreatic *α*-amylase**.

amylopullanase an amylolytic enzyme present in many microorganisms but especially in thermophilic bacteria and archaea. It cleaves *α*1,4- and *α*1,6-glycosidic bonds on the same substrate molecule.

amylose a form of starch comprising a long unbranched **glucan** with *α*(1→4) glycosidic linkages.

amylosucrase *an alternative name for* **sucrase** (def. 3).

amylo-(1,4–1,6)-transglycosylase *see* **branching enzyme**.

amyotrophic lateral sclerosis *abbr*.: ALS; a devastating progressive degeneration of lower motor neurons, usually occurring in adulthood, that leads to weakness and atrophy of the muscles of the face, limbs, and chest, and to death within ≈5 years. Some 10% of cases are familial, and about a fifth of these (ALS1) show autosomal dominant transmission and are due to numerous mutations in the gene for cytosolic superoxide dismutase at 21q22.1. A small subset (ALS2) are recessively transmitted; these are associated with mutations in a locus at 2q33-q35. However, most cases are sporadic. *See* **superoxide dismutase**.

Amytal *proprietary name for* the barbituric sedative 5-ethyl-5-isoamylbarbituric acid, 5-ethyl-5-isopentylbarbituric acid. It inhibits the **electron-transport chain** between flavoproteins and ubiquinone.



an+ *or (before a consonant)* **a+** *prefix* indicating not, without.

+an *suffix* used in forming the semisystematic name of a parent chemical structure from the trivial name of the key compound to which the parent structure is related if the parent structure contains a heteroatom and is saturated; e.g. glucosan, any internal anhydride of glucose.

An *symbol for* **anhydro+**.

anabiosis a return to life after apparent death; a state of suspended animation induced in an organism by, e.g., desiccation or freezing, and reversed by rehydration or warming.

anabolic pertaining to, involving, or exhibiting **anabolism**.

anabolic pathway any sequence of reactions involving **anabolism**; i.e. one in which energy is taken up. *Compare* **catabolic pathway**. *See also* **amphibolic**.

anabolic steroid any of various synthetic steroids that stimulate protein production *in vivo* by mimicking the action of **androgens**.

Drug design aims to minimize masculinizing effects when used in female patients.

anabolism the energy-requiring part of metabolism in which simpler substances are transformed into more complex ones, as in growth and other biosynthetic processes. *Compare* **catabolism**.

anabolite any product of an **anabolic pathway**.

anabolize *or* **anabolise** to effect **anabolism**.

anaemia *a variant spelling (esp. Brit.) of* anemia.

anaerobe any organism that can grow in an atmosphere devoid of dioxygen. A **facultative anaerobe** is also capable of growing in a dioxygen-containing atmosphere whereas an **obligate anaerobe** (or strict anaerobe) can only grow in the absence of dioxygen.

anaerobic **1** describing an organism that is able to grow in the absence of dioxygen. **2** of or produced by an **anaerobe**. **3** (of an atmosphere) devoid of dioxygen. **4** (of a process) characterized by the absence of dioxygen.

anaerobic fermentation any of several catabolic pathways used by living organisms to extract chemical energy from various organic substances in the absence of dioxygen. *Compare* **anaerobic respiration**.

anaerobic glycolysis the metabolic pathways by which glucose is degraded anaerobically to lactate or ethanol. *See* **glycolysis**.

anaerobic indicator any indicator of the attainment and maintenance of anaerobic conditions in an **anaerobic jar**. It may be based on a dye that is decolorized in anaerobic conditions or consist of a culture of a strict anaerobe in one of the dishes in the jar.

anaerobic jar *or* **McIntosh & Fildes jar** an apparatus used to hold culture dishes or tubes under anaerobic conditions. It usually consists of an upright jar with an airtight lid; the air is evacuated and replaced by dihydrogen, which combines with any remaining dioxygen, the reaction being catalysed by a palladium catalyst. [After James McIntosh (1882–1948) and (Sir) Paul (Gordon) Fildes (1882–1971), British bacteriologists who first described the apparatus in 1916.]

anaerobic respiration the metabolic processes by which organisms degrade organic compounds in the absence of dioxygen to yield energy. They make use of inorganic oxidizing agents or accumulate reduced coenzymes. *Compare* **anaerobic fermentation**.

anaerobiosis life in the absence of dioxygen or air.

anagenesis the progressive or 'upward' evolution of a species; any evolutionary process that results in biological improvement. *Compare* **cladogenesis**. **—anagenetic** *adj.*; **anagenetically** *adv.*

anaglyph a stereoscopic moving or still picture made up of two superimposed images of the same object, taken from slightly different angles and reproduced in complementary colours (usually red and bluish green) so as to produce a three-dimensional effect when viewed through spectacles having one lens of each colour.

AnalaR *proprietary name for* any analytical (chemical) reagent that conforms to the tests and purity standards in *'AnalaR' Standards for Laboratory Chemicals* (1977) AnalaR Standards Ltd.

analbuminemia *or (esp. Brit.)* **analbuminaemia** an autosomal recessive condition in which plasma **albumin** is missing, or present in very small amounts, and accompanied by compensatory increases in other plasma protein fractions and frequently hypercholesterolemia. It is associated with several splice junction or nonsense mutations in the gene for albumin at 4q11-q13.

analogous **1** having or showing similar or corresponding attributes. **2** *(in biology)* describing parts, organs, or tissues that have a similar function but differ in structure or evolutionary origin.

analogue *or (esp. US)* **analog** **1** a chemical compound that is structurally similar to another. Such compounds can be used as probes to investigate specificity of, e.g. enzyme activity. **2** a molecule that has acquired similar characteristics to another (e.g. a similar structure or similar active site) from an unrelated ancestor via the process of convergent evolution. For example, the bakers' yeast triose phosphate isomerase and flavocytochrome b_2 C-terminal domain share a TIM-barrel architecture, but have no sequence similarities; the enzymes subtilisin and chymotrypsin are functional analogues that share a Ser–His–Asp catalytic triad with near identical spatial geometries, but have no other sequence or structural similarities.

analogue enrichment *or* **analog enrichment** enrichment of microorganisms capable of co-metabolic degradation of organic pollutants by application of biodegradable analogues of the pollutant to the microbial ecosystem. *See* **co-metabolism**.

analyser *or (US)* **analyzer** **1** the **Nicol prism** of a polariscope or **polarimeter** that receives the light and indicates the degree and/or direction of rotation of its plane of polarization. *Compare* **polarizer**. **2** an instrument for routinely performing chemical analyses, often automatically and/or on a succession of samples. *See* **amino-acid analyser**, **autoanalyser**, **sequenator**.

analysis (*pl.* **analyses**) **1** the process of determining the nature of the chemical constituents of a mixture or of the chemical groups present in a compound (**qualitative analysis**), or the process of determining the amounts of the constituents of a mixture (**quantitative analysis**). **2** the results of such an analysis. **3** the branch of mathematics concerned with the concepts of algebra and calculus. **—analytic** *or* **analytical** *adj.*

analysis of covariance a statistical method for determining the extent of the variance of one variable that is due to variability in some other variable.

analysis of variance a statistical method for segregating the experimentally observed variance between two populations into portions traceable to specific sources.

analyte a component to be measured in an **analysis** (def. 1).

analytical chemistry the branch of chemistry concerned with analysing materials by chemical (or physical) methods.

analytical ultracentrifuge an **ultracentrifuge** equipped with optical systems designed to determine concentration distributions at any time during the measurement. It is used in determinations of **sedimentation coefficients** and **sedimentation equilibrium**.

anamnestic reaction any immunological response in which a second or subsequent exposure to an antigen causes a greater and more rapid reaction than that elicited by the initial exposure. It is a manifestation of immunological memory.

anandamide arachidonoyl ethanolamide; a specific endogenous agonist that serves as a neurotransmitter of the **cannabinoid receptor**. Ligand binding to the G-protein-associated receptor increases tyrosine kinase and decreases adenylate cyclase and cAMP-dependent protein kinase activities. Gap junction intercellular communication betwen striatal astrocytes is also inhibited. Anandamide is formed in neurons by phosphodiesterase cleavage of *N*-arachidonoyl-phosphatidylethanolamine, and is probably then released to the extracellular space. A series of analogues such as *N*-linoleoyl ethanolamide and *N*-palmitoyl ethanolamide are formed simultaneously from appropriate precursors, but their role remains unclear. It may also be formed by condensation of arachidonate with ethanolamine. It is inactivated by reuptake into neurons and hydrolysis by *N*-acyl-ethanolamine amidohydrolase to ethanolamine and arachidonate.



anaphase a stage in **mitosis** or **meiosis** during which the two sister chromatids of each chromosome separate and move towards opposite poles of the spindle.

anaphase promoting complex *abbr.*: APC; a protein complex that initiates the separation of sister chromatids and the onset of anaphase during cell division. It is a 20S particle that contains Cdc16, Cdc23, and Cdc 27 and acts as an E3 enzyme (ubiquitin–protein ligase) in the ubiquitination of cyclin B. *See* ***cdc* gene**, **cyclin**, **ubiquitin–protein ligase**.

anaphylactic shock a severe generalized form of **anaphylaxis** in which there is widespread release of histamine and other vasoactive substances causing edema, constriction of the bronchioles, heart failure, circulatory collapse, and sometimes death.

anaphylactoid reaction an acute syndrome resembling **anaphylac-**

tic shock though caused not by an immunological reaction but by injection of a variety of substances such as bee or snake venom.

anaphylatoxin any of a group of substances that mediate inflammation and are produced in serum during the fixation of **complement**, especially during the production of C3a and C5a. They cause mast cell degranulation and histamine release.

anaphylaxis extreme immunological sensitivity of the body or tissues to the reintroduction of an antigen. It is a form of **anamnestic reaction** and is accompanied by pathological changes in tissues or organs due to the release of pharmacologically active substances. —**anaphylactic** *adj.*

anaphylotoxin inactivator *see* **lysine(arginine) carboxypeptidase**.

anaplasia the reversion by a cell or tissue to a more primitive, embryonic, or undifferentiated form with loss of its characteristics and increased capacity for multiplication.

anaplerosis **1** the filling up of a deficiency; the repair or replacement of losses, especially of tissue. **2** *(in biochemistry)* the process in which an intermediate in the tricarboxylic-acid cycle is replenished through a distinct **anaplerotic metabolic pathway**. This prevents the cycle from ceasing to function because of withdrawal of the intermediate for some other metabolic purpose. [From Greek *ana*, again, back, up + *plerosin*, to fill.] —**anaplerotic** *adj.*

anaplerotic metabolic pathway any sequence of metabolic reactions that serves to maintain the operation of the central pathways of metabolism and which allows the operation and coordination of other metabolic pathways that enter and leave the central pathways.

ANC-1 *abbr. for* anchorage defective-1; a protein (8546 amino acids) of *Caenorhabditis elegans* that is involved in the positioning of nuclei and mitochondria within cells. It contains two actin-binding domains, six repeats (each of ≈903 residues) that form coiled coils, and a C-terminal nuclear envelope transmembrane domain. It is homologous with MSP-300 of *Drosophila* and the mammalian Syne proteins. Mutations in *anc-1* disrupt the positioning and shape of mitochondria.

ancestral sequence *(in molecular phylogeny)* a hypothetical biomolecular sequence reconstructed (using, say, **maximum parsimony** or **maximum likelihood** methods) from the relationships between modern sequences.

anchorage-dependent growth the form of growth shown by mammalian cells cultured from tissue explants that requires them to be attached to solid substrata in order to grow and divide. Cells vary in their requirements for attachment, with some thriving on plastic surfaces whereas others need components of the extracellular matrix such as collagens. Transformed cells such as those derived from tumours do not always exhibit anchorage-dependent growth and can be grown by suspending them in culture media.

anchorin CII *see* **annexin V**.

ancrod an enzyme, extractable from the venom of the Malayan pit viper, *Agkistrodon rhodostoma*, that produces unstable fibrin from fibrinogen by proteolysis. The resulting fibrinogen depletion results in an anticoagulant effect.

Andersen's disease *an alternative name for* type IV **glycogen disease**. [After Dorothy Hansine Andersen (1901–63), US physician.]

androgamone *see* **gamone**.

androgen any substance, natural or synthetic, that is able to stimulate the development of male sexual characteristics. Naturally occurring androgens are C_{19}-steroid hormones. They are produced especially by the testis (e.g. testosterone) and also by the adrenal cortex, ovary, and placenta. *Compare* **estrogen**. —**androgenic** *adj.*

androgen receptor any of the androgen-binding nuclear proteins that mediate the effects of androgens by regulating gene expression; they are **zinc-finger** proteins that bind discrete DNA sequences upstream of transcriptional start sites when the hormone–receptor complex is formed. The steroid-binding domain is in the C-terminal region. In humans, many variants are known that are associated with abnormalities, including testicular feminization syndrome, and complete or partial androgen insensitivity leading to external genitalia varying between female and nearly normal male.

androgen resistance *see* **testicular feminization**.

androstane the C_{19} parent compound from which androgens are structurally derived.

androstenediol 5-androstene-3β,17β-diol; a metabolite of dehydroepiandrosterone, from which it is formed by the action of 17β-hydroxysteroid dehydrogenase, EC 1.1.1.51.



androstenediol

androstenedione 4-androstene-3,17-dione; a precursor of **testosterone** and **estrone**, formed in the testis and ovary from 17α-hydroxyprogesterone by the action of 17α-hydroxyprogesterone aldolase (17,20-lyase), EC 4.1.2.30, or from dehydroepiandrosterone by the action of 3β-hydroxy-Δ^5-steroid dehydrogenase, EC 1.1.1.145. It is also formed in adrenal cortex, from 17-hydroxypregnenolone by an isoenzyme of the 17,20-lyase. Androstenedione is secreted by the adrenals into the circulation and serves as a precursor for sex-hormone formation in peripheral tissues.



androst-16-en-3α-ol 3α-hydroxy-5α-androst-16-ene; 'boar taint'; a major constituent of boar pheromone. It is also present in truffles, which may account for the ability of pigs to locate these underground delicacies.



androsterone 5α-androstan-3α-ol-17-one; a metabolite of **testosterone**, from which it is formed in the liver via androstenedione. The latter is converted to androstanedione by 3-oxo-5α-steroid 4-dehydrogenase, EC 1.3.99.5. Androstanedione in turn is acted on by 3α-hydroxysteroid dehydrogenase, EC 1.1.1.213, forming androsterone.



+ane *suffix (in systematic chemical nomenclature)* denoting **1** an alkane, e.g. pentane. **2** a saturated heterocyclic compound in which the heteroatom is other than nitrogen, e.g. thiolane. **3a** a hydride of boron, silicon, germanium, tin or lead, e.g. borane, silane; **b** a hydride of an unbranched chain of identical atoms of certain elements.

anemia *or (esp. Brit.)* **anaemia** any condition in which the blood has an abnormally low number of red cells (i.e. erythrocytes) or hemoglobin content, or is deficient in total volume. There are many causes, including hypersensitivity reactions to (e.g.) drugs (**hemolytic anemia**) and imbalance of Fe^{2+} metabolism (**iron deficiency anemia**). **Pernicious anemia** is characterized by defective production of erythrocytes and the presence of megaloblasts in the bone marrow; sometimes it is accompanied by neurological changes. It is caused by deficiency of vitamin B_{12} due either to a dietary deficiency of the vitamin or to a failure to produce **intrinsic factor** required for its absorption from the gut.

anergy *(in immunology)* any deficiency in the immune response to an agent that normally induces a response.

aneuploid describing a nucleus or organism in which the chromosome number is not an exact multiple of the haploid number (n). In humans ($n = 23$) examples include the presence of an extra copy of a single chromosome, e.g. trisomy 21 (Down's syndrome), or the absence of a single chromosome, e.g monosomy (as found in Turner's syndrome, 45,X). *Compare* **euploid**, **monosomic**, **nullisomic**, **trisomic**.

aneurin *or* **aneurine** *a former name for* **thiamine**.

ANGEL *abbr. for* activator nongenotropic estrogen-like; a synthetic estrogen-like compound (e.g. Estren, 4-estren-3α,17β-diol) that produces effects on certain parts of the body (e.g. osteoblasts) without affecting reproductive organs.

angiogenesis the formation of blood vessels, whether during embryogenesis, tissue repair, or invasive growth of tumours.

angiogenin a **cytokine**, produced by fibroblasts, lymphocytes, and colon epithelial cells, that induces neovascularization, and can serve as a substratum for endothelial and fibroblast cell adhesion. A monomeric protein, it is a member of the pancreatic ribonuclease family, and specifically hydrolyses tRNAs, thus inhibiting protein synthesis.

angioneurotic edema *or (esp. Brit.)* **angioneurotic oedema** *an alternative name for* **hereditary angioedema**.

angiopoietin either of two secreted glycoproteins that have considerable sequence homology, contain a coiled coil and a fibrinogen-like domain, and are major regulators of angiogenesis. Ang1 contains 498 amino acids, and Ang2 has 496 amino acids. Both bind to specific endothelial cell-specific receptor tyrosine kinases. Ang1 is widely expressed in embryonal and adult tissues, whereas Ang2 is widely expressed in the embryo but only in ovary, uterus, and placenta in adults.

angiosperm a flowering plant; any member of the class Angiospermae, division Spermatophyta (seed plants). *Compare* **gymnosperm**.

angiostatin an internal fragment of **plasminogen**, released by the action of elastase, that contains the first four kringle domains of plasminogen. It is a potent inhibitor of angiogenesis and of the growth of certain tumours.

angiotensin any of three related peptides, two of which regulate adrenal activity and also increase vasoconstriction and raise blood pressure. **Angiotensin I**, the decapeptide H–Asp-Arg-Val-Tyr-Ile-His-Pro-Phe-His-Leu–OH, is cleaved off **angiotensinogen** by the kidney enzyme **renin**; this peptide has no physiologically important action. **Angiotensin II**, the octapeptide formed from angiotensin I by removal of -His-Leu–OH by the action of **angiotensin converting enzyme**, is the most powerful pressor agent known, and the substance responsible for essential hypertension. It is also one of the most potent known stimulators of aldosterone production by the adrenal gland. It is rapidly destroyed by tissue peptidases, including **angiotensinase**. **Angiotensin III**, the heptapeptide formed by removal of the N-terminal Asp residue from angiotensin II (and the only one of its breakdown products to have activity), appears to be as active on the adrenal gland as angiotensin II, and may also have significant vasoconstrictor activity.

angiotensinase an enzyme with proteinase activity that inactivates angiotensin II. Angiotensinase A is an alternative name for **glutamyl aminopeptidase**, EC 3.4.11.7, and angiotensinase C is another name for **lysosomal Pro-X carboxypeptidase**, EC 3.4.16.2.

angiotensin converting enzyme *abbr.*: ACE; EC 3.4.15.1; *recommended name*: peptidyl dipeptidase A; *other names*: serum converting enzyme; peptidase P; peptidyl carboxypeptidase I; carboxycathepsin; kininase II. A Cl^--dependent zinc-containing dipeptidase present in lung, the brush borders of the proximal renal tubule, the endothelium of vascular beds, and plasma. It catalyses the release of a C-terminal dipeptide, -Xaa-|-Xbb-Xcc, when neither Xaa nor Xbb is proline, hence its conversion of angiotensin I to angiotensin II. It also acts on bradykinin. It is a transmembrane glycoprotein; two types (testis and somatic) arise by alternative splicing and different transcriptional start points. The presence (I) or absence (D) of a 287bp Alu repeat in intron 16 in a locus at 17q23 gives three genotypes: I/I, I/D, and D/D. The D allele is associated with increased plasma ACE levels and statistically is associated with hypertension in males, and hence has a bearing on the pathophysiology of cardiovascular disease.

angiotensin converting enzyme inhibitors compounds that prevent the synthesis of angiotensin II from its precursor, angiotensin I, e.g. **captopril**, **enalapril**. Such inhibitors are used in the treatment of cardiac failure and hypertension.

angiotensinogen a plasma α_2-globulin formed in liver, and the precursor of **angiotensin** I, II and III; it is similar to the **serpins**.

angiotensinogenase *see* **renin**.

angiotensin receptor any of several membrane proteins that bind angiotensin, and mediate its intracellular effects. Two types of receptor, AT_1 and AT_2, have been identified on the basis of their response to drugs. The AT_1 receptor (previously known as AII_1 or AII_α) has high affinity for **losartan**, and lower affinity for CGP42112A; the reverse is true for AT_2 receptors. The potency of endogenous ligands is angiotensin II > angiotensin III. In peripheral tissues, AT_1 receptors, but not AT_2 receptors, interact with G proteins, inhibit adenylate cyclase, and activate phospholipases C and A_2. AT_2 receptors may stimulate a phosphotyrosine phosphatase leading to inhibition of guanylate cyclase. Sulfhydryl reducing agents inhibit the binding of angiotensin II to AT_1 receptors, but enhance its binding to AT. Both types are G protein-coupled **7TM proteins**.

angle 1 the inclination between two lines or planes: **plane angle**. It is dimensionless and given in radians (*symbol*: rad), degrees (*symbol*: °; $1° = \pi/180$ rad); minutes (*symbol*: ′) $1' = \pi/10\,800$ rad; or seconds (*symbol*: ″); $1'' = \pi/64\,800$ rad. **2** the (three-dimensional) vertex of a cone: **solid angle**. It is dimensionless but may be expressed in **steradians** (*symbol*: sr).

angle head *or* **angle rotor** any rotor for a centrifuge in which the tubes containing the liquid are at a fixed angle to the axis of rotation. *Compare* **swinging bucket rotor**.

ångström *or* **Ångstrom** *symbol*: Å; a unit of length equal to 10^{-10} metres. It is used in atomic measurements and for wavelengths of electromagnetic radiation, and is temporarily approved for use with SI units. [After Anders Jonas Ångström (1814–74), Swedish physicist noted for his work on spectroscopy.]

angular velocity *symbol*: ω; the rate of rotation of an object expressed as its rate of motion through an angle about an axis. It is expressed in rad s^{-1}.

anhydrase *see* **carbonic anhydrase**.

anhydride a derivative of a substance that yields the substance when combined chemically with water.

anhydro+ *symbol*: An; *prefix* (in a chemical name) denoting the loss of the elements of water from within one molecule or residue. The positions from which removal has occurred may be indicated by a pair of locants, e.g. 2,5-anhydro-D-gluconic acid.

anhydrosialidase EC 3.2.1.138; *other names*: anhydroneuraminidase; sialidase L; an enzyme that catalyses the hydrolysis of α-sialosyl linkages in *N*-acetylneuraminic acid glycosides, releasing 2,7-anhydro-α-*N*-acetylneuraminic acid.

anhydrosugar any intramolecular ether formed by the elimination of water from two (indicated) alcoholic hydroxyl groups of a single molecule of a monosaccharide, whether aldose or ketose; i.e. any anhydromonosaccharide whose formation does not involve the reducing group.

anhydrous devoid of water, especially (of a substance or material) lacking water of crystallization or adsorbed water, or (of an environment) very dry. *See also* **dehydration**.

animal pole *see* **vegetal pole**.

animal protein factor a name formerly used for a growth factor for livestock, found to be present in meat and fish but not in feeds of plant origin. It was later shown to be identical with anti-pernicious anemia factor, i.e. vitamin B_{12}.

anion an **ion** with a net negative charge; during electrolysis of a solution anions migrate towards the **anode**. *Compare* **cation**. —**anionic** *adj.*

anion channel protein *or* **band 3 protein** *or* **anion exchanger** *or* **Cl^-/HCO_3^- exchanger** either of two integral plasma membrane glycoproteins, both 911 residues long and showing ≈70% sequence homology. Their N-terminal 403 residues are cytoplasmic, the rest form 12–14 putative transmembrane segments. AE1 (locus at 17q21-q22), the erythroid form, is predominant in erythrocyte membranes, where it mediates exchange of Cl^- for HCO_3^- and is the major site for anchoring of the submembranous cytoskeleton. Mutations at this locus are associated with hereditary spherocytosis, elliptocytosis, ovalocytosis, or acanthocytosis, or with distal renal tubular acidosis. An isoform of AE1 that lacks the N-terminal 66 residues occurs in the basolateral membrane of cells of renal collecting ducts. AE2 (locus on chromosome 7) is the non-erythroid form. *See* **band protein**.

anion exchanger **1** *or* **anion-exchange resin** any **ion-exchange resin** that carries positively charged groups, e.g. quaternary ammonium groups, and binds anions. **2** *an alternative name for* **anion channel protein**.

anion gap *(in clinical chemistry)*, the difference, in meq l^{-1}, between the concentrations of serum sodium plus potassium and of the serum chloride plus bicarbonate; i.e.

$$\text{anion gap} = [Na^+ + K^+] - [Cl^- + HCO_3^-].$$

Normal values are 12 ± 2 meq L^{-1}. Variations in the anion gap provide a useful insight into the acid–base status of a subject.

anionic detergent a detergent in which the polar part of the molecule carries a negative charge. *Compare* **nonionic detergent**.

anisotropic describing a medium in which physical properties, such as the velocity of electromagnetic radiation transmission, electrical or heat conductivities, or compressibility, have different values when measured along axes in different directions. —**anisotropically** *adv.*; **anisotropy** *or* **anisotropism** *n.*

anisotropic motion rotation about a single axis, especially of a molecule or a **spin label**.

anisotropy the property of molecules and materials of exhibiting variations in physical properties along different axes of the substance.

ankyrin *or* **band 2.1 (protein)** *or* **nexin** *or* **syndein** a 200 kDa cytoskeletal protein that attaches other cytoskeletal proteins to integral membrane proteins. It is bound tightly to the cytoplasmic surface of the human erythrocyte membrane, to which it attaches the cytoskeletal protein **spectrin**. [After the Greek *ankyra*, anchor.]

ankyrin repeat a 33-amino acid sequence that occurs 24 times in the 'membrane' part of **ankyrin** and is also present in several hundred other proteins. It forms a beta hairpin-alpha helix-loop-alpha helix structure.

ANN *abbr. for* artificial neural network.

annealing **1** the renaturation of heat-denatured nucleic acids or proteins by slow cooling. **2** the formation of hybrid double-stranded nucleic acid molecules by the slow cooling of a mixture of denatured, single-stranded nucleic acids. It is used to detect complementary regions of different nucleic-acid molecules. When one of the nucleic acids is an oligonucleotide, perfect complementarity with a target sequence can be distinguished from mismatched duplexes by selecting an annealing temperature close to the **melting temperature** (T_m) for the oligonucleotide. **3** the second phase of a **polymerase chain reaction**. **4** the slow regulated cooling, especially of metals or glasses, to relieve the stresses caused by heating or other treatments. —**annealer** *n.*

annexin any of a ubiquitous family of Ca^{2+}-dependent phospholipid-binding proteins. They have been isolated from organisms as diverse as mammals, *Drosophila melanogaster*, and *Hydra vulgaris*. Characteristically they have a low intrinsic affinity for Ca^{2+} (K_d 25–1000 μm), although annexin VI has K_d ≈1 μm, but in the presence of phospholipid the affinity for Ca^{2+} increases up to 100-fold. The Ca^{2+}- and phospholipid-binding properties that typify the family derive from a region of common primary structure (identity with any other member of the family is 40–60%) in a conserved 34 kDa C-terminal region (the 'core'); each different type of annexin has a unique N-terminal domain known as the 'tail'. The C-terminal region in all cases except one consists of four repeats of a ≈70 amino-acid sequence, in which there is a high homology region known as the **endonexin fold**, with a characteristic motif GXGTDE; the exception is annexin VI, which has eight repeats. The true physiological roles of the annexins remain unknown, but their main characteristics, exhibited variously by different annexins and reflected in the alternative names they acquired in the course of discovery, include: the ability to aggregate membranes and vesicles (all annexins); inhibition of phospholipase A_2 (especially I, but also II to VI); formation of ion channels (especially I and V to VII); anticoagulant properties (especially I, and VIII); and acting as substrates for tyrosine kinases (I and II) and protein kinase C (I, II, IV, and XII). Alternative names are given under the individual entries.

annexin I *other names*: annexin A1; lipocortin I; p35 (EGF receptor substrate); calpactin II; chromobindin 9; GIF; lipomodulin; macrocortin; phospholipase A2 inhibitory protein; renocortin.

annexin II *other names*: annexin A2; calpactin I heavy chain; lipocortin II; p36 ($pp60^{src}$ substrate); chromobindin 8; protein I; placental anticoagulant protein (PAP)-IV.

annexin III *other names*: annexin A3; lipocortin III; placental anticoagulant protein (PAP)-III; 35-*α*-calcimedin; calphobindin III; inositol 1,2-cyclic phosphohydrolase.

annexin IV *other names*: annexin A4; endonexin I; protein II; P32.5; lipocortin IV; chromobindin 4; placental anticoagulant protein (PAP)-II; PP4-X; 35-*β*-calcimedin; placental anticoagulant protein II; carbohydrate-binding protein P33/P41.

annexin V *other names*: annexin A5; lipocortin V; endonexin II; calphobindin I; CBP-I; placental anticoagulant protein (PAP)- I; PP4; thromboplastin inhibitor; vascular anticoagulant (VAC)-alpha; anchorin CII.

annexin VI *other names*: annexin A6; p68; p70; 73K; 67K calelectrin; lipocortin VI; protein III; chromobindin 20; 67 kDa calelectrin; calphobindin II; CPB-II.

annexin VII *other names:* annexin A7; **synexin**.

annexin VIII *other names*: annexin A8; vascular anticoagulant (VAC)-β.

annexin IX *other name*: annexin B9.

annexin X *other name*: *Drosophila melanogaster* annexin.

annexin XI *other names*: annexin A11; calcyclin-associated annexin 50; CAP-50; 56 kDa autoantigen.

annexin XII *other names*: annexin B12; a member of the annexin family obtained from *Hydra attenuata* (*Hydra vulgaris*). [

annexin XIII *other names*: annexin A13; intestine-specific annexin (ISA).

annexin XXI *other names*: annexin E1; a member of the annexin family obtained from *Giardia lamblia* (*Giardia intestinalis*).

annexin XXXI *other names*: annexin A9; annexin 31.

annexin 14 *other name*: annexin A10.

annihilation radiation electromagnetic radiation of wavelength 2.4 pm (energy 0.51 MeV) that is emitted as a pair of photons when a positron absorbed into matter reaches the end of its range and combines with an electron in mutual destruction.

annotation a set of descriptive notes (detailing, e.g., function, structure, disease associations, keywords, literature references) that are attached to database entries (such as protein or nucleic acid sequences, or protein families).

anode **1** the electrode of an electrolysis cell or electrophoresis apparatus towards which anions of the electrolyte migrate under the influence of an electric field applied between the electrodes. **2** the positive electrode, pole, or terminal of such a cell or apparatus, or of a discharge tube, solid-state rectifier, or thermionic valve; the electrode by which electrons flow out of the device. **3** the negative pole or terminal of an electric (primary or secondary) cell or battery (of cells). *Compare* **cathode**. —**anodal** *or* **anodic** *adj*; **anodally** *or* **anodically** *adv.*

anodic stripping voltammetry *abbr.*: ASV; an electrochemical procedure for estimating the concentration of metal ions in a solution. Exhaustive or partial (depending on the concentrations involved) deposition of the metal occurs on the cathode of an electrolytic cell at a constant applied electric potential (controlled potential deposition can be used for selectivity when mixtures are involved). The metal deposit is then anodically stripped by using a rapid sweep of voltage of opposite polarity and a peak-type current–voltage curve is obtained. The amount of metal deposited may be calculated coulometrically from the area under the peak, or by other means, and hence the concentration of metal ions in the initial solution may be determined.

anodic to during electrophoresis, migrating further towards the anode or less far towards the cathode than (the specified substance).

anolyte the electrolyte in immediate contact with the anode in isoelectric focusing.

anomalous dispersion **1** an X-ray crystallographic dispersion that occurs when the frequency of the X-rays used falls near an absorption frequency of an atom in the crystal. Anomalous dispersion techniques are frequently used in the determination of absolute configuration. **2** an optical rotatory dispersion that cannot be expressed by a simple one-term **Drude equation**.

anomer either of the two stereoisomers of the cyclic form of an **aldose** or a **ketose**, or an aldose or ketose derivative, dependent on the position of the free hydroxyl group belonging to the internal hemiacetal grouping. The anomer having the same configuration, in the **Fischer projection**, at the anomeric and the reference asymmetric carbon atom is designated α; the other anomer is designated β. In correct usage in regard to carbohydrates, the anomeric and configurational descriptors must always be linked together; e.g. α-D-glucopyranose, not α-glucose.

anomeric **1** of or pertaining to an **anomer**. **2** *or* **glycosidic** of or pertaining to the free hydroxyl group belonging to the internal hemiacetal grouping in the cyclic form of a monosaccharide or monosaccharide derivative.

anomeric effect the tendency for an electronegative substituent at C-1 of a pyranose to assume the axial orientation, in contrast to the equatorial orientation predicted on steric grounds.

anorexia absence of desire for food. In infants it is the failure to thrive. **Anorexia nervosa** is a feeding disorder, predominantly of females, that starts typically in adolescence and is associated with amenorrhea and regression of secondary sexual characteristics common in hypothalamic dysfunction.

anosmia loss of the sense of smell.

anoxia the absence or a deficiency of dioxygen. *Compare* **hypoxia**. —**anoxic** *adj.*

ANP *abbr. for* atrial natriuretic peptide. *See* **natriuretic peptide**.

ANPR *abbr. for* atrial natriuretic peptide receptor.

ANS *abbr. for* 1-anilino-8-naphthalene sulfonate; a common fluor used in extrinsic fluorescence studies of proteins.

ansamycin any antibiotic belonging to the **rifamycin** or the **streptovaricin** classes.

anserine *N*-β-alanyl-N^{π}-methyl-L-histidine; an isopeptide occurring in skeletal muscle and brain of some animals and humans (up to 20 mmol kg^{-1}). *Compare* **carnosine**.



ANSI *abbr. for* American National Standards Institute; an organization responsible for, among other standards, ANSI escape sequences for printing certain effects and available on some computers, and ANSI C (a standard for the C programming language).

Anson unit an old measure of the activity of a proteinase. It was based upon the extent to which a sample containing a particular proteinase can digest denatured hemoglobin, under standard conditions appropriate to the enzyme in question, with liberation of nonprecipitable material giving the same colour value as one millimole of tyrosine on reaction with a diluted Folin–Ciocalteau reagent. [After Mortimer Lewis Anson (1901–68), US protein chemist, who described it in 1958.]

ant+ *a variant of* **anti+**.

Antabuse *proprietary name for* **disulfiram**.

antagonism **1** opposition; counteraction. **2** the mutual opposition of an agonist and an antagonist. **3** the interference with, or inhibition of, the growth of an organism by one of another kind, as by competing for nutrients or producing an antibiotic substance.

antagonist **1** anything that antagonizes. **2** any agent, especially a drug or hormone, that reduces the action of another agent, the **agonist**. Many act at the same receptor as the agonist. Such antagonists may be either surmountable or insurmountable, depending on prevailing conditions. Antagonism may also result from combination with the substance being antagonized (**chemical antagonism**), or the production of an opposite effect through a different receptor (**functional antagonism** or **physiological antagonism**), or as a consequence of competition for the binding site of an intermediate that links receptor activation to the effect observed (indirect antagonism). The term ‘functional antagonism’ is also used to describe a less well-defined category in which the antagonist interferes with other events that follow receptor activation. **3** a muscle that works in opposition to another (the agonist). *See also* **competitive antagonism**, **noncompetitive antagonism**. *Compare* **agonist**, **inverse agonist**, **synergist**. —**antagonistic** *adj.*; **antagonistically** *adv.*

antagonize *or* **antagonise** to act in opposition to; to counteract. —**antagonized** *or* **antagonised** *adj.*

antanamide a highly lipophilic homodetic cyclic decapeptide, cyclo(-Pro-Phe-Phe-Val-Pro-Pro-Ala-Phe-Phe-Pro-). It occurs in the death-cap fungus, *Amanita phalloides*, together with the **amatoxins** and **phallotoxins**. When administered to experimental animals (at 1 mg per kg of body weight), either before or at most a few minutes after a lethal dose of phallotoxin, it acts as an antidote to the toxin, apparently by competing for binding sites. *In vitro* it readily forms complexes with sodium and calcium ions, and can act as a sodium ionophore.

ANT-C *abbr. for* antennapedia complex; one of two major families of homeotic genes of *Drosophila* (the other being **BX-C**), mutation of which affects head and thoracic segments. Antennapedia protein is a penetratin.

ante+ *prefix* denoting before in time or position.

antegrade *a variant of* **anterograde**.

anteiso+ *prefix* denoting a branched-chain fatty acid having a methyl group at the *n*-3 position; e.g. 16-methyloctadecanoic acid, also named anteisononadecanoic acid.

antenna complex any of the light-harvesting pigment-protein complexes of photosynthetic organisms that funnel absorbed incident radiation to the photochemical reaction centres.

antennapedia complex *see* **ANT-C**.

anterograde *or* **antegrade** **1** moving forwards; extending towards the front. **2** moving along the axon of a nerve cell in a direction away from the cell body (as in anterograde transport of vesicles). *Compare* **retrograde**.

antheridiol a steroid hormone produced by water moulds (e.g. *Achyla* spp.) to regulate their sexual reproduction.

anthocyanidin any member of a group of water-insoluble coloured polyhydroxylated 2-phenylbenzopyrylium compounds that occur as glycosides – anthocyanins – in flowers. They comprise one class of the widespread group of flavonoids. There are three coloured aglycones: the pelargonidins (of geraniums), which are orange, salmon, pink, or red; the cyanidins (of roses), which are magenta or crimson; and the delphinidins (of larkspur), which are purple, mauve, or blue. These aglycones differ by having one, two, or three hydroxyl groups, respectively, in the 2-phenyl nucleus.

anthocyanin any member of a group of intensely coloured soluble glycosides of anthocyanidins that occur in plants. They are responsible for most of the scarlet, purple, mauve, and blue colouring in higher plants, especially of flowers.

antho-K amide L-3-phenyllactyl-Phe-Lys-Ala–NH_2; a neuropeptide from the sea anemone, *Anthopleura elegantissima*.

anthracene a tricyclic aromatic compound, $C_{14}H_{10}$; it is a component of a number of **scintillation cocktails**.



anthralin 1,8-dihydroxyanthrone; a substance that inhibits **leukotriene** biosynthesis. It is used as an antipsoriatic drug.



anthranilate 2-aminobenzoate (anion, salt, or ester); an intermediate in the biosynthesis of tryptophan.

anthranilate synthase EC 4.1.3.27; *systematic name*: chorismate pyruvate-lyase (amino-accepting). An enzyme that catalyses the first step in tryptophan biosynthesis, in which chorismate and L-glutamine react to form anthranilate, pyruvate, and L-glutamate. It is a tetramer of two components, I and II: in the absence of II, I catalyses the formation of anthranilate using NH_3 rather than glutamine; II provides glutamine amidotransferase activity.

anthrax toxin a group of proteins secreted by *Bacillus anthracis* that causes anthrax, a highly contagious and potentially lethal disease.The toxin comprises protective antigen (PA), edema factor (EF), and lethal factor (LF). PA forms a hexamer that binds to cell-surface receptors on skin, lung, and gastrointestinal tract, and helps to translocate EF and LF into the cytoplasm. EF is a calmodulin-dependent adenylate cyclase, while LF is a zinc metalloproteinase uniquely specific for mitogen-activated protein kinase, which it inactivates by cleaving between the N-terminal region and the catalytic domain.

anthrone 9(10*H*)-anthracenone; a compound used in the colorimetric determination of carbohydrates, especially hexoses, with which it gives a green colour.



anti+ *or (sometimes before a vowel or h)* **ant+** *prefix* **1** acting against, counteracting, or inhibiting. **2** opposite to (in direction). **3** converse or reverse of; complementary to.

anti+ *prefix (obsolete)* denoting a *cis* isomer.

antiamoebin *or* **antiamebin** *see* **peptaibophol**.

antiarose the D isomer, 6-deoxy-D-gulose; occurs in glycosidic linkage in some **cardiac glycosides**.



β-D-pyranose form

antibiotic 1 any of numerous substances of relatively low M_r produced by living microorganisms (and also certain plants) that are able selectively and at low concentrations to destroy or inhibit the growth of other organisms, especially microorganisms. Also included are the many semi- or wholly synthetic organic compounds with similar antimicrobial properties. Many are useful chemotherapeutic agents. **2** of or relating to an antibiotic.

antibody any glycoprotein of the **immunoglobulin** family that is capable of combining noncovalently, reversibly, and in a specific manner with a corresponding antigen. Antibodies frequently, but not always, counteract the biological activity of antigens. They are produced in higher animals by cells of the lymphoid cell series, especially plasma cells, in direct response to the introduction of immunogens or autocoupling haptens. Antibodies were originally identified as a class of serum proteins, and most are present in the γ-globulin fraction of the serum. In the ultracentrifuge most antibodies have a sedimentation coefficient of 7S, except for the pentameric IgM at 19S. *See also* **cell-bound antibody**.

antibody-dependent cellular toxicity (ADCT) A cytotoxic reaction in which an antibody-coated target cell is directly killed by an Fc receptor-bearing **leucocyte**, such as a **NK cell**, a **macrophage**, or a **neutrophil**.

antibody-mediated hypersensitivity *or* **type II hypersensitivity** an immune response caused by the presence of antibody to cell-surface antigens and components of the extracellular matrix. These antibodies can sensitize the cells for antibody-dependent cytotoxic attack by **K cells** or **complement**-mediated lysis. Type II hypersensitivity is seen in the destruction of red cells in transfusion reactions and in hemolytic disease of the newborn.

anticholinesterase any agent, other than an antibody, that inhibits **cholinesterase** (def. 2). An example is **physostigmine**, used in the diagnosis and treatment of myasthenia gravis.

anticipation the phenomenon whereby the age of onset of a disease becomes earlier and the severity of disease symptoms increases with successive generations. It is common in disorders resulting from trinucleotide repeat mutations that increase in size through generations, such as **Huntington's disease**.

anticircular chromatography a technique of thin-layer chromatography in which the substances to be separated are applied just inside the perimeter of a circular thin-layer plate and are made to travel radially inwards by subsequent application of the developing solvent at the edge of the plate. It is very fast and is particularly useful for the resolution of substances whose R_f values approach unity. *Compare* **circular chromatography**.

anticlinal *see* **conformation** (def. 2).

anticoagulant 1 retarding or preventing coagulation. **2** any substance that retards or prevents coagulation, especially of blood or milk.

anticoagulate to treat (esp. blood) so as to prevent coagulation.

anticodon a triplet of nucleotides in any particular transfer RNA that is complementary to and therefore pairs with a given **codon** in messenger RNA. The pairing is antiparallel, 5′→3′ in the messenger, 3′→5′ in the anticodon. Thus the anticodon of 5′-ACG-3′ is 3′-UGC-5′. However, to maintain the convention of writing sequences in the 5′→3′ direction, the anticodon is thus written, but with a reverse arrow above: $\overleftarrow{\text{CGU}}$.

anticodon arm the part in the clover-leaf model of transfer RNA containing a loop bearing the anticodon.

anticooperativity negative **cooperativity** between binding sites on the same (macro)molecule by which binding of a ligand to one site makes the binding of a second ligand more difficult.

antidiuretic 1 describing any drug or other agent that decreases the excretion of urine. **2** an antidiuretic substance.

antidiuretic hormone *abbr*.: ADH; *an alternative name (esp. in clinical chemistry) for* **vasopressin**. It is so named from the hormone's most important biological action, viz. reducing the rate of urine output by stimulating the rate of water reabsorption by the kidney(s).

antidote a substance or other agent that limits or reverses the effects of a poison.

antifolate any of a class of drugs that interfere with the formation of tetrahydrofolate, and are used in the treatment of acute leukemia and choriocarcinoma. One of the best known is **methotrexate**.

antifreeze glycoprotein any of a group of glycoproteins found in the serum of certain cold-water fish, particularly notothanids and chaenichthyids, which inhabit polar seas; e.g., *Trematomus borchgrevinki* and *Dissostichus mawsoni*. These glycoproteins depress the freezing point of aqueous solutions about 200–500 times as effectively as sodium chloride on a molar basis. They differ only in mass (10.5 kDa, 17 kDa and 21.5 kDa), and are composed of repeating units of a diglycosyl tripeptide, Ala-Ala-Thr-*O*-disaccharide, in which the disaccharide consists of a β-galactosyl residue bound to an internal α-*N*-acetylgalactosaminyl residue.

antigen **1** (*or* **complete antigen**) any agent that, when introduced into an immunocompetent animal, stimulates the production of a specific antibody or antibodies that can combine with the antigen. It may be a pure substance, a mixture of substances, or particulate material (including cells or cell fragments). In this sense the term includes **agglutinogen** and **allergen** and is synonymous with **immunogen** (def. 1). **2** (*or* **incomplete antigen**) any substance that can combine with a specific antibody but is not an **immunogen** (def. 2), i.e. it is not by itself able to stimulate antibody production though it may do so if combined with a **carrier** (def. 8). In this sense the term includes **hapten**. **—antigenic** *adj.*

antigen–antibody complex *or* **immune complex** any specific macromolecular complex of antigen and antibody. It may be soluble, especially in **antigen excess**, or insoluble (as a precipitate) when antigen and antibody are present in optimal proportions. Components of **complement** may bind to antigen–antibody complexes. *See also* **immune complex-mediated hypersensitivity**.

antigen-binding capacity *abbr.*: ABC; the total amount of antibody in a preparation, e.g. serum, based on a determination of the amount of antigen bound by unit amount of the preparation.

antigen excess the condition when a mixture of antigen and antibody contains sufficient antigen to combine with all the combining sites of the specific antibody molecules, leaving some free uncombined antigenic determinants and resulting in the formation of soluble antigen–antibody complexes. This is the explanation for the type of 'precipitin' curve when increasing amounts of antigen are incubated with a fixed amount of antibody and the amount of precipitate is measured.

antigenic determinant any specific chemical structure within, and generally small in relation to, an antigen molecule that is recognizable by a combining site of an antibody, or T-cell or B-cell receptor, and at which combination takes place. It determines the specificity of the antibody–antigen reaction. Several different antigenic determinants may be carried by a single molecule of antigen. *See also* **epitope**.

antigenic drift any of the minor changes in the antigenicity of influenza virus that result from spontaneous mutation, with corresponding minor changes in the amino-acid sequence of the viral hemagglutinin. *Compare* **antigenic shift**.

antigenicity the capacity of an agent to stimulate the formation of specific antibodies to itself.

antigenic mimicry the sharing of antigenic determinants by microbial agents and body proteins as a result of similarity in amino acid sequences. This might play a role in autoimmune disease because the microbial sequences produce antibodies against the equivalent sequences in body proteins.

antigenic shift any of the major changes in the antigenicity of influenza virus that result from spontaneous mutation, with corresponding major changes in the amino-acid sequence of the viral hemagglutinin. *Compare* **antigenic drift**.

(antigen-independent) mitogenic factor a **lymphokine** that acts as a **mitogen** for lymphocytes.

antigen-presenting cell *abbr.*: APC; a cell, especially a macrophage or dendritic cell, that recognizes an antigen to be targeted for neutralization. It takes up the antigen and processes it, incorporating antigen fragments into its own membrane and presenting them in association with class II **major histocompatibility complex** molecules to T lymphocytes, which are then stimulated to mount a response.

antigibberellin any of the organic compounds that cause plants to grow with thick stems or with an appearance differing from that obtained with **gibberellin**. The effect can usually be reversed by gibberellin.

antiglobulin consumption test a serological method for demonstrating antibody (globulin) attachment to cells. It is based on showing that antiglobulin is removed from solution on addition of the cells in question.

antiglobulin test *or* **Coombs test** a test for the presence of incomplete **antibody** against red blood cells. It entails the addition of heteroantibody to immunoglobulin (i.e. antiglobulin) to cause the agglutination of red blood cells previously coated with nonagglutinating incomplete antibody. *Compare* **double-antibody method**. [After Robin Royston Amos Coombs (b. 1921), British immunologist and hematologist who (with others) described it in 1945.]

antihemophilic factor *or* **antihemophilic factor A** *or* **antihemophilic globulin** *an alternative name for* factor VIII; *see* **blood clotting factors**.

antihemophilic factor B *an alternative name for* factor IX; *see* **blood coagulation**.

antihemophilic factor C *an alternative name for* factor XI; *see* **blood coagulation**.

antihemophilic globulin *an alternative name for* **antihemophilic factor**.

antihistamine any drug or other agent that antagonizes an action of histamine on the body. Antihistamines are used in the treatment of immediate-type hypersensitivity.

antihormone any substance that acts to attenuate hormone-induced responses, regardless of the mechanism involved.

anti-idiotype an antibody that reacts with **epitopes** on the V region of the **T-cell receptor**.

anti-inducer any compound that inhibits **operon** induction by competing for inducer binding to free repressor and stabilizing the repressor–operator complex.

antilipolytic **1** describing any agent that inhibits **lipolysis**. **2** an antilipolytic agent.

antilipotropic **1** describing any agent that is active metabolically in deflecting methyl groups from the synthesis of choline. **2** an antilipotropic agent.

antilogarithm *abbr.*: antilog; *symbol*: (decadic) lg^{-1}; (napierian) ln^{-1}; the number that is represented by a **logarithm**.

antilymphocyte globulin the globulin fraction of an **antilymphocyte serum**.

antilymphocyte serum *abbr.*: ALS; any serum containing antibodies to lymphocytes. It is used as a selective immunosuppressive agent.

anti-messenger DNA *abbr.*: amDNA; *an alternative name for* **complementary DNA**.

antimetabolite any substance that inhibits the utilization of a metabolite, e.g. by acting antagonistically through competition in a transport system or at a key enzyme site.

antimicrobial **1** describing a drug, antibiotic agent, physical process, radiation, etc. that is inimical to microbes. **2** any substance having antimicrobial properties.

antimicrobial spectrum a list of the types of microbes against which an antimicrobial agent is effective.

antimitotic **1** describing any agent that decreases the rate of mitosis. **2** an antimitotic agent.

antimonial **1** of, relating to, or containing antimony. **2** a drug containing antimony.

antimorph **1** a mutant gene producing an effect opposite to the wild-type gene at the same locus. *Compare* **allele**. **2** *obsolete term for* an **enantiomorph**.

anti-Müllerian hormone *or* **Müllerian inhibiting factor** a glycoprotein, derived from a larger precursor and secreted by Sertoli cells of fetal testes, that causes regression of the Müllerian duct, which in normal female embryos develops into the uterus, Fallopian tubes, and vagina. Its receptor is a transmembrane serine/threonine kinase. Mutations in the gene for the hormone result in persistence of Müllerian duct derivatives (discovered during surgery) in normal males.

antimutagen any agent (often a purine nucleoside) that can decrease the rate of induced or spontaneous mutation.

antimutator gene any mutant gene that decreases the mutation rate.

antimycin any member of a group of antibiotics produced by *Streptomyces* spp. They associate strongly with mitochondria and block the passage of electrons from cytochrome *b* to cytochrome c_1; as little as 7 pmol antimycin A_1 per gram of mitochondrial protein is effective. They are used experimentally to distinguish between events in the earlier and later parts of the electron-transport chain.

antineoplastic **1** describing any drug or other treatment that prevents or limits the growth of a neoplasm. **2** an antineoplastic agent.

antinuclear factor *or* **antinuclear antibody** any antibody that reacts with a component of the cell nucleus.

antinutrient any natural or synthetic compound that interferes with the absorption of a nutrient. An example is phytic acid, which forms insoluble complexes with zinc, iron, and copper.

antioxidant any substance, often an organic compound, that opposes oxidation or inhibits reactions brought about by dioxygen or peroxides. Usually the antioxidant is effective because it can itself be more easily oxidized than the substance protected. The term is often applied to components that can trap **free radicals**, such as α-tocopherol (*see* **vitamin E**), thereby breaking the chain reaction that normally leads to extensive biological damage. The mechanism by which the free-radical scavenger is discharged of its free radical is not clear, but it is likely that ascorbate and/or glutathione are involved. Compounds such as **di-*tert*-butyl-*p*-cresol** act as antioxidants and are often added to protect labile compounds during storage or incubation. *See also* **quinhydrone**.

antiparallel **1** *(in biochemistry)* (describing of a pair of parallel linear structures, such as two polynucleotide or polypeptide chains, having directional polarity or asymmetry in opposite directions. **2** *(in quantum physics)* (of the spins of a pair of electrons occupying the same atomic or molecular orbital) described by different spin quantum numbers. *Compare* **parallel** (def. 2). **—antiparallelism** *n.*

antiperiplanar *see* **conformation**.

antipernicious anemia factor *former name for* **vitamin B_{12}**.

antiphospholipid antibodies autoantibodies against phospholipids that bind to soluble blood factors involved in activating the coagulation cascade. The resultant hypercoagulability can lead to deep vein thrombosis, pulmonary embolism, or complications in pregnancy. The syndrome can be primary (without evidence of other autoimmune disease); secondary (with evidence of such disease); or catastrophic (extensive and often fatal).

antiport *or* **countertransport** the process of coupled solute translocation in which two solutes equilibrate across an osmotic barrier, the translocation of one solute being coupled to the translocation of the other in the opposite direction. *Compare* **symport**.

antiporter any substance or structural feature, but usually a protein, that promotes the exchange diffusion of two specific substances across a membrane by **antiport**. The convention for denoting such a protein (e.g. a tetracycline-resistance protein) is tetracycline/H^+ antiporter.

antirachitic **1** describing any agent that opposes or prevents the development of **rickets**. **2** any agent with antirachitic properties.

antirachitic factor *or* **antirachitic vitamin** *former term for* any substance with **vitamin D** activity.

antirepressor any gene product that acts to decrease repression by a repressor of gene expression.

antirestriction the process whereby a host bacterium is prevented from inactivating foreign duplex DNA; i.e. the prevention of **restriction**. It is commonly achieved by **host-controlled modification** of the DNA, but in certain cases a specific bacteriophage-coded **antirestriction protein** is produced that directly inhibits the host's **restriction endonuclease**.

antirestriction protein *see* **antirestriction**.

anti-RNA single-stranded RNA complementary to mRNA. *See* **antisense RNA**.

antiscorbutic **1** describing an agent that opposes or prevents the development of **scurvy**. **2** any agent with antiscorbutic properties.

antiscorbutic factor *or* **antiscorbutic vitamin** *former term for* any substance with **vitamin C** activity.

antisense DNA *see* **noncoding strand**.

antisense oligonucleotide an oligoribonucleotide, or an analogue of one, having properties similar to those of **antisense RNA**.

antisense RNA *or* **messenger-RNA-interfering complementary RNA** (*abbr*.: micRNA) an artificial single-stranded RNA molecule complementary in sequence to all or part of a molecule of messenger RNA or of some other specific RNA transcript of a gene. It can therefore hybridize with the specific RNA and so interfere with the latter's actions or reactions. *Compare* **complementary RNA**.

antisense strand *see* **noncoding strand**.

antisepsis the elimination of pathogenic and other microorganisms using chemical or physical methods; the promotion of **asepsis**.

antiseptic **1** of, relating to, or bringing about **antisepsis**. **2** any chemical agent used in antisepsis, especially one that can be safely applied to the skin.

antiserum (*pl.* **antisera** *or* (*esp. US*) **antiserums**) serum that contains a high level of antibodies, usually antibodies against specific antigens.

antisigma factor a protein that interferes with the recognition of initiation sites by the **sigma factor** of DNA-dependent RNA polymerase.

antistasin *the generic name for* a family of potent inhibitors of factor Xa. Antistasins are isolated from leeches, the name having been first given to a 119-amino-acid protein present in salivary gland of the Mexican leech *Haementeria officinalis*; the protein has 20 cysteine residues, all in disulfide bridges (probably characteristic of the family). It appears to present a **bait**-like structure to factor Xa, which cleaves it at Arg^{34}. The 3-D structure has been partially solved, indicating a reactive site in domain I, sequence CRKTC. Antistasins have been considered as possible chemotherapeutic anticoagulants, but have strong metastatic activity. Example, **ghilanten** from the Amazonian leech *H. ghillianii*.

antistreptolysin-O *abbr*.: ASO; antibody formed against streptolysin-O. *See* **streptolysin**.

antisuppressor any mutation that diminishes the effects of a suppressor of gene expression.

antitemplate strand *see* **coding strand**.

antiterminator (*or* **antitermination factor**) a protein that prevents the termination of RNA synthesis. It is found as a regulatory device in, e.g., phage lambda, allowing a terminator to be masked from RNA polymerase so that distal genes can be expressed. Antiterminators are associated with switches from early to middle expression following induction (gene N product), and from early to late expression (gene Q product). The N system is referred to under **nus**. Antitermination is an important mechanism in the reproduction of some bacteriophages, allowing RNA polymerase to read through the terminator to the immediate early genes of the phage, and thus to initiate production of the mature phage, with consequent cell lysis.

antithrombin III *or* **heparin cofactor** *or* **factor Xa inhibitor** a 62 kDa protein inhibitor of serine proteases, normally present in plasma, that reacts with factor IIa (thrombin), and also factors IXa, Xa, XIa and XIIa, to form inert 1:1 stoichiometric complexes. The formation of complexes is slow in the absence of heparin, but very fast in its presence.

antitoxin any antibody to a **toxin** of a (micro)organism that neutralizes the toxin both *in vitro* and *in vivo*.

α_1-antitrypsin *or* **α_1-proteinase inhibitor** a major α_1-globulin, normally present in human plasma, that inhibits many serine proteases, including trypsin, but especially elastase, and is the archetypal **serpin**. Its concentration rises dramatically in response to infection or tissue injury (*compare* **acute-phase protein**). A 51 kDa glycoprotein, its prime physiological role is to inhibit elastase released by neutrophil leukocytes. In humans, its synthesis is controlled by an autosomal allelic system, and over 20 different phenotypes have been classified, one of which is associated with emphysema of early onset; in particular, the so-called Z mutant (Glu → Lys at position 342) is associated with a decreased level of α-antitrypsin in the blood. Smoking tends to cause oxidation of Met^{358}, by increasing hydrogen peroxide formation by lung neutrophils, and this leads to a less active α_1-antitrypsin, and hence reduced inhibition of elastase. Excessive activity of elastase may damage lung tissue, resulting in emphysema. Thus, smoking is associated with emphysema of early onset. Individuals who are homozygous for the Z mutant, and who also smoke, suffer decreased levels of a less active anti-elastase, and have a high probability of developing emphysema. The protein has two chains.

antitussive **1** relieving or suppressing coughing. **2** an agent with antitussive properties.

antivitamin any agent that antagonizes a specific vitamin. Sometimes it is a structural analogue of the vitamin and a competitive inhibitor of the vitamin's action.

antixerophthalmic factor *former term for* any substance with **vitamin A** activity.

antizyme a protein (26 kDa) that is induced by polyamines and binds specifically to form a tight 1:1 complex with **ornithine decarboxylase**. It inactivates the latter, and promotes its destruction by proteasomes.

antoxidant *a variant spelling of* **antioxidant**.

antrin a decapeptide, isolated from rat gastric antrum. It has the sequence Ala-Pro-Ser-Asp-Pro-Arg-Leu-Arg-Gln-Phe, and is identical to residues 25–34 of preprosomatostatin (*see* **somatostatin**).

anucleate *or* **anucleated** lacking a **nucleus**.

anucleolate lacking a **nucleolus**.

***Aor*13HI** a type 2 **restriction endonuclease**; recognition sequence: T↑CCGGA. *Bsp*MII and *Acc*III are **isoschizomers**.

***Aor*51HI** a type 2 **restriction endonuclease**; recognition sequence: AGC↑GCT. *Eco*47III is an **isoschizomer**.

AOX *abbr. for* **alcohol oxidase**.

AP *see* **AP endonuclease**, **AP protein**.

6-APA *abbr. for* 6-aminopenicillanic acid.

Apache freely distributed WWW server software that is very widely used on academic sites.

Apaf *abbr. for* apoptosis protease-activating factor.

Apaf1 *abbr. for* apoptosis protease activating factor 1.

***Apa*I** a type 2 **restriction endonuclease**; recognition sequence: GGGCC↑C. *Eco*47III is an **isoschizomer**.

***Apa*LI** a type 2 **restriction endonuclease**; recognition sequence: G↑TGCAC.

apamin a neurotoxin comprising about 2% of the dry mass of the venom of the honey bee (*Apis mellifera*). It is a highly basic octadecapeptide amide, structure

$$\mathrm{CNCKAPETALCAKKCEEH{-}NH_2},$$

containing two disulfide bridges (between Cys residues 1 and 11, and 3 and 15), and is the smallest neurotoxic peptide known. *Compare* **melittin**.

APC *abbr. for* **1** activated protein C. **2** antigen-presenting cell. **3** anaphase-promoting complex.

APC the human gene for adenomatous polyposis coli protein. The gene is a tumour suppressor, and mutations are associated with familial adenomatous polyposis, Gardner's syndrome, etc. and contribute to colorectal cancer. The protein product has serine phosphorylation, glycosylation, and myristoylation sites. It plays an important role in regulating the stability of free β-**catenin** by binding to it – in a complex with **actin** and **GSK-3** – and targeting it to ubiquitination and degradation by proteasomes during WNT signalling. It also regulates assembly of microtubules and binds directly to kinetochores. Deficient or dysfunctional APC protein (as occurs in many human tumours) permits β-catenin to act as a transcriptional enhancer for certain transcription factors. It is concentrated in the basolateral region of crypt epithelial cells. *See* **WNT family**.

Ape *symbol for* a residue of the α-amino acid L-α-aminovaleric acid, L-2-aminopentanoic acid.

AP endonuclease *abbr. for* apyrimidinic or apurinic nuclease; any of various DNA repair enzymes that make breaks at sites generated by DNA glycosylase. There are three types: (1) **deoxyribonuclease V**; (2) exodeoxynuclease III (endonuclease activity) *see* **deoxyribonuclease** III; and (3) DNA-(apurinic or apyrimidinic site) lyase, EC 4.2.99.18; *other names*: AP lyase; AP endonuclease class I; endodeoxyribonuclease (apurinic or apyrimidinic); deoxyribonuclease (apurinic or apyrimidinic); *Escherichia coli* endonuclease III; phage-T4 UV endonuclease; *Micrococcus luteus* UV endonuclease. They catalyse a reaction in which the C–O–P bond 3′ to the apurinic or apyrimidinic site in DNA is broken by a β-elimination reaction, leaving a 3′-terminal unsaturated sugar and a product with a terminal 5′-phosphate. Endonuclease III from *E. coli* binds a Fe_4S_4 cluster, which is not important for the catalytic activity but is probably involved in the proper positioning of the enzyme along the DNA.

A peptide the octadecapeptide cleaved from the α chains of a fibrinogen molecule when it is converted into fibrin by the proteolytic action of thrombin. *Compare* **B peptide**.

aperture *(in physics)* **1** an opening in an optical or other similar instrument that controls the amount of radiation entering or leaving it. **2** the diameter of the refracting surface of a lens or reflecting surface of a mirror. *See also* **f-number**.

aphidicolin a potent antiviral and antimitotic agent, first isolated as an antibiotic from the fungus *Cephalosporium aphidicola*. It inhibits eukaryotic DNA polymerase.

Api *symbol for* D-apiose.

API *abbr. for* Application Programming Interface; a standard used for ensuring portability of computer software. Familiar APIs are the software development kits such as SDK (or JDK) used by Java programmers, but APIs can also include methods for validation of data transmission, etc.

apical surface the surface of an epithelial cell that faces the lumen.

apigenin 4′,5,7-trihydroxyflavone; the aglycon of **apiin**. It inhibits cyclooxygenase and estrogen synthase. *See* **D-apiose**.



apiin apigenin-7-apiosylglucoside, apioside; the name is derived from *Apium* (celery) from which apiin is isolated. *See also* **apigenin**, **apiose**.

apiose *symbol*: Api; the D isomer, 3-*C*-(hydroxymethyl)-D-*glycero*-aldotetrose is a branched carbon chain sugar that occurs widely in plants either in glycosides or polysaccharides. It is a component of **apiin**.



D-apiose

aplasia incomplete or deficient development of an organ or tissue.

aplastic **1** not showing normal growth or change in structure. **2** relating to or showing **aplasia**.

APLP *abbr. for* amyloid precursor-like protein.

Apm *symbol for* a residue of the α-amino acid α-aminopimelic acid, 2-aminoheptanedioic acid.

A_2pm *or* **Dpm** *symbol for* the di(α-amino acid) α, ε-diaminopimelic acid, 2,6-diaminoheptanedioic acid.

APMSF *p*-amidinophenylmethylsulfonylfluoride; a specific irreversible inhibitor of trypsin-like serine endopeptidases, with greater inhibitory activity than **phenylmethylsulfonylfluoride**.

apo+ *prefix* denoting detached, separate. It is used especially of enzymes and other proteins. For example, apocarboxylase is the protein part of the holoenzyme carboxylase, i.e. it lacks the covalently bound biotin residue(s). Apoferritin is a 450 kDa protein with 24 identical subunits, that combines with ferric hydroxide-phosphate to form **ferritin**. *See also* **apoenzyme**.

Apo-1 *an alternative term for* **Fas**.

Apo(a) *or* **lipoprotein(a)** a plasma glycoprotein serine endopeptidase (EC 3.4.21.–). It is related to **plasminogen**, having 37 repeats of plasminogen **kringle** domains and capable of cleaving **fibrinogen**. Its gene is closely linked to that of plasminogen at 6q21, from which it originated by gene duplication. It is mostly covalently linked (by disulfide bond) to apolipoprotein B-100, when it forms lipoprotein (a). Its plasma concentration is related to the incidence of atherosclerosis.

APOBEC-1 *abbr. for* apoB editing enzyme.

apoB editing enzyme *abbr.*: APOBEC-1; the catalytic subunit of the complex that converts the cytosine of codon 2153 (CAA for glutamine) in **apolipoprotein B** (apoB) pre-mRNA into uracil (UAA for termination) thus converting the mRNA for B-100 into one for B-48 in nuclei of human enterocytes. A locus at 12p13.1-p13.2 encodes 229 amino acids, which incorporate a deaminase domain that contains a zinc atom and a glutamate residue that are essential for activity. Complex formation requires APOBEC-1 complementation factor, which contains three RNA-recognition motifs. A cluster of APOBEC-1-related sequences has been reported on chromosome 22.

apocrine 1 describing a type of secretion that entails loss of part of the cytoplasm of the secretory cell. 2 describing a gland made up of such cells. *Compare* **eccrine**, **holocrine**, **merocrine**.

apoenzyme the protein part of an enzyme that forms a catalytically active enzyme (holoenzyme) when combined with an activator, a coenzyme, or a prosthetic group. It determines the specificity of the catalytic system.

***APOE* polymorphism** polymorphism at the gene for apolipoprotein E (*APOE*). There are three major alleles at the *APOE* locus, *APOE*ε2*, *APOE*ε3* and *APOE*ε4*, with a prevalence in the population of 6%, 78%, and 16% respectively. *APOE*ε4* increases the risk of developing Alzheimer's disease. Individuals homozygous for *APOE*ε4* are more likely to be affected and at an earlier age than heterozygotes, who in turn are more likely to develop the disorder than those who do not have this allele.

apoferritin *see* **ferritin**.

apolar 1 lacking poles, especially of nerve cells. 2 **nonpolar**.

apolar interaction any of the entropy-driven interactions between nonpolar parts of molecules when in polar solvents. It is important in maintaining the structure of protein molecules in polar solvents, in antigen–antibody interactions, in virus– protein and enzyme–subunit aggregation and disaggregation, and in determining enzyme specificity.

apolipophorin a protein component of **lipophorin**. This is an exchangeable apolipoprotein, found in many insect species, that functions in transport of diacylglycerol (DAG) from the fat body lipid storage depot to flight muscles in the adult life stage. An equilibrum is maintained between a soluble monomer and a bound lipoprotein form. Apolipophorin-III associates with lipophorin during lipid loading, until each particle contains 9 or 14 molecules of apolipophorin-III.

apolipoprotein the protein component of any lipoprotein, but especially of plasma lipoproteins. The latter are designated by the abbreviation 'Apo', e.g. ApoA (for apolipoprotein A), ApoB, etc., and are subdivided into subtypes, e.g. ApoA-I for apolipoprotein A, subtype I. See following entries for individual types of apolipoprotein.

apolipoprotein A-I *abbr.*: ApoA-I; the major protein of plasma **high-density lipoprotein** (HDL), also found in chylomicrons. It is synthesized in the liver and small intestine, and participates in the reverse transport of cholesterol from tissues to the liver by promoting cholesterol efflux from tissues; it acts as a cofactor for **lecithin–cholesterol acyltransferase**. Deficiency of ApoA-I is associated with **Tangier disease**.

apolipoprotein A-II *abbr.*: ApoA-II; an apolipoprotein associated with **high-density lipoprotein**, which it stabilizes. It is a homodimer (disulfide linked).

apolipoprotein A-IV *abbr.*: ApoA-IV; an apolipoprotein that is a major component of **high-density lipoprotein** and chylomicrons. It is involved in the catabolism of chylomicrons and very-low-density lipoprotein, being required for efficient activation of **lipoprotein lipase** by apolipoprotein C-II. It is a potent activator of **lecithin–cholesterol acyltransferase**.

apolipoprotein B *abbr.*: ApoB; a major protein constituent of chylomicrons, very-low-density lipoprotein and low-density lipoprotein. It exists in two forms: B-100 (amino acids 28–4563 of the sequence) and B-48 (amino acids 28–2179); the latter is of intestinal origin, and derived from editing of mRNA to form an internal stop codon. Excessive plasma levels occur in familial **hypercholesterolemia**.

apolipoprotein C-I *abbr.*: ApoC-I; a component of chylomicrons and very-low-density lipoprotein (VLDL), synthesized mainly in liver. It modulates the interaction of apolipoprotein E with β-migrating VLDL, and inhibits binding of β-VLDL to low-density lipoprotein receptor-related protein.

apolipoprotein C-II *abbr.*: ApoC-II; a component of very-low-density lipoprotein (VLDL), and an activator of several triacylglycerol lipases. It has a reversible association with plasma chylomicrons, VLDL and high-density lipoprotein. Deficiency results in hypertriglyceridemia, xanthomas, and increased risk of pancreatitis and early atherosclerosis (hyperlipoproteinemia, type IB).

apolipoprotein C-III *abbr.*: ApoC-III; an apolipoprotein that constitutes 50% of the protein fraction of very-low-density lipoprotein. It binds to sugar and sialic-acid residues, and inhibits lipoprotein and hepatic lipases.

apolipoprotein D *abbr.*: ApoD; an apolipoprotein that occurs in a macromolecular complex with **lecithin–cholesterol acyltransferase** and in high-density lipoprotein. It is a **lipocalin**, probably involved in the transport and binding of bilin. The homodimer shows wide tissue distribution.

apolipoprotein E *abbr.*: ApoE; an apolipoprotein that constitutes 10–20% of very-low-density lipoprotein. It mediates binding, internalization and catabolism of lipoprotein particles, and is a ligand for the low-density lipoprotein (ApoB/E) receptor and for the ApoE receptor (chylomicron remnant) of hepatic tissues. It is present in brain, and may have a role in cholesterol transport. *O*-glycoside and sialic-acid residues occur, but it is de-sialylated in plasma. It has nine allelic variants, two of which are associated with hyperlipoproteinemia type III. The structure contains a heparin-binding motif.

apolipoprotein H *abbr.*: ApoH; *other names*: β_2-glycoprotein II precursor; APC inhibitor (*see* **activated protein C**). An apolipoprotein that binds to anions, such as heparin, and phospholipids. It may prevent activation of the intrinsic blood coagulation cascade by binding to phospholipids on the surface of damaged cells. *See also* **amyloid A protein**.

apolipoprotein J *abbr*: Apo J; *other name*: clusterin; an apolipoprotein associated with high-density lipoprotein (HDL) particles and produced in many tissues. A locus at 8p21 encodes a precursor, which is cleaved to form a two-chain disulfide-bonded glycoprotein in which ApoJα contains residues 1–205, and ApoJβ contains residues 206–427. Both contain amphipathic sequence repeats. ApoJ binds numerous proteins and seems to be cytoprotective.

apolipoprotein receptor *see* **LDL receptor**, **VLDL receptor**.

Apollon *or* **BRUCE** (*abbr. for* baculovirus repeat-containing ubiquitin-conjugating enzyme); an **IAP** (4845 amino acids) that is associated with membranes of the Golgi apparatus and vesicular system. It is expressed in most adult human tissues, and in cancer cells from various tissues including brain.

apomorphine 6a*β*-aporphine-10,11-diol; 5,6,6a,7-tetrahydro-6-methyl-4*H*-dibenzo[*de*,*g*]quinoline-10,11-diol; a synthetic opiate. The (*R*)-enantiomer is a potent dopamine receptor agonist, noted for its powerful emetic effects.



apomucin the polypeptide part of a **mucin**.

apopain an apoptosis-specific cysteine protease of mammalian cells. It targets poly(ADP-ribose) polymerase, DNA-dependent protein kinase, sterol regulatory element-binding protein, and huntingtin.

apoplast the nonliving part of plant tissue, external to the plasmalemma and composed of the cell walls, the intercellular spaces, and the lumen of dead structures such as xylem cells.

apoprotein the protein part of a **conjugated protein**.

apoptosis *or* **programmed cell death** an intracellular controlled process characterized by cell shrinkage and detachment from the extracellular scaffolding, chromatin condensation and DNA fragmentation by activation of a calcium-dependent endonuclease, blebbing of plasma membrane, activation of **caspases**, and collapse of the cell into small membrane-enclosed fragments (called **apoptotic bodies**) that are removed by phagocytosis. There is no release of cell constituents and no inflammatory response. A cascade of caspases (which cleave at specific aspartic residues hence the name) is involved. In this cascade, caspases cleave procaspases to form additional caspases. Some of the caspases thus formed cleave other proteins, including deoxyribonucleases. Largely a phenomenon of multicellular organisms, apoptosis occurs under various physiological (e.g. during normal embryonal development, cell turnover) and pathological (nonlethal stress) conditions. It is distinguished from necrosis, in which the cell swells in response to lethal stress, bursts open and releases its contents into the surroundings, and elicits an inflammatory response. –**apoptotic** *adj.*; **apoptotically** *adv.* [From **apo+** + Greek *ptosis*, falling.]

apoptosis antigen 1 *an alternative term for* **Fas**.

apoptosis inducing factor *abbr.*: AIF; a flavoprotein of the mitochondrial intermembrane space that, when released by cellular stress, translocates to the nucleus and induces chromatinolysis and apoptosis.

apoptosis protease-activating factor 1 *abbr.*: Apaf-1; a mammalian cytosolic monomeric protein (≈130 kDa) involved in triggering **apoptosis**. It oligomerizes on binding cytochrome *c* (released from mitochondria) and binds procaspase 9, which becomes autocatalytically active and promotes apoptosis.

apoptosome a large complex of proteins that induces **apoptosis**. Of molecular mass ≈700–1400 kDa, it consists of several copies each of: cytosolic apoptosis protease-activating factor-1 (Apaf-1); cytochrome *c* (released from mitochondria); and cytosolic procaspase-9, which thereby becomes autocatalytically activated.

apoptotic bodies *see* **apoptosis**.

aporepressor the protein component of a complex that can act to inhibit gene expression. *See also* **repressor**.

APP *abbr. for* precursor protein.

apparent describing a physical quantity, especially an association constant, dissociation constant, equilibrium constant, etc., that has been determined under particular experimental conditions and hence is not the true (i.e. thermodynamic) constant. *See* **equilibrium constant**.

apparent exchangeable mass a term used in tracer kinetics in whole animals for a mass obtained by dividing the quantity of administered radioactivity that is retained by the specific activity of the tracer in the (blood) plasma. It equals the total exchangeable mass when the specific activities are equal throughout the system. *Compare* **compartment**.

apparent molecular weight *former name for* **apparent relative molecular mass**.

apparent relative molecular mass **relative molecular mass** that has been determined by a method that does not make allowance for any nonideality of the system.

appetite peptide *or* **orexigenic peptide** any of a group of peptides, such as neuropeptide Y, that enhance appetite for food.

apple domains sequences of ~90 amino-acid residues stabilized by three highly-conserved disulfide bonds, linking the first and sixth, second and fifth, and third and fourth cysteine residues (this cross-linking pattern can be drawn in the shape of an apple, hence the name). They may occur in multiple tandem repeats: e.g., four copies are present in human kallikrein and in human coagulation factor XI.



apple domains

applet a software application, written in Java, loaded from a server via HTML pages. Applets are executed on the local computer.

applicator any device or instrument, such as a comb, rod, spatula, or tube, for applying samples in a reproducible manner to a small defined area, e.g. in chromatography, or for applying something to a particular part of the body.

approach to (sedimentation) equilibrium method *or* **Archibald method** a method for determining the relative molecular masses of (macro)molecules by sedimentation in an ultracentrifuge, by measuring the depletion of the macromolecules from the meniscus and their accumulation at the cell bottom. Its advantage is that only very short periods of sedimentation are required. [After William James Archibald (1912–).]

AP protein *abbr. for* activator protein, one of two **transcription factors**; AP1, a product of c-*jun* (*see* **JUN**), interacts with Fos (product of c-*fos*) to form a dimer. It harbours two functional domains, one responsible for DNA binding and one for binding to Fos, and includes a leucine zipper. AP2 interacts with inducible viral and cellular enhancer elements to stimulate transcription of selected genes. It contains the consensus binding sequence CCCAGGC and a helix-span-helix motif.

A_2pr *or* **Dpr** *symbol for* a residue of the *α*,*β*-diamino acid L-*α*,*β*-diaminopropionic acid; L-2,3-diaminopropanoic acid.

aprotic describing a substance, especially a solvent, that is unable to act as a proton acceptor or donor.

aprotinin a proteinase inhibitor derived from animal tissues. It is a basic polypeptide of known sequence of 58 amino-acid residues (≈6.5 kDa) that exists as a homodimer. It is stable in acid or neutral media and at high temperature, and it inhibits kallikrein, trypsin, chymotrypsin, plasmin, and, to a lesser extent, papain. *See also* **Trasylol**.

APRT *abbr. for* adenine phosphoribosyltransferase.

APS *abbr. for* adenosine 5′-phosphosulfate.

APT *abbr. for* alum-precipitated toxoid.

aptamer a short strand of DNA that binds a target protein sequence. Decoy aptamers may activate or inactivate genes by inactivating DNA-binding proteins, such as transcription factors. –**aptameric** *adj.*

aptitude *(in microbiology)* the specific physiological state of a **lysogenic bacterium** that enables it, upon induction, to react so as to produce infectious bacteriophage particles.

apud *or* **APUD** *abbr. for* amine precursor uptake and decarboxylation; designating any of a series of cells that produce peptides and/or amines active as hormones or neurotransmitters, share a spectrum of cytochemical qualities, and appear in many cases to have a common embryological origin. They are thought to include the A, B, and D cells of the endocrine pancreas, the C cells of the thyroid, and the various hormone-producing cells of the pituitary and the gut.

apudoma any tumour of an **apud** cell, e.g. a gastrinoma, glucagonoma, insulinoma, or VIPoma.

apurinic acid a DNA derivative in which all the purine bases have been removed by selective hydrolysis, leaving the pyrimidine–deoxyribose bonds and the phosphodiester bonds of the backbone intact. It results from the gentle acid hydrolysis of DNA at pH 3.0.

apurinic endonuclease *see* **AP endonuclease**.

apyrase EC 3.6.1.5; *other names*: ATP-diphosphatase; adenosine diphosphatase (*abbr*.: ADPase); a Ca^{2+}-requiring enzyme that catalyses the hydrolysis of ATP to AMP and 2 orthophosphate. It also hydrolyses other nucleotides, especially ADP to AMP and orthophosphate. It was originally identified in plants, especially potatoes, but enzymes of this type have also been found in animals, e.g. as a surface enzyme on lymphoid cells identical to CD39, and as a secreted enzyme of the yellow-fever mosquito, *Aedes aegypti*. It is used in platelet incubations to destroy ADP.

apyrimidinic acid a DNA derivative from which the pyrimidine bases have been removed chemically, leaving the purine–deoxyribose bonds and the phosphodiester bonds of the backbone intact.

apyrimidinic endonuclease *see* **AP endonuclease**.

aq *(in chemistry) abbr. for* aqueous.

aqua+ *comb. form* **1** denoting acting on or reacting with water. **2** denoting presence of water as a neutral ligand in a coordination entity, e.g. aquacobalamin. The number of water molecules per entity is indicated by an approximate multiplying prefix, e.g. hexaquachromium trichloride.

aquacide a substance that when added to a mixture removes water molecules, usually by forming a compound with the elements of water. —**aquacidal** *adj.*

aquaflavin *or* **uroflavin** a fluorescent alloxazine derivative of riboflavin, present in the urine of most animals.

aqueous 1 of, having the characteristics of, or relating to water. **2** dissolved in or mixed with water. **3** *or* **aqueous humour** the fluid occupying the space between the crystalline lens and the cornea of the eye.

aquo+ *comb. form* **1** containing one or more water molecules in a coordination complex. **2** *(in chemical nomenclature)* derived from water.

aquo-ion a complex ion containing one or more water molecules held by coordination.

Ar *symbol for* **1** argon. **2** aryl.

Ara *symbol for* arabinose.

ara a plant gene related to ***ras***.

araBAD an operon characterized in *Escherichia coli* and encoding L-ribulokinase, L-arabinose isomerase, and L-ribulose 5-phosphate 4-epimerase, three of the enzymes that metabolize arabinose. *See also* ***araC***.

Arabidopsis thaliana a small Cruciferous plant (common wall cress) widely used in plant genetic research because of its small genome and very short generation time.

arabin+ *a variant (before a vowel) of* **arabino+**.

arabinan a branched homopolymer of L-arabinose found in plant pectins.

arabinaric acid *see* **aldaric acid**.

arabino+ *or (before a vowel)* **arabin+** *comb. form* indicating arabinose.

arabino- *prefix (in chemical nomenclature)* indicating a chemical compound containing a particular configuration of a set of three (usually) contiguous >CHOH groups, as in the acyclic form of D- or L-arabinose. *See* **monosaccharide**.

arabinofuranosylcytosine cytosine arabinoside; *see* **cytarabine**.

arabinogalactan any member of a subgroup of plant hemicelluloses that contain arabinose and galactose and are particularly abundant in larch.

arabinogalactan proteins *abbr*.: AGP; one of the four major classes of **plant cell-wall proteins**. They contain ≈95% of their mass as carbohydrate (highly branched galactan chains decorated with arabinose moieties). They are present in the Golgi apparatus, plasma membrane, and cell wall. Enriched in proline/hydroxyproline, alanine, and serine/threonine, they are a diverse group related only by the glycan structure.

arabinonucleoside the 1-*β*-D-arabino-*N*-furanoside of a purine or pyrimidine base. It is a structural analogue of a **riboside**.

arabinose *arabino*-pentose; a monosaccharide. L-Arabinose occurs free, e.g. in the heartwood of many conifers, and in the combined state, in both furanose and pyranose forms, as a constituent of various plant hemicelluloses, bacterial polysaccharides, etc. D-Arabinose occurs to some extent in plant glycosides and is a constituent of the **arabinonucleosides**.



β-D-arabinose

D-arabinose isomerase EC 5.3.1.3; *systematic name*: D-arabinose ketol-isomerase. An enzyme that catalyses the reaction:

D-arabinose = D-ribulose.

See also **L-arabinose isomerase**.

L-arabinose isomerase EC 5.3.1.4; *systematic name*: L-arabinose ketol-isomerase. An enzyme that catalyses the reaction:

L-arabinose = L-ribulose.

It initiates the metabolism of L-arabinose. *See also* ***araBAD***, **D-arabinose isomerase**.

arabinose-5-phosphate isomerase EC 5.3.1.13; *systematic name*: D-arabinose-5-phosphate ketol-isomerase. An enzyme that catalyses the reaction:

D-arabinose 5-phosphate = D-ribulose 5-phosphate.

arabinoside any glycoside derived from arabinose.

arabinoxylan any of various neutral polysaccharides that occur in association with acidic polysaccharides in cereal gums. They consist of a chain of (1→4)-linked *β*-D-xylan units with single *α*-L-arabinofuranosyl groups in (1→3) linkage.

arabitol *or* **arabinitol** *arabino*-pentitol; the pentitol formally derived by reduction of the aldehyde group of arabinose or lyxose. The D enantiomer is present in lichens and mushrooms.

ara-C *abbr. for* arabinosylfuranosylcytosine.

araC the gene for the araC protein, which acts as a regulator of expression of the *araBAD* operon and of *araC* itself. AraC acts as both a repressor (when intracellular arabinose levels are low), binding to *araO* operator sites, and an activator (in the presence of arabinose), when bound to the *araI* site, but only in the presence of cyclic AMP–CRP complex. It is a typical **helix-turn-helix** DNA-binding regulatory protein.

arachain an unclassified proteinase obtained from the peanut, *Arachis hypogaea*.

arachidic acid *the trivial name for* eicosanoic acid; CH_3–$[CH_2]_{18}$–COOH; a constituent of arachis oil (from the peanut, *Arachis hypogaea*) and other oils. *See also* **arachidoyl**.

arachidonate 5-lipoxygenase EC 1.13.11.34; *other names*: 5-lipoxygenase; leukotriene-A$_4$ synthase; a **lipoxygenase** (def. 2) enzyme that catalyses the reaction of arachidonate with dioxygen to form (6*E*,8*Z*,11*Z*,14*Z*)-(5*S*)-5-hydroperoxyeicosa-6,8,11,14-tetraenoate. Iron is a cofactor.

arachidonate 12-lipoxygenase EC 1.13.11.31; *other name*: 12-lipoxygenase; a **lipoxygenase** (def. 2) enzyme that catalyses the reaction of arachidonate with dioxygen to form (5*Z*,8*Z*,10*E*,14*Z*)-(12*S*)-12-hydroperoxyeicosa-5,8,10,14-tetraenoate. Iron is a cofactor.

arachidonate 15-lipoxygenase EC 1.13.11.33; *other names*: arachidonate *ω*-6 lipoxygenase; 6-lipoxygenase; a **lipoxygenase** (def. 2) enzyme that catalyses the reaction of arachidonate with dioxygen to form (5*Z*,8*Z*,11*Z*,13*E*)-(15*S*)-15-hydroperoxyeicosa-5,8,11,13-tetraenoate. Iron is a cofactor.

arachidonic acid *see* **eicosatetraenoic acid**.

arachidonoyl *symbol*: Δ_4Ach; *the trivial name for* (*all-Z*)-eicosa-5,8,11,14-tetraenoyl; CH_3–$[CH_2]_3$–$[CH_2$–$CH{=}CH]_4$– $[CH_2]_3$–CO– (*all-Z* isomer); the acyl group derived from arachidonic (i.e.(*all-Z*)-eicosa-5,8,11,14-tetraenoic) acid, a polyunsaturated, unbranched, acyclic, aliphatic acid. It occurs naturally in membrane phospholipids, and is a biochemical precursor of **prostaglandins** and **leukotrienes**. It is also present in mosses, algae, and ferns, but not in higher plants. Distinguish from **arachidonyl** and **arachidoyl**.

arachidonyl *the trivial name for* the alkyl group, $CH_3–[CH_2]_3–[CH_2–CH=CH]_4–[CH_2]_3–CH_2–$, derived from the alkenol analogue of arachidonic acid. Distinguish from **arachidonoyl**.

2-arachidonylglycerol an endocannabinoid, chemically similar to **anandamide**.

arachidoyl *or (formerly)* **arachidyl** *or* **arachyl** *symbol*: Ach; *the trivial name for* eicosanoyl; $CH_3–[CH_2]_{18}–CO–$; the acyl group derived from arachidic (*or* eicosanoic *or (formerly)* arachic) acid, a saturated, unbranched, acyclic, aliphatic acid. It occurs naturally as triarachin in certain seeds, oils, and butter fat. Arachidyl is now the name for the alkyl group, $CH_3–[CH_2]_{18}–CH_2–$. Distinguish from **arachidonyl**.

arachidyl *the trivial name for* the alkyl group, $CH_3–[CH_2]_{18}– CH_2–$, the alkanol analogue of arachidic acid. *See also* **arachidoyl**.

arachin the major protein of the groundnut, *Arachis hypogaea*, comprising a 345 kDa globulin with 12 subunits. Not all groundnuts contain the same arachin; there exist at least two forms, designated A and B, having similar amino-acid compositions and general properties, but differing in their subunit composition. *See also* **conarachin**.

arbovirus *abbr. for* arthropod-borne virus (a term formerly used for **togavirus**).

arc a continuous curved line, as part of a circle or ellipse; e.g. the line of antigen–antibody precipitate obtained in **immunodiffusion** or **immunoelectrophoresis**.

ARC *abbr. for* ADP-ribosyl cyclase.

Archaea one of three primary kingdoms of cells, together with **Eukarya** and **Bacteria** (formerly **Eubacteria**), defined when cells are classified on the basis of rRNA sequence homologies. Archaea include all methanogens, extreme halophiles and most extreme thermophiles. Representative genera are: *Halobacterium*, *Methanobacterium*, *Sulfolobus*, *Thermoplasma*, and *Purodictium* (growth optimum = 105°C); about 40 others are known. **—archaeal** *adj.*

Archaebacteria *former name for* **Archaea**.

Archibald method *see* **approach to (sedimentation) equilibrium method**.

Archimedes' principle the principle that when a body is partly or wholly immersed in a fluid there is an apparent loss of weight equal to the weight of the fluid displaced. [After Archimedes of Syracuse (?287–212 BC), Greek philosopher and applied mathematician.]

architectural gene a gene that determines the site of an enzyme within a cell.

A-region the presumptive initial oxidation site of a carcinogenic polycyclic aromatic hydrocarbon, on the terminal ring of the **bay region**, in the metabolic pathway leading to carcinogenesis (corresponding to what has sometimes been called the M-region). *Compare* **B-region**, **K-region**, **L-region**.

arenavirus any of a group of RNA viruses consisting of enveloped pleomorphic particles of 80–120 nm with helical nucleocapsids. The group includes Lassa virus and other viruses that spread to humans from rodents.

arene any monocyclic or polycyclic aromatic hydrocarbon.

arene oxide any epoxide formed by the addition of an atom of oxygen across any double bond of an **arene**.

ARF *abbr. for* ADP-ribosylation factor; a small monomeric highly conserved cytosolic **GTPase** that, when bound to GTP, becomes myristoylated and binds to the membranes of cells. It was originally discovered as a factor required for cholera toxin to ADP-ribosylate G_s, hence its name. It is a member of the **RAS** superfamily. Functions of ARF include regulation of membrane traffic in both endocytic and exocytic pathways, maintenance of organelle integrity, assembly of coat proteins (*see* **coatomer**), and activation of phospholipase D. *See* **phospholipase**.

Arg *symbol for* a residue of the α-amino acid L-arginine (alternative to R).

argentaffin cell a type of cell of the **apud** class, characterized by taking up silver stains with high affinity, without the addition of reducing agent. [Named from Latin *argentum*, silver, and affinity.]

argentation chromatography any method of chromatography in which an adsorbent impregnated with silver nitrate is used to separate lipid classes according to the degree and geometry of their saturation. The technique may be used with either thin-layer chromatography or column chromatography, or in conjunction with gas–liquid chromatography.

arginase *abbr. (in clinical biochemistry)*: ARS; *recommended name for* EC 3.5.3.1; *other names*: arginine amidinase; *systematic name*: L-arginine amidinohydrolase. An enzyme that catalyses the hydrolysis of L-arginine to L-ornithine and urea; it also acts on α-*N*-substituted L-arginines and canavanine. It is a key enzyme in the **ornithine–urea cycle**, occurring in high concentrations in the liver of ureotelic vertebrates and being absent or nearly so from the liver of uricotelic species. It has a very wide species distribution. In humans the liver (and erythrocyte) isozyme is a cytosolic homotrimer containing an $Mn^{2+}–Mn^{2+}$ cluster in each subunit. Over a dozen mutations in the locus at 6q23 result in the rare autosomal recessive disorder argininemia, which is associated with hyperammonemia, progressive psychomotor and growth impairment, and spasticity. The renal isozyme shows some 57% sequence homology and occurs in mitochondrial matrix.

argininate **1** arginine anion; $H_2N–C(=NH)–NH–[CH_2]_3–CH(NH_2)–COO^-$. **2** any salt containing the arginine anion. **3** any ester of arginine.

arginine *trivial name for* N^5-amidino-ornithine; α-amino-δ-guanidinovaleric acid; 2-amino-5-guanidinopentanoic acid; $H_2N–C(=NH)–NH–[CH_2]_3–CH(NH_2)–COOH$; a chiral α-amino acid. L-Arginine *(symbol*: R *or* Arg), (*S*)-2-amino-5-guanidinopentanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: AGA (not in mitochondria of fruit fly or mammals) or AGG (not in mitochondria of mammals); CGA, CGC, CGG, or CGU. It is an essential dietary amino acid in rats and probably in young humans, and is glucogenic in mammals. D-Arginine (*symbol*: D-Arg *or* DArg), (*R*)-2-amino-5-guanidinopentanoic acid, is not known to occur naturally.



L-arginine

arginine (base) the ionic form of an arginine residue when the guanidino group is unprotonated.

arginine carboxypeptidase *see* **lysine(arginine) carboxypeptidase**.

arginine kinase EC 2.7.3.3; an enzyme that catalyses a reaction between ATP and L-arginine to form ADP and N^{ω}-phospho-L-arginine. The latter compound may play a role in invertebrate muscle analogous to that of **creatine phosphate** in vertebrate muscle.

arginine phosphate *former name (not recommended) for* **phosphoarginine**.

arginine–urea cycle *see* **ornithine–urea cycle**.

[8-arginine]vasopressin *or (less correctly)* **arginine vasopressin** *abbr*.: AVP *or* [Arg^8]vasopressin; the molecular form of **vasopressin** in which the variable eighth position in its amino-acid sequence is occupied by an arginine residue. This is the form present in humans and most other mammals.

arginine vasotocin *or* **[Arg^3]oxytocin** a pituitary peptide found in nonmammalian vertebrates with activity resembling both oxytocin and vasopressin.

argininium **1** argininium(1+); the monocation of arginine. In theory, the term denotes any ion, or mixture of ions, formed from arginine, and having a net charge of plus one, although in practice the predominant species is generally $H_2N–C(=NH_2^+)–NH–[CH_2]_3–CH(NH_3^+)–COO^-$. **2** *the systematic name for* argininium(2+); the dication of arginine.

arginino **1** N^2-arginino; the alkylamino group, $H_2N–C(=NH)–NH–[CH_2]_3–CH(COOH)–NH–$, derived from arginine by loss of a hydrogen atom from its α-amino group. **2** N^{ω}-arginino; the alkylguanidino group, $HOOC–CH(NH_2)–[CH_2]_3–NH– C(=NH)–NH–$, derived from arginine by loss of a hydrogen atom from its ω-amino group.

argininosuccinase EC 4.3.2.1; *systematic name*: *N*-(L-argininosuccinate) arginine lyase; *recommended name*: argininosuccinate lyase.

An enzyme of the **ornithine–urea cycle** that catalyses the hydrolysis of *N*-(L-arginino)succinate to fumarate and L-arginine. The human enzyme is a homotetramer of hepatocyte cytosol with very strong similarity to bird and reptile δ-crystallin. Severe deficiency results from any of over a dozen mutations in a locus at 7cen-p21, and produces hyperammonemia and argininosuccinic aciduria.

argininosuccinate 2-(N^{ω}-arginino)succinate; L-argininosuccinate is an intermediate in the **ornithine–urea cycle**, where it is synthesized by the enzymic condensation of L-citrulline with L-aspartate. *See* **arginosuccinate synthase**.



argininosuccinate synthase EC 6.3.4.5; *systematic name*: L-citrulline:L-aspartate ligase (AMP-forming); *other names*: argininosuccinate synthetase; citrulline–aspartate ligase. An enzyme of the **ornithine–urea cycle** that catalyses a reaction between ATP, L-citrulline, and L-aspartate to form L-argininosuccinate with release of AMP and pyrophosphate. The human enzyme is a cytosolic homotetramer expressed mainly in hepatocytes. More than 20 mutations in a locus at 9q34 result in enzyme deficiency with consequent hypercitrullinemia and hyperammonemia.

arginyl the acyl group, $H_2N–C(=NH)–NH–[CH_2]_3–CH(NH_2)–CO–$, derived from arginine.

Argonaute any of a family of proteins that are important in diverse post-transcriptional RNA-mediated gene-silencing systems in plants, *Drosophila*, and fission yeast. They are components of **RISC**, are highly conserved in plants and animals, and have been implicated in methylation of histones and DNA.

argon detector a sensitive detector used in gas chromatography that depends on the unique ionization properties of argon whereby its long-lived metastable excited atoms can transfer their energy of excitation by collision to other gas molecules of lower excitation potential. Thus argon can be used as the chromatographic carrier gas, the detector being an ionization chamber containing a source of ionizing radiation. Detectable changes of the level of ionization occur when the argon issuing from the column has another gas mixed with it. The detector was invented by James E. Lovelock. Its great advantage is that it does not depend on the chemical nature of the substances being separated.

[Arg^8]vasopressin *abbr. for* [8-arginine]vasopressin.

ARH protein a protein that is mutated in autosomal recessive hypercholesterolemia with normal low-density lipoprotein (LDL) receptors. The gene locus, at 1p35, encodes 308 amino acids. This product includes a 170-residue sequence homologous to the phosphotyrosine-binding domain of many adaptor proteins, and binds a cytoplasmic domain of several cell-surface tyrosine kinase receptors.

ARID protein *abbr. for* AT-rich interaction domain protein; any of various proteins containing a domain that binds AT-rich regions in DNA. ARID proteins are involved in embryonic development, cell-lineage gene regulation, and cell-cycle control. The ARID sequence is ≈80 residues long.

arithmetic mean *see* **mean**.

arm a base-paired segment of the clover-leaf model of transfer RNA. There are several such arms: **amino-acid arm**, **anticodon arm**, **dihydrouridine arm**, **extra arm**, and **TψC arm**.

armadillo any of a family of proteins that includes β-catenin, which forms a multimeric complex with presenilins. These proteins contain an imperfect repeat of ≈42 residues, which forms three alpha helices. *See* **catenin**.

ARNT *abbr. for* aryl-hydrocarbon receptor nuclear translocator; *other name*: dioxin receptor; a protein that mediates translocation of the **Ah receptor** from the cytoplasm to the nucleus after ligand has been bound.

A-RNA *abbr. for* A form of RNA.

aro1 a fungal gene for aromatic amino-acid biosynthesis. It encodes a multifunctional protein for, e.g., **3-dehydroquinate synthase**, 3-dehydroquinase, **shikimate 5-dehydrogenase**, **shikimate kinase**, **EPSP synthase**.

aroA–H, *aroL Escherichia coli* genes for **chorismate** synthesis.

arogenate *or* **pretyrosine** 3-(1′-carboxylato-4′-hydroxy-2′,5′-cyclohexadienyl)alanine; an intermediate in phenylalanine and tyrosine biosynthesis in *Euglena gracilis* and some other microorganisms, and in plants. It is formed by transamination of **prephenate** and is subsequently decarboxylated and converted to tyrosine, or converted to phenylalanine by dehydration and decarboxylation.



aromatase *or* **P450 arom** *or* **CYP19** an enzyme complex responsible for converting testosterone to estradiol. It catalyses complete oxidation and removal of the angular methyl group at C19, dehydrogenation and isomerization of the A ring, and reduction of the 3α position. It occurs in estrogen-producing cells in ovarian granulosa tissue, testes, placenta, brain (hippocampus, hypothalamus, and amygdala), and adipocytes. It consists of cytochrome P450 aromatase (CYP19) and a ubiquitous flavoprotein NADPH-cytochrome P450 reductase, which contains FAD and FMN and binds the substrate. Mutations in the gene for CYP19 lead to aromatase deficiency, characterized by female pseudohermaphroditism.

aromatic describing any organic compound characterized by one or more planar rings, each of which contains (usually) three conjugated double bonds and $(4n + 2)$ delocalized pi-electrons, where n is a small integer. They undergo substitution reactions more readily than addition reactions. The simplest member of the class is benzene. The term was originally used to distinguish fragrant compounds from **aliphatic** compounds. —**aromaticity** *n.*

aromatic amino acid any amino acid containing an aromatic ring. In proteins, these are phenylalanine, tryptophan, and tyrosine.

aromatic-L-amino acid decarboxylase *abbr.*: AADC; EC 4.1.1.28; *systematic name*: aromatic-L-amino-acid carboxy-lyase; *other names*: dopa decarboxylase; tryptophan decarboxylase; hydroxytryptophan decarboxylase. An enzyme that catalyses the decarboxylation of L-tryptophan to tryptamine, and acts on 5-hydroxy-L-tryptophan to yield 5-hydroxytryptamine, and on dihydroxy-L-phenylalanine (dopa) to yield **dopamine**; pyridoxal 5′-phosphate is a coenzyme. AADC is present in brain, liver, and other tissues. Several mutations in a locus at 7p12.1-p12.3 lead to enzyme deficiency. The human enzyme is a homodimer, and structurally similar to certain other eukaryotic decarboxylases.

aromatic amino acid hydroxylase any of three monooxygenase enzymes: phenylalanine 4-monooxygenase (EC 1.14.16.1); tyrosine 3-monooxygenase (EC 1.14.16.2); and tryptophan 5-monooxygenase (EC 1.14.16.4). All require tetrahydrobiopterin as coenzyme (*see* **biopterin**), and are homologous in amino acid sequence and gene structure. In each the N-terminal region binds the substrate, while the C-terminal region binds the coenzyme and catalyses the monooxygenation.

Arp *abbr. for* actin-related protein; either of two proteins, Arp2 and Arp3, that with five other polypeptides form a complex (the **Arp2/3 complex**) that mediates initiation of a new actin filament at an actin branchpoint. The complex is necessary for the formation of actin-filament networks. It is activated by binding to **WASP** before binding to the side of an existing actin filament. It also binds **cortactin**.

ARP$_a$ *abbr. for* assimilatory regulatory protein a, i.e. ferredoxin-thioredoxin reductase.

ARP$_b$ *abbr. for* assimilatory regulatory protein b, i.e. **thioredoxin**.

arrestin *or* **S antigen** any of a protein family that includes the Ca^{2+}-binding protein of the retinal rod outer segments. It binds to photoactivated-phosphorylated rhodopsin, thereby apparently preventing the transducin-mediated activation of phosphodiesterase. It has been implicated in autoimmune uveitis. β-Arrestin is a member of the arrestin family, sharing similarity in the C-terminal part with α-transducin and with other purine nucleotide-binding proteins. β-Arrestins regulate β-adrenergic receptor function; they seem to bind phosphorylated β-adrenergic receptors, thereby causing a significant impairment of their capacity to activate G_S proteins.

(Arrhenius) activation energy *symbol*: E_a or E_A; *see* **Arrhenius equation**.

Arrhenius equation an equation representing the effect of temperature on the velocity of a chemical reaction. It may be expressed in the forms:

$$d\ \ln k/dT = E_a/RT^2\ (1)$$

or

$$d\ \ln k/d(1/T) = -E_a/R\ (2)$$

or

$$k = Ae^{-Ea/RT}\ (3)$$

where k is the rate constant for the reaction, E_a is its **(Arrhenius) activation energy**, R is the gas constant, T is the thermodynamic temperature, and A is a constant termed the frequency factor or the pre-exponential factor. Version 2 may be integrated to:

$$\ln k = \ln A - E_a/RT\ (4).$$

Version 4 of the equation requires a plot of ln$k$ against $1/T$, known as an **Arrhenius plot**, to be a straight line of slope $-E_a/R$, a relationship that has been shown to obtain for a considerable number of chemical reactions. *See also* **temperature coefficient of reaction**. [After Svante August Arrhenius (1859–1927), Swedish chemist and physicist.]

Arrhenius plot *see* **Arrhenius equation**.

ARS *abbr. for* **1** autonomously replicating sequence; any DNA sequence that can confer upon a plasmid the property of becoming a **replicon** in a particular host. The term is largely confined to fungal genetics. **2** *(in clinical biochemistry) abbr. for* arginase.

Arsenazo III 2,2′-(1,8-dihydroxy-3,6-disulfonaphthalene-2,7-bisazo)bisbenzenearsonic acid; an indicator substance used in the determination of low (micromolar) concentrations of free calcium ions. The free acid is purple; the calcium adduct is blue-violet.

arsenic *symbol*: As; a semi-metal element of group 15 of the IUPAC **periodic table**; atomic number 33; relative atomic mass 79.41. It exists in three forms: yellow, grey, and black. The yellow form, comparable to white phosphorus, is less stable than the other forms and is converted into the grey (metallic) form by heat. The black form is more stable than the yellow form but is metastable with respect to the grey form. Arsenic is required in trace amounts by some organisms, but generally it acts as an antimetabolite.

arsenical **1** of or containing arsenic. **2** a drug or other agent (e.g. an insecticide, rodenticide, or nerve gas) containing arsenic as an active principle.

artemesinin *see* **sesquiterpene lactone**.

Artemis *see* **genome annotation software**.

arteriosclerosis a pathological condition in which there is a thickening and loss of elasticity of the walls of the arteries, which may become calcified. This interferes with the blood supply to various organs and tissues, resulting in impaired function. It normally, though not invariably, results from **atherosclerosis**.

arthritis any abnormality of a joint in which heat, redness, swelling, tenderness, or loss of motion or deformity are present. The two main types are osteoarthritis (OA) and rheumatoid arthritis (OR). OA is defined pathologically by reduced joint space secondary to a loss of cartilage. RA is of unknown etiology but may be caused by an infective agent or by **autoimmunity** to **type II collagen** or to **IgG**.

Arthus reaction a **complement**-dependent hypersensitivity reaction caused when antigen reacts with precipitating antibody in the skin or other tissues, forming microprecipitates in and around the small blood vessels and, secondarily, damaging cells. In the **passive Arthus reaction** antibody is injected intravenously and the antigen applied locally; in the **reversed passive Arthus reaction** the opposite applies. An **active Arthus reaction** may occur when antigen is injected locally subsequent to previous injection of the same antigen. The inflammation that results is by type III mechanisms (*see* **hypersensitivity** (def. 2)). [Described by (Nicholas) Maurice Arthus (1862–1945), French physiologist and bacteriologist, in 1903.]

articulin any of a family of cytoskeletal proteins of the **epiplasm** of flagellate and ciliate organisms. They form filaments and larger sheets or tubes. They contain repeated valine- and proline-rich motifs with the consensus VPVP_ _V_ _ _V.

artificial intelligence *abbr.*: AI; the computational simulation of human intelligence. AI methods try to capture human expertise in explicit rules, or with **neural networks** trained to recognize complex patterns.

artificial neural network *abbr.*: ANN; *an alternative name for* **neural network**.

aryl any univalent organic radical derived from an **arene** by loss of one hydrogen atom.

arylene any bivalent organic group derived from an **arene** by loss of two hydrogen atoms.

arylsulfatase any of a group of enzymes that catalyse the hydrolysis of a phenol sulfate to a phenol and sulfate. All sulfatases contain a cysteinyl residue that has been modified to a formylglycinyl residue required for activity. Arylsulfatases A, B, and C are common names for **cerebroside-sulfatase**, ***N*-acetylgalactosamine-4-sulfatase**, and **steryl-sulfatase** respectively. A cluster of genes at Xp222.3 encodes arylsulfatases C, D, E, and F. All are associated with the endoplasmic reticulum and have a neutral-to-alkaline pH optimum. The gene for arylsulfatase E is involved in X-linked chondrodysplasia punctata.

As *symbol for* arsenic.

ASA dehydrogenase *see* **aspartate-semialdehyde dehydrogenase**.

ASAT *(in clinical biochemistry) abbr. for* aspartate aminotransferase. *See* **aspartate transaminase**.

AS-C *abbr. for* Achaete–Scute complex. *See also* **AS-C protein**.

ascarylose 3,6-dideoxy-L-mannose; 3,6-dideoxy-L-*arabino*-hexose; a component of glycolipids found in eggs of the nematode, *Ascaris*, and in the bacterium, *Yersinia pseudotuberculosis*, type V. For the D enantiomer *see* **tyvelose**.

ascending boundary the solute boundary that moves upwards in one arm of the cell during electrophoresis in a **Tiselius apparatus**.

ascending chromatography any of the techniques of **chromatography** in which the mobile phase moves upwards over the solid phase.

ASCII *abbr. for* American Standard Code for Information Interchange; a set of standard characters readable by all computers. Strictly ASCII uses characters in the range 0–127, but an 8-bit version (range 0–255) is used, the higher numbers representing characters not in the Latin or Carolingian alphabets (e.g. Å or é).

ascites the accumulation of serous fluid in the peritoneal cavity. The presence of ascites may be due to the growth of a tumour elsewhere in the body, the ascitic fluid then containing a suspension of single tumour cells. Administration of a **hybridoma** results in the formation of **monoclonal antibodies** which can be recovered from the ascitic fluid. **—ascitic** *adj.*

Ascoli test a precipitin test used in the serological diagnosis of anthrax. The antigens are extracted with boiling saline and detected by a ring test with immune serum.

ascorbic acid a hexose, the L enantiomer of which is found in fruit and vegetables. It has vitamin C activity in humans (most other primates can synthesize ascorbic acid) and guinea pigs. Humans are among the few higher animals that are unable to synthesize it, being deficient in **L-gulonolactone oxidase**, the enzyme catalysing the terminal step in L-ascorbic acid synthesis. Ascorbic acid contains an enediol group, one hydroxyl group of which is acidic (pK_a 4.04) and ionizes to give an anion ascorbate; the other ene-diol hydroxyl acts as a reducing group ($E^{o\prime}$ = +0.058 V, pH 7), and is oxidized on conversion to dehydroascorbate. Ascorbate is required together with ferric ion as a cofactor in the oxidation of prolyl residues in collagen to hydroxyprolyl residues and in other reactions. Glucose transporter 1 (GLUT1) mediates transport of dehydroascorbic acid across cell membranes.



ascorbic acid



ascorbate ion



dehydroascorbic acid

ascospore a (usually sexually derived) haploid spore formed within an **ascus**.

AS-C protein *abbr. for* Achaete–Scute complex protein; any of a family of proteins encoded by the Achaete–Scute complex, a gene cluster first discovered in *Drosophila,* but with analogues in mammals and other organisms. They are involved in the determination of the neuronal precursors in the peripheral and central nervous systems. The T3, T4, and T5 proteins label strongly in the presumptive stomatogastric nervous system, while T8 is more prominent in the presumptive procephalic lobe. They resemble other members of the **MYC** family of helix-turn-helix transcription factors.

ascus (*pl.* **asci**) a sac-like fruiting body formed in ascomycete fungi, e.g. yeasts and *Neurospora*; it contains (typically eight) **ascospores** when mature.

+ase *suffix* denoting an enzyme; it is generally attached to a root indicating the substrate and/or the nature of the reaction catalysed. [from **diastase**.]

asemantic molecule any molecule that is not produced by an organism and therefore does not express any of the information that the organism contains. Absorbed molecules, although not derived from information contained within the organism, may nevertheless offer information about the organism relating to its absorption mechanisms. *See* **semantide**. *See also* **episemantic molecule**.

asepsis **1** the state of being **aseptic**. **2** the methods of making or keeping something aseptic. *Compare* **antisepsis**.

aseptic sterile; free from pathogenic microorganisms. *Compare* **antiseptic** (def. 2).

aseptic technique any technique incorporating measures that prevent the contamination of cultures, sterile media, etc. and/or the inappropriate infection of persons, animals or plants, by extraneous microorganisms.

asexual reproduction *or* **agamic reproduction** the development of a new individual from either a single cell or a group of cells without any sexual process. The term includes **agamogeny** and **vegetative reproduction**.

Ash protein *another name for* **Grb2**.

asialo+ *comb. form* denoting the absence from a compound of sialic-acid residues, e.g. after their deliberate enzymic removal from a naturally occurring **sialo-** (def. 2) compound.

A side the side of the nicotinamide ring of NAD(P)H from which projects the *pro-R* hydrogen atom (known as H_A) at the 4 position. *Compare* **B side**. *See also* **pro-*R*/pro-*S* convention**.

A site *abbr. for* aminoacyl-tRNA site (of a ribosome).

Asn *symbol for* a residue of the α-amino acid L-asparagine (alternative to N).

AsnC the asparagine biosynthetic operon regulatory protein, the product of *asnC*. In *Escherichia coli,* it is the activator of *asnA* expression, the autogenous regulator of *asnC* expression, and the repressor of *gidA* (a gene of *E. coli* associated with glucose-inhibiting division) at the post-transcriptional level. It is a **helix-turn-helix** (HTH) protein, and the prototype for the AsnC HTH family of regulatory proteins.

ASO *abbr. for* antistreptolysin-O; *see* **streptolysin**.

Asp *symbol for* a residue of the α-amino acid L-aspartic acid (alternative to D).

ASP *abbr. for* **agouti signal protein**.

asparaginase EC 3.5.1.1; *other names*: L-asparaginase; *systematic name*: L-asparagine amidohydrolase; an enzyme that catalyses the hydrolysis of L-asparagine to L-aspartate and NH_3. It is an effective antileukemic drug when injected into the bloodstream, its action being to deprive fast-growing tumour cells of the exogenous asparagine they require for rapid growth. Its clinical usefulness is limited because it causes damage to tissues with low asparagine synthetase activity. Several isoenzymes are found in several bacteria.

asparaginate **1** asparagine anion; the anion, $H_2N–CO–CH_2–CH(NH_2)–COO^–$, derived from asparagine. **2** any salt containing the asparagine anion. **3** any ester of asparagine.

asparagine *trivial name for* the β-amide of aspartic acid: aspartic 4-amide; α-aminosuccinamic acid; 2-amino-3-carbamoylpropanoic acid, $H_2N–CO–CH_2–CH(NH_2)–COOH$; a chiral α-amino acid. L-Asparagine (*symbol*: A *or* Asn; *(formerly) also* Asp(NH_2)), (*S*)-2-amino-3-carbamoylpropanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: AAC or AAU. It is a non-essential dietary amino acid in mammals, and is glucogenic. One residue per molecule of D-asparagine (*symbol*: D-Asn *or* DAsn), (*R*)-2-amino-3-carbamoylpropanoic acid, may occur in the antibiotic bacitracin A as an alternative to one of D-aspartic acid. *Compare* **isoasparagine**.



L-asparagine

asparagine repeat *or* **N repeat** a sequence in proteins that consists only of asparaginyl residues. For example, insulin receptor substrate 2 contains a sequence of eight such residues. Unlike glutamine repeats they are rare in mammalian proteins.

asparagine synthase (glutamine-hydrolysing) EC 6.3.5.4; *other name*: asparagine synthetase (glutamine-hydrolysing). An enzyme that catalyses a reaction between ATP, L-aspartate, and L-glutamine to form AMP, pyrophosphate, L-asparagine, and L-glutamate. *Compare* **aspartate– ammonia ligase**.

asparagino **1** N^2-asparagino; the alkylamino group, $H_2N–CO–CH_2–CH(COOH)–NH–$, derived from asparagine by loss of a hydrogen atom from its α-amino group. **2** N^4-asparagino; the acylamino group, $H_2N–CH(COOH)–CH_2– CO–NH–$, derived from asparagine by loss of a hydrogen atom from its amide group.

asparaginyl the acyl group, $H_2N–CO–CH_2–CH(NH_2)–CO–$, derived from asparagine. *Compare* **isoasparaginyl**.

aspartame *N*-L-*α*-aspartyl-L-phenylalanine methyl ester; a low-calorie artificial sweetener, about 160 times sweeter than sucrose in aqueous solution. Its sweetness is lost in cooking due to hydrolysis of the methyl ester. It is to be avoided in patients with phenylketonuria.

aspartase EC 4.3.1.1; *recommended name*: aspartate ammonia-lyase; *other name*: fumaric aminase. An enzyme that catalyses the hydrolysis of L-aspartate to fumarate and NH_3.

aspartate 1 aspartate(1–) *or* hydrogen aspartate; the monoanion derived from aspartic acid. In theory, the term denotes any ion or mixture of ions formed from aspartic acid and having a net charge of –1, although the species $^{-}OOC–CH_2–CH(NH_3^{+})–COO^{-}$ generally predominates in practice. **2** *the systematic name for* aspartate(2–); the dianion derived from aspartic acid. **3** any salt containing an anion of aspartic acid. **4** any ester of aspartic acid.

aspartate aminotransferase *see* **aspartate transaminase**.

aspartate–ammonia ligase EC 6.3.1.1; *other name*: asparagine synthetase; an enzyme that catalyses the reaction of ATP with L-aspartate and NH_3 to form AMP, pyrophosphate, and L-asparagine. *Compare* **asparagine synthase (glutamine-hydrolysing)**.

aspartate carbamoyltransferase *see* **aspartate transcarbamylase**.

aspartate kinase EC 2.7.2.4; *other name*: aspartokinase; an enzyme that catalyses the formation of 4-phospho-L-aspartate from ATP and L-aspartate with release of ADP. The reaction is the first step in the biosynthesis of lysine, methionine, and threonine in plants and bacteria. In *Escherichia coli*, the pathway for the synthesis of each amino acid is independently controlled by regulation of isoenzymes specific for each pathway. *See* **homoserine dehydrogenase** for another example.

aspartate-semialdehyde dehydrogenase EC 1.2.1.11; *systematic name*: L-aspartate-4-semialdehyde:NADP$^+$ oxidoreductase (phosphorylating); *other name*: ASA dehydrogenase; an enzyme that, although reversible, normally catalyses the formation of L-aspartate-4-semialdehyde, orthophosphate, and NADP$^+$ from L-4-aspartylphosphate and NADPH. Its product is a component of a pathway involved in the biosynthesis of lysine and methionine, and can be converted either into dihydropicolinate (a precursor of lysine) or into homoserine (a precursor of methionine). Example from *Escherichia coli*: DHAS_ECOLI, 367 amino acids (39.97 kDa).

aspartate transaminase *abbr. (in clinical biochemistry)*: AST; EC 2.6.1.1; *systematic name*: L-aspartate:2-oxoglutarate aminotransferase; *other names*: transaminase A; glutamic– oxaloacetic transaminase; glutamic–aspartic transaminase. An enzyme that catalyses a reaction between L-aspartate and 2-oxoglutarate to form oxaloacetate and L-glutamate. It is a pyridoxal-phosphate enzyme, very widely distributed, performing a pivotal role in amino-acid metabolism. In mammals this includes the transfer of amino groups to aspartate, which then transfers them into the **urea cycle** through **argininosuccinate synthase**. Very high plasma concentrations of AST (more than 100 times normal) are found in cases of severe tissue damage including acute hepatitis, crush injuries, and tissue hypoxemia. In jaundice and myocardial infarction the levels reach 10 to 20 times normal; in myocardial infarction AST starts to rise about 12 h after the infarct, reaching a peak at 24 to 36 h, then declining over 2 to 3 days. The normal level in human plasma is in the range 10–50 IU L^{-1} (method-dependent; assumed presence of vitamin B_6 in the assay).

aspartate transcarbamylase *abbr.*: ATCase; EC 2.1.3.2; *recommended name*: aspartate carbamoyltransferase; *other names*: carbamylaspartotranskinase. An enzyme that catalyses a reaction between carbamoyl phosphate and L-aspartate to form *N*-carbamoyl-L-aspartate with release of orthophosphate. In many eukaryotes it is an activity of the **CAD protein**. In *Escherichia coli*, operon *pyrBI* codes for catalytic and regulatory chains; the catalytic chain consists of 311 amino acids (34.37 kDa). There are six motifs and the 3-D structure of the enzyme in several states is known. The protein has a very high α-helical content. Carbamoyl aspartate is an important component of the pathway for *de novo* synthesis of pyrimidines.

aspartic denoting a residue of aspartic acid, whether or not the *β*-carboxyl group is protonated.

aspartic acid *trivial name for α*-aminosuccinic acid; 2-aminobutanedioic acid, $HOOC–CH_2–CH(NH_2)–COOH$; a chiral *α*-amino acid. L-Aspartic acid (*symbol*: D *or* Asp), (*S*)-2-aminobutanedioic acid, is a coded amino acid found in peptide linkage in proteins; codon: GAC *or* GAU. In mammals it is a nonessential dietary amino acid and is glucogenic. Residues of D-aspartic acid (*symbol*: D-Asp *or* dAsp), (*R*)-2-aminobutanedioic acid, are found in the cell-wall material of bacteria of various species, and one residue per molecule may occur in the antibiotic bacitracin A as an alternative to one of D-asparagine. It is also formed by racemization of L-aspartic acid residues in long-lived proteins such as crystallins, dentine, and myelin.



L-aspartic acid

aspartic amide 1 aspartic 1-amide; *an alternative name for* **isoasparagine**. **2** aspartic 4-amide; *an alternative name for* **asparagine**.

aspartic andopeptidase *or (formerly)* **acid proteinase** *or* **aspartyl protease** *or* **carboxyl protease** any enzyme of the sub-subclass EC 3.4.23, comprising endopeptidases having a pH optimum below 5 by virtue of an aspartic residue being involved in the catalytic process. The group includes cathepsin D, chymosin, the pepsins, and renin.

aspartic proteinase any **endopeptidase** that contains an aspartyl residue that is essential for catalytic activity. Examples include pepsin, renin, rennin, and HIV protease.

asparto the alkylamino group, $HOOC–CH_2–CH(COOH)–NH–$, derived from aspartic acid.

aspartoacylase an enzyme, EC 3.5.1.15, that catalyses the hydrolysis of *N*-acetyl-L-aspartate..

aspartokinase *see* **aspartate kinase**; *see also* **aspartokinase/ homoserine dehydrogenase**.

aspartokinase/homoserine dehydrogenase a multifunction enzyme, characterized in *Escherichia coli*, that catalyses two steps in the pathway from aspartate to diaminopimelate and lysine, to methionine, and to threonine and isoleucine. It is allosterically regulated by threonine. The *E. coli* protein is a homotetramer consisting of 820 amino acids (89.02 kDa); the first 149 amino acids form the aspartokinase domain, while the last 350 residues form the homoserine dehydrogenase domain.

aspartoyl the diacyl group, $–CO–CH_2–CH(NH_2)–CO–$, derived from aspartic acid.

***α*-aspartyl** aspart-1-yl; the *α*-monoacyl group, $HOOC–CH_2–CH(NH_2)–CO–$, derived from aspartic acid.

***β*-aspartyl** *or (formerly)* **isoaspartyl** aspart-4-yl; the *β*-monoacyl group, $HOOC–CH(NH_2)–CH_2–CO–$, derived from aspartic acid.

***β*-aspartyl-*N*-acetylglucosaminidase** EC 3.2.2.11; *systematic name*: 1-*β*-aspartyl-*N*-acetyl-D-glucosaminylamine L-asparaginohydrolase. An enzyme that catalyses the hydrolysis of 1-*β*-aspartyl-*N*-acetyl-D-glucosaminylamine to *N*-acetyl-D-glucosamine and L-asparagine. *See also* **aspartylglucosaminuria**.

aspartylglucosaminuria an autosomal recessive disorder of worldwide distribution associated with progressive mental retardation due to lysosomal accumulation of aspartylglucosamine (2-acetamido-1-*β*-L-aspartamido-1,2-dideoxy-*β*-D-glucose), which is excreted in abnormally high amounts in the urine. This compound is commonly found in several glycoproteins in normal individuals. The first sign of the condition is usually a delay in speech development (1–4 years). The enzymic effect is a deficiency of lysosomal aspartylglucosaminidase (N^4-(*β*-*N*-acetylglucosaminyl)-L-asparaginase, EC 3.5.1.26), which consists of two each of glycosylated A and B chains (130 and 205 residues, respectively), both derived from a precursor (346 residues) by proteolytic cleavage. A score of mutations in a locus at 4q34-q35 are associated with the disorder.

aspartylglucosylamine deaspartylase *see* **N^4-(β-N-acetylglucosaminyl)-L-asparaginase**.

β-aspartyl phosphate *or* **4-phospho-**L-aspartate *or* **aspartyl-β-phosphate** an intermediate in the biosynthesis of lysine, threonine, and methionine in bacteria and plants. It is formed by **aspartate kinase**. It is converted to *β*-aspartyl semi-aldehyde, which is converted by the action of **homoserine dehydrogenase** to homoserine, a precursor of threonine or methionine. Alternatively addition of pyruvate to *β*-aspartyl phosphate leads to formation of dihydropicolinate, a precursor of lysine. A *β*-aspartyl phosphate residue is formed by phosphorylation of an aspartyl residue of Na^+,K^+-ATPase during the transport process.

aspartyl protease *an older name for* **aspartic proteinase**.

β-aspartyl semi-aldehyde OHC–CH_2–CH(NH_2)–COOH; *see* **β-aspartyl phosphate**.

aspartyl shift *or* **α → β-aspartyl shift** an intramolecular rearrangement reaction involving aspartic-acid residues that can occur during chemical synthesis or degradation of peptides. The *β*-carboxyl group of an aspartic residue displaces the *α*-carboxyl of the same residue from its amide (= peptide) linkage to the amino group of the adjacent amino-acid residue, thus forming an acid-sensitive *β*-amide (= isopeptide) linkage. Conditions must favour ionization of the *β*-carboxyl group. The reaction may be used to advantage in the partial hydrolysis of polypeptides and proteins by very dilute acid, but may occur to disadvantage during base-catalysed hydrolytic removal of protecting groups in the course of peptide synthesis.

Aspergillus a genus of filamentous fungi containing species of industrial and genetic importance. *A. niger* and *A. oryzae* are used in the production of citric acid, industrial enzymes, and fermented foods. The sexual species *A. nidulans* has been an important research tool in both biochemical and mitochondrial genetics. *A. flavus* is a source of **aflatoxins**.

asperlicin a naturally occurring antagonist of the peptide **cholecystokinin**, produced by various strains of *Aspergillus alliaceus*.

aspirin *or* **acetylsalicylic acid** 2-(acetyloxy)benzoic acid; an irreversible inhibitor of **prostaglandin-endoperoxide synthase**, through covalent acetylation of the *α*-amino group on the terminal serine active site. It is used as a drug for its antithrombotic activity and nonsteroidal anti-inflammatory and associated actions (antipyrexia, analgesia). *See also* **salicylic acid**.

Asp(NH_2) *(formerly) symbol for* L-asparagine.

Asp-NH_2 *symbol for* L-isoasparagine, an *α*-amino acid.

Asp(OMe) *symbol for β*-methyl aspartate; O^4-methyl hydrogen aspartate.

Asp-OMe *symbol for α*-methyl aspartate; O^1-methyl hydrogen aspartate.

assay *n.* **1** the determination of the activity, potency, strength, etc. of a substance, either on an absolute basis or in comparison with that of a standard preparation. **2** the determination of the relative amount(s) of one or more components of a mixture, or of the degree of purity of a substance. **3** to carry out such a determination. *See also* **bioassay**, **immunoassay**, **microbiological assay**, **radioassay**.

assembly *an alternative name for* **sequence assembly**.

assembly language *see* **programming language**.

assignment the identification of the part of a molecule that is responsible for a particular property, for example a cellular function or spectroscopic signal.

assimilation the absorption of simple foodstuffs (or of the products of their digestion) and their use in the biosynthesis of complex constituents of the organism; sometimes restricted to **photosynthesis**. —**assimilatory** *adj.*

assimilatory relating to autotrophic metabolism in which a substrate such as nitrate or sulfite is reduced and converted to organic compounds. *See* **nitrate reduction**. *Compare* **dissimilatory**.

assimilatory regulatory protein a *abbr.*: ARP_a; *obsolete name for* ferredoxin–thioredoxin reductase, obtained from chloroplasts.

assimilatory regulatory protein b *abbr.*: ARP_b; *obsolete name for* thioredoxin, obtained from chloroplasts.

association a reversible union between two chemical entities, whether alike or different, to form a more complex substance. *Compare* **dissociation** (def. 1).

association constant *symbol*: K_{ass} *or* K_a; the **equilibrium constant** for the reversible formation of a complex chemical compound from two or more simpler entities; the reciprocal of the **dissociation constant**, K_{diss}. Sometimes an **apparent** association constant, K'_{ass}, constrained with respect to stated values of certain variables (e.g. pH), is determined (*see* **equilibrium constant**). For an association of the type: A + B AB the (concentration) association constant is given by:

$$K_{ass} = [AB]/([A] \times [B]) = 1/K_{diss}$$

See also **affinity constant**, **off-rate**, **on-rate**, **stability constant**.

assortment *or* **reassortment** during meiosis, the distribution to opposing cell poles of the two members of each pair of chromosomes at anaphase I and of the two members of each pair of chromatids at anaphase II.

AST 1 *(in clinical biochemistry) abbr. for* aspartate transaminase. **2** *abbr. for* anion and sugar transporter, or sialin.

astacin EC 3.4.24.21; *other name*: *Astacus* proteinase; crayfish small-molecule proteinase; an enzyme that catalyses the hydrolysis of peptide bonds in substrates containing five or more amino acids, preferentially with Ala in the P1′ and Pro in the P2′ positions (*see* **peptidase P-sites**). Zinc is a cofactor.

astatin any of a subfamily of zinc metalloendopeptidases of unallocated number within sub-subclass EC 3.4.24, including **tolloid** (*Drosophila*) and bone morphogenetic protein 1 (i.e. C-proteinase of type I procollagen) (human), involved in differentiation.

astatine *symbol*: At; a halogen element of group 17 of the IUPAC **periodic table**; atomic number 85. It occurs as short-lived isotopes of mass numbers 215, 216, and 218 resulting from β-decay of other radioactive elements. Astatine-211, an α-emitter of half-life 7.5 h, results from α-bombardment of bismuth; it has potential in radiotherapy.

astaxanthin 3,3′-dihydroxy-*β*,*β*-carotene-4,4′-dione; a carotenoid pigment found mainly in animals (e.g. crustaceans, echinoderms) but also occurring in plants. It can occur free (as a red pigment), as an ester (e.g. the dipalmitate), or as a blue, brown, or green chromoprotein.

aster a system of cytoplasmic microtubules radiating from a **centriole**. It is present during cleavage of an ovum, during fusion of nuclei at fertilization, and in animal cells during cell division. *See* **importin**, **NuMA**.

asthma a common chronic and debilitating illness in which swollen and inflamed airways are produced by IgE-mediated allergic reactions to airborne allergens (most commonly from cockroaches, house-dust mites, or pets) or induced by exercise or cold . Two genes that seem to be involved are those for elevated IgE levels (locus at 5q31-q33) and for **ADAM-33** (locus at 20p). –**asthmatic** *adj., n.*; –**asthmatically** *adv*.

astral microtubule *see* **prometaphase**.

astray *or* **Robo-2** a homologue (1513 residues) in zebrafish of **Robo**. Mutations in the gene cause disruption of retinal axon guidance.

Astrup technique a micro technique for the rapid determination of the acid–base status of a sample of blood. The pH of the blood as taken is measured and the remainder of the sample split into two and each part equilibrated with a different CO_2/O_2 mixture of known $p(CO_2)$ and their pH values measured. These last two pH values and the corresponding $p(CO_2)$ values are plotted on a **Siggaard–Andersen nomogram** and the points joined by a straight line. The $p(CO_2)$ of the original sample may be obtained from the point on this line corresponding to the pH of the blood as taken. Furthermore, the **standard bicarbonate value** of the blood may be obtained from the point where the straight line intersects with a scale on the $p(CO_2)$ axis at 5.33 kPa (40 mmHg).

ASV *abbr. for* anodic stripping voltammetry.

Asx *symbol for* a residue of either of the *α*-amino acids L-aspartic acid or L-asparagine when the state of amidation is uncertain (alternative to B).

asymmetric synthesis any synthesis of a compound that produces only one of two possible enantiomers of the product. This is usually the case for enzymic but not for nonenzymic reactions.

asymmetry absence of **symmetry**. A particular example of its meaning in biochemistry relates to the different phospholipid composition of the inner and outer leaflets of a lipid bilayer, said to confer asymmetry of composition. **—asymmetric** *adj.*

asymmetry potential the usually small potential across a membrane electrode, such as a glass electrode, when both sides are immersed in identical solutions. It is probably due to slight imperfections in the membrane.

asynapsis absence of **synapsis** (def. 1); i.e. the failure of homologous chromosomes to pair during meiosis.

asynteny the state when two genetic loci are situated on different, nonhomologous chromosomes. *Compare* **synteny**. **–asyntenic** *adj.* **–asyntenically** *adv.*

At *symbol for* astatine.

AT *abbr. for* **ataxia telangiectasia**.

atactic characterized by or showing irregularity in the spatial arrangement of the parts of a molecule.

atactic polymer any regular polymer in which the molecules display essential randomness with regard to the configurations at all main-chain sites of steric isomerism.

ataxia telangiectasia *abbr.*: AT; an autosomal recessive progressive cerebellar ataxia that presents in early childhood and is followed by variable degrees of telangiectasia and frequently immunodeficiency and cancer (usually lymphoid). The serum α-fetoprotein level is elevated in most patients, and X-ray sensitivity is also a feature of the disease. The gene locus at 11q22-q23 for AT mutated (ATM) encodes a protein containing 3056 residues, which includes regions of homology with yeast and *Drosophila* proteins involved in DNA repair and also with phosphatidylinositol kinases. Many mutations (most leading to truncated proteins) are associated with the disease.

ataxia with isolated vitamin E deficiency *abbr.*: AVED; an autosomal recessive neurodegenerative disease that is clinically similar to **Friedreich's ataxia** but characterized by very low plasma levels of tocopherol. Patients absorb dietary vitamin E normally by incorporating it into chylomicrons in intestinal mucosa but do not transfer it into very-low-density lipoproteins (VLDLs) in hepatocytes. Some 20 mutations in a gene at 8q13.1-q13.3 for α-tocopherol transfer protein (278 residues) are associated with the disease.

ataxin any of a group of proteins (of no known function) that contain glutamine repeats that expand in various forms of spinocerebellar ataxia (SCA). The gene for **ataxin-1** (at 6p23) encodes a polypeptide of 792–830 amino acids depending on the length (6–44 residues) of the repeat. Ataxin-1 is predominant in neuronal nuclei but also occurs in the cytoplasm in other tissues. The repeat length expands to 39–82 residues in SCA 1. **Ataxin-2** (≈140 kDa) is encoded by a gene at 12q24. It has a tissue distribution similar to that of ataxin-1. Its wild-type repeat of 15–32 residues expands to 36–63 in SCA 2. **Ataxin-3** (locus at 14q24.3-q31) has a wild-type repeat of 17–41 residues, which expands to 62–84 residues in SCA 3 (or Machado–Joseph disease). **Ataxin-7** (locus at 3p12-p13) is expressed ubiquitously but especially in the cerebellum, and is present in nuclei. The wild-type repeat of 4–35 residues expands to 37–306 in SCA 7. Ataxins-4, -5, -6, -8, -9, and -10 have different chromosomal loci and their repeat lengths also expand in the respective types of SCA.

+ate *suffix* **1** designating any anion (including mixtures of anion and free acid), salt, or ester of any **oxoacid** (def. 1) other than an +ous acid. **2** denoting the product of a process, e.g. distillate, hydrolysate.

ATF *abbr. for* activating (or activator) transcription factor; any of various transcription factors for eukaryotic RNA polymerase II promoters that bind to **CRE**. Example, ATF-A and ATF-A-δ (human): these form a dimer; they have different sequences (amino acids 114–134 missing in δ), and possess a leucine zipper.

(A + T)/(G + C) ratio the ratio of the sum of the adenine plus thymine bases to the sum of the guanine plus cytosine bases in a DNA molecule or preparation. The ratio is to some extent a characteristic of an individual type of DNA molecule. *Compare* **Chargaff's rules**.

athero-ELAMs endothelial leukocyte-adhesion molecules, i.e. **selectins**, expressed in atherosclerotic plaques.

atheroma a condition or process affecting blood vessels in which plaques form beneath the intima (i.e. inner lining). These start as infiltration by lipid-containing cells but later become invaded by fibrous tissue or become calcified. It is associated with hypercholesterolemia and defects in the **apolipoprotein B receptor —atheromatous** *adj.*

atherosclerosis an extremely common degenerative condition of the arteries that predisposes to myocardial infarction, cerebral thrombosis, ischemic gangrene of the extremities, and other serious complications. The arterial outer coat is thickened, the elastic lamina is fragmented and infiltrated by calcified deposits of cholesterol and other lipids, and the intima is hypertrophied and irregular. Hypertension, cigarette smoking, hypercholesterolemia, diabetes mellitus, and obesity are well-recognized risk factors.

aThr *symbol for* a residue of the α-amino acid L-allothreonine, (2*S*,3*S*)-2-amino-3-hydroxybutanoic acid.

ATM *abbr. for* ataxia telangiectasia mutated. *See* **ataxia telangiectasia.** .

atmosphere 1 the envelope of gas surrounding the Earth. **2** any local gaseous environment. **3** *symbol*: atm; a non-SI unit of pressure equal to 101.325 kPa; the pressure that will support a column of mercury 760 mm high at 273.15 K, sea-level, and latitude 45°.

atom a unit of matter consisting of a single **nucleus** surrounded by one or more orbital **electrons**. The number of electrons is normally sufficient to make the atom electrically neutral; adding or removing electrons converts the atom into a negative or positive ion, but this is regarded as a state of the same atom since the atom is characterized by its nucleus.

atomic absorption spectrophotometry a quantitative version of **atomic absorption spectroscopy** in which the absorption of electromagnetic radiation by the ground-state atoms in the flame is measured photoelectrically and the concentration of the element in question calculated by reference to the absorption observed with solutions of the elements of known concentration.

atomic absorption spectroscopy an analytical technique, based on the observation of the absorption of light energy by atoms, in which an atomic vapour of an element is formed by aspiration of a solution of the element into a flame, or otherwise, so that the large majority of the element's atoms remain in the non-emitting ground state. These ground-state atoms absorb electromagnetic radiation of their own specific resonance frequency, to an extent that is proportional to the density of the elemental atoms in the flame.

atomic mass constant *symbol*: m_u; a fundamental constant equal to the mass of a carbon-12 atom divided by 12; it is equal to the **unified atomic mass unit**.

atomic mass unit *abbr. (formerly)*: amu; *see* **unified atomic mass unit**.

atomic number *an older alternative name for* **proton number**.

atomic orbital the volume containing all the points within a free atom at which the Schrödinger wave-function of an electron is of appreciable magnitude.

atomic radius the distance between the centre of the nucleus and the outermost electron shell of an atom. *Compare* **van der Waals radius**.

atomic weight *abbr.*: at. wt.; *former name for* **relative atomic mass**.

atomic weight unit *abbr.*: awu; one-twelfth of the mean mass of the neutral atoms of naturally occurring carbon.

atomizer *or* **atomiser** an instrument for breaking up a solution into a spray of fine droplets.

atom percent the proportion of any nuclide in a mixture expressed as a numerical percentage of all the atoms of that element present irrespective of their nuclidic masses.

atom percent excess a measure of the abundance of a stable nuclide in a sample expressed in terms of the excess, in **atom percent**, over that naturally present. It is used to express the extent of enrichment or dilution of substances labelled with stable isotopes.

atopy *or* **atopic allergy** an IgE-mediated allergic response occurring in some individuals and produced by T lymphocytes, which secrete various cytokines when triggered by environmental antigens. The clinical result is asthma, eczema, or rhinitis. It is associated with a gene at 5q31-q33 for elevated IgE levels.

ATP *abbr. for* adenosine 5′-triphosphate.

ATPase *abbr. for* adenosine triphosphatase.

ATPase associated with varied activities *see* **AAA protease**.

ATP-dependent K$^+$ channel *see* **KATP**.

ATP-diphosphatase *see* **apyrase**.

ATP[α,β-CH$_2$] *abbr. for* α,β-methyleneadenosine 5′-triphosphate; i.e. adenosine 5′-[α,β-methylene]triphosphate.

ATP[β,γ-CH$_2$] *abbr. for* β,γ-methyleneadenosine 5′-triphosphate; i.e. adenosine 5′-[β,γ-methylene]triphosphate.

ATP[β,γ-NH] *abbr. for* β,γ-imidoadenosine 5′-triphosphate; i.e. adenosine 5′-[β,γ-imido]triphosphate.

ATP(s) *abbr. for* adenosine 5′-γ-thiotriphosphate.

ATP synthetase *see* **H$^+$-transporting ATP synthase**.

atractyloside an extremely toxic glycoside, obtained from the rhizomes of the Mediterranean thistle *Atractylis gummifera*, that produces hypoglycemia and convulsions in animals. It inhibits oxidative phosphorylation, in particular the translocation of mitochondrial adenine nucleotides. Carrier-bound adenine nucleotides are apparently replaced by atractyloside owing to the latter's higher affinity for a common translocation site. *Compare* **bongkrekic acid**.



A-transferase EC 2.4.1.40; *recommended name*: fucosylgalactose α-*N*-acetylgalactosaminyltransferase; *other names*: fucosylglycoprotein α-*N*-acetylgalactosaminyltransferase, [histo- blood group] A-transferase; an enzyme that can catalyse a reaction between UDP-*N*-acetyl-D-galactosamine and glycoprotein α-L-fucosyl-(1,2)-D-galactose to form UDP and glycoprotein*N*-acetyl-α-D-galactosaminyl-(1,3)-[L-fucosyl-(1,2)]-D-galactose. It thus catalyses the addition of *N*-acetylgalactosamine to the H antigen of the **ABH antigen** system, forming the A antigen. This and the **B-transferase** protein are products of alleles of the *ABO* gene, differing in only four residues.

atrial of or pertaining to an **atrium**.

atrial natriuretic peptide *see* **natriuretic peptide**.

atrial natriuretic peptide receptor *see* **natriuretic peptide receptor**.

atrioactivase a specific serine protease, present in bovine cardiac atria, that catalyses processing of the precursor of **natriuretic peptide** by selective cleavage at Arg^{89}.

atriopeptins biologically active peptides isolated from mammalian cardiac atria. Atriopeptin I (I) has 21 amino acids, with the structure

SSCFGGRIDRIGAQSGLGCNS

(3–19 disulfide link); atriopeptin II (II) is the same with additional Phe-Arg residues at the C terminus; atriopeptin III is the same as II but with an additional Tyr residue at the C terminus. I relaxes intestinal smooth muscle but not vascular smooth muscle, while II relaxes both. *Compare* **natriuretic peptide**.

atrium *or (formerly)* **auricle** (*pl.* **atria**) **1** either of the two chambers of the heart that lie above the ventricles. They receive blood from the afferent veins and pump it into the ventricles. **2** any of various anatomical chambers that receive the openings of other cavities.

atrolysin B EC 3.4.24.41; *other names*: *Crotalus atrox* metalloendopeptidase B; hemorrhagic toxin B (*abbr.*: HT-B); a snake-venom enzyme that catalyses the cleavage of His^5-|-Leu^6, His^{10}-|-Leu^{11}, Ala^{14}-|-Leu^{15}, Tyr^{16}-|-Leu^{17}, and Gly^{23}-|-Phe^{24} of the insulin B-chain. The reaction is identical to the cleavage of insulin B-chain by **atrolysin C**. The enzyme also cleaves Ser-|-Xaa bonds in glucagon. It is a zinc-requiring enzyme.

atrolysin C EC 3.4.24.42; *other names*: *Crotalus atrox* metalloendopeptidase C; hemorrhagic toxin C and D; a snake-venom enzyme from the Western diamondback rattlesnake that catalyses the cleavage of His^5-|-Leu^6, His^{10}-|-Leu^{11}, Ala^{14}-|-Leu^{15}, Tyr^{16}-|-Leu^{17}, and Gly^{23}-|-Phe^{24} of the insulin B-chain. With small-molecule substrates it prefers hydrophobic residues at the P2′ position and small residues such as Ala or Gly at the P1 position (*see* **peptidase P-sites**). It is a zinc-requiring enzyme.

atrolysin E EC 3.4.24.44; *other names*: *Crotalus atrox* metalloendopeptidase E; hemorrhagic toxin E; a snake-venom enzyme from the Western diamondback rattlesnake that catalyses the cleavage of Asn^3-|-Gln^4, Ser^9-|-His^{10}, and Ala^{14}-|-Leu^{15} bonds in the insulin B-chain and Tyr^4-|-Gln^5 and Ala^8-|-Ser^9 in the A chain. It cleaves type IV collagen at Ala^{258}-|-Gln^{259} in α_1-collagen and at Gly^{191}-|-Leu^{192} in α_2-collagen. It is a zinc-requiring enzyme.

atrolysin F EC 3.4.24.45; *other names*: *Crotalus atrox* metalloendopeptidase F; hemorrhagic toxin F; a snake-venom enzyme that catalyses the cleavage of Val^2-|-Asn^3, Gln^4-|-His^5, Leu^6-|-Cys^7, His^{10}-|-Leu^{11}, Ala^{14}-|-Leu^{15}, and Tyr^{16}-|-Leu^{17} bonds in the insulin B-chain. It is a zinc-requiring enzyme.

atrophin a cytosolic protein that is widely expressed in tissues and contains glutamine, proline, and lysine repeats. It has no known function or homology to other proteins. The atrophin gene, at 12p13.31, encodes 1185 amino acids. The glutamine repeat (6–36 residues) expands to 49–84 residues (but the proline and lysine repeats are unchanged) in the form of spinocerebellar ataxia known as dentatorubropallidoluysian atrophy.

atrophy diminution in the size of a tissue or organ after full normal development has been attained. It is often a result of nutritional deficiency and/or decreased functional activity.

atropine (±)-hyoscyamine; tropyl dl-tropate; 1αH,5αH-tropan-3-ol (±)-tropate a tropane alkaloid obtained from deadly nightshade, *Atropa belladonna*; and other Solanaceae. The racemic mixture is a tertiary ammonium compound that acts as a **muscarinic receptor** antagonist. It is used as an anticholinergic, mydriatic, etc. *See also* **hyoscine**.



attachment proteins *general term for* proteins that are involved in binding other proteins to cell structures, e.g. **vinculin**, or α-actinin (*see* **actinin**), which bind actin to the plasma membrane.

attachment site *see* **active site** (def. 2).

A–T tailing **homopolymer tailing** of two types of duplex DNA molecule or fragment by the successive addition of adenine deoxynucleotide residues (A) to the 3′ ends of molecules of one type and the complementary addition of thymine deoxynucleotide residues (T) to the 3′ ends of molecules of the second type.

attB a bacterial attachment site that in the *E. coli* chromosome consists of a core of approx. 25 bp located between the *gal* and *bio* genes. In addition there are a number of secondary sites. Bacteriophage lambda DNA is integrated at this site through its attachment site **attP** (243 bp) in a reaction catalysed by the phage-encoded integrase (Int) and the integration host factor (IHF). On integration the prophage is bounded on its left side by the **attL** site, and on the right side by the **attR** site. Excision of the prophage takes place by recombination at the attL and attR sites in a reaction catalysed by Int, IHF, and excisionase (Xis). This recreates the **attB** site in the bacterial chromosome and the attP site in lambda DNA. attB and attP sites are used in plasmid vectors designed from cloning by site-specific recombination.

attenuance *symbol*: *D*; the logarithm to the base 10 of the ratio of the **radiant powers** of the incident radiation, P_0, and the transmitted radiation, *P*; thus:

$$D = \lg(P_0/P) = \lg T^{-1},$$

where *T* is the **transmittance**. Attenuance reduces to **absorbance** if the incident beam is only either transmitted or absorbed, but not reflected or scattered.

attenuated virus a virus that has become less pathogenic following passage in culture outside its natural host, or by the use of physical or chemical means.

attenuator a sequence in DNA that is located between the **operator** and the gene for the first protein in an **operon**. It can cause transcription termination. The operon for the synthesis of **tryptophan** in bacteria is an example of an operon that contains an attenuator.

atto+ *symbol*: a; *prefix* used with SI units denoting 10^{-18} times.

attractant *or* **chemoattractant** a substance that a motile cell or organism tends to move towards; i.e. one that elicits positive **chemotaxis**. For a responsive bacterium, attractants can be either nutritive or nonmetabolizable. An example is **cytotaxin**.

Au *symbol for* gold.

AUA 1 a codon in mRNA, excluding that of mammalian mitochondria, for L-isoleucine. **2** a codon in mammalian mitochondrial mRNA for L-methionine (and for *N*-formyl-L-methionine, chain initiation, in some species).

Aubergine a protein of *Drosophila* that is required for activation of mRNA for ***oskar***-encoded protein. It is related to eIF2C.

AUC a codon in mRNA for L-isoleucine.

AUG a codon in mammalian mitochondrial mRNA, and in non-mitochondrial mRNA the only codon for L-methionine and usually for *N*-formyl-L-methionine, chain initiation.

Auger effect a process by which an orbital electron in an atom passes from an excited to a lower energy level. The X-ray so produced collides with, and ejects, another orbital electron, known as an **Auger electron**, with energy in the X-ray range. [After Pierre Victor Auger (1899–1993), French physicist.]

auracyanin a small blue copper-containing bacterial outer membrane glycoprotein (one Cu^{2+} ion per protein) that donates electrons to cytochrome c_{554}.

auranofin tetraacetylthioglucosato-*S*)(triethylphosphane)gold(I); a gold compound used in the treatment of rheumatoid arthritis.

aureomycin 7-chlortetracycline. *See* **tetracycline**.

auriculin either of two overlapping N-terminal fragments of atrial **natriuretic peptide**, termed auriculin A and auriculin B.

Auriculin *a proprietary name for* atrial natriuretic peptide.

aurosome an artificially induced organelle occurring in animal cells cultured in the presence of gold. It is an electron-dense lysosomal body containing gold particles.

Australia antigen *an alternative name for* hepatitis B antigen. *See* **hepatitis**.

aut+ *a variant form of* **auto+**.

autacoid any druglike principle that is produced in or can be extracted from the organs of internal secretion. Autacoids include both excitatory substances (**hormones**) and inhibitory substances (**chalones**).

auto+ *or (before a vowel)* **aut+** *comb. form* **1** self; one's own. **2** occurring within oneself or itself. **3** acting by itself; automatic; spontaneous.

autoagglutination the tendency of a suspension of bacteria or other cells to agglutinate spontaneously in a simple medium not containing an **agglutinin** or other similar reagent.

autoallergy *an alternative term for* **autoimmunity**.

autoanalyser *or (esp. US)* **autoanalyzer** any instrument for effecting analyses automatically.

autoantibody an **antibody** produced in an animal that reacts with a constituent of the animal's own tissues, which thus acts as a 'self' antigen or **autoantigen**.

autoantigen an **antigen** that is a normal constituent of an individual and has the capacity to produce an **immune response** in the same individual in certain circumstances. Examples include: thyroid peroxidase (in autoimmune thyroiditis); TSH receptor (in Graves' disease); skeletal muscle acetylcholine receptor (in myasthenia gravis); and myelin basic protein (in multiple sclerosis).

autocatalysis the catalysis of a chemical or biochemical reaction by one of the reaction products. **—autocatalytic** *adj.*

autochthonous derived from that part of the body where found; native. *Compare* **autologous**.

autoclave an instrument, used for sterilizing culture media, instruments, etc., that consists of an airtight chamber which can be filled with, or surrounded by, steam at high pressure.

autocoupling hapten a reactive compound of low molecular mass that, when injected into an animal, reacts with tissue antigens to form hapten–antigen compounds. These then lead to the formation of antibodies to the **hapten**.

autocrine describing an agent that acts on the cell in which it is produced.

autofluorogram *an alternative name for* **fluorogram** (when produced by **fluorography** (def. 2)).

autofluorography *an alternative term for* **fluorography** (def. 2).

autogenesis *or* **autogeny** *an alternative term for* **abiogenesis**. **—autogenetic** *adj.*

autogenous 1 self-produced. **2** originating within, especially within one's own body.

autogenous regulation the mechanism by which a protein directly controls the expression of its own structural gene.

autograft any graft or transplant of the subject's own tissue(s).

***Autographa californica* nuclear polyhedrosis virus** *abbr.*: AcNPV *or* AcMNPV; the baculovirus most commonly used as a gene expression vector. It is used for the biocontrol of the alfalfa looper (*Autographa californica*), a moth whose larvae cause crop damage.

autoimmune regulator *abbr.*: AIRE; a transcriptional activator protein that contains zinc finger domains and is expressed predominantly in the thymus but also in other tissues. It consists of 545 amino acids, and is encoded by a locus at 21q22.3. Several mutations in the gene result in autoimmune polyendocrinopathy and ectodermal dystrophy.

autoimmunity *or* **autoallergy** a state of immunological reactivity against constituents of the subject's own tissues. Autoimmune diseases include myasthenia gravis, multiple sclerosis, rheumatoid arthritis, lupus erythematous, Graves' disease, and thyroiditis.

autoimmunization *or* **autoimmunisation** the process of inducing **autoimmunity**.

autologous derived from the same organism. *Compare* **autochthonous**.

autolysate *or (esp. US)* **autolyzate** a product of **autolysis**, e.g. a suspension of broken cells.

autolysin EC 3.5.1.28; *other name*: *N*-acetylmuramoyl-L-alanine amidase; an enzyme that catalyses the hydrolysis of the link between *N*-acetylmuramoyl residues and L-amino-acid residues in certain bacterial cell-wall glycopeptides. The enzyme is required for cell separation, cell-wall turnover, etc. *See also* **lysostaphin**.

autolysis the process of self-digestion that occurs in plant and animal tissues after death of the organism or following separation of tissue from the rest of the organism. It is due to the action of the tissue's own enzymes. **—autolytic** *adj.*

autolysosome an **autophagic vacuole**.

automutagen any **mutagen** formed in an organism as a normal or abnormal metabolic product that is mutagenic in the same organism.

autonomic nervous system *abbr.*: ANS; those parts of the **peripheral nervous system** and **central nervous system** that govern homeostasis in vertebrates and are generally independent of voluntary control.

autonomous existing or able to exist independently; used, e.g., of a tumour cell that is free of host control or of an episome or plasmid that replicates independently of the chromosome.

autophagic vacuole an enlarged **lysosome** containing subcellular structures such as mitochondria; a secondary lysosome.

autophagosome a **phagosome** containing endogenous cellular debris. *Compare* **heterophagosome**.

autophagy a process, apparently ubiquitous among eukaryotes, by which cells digest parts of their own cytoplasm. *Compare* **heterophagy**. **—autophagic** *adj.*

autophagy factor *abbr.*: Apg; any of ≈16 ubiquitin-like modifier proteins of yeast that are required for autophagy induced by starvation. They show weak homology with ubiquitin.

autophosphorylation the phosphorylation by a protein of one of its own residues. It is important in signal transduction by growth hormone receptors (*see*, e.g., **epidermal growth factor receptor**), but occurs in the case of other proteins, e.g. **caldesmon**.

autoprothrombin I *an alternative name for* factor VII; *see* **blood coagulation**.

autoprothrombin II *an alternative name for* factor IX; *see* **blood coagulation**.

autoprothrombin IIA *an alternative name for* **protein C**.

autopsy *or* **necropsy** the examination of a dead body, commonly to determine the cause of death or the presence of disease processes; a post-mortem (examination). *Compare* **biopsy**.

autoradiogram an **autoradiograph**, especially of a chromatogram or electrophoretogram.

autoradiograph *or* **autoradiogram** the image produced by **autoradiography**.

autoradiography a method by which radioactive material can be localized in, e.g., a tissue, cell, a cell part, or molecule, or in a chromatogram or electrophoretogram. The sample containing a radioactive substance is put in direct contact with a thick layer of specially prepared photographic emulsion. The radiation emitted in the decay of the radionuclide(s) activates individual silver halide grains in the emulsion rendering them susceptible to conversion to metallic silver grains by a photographic developer. After fixation the silver grains may be located either visually or by microscopy.

autosomal of, relating to, or being an **autosome**.

autosomal disease disease that results from an abnormality affecting the **autosomes**.

autosomal dominant polycystic kidney disease *abbr*.: ADPKD; a disease that affects 1:1000 people and is characterized by development of numerous renal cysts and consequent renal failure. It is usually caused by mutation of the *PKD1* gene, locus 16p13.3-p13.12, encoding **polycystin** 1, but can also arise through mutation of the *PKD2* gene, locus 4q21-q23, encoding polycystin 2.

autosomal limb girdle dystrophy a genetically heterogeneous group of diseases occurring in both dominant and recessive forms. Limb girdle muscular dystrophies (LGMD) are characterized by muscle weakness of both upper arms and legs. Genes for five forms of autosomal dominant LGMD have been localized or identified, including the myotilin locus at 5q31 and the caveolin-3 locus at 3p25. Genes for nine forms of autosomal recessive LGMD have been localized or identified including five that involve the sarcoglycan complex. Dominant forms of the disease usually show adult onset whereas the recessive forms have childhood onset.

autosomal sex reversal *or* **campomelic dysplasia.** *See* ***SOX.***

autosome any **chromosome** except the **sex chromosomes**. Hence the genes carried by the autosomes show **autosomal linkage** (or **autosomal inheritance**) according to the assortment of their respective autosomes to gamete cells during meiosis. Humans have 22 pairs of autosomes in addition to a pair of sex chromosomes.

autosteric effector any **effector** that binds to, and exerts its effect at, part of or immediately adjacent to the **active site** of an **allosteric** protein. It is distinguished from an **allosteric effector** operating at a distant site.

autotroph *or* **lithotroph** any organism that requires only simple inorganic substances to fulfil its nutritional requirements and for which gaseous or dissolved carbon dioxide is the sole source of carbon for the synthesis of cellular constituents. The term often includes any microorganism for which trace amounts of certain substances, e.g. vitamins, must also be supplied. Autotrophs may be subdivided into **chemoautotrophs** (*or* chemolithotrophs) and **photoautotrophs** (*or* photolithotrophs) according, respectively, to whether they are **chemotrophs** or **phototrophs**. *Compare* **heterotroph**. **—autotrophic** *adj.*; **autotrophy** *n.*

autoxidation *or* **autooxidation** an oxidation reaction that occurs spontaneously in the presence of an oxidant, usually oxygen.

AUU a codon in mRNA for L-isoleucine.

auxiliary amino acid any amino-acid residue in the **active site** (def. 1) of an enzyme that is more than one bond distance removed from the substrate molecule in the enzyme–substrate complex. *Compare* **contact amino acid**.

auxin any of a group of plant hormones, produced by regions of actively dividing and enlarging cells, that regulate aspects of plant growth. They include indole-3-acetic acid and indole-3-acetonitrile. Auxins bind an auxin-response protein, which contains an N-terminal domain that binds to a 6 bp auxin-response element in auxin-inducible genes.

auxin-binding protein 1 *abbr*.: ABP1; a small family of proteins (≈23 kDa) that bind indole 3-acetic acid, naphthalene 1-acetic acid, and other molecules with auxin activity in plants. They contain a C-terminal HDEL putative ER-retention domain. Strong circumstantial evidence suggests that they may be auxin receptors. Plant cells contain a variety of enzymes and other proteins that also bind auxin.

auxochrome any saturated atomic grouping (e.g. -OH, $-CH_3$, $-NH_2$, -Cl, -SH) that, when attached directly to a **chromophore**, shifts the selective absorption of light in the direction of longer wavelengths and enhances the intensity of absorption.

auxostat in industrial fermentation, a **chemostat** in which the **dilution rate** can be varied, normally in response to some parameter such as growth rate or pH, so that growth rate is more readily maximized.

auxotroph any strain of microorganism (alga, bacterium, or fungus) that differs from the **wild-type** by requiring a supply of one or more growth factors. *Compare* **prototroph**. **—auxotrophic** *adj.*

auxotrophy the condition of being an **auxotroph**.

***Ava*I** a type 2 **restriction endonuclease** recognition sequence: C↑[TC]CG[AG]G.

***Ava*II** a type 2 **restriction endonuclease**; recognition sequence: G↑G[AT]CC.

avenacin A-1 a triterpenoid saponin present in roots of oat plants but not in those of wheat or barley. It is highly effective against a major pathogen of cereal roots, one that therefore affects wheat and barley but not oat plants. The terminal *β*-D-glucose (1→2 or 1→4) units are removed by the saponin-detoxifying avenacinase that is produced by a variety of this pathogen that affects oats.

avenacinase *see* **avenacin A-1**

avenic acid a phytosiderophore (or iron chelator) secreted by roots of oat plants (*Avena sativa*). It is a nonprotein amino acid derived from the *α*-aminobutyrate moieties of three *S*-adenosylmethionine molecules.

average *an alternative term for* (arithmetic) **mean**.

average life *see* **mean life**.

average molar mass *or (formerly)* **average molecular weight** any of a series of numeric characteristics of a macromolecular system that are useful for assessing the extent of its polydispersity. The three most important are the **number-average molar mass**, M_n, the **mass-average molar mass**, M_m, and the **Z-average molar mass**, M_z . These three characteristics are given by the expressions:

$$M_n = \Sigma n_i M_i / \Sigma n_i \text{ (kg mol}^{-1}\text{)}$$

$$M_m = \Sigma n_i M_i^2 / \Sigma n_i M_i \text{ (kg mol}^{-1}\text{)}$$

$$M_z = \Sigma n_i M_i^3 / \Sigma n_i M_i^2 \text{ (kg mol}^{-1}\text{)}$$

where n_i is the amount of substance of species *i* and M_i is the molar mass of species *i*. Measurement of a **colligative property**, e.g. osmotic pressure, or end-group analysis, gives M_n; light scattering, dielectric dispersion, or fluorescence depolarization measurements give M_m ; and data obtained by equilibrium ultracentrifugation will yield either M_m or M_z depending on how they are treated. For polydisperse or heterogeneous systems, $M_z > M_m > M_n$, whereas for monodisperse systems these three characteristics are equal (i.e. equal to the relative molecular mass, M_r, of the single species).

average molecular weight *former name for* **average molar mass**.

average radius of gyration *an alternative term for* **mean radius of gyration**.

average relative molecular mass *former name for* **average molar mass**.

avermectin B_1 *an alternative name for* **abamectin**.

avidin a 66 kDa glycoprotein comprising four essentially identical subunits, each of which consists of a single polypeptide chain of 128 amino-acid residues. Isolated from the white of the eggs of birds and amphibia, it binds extremely strongly to **biotin,** and produces biotin deficiency when fed to experimental animals.

avidity **1** the tendency of an antibody to form more-or-less stable complexes with a (macromolecular) antigen; a measure of this tendency. **2** *an alternative term for* **affinity**.

***Avi*II** a type 2 **restriction endonuclease**; recognition sequence: TGC↑GCA. *Mst*I and *Fsp*I are **isoschizomers**.

avirulent lacking **virulence**.

avitaminosis a condition resulting from deficiency of one or more **vitamins**. The deficient vitamin may be specified, as in avitaminosis A, B, etc.

Avogadro constant *or (formerly)* **Avogadro's number** *symbol*: L *or* N_A ; the number of molecular entities in one mole of any chemical species. It is a fundamental physical constant, of value 6.022 136 7(36) × 10^{23} mol^{-1}. *Compare* **Loschmidt constant**.

Avogadro number *or* **Avogadro's number** the numerical value of the **Avogadro constant**.

Avogadro's hypothesis *or* **Avogadro's law** the principle that equal volumes of all ideal gases, at the same temperature and pressure, contain equal numbers of molecules. [After Lorenzo Romano Amadeo Carlo Avogadro, Count of Quaregna and Cerreto (1776–1836), Italian physicist and chemist who formulated it in 1811.]

avogram *see* **dalton**.

AVP *abbr. for* arginine vasopressin.

awk *see* **programming language**.

axenic pertaining to the growth of organisms of a single species in the absence of living organisms or living cells of any other species (also, strictly, in the absence of living cells of the organism itself except those in the intact living organism and its gametes). **—axenity** *n.*; **axenically** *adj.*

axenize *or* **axenise** to render axenic.

axenite an organism grown axenically.

axial **1** of, relating to, or being an **axis** (def. 1 or 2); located on or close to such an axis. **2** *(in stereochemistry) Symbol*: a. *See* **conformation**.

axial ratio the ratio of the length of the major axis to that of the minor axis of a prolate ellipsoid of rotation, a model often used for a protein or other macromolecule in solution.

axin any of a small family of proteins that bind glycogen synthase kinase 3 (a serine/threonine kinase), β-catenin, and APC protein (*see* ***APC***) to form a complex that targets β-catenin for degradation (*see* **catenin**). It also interacts with the catalytic subunit of protein phosphatase A2 and is a negative regulator of Wnt signaling. Axin 2 is also called conductin or axil.

axis **1** a straight line about which a body or three-dimensional figure, e.g. a crystal, is considered to rotate. **2** one of the reference lines of a co-ordinate system. **3** the second vertebra of the neck in higher vertebrates.

axis of rotation *see* **rotation axis**.

axis of symmetry *see* **symmetry, axis of**.

axokinin a heat-stable phosphoprotein, M_r 56 000, present in flagella and cilia of vertebrate and invertebrate species. Its cyclic AMP-dependent phosphorylation is required for initiation and maintenance of flagellar motility.

axon the long process of a neuron that conducts nerve impulses, usually away from the cell body to the terminals which are the site of storage and release of neurotransmitter. *Compare* **dendrite**.

axonal transport the directed transport of organelles and molecules along the axon of a neuron. It can be anterograde (i.e. outwards from the cell body) or retrograde (i.e. towards the cell body).

axoneme the bundle of microtubules and associated proteins that forms the core of cilia and flagella in eukaryotic cells and is responsible for their movements.

axoplasm the cytoplasm of the axon of a neuron, especially after it has been extruded from the axon.

aza+ *prefix* **1** *(in systematic chemical nomenclature)* denoting the replacement of a designated carbon atom (together with one associated hydrogen atom) by a nitrogen atom. **2** *(in trivial chemical names)* denoting presence of one or more nitrogen atoms.

azaserine *trivial name for* serine diazoacetate; *O*-diazoacetyl-L-serine, $N_2{=}CH{-}CO{-}O{-}CH_2{-}CH(NH_2){-}COOH$; an antibiotic substance produced by *Streptomyces* spp. It is an inhibitor of amidotransferase enzymes and interferes with glutamine utilization in purine synthesis; it also retards the growth of transplantable animal neoplasms and is a specific inhibitor of L-glutamate ferredoxin oxidoreductase (transaminating), EC 1.4.7.1, in ammonium assimilation in plants.

azathioprine 6(1-methyl-4-nitro-5-imidazolyl) mercaptopurine: 6-[(1-methyl-4-nitroimidazol-5-yl)thio]purine; a derivative of **mercaptopurine**, into which it is converted *in vivo*. It is useful as an immunosuppressive and antimitotic agent. *One proprietary name*: Imuran.

azelaic acid 1,7-heptanedicarboxylic acid, nonanedioic acid; a substance that acts as a substitute for biotin in the growth of a number of microorganisms and is proposed as an intermediate in biotin biosynthesis from oleic acid.

azeotrope a mixture of two or more liquids that distils without change in composition and has a constant boiling temperature.

AZF *abbr. for* azoospermia factor; a protein whose deficiency is associated with the absence of living sperm in semen (azoospermia). It consists of 366 amino acids, encoded by a gene at Yq11. The N-terminal region contains an 85-residue sequence homologous to one in many proteins that bind RNA or single-stranded DNA, and its C-terminal region includes seven tandem repeats of a 27-residue sequence. Deletion of the locus accounts for ≈13% of infertile men with azoospermia.

azide **1** any organic compound containing the monovalent azido group, $-N{=}N^+{=}N^-$. **2** the ion N_3^-, derived from hydrazoic acid, HN_3. This ion blocks the electron transport chain by reacting with the ferric form of cytochrome aa_3 and thus acts as an inhibitor of respiration. **3** any salt or ester of hydrazoic acid.

azidothymidine *see* **AZT**.

azo the bivalent group –N=N–. It participates in noncyclic covalent linkage in organic molecules forming **azo compounds** or **diazo compounds**.

azocoll an insoluble bright-red collagen-rich proteinaceous material prepared by dyeing powdered cowhide or kangaroo-tail tendon with a dye prepared from tetrazolized benzidine, disodium 2-naphthol-3,6-disulfonate and sodium acetate. It is digested by most types of proteinase, the consequent solubilization of dye forming the basis of a simple nonspecific technique for the assay of proteolytic activity.

azo compound any organic compound with the general formula R–N=N–R'. Such compounds thus contain the bivalent azo group in covalent linkage, each nitrogen atom being linked to a carbon atom and replacing one hydrogen atom of each of the parent molecules RH and R'H. The latter may be the same or different, aliphatic or aromatic; e.g. azomethane, $CH_3{-}N{=}N{-}CH_3$; naphthalene-2-azobenzene, $C_{10}H_7{-}N{=}N{-}\ C_6H_5$. *Compare* **diazo compound**.

azoferredoxin *or* **protein II** *a former name for* **dinitrogenase reductase**.

azomethine strictly, any **imine** having the more limited general structure RR'C=NR where R and R' are any organyl groups, but often extended to include any compound where R' is H, the term then being considered to be synonymous with **Schiff base**.

azoospermia factor *see* **AZF**.

azoprotein any of the modified proteins formed by coupling an aromatic diazo compound to one or more of the tyrosine residues of a protein, e.g. azoalbumin, azocasein.

azotemia *former term for* the accumulation of abnormally large concentrations of nitrogenous compounds, especially urea, in the blood.

Azotobacter a genus of Gram-negative strictly aerobic soil bacteria, all members of which can effect **nitrogen fixation**.

azotoflavin a somewhat larger than normal **flavodoxin** that is believed to act as a one-electron carrier between ferredoxin and azoferredoxin during nitrogen fixation in some bacteria, e.g. *Azotobacter*.

AZT *abbr. for* azidothymidine; 3′-azido-3′-deoxythymidine; *other names*: zidovudine; Retrovir; an analogue of thymidine, the phosphorylated form of which is an inhibitor of **reverse transcriptase** in retroviruses; it also terminates DNA synthesis and depletes mitochondrial DNA. AZT undergoes phosphorylation in human T-cells to a nucleoside 5′-triphosphate, which competes with thymidine triphosphate and serves as a chain-terminating inhibitor of HIV reverse transcriptase. It is used clinically to treat patients with **HIV** infection and **AIDS**.

azurin any member of a group of brilliant-blue, copper-containing proteins of low M_r, found in some bacteria, and thought to transfer electrons to cytochrome oxidase.

azurocidin *or* **CAP37** a **serpocidin** of 37 kDa that acts as a cationic antimicrobial protein in neutrophil azurophil granules.

azurophil(e) *or* **azurophilic** a blue-staining lysosome of neutrophil leukocytes that also contains **serpocidins**.

azurophil(e) granule *or* **primary granule** a blue-staining lysosome of neutrophil leukocytes.

Bb

b *symbol for* **1** molality. **2** one of two van der Waals coefficients. **3** breadth.

B *symbol for* **1** boron. **2** a residue of either of the α-amino acids L-aspartic acid or L-asparagine when the state of amidation is uncertain (alternative to Asx). **3** a residue of an incompletely specified base in a nucleic acid sequence that may be cytosine or guanine or either thymine (in DNA) or uracil (in RNA). **4** the ribonucleoside (5-)bromouridine (alternative to BrUrd). **5** the B blood group. *See* **ABO system**.

B *symbol for* **1** Napierian absorbance (*see* **absorbance**). **2** magnetic flux density (bold italic).

-*B* conformational descriptor designating the boat conformation of a six-membered ring form of a monosaccharide or monosaccharide derivative. Locants of ring atoms that lie on the side of the structure's reference plane from which the numbering appears clockwise are indicated by superscripts preceding the letter, and those that lie on the other side of the reference plane by subscripts following the letter; e.g. methyl 2,6-anhydro-α-D-altropyranoside-$^{2,5}B$. *See also* **conformation** (under *cyclic compounds*).

$B_{\max}$ *symbol for* the amount of drug required to saturate a specific population of receptors in a membrane sample and hence an index of the density of receptor binding sites in the sample. It is usually derived from Scatchard analysis (*see* **Scatchard plot**) or from nonlinear regression analysis of data from a saturation binding assay.

Ba *symbol for* barium.

Baa helices *abbr. for* basic amphiphilic α helices; α helices that contain an array of basic amino-acid residues (His, Lys, or Arg) on one side and hydropathic residues on the other. They are found, e.g., in the calmodulin-binding regions of many proteins.

Babes–Ernst body *or* **Babes–Ernst granule** a **volutin granule** seen in *Corynebacterium diphtheriae*. [After Victor Babes (1854– 1926), Romanian bacteriologist, and Paul Ernst (1859–1937), German pathologist.]

BAC *abbr. for* bacterial artificial chromosome, based on the F factor (**F plasmid**) of *Escherichia coli*. *Compare* **YAC**.

BACE2 *abbr. for* beta-site APP-cleaving enzyme 2. *See* **secretase**.

Bacillaceae a family of eubacteria that includes the genera *Bacillus* and *Clostridium*.

bacillary *or* **bacillar** **1** of, relating to, caused by, or containing bacilli. **2** *an alternative term for* **bacilliform** (def. 1).

bacilliform **1** rod-shaped. **2** resembling a bacillus.

bacillus (*pl.* **bacilli**) any straight rod-shaped bacterial cell.

Bacillus a genus of large rod-shaped Gram-positive eubacteria belonging to the family Bacillaceae. Its members are aerobic or facultatively anaerobic, spore-bearing organisms. *B. subtilis* has become widely established as a vehicle for genetic engineering and many cloning **vectors** are available. *B. thuringiensis* synthesizes a toxin that is active against insects; different strains of the bacterium produce different forms of the toxin specific for different insect species.

bacitracin a cyclic antibiotic polypeptide complex produced by *Bacillus subtilis* and *B. licheniformis*. Commercial bacitracin is a mixture of at least nine bacitracins, mostly bacitracin A. Bacitracin A contains, in addition to several L amino acids, a number of D amino acids. Bacitracin inhibits bacterial cell wall synthesis by blocking the dephosphorylation of undecaprenyl diphosphate (undecaprenyl pyrophosphate) to the monophosphate form; it similarly inhibits the dephosphorylation of dolichyl diphosphate thereby blocking the formation of the core oligosaccharides of glycoproteins.

backbone **1** *(in biochemistry)* the sequence of bonded atoms of a polymer to which the side groups and/or the side chains are attached. **2** *(in zoology)* the vertebral column or spine.

backcross **1** any cross of a first-generation hybrid, F_1, with one parent or an individual genetically identical to one of the two parents. **2** the offspring of such a mating.

back-flush *an alternative term for* **back-wash**.

background any intrusive sound or electronic signal registered by a detector but not coming from the source being measured, e.g. the radioactivity registered by a counter in the absence of a radioactive sample.

back mutation *an alternative term for* **reverse mutation**.

back scattering *an alternative term for* **backward scattering**.

back titration an indirect titration procedure in which a measured excess of the reagent is added and the amount remaining after reaction with the analyte is titrated back to an end-point, the proportion consumed in the reaction being obtained by difference.

backward scattering *or* **back scattering** any scattering of radiation in a direction towards the source of the incident radiation.

back-wash *or* **back-flush** to pass a fluid through a chromatographic column in the direction opposite to that of the eluent flow. It is useful, e.g., to relieve bed-compression and to remove entrained gas.

baclofen γ-amino-β-(*p*-chlorophenyl)butyric acid; 3-(aminomethyl)-3-(4-chlorophenyl)propanoic acid; a 4-chlorophenyl derivative of γ-aminobutyric acid (GABA) that acts as a selective agonist for the **$GABA_B$ receptor** and inhibits the release of other neurotransmitters in the central nervous system. It is used for its antispastic (muscle-relaxing) effects.



bactenecin any of several highly cationic polypeptides, originally isolated from bovine neutrophil granules, but also found in sheep, that exert, *in vitro*, a potent antimicrobial activity, possibly owing to inhibition of respiratory chain function.

bacteremia *or (esp. Brit.)* **bacteraemia** the presence of live bacteria in the blood.

bacteria *plural of* **bacterium**.

Bacteria one of three superkingdoms (domains) of cellular organisms, the others being Archaea and Eukarya. Bacteria are unicellular and anucleate i.e. **prokaryotes**. They embrace a great diversity of forms, major divisions including the Cyanobacteria, Proteobacteria (which includes Gram-negative bacteria), and Gram-positive bacteria.

bacterial conjugation the process whereby genetic material is transferred from one bacterial cell (the donor) to another (the recipient). Material is usually transferred via a tubelike pilus, which extends from the donor cell to the recipient cell. The terms 'donor' and 'recipient' are preferred to 'male' and 'female' since the latter refer only to the presence or absence of **F plasmid**.

bacterial histone *see* **H-NS**.

bacterial/permeability-increasing protein *see* **BPI protein**.

bacterial photosynthetic reaction centre *see* **photosynthetic reaction centre**.

bacterial porin *see* **porin**.

bacterial recombinant *see* **transconjugant**.

bacterial virus *see* **bacteriophage**.

bactericide *or* **bacteriocide** any agent (biological, chemical, or physical) that destroys bacteria. **—bactericidal** *or* **bacteriocidal** *adj.*

bactericidin *or* **bacteriocidin** *or* **bacteriolysin** any antibody that, with **complement**, kills bacteria against which it is active.

bacteriochlorophyll any of the **chlorophylls** of photosynthetic bacteria. They differ structurally from the chlorophylls of higher plants. Bacteriochlorophylls *a* to *g* are known. Bacteriochlorophylls *a* and *b* are the best known, being the photosynthetic pigments of purple bacteria. Their purple colour results from the fact that they are reduced in both rings B and D, and thus may be regarded as tetrahydropyrroles. Tetrapyrrole carbon atoms and carbon rings are numbered according to the Fischer and IUPAC systems as indicated below. The structure of bacteriochlorophyll *a* is shown. Bacteriochlorophyll *b* has =CH–CH$_3$ in place of the ethyl group on ring B of bacteriochlorophyll *a*. In some bacteriochlorophylls *a* the phytyl group may be replaced by a geranylgeranyl group. Bacteriochlorophylls *c*, *d*, and *e* are antenna pigments of Chlorobiaceae, located in chlorobium vesicles (a core structure is shown). These are dihydropyrrole structures, being reduced in ring D only. The esterifying alcohol is farnesol. In these bacteriochlorophylls, the side chain R$_1$ (see core structure) on ring B varies, being ethyl, *n*-propyl, or isobutyl (in bacteriochlorophyll *d* neopentyl is also possible). On ring C the side chain R$_2$ is ethyl (in bacteriochlorophyll *d* methyl is also possible). R$_3$ is methyl in bacteriochlorophylls *c* and *e*, and H in bacteriochlorophyll *d*.



bacteriochlorophyll *c, d, e* core structure



bacteriochlorophyll *a*



tetrapyrrole carbon numbering Fischer system



tetrapyrrole carbon numbering IUPAC system

bacteriocide *a variant spelling of* **bactericide**.

bacteriocidin *a variant spelling of* **bactericidin**.

bacteriocin any of a heterogeneous group of polypeptide antibiotics that are secreted by certain bacterial strains, and are able to kill cells of other susceptible (frequently related) strains after adsorption at specific receptors on the cell surface. They include the colicins, and their mechanisms of action vary. Examples: colicin E1 from *Escherichia coli*; this is a channel-forming transmembrane protein that results in membrane depolarization; colicin E3 from *E. coli*; this is an rRNA ribonuclease; plantaricin A from *Lactobacillus plantarum*; this is a channel-forming peptide dimer of α and β chains; the amino-acid sequence of the β chain is:

AYSLQMGATAIKQVKKLFKKWGW

the α chain lacks the N-terminal A. —**bacteriocinogenic** *adj.*

bacteriocinogenic factor any **plasmid** that carries genetic information for the production of a **bacteriocin**. Generally only a small proportion of cells containing the factor actually produce bacteriocin. *See also* **col plasmid**.

bacterioferritin *abbr*: BFR; *other names:* cytochrome b$_1$ or cytochrome b$_{557}$; an iron-storage protein comprising 24 identical subunits that pack to form a symmetrical, near-spherical shell, surrounding an ~8 nm central cavity. There is close structural similarity between BFR and the iron-storage **ferritin** found in eukaryotes and bacteria. BFRs store large quantities of iron within their hollow interior (13–20% w/w of iron), in the form of a hydrated ferric oxide mineral containing variable amounts of phosphate anion.

bacteriology the branch of science that deals with the study of **bacteria**.

bacteriolysin *an alternative term for* **bactericidin**.

bacteriolysis the lysis of bacteria. —**bacteriolytic** *adj.*

bacteriophaeophytin *a variant spelling of* **bacteriopheophytin**.

bacteriophage *or* **phage** *or* **bacterial virus** any virus that can infect and multiply in a bacterium. Phages parasitize almost every group of prokaryotes. Commonly they consist of a core of nucleic acid enclosed within a protein coat, the capsid; additional components, e.g. lipid, occur in some phages. Depending on the type of phage, the nucleic acid may be either DNA (single-stranded or double-stranded) or RNA (single-stranded), and may be either linear or circular. Phages may be filamentous, polyhedral, or polyhedral and tailed; the tubular tails, to which one or more tubular tail fibres are attached in certain circumstances, are involved in attachment of the phages to the bacterial surface and for the injection of the DNA into the host cells. The smallest phages, e.g. φX174, are $\approx$25 nm in diameter, whereas tailed polyhedral phages, such as the **T-even phages**, are 200–250 nm long, while filamentous phages measure roughly 800 nm × 5 nm. In general, a given bacteriophage can infect only one particular species, or strain, or group of closely related strains, though a given strain may be susceptible to infection by a number of different phages. Bacteriophages can bring about **transduction** (def. 1) between bacterial cells. *Compare* **cyanophage**. *See also* **(bacterio)phage conversion**, **lysogeny**, **phage induction**, **phage typing**, **prophage**, **temperate phage**, **virulent phage**.

(bacterio)phage conversion *or* **prophage-mediated conversion** *or* **lysogenic conversion** the introduction of new properties to a host bacterium by the genome of an infecting lysogenic prophage. Such properties may include resistance to lysis by related phages, changes in antigenic constitution, or the appearance of toxigenicity.

bacteriophage vector *see* **cloning vector**.

bacteriopheophytin *or (esp. Brit.)* **bacteriophaeophytin** a **bacteriochlorophyll** in which Mg^{2+} is replaced by $2\ H^+$.

bacteriorhodopsin a retinal-containing protein, resembling animal **rhodopsin**, formed by *Halobacterium halobium* and other halophilic archaebacteria, and inserted into patches of **purple membrane** in the cell surface. The purple membranes serve as light-operated proton pumps to translocate protons from the inside to the outside of the cells. The mature protein is a **7TM protein** of known 3-D structure; until the structure of bovine rhodopsin was determined, this provided a model for the architecture of **opsin** and related G protein-coupled receptors in eukaryotic cells.

bacteriostatic *or* **bacteristatic** describing a drug, antibiotic, or other agent that inhibits the growth and multiplication of bacteria. *Compare* **bactericide**. —**bacteriostasis** *n.*

bacterium (*pl.* **bacteria**) any of a vast and ubiquitous group of prokaryotic microorganisms that exist as single cells or in clusters or aggregates of single cells. Most authorities now place them in the exclusively prokaryotic kingdom Monera, along with the **cyanobacteria** (blue-green algae). The majority of bacteria possess a rigid cell wall; those lacking this feature are termed **Archaea**. Bacteria, Archaea, and Eukarya constitute the three primary Kingdoms (domains). —**bacterial** *adj.*

Bacteroides a genus of Gram-negative anaerobic rodlike bacteria. Mostly nonmotile, they are commonly present in the alimentary and urogenital tracts of mammals and may behave as opportunistic pathogens.

bactoprenol *an alternative name for* **undecaprenol**.

Bactrim *see* **sulfamethoxazole**.

baculovirus any of a group of DNA viruses that are known to multiply only in invertebrates and are now classified in the family Baculoviridae. Their genome consists of double-stranded circular DNA of 58–100 MDa. Because of their host range they have potential as pest-control agents. Baculovirus vectors are valuable as a means of expressing certain animal proteins (*see* **expression system**).

BAF *abbr. for* B-cell activating factor (*see* **interleukin 1**).

bafilomycin A1 an extremely hydrophilic macrolide antibiotic secreted by *Streptomyces*. It interacts with and specifically inhibits vacuolar H^+ ATPases.

baicalein 5,6,7-trihydroxyflavone; a pigment (greenish-brown in dilute alkali) found in the root of *Scutellaria baicalensis*. It is a selective 12-lipoxygenase inhibitor. Baicalein inhibits leukotriene biosynthesis and cellular Ca^{2+} uptake and mobilization.



bait a hybrid protein containing the GAL4 DNA-binding domain, used in the **yeast two-hybrid system**. *See also* **bait region**.

bait region a restricted region in the sequence of **α_2-macroglobulin** (α_2M) that is cleaved by proteases in the process leading to the conformational changes instrumental in the protease inhibitory function of α_2M. The bait region occurs in all α-macroglobulins, but shows great variation in length and amino-acid sequence between different α-macroglobulins. In human α_2M, it covers approximately residues 666–706. Outside the bait region, α_2Ms from different species exhibit very high sequence similarity. *See also* **trap hypothesis**.

bakers' yeast any of various strains of the yeast *Saccharomyces cerevisiae* that are used in baking.

baking soda *see* **soda**.

BAL *abbr. for* British anti-lewisite (*see* **dimercaprol**).

balance 1 *(in physiology)* the relation between the intake of a particular nutrient and its excretion (or the excretion of its metabolites). **2** any instrument for determining the equality in mass of two objects (or sets of objects). In cases where one (set) is of known mass the mass of the second (set) is thus obtained; e.g. an analytical balance. **3** any instrument designed to measure the weight of an object, e.g. spring balance, torsion balance.

balanced growth a type of growth such that over a time interval (within the exponential phase) every extensive property of the growing system increases by the same factor. Balanced growth for an individual cell requires that each cell after division is an exact replica of the one of the previous cycle.

balanced salt solution any solution designed to provide a normal environment, in terms of ionic composition, pH, and osmotic pressure, for cells in tissue culture.

balance study any study to determine **balance** (def. 1).

balata *see* **rubber**.

BALB/c a strain of inbred white mice that readily develop experimental myelomatosis.

Balbiani ring a large **puff** of giant chromosomes present during a greater portion of larval development in members of the Diptera. The structural modification of specific loci is characteristically large and ring-shaped. [After Eduard Gérard Balbiani (1823–99), French entomologist who reported it in 1881.]

***Bal*I** a type 2 **restriction endonuclease**; recognition sequence: TGG↑CCA.

BAL 31 nuclease an exonuclease from *Alteromonas espejiana* used in making deletions by digestion from the ends of double-stranded DNA. It does not cleave DNA internally.

Baltimore classification a classification of animal viruses based on the nature of the genome and the mechanism for synthesis of mRNA, which is always regarded as the **plus strand** (def. 2). There are six classes:

Class I Viruses having a dsDNA genome that make mRNA by asymmetric transcription. In many, different mRNA species come from different DNA strands.

Class II Viruses having a ssDNA genome of the same polarity as the mRNA. Some have strands of both polarities in different particles.

Class III Viruses having a dsRNA genome that make mRNA by asymmetric transcription. Most have multiple pieces of dsRNA, each of which apparently contains the information for the synthesis of a single protein.

Class IV Viruses having an ssRNA genome that make mRNA of base sequence identical to the genomic RNA.

Class V Viruses having an ssRNA genome that make mRNA with a base sequence complementary to the genomic RNA.

Class VI **Retroviruses** having an ssRNA genome and a DNA intermediate in their growth. [After David Baltimore (1938–), US microbiologist and molecular biologist.]

***Bam*HI** a type 2 **restriction endonuclease**; recognition sequence: G↑GATCC. The M.*Bam*HI modification site is C5.

band 1 an **absorption band** in an electromagnetic spectrum. **2** a zone of (macro)molecules such as that obtained in density-gradient centrifugation, zone electrophoresis, isoelectric focusing, chromatography, or other similar method. **3** any of the zones readily distinguishable by microscopy in a **sarcomere** of a muscle. **4** the specific association of a large number of **chromomeres** at the same level in somatically paired **polytenic** giant chromosomes of members of the Diptera. *See also* **cytochrome absorption bands**.

band centrifugation *see* **isopycnic centrifugation**.

band compression inadequate separation of the bands on a gel electrophoretogram, especially in DNA sequencing gels. It results in poor resolution and difficulties in interpretation.

band electrophoresis *an alternative name for* **zone electrophoresis**.

banding the formation of distinct bands or zones in density-gradient centrifugation, column chromatography, or other separation techniques.

banding density the density of the suspending medium at which a particular type of particle, e.g. a cell organelle, forms a band during centrifugation in a specified density gradient.

band intensity *(in NMR spectrometry)* the area under the band between the signal trace and the baseline. *See* **nuclear magnetic resonance**.

band-pass filter 1 an electric circuit or other device that transmits only frequencies within a selected band. **2** an **interference filter**.

band protein erythrocyte proteins are referred to as bands, numbered according to the position they occupy on electrophoresis gels. Some of the more important bands are: 1 and 2, α and β **spectrin**; 3, an anion channel protein; 4.1, always referred to as such, involved in spectrin junctions; 5, **actin**.

band 3 protein *an alternative name for* **anion channel protein**.

band width *(in NMR spectrometry)* the distance between the sides of the band at half the band height of a reasonably smooth and symmetrical band. *See* **nuclear magnetic resonance**.

Bangasome *or* **Bangosome** *(colloquially) an alternative name for* **liposome**. [After its inventor, Alec Douglas Bangham (1921–), British biophysicist and medical scientist.]

***Ban*II** a type 2 **restriction endonuclease**; recognition sequence: G[AG]GC[TC]↑C. *Hgi*JII is an **isoschizomer**.

Bantu siderosis *see* **iron overload**.

BAPTA 1,2-bis(*o*-aminophenoxy)ethane-*N*,*N*,*N′*,*N′*-tetraacetate; a Ca^{2+} chelator exhibiting a 10^5-fold greater affinity (110 nM) than for Mg^{2+}. Its UV absorption maximum is at 254 nm which, after Ca^{2+} is bound, shifts to 279 nm, a property that can be exploited in its use as an indicator of intracellular Ca^{2+} concentration. Its esterified form can enter cells where it is hydrolysed to BAPTA.



bar a unit of pressure temporarily approved for use with SI units. 1 bar = 10^5 Pa = 10^5 Nm^{-2}.

barbed end *see* **plus end**.

barbital *or* **barbitone** 5,5-diethylbarbituric acid; 5-diethylmalonylurea; 5,5-diethyl-2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione; a long-acting depressant of the central nervous system, widely used as a buffer substance; pK_a = 7.98 (25°C), 8.06 (20°C). *One proprietary name*: Veronal.

barbiturate 1 the tautomeric anion derived from barbituric acid (malonylurea; 2,4,6(1*H*,3*H*,5*H*)-pyrimidinetrione). **2** any mixture of free barbituric acid and its anion. **3** any salt of barbituric acid. **4** any of various pharmacologically active derivatives of barbituric acid, including barbitone, pentobarbitone, phenobarbitone, and thiopentone. Barbiturates are potent CNS depressants that potentiate the actions of GABA by binding to the **GABA$_A$** receptor. Pentobarbitone and thiopentone are used to induce anesthesia.

Barcroft apparatus *or* **Barcroft respirometer** a differential respirometer for studying gas exchange of cells, tissue slices, or tissue homogenates, now rarely used. It is a closed system comprising two flasks of equal volume connected by a U-shaped manometer (the Barcroft manometer). In operation, both flasks contain the same volumes of liquid and gas; one, the reaction flask, contains the cells or tissue; the other, the compensation flask, is free from cells or tissue and serves to compensate for changes in temperature and barometric pressure during the course of an experiment. The respirometers are arranged so that they may be shaken with the flasks in a constant-temperature bath. The reading of the apparatus is the difference between the levels of the manometer fluid in the two sides of the manometer. [After Joseph Barcroft (1872–1947), British physiologist, who described it in 1908.]

BARD1 *abbr. for BRCA1*-associated ring domain protein; a protein homologous with ***BRCA1*** in its N- and C-terminal regions. It interacts with the RING finger of *BRCA1* and is localized with *BRCA1* in the nucleus during the S phase of the cell cycle.

Barfoed's reagent a solution containing cupric acetate in dilute acetic acid that is reduced when heated with monosaccharides but not with disaccharides or oligosaccharides. [After Christen Thomsen Barfoed (1815–99), Swedish physician.]

barn *symbol*: b; a unit of area temporarily accepted for use with the SI. It is equal to 10^{-28} m^2. It is used as a unit of atomic nuclear cross section.

barnase *or* **ribonuclease BA** a small extracellular endoribonuclease from *Bacillus amyloliquefaciens*. Its action involves formation of a 2′:3′-cyclic phosphate (*see* **ribonuclease**). It has been studied as a model for protein folding. The sequence and 3-D structure are known.

baroceptor *a variant spelling of* **baroreceptor**.

barometer an instrument for measuring the pressure of the atmosphere.

barometric pressure the pressure exerted by the atmosphere at a given place and time. It is often expressed in terms of the supported height of a column of mercury, usually measured in millimetres. The SI unit is the **pascal**. Other non-SI units frequently used in addition to the **millimetre of mercury** are the **atmosphere**, the **bar**, and the **torr**.

baroreceptor *or* **baroceptor** any physiological receptor that is sensitive to changes in pressure, especially the sensory nerve endings in the carotid sinus that set off nerve impulses in response to alterations in blood pressure at that point.

Barr body *see* **sex chromatin**. [After Murray Barr (1908–1995), Canadian anatomist.]

barrel *see* **beta-barrel**.

barrier an extracellular protein, probably a protease, excreted by yeast cells of mating type **a**. Its role may be to act as an antagonist of the α-type mating pheromone, and to establish optimal pheromone concentration for conjugation.

Barth syndrome *or* **3-methylglutaconic aciduria type II** an X-linked mitochondrial myopathy with cardiomyopathy, growth retardation, and leukopenia. There may also be 3-methylglutaconic aciduria but with normal 3-methylglutaconyl-CoA hydratase activity. There is marked decrease in tetralinoleylcardiolipin in skeletal and cardiac muscle and in platelets. It is caused by mutations in the gene for **tafazzin**.

barwin a barley seed protein (possibly a lectin) involved in defence mechanisms. It is closely related to the C-terminal domain of proteins encoded by wound-induced plant genes. It gives its name to a family of such proteins.

basal 1 at, of, or being a **base** (def. 4). **2** at, of, or being the minimum level for maintaining the normal or essential functioning of an organism.

basal body 1 *(in prokaryotes)* a structure that apparently attaches the **flagellum** (def. 1) to the cell envelope. The proximal end of the flagellum, the hook, appears curved and thickened and leads into the basal body, which consists of parallel ring-shaped structures, arranged around a rod-shaped core. The rings of the basal body make contact with the layers of the cell envelope. **2** *(in eukaryotes)* a structure at the base of a cilium consisting of spherical granules or short rods arranged in rows below the cell surface. Electron microscopically they are cylindrical bodies, 300–500 nm long and 120–150 nm in diameter, open at one or both ends. They consist of nine sets of triplet microtubules, each triplet containing one complete microtubule fused to two incomplete microtubules.

basal granule *an alternative term for* **basal body** (esp. in ciliated epithelium).

basal lamina a thin sheet of proteoglycans and glycoproteins, especially **laminin**, secreted by cells as an extracellular matrix, forming a region between the cells and adjacent connective tissue. The basal lamina has important functions in the organization of tissues including an influence on cell polarity, cell differentiation, and cell migration. The basal lamina is subdivided into the *lamina lucida* (an electron-lucent region) immediately adjacent to the cell layer, and the *lamina densa* (an electron-dense region) external to it. Frequently there is a further outermost layer, the *lamina reticularis*, containing collagen fibrils. The three laminae are often collectively referred to as the **basement membrane**.

basal medium any culture medium that will support the growth of nutritionally undemanding chemoorganotrophs.

basal metabolic rate *abbr*.: BMR; the rate of energy metabolism of an animal at rest but not asleep. It is measured with the animal in a 'comfortable' ambient temperature, and in the postabsorptive state, at least 12 hours after taking food. It may be determined from the oxygen consumption and carbon dioxide (and urinary nitrogen) excretion, or from the heat production of the animal.

basal metabolism the minimum amount of energy required to maintain life. *See* **basal metabolic rate**.

base 1 *(in chemistry)* **a** a **Brønsted–Lowry base**. **b** a **Lewis base**. *See also* **acid** (def. 2). **2** *(in molecular biology)* any purine or pyrimidine that occurs as a component residue in polynucleotides or nucleic acids. Purines and pyrimidines are **nitrogen bases**, hence the terminology. **3** a unit of length of a polynucleotide or nucleic acid, equal to one nucleotide residue. Large molecules are usually measured in kilobases (10^3 bases; *symbol*: kb) or megabases (10^6 bases; *symbol*: Mb). *See also* **nitrogenous base**. **4** *(in mathematics)* **a** the number of units in a system of counting that is equivalent to one unit in the next higher counting place. **b** the number that when raised to a specified power, its **exponent**, has a logarithm equal to the specified power. **5** the bottom or supporting part of anything; the point of attachment of an organ or part to an organism.

base analogue *or (esp. US)* **base analog** any unnatural purine or pyrimidine base that can be incorporated *in vivo* into DNA but that, because of its different properties, causes altered base-pairing during incorporation or in subsequent DNA replication. Thus 5-bromouracil, an analogue of thymine, pairs with guanine thereby causing transitions of A–T → G–C. Similarly, 2-aminopurine, an analogue of adenine, pairs with cytosine thereby causing transitions of A–T → G–C. Some base analogues have been used as anticancer and antivirus agents.

base calling the automated reading of DNA-sequencing gels using a scanner and appropriate software.

base composition the relative amounts of the various purines and pyrimidines occurring in a specimen of polynucleotide or nucleic acid. It is often expressed as moles percent.

base excision repair *see* **excision repair**.

baseline an imaginary line or a standard or reference value, etc. by means of which measurements may be compared, especially the zero line in the tracing of a chromatogram, spectrum, ultracentrifuge pattern, etc.

basement membrane a thin layer of dense material found in various animal tissues interposed between the cells and adjacent connective tissue. It consists of the **basal lamina**, composed mainly of a tightly cross-linked meshwork of type IV **collagen** molecules interwoven with a laminin network, to which it is bound by **entactin** molecules. The collagen molecules are glycosylated, made up of largely triple-helical combinations of α chains, which may be of six types: α-1(IV) to α-6(IV). There is also an associated layer of reticulin fibres. Occurring in, e.g., capillary linings, kidney tubules, lung alveoli, and renal glomeruli, basement membrane has a supportive function in some tissues and may also act as a passive selective filter for substances diffusing in or out of the cells; e.g. in renal glomeruli it retains protein molecules. It gives a strong periodic acid–Schiff reaction. *See* **Alport syndrome**.

base pair *symbol*: bp; any of the possible pairings between two bases in opposing strands of double-stranded DNA or RNA molecules. Adenine forms a base pair with thymine (in DNA) or uracil (in RNA) and guanine with cytosine, hence the number of adenine residues equals the number of thymine (and/or uracil) residues while the number of guanine residues equals that of the cytosine residues. *See also* **Chargaff's rules**. **—base-pair** *vb.*; **base-pairing** *n.*

base-pair ratio *see* **Chargaff's rules**.

base sequence the sequential order of nucleotide residues in a polynucleotide or nucleic acid molecule.

base stacking the arrangement of base pairs in parallel planes, at an angle to the helix axis, in the interior of a helical double-stranded polynucleotide or nucleic acid molecule.

base triplet any sequence of three bases in a nucleic acid that codes for an amino acid, or some other signal, in protein synthesis. *Compare* **anticodon**; **codon**.

basic 1 of, relating to, containing, or characteristic of a **base** (def. 1). *Compare* **acidic** (def. 1). **2** having an alkaline reaction; of or relating to an aqueous solution having a pH value >7.0. *Compare* **acidic** (def. 2).

basic amino acid any amino acid possessing a net positive charge at neutral pH.

basic azo-dye binding protein *abbr*.: B-ABP; a 45 kDa (Sephadex) protein, isolated from the soluble cell supernatant fraction from livers of rats given 4-dimethylaminoazobenzene. It was later named **ligandin**.

basic dissociation constant *or* **basicity constant** *symbol*: K_b; the thermodynamic dissociation constant for the dissociation of a **base** (def. 1, 2). For a dilute solution of a weak base, B, dissociating in water according to the equilibrium:

$$\mathrm{BOH} \rightleftharpoons \mathrm{B}^+ + \mathrm{OH}^-,\ K_b = a_{\mathrm{B}^+} \times a_{\mathrm{OH}^-} / a_{\mathrm{BOH}}$$

where *a* is the **activity** of the species designated by the subscripts. The activity of the water has been omitted from the equation since it may be taken as unity in dilute aqueous solution. K_b is a measure of the strength of a base, i.e. of its ability to accept hydrons from water (*compare* **acid dissociation constant**; *see also* **p*K***). The concept is no longer used since the conjugate acid, B^+, may be considered as an acid and an acid dissociation constant, K_a, for it defined. Also, in aqueous solutions

$$K_a \times K_b = [\mathrm{H}^+][\mathrm{OH}^-] = K_w,$$

where K_w is the ion product of water, whence K_b may be calculated from K_a or vice versa.

basic dye *or* **basic stain** any cationic dye that binds to, and hence stains, anionic macromolecules or other materials.

basic salt any salt containing hydroxyl or oxide groups in partial replacement of, or in addition to, ions or groups derived from an acid, e.g. basic lead acetate, $(CH_3COO)_2Pb{\bullet}Pb(OH)_2$.

basic stain *an alternative term for* **basic dye**.

basic zipper *see* **bZIP**.

basolateral surface the surface of an epithelial cell that adjoins underlying tissue. *Compare* **apical surface**.

basonuclin a **zinc finger** nuclear protein of epidermis, likely to be a transcription factor specific for squamous epithelium and its keratinocytes prior to terminal differentiation. It is present mainly in the nuclei of the basal cell layer.

basophil *or* **basophil(ic) leukocyte** a polymorphonuclear phagocytic leucocyte of the myeloid series that is distinguished by the presence of coarse cytoplasmic granules that stain with basic dyes. The granules are believed to contain histamine, heparin, and other vasoactive amines. Basophils are closely related to **mast cells** and constitute <0.5% of blood leukocytes.

basophilia 1 the property of being **basophilic**. **2** an increase in the number of **basophils** circulating in the blood.

basophilic staining readily with basic dyes.

basotropic seeking a basic environment; a term used especially in connection with protein kinases that have a requirement for basic residues near the target residue. *Compare* **acidotropic**.

bAT *abbr. for* basic amino acid transporter. *See* **cystinuria**.

batch a quantity of material produced or processed in one operation on a single occasion, as opposed to a continuous operation; hence batch adsorption, batch culture, etc.

batch elution a method of column chromatography in which conditions are chosen to ensure complete retention of the material under investigation, using the minimal amount of stationary phase, followed by elution with a solvent or buffer that ensures complete and rapid removal in the minimal possible volume.

batch process *(in biotechnology)* a process in which a bio-reactor is loaded with substrates inoculated with microorganisms or enzymes and allowed to run to completion, usually without removing biomass and products during the process.

bathochromic *(in absorption spectroscopy)* describing a shift of an absorption band in the direction of longer wavelengths. *Compare* **hypsochromic**.

batrachotoxin a steroidal alkaloid neurotoxin from the skin of Colombian arrow-poison frogs of genus *Phyllobates*. It is the most potent known venom. It binds specifically to the voltage-gated sodium channel and renders the membrane permeable to sodium ions. *Compare* **tetrodotoxin**, which reverses its depolarizing effect.



batroxobin *see* **venombin**.

battenin a protein of unknown function occurring in the membranes of lysosomes, mitochondria, nuclei, and synaptic vesicles. It consists of 438 amino acids, and is considered to contain 5–7 transmembrane segments. Some 20 mutations in the battenin locus at 16p12 are associated with Batten's disease (juvenile neuronal ceroid lipofuscinosis), an autosomal recessive neurodegenerative disease of childhood. This is characterized by the accumulation in lysosomes of storage bodies whose principal constituent is subunit c of mitochondrial ATPase. *See* **H$^+$-transporting ATP synthase**.

Batten's disease *see* **H$^+$-transporting ATP synthase**.

batyl alcohol 1-*O*-octadecyl-*sn*-glycerol; 3-octadecyloxy-1,2-propanediol; a hydrolysis product of **ether lipids**.

Bayesian statistics a statistical approach for estimating the probability of an observation given some prior knowledge or expectation. Bayesian statistics are often applied to the analysis of microarray data, phylogenetic tree data, evolutionary parameters, and so on, where they are used to estimate the likelihood (posterior probability) of a model being true given a particular data set, by estimating the probability of obtaining the data set if the model were true. [After Thomas Bayes (1702–61), English mathematician.]

bay region a concave exterior region, bordered by three phenyl rings, of a polycyclic aromatic hydrocarbon when an angularly fused terminal benzo-ring is present. For example, the sterically hindered area between carbon atoms 4 and 5 of phenanthrene, between carbon atoms 1 and 12 of benz[*a*]anthracene, or between carbon atoms 10 and 11 of benzo[*a*]pyrene. It has been suggested that dihydrodiol epoxides in the bay region of such compounds may be responsible for their mutagenicity and carcinogenicity. *See also* **A region**, **B region**, **K region**, **L region**.

***Bbe*I** a type 2 **restriction endonuclease**; recognition sequence: GGCGC↑C. *Nar*I is an **isoschizomer**.

BCAA *abbr. for* branched-chain amino acid.

B cell **1** *or (formerly)* **beta cell** the principal cell (60–80%) of the islets of Langerhans of the pancreas. It produces, stores (as B granules), and secretes the hormone **insulin**. **2** *an alternative name for* **B lymphocyte**.

B-cell activation factor *abbr*.: BAF; *an alternative term for* **interleukin 1**.

B-cell antigen receptor complex a complex consisting of membrane immunoglobulin associated non-covalently with two proteins known as mb-1 (*other names*: Igα, CD79a) and B29 (*other names*: Igβ, CD79b) that binds antigen and initiates B-cell transformation. mb-1 and B29 are often designated α and β respectively, and the complex consists of $Ig(\alpha\beta)_2$. Signalling occurs by activation of tyrosine kinases of the Src family (lyn, blk, fyn, or lck). α and β are themselves phosphorylated on activation. All five immunoglobulin isotypes (IgG, IgM, IgD, IgA, IgE) bind two α/β heterodimers and use a similar signalling pathway, but the glucosylation of the α chain differs according to the isotype with which it associates.

B-cell differentiation factor *abbr*.: BDF; *an alternative term for* **interleukin 1**.

BCG *abbr. for* bacille Calmette–Guérin; the bacillus from which is made a vaccine composed of live bovine-strain tubercle bacilli, *Mycobacterium bovis*, attenuated by long cultivation on a potato–glycerol–bile medium. [After Léon Charles Albert Calmette (1863–1933), French physician and bacteriologist, and Camille Guérin (1872–1961), French veterinary surgeon and bacteriologist, who described its preparation in 1908.]

B chromosome any of a heterogeneous group of accessory, extra, or supernumerary chromosomes found in many species of animals and plants. They differ from normal, or A chromosomes, by being usually smaller and frequently heterochromatic and telocentric, without great effect on the phenotype of their carriers. Both their numbers and their meiotic and mitotic behaviour are highly variable.

BCIP *abbr. for* 5-bromo-4-chloro-3-indolyl phosphate; a substrate for alkaline phosphatase. The soluble colourless 5-bromo-4-chloro-3-indolyl group is oxidized to give a purple-blue insoluble product. Redox coupling to the reduction of nitroblue tetrazolium (NBT) increases the sensitivity of detection.



BCKDH *abbr. for* branched-chain α-keto acid dehydrogenase.

Bcl a family of proteins that form pores in nuclear, endoplasmic reticulum, and outer mitochondrial membranes. Some members are antiapoptotic (e.g. Bcl-2, Bcl-XL) while others are proapoptotic. The structure of Bcl-XL is similar to that of the secreted bacterial pore-forming protein **colicin**. *See* ***BCL***.

BCL any of several genes associated with B-cell leukemia and lymphoma. *BCL1* is identical to the gene for human **cyclin** D1; its product activates $p34^{cdc2}$ kinase and is phosphorylated in G_1 of the cell cycle. *BCL2* is a protooncogene encoding a protein (locus at 18q21) that is localized to nuclear, endoplasmic reticulum, and outer mitochondrial membranes, and prolongs survival of hematopoietic cells; its product is able to block **apoptosis**, and if overexpressed with Myc counteracts the oncogenic action of Myc. Translocation of the enhancer region of the gene for Ig heavy chain constant region from14q32.33 to the *BCL* locus is associated with B-cell leukemias and lymphomas. *BCL2* proteins contain four homology regions each ≈18 residues long. *BCL3* encodes a probable transcription factor of the I-κB family.

***Bcn*I** a type 2 **restriction endonuclease**; recognition sequence: CC↑[CG]GG. *Cau*II is an **isoschizomer**.

BCR *abbr. for* breakpoint cluster region, a human gene (locus at 22q11.21) for a 160 kDa member of the family of protein serine/threonine kinases, widely expressed in human hematopoietic and other cell lines. *See also* ***abl***, **Philadelphia chromosome**.

BDF *abbr. for* B-cell differentiation factor interleukin (*see* **interleukin**).

B-DNA *abbr. for* B form of DNA.

BDNF *abbr. for* brain-derived neurotrophic factor.

Be *symbol for* beryllium.

Becker muscular dystrophy a mild form of Duchenne muscular dystrophy in which muscle **dystrophin** is reduced in amount or altered in structure by point mutations in the gene at Xp21.2. [After Peter Emil Becker (1908–2000), German geneticist.]

Beckmann thermometer a sensitive mercury-in-glass thermometer used for measuring small differences or changes of temperature. [After Ernst Otto Beckmann (1853–1923), German chemist.]

becquerel *symbol*: Bq; the SI derived unit of (radioactive) **activity** (def. 2) of a radionuclide; it corresponds to one **nuclear transformation** per second; i.e. 1 Bq = 1 disintegration s^{-1}. *See also* **curie**: 1 Ci = 3.7×10^{10} Bq or 1 Bq = 2.70×10^{-11} Ci. [After Antoine Henri Becquerel (1852–1908), French physicist.]

bed volume in column chromatography, the total volume of material, both solid and liquid, in the column; i.e. the volume of the support particles plus the **void volume**. It is synonymous with **column volume** for a packed column.

Beer–Lambert law *or* **Beer–Lambert–Bouguer law** *or* **Lambert–Beer law** a combination of **Beer's law** (def. 1) and **Lambert's law**; put into modern terms, it states that the **absorbance**, A, of a beam of collimated monochromatic radiation in a homogeneous isotropic medium is proportional to the absorption pathlength, l, and to the amount-of-substance concentration, c, (or, in the gas phase, to the pressure) of the absorbing species. The law may be expressed by the relations

$$A = \lg (\Phi_0/\Phi) = \varepsilon\, cl \text{ or } \Phi = \Phi_0 = 10^{-\varepsilon\, cl}$$

where Φ_0 and Φ are respectively the **spectral powers** of the incident and transmitted radiation beams, and the proportionality constant, ε, is the molar (decadic) absorption coefficient – *see* **absorption coefficient**.

Beer's law 1 *or (sometimes)* **Bouguer–Beer law**; a physical law extending **Bouger's law** to solutions: it states that when light passes through a given thickness of an absorbing solution of concentration c, the intensity of the transmitted light, I_{trs}, decreases exponentially as c increases linearly. It may be expressed as $I_{trs} = I_0\, e^{-kc}$, where I_0 is the intensity of the incident light and k is a constant. The law applies in practice only to monochromatic light (or other electromagnetic radiation) and when factors such as reflection or scattering are negligible or can be corrected for. *See also* **Beer–Lambert law**. **2** name commonly but incorrectly applied to **Beer–Lambert law** [After August Beer (1825–63), German physicist who formulated it in 1857.]

beet sugar *an alternative name for* **sucrose** when this has been extracted from sugar beet.

Beh *symbol for* the behenoyl group.

behenoyl *symbol*: Beh; *trivial name for* docosanoyl, $CH_3–[CH_2]_{20}–CO–$, the acyl group derived from the aliphatic acid behenic acid (= docosanoic acid), which occurs naturally in animal tissues and most seed fats.

bek a gene related to that for the **fibroblast growth factor** (FGF) receptor. Named after bacterial expressed kinase, it encodes a plasma membrane protein tyrosine kinase of class IV with an insert in the kinase region that binds FGFA with high affinity.

Bence-Jones protein any of a group of **myeloma proteins**, occurring in the urine of patients with multiple myelomatosis and related conditions, that precipitate on heating the urine to 60 °C, but redissolve at higher temperatures. They consist of light chains of **immunoglobulins** synthesized by the myeloma cells. [After Henry Bence-Jones (1813–73), English physician who described them in 1847.]

Benedict's solution a reagent used to test for the presence of glucose and other reducing sugars. When heated with reducing sugars it is reduced and a red precipitate of cuprous oxide is formed. There are separate formulations for qualitative and quantitative analysis. [After Stanley Rossiter Benedict (1884–1936), US biochemist.]

benign describing a neoplasm that is harmless, localized, and nonmetastasizing, although it may physically impede the function of a nerve or muscle.

bentonite a colloidal, native hydrated aluminium silicate clay consisting principally of montmorillonite, a complex aluminosilicate, $Al_2O_3 \bullet 4SiO_2 \bullet H_2O$, which has marked adsorptive properties. It is used as an inhibitor of nucleases and also in the **bentonite flocculation test**, a passive agglutination test in which antigen-coated bentonite particles are used to detect specific antibody.

benzidine *trivial name for* 4,4′-diaminobiphenyl, a substance that is carcinogenic for humans. It was formerly used in a highly sensitive test for the presence of blood, giving a green or blue colour in acetic acid solution on addition of hydrogen peroxide. Another former application was in the chromogenic assay of peroxidases. In view of the carcinogenicity, it has been replaced by **2,7-diaminofluorene** and other compounds.

benzo+ *or (sometimes before a vowel)* **benz+** *comb. form* **1** denoting the fusion of a benzene ring to a cyclic organic molecule. **2** indicating derivation from benzene or benzoic acid; *compare* **phenyl**.

benzoate 1,2-dioxygenase EC 1.14.12.10; *systematic name*: benzoate,NADH:oxygen oxidoreductase (1,2-hydroxylating, decarboxylating); *other name*: benzoate hydroxylase. A bacterial dioxygenase that is involved in the utilization of aromatic compounds. It catalyses a reaction between benzoate, NADH, and dioxygen to form catechol, CO_2, and NAD^+. Iron is a cofactor. In *Acinetobacter calcoaceticus* the enzyme comprises three subunits, two of which, α and β, represent the hydroxylase, while the third, γ, is an electron-transport flavoprotein. The β subunit is probably involved in substrate specificity, and the γ subunit is similar to ferredoxin reductase with 2Fe–2S motifs.

benzodiazepine *abbr*.: BZ; **1** 2*H*-1,4-benzodiazepine; a bicyclic compound consisting of a benzene ring fused to a seven-membered partially unsaturated ring containing two nitrogen atoms. **2** any member of a large class of pharmacologically active substances containing the benzodiazepine ring system. They are CNS depressants of low toxicity, having sedative and anxiolytic effects. A number are useful therapeutically; one of the most widely used is **diazepam** (*one proprietary name*: Valium). Specific high-affinity **benzodiazepine binding sites** are present in the CNS. They have been classified as BZ_1, primarily associated with anxiolytic effects, and BZ_2. It has been suggested that the effects of benzodiazepines are mediated through enhancement of the inhibitory action of GABA on the brain, and they are known to modulate the effects of GABA at **GABA$_A$ receptors**. Cloning studies of the $GABA_A$ receptor subunits have indicated that the γ subunit confers benzodiazepine sensitivity, and that the combination of different subunit types affects the receptor specificity, the presence of α1 subunits in the complex conferring BZ_1 pharmacology.



1*H* form

benzodiazepine inverse agonist a drug or other compound that binds to benzodiazepine receptors but has effects that are the opposite of those produced by a benzodiazepine agonist, i.e. it causes anxiety and convulsions.

benzoic acid *or* **benzene monocarboxylic acid** a white crystalline solid found naturally in plants and also used as a food preservative. In plants it is derived metabolically from phenylalanine. It accumulates (with salicylic acid), free and as a glycoside, in the immediate vicinity of infection sites. In animals and humans it is excreted in urine after conjugation to benzoylglycine (or hippuric acid) in the liver.

***o*-benzoquinone** 3,5-cyclohexadiene-1,2-dione; 1,2-benzoquinone; *o*-quinone. The oxidized form of **pyrocatechol**.

***p*-benzoquinone** 2,5-cyclohexadiene-1,4-dione; 1,4-benzoquinone; (*p*-)quinone. The oxidized form of **hydroquinone**. *See also* **quinhydrone**.

benzoyl *symbol*: Bz *or (preferably)* PhCO; the $C_6H_5–CO–$ group; the acyl group derived from benzoic (= benzenecarboxylic) acid.

benzyl *symbol*: Bzl *or (preferably)* $PhCH_2$; the $C_6H_5–CH_2–$ group; the alkyl group derived from benzyl alcohol (= benzenemethanol).

benzyloxycarbonyl *or (formerly)* **carbobenzoxy** *or* **carbobenzyloxy** *symbol*: Z *or* Cbz; the $C_6H_5–CH_2–O–CO–$ group, which is introduced into amino groups of peptides and proteins with reagents such as *N*-(benzyloxycarbonyloxy)succinimide.

beriberi a disease due to thiamine (vitamin B_1) deficiency and characterized by degenerative changes in the peripheral nerves, digestive system, and heart accompanied by edema.

Berkfeld filter a (candle) filter, made of diatomaceous earth, used to sterilize solutions. The pore size is relatively large and three porosities are graded V, N, and W (German *viel*, *normal*, and *wenig*) corresponding to coarse, normal, and fine. [After Wilhelm Berkefeld (1836–97), German chemist and manufacturer (the owner of the mine at Kieselguhr, where the earth was mined for production of the filter).]

Bernal chart a means of specifying the position of a spot on an X-ray diffraction photograph by two coordinates. [After John Desmond Bernal (1901–71), British crystallographer who described it in 1926.]

Bernard–Soulier syndrome *see* **von Willebrand factor**.

Bes *or* **BES** *abbr. for* 2-[bis(2-hydroxyethyl)amino]ethanesulfonic acid; a **Good buffer substance**, pK_a (20°C) = 7.15.

bestatin [(2*S*,3*R*)-3-amino-2-hydroxy-4-phenylbutanoyl]-L-leucine; an inhibitor of aminopeptidase B and leucine aminopeptidase with a variety of pharmacological functions. It is an inhibitor of enkephalin degradation in brain extracts, an anticarcinogenic agent, an immunomodulating agent, and an inhibitor of leukotriene-A_4 hydrolase.



bestrophin a protein of retinal pigment epithelium but with no known function. It comprises 585 amino acids, and contains four transmembrane segments. Numerous mutations of its gene locus at 11q13 are associated with Best macular dystrophy.

beta *symbol*: β (lower case) *or* B (upper case); the second letter of the Greek alphabet. For uses *see* **Appendix A**.

beta adrenergic *or* **β adrenergic** *see* **adrenergic**.

beta adrenoceptor *or* **β adrenoceptor** *see* **adrenoceptor**.

beta barrel *or* **β-barrel** a polypeptide super-secondary structure in which a single β-sheet folds back upon itself such that the first strand usually hydrogen-bonds to the last; such structures are found in both globular and membrane proteins.

beta-barrel porins members of a subclass of transport proteins of the TC system, designated 1.B. Their secondary structure is of the β-strand type, usually forming β-barrels. The subclass contains nearly 40 families, including general bacterial porins, alginate export porins, raffinose porins, two-partner secretion porins, secretins (not to be confused with the digestive hormone), and outer membrane factors. See also **porin**.

beta bend *or* **beta turn** *or* **β-bend** *or* **β-turn** a short stretch of polypeptide chain that allows the main direction of the chain to change. It consists of four amino-acid residues in which the CO group of residue *n* is hydrogen bonded to the NH group of residue *n* + 3. *See also* **reverse turn**.

beta blockade the process of inhibiting beta adrenoceptors with an antagonist.

beta blocker an antagonist of beta adrenoceptors.

beta carbon atom (*symbol*: Cβ) *or* **C-beta** the first carbon atom of an amino acid side chain, which is attached to the polypeptide chain via the main-chain **alpha carbon atom**.

beta cell *or* **β cell** *(formerly) an alternative name for* **B cell** (def. 1).

beta-cell tropin *or* **β-cell tropin** a peptide fraction obtained from the *pars intermedia* of mouse pituitary that stimulates insulin secretion by perfused rat pancreas or isolated pancreatic islets. It is immunochemically related to, but separable from, **corticotropin-like intermediary lobe peptide**.

betacellulin a potent mitogenic glycoprotein with EGF-like domains, purified from the conditioned medium of mouse pancreatic beta tumour cells, retinal pigment epithelial cells, and vascular smooth muscle cells. It may play a role in the vascular complications associated with diabetes. The C-terminal region shares 50% similarity with rat **transforming growth factor** α. The precursor is a type I **membrane protein**, and the mature form is a secretory protein.

beta conformation *or* **β-conformation** a stable conformation of a polypeptide chain in which the chain is almost fully extended, but slightly puckered; the **torsion angle** of N-Cα-C-N in the backbone is about 120°, causing the side-chains of neighbouring residues to project in opposite directions from the backbone. Adjacent polypeptide chains may hydrogen bond, forming a **beta sheet**, the axial distance between adjacent amino-acid residues being ~0.35 nm; the chains may be either **parallel** (running in the same direction) or **antiparallel** (running in opposite directions).

betacyanin *see* **betalain**.

beta decay *or* **β decay** decay of a radionuclide by the emission of a **beta particle**.

beta emitter *or* **β emitter** any nuclide that emits either positive or negative beta particles.

beta globulin *or* **β globulin** any of a diverse group of **plasma proteins**, including lipoproteins and transferrin, that migrate slower than the **alpha globulins** during electrophoresis at slightly alkaline pH values.

betaglycan a cell-surface single-pass transmembrane protein that contains covalently bound chondroitin sulfate and heparan sulfate chains. It acts as a coreceptor for **transforming growth factor** β (TGFβ).

beta granin *or* **β granin** *see* **chromogranins**.

beta granule *an alternative name for* **B granule**.

beta helix *or* **β-helix** a polypeptide conformation in which a serial linkage of β-strands, connected via loop regions, coils into a wide helix. In a simple two-sheet β helix, each turn of helix contains two strands and two loops. In extracellular bacterial proteases, this simple unit is repeated three times, forming a right-handed, coiled structure comprising two adjacent three-stranded parallel β-sheets, enclosing a hydrophobic core. A more complex β-helical structure arises when the repeat unit is three short strands separated by loop regions, giving rise to a helix in which three parallel β-sheets are arranged such that two of the sheets are parallel to each other and perpendicular to the third; this structure was first seen in pectate lyase.

beta hemolysis *or* **β hemolysis** a type of hemolysis, characteristic of certain strains of streptococci, in which a clear zone is formed around the bacterial colonies when cultured on a blood agar plate. *Compare* **alpha hemolysis**.

betaine the *N*-trimethyl derivative of an amino acid; the term originally denoted **N-trimethylglycine**, now called **glycine betaine**. Glycine betaine acts as a methyl-group donor in some reactions; *see*, e.g., **betaine–homocysteine S-methyltransferase**.

betaine-aldehyde dehydrogenase EC 1.2.1.8; an enzyme involved in the formation of **betaine**. It catalyses the reaction:

$$\text{betaine aldehyde} + NAD^+ + H_2O = \text{betaine} + NADH.$$

betaine–homocysteine *S*-methyltransferase EC 2.1.1.5; an enzyme that catalyses the reaction:

trimethylammonioacetate (glycine **betaine**) +
L-homocysteine = dimethylglycine + L-methionine.

beta lactoglobulin *or* **β lactoglobulin** the principal protein of the whey of ruminants' milk, in which it constitutes 50–60% of the protein content. It has an M_r of ~40 000, and an isoelectric point of 5.2. Its function is unknown, but it binds retinol, and belongs to the family of transport proteins, known as **lipocalins**, that bind small hydrophobic molecules. *See also* **lactalbumin** (def. 1).

betalain any of a group of coloured alkaloids occurring widely in plants of the order Centrospermae. They are divided into two groups, **betacyanins** and **betaxanthins**, and both occur in plant vacuoles. The former impart a red-violet colour and the latter a yellow colour to the plant organs that contain them.

beta lipoprotein *or* **β lipoprotein** any of the plasma lipoproteins that behave electrophoretically as **beta globulins**, but normally designated **low-density lipoprotein**. *See also* **plasma protein**.

beta oxidation *or* **β oxidation** the metabolic oxidation of a long-chain fatty acid by successive cycles of reactions during each of which the fatty acid is shortened by a two-carbon-atom fragment removed as acetyl coenzyme A. The name derives from the fact that the *β*-carbon atom is the point of oxidation. *See also* **beta-oxidation system**, **Knoop's hypothesis**.

beta-oxidation system a mitochondrial complex that carries out the reactions of beta oxidation. It contains enzymes that fall into the following four categories:

(1) Acyl-CoA dehydrogenases. See **acyl-CoA dehydrogenase**.

(2) **enoyl-CoA hydratase** EC 4.2.1.17; this catalyses a reaction forming (3*S*)-3-hydroxyacyl-CoA from *trans*-2(or 3)-enoyl-CoA, hydrating the double bond introduced by the enzymes in category 1. It is a homohexamer and a mitochondrial matrix protein.

(3) **3-hydroxyacyl-CoA dehydrogenase** EC 1.1.1.35; this catalyses the oxidation of (3*S*)-3-hydroxyacyl-CoA by NAD^+ to 3-oxoacyl-CoA with formation of NADH. It is a homodimer and mitochondrial matrix protein.

(4) **3-ketoacyl-CoA thiolase** (*see* **thiolase**). This is a homotetramer and a mitochondrial protein.

beta particle *or* **β particle** either a (negatively charged) electron or a (positively charged) positron emitted in the **transformation** (def. 5) of a radionuclide.

beta-pleated sheet *or* **β-pleated sheet** *another name for* **beta sheet.**

beta propeller a toroidal arrangement, present in some proteins, that is made up of seven conserved repeats each of ≈60 residues that form seven beta sheets around a central axis so as to resemble a propeller. Each beta sheet contains four antiparallel beta strands. *See* **glycoprotein IIb/IIIa**.

beta radiation *or* **β radiation** an emission of **beta particles**.

beta receptor *or* **β receptor** *see* **adrenoceptor**.

beta sheet *or* **β-sheet** *or* **β-pleated sheet** an approximately planar array of two or more adjacent **beta strands** such that hydrogen bonds may be formed between C=O groups of one β-strand and NH groups of another. *See also* **beta conformation.**

beta strand *or* **β-strand** one of the two basic elements of the **secondary structure** adopted by a polypeptide chain of a protein (*see also* **alpha helix**). It consists of a single chain in a **beta conformation**. Two or more strands may interact to form a **beta sheet**.

beta structure *or* **β-structure** any part of the structure of a protein molecule consisting of one or more β-strands.

beta turn *or* **β turn** *an alternative name for* **beta bend**.

betaxanthin *see* **betalain**.

beticolin any of a family of eight nonpeptidic channel-forming toxins produced by the fungus *Cercospora beticola*. The structure of beticolin 2 is naphtho[2′,3′:1,2]cyclohepta[5,6-c]xanthene-14a-acetate. It is classified in the TC system under number 1.D.7.

B form of DNA *abbr*.: B-DNA *or* DNA-B; the molecular conformation adopted by fibres of the sodium salt of duplex DNA at high relative humidity and in aqueous solution. It consists of a right-handed double helix containing about ten nucleotide residues per turn with the planes of the base pairs normal to the axis of the helix. It is the basis of the **Watson–Crick model of DNA**, and is thought to resemble the conformation of most of the DNA *in vivo. See also* **A form** (def. 1), **C form**, **Z form**.

B/F ratio *abbr. for* bound-to-free ratio (in ligand binding). A plot of the B/F ratio versus the concentration of free ligand is known as a **Scatchard plot**.

BGG *abbr. for* bovine gamma globulin; the component of bovine serum represented by fraction II of a **Cohn fractionation**.

***Bgl*I** a type 2 **restriction endonuclease**; recognition sequence: GCCNNNN↑NGG.

***Bgl*II** a type 2 **restriction endonuclease**; recognition sequence: CCCN$_1$↑NNN$_2$NGGC, in which N$_1$ and N$_2$ are complementary.

B granule *or* **beta granule** any of very numerous membrane-bound vesicles (granules) containing stored insulin that are found in the **B cells** of the pancreatic islets. The granules stain a deep bluish purple with Gomori's aldehyde fuchsin and Ponceau stain.

bhang *see* **cannabis**.

BHK cell *abbr. for* baby hamster kidney cell; a cultured cell derived from this organ.

BHT *abbr. for* butylated hydroxytoluene, di-*tert*-butyl-*p*-cresol, an **antioxidant**.

bi+ 1 *comb. form* meaning two, twice, or double. **2** *prefix* (in organic chemical nomenclature) indicating two identical groups or rings joined by a link; e.g. biacetyl, biphenyl. **3** *prefix* (in inorganic chemical nomenclature) signifying an acid salt of a dibasic acid; e.g. sodium bicarbonate (though now more correctly termed sodium hydrogencarbonate). **4** *(in enzymology)* denoting two kinetically important substrates and/or products of an enzymic reaction (*see* **reactancy of enzymes**). *See also* **bis+**, **di+**.

Bi *symbol for* bismuth.

BIAcore *proprietary name* of an optical biosensor instrument that measures real-time interactions of macromolecules using **surface plasmon resonance**. Ligands are immobilized on a dextran-coated gold surface. The resulting 'sensorgrams' can be used to derive kinetic parameters of the interactions.

bialaphos a linear tripeptide produced as a secondary metabolite by *Streptomyces hygroscopicus*. The structure is PT-Ala-Ala, where PT is the glutamate analog, phosphinothricin. After hydrolysis of bialaphos by intracellular nonspecific peptidases, PT acts as an inhibitor of **glutamate-ammonia ligase** (glutamine synthetase), and thereby derives herbicide and antibiotic activities.



Bial's test a colorimetric test for aldopentoses. *See* **orcinol test**. [After Manfred Bial (1870–1908), German physician.]

bibliographic database a database that houses bibliographic information, primarily in the form of citations, controlled vocabulary terms, index codes and abstracts. Examples include MEDLINE, which covers the worldwide biomedical literature; EMBASE Excerpta Medica, which covers the worldwide biomedical and pharmaceutical literature; and PASCAL, which covers the major international literature on science, technology and medicine.

bibrotoxin a vasoconstrictor peptide of the **endothelin/sarafotoxin** family, isolated from the venom of the burrowing wasp *Atractaspis bibroni*. The sequence,

CSCADMTDKECLYFCHQDVIW,

is identical to that of sarafotoxin B except that Ala^4 replaces Lys^4.

bicarbonate the HCO_3^- ion; now more correctly termed hydrogencarbonate.

bichromatic analysis a term sometimes used to describe any analytical method involving observation at two wavelengths.

Bicine *or* **BICINE** *abbr. for N*,*N*-bis(2-hydroxyethyl)glycine; a **Good buffer substance**; pK_a (20 °C) = 8.35.

bicoid protein a segment-polarity protein, discovered in *Drosophila*, that provides positional cues for the development of head and thoracic segments. It regulates the expression of zygotic genes, possibly through its **homeodomain**, and inhibits the activity of other maternal gene products. It forms an anterior–posterior gradient in the embryo, and acts as a transcriptional activator. It binds to *caudal* mRNA. It shares similarity with other **paired**-type homeobox proteins.

bicuculline 6-(5,6,7,8-tetrahydro-6-methyl-1,3-dioxolo[4,5-*g*]isoquinolin-5-yl)furo[3,4-*e*]-1,3-benzodioxol-8(6*H*)-one; a naturally occurring alkaloid with several sources, including *Dicentra cucullaria* and *Adlumia fungosa*. It is a potent convulsant with effects probably mediated by its GABA antagonist activity at **GABA$_A$ receptors**.



bidentate 1 having two teeth or two toothlike processes. **2** describing a **ligand** molecule that chelates a metal ion by means of two donor atoms.

bifunctional having two functions.

bifunctional antibody an antibody having two combining sites for antigen.

bifunctional catalyst a catalyst that provides both acidic and basic catalytic functions.

bifunctional reagent a compound with two reactive functional groups that can interact with two groups in one molecule or with one group in each of two different molecules.

big-big gastrin *or* **big gastrin** *see* **gastrin**.

BigCHAP *N*,*N*-bis(3-D-gluconamidopropyl)cholamide; a nonionic detergent analogue of **CHAPS**, but with reduced electrostatic properties; aggregation number 10, CMC 3.4 mM.



BigDye terminator *a proprietary name for* reagents used in DNA sequencing in which the dideoxynucleoside triphosphates are each labelled with a different fluorescent dye to facilitate their identification when the products of sequencing reactions are separated by gel or by capillary electrophoresis.

big gastrin *see* **gastrin**.

big glucagon *or* **big plasma glucagon** material that is separable from normal human plasma and shows glucagon-like immunoreactivity. It has an estimated M_r of 160 000.

biglycan bone and cartilage proteoglycan I precursor; a connective tissue glycoprotein of the extracellular matrix related to **decorin** and fibromodulin.

bijou bottle a small glass screw-capped bottle of 5–7 ml capacity, used especially for liquid and solid cultures.

bikunin a plasma glycoprotein found both in the free state and complexed with the heavy chains of the inter-α-inhibitor family, forming the light chain. It is a serine protease inhibitor, having a tandem arrangement of Kunitz domains; it may participate in the control of events such as endothelial cell growth, and oocyte cumulus expansion and stabilization. It is synthesized from an α_1-microglobulin/bikunin precursor.

biladiene *the semisystematic name for* either of two linear tetrapyrroles in which the carbon bridges contain two more double bonds than **bilane** i.e. two of the three carbon bridges in the molecule are methine groups.

bilamellar having two **lamellae**; formed of two plates.

bilane *the systematic name for* a linear tetrapyrrole in which each of the three carbon bridges linking the pyrrole nuclei is saturated, i.e. is a methylene group, and in which, unless otherwise specified, each of the four nitrogen atoms also is saturated. It is the fundamental structure for the naming of linear tetrapyrroles, is defined without oxygen substituents, and is numbered (omitting C_{20}) to agree with the numbering of the unsubstituted porphyrin ring system. *Trivial name*: bilinogen.



bilatriene *an alternative (less-favoured) name for* **bilin**.

bilayer a layer that is two molecules thick, as in some membranes. *See* **lipid bilayer**, **unit membrane**.

bilayer lipid membrane *see* **black lipid membrane**.

bile a secretion produced by the vertebrate liver and conveyed through the bile duct to the duodenum. Its alkaline nature helps to neutralize acidic gastric secretions passing from the stomach, and the **bile salts** it contains are involved in the digestion of fat. Bile also serves as a medium for the excretion of various substances, notably cholesterol (either as such or in the form of bile salts to which it is converted), pigments (from hemoglobin breakdown), heavy metals, and other waste products (usually of >400 Da).

bile acid any member of a group of steroid carboxylic acids occurring in bile, where they are present as the sodium salts of their amides with glycine or taurine (*see* **bile salt**). The C_{24} acids are hydroxy or keto derivatives of cholanic or allocholanic acids; some C_{27} bile acids are known in eutherian mammals. In mammals, the C_{24} acids are found conjugated with glycine (*see* **glycocholate**) as well as with taurine (*see* **taurocholate**); in other animals only taurine conjugates have been found. Bile acids play an important role as emulsifiers in digestion and absorption of dietary lipids. In human adults 30 g are excreted daily, most of which are reabsorbed by an Na^+-dependent active-transport glycoprotein (locus on chromosome 14 encodes 349 residues) with several transmembrane segments. *See* **enterohepatic circulation**.

bile acid receptor *see* **farnesoid X receptor**.

bile alcohol any of a group of polyhydroxy derivatives of **cholestane**, present as their sulfuric acid esters in the bile of amphibians and some fishes.

bilene *the semisystematic name for* either of two tetrapyrroles in which the carbon bridges contain one more double bond than **bilane**; i.e. one of the three bridges in the molecule is a methine group.

bile pigment any bilirubinoid pigment present in bile; i.e. any linear tetrapyrrole derived from a **porphyrin** (which is a cyclic tetrapyrrole). For physiological reasons certain dipyrroles are also sometimes regarded as bile pigments.

bile salt the sodium salt of the conjugate of any **bile acid** with either glycine or taurine. Bile salts are potent surfactants; in the gut they emulsify ingested lipid, promote its hydrolysis by the activation of lipases, and facilitate its absorption, thereafter being excreted in the feces. *See also* **glycocholate**, **taurocholate**.

biliary of or relating to **bile**.

bilin 1 *the systematic name for* the linear tetrapyrrole in which the carbon bridges contain three more double bonds than **bilane**; i.e. all three bridges are methine groups. This name is preferred to bilatriene. **2** any coloured **bile pigment** formed by the oxidation of a colourless bile pigment, or **bilinogen** (def. 2). Thus the bilinogens urobilinogen and stercobilinogen form urobilin and stercobilin, respectively, on oxidation.

bilinogen 1 *trivial name for* bilane. **2** any colourless **bile pigment** that may be oxidized to a coloured bile pigment (*see* **bilin** (def. 2)).

biliprotein *an alternative name for* **phycobiliprotein**.

bilirubin *or (formerly)* **bilirubin IXα** *the recommended trivial name for* the linear tetrapyrrole 8,12-bis(2-carboxyethyl)-2,7,13,17-tetramethyl-3,18-divinylbiladiene-*ac*-1,19(21*H*,24*H*)-dione. It is produced in the reticuloendothelial system by the reduction of **biliverdin** and transported to the liver as a complex with serum albumin. The liver produces bilirubin from hepatic heme proteins and renders it water-soluble by conjugation of the carboxyethyl side-chains to form bilirubin bisglucuronide, most of which is excreted in the bile by an ABC-transporter called canalicular multiorganic anion transporter (or cMOAT). Bilirubin accumulates in the blood and tissues in jaundice, which may arise from acquired or hereditary causes. Unconjugated bilirubin is toxic to parts of the brain and is associated with kernicterus. *See* **Dubin–Johnson syndrome**.



bilirubin oxidase EC 1.3.3.5; an enzyme that catalyses the oxidation by dioxygen of bilirubin to biliverdin and H_2O.

biliverdin *or (formerly)* **biliverdin IXα** *the recommended trivial name for* the linear tetrapyrrole 8,12-bis(2-carboxyethyl)-2,7,13,17-tetramethyl-3,18-divinylbilin-1,19(21*H*,24*H*)-dione. It is formed in the reticuloendothelial system and in hepatocytes by the first step in heme degradation, catalysed by heme oxygenase (decyclizing), EC 1.14.99.3, a reaction in which the α-methene group of heme is oxidized to carbon monoxide. Biliverdin is then reduced by biliverdin reductase, EC 1.3.1.24, to **bilirubin**.



biliverdin reductase EC 1.3.1.24; an enzyme that catalyses the reaction of bilirubin with $NAD(P)^+$ to form biliverdin and NAD(P)H.

bimodal *(in statistics)* distribution with two **modes**.

bimolecular having a **molecularity** of two; relating to, consisting of, or involving two molecular entities.

bimolecular layer a layer that is two molecules thick.

bimolecular reaction any chemical reaction in which there is a transition state composed of the atoms of two separate molecular entities, which may be the same or different.

binal double; twofold.

binary 1 consisting of or forming two things or parts; dual. **2** describing a number system having the numeral 2 as its **base** (def. 4b). *See also* **bit**.

binary compound a compound consisting of only two chemical elements; e.g. ammonia, sodium chloride, water.

binary digit *see* **bit**.

binary fission the reproduction of a living cell by division into two equal, or near-equal, parts.

binary operator any arithmetic or logical operator (e.g. +, AND, OR) that operates on two quantities.

binary representation a notation by which **alphanumeric** symbols are represented by two digits, 0 and 1, in a known sequence. The displacement of one digit position to the left denotes multiplication by a power of 2.

BIND *abbr. for* biomolecular interaction network database; *see* **pathway database**.

binder protein I *see* **cortisol metabolite binding protein (large)**.

bindin a protein of 285 amino acids, M_r 35 000, extracted from the insoluble granular material of sea-urchin sperm, responsible for the attachment of the sperm to the vitelline layer of the egg. Bindins may mediate the species-specific recognition of eggs by sperm. *See also* **spermadhesin**, **zona pellucida sperm-binding protein**.

binding the act or process by which one molecule attaches to another by noncovalent forces; ligation *see* **ligate** (def. 3). *See* **ligand**. *See also* **binding site**.

binding assay *an alternative term for* **saturation analysis**.

binding capacity a measure of the quantity of ligand or the number of ligand molecules that can be bound by a given amount of a particular binding agent or system.

binding constant *an alternative term for* **affinity constant**.

binding curve any graphical representation of the extent of binding between two compounds at varying relative concentrations of the reactants.

binding energy the free energy change accompanying the binding of n_i ligand molecules to a macromolecule to produce a particular configuration of the liganded macromolecule.

binding fraction *an alternative term for* **saturation fraction**.

binding potential *symbol*: Π; a concept introduced to clarify the definition of linked functions, linkage groups, and linked sites in ligand binding. It is defined by: $\nu_i = \delta\Pi/\delta\mu_i$ where ν_i is the ratio of component *i* to that of a reference component and μ_i is the chemical potential of *i*.

binding protein *abbr.*: BiP; a **luminal protein** of the endoplasmic reticulum that is a member of the hsp70 family of **heat-shock proteins**, and is a typical **molecular chaperone**. It recognizes incorrectly-folded proteins, as well as protein subunits that have not yet assembled into their oligomeric complexes, and facilitates their oligomerization and folding. BiP activity requires the participation of ATP, which is hydrolysed to ADP and inorganic phosphate.

binding set the spatially organized collection of all the groups or residues of *one* protomer that are involved in its binding to *one* other protomer.

binding site a specific region in a macromolecule or other molecular entity, or in a membrane, that takes part directly in the combination with a **ligand**. Binding sites may be independent or interacting, depending on whether or not the binding of one ligand to one site affects the binding of other ligands to other sites on the same macromolecule, or membrane. *See also* **cooperative ligand binding**.

binomial 1 a mathematical expression made up of two terms, e.g. $2x + 5y$. **2** a two-part taxonomic name (*see* **binomial nomenclature**).

binomial coefficient the coefficient of any term arising from the expansion of the algebraic binomial $(a + b)^n$.

binomial distribution a statistical function in which the probabilities that an event will or will not occur are given by the successive coefficients of a binomial expansion of the form $(a + b)^n$, where *a* and *b* are the probabilities that an event will and will not occur, respectively.

binomial nomenclature a system of naming organisms, devised by the Swedish botanist Carolus Linnaeus (1707–78), that employs two Latin names, the first being the genus and the second the species to which the organism belongs.

binuclear *an alternative term for* **dinuclear**.

bio+ *comb. form* denoting life or living organisms, or systems derived from them.

bioaccumulation a progressive increase in the amount of a substance in an organism or part of an organism that occurs because the rate of intake exceeds the organism's ability to remove the substance.

bioactivation the activation of a drug or other substance in an organism or by means of a biological or biochemical system.

bioactive *an alternative term for* **biologically active**.

bioanalytical of or pertaining to biochemical analysis.

bioassay *or* **biological assay** any quantitative estimation of biologically active substances by measurement of the magnitude of their actions on living organisms or parts of organisms. It is performed under standard conditions and by reference to preparations of defined potency or activity.

bioautograph the record obtained in **bioautography**.

bioautography a method for detecting, in a complex mixture, small amounts of substances that are able to act as essential growth factors for a test organism(s). The components of the mixture are first separated by chromatography. The resulting chromatogram is then placed in contact with a culture of the test organism in a solid medium lacking a specific component. Hence, the organism will only grow where the component is present in the chromatogram, thereby establishing its presence in the original mixture.

bioavailability **1** the relative amount of the dose of a drug or other substance reaching the systemic circulation. **2** the rate and extent to which the therapeutic moiety of a drug is absorbed and becomes available to the site of drug action.

bioblast any very small mass of protoplasm having formative powers, formerly considered to be the ultimate elementary living particles; it is now thought the particles seen may have been **mitochondria**.

biocatalyst any agent, present in or obtained from living material, that can increase the rate at which a chemical reaction occurs without itself undergoing permanent change; a biological or biochemical **catalyst**. Biocatalysts are commonly **enzymes**. *See also* **ribozyme**. —**biocatalysis** *n.*

biochemical **1** of or pertaining to **biochemistry**. **2** any chemical substance occurring in or isolated from an organism.

biochemical engineering *or* **bioengineering** the scientific discipline underlying the industrial processing of biological materials, e.g. fermentation-based pharmaceuticals, foods, and effluents.

biochemical evolution the evolution of the biochemical processes and components of living organisms, such as the structure and function of biologically important molecules, metabolic pathways, subcellular structures, and cells.

biochemical genetics the branch of genetics concerned with the chemical nature of hereditary determinants and how they function at the molecular level.

biochemical imprinting the adaptive increase in enzyme activities that can occur along specified metabolic pathways when there is a large and sustained traffic through them.

biochemical lesion any biochemical change, such as the absence or inactivation of an enzyme, that diminishes the fitness of an organism or leads to a pathological condition.

biochemical marker any specific character that may be detected by a biochemical test, e.g. the presence or absence of a particular enzyme.

biochemical oxygen demand *or* **biological oxygen demand** *abbr.*: BOD; a measure of pollution of water in lakes, rivers, etc. due to the presence of organic matter. Oxidation of the latter by microorganisms removes dissolved oxygen, hence reducing the ability of the water to sustain aquatic life. BOD is the amount of oxygen (mg) taken up by a 1-litre sample of water in 5 days (BOD$_5$) at 20°C in the dark; it may be necessary to add additional, uncontaminated, water to augment the amount of oxygen available. Sometimes incubation is for a longer time, e.g. 20 days, in which case it is indicated by BOD$_{20}$. *Compare* **chemical oxygen demand**.

biochemistry *or* **biological chemistry** the branch of science dealing with the chemical compounds, reactions, and other processes that occur in living organisms. Lehninger expressed the challenge to the biochemist as follows: ‘Living things are composed of lifeless molecules. When these molecules are isolated and examined individually, they conform to all the physical and chemical laws that describe the behaviour of inanimate matter. Yet living organisms possess extraordinary attributes not shown by collections of inanimate molecules.’ In this regard Horowitz has proposed a set of criteria for living systems: ‘Life possesses the properties of replication, catalysis and mutability.’ Biochemists are, therefore, concerned with the manner in which living organisms exhibit these properties. —**biochemist** *n.*

biochip **1** an electronic device in which electrical and logical functions are performed by protein molecules appropriately manipulated. *See* **nanotechnology**. **2** *an alternative name for* **microchip**.

biocide any chemical substance that kills living cells or organisms. —**biocidal** *adj.*

biocompatible compatible with life; having no injurious effect on living organisms. —**biocompatibility** *n.*

bioconversion a technique in which the enzymic apparatus of an organism is used to convert or process a chemical substance, not normally present in the organism, into another, (often commercially) useful one.

biocytin ε-*N*-biotinyl-L-lysine; a naturally occurring derivative of **biotin**, found especially in autolysates of rapidly growing yeast. It is liberated from biotin holoenzymes by proteolysis, and is cleaved to biotin and lysine by biotinidase.

biodegradable capable of being broken down by the action of living organisms. —**biodegradability** *n.*

biodegradation **1** the processes by which exogenous, usually waste materials are broken down by living organisms. Sometimes this breakdown involves two or more kinds of organisms acting in cooperation. Such degradative abilities are employed to convert waste materials into more acceptable and manageable forms or to produce useful end products. **2** *an alternative term for* **catabolism**. *Compare* **biosynthesis**.

biodeterioration any undesirable change in the properties of a material brought about by the activities of organisms.

bioelectricity electric current or electric potential produced in living organisms. —**bioelectric** *adj.*

bioelectrochemistry the application of electrochemical models and techniques to biological problems.

bioelectronics the application of biomolecular principles to microelectronics, as in **biosensors** and **biochips**.

bioelement any element that is an essential component of living organisms. Bioelements include: as major elements, C, H, O, N, P, and S, found chiefly in combination in organic compounds, and the elements, Na, K, Mg, Ca, and Cl, found mainly as monatomic ions. Many other ‘trace elements’ occur in relatively minute amounts.

bioenergetics the study of energy transformations in living systems.

bioengineering **1** engineering relating to the operation on an industrial scale of biochemical processes, especially fermentation. This is usually now termed **biochemical engineering**. **2** the application of the physical sciences and engineering to the study of the functioning of the human body and to the treatment and correction of medical conditions.

biofuel cell any fuel cell (a cell in which electricity is produced directly by oxidation of fuel) in which one or both electrode reactions are promoted or catalysed by a biological process.

Bio-Gel *proprietary name for* a group of materials used in gel filtration, consisting of either cross-linked agarose (Bio-Gel A) or porous polyacrylamide (Bio-Gel P).

biogenesis **1** the synthesis of a substance in a living organism; biosynthesis. **2** the principle that a living organism can originate only from a parent or parents that are similar to itself. *Compare* **abiogenesis**. —**biogenetic**, **biogenetical**, **biogenous** *adj.*

biogenic produced by living organisms.

biogenic amine any of various amines, especially those with neurological activity, isolated from plants or animals.

biohazard any organism or material derived from a biological source that is hazardous to health or life.

bioinformatics *see* **informatics**.

bioinformatics institute a research and service centre that creates and manages biological databases (e.g. of nucleic acid and protein sequences, protein families, macromolecular structures), and develops software (e.g. for analysing protein sequences and structures, genome sequences, microarray data) for free use by the community. The European Bioinformatics Institute (EBI) and the National Center for Biotechnology Information (NCBI) are the primary bioinformatics research and service centres for Europe and the USA respectively.

bioinorganic chemistry a branch of inorganic chemistry concerned with the interactions between inorganic substances (especially metallic ions or their complexes) and biological or biochemical systems, and with the properties of related model systems. *Compare* **inorganic biochemistry**.

bioinorganic motif *abbr*.: BIM; a structural feature shared by functionally related (not necessarily homologous) proteins, consisting of one or more metal atoms and first-coordination shell ligands.

bioleaching the extraction of metals from ores or soil by biological processes, mostly by lithotrophic bacteria.

biolistics descriptive of the administration of DNA in gold particles, using a device known as a 'gun' to deliver the particles to the cell interior. One use has been in the development of vaccines by the administration of suitable genes to foreign cells.

biolith a rock or other deposit (e.g. peat, humus) formed from organic material.

biological *adj*. **1** of or pertaining to **biology**. **2** of or pertaining to life or living organisms. **3** a biological product that is used prophylactically or therapeutically. —**biologically** *adv*.

biological activity any activity of a substance that is demonstrable in living organisms. Biologically active substances are often of biological origin themselves.

biological clock any biological mechanism that allows the expression of a certain biological structure (e.g. a gene) or a biological function (e.g. sleep) at periodic intervals. The term is also used colloquially to describe ageing, e.g. in respect to a woman's ability to bear a child.

biologically active *or* **bioactive** active in a living organism.

biological value *abbr*.: B.V.; a measure of the value of a protein in a foodstuff for the maintenance of growth and normal functioning of any given animal or species. It is based on the amino-acid composition of the protein, its digestibility, and the availability of its digestion products.

biology **1** the scientific study of living organisms, including their structure, functioning, development, distribution, interrelationships, and evolution. **2** the animal and plant life of a particular region considered as a unit. **3** the structure, functioning, etc. of a particular organism or group of organisms. —**biologist** *n*.

bioluminescence the production of light by certain enzyme-catalysed reactions in living organisms. —**bioluminescent** *adj*.

biolysis any decomposition of organic material by biological means. —**biolytic** *adj*.

biomarker an indicator signalling an event or condition in a biological system or sample and giving a measure of exposure, effect, or susceptibility. A biomarker may be a measurable chemical, biochemical, physiological, behavioural, or other alteration within an organism.

biomass **1** the total mass of living organisms, of a specified kind, forming a population inhabiting a given region. **2** the material produced by the growth of microorganisms, plants, or animals, especially as a product of or raw material for an industrial process, such as farming or fermentation.

biomedical science *or* **biomedicine** any branch of science that is relevant to medicine.

biomembrane any membrane surrounding a cell or a subcellular organelle, or derived from these structures.

biometry the statistical study of biology. —**biometric** *adj*.; **biometrically** *adv*.

biomimetic **1** describing a laboratory procedure designed to imitate a natural chemical process. **2** describing a compound that mimics a biological material in its structure or function.

biomimetic chemistry a branch of organic chemistry that aims to imitate natural reactions and enzymatic processes as a means to improve the power of organic chemistry.

biomineralization the synthesis of inorganic crystalline or amorphous mineral-like materials by living organisms. Among the minerals synthesized biologically in various forms of life are fluoroapatite ($Ca_5(PO_4)_3(F,OH)$), hydroxyapatite, magnetite (Fe_3O_4), and calcium carbonate ($CaCO_3$).

biomolecular engineering a term sometimes used to cover those branches of biotechnology dealing with enzyme engineering and genetic engineering.

biomolecule any molecule, especially a macromolecule, that occurs in or is formed by living organisms. —**biomolecular** *adj*.

bioorganic chemistry a branch of organic chemistry concerned with the study of organic molecules from living systems.

biophotolysis any type of **photolysis** reaction occurring in a biological system; e.g. the lysis of a water molecule in the reactions of **photosystem II** during photosynthesis.

biophysical chemistry the application of the techniques or methods of physical chemistry to biological systems. It is principally concerned with the conformations, shape, structure, conformational changes, dynamics, and interactions of macromolecules and complexes or arrays of macromolecules. *Compare* **biophysics, physical chemistry**.

biophysics the application of physical techniques and physical methods of analysis to biological problems. Traditionally, the discipline has focused on two main areas: first, the transmission of nerve signals and the maintenance of electrical potentials across membranes; and second, large-molecule crystallography and enzyme structure and mechanisms. For the latter X-ray crystallography has been supplemented by a number of physical techniques, including nuclear magnetic resonance spectrometry, mass spectrometry, fluorescence-depolarization measurements, and circular-dichroism studies. —**biophysical** *adj*.; **biophysicist** *n*.

biopolymer any **polymer**, such as a protein, nucleic acid, or polysaccharide, occurring in, or formed by, living systems.

biopotency the extent to which a material (e.g. drug or hormone) influences a biological process.

bioproduct any (usually) useful product produced by living organisms or by systems derived from living organisms.

biopsy examination of (usually) a sample of tissue, cells, or fluid from a living human or animal for diagnostic purposes. The term is also now commonly used for the process of removing such a sample. *Compare* **necropsy**.

biopterin 2-amino-4-hydroxy-6-(1,2-dihydroxypropyl)-pteridine; 1-(2-amino-4-hydroxy-6-pteridinyl)-1,2-propanediol; a growth factor for certain protozoans, e.g. *Crithidia fasciculata* and *Trypanosoma platydactyli*. It is widely distributed in tissues and functions in a reduced form, **tetrahydrobiopterin**, as a hydroxylation coenzyme, e.g. in the conversion of phenylalanine to tyrosine, of tyrosine to 3-OH tyrosine (DOPA), and of tryptophan to 5-OH tryptophan. It is also a coenzyme for nitric oxide synthase. Biopterin is synthesized from GTP. It has been isolated from queen-bee jelly and is considered a growth factor for some insects. *See* **guanosine triphosphate cyclohydrolase**, **phenylketonuria**.



bioreactor any reactor containing immobilized enzymes or cells that is used to effect specific chemical reactions in the production of some economically desirable product.

bioregulator omnibus term sometimes used for any substance occurring within a cell or organism that has a specific and reversible controlling action on a particular biochemical event within that cell or organism; it may be, e.g., a hormone, an enzyme, an intermediate metabolite, an inorganic ion, or a cyclic nucleotide.

bioremediation the use of biological systems to remedy environmental damage.

bios *the former name for* various growth factors required by yeast. Originally believed to be a single factor, it was later fractionated into bios I (shown to be **inositol**), bios IIA (***β*-alanine**), and bios IIB (**biotin**).

bioscience(s) collectively all the individual branches of science that are concerned with biology.

biose disaccharide; stem name used in the established trivial names for particular disaccharides whether or not they contain a single type of sugar residue and linkage, as in cellobiose and gentiobiose.

+biose *suffix* used in nomenclature of glycolipids to indicate a compound containing an oligosaccharide moiety composed of two sugar residues (which may be the same or different), as in galabiose.

biosemiotics the study of signs, of communication, and of information in living organisms.

biosensor a device that uses specific biochemical reactions mediated by isolated enzymes, immunosystems, tissues, organelles, or whole cells to detect chemical compounds, usually by electrical, thermal, or optical signals.

biospecific describing: **1** a reagent, e.g. an antibody or hormone, that can recognize and interact only with cells (e.g. within a mixed population of cells) displaying a particular surface characteristic, e.g. a corresponding antigen or receptor. **2** any reagent that, in a similar way, recognizes and interacts with a particular biospecifically occurring substance. **3** any reagent that interacts specifically with a particular biomolecule (e.g. an enzyme). **4** the reaction between two biospecific reagents.

biospecific-elution chromatography *an alternative name for* **affinity-elution chromatography** (when the ligand in the eluting solvent is a biospecific macromolecule).

biosphere the parts of the Earth's crust and atmosphere that contain living organisms.

biosynthesis the production of substances by processes occurring in living systems; **anabolism**; **biogenesis**. *Compare* **biodegradation**.

biosynthetic **1** of or relating to **biosynthesis**. **2** any substance produced by biosynthesis.

biosynthetic pathway any metabolic pathway effecting **biosynthesis**; an anabolic pathway.

biotechnology 'the integration of natural sciences and engineering sciences in order to achieve the application of organisms, cells, parts thereof and molecular analogues for products and services' (European Federation of Biotechnology General Assembly, 1989); a field of technological activity in which biochemical, genetic, microbiological, and engineering techniques are combined for the pursuit of technical and applied aspects of research into biological materials and, in particular, into biological processing. It includes traditional technologies such as fermentation processes, antibiotic production, and sewage treatment, as well as newer ones such as **biomolecular engineering**, and **single-cell protein** production. —**biotechnological** *adj.*

biotin *cis*-tetrahydro-2-oxothieno[3,4-*d*]imidazoline-4-valeric acid; hexahydro-2-oxo-1*H*-thieno[3,4-*d*]imidazole-4-pentanoic acid; vitamin H; *formerly known as* bios IIB and coenzyme RCO_2. A substance whose (+) enantiomer is very widely distributed in cells and serves as a carrier in a number of enzymic *β*-carboxylation reactions. In biotin-containing enzymes it is covalently bound at the active site to the *ε*-amino group of a lysine residue. It is a growth factor for yeasts. *Compare* **biocytin**. *See also* **streptavidin**.



biotin carboxylase a carboxylase enzyme that contains biotin (as a **biocytin** residue) in its active site. In humans such enzymes include **pyruvate carboxylase**, **propionyl-CoA carboxylase**, and **β-methylcrotonyl-CoA carboxylase**, which are present in mitochondrial matrix, and **acetyl-CoA carboxylase**, which is cytosolic.

biotinidase EC 3.5.1.12; an enzyme that releases biotin from biocytin or biocytin peptides but not from biotin holocarboxylases. It is present in many human tissues. Serum biotinidase is a glycoprotein with about nine isoforms (67–76 kDa) and is derived from the liver. Many mutations in a locus at 3p25, which encodes a mature protein of 502 residues, result in biotinidase deficiency. This is an autosomal recessive disorder of highly variable clinical expression that commonly includes seizures, hypotonia, developmental delay, ketolactic acidosis, and organic aciduria. Serum biotinidase activity is below 10 to 30% of normal. *See* **holocarboxylase synthetase**.

biotinyl the acyl group derived from **biotin**.

biotinylation **1** the act or process of attaching a biotinyl residue by use of an appropriate reactive derivative, e.g. biotin 4-nitrophenyl ester. It is useful for labelling cell-surface functional groups or biologically active molecules. The presence of the label is subsequently detected, or the labelled material is separated, by means of the specific and high-affinity avidin–biotin reaction, using avidin or **streptavidin** conjugated with, e.g., a fluorochrome, an enzyme, an antibody, or an immobilizing agent. **2** the addition of biotin to the ε-amino group of a lysine residue, catalysed by holocarboxylase synthetase, to form a **biotin carboxylase**. —**biotinylate** *vb.*; **biotinylated** *adj.*

biotransformation the conversion or conjugation of a foreign compound introduced into an organism or a culture of cells, especially (*in biotechnology*) with formation of a substance of commercial value. *Compare* **detoxication**.

BiP *abbr. for* binding protein.

biphenylylphenyloxadiazole *abbr.*: PBD; 2-phenyl-5-(4-biphenylyl)-1,3,4-oxadiazole; a high-efficiency primary scintillator. The *tert*-butyl derivative, 2-(4-*tert*-butylphenyl)-5-(4-biphenylyl)-1,3,4-oxadiazole (*abbr.*: butyl-PBD) has greater solubility and only a slightly lower photon yield. *See also* **scintillation cocktail**.



biphosphate *an obsolete name for* the anion $H_2PO_4^-$ or $PO_2(OH)_2^-$, now correctly termed dihydrogenphosphate.

BIPM *abbr. for* Bureau International des Poids et Mesures.

BIR *abbr. for* baculovirus IAP repeat; a cysteine-rich protein sequence (≈70 amino acids) that is present in several **IAPs** in humans. It is named after the baculovirus, in which it was first discovered.

biradical *or* **diradical** any molecular entity in an electronic state (described by a formula or by a combination of contributing structures) that contains two unpaired electrons in atomic orbitals on different atoms (*compare* **carbene**). Both singlet and triplet species are embraced.

bird flu a disease caused by the avian influenza virus with haemagglutin H5 and neuraminidase N1 and transmissible to the human species, leading to a dangerous respiratory infection..

birefringence *an alternative term for* **double refraction**. — **birefringent** *adj.*

bis+ *comb. form* **1** denoting two, twice, doubled; *see also* **bi+** (def. 1), **di+** (def. 1). *See* **multiplying prefix**. **2** *(in chemical nomenclature)* **a** indicating the presence in a molecule of two identical organic groups each substituted in the same way, e.g. **bis(2-chloroethyl)sulfide**. **b** indicating the presence in a molecule of two separate inorganic oxoacid residues, e.g. fructose 1,6-bisphosphate (formerly known as fructose 1,6-diphosphate). *Compare* **di+** (def. 1).

bisalbuminemia *or (esp. Brit.)* **bisalbuminaemia** a symptomless human condition in which the presence of a variant serum albumin leads to a double albumin band on electrophoresis of serum proteins.

bisbenzimide 4-[5-(4-methyl-1-piperazinyl)-2-benzimidazolyl]-2-benzimidazolyl phenol (Hoechst 33258) or its ethyl ether (Hoechst 33342); a substance that is useful as a DNA-binding fluorochrome for staining chromosomes within cell nuclei. It is believed to be specific for A–T base pairs.

bis(2-chloroethyl)sulfide *or (formerly)* **mustard gas** ($ClCH_2$–$CH_2)_2S$; a bifunctional alkylating agent that causes lethal cross-linking of DNA chains.

bisindolylmaleimide GF 109203X; a protein kinase inhibitor, structurally similar to **staurosporine**, that is highly selective for **protein kinase C** (PKC), though not between isotypes α, βI, βII, or γ. It acts as a competitive inhibitor at the ATP-binding site on PKC. It



bisbenzimide

exhibits a K_i of 14 nm for the purified enzyme, but its potency on whole cells is much lower (K_i 1–2 µm), possibly owing to high cellular ATP levels.



bismethylstyrylbenzene *abbr*.: bis-MSB; 1,4-bis(2-methylstyryl)-benzene; a secondary scintillator with good resistance to quenching and low reactivity with compounds in samples. *See also* **scintillation cocktail**.



bis(methylthio)gliotoxin a naturally occurring analogue of **gliotoxin**. It inhibits platelet activating factor (PAF)-induced platelet aggregation (IC$_{50}$ = 84 µm) (but not platelet aggregation induced by arachidonic acid or ADP) and *in vivo* PAF-induced bronchoconstriction; it lacks the antiviral and immunomodulating effect of gliotoxin.



bis-MSB *abbr. for* bismethylstyrylbenzene.

bisphosphate any compound containing two independent phosphoric residues in ester linkages, at positions indicated by locants. *Compare* **diphosphate** (def. 3, 4).

bisphospho+ *prefix* to a chemical name indicating the presence of two independent phosphoric residues in ester linkages, at positions indicated by locants. *Compare* **diphospho+**.

2,3-bis(phospho)-D-glycerate *a recommended name for* (*R*)-[2,3-dihydroxypropanoate 2,3-bis(dihydrogenphosphate)] (formerly termed 2,3-diphosphoglycerate); *abbr*.: BPG; it decreases the dioxygen affinity of hemoglobin, its concentration in the erythrocyte being regulated by **bisphosphoglycerate mutase** (synthesis) and **bisphosphoglycerate phosphatase** (degradation). It does not pass through the erythrocyte membrane. *See also* **bisphosphoglycerate pocket**.

bisphosphoglycerate mutase *abbr*.: BPGM; EC 2.7.5.4; *systematic name*: 3-phospho-D-glycerate 1,2-phosphomutase; *other names*: 2,3-bisphosphoglycerate mutase; 2,3-bisphosphoglycerate synthase; diphosphoglycerate mutase; glycerate phosphomutase; bisphosphoglycerate synthase. In human reticulocytes and erythrocytes, an activity on a multifunctional homodimer (locus at 7q34-q22) that catalyses the reaction:

3-phospho-D-glyceroyl phosphate =
2,3-bisphospho-D-glycerate.

The same protein also has **bisphosphoglycerate phosphatase** activity, and the two activities together regulate the dioxygen affinity of hemoglobin by controlling 2,3-bisphosphoglycerate concentration in erythrocytes. Several rare mutations lead to deficiency of these reactions and are associated with erythrocytosis. The protein also has a third activity, that of 3-phosphoglycerate mutase, which catalyses the reaction: 3-phosphoglycerate = 2-phosphoglycerate.

bisphosphoglycerate phosphatase EC 3.1.3.13; *systematic name*: 2,3-bisphospho-D-glycerate 2-phosphohydrolase; in human reticulocytes and erythrocytes, an activity on a multifunctional homodimer (locus at 7q34-q22) that catalyses the hydrolysis of 2,3-bisphosphoglycerate to 3-phosphoglycerate and orthophosphate; it thereby assists regulation of the concentration of 2,3-bisphosphoglycerate (in conjunction with the **bisphosphoglycerate mutase** activity of the same protein), and thus also the dioxygen affinity of hemoglobin.

bisphosphoglycerate pocket *abbr*.: BPG pocket; the cavity (pocket) between the two β chains of deoxyhemoglobin in which a single molecule of 2,3-bisphospho-D-glycerate (BPG) binds; the binding of this molecule reduces the affinity of hemoglobin for dioxygen. Residues Val^1 (terminal –NH$_3^+$), His^2, Lys^{82}, and His^{143} of each β chain participate in this binding. It plays an important part in establishing the difference in oxygen affinity that is found between maternal and fetal hemoglobin; in fetal hemoglobin, the γ chain has a serine in the position occupied by His^{143} of the β chain of the adult hemoglobin, which weakens the affinity of fetal hemoglobin for BPG and thus results in a higher affinity for dioxygen than adult hemoglobin.

bis[2-succinimidooxycarbonyloxyethyl]sulfone a non cytotoxic, homobifunctional, lysine-specific cross-linking agent that reacts at 0 °C; the cross-links can be reversed at pH 11.6 at 37 °C.



2,5-bis(3,4,5-trimethoxyphenyl)-1,3-dioxolane a substance, the *trans*-isomer of which inhibits platelet activating factor-induced platelet aggregation. The *cis*-isomer is inactive.



Bistris *or* **bis-tris** *abbr. for* bis(2-hydroxyethyl)imino-tris(hydroxymethyl)methane; 2-[bis(2-hydroxyethyl)amino]-2-(hydroxymethyl)-propane-1,3-diol. A buffer substance useful for the calibration of glass electrodes and for the preparation of biochemical and biological buffer solutions; pK_a (25°C) = 6.5. It is inexpensive, stable, and readily crystallizable.



bis-tris propane *abbr. for* 1,3-bis[tris(hydroxymethyl)methylamino]propane; a water-soluble buffer substance used for the preparation of biochemical and biological buffer solutions; pK_a (20°C) = 6.8.



bit a single binary digit having the value of either 0 or 1; the smallest unit of information in a binary system. A group of (usually) eight bits comprises a **byte**, which can represent numbers between 0 and 11111111 in binary (equal to 0 and 255 in decimal). [*abbr. for* binary digit.]

bithorax complex *see* **BX-C**.

Bittner factor *or* **Bittner particle** *former name for* murine mammary tumour virus. [After John Joseph Bittner (1904–61), US biologist.]

biuret reaction the formation of a characteristic purple colour when biuret (carbamoylurea) or compounds containing two or more adjacent peptide bonds (e.g. proteins) react with copper sulfate in alkaline solution. It forms the basis of the **biuret test**, a colorimetric method for the qualitative or quantitative determination of proteins.

Bjerrum formation function a function used in studies of the binding of *n* ligand atoms, ions, or molecules to an acceptor atom, ion, or molecule. It is:

$$\nu = (K_1[L] + 2K_1K_2[L]^2 + ...nK_1K_2...K_n\,[L]^n\,)/(1 + K_1[L] + 2k_1k_2[L^2] + ...nK_1K_2...K_n\,[L]^n\,),$$

where ν is the average number of ligand molecules bound per molecule of acceptor; K_1, K_2, ...K_n are the stepwise formation (stability) constants of the *n* complexes; and [*L*] is the free ligand concentration. This function expresses an unambiguous connection between the quantity ν and [*L*]. It is a generalized form of the **Adair equation**. [After Jannik Bjerrum (1909–92), Danish chemist who described it in 1941.]

Bjerrum plot a plot of ν, the average number of ligand molecules bound per molecule of acceptor, versus –log[*L*], where [*L*] is the free ligand concentration. It is used for evaluating the association constants in a **Bjerrum formation function**.

Bk *symbol for* berkelium.

BK *abbr. for* bradykinin.

BK$_{1–8}$ *abbr. for* des-Arg^9-bradykinin (*see* **bradykinin**).

BL21 a strain of *Escherichia coli* carrying a lambda phage DE(T7) lysogen. Inducible expression of T7 RNA polymerase gives high levels of transcription from plasmid vectors such as pET and high yields of protein product.

bla *symbol for* β-lactamase gene.

black lipid membrane *abbr.*: BLM; *other names*: black lipid film; bimolecular lipid membrane; bilayer lipid membrane; lipid bilayer. An experimental membrane formed by introducing a small amount of suitable lipid solution on to an opening in the wall of a hydrophobic support immersed in an aqueous solution. The thickness of the black membrane does not differ greatly from the length of two of the lipid molecules used and is often about 4.5 nm.

blank (determination) any analytical mixture from which analyte is deliberately omitted and which undergoes the same procedures as the complete mixture. It is used to ascertain the contribution of extraneous factors, e.g. reagent impurities or photometric absorption by the reagents, to the analytical result.

blast+ *a variant form of* **blasto+**.

+blast *suffix* denoting a formative cell, e.g. erythroblast, fibroblast, osteoblast.

BLAST *abbr. for* basic local alignment search tool; *see* **alignment algorithm**.

blast cell *or* **blastocyte** any undifferentiated embryonic cell. Such cells characteristically have a cytoplasm rich in RNA, and are actively synthesizing DNA.

blast crisis the appearance of heterogeneity in the cell surface characteristics of white blood cells when chronic myeloid leukemia evolves into acute leukemia. This process is virtually inevitable and often rapid.

blasticidin S a peptidylnucleoside antibiotic produced by *Streptomyces griseochromogenes* that inhibits protein synthesis through inhibition of peptide bond formation. Resistance to blasticidin is conferred by the expression of the blasticidin S resistance gene (*bsr*) from *Bacillus cereus* or the *BSD* gene from *Aspergillus terreus*. Both encode blasticidin S deaminase (BSD).

blasto+ *or (before a vowel)* **blast+** *prefix* denoting **1** an embryo in its early stages; e.g. blastocyst, blastula. **2** a germ cell; e.g. blastocyte.

blastokinin *see* **uteroglobin**.

blast transformation *see* **transformation** (def. 3).

bleb 1 a spherical vesicle, about 10 µm in diameter, formed when a chloroplast swells on suspension in very hypotonic medium. It is bounded by a single membrane, on the surface of which a part of the **thylakoid** system remains concentrated in a few patches. **2** animal membranes are said to form blebs under special conditions that cause small vesicles to pinch off.

blebbistatin a highly specific inhibitor of ATPase activity of mysoin II, and of contraction of the cleavage furrow during cytokinesis. It rapidly and reversibly blocks formation of cell blebs. .

blender *or (sometimes, US)* **blendor** a device for disrupting tissue or any aggregate. It consists of blades rotating at the bottom of a glass or stainless-steel vessel (originally named a **Waring blendor**, from a trade name); in an alternative design, known as a top-drive blender, the blades rotate on a spindle from the top of the vessel. The method is undiscriminating and may damage organelle membranes through excessive force or generation of heat. For more precise work, a **Potter–Elvehjem homogenizer** or a **Dounce homogenizer** preserves organelle structure.

bleomycin any of a group of related glycopeptide antibiotics isolated from *Streptomyces verticillus*. Bleomycin acts to stop the cell cycle in the G_2 phase (*see* **cell-division cycle**). It is used to induce synchrony in cell cultures and as an antineoplastic agent, especially in lymphomas.

blepharoplast *an alternative term for* **basal body** of a flagellate.

Blk a gene encoding a protein tyrosine kinase of the Src family, specifically expressed in the B-cell lineage.

BLM *abbr. for* black lipid membrane.

BLM protein *or* **BLM helicase** *or* **RecQ-like protein 2** *or* **RECQL2** a protein of 1417 residues encoded by the locus for **Bloom syndrome** at 15q26.1. It contains a 350-residue domain that comprises seven sequences characteristic of DNA and RNA helicases and present in RecQ helicases. Numerous mutations are associated with Bloom syndrome. The *recQA* gene was first identified in an *E. coli* mutant resistant to thymineless death. RecQ protein is a DNA helicase. Apart from BLM protein, mammalian cells also contain the homologous RecQ-like protein 1 (RECQL1) of 652 residues, WRN (mutated in Werner syndrome), RECQL4, and RECQL5.

***Bln*I** a type 2 **restriction endonuclease**; recognition sequence: C↑CTAGG. *Avr*II is an **isoschizomer**.

block 1 *(in chemistry)* a portion of a polymer molecule comprising many **constitutional base units**; such a portion has a constitutional or configurational feature not present in the adjacent multiple-unit portions. **2** *(in physiology)* an interference in the normal metabolic or physiological functioning of an organ or tissue; e.g. metabolic block, heart block. **3** (*in bioinformatics*) an ungapped local **alignment**

(def. 2) derived from a conserved region in an aligned family of protein sequences, used to build a diagnostic familial signature. Within a block, segments are clustered to reduce multiple contributions from highly similar or identical sequences, each cluster being treated as a single segment, with a score giving a measure of its relatedness – the most distant segment is given a weight of 100. **4** to impede, retard, or prevent an action or activity, e.g. of an agonist, antigen, chemical reagent, enzyme, or receptor.

blockade **1** *(in pharmacology)* the saturation of a specific type of receptor with an antagonist to its normal agonist. **2** *(in immunology)* the overloading or saturation of the **reticuloendothelial system** with inert particles, such as carbon particles. **3** to impose any such blockade.

blocker something that blocks an action or activity; an antagonist or inhibitor.

blocking agent **1** a chemical reagent that introduces a **blocking group**. **2** a specific pharmacological antagonist.

blocking antibody **1** an incomplete antibody that does not agglutinate its antigen but attaches to it and so prevents its agglutination by normal, complete antibody. **2** antibody formed during specific **desensitization** in **atopy**.

blocking group **1** *or* **protecting group** a chemical group, often easily removable, that is substituted into a reactive part of a molecule to prevent its participation in subsequent chemical or enzymic reactions occurring at another part of the molecule. **2** a chemical group, not easily removable, that is substituted into the active site of an enzyme to prevent its action.

block polymer a polymer whose molecules contain two or more species of **block** (def. 1) attached linearly.

Blocks *see* **pattern database**.

Blocks-format-PRINTS *see* **derived database**.

blood a fluid tissue in animals that acts primarily as a transport medium. It is contained in vessels or spaces lined with endothelial cells. Metabolites, nutrients, and excretory substances are carried in solution or suspension from one part of the body to another. Respiratory pigments are often present to assist in the transport of dioxygen. It may also contain suspended cells.

blood–brain barrier the semipermeable membranous barrier that regulates the passage of dissolved materials from the blood into the cerebrospinal fluid that bathes the brain and spinal cord.

blood coagulation *or* **blood clotting** a mechanism that prevents blood loss at the site of an injury. It involves the formation of a semi-solid mass of material, the blood clot, which plugs the wound. The clot consists of aggregated platelets and a mesh of fibrin molecules. The fibrin components include 13 or 14 plasma proteins, at least one tissue protein, phospholipid membrane surfaces, Ca^{2+} ions, and platelets. The current concept of the mechanism has changed from one involving a linear sequence of activations of proenzymes to one involving protein–protein and protein–lipid–Ca^{2+} interactions between protease, protein substrates, and protein cofactors, to give discrete complexes and reaction steps. The following factors are involved in coagulation:

Factor I (*or* **fibrinogen**) concn. ~2–4 g L^{-1} human plasma; a soluble fibrous protein of 330 kDa, it has an axial ratio of ~5 and comprises six disulfide-linked polypeptide chains: two Aα chains (66 kDa); two Bβ chains (52 kDa); and two γ chains (47 kDa). After proteolysis by thrombin, it polymerizes to form an insoluble fibrin clot.

Factor II (*or* **prothrombin**) concn. 200 mg L^{-1} human plasma, 72.5 kDa; a vitamin K-dependent single-polypeptide-chain glycoprotein containing ten γ-carboxyglutamate residues. It is converted to **thrombin** (*or* fibrinogenase), EC 3.4.21.5, by the protease factor Xa.

Factor III (*or* thromboplastin *or* tissue factor) a factor that, when added to blood plasma, markedly shortens the time required for clot formation.

Factor IV (*or* calcium ion) calcium ions form bridges between vitamin K-dependent proteins and acid phospholipids of cell membranes. They also stabilize factor V and fibrinogen, and are involved in activation of factor XIII.

Factor V (*or* accelerator globulin *or* proaccelerin) a glycoprotein of ~330 kDa. After activation to **factor Va** (accelerin), it acts with the protease factor Xa in activating prothrombin.

Factor VI an obsolete term (originally named accelerin).

Factor VII (*or* proconvertin) concn. 2 mg L^{-1} human plasma; 50 kDa; a vitamin K-dependent single-polypeptide-chain glycoprotein containing γ-carboxyglutamate residues. It is the precursor of **factor VIIa**, convertin, a Ca^{2+}-dependent protease, EC 3.4.21.21, that activates factor X, and is the first component of the extrinsic pathway of coagulation.

Factor VIII (*or* antihemophilic factor); an accessory protein that participates with protease factor IXa in the activation of factor X in the intrinsic pathway of coagulation.

Factor IX (*or* Christmas factor) concn. 3–4 mg L^{-1} human plasma; 57 kDa (human), 55.4 kDa (bovine); a vitamin K-dependent single-polypeptide-chain glycoprotein containing 17% carbohydrate (human; 25% in bovine) and γ-carboxyglutamate residues. After proteolytic activation, it consists of two chains: **factor IXa**, a serine protease, EC 3.4.21.22, of 27 kDa that activates factor X in the intrinsic pathway of coagulation; and a light chain of 16 kDa that contains the γ-carboxyglutamate residues.

Factor X (*or* Stuart–Prower factor; *other names*: Stuart factor; thrombokinase; prothrombase; prothrombinase) concn. 6–8 mg L^{-1} human plasma; a vitamin K-dependent two-polypeptide-chain glycoprotein, containing 15% carbohydrate (human; 10% in bovine): the 40 kDa chain is a serine protease; the 15 kDa chain contains 12 γ-carboxyglutamate residues. It is the circulating precursor to the protease **factor Xa**, EC 3.4.21.6, that converts prothrombin into thrombin by selective cleavage of Arg-|-Thr then Arg-|-Ile bonds.

Factor XI (*or* plasma thromboplastin antecedent) 160 kDa (human), 124 kDa (bovine); a protein of two disulfide-linked chains of apparently equal molecular mass. It is the circulating precursor of the serine protease **factor XIa**, EC 3.4.21.27, to which it is converted by proteolysis: selective cleavage of Arg-|-Ala and Arg-|-Val bonds in factor IX, to form factor IXa, triggers the middle phase of the intrinsic pathway of blood coagulation by activating factor IX. Factor XIa converts factor IX into factor IXa.

Factor XII (*or* Hageman factor) 80 kDa (human), 74 kDa (bovine); a single-polypeptide-chain glycoprotein. It is the circulating precursor of the protease **factor XIIa**, which activates factor XI.

Factor XIII (*or* plasma transglutaminase) 320 kDa (plasma, tetrameric), 160 kDa (platelets, dimeric). An enzyme precursor whose subunits are proteolytically cleaved by thrombin to form the transglutaminase, **factor XIIIa**, EC 2.3.2.13, which covalently cross-links fibrin monomers into the fibrin polymer.

Prekallikrein a plasma protein, 88 kDa (bovine), that is the precursor of the protease **kallikrein**. This consists of a heavy chain (52 kDa) and a light chain (33–38 kDa), and cleaves factor XII to form factor XIIa.

High-molecular-weight kininogen a single-polypeptide-chain glycoprotein of ~150 kDa (human), 76 kDa (bovine). It is the source of **bradykinin**, which is released from it by **kallikrein**, and acts as an accessory protein in the activation of factor XI by factor XIIa.

Plasminogen 86 kDa (human); a single-polypeptide-chain protein that, on proteolysis, is converted into the protease **plasmin**, which degrades the fibrin clot. There are two pathways of coagulation: in the **intrinsic pathway**, which occurs during the clotting of platelet-poor plasma, activation of factor X to factor Xa is effected by the combination of factor IXa + factor VIIIa + Ca^{2+} + phospholipid; in the **extrinsic pathway,** the earlier stages of the cascade are bypassed, and the activation of factor X to factor Xa is effected by the combination of factor VIIa + thromboplastin; this second pathway occurs when tissue extracts are present in optimal amounts, and is much more rapid than the intrinsic pathway.

blood group any of various systems of classifying erythrocytes according to their surface isoantigens. In humans 14 different, genetically independent blood-group systems are known. They arise from naturally occurring antibodies and from the **blood-group substances**, antigenic substances present on the surface of the erythrocytes of only certain members of a species. These antigens are also found in a wide variety of other tissues, including endothelial and epithelial cells, and in certain body fluids. The specificities of the blood-group antigens arise in some cases from oligosaccharide chains linked to protein or lipid (ceramide); antigens that fall into this category are those associated with the ABH system, Lewis system, Ii system, and P1/P-related system. In other cases, antigenicity arises directly from the polypeptide chain composition of a surface protein; antigens that fall into this category are associated with the MN system, Ss system, Gerbich system, Rhesus system, Kell system, Duffy system, and Cromer-related system. The blood-group substances were discovered because of the presence in human blood of naturally occurring antibodies (i.e. not resulting from infection or other external cause) that react with these antigens on red blood cells causing them to agglutinate. Only the presence of a blood-group antigen during fetal life ensures that no antibody against it will be produced. Hence if blood from an individual (the donor) who lacks a particular antigen is transfused into an individual (the recipient) who possesses the same antigen, a transfusion reaction will result in the recipient owing to the presence in the donor's blood of antibody against the antigen in question. The blood-group substances have therefore been of interest largely in relation to blood transfusion, and in most cases the true physiological function of these substances is unknown.

blood-group substance any of numerous antigenic substances present on the surface of erythrocytes of certain members of a species but absent from those of other members of the same species. These same antigens are also found in a wide variety of tissues and in certain body fluids, e.g. saliva, milk, gastric juice, seminal fluid, urine, and ovarian-cyst fluid. The specificities of the A, B, and H antigens of the **ABO system** are determined by structures present at the nonreducing ends of oligosaccharides of both glycoproteins and glycolipids. The **Lewis antigens**, Le_a and Le_b, are associated with glycosphingolipids adsorbed from plasma lipoproteins on to adult cells and are not synthesized in the developing erythrocyte. Antigenic determinants of the **MN system** are associated with glycoproteins rich in sialic acid.

blood plasma 1 the fluid portion of blood in which the red blood cells and other cellular components (the 'formed elements') are suspended. Clotting may be prevented by the addition of disodium hydrogen citrate which removes ionized Ca^{2+} by the formation of an un-ionized complex. Fluoride or oxalate may also be used to precipitate the Ca as an insoluble salt. **Heparin** is often used. When whole blood containing such an anticoagulant is centrifuged, the formed elements sediment in a volume equal to about 45% of the total volume of blood. The supernatant is known as the plasma. In vertebrates it is clear and almost colourless and clots as easily as whole blood. *See also* **anticoagulant**. *Compare* **serum**.

blood sugar *old term for* the glucose concentration in the blood; when estimated by older methods it included small amounts of other reducing substances. *See also* **glycemia**.

Bloom syndrome an autosomal recessive condition characterized by profound disposition to neoplasias and associated with small body size, a sun-sensitive erythematous skin rash, characteristic facies and head shape, immunodeficiency, and chronic lung dissease. Heterozygotes have twice the normal risk of developing colorectal cancer. It is caused by many mutations in the gene for **BLM protein**. [After David Bloom (1892–), US dermatologist.]

BLOSUM *abbr. for* Blocks substitution matrix; *see* **substitution matrix**.

blotting *or* **blot transfer** a technique useful for identifying similar macromolecules, e.g. sets of DNA or RNA fragments, or mixtures of intact proteins, that are separable by gel electrophoresis. The separated components are then transferred from the gel to a sheet of an appropriate medium while preserving their two-dimensional relationships. This can be achieved either by capillary flow between an underlying wick loaded with buffer solution and an overlay of dry blotting paper, or by applying an electric potential to move separated components on to the medium, to which they bind firmly. Once on the transfer medium the substances may be detected with specific radioactive or fluorescent probes, e.g. complementary polynucleotides or antibodies. The original version of the technique, used for DNA fragments and often referred to as **Southern blotting**, has been extensively developed and adapted for other applications, e.g. **dot hybridization** (or dot blotting), **colony hybridization**, **electrophoretic transfer**, **Northern blotting**, and **Western blotting**.

BLOTTO *abbr. for* Bovine Lacto Transfer Technique Optimizer; a 5% solution of non-fat dried milk sometimes used in Southern hybridizations.

blue agarose any insoluble beaded form of agarose gel that is artificially cross-linked between the individual polysaccharide chains and conjugated with the dye Reactive Blue 2. Carboxymethyl (CM) or diethylaminoethyl (DEAE) groups may also have been introduced. It is useful in **triazine-dye affinity chromatography**.

blue copper protein an **electron transfer protein** containing a **type 1 copper** site. It is characterized by strong absorption in the visible region owing to coordination of the copper by cysteine sulfur.

blue dextran a soluble dextran, of average M_r 10^6, conjugated with the dye Reactive Blue 2. It is useful in gel filtration for checking column packing and determining the void volume.

blue-green algae *an alternative name for* **cyanobacteria**.

blue oxidase any of a small number of copper-containing oxidase enzymes in which the product of enzyme action in the reduction of dioxygen is water. Blue oxidases are the most complicated of copper proteins; the blue colour is due to a strong absorption band around 600 nm. Among the blue oxidases are laccase (EC 1.10.3.2), L-ascorbate oxidase (EC 1.10.3.3), and the weak oxidase **ceruloplasmin**.

blue shift any shift of the peaks of absorption or emission of a spectrum of electromagnetic radiation to shorter wavelengths, including from the visible to the ultraviolet region.

Blue Tetrazolium *or* **Tetrazolium Blue** 3,3′-dianisole bis[4,4′-(3,5-diphenyl)tetrazolium chloride]; a dye that yields a dark-blue diformazan pigment on reduction; it has a redox potential of approximately –0.08 V. It is useful as a stain for bacteria and moulds, in histochemical studies to demonstrate oxidoreductase activity, and in the colorimetric assay of some dehydrogenases.



blunt end (of DNA) *an alternative term for* **flush end** (of DNA).

B lymphocyte *or* **B cell** *or (archaic)* **bursacyte** any 'bursa-dependent' lymphocyte concerned in the synthesis of circulating antibody. B lymphocytes arise from primitive lymphoid cells of the bone marrow and develop into the **plasma cell** series. Their maturation is determined by processing within the **bursa of Fabricius** in birds, or equivalent hematopoietic tissue in other vertebrates. B lymphocytes may be differentiated from **T lymphocytes** by their surface markers which contain immunoglobulins. In humans the majority of B lymphocytes are derived from bone marrow stem cells, but a minor population, distinguished by the CD5 marker, appears to form a self-renewing set. Cells in this set respond to a number of common microbial antigens and sometimes generate **autoantibodies**.

BMAL1 a basic helix-loop-helix transcription factor that forms heterodimers with the transcription factors **clock** and **NPAS2**. Binding to a DNA motif (CACGTG) enhances expression of period proteins and cytochromes in the suprachiasmatic nucleus and forebrain nuclei. Transcription of genes activated by clock-BMAL1 dimers is repressed by CRY2 (*see* **cryptochrome**).

Bmi-1 a murine gene encoding a protein that is probably a transcriptional regulator. It is named from B-cell-specific Moloney murine leukemia virus integration site. The protein contains putative **zinc finger** and **helix-loop-helix** domains, as well as C-terminal PEST sequences. *See* **PEST hypothesis**.

BMI *abbr. for* body mass index; an anthropometric measurement equal to weight in kg/(height in m)^2. Values in the range 25.0–29.9 indicate that an individual is overweight, values >30 indicate obesity.

BMP *abbr. for* bone morphogenetic protein.

BMPR *abbr. for* bone morphogenetic protein receptor.

BMR *abbr. for* basal metabolic rate.

BmrR a protein of *Bacillus subtilis* that is a transcription regulator of the gene *bmr*, which encodes a multidrug transporter (**Bmr transporter**) and is expressed in response to a variety of structurally and chemically dissimilar hydrophobic cations, many of which are substrates of the Bmr transporter. It contains an N-terminal DNA-binding region specific for the promoter of *bmr*, and a C-terminal domain that contains a hydrophobic core and a buried glutamate residue and functions in inducer binding and in dimerization. The crystal structure of the C-terminal domain has been solved.

Bmr transporter *see* **BmrR**.

BNP *abbr. for* brain natriuretic peptide (*see* **natriuretic peptide**).

boat conformation any conformation of a nonplanar six-membered saturated ring compound when ring atoms in relative positions 1, 2, 4, and 5 lie in one plane, and those in relative positions 3 and 6 lie on the same side of that plane. Boat conformations of a monosaccharide or monosaccharide derivative may be designated by the conformational descriptor -*B*. *See also* cyclic compounds at **conformation**.

Boc *or* ***t*-BOC** *symbol for* the *tert*-butoxycarbonyl group, $(CH_3)_3C–O–CO–$, a **protecting group** used in polypeptide chemistry. It can be introduced using reagents such as di-*tert*-butyl dicarbonate (Boc anhydride).

BOD *abbr. for* biochemical oxygen demand.

body mass index *see* **BMI**.

body water the water content of the body of an organism. The **total body water** (*abbr.* TBW) of a man of average build (70 kg) has a volume of approximately 42 L and represents ≈ 60% of the body weight. It may be divided functionally into two parts: **intracellular fluid** and **extracellular fluid**.

Bohr coefficient (for hemoglobin) the ratio of the change in the logarithm of the partial pressure of oxygen when there is half-saturation of the hemoglobin to the change in pH; i.e. $\Delta \log P_{50}/\Delta \mathrm{pH}$. *See also* **Bohr effect**. [After Christian Bohr (1855–1911), Danish physiologist.]

Bohr effect the variation of oxygen affinity of hemoglobin with pH (the oxygen affinity increases with increasing pH). It is one of the effects arising from oxygen-linked acid groups in hemoglobin and similar oxygen-carrying proteins, and also encompasses similar effects involving other acid-linked functions, e.g. oxidation loss of protons causing increased dioxygen binding. The effect was discovered by Christian Bohr *et al.* following observations that changes in the partial pressure of CO_2 influence the oxygen equilibrium of the blood.

Bohr magneton *symbol*: μ_B; the intrinsic magnetic moment of an electron given by $\mu_B = eh/4\pi m_e$, where e is the elementary charge, h is the Planck constant, and m_e is the rest mass of an electron. It is a fundamental physical constant, of value $9.2740154(31) \times 10^{-24}$ J T^{-1}. *Compare* **nuclear magneton**. [After Niels Bohr (1885–1962), Danish physicist and son of Christian Bohr.]

boivinose the D-enantiomer, 2,6-dideoxy-D-*xylo*-hexose, is a component of some **cardiac glycosides**.

Bollum's enzyme DNA nucleotidylexotransferase, EC 2.7.7.31. *See* **terminal transferase**. [After Frederick James Bollum (1927–), who described it in 1971.]

Bolton and Hunter reagent *or* **Bolton–Hunter reagent** 3-(4-hydroxyphenyl) propionic acid *N*-hydroxysuccinamide ester, iodinated with ^{125}I. This may be the di-iodo derivative, or the commercially available mono-iodo *N*-succinimidyl 3-(4-hydroxy-5-[^{125}I]iodophenyl)propionate; a reagent for **conjugation labelling** of polypeptides or proteins with iodine-125. It is specific for free amino groups, which under mild conditions become acylated to form (4-hydroxy-5-[^{125}I]iodophenyl)propionylamino groups. [After Anthony E. Bolton and William M. Hunter who described its use in 1972.]

Boltzmann constant *symbol*: k; the ratio of the gas constant, R, to the Avogadro constant, N_A. It is given by $k = R/N_A = 1.380658\ (12) \times 10^{-23}$ J K^{-1}. [After Ludwig Boltzmann (1844–1906), Austrian physicist.]

Boltzmann distribution law a law describing the population distribution of a system of particles in different energy states but at thermal equilibrium, given by: $n_i / n_0 = e^{-(Ei-E0)/kT}$, where n_i is the number of particles in energy state i, n_0 is the number in the lowest energy state, E_i and E_0 are the energies of states of i and 0 respectively, T is the thermodynamic temperature, and k is the **Boltzmann constant**.

bolus 1 a soft, rounded mass, especially of chewed food. **2** a large pill, as used in veterinary or clinical medicine.

bomb calorimeter an apparatus with which the heat of combustion of a substance may be determined. The substance is placed in a metal bomb with dioxygen under pressure, and then ignited electrically. The heat evolved is measured by the rise in temperature of the water in a surrounding jacket.

bombesin a tetradecapeptide amide isolated from frog skin. It has an N-terminal 5-oxoprolyl residue, and shares striking sequence similarity with other peptides isolated from amphibian skin, all of which have a C-terminal methioninamide residue. The (toad) sequence is:

$$\mathrm{QQRLGNQWAVGHLM–NH_2},$$

In mammals, it is a potent releaser of, *inter alia*, gastrin and cholecystokinin, and bombesin-like immunoreactivity has been detected in mammalian gut and brain. It is mitogenic in a number of cell types, and stimulates smooth muscle contraction. The peptide is said to occur in gastrointestinal nerves of mammals, while in frogs and birds it occurs in endocrine cells.

bombesin receptor any of several membrane proteins that bind bombesin, and mediate its intracellular effects. Binding studies have indicated two receptor subtypes: on gastrin releasing peptide (GRP)-preferring receptors (e.g., rat pancreas), GRP is more potent than neuromedin B; on other receptors (e.g., rat esophagus), neuromedin B is more potent than GRP. All receptors are of the **7TM**, G protein-coupled type. The effector pathway involves the phosphoinositide/Ca^{2+} second messenger system (*see* **phosphatidylinositol cycle**).

bombolitin any of five structurally related peptides from the venom of the bumblebee, *Megabombus pennsylvanicus*, that are rich in hydrophobic amino-acid residues (*e.g.*, bombolitin I has sequence IKTITTMLAKLGKVLAHV). They all lyse erythrocytes and liposomes, release histamine from mast cells, and stimulate phospholipase A_2; their properties are similar to those of **melittin**.

bombyxin any of a family of brain secretory peptides of the silkmoth that activate prothoracic glands to produce ecdysone. They contain an A and B chain joined by disulfide bonds, and are homologous to vertebrate insulins.

bond 1 *or* **covalent bond** a region of high electron density between atoms that arises, at least partly, from sharing of electrons and gives rise to an attractive force and a characteristic internuclear distance between the atoms. *See* **coordination**, **dipolar bond**, **hydrogen bond**. **2** the representation of a covalent bond in an extended chemical formula. **3** to join or link together (esp. chemical entities); to **ligate** (def. 1).

bond angle the angle formed between two bonds at a given polyvalent atom.

bond-dissociation energy *see* **dissociation energy**.

bond energy 1 the average value of the gas-phase **bond dissociation energies** (usually at 298 K) of a given type of bond in the same chemical species: **mean bond energy**. **2** loosely, the free energy change occurring on hydrolysis of a hydrolysable chemical bond.

bonding the act or process of forming a covalent **bond** (def. 1); the state of being so linked. *See also* **domain of bonding**.

bond length the distance between the centres of the nuclei of two bonded atoms.

bone the hard, dense connective tissue that constitutes the skeleton of many animals. It consists of an organic matrix impregnated with bone mineral salts. The matrix is made up of 90–95% type I collagen, a small amount of proteoglycan, and a 49-residue protein containing three γ-carboxyglutamate residues, the formation of which is vitamin K-dependent. This protein binds strongly to the hydroxyapatite crystals of the bone mineral. The inorganic part of the bone consists largely of basic calcium phosphate, which is organized into small crystals of hydroxyapatite, 0.8–1.5 nm thick, 2–4 nm wide, and 20–40 nm long, of approximate composition $Ca_{10}(PO_4)_6(OH)_2$. Other anions present are carbonate, fluoride, hydroxide, and citrate. Most of the body's Mg^{2+}, about 25% of its Na^+, and a smaller proportion of its K^+ is found in bone.

bone GLA-protein (BGP) *see* **osteocalcin**.

bone marrow the soft tissue contained within the internal cavities of bones. **Red marrow** (*or* myeloid tissue), found in developing bone, ribs, vertebrae, and in parts of the long bones, is actively hemopoietic and contains all the cells of the circulating blood and their precursors together with megakaryocytes, reticulum cells, macrophages, and plasma cells. In adult animals the marrow of many bones, particularly limb bones, becomes filled with fatty tissue known as **yellow marrow**. In adult mammals, B lymphocytes develop and differentiate in the bone marrow.

bone-marrow-derived cell any cell derived from bone marrow tissue, including erythrocytes, lymphocytes, granulocytes, etc. The term is often used misleadingly to refer to the **B lymphocytes**.

bone morphogenetic protein *abbr*: BMP; any of several zinc metalloendopeptidases belonging to the sub-subclass EC 3.4.24, and having an **EGF** motif repeat; they are members of the **astacin** subfamily. BMP enzymes are disulfide-linked homodimers of the transforming growth factor-β family, and are related to **tolloid**. They are involved in induction of bone and cartilage formation.

bone morphogenetic protein receptor *abbr.*: BMPR; either of two receptors for **bone morphogenetic proteins**. They occur together on cell surfaces and are single-pass transmembrane proteins whose intracellular domains are serine/threonine protein kinases. They function via phosphorylation of Smad 5, which then dimerizes with Smad 4 before entering the nucleus to regulate DNA transcription. Many mutations in the BMPR II gene at 2q31-q32 are associated with primary pulmonary hypertension. *See* **Smad**.

bone sialoprotein 1 *see* **osteopontin**.

bongkrekic acid 3-carboxymethyl-17-methoxy-6,18,21-trimethyldocosa-2,4,8,12,14,18,20-heptaenedioic acid; a toxic antibiotic formed by *Pseudomonas cocovenenans* grown on partially defatted coconut. It is named after 'bongkrek', a product of mouldy Indonesian coconut that becomes highly toxic when the *Pseudomonas* outgrows the mould. It is an inhibitor of oxidative phosphorylation, an effect ascribable to its inhibitory action on mitochondrial adenine nucleotide translocation, apparently by fixing the adenine nucleotides to the translocation sites thus rendering dissociation of the nucleotides from the translocator rate-limiting in the overall transport process. *Compare* **atractyloside**.



bookmark *(in computing)* a URL stored in a browser file, usually to allow quick access to frequently used WWW pages.

booster dose a second or subsequent dose of antigen, especially in the form of a vaccine, given after the priming dose with the object of stimulating rapid production of large amounts of antibody.

bootstrap 1 *(in computing)* to restart a computer, often after a crash. **2** (*in statistics*) a form of randomization test that involves sampling data with replacement from the original data set, used to estimate the reliability of a result. Bootstrapping is used, for example, in phylogeny to assess the reliability of the branching structure in phylogenetic trees.

Born equation an equation for the free energy change, ΔG, when a sphere of charge e and radius r is brought into a uniform medium of unvarying dielectric constant D:

$$-\Delta G = (1-1/D)(e^2/2r).$$

[After Max Born (1882–1970), German-born British physicist.]

borohydride any member of a group of compounds with the structure MBH_4, where M is an alkali metal. These compounds will reduce aldehydes, ketones, and Schiff bases in nonaqueous solvents, and also acids, esters, acid chlorides, and nitriles. ^3H-labelled borohydrides are useful for the facile reductive tritiation of the aforementioned compounds.

boronyl the group $-B(OH)_2$; it is used attached to a matrix to complex with *cis*-diols (as in some saccharides).

borosilicate (glass) a silicate glass containing at least 5% boric oxide. Such a material has a high melting point and a low coefficient of thermal expansion, and hence is useful for the manufacture of heat-resistant glassware.

boss *symbol for* bride-of-sevenless gene (*see* **Sevenless protein**).

bottom yeast *the popular name for* any of various strains of **brewers' yeast** that effect fermentation at a comparatively low temperature and tend to sediment to the bottom of the fermentation vessel. It is used for the manufacture of light beers, e.g. lager. Bottom yeast is generally distinguishable from **top yeast** by its ability to produce extracellular *β*-galactosidase, EC 3.2.1.23.

botulinum toxin a mixture of neurotoxins formed by *Clostridium botulinum*, the causal agent of botulism, that is a potent inhibitor of acetylcholine release from cholinergic neurons. Neurotoxins A and B are homologous zinc metalloproteases that cleave synaptobrevin and synaptosome-associated protein 25 (SNAP 25), respectively. Both consist of a catalytic light (or L) chain disulfide-linked to a heavy (or H) chain that mediates binding of the toxin to, and channel formation in, the host cell membrane. Local injection of the toxin (popularly termed 'Botox') is used to remove wrinkles and frown lines and to decrease muscle spasticity in wrist and fingers following cerebral thrombosis. The type A precursor consists of 1295 amino acids; residues 1–447 form the L chain and 448–1295 form the H chain.

Bouguer–Beer law *another name for* **Beer's law** (def. 1).

Bouguer's law a physical law stating the relation between the amount of light transmitted by an absorbing medium and its thickness, based upon the finding that successive equal thicknesses of sheets of glass absorbed equal fractions of the light incident upon them. It may be expressed in the form $I_{trs} = I_0e^{-kd}$, where I_0 is the intensity of the incident light, I_{trs} is the intensity of the transmitted light, d is the thickness of the absorbing medium, and k is a constant. The law was later restated by Lambert — *see* **Lambert's law (of absorption)** — and extended to solutions by Beer — *see* **Beer's law** (def. 1). [After Pierre B. Bouguer (1698–1758), French astronomer and mathematician who discovered it in 1728.]

boundary any zone of transition, either between solvent and solution or between two solutions; i.e. a zone in which the composition of a solution changes.

boundary spreading the broadening of a boundary during ultracentrifugation of macromolecules due to the effects of diffusion.

bound-to-free ratio *abbr.*: B/F ratio; the ratio of the amount of a ligand bound by a specific macromolecule or receptor to the amount of ligand free in solution, in a specified system. Plotting [B]/[F] versus [F] yields a **Scatchard plot**.

boutique database *an alternative name for* **specialist database**.

bouvardin a cyclic hexapeptide isolated from the plant *Bouvarda ternifolia*, used as a drug against dysentery. It has anti-tumour properties and inhibits eukaryotic protein synthesis.

bovine of, belonging to, or characteristic of the ox tribe Bovini, which includes cattle, especially of the genus *Bos*.

bovine albumin *or* **bovine serum albumin** *see* **serum albumin**.

bovine pancreatic inhibitor *or* **bovine pancreatic trypsin inhibitor** *or* **basic protease inhibitor** a protein from cattle pancreas that inhibits trypsin, kallikrein, chymotrypsin, and plasmin. A popular molecule for studies on protein folding, etc., it contains three disulfide bonds. The sequence is:

RPDFCLEPPYTGPCKARIIRYFYNAKAGLCQT-
FVYGGCRAKRNNFKSAEDCMRTCGGA.

(10.903 kDa). The 3-D structure is also known.

bovine spongiform encephalopathy *abbr.*: BSE; a transmissible dementia in cattle, sometimes also known as 'mad cow disease', characterized by a spongy degeneration of neuronal cells in the brain and also enlargement of the astrocytes therein. It appears to be caused by a **prion**, and original outbreaks were thought to be the result of feeding cattle on offal derived from sheep infected with **scrapie**.

Bowman–Birk inhibitor *see* **soybean trypsin inhibitor**.

Bowman's capsule *or* **glomerular capsule** the dilated, cup-shaped vesicle at the proximal end of a nephron that encloses a knot of blood capillaries constituting the glomerulus. It is the site of primary filtration of blood into the nephron. [After William Paget Bowman (1816–92), British histologist and ophthalmic surgeon.]

Boyden chamber an apparatus, consisting of two small chambers separated by a micropore filter, used in the study of chemotaxis.

Boyle's law *see* **gas laws**. [After Robert Boyle (1627–91), Irish chemist and physicist.]

bp *symbol for* base pair(s).

b.p. *abbr. for* boiling point.

53Bp1 *abbr. for* p53 binding protein 1; a protein that contains tandem *BRCA1* C-terminal sequence motifs in its C-terminal region, through which it binds the tumour suppressor protein p53. It colocalizes with DNA damage response proteins and is a critical regulator of ATM protein in cell cycle checkpoint signalling. Mice deficient in 53Bp1 show growth retardation, immune deficiency, and sensitivity to irradiation and are cancer prone.

BP *abbr. for* **1** blood pressure. **2** British Pharmacopoeia.

BP-80 a membrane protein from pea and *Arabidopsis thaliana* that binds the N-terminal propeptide of several vacuolar proteins. It may be a receptor for a subset of these proteins and is produced in these plants by a multigene family. Homologues occur in the Golgi apparatus and in clathrin-coated vesicles .

BPAG *abbr. for* bullous pemphigoid antigen.

BPC *abbr. for* British Pharmaceutical Codex.

B peptide *or* **fibrinopeptide B** the 20-residue peptide cleaved from the β chains of a fibrinogen molecule when it is converted into fibrin by the proteolytic action of thrombin.

BPG *abbr. for* 2,3-bis(phospho)-D-glycerate.

BPI protein *abbr. for* bacterial/permeability-increasing protein; a potent antimicrobial lysosomal protein of polymorphonuclear leukocytes that binds lipopolysaccharide of Gram-negative bacteria, thereby neutralizing its effects. Comprising 456 residues, it is homologous with the plasma proteins LPS-binding protein, CETP (cholesteryl ester transfer protein), and PLTP (phospholipid transfer protein).

BPOC *abbr. for* biphenylisopropyloxycarbonyl-; an acid-labelling group for amino acids, introduced using, e.g., 2-(4-biphenylyl)-prop-2-yl 4′-methoxycarbonylphenylcarbonate (reagent structure shown).



***Bpu*1102 I** a type 2 **restriction endonuclease**; recognition sequence: GC↑TNAGC. *Esp*I is an **isoschizomer**.

Bq *symbol for* becquerel.

Br *symbol for* **1** bromine. **2** the butyryl group.

brachyurin EC 3.4.21.32; *other name*: collagenolytic proteinase; a serine proteinase that catalyses the hydrolysis of proteins with broad specificity for peptide bonds. It degrades native collagen at about 75% of the length of the molecule from the N terminus; it also shows low activity on small-molecule substrates of both trypsin and chymotrypsin.

Bradford assay a method for estimation of protein, based on binding of the dye **Coomassie brilliant blue** G-250. [After Marion M. Bradford, US biochemist.]

bradykinin *or* **kinin-9** *abbr.*: BK; a vasoactive nonapeptide, H-Arg-Pro-Pro-Gly-Phe-Ser-Pro-Phe-Arg-OH, formed by the action of **plasma kallikrein**, which hydrolyses the sequence out of the plasma globulin **kininogen**. Glandular kallikrein cleaves kininogen one residue earlier to give the decapeptide Lys-bradykinin (kallidin, *abbr.*: Lys-BK). Met-Lys-bradykinin is also formed, perhaps by the action of leukocyte kallikrein. Pharmacologically important analogues include des-Arg^9 or BK$_{1-8}$ and Ile-Ser-bradykinin (or T-kinin), [Hyp^3]bradykinin, and [Hyp^4]bradykinin. Bradykinin is formed in a variety of inflammatory conditions and in experimental anaphylactic shock. It is a powerful blood-vessel dilator, increasing vascular permeability and causing a fall in blood pressure; it is also a constrictor of smooth muscle. *See also* **lysine(arginine) carboxypeptidase**.

bradykinin receptor any membrane protein that binds bradykinin (BK) and mediates its intracellular effects. Two types of receptor are recognized: B$_1$ (previously BK$_1$), on which order of potency is des-Arg^9-bradykinin (*abbr.*: BK$_{1-8}$) = kallidin (Lys-BK) > BK; and B$_2$ (previously BK$_2$), with order of potency kallidin > BK >> BK$_{1-8}$. Hence, BK$_{1-8}$ is a powerful discriminator. B$_1$ receptors are considerably less common than B$_2$ receptors, which are present in most tissues. The rat B$_2$ receptor is a seven-transmembrane-domain protein which has been shown on activation to stimulate phosphoinositide turnover.

Bragg's law a law stating that when a crystal is pictured as a set of reflecting planes uniformly spaced at a distance d and a beam of X-rays of wavelength λ strikes the crystal at an angle θ, reinforcement of the reflected waves occurs when $\sin\theta = n\lambda/2d$, where n is an integer known as the **order of reflection**. [After William Lawrence Bragg (1890–1971), Australian-born British experimental physicist.]

brain-derived neurotrophic factor *abbr.*: BDNF; a protein that promotes the survival of neuronal populations located either in the central nervous system or directly connected to it. It is a key player in neuronal plasticity. Activity-dependent release of BDNF induces protein synthesis in dendrites via a receptor tyrosine kinase, and is important in induction of long-term potentiation.

brain natriuretic peptide *see* **natriuretic peptide**.

Brain tumor *see* **Pumilio**.

branch 1 a subdivision of the stem or the root of a plant; any smaller structure growing or arising from a larger one. **2** a side chain attached to the main chain of a molecular entity. **3** to form a branch; to bifurcate; to divide into offshoots. —**branched** *adj.*; **branching** *n.*

branch-and-bound *(in phylogeny)* a heuristic method for searching tree space for optimal trees. It is faster than an **exhaustive tree search**, but remains impractical for large numbers of taxa (e.g. more than 18).

branched-chain describing any molecular entity with one or more **branches** (def. 2).

branched-chain amino acid *abbr.*: BCAA; any of the neutral aliphatic essential amino acids L-leucine, L-isoleucine, and L-valine. They are incorporated into proteins or degraded oxidatively in mitochondria, especially in skeletal muscle, liver, and brain, and are ketogenic. BCAA infusions counteract the catabolic state of severe trauma and sepsis. Maple-syrup urine disease results from their defective oxidative decarboxylation.

branched-chain α-keto-acid dehydrogenase *abbr.*: BCKDH; EC 1.2.4.4; *recommended name*: 3-methyl-2-oxobutanoate dehydrogenase (lipoamide); *other name*: 2-oxoisovalerate dehydrogenase. An enzyme that catalyses the conversion of α-oxo acids to acyl-CoA and CO$_2$. Thiamine diphosphate is a coenzyme. The enzyme consists of a multienzyme complex of branched-chain α-keto-acid dehydrogenase (E1), lipoamide acyltransferase (E2), and lipoamide dehydrogenase (E3). The complex is associated with the matrix side on the inner mitochondrial membrane. In humans, E1 is a dimer of α (gene at 1p31) and β (gene at 7q31-q32) subunits; E2 is encoded by a gene at 1p31; and E3 is a homodimer (gene at 7q31-q32). Numerous mutations in each of these genes are associated with different forms of maple-syrup urine disease.

branched-chain α-keto-acid dehydrogenase kinase *see* **[3-methyl-2-oxobutanoate dehydrogenase (lipoamide)] kinase**.

branched-chain oxo-acid dehydrogenase phosphatase *see* **[3-methyl-2-oxobutanoate dehydrogenase (lipoamide)]-phosphatase**.

branched polymer any polymer in which there are side chains attached to a main chain.

brancher-deficiency amylopectinosis *an alternative name for* type IV **glycogen disease**.

branching *(in nuclear physics)* the simultaneous existence of more than one disintegration pathway for a particular radionuclide.

branching enzyme EC 2.4.1.18; *recommended name*: 1,4-α-glucan branching enzyme; *systematic name*: 1,4-α-D-glucan: 1,4-α-D-glucan 6-α-D-(1,4-α-D-glucano)-transferase; *other names*: amylo-(1,4–1,6)-transglycosylase; corn starch branching enzyme II; amylo-transglycosylase; glucanotransferase; starch branching enzyme II. Any 1,4-α-glucan branching enzyme that catalyses the transfer of a segment of 1,4-α-glucan chain to a primary C-6 hydroxyl group in a similar glucan chain. Branching enzymes fall into two types: the plant **Q-enzymes** and the mammalian enzymes, which are able to produce glycogen, a more highly branched molecule than the amylopectin produced in plants by Q-enzymes. The name should always be qualified, e.g. glycogen branching enzyme, amylopectin branching enzyme. Deficiency in humans results in glycogen disease type IV.

branch migration a proposed model to explain the occurrence of apparently branched DNA structures, as seen by electron microscopy, and their conversion into linear duplex DNA. The branched structures may form by association over parts of their lengths of three or more polynucleotide strands. The migration of the branch point is presumed to occur by displacement of a strand from its fellow in one branch by a strand in another. Such a process may occur in transcription or in recombination.

brassinolide *see* **brassinosteroid.**

brassinosteroid a class of steroids that contain 27, 28, or 29 carbon atoms, with different substituents on rings A and B and on the side chain. They occur in algae, ferns, gymnosperms, and angiosperms and induce a broad variety of biological responses. Brassinolide (a 28C steroid) is a plant growth regulator discovered in rape (*Brassica napus*) but widely distributed throughout the plant kingdom. It is the most active of the class, its immediate metabolic precursor being castasterone. The latter was discovered in insect galls of sweet chestnut (*Castanea crenata*) and has campesterol as a precursor.

BRCA either of two genes, *BRCA1* and *BRCA2*, implicated in susceptibility to breast cancer. Up to 80% of women who inherit mutated forms of either gene develop breast cancer, and *BRCA1* mutations imply a high risk of ovarian cancer. *BRCA1* (at 17q21) encodes 1863 amino acids. The protein includes a RING finger motif in the N-terminal region and two domains in the C-terminal region that are involved in DNA binding and in protein–protein interactions. It is implicated in transcriptional regulation of DNA damage-inducible genes that function in cell-cycle arrest. *BRCA2* (at 13q12-q13) encodes 3418 amino acids. The protein has histone acetyltransferase (HAT) activity and forms complexes with phosphorylated *BRCA1*, RAD51, and RAD52 for cell-cycle control and DNA repair through homologous recombination. Several hundred mutations in each gene have been reported.

brdU *or* **BrdU** *abbr. for* bromodeoxyuridine (the symbol BrdUrd is recommended).

BrdUrd *symbol for* bromodeoxyuridine. *Compare* **BrUrd**.

breakage and reunion model the classical and generally accepted model of chromosomal crossing-over; it involves breakage of the chromatids and reunion of the alternative fragments.

breakpoint cluster region term originally suggested for a limited region of 5–6 kb in the base sequence of chromosome 22, in which breakpoints involved in formation of the **Philadelphia chromosome** were found to cluster. Molecular cloning of specific areas of DNA (e.g. band 22q11) gave a probe specific for the breakpoint translocation domain. Subsequent work led to this region being identified as the ***BCR*** gene.

breathing *a colloquial term for* transient dynamic changes in the structure of macromolecules involving expansion and contraction of the 3-D structure.

brefeldin A a fungal metabolite, isolated from *Penicillium brefeldianum*, that inhibits a wide variety of membrane transformations of importance in intracellular transport. It effects a rapid increase in the volume of Golgi cisternae and loss of recognizable Golgi apparatus in treated cells. There is a rapid reversible dissociation of a Golgi-associated peripheral protein identical with a coat protein subunit of non-clathrin-coated vesicles (β-COP). *See* **coatomer**.



B region the site of final epoxidation of carcinogenic polycyclic aromatic hydrocarbons. It is located on the terminal ring of the **bay region** on a bond adjacent to the bay region. *Compare* **A region**, **K region**, **L region**.

brei a finely and uniformly ground tissue suspension containing all the enzymes of the original material but with the normal spatial relationships between them disrupted. *Compare* **homogenate**.

bremsstrahlung the **X-rays** produced when an electrically charged particle, usually a β particle or an accelerated electron, is decelerated by the electric field of an atomic nucleus. The yield is directly dependent upon the magnitude of the atomic number of the target element. [German: braking radiation.]

brevetoxin any of the highly toxic lipid-soluble polyether compounds isolated from *Ptychodicus brevis* (*Gymnodinium breve*), the red-tide organism. They cause the death of fish and are responsible for shellfish poisoning in humans. They are activators of voltage-dependent Na^+ channels.

brevican a **proteoglycan** that contains linked chondroitin sulfate chains and is expressed primarily in cerebellar astrocytes. It contains an N-terminal hyaluronan-binding domain. The bovine protein contains 912 amino acids.

brevin *an alternative term for* **gelsolin**.

brevinin a secreted amphibian peptide with antibacterial and hemolytic activities. Example, brevinin-1 from *Rana brevipoda porsa* has sequence FLPVLAGIAAKVVPALFCKITKKC.

brewers' yeast *the common name for* strains of the yeast *Saccharomyces cerevisiae* that are used in brewing. In addition to their ability to produce, and remain viable under, appreciable levels of ethanol, such strains are able to ferment maltose, maltotriose, and other sugars in the wort, and to withstand its relatively high osmotic pressure. *See also* **bottom yeast**.

bridge *(in chemistry)* a valence bond, atom, or unbranched chain of atoms connecting two different parts of a molecule.

bridgehead *(in chemistry)* either of the two atoms, e.g. tertiary carbon atomks, that are connected by a **bridge**.

bridge-receptor any molecular entity with two or more specific binding sites able to interact with and join a corresponding number of complementary ligands, which may or may not be the same.

bridging ligand a ligand that binds to two or more atoms, usually metals, linking them together to produce a polynuclear coordination complex. Bridging is indicated by the Greek letter mu (μ) appearing before the ligand name and separated by a hyphen. An example is sulfide in an **iron–sulfur cluster**.

Briggs–Haldane theory an alternative to the Michaelis–Menten theory of the kinetics of enzyme reactions for cases where breakdown of the enzyme–substrate complex to products is not slow in comparison with its dissociation to enzyme and substrate. *Compare* **Michaelis kinetics**. [After George Edward Briggs (1893–1985), British plant physiologist, and John Burdon Sanderson Haldane (1892– 1964), British enzymologist, geneticist, philosopher, and popularizer of science, who put forward their theory in 1925.]

Brij *proprietary name for* any of a series of polyethylene ethers of higher fatty alcohols. They are surfactants useful for the solubilization of membrane fractions. Brij 35 is polyoxyethylene (23) lauryl ether, aggregation number 40, CMC 92 μM.

Brilliant blue *see* **Coomassie blue**.

British antilewisite *abbr.*: BAL; *another name for* **dimercaprol**.

British thermal unit *abbr.*: Btu; a non-SI unit given by the energy required to raise the temperature of 1 pound of water through 1 °F. Since this depends on the temperature of the water, the temperature range should be specified. The Btu(mean), defined as the 1/180 part of the energy required to raise the temperature of 1 pound of water from 32 °F to 212 °F, is equal to 1055.06 J.

Brix *abbr. for*: biogenesis of ribosomes in *Xenopus*; a protein involved in ribosome assembly, that colocalizes with fibrillarin in nucleoli, and associates with the RNA of large ribosomal subunits. Comprising 339 residues, it contains a central globular domain (≈150–180 residues) found in about 50 other proteins. Knockout of the yeast orthologue is lethal and produces defects in synthesis of the large ribosomal subunit.

Brk *abbr. for* Bek-related kinase; *an alternative name for Cek2*. *See* ***Cek***.

BRN a family of neurally expressed genes encoding brain-specific transcription factors. They contain a **POU domain**. Brn-3.1 and Brn-3.2 modulate the terminal differentiation of auditory and visual system development respectively.

broad host range relating to the ability of a plasmid to be subjugated as a vector in a broad range of hosts, especially Gram-negative bacteria. Such plasmids are also termed promiscuous.

broad-spectrum antibiotic any antibiotic that is active against a wide range of bacterial species.

Brockmann body a discrete organ, occurring in fish, that contains tissue corresponding to that found in the islets of Langerhans of mammals. One or more Brockmann bodies occur in various teleost species. They are free of pancreatic acinar tissue, which makes them particularly suitable for biochemical studies and a good source of fish insulin. The principal islet weighs in the region of 1–50 mg; smaller secondary islets may also occur.

Brodie's fluid a **manometer fluid** containing 23 g NaCl, 5 g sodium tauroglycerate, 100 mg Evan's Blue, and a few drops of an ethanolic thymol solution, in 1000 mL of water; $D = 1.033$. The standard pressure (760 mmHg) in mm of manometer fluid is 10 000.

brom+ *a variant form of* **bromo+**.

bromelain *or* **bromelin** either of two similar **cysteine proteinases**: **stem bromelain**, EC 3.4.22.32, isolated from the stem of the pineapple, *Ananas comosus*; and **fruit bromelain**, EC 3.4.22.33, from the same plant. They are broad-specificity proteinases, similar to other cysteine proteinases but with so far unique geometry and reactivity at the active site. The two types of enzyme are distinguished by the substrate Z-Arg-Arg-NHMec, which is hydrolysed by stem bromelain but not by fruit bromelain.

bromination the introduction of one or more bromine atoms (bromo residues) into an organic molecule, whether by addition or substitution. —**brominate** *vb.*

bromine *symbol*: Br; a halogen element of group 17 of the IUPAC **periodic table**; atomic number 35; relative atomic mass 79.909. Natural bromine consists of the two isotopes ^{79}Br and ^{81}Br at almost equal relative abundances.

bromine-82 the radioactive nuclide $^{82}_{35}$Br; half-life 35.3 h; it emits beta radiation (0.444 MeV) and gamma radiation of various energies.

bromo+ *or (sometimes before a vowel)* **brom+** *prefix* denoting a bromine atom in organic linkage.

bromocriptine *or* **bromoergocriptine** 2-bromoergocryptine; an ergotoxin **ergot** alkaloid derivative that acts as a dopamine (D_2) receptor agonist. It inhibits the secretion of prolactin and somatotropin by the pituitary gland, and has potential applications in the treatment of Parkinson's disease.



bromodeoxyuridine *symbol*: BrdUrd; 5-bromo-2′-deoxyuridine; 5-bromouracil 2′-deoxyriboside; a synthetic analogue of thymidine. It acts as an inhibitor of cell differentiation, and also has antiviral properties. *See* **bromouracil**.

bromodomain a domain present in some 75 proteins that forms a left-handed four-helix bundle whose pocket interacts with *ε-N*-acetyl-lysyl residues in the N-terminal segments of core histones. It is also present in many transcriptional regulators that have intrinsic histone acetyltransferase activity.

Bromophenol Blue a dye used as a pH indicator, changing from yellow to blue over the pH range 3.0–4.6



Bromophenol Red a dye used as a pH indicator, changing from yellow to red over the pH range 5.2–6.8



***N*-bromosuccinimide** *abbr.*: NBS; an oxidizing and brominating agent, used for the oxidation of tryptophan residues in proteins. Tyrosine, histidine, and methionine may be oxidized to a lesser extent.



Bromothymol Blue a dye used as a pH indicator, changing from yellow to blue over the pH range 6.0–7.6



bromouracil *symbol*: BrUra; 5-bromouracil; 5-bromo-2,4(1*H*,3*H*)-pyrimidine-dione; a synthetic analogue of thymine with mutagenic activity. It is incorporated into DNA as **bromodeoxyuridine**, which replaces thymidine and induces transitions of G–C base-pairing to

A–T pairing. It can be used as a density marker for DNA. The free compound is an inhibitor of dihydrouracil dehydrogenase.



bromouridine *symbol*: B *or* BrUrd; 5-bromouridine; 5-bromouracil riboside; a synthetic analogue of ribothymidine.

Brønsted catalysis law an expression of the relation between the rate constant, *k*, of a catalysed reaction, and the p*K* of the catalyst: $\log k = c + b\mathrm{p}K$, where *b* and *c* are constants and the value of *b* provides a measure of the balance between nucleophilic and general base character of the catalysis. [After Johannes Nicolaus Brønsted (1879–1947), Danish physical chemist.]

Brønsted–Lowry acid any chemical species capable of donating a hydron to a base. Examples are H_2O, H_3O^+, CH_3COOH, $H_2PO_4^-$, NH_4^+. [After J. N. Brønsted (*see* **Brønsted catalysis law**) and Thomas Martin Lowry (1874–1936), British chemist.]

Brønsted–Lowry base any chemical species capable of accepting a hydron from an acid. Examples are OH^-, H_2O, CH_3COO^-, HPO_4^{2-}, NH_3.

Brookhaven database *see* **PDB**.

broth *(in bacteriology)* any liquid culture medium, especially nutrient broth.

brown adipose tissue a highly specialized tissue with a high content of lipid and cytochromes found in some animals, particularly hibernating animals and the newborn of some species. It is highly vascular and consists of small polygonal cells, each containing many separate lipid droplets and many mitochondria. Its function is thermogenesis during the arousal period after hibernation or, in the young, to provide heat before shivering has developed. It is active also in normal but not in obese humans. The colour is due to the high cytochrome content. Heat is generated by lipid oxidation through electron transport not coupled to oxidative phosphorylation. The uncoupling is mediated by **brown fat uncoupling protein**. *Compare* **white adipose tissue**.

brown fat uncoupling protein *abbr.*: UCP; *other names*: mitochondrial UCP; thermogenin; a dimeric integral mitochondrial inner membrane protein that forms a H^+-channel, is unique to brown adipose tissue mitochondria, and is important for thermogenesis of this tissue. By causing the membrane to leak protons, it abolishes the proton gradient that drives oxidative phosphorylation, so that electron transport results solely in heat production.

Brownian movement the peculiar random movements shown by microscopic particles in a disperse phase, i.e. when suspended in a liquid or gas. It is caused by the continuous irregular bombardment by the molecules of the surrounding medium. [After Robert Brown (1773–1858), British botanist who first observed it in 1827.]

browning reaction any of a group of complex reactions, both enzymic and nonenzymic, that occur in some foods during processsing and/or storage and cause a brownish discoloration. Members of this group include the oxidation of phenolic compounds (which is believed to be enzymic) together with caramelization, ascorbate decomposition, and the **Maillard reaction** (all of which are believed to be nonenzymic).

BRUCE *abbr. for* baculovirus repeat-containing ubiquitin-conjugating enzyme. *See* **Apollon**.

brucine 2,3-dimethoxystrychnidin-10-one; a highly toxic bitter-tasting alkaloid obtained from *Strychnos* seeds. It is used as a resolving agent for some racemates. *Compare* **strychnine**.



BRUNO a protein of *Drosophila* that is essential for repression of mRNA for the ***oskar***-encoded protein as it is in transit from nurse cells to the posterior pole of the oocyte.

BrUra *symbol for* bromouracil.

BrUrd *symbol for* bromouridine (alternative to B). *Compare* **BrdUrd**.

brush border the dense covering of **microvilli** on the apical surface of epithelial cells in the intestine and kidney. The microvilli aid absorption by increasing the surface area of the cell.

Bruton's tyrosine kinase a cytoplasmic protein-tyrosine kinase expressed throughout B lymphocyte differentiation and in myeloid cells but not in the B lymphocyte lineage. The locus at Xq22 encodes a protein of 659 amino acids that contains: an N-terminal plekstrin homology domain that binds phosphoinositides, protein kinase C, and subunits of trimeric G-proteins; a region that is proline-rich and binds SH3 domains; and a C-terminal kinase domain. It is a mediator of radiation-induced apoptosis of lymphoma B lymphocytes. Over 400 mutations in the gene are associated with X-linked agammaglobulinemia. [After Ogden C. Bruton (1908– 1994), US paediatrician.]

bryostatin any of a number of highly potent activators of protein kinase C found in bryozoans, especially *Bugula neritina*. They were isolated as the active anti-leukemic agent of bryozoan extracts. They block phorbol ester-induced differentiation of human promyelocytic leukemia cells and other actions of phorbol esters.



bryostatin 1

BSA *abbr. for* bovine serum albumin. *See* **serum albumin**.

BSE *abbr. for* bovine spongiform encephalopathy.

B side the side of the nicotinamide ring of NADH or NADPH at which projects the *pro-S* hydrogen atom (known as H_B) at the 4 position. *Compare* **A side**.

***Bsp*1286I** a type 2 **restriction endonuclease**; recognition sequence: G[AGT]GC[ACT]C. *Sdu*I is an **isoschizomer**.

***Bsp*1407I** a type 2 **restriction endonuclease**; recognition sequence: T↑GTACA.

***Bsp*T104I** a type 2 **restriction endonuclease**; recognition sequence: TT↑CGAA. *Asu*II and *Nsp*V are **isoschizomers**.

***Bsp*T107I** a type 2 **restriction endonuclease**; recognition sequence: G↑G[TC][AG]CC. *Hgi*CI is an **isoschizomer**.

***Bss*HII** a type 2 **restriction endonuclease**; recognition sequence: G↑CGCGC. *Bse*PI is an **isoschizomer**.

***Bst*1107I** a type 2 **restriction endonuclease**; recognition sequence: GTA↑TAC. *Sna*I is an **isoschizomer**.

***Bst*PI** a type 2 **restriction endonuclease**; recognition sequence: G↑GTNACC. *Bst*EII and *Eco*065I are **isoschizomers**.

***Bst*XI** a type 2 **restriction endonuclease**; recognition sequence: CCANNNNN↑NTGG.

BTEE *abbr. for* *N*-benzoyl-L-tyrosine ethyl ester (a substrate for the assay of chymotrypsin).

B-transferase EC 2.4.1.37; *recommended name*: fucosylglycoprotein 3-*α*-galactosyltransferase; *other name*: [histo-blood group] B transferase; an enzyme that catalyses the reaction:

UDPgalactose + glycoprotein *α*-L-fucosyl-(1,2)-D-galactose = UDP + glycoprotein *α*-D-galactosyl-(1,3)-[*α*-L-fucosyl-(1,2)]-L-galactose,

thus adding galactose to the H antigen of the **ABH antigen** system, leading to formation of the B antigen. The protein is a product of one allele of the *ABO* gene. It has virtual identity of sequence with that catalysing **A-transferase** activity, differing only at residues 176 (A has Arg, B has Gly), 235 (A Gly, B Ser), 266 (A Leu, B Met), and 268 (A Gly, B Ala).

BT toxin *abbr. for Bacillus thuringiensis* toxin; any of a class of related protein toxins produced by different subspecies of the bacterium *Bacillus thuringiensis*. They are insecticidal and have been used, by spraying or by transgenic expression, to protect crops (e.g. cotton, maize, potato). The CryIA(a) toxin is active against lepidopterans, whereas CryIIIA toxin is active against coleopterans. The crystal structures of both have been elucidated.

Btu *abbr. for* British thermal unit.

Bu *symbol for* the butyl group.

BU *(sometimes) abbr. for* bromouracil (BrUra is recommended).

bubble column a column-shaped bioreactor in which the reaction medium is kept mixed and aerated by the introduction of air at the bottom.

Büchner funnel a cylindrical funnel for filtration, usually of porcelain or plastic, that includes a perforated plate on which a filter paper is placed. It is generally used with a vacuum. *See also* **Hartley filter funnel**.

bud 1 a small lateral or terminal protuberance on the stem of a plant that contains undeveloped foliage or floral leaves. **2** a budlike protuberance on the surface of a yeast cell or other simple organism. **3** to form a bud. **4** to reproduce asexually, as in yeasts, by the process of **budding**.

budding 1 the production of a bud or buds. **2** a form of asexual reproduction, occurring in certain bacteria and fungi (e.g. yeasts) and some primitive animals in which an individual arises from a daughter cell formed by pinching off a part of the parent cell. The budlike outgrowths so formed may sometimes remain attached to the parent cell.

BUdR *or* **BUDR** *(sometimes) abbr. for* bromodeoxyuridine (the symbol BrdUrd is preferred).

bufadienolide any of various naturally occurring doubly unsaturated lactones of certain steroids with important pharmacological effects on heart muscle (*see* **cardiac glycoside**). They are so named because they were originally found in the venomous secretion of the skin glands of some toads (*Bufo*), and are hence also known as **toad poisons**. They also occur in certain plants, e.g. *Digitalis*. *See also* **bufogenin B**.

buffer 1 any substance or mixture of substances that, when dissolved (usually in water), will maintain its solution at approximately constant pH despite small additions of acid or base. The commonest examples are moderately strong solutions containing both a weak acid and its conjugate base (or a weak base and its conjugate acid). A substance is useful as a buffer over a range of about one pH unit either side of its p*K*, but is most effective at or near the p*K*. Buffer substances used for biochemical or biological purposes include: acetate, bicarbonate, bis-tris propane, borate, citrate, dimethylmalonate, glycinamide, glycylglycine, imidazole, phosphate, succinate, and **Tris** together with any **good buffer substances**. By extension, the term may be applied to agents controlling the activities of various other specified entities, e.g. redox buffer, carbon-dioxide buffer, metal-ion buffer. Also used attributively: e.g. buffer action; buffer salt; buffer solution. **2** a solution of a **buffer** (def. 1). **3** a short-term storage facility (e.g. as part of the memory of a computer), especially one whose patterns or rates of input and output can differ. **4** to treat with or to incorporate a buffer (def. 1); to act as a buffer. *See also* **buffering capacity**, **buffer value**. —**buffered** *adj.*; **buffering** *n.*

buffering capacity *or* **buffering power 1** the number of gram-equivalents of either hydrogen ions or hydroxide ions required to change the pH of 1 litre of 1 m buffer solution by one unit. Buffering capacity = $(1/m)\,(\mathrm{d}n/\mathrm{dpH})$, where m is the number of moles of buffer, and dpH is the pH change produced by addition of dn equivalents of hydrogen ions or hydroxide ions. **2** *an alternative term for* **buffer value**.

buffer solution *see* **buffer** (def. 2).

buffer value *or* **Van Slyke buffer value** *or* **buffering capacity** *symbol*: β; the amount of acid or base, in gram-equivalents, needed to change the pH of 1 litre of a buffer solution by one unit at any pH; i.e. $\beta = \mathrm{d}b/\mathrm{dpH}$, where b is the molar concentration of base in the solution. [After Donald Dexter Van Slyke (1883–1971), US biochemist, who described it in 1922.]

buffy coat the layer of white cells that forms between the layer of red cells and the plasma when unclotted blood is centrifuged or allowed to stand.

bufogenin B 3*β*,14,16*β*-trihydroxy-5*β*-bufa-20,22-dienolide; a **bufadienolide** found in the Chinese drug Ch'an Su, prepared from Chinese toads (*Bufo asiaticus*).



bulge loop a structure in a polynucleotide duplex in which one strand contains a nonterminal extra sequence that is not able to base-pair with the second strand, thereby forming a bulge on one side of the duplex.

bullous pemphigoid antigen *abbr.*: BPAG; either of two proteins present in epithelia, to which autoantibodies are present in bullous pemphigoid (an acquired disease characterized by subepidermal blistering). BPAG1e (BPAG epithelial, 230 kDa) is an intracellular coiled-coil protein that attaches keratin intermediate filaments to hemidesmosomes. It is highly homologous with desmoplakin and plectin. BPAG1n is a neuronal isoform. The gene at 6p11-p12 encodes a protein of 2632 residues, and mutations in the mouse orthologue are associated with dystonia musculorum. BPAG2 (180 kDa) is a type XVII collagen and has a cytoplasmic N-terminal domain, one transmembrane segment, and an extracellular C-terminal domain that consists of 15 Gly–X–Y repeats interrupted by other short sequences. Mutations in the gene on 10q24.3 (for type XVII procollagen α1 chain) are associated with a benign form of epidermolysis bullosa.

BUN *abbr. for* blood urea nitrogen, an index of the blood-urea concentration.

bundle sheath a parenchymal sheath surrounding a vascular bundle in plants.

bungarotoxin any of various neurotoxins derived from the venom of the elapid snake, *Bungarus multicinctus*. The chief components are: (1) α bungarotoxin, a single polypeptide chain of 74 amino-acid residues; it is an irreversible antagonist of nicotinic cholinergic receptors and causes paralysis; (2) β bungarotoxin, a multicomponent protein composed of two polypeptide chains: a long chain (120 amino-acid residues) and a short chain (60 residues); it prevents the release of acetylcholine from cholinergic neurons.

Bunsen coefficient *symbol*: α; the absorption coefficient of a gas in a solution. It is defined as the volume of gas in litres, reduced to 273.15 K and 1 atm (101 325 Pa) pressure, that dissolves in 1 litre of liquid when the partial pressure of the gas in the gas phase is 1 atm. [After Robert Wilhelm Bunsen (1811–99), German chemist.]

bunyavirus any of a group of RNA animal viruses consisting of enveloped particles, 90–100 nm in diameter with helical nucleocapsids, and containing segmented RNA (minus strand) of 3–4 MDa. The group has been recognized as different from **togaviruses** and includes arthropod-borne viruses that can cause encephalitis.

buoyant density the density of a solute molecule as determined by density-gradient ultracentrifugation. It is the density of the solution, ρ, at the point in the gradient where: $\rho = 1/\gamma$, where γ is the **partial specific volume** of the solute in question.

buoyant force *symbol*: F_B; the force acting on an object suspended in a liquid due to the liquid displaced by the object. It is given by: $F_b = V_p \rho_m g$, where V_P is the volume of the object, ρ_m is the density of the displaced liquid m, and g is the acceleration due to gravity.

Bureau International des Poids et Mesures the agency in Sèvres, near Paris, that maintains the SI system of units.

burette *or (US)* **buret** a graduated (often glass) tube with a pinchclamp, stopcock, or valve at one end used for measuring or dispensing known volumes of fluids, especially liquids. A graduated syringe used for the same purpose may also be termed a burette.

Burkitt's lymphoma a malignant tumour of the lymphatic system, most commonly affecting children in tropical Africa within 15° north and south of the equator. **Epstein–Barr virus** can be demonstrated in a proportion of cultured tumour cells though it is unlikely that the virus is the sole cause of the malignancy. [After Denis Parsons Burkitt (1911–93), British surgeon.]

Burnet's theory of immunity *see* **clonal selection theory**.

bursacyte *an alternative name (archaic) for* **B lymphocyte**.

bursa of Fabricius *or* **cloacal bursa** a saclike lymphoepithelial structure opening into the dorsal part of the cloaca in young birds. It usually degenerates as the birds reach maturity. It is associated with humoral immunity and the lymphocytes processed by it are termed **B lymphocytes**. In mammals it is likely that hemopoietic tissue itself fulfils the equivalent role, providing the appropriate microenvironment for the maturation of B lymphocytes from precursor stem cells.

bursectomy removal of the **bursa of Fabricius**, either by surgery *in ovo* or shortly after hatching, or by destruction *in ovo* by application of, e.g., testosterone. Bursectomy inhibits the formation of **B lymphocytes** and hence circulating antibody.

bursin the tripeptide Lys-His-Gly-NH_2; a selective B-cell differentiating hormone from the bursa of Fabricius of chickens.

burst 1 the initial pre-steady-state liberation of the first product, B, in an enzymic reaction of the type: $E + AB = EAB \rightarrow EA + B$ and $EA \rightarrow E + A$, where E is the enzyme and A is the second product. **2** the sudden release of phage particles accompanying lysis of a phage-infected bacterial cell. *See also* **burst size, respiratory burst**.

burst size the mean number of bacteriophage particles set free per infected bacterium upon lysis of phage-infected cells.

butanediol fermentation a type of fermentation effected by some members of the Enterobacteriaceae, e.g. *Enterobacter*, *Erwinia*, *Klebsiella*, and *Serratia*, in which glucose is fermented with the production of 2,3-butanediol and other substances.

butanoyl *another name for* **butyryl**.

butyl *symbol*: Bu; the alkyl group, $CH_3–[CH_2]_2–CH_2–$, derived from butane.

butylated hydroxytoluene *an alternative name for* **di-*tert*-butyl-*p*-cresol**.

butyl-PBD *see* **biphenylylphenyloxadiazole**.

butyrate 1 *trivial and preferred name for* **butanoate**; the anion $CH_3–[CH_2]_2–COO^–$, derived from butyric acid (butanoic acid), a saturated, unbranched, aliphatic acid. **2** any mixture of free butyric acid and its anion. **3** any salt or ester of butyric acid.

butyric acid fermentation a type of fermentation effected by some saccharolytic species of *Clostridium*, e.g. *C. butyricum*, in which glucose is fermented, with the production of acetic acid, butyric acid, carbon dioxide, and dihydrogen.

butyrophenone any of a group of antipsychotic drugs, e.g. **haloperidol**, that are more selective than the **phenothiazine** group. Butyrophenones interact rather more specifically with dopamine D_2 receptors and reduce the firing of dopaminergic neurons.

butyrophilin a type I **membrane protein** of mammary gland, probably involved in stimulating the secretion of droplets of fat in milk.

butyryl *symbol*: Br; *trivial and preferred name for* **butanoyl**; the acyl group, $CH_3–[CH_2]_2–CO–$, derived from butyric acid (butanoic acid).

BX-C *abbr. for* the bithorax complex, one of two (*see* **ANT-C**) major families of **homeotic genes** in *Drosophila*, mutations in which affect thoracic and abdominal segments.

byssus an elastomeric protein of bivalve molluscs, threads of which attach mussels to hard surfaces such as rocks. It consists of 882 amino acids; the N- and C-terminal regions are histidine-rich domains, while the central region is a collagen-like domain flanked by elastomeric domains.

byte a single unit of information handled by a computer; the binary unit required for storage of a character, usually comprising eight **bits**.

Bz *symbol for* the benzoyl group.

bZIP *abbr. for* basic zipper; a characteristic feature of a family of proteins that possess a basic region (b) and a **leucine zipper** domain (ZIP). The basic region harbours a DNA-contact surface, and the leucine zipper domain is essential for homodimer formation, or formation of heterodimers with other leucine zipper proteins. The family includes the **AP**, **ATF**, and **CREB protein** transcription factors.

Bzl *symbol for* the benzyl group.

BZLF1 one of a group of transcription factors related to the *jun* and *fos* gene products. It is involved in the switch from latency to virus-particle production following infection by **Epstein–Barr virus**.

Cc

c 1 *symbol for* **a** centi+ (SI prefix denoting 10^{-2}). **b cyclic** (def. 3) or **cyclo+** (denoting cyclic compounds, as in cAMP for cyclic AMP or Hx_c for cyclohexyl. **c** *(obsolete)* **curie** (use Ci). **2** *abbr. for* **a** complementary (as in **cDNA**). **b** ***cis*** (not recommended). **c** *(obsolete)* cubic (i.e. to the third power).

c- *(in genetics) prefix* denoting cellular, as in c-*myc*, the cellular as opposed to viral (v-) version of a (proto)oncogene; *see*, e.g., ***MYC***.

c *symbol for* **1** amount-of-substance concentration; that for a particular substance may be denoted by adding a subscript, e.g. c_B for amount concentration of a substance B. **2** speed (alternative to *v*, *u*, or *w*). **3** (bold italic) velocity (alternative to ***v***, ***u***, or ***w***).

c- *abbr. for* ***cis-***.

c_0 *symbol for* speed of light *in vacuo*. the subscript may be omitted when there is no risk of ambiguity.

C 1 *symbol for* **a** carbon; *see* **carbon-11**, **carbon-12**, **carbon-13**, **carbon-14**. **b** designating a specific carbon atom, e.g. C-1, C-2. **c** a residue of the α-amino acid L-cysteine (or L-half-cysteine) (alternative to Cys). **d** a residue of the base cytosine in a nucleic acid sequence. **e** a residue of the ribonucleoside cytidine (alternative to Cyd). **f coulomb**. **g** *or (formerly)* C′ complement (the main components of complement are designated C1–C9). **2** *see* **programming language**.

°C *symbol for* degree Celsius (*formerly* degree centigrade). *See* **Celsius temperature**.

C_H *symbol for* the constant region of an immunoglobulin **heavy chain**. The particular constant domain in question may be indicated as C_H1, C_H2, C_H3.

C_L *symbol for* the constant region of an immunoglobulin **light chain**.

C *symbol for* **1** capacitance. **2** heat capacity (C_p at constant pressure, C_V at constant volume, C_m molar heat capacity). **3** number concentration (C_B for a substance B).

C- *(in chemical nomenclature)* a locant indicating substitution on carbon; a particular carbon atom may be specified by a right superscript.

-*C* a conformational descriptor designating the **chair conformation** of a six-membered ring form of a monosaccharide or monosaccharide derivative. Locants of ring atoms that lie on the side of the structure's reference plane from which the numbering appears clockwise are indicated by left superscripts and those that lie on the other side of the reference plane by right subscripts; e.g. $-^1C_4$, $-^4C_1$. *See also* **conformation** (def. 2).

$-^1C_4$ *or (formerly)* **-1*C*** conformational descriptor for an aldopyranose in the chair conformation, with C2, C3, C5, and O5 in the structure's reference plane, and with C1 above and C4 below the plane; e.g. α-D-glucopyranose-$^1C_4$.



$^1C_4$

$-^4C_1$ *or (formerly)* ***-C1*** a conformational descriptor for an aldopyranose in the chair conformation, with C2, C3, C5, and O5 in the structure's reference plane, and with C1 below and C4 above the plane; e.g. α-D-glucopyranose-$^4C_1$.



$^4C_1$

C++ *see* **programming language**.

Cα *symbol for* **alpha carbon atom**.

Cβ *symbol for* **beta carbon atom**.

Ca *symbol for* calcium.

CAA a codon in mRNA for L-glutamine.

CAAT box *or* **CAT box** a conserved sequence in DNA found within the **promoter** region of the protein-encoding genes of many eukaryotes. It has the consensus sequence GGCCAATCT and is believed to determine the efficiency of transcription from the **promoter**.

CAAX *abbr. for* Cys–aliphatic–aliphatic–X; a C-terminal tetrapeptide motif that is present in proteins that become prenylated. Following prenylation, the AAX is removed by a CAAX-prenyl endopeptidase (a metal-dependent integral membrane protein) and the new C-terminal cysteine is carboxymethylated.

Cab-O-Sil *proprietary name for* **fumed silica** supplied by Cabot Carbon Ltd.

CaBP3 *see* **calreticulin**.

CAC a codon in mRNA for L-histidine.

cachectic factor a 24 kDa proteoglycan isolated from the murine adenocarcinoma MAC16 that has been implicated in the production of **cachexia**. The peptide has the N-terminal sequence YDPEAASAPGSGDPSHEA, and has *N*- and *O*-glycans. Intravenous injection of the proteoglycan induces rapid weight loss.

cachectin *see* **cachexia**, **tumour necrosis factor**-α.

cachexia a condition caused by chronic disease, such as cancer, and characterized by wasting, emaciation, feebleness, and inanition. It led to the name 'cachectin' for the protein now known as **tumour necrosis factor** but a 24 kDa proteoglycan has more probably been implicated in this. *See* **cachectic factor**.

CACNA1A *abbr. for* calcium channel alpha subunit 1A. *See* **hemiplegic migraine**.

cacodylate 1 dimethyl arsinate, the anion $(CH_3)_2$–$AsOO^-$ derived from cacodylic acid. It is useful as a buffer substance ($pK_a = 6.2$). **2** any salt of cacodylic acid.

CAD 1 *or* **CAD protein** a multifunctional protein found in many eukaryotes and containing domains for three enzymes of pyrimidine biosynthesis: **carbamoyl phosphate synthase** (glutamine-hydrolysing); **aspartate transcarbamylase**; and **dihydroorotase**. **2** *abbr. for* caspase-dependent DNase; a lysosomal enzyme that cleaves DNA in cells undergoing **apoptosis**.

cadaverine 1,5-pentanediamine; a substance formed by microorganisms in decaying meat and fish by the decarboxylation of lysine. It also occurs as an intermediate in the biosynthesis, via lysine, of some quinolizidine alkaloids (e.g., lupinine) in plants.

cadherin any member of a family of calcium-dependent cell adhesion proteins that preferentially interact in a homophilic manner in cell–cell interactions. Cadherins may thus contribute to the sorting of heterogeneous cell types; they are type I **membrane proteins**. The names of different classes indicate the tissues in which they were first found: E-cadherin is present on many types of epithelial cells; N-cadherin is present on nerve, muscle and lens cells; and P-cadherin is present on placental and epidermal cells. Typically, cadherins have five similar extracellular domains, the outermost three of which have Ca^{2+}- binding sites, and an intracellular C-terminal domain that interacts with the actin cytoskeleton.

cadmium mycophosphatin a cadmium-binding phosphoglycoprotein, M_r 12 000; it lacks sulfur-containing amino acids, but is rich in aspartic and glutamic acids, and phosphoserine.

CAD protein a multifunctional protein found in many eukaryotes, and containing domains for three enzymes of pyrimidine biosynthesis: **carbamoyl phosphate synthase** (glutamine-hydrolysing); **aspartate transcarbamylase**; and **dihydroorotase**.

cadystin the **phytochelatin** of *Saccharomyces pombe*.

Caenorhabditis elegans a nematode (roundworm), with a genome of about 97 million base pairs. Its cellular anatomy has been fully described, and the nucleotide sequence of the genome determined, revealing over 19 000 genes, 40% of the predicted protein products having significant matches in other organisms.

caerulein *the Brit. spelling of* **cerulein**.

caeruloplasmin *the Brit. spelling of* **ceruloplasmin**.

caesium *alternative spelling (esp. Brit.) for* cesium.

CAF1 *abbr. for* chromatin assembly factor 1; a complex of p150 and p60 subunits, present in *Drosophila* and human cells, that is responsible for chaperoning histones H3 and H4 to DNA during replication. The p60 gene maps to a locus on chromosome 21 that is strongly associated with the major features of Down syndrome. *See* **NAP1**.

caffeine 1,3,7-trimethylxanthine, 3,7-dihydro-1,3,7-trimethyl-1*H*-purine-2,6-dione; a substance found in certain plants, notably in tea and coffee and the beverages derived from them. It is an adenosine (A_1 and A_2) receptor antagonist and phosphodiesterase inhibitor, and a stimulant of the central nervous system, affecting the cardiovascular system and causing diuresis. Its actions are similar to those of **theophylline** but less potent.



caffetannic acid *an alternative name for* **chlorogenic acid**.

CAG a codon in mRNA for L-glutamine.

cage carrier *see* **ionophore**.

cage compound **1** *an alternative name for* **clathrate** (def. 1). **2** any compound possessing a nonplanar bicyclic or polycyclic molecular structure that encloses a cavity.

caged ATP a type of protected ATP analogue, e.g. adenosine-5′-triphospho-1-(2-nitrophenyl)ethanol (or the methanol-containing equivalent), that releases ATP in good yield when photolysed by a short pulse of light of 360 nm wavelength. Similarly, guanosine-5′-triphospho-1-(2-nitrophenyl)ethanol is used as **caged GTP**. These compounds can be introduced into cells prior to photolysis. Caged ATP has been used, e.g., to study muscle contraction on the millisecond timescale.

caged GTP *see* **caged ATP**.

Cahn–Ingold–Prelog rule *or* **Cahn–Ingold–Prelog system** *an alternative name for* **sequence rule**.

CAK *see* **Cdk-activating kinase**.

cal *symbol for* calorie.

calbindin *other names*: cholecalcin; calbindin D9K; CABP; vitamin D-dependent calcium-binding protein; an **EF-hand** Ca^{2+}- binding protein from intestine. It is present in a variety of cells, including absorptive cells of the duodenum (in which its synthesis is vitamin D_3-dependent), in hippocampal cells, and in kidney.

calcemic factor *or (esp. Brit.)* **calcaemic factor** the prohormone of **parathyrin**.

calcidiol *the recommended trivial name for* calcifediol, 25-hydroxycholecalciferol. It is formed in liver from cholecalciferol, and is the major store of the vitamin in the body, being present largely in plasma. It is the precursor of the hormonal form of the vitamin, calcitriol. *See also* **vitamin D**.



calciductin *a name proposed for a* 23 kDa sarcolemmal protein that, when phosphorylated by a cAMP-dependent protein kinase, causes an approximately two-fold stimulation of the slow Ca^{2+} inward current.

calcifediol 25-hydroxyvitamin D_3; *another name for* **calcidiol**. *See also* **vitamin D**.

calciferol *an alternative (older) name for* **ergocalciferol**, also known as vitamin D_2. *See also* **vitamin D**.

calcification the deposition of calcium salts in the tissues. It is part of the normal process of bone formation in which **hydroxyapatite** crystals are deposited, in the neighbourhood of osteoblast cells, in a pre-existing collagen-containing matrix.

calcified describing a tissue that has been solidified by deposition of calcium; having undergone **calcification**.

calcimedin *see* **annexin**.

calcimycin *see* **A23187**.

calcineurin *or* **protein phosphatase 2B** (*abbr.*: PP-2B) *or* **CaMBP$_{80}$** a major heat-labile calmodulin-binding protein isolated from bovine brain, but later found in all cells from yeast to mammals. It has protein serine/threonine phosphatase activity, and is classified as a protein phosphatase 2B (EC 3.1.3.16). It plays an important role in terminating synaptic transmission, and in T-cell activation. It is only weakly inhibited by **okadaic acid**, but potently inhibited by certain pyrethrin compounds. It consists of two subunits, A and B, the A subunit having the catalytic activity, the B subunit conferring calcium sensitivity.

calciol *an alternative trivial name for* **cholecalciferol**.

calciosome a discrete cytoplasmic organelle in non-muscle cells, and a candidate for the inositol 1,4,5-trisphosphate-sensitive Ca^{2+} store. It has a high content of a **calsequestrin**-like protein.

calciotropic describing any hormone or other agonist acting on calcium metabolism.

calciphorin a calcium ionophore polypeptide, M_r 3000, isolated from the inner membrane of calf mitochondria.

calcitetrol *the recommended trivial name for* $1\alpha,24R,25$-trihydroxycholecalciferol. It is the inactivation product of calcitriol, from which it is formed by calcitriol 24-hydroxylase. *See also* **vitamin D**.



calcitonin *or* **thyrocalcitonin** a 3.4 kDa polypeptide hormone that regulates the levels of calcium and phosphate in blood. In all species studied it consists of a single polypeptide chain of 32 amino-acid residues with a C-terminal prolinamide residue and an N-terminal seven-membered ring formed by a disulfide bridge between hemicystine residues at positions 1 and 7. The single letter code structure for the polypeptide is

CGNLSTCMLGTYTQDFNKFHTFPQTAIGVGAP–NH_2.

Calcitonin is secreted by the **C cells**, which in mammals occur primarily in the thyroid gland; in more primitive vertebrates they are found mainly in the ultimobranchial bodies and the lung. The hormone is concentrated in the hypothalamus of humans and some other vertebrates, and in the primitive brain of the chordate organism *Ciona intestinalis*. Calcitonin causes a rapid but short-lived drop in the level of calcium and phosphate in blood by promoting their incorporation in the bones. Overall its action is antihypercalcemic, opposing that of **parathyrin**. The response of plasma calcitonin to stimulation by administered **pentagastrin** or calcium may be used to screen for medullary cell carcinoma of the thyroid; the level rises to abnormally high values after stimulation, though normal in its absence. The precursor (locus at 11p15.2-p15.1) also contains **katacalcin**. Both the calcitonin precursor and **calcitonin gene-related peptide** precursor are formed by alternative splicing of the same gene.

calcitonin gene-related peptide *abbr.*: CGRP; a pleiotropic 3.8 kDa polypeptide of 37 amino-acid residues, found in parts of the nervous system and endocrine system, and in some other organs. It is a potent vasodilator and hypotensive agent, and is regarded as a neuromodulatory peptide. The mRNA is formed by **alternative splicing** of the transcript of the **calcitonin** gene, which has exons coding for a region common to both CGRP and calcitonin precursors together with specific calcitonin and CGRP exons. The polypeptide has the structure (rat):

SCNTATCVTHRLAGLLSRSGGVV-
KDNFVPTNVGSEAF-NH_2,

a form known as α-CGRP. β-CGRP is identical except for Lys instead of Glu at position 35, and is encoded by a separate but related gene. α-CGRP is present in trigeminal and spinal sensory ganglion cells, in olfactory and gustatory systems, and at neuromuscular junctions. CGRP is also found in the endocrine system – in a subset of adrenal medullary cells and in thyroid C cells – in bronchiolar cells, and in intestinal cells. Administration of synthetic rat CGRP causes a drop in blood pressure (CGRP is the most potent known hypotensive gene peptide), and increase in heart rate. *In vitro* it can relax arteries from many vascular beds taken from a variety of species, and is one of the most potent vasodilators known. It also inhibits gastrointestinal motility and causes catecholamine release and gastric hypoacidity. In Raynaud's disease there is deficiency of perivascular neurons that contain CGRP. CGRP is homologous to **amylin**.

calcitonin gene-related peptide receptor any of several membrane proteins that bind calcitonin gene-related peptide (CGRP) and mediate its effects. $CGRP_1$ and $CGRP_2$ subtypes have been proposed; the antagonist $CGRP_{8\text{-}37}$ is selective for $CGRP_1$ receptors, and $[Cys(Acm)^{2,7}]CGRP$ for $CGRP_2$ receptor types. CGRP receptors are widely distributed in the nervous system, following the pattern of distribution of CGRP, except that receptor numbers are high in cerebellum. They are also widespread in the cardiovascular system, as well as in adrenal, pituitary, exocrine pancreas, kidney, and bone. CGRP receptor stimulation leads to cyclic AMP accumulation in a number of tissues (heart, liver, muscle, pancreatic acinar cells) indicating coupling to one or more G-proteins.

calcitonin receptor any of the membrane proteins that bind calcitonin and mediate its effects. They are seven-transmembrane-helix receptors, normally coupled to G-proteins. In many systems they can activate both adenylate cyclase and the phosphatidylinositol cycle.

calcitriol *the recommended trivial name for* 1α,25-dihydroxycholecalciferol. Produced from **cholecalciferol** by hydroxylation of C-25 in liver and C-1 in kidney, it increases calcium absorption by inducing synthesis of **calbindin** in duodenal mucosa, and promotes calcium deposition in bone by inducing **osteocalcin** in osteoblasts. *See* **vitamin D**.



calcium *symbol*: Ca; an alkaline-earth metal of group 2 of the IUPAC **periodic table**; relative atomic mass 40.08, atomic number 20; it occurs naturally only in an ionized (Ca^{2+}) or combined state, and is a mixture of stable nuclides of relative mass 40 (96.97 atom percent) and 44 (2.06 atom percent) with small proportions of nuclides of relative mass 43, 46, and 48. Calcium is the fifth most abundant element of the Earth's crust and is an essential component of all living material. It occurs in bone, shell, and teeth and low concentrations of ionic calcium play many important roles in the regulation of diverse cellular processes. The most abundant mineral in the human body, most of it is in the skeleton. It has especially important functions in bone, in the control of nervous, muscle, and other excitable tissue, and as a **second messenger** and regulator of enzyme activity. Calcium homeostasis depends on the action of: (1) **parathyroid hormone**, which increases tubular reabsorption of calcium, and releases calcium from bone, thereby having overall a hypercalcemic action; (2) **vitamin D** (calcitriol), which causes absorption of calcium from the gut and its release from bone, and also therefore has a hypercalcemic action; and (3) **calcitonin**, which reduces calcium resorption from bone. The range of plasma calcium in normal human adults is 2.2–2.6 mmol L^{-1}. *See also* **hypercalcemia**, **hypocalcemia**.

calcium-45 *symbol*: ^{45}Ca; an artificial radioactive nuclide of calcium, with a half-life of 165 days. It emits β^--particles (i.e. electrons) of 0.252 MeV max. and no γ-radiation.

calcium-47 *symbol*: ^{47}Ca; an artificial radioactive nuclide of calcium, with a half-life of 4.54 days. It emits β^--particles (i.e. electrons) of two energy ranges (1.98 and 0.67 MeV max.) and γ-radiation of three energies (1.31, 0.815, and 0.49 MeV).

calcium channel any of several proteins that permit the controlled (gated) passage of calcium ions through membranes. There are several types. **L-type channels** are involved in excitation–contraction coupling in muscle; they bind 1,4-dihydropyridine (DHP). The DHP receptor is a protein located in transverse (T-) tubules that specifically binds DHP compounds such as **nifedipine**. This modulates the slow L-type channel in skeletal muscle, neurons, and cardiac cells. **N-type channels**, identified only in neurons, participate in neurotransmitter release and are blocked by ω-conotoxin. **T-type channels** influence pacemaker activity in the heart and repetitive spike activity in neurons; they are blocked by octanol. **P-type channels**, identified in some CNS neurons and prominent in Purkinje cells, are blocked by ω-agatoxin, much less so by ω-conotoxin. The L-type channel from skeletal muscle consists of five subunits: α1, α2, β, γ, and δ. The largest subunit (α1) is responsible for many of the functional features, including DHP binding and the voltage-gated pore. It is structurally similar to the Na^+ channel α subunit, with four internal repeats of 200–300 amino acids exhibiting sequence homology. Each of these repeats contains six putative transmembrane segments, S1 to S6; segment S4 in all repeats has positively charged groups in -(K/R)XX- repeats (four to six K or R residues per segment), that have been implicated in sensing voltage changes; potential *N*-glycosylation sites and potential cAMP-dependent phosphorylation sites have been identified on the α_1 protein. Missense mutations in the gene at 19p13 for the α1A subunit are associated with familial hemiplegic migraine and with episodic ataxia-2, while expansion of the polyglutamine tract is associated with a form of spinocerebellar ataxia. *See also* **verapamil**.

calcium-dependent regulator protein *or* **calcium-dependent modulator protein** *abbr.*: CDR; *former name for* **calmodulin**.

calcium ion (Ca^{2+})-release channel *another name for* the **ryanodine receptor**.

calcium phosphate-mediated transfection a method for introducing exogenous DNA such as a plasmid into mammalian or other eukaryotic cells. Cells in culture are exposed to a calcium phosphate coprecipitate of DNA and a proportion of them take up the complex by endocytosis and express the transfected genes. Efficiency of transfection varies greatly with different cell lines.

calcium pump any system that transports calcium ions across a biological membrane from a lower to a higher concentration with the consumption of energy. The term is used especially of the pump in the sarcoplasmic reticulum of muscle of which a transmembrane **calcium-transporting ATPase** is an integral part.

calcium-regulated actin bundling protein a protein that is probably involved in the formation of filopodia.

calcium-sensing receptor a G-protein-coupled receptor that is expressed in parathyroid glands and renal tubules. It consists of 1078 amino acids, encoded by a gene at 3q13.3-q21. Loss-of-function mutations are associated with familial hypercalcemic hypocalciuria, and gain-of-function mutations with familial hypocalcemic hypercalciuria.

calcium-transporting ATPase EC 3.6.1.38; an integral membrane protein that forms an essential component of the **calcium pump** in sarcoplasmic reticulum. It catalyses the hydrolysis of ATP to ADP and orthophosphate, simultaneously transporting two calcium ions from the cytosol into the sarcoplasmic reticulum for each ATP hydrolysed. Probably comprising 10 transmembrane domains, it is related to other metal-ion-transporting ATPases. A number of types exist.

calcium-trigger protein any of a group of small calcium-binding **trigger** proteins, including **calmodulin**, troponin C (*see* **troponin**), and **parvalbumin**.

calculus (*pl.* **calculi**) a concretion of material that forms within the body. It often resembles a small pebble, hence is called a 'stone'. Calculi are most common in the gall bladder or kidney, and are composed variously of organic or inorganic salts, frequently of calcium; cholesterol calculi are gallstones of pure cholesterol.

calcyclin *other names*: prolactin receptor associated protein, growth factor-inducible protein 2A9, S100 calcium-binding protein A6; a small protein that copurifies with **prolactin receptor**. It is induced in fibroblasts by growth factors and is overexpressed in acute myeloid leukemia. It binds specifically **annexin** XI.

caldecrin a pancreatic protein that lowers serum calcium. It also has chymotrypsin-like activity, which is not needed for the calcium-lowering effect.

caldesmon an F-actin cross-linking protein in thin filaments in smooth muscle and in stress fibres in (non-muscle) fibroblasts. It also binds myosin and tropomyosin. It appears to be a homo- dimer comprising two polypeptide chains, each with a single actin-binding site and a single self-association site. It controls actin–myosin interactions, and inhibits the actin-activated ATPase of myosin. Its action is attenuated by calcium-calmodulin, and potentiated by tropomyosin. Caldesmon will interact with Ca^{2+}-calmodulin (but not with calmodulin alone), an interaction that causes caldesmon to dissociate from F-actin. *See also* **caldesmon kinase**, **caldesmon phosphatase.**

caldesmon kinase EC 2.7.1.120; the name given to a reaction now known to result from the autophosphorylation of **caldesmon** (by ATP) in the presence of calcium. This autophosphorylation abolishes the ability of caldesmon to bind actin.

caldesmon phosphatase EC 3.1.3.55; an enzyme that hydrolyses the phosphate from caldesmon phosphate.

caldolysin an extracellular protease isolated from *Thermus aquaticus* strain T-351, an extreme thermophile. It contains 13% carbohydrate by weight, and one atom of zinc; M_r 21 000.

calelectrin *see* **annexin IV**, **annexin V**, **annexin VI**.

calgizzarin an **EF-hand** Ca^{2+}-binding protein isolated from chicken gizzard smooth muscle. It is also abundant in rabbit lung and is found in other tissues. It is homologous to **annexin** II light chain, and is a homodimer (disulfide-linked). It is over-expressed in human colorectal tumours.

callipyge a mutation in sheep that produces enlarged hindquarters by enhanced expression of several genes of muscle

callose a linear (1,3)-β-D-glucan insoluble in water but soluble in dilute alkali. The glucan chains form stable double or triple helices. Callose is a ubiquitous higher plant polysaccharide occurring as a component of specialized, and often transient, cell walls, especially in reproductive tissues and is a component of the cell plate. Callose is synthesized at the outer plasma membrane surface of a few cell types. It is rapidly deposited as drops, plugs, or plates on wounding or physiological stress, or attempted penetration by fungal hyphae. Callose synthase is activated by Ca^{2+}, which increases in concentration on wounding. Callose deposits on cell walls stain specifically with Aniline Blue or its fluorochrome. Specific hydrolases, e.g. glucan endo-1,3-β-D-glucosidase (EC 3.2.1.39) for callose and membrane-bound callose synthetase (EC 2.4.1.34), are found in plants. Functionally callose may act as a temporary wall matrix, as a special permeability barrier or as a wall strengthening agent. Other (1,3)-β-D-glucans include yeast glucan, pachyman, lamarin, scleroglucan, curdlan, leucosin, mycolamarin, paramylon, chrysolamarin, and lentinan.

callus **1** a mass of relatively unspecialized tissue that develops at wound sites in plants, forming a protective covering. Callus cells are used in tissue culture as the starting material for the propagation of plant clones. **2** tissue formed during the healing of broken bone.

calmegin a spermatogenesis-specific chaperone protein that is homologous to **calnexin**, **calreticulin**, and CALNUC. Mouse knockouts produce sperm that cannot bind to the zona pellucida of ova.

calmitine a mitochondrial Ca^{2+}-binding protein of fast-twitch muscle fibres with a characteristic 28-residue signal. The mature protein is identical to **calsequestrin** of the sarcoplasmic reticulum.

calmodulin *abbr.*: CAM; a small, heat-stable, acidic, calcium-dependent modulator protein that binds four calcium ions per molecule and is then able to stimulate a variety of eukaryotic enzymes or enzyme systems. These include brain adenylate cyclase, cytosolic cyclic nucleotide phosphodiesterase, myosin light-chain kinase, erythrocyte Ca^{2+},Mg^{2+}-ATPase, plant NAD^{+} kinase, and a number of calcium-dependent protein kinases including phosphorylase kinase (to which it contributes the δ subunits); these enzymes bind to calmodulin via basic amphiphilic alpha-helices they contain. Various other cellular processes such as membrane phosphorylation and microtubule disassembly also are stimulated. Calmodulin is a single-chain polypeptide, of which aspartic and glutamic account for about 30% of the total residues; it contains one residue of N^6-trimethyllysine per mole but no cysteine, hydroxyproline, or tryptophan residues. Calmodulin appears to be ubiquitous within the animal and plant kingdoms, to be without species or tissue specificity, and to be almost invariant in structure, being conserved nearly perfectly throughout evolution; it has **EF-hand** domains and is similar to troponin C from muscle. It has been known by a variety of names including modulator protein, phosphodiesterase activator protein, troponin C-like (modulator) protein, and calcium- (or Ca^{2+})-dependent regulator (or modulator) protein (CDR protein).

calmodulin-dependent protein kinase II *recommended name*: Ca^{2+}/calmodulin-dependent protein kinase, EC 2.7.1.123; *other names*: Ca^{2+}-CAM kinase II; microtubule-associated protein 2 kinase; multifunctional Ca^{2+}-CAM kinase. An enzyme with broad specificity and activated by Ca^{2+} that catalyses the phosphorylation of Ser and Thr residues in proteins by ATP. It is involved in cell regulation. It is composed of α (M_r 60 000) and β (M_r 55 000) subunits in a dodecahedral structure. On activation by Ca^{2+}-CAM, autophosphorylation converts the enzyme to a Ca^{2+}-CAM-independent form. Substrates include synapsin I, tryptophan hydroxylase, skeletal muscle glycogen synthetase, and microtubule-associated proteins tau and MAP-2. A synthetic peptide substrate is PLSRTLSVSS.

calmodulin-like domain protein kinase *abbr.*: CDPK; EC 2.7.1.–; *other name*: Ca^{2+}-binding Ser/Thr protein kinase. An enzyme that is subject to autophosphorylation and resembles calmodulin-dependent protein kinases in its N-terminal region and contains four EF hands in the C-terminal region. It may be ubiquitous in plant cells, being attached to the cytoskeleton, by N-terminal myristoylation to the inner surface of the plasma membrane, or in the cytoplasm.

calnexin a calcium-binding protein of the endoplasmic reticulum. It appears to play a role in the processing of endoplasmic reticulum proteins, in monitoring assembly, and in retaining unassembled or incorrectly folded proteins. It has a single transmembrane helical region.

CALNUC a calcium-binding protein of Golgi apparatus, homologous with **calreticulin**.

calomel electrode the mercury–mercurous chloride (mercury–calomel) (Hg;Hg$_2$Cl$_2$, Cl$^-$) half-cell that is reversible to chloride ions. Because of its stability and simplicity, it is frequently used in conjunction with a saturated-KCl bridge as a reference electrode in pH meters, etc.

calorie *or (sometimes)* **gram calorie** *or* **small calorie** *symbol*: cal; any of several units of heat or energy in the CGS system. A calorie originally represented the quantity of heat required to raise one gram of water through one degree centigrade (i.e. Celsius). However, the energy represented by a calorie varies slightly according to the initial temperature of the water. Hence, the **International Table calorie** (*symbol*: cal$_{\mathrm{IT}}$) is now taken to equal 4.1868 J exactly, while the **15°C calorie** (*symbol*: cal$_{15}$) is equal approximately to 4.1855 J. Thermochemical calculations have often used a slightly different value; one **thermochemical calorie** (*symbol*: cal$_{\mathrm{th}}$) is now taken to equal 4.184 J exactly. In nutrition and physiology, the term 'calorie' is often used to mean the kilocalorie or Calorie (initial capital), equal to 10^3 cal$_{\mathrm{IT}}$. Use of all these units is now deprecated, the joule now being preferred.

Calorie *or (sometimes)* **kilogram calorie** *or* **large calorie** the name used, especially in nutrition, for the kilocalorie, i.e. 10^3 cal$_{\mathrm{IT}}$. *Compare* **calorie**.

calorific of, relating to, or generating heat.

calorific value the amount of heat produced by the complete combustion of a given mass of a substance, such as a fuel or foodstuff. It is usually expressed in J kg^{-1}.

calorigen any agent that increases heat production by increasing metabolism. *See* **salicylic acid.**.

calorigenesis the production or increased production of heat in an organism. —**calorigenic** *adj.*

calorimeter an instrument for determining quantities of heat evolved, transferred, or absorbed.

calorimetry the measurement of the amount of heat evolved, transferred, or absorbed by a system. —**calorimetric** *adj.*

calpactin *see* **annexin**.

calpain *abbr.*: CAPN; EC 3.4.22.17; a Ca^{2+}-activated, neutral, thiol proteinase enzyme that preferentially cleaves the bonds: Tyr-|-Xaa, Met-|-Xaa, or Arg-|-Xaa with Leu or Val as the P2 residue. Calpains are cytosolic mammalian enzymes, of five main types: CAPN1 and 2 are ubiquitous; CAPN3 is muscle-specific; and CAPN4 and 5 are stomach-specific. These have an identical small regulatory **EF-hand** subunit and a large catalytic subunit, which contains an N-terminal domain that is cleaved by autocatalytic activation, a catalytic domain, and a C-terminal region that contains five EF hands. Mutations in CAPN3 (gene locus at 15q15.1-q21 encodes 996 amino acids) are associated with a form of limb girdle muscular dystrophy (LGMD2A).

calpastatin a protein, found in liver and erythrocytes of several mammals, that is a specific calpain inhibitor. Four characteristic domains are involved in the inhibitory action.

C-alpha *an alternative term for* **alpha carbon atom**.

calphostin C one of a group of compounds isolated from *Cladosporium cladosporioides* having a unique structural feature in possessing a perylene quinone. It was identified in a search for inhibition of protein kinases. It inhibits protein kinase C by action on the regulatory domain and has a relatively high degree of specificity, but acts equally on all isoforms having the common regulatory domain. It is a highly potent and specific inhibitor (IC$_{50}$ = 50 nM) of protein kinase C. At higher concentrations it inhibits other kinases, including myosin light chain kinase, and cyclic GMP- and cyclic AMP-dependent kinases.



calphotin a Ca^{2+}-binding protein found in the cytoplasm of photoreceptor cells of *Drosophila melanogaster*. The C-terminal region contains a leucine zipper uninterrupted by prolines. The protein contains >50% proline, alanine, and valine.

calponin a thin filament-associated protein implicated in regulation and modulation of smooth muscle contraction. It is found as an actin-, calmodulin-, and tropomyosin-binding protein present in many vertebrate smooth muscles, and is related to troponin T in immunological and biochemical characteristics.

calpromotin *an alternative name for* **torin**.

calregulin *see* **calreticulin**.

calreticulin *other names*: calregulin; Crp55; CaBP3; HACBP; erp60; a Ca^{2+}-binding protein of the endoplasmic reticulum lumen; its C terminus contains the **KDEL** sequence.

calsequestrin a 44 kDa calcium-binding protein of low isoelectric point, found on the interior surface of the membrane of the **sarcoplasmic reticulum** of muscle. It acts as an internal calcium store in muscle and releases Ca^{2+} at **calcium channels**. It has only a moderate affinity for calcium ions, but a high capacity (>40 Ca^{2+} ions per molecule); selective binding of Ca^{2+} in preference to other cations is promoted by ATP; it also exhibits protein kinase activity. Calsequestrin makes up some 19% of the protein of isolated sarcoplasmic vesicles, and is thought to assist in depleting the sarcoplasm of free calcium ions during relaxation. The human muscle isoform (390 amino acids, 44.53 kDa) is very acidic (47 Asp, 56 Glu), with a sequence of eight aspartic-acid residues at the C terminus.

calspectin *an alternative name for* **fodrin**.

calstorin a calcium-binding protein of the microsomal lumen of rat brain, similar to **calsequestrin**.

caltractin *or* **centrin** an **EF-hand** Ca^{2+}-binding protein of the centrosome of interphase and mitotic cells that plays a fundamental role in microtubule-organizing centre structure. It is present in the centrosome/basal body apparatus of the green alga *Chlamydomonas reinhardtii*. It contains four EF-hands, and belongs to the calmodulin/parvalbumin/troponin C superfamily.

caltrin *abbr. for* calcium transport inhibitor; *other name*: seminalplasmin; a small basic protein of male seminal vesicle fluids. It binds to calmodulin, and inhibits Ca^{2+} uptake by epididymal spermatozoa. It has antimicrobial properties.

Calvin cycle *see* **reductive pentose phosphate cycle**.

Calx a gene of *Drosophila* that encodes a Na$^+$/Cl$^-$ exchanger channel protein.

Cam *symbol for* the **carbamoylmethyl** group.

CAM *abbr. for* **1** calmodulin. **2** crassulacean acid metabolism.

camalexin a sulfur-containing phytoalexin produced by plants of the *Brassica* genus and their relatives in response to attack by bacterial pathogens.

CaM-BP$_{80}$ *an alternative name for* **calcineurin**.

CAMDA *abbr. for* critical assessment of microarray data analysis; *see* **critical assessment competition**.

cAMP *abbr. for* cyclic AMP; *see* **adenosine 3′,5′-phosphate**.

campesterol (24*R*)-ergost-5-en-3*β*-ol; a sterol found in small amounts in rapeseed and other vegetable oils.



camphor 1,7,7-trimethylbicyclo[2.2.1]heptan-2-one; a compound obtained from the camphor tree, *Cinnamomum camphora*, which is indigenous to Taiwan. It is widely used in ointments and liniments. It is also used as a starting material in organic chemistry.

campomelic dysplasia *or* **autosomal sex reversal** a rare autosomal dominant chondrodysplasia caused by mutations in *SOX9* and fatal in early infancy. In most affected genotypic male patients it is associated with feminization.

cAMP receptor *see* **CAR**.

cAMP receptor protein *see* **catabolite (gene) activator protein**.

cAMP-regulatory protein *see* **catabolite (gene) activator protein**.

CaMV promoter *abbr. for* cauliflower mosaic virus promoter; a promoter used to obtain expression of exogenous genes in green plants.

canaline O^4-aminohomoserine; 2-amino-4-(aminooxy)-butanoic acid; $H_2N–O–[CH_2]_2–CH(NH_2)–COOH$; a basic α-amino acid found as the L-enantiomer in the jack bean, *Canavalia ensiformis*, and in some other legumes containing L-canavanine. It is formed from **canavanine** by deamidination or transamidination. It inhibits pyridoxal-dependent enzymes.



canavalin the major globular protein isolated from ripe seeds of the jack bean, *Canavalia ensiformis*. It is a seed storage protein, with sequence similarity to **phaseolin**, **vicilin**, and related proteins. *See also* **concanavalin A**.

canavanase *see* **arginase**.

Canavan disease an autosomal recessive degenerative disease due to a defect in the gene for aspartoacyclase. Onset is in early infancy, consisting of blindness, psychomotor regression, enlarged head, optic atrophy, hypotonia, spasticity, and increased urinary excretion of *N*-acetylaspartate.

canavanine 2-amino-4-(guanidinooxy)butanoic acid; $H_2N–C(NH)–NH–O–[CH_2]_2–CH(NH_2)–COOH$; a basic amino acid, occurring as the L-enantiomer in certain legumes, esp. the jack bean, *Canavalia ensiformis*. In seeds of the jack bean, it constitutes up to 8% of their dry mass, and forms their main storage compound for nitrogen. On germination of the seeds, the nitrogen is released for synthetic purposes by hydrolysis of L-canavanine to L-canaline and urea, from each of which ammonium is then formed by further hydrolysis. It is a structural analogue of L-arginine, and a potent growth inhibitor of many organisms, in which it interferes with arginine metabolism. *See also* **canaline**.



cancellate *or* **cancellated** *or* **cancellous** having a porous or spongy structure; meshlike or lattice-like.

cancer any malignant **neoplasm**. Cancers are usually divided into **carcinomas**, derived from epithelial tissue, and **sarcomas**, derived from connective tissue. Some 300 genes are known to be involved in carcinogenesis. *See* **APC**, **BRCA**, **retinoblastoma**, **Wilms' tumour**.

cancer-associated retinopathy protein *see* **recoverin**.

candela *symbol*: cd; the SI base unit of **luminous intensity**, defined as the luminous intensity, in a given direction, of a source that emits monochromatic radiation of frequency 540 × 10^{12} hertz and that has a radiant intensity in that direction of 1/683 watt per steradian.

Candida a genus of (in many cases) dimorphic yeasts containing species of medical (*C. albicans*) and industrial importance: *C. cylindrica* is a source of **lipases** and is a rare example of a eukaryote with a non-standard genetic code for nuclear/cytoplasmic gene expression.

cane sugar *an old and common name for* **sucrose**.

cannabinoid any of about 30 derivatives of 2-(2-isopropyl-5-methylphenyl)-5-pentylresorcinol found in the Indian hemp, *Cannabis sativa*, among which are those responsible for the narcotic actions of the plant and its extracts. The most important cannabinoids are cannabidiol, cannabinol, *trans*-Δ^9-tetrahydrocannabinol, *trans*-Δ^8-tetrahydrocannabinol, and Δ^9-tetrahydrocannabinolic acid. *See also* **cannabis**.

cannabinoid receptor any of several membrane proteins that bind cannabinol and structurally similar compounds and mediate their intracellular action. Two types have been characterized, and both are G-protein-coupled receptors. CB1 receptors are found in brain and testis. CB2 receptors are found in spleen and immune tissues, but not in brain. For both types arachidonoylethanolamide (anandamide) is a putative endogenous ligand and both types are negatively coupled to adenylate cyclase decreasing intracellular cyclic AMP levels. CB3 receptors also occur in brain.

cannabinol *see* **cannabinoid**.

cannabis the dried flowering or fruiting tops of Indian hemp, *Cannabis sativa*; numerous synonyms exist, including **marijuana**, **bhang**, and **maconha**. A resin, known variously as cannabin, hashish, or charas, is also obtained from the plant. Both preparations contain active principles, **cannabinoids**, and are used as recreational drugs, producing relaxation, euphoria, and enhanced awareness. Occasionally, anxiety or mental disturbance may result, and, rarely, loss of consciousness or even death. The major active ingredients are tetrahydrocannabinols. Cannabis is a controlled substance in the US Code of Federal Regulations.

Cannizzaro reaction the base-catalysed dismutation of aldehydes with no α hydrogen atoms into the corresponding acids and alcohols:

$$2R–CHO + OH^– \rightarrow R–COO^– + R–CH_2OH.$$

[After Stanislo Canizzaro (1826–1910).]

canonical form *or* **canonical structure** *an older name for* **contributing structure**.

canonical sequence a nucleotide or amino-acid sequence regarded as the archetype with which variants are compared.

cap 1 *or* **cap structure** a structural feature present at the 5′ end of most eukaryotic (cellular or viral) mRNA molecules and also of some virion mRNA molecules but not of bacterial mRNA molecules. It consists of a residue of 7-methylguanosine and a triphosphate bridge linking it 5′–5′ to the end of the polynucleotide chain; in addition, the first one or two nucleotide residues in the chain may possess a 2′-*O*-methyl group and the first, if adenylyl, a 6-*N*-methyl group. The cap structure is thought to protect the 5′ end of the mRNA from degradation by phosphatases or nucleases and to facilitate initiation of translation of mRNA by the eukaryotic (but not by the bacterial) ribosome. **2** a cluster or patch of aggregated proteins at one site on the surface of a cell, e.g. a lymphocyte. Surface components of the cell membrane are aggregated, e.g., by the action of polyvalent ligands, and may be swept to the posterior area of the cell when the cell moves, forming a cap at that site. **3** to form or place a cap on a molecule (or structure).

CAP *abbr. for* **1** catabolite (gene) activator protein. **2** chloramphenicol (use deprecated, full name preferred). **3** *Clostridium* (*histolyticum*) aminopeptidase, EC 3.4.11.13. **4** cyclic AMP receptor protein; *see* **CRP**.

capacitance *or* **electric capacitance** *symbol*: *C*; the ability of a system to store electric charge or a measure of this capacity for a particular system. $C = Q/U$ where Q is the quantity of charge stored to raise the system's potential by U volts. The SI derived unit of capacitance is the **farad**.

capacitance minimization method a simple method for the determination of asymmetric surface potentials in lipid bilayers, based on the dependence of bilayer capacitance on transmembrane voltage. The capacitance is measured by rectifying the 90° component of an applied a.c. current signal. A superimposed slow triangular wave results in a hysteresis-like time course of capacitance. The centre of the hysteresis figure is shifted along the voltage axis by an amount equal to the **capacitance minimization potential**, the difference between the dipole plus surface-charge potentials on the two sides of the membrane.

CAPB *see* **calbindin**.

cap-binding protein any protein (e.g. a 24 kDa protein obtainable from rabbit reticulocytes) that specifically binds to the **cap** (def. 1) of eukaryotic capped mRNA. Such proteins may facilitate the translation of capped mRNA molecules. In the nucleus a heterodimer is involved; in the cytosol a complex comprising the **initiation factors** eIF4A, eIF4E, eIF4GI, and eIF4GII is involved.

Capecitabine *or* **Xeloda** 5′-deoxy-5-fluoro-*N*-[(pentyloxy)carbonyl]-cytidine. The first tumour-activated drug. It acts by inducing the tumour to produce more thymidine phosphorylase, which causes the tumour to make more cytotoxic 5-fluorouracil, to which the drug is converted.

CAP factor *see* **catabolite (gene) activator protein**.

capillarity the phenomenon, resulting from surface tension, in which liquids rise up capillary tubes and which also causes them to form a concave or convex meniscus at their surface where it contacts a solid.

capillary **1** of, or relating to, a hair or hairlike structure. **2** of, or relating to, a tube with a very fine bore. **3** any of the very fine blood vessels that form a network between the arterioles and the venules throughout the body. **4** a capillary tube.

capillary column a chromatography column that has a very fine bore (0.1–0.25 mm), the inner surface of which may be coated with **stationary phase** or other support. Such columns are used in gas chromatography, supercritical fluid chromatography, or capillary electrophoresis. The column may be up to a few metres in length, coiled, and made of glass or fused silica. In high-performance liquid chromatography, columns of somewhat wider bore and shorter length are referred to as capillary columns.

capillary electrophoresis *abbr.*: CE; a very-high-resolution method of electrophoresis, also known as **capillary zone electrophoresis** (*abbr.*: CZE) *or* **high-performance electrophoresis**. It is based on the use of long (up to 100 cm), narrow (<100 μm) silica columns for separation of peptides, etc. by electro-osmotic flow. By using sensitive detectors (e.g. laser-induced fluoresence), sensitivity in the attomole range can be achieved.

capillary filtration a technique for **membrane filtration** in which the membrane is supported inside porous capillary tubes (capillary membranes). Bundles of such tubes make up a larger filtration unit. *Compare* **hollow-fibre technique**.

capillary viscometer an instrument for measuring the viscosity of a liquid by determining the rate of flow of the liquid through a capillary tube of known dimensions. An **Ostwald viscometer** is a simple capillary viscometer; an **Ubbelholde viscometer** is a viscometer with several different capillary tubes, so that measurements may be made at different shear values.

capped mRNA an mRNA molecule that has a **cap** (def. 1).

capping the act or process of forming or placing a **cap** on a molecule or structure.

capping enzyme any guanylyltransferase enzyme concerned in the formation of a **cap** (def. 1) on an RNA molecule.

caprate *or* **caprinate** *a trivial name for* **decanoate**, or for any salt or ester of decanoic acid.

capric acid *or* **caprinic acid** *a trivial name for* decanoic acid; *see* **decanoate**.

caprin *a trivial name for* any of the glyceryl esters of decanoic acid (*see* **decanoate**); these often occur in milk fat, especially the triester tricaprin, $(CH_3\text{–}[CH_2]_8\text{–}COO)_3C_3H_5$.

caprinate *see* **caprate**.

caprinyl (*formerly*) *an alternative name for* **caproyl** (def. 1).

caproate *a trivial name for* **hexanoate**, or any salt or ester of hexanoic acid.

caproic acid *a trivial name for* hexanoic acid (*see* **hexanoate**).

caproin *a trivial name for* any of the glyceryl esters of hexanoic acid (*see* **hexanoate**); these often occur in milk fat, especially the triester tricaproin, $(CH_3\text{–}[CH_2]_4\text{–}COO)_3C_3H_5$.

caproyl **1** *or (formerly)* **caprinyl**; *symbol*: Dco; *trivial name for* decanoyl, $CH_3\text{–}[CH_2]_8\text{–}CO\text{–}$, the univalent acyl radical derived from decanoic acid (*formerly* capric acid *or* caprinic acid). Use of the term caproyl is disfavoured because of confusion with **caproyl** (def. 2) and **capryloyl**. **2** *an old trivial name for* hexanoyl, the univalent group derived from hexanoic acid (*formerly* caproic acid), a saturated unbranched, acyclic, aliphatic acid (i.e. fatty acid). It occurs naturally in acylglycerols in, e.g., coconut and palm nut oils, and milk fat. Use abandoned (*see* **caproyl** (def. 1)).

capryl **1** *an old trivial name for* **octyl**. **2** *an old trivial name for sec*-octyl. **3** *symbol*: Dec; *a trivial name sometimes used for* **decyl**.

caprylate *former name for* **octanoate** or for any salt or ester of octanoic acid.

caprylic acid *a former name for* octanoic acid; *see* **capryloyl**.

caprylic alcohol **1** *or* ***n*-caprylic alcohol** *a former name for* (*n*-)octyl alcohol (octan-1-ol). **2** *or* ***sec*-caprylic acid** *a former name for sec*-octyl alcohol (octan-2-ol). *See also* **caprylic acid**.

caprylin *a former name for* any of the glyceryl esters of **octanoic acid**; these occur in milk fat, especially the triester tricaprylin, $(CH_3\text{–}[CH_2]_6\text{–}COO)_3C_3H_5$.

capryloyl *or* **caprylyl** *an old trivial name for* **octanoyl**.

Caps *or* **CAPS** *abbr. for* 3-(cyclohexylamino)propanesulfonic acid; a compound with properties similar to a **Good buffer substance**, pK_a (20°C) = 10.4.

capsaicin (*E*)-*N*-(4-hydroxy-3-methyoxybenzyl)-8-methyl-non-6-enamide; the active principle in chilli pepper (*Capsicum*), paprika, and cayenne that causes a burning sensation by stimulation of nociceptive (pain sensory) neurons followed by desensitization of nociceptive responses and neuronal depletion of **substance P**. It binds to and activates the vanilloid receptor, an integral membrane protein with homology to a family of putative calcium channel proteins. The receptor is also activated by heat.



capsaicin

capsanthin (3*R*,3′*S*,5′*R*)-3,3′-dihydroxy-*β*,*κ*-caroten-6′-one; the main carotenoid pigment of red pepper (*Capsicum annuum*).

capsid the protein coat that surrounds the infective nucleic acid in some virus particles. It comprises numerous regularly arranged subunits, or **capsomeres**.

capsomere *or* **capsomer** any of the (protein) subunits that comprise the closed shell or coat (capsid) of certain viruses.

cap structure *see* **cap** (def. 1).

capsular antigen *or* **capsular polysaccharide** *or* **capsular substance** any of the antigens, usually polysaccharide in nature, that are carried on the surface of bacterial capsules. The term **K antigen** is used for those that mask somatic (O) antigens.

capsule **1** an outer layer, rich in polysaccharides, that is present in certain types of bacteria. Presence of a capsule is often linked with **virulence** and the capsular material is often immunogenic. **2** a membrane or sheath of connective tissue that encloses an organ or tissue.

capsulin *or* **epicardin** a member of the MyoD family of basic HLH transcription factors that control formation of skeletal muscles in vertebrates. Like the related **MyoR (musculin)**, capsulin is expressed transiently in specific facial muscle precursors derived from the first branchial arch. A null mutation in the mouse capsulin gene causes death very soon after birth from pulmonary hypoplasia but no obvious skeletal muscle abnormality. Mice homozygous for mutations in both MyoR and capsulin also die immediately after birth but lack the major muscles of mastication.

captopril D-3-mercaptomethylpropanoyl-L-proline, (*S*)-1-(3-mercapto-2-methyl-1-oxopropyl)-L-proline; an antihypertensive drug that acts as an inhibitor of **angiotensin converting enzyme**. It was designed to fit the known active site of carboxypeptidase A; the mercapto group binds to the enzyme zinc ion, the amide carbonyl to a hydrogen-bonding site, and the proline carboxylate to an electrophilic centre. A related compound, **enalapril**, is more potent when administered orally and has fewer side effects.



captopril

capture cross-section the probability of a particle that impinges on an atomic nucleus being captured by that nucleus multiplied by the cross-sectional area of the nucleus (measured in **barns**).

CapZ a heterodimer protein (subunits of 33 and 31 kDa) that interacts with α-actinin 2 and the barbed end of F-actin polymers at the Z disks of skeletal muscle.

CAR *abbr. for* **1.** coxsackie and adenovirus receptor; a single-pass transmembrane protein whose extracellular region contains two immunoglobulin-like domains and binds coxsackie virus and adenovirus 2 and 5. The gene locus on chromosome 21 encodes 351 amino acids, but the physiological ligand is unknown. **2.** cAMP receptor; a receptor of the slime mould *Dictyostelium* that senses extracellular cAMP gradients. **3.** constitutive androstane receptor; a receptor that activates the phenobarbital-inducible *CYP2B* gene.

carba+ *comb. form (in chemical nomenclature)* indicating the replacement of a heteroatom by a carbon atom.

carbamide *former name for* **urea**.

carbamido *an alternative term for* **ureido**.

carbamino the chemical group –NH–COO⁻, which is stable only in the salt form. Carbamino compounds are formed by spontaneous reversible reaction of CO_2 with unprotonated primary aliphatic amino groups; e.g. with α-amino acids to form carbamino acids, or with the N termini of proteins, as in the formation of carbamino hemoglobin from hemoglobin. *Compare* **carbamoyl**.

carbamoyl *or (formerly)* **carbamyl** *or* **carboxamido** *symbol*: Cbm; the acyl group, $-CO-NH_2$, corresponding to carbamic acid (an acid unknown in the free state). *See also* **carboxamide**.

carbamoylmethyl *symbol*: Cam; the chemical group 2-amino-2-oxoethyl, $-CH_2-CO-NH_2$.

carbamoyl-phosphate synthase 1 *or* **carbamoyl-phosphate synthase (glutamine-hydrolysing)** EC 6.3.5.5; *other names*: carbamoyl-phosphate synthetase (glutamine-hydrolysing); GD-CPSase. A glutamine-dependent enzyme that is the first step in the pathway for pyrimidine biosynthesis. It catalyses a reaction between 2 ATP, glutamine, CO_2, and H_2O to form 2 ADP, orthophosphate, glutamate, and carbamoyl phosphate; this enzyme is part of the **CAD protein** in many eukaryotes. **2** *or* **carbamoyl-phosphate synthase (ammonia)** EC 6.3.4.16; *other names*: carbamoyl-phosphate synthetase (ammonia); carbamoyl-phosphate synthetase I, carbon-dioxide–ammonia ligase. An enzyme that incorporates free ammonium ion into carbamoyl phosphate, which then enters the **ornithine–urea cycle**. It catalyses a reaction between 2 ATP, NH_3, CO_2, and H_2O to form 2 ADP, orthophosphate, and carbamoyl phosphate. It constitutes ≈20% of mitochondrial protein and ≈4% of total cell protein in liver. Rare mutations in the gene at 2q35 that lead to enzyme deficiency are associated with hyperammonemia, protein intolerance, and impaired mental and physical development from birth.

carbamyl *former name for* **carbamoyl**.

carbanion any anion containing an even number of electrons in which a significant part of the excess negative charge is located on one or more carbon atoms.

carbapenem antibiotic any of various broad-spectrum β-lactam antibiotics, such as thienamycin derived from *Streptomyces cattleya*, that inhibit peptidoglycan synthesis. Semisynthetic derivatives include imipenem.

carbene 1 any chemical species of the type R_2C**:** containing an electrically neutral, bivalent carbon atom with two nonbonding electrons. The spins of such electrons may be either antiparallel (in the singlet state) or parallel (in the triplet state). Carbenes are highly reactive short-lived groups formed as intermediates in the course of certain organic reactions. **2** *or (formerly)* **methylene** the chemical group H_2C:, the simplest of the carbenes.

carbenium ion any real or hypothetical **carbocation** with one important contributing structure containing a tervalent carbon with a vacant *p*-orbital. These structures have often been described as **carbonium ions**.

carbenoxolone glycyrrhetic acid hydrogen succinate, a 3-(3-carboxy-1-oxopropoxy)-11-oxoolean-12-en-29-oic acid, steroid agent with anti-ulcerative effects, the mechanism of which is unresolved.

carbobenzyloxy *or* **carbobenoxy** *former name for* **benzyloxycarbonyl**.

carbocation a cation with an even number of electrons with a significant portion of the excess positive charge located on one or more carbons. This general term includes **carbenium ions**, **carbonium ions**, etc.

carbocycle any compound or molecular structure that is **carbocyclic** (def. 1); a **carbocyclic** (def. 2).

carbocyclic 1 describing any cyclic molecular structure containing only carbon atoms in the ring or rings; describing any compound having such a stucture. *See also* **homocyclic** (def. 1). *Compare* **heterocyclic** (def. 1). **2** *or* **carbocycle** any such compound.

carbodiimide any organic compound of general structure R–N=C=N–R, widely used for forming amide (peptide) or phosphodiester linkages in the laboratory. Water-soluble carbodiimides, e.g. 1-ethyl-3-(3-dimethylaminopropyl)carbodiimide, are used to couple carboxylic acid residues to ω-aminoalkyl agarose, while for reactions in nonaqueous media *N*,*N*′-dicyclohexylcarbodiimide is much used.

carbohydrase *former name for* **glycosidase**.

carbohydrate any of a group of organic compounds based on the general formula $C_x(H_2O)_y$. The group comprises the **monosaccharides**, **oligosaccharides**, and **polysaccharides**, and is usually extended to include their derivatives and, sometimes, the **cyclitols**. Some of the simplest members of the group may, notionally, be considered as hydrates of carbon. However, 2-deoxy-D-ribose ($C_5H_{10}O_4$) does not fit the empirical formulation. Carbohydrates are also components of nucleosides, nucleotides, RNA and DNA, glycoproteins, glycolipids, and glycosaminoglycans. Examples include **amylose**, **amylopectin**, **chitin**, and **glycogen**.

carbohydrate-deficient glycoprotein syndrome (*abbr.*: CDGS) *or* **glycoconjugate syndrome** *or* **congenital defect of glycosylation** any of several defects in N-glycan synthesis of glycoproteins. Such defects are usually identified by isoelectric focusing of serum transferrin, which shows a cathodal shift as a result of sialic acid deficiency. Type I defects are those where the defect is in the cytosol or in the endoplasmic reticulum. These include: **type Ia**, or **phosphomannomutase** deficiency; **type Ib**, or **mannose-6-phosphate isomerase** deficiency; **type Ic**, or α-1,3-glucosyl transferase deficiency; **type Id**, or α-1,3-mannosyl transferase deficiency; and **type Ie**, or dolichylphosphate-mannose synthase 1 deficiency. Type II disorders have a defect in the Golgi apparatus.These include: **type IIa**, or ***N*-acetylglucosaminyl transferase** deficiency; and **type IIb**, or **glucosidase** deficiency. In leukocyte adhesion deficiency II there is defective import of GDP-fucose into the Golgi apparatus.

carbon *symbol*: C; a nonmetallic element of group 14 of the IUPAC **periodic table**; atomic number 6; relative atomic mass 12.011. It exists in two main allotropic forms, diamond and graphite, and as a third allotrope, fullerene; there are also several amorphous forms, such as carbon black and charcoal. Carbon also forms a vast array of compounds, the organic compounds, based on chains and rings of covalently bonded carbon atoms. There are two stable nuclides, the predominant one being carbon-12. This has a relative abundance in natural carbon of 98.89 atom percent. Its mass is used as the reference standard for all relative atomic masses of nuclides. The other stable nuclide is **carbon-13**. There are also four radioactive nuclides: carbon-10, **carbon-11**, **carbon-14**, and carbon-15.

carbon-11 a radioactive nuclide of carbon, ${}^{11}_{6}C$. It emits a positron (β^+-particle) (0.97 Mev), no γ-ray, and has a half-life of 20.3 min.

carbon-13 *or* **heavy carbon** the stable nuclide ${}^{13}_{6}C$. Relative abundance in natural carbon 1.108 atom percent. It is used as a tracer in studies of reaction mechanisms and of carbon metabolism; now often replaced by **carbon-14** unless double labelling is required. Carbon-13 was/is used when a non-radioactive isotope is essential. *See also* **carbon-13 nuclear magnetic resonance spectroscopy**.

carbon-14 a radioactive nuclide of carbon, ${}^{14}_{6}C$. It emits an electron (β^--particle) (0.156 Mev), no γ-radiation, and has a half-life of 5730 years, decaying to ${}^{14}_{7}N$. A minute proportion occurs in atmospheric CO_2 due to the action of cosmic rays, and it forms the basis of **carbon dating**. It is used very widely as a radioactive tracer, for which it is produced artificially.

carbonate dehydratase EC 4.2.1.1; *systematic name*: carbonate hydro-lyase; *other names*: carbonic dehydratase; carbonic anhydrase (*abbr*.: CA); an enzyme that catalyses the reversible hydration of carbon dioxide to carbonic acid (or to bicarbonate ion at certain pH values) in a wide range of species. Zinc is a cofactor. At least seven enzymatic forms are known, and are classified into: (1) cytosolic (CA-I in erythrocytes; CA-II in bone, kidneys, brain, and other tissues; CA-III in skeletal muscle; and CA-VII in salivary glands); (2) GPI-anchored to plasma membrane (CA-IV in microvasculature; CA-IX in gastrointestinal mucosa); (3) mitochondrial (CA-VA and CA-VB); and (4) salivary secretion (CA-VI). CA-I, CA-II, and CA-III are encoded by a gene cluster at 8q22, whereas the others have different loci. Deficiency of CA-I in erythrocytes has no pathological consequences. Deficiency due to inactivating mutations in the gene for CA-II is associated with a syndrome of osteopetrosis, renal tubular acidosis, and cerebral calcification. *See also* **dehydratase**.

carbon cycle the sum total of chemical and biochemical processes whereby carbon is cycled between carbon dioxide in the atmosphere (and oceans) and organic compounds in organisms and their remains. Atmospheric carbon dioxide is fixed during photosynthesis by green plants and other photoautotrophic organisms, using solar energy to split water molecules and liberate O_2. The carbon dioxide is thus converted into glucose and other organic compounds, which are used as metabolic fuel and building blocks by the majority of organisms. Aerobic organisms, in particular, are able fully to oxidize organic compounds during respiration to release carbon dioxide to the atmosphere. The carbon stored in the remains of dead organisms is liberated by the respiration of decomposers or, especially that in fossil fuels, by combustion. Hence, photosynthetic organisms and aerobic heterotrophic organisms exist in a state of syntrophy. However, green plants and other aerobic autotrophs also liberate carbon dioxide during respiration. *Compare* **oxygen cycle**.

carbon dating *or* **radiocarbon dating** a technique for determining the age of specimens of biological origin, e.g. wood. It is based on determining the amount of **carbon-14** remaining in the specimen, the known half-life of carbon-14, and the assumption that the abundance of this radionuclide in the atmosphere has remained constant since its incorporation into the material from atmospheric CO_2.

carbon-dioxide buffer any aqueous solution of a water-soluble salt, pK_a 9–10, that, when equilibrated with CO_2, is capable of maintaining a constant partial pressure of CO_2 (pCO_2) in the gas phase in a closed vessel. Carbon-dioxide buffers are used especially in maintaining a constant pCO_2 in manometric experiments on reactions involving the steady production of that gas.

carbon-dioxide electrode an electrode system for determining CO_2 tension in a gas or a liquid. It consists of a combination pH electrode bathed in a thin layer of a dilute bicarbonate solution, the whole being separated from the sample by a rubber or silicone-rubber membrane permeable to CO_2 but not to water or ionizable solutes. The pH of the layer of bicarbonate solution, and hence the electrode's response, varies logarithmically with the CO_2 tension in the sample.

carbon-dioxide fixation the process whereby the carbon atoms of carbon dioxide are incorporated into hexoses by the **reductive pentose phosphate cycle**.

carbon-dioxide snow solid carbon dioxide in powder form. *See also* **dry ice**.

carbonic anhydrase *common name for* **carbonate dehydratase**.

carbonium ion any real or hypothetical cation, containing an even number of electrons and at least one penta-coordinate carbon atom, in which a significant part of the excess positive charge is located on one or more carbon atoms. *See also* **carbenium ion**, **carbocation**.

carbon monoxide CO; a colourless, odourless, toxic gas that combines with hemoglobin to form **carboxyhemoglobin**; it also combines with and inhibits cytochrome oxidase. It is produced physiologically during conversion of heme to biliverdin by heme oxygenase. Like nitric oxide, it is a neurotransmitter in the brain, where it activates cytosolic guanylyl cyclase by binding to its heme prosthetic group.

carbon monoxide-dehydrogenase any enzyme that catalyses the oxidation of carbon monoxide to carbon dioxide. Enzymes of this type contain either a nickel–iron–sulfur cluster or a molybdenum–pyranopterin. The 'hydrogen' involved comes from water; the oxygen is added to the carbon monoxide. Examples are carbon-monoxide dehydrogenase (cytochrome b_{561}) (EC 1.2.2.4) and carbon-monoxide dehydrogenase (ferredoxin) (EC 1.2.7.4). The term is also applied to acetyl-CoA synthase.

carbon-13 nuclear magnetic resonance spectroscopy *or* **^{13}C-NMR spectroscopy** a variant of **nuclear magnetic resonance spectroscopy** in which resonances in **carbon-13** nuclei in natural carbon of organic molecules are examined instead of proton responses. Carbon-12 has no NMR spectrum, and with a natural abundance of carbon-13 of 1.11%, a carbon-13 NMR spectrum has a several thousandfold disadvantage in signal-to-noise ratio compared with a proton NMR spectrum. However, the carbon-13 spectrum is much simpler and therefore has a particular advantage in large molecules. Since ${}^{13}C$–${}^{13}C$ coupling can be observed, a double labelling tracer technique is possible, using e.g. ${}^{13}CH_3$–${}^{13}COOH$ as a precursor in studies of **polyketide** biosynthesis.

carbon skeleton the arrangement of the carbon atoms in an organic molecule.

carbonyl the bivalent group =C=O (often written =CO); it is a characteristic group in aldehydes, ketones, and carboxylic acids. It is also the name of the carbon monoxide ligand in metal complexes.

carboprost (15*S*)-15-methylprostaglandin $F_{2\alpha}$; an oxytocic agent used to terminate pregnancy. *See also* **prostaglandins**.



Carbowax *proprietary name for* a group of polyethylene glycols of general formula $H[OCH_2–CH_2]_n–OH$ and of average M_r 400 to 20000.

carboxamide an amide derived from a carboxylic acid. The carboxamide group is $–CO–NH_2$. *See also* **carbamoyl**.

carboxamido *former name for* **carbamoyl**.

carboxy+ *prefix (in chemical nomenclature)* denoting the presence of a carboxyl group.

carboxyethyl *symbol*: Cet; the $–CH_2–CH_2–COOH$ group.

4-carboxyglutamic acid *or* **γ-carboxyglutamic acid** *symbol*: Gla; 1-aminopropane-1,3,3-tricarboxylic acid; a **noncoded amino acid**, one or more residues of which are present in a number of calcium-binding proteins, e.g. **osteocalcin** and **blood coagulation** factors II, VII, IX and X. It is formed subsequent to biosynthesis of the proteins by vitamin K-dependent carboxylation of glutamic acid residues.

carboxyhemoglobin a form of hemoglobin in which carbon monoxide has displaced oxygen from the heme group of hemoglobin, to which it binds with much greater affinity, and hence less reversibly than oxygen. The formation of carboxyhemoglobin thus reduces the oxygen-carrying capacity of the blood, and deprives tissues of oxygen. It is the basis of carbon monoxide poisoning.

carboxyl the chemical group –COOH in an organic molecule; it is acidic in character.

carboxylate **1** the anionic group $-COO^-$, formed by dissociation of a **carboxyl** group. **2** any salt, anion, or ester formed from a **carboxylic acid**. **3** to perform or undergo **carboxylation**.

carboxylation the introduction of a molecule of CO_2 into an organic compound.

carboxylic acid any organic acid containing one or more carboxyl (–COOH) groups.

carboxyl proteinase *or* **acid proteinase** *or* **aspartic proteinase** any enzyme of the sub-subclass EC 3.4.23 (aspartic endopeptidases), a common feature of which is a low pH optimum and an aspartic acid residue in the active centre. It includes **pepsins**, **rennins**, and **cathepsin D**.

carboxyl terminus *or* **carboxyl terminal** *an alternative name for* the **C terminus** (also called, less correctly, carboxy terminus or carboxy terminal). **—carboxy-terminal** *adj. Compare* **amino terminus**.

carboxy-lyase any enzyme of sub-subclass EC 4.1.1 that catalyses a decarboxylation reaction.

carboxymethyl *symbol*: Cm; the $-CH_2-COOH$ group.

carboxymethylation the process of introducing **carboxymethyl** groups into a substance; e.g. cellulose may be carboxymethylated to produce a cation-exchanger.

carboxypeptidase any enzyme of the sub-subclasses serine carboxypeptidases (EC 3.4.16) or metallo-carboxypeptidases (EC 3.4.17). Both types hydrolyse C-terminal amino-acid residues from oligopeptides or polypeptides. *See* **carboxypeptidase A**, **carboxypeptidase B**, **carboxypeptidase H**.

carboxypeptidase A EC 3.4.17.1; *other name*: carboxypolypeptidase. A **carboxypeptidase** enzyme that catalyses the hydrolysis of free C-terminal residues; zinc is a cofactor. The enzyme from bovine pancreas contains 307 amino acids, and its X-ray structure shows an eight-stranded mixed beta sheet.

carboxypeptidase B EC 3.4.17.2; *other name*: protaminase. A **carboxypeptidase** enzyme of bovine pancreas that catalyses the hydrolysis of C-terminal L-lysine (or L-arginine) to peptide and L-lysine (or L-arginine); zinc is a cofactor. It is also called thrombin-activated fibrinolysis inhibitor (TAFI) because it cleaves free C-terminal L-lysine from a fibrin clot.

carboxypeptidase C a **carboxypeptidase** enzyme, extracted from citrus leaves, that cleaves all free C-terminal residues.

carboxypeptidase D a **carboxypeptidase** enzyme, present particularly in *trans* Golgi network of glia cells and neurons, that plays a role in processing neuroendocrine peptides. It is specific for C-terminal L-lysine or L-arginine residues, and is a transmembrane protein with three carboxypeptidase domains, two of which are active.

carboxypeptidase E *see* **carboxypeptidase H**.

carboxypeptidase H EC 3.4.17.10; *other names*: carboxypeptidase E; enkephalin convertase; *(wrongly)* enkephalinase. A **carboxypeptidase** enzyme involved in prohormone processing. It catalyses the hydrolysis of free C-terminal L-lysine (or L-arginine) to peptide and L-lysine (or L-arginine); zinc is a cofactor. The enzyme (gene locus at 4q32) is expressed in brain, pituitary, and neurons, and is localized with prohormone convertases in peptide-containing secretory vesicles. A missense mutation (called fat mouse) in the mouse orthologue gene leads to maturity-onset obesity and infertility.

carboxypeptidase-tubulin *see* **tubulinyl-Tyr carboxypeptidase**.

carboxypeptidase Y a **carboxypeptidase** enzyme of yeast that cleaves all free C-terminal residues (glycine very slowly).

carboxy-terminal *see* **carboxyl terminus**.

carboxy terminus *a less correct alternative term for the* **C terminus** of a polypeptide chain. *See also* **carboxyl terminus**.

carcinoembryonic antigen *abbr.*: CEA; any member of a subfamily of immunoglobulin-like proteins on the outer cell surface and grouped in the cluster CD66 (*see* **CD markers**). **CD66e**, *other name*: **meconium antigen 100**, mass 180–200 kDa. It is a glycoprotein, attached to the membrane by a GPI-anchor. It is present in elevated concentrations in numerous nonmalignant conditions, and it can be used for monitoring therapy. **CD66d**, *other names*: **CGM1**, **CEA gene member 1**, is present on leukocytes and granulocytes, but not lymphocytes, monocytes, or tumours. Several forms are produced by alternative splicing. **CD66b** (*formerly* CD67), *other names*: **CGM6**, **CEA gene member 6**, is expressed in leukocytes of chronic myeloid leukemia patients and bone marrow. It is attached to the membrane by a GPI-anchor.

carcinogen any agent that directly or indirectly induces the transformation of a normal cell into a neoplastic cell. Such agents include various substances of small M_r (often termed **chemical carcinogens**), **oncogenic** viruses, ionizing radiations, and ultraviolet light. *See also* **precarcinogen**, **proximate carcinogen**. **—carcinogenic** *adj.*

carcinogenesis the process(es) involved in the production of **cancers**, including the action of **carcinogens** on living cells. *See also* **oncogenesis**.

carcinogenicity the measure or extent of the potency of a chemical **carcinogen**.

carcinoid (tumour) *or* **argentaffin carcinoma** *or* **argentaffinoma** any tumour arising from **argentaffin cells**. Carcinoids arise from any site of such cells, notably in the ileocecal region, and produce large amounts of 5-hydroxytryptophan and 5-hydroxytryptamine, the former mainly by bronchial tumours and the latter by the decarboxylase-containing intestinal tumours. Histamine, kinins, and substance P may also be produced.

carcinoma any cancer that arises from epithelial tissue. Carcinomas form malignant tumours that tend to invade lymph spaces in surrounding connective tissue and to spread by lymphatic permeation and embolism; they also enter the bloodstream to form **metastases**. **—carcinomatous** *adj.*

CARD domain *abbr. for* caspase recruitment domain; a protein interaction module comprising a bundle of six α-helices. CARD-containing proteins are involved in the regulation of apoptosis and inflammation through their activation of CARD-containing caspases and **jNF-κB**, which typically involves assembly of multi-protein complexes that facilitate dimerization or trimerization, or that serve as scaffolds on which proteases and kinases are assembled and activated. The module is related in sequence and structure to **death domains** and death effector domains, and shows similar interaction properties. The domains may occur in isolation, or in combination with other domains (e.g. **leucine-rich repeats**, **SH domains**, **RING**, kinase, and death domains).

cardenolide any of a group of C_{23} cardiotonic steroids characterized by a 14β-hydroxyl group and an unsaturated γ-lactone ring on C-17. They occur free or as the aglycons of **cardiac glycosides** in plants and insects.

cardiac **1** of, relating to, or affecting the heart. **2** of, or relating to, the upper part of the stomach.

cardiac glycoside any of a group of toxic steroid glycosides, derived from plants, that in pharmacological doses increase the power of the contractions of the mammalian heart; some are inhibitors of Na^+,K^+-ATPase. The steroid aglycon carries a 17β unsaturated pentenyl lactone ring and a 3β-hydroxyl group to which the carbohydrate moiety is attached. Examples are **digitoxin** from *Digitalis purpurea*, **ouabain** from *Strophanthus gratus*, and **strophanthin** from *Strophanthus kombe*.

cardiac K channel *see* **HERG**, **KCNE1**, **KVLQT1**, **long QT syndrome**.

cardiac muscle the specialized muscle of which the walls of the vertebrate heart are made. It is composed of a network (syncytium) of branching elongated cells (fibres) with cross striations, and undergoes spontaneous rhythmical contractions.

cardiac Na channel *see* **long QT syndrome**, **SCN5A**.

cardiac puncture a convenient and quick method for obtaining reasonable volumes of blood from an animal by inserting a syringe needle directly into the heart.

Cardice *proprietary name for* solid carbon dioxide. *See* **dry ice**.

cardio+ *or (before a vowel)* **cardi+** *comb. form* denoting heart.

cardioid *(in mathematics)* a type of expression that yields a heart-shaped curve.

cardiolipin an immunogenic 1,3-bis(3-phosphatidyl)glycerol. It is synthesized within mitochondria from two molecules of phosphatidyl glycerol with release of one molecule of glycerol and one of cardiolipin. It is present exclusively in the inner mitochondrial membrane. Antibodies against cardiolipin are commonly present in patients with systemic lupus erythematosus. Prepared from beef heart, it is used as an active antigen in the Wassermann reaction and other serological tests for syphilis. It may carry antigenic determinants similar to *Treponema pallidum* or be similar to products of tissue necrosis formed when the spirochaete attacks human tissues.

cardiomyopathy a progressive disorder that impairs the structure or function of the muscles in the ventricles of the heart. It is frequently **secondary** to an underlying condition, for example viral myocarditis, hypertension, or ischemic heart disease, and is an important cause of morbidity and mortality worldwide. Much less frequently it is **primary** and associated with defects of fatty acid beta-oxidation or in oxidative phosphorylation (due to mutations in nuclear or in mitochondrial genes). **Dilated cardiomyopathy** is connected with mutations in more than a dozen genes, including those for lamin A/C, desmin, α-cardiac actin, and Duchenne and Becker muscular dystrophies. **Hypertrophic cardiomyopathy** is associated with mutations in at least ten genes, including those for cardiac forms of actin, troponin T and troponin I, α-tropomyosin, regulatory or essential myosin light chains, myosin heavy chain, and myosin-binding protein C.

cardiotonic having the effect of improving the tone of heart muscle. Cardiotonic steroids (**cardiac glycosides**) act directly on heart muscle to restore the power of the heart's contractions.

cardiovascular of, or relating to, the heart and the system of blood vessels.

cargo protein any protein that is carried within the vesicles of a cell's secretory system (i.e. from the endoplasmic reticulum to the Golgi apparatus to the plasma membrane). *Compare* **resident protein**.

carmustine 1,3-bis(2-chloroethyl)-1-nitrosourea; an antineoplastic derivative of chloroethylnitrosourea with immunosuppressive and antifungal activity.



carnitine *γ*-amino-*β*-hydroxybutyric acid trimethylbetaine, 3-carboxy-2-hydroxy-*N*,*N*,*N*-trimethyl-1-propanaminium hydroxide, inner salt; $(CH_3)_3N^+–CH_2–CH(OH)–CH_2–COO^–$; a compound that is found in striated muscle, liver, and other tissues and participates in the transfer of acyl groups across the inner mitochondrial membrane. It is synthesized in liver and kidney from *N*-trimethyllysine (released by degradation of certain proteins) by a pathway that involves two ascorbic acid-dependent hydroxylations. The rate of synthesis is low in newborn and premature infants. Deficiency results from hemodialysis and from excessive renal loss in various organic acidurias. It is considered to be vitamin-like for such individuals.



L-carnitine

carnitine/acylcarnitine translocase a 32 kDa transmembrane protein, found in the inner mitochondrial membrane, that has a high affinity for the exchange of C_{12}–C_{16} acylcarnitine esters with **carnitine**. Several mutations of a gene at 2p21.3 lead to a deficient or nonfunctional translocase.

carnitine acyltransferase *or (sometimes)* **carnitine acylase** any of various enzymes that catalyse a reaction between acyl-CoA and carnitine to form CoA and *O*-acylcarnitine, which exchanges (via a carnitine/acylcarnitine translocase) across the inner mitochondrial membrane. This movement of carnitine is sometimes called the 'carnitine shuttle'. Carnitine *O*-acetyl transferase, EC 2.3.1.7, is found (in eukaryotes) in the mitochondrial matrix, peroxisomes, and the lumen of the endoplasmic reticulum. It is specific for short-chain fatty acyl-CoA (C_2–C_{14}) and provides a mechanism for the transport of acetyl groups, as acetylcarnitine, through the mitochondrial inner and peroxisomal membranes. Rare mutations in the gene at 9q34.1 result in a deficiency syndrome. Mitochondrial carnitine palmitoyltransferase, EC 2.3.1.21, exists as two isoforms. One isoform, CPT_1 *or* CPT-I, is a mitochondrial outer membrane protein involved in regulating fatty acid β-oxidation by controlling the rate of formation of carnitine acyl esters. Another isoform, CPT_2 *or* CPT-II, is located in the mitochondrial inner membrane and re-forms acyl-CoA esters in the mitochondrial matrix after the carnitine esters have been transported through the inner membrane by acylcarnitine:carnitine antiporter.

carnitine transporter an Na^+-dependent organic cation transporter (OCNT 2) present in the plasma membrane of cells of liver, muscle, and other tissues. The gene at 5q31.2-q32 encodes a protein of 557 amino acids, which shows ≈80% sequence homology with OCTN 1. Several mutations in the OCTN 2 gene result in systemic carnitine deficiency.

carnosine *N*-*β*-alanyl-L-histidine; a substance that occurs in the skeletal muscle of some animals, including humans (up to 30 mmol kg^{-1}). *Compare* **anserine**.



carnosine

carotene *see* **carotenoid**.

carotenoid any of the naturally occurring tetraterpenes that are widely distributed in plants and animals but only synthesized by higher plants, algae, fungi, and bacteria. They may be represented formally as consisting of eight isoprenoid (ip) residues and formed by the joining tail to tail of two units each comprising four ip residues joined head to tail: ip.ip.ip.ip.pi.pi.pi.pi. There are two groups: **carotenes**, which are hydrocarbons, and **xanthophylls**, which contain oxygen in various forms. They occur in all photosynthetic tissues, where they function as protectors against photosensitization and as antenna pigments in photosynthesis. α-Carotene is the precursor of vitamin A.

carrageenan *or* **carrageen** *or* **carrageenin** a mixture of sulfated galactans, also known as **Irish moss**, extracted from red seaweeds (class Rhodophyceae), particularly *Chondrus crispus* and *Gigartina stellata*. It shows blood anticoagulant activity and is used as a gelling and stabilizing agent in foods and pharmaceuticals. Three major types are known: ι-carrageenan is the most highly sulfated and contains alternate units of 3-linked *β*-D-galactopyranose 4-sulfate and 4-linked 3,6-anhydro-α-D-galactopyranose 2-sulfate; κ-carrageenan is precipitated by potassium chloride and contains only one sulfate per disaccharide unit; λ-carrageenan is largely devoid of the 3,6-anhydro component. ι-Carrageenan forms a kinked double-helical structure. [After Carragheen, near Waterford, Republic of Ireland.]

κ-carrageenase EC 3.2.1.83; an enzyme that catalyses the hydrolysis of 1,4-*β*-D-linkages between D-galactose 4-sulfate and 3,6-anhydro-D-galactose in various carrageenans.

carrier 1 any known or putative component of a biological membrane that effects the transfer of a specific substance or group of related substances from one side of the membrane to the other. The mechanism is supposedly a cyclic process, involving combination of the carrier with the substance(s) on one side of the membrane, diffusion of the combined form across the membrane, release of the substance(s) on the far side, and diffusion of the carrier back across the membrane in uncombined form. *See also* **facilitated diffusion**, **per-**

mease, **translocation**, **transport**. **2** any component of a biological fluid (e.g. a blood protein) that can combine with a specific substance (e.g. a hormone or metabolite) and transport it from one part of the organism to another. **3** *(in enzymology)* any substance undergoing reversible combination with a metabolite or reversible oxidation–reduction and thereby carrying the metabolite, electron(s), or hydrogen atom(s) between enzymes or cellular organelles, or into cells. Some **coenzymes** may act as carriers. *See* **electron carrier**, **hydrogen carrier**. **4** a substance that is mixed with a reagent or other substance to facilitate the chemical or physical manipulation of the latter. The carrier is commonly of similar constitution and/or properties to the reagent, and present at relatively high concentration. The term is used especially for the nonradioactive chemical counterpart of a radionuclide or of a compound containing a radionuclide, whether deliberately added or present from the time of initial preparation of the radioactive substance. *Compare* **carrier-free**. **5** *(in chromatography)* the **mobile phase** or a component thereof. *See* **carrier ampholyte**, **carrier displacement chromatography**, **carrier gas**. **6** *or* **matrix** the inert support material to which a small molecule, biopolymer, cell fragment, or intact cell is artificially linked to form an immobilized or insolubilized derivative. *See also* **microcarrier**. **7** any vesiculated structure within which a biologically active substance (e.g. a drug or enzyme) is artificially incorporated, commonly to protect the substance from degradation and/or to direct it to a target organ upon injection into the bloodstream. Such a carrier may be either artificial (e.g. a **liposome**) or of natural origin (e.g. an erythrocyte **ghost**). **8** *(in immunochemistry)* any substance of high M_r (e.g. a protein) to which a non- or poorly immunogenic substance (e.g. a **hapten**) is naturally or artificially linked to enhance its immunogenicity. **9** *(in genetics)* any individual who is heterozygous for a specified recessive allele and who thus does not normally display any characteristic (e.g. a disease) associated with that allele but who may, with appropriate mating, produce homozygous offspring that exhibit the recessive characteristic. **10** *(in pathology)* any individual who harbours a specified infectious microorganism without showing signs of disease, and is capable of transmitting the microorganism to others. *Compare* **vector** (def. 2). *See also* **vehicle**.

carrier ampholyte a mixture of amphoteric electrolytes used in **isoelectric focusing** to generate a linear and stable pH gradient, and in **isotachophoresis** and **ampholyte displacement chromatography**. The component electrolytes are commonly of similar constitution, low molecular mass, and closely spaced isoelectric points. *See also* **Ampholine**.

carrier displacement chromatography a variant of **displacement chromatography** in which substance(s), either related or unrelated, are added to the mixture being chromatographed to assist in the manipulation of the components separated.

carrier-free describing a preparation of a radionuclide, or of a radionuclide-labelled compound, to which no carrier has been added, and for which precautions have been taken to minimize contamination with other isotopic nuclides. It does not necessarily imply, however, 100% isotopic abundance. Material of high specific activity is often wrongly referred to as 'carrier-free'; more correctly it would be of high isotope abundance.

carrier gas the inert gas that forms the mobile phase in **gas–liquid chromatography** or gas–solid chromatography and that carries the eluted substances in gaseous form into the detector.

carrier lipid *see* **undecaprenol**.

carrier protein any protein that functions as a **carrier** (def. 8); e.g., **acyl carrier protein**. The term has been applied more specifically to describe **cytochome b_5**, **ADP**, **ATP carrier protein**, and **GDC** (Graves' disease carrier protein).

Carr-Price reaction the reaction of an anhydrous solution of antimony trichloride in chloroform with retinol (vitamin A) to produce a transient blue colour, maximal at about 10 s. It can be used to estimate retinol.

CARS *abbr. for* **coherent anti-Stokes Raman spectroscopy**.

Cartesian of, or relating to, the French philosopher and mathematician René **Descartes** (1596–1650) or his works.

Cartesian coordinates a system of coordinates that defines the location of a point in a plane (two dimensions) or in a space (three dimensions) in terms of its perpendicular distance from each of a set (two or three) of mutually perpendicular axes.

Cartesian diver *or* **Cartesian devil** a device, devised as a toy, adapted as an ultramicrorespirometer, consisting of a small piece of capillary glass tubing open at one end and closed and slightly expanded at the other. A sample of tissue, in approximately 2 μL buffer, is placed in the vessel, which is then filled with gas and the neck sealed with a drop of oil. The diver is placed in a constant-temperature vessel filled with a solution in which the diver just floats. If the pressure in the vessel is reduced the diver will rise and if the pressure is increased the diver will fall. The buoyancy of the diver is determined by the gas volume within it, and changes in the latter may be measured by adjusting the pressure in the vessel so that the diver floats in the same position.

cartilage a tough, elastic type of **connective tissue**, found in most vertebrates. It is a major component of the embryonic skeleton, but in higher vertebrates it is mostly converted to bone during development. In adult humans, it is largely confined to the ears, nose, trachea, the anterior ends of the ribs, and the articular surfaces of bones. Cartilage consists of a firm resilient matrix, formed by chondroblasts (which become enclosed as chondrocytes), and composed of glycosaminoglycans including **chondroitin sulfate** A and C, hyaluronic acid, and keratosulfate II, together with varying amounts of **collagen**. The entire skeleton of some lower vertebrates, notably the cartilaginous fishes (class Chondrichthyes), consists of cartilage. **—cartilaginous** *adj.*

cartilage link protein a protein that stabilizes the aggregates of proteoglycan monomers with hyaluronic acid in the extracellular cartilage matrix.

cartilage oligomeric matrix protein *abbr.*: COMP; a pentameric disulfide-linked Ca^{2+}-binding **EF-hand** protein of the cartilage matrix.

cartilage-specific proteoglycan core protein a major proteoglycan of the extracellular matrix of cartilaginous tissues. The N-terminal region binds hyaluronic acid. Chondroitin sulfate is the main glycan component, but keratan sulfate and O-linked and N-linked oligosaccharides are also present. It also has an epidermal growth factor-like domain and a **Sushi domain**.

caryon *a variant spelling of* **karyon**.

caryopsis *see* **grain**.

CAS 1 *abbr. for* carbonic anhydrase. **2** *abbr. for* Chemical Abstracts Service.

cascade sequence *or* **waterfall sequence** a sequence of successive activation reactions involving either enzymes (**enzyme cascade**) or hormones (**hormone cascade**), or both. There are various examples: (1) the series of transformations of proteolytic enzymes in **blood coagulation** in which each enzyme activates the next until the final substrate, fibrinogen, is reached; (2) the series of reactions involved in the formation of, and mediation of the action of second messengers, e.g. in the activation of **glycogen phosphorylase**; (3) the process of activation of **steroidogenesis** in the adrenal gland by hypothalamic and pituitary hormones. The term has also been applied to other sequential phenomena, e.g. DNA → RNA → protein. Cascade sequences are characterized by a series of amplifications of a weak initial stimulus, and may be activated at more than one point along the sequence.

cascara the dried bark of the small tree *Rhamnus purshiana*. It is a potent purgative due to its constituent hydroxyanthracene derivatives (anthroglycosides), including cascarosides and related glycosides. These yield active anthracene derivatives after metabolism by colonic bacteria.

casein 1 *or (esp. Brit.)* **caseinogen** the principal protein fraction of milk; it is present as a colloidal suspension, and may be precipitated by acidification. It is a mixture of several related proteins (α-, β-, γ-, and λ-caseins), which differ in amino-acid composition and which may be separated electrophoretically. The α- and β-caseins are rich in phosphate, present mainly as *O*-phosphoserine residues, which bind calcium ions. Casein is easily prepared, and is valuable as a dietary supplement. **2** *or (esp. US)* **paracasein** the product formed by coagulation of milk (or **casein** (def. 1)) by treatment with chymosin (rennin). This enzyme removes a 64-residue carbohydrate-rich hydrophilic C-terminal moiety of λ-casein, thereby destroying the latter's protective action on the casein micelles, thus allowing them to be precipitated by the calcium ions present.

casein kinase I any of a family of ubiquitously expressed monomeric serine/threonine protein kinases found in a variety of subcellular locations in all eukaryotic organisms from protozoa to humans. There are seven isoforms in human cells, and all contain a kinase domain flanked by divergent N- and C-terminal extensions. They play roles in Wnt signalling, circadian rhythms, nuclear import, and progression of Alzheimer disease, and have a general preference for acidic substrates. The family is named after the first of two fractions to elute from an anion-exchange column with the ability to phosphorylate the acidic milk protein casein.

caseinogen *an alternative name (esp. Brit.) for* **casein** (def. 1).

CAS number *abbr. for* Chemical Abstracts Service Registry Number; a unique identifier for a compound.

casomorphin *or* **exomorphin** any of a number of opioid peptides isolated from an enzymatic digest of bovine casein; activity corresponds to residues 60–66 of bovine β-casein. *See also* **morphiceptin**.

CASP *abbr. for* **1** critical assessment of structure prediction; *see* **critical assessment competition**. **2** CTD-associated SR-like protein (carboxy terminal domain-associated splicing-recognition-like protein); any protein that contains a motif for sequence-specific RNA-binding and a domain for binding to the C-terminal domain of RNA polymerase II. *See* **SCAF**.

caspase any of a family of cysteine endopeptidases that cleave proteins at specific aspartic acid residues. The prototype is ICE (interleukin 1β-converting enzyme, now called caspase 1). Procaspases are activated in cascade fashion in response to a proapoptotic stimulus (e.g. DNA damage, heat stress, oxidative stress) by proteolytic cleavage at consensus sites. Activation is controlled by apoptosis inhibiting factors, e.g. Bcl-2 (*see* ***BCL***), which is an integral protein of the outer mitochondrial membrane and regulates release of **apoptosis protease-activating factor 1** (Apaf-1) and cytochrome *c* from the intermembrane space. The cascade involves initiator (or upstream) components that contain a death effector domain. It starts with binding of procaspase 8 (also called FLICE) to death receptors, its activation, formation of a death-inducing signalling complex (DISC), and activation of several procaspases. A major effector (or executioner, or downstream) component is caspase 3, which is activated by caspase 9, Apaf-1, and cytochrome *c*. Procaspase 12 is associated with the endoplasmic reticulum. Caspases are essential for the proteolytic reactions of **apoptosis**..

cassette an informal name given to a functional segment of DNA, for example a dominant selectable marker such as *neo*^{R} under the control of an appropriate promoter. Cassettes may be used in making DNA constructs such as plasmids. Naturally occurring cassettes include those involved in mating type switching in yeasts.

castasterone 24-methylcholesterol the precursor of brassinolide in plants. *See* **brassinosteroid**.

castor oil an oil derived from seeds of the plant *Ricinus communis*. It contains triglycerides of ricinoleic, oleic, linoleic, palmitic, and stearic acids.

CAT *abbr. for* **1** computer of average transients. **2** chloramphenicol *O*-acetyltransferase. **3** computer-assisted tomography.

catabolic dead-end a point in a **catabolic pathway** where, in a particular organism, a metabolite is neither catabolized further nor excreted but accumulates intracellularly. Consequently the pathway is unable to function as an energy-yielding process. The enzyme that can form the metabolite thus lacks an obvious role in that organism.

catabolic pathway any degradative, usually exergonic, sequence of reactions. *Compare* **anabolic pathway**. *See also* **amphibolic**.

catabolism *or* **katabolism** any metabolic process involving the breakdown of complex substances into smaller products, including the breakdown of carbon compounds with the liberation of energy for use by the cell or organism. *Compare* **anabolism**. **—catabolize** *or* **catabolise** *vb.*; **catabolic** *adj.*

catabolite any product of a **catabolic pathway**.

catabolite (gene) activator protein *abbr.*: CAP; *other names* **cAMP receptor protein**, **cAMP-regulatory protein** (*abbr.*: CRP); a protein that binds to and is activated by cAMP. It then acts as a transcription-initiation factor, binding near the operator of bacterial operons that are subject to **catabolite repression** and being necessary for their efficient transcription. For example, transcription of the *lac* operon is increased 50-fold in the presence of the CAP/cAMP complex. It belongs to the **CRP** family of transcription factors.

catabolite inhibition a general regulatory mechanism, found in *Escherichia coli*, that controls the activity of an early reaction in carbohydrate metabolism. For instance when *E. coli* is grown in synthetic medium with radioactive galactose or lactose as the carbon source, the addition of glucose rapidly inhibits utilization of the radioactive substrate. Subsequent removal of the glucose rapidly reverses the inhibition.

catabolite repression a mechanism of genetic regulation in bacteria in which the accumulation of catabolites in the cell represses the formation of enzymes that contribute to the formation of the catabolites. In *E. coli* the intracellular concentration of cAMP is low when cells are grown on media containing glucose and high when glucose is depleted. Binding of cAMP to **catabolite (gene) activator protein** (CAP) promotes transcription of *lac* and other operons such as *ara*.

catalase EC 1.11.1.6; a widely distributed homotetrameric enzyme that catalyses the formation of $O_2 + 2\ H_2O$ from two molecules of H_2O_2; most commonly heme is a cofactor. It plays an important role in removing H_2O_2 formed in peroxisomes in animals and plants and in **glyoxysomes** in plants. In erythrocytes it is cytosolic. The molecule is an eight-stranded beta barrel and contains 13 alpha helices. A mutation in the gene locus at 11p13 is associated with acatalasemia. A microbial catalase contains a dinuclear manganese centre instead of heme.

catalase-peroxidase an enzyme with both **catalase** and **peroxidase** activity. The enzyme from *Mycobacterium tuberculosis* is required for sensitivity to isoniazid.

catalatic of, or pertaining to, **catalase**.

catalyse *or (esp. US)* **catalyze** to influence a reaction through **catalysis**.

catalysis an increase in the rate of a chemical reaction brought about by a **catalyst**. **—catalytic** *adj.*; **catalytically** *adv.*

catalysome **1** an enzyme-containing cap found on lipid droplets in the fat body of some insects. **2** a mitochondrion-like organelle specialized for lipid metabolism, found in adipose tissue.

catalyst any substance that increases the rate of a chemical reaction but is itself unchanged at the end of the reaction. Catalysts are usually present in very low concentrations relative to those of the substances whose reaction they are catalysing.

catalytic activity an index of the actual or potential activity of a catalyst. The catalytic activity of an enzyme or an enzyme-containing preparation is defined as the property measured by the increase in the rate of conversion of a specified† chemical reaction that the enzyme produces in a specified† assay system. [†This word, in one or other position, has been misprinted as 'specific' in certain published versions of this definition.] Catalytic activity is an extensive quantity (*see* **extensive property**) and is a property of the enzyme, not of the reaction mixture; it is thus conceptually different from rate of conversion although measured by and equidimensional with it. The unit for catalytic activity is the **katal**; it may also be expressed in mol s^{-1}. Dimensions: N T^{-1}. Former terms such as catalytic ability, catalytic amount, and enzymic activity are no longer recommended. Derived quantities are **molar catalytic activity**, **specific catalytic activity**, and **catalytic activity concentration**.

catalytic activity concentration *or* **catalytic concentration** the **catalytic activity** of an enzyme per unit volume, where volume refers to that of the original enzyme-containing preparation, not that of the assay system. It may be expressed in katals per litre.

catalytic amount the amount of a substance used in a chemical reaction as a catalyst, primer, or sparker. It is generally much smaller than the stoichiometric amounts of either reactants or products. For an enzyme the term is now obsolete and replaced by **catalytic activity**.

catalytic antibody a monoclonal antibody that emulates an enzyme activity. Typically it is raised against a compound that mimics the transition state of the reaction.

catalytic assay a technique for measuring low concentrations

(≈1 μM) of substrates in certain enzyme-catalysed reactions (e.g. NAD(P)$^+$ or coenzyme A), where simple kinetic methods are not feasible because too-rapid consumption makes reaction rates impossible to measure reliably. Conditions are arranged so that the concentration of the substrate in question is kept constant by a regeneration reaction, the substance being made to behave as an intermediate catalyst. The regeneration reaction may act also as the indicator reaction. For example, NAD$^+$ may be determined by coupling the reaction catalysed by alcohol dehydrogenase (EC 1.1.1.1) to the combined regeneration/indicator reaction catalysed by cytochrome *c* reductase (EC 1.6.99.3), according to the equations:

$$\mathrm{NAD^+ + C_2H_5OH \rightarrow NADH + CH_3CHO + H^+}$$

and

$$\mathrm{NADH + H^+ + 2\ Cyt}\ c^{3+} \rightarrow \mathrm{NAD^+ + 2\ Cyt}\ c^{2+} + 2\ \mathrm{H^+}.$$

The rate of increase in absorbance of Cyt c^{2+} at 550 nm is measured. If the coupled regeneration reaction does not act as an indicator reaction, the technique is known as **enzymic cycling**. *Compare* **coupled assay**.

catalytic concentration *an alternative term for* **catalytic activity concentration**.

catalytic constant *symbol*: k_{cat} *or* k_0; a measure of the catalytic potential of an enzyme, customary unit s^{-1}. In general it is the value of the velocity of the reaction, *v*, divided by the stoichiometric concentration of active sites, $[E]_0$, obtained by extrapolating all substrate concentrations to infinity; alternatively it can be expressed as $V_{\mathrm{max}}/[E]_0$, where V_{max} is the **limiting rate**. k_{cat} is also known as the **turnover number**, because it represents the number of reactions catalysed per unit time by each active site.

catalytic domain *see* **domain** (def. 3).

catalytic exchange method a method for randomly labelling a compound with tritium. A solution of the compound in a tritiated hydroxylic solvent is allowed to stand in the presence of metal catalysts and either acid or base.

catalytic facilitation a process whereby the product formed by one enzyme in a complex is passed directly to the catalytic site of the next enzyme in a reaction sequence more efficiently than when the second substrate is supplied from the environment.

catalytic factor a term sometimes used of a specified enzyme to define the quantitative ratio between the rates of a chemical reaction in the presence and the absence of the enzyme but otherwise under the same conditions.

catalytic intermediate a chemical species produced during the course of a catalytic reaction, intermediate between reactants and products.

catalytic power a measure of the ability of an enzyme to accelerate a chemical reaction.

catalytic residue any of the amino-acid residues in an enzyme that are directly involved in making or breaking covalent bonds while the enzyme is acting on a substrate.

catalytic site the site on a catalyst that is concerned with catalysis, especially as part of the **active site** of an enzyme.

catalytic triad a group of three amino acid residues in an enzyme whose specific conformation and proximity in 3D space mediates the catalytic activity. For example, in serine proteases the catalytic triad Ser–His–Asp cleaves substrates at specific peptide bonds. Protein families with markedly different structures possess this triad, suggesting possible convergent evolution from independent origins.

catalyze *the US spelling of* **catalyse**.

cataplerosis the process by which an intermediate in the citric acid cycle is removed to prevent its accumulation in the mitochondrial matrix. –**cataplerotic** *adj.*

cataract opacity of the eye lens resulting from modification or degeneration of lens **crystallins**. It is the commonest form of blindness in many developing countries, and can result from biological aging, from other pathological processes (e.g. injury, radiation, diabetes mellitus), or as a consequence of primary ocular or dysmetabolic genetic disorders. It is described as congenital or infantile, juvenile, presenile, or senile, depending on age of onset.

CAT assay assay of **chloramphenicol *O*-acetyltransferase**, frequently employed to detect expression of its gene in cDNA technology.

catastrophe theory *see* **error catastrophe hypothesis**.

CAT box *see* **CAAT box**.

catechin the type compound for one of the 12 classes of flavanoids. It is characterized by oxidation state (OH at C-3) of the central pyran ring. Some 70 catechins are known; e.g. (+)-catechin is (2*R*,2*S*)-3,3′,4′,5,7-flavanpentol. Catechins are among the polyphenols widely distributed in vegetable foods, arising biosynthetically from the **shikimate** pathway. (+)-Catechin produces artificial cross-links in collagen *in vitro* and has anti-tumour activity. Catechin and **curcumin** have been found to be non-toxic, non-mutagenic, non-teratogenic and excellent anti-mutagens and anti-carcinogens.



(+)-catechin

catechol 1 *former name for* **pyrocatechol**. **2** any aromatic *o*-diol; any compound containing a pyrocatechol nucleus or substituent. *Compare* **hydroquinone** (def. 2), **quinone** (def. 2).

catecholamine any of a group of physiologically important **biogenic amines** that possess a **catechol** (def. 2) (i.e. 3,4-dihydroxyphenyl) nucleus and are derivatives of 3,4-dihydroxyphenylethylamine. They include **adrenaline** (epinephrine), **noradrenaline** (norepinephrine), and **dopamine**. Catecholamines have various physiological roles, particularly as neurotransmitters, and produce effects in the brain, the cardiovascular system, and other organs; they also help to regulate carbohydrate and fat metabolism.

catechol melanin any of various deep-brown or black plant pigments, so called because they yield catechol on alkali fusion. *See also* **melanin**.

catechol-*O*-methyltransferase EC 2.1.1.6; *systematic name*: *S*-adenosyl-L-methionine:catechol *O*-methyltransferase. An enzyme found primarily in non-neuronal tissues and catecholamine-releasing neurons, especially in the periphery; it effects *O*-methylation of catecholamines and their deaminated metabolites, but is less active against catechols. It catalyses the reaction between *S*-adenosyl-L-methionine and catechol to form *S*-adenosyl-L-homocysteine and guaiacol; in catecholamines it methylates the phenolic group at position 4. This inactivates catecholamine neurotransmitters and catechol hormones. In humans the membrane-bound protein consists of 271 amino acids; a cytosolic form (residues 52–271) lacks the transmembrane signal anchor.

catechol oxidase *see* **polyphenol oxidase**. *See also* **monophenol monooxygenase**.

catenane any type of compound containing two or more rings that are interlocked but not covalently joined; i.e. resembling the links of a chain. An example is an interlocked circular duplex DNA molecule found in mitochondria. *Compare* **concatemer**.

catenate 1 to interlock, without covalent bonding, two or more circular structures, e.g. cyclic molecules. **2** linked as the interlocked rings of a chain. *Compare* **concatenate**. —**catenated** *adj.*; **catenation** *n.*

catenin any of four intracellular attachment proteins of the armadillo family, designated α, β, γ, and δ. They bind actin microfilaments to the cytoplasmic domain of E-cadherin at adherens junctions of epithelial cells. **α-Catenin** (906 amino acids) is homologous with **vinculin**. **β-Catenin** (781 amino acids) is enriched in adherens junctions in cells lining the mammalian cerebral ventricles; it is homologous with **γ-catenin** (*or* **plakoglobin**). **δ-Catenin** is expressed in neurons, where it associates with presenilins. APC protein (*see* ***APC***) plays an important role in regulating the stability of free β-catenin. A complex containing β-catenin, APC protein, **axin**, and **GSK-3** is targeted for ubiquitination and degradation by proteasomes. In the absence of functional APC protein (as occurs in many human cancers, including colorectal cancer) β-catenin is not degraded, enters the nucleus and enhances transcription by binding to members of the T cell-specific transcription factor/lymphoid enhancer-binding factor (TCF/LEF) family. Also, β-catenin acts as a transcriptional enhancer during Wnt protein signalling.

catestatin the 21-residue polypeptide that constitutes residues 352 to 372 of chromogranin A. It inhibits catecholamine release from the adrenal medulla.

cat-eye syndrome (*abbr.*: CES) *or* **Schmid–Fraccaro syndrome** a genetic disorder in which there is partial trisomy or tetrasomy of chromosome 22pter-22q11. It is named after a distinctive eye abnormality seen in some individuals in which there is partial absence of eye tissue (coloboma). Symptoms vary in type and severity but can include malformations of the skull and face, heart and kidneys. The anal canal may be absent and a fistula or abnormal passage formed between the rectum and the bladder or vagina of females, and the bladder or urethra of males.

CATH *abbr. for* class architecture topology homology; *see* **structure classification database**.

cathepsin any of a group of intracellular peptide hydrolases.

cathepsin A *an alternative name for* **protective protein/cathepsin A**.

cathepsin B EC 3.4.22.1; *other name*: lysosomal cysteine endopeptidase. An enzyme that catalyses the hydrolysis of proteins with broad specificity for peptide bonds; preferentially, it cleaves -Arg-Arg-|-Xaa- bonds in small substrates. It is a glycoprotein dimer, comprising a heavy chain and a light chain cross-linked by a disulfide bond.

cathepsin C EC 3.4.14.1; *recommended name*: dipeptidyl peptidase I. An enzyme that catalyses the hydrolysis of dipeptides from the N terminus of a polypeptide, except where the N-terminal residue is Arg or Lys, or where the adjacent amino acid is Pro. It also catalyses the transfer of dipeptide residues.

cathepsin D EC 3.4.23.5; a lysosomal aspartic endopeptidase that is active in intracellular protein breakdown. It has a specificity similar to, but narrower than, that of **pepsin A**. The molecule comprises a light chain and a heavy chain.

cathepsin E EC 3.4.23.34; an aspartic endopeptidase with similar activity to **cathepsin D**, but found in lymphoid-associated tissue. It may have a role in immune function.

cathepsin G EC 3.4.21.20; a glycoprotein serine endopeptidase with a specificity similar to that of **chymotrypsin**. It is found in the lysosomes of polymorphonuclear leukocytes and exhibits bactericidal activity against fungi and Gram-negative bacteria. It is therefore a **serpocidin**. Its gene is at 14q11.2.

cathepsin H EC 3.4.22.16; a lysosomal cysteine endopeptidase that also acts as an aminopeptidase on peptide substrates with a free N terminus. It is composed of a minichain and a large chain; the large chain may be split into heavy and light chains; all chains are held together by disulfide bonds.

cathepsin K a cysteine protease, with strong collagenase and gelatinase activity, that is selectively expressed in osteoclasts and plays a key role in bone growth and remodelling. The gene, at 1q21, encodes a protein of 329 amino acids, which is processed into a mature enzyme of 215 amino acids; this shows ≈60% sequence homology with cathepsins L and S. At least 10 mutations in the gene are associated with deficiency of cathepsin K and **pycnodysostosis**, a disorder of bone matrix remodelling.

cathepsin L EC 3.4.22.15; *other name*: major excreted protease (*abbr.*: MEP). A lysosomal cysteine endopeptidase that hydrolyses proteins but not acylamino acid esters, and has no peptidyl-dipeptidase activity – the activity is similar to that of **papain**. It is found in rat-liver and other mammalian lysosomes, and is inhibited by **leupeptin**. It consists of a heavy and a light chain linked by disulfide bonds. It shows ≈60% sequence homology with cathepsins K and S.

cathepsin S EC 3.4.22.27; a lysosomal cysteine endopeptidase with similar activity to **cathepsin L** but more activity for -Val-Val-Arg-|-Xaa. It shows ≈60% sequence homology with cathepsins K and L. Its gene is located near that for **cathepsin K** on 1q21, but unlike the latter is not associated with pycnodysostosis.

cathilicidin a pore-forming toxin permitting passage of small molecules across biomembranes. It is produced by certain mammals, such as horses, and contains 90–250 amino acid residues. Cathilicidin is classified in the TC system under number 1.C.33.

cathinone S(–)-2-amino-1-phenyl-1-propanone, the major central nervous system stimulant of the khat shrub, *Catha edulis*. Like amphetamine, it is a potent releaser of norepinephrine and dopamine from their intracellular stores.



cathode *or (formerly)* **kathode 1** the electrode of an electrolysis cell or electrophoresis apparatus towards which cations of the electrolyte migrate under the influence of an electric field applied between the electrodes. **2** negative electrode: the electrode, pole, or terminal of a discharge tube, solid-state rectifier, thermionic valve, or other apparatus by which conventional electric current returns to an external source; i.e. the electrode through which electrons flow into such a device. **3** the positive pole or terminal of an electric (primary or secondary) cell or battery (of cells); i.e. the pole from which electrons emerge from such a device. *Compare* **anode**. —**cathodal, cathodic,** *or* **cathodical** *adj.*; **cathodally** *or* **cathodically** *adv.*

cathode-ray tube a vacuum tube in which a beam of electrons is emitted and focused by an electron gun onto a fluorescent screen. The beam can be deflected by horizontal and vertical electrostatic or magnetic fields to produce a visual display of electric signals, as in a television tube or cathode-ray oscilloscope.

catholyte in isoelectric focusing, the electrolyte that is in immediate contact with the cathode.

cation *or (formerly)* **kation** any **ion** with a net positive charge. In a solution being electrolysed, a cation migrates towards the **cathode**. *Compare* **anion**. —**cationic** *adj.*

cation exchange the process of **ion exchange** in which one cation is exchanged for another cation.

cation exchanger any **ion exchanger** that is able to exchange cations with the surrounding solution. *See also* **ion-exchange resin**.

cationic acid any acid that carries a positive charge, i.e. is a **cation**.

cationic detergent any **detergent** in which the polar part of the molecule carries one or more positive charges.

cationized ferritin a polycationic derivative of **ferritin** prepared by coupling horse-spleen ferritin with *N*,*N*-dimethyl-1,3-propanediamine, most of the carboxyl groups on the ferritin molecule thereby being converted into positively charged tertiary amino groups. It is useful for labelling negatively charged groups on cell surfaces, where the ferritin particles may easily be identified by electron microscopy because of their electron-dense iron cores.

cationmotive describing any enzyme, enzyme system, or other process that produces the vectorial movement of cations, especially across a biomembrane. The particular cation(s) may be specified, e.g. protonmotive, Na^+/K^+-motive.

catsper a protein of spermatozoa. Deficiency in the mouse leads to infertility and defective motility of spermatozoa.

CAU a codon in mRNA for L-histidine.

caudal a homeodomain transcription factor which forms a concentration gradient in the opposite direction to that of **bicoid protein**, possibly as a result of the translation control exerted on the caudal mRNA by bicoid.

cauliflower mosaic virus a double-stranded DNA virus that is a potential recombinant vector for plants.

caulimovirus any double-stranded DNA plant virus belonging to the *Caulimovirus* group, the type member of which is the **cauliflower mosaic virus**.

caustic soda *see* **soda**.

caveola (*pl.* **caveolae**) a flask-shaped invagination of the plasma membrane, rich in cholesterol, glycosphingolipids, caveolins, and glycosylphosphatidylinositol (GPI)-anchored proteins and proteins involved in transmembrane signalling (e.g. receptors, G-proteins, and protein kinases). Caveolae are clathrin-independent and do not undergo lysosomal degradation. They are sites for the concentration and uptake of small molecules that are ligands for GPI-anchored proteins. Folates, chemokines, and many pathogens or their products (e.g. HIV, cholera toxin) enter cells through caveolae.

Cholesterol efflux also is mediated by caveolae. They are prominent in fibroblasts and endothelial cells, but are found in many other cell types. Their formation is decreased in transformed cells. *See* **potocytosis**. [From Latin *cavea*, a small cavity.]

caveolin a protein that lines the cytoplasmic surface of a **caveola**.

C-beta *an alternative term for* **beta carbon atom**.

CBF *abbr. for* centromere binding factor (*see* **centromere binding proteins**).

CBG *abbr. for* cortisol binding globulin. *See* **transcortin**.

CBL a protooncogene related to v-*cbl*, the nuclear oncogene of Cas NS-1 retrovirus, named from Casitas B-lineage lymphoma. The function of the normal protein is unknown, but it may be a transcriptional regulator. v-*cbl* encodes a truncated form of Cbl, which has lost a C-terminal leucine zipper and a 208-residue proline-rich region.

Cbm *symbol for* carbamoyl.

CBN *abbr. for* (IUPAC-IUB) Commission on Biochemical Nomenclature; now succeeded by **JCBN**.

CBP *abbr. for* CREB protein-binding protein; a large nuclear multifunctional protein expressed in most vertebrate cell types that binds to a wide variety of transcription factors and has intrinsic histone acetyltransferase activity. The gene for CBP at 16p13.3 encodes a multidomain protein of 2442 amino acids, which contains domains for nuclear hormone receptor and **CREB protein** binding, four zinc fingers, a bromodomain, a glutamine-rich domain, and a histone acetyltransferase domain. It is thus a general transcriptional adaptor and integrator. Microdeletions and point mutations in the gene are responsible for Rubinstein–Taybi syndrome, which is characterized by abnormalities of the face, thumbs, and big toes, and physical and mental retardation. CBP is usually, but erroneously, lumped with p300 (adenovirus E1A-associated protein), from which it is almost indistinguishable functionally. However, mutations in the gene for p300 at 22p13 are not associated with the Rubinstein–Taybi syndrome.

Cbz *symbol for* the benzyloxycarbonyl group.

cc *symbol for* cubic centimetre (cm^3 is preferred).

CC *abbr. for* cholecalciferol (**vitamin D_3** is preferred).

CCA a codon in mRNA for L-proline.

CCA-adding enzyme a CTP/ATP:tRNA nucleotidyl transferase that builds or repairs the trinucleotide sequence CCA at the 3′ end of all tRNAs. The CCA is the site of attachment of amino acid residues for polypeptide synthesis. In the eubacterium *Aquifex aeolius* it consists of two subunits, one specific for CTP and one for ATP.

C_{55} carrier lipid *or* **C_{55} lipid carrier** *an alternative name for* **undecaprenol**.

CCC **1** a codon in mRNA for L-proline. **2** *abbr. for* *β*-chloroethyltrimethylammonium chloride; an inhibitor of gibberellin synthesis in plants.

cccDNA *see* **DNA**.

CCCP *abbr. for* carbonyl cyanide *m*-chlorophenylhydrazone, a powerful uncoupler of oxidative phosphorylation.

CCD *abbr. for* charge coupled device; an array of metal oxide semiconductor (MOS) capacitors that captures an optical image and converts it to an electronic digital form.

C cell the distinctive type of apud cell that secretes the polypeptide hormone **calcitonin**. In mammals C cells are found predominantly in the thyroid gland (when they are also known as **parafollicular cells**), and in some mammals and birds they also occur in the parathyroid gland and the thymus. In other vertebrates the cell type is present mainly in the discrete **ultimobranchial body** and the lung. [The name C cell was chosen to signify calcitonin-secreting cell.]

CCG a codon in mRNA for L-proline.

CCK *abbr. for* cholecystokinin.

CCK cell *see* **I cell**.

CCK-PZ *abbr. for* cholecystokinin–pancreozymin. *See* **cholecystokinin**.

cCMP *abbr. for* cyclic CMP.

C_1 compound *or* **one-carbon compound** *or* **single-carbon compound** any (real or hypothetical) organic compound that consists of a single carbon atom with attached hydrogen atom(s), and sometimes also an oxygen atom or imino group, and that functions as a unit in metabolism. Examples include the methyl group of *S*-adenosylmethionine or the iminomethyl-formimidoyl- (or formimino-), formyl-, hydroxymethyl-, methyl-, methylene-, and methenyl- groups of tetrahydrofolate coenzymes.

C3/C5 convertase *see* **complement**.

C5 convertase *see* **complement**.

CCP *abbr. for* Collaborative Computational Programs; an initiative, started in the UK, for the development and distribution of software for scientific applications. Programs include: CCP4 (crystallographic software), CCP5 (molecular dynamics), and CCP11 (sequence analysis).

CCU a codon in mRNA for L-proline.

C_3 cycle *an alternative name for* **reductive pentose phosphate cycle**.

C_4 cycle *an alternative name for* the **Hatch–Slack pathway**.

cd *symbol for* candela.

Cd *symbol for* cadmium.

CD *abbr. for* **1** circular dichroism. **2** cluster of differentiation *or* cluster determinant; *see* **CD marker**. **3** compact disc.

CD2 a T-cell-specific plasma membrane protein expressed early during T-cell development. It binds CD58, a PIGylated surface protein expressed on many cells, and thus facilitates adhesion of T cells to these other cells.

CD3 a **CD marker**, expressed exclusively in T lymphocytes, that consists of the γ (25 kDa), δ (20 kDa), and ε (20 kDa) polypeptides of the T-cell receptor complex. CD3 proteins are members of the immunoglobulin superfamily; each contains one transmembrane segment and an immunoreceptor tyrosine-based activation motif (ITAM). They chaperone the newly synthesized **T-cell receptor** to the cell membrane and help transduce the signal of antigen binding.

CD4 a **CD marker** that occurs on T-helper cells and is involved in MHC class II restricted interactions. It is a type I membrane glycoprotein of the immunoglobulin superfamily, acts as a receptor for HIV, and binds interleukin 16 (IL-16). Its intracellular domain binds the protein-tyrosine kinase Lck.

CD8 a **CD marker** that occurs on human cytotoxic T-cells and suppressor T-cells. It is associated with MHC class I restricted interactions. It is a heterodimer of an α and β chain and isoforms of the β chain result from alternative splicing. The α chain binds to the MHC α_3 domain. Both chains belong to the immunoglobulin protein superfamily and their intracellular domains (like those of CD4) bind Lck.

CD18 *see* **integrin**.

CD21 *see* **complement receptor**.

CD25 *see* **myelin protein**.

CD32 *or* **Fc receptor for IgG** *or* **FcγRII** a low-affinity receptor for the Fc region of antigen-bound IgG, present on B lymphocytes and other leukocytes. Its intracellular domain contains an immunoreceptor tyrosine-based inhibitory motif (ITIM), which binds a phosphoprotein phosphatase. *See* **Fc receptor**.

CD34 a **CD marker** displayed on the surface of stem cells.

CD35 *see* **complement receptor**.

CD36 *or* **platelet GPIV** *or* **CD36 activation antigen** *or* **Naka** a transmembrane multifunctional glycoprotein (88 kDa) present in platelets, endothelial cells, and many other cell types. It mediates adherence to collagen, thrombospondin, *Plasmodium falciparum*-infested erythrocytes, and oxidized low-density lipoproteins (LDL). About 3% of the apparently healthy Japanese population lacks this antigen (i.e. are Naka-negative) and have no problems with hemostasis.

CD38 *or* **T10** *or* **ADP-ribosyl cyclase/cyclic ADP-ribose hydrolase** a cell surface leukocyte antigen that catalyses multiple reactions, including NAD glycohydrolase, ADP-ribosyl cyclase, cyclic ADP ribose hydrolase, and base-exchange activities. Two of the reaction products, cyclic ADP-ribose and nicotinic acid adenine dinucleotide phosphate, are calcium messengers in a variety of cells. CD38 is a positive and negative regulator of cell activation and proliferation, depending on the cellular environment. It is involved in adhesion between human lymphocytes and endothelial cells.

CD40 a **CD marker** present on the plasma membrane of B lymphocytes and other cells including epithelial and endothelial cells. It is the receptor for **CD40L**, which is expressed on activated T lymphocytes. Binding of CD40L to CD40 induces growth, differentiation, activation, and immunoglobulin class switching of the CD40 cells.

CD44 *other names*: phagocyte glycoprotein I; lymph node homing receptor; HERMES antigen; extracellular matrix receptor III. A transmembrane glycoprotein (85–90 kDa) that is constitutively expressed on the surface of B and T cells, monocytes, neutrophils, epithelial cells, fibroblasts, glial cells, and myocytes. It plays a general role in cell adhesion, including lymphocyte homing; it binds to collagen and hyaluronate. Several splicing variants seem to be expressed preferentially in gastric tumour cells.

CD45 a **CD marker** present on T lymphocytes. It is the receptor for the membrane protein CD22, present in B lymphocytes. Binding of the ligand activates the protein tyrosine kinases Fyn and Lck.

CD55 *see* **complement decay-accelerating factor**.

CD58 *see* **CD2.**

CD59 a GPI-anchored glycoprotein that is expressed in erythrocytes, leukocytes, and endothelial cells, and is a potent inhibitor of complement membrane attack complex (MAC); it acts after C5b8 assembly (*see* **complement**). It is involved in signal transduction for T-cell activation, being complexed to a protein tyrosine kinase. It is a member of a protein family that includes the protooncogenes *Sis* and *Myc*. Mutation in the gene at 11p13 produces a CD59 deficiency that is manifest as paroxysmal nocturnal hemoglobinuria.

CD62 *see* **selectin**.

CD66 *see* **carcinoembryonic antigen**.

CD74 *an alternative name for* **invariant chain**.

CD79 *see* **B cell antigen receptor complex associated protein**.

CD95 *an alternative term for* **Fas**.

CD105 *see* **endoglin**.

CD2AP *abbr. for* CD2-associated protein; an SH3 domain protein present mainly in epithelial and lymphoid cells that is implicated in endocytosis and lysosomal sorting. Mutations in humans result in focal segmental glomerulosclerosis; mutations in mice lead to early death from massive proteinuria.

CD11b/18 *see* **complement receptor**.

CD11c/18 *see* **complement receptor**.

Cdc-activating kinase *abbr.*: CAK; a heterodimer of cyclin H and Cdk7. It is a protein serine/threonine kinase and a component of human transcription factor TFIIH. Among its substrates are Cdk subunits and the C-terminal domain of RNA polymerase II.

***cdc* gene** *abbr. for* cell-division-cycle gene. Many genes encode proteins essential for cell division. These were initially identified in yeast, and named in a series *cdc1*, *cdc2*, etc. Homologues of these genes have since been found in many other species, but the *cdc* nomenclature is used specifically for the fission yeast, *Schizosaccharomyces pombe*. The convention Cdc followed by a numeral is used for the protein products of these genes. Many of these products are not directly involved in the control of cell division, being proteins such as DNA polymerases. Some of those involved in cell-division control are detailed below.

Cdc2, a major cell regulatory protein, with counterparts in all eukaryotic cells. *cdc2* is homologous to *CDC28* in budding yeast. Cdc2 is a Ser/Thr protein kinase, alternatively denoted p34^{cdc2}, and regulated by cyclin B. p34^{cdc2} and cyclin B comprise **maturation promoting factor** (MPF). Cdc2 is the patriarch of a family of cyclin-dependent kinases; Cdc2 is Cdk1. Cdc2 is important at the G_1/S and G_2/M phases of the cycle in yeast. The human homologue of Cdc2 phosphorylates retinoblastoma protein.

cdc25 encodes a protein phosphatase that positively regulates p34^{cdc2} by dephosphorylation of Tyr^{15}. Entry to mitosis is negatively regulated by ***wee1***, a gene in *S. pombe* that encodes a protein tyrosine kinase. Its action on mitosis results from phosphorylation of Tyr^{15} of p34^{cdc2}. Note: *CDC25* from budding yeast encodes a guanine nucleotide exchange protein.

Cdc28, a Ser/Thr protein kinase required for completion of both the START transition of the cycle and also the G_2/M transition.

Cdc31, an **EF-hand** protein involved in microtubular organization.

Cdc46, a protein mobilized from the cytoplasm to the nucleus after mitosis, and a potential ATP-binding protein.

Cdc48, a putative ATP-binding protein involved in spindle formation.

Cdc42 a human homologue of a yeast protein, and a member of the Rho family of p21 GTPases. It is activated by several proteins including FGD1, which is a guanine nucleotide exchange protein. Cdc42 interacts with various protein kinases including WASP, **MRCK**, and PAK.

Cdc48 *or* **VCP/Cdc48** a hexameric AAA protein complex of yeast that is involved in endoplasmic reticulum (ER)-associated protein degradation and copurifies with 26S proteasomes. It interacts with proteasomes and with polyubiquitin chains of proteins targeted for degradation. The human homologue is VCP (valosin-containing protein).

Cdc53p *see* **cullin**.

CD66d *see* **carcinoembryonic antigen**.

CDD *abbr. for* conserved domain database; *see* **derived database**.

CD66e *see* **carcinoembryonic antigen**.

CDE *abbr. for* centromere DNA element; CDE-I is a group of DNA sequences, RTCACRTG, found in centromeres and some promoters. *See also* **centromere-binding proteins**.

CD59 glycoprotein precursor *see* **membrane attack complex inhibition factor**.

CDH *abbr. for* ceramide dihexoside (Cer(Hex)$_2$ is preferred).

c-di-GMP *abbr. for* cyclic diguanylic acid.

CDI *abbr. for N*,*N′*-carbonyldiimidazole; 1,1′-carbonylbis-1*H*-imidazole, a reagent used in the synthesis of nucleotide triphosphates and peptides, and for cross-linking proteins.

Cdk *abbr. for* cyclin-dependent protein kinase.

Cdk inhibitor *abbr.*: CKI; a protein that binds directly to, and inhibits, **Cdk** activity. In yeast some CKIs are inducible, whereas others are intrinsic to the mitotic cycle. In mammalian cells, one type (comprising p21, p27, and p57) inhibit most Cdks, whereas another type (called INK4 proteins) are specific for Cdk4 and Cdk6. Inactivating mutations in some of these CKIs are found in some human neoplasms.

CD40L *or* **CD154** *or* **gp39** *or* **TNFSF5** a type II transmembrane protein of the tumour necrosis factor (TNF) superfamily that is expressed in activated T lymphocytes. It is the ligand for **CD40** present on B lymphocytes and certain other cells. The gene for CD40L on Xq26 encodes a protein of 261 amino acids. Over a hundred mutations, of various types, cause X-linked hyper-IgM syndrome.

CD95 ligand *an alternative term for* **FasL**.

CD marker *(in immunology)* any of a series of antigenically distinct molecules occurring on the surface of leukocytes and other cell types, and used in the characterization of such cells. More than 80 individual CD marker molecules are recognized, as identified by **monoclonal antibodies**. The most frequently encountered CD molecules are those used to distinguish T cells. CD2 is present on all T cells and is involved in antigen-nonspecific activation. CD3 is also present on all T cells and is an invariant part of the T-cell antigen receptor involved in antigen-specific T-cell activation. **CD4** occurs on T-helper cells and is involved in MHC class II restricted interactions, **CD8** occurs on cytotoxic T cells and is involved in MHC class I restricted interactions. *See also* **CD44**, **CD59**. Other CD markers listed here under other names include CD16 (*see* **Fc receptor**), CD29 (*see* **VLA**), CD31 (*see* **PECAM**), CD32 (*see* **Fc receptor**), CD49a and CD51 (*see* **VLA**), CD50 and CD54 (*see* **ICAM**), CD62 (*see* **selectin**), CD64 (*see* **Fc receptor**), CD102 (*see* **ICAM**), and CD106 (*see* **VCAM**). [From 'cluster of differentiation'.]

cDNA *abbr. for* complementary DNA.

C-DNA *abbr. for* C form of DNA.

cDNA clone any bacterial cell transformed by a plasmid containing a **complementary DNA** copy of an RNA molecule.

cDNA library a collection of cloned recombinant cDNA, usually in bacteria or yeast. The clones represent cDNAs prepared from all the mRNAs in any particular species or organ.

CDP *abbr. for* **1** cytidine 5′-diphosphate *or* the group cytidine(5′)-diphospho. **2** cardiodilatin related peptide; *see* **natriuretic peptide**.

CDPcholine *see* **cytidine(5′)diphosphocholine**.

CDPdiacylglycerol *see* **cytidine(5′)diphosphodiacylglycerol**.

CDPdiacylglycerol–inositol 3-phosphatidyltransferase EC 2.7.8.11; *other names*: phosphatidylinositol synthase; CDPdiacylglyceride–inositol phosphatidyltransferase; an enzyme that catalyses the formation of phosphatidyl-1-D-*myo*-inositol from CDPdiacylglycerol and *myo*-inositol with release of CMP. It is a component of the pathway for the biosynthesis of phosphatidylinositol and also for its resynthesis after activation of the **phosphatidylinositol cycle**.

CDPdiacylglycerol–serine *O*-phosphatidyltransferase EC 2.7.8.8; *systematic name*: CDPdiacylglycerol:L-serine 3-*O*-phosphatidyltransferase; *other names*: phosphatidylserine synthase; CDPdiglyceride–serine *O*-phosphatidyltransferase. It is an enzyme of the pathway that effects *de novo* synthesis of phosphatidylserine. It catalyses the formation of *O*-*sn*-phosphatidyl-L-serine from CDPdiacylglycerol and L-serine with the release of CMP.

CDPethanolamine *see* **cytidine(5′)diphosphoethanolamine**.

CDP-glycerol pyrophosphorylase *see* **glycerol-3-phosphate cytidylyltransferase**.

CDPK *abbr. for* calmodulin-like domain protein kinase.

CDP-*Star* a proprietary chemilumigenic 1,2-dioxetane substrate for alkaline phosphatase giving a brighter signal than **AMPPD**.

CDR *abbr. for* calcium-dependent regulator protein (i.e. **calmodulin**).

CDS *abbr. for* coding sequence; *see* **coding region**.

CDTA *abbr. for trans*-cyclohexylene-1,2-diamine-*N*,*N*,*N*′,*N*′-tetraacetate, the anion of *trans*-1,2-diaminocyclohexane-*N*,*N*,*N*′,*N*′-tetraacetic acid. A **chelating agent** with a high affinity for Mg^{2+}; the abbreviation is also used for its partially or fully protonated forms.

Ce *symbol for* cerium.

C_xE_y a series of non-ionic detergents useful for the solubilization of membrane-bound proteins in their native state. They include $C_{10}E_6$, hexaethyleneglycol mono-*n*-decyl ether; $C_{10}E_8$, octaethyleneglycol mono-*n*-decyl ether; $C_{12}E_6$, hexaethyleneglycol mono-*n*-dodecyl ether; $C_{12}E_8$ octaethyleneglycol mono-*n*-dodecyl ether; and $C_{12}E_9$, nonaethyleneglycol mono-*n*-dodecyl ether; the latter two are constituents of the proprietary detergent Lubrol-PX, a detergent useful for the solubilization of membrane-bound proteins in their native state.

CEA *abbr. for* carcinoembryonic antigen.

CEA gene member 1 *see* **carcinoembryonic antigen**.

cecropin any of a group of small, basic polypeptides with potent antibacterial activity. Cecropins are active against *Escherichia coli* and several other Gram-negative species, and are isolated from the cecropia moth, *Hyalophora cecropia*, and several other insects.

CEF10 *or* **CEF-10** a secreted protein that is implicated in growth regulation. It is induced by v-*src*, and belongs to a family of growth regulators that includes **connective tissue growth factor**.

Cek a chick gene encoding receptor-type protein tyrosine kinases, and named from chicken embryo kinase. The protein product Cek-1 is the chicken **fibroblast growth factor** receptor; Cek-2 and Cek-3 are related to ***Bek***; Cek-4 and Cek-5 are homologous to ***Eph***.

Celebrex a drug that inhibits the enzyme **COX-2** (see **prostaglandin-endoperoxide synthase**) and hence is used in the treatment of arthritis. The active ingredient is celecoxib, 4-[-5-(4-methylpentyl)-3-trifluoromethyl-1*H*-pyrazol-1-yl]benzenesulfonamide.

celiac *or (esp. Brit.)* **coeliac** of, or belonging to, the abdominal cavity.

celiac disease *or (Brit.)* **coeliac disease** *or* **gluten enteropathy** *or* **nontropical sprue** a condition caused in genetically susceptible individuals by damage to the mucosa of the upper small intestine triggered by the α-gliadin component of **gluten** in wheat and rye. α-Gliadin is rich in glutamine residues, and the condition is marked by the presence of circulating antibodies to tissue transglutaminase. This enzyme, normally in inactive form in submucosal cells of the upper small intestine, is released by mechanical or inflammatory stress. The enzyme deamidates specific glutamine residues in peptides derived from α-gliadin thus producing peptides that activate the T cells of the submucosa. The disease is characterized by diarrhoea and malabsorption, but can be relieved by elimination of gluten from the diet.

Celite *proprietary name for* preparations of amorphous diatomaceous silica, used as a filter-aid and in partition chromatography.

cell 1 the basic structural unit of all living organisms; it typically comprises a small, usually microscopic, discrete mass of organelle-containing cytoplasm, bounded externally by a membrane. Each cell is capable of interacting with other cells and performing all the fundamental functions of life. In plants the cell usually also includes the cell wall. Originally the term referred to the bounding wall of a plant cell that had lost its living content. *See also* **+cyte**, **cyto+**. **2** a container for liquid during measurement or separation procedures, such as dialysis, electric conductivity measurement, electrolysis, microdiffusion, moving boundary electrophoresis, analytical ultracentrifugation, ultrafiltration, and (spectro)photometry; *see also* **cuvette**. **3** or **electric cell** a device for producing electric current by converting chemical energy into electric energy; it consists of two electrodes in contact with an electrolyte. **4** *(in crystallography) see* **unit cell**. **—cellular** *adj.*

cell-adhesion molecule *see* **adhesion molecules**.

cell body *an alternative term for* **perikaryon**.

cell-bound antibody *or* **cell-fixed antibody** any antibody molecule that is bound to the surface of a cell, e.g. an **incomplete antibody** (def. 1) or a **cytophilic antibody**.

cell coat *another name for* the **glycocalyx**.

cell cortex the part of the microtrabecular lattice lying just under the outer cell membrane of certain protozoans, e.g. paramecia.

cell counter any device for determining the number of cells in a known volume of a liquid suspension. *See* **Coulter counter**, **flow cytometer**, **hemocytometer**.

cell culture *see* **tissue culture**.

cell cycle the period between the formation of a cell by division of its mother cell and the time when the cell itself divides to form two daughter cells. *See also* **cell-division cycle**, **DNA cycle**.

cell-cycle engine all the biochemical components, and the reactions between them, that cause the periodic activation and inactivation of **M-phase-promoting factor** during cell maturation.

cell differentiation *see* **differentiation**.

cell-division cycle the pattern of DNA synthesis in dividing eukaryotic cells. It is divided into four periods: G_1 is the first ‘gap’ in DNA synthesis between **telophase** and the period of DNA synthesis, designated S. This S phase is followed by G_2, the second gap in DNA synthesis. This runs on into the period of **mitosis**, M, which lasts from early **prophase** to late **telophase**.

cell division protein kinase *abbr.*: CDK; any of various protein kinase enzymes involved in the regulation of **cyclin** activity, such as CDC20. *See also* ***cdc***.

cell-fixed antibody *an alternative name for* **cell-bound antibody**.

cell fractionation the fractionation of disrupted cells into their subcellular components.

cell-free extract a fluid, made by breaking open cells, that contains most of the constituents of the cells in question but no intact cells.

cell-free system any experimental system composed of subcellular fractions and/or cell-free extracts. Cell-free systems for amino-acid incorporation (protein synthesis) generally contain ribosomes, natural or synthetic mRNA, tRNAs, enzymes, amino acids, an ATP generating system, GTP, buffer, certain inorganic salts, and some organic compounds.

cell fusion the formation of a single hybrid cell containing the nuclei and cytoplasms from different cells. It may be induced by treatment of a mixed cell population with certain **fusogens** (e.g. killed Sendai virus or polyethylene glycol). It is an important step in the technique of forming **hybridoma cells** for the production of **monoclonal antibodies**.

cell junction a specialized region of connection between two cells or between a cell and the extracellular matrix. *See also* **desmosome**, **gap junction**, **hemidesmosome**, **tight junction**.

cell line a population of cells cultured *in vitro* that are descended through one or more generations (and possibly subcultures) from a single primary culture. The cells of such a population share common characteristics.

cell locomotion *see* **cell migration**.

cell matrix *see* **extracellular matrix**.

cell-mediated immunity specific immunity that depends on the presence of T lymphocytes. It is responsible for, e.g., allograft rejection, delayed hypersensitivity, and tuberculin test reactions, and is important in the organism’s defence against viral and some bacterial infections.

cell membrane any **membrane** found in a cell. The term is sometimes used loosely to indicate the **plasma membrane**. *See also* **cytoplasmic membrane**.

cell migration the active movement of a cell from one location to another, particularly the migration of a cell over a surface.

***β*-cellobiase** *another name for β*-glucosidase; *see* **glucosidase**.

cellobiose 4-*O*-*β*-D-glucopyranosyl-D-glucose; a disaccharide that represents the basic repeating unit of **cellulose**; it is liberated by **cellulase**.



α-anomer

cellobiuronic acid 4-*O*-*β*-D-glucopyranuronosyl-D-glucose; *condensed form*: GlcA(*β*1-4)Glc. It is a component of, e.g., type III pneumococcal bacterial capsule polysaccharides.



α-anomer

cellodextrin a glucan chain linked to **sitosterol**. It is formed by the transglucosylase components of cellulose synthase in plant cell plasma membranes, by transfer of the glucosyl moiety of UPD-glucose onto the sitosterol β-glucoside primer. The glucan is released by Korrigan cellulase to form the microfibrils of cellulose and to regenerate the sitosterol β-glucoside primer.

cellophane a form of transparent, flexible sheeting made from regenerated **cellulose**; originally a proprietary name.

Cellosolve *proprietary name for* a range of ethanediol monoalkyl ethers, especially 2-ethoxyethanol. They are useful as solvents, e.g. in liquid scintillation mixtures, to facilitate the dispersion of aqueous samples in organic solvents.

cellotetraose a tetrasaccharide composed of D-glucose units in *β*1-4 linkage.

cellotriose the trisaccharide *O*-*β*-D-glucopyranosyl-(1-4)-*O*-*β*-D-glucopyranosyl-(1-4)-D-glucose; *condensed form*: Glc(*β*1-4)Glc(*β*1-4)Glc.



β-D-pyranose form

cell plate the nascent cell membrane and cell wall structure that forms between the two daughter nuclei near the centre of a dividing plant cell. It develops at the equatorial region of the **phragmoplast**. It grows outwards to join with the lateral walls and form two daughter cells.

cell sorter any **flow sorter** for sorting cells in liquid suspension, on the basis of some characteristic that is detectable by the sorter.

cell-surface protein *abbr.*: CSP; *an alternative name for* **fibronectin**.

cellubrevin a **synaptobrevin** homologue that is involved in membrane traffic as part of a constitutively recycling pathway. With VAMP proteins, it is a component of the machinery controlling docking and fusion of secretory vesicles with their target membrane. It is a ubiquitous substrate for **tetanus toxin** light chain.

cellugyrin *see* **gyrin**.

cellular affinity the tendency of cells to adhere specifically to cells of the same type, but not to cells of a different type. This property is lost in cancer cells.

cellular immunity **1** the increased ability of phagocytic cells to destroy parasitic organisms, i.e. macrophage immunity. **2** *an alternative name for* **cell-mediated immunity**.

cellulase **1** EC 3.2.1.4; *other names*: endoglucanase; endo-1,4-*β*-glucanase; carboxymethyl cellulase. An enzyme that catalyses the endohydrolysis of 1,4-*β*-D-glucosidic linkages in **cellulose**, thereby hydrolysing cellulose to cellobiose. It causes abscission in plants, and its synthesis is stimulated by ethylene. Microbial cellulases play an important part in the digestion of cellulose by ruminants. **2** any lytic enzyme whose substrate is cellulose. *See* **cellulose 1,4-*β*-cellobiosidase**, **glucosidase**, **Korrigan cellulase**.

cellule **1** (*archaic*) a minute cavity or very small **cell**. **2** *a former name for* a **liposome** bounded by a single lipid bilayer.

cellulose a linear *β*1-4 **glucan** of molecular mass 50–400 kDa with the pyranose units in the **-$^4C_1$** conformation. It is predominantly a plant polysaccharide though it also occurs in some tunicates. Cellulose microfibrils are major components of plant cell walls. Cellulose is insoluble in water but will dissolve in ammoniacal solutions of cupric salts. It is often said to be the most abundant organic compound in the biosphere, but this distinction has also been accorded to the **hopanoids**.

cellulose 1,4-*β*-cellobiosidase EC 3.2.1.91; *other names*: exoglucanase; exocellobiohydrolase; 1,4-*β*-cellobiohydrolase. An enzyme that catalyses the hydrolysis of 1,4-*β*-D-glucosidic linkages in cellulose and cellotetraose, releasing cellobiose from the nonreducing ends of the chains.

cellulose synthase an enzyme complex present in plant cell plasma membranes that synthesizes cellodextrin by transfer of glucose from UDP-glucose to a sitosterol *β*-glucoside primer. The primer is first synthesized by a component of the complex by transfer of glucose from UDP-glucose to **sitosterol**. The elongating transglucosylation reactions are catalysed by several subunits that surround the primer synthase. Cleavage of the cellodextrin from the sitosterol *β*-glucoside primer is achieved by **Korrigan cellulase**, itself a component of the complex.

cellulosic **1** of, or pertaining to, cellulose; of the nature of cellulose; composed (primarily) of cellulose; derived from or made by chemical modification of cellulose. **2** a substance made from cellulose or a derivative of cellulose.

cellulolysis the process of hydrolysing cellulose. —**cellulolytic** *adj.*

cell wall the rigid or semi-rigid envelope lying outside the **cell membrane** of plant, fungal, and most prokaryotic cells maintaining their shape and protecting them from osmotic lysis. In prokaryotes it lies inside any capsule and slime layer, usually consists mainly of **peptidoglycan**, and can be removed by various techniques with retention of its three-dimensional form. In fungi the cell wall is composed largely of polysaccharides, while in plants it is made up of cellulose and, often, lignin.

Celsius temperature *symbol*: *θ or t*; a temperature defined as the excess of the thermodynamic temperature, *T*, over 273.15 K; i.e. $\theta = T - 273.15$, where *θ* is measured in °C (i.e. **degrees Celsius**, formerly called degrees centigrade) and *T* is measured in **kelvins**. It is identical with centigrade temperature. [After Anders Celsius (1701–44), Swedish astronomer.]

cenancestor the common ancestor of all living things.

CENP-A *abbr. for* centromere protein-A; a member of the histone H3 family of proteins. In mammalian cells it replaces histone H3 in the histone octamers of nucleosomes of **centromeres**.

centi+ *symbol*: c; SI prefix denoting 10^{-2}.

centigrade temperature *former name for* **Celsius temperature**.

centimetre–gram–second system *see* **cgs system**.

centimorgan *or* **centiMorgan** *abbr.*: cM; a unit of **map distance** used in genetic mapping, equal to 1% crossover found in recombination studies; 1 cM equals 1 map unit. Hence, if two genes are separated by 1 cM, there is a 1% probability of recombination in a single meiotic event.

central dogma a fundamental principle of molecular biology, first articulated by British molecular biologist Francis **Crick** (1916–) in 1958. He wrote that the central dogma states that once 'information' has passed into protein *it cannot get out again*. In more detail, the transfer of information from nucleic acid to nucleic acid, or from nucleic acid to protein may be possible, but transfer from protein to protein, or from protein to nucleic acid is impossible. Information means here the *precise* determination of sequence, either of bases in the nucleic acid or of amino-acid residues in the protein. The dogma has been taken to relate primarily to the following transfers of information that can occur in all cells: DNA → DNA, DNA → RNA, and RNA → protein. However, the transfer of information from RNA to RNA occurs in the replication of RNA viruses. The transfer of information from RNA to DNA occurs following infection of a cell with a retrovirus; the DNA is then incorporated into the host genome. When challenged that the reverse transfer of information from RNA to DNA by retroviruses contradicted the dogma, Crick refuted the challenge by drawing attention to the fact that as originally formulated the dogma permitted the transfer of information from (any) nucleic acid to (any other) nucleic acid (although the action of retroviruses was not known at that time) and that the essential point was that *sequence* information could not be passed from protein to nucleic acid, or from protein to protein.

central nervous system *abbr.*: CNS; the part of the nervous system of an animal that contains a high concentration of cell bodies and synapses and is the main site of integration of nervous activity. In higher animals it is isolated from the circulation by the **blood–brain barrier**. It consists essentially of a brain or cerebral ganglia, and a nerve cord, which may be dorsal or ventral, single or double. *Compare* **peripheral nervous system**.

centrifugal 1 moving, acting, or tending to act away from a centre or axis. **2** of, pertaining to, or operated by a **centrifugal force**. **3** *(in botany)* developing outwards from a centre, as the flowers of certain types of inflorescence. **4** *(in physiology)* sending nerve impulses from a central location to parts supplied by that nerve; **efferent**. *Compare* **centripetal**.

centrifugal analyser *or* **centrifugal fast analyser** an apparatus widely used in clinical chemical laboratories for the simultaneous and very rapid chemical, biochemical, or immunochemical determination of one particular constituent in each of a large number of samples. Basically it consists of an appropriately designed transfer disk into which reagent(s) and samples are discretely and automatically pipetted. When loaded, the transfer disk is placed in the centre of a cuvette rotor in the centrifuge, and the rotor is accelerated. Reagent(s) and each sample are mixed together as they are radially propelled along specially shaped channels into the cuvettes. Absorbance, fluorescence, or other measurements are then made automatically on the cuvettes as they are rotating. The whole process, including data handling, is controlled by a computer.

centrifugal elutriation a technique in which cells or other particles are separated by **elutriation** in a specially constructed centrifuge rotor; the increased gravitational field resulting from centrifugation speeds up separation of the particles.

centrifugal field any space in which a **centrifugal force** is operating, as in the spinning rotor of a centrifuge.

centrifugal force a force acting radially outwards on any body moving in a curved path, equal and opposite to the **centripetal force**. The centrifugal force on a body of mass m, moving in a circular path of radius r, with velocity v, is: mv^2/r.

centrifuge 1 an apparatus in which fluids may be rotated rapidly so that substances (solutes or dispersed particles) of different densities may be separated by centrifugal force. **2** to rotate rapidly in a centrifuge. **—centrifugation** *n.*

centrin *an alternative name for* **caltractin**.

centriole a cellular organelle, found close to the nucleus in many eukaryotic cells, consisting of a small cylinder with microtubular walls, 300–500 nm long and 120–150 nm in diameter. It contains nine short, parallel, peripheral microtubular fibrils, each fibril consisting of one complete **microtubule** fused to two incomplete microtubules. Cells usually have two centrioles, lying at right angles to each other. At division, each pair of centrioles generates another pair and the twin pairs form the poles of the mitotic spindle. *Compare* **basal body**.

centripetal 1 moving, acting, or tending to act towards a centre or axis. **2** of, pertaining to, or operated by a **centripetal force**. **3** *(in botany)* developing inwards from the outside, as the flowers of certain inflorescences. **4** *(in physiology)* sending nerve impulses towards a central location from peripheral parts supplied by that nerve; **afferent**. *Compare* **centrifugal**.

centripetal force a force acting radially inwards on any body moving in a curved path; it constrains the body to a curved path. It is equal and opposite to the **centrifugal force**.

centromere the region of a eukaryotic chromosome that is attached to the spindle during nuclear division. It is defined genetically as the region of the chromosome that always segregates at the first division of meiosis; i.e. the region of the chromosome in which no **crossing over** occurs. At the start of M phase, each chromosome consists of two sister chromatids with a constriction at a point that forms the centromere. During late prophase two **kinetochores** assemble on each centromere, one kinetochore on each sister chromatid. The DNA of centromeres is several megabase long and consists of tandem arrays of repetitive sequences (sometimes called alphoid DNA) with high affinity for specific nuclear proteins (e.g. **CENP-A**). In the human genome such repetitive sequences amount to ≈10% of total DNA.

centromere-binding proteins proteins from, e.g., the yeast **kinetochore** that are able to bind centromere DNA; examples from yeast: centromere-binding protein 1, a helix-turn-helix protein that binds to a conserved DNA sequence termed CDE-I, and is involved in chromosome segregation; centromere-binding protein 5, which is involved in mitotic chromosome segregation, and is essential for cell growth.

centrosome a structure occurring close to the nucleus during **interphase** in many eukaryotic cells. It comprises a pair of **centrioles**, satellite bodies, and a cytoplasmic zone from which the mitotic microtubule spindle is organized. The structure of the centrosome in animal cells changes continually during the **cell-division cycle**. The protein PCM-1 recruits centrosomal proteins such as centrin, pericentrin, ninein, and dynactin. On phosphorylation by Cdk2, the centrosomal nucleophosmin is released to initiate centrosomal duplication. In some cells, lack of p53 leads to multiple copies of the centrosome being generated during a single cell cycle.

centrosphere a more or less well-delineated part of the cytoplasm at the poles of the spindle (*see* **mitotic spindle**).

cephaeline an alkaloid derived from *Uragoga ipecacuanha*. It is a gastric irritant, inducing emesis. See also **emetine**, **ipecachuanha**.

cephalin *a former name for* **1 phosphatidylethanolamine**. **2 phosphatidylserine**.

cephalosporin any of a heterogeneous group of natural and semisynthetic, often *β*-lactam, antibiotics. Cephalosporins C, N, and P are obtained from cultures of moulds such as *Cephalosporium acremonium*. Cephalosporins are active against a range of Gram-positive and Gram-negative bacteria.

cephalosporinase *an alternative name for* ***β*-lactamase** II.

Cer *symbol for* a ceramide residue. *See also* **Cer(Hex)**.

ceramidase EC 3.5.1.23; *other name*: acylsphingosine deacylase; an enzyme involved in the degradation of sphingolipids. It catalyses the hydrolysis of *N*-acylsphingosine to a fatty acid and sphingosine.

ceramide *symbol*: Cer; any *N*-acylated **sphingoid**. Ceramide is released from sphingomyelin by sphingomyelinase (sphingomyelin phosphodiesterase). Activation of neutral sphingomyelinase (e.g. by tumour necrosis factor, FasL, cannabinoids, interleukin 1) releases ceramide, which activates several serine/threonine protein kinases, a serine/threonine phosphoprotein phosphatase, and other targets that influence apoptosis and the cell cycle. Membranes of the Golgi apparatus may also participate in ceramide signalling.

ceramide cholinephosphotransferase EC 2.7.8.3; an enzyme involved in the biosynthesis of sphingomyelin by the reaction of CDPcholine with *N*-acylsphingosine with the release of CMP.

ceramide glucosyltransferase EC 2.4.1.80; an enzyme that catalyses the formation of glucosylceramides. The reaction involves the formation of D-glucosyl-*N*-acylsphingosine from UDPglucose and *N*-acylsphingosine with the release of UDP.

cercidosome an atypical mitochondrion or oxidizing body, found, e.g., in trypanosomes, whose function may primarily be to regulate the NAD^+/NADH ratio of the cytosol. [From Greek *kerkis, kerkido*, weaver's shuttle, + **+some**.]

cerebellin *see* **precerebellin**.

cerebral 1 of, or relating to, the cerebrum. **2** *(loosely)* of, or relating to the brain.

cerebrodiene a lipid, resembling **sphingosine**, that is obtained from the brain of sleep-deprived cats.

cerebroglycan an integral membrane heparan sulfate proteoglycan unique to the developing nervous system, and expressed specifically during neuronal differentiation.

cerebronate 2-hydroxytetracosanoate; $CH_3(CH_2)_{21}CH(OH)COO^-$; the 2-hydroxy derivative of lignocerate. It is enriched in brain cerebrosides, the fraction containing this fatty acid being known as **phrenosin**.

cerebrose *see* **galactose**.

cerebroside any **glycosphingolipid** that contains a monosaccharide, normally glucose or galactose, in 1-*O*-*β*-glycosidic linkage with the primary alcohol of an *N*-acyl **sphingoid** (ceramide). In plants the monosaccharide is normally glucose; in animals it is normally galactose, though this may vary with the tissue, glucose being present in blood cerebroside. In plants, the sphingoid is usually phytosphingosine, in animals sphingosine or dihydrosphingosine (sphinganine). Cerebrosides frequently contain large amounts of longer-chain fatty acids such as behenic (22:0), lignoceric (24:0), and nervonic (24:1) acids, and 2-hydroxy fatty acids such as cerebronic (α-OH24:0) and 2-hydroxynervonic acids. Cerebroside synthesis may proceed either by acylation of psychosine or transfer of glucose or galactose to ceramide.

cerebroside-sulfatase EC 3.1.6.8; *other name*: arylsulfatase A; an enzyme involved in the catabolism of sulfatides. It catalyses the hydrolysis of a cerebroside 3-sulfate to a cerebroside and sulfate. It is a lysosomal enzyme of most tissues, active at acid pH, whose catalytic activity requires the noncatalytic activator protein saposin B. A formylglycinyl residue (formed by modification of a cysteinyl residue) is present in the active site. Over 60 mutations of the gene locus at 22q13.31-qter are associated with metachromatic leukodystrophy.

cerebrospinal fluid *abbr.*:CSF; a clear fluid, containing little protein and few cells, that fills the subarachnoid space and ventricles of the brain, and the central canal of the spinal cord. About 80% of the protein is derived from plasma, the rest is brain-specific and includes myelin basic protein, glial fibrillary acid protein, creatine kinase (BB isozyme), and neuronal enolase.

cerebrotendinous xanthomatosis a rare familial sterol storage disease caused by mutations that lead to deficiency of sterol 27-monooxygenase. There is accumulation of cholestanol and cholesterol in most tissues (but particularly in cerebellum, bile, and xanthomas), and of cholestanol, but not usually of cholesterol, in plasma. Clinical features include neurological dysfunction (cerebellar ataxia, dementia), xanthomas, early atherosclerosis, and cataracts.

Cerenkov counter *a variant spelling of* **Cherenkov counter**.

Cerenkov radiation *a variant spelling of* **Cherenkov radiation**.

Cer(Hex) *symbol for* ceramide monohexoside. The di- and trihexosides are symbolized by $Cer(Hex)_2$ and $Cer(Hex)_3$ respectively. *See also* **Cer**.

cerinic acid *see* **cerotoyl**.

ceroid an autofluorescent, insoluble lipopigment that accumulates in the livers of rats with nutritional cirrhosis. It is present in atherosclerotic plaques and builds up in lysosomes of neurons and other tissue cells in the ceroid lipofuscinoses.

ceroid lipofuscinosis (neuronal) *abbr.*: CLN; any of several progressive myoclonic epilepsies characterized by accumulation of **ceroid** in the lysosomes of neurons and other cell types. The diseases are distinguished largely by their age of onset and the mutated (loss-of-function) gene involved. **CLN1** is an infantile form caused by deficiency of palmitoylprotein thioesterase. **CLN2** is a late infantile form caused by deficiency of lysosomal tripeptidyl peptidase I. **CLN3** is a juvenile form caused by loss of the lysosomal transmembrane protein **battenin**. In **CLN5** and **CLN8** the function of the gene involved is unknown.

cerotoyl *symbol*: Crt; *the trivial name for* hexacosanoyl, $CH_3–[CH_2]_{24}CO–$, the univalent acyl group derived from hexacosanoic acid (*also called* **certoic acid** *or (formerly)* **cerinic acid**), a saturated, unbranched, acyclic, aliphatic acid, which occurs naturally in wool fat.

certoic acid *see* **cerotoyl**.

cerulein *or (Brit.)* **caerulein** a decapeptide, pGlu-Gln-Asp-Tyr(SO_3H)-Thr-Gly-Trp-Met-Asp-PheNH_2, isolated from the skin of various frogs, e.g. *Hyla caerulea*. It is often accompanied by the nonapeptide **phyllocerulein** (*or* **phyllocaerulein**). Both have the same C-terminal pentapeptide amide sequence as porcine **cholecystokinin**. Cerulein-like peptides have been isolated from the antrum and small intestine of amphibians, in which they stimulate strongly the secretion of gastric acid.

cerulenin (2*R*,3*S*)-epoxy-4-oxo-7*E*,10*E*-dodecadienamide; an antifungal antibiotic isolated from *Cephalosporium caerulens* and other sources. It inhibits fatty-acid biosynthesis by binding with 3-oxoacyl-[acyl carrier protein] synthase (*see* **fatty acid synthase complex**) and also interferes with sterol biosynthesis by inhibiting **hydroxymethylglutaryl-CoA synthase** activity.

cerulin *a variant spelling of* **cerulein**.

ceruloplasmin *or (Brit.)* **caeruloplasmin** a bright-blue, copper-containing protein found in blood plasma. It has ferroxidase activity, EC 1.16.3.1, and catalyses the reaction:

$$4\ \text{iron(II)} + 4\ H^+ + O_2 = 4\ \text{iron(III)} + 2\ H_2O$$

It binds six or seven Cu^{2+} ions per molecule. It is important in iron metabolism, and is abnormally low in hepatolenticular degeneration (Wilson's disease). It is an acute phase protein, its level rising late in the acute phase.

ceryl *the common name for* hexacosyl, $CH_3–[CH_2]_{24}–CH_2–$, a saturated, unbranched, acyclic, alkyl group.

cesium chloride *or (esp. Brit.)* **caesium chloride** a salt that forms dense solutions in water and so is used in **isopycnic centrifugation** to separate DNA molecules of different densities.

Cet *symbol for* the carboxyethyl group, $–CH_2–CH_2–COOH$.

cetaceum *an alternative term for* **spermaceti**.

Cetavlon *a proprietary name for* **cetrimide**.

cetoleic acid *see* **docosenoic acid**.

CETP *abbr. for* cholesteryl ester transfer protein; a hydrophobic glycoprotein of plasma, secreted mainly from liver and associated largely with high-density lipoproteins (HDL). It effects the exchange of cholesteryl esters from HDL with triglyceride from chylomicrons and very-low density lipoproteins (VLDL), and is responsible for about half of the plasma phospholipid exchange. The gene locus at 16q21 encodes a protein (476 residues) with sequence homology to **BPI protein**, PLTP (phospholipid transfer protein), and LPS-binding protein. Deficiency of CETP is associated mostly with a splice junction or missense mutation, and is common in Japan. Heterozygotes have a modest increase, and homozygotes a massive increase, in HDL cholesterol content. Several missense mutations are also associated with increased HDL levels.

cetrimide *or* **cetrimidum** a detergent disinfectant consisting of a mixture of alkylammonium bromides, principally **cetyltrimethylammonium bromide**. *See* **quaternary ammonium compounds**.

cetyl *or* **palmityl** *the common name for* hexadecyl, $CH_3–[CH_2]_{14}–CH_2–$, a saturated, unbranched, acyclic, alkyl group (hexadecyl is preferred).

cetyltrimethylammonium bromide *abbr.*: CTAB; hexadecyltrimethylammonium bromide; *N*,*N*,*N*-trimethyl-1-hexadecanaminium bromide; a cationic detergent useful in the solubilization of membrane proteins; aggregation number 170, CMC 1 mM. It is the principal component of **cetrimide**.

Cf *symbol for* californium.

CFEM domain *abbr. for* common in fungal extracellular membrane proteins domain; a protein sequence (≈60 residues) that consists predominantly of hydrophobic residues and contains eight cysteine residues. It is present mainly in fungal and in some plant transmembrane or PIG-anchored proteins. The causal agent of rice blast disease contains at least eight proteins with this domain.

C form of DNA *abbr.*: C-DNA *or* DNA-C; the molecular conformation adopted by fibres of the lithium salt of duplex DNA at low relative humidity (below approximately 44%). It consists of a right-handed double helix containing about 9.3 nucleotide residues per turn; otherwise it is similar to the **B form**. *See also* **A form** (def. 1), **Z form**.

***Cfr*10I** a type 2 **restriction endonuclease**; recognition sequence: [AG]↑CCGG[TC].

***Cfr*13I** a type 2 **restriction endonuclease**; recognition sequence: G↑GNCC. *Asu*I is an **isoschizomer**.

CFTR *abbr. for* cystic fibrosis transmembrane conductance regulator.

CG *abbr. for* chorionic gonadotropin (*see* **choriogonadotropin**).

CgA1-40 the N-terminal 40 residues of chromogranin A, and of vasostatin. It increases secretion of calcitonin and calcitonin gene-related peptide (CGRP) from lung tumour cells but inhibits secretion of parathyroid hormone. *See* **chromogranin**.

cg clone any crown gall **clone** (def. 1); *see* **crown gall disease**.

CGM1 *see* **carcinoembryonic antigen**.

cGMP *abbr. for* cyclic GMP; *see* **guanosine 3′,5′-phosphate**.

CGRP *abbr. for* **calcitonin gene-related peptide**.

cgs system *or* **CGS system** *abbr. for* centimetre–gram–second system; a metric system of units based on the centimetre (length), gram (mass), and second (time). It has now been superseded by the **SI** system.

Chaikoff homogenizer a hydraulically operated tissue or cell homogenizer in which the sample is forced through an annulus by a piston. The piston diameter relative to that of the annulus is chosen to suit the size of the component that it is desired to isolate with minimal damage.

chain reaction a chemical reaction in which one or more reactive intermediates are continuously regenerated, often through a repetitive cycle of elementary 'propagation' steps.

chain-termination codon *an alternative name for* **termination codon**.

chain-termination method *or* **dideoxy method** *or* **Sanger method** a rapid technique for determining nucleotide sequences in DNA in which the 2′,3′-dideoxy analogues of the normal deoxynucleoside triphosphates are used as specific chain-terminating inhibitors of DNA polymerase. In the original method single-stranded DNA fragments are used as templates for the **Klenow enzyme** of DNA polymerase I in the presence of a primer and a mixture of a dideoxynucleoside triphosphate and the four normal deoxynucleoside triphosphates, one of which is labelled with ^{32}P. Separate incubations are carried out using analogous terminators for the other nucleotides. The effect is to yield radioactively labelled stretches of DNA corresponding in length to the number of bases between the 5′ end and the position of the base corresponding to the terminator, which will be incorporated once into each stretch of DNA in such a way that it yields an appropriate stretch of DNA for every position occupied by the base in question. The resulting products from each incubation are separated in parallel by gel electrophoresis and detected by autoradiography. From the pattern of radioactive bands obtained the sequence of the fragment can be read off. The method is reasonably accurate for sequences of 15 to about 200 nucleotides. Three modifications are made for automated DNA sequencing: (i) a different fluorescent label is covalently attached to each of the dideoxy chain terminators, or alternatively to the primer; (ii) **cycle sequencing** is used to generate dideoxy-terminated fragments; and (iii) a mixture of the four termination reactions is separated rapidly by capillary electrophoresis. Many hundreds of nucleotides can be read in a single run. [After Frederick Sanger (1918–), British biochemist.]

chair configuration (of a cyclobutadipyrimidine) *see* **pyrimidine dimer**.

chair conformation any **conformation** of a nonplanar, six-membered, saturated ring compound in which the ring atoms in relative positions 1, 2, 4, and 5 lie in one plane, and those in relative positions 3 and 6 lie on opposite sides of that plane. For a monosaccharide or monosaccharide derivative the conformational descriptor -*C* may be added to its name, and the reference plane is so chosen that the lowest-numbered carbon atom in the ring is exoplanar. *See also* **$^1C_4$**, **$^4C_1$**. *Compare* **boat conformation**.

chalcone **1** phenyl styryl ketone;1,3-diphenyl-2-propen-1-one. **2** any of a group of hydroxylated derivatives of chalcone (def. 1); they are important intermediates in plants in the biosynthesis of flavanones, flavones, flavonols, and anthocyanidins. The chalcone derivative **isoliquivitigenin** has anti-platelet activity, inhibiting 12-lipoxygenase. It stimulates soluble guanylate cyclase. It has anti-tumour activity and potently prevents tumour promotion by phorbol esters.

challenge **1** *(in immunology)* the act or process of injecting antigenic material into an immunized animal to test for immunity or to provoke a further immune response. **2** *(in endocrinology)* the act or process of administering an agent to evaluate hormonal responses. It is used to test hormonal control and function.

chalone any inhibitor affecting the cell cycle before the onset of mitosis that is tissue-specific and present in the tissue of action; it need not be species-specific. [From Greek *khalon*, to make slack.]

channel **1** a passage, often tubular or trough-shaped, along or through which movement of substances, especially fluids, can occur. **2** the span between selected settings of two discriminators in a pulse counter, e.g. a scintillation counter, that defines the range of pulse intensities that will be recorded. **3** to guide into or cause to move through a particular channel or along a particular route; e.g. to channel a metabolite along a particular metabolic pathway. **4** descriptive of a membrane protein or a protein complex that transports solutes, mainly of ionic nature, across a cell membrane down their concentration or electrochemical potential gradient (in the TC system families 1.A.1–1.A.36 and 1.B.1–1.B.34). Channels are either closed or open to both membrane sides simultaneously and can be gated (regulated) (i) electrically (e.g. nerve Na$^+$ and K$^+$ channels), (ii) chemically (e.g. acetylocholine receptor-channel), (iii) mechanically (K$^+$ channels in inner ear hair cells), or (iv) nongated (bacterial porins). *See also* **calcium channel**, **potassium channel**, **sodium channel**. **—channelled** *or* (*US*) **channeled** *adj.*

channel carrier *see* **ionophore**.

channel-forming integral membrane protein 28 *abbr.*: CHIP 28; *other name*: aquaporin 1; an integral membrane protein that forms a water-specific channel, conferring high permeability to water on the plasma membranes of red cells and kidney proximal tubules. It is a homotetramer.

channel gating the change that drives conformational changes in the structure of a membrane channel between closed and open states of the pore.

channelling *or* (*US*) **channeling** (*in column chromatography*) the uneven flow resulting from inhomogeneous packing of the column.

channel protein an **integral (cell membrane) protein** that permits the controlled (gated) movement of ions through a membrane. *See* **calcium channel**, **potassium channel**, **sodium channel**.

channel rhodopsin a light-gated protein channel in green algae. It consists of a seven-pass transmembrane protein (712 amino acids) whose hydrophobic core is homologous to that of **bacteriorhodopsin**.

channels-ratio method a method of quench correcting in liquid scintillation counting in which two channels are used to measure the average energies of beta particles both before and after quenching.

chaoptin an extracellular membrane glycoprotein required for *Drosophila melanogaster* photoreceptor cell morphogenesis, and containing a **leucine-rich repeat** domain. It is a cell-type specific adhesion molecule, exclusively localized to photoreceptor cells, linked to the outer surface of the membrane by a **GPI-anchor**.

Chaotropase *the proprietary name for* a mixture of endopeptidases isolated from *Streptomyces griseus*, so named for their stability and activity in the presence of the **chaotrope** 6 M guanidinium chloride.

chaotrope *or* **chaotropic agent** any substance that increases the transfer of apolar groups to water because of its ability to decrease the 'ordered' structure of water and to increase its lipophilicity. Chaotropes are usually ions, e.g. SCN^-, CNS^-, ClO_4^-, I^-, Br^-, CH_3–COO^-. They cause the dissolution of biological membranes, the solubilization of particulate proteins, changes in the secondary, tertiary, and quaternary structure of proteins, and denaturation of nucleic acids.

chaotropic dissociation assay a technique used to measure the heterogeneity of antibody affinities in, e.g., serum. Immune complexes are dissociated in buffers of varying strengths and pH or in chaotropic agents (*see* **chaotrope**). Low-affinity antibodies dissociate more readily.

chaperone any of a functional class of unrelated families of proteins that assist the correct non-covalent assembly of other polypeptide-containing structures *in vivo*, but are not components of these assembled structures when they are performing their normal biological functions. *See also* **chaperonin**, **heatshock protein**.

chaperonin any of a ubiquitous subclass of molecular **chaperones** implicated in the folding of other proteins. They include two kinds of protein: (1) chaperonin 60 kDa (*also called* chaperonin-60 *or* cpn 60; the counterpart in other structures of the product of the **groEL** gene of *Escherichia coli*); and (2) chaperonin 10 kDa (*also called* chaperonin-10 *or* cpn 10; the counterpart in, e.g., *Mycobacterium* of the product of the **groES** gene of *E. coli*). *See also* **heat-shock protein**.

CHAPS 3-[(3-cholamidopropyl)dimethylammonio]-1-propanesulfonate; a zwitterionic detergent combining the properties of sulfobetaine and bile-salt types of detergent. It is used for membrane solubilization. Aggregation number 4–14, CMC 6–10 mM.



$$R = -(CH_2)_3-\overset{H_3C\ \ CH_3}{\underset{+}{N}}-(CH_2)_3-SO_3^-$$

CHAPSO 3-[(3-cholamidopropyl)dimethylammonio]-2-hydroxy-1-propanesulfonate; a zwitterionic detergent combining the properties of sulfobetaine and **bile-salt** types of detergent; it is more soluble than **CHAPS**. Aggregation number 11, CMC 8 mM.



$$R = -(CH_2)_3-\overset{H_3C\ \ CH_3}{\underset{+}{N}}-CH_2-CHOH-CH_2-SO_3^-$$

characteristic group *(in chemistry)* any atom or group that is incorporated into a parent compound otherwise than by a direct carbon–carbon linkage, but including the groups –C=N and =C=X where X is O, S, Se, Te, NH, or substituted NH.

characteristic time a measure of the time required for a system to change from one state of motion to another, usually taken as the time required for the system to approach within one half of the new state of motion.

characteristic X-ray *see* **X-rays**.

Charcot–Marie–Tooth disease *abbr*.: CMT; a clinically and genetically heterogeneous polyneuropathy syndrome, affecting both motor and sensory peripheral nerves. It occurs in dominant, recessive, and X-linked forms and is one of the most common inherited neurological disorders, affecting 1:2500 people in the USA. Symptoms include weakness of the foot and lower leg muscles. The type I phenotype is due to demyelination of motor nerves and may be caused by overexpression (from a gene duplication) or underexpression (from a gene deletion) of peripheral myelin protein (PMP22), or by mutation in the genes for myelin protein zero, connexin 32, or EGR2. These are all proteins synthesized in myelinating Schwann cells. The type II phenotype is not well characterized at a molecular level. *See* **myelin protein**. [After Jean Charcot (1825–1893) and Pierre Marie (1853–1940), French neurologists; and Howard Tooth (1856–1925), British physician.]

Chargaff's rules a set of quantitative rules describing the base composition of duplex DNA: (1) [A] = [T] and (2) [G] = [C], where the square brackets denote the concentrations of the bases in moles per cent; minor bases, if present, are included with the appropriate major base. Three corollaries follow: (1) [A]/[T] = [G]/[C]; (2) total purines = total pyrimidines, i.e. [A] + [G] = [C] + [T]; and (3) total 6-aminobases = total 6-ketobases, [A] + [C] = [G] + [T]. A further consequence of these relationships is that the [A + T]/[G + C] ratio is a characteristic property of individual DNAs. [After Erwin Chargaff (1905–2002), US biochemist.]

charge 1 to load with the proper or appropriate quantity, e.g. to charge a tRNA molecule with an aminoacyl group, or to charge (an accumulator, capacitor, etc.) with electricity. **2** *see* **electric charge**. **3** the quantity of electricity held in, e.g., an accumulator or a capacitor. **4** a load. *Compare* **discharge**.

charge density *symbol* ρ; SI unit C m^{-3} (coulombs m^{-3}).

charged tRNA any **aminoacyl-tRNA** molecule.

charge-relay system a catalytic triad found in the serine proteases, comprising, in chymotrypsin, residues His^{57}, Ser^{195} and Asp^{102}, the histidine being hydrogen bonded to the carboxylate of the buried aspartate. Spatially, these residues occur in positions such that the electronegativity of the aspartate carboxyl group can be relayed through the histidine nitrogen atoms to the serine hydroxyl group, enhancing its reactivity.

chargerin II *other names*: A61; protein 8 of H^+-transporting ATP synthase (EC 3.6.1.34); one of the chains of the non-enzymic component (CF_0 subunit) of the mitochondrial ATPase complex (membrane bound). *See also* **H^+-transporting ATP synthase**.

charge-shift electrophoresis a method of **electrophoresis** in a detergent solution in which the net charges of the complexes between amphiphilic proteins and the detergent depend on the charge of the latter, while the net charges on hydrophilic proteins are unaffected. This effect is exploited in, e.g., SDS–polyacrylamide gel electrophoresis.

charge-transfer bond an absorption band in the UV-visible region observed in a charge-transfer complex. Such absorption bands are common in complexes of transition metals, and other redox-active molecules such as flavins.

charge-transfer chromatography a method of **liquid-gel chromatography** in which separation is due to electronic coupling between molecules being chromatographed and strong electron donor or acceptor groups attached to the supporting gel.

charge-transfer complex a complex that may be formed in an oxidation–reduction reaction, corresponding to electronic transition(s) to an excited state in which there is a partial transfer of electronic charge from the electron donor to the electron acceptor.

charging the covalent attachment of an aminoacyl group to a tRNA molecule to form an **aminoacyl-tRNA** molecule.

Charles's law *see* **gas laws**. [After Jacques Alexandre Cesar Charles (1746–1823), French physicist.]

charybdotoxin *abbr.*: ChTX; a 37-residue peptide isolated from the venom of the scorpion *Leiurus quinquestriatus hebraeus*. It is a potent inhibitor of some Ca^{2+}-activated K^+ channels and voltage-dependent K^+ channels, and probably acts at the outer face of the membrane, blocking the ion conductance channel. It has links between Cys residues 7–28, 13–33, and 17–35; amino-acid sequence:

XFTNVSCTTSKGCWSVCQRLHNTSRGKCMNKKCRCYS

(X = pyroglutamyl).

chase 1 the effective termination of incorporation of either a (radio)nuclide or a labelled compound into a substance, brought about by the addition of a large excess of an isotope of the (radio)nuclide or the unlabelled compound to the system, used especially after a pulse. **2** the quantity of isotope or unlabelled compound added to stop the incorporation of a (radio)nuclide or a labelled compound.

che the symbol for any of a class of genes that are implicated in chemotaxis in *Escherichia coli*. For example, *cheA* encodes a chemotaxis protein, protein phosphotransferase (EC 2.7.1.–), that is autophosphorylated and transfers its phosphate to CheB and CheC. Other two-component bacterial regulatory proteins are related. *cheB* encodes a chemotaxis protein, **protein-glutamate methylesterase** (EC 3.1.1.61), that catalyses the hydrolysis of protein L-glutamate *O*-methyl ester to protein L-glutamate and methanol. The protein is a **methyl-accepting chemotaxis protein** (MCP), the methylation state of which is crucial for sensory responses and adaptations. *cheR* encodes the chemotaxis protein methyltransferase (EC 2.1.1.80); it catalyses the reaction:

$$\begin{gathered}S\text{-adenosyl-L-methionine} + \text{protein L-glutamate} = \\ S\text{-adenosyl-L-homocysteine} + \text{protein L-glutamate methyl ester.}\end{gathered}$$

The protein is an MCP, the methylation state of which is crucial for sensory responses and adaptations. *cheW* encodes a purine-binding chemotaxis protein that is involved in the transmission of sensory signals from chemoreceptors to the flagellar motors. *cheY* encodes a chemotaxis protein involved in the transmission of sensory signals from chemoreceptors to flagellar motors and the regulation of clockwise rotation. The structure is largely alpha helical, with some beta strands. *cheZ* encodes a chemotaxis protein thought to be involved in generating a regulating signal for bacterial flagellar rotation.

checkpoint a point in the eukaryotic **cell division cycle** where the cycle can be halted until conditions are suitable for the cell to proceed to the next stage – e.g. to allow for repair of damaged DNA.

checkpoint kinase a cell-cycle checkpoint protein kinase that is activated in response to DNA damage. Its action prevents the cell from entering mitosis.

CHEF *abbr. for* contour-clamped homogeneous electric field; one of several designs of apparatus for performing **pulsed field gel electrophoresis**.

chel *abbr. for* chelate effect.

chelate 1 any chemical species in which there is **chelation**. **2** of, or denoting, a chelate (def. 1). **3** to form a chelate compound; to effect **chelation**. A chelate compound is a chemical compound in which a metal ion is combined with a substance that contains two or more electron donor groups so that the resulting structure contains one or more rings. **—chelated** *adj.*

chelate effect *abbr.*: chel; the stability difference between a chelate complex and the corresponding complex with simple ligands. For the displacement reaction:

$$MA_n + mL \rightarrow ML_m + nA,$$

$$\text{chel} = \log \beta_m\,(ML_m) - \log \beta_n\,(MA_n),$$

where ML_m and MA_n are complexes containing an equal number of the same donor atoms. Ligand L is multidentate, containing several donor atoms of the same element as the unidentate ligand A, and β_m and β_n are the overall stability constants.

chelating agent *or* **chelator** a substance that is able to form a **chelate compound** with a metal ion.

chelation the formation or presence of bonds from two or more atoms within the same ligand to a single central (metal) atom.

chelation therapy the therapeutic use of chelating (metal-binding) agents for the removal of toxic amounts of metal ions from living organisms. The metal ions are sequestered by the chelating agents and are either rendered harmless or excreted. Chelating agents such as dimercaprol, EDTA, desferrioxamine, and penicillamine have been used effectively in chelation therapy for arsenic, lead, iron, and copper respectively.

Chelex 100 *the proprietary name for* a synthetic ion-exchange resin consisting of a styrene divinylbenzene copolymer containing paired iminodiacetate groups that act as chelating groups in binding metal ions, especially transition-metal or other divalent ions.

chemical adsorption *an alternative term for* **chemisorption**.

chemical antagonism antagonism resulting from the chemical combination of an **antagonist** with the substance being antagonized.

chemical carcinogen any carcinogenic substance of low relative molecular mass. *See* **carcinogen**.

chemical cleavage method 1 *or* **Maxam–Gilbert method** a rapid technique for determining nucleotide sequences in DNA (or in restriction fragments) that depends on labelling either end of a DNA strand with ^{32}P and the subsequent preferential, partial chemical cleavage of the labelled DNA specifically at positions occupied by one of the four possible bases. This results in a nested set of radioactive fragments extending from the ^{32}P label to each of the positions occupied by the particular base. The process is then repeated with cleavage, in turn, at each of the other three bases. The four sets of radioactive fragments are then separated, in adjacent lanes, by polyacrylamide gel electrophoresis, which arranges oligonucleotides in ascending order of the number of nucleotide residues contained. The base sequence of the original piece of DNA can be read directly from an autoradiograph of the resultant gel. The method can be used for sequences of 150 or more nucleotide residues. *Compare* **chain-termination method**. [After Allan M. Maxam and Walter Gilbert (1932–).] **2** a method for detecting the position of a mutation in DNA. In a heteroduplex formed between the normal and mutant DNA the deoxyribose phosphate backbone of DNA can be cleaved at the mismatched nucleotides by exposure to chemicals such as hydroxylamine and osmium tetroxide. The position of the mutation in polymerase chain reaction (PCR) products can be ascertained from the lengths of the resulting fragments.

chemical coupling hypothesis the hypothesis that the coupling of ATP synthesis to oxidation in oxidative phosphorylation is due to the formation of common 'high-energy' intermediates during electron transport that are subsequently used to phosphorylate ADP to ATP. It has been superseded by the **chemiosmotic coupling hypothesis**.

chemical equivalent the combining proportion of a substance, by mass, relative to a hydrogen standard. The chemical equivalent of an element is the number of grams of that element that will combine with or replace 1 g of hydrogen.

chemical exchange the changing magnetic environment of an atomic nucleus in a molecule that is rapidly undergoing reversible chemical or physical changes, which in turn produces changes in the **chemical shift** of that nucleus.

chemically induced dynamic nuclear polarization *abbr.*: CIDNP; a technique for the direct detection and identification of low concentrations of free radicals by **electron spin resonance**. It depends on strong polarization of certain nuclear spins by the unpaired electron during the molecule's existence as a free radical.

chemical messenger a term sometimes used loosely to mean variously a hormone, a neurocrine or paracrine transmitter, or a rheoseme. *See also* **second messenger**.

chemical oxygen demand *abbr.*: COD; a measure of the oxygen equivalent of that portion of the organic matter in a sample of water that is susceptible to oxidation by a strong chemical oxidant. Essentially the sample is boiled under a reflux condenser with potassium dichromate in strong sulfuric acid (with silver sulfate as catalyst); part of the dichromate is reduced by the contained organic matter and the remaining dichromate is titrated with ferrous sulfate. The result is expressed as milligrams oxygen absorbed from standard dichromate per litre of sample. *Compare* **biochemical oxygen demand**.

chemical pathology the branch of pathology dealing with the biochemistry of disease processes and the measurement of the amounts of substances present in body fluids and other samples as an aid to diagnosis.

chemical potential *symbol*: μ; the partial molar free energy of a chemical entity; the entity in question may be indicated by a subscript. For example, μ_B symbolizes the chemical potential of entity B in a mixture of entities B, C, ... etc. It is defined by:

$$\mu_B = (\partial G/\partial n_B)_{T,P,n_C},$$

where G is the Gibbs energy of the mixture, T is the thermodynamic temperature, P is the pressure, and n_B, n_C, ... etc. are the amounts of the entities B, C, ... etc. in the mixture.

chemical quenching *or* **impurity quenching** the **quenching** that occurs in liquid scintillation counting due to diffusion-controlled collisional interaction between the quencher molecules and the excited solvent and solute molecules. *Compare* **colour quenching**.

chemical reaction any single process or operation involving the interconversion of chemical species through changes in orbital electrons but not in the atomic nuclei.

chemical score a measure of the nutritional value of a protein. The limiting essential amino acid in the test protein is expressed as the percentage of the amount of the same amino acid present in egg albumin, the nutritionally perfect protein. Chemical score is numerically equal to **biological value**.

chemical shift the displacement of a resonance signal in NMR spectroscopy along the magnetic field coordinate resulting primarily from the magnetic effects of the chemical environment of the nuclei producing that signal. *See* **nuclear magnetic resonance**.

chemical shift anisotropy a technique based on nuclear magnetic resonance in which the chemical shift changes with the orientation of the sample in the magnetic field, used in molecular dynamics on proteins and in some other fields.

chemical species any set of chemically identical **molecular entities**, the members of which have the same composition and can explore the same set of molecular energy levels within the time scale of a particular experiment. Two conformational isomers may interconvert sufficiently slowly to be considered separate chemical species on an NMR time scale, but in a slow chemical reaction they may interconvert sufficiently quickly to be considered as a single chemical species.

chemical transmitter *(sometimes) an alternative term for* **neurotransmitter**.

chemiluminescence the production of visible light (luminescence) occurring as a result of a chemical reaction. It occurs, for example, during the **respiratory burst** in neutrophils and other phagocytic cells. The phenomenon is now exploited in sensitive enzyme assays and labelling methods in nucleic-acid hybridization, etc.

cheminformatics *an alternative name for* chemoinformatics; *see* **informatics**.

chemiosmotic coupling hypothesis a hypothesis proposed in 1961 by the British biochemist Peter Mitchell (1920–92) to explain ATP formation in mitochondria. Essentially it states that the energy-yielding reactions of the **respiratory chain** are coupled to the energy-requiring reactions of phosphorylation through the creation of a membrane electrochemical potential. An electrochemical gradient of H^+ ions, and a voltage gradient, is established across the mitochondrial inner membrane during electron flow through the respiratory chain. The electron carriers of the respiratory chain serve as an active-transport system or 'pump' to transport H^+ ions from the mitochondrial matrix across the inner membrane, which is an integral part of the coupling mechanism. The electrochemical gradient thus formed drives the synthesis of ATP from ADP and P_i. A similar mechanism is believed to drive oxidative phosphorylation in the chloroplast during the **light reactions of photosynthesis**.

chemism *(rare)* chemical action, operation, activity, or force.

chemisorption *or* **chemical adsorption** a type of **adsorption** in which the forces involved are valence forces of the same kind as those operating in the formation of chemical compounds. *Compare* **physisorption**.

chemoattractant *an alternative term for* **attractant**.

chemoautotroph *or* **chemolithotroph** any organism that is both an **autotroph** and a **chemotroph**. **—chemoautotrophic** *adj.*

chemoceptor *an alternative name for* **chemoreceptor** (esp. in immunology).

chemography an artefact in autoradiography due either to the creation of reduced crystals in the photographic emulsion by chemicals present in the specimen (**positive chemography**), or to the removal of latent images, also by chemicals in the specimen (**negative chemography**).

chemoheterotroph *or* **chemoorganotroph** any organism that is both a **chemotroph** and a **heterotroph**. **—chemoheterotrophic** *adj.*

chemoinformatics *or (sometimes)* **cheminformatics** *see* **informatics**.

chemokine *or* **intercrine** any of a subgroup of cytokines acting primarily as chemotactic agents that cause accumulation of leukocytes into tissues. They are secreted in response to inflammatory cytokines (e.g. interleukin 1, THFα), bacterial products, or viral infection. They are basic polypeptides (8–10 kDa), more than 40 of which are known and showing 20–70% homology. Subdivison into four families is on the basis of the number and relative position of their cysteine residues. More than a dozen G-protein-associated cytokine receptors activate phospholipase C. Cytokine receptor 5 is a coreceptor (with T-cell receptor) for HIV. A codon deletion in its gene (at 3p21) is present in ≈10% of white people and confers high resistance to HIV infection.

chemolithotroph *an alternative term for* **chemoautotroph**.

chemoorganotroph *an alternative term for* **chemoheterotroph**.

chemoreceptor *or* **chemoceptor** any **receptor** on a cell that receives chemical stimuli and reacts to them or binds them.

chemostat a device for the continuous culture of bacterial (and other) cells. Growth occurs in an aerated fermenter vessel and its rate is controlled by the rate of addition of fresh nutrient from a reservoir (i.e. the dilution rate); this in turn controls the rate of removal of cells (and culture medium). In a chemostat, as opposed to an **auxostat**, the dilution rate is constant. At equilibrium, the rate of production of new cells by multiplication is equal to the rate of removal of grown cells.

chemosynthesis the synthesis of organic chemical compounds by an organism using energy obtained from the oxidation of inorganic chemical compounds rather than from light. *Compare* **photosynthesis**. **—chemosynthetic** *adj.*

chemotactic factor for macrophages *see* **lymphokine**.

chemotaxin *(sometimes) an alternative term for* **cytotaxin**.

chemotaxis 1 a movement of a motile cell or organism (*see* **taxis**) in response to a specific chemical concentration gradient. Movement may be towards a higher concentration (**positive chemotaxis**) or towards a lower concentration (**negative chemotaxis**). In *Escherichia coli* the ***che*** family of genes has been implicated in controlling certain aspects of chemotaxis, and **galactose/glucose binding protein** is also involved. *See also* **cytotaxis**. **2** *(in immunology)* the migration of polymorphonuclear leukocytes and macrophages towards higher concentrations of certain fragments of complement such as C3a and C5a. *See also* **lymphokine**. **—chemotactic** *adj.*

chemotaxonomy the classification of organisms on the basis of the nature, content, and/or the distribution of constituent chemical substances, e.g. DNA.

chemotherapy the treatment of disease, especially infections and neoplasms, with chemical agents (**chemotherapeutic agents**) that act specifically on infective organisms or tumours. The term also describes the treatment of psychiatric disease with chemical agents (as opposed to cognitive therapy). **—chemotherapeutic** *adj.*

chemotractant *see* **attractant**.

chemotroph any organism that derives its energy from exogenous chemical sources, independently of light. Chemotrophs may be subdivided into (1) chemoautotrophs (or chemolithotrophs), i.e. organisms that are both chemotrophs and **autotrophs**; and (2) chemoheterotrophs (or chemoorganotrophs), i.e. organisms that are both chemotrophs and heterotrophs. *Compare* **phototroph**. **—chemotrophic** *adj.*; **chemotrophy** *n.*

chemotropism the orientation of cells or organisms in response to chemical stimuli. The term is used especially of plants or plant organs. *See also* **tropism**. **—chemotropic** *adj.*

Cheng–Prussoff equation an equation relating the concentration, I_{50}, of a competitive ligand required to reduce the binding of a substrate to an enzyme by 50%, to the dissociation constant, K_i, of the enzyme–inhibitor complex; it is:

$$I_{50} = K_i\,(1 + S/K_m),$$

where S is the substrate concentration and K_m the Michaelis constant for the enzyme–substrate complex.

chenodeoxycholate *or* **chenodiol** the anion of $(3\alpha,5\beta,7\alpha)$-3,7-dihydroxycholan-24-oic acid; a major component of bile in some species (hens, geese) but a minor component in humans. It is used therapeutically to decrease the synthesis of cholesterol and to help dissolve cholesterol gallstones.



Cherenkov counter *or* **Cerenkov counter** a device for counting charged particles, or radionuclides emitting them, that depends on **Cherenkov radiation**.

Cherenkov radiation *or* **Cerenkov radiation** a radiation of bluish light, consisting of photons, emitted when charged particles, especially high-energy beta particles, pass through either a solid or liquid medium at velocities greater than that at which light passes through the same medium. The effect is analogous to the creation of a sonic boom that occurs when an object exceeds the speed of sound in a medium. [After Pavel Alekseyevich Cherenkov (1904–1990), Russian-born Soviet physicist.]

Ches *abbr. for* 2-(cyclohexylamino)ethanesulfonic acid; a compound with similar properties to a **Good buffer substance**; pK_a (25°C) = 9.3.



chewing gum *see* **chicle**.

chi *symbol*: χ (lower case) *or* X (upper case); the twenty-second letter of the Greek alphabet. For uses *see* **Appendix A**.

chiasma (*pl.* **chiasmata**) **1** *(in genetics)* a connection formed between **chromatids**, visible during **meiosis**, thought to be the point of the interchange involved in crossing-over. **2** *or (esp. US)* **chiasm** (*pl.* **chiasms**) *(in anatomy)* a decussation or intersection, as of two nerves; e.g. optic chiasma.

chicle a mixture of *cis*- and *trans*-1,4-polyprenoids obtained from the evergreen tree, *Achras sapota*; the original chewing gum base.

Chico an insulin receptor substrate-like protein in *Drosophilia* that links the insulin receptor to phosphatidylinositol 3-kinase and then protein kinase B and protein synthesis. A mutation of the corresponding gene results in fruit flies less than half the normal size.

chimera *or (esp. Brit.)* **chimaera** *(in genetics)* an organism comprising tissues of two or more **genotypes**. Chimeras can occur as a result of mutation, abnormal distribution of chromosomes, grafting, or genetic manipulation. For example, a chimera can be created by mixing the cells from embryos of two different animal species at the blastocyst stage of development and implanting the chimeric embryo in a surrogate mother to continue development. When the species are sheep and goats, the resulting chimeric progeny are called 'geep', or 'shoats'. Alternatively, in mice, genetically manipulated mouse embryonic stem (ES) cells are injected into the blastocoel of a blastocyst. Later stages of development are completed in the reproductive tract of a surrogate mother to produce chimeric mice. These are readily identified if the strain from which the ES cells are derived has a different coat colour from that of the strain producing the blastocyst. Production of chimeras is a step in the generation of mice carrying gene knockouts produced by homologous recombination in ES cells. *See* **mosaic**, **transgenic**, **chimeric molecule**. —**chimeric** *or* **chimaeric** *adj.*

chimeraplast any RNA–DNA chimeric oligonucleotide used to induce base pair conversions at the genomic level and used in gene repair strategies for gene therapy. –**chimeraplastic** *adj.*

chimeric molecule **1** any of the hybrid DNA molecules formed when DNAs from different sources are digested with the same **restriction endonuclease** and the digests are mixed. The DNA fragments in the mixture become associated by hydrogen bonds between complementary sequences to form new arrangements, which may be converted into covalently linked molecules by the action of DNA ligase. This process can produce **chimeric plasmids** and other chimeric structures. **2** a **chimeric protein** (*or* **fusion protein**) is a protein obtained by the insertion or substitution of a partial sequence from one protein into another, typically using cDNA technology. The resultant protein thus has elements of both the original proteins. Such proteins frequently form naturally as a result of chromosomal translocations during neoplastic transformation. *See* **acute myeloid leukemia**. **3** a recombinant antibody that has, e.g., structural characteristics of both human and mouse antibodies.

chimerin any of several related proteins that function as GTPase-activating proteins, specific for the p21 Ras-related Rac GTPase. They include n-chimerin, and α- and β-chimerins. n-Chimerin is a cerebellar protein, and β-chimerin is expressed in testis. They are phorbol ester receptors, with an N-terminal domain similar to the zinc-finger region of protein kinase C, and a C-terminal domain similar to the product of **BCR**. Through their action on Rac, they lead to changes in cytoskeletal organization.

chimyl alcohol glycerol 1-hexadecyl ether, (+)-3-(hexadecyloxy)-1,2-propanediol; a hydrolysis product of **ether lipids**.

Chinese restaurant syndrome *see* **monosodium glutamate**.

ChIP *abbr. for* chromatin immunoprecipitation.

CHIP 28 *abbr. for* channel-forming integral membrane protein 28; *also called* AQP 1 (*see* **aquaporin**).

chiral describing a chemical compound that displays **chirality**.

chiral drug a single pure enantiomer of a specified drug rather than the racemate; the enantiomers may have very different pharmacological effects, e.g. in the case of propoxyphene and levopropoxyphene.

chirality topological handedness; the property of nonidentity of an object with its mirror image. A chiral chemical compound, i.e. one that possesses chirality, is one that cannot be superimposed on its mirror image, either as a result of simple reflection or after rotation and reflection. If superposition can be achieved then the molecule is said to be **achiral**. Chirality is most commonly due to the presence of one or more **chiral centres** (formerly referred to as asymmetric carbon atoms) or the presence of a **chiral axis** (as in allene structures, some of which are found in natural products). Rarely, chirality may also result from the presence of a chiral plane. *See also* **prochiral**. [From Greek *kheir*, hand.]

chiral methyl a carbon atom carrying the three hydrogen isotopes, i.e. -$C^1H^2H^3H$.

chiral recognition the differentiation of the enantiomers of a compound. This can be achieved by living organisms, chiral molecules, enzymes, drug receptors, etc.

chiroid *(rare)* any molecule that has **chirality**.

chiroptical describing any of the phenomena that depend on the ability of chiral and other intrinsically asymmetric molecules to rotate the plane of polarized light, known collectively as **optical activity**. Such phenomena include **optical rotation**, **optical rotatory dispersion**, and **circular dichroism**. The term is also applied to any of the techniques used for investigating these phenomena.

chi sequence *or* **chi site** a sequence of base pairs first discovered in a phage lambda mutant, called *chi*. These mutants were found to have single base pair changes creating sites that stimulate **recombination**. Characteristic of chi sites is a nonsymmetrical sequence of eight base pairs, consensus sequence:

5′ GCTGGTGG 3′.

A recombinational hot spot in *Escherichia coli* and a binding site for **Rec A** is a chi site.

chi site *see* **chi sequence**.

chi-square test a statistical test to determine whether an observed series of values differs from a series of values expected on a hypothesis, to a greater degree than would be expected by chance. If *m* is the expected value and ($m + x$) is the observed value then $\chi^2 = \Sigma(x^2/m)$. The goodness of fit may be found from available tables of χ^2 and the number of degrees of freedom, *n*, in which the observed series may differ from the hypothetical.

chi structure a structure formed when circular duplex DNA that is undergoing **recombination** is cut with a restriction enzyme. This yields two strands joined at a site intermediate between the ends, which by electron microscopy can yield a shape with the appearance of the Greek letter χ. The structure results from the fact that if two circular duplex DNAs undergo site-specific recombination, a single strand from each duplex will be opened and the two single strands ligated to each other to form a figure of eight. If each of the loops of this figure of eight is cut by the restriction enzyme the chi structure will result. *Compare* **Holliday junction**.

chitin a linear polysaccharide consisting of *β*-1,4-linked *N*-acetyl-D-glucosamine residues. It is found in annelid cuticle, arthropod exoskeleton, and in some plants and fungi. In fungi, chitin represents the microfibrillar component of the cell wall. *See also* **chitobiose**, **chitosan**.

chitinase EC 3.2.1.14; *other names*: chitodextrinase; 1,4-*β*-poly-*N*-acetylglucosaminidase; poly-*β*-glucosaminidase. An enzyme that catalyses the hydrolysis of the 1,4-*β*-linkages of *N*-acetyl-D-glucosamine polymers of chitin.

chitin synthase EC 2.4.1.16; *other name*: chitin–UDP *N*-acetylglucosaminyltransferase; an enzyme that catalyses the reaction between UDP-*N*-acetyl-D-glucosamine and [1,4-(*N*-acetyl-*β*-D-glucosaminyl)]$_n$ to form UDP and [1,4-(*N*-acetyl-*β*-D-glucosaminyl)]$_{n+1}$.

chitobiose 4-*O*-(2-amino-2-deoxy-*β*-D-glucopyranosyl)-2-amino-2-deoxy-D-glucose; *condensed form*: Glc*p*N(*β*1-4)GlcN; a disaccharide found in its acetylated form in chitin. This acetylated form, Glc*p*NAc(*β*1-4)GlcNAc, is the repeating unit of chitin, and should, logically, have the name chitobiose (by analogy with cellobiose, the repeating unit of cellulose). However, historically the nonacetylated form received the name chitobiose, a convention that has persisted.



α-anomer

chitosamine *see* **glucosamine**.

chitosan the cationic polymeric carbohydrate obtained by the deacetylation of **chitin**.

chitosome a body found in fungi and containing chitin synthase; it synthesizes chitin microfibrils.

chitotriose a triose formed of beta-1,4-linked *N*-acetyl-D-glucosamine.

chitotriosidase an enzyme able to hydrolyse the trisaccharide derived from chitin. Activities are greatly elevated in **Gaucher's disease**, in which it is used as a marker to assess whether enzyme replacement therapy with **glucosylceramidase** has been successful.

Chl *abbr. for* chlorophyll.

chlor+ *a variant of* **chloro+** (sometimes before a vowel).

chlorambucil 4-[bis(2-chloroethyl)amino]benzenebutanoic acid; an alkylating agent that reacts with DNA causing the formation of covalent bonds that cross-link with the two strands of DNA, thereby preventing its replication.



chloramine T *N*-chloro-4-methylbenzenesulfonamide sodium salt; sodium 4-toluenesulfonchloramide hydrate; CH_3–C_6H_4– SO_2-$NClNa \cdot xH_2O$. A white crystalline solid with a faint odour of chlorine. In aqueous solution it slowly decomposes to sodium hypochlorite and thus is a mild oxidant and antiseptic. It is widely used for the oxidation of radioiodide in the preparation at high specific radioactivity of radioiodine-labelled peptides and proteins for use in radioimmunoassay or other *in vitro* techniques. Microgram quantities of many proteins are labelled efficiently at or near pH 7; however, some proteins may suffer an unacceptable degree of oxidative damage.



chloramphenicol *abbr.*: CAP; a broad-spectrum, chlorine-containing antibiotic produced by *Streptomyces venezuelae*; it is now produced by chemical synthesis. The configurations at C-1 and C-2 are (*S*), as shown in the structure. It inhibits prokaryotic protein synthesis by attaching to the 50S ribosomal subunit and inhibiting peptidyltransferase (EC 2.3.2.12), thereby preventing the formation of peptide bonds. Chloramphenicol also inhibits protein synthesis in mitochondria, and this accounts for its toxic effect in causing aplastic anemia. It is much used for the treatment of typhoid fever.



chloramphenicol *O*-acetyltransferase *abbr.*: CAT; EC 2.3.1.28; a bacterial enzyme, not found in eukaryotes, that catalyses the reaction between acetyl-CoA and chloramphenicol to form CoA and chloramphenicol 3-acetate. This reaction forms the basis for acquired chloramphenicol resistance in certain bacterial strains. Also the gene for CAT is used as a **reporter** because its expression can be detected by a sensitive radiochemical assay. In cDNA technology, for example, the expression of a eukaryotic promoter can be characterized by assay of the enzyme if CAT cDNA is included in the genes to be expressed.

chloramphenicol amplification a technique whereby chloramphenicol is added to growing cultures of bacteria harbouring plasmids, to inhibit cell growth and division without interfering with plasmid replication. This results in an increased plasmid copy number per cell.

chlordiazepoxide 7-chloro-*N*-methyl-5-phenyl-3*H*-1,4-benzodiazepin-2-amine 4-oxide; a CNS depressant noted primarily for its effective anti-anxiety effects at nonsedative doses. It is the prototypical **benzodiazepine**, used therapeutically as the hydrochloride. It is a controlled substance in the US Code of Federal Regulations. One proprietary name of the hydrochloride is Librium.



chloride 1 *symbol*: Cl^-; the anion of the element chlorine. **2** any salt of hydrochloric acid. **3** any compound containing a chlorine atom in organic linkage.

chloride channel any of a family of proteins that facilitate Cl^- transport through a membrane. These channels are of two types: (1) ligand-gated Cl^- channels associated with inhibitory neurotransmitter receptors, such as the **GABA receptor** or **glycine receptor**; and (2) voltage-gated Cl^- channels. These are structurally unrelated to other voltage-gated channels, and are believed to possess 10 or 12 transmembrane domains, with both N- and C-termini residing in the cytoplasm. They are found in a wide range of organisms, from bacteria and yeasts to plants and animals. Their functions in higher animals are thought to include regulation of cell volume, control of electrical excitability, and trans-epithelial transport. *See also* **cystic fibrosis transmembrane conductance regulator**.

chloride shift *or* **Hamburger shift** the phenomenon whereby, because of the **isohydric shift**, there is a higher concentration of hydrogencarbonate ions in the erythrocytes in blood leaving the tissues (venous blood) than in arterial blood, and hence the hydrogencarbonate/chloride ion ratio is higher in the erythrocytes than in plasma. This results in a movement of hydrogencarbonate ions out of the erythrocytes into the plasma and an equivalent movement of chloride ions from the plasma into the erythrocytes. In the lungs the reverse ion movements occur upon the oxygenation (arterialization) of the blood there.

chlorin *a trivial name for* 2,3-dihydroporphyrin.

chlorinate 1 to treat or react (a substance) with dichlorine. **2** to introduce one or more chloro groups into an organic compound, whether by addition or substitution. **3** to disinfect (especially water) with dichlorine. —**chlorination** *n.*

chlorine 1 *symbol*: Cl; a halogen element of group 17 of the IUPAC **periodic table**; atomic number 17; relative atomic mass 35.453. The 15th most abundant element of the Earth's crust, occurring in the combined state, mostly as inorganic chlorides. **2** *symbol*: Cl_2; the common name for the yellowish-green gaseous substance, correctly known as **dichlorine**.

chloro+ *or (sometimes before a vowel)* **chlor+** *comb. form* **1** denoting a chlorine atom in organic linkage. **2** denoting the colour green.

chlorocruorin any green, ~3 MDa, hemochrome respiratory pigment found in the blood of certain polychaete annelids; it contains 96 heme groups.

chlorogenic acid 3-*O*-(3,4-dihydroxycinnamoyl)-D-quinic acid; a tannin found in tea and coffee.

chlorolabe *or* **chloropsin** *or* **cyanopsin** *See* **cyanopsin**, **opsin**.

***p*-chloromercuribenzenesulfonate** *abbr.*: PCMBS; 4-(chloromercuri)benzenesulfonate; $Cl–Hg–C_6H_4–SO_3^-$; a reagent that reacts with thiol groups; it is more soluble than *p*-chloromercuribenzoate.

***p*-chloromercuribenzoate** *abbr.*: PCMB; 4-(chloromercuri)benzoate; $Cl–Hg–C_6H_4–COO^-$; a reagent that reacts with thiol groups. It is supplied either as *p*-chloromercuribenzoic acid or as *p*-hydroxymercuribenzoate sodium salt.

4-chloromercuriphenylsulfonate *see* ***p*-chloromercuribenzenesulfonate**.



chlorogenic acid

chloroperoxidase EC 1.11.1.10; *other name*: chloride peroxidase. An enzyme that catalyses a reaction between H_2O_2, two molecules of Cl^- ion, and two molecules of an organic compound to form two molecules of an organic chloride and two molecules of H_2O. It is useful for the introduction of (radioisotopes of) chlorine, bromine, or iodine into tyrosine residues in proteins. It is involved in the synthesis of chlorine-containing compounds such as (1*S*-*trans*)-2,2-dichloro-1,3-cyclopentanedione (caldariomycin).

***p*′-chloro-*p*-phenylaniline** *see* **4-amino-4′-chlorodiphenyl**.

chlorophyll any of the several green (or purple, *see* **bacteriochlorophyll**) pigments, found in plants and photosynthetic bacteria, that function in **photosynthesis** by absorbing light energy mainly in the red and violet-blue parts of the spectrum. Chlorophylls are magnesium complexes of various closely related porphyrins or chlorins. The main chlorophylls of land plants are chlorophylls *a* and *b*, and some algae contain chlorophylls *c*. Chlorophylls *a* and *b* are dihydroporphyrins, having no double bond at position 3 of ring B, while chlorophylls *c* are porphyrins. Photosynthetic bacteria contain various bacteriochlorophylls. The structure of chlorophyll *a* is shown. Chlorophyll *b* differs from chlorophyll *a* only in the presence of a formyl group in place of the methyl group at position 3 on ring B (Fischer system: *see* **bacteriochlorophyll**). Several chlorophylls *c* are known. They are accessory light-harvesting pigments found in eukaryotic algae that do not contain chlorophyll *b*. The structure of chlorophyll c_2 is shown, chlorophyll c_1 differing from this in having an ethyl group at position 4 of ring B, and chlorophyll c_3 differing from it in having a methylformyl group at position 3 of ring B. Most chlorophylls exist in **antenna complexes**, where their function is to absorb visible light and to transmit the energy so absorbed to a reaction centre in which other chlorophyll molecules are excited by



chlorophyll *a*

the accumulated energy to transfer an electron to an electron transfer system known as a **photosystem**. Differences in structure have significant effects on the absorption spectrum of the chlorophyll molecule, i.e. on the wavelength of the light absorbed, and thus on the energy available as a result of the absorption (*see* **Planck constant** for the relationship). To restore its electronic state, the oxidized chlorophyll molecule can accept an electron from a water molecule (or, in photosynthetic sulfur bacteria, from hydrogen sulfide), the transfer being catalysed by a manganese-rich protein complex that is part of the photosystem. This reaction is responsible for the dioxygen (or sulfur) that is formed during photosynthesis, one molecule of dioxygen, four protons, and four electrons being produced from two water molecules. *See also* **P680**, **P690**, **P700**. [From the Greek *khloros*, yellowish or pale green, and *phyllon*, leaf.]



chlorophyll c_2

chlorophyllide a **chlorophyll** lacking the terpenoid side chain, usually phytol. The penultimate intermediate in chlorophyll biosynthesis. It is formed by the light-catalysed reduction of protochlorophyllide attached to a protein, protochlorophyllide holochrome.



chlorophyllide *a*

chloroplast *or (sometimes)* **chloroplastid** a chlorophyll-containing **plastid**, found in cells of algae and higher plants, that is the site of **photosynthesis**. Chloroplasts are characterized by a system of membranes embedded in a hydrophobic proteinaceous matrix, or stroma. The basic unit of the membrane system is a flattened single vesicle called the **thylakoid**; thylakoids stack into grana (*sing.* **granum**). All the thylakoids of a granum are connected with each other, and the grana are connected by intergranal lamellae. Chloroplasts are rich in various proteases (e.g. serine, aspartic, ATP-dependent, light-activated, for oxidized or photodamaged proteins, for trafficking of protein precursors into the plastids). Some of these may have a role in senescence. *See* **Clp protease**.

chloroquine [N^4-(7-chloro-4-quinolinyl)-N^1,N^1-diethyl-1,4-pentanediamine; a widely used synthetic quinoline antimalarial drug, with action similar to **quinine**. It accumulates in the cells of the malaria parasites and prevents digestion of their host's hemoglobin; it may also possibly disrupt the parasite's ribonucleotide metabolism. *See also* **acridine**.



chlorosome a small compartment found in photosynthetic Chlorobiaceae bacteria. It contains **bacteriochlorophyll** *c* and is attached to the cytoplasmic membrane.

chlorosulfolipid a class of **sulfolipid** found in the alga, *Ochramonas danica*. They are based on *n*-docosane-1,14-diol disulfate; chlorine atoms have been located at C-2, C-13, C-15, and C-16.

chlorpromazine 2-chloro-10-(3-dimethylaminopropyl)phenothiazine; a **neuroleptic** drug with sedative and antiemetic actions. It acts as an antagonist at dopaminergic (D_2), α-adrenergic, and many other receptors (*see* **adrenoceptor**). It was formerly classed as a **major tranquillizer**, a term now deprecated. Largactil is one proprietary name of the hydrochloride.



Cho *symbol for* a residue of choline.

CHO *abbr. for* Chinese hamster ovary (applied to cell cultures derived from this organ).

chole+ *or (before a vowel)* **chol+** *comb. form* denoting bile.

cholecalciferol *or* **calciol** *the recommended trivial name for* vitamin D_3; (5*Z*,7*E*)-(3*S*)-9,10-seco-5,7,10(19)-cholestatrien-3-ol. It is formed in skin by UV-irradiation of 7-dehydrocholesterol, and is metabolized to 1α,25-dihydroxycholecalciferol (calcitriol). The latter affects the absorption of calcium from the gastrointestinal tract and the metabolism of calcium in bone. *See* **vitamin D**.



cholecalcin an intracellular calcium-binding protein.

cholecystokinin *abbr.*: CCK; *formerly called* cholecystokinin–pancreozymin (*abbr.*: CCK-PZ); a peptide hormone from **I cells** of the duodenum and proximal jejunum of mammals, also present in most parts of the brain and in the neurons of the gastrointestinal tract. It is identical with **pancreozymin**. The sequence of human cholecystokinin is

KAPSGRMSIVKNLQNLDPSHRISDRDY(-SO$_3$)MGWMDF-NH$_2$.

Sulfation of the tyrosine is essential for activity. Highly heterogeneous, the various species are known as CCK-39, CCK-33 (e.g. human), CCK-12, CCK-8, CCK-4, etc. and are truncated from the N terminus. Their common C-terminal tetrapeptide amide sequence is identical to that in which the functional activity of **gastrin** largely resides. CCK is released by entry of food into the duodenum; it causes contraction of the gall bladder and secretion of enzyme precursors from pancreatic acinar tissue. It is also a neurotransmitter and decreases appetite.

cholecystokinin receptor either of two G-protein-associated receptors (called CCK-A and CCK-B) that bind the peptide hormone **cholecystokinin** (CCK) and stimulate phospholipasae C. CCK-A is present mostly in the alimentary tract and preferentially binds the sulfated form of CCK-8. CCK-B is widely distributed in the brain, binds both the sulfated and unsulfated forms of CCK-8, CCK-4, and gastrin.

choleragen *(sometimes) an alternative name for* **cholera toxin**.

choleragenoid a 57 kDa protein that occurs naturally in the cell-free culture fluid of *Vibrio cholerae* and is immunologically almost indistinguishable from **cholera toxin** but is nontoxic. It consists of the pentamer of the B subunit of the toxin without its A subunit.

cholera toxin *or* **choleragen** the antigenic and potently diarrhoeagenic **enterotoxin** produced by *Vibrio cholerae*. Pathogenic strains secrete the toxin, which is an 84 kDa multimeric protein of exceptional stability with two subunits: an A subunit that consists of an α (22 kDa) and a β (5 kDa) chain linked by a single disulfide bond; and a B subunit consisting of four to six noncovalently associated β chains (11.5 kDa each). Binding of the toxin to its receptor ganglioside (G$_{M1}$) on sensitive cells occurs via the B subunit; the A subunit then activates cellular adenylate cyclase; together with cellular **ADP-ribosylation factor** it constitutes an **ADP-ribosyltransferase**, which transfers ADP-ribose to the **G-protein** α_s subunit, inhibiting its GTPase and converting it to an irreversible activator of adenylate cyclase.

cholestane the fully saturated carbon skeleton from which **cholesterol** is structurally derived; the configuration at C-5 can be *α* or *β*; 5*β*-cholestane is known as **coprostane**.



5*β*-cholestane

cholestanol 3*β*,5*α*-cholestan-3-ol; dihydrocholesterol; 3*β*-hydroxycholestane; a steroid that occurs in human feces, gallstones, and in eggs.



cholestanol

cholestasis the arrest (stasis) or impairment of bile flow. It may originate intrahepatically, due to hepatocellular defects (usually in the secretion of bile acids into the bile canaliculi), or extrahepatically, often due to obstruction of the bile duct by calculi. The former variety are often familial.

cholesteric of, relating to, or resembling cholesterol or a derivative of cholesterol. *See also* **liquid crystal**.

cholesterol cholest-5-en-3*β*-ol; the principal sterol of vertebrates and the precursor of many steroids, including bile acids and steroid hormones. It is found in all animal tissues, especially brain and spinal cord, in the bile, and in gallstones, being a component of the plasma membrane lipid bilayer. Both cholesterol and cholesterol esters are present in plasma lipoproteins and excessive levels in the plasma are implicated in atherogenesis. It is synthesized from acetyl-CoA via hydroxymethylglutaryl-CoA and squalene, by enzymes in the cytosol (acetyl-CoA → mevalonate), peroxisomes (mevalonate → farnesyl pyrophosphate), and endoplasmic reticulum (farnesyl pyrophosphate → cholesterol). Deficiency of cholesterol occurs in Smith–Lemli–Opitz syndrome. Cholesterol accumulates in hypercholesterolemia, cholesterol ester storage disease, Wolman disease, and some forms of Niemann–Pick disease.



cholesterol acyltransferase *see* **sterol *O*-acyltransferase**.

cholesterol desmolase *see* **cholesterol monooxygenase**.

cholesterol ester storage disease an autosomal recessive disease, sometimes not detected until adulthood, in which there is widespread deposition of cholesterol esters and triacylglycerols in tissues. It is associated with a relatively common mutation in the gene for lysosomal acid lipase, which has ≈5% of the activity of the wild type. *See* **acid lipase**.

cholesterol ester transfer protein *see* **CETP**.

cholesterol 7*α*-hydroxylase *see* **cholesterol 7*α*-monooxygenase**.

cholesterol 7*α*-monooxygenase EC 1.14.13.17; *other names*: cholesterol 7*α*-hydroxylase; cytochrome P450 VII; a cytochrome P450 enzyme that catalyses the hydroxylation of cholesterol to form 7*α*-cholesterol. NADPH and dioxygen are reactants, NADP$^+$ and H$_2$O being formed. This is the first step in the biosynthesis of bile acids from cholesterol and is rate-limiting.

cholesterol monooxygenase (side-chain cleaving) EC 1.14.15.6; *systematic name*: cholesterol,reduced-adrenal-ferredoxin:oxygen oxidoreductase (side-chain-cleaving); *other names*: CYPiiA cholesterol desmolase; cholesterol side-chain cleavage enzyme; cytochrome P450$_{scc}$; a cytochrome P450 enzyme that in association with adrenodoxin and adrenodoxin reductase catalyses the formation of pregnenolone from cholesterol, with release of 4-methylpentanal and H$_2$O. An integral membrane protein of the inner mitochondrial membrane, it is phosphorylated and activated by cAMP released in response to ACTH during the biosynthesis of steroid hormones from cholesterol in the adrenal cortex, gonads, and placenta. The reaction involves an oxidation by dioxygen, reduced adrenal ferredoxin being oxidized in the process. Enzyme activity is dependent on the entry of cholesterol into the mitochondrial matrix, a process that is facilitated by **StAR**.

cholesterol side-chain cleavage enzyme *see* **cholesterol monooxygenase (side-chain cleaving)**.

cholesteryl ester transfer protein *see* **CETP**.

cholestyramine resin *proprietary name*: Dowex 1-X2-Cl; a basic anion-exchange resin that consists predominantly of polystyrene trimethylbenzylammonium chloride. If administered orally, it exchanges anions of chloride with those of intestinal bile salts, which are then excreted as an insoluble complex. The resulting reduction in cholesterol absorption culminates in reduced circulating levels of low-density lipoproteins (LDLs), hence its therapeutic application in relieving hyperlipidemia and LDL-induced hypercholesterolemia.

cholic acid $3\alpha,7\alpha,12\alpha$-trihydroxy-5β-cholan-24-oic acid; a metabolic derivative of cholesterol, produced in the liver and secreted as a **bile acid**. It is used as a detergent, as the sodium salt; aggregation number 2, CMC 9–15 mM.



choline *symbol*: Cho; *abbr*.: Ch; *N*,*N*,*N*-trimethylethanolammonium (ion); 2-hydroxyethyltrimethylammonium (ion); 2-hydroxy-*N*,*N*,*N*-trimethylethanaminium; $(CH_3)_3N^+–CH_2–\ CH_2–OH$. An amino alcohol that functions as a methyl group donor in metabolism; it also occurs in the neurotransmitter acetylcholine and in some phospholipids. It is considered to be an essential dietary factor for humans.

choline acetyltransferase EC 2.3.1.6; *recommended name*: choline *O*-acetyltransferase; *systematic name*: acetyl-CoA:choline *O*-acetyltransferase. An enzyme that catalyses the reaction between acetyl-CoA and choline to form *O*-acetylcholine and CoA. It is instrumental in the synthesis of the neurotransmitter acetylcholine. *See also* **cholinoceptor**.

choline kinase EC 2.7.1.32; an enzyme that catalyses the phosphorylation by ATP of choline to form *O*-phosphocholine and ADP. Phosphocholine (choline phosphate) is an important intermediate in phospholipid biosynthesis, reacting with CTP to form CDP-choline. *See also* **choline-phosphate cytidylyltransferase**.

choline-phosphate cytidylyltransferase EC 2.7.7.15; *systematic name*: CTP:choline-phosphate cytidylyltransferase; *other name*: phosphorylcholine transferase. An enzyme that catalyses the formation of **cytidine(5′)diphosphocholine** (CDPcholine) from CTP and choline phosphate with release of pyrophosphate.

cholinergic describing nerve fibres that, when activated, release acetylcholine or an acetylcholine-like substance from their endings. *Compare* **adrenergic**, **peptidergic**, **purinergic**. *See also* **cholinoceptor**.

cholinesterase **1** *recommended name for* EC 3.1.1.8; *other names*: choline esterase II, pseudocholinesterase, butyrylcholinesterase. A glycoprotein homotetramer (gene locus at 3q26.1-q26.2, encodes 579 amino acids) that hydrolyses a variety of choline esters to choline and a carboxylic acid. It is found in most tissues including liver and brain. Its function is unknown. Serum activity is decreased in infancy, pregnancy, liver disease, thyroid deficiency, malnutrition, or as a result of gene mutation. In humans, individuals with abnormally low activity of cholinesterase fail to hydrolyse succinylcholine, used as a muscle relaxant in anesthesia with procaine and cocaine. They may suffer from procaine toxicity, prolonged succinylcholine apnea, and cocaine toxicity. The gene (E_1) encoding the enzyme can exist in at least five allelic forms, the normal ($E_1{}^u$), and four variants, $E_1{}^a$ (atypical), $E_1{}^f$ (fluoride resistant), $E_1{}^s$ (silent), and $E_1{}^K$, which has 66% of normal activity and is the commonest variant. Homozygotes for the atypical gene have a dibucaine-resistant enzyme that is weakly active against most enzyme substrates, and homozygotes for the silent gene exhibit minimal enzyme activity. **2** *an alternative name for* **acetylcholinesterase**.

cholinoceptor any receptor for acetylcholine on the postjunctional membrane of synaptic clefts or on terminal axons that mediates its action. There are two types: (1) **muscarinic cholinoceptors** of smooth muscle, cardiac muscle, endocrine glands, and the central nervous system at which muscarine, but not nicotine, can readily mimic the action of acetylcholine; and (2) **nicotinic cholinoceptors** of skeletal muscle, ganglia, and the central nervous system at which nicotine, but not muscarine, can readily mimic the action of acetylcholine.

Muscarinic acetylcholine receptors are G-protein-associated membrane proteins. M_1 and M_3 activate phosphoinositide-specific phospholipase C; M_2 and M_4 are negatively coupled to adenylate cyclase; M_2 also increases potassium channel conductance through the action of G-proteins.

Nicotinic acetylcholine receptors are glycosylated pentamers (i.e. α, β, γ, δ, and ε) with an intrinsic cation-permeable channel with little selectivity among cations. They respond by an extensive change in conformation that affects all subunits and leads to opening of an ion-conducting channel across the plasma membrane. *Torpedo* electric organ and embryonic muscle pentamers have $\alpha_2\beta\gamma\delta$, adult mammalian muscle $\alpha_2\beta\delta\varepsilon$, and mammalian neurons $\alpha_2\beta_3$ stoichiometry; each subunit contains four transmembrane segments. Bungarotoxin is a selective antagonist. The neuronal receptor has two subunits (α and non-α).

cholinomimetic describing a drug with an acetylcholine-like action.

cholyl the acyl group derived from **cholic acid**.

chondrioma *or* **chondriome** **1** the entire mitochondrial content of a cell. **2** all the hereditary determinants that are localized in mitochondria.

chondriosome *a former name for* **mitochondrion**.

chondroblast a cell that secretes the matrix of **cartilage**.

chondrocalcin the C-terminal peptide formed from amino acids 1173–1418 of human procollagen α_1.

chondroclast a large, multinucleate cell that digests the cartilage matrix.

chondrocyte a cartilage cell, formed from a **chondroblast**.

chondroitinase *see* ***N*-acetylgalactosamine-4-sulfatase**, ***N*-acetylgalactosamine-6-sulfatase**.

chondroitinsulfatase *see* ***N*-acetylgalactosamine-4-sulfatase**, ***N*-acetylgalactosamine-6-sulfatase**, **iduronate-2-sulfatase**.

chondroitin sulfate any member of a group of 10–60 kDa glycosaminoglycans, widely distributed in cartilage and other mammalian connective tissues, the repeat units of which consist of *β*(1–4)-linked D-glucuronyl*β*(1–3)*N*-acetyl-D-galactosamine sulfate. They usually occur linked to a protein to form proteoglycans. Two subgroups exist, one in which the sulfate is on the 4-position (chondroitin sulfate A) and the second in which it is in the 6-position (chondroitin sulfate C). They often are polydisperse and often differ in the degree of sulfation from tissue to tissue. The chains of repeating disaccharide are covalently linked to the side chains of serine residues in the polypeptide backbone of a protein by a glycosidic attachment through the trisaccharide unit galactosyl–galactosyl–xylosyl. Chondroitin sulfate B is more usually known as **dermatan sulfate**.

chondromodulin a 28 kDA glycoprotein released by proteolytic cleavage of a larger precursor and localized in the interterritorial matrix of avascular zones of epiphyseal cartilage. It is abundant in fetal cartilage and inhibits angiogenesis. It is not produced in chondrosarcoma.

chondrosamine *former name for* the D-enantiomer of **galactosamine**, reflecting its presence in **chondrosine**.

chondrosine the disaccharide 2-amino-2-deoxy-3-*O*-*β*-D-glucopyranuronosyl-D-galactopyranose; *condensed form*: Glc*p*A(*β*1-3)GalN. In sulfated form it is the core unit of **chondroitin sulfate**.



chopper 1 a device for chopping tissue e.g. the McIlwain chopper. **2** *(in optics)* a device for interrupting a light beam in a regular manner. For example, in a spectrophotometer it consists of a rotating wheel with alternate silvered and cut-out sectors that is placed in the light beam to allow the light to pass alternately through the sample and the reference cells, the photocell thereby generating an alternating current.

chordin a secreted protein of the notochord that contains cysteine-rich repeats. It binds and antagonizes **bone morphogenetic protein**.

choriocarcinoma a malignant tumour, typically occurring in the uterus, originating as a proliferation of chorionic villi. It may follow pregnancy or develop from a hydatidiform mole. **Choriogonadotropin** is an excellent marker for the presence of this tumour.

choriogonadotropin *or* **chorionic gonadotropin** *or* **choriogonadotrophin** *abbr.*: CG; *the recommended name for* a placental **glycoprotein hormone** that has the gonadotropic activities of both luteinizing hormone (LH) and follicle-stimulating hormone (FSH). It is a member of the family of glycoprotein hormones that includes LH and FSH, the β subunit being specific to choriogonadotropin. It is produced by the corpus luteum after fertilization of the ovum; the blood level rises to a detectable concentration 7–9 days after conception and CG may be detected in urine 1–2 days later, which yields a highly sensitive and specific test for pregnancy. Its administration to males causes increased secretion of testosterone; the lack of such a response indicates testicular failure. It is also a good marker for **choriocarcinoma**. It is a heterodimer of an α chain (identical with that of LH and FSH) and a β chain that confers specificity.

choriomammotropin *or* **chorionic somatomammotropin** *or* **choriomammotrophin** *other name*: placental lactogen (*abbr.*: PL); a placental hormone similar in action to **somatotropin** and **prolactin**. It shows ≈85% homology with the former and ≈13% with the latter. It is partly responsible for the rise in insulin-like growth factor I (IGF-I) level observed in pregnancy. Its absence does not affect fetal growth, pregnancy, or lactation. The gene at 17q22-q24 is near those for somatotropin and prolactin.

chorion 1 the highly vascular outermost embryonic membrane of higher vertebrates. In placental animals it has a villous part that enters the placenta. **2** the membrane of an animal egg, especially the hardened external membrane of an insect's egg.

chorionic gonadotropin *or* **chorionic gonadotrophin** *an alternative name for* **choriogonadotropin**.

chorionic somatomammotropin *or* **chorionic somatomammotrophin** *an alternative name for* **choriomammotropin**.

chorion villus sampling *abbr.*: CVS; a technique for a biopsy of the chorion frondosum during pregnancy to obtain fetal tissue for prenatal diagnosis.

chorismate the anion of (3*R*-*trans*)-3-[(1-carboxyethenyl)oxy]-4-hydroxy-1,5-cyclohexadiene-1-carboxylic acid; the unsymmetrical ether derived from phospho*enol*pyruvate and 5-phosphoshikimic acid (*see* **shikimate pathway**); it is formed as an intermediate in the biosynthesis of aromatic amino acids and many other compounds. The common pathway to aromatic amino acids bifurcates at chorismate: one branch, the prephenate pathway, leads to phenylalanine and tyrosine; the other branch, the anthranilate pathway, leads to tryptophan. There are many other branchpoints in the shikimate pathway. (Note: the configurations can be stated as 3*R*,4*R*.)



chorismate mutase EC 5.4.99.5; an enzyme that catalyses the conversion of chorismate to prephenate. It is the first enzyme in the branch of the **shikimate pathway** that leads to synthesis of phenylalanine. Isoenzymes are found in cytoplasm and in chloroplasts. The chloroplast isoenzyme is activated by tryptophan and inhibited by phenylalanine and tyrosine. For an example see **prephenate dehydratase**.

chorismate synthase EC 4.6.1.4; *other name*: 5-*enol*pyruvylshikimate-3-phosphate phospholyase; an enzyme that catalyses the formation of chorismate from 5-*O*-(1-carboxyvinyl)-3-phosphoshikimate with release of orthophosphate. *See also* **shikimate pathway**.

CHRAC *abbr. for* chromatin accessibility complex; an ATP-dependent chromatin remodelling complex that causes *cis*-displacement or sliding of a nucleosome along a stretch of DNA.

Christmas disease *or* **hemophilia B** a sex-linked inherited disorder of **blood coagulation** due to a deficiency of coagulation factor IX (Christmas factor) activity in the blood. It occurs in humans, dogs, cats, and other species, but is less common than classical **hemophilia** (hemophilia A). [After S. Christmas, the first described sufferer of the disease.]

Christmas factor *an alternative name for* **factor IX**. *See also* **blood coagulation**, **Christmas disease**.

chrom+ *see* **chromo+**.

chromacin the 22-residue polypeptide that constitutes residues 176 to 197 of chromogranin A. It is bacteriolytic and antifungal. *See* **chromogranin**.

chromaffin *or* **chromaffine** describing a tissue, cell, or subcellular granule that stains deeply with chromium salts.

chromaffin tissue a tissue made up of modified neural cells (chromaffin cells) that synthesize, store, and secrete catecholamines. The catecholamines are stored in special subcellular organelles, **chromaffin granules**, ready for release. Chromaffin tissue is found in all vertebrates, at various bodily locations but especially in the medulla of the adrenal gland. Tumours of this tissue, usually in the adrenal medulla, cause a syndrome of intermittent hypertension and excessive catecholamine secretion.

chromat+ *see* **chromato+**.

chromatic of, or related to, colour.

chromatid one of the two daughter strands of a duplicated chromosome that become apparent between early prophase and metaphase in mitosis and between diplotene and second metaphase in meiosis.

chromatin the complex of a double-stranded DNA fibre with histone and nonhistone proteins that makes up the **chromosomes** of the eukaryotic nucleus during interphase. It stains strongly with basic dyes. Some parts of the chromosomes are highly dispersed (called **euchromatin**) and other parts are highly condensed (called **heterochromatin**). Chromatin is made up of repeating units, each unit consisting of some 147 DNA base pairs and two each of **histones** H2A, H2B, H3, and H4 (thus forming a histone octamer); most of the DNA is wound around the outside of a core of histones to form **nucleosomes**. Adjacent nucleosomes are joined by a stretch of linker DNA (variable in length but usually ≈55 bp) to which a molecule of histone H1 binds, thereby contributing flexibility to the **chromatin fibre**.

chromatin accessibility complex *see* **CHRAC**.

chromatin assembly factor 1 *see* **CAF1**.

chromatin body a body, containing ribosomal DNA, that occurs during early oogenesis in some water beetles. It disappears at about the time of vitellogenesis and its contents become dispersed in the nuclear interior.

chromatin compaction the degree of packing of nucleosomes in **chromatin**. Increased compaction impedes accessibility to the nucleosomal DNA and represses its genomic activity, whereas decompaction increases the accessibility of DNA for transcription or replication. The conformational changes are facilitated by enzymes that act on the histones (kinases, methylases, acetylases) or on DNA (methylases), and by nucleosome-remodelling complexes and high-mobility group proteins (e.g. HMGN), which bind nucleosomes.

chromatin fingerprinting a two-dimensional electrophoretic technique for simultaneously mapping the total distributions of DNA sizes, protein compositions, and nuclease-mediated precursor–product relationships present in heterogeneous populations of mono- and polynucleosomes. Chromatin, partially digested with micrococcal nuclease, is electrophoretically separated in the first dimension in the presence of inactive DNase I. Subsequently the enzyme is activated by incubating the gel in a magnesium ion-containing buffer and the histones are then separated by electrophoresis in the second dimension.

chromatin immunoprecipitation *abbr.*: ChIP; a method used to demonstrate the association between transcription factors or other DNA-binding proteins and specific regions of genomic DNA. Chromatin is isolated from preparations of nuclei, chemically cross-linked, and sheared to provide short fragments. Antibodies are used to immunoprecipitate the specific DNA-binding protein and with it the fragment of DNA to which it is bound. Polymerase chain reaction (PCR) is then used to identify the presence of specific DNA fragments.

chromatin silencing the conversion of large regions of chromosomes into a form that does not permit transcription. Transcriptional silencers are required for initiation of chromatin silencing, a state that is correlated with decreased histone acetylation.

chromato+ *or (before a vowel)* **chromat+** *comb. form* **1** denoting colour or coloured. **2** denoting **chromatin**. **3** indicating **chromatogram**, **chromatograph**, or **chromatography**.

chromatofocusing a column-chromatographic technique of high capacity and high selectivity for separating proteins according to their isoelectric points. A pH gradient is formed in a column containing an anion exchanger, by use of a special eluting buffer containing a large number of differently charged species. Proteins emerge from the column as a series of sharply focused zones in descending order of their p*I* values, with peak widths in the range 0.04–0.05 pH unit.

chromatogram the result of a chromatographic separation. It may be directly visible, e.g. in the form of a column or strip of material, or, after processing of data, take the form of a graph.

chromatograph **1** to effect a separation by **chromatography**. **2** an apparatus with which to carry out a particular form of chromatography. **—chromatographic** *adj.*; **chromatographically** *adv.*

chromatography any technique, analytical or preparative, for separating the components of a mixture by differential adsorption of compounds to adsorbents, partition between stationary and mobile immiscible phases, ion exchange, or a combination of these. *See* individual entries for the many different types of chromatography; these include: adsorption, affinity, affinity-elution, ampholyte-displacement, argentation, ascending, biospecific-elution, charge-transfer, circular, countercurrent, covalent, descending, dye-ligand, electro, exclusion, frontal, gas, gas–liquid, gel-filtration, gel-permeation, high-performance liquid-affinity, high-performance liquid, high-pressure liquid, hydrophobic, ion-exchange, ion-exclusion, ionic-interaction, ion-moderated partition, ligand-mediated, liquid, liquid–liquid, metal-chelate affinity, molecular-exclusion, molecular-sieve, negative, paper, partition, permeation, positive, pseudoaffinity, reverse(d)-phase, salting-out, sievorptive, steric-exclusion, subunit-exchange, thermal-elution, thin-layer, triazine-dye affinity.

chromatophore **1** a pigment-containing cell, especially one in the integument of an animal, that is capable of changing the apparent skin colour by contracting or expanding. **2** any of the particles isolated from photosynthetic organisms that contain photosynthetic pigments, e.g. a **chromoplast**, or membrane fragments from photosynthetic bacteria.

chromatopile a stack of filter papers, of the same diameter, that is compressed in a chromatographic column in large-scale separations.

chromatoplate the plate that is covered with the support during **thin-layer chromatography**.

chromatosome a **nucleosome** lacking the linker DNA.

+chrome *comb. form* denoting colour, coloured, or pigment.

chromium *symbol*: Cr; the element of proton number 24. It is a paramagnetic, metallic transition element of group 6 of the IUPAC **periodic table**, with oxidation states of II, III, and IV. Natural chromium has a relative atomic mass of 51.966 and is a mixture of four stable nuclides with nucleon numbers of 50, 52, 53, and 54, the predominant one being chromium-52 (relative abundance 83.789 atom percent). A number of artificial radioactive nuclides are known, of which **chromium-51** is the longest lived. Chromium has an abundance of about 0.02% of the igneous rocks of the earth and it occurs in nature exclusively in the combined form, the mixed oxide chromite $Fe_2Cr_2O_4$ being the chief ore. It is an essential dietary trace metal, but functions in the body primarily as a component of **glucose-tolerance factor**, the chief symptom of experimental chromium deficiency in animals being impaired glucose tolerance.

chromium-51 the artificial radioactive nuclide of chromium, $^{51}_{24}$C. It decays by electron capture, 9.8% of nuclei emitting γ-radiation (0.32 MeV); it also emits X-rays (0.005 MeV, 22%) but no β-particles; it has a half-life of 27.7 days. It is used as chromate for labelling blood cells, and as the 1:1 complex of Cr^{2+} with EDTA for measuring glomerular filtration rate.

chromo+ *or (before a vowel)* **chrom+** *comb. form* **1** denoting colour, coloured, or pigment. **2** indicating **chromium**.

chromobindin *see* **annexin I**, **annexin II**, **annexin IV**, **annexin VI**.

chromodomain a protein domain that recognizes the C-terminal tails of nucleosomal histones that contain specifically methylated lysine residues. It consists of an alpha helix and three beta strands. Chromodomains are present in the HP1 family of heterochromatin-associated proteins, in diverse chromatin remodelling factors (e.g. Mi2 of **NURD**), and in histone methyltransferase.

chromogen **1** the colourless precursor of a dye or pigment that is converted into the dye or pigment, e.g. by oxidation. **2** a compound containing a **chromophore** that is not itself coloured but becomes so when an auxochromic group (*see* **auxochrome**) is introduced into the molecule. **3** any microorganism that produces pigment.

chromogenic **1** producing colour. **2** of, or pertaining to, a **chromogen**.

chromogenic substrate a substrate that, when acted on by an enzyme, gives rise to a coloured product.

chromogranin *abbr.*: Cg; either of two soluble proteins, originally discovered in bovine chromaffin granules (*see* **chromaffin tissue**), but now known to be widely distributed in endocrine (including neuroendocrine) tissues. They are designated chromogranin A (CgA) and chromogranin B (CgB; *also called* **secretogranin I**). Both proteins are acidic (pI 4.5–5.0), but similarity is limited except in the N- and C-terminal regions, and there is a lack of immunological reactivity. Both have been detected immunologically in various mammals, amphibians, birds, and fishes; CgA also occurs in *Drosophila*. CgA is a 430 amino acid Ca^{2+}-binding glycoprotein; it is hydrophilic, with no hydrophobic stretches, and is co-secreted with many hormones from, e.g., pancreas and thyroid C cells. Both proteins have **dibasic cleavage sites** for endopeptidases, the action of which leads to the formation of several active peptides: CgA yields **parastatin** (porcine $\mathrm{CgA}_{347–419}$), an inhibitor of low calcium-stimulated parathyroid cell secretion; **pancreastatin** (porcine $\mathrm{CgA}_{240–288}$), an inhibitor of glucose-induced insulin release from the pancreas; **chromostatin** (bovine $\mathrm{CgA}_{124–143}$), an inhibitor of catecholamine release by chromaffin cells; **vasostatin** (bovine $\mathrm{CgA}_{1–76}$); **beta-granin** (bovine $\mathrm{CgA}_{1–114}$), an inhibitor of parahormone secretion; and a peptide WE-14. CgB is co-secreted from adrenal medulla with catecholamines, from sympathetic nerve with norepinephrine, and from some cell lines; proteolytic cleavage releases several peptides of unknown function.

chromomere any of the beadlike concentrations of **chromatin** that are arranged linearly along a **chromosome**.

chromonema (*pl.* **chromonemata**) *cytological term for* **1** all of the threads which make up the **nuclear reticulum**. **2** any of the smallest strands of DNA in a chromosome or chromatid. **3** a twisted chromatid thread within the chromosome.

chromophore any functional grouping within a molecular entity that gives rise to the colour (or characteristic absorption spectrum) of the substance.

chromoplast any yellow, orange, or red **plastid** containing carotenoid pigments but not chlorophyll, the colour depending on the relative amounts of carotenoids and xanthophylls present. Chromoplasts give the yellow to red colours of many flowers (e.g. daffodil), fruits (e.g. tomato), and some roots (e.g. carrot). They synthesize and store carotenoids in their membranes and when loaded with carotenoids are called **carotenoid bodies**. In ripening fruit tissues these are specifically associated with fibrillin-type proteins.

chromoprotein any of a class of proteins that contain a colour-producing group or **chromophore**. Both chlorophylls and carotenoids exist in chloroplasts as chromoproteins.

chromosomal inversion *see* **inversion** (def. 3).

chromosomal translocation the exchange of segments of non-homologous chromosomes. Translocations are apparent when the chromosome number is correct, but two chromosomes have abnormal sizes and banding patterns. Some are associated with malignancy.

chromosome a structure composed of a very long molecule of **DNA** (in humans 50–250 Mb long) and associated proteins (e.g. **histones**) that carries hereditary information. Chromosomes are especially evident in plant or animal cells undergoing mitosis or meiosis, where each chromosome becomes condensed into a compact, readily visible thread. In nondividing cells chromosomes typically assume a more dispersed form called **chromatin**. The number of chromosomes is characteristic for the species concerned. In a bacterium only one chromosome is evident as the cell is about to divide. This is a circular molecule of DNA, 4.6 Mb long in *E. coli*, with attached proteins. After DNA replication, the two new chromosomes attach to a specialized site on the bacterial plasma membrane for segregation to the two daughter cells. Mitochondria and chloroplasts contain several copies of a much smaller circular DNA molecule with some attached proteins. **—chromosomal** *adj.*

chromosome band any of numerous transverse bands along a chromosome that show differential intensity of staining. The pattern of such bands is highly characteristic for each chromosome of a given species, and is thus useful for large-scale physical mapping. The bands are an effect of staining, and were thought to be related to regional base composition. However, it is now believed that the intensity of staining depends on the packing density of the chromatin: more tightly packed regions contain a greater density of DNA to take up stain.

chromosome mutation a type of **mutation** (def. 1) involving alteration(s) in chromosome structure, including breakage and loss of chromosomal segments. Some deletions are associated with human genetic diseases (e.g. in chromosome 4, giving rise to Charcot–Marie–Tooth disease, and chromosome 22, leading to DiGeorge syndrome). *See also* **chromosomal translocation**, **inversion** (def. 3).

chromosome walking a method used to identify which clone in a gene bank contains a desired gene or sequence that cannot easily be selected for. The gene bank must contain the entire DNA sequence of the chromosome as a series of overlapping fragments. A series of **colony hybridizations** is carried out, starting with a cloned gene that has already been identified and that is known to be on the same chromosome as the desired gene. This identified gene is used as a probe to pick out clones containing adjacent sequences. These are then used in turn as probes to identify clones carrying sequences adjacent to them, and so on. At each round of hybridization one 'walks' further along the chromosome from the identified gene.

chromostatin a 20-amino-acid peptide that can be released *in vitro* by the proteolytic cleavage of **chromogranin** A. It potently inhibits catecholamine release by **chromaffin** cells induced by carbamoylcholine or by depolarizing K^+ concentration, and it inhibits secretagogue-induced calcium influx. Its physiological status is uncertain – it is not flanked by **dibasic cleavage sites** in the precursor.

chronic **1** continuing over a long time; repeatedly recurring. **2** *(of a disease)* developing slowly or lasting for a long time.

chronic external ophthalmoplegia *an alternative name for* **Kearns–Sayre syndrome**.

chronic granulomatous disease a rare condition characterized by suppurative bacterial and fungal infections starting in early childhood. Phagocytic cells from patients exhibit normal chemotaxis, degranulation, and phagocytosis but do not experience a respiratory burst that generates superoxide radical and other antimicrobial reactive oxygen species. This defect is caused by a hereditary dysfunction in any of four protein components of the NADPH oxidase complex.

chrono+ *or (before a vowel)* **chron+** *comb. form* denoting time.

chronobiochemistry the branch of biochemistry concerned with the biochemical aspects of **chronobiology**, the study of the inherent rhythmicity or periodicity of living organisms and their activities.

chrysolamarin *see* **callose**.

chrysotherapy the use of gold-containing substances in the treatment of disease.

CHS *(in clinical biochemistry) abbr. for* cholinesterase (def. 1).

ChTX *abbr. for* charybdotoxin.

CHX10 a human homeodomain transcription factor (361 amino acids) that is highly conserved in mammals and abundantly expressed in the adult retina. Homozygous null mutations affect only the eye and produce microphthalmia, cataracts, and blindness.

chyle the white lymph found in the lymph vessels of the intestine (lacteals) during the digestion of fats. It contains globules with a high fat content. *See also* **chylomicron**.

chylomicron a large lipoprotein particle, of molecular mass up to 10^7 kDa, measuring up to 100 nm in diameter, and of density < 1.006. Chylomicrons appear in plasma during absorption of a fat-containing meal and normally disappear by 12–15 hours. Their approximate composition (% by weight) is 2% cholesterol, unesterified; 5% cholesterol, esterified; 7% phospholipid; 84% triacylglycerol; 2% protein. Their apolipoprotein composition (% by weight total apolipoprotein) is 7.4% A-I; 4.2% A-II; 22.5% B-48; 66% C-I + C-II + C-III. Chylomicrons are formed in the mucosa of the small intestine, and contain mostly triacylglycerols re-esterified in the mucosal cells from dietary long-chain fatty acids associated with apolipoproteins. They then enter the lymphatic capillaries (lacteals) of the intestinal villi, and thence the bloodstream. Binding to lipoprotein lipase on the capillary endothelial surface deprives them of triglycerides, and converts them into chylomicron remnants. They are the vehicle by which fat and fat-soluble vitamins are absorbed. **Hyperchylomicronemia** results from deficiency of lipoprotein lipase. **Chylomicron retention disease** is a defect in secretion of chylomicrons characterized by fat malabsorption, absence of chylomicrons in plasma after ingestion of fat, and sometimes acanthocytosis and neurological abnormalities. There is accumulation in enterocytes of chylomicron-like particles that are rich in ApoB-48 (*see* **apolipoprotein B**).

chylomicron remnant a particle derived by the impoverishment of a **chylomicron** of triacylglycerols (triglycerides) by the action of lipoprotein lipase. Such remnants are enriched in cholesterol ester and contain less apolipoprotein A and apolipoprotein C than chylomicrons. In the liver, hepatic lipase degrades the remaining triacylglycerols, and remnants bind, through their apolipoprotein E, to low-density lipoprotein (LDL) receptors and to LRP in coated pits. They are then endocytosed and degraded in lysosomes. Chylomicron remnants accumulate – along with very-low-density lipoprotein (VLDL) remnants – in remnant (or type III) hyperlipidemia.

chymase EC 3.4.21.39; *other names*: mast cell protease I; skeletal muscle (SK) protease. An enzyme that catalyses preferential cleavage of the bonds: Phe-|-Xaa > Tyr-|-Xaa > Trp-|-Xaa > Leu-|-Xaa. It is a trypsin-like serine proteinase, and a homologue of chymotrypsin; it is found in mast cell granules (heart, lung, etc.).

chyme the semifluid mass of partially digested food that passes through the pylorus of the stomach into the small intestine.

chymopapain EC 3.4.22.6; *other name*: papaya proteinase II; the major endopeptidase enzyme of papaya (*Carica papaya*) latex; its specificity is similar to that of **papain**.

chymosin *or* **rennin** EC 3.4.23.4; an aspartic proteinase enzyme that cleaves a single bond in κ **casein** (Ser-Phe^{105}-|-Met-Ala) and is responsible for clotting of milk. It is produced from a precursor in the mucosa of the fourth stomach of calves. It is now produced by cDNA technology. (*Note*: use of the synonym rennin is now deprecated because of possible confusion with **renin**.)

chymotrypsin a serine endopeptidase, EC 3.4.21.1, formed from the proenzyme **chymotrypsinogen** by the action of trypsin. In vertebrates, chymotrypsins are contained in **pancreatic juice**, and hydrolyse protein in the small intestine. Chymotrypsinogen is synthesized in the acinar cells of the exocrine pancreas and stored in **zymogen** granules until released. **Chymotrypsin A** is formed from bovine and porcine chymotrypsinogen A. It hydrolyses peptides, amides, and esters, preferentially at the carbonyl end of Tyr, Trp, Phe, and Leu residues. **Chymotrypsin B**, formed from chymotrypsinogen B, is homologous with chymotrypsin A. **Chymotrypsin C**, EC 3.4.21.2, is formed from porcine chymotrypsinogen C and from bovine subunit II of procarboxypeptidase A. It preferentially cleaves at the carbonyl end of Leu, Tyr, Phe, Met, Trp, Gln, and Asn residues. Enzymes homologous to and with similar specificities to chymotrypsin have been isolated from many species. Chymotrypsinogens are synthesized as a single 245-residue polypeptide chain cross-linked by five disulfide bonds. This is fully activated when the bond between Arg^{15} and Ile^{16} is cleaved by trypsin to yield π-chymotrypsin; subsequent autocatalytic cleavage of more peptide bonds (to remove 14–15, 147–148) converts it into α-chymotrypsin. Amino acids 1–13 form the A-chain, 16–146 form the B-chain, and 149–245 form the C-chain of chymotrypsin, the three chains being covalently linked by disulfide bonds. The mechanism involves a **charge-relay system** of His^{57}, Asp^{102}, and Ser^{195}. Chymotrypsin is more active than trypsin against certain esters, e.g. *N*-acetyl-L-tyrosine ethyl ester. Chymotrypsin binds α_1-antitrypsin.

chymotrypsinogen *see* **chymotrypsin**.

chymotryptic of, or relating to, **chymotrypsin**; **chymotryptic digestion** is the partial hydrolysis of a protein by chymotrypsin.

cI857 a temperature-sensitive mutant of **lambda repressor** that has normal activity at 28°C but is denatured at 42°C. Bacteriophage lambda lysogens carrying this mutation can be induced by exposing them to a temperature of 42°C. *See* **induction**.

Ci 1 *symbol for* curie. **2** *abbr. for* cubitus interruptus.

cI, cII, cIII *symbols for* genes in bacteriophage lambda that give clear plaques when mutated. *cI* encodes the **lambda repressor**, which blocks the activities of lytic promoters. The *cII* gene product is necessary for transcription of repressor from the P_{RE} promoter and of the *int* gene. The *cIII* gene product inhibits cII proteolysis.

CI *abbr. for* Colour Index (especially as a prefix to the identifying number for a particular dye or stain).

CIDNP *abbr. for* chemically induced dynamic nuclear polarization.

CIE *abbr. for* counterimmunoelectrophoresis.

ciliary neurotrophic factor *abbr.*: CNTF; a protein that promotes survival of neurons of the parasympathetic ciliary ganglion and elsewhere. The richest sources of CNTF are Schwann cells of peripheral nerves and glial cells of the central nervous system. The **CNTF receptor** consists of a GPI-anchored α subunit, and two homologous transmembrane β subunits. Ligand binding activates JAK1 and JAK2, and STAT proteins (*see* **JAK**).

ciliatine *see* **phosphono+**.

cilium (*pl.* **cilia**) a specialized eukaryotic locomotor organelle that consists of a filiform extrusion of the cell surface. Each cilium is bounded by an extrusion of the cytoplasmic membrane, and contains a regular longitudinal array of **microtubules**, anchored basally in a **centriole**. *Compare* **flagellum**. *See* **immotile cilia syndrome**. **—ciliary** *adj.*

cimetidine *N*-cyano-*N′*-methyl-*N″*-[-2-[[(5-methyl-1*H*-imidazol-4-yl)methyl]thio]ethyl]guanidine; a competitive antagonist of histamine H_2 receptors used clinically as an anti-ulcer drug; it inhibits gastric acid secretion and reduces the output of pepsin. One proprietary name is Tagamet.



cIMP *abbr. for* cyclic IMP; *see* **inosine 3′,5′-phosphate**.

cin4 the gene for the enzyme ***trans*-cinnamate 4-monooxygenase** found in many plants.

cinchonine an alkaloid obtained from cinchona bark and possessing antimalarial properties. *See also* **quinine**.

CINEMA *abbr. for* colour interactive editor for multiple alignments; *see* **alignment editor**.

C1 inhibitor a plasma glycoprotein of molecular mass 105 kDa that is secreted primarily by the liver and acts as a serine proteinase inhibitor. It binds covalently to, and inhibits, C1r and C1s of the **complement** system. It also inhibits coagulation factors Xi and XII, and kallikrein. It shares ≈20% homology with $\alpha 1$-antitrypsin. Deletions and null mutations in the gene at 11q11-q13.1 result in a severe form of hereditary angioedema, while point mutations result in a milder form.

cinnamate the anion of 3-phenyl-2-propenoic acid; *trans*-cinnamate (3-phenyl-2*E*-propenoate) is a compound formed from phenylalanine by phenylalanine ammonia-lyase, EC 4.3.1.5; it is the precursor of ferulic and sinapic acids in the pathway for **lignin** synthesis.

***trans*-cinnamate 4-monooxygenase** *abbr.*: CA4H; EC 1.14.13.11; *systematic name*: *trans*-cinnamate,NADPH:oxygen oxidoreductase (4-hydroxylating); *other names*: cinnamic acid 4-hydroxylase; cinnamate 4-hydroxylase. An enzyme that catalyses a reaction between *trans*-cinnamate, NADPH, and dioxygen to form 4-hydroxycinnamate, $NADP^+$, and H_2O. It is an endoplasmic reticulum enzyme of high specificity – it does not act on amino acids, phenylacetate, or benzoate – and is the first enzyme in the pathway from **cinnamate** to **lignin**.

cinoxacin azolinic acid; 1-ethyl-1,4-dihydro-4-oxo[1,3]dioxolo[4,5-*g*]cinnoline-3-carboxylic acid; a **4-quinolone antibiotic** with activity against Gram-negative bacteria through the inhibition of DNA gyrase.

ciprofloxacin a fluorinated 4-**quinolone antibiotic** active against both Gram-positive and Gram-negative bacteria, chlamydias, and mycobacteria. It inhibits prokaryotic type II DNA topoisomerase.

circadian describing biological activity (e.g. behavioural, physiological, metabolic) that exhibits an endogenous periodicity of approximately 24 hours independently of any daily variation in the environment. *Compare* **diurnal**, **infradian**, **ultradian**. [From Latin *circa*, about, + *dies*, day.]

Circe effect the phenomenon underlying any physicochemical description of the action of an enzyme upon a substrate. It refers to the strong attractive forces that bind the substrate into the active site of the enzyme, where it undergoes a radical transformation of form and structure. It is named after the sorceress, Circe, who according to Greek mythology transformed the men of Odysseus into beasts.

circular birefringence the **birefringence** produced by left and right circularly polarized light.

circular chromatography a technique of paper chromatography in which the substances to be separated are allowed to travel radially from the centre of a filter-paper disk. The material is applied to the centre of the disk from which a small sector is cut out and folded down to allow it to dip into the eluting solvent.

circular chromosome a circular DNA duplex, the form taken by the chromosomes of some prokaryotic organisms, e.g. *Escherichia coli*, *Bacillus subtilis*, and *Pseudomonas aeruginosa*.

circular dichroism *abbr.*: CD; the difference in absorption of left and right circularly polarized light. The shape and magnitude of the CD curve as a function of wavelength of solutions of proteins (and other macromolecules) are sensitive to changes in conformation of these solutes. *See also* **Cotton effect**, **ellipticity**, **molecular ellipticity**, **optical rotatory dispersion**.

circular DNA any single- or double-stranded DNA molecule with a circular (but not necessarily geometrically circular) structure. If single-stranded, the circle is closed covalently, but if double-stranded, one or both strands may be open. *See also* **covalent (closed) circle of DNA**.

circularly polarized light *see* **polarized light**.

circular peptide a naturally occurring polypeptide (of 14–70 residues) whose N- and C-termini are joined by a peptide bond. It is derived from a DNA-encoded protein precursor. For example, bacteriocin AS-48 of *Enterococcus faecalis* S-48 is a circular peptide that contains 70 residues, is hydrophobic, mostly alpha-helical, and forms pores in the plasma membrane of sensitive organisms. Microcin J25 of *E. coli* contains 21 residues of a sequence unrelated to other microcins, consists mostly of beta-sheet structure, and interferes with cell division in sensitive organisms. Other examples include cyclotides of plants, and rhesus theta-defensin-1 (RTD-1) of leukocytes from *Macaca mulatta*, which contains 18 residues and three disulfide bonds, forms two beta strands, and is antibacterial.

circular permutation a linear DNA molecule whose sequence appears as if produced by cleaving circular molecules at different points. For example, circular permutations of ABCDEFG would be CDEFGAB, EFGABCD, etc.

cis *abbr.*: c; *conformational descriptor* denoting synperiplanar (use not recommended); *see* **conformation**.

cis- *abbr.*: *c*-; *prefix (in chemical nomenclature)* denoting that two specified substituents lie on the same side of a reference plane in the molecule. (*cis* means 'on this side'.) In systematic names it is denoted by the symbol *Z*. *See* ***cis–trans*** **isomerism**, ***E*/*Z*** **convention**. *Compare* ***trans-***.

CIS *abbr. for* cytokine-inducible SH2 protein; any of a family of proteins that are induced by various **cytokines** (e.g. interleukins 2 and 3, erythropoietin) and contain an SH2 domain. They bind cytokine receptors and suppress cytokine signalling through **STAT proteins**.

***cis*-acting** *(in genetics)* describing a regulatory genetic element whose effects are sensitive to its position relative to the gene being regulated, i.e. on the same molecule of DNA. Examples include bacterial **operators**.

cis* configuration** *(in genetics)* describing the configuration of two linked heterozygous genes in which both wild-type alleles occur on one of the paired homologous chromosomes while the mutant alleles occur on the other homologue; i.e. (++/*ab*). *Compare* ***trans **configuration**.

cis* isomer** *see* ***cis–trans **isomer**.

CISP *abbr. for* corticotropin-induced secreted protein; now called thrombospondin-2 (*see* **thrombospondin**).

cisplatin *cis*-diammineplatinum(II) dichloride; *cis*-diaminedichloroplatinum; a substance that interacts with, and forms cross-links between, DNA and proteins. It is used as a neoplasm inhibitor to treat solid tumours, primarily of the testis and ovary.

cisterna (*pl.* **cisternae**) **1** *(in cytology)* the flattened, saclike space enclosed between paired membranes of the **endoplasmic reticulum** and the **Golgi apparatus**. **2** *(in anatomy)* an enlarged space, such as the cisterna magna in the rear of the brain or the cisterna chyli between the crura of the diaphragm. **—cisternal** *adj.*

***cis–trans* complementation test** a genetic test to determine whether two gene mutations (*a* and *b*) occur in the same functional gene (or **cistron**). It involves comparison of heterozygotes in which the relevant mutations are in the same chromosome, i.e. in the *cis* configuration (++/*ab*), with heterozygotes in which the mutations are in separate chromosomes, i.e. the *trans* configuration (*a*+/+*b*).

cis–trans* isomer** *or (sometimes)* **geometric isomer** *or* **geometrical isomer** either of a pair of **diastereoisomers** that differ only in the positions of atoms relative to a specified reference plane in the molecules, in cases where these atoms are, or are considered as if they were, parts of a rigid structure. The two isomers are designated the *cis* isomer and the *trans* isomer when the two particular atomic groupings lie respectively on the same or on opposite sides of the reference plane. *See also* ***cis–trans **isomerism**. **—*cis–trans*-isomeric** *adj.*

cis–trans* isomerism** *or (sometimes)* **geometrical isomerism** the phenomenon of the existence of *cis–trans* isomers in general, or the occurrence of paired *cis* and *trans* isomers in a particular molecule. Atoms or groups are termed *cis* or *trans* to one another when they lie respectively on the same or on opposite sides of a reference plane identifiable as common among stereoisomers. For compounds containing only doubly bonded atoms the reference plane contains the double-bonded atoms and is perpendicular to the plane containing these atoms and those directly attached to them. For cyclic compounds the reference plane is that in which the ring skeleton lies or to which it approximates. *See also* ***E*/*Z **convention**.

cistron a unit of DNA sequence that codes for a single polypeptide or protein. It may be a smaller unit than the **gene**, which contains the unit of DNA determining a single character. Whether or not a cistron is the same as a gene can be determined by the ***cis–trans*** **complementation test**, hence the name cistron (*cis* means 'on this side').

Cit *symbol for* a residue of the α-amino acid L-citrulline.

citraconate **1** *the trivial name for* methylmaleate, *cis*-1,2-propylenedicarboxylate, (*Z*)-2-methyl-2-butenedioate, the dianion of citraconic acid, (*Z*)-2-methyl-2-butenedioic acid. **2** any mixture of citraconic acid and its mono- and dianions. **3** any salt or ester of citraconic acid.



citraconic acid

citraconoyl the bivalent *cis*-acyl group, $-\mathrm{CO{-}CH{=}C(CH_3){-}CO}-$, derived from citraconic acid. *Compare* **citraconyl**.

citraconyl either of the isomeric univalent *cis*-acyl groups, $\mathrm{HOOC{-}C(CH_3){=}CH{-}CO}-$ or $\mathrm{HOOC{-}CH{=}C(CH_3){-}CO}-$, derived from citraconic acid. *See also* **citraconylation**.

citraconylation introduction of one or more **citraconyl** groups into a substance by acylation. Similarly to **maleylation** (and succinylation), citraconylation of a protein with citraconic anhydride is used to acylate its free lysine (and other) amino groups in order to change their charge at neutral pH from positive to negative and to render the adjacent peptide bond resistant to hydrolysis by trypsin. Reaction occurs at pH 8 and the citraconyl groups can be removed at pH 3.5 (both operations at 20°C). Introduction of citraconyl groups is slower than is the case with maleyl groups, but their removal is faster and more complete. **—citraconylate** *vb.*; **citraconylated** *adj.*

citrase *see* **citrate lyase**.

citratase *see* **citrate lyase**.

citrate **1** *the trivial name for* β-hydroxytricarballylate, 2-hydroxy-1,2,3-propanetricarboxylate,

$$\mathrm{HO{-}C(CH_2{-}COO^-)_2{-}COO^-},$$

the trianion of citric acid, 2-hydroxy-1,2,3-propanetricarboxylic acid. **2** any mixture of free citric acid and its anions; the trianion is the predominant form at physiological pH values. It is widely distributed in nature and is an important intermediate in the **tricarboxylic-acid cycle** and the **glyoxylate cycle**. Citrate (alone or in mixtures) is useful as a buffer; $\mathrm{p}K_{a1}$ (25°C) = 3.13, $\mathrm{p}K_{a2}$ (25°C) = 4.76, $\mathrm{p}K_{a3}$ (25°C) = 6.40. It is useful also as a component of anticoagulant solutions and has many commercial applications in the chemical, food, pharmaceutical, and other industries. Industrial production of citrate is usually by fermentation of inexpensive sources of glucose or sucrose with selected strains of *Aspergillus niger*; world production in 1992 was 5×10^8 tons. **3** any (partial or full) salt or ester of citric acid.



citrate aldolase *see* **citrate lyase**.

citrate cleavage enzyme EC 4.1.3.8; *recommended name*: ATP–citrate (*pro-S*)-lyase. An enzyme that catalyses a reaction between ATP, citrate, and CoA to form acetyl-CoA, oxaloacetate, ADP, and orthophosphate. In mammals it participates in the release of acetyl-CoA in the cytosol, particularly as a precursor for fatty acid synthesis, there being no system for transporting excess acetyl-CoA out of the mitochondrion. The acetyl carbons are thus transported across the mitochondrial membrane as citrate and then released by this enzyme.

citrate cycle *another name for the* **tricarboxylic-acid cycle**.

citrate (*pro*-3*S*)-lyase EC 4.1.3.6; *other names*: citrase; citratase; citritase; citridesmolase; citrate aldolase; a bacterial enzyme that catalyses the formation of acetate and oxaloacetate from citrate. ATP–citrate lyase is another name for **citrate cleavage enzyme**.

citrate (*Re*)-synthase EC 4.1.3.28; an enzyme from some bacteria that forms citrate with the incoming $-CH_2-COOH$ group in the *pro-R* position of citrate. The addition is to the *Re*-face of the carbonyl group of oxaloacetate.

citrate (*Si*)-synthase EC 4.1.3.7; *other names*: citrogenase; oxaloacetate transacetase; condensing enzyme; citrate condensing enzyme. An enzyme that catalyses a reaction between acetyl-CoA, H_2O, and oxaloacetate to form citrate and CoA. It synthesizes citrate from oxaloacetate and acetyl-CoA, placing the incoming $-CH_2-COOH$ in the *pro-S* position in citrate (*see* **oxaloacetate**). The addition is to the *Si*-face of the carbonyl group of oxaloacetate. This is the usual mammalian citrate synthase; mitochondrial enzymes are closely related homodimers (six motifs).

citric acid *see* **citrate**.

citric-acid cycle *an alternative name for* **tricarboxylic-acid cycle**.

citridesmolase *see* **citrate lyase**.

citritase *see* **citrate lyase**.

citrovorum factor *(formerly) an alternative name for* **folinic acid**.

citrulline N^5-carbamoyl-L-ornithine; 2-amino-5-ureiodovaleric acid; an α-amino acid, not found in proteins. L-Citrulline is an intermediate in the **urea cycle** in animals, and in a modified urea cycle in plants. It was first isolated from the juice of watermelon, *Citrullus vulgaris*.



citrullinemia *or* **citrullinuria** an autosomal recessive disease caused by deficiency of the enzyme **argininosuccinate synthase**. It is characterized by hyperammonemia, hypercitrullinemia, and citrullinuria. It has a neonatal onset and if untreated results in neurological damage and mental retardation.

CJD *abbr. for* Creutzfeldt–Jakob disease.

c-Jun N-terminal kinase *see* **JNK**.

CKI *abbr. for* **Cdk inhibitor**.

C-kinase *see* **protein kinase C**.

Cl *symbol for* chlorine.

clade **1** a monophyletic taxonomic group, i.e. a group that includes all descendants of a single ancestor. **2** a subtree of a rooted phylogenetic tree comprising a given node and all of its descendants.

cladinose 2,6-dideoxy-3-*C*-methyl-3-*O*-methyl-L-*ribo*-hexose; 3-*O*-methyl mycarose; a component of **erythromycins** A and B.



β-L anomer

cladistics phylogenetic studies aimed at establishing evolutionary relationships between different species or other groupings based on the identification of natural **clades**. —**cladistic** *adj.*; **cladistically** *adv.*

cladogenesis a process of adaptive evolution leading to the development of a greater variety of organisms; branching evolution. —**cladogenetic** *adj.*

cladogram a **phylogenetic tree** that illustrates ancestor-descendant relationships determined by cladistics.

***Cla*I** a type 2 **restriction endonuclease**; recognition sequence: AT↑CGAT. The M.*Cla*I modification site is A5.

clan *(in protein sequence analysis)* a group of families for which there is evidence of evolutionary relatedness (e.g. shared function) but between which there is no significant sequence or structural similarity. For example, the serine proteases have been grouped into six clans on the basis of structural and functional similarities, but the sequences and structures of the different clans appear to be unrelated.

clarify to make or become clear, especially to remove finely divided suspended material from a solution, e.g. by centrifugation or filtration. —**clarified** *adj.*; **clarification** *n.*

Clark and Lubs buffers one of the early series of buffer mixtures of predetermined pH, covering the range pH 2.2–10.0. [After William Mansfield Clark (1884–1964), US biochemist, and Herbert A. Lubs.]

Clark electrode a type of **oxygen electrode**. [After Leland Charles Clark (1918–).]

class a taxonomic category ranking below the **phylum** (or division) and containing several **orders** (or sometimes only a single order).

classical pathway of complement activation *see* **complement**.

class switch a change (switch) in the expression of B lymphocytes from one class of antibody to another.

clastic dividing into parts, especially of a chemical reaction in which one molecular species is divided into parts; e.g. phosphoroclastic, thioclastic.

clastogen an agent that is able to bring about breakage in chromosomes. —**clastogenic** *adj.*

clathrate **1** *or* **cage compound** *(in chemistry)* a solid complex or an addition compound in which the crystal lattice or structure of one component (the **host molecule**) completely encloses spaces in which a second component (the **guest molecule**) is located. There is no chemical bonding between the two components. *Compare* **inclusion complex**. **2** designating or relating to a clathrate. **3** *(in biology)* lattice-shaped.

clathrin a 180 kDa protein that is the main component of the coat of **coated vesicles** and **coated pits**, which are involved in the transfer of molecules between the membranous components of eukaryotic cells. Clathrin also occurs in **synaptic vesicles**. The clathrin coat is a polyhedral lattice of subunits; each subunit, or clathrin **triskelion**, comprises three heavy chains and three light chains.

clathrin uncoating protein *or* **uncoating ATPase** a protein from brain or erythrocyte cytosol that disassembles **clathrin** coats to **triskelions** in an ATP-dependent manner. It is thought that the uncoating ATPase is a chaperone from the hsp70 family, and that the dismantling process may be triggered by auxillin, a protein that can be found attached to clathrin-coated vesicles.

clavaminate synthase a nonheme iron-containing oxygenase, EC 1.14.11.21, from *Streptomyces* spp., that catalyses three steps in the biosynthesis of clavulanic acid: the first step (hydroxylation) is separated from the latter two (oxidative cyclization and desaturation) by the action of EC 3.5.3.22, proclavaminate amidinohydrolase.

clavulanic acid 3-(2-hydroxyethylidene)-7-oxo-4-oxa-1-azabicyclo[3.2.0]heptane-2-carboxylic acid; a weak antibacterial agent but potent *β*-lactamase inhibitor produced by *Streptomyces clavulingerus*. It protects lactamase-sensitive but otherwise potent antibiotics from deactivation, and is used in combination with *β*-lactam antibiotics to increase their efficacy. It has no antibacterial activity but by inactivating penicillinases it makes a combination active against penicillin-resistant bacteria. These include *Staphylococcus aureus*, 50% of many *Bacteroides*, and *Klebsiella* spp. A commonly used proprietary combination is Augmentin.

clearance *(in physiology) symbol*: *C*; a measure of the efficiency of the kidney in removing a substance from the blood. $C = UV/P$, where U and P are the concentrations of the substance in the urine and plasma, respectively, and V is the rate of urine flow in ml min^{-1}. Clearance is therefore a rate, with the dimensions of ml plasma per min.

clearing **1** *(in histology)* the process of preparing tissue samples for microscopical examination by removing the dehydrating agent and rendering the sample transparent. **2** *(in physiology)* the removal of a substance from the body or from the blood; *see* **clearance**.

clearing factor *an alternative name for* **lipoprotein lipase**; an enzyme found bound to heparan sulfate on the capillary endothelium of various tissues, notably heart, lung, skeletal muscle, and adipose tissue, so called because it clears the opalescence from lipemic plasma. It is released into plasma by intravenous injection of heparin.

cleavage **1** the tendency of a crystal to split in certain preferred directions with the formation of smooth surfaces, or the act of so splitting a crystal; hence **cleavage plane**, **cleavage face**. **2** the rupture of a (usually specified) chemical bond in a molecule with the formation of smaller molecules. **3** *or* **segmentation** *(in embryology)* the series of mitotic divisions by which a fertilized animal ovum changes, without any overall change in size, into a ball of smaller cells constituting the primitive embryo.

cleavage division the mitotic division of a fertilized egg up to the point at which the regions of the egg shift relative to each other.

cleavage-polyadenylation specificity factor *see* **CPSF**.

cleave to split or cause to divide, especially along the line of a natural weakness; to split a chemical bond; to effect or undergo **cleavage**. **—cleavable** *adj.*

cleft lip/palate a dysmorphology of the head of mammals resulting from mutation of any one of numerous genes such as Nectin-1.

Cleland's reagent *see* **dithiothreitol**. [After William Wallace Cleland (1937–).]

Cl^-/HCO_3^- exchanger *an alternative name for* **anion channel protein**.

climacteric 1 *(in medicine)* the female menopause, or the corresponding time of life in men. **2** *(in botany)* the marked increase in respiration in some fruits (e.g. tomato) just before and during ripening. This is usually associated with an increase in production of ethylene.

clindamycin (7*S*)-7-chloro-7-deoxylincomycin; a semisynthetic antibiotic that is useful against anaerobic bacteria; for structure and action *see* **lincomycin**, **lincosamide**.



clinical of, or pertaining to, the course of disease in an individual, or the examination and treatment of an individual directly, as opposed to the laboratory investigation of disease.

clinical chemistry a branch of applied biochemistry concerned with the nature and determination of chemical substances of interest in the investigation of diseases.

CLIP *abbr. for* **1** corticotropin-like intermediate peptide. **2** Class-II HLA-associated invariant-chain peptide (*see* Class II MHC antigens in **major histocompatibility complex**).

CLIP-170 *see* **restin**.

CLN *abbr. for* **ceroid lipofuscinosis (neuronal)**.

clock 1 *abbr. for* circadian locomotor output cycles kaput; a basic helix-loop-helix (HLH) transcription factor expressed primarily in the suprachiasmatic nucleus of the hypothalamus . First detected in *Drosophila* as a key regulator of circadian rhythms, it occurs widely in the animal kingdom. It forms heterodimers with the basic HLH proteins **BMAL1** and **NPAS2** and binds to a specific DNA motif to regulate circadian activity, by stimulating expression of genes encoding period proteins and **cryptochromes**. Transcription of target genes for the clock-BMAL1 dimer is repressed by cryptochromes. **2** *see* **molecular clock**.

clofazimine *N*,5-bis(4-chlorophenyl)-3,5-dihydro-3-[(1-methylethyl)imino]-2-phenazinamine; an iminophenazine dye with anti-inflammatory, tuberculostatic, and leprostatic activity. It is used to treat multibacillary or sulfone-resistant leprosy.

clofibrate ethyl 2-(*p*-chlorophenoxy)-2-methylpropionate; 2-(4-chlorophenoxy)-2-methylpropanoic acid ethyl ester; a drug that reduces high plasma levels of triacylglycerols, very-low-density lipoproteins (VLDL), and (less so) cholesterol. Its actions are probably mediated by the stimulation of **lipoprotein lipase**, which reduces the triacylglycerol composition of VLDL and stimulates clearance of low-density lipoproteins by liver. It is used primarily in the treatment of type III (but also in type IV, type V, and type IIb) hyperlipoproteinemia. Clofibrate causes proliferation of peroxisomes in rat, but not in human, liver. *Compare* **gemfibrozil**.



clomifene *or* **clomiphene** 2-[4-(2-chloro-1,2-diphenylethenyl)phenoxy]-*N*,*N*-diethylethanamine; an antiestrogenic aminoether derivative of stilbene; it blocks estradiol receptors in the hypothalamus and may stimulate the secretion of gonadotropin-releasing hormone. It is active as an antitumour agent against mammary carcinomas, and can be used to induce ovulation in infertile women. Both its structure and actions are similar to those of **tamoxifen**.



clonal culture any culture of cells produced in such a way that an individual **clone** (def. 1) can be selected.

clonal selection theory *or* **Burnet's theory of immunity** a theory to account for the phenomenon of **acquired immunity** and the ability of the immune system to produce large quantities of highly specific antibody for any particular immunogen. According to the theory, proposed by the Australian physician (Sir) Frank Macfarlane Burnet (1899–1985), the ability to produce a given antibody is a pre-existing and genetically determined characteristic of a particular clone of B lymphocytes. An encounter with the antigen triggers proliferation of the corresponding clone, producing a greatly expanded population of cells that secrete specific antibody. Some members of the expanded clone assume the role of memory cells, which respond to any subsequent encounter with the same immunogen, which accounts for the secondary response being greater than the primary response.

clone 1 the descendants produced vegetatively or by apomixis from a single plant, or asexually or parthenogenetically from a single animal; a group of cells produced by division from a single cell. The members of a clone are of the same genetic constitution, unless **mutation** has occurred amongst them. **2** a homogeneous population of DNA molecules; *see* **molecular cloning**. **3** to propagate a selected organism or cell, or to replicate a particular DNA molecule so as to produce a clone. **—clonal** *adj.*; **cloning** *n.*

cloned library *an alternative name for* **gene library**.

clonidine 2,6-dichloro-*N*-2-imidazolidinylidenebenzenamine; an antagonist at α_2 (presynaptic) adrenergic receptors, P_1 purinergic receptors, and H_2 histamine receptors. It is used as a central antihypertensive drug; it also abolishes most symptoms of opiate withdrawal.



cloning vector *or* **cloning vehicle** the DNA of any transmissible agent (e.g. plasmid or virus) into which a segment of foreign DNA can be spliced in order to introduce the foreign DNA into cells of the agent's normal host and promote its replication and transcription therein. (1) **Plasmid vectors** contain (i) an origin of replication, so that the plasmid can be replicated; (ii) an antibiotic resistance gene to allow selection of transformed host cells; (iii) often, a 'polylinker' containing several different restriction enzyme recognition sites and a second marker gene (e.g. *lacZ*; *see* **X-gal**), which will be inactivated when foreign DNA is inserted therein, thus allowing identification of transformants bearing plasmids containing inserts, rather than 'empty' vectors. Examples include **pBR322** and the **pUC vectors**. *See also* **expression vectors**. (2) **Bacteriophage vectors**, usually based on **lambda phage**, can accommodate longer fragments of foreign DNA. In insertion vectors (e.g. λgt10) the foreign DNA is inserted into the phage DNA while in replacement vectors (e.g. λEMBL4) the foreign DNA is ligated between two phage fragments, or arms. (3) Hybrid vectors, **cosmids**, **phagemids** and **phasmids** (def. 1), with features of both plasmids and phage, have also been constructed. *See also* **molecular cloning**.

closed circle (of DNA) *see* **covalent (closed) circle (of DNA)**.

closed double-stranded DNA *see* **covalent (closed) circle (of DNA)**.

closed duplex DNA *or* **DNA I** a closed double-stranded DNA molecule in which the DNA helical structure is preserved.

closed-loop system a type of system, e.g. a metabolic pathway or an electrical circuit, in which control is exerted by **feedback**. *Compare* **open-loop system**.

closed system any (thermodynamic) system that cannot gain or lose matter, heat, or work. *Compare* **open system**.

close packing the structure of a solid in which nonbonded atoms (or molecules) are surrounded by other nonbonded atoms (or molecules) in such a way that the distance between them is close or equal to the sum of their van der Waals contact radii (*see* **van der Waals radius**).

clostridiopeptidase A the **collagenase** obtained from *Clostridium histolyticum*.

Clostridium a genus of spore-forming rod-shaped bacteria of the family Bacillaceae. Its members are chemoorganotrophic, obligately anaerobic, and typically Gram-positive. They are widespread in soil, mud, and in the intestinal tract of animals. Some species are pathogenic if they gain access to the tissues, and produce a range of toxins.

***Clostridium histolyticum* collagenase** *see* **microbial collagenase**.

clostripain *or* **clostridiopeptidase B** EC 3.4.22.8; a cysteine proteinase enzyme from *Clostridium histolyticum*. It preferentially cleaves Arg-|-Xaa and Arg-|-Pro bonds and is inactivated by substituted arginine and lysine chloromethyl ketones. It is a heterodimer of α and β chains.

clot retraction the contraction of a blood clot after its formation, accompanied by the expression of serum.

clotrimazole 1-[(2-chlorophenyl)diphenylmethyl]-1*H*-imidazole; an **imidazole** used topically as an antifungal agent. It inhibits ergosterol synthesis and disrupts the transport of amino acids into the fungus.



clotting factor *an alternative term for* coagulation factor; *see* **blood coagulation**.

clotting time *an alternative term for* **coagulation time**.

clover-leaf structure one of the models for the secondary structure of **transfer RNA** (tRNA). The nucleotide sequences of different tRNAs can be arranged in similar two-dimensional representations, resembling a clover leaf in shape, in which there are four bi-helical regions, containing the maximal number of base pairs, connected by three loops. Some tRNAs have a small extra loop. The clover leaf structure has been largely supported by the tertiary structure of those tRNAs for which structure has been determined by X-ray crystallography.

cloxacillin a semisynthetic penicillin that is resistant to penicillinase and is useful against certain staphylococci.



Clp protease *or* **ClpAP protease** a proteinase/ATPase from *Escherichia coli* with little protein specificity (EC 3.4.21.–). It is a **heat-shock protein** but supposedly a housekeeping proteinase; counterparts occur in many organisms (five motifs). The enzyme is a heterodimer with subunits named from the *clp* genes. The proteolytic subunit is ClpP, the ATP-binding subunit is one of ClpA or ClpX. A homologous protein in chloroplasts consists of two stacked heptameric rings of ClpP subunits (each a serine protease of 21 kDa), that are activated by a heptameric ring of ClpA subunits (each an ATPase of 81 kDa), which also unfolds the substrates for degradation. This enzyme is particularly important during leaf senescence.

clupein a **protamine** derived from herring sperm. Arginine constitutes 80–90% of its amino acid content.

Clustal *see* **multiple alignment program**.

cluster 1 (in chemistry) a number of metal centres grouped close together, which can have direct metal bonding interactions or interactions through a bridging ligand. **2** a group of iron and sulfur atoms, e.g. [2Fe-2S] or [4Fe-4S] , in an iron–sulfur protein. The term is sometimes extended to include other metal atoms, as in the Fe_7MoS_9 cluster in nitrogenase. **3** *or* **cluster of enzymes** *or* **enzyme cluster** the phenomenon of the emergence of new enzymes, or the upsurge of enzymes already present in low concentration, at certain (usually defined) periods along the age axis of the organism. **4** a set of sequences, genes, or gene products grouped according to given similarity criteria (e.g. distance-based, associative, correlative, probabilistic). Such clusters facilitate the recognition of patterns and reveal otherwise hidden relationships, especially in **high-throughput** data.

cluster analysis a method of statistical analysis used, e.g., in **phylogeny** deduced from phenetic characters.

cluster-crystal any of the globular aggregates of calcium oxalate crystals found in some plants.

cluster database a database whose entries are grouped by means of, and whose groupings depend on, specified clustering parameters, and hence may not map to precise biological roles. For example, CluSTr and ProDom are automatic similarity-based clusterings of sequences in the Swiss-Prot database and its supplement, TrEMBL; COG is a similarity-based protein clustering from an all-against-all comparison of sequenced genomes; UniGene is a dynamic mapping of overlapping sequences from GenBank into clusters representing single genes.

clusterin *an alternative name for* **apolipoprotein J**.

clustering the occurrence of a number of objects, like or unlike, in clusters; the term is used especially of components of cell membranes, such as receptors.

CluSTr *abbr. for* clusters of Swiss-Prot and TrEMBL proteins; *see* **cluster database**.

cm *symbol for* centimetre, i.e. 10^{-2} m.

Cm *symbol for* **1** the carboxymethyl group, $–CH_2–COOH$. **2** curium.

CM *abbr. for* carboxymethyl; e.g. CM-cellulose.

CMAR a gene, cloned from a colon cancer cell line, encoding an 82-amino-acid protein that enhances the attachment of cells to collagen and laminin; the gene is named from cell matrix adhesion regulator. The protein has an N-terminal myristoylation motif (underlined in the partial sequence) and a tyrosine phosphorylation site (bold in the partial sequence), this tyrosine being required for activity. Sequence:

MLRGSDMKGP...............TAL**RIVEILY**.

CMC *abbr. for* **1** critical micellar concentration. **2** carboxymethylcellulose.

CMH *abbr. for* ceramide monohexoside (Cer(Hex) preferred).

CMP *abbr. for* cytidine monophosphate, i.e. cytidine phosphate.

CMR1 *abbr. for* cold and menthol receptor 1; a protein found in nerve endings that respond to cooling (to 15–25°C), and to menthol, in the mammalian skin and mouth, respectively. It belongs to the transient receptor potential (TRP) superfamily of calcium channels, and is a homotetramer of four 1104-residue subunits. Each subunit has long intracellular N- and C-terminal regions containing coiled-coil domains, and six transmembrane segments. On activation, the channel permits the entry of Ca^{2+} and Na^{+} ions into the neuron. CMR1 is identical with TRPM8, which senses heat and capsaicin.

CMR (spectroscopy) *(sometimes) abbr. for* ^{13}C-nuclear magnetic resonance (spectroscopy).

CMU *abbr. for* 3-(*p*-chlorophenyl)-1,1′-dimethylurea; monuron; a herbicide that acts by blocking noncyclic photophosphorylation.

CMV abbr. for **cytomegalovirus**.

CMV promoter *abbr. for* the immediate early cytomegalovirus promoter; a strong promoter used to obtain expression of exogenous genes in mammalian and other higher eukaryotic cells.

Cn3d *see* **visualization software**.

^{13}C-NMR (spectroscopy) *abbr. for* carbon-13 nuclear magnetic resonance (spectroscopy).

CNP *abbr. for* C-type natriuretic peptide; it is similar to atrial **natriuretic peptide**.

CNS *abbr. for* central nervous system.

CNTF *abbr. for* **ciliary neurotrophic factor**.

co+ *prefix* denoting **1** together, joint or jointly; in partnership, an equality; to the same degree. **2** *(in mathematics)* of the complement of an angle.

Co **1** *symbol for* cobalt. **2** *abbr. for* coenzyme.

Co I *(obsolete) abbr. for* coenzyme I; *see* **nicotinamide adenine dinucleotide**.

Co II *(obsolete) abbr. for* coenzyme II; *see* **nicotinamide adenine dinucleotide phosphate**.

CoA *symbol for* (free or combined) coenzyme A.

coacervate any viscous phase obtained by **coacervation** of solutions of two or more polymers.

coacervate droplet any of the droplets that, it has been suggested, may have formed in the **primordial soup** by **coacervation** and, perhaps, entrapped primitive catalyst(s); they may have given rise to the first cells. *Compare* **protobiont**.

coacervation any process in which there is a spontaneous separation of a continuous one-phase aqueous solution of a highly hydrated polymer into two aqueous phases, one with a relatively high polymer concentration, the other with a relatively low polymer concentration.

coactone an **ecomone** active in the process of relationship between an active and directing organism and a passive and receiving organism.

coagulant any substance that produces, or aids the production of, coagulation.

coagulase any of a number of serologically distinguishable bacterial enzymes that catalyse the coagulation of citrated or oxalated blood plasma. The extracellular bacterial protein specifically forms a complex with human **prothrombin**; this complex can clot fibrinogen without any proteolytic cleavage of prothrombin.

coagulase/fibrinolysin precursor *see* **plasminogen activator**.

coagulate **1** to cause a fluid or part of a fluid to change into a solid or semisolid mass by the action of, e.g., heat or chemical substances; to clot. **2** the solid or semisolid mass produced by coagulation. —**coagulable** *adj.*; **coagulation** *n.*

coagulation factors *see* **blood coagulation**.

coagulation time *or* **clotting time** **1** the time taken for a freshly drawn specimen of blood or blood plasma to coagulate (clot) when measured under standard, controlled conditions; it is an indication of the state of the coagulation processes in the specimen. **2** the time taken for a specimen of milk, or of a casein fraction, to coagulate in standard, controlled conditions.

coagulogen a ~16 kDa fibrinogen-like protein that is found in the hemocyte (amoebocyte) of horseshoe crab (*Limulus polyphemus*) hemolymph, and participates in hemostasis. Coagulogen consists of a single, basic polypeptide chain, and constitutes about 50% of the protein in horsehoe-crab hemocyte lysates.

coagulum (*pl.* **coagula**) any semisolid coagulated mass or clot, especially that formed by clotting of blood.

coarctation the state of being pressed together or constricted, especially of the aorta or other blood vessel.

coarse descriptive of **1** things that are rough in texture or structure. **2** particles that are large or powders composed of such particles. **3** threads, filaments, or fibres of relatively large diameter. **4** means of adjustment (as of instruments or processes) that provide only inaccurate or gross control, or the adjustments so made.

CoASAc (occasionally) *symbol for* acetyl-coenzyme A.

CoASH *symbol for* (free) coenzyme A.

coated pit an invagination of the cell membrane of many eukaryotic cells, concerned in receptor-mediated selective transport of many proteins and other macromolecules across the cell membrane. During endocytosis it is converted into a **coated vesicle**. The coat is of **clathrin**.

coated-tube method a solid-phase **radioimmunoassay** method in which the specific antibody is immobilized on the inner surface of a small test tube.

coated vesicle a vesicle, formed from a **coated pit**. Observed in the cytoplasm of many eukaryotic cells, coated vesicles measure 50–250 nm in diameter and are characterized by a ‘bristle’ coat on the outer surface of their lipid membrane. This coat is made up of a polyhedral lattice of **clathrin** subunits together with smaller amounts of other proteins, notably ones of about 100 kDa (**adaptins**), 50 kDa, and 20 kDa. Coated vesicles are concerned with the rapid and continuous transport of molecules between specific membranous organelles of the cell and to and from the cell membrane.

coatomer a large protein complex that forms part of the coat of specific Golgi intercisternal transport vesicles that are involved in constitutive vesicular transport between endoplasmic reticulum, Golgi apparatus, and plasma membrane. It has seven subunits known as COPs (from coat protein). Example: the yeast coatomer is a 700–800 kDa complex; one component is the transport protein product of *SEC21*.

coat protein **1** one of the outer structural proteins of a coated **virus**. **2** any of those subunits of the **coatomer** known as COPs.

cobalamin *the trivial name for* many members of the **vitamin B$_{12}$** group and their derivatives. A cobalamin is a **cobamide** in which 5,6-dimethylbenzimidazole is the aglycon that forms a link between the cobalt atom and the α1-position of the ribose residue. The sixth position of the cobalt atom may be (artefactually) filled by a variety of groups, e.g. a cyano group giving cyanocobalamin. The oxidation state of the cobalt may be indicated by using a Roman numeral, e.g. cob(I)alamin for Co$^{\text{I}}$. *See also* **intrinsic factor**.

cob(I)alamin adenosyltransferase EC 2.5.1.17; *other name*: aquacob(I)alamin adenosyltransferase; an enzyme that catalyses the formation of adenosylcobalamin from ATP, cob(I)alamin, and H_2O, with release of orthophosphate and pyrophosphate. The enzyme requires manganese.

cob(II)alamin reductase EC 1.6.99.9; *other name*: vitamin B_{12r} reductase; a flavoprotein enzyme that catalyses a reaction between NADH and two molecules of cob(II)alamin to form two molecules of cob(I)alamin and NAD$^+$.

cobamide any member of a group of compounds (including the **cobalamins**) that have molecules consisting of a highly substituted tetrapyrrole ring system (corrin) in which a cobalt atom is linked to the four pyrrole nitrogen atoms and with an α-D-ribofuranose 3-phosphate residue attached to one of the side chains.

cobamide coenzyme any of the biochemically active forms of **vitamin B$_{12}$**. They are **cobalamins** in which either a methyl or 5′-deoxy-5′-adenosyl residue is attached to the sixth position on the cobalt atom.

Cobol *see* **programming language**.

cocaine 2β-carbomethoxy-3β-benzoxytropane; an alkaloid obtained from dried leaves of the South American shrub *Erythroxylon coca* or by chemical synthesis. It is a cerebral stimulant and narcotic, and has been used as a local anaesthetic. Cocaine acts by blocking neuronal reuptake of, especially, **norepinephrine**, hence its potent vasoconstrictor effects, which can lead to tissue necrosis. Its use is restricted in many countries.



cocaine

cocarboxylase *a former name for* thiamine diphosphate (*see* **vitamin B$_1$**).

cocarcinogen any noncarcinogenic agent that enhances the effect of a **carcinogen**.

cochlin a protein produced in the cochlea and predicted to be secreted into the extracellular matrix. The gene at 14q12-q13 encodes 550 amino acids, which include two **von Willebrand factor**-like domains. Several missense mutations in the gene cause a form of hereditary deafness.

cochromatography a chromatographic technique in which an unknown substance is applied to a chromatographic support together with one or more known compounds, in the expectation that the relative behaviour of the unknown and known substances will assist in the identification of the unknown one.

Cockayne syndrome *abbr.*: CS; a rare syndrome of sensitivity to sunlight, dwarfism, skeletal abnormalities, and neurological dysfunction that is transmitted as an autosomal recessive trait. Cultured fibroblasts from patients are hypersensitive to UV irradiation but there is no increased predisposition to skin cancer. **CSA** is the more common phenotype, with late onset and slow progression. It is caused by deficiency or dysfunction of a 396-residue protein (encoded by a locus on chromosome 5), which contains five **WD40** repeats. **CSB** is an early-onset, rapidly progessive, more severe form. It is caused by deficiency or dysfunction of a DNA-dependent ATPase whose gene at 10q11-q21 encodes 1493 amino acids. This protein is normally a component of RNA polymerase II complex and functions as an RNA elongation factor. The CSA and CSB proteins are required for nucleotide **excision repair**. In rare cases, CS can also be associated with abnormality in XPB, XPD, and XPG components of nucleotide excision repair. [After Edward A. Cockayne (1880–1956), British physician.]

cocktail a mixture of substances prepared according to a recipe, especially reagent mixtures such as those for use in electrofocusing (**electrofocusing cocktails**), in liquid scintillation counting (**scintillation cocktails**), and in cell-free translation systems (**translation cocktails**). Many such cocktails are commercially available.

COD *abbr. for* chemical oxygen demand.

code 1 any system of symbols, together with the rules for their association, that can be used to represent or transfer information; e.g. the **genetic code**. **2** to contain, to be arranged in, or to be expressed through a code; used especially of DNA and mRNA. A gene is said to code for (or encode) its protein product. *Compare* **decoding**.

coded amino acid any of the 20 α-amino acids whose occurrence in proteins is under direct genetic control, i.e. for which a **codon** exists.

codehydrase I *or* **codehydrogenase** I *an obsolete name for* **nicotinamide adenine dinucleotide**.

codehydrase II *or* **codehydrogenase II** *an obsolete name for* **nicotinamide adenine dinucleotide phosphate**.

codeine methylmorphine; $(5\alpha,6\alpha)$-7,8-didehydro-4,5-epoxy-3-methoxy-17-methylmorphinan-6-ol; an opioid found in opium and manufactured by the methylation of **morphine**. It acts as an agonist at μ, δ, and κ-**opioid receptors** but is generally less potent than morphine, being metabolized in the liver to morphine and norcodeine. It is a narcotic analgesic with **antitussive** activity and is a controlled substance in the US Code of Federal Regulations.



coding ambiguity an adjustment to the prediction of British molecular biologist Francis **Crick** (1916–) that a single nucleotide triplet (codon) would not code for more than one particular amino acid, which was shown by subsequent work to require modification. Thus two codons, AUG and GUG, code not only for the amino acids, methionine and valine respectively, but also are important in chain initiation. Furthermore, there are differences between codon usage in the cytoplasm and mitochondria. In mitochondria UGA codes for Trp rather than chain termination, AUA for Met rather than Ile, and AGA for termination rather than Arg. There is also the problem of proteins containing selenocysteine, which is coded by a unique tRNA$^{\text{Sec}}$, the codon being UGA, which usually codes for termination.

'coding' problem the description given by British molecular biologist Francis **Crick** (1916–) and co-workers in 1957 to the crucial puzzle of the **genetic code**, namely how a sequence employing combinations of only four different nucleotides (i.e. genes) can determine sequences containing combinations of up to 20 different amino acids (i.e. proteins). Crick predicted that groups of three nucleotides would code for each amino acid providing the possibility of 64 codons, more than sufficient for the 20 amino acids. (A binary code of two nucleotides would only provide 16 codons.) The prediction was confirmed with the elucidation of the genetic code in the early 1960s.

coding region *or* **coding sequence 1** (of a DNA molecule) *an alternative name for* **exon**. **2** (of a messenger RNA molecule) the portion of its complete nucleotide sequence that is translatable into polypeptide. It starts with the **initiation codon** AUG and ends with one of the **termination codons** UAA, UAG, or UGA.

coding sequence *abbr.*: CDS; *an alternative name for* **coding region**.

coding single nucleotide polymorphism (*abbr.*: cSNP) *or* **coding SNP** a single nucleotide polymorphism (SNP) present in a coding sequence that may alter the encoded amino acid sequence.

coding SNP *see* **coding single nucleotide polymorphism**.

coding strand the strand in genomic duplex DNA that contains the same sequence of bases as messenger RNA transcribed from the DNA (excepting uracil in RNA in place of thymine in DNA). Its complement is the **noncoding strand,** on which transcription of RNA takes place. When DNA sequence is represented as a single strand it is usually the coding strand that is given. In some bacteria and viruses, alternate segments of both strands of duplex DNA may be coding, in some instances with overlap. *Other names*: antitemplate strand; codogenic strand; nontranscribing strand; plus strand; sense DNA; sense strand.

coding triplet *or* **coding unit** *an alternative name for* **1 codon**. **2 anticodon**.

cod-liver oil a fish oil obtained from the liver of cod, especially the Atlantic cod (*Gadus morhua*). It is a good source of long-chain *n*-3 **fatty acids**. The typical composition (% total) of major acids is: 16:0, 14%; 16:1 *n*-7, 12%; 18:1 *n*-9, 22%; 20:1 *n*-9, 12%; 22:1 *n*-11, 11%; 20:5 *n*-3, 7%; 22:6 *n*-3, 7%. *See also* **fish oil**.

codogenic strand *an alternative name for* **coding strand**.

codominance the state in which both alleles of a gene are expressed to an equal extent, for example the genes for the M and N, and A and B blood group antigens. —**codominant** *adj.*

codon any group of three consecutive nucleotide bases (base triplet) in a given messenger RNA molecule that, by its composition and sequence, specifies either a particular amino-acid residue in the polypeptide chain synthesized by translation of that messenger

RNA, or signals the beginning or the end of the message (i.e. **start codon**, **stop codon**). The term is also used loosely for base triplets in the genomic nucleic acid – in the case of duplex DNA, either on the **coding strand** or **noncoding strand**. For the full set of codons *see* **genetic code**.

codon matrix an amino acid **scoring matrix** based on the number of DNA bases that must be changed to cause a mutation from one amino acid to another.

codon optimization the systematic alteration of codons in recombinant DNA to be expressed in a heterologous system to match the pattern of **codon usage** in the organism used for expression. The intention is to enhance yields of the expressed protein.

codon usage the frequency with which the various alternative codons are used to specify an amino acid in a given organism. Most amino acids can be specified by more than one codon, and organisms differ in their pattern of codon usage for a particular amino acid.

codon usage bias the nonrandom use of synonymous codons in an organism. Bias varies between genomes, which have different synonym preferences for given amino acids, to some extent reflecting the background base composition of different genomes (and sometimes the relative abundance of alternative tRNA isoacceptors). Highly expressed genes tend to exhibit greater codon usage bias.

codon usage oligonucleotide design the selection of codons for incorporation into synthetic oligonucleotides that is based on the pattern of codon usage in the organism under investigation.

coefficient of danger (of a drug or other agonist) the percentage lethal responses to be expected at a dose level that is effective in 95% of trials.

coefficient of variation *or* **coefficient of variability** a parameter used in comparing dispersion in distributions. It is the ratio of the **standard deviation** to the **mean**, i.e. $sx/\bar{x}$. The coefficient of variation is an abstract number independent of the units of measurements; it may also be expressed as a percentage, i.e. $100sx/\bar{x}$.

coefficient of viscosity *see* **viscosity**.

coeliac *a variant spelling (esp. Brit.)* of **celiac**.

coenzyme any of various nonprotein organic **cofactors** that are required, in addition to an enzyme and a substrate, for an enzymic reaction to proceed. Compared with a **prosthetic group** a coenzyme is more easily removed from the **apoenzyme**. The term 'coenzyme' is frequently used imprecisely, although it is now possible to give more informative chemical names to such substances and to define their roles in specific enzymic reactions. *Compare* **cosubstrate**.

coenzyme I *an obsolete name for* **nicotinamide adenine dinucleotide**.

coenzyme II *an obsolete name for* **nicotinamide adenine dinucleotide phosphate**.

coenzyme A *symbol*: (combined form) CoA *or* (free form) CoASH; 3′-phosphoadenosine-(5′)diphospho(4′)pantetheine; a heat-stable compound that functions as an acyl carrier in a number of biochemical acylation and acyl-transfer reactions, in which the intermediate is a thiol ester. It is synthesized in mammalian cells in a pathway that starts with the water-soluble vitamin pantothenate. It was originally known as the **acetylation coenzyme**, hence its present name.





coenzyme B *abbr*. CoB; *N*-(7-mercaptoheptanoyl)-L-threonine 3-*O*-phosphate; a compound involved in the methanogenic pathway in methanogenic archaea.



coenzyme C a name sometimes given to a polyglutamate derivative of **tetrahydrofolate**.

coenzyme F *abbr.*: CoF; a name sometimes given to **tetrahydrofolate** or some of its derivatives.

coenzyme F_{420} the *N*-(*n*-L-lactyl-γ-glutamyl)-L-glutamic acid phosphodiester of 7,8-didemethyl-8-hydroxy-5-deazariboflavin that functions as a coenzyme for several oxidoreductases, e.g. methylenetetrahydromethanopterin dehydrogenase. It was first found in **methanogenic** Archaea, but later also in other Archaea, and some Bacteria and Eukarya. The oxidized form acts also as a photosensitizer in DNA photolyases. Reduction results in addition of hydrogen at C-1 and C-5, in all cases so far reported being stereospecific for the *Si*-face of the coenzyme.



oxidized
oxidized form



reduced form (R = substituent at N_{10})

coenzyme F_{430} *see* **factor F_{430}**.

coenzyme factor *an alternative name for* **diaphorase**.

coenzyme M *abbr.*: CoM; 2-thioethanesulfonate, $HSCH_2–CH_2SO_3^-$; it is involved as a coenzyme in the pathway of methanogenesis in **methanogenic** bacteria. In the terminal step of the pathway, a methyl group is transferred from methyltetrahydromethanopterin (*see* **tetrahydromethanopterin**) to CoM to form CH_3–S–CoM, from which methane is formed in a reductive step involving **methyl CoM reductase**.

coenzyme Q *abbr.*: CoQ; *an obsolete name for* **ubiquinone** (the abbreviation Q is, however, frequently used in diagrams).

coenzyme R *(sometimes) an alternative name for* **biotin**.

CoF *abbr. for* coenzyme F; *see* **tetrahydrofolate**.

cofactor 1 any accessory, nonprotein substance, commonly of low molecular mass, that is necessary for the activity of an enzyme. Metal-ion cofactors have been called **activators**; organic cofactors that are easily removable from the enzyme (e.g. by dialysis) may be called **coenzymes**, but if they are tightly bound they are often termed **prosthetic groups**. *See also* **apoenzyme**, **holoenzyme**. **2** any amino acid that must be present in the medium to allow certain phages to be adsorbed by host bacteria.

cofilin a pH-sensitive nuclear actin depolymerization factor, similar to **destrin**.

COG *abbr. for* clusters of orthologous groups; *see* **cluster database.**

cognitive neuroscience the area of neurobiology that aims to explain how the brain enables an animal to interact successfully with its environment. The term cognition has come to refer to that level of description that links molecular science to behaviour.

coherent *(in physics)* describing two or more waves having the same wavelength and the same phase, e.g. coherent light. The laser is a source of coherent light.

coherent anti-Stokes Raman spectroscopy *abbr.*: CARS; a nonlinear optical technique for obtaining **Raman spectra** with high efficiency. The signal levels, signal-to-noise ratios, resolution, and fluorescence rejection are far better than with normal Raman spectroscopy. CARS can be used for substances at about 1 mM concentration in aqueous solution.

cohesin a multimeric protein complex that binds to chromosomes from telophase to the onset of anaphase in the next cell cycle. It contains SMC1 and SMC3, and Scc1 and Scc3 (*see* **Scc**). The complex binds to more than half the Alu sequences on most of the human chromosomes. It is cleaved by **separase**, a cysteine protease that is inhibited by binding to **securin**.

cohesive end *or* **cohesive terminus** *or* **sticky end** the protruding (3′ or 5′) single-stranded terminus on a double-stranded DNA fragment that can associate with a complementary, similarly protruding sequence at the opposite end of the same DNA fragment, or on another fragment, to form a circular, or larger, DNA molecule.

Cohn fractionation a method for the fractionation of human blood plasma proteins to produce minimally altered proteins suitable for clinical use. It involves fractional precipitation with ethanol at temperatures near or below 0°C, with careful control of pH and ionic strength and additions of certain bivalent metal ions, especially Zn^{2+}. The numbered **Cohn fractions** contain the following main constituents: I, fibrinogen; II, γ-globulins; III, β-globulins; IV, α-globulins; V, albumin; VI, glycoproteins. The method has also been applied to the fractionation of plasma proteins of other animals. [After Edwin Joseph Cohn (1892–1953), US biochemist.]

coiled coil an arrangement of fibrous polypetide chains in which two alpha helices wind around each other as a consequence of a seven-residue (heptad) pseudorepeat, a-b-c-d-e-f-g, in which non-polar residues predominate in positions a and d. The hydrophobic residues fall on roughly the same side of the helix, slightly out of phase, such that, when two or three heptads associate, the helices coil around each other in a left-handed supercoil. Coiled coils are often associated with specific functions, and examples include myosin heavy chains and intermediate filaments. *Compare* **leucine zipper**.

co-immunoprecipitation a technique for analysing protein–protein interactions in which antibodies to the protein of interest are used to precipitate it and any other proteins with which it forms stable associations.

coincidence 1 *(in physics)* the occurrence of radioactive nuclide disintegrations within a time span too short for them to be resolved by a radiation counter. **2** *(in genetics)* the ratio of the number of observed double crossovers to the number expected from the random combination of single crossovers among three or four linked genes.

coincidence correction a correction applied in counting radioactive events for **coincidence losses**, i.e. those events occurring at high count rates when two or more pulses arrive within the resolving time of the counter.

coincidence counter a counter for radioactive events that consists of two opposed detectors and appropriate electronic circuitry so that only those pulses observed by both detectors are registered. This arrangement, common in liquid scintillation spectrometers, considerably reduces the number of background counts attributable to random thermionic noise arising in the detectors.

co-ion any ion of low molecular mass present in a colloidal solution or substance that has a charge of the same sign as the (net) charge of a (specified) colloidal ion under particular conditions. *Compare* **counterion**.

colcemide *or* **demecolcine** a derivative of **colchicine** in which the amino group (attached to the non-tropolone seven-membered ring) is methylated instead of acetylated. It binds tubulin and inhibits formation of the mitotic spindle.

colchicine a major alkaloid from the autumn crocus, *Colchicum autumnale* L. It is used experimentally to inhibit the polymerization of **tubulin**, to which it binds specifically and tightly, and to encourage depolymerization of **microtubules**. This action inhibits spindle formation, arrests mitosis at metaphase, and promotes polyploidy in plants. Colchicine also disrupts neutrophil migration and phagocytosis, and inhibits leukotriene B_4 synthesis; it is useful in the treatment of gout. The molecule is noted for a tropolone ring, which is rather rare in natural products. *See also* **colcemide**.



cold 1 of low, or lower than normal, temperature. **2** *(in radiochemistry)* containing no, or an insignificant amount of, a radioactive nuclide; the nonradioactive counterpart of a radionuclide-labelled substance. *Compare* **hot**.

cold agglutinin *see* **cold autoantibody**.

cold autoantibody *or* **cold agglutinin** an antibody that attaches to red cells at low temperatures, reacting better at 4°C than at 37°C, and dissociates as the red cells are warmed. Cold autoantibodies are mainly directed against antigens of the **Ii system** of blood groups.

cold-insoluble globulin a **cryoglobulin** present in blood plasma or serum. It is normally present at only very low concentrations in human serum, but may be elevated in certain rare diseases such as systemic lupus erythematosis. *See also* **fibronectin**.

cold-labile enzyme *or* **cold-sensitive enzyme** any enzyme that, unlike most enzymes, is less stable at 0°C than at room temperature. In some, but not all, instances activity slowly returns on warming. The phenomenon can be due, e.g., to exothermic dissociation of a stabilizing cofactor from the enzyme or to dissociation into inactive subunits.

cold receptor *see* **CMR1**.

cold-sensitive mutation any mutation producing a gene that is functional at a high temperature (the permissive temperature) but inactive at a low temperature (the restrictive temperature). *See* **temperature-sensitive mutation**.

cold-shock protein any of various proteins, synthesized by microorganisms in response to a sudden drop in temperature. These are typically DNA-binding transcription activators, many of which have a characteristic **cold-shock domain**. *Compare* **heat-shock proteins**.

coleoptile the protective sheath covering the first leaves of seedling grasses.

ColE1 replicon an origin of DNA replication found in the naturally occurring colicin E1 plasmid of *Escherichia coli.* It has been used in the construction of certain synthetic plasmids. Synthesis of the leading strand of DNA is primed by RNAII.

colestipol a basic anion-exchange resin that when given orally as the Cl^- form, exchanges anions of chloride in the intestine with those of bile salts, which are then excreted and thus removed from the enterohepatic circulation as an insoluble complex. The resulting reduction in cholesterol absorption culminates in reduced circulating levels of low-density lipoproteins but can increase plasma triacylglycerols. It has therapeutic application in relieving hyperlipoproteinemia.

Col factor *(formerly) an alternative name for* **Col plasmid**.

colforsin *an alternative name for* **forskolin**.

colicin *or (formerly)* **colicine** any member of a range of 40–80 kDa proteins secreted by certain strains of the Enterobacteriaceae. They form pores on the outer surface of other susceptible strains within this family, or deliver DNAase or RNAase enzymes into the cytoplasm, to cause cell death. Colicins form a subcategory of **bacteriocin**. Different colicins are designated B, E_1, E_2, I, K, or V, and may be distinguished by their diffusibility and immunogenic and host specificities. They may be coded for by a **Col plasmid**.

colicin factor *or* **colicinogenic factor** *(formerly) an alternative name for* **Col plasmid**.

colicinogenic describing bacteria that are able to produce **colicins**.

colicinogenic factor *see* **Col plasmid**.

coliform 1 describing any bacterium belonging to the genera *Escherichia* or *Klebsiella*. **2** describing any Gram-negative, lactose-fermenting, enteric bacillus or, more loosely, any Gram-negative, enteric bacillus or related organism. **3** any coliform microorganism.

colipase a cofactor of **pancreatic lipase** that inhibits the surface denaturation of lipase and anchors the protein to the lipid–water interface of lipid micelles to prevent inhibition and displacement by bile salts (four motifs). The human precursor protein consists of 112 amino acids: amino acids 1–17 form the signal; 18–22 form enterostatin activation peptide; and 23–112 form the colipase.

coliphage any **bacteriophage** that infects a strain of *Escherichia coli.*

colistin *or* **polymyxin E** a **polymyxin** antibiotic derived from *Bacillus colistinus* and comprising colistins A, B, and C. It acts as a cationic surface-active detergent, disrupting microbial cell wall structure.

colitose 3,6-dideoxy-L-*xylo*-hexose; 3,6-dideoxy-L-galactose; a sugar present in lipopolysaccharide of some strains of *Escherichia coli.* For the D enantiomer, *see* **abequose**.

collagen a group of fibrous proteins of very high tensile strength that form the main component of connective tissue in animals. Collagen is highly enriched in glycine (up to one-third of its amino-acid residues) and somewhat less so in proline and 3- and 4-hydroxyproline (about 21%). The primary structure is characterized by a tripeptide repeating unit (G-x-P) that forms extended helical structures (prolines at the third position of the repeat unit are hydroxylated in some or all of the chains); three such chains twist together and are hydrogen bonded via the imino group of every third amino acid and a carbonyl group in one of the other two chains. Collagen of bones and skin is metabolically stable, but that of organs has a high metabolic turnover. Collagens are products of a superfamily of closely related genes found in multicellular animals. The products have been classified into types I to XIII in the order in which they were purified and characterized, and grouped into classes 1 to 4 according to their properties.

Class 1 comprises types I to III, V and XI. All of these are fibre-forming, of approximately the same length, having a a large C-terminal globular domain following a lengthy triple helical domain. Each is synthesized as a procollagen molecule. Several types of α chain are found variously in the different types of class 1 collagen. All of these aggregate into staggered arrays, first into microfibrils of five collagen molecules that then aggregate into fibres.

Class 2 comprises types IX and XII. Type IX was first isolated from pig hyaline cartilage. It comprises three different α chains, α-1, α-2 and α-3, and has three short triple-helical domains interrupted by non-collagenous domains. At the N-terminus, there is a large globular domain. A glycosaminoglycan molecule, chondroitin sulfate, is attached to the α-2 chain. Type XII was discovered by screening a DNA library and has structural similarities to type IX. The function of these molecules is not known.

Class 3 comprises types IV, VI, VII and X, which serve unique functions. Type IV is the major component of basement membranes. It has long triple-helical domains, with a complex globular domain at the C-terminal end. There are six α-x chain isoforms, numbered 1 to 6. Type VI is a short molecule, having a triple- helical domain, 105 nm in length, separating two globular domains. It aggregates into tetramers stabilized by disulfide bonds. Carbohydrate chains consisting of glucosamine, mannose, galactose, fucose, and sialic acid are associated with type VI, amounting to 10% of the total mass. Type VII is known as the **anchoring fibril network,** and is the largest collagen yet described, with a total molecular mass of the precursor of ~1050 kDa. It has an N-terminal globular domain, a triple-helical domain 424 nm long, and a highly complex C-terminal globular domain. Anchoring fibrils are found within the sub-basal lamina, and appear to anchor the lamina densa to the underlying matrix. Type X collagen has a restricted tissue distribution, being synthesized mainly by chondrocytes, and is 1438 nm in length.

Class 4 comprises types VIII and XIII. Type VIII was first observed as a cell culture product of endothelial cells. It is a 130–140 nm rod found in specialized tissues, including the sclera, periosta, perichondria, and cartilage growth plate. Type XIII was identified from a cDNA clone encoding short chains that form a triple-helical domain. Its function is unknown. *See also* **hydroxyproline**.

collagenase any of the proteinases that hydrolyse **collagen**, in particular *Clostridium histolyticum* collagenase (clostridiopeptidase A, EC 3.4.24.3), which preferentially cleaves at Xaa-|-Gly in the sequence

-Zaa-Pro-Xaa-Gly-Pro-Xaa.

It is widely used experimentally in the release of many types of cells from animal tissues, e.g. adipocytes and hepatocytes. *See also* **gelatinase**, **interstitial collagenase**, **microbial collagenase**.

collapsin *an alternative name for* **semaphorin**.

collectin one of a family of plasma **lectins** with a trimeric structure similar to complement C1q.

colligation the formation of a covalent bond by means of two combining groups donating one electron each; the reverse of unimolecular **homolysis**. *Compare* **coordination** (def. 2). **—colligate** *vb.*

colligative property the property of any substance or system (e.g. an ideal solution) that depends only on the number of particles (atoms, molecules, and ions) and not on their nature. For example, gaseous pressure and osmotic pressure are colligative properties.

collimator any device, generally embodying a system of slits and (sometimes) lenses (optical, electric, or magnetic), that is used to produce a nondivergent beam of electromagnetic radiation or particles.

collinear 1 lying in or on the same (straight) line. **2** having a (straight) line in common. **3** describing the state of congruence between the order of amino acids along a polypeptide chain and the order of the corresponding codons along the polynucleotide chain encoding the polypeptide. **—collinearity** *n.*

collision coupling hormone–receptor–enzyme model a model of enzyme activation summarized by the scheme:

$$H + R + E \overset{K_{mH}}{\rightleftharpoons} HR + E \xrightarrow{k_1} HRE \xrightarrow{k_3} HR + E'$$

where H is the hormone, R is the receptor, E is the inactive enzyme, E′ is the activated enzyme, K_{mH} is the hormone–receptor dissociation constant, k_1 is the bimolecular rate constant governing HRE formation, and k_3 is the rate constant governing enzyme activation. In this model the enzymically inactive intermediate, HRE, never accumulates and constitutes only a small fraction of the total receptor and enzyme concentrations.

collision frequency *or* **collision number** the number of collisions per second when there is only one molecule of reactant per cubic centimetre of gas or liquid e.g. in kinetics.

collodion a solution of 4 g pyroxylin (mainly nitrocellulose) in 100 ml of a mixture of 25 ml ethanol and 75 ml diethylether. When exposed to the atmosphere in thin layers it evaporates leaving a tough, colourless film that may be used as a **dialysis membrane**.

colloid *or* **colloidal system** **1** a state of subdivision of matter implying that the molecules or polymolecular particles (the dispersed phase) dispersed in a medium (the continuous phase) have, at least in one direction, a dimension roughly in the range 1 nm–1 µm or that in a system discontinuities are found at distances of this order. All three dimensions need not be in the colloidal range nor is it necessary for the units of a colloidal system to be discrete. Colloids may comprise many individual large molecules such as proteins or polysaccharides, or aggregations of smaller molecules such as colloidal gold. The colloids do not pass, or pass very slowly, through semipermeable membranes. **2** *(in histology)* the structureless substance seen in thyroid gland follicles. **—colloidal** *adj.*

colloidal dispersion any thermodynamically unstable colloidal system in which particles of colloidal size of any nature (e.g. solid, liquid, or gas) are dispersed in a continuous phase of different composition (or state), and which cannot easily be reconstituted after separation of the dispersed phase and the dispersion phase. *Compare* **colloidal solution**.

colloidal electrolyte any electrolyte that gives ions of which at least one is of colloidal size; it includes **polyelectrolytes**.

colloidal solution any thermodynamically stable solution consisting of colloidal macromolecules and solvent that can be easily reconstituted after separation of the macromolecules from the solvent. *Compare* **colloidal dispersion**.

colloid osmotic pressure that part of the osmotic pressure exerted by a solution that is due to dissolved colloids. *See* **osmotic pressure** (def. 1).

colon **1** *(in vertebrates)* the part of the large intestine that extends from the cecum to the rectum. **2** *(in insects)* the second part of the intestine.

colon bacillus *a former term for* ***Escherichia coli***.

colony *(in microbiology)* a circumscribed group of cells, normally derived from a single cell or small cluster of cells, growing on a solid or semisolid medium.

colony hybridization *or* **colony hybridisation** a blot-transfer method (*see* **blotting**) whereby a very large number of colonies of a bacterium carrying different hybrid plasmids can be rapidly screened to determine which hybrid plasmids contain a specified DNA sequence or gene(s). The bacterial colonies are grown on an agar plate, then replica plated onto nitrocellulose filters. A reference set of the colonies is retained. Then the colonies on the filter are lysed and their DNA is denatured and fixed to the filter *in situ*. The resulting DNA-prints of the colonies are then hybridized to a radioactive RNA probe for the sequence or gene of interest. DNA that binds the probe is then assayed by autoradiography or another detection method, enabling the selection of corresponding colonies from the reference plate.

colony PCR *or* **colony polymerase chain reaction** a procedure performed on a suspension of bacteria from a single colony and used to check whether plasmids carried by the cells have a cloned insert of interest. Oligonucleotide primers used for PCR are usually designed to anneal to vector sequences flanking the cloning site.

colony stimulating factor *abbr.*: CSF; any of the **cytokines** that control the differentiation of hemopoietic stem cells, both in the **bone marrow** and in the periphery. The group consists of granulocyte, macrophage, and granulocyte/macrophage CSFs. These promote the development of their specific subsets of leukocytes. **Interleukin**-3 (IL-3), interleukin-5 (IL-5), and **erythropoietin** are also members of this group. IL-3 promotes the differentiation of all the leukocyte lineages, whereas IL-5 is necessary for eosinophil development. Erythropoietin promotes the expansion of erythroid colony forming units. **Granulocyte-colony stimulating factors** (G-CSFs) act in hemopoiesis by controlling the production, differentiation, and function of two related white cell populations: granulocytes and monocytes–macrophages. **Granulocyte/macrophage-colony stimulating factors** (GM-CSFs) are glycoproteins that act in hemopoiesis by controlling the production, differentiation, and function of the granulocytes and the monocytes–macrophages. **Macrophage-colony stimulating factor** (M-CSF) is produced by fibroblasts, endothelium, and epithelium; it stimulates growth of macrophage colonies. Membrane receptors for CSFs, like those for other cytokines, are type I transmembrane proteins that signal through JAKs and STATs. Several missense mutations in the gene for the G-CSF receptor (at 1p35, which encodes 813 amino acids) result in severe congenital neutropenia frequently associated with acute myeloid leukemia.

colorimeter a device for measuring colour intensity or differences in colour intensity, either visually or photoelectrically. It is used for quantitative determination of coloured compounds in solutions.

colorimetry any method of quantitative chemical analysis in which the concentration or amount of a compound is determined by comparing the colour produced by the reaction of a reagent with both standard and test amounts of the compound, often using a **colorimeter**.

colostrum the milk secreted by the mammary gland just prior to and for a short period after parturition. It has high levels of protein and immunoglobulin, and its ingestion confers passive maternal immunity on the offspring of some species.

Colour Index *abbr.*: CI; a catalogue of commercially available dyes, identifying each by chemical class, colour, and generic name, and giving their chemical composition where disclosed. Each dye is assigned a five-digit number, prefixed by ‘CI’. The preferred trivial name of each dye, its commoner synonyms, and the name(s) of its known manufacturer(s) also are listed.

colour quenching the **quenching** that occurs in liquid scintillation counting due to the absorption of the scintillation emission by the specimen, resulting in a decrease in the light-collecting factor. It can often be reduced by prior bleaching or dilution of the specimen before introduction into the scintillator. *Compare* **chemical quenching**.

Col plasmid *or (formerly)* **Col factor** *or* **colicin factor** *or* **colicinogenic factor** any **plasmid** that carries genetic information for the production of a **colicin**; a subcategory of **bacteriocinogenic factor**.

Colton blood group antigen a human blood group antigen based on the presence or absence of a particular point mutation in an extracellular domain of aquaporin 1 of erythrocytes.

columbinic acid *or* **ranunculeic acid** (5*E*,9*Z*,12*Z*)-octadeca-5,9,12-trienoic acid; a fatty acid occurring in some seed oils. It can relieve many of the symptoms of essential fatty acid deficiency, although it does not act as a precursor for prostaglandin synthesis.

column an upright cylindrical shaft or tube, especially the tube used to contain the stationary phase in **column chromatography** or **column electrophoresis**, or to contain the packing material in fractional distillation. By extension, the term is also used for the tube (whether vertical, horizontal, or spiral) used in **gas chromatography**.

column chromatography any method of **chromatography** in which the stationary phase is a porous solid contained in a column through which the liquid or gas phase percolates. The principal examples are **adsorption chromatography**, **gel-filtration chromatography**, **gas–liquid chromatography**, and **ion-exchange chromatography**.

column electrophoresis any method of **electrophoresis** in which the support material is contained in a column. Such a technique is usually used for preparative scale separations by **electrofocusing** or **isotachophoresis**.

column volume *symbol*: *X*; the volume (empty) of that part of a chromatographic column that contains the packing, calculated from the inner diameter and the height or length of the column occupied by the stationary phase under the conditions of use. *Compare* **bed volume**.

CoM *abbr. for* coenzyme M.

combination electrode an electrode comprising a glass electrode and a reference electrode in the same envelope providing a smaller, more compact instrument and ensuring the two electrodes are in the same environment.

combinatorial describing any process that is governed by a specific combination of factors, rather than by any single factor, with different combinations having different effects.

combinatorial chemistry *or* **virtual screening** *or* ***in silico* screening** mass screening and selection of chemical entities based on the desirability of their properties (usually as pharmaceuticals) according to a computational model.

combined test of pituitary function a test for suspected hypopituitarism. Insulin, luteinizing hormone-releasing hormone (LHRH), and thyrotropin releasing hormone (TRH) are administered and the response of pituitary hormones is compared with their levels before insulin administration. The lowering of the blood glucose level should stimulate a rise in the blood levels of cortisol and growth hormone; LHRH should increase follicle stimulating hormone (FSH) and luteinizing hormone (LH); and TRH should increase thyrotropin and prolactin.

combining site the site on an **antibody** molecule that combines with the corresponding antigen.

combrestatin a stilbene phytoalexin from *Arabidopsis thaliana* that has important antineoplastic activity.

combustion the act or process of burning, especially the quantitative conversion of organic compounds to carbon dioxide and water for elementary analysis, in the estimation of carbon-14 and tritium, or in the determination of a **heat of combustion**.

co-metabolism any oxidation of substances by a microorganism in which the energy yielded by the oxidation is not used to support microbial growth. The presence or absence of growth substrate therefore cannot be inferred from such an oxidation.

commensal **1** describing either of two different species of organism that live in close physical association with benefit to one partner but with little effect – either beneficial or harmful – on the other partner. **2** any organism in a commensal association. *Compare* **symbiosis**. **—commensalism** *n.*

commissureless a cell protein that regulates exposure of **Robo** receptors in growth cones of *Drosophila* axons that do not cross the midline. It alters intracellular trafficking of these receptors.

committed step *or* **committing reaction** a reaction in a multienzyme reaction sequence (e.g. a metabolic pathway) that once it occurs, causes all the ensuing reactions of the sequence to take place. The sole metabolic role of the committed step is to provide precursors of the final product of the pathway; it is usually a physiologically irreversible step.

common ancestor **1** the most recent ancestral form or species from which two different forms or species have evolved. **2** the node in a phylogenetic tree that is an ancestor of two given branches or leaves.

co-monomer the cross-linking agent added to the monomer in forming the gel used in **polyacrylamide gel electrophoresis**.

COMP *abbr. for* cartilage oligomeric matrix protein; a homopentameric glycoprotein (540 kDa) belonging to the thombospondin family, of unknown function and secreted by chondrocytes into their surrounding space. Each subunit contains an N-terminal region required for pentamer formation, four epidermal growth factor-like repeats, eight calcium-binding calmodulin-like repeats, and a globular C-terminal region. Over 70 mutations in the gene locus at 19p13.1 are associated with pseudoachondroplasia, in which the mutant protein forms large lamellar inclusions in the rough endoplasmic reticulum of chondrocytes and causes their death.

compactin *an alternative name for* **mevastatin**.

comparative genomics the systematic study of the similarities and differences in gene content and structure of whole genomes. Genome comparisons may shed light on the evolution of organisms, for example by locating 'missing' genes, pinpointing horizontal transfer events, and so on.

compartment **1** *(in tracer kinetics)* any anatomical, physiological, chemical, or physical subdivision of a system throughout which the concentration ratio of labelled to unlabelled substance is uniform at any given time. It is understood that the rate at which the tracer entering the compartment is mixed with tracer in the compartment is rapid compared with the rate at which the substance leaves the compartment. **2** any subdivision of a model used for the analysis of experimental observations.

compartmentation *or* **compartmentalization** the unequal distribution of a metabolite, enzyme, or metabolic pathway between different parts of a cell (e.g. in cell organelles) or of a whole organism. Consequently only a part of the total of any given chemical present is apparently available for a given reaction. It may refer to morphologically recognizable structures or to **metabolic pools**.

compatibility group *see* **incompatibility group**.

compatible solute a compound accumulated in plants and microorganisms to maintain osmotic balance, and to stabilize macromolecules against various forms of stress, including heat, freezing, and radical damage. Examples include trehalose and glycine betaine.

competence **1** the ability of a cell to take up a molecule of exogenously added DNA, and to be transformed by it (*see* **transformation**). **2** the ability of bacterial cells to incorporate phage DNA and to produce phage progeny (*see* **bacteriophage**). **3** the state of reactivity of a cell, tissue, or organism that allows it to respond to specific stimuli by forming new morphological structures or by synthesizing specific proteins (enzymes).

competence factor a secreted protein, or other substance added in culture, that is essential for **competence** in a bacterial or other cell. A 10 kDa basic protein of this type has been isolated from streptococci. It does not bind to DNA but interacts with the cell surface.

competition *(in chemistry)* rivalry between two or more different, but often similar, chemical species for a specific biochemical system, e.g. a receptor, enzyme, transport system, antibody molecule, or ion exchanger.

competition binding *see* **displacement binding**.

competitive antagonism the competition between an **agonist** and an antagonist for a receptor that occurs when the binding of agonist and antagonist is mutually exclusive. This may be because the agonist and antagonist compete for the same binding site, or combine with adjacent but overlapping sites. A third possibility is that different sites are involved but that they influence the receptor macromolecule in such a way that agonist and antagonist molecules cannot be bound at the same time. If the agonist and antagonist form only short-lived combinations with the receptor, so that equilibrium between agonist, antagonist, and receptor is reached during the presence of the agonist, the antagonism will be surmountable over a wide range of concentrations (*see* **reversible competitive antagonism**). In contrast, some antagonists, when in close enough proximity to their binding site, may form a stable covalent bond with it (*see* **irreversible competitive antagonism**); the antagonism becomes insurmountable when no spare receptors remain. More generally, the extent to which the action of a competitive antagonist can be overcome by increasing the concentration of agonist is determined by the relative concentrations of the two agents, by the association and dissociation rate constants for their binding, and by the duration of the exposure to each. The action of a competitive antagonist can therefore be surmountable under one set of experimental conditions and insurmountable under another.

competitive binding competition between two or more different chemical species for a limited number of binding sites in a biochemical system, such as a receptor, enzyme, transport system, or antibody molecule. *See also* **competition**.

competitive inhibition any inhibition of an enzyme activity by an inhibitor that binds to the same active site on the enzyme as does the substrate and when there is no interaction between the inhibitor and the enzyme–substrate complex, nor between the substrate(s) and the enzyme–inhibitor complex. Characteristically, analysis using a Lineweaver–Burk plot reveals that in the presence of a **competitive inhibitor** $V_{\max}$ is unchanged and K_m is increased.

competitive inhibitor any inhibitor that produces **competitive inhibition** of the activity of an enzyme. Inhibition produced by a given level of inhibitor can be overcome by an increase of substrate concentration.

competitive protein-binding assay *abbr.*: CPBA; a form of **saturation analysis** in which a naturally occurring proteinaceous binding substance is used.

complement *or (formerly)* **alexin(e)** a system of proteins and cell receptors, found in the plasma of vertebrates, that participates in immune defence against infection by microorganisms; the activation products of complement components cause lysis of antigenic cells, attract phagocytic cells to the site of activation, and assist the uptake and destruction of antigenic cells by phagocytes. Complement is also involved in immunological tissue injury. The plasma components comprise a recognition unit, three alternative pathways for activation of C3 (the classical pathway uses C2 and C4), and a terminal pathway that ends in the formation of the membrane attack complex (C356789). Synthesis occurs mainly in hepatocytes and that of several components is regulated by interleukins 1 and 6, tumour necrosis factor, γ interferon, and endotoxic polysaccharide. The plasma components amount to about 2000 mg L^{-1} (C1 ≈250, C3 ≈1200, C4 ≈400 mg L^{-1}). The components of complement, mostly β- or γ-globulins, are generally designated by the symbol C and an identifying suffixed numeral. There are three alternative pathways for activation of complement, and these probably work together. The classical pathway is followed below. The alternative pathway uses properdin and factors B and D to activate C3 and C5. The lectin pathway utilizes mannose-binding protein and its associated serine protease (MASP), and activates C3 as in the classical pathway but without a requirement for C1.

C1 is a Ca^{2+}-dependent complex of C1q, C1r, and C1s in the molar ratio of 1:2:2. C1q has a 'bunch-of-tulips' structure that consists of six collagen-like triple helices each ending in a globular C-terminal domain, which binds the Fc region of immune complexes. Each triple helix consists of homologous A, B, and C chains, which are encoded on neighbouring genes, and contain a collagen-like domain over ≈80% of their length, while the rest contributes to the C-terminal globular head. C1r and C1s are highly homologous serine protease zymogens (83 kDa per subunit). Two subunits of each bind C1q in a calcium-dependent but noncovalent manner. Binding of ligand to C1q causes a conformational change in, and autocatalytic activation of, C1r (EC 3.4.21.41), which then cleaves and activates C1s. The natural substrates for C1s are C2 and C4. Deficiency of A, B, or C chains of C1q results in the clinical phenotype of lupus erythematosus. Deficiency of C1r or C1s also leads to this phenotype or to glomerulonephritis.

C2 is a single-chain polypeptide (102 kDa) that is highly homologous with factor B. C1s releases a small peptide (S2b) and (active) C2a. C2a and C4b form a bimolecular enzyme called **C3 convertase**, a serine proteinase (EC 3.1.21.43). Deficiency of C2 results in rheumatic disorders and pyogenic infections.

C3 is a glycoprotein (185 kDa) that consists of an α chain linked by a disulfide bond to a β chain, both being derived from the same precursor, which is homologous with C4 and C5. The α chain contains an intrachain thiol ester that is important for the function of C3. C3 convertase (i.e. C4b2a) cleaves a small peptide, which is the N-terminal region of the α chain, to expose the thiol ester. C3a is an anaphylatoxin. The rest of the molecule (C3b) binds covalently (through the thiol ester) to cell surfaces or the immune complex, and in complex with C3 convertase forms C4b2a3b, which is called **C5 convertase**. Deficiency of C3 leads to rheumatic disorders and pyogenic infections.

C4 is a glycoprotein (200 kDa) that consists of disulfide bond-linked α, β, and γ chains, all derived from the same precursor, which is homologous to those of C3 and C5. The α chain contains an intrachain thiol ester, which is important for the function of C4. C1s releases C4a, the N-terminal portion of the α chain, and exposes the thiol ester. This binds covalently to cell surfaces or to immune complexes. The rest of the molecule is C4b, which with C2a forms C4b2a, or C3 convertase. In combination with C3b, C3 convertase forms C4b2a3b, which is C5 convertase. Deficiency of C4 leads to a lupus erythematosus phenotype. The human form is polymorphic, the allotype being C4a. C4a alleles carry blood group Rogers and C4b alleles carry Chido. Total deficiency of C4a6 allotype is associated with hemolytic disease.

C5 is a glycoprotein (190 kDa) that consists of an α chain linked by a disulfide bond to a β chain, both derived from a precursor homologous to those of C3 and C4. C5 convertase (i.e. C4b2a3b) releases a small anaphylatoxic and leukocyte-attractant peptide (C5a), which is the N-terminal region of the α chain. Activation of C5 initiates the spontaneous assembly of the late complement components, C5–C9, into the membrane attack complex (*see* **MAC** (def. 1)). C5b recruits a molecule of each of C6, C7, and C8, which insert their hydrophobic regions into the target cell membrane. Deficiency of C5 leads to meningococcal infection.

C6, **C7**, **C8**, and **C9**, together with C5b, constitute the membrane attack complex; all are structurally related and similar to **perforin**. C6 is a single-chain polypeptide (128 kDa) that interacts with C5b, C7, and C8. C7 is a single-chain polypeptide that interacts with C5b, C6, and C8. C8 is a heterotrimer comprising α, β, and γ subunits. An α chain is linked by a disulfide bond to a γ chain, and a β chain then links to these two chains. C8 interacts with C5b, C6, and C7, the complex inserting into the target cell membrane. C9 is a single-chain polypeptide (70 kDa). From 1 to 18 molecules of C9 are recruited by the C5b678 complex to form a tubular transmembrane channel that disturbs the target cell membrane and increases its permeability. It is cleaved by thrombin to form C9a and C9b. Deficiency of C6, C7, C8, or C9 is associated with meningococcal infection.

Factor B, a zymogen of M_r 100 000, is activated by factor D, which selectively cleaves an Arg-|-Lys bond when factor B is complexed with C3b to form factor Bb. Following cleavage the C3b–Bb complex acts as **alternative-complement-pathway C3/C5 convertase** (EC 3.4.21.47), which can convert C3 to C3a and C3b by cleaving an Arg-|-Ser bond, and C5 to C5a and C5b by cleavage of an Arg-|-Xaa bond.

Factor $\overline{\mathrm{D}}$ is a serine proteinase (EC 3.4.21.46) of M_r 24 000; its concentration in human plasma is approximately 1.5 mg L^{-1}.

Factor H is a cofactor for **factor I** (EC 3.4.21.45), a serine proteinase that cleaves the α chains of C4b and C3b in the presence of the cofactors for C4-binding.

Properdin, a glycoprotein of M_r 220 000, is composed of four, probably identical, noncovalently linked polypeptide chains. Two alternative reaction cascades for the activation of complement exist. In the so-called **classical pathway**, activation (which requires both Ca^{2+} and Mg^{2+}) is initiated by the binding of the C1q moiety of C1 to the C_H2 regions of antibody molecules in antibody–antigen aggregates or in antibody bound to cells, thus causing C1 to be converted to a proteinase, $\mathrm{C}\overline{1}$. $\mathrm{C}\overline{1}$ activates C4 and C2 leading to the formation of **C3 convertase**, a complex proteinase, $\mathrm{C}\overline{42}$, consisting of the activated components $\mathrm{C}\overline{4}$ and $\mathrm{C}\overline{2}$. $\mathrm{C}\overline{42}$ splits C3 to the chemotactic and anaphylatoxic fragment C3a and the fragment $\mathrm{C}\overline{3}$, C3b, which associates with $\mathrm{C}\overline{42}$ to give a $\mathrm{C}\overline{42\,3}$ complex, **C5 convertase**. The latter is a complex proteinase that in turn splits C5 to $\mathrm{C}\overline{5}$ and the chemotactic and anaphylatoxic fragment C5a. In the so-called **alternative pathway**, activation (which requires Mg^{2+} but not Ca^{2+}) is initiated by polysaccharides such as those present on bacterial and yeast cell walls. The proteinase $\overline{\mathrm{D}}$ is analogous to $\mathrm{C}\overline{1}$ but is normally present in serum, where it causes a continuous slow activation, which is greatly enhanced when polysaccharides are present. $\overline{\mathrm{D}}$ acts on B and $\mathrm{C}\overline{3}$ to produce $\mathrm{C}\overline{3\mathrm{B}}$, an alternative C3 convertase. $\mathrm{C}\overline{3\mathrm{B}}$, which is stabilized by properdin, acts on C3 to produce $(\mathrm{C}\overline{3})_n\overline{\mathrm{B}}$, an alternative C5 convertase. In both pathways, $\mathrm{C}\overline{5}$ production is the last proteolytic step, and there follows a spontaneous association of $\mathrm{C}\overline{5}$ with C6, C7, C8, and C9 to form a lytic complex, $\mathrm{C}\overline{56789}$. *See also* **lysine(arginine) carboxypeptidase**.

complementarity **1** the interrelationship between one or more units supplementing, being dependent on, or being in a polar position to another unit or units. **2** a reverse correspondence of part of one molecule to part of another molecule, especially of antigen to antibody, enzyme to substrate, or the partners in a **base pair**.

complementarity-determining region (*abbr.*: CDR) *or* **hyper-**

variable region the most variable (hypervariable) region of an antibody molecule (or other member of the immunoglobulin superfamily), comprising three loops (CDR1, CDR2, CDR3) from the heavy chain and three from the light chain. Together, the CDRs form a complementary surface to the antigen, and act as the antigen-binding site. Antibodies with different specificities have different CDRs; those with the same specificity have identical CDRs.

complementary base sequence a sequence in a polynucleotide chain in which all the bases are able to form **base pairs** with a sequence of bases in another polynucleotide chain.

complementary catalysis catalysis in the presence of a prototype molecule, leading to the formation of products with a structure that is in some way complementary to that of the prototype.

complementary DNA *abbr*.: cDNA; a DNA molecule that has a **complementary base sequence** to a molecule of a messenger RNA. The first strand, with the complementary nucleotide sequence, is synthesized by reverse transcriptase using the RNA as template. A second DNA strand is then synthesized by DNA polymerase using the first strand as template. The two strands together represent a double-stranded DNA copy of the mRNA. cDNA is used for **molecular cloning**, or to yield molecular **probes** (def. 3) in hybridization tests for a specific sequence in cellular DNA. It has the advantage that, unlike genomic DNA, it contains no introns. A population of cDNAs cloned in a suitable vector and representative of the mRNAs in a cell or tissue constitutes a **cDNA library**. cDNA must be distinguished from the complementary strand of duplex DNA (*see* **noncoding strand**).

complementary genes any genes that interact to produce a qualitative effect that is distinct from the effects of any one of them separately.

complementary RNA *abbr*.: cRNA; a single-stranded RNA molecule that has a **complementary base sequence** to a specific (chromosomal) DNA sequence (of either strand), from which it is produced by the action of DNA-directed **RNA polymerase**. Naturally occurring cRNA may represent **pre-messenger RNA**, **ribosomal RNA**, or **transfer RNA**. cRNA can also be produced by transcription *in vitro*, usually from a DNA template with a promoter for a bacteriophage RNA polymerase. *Compare* **antisense RNA**.

complementary strand (of duplex DNA) *see* **noncoding strand**.

complementation 1 any instance in which the interaction of two incomplete, nonfunctional systems results in a fully functional system. **2** the interaction between viral gene products or gene functions in cells that are multiply or mixedly infected with virus(es), leading to an increased yield of infective virus of one or more parental types. **3 genetic complementation**.

complementation test any experimental test for **genetic complementation**. *See* ***cis–trans* complementation test**.

complement-3 convertase *an alternative name for* C3 convertase; *see* **complement**.

complement-5 convertase *an alternative name for* C5 convertase; *see* **complement**.

complement decay-accelerating factor *abbr*.: DAF; a factor that interferes with catalysis of the conversion of component C2 and factor B of **complement**, and prevents formation of the amplification convertases of the complement cascade. DAF is expressed on the plasma membranes of all cell types that are in intimate contact with plasma complement proteins, and is a glycosylphosohatidylinositol-anchored protein. Human proteins DAF1 and DAF2 are formed by alternative splicing of a transcript of the same gene.

complement fixation activation of the **complement** system, characteristically *in vitro* by an antigen–antibody interaction, in which complement components C1 to C9 are activated sequentially.

complement-fixation inhibition test a serological test in which the presence of a substance of known structure either may or may not inhibit the interaction of antibody with complex antigen, and hence also the fixation of **complement**. *Compare* **complement-fixation test**.

complement-fixation test a serological test for the presence of antibody that can fix **complement** on interaction with antigen. The presence or absence of residual complement is detected by an indicator system, e.g. added sheep erythrocytes sensitized with an antibody to sheep erythrocytes. If complement is still present, lysis of the erythrocytes occurs, but if no complement remains, no lysis takes place.

complement receptor any cell-surface receptor that binds activated **complement** components, e.g. the receptor for C3b found on macrophages, neutrophils, and B lymphocytes.

complete Freund's adjuvant *see* **Freund's adjuvant**.

complex 1 any distinct chemical species in which two or more identical or nonidentical chemical species (ionic or uncharged) are associated, usually in stoichiometric proportions, and bound together by weaker interactions than covalent bonds. The term is used for various entities, e.g. coordination complexes, antigen–antibody complexes, enzyme–substrate or enzyme–inhibitor complexes, multienzyme complexes, and receptor–agonist complexes; it is often employed where the precise nature of the interaction is uncertain. **2** to make a complex or incorporate into a complex, especially of a metal ion and a **chelating agent**; to chelate.

complex I, II, III, IV the cytochrome-containing protein complexes that, with associated ligands including ubiquinone, Fe–S clusters, FMN, FAD, and nicotinamide nucleotides, form the mitochondrial electron-transport chain or **respiratory chain**. Each complex can be isolated separately and with suitable substrates and electron acceptors can function independently in transporting electrons. Complexes I, III, and IV are also involved in proton translocation, a function that requires the complex to be embedded in an orientated environment such as that provided by the intact lipid bilayer of the mitochondrial inner membrane. Complex I (EC 1.6.5.3) – NADH dehydrogenase (ubiquinone) – contains ≈40 different polypeptides of which 7 are encoded in mtDNA. The complex includes one flavoprotein and seven polypeptide subunits including **NADH dehydrogenase (ubiquinone)**, together with FMN and a number of different iron–sulfur clusters containing nonheme iron in the forms Fe–S, Fe_2–S_2, and Fe_4–S_4, the iron of which undergoes oxidation–reduction between oxidation states II and III. The complex contains ≈31 hydrophobic polypeptides. The reaction catalysed is the oxidation of NADH by ubiquinone. Complex II (EC 1.3.5.1) contains four subunits of **succinate dehydrogenase (ubiquinone)**, FAD, and iron–sulfur. It catalyses the oxidation of succinate by ubiquinone. Complex III (EC 1.10.2.2) contains 11 polypeptides including the four redox centres: cytochrome b_{562}, cytochrome b_{566}, cytochrome c_1, and the Rieske protein, which contains an Fe_2– S_2 cluster. Cytochrome *b* is encoded in mtDNA. It catalyses the oxidation of ubiquinol by oxidized cytochrome *c*. The transfer of electrons to cytochrome c_1 involves the **protonmotive Q cycle**. Complex IV (EC 1.9.3.1) contains the 13 polypeptide subunits of cytochrome *c* oxidase, including cytochromes *a* and a_3, and Cu^{2+}. Three polypeptides are encoded in mtDNA. It catalyses the oxidation of reduced cytochrome *c* by dioxygen. Numerous mutations in the genes in nuclear DNA and in mtDNA for protein components of these complexes produce a vast array of clinical manifestations in virtually all age groups and in most body tissues and systems.

complexation the act or process of forming a (chelate) **complex**, e.g. to render inorganic substances soluble in organic solvents.

complex closed DNA a DNA structure comprising catenated and concatenated circular polynucleotide oligomers. *See* **catenane**, **concatemer**.

complex formation *see* **complex** (def. 2), **complexation**.

complexity *(in molecular biology)* the number of different sequences in DNA as defined by hybridization kinetics.

complexometric titration any titration in which the titrant contains a complexing (chelating) agent that interacts with a metal ion or other chemical species in the test solution, the end point being determined either electrometrically or with an indicator.

complexometry any method for the determination of a metal ion (or other chemical species) involving the formation of a chemical **complex**.

complexone any complex-forming or chelating agent, especially any macrocyclic antibiotic that complexes metal ions.

Complexone *a proprietary name for* **EDTA**.

composite database a database that amalgamates different primary sources, often using criteria that determine the priority of inclusion of the sources and the level of redundancy retained. For example, nrdb (nonredundant database) combines sequences from GenBank (CDS translations), PDB, Swiss-Prot, PIR, and PRF; INSD (International Nucleotide Sequence Database) is an amalgam of nucleotide sequences in EMBL, GenBank, and DDBJ; UniProt (universal protein sequence database) is a collation of protein sequences from PIR-PSD, Swiss-Prot, and TrEMBL; wwPDB (worldwide PDB) is a composite of 3D structures in the RCSB (Research Collaboratory for Structural Bioinformatics), PDB, MSD, and PDBj. *See* **sequence database**.

compound any substance containing two or more identical or nonidentical chemical atoms in fixed numerical proportions and held together by one or more kinds of chemical bond.

compound A, B, C (etc.) *see* **Kendall's compounds**.

compound heterozygote an individual who has a recessive genetic disease resulting from the inheritance of two different mutant alleles of the same gene.

compressed file a computer file or collection of these in **archive format** that has been compressed by an appropriate algorithm such as that of Lempel-Zif. In UNIX and Linux such files have the extensions .Z or .gz. For PCs the extension is usually .zip and for Apple Macintosh 'stuffit'. The program that does the compression shows the file as an appropriate icon. Some compressed files may be programs that uncompress themselves. Others require decompression utilities such as WINZIP (Microsoft PCs) or uncompress or gunzip (UNIX and Linux). A good **software archive** will include notes (typically in a file called README or 00README) on decompression utilities that are required.

compression *see* **band compression**.

comproportionation any chemical reaction that is the reverse of **disproportionation**.

Compton effect *or* **Compton scattering** the scattering of photons by free particles that results in an increased photon wavelength (i.e. a decrease in photon energy) and a corresponding increase in the particles' velocity (i.e. an increase in the particles' kinetic energy). [After Arthur Holly Compton (1892–1962), US physicist.]

computer-assisted tomography *abbr*.: CAT; *see* **tomography**.

computer of average transients *abbr*.: CAT; an electronic device of many separate channels in which a set of signals (e.g. an NMR spectrum) is repeatedly scanned and the signals stored additively. The stored signals grow linearly with the number of scans but the noise, being random, grows only as the square root of the number of scans taken, thereby improving the signal-to-noise ratio.

COMT *abbr. for* catechol *O*-methyltransferase, EC 2.1.1.6.

comutagen any nonmutagenic agent that enhances the effect of a mutagen.

comutation the occurrence of a mutation near to, and at the same time as, another specified mutation.

con A *abbr. for* concanavalin A.

conalbumin *or* **ovotransferrin** a protein of ~77 kDa that comprises ~12% of the total solids of egg white. It is distinguishable from **ovalbumin** by its lower thermal coagulation point. It binds Fe^{3+} ions. The amino-acid sequence of conalbumin is identical to that of chicken serum **transferrin**, but their carbohydrate moieties are different.

conantokin G *also called* **sleeper peptide**; a toxic peptide from the venom of *Conus geographicus* (fish-hunting cone snail). It is an antagonist of brain **NMDA receptors**. It has the sequence

GEXXLQXNQXLIRXKSN,

where X = γ-carboxyglutamate (Gla). The five Gla residues bind Ca^{2+}.

conarachin a minor globulin occurring, together with **arachin** (def. 1), in seeds of the peanut, *Arachis hypogaea*.

conc. *abbr. for* concentrated.

concanavalin A *abbr*.: con A; an agglutinating and mitogenic protein (*see* **lectin**) that constitutes the major component of the subsidiary globulin fraction (originally named **concanavalin** because it accompanied **canavalin** in purification) obtained from the ripe seeds of the **jack bean**. It is separable from **canavalin** and from the minor component **concanavalin B** by differences in solubility. It is a crystallizable tetramer, with 27.5 kDa subunits, dissociating to a dimer below pH 5.8. Each subunit contains one binding site for Mn^{2+} (or other transition metal ion), one for Ca^{2+}, and one for carbohydrate (specifically α-D-mannopyranoses or α-D-glucopyranoses with unmodified hydroxyl groups at C-3, C-4, and C-6); carbohydrate does not bind until the metal binding sites are filled. It agglutinates erythrocytes, and precipitates polysaccharides containing a sufficient number of appropriate terminal residues. It is mitogenic, transforming lymphocytes to blast cells, and can agglutinate some animal tumour cells and inhibit their growth. The precursor is processed in an unusual way: the mature chain consists of residues 164–281 followed by 30–148; to form a mature chain, the precursor undergoes further **PTM**, after removal of the signal sequence; cleavage after Asn at positions 148, 163, and 281 is followed by transposition and ligation (by formation of a new peptide bond) of residues 164–281 and 30–148.

concanavalin B a minor crystallizable protein obtained from ripe seeds of the **jack bean**, and separable from **canavalin** and **concanavalin A**.

concatemer *or* **concatenate** originally, an intermediate structure in the biosynthesis of certain DNA viruses, consisting of a number of genomes connected together end to end, and thought to be the immediate precursor to the mature viral genome. The term is now extended to include any linear or circular DNA structure composed of viral genomes joined end to end. The term is also used for circular DNAs which are physically inseparable, one being threaded through the other. *Compare* **catenane**. **—concatemeric** *adj.*

concatenate **1** to join or link together, end to end. **2** joined or linked together. **3** *an alternative term for* **concatemer**. *Compare* **catenate**. **—concatenated** *adj.*; **concatenation** *n.*

concatenated dimer *or* **circular dimer** any circular **concatemer** containing two DNA molecules.

concentrate **1** to reduce the volume of a solution or dispersion by removal of solvent or dispersing medium. **2** to make or become purer or more concentrated by removal of impurities from a substance or material. **3** a concentrated solution or material, especially of foodstuffs, e.g. a vitamin concentrate. **—concentrating** *n.*

concentrated **1** *abbr*.: conc.; *(of a solution, dispersion, or mixture)* containing a relatively high concentration (of a specified solute, kind of dispersed particle, or component); (of substance, particles, etc.) present at relatively high concentration (in a solution, dispersion, etc.). *Compare* **dilute** (def. 1). **2** *(of a solution, dispersion, or mixture)* increased in concentration and reduced in volume by removal of solvent, dispersing medium, or admixed material. *Compare* **diluted**.

concentration *abbr*.: concn.; **1** (**a**) **mass concentration** *or* **mass density** *symbol*: ρ or γ; an SI derived physical quantity; it equals the mass of a specified component per unit volume of the system in which it is contained. It is expressed in kg m^{-3}. (**b**) **amount-of-substance concentration** *or* **amount concentration** *or (in clinical chemistry)* **substance concentration** *symbol*: *c*; an SI derived physical quantity; it equals the number of moles of a specified component per unit volume of the system in which it is contained. Where there is no risk of confusion the term **concentration** may be used alone. It is expressed in mol m^{-3} or mol dm^{-3}. Amount concentration continues to be expressed often in terms of the litre (*symbol*: l *or* L), which is not an SI unit, although 1 L = 1 dm^3. The older, non-SI, term *molarity* is still commonly used for this quantity; a solution of, say, 1 mol dm^{-3} concentration may thus be referred to also as a 1 molar solution or denoted a 1 M solution, where M is treated as a symbol for mol dm^{-3} (or mol L^{-1}). *See* **molar** (def. 2). (**c**) **surface concentration** *symbol*: Γ; an SI derived physical quantity; it equals the number of moles of a specified substance per unit area of the surface at which it is present. It is expressed in mol m^{-2}. (**d**) **number concentration** *or* **number density** *symbol*: *C or (sometimes) n*; an SI derived physical quantity; it equals the number of specified particles or molecular entities per unit volume of the system in which it is contained. It is expressed in m^{-3}. *Note*: The concentration of a solute in solution may sometimes be expressed in more convenient units esp. in a percentage; e.g. (for solids) as the mass of solute in grams per 100 millilitres of solution (*abbr*.: % w/v), or (for liquids) as the number of volumes of solute per 100 volumes of solution (*abbr*.: % v/v). *See also* **activity** (def. 3), **molality**, **osmolality**, **osmolarity**. **2** the act or process of concentrating. *See* **concentrate** (def. 1, 2).

concentration equilibrium constant any **equilibrium constant** expressed in terms of concentrations rather than activities.

concentration gradient the change of concentration with distance, e.g. the change in concentration of a solute across a membrane or along a gradient.

concentration of enzymic activity *(obsolete) see* **enzymic activity**.

concentration polarization *(in membrane ultrafiltration)* the accumulation of retained macrosolutes on the membrane, forming a secondary membrane, that results in restriction of transport through the filter and alteration of selectivity, which may lead to rejection of normally permeating species.

concentration quenching the **quenching** of fluorescence that becomes significant when the fluor concentration is increased beyond a certain point. It is of importance, e.g., in liquid scintillation counting and in experiments involving the introduction of fluorescent groups (probes) into macromolecules.

concentration ratio *or* **dose ratio** *symbol*: r; the ratio of the concentration of an agonist that produces a specified response (often but not necessarily 50% of the maximal response to that agonist in an assay) in the presence of an antagonist, to the agonist concentration that produces the same response in the absence of antagonist.

concentric cylinder viscometer *an alternative name for* **Couette viscometer**.

conceptual translation the computational process of translating the sequence of nucleotides in mRNA, by means of the genetic code, to a sequence of amino acids.

concerted reaction any chemical reaction in which two chemical processes occur within the same reaction step; i.e. one in which a new chemical bond is formed at the same time as, and as a direct result of, the breaking of another chemical bond.

concerted symmetry model a model of ligand binding to oligomeric proteins in which the characteristic assumption is that molecular symmetry of the **oligomer** is conserved so that only two states are accessible to it: either with all the **protomers** in the first conformational state, or all the protomers in the second state. *See* **Monod–Wyman–Changeux model**.

concerted transition the simultaneous transition of all identical subunits (i.e., protomers) of an oligomeric molecule from the first conformational state to the second state, and vice versa, as is required in any **concerted symmetry model** for allosteric proteins.

concn. *abbr. for* concentration.

concordance the condition in which both members of a twin pair, or any two comparable individuals or species, possess the same gene, phenotype, or trait. **—concordant** *adj.*; **concordantly** *adv.*

condensate any product of a **condensation**, especially a liquid from a gas or vapour.

condensation 1 the act or process of condensing; the state of being condensed. **2** the product of condensing; a condensed mass. **3** any (usually stepwise) chemical reaction in which two or more identical or nonidentical molecular entities, or two parts of one entity, combine with the elimination of a molecule of water, ammonia, ethanol, hydrogen sulfide, or other simple substance. The combining entities or parts each (formally) contribute a moiety to the molecule eliminated.

condensation polymerization a polymerization by repeated condensation, i.e. with elimination of some simple substance, to form a **condensation polymer**.

condense 1 to make or to be made more compact or denser. **2** to change or cause to change a gas or vapour to a liquid or solid. **3** (of a compound) to undergo or cause to undergo a **condensation** (def. 3).

condensed 1 converted to a dense or denser form; e.g. **condensed DNA** in **nucleosomes** or in the early stages of maturation of T-even phages; or the **condensed form of mitochondria** in which the cristae are swollen, the matrix volume is much reduced, and the inner membrane space is increased. **2** reduced from the gaseous to the liquid state.

condenser 1 any device for converting a gas or vapour into a liquid (or solids) by cooling. **2** a lens or set of lenses that concentrates light into a small area. **3** *a former name for* capacitor; an electrical component that stores electric charge.

condensin a protein complex that binds to sister chromatids to cause their disentanglement. It consists of Smc2 and Smc4 (*see* **Smc**) and three other proteins.

condensing enzyme 1 citrate condensing enzyme, EC 4.1.3.7; *see* **citrate (*si*)-synthase**. **2** β-oxoacyl-ACP synthase, EC 2.3.1.41; 3-oxoacyl-[acyl-carrier-protein]synthase (*see* **fatty acid synthase complex**).

conditional association constant *or* **conditional stability constant** an **association constant** determined in conditions similar to those in which the reaction under consideration is taking place, e.g. in the internal milieu of a cell.

conditional lethal mutation any mutation that produces a mutant (**conditional lethal mutant**) whose viability depends on the conditions of growth. It grows normally in permissive conditions but in restrictive conditions it does not grow, thereby expressing its lethal mutation. *See*, e.g., **temperature-sensitive mutation**.

conduct to allow the passage of electricity, heat, or electromagnetic radiation.

conductance *see* **electric conductance**.

conductance water *an alternative name for* **conductivity water**.

conductimetric *or* **conductiometric** *a variant spelling of* conductometric; *see* **conductometry**.

conductimetry *or* **conductiometry** *a variant spelling of* **conductometry**.

conduction 1 the transfer of heat or electricity through a material. **2** the transmission of an impulse, either electrical or chemical, along a nerve fibre.

conductivity 1 electrical conductivity *symbol*: κ; a measure of the ability of a material to conduct an electric current or impulse. It is defined as the reciprocal of the resistivity of the material, and is expressed in siemens m^{-1}. *See also* **electrolytic conductivity**. **2 thermal conductivity**.

conductivity water *or* **conductance water** very pure water, of electrolytic conductivity $<1 \times 10^{-4}$ siemens m^{-1}.

conductometric titration any titration in which the end point is indicated by an inflection in the curve of conductivity against volume of titrant added. For instance when an HCl solution is titrated with an NaOH solution, the conductivity decreases as the faster moving H_3O^+ ions are replaced by slower moving Na^+ ions; after the equivalence point the conductivity increases as the concentration of the fast-moving OH^- ions increases.

conductometry *or* **conductimetry** *or* **conductiometry** any method of chemical analysis based on measurements of electrical conductivity. **—conductometric** *adj.*

conductor any substance or system that allows the passage of electricity, heat, or electromagnetic radiation.

cone cell *or* **cone** one of the two types of light-sensitive cell of the vertebrate retina (*compare* **rod cell**). Cone cells are conical or flask-shaped, and contain the photopigment **iodopsin** or (in freshwater and migratory fishes and some amphibians) **cyanopsin**. They are responsible for photopic (daylight) vision, and are densest in the fovea and absent from the margin of the retina. Human cone cells are thought to be of three types, each containing an iodopsin of different spectral sensitivity; hence they are responsible also for colour vision.

cone/rod dystrophy any of the disorders of eyesight resulting mainly from mutation of the *CRX* (cone-rod homeobox containing) or *RPGR* (retinitis pigmentosum GTPase regulator) genes. *See* **CRX**.

cone-rod homeobox protein *see* **CRX**.

confidence limits *(in statistics)* the upper and lower limits of the range of values within which the true mean is expected to lie, on the basis of an estimate of the mean obtained from a sample of values. The confidence limits vary according to the (specified) probability that they will be correct.

configuration classically, the arrangement of the atoms of a molecule in space, without regard to arrangements that differ only as after rotation about one or more single bonds; the term is now sometimes limited so that no regard is paid to π-bonds or to bonds of a partial order between one and two, and sometimes further limited so that no regard is paid to rotation about bonds of any order, including double bonds. Interconversion of molecules of different configurations requires the formal making and breaking of covalent bonds, no account being taken of changes to hydrogen bonds.

Compare **conformation**. *See also* **absolute configuration**, **pyrimidine dimer**. —**configurational** *adj.*

configurational base unit (of a polymer) a **constitutional base unit** of the polymer whose configuration is defined at the minimum at one site of steric isomerism in the main chain of the polymer.

configurational block a **block** in a polymer containing only one species of **configurational base unit**.

configurational inversion *see* **racemize**, **Walden inversion**.

configurational isomer any of two or more isomers that differ only in stereochemical **configuration**.

confluence *(in cell culture)* the state reached when one or more cells or groups of cells, grown in culture on (so-called) solid medium, have multiplied to cover the surface of the medium completely but without overlying each other. —**confluent** *adj.*

confocal microscope a microscope that produces a series of images, often called optical sections, that have much better resolution than images of the same specimens obtained using conventional epifluoresence light microscopy. Such a microscope depends on laser light focused through a pinhole onto a single point in the specimen. From a succession of such images a 3-D image can be created. This is primarily used in biological imaging for mapping the distribution of fluorescently labelled macromolecules, such as antibodies, in various tissues.

conformation the various arrangements of the atoms of a molecule (of defined **configuration**) in space that differ only as after rotation about single bonds; the term is now sometimes extended to include rotation about π-bonds or bonds of partial order between one and two, and sometimes further extended to include also rotation about bonds of any order, including double bonds. Interconversion of molecules of different conformations does not involve the breaking and making of chemical bonds (except hydrogen bonds) or changes in **chirality**. The following special terms and symbols distinguish different possible conformations of various classes or portions of molecules.

(1) **Cyclic compounds**. Nonplanar six-membered rings may exist in **boat conformation**, **chair conformation**, **half-boat conformation**, **half-chair conformation**, **skew conformation** (def. 1), or **twist conformation** (def. 1); and nonplanar five-membered rings may exist in **envelope conformation** or **twist conformation** (def. 2). For a six-membered or five-membered ring form of a monosaccharide or monosaccharide derivative these conformations may be designated by the following conformational descriptors suffixed to their chemical names: -*B*, boat; -*C*, chair; -*E*, envelope; -*H*, half-chair; -*S*, skew; -*T*, twist; the locants of the ring atoms that lie above and/or below the reference plane, when the numbering appears clockwise, may be added to these symbols as left superscripts and/or right subscripts, respectively. A bond to a tetrahedral atom in a six-membered ring is termed **axial** (*abbr.*: a) if it or its projection makes a large angle with the plane containing a majority of the ring atoms, and **equatorial** (*abbr.*: e) if this angle is small; the same terms are applied to atoms or groups attached to such bonds. The corresponding terms for a bond from an atom directly attached to a doubly bonded atom in a monounsaturated six-membered ring are **pseudoaxial** (*abbr.*: a′) and **pseudoequatorial** (*abbr.*: e′), respectively.

(2) **Nucleotides**. When atom C-2′ or C-3′ of the ribo- or deoxyribofuranose ring of a nucleotide lies out of the plane of the other four ring atoms, the ring conformation is designated by the descriptor *endo*- if either atom lies above the ring, i.e. towards the nitrogenous base, and by the descriptor *exo*- if it lies below the ring, i.e. away from the base. In addition the base and sugar rings may be in either of two relative positions: the conformation is said to be **anticlinal** (*abbr.*: *anti*-) if the groups at positions 2 and 3 of a pyrimidine residue or positions 1, 2, and 6 of a purine residue lie away from the sugar ring, and **synclinal** (*abbr.*: *syn*-) if these groups lie over the sugar ring.

(3) **Torsion angle**. If rotation about a given bond in a molecule is restricted for any reason, the conformation of atoms or groups about that bond may be described by the **torsion angle** (*symbol*: θ). When, in a **Newman projection**, two atoms or groups attached at opposite ends of a bond appear one more or less directly behind the other, i.e. $\theta \approx 0°$, these atoms or groups are termed **eclipsed**, and that portion of the molecule is described as being in the eclipsed conformation. If not eclipsed (in an ideal case, when all torsion angles equal 60°), the atoms or groups are termed **staggered**, and the molecule is described as being in the staggered conformation; such a conformation is termed **synperiplanar** (*abbr.*: *sp*) (or sometimes *cis* (*abbr.*: c)), **synclinal** (*abbr.*: *sc*) (or sometimes *gauche* (*abbr.*: g) or *skew*), **anticlinal** (*abbr.*: *ac*), or **antiperiplanar** (*abbr.*: *ap*) (or sometimes *trans* (*abbr.*: t)) according as the torsion angle is, respectively, within ±30°, ±60°, ±120°, or ±180° of 0°, the torsion angle being defined according to specified criteria. (*Note*: Because the terms *cis* and *trans* have other meanings, their use in this context is not recommended.) —**conformational** *adj.*



conformational analysis the application of a set of specific rules to determine the conformation of a molecule in which the strain will be minimal, i.e. the most stable and preferred conformation of the molecule.

conformational change **1** any change in conformation. **2** any change in the three-dimensional structure of a macromolecule, membrane, or other entity.

conformational-coupling hypothesis a hypothesis (now superseded) that the energy yielded by the processes of electron transport, e.g. in mitochondria, is conserved in the form of a conformational change in an electron carrier protein or in the coupling factor (F_1 ATPase) molecule. The high-energy conformational state results from an energy-dependent shift in the number and location of weak bonds that maintain the three-dimensional conformation of the protein. The energy inherent in this 'energized' conformation is thought to be used to cause the formation of ATP from ADP and inorganic phosphate. This hypothesis was put forward after attempts to find a high-energy intermediate that coupled electron transport to oxidative phosphorylation, failed. It has been superseded by the **chemiosmotic coupling hypothesis**.

conformational formula a diagrammatic representation on a plane surface of the structural formula of a molecule that shows the relative dispositions in space of the constituent atoms or groups. Such representations are used especially to depict instances of conformational isomerism. For a monosaccharide or monosaccharide derivative, the conformational formula may be combined with a **Haworth representation**. *See also* **Newman projection**.

conformational isomer *or (sometimes)* **conformer** any of two or more isomers that differ only in their stereochemical **conformation**.

conformational map *an alternative name for* **Ramachandran plot**.

conformer **1** a molecule in a conformation into which its atoms return spontaneously after small displacements. **2** *an alternative term for* **conformational isomer**.

conformon a quantized energy package that, according to the **conformational-coupling hypothesis**, is associated with a localized conformational change in a protein in the mitochondrial membrane.

congener **1** any member of a (specified) group. **2** *(in taxonomy)* any member of a specified genus. **3** *(in chemistry)* **a** a chemical substance related to another, e.g. as a derivative or as an element of the same group of the periodic table. **b** a secondary product retained in an alcoholic beverage (or extract of a natural product) that contributes significantly to the final characteristics of the beverage (or the extract).

congenic **1** describing an inbred strain of animals in which a defined chromosomal segment has been transferred from a donor to a recipient strain. *Compare* **consomic**. **2** of, or pertaining to, a **congener**; **homogenic**.

congenital describing a character or trait (phenotype) that exists at or dates from birth. It neither includes all inherited conditions nor excludes characters resulting from environmental causes.

congenital adrenal hyperplasia a syndrome of abnormal adrenal steroid hormone biosynthesis,usually caused by deficiency of 21-hydroxylase (steroid 21-monooxygenase, EC 1.14.99.10). There is failure to synthesize cortisol, overproduction of ACTH (due to release from negative feedback by cortisol), hyperplasia of the adrenal cortex, and overproduction of 17-hydroxyprogesterone and androstene 3,17-dione by overstimulated alternative pathways. Deletion of the *CYP21* gene at 6p21.3, crossing over of this gene with the neighbouring pseudogene *CYP21P*, and various inactivating mutations in *CYP21* cause absence or marked deficiency of 21-hydroxylase activity. Deficiency (usually partial) of 11β-hydroxylase (steroid 11β-monooxygenase, EC 1.14.15.4) accounts for most other cases; in this condition, 11-deoxycorticosterone accumulates. Very rarely, deficiency of 17-hydroxylase (steroid 17α-monooxygenase, EC 1.14.99.9) or 18-hydroxylase (corticosterone 18-monooxygenase, EC 1.14.15.5) is the cause.

congenital lipid adrenal hyperplasia a rare condition in which there is a defect in production of all major steroid hormones in the adrenal cortex. The latter is grossly hyperplastic and its cells are engorged with cholesterol and cholesterol esters. A mutation in **StAR**, a protein essential for translocation of cholesterol into mitochondria in adrenal cortex and gonads, decreases or stops production of pregnenolone, which is the first step in corticosteroid synthesis.

conglutination the agglutination of bacterial or red blood cells, that have been sensitized with specific antibody, in the presence of (nonhemolytic) **complement** and **conglutinin**.

conglutinin a nonimmunoglobulin protein, present in the plasma of cattle and other bovids, that aggregates **complement**-coated immune complexes or cells.

conglycinin a 7S globulin storage protein of soybean (*Glycine max*) that is present as a glycosylated trimer in protein storage vacuoles in the embryo and aleurone layer. It is homologous with phaseolin and vicilin. All three globulins are synthesized as 45–50 kDa preproproteins.

Congo Red sodium diphenyldiazo-bis-α-naphthylaminesulfonate; CI 22120; Direct Red 28; an indicator dye that is blue-violet at pH 3.0 and red at pH 5.0. It is used for detecting and estimating free HCl in gastric contents, as an addition to culture media, and for staining **amyloid**.



Congo Red fibrin a preparation obtained by heating fibrin to 80°C in a slightly alkaline Congo Red solution and thoroughly washing. It was formerly used in the detection of proteolytic activity since the dye does not dissolve in aqueous solutions unless the fibrin is digested.

congruence *(in phylogeny)* agreement between characters or trees. –**congruent** *adj.*

coniferin 4-(3-hydroxy-1-propenyl)-2-methoxyphenyl β-D-glucopyranoside; the major **glycoside** present in conifers and some other plants.



coniferyl alcohol the aglycon of **coniferin**; it occurs as a building unit of plant **lignins**.

coniine 2-propylpiperidine; the toxic alkaloid of poison hemlock, *Conium maculatum*. The natural enantiomer has *S* configuration.



conjugase γ-Glu-X carboxypeptidase, EC 3.4.19.9 (formerly EC 3.4.22.12); γ-glutamyl hydrolase; an enzyme that hydrolyses γ-glutamyl bonds in *N*-pteroyl-γ-oligoglutamate, pteroyl-γ-diglutamate being a prominent product.

conjugate **1** to effect or undergo **conjugation**. **2** describing either of a pair of interconvertible substances, e.g. a **conjugate acid–base pair**. **3** the product formed as a result of conjugation.

conjugate acid–base pair the relationship between two chemical species, BH^+ and B, that are related by the reaction: $BH^+ = B + H^+$. Then BH^+ is the **conjugate acid** of the base B, B is the **conjugate base** of the acid BH^+, and BH^+ and B are a conjugate acid–base pair.

conjugate base *see* **conjugate acid–base pair**.

conjugated **1** describing a compound that is formed by the linking of two compounds. **2** displaying or having undergone **conjugation**.

conjugated double bond any of two or more double bonds in a molecule where each double bond is separated from the next one by one single bond. *Compare* **conjugation** (def. 2).

conjugated protein any protein that contains a non-protein component, often in stoichiometric proportion. The non-protein component may be a metal ion, a lipid, a carbohydrate, or a nucleic acid, and may be either loosely or tightly bound to the polypeptide chain(s).

conjugation **1** the act of joining together; the state of being joined together. **2** an alternating sequence of multiple and single chemical bonds containing at least two multiple bonds with delocalization of pi-electrons and resultant additional chemical stability. **3** the covalent or noncovalent joining together of one (larger) molecule, e.g. a protein or bile acid, with a second (smaller) molecule. **4** a process of sexual reproduction occurring in various types of unicellular organisms. In bacteria, e.g. *Escherichia coli*, it involves the transfer of DNA from a donor cell to a recipient cell via a sex **pilus**; in protozoa, e.g. *Paramecium aurelia*, a true exchange of DNA occurs between the participating cells, which belong to different mating types.

conjugation labelling a procedure for introducing a **label** into a large molecule of interest by covalently coupling it, in a specific chemical reaction, to a small molecule containing the label (*see* **conjugation** (def. 3)). It is particularly useful for labelling with radioiodine any protein or peptide that is sensitive to oxidative procedures or to noxious components of commercial radioiodine, that lacks tyrosine residues reactive to iodine, or that requires to be labelled at a residue other than tyrosine. *See also* **Bolton and Hunter reagent**.

conjugative plasmid any **plasmid** that can bring about the transfer of DNA by **conjugation**.

conjugon any genetic element that is required for bacterial **conjugation** (def. 4), e.g. **fertility factor**.

connective tissue any supporting tissue that lies between other tissues and consists of cells embedded in a relatively large amount of extracellular matrix.

connective tissue growth factor *abbr.*: CTGF; a growth factor of testis, spleen, kidney, lung, heart, and brain, that is similar to **CEF10**; one of a family of growth regulators that belong to a group of immediate-early genes expressed after induction by growth factors or certain oncogenes. The family includes **Cyr61**, βIG-M1 and βIG-M2.

connectivity *(in chemistry)* the information in any molecular formula or model regarding the order in which the constituent atoms of the molecule are linked, irrespective of the nature of the linkages.

connexin the main protein component of a **connexon**. Each connexin contains four putative membrane-spanning α-helices, and six connexins make up each connexon. A number of different subtypes of connexin exist within each species, contributing different functional behaviour to different connexons.

connexon the structural subunit of a **gap junction**, the structure that forms a bridge between adjacent cells in certain tissues of vertebrates. Seen by electron microscopy or low-angle X-ray diffraction, an individual gap junction consists of a number ($10–10^4$) of connexons, often in hexagonal array, embedded in and protruding from either side of each of the opposed cell membranes in register and linked to one another. Each connexon is a cylindrical structure, about 6–8.5 nm in diameter and 7.5 nm long, that consists of six rod-shaped, essentially rigid subunits (**connexins**). The diameter of the central opening can apparently be varied by radial displacement of the subunits at their cytoplasmic extremities. Each connexin spans one cell membrane, two with connecting ends being required to form a channel across both membranes. Such channels provide a regulable hydrophilic pathway permitting the passage of small molecules (up to about 800 Da) between adjacent cells; the specificity of each channel is determined by the type of connexin it contains.

conotoxin *abbr.*: ω-CT; any of several peptides of the family of ω-conotoxins isolated from the venoms of two marine snails, *Conus geographicus* and *C. magus.* All ω-conotoxins have a conserved pattern of cysteine residues linked by four disulfide bridges. They are neurotoxins that inhibit voltage-gated Ca^{2+} channels and neurotransmitter release. ω-Conotoxin GVIA has the structure:

[tricyclic (1→16, 8→19, 15→26)(H-Cys^1-Lys-Ser-Hyp-Gly-Ser-
Ser-Cys^8-Ser-Hyp-Thr-Ser-Tyr-Asn-Cys^{15}-Cys^{16}-Arg-Ser-Cys^{19}-
Asn-Hyp-Tyr-Thr-Lys-Arg-Cys^{26}-Tyr-NH_2)].

consanguinity the relationship between individuals who are descended from the same ancestors and consequently are more likely to have mutant alleles in common. **—consanguineous** or **consanguine** *adj.*; **consanguineously** *adv*.

consensus sequence an idealized sequence of nucleotides, or their constituent bases, or amino acids, base, or amino acid that represents the nucleotide most likely to occur at each position in the sequence. Consensus sequences are used to identify RNA splicing sites, other sites, plasmids, and families of proteins.

consensus tree (*in phylogenetics*) a tree that summarizes relationships from multiple phylogenies, wherein groups of taxa that appear in all individual trees are shown, typically with multifurcations indicating disagreements between trees. Trees are often combined into a consensus phylogeny when tree-building tools generate more than one topology. *Compare* **majority-rule consensus tree**.

conservation the retention of structure by a macromolecule, or by a specified segment of one, with variation of circumstance (environmental, genetic, etc.). When used of primary structure, it can be synonymous with **sequence homology**. The degree of retention of structure is usually specified. *See also* **conserved**.

conservation of energy (law of the) *see* **thermodynamics**.

conservative base change *or* **conservative base substitution** any mutational change, including substitution of a base, in a particular base triplet in a DNA molecule such that either the amino acid encoded by that base triplet is not altered, or there is no major change in the properties of the R group of the amino acids involved, e.g. Glu for Asp. *See* **genetic code**, **wobble hypothesis**.

conservative replacement *or* **conservative substitution** any replacement or substitution in a polypeptide chain of a particular amino-acid residue by another with similar properties: e.g., Arg for Lys, Phe for Tyr, Glu for Asp.

conserved describing a tendency to invariance in corresponding residues or sequences of residues of encoded macromolecules (e.g. proteins) obtained from specimens of genetically different sources. Macromolecules showing a high degree of invariance of their primary structure are said to be highly conserved; ones exhibiting considerable variation are described as poorly conserved. *See also* **conservation**, **homologous**.

consomic describing an inbred strain of animals in which an entire chromosome has been transferred from a donor to a recipient strain. *Compare* **congenic** (def. 1).

constant region the region of a chain of an **immunoglobulin** molecule that is characterized by invariability of the amino-acid sequence from molecule to molecule, apart from certain residues at allotypic marker sites. The constant region of the light chain (corresponding to the C-terminal part) is designated C_L, while the constant region of the heavy chain is designated C_H. Within a constant region, individual domains may be further designated C_H1, C_H2, etc. In a more precise designation of a heavy chain the 'H' subscript is replaced by the Greek letter corresponding to the type of heavy chain that defines the particular class of immunoglobulins. Hence, the constant region of an **immunoglobulin G**, in which the heavy chain is designated γ, can be designated $C_\gamma1$, $C_\gamma2$, etc.

constitutional base unit the smallest possible regularly repeated unit (i.e. identical group of monomers) of a regular **polymer**.

constitutional block a **block** of a polymer that contains only one species of **constitutional base unit**.

constitutional isomer *or (formerly)* **structural isomer** any of two or more **isomers** that differ in their molecular constitution, i.e. in the nature and sequence of bonding of their atoms rather than in the arrangement of their atoms in space. For example, ethanol, $CH_3–CH_2–OH$, and dimethyl ether, $CH_3–O–CH_3$, are constitutional isomers. *Compare* **stereoisomer**.

constitutive enzyme any enzyme that is formed at a constant rate and in constant amount in a given cell, regardless of the metabolic state of the cell or organism. *Compare* **induced enzyme**.

constitutive genes genes that are expressed following interaction between a promoter and RNA polymerase without additional regulation. *Also known as* **housekeeping genes**, they are expressed in virtually all cells since they are essential for the cell's activity.

constitutive morphogenetic protein 1 *see* **COP1**.

constitutive mutation any mutation that results in an increased constitutive synthesis (i.e. synthesis as if by a **constitutive gene**) by a prokaryote of several functionally related, inducible enzymes. In such mutations either an operator gene is modified so that the repressor cannot combine with it or the regulator gene is modified so that the repressor is not formed.

contact amino acid any of the amino-acid residues in the **active site** (def. 1) of an enzyme that are at some stage within one bond distance of some point on the substrate molecule in the enzyme–substrate complex. They may include both catalytic residues and specificity residues. *Compare* **auxiliary amino acid**.

contact hypersensitivity a form of immunological **hypersensitivity**, immediate or delayed, that is provoked in the skin or mucous surfaces by contact with specific agents acting as either antigens or haptens.

contact inhibition a phenomenon, seen in cultures of normal eukaryotic cells, in which cell division is inhibited by cell-to-cell contact. When one cell contacts another cell as a result of increased cell density, it first ceases to move, then metabolizes more slowly and ceases to divide. An outstanding feature of malignant cells is their loss of contact inhibition so that they multiply unchecked. *See also* **transformation** (def. 2).

contact residue *see* **contact amino acid**.

contact sensitivity the ability of an organism to respond to a biocide, e.g. an insecticide or a selective herbicide, applied to the integument.

containment the use of any structural or procedural safeguards to minimize the possible risks, to the experimenter or to the environment, in hazardous or potentially hazardous operations, especially genetic manipulations or the use of ionizing radiation.

contamination the presence of any contaminant; the act of introducing a contaminant; pollution; the presence of harmful or invasive microorganisms in a population of desirable ones. *Compare* **decontamination**.

context 1 any parts of a piece of writing or speech that precede or follow a specified word or passage and contribute to its full meaning. **2** *(in mycology)* the layers that develop between the hymenium and the true mycelium in certain fungi.

context effect any effect of nucleotide residues outside a codon in an mRNA molecule in influencing the efficiency of the reading of that codon by the appropriate tRNA molecule. *Compare* **context** (def. 1).

context mutation any mutation that brings about an alteration in the **context effect** of nucleotide residues outside a particular **codon** in an mRNA molecule.

contig one of a set of overlapping clones that represent a continuous region of DNA. Each contig is a genomic clone, usually in a **cosmid** or a **YAC**. They are used in **contig mapping**.

contig mapping a technique used in projects such as the Human Genome Project to enable the physical map of (part of) a chromosome to be determined. The method relies on the use of overlapping clones, referred to as **contigs**.

contiguous gene syndrome any of the complex disease phenotypes associated with a chromosomal microdeletion affecting multiple, unrelated genetic loci physically contiguous on a chromosome.

continuous culture any cell culture in which the cells are in the growth phase over a prolonged period of time. *See also* **chemostat**.

continuous distribution any nonquantized distribution; e.g. in a large population one measurement, x, may be considered to vary continuously, and the probability, y, of the occurrence of a particular value of x is given by $y = f(x)$.

continuous epitope an immunological determinant (i.e. **epitope**) on an antigen that is formed from a single linear stretch of amino acids. It is much less common than a **discontinuous epitope**.

continuous-flow centrifugation any preparative centrifugation technique, used for collecting materials from relatively large volumes of liquid, in which a liquid is continuously fed into a rotor, the sediment is collected, and the supernatant is withdrawn continuously as the rotor rotates. *See* **centrifugal elutriation**, **Sharples supercentrifuge**, **zonal centrifugation**.

continuous-flow electrophoresis a method of electrophoresis in which the protein (or other) solution is applied continuously to an inert support such as paper (then usually called **curtain electrophoresis**) or glass beads or is allowed to flow between two closely spaced parallel plates. The solution flows down the support by gravity and an electric potential applied at right angles causes migration of components away from the main stream. Fractions are collected at different positions across the bottom of the support.

continuous-flow technique a technique for following rapid chemical reactions in which two solutions, containing the reactants, are rapidly mixed and the mixture pumped at a predetermined speed through a tube of known dimensions that contains an observation chamber. By changing the rate of flow, the time between mixing and observation can be varied. Thus, given a method of analysis for reactants or products in the observation chamber, the extent of reaction as a function of time can be determined.

continuous process a method of cultivation in which nutrients are supplied and components of the culture medium are removed continuously at volumetrically equal rates, maintaining the cells in a condition of stable multiplication and constant growth rate.

continuous variation *or* **Job's method** a method for investigating metal–ligand (or other) equilibria in solution in which the mole ratio of, e.g., metal ion to ligand species is varied while the sum of their concentrations is kept constant and some property that varies in a fashion proportional to the concentration of one of the molecular entities present, e.g. absorbance or conductivity, is measured. The curve of the magnitude of the property observed versus the concentration ratio gives information about the stoichiometry of the metal–ligand (or other) complex formed and allows the stability (association) constant to be calculated.

contour-clamped homogeneous electric field *see* **CHEF**.

contractile vacuole any of the small spherical vesicles, found in the cytoplasm of freshwater protozoans, that function to expel surplus water from the organism.

contrapsin a glycoprotein plasma serine protease inhibitor, similar to the **serpin**-type inhibitors. It specifically inactivates serine proteases of the trypsin class, but not of the chymotrypsin class. It shares 64% similarity with human α_1-antichymotrypsin.

contrast agent a substance used to improve the resolution in 'highlighting' an organ or tissue during X-ray tomography or magnetic resonance imaging. Analogous to the stains used in microscopy, it permeates the organ of interest or the surrounding medium. In X-ray examination, heavy nuclei such as iodine are used as contrast agents. For magnetic resonance imaging contrast agents are paramagnetic compounds such as lanthanide complexes.

contributing amino acid (in an enzyme) any amino-acid residue whose only function appears to be that of a foundation for the **contact amino acid** and **auxiliary amino acid** residues in the **active site**. They are required in the natural enzyme to maintain the framework to which the contact and auxiliary amino acids are attached.

contributing structure *or (formerly)* **canonical form** any one of two or more formal valence bond representations of a mesomeric molecular structure. *Compare* **mesomerism**.

control 1 any object or system in an experiment that is a standard of comparison. A control is prepared or carried out exactly as the other parts of an experiment but differs in respect of a single variable, allowing the significance of the latter to be assessed. *Compare* **experimental** (def. 3). **2** the regulation of a biochemical process such as a metabolic pathway or the expression of a gene. For metabolism, a distinction is sometimes made between control and **regulation**. Control is described as the power to change the state of metabolism in response to an external signal. This is a measure of the strength of response to external factors.

controllability coefficient *former name for* **elasticity coefficient**.

controlled pore glass a type of glass in the form of rigid particles honeycombed with a great number of pores of selected, precisely defined size. It is useful as a supporting matrix in a large variety of chromatographic techniques, including affinity, gel-permeation, and ion-exchange methods.

control point the point – corresponding to a particular enzyme – in a metabolic pathway or other biochemical sequence where control is exercised.

control region *or* **control sequence** the part of a DNA molecule containing the **promoter** and the **operator** region of an **operon**.

control strength *former name for* **flux control coefficient**.

convergence *see* **convergent evolution**.

convergent evolution *or* **convergence** evolution such as to produce an increasing similarity in some characteristic(s) between initially different groups of, e.g., organisms or **gene products**. *Compare* **divergent evolution**.

convertin *an alternative name for* factor VIIa (*see* **blood coagulation**).

convertin enzyme (factor) *see* **serum converting enzyme**.

convolution 1 a twisting together, a coil. **2** a folding, such as those that produce the irregular ridges on the surface of the cerebrum of the brain.

Conway microdiffusion method a microchemical analytical method applicable to substances from which a gas, e.g. ammonia or carbon dioxide, can be liberated quantitatively by a specific reagent or enzyme; the method can also be used to assay an enzyme. The technique employs a special microdiffusion dish, variously termed a **Conway cell**, **Conway dish**, **Conway unit**, or **Conway vessel**. This consists of a shallow circular glass vessel, 40–70 mm in diameter, containing a central well and with a closely fitting lid sealed with grease; the lid closes the outer annular space but does not touch the wall of the central well. The sample is placed in the outer annulus, and a gas-absorbing reagent is placed in the centre well. The specific reagent is added to the sample, the lid is closed, and diffusion of the evolved gas allowed to proceed. Subsequently the remaining gas-absorbing reagent is titrated. [After Edward Joseph Conway (1894–1968), Irish biochemist.]

Coomassie blue *or* **Brilliant blue** one of a series of naphthalene dyes, originally developed for wool, and commonly used for staining proteins on electrophoresis gels. It also forms the basis of the **Bradford assay** for proteins. [After the ancient Ashanti capital, Kumasi, now in Ghana.]

Coombs' test *an alternative name for* **antiglobulin test**. [After Robert Royston Amos Coombs (1921–), British immunologist.]

cooperative acting together or with others. *See also* **cooperativity**.

cooperative affinity the state of increased potency, receptor affinity, and resistance to destruction that is exhibited by agonist molecules covalently attached to a macromolecule in any situation where ligand and acceptor possess more than one mutual recognition or binding site, deployed in such a manner that simultaneous interaction is stereochemically feasible.

cooperative binding *see* **cooperative ligand binding**.

cooperative feedback inhibition the **feedback inhibition** of an enzyme by two or more end products of a reaction sequence such that the degree of inhibition caused by the mixture is greater than the sum of the effects of the individual end products.

cooperative hydrogen bonding the interaction between adjacent hydrogen bonds in a molecule such that the energy required to form them is less than the sum of the energies required to form the individual bonds, and the energy required to break these bonds is greater than the sum of the energies required to break the individual bonds. Such an interaction increases the stability of the molecular conformation in which it occurs.

cooperative ligand binding the binding of ligands to interacting sites on a macromolecule such that the binding of one ligand molecule to one site either increases (**positive cooperativity**) or decreases (**negative cooperativity**) the affinity of the other site(s) for ligand(s). Such effects may be either **homotropic**, i.e. one ligand species affects the binding of the same ligand species, or **heterotropic** (def. 1), i.e. one ligand species affects the binding of a different ligand species.

cooperativity *(in biochemistry)* any **cooperative** phenomenon, especially **cooperative ligand binding** or the situation in an enzyme that has more than one binding site for its substrate or allosteric effector where the binding of one molecule to the enzyme alters the affinity with which the others are bound.

cooperativity index *see* **saturation ratio**.

coordinate 1 to integrate or classify diverse elements or things. **2** *(in chemistry)* to be or become linked by **coordination** (def. 2). **3** *(in mathematics)* any of a set of values that defines the position of a point in space with reference to a system of axes.

coordinate bond *or* **coordinate covalence** *or* **coordinate link** *an alternative term for* **dipolar bond**.

coordinated enzymes enzymes whose rates of synthesis vary together; they are controlled by cistrons of the same **operon**.

coordinated enzyme synthesis the synthesis of enzymes that are controlled by the genes of one operon and are thus induced or repressed together.

coordinate induction/repression the simultaneous induction/repression of a number of enzymes that catalyse a sequence of either consecutive or related reactions and are controlled by scattered genes.

coordination 1 the balanced and effective interaction of processes. **2** the formation or existence of a covalent bond whose pair of electrons is regarded as originating from only one of the two parts of the molecular entity linked by it; linking by means of such a bond or bonds. *Compare* **colligation**. *See also* **dipolar bond**, **pi adduct.**

coordination number *or* **ligancy** the number of other atoms directly linked to a specified atom in a chemical species.

cooxidation *an alternative term for* **co-metabolism**.

COP *abbr. for* **1** coat protein; a protein subunit of a **coatomer**. **2** constitutive photomorphogenetic protein; a plant protein that represses photomorphogenesis.

COP1 *abbr. for* constitutive morphogenetic protein 1; a protein (675 amino acids) of *Arabidopsis* that contains a RING finger, a coiled-coil domain, and several WD40 repeats. It shuttles between nucleus and cytoplasm in a light-dependent manner. Accumulation in the nucleus requires the integrity of **COP9 signalosome**. In the nucleus it binds a number of proteins and is found in nuclear foci or bodies, where it might be responsible for recruiting specific transcription factors for ubiquitination and degradation. Its cell distribution, dynamics, and structure resemble those of **PML**. A mouse homologue of COP1 is known.

copeptin *see* **vasopressin–neurophysin 2–copeptin precursor**.

copigmentation the chemical association between a pigment molecule and another colourless molecule that results in altered absorption characteristics of the pigment and consequently a change in its shade or colour. Some flower petal colours are changed by hydrogen bonding between an anthocyanin pigment and a colourless flavonoid. For example, the anthocyanin in both purple and crimson roses is cyanidin 3,5-diglucoside, but in crimson flowers it is copigmented with large amounts of gallotannin. This results in a spectral shift of the absorption maximum by 5 nm to longer wavelengths.

copolymer the product of the polymerization of a mixture of more than one species of **monomer**.

copolymerization *or* **copolymerisation** the polymerization of a mixture of two or more species of **monomer**.

copper-chelate chromatography a type of **metal-chelate affinity chromatography** employing Cu^{2+} ions.

copro+ *or (before a vowel)* **copr+** *comb. form* indicating feces.

coprophagy the act of feeding on feces.

coproporphyrinogen III an intermediate in the biosynthesis of **metalloporphyrins** (hemes and chlorophylls).

coprostane 5β-cholestane; *see* **cholestane**.

coprostanol *or* **coprosterol** 5β-cholestan-3β-ol; a major **sterol** in feces. It is formed from cholesterol by bacterial action.



COP9 signalosome (*abbr.* CSN) *or* **signalosome** a protein complex first discovered in photomorphogenetic mutants of *Arabidopsis*, but widely distributed in plants and animals. Its eight subunits resemble in sequence those of the lid complex (19S) of the 26S **proteasome**. It may function in collaboration with **COP1**.

copy-choice hypothesis a hypothesis to explain interchromosomal genetic recombination, according to which copying to form a new DNA strand alternates from one parent strand to the other. If the parent strands contain different alleles, a recombinant chromosome may be produced possessing some alleles from one parental strand and some from the other.

copy error a mutation arising from an error in DNA replication.

copy number the number of copies of any gene or plasmid in a given cell. *See* **plasmid**.

CoQ *symbol for* coenzyme Q (obsolete; *see* **ubiquinone**).

CoQH$_2$ *symbol for* reduced coenzyme Q (obsolete; the reduced form of **ubiquinone**).

cord blood blood taken from the umbilical cord.

cord factor 6,6′-dimycolyl trehalose; a highly toxic glycolipid extractable with nonpolar solvents from the cell walls of certain, especially virulent, strains of *Mycobacterium* that characteristically grow in long cords in liquid media.

cordycepin 3′-deoxyadenosine; a substance found in culture fluids of the microfungus *Cordyceps militaris*. It inhibits poly(A) synthesis and interferes with the processing of much eukaryotic mRNA and hence with protein synthesis. The α-^{32}P-labelled 5′-triphosphate is used to label the 3′ ends of DNA fragments in DNA sequence analysis.

cordycepose 3-deoxy-D-ribose; 3-deoxy-D-*erythro*-pentose; the carbohydrate component of **cordycepin**.

core the central, innermost, or least easily destroyed or removed part of a structure; e.g. the core of a partially digested biopolymer, the protoplast core of an endospore, or the core of a virus.

core debranching enzyme *see* **β-1,3-galactosyl-*O*-glycosyl-glycoprotein β-1,6-*N*-acetylglucosaminyltransferase.**

core enzyme the part of bacterial (*Escherichia coli*) **RNA polymerase** lacking the σ subunit. It will catalyse chain elongation but not initiation.

core glycosylation the first of two stages in the biosynthesis of the carbohydrate moiety of some glycoproteins; it takes place in the endoplasmic reticulum.

core particle **1** the RNA-rich particle obtained from a **ribosome** by the gentle removal of some of the ribosomal proteins. The particle retains peptidyltransferase activity. **2** any of the eukaryotic **chromatin** particles containing 140 base pairs of DNA and an octamer of the four conservative **histones** (two each of histones H2A, H2B, H3, and H4) but not histone H1. These particles are obtained by the treatment of chromatin with DNase. In the intact chromatin they are linked by stretches of variable length of so-called linker DNA.

core polymerase *see* **RNA polymerase**.

corepressor any metabolite that by its specific combination with a **repressor** causes the activation of the latter.

core promoter *or* **basal promoter** a stretch of DNA upstream from the transcription start site of a eukaryote gene at which a complex of general transcription factors such as TFIID, TFIIB, and others is formed with RNA polymerase II prior to initiation of transcription.

core protein any of the many types of protein in glycosaminoglycans to which oligosaccharide side-chains are covalently attached, and which are themselves covalently attached to a long oligosaccharide backbone. Each glycosaminoglycan will typically contain many core protein molecules. An example is **heparan sulfate proteoglycan core protein**.

CoREST the corepressor of **REST**.

Cori cycle *or* **lactic acid cycle** an energy-requiring metabolic pathway in animals in which carbon atoms of glucose pass along the circular route: muscle glycogen → blood lactate → blood glucose → muscle glycogen. [After Carl Ferdinand Cori (1896–1984) and Gerty Theresa Cori (née Radnitz, 1896–1957), Czech-born US biochemists, who together formulated it in 1929.]

Cori ester *an alternative name for* **α-D-glucopyranose 1-phosphate**. [After C. F. and G. T. Cori who reported its isolation in 1936.]

corin a single-pass transmembrane protein that has a ≈970-residue extracellular region containing various domains, including one for serine protease. The human protein (1042 residues) is highly homologous to that of mouse and is present in heart muscle. *See* **TTSP**.

Cori's disease *an alternative name for* type III **glycogen disease**. [After G. T. Cori who first described it in 1953.]

CORN a mnemonic for remembering the absolute configuration of L amino acids. When viewed along the axis of the H–Cα, the carbonyl (CO), R, and amino (N) groups spell the word CORN in a clockwise direction..

cornea the transparent curved part of the front of the eyeball that refracts incident light onto the lens. It is composed of many layers, the thickest being the stroma, which is composed of uniformly fine collagen fibrils. These are kept in an orderly distribution by the expansive force between them of the contained glycosaminoglycan (mainly keratan sulfate I). The cornea has a high oxygen consumption and approximately 50% of the glucose utilized is oxidized via the phosphogluconate pathway. **—corneal** *adj.*

Cornelia de Lange syndrome a sporadic autosomal dominant disorder of unknown biochemical and genetic basis that is characterized by distinctive facial features, pre- and post-natal growth retardation, mental retardation, and upper limb abnormalities in many cases. [After Cornelia de Lange (1871–1950), Dutch paediatrician.]

cornifin *or* **small proline-rich protein I** a cross-linked envelope protein of keratinocytes that first appears in the cell cytosol, but ultimately becomes cross-linked to membrane proteins by transglutaminase. Its presence correlates with squamous differentiation. It is down-regulated by retinoids. Structurally, it is rich in proline, glutamine, and cysteine, and contains repeats of a consensus octapeptide, EPCQPKVP.

corn-steep liquor *or* **corn-steep water** a concentrated fluid obtained by steeping corn (maize) grains in water (containing 0.2% SO_2) for 36–40 hours at 46–50°C. It is used in the manufacture of **penicillin** to increase antibiotic yield.

corn sugar *a common name for* **D-glucose**.

corn syrup *or (sometimes)* **liquid glucose** a partial hydrolysate of corn (maize) starch containing **glucose** and glucose oligosaccharides.

coronand *an alternative name for* **crown compound**.

coronate *see* **crown compound**.

coronavirus any of a group of RNA animal viruses consisting of enveloped particles 80–120 nm long, with helical nucleocapsids. They contain the largest known viral RNA genomes (27–31 kb) and cause devastating epizootics (of respiratory or enteric disease) in livestock and poultry. Human coronaviruses cause upper respiratory tract infections and severe acute respiratory syndrome (SARS). *See* **main protease**.

corphin a tetrapyrrole ligand that combines the structural elements of porphyrins and corrins. **Factor F_{430}**, the prosthetic group for coenzyme-B sulfoethylthiotransferase, comprises a nickel ion coordinated by tetrahydrocorphin.

corpuscle any living metazoan cell, especially the red corpuscles (erythrocytes) and the white corpuscles (leukocytes) of the blood.

corpuscular radiation *a former term for* **particulate radiation**.

corpus luteum (*pl.* **corpora lutea**) a yellow, progesterone-secreting, glandular body formed in the mammalian ovary from a **Graafian follicle** after extrusion of an ovum.

correlated mutation a change in a (DNA, RNA or protein) sequence that is induced by a change in a different part of the sequence with which it interacts.

correlation *(in statistics)* the interdependence of two or more simultaneously variable quantities; or the nature or degree of this interdependence. If two variates both increase or both decrease together there is said to be **positive (direct) correlation** between them, whereas if they change in opposite directions to each other there is said to be **negative (inverse) correlation**.

correlation coefficient *(in statistics) symbol*: r; a measure of the correlation between two variates, x and y. If one variate has the values $x_1, x_2, \dots x_n$ and the corresponding values of the other variate are $y_1, y_2, \dots y_n$, with respective mean values of $\bar{x}$ and $\bar{y}$ then the correlation coefficient, r, is given by:

$$r = \sum_{i=1}^{n}(x_i - \bar{x})(y_i - \bar{y}) \Big/ \Big[\sum_{i=1}^{n}(x_i - \bar{x})^2 \sum_{i=1}^{n}(y_i - \bar{y})^2\Big]^{1/2}$$

If $r = 0$, x and y are completely independent. If $r = 1$ there is complete correlation and one variate may be calculated from the other variate.

correlation time *symbol*: τ_C ; the average time between molecular collisions for molecules in some state of motion. The reciprocal of the correlation time is given by the equation:

$$1/\tau_C = 1/\tau_R + 1/\tau_M + 1/\tau_S$$

where $1/\tau_R$ is the rate at which the molecule is tumbling (τ_R being the **rotational correlation time**), $1/\tau_M$ is the rate at which two dipoles approach each other (τ_M being the **residence time**), and $1/\tau_S$ is the electron spin lattice relaxation rate (τ_S being the time for the upper electron spin state to dissipate its excess energy).

correndonuclease any correctional **endonuclease** that specifically acts on damaged DNA initiating a correctional pathway *in vivo*. The name is misleading because nuclease activity itself does not lead to repair.

corrin $C_{19}H_{22}N_4$, the fundamental heterocyclic skeleton of the **corrinoids**. It consists of four reduced pyrrole rings joined into a macrocyclic ring by links between their α positions; three of these links are formed by a one-carbon unit (methylidyne group) and the other by a direct Cα–Cα bond. Corrin is so named because it is the core of the **vitamin B_{12}** molecule.

corrinoid any of a group of compounds containing the **corrin** skeleton. This group includes various B_{12} vitamins, factors, and derivatives. Some are more unsaturated than corrin itself; many have a regular pattern of substituents on the methylene carbon atoms of the reduced pyrrole rings and a cobalt atom in the centre of the macrocyclic ring.

corrole *a trivial name for* octadehydrocorrin; *see* **corrin**.

cortactin a protein that stabilizes Arp2/3 complex-mediated branches in actin filament networks. Its N-terminal region binds Arp2/3, the central region contains several repeats of a 37-residue sequence, and the C-terminal region contains an SH3 domain and three tyrosyl residues that are targets for Src-related kinases. *See* **Arp.**

cortex (*pl.* **cortices**) **1** the outer layer of an animal organ, situated immediately beneath the capsule or outer membrane. It is usually morphologically distinct from the rest of the organ; e.g. adrenal cortex, cerebral cortex, renal cortex. **2** the unspecialized tissue in plant stems and roots lying between the vascular bundles and the epidermis; the outer layer of a stem. —**cortical** *adj.*

cortexillin an actin-binding protein discovered in the slime mould *Dictyostelium discoideum*. It has a C-terminal basic nonapeptide that binds **phosphatidylinositol 4,5-bisphosphate**.

corticoid *an alternative name for* **corticosteroid**.

corticoliberin *an alternative name for* corticotropin-releasing hormone (*see* **CRH**).

corticosteroid *or* **corticoid** any of a large group of C_{21} steroids synthesized from cholesterol in the **adrenal cortex**, especially the adrenocortical hormones. Usage is often extended to include synthetic analogues with hormonal activity. Corticosteroid hormones are divided into **glucocorticoids**, i.e. cortisol and related compounds, and **mineralocorticoids**, i.e. aldosterone and related compounds.

corticosteroid-binding globulin *or* **corticosteroid-binding protein** *an alternative name for* **transcortin**.

corticosterone 11*β*,21-dihydroxypregn-4-ene-3,20-dione; Kendall's compound B; Reichstein's substance H; a **glucocorticoid**, but on the biosynthetic route to aldosterone. Quantitatively it is the second most important corticosteroid of the normal human adrenal cortex. **Cortisol**, synthesized in the adrenal zona fasciculata, is the predominant corticosteroid in humans; corticosterone, synthesized in the adrenal zona fasciculata and glomerulosa, much less so, but it is the main corticosteroid in some rodents.



corticotrope a type of cell in the anterior pituitary that synthesizes **proopiomelanocortin**, a **polyprotein** from which **corticotropin** and a number of other peptide hormones are formed.

corticotrophin *(formerly) a variant spelling of* **corticotropin**.

corticotropin *or* **adrenocorticotropin** *or* **adrenocorticotropic hormone** (*abbr.*: ACTH) a 39-residue polypeptide hormone, secreted by the adenohypophysis of the pituitary, that stimulates growth of the adrenal cortex and the synthesis and secretion of various corticosteroids. It has the sequence (human):

[SYSMEHFRWGKPV]GKKRRPV-
KVYPNGAEDESAEAFPLEF.

The first 13 residues (in brackets) comprise, after proteolysis, α-**melanocyte-stimulating hormone**. Under normal conditions its own secretion is under feedback control from the plasma cortisol level, both directly and through hypothalamic regulatory factors. Biosynthesis occurs via the multihormone precursor peptide **proopiomelanocortin**. Hormonal activity is confined to the species-invariant N-terminal 24 amino acids (*see* **tetracosactide**). Corticotropin secretion is regulated by corticotropin-releasing hormone (**CRH**), is episodic (in bursts at intervals of a few hours), exhibits diurnal rhythm, and is increased by stress such as trauma, surgery, and hypoglycemia. The effects of fever may be mediated by cytokines 1, 2, and 6, which act indirectly by causing the release of CRH. *See also* **corticotropin-like intermediate lobe peptide**, **corticotropin receptor**, **melanotropin**.

corticotropin-induced secreted protein *abbr.*: CISP; *a former name for* thrombospondin-2 (*see* **thrombospondin**).

corticotropin-like intermediate lobe peptide *abbr.*: CLIP; a 22-residue peptide identical in sequence to the C-terminal moiety (residues 18–39) of a molecule of **corticotropin** from the same species. It is obtained from extracts of the pars intermedia of the pituitary of certain animals (rat, pig, dogfish), and has been found also in a carcinoid tumour from a human patient who was secreting ectopic corticotropin; it has not been found in extracts of human pituitary. It is derived from **proopiomelanocortin**. CLIP has B-cell tropin activity and acts to stimulate insulin release from B cells. *See also* **beta-cell tropin**.

corticotropin–lipotropin precursor *see* **proopiomelanocortin**.

corticotropin receptor one of a number of membrane proteins that bind corticotropin and couple to heterotrimeric G-protein-activated **adenylate cyclase**; they are seven-transmembrane-domain proteins and are distributed on cells of the adrenal cortex, on cells of the immune system, and in the brain. EC_{50} values for binding are near 10^{-8} M for corticotropin. *See also* **melanocortin receptor**.

corticotropin-releasing factor *an alternative name for* corticotropin-releasing hormone (*see* **CRH**).

corticotropin-releasing-factor binding protein a protein that binds and inactivates corticotropin-releasing hormone (**CRH**), to prevent inappropriate pituitary-adrenal stimulation in pregnancy.

corticotropin-releasing hormone *see* **CRH**.

cortisol *or (recommended name)* **hydrocortisone** 17-hydroxycorticosterone; 11*β*,17,21-trihydroxy-4-pregnene-3,20-dione; Kendall's compound F; Reichstein's substance M; the most powerful naturally occurring **glucocorticoid** hormone and the most abundant product of the adrenal cortex in humans. It is produced by the cells of the zona reticularis; its best known action is anti-inflammatory. The biosynthesis of cortisol is under the control of **corticotropin**.



cortisol-binding globulin *or* **cortisol-binding protein** *abbr.*: CBG; *an alternative name for* **transcortin**.

cortisone 11-dehydrocortisol; Kendall's compound E; Reichstein's substance F; a prodrug that is biologically inactive but is converted in the liver and, to a lesser extent, in other tissues, to cortisol, a substance with **glucocorticoid** activity. Cortisone was the first glucocorticoid to be isolated and made available for therapeutic use. It is not a primary secretory product of the adrenal cortex, being formed during tissue metabolism from cortisol by 11*β*-hydroxysteroid dehydrogenase. In fetal plasma, however, cortisone levels are about three times higher than those of cortisol.



cortoic acid any member of a group of acidic metabolites of 17-hydroxycorticosteroids in which the primary alcohol group at C-21 has been oxidized to a carboxylic-acid group. They are the principal acidic metabolites of **cortisol** in humans.

corynecin any of a number of antibiotic compounds produced by the cultivation of *Corynebacterium* KY 4339 in a medium containing C_{12} to C_{14} alkanes as the sole carbon source. Their antibacterial properties are similar to those of **chloramphenicol** but they are less potent.

coryneform 1 club-shaped. **2** describing any Gram-positive, asporogenous, club- or rod-shaped bacterium belonging to the genera *Corynebacterium* or *Brevibacterium*, possibly related to *Streptomyces*. Such bacteria are of biotechnological importance (amino-acid fermentations) and are amenable to genetic manipulation. **3** any coryneform microorganism.

cos *abbr for* **cosine**.

COS cell any member of a cell line, derived from monkey cells, that contains an integrated segment of **SV40** DNA coding for T antigen. Hence these cells will support replication of vector molecules containing the SV40 origin of replication, but no other DNA sequences from that virus.

cosec *abbr. for* cosecant.

cosecant *abbr*.: cosec *or* csc; the reciprocal of the **sine** of an angle.

cosine *abbr*.: cos; a trigonometric function defined, for a given angle of a right-angled triangle, as the ratio of the length of the side adjacent to the angle and the length of the hypotenuse. The cosine of an obtuse angle is numerically equivalent to that of its supplement but of opposite sign.

cosmid a hybrid **cloning vector** used for cloning DNA. Cosmids are derived from plasmids but also contain ***cos* sites** from phage lambda.

***cos* site** the cohesive ends (sticky ends) of certain **phage** DNA molecules. The *cos* site usually referred to is from phage lambda.

costamere a vinculin-containing myofibril attachment site. Costameres form one of the major linkage sites of the skeletal muscle cell, encircling the cell and connecting the Z-discs to the sarcolemma.

co-stimulator *an alternative name for* **interleukin 2**.

cost-selectivity equation a relation between the accuracy gained by editing and the cost in terms of the wasteful hydrolysis of correct products in any enzyme system synthesizing informational macromolecules. It is useful in the rationalization of some observations and proposed editing mechanisms.

cosubstrate an imprecise term used for an organic cofactor that is necessary for the activity of some enzymes. Although not the substrate of principal interest, the cosubstrate acts as an acceptor or donor of atoms or of functional groups and participates stoichiometrically in the reaction. *Compare* **coenzyme**.

cosuppression *an alternative term for* **RNA silencing**.

COSY *abbr. for* correlated spectroscopy; a technique employed in the first two-dimensional **NMR** experiment, designed to elucidate which resonances of the NMR spectrum are connected by spin–spin J-coupling. J-couplings arise out of the perturbation of the nuclear energy levels of one nuclear spin by another nuclear spin that is propagated through the intervening electronic orbitals. In a one-dimensional NMR spectrum these J-couplings are manifested as a splitting in the Lorentzian lineshape. In 2D-COSY spectra the couplings are indicated by off-diagonal cross-peaks connecting the frequencies of the J-coupled spectra. Ordinarily the J-couplings are only large enough for pairs of ^{1}H nuclei separated by a maximum of two or three bonds to exhibit COSY cross-peaks.

Cot *see* ***C_0t***.

cotransduction the **transduction** of two or more identifiable genes in a single event, probably because the transduced element contains more than one genetic locus.

cotransfection a technique in which two different plasmids are simultaneously introduced into mammalian, or other cells, by one of several methods of transfection. Relatively few cells take up DNA, but in those that do, both plasmids are taken up efficiently. One plasmid might carry a gene whose expression is of interest and the other a reporter gene used to monitor transfection efficiency.

cotranslation *(in recombinant DNA technology)* the synthesis of a hybrid molecule consisting of the desired protein product covalently linked to a normal protein secreted by the organism being used, through translation of a hybrid mRNA molecule generated on the recombinant DNA. —**cotranslate** *vb.*

cotranslational transport the transport of nascent protein chains through the membrane of the cisterna of the endoplasmic reticulum while translation is still proceeding at the ribosome. It is a common phenomenon in higher eukaryotes.

cotransmitter a substance, usually a peptide, that is released from neurons and modifies the actions of the substance regarded as the primary transmitter. For example, vasoactive intestinal peptide is a cotransmitter with acetylcholine, and neuropeptide Y performs a similar role with norepinephrine. Cotransmitters may also have direct effects on target cells.

cotransport 1 increased transport of a substance in excess to its concentration dependence, as found in positively cooperative systems. **2** *sometimes used as equivalent to* **symport**

co-trimoxazole an antibacterial drug that comprises a mixture of **sulfamethoxazole** and **trimethoprim** in a ratio of about 5:1. The combination may have synergistic effects.

Cotton effect an anomalous change in optical rotation with wavelength in the region of an absorption band. As the absorption band is approached there is a change in the rotation to a maximum, which may be either positive or negative, followed by a decrease to a minimum passing through zero at the wavelength of maximum absorption. Similarly there is a change in circular dichroism, either positive or negative, coinciding with the absorption band. The magnitudes and directions of these effects have been used to study macromolecular conformations. [After Aimé Cotton (1859–1951), French physicist.]

cotyledon the leaf-forming part of the embryo of seeds. —**cotyledonous** *adj.*

Couette viscometer an instrument for measuring viscosity, consisting of two concentric cylinders separated by a narrow annulus, which is filled with the sample. One cylinder is fixed and the other is rotated. From the angular velocity at a given torque and the dimensions of the cylinders, the viscosity of the sample can be calculated. The Couette viscometer is designed for use at relatively low shear gradients.

coulomb *symbol*: C; the SI derived unit of electric charge; the quantity of electricity transported in one second by a current of one ampere. Hence, 1 C = 1 A s. [After Charles Augustin de Coulomb (1736–1806), French physicist.]

coulomb force *or* **coulombic force** the electrostatic attraction or repulsion between two charged particles. *See* **Coulomb's law**.

Coulomb's law (of electrostatics) the law stating that the force, F, of attraction or repulsion between two point charges, Q_1 and Q_2, is proportional to the product of the charges and inversely proportional to the square of the distance, d, between them multiplied by the permittivity, ε, of the medium between them. Hence, $F = (Q_1Q_2)/\varepsilon d^2$. A similar law exists for magnetism.

coulometer *or* **coulombmeter** *or* **voltameter** an electrolytic cell for measuring a quantity of electricity passing through a circuit containing the cell by determining the amount of a metal (usually copper or silver) deposited on the cathode from a solution of a salt of the metal.

coulometry *or* **coulombmetry** *or* **voltametry** a method of chemical analysis based on the measurement of a quantity of electricity, in coulombs, in an electrode reaction. —**coulometric** *or* **coulombmetric** *adj.*; **coulometrically** *or* **coulombmetrically** *adv.*

Coulter counter a device for counting particles in a suspension, e.g. blood cells, microorganisms, or spores. Its functioning depends on changes in electric conductivity as the particles pass through a small aperture.

4-coumaric acid *trans*-4-hydroxycinnamic acid, an intermediate in the biosynthesis of flavonoids, and in the synthesis of lignin. 4-



coumarate is a chromophore of photoactive yellow protein from *Halorhodospira halophila*.

coumarin 1 1,2-benzopyrone; 2*H*-chromen-2-one; a fluorescent indicator. **2** any of a number of coumarin derivatives that are widespread in seed coats, leaves, and stems, and occur at high concentration in fruits and flowers. They have antimicrobial, antifeedant, UV-screening, and germination inhibitor properties. Coumarins from clover produce massive internal bleeding in mammals, which led to the synthesis of the rodenticide and *in vivo* anticoagulant warfarin. Some (e.g. 8-methylpsoralen) can cause photodermatitis and are used in treatment of skin conditions such as psoriasis and eczema. The coumarins are important in the perfume industry since they smell of new-mown hay and grass, though some are no longer used (acernocoumarol and phenindiene) because of adverse allergenic effects. Some are useful in forming fluorescent analytes. Others are antibiotics, e.g. **novobiocin**, or mycotoxins (*see* **aflatoxin**).

coumarin anticoagulants *see* **dicoumarol**.

counter any device for enumerating, especially one for detecting and determining particles and photons emitted from the disintegration of a radionuclide. *See*, e.g., **Cherenkov counter**, **Geiger counter**, **scintillation counter**.

countercurrent chromatography a form of **partition chromatography** that eliminates the need for a solid support, in which one of the components of a two-phase solvent system is allowed to flow through the second component in a coiled tube. The technique is claimed to have the advantages of both **countercurrent distribution** and **liquid–liquid chromatography** with the disadvantages of neither, and to be applicable to a broad spectrum of samples ranging from micromolecules to macromolecules, particles, and cells.

countercurrent distribution *or* **countercurrent separation** a method for the separation and purification of (usually organic) substances that depends on the repetitive distribution of solute between two immiscible liquid phases in a series of vessels in which the phases are in contact. The process is continued until homogeneous substances are distributed in various sets of vessels in accordance with their **distribution coefficients** between the two liquid phases. *See also* **Craig apparatus**.

countercurrent transport the movement of a solute in or out of a cell against a concentration gradient by an ATP-independent process. It is due to competition between the solute under consideration and a second solute, with an opposite concentration distribution, for the same membrane carrier protein.

counterelectrophoresis *see* **counterimmunoelectrophoresis**.

counterflow the movement of a substance across a membrane against a concentration gradient.

counterimmunoelectrophoresis *or* **counterelectrophoresis** *other names:* countermigration electrophoresis; immunoelectroosmophoresis; *abbr.*: CIE; a one-dimensional double **electroimmunodiffusion**; a technique wherein diffusion of the reactants towards each other, and hence the formation of precipitin lines, is accelerated by the combination of electrophoresis and electroendosmosis that occurs when an electric potential difference is applied across the gel between the antigen- and antibody-containing wells, with the latter positive to the former.

counterion any ion carrying a charge opposite to that of the charged chemical species with which it is associated; an ion of low M_r with a charge of opposite sign to that of the colloidal ion. *Compare* **co-ion**.

countermigration electrophoresis *an alternative name for* **counterimmunoelectrophoresis**.

counterstain 1 to apply a second stain to a preparation for microscopy. Counterstaining is used to stain in a contrasting way those parts of the preparation that have not been stained by the first stain. **2** any stain so used.

countertranscript *an alternative term for* **antisense RNA**.

countertransport 1 transient outward movement of a substance in equilibrium (radioactively labelled for experimental purposes) caused by addition of the same nonlabelled substance at higher concentration. It is most easily observed in systems of mediated diffusion. **2** *sometimes used, not quite correctly, for* **antiport**.

countertrypsin a glycoprotein trypsin inhibitor from mouse plasma and a member of the **fetuin** family.

counting efficiency the ratio of recorded radioactivity events to the number of actual radioactive disintegrations occurring in the same time and in the same sample. It is sometimes expressed as the percentage efficiency.

COUP *other names*: COUP-TF; v-erbA-related protein; EAR-3; a transcription factor named from one activity, chicken ovalbumin upstream promoter. In association with transcription factor IIB it stimulates initiation of transcription. It is similar to the steroid/thyroid/retinoic nuclear hormone receptors and **seven-up**.

couple 1 a pair of equal and opposite, parallel but not collinear, forces acting on a body, thus producing a turning effect. **2** to join or link (two things) together.

coupled assay a type of enzymic assay of a substrate (or of an enzyme) employed when the reaction in question does not give chromophoric or fluorescent products. A second enzyme reaction that acts on one of the products of the first reaction, and that gives an easily detectable product, is carried out simultaneously with the first reaction. Many coupled assays are based on the formation or disappearance of NADH, which can be easily detected by its absorbance at 340 nm.

coupled oxidation and phosphorylation an intimate relationship between oxidation of substrate and phosphorylation of ADP to ATP such that the two processes cannot proceed independently, as in mitochondria. *See also* **coupling** (def. 3).

coupled reaction either of two reactions, one endergonic and the other exergonic, that are linked energetically, occur simultaneously, and share a common intermediate, such that the overall free energy change for the two reactions is negative.

coupling 1 *(in chemistry)* the covalent linking of one chemical entity to another; *see* **covalent bond**. **2** *(in physics)* **a** an interaction between different parts of a system, e.g. between groups of atoms, electrons, or nuclei. **b** an interaction between two electronic circuits so that power is transferred from one to the other. **3** *(in biochemistry)* the linking of **electron transport** and **oxidative phosphorylation** in isolated mitochondria. Thus, if the **phosphorus:oxygen ratio** is high the mitochondria are said to be tightly coupled. *See also* **uncoupling**.

coupling constant the separation between any two bands of multiple peaks in nuclear magnetic resonance spectroscopy; it is proportional to the magnitude of the **spin–spin coupling** constant.

coupling factor *abbr.*: CF; *archaic term for* **1** any of the proteins functioning in the coupling of ATP synthesis to electron transport in mitochondria. CF1–CF4 are obsolete names for the α–δ subunits of mitochondrial **H^+-transporting ATP synthase**. **2** any of the proteins required for the coupling of ATP synthesis to the photoinduced electron transport in chloroplasts during photosynthesis. The concept has been replaced by the **chemiosmotic coupling hypothesis**.

coupling membrane any biological membrane in which energy-yielding and energy-requiring biochemical processes occur together.

covalence *or* **covalency** nonionic valence between two atoms in a chemical compound, characterized by their sharing of one or more electrons. **—covalent** *adj.*

covalent bond a chemical **bond** formed between two atoms in a molecule by the sharing of electrons, usually in pairs, by the bonded atoms.

covalent catalysis the catalysis of any reaction in which the substrate is modified by forming a covalent bond with the catalyst (enzyme).

covalent chromatography any technique of **column chromatography** in which the substance of interest binds covalently with groups, e.g. –SH groups, on the support medium and is subsequently displaced by an appropriate reagent.

covalent (closed) circle (of DNA) *or* **covalently closed circular DNA** *or* **closed double-stranded DNA** *abbr.*: cccDNA; any double-stranded DNA molecule that is circular (but not necessarily geometrically circular) and in which both polynucleotide strands are completely continuous. *Compare* **Hershey circle**, **open circle**.

covalent modification any of a diverse group of processes in which the initially synthesized structures of biopolymers, especially enzymes, proenzymes, or structural macromolecules, are enzymically modified by the breakage of covalent bonds or the addition of new covalently linked groups. It includes **post-translational modifica-**

tion. The term may sometimes be used in the more restricted sense of reversible interconversion of active and inactive forms of certain metabolic enzymes or other proteins by sets of control enzymes, often by phosphorylation–dephosphorylation.

covariance a measure of the association between two variables. For n pairs of values of two random variables, x and y, this is given by:

$$\mathrm{Cov.}\ (x,y) = (x - \bar{x})(y - \bar{y})/(n - 1)$$

where $\bar{x}$ and $\bar{y}$ are the means of the populations of x and y, respectively. *Compare* **correlation coefficient**, **regression coefficient**, **variance**.

covarion any of the codons in a given gene that may concomitantly vary, so resulting in favourable mutations or in mutations leading to amino-acid substitutions that have little or no effect. [From concomitantly variable codon.]

covirus any virus that exists as two or more separate particles all of which must be present together in the host organism for the complete replication cycle of the virus to occur.

covolume the amount by which the apparent volume of a molecule exceeds the sum of the volumes of the constituent atoms. It is usually 13–14 $\mathrm{cm^3\ mol^{-1}}$ for protein molecules.

coxsackie and adenovirus receptor *see* **CAR**.

cozymase originally, the heat-stable, diffusible fraction of a crude aqueous extract of brewers' yeast that, if added to the heat-labile, nondiffusible fraction (zymase), would enable the alcoholic fermentation of glucose to occur in a cell-free system. The term was subsequently applied to one particular substance present in that fraction, now known as **nicotinamide adenine dinucleotide**.

C_3 pathway *an alternative name for* **reductive pentose phosphate cycle**.

C_4 pathway *an alternative name for* **Hatch–Slack pathway**.

CPBA *abbr. for* competitive protein-binding assay.

CPE *abbr. for* **1** cytopathic effect. **2** cytoplasmic polyadenylation element-binding protein; a protein that binds a specific sequence (called a CPE) at the 3′ untranslated region (UTR) of mRNA, and promotes elongation of the poly(A) tail of the mRNA. The elongation also requires binding of a cleavage-polyadenylation specificity factor (*see* **CPSF**) to the hexanucleotide sequence AAUAAA in the same region.

CPEB *abbr. for* CPE-binding protein. *See* **cytoplasmic polyadenylation element.** .

C peptide **1** **a** the inactive polypeptide excised from **proinsulin** during its conversion to insulin. It contains 31 amino-acid residues in the human but shows greater species variability in both length and amino-acid sequence than does insulin. The structure of porcine C-peptide is (including the flanking basic residues):

RREAQNPQAGAVELGGGLGGLQALALEGPPQKR.

It is released into the bloodstream concomitantly with insulin, hence the blood level is useful in evaluation of B-cell function. **b** that segment of the amino-acid sequence of proinsulin lying between the two residues destined to become respectively the C-terminal residue of the B chain of insulin and the N-terminal residue of the A chain. It consists structurally of the above polypeptide plus two flanking pairs of basic residues. C peptide is named from connecting peptide, and perhaps also because, after A (chain) and B (chain), C (peptide) represents alphabetically the third major structural component of proinsulin. **2** *an alternative name for* C fragment (of *β*-lipotropin) (*see* **lipotropin**).

CpG island a region of 1–2 kb containing a high density of methylated cytosine residues and occurring immediately 5′ to G residues, i.e. in the sequence CpG. CpG islands are frequently found in animal genomes at the 5′ end of genes. In plants the methylated sequence is ...CpNpGp... where N can be any base. Methylation of DNA is a heritable phenomenon that reduces gene expression, probably by increasing the binding of a repressor. CpG islands are a site of high mutational frequency because spontaneous deamination of the methylated cytosine gives thymine, which is not recognized by DNA repair enzymes.

CPK Colours a colour scheme for molecules, conventionally used by chemists for molecular modelling software and based upon the colours of the popular plastic molecular models that were developed by Corey and Pauling, and later improved by Koltun. The assignment of elements to colours includes: carbon, black or grey; oxygen, red; hydrogen, white; nitrogen, blue; and sulfur, yellow.

C_3 plant any plant in which fixation of carbon dioxide occurs predominantly by the **reductive pentose phosphate cycle**; i.e. by incorporation initially into the three-carbon compound 3-phosphoglycerate.

C_4 plant any plant in which fixation of carbon dioxide occurs predominantly by the **Hatch–Slack pathway**; i.e. by incorporation initially into the four-carbon compound oxaloacetate. Such plants are found usually in semiarid conditions with high light levels. They include sugar cane, corn (maize), and many weeds.

cpm *or* **c.p.m.** *abbr. for* counts per minute.

***Cpo*I** a type 2 **restriction endonuclease**; recognition sequence: CG↑G[AT]CCG. *Rrs*II is an **isoschizomer**.

CPSF *abbr. for* cleavage-polyadenylation specificity factor; a protein that specifically binds the hexanucleotide sequence AAUAAA in the polyadenylation signal sequence during processing of the 3′ end of pre-mRNA. It also interacts with the general transcription factor TFIID and with the C-terminal domain of RNA polymerase II.

Cr *symbol for* chromium.

Crabtree effect the inhibition of respiration by glycolysis. The inhibition is small and occurs only in a few types of cells that possess a high glycolytic capacity, e.g. ascites tumour cells and other neoplastic tissues, renal medulla, leukocytes, and cartilage. *Compare* **Pasteur effect**. [Named after Herbert Grace Crabtree, English physician and biochemist, who reported it in 1929.]

Craig apparatus the most widely used type of apparatus for carrying out **countercurrent distribution** experiments. The earlier version (1944) was constructed of metal and the later version (1949) was of modular design and constructed of glass. [After Lyman Creighton Craig (1906–74).]

crambin a hydrophobic protein obtained from seeds of *Crambe abyssinica*. It comprises 46 amino acids, and has two isoforms. The protein belongs to the plant thionin family; its function is unknown.

cranin a form of **dystroglycan**.

Cre a member of the Int family of **recombinases** encoded in the genome of bacteriophage P1. The enzyme catalyses recombination of DNA at *loxP* sites. Linear DNA molecules with *loxP* sites in the same orientation are circularized in *Escherichia coli* strains expressing Cre. Cre can also be expressed in transgenic mammals under the control of a suitable promoter. *See* **Cre-LoxP system**.

CRE *abbr. for* cyclic AMP response element; a sequence,

GTGACGT[A/G][A/G],

that is present in many viral and cellular promoters. When it binds **CREB protein**, transcription of the genes regulated by such a promoter is turned on.

C-reactive protein *abbr.:* CRP; an acidic, crystallizable, heat- sensitive protein of ~118 kDa that is detectable in human or monkey blood serum early in the course of various infections, or when there is inflammation, tissue damage, or necrosis. One of the so-called **acute phase proteins**, it is normally undetectable. Not an immunoglobulin and of unknown function, it is named for its ability, in the presence of $\mathrm{Ca^{2+}}$ ions, to form a precipitate with a pneumococcal somatic C polysaccharide.

creatine *N*-(aminoiminomethyl)-*N*-methylglycine; an important metabolite in muscle, the precursor of **phosphocreatine**.



creatine kinase EC 2.7.3.2; *systematic name*: ATP:creatine *N*-phosphotransferase; an enzyme that catalyses the formation of **phosphocreatine** from ATP and creatine with release of ADP. The enzyme has M and B subunits, derived from different genes, and may exist as the homodimers MM and BB or the heterodimer MB. BB mainly occurs in brain and thyroid, while MM occurs in muscle; MB occurs to a much greater extent in cardiac muscle (30% of total) than skeletal muscle (1% of total) and is thus a useful diagnostic isoenzyme in myocardial infarction, an increased level of the MB isoenzyme occurring between 12 and 36 hours after the infarct. It is present in cytosol and in the intermembrane space of mitochondria, where it is coupled to the ATP/ADP translocator.

creatine phosphate *an alternative name (not recommended) for* **phosphocreatine**.

creatinine 2-amino-1,5-dihydro-1-methyl-4*H*-imidazol-4-one; an end product of creatine metabolism and a normal constituent of urine.



creatinuria the presence of excessive creatine in urine. It occurs during growth in children, in women especially during and after pregnancy, and in conditions of muscle breakdown.

CREB protein *abbr. for* cyclic AMP response element binding protein; a protein that, following phosphorylation by **cyclic AMP-dependent protein kinase** on a single serine residue, binds to the cyclic AMP response element (**CRE**). This then stimulates transcription of genes controlled by regulatory regions that contain the CRE. It regulates genes (responsive to nerve growth factor) for ion channels, for enzymes of neurotransmitter synthesis, and for cytoskeletal components, and is involved in learning, memory, and drug addiction. *See* **CBP**.

CREB protein-binding protein *see* **CBP**.

C region *abbr. for* constant region (of an immunoglobulin).

Cre-LoxP system a site-specific recombination system, derived from *Escherichia coli* bacteriophage P1, that allows the introduction of genetic modifications into specific genes. The method involves engineering short DNA sequences (*loxP* sites) that flank the target DNA, recombination between these sites via the P1-derived recombinase Cre, and excision of the intervening sequence when two *loxP* sites have the same orientation on the same DNA strand.

cretinism a condition of congenital **hypothyroidism** characterized by arrested mental and physical development.

Creutzfeldt–Jakob disease *abbr.*: CJD; a transmissible **spongiform encephalopathy** of humans. It has occurred in four forms: (1) familial (about 15% of cases), caused by mutations of the **prion** protein, in the form of an insertion of 2–9 octapeptide repeats (in addition to the 5 normally present), or a Glu → Lys substitution at codon 200; (2) iatrogenic or acquired, due to inadvertent exposure to CJD-contaminated material, notably human cadaveric growth hormone; (3) **kuru**, which is transmitted by ritualistic cannibalism; and (4) variant CJD (vCJD), an unusual form of the disease thought to be due to consumption of bovine products contaminated with the abnormal **prion** protein responsible for **bovine spongiform encephalopathy** (BSE). The latter is apparently able to cross species. They are all associated with the accumulation in affected brains of an abnormal isoform of a glycoprotein. The familial form shows an autosomal pattern of disease segregation. Forms (1) and (3) usually occur in the fifth or sixth decade of life and progress rapidly (within six months) to severe dementia and death typically in one year. [After Hans Gerhard Creutzfeldt (1885–1964) and Alfons Maria Jakob (1884–1931), German physicians.]

CRF *abbr. for* corticotropin-releasing factor; *see* **CRH**.

CRH *abbr. for* corticotropin-releasing hormone; *other names*: **corticotropin-releasing factor** *or* **corticoliberin** *or* **adrenocorticotropic hormone-releasing factor**. A 41-residue polypeptide released by the hypothalamus into the hypophyseal-portal circulation in response to neural and/or chemical stimuli. It controls the secretion by the anterior pituitary gland (i.e. adenohypophysis) of corticotropin, and possibly also of β-lipotropin and pro-γ-melanotropin – all three are derived from proopiomelanocortin. CRH binds to specific G-protein-associated receptors on the **corticotrope** and increases cyclic AMP levels in the cell, stimulating hormone release only in the presence of Ca^{2+}. It also enhances the rate of transcription of mRNA coding for corticotropin. CRH and its receptors occur in other parts of the brain, indicating that it might be a neuromodulator, and in other parts of the body, where it might have paracrine and immunoregulatory functions. CRH may be secreted by bronchial carcinoid tumours. *See also* **CRH test**.

CRH test a test that is useful in distinguishing **Cushing's disease** from ectopic corticotropin secretion. If **CRH** is given intravenously, there is an increase in plasma cortisol in normal individuals, while usually in Cushing's disease there is an exaggerated response; in ectopic corticotropin secretion there is usually no cortisol response.

Crick strand the lower, or minus, strand in a representation of double-stranded DNA. Open reading frames (ORFs) may occur on either strand of a genomic DNA duplex and it is convenient to distingish between the strands in order to identify ORFs. ORFs in the Crick strand of the yeast genome, for example, are given the suffix C as in the systematic name YLR452C for the *SST2* gene on yeast chromosome XII. *Compare* **Watson strand**.

Crigler–Najjar syndrome an autosomal recessive disease in which there is absence (type I, leading to kernicterus) or deficiency (type II, usually benign) of bilirubin glucuronidation, which results in predominantly unconjugated hyperbilirubinemia. A variety of mutations (deletion, insertion, missense, or nonsense) in a locus at 2q37 for UDP-glucuronosylytransferase I of endoplasmic reticulum of hepatocytes and other cell types is responsible. *See* **Gilbert syndrome**. [After John Fielding Crigler (1919–) and Victor Assad Najjar (1914–), US physicians.]

crinophagy a cellular process in which secretion granules fuse with lysosomes. It serves to dispose of excess secretory products in a cell when the stimulus for their discharge is lacking.

CRISP *abbr. for* cysteine-rich secretory protein; any of a small family of cysteine-rich secretory glycoproteins that escort or guide spermatozoa on their way from the testes to the egg. Examples include TPX1, which promotes adhesion of sperm to Sertoli cells in testes; AEG (acidic-epididymal glycoprotein), which binds sperm during maturation in the epididymis; and allurin, a sperm attractant from the egg jelly of *Xenopus* eggs.

crista (*pl.* **cristae**) **1** any of the inward folds of the inner mitochondrial membrane. Their number, extent, and shape differ in mitochondria from different tissues and organisms. They appear to be devices for increasing the surface area of the inner mitochondrial membrane, where the enzymes of electron transport and oxidative phosphorylation are found. Their shape can vary with the respiratory state of the mitochondria. **2** a sensory structure within the ampulla of a semicircular canal of the inner ear.

critical angle *symbol*: C; the least angle of incidence at which total internal reflection of a ray of light or other electromagnetic radiation occurs when passing through a medium and meeting the boundary with a medium of lesser density (e.g. of glass with air).

critical assessment competition a community-wide competition that aims to stimulate the production of better computational methods in a particular field. Examples include: CASP (Critical Assessment of Structure Prediction), which assesses the reliability of protein structure prediction tools; GASP (Genome Annotation Assessment Project), which assesses the reliability of gene prediction algorithms on eukaryotic genome sequences; and CAMDA (Critical Assessment of Microarray Data Analysis), which assesses the reliability of microarray data analysis tools.

critical electrolyte concentration *or* **critical salt concentration** the concentration of a particular small ion that will displace an ionic molecule (e.g. of a dye or detergent) of like charge from a polyelectrolyte macromolecule. For example, if a polymer P with z negative charges is stained with a dye R^+, the dyed polymer, $P^z zR^+$, is formed according to the equation:

$$P^{z-}zM^+ + zR^+ \rightleftharpoons P^{z-}zR^+ + zM^+$$

where M^+ is a small cation. Hence the ratio of dyed to undyed polymer, D, is given by:

$$D = [P^{z-}zR^+]/[P^{z-}zM^+] = K[R^+]^z/[M^+]^z$$

where K is a constant. If z is large, there is a very sharp change in D at a critical value of $[R^+]/[M^+]$. Then if $[R^+]$ is held constant and

$[M^+]$ varied, an 'all-or-none' change in D is observed at a well-defined $[M^+]$. This concept is used in the **critical electrolyte concentration method** for staining proteoglycans and polynucleotides, and for fractionation of nucleic acids and other polyanions.

critical micellar concentration *or* **critical micelle concentration** *abbr*.: CMC; *symbol*: c_M ; the concentration at which surfactant molecules in a lipid–water mixture begin to aggregate amongst themselves to form micelles in the mixture.

critical pressure the minimum pressure capable of liquefying a gas at its critical temperature.

critical temperature **1** the temperature at or above which a partially miscible two-component system exists as one phase and below which it separates into two phases. **2** the temperature above which liquefaction of a gas cannot occur however great the pressure.

Crk *symbol for* a protooncogene related to v-*crk*, the oncogene of avian sarcoma viruses CT10. The name derives from CT10 regulator of kinase, because the protein causes tyrosine phosphorylation but is not itself a tyrosine kinase. Human Crk contains SH2 and SH3 domains (*see* **SH domain**).

CRM *abbr. for* (immunologically) cross-reacting material.

CRM-positive describing a mutant strain of a microorganism that produces a substance that is immunologically cross-reactive with another (specified) substance, e.g. an enzyme or a toxin, produced by a nonmutant (wild-type) strain. Similarly, a **CRM-negative** strain does not produce such a cross-reactive substance.

cRNA *abbr. for* complementary RNA.

cro *symbol for* a regulatory gene in phage lambda, named from 'C-repressor and other things'. Its product, Cro protein, is a repressor that regulates the expression of the *cI* gene. Cro protein is a small globulin, with a **helix-loop-helix** motif; it occurs as a dimer when bound to the operator.

Crohn's disease *or* **regional enteritis** a chronic inflammatory disease that usually affects the ileum and colon, and frequently runs in families. The inflamed lesions are rich in the inflammatory cytokines, particularly interleukins 1, 6, and 12 and tumour necrosis factor α. Homozygosity for a mutation in a gene (called *NOD2*) on chromosome 16 increases the risk of the disease by a factor of 20–40. *NOD2* encodes an intracellular protein that contains 2 caspase-recruitment domains, a nucleotide-binding domain, and 10 leucine-rich sequence repeats in the C-terminal region. It may have a role in apoptosis or in the recognition of specific components of enteric flora. [After Burrill B. Crohn (1884–1983), US gastroenterologist.]

Cromer-related blood group a blood group antigen carried by **complement decay accelerating factor**.

cromolyn 1,3-bis(2-carboxychromon-5-yloxy)-2-hydroxypropane; a chromone complex that prevents mast cell degranulation; its mechanism of action is unclear. Commonly prepared as the disodium salt, **disodium chromoglycate**, it is used therapeutically to prevent hypersensitivity reactions, especially asthma.



cross-bridge any connection, seen in electron microcopy, between the contractile elements of muscle, specifically between the head of a myosin molecule and an actin filament.

crossed immunoelectrophoresis *or (sometimes)* **quantitative immunoelectrophoresis** two-dimensional single **electroimmunodiffusion**; a rapid and sensitive technique for separation with high resolution and for quantification of antigenic macromolecules. These are separated first by one-dimensional gel electrophoresis and second by gel electrophoresis orthogonally into a gel containing antibodies to one or more known substances, thereby forming a pattern of loop-shaped precipitation zones between antibodies and corresponding antigens. The height and shape of the loops give information about the quantity and quality of the antigens and of the precipitating antibodies. In **tandem-crossed immunoelectrophoresis** two antigen samples are run at the same time with the application holes placed in such a way that related precipitin peaks formed from the respective samples generate double peaks, permitting direct comparison between them. *Compare* **rocket immunoelectrophoresis**.

crossed immunoisoelectric focusing *or* **crossed immunoelectrofocusing** a two-dimensional separation technique for analysing complex mixtures of macromolecules, e.g. samples of body fluids, that combines the high resolution of **isoelectric focusing** with the selectivity of detection of **immunoelectrophoresis**. Isoelectric focusing in a thin layer of gel (polyacrylamide or, preferably, specially modified agarose) is followed by electrophoresis into an antibody-containing gel orthogonally to the first separation; a pattern of precipitation zones is formed by reaction of antibody with corresponding antigen as in **rocket immunoelectrophoresis**.

crossed-line immunoelectrophoresis a technique that combines the procedures of **crossed immunoelectrophoresis** and **line immunoelectrophoresis**. Antigens are separated in a one-dimensional run (as in crossed immunoelectrophoresis) and the resulting gel is applied to the edge of a spacer gel in which a strip of gel containing a uniform mixture of the antigens (as used in line immunoelectrophoresis) is embedded parallel to the edge; this combination of the spacer gel and the first gel is then applied to the edge of an antibody-containing gel into which the antigens are introduced by electrophoresis. The resulting sum pattern of crossed immunoelectrophoresis peaks, each standing on individual baselines, permits a direct comparison of crossed and line immunoelectrophoresis patterns and in addition provides a higher power of resolution.

cross-flow filtration a method of operating a filtration device in which retained fluid is circulated over the membrane surface thus preventing undue build-up of filtered material on the membrane.

cross-hybridization *or* **cross-hybridisation** the hybridization of a polynucleotide probe to another polynucleotide molecule.

crossing over the reciprocal exchange of segments at corresponding positions along pairs of homologous chromosomes by symmetrical breakage and crosswise rejoining of the chromatids. It results in the **recombination** of alleles. In eukaryotes, crossing over usually accompanies meiosis. Mitotic homologous recombination, while common in yeast, is rare in higher eukaryotes. *See also* **Holliday junction**.

cross-link a side bond between different chains (or parts of a single chain) of a polymer, increasing molecular rigidity. **—cross-linked** *adj.*; **cross-linking** *n.*

cross-matching a serological procedure used to select blood for transfusion. The donor's erythrocytes are mixed with the recipient's serum; agglutination of the erythrocytes indicates incompatibility, demonstrating that the recipient's serum contains antibodies to the donor's erythrocytes.

cross of isocline the dark cross formed in **flow birefringence** experiments between concentric cylinders when the polarizer and analyser are orthogonal. As the system has cylindrical symmetry, there are two regions where the average orientation is parallel to the polarizer direction and two regions, orthogonal to the first two, where the average orientation is parallel to the analyser. In these regions no light is transmitted and a dark cross appears. *See also* **extinction angle**.

crossover **1** *an alternative term for* **crossover chromatid**. **2** the individual resulting from a **crossing over**.

crossover chromatid a **chromatid** resulting from **crossing over** of corresponding segments of the chromatids of homologous chromosomes.

crossover effect *(in pharmacology)* the phenomenon in which a drug shows a positive effect at one concentration and a deleterious effect at another.

crossover method any method for investigating a metabolic (or electron transport) pathway by application of the **crossover theorem**.

crossover nuclease a **deoxyribonuclease** that is involved in recombination.

crossover point the point in a series of reactions in a metabolic (or electron transport) pathway, that, when one reaction is specifically inhibited, marks the boundary between reactants whose concentrations increase and reactants whose concentrations decrease. In particular, it is the point in the respiratory chain that, because of the specific action of an inhibitor, marks the boundary between respiratory catalysts that are more reduced and ones that are more oxidized (at steady-state levels). *See also* **crossover theorem**.

crossover theorem a theorem stating that when a series of reactions in a metabolic (or electron transport) pathway is inhibited at a specific reaction, the concentrations of reactants before the inhibited reaction increase above their steady-state values while the concentrations of the reactants after the inhibited reaction decrease below their steady-state values.

crossover unit *an alternative name for* **map unit**.

cross-react to react with a substance other than that for which the reagent is supposedly specific. *Compare* **cross-reaction**. **—cross-reactive** *adj.*

cross-reacting antibody any antibody that is able to react with an antigen that did not specifically stimulate its production. Such cross-reactions may be weaker than the reaction of the antibody with the antigen that caused its production.

cross-reacting antigen **1** any antigen that is able to react with an antibody produced in response to another antigen. This may be because the two antigens share the same determinants or carry determinants that are sufficiently alike stereochemically to enable the antibody to react with both of them. **2** any antigen that has an identical structure in two strains of microorganism, so that antibody raised against one strain will react with the second strain.

cross-reaction the immunological phenomenon in which an antigen reacts with an antibody raised against a different antigen. *See* **cross-reacting antibody**, **cross-reacting antigen**.

cross-reactivation the reappearance of activity in the progeny of a lethal mutant virus following mixed infection of a host cell with one or more active viruses. If the active viruses differ from each other in one or more of their genetic loci, the mutant virus is reactivated by genetic exchange leading to the replacement of its damaged nucleic acid.

cross-sensitivity a state of immunological hypersensitivity to one substance produced by priming an animal with another substance that bears **cross-reacting antigen**.

cross-tolerance **1** a state of immunological **tolerance** to one substance produced by priming an animal with another substance that bears **cross-reacting antigen**. **2** a state of physiological tolerance to one drug resulting from chronic administration of another.

croton oil an oil obtained from the seeds of *Croton tiglinum*, a member of the family Euphorbiaceae. It is an irritant, and contains tumour-promoting **phorbol esters**.

crotoxin a neurotoxic protein of the venom of the South American rattlesnake *Crototus durissus terrificus*. It has phospholipase A2 activity.

crown compound *or* **coronand** any synthetic macrocyclic polydentate nonplanar (generally uncharged) organic compound a molecule of which has three or more ring heteroatoms (usually nitrogen or oxygen) capable of ligation to a metal ion or other cationic entity. The resulting complex is termed a **coronate**. *See also* **crown ether**. *Compare* **cryptand**.

crown ether any of a large subclass of crown compounds that are synthetic macrocyclic polyethers, the molecules of which contain 9–60 atoms in the ring, including 3–20 oxygen atoms. Many crown ethers, especially those containing 5–10 ring oxygen atoms in the molecule, can act as ion-selective complexing agents and ionophores with metal cations; some will solubilize inorganic salts in nonpolar solvents.

crown-gall disease a tumorous disease of many dicotyledonous plants caused by the bacterium *Agrobacterium tumefaciens* and marked by enlargement of the stem near the root crown. The swelling, or **gall**, is produced by the transformation of cells at an infected wound through transfer of the **T-DNA**, part of a large (150–230 kb) plasmid (the **Ti plasmid**) found in oncogenic strains of the bacterium. Transformed tissue is distinguishable by its ability to grow in tissue culture in the absence of plant hormones and by the synthesis of a characteristic **opine**, which is invariably a specific substrate for the particular inducing strain of the bacterium.

CRP *abbr. for* **1** C-reactive protein; **2** cyclic AMP receptor protein; a bacterial that complexes with cyclic AMP, and binds to specific DNA sites near the promoter to regulate the transcription of several catabolite-sensitive operons. The protein induces a severe bend in DNA, and acts as a negative regulator of its own synthesis. It binds to DNA as a dimer.

Crt *symbol for* the cerotoyl (i.e. hexacosonyl) group.

cruciform **1** cross-shaped. **2** a DNA conformation that can be generated from long **palindromes**, e.g.



crustacyanin a protein, found in the carapace of lobsters, that binds the carotenoid **astaxanthin**, which provides the blue colour. a-Crustacyanin is a dimer; ß-crustacyanin is a 16-mer. There are five types of subunit: A1, A2, A3, C1, and C2. Crustacyanin is a member of the **lipocalin** superfamily.

cruzaine *an alternative name for* **cruzipain**.

cruzipain *or* **cruzaine** a cysteine proteinase (EC 3.4.22.–) that hydrolyses chromogenic peptides at the carboxyl Arg or Lys. It requires at least one more amino acid, preferably Arg, Phe, Val, or Leu, between the terminal Arg or Lys and the amino-blocking group. The purified enzyme digests itself. The enzyme plays a role in development and differentiation of *Trypanosoma cruzi*.

CRX *abbr. for* cone-rod homeobox protein; a transcription factor protein (299 residues) that contains a homeodomain in its N-terminal region and is expressed specifically in developing and mature photoreceptor cells of the retina. It regulates expression of the genes for rhodopsin and other photoreceptor-specific proteins. Mutations in the gene at 19q13.3 result in a form of blindness called Leber's congenital amaurosis.

CRY *abbr. for* **cryptochrome**.

cryo+ *comb. form* indicating low temperature.

cryobiochemistry the study of biochemical substances and processes at subzero temperatures, i.e. below the freezing point of water. The field has expanded because of the development of **cryosolvents**. *See also* **cryoenzymology**.

cryobiology the science that is concerned with the study of the effects of very low temperatures on organisms.

cryoelectron microscopy *see* **electron microscopy**.

cryoenzymology the study of enzymes at low temperatures. By employing temperatures below 0°C and fluid **cryosolvents**, enzyme reaction rates can be reduced sufficiently for normally transient enzyme–substrate intermediates to be studied.

cryogen any substance used to produce a low temperature; e.g. a freezing mixture.

cryogenic of, or relating to, very low temperatures.

cryogenics the branch of science concerned with the production of very low temperatures and the study of phenomena occurring at these temperatures.

cryoglobulin any **globulin**, especially IgG or IgM, that forms a gel or flocculent precipitate, or spontaneously crystallizes, on cooling of a solution or a sample of serum containing it. *See also* **cold-insoluble globulin**.

cryomicrotome any **microtome** arranged in a **cryostat** and used to prepare thin sections of frozen tissue for microscopic examination.

cryoprecipitate the precipitate of a **cryoglobulin**.

cryopreservation the science of preserving cells, tissues, or organs over long periods with the aid of very low temperatures.

cryoscope any instrument or device for the determination of freezing points.

cryoscopy the measurement of freezing points, especially the determination of relative molecular mass or osmotic pressure by measurements of freezing point depressions. **—cryoscopic** *adj.*

cryosolvent any mixture of water and one of a select number of polar organic solvents that is used to maintain proteins in fluid solution at temperatures below 0°C without denaturation.

cryostat an apparatus used to produce and maintain a constant low temperature in an enclosure or liquid bath.

cryosublimation the process whereby water, or another solvent, is sublimed from a frozen sample and is collected in a cold trap. *Compare* **lyophilization**.

cryotolerant tolerant of low temperatures.

cryptand any synthetic macrooligocyclic organic compound, a molecule of which consists of two or more rings linked together by bridgehead (generally nitrogen) atoms to form a three-dimensional cagelike molecular structure having sufficient space within it to accommodate any one of various cations and thereby form a **cryptate**. *Compare* **crown compound**.

cryptate the adduct of a **cryptand** and a metal ion or other cationic entity. The cation is bound within the molecule by polydentate ligation to heteroatoms in the cryptand, an exceptionally stable compound being formed.

cryptic **1** hidden, secret. **2** not apparent, unrecognized, masked; e.g. of a medical condition. **3** (especially of the colouring of an animal) serving to conceal. **4** of a particle-bound enzyme, that it is not as accessible to substrate as when it has been solubilized.

crypticity *or* **latency** the property of being **cryptic**.

cryptic plasmid a **plasmid** to which no phenotypic traits have been ascribed.

cryptic splice site a randomly occurring site in the genome that contains the consecutive six-nucleotide consensus sequence for 5′ or 3′ intron splicing but is not normally used for that purpose. Such sites are expected to occur randomly every 4 kb or so on average. Mutations at splice sites may result in a nearby cryptic splice site being used instead, with the consequence that an abnormally spliced mRNA transcript is produced.

crypto+ *or (before a vowel)* **crypt+** *comb. form* meaning secret, hidden, concealed, unrecognized.

cryptochrome *abbr.*: CRY; an FAD-containing protein that is a receptor for blue light in plants and in *Drosophila* and other animals. In *Arabidopsis* it interacts with **COP1** to mediate photomorphogenetic development. In animals expression in the suprachiasmatic nucleus of the hypothalamus is enhanced by the clock-BMAL1 dimer, and in the forebrain by the NPAS2-BMAL1 dimer. CRY is regulated by a protein serine/threonine kinase. Humans possess genes for CRY1 and CRY2. *See* **BMAL1**, **clock**, **NPAS2**.

cryptotope a hidden immunological determinant. *Compare* **epitope**.

cryst. *abbr. for* crystalline, or crystallized.

crystal any three-dimensional solid aggregate in which the plane faces intersect at definite angles and in which there is a regular internal structure of the constituent chemical species.

crystal lattice the array of **unit cells** along parallel straight lines that makes up the structure of a crystal.

crystallin any of numerous water-soluble structural proteins found in the lens of the eye. Together, the crystallins account for almost 90% of the total lenticular protein. Most vertebrate lenses contain three major classes of crystallin, designated α-, β-, and γ-; in birds and reptiles, there is a fourth, designated δ-, which is homologous to the urea cycle enzyme argininosuccinate lyase. ε-Crystallin is a homologue of the enzyme **acetate dehydrogenase**. Although there are wide variations between species in the proportions of the various crystallins, and in the extent of their post-translational modification, or degree of aggregation, they display significant conservation of primary structure.

crystalline *abbr.*: cryst.; having the structure or characteristics of a **crystal**; made up of crystals; like a crystal.

crystallize *or* **crystallise** to form, or cause to form, crystals, e.g. by slowly removing solvent from a solution to make a solute form one or more crystals.

crystallized *or* **crystallised** *abbr.*: crys.; (of a substance) having been induced into a crystalline form.

crystallography the study of the geometric forms of crystals. *See also* **X-ray crystallography**. **—crystallographer** *n.*; **crystallographic** *adj.*

crystalloid **1** *an alternative term for* **crystalline**. **2** any solute that can pass through a semipermeable membrane that does not allow the passage of a **colloid**. **3** any of the protein crystals that occur in seeds and other plant storage organs.

crystalluria the presence of rather insoluble metabolic products (e.g. orotic acid, xanthine, uric acid, cysteine, oxalic acid) in crystalline form in urine, usually as a result of metabolic disorder. Calcium phosphate crystals are common especially in alkaline urine.

Cs *symbol for* cesium.

CS *abbr. for* choriomammotropin.

CSD *abbr. for* cold-shock domain (*see* **cold-shock protein**).

CSF *abbr. for* **1** cerebrospinal fluid. **2** colony stimulating factor.

cSNP *abbr. for* coding single nucleotide polymorphism.

CSP *abbr. for* cell surface protein; *see* **fibronectin**.

CSPCP *abbr. for* cartilage-specific proteoglycan core.

CstF *abbr. for* CTD-associated cleavage stimulatory factor; a protein that stimulates cleavage of eukaryotic pre-mRNA at a site situated 15–25 nucleotides 3′ of the AAUAAA sequence in the 3′ untranslated region. Like CPSF (see **polyadenylation element**), CstF binds the C-terminal domain of the largest component of RNA polymerase II and activates poly(A) polymerase to form the poly(A) tail of the mature mRNA.

$C_{o}t$ *or* **Cot** a measure of DNA kinetic **complexity** used in the renaturation analysis of DNA genomes. It is the product of initial DNA concentration, C_{o}, and time, t. Highly reiterated sequences will renature at low $C_{o}t$ values while unique sequences will renature at high $C_{o}t$ values. $C_{o}t_{1/2}$ is the value representing half complete renaturation.

CT *abbr. for* computerized tomography (*see* **tomography**).

CTAB *abbr. for* cetyltrimethylammonium bromide.

CTAC *abbr. for* cetyltrimethylammonium chloride; a detergent used for the solubilization of inclusion bodies.

CTAP-III *abbr. for* connective-tissue activating peptide III; *see* **LA-PF4**.

CTD *abbr. for* C-terminal domain; usually used specifically for the C-terminal domain of the largest subunit of RNA polymerase II, which contains 52 heptapeptide (YSPTSPS) repeats in which Y, S, and T are potential targets for protein kinases. In budding yeast, the domain contains 26 such repeats. The domain interacts with many proteins including those that contain a WW domain. It plays an intimate role in pre-mRNA capping, splicing, and polyadenylation. *See* **CstF**.

CTD kinase *see* **[RNA-polymerase]-subunit kinase**.

ctDNA *see* **DNA**.

C-terminal peptide amidation a type of post-translational modification, occurring in the Golgi apparatus, whereby a C-amidated peptide is formed and released from a precursor polypeptide. Many biologically active peptides and peptide hormones are only active in the C-amidated form. The amide group is derived from a glycine residue next to the peptide's C-terminus. Two enzymes are required for the reaction: peptidylglycine α-amidating monooxygenase and peptidyl α-hydroxyglycine α-amidating lyase. *See* **peptide amidation**.

C terminus *or* **C terminal** that end of any peptide chain at which the 1-carboxy function of a constituent *a*-amino acid is not attached in peptide linkage to another amino-acid residue. This function may bear an amide group, or other substituent, in nonpeptide linkage; more commonly, it is free (also unprotonated and negatively charged) – the chain end may then also be termed the **carboxy(l) terminus** or **carboxy(l) terminal**. *Compare* ***N* terminus**. —**C-terminal** *adj.*

C1-tetrahydrofolate synthase a trifunctional enzyme that consists of two major domains: an N-terminal domain, containing N^5,N^{10}-methylenetetrahydrofolate dehydrogenase and N^5,N^{10}-methenyltetrahydrofolate cyclohydrolase, and a C-terminal domain containing **formate–tetrahydrofolate ligase** domain. It is a homodimer.

CTF **1** *abbr. for* CAAT box-binding transcription factor *or* nuclear factor 1 (*abbr.*: NF-I); any of a class of **transcription factors** for the eukaryotic RNA polymerase II promoters, **CAAT box** sequences; CTF binds to DNA as a homodimer. **2** *abbr. for* competence transcription factor *or* competence protein K; a product of a bacterial regulatory gene required for expression of late competence genes.

CTGF *abbr. for* connective tissue growth factor.

CTH *abbr. for* ceramide trihexoside (Cer(Hex)$_3$ preferred).

CTP *abbr. for* cytidine 5′-triphosphate.

CTP synthase EC 6.3.4.2; *systematic name*: UTP:ammonia ligase (ADP-forming); *other names:* CTP synthetase; UTP– ammonia ligase. An enzyme responsible for *de novo* synthesis of CTP that in bacteria catalyses the reaction between ATP, UTP, and NH_3 to form CTP, ADP, and orthophosphate. In animals, the amino group is donated by glutamine. The enzyme bears the same EC number and the reaction is analogous to that of the bacterial enzyme, with glutamine replacing ammonium ion, and CTP and glutamate as products.

CTS *(in clinical biochemistry) abbr. for* catalase.

C-type lectin any of a group of carbohydrate-binding proteins of related structure that require Ca^{2+} for activity. An example is mannose-binding protein.

Cu *symbol for* copper.

CUA a codon in mRNA for L-leucine.

cubic symmetry the symmetry of one of the three **point groups** of a globular oligomeric protein; it may be **tetrahedral**, designated T_n, where n is 12; **octahedral**, designated O_n, where n is 24; or **icosahedral**, with 60 identical subunits.

cubitus interruptus *abbr.*: Ci; a transcription factor of *Drosophila* that is activated by the G-protein-coupled receptor Smoothened when this is released by binding of Hedgehog to Patched. Ci is a 155 kDa protein found in a multiprotein complex that is associated with microtubules. Its N-terminal region contains four zinc-finger domains, and its C-terminal region interacts with CREB protein, which appears to be a cofactor for Ci. In the inactive form, Ci is cytosolic, but on activation by protein kinase A it enters the nucleus. In vertebrates there are three Ci homologues called Gli1, Gli2, and Gli3. Several autosomal dominant syndromes that produce a number of malformations in humans are associated with truncating mutations in Gli3.

cubulin a peripheral membrane protein (≈400 kDa) that is the receptor for the intrinsic factor–cobalamin complex in the ileum, and facilitates its endocytosis. It copurifies with **LRP2** and colocalizes with it in intestinal and renal epithelium. The N-terminal region of cubulin contains 8 EGF repeats and 27 contiguous CUB domains (each of ≈110 residues) similar to those of certain development control proteins. Several mutations in the gene at 10p12.1 cause megaloblastic anemia from cobalamin deficiency.

CUC a codon in mRNA for L-leucine.

cucurbitacin any of a group of complex triterpenoids that are the bitter principles of the cucumber family, Cucurbitaceae.

CUG a codon in mRNA for L-leucine.

cullin *or* **Cdc53p** any of a small family of proteins homologous with Cdc53p of yeast and Cul1 of *Caenorhabditis elegans*. In yeast Cdc53p is present in complexes that target specific proteins for ubiquitin-mediated degradation. Cul1 regulates cell cycle exit in *C. elegans*. Several homologues are present in mammalian cells as components of complexes that contain E3 ubiquitin ligase.

culture **1** **a** a collection of cells, tissue fragments, or an organ that is growing or being kept alive in or on a nutrient medium (i.e. **culture medium**); *see also* **cell culture**, **tissue culture**. **b** any culture medium to which such living material has been added, whether or not it is still alive. **2** the practice or process of making, growing, or maintaining such a culture. **3** to grow, maintain, or produce a culture.

culture medium any nutrient medium that is designed to support the growth or maintenance of a **culture** (def. 1). Culture media are typically prepared artificially and designed for a specific type of cell, tissue, or organ. They usually consist of a soft gel (so-called solid or semisolid medium) or a liquid, but occasionally they are rigid solids.

cUMP *abbr. for* cyclic UMP; *see* **uridine 3′,5′-phosphate**.

cumulative inhibition the inhibition of an enzyme resulting from the action of a number of **effectors**, each of which reduces the activity of the enzyme by a fixed percentage irrespective of the degree of inhibition already extant as a result of the presence of other inhibitors.

cupin any of a superfamily of protein domains, with some 18 subclasses, found in archaea, eubacteria, and eukaryotes. They are present most often in enzymes with zinc-containing active sites based around a histidine cluster. The domain consists of a flattened beta barrel made of two sheets, each of five antiparallel beta strands, that form a cleft for the metal ion. It was first found in **germin**, where a manganese ion is coordinated to three histidines and a glutamate residue.

cuprein any of a group of copper proteins now known as **superoxide dismutase**.

Cuprolinic Blue *the proprietary name for* quinolinic phthalocyanine (*abbr.*: QPC; no CI number); a copper-containing, intensely blue dye used for the visualization of RNA and other polynucleotides. The size and shape of the molecule have been designed to provide an exactly complementary fit between any pair of adjacent isoindole rings in the dye and base pairs in nucleic acids.



cuproprotein any protein containing one or more copper atoms.

curare a poisonous extract from certain tropical South American vines of the genera *Strychnos* and *Chondodendron*, used by Amazon and Orinoco Indians as an arrow poison; it blocks neuromuscular transmission in voluntary muscle and is useful as a muscle relaxant, e.g. in surgery. *See* **(+)-tubocurarine** (the active principle) for the mechanism.

curarize *or* **curarise** to treat with (or as if with) curare; especially to cause muscular relaxation or paralysis. —**curarization** *or* **curarisation** *n.*

curculin a polypeptide present in the fruit of *Curculigo latifolia*, a stimulant herb that grows wild in western Malaysia. It is sweet tasting, and has taste-modifying activity. It exists as a homodimer.

curcumin 1,7-bis(4-hydroxy-3-methoxyphenyl)-1,6-heptadiene-3,5-dione; turmeric yellow; a condiment and dye obtained from dried and powdered rhizomes of *Curcuma domestica (C. longa)*. It pro-



vides the characteristic colour of curries, and is also an inhibitor of 5-lipoxygenase and **prostaglandin-endoperoxide synthase** cyclooxygenase activity. *See also* **catechin**.

curdlan *see* **callose**.

curie *abbr*.: Ci *(formerly* C); a non-SI unit of (radio)activity or of radioactive material. Originally (1910) it was defined as the quantity of radon in radioactive equilibrium with one gram of radium. Latterly (1968) it was defined as a unit of activity equal to 3.7×10^{10} disintegrations per second or, less correctly, as the quantity of any radioactive material having such activity. Hence, 1 Ci = 3.7×10^{10} **becquerels**. [After Pierre Curie (1859–1906), French physicist and chemist (not after Marie Curie as sometimes stated).]

curing *(in genetics)* the elimination of a **plasmid** from its host cell.

curli a class of proteins that form highly aggregated fibres on the outer surface of *E. coli* and *Salmonella* species. They are involved in colonization of inert surfaces and mediate binding to a variety of host proteins. They have amyloid-specific properties and are rich in beta-sheet structure.

curtain electrophoresis *see* **continuous-flow electrophoresis**.

cushingoid of, or relating to, **Cushing's disease** or **Cushing's syndrome**, or any of the signs and symptoms associated with these conditions.

Cushing's disease a pituitary-dependent, corticotropin-induced, bilateral adrenal hyperplasia that is one of several conditions embraced by **Cushing's syndrome**. [After Harvey Williams Cushing (1869–1939), US neurosurgeon.]

Cushing's syndrome the group of symptoms and signs resulting from prolonged exposure to inappropriately high plasma **cortisol** concentrations, caused either by primary disease (e.g. tumour) of the adrenal glands or by excessive production of **corticotropin** because of disease (e.g. basophil tumour) of the anterior pituitary. It may also be caused by excessive secretion of cortisol or corticotropin from ectopic sites, or by prolonged therapy with (large doses of) cortisol or other glucocorticoids. The syndrome is characterized by obesity of the trunk, polycythemia, osteoporosis, and glycosuria. The underlying disorder may be corticotropin-dependent or -independent. Of the corticotropin-dependent disorders, **Cushing's disease** is the most common, accounting for 68% of all types of Cushing's syndrome. The remainder (15% of all types) result from ectopic corticotropin-secreting tumours, that is, non-endocrine tumours such as lung, gut, ovarian, or carcinoid, which in some cases secrete corticotropin. Corticotropin-independent disorders include adrenocortical adenoma (5%) or carcinoma (3%) and nodular adrenal hyperplasia (9%).

cut **1** to sever, to make an incision, to divide (with a sharp instrument). **2** to separate into **fractions**. **3** a double-stranded scission in a polynucleotide duplex. *Compare* **nick**. **4** informal term for a **fraction**, such as one obtained in column chromatography or distillation.

cutaneous of, pertaining to, or in the skin.

cutin a polyester consisting of polyoxygenated C_{16} and C_{18} fatty acids esterified to each other to form a tough, inelastic, and hydrophobic meshwork that (like suberin) renders the walls of plant epidermal cells impermeable to water. It is usually associated with waxes on leaf and stem surfaces. The fatty acyl-CoAs are hydroxylated by oxidases in the endoplasmic reticulum and secreted into the cell wall space where esterification is catalysed by hydroxyacyl CoA:cutin transacylase.

cutinase an enzyme that catalyses the hydrolysis of the plant polyester, cutin, to allow penetration by phytopathogenic fungi.

CUU a codon in mRNA for L-leucine.

cuvette a small transparent vessel, often with parallel sides of specified separation, used to hold a liquid specimen, especially for optical or spectral measurements. *See also* **cell** (def. 2).

C-value the quantity of DNA present in a single haploid genome.

C-value paradox the lack of correlation between the amount of DNA in the haploid genome (i.e. **C-value**) and the complexity of the organism. The paradox was explained when it was discovered that a large proportion of some genomes is made up of repetitive DNA.

Cya *symbol for* a residue of the α-amino acid cysteic acid (an artefact in peptide sequences).

cyan+ *a variant form (before a vowel) of* **cyano+**.

cyanate **1** the anion, $N{\equiv}C{-}O^{-}$, derived from cyanic acid ($HOC{\equiv}N$). **2** any salt of cyanic acid. **3** any organic compound containing the monovalent group $-O{-}C{\equiv}N$. *Compare* **isocyanate**.

cyanelle a cyanobacterium-like structure, considered as a descendant of an ingested cyanobacterium, that exists as an endosymbiont in the biflagellate protist *Cyanophora paradoxa*. The cyanelle has photosynthetic properties resembling those of cyanobacteria but its genome size is about 10% of those reported for cyanobacteria.

cyanhydrin *a former name for* **cyanohydrin**.

cyanide **1** the anion, $N{\equiv}C^{-}$, derived from hydrocyanic acid (HCN). This ion blocks the electron transport chain by reacting with the ferric form of cytochrome aa_3 and thus acts as an inhibitor of respiration. **2** any salt of hydrocyanic acid. **3** any organic compound containing the monovalent cyano group, $-C{\equiv}N$; such a compound may also be known either as a nitrile or as a carbonitrile, depending respectively on whether its carbon atom is included in or excluded from the numbering of an attached chain.

cyanide-resistant oxidase *an alternative name for* **alternative oxidase.**.

cyanide-resistant respiration a respiratory pathway, occurring only in mitochondria of some plants, yeasts, and bacteria, that is unaffected by **cyanide**. Electron transport from NADH or succinate to O_2 involves a nonheme iron protein as the terminal oxidase; this is insensitive to cyanide. The cyanide-resistant pathway complements the more usual cyanide-sensitive pathway; this contains cytochrome oxidase, which is inhibited by cyanide. Cyanide-resistant respiration is not found in animals.

cyanidin *see* **anthocyanidin.**

cyano+ *or (before a vowel)* **cyan+** *comb. form* denoting **1** the cyanide ion or hydrocyanic acid. **2** the –CN group in covalent linkage. **3** (dark) blue.

cyanobacteria *or* (*formerly*) **blue-green algae** a very heterogeneous group of prokaryotic photosynthetic organisms all of which contain chlorophyll *a*, carotenoids, and phycobiliproteins arranged in thylakoids. They lack chloroplasts, unlike true algae, and differ from photosynthetic bacteria, in, e.g., evolving oxygen during photosynthesis. Many can fix nitrogen.

cyanoborohydride any member of a group of compounds with the structure MBH_3CN, where M is an alkali metal (usually sodium). They are reducing agents similar in action to borohydride but more stable, more lipophilic, and more selective. They are especially useful for the facile reduction of aldehydes and ketones in acid conditions to the corresponding alcohols, for the reductive amination of aldehydes and ketones in the presence of an amine, and for the reductive methylation of amines (including amino acids and proteins) in the presence of formaldehyde.

cyanocobalamin the most usual form of **vitamin B_{12}**, in which the sixth position on the cobalt atom in **cobalamin** is filled by a cyanide group (the cyanide group being an artefact of the isolation procedure).

cyanogen bromide *or* **bromine cyanide** CBrN, or CNBr, or BrCN; a volatile solid (at ordinary temperatures) with two main uses in biochemistry: (1) in the sequencing of proteins, because (in 90% formic acid) it converts methionine residues in peptide linkage to homoserine residues, with simultaneous cleavage of peptide bonds whose carbonyls are contributed by methionine residues; also (in anhydrous heptafluorobutyric acid) it specifically cleaves tryptophanyl peptide bonds; and (2) for activating cross-linked agarose so that almost any molecule containing amino groups can be coupled to it to prepare a specific affinity adsorbent.

cyanogenesis the production or yielding of cyanide ions or hydrocyanic acid.

cyanogenic *or* **cyanogenetic** **1** *or* **cyanophoric** describing any glucoside or other glycoside containing a cyano group that is released as hydrocyanic acid on acid hydrolysis; e.g. amygdalin. Such compounds occur in the kernels of various fruits. **2** describing any plant that synthesizes such a glycoside.

cyanoginosin a cyclic heptapeptide toxic agent responsible for numerous cases of poisoning among South African livestock that consume water contaminated with blooms of cyanobacteria. About seven variants are known.

cyanoglobin an unusal monomeric myoglobin-like hemoprotein found in multicellular cyanobacteria.

cyanohydrin *or* (*formerly*) **cyanhydrin** any member of a class of *α*-hydroxynitriles formed by the base-catalysed addition of a cyanide ion to an aldehyde; such compounds are formed also from some reactive ketones.

cyanolabe *or* **cyanopsin** *or* **chloropsin** *or* **chlorolabe** *See* **cyanopsin**, **opsin**.

cyanophage any virus whose host is a cyanobacterium.

cyanophoric *an alternative term for* **cyanogenic** (def. 1).

cyanophycin granule *or* **structured granule** a type of granule, without apparent limiting membrane, that is observed in most, if not all, cyanobacteria. These granules are variable in size and shape, with diameters up to about 500 nm, and contain polypeptides of 25–100 kDa with a 1:1 arginine:aspartic acid ratio. They are believed to act as a nitrogen reserve.

cyanopsin *or* **chloropsin** *or* **chlorolabe** a greenish-blue, light-sensitive, visual pigment occurring in the cone cells of the retina. It consists of a specific opsin combined (as a Schiff's base) with 3,4-didehydro-11-*cis*-retinal. *See also* **3,4-didehydroretinal, opsin**.

cyanosis the bluish appearance of the skin and mucous membranes due to insufficient oxygenation of the blood in the capillaries. —**cyanotic** *adj.*

cyanosome *an alternative name for* a **phycobilisome** in cyanophytes.

cybrid a portmanteau word used to denote a line of cultured mammalian cells that is a cytoplasmic hybrid of two other lines, as shown by inheritance of biochemical or other characteristics.

cycacin methylazoxymethanol *β*-D-glucoside; a toxic substance from the seeds of *Cycas revoluta*, the aglycon of which is carcinogenic.

cycl+ *a variant form (before a vowel) of* **cyclo+**.

cyclamate the anion of cyclamic acid, cyclohexylsulfamic acid. It is used in some countries as a sweetening agent, but is banned in the USA because of its possible carcinogenicity.

cyclase any enzyme that catalyses ring closure, e.g. **adenylate cyclase**.

cyclazocine 3-(cyclopropylmethyl)-1,2,3,4,5,6-hexahydro-6,11-dimethyl-2,6-methano-3-benzazocin-8-ol; a potent benzomorphan narcotic analgesic agent. It is an antagonist at μ-, and an agonist at δ- and especially κ-opioid receptors. Binding to σ-receptors may explain its psychotomimetic actions.



cycle 1 any recurring period of time in which certain events or operations occur, complete themselves, or repeat themselves in a regular sequence. **2** any sequence of changes occurring in a system in which the system is eventually restored to its initial state. **3** *(in biochemistry)* any closed sequence of metabolic reactions in which an end product acts as a reactant in the initiation of the cycle, e.g. the **tricarboxylic-acid cycle**. **4** *(in ecology)* any closed sequence of large-scale processes that describes the nutritional interdependence of animals, plants, and microorganisms, e.g. the **nitrogen cycle**. **5** to process through a cycle or cyclic system; to pass through cycles or to vary in a cyclical manner.

cycle sequencing a method for DNA sequencing based on dye-termination and employing repeated cycles of melting, annealing, and synthesis in a manner similar to that of **polymerase chain reaction**. *See* **dye-terminator sequencing**.

cyclic 1 of, relating to, moving in, or being a cycle. **2** (of an organic chemical compound) containing one (i.e. monocyclic) or more (i.e. polycyclic) rings of atoms. *Compare* **heterocyclic**, **homocyclic**. —**cyclically** *adv.*

cyclic adenosine 5′-diphosphoribose *or* **cyclic ADP-ribose** *abbr.*: cyclic ADPR *or* cADPR; a metabolite formed from NAD^+ by ADP ribosyl cyclase (ARC) that may be responsible for mediating certain of the latter's regulatory effects. It consists of a ribose molecule linked by its C-5 hydroxyl to the *β*-phosphate of ADP and by its C-1 hydroxyl to the adenosine amino group. It may be involved in regulating intracellular Ca^{2+} concentrations and in activating the nonskeletal form of the ryanodine receptor Ca^{2+} channel.

cyclical *a variant form of* **cyclic** (def. 1).

cyclic AMP *or* **cAMP** *abbr. for* adenosine 3′,5′-phosphate. *See also* **adenylate cyclase**.

cyclic AMP-dependent protein kinase *or* **protein kinase A** (*abbr.*: PKA) a **protein kinase** that is regulated by cyclic AMP (cAMP). In **type I**, the inactive form of the enzyme is composed of two regulatory and two catalytic subunits; activation by cAMP produces active catalytic monomers and a regulatory dimer with four bound cAMP molecules. Expression of regulatory subunits in some tissues is constitutive and in others is inducible. In **type II**, regulatory subunits mediate membrane association by binding to anchoring proteins, including the MAP-2 kinase and **AKAP**. The inactive enzyme is composed of two regulatory and two catalytic subunits; activation by cAMP produces two active catalytic monomers and a regulatory dimer that binds four cAMP molecules.

cyclic AMP phosphodiesterase (number EC 3.1.4.17 shared with **cyclic GMP phosphodiesterase**); *recommended name*: 3′,5′-cyclic-nucleotide phosphodiesterase; an enzyme that catalyses the hydrolysis of a nucleoside 3′,5′-cyclic phosphate to a nucleoside 5′-phosphate. The intracellular concentration of cyclic AMP is regulated by low-affinity (type 1) and high-affinity (type 2) enzymes. The enzymes are monomers; type 2 are well conserved.

cyclic AMP receptor any of various receptor molecules that bind cyclic AMP, especially **CRP** (def. 2), a bacterial catabolite (gene) activator protein. Other examples are the signalling receptors of the slime mould, *Dictyostelium discoideum*, which are similar to other eukaryotic G-protein-linked receptors. Receptor 1 is involved in aggregation, and receptor 2 is expressed after aggregation in prestalk cells.

cyclic AMP response element *see* **CRE**.

cyclic analysis a procedure that is useful, e.g. in flame spectrophotometry, for minimizing the effects of any mutual interference between two or more components of a sample being analysed. First, the concentration of each such component is estimated. Next, standards for each of the components are prepared containing the other interfering components at their estimated concentrations and the estimations are repeated. Then fresh standards are prepared, using the revised values for the concentrations of the interfering components, and further estimations are made; and so on, until a constant and accurate value for each component is obtained. In practice, usually only two or three such cycles of analysis are necessary.

cyclic CMP *see* **cytidine phosphate**.

cyclic diguanylic acid bis(3′-5′)cyclic guanylic acid; a potent activator of cellulose synthase in the bacterium *Acetobacter xylinum*.

cyclic electron flow *see* **cyclic photophosphorylation**.

cyclic fatty acid any of a class of fatty acids that contain a carbocyclic unit. They include those with a cyclopropane unit, such as **lactobacillic acid** found in bacterial membranes, those with a cyclopropene unit such as sterculic acid (*see* structure), found in Sterculiaceae, and those with a cyclopentene unit, found in seed fats of Flacourtiaceae, these including manaoic acid (*see* structure). **Mycolic acids** are 2-alkyl-3-hydroxy acids with up to 80 carbons, and contain cyclopropane units. Fatty acids containing a cyclohexane unit are also known.



sterculic acid



manaoic acid

cyclic GMP *abbr. for* guanosine 3′,5′-phosphate.

cyclic GMP-dependent protein kinase *or* **PKG** a cytosolic protein serine/threonine kinase that contains a catalytic and a regulatory domain in a single polypeptide (80 kDa). Binding of cGMP causes activation by releasing part of the regulatory domain from the catalytic site.

cyclic GMP phosphodiesterase (EC 3.1.4.17, number shared with **cyclic AMP phosphodiesterase**); *recommended name*: 3′,5′-cyclic-nucleotide phosphodiesterase. An enzyme that catalyses the hydrolysis of a nucleoside 3′,5′-cyclic phosphate to a nucleoside 5′-phosphate. It is involved in the regulation of the concentration of cyclic GMP, and thereby involved in the transmission and amplification of the visual signal; *see* **guanosine 3′,5′-phosphate**. Example from mouse rod cells has three subunits: α and β are catalytic subunits (short form of β is β′ from alternative splicing), and γ is a regulatory subunit; α and β are typical cyclic nucleotide phosphodiesterases.

cyclic IMP *symbol*: cIMP *or* Ino-3′,5′-*P*; inosine 3′,5′-(cyclic)phosphate.

cyclic nucleotide any nucleotide in which the phosphate group is in diester linkage to two positions on the sugar residue, usually 3′,5′ but also sometimes 2′,3′.

cyclic peptide nanotube a stack of synthetic, cyclic, antibacterial peptides in which each monomer consists of 6–8 residues of alternating D- and L-amino acids. The peptides enter the disease-causing bacteria, insert as nanotubes into their membrane, and kill them.

cyclic photophosphorylation the processes that occurs in photosystem I in which the high-potential electron in bound ferredoxin can be transferred to cytochrome b_{563}, rather than to NADP$^+$, and then back to the oxidized form of P700 through cytochrome c_{552} and plastocyanin with the generation of one molecule of ATP. *See* **photosystem**.

cyclic symmetry the symmetry of a **point group**, designated C_n, having a geometric arrangement of the subunits such that a rotation of 360°/*n* transposes the structure into itself (i.e. it is indistinguishable from the original one). A dimeric molecule with chemically and spatially identical subunits must necessarily belong to the point group C_2. In general, a molecule with C_n symmetry will be a closed ring containing *n* subunits (e.g. of triangular, square, pentagonal, and hexagonal appearance for molecules containing three, four, five, and six subunits, respectively). If *n* is an odd number, C_n is the only symmetry possible.

cyclic UMP *symbol*: cUMP *or* Urd-3′,5′-*P*; uridine 3′,5′-(cyclic)phosphate.

cyclic voltammetry a form of **voltammetry** in which the working electrode potential is swept back and forth across the formal potential of the analyte. Repeated reduction and oxidation of the analyte causes alternating cathodic and anodic currents to flow at the electrode. Experimental results are usually plotted as a graph of current versus potential. The method is used to measure midpoint redox potentials of compounds, including proteins, and to follow intramolecular electron transfer. A three-electrode system is used, comprising a working electrode (such as platinum or glassy carbon), a counter-electrode, and a reference electrode.

cyclin any of a group of proteins that are involved in regulation of the eukaryotic **cell-division cycle**. Cyclins periodically rise and fall in concentration in step with the cycle. Individual cyclins activate particular **cyclin-dependent protein kinases** (Cdks) and thereby help to control progression from one stage of the cycle to the next (e.g. p34^{cdc2} /cyclin B regulates the G_2 to M transition in all eukaryotes). All the following examples are from *Saccharomyces cerevisiae*: (1) G_1/S-specific cyclin Cln1; this is essential for control of the cell cycle at the G_1/S (START) transition; it interacts with the Cdc28 protein kinase to form S-phase promoting factor (**SPF**). (2) G_1/S-specific cyclin Cln2; this has an overlapping function with Cln1. Cln1 and Cln2 mRNAs fluctuate in the cell cycle. (3) G_2/mitotic-specific cyclin C1B1; this interacts with the Cdc2 protein kinase to form MPF. G_2/M cyclins accumulate steadily during G_2 and are abruptly destroyed at mitosis. G_2/mitotic-specific cyclins C1B2–4 are similar. (4) S-phase entry cyclins C1B5 and 6; these are maximally expressed just before the S-phase of the cell cycle. Animal cells have ≈10 cyclins, which dimerize with ≈8 Cdks. Cyclins C, D, and E function in G_1 phase of the cell cycle; cyclins A and B function in S and G_2/M phases; and cyclin H–Cdk7 is Cdk-activated kinase (CAK), also a component of the transcription factor TFIIH (*see* **TFII**). The cyclins contain a homologous nine-residue sequence near the N-terminus. This motif is called the **cyclin box**, or **destruction box**. It is recognized by a destruction box-recognizing protein, which targets cyclins to ubiquitination and proteosomal degradation. *See also* **cdc gene**, **cyclin regulatory protein**.

cyclin-dependent protein kinase Cdk; a protein kinase that is only active when complexed with a regulatory protein, a **cyclin**. Different Cdk–cyclin complexes are thought to trigger different steps in the cell-division cycle by phosphorylating specific target proteins. *See also* **cyclin regulatory protein**.

cyclin regulatory protein any protein involved in the regulation of **cyclin** gene expression. An example from *Saccharomyces cerevisiae* is Cdc68. This plays a role in general transcription, with both positive and negative effects on gene expression; it is required for the appropriate synthesis during heat shock, and for continued expression of cyclin genes. A further example, also from yeast, is the Ser/Thr protein kinase Cdc28 (*see* ***cdc* gene**).

cyclitol any cycloalkane containing one hydroxyl group on each of three or more ring atoms. Notable members are the **inositols** and their derivatives.

cyclo+ *or (before a vowel)* **cycl+** *comb. form* indicating a circle or ring, especially one in a cyclic organic chemical compound.

cycloartenol the first triterpene intermediate in the biosynthesis of sterols in photosynthetic tissues. It is formed from (*S*)-squalene-2,3-epoxide by a cyclization reaction catalysed by cycloartenol synthase, EC 5.4.99.8. The corresponding intermediate in animal tissues is **lanosterol**.



cyclobutadipyrimidine a type of **pyrimidine dimer** formed within a DNA strand between neighbouring pyrimidine residues.

cyclobuxine a steroidal alkaloid extracted from *Buxus microphylla*. The extracts are used as folk remedies for malaria and venereal diseases. It protects the heart from ischemia and reperfusion damage by inhibiting the release of ATP metabolites during reperfusion.



cyclobuxine D

cyclodeaminase *an informal name for* **formiminotetrahydrofolate** cyclodeaminase.

cyclodepsipeptide *see* **depsipeptide**.

cyclodextrin any of a group of cyclic nonreducing **dextrins** formed from starch or glycogen by the extracellular enzyme cyclomaltodextrin glucanotransferase (EC 2.4.1.19), produced by *Bacillus macerans*. They consist of cyclic polymers containing six, seven, or eight α-(1,4)-linked D-glucose residues. These were formerly known, respectively, as Schardinger α-, β-, or γ-dextrins, or α-, β-, or γ-cyclodextrins, but now are more correctly named cyclomaltohexaose, cyclomaltoheptaose, or cyclomaltooctaose. Cyclodextrins have a toroidal molecular structure enclosing a hydrophobic cavity, thereby permitting the formation of inclusion complexes with a wide variety of molecules.

cyclofenil bis-(*p*-acetoxyphenyl)cyclohexylidenemethane; an agent that prevents feedback inhibition of ovulation by inhibiting the binding of estrogen in the brain. The resulting increased secretion of gonadotropin-releasing hormone, gonadotropins, and estrogen promotes ovulation.

cycloheximide *or* **actidione** 3-[2(3,5-dimethyl-2-oxocyclohexyl)-2-hydroxyethyl]glutarimide; an antibiotic produced by some *Streptomyces* spp. It interferes with protein synthesis in eukaryotes by inhibiting peptidyltransferase activity of the 60S ribosomal subunit.



cyclohydrolase *an informal name for* the enzyme **methenyltetrahydrofolate cyclohydrolase**, EC 3.5.4.9.

cyclo-ligase any **ligase** enzyme of the sub-subclass EC 6.3.3 that catalyses the formation of a heterocyclic ring containing a C–N bond; e.g. dethiobiotin synthase, EC 6.3.3.3.

cyclomaltoheptaose *see* **cyclodextrin**.

cyclomaltohexaose *see* **cyclodextrin**.

cyclomaltooctaose *see* **cyclodextrin**.

cyclooxygenase *an alternative (informal) name for* **prostaglandin–endoperoxide synthase**.

cyclooxygenation the process that introduces one molecule of dioxygen at C-9 and a second dioxygen at C-15 of a molecule of arachidonic acid, accompanied by formation of a bond between C-8 and C-12 and an endoperoxide bridge across C-9 and C-11.

cyclophilin a protein of the immunophilin class that binds the immunosuppressant **cyclosporin A**. Cyclophilin possesses **peptidylprolyl isomerase** activity. Under physiological conditions it may have a role in the entry of proteins into, and protein folding within, the mitochondrial matrix. Cyclophilin binds to all six peroxiredoxins found in mammalian cells.

cyclophorase originally, a supposed integrated complex of enzymes that carries out the tricarboxylic-acid cycle, fatty-acid oxidation, oxidative phosphorylation, and terminal electron transport. This system was identified later with **mitochondria**. The cyclophorase complex and the mitochondria are thus the functional and structural sides of the same unit.

cyclophosphamide *N*,*N*-bis(2-chloroethyl)tetrahydro-2*H*-1,3,2-oxazaphosphorin-2-amine 2-oxide; an alkylating agent that is metabolized by the liver cytochrome P450 system to 4-hydroxycyclophosphamide, which is in equilibrium with aldophosphamide. These are transported to tissues, which convert them to the cytotoxic agent, phosphoramine mustard, and acrolein. Cyclophosphamide is useful as an immunosuppressant. *See also* **chlorambucil**.



cyclopropylamine *see* **monoamine oxidase inhibitors**.

D-cycloserine D-4-amino-3-isoxazolidinone; a tuberculostatic antibiotic found in cultures of *Streptomyces orchidaceus*. It is a potent inhibitor of alanine racemase (EC 5.1.1.1) and D-alanine–D-alanine ligase (EC 6.3.2.4; alanylalanine synthetase), two enzymes concerned in the biosynthesis of bacterial cell wall peptidoglycan.



cyclosporin A *or* **ciclosporin** A a cyclic undecapeptide isolated from the fungi *Cylindrocarpon lucidum* and *Tolypocladium inflatum* (formerly *Trichoderma polysporum*). It is a potent immunosuppressive drug that prevents the rejection of allografts, and is used extensively in human transplant operations. Its main target appears to be the T lymphocyte: it contains D-alanine and several nonprotein amino acids, and blocks a calcium-dependent signal from the **T-cell receptor** that normally leads to T-cell activation. When bound to **cyclophilin**, cyclosporin A binds and inactivates the key signalling intermediate **calcineurin**.

cyclosporin synthetase a multimodular enzyme protein (1.7 MDa, 15 281 amino acids) that catalyses the synthesis of cyclosporin. Each module is 1000–1200 residues long. This is an example of nonribosomal peptide synthesis in which the composition and sequence of the peptide product is determined by the sequence and specificity of the catalytic modules in the protein.

cyclotide any of a large group of circular polypeptides of plants. They contain $\approx$30 residues, of which 6 are conserved cysteines, and are derived from larger precursor proteins. They have diverse actions. Examples (from Rubiaceae family) include: circulins A and B, which are active against HIV; cyclopsychotride A, which inhibits neurotensin; and kalata B, which is uterotonic.

cyclotron a machine used to accelerate charged particles of atomic magnitudes to energies of the order of 25 MeV. The particles move in spiral paths under the influence of a uniform vertical magnetic field and are accelerated by a constant frequency electric field.

Cyd *symbol for* a residue of the ribonucleoside **cytidine** (alternative to C).

Cyd*P* *symbol for* cytidine phosphate (*see* **cytidine phosphate**).

Cyd2′*P* *symbol for* cytidine 2′-phosphate (*see* **cytidine phosphate**).

Cyd-2′,3′-*P* *symbol for* cytidine 2′,3′-phosphate (*see* **cytidine phosphate**).

Cyd3′*P* *symbol for* cytidine 3′-phosphate (*see* **cytidine phosphate**).

Cyd-3′,5′-*P* *symbol for* cytidine 3′,5′-phosphate (*see* **cytidine phosphate**).

Cyd5′*P* *symbol for* cytidine 5′-phosphate (*see* **cytidine phosphate**).

Cyd5′*PP* *symbol for* cytidine 5′-diphosphate (*see* **cytidine phosphate**).

Cyd5′*PPP* *symbol for* cytidine 5′-triphosphate (*see* **cytidine phosphate**).

Cy3 dye *a proprietary name for* an orange fluorescent cyanine dye having $\lambda_{\max}$ excitation 550 nm and $\lambda_{\max}$ emission 570 nm. It is used to label dideoxyribonucleotides in automated DNA sequencing and as a label for proteins.

Cy5 dye *a proprietary name for* a sulfoindocyanine dye having $\lambda_{\max}$ excitation 649 nm and $\lambda_{\max}$ emission 670 nm, and uses similar to those of **Cy3 dye**.

c*-yes** *see* ***YES.

D-cymarose 2,6-dideoxy-3-*O*-methyl-*ribo*-hexose; the D enantiomer is a constituent of some **cardiac glycosides**.

CYP19 *an alternative name for* **aromatase**.

cyproterone 6-chloro-6-dehydro-17α-hydroxy-1,2α-methylene-progesterone; a progesterone derivative with anti-androgen activity through partial agonist activity at androgen receptors. It inhibits the secretion of gonadotropins and spermatogenesis in humans.

Cyr61 a growth factor binding protein expressed from G_0/G_1 to mid-G_1 of the cell cycle. It is expressed in high amounts in lung. *Compare* **connective tissue growth factor**.

Cys *symbol for* a residue of the α-amino acid L-cysteine. When written



$$\overset{|}{\mathrm{Cys}} \quad \text{or} \quad \underset{|}{\mathrm{Cys}},$$

it represents L-half-cystine.

cyst 1 any saclike structure, generally of a pathological nature, comprising a central cavity lined with epithelium and containing fluid or semisolid material. **2** the capsule enclosing a dormant larva or spore. **—cystic** *adj.*

cystamine β,β'-diaminodiethyl disulfide; 2,2′-dithiobis(ethylamine); 2,2′-dithiobisethanamine; $H_2N–CH_2–CH_2–S–S–CH_2–$ $CH_2–NH_2$; the decarboxylation product of cystine and an oxidation product of **cysteamine**.

cystate 1 the **cystine** anion; the dianion, $^-OOC–CH(NH_2)–CH_2–S–S–CH_2-CH(NH_2)–COO^-$, derived from cystine. **2** any salt containing the cystine anion. **3** any ester of cystine. *Distinguish from* **cysteate** and **cysteinate**.

cystathionine *trivial name for* *S*-(β-amino-β-carboxyethyl)homocysteine; (*R**)-2-amino-4-[(*S**)-2-amino-2-carboxyethylthio]butanoic acid; $HOOC–CH(NH_2)–CH_2–S–CH_2–CH_2–CH(NH_2)–COOH$; a di($\alpha$-amino acid) and a mixed thioether with two chiral centres. L-Cystathionine



$$(\textit{symbol}\text{: } \underset{\mathrm{Hcy}}{\overset{\mathrm{Ala}}{|}}),$$

S-(L-alanin-3-yl)-L-homocysteine; (*S*)-2-amino-4-[(*R*)-2-amino-2-carboxyethylthio)butanoic acid – in which both moieties are in the L-configuration – does not occur in proteins but is an intermediate in the transfer of the sulfur atom from methionine, via homocysteine, to cysteine in mammals. (*Note*: The pair of (*R**,*R**)-enantiomers, in which one moiety is in the D-configuration and the other in the L-configuration, is sometimes known as **allocystathionine**.)



cystathionine γ-cystathionase *see* **cystathionine** γ **-lyase**.

cystathionine γ-lyase EC 4.4.1.1; *systematic name*: L-cystathionine cysteine-lyase (deaminating); *other names*: homoserine deaminase; homoserine dehydratase; γ-cystathionase; cystine desulfhydrase; cysteine desulfhydrase; cystathionase; a multifunctional pyridoxal-phosphate enzyme that catalyses the formation of L-cysteine with release of 2-oxobutanoate and ammonium ion from L-cystathionine and water. It also acts on homoserine and cysteine to remove NH_3, forming oxobutanoate from homoserine or pyruvate and H_2S from cysteine. The enzyme carries out the final reaction in the pathway for the synthesis of cysteine from methionine.

cystathionine β-synthase EC 4.2.1.22; *systematic name*: L-serine hydro-lyase (adding homocysteine); *other names:* serine sulfhydrase; β-thionase; methylcysteine synthase. An enzyme that catalyses the reaction between L-serine and L-homocysteine to form cystathionine and water. This is the first step in the synthesis of cysteine from serine. Pyridoxal-phosphate is a cofactor. *See* **homocystinemia**.

cystathionine γ-synthase EC 4.2.99.9; *recommended name: O*-succinylhomoserine (thiol)-lyase. An enzyme in the pathway for the synthesis of methionine in plants and bacteria. It catalyses the formation of cystathionine from *O*-succinyl-L-homoserine and L-cysteine to form succinate. Pyridoxal-phosphate is a cofactor. The enzyme can utilize hydrogen sulfide or methanethiol as a thiol substrate.

cystathioninuria the excessive excretion of L-cystathionine in the urine in humans. It is usually benign, pyridoxine-responsive, and caused by an inherited deficiency of cystathionine γ-lyase.

cystatin any of a group of proteins, present in tissues and body fluids, that inhibit cysteine proteases. The cystatins constitute a single evolutionary superfamily, and are classified into three different families. Family 1 proteins contain ~100 amino-acid residues (M_r 11 000–12 000), and lack disulfide bonds. Family 2 proteins have ~120 residues (M_r 13 000–14 000), with two intrachain disulfide bonds. Family 3 proteins (*also called* **kininogens**) contain three cystatin-like domains, each of which has two disulfide bonds at positions homologous to those in family 2. Examples: cystatin A (*also called* stefin A); type 2 cystatin C (*also called* **neuroendocrine basic polypeptide** *or* **post-γ-globulin**); in humans, this is expressed in highest levels in the epididymis, vas deferens, brain, thymus, and ovary, and is found in sera from patients with Icelandic cerebrovascular type amyloidosis, and related diseases.

cysteamine thioethanolamine; β-mercaptoethylamine; 2-aminoethanethiol; $HS–CH_2–CH_2–NH_2$; the decarboxylation product of cysteine. It readily oxidizes in air to **cystamine**. Pantetheine, a component of coenzyme A, is the amide formed between cysteamine and pantothenic acid.

cysteate 1 *the common name for* cysteate(1–); cysteic-acid monoanion; hydrogen cysteate. (*Note:* in theory, the term denotes any ion, or mixture of ions, formed from **cysteic acid**, and having a net charge of minus one, although the species $^-O_3S–CH_2–CH(NH_3^+)–COO^-$ generally predominates in practice.) **2** *the systematic name for* cysteate(2–); cysteate-acid dianion. **3** any salt containing an anion of cysteic acid. **4** any ester of cysteic acid. *Compare* **cystate**, **cysteinate**.

cysteic acid *the trivial name for* 3-sulfoalanine; a-amino-β-sulfopropionic acid; 2-amino-3-sulfopropanoic acid; $HO_3S–CH_2–CH(NH_2)–COOH$; a chiral a-amino acid, and an oxidation product of cysteine or cystine. Residues of L-cysteic acid (*symbol*: Cya), (*R*)-2-amino-3-sulfopropanoic acid, do not occur normally in proteins, although they are found in wool from the outer part of the fleece of sheep, following exposure to sunlight. They are commonly encountered during sequencing of peptides and proteins as the end product of oxidative cleavage of the disulfide bonds of cystine residues and concomitant oxidation of cysteine residues.



cysteinate 1 cysteinate(1–); cysteine monoanion; the anion, $HS–CH_2–CH(NH_2)–COO^-$, derived from **cysteine**. **2** cysteinate(2–); cysteine dianion; the anion, $^-S–CH_2–CH(NH_2)–COO^-$, derived from cysteine. **3** any salt containing an anion of cysteine. **4** any ester of cysteine. *Compare* **cystate**, **cysteate**.

cysteine *the trivial name for* β-mercaptoalanine; α-amino-β-thiolpropionic acid, 2-amino-3-mercaptopropanoic acid; $HS–CH_2–CH(NH_2)–COOH$; a chiral α-amino acid. In neutral or alkaline solution it is readily oxidized by air to **cystine**. L-Cysteine (*symbol*: C *or* Cys), (*R*)-2-amino-3-mercaptopropanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: UGC or UGU. In mammals it is a nonessential dietary amino acid and is glucogenic. D-Cysteine (*symbol*: D-Cys *or* DCys), (*S*)-2-amino-3-mercaptopropanoic acid, occurs naturally in firefly **luciferin**. (*Note*: application of the **sequence rule** to the enantiomers of cysteine, results in their stereochemical designation as either *R* or *S* being the converse of that possessed by most chiral α-amino acids found in proteins.)



L-cysteine

cysteine (acid) the protonated form of a **cysteine** residue, i.e. with an undissociated thiol group.

cysteine desulfhydrase *see* **cystathionine γ-lyase**.

cysteine endopeptidase *or (formerly)* **thiol proteinase** any enzyme of the sub-subclass EC 3.4.22, which consists of proteinases characterized by having a cysteine residue at the active centre and by being irreversibly inhibited by sulfhydryl reagents such as iodoacetate. The group includes cathepsins B, H, and L. There are at least three superfamilies that are unrelated in structure. These are (1) papain-like proteases; (2) caspase-hemoglobinase proteases; and (3) adenovirus-type proteases. *See* **cathepsin B**, **cathepsin H**, **cathepsin L**, **clostripain**, **ficain**, **papain**. *See also* **apoptosis**.

cysteine-rich secretory protein *see* **CRISP**.

cysteine-type carboxypeptidase EC 3.4.18.1; *other names*: lysosomal carboxypeptidase B; cathepsin B_2; cathepsin IV; acid carboxypeptidase; an enzyme that catalyses the liberation of a C-terminal amino-acid residue from a protein. It is an enzyme with broad specificity, but lacks action on C-terminal proline.

cysteinyl the acyl group, $HS–CH_2–CH(NH_2)–CO–$, derived from **cysteine**. (*Note:* although this name is formed atypically, its use is recommended to avoid confusion with **cysteyl**.) *Compare* **cystyl**, **half-cystyl**.

cystein-S-yl the alkylthio group, $HOOC–CH(NH_2)–CH_2–S–$, derived from **cysteine**.

cysteyl 1 the acyl group, $HO_3S–CH_2–CH(NH_2)–CO–$, derived from **cysteic acid**. **2** *an alternative name for* **cysteinyl** (use now discouraged).

cystic fibrosis a heterogeneous disorder affecting all exocrine glands and probably other tissues. It is the most common lethal genetic disorder of Caucasians, but is also found in other races. There is an abnormality in the secretions of the exocrine glands, which have higher than normal concentrations of Na^+, Cl^-, nucleotides, Ca^{2+}, etc.; a number of abnormal protein factors have been described in the exocrine glands of patients. It is due to mutation in the gene for **cystic fibrosis transmembrane conductance regulator**.

cystic fibrosis transmembrane conductance regulator *abbr.:* CFTR; a 168 kDa integral membrane protein encoded by the cystic fibrosis gene, and with structural similarity to membrane-associated ATP-dependent transporter protein (*see* **ABC transporters**), one of a family of proteins involved in the active transport of ions and small molecules across membranes. CFTR belongs to the subfamily. The CFTR protein appears to be involved in the functioning of a chloride ion channel. A mutation in this protein has been identified as being responsible for 70% of the cystic fibrosis chromosomes in Northern Europe.

cystine *the trivial name for* dicysteine; *β,β′*-dithiodialanine; *a,a′*-diamino-*β,β′*-dithiobis(propionic acid); (*R**,*R*'*)-3,3′-dithiobis(2-aminopropanoic acid);

$$HOOC–CH(NH_2)–CH_2–S–S–CH_2–CH(NH_2)–COOH;$$

a di(α-amino acid) with two chiral centres, formed by the oxidation of cystein. L-Cysteine,

$$[\textit{symbol}: \begin{array}{c}\text{Cys}\\|\\\text{Cys}\end{array}],$$

(*R*,*R*′)-3,3′-dithiobis(2-aminopropanoic acid), is found in peptide linkage in proteins, having been formed by post-translational oxidation of cysteine. In mammals it is a nonessential dietary amino acid and is glucogenic. As it is somewhat insoluble in neutral aqueous solutions, it sometimes forms urinary stones. *meso*-Cystine, (*R*,*S*′)-3,3′-dithiobis(2-aminopropanoic acid), is the internally compensated achiral diastereoisomer, in which D- and L-half-molecules are combined. *See also* note at **cysteine**.



L-cystine

cystine desulfhydrase *see* **cystathionine γ-lyase**.

cystine knot a structure, found in some proteins, that results from the formation of three disulfide bonds between six cysteine residues, positioned in such a way as to form a knot-like topology. It was originally found in transforming growth factor-ß and platelet-derived growth factor.

cystinosin a membrane protein of lysosomes that is encoded by the gene for cystinosis. It consists of 367 amino acids, 7 transmembrane segments, and 8 potential glycosylation sites.

cystinosis a genetic disease caused by mutation of the gene for cystinosin, a lysosomal cystine transport protein (gene locus 17p13). Cystine crystals are stored in lysosomes of many tissues including kidney, eyes, liver, muscles, pancreas, brain, and white blood cells. Without treatment the result is end-stage renal failure before the age of 10 years. —**cystinotic** *adj.*

cystinuria a disorder of cystine and diamino acid (arginine, lysine, and ornithine) transport in humans affecting the epithelial cells of the renal tubules and the gastrointestinal tract. It is characterized by the formation of cystine stones in the urinary tract and elevated levels of cystine and diamino acids in the urine. **Cystinuria type I** is a fully autosomal recessive disorder in which heterozygotes have normal urinary amino-acid excretion. It is caused by mutations in the gene (*SLC3A1*) for a four-transmembrane segment protein of 685 amino acids, called rBAT. **Cystinuria non-type I** (i.e. types II and III) is an incompletely autosomal recessive disorder in which heterozygotes have abnormal urinary excretion of cystine and basic amino acids. It is caused by mutation in the gene (*SLC7A9*) for a 12-transmembrane segment protein called bAT. Both genes are expressed in kidney and small intestine.

cystyl the diacyl group, $–OC–CH(NH_2)–CH_2–S–S–CH_2–CH(NH_2)–CO–$, derived from **cystine**. *Compare* **cysteinyl**, **half-cystyl**.

Cyt *symbol for* a residue of the pyrimidine base cytosine (alternative to C).

cytarabine *β*-cytosine arabinoside; 1-*β*-D-arabinofuranosylcytosine; *abbr.*: ara-C; a cytotoxic drug used as an antineoplastic and antiviral agent. It is effective in the treatment of acute myeloblastic leukemia. It is converted metabolically to 1-*β*-D-arabinofuranosylcytidine 5′-triphosphate (*abbr.*: *ara*-CTP), a potent inhibitor of DNA synthesis.



+cyte *comb. form* indicating a **cell** (def. 1).

cytidine *symbol*: C *or* Cyd; cytosine riboside; 1-*β*-D-ribofuranosyl cytosine; a widely distributed **nucleoside**.



cytidine 2′,3′-(cyclic)phosphate *see* **cytidine phosphate**.

cytidine 3′,5′-(cyclic)phosphate *or* **cytidine 3′,5′-cyclophosphate** *see* **cytidine phosphate**.

cytidine deaminase EC 3.5.4.5; *systematic name*: cytidine aminohydrolase. An enzyme that catalyses the reaction:

cytidine + H_2O = uridine + NH_3.

It is a homodimer, with bound Zn^{2+}. Specificity is poor, and deoxycytidine is also a substrate.

cytidine 5′-diphosphate *symbol*: Cyd5′*PP or* ppC; *the recommended name for* cytidine diphosphate (*abbr.*: CDP), 5′-diphosphocytidine, 5′-cytidylyl phosphate, cytidine 5′-(trihydrogen diphosphate), a universally distributed nucleotide that occurs both in the free state and as a component of certain **nucleotide coenzymes**. It is a metabolic precursor of cytidine 5′-triphosphate, CTP. It is a product of nucleoside triphosphatase, EC 3.6.1.15, and is also formed in a few cases when CTP is involved in phosphotransferase reactions (e.g. dolichol kinase, EC 2.7.1.108); it is converted to deoxycytidine 5′-diphosphate by **ribonucleoside-diphosphate reductase** (EC 1.17.4.1).

cytidine(5′)diphosphocholine *or* **cytidine diphosphate choline** an intermediate in phospholipid synthesis, especially of phosphatidylcholines and sphingomyelins.



cytidine(5′)diphosphoethanolamine *or* **cytidine diphosphate ethanolamine** an intermediate in the synthesis of phosphatidylethanolamines.



cytidine monophosphate *abbr.*: CMP; an alternative name for any cytidine phosphate, but in particular for cytidine 5′-phosphate, especially when its distinction from cytidine (5′-)diphosphate and cytidine (5′-)triphosphate requires emphasis.

cytidine phosphate *symbol*: Cyd*P*; cytidine monophosphate (*abbr.*: CMP); any phosphoric monoester or diester of cytidine. There are three monoesters: cytidine 2′-phosphate, cytidine 3′-phosphate, and **cytidine 5′-phosphate**, and two possible diesters: cytidine 2′,3′-phosphate and cytidine 3′,5′-phosphate, although cytidine 5′-phosphate is the ester commonly denoted (the locant being omitted if no ambiguity may arise). Cytidine 2′,3′-phosphate (*symbol*: Cyd-2′,3′-*P*), also named cytidine 2′,3′-(cyclic)phosphate *or* cyclic cytidine 2′,3′-monophosphate (*abbr.*: 2′,3′-cyclic CMP), is formed as an intermediate during the alkaline hydrolysis of ribonucleic acid. This diester then readily hydrolyses to a mixture of the two monoesters cytidine 2′-phosphate (*symbol*: Cyd2′*P*), *also named* cytidine 2′-monophosphate (*abbr.*: 2′CMP) *or* 2′-cytidylic acid *or* cytidylic acid a, and cytidine 3′-phosphate (*symbol*: Cyd3′*P*), also named cytidine 3′-monophosphate (*abbr.*: 3′CMP) *or* 3′-cytidylic acid *or* cytidylic acid b. Cytidine 3′,5′-phosphate (*symbol*: Cyd-3′,5′-*P*), also named cytidine 3′,5′-(cyclic)phosphate *or* cyclic cytidine 3′,5′-monophosphate (*abbr.*: 3′,5′-cyclic CMP), is a product of cytidylate cyclase, EC 4.6.1.6.

cytidine 2′-phosphate *see* **cytidine phosphate**.

cytidine 2′3′-phosphate *see* **cytidine phosphate**.

cytidine 3′-phosphate *see* **cytidine phosphate**.

cytidine 5′-phosphate *or* **5′-cytidylic acid** *or* **5′-phosphocytidine** *or* **5′-*O*-phosphonocytidine** *symbol*: Cyd5′*P*; *alternative recommended names for* cytidine 5′-monophosphate (*abbr.*: 5′CMP), cytidine 5′-(dihydrogen phosphate), cytidine (mono)-ribonucleotide. (The locant is commonly omitted if there is no ambiguity as to the position of phosphorylation). It is formed by pyrophosphatase-catalysed cleavage of (inorganic) diphosphate from CTP, and also as a product of a variety of reactions, e.g. that in which phosphatidylcholine is formed from CDPcholine and diacylglycerol (diacylglycerol cholinephosphotransferase, EC 2.7.8.2).

cytidine 5′-triphosphate *symbol*: Cyd5′*PPP or* pppC; *recommended name for* cytidine triphosphate (*abbr.*: CTP), 5′-triphosphocytidine, 5′-cytidylyl diphosphate, cytidine 5′-(tetrahydrogen triphosphate), an important coenzyme. It is formed by **CTP synthase**. It participates as coenzyme in reactions in which a cytidylyl group is transferred, e.g. in lipid metabolism, to choline phosphate (EC 2.7.7.15, to form CDPcholine) and similar reactions, or in carbohydrate metabolism to form CDPglucose (EC 2.7.7.33), or in the phosphotransferase dolichol kinase (EC 2.7.1.108).



cytidyl any chemical group formed by the loss of a 2′-, a 3′-, or a 5′-hydroxyl group from the ribose moiety of cytidine. *Compare* **cytidylyl**.

cytidylate **1** either the mono- or the di-(phosphoric) anion of **cytidylic acid**. **2** any mixture of cytidylic acid and its anions. **3** any salt or ester of cytidylic acid.

cytidylic acid *the trivial name for* any phosphoric monoester of cytidine. The position of the phosphoric residue on the ribose moiety of a given ester may be specified by a prefixed locant. *See* **cytidine phosphate**. However, 5′-cytidylic acid is the ester commonly denoted, its locant usually being omitted if no ambiguity may arise. 5′-

cytidylic acid is also an alternative recommended name for **cytidine 5′-phosphate**.

cytidylyl the cytidine[mono]phospho group, the acyl group derived from **cytidylic acid**. *Compare* **cytidyl**.

cytidylylation the process of introducing a cytidylyl group into a substance.

cyto+ *comb. form* indicating a **cell** (def. 1).

cytochalasin any of a group of structurally related fungal metabolites (designated A, B, C, D, E, F, etc.) that share a number of unusual and characteristic effects on cultured mammalian cells. The most notable are inhibition of cytoplasmic cleavage following nuclear division, induction of nuclear extrusion, and inhibition of cell motility. They bind to the growing plus ends of actin filaments, preventing further addition of actin molecules, and thus affect functions that involve assembly and disassembly of actin filaments. The basic structure is a benzyl-substituted hydroisoindolone nucleus to which is fused a small macrolide-like ring. [From Greek *cytos*, cell; *chalasis*, relaxation.]

cytochemical bioassay a technique for the assay of various polypeptide hormones, based on function rather than structure. It involves measuring changes in the biochemical activity of a specific target cell, appropriate to the physiological effect of the hormone in question, by quantitative cytochemical methods. It is claimed to be more sensitive and more specific than equivalent radioimmunoassays.

cytochemistry the chemistry of living cells, especially the cellular localization of biochemical substances and processes; microscopical biochemistry. —**cytochemical** *adj.*

cytochrome any member of a class of hemoproteins whose characteristic mode of action involves the transfer of electrons in association with a reversible change in oxidation state (between Fe(II) and Fe(III), and sometimes Fe(IV)) of the heme iron. The name embraces all intracellular hemoproteins except hemoglobin, myoglobin, peroxidases, catalase, tryptophan 2,3-dioxygenase, nitrite and sulfite reductases, and heme-thiolate proteins. There are four major established subclasses; well-established members of each subclass are generally distinguished by consecutive numerical subscripts; remaining members are designated by a suffixed number based upon the wavelength (in nanometres) of the α-band (e.g. cytochrome c_1, cytochrome c_{555}); *see* **cytochrome absorption bands**. (1) In **cytochromes *a*** the heme prosthetic group contains a formyl side-chain, i.e. heme *a*. (2) **Cytochromes *b*** contain protoheme or a related heme (without a formyl group) as prosthetic group, not covalently bound to the protein. The group includes **cytochrome *o***, **cytochrome P-450**, and **helicorubin**, as well as **ubiquinol-cytochrome *c* reductase**, **cytochrome *b***, **cytochrome b_2**, **cytochrome b_5**, **cytochrome b_{245}**, **cytochrome b_{599}**, **cytochrome b_6**, and **cytochrome b_6–*f* complex.** (3) In **cytochromes *c*** there are covalent linkages, not necessarily thioether linkages, between the heme side-chains and the protein (*see also* **cytochrome *c***, **cytochrome c_1**). (4) **Cytochromes *d*** contain a tetrapyrrollic chelate of iron as prosthetic group, in which the degree of conjugation of double bonds is less than in porphyrin. *See also* **cytochrome *f***.

cytochrome absorption bands three principal absorption bands in the absorption spectrum of many ferrohemoproteins, being the α-band, β-band, and γ-band (*or* **Soret band**), resulting from the absorption of radiation by the heme groups. They are useful in the characterization and study of these proteins. Characteristic absorption maxima for cytochromes *a*, *b*, *c*, and c_1 are for the α-band: 600, 563, 550, and 554 nm respectively; for the β-band: (none for *a*) 532 (*b*), 531 (*c*), and 524 (c_1) nm; and for the γ-band 439, 429, 415, and 418 nm.

cytochrome *b* a component of the eukaryotic mitochondrial **respiratory chain** complex III. It is an integral membrane protein that contains eight transmembrane segments and two heme groups, b_{562} and b_{566}. It is encoded in mitochondrial DNA. Several mutations in it result in mitochondrial myopathy or cardiomyopathy.

cytochrome b_2 EC 1.1.2.3; an enzyme (*recommended name*: L-lactate dehydrogenase (cytochrome)) that catalyses the oxidation of L-lactate by 2 ferricytochrome *c* to form pyruvate and 2 ferrocytochrome *c*. Flavin mononucleotide (FMN) and protoheme IX are cofactors. Cytochrome b_2, is a mitochondrial intermembrane-space protein induced by lactate during respiratory adaptation (in yeast).

cytochrome b_5 an electron carrier for several oxygenases, present in animal microsomes and in erythrocytes. It is reduced by **cytochrome b_5 reductase**. Two forms are synthesized by alternative splicing.

cytochrome b_5 reductase EC 1.6.2.2; a flavoprotein (FAD) enzyme that catalyses the reaction:

$$\text{NADH} + 2\text{ ferricytochrome } b_5 = \text{NAD}^+ + 2\text{ ferrocytochrome } b_5.$$

It is cytosolic in erythrocytes and a myristoylated peripheral membrane protein of 275 amino acids in hepatocytes. Point mutations in the gene cause hereditary enzymopenic methemoglobinemia.

cytochrome b_6 *or* **cytochrome b_{563}** a *b*-type cytochrome that contains two heme moieties and forms part of cytochrome b_6f complex functioning between photosystems II and I of photosynthesis.

cytochrome b_6f complex a complex, present in thylakoid membranes of chloroplasts, that consists of cytochrome b_6, cytochrome *f*, and the **Rieske protein**. It transmits electrons between photosystems II and I of photosynthesis.

cytochrome b_{245} *or* **cytochrome b_{558}** an integral membrane component of the phagocyte NADPH oxidase complex. The protein is a dimer (human) of α (the glycoprotein gp91-phox, which contains two heme and one FAD moieties) and β (the protein p22-phox) subunits. Deficiency or structural variation in the α subunit causes X-linked chronic granulomatous disease, while similar defects in the β subunit cause an autosomal recessive form of the same disease.

cytochrome b_{599} a cytochrome of photosystem II of photosynthesis. It exists as a dimer of α and β chains. *See* **photosystem**.

cytochrome bd a terminal quinol oxidase in bacteria such as *E. coli*, containing heme and copper.

cytochrome bo a terminal quinol oxidase in bacteria such as *E. coli*, containing heme and copper.

cytochrome *c* a soluble protein of the intermembrane space of mitochondria that associates with the inner mitochondrial membrane and functions to transfer electrons between **respiratory chain** complexes III and IV. The sequence from many (>100) species has been determined. About 26 residues are completely invariant, especially those with side chains packing against the heme. The apoprotein is nucleus-encoded, synthesized on free ribosomes, and transported into the mitochondrion, for which the action of heme lyase (holocytochrome-*c* synthase) is essential. It is released into the cytosol after induction of apoptosis, binds to Apaf1, and activates procaspase 9.

cytochrome c_1 an inner mitochondrial membrane protein component of **respiratory chain** complex III. Comprising 241 amino acids (bovine heart), its C-terminal globular heme-containing domain extends into the intermembrane space, while its C-terminal region forms a transmembrane segment that anchors it into the inner mitochondrial membrane. It transfers electrons directly to cytochrome *c*.

cytochrome *c* oxidase *or* **cytochrome oxidase** *or* **cytochrome aa_3** EC 1.9.3.1; an oxidoreductase, containing heme and copper, that catalyses the oxidation of cytochrome *c* by dioxygen with the production of water. The reaction is:

$$4\text{ ferrocytochrome } c + O_2 = 4\text{ ferricytochrome } c + 2\ H_2O.$$

It is an integral mitochondrial membrane protein comprising a complex of 13 subunits; subunits I, II, and III are encoded in the mitochondrion and the remaining 10 are nucleus encoded. Electrons originating in cytochrome *c* are transferred via heme *a* and Cu_A to the binuclear centre formed by heme a_3 and Cu_B. Subunit I binds the two hemes and Cu_B. Subunit II binds Cu_A and cytochrome *c*.

cytochrome *c* reductase *see* **NADH dehydrogenase**.

cytochrome *f* *or* **cytochrome b_{552}** a cytochrome, designated after the Latin *frons* (leaf), that occurs in high concentration in leaves (up to 25% of the concentration of chlorophyll). It is a typical *c*-type cytochrome, and a component of the **cytochrome b_6 *f* complex** of thylakoid membrane, transferring electrons from photosystem II to I. *See also* **cytochrome b_6**.

cytochrome *h* a *b*-type cytochrome found in the hepatopancreas of the snail *Helix pomatia*.

cytochrome *m* *an alternative name for* **cytochrome P450**.

cytochrome *o* any *b*-type prokaryotic cytochrome containing protoheme as the prosthetic group that, unlike a typical cytochrome *b*, serves as a terminal electron acceptor (cytochrome oxidase) and is autoxidizable by dioxygen. Use of the term is discouraged.

cytochrome P450 *or (sometimes)* **cytochrome *m*** *abbr*.: (of protein) CYP, (of gene) *CYP*; any *b*-type cytochrome that has a cysteine sulfur atom ligated to the heme iron and that, when reduced, forms carbon monoxide complexes – the latter are pigments with a major absorption peak (Soret band) near 450 nm. These cytochromes are mixed-function oxidase enzymes, including unspecific monooxygenase (EC 1.14.14.1), camphor 5-monooxygenase (EC 1.15.15.1), alkane 1-monooxygenase (EC 1.14.15.3), steroid 11*β*-monooxygenase (EC 1.14.15.4), cholesterol monooxygenase (side-chain-cleaving) (EC 1.14.15.6), prostacyclin synthase (EC 5.3.99.4), and thromboxane synthase (EC 5.3.99.5). They catalyse the reaction:

$$\mathrm{RH + NADPH + H^+ + O_2 = ROH + NADP + H_2O.}$$

This reaction requires a specific cytochrome P450 and cytochrome P450 reductase (which contains FAD and FMN). They occur in most animal cells, mainly in smooth endoplasmic reticulum, and in plants and microorganisms, and their chief function is the monooxygenation of lipophilic substances (RH can be steroid, fatty acid, or xenobiotics), as in the case of cytochrome $\mathrm{P450_{SCC}}$, cholesterol monooxygenase (side-chain-cleaving). In mammalian liver many cytochromes P450 are inducible by drug and other treatment, e.g. the major phenobarbital-inducible cytochrome in rabbit liver microsomes, known as $\mathrm{P450_{LM2}}$.

Over 1000 genes for cytochrome P450 (450–530 amino acids) are known in animals, bacteria, fungi, and plants. They are classed into 27 families, of which 10 are found in all mammals. Each family consists of a group of proteins that exhibit 40% or greater sequence identity, and the family is described by an Arabic number. Within these families, subgroups of proteins having greater than 55% identity are classified into subfamilies, designated by a capital letter, and individual proteins within subfamilies are arbitrarily assigned numbers. Under this nomenclature, $\mathrm{P450_{LM2}}$ is known as CYP2B4, or P4502B4, and the gene as *CYP2B4*. Mutations in CYP21A2 cause congenital adrenal hyperplasia, and in CYP1B1 cause congenital glaucoma.

cytochrome P450 reductase a flavoprotein enzyme (76.5 kDa) that contains one molecule each of FAD and FMN and is homologous to **nitric-oxide synthase**. Its N-terminal region is hydrophobic and keeps the enzyme attached to the endoplasmic reticulum, while the rest of the protein projects into the cytosol. It catalyses transfer of electrons from NADPH, via FAD and FMN, to the heme of **cytochrome P450**, and then on to O_2 to form water during hydroxylation reactions involving lipophilic substrates.

cytocuprein *an alternative name for* Cu/Zn **superoxide dismutase**.

cytoflav(e) *or* **cytoflavin** *a historical name for* the yellow pigment(s) discovered in heart muscle and other tissues. In some cases these pigments were subsequently shown to be riboflavin or a flavin-containing enzyme, especially **yellow enzyme**.

cytofluorometry a technique for the detection, localization, and estimation of substances in or attached to cells, using naturally fluorescent substances or those to which a fluorescent label has been attached. The technique has many applications, including specific labelling of cells using fluorescent antibodies, using fluorescent **probes** to report intracellular events or membrane dynamics, or following the fate of a protein with a fluorescent label after injection into a cell.

cytogenetics the branch of genetics concerned with correlating inherited traits with cytological features, especially the appearance, structure, and behaviour of chromosomes. —**cytogenetic** *adj.*

Cytohelicase *the proprietary name for* a commercial enzyme preparation consisting predominantly of a 1,3-*β*-D-glucanase. It is useful for the isolation of protoplasts because it lyses cell walls.

cytohemolysin any of a family of pore-forming toxins of molar mass of 50–82 kDa, produced, e.g., by *Vibrio cholerae*. Cytohemolysins are classified in the TC system under number 1.C.14.

cytokeratin *see* **keratin**.

cytokine any protein that is released by mammalian cells and has **autocrine** or **paracrine** activity. Cytokines elicit a variety of responses depending on the cytokine and target cell. Their actions include control of cell proliferation and differentiation, regulation of immune responses, hemopoiesis, and inflammatory responses. Cytokines produced by lymphocytes are known also as **lymphokines**; those produced by monocytes are also called **monokines**. Other types of cytokine include **chemokines**, growth factors, **colony stimulating factors**, **transforming growth factors**, **interferons**, and **tumour necrosis factors**. *See also* **angiogenin**, **epidermal growth factor**, **erythropoietin**, **fibroblast growth factor**, **heparin-binding EGF-like growth factor**, **hepatocyte growth factor**, **insulin-like growth factor**, **interleukin**, **leukemia inhibitory factor**, **macrophage inflammatory protein**, **nerve growth factor**, **oncostatin M**, **platelet-derived endothelial growth factor**, **platelet-derived growth factor**, **RANTES**, **stem cell factor**, **vascular endothelial growth factor**.

cytokine-inducible SH2 protein *see* **CIS**.

cytokine receptor any of a group of membrane receptors for a variety of interleukins and some colony stimulating factors. They consist of specific α or β (or both) type I transmembrane proteins that signal through JAK1 and STATs, and a common γ type I transmembrane protein that signals through JAK3 and STAT5.

cytokinesis **1** the changes that occur in the cytoplasm of a cell during nuclear division. **2** the division of the cytoplasm of a parent cell into daughter cells after nuclear division. *Compare* **karyokinesis**.

cytokinin *or* **phytokinin** any of a group of plant hormones that have a stimulatory effect on the division of plant cells and a retarding effect on leaf senescence. They are purine derivatives. The receptor is a histidine kinase that targets ARR1 (*Arabidopsis* response regulator 1), a transcription factor that binds DNA.

cytolemma *an alternative name for* **cell membrane**.

cytology the branch of science dealing with the origin, structure, function, biochemistry, and life history of cells. It includes the (microscopic) examination of cells, particularly in the detection and diagnosis of disease.

cytolysin any protein, especially an antibody, that can induce **cytolysis**.

cytolysis the breakdown of cells, especially by destruction of their outer membranes; the lysis of cells. —**cytolytic** *adj.*

cytomegalovirus (CMV) a common virus of the Herpesviridae family that rarely causes illness unless the immune system is compromised. The double-stranded DNA genome is packed into an icosahedral capsid that is surrounded by an amorphous layer called the ‘tegument’, which includes 15 distinct proteins. The tegument is enclosed in a cell-derived lipid membrane envelope containing virus encoded **glycoproteins** that are important for the attachment of the virus particle to the host cell. CMV causes the retrotranslocation of **Class I MHC** proteins from the **endoplasmic reticulum** to the **cytosol** where they are degraded by **proteasomes**.

cytometer **1** a **cell counter**. **2** a device for measuring cells.

cytometry the counting and/or measuring of cells in a fluid suspension.

cyton *or* **cytone** the body of a cell, especially a nerve cell, as distinct from its processes.

cytopathic damaging to cells.

cytopathic effect the morphological changes that cells may show in response to toxic agents or viruses.

cytopempsis the intracellular phase of **transcytosis**, whereby droplets, molecules, or particles are transported across a polarized cell from one surface to another.

cytophilic having an affinity for cells.

cytophilic antibody any antibody that binds to the surface of cells by means other than by combination of the antibody-combining site with antigenic determinants on the cell surface. Antibody thus fixed to a cell is still able to bind antigens in the vicinity; i.e. the cells become able specifically to absorb antigen.

cytophotometry a technique that employs a combination of microscopy and spectrophotometry for the detection, localization, and determination of substances in cells. It may be done on stained or unstained preparations.

cytoplasm all the **protoplasm** of a living cell excluding the nucleus and the **plasma membrane** but including the other intracellular organelles and structures. Some authors currently also exclude mitochondria, chloroplasts, or other structures containing independently replicating DNA. The term is not synonymous with **cytoplasmic fraction**. *See also* **cytosol**. —**cytoplasmic** *adj.*

cytoplasmic droplet a large (1–8 μm) piece of membrane-bound cytoplasm, containing the usual cytoplasmic organelles (but no nucleus) and one or more large lipid droplets, found in skimmed freshly secreted goat's milk. The droplets are capable of triglyceride biosynthesis.

cytoplasmic fraction the material obtained after the removal of unbroken cells, cell debris, and nuclei from a **homogenate** of eukaryotic cells or tissue. It may be further resolved into a **mitochondrial fraction**, a **microsomal fraction**, and a soluble fraction. The term is not synonymous with **cytoplasm**. *See also* **cytosol**.

cytoplasmic gene any extranuclear gene located in certain eukaryotic cellular organelles, e.g. mitochondria and chloroplasts.

cytoplasmic inheritance the inheritance of characters or traits whose determinants are not located on a chromosome. The determinants may be, e.g., viral, mitochondrial, or on plasmids.

cytoplasmic matrix *an alternative name for* **groundplasm**.

cytoplasmic membrane **1** any of the membranous structures within the **cytoplasm** of eukaryotes, such as the rough and smooth **endoplasmic reticulum** and the **Golgi apparatus**. *See also* **microsomal fraction**, **microsome**. **2** *an alternative term for* **cell membrane** (especially in relation to bacteria).

cytoplasmic polyadenylation element *abbr.*: CPE; a uridine-rich sequence in the 3′ untranslated region of eukaryotic mRNA that is required for cytoplasmic polyadenylation. It binds **CPE-binding protein** (CPEB), which recruits other proteins (e.g. maskin, XPum).

cytoplasmic polyadenylation element-binding protein *see* **cytoplasmic polyadenylation element**.

cytoplast **1** an anuclear eukaryotic cell resulting, e.g., from treatment with cytochalasin B (*see* **cytochalasin**). **2** the apparent single structural and functional unit of the eukaryotic cell, consisting of the **microtrabecular lattice** linking the subcellular organelles and structural fibres.

cytosegresome *an alternative name for* **autophagic vacuole**.

cytosine *symbol*: Cyt; 4-amino-2-hydroxypyrimidine; 4-amino-2(1*H*)-pyrimidinone; a pyrimidine derivative that is one of the five main bases found in nucleic acids; it occurs widely in **cytidine** derivatives.



β-cytosine arabinoside *see* **cytarabine**.

+cytosis *suffix* indicating an increase in the number of cells (in an indicated tissue or organ).

cytoskeleton any of the various filamentous elements within the cytoplasm of eukaryotic cells that remain after treatment of the cells with mild detergent to remove membrane constituents and soluble components of the cytoplasm. The term embraces **intermediate filaments**, **microfilaments**, **microtubules**, and the **microtrabecular lattice**. The various elements of the cytoskeleton not only serve in the maintenance of cellular shape but also have roles in other cellular functions, including cellular movement, cell division, endocytosis, and movement of organelles. (*Note:* The term was coined to describe hypothetical structural cytoplasmic mosaics envisaged as providing physical support for, and thus spatial coordination of, enzymes effecting sequences of reactions, and as imposing restriction of mobility of the cell. Subsequently the cytoskeleton was regarded also as a possible subcellular site of action of various hormones.) —**cytoskeletal** *adj.*

cytosol the part of the **cytoplasm** that does not appear to contain membranous or particulate subcellular components. The term is not synonymous with **soluble fraction**. —**cytosolic** *adj.*

cytosol aminopeptidase *another name for* **leucyl aminopeptidase**.

cytosome any cytoplasmic structure bounded by a single **unit membrane** and of dubious identity.

cytostatic any agent that suppresses cell growth and multiplication.

cytotactin *another name for* **tenascin**.

cytotaxigen any substance that acts indirectly to induce **cytotaxis** by inducing **cytotaxin** formation. For instance, the fixing of complement by antigen–antibody complexes causes the liberation of cytotaxins, and hence cytotaxis. —**cytotaxigenic** *adj.*

cytotaxin *or (sometimes)* **chemotaxin** any chemotactic substance acting directly to induce **cytotaxis**. *See also* **cytotaxigen**.

cytotaxis **1** positive or negative **chemotaxis** of motile cells in response to diffusible substances (cytotaxins) emitted by other cells. **2** the rearrangement of cells leading to the ordering and arranging of new structures. —**cytotactic** *adj.*

cytotoxic causing cell death.

cytotoxicity the attribute of being cytotoxic.

cytotoxicity test any test of cell viability after exposure of cells to (potentially) toxic agents, e.g. antibody and complement. Loss of viability may be demonstrated by a **dye exclusion test**.

cytotoxic T-cell any of a subset of T lymphocytes, bearing the CD8 (human) or Ly2 (mouse) surface marker, that have the ability to kill infected cells. This requires cooperation from T-helper cells. Each cytotoxic T-cell specifically recognizes one antigen, which must be associated with a syngeneic class I MHC molecule.

cytotrophoblast the inner cellular layer of the **trophoblast** of a mammalian conceptus, from which chorionic villi arise. *Compare* **syncytiotrophoblast**.

cytotropism the mutual attraction of two or more cells. —**cytotropic** *adj.*

cytovillin *another name for* **ezrin**.

Dd

dyskerin d *symbol for* **1** deci+ (SI prefix denoting 10^{-1} times). **2** a deuteron. **3** day.

d+ **1** *abbr. for* deoxy+ (def. 1); used as a prefix especially to form the symbol dRib for deoxyribose. **2** deoxy+ (def. 2); used as a prefix to form symbols for 2′-deoxyribonucleosides (e.g. dAdo *or* dA for deoxyadenosine) and abbreviations for 2′-deoxyribonucleotides (e.g. dGMP for deoxyguanosine monophosphate).

d *symbol for* **1** diameter, distance, or thickness. **2** relative density.

d- *abbr. for* dextro- used *(formerly) as symbol* denoting dextrorotatory; (+)- should now be used. *See* **optical isomerism**.

D *symbol for* **1** a residue of the α-amino acid L-aspartic acid. **2** a residue of an incompletely specified base in a nucleic-acid sequence that may be adenine, guanine, or either thymine (in DNA) or uracil (in RNA). **3** a residue of the ribonucleoside (5,6-)dihydrouridine. **4** debye. **5** deuterium (use deprecated).

D600 gallopamil, 5-methoxyverapamil, α-(3- [2-(3,4-dimethoxyphenyl)ethyl] methylamino propyl)-3,4,5-trimethoxy-α-(1-methylethyl) benzeneacetonitrile; a drug used in the laboratory to block transport of calcium ions in biological membranes; it is more potent than **verapamil**.

2,4-D *abbr. for* 2,4-dichlorophenoxyacetic acid, a synthetic **auxin** used as a herbicide and to increase latex output from old rubber trees. When sprayed onto foliage at appropriate concentrations it kills broad-leaved plants but not grasses.



D *symbol for* **1** diffusion coefficient. **2** (decadic) attenuance. **3** absorbed dose. **3** (bond) dissociation energy. **4** dilution rate.

D_i *symbol for* **1** electric polarization. **2** internal transmission density (*formerly called* optical density).

D- *prefix* denoting one of two possible **absolute configurations** around a chiral element in certain classes of compounds. *See* **D/L convention**.

2D two-dimensional, e.g. 2D gel electrophoresis, 2D NMR spectroscopy.

da *symbol for* deca+ (the SI prefix denoting 10 times).

dA a residue of the deoxynucleoside deoxyadenosine (alternative to dAdo).

Da *symbol for* dalton.

DA *abbr. (sometimes) for* dopamine.

Dab *see* **A_2bu**.

DAB *abbr. for* diaminobutyric acid.

DABA *abbr. for* diaminobenzoic acid.

DABITC *abbr. for* dimethylaminobenzene isothiocyanate, 4-*N,N*-dimethylaminoazobenzene 4′-isothiocyanate; a sensitive and versatile chromophoric reagent used in sequencing polypeptides by the **Edman degradation**.



dabsyl *abbr. for* dimethylaminobenzenesulfonyl, 4-dimethylaminobenzene-4′-sulfonyl; a group used as a chromophoric label for free amino groups in amino acids, peptides, and proteins. It is introduced by reaction with dabsyl chloride, 4-dimethylaminobenzene-4′-sulfonyl chloride.



dAdo *symbol for* a residue of the deoxynucleoside deoxyadenosine; 2′-deoxyribosyladenine; adenine 2′-deoxyriboside (alternative to dA).

dAdo5′*P* *symbol. for* deoxyadenosine 5′-phosphate.

daf-2 a *Caenorhabditis elegans* gene encoding a receptor like that for insulin. Partial loss-of-function mutations result in a long-lived phenotype with resistance to killing by several bacterial pathogens. *See* ***age-1***.

DAF *abbr. for* complement decay-accelerating factor.

DAG *abbr. for* diacylglycerol.

DAHP *abbr. for* 3-deoxy-D-*arabino*-(2-)heptulosonate 7-phosphate.

daidzein an isoflavone that, like genestien, is synthesized by soybean and induces *nod* genes in some *Rhizobium* species.

dal *(sometimes) symbol for* dalton (Da is usual).

Dale's principle the principle that a given neuron is likely to release the same active substance from all its active terminals. Sometimes aggrandized into **Dale's law** – one neuron, one neurotransmitter – its only subsequent modification has been the recognition that a neuron may release more than one active substance. *See* **cotransmitter**. [After (Sir) Henry Hallett Dale (1875–1968), British physiologist.]

dalton *symbol*: Da; a non-SI unit of atomic and molecular mass, equal to one-twelfth of the mass of the nuclide carbon-12. It is identical with the **unified atomic mass unit**. It is widely used in biochemistry. Sometimes it is used incorrectly as a supposed unit of the dimensionless terms **relative atomic mass** and **relative molecular mass**. [After John Dalton (1766–1844), British chemist and physicist.]

Dalton's law of partial pressures a statement that the total pressure of a mixture of gases is equal to the sum of the partial pressure of the constituent gases.

Dalziel coefficient any of the coefficients of an equation expressing the initial rate, ν, of a sequential two-substrate enzymic reaction of the form:

$$\nu = EAB\,/\,[AB\,\phi_0 + B\,\phi_1 + A\,\phi_2 + \phi_{12}]$$

where E is the enzyme concentration, A and B are the substrate concentrations, and ϕ_0, ϕ_1, ϕ_2, and ϕ_{12} are the Dalziel coefficients. The method can be extended to the evaluation of the eight Dalziel coefficients needed to describe the rate of a three-substrate reaction. [After Keith Dalziel (1921–94), British biochemist.] *Compare* **Michaelis kinetics**.

dam a gene of *Escherichia coli* encoding DNA-adenine methylase. *See* **DNA methylase**.

damascenine 3-methoxy-2(methylamino) benzoic acid methyl ester; a **protoalkaloid** from the seeds of *Nigella damascena* (love-in-a-mist) and the odoriferous principle of the oil of nigella.

dam* methyltransferase** an enzyme that introduces a methyl group at the C5 position of the inner cytosine of the sequence 5′CCAGG3′ or 5′CCTGG3′. This prevents cleavage by the *Eco*RII restriction endonuclease. *Compare* ***dam.

dAMP *abbr. for* deoxyadenosine monophosphate, the common name for 2′-deoxyadenosine 5′-phosphate; 2′-deoxy-5′-adenylic acid; adenine 2′-deoxyriboside 5′-phosphate.

danazol 17*α*-pregna-2,4-dien-20-ynol[2,3-*d*]isoxazol-17*β*-ol; a derivative of ethisterone that is an inhibitor of anterior pituitary function. It inhibits secretion of gonadotropins and synthesis of sex steroids and acts as a ligand for their receptors.



Dane particle *see* **hepatitis**.

Danielli–Davson model *see* **Davson–Danielli model**.

dansyl *symbol*: Dns; *abbr. for* 5-dimethylaminonaphthalene-1-sulfonyl, a group used in **extrinsic fluorescence** studies of proteins. *See also* **dansylate**.



dimethylaminonaphthalene sulfonyl chloride

dansylate to derivatize with a dansyl group by reacting with dansyl chloride, 5(dimethylamino)naphth-1-ylsulfonyl chloride. The method is used to acylate free amino groups in protein end-group analysis. The dansyl amino acids, isolated after hydrolysis of the protein, are highly fluorescent and amounts as small as 1nmol may be detected. —**dansylated** *adj.*; **dansylation** *n.*

Danysz's effect *or* **Danysz's phenomenon** the variation in the toxicity of toxin–antitoxin mixtures dependent on whether toxin is added to equivalence in one lot (nontoxic mixture produced) or in smaller lots over a time period (toxic mixture produced). When added in small lots the toxin reacts with more than one equivalent of antitoxin (antibody) so that insufficient antibody is left to neutralize all the subsequent lots of toxin. [After its discoverer, Jean Danysz (b. 1860), Polish pathologist working in Paris.]

DAP *abbr. for* diaminopimelate.

DAP pathway *see* **diaminopimelic-acid pathway**.

dapsone 4,4′-diaminodiphenyl sulfone; bis(4-aminophenyl)sulfone; an antibacterial and antiprotozoal substance used especially against *Mycobacterium leprae*, the causative agent of leprosy, and as an adjunct in the treatment of malaria. It acts as a competitive antagonist of *p*-aminobenzoic acid and an inhibitor of folate synthesis.



DARC *abbr. for* Duffy antigen receptor for chemokines. *See* **Duffy system**.

dark adaptation the process by which the rods of the retina gradually become fully responsive to dim light when no longer exposed to bright light. —**dark-adapted** *adj.*

dark band *see* **light band**.

dark current the electric current observed in any photoelectric device in the absence of incident radiation. It is caused by thermal effects.

dark-field microscope *or* **dark-ground microscope** a form of light microscope in which the specimen is illuminated by the apex of a hollow cone of light. On diverging, the light does not enter the aperture of the objective lens, so that unstained or transparent specimens appear as bright objects on a black background.

dark reactions of photosynthesis traditional term for the reactions of the **reductive pentose phosphate cycle** that utilize the ATP and NADPH produced by the light-driven reactions of photosynthesis. The term misleadingly indicates that these reactions occur in the dark. This is true only in the sense that, over very short time intervals, they can occur in the absence of light provided ATP and NADPH are present. However, they are subject to regulatory mechanisms that are stimulated by light, and inhibited by the dark. In growing plants, these reactions occur during daylight hours. The reactions of photosynthesis are used to convert CO_2 into hexoses and other organic compounds by the reactions of the reductive pentose phosphate cycle.

dark reactivation *or* **dark repair** any light-independent enzymic mechanism for the repair of damaged DNA molecules. *Compare* **photoreactivation**.

DARPP-32 *abbr. for* dopamine and cAMP-regulated phosphoprotein 32 kDa; a cellular glycoprotein produced by phosphorylation of a threonine residue by protein kinase A when dopamine binds the dopamine receptor. It is dephosphorylated mainly by calcineurin, and is involved in the psychomotor effects of caffeine.

database a collection of information organized within a (usually relational or object-oriented) management system (the term is also often inaccurately applied to data collected within a flat-file). Hundreds of biodatabases are now available, containing biomolecular sequences or structures, complete genomes, genetic disease information, biochemical pathway data, protein–protein interactions, biomedical literature, etc. Many are listed in the online catalogue **DBCAT**.

database division a data subset created to ease management and to facilitate rapid, specific searches of large databases. For example, EMBL, GenBank, and DDBJ are split into divisions that are largely taxonomic (e.g. prokaryotes, fungi, plants, mammals), although some divisions are based on the types of data being held – e.g. sequence and mapping data from expressed sequence tags (ESTs); sequence-tagged sites (STSs); genome survey sequences (GSSs); high-throughput genomic sequences (HTGs); and unfinished high-throughput cDNA sequences.

database ID *an alternative name for* **database identification code**.

database identification code *or* **database ID** a (usually human readable) code that identifies a particular entry in a particular database. Database IDs are assigned when entries are first added to a database but may change between updates, so are not a reliable means of locating them in subsequent releases. Some databases use systematic IDs, some use fixed-length mnemonics, and others use the same code as the accession number. For example, OPSD_BOVIN identifies bovine rhodopsin in Swiss-Prot; GPCR_Rhodpsn identifies the rhodopsin-like G-protein-coupled receptor superfamily in InterPro; and O96585 identifies the long-wavelength rhodopsin from the bumblebee (*Bombus terrestris*) in TrEMBL.

database-search program **1** any software used to search a database with a user query. **2** *(in sequence analysis)* software for protein or nucleotide sequence searches, such as FastA, BLAST and its variants, e.g. PSI-BLAST (position-specific iterated-BLAST) searches databases such as nrdb or Swiss-Prot iteratively by creating a profile from an alignment of the best-scoring hits and refining the profile with the results of each new search. PHI-BLAST (pattern hit initiated BLAST) searches iteratively for sequences that contain a user-specified pattern, each time refining the results via PSI-BLAST. **3** *(in structure analysis)* software for protein structure searches. For example, VAST (vector alignment search tool) searches for structurally similar proteins in MMDB (molecular modelling database). *See* **structure database**.

data cleaning the removal from, or correction of, erroneous data in a data set.

data mining 1 the process by which implicit information is extracted from data. **2** the process of searching for statistically significant relationships and global patterns in databases.

DATD *abbr. for* diallyltartardiamide, a cross-linking agent.

dative bond *an alternative term for* **dipolar bond**.

dATP *abbr. for* deoxyadenosine triphosphate, the common name for 2′-deoxyadenosine 5′-triphosphate, 2′-deoxy-5′-adenylyl diphosphate, adenine 2′-deoxyriboside 5′-triphosphate.

Daudi a human cell line established from a patient with Burkitt's lymphoma.

daughter *(as modifier)* **1** denoting a cell (or cell nucleus) produced by the fission of the original (mother) cell or nucleus. **2** denoting either of the two strands of DNA that originate from the parental duplex DNA molecule at replication. **3** denoting a nuclide produced by the nuclear disintegration (either spontaneous or induced) of another nuclide.

daunomycin *or* **daunorubicin** an anthracycline antibiotic and antineoplastic isolated from fermentation broths of *Streptomyces peucetius* widely used in the treatment of cancer. It is a glycoside formed from the tetracyclic aglycon daunomycinone ($C_{21}H_{18}O_8$) and the aminohexose **daunosamine**. It inhibits DNA replication by intercalation into duplex DNA and also inhibits RNA transcription. *Compare* **doxorubicin**.

daunosamine 3-amino-2,3,6-trideoxy-L-*lyxo*-hexose; the aminodeoxy sugar component of **adriamycin**, **daunomycin**, **doxorubicin**, and other antibiotics



α-L anomer

Davson–Danielli model *or (sometimes)* **Danielli–Davson model** a structural model of the **plasma membrane** consisting, as originally proposed, of a lipid bilayer covered on both surfaces by a film of adsorbed globular proteins. Essentially it was a lamellar model: two sheets of protein separated by a sheet of lipid. The lipid layer had a hydrophobic core and more hydrophilic surfaces. To account for the permeability properties of the plasma membrane the model was subsequently modified by the proposal that pores allow polar solutes to penetrate the lipid layer, and that these pores are lined by protein molecules, providing hydrophilic tubes through the membrane. The model has been totally superseded by more recent concepts. *See* **cell membrane**. [After Hugh Davson (1909–96), British biochemist and physiologist and J. F. Danielli (1911–84), British biochemist.]

day *symbol*: d; a non-SI unit of time equal to 24 hours or 86 400 s.

dbcAMP *abbr. for* dibutyryl cyclic AMP; $N^6,O^{2'}$-dibutyryladenosine 3′,5′-(cyclic)phosphate; a fat-soluble analogue of cyclic AMP, **adenosine 3′,5′-phosphate**.

DBCAT *abbr. for* the Catalogue of Databases; an online catalogue of biomolecular, genetic, genomic, and literature databases.

D-bifunctional enzyme *see* **peroxisomal bifunctional enzyme**.

DBL a gene, isolated and named from a human diffuse B-cell lymphoma, that encodes a protein that contains a Dbl domain of ≈200 amino acids, which is active as a Rho guanine nucleotide exchange factor, and a pleckstrin domain for binding phosphoinositides. It is a protooncogene that when mutated results in hemopoietic tumour.

Dbl domain a protein domain comprising a sequence of ≈200 amino acids, for which the prototype is the Rho guanine nucleotide exchange factor (*see* **RhoGEF**) of DBL. It shows 29% sequence identity with yeast Cdc24 (which is an activator of yeast Cdc42), and 25–30% homology with domains in other RhoGEFs. It seems to be usually accompanied by a pleckstrin homology domain. These proteins help transduce signals from receptors for growth factors, cytokines, and adhesion factors, and from G-protein-coupled receptors.

DBM *abbr. for* 2-diazobenzyloxymethyl, $–CH_2–O–CH_2–C_6H_4– N_2^+$; a group that introduces reactive diazonium groups into cellulose or paper forming **DBM-cellulose** or **DBT-paper** in **blot transfer** of proteins or nucleic acids. DBM is formed by diazotization of 2-aminobenzyloxymethyl (ABM) groups previously coupled to the support.

DBMIB *abbr. for* 2,5-dibromo-3-methyl-6-isopropyl-*p*-benzoquinone; a competitor of **plastoquinone** in photosynthetic electron flow.

DBP *see* **vitamin D binding protein**.

dbSNP a repository of genetic variations – mostly single nucleotide polymorphisms (SNPs) and a few small insertions and deletions – that includes, for example, sequence information around the polymorphism, descriptions of the population containing the variation, and frequency information by population or individual genotype.

d.c. *or* **DC** *abbr. for* **1** direct current. **2** a voltage of constant polarity.

dC *symbol for* a residue of the deoxynucleoside deoxycytidine (alternative to dCyd).

DCC *or* **DCCD** *or* **DCCI** *abbr. for N,N′*-dicyclohexylcarbodiimide, a coupling agent useful in peptide synthesis and other coupling reactions. *See also* **carbodiimide**.

DCC *abbr. for* deleted in colonic carcinoma; a human gene that encodes a transmembrane protein that is produced in intestinal mucosa and brain, and in small amounts in other tissues. Its N-terminal extracellular segment contains four immunoglobulin-like and seven fibronectin repeats, and shows about 30% homology with netrin receptor. The gene, at 18q21.2 and comprising ≈1.4Mb, is deleted in over 70% of cancers of the colon and rectum. Hence, *DCC* is classed as a tumour suppressor gene

D cell *or (formerly)* $\mathbf{A_1}$ **cell** *or* $\boldsymbol{\alpha_1}$ **cell** a type of endocrine cell of the **apud** series, found in gut mucosa and the pancreatic islets. It was formerly thought to produce gastrin, but is now believed to produce **somatostatin**.

dCMP *or* **dCyd5′*P*** *abbr. for* deoxycytidine monophosphate, the common name for 2′-deoxycytidine 5′-phosphate; 2′-deoxy-5′-cytidylic acid; cytosine 2′-deoxyriboside 5′-phosphate.

dCMP hydroxymethylase *systematic name*: 5,10-methylenetetrahydrofolate:deoxycytidylate 5-hydroxymethyl transferase. EC 2.1.2.8; *other names*: deoxycytidylate hydroxymethylase; deoxycytidylate hydroxymethyltransferase; an enzyme that catalyses the reaction:

$$\text{5,10-methylenetetrahydrofolate} + H_2O + \text{deoxycytidylate} = \text{tetrahydrofolate} + \text{5-hydroxymethyldeoxycytidylate.}$$

It is a gene product of T-even bacteriophage; the DNA of these phages contains glycosylated 5-hydroxymethylcytosine residues in place of cytosine residues. There is similarity to *Escherichia coli* **thymidylate synthase**.

DCMU *abbr. for* 3-(3,4-dichlorophenyl)-1,1-dimethylurea; a herbicide that blocks electron transport on the reducing side of photosystem II. One proprietary name is Diuron.



Dco *symbol for* the decanoyl group, $CH_3–[CH_2]_8–CO–$.

DCoH *abbr. for* dimerization cofactor for HNF-1α; an activity of a bifunctional protein (PCD/DCoH; 103 amino acids) that is required for dimerization of **hepatocyte nuclear factor**-1α. *See* **pterin-4*α*-carbinolamine dehydratase**.

DC-SIGN *abbr. for* dendritic cell-specific ICAM-3-grabbing nonintegrin; either of two type II transmembrane proteins that are specific to dendritic cells (i.e. antigen- presenting macrophages, mainly of spleen and lymph nodes) and bind T lymphocytes by ICAM-3 on their surfaces. DC-SIGN1 is also found on endothelial cells and shows 77% homology with DC-SIGN2, which is also found on liver sinusoidal cells. Their extracellular C-terminal regions contain seven 23-residue repeats in tandem, and a Ca^{2+}-dependent lectin domain that binds mannose-containing ligands. Both proteins bind gp120 of the HIV-1 envelope.

dCTP *abbr. for* deoxycytidine triphosphate, the common name for 2′-deoxycytidine 5′-triphosphate, 2′-deoxy-5′-cytidylyl diphosphate, cytosine 2′-deoxyriboside 5′-triphosphate.

dCyd *symbol for* a residue of the deoxynucleoside deoxycytidine; 2′-deoxyribosylcytosine; cytosine 2′-deoxyriboside (alternative to dC).

dCyd5′*P* *symbol for* deoxycytidine 5′-phosphate.

dd+ *abbr. for* dideoxy+ (def. 2); **1** used as a *prefix* to the appropriate three-letter or one-letter symbols for ribonucleosides in order to form symbols for 2′,3′-dideoxyribonucleosides (e.g. ddNuc *or* ddN, *symbol for* any (unknown or unspecified) 2′,3′-dideoxyribonucleoside; ddAdo *or* ddA, *symbol for* dideoxyadenosine). **2** used similarly to form abbreviations for 2′,3′-dideoxyribonucleoside 5′-triphosphates (e.g. ddNTP, *abbr. for* any (unknown or unspecified) 2′,3′-dideoxyribonucleoside 5′-triphosphate; ddCTP, *abbr. for* dideoxycytidine triphosphate).

DDBJ *abbr. for* DNA databank of Japan; *see* **sequence database**.

DDT *abbr. and common name for* dichlorodiphenyltrichloroethane; 1,1,1-trichloro-2,2-bis(*p*-chlorophenyl)ethane; a contact insecticide that has proved particularly valuable in controlling insect disease vectors, especially mosquitoes (*Anopheles* spp.). However, it is toxic to higher animals as well. It has a very long persistence of activity from residual deposits which has caused it to be banned in many countries.



de+ *prefix (in organic chemical nomenclature)* denoting replacement of a specified group or atom in a specified chemical compound by a hydrogen atom. An exception is **deoxy+** when applied to hydroxy compounds, which denotes replacement of a hydroxyl group by a hydrogen atom. *See also* **dehydro+**, **des+**.

deacylase *informal name for* any enzyme that catalyses a deacylation reaction; it may be a hydrolase or a transferase.

deacylation the act or process of removing an acyl group from a chemical compound.

DEAD box a highly conserved motif in a family of putative RNA **helicases**, named after the single-letter code for the amino-acid sequence involved, i.e. Asp-Glu-Ala-Asp. The first DEAD-box protein shown to have RNA-helicase activity was the eukaryotic translational initiation factor eIF4-A. Other proteins have since been included in the family, based on sequence similarities; some have been shown to have ATP-dependent RNA-helicase activity, while in others this remains to be experimentally confirmed. *See also* **DEAH family**.

dead-end complex *an alternative name for* **abortive complex**.

dead ringer an **ARID protein** of *Drosophila* whose DNA-binding sequence is the prototype for the dead ringer domain that is present in human and mouse jumonji proteins. Mutations in dead ringer are lethal at the embryonic stage in *Drosophila* and mouse.

DEAE *abbr. for* diethylaminoethyl, $(C_2H_5)_2N–CH_2–CH_2–$, a weakly basic group widely used as a substituent in hydroxylated chromatographic support matrices, e.g. cellulose, Sephadex, to form anion exchangers. *Compare* **QAE**.

DEAE-dextran *abbr. for* diethylaminoethyl-dextran; a polycationic derivative of dextran used in the transfection of mammalian cells with exogenous DNA.

de-aerate to remove air from a liquid or a slurry, commonly by heating and/or reduction of pressure.

DEAH family yeast proteins that are structurally similar to **DEAD-box** proteins, but larger. They differ fom DEAD-box proteins in parts of the conserved region, especially in having a conserved DEAH sequence rather than DEAD. Some of them are known to be involved in RNA splicing, e.g. in *trans*-esterification steps and spliceosome release.

deamidase *name sometimes used for* an enzyme that catalyses the hydrolytic cleavage of the C–N bond in a carboxamide, but that is correctly termed an **amidase**.

deamidation the process of removing an amino group from an amide, either by hydrolysis or by a transfer reaction.

deaminase any of the enzymes that catalyse the nonoxidative removal of amino groups, with production of ammonia. They are usually aminohydrolase enzymes (sub-subclass EC 3.5.4), which hydrolytically deaminate amino-substituted cyclic amidines including various (free or combined) pterins, purines, or pyrimidines. Certain hydro-lyase (sub-subclass EC 4.2.1) and hydrolytic or nonhydrolytic ammonia-lyase (sub-subclass EC 4.3.1) enzymes also are commonly called deaminases.

deamination the process of removing an amino group from an organic compound. *Compare* **transamination**.

deaminooxytocin *or* **demoxytocin** a synthetic analogue of **oxytocin**, in which the N-terminal half-cystine residue has been replaced by a residue of 3-mercaptopropanoic acid. It is more potent than the parent compound.

de-ashing a procedure in which interfering inorganic (i.e., ash-forming) components are removed from samples of carbohydrates being analysed by liquid chromatography by passing them first through anion- and cation-exchange resins.

death domain a region of limited similarity, comprising ~80 residues close to the intracellular C terminus of certain cell-membrane receptors (e.g., the **TNF receptor**), that is essential for the receptors to generate a signal leading to apoptosis.

death-inducing signalling complex *see* **DISC**.

death receptor a transmembrane receptor protein involved in inducing apoptosis. It oligomerizes on binding of its ligand and contains an intracellular **death domain** that recruits a cytosolic death domain protein (e.g. **FADD**) to initiate apoptosis. Examples include **Fas** and TNF receptor-1.

7-deaza-dGTP an analogue of dGTP used when sequencing DNA with a high content of GC base pairs.

deblock to remove a **blocking group**. **—deblocking** *n.*

debrancher deficiency *an alternative name for* type III **glycogen** (storage) **disease**.

debranching enzyme any enzyme that catalyses the cleavage of branch points in particular branched biopolymers, e.g. **isoamylase**, **oligo-1,6-glucosidase** and **pullulanase**.

debye *symbol*: D; a non-SI unit of molecular dipole moment: $1D \approx 3.335\,64 \times 10^{-30}$ Cm.

Debye–Hückel theory a theory used to calculate the electric potential at a point in a solution in terms of the concentrations and charges of the ions and the properties of the solvent. It yields the logarithm of the mean rational activity coefficient:

$$\mathrm{lg} f^{+/-} = (A|z_1 z_2|\, I^{1/2})/(1 + BaI^{1/2}),$$

where the constants A and B involve the temperature and the dielectric constant of the solvent, a is an adjustable ‘ion-size’ parameter, I is the **ionic strength**, and $|z_1 z_2|$ is the absolute value of the valence product of the electrolyte under consideration. [After Petrus (‘Peter’) Debye (1884–1966), Dutch-born US physicist and physical chemist, and Eric Hückel (1896–1980), German physicist.]

dec+ *see* **deca+** (def. 2).

Dec *symbol for* the decyl group, $CH_3–[CH_2]_8–CH_2–$.

deca+ **1** *symbol*: da; the SI prefix denoting 10 times. **2** *or (before a vowel)* **dec+** *comb. form* denoting ten, tenfold, or ten times; formerly sometimes written as deka+ *or* dek+.

decamethonium *N*,*N*,*N*,*N*^{1},*N*^{1},*N*^{1}-hexamethyl-1,10-decanediaminium a nicotinic receptor ligand that causes sustained activation of the receptors, with consequent blockade of synaptic transmission (termed ‘depolarizing block’). *See also* **suxamethonium**.



decanoate **1** the anion, $CH_3–[CH_2]_8–COO^-$, derived from decanoic acid (formerly capric acid). **2** any mixture of decanoic acid and the anion. **3** any salt or ester of decanoic acid.

decanoyl *symbol*: Dco; the univalent acyl group, $CH_3–[CH_2]_8–CO–$, derived from decanoic acid. *See also* **caproyl** (def. 1).

decant to pour off a supernatant liquid from a precipitate or other sediment. **—decantation** *n.*

decap to (enzymically) remove a **cap** (def. 1) from the 5′ end of a capped mRNA molecule. **—decapped** *adj.*

decapentaplegic *abbr.*: dpp; a secreted protein of the transforming growth factor β superfamily that triggers various morphogenetic processes in *Drosophila*. It participates in an intercellular signalling pathway that activates a specific transcription factor required for normal embryonal development. A homologue of dpp occurs in mammals.

decapsidate to remove the capsid from a virus. **—decapsidation** *n.*

decarboxylase any of the enzymes of the sub-subclass EC 4.1.1, carboxy-lyases; they catalyse the removal of carboxyl groups from carboxylic acids.

decarboxylation the act or process of removing the carboxyl group from a carboxylic acid as carbon dioxide. The reaction may be enzyme-catalysed by a **decarboxylase** or, in some instances, particularly with 2-oxo acids, it may be spontaneous. **—decarboxylate** *vb.*; **decarboxylated** *adj.*

decay **1** a decrease in activity, force, quantity, or other physical attribute, especially with a characteristic time constant. **2** (**a**) **nuclear decay**: the spontaneous change of one nuclide into another, its daughter, with a different proton number or nucleon number. (**b**) **radioactive decay**: nuclear decay in which particulate or electromagnetic radiation (or both) is emitted, or in which spontaneous fission of the nucleus occurs. *See also* **disintegration**. **3** the decline of an atom or molecule from an excited state. **4** the biochemical decomposition of plant and animal remains, due chiefly to the activities of microorganisms.

decay accelerating factor *see* **complement decay-accelerating factor**.

decay constant *an alternative term for* **disintegration constant**.

deci+ **1** *symbol*: d; the SI prefix denoting 10^{-1} times. **2** *comb. form* denoting one tenth, one in ten.

decimolar *(informal)* one-tenth molar; i.e. denoting a solution of concentration 0.1 mol dm^{-3}.

decinormal *(informal; not now recommended)* one-tenth normal; i.e. denoting a solution of concentration 0.1 equivalents per litre (*see* **normal** (def. 2)).

Declomycin *proprietary name for* **demeclocycline**. *See also* **tetracycline**.

decoding *(informal) an alternative term for* **translation** (def. 1).

decontaminant an agent for removing or neutralizing a contaminant.

decontamination the act or process of removing or neutralizing any toxic or potentially toxic materials, or of reducing their concentrations to nonhazardous levels. The term is used especially in regard to microbes, toxic chemicals, carcinogens, and radioactive substances. *Compare* **contamination**.

decorin *or* **fibromodulin** *or* **bone proteoglycan II precursor** a collagen-binding protein of the extracellular matrix, so called because it 'decorates' collagen fibrils. The core protein has a single **glycosaminoglycan** chain, together with other oligosaccharide substituents.

decose any **aldose** having a chain of ten carbon atoms in the molecule.

dCTP deaminase EC 3.5.4.13; *systematic name*: dCTP aminohydrolase; *other name*: deoxycytidine triphosphate deaminase. An enzyme that hydrolyses the amino group of dCTP to form dUTP and NH_4^+.

deculose any **ketose** having a chain of ten carbon atoms in the molecule.

decyl *symbol*: Dec; the alkyl group, $CH_3–[CH_2]_8–CH_2–$, derived from decane.

***n*-decyl-*β*-D-glucopyranoside** a nonionic detergent, useful for solubilizing membrane proteins; CMC 2–3 mm.

***n*-decyl-*β*-D-maltopyranoside** a nonionic detergent, useful for solubilizing membrane proteins; CMC 1.6 mm.

dedifferentiation the loss of the characteristics of a specialized cell and regression to a simpler state. **—dedifferentiate** *vb.*

defective virus a virus that is unable to reproduce itself whilst infecting a cell without the presence of a **helper virus**.

defensin any of a family of small cationic peptides, containing six cysteines in disulfide linkage, that have broad-spectrum antibiotic action, and contribute to host defence against microorganisms. They are abundant in phagocytes, in the small intestinal mucosa of humans and other mammals, and in the hemolymph of insects. Defensins adopt multimeric pore-forming complexes in membranes, thereby rendering the membrane permeable. They are distinguished by having a predominantly **beta sheet** structure.

deficiency disease any disease resulting from the deficiency of one or more essential nutrients, e.g. a vitamin, an essential amino acid, or an essential mineral.

deficient lacking some essential component; inadequate in amount. The term can be used, e.g., for a deficient (culture) medium, deficient diet, or deficient strain (of an organism).

defined medium any culture medium in which the concentrations of all the constituents, including trace substances, are quantitatively known.

deformylase *see* **formylmethionine deformylase**.

degeneracy **1** *(in a code)* the existence of two or more synonyms specifying a particular item or function; *see also* **degenerate code**. **2** *(in a quantized system)* the existence of two or more linearly independent **eigenfunctions** with the same **eigenvalue**, especially the condition of an atom or molecule. **3** *(of an atom or molecule)* the condition in which the energy levels of different quantum states have the same energy level. **—degenerate** *adj.*

degenerate code a code in which more than one symbol represents the same entity. One such is the **genetic code**, wherein a specific amino acid may be encoded by two or more nucleotide triplets, or **codons** present in a nucleic acid or polynucleotide.

degenerate oligonucleotides a mixture of oligonucleotides corresponding to a known protein sequence and accommodating all the possible coding sequences that arise from the degeneracy of the genetic code.

degeneration the process whereby a cell, tissue, or organ changes to a less specialized or functionally less active form.

degradation *(in chemistry)* **1** the gradual stepwise and deliberate conversion of a molecule into smaller chemical entities, commonly to elucidate its chemical structure. **2** any undesired breakdown of a molecule or material with impairment or loss of its characteristic properties. **3** depolymerization; decomposition. **4** *(in biochemistry)* catabolism.

degradosome a multienzyme complex involved in the degradation of mRNA in *E. coli*. It contains RNase E (the microbe's main endoribonuclease), polynucleotide phosphorylase, the glycolytic enzyme enolase, and a DEAD-box RNA helicase. Under certain conditions it may also contain poly(A) polymerase, polyphosphate kinase, and another DEAD-box RNA helicase. *Compare* **exosome**.

degranulation **1** any process by which granular cells lose their granules. **2** the stripping of polysomes from rough endoplasmic reticulum *in vitro*.

degree *see* **angle**, **temperature**.

degree Celsius *symbol*: °C; the SI derived unit of **Celsius temperature**. It denotes the same interval of temperature as the **kelvin** on a scale with different reference points.

degree of polymerization the number of **monomeric units** in the molecule of a polymer.

degrees of freedom **1** *(in statistics)* the number of unrestricted independent variables constituting a statistic; thus in a sample of *n* values of x there are n deviations ($x_i - \bar{x}$), where $\bar{x}$ is the estimate of the mean, used in calculating the sample **variance**, s^2, but they are not all independent, since there is a linear relation connecting them, namely:

$$\sum_{i=1}^{n} (x - \bar{x}) = 0$$

hence only ($n - 1$) of the quantities are independent, and there are ($n - 1$) degrees of freedom in the calculation of s^2. **2** *(in physics)* the minimum number of parameters necessary to the description of the state of a system. **3** the number of independent equations by which the energy of a system may be expressed. **4** *(in chemistry)* the number of independently variable intensive properties that must be specified in order to describe completely the state of the system. *See* **phase rule**.

dehydrase *obsolete term for* **dehydratase** or **dehydrogenase**.

dehydratase *or (formerly)* **dehydrase** any hydro-lyase enzyme, of sub-subclass EC 4.2.1, that catalyses the (reversible) breakage of a carbon–oxygen bond leading to the formation of an unsaturated product and the elimination of water; e.g. citrate dehydratase, EC 4.2.1.4. When named after the alternative, i.e. unsaturated, substrate, the enzyme is termed a **hydratase**; e.g. aconitate hydratase, EC 4.2.1.3. *See also* **carbonate dehydratase**.

dehydration **1** the removal of combined, or adsorbed, water from a chemical compound; *see also* **anhydrous**. **2** the process or result of losing water, especially the abnormal loss of water from an organism. **3** the replacement of water by solvents.

dehydro+ *prefix (in chemical nomenclature)* denoting the loss of two hydrogen atoms. In common usage it is often used in place of **didehydro+**; e.g. 7,8-didehydrocholesterol is often termed dehydrocholesterol. *Distinguish from* **anhydro+**.

7-dehydrocholesterol reductase EC 1.3.1.21; *systematic name*: 3β-hydroxysteroid-Δ^7-reductase; an enzyme of the endoplasmic reticulum that reduces 7-dehydrocholesterol to cholesterol, using NADPH as coenzyme. The gene at 11q12-q13 encodes a multipass transmembrane protein of 475 amino acids. Inactivating mutations are responsible for Smith–Lemli–Opitz syndrome.

2-dehydro-3-deoxyphosphooctonate aldolase *another name for* **3-deoxy-D-*manno*-octulosonic acid 8-phosphate synthase**.

dehydroepiandrosterone *abbr.*: DHEA; androstenolone, *trans*-dehydroandrosterone (*abbr.*: DHAS), 3β-hydroxyandrost-5-en-17-one; an intermediate in androgen and estrogen biosynthesis, formed from 17α-hydroxypregnenolone in testis, ovary, and adrenal cortex by the action of 17α-hydroxyprogesterone aldolase, EC 4.1.2.30. It is the immediate precursor of androstenedione, which is formed from it by the action of 3β-hydroxy-Δ^5-steroid dehydrogenase, EC 1.1.1.145 and it can be converted to androst-5-en-17-one 3β-sulfate (DHEA-S), in which form it is measured in plasma, there being about 1000 times more DHEA-S than DHEA in plasma.



dehydrogenase any donor:acceptor **oxidoreductase** enzyme, of the class EC 1, when named after the alternative, i.e. more reduced, substrate and when dioxygen is not the acceptor.

dehydrogenate to oxidize an organic compound by the removal of one or more hydrogen atoms. —**dehydrogenation** *n.*

3-dehydroquinate dehydratase EC 4.2.1.10; *systematic name*: 3-dehydroquinate hydro-lyase; *other name*: 3-dehydroquinase; an enzyme that catalyses the reaction:

$$\text{3-dehydroquinate} = \text{3-dehydroshikimate} + H_2O.$$

The reaction forms part of the **shikimate pathway**. For example, *see* ***aro1***. *See also* **pentafunctional arom polypeptide**.

3-dehydroquinate synthase EC 4.6.1.3; an enzyme that catalyses the hydrolysis of 7-phospho-3-deoxy-*arabino*-heptulosonate to 3-dehydroquinate and orthophosphate. *See* **pentafunctional arom polypeptide; shikimate pathway**.

(3-)dehydroretinal *an alternative name for* **3,4-didehydroretinal** (not recommended, except for nutritional usage).

(3-)dehydroretinoic acid *an alternative name for* **3,4-didehydroretinoic acid** (not recommended, except for nutritional usage).

(3-)dehydroretinol *an alternative name for* **3,4-didehydroretinol** (not recommended except for nutritional usage).

deionize *or* **deionise** to remove all ions from a solution. *See also* **desalt**. —**deionization** *or* **deionisation** *n.*

deionizer *or* **deioniser** a device used to remove ions from solutions, usually by the use of **ion exchangers**.

Dejerine–Sottas syndrome *see* **periaxin**.

deka+ *or (before a vowel)* **dek+** *former spelling of* **deca+** (def. 2).

delayed early gene *see* **early gene**.

delayed hypersensitivity *or* **type IV hypersensitivity** *(in immunology)* a **hypersensitivity** reaction that arises more than a day after encounter with the antigen and is mediated by antigen-sensitized CD4$^+$ T cells that release **cytokines**, attracting macrophages to the site and activating them. This type of hypersensitivity is seen in skin contact reactions and in response to some chronic pathogens such as those that cause leprosy, tuberculosis, and schistosomiasis. *Compare* **immediate hypersensitivity**.

deletion the loss of a segment of genetic material from a chromosome. A deletion can vary in size from a single nucleotide residue to a segment containing a number of genes. A **terminal deletion** occurs at one end of the chromosome, whereas an **intercalary deletion** occurs elsewhere along the chromosome. Some deletions are associated with genetic diseases (e.g. in human chromosome 4, giving rise to Charcot–Marie–Tooth disease, and in human chromosome 22, leading to DiGeorge syndrome).

DELFIA *the registered abbr. for* Dissociation Enhanced Lanthanide Fluoroimmunoassay; a collection of proprietary diagnostic methods based on heterogeneous immunoassays and time-resolved fluorescence.

delipidation the removal of lipid from a sample.

deliquescent *(of certain salts)* tending to absorb water from the surrounding atmosphere at ordinary temperature and pressure and then to dissolve in the water so taken up. *Compare* **hygroscopic**. —**deliquesce** *vb.*; **deliquescence** *n.*

DELLA protein any of a family of highly conserved proteins that repress plant growth. They are present in plant cell nuclei and, in response to gibberellin, become phosphorylated, polyubiquitinated, and targeted for degradation by proteasomes.

delocalization *or* **delocalisation** a quantum-mechanical concept implying that the unpaired electron density in a molecule is spread over several atoms. Analogously, delocalization of the spin of an unpaired electron can occur.

delphinidin *see* **anthocyanidin**.

delta *symbol*: δ (lower case) *or* Δ (upper case); the fourth letter of the Greek alphabet. For uses *see* **Appendix A**.

Delta *see* **Notch**.

deltahedron (*pl.* **deltahedra**) any polyhedron whose faces are all equilateral triangles. Some viruses disaggregate to form particles that are deltahedra. —**deltahedral** *adj.*

deltakephalin (D-Thr^2)-Leu-enkephalin-Thr; a highly potent and specific synthetic hexapeptide δ-opiate receptor agonist; structure Tyr-D-Thr-Gly-Phe-Leu-Thr. *See also* **enkephalin**.

delta-sleep-inducing peptide *or* **sleep peptide** a nonapeptide, Trp-Ala-Gly-Gly-Asp-Ala-Ser-Gly-Glu, found in the plasma of rats and rabbits, that shows a several-fold increase in concentration during sleep. It rapidly induces slow-wave (i.e. delta) sleep on injection into awake animals.

deltex a conserved positive regulatory protein for Notch signalling in humans. It contains an N-terminal globular region that includes two divergent sequence repeats of ≈80 residues each, called **WWE motifs** for their most conserved residues. These motifs are predicted to mediate protein interactions in ubiquitin and ADP-ribose conjugation systems. The protein's C-terminus has a RING finger domain.

dematin a protein involved in the formation of actin bundles, abundantly expressed in brain, heart, skeletal muscle, kidney, and lung, whose activity is abolished upon phosphorylation by cAMP-dependent protein kinase. It is a member of the **villin** family.

demeclocycline 6-demethyl-7-chlorotetracycline; *see* **tetracycline**.

demethylation any reaction involving the removal of one or more methyl groups from a molecule, whether by oxidation or transfer to an acceptor molecule.

demineralization *or* **demineralisation** **1** the process of removing inorganic salts, e.g. from water or other liquid; deionization. **2** excessive loss of mineral salts from the tissues, especially bone, as occurs in certain diseases.

demoxytocin *an alternative name for* **deaminooxytocin**.

denaturation **1** *(of a protein)* a process in which the three-dimensional shape of a molecule is changed from its **native state** without rupture of peptide bonds. It is sometimes taken to include disulfide bond rupture or chemical modification of certain groups in the protein if these processes are also accompanied by changes in its overall three-dimensional structure. Denaturation is frequently irreversible and accompanied by loss of solubility (especially at the isoelectric point) and/or of biological activity. **2** *(of a nucleic acid)* a process whereby a molecule is converted from a firm, two-stranded, helical structure to a flexible, single-stranded structure. *Compare* **renaturation**.

denaturation loop a non-base-paired interstrand loop formed in the more thermally unstable regions (i.e., of high A+T content) of a duplex DNA molecule during **melting** (def. 3).

denaturation mapping the identification of regions of low thermal (or alkali) stability (i.e., of high A+T content) in a duplex DNA molecule, by trapping the partly melted structure and blocking renaturation, e.g. with formaldehyde (which preferentially couples with the amino groups of the single-stranded regions), and subsequently examining the specimen by electron microscopy.

denaturing gradient gel electrophoresis *abbr*.: DGGE; a method used to detect sequence differences in relatively short double-stranded (ds) DNA molecules (<500 bp). Electrophoresis of dsDNA through increasing concentrations of urea and formamide causes dissociation of the duplex in a manner that depends on sequence domains. The resulting single-stranded DNA has a much lower electrophoretic mobility than dsDNA. The method is used to detect heteroduplexes formed after polymerase chain reaction (PCR) by annealing of wild-type and mutant strands, and in separation of mixtures of PCR products generated by amplification of 16S RNA genes in naturally occurring populations of bacteria.

denaturing high-performance liquid chromatography *abbr*.: DHPLC; a technique used to distinguish between short double-stranded (ds) DNA molecules whose strands are complementary and those that contain one or more mismatched deoxynucleotides. The latter are heteroduplexes and have a lower melting temperature and behave differently on chromatography. The technique is used in screening for individuals who are heterozygotes at a specific genetic locus.

dendrite a freely branching protoplasmic process of a nerve cell that transmits nerve impulses to the body of the cell and that communicates functionally with dendrites or bodies of other nerve cells.

dendritic cell a type of cell derived from bone marrow that is characterized by branching projections and present in lymphoid tissue, skin, and squamous epithelium. It is the major antigen-presenting cell in the human body. This it does by engulfing protein antigens, cleaving them, and displaying the fragments on the cell surface by means of the **major histocompatibility complex** (MHC) molecules.

dendrogram any branching treelike diagram that illustrates the relationships between organisms or objects.

Denhardt's solution a solution containing Ficoll, polyvinylpyrrolidone, and bovine serum albumin; 1% (w/v) of each component gives 50× concentrated Denhardt's reagent. It is a constituent of solutions used as blocking reagents for nitrocellulose membranes in Northern and Southern hybridizations. [After David Tilton Denhardt (1939–), US biochemist.]

denitrification the reduction, especially by denitrifying bacteria, of simple inorganic nitrogen compounds, such as nitrates and nitrites, to gaseous products such as nitric oxide, nitrous oxide, and/or dinitrogen. *See also* **nitrate reduction**. *Compare* **nitrification**, **nitrogen fixation** (def. 1).

denitrifying bacteria soil bacteria that, in the absence of dioxygen, reduce nitrates and nitrites to gaseous products. *Compare* **nitrifying bacteria**.

de novo *Latin* anew, from the beginning; e.g. *de novo* synthesis.

densimeter *an alternative name for* **densitometer** (def. 2).

densitometer **1** *or* **photodensitometer** an apparatus for measuring the extent to which a material absorbs light (*see* **absorptiometer** (def. 1)) or reflects light (*see* **reflectometer**). It is useful for scanning chromatograms or electrophoretograms, for determining the opacity of solutions or suspensions, or for measuring the blackening of photographic films. **2** *or* **densimeter** an instrument for measuring the mass density or relative density of liquids or gases. —**densitometry** *n.*; **densitometric** *adj.*

density **1** **a** *or* **mass density** *symbol*: ρ; the mass of a substance per unit volume. **b** *or* **linear density** *symbol*: ρ_l; the mass of a substance per unit length. **c** *or* **surface density** *symbol*: ρ_A *or* ρ_S; the mass of a substance per unit area. *Compare* **relative density**. **2** the distribution of a scalar physical quantity per unit area of space (e.g. radiant energy density) or per unit volume (e.g. charge density). **3** the distribution of a vector physical quantity per unit area of space (e.g. electric current density, magnetic flux density). **4** **optical density**. *See* **absorbance**.

density functional theory a method of calculating the chemical properties of complex materials such as proteins. The complexity of using quantum wave-function calculations is simplified by the local density approximation, which substitutes the exchange-correlation energy density of an inhomogeneous system by that of an electron gas evaluated at the local density.

density-gradient centrifugation *see* **isopycnic centrifugation**.

density-gradient sedimentation equilibrium *see* **isopycnic centrifugation**.

density-marker bead any small coloured bead of accurately known mass density that is used for calibrating density gradients. Generally a set of several such beads, covering a range of densities, is used.

dentate having teeth or toothlike projections. *See also* **multidentate**.

dentatorubralpallidoluysian atrophy *abbr*.: DRPLA; a neurodegenerative genetic disease that shows genetic **anticipation** due to expansion of a trinucleotide repeat (CAG) in the atrophin 1 gene at locus 12p13.31.

denticity the number of distinct but linked atoms of a specified ligand binding to the central atom in a coordination entity. *Compare* **ligancy**.

dentine *or* **dentin** the hard, dense, calcified tissue of a tooth lying between the enamel and the pulp. It is 75% mineral, mainly hydroxyapatite.

dentinogenesis imperfecta *abbr*.: DGI; a group of genetically and clinically heterogeneous conditions characterized by abnormal dentine formation. DI type I is associated with **osteogenesis imperfecta**; types II and III are autosomal dominant conditions linked to the chromosomal locus 4q12-21 and are caused by the same mutation of the dentine sialophosphoprotein (*DSPP*) gene. It is likely that DGI type I and DGI type II are not separate diseases but rather the phenotypic variation of a single disease.

D-enzyme *or* **plant glucosyltransferase** an enzyme of plants that condenses short α1-4-glucans in the reaction α-glucan$_m$ + α-glucan$_n$ = α-glucan$_{(m+n-1)}$ + glucose. The product is long enough to be a substrate for starch phosphorylase.

deoxy+ *or (formerly)* **desoxy+** *prefix (in organic chemical nomenclature)* **1** denoting the replacement of a hydroxyl group by a hydrogen atom; *see also* **de+**. **2** (*abbr*.: d+) indicating the presence of one or more residues of 2-deoxy-D-ribose. *Compare* **ribo+** (def. 2). **3** used especially with hemoglobin, to signify absence or removal of dioxygen. *Compare* **oxy+**.

5′-deoxy-5′-adenosylcobalamin *or* **adenosylcobalamin** *see* **cobamide coenzyme**.

3-deoxy-D-*arabino*-(2-)heptulosonate 7-phosphate *or (less formally)* **3-deoxy-D-*arabino*-heptulosonate 7-phosphate** *abbr*.: DAHP; an early intermediate in aromatic amino acid biosynthesis by the **shikimate pathway** in autotrophic organisms.



α-pyranose form

deoxy-BigCHAP *N*,*N*-*bis*-(3-D-gluconamidopropyl)-(7-deoxy)cholamide; a nonionic detergent analogue of **CHAPS**, **CHAPSO**, and **BigCHAP**; aggregation number 8–16; CMC 1.1–1.4 mm.



deoxycholic acid 3*α*,12*α*-dihydroxy-5*β*-cholan-24-oic acid; one of the **bile acids** occurring as its conjugate with glycine or taurine in the bile of most mammals, including dog, goat, human, ox, sheep, and rabbit. The sodium salt, sodium deoxycholate, is used as a detergent. Aggregation number 3–12; CMC 2–6 mm.



deoxycorticosterone *abbr*.: DOC; Kendall's desoxy compound B, Reichstein's substance Q, 21-hydroxyprogesterone, 21-hydroxypregn-4-ene-3,20-dione; a **mineralocorticoid** hormone with little glucocorticoid activity, synthesized by the adrenal gland. For clinical purposes it may be administered as its ester, deoxycorticosterone acetate (*abbr*.: doca *or* DOCA).



deoxycytidine deaminase *see* **cytidine deaminase**.

deoxycytidylate deaminase *an alternative name for* dCMP deaminase.

3-deoxy-D-*manno*-octulosonic acid 8-phosphate synthase EC 4.1.2.16; *recommended name*: 2-dehydro-3-deoxyphosphooctonate aldolase; *other name*: phospho-2-keto-3-deoxyoctonate (*abbr*.: phosphoKDO) aldolase; an enzyme that catalyses the formation of 3-deoxy-D-*manno*-octulosonic acid 8-phosphate from D-arabinose 5-phosphate and phospho*enol*pyruvate with release of orthophosphate. It is the first step in the biosynthesis of the bacterial lipopolysaccharide, lipid A, and is required for cell growth.

deoxynojirimycin an antibiotic produced by *Bacillus* species, the reduced form of **nojirimycin**; it inhibits formation of N-linked complex oligosaccharides in culture.

deoxynucleoside *an alternative name for* **deoxyribonucleoside**.

deoxynucleotide *an alternative name for* **deoxyribonucleotide**.

deoxynucleotidyltransferase EC 2.7.7.31; *recommended name*: DNA nucleotidylexotransferase; *other names*: terminal addition enzyme; terminal transferase; terminal deoxyribonucleotidyltransferase. It is a Mg^{2+}-dependent polymerase enzyme that extends the 3′ end of a DNA strand one nucleotide at a time, independent of a template. It catalyses the reaction (if *n* nucleotides are added in all):

$$n \text{ (deoxynucleoside triphosphate)} + \text{(deoxynucleotide)}_m = n \text{ (pyrophosphate)} + \text{(deoxynucleotide)}_{m+n}.$$

deoxypentose any monosaccharide in which one alcoholic hydroxyl group of a pentose has been replaced by a hydrogen atom.

deoxypentose nucleic acid *former term for* **deoxyribonucleic acid**.

deoxypolymeric tailing extension of the 3′ end of a strand of DNA, or of each strand of (a fragment of) duplex DNA, by a tail comprising a homooligomer or homopolymer of a deoxyribonucleotide. It is effected by the enzyme **deoxynucleotidyl transferase**. The process is useful for forming cohesive termini to DNA fragments in the preparation of **recombinant DNA**. *See* **cohesive end**.

deoxyribonuclease *abbr*.: DNase (*or sometimes* DNAse *or* DNAase); any enzyme within subclass EC 3.1, esterases, that catalyses the hydrolytic cleavage of phosphodiester linkages in DNA. If such an enzyme catalyses endonucleolysis (i.e. hydrolysis of nonterminal phosphodiester linkages) it is termed an **endodeoxyribonuclease**; if it catalyses exonucleolysis (i.e. hydrolysis of terminal linkages) it is termed an **exodeoxyribonuclease**. *See also* **AP endonuclease**, **crossover point**, **deoxyribonuclease I**, **deoxyribonuclease II**, **deoxyribonuclease III**, **deoxyribonuclease IV (phage T4-induced)**, **deoxyribonuclease V**, **deoxyribonuclease X**, **deoxyribonuclease KI**, **deoxyribonuclease (pyrimidine dimer)**, **endonuclease**, **exodeoxyribonuclease I**, **exodeoxyribonuclease V**, **exodeoxyribonuclease VII**, **exodeoxyribonuclease (phage SP3-induced)**, ***myt5***, **restriction enzyme**.

deoxyribonuclease I EC 3.1.21.1; *other names*: pancreatic DNase; DNase; thymonuclease. An enzyme that catalyses the endonucleolytic cleavage of DNA to 5′-phosphodinucleotide and 5′-phosphooligonucleotide end products. It shows a preference for double-stranded DNA. *See also* **streptodornase**.

deoxyribonuclease II EC 3.1.22.1; *other names*: DNase II; pancreatic DNase II. An enzyme that catalyses endonucleolytic cleavage of DNA to 3′-phosphomononucleotide and 3′-phosphooligonucleotide end products.

deoxyribonuclease III EC 3.1.11.2; *other name*: exonuclease III. An enzyme that catalyses exonucleolytic degradation of double-stranded DNA progressively in the 3′- to 5′-direction, releasing 5′-phosphomononucleotides.

deoxyribonuclease IV (phage T4-induced) EC 3.1.21.2; *other names*: endodeoxyribonuclease IV (phage T4-induced); endonuclease IV. An enzyme that catalyses endonucleolytic cleavage of DNA to 5′-phosphooligonucleotide end products.

deoxyribonuclease V EC 3.1.22.3; *other name*: endodeoxyribonuclease V. An enzyme that catalyses endonucleolytic cleavage at apurinic or apyrimidinic sites within DNA to yield products with a 3′-phosphate. It is involved in DNA repair. The enzyme from *Escherichia coli* consists of three subunits, RECB, RECC, and RECD, also known as the β chain, γ chain, and α chain, respectively.

deoxyribonuclease X EC 3.1.22.5; an enzyme that catalyses endonucleolytic cleavage of supercoiled plasmid DNA to produce linear DNA duplexes.

deoxyribonuclease K1 *or Aspergillus* **deoxyribonuclease K1** EC 3.1.22.2; *other name*: *Aspergillus* DNase K1. An enzyme that catalyses endonucleolytic cleavage of DNA to 3′-phosphomononucleotide and 3′-phosphooligonucleotide end products.

deoxyribonuclease (pyrimidine dimer) EC 3.1.25.1; *other name*: endodeoxyribonuclease (pyrimidine dimer). An enzyme involved in DNA repair; it can induce single-strand breaks in DNA on the 5′-side of pyrimidine dimers in the strand containing the lesion, after formation of the dimers as a result of, e.g., ultraviolet radiation.

deoxyribonucleate 1 *abbr*.: DNA; any anionic form of deoxyribonucleic acid. **2** any salt of deoxyribonucleic acid.

deoxyribonucleic acid *former names*: desoxyribonucleic acid *or* thymonucleic acid; *also* deoxypentose nucleic acid *or* deoxyribose nucleic acid *or* desoxyribose nucleic acid *or* thymus nucleic acid. *See* **DNA**.

deoxyribonucleoprotein *abbr*.: DNP; any conjugated protein that contains DNA as the nonprotein moiety.

deoxyribonucleoside *or* **deoxynucleoside** any **nucleoside** (def. 1) in which the glycose moiety is 2-deoxy-β-D-ribofuranose.

deoxyribonucleoside monophosphate kinase any of several enzymes within sub-subclass EC 2.7.4 that catalyse the transfer of a phosphoric residue from a nucleoside triphosphate to a deoxyribonucleoside monophosphate, e.g. from ATP to a deoxyribonucleoside phosphate to form ADP and a deoxyribonucleoside diphosphate.

deoxyribonucleotide *or* **deoxynucleotide** a deoxyribonucleoside in ester linkage to phosphate, commonly at the 5′ position of its deoxyribose moiety. *See* **nucleotide**.

deoxyribose 1 *symbol*: dRib; *the trivial name for* 2-deoxyribose; 2-deoxy-*erythro*-pentose. The D enantiomer, as 2-deoxy-β-D-ribofuranose, forms the glycose moiety of all deoxyribonucleosides, deoxyribonucleotides, and deoxyribonucleic acids. **2** 3-deoxyribose (*see* **cordycepose**).



2-deoxy-α-D-ribofuranose

deoxyribose nucleic acid *former name for* **deoxyribonucleic acid**.

deoxyriboside any glycoside or glycosylamine in which deoxyribose forms the glycose moiety, especially a deoxyribonucleoside.

deoxyribosome *see* **nu body**.

deoxyribosylthymine *an alternative name for* thymidine.

deoxyribotide any deoxyriboside esterified with phosphate at the 5′ position on its ribose moiety, especially a deoxynucleotide.

deoxyribovirus *an alternative name for* **DNA virus**.

deoxyribozyme *see* **DNAzyme**.

deoxysaccharide *or* **deoxysugar** any saccharide in which one alcoholic hydroxyl group has been replaced by a hydrogen atom.

depactin a protein isolated from starfish eggs, able to depolymerize F-actin, and to inhibit the extent of actin polymerization. It binds to actin monomers from filaments and in solution.

DEPC *abbr. for* diethylpyrocarbonate.

dependent form of glycogen synthetase the phosphorylated form of the enzyme glycogen synthetase that is ‘dependent’ for its activity on the presence of glucose 6-phosphate, a positive effector.

dependent variable any variable in a mathematical statement or equation whose value depends on the values taken by the related independent variables.

dephospho-[reductase kinase] kinase EC 2.7.1.110; *other name*: reductase kinase kinase; an enzyme that catalyses the phosphorylation of dephospho-[[3-hydroxy-3-methylglutaryl-CoA reductase (NADPH)] kinase] by ATP with release of ADP. It is involved in the regulation of **hydroxymethylglutaryl-CoA reductase** (HMGCoA reductase). By phosphorylating reductase kinase, it activates that enzyme to phosphorylate HMGCoA reductase, thereby inactivating the latter.

dephosphorylation any reaction in which phosphate groups are removed chemically or enzymatically. In gene cloning the removal of 5′ phosphate from cloning vectors by treatment with calf intestinal phosphatase (CIP) or bacterial alkaline phosphatase (BAP) prevents religation of the vector ends and increases the probability of cloning a DNA insert.

depolarization *or* **depolarisation 1** a reduction in the electric potential measured across a cell membrane, especially that brought about in a nerve or muscle cell by an electrical stimulus or a drug. **2** the decrease of the angle of polarization of polarized light so that it appears altered when viewed through an analyser. *See also* **fluorescence depolarization**.

depolarization ratio *or* **depolarisation ratio** *(in light scattering)* the ratio of the horizontally to the vertically polarized components of the light scattered by scattering particles when illuminated by unpolarized light. If the scattering particles are isotropic the depolarization ratio will be zero; if they are anisotropic it will not be zero.

deproteinization *or* **deproteinisation** the process of removing protein from a biological sample, either by precipitation of protein from solution or by hydrolysis of protein with proteolytic enzymes.

depside any of a family of natural or artificial compounds derived from two or more molecules of various trihydroxybenzoic acids by esterification of a carboxyl group on one molecule with a hydroxyl group on another molecule (which may or may not be of the same structure as the first). By analogy with peptides, depsides derived from two, three, etc., or several trihydroxybenzoic acid units may be termed **didepside**, **tridepside**, etc., or **polydepside**, respectively. Depsides occur widely in lichens and also as components of some tannins.

depsidone any compound derived from two phenolcarboxylic acid molecules (which may or may not be the same molecules) that are joined together by both an ester and an ether link. Such substances are found in lichens.

depsipeptide any linear or macrocyclic compound containing (alternating) amino-acid and hydroxy-acid residues, linked by amide, *N*-methylamide, and ester bonds. Among the naturally occurring **cyclodepsipeptides** (sometimes alternatively termed peptolides) are the antibiotics **valinomycin**, the **enniatins**, and the monamycins.

depth of coverage the number of times a genome is sequenced to ensure data accuracy and to help assembly of the DNA fragments into the correct order. Half-shotgun coverage implies 4–5-fold sequencing, to provide a robust framework for fragment assembly; full-shotgun coverage implies 8–9-fold sequencing, to reduce ambiguities and errors, and to close gaps. *See also* **draft genome sequence**, **finished genome sequence**, **shotgun sequencing**.

depurinate to remove purine residues from DNA or another polynucleotide by exposure to weak acid. The reaction may be used in preparation for **Southern blotting** when partial depurination of large DNA molecules (>15 kb) followed by treatment with a strong base causes hydrolysis of the phosphodiester backbone at sites of depurination. The resulting DNA fragments are more readily transferred from the agarose gel to the membrane by capillary transfer. **—depurinated** *adj.*; **depurination** *n.*

depyrimidinate to remove pyrimidine residues from a polynucleotide. **—depyrimidinated** *adj.*; **depyrimidination** *n.*

derepression the phenomenon in which a repressor is prevented from interacting with the operator component of an **operon** and an increase in the synthesis of a gene product thereby occurs. With an inducible enzyme, the inducer derepresses the operon. Derepression may also result from mutations, either in the **regulator(y) gene**, thus blocking repressor synthesis, or in the operator gene, thus rendering it insensitive to the repressor.

deRib *(sometimes) symbol for* 2-deoxy-D-ribose (dRib is the correct symbol).

derivative 1 any compound that may, at least theoretically, be formed from another compound to which it is structurally related. **2** *see* **derivative of a function**.

derivative of a function *(in mathematics)* the limit of the ratio of an increment of a dependent variable to the corresponding increment of an associated independent variable as the latter increment tends to zero.

derivatize *or* **derivatise** to convert a chemical compound into a derivative. **—derivatization** *or* **derivatisation** *n.*

derived database a database derived from other resources but including relationships or data not found in those resources. There are a number of examples as follows. Swiss-Prot was originally derived from sequences in the PIR-PSD, but included additional annotation and an EMBL-like format. Blocks-format-PRINTS is derived from motifs in PRINTS, but includes Blocks scoring methods and a Swiss-Prot-compatible format. eMOTIF is derived from motifs in Blocks and PRINTS using the emotif-maker algorithm. CDD (conserved domain database) is derived from protein domains in Pfam, SMART (simple modular architecture research tool), and COG, with links to the Cn3D structure viewer and domain searches via BLAST. InterPro is a composite of protein families from sources such as PROSITE, PRINTS, Pfam, and ProDom, providing sibling and partonomic links between families, with functional links to GO (gene ontology) and structural links to PDB (protein database). *See also* **composite database**, **partonomy**.

dermaseptin any of a series of antimicrobial peptides derived from amphibian skin. Dermaseptins s1–5 constitute a family of cationic lysine-rich amphipathic antifungal peptides of 28– 34 residues. Presumed to protect the naked frog skin from infections, they have wider application, being the first vertebrate peptides to show lethal effects against the filamentous fungi that can cause infections in immunodeficiency syndrome, or during the use of immunosuppressive agents. Dermaseptin is classified in the TC system under number 1.C.52. *Compare* **magainin**.

dermatan sulfate *or* **chondroitin sulfate B** any of a group of glycosaminoglycans with repeats consisting of $\beta1\rightarrow4$-linked L-iduronyl-($\beta1\rightarrow3$)-*N*-acetyl-D-galactosamine 4-sulfate units. They are important components of ground substance or intercellular cement of skin and some connective tissues (*see* **matrix** (def. 3)). They usually occur attached to proteins as proteoglycans, the mode of linkage being the same as for **chondroitin sulfate**. A hereditary deficiency in the ability to degrade dermatan sulfate characterizes certain types of **mucopolysaccharidosis**.

dermatosparaxis a disorder of cattle, sheep, cats, and dogs characterized by generalized skin fragility, joint laxity, and early death from sepsis. In cattle it is caused by inactivating mutations in procollagen N-endopeptidase.

dermis *or* **corium** the thick layer of tissue forming part of the skin and lying beneath the epidermis. It consists of loose connective tissue in which are blood capillaries, smooth-muscle fibres, sweat glands and sebaceous glands with their ducts, hair follicles, and sensory nerve endings. **—dermal**, **dermic** *adj.*

dermorphin any of a group of heptapeptide amides of the general structure H-Tyr-DAla-Phe-Gly-Tyr-Xaa-Ser-NH$_2$, isolated from the skin of frogs of the genus *Phyllomedusa,* and from some other amphibians; they show high- and long-lasting opiate-like activity.

DES *abbr. for* diethylstilbestrol.

des+ *prefix* **1** (in the trivial name of a polycyclic compound, e.g. a steroid) indicating the removal of a terminal ring, with addition of a hydrogen atom at each junction arm with the adjacent ring; it should be followed by the italic capital letter designating the terminal ring in question, e.g. des-*A*-androstane. **2** (in the trivial name of a polypeptide) indicating the removal of an amino-acid residue, terminal or otherwise; it should be followed by the name or symbol for the amino acid in question and an arabic number indicating its position in the normal polypeptide, e.g. des-7-proline-oxytocin, or des-Pro^7-oxytocin. **3** indicating the removal of a specified atom or group from a molecule of an indicated substance; *see* **desamido+**, **desthio+**; *see also* **descarboxy-clotting factor**. **4** *(formerly) a variant of* **de+** (still preferred in some languages, e.g. French, German).

desalinate to remove salt, especially from seawater to render it suitable for drinking or irrigation. *Compare* **desalt**. **—desalination** *n.*

desalt to remove small, usually inorganic ions from a sample. Methods that may be used include electrodialysis, electrophoresis, gel filtration, and ion-exchange chromatography. *See also* **deionize**. *Compare* **desalinate**.

desamidation the hydrolysis of one or more carboxamide groups in a molecule to carboxyl groups.

desamido+ *prefix* indicating **desamidation** of a molecule, especially of a peptide.

desaturase *general name for* any enzyme catalysing a desaturation reaction. The name specifically often refers to any of several fatty-acyl-CoA desaturases, enzymes coming within sub-subclass EC 1.14.99; in animals these are associated with the endoplasmic reticulum, require dioxygen, and insert double bonds into saturated and *Z*(i.e. *cis*)-unsaturated fatty acids. They also occur in higher plants, protozoa, and fungi. These enzymes are specific for position in the fatty-acyl chain, and are termed Δ^5-desaturase, Δ^9-desaturase, and so on, according to the distance from the carboxyl carbon atom to the first carbon atom of the double bond. In mammals, there is a lack of any desaturase that inserts a double bond nearer to the terminal methyl group of the fatty acid than nine carbon atoms, hence the need for *n*-3 and *n*-6 precursor fatty acids (the **essential fatty acids**). *See also* **linoleic family**, **linolenic family**.

desaturation **1** any process or reaction in which an organic compound becomes **unsaturated** (def. 2), e.g. by removal of two hydrogen atoms, or a hydrogen atom and a hydroxyl group, from adjacent carbon atoms. **2** any process in which ligands are removed from a macromolecule so that all the binding sites for that ligand are no longer occupied. **—desaturate** *vb.*; **desaturated** *adj.*

descarboxy-clotting factor any of the abnormal blood clotting factors containing glutamic- instead of γ-carboxyglutamic-acid residues. They are formed in animals deficient in vitamin K, or during administration of vitamin K antagonists. *Compare* **PIVKA.**

descending chromatography any chromatographic technique in which a liquid mobile phase runs downwards through the supporting matrix.

descriptive name name of an organic substance that is more descriptive of action or function and often more convenient than its **trivial name**, **semisystematic name**, **systematic name**, or other type of name permitted by the rules of chemical nomenclature.

desensitization *or* **desensitisation** **1** a spontaneous decline in response resulting from continuous application of agonist, or to repeated applications or doses; such attenuation may result within minutes of prior stimulation, or may take hours to develop. It is recommended that this term be used where **fade** or **tachyphylaxis** are considered to involve the receptor itself, or to be a direct consequence of receptor activation. **Homologous desensitization** results from prior stimulation with the receptor's own agonist, whereas **heterologous desensitization** results from the activity of other agonists acting at other receptors. On the longer time scales, desensitization may result from receptor internalization in **coated pits**, and over shorter time scales from modification of the receptor in a way that uncouples it from signal transduction systems, e.g. by phosphorylation (*see* **adrenergic receptor kinase**). **2** the modification of an enzyme, either by mutation or chemically, so that it no longer responds to **effectors** but retains its catalytic activity. **3** the suppression of an established (immunological) hypersensitivity by injection of antigen, usually in very small doses. In delayed hypersensitivity the antigen reacts with sensitized cells, so neutralizing them. In immediate hypersensitivity the antigen either causes blocking antibody production (in atopy) or forms nontoxic complexes with existing antibodies (in anaphylaxis). **—desensitize** *vb.*; **desensitized** *adj.*

deserpidine desmethoxyreserpine, 11-desmethoxy-*O*-(3,4,5-



trimethoxybenzoyl)reserpic acid methyl ester; an alkaloid derived from roots of *Rauwolfia canescens* with pharmacological actions similar to the parent methoxy compound, **reserpine**.

desferrioxamine a siderophore of the hydroxamate type derived from *Streptomyces pilosus* that forms a chelate complex specifically with Fe(III) ions, yielding **ferrioxamine**. It is used parenterally to treat acute iron poisoning and to reverse iron and aluminium overload. Its natural function is to transport iron into the microbial cell and/or to make iron available for the synthesis of heme.



desiccant a substance such as $CaCl_2$ or P_2O_5 that has a high affinity for water and is used to remove moisture from a gas or another substance; a drying agent.

desiccate to remove (most of) the water from a substance or material containing moisture, especially with the aid of a **desiccant**; to dry. **—desiccation** *n.*

desiccator an apparatus in which to effect desiccation.

desmin *or (formerly)* **skeletin** a 50–55 kDa protein found in the Z disk of skeletal and cardiac muscle cells, and in **intermediate filaments** in smooth muscle and non-muscle cells.

desmo+ *or (before a vowel)* **desm+** *comb. form* denoting ligament or bond.

desmofibrin a stabilized insoluble fibrin polymer formed from soluble fibrin polymer (*see* **fibrin**) in the final stage of **blood coagulation** by the action of factor XIII (fibrin-stabilizing factor) (*see* **blood coagulation**).

desmoglein a type I **membrane protein** of the mature desmosomal junction, involved in the interaction of plaque proteins and intermediate filaments, mediating cell–cell adhesion. It contains **cadherin**-like repeats.

desmolase *former term for* any enzyme that catalyses the formation or rupture of a carbon–carbon bond.

desmoplakin any of several intracellular desmosome proteins that are probably involved in attaching intermediate filaments (e.g., keratin filaments in epithelial cells, desmin filaments in heart cells) to the desmosome. *See also* **plakoglobin** (for desmoplakin III).

desmopressin 1-(3-mercaptopropanoic acid)-8-D-arginine vasopressin, desamino-[8-D-arginine]vasopressin; a synthetic analogue of **vasopressin** with greater antidiuretic activity and less pressor activity than the parent compound.

desmosine 4-(4-amino-4-carboxybutyl)-1-(5-amino-5-carboxypentyl)-3,5-bis(3-amino-3-carboxypropyl)pyridinium; a tetra(α-amino acid) isolated from hydrolysates of the fibrous protein **elastin**. Desmosine and **isodesmosine** covalently cross- link two or more polypeptide chains in this protein, the postulated mode of formation of both compounds being condensation of two residues of **allysine** in one polypeptide chain with one allysine and one lysine residue in a second chain.



desmosome *or* **macula adherens** a patchlike intercellular junction found in vertebrate tissue. It consists of parallel zones of two cell membranes, separated by an interspace of 25–35 nm and having dense fibrillar plaques in the subjacent cytoplasm. The interspace is continuous with the intercellular space and contains a dense, central plaque of material rich in protein. These proteins are known as linker proteins and consist of cell–cell adhesion molecules of the **cadherin** type. Desmosomes are important in cell-to-cell adhesion and are particularly numerous in stratified squamous epithelium that is subject to mechanical stress. A similar type of intercellular junction, the **zona adherens**, sometimes also referred to as a desmosome, encircles the cell like a belt. **—desmosomal** *adj.*

desmotubule *see* **plasmodesma**.

desorb to remove adsorbed substances from a surface. **—desorption** *n.*; **desorbed** *adj.*

desosamine 3,4,6-trideoxy-3-(dimethylamino)-D-*xylo*-hexose; an aminodeoxy sugar component of several **macrolide** antibiotics, including **erythromycins** A, B, and C.



β-D anomer

desoxy+ *an obsolete variant of* **deoxy+**.

destain to remove dye in excess of that required to stain specifically the material in question, e.g. in staining proteins in an electrophoretogram. **—destaining** *n.*

destainer any apparatus used for removing excess dye electrophoretically from stained gels.

desthio+ *prefix* indicating the replacement of a sulfur atom by two hydrogen atoms.

destrin an **actin binding protein** similar to **cofilin** with wide tissue distribution. It severs actin filaments and binds to actin monomers.

Desulfovibrio a genus of Gram-negative, obligately anaerobic, asporogenous, chemotrophic bacteria that obtain energy by anaerobic respiration using reducible inorganic sulfur compounds.

desumoylation *see* **SUMO**.

detergent **1** a cleansing agent, especially a soap or (usually synthetic) soaplike substance that, when used in aqueous solution, cleanses by reducing surface tension. **2** having the properties of a detergent. *See also* **BigCHAP**, **Brij**, **$C_x E_y$**, **cetyltrimethylammonium bromide**, **CHAPS**, **CHAPSO**, **cholic acid**, ***n*-decyl-β-D-glucopyranoside**, ***n*-decyl-β-D-maltopyranoside**, **deoxyBigCHAP**, **deoxycholic acid**, **digitonin**, **dodecylglucopyranoside**, **dodecylmaltoside**, ***n*-dodecyl-*N, N*-dimethylglycine**, **Genapol**, **glycocholate**, **glycodeoxycholate**, **heptyl glucoside**, **heptyl thioglucoside**, **hexyl glucoside**, **lauryldimethylamine oxide**, **sodium dodecylsulfate**, **Lubrol**, **Mega-8**, **nonyl glucoside**, **NP-40**, **octyl glucoside**, **octyl thioglucoside**, **taurocholate**, **taurodeoxycholate**, **Triton**, **Tween**, **Zwittergent**.

detergent gel electrophoresis *an alternative name for* **SDS-polyacrylamide gel electrophoresis**.

deteriosome a microvesicle that is found in eukaryotic cells and is rich in phospholipase A_2 (*see* **phospholipase**). It is believed to represent a stage in membrane degradation.

deterministic a property or relationship that holds to some defined rule or formula. For example, the equation $v = f\lambda$ describes the relationship between the velocity (v), frequency (f) and wavelength (λ) of light. **–deterministically** *adv.*

detoxication *or (sometimes)* **detoxification**; the act or process of counteracting or rendering innocuous a poisonous substance. In an organism this involves various enzymic reactions by which harmful compounds, whether produced in the organism or introduced into it, are converted into (normally) less harmful substances and into more readily excretable products. Enzymic detoxication is brought about by chemical modification (frequently by oxidation) and/or conjugation with a normal metabolite. The enzymic process does not always result in a less toxic product and the term is sometimes restricted to those instances in which a less toxic product actually occurs, as distinct from **intoxication**. Enzymic detoxication may be divided into two phases. Phase 1 concerns metabolic transformation by a wide variety of oxidations, reductions, hydrolyses, etc., usually resulting in the introduction of functional groups that increase the polarity of the molecule and act as centres for phase 2 reactions. Phase 2 involves conjugation, in which the foreign compound itself or the compound resulting from phase 1 reactions is combined with endogenous substances, such as acetate, glucuronate, sulfate, or an amino acid, or is alkylated by introduction of methyl, or other groups, to form the more water-soluble ultimate excretory metabolite. *See also* **lethal synthesis**. **—detoxicate** *vb.*

detoxification **1** the removal of poison. **2** *(sometimes)* **detoxication**.

detoxify **1** to remove a poison or the effect of a poison. **2** to bring about **detoxication**.

deuterate to combine or label with **deuterium**. **—deuteration** *n.*; **deuterated** *adj.*

deuterium *symbol*: ^{2}H *or (deprecated)* D; a stable isotope of hydrogen, relative atomic mass 2.014, sometimes known as heavy hydrogen. Its relative abundance in natural hydrogen is 0.015 atom percent. It was much used as a tracer in studies of the chemistry and biochemistry of compounds containing nonlabile hydrogen before the ready availability of tritium and carbon-14; its use continues in tracer experiments with detection by NMR spectroscopy, and where the use of radioactive compounds is contra-indicated. *See also* **heavy water**, **protium**, **tritium**.

deuterium (discharge) lamp a **hydrogen (discharge) lamp** filled with dideuterium in place of dihydrogen; this substitution increases the intensity 3-to 5-fold for the same power consumption and extends the upper limit of the continuum further into the visible range.

deutero+ *or (before a vowel)* **deuter+** *comb. form* **1** denoting that an indicated chemical compound or class of compound contains deuterium. **2** denoting second or secondary.

deuteron **1** *symbol*: ^{2}H$^+$; the cation derived from an atom of deuterium. *Compare* **hydron**. **2** *symbol*: d; a particle of nucleon number two, having a charge equal and opposite to that of an **electron** and having a mass of 2.0136 dalton.

develop **1** to process an exposed photographic film with a **developer** in order to render the image visible. **2** to render visible the colourless substances on a chromatogram or electrophoretogram by treatment with a stain or chromogenic reagent. **3** to cause a solvent to flow through a chromatographic support in order to separate the components of an applied mixture. **4** *(of a cell, organ, or organism)* to undergo or cause to undergo a series of orderly changes whereby a mature state is attained. **—development** *n.*

developer **1** a solution of a reducing agent that renders visible the latent image on an exposed photographic film or paper by reducing to metallic silver those areas of silver halide that had been exposed to light. **2** a solution of a stain or chromogenic reagent used to render visible the colourless substances on a chromatogram or electrophoretogram.

Dewar flask *or* **Dewar** a double-walled vessel or flask, usually of silvered glass but sometimes of metal, in which the space between the walls is evacuated to prevent conduction and convection of heat between the inner and outer walls. It is used to maintain the contents at temperatures either higher or lower than that of the environment. [After its inventor Sir James Dewar (1842–1923), British chemist and physicist.]

dexamethasone 9α-fluoro-16α-methylprednisolone; a synthetic **glucocorticoid** with negligible mineralocorticoid activity that has actions similar to adrenal corticosteroids.



DEXD/H box an element of protein sequence that is a variant of the **DEAD box** in which the third residue is variable and the fourth residue can be D or H. It is present in several putative NTP-dependent RNA helicases that frequently form part of large ribonucleoprotein assemblies (e.g. spliceosomes), and are involved in many aspects of RNA turnover and in replication of many viruses. *See* **Dicer**.

dextr+ *see* **dextro+**.

dextran any glucan of very high relative molecular mass and consisting of linear chains of $\alpha(1\to6)$-linked D-glucose residues, often with $\alpha(1\to2)$- or $\alpha(1\to3)$-branches. Native dextran, produced by a number of species of bacteria of the family Lactobacilliaceae, is a polydisperse mixture of components of M_r $<10^3$ to $>10^7$. Specific fractions of (partially hydrolysed) native dextran that have a narrow and well-defined size distribution may be designated by a numeric suffix equal to $10^{-3} \times$ mass-average molar mass; e.g. Dextran T 500. Dextrans used in medicine are acid-degraded native dextrans.

dextranosome a **lysosome** loaded with dextran. It has higher than normal density.

dextransucrase EC 2.4.1.5; *systematic name*: sucrose:1,6-α-D-glucan 6-α- D-glucosyltransferase; *other name*: sucrose 6-glucosyltransferase. An extracellular bacterial enzyme that catalyses the reaction:

$$\text{sucrose} + (1,6\text{-}\alpha\text{-D-glucosyl})_n = \text{D-fructose} + (1,6\text{-}\alpha\text{-D-glucosyl})_{n+1}.$$

Streptococcus mutans dextransucrases are of several types: dextransucrase S produces water-soluble glucans ($\alpha(1\to6)$-linked glucose); dextransucrase I produces water-insoluble glucans ($\alpha(1\to3)$-linked glucose and some $\alpha(1\to6)$-linkages); and dextransucrase SI produces both types; the sequences are related. *See also* **sucrase** (def. 3).

dextrin any of the poly-D-glucosides of intermediate chain length that are formed during the hydrolytic degradation of starch or glycogen by enzymes, acid, or heat. *See also* **limit dextrin**, **Schardinger dextrin**.

α-dextrin endo-1,6-*α*-glucosidase EC 3.2.1.41; *other names*: pullulanase; pullulan 6-glucanohydrolase; limit dextrinase; debranching enzyme; amylopectin 6-glucanohydrolase; the starch-debranching enzyme, which hydrolyses (1→6)-α-D-glucosidic linkages in pullulan and starch to form maltotriose.

dextro- *symbol*: *d-*; a prefix, no longer used, to denote a compound that is **dextrorotatory**; the dextrorotatory enantiomer of compound A is now designated as (+)-A.

dextro+ *or (before a vowel)* **dextr+** *comb. form* denoting on or towards the right. *Compare* **levo+**.

dextroamphetamine (*S*)-methylbenzeneethanamine; the potent (–)-stereoisomer of **amphetamine**. One proprietary name is Dexamphetamine.



dextrorotatory *or (US)* **dextrorotary** **1** *symbol*: (+)- *or (formerly) d*-; describing a chemical compound that rotates the plane of polarization of a transmitted beam of plane-polarized light to the right, i.e. in a clockwise direction as viewed by an observer looking toward the light source. **2** describing any rightwards or clockwise rotation. *Compare* **levorotatory**. —**dextrorotation** *n.*

dextrorphan *see* **levorphanol**.

dextrose *traditional name (still used in pharmacy)* for D-glucose, D-(+)-glucopyranose, the dextrorotatory component of **invert sugar**. *Compare* **levulose**.

DFP *abbr. for* diisopropyl fluorophosphate.

dG *symbol for* a residue of the deoxynucleoside deoxyguanosine (alternative to dGuo).

DGGE *abbr. for* denaturing gradient gel electrophoresis.

dGMP *abbr. for* deoxyguanosine monophosphate, the common name for 2′-deoxyguanosine 5′-phosphate; 2′-deoxy-5′-guanylic acid; guanine 2′-deoxyriboside 5′-phosphate.

dGuo *symbol for* a residue of the deoxynucleoside deoxyguanosine; 2′-deoxyribosylguanine; guanine 2′-deoxyriboside (alternative to dG).

dGuo5′*P* *symbol for* deoxyguanosine 5′-phosphate.

dGTP *abbr. for* deoxyguanosine triphosphate, the common name for 2′-deoxyguanosine 5′-triphosphate, 2′-deoxy-5′-guanylyl diphosphate, guanine 2′-deoxyriboside 5′-triphosphate.

DH+ *abbr. for* dehydro+ *or* dihydro+ *or* dihydroxy+, sometimes prefixed to chemical names or alternatives. Its use is deprecated.

DH5 alpha a strain of *Escherichia coli* used in gene cloning using pUC and similar plasmid vectors and permitting **alpha complementation**.

DHAS *abbr. for trans*-dehydroandrosterone, i.e. **dehydroepiandrosterone**.

DHEA *abbr. for* dehydroepiandrosterone.

DHFR *abbr. for* dihydrofolate reductase.

DHPLC *abbr. for* denaturing high-performance liquid chromatography.

DHPR *abbr. for* dihydropteridine reductase.

DHU arm *abbr. for* dihydrouridine arm of transfer RNA.

dhurrin L-*p*-hydroxymandelonitrile-*β*-D-glucopyranoside; a glucoside from the fruit of young *Sorghum vulgare*. *See also* **amygdalin**.



di+ *comb. form* **1** *(in chemical nomenclature)* (*distinguish from* **bis+** (def. 2)) **a** indicating the presence in a molecule of two identical unsubstituted groups, e.g. diethylsulfide, 1,3-dihydroxyacetone. **b** indicating the presence in a molecule of two identical inorganic oxoacid residues in anhydride linkage, e.g. adenosine 5′-diphosphate. **2** *or* **bis+** (def. 1) denoting two, twofold, twice, doubled.

diabetes any clinical condition characterized by thirst and the passing of large volumes of dilute urine, especially **diabetes mellitus**. *See also* **diabetes insipidus**. —**diabetic** *adj., n.*

diabetes-associated peptide *abbr*.: DAP; *another name for* **amylin**.

diabetes insipidus a disease characterized by thirst and the excretion of large volumes of hypotonic (dilute) urine, caused by any lesion, nervous or endocrine, that interferes with the normal secretion of **vasopressin** by the posterior pituitary gland. *See also* **nephrogenic diabetes insipidus**.

diabetes mellitus *or* (commonly) **diabetes** a disorder in which the level of blood glucose is persistently above the normal range. Two main forms of the disease are generally recognized. **Type 1 diabetes mellitus**, the so-called juvenile type, often manifests itself in children and young adults. There is a marked failure to release **insulin** from the B cells of the **islets of Langerhans** in the pancreas, and frequently an almost complete absence of insulin in the B cells. The only effective treatment is administration of insulin, hence the frequent designation of this form as **insulin-dependent diabetes mellitus** (*abbr*.: IDDM). Type 1 diabetes mellitus is thought to arise in many patients from autoimmune attack on the B cells. Without insulin a severe **ketoacidosis** rapidly develops, with tissue wasting resulting from breakdown of muscle protein and hydrolysis of triacylglycerols in fat depots. **Type 2 diabetes mellitus** or **maturity onset diabetes** tends to manifest itself in adults, especially if obese, though the distinction between types 1 and 2 is blurred. In type 2 there may often be secretion of significant amounts of insulin, but for reasons not well understood these are not fully effective. There is by definition a failure to lower blood glucose adequately after a **glucose tolerance test**; patients of this type seldom develop severe ketoacidosis. **Tolbutamide** and related sulfonylureas can be used to stimulate insulin release in type 2. In both types of diabetes mellitus there may develop serious complications, including neuropathy, retinopathy, atherosclerosis, peripheral vascular disease, and nephropathy. Type 2 diabetes mellitus is also referred to as **non-insulin-dependent diabetes**.

diabetes mutation a mutation first identified in mice that spontaneously develop diabetic symptoms. It appears to be a mutation in the **leptin receptor** gene.

diabetic a sufferer from diabetes.

diabetogenic causing or being caused by **diabetes**.

diabetogenic hormone *former term for* **somatotropin**.

Diablo *abbr. for* direct IAP-binding protein with low pI; *other name*: second mitochondria-derived activator of caspases (*abbr*.: Smac); a mammalian proapoptotic protein that is released, like apoptosis inducing factor (AIF) and cytochrome *c*, from the intermembrane space of mitochondria on induction of **apoptosis**. It binds **IAP** and abrogates the inhibition of caspases 3 and 9.

diabolic a term suggested to categorize enzymes that appear to serve a complex or multiple metabolic function. *See also* **amphibolic**.

diacetylchitobiose 4-*O*-(2-acetamido-2-deoxy-*β*-D-glucopyranosyl)-2-acetamido-2-deoxy-D-glucose; the repeating unit of **chitin**. *See also* **chitobiose**.

diacetylmorphine *other names*: diamorphine, heroin; a semisynthetic narcotic analgesic derived from **morphine** by acetylation and used either as the free base or its hydrochloride. It has more potent analgesic activity than the parent compound but otherwise its actions are similar. Noted for its dependence-inducing actions and potential for abuse, it is a controlled substance under the US Code of Federal Regulations; import and manufacture of diacetylmorphine and its salts are forbidden in the USA and other countries. *See also* **codeine**.

diacylglycerol *or (formerly)* **diglyceride** any (1,2- or 1,3-) diester of glycerol and two fatty acids; the latter may be identical or different.

diacylglycerol *O*-acyltransferase EC 2.3.1.20; *other name*: diglyceride acyltransferase; an enzyme that catalyses the synthesis of triacylglycerol from acyl-CoA and 1,2-diacylglycerol with release of CoA.

diacylglycerol cholinephosphotransferase EC 2.7.8.2; *other names*: phosphorylcholine–glyceride transferase; alkyl-acylglycerol cholinephosphotransferase; 1-alkyl-2-acetylglycerol cholinephosphotransferase; an enzyme of the pathway for the *de novo* synthesis of phosphatidylcholines. It catalyses the formation of a phosphatidylcholine from CDPcholine and 1,2-diacylglycerol with release of CMP.

diacylglycerol kinase *abbr*.: DGK; EC 2.7.1.107; *systematic name*: ATP:1,2-diacylglycerol 3-phosphotransferase; *other name*: diglyceride kinase. An enzyme that catalyses the reaction between ATP and 1,2-diacylglycerol to form ADP and 1,2-diacyl-*sn*-glycerol 3-phosphate (phosphatidic acid). It plays an important part in the response of cells to agonists that stimulate the **phosphatidylinositol cycle**, being involved in the resynthesis of inositolphospholipids. The enzyme is stimulated by Ca^{2+} and phosphorylated by protein kinase C; it is an **EF-hand** protein.

diacytosis the process of transporting material across a cell, especially an epithelial cell, by **pinocytosis** at one surface, movement of the **pinocytic vesicle** across the cell, and **exocytosis** of its contents at another part of the cell surface.

diafiltration the process of separating microsolutes, e.g. salts, from a solution of larger molecules (or of exchanging them for different microsolutes) by **ultrafiltration** with continuous addition of solvent (or of a solution of the new microsolutes). This rapidly removes the original microsolutes from the solution, whose volume remains constant.

diagnostic performance *or* **diagnostic power** a measure of the ability of a discriminator to distinguish true from false matches at a given scoring threshold.

diagnostic power *an alternative term for* **diagnostic performance**.

diagonal chromatography a two-dimensional chromatographic technique used to determine the sensitivity of a constituent of a mixture to some (photo)chemical process, e.g. oxidation. The sample is chromatographed in one direction, the process carried out *in situ*, and the specimen is then rechromatographed at right angles. Compounds unmodified by the treatment all lie on a diagonal line across the chromatogram.

diagonal electrophoresis a two-dimensional electrophoretic technique for determining the position of disulfide bonds in a polypeptide. The polypeptide is partially hydrolysed and the resulting smaller peptides separated by paper electrophoresis in one direction. After treatment on the paper with performic acid vapour, they are subjected to a second electrophoresis step at right angles. Those peptides not falling on a diagonal line on the paper contain cysteic acid residues formed by the oxidation of disulfide groups.

diakinesis the final phase of prophase I in **meiosis**.

dialdose any monosaccharide derivative containing two (potential) aldehydic carbonyl groups. *Compare* **aldose**, **diketose**.

diallyltartardiamide *abbr*.: DATD; *N*,*N*′-diallyl-L-tartramide, $[CH(OH)–CO–NH–CH_2–CH{=}CH_2]_2$; a compound sometimes used as a cross-linking agent in the preparation of polyacrylamide gels for electrophoresis or related separative procedures. Its structure contains a 1,2-diol grouping, which is susceptible to **periodate oxidation**. Such gels may thereby be solubilized after use to facilitate recovery of separated substances.

dialysable *or (esp. US))* **dialyzable** capable of being purified or separated by **dialysis**. The term has been used also, variously, to describe material that either can or cannot traverse a dialysis membrane. Some authorities prefer the term **diffusible** for material that can traverse a dialysis membrane. *See also* **dialysate**.

dialysate *or (esp. US)* **dialyzate** the solution resulting from **dialysis** that is free from colloidal material, i.e. free from material unable to pass through a dialysis membrane; the opposite of **retentate**. In the past the term has been used confusingly to describe both the material retained by the membrane and the material that has passed through a membrane. Some authorities prefer the term **diffusate** for the resulting colloid-free material and the term **analysis residue** for the retentate. *See also* **dialysable**.

dialyser *or (esp. US)* **dialyzer** an apparatus consisting of two or more compartments separated by **dialysis membrane(s)**, in which to carry out **dialysis**.

dialysis a process in which solute molecules are exchanged between two liquids through a membrane in response to differences in chemical potentials between the liquids. It is used especially for separating macromolecules (colloids) in solution from smaller dissolved substances (crystalloids) by selective **diffusion** through a **semipermeable membrane**, which allows the passage of all components of the system except the macromolecules. *See also* **diafiltration**, **diasolysis**, **electrodecantation**, **electrodialysis**, **equilibrium dialysis**, **reverse dialysis**, **thin-film dialysis**, **ultrafiltration**. [From Greek *dialusis*, a separation or dissolution.] **—dialyse** *or (esp. US)* **dialyze** *vb*.; **dialytic** *adj*.; **dialytically** *adv*.

dialysis bag the significant component of a simple **dialyser**, commonly made from a convenient length of **dialysis tubing** by knotting or tying off one or both ends. When filled with the colloidal solution to be dialysed it is immersed or suspended in an appropriate colloid-free aqueous medium.

dialysis cell any small device for use as a **dialyser**.

dialysis membrane any semipermeable membrane suitable for **dialysis**, often made of cellulose acetate, cellulose nitrate, or regenerated cellulose. It may be fashioned into flat sheets or into continuous tubing. Most dialysis membranes are permeable to molecules of up to 12–14 kDa.

dialysis residue *an alternative name for* **retentate**.

dialysis tubing seamless tubular **dialysis membrane**.

diamagnetic pair a diamagnetic dimer produced by spin coupling of two paramagnetic (molecular or atomic) species.

diamagnetism the property displayed by substances that have a very small negative magnetic susceptibility, due to the changes induced in the orbital motions of atomic electrons by an applied external magnetic field; such changes generate a magnetic field in opposition to the applied field. Whereas such a phenomenon occurs in all substances it is often masked by the opposing and stronger effects of **ferromagnetism** or **paramagnetism**. **—diamagnetic** *adj.*

diamine any compound containing two amino groups or substituted amino groups.

diamine oxidase *see* **amine oxidase (copper-containing)**.

diamino+ *prefix (in chemical nomenclature)* indicating the presence of two (unsubstituted or substituted) amino groups.

diamino acid any organic acid, usually an alkanoic acid, that contains two (unsubstituted or substituted) amino groups.

di(α-amino acid) any compound whose molecules may be derived from two (identical or differing) molecules of α-amino- alkanoic acid, however they are linked. The term comprehends (but is not limited to) any dipeptide.

diaminobenzoic acid *abbr*.: DABA; 3,5-diaminobenzoic acid; a compound that gives fluorescent products when heated in mineral acid solution with aldehydes. It is used for the microfluorimetric determination of DNA (as it does not react with RNA) and in the analysis of sialic acid.

diaminobutyric acid *symbol*: A_2bu; *abbr*.: Dab; α,γ-diaminobutyric acid; 2,4-diaminobutanoic acid; a diamino acid not occurring in proteins. The L enantiomer is sometimes found replacing *meso*-diaminopimelic acid in peptidoglycan of bacterial cell walls, and several residues per molecule are present in the peptide antibiotics of the polymyxin group (together with one residue of the D enantiomer in polymyxin B_1). It also occurs in higher plants as a nonprotein amino acid.

diaminocaproic acid *see* **lysine**.

2,7-diaminofluorene a dye used in the chromogenic assay of peroxidases. It replaces benzidine, which was formerly used but is now known to be carcinogenic.

diaminopimelic acid *symbol*: A_2pm *or* Dpm; *abbr*.: DAP; α,ε-diaminopimelic acid, 2,6-diaminoheptanedioic acid; a α,ε-diaminodicarboxylic acid with two chiral centres. *meso*-Diaminopimelic acid is the stereoisomer occurring in peptidoglycan in the cell walls of *Escherichia coli* and all other Gram-negative bacteria. *See also* **diaminopimelic-acid pathway**.

diaminopimelic-acid pathway *or* **DAP pathway** a metabolic pathway for the synthesis of L-lysine from L-aspartic acid via α,ε-diaminopimelate. Found in bacteria, some lower fungi, and green plants, it involves an initial condensation between pyruvate and aspart-4-al, yielding, following dehydration, 2,3-dihydropicolinate. This substance is then reduced; ring opening occurs followed by succinylation to form α-(succinylamino)-ε-oxo-L-aminopimelic acid. Transamination, deacylation, and epimerization yield the corresponding *meso*-α,ε-diaminopimelic acid; then decarboxylation completes the overall synthesis of L-lysine. *Compare* **aminoadipic pathway**.

diamorphine *see* **diacetylmorphine**.

diaphanous a gene that is homologous in *Drosophila*, mouse, and human. It encodes a protein (≈1250 amino acids) that binds profilin and regulates polymerization of actin in the cytoskeleton of hair cells of the inner ear. A protein-truncating mutation in the human gene *diaphanous 1* (at 5q31) leads to an autosomal dominant form of deafness. The locus for *diaphanous 2* (at Xq22) is the same as that for an X-linked form of deafness.

diaphorase *name formerly applied indiscriminately to* any enzyme capable of catalysing the oxidation of either NADH or NADPH in the presence of an electron acceptor such as a dye (e.g. Methylene Blue, or 2,6-dichlorophenolindophenol), ferricyanide, a quinone, or a cytochrome but not dioxygen. *Also formerly known as* **coenzyme factor**.

diaphragm 1 *(in chemistry)* a semipermeable membrane, or porous plate, used to separate two solutions in **dialysis** or **osmosis**. 2 *(in anatomy)* any separating membrane, especially the thin, domed fibromuscular partition separating the thorax from the abdomen. Flattening of the diaphragm, accompanied by expansion of the rib cage, causes air to be sucked into the lungs. 3 *(in optics)* any device, sometimes adjustable (e.g. iris diaphragm), that can limit or vary the aperture of a lens or optical system. 4 any other thin dividing membrane.

diarylpropane peroxidase *see* **ligninase**.

diasolysis a membrane permeation process for the separation of organophilic from hydrophilic solutes, akin to **dialysis** but differing in that separation depends primarily on the relative solubilities of the solutes in the membrane rather than on their molecular dimensions. Such a process may play a part in the selective passage of solutes through membranes of living cells.

diastase 1 *obsolete name for* α-amylase (EC 3.2.1.1). 2 the crude mixture of amylases obtained commercially as a yellowish white amorphous powder from malt. [From Greek *diastasis*, a separation.] **—diastatic** *adj.*

diastatic activity the enzymic activity of α-amylase.

diastereoisomer *or* **diastereomer** any **stereoisomer** that is not **enantiomeric**; it may be either chiral or achiral. The term includes ***cis–trans*** **isomer**, **configurational isomer**, **conformational isomer**, and **epimer**. **—diastereoisomeric** *or* **diastereomeric** *adj.*; **diastereoisomerism** *or* **diastereomerism** *n.*

diastereotopic 1 chemically-like ligands in constitutionally equivalent locations that are not symmetry related (cannot be interchanged by rotation about an axis (C_n) or alternating axis (S_n) of symmetry) are diastereotopic; the two ligands are in a stereochemically different, nonmirror-image environment. Separate replacement of each ligand by a different achiral ligand yields two products that are in a diastereoisomeric relationship. Example: replacement of the H_R hydrogen of the methylene group in (R)–CH_3–CH_2–CHBr–CH_3 with chlorine yields (2*R*,3*R*)-2-bromo-3-chlorobutane; the similar replacement of the H_S hydrogen yields the diastereoisomeric (2*R*,3*S*)-2-bromo-3-chlorobutane. A biochemically important example is that both of the methylene groups of citric acid have diastereotopic hydrogens. 2 the two faces of a double bond or of a planar cyclic ring system that are not related by any symmetry operation (axis, plane, centre, or alternating axis) are diastereotopic; the two faces show stereochemically different, nonmirror-image environments. Separate addition of an achiral reagent to each face yields two diastereoisomeric products. Example: hydrogenation of the C=O bond in (3*S*)–CH_3–CH_2–$CH(CH_3)$–CO–COOH (in absence of any chiral influence such as a chiral catalyst) yields the two diastereoisomers, (2*R*,3*S*)-2-hydroxy-3-methylpentanoic acid and (2*S*,3*S*)-2-hydroxy-3-methylpentanoic acid. A biochemical example is the two diastereotopic faces, *A* and *B*, of the (dihydro)pyridine ring of nicotinamide-adenine coenzymes (*see* **nicotinamide-adenine dinucleotide (reduced)**). *Compare* **enantiotopic**.

diastole 1 the passive dilatation of the chambers of the heart that occurs between the rhythmical contractions. 2 the rhythmical expansion of a pulsating vacuole. *Compare* **systole**. **— diastolic** *adj.*

diastrophic dysplasia sulfate transporter *abbr.*: DTDST; a 739-residue integral membrane protein that contains 12 transmembrane segments, is produced in many mammalian tissues, and functions as a sulfate–chloride antiporter. Many mutations in the gene at 5q32-q33.1 result in insufficient sulfation of cartilage glycoproteins and are associated with various autosomal recessive skeletal dysplasias, some of which are lethal.

diatomaceous earth *or* **kieselguhr** a friable, whitish material consisting mostly of silica, derived from diatomite, a rock consisting largely of the remains of diatoms. It is used as a filter aid and as an absorbent in column chromatography. *See also* **Berkefeld filter**.

diatomic *(of a molecular entity)* composed of only two atoms. **—diatomicity** *n.*

diatrizoate the anion 3,5-diacetamido-2,4,6-triiodobenzoate. Its sodium salt forms solutions of low viscosity and high relative density. A mixture with Ficoll provides a solution having the optimal density and osmolarity for the rapid, one-step isolation of lymphocytes from small volumes of blood by centrifugation. It is also used as a radiopaque material.



diauxy the adaptation of microorganisms to culture media containing two different carbohydrates. Growth occurs in two phases separated by a period of less rapid or zero growth. In the first phase, the organism utilizes the carbohydrate for which it possesses constitutive enzymes. During the interlude the organism synthesizes the required induced enzymes for the metabolism of the other carbohydrate, which it then proceeds to exploit in the second growth phase. **—diauxic** *adj.*

diazepam 7-chloro-1,3-dihydro-1-methyl-5-phenyl-2*H*-1,4-benzodiazepin-2-one; one of the most widely used **benzodiazepine** drugs, noted for its CNS depressant effects. Used as an anti-anxiety–hypnotic agent at subsedative doses, its actions are similar to those of chlordiazepoxide, but it has greater potency. One proprietary name is Valium.



diazepam binding inhibitor a 10 kDa, 86-residue polypeptide, that acts as an endogenous ligand for a mitochondrial receptor (formerly regarded as a peripheral benzodiazepine binding site) in steroidogenic cells (i.e., adrenocortical, glial, and Leydig cells), and regulates stimulation of steroidogenesis by tropic hormones. It also binds to the benzodiazepine binding site on the $GABA_A$ receptor, and modulates glucose-dependent insulin secretion and synthesis of acyl-CoA esters.

diazo compound any organic compound, other than an **azo compound**, that contains the bivalent **azo** group –N=N– (or $=N_2$) in covalent linkage. It may be (1) any aliphatic compound of general formula R–CH=N_2, in which both nitrogen atoms are linked to the same carbon atom by replacing two hydrogen atoms of the parent molecule, e.g. diazomethane, CH_2=N_2; or (2) any aromatic compound of general formula Ar–N=N–X in which one nitrogen atom is linked to a carbon atom of the aromatic ring by replacing one hydrogen atom of the parent molecule, and the other nitrogen atom is linked covalently to a group X through an atom other than carbon (except when X = CN), e.g. benzenediazohydroxide, C_6H_5–N=N–OH.

diazonium compound any aromatic organic compound of general formula Ar–N_2^+, containing the univalent cationic **diazonium group**, $-N^+{\equiv}N$, linked to a carbon atom of an aromatic ring system by replacing one hydrogen atom of the parent molecule. The positive charge is balanced by an anion to form a **diazonium salt**, e.g. benzenediazonium chloride, C_6H_5–$N_2^+Cl^-$.

diazotize *or* **diazotise** to cause a primary aromatic amine to form a

diazonium compound by reaction with nitrous acid in the presence of a strong acid, according to the equation:

$$\text{Ar-NH}_2 + \text{HONO} + \text{H}^+ = \text{Ar-N}_2{}^+ + 2\text{H}_2\text{O}.$$

—**diazotized** *adj.*; **diazotization** *n.*

dibasic cleavage site a site within a proprotein structure at which endopeptidases act specifically to cleave the protein to one or more active polypeptides. It comprises a connected pair of basic amino-acid residues (Arg–Arg, Arg–Lys, Lys–Arg or Lys–Lys). The cleavage is effected by a family of cellular endoproteases; these have catalytic domains related to **subtilisin,** and go under the general name mammalian **prohormone convertases** (PCs). Examples are **kex2**, first described in yeast, PC2 in human insulinoma, PC3, and **furin**. Dibasic cleavage sites occur, e.g., in **proinsulin**, **proopiomelanocortin**, and **chromogranins**.

dibenzazepine any of a group of compounds with a tricyclic structure related to phenothiazines that prevent the neuronal reuptake of norepinephrine or 5-hydroxytryptamine from the synaptic cleft, and are useful as drugs in the treatment of depression, e.g. imipramine, clomipramine.

dibenzocycloheptene any of a group of agents that prevent neuronal reuptake of norepinephrine and 5-hydroxytryptamine from the synaptic cleft and are useful as drugs in the treatment of depression, e.g. amitriptyline.

dicarboxylate transport protein *former name for* **oxoglutarate/malate carrier protein**.

dicarboxylic acid any organic compound containing two carboxyl groups.

dicaryon *a variant spelling of* **dikaryon**.

DICE *abbr. for* differentiation control element; a nucleotide sequence in the 3′ untranslated region of mRNA for 15-lipoxygenase. In erythroid precursor cells DICE binds and is repressed by the hnRN proteins K and E1. The repression is removed in the terminal stages of erythrocyte differentiation and the encoded lipoxygenase mediates mitochondrial breakdown.

Dicer a multidomain endonuclease of ribonuclease III-type that is involved in the generation of small interfering RNAs (siRNA) and other forms of microRNA (miRNA) species. It is important for normal development in *Caenorhabditis elegans*. The human and *Drosophila* enzymes are homologous and contain a DEXH-box ATP-dependent RNA helicase domain, tandem RNase III motifs, and a C-terminal dsRNA-binding domain. In animals, Dicer and its cofactors are absent in differentiated cells.

2′,7′-dichlorofluorescein a dye useful as a detection reagent for lipids, yielding fluorescent spots on chromatograms under UV light.



5,6-dichloro-1β-D-furanosyl benzimidazole *see* **DRB**.

dichroic ratio the ratio of the absorbance of light polarized perpendicularly to the axis of a nonisotropic sample (e.g. the fibre axis of a protein or nucleic-acid molecule or one axis of a crystal) to the absorbance of light polarized parallel to the sample axis. If the dichroic ratio is greater than unity, the vibrational transition observed is said to exhibit **perpendicular dichroism**; if less than unity, it is said to show **parallel dichroism.**

dichroism 1 the directional effect observed in the absorption of electromagnetic radiation resulting from the relative orientations of the absorbing chromophore and the direction of the electric vector in the polarized electromagnetic radiation. Thus the absorption of such radiation may be restricted only to atoms or groups that vibrate in a specific direction or to a component of the radiation that is polarized in a specific direction. *See* **circular dichroism**, **dichroic ratio**, **electric dichroism**. **2** concentration- and path-length-dependent changes in the frequencies of electromagnetic radiation absorbed by solutions of certain substances. —**dichroic** *adj.*

dicoumarol *or* **dicumerol** *or (esp. US)* **dicumarol** (*formerly* bishydroxycoumarin);3,3′-methylenebis(4-hydroxycoumarin), 3,3′-methylenebis(4-hydroxy-2*H*-1-benzopyran-2-one); a substance originally isolated from spoiled sweet clover but now synthetic, that prevents the normal formation of prothrombin and other blood coagulation factors. It interferes with the action of vitamin K in γ-carboxylation of certain glutamic residues in the precursors of the coagulation proteins. It is used therapeutically as an anticoagulant, and is also used as a rodenticide. **Warfarin** is one of the **coumarins**.



dictyosome 1 *or* **golgiosome** *an alternative name for* **Golgi apparatus**, especially in cells of invertebrates and plants; there are usually several scattered dictyosomes per cell. **2** a collar-like structure that may form an anchor for the base of the flagellum in uniflagellate fungi.

Dictyostelium discoideum a cellular **slime mould**. It exists in the vegetative form as unicellular, haploid **myxamoebae**, 8–12 μm maximum dimension, using bacteria as food. In the absence of bacteria, chemotactic aggregation of myxamoebae occurs, mediated by myxamoebal secretion of acrasin (i.e., cyclic AMP), to form an elongated, finger-like, multicellular **pseudoplasmodium**, 1–4 mm maximum dimension. Aggregation is assisted by the synthesis of a multivalent carbohydrate-binding lectin, **discoidin**, found in the outer membrane of starved cells. The pseudoplasmodium differentiates to form a single, unbranched stalk, the **sorocarp**, which carries a spheroidal or ovoid mass of yellow spores, each commonly 5–10 μm × 3–6 μm with a thick cellulose-containing wall. Germination of spores only occurs in the presence of an adequate supply of amino acids.

dicyclohexylcarbodiimide *see* **DCC**. *See also* **carbodiimide**.

didehydro+ *prefix (in chemical nomenclature)* denoting the loss of two hydrogen atoms. *See also* **dehydro+**.

3,4-didehydroretinal *recommended trivial name for* (3-)dehydroretinal; (3-)dehydroretinaldehyde; retinal$_2$; vitamin A$_2$ aldehyde; retinene$_2$; (2*E*,4*E*,6*E*,8*E*)-3,7-dimethyl-9-(2,6,6-trimethylcyclohex-1,3-dien-1-yl)nona-2,4,6,8-tetraen-1-al; the didehydro derivative of **retinal** (def. 2). This all-*E*-isomer, 3,4-didehydro-all-*trans*-retinal, often termed all-*trans*-retinal$_2$, plays a role in the visual process in freshwater fish and some amphibians analogous to that of all-*trans*-retinal in other vertebrates; *see* **retinal** (def. 2). Its isomerization product, the (2*E*,4*Z*,6*E*,8*E*)-stereoisomer, generally termed 11-*cis*-retinal$_2$, combines (as a **Schiff base**) with an opsin to form (in cone cells) **cyanopsin** or (in rod cells) **porphyropsin**. *Note*: The numbering system of the systematic name is different from that of the trivial name, the latter following the rules used for carotenoids.



(all-*E*) isomer



(2*E*,4*Z*,6*E*,8*E*) isomer

3,4-didehydroretinoic acid *recommended trivial name for* (3-)dehydroretinoic acid; vitamin A_2 acid; (2*E*,4*E*,6*E*,8*E*)-3,7-dimethyl-9-(2,6,6-trimethylcyclohex-1,3-dien-1-yl)nona-2,4,6,8-tetraenoic acid; the didehydro derivative of **retinoic acid**.



3,4-didehydroretinol *recommended trivial name for* (3-)dehydroretinol; retinol_2; vitamin A_2; vitamin A_2 alcohol; (2*E*,4*E*,6*E*,8*E*)-3,7-dimethyl-9-(2,6,6-trimethylcyclohex-1,3-dien-1-yl)nona-2,4,6,8-tetraen-1-ol; the didehydro derivative of **retinol**, being characterized by a second double bond in the terminal ring of the molecule. It is the predominant form of vitamin A in freshwater fishes. *See also* **vitamin A**.



dideoxy+ *prefix (in organic chemical nomenclature)* **1** denoting the replacement of two hydroxyl groups by two hydrogen atoms. **2** (*abbr*.: dd+) indicating the presence in a nucleoside of a residue of 2,3-dideoxy-D-ribose.

dideoxyadenosine *symbol*: ddAdo *or* ddA; *abbr*.: DDA; 2′,3′-dideoxyadenosine; an adenosine analogue with antiviral activity.



dideoxycytidine *symbol*: ddCyd *or* ddC; *abbr*.: DDC; 2′,3′-dideoxycytidine; a cytidine analogue with antiviral activity.





9,11-dideoxy-9α,11α-epoxymethanoprostaglandin $F_{2\alpha}$ U46619; a stable **thromboxane** A_2 mimetic.



dideoxyinosine *symbol*: ddIno *or* ddI; *abbr*.: DDI; 2′,3′-dideoxyinosine; an **inosine** analogue with antiviral activity.



dideoxy method *or* **dideoxy(nucleotide) sequencing analysis** *an alternative name for* **chain-termination method** (for sequencing DNA molecules).

dideoxynucleoside triphosphate *abbr*.: ddNTP; any artificial nucleoside triphosphate in which both of the hydroxyl groups on C-2′ and C-3′ of the pentose moiety have been replaced by hydrogen atoms. They are used in sequencing DNA molecules by the **chain-termination method**.

DIDS *abbr. for* 4,4′-diisothiocyano-2,2′-disulfonic acid stilbene; a powerful anion-transport inhibitor



didymium glass a glass with a bluish-pink coloration due to the inclusion of a mixture of rare-earth elements, chiefly neodymium and praseodymium. It has intense, narrow, light-absorption bands, and is used for calibrating spectrometers. An example is a glass known as Corning 5120, which has absorption bands at 441, 528.7, 585, 684.8, 743.5, 754, 808, 883, and 1067 nm.

dielectric **1** a substance or medium that can sustain an electric field but does not conduct electricity; an insulator. **2** of, relating to, or being a dielectric.

dielectric absorption the strong absorption of microwave electric fields shown by polar liquids, particularly water. It is especially troublesome in **electron spin resonance spectroscopy**.

dielectric constant *an obsolete term for* **relative permittivity**.

dielectric dispersion variation of the **relative permittivity** with the frequency of the applied electric field.

dielectric increment the change in the **relative permittivity** of a solution with the change in the concentration of the solute. For low concentrations of solute in polar solvents, the dielectric increment, $\delta D/\delta c$, is equal to $(D - D_0)/c$, where D and D_0 are the relative permittivities of the solution and solvent, respectively, and c is the solute concentration.

dielectrophoresis the translational motion of neutral suspended particles relative to that of the suspending medium when the suspension is subjected to a nonuniform electric field. The movement is the result of polarization induced in the particles, the degree of which is dependent on the ratio of the relative permittivities (*formerly* dielectric constants) of particles and medium. In **positive dielectrophoresis** (that most commonly observed), movement of the particles is towards the region of highest field intensity, irrespective of its sign (*compare* **electrophoresis**). **Negative dielectrophoresis** may be observed in certain frequencies when an alternating field is used, the particles then being attracted less than the medium to the region of most intense field; at such frequencies the polarizability of the particles is not greater than that of the medium. Dielectrophoresis is used, e.g., in the concentration of certain biological products, the characterization of single-celled organisms or cellular organelles by their characteristic yield spectrum (i.e. yield vs. field frequency), and the determination of the diffusion coefficients of proteins in solution.

diene any **alkadiene** or substituted alkadiene.

+diene(+) *or (before a vowel)* **+dien+** *(in chemical nomenclature) infix or suffix* in systematic names denoting the presence in a molecular structure of an unsaturated aliphatic hydrocarbon chain containing two (conjugated or unconjugated) double bonds. The position of each double bond may be indicated by a locant for its lowest-numbered carbon atom; e.g. cyclohexa-1,3-diene, eicosa-8,11-dienoic acid.

dienoic indicating a compound having an aliphatic chain with two double bonds and a carboxyl group.

dienoyl *general name for* any acyl group derived from an unsaturated fatty acid containing two (conjugated or unconjugated) double bonds.

2,4-dienoyl-CoA reductase (NADPH) EC 1.3.1.34; *systematic name*: *trans*-2,3-didehydroacyl-CoA:NADP$^+$ 4-oxidoreductase; *other name*: 4-enoyl-CoA reductase (NADPH). An enzyme of the pathway for oxidation of unsaturated fatty acids that catalyses the reduction by NADPH of *trans*,*trans*- 2,3,4,5-tetradehydroacyl-CoA to *trans*-2,3-didehydroacyl- CoA, a normal substrate of β oxidation. For the bacterial enzyme, this is a direct product of the enzyme, but for the mammalian enzyme the product is *trans*-3,4-didehydroacyl- CoA, which must undergo isomerization to *trans*-2,3-didehydroacyl- CoA. *See also* **unsaturated fatty acid oxidation**.

diesterase *see* **phosphodiesterase**.

dietary deficiency a nutritional deficiency due to inadequate intake of one or more specific and necessary constituents of the diet, even though the diet may in other respects be adequate quantitatively.

dietary fibre **1** all ingested food that reaches the large intestine in an essentially unaltered state. **2** the structural parts of plant foods that are poorly digested in the gastrointestinal tract. These consist mostly of lignin and the polysaccharides celluloses, hemicelluloses, glucans, xylans, gums, and pectins. The whole-grain cereals wheat, maize, and rice are rich sources of the insoluble celluloses and lignin. Oats, barley, and rye are rich in soluble gums and pectins. Dietary fibre binds bile acids and cholesterol, delays the postprandial rise in blood glucose, and therefore decreases insulin secretion; it also retains water, which promotes the formation of larger and softer feces. Much dietary fibre is digested in the large intestine by anaerobic microorganisms into short-chain fatty acids – which are absorbed into the portal vein and used as an energy source – and into the gases carbon dioxide, hydrogen, and methane. Low fibre intake is associated with increased incidence of constipation, diverticular disease, cancer of the large bowel, diabetes mellitus type II, and coronary artery disease.

diethyldithiocarbamate a chelating agent used for estimation of copper. The iron complex is used as a spin-trap for nitric oxide.

diethyl ether *see* **ether**.

diethylpyrocarbonate *abbr*.: DEPC; a powerful protein denaturant used to treat water to be used for dissolving RNA. DEPC treatment inactivates ribonucleases whose activity would be detrimental to RNA integrity.

diethylstilbestrol *or (esp. UK)* **diethylstiboestrol** 4,4′-(1,2-diethyl-1,2-ethenediyl)bisphenol; a nonsteroidal compound that possesses the activity of an **estrogen**. It is used therapeutically to replace natural hormones, and was formerly used as a growth promoter in livestock (this use is now prohibited in many countries, including the UK and USA). It was originally used for the treatment of prostatic cancer.

difference spectrophotometry a spectrophotometric method for investigating the effects of potential perturbants on a chemical substance or system in solution. Two samples are prepared containing identical solutions except that one contains a potential perturbant, e.g. a protein denaturant. The absorbances of the two samples at each frequency are subtracted one from another generating a **difference spectrum** and thereby highlighting any small differences between the spectra of the normal and perturbed systems.

differential centrifugation centrifugation of a suspension in a succession of increasing gravitational fields so that particles of differing sizes and/or relative densities may be separated and collected.

differential counting counting of the pulses produced in a **scintillation counter** that fall within two or more differing energy ranges selected for with a pulse-height analyser. The technique is used for counting the disintegrations due to two or more radionuclides in the same sample.

differential display PCR a type of real-time polymerase c hain reaction (RT-PCR) for comparing differences in mRNA expression between cells or tissues. It is based on the generation of a representative set of cDNA fragments corresponding to the 3′ ends of mRNAs from each source, which are run side by side on electrophoresis gels. Increases or decreases in the abundance of fragments separated by gel electrophoresis indicate changes in the abundance of mRNAs. Excision of bands of interest from the gel, cloning, and sequencing permits identification of genes whose expression has changed.

differential labelling a method of determining the part of a molecule that reacts in a particular way by blocking one part with a specific reagent and investigating whether a particular reaction will still occur. It is used, e.g., for investigating the combining sites of antibodies.

differential medium any medium used for growing microorganisms that reveals specific properties of the organism(s) grown and hence aids in identification of the organism(s). *See also* **selective medium**.

differential scanning calorimetry *abbr*.: DSC; a form of **differential thermal analysis** in which the temperatures of both the sample and the reference substance are maintained at either the same or a constant difference; the amount of heat that must flow into the sample to maintain the temperature differential during a transition is then measured.

differential thermal analysis *abbr*.: DTA; a method for analysing temperature-induced transitions in a sample. The sample and an inert reference material are heated or cooled at the same rate and the difference in temperature between them is monitored. This difference is zero or constant until a thermally induced transition occurs in the sample, when the temperature difference changes. The direction of the change shows whether the transition is endo- or exothermic.

differential titration the titration of a group, e.g. an acid group, before and after another group in the same molecule has reacted with some other reagent. It is used to determine the extent, if any, of **linkage** between the functions of the groups in question. *See* **titrate**.

differentiating-stimulating factor *see* **leukemia inhibitory factor**.

differentiation the process whereby relatively unspecialized cells, e.g. embryonic or regenerative cells, acquire specialized structural and/or functional features that characterize the cells, tissues, or organs of the mature organism or some other relatively stable phase of the organism's life history.

differentiation antigen any cell-surface antigen whose expression varies during successive developmental stages of a particular cell type.

diffraction the bending of light, or other waves, by an obstacle or aperture, into the region of the geometrical shadow of the object; any redistribution in space of the intensity of waves resulting from the presence of an object in their path causing variations of either their amplitude or their phase. The effect is particularly marked when the size of the object is of the same order as that of the wavelength of the waves. Diffraction accounts for the phenomenon observed when light passes through an aperture and falls on a screen; this takes the form of patterns of light and dark bands (with monochromatic light) or coloured bands (with heterochromatic light) near the edges of the beam and extending into the shadow. Diffraction is also responsible for the propagation of radio waves over the surface of the globe and of sound waves around solid objects. *See* **diffraction grating**, **electron diffraction**, **X-ray diffraction**.

diffraction grating a glass or quartz plate on the surface of which there is a large number of equidistant parallel black lines (500 or more per millimetre). When light or other electromagnetic radiation passes through such a grating it is diffracted in a manner dependent on the wavelength of the radiation. Other plane surfaces, e.g. metals, may be used.

diffusate a product of a process of diffusion, especially the material that enters into or traverses a barrier of restricted or selective permeability. In **dialysis** the term is sometimes preferred to **dialysate**. *Compare* **nondiffusible material**.

diffusible 1 capable of diffusing. **2** *(sometimes) a preferred alternative term for* **dialysable** (i.e. capable of passing through a semipermeable membrane used in dialysis).

diffusion 1 the net flow of molecules from a region of high concentration, or high chemical potential, to one of low concentration, or low chemical potential, due only to random thermal motion. *See also* **facilitated diffusion**. **2** the irregular reflection or transmission of light or other electromagnetic radiation; scattering. **3** the act or process of dispersing or of being dispersed widely. **—diffuse** *vb., adj.*

diffusion cell *or* **diffusion chamber 1** a cell or chamber with porous walls that allow the passage of dissolved substances but not of biological cells. It is used in studying materials released by cells. **2** a device for measuring the diffusion of macromolecules and consisting of two chambers separated by a porous membrane of nearly parallel channels. The channels are large compared with the size of the macromolecules but small enough that the bulk flow of liquid through them is negligible.

diffusion coefficient *or* **diffusion constant** *symbol*: D; a coefficient of proportionality between flux and concentration gradient for a solute diffusing in a system of constant temperature and pressure in accordance with **Fick's first diffusion law** and **Fick's second diffusion law**. For an ideal solute it is a constant, but in practice usually varies with concentration. The cgs unit for D is cm^2 s^{-1} (*see also* **Fick unit**) and the SI unit is m^2 s^{-1}.

diffusion-controlled *or* **diffusion-limited** describing a chemical reaction (or other process) whose velocity is dependent on the rate at which one or all of the reactants (or participants) can diffuse to the site at which the reaction (or process) occurs, as to the active site of an enzyme catalysing the reaction.

diffusion gradient any gradient e.g. in the concentration of a dissolved solute that forms if the solute is capable of diffusing from a region of higher concentration to a region of lower concentration until its concentration in the solution is uniform.

diffusion-limited *see* **diffusion-controlled**.

diffusion potential an electric potential difference across a membrane due to the diffusion through the membrane of more cationic charges than anionic charges, or vice versa.

diffusive characterized by diffusion. **—diffusively** *adv.*

DIFP *see* **DFP**.

DiGeorge syndrome a variety of phenotypes mostly arising from deletion of a portion of chromosome 22q11.2. The CATCH phenotype includes **c**ardiac **a**bnormality, abnormal facies, **T**-cell deficit due to hypoplasia of the thymus, **c**left palate, and **h**ypocalcemia. [After Angelo DiGeorge (1921–), US paediatrician.]

digest 1 to subject material to enzymic or chemical breakdown. **2** to subject food to **digestion** (def. 1). **3** to break down nitrogenous compounds by hot sulfuric acid to convert them to ammonium salts. **4** to treat biological materials with powerful oxidants to facilitate determination of trace elements present. **5** the mixture of compounds obtained from the enzymic or chemical degradation of a macromolecule or other substance. **—digester** *n.* an apparatus that facilitates digestion procedures.

digestion 1 the whole of the physical, chemical, and biochemical processes carried out by living organisms to break down ingested nutrients into components that may be easily absorbed and directed into metabolism. **2** the process of breaking down complex substances or materials into smaller parts either enzymically or chemically, especially in the course of their analysis.

digestive enzyme any hydrolytic enzyme that brings about or assists in **digestion** (def. 1).

digestive juice any of the secretions entering the digestive tract that contain digestive enzymes. They include saliva, **gastric juice**, **intestinal juice**, and **pancreatic juice**.

digestive system the digestive tract together with related organs, such as the pancreas and liver.

digestive tract *or* **alimentary tract** the tubelike passage in higher animals, extending from the mouth to the anus, in which the food is digested, from which absorption of nutrients occurs, and which serves to eliminate waste products.

diginose the D enantiomer, 2,6-dideoxy-3-*O*-methyl-D-*lyxo*-hexose, is a component of some **cardiac glycosides**

digital imaging the process of recording an image directly in digital form using a digital camera or similar device.

digitalis 1 any plant of the genus *Digitalis*. **2** a preparation of powdered dried leaves of the purple foxglove (*Digitalis purpurea*). It contains the cardiac glycosides **digitoxin**, **gitoxin** (a glycoside of 3,14,16-trihydroxycard-20(22)-enolide), and **gitaloxin** (16-formylgitoxin), and is used therapeutically to increase the strength of the heart's contraction and to slow auricular–ventricular conduction.

digitalose the D enantiomer, 3-methyl-D-fucose, 6-deoxy-3-*O*-methyl-D-galactose, is a component of some **cardiac glycosides**, e.g. digitoxin.

digitogenin (25*R*)-5*α*-spirostan-2*α*,3*β*,15*β*-triol; the aglycon of the glycosides (saponins) present in **digitonin**.



digitonin a mixture of at least four steroid saponins obtained from the seeds of the purple foxglove, *Digitalis purpurea*. It is useful in the fractional precipitation and analysis of cholesterol and other steroids and as a nonionic detergent in the solubilization of membrane proteins. Aggregation number 60. Its aglycon is **digitogenin**.

digitoxigenin 3*β*,14-dihydroxy-5*β*-card-20(22)-enolide; the aglycon of **digitoxin**.



digitoxin a secondary glycoside, or mixture of glycosides comprised mainly of digitoxin, that is extracted from *Digitalis purpurea*. It has actions similar to, but longer-lasting than, **digoxin**. Its aglycon is digitoxigenin. *See also* **cardiac glycoside**.

digitoxose the D enantiomer, 2,6-dideoxy-D-*ribo*-hexose, is a component of some **cardiac glycosides**.

diglyceride *former name for* **diacylglycerol** (it is still quite commonly used, as in 'diglyceride fraction', but its use is discouraged for such purposes as diglyceride is properly a generic term for any compound having two glyceryl residues, e.g. **phosphatidylglycerol**).

digoxigenin *or* **digoxygenin** 3β,12β,14-trihydroxy-5β-card-20(22)-enolide; the aglycon of **digoxin**. In molecular biology digoxigenin is used as a hapten for labelling RNA and DNA probes. Uridine triphosphate and deoxyuridine triphosphate are modified by attaching digoxigenin at position 5 of the pyrimidine ring by a spacer arm. These analogues can then be incorporated into probes by RNA or DNA polymerases respectively. Detection of the labelled probes depends on anti-digoxigenin antibodies coupled to an enzyme such as alkaline phosphatase.



digoxin a secondary glycoside extracted from the Austrian (or woolly) foxglove, *Digitalis lanata*. It acts on the heart to potentiate contractility and reduce conductivity mainly through inhibition of Na^+,K^+-ATPase, hence its use in congestive heart failure and atrial dysrhythmia. Its aglycon is digoxigenin. *See also* **cardiac glycoside**.

dihedral having or contained by two planes or plane faces.

dihedral angle the inclination of two planes that meet at an edge.

dihedral symmetry the symmetry of a **point group**, designated D_n, containing an n-fold axis with n twofold axes perpendicular to it.

dihomo-(6,9,12)-linolenate dihomogammalinolenate, dihomo-γ-linolenate, (*all-Z*)-eicosa-8,11,14-trienoate; an intermediate in the synthesis of arachidonate from linoleate, formed by Δ^6 desaturation and chain elongation. It acts as a precursor for the PG_1 series of **prostaglandins**. *See also* **eicosatrienoic acid**.

dihydric describing a chemical compound containing two hydroxyl groups per molecule. It is used especially of **alcohols**. *Compare* **dihydroxy+**.

dihydro+ *prefix (in chemical nomenclature)* indicating the presence of two additional hydrogen atoms.

dihydrobiopterin reductase EC 1.6.99.7; an NADH-requiring enzyme of 244 amino acids, present in liver, brain, and adrenal medulla, that converts dihydrobiopterin into tetrahydrobiopterin. It is a homodimer and essential for supplying tetrahydrobiopterin to the aromatic amino acid hydroxylases that require it. Deficiency arises from many mutations in the gene at 4p15.3 and causes a phenylketonuria phenotype that is characterized by convulsions and progressive mental deterioration. This can be treated by maintaining the patient on a low-phenylalanine diet supplemented with DOPA, 5-hydroxytryptophan, and folinic acid.

dihydrofolate *abbr*.: H_2folate (DHF not recommended); **1** 7,8-dihydrofolate, 7,8-dihydropteroylglutamate; *the trivial name for* the 7,8-dihydro derivative of **folate** (def. 1). **2** any **folate** (def. 2) that is a dihydro compound, especially any of the respective 7,8-dihydro intermediates in the conversion of nonreduced folates to their corresponding folate coenzymes (i.e. tetrahydrofolates) by the enzyme dihydrofolate reductase. *See also* **antifolate**, **tetrahydrofolate**.



dihydrofolate reductase *abbr*.: DHFR; EC 1.5.1.3; *systematic name*: 5,6,7,8-tetrahydrofolate:$NADP^+$ oxidoreductase; *other name*: tetrahydrofolate dehydrogenase. An enzyme that catalyses the interconversion of 5,6,7,8-tetrahydrofolate and 7,8-dihydrofolate, and also slowly interconverts 7,8-dihydrofolate and folate; both reactions are linked to the reduction/oxidation of $NADP^+$/NADPH. It is inhibited by **aminopterin**, amethopterin (*also termed* **methotrexate**), and **trimethoprim**.

dihydrofolate synthase EC 6.3.2.12; *other name*: dihydrofolate synthetase; an enzyme of the pathway for the *de novo* synthesis of dihydrofolate. It catalyses the formation of dihydrofolate from ATP, dihydropterate, and L-glutamate with release of ADP and orthophosphate.

dihydrogen *systematic name for* the diatomic compound H_2, commonly termed (molecular) hydrogen.

dihydrolipoamide *S*-acetyltransferase EC 2.3.1.12; *other names*: lipoate acetyltransferase; thioltransacetylase A; an enzyme that catalyses the formation of acetyl-CoA and dihydrolipoamide from *S*-acetyldihydrolipoamide and CoA. A lipoyl group is required as a coenzyme, the enzyme having three covalently linked lipoyl groups. This is the E_2 component of the **pyruvate dehydrogenase complex**. Example: dihydrolipoamide acetyltransferase component (E_2) of a human pyruvate dehydrogenase complex precursor (PDC-E_2): (incomplete sequence) ODP2_HUMAN, 615 amino acids (65.32 kDa).

dihydrolipoamide dehydrogenase EC 1.8.1.4; *other names*: lipoamide reductase (NADH); lipoyl dehydrogenase; dihydrolipoyl dehydrogenase; diaphorase; the E_3 component of α-ketoacid dehydrogenase complexes, an FAD-flavoprotein enzyme that catalyses the oxidation by NAD^+ of dihydrolipoamide to lipoamide and NADH. Example (precursor) from human: DLDH_HUMAN, 509 amino acids (54.09 kDa). *See also* **oxoglutarate dehydrogenase complex**; **pyruvate dehydrogenase complex**.

dihydrolipoamide *S*-succinyltransferase EC 2.3.1.61; an enzyme that catalyses the formation of succinyl-CoA and dihydrolipoamide from *S*-succinyldihydrolipoamide and CoA. It is the E_2 component of the **oxoglutarate dehydrogenase complex**. The human precursor protein consists of 453 amino acids; the enzyme is formed from residues 68–453, 1–67 forming the transit peptide.

dihydrooratase EC 3.5.2.3; *systematic name*: (*S*)-dihydroorotate amidohydrolase; *other names*: carbamoylaspartic dehydrase; DHOase. An enzyme that catalyses the formation of *N*-carbamoyl-

L-aspartate from (*S*)-dihydroorotate. In many eukaryotes this is an activity of **CAD protein**.

dihydropyridine receptor a voltage-gated Ca^{2+} channel of skeletal muscle transverse tubules that specifically binds 1,4-dihydropyridine compounds. It is an integral membrane protein containing four homologous repeats that form six transmembrane helices each. It is in close proximity to the foot region of the ligand-gated **ryanodine receptor** of the sarcoplasmic reticulum.

5*α*-dihydrotestosterone 4,5-dihydrotestosterone; 5*α*-androstan-17*β*-ol-3-one; a potent metabolite of testosterone, formed by either of the steroid 5*α*-reductases. It mediates many of the differentiating, growth-promoting, and functional actions of testosterone by binding to the **androgen receptor.** Many mutations that inactivate steroid 5*α*-reductase 2 cause an autosomal recessive form of **testicular feminization**.



dihydrouracil 5,6-dihydrouracil, a minor pyrimidine base. It occurs in the **dihydrouridine arm** of **transfer RNA**.



dihydrouridine *symbol*: D *or* hU; 5,6-dihydrouracil riboside; 1-*β*-D-ribofuranosyl-5,6-dihydrouracil; a rare nucleoside occurring in the **dihydrouridine arm** of **transfer RNA**.



dihydrouridine arm *abbr.*: DHU arm; the base-paired segment of the **clover leaf structure** of **transfer RNA** that has attached to it the loop containing 5,6-dihydrouracil (*see* **dihydrouracil**).

dihydroxy+ *prefix (in chemical nomenclature)* indicating the presence of two substituent hydroxyl groups.

dihydroxyacetone *older name for* **glycerone**.

dihydroxyacetone phosphate *older name for* **glycerone phosphate**.

dihydroxyacetone synthase *see* **formaldehyde transketolase**.

dihydroxyacetone transferase *see* **transaldolase**.

2,8-dihydroxyadenine an abnormal metabolite of adenine that is formed in excess by xanthine oxidase when there is a deficiency of **adenine phosphoribosyltransferase**. It is protein-bound in the circulation and actively secreted into the urine, where it is very insoluble and results in crystalluria and possibly calculus formation.

dihydroxyeicosatetraenoate *abbr.*: diHETE; any of several products resulting from dioxygenation of arachidonate at two sites, normally resulting from **lipoxygenase** action on **hydroxyeicosatetraenoates**. (6*E*,8*Z*,10*E*,14*Z*)-(5*S*,12*S*)-5,12-dihydroxyeicosa-6,8,10,14-tetraen-1-oate (*abbr.*: 5(*S*),12(*S*)-diHETE) is synthesized in human leukocytes by two successive lipoxygenase reactions and acts as a leukotriene B$_4$ antagonist. *See* **leukotriene B**. (6*E*,8*Z*,11*Z*,13*E*)-(5*S*,15*S*)-5,15-dihydroxyeicosa-6,8,11,13-tetraen-1-oate (*abbr.*: 5(*S*),15(*S*)-diHETE) is synthesized in human neutrophils and enhances neutrophil degranulation. (5*Z*,9*E*,11*Z*,13*E*)-(8*S*,15*S*)-8,15-dihydroxyeicosa-5,9,11,13-tetraen-1-oate (*abbr.*: 8(*S*),15(*S*)-diHETE) is synthesized in human leukocytes, eosinophils, and platelets and is chemotactic for human polymorphonuclear leukocytes.

3,4-dihydroxymandelate an intermediate in the formation of 4-hydroxy-3-methoxymandelate from **norepinephrine**.



3,4-dihydroxyphenylalanine *see* **dopa**.

3,4-dihydroxyphenylethylamine *see* **dopamine**.

3,4-dihydroxyphenylglycolaldehyde the product of the action of monoamine oxidase on **norepinephrine**. It is converted by an NAD$^+$-dependent aldehyde dehydrogenase to 3,4-dihydroxymandelate.



1,25-dihydroxyvitamin D$_3$ *another name for* **calcitriol**.

diiodotyrosine *abbr.*: DIT; 3,5-diiodotyrosine; iodogorgoic acid, 3,5-diiodo-4-hydroxyphenylalanine, 2-amino-3-(3,5-diiodo-4-hydroxyphenyl)propanoic acid. Residues of the L enantiomer, together with residues of the monoiodo compound, 3-iodo-L-tyrosine, are formed by iodination of L-tyrosine residues in thyroglobulin as precursors of thyroid hormones. *See* **thyroperoxidase**.



diisopropylfluorophosphonate diisopropylfluorophosphate; dyflos; *abbr.*: DIPF *or* DFP; an inhibitor of **cholinesterase** and other **serine proteases**. It phosphorylates the serine in the enzyme's active site, causing long-lasting inhibition. Recovery of enzymic activity requires *de novo* enzyme synthesis.



diisopropylphospho *symbol*: Dip; *abbr.*: DIP; the doubly esterified phosphoric acyl group, [(CH$_3$)$_2$CH–O–]$_2$P(O)–, derived from diisopropyl fluorophosphate by loss of a fluorine atom.

dikaryon *or* **dicaryon** a living cell containing two nuclei, or a structure (e.g. a mycelium) composed of such cells. It may contain nuclei of the same genetic constitution (i.e. **homokaryons**) or of differing genetic constitutions (i.e. **heterokaryons**). —**dikaryotic** *or* **dicaryotic** *adj.*

diketose any monosaccharide derivative containing two (potential) ketonic carbonyl groups. *Compare* **ketose**.

dikinase either of the two enzymes belonging to the sub-subclass EC 2.7.9, comprising phosphotransferases with paired acceptors. For example, pyruvate,orthophosphate dikinase, EC 2.7.9.1, catalyses the reversible reaction:

ATP + pyruvate + orthophosphate = AMP + phospho*enol*pyruvate + pyrophosphate.

dil. *abbr. for* dilute (def. 2).

dilate to expand or cause to expand; to make larger or wider; e.g. of the pupil of the eye or a chamber of the heart. —**dilation** *or* **dilatation** *n.*

dilatometer any instrument for measuring small changes in the volume of liquids. One design consists of a (glass) bulb fitted with a graduated hollow stem in which changes in volume may be observed. In another design, the (glass) bulb is fitted with a stopper through which runs a capillary tube so that any increased volume of the contained liquid may escape; the change in mass of the bulb and its contained liquid may then be determined. —**dilatometry** *n.*

diluent a diluting agent; *see* **dilute** (def. 1).

dilute 1 a to lower the concentration of a solute in a solution (or of particles in a suspension). **b** to mix one fluid with another thereby lowering the concentration of the first. **2** *abbr.*: dil.; describing a solution (dispersion or mixture) having a relatively low concentration (of a specified solute, type of dispersed particle, or component). *Compare* **concentrated** (def. 1).

diluted (of a solution or suspension) lowered in concentration and increased in volume by addition of solvent or other diluent. *Compare* **concentrated** (def. 2).

dilution 1 the act or process of making more **dilute** (def. 2). **2** a diluted solution or suspension. **3** the (specified) extent to which a solution or suspension has been diluted.

dilution end-point analysis the determination of the concentration of antibody in a solution by allowing a given amount of antigen to react with increasing dilutions of the antibody. The most dilute solution that produces a detectable effect, e.g. precipitation, is taken as the end point.

dilution law *see* **Ostwald dilution law**.

dilution quenching the lowering of **counting efficiency** of a liquid scintillation counter by the addition of solvent to the contents of the scintillation vial. *See also* **quenching**.

dilution rate *symbol*: D; the rate, F, at which existing medium is replaced with fresh medium in a **continuous culture**, divided by the volume, V, of the culture: $D = F/V$. Under steady-state conditions the dilution rate numerically equals the specific growth rate of the culture. *See also* **auxostat**, **chemostat**.

dilution value of a buffer *symbol*: $(\Delta pH)_{1/2}$; the change in pH that occurs when a buffer solution is diluted with an equal volume of water.

dimer 1 any molecular structure of any size in which two initially identical chemical entities have become covalently combined. **2** any macromolecular structure in which two (either identical or non-identical) subunits are noncovalently associated. *See also* **heterodimer**, **homodimer**. —**dimeric** *adj.*

dimercaprol *or* **British anti-lewisite** (*abbr.*: BAL); 2,3-dimercaptopropanol; an antidote to the arsenical war gas, lewisite, that is also useful as a chelating agent and detoxicant for heavy-metal ions and as a protective agent for sulfhydryl groups in enzymes, coenzymes, or the like.

dimerize *or* **dimerise** cause a **dimer** to be formed. —**dimerization** *or* **dimerisation** *n.*

dimerizer hypothesis *or* **dimeriser hypothesis** an unsubstantiated model of facilitated diffusion proposed to explain the rates of entry of sugars into human erythrocytes from various mixtures of sugar species. According to this hypothesis, permeation occurs as a result of pairs of sugar molecules interacting with a membrane component, followed by the association of the sugars into dimers, a form in which a reduced number of free hydrogen-bond-forming groups would be available.

dimethoxytrityl *abbr.*: DMT; 4,4′-dimethoxytriphenylmethyl; a group used for protecting hydroxyl groups (especially the 5′-hydroxyl groups of nucleosides) during chemical synthesis or other procedures. It is usually introduced by reaction with dimethoxytrityl chloride, 4,4-dimethoxytriphenylmethyl chloride. *Compare* **trityl**.



4,4-dimethoxytriphenylmethyl chloride

dimethylallyl *trans*transferase EC 2.5.1.1; *systematic name*: dimethylallyl-diphosphate:isopentenyl-diphosphate dimethylallyl-*trans*transferase; *other names*: prenyltransferase; geranyl-diphosphate synthase. An enzyme that catalyses the reaction of dimethylallyl diphosphate with isopentenyl diphosphate to form pyrophosphate and geranyl diphosphate. It participates in the pathway for the formation of **polyprenyl** groups, sesqui- and higher terpenes, and **cholesterol**.

dimethylaminoazobenzene isothiocyanate *see* **DABITC**.

dimethylaminoazobenzene sulfonyl chloride *see* **dabsyl**.

dimethylaminobenzaldehyde *see* **Ehrlich's reagent**.

dimethylaminonaphthalene sulfonyl chloride *see* **dansyl**, **dansylate**.

dimethylformamide *see* **DMF**.

dimethyl sulfoxide an unpleasant-smelling colourless liquid that is water- and alcohol-soluble. It is used as a cryoprotectant when cells are frozen for storage and for dissolved substances that are not readily water-soluble but are to be applied to cultured cells.

dimethyltryptamine *N*,*N*-dimethyltryptamine; 3-[2-(dimethylamino)ethyl]indole; a hallucinogenic agent extracted from several plant species including *Piptadenia peregrina*. It is also a metabolite of 5-hydroxytryptamine. It is a controlled substance under the US Code of Federal Regulations.



dimorphism 1 the existence of a chemical compound in two distinct physical forms, e.g. two different crystalline forms. **2** the existence of individuals belonging to two distinct forms within the same species of organism; e.g. in **sexual dimorphism** the males and females of the same species are markedly different. **3** the occurrence in certain plants of two distinct forms of leaves or other parts in the same individual. —**dimorphic** *or* **dimorphous** *adj.*

dinactin *see* **nonactin**.

dinitrofluorobenzene *abbr.*: DNFB; *a (less correct) name for* fluorodinitrobenzene. *See* **Sanger's reagent**.

dinitrogen *systematic name for* the diatomic compound N_2, commonly termed (molecular) nitrogen.

dinitrogenase reductase or nitrogenase, Fe-protein or component II of nitrogenase. A very oxygen-sensitive iron–sulfur protein that is a component of the **nitrogenase** enzyme system. It is a dimer of identical 30 kDa peptide chains. It is the electron carrier responsible for the reduction of molybdenum in **molybdoferredoxin**.

dinitrophenate the strongly yellow-coloured anion, $(NO_2)_2–C_6H_3–O^-$, formed from dinitrophenol.

dinitrophenol *abbr*.: DNP; 2,4-dinitrophenol; a pale-yellow crystalline solid. It is a powerful uncoupler of **oxidative phosphorylation**, and hence toxic.

dinitrophenyl *symbol*: Dnp; the group formed by loss of the phenolic hydroxyl group from 2,4-dinitrophenol. *See* **Sanger's method**.

dinitrophenylate to introduce a dinitrophenyl group into a compound. **—dinitrophenylation** *n.*

dinoprost *a generic name for* prostaglandin $F_{2\alpha}$. *See* **prostaglandin**.

dinor+ *prefix (in chemical nomenclature)* indicating shortening of a carbon chain or contraction of a ring by two methylene groups. *See also* **nor+**.

DInR *abbr. for Drosophila* insulin receptor.

Dintzis procedure a procedure for investigating the direction and rate of biosynthesis of a polypeptide. It requires the addition to a protein-synthesizing system *in vitro* of a **pulse** of a labelled form of an amino acid. After various periods of elapsed time completed molecules of the polypeptide are isolated. Over all the samples, a gradient of radioactivity (increasing from the N terminus to the C terminus of the chain) is found, indicating that the pulse tends to enter the more C-terminal positions and that the more N-terminal region has already been synthesized. By these means it was clearly shown for the first time that polypeptide chains are assembled from amino acids on a template and that synthesis takes place from its N terminus. [After Howard Marvin Dintzis (1927–), US biochemist, who conceived the procedure and described its use in 1961.]

dinuclear *or* **binuclear** describing a complex containing two metal atoms.

dinucleotide **1** any **oligonucleotide** consisting of two mononucleotides in 3′–5′ phosphodiester linkage. **2** any **nucleotide coenzyme** in which either of the mononucleotides adenosine 5′-phosphate or adenosine 2′,5′-bisphosphate is in 5′–5′ diphosphate (i.e. phosphoric anhydride, pyrophosphate) linkage with nicotinamide mononucleotide or riboflavin 5′-phosphate.

dinucleotide fold *an alternative name for* **nucleotide binding fold**.

diode **1** a semiconductor device, containing one p–n junction, used in circuits to rectify **alternating current** to a **direct current**: semiconductor diode. **2** a thermionic valve containing an anode and a cathode and functioning in a similar manner: **thermionic diode**.

dioestrus *see* **estrous cycle**.

diol any organic compound (or portion of such a compound) containing two hydroxyl groups.

diol lipid any of various neutral lipids that are fatty-acid esters of dihydroxy alcohols (i.e. are not glycerides). They occur in small amounts in seed oils; e.g. 1-palmitoleoyl-2-*trans*-vaccenoyl-*erythro*-butane-2,3-diol, which is found in seeds of *Coix lachrima*.

dioxin any of a family of over 200 chlorinated heterocyclic compounds that are persistent in the environment. The term is most commonly applied to 2,3,7,8-tetrachlorodibenzo-*p*-dioxin (TCDD), which is an impurity in the defoliant Agent Orange and in the pesticide 2,4,5-T. Dioxins are also produced when chlorinated materials such as plastics are burned. They are known to cause cancer, birth defects, miscarriages, and skin diseases (chloracne).



TCDD

dioxin receptor *see* **ARNT**.

dioxygen *systematic name for* the diatomic compound O_2, commonly termed (molecular) oxygen. *Compare* **trioxygen**.

dioxygenase any oxidoreductase enzyme of the sub-subclass EC 1.13.11. Such enzymes catalyse reactions involving the incorporation of both oxygen atoms of dioxygen into a second substrate; *see* e.g. **ethylene-forming enzyme**, **benzoate 1,2-dioxygenase**.

DIP **1** *abbr. for* the diisopropylphospho group. **2** *abbr. for* database of interacting proteins; *see* **specialist database**.

dipentene a racemic mixture of the (+) and (–) enantiomers of **limonene**.

dipeptide any **oligopeptide** consisting of two (α-)amino-acid residues.

dipeptide mimic any synthetic dipeptide that inhibits **angiotensin-converting enzyme**. An example is **captopril**.

dipeptidyl-peptidase *abbr*.: DPP; any member of a group of enzymes belonging to the sub-subclass EC 3.4.14, dipeptidylpeptide and tripeptidylpeptide hydrolases, that release an N-terminal dipeptide from an oligo- or polypeptide. **Dipeptidyl-peptidase I** (*or* cathepsin C), EC 3.4.14.1, is a lysosomal cysteine-type peptidase that acts on polypeptides, but not if the terminal amino-acid residue is Arg or Lys, and not if either of the adjacent residues is Pro. **Dipeptidyl-peptidase II**, EC 3.4.14.2, is a lysosomal serine-type peptidase that acts preferentially on tripeptides. **Dipeptidyl-peptidase III**, EC 3.4.14.4 (*other names*: red cell angiotensinase; enkephalinase B), is a cytosolic serine-type peptidase that acts on tetra- or longer peptides. **Dipeptidyl-peptidase IV**, EC 3.4.14.5 (*other names*: dipeptidyl aminopeptidase IV; Xaa-Pro-dipeptidyl-aminopeptidase; Gly-Pro naphthylamidase; post-proline dipeptidyl aminopeptidase IV), catalyses the release of an N-terminal dipeptide, Xaa-Xbb-|-Xcc, from a polypeptide, preferentially when Xbb is Pro, provided Xcc is neither Pro nor hydroxyproline. The protein is a serine proteinase, type II transmembrane glycoprotein, and a homodimer. **Dipeptidyl-dipeptidase**, EC 3.4.14.6, is a thiol-activated peptidase from *Brassica oleracea* that acts preferentially on tetrapeptides.

dip-F *symbol for* diisopropyl fluorophosphate.

DIPF *abbr. for* diisopropylphosphofluoridate. *See* **diisopropyl fluorophosphonate**.

diphenylamine reaction the reaction of an acidic solution of diphenylamine with deoxypentoses to give a blue colour. It is used in the quantitative determination of DNA, and alone or in combination with other reagents as a detection reagent.

2,5-diphenyloxazole *abbr*.: PPO; a compound used as a primary scintillant in scintillation counting. *See* **scintillation counter**. *See also* **scintillation cocktail**.



2,5-diphenyloxazole

diphosphate **1** the tetravalent anion, $P_2O_7^{4-}$, derived from diphosphoric acid (earlier known as pyrophosphoric acid), heptaoxodiphosphoric(V) acid, $(HO)_2PO–O–PO(OH)_2$. **2** any mixture of free diphosphoric acid and its anions. *see also* **inorganic diphosphate**, **pyrophosphate**. **3** any (partial or full) salt or ester of diphosphoric acid. **4** any organic compound containing two phosphoric residues linked by an oxygen atom. **5** name of the univalent group $–O–PO(OH)–O–PO(OH)_2$ (irrespective of its state of ionization). **6** *formerly*, any organic compound containing two independent phosphoric residues attached to different parts of the molecule; now incorrect, use **bisphosphate**.

(+)diphospho+ **1** *prefix to (or infix in)* a chemical name indicating the presence in ester (or diester) linkage of a diphosphoric residue. **2** *formerly*, *prefix* to a chemical name indicating the presence of two independent phosphoric residues in ester linkages; now incorrect, use **bisphospho+**.

diphosphoglycerate *former name for* **1** **2,3-bisphospho-**D-glycerate. **2** **3-phospho-**D-glyceroyl phosphate.

diphosphoglycerate pocket *abbr.*: DPG pocket; *see* **bisphosphoglycerate pocket**.

diphosphoinosotide *former name for* **phosphatidylinositol 4-phosphate**.

diphosphopyridine nucleotide (oxidized) *abbr.*: DPN; *obsolete name for* the oxidized form of nicotinamide adenine dinucleotide; *see* **NAD⁺**.

diphosphopyridine nucleotide (reduced) *abbr.*: DPNH; *obsolete name for* the reduced form of nicotinamide adenine dinucleotide; *see* **NADH**.

diphosphoric *symbol*: *PP or* (in the one-letter convention for nucleotides) pp; *general name for* a residue of diphosphoric acid, $(HO)_2PO–O–PO(OH)_2$, whether singly or multiply attached through oxygen to other groups and whether or not any residual hydroxyl groups are dissociated.

diphthamide a modified histidine residue on EF-2. *See* **elongation factor**.



diphtheria toxin an enzyme toxin produced by strains of *Corynebacterium diphtheriae,* which are lysogenic for corynephage, whose genome contains the *tox* structural gene (carried by phage β*tox*⁺). The toxin has the activity of EC 2.4.2.36; *recommended name*: NAD⁺-diphthamide ADP-ribosyltransferase; *systematic name*: NAD⁺:peptide-diphthamide *N*-(ADP-D-ribosyl)transferase. It catalyses the reaction between NAD⁺ and peptide diphthamide to form nicotinamide and peptide *N*-(ADP-D-ribosyl)diphthamide. The toxin molecule is a proenzyme comprising a single polypeptide chain of ~62 kDa; the toxin is lethal for susceptible animals at around 100 ng per kg of body mass. On cleavage of one peptide bond and one disulfide bond, the toxin splits into an N-terminal fragment, A (21.15 kDa), the enzyme that specifically inhibits protein synthesis by catalysing transfer of the ADP-ribosyl moiety of NAD⁺ to eukaryotic EF-2 (*see* **elongation factor**) in the cytoplasm, and a C-terminal fragment, B (~40 kDa), that is required for recognition of specific surface receptors on sensitive cell membranes. Fragment B is necessary for the toxicity of fragment A, as it allows the latter to cross the plasma membrane.

dipicolinate 2,6-pyridinedicarboxylate; a substance that is abundant (10%) in bacterial spores. Its production is a striking feature of sporulation and it may play a part in making spores resistant to heat.



dipicolinic acid

diplochromosome a ‘double chromosome’, comprising the arms of two daughter chromosomes attached to a single centromere. It arises due to failure of the centromere to divide following duplication of a chromosome.

diploid describing a cell or nucleus having two sets of homologous **chromosomes**; i.e. containing twice the **haploid** number. —**diploidy** *n.*

diploid state the chromosome state of a cell in which each type of chromosome, except for the sex chromosomes, is always represented twice.

diplotene the fourth phase of prophase I in **meiosis**.

dipolar bond *or* **coordinate bond** *or* **coordinate covalence** *or* **coordinate link** *or* **dative bond** *or* **semipolar double bond** a covalent bond formed (actually or conceptually) between two initially uncharged moieties by **coordination** (def. 2). The consequent generation of opposing charges on the linked structures creates a **dipole**; e.g.

$$R_3N\colon + \ddot{\underset{\cdot\cdot}{O}}\colon \rightarrow R_3N^{+}–\ddot{\underset{\cdot\cdot}{O}}\colon^{-}.$$

The term is preferred to the alternatives, which are now either obsolescent or obsolete. *Compare* **polar bond**.

dipolar correlation time time taken for an atomic spin system to rotate through one radian from its previous orientation, the rotation being caused by interactions with other, neighbouring spins.

dipolar interaction the interaction between two **magnetic moments** due to the effect of the magnetic field of one on the other.

dipolar ion *or* **zwitterion** a molecule containing ionic groups of opposite charge in equal numbers. *Compare* **amphion**.

dipole a pair of equal and opposite electric charges or magnetic poles (especially in a molecular entity) separated by a, usually, small distance. —**dipolar** *adj.*

dipole moment *or* **electric dipole moment** *symbol*: ***p*** *or* ***μ***; a vector quantity equal to the product of the absolute magnitude of either charge in a dipole (the two are equal in an uncharged molecule) multiplied by the distance separating them. If a molecule possessing a dipole moment is placed in a uniform electric field, it will be subject to torque tending to line it up in the direction of the field. $p = \Sigma Q_i \boldsymbol{r}_i$ coulomb metres, where Q_i is the charge and r_i is the position vector.

dipyridamole an inhibitor of cyclic AMP phosphodiesterase and 5-lipoxygenase, used as a coronary vasodilator.



4 dipyridamole

diradical *an alternative term for* **biradical**.

direct current *abbr.*: d.c. *or* DC; an electric current that flows in only one direction.

directional cloning a procedure that ensures the insertion of a DNA insert into a plasmid or other cloning vector in a known orientation with respect to the flanking vector sequences. It is accomplished by providing each end of the insert with different restriction endonuclease sites that are also present in the multiple cloning site of the vector.

directional selection any genetic **selection** that shifts the population mean in the direction desired by the breeder.

dis+ *prefix* indicating **1** reversal. **2** deprivation, exclusion, or lack. **3** negation. **4** removal or release.

dis2 a gene in fission yeast that is the equivalent of ***DIS2 S1*** in budding yeast.

disabled strain any strain of organism, especially a microorganism, that because of some character, e.g. a nutritional requirement, is unable to reproduce in the normal environment, including the normal host, and can only survive in laboratory conditions.

disaccharidase any enzyme within sub-subclass EC 3.2.1 that hydrolyses a disaccharide to its constituent monosaccharides.

disaccharidase deficiency *see* **lactase deficiency**.

disaccharide any **oligosaccharide** consisting of two monosaccharide residues. It may be a **nonreducing disaccharide** or a **reducing disaccharide**, depending on the mode of linkage between the residues.

disalicylidenepropanediamine *abbr.*: DSPD; *N*,*N*′-disalicylidene-1,3-diaminopropane; an inhibitor of photosynthetic electron flow at the ferredoxin level.



disassociation *a variant form of* **dissociation** (def. 1).

disc *a variant spelling (esp. Brit.) of* **disk**.

DISC *abbr. for* death-inducing signalling complex; the complex formed by **FasL**, **Fas**, **FADD** and procaspase 8, that initiates the caspase cascade and apoptosis.

DISC1, DISC2 human genes at locus 1q42.1 that are disrupted in schizophrenia with a balanced translocation t(1;11)(q42.1;q14.3).

discharge **1** *(in physics)* the release of an electric charge, e.g. from a condenser or a battery, or the equalization of an electric potential difference. **2** *(in physics)* the intermittent or continuous flow of electricity through a gas by the formation of electrons and ions. **3** *(in medicine)* an abnormal secretion from a body cavity, or the secretion from a wound.

discoidin any of a group of endogenous carbohydrate-binding proteins (lectins) produced by cells of the slime mould *Dictyostelium discoideum* during differentiation. Similar to **pallidin**, they may be involved in cell adhesion.

discoidin domain *or* **discoidin-like domain** a protein domain with a jelly-roll fold first described in the lectin discoidin from the cellular slime mould *Dictyostelium discoideum*. Proteins with discoidin domains are implicated in interactions with cell-surface carbohydrates.

discoidin domain receptor any of the family of membrane receptors with a discoidin domain. They are tyrosine kinases that are activated by binding to collagen in the extracellular matrix and differ in this respect from other receptor tyrosine kinases.

discontinuous epitope an immunological determinant (i.e. **epitope**) on an antigen that comprises different sections of a protein molecule brought together by folding of the polypeptide chain. *Compare* **continuous epitope**.

discordance *(in genetics)* the state in which a character or gene is present in only one of two comparable individuals or species; for example, when only one of a pair of twins has a particular character. *Compare* **concordance**. **–discordant** *adj.* –**discordantly** *adv.*

discriminator **1** any (electronic) device that gives an output signal only when the input signal is above a certain preset level or has certain preset characteristics. **2** any criterion used in sorting objects, experimental results, signals, etc.

disease any anatomical abnormality or impairment of the normal functioning of an organism or of any of its parts other than one arising directly from physical injury. It may be caused by environmental factors (e.g. malnutrition, toxic agents, etc.), infective agents (bacteria, viruses, etc.), inherent defects in the organism (e.g. genetic disease), or any combination of these factors.

disequilibrium assay any radioimmunoassay in which the reagents are not added at the same time and are not allowed to reach thermodynamic equilibrium. *Compare* **equilibrium assay**.

Disheveled a transduction component of Wnt/Frizzled signalling, that protects β-catenin against phosphorylation and degradation via ubiquitination and proteasomes. *See* **catenin**.

disinfectant a substance that destroys or inhibits pathogenic microorganisms, but not necessarily bacterial spores, in the inanimate environment. *Compare* **sanitizer**, **sterilant**.

disinfection the destruction or removal of all organisms capable of giving rise to infection. *Compare* **sterilize** (def. 1).

disintegration *or* **nuclear disintegration** any process of nuclear **decay** involving a splitting into more nuclei or the emission of particles (either spontaneously or as a result of a collision).

disintegration constant *or* **decay constant** *symbol*: λ; for a radionuclide, the probability of the nuclear decay of one of its nuclei in unit time. It is given by:

$$\lambda = -(1/t)\ln(A/A_0),$$

where A_0 is the radioactivity at zero time and A is the activity at time t. *See also* **average life**.

disintegrin any of a group of compounds that act as inhibitors of platelet–fibrinogen interaction and other aggregations. They are found in certain snake venoms.

disjunction the separation of chromosomes at **anaphase** during nuclear division.

disk *or (esp. Brit.)* **disc** **1** a circular, flattened structure, or any object having or resembling such a shape. *See also* **retinal rod**. **2**. *(in computing)* a disk-shaped device on which files are stored electromagnetically.

disk (gel) electrophoresis a technique of separation by electrophoresis in which a tube is loaded first with the sample, applied in a gel support (usually polyacrylamide), followed by a spacer gel and finally by the running gel, in which separation occurs. The gels are so formed as to give a gradient of progressively smaller pore size, and a discontinuous buffer system is used. This arrangement causes the separating components of the applied mixture to stack as a series of very thin bands and permits very high resolution.

dismembrator an ultrasonic device for rapidly disrupting cells in bacteriological and cytological studies. It consists of a probe oscillating at ≈20 kHz and an acoustical power of up to 150 W that is dipped into a cell suspension, contained in either a stainless-steel or glass beaker.

dismutase *see* **superoxide dismutase**.

dismutation a chemical reaction in which a single compound serves both as an oxidizing agent and as a reducing agent; e.g. the reaction of two molecules of pyruvate and one of water giving rise to one molecule each of lactate, acetate, and carbon dioxide. *Compare* **disproportionation**.

disodium chromoglycate *see* **cromolyn**.

disodium etidronate *see* **etidronate**.

disome a **polysome** in which two ribosomes are attached to a strand of messenger RNA. *Compare* **monosome**, **nucleodisome**.

Dispase *proprietary name for* a highly stable neutral metalloproteinase obtained from *Bacillus polymyxa*. It is so named from its use, alone or with collagenase, for gentle enzymic disaggregation and dispersal of animal tissues into separated cells for primary **cell culture** and for redispersal of cells on subculturing. *See also* **Chaotropase**, **Pronase**.

disperse phase *or* **dispersed phase** the phase in a two-phase system that consists of the particles in a colloid, emulsion, or suspension.

dispersion **1** the selective separation of an inhomogeneous emission according to some criterion (especially frequency, particle mass, speed, or energy); e.g. the separation of heterochromatic light into its components. **2** any system in which particles of any nature (e.g. solid, liquid, gas, or composite) are dispersed in a solid, liquid, or gas of different composition. **3** *(in statistics)* the extent to which values of a statistical frequency distribution are scattered around a mean or median value.

dispersion force *or* **London force** a long-range attractive interaction occurring between atoms or molecules whether or not they have permanent charges or dipole moments. Since the electrons in an atom or molecule are moving, an instantaneous dipole moment is induced in the atom or molecule; this averages to zero over a short time. This instantaneous dipole moment will induce an oppositely oriented dipole moment in a neighbouring atom or molecule in a manner that does not time-average to zero. This interaction energy, $V(R)$, is given approximately by:

$$V(R) = -\begin{matrix} 3 & h\nu_A\nu_B & \alpha_A\alpha_B & 1 \\ 2 & \nu_A + \nu_B & (4\pi\varepsilon_0) & R^6 \end{matrix}$$

where ν_A and ν_B are the approximate frequencies of the first electron transitions of entities A (~~and B, α_A~~) ~~and α_B are~~ their polarizabilities, ε_0 is the permittivity of vacuum, h is the Planck constant, and R the distance between the entities. [After Fritz London (1900–54), German-born US physicist.]

dispersive replication of DNA *see* **replication of DNA**.

displacement binding a technique in which the displacement of radioligand bound to a population of receptors is measured as the concentration of an unlabelled ligand, which binds to the same receptors, is increased. It is used to distinguish different affinity states of the receptor population or receptor selectivity of the radioligand.

displacement chromatography an analytical chromatographic technique in which a mixture is applied to a chromatographic column and the components of the mixture are then successively displaced by elution with a solution containing another substance of higher affinity for the column material than that of the most firmly held component. The relative proportions of the components of the mixture are determined by **frontal analysis** of the eluate.

displacement electrophoresis *an alternative term for* **isotachophoresis**.

displacement loop *an alternative name for* **D-loop**.

displacement reaction a chemical reaction in which an atom or group is displaced from its covalent attachment to a central (frequently a carbon) atom following an attack by either an **electrophile** or a **nucleophile**.

disproportionation any chemical reaction of the type:

$$A + A \rightarrow A' + A'',$$

where A, A′, and A″ are different chemical species. *Compare* **dismutation**.

disRNA *abbr. for* **Dicer**-substrate RNA **shRNA**s with 29 bp stem and 2 nt 3′ overhangs. They are thought to be more potent inducers of **RNAi** than shorter hairpins.

DIS2 S1 a gene of budding yeast encoding protein phosphatase I (its equivalent in fission yeast is ***dis2***). In the absence of gene function **mitosis** is arrested. The product in *Saccharomyces cerevisiae* consists of 312 amino acids (35.93 kDa).

dissimilation *a less common alternative term for* **catabolism**. *Compare* **assimilation**. **—dissimilatory** *adj.*

dissimilatory nitrate reduction *see* **nitrate reduction**.

dissociation 1 *or* **disassociation** a reversible splitting of a chemical substance into simpler entities; *compare* **association**. In this sense, the term may be applied to: **a** the **heterolysis** of a covalent bond, yielding, in the case of an initially uncharged molecule, positively and negatively charged ions: **ionic dissociation**; **b** the disaggregation of a macromolecular homopolymer or heteropolymer into its constituent units (i.e. **protomers**), usually by a stepwise process through components of intermediate size (i.e. **oligomers**) and without rupture of covalent bonds; **c** the breakdown of an enzyme–substrate complex, which may or may not involve cleavage of a covalent bond; or **d** the separation of a complex of two or more molecules into the constituent molecules. **2** a splitting of a chemical substance by the **homolysis** of a covalent bond, yielding **radicals**. **3 translocation** between a large chromosome and a small supernumerary one, in effect splitting the large chromosome into two chromosomes. **4** separation (induced or spontaneous) of the nuclear components of a heterokaryotic **dikaryon**. **—dissociated**, **dissociable, dissociative** *adj.*; **dissociate** *vb.*

dissociation constant *symbol*: K_{diss} *or* K_d; the **equilibrium constant** for the reversible breakdown of a complex or a chemical compound into two or more simpler entities; the reciprocal of the **association constant**, K_{ass}. In some cases, an **apparent dissociation constant** (K'_d) is determined (for the distinction *see* **equilibrium constant**). It is also known as the **ionization constant** in cases where a substance dissociates into ions. For a dissociation (or ionization) of the general type $AB \rightleftharpoons A + B$, the dissociation (or ionization) constant is given by:

$$K_{diss} = [A][B]/[AB] = 1/K_{ass}.$$

dissociation energy *symbol*: *D*; the enthalpy (per mole) required to break a given chemical bond in a specified chemical entity by homolysis.

distal situated furthest from an origin, central line, or point of attachment.

distal protein a protein that binds late in the assembly of complex structures, such as ribosomes. *Compare* **proximal protein**.

distance matrix a set of pairwise distances between taxa, based on some observation such as the number of observed nucleotide differences, the reconstructed distances between sequences (based on some model of sequence evolution), or observed morphological, immunological, ecological, or behavioural differences. Distance matrices are often used to construct dendrograms.

distil *or (US)* **distill** to undergo, to subject to, to purify, or to separate by **distillation**.

distillate the liquid (or solid) product of **distillation**.

distillation the act or process of evaporating a liquid by boiling so that its components, which are vaporized at different temperatures or at different rates, can be separated and condensed back to a liquid (or solid). It is used to purify one liquid from a mixture of liquids or from (dissolved) solids. *See* **fractional distillation**.

distribution 1 *(in chemistry) an alternative term for* **partition**. **2** *(in biochemistry)* the pattern of occurrence of a substance within or between cells or tissues, or within a group of organisms, taxa, etc. **3** *(in biology)* the geographical range or pattern of occurrence of a particular taxon or genetic variant. **4** *(in statistics)* the frequency of occurrence of a variable at each of a number of discrete values. *See also* **normal distribution**.

distribution coefficient 1 *an alternative term for* **partition coefficient**. **2** in **gel chromatography**, the fraction of the stationary phase that is available for diffusion of a given solute species.

distribution law *an alternative name for* **partition law**.

distributive 1 of, relating to, or characterized by distribution. **2** *(in molecular biology) or* **nonprocessive** describing (the action of) any enzyme or catalytic complex that progressively synthesizes or degrades a biopolymer by effecting several or many cycles of the same type of reaction or reaction sequence and dissociates from the template or intermediate product after each catalytic event. *Compare* **processive**. **—distributively** *adv.*

disulfide *or* **disulphide** *(in organic chemistry)* any compound containing two bivalent sulfur atoms linked by a covalent bond and each attached to a carbon atom.

disulfide bond *or* **disulfide bridge** *or* **disulfide link** a covalent bond between two sulfur atoms. Such bonds in biomolecules are usually formed by the oxidation of **sulfhydryl groups** in two neighbouring cysteine molecules or residues. Disulfide bonds may link two half-cystine residues in the same polypeptide chain, as in ribonuclease, or in different peptide chains, as in insulin or oxidized glutathione, and they often are important in maintaining the three-dimensional structure of polypeptides and proteins. They may also be reversibly formed in oxidation–reduction reactions as in the interconversion of lipoamide and dihydrolipoamide. Also: **disulphide bond** *or* **disulphide bridge** *or* **disulphide link**.

disulfide interchange *or* **disulphide interchange** any chemical reaction in which there is an interchange in the groups attached to two or more disulfide bonds; e.g.:

$$R–S–S–X + Y–S–S–Z \rightleftharpoons R–S–S–Y + X–S–S–Z,$$

where r, X, Y, and Z are different polypeptide chains or other SH-bearing molecules. *See also* **protein disulfide isomerase**.

disulfide knot *or* **disulphide knot** a region at the centre of a **fibrinogen** molecule where the six polypeptide chains are linked together by eight disulfide bonds. *Compare* **cystine knot**.

disulfiram *trivial name for* tetraethylthiuram disulfide; bis(diethylthiocarbamoyl) disulfide; a drug used to deter alcohol abuse in the treatment of alcoholism. Alcohol ingestion after disulfiram causes vasomotor disturbances, nausea, vomiting, and even unconsciousness and death. It acts by inhibiting the enzyme acetaldehyde dehydrogenase and hence slows the removal of acetaldehyde. It occurs naturally in the otherwise edible fruit body of the agaric mushroom *Coprinus atramentarius*. One proprietary name is Antabuse.



DIT *abbr. for* diiodotyrosine.

di-*tert*-butyl-*p*-cresol *or* **butylated hydroxytoluene** 2,6-di-*tert*-butyl-4-methylphenol; a common antioxidant used in foods containing fats.



dithioerythritol *abbr.*: DTE; *erythro*-1,4-dimercapto-2,3-butanediol; both this and **dithiothreitol** are known as **Cleland's reagent**. It has similar properties to dithiothreitol but is less often used.

dithiothreitol *abbr.*: DTT; *threo*-1,4-dimercapto-2,3-butanediol; both this and **dithioerythritol** are known as **Cleland's reagent**. A water-soluble solid compound which, because of its low redox potential (–0.33 V, pH 7.0), is capable of maintaining monothiols completely in the reduced state and of reducing disulfides quantitatively, so becoming oxidized to a cyclic disulfide; it has little tendency to be oxidized directly by air.

diuresis increased or excessive flow of urine.

diuretic **1** producing an increase in the volume of urine. **2** any agent that increases the volume of urine.

diurnal **1** occurring during the day. **2** repeating every day; having a periodicity of approximately 24 hours. *Compare* **circadian**.

Diuron *see* **DCMU**.

divalent metal transporter 1 *abbr.*: DMT1; *an alternative name for* NRAMP2. *See* **Nramp1**.

divergent evolution *or* **divergence** biological evolution that tends to produce an increasing difference in some characteristic(s) between initially similar groups of, e.g., organisms or gene products. *Compare* **convergent evolution**.

divergent transcription the transcription of adjacent genes from opposite strands of duplex DNA and in opposite directions.

dixenic *see* **synxenic**.

Dixon plot a graphical method for the presentation of enzyme-kinetic data by which a Michaelis constant, K_m (*see* **Michaelis kinetics**), or an **inhibitor constant**, K_i, may be determined. The method is primarily used as a means of readily obtaining K_i. the reciprocal of the initial velocity (i.e.$1/V$) is plotted against a series of inhibitor concentrations [I], at constant substrate concentration, [S]. When this is done for a number of values of [S], the resulting lines intersect at a point corresponding to K_i. The value of [I] at which this occurs is to the left of the ordinate (for competitive inhibition) and corresponds to $-K_i$. For non-competitive inhibition the lines meet on the abscissa. [After Malcolm Dixon (1899–1985), British enzymologist, who described it in 1972.]

dizygotic describing twin offspring formed from two separate ova fertilized by two separate sperms. *Compare* **monozygotic**.

DJ-1 a human gene (locus at 1p36) encoding a 189-residue protein that is widely distributed in tissues, including brain, is highly conserved, and may be involved in the response to oxidative stress. Mutations in it are associated with an autosomal recessive early-onset form of Parkinson's disease.

DL *prefix (in chemical nomenclature)* denoting an equimolar mixture of D and L enantiomers. *See* **D/L convention**.

dl- *prefix (in chemical nomenclature)* formerly used to denote **racemic**; now obsolete, use (±)-, *racemo*-, or *rac*-.

D/L convention a convention of symbols used to designate the **absolute configuration** around a chiral element in α-amino acids, cyclitols, monosaccharides, and derivatives of these classes of compounds. Within these classes it can be applied to any molecule of the type R_1CHXR_2 that can be oriented in a **Fischer projection** with the most highly oxidized atom at the top; then if X is on the right the configuration is designated by the prefix D-, whereas if X is on the left the configuration is designated by the prefix L-, relative to D-(+)- or L-(–)-glyceraldehyde. Racemic (i.e. equimolar) mixtures of D and L enantiomers are designated by the prefix DL-. α-Amino acids are designated D- or L- according to the configuration at the α-carbon atom. Cyclitols are designated D- when the formula is drawn in such a way that the substituent on the lowest-numbered asymmetric carbon atom is above the plane of the ring and the numbering is anticlockwise, and L- when it is clockwise; the locant of the defining centre should precede the prefix D- or L-, e.g. 1D-1-*O*-methyl-*myo*-inositol. For monosaccharides the highest-numbered chiral centre (i.e. carbon atom) is the reference atom determining whether the monosaccharide is D or L. When a compound contains more than one class of residue the configuration designators are $\mathrm{D_s}$ or $\mathrm{L_s}$ if they apply to an amino-acid residue, $\mathrm{D_c}$ or $\mathrm{L_c}$ to a cyclitol residue, and $\mathrm{D_g}$ or $\mathrm{L_g}$ to a monosaccharide residue (the subscript s denoting the reference α-amino acid serine, the subscript c denoting cyclitol, and the subscript g denoting the reference monosaccharide glyceraldehyde). The absolute configurations of chiral compounds of classes other than those listed are designated by application of the **sequence rule**. *Compare* ***ambo-***, ***d-***, ***l-***, ***dl-***, **isomerism**.

D-loop *or* **displacement loop** a DNA structure generated when an additional strand of DNA is taken up by a DNA duplex, so that one strand of the original duplex is displaced, forming a D-shaped loop. Formation of a D-loop is favoured in negatively supercoiled DNA and can occur spontaneously. Such D-loops are formed in covalently closed mammalian mitochondrial DNA, and are prominent as intermediates in genetic recombination, in which their formation is catalysed by strand-exchange enzymes, the best characterized of which is the RecA protein of *Escherichia coli*.

DMEM *abbr. for* Dulbecco's Modification of Eagle's Medium; one of many formulations of culture media for the growth of mammalian cells.

DMF *or* **DMFA** *abbr. for N,N*-dimethylformamide; a neutral liquid of low melting point (–61°C) and a reasonably high boiling point (153°C), miscible with water and with most common organic solvents, hence sometimes termed the **universal solvent**.

DMR *abbr. for* differentially methylated region. In the epigenetic regulation of parentally imprinted genetic loci, one allele is methylated at **Cp G islands** within the DMR and is not transcribed, while the other allele is unmethylated and is transcribed. DMRs can map to the promoter regions of imprinted genes but are also found in non-promoter sequences. *IGF2* is an example of a maternally imprinted, paternally expressed gene that contains a DMR.

DMSO *abbr. for* dimethylsulfoxide (use discouraged, Me_2SO preferred).

DMT *abbr. for* the dimethoxytrityl group.

dna *symbol for* any of various bacterial genes that are involved in DNA replication. The following applies to *Escherichia coli*: *dnaA* encodes a 52 kDa protein (DnaA) of which up to 30 subunits bind to the *oriC* region and unwind it at the start of replication; *dnaB* encodes a helicase that, as a 300 kDa homohexamer of DnaB proteins, causes unwinding beyond the *oriC* region complexed to DnaA proteins; *dnaC* encodes DnaC (29 kDa), required for binding of DnaB; *dnaG* encodes DnaG, which with DnaB constitutes the ≈600 kDa assembly called a **primosome**.

DNA *abbr. and common name for* **deoxyribonucleate** (def. 1), or **deoxyribonucleic acid**; one of the two main types of **nucleic acid**, consisting of a long, unbranched macromolecule formed from one, or more commonly, two, strands of linked deoxyribonucleotides, the 3′-phosphate group of each constituent deoxyribonucleotide being joined in 3′,5′-phosphodiester linkage to the 5′-hydroxyl group of the deoxyribose moiety of the next one. *Compare* **RNA**. The absence of a 2′-hydroxyl group on each deoxyribose moiety renders these phosphodiester linkages resistant to hydrolytic attack by alkali, in contrast to those of RNA. A DNA strand, unless circular, has polarity, with one 5′ end and one 3′end, the two strands in duplex DNA having opposed polarities. Two purines, adenine and guanine, and two pyrimidines, cytosine and thymine, are the major bases present. The linear sequence of the purine and pyrimidine bases carries genetic information, whereas the deoxysugar and phosphoric residues play a structural role; the base sequence is written in the 5′→3′ direction. *See also* **double helix**. Specific forms, functions, molecules, or preparations of DNA may be designated by prefixes or suffixes, thus:

A-DNA *or* **DNA-A**, **A form** of DNA; **amDNA**, **anti-messenger DNA**; **B-DNA** *or* **DNA-B**, **B form** of DNA; **cDNA**, **complementary DNA**; **cccDNA**, **covalently closed circular DNA**; **C-DNA** *or* **DNA-C**, **C form** of DNA; **ctDNA**, chloroplast DNA; **dsDNA**, double-strand(ed) DNA (*see* **duplex DNA**); **iDNA**, **intercalary DNA; msDNA**, **multicopy single-strand(ed) DNA; mtDNA**, **mitochondrial DNA; nDNA**, nuclear DNA; **pDNA**, plasmid DNA; **rDNA**, **ribosomal DNA**; **recDNA**, **recombinant DNA**; **rfDNA**, **replicative-form DNA**; **rtDNA**, **recombinant DNA; scDNA**, **single-copy DNA**; **ssDNA**, **single-strand(ed) DNA; tDNA**, **transfer DNA; T-DNA**, transfer DNA of the **Ti plasmid**. *See* full entry for **T-DNA**. **Z-DNA** *or* **DNA-Z**, **Z form** of DNA.

DnaA protein *see* ***dna***.

DNAase *or* **DNAse** *abbr.* sometimes used for **deoxyribonuclease**; DNase is more usual.

DNA-binding protein F/G *see* **matrin**.

DNA blot transfer *see* **blot-transfer technique**.

DnaB protein *see* ***dna***.

DNA chip *an alternative name for* DNA **microarray**.

DNA cloning *see* **molecular cloning**.

DnaC protein *see* ***dna***.

DNA cycle *see* **cell-division cycle**.

DNA-dependent DNA polymerase *see* **DNA polymerase**.

DNA-dependent protein kinase *see* **DNA-PK**.

DNA-dependent RNA polymerase *see* **RNA polymerase**.

DNA-directed DNA polymerase *recommended name for* **DNA polymerase**, EC 2.7.7.7.

DNA-directed RNA polymerase *recommended name for* **RNA polymerase**, EC 2.7.7.6.

DNAfingerprinting a term sometimes used to refer to **genetic profiling**.

Dna G protein *see* **DNA**.

(DNA) glycosylase *or* **DNA glycosidase** any of a group of glycohydrolases that initiate repair of DNA by hydrolysing N-glycosyl bonds linking deoxyribose residues with modified or incorrect bases to generate apurinic or apyrimidinic sites in the DNA and release the bases. They include DNA-3-methyladenine glycosidase I (EC 3.2.2.20), DNA-3-methyladenine glycosidase II (EC 3.2.2.21), and formamidopyrimidine-DNA glycosidase (EC 3.2.2.23). The enzymes form part of the pathway of base-excision repair, which acts on oxidative or nonoxidative damage, as determined by the specificity of individual enzymes. Sequences tend to be related; examples from *Escherichia coli* are: DNA-3-methyladenine glycosidase I, which is constitutive and specific to the named base; and DNA-3-methyladenine glycosidase II, which is inducible and releases any of 3-methyladenine, 3-methylguanine, 7-methylguanine, *O*-2-methylthymine, and *O*-2-methylcytosine.

DNA gyrase *see* type II **DNA topoisomerase**.

DNA helicase an enzyme that catalyses unwinding of the DNA double helix during DNA replication and repair. It requires ATP. An example is the *rep* gene product from *Escherichia coli.*

(DNA) joinase *an alternative name for* **DNA ligase**.

DnaK *or* **heat-shock protein 70** *abbr*.: hsp70; a **heat-shock protein** that plays an essential role in the initiation of DNA replication in **lambda phage,** and, in combination with DnaJ protein, acts to release proteins O and P.

DNA ligase *or* **(DNA) joinase** *or* **DNA repair enzyme** either of two enzymes that restore broken phosphodiester bonds in deoxyribonucleic acids. (1) **DNA ligase (ATP)** EC 6.5.1.1; *systematic name*: poly(deoxyribonucleotide):poly(deoxyribonucleotide) ligase (AMP-forming); *other names*: polynucleotide ligase; DNA repair enzyme; (DNA) joinase; *former name*: sealase. An enzyme that catalyses the reaction:

$$\text{ATP} + (\text{deoxyribonucleotide})_n + (\text{deoxyribonucleotide})_m = \text{AMP} + \text{pyrophosphate} + (\text{deoxyribonucleotide})_{n+m}.$$

(2) **DNA ligase (NAD^+)** EC 6.5.1.2; *systematic name*: poly(deoxyribonucleotide):poly(deoxyribonucleotide) ligase (AMP-forming, NMN-forming); *other names*: polynucleotide ligase (NAD^+); DNA repair enzyme; (DNA) joinase. An enzyme that catalyses the reaction:

$$\text{NAD}^+ + (\text{deoxyribonucleotide})_n + (\text{deoxyribonucleotide})_m = \text{AMP} + \text{nicotinamide mononucleotide} + (\text{deoxyribonucleotide})_{n+m}.$$

DNA-like RNA *abbr*.: D-RNA *or* dRNA; a minor fraction of eukaryotic cellular RNA that has a base composition much closer to that of DNA than the bulk of RNA. It is mainly of high molecular mass, short half-life, and confined to the nucleus, and is probably the same as **giant messenger-like RNA** and **pre-messenger RNA**.

DNA-3-methyladenine glycosidase *see* **(DNA) glycosylase**.

DNA methylase either of two enzymes involved in **modification** and other roles. (1) **Site-specific DNA-methyltransferase (adenine-specific)** EC 2.1.1.72; *other names*: *N*-6 adenine-specific DNA methylase; modification methylase; restriction– modification system; it catalyses the reaction:

$$S\text{-adenosyl-L-methionine} + \text{DNA-adenine} = S\text{-adenosyl-L-homocysteine} + \text{DNA-6-methylaminopurine}.$$

In *E. coli* the enzyme recognizes the base sequence GATC and is part of the system for postreplicative mismatch repair. (2) **Site-specific DNA-methyltransferase (cytosine-specific)** EC 2.1.1.73; *other names*: *C*-5 cytosine-specific DNA methylase; modification methylase; restriction–modification system; it catalyses the reaction between *S*-adenosyl-L-methionine and DNA-cytosine to form *S*-adenosyl-L-homocysteine and DNA-5-methylcytosine. In *E. coli* it recognizes the base sequence CCWGG and methylates both strands.

DNA methyltransferase one of a group of eukaryotic enzymes such as DNMT1 – DNA (cytosine-5-) methyltransferase – that functions in establishing and regulating tissue-specific patterns of methylated cytosine residues. CpG methylation is an epigenetic modification that is important for embryonic development, imprinting, and X-chromosome inactivation. Mutation of the DNMT3B DNA methyltransferase gene causes the autosomal recessive disorder ICF (immunodeficiency, centromeric instability, and facial anomalies).

DNA microarray *or* **DNA chip** *see* **microarray**.

(DNA) nicking–closing enzyme *or* **nicking-and-closing enzyme** *alternative names for* type I **DNA topoisomerase**.

DNA nucleotidylexotransferase *recommended name for* **terminal deoxynucleotidyltransferase** .

DNA photolyase EC 4.1.99.3; *recommended name*: deoxyribodipyrimidine photo-lyase; *other name*: photoreactivating enzyme. An enzyme that splits cyclobutadipyrimidine (in DNA) into two pyrimidine residues (in DNA), thereby repairing the DNA after light-induced **pyrimidine dimer** formation. It is light dependent, requiring the cofactors reduced flavin and either (in different enzyme types) a folate coenzyme or a modified flavin.

DNA-PK *abbr. for* DNA-dependent protein kinase; a mammalian nuclear protein serine/threonine kinase involved in DNA replication, transcription, repair of dsDNA breaks, and in V(D)J recombination. It consists of a catalytic subunit and a DNA-binding heterodimer (subunits of 70 and 80 kDa) called Ku that binds the dsDNA breaks.

DNA polymerase *common name for* any enzyme that catalyses the synthesis of DNA from deoxyribonucleoside triphosphates in the presence of a nucleic-acid primer. There are two families based on structural similarities. In family A are *Escherichia coli* and various other bacterial polymerases I, *Thermus aquaticus* taq polymerase, some bacteriophage polymerases, and yeast mitochondrial polymerase γ. In family B are many polymerases of higher eukaryotes, yeast polymerases I to III, and polymerase REV3, *E. coli* polymerase II, archaebacterial polymerases, and many viral polymerases.

(1) **DNA-directed DNA polymerase** EC 2.7.7.7; *other name*: DNA nucleotidyltransferase (DNA-directed); it is required for DNA replication and repair and has 3′-exonuclease activity (*see* **proofreading**). Eukaryotic DNA-directed DNA polymerases are of five types: (a) DNA polymerase-α (also called DNA polymerase I *or* Kornberg enzyme) was first detected in *E. coli*; in association with **DNA primase** it is replicative. The human enzyme belongs to the polymerase B family, with six conserved regions, four of which are involved in substrate binding. Several DNA viruses have type B polymerases; examples include adenoviruses and herpesviruses.

(b) DNA polymerase-β (*or* DNA polymerase II) is a low-molecular-mass (<50 kDa) enzyme recovered almost entirely in nuclear extracts.

(c) DNA polymerase-γ (*or* DNA polymerase III) is an enzyme that copies synthetic polyribonucleotides with high efficiency, but does not copy DNA well.

(d) DNA polymerase-δ is a zinc finger protein with both polymerase and 3′-exonuclease activities; it is a heterodimer of 125 kDa and 50 kDa subunits.

(e) DNA polymerase-mt is the mitochondrial DNA polymerase.

E. coli has three DNA polymerases: (a) pol I, which has 5′- and 3′-exonuclease activities; the 5′-exonuclease activity is involved in DNA replication; the polymerase activity is employed during DNA repair. (b) pol II, which is regulated by **lexA** and belongs to family B (above). (c) pol III, the major replication polymerase, has an α subunit with polymerase activity, 1160 amino acids (129.76 kDa), and a total subunit composition of $(\alpha,\varepsilon,\theta)_2\text{-}\tau_2\text{-}(\gamma,\delta,\delta',\psi,\chi)_2\text{-}\beta_4$. The complex $(\alpha,\varepsilon,\theta)$, the ‘core’, is assembled first.

(2) **RNA-directed DNA polymerase** is the EC recommended name for **reverse transcriptase**.

DNA primase a DNA-directed **RNA polymerase** (EC 2.7.7.–) of the bacterial **primosome**. It associates transiently with the primosome and synthesizes short RNA primers for the **Okazaki fragments** on both template strands at replication forks.

DNA print the pattern formed by denaturing the DNA in colonies of bacteria grown on a support and fixing the DNA to the support.

DNA provirus *see* **provirus**.

DNA repair enzyme any of the various enzymes involved in the different stages of DNA repair. Three steps are involved, each catalysed by a different set of enzymes: (1) the altered portion of DNA is removed by repair nucleases; (2) **DNA polymerase** fills the gap with a complementary copy; (3) the break is sealed by **DNA ligase**. There are two other related repair pathways, called (base-)**excision repair** and nucleotide-excision repair. *See also* **repair enzyme**.

DNA replication *see* **replication of DNA**.

DNA–RNA hybrid a double helix consisting of one DNA chain and one complementary RNA chain, the two chains being held together by hydrogen bonds between the complementary **base pairs**.

DNA–RNA hybridization *or* **DNA–RNA hybridisation** the formation of a **duplex** (def. 2) nucleic-acid structure that occurs when DNA and RNA molecules that have complementary base sequences are brought together. This phenomenon is exploited in a technique used to localize genes in a chromosome that depends on allowing radioactively labelled RNA to hybridize with denatured, single-stranded DNA from which the RNA was transcribed and then determining the position on the DNA where hybridization has taken place by autoradiography. It also forms the basis of **Northern blotting**.

DNase *usual abbr. for* deoxyribonuclease. *Compare* **DNAase**.

(DNA) sealase *an alternative name for* **polynucleotide ligase** (def. 1).

DNase I hypersensitivity the phenomenon whereby treatment of chromatin with deoxyribonuclease I (DNase I) results in cleavage of DNA at sites that are poorly protected by histones. These ‘hypersensitive sites’ correspond with sites of active transcription in the genome.

DNA sequencing determination of the order in which deoxynucleotides occur in DNA. Fragments of DNA, often cloned in a plasmid vector, are subjected to either the **chemical cleavage method** or, much more commonly, the **chain-termination method**.

DNA superhelix *see* **supercoil**.

(DNA) swivelase *a former name for* type I **DNA topoisomerase**.

DNA topoisomerase any enzyme that alters superhelix density in supercoiled DNA. Topoisomerases are found in all cell types, from microorganisms to those of humans, and in some viruses e.g. bacteriophage T4 and vaccinia. All known topoisomerases relax negatively supercoiled DNA, converting it to a less supercoiled form. Type I makes a transient single-strand break, whereas type II makes a transient double-strand break. **Type I DNA topoisomerase**, EC 5.99.1.2; *other names*: DNA topoisomerase, relaxing enzyme, untwisting enzyme, swivelase, nicking–closing enzyme, ω-protein; it catalyses the ATP-independent breakage of a single strand of DNA, which may be followed by passage (i.e., in the case of duplex DNA, transfer of the unbroken strand through the broken strand) and rejoining. This has the effect of relaxing one negative supercoil. This enzyme can relax only negatively supercoiled DNA, whereas some enzymes, e.g. that from calf thymus, can relax both negatively and positively supercoiled DNA. **Type II DNA topoisomerase**, EC 5.99.1.3; *other name*: DNA topoisomerase (ATP-hydrolysing); it catalyses ATP-dependent breakage, passage (in this case, of a double-strand through a double-strand break) and rejoining of the double-stranded DNA. This enzyme can thus decatenate circular duplex DNA. All type II enzymes can relax both positively and negatively supercoiled DNA. Bacterial **DNA gyrase** is a special example of this class of enzyme because it catalyses the ATP-dependent introduction of negative superhelical turns into a closed circular DNA. It is an A_2B_2 tetramer. The energy-free topoisomerase activity of the A subunit, which breaks the DNA, is inhibited by 4-quinolone antibiotics such as nalidixic acid and ciprofloxacin. The energy-transducing activity of the B subunit is inhibited by novobiocin and other coumarin antibiotics. This enzyme can introduce negative superhelical turns into a closed circular DNA molecule with the coupled hydrolysis of ATP. *See also* **linkage number**, **supercoil**, **winding number**, **writhing number**.

(DNA) untwisting enzyme *an alternative name for* **(DNA) swivelase**.

DNA vaccines **plasmids** containing foreign genes under the control of a strong promoter induce transient expression of the foreign genes in tissue cells when introduced into animals. Immune responses are induced when the gene is taken up and expressed in antigen-presenting cells. DNA may be given by parenteral injection, by shooting DNA-coated particles into the skin using compressed gas (a ‘gene gun’), or by the nasal or oral routes. Cellular and humoral immune responses are induced but with different patterns of **cytokine** production and **immunoglobulin** classes depending on the method of administration. An advantage of the method is that antigens of an organism can be screened for immunogenicity by immunising with expression libraries without the labour of purifying each antigen. DNA immunisation alone is not yet proven in man but may be more effective when combined with other methods (‘prime-boost regimes’). DNA has the advantage that it is stable and simple to produce and plasmids can be engineered to contain **adjuvant** activity. Side effects of DNA immunisation are few. Although insertional mutagenesis remains a possibility, attempts to demonstrate this experimentally have shown it to be extremely rare.

DNA virus *or* **deoxyribovirus** any virus in which the genome consists of DNA, either double-stranded (in class I viruses) or single-stranded (in class II viruses). *See* **Baltimore classification of viruses**.

DNAzyme *or* **deoxyribozyme** a synthetic DNA molecule with catalytic properties.

DNFB *abbr. for* (2,4-)dinitrofluorobenzene. *See* **Sanger's reagent**.

Dnm1 a dynamin-like protein of yeast that is involved, with Fis1 and Mdv1, in forming the contractile ring around the outer membrane of mitochondria that brings about their fission. Homologues occur in animals (e.g. Drp1) and in plants.

Dnp *symbol for* **dinitrophenyl** group.

DNP *abbr. for* **1** (2,4-)dinitrophenol. **2** deoxyribonucleoprotein (use deprecated).

Dns *symbol for* 5-(dimethylamino)naphth-1-ylsulfonyl; *see also* **dansyl**.

dNTP *abbr. for* any deoxynucleoside (5′-)triphosphate (the deoxynucleoside being either unspecified or unknown).

DOC *abbr. for* (use discouraged) **1** deoxycholate (*see* **deoxycholic acid**). **2** **deoxycorticosterone**.

doca *or* **DOCA** *abbr. for* deoxycorticosterone acetate (*see* **deoxycorticosterone**).

Docetaxel *a proprietary name for* a semisynthetic analogue of **taxol**.

Dock an adaptor protein for the insulin receptor in *Drosophila*. It contains SH3 domains through which it binds the C-terminal region of the receptor.

docking the binding of any macromolecule or part of such a molecule to its specific harbouring site on another molecular structure. *See also* **signal recognition particle receptor**.

docking protein *another name for* **signal recognition particle receptor**.

docosa+ *or (before a vowel)* **docos+** *prefix* indicating twenty-two or twenty-two times.

docosadienoic acid any straight-chain fatty acid having 22 carbon atoms and two double bonds. The (5*Z*,13*Z*)-form has been reported to occur in *Limnanthes douglasii*.

docosahexaenoic acid any straight-chain fatty acid having 22 carbon atoms and six double bonds. Only the (all-*Z*)-4,7,10,13,16,19-isomer, of the *n*-3 family, occurs naturally, being present in substantial amounts (10–15% of total fatty acids) in fish oils, and in variable amounts (a few percent of total) in animal glycerophospholipids. It can be formed metabolically from α-linolenic acid, is present in highest concentration in the retina, and is a major component of brain lipids.

docosanoic acid *or* **behenic acid** a straight-chain saturated fatty acid having 22 carbon atoms that occurs as a constituent of cerebrosides and some seed oils (especially of *Lophira* spp.); in some of the latter it accounts for 20–30% of total fatty acids.

docosapentaenoic acid any straight-chain fatty acid having 22 carbon atoms and five double bonds. The (all-*Z*)-4,7,10,13,16-isomer is a member of the *n*-6 family and can be formed metabolically from linoleic acid; it is a constituent of animal glycerophospholipids. The (all-*Z*)-7,10,13,16,19-isomer, of the *n*-3 family, can be formed metabolically from α-linolenic acid; it is a precursor of 4,7,10,13,16,19-docosahexaenoic acid, and is present in small amounts (a few percent) in animal glycerophospholipids and in larger amounts (up to 10%) in fish oils.

docosatetraenoic acid any straight-chain fatty acid having 22 carbon atoms and four double bonds. Adrenic acid is found in animal glycerophospholipids, especially in brain and heart of animals fed sunflower or corn oil, and is presumed to be the (all-*Z*)-7,10,13,16-isomer.

docosatrienoic acid any straight-chain fatty acid having 22 carbon atoms and three double bonds. The (all-*Z*)-7,10,13-isomer occurs in animal lipids, especially during essential fatty acid deficiency.

docosenoic acid any straight-chain fatty acid having 22 carbon atoms and one double bond. The (11*Z*)-isomer, cetoleic acid, occurs in marine oils and rapeseed oil. The (13*Z*)-isomer, erucic acid, is an important constituent of rapeseed and other oils of plants belonging to the family Cruciferae. The possibility that it may be harmful has prompted efforts to breed crop varieties that yield oils containing low levels or none of this fatty acid.

Dod *symbol for* the dodecyl group.

dodeca+ *or (before a vowel)* **dodec+** *prefix* indicating twelve.

dodecandrin a type I **ribosome-inactivating protein**.

dodecanoic acid *systematic name for* lauric acid, a straight-chain saturated fatty acid having 12 carbon atoms. *See also* **laurate**.

dodecanoyl *symbol* Lau; *systematic name for* **lauroyl**.

dodecenoic acid any straight-chain fatty acid having 12 carbon atoms and one double bond.

dodecenoyl the acyl group derived from any dodecenoic acid.

dodecenoyl-CoA *Δ*-isomerase EC 5.3.3.8; *systematic name*: dodecenoyl-CoA Δ^3-*cis*–Δ^2-*trans*-isomerase; *other names*: Δ^3-*cis*-Δ^2–*trans*-enoyl-CoA isomerase; acetylene–allene isomerase; 3,2 *trans*-enoyl-CoA isomerase. An enzyme that is involved in **unsaturated fatty acid oxidation**; it catalyses the isomerization of 3-*cis*-dodecenoyl-CoA to 2-*trans*-dodecenoyl-CoA, thereby producing a substrate for **enoyl-Coa hydratase**. *See also* **peroxisomal bifunctional enzyme**.

dodecyl *symbol*: Dod; *preferred name for* the alkyl group, $CH_3–[CH_2]_{10}–CH_2–$ (*also known as* **lauryl**), derived from dodecane.

***n*-dodecyl-*N,N*-dimethylglycine** lauryldimethylbetaine; a zwitterionic betaine detergent, CMC 1.6–2.1 mm. *Proprietary name*: Empigen BB.

***n*-dodecyl-*β*-D-glucopyranoside** a water-soluble nonionic detergent, CMC 0.13 mm.

***n*-dodecyl-*β*-D-maltoside** a water-soluble nonionic detergent, aggregation number 98, CMC 0.1–0.6 mm.

dodecylsulfate the $CH_3–[CH_2]_{10}–CH_2–O–SO_3^-$ anion. *See* **sodium dodecyl sulfate**.

doghouse configuration (of a cyclobutadipyrimidine) *see* **pyrimidine dimer**.

DOGS *abbr. for* dioctadecylamidoglycylspermine; a reagent used in **lipofection**.

dolichol *the recommended term for* any 2,3-dihydropolyprenol derived from four or more linked isoprene units, i.e. any prenol derivative of general structure $H–[–CH_2–C(CH_3)=CH–CH_2–]_n–CH_2–CH(CH_3)–CH_2–CH_2–OH$ where *n* is greater than 3; in naturally occurring dolichols *n* is commonly in the range 13–23. (*Note*: Because the isoprene unit carrying the hydroxyl group is saturated in dolichols, they are not true **prenols** or **polyprenols**, though often classed as such. It is therefore recommended that, unless qualified, these collective terms are not used to include dolichols.) Dolichol is synthesized from mevalonate in peroxisomes. The phosphoric esters of dolichol (dolichol phosphate *or* phosphodolichol *or* dolichyl phosphate) and the diphosphoric esters (dolichol diphosphate *or* diphosphodolichol *or* dolichyl diphosphate) function in eukaryotes as carriers of mono- and oligosaccharide residues in the glycosylation of lipids and proteins in the endoplasmic reticulum membrane. First, glycosyl groups are transferred from soluble nucleoside-diphosphosugars such as GDPmannose, UDP-*N*-acetylglucosamine, UDPglucose, or UDPxylose to form dolichyl phospho- or diphosphosugars. Then dolichyl diphosphooligosaccharides are built up from these by stepwise transfer of additional sugar residues. Finally the completed oligosaccharide moiety is transferred to a lipid or to a growing polypeptide chain with release of dolichyl diphosphate.

dolichol kinase EC 2.7.1.108; an enzyme that catalyses the formation of dolichyl phosphate from CTP and dolichol with release of CDP. Dolichyl phosphate is a precursor of dolichyl diphosphooligosaccharides, dolichyl phosphoglucose, and dolichyl phosphomannose, intermediates in N-linked glycoprotein oligosaccharide biosynthesis.

dolichol *O*-acyltransferase EC 2.3.1.123; an enzyme that catalyses the formation of dolichyl palmitate from palmitoyl-CoA and dolichol with release of CoA. Acylated dolichols are found in some cell membranes, though their function is obscure.

dolichyl the alkyl group derived from a **dolichol** by loss of its hydroxyl group.

dolichyl diphosphooligosaccharide a precursor for the transfer of N-linked oligosaccharide chains to protein in the synthesis of glycoproteins. It consists of dolichol esterified to diphosphate with an oligosaccharide chain linked to the diphosphate by the C-1 of the sugar at the reducing end of the chain.

dolichyl-diphosphooligosaccharide–protein glycosyltransferase EC 2.4.1.119; an enzyme that catalyses the reaction of dolichyl diphosphooligosaccharide with protein L-asparagine to form a glycoprotein with the oligosaccharide chain attached by glycosylamine linkage to protein L-asparagine, with release of dolichyl phosphate.

dolichyl-phosphate *β*-D-glucosyltransferase EC 2.4.1.117; an enzyme that catalyses the reaction of UDPglucose with dolichyl phosphate to form dolichyl β-D-glucosyl phosphate (an intermediate in the biosynthesis of N-linked glycoprotein oligosaccharides) and UDP. It is a type II membrane protein of the endoplasmic reticulum involved in the glycosylation pathway.

dolichyl-phosphate-mannose–protein mannosyltransferase EC 2.4.1.109; an enzyme that catalyses the reaction of dolichyl phosphate D-mannose with protein to form *O*-D-mannosylprotein and dolichyl phosphate. *See also* **dolichyl-phosphate** β-D-mannosyltransferase.

dolichyl-phosphate *β*-D-mannosyltransferase EC 2.4.1.83; an enzyme that catalyses the formation of dolichyl D-mannosyl phosphate, an intermediate in the biosynthesis of N-linked glycoprotein oligosaccharides, from GDPmannose and dolichol phosphate with release of GDP. *See also* **dolichyl-phosphate-mannose–protein mannosyltransferase**.

domain **1** any topological region having specific characteristics, contained within certain limits, and/or under individual control. **2** *or* **structural domain** a compact, globular region in the structure of a single protein molecule, which may consist of several such globular regions held together by more flexible parts of the polypeptide chain. It has been suggested that the word be reserved for large subassemblies that would be stable if the polypeptide chain connecting them to the rest of the protein molecule were to be cleaved, and that the term **folding unit** be used to define small assemblies of secondary structure segments in a protein molecule. **3** a region of a protein molecule delimited on the basis of sequence or function, without knowledge of its molecular substructure, e.g., that binds to a receptor or substrate, that possesses a catalytic function (forming a **catalytic domain**), or that traverses a membrane (forming a **transmembrane domain**). Such a region may contain more than one structural domain (*see* def. 2). **4** a poorly characterized length of chromosomal DNA, ~50–200 kbp, that comprises all the (coding or non-coding) sequences required for the formation of mRNA for any one (specified) protein. **5** a zone within a cellular membrane consisting of one class of component, e.g. lipid. **6** a diverse set of cellular events, processes and metabolic reactions controlled or affected by a specific agent, e.g. a hormone or another messenger. *See* **metabolic code**. **7** a mathematical aggregate to which a variable is confined. **8** *(in physics)* any region in a ferromagnetic solid in which all the atoms have the spins of their unpaired electrons aligned in the same direction: **magnetic domain**.

domain family a structurally and functionally diverse group of proteins that share a local sequence region that mediates a particular biological role (e.g. a kringle or SH2 domain). Different processes underpin the evolution of domain families and gene families, with different functional consequences.

domain of bonding the two linked **binding sets** through which a pair of associated **protomers** are associated.

domain of unknown function *abbr*.: DUF; part of a (usually) protein sequence that is conserved in a family of sequences but whose function is unknown.

dominant *(in genetics)* describing a gene that produces the same character or phenotype whether present in the homozygous state or in the heterozygous state (i.e. together with a different specified allele). The ineffective heterozygous allele is described as **recessive** to the dominant one. Dominant inherited diseases fall into one of three categories: (1) '**change of function**' in which the abnormal protein acquires a novel activity that is deleterious to the cell, (2) '**dominant negative**' in which the abnormal protein forms heterooligomeric complexes with the protein from the normal allele thereby knocking out the function of the entire protein complex, (3) '**haplo-insufficiency**' in which a single copy of the gene has lost function and the 50% of the normal amount of protein that is produced from the non-mutated allele is not adequate to preclude clinical symptoms. Examples: type (1), sodium channel disorders; type (2), mutations in collagen genes which lead to osteogenesis imperfecta; type (3), loss of function in one copy of the low-density-lipoprotein receptor gene resulting in familial hypercholesterolemia.

dominant selectable marker *(in molecular genetics)* a marker, usually an enzyme, that confers resistance to the toxic effects of a drug or other pharmacologically active compound used for selection. Such markers are used to confer an advantage on mammalian and other cells that have been transfected with exogenous DNA constructs. For example, the gene for aminoglycoside phosphotransferase is commonly incorporated in plasmids to confer resistance (denoted as neo^R) to antibiotics such as G418. Dominance refers to the fact that a single copy of the marker is sufficient to confer the resistant phenotype.

Donnan effect *or* **Donnan (membrane) equilibrium** the effect of the presence of charged macromolecules upon one side of a semipermeable membrane on the distribution of small, permeable ions across the membrane. At equilibrium, the small counterions will be more concentrated on the macromolecules' side of the membrane and the small ions of the same charge as the macromolecules will be less concentrated there, whereas on the side of the membrane with no macromolecules the concentrations of the small ions of opposite charge will be equal. It can be shown that, if the small ions are A^+ and B^-,

$$[A^+]_{(1)}/[A^+]_{(2)} = [B^-]_{(2)}/[B^-]_{(1)} = r_D,$$

where r_D is the **Donnan ratio** and the subscripts 1 and 2 indicate the two sides of the membrane. [After Frederick George Donnan (1870–1956), British physical chemist.]

donor *(in chemistry)* any chemical species that is able to donate one or more electrons, atoms, or groups to another species, the acceptor.

donor atom 1 an atom that supplies two electrons in forming a **dipolar bond**. **2** an atom, added as an impurity to a semiconductor, that provides additional electrons in the conduction band. *See also* **electron donor**.

donor cell any living cell that contributes genetic information to another, **recipient** cell. *See* **conjugation** (def. 3), **transduction**, **transformation**.

dopa *or* **DOPA** *abbr. for* 3-hydroxytyrosine; 3,4-dihydroxyphenylalanine; 2-amino-3-(3,4-dihydroxyphenyl)propanoic acid; the naturally occurring enantiomer is 3-hydroxy-L-tyrosine (*abbr*.: L-dopa, also known as levodopa because it is levorotatory; $[\alpha]^{20}_{546} \approx 13.0$). L-Dopa is formed from L-tyrosine by tyrosine 3-monooxygenase, EC 1.14.16.2, and is an immediate metabolic precursor of the neurotransmitter **dopamine** and other **catecholamines**. L-Dopa is used in the treatment of **Parkinson's disease**.



dopac *or* **DOPAC** *abbr. for* dihydroxyphenylacetate.

dopachrome Δ-isomerase EC 5.3.3.12; *systematic name*: dopachrome *Δ*7–*Δ*2-isomerase; an enzyme that catalyses the conversion of dopachrome (2-carboxy-2,3-dihydroindole-5,6-quinone) to 5,6-dihydroxyindole-2-carboxylate. Dopachrome is formed nonenzymatically from dopaquinone, the product of **monophenol monooxygenase**. These are reactions in the pathway of melanin synthesis. A deficiency in the enzyme results from a mutation in mice known as ***slaty***. The enzyme contains zinc.

dopa decarboxylase *see* **aromatic-L-amino-acid decarboxylase**.

dopamine *an alternative name for* 3,4-dihydroxyphenylethylamine; 3-hydroxytyramine; 3,4-dihydroxyphenylethylamine; 4-(2-aminoethyl)-1,2-benzenediol; a **catecholamine** neurotransmitter formed by aromatic-L-amino-acid decarboxylase, EC 4.1.1.28, from 3,4-dihydroxy-L-phenylalanine. A metabolic precursor of **norepinephrine** and **epinephrine**, it is found in **dopaminergic** nerves in the brain and in the adrenal medulla. *See also* **Parkinson's disease**.



dopamine β-hydroxylase EC 1.14.17.1; *recommended name*: dopamine *β*-monooxygenase; *systematic name*: 3,4-dihydroxyphenethylamine,ascorbate:oxygen oxidoreductase (*β*-hydroxylating). An enzyme that catalyses hydroxylation of dopamine to norepinephrine in aminergic neurons releasing norepinephrine and epinephrine; ascorbate is simultaneously oxidized to dehydroascorbate. The enzyme is a copper protein, stimulated by fumarate. It is absent from dopaminergic neurons.

dopamine β-monooxygenase *see* **dopamine β-hydroxylase**.

dopamine receptor any protein that binds dopamine and mediates its intracellular effects. Types D_1 to D_5 have been recognized; D_1 and D_5 (also called D_{1A} and D_{1B}) comprise one subfamily; D_2, D_3, and D_4 (also called D_{2A}, D_{2B}, and D_{2C}) comprise a second subfamily. D_3 receptors seem to be insensitive to guanine nucleotides and regulate conductance of Ca^{2+}. All are G-protein-associated receptors. D_1 and D_5 elevate cyclic AMP, but vary in binding characteristics; D_2 has a short and a long form originating from alternative splicing; in humans, the short form (D_{2S}) has 414 amino acids, and the long form (D_{2L}) has 443 amino acids. D_2 lowers cyclic AMP levels and regulates ion channels, opening K^+ and inhibiting Ca^{2+} channels. D_3 and D_4 have binding characteristics similar to, but distinct from D_2; their action is not mediated by G-protein interaction with adenylate cyclase. *See* **DARPP-32**.

dopaminergic describing a nerve that is activated by dopamine.

The term is applied to nerves that act by releasing dopamine at their nerve endings. *Compare* **adrenergic**, **aminergic**, **cholinergic**, **peptidergic**, **purinergic**, **serotonergic**.

dopamine transporter an integral membrane protein of dopaminergic nerve terminals that permits re-entry of dopamine in a Na^+- and Cl^--dependent manner. Cocaine binds strongly to, and inhibits, the transporter. A variety of mood-modifying drugs act similarly.

DOPA-responsive dystonia *or* **hereditary progressive dystonia**; an autosomal dominant progressive dystonia that starts in childhood and results from deficiency of tetrahydrobiopterin, the cofactor for tyrosine hydroxylase. Caused by mutations in guanosine triphosphate cyclohydrolase, it responds dramatically to treatment with DOPA or dopamine.

DOPE *abbr. for* dioleoylphosphatidylethanolamine; a phospholipid used in conjunction with cationic lipids for **lipofection**.

Doppel a mouse protein that resembles a truncated version of cellular **prion protein**. It lacks the N-terminal region up to and including the transmembrane segment. It is not normally abundant in brain but is abundant in testes. When overexpressed it causes cerebellar cell death and ataxia.

Doppler effect the apparent change in the frequency of acoustic or electromagnetic waves due to relative motion between the source and the observer. The frequency appears to increase when the source and the observer move towards each other, and to decrease when they move away from each other. [After Christian Johann Doppler (1803–53), Austrian mathematician and physicist.]

dorsal protein embryonic developmental morphogenetic nuclear protein; a protein whose concentration in the nucleus of a cell during the blastoderm stage of development determines the cell's lateral or ventral identity. It is similar to the product of the vertebrate proto-oncogene c-*rel*.

dosage compensation the epigenetic inactivation of one of the two X chromosomes of female cells that results in them having only one functional copy, thereby making them comparable with X-chromosome dosage in male cells, which have only one.

dose 1 a measured quantity of a drug, microorganism, radiation, etc. administered to an organism, often at specified intervals. In experimental pharmacology, the units and routes of administration should be specified and the quantity of the drug expressed per unit of animal mass, e.g. $mol\ kg^{-1}$, $mg\ kg^{-1}$, $mg\ min^{-1}\ kg^{-1}$. **2** to prescribe or administer a dose or doses. —**dosage** *n.*

dose equivalent *symbol*: *H*; a measure of the biological effects of **ionizing radiation** upon humans (or other mammals) used in radiation dosimetry and health physics. It is usually equal to the **absorbed dose** multiplied by the **quality factor**. In the case of radiation arising from radioactive material within a person's body, the absorbed dose must be multiplied also by a distribution factor (normally unity, but in certain instances given a value of 5) in order to take account of any nonuniform distribution of radioactivity. The CGS unit of dose equivalent is the **rem**; the corresponding SI derived unit is the **sievert** (def. 1).

dose rate in radiation dosimetry, the amount of **ionizing radiation** (expressed in grays, rads, rems, röntgens, or sieverts) received or receivable by an irradiated object or organism in unit time. For personnel, it is usually expressed in sieverts per hour. (There is no separately named unit of dose rate.)

dose ratio *an older name for* **concentration ratio**.

dose–response curve any graphical representation of the relationship between the size of an administered dose and the extent of the response of the organism, or other test system, to the dose. The response may be some biochemical or physiological change in one or more organisms, tissue samples etc., or the proportion of organisms in a group that show a response.

dosimeter *or* **dose meter** an instrument for measuring the quantity of ionizing radiation administered to an organism or an object, or the intensity of a source of such radiation.

dosimetry the process of measuring administered quantities of ionizing radiation, drugs, microorganisms, etc.

DOSPA *abbr. for* 2,3-dioleoyloxy-*N*-[2(sperminecarboxamido)-ethyl]-*N*,*N*-dimethyl-1-propaniminium trifluoroacetate; a polycationic lipid used for **lipofection**.

DOSPER *abbr. for* 1,3-dioleoyloxy-2-(6-carboxyspermyl)-propylamide; a dicationic lipid used for **lipofection**.

DOTAP *abbr. for* *N*-[1-(2,3-dioleoyloxy)-propyl]-*N*,*N*,*N*-trimethylammonium methyl sulfate; a monocationic lipid used for **lipofection**.

dot hybridization *or* **dot hybridisation** *or* **dot blotting** a development of **blotting** or blot transfer, in which as little as 1 pg of a specific nucleic-acid sequence, bound to nitrocellulose as a small spot, can be detected using a ^{32}P-labelled probe as a 'dot blot'.

DOTMA *abbr. for* *N*-[1-(2,3-dioleoyloxy)-propyl]-*N*,*N*,*N*-trimethylammonium chloride; a monocationic lipid used for **lipofection**.

dotplot a graphical depiction of the similarity between pairs of sequences, sometimes used as the basis for sequence alignment. Identical regions form straight lines along, or parallel to, the plot diagonal, their offset from the diagonal indicating the number of gaps needed to bring these regions into register.

double-antibody method any technique in which a specific antibody, used to detect or measure its corresponding antigen, as in **immunoassay**, is isolated from the reaction mixture by combination with heterologous antibody to the specific antibody. *Compare* **antiglobulin test**.

double-beam spectrophotometer a **spectrophotometer** in which the incident light beam is split into two halves, one half passing through the sample and the second half passing through the reference so that direct measurement of the difference in absorption can be made. In one type the two emergent beams fall on different detectors and the resulting signal is a direct current; in another type the incident beam passes alternately through the sample and the reference, and the two emergent beams fall on the same detector resulting in an alternating current signal.

double-blind testing a method of evaluating the efficacy of a substance (e.g. a drug) in which neither the subjects nor the experimenter knows the identity of the samples at the time of the evaluation.

double bond a **covalent bond** that consists of two electron pairs shared by two atoms.

doublecortin a tubulin-binding protein (40 kDa) expressed in the developing nervous system. It is homologous to a mouse protein that contains a Ca^{2+}-dependent protein kinase domain. Several mutations in the gene at Xq22.3-q23 produce X-linked lissencephaly in males and double cortex syndrome in females.

double-displacement (enzyme) mechanism *or* **ping-pong mechanism** *or* **substituted-enzyme mechanism** any enzymic mechanism in which an enzyme reacts with one substrate to give a covalently modified enzyme together with the release of one product, and the modified enzyme then reacts with the second substrate with the subsequent release of the second product and the return of the enzyme to its initial state.

double helix *or* **Watson–Crick model of DNA** the main features of this model are that DNA consists of two antiparallel helical polynucleotide chains coiled around the same axis to form a double helix. Deoxyribose–phosphate backbones are on the outside of the helix and purine and pyrimidine bases lie approximately at right angles to the axis on the inside of the helix. The diameter of the helix is 2.0 nm and there is a residue on each chain every 0.34 nm. The angle between each residue on the same chain is 36°, so that the structure repeats after 10 residues (3.4 nm) on each chain. The two chains are held together by hydrogen bonds between pairs of bases, each member of the pair belonging to a different polynucleotide chain. Adenine is always paired with thymine and guanine with cytosine. The two chains are therefore complementary.

double heterozygote an individual who is heterozygous at two separate genetic loci.

double immunodiffusion *or* **double diffusion** a technique of **immunodiffusion** in which both the antibody and the antigen diffuse towards each other through a gel to form lines of precipitation. *See* **Ouchterlony technique**.

double labelling an experimental strategy in which either a single chemical compound is labelled with two different nuclides or two compounds are each labelled with a different nuclide. It is used to follow the simultaneous transformations of two substances or two parts of one substance, or to distinguish identical molecules synthesized at different times. —**doubly labelled** *adj.*

double layer *see* **electric double layer**.

double membrane *see* **unit membrane**.

double-reciprocal plot a plot of 1/*x* versus 1/*y*, where *x* and *y* are two variables. If the plot of *y* versus *x* has the shape of a **rectangular hyperbola** the corresponding double-reciprocal plot will be a straight line. Note: the *x* and *y* axes are not the asymptotes of the rectangular hyperbola. The **Lineweaver–Burk plot** is a double-reciprocal plot. *See also* **hyperbolic kinetics curve**.

double refraction *see* **birefringence**.

double refraction of flow *see* **flow birefringence**.

double-sector cell a **cell** (def. 2), used in analytical ultracentrifugation experiments, with two radial sector-shaped cavities, allowing the concentration distribution of a solute in one sector to be related to that of the solvent alone in the other sector: i.e. the second sector provides a reference for the first.

doublesex a gene of *Drosophila* involved in sex determination. It encodes two zinc-binding transcription factors derived by alternative splicing of the pre-mRNA transcript. The proteins, called DsxF and DsxM, determine whether the embryo is female or male, respectively.

double-sieve hypothesis a hypothesis invoked to account for the unexpectedly low level of error (misreading) observed in protein biosynthesis. According to this hypothesis, the discrete synthetic and hydrolytic sites that exist on certain aminoacyl-tRNA synthetases provide a two-stage stereochemical sorting mechanism – likened in action to a pair of sieves – for the elimination of inappropriate amino acids. The synthetic site first rejects amino acids larger than that genetically specified; the hydrolytic site then preferentially destroys reaction products of amino acids smaller than, or isosteric with, the one specified. The second process has also been termed **editing** or proofreading. Such a mechanism would have particular importance in discriminating between a pair of very similar amino acids such as isoleucine and valine. *Compare* **kinetic proofreading**.

double-stop terminator two consecutive **termination codons** in a molecule of mRNA.

double-stranded *or* **double-strand** describing a **duplex** form of a nucleic acid. *See* **double-stranded RNA**, **duplex DNA**.

double-stranded RNA *abbr*.: dsRNA; a structure that occurs when complementary base sequences in single-stranded RNA form a **duplex** (def. 2). The Rna may fold back on itself to generate an antiparallel duplex structure, known as the stem, with a loop of unpaired bases at the end. The loop and stem together are called a **hairpin**. The two complementary sequences can result from an inverted repeat. *See also* **palindrome**.

double-stranded template double-stranded DNA that can be used as a template for sequencing. DNA cloned in plasmids can be sequenced without preparing single-stranded DNA as a template. Denaturation of double-stranded templates exposes sufficiently long stretches of the template strand to enable sequencing reactions to take place.

doublet **1** any sequence of two nucleotides in a polynucleotide strand. **2** a closely spaced pair of spectral lines or peaks. *Compare* **twin**.

doubling dilution a serial dilution effected so that the concentration in each tube of the particular cell, substance, etc. of interest is half that in the preceding tube of the series.

doubling time the average time taken for the number of cells in a population to double. It will equal the **generation time** only if every cell in the population is able to form two daughter cells and there is no cell lysis.

Dounce homogenizer *or* **Dounce homogeniser** a hand-operated tissue homogenizer, usually of glass, consisting of a ball that is operated as a piston in a tube. The clearance is adjusted to give a fine-particle size reduction without damage to cell nuclei or mitochondria. [After Alexander Latham Dounce, US biochemist (1909–).]

Dowex *proprietary name for* a group of synthetic ion-exchange resins made by Dow Chemical Company. *See also* **cholestyramine resin**.

down regulation **1** a decrease in response of a cell to a hormone brought about either by a decrease in receptor number or by the uncoupling of an effector component. **2** a decrease in the activity of an enzyme or the amount of a protein resulting from the action of an effector molecule on gene expression or protein synthesis. **—down-regulated** *adj.*

Down's syndrome *or* **Down syndrome** *or (formerly)* **mongolism** a type of mental abnormality frequently associated with **trisomy** of chromosome 21. The condition is characterized by a small stature, a rounded head with obliquely slanted ('Mongol-like') eyes and high cheekbones, a fissured tongue with enlarged papillae, and a characteristic palmprint. The degree of mental defect varies considerably. [First described in 1866 by John Langdon Haydon Down (1828–96), British physician.]

downstream **1** *(in molecular biology)* that part of a strand of DNA lying towards the 3′ end from the recognition sequence for a particular restriction enzyme. **2** towards the end of a multistage process, or at a stage nearer to the endpoint of the process than a key stage or one under consideration. *Compare* **upstream**.

doxorubicin a cytotoxic anthracycline antibiotic from *Streptomyces peucetius* var. *caesius*; its carbohydrate is **daunosamine**. It intercalates with DNA and prevents the actions of type II **DNA topoisomerase**. It also inhibits reverse transcriptase and acts on cell membranes. It has anti-tumour activity and has been used to treat some forms of cancer.



doxycycline 5-hydroxy-6-deoxytetracycline; an antibiotic having a wide range of activity against both Gram-positive and Gram-negative organisms. It is closely similar to **tetracycline** in structure and mechanism of action. One proprietary name is Vibramycin.



DPG *or* **2,3-DPG** *abbr. for* (2,3-)diphosphoglycerate (former name for **2,3-bis(phospho)-**D-glycerate).

DPG pocket *abbr. for* diphosphoglycerate pocket. *See* **bisphosphoglycerate pocket**.

dpm *or* **d.p.m.** *abbr. for* disintegrations per minute.

Dpm *see* **A$_2$pm**.

DPN *abbr. for* diphosphopyridine nucleotide when its oxidation state is unknown or unspecified (obsolete; NAD now used).

DPN$^+$ *abbr. for* diphosphopyridine nucleotide (oxidized) (*obsolete name for* **NAD$^+$**).

DPNH *abbr. for* reduced diphosphopyridine nucleotide (obsolete; NADH now used).

DPP *abbr. for* **1** dipeptidyl peptidase. **2** deafness-dystonia protein; a protein (97 amino acids) of the intermembrane space of mitochondria. It is homologous to a yeast Tim protein and seems to be involved in importing proteins into mitochondria. Deficiency of DPP causes an X-linked syndrome of deafness, dystonia, dementia, and blindness. *See* **TIM**.

Dpr *see* **A$_2$pr**.

dps *abbr. for* disintegrations per second.

DPT *abbr. for* 2-diazophenylthioether, *the short name of* the group –O–CH$_2$–CH(OH)–CH$_2$–O–[CH$_2$]$_4$–O–CH$_2$–CH(OH)–CH$_2$–S–C$_6$H$_4$–N$_2^+$, used to introduce reactive diazonium groups into cellulose or paper, forming **DPT-cellulose** or **DPT-paper**. These are used in **blot transfer** of proteins or nucleic acids. DPT is formed by diazotization of 2-aminophenylthioether (*abbr*.: APT) groups previously coupled to the support.



draft genome sequence a genome that has been sequenced 4–5 times (4–5-fold coverage), providing a framework for DNA fragment assembly and potentially allowing up to 95% of genes to be identified. Draft sequence is mostly in the form of 10000-bp fragments whose approximate chromosomal locations are known; the fragments may contain gaps and their true order and orientation may not be known. *Compare* **finished genome sequence**.

DRAGON *abbr. for* Database Referencing of Array Genes Online; an internet site providing free access to a number of bioinformatics tools including analysis of microarray data.

***Dra*I** a type 2 **restriction endonuclease**; recognition sequence: TTT↑AAA. *Aha*III is an **isoschizomer**.

DRB *abbr. for* 5,6-dichloro-1*β*-D-furanosyl benzimidazole; a protein kinase inhibitor that affects synthesis of most mRNAs by inhibiting phosphorylation of the C-terminal domain of the largest subunit of RNA polymerase II. See **DRB-sensitivity inducing factor**.

DRB-sensitivity inducing factor *abbr*. DSIF; a protein kinase that phosphorylates the C-terminal domain of the largest subunit of RNA polymerase II and functions as a positive transcriptional elongation factor. It is sensitive to **DRB**.

DREAM *abbr. for* downstream regulatory element antagonistic modulator; a protein that acts as a Ca^{2+}-regulated transcription factor by binding the 3′ regulatory element of the gene for preprodynorphin and inhibiting its transcription.

D region the (third) hypervariable region occurring between the V region and the J region in the heavy chains (but not in the light chains) of **immunoglobulin** molecules. It is coded for by the D (for ‘diversity’) gene segment.

dRib *symbol for* the monosaccharide deoxyribose, 2-deoxy-D-ribose.

Drk *abbr. for* **1** a small protein that bears SH2 domains (*see* **SH domain**), and acts as a link between **sevenless** protein and **son of sevenless** protein in the *Drosophila* photoreceptor system (downstream of receptor kinases). **2 Drk1** a mammalian integral membrane protein forming a voltage-dependent potassium channel of the delayed rectifier class. The voltage sensor, probably segment S4, is characterized by a series of positively charged amino-acid residues at every third position.

D-RNA *or* **dRNA** *abbr. for* DNA-like RNA.

dropping-mercury electrode an electrode used in **polarography** in which mercury drops from a reservoir through a capillary tube into the solution under study. It has the advantage of constantly presenting a clean, unpolarized mercury surface to the solution.

Drosha a nuclear RNase III that is specific for dsRNA. It contains a dsRBM and 2 RNase III domains and processes pri-miRNA to pre-miRNA. It interacts with **Pasha** in the nuclear Microprocessor complex.

drosomycin a peptide from *Drosophila* that is highly homologous with a defensin (RS-AFP1) from radish plants. Both exhibit antifungal activity and have a similar tertiary structure.

Drosophila a genus of small dipterous insects that includes the fruit fly, *D. melanogaster*, also known as vinegar fly or banana fly. This is much used in genetic research because of the giant chromosomes, which occur in the cells of its salivary glands, and because of its short life cycle.

Drp1 an animal homologue of **Dnm1**, a yeast protein involved in forming the contractile ring on the outer mitochondrial membrane that brings about fission of a mitochondrion. Knockout of the Drp1 gene in mice leads to highly interconnected tubular mitochondria.

DRPLA *abbr. for* dentatorubralpallidoluysian atrophy.

Drude equation an equation describing the variation of optical rotation with wavelength of light. It is useful in the interpretation of measurements of **optical rotatory dispersion**, when it may be expressed in the form:

$$[m']_\lambda = \frac{96\pi N_A}{h\,c} \times \frac{R\lambda_0^2}{\lambda^2 - \lambda_0^2}$$

where N_A is the Avogadro constant, h is the Planck constant, c is the speed of light, R is the rotational strength, λ_0 is the wavelength of the centre of an absorption band, λ is the wavelength of the observation, and $[m']_\lambda$ is the reduced mean residue rotation at that wavelength, as defined at **molar optical rotation**. *See also* **Moffitt–Yang equation**. [After Paul Karl Ludwig Drude (1863–1906), German physicist, noted for, *inter alia*, his work on refraction of light.]

drug any naturally occurring or synthetic substance, other than a nutrient, that, when administered or applied to an organism, affects the structure or functioning of the organism; in particular, any such substance used in the diagnosis, prevention, or treatment of disease.

drug discovery the process of identifying compounds (often via high-throughput methods, such as **combinatorial chemistry** and **high-throughput** screening) that interact with, and modulate the activity of, specific proteins or genes, and the subsequent production of candidate drugs for testing.

druggable target *see* **drug target**.

drug-metabolizing enzyme *or* **xenometabolic enzyme** any enzyme that acts on a drug or other foreign compound but is not known to have any action on a normal metabolite. Many enzymes previously included in this category have subsequently been found to act also on normally occurring substrates.

drug resistance the relatively enhanced resistance of an organism to the action of a drug. It may be caused by induction of an enzyme acting on the drug, by mutation, or by the acquisition of a plasmid coding for drug resistance.

drug target a biological entity (usually a protein or gene) that interacts with, and whose activity is modulated by, a particular compound. If its biochemical profile makes it a suitable candidate for drug testing it is deemed a **druggable target**.

dry ice solid carbon dioxide. It is a convenient cooling agent because, at ordinary atmospheric pressures, heat converts it directly to the gaseous form (sublimation point 194.65K at 101325 Pa; –78.5°C at 760 Torr).

ds *abbr. for* double-stranded.

DsbA a 21 kDa protein that is the bacterial functional equivalent in *Escherichia coli* of the eukaryotic **protein disulfide-isomerase**; however, there is little sequence similarity between the two proteins. The structure of DsbA has been determined, and shown to be similar, in part, to **thioredoxin**.

DSC *abbr. for* differential scanning colorimetry *or* differential scanning calorimeter.

dsDNA *abbr. for* double-strand(ed) DNA (*see* **duplex DNA**).

DSIF *abbr. for* DRB-sensitivity inducing factor.

DSPD *abbr. for* disalicylidenepropanediamine.

dsRBM *abbr. for* dsRNA-binding motif; a protein sequence of ≈70 amino acids that interacts with dsRNA, partially duplexed RNA, and in some cases RNA-DNA hybrids, generally without obvious specificity for the RNA nucleotide sequence. It is predicted to consist of three beta strands flanked by two alpha helices, and may occur up to five times in a protein (e.g. in **Staufen**). Numerous proteins from viruses, bacteria, and eukaryotes that contain the motif fall into nine major groups.

dsRNA *abbr. for* double-strand(ed) RNA.

dsRNA-binding motif *see* **dsRBM**.

DSS *abbr. for* 2,2-dimethylsilapentane 5-sulfonic acid; a compound used as a water-soluble reference substance in **nuclear magnetic resonance spectroscopy**.

dsx *symbol for doublesex*; a gene in *Drosophila melanogaster* that encodes both female-specific and male-specific polypeptides whose synthesis is regulated by alternative sex-specific splicing of the *dsx* transcript. The gene products are transcription factors that repress expression of terminal differentiation genes specific to the opposite sex.

dT *symbol for* a residue of the deoxynucleoside thymidine (alternative to dThd).

dTDP *abbr. for* deoxyribosylthymine diphosphate *or* thymidine diphosphate, the common names for 2′-deoxyribosylthymine-5′-diphosphate; thymidine 5′-diphosphate; 5′-thymidylyl phosphate; thymine 2′-deoxyriboside 5′-diphosphate.

DTDST *abbr. for* diastrophic dysplasia sulfate transporter.

DTE *abbr. for* 1,4-dithioerythritol.

dThd *symbol for* a residue of the deoxynucleoside thymidine; 2′-deoxyribosylthymine; thymine 2′-deoxyriboside (alternative to dT).

dThd5′*P* *symbol for* thymidine 5′-phosphate.

dThd5′*PP* *symbol for* thymidine 5′-diphosphate (alternative to ppdT).

dThd5′*PPP* *symbol for* thymidine 5′-triphosphate (alternative to pppdT).

dTMP *abbr. for* deoxyribosylthymine monophosphate *or* thymidine monophosphate, the common names for 2′-deoxyribosylthymine 5′-phosphate, thymidine 5′-phosphate, 5′-thymidylic acid, thymine 2′-deoxyriboside 5′-phosphate.

DTNB *abbr. for* 5,5′-dithiobis(2-nitrobenzoic acid); *see* **Ellman's reagent**.

DTT *abbr. for* 1,4-dithiothreitol.

dTTP *abbr. for* deoxyribosylthymine triphosphate *or* thymidine triphosphate, the common names for 2′-deoxyribosylthymine 5′-triphosphate; thymidine 5′-triphosphate; 5′-thymidylyl diphosphate; thymine 2′-deoxyriboside 5′-triphosphate.

dU *symbol for* a residue of the deoxynucleoside 2′-deoxyuridine (alternative to dUrd).

dual luciferase reporter assay system a plasmid carrying the genes for firefly and *Renilla reniformis* luciferases with provision for cloning a mammalian promoter upstream from the firefly luciferase reporter gene. The *Renilla* luciferase is under the control of a constitutive promoter and is used to monitor transfection efficiency. Both luciferases can be assayed in cell extracts by the bioluminescence generated using their respective substrates.

dual specificity mitogen-activated protein kinase kinase *see* **MAP kinase kinase**.

dual specificity protein phosphatase an enzyme capable of hydrolysing phosphate monoesters in peptides that contain phosphotyrosine, or phosphoserine/threonine. At least 20 such phosphatases have been detected in mammalian cells. They include Cdc25 and a vaccinia H1-related (VHR) phosphatase (184 amino acids) of humans. The crystal structure of the latter consists of seven alpha helices and five beta strands, and shows a cysteine that is essential for activity.

Dubin–Johnson syndrome a rare inherited defect of liver function characterized by elevated levels of (mainly conjugated) serum **bilirubin**, with accumulation of a melanin-like pigment in hepatocyte lysosomes. It is transmitted as an autosomal recessive trait, and caused by mutations in a gene at 10q23-q24 for canalicular multiorganic anion transporter (cMOAT), an ABC-transporter of 1545 amino acids. [After Nathan Dubin (1913–1980), US pathlogist, and Frank Johnson (1919–), US pathologist.]

Dubnoff shaker a controlled-temperature water bath with a uniformly oscillating load platform and facilities for maintaining a controlled atmosphere. It is used for studies of the metabolism of tissues and microorganisms and for enzyme and blood-coagulation studies. [After Jacob William Dubnoff (1909–), US biochemist.]

Duboscq colorimeter an early, accurate visual colorimeter for determination of small quantities of substances in solution, in which the intensities of colour of two solutions, standard and unknown, were compared by varying the path-lengths of light passing through them from a single source until their apparent colours matched. This was achieved by placing the solutions in flat-bottomed vessels (termed cups) and adjustment of their positions in relation to two identical, fixed, transparent plungers through which the light passed, via prisms, to a divided-field eyepiece. The path-length in each solution was then read from a vernier scale. [After Jules Duboscq (1817–86), French optician.]

Duchenne muscular dystrophy *see* **dystrophin**.

ductless gland *an alternative name for* **endocrine gland**.

dUDP *abbr. for* deoxyuridine diphosphate, the common name for 2′-deoxy-5′-uridylyl phosphate; 2′-deoxyuridine 5′-diphosphate; uracil 2′-deoxyriboside 5′-diphosphate.

DUF *abbr. for* domain of unknown function.

Duffy system *symbol*: Fy; a blood-group system for which the antigenic determinant depends on the structure of an erythrocyte membrane glycoprotein, of molecular mass 35–45 kDa, named GPD. This functions as a chemokine receptor (Duffy antigen receptor for chemokines; *abbr.*: DARC) and as a receptor for the malaria parasite *Plasmodium vivax.* The parasite is unable to enter Duffy-negative erythrocytes. GPD is also a receptor for several proinflammatory cytokines and is expressed in other cell types besides erythrocytes. The system is encoded by a locus at 1q21-q22, and there are three major alleles: FY*A, FY*B, and FY*O.

dulcitol *another (older) name for* **galactitol**.

dUMP *abbr. for* deoxyuridine monophosphate, the common name for 2′-deoxyuridine 5′-phosphate; 2′-deoxy-5′-uridylic acid; uracil 2′-deoxyriboside 5′-phosphate.

duodenase a type II transmembrane serine protease produced by duodenal mucosa. It has been proposed as the activator of enteropeptidase, which has very low autocatalytic activity.

duodenum that part of the small intestine extending from the pylorus of the stomach to the jejunum. In mammals it lies around the head of the pancreas and receives the duct from the exocrine pancreas and the gall bladder. —**duodenal** *adj.*

Duolite *proprietary name for* a group of ion-exchange resins. It includes those formerly known by the names Biodeminrolit, De-Acidite, Zeo-Karb, and Zerolit.

duplex **1** having two parts or elements, especially of similar form or function. **2** describing a molecular structure (or part of one) in which two polynucleotide strands lie side by side in a head-to-tail orientation and are linked together along their length; *see* **duplex DNA**. **3** describing a telegraphic system, computer channel, etc. that permits two messages to be sent simultaneously in opposite directions.

duplex DNA double-stranded **DNA** in which the two polynucleotide chains are linked together by hydrogen bonds between complementary **base pairs** along their lengths, with the 3′→5′ phosphodiester bonds of the two chains running in opposite directions. Such a molecule is usually coiled into a double helix and it may or may not be covalently closed into a circular molecule and/or formed into superhelical DNA(*see* **supercoil**) *See also* **double helix**.

duplicate *(in biology)* to reproduce by division into two equal parts; *see* **binary fission**.

duplication *see* **gene duplication**.

dUrd *symbol for* a residue of the deoxynucleoside deoxyuridine; 2′-deoxyribosyluracil; uracil 2′-deoxyriboside (alternative to dU).

dUrd5′*P* *symbol for* deoxyuridine 5′-phosphate.

dUrd5′*PP* *symbol for* deoxyuridine 5′-diphosphate (alternative to ppdU).

dUrd5′*PPP* *symbol for* deoxyuridine 5′-triphosphate (alternative to pppdU).

DUST *see* **sequence filter**.

dUTP *abbr. for* deoxyuridine triphosphate, the common name for 2′-deoxyuridine 5′-triphosphate; 2′-deoxy-5′-uridylyl diphosphate, uracil 2′-deoxyriboside 5′-triphosphate.

dUTPase EC 3.6.1.23; *recommended name*: dUTP pyrophosphatase; *systematic name*: dUTP nucleotidohydrolase; *other name*: deoxyuridine-triphosphatase. An enzyme of nucleotide metabolism in eukaryotes that prevents the incorporation into DNA of deoxyuridylyl residues from dUTP by catalysing the hydrolysis of the latter to dUMP and pyrophosphate. Genes for dUTPase are found in several viruses, e.g. herpes simplex type 1.

Duve *see* **de Duve**.

dwarfism atypically short stature reaching adult heights of generally less than 1.25 m. There are various causes. A common one is an acquired or inherited defect related to the synthesis, secretion, or function of somatotropin (e.g. pituitary dwarfism, Laron dwarfism, and pigmyism). Other causes include congenital hypothyroidism, resistance to parathyroid hormone or fibroblast growth factor, and a wide variety of achondroplasias and metabolic disorders.

Dy *symbol for* dysprosium.

dyad **1** two units treated as one. **2** a meiotic chromosome in which the two homologous members of the tetrad have separated. **3** a pair of cells resulting from the first meiotic division. **4** a bivalent atom, molecule, or group. *See also* **dyad symmetry**.

dyad axis a twofold **rotation axis**.

dyad-related describing a phenomenon that occurs at a specific position with respect to a **dyad axis**.

dyad symmetry **1** the type of symmetry occurring in molecular structures in which there is repetition after every 180° rotation around a dyad axis. **2** *(in molecular biology)* the formal description of a palindromic sequence in which the axis of symmetry is at the centre of the palindromic sequence. *See* **palindrome**.

dye a natural or synthetic substance that strongly absorbs certain wavelengths of visible or near ultraviolet light and is used to colour material by becoming firmly attached to it. *See also* **stain**.

dye-exclusion test a test for cell viability based on the phenomenon that living cells exclude some dyes, e.g. Eosin and Trypan Blue, whereas dead cells take them up and become stained.

dye-laser a device for obtaining high-intensity light of chosen wavelength by passing the monochromatic emission beam of a **laser** through a stream of liquid containing a fluorescent dye, and then passing the emitted broad-band fluorescent light through a monochromator. By variation of the dye employed a wide range of wavelengths of high-intensity light can be obtained from the single-wavelength laser emission. The light obtained by this device is necessarily of longer wavelength than that of the laser emission.

dye-ligand chromatography *or* **pseudo-affinity chromatography** *or* **pseudo-ligand affinity chromatography** a technique similar to **affinity chromatography** in which the immobilized ligand is any one of certain reactive dyes (coupled usually to cross-linked agarose), the dye commonly being a triazinyl compound, e.g. Reactive Blue 2 or Reactive Red 120. The technique is thus sometimes referred to (inappropriately) as **triazine-dye affinity chromatography**. The fixed dye molecules selectively bind particular enzyme or other protein molecules; the specificity of the interaction varies widely with both protein and dye, although frequently the dye appears to mimic a natural ligand of the protein. Examples of use are the isolation of nucleotide-requiring enzymes (*see also* **nucleotide-binding fold**) and the removal or purification of albumin from serum. The underlying mechanism is not fully understood but appears to involve both hydrophobic (i.e. apolar) and strongly ionic interactions. Many uses may in reality be examples of **affinity-elution chromatography**.

dye-primer sequencing DNA sequencing reactions in which the primer is labelled with a fluorescent dye. Four reactions are carried out, each with a different dideoxynucleoside triphosphate and a primer labelled with one of four distinctive fluorescent dyes.

dye-terminator sequencing DNA sequencing reactions in which the four dideoxynucleoside triphosphates are each labelled with a different fluorescent dye.

dynactin the largest protein component of the **dynactin complex**, a 20S multiprotein assembly of total mass ~1.2 MDa, that activates dynein-based activity *in vivo*. A large structural component of the complex is an actin-like 40 nm filament composed of actin-related protein, to which other components attach. Vertebrate dynactin is a ubiquitously expressed cytoplasmic protein; several isoforms, of mass ranging from 117 kDa to 160 kDa, are produced by alternative splicing. It shares a high degree of similarity with the product of the *Drosophila* gene *glued*, essential during embryogenesis, some mutations of which kill homozygous embryos.

dynamic of, or concerned with, motion or force, or with dynamics.

dynamic programming a programming method that finds the optimal alignment between pairs of protein or nucleotide sequences by exploring all possible alignments and choosing the best, based on a given scoring matrix. Dynamic programming solves complex problems by building up from smaller subproblems using a recursion relation. For example, the **Needleman–Wunsch alignment algorithm** is a dynamic global alignment algorithm, whereas the **Smith–Waterman alignment algorithm** is a dynamic local alignment algorithm.

dynamics **1** the branch of a science, especially mechanics, concerned with the motions of objects and the forces that produce such motions. It includes **kinetics**. **2** those forces that produce change or movement in a system or molecule; the motions (e.g. of residues within a macromolecule) so resulting.

dynamic state of body constituents the phenomenon, discovered in the early 1940s, that body components, especially proteins, are in a state of continuous degradation and resynthesis (i.e. of dynamic equilibrium). It was subsequently found to be applicable to other body constituents, although genomic DNA is a notable exception.

dynamin a microtubule-associated protein able to bind and hydrolyse GTP. The dynamin family includes two types, neuron-specific dynamin 1, and the widely expressed dynamin 2, which exhibit a high degree of sequence similarity in the 300 amino acid N-terminal region containing the GTP-binding site, but show divergence in a 100 amino acid proline-rich C- terminal region that in dynamin 1, but not dynamin 2, is a site for regulation of GTPase activity by phosphorylation–dephosphorylation. Dynamins are activated by protein kinase C and have a **pleckstrin homology domain**, which binds acidic (especially inositol-) phospholipids, with activation of the GTPase activity. Dynamins are involved in formation of microtubule bundles, and in vesicular trafficking; purified dynamin 2 in solution forms helical structures that *in vivo* may facilitate clipping of vesicles budding from the plasma membrane, and accelerate endocytic recycling. The *Drosophila* protein (a dynamin 2) is a product of *shibire*, a gene known to be involved in endocytosis.

dyne *symbol*: dyn; the CGS unit of force, defined as the force required to give one gram an acceleration of one centimetre per second per second. A gram weight thus represents a force of about 980 dyn. 1 dyn = 10^{-5} N.

dynein a large, multisubunit protein complex with ATPase activity, that is associated with microtubules, and functions as a molecular motor to drive the movement of a diverse range of intracellular structures, such as endosomes, lysosomes, and mitochondria, along microtubules towards the centrosome. It is also attached to the peripheral fibrous components of eukaryotic flagella and cilia, and is responsible for their movement; it may also play a role in the separation of chromosomes at cell division. The complex consists of two heavy chains (~500 kDa), three or four intermediate chains (~70 kDa), and four light chains (~50 kDa).

dynorphin an opioid tridecapeptide of high potency found in pig brain, duodenum and pituitary, having the structure

Tyr-Gly-Gly-Phe-Leu-Arg-Arg-Gln-Phe-Lys-Val-Val-Thr,

the N-terminal pentapeptide sequence of which is identical to **[5-leucine]enkephalin**. It is synthesized as **preprodynorphin** (*also called* preproenkephalin B), from which its precursor protein **prodynorphin** (*also called* β-neoendorphin *or* proenkephalin B), a 236-residue polypeptide, is formed. *See also* **endorphin**.

dys+ *prefix* indicating abnormal, diseased, impaired, painful, or difficult.

dysferlin a protein (2080 amino acids) of heart and skeletal muscle. It has no known function and is homologous with the spermatogenesis factor fer-1 of *Caenorhabditis elegans*. Nonsense mutations in the gene at 2p13 produce dysferlin deficiency and limb-girdle muscular dystrophy type 2B.

dysfunction any abnormality or disturbance in the function of an organ, tissue, cell, or part of a cell. —**dysfunctional** *adj.*

dysgenic genetically deleterious.

dyskeratosis congenita a rare syndrome of skin defects (leukoplakia, atrophy and pigmentation, nail dystrophy), heightened susceptibility to epithelial cancers, and bone marrow failure. It is caused by mutations in the gene for **dyskerin**.

dyskerin a putative pseudouridine synthase that catalyses site-specific isomerization of uridine residues in RNA to pseudouridine. It is associated with snoRNA and binds to the RNA component of telomerase. Mutations in the gene at Xq28 result in **dyskeratosis congenita**.

dysmorphology **1** the abnormal development of form or shape. **2** an anatomical feature that is abnormal. Some are caused by mutations, such as cleft lip and palate. **3** the study of abnormal development. –**dysmorphological** *adj*. –**dysmorphologically** *adv*.

dysplasia the abnormal development of tissue. –**dysplastic** *adj*.

dystrobrevin a phosphoprotein of human and murine muscle that is associated with the C-terminal region of **dystrophin**. It is a homologue of an 87 kDa protein of the postsynaptic membrane of the electric organ of electric rays (*Torpedo* spp.).

dystroglycan a protein precursor yielding a 43 kDa trans-membrane glycoprotein and an extracellular 156 kDa dystrophin-associated glycoprotein in skeletal muscle; the 156 kDa component binds **laminin**, acting as a laminin receptor that links the extracellular matrix and **sarcolemma** in skeletal muscle.

dystrophin a protein present in small amounts in normal muscle, but absent or abnormal in patients with **Duchenne muscular dystrophy**. It interacts with syntrophins, and may play a role in anchoring the cytoskeleton to the plasma membrane. The DMD gene is the largest in humans, with 2.4 million bp; it contains 79 exons, and takes more than 16 hours to be transcribed and co-transcriptionally spliced. *See also* **dystroglycan, utrophin**.

dystrophin-related protein (*abbr* DRP) *see* **utrophin**.

dystrophy any disorder, sometimes genetic, of the structure and functions of an organ or a tissue, as of muscle or bone. —**dystrophic** *adj.*

Ee

e *symbol for* **1** electron; it may be written as e^- to indicate its charge; e^+ denotes a positron. **2** *(in mathematics)* the transcendental number equal to the limiting value of the series [1 + (1/*n*!)] for *n* = 1 to infinity; its value is 2.71828182846. It is used as the base of natural (Napierian) logarithms. **3** equatorial; *see* **conformation**.

e′ *symbol for* pseudo-equatorial; *see* **conformation**.

e *symbol for* **1** elementary charge (or proton charge) **2** efficacy (of a drug).

E *symbol for* **1** a residue of the α-amino acid L-glutamic acid (alternative to Glu). **2** elimination reaction. **3** electromeric effect (in electron displacement). **4** exa+ (SI multiplicative prefix denoting 10^{18}).

$[E]_0$ *or* $[E]_t$ *or* $[E]_{stoich}$ *(in enzyme kinetics) symbol for* the total or stoichiometric concentration of active (catalytic) centres.

E_2

E_1 **1** *abbr. for* estrone. **2** the pyruvate dehydrogenase (lipoamide) component of **pyruvate dehydrogenase complex**. **3** *see* **ubiquitin-activating enzyme E1**.

E_2 **1** *abbr. for* estradiol. **2** the dihydrolipoamide *S*-transacetylase component of **pyruvate dehydrogenase complex**. **3** *see* **ubiquitin-conjugating enzyme**.

E_3 **1** the dihydrolipoamide dehydrogenase component of **pyruvate dehydrogenase complex**. **2** *see* **ubiquitin–protein ligase**.

E74 a protein, expressed during development of *Drosophila*, that correlates with an ecdysone-induced activity of puff 74EF. It is encoded by *Drosophila EIP74Ef*, an ecdysone-inducible gene that encodes two *ETS*-related protein products, E74A and E74B, that differ mainly in their N-terminal regions, and have substantial poly-Ala, poly-Asn, poly-Gln, poly-Gly and poly-Ser domains.

E *symbol for* **1** *(in chemical nomenclature)* a specific configuration around a double bond; *see* ***E*/*Z* convention**. **2** electromotive force. **3** electric potential difference (of a galvanic cell). **4** energy; kinetic energy and potential energy may be denoted by the symbols E_k and E_p respectively. **5** extinction coefficient (no longer recommended). **6** *(bold italic)* electric field strength (*see* **electric field**).

(*E*)- prefix *(in chemical nomenclature)* denoting a geometric isomer in which the highest priority ligands according to the Cahn–Ingold–Prelog rules (*see* **sequence rule**) are located on opposite sides of a double bond. *See also* ***E*/*Z* convention**.

-*E* conformational descriptor denoting the envelope conformation of a monosaccharide or monosaccharide derivative.

E^o *or* $E^{\ominus}$ *symbol for* standard electrode potential.

E' *or* $E^{\ominus\prime}$ *symbol for* standard electrode potential at a specified pH.

E_a *or* E_A *symbol for* (Arrhenius) activation energy.

E_{ea} *symbol for* electron affinity (def. 2).

Eadie–Hofstee plot a graphical representation of enzyme kinetic data in which the reaction velocity divided by the substrate concentration, *v*/[S], is plotted as ordinate against the reaction velocity, *v*, as abscissa. If a straight line is obtained, the intercept on the abscissa gives the maximum velocity, *V*, and that on the ordinate V/K_m. The slope is $-1/K_m$. [After George Sharpe Eadie (1895–1976) and Barend Hendrik Jan Hofstee (1912–80). US biochemists, who independently described it in 1942 and 1952, respectively.]

***Eae*I** a type 2 **restriction endonuclease**; recognition sequence: [TC]↑GGCC[AG]. *Cfr*I is an **isoschizomer**.

Eagle's medium any of various growth or maintenance media used in tissue culture and essentially comprising a balanced salt solution, usually **Earle's balanced salt solution** or **Hanks's balanced salt solution**, supplemented with amino acids, vitamins, serum, and antibiotics.

***Eam*1105I** a type 2 **restriction endonuclease**; recognition sequence: GACNNN↑NNGTC.

EAR-3 *see* **COUP**.

Earle's balanced salt solution a solution used in tissue culture to provide a normal ionic, pH, and osmotic environment for cell growth. It contains, per 100 ml distilled water, 0.68 g NaCl, 0.04 g KCl, 0.02 g $CaCl_2$, 0.02 g $MgSO_4 \cdot 7H_2O$, 0.0125 g $NaH_2PO_4 \cdot H_2O$, 0.22 g $NaHCO_3$, 0.1 g glucose, and 0.002 g phenol red; it has a pH of 7.6–7.8.

early enzyme an enzyme that is transcribed from an **early gene** (def. 2) of a virus. *Compare* **late enzyme**.

early gene 1 *or* **immediate gene** any of a number of genes involved in the earliest responses of cells to factors that initiate the transition from quiescence to proliferation. Early genes include those that encode transcription factors, such as the c-*jun*, c-*fos*, and c-*egr* genes, and those coding for structural proteins such as actin. Early genes are further subdivided into immediate-early and delayed-early genes. **2** any viral gene that is transcribed early after the virus infects a host cell. Such genes probably code for proteins that are necessary for viral nucleic acid replication. *Compare* **late gene**.

early growth response protein any of a family of proteins that are expressed early in response to growth factors and function as transcriptional regulators, binding to the DNA sequence 5′-CGCCCCCGC-3′.

early protein a protein that is transcribed from an **early gene** (def. 2) of a virus. *Compare* **late protein**.

early quitter any incomplete polypeptide formed in an *in vitro* translation system.

Easson–Stedman model a model to explain the differences in biological activity of two enantiomeric molecules; it assumes that three of the groups attached to an asymmetric carbon atom in an agonist (or substrate) are involved in its attachment to a specific receptor (or enzyme), one enantiomer will therefore be a better agonist (or substrate) than the other. The concept is similar to, but considerably pre-dates, that developed by Ogston (*see* **Ogston concept**).

EBI *abbr. for* European Bioinformatics Institute; *see* **bioinformatics institute**.

4E-BP *abbr. for* eIF4E-binding protein; any of a group of small proteins that bind eIF4E (the mRNA 5′ cap-binding protein) thus controlling its availability for initiating translation. The state of phosphorylation of 4E-BP controls its binding to eIF4E. Under conditions that induce **apoptosis**, interaction of 4E-BP with eIF4E increases, so that initiation of translation decreases.

EBV *or* **EB virus** *abbr. for* Epstein–Barr virus.

EC *abbr. for* **1** Enzyme Commission; it is used as a prefix in the numerical designation of an enzyme (*see* **enzyme classification**). **2** electron capture. **3** enterochromaffin (as in **EC cell**).

EC_{50} *abbr. for* half effective concentration; the molarity of an agonist that produces 50% of the maximal possible effect of that agonist. Other percentage values (EC_{20}, EC_{40}, etc.) can be specified. The action of the agonist may be stimulatory or inhibitory.

EC cell *abbr. for* enterochromaffin cell.

eccrine 1 describing a secretory cell that discharges its product without loss of cytoplasm. **2** describing a gland made up of such cells. *Compare* **apocrine**, **holocrine**, **merocrine**.

ECD *abbr. for* **1** electron capture detector. **2** electrochemical detection. *See* **polarography**.

ecdysis the periodic shedding of the exoskeleton and construction of a new cuticle, as in insects and crustaceans, or the shedding of the outer layer of the skin, as in reptiles. —**ecdysial** *adj.*

ecdysone 1 α-ecdysone (22*R*)-2*β*,3*β*,14,22,25-pentahydroxycholest-7-en-6-one; the **ecdysteroid** that is synthesized in and secreted by the prothoracic glands of immature insects and the ovaries of the adult females. First isolated from the silkworm moth (*Bombyx mori*), it is the inactive prohormone of the moulting hormone **ecdysterone**; it may also have intrinsic hormonal activity at other stages of insect development. **2 β-ecdysone** *an alternative name for* **ecdysterone**. **3** *a former name for* **ecdysteroid**.

ecdysone-inducible mammalian expression system a system for the expression of exogenous transgenes in mammalian cells in which the timing of expression is dependent on the administration of the insect hormone ecdysone.

ecdysone receptor a receptor for ecdysone, located in the cell nucleus and related to the steroid/thyroid/retinoic acid family of nu-



ecdysone

clear hormone receptors. It consists of a heterodimer of a subunit named EcR (ecdysone receptor) and another named USP (ultraspiracle), the insect homologue of vertebrate retinoid X receptor. The heterodimer binds ecdysone with high affinity, and the ternary complex binds to DNA.

ecdysteroid *or (formerly)* **ecdysone** any of a group of polyhydroxylated ketosteroids of which α-ecdysone is the parent substance for the purpose of nomenclature (*see* **ecdysone**). They are almost invariably C_{27} steroids, differing only in the number and/or steric arrangement of their hydroxyl groups. Ecdysteroids are ubiquitous in insects and other arthropods, in which they initiate postembryonic development, including the metamorphosis of immature forms and the development of the reproductive system and the maturation of oocytes in adult females. They have been found also in annelids, molluscs, and nematodes. Cognate substances, often known as **phytoecdysones**, have been identified in plants. The principal ecdysteroids in insects are α-ecdysone (*see* **ecdysone** (def. 1)) and **ecdysterone**.

ecdysterone *or* **β-ecdysone** *or* **crustecdysone** *or* **(insect) moulting hormone** 20-hydroxyecdysone; (22*R*)-2β,3β,14,20,22,25-hexahydroxycholest-7-en-6-one; the **ecdysteroid** isolated both from insects and from crustaceans. In insects, ecdysterone is formed in peripheral tissues from α- **ecdysone** through the action of ecdysone 20-monooxygenase (EC 1.14.99.22). The hormone causes puffing of polytene chromosomes, and initiates moulting of larval and pupal forms by stimulating the epidermal cells to enlarge, divide, and secrete degradative enzymes that dissolve the protein and chitin components of the cuticle. Moreover, in the adult females of certain insects, e.g. mosquitoes (*Aëdes* spp.) and *Drosophila melanogaster*, ecdysterone formed from α-ecdysone in the ovaries stimulates vitellogenin synthesis in the fat body.



e-cell a computer model of a cell generated using genomic, proteomic, transcriptomic, and metabolomic data.

ECF *abbr. for* extracellular fluid.

ECG *or (US)* **EKG** *abbr. for* **1** electrocardiograph. **2** electrocardiogram.

echinocandin any of a group of cyclic hexapeptides that contain an *N*-acyl aliphatic or aryl side chain. They inhibit synthesis of 1,3β-glucans of fungal cell walls and are effective against *Candida* spp., *Aspergillus* spp., and *Pneumocystis carinii*. Examples include caspofungin, micafungin, and anidulafungin.

echinochrome A 2-ethyl-3,5,6,7,8-pentahydroxy-1,4-naphthalenedione; a red pigment of sea urchin eggs.



echinoderm any of the phylum Echinodermata of marine invertebrates that contains sea urchins, sea cucumbers, starfish, etc. They are more or less radially symmetrical, with calcareous skeletal plates in their skin and a well-developed coelom. Locomotion and gaseous exchange are accomplished by means of retractable tube feet. They are related to the same ancestral stock that gave rise to the vertebrates.

ECL *abbr. for* enhanced chemiluminescence.

eclipsed conformation *see* **torsion angle**.

eclosion hormone any peptide hormone that programmes the death of certain muscles and neurons during metamorphosis of insects.

***Eco*52I** a type 2 **restriction endonuclease**; recognition sequence: C↑GGCCG. *Xma*III is an **isoschizomer**.

***Eco*81I** a type 2 **restriction endonuclease**; recognition sequence: CC↑TNAGG. *Sau*I is an **isoschizomer**.

EcoCyc *see* **pathway database**.

E. coli *abbr. for Escherichia coli.*

ecology the branch of biology dealing with the relations of living organisms to their surroundings. —**ecological** *adj.*; **ecologically** *adv.*; **ecologist** *n.*

ecomone any nontrophic molecule that ensures a flux of information between organisms in an **ecosystem**.

***Eco*O65I** a type 2 **restriction endonuclease**; recognition sequence: G↑GTNACC. *Bst*EII and *Bst*PI are **isoschizomers**.

***Eco*O109I** a type 2 **restriction endonuclease**; recognition sequence: [AG]G↑GNCC[TC]. *Dra*II is an **isoschizomer**.

***Eco*RI** a type 2 **restriction endonuclease**; recognition sequence: G↑AATTC. The M.*Eco*RI modification site is A3.

***Eco*RV** a type 2 **restriction endonuclease**; recognition sequence: GAT↑ATC.

ecosystem a unit of the environment together with the organisms it contains. There is a constant interchange between living organisms and their chemical and physical environment.

***Eco*T14I** a type 2 **restriction endonuclease**; recognition sequence: C↑C[AT][AT]GG. *Sty*I is an **isoschizomer**.

***Eco*T22I** a type 2 **restriction endonuclease**; recognition sequence: ATGCA↑T. *Ava*III is an **isoschizomer**.

ecotin a monomeric periplasmic protein of *Escherichia coli* that inhibits the pancreatic serine proteases chymotrypsin, trypsin, and elastase, allowing the organism to survive in the presence of these enzymes. It also inhibits blood coagulation factors Xa and XIIa, and kallikrein, thereby having anticoagulant effects.

ECP *abbr. for* eosinophil cationic protein.

ecstasy *see* **3,4-methylenedioxymethamphetamine**.

ECTEOLA cellulose *abbr. for* a weakly basic (p*K* ≈7.5) anion-exchange material of uncertain structure, prepared by the condensation of epichlorhydrin, triethanolamine (hence e,c + t,e,ola), and cellulose. It is useful for separations of proteins, nucleoproteins, and nucleic acids.

ecto+ *comb. form* indicating external, outer.

ectocrine describing or relating to a metabolite that, when released from the organism in which it was made, differentially affects other organisms of the same or a different species. Such a metabolite might be harmful to some members of a community and beneficial to others. The term includes **allomone**, **ectohormone**, **kairomone**, and **pheromone**. *Compare* **endocrine** (def. 1), **exocrine** (def. 1).

ectodysplasin A *abbr.*: EDA-A; a type II transmembrane protein of the tumour necrosis factor (TNF) family that contains a furin recognition sequence. It is present in keratinocytes, hair follicles, and sweat glands, and regulates development and differentiation of epidermal structures. There are two isoforms: EDA-A1 (391 amino acids) and EDA-A2 (389 amino acids). Their receptors activate NF-κB. Mutations in the furin recognition sequence cause X-linked anhidrotic ectodermal dysplasia.

ectoenzyme any enzyme that is attached to the external surface of the plasma membrane of a cell.

ectohormone any **ectocrine** substance whose production and release benefits either the organism producing it or other members of the same species. *Compare* **endohormone**.

ectoparasite any **parasite** that lives on the exterior of its host organism.

ectopic occurring in an unusual place or in an unusual form or manner. For example, an **ectopic protein** is a protein produced by a neoplasm derived from a tissue that does not normally produce that protein. An example is the production of **vasopressin** and **corticotropin** by small cell lung cancer. Ectopic pregnancy occurs when the fertilized ovum implants outside the uterus e.g. in a fallopian tube. *Compare* **entopic**.

ectoplasm the outer, relatively rigid part of the **cytoplasm**. *Compare* **endoplasm**. **—ectoplasmic** *adj.*

ectoplast the part of the plasma membrane of a plant cell that is in contact with the cell wall.

ectoprotein any individual protein found on the exterior of cells. Such proteins may function, e.g., as mediators of cell–cell or cell–surface interactions, or as receptors for substances with regulatory actions on cells.

ectosymbiont a partner in a symbiotic relationship that remains outside the tissues and cells of the other partner, often occupying a body cavity; e.g. one of the cellulose-metabolizing microorganisms occurring in the digestive tract of ruminants. *Compare* **endosymbiont**. *See also* **symbiosis**.

ED_{50} *abbr. for* median effective dose; i.e. the dose of a drug or other agent that produces, on average, a specified all-or-none response in 50% of a test population, or, if the response is graded, the dose that produces 50% of the maximal response to that drug or agent.

edeine any of several pentapeptide-amide antibiotics elaborated by a strain of *Bacillus brevis* and effective against Gram-positive and Gram-negative bacteria, some fungi and other eukaryotic cells, and some neoplastic cells. Edeine A_1, N^{a}[(N^2-{N^2-[*N*-(*b*-tyrosyl)-isoseryl]-2,3-diaminopropionyl}-2,6-diamino-7-hydroxyazela-9-yl)-glycyl]-spermidine, and its N^{x}-amidinospermidine analogue, edeine B_1, are highly active; their respective constitutional isomers, edeines A_2 and B_2, have low intrinsic activity. In intact bacteria, low concentrations of edeine reversibly inhibit DNA synthesis and enhance RNA synthesis but do not affect protein synthesis. In cell-free systems, edeine A_1 interacts with both ribosomal subunits (preferentially the smaller one) and strongly inhibits translation.



edeine A_1

EDEM a stress-inducible endoplasmic reticulum (ER) membrane protein that is homologous with α-mannosidase but is catalytically inactive. Through its transmembrane segment it interacts with calnexin and recognizes the folding status of glycoproteins in the ER.

edema *or (esp. Brit.)* **oedema** swelling of an organ or tissue due to the accumulation of fluid. **—edematous** *or (esp. Brit.)* **oedematous** *adj.*

edema factor *or (esp. Brit.)* **oedema factor** a protein component of the *Bacillus anthracis* toxin (responsible for anthrax) that causes tissue swelling.

edestin a 300 kDa globulin obtained from hemp seed, castor- oil beans, and certain other seeds. It readily forms polymorphic crystals and will support the growth of animals in the absence of other dietary proteins. [From Greek *edestos*, edible.]

edetate *see* **EDTA**.

EDF *abbr. for* erythroid differentiation protein; *see* **activin**.

Edg *abbr. for* endothelial differentiation gene; a gene that encodes a G-protein-coupled receptor present on endothelial cells. A major ligand for the receptor is sphingosine 1-phosphate, which on binding activates nitric oxide synthase.

editing **1** the process or act of altering or adapting erroneous molecular structures, especially nucleotide sequences in polynucleotides, so as to preserve fidelity in the transfer and expression of genetic information. For example, the 3′→5′ exonuclease activity of DNA polymerase I has an editing function in DNA polymerization by removing mismatched residues at the primer terminus of the growing chain. Another editing function is shown by aminoacyl-tRNA synthetases. In the presence of ATP and the 'wrong' amino acid, these enzymes do not catalyse the formation of the incorrect aminoacyl-tRNA but act as ATP pyrophosphatases, hydrolysing ATP to AMP and pyrophosphate. The term is applied also to the processes of conversion of RNA precursors, e.g. hnRNA, to the mature form, mRNA. **2** the insertion, deletion, or substitution of nucleotides within nascent RNA transcripts to produce RNA molecules with sequences that differ from those coded genomically. Most examples have been found in organelle-encoded RNAs, e.g. mitochondrial RNAs, and include ApoB, several **glutamate receptor** mRNAs, and **Wilms tumour** susceptible gene mRNA. In the case of ApoB, a cytidine residue is deaminated to a uridine residue so that the codon for glutamine (CAA) becomes a stop codon (UAA); hence, translation results in a shortened form of the protein.

editosome a macromolecular complex involved in the editing of RNA transcripts. Specific ribonucleotide complexes include guide RNA (*see* **gRNA**), which specifies the edited sequence.

Edman degradation a procedure used in sequencing (poly)peptides in which amino-acid residues are removed stepwise from the N terminus by reaction with phenylisothiocyanate, C_6H_5–N=C=S, to form the phenylthiocarbamyl-peptide (*abbr.*: PTC-peptide). This is then cleaved in anhydrous acid (which favours attack by the sulfur atom on the carbonyl carbon of the terminal peptide) to give a thiazolinone intermediate and the release of the remainder of the peptide chain. The thiazolinone intermediate is hydrolysed to the phenylthiocarbamyl derivative of the N-terminal amino acid, which then cyclizes to form the phenylthiohydantoin derivative (*abbr.*: PTH-amino acid). The PTH-amino acid is extracted into organic solvents and identified by chromatography. These derivatives have a strong UV-absorption at about 259 nm, which permits them to be visualized against a fluorescent screen using an ultraviolet light source. As the remainder of the peptide chain is liberated intact, the procedure may be repeated – up to about ten amino-acid residues may be sequenced in this way, or more in favourable cases. The procedure may be automated, e.g. in a **sequenator**. [After Pehr Victor Edman (1916– 77), Swedish protein chemist, who described the method in 1956.]

Edman reagent phenylisothiocyanate; C_6H_5–N=C=S. *See* **Edman degradation**.

EDR *abbr. for* equi-effective dose ratio.

EDRF *abbr. for* endothelium-dependent releasing factor (*see* **nitric oxide**).

EDTA ethylenediaminetetraacetate; edetate; any anion or salt, esp. the (hydrated) disodium salt, of edetic acid, ethylenediamine-*N,N,N′,N′*-tetraacetic acid, (ethylenedinitrilo)tetraacetic acid. Commonly used as the disodium salt, it is a powerful chelating agent for divalent metal ions.



ethylenediaminetetraacetic acid

EEDQ *abbr. for* *N*-ethoxycarbonyl-2-ethoxy-1,2-dihydroquinoline; an agent for peptide condensation that causes little or no racemization; it is useful in coupling ligands to insoluble polymers. It also causes progressive and irreversible inhibition of mitochondrial F_1-ATPase.



eEF-2 a eukaryotic **elongation factor** that is equivalent to the prokaryotic **EF-G**.

eEFsec *an alternative name for* **SelB**.

EET *(formerly) abbr. for* epoxyeicosatetraenoate.

EF *abbr. for* elongation factor.

EF-1 *see* **EF-T**, **elongation factor**.

EFE *abbr. for* ethylene-forming enzyme.

EFEMP *abbr. for* EGF-containing fibrillin-like extracellular matrix protein; either of two glycoproteins that contain multiple EGF repeats and belong to the fibrillin family of extracellular matrix proteins. A missense mutation in the EFEMP1 gene is common in an autosomal dominant form of retinal dystrophy. EFEMP2 is encoded at a different locus.

effective dose *see* **ED_{50}**.

effective theoretical plate number *symbol*: *N*; a number indicative of chromatographic column performance when resolution is taken into account: $N = 16R_s^2/(1–\alpha)^2$, where R_s is the peak resolution and α the separation factor (i.e. the ratio of the distribution ratios or coefficients for the two substances being resolved when measured under identical conditions); by definition α is greater than unity. *Compare* **height equivalent to an effective theoretical plate**. *See also* **theoretical plate**.

effectomer the part of a two-component agonist that brings about the biological effect but only when bound to a **haptomer**, which enables it to interact with the cell membrane and exert its toxic action on intact cells. For example, the A fragment of diphtheria toxin can only exert its toxic effects on a target cell when bound to the B fragment.

effector **1** *or* **modifier** *or* **modulator** *(in molecular biology)* any small molecule or ligand that interacts with an enzyme thereby changing its catalytic behaviour but that is not itself changed during the enzyme action. A **positive effector** enhances catalytic activity while a **negative effector** reduces it. *See also* **allosteric effector**. **2** *(in physiology)* a cell or organ that produces a physiological response when stimulated by the nervous system.

effector site *or* **regulatory site** any site on an enzyme molecule that binds an **effector**.

efferent **1** conveying outwards from a part, organ, or centre; e.g. of a blood vessel, nerve, or duct. **2** an efferent part, e.g. a blood vessel or nerve. *Compare* **afferent**.

efficacy *symbol*: *e*; a quantitative index of drug action related to the magnitude of a tissue response generated at a given level of receptor occupancy with (full) agonists (of high efficacy) generating the maximum possible response. Drugs with lower efficacy that cannot generate a maximal response even when all receptors are occupied are known as **partial agonists**; **antagonists** have an efficacy of zero. The overall response to a drug will be a function of its efficacy and receptor binding affinity, which determines the proportion of receptors occupied at a given concentration of drug. It may be formulated as the combination of an agonist with its receptors that results in a signal or a **stimulus**, *S*, equal to the product of the efficacy of the agonist, e_A, and the proportion of receptors occupied, P_{AR}; i.e. $S_A = e_A P_{AR}$. *See also* **intrinsic efficacy**, **maximal agonist effect**.

efficiency the ratio of the useful output of a machine, device, system, etc. to the input, whether in terms of thermal, mechanical, or radiation energy, or of biological or chemical conversions.

efficiency of counting *see* **counting efficiency**.

efficiency of plating *abbr.*: EOP; a quantification of the relative efficiencies with which different cells can be infected by viruses, and support viral replication. It is the ratio of the plaque count to the number of virions in the inoculum.

efflux *see* **flux**.

EF-G *or* **translocase** *abbr. for* an **elongation factor** of *Escherichia coli* that promotes the GTP-dependent translocation of the nascent protein chain from the A-site to the P-site of the ribosome. An equivalent factor in eukaryotes is named eEF-2.

EF-hand a **helix-turn-helix** motif that binds Ca^{2+}; it is found in many Ca^{2+}-binding membrane proteins and also in certain others, e.g. **myosin** light chain, and is so called because it involves helices E and F of the Ca^{2+}-binding protein. To envisage the motif, use the right hand with thumb and forefinger extended at ~90°, with the remaining three fingers clenched. The thumb will then point towards the C terminus of helix F, and the forefinger will point along helix E in the N-terminal direction, the clenched fingers tracing the course of the E–F loop about the bound calcium ion. Two apposed right-hands, representing the E and F and the C and D helices of the molecule, are related by a 2-fold axis of symmetry.

efrapeptin *or* **efrastatin** *or* **A23871** a hydrophobic peptide fungal antibiotic that inhibits oxidative phosphorylation by binding to the soluble component, F_1, of mitochondrial **H^+-transporting ATP synthase**.

EF-T *or* **transfer factor** a cytoplasmic protein of *Escherichia coli* and other prokaryotes that functions in protein synthesis to promote the GTP-dependent binding of aminoacyl-tRNAs to the A-site of the ribosome during protein chain elongation. EF-T can be dissociated into two polypeptides, EF-Tu and EF-Ts, so termed because, on initial isolation, one was heat-labile or unstable (Tu), and the other heat-stable (Ts); the complex is the main form in bacterial cells. Only Tu functions directly in the GTP-dependent binding of the aminoacyl-tRNA to the A-site of the ribosome, but Ts is required for regenerating Tu·GTP after the binding reaction, which results in the hydrolysis of GTP to GDP. The factors were originally isolated from both *E. coli* and *Pseudomonas fluorescens*. The 3-D structure of Tu shows high alpha-helix content, with identified binding sites for GTP and aminoacyl- tRNA. The Tu from *E. coli* is also a subunit of RNA polymerase of phage Qβ (Q beta). *See also* **elongation factor**.

EF-Ts *now designated* **EF-1B**; *see* **EF-T**.

EF-Tu *now designated* **EF-1A**; *see* **EF-T**.

egasyn an amphipathic glycoprotein, found in microsomal (i.e., endoplasmic reticulum) membranes of mouse liver, that forms a complex with microsomal (but not lysosomal) *β*-D-glucuronidase (EC 3.2.1.31), and thereby anchors it to the microsomal membranes. It may similarly anchor other polar proteins. It hydrolyses carboxylic esters to an alcohol and carboxylic anion. It has a C-terminal consensus sequence, HXEL, that retains the proteins in the endoplasmic reticulum. [From e (endoplasmic) + g (glucuronidase) + Greek *syn*, with.]

EG cell *or* **L cell** an **enteroglucagon**-producing endocrine cell. Such cells are found in the basal part of the mucosal glands in the lower intestine; the highest concentrations occur in the terminal ileum and colon. They contain large, dense, secretory granules and are easily distinguishable from other endocrine cells in the same area.

EGF *abbr. for* epidermal growth factor.

EGFP *abbr. for* enhanced green fluorescent protein.

egg the reproductive structure of certain animals, e.g. reptiles, birds, and insects, consisting of an **ovum** together with nutritive and protective tissues, and from which, when fertilized, a young offspring emerges.

egg albumin *the common name for* **ovalbumin**.

egg cell *an alternative name for* **ovum**.

egg white the white part of an egg (especially a bird's egg) surrounding the yolk. Its principal organic constituent is egg albumin (*see* **ovalbumin**).

EGR2 *abbr. for* early growth response 2; a C_2H_2-type of zinc-finger protein that is a transcription factor involved in myelination in the peripheral nervous system. Mutations in the gene on 10q21-q22 cause a Charcot–Marie–Tooth type 1 disease. *See* **myelin protein**.

EGTA *abbr. for* ethylene glycol-*O,-O′*-bis(2-amino-ethyl)-*N,N,N′,N′*-tetraacetic acid, [ethylenebis(oxyethylenetrinitrilo)]tetraacetic acid; also for any anion or salt thereof. It is a chelating agent with a high affinity for Ca^{2+} ions.



Ehlers–Danlos syndrome a heterogeneous group of inherited human disorders sharing many phenotypic features. Classically the clinical picture includes hyperelastic, fragile skin, poor wound healing, hyperextensible joints, and easy bruising. Ten distinct genetic forms have been described. Type I, which is severe, is inherited as an autosomal dominant; and is caused by mutations in collagen type V. Types II and III are inherited as autosomal dominants; they are due to mutations in collagen type V and type I, respectively. Type IV is inherited as an autosomal dominant and is caused by mutations in collagen type III. Type V shows X-linked inheritance but the cause is unknown. Type VI is inherited as an autosomal recessive, and is caused by deficiency of lysyl hydroxylase (EC 1.14.11.4). Types VIIA and VIIB are autosomal dominant and caused by mutations in collagen type I. Type VIIC is autosomal recessive and is caused by a deficiency of procollagen peptidase. Type VIII is autosomal dominant and of unknown cause. Type IX shows X-linked inheritance and is a variant of Menkes disease. Type X is autosomal recessive and associated with a defect in fibronectin. [After Edvard Ehlers (1863–1937), German dermatologist, and Henri Alexandre Danlos (1844–1932), French dermatologist, whose respective descriptions of the disorders were published in 1901 and 1908.]

Ehrlich's reagent a solution of *p*-dimethylaminobenzaldehyde in conc. HCl. It forms coloured complexes with a number of compounds, such as indoles, aromatic amines, ureides, and hydroxyproline, and is useful in the detection and estimation of these compounds. [After Paul Ehrlich (1854–1915), German medical scientist.]

EIA *abbr. for* enzyme immunoassay.

eicosa+ *or (before a vowel)* **eicos+** *a variant spelling (esp. US) of* **icosa+** (*comb. form* denoting twenty or twenty times). This spelling is universally used in naming **eicosanoids**, although not officially recommended.

eicosadienoic acid any straight-chain fatty acid having twenty carbon atoms and two double bonds per molecule. The *all-Z*-(8,11)-isomer is a normally minor metabolite of oleic acid in mammals, but is important as an intermediate in the pathway synthesizing *all-Z*-eicosa-5,8,11-trienoic acid (**Mead acid**) during essential fatty acid deficiency. The (5,11)-isomer occurs in gymnosperms, and several others have been synthesized. The (11*Z*,14*Z*)-isomer occurs as an intermediate in the synthesis of arachiodonate from linoleate via dihomo-γ-linolenate, but this is not the major pathway for this biosynthesis.

eicosanoic acid *the systematic name for* **arachidic acid**.

eicosanoid any C_{20} polyunsaturated fatty acid, commonly arachidonic acid (*see* **eicosatetraenoic acid**), or an **eicosapentaenoic acid**, or their derivatives. They include the **prostanoids** (i.e. prostaglandins, prostacyclins, and thromboxanes), **leukotrienes**, and **lipoxins**. They are noted for their widespread biological activity, such as contraction or relaxation of smooth muscle, platelet aggregation, and the inflammatory response. Produced mostly from arachidonate, they are released from phospholipids of the inner plasma-membrane leaflet by the action of phospholipase A_2, and modified by enzymes of the smooth endoplasmic reticulum. They are secreted and act as paracrine hormones that bind G-protein-associated receptors on neighbouring cells. Their catabolism occurs primarily in peroxisomes.

eicosapentaenoic acid any straight-chain fatty acid having twenty carbon atoms and five double bonds per molecule. The most noteworthy is the *all-Z*-(5,8,11,14,17)-isomer, which occurs in animal phospholipids, especially those of many marine species; fish oils are a good source, with eicosapentaenoic acids often representing up to 10% of total fatty acids. Eicosapentaenoic acids act as precursors of the PG_3 series of **prostaglandins**. The suggestion has been made that a higher than normal content of this acid in the diet can protect against heart disease.

eicosatetraenoic acid any straight-chain fatty acid having twenty carbon atoms and four double bonds per molecule. The *all-Z*-(5,8,11,14)-isomer is **arachidonic acid**. The (8,11,14,17)-isomer is an important intermediate in the formation of long-chain *n*-3 fatty acids from (9,12,15)-linolenic acid, being formed from that acid by desaturation at C-6 and chain elongation. The (5,11,14,17)-isomer is another naturally occurring form.

eicosatetraynoic acid any straight-chain fatty acid having twenty carbon atoms and four triple bonds per molecule. eicosa-5,8,11,14-tetraynoic acid (*abbr*.: ETYA) is a relatively nonspecific inhibitor of reactions involving arachidonate, including phospholipase A_2, **prostaglandin-endoperoxide synthase**, and **lipoxygenase**.

eicosatrienoic acid any straight-chain fatty acid having twenty carbon atoms and three double bonds per molecule. The *all-Z*-(5,8,11)-isomer (**Mead acid**) is synthesized in mammals in essential fatty-acid deficiency. The *all-Z*-(8,11,14)-iso mer, known also as dihomo-(6,9,12)-linolenic acid (*or* dihomo-γ-linolenic acid), is a precursor of arachidonic acid and of the PG_1 series of **prostaglandins**. The (5,11,14)-isomer has been found in higher plants and algae, cats, marine organisms, and insects.

eicosatriynoic acid any straight-chain fatty acid having twenty carbon atoms and three triple bonds per molecule. 5,8,11-eicosatriynoic acid (*abbr*.: ETI) is an agent that selectively inhibits 5- and 12-**lipoxygenase** without inhibiting **prostaglandin-endoperoxide synthase**.

eicosenoic acid any straight-chain fatty acid having twenty carbon atoms and one double bond per molecule. The 9*E*-isomer is gadelaidic acid (*see* **gadelaidate**); the 9*Z*-isomer is gadoleic acid (*see* **gadoleate**), a constituent of fish oils; and the 11*Z*-isomer is gondoic acid, present in seeds and fish oils.

EID *abbr. for* electroimmunodiffusion.

eIF *abbr. for* eukaryotic initiation factor (*see* **initiation factor**).

eIF4E-binding protein *see* **4E-BP**.

eIF2 kinase *an alternative name for* **PERK**.

eigenfunction a solution of a differential equation that has solutions only for particular values of some parameters.

eigenvalue any one of the possible values for a parameter of an equation for which the solution will be compatible with the boundary conditions.

einstein a non-SI unit used to express the energy associated with one mole of photons during a photochemical reaction. 1 einstein = $N_A h\,\nu$, where N_A is the Avogadro constant, h is the Planck constant, and ν is the particular frequency of the electromagnetic radiation effecting the reaction. [After Albert Einstein (1879–1955), German-born Swiss then US mathematical physicist]

Einstein–Sutherland relation a relation between the diffusion coefficient at infinite dilution, D_0, and certain molecular parameters. $D_0 = kT/f$, where T is the thermodynamic temperature, k is the Boltzmann constant, and f is the frictional coefficient of the diffusing particle.

EKG *abbr. (US) for* **1** electrocardiograph. **2** electrocardiogram.

elafin *another name for* **SKALP**. [From elastase f inhibitor. The ‘f’ was inserted to avoid confusion with elastin and gives an association to the Latin *finire*, to terminate.]

elaidate **1** *numerical symbol*: 18:1(9); *the trivial name for* (*E*)-octadec-9-enoate; $CH_3–[CH_2]_7–CH=CH–[CH_2]_7–COO^–$ (*trans* isomer); the anion derived from elaidic acid, (*E*)-octadec-9-enoic acid, a monounsaturated straight-chain higher fatty acid. **2** any mixture of free elaidic acid and its anion. **3** any salt or ester of elaidic acid. *Compare* **oleate**.

elaidinization *or* **elaidinisation** the *cis* to *trans* isomerization of mono- and polyunsaturated fatty acids, as in the isomerization of oleic acid to elaidic acid brought about by treatment with nitrous acid or by the action of rumen bacteria.

elaidoyl *the trivial name for* (*E*)-octadec-9-enoyl; $CH_3–[CH_2]_7–CH=CH–[CH_2]_7–CO–$ (*trans* isomer); the acyl group derived from elaidic acid, (*E*)-octadec-9-enoic acid. It occurs in acylglycerols to an appreciable extent in the body fats of ruminants, possibly having arisen from oleic acid by elaidinization. *Compare* **oleoyl**.

elaioplast any oil-storing **leukoplast** that occurs in plant cells.

ELAM *abbr. for* endothelial leukocyte adhesion molecule; i.e. E-selectin (*see* **selectin**).

elasmobranch **1** any member of the subclass Elasmobranchii, comprising fishes with cartilaginous skeletons such as sharks, skates, and rays. **2** of, pertaining to, or relating to the Elasmobranchii.

elastase historically, any proteinase that hydrolyses elastin. However, the name is now applied to a group of enzymes that vary in specificity. **pancreatic elastase**, EC 3.4.21.36 (*other names*: pancreatopeptidase E; pancreatic elastase I), catalyses the hydrolysis of proteins, including elastin, with preferential cleavage at Ala-|-Xaa. **Pancreatic elastase II**, EC 3.4.21.71, preferentially cleaves the carbonyl side of Leu, Met, and Phe. **leukocyte elastase** EC 3.4.21.37 (*other names*: lysosomal elastase; neutrophil elastase; bone marrow serine protease; medullasin), catalyses the hydrolysis of proteins, including elastin, with preferential cleavage at Val-|-Xaa > Ala-|-Xaa. Pancreatic elastase and leukocyte elastase, in common with most elastases, are serine proteinases, but others, e.g. elastase (EC 3.4.24.26) from *Pseudomonas aeruginosa*, are zinc-containing metalloproteinases. **Elastase III** is pancreatic endopeptidase E (EC 3.4.21.70; *other name*: cholesterol-binding proteinase); it shows preferential cleavage at Ala-|-Xaa, but does not hydrolyse elastin.

elastatinal a peptide produced by actinomycetes that inhibits serine proteineases, particularly elastase.



elastic *(of a body or a substance)* capable of returning to its original shape after deformation. **—elasticity** *n.*

elasticity coefficient *symbol*: ε_S^v; for a metabolic system in a steady state, the fractional change in the velocity, *v*, of an enzyme step caused by a fractional change in substrate, effector, or product concentration, *S*. It is given by:

$$\varepsilon_S^v = \frac{S}{v}\left(\frac{\partial v}{\partial S}\right)_{y,z,...} = \frac{\partial \ln v}{\partial \ln S}$$

Since the elasticity coefficient is defined as the partial derivative of a velocity, *v*, with respect to *S* (multiplied by the scaling factor, *S*/*v*) all other variables that are able to influence the rate through the enzyme are held constant. There are, for any reaction, as many elasticity coefficients as there are metabolites and effectors that interact with the enzyme in question. *See also* **controllability coefficient**, **response coefficient**, **sensitivity coefficient**.

elastin a major structural protein of mammalian connective tissues, especially elastic fibres, and found at sites such as the aorta, nuchal ligament, and lung. Glycine makes up one third of the amino-acid residues in elastin; glycine, proline, alanine, and valine together account for over 80% of its residues. The polymeric chains are cross-linked together into an extensible 3-D network, lysinonorleucine and desmosine cross-links being formed between allysine and lysine residues. A soluble precursor of elastin, **proelastin**, has been isolated from copper- deficient pigs in which the formation of allysine is blocked.

elastonectin a protein, M_r 120 000, from human skin fibroblasts, associated with adhesion of mesenchymal cells to elastic fibres.

elective theory of immunity *an alternative name for* **selective theory of immunity**

electrical coupling the phenomenon of ion transport across a membrane, in the absence of a cation–anion cotransport system, when the movement of anions and cations, following the law of electroneutrality, is governed only by the passive permeabilities of the membrane to the ions in question.

electric birefringence a form of **birefringence**, also known as the **Kerr effect**, caused by the alignment of (macro)molecules in an electric field.

electric capacitance *see* **capacitance**.

electric cell an apparatus consisting of two reversible electrodes dipping into the same solution, or into separate solutions electrically connected through an electrolyte bridge. It is used to generate an electromotive force, for electrolysis, or to measure the chemical activity of a chemical species in one of the solutions. *See also* **half-cell**.

electric charge *or* **quantity of electricity** *symbol*: *Q or q*; the attribute of certain elementary particles that is responsible for electric phenomena. Electric charge may be of two kinds, positive or negative, which interact electromagnetically such that like charges repel one another while unlike charges are attracted one to another. The SI derived unit of electric charge is the coulomb. *See also* **charge** (def. 3).

electric conductance *or* **conductance** *symbol*: *G*; a measure of the readiness with which an electric current can flow through a given component of a circuit. For a direct-current circuit it is equal to the reciprocal of the resistance; for an alternating-current circuit it is equal to the resistance divided by the square of the impedance. The SI derived unit of conductance is the siemens. *See also* **mho**.

electric current *or* **current** *symbol*: *I or i*; one of the seven SI base physical quantities – flow of electric charge through a conductor. The magnitude of a current is given by the amount of charge flowing per unit time. The SI base unit of electric current is the ampere.

electric dichroism the form of **dichroism** (def. 1) caused by orientation of (macro)molecules in an electric field.

electric dipole moment *see* **dipole moment**.

electric double layer *an alternative name for* **electrochemical double layer**.

electric field a **field** in which a stationary electric charge, *Q*, experiences a force, *f*, proportional to the magnitude of the charge. The electric field strength, *e*, is given by: $e = f/Q$; it is expressed in V m^{-1}. If the field is produced by other stationary charges it is called an **electrostatic field**. *Compare* **Coulomb's law**.

electricity **1** any of the forms of energy associated with moving or stationary electrons, protons, or other charge-bearing entities (whether molecular or otherwise). **Static electricity** is associated with stationary charges, **current electricity** with moving charges. **2** the science dealing with electricity.

electric potential *or* **potential** *symbol*: *V or* ϕ; the work done in bringing unit electric charge from infinity to a specified point in an electric field. The SI derived unit of electric potential is the volt.

electric potential difference *or* **potential difference** *symbol*: *E or U or* ΔV *or* Δu; *abbr.*: pd; the work done when a unit electric charge is moved between two points having different electric potentials. If the points are joined by a conductor an electric current will flow between them. The SI derived unit of electric potential difference is the volt. *Compare* **electromotive force**.

electric resistance *or* **resistance** *symbol*: *R*; the impediment to the flow of an electric current through a component of a circuit, a medium, or a substance. The SI derived unit of resistance is the ohm.

electro+ *or (sometimes before a vowel)* **electr+** *comb. form* indicating electric, electrically, electrolytic.

electroblot *see* **electrophoretic transfer**.

electroblotting *an alternative name for* **electrophoretic transfer**.

electrochemical analysis *or* **electrochemical assay** a chemical analysis or assay performed by means of electrolysis or electrodeposition.

electrochemical double layer any double layer of charges formed in a solution by the adsorption of a layer of ions of opposite charge at the surface of another charge-carrying phase, e.g. the walls of the vessel or the surface of a macromolecule.

electrochemical equivalent the mass of an ion deposited or liberated by the passage of 1 coulomb of electricity. In grams it is 1/96487 of the **chemical equivalent**.

electrochemical potential *symbo l*: $\tilde{\mu}$; the change in free energy occurring when a charged solute is transported either up or down a concentration gradient. It is the sum of the free energy changes due both to the concentration gradient and to the electric potential. It is expressed in J mol^{-1}.

electrochemical series *an alternative name for* **electromotive series**.

electrochemistry the branch of science concerned with the study of electrolysis, electrolytic cells, and the applications and properties of ions in solution. —**electrochemical** *adj.*

electrochromatography the form of **chromatography** in which separation of the constituents of a mixture is due to the effect of a constant electric field. *See also* **zone electrophoresis**.

electrochromism any reversible change in optical absorption or emission spectra of a molecule in the condensed phase due to an external electric field. *Compare* **photochromism**, **thermochromism**. —**electrochromic** *adj.*

electrocompetent describing *Escherichia coli* or other bacterial cells that have been suspended in a medium of low conductivity such as water or 10% glycerol to prepare them for transformation by electroporation.

electrocortin *the former name for* **aldosterone** (before establishment of its structure).

electrocrystallization *or* **electrocrystallisation** **electrodeposition** that results in crystal formation.

electrode any conductor, such as metal, metal covered with one of its salts, carbon, or a thin glass or other membrane, used to establish electric contact with a solution or other nonmetallic part of an electric circuit. The potential assumed by the electrode may depend on the (thermodynamic) activity of one of the solutes in the solution with which it is in contact. *See also* **anode**, **calomel electrode**, **cathode**, **enzyme electrode**, **hydrogen electrode**, **ion-selective electrode**, **oxygen electrode**, **quinhydrone electrode**, **reference electrode**.

electrodecantation *or* **electrophoresis convection** a technique for separating and fractionating proteins and other sols that exploits local differences in concentration and density that may occur during **electrodialysis**. Under the influence of gravity such density differences lead to large-scale separation of sols of high and of low concentrations. This results in a gradual increase in the concentration of a sol in the lower layers of the solution and a decrease in the upper layers.

electrodeposition the deposition of material from a dissolved or suspended state onto an electrode by the application of an electric field; it includes **electrocrystallization**.

electrode potential *symbol*: E; the electric potential between a reversible electrode and the solution in which it is immersed. It may be due to the loss or gain of electrons, if the solution contains a redox couple, or to the formation of ions from unchanged atoms or of atoms from ions, if the solution contains ions of a chemical element present as uncharged atoms in the electrode.

electrodialysis a form of **dialysis** conducted in the presence of an electric field across the membrane(s). It is useful for quickly removing ionic microsolutes from a solution containing nondiffusible material.

electroelution a technique in which application of an electric potential causes biomolecules to be transferred from an electrophoresis gel to a membrane during **blotting** procedures. *See also* **transfer membrane**.

electroendosmosis *a former term for* **electroosmosis**. —**electroendosmotic** *adj.*

electrofocusing *a newer name for* **isoelectric focusing**.

electrofuge *(in chemistry)* a leaving group in a reaction that does not carry away the bonding electron pair.

electrogenesis the generation of an electrochemical potential gradient, esp. across a membrane.

electrogenic pump any biological system that generates an electrochemical potential across a membrane by pumping one ion across the membrane without the concomitant movement of another ion of the same charge in the opposite direction.

electroimmunoassay *the original name for* **rocket immunoelectrophoresis**.

electroimmunodiffusion *abbr.*: EID; any technique for the analysis of antigenic macromolecules in which a combination of electrophoresis and immunodiffusion is employed. Four types may be distinguished: (1) one-dimensional single, i.e. **rocket immunoelectrophoresis**; (2) one-dimensional double, i.e. **counter immunoelectrophoresis**; (3) two-dimensional single, i.e. **crossed immunoelectrophoresis**; and (4) two-dimensional double, not so far individually named or much used.

electroimmunodiffusogram the immunoprecipitation pattern produced by any type of **electroimmunodiffusion**.

electrokinetic potential *or* **zeta potential** *symbol*: ζ; the potential drop across the mobile part of an **electrochemical double layer** that is responsible for electrokinetic phenomena. The electrokinetic potential is positive if the potential increases from the bulk of the liquid phase towards the interface.

electrolectin a lectin of the **galaptin** family from *Electrophorus electricus*, and the name of a group of β-D-galactoside-binding lectins found in teleosts, amphibians, and mammals.

electrolysis the chemical change produced by passing a direct electric current through a solution of an electrolyte, or through a fused electrolyte. Positively charged ions (cations) move towards the cathode and negatively charged ions (anions) move towards the anode, thus carrying the electric current. At the electrodes the positively charged ions gain electrons and negatively charged ions give up electrons, forming uncharged atoms, molecules, or radicals, which may either be deposited on the electrode or react with the electrode, the solvent, or each other. Alternatively, atoms of the electrode material may ionize and go into solution.

electrolyte any substance that, when in solution or molten, can undergo (partial or complete) dissociation into ions and hence is able to conduct an electric current by the movement of the ions.

electrolyte balance *(in physiology)* the sum total of the reactions and processes concerned with the maintenance of a constant internal environment in the body with respect to the distribution of ions between the various fluid compartments and excretions.

electrolytic **1** of, pertaining to, or produced by **electrolysis**. **2** of or pertaining to an **electrolyte**.

electrolytic conductivity *or (formerly)* **specific conductance** *symbol*: κ; the ability of an electrolyte to permit the flow of electric current, defined by the equation: $\kappa = j/e$, where j is the electric current density and e is the electric field strength. In SI units, κ is in S m^{-1}, j in A m^{-2}, and E in V m^{-1}. Electrolytic conductivity is usually measured in a rigid conductivity cell whose cell constant has been determined by means of a reference potassium chloride solution.

electromagnetic **1** of, relating to, or involving both electricity and magnetism; having both electrical and magnetic properties. **2** of or relating to **electromagnetic radiation**. **3 a** of, relating to, containing, or operated by an electromagnet. **b** of or relating to electromagnetism.

electromagnetic radiation *abbr.*: emr *or* EMR; radiation consisting of transverse waves of energy with associated electric and magnetic fields that can be represented by vectors at right angles to each other and to the direction of its propagation. The radiation results from the acceleration of electric charges and can be propagated through free space (i.e. it requires no supporting medium). The characteristics of the radiation vary with the frequency (or the wavelength) of the wave motion, the range of possible frequencies constituting the **electromagnetic spectrum**. From the low-frequency end of the spectrum to the high end are ranged: **radiofrequency radiation**, **infrared radiation**, visible radiation or **light**, **ultraviolet radiation**, **X-**

rays, and **gamma-radiation**. Radiation of all frequencies travels at the same velocity through space. The speed of light in vacuum, c_0, is defined as 299792458 ms^{-1}.

electromagnetic unit *abbr*.: emu *or* EMU; any of the electrical units based on the magnetic properties of electric currents. The force, F, between two magnetic poles of strength m_1 and m_2 placed a distance d apart in a medium of permeability μ is given by $F = m_1m_2/\mu\ d^2$. If F, μ, and d each be unity and if $m_1 = m_2 = m$, then m_1 and m_2 are poles of unit strength. Units based on this definition of m are electromagnetic units and are denoted by the prefix 'ab+'.

electromeric effect an obsolescent term for a molecular polarizability effect occurring by intramolecular electron displacement characterized by the substitution of one electron pair for another in the same atomic octet of electrons.

electrometer any instrument of very high input impedance that is used for detecting or measuring (changes in) the magnitude of an electric potential difference or electric charge esp. if of small value. Hence it is useful also for the (indirect) measurement of a very low electric current or a very high electric resistance, and for the detection or measurement of ionizing radiation. **—electrometric** *adj.*

electrometric titration 1 *an alternative name for* **potentiometric titration**. 2 *a name sometimes used generically for* **conductometric titration** and **potentiometric titration**.

electromotive force *abbr*.: emf *or* EMF; *symbol*: E; the energy supplied by a source of electric current in driving unit electric charge through an electric circuit. The SI derived unit of electromotive force is the volt. *Compare* **electric potential difference**.

electromotive series *or* **electrochemical series** a series in which the metals are arranged in decreasing order of their tendency to form cations by a reaction of the type: $M \rightleftharpoons M^+ + e^-$.

electromyogram *abbr*.: EMG; the tracing produced by an **electromyograph**.

electromyograph an instrument for detecting and recording the electrical activity of a muscle or group of muscles.

electron 1 *symbol*: e *or* e^- *or* β^-; a negatively charged elementary particle of rest mass, m_e, ≈9.109 39 × 10^{-31} kg and electric charge 1.602 177 33(49) × 10^{-19} C. It is sometimes termed a **negatron**, especially to distinguish it from its antiparticle, the positron. Electrons are present orbiting in all atomic nuclei and are involved in the formation of bonds between atoms. Specific designations of electrons in atoms and molecules include: σ-electrons, which participate in single bonds; π-electrons, which participate in double or triple bonds; and **p-electrons**, which participate in unshared electron pairs. 2 *(sometimes)* either a negatron (i.e. **electron** (def. 1)) or a **positron**. *See also* **beta-particle**.

electron acceptor 1 any substance to which an electron may be transferred. 2 *an alternative name for* **Lewis acid** (use discouraged). *Compare* **electron donor**.

electron affinity 1 the degree to which any molecular entity attracts one or more additional electrons. 2 *symbol*: E_{ea}; the minimum energy, expressed in joules, needed to remove an electron from a negatively charged molecular entity, or the reciprocal of the energy required to introduce an electron into a molecular entity.

electron-affinity spectroscopy a sensitive ionization method for the qualitative analysis of small quantities of organic compounds separated by gas chromatography, based on the differences in electron-capture ability that exist between the principal classes of organic compounds. The substances to be detected are passed through an ionized gas; the detector is sensitive to the resulting reduction in current.

electron capture 1 *or* **K-capture** *abbr*.: EC; a mode of decay of radionuclides in which an electron from an inner orbit of a decaying atom is absorbed into its nucleus, wherein a proton is converted to a neutron. Rearrangement of the orbital electrons then leads to the emission of characteristic X-radiation (*see* **X-radiation**). Generally the captured electron is derived from the K-shell, hence the alternative name. 2 *see* **electron-affinity spectroscopy**.

electron-capture detector *abbr*.: ECD; the type of detector used in **electron-affinity spectroscopy**.

electron carrier any molecular entity that serves as an electron acceptor and electron donor in an electron transport system.

electron-dense describing any structure, material, or compound that scatters an impinging electron beam, thus becoming apparent in **electron microscopy**, etc.

electron-dense label any atom group or substance (e.g. ferritin) that is **electron-dense** and that has been or may be attached in a specific manner to compounds or structures so as to show them up by electron microscopy, etc.

electron density the electron probability distribution in any molecular entity. If $P(x,y,z)$ is the electron density at the point with coordinates x,y,z, then the probability of finding an electron in the volume element $dxdydz$ is $P(x,y,z)\ dxdydz$. In, e.g., X-ray scattering experiments the scattering at this position is proportional to this probability. The term is often wrongly applied to negative **charge density**.

electron-density map a three-dimensional representation of the structure of a molecule or substance derived from X-ray diffraction data and made by the superposition of the electron-density contours of a series of imaginary parallel planes through the specimen being examined.

electron diffraction an effect observed when a narrow beam of electrons passes through a layer of material, e.g. a crystal, and is deflected by this material. The effect is due to the wavelike nature of electrons.

electron donor 1 any substance that is able to transfer an electron to another chemical species. 2 *an alternative name for* **Lewis base** (use discouraged). *Compare* **electron acceptor**. *See also* **donor atom**.

electron donor–acceptor chromatography *see* **charge-transfer chromatography**.

electron donor–acceptor complex *(sometimes) an alternative name for* 1 **charge-transfer complex** (use not recommended). 2 **Lewis adduct** (use not recommended).

electronegative 1 describing an atom or a group of atoms that tends to attract electrons, especially in the formation of a covalent bond. 2 describing any chemical or other entity that carries a negative charge and hence tends to move to the anode in electrophoresis.

electronegativity a measure of the power of an atom or group of atoms to attract electrons to itself from other parts of the same molecular entity.

electron equivalent the **equivalent** of any oxidizing (or reducing) agent that is equivalent to one entity of electrons.

electroneutrality condition the condition that in any solution the sum of the negative electric charges on ions must be equal to the sum of the positive charges on ions.

electron-exchange resin any synthetic resin containing groups able to undergo reversible oxidation–reduction reactions; such resins are useful as insoluble oxidizing or reducing agents.

electron gun a device used in electron microscopes, mass spectrometers, and other instruments to generate a beam of high-velocity electrons. It consists of a white-hot tungsten filament, as the electron source, and an anode kept at a potential of several tens of kilovolts above that of the filament. The electrons are accelerated towards the anode, which contains a small orifice through which some of the fastest electrons pass to form the electron beam.

electron hole the hole in the valency structure of an atom created by the absence of an electron when the energy level of an electron is raised from the valency band to the conduction band. The hole has a great tendency to recapture an electron. *See also* **hole**.

electronic 1 of or relating to an electron or electrons. 2 of, relating to, or operated by **electronics** (def. 2).

electronics 1 *(functioning as sing.)* the branch of science and technology concerned with electronic devices and circuits and with their development and applications. 2 *(functioning as pl.)* the circuits, devices, and equipment that function by the passage of electrons through semiconductors, transistors, and thermionic valves.

electronic transition the passage of an electron in a chemical entity from one energy level to another.

electron lens any arrangement of coils and/or electrodes producing a magnetic and/or an electric field used to focus an electron beam, e.g. in an electron microscope.

electron micrograph any photograph of an object taken with an **electron microscope**.

electron microscope *abbr*.: EM *or* e.m.; an instrument in which a magnified image of a sample is produced using a beam of high-energy electrons. The electrons are accelerated by means of an **electron gun**, using voltages in the range 40–100 kV, and the apparatus is evacuated to minimize electron scatter by air. In the **transmission electron microscope** (*abbr*.: TEM) the electron beam is focused onto a thin sample by a combination of magnetic and electric lenses and, after passing through the sample, the electrons are focused onto a fluorescent screen or photographic plate. The resolving power can be as great as 0.2–0.5 nm. In **cryoelectron microscopy**, lightly fixed frozen sections are employed. If these are used for the detection of antigens with antibodies coupled to colloidal gold, the technique is called **cryoimmunoelectron microscopy**. In the **scanning electron microscope** (*abbr*.: SEM) a narrow beam of electrons is made to scan to and fro across the sample by a varying field, and emitted **secondary electrons** are focused onto a screen to produce an image of the specimen. The specimen may be thicker than in the transmission electron microscope and, though resolution is lower with the scanning instrument, the depth of field is greater and the image gives a three-dimensional effect.

electron multiplier an electronic device for detecting, and counting, electrons, using **secondary emission**. It consists of an evacuated tube containing a series of electrodes, each held at a higher positive electric potential than the preceding one. When an electron hits the first electrode two or more **secondary electrons** are emitted; these are accelerated to the second electrode, where more electrons are produced, and so on.

electron nuclear double resonance *abbr*.: ENDOR; a phenomenon in nuclear magnetic resonance spectroscopy in which saturation of an electron resonance by the simultaneous application of a microwave field causes, under appropriate conditions, an improvement of the resolution of nuclear hyperfine structures.

electron optics the branch of science concerned with the effects of electric and magnetic fields on the movement of electrons, especially with the focusing and deflection of electron beams in **cathode-ray tubes**, **electron microscopes**, and similar devices.

electron paramagnetic resonance spectroscopy *abbr*.: EPR (spectroscopy); a technique, also called **electron spin resonance spectroscopy** (*abbr*.: ESR (spectroscopy)) and analogous to **nuclear magnetic resonance spectroscopy**, that is used to investigate paramagnetic centres in the system under study; only electrons whose spin is not paired with the oppositely directed spin of another electron give an ESR signal. Useful information is obtained by this technique about certain transition-metal ions (notably Cu^{2+}), (free) radicals, and free electron centres such as may be produced by X-irradiation of (macro) molecules. A **probe** (def. 2) giving an ESR signal may be incorporated into membrane lipids or attached to proteins to enable otherwise inaccessible systems to be studied by this technique. A distinction is sometimes made between EPR as applied to transition-metal complexes, in which the paramagnetism often comprises a strong orbital contribution, and ESR as to radicals, in which the *g*-factors are close to the free electron value.

electron probe X-ray microanalysis a highly sensitive technique for elemental microanalysis based on the frequencies and/or intensities of the characteristic X-rays emitted by each element present in a sample when it is excited by a beam of accelerated electrons.

electron sink *or* **electron trap** an **electrophilic** atom or group of atoms that can capture an electron from another part of a molecular system.

electron spectroscopy for chemical analysis *abbr*.: ESCA; *see* **photoelectron spectroscopy**.

electron spin *see* **spin** (def. 3).

electron spin-echo envelope modulation *abbr.* ESEEM; a pulsed technique in EPR spectroscopy, used to measure anisotropic nuclear hyperfine coupling. The intensity of the electron spin-echo resulting from the application of two or more microwave pulses is measured as a function of the temporal spacing between the pulses. The echo intensity is modulated as a result of interactions with the nuclear spins. The frequency-domain spectrum corresponds to hyperfine transition frequencies. The method gives analogous results to **ENDOR**, and is particularly effective for nuclei with a **quadrupole moment**.

electron spin-echo spectroscopy a technique giving precise values for electron spin relaxation times, in which intense microwave pulses at a frequency satisfying the resonance condition are applied to a paramagnetic sample in a magnetic field. Phase coherence in the spins is lost through relaxation when the pulse is switched off but can be restored by a second pulse 180° out of phase. The restoration of phase coherence gives rise to a nuclear induction signal (the echo).

electron spin-lattice relaxation time *(in* **electron spin resonance spectroscopy** *)* a measure of the time taken for the spin population to return to its equilibrium value by interaction with the fluctuating internal electric fields surrounding it.

electron spin resonance spectroscopy *abbr*.: ESR (spectroscopy); *see* **electron paramagnetic resonance spectroscopy.**

electron spin–spin relaxation time *(in* **electron spin resonance spectroscopy** *)* a measure of the time taken for phase coherence to be lost and equilibrium to be re-established through interaction with neighbouring spins. It is inversely proportional to the line width of the signal.

electron-transfer flavoprotein *or* **electron-transferring flavoprotein** *abbr*.: ETF; a protein containing flavin adenine dinucleotide (FAD) that in mammalian mitochondria and some bacteria, forms an intermediary electron carrier between several primary flavoprotein dehydrogenases (e.g. acyl- CoA dehydrogenase, EC 1.3.99.3) and the terminal respiratory chain. In mitochondria it consists of an α subunit (30 kDa, containing one FAD) and a β subunit (28 kDa, containing one adenosine 5′-monophosphate). *See* **glutaric acidemia**.

electron-transferring flavoprotein dehydrogenase *abbr*.: ETF dehydrogenase EC 1.5.5.1; an enzyme (pig heart, 64 kDa) that catalyses the oxidation of reduced ETF by ubiquinone to form ETF and ubiquinol. The ubiquinol is then oxidized by **ubiquinol–cytochrome *c* reductase**. It is an iron–sulfur flavoprotein involved in coupling the **beta-oxidation system** to the **respiratory chain**. *See* **glutaric acidemia**. *See also* **electron-transferring flavoprotein**.

electron-transferring fluoroprotein *see* **azurin**.

electron transport 1 respiratory electron transport; the process by which pairs of electrons derived from intermediates of the **tricarboxylic-acid cycle** and other substrates flow down the **respiratory chain** to dioxygen, the ultimate electron acceptor in respiration. **2 photosynthetic electron transport**; the process by which pairs of electrons are transported from H_2O to $NADP^+$ in the light phase of photosynthesis during noncyclic **photophosphorylation**.

electron-transport chain *an alternative name for* **respiratory chain**.

electron trap *an alternative name for* **electron sink**.

electronvolt *or* **electron volt** *symbol*: eV; a non-SI unit of energy equal to the kinetic energy acquired by an electron when accelerated through an electric potential difference of 1 volt. $1\ \mathrm{eV} = e \times \mathrm{V} \approx 1.602\ 18 \times 10^{-19}\ \mathrm{J}$, where *e* is the **elementary charge** and V is the volt.

electroosmosis *or (formerly)* **electroendosmosis** the motion of a liquid through a membrane (or plug or capillary) consequent upon the application of an electric field across the membrane. A similar phenomenon may occur in electrophoresis, where many of the supporting media used, e.g. paper or agar, acquire negative charges during electrophoresis at alkaline pHs and, since the medium cannot move, H_3O^+ ions move towards the cathode, giving the effect of an osmotic movement of solvent towards the cathode and making electrically neutral molecules appear to be cationic. **—electroosmotic** *adj.*

electropherogram *a variant spelling of* **electrophoretogram**.

electrophile *or* **electrophilic reagent** any chemical species that is preferentially attracted to a region of high electron density in another species during a chemical reaction. Such reagents normally are positively charged or contain electron-deficient chemical groups. They tend to react with electron-rich or negatively charged chemical species. *Compare* **nucleophile**.

electrophilic 1 of, pertaining to, or being an **electrophile**; having or involving an affinity for regions of high electron density in a chemical reactant. **2** describing a chemical reaction in which an electrophile participates.

electrophilic catalysis catalysis by a Lewis acid, i.e. any chemical species that abstracts an electron pair from the reactant.

electrophilic displacement *an alternative term for* **electrophilic substitution reaction**.

electrophilicity the relative reactivity of an **electrophile**, measured by the relative rate constants of different electrophiles towards a common reactant.

electrophilic reagent *an alternative name for* **electrophile**.

electrophilic substitution reaction *or* **electrophilic displacement** a chemical reaction in which an **electrophile** effects heterolytic substitution in another reactant, both bonding electrons being supplied by that other reactant.

electrophoresis 1 the phenomenon of the movement of ions (including macromolecular ions) or charged particles or ions through a fluid under the influence of an electric field applied to the fluid. A number of different media have been used as the fluid support, including paper, cellulose acetate, starch gel, and polycrylamide gel. Ions or particles bearing a net positive charge tend to move towards the negative pole of the electric field and vice versa, the rate of movement of a particular variety of ion or particle depending, *inter alia*, on its charge-to-mass ratio. The phenomenon has been widely applied in separating proteins, nucleic acids, and other charged molecular species for analytical or preparative purposes, and also in the analytical or preparative fractionation of heterogeneous populations of dispersed cells or other types of macroscopic particles. **2** the act or process of causing ions or charged particles so to migrate; any technique based upon such a phenomenon, e.g. **continuous flow electrophoresis**, **immunoelectrophoresis**, **moving boundary electrophoresis**, **paper electrophoresis**, **polycrylamide gel electrophoresis**, **zone electrophoresis**. *See also* **electrodecantation**. —**electrophoretic** *adj.*

electrophoresis convection *an alternative term for* **electrodecantation**.

electrophoretic effect the phenomenon of decreased **electrophoretic mobility** of a charged macromolecule caused by the movement of counter ions and/or solvent molecules in the opposite direction to that of the macromolecule.

electrophoretic mobility *symbol*: *u*; the **electrophoretic velocity**, *v*, of a charged particle expressed per unit field strength; hence, $u = v/e$, where *e* is the field strength. The value of *u* is positive if the particle moves towards the pole of lower potential and negative in the opposite case. The electrophoretic mobility depends only on molecular parameters.

electrophoretic mobility shift assay (*abbr*.: EMSA) *or* **gel retardation assay** a method to evaluate the binding of transcription factors to response elements in which the electrophoretic mobility of short, radiolabelled double-stranded DNA is reduced by the bound protein.

electrophoretic molecular sieving *(sometimes) an alternative term for* **polyacrylamide (gel) electrophoresis**.

electrophoretic titration curve the pH-mobility curve of an ampholyte, e.g. a protein, generated by subjecting a zone of it to electrophoresis in a gel slab at right angles to a preformed, stationary pH gradient. *Compare* **isoelectric focusing**.

electrophoretic transfer *or* **electroblotting** a development of the technique of blot transfer, in which proteins or nucleic acids are transferred from a separation gel to nitrocellulose or diethylaminoethyl- (DEAE-) cellulose membranes or to diazobenzyloxymethyl- (DBM)- or diazophenylthioether- (DPT-) paper by electrophoresis, rather than by capillary flow, with a consequent decrease in the time required for the transfer. The membrane or paper bearing a resultant pattern of separated substances has been termed an **electroblot**. *see* **blotting**.

electrophoretic velocity *symbol*: *v*; the velocity of a charged particle during electrophoresis. It is normally proportional to the electric field strength. *Compare* **electrophoretic mobility**.

electrophoretogram *or* **electropherogram** the result of a zone-electrophoretic separation, either directly visible or after staining or processing to produce a graph.

electrophysiology the part of physiology concerned with the electrical phenomena associated with bodily processes, such as nervous and muscular activity.

electroporate to create momentary pores in the membranes of living cells, without loss of their viability, by exposing them to a sequence of brief electrical pulses of high field strength. The reversible breakdown of the cell membranes thus caused enables treated cells to take up exogenous material (e.g. drugs or foreign DNA). —**electroporated** *adj.*; **electroporation** *n.*

electroporator an apparatus or device for effecting electroporation.

electropositive 1 describing an atom or group of atoms that tends to give up electrons, especially in the formation of a covalent bond. **2** describing any chemical or other entity that carries a positive charge and hence tends to move to the cathode in **electrophoresis**.

electropositivity a measure of the power of an atom or group of atoms to give up electrons to other parts of the same molecular entity.

electrospray a technique used in **mass spectrometry** in which a dilute acidic solution of the macromolecule is sprayed from a metal syringe needle maintained at +5000 v, forming fine highly charged droplets from which the solvent rapidly evaporates.

electrostatic of or pertaining to static electricity or electrostatics.

electrostatic bond any valency linkage between atoms arising from the transfer of one or more outer-shell electrons of one atom to the outer shell of another atom, leading to more complete outer shells in both atoms. The dissociation of an electrostatic bond leads to the production of ions.

electrostatic field any **electric field** produced by stationary charges.

electrostatic interaction any of the attractive or repulsive forces between atoms and/or groups of atoms and/or molecules that are due to the presence of ionized chemical entities and to the electronegative and electropositive properties of these atoms, groups, or molecules. *Compare* **electric field**.

electrostatic precipitation the removal of small particles suspended in a gas by electrostatic charging followed by precipitation onto a highly charged collector.

electrostatics the branch of physics concerned with static electricity.

electrostatic units *abbr*: esu *or* ESU; a system of electrical units, used in the cgs system, based upon the electrostatic unit of electric charge, i.e. the quantity of electricity that will repel an equal quantity of electricity, 1 cm distant from it in a vacuum, with the force of 1 dyne.

electrostriction the reversible change in dimensions of a dielectric when an electric field is applied to it. For example, the electrostatic field associated with a dissolved electrolyte causes a shrinkage in the volume occupied by the solvent.

electrotaxis the directional movement of an organism in an electric field. —**electrotactic** *adj.*

electrotropism any orientation response of a sessile organism to an electrical stimulus.

electrovalency *or (esp. US)* **electrovalence 1** the type of **valency** characterized by the transfer of one or more electrons from one atom to another atom, with the formation of ions. **2** the number of negative or positive charges acquired by an atom by the respective gain or loss of electrons. —**electrovalent** *adj.*; **electrovalently** *adv.*

electrovalent bond *an alternative term for* **ionic bond**.

electroviscosity the, usually minor, change in viscosity that occurs when an electric field is applied to some polar liquids.

eledoisin a **tachykinin** with the structure Glp-Pro-Ser-Lys-Asp-Ala-Phe-Ile-Gly-Leu-Met-NH_2; it is obtained from the posterior salivary glands of small octopus (*Eledone* spp.). It is more potent than **physalaemin** and **substance P** in some assay systems. It is useful as a lachrymal and salivary secretagogue and in the study of receptors for substance P.

element any basic and distinct component of matter that is not resolvable into simpler components with differing chemical properties. Each consists exclusively of atoms with the same unique **proton number** (although such atoms may not necessarily have the same **nucleon number** or **relative atomic mass**). Ninety-three chemical elements are known to occur naturally, either in the free state or in combination with others; to date, a further 16 have been produced artificially. —**elemental** *or* **elementary** *adj.*

elementary analysis any quantitative chemical analysis of the amounts of different chemical elements present in a sample.

elementary charge *or* **proton charge** *symbol*: *e*; a fundamental physical constant representing the electric charge on one electron (or proton). Its recommended value is $1.602\ 177\ 33\ (49) \times 10^{-19}$ C.

elementary particle **1** *or* **fundamental particle** any of the particles that form the base units of which all matter is composed. The stable elementary particles are protons, electrons, and neutrinos; they combine with neutrons to form stable atoms. Other, short-lived elementary particles are known. **2** *or* **Fernández–Morán particle** *or* **oxysome** *or* **stalked particle** any of the knoblike structures, 8–9 nm in diameter, seen in the electron microscope on the inner surface of the inner membrane of unfixed mitochondria negatively stained with phosphotungstate.

elementary rest mass *symbol*: m_e; the mass of an electron, it is a fundamental atomic constant, $9.109\ 3897(54) \times 10^{-31}$ kg.

eleostearate **1** *numerical symbol*: 18:3(9,11,13); *the trivial name for* octadeca-9,11,13-trienoate; $CH_3–[CH_2]_3–[CH{=}\ CH]_3–[CH_2]_7–COO^–$; the anion derived from eleostearic acid, octadeca-9,11,13-trienoic acid, a triunsaturated straight-chain higher fatty acid. It is a constitutional isomer of (6,9,12)-linolenate with conjugated double bonds. **2** any mixture of free eleostearic acid and its anion. **3** any salt or ester of eleostearic acid. *See also* **eleostearoyl**.

eleostearoyl *symbol*: eSte; *the trivial name for* octadeca-9,11,13-trienoyl; $CH_3–[CH_2]_3–[CH{=}CH]_3–[CH_2]_7–CO–$; the acyl group derived from eleostearic acid. The 9*Z*,11*E*,13*E*-isomer occurs naturally as acylglycerols in some seed oils, especially tung oil.

ELF *abbr. for* embryonic liver fodrin.

ELF1 a gene encoding transcription factors, related to the protooncogene ***ETS*** and named from E74-like factor (*see* **E74**), a *Drosophilia* protein that binds a regulatory element of the dopa decarboxylase gene.

elicitor a substance that induces the production of **phytoalexins** in higher plants. Elicitors may be exogenous (e.g. produced by potentially pathogenic bacteria or fungi) or endogenous, such as cell-wall degradation products.

elimination reaction a chemical reaction in which two groups are removed from a molecule of an organic compound without being replaced by other groups. In most such reactions the groups are lost from adjacent carbon atoms: one of the groups eliminated is commonly a hydron and the other a nucleophile, and the elimination results in the formation of a multiple bond. The reverse process is an **addition reaction**.

ELISA *abbr. for* enzyme-linked immunosorbent assay.

eLiXiR an agonist or antagonist of the oxysterol receptor.

Elk a family of cell-surface proteins similar to those encoded by the protooncogene **ETS**, and with presumed similar function (named from eph-like kinase); they are protein tyrosine kinases, restricted to brain and testis, having a single transmembrane domain and two fibronectin-like domains.

Elk-1 a gene-regulating protein, found in lung and testis, that binds to DNA at purine-rich sites. It is a substrate for a **MAP kinase** in the phosphorylation cascade, originating with activated protein kinase C or Ras; on phosphorylation, it forms a ternary complex with the transcription factor **SRF**, which binds to the **serum response element** of DNA, turning on *FOS* transcription.

ellagic acid 4,4′,5,5′,6,6′-hexahydroxydiphenic acid 2,6,2′,6′-dilactone; a commonly occurring plant polyphenol that inhibits glutathione S-transferase. It is present in many berries, is an antioxidant, and may prevent certain cancers.



ellipse any closed plane figure whose perimeter is the locus of a point that moves so that the sum of its distances from two fixed points, the foci, is constant. An ellipse has two axes of symmetry, the major axis at the furthest distance between opposing points on its circumference and the minor axis at the nearest distance.

ellipsoid any surface or solid figure whose plane sections are all either ellipses or circles. **—ellipsoidal** *adj.*

ellipsoid of rotation *or* **ellipsoid of revolution** a solid figure generated by the rotation of an ellipse about one of its axes. If the rotation is about the major axis the ellipsoid of revolution is said to be **prolate**, whereas if the rotation is about the minor axis it is said to be **oblate**. *See also* **equivalent ellipsoid of rotation**, **spheroid** (def. 2).

ellipsosome a compartment in the retinal cones of fish that contains cytochrome-like pigment.

elliptical of, relating to, or having the shape of an **ellipse** or **ellipsoid**. **—elliptically** *adv.*

elliptically polarized *or* **elliptically polarised** describing light (or other electromagnetic radiation), whose electric vector appears to follow an elliptical path when viewed along the light beam. *See also* **polarized light**.

ellipticity **1** the ratio of the lengths of the major to the minor axis of an **ellipse** or **ellipsoid**. **2** the arc tangent of the ratio of the lengths of the minor to the major axis of an ellipse. *See also* **circular dichroism**, **Cotton effect**, **molecular ellipticity**.

Ellman's reagent bis(4-nitro-5-carboxyl phenyl)disulfide, (formerly 5,5′-dithiobis(2-nitrobenzoic acid)) (*abbr*.: DTNB); a reagent used for labelling thiol (SH) groups in protein side-chains. The reagent reacts quantitatively with thiol groups, forming mixed disulfides and releasing the anion 5-sulfido-2-nitrobenzoic acid; this absorbs light at 412 nm, thus permitting the determination of the number of thiol groups in the protein sample. [After George Leon Ellman (1923–).]



elongase any of the long-chain fatty-acyl-coenzyme A elongating enzymes, found in mammalian microsomes, that act on saturated and unsaturated fatty-acyl derivatives having 16 or more carbon atoms per molecule of fatty acid.

elongation factor *abbr*.: EF; any of a group of soluble proteins required for chain elongation during polypeptide synthesis at the ribosome. In *Escherichia coli* there are three elongation factors: EF-Tu, EF-Ts (*see* **EF-T**), and **EF-G**. EF-Tu helps to bind aminoacyl-tRNA, via a tertiary complex, aminoacyl-tRNA•EF-Tu•GTP, to the ribosomal A-site. After EF-Tu-dependent GTP hydrolysis, the EF-Tu•GDP complex dissociates from the ribosome and is recycled to EF-Tu•GTP, probably via an EF-Tu•EF-Ts intermediate. *E. coli* EF-Tu and GTP form ternary complexes with all aminoacyl-tRNAs except the initiator, $\text{tRNA}^{\text{Met}}_{\text{f}}$ EF-G catalyses the GTP-dependent movement of the ribosome and the codon–anticodon-linked mRNA•peptidyl-tRNA complex relative to each other, resulting in the removal of a deacylated tRNA and the location of peptidyl-tRNA from the ribosomal A-site to the P-site. In eukaryotes three proteins, EF-1α, EF-1β, and EF-2, are required for the elongation events. EF-1α, which occurs in different tissues as aggregates of varying size of a polypeptide chain of M_r 53000, functions during chain elongation, like EF-Tu, to bring the aminoacyl-tRNA to the ribosomal A-site in a reaction in which GTP is hydrolysed. EF-1β, of M_r 30000, functions as EF-Ts. EF-2, like EF-G, catalyses the translocation of the peptidyl-tRNA from the ribosomal A-site to the P-site in a GTP-dependent reaction. Rat liver EF-2 has an M_r of 110000, while wheatgerm EF-2 has an M_r of 70000. *Compare* **initiation factor**, **release factor**.

elongin a heterotrimeric protein complex that is highly conserved in eukaryotes. It consists of elongin A, the catalytic subunit (773 residues); and the regulatory subunits elongin B (118 residues), which contains a ubiquitin-homology domain, and elongin C (112 residues). It enhances transcriptional elongation by suppressing pausing by eukaryotic RNA polymerase II. Elongins B and C also form part of a ubiquitin ligase complex and of the **VHL** protein complex.

Elson–Morgan reaction a colorimetric reaction for the estimation of combined and free hexosamines. The specimen is heated in alkaline solution with acetylacetone to form a pyrrole derivative, which then gives a red colour with *p*-dimethylaminobenzaldehyde on acidification. [After Leslie Alderman Elson and Walter Thomas James Morgan (1900–), British biochemist, who together described the reaction in 1933.]

eluant *a variant spelling of* **eluent**.

eluate 1 *(in chromatography)* the solution flowing from a chromatographic column; the desired material in such a solution. **2** *(in immunology)* a solution of material derived from an insoluble or particulate antigen–antibody complex, e.g. by heating or by treatment with an appropriate buffer solution.

eluent *or* **eluant** a liquid used in **elution**, particularly in **chromatography**.

eluent strength function *(in chromatography)* the order of an **eluotropic series** defined as the adsorption energy per unit area of standard activity of the solvent:

$$\log K = \log V_a + \alpha(S^o – A_s\varepsilon^o),$$

where K is the distribution coefficient in mass/volume of adsorbent and is independent of the solute concentration, V_a is the adsorbent surface volume, α is an adsorbent function proportional to the average surface energy of the adsorbent, S^o is a solute parameter equivalent to the adsorption energy of the solute from solution, A_s the area of absorbant occupied by solvent, and ε^o is a solvent strength parameter; the larger ε^o, the stronger the solvent.

eluotropic series a series of solvents arranged in the order of their relative abilities to effect **elution**.

elute to wash out or extract retained material, particularly from a chromatography column.

eluting 1 of or relating to **elution**, e.g. an eluting solvent. **2** the process of carrying out an **elution**.

elution the process of washing out or extracting adsorbed material from a chromatographic column.

elution volume *(in chromatography)* the volume of mobile phase that must pass through a chromatographic column, after sample application, to produce a peak in the concentration of a particular solute in the effluent or eluate.

elutriation the process of separating and purifying particles in a powder or suspension according to their rates of sedimentation. It may be effected by repeatedly washing, decanting, and settling, or by allowing a liquid or gas containing the particles to flow upwards (against gravity), when particles whose sedimentation rates are less than the rate of upward flow are washed away from the larger, heavier particles. *Compare* **centrifugal elutriation**, **electrodecantation**.

elutriator a device for grading finely divided material according to the sizes and weights of the particles by means of a stream of liquid or gas.

elymoclavine an **ergot alkaloid** produced by *Claviceps purpurea* and other fungi.

em+ *prefix; a variant of* **en+** *(sometimes before b, m, and p).*

EM *or* **e.m.** *abbr. for* electron microscope (*or* electron microscopy).

e-mail *abbr. for* electronic mail.

e-mail address an address for e-mail of the form <name>@<address> where the <address> is an **IP address** in its named format, for example, president@whitehouse.gov.

EMBASE *see* **bibliographic database**.

Embden–Meyerhof pathway *or* **Embden–Meyerhof–Parnas pathway** *alternative names for* **glycolytic pathway**. [After Gustav Embden (1874–1933) and Otto **Meyerhof** (1884–1951), German biochemists, and Jacob Karol Parnas (1884–1949), Polish biochemist.]

EMBL 1 *abbr. for* European Molecular Biology Laboratory; an international research facility based at Heidelberg in Germany. **2** a major database of nucleic acid and protein sequences maintained by EMBL. *See* **sequence database**.

EMBL4 a bacteriophage lambda replacement vector.

EMBO *abbr. for* European Molecular Biology Organization.

embolus (*pl.* **emboli**) a thrombus fragment that is transported in the circulation to distant tissues, where it can cause ischemic tissue damage.

EMBOSS *abbr. for* European Molecular Biology Open Software Suite; *see* **sequence analysis package**.

embryo the structure that develops from a **zygote**, up to the time of birth or hatching in eutherian animals, or of germination in plants. In mammals the term is restricted to the structure present in the early part of gestation that develops into a **fetus**. **—embryonic, embryonal** *adj.*

embryogenesis *or* **embryogeny** the formation of an embryo from an ovum and the processes of its development. **—embryogenic** *adj.*

embryology the branch of biology concerned with the study of embryos and their development. **—embryological** *or* **embryologic** *adj.*; **embryologically** *adv.*; **embryologist** *n.*

embryonated differentiated into, or having an embryo, e.g. an embryonated hen's egg.

embryonic stem cell *abbr.*: ES cell; a **totipotent** cell that can be cultured from an early embryo.

embryonin *another name for* bovine **α_2-macroglobulin**.

emerimicin *see* **peptaibophols**.

emerin a nuclear membrane protein (254 amino acids) that is present in most tissues and is linked to the lamins of the nuclear lamina. It is serine-rich, homologous with lamina-associated protein 2 (LAP2) and contains a C-terminal transmembrane segment. During mitosis it becomes dispersed throughout the cell and participates in formation of the daughter nuclei. In the heart, it is also localized with the intercalated discs. Mutations in the gene at Xq24.3 cause the X-linked form of Emery–Dreifuss muscular dystrophy.

Emerson enhancement the phenomenon in photosynthesis in which the **quantum yield** of light in the far-red region of the spectrum is enhanced by weak background illumination with shorter wavelength light. *Compare* **enhancement spectrum**. [After Robert Emerson (1903–59).]

emetic 1 having the power to cause vomiting. **2** any compound with emetic properties.

emetine 6′,7′,10,11-tetramethoxyemetan; an alkaloid from *Cephaelis ipecacuanha* that is a gastrointestinal irritant and potent emetic and used as an expectorant and antiamoebic agent. It inhibits protein synthesis by preventing translocation of peptidyl-tRNA from the A- to the P-site on the ribosome.



emf *or* **EMF** *abbr. for* electromotive force.

emg *abbr. for* electromyogram.

+emia *or (esp. Brit.)* **+aemia** *suffix* denoting blood, especially some abnormal condition of the blood.

emilin *abbr. for* elastin microfibril interface located protein; an extracellular matrix glycoprotein, gp115. It is a component of elastin fibres, preferentially located at the elastin–microfibril interface.

emiocytosis a process whereby a secretory substance is released from a cell; a form of **exocytosis**. A secretory granule moves to the cell surface, where the membrane sac enclosing the granule fuses with the plasma membrane, ruptures, and liberates the granule into the extracellular space.

emission *(in physics)* the release of energy in the form of radiation or particles.

emission spectrophotometry *or* **emission photometry** the processes of measuring an **emission spectrum**, either photometrically or photographically.

emission spectroscopy the **spectroscopy** of an **emission spectrum**. This differs from emission spectrophotometry in being a generic term. Thus measurement may be photometric or photographic, for example.

emission spectrum any **spectrum** of emitted electromagnetic radiation produced by a sample after its atoms or molecules have been put into excited states by the absorption of energy, each line in the emission spectrum being produced by the decay of a particular species of excited atom or molecule to some lower energy level. The exciting energy may be supplied as heat, bombardment by particles, or irradiation with other electromagnetic radiation. *Compare* **absorption spectrum**, **excitation spectrum**.

EMIT *abbr. and trademark for* enzyme-multiplied immunoassay technique; *see* **homogeneous enzyme immunoassay**.

emodin 1,3,8-trihydroxy-6-methylanthraquinone; a compound found (as its rhamnoside) in rhubarb root and other plants.



eMOTIF *see* **derived database**.

EMPIGEN BB *proprietary name for* **dodecyl-*N,N*-dimethylglycine**.

EMR *abbr. for* **1** equi-effective molarity concentration ratio. **2** *or* **emr** electromagnetic radiation.

EMSA *abbr. for* electrophoretic mobility shift assay.

emu *or* EMU *abbr. for* electromagnetic unit.

emulsifier **1** *an alternative name for* **emulsifying agent**. **2** a machine for making emulsions.

emulsify to form or to convert into an **emulsion**. —**emulsifiable** *or* **emulsible** *adj.*; **emulsification** *n.*

emulsifying agent *or* **emulsifier** any amphiphile or surfactant, such as a phospholipid or a soap, small quantities of which promote the formation of, and stabilize, an **emulsion**.

emulsin a ferment (i.e. an enzyme preparation) obtained from sweet or bitter almonds and originally studied in 1837 by the German chemists Justus von Liebig (1803–73) and Friedrich Wöhler (1800–82) for its ability to degrade **amygdalin**. Together with invertin, it played an important role in Fischer's work on enzyme specificity leading to his **lock and key model**. In modern terms, it was an enzyme mixture containing mainly *β*-glucosidase activity (EC 3.2.1.21).

emulsion **1** a temporary or permanent dispersion of an oil or other hydrophobic material in an aqueous solution, or vice versa, forming an **oil-in-water emulsion** or a **water-in-oil emulsion** respectively. **2** *short for* **photographic emulsion**.

EMX2 one of several homeodomain proteins that are expressed in forebrain neurons and are important in brain regionalization. Mutations in the gene at 10q26 lead to the inherited epilepsy syndrome designated **schizencephaly**.

en+ *or (sometimes before b, m, and p)* **em+** *prefix* **1** *(forming verbs)* put in or into, e.g. encapsulate, encode; surround or cover with, e.g. enmesh; to make into a certain condition, e.g. enrich. **2** *(forming nouns and adjectives)* in, into, e.g. endemic.

enabled a protein of *Drosophila* that suppresses the gene for D-Abl (i.e. Abelson protein tyrosine kinase).

ENaC *abbr. for* epithelial Na channel; a trimer of similar subunits, each of which has two transmembrane segments and intracellular N- and C- termini. The C-terminal tails of the β and γ subunits bind Nedd-4 with great affinity. Mutations that eliminate the C-terminal tail of β or γ subunits result in Liddle syndrome.

enalapril (*S*)-1-[*N*-[1-(ethoxycarbonyl)-3-phenylpropyl]-L-alanyl]-L-proline; an inhibitor of **angiotensin converting enzyme** (ACE) and a valuable antihypertensive drug. It has the advantage over **captopril** that it is more easily absorbed and has fewer side effects, and also that enalaprilate, to which it is converted after absorption by removal of the ethyl ester group, is a much more potent ACE inhibitor than captopril. ACE inhibitors were developed from compounds such as succinylproline, an early inhibitor. Conversion of the free succinyl carboxyl group to a sulfhydryl, and addition of a methyl group, yielded captopril with greatly enhanced binding properties. In enalaprilate there was addition of further binding affinity by a phenylethyl group, restoration of carboxyl in place of sulfhydryl and introduction of a secondary amino group. These drugs lower angiotensin II levels which lowers blood pressure, both because of a reduction in direct action of angiotensin as a vasoconstrictor and also by reducing its actions in stimulating aldosterone and norepinephrine release, both of these latter substances having hypertensive effects.



enamel the hard, white, calcified material that forms the outer covering of the crown of a tooth.

enamilin *see* **tuftelin**.

enamine *or* **alkenylamine** any organic molecule having the general structure $R^1R^2NCR^3{=}CR^4R^5$ (where the R groups may be any hydrocarbyl group or H, and the same or different).

enanthate *see* **heptanoate**.

enantiomer either of a pair of **stereoisomers** whose molecules as a whole display **chirality**, i.e. are mirror images of each other and thus not superposable. They are sometimes referred to as optical isomers or optical antipodes; these terms are not recommended. *See also* **enantiomorph** (def. 2), **racemate** (def. 1). *Compare* **diastereoisomer**.

enantiomeric of, or pertaining to, an **enantiomer**; pertaining to the phenomenon of, or displaying **enantiomerism**. Chiral groups that are mirror images of one another are termed **enantiomeric groups**. *See also* **enantiomorphic**, **racemic**.

enantiomeric purity a measure of the proportion of one enantiomer in an enantiomeric mixture expressed as either a fraction or a percentage. *Distinguish from* **optical purity**.

enantiomerism the phenomenon of the existence of **enantiomers** in general, or the existence of enantiomeric molecules in a particular instance; it includes **optical isomerism**.

enantiomorph **1** either of two objects, especially crystals, that are mirror images of each other and thus are not superposable. **2** either of the two crystalline forms exhibited by a pair of enantiomers. Use of the term to mean **enantiomer** is deprecated.

enantiomorphic *or* **enantiomorphous** of, or pertaining to, an **enantiomorph**; pertaining to the phenomenon of, or displaying **enantiomorphism**. The term is often used synonymously with **enantiomeric** (enantiomeric molecules frequently form enantiomorphic crystals).

enantiomorphism the phenomenon of being related as between an object and its nonsuperposable mirror image. The term is used especially in relation to enantiomorphic crystals.

enantiomorphous *see* **enantiomorphic**.

enantiotopic **1** when chemically-like ligands in constitutionally equivalent locations (generally the two *a* ligands in C*aabc*) are related by a centre or plane of symmetry, or by an alternating axis of symmetry (but not by a simple axis of symmetry), they are enantiotopic. The two ligands are in a stereochemically different, mirror-image environment. If each *a* ligand of C*aabc* is replaced separately by a different, achiral ligand, *d*, the products are the two enantiomers of C*abcd*. Example: the methylene hydrogens of ethanol are enantiotopic; if ethanol is written as a Fischer projection structure with OH at the top, H–C–H in the middle, and CH_3 at the bottom, the left-hand hydrogen of the central methylene is H_S , while that at the right is H_R (*see* ***pro-R*/*pro-S* convention**). Replacement of ^1H_R by ^2H yields (+)-(*R*)-[1-$^2H_1$]ethanol and the same replacement of ^1H_S yields the enantiomer, (–)-(*S*)-[1-$^2H_1$]ethanol. In another important compound, citric acid, the two CH_2COOH groups are also enantiotopic. **2** the two faces of a double bond or of a planar cyclic ring system that are related by a symmetry plane but not by a C_2 axis (i.e., a two-fold axis of symmetry) are enantiotopic; the two faces show stereochemically different, mirror-image related environments. Separate addition of the same achiral reagent to the two faces (*see* ***Re*/*Si* convention**) gives enantiomeric products. Example: the simple addition of HCN to CH_3–CHO yields a racemic mixture of the (*R*) and (*S*) cyanohydrins, CH_3–CH(OH)–CN, with both faces of C=O being involved. The reduction of the C=O bond of CH_3–CHO to form ethanol by alcohol dehydrogenase requires addition of a hydride ion from NADH at the C atom and a hydron at the O atom. Thus, reduction of CH_3–CHO with NAD^{2}H at its *A* face (*see* **diastereotopic** (def. 2)) yields (*R*)-[1-$^2H_1$]ethanol and reduction of CH_3–C^2HO with *A*-NADH yields (*S*)-[1-$^2H_1$]ethanol. The enzymatic reduction is stereospecific and only one of the enantiotopic faces of C=O is attacked; it is the same one (the *Re* face) in both of these situations. *Compare* **diastereotopic**.

encapsidate to surround (a particle of viral nucleic acid) with a **capsid**. —**encapsidation** *n.*

encapsis the association of myofibrils into bundles and the further association of these bundles into larger bundles, etc.

encephalin *a variant spelling of* **enkephalin**.

encephalitis inflammation of the brain.

encephalomyocarditis virus a cardiovirus in the family Picornaviridae that is pathogenic in pigs.

3′ end the end of a linear polynucleotide strand at which the 3′-hydroxyl group of the terminal nucleoside residue is normally not phosphorylated.

5′ end the end of a linear polynucleotide strand at which the 5′-hydroxyl group of the terminal nucleoside residue is normally phosphorylated.

end+ *a variant form of* **endo+** *(sometimes before a vowel).*

endA an *Escherichia coli* gene encoding endonuclease A, an enzyme that digests plasmid DNA. Strains of *E. coli* lacking this enzyme consequently give higher yields and better quality plasmids.

end capping *(in chromatography)* the blocking of residual silanol groups on the surface of silica where these remain exposed after the bonding of C_{18} or other alkyl chains to the silica in the formation of reversed-phase stationary phases for column chromatography. For this purpose hydrocarbyl silanes (*see* **silane** (def. 3)) having small alkyl (usually methyl) groups are used so that they can penetrate between the main bonded-phase groups.

endemic present in or peculiar to a more or less localized area, e.g. an endemic disease. *Compare* **enzootic**.

endergonic describing a process or reaction on which work must be done, i.e. one requiring an energy input, for it to take place. At constant pressure and temperature the free energy content of such a system increases. *Compare* **exergonic**. [From **endo+** plus Greek *ergon*, work.]

end group any residue at an extremity of a branched or linear macromolecule.

end-group analysis determination of both the nature and the number of terminal groups in a macromolecule, e.g. in proteins, the N- and C-terminal amino-acid residues; in polynucleotides, the 3′- and 5′-terminal nucleotide residues.

end labelling the introduction of a radiolabelled molecule such as ^{32}P at the end of a DNA chain by an enzyme such as **polynucleotide kinase**. Alternatively a deoxynucleotide labelled with a fluorescent dye can be introduced using **terminal deoxynucleotidyltransferase**.

endo+ *or (sometimes before a vowel)* **end+** *comb. form* meaning within, inner, absorbing, containing. *Compare* **exo+**. *See also* **intra+**.

endo- *prefix (in chemical nomenclature)* denoting insertion (of the additional constituent(s) specified) into the structure of (a named compound); e.g. endo-4a-glycine-[5-leucine]enkephalin; endo-Gly^{4a}-[Leu^5]enkephalin; Tyr-Gly-Gly-Phe-Gly-Leu; a synthetic polypeptide in which a glycine residue has been inserted between residues 4 and 5 of [5-leucine]enkephalin.

endo- *prefix (in stereochemistry). See* **conformation**.

endoamylase any **amylase** that hydrolyses nonterminal glycosidic linkages; it is a subcategory of **endoglycosidase**.

endocannabinoid any endogenous compound that binds a **cannabinoid receptor**, such as anandamide and 2-arachidonylglycerol. In the brain these function as retrograde synaptic messengers and may affect memory, cognition, and pain perception by suppressing neurotransmitter release. They are degraded by intracellular enzymes.

endocrine **1** describing or relating to any gland or other group of cells that synthesizes **hormones** and secretes them directly into the blood, lymph, or other intercellular fluid. **2** describing or relating to a secretion of endocrine tissue. **3** a secretory product of endocrine tissue; a hormone. Originally known as **internal secretion**. *Compare* **exocrine**.

endocrine gland *or* **ductless gland** any of the ductless glandular structures that secrete (one or more) hormones directly into the bloodstream.

endocrinology the science concerned with the endocrine organs, their products, and the effects of these products. — **endocrinological** *adj.*

endocytic **1** situated within a living cell but not belonging to the cell itself; intracellular. **2** *an alternative term for* endocytotic (*see* **endocytosis**).

endocytosis the uptake of external materials by cells through the mechanism of **phagocytosis** or **pinocytosis**. The term is often used interchangeably with pinocytosis. *Compare* **exocytosis**, **transcytosis**. *See also* **internalize**, **viropexis**. —**endocytic** *or* **endocytotic** *adj.*; **endocytose** *vb.*

endocytotic vesicle *see* **pinocytotic vesicle**.

endodeoxyribonuclease *see* **deoxyribonuclease**.

endoenzyme **1** any intracellular enzyme. *Compare* **ectoenzyme**, **exoenzyme** (def. 1). **2** any enzyme that catalyses **endohydrolysis**. It may be an **endoglycosidase**, an **endonuclease**, or an **endopeptidase**. *Compare* **exoenzyme** (def. 2).

endogenous arising or developing within an organism, tissue, or cell, and excluding any consequences of externally added agents or materials. —**endogenously** *adv.*

endoglin a major glycoprotein of vascular endothelium that may be important in the binding of endothelial cells to integrins. It forms a heteromeric complex with the signalling receptors for transforming growth factor β (TGF-β). It has an **RGD** integrin-recognition motif, and is a homodimer of disulfide-linked subunits.

endoglycosidase any enzyme within subclass EC 3.2, glycosidases, that hydrolyses nonterminal glycosidic linkages in oligo- or polysaccharides. Many activities of this type are known, e.g. from *Flavobacterium meningosepticum*.

endohormone any hormone acting within the individual organism that produces it. *Compare* **ectohormone**.

endohydrolysis the hydrolysis, esp. by an **endoenzyme**, of any linkage between residues in a biopolymer. For example, **endopeptidases** attack neither the C-terminal nor the N-terminal peptide linkages of an oligo- or polypeptide, and **endoglycosidases** attack the terminal glycosidic linkages at either the reducing or nonreducing end of an oligo- or polysaccharide.

endolyn-78 a glycoprotein, M_r 78 000, present in substantial amounts in membranes of endosomes and lysosomes, but occurring only at low levels in plasma membrane and peripheral tubular endosomal compartment.

endolysins phage-encoded peptidoglycan-degrading enzymes that affect some bacterial cell walls. Access to the peptidoglycan layer is made possible by one or more of the **holins**.

endomembrane system a hypothetical integrated membrane system of eukaryotic cells, proposed by Morré and Mollenhauer, that represents a developmental and functional continuum. It comprises the endoplasmic reticulum, nucleus, Golgi apparatus and vesicles, plasmalemma, tonoplast, and outer membranes, but not the inner membranes of the mitochondria and chloroplasts.

endometrium the mucous membrane that lines the uterus. It becomes progressively thicker and more glandular in the later stages of the estrous (menstrual) cycle, which prepares it for embryo implantation. If pregnancy occurs the endometrium becomes the decidua, which is shed after birth. If pregnancy does not occur the endometrium returns to its original state; in primates, including humans, much of the endometrium breaks down and is lost in menstruation. —**endometrial** *adj.*

endomitosis the replication of chromosomes without cellular or nuclear division. It is a form of polyploidization that is fairly common in differentiated or differentiating tissues. It is characterized by an increase in nuclear DNA content.

endonuclease any enzyme of a large group of phosphoric diester hydrolases, forming sub-subclasses EC 3.1.21–31, that catalyses the hydrolysis of nonterminal diester linkages in polynucleotides to yield oligonucleotides. Examples include certain of the **deoxyribonucleases** and **ribonucleases**. *Compare* **exonuclease**. *See also* **restriction endonuclease**.

endopeptidase *or* **endoproteinase** *or (formerly)* **proteinase** any enzyme within subclass EC 3.4, peptide hydrolases, that hydrolyses nonterminal peptide linkages in oligopeptides or polypeptides, and comprising any enzyme of sub-subclasses EC 3.4.21–99. They are classified according to the presence of essential catalytic residues or ions at their active sites. Four distinct sub-subclasses are: (1) serine proteinases (EC 3.4.21); (2) cysteine proteinases (EC 3.4.22); (3) aspartic proteinases (EC 3.4.23), and (4) metalloproteinases (EC 3.4.24). There are two major families of serine proteinases, the **chymotrypsins** and the **subtilisins**. Aspartic proteinases contain two aspartic residues at their active site. The metalloproteinases contain metal ions, usually zinc. The proteinases can be distinguished by inhibitors, which are usually specific for a particular class or type.

endopeptidase La the enzyme EC 3.4.21.53; *other names*: ATP-dependent serine proteinase; ATP-dependent protease La; a serine proteinase that catalyses the hydrolysis of large proteins such as globin, casein, and denatured serum albumin in the presence of ATP. It is seemingly the sole member of its own superfamily.

endoperoxide a cyclic peroxide formed from a long-chain polyunsaturated fatty acid, especially arachidonic acid, through the action of **prostaglandin-endoperoxide synthase**.

endoplasm the inner, relatively fluid, part of the **cytoplasm**. *Compare* **ectoplasm**. **—endoplasmic** *adj.*

endoplasmic reticulum *abbr.*: ER; the irregular network of unit membranes, visible only by electron microscopy, that occurs in the cytoplasm of many eukaryotic cells. The membranes form a complex meshwork of tubular channels, which are often expanded into slitlike cavities called **cisternae**. The ER may be rough (or granular), with ribosomes adhering to the outer surface, or smooth (with no ribosomes attached). When cells are disrupted by homogenization, the cisternae break up into small closed vesicles called rough **microsomes** or smooth microsomes. The ribosomes attached to the rough ER are the site of translation of the mRNA for those proteins which are to be retained within the cisternae (**ER-resident proteins**), targeted to the **lysosomes**, or destined for export from the cell. Glycoproteins undergo their initial glycosylation within the cisternae. The smooth ER is the recipient of the proteins synthesized in the rough ER. Those proteins to be exported are passed to the Golgi complex (*see* **Golgi apparatus**), the resident proteins are retained in the rough ER, and the lysosomal proteins after phosphorylation of their **mannose** residues are passed to the lysosomes. Glycosylation of the glycoproteins also continues. The smooth ER is the site of synthesis of lipids, including the phospholipids. The major membrane phospholipids are phosphatidylcholines, phosphatidylethanolamines, phosphatidylserines, and sphingomyelins. The ER also produces cholesterol, triacylglycerols, eicosanoids, and ceramides, and contains enzymes that catalyse reactions to detoxify lipid-soluble drugs and harmful products of metabolism. Large quantities of certain compounds such as phenobarbital cause an increase in the amount of the smooth ER.

endoproteinase *or (formerly)* **proteinase** *an alternative name for* **endopeptidase**.

ENDOR *abbr. for* electron nuclear double resonance.

endorphin any endogenous peptide with morphine-like activity. The term includes the pentapeptide **enkephalins**, and the peptides of the pituitary gland, including α-endorphin, which has the structure Tyr-Gly-Gly-Phe-Met-Thr-Ser-Glu-Lys-Ser-Gln-Thr-Pro-Leu-Val-Thr; γ-endorphin consists of α-endorphin with an additional Leu at the C terminus; β-endorphin consists of α-endorphin with -Leu-Phe-Lys-Asn-Ala-Ile-Ile-Lys-Asn-Ala-His-Lys-Lys-Gly-Gln-OH at the C terminus. Endorphins have the same N-terminal tetrapeptide sequence as the enkephalins. Preproopiomelanocortin is the precursor of β-endorphin, both in brain and other tissues, and [Met^5]enkephalin; preprodynorphin (preproenkephalin B) is the precursor of dynorphin; [Leu^5]enkephalin is formed from preproopiomelanocortin and from preproenkephalin A. Tissue endorphins are larger polypeptides (about 7 kDa) found in pancreas, placenta, and adrenal medulla. *Compare* **exorphin**. [From endo(genous) + morphine.]

endo-*α*-sialidase EC 3.2.1.129; *other names*: endo-*N*-acetylneuraminidase; endoneuraminidase; poly(α-2,8-sialosyl) endo-*N*-acetylneuraminidase; an enzyme that catalyses the endohydrolysis of *α*-2,8-sialosyl linkages in oligo- or poly(sialic) acids.

endoskeleton any skeleton lying within an organism, such as the axial skeleton of vertebrates. *Compare* **exoskeleton**.

endosmosis the osmotic flow of water or of an aqueous solution into a cell, organism, or vessel from a surrounding aqueous medium. *Compare* **exosmosis**. **—endosmotic** *adj.*

endosome a membrane-bound organelle in animal cells that carries materials newly ingested by **endocytosis**. It passes many of the materials to lysosomes for degradation.

endosperm the nutritive tissue, found in the seeds of most angiosperms, that surrounds and nourishes the embryo.

endosperm albumin the proteins occurring in the endosperm of, e.g., barley; *see* **protein Z**.

endospore 1 an asexual spore formed within a cell, especially one produced by some bacteria and algae. **2** *or* **endosporium** the innermost coat of the wall of a spore or pollen grain.

endostatin a monomeric (≈20 kDA) cleavage product that consists of the C-terminal domain of either of the two endostatin-forming **collagens** (types XV and XVII), which are expressed only in endothelial cells. They are the most potent inhibitors of angiogenesis and of endothelial cell migration. On binding to a specific receptor endostatin activates a protein tyrosine kinase and causes expression of specific genes.

endosymbiont a partner in a symbiotic relationship that penetrates the tissues or cells of the other partner; e.g. any of the nitrogen-fixing species of bacteria that occur in the root nodules of legumes. *See* **symbiosis**. *Compare* **ectosymbiont**.

endosymbiotic infection an infection of cells by viruses that replicate without cytopathic effect.

endothelial leukocyte adhesion molecule *abbr.*: ELAM; *another name for* **selectin**.

endothelin *abbr.*: ET; any one of three 21-residue peptides, called endothelins 1, 2, and 3 (*abbr.*: ET-1, ET-2, ET-3). Endothelins 2 and 3 are homologous with ET-1, which is known to be made by the endothelial cell. ET-1 is the most potent vasopressor known, being ten times more potent than angiotensin II. They have disulfide bonds, between cysteine residues 1 and 15, and 3 and 11; these hold the structure in a conical spiral shape. The amino-acid sequence of ET-1 is bicyclic(1→15, 3→11) [Cys^1-Ser-Cys^3-Ser-Ser-Leu-Met-Asp-Lys-Glu-Cys^{11}-Val-Tyr-Phe-Cys^{15}-His-Leu-Asp-Ile-Ile-Trp]; ET-2 differs in having -Trp-Leu- at positions 6,7; ET-3 has the substitutions (position in parentheses) Thr(2), Phe(4), Thr(5), Tyr(6), Lys(7), and Tyr(14). The endothelins are products of different genes, and are synthesized as part of a large precursor molecule, **preproendothelin** (prepro-ET), which is then proteolytically processed. The 2.2 kb mRNA for human prepro-ET-1 is encoded in five exons, the 5′-flanking region containing response elements for phorbol ester (Fos/Jun-inducible) and nuclear factor 1 (TGF-β-induced expression; *see* **transforming growth factor**), and its expression is stimulated by vasopressor hormones such as epinephrine, angiotensin II, and arginine vasopressin, as well as TGF-β (from aggregating platelets), thrombin, and interleukin-1. Prepro-ET-1 is a 203-residue peptide, which is cleaved to the 92-residue pro-ET (**big endothelin**), from which ET-1 is formed by **endothelin converting enzyme**. Related peptides are **vasoactive intestinal contractor** and **sarafotoxin**, a peptide produced by *Atractaspsis engaddensis*. Only ET-1 is detected in vascular endothelial cells; it is also expressed in nonvascular cells in other tissues, including brain, kidney, and lung. ET-2 and ET-3 are expressed in tissues such as brain, kidney, adrenal, and intestine. Mutations in the ET-3 gene occur in some patients with Hirschsprung disease.

endothelin receptor any of several membrane proteins that bind **endothelins** and mediate their intracellular effects. They are G-protein-coupled receptors. ET$_A$ (human, 427 amino acids) has affinity

ET-1 > ET-2 >> ET-3, while ET_B (human, 442 amino acids) is equipotent for all three. Loss-of-function mutations in the endothelin receptor B gene occur in Waardenburg syndrome with Hirschsprung disease.

endothelium the single layer of thin, flattened cells of mesoblastic origin that lines the blood vessels and some body cavities, e.g. those of the heart. *Compare* **epithelium**, **mesothelium**. **—endothelial** *adj.*

endothelium-derived relaxing factor *abbr*.: EDRF; *see* **nitric oxide**.

endothermic describing a process or reaction that absorbs heat, i.e. a process or reaction for which the change in enthalpy, ΔH, is positive at constant pressure and temperature. *Compare* **exothermic**.

endothiapepsin EC 3.4.23.22; *other name*: *Endothia* aspartyl protease. An enzyme, similar to other aspartic proteases, that catalyses the hydrolysis of proteins with broad specificity similar to that of **pepsin** A; it prefers hydrophobic residues at P1 and P1′, but does not cleave the Ala–Leu linkage in the B chain of insulin, or the protected dipeptide Cbz-Glu-Tyr; it clots milk.

endotoxin any microbial toxin that cannot easily be separated from the structure of the cell. *Compare* **exotoxin**.

end point *or* **endpoint** the point in a titration that should (but may not always) correspond to the theoretical **equivalence point**.

end product the final chemical substance formed in a sequence of metabolic (or chemical) reactions.

end-product inhibition the inhibition of a sequence of metabolic reactions by the end product of the sequence, usually by action on a reaction which is often at the beginning of the sequence.

end-window counter a **Geiger counter** or **proportional counter** so constructed that its base is relatively transparent to the radiation to be detected.

+ene *suffix (in chemical nomenclature)* indicating the presence of one or more carbon–carbon double bonds in an organic compound.

enediol any acyclic organic compound in which there is a hydroxyl group attached to each of two carbon atoms that are linked by a double bond. *Compare* **enol**.

energy *symbol*: *E*; the capacity of a system for doing work. There are various forms of energy – potential, kinetic, electrical, chemical, nuclear, and radiant – which can be interconverted by suitable means. The SI unit of energy is the joule.

energy balance the algebraic balance of the various energy inputs versus energy outputs of a system; it is positive if energy is released and negative if it is absorbed. In physiology it is the relation of the amount of energy taken into the organism to the amount used for internal work, external work, and for the growth and repair of tissues.

energy barrier *see* **potential energy barrier**.

energy charge *see* **adenylate energy charge**.

energy coupling the coupling of ATP synthesis to electron transport in the **respiratory chain**.

energy diagram a diagram representing the energy contents of various states of the reactants, activated complexes, and products in a chemical reaction; or of the nuclear energy levels of an atom; or of the electronic energy levels of an atom or molecule.

energy flow *(in ecology)* the transfer of energy between organisms in an ecosystem.

energy level any of the stable energy states that a molecular entity can take up. In **quantum mechanics** only certain discrete energy levels are possible and continuous variation of the energy level of a molecular entity is excluded.

energy metabolism the metabolic reactions of a cell or organism concerned with energy transformations.

energy of activation *see* **activation energy**.

energy-poor *term sometimes used to describe* **1** a compound whose hydrolysis under standard conditions manifests a small negative free energy change. *See also* **low-energy compound**. **2** a chemical group with a low **group potential**. **3** the linkage of such a chemical group to some other group.

energy requirement the amount of energy needed to maintain a cell or organism.

energy sink a molecule or a group in a molecule that is able easily to accept energy transferred to it from another component of the system.

energy transduction *see* **transduction** (def. 2).

energy transfer the transfer of excitation energy from one chromophore or one molecular entity to another by a process not involving radiation; the energy may then be dissipated in a variety of ways, e.g. by fluorescence. Such energy transfer is very dependent on the distances involved and is useful in studies of structural relationships between groups on a macromolecule.

energy trapping the processes by which energy released in a catabolic reaction is coupled to the synthesis of another compound, often a nucleoside triphosphate such as ATP.

engineered **1** (of a cell or organism, or a strain of cells or organisms) *colloquial term for* **genetically engineered**. **2** (of a nucleotide sequence) *jargon term, usually followed by 'into'* artificially inserted (into a longer sequence, such as a vector). **3** (of a protein) *jargon term* describing an altered protein synthesized by a cell or organism (or a strain of cells or organisms) whose genetic material has been manipulated to that end.

engrailed any of various protein products of the **homeotic gene** *engrailed*; in *Drosophila,* this is a segment-polarity gene.

enhanced chemiluminescence *abbr*.: ECL; an increased intensity of light output for a greatly extended period in chemiluminescence reactions involving the peroxidase-catalysed oxidation of luminol. The effect is achieved by the addition of molecules such as 6-hydroxybenzothiazole.

enhanced green fluorescent protein *abbr*.: EGFP; a modified form of green fluorescent protein (GFP) in which the λ_{max} excitation is shifted to 488 nm making it more suitable for analysis by flow cytometry. The λ_{max} emission is unchanged at 509 nm.

enhanced yellow fluorescent protein *abbr*.: EYFP; a proprietary green-yellow variant of green fluorescent protein (GFP) optimized for brighter fluorescence, and higher expression, in mammalian cells. It has λ_{max} excitation 513 nm and λ_{max} emission 527 nm.

enhancement **1** the improvement of the effects of ionizing radiation on tissue by dioxygen or other chemical agents. **2** the increased yield of one virus from cells infected by another virus; the term is often used when the mechanism of the process is not known. *Compare* **complementation** (def. 2), **interference**. **3** *see* **Emerson enhancement**. **4** *see* **fluorescence enhancement**.

enhancement of fluorescence *an alternative term for* **fluorescence enhancement**.

enhancement spectrum a spectrum showing the enhancement of photosynthetic **quantum yield** from that produced at a fixed-wavelength background illumination to that produced by illumination with a variable-wavelength beam. Such spectra show peaks that can sometimes be reasonably well identified with specific pigments in the system. *Compare* **Emerson enhancement**.

enhanceosome a protein complex that forms on an enhancer site of DNA and influences the rate of transcription at a promoter, which may be thousands of base pairs away. For example, that for the interferon β gene in mammals contains high-mobility group protein 1 (HMG1) and recruits two histone acetyl transferases, which acetylate core histones on neighbouring nucleosomes and also HMG1 of the complex. Another example is the disclike structure formed by a 180 bp loop of DNA and dimers of the *Xenopus* transcription factor xUBF. This is involved in rRNA transcription.

enhancer *(in molecular biology)* a eukaryotic control element that can increase the expression of a gene when transcription factors are bound to it. Enhancers may be located thousands of base pairs from the gene and may be either upstream, downstream, or in the gene itself.

enhancer trap vector a vector designed to identify genes expressed during development. It consists of a linear DNA molecule in which the *lacZ* reporter gene is placed under the control of a weak eukaryotic promoter and alongside a **dominant selectable marker** such as neo^R under the control of its own strong promoter. In mice, for example, random integration of the vector into the genome of ES cells allows clones of recombinants expressing neo^R to be isolated. These in turn can be used to create mosaic animals in which reporter activity is expressed if integration is, fortuitously, close to an enhancer. DNA from the region of integration can be cloned thereby allowing identification of the enhancer that is active during development. *Compare* **gene trap vector**.

enkephalin any pentapeptide **endorphin** with the sequence Tyr-Gly-Gly-Phe-Xaa. There are two similar naturally occurring enkephalins, present in brain, spinal cord, and gut; their recommended trivial names are: [5-leucine]enkephalin (*abbr*.: [Leu^5]enkephalin *or* [Leu]enkephalin), Tyr-Gly-Gly-Phe-Leu (I); and [5-methionine]enkephalin (*abbr*.: [Met^5]enkephalin *or* [Met]enkephalin), Tyr-Gly-Gly-Phe-Met (II). (II has the same sequence as residues 61–65 of β-**lipotropin**.) The common precursor of I and II, proenkephalin – itself formed from preproenkephalin by removal of the signal peptide – contains four copies of II and one each of I, the heptapeptide [Met^5]enkephalinyl-Arg-Phe, and the octapeptide [Met^5]enkephalinyl-Arg-Phe-Leu. (*Note*: Designations such as Leu-, leucyl-, or leucine-enkephalin have commonly been given to I, with corresponding terms for II, but all of these incorrectly imply N-terminal extension with a residue of leucine or methionine, respectively.)

enkephalinase *see* **carboxypeptidase H**.

enkephalin convertase a specific carboxypeptidase that converts enkephalin precursors into enkephalin in adrenal chromaffin granules. It is now known as **carboxypeptidase H**.

enniatin any of various antibiotics from *Fusarium* spp. that function as **ionophores**. They are cyclodepsipeptides (*see* **depsipeptide**).

enol any acyclic organic compound with a hydroxyl group attached to either of two carbon atoms that are linked by a double bond. *Compare* **enediol**. *See also* **keto–enol tautomerism**.

enolase EC 4.2.1.11; *recommended name*: phosphopyruvate hydratase; *other name*: 2-phosphoglycerate dehydratase. A cytosolic enzyme that catalyses the conversion of 2-phospho-D-glycerate to phospho*enol*pyruvate and H_2O; magnesium is a cofactor. There are three isoenzymes in human tissues: α2 is ubiquitous; β2 is in skeletal muscle; and γ3 is in the nervous system. A rare deficiency in which enolase activity is ≈50% of normal in erythrocytes may be accompanied by hemolytic anemia.

enology *or (esp. Brit.)* **oenology** the study of wines.

5-enolpyruvylshikimate-3-phosphate phospholyase *see* **chorismate synthase**.

eNOS *see* **nitric-oxide synthase**.

enoyl an acyl group derived from any alkenoic acid.

enoyl-[acyl-carrier protein] reductase (NADPH, A-specific) EC 1.3.1.39; *other name*: acyl-ACP dehydrogenase; an enzyme of the **fatty acid synthase complex** in liver. It catalyses the reduction by NADPH of *trans*-2,3-dehydroacyl-[acyl-carrier protein] to form acyl-[acyl-carrier protein] and $NADP^+$.

enoyl-CoA hydratase **1** EC 4.2.1.17; *systematic name*: (3*S*)-3-hydroxyacyl-CoA hydro-lyase; *other names*: enoyl hydrase, unsaturated acyl-CoA hydratase; an enzyme of the **beta-oxidation system**, present in mitochondria and peroxisomes. It catalyses the hydration of (3*S*)-3-hydroxyacyl-CoA to *trans*-2(or 3)-enoyl-CoA. It is a mitochondrial matrix protein, a homohexamer; a characteristic transit peptide sequence is found in the precursor. **2** EC 4.2.1.74; *recommended name*: long-chain-enoyl-CoA hydratase; an enzyme that catalyses a similar reaction to the above; it does not act on crotonoyl-CoA. *See also* **beta-oxidation system**.

enoyl-CoA isomerase *see* **dodecenoyl-CoA** Δ**-isomerase**.

3,2-*trans*-enoyl-CoA isomerase *see* **dodecenoyl-CoA** Δ**-isomerase**.

enrich to increase in content or abundance; e.g. to increase the abundance of one (usually stable) nuclide of an element above its naturally occurring level; to increase the content in a foodstuff of one or more specific nutrients (such as vitamins or minerals) above the natural level. —**enrichment** *n.*

enrichment medium a selective culture medium that favours the growth of a desired microorganism.

Ensembl *see* **genome annotation software**.

entactic describing an enzyme poised for catalytic action in the absence of substrate.

entactin *or* **nidogen** a sulfated Ca^{2+}-binding protein occurring in basement membrane, and involved in cell adhesion; it binds **laminin** and type IV collagen. The protein has two globular domains, an **EF-hand** domain, EGF-like domains, and a thyroglobulin type I domain.

enteric *or* **enteral** of or pertaining to the intestine or gut.

enteric-coated describing a drug or medicament that is prepared in a form enabling it to pass through the stomach unaltered and be released in the intestine.

entero+ *or (before a vowel)* **enter+** *comb. form* denoting the intestine.

enterobactin *or* **enterochelin** *N′*,*N′*,*N″*-tris(2,3-dihydroxybenzoyl)-2,6,10-trioxo-1,5,9-trioxacyclododecane-3,7,11-triamine; a **siderochrome** of the catechol-derivative variety produced by certain members of the Enterobacteriaceae, e.g. *Escherichia coli*, *Salmonella* spp. It is the cyclic self-triester (trilactide) of *N*-(2,3-dihydroxybenzoyl)-L-serine, and a product of the **shikimate pathway**.

enterochelin *an alternative name for* **enterobactin**.

enterochromaffin cell *abbr.*: EC cell; any gut endocrine cell containing biogenic monoamines that gives a positive **chromaffin** reaction and displays a characteristic yellow formaldehyde-induced fluorescence. Such cells may be divided immunocytochemically and ultrastructurally into functionally distinct types.

enterocrinin a putative peptide hormone, crystallizable from extracts of intestine of certain mammals, that is held to stimulate duodenal and jejunal secretion of digestive enzymes.

enterocyte any of the columnar epithelial cells on the luminal surface of the villi of the small intestine. Enterocytes are immature in the crypts, mature in the middle of the villi, and senile at the exfoliation area at the villous tips. They have numerous microvilli on their luminal surface (the brush border) and are responsible for the synthesis of digestive enzymes and for the absorption of materials from the gut.

enterogastrone the putative hormone from the duodenum that inhibits gastric activity. Some or all of the actions attributed to enterogastrone are probably due to **glucose-dependent insulinotropic peptide**.

enterogastrone effect *see* **gastric inhibitory peptide**.

enteroglucagon **1** a collective term for a small family of polypeptides derived from **proglucagon** by post-translational processing in the L cells (or **EG cells**) of the distal small intestine and colon. One component is GLP-$1^{7–37}$ (*see* **GLIP**). **2** *or* **glucagon-37** *or* **oxyntomodulin** a polypeptide isolated from porcine jejuno-ileum that binds glucagon receptors and activates adenylate cyclase in hepatocytes. It specifically inhibits gastric acid secretion. Its N-terminal 29 residues (of a total of 37) are identical to those of glucagon.

enterohepatic recirculation the cycle of secretion from the gall bladder into the upper intestinal tract with reabsorption in the lower tract and transport to the liver followed by resecretion. *See* **bile acids**.

entero-insular axis the interrelationship of endocrine function between the gastrointestinal tract and the pancreatic islets in which signals arising in the gut after ingestion of nutrients effect endocrine responses by the islets.

enterokinase *a former name for* **enteropeptidase**.

enteropeptidase *or (formerly)* **enterokinase** the enzyme EC 3.4.21.9; a serine proteinase enzyme of the brush border of the upper small intestine that activates **trypsinogen** by the selective cleavage of the Lys^6-|-Ile^7 bond in the latter. The bovine protein consists of 1035 amino acids; residues 1–800 form the non-catalytic heavy chain, and residues 801–1035 the catalytic light chain. *See* **duodenase**.

enterostatin a pentapeptide generated by tryptic hydrolysis of procolipase in the intestinal lumen. It has the sequence APGPR in human, and VPDPR in pig, horse, and rat. It decreases fat intake and secretion of insulin and pancreatic enzymes in rodents. It has been found in rodent serum and brain.

enterotoxin any bacterial **exotoxin**, whether ingested or produced within the intestine, that has an action upon the intestinal mucosa, usually giving rise to diarrhoea and other unpleasant symptoms. **Cholera toxin** is an example. Other enterotoxins are produced by *Escherichia coli* and some Staphylococci. Of the *E. coli* enterotoxins, LT (from labile, i.e. heat-labile, toxin) is similar in structure to cholera toxin and has a similar mode of action. ST (from heat-stable toxin) has an effect similar to atrial **natriuretic peptide**, activating guanylate cyclase. It has 13 amino acids. Other enterotoxins produced by *E. coli* include **hemolysin** and vero toxin, a Shiga-like toxin similar to that of *Shigella dysenteriae* that has *N*-glycosidase activity, and cleaves an adenine residue from the 28S rRNA of the 60S ribosome subunit.

enthalpimetry the measurement of the **enthalpy** of a body or system.

enthalpy *or* **heat content** *symbol*: H; a physical quantity and a thermodynamic property defined as the sum of the internal energy of a system, U and the product of the volume, V, multiplied by the pressure, p, i.e. $H = U + pV$. Enthalpy is related to the **Gibbs energy**, G, by the equation $G = H - TS$, where T denotes the thermodynamic temperature and S denotes **entropy**.

Entner–Doudoroff enzyme the 'catabolic' D-glucose-6-phosphate dehydrogenase (EC 1.1.1.49) from *Pseudomonas fluorescens*. It is a 220 kDa protein composed of four, apparently identical, polypeptide chains. *See also* **Entner–Doudoroff pathway**.

Entner–Doudoroff pathway a metabolic pathway occurring in *Pseudomonas* spp. in which D-glucose 6-phosphate is first oxidized to 6-phospho-D-gluconate, which is then acted on by 6-phosphogluconate dehydratase (EC 4.2.1.12) to form 2-dehydro-3-deoxy-6-phospho-D-gluconate. This is then split by 2-dehydro-3-deoxyphosphogluconate aldolase (EC 4.1.2.14) to give pyruvate and D-glyceraldehyde 3-phosphate. [After Nathan Entner (1920–) and Michael Doudoroff (1911–).]

entomology the science of the study of insects.

entopic occurring in the usual place. *Compare* **ectopic**.

Entrez *see* **information retrieval software**.

entropic union a polymerization, or other reaction, resulting from an energetically unfavourable interaction of a surface of the molecule in question with water molecules; the polymerization causes the removal of water from the molecules' surfaces and a hence a decrease in the free energy content of the system.

entropy *symbol*: S; a physical quantity and a thermodynamic property indicating the amount of disorder in a system; i.e. the amount of energy in a system that is unavailable for doing work. In any irreversible process the total entropy of all systems concerned is increased. In a reversible process the total increase in entropy in all systems concerned is zero, while the increase in entropy, dS, of any individual system, or part of a system, is equal to the heat that it absorbs, dq_{rev}, divided by the thermodynamic temperature, T; i.e. $dS = dq_{rev}/T$. Entropy is related to **Gibbs energy**, G, and **enthalpy**, H, by the equation $G = H - TS$. The SI unit for entropy is JK^{-1} —**entropic** *adj.*

entry exclusion the phenomenon in which a resident plasmid interferes with the entry of genetic material to a cell by (bacterial) **conjugation** (def. 4).

enucleate 1 to remove the nucleus from (a cell). **2** (of a cell) deprived of its nucleus. —**enucleation** *n.*

ENU mutagenesis *abbr. for* *N*-ethyl-*N*-nitrosourea mutagenesis; ENU is an alkylating agent and powerful mutagen used to induce mutations in living organisms. AT base pairs are predominantly modified and a high proportion of the mutations are missense.

enuresis the involuntary passing of urine. —**enuretic** *adj.*

env a viral gene for **envelope protein**.

envelope 1 any covering or enclosing structure, e.g. a membrane, capsule, shell, or skin. **2** the cell membrane of a bacterium, together with all the structures external to it including the cell wall and, sometimes, the capsule. **3** *or* **peplos** an outer lipoprotein coat of a virion that occurs in an **enveloped virus**. **4** *see* **nuclear envelope**.

envelope conformation any **conformation** of a nonplanar five-membered saturated ring compound when four of its ring atoms lie in one plane and the remaining atom lies outside that plane. For a monosaccharide or monosaccharide derivative the conformational descriptor -*E* may be added to its name.

enveloped virus any virus in which a nucleoprotein core is surrounded by a lipoprotein envelope consisting of a closed bilayer of lipid derived from that of the host cell's membrane(s), with glycoprotein on the outside and matrix protein or nucleocapsid protein on the inside. Enveloped viruses include herpesviruses, negative-strand RNA viruses, retroviruses, and togaviruses.

envelope protein any protein (usually a glycoprotein) of the envelope of a virus. Example: envelope polyprotein gp160 precursor of human immunodeficiency virus (HIV) type 1: residues 1–29 are the signal peptide; 30–509 form exterior membrane glycoprotein gp120; 510–855 form transmembrane glycoprotein gp41. The variable (very rapidly evolving) antigenic regions of HIV are in the gp120 sequence.

envelysin EC 3.4.24.12; *other names*: sea-urchin-hatching proteinase; hatching enzyme; an enzyme so named because it dissolves (lyses) the fertilization envelope of the sea-urchin embryo. It is a metalloendopeptidase that catalyses the preferential cleavage of proteins on the amino side of bulky hydrophobic residues, Leu, Ile, Phe, and Tyr. The enzyme requires zinc and calcium.

envoplakin a precursor (2033 amino acids) of the crosslinked protein (called cornified envelope) present under the plasma membrane of keratinocytes. It is closely related to plectin, desmoplakin, and bullous pemphigoid antigen.

Enzacryl *the proprietary name for* a group of synthetic carriers for the immobilization of enzymes and other organic biomolecules that are copolymers of acrylamide and various derivatives of *N*,*N*′-methylene diacrylamide.

enzootic present in or peculiar to animals in a more or less localized area; e.g. an enzootic disease. *Compare* **endemic**.

enzymatic *an alternative term for* **enzymic**.

enzyme any naturally occurring or synthetic macromolecular substance composed of protein, that catalyses, more or less specifically, one or more (bio)chemical reactions at relatively low temperatures. RNA that has catalytic activity (*see* **ribozyme**) is often regarded as enzymic. The substances upon which enzymes act are known as **substrates**, for which the enzyme possesses a specific binding or **active site**. *See also* **enzyme classification**, **isoenzyme**. [From German *enzym*, possibly from modern Greek *enzumos*, leavened, or more probably from Greek *en*, in, + *zum ē*, leaven, yeast.] —**enzymic** *or* **enzymatic** *adj.*

enzyme I EC 2.7.3.9; enzyme I of the **phosphotransferase** system; phospho*enol*pyruvate–protein phosphotransferase; *systematic name*: phospho*enol*pyruvate:protein-L-histidine N^{π}-phosphotransferase. A soluble bacterial enzyme, part of a system for the transport of hexoses across the cell membrane, that catalyses the phosphorylation by phospho*enol*pyruvate of a low M_r, heat-stable protein, **HPr**. *Compare* **enzyme II** (def. 1).

enzyme II 1 EC 2.7.1.69; enzyme II of the **phosphotransferase** system; protein-N^{π}-phosphohistidine–sugar phosphotransferase; *systematic name*: protein-N^{π}-phosphohistidine:sugar N^{π}-phosphotransferase. Any of a group of related membrane-bound bacterial enzymes, part of the system for the transport of hexoses across the cell membrane, that catalyse the phosphorylation of hexoses by phospho-HPr (*see* **enzyme I**). Enzyme II is responsible for the specificity of the transport process with respect to the sugar. **2** *a former name for* **acyl-carrier protein**.

enzyme-activated irreversible inhibitor *an alternative name for* **suicide inhibitor**.

enzyme activation the generation of a catalytically active enzyme from an inactive or poorly active form or from a biosynthetic precursor (proenzyme). Activation may be by enzymic or chemical covalent modification or by addition of a specific activator.

enzyme adaptation *see* **inducible enzyme**.

enzyme cascade *see* **cascade sequence**.

enzyme classification the systematic arrangement and naming of enzymes by the **Enzyme Commission**. The basis of the classification is the reaction classified; enzymes that catalyze the same reaction but have different genetic origins, protein structure, and cofactors, are generally all given the same EC number. Each enzyme is denoted by the abbreviation EC followed by a set of four numbers separated by stops. The first number denotes one of the six main divisions: EC 1, oxidoreductases; EC 2, transferases; EC 3, hydrolases; EC 4, lyases; EC 5, isomerases; and EC 6, ligases. The second number denotes the subclass, the third number denotes the sub-subclass; the fourth number is the serial number of the particular enzyme. The most recent edition of the classification at

http://www.cehm.qmul.ac.uk/iubmb.enzyme

lists approximately 4000 enzymes.

enzyme cluster *or (sometimes)* **multienzyme cluster 1** any physiologically significant system of two or more enzymes in physical (i.e. noncovalent) association. The term embraces any **enzyme complex**,

multienzyme complex, or membrane-bound enzyme array. Clustered enzymes usually display different kinetic and/or regulatory features from their unassociated counterparts; they may be encoded in a cluster-gene. *See also* **multienzyme system**. **2** *an alternative term for* **cluster** (def. 2).

Enzyme Commission *or* **the International Commission on Enzymes** a body established in 1956 by the International Union of Biochemistry (IUB) to consider the classification and nomenclature of enzymes and coenzymes, their units of activity and standard methods of assay, together with the symbols used in the description of enzyme kinetics. The Commission, which worked closely with the Biological Chemistry Nomenclature Commission of the International Union of Pure and Applied Chemistry (IUPAC), was dissolved in 1961 and its work has been carried on in turn by the Standing Committee on Enzymes of IUB, by the IUPAC/IUB Joint Commission on Biochemical Nomenclature (JCBN), by an Expert Committee on Enzymes, and most recently by the Nomenclature Committees of IUB (NC-IUB) or the International Union of Biochemistry and Molecular Biology (NC-IUBMB). *See also* **enzyme classification**.

enzyme complex an operational term for any structural and functional entity composed of a number of dissociable enzymes that catalyse a sequence of closely related chemical reactions. *Compare* **multienzyme**.

enzyme detergent any detergent preparation incorporating an enzyme to assist its cleansing action. The enzymes used in such detergents are usually proteinases of high thermal and alkaline stability, e.g. **Alcalase**.

enzyme differentiation the process whereby, during the development of an organism, each tissue acquires its own characteristic quantitative pattern of enzymes, which underlies the physiological functions and morphological features of the tissue. From a fairly uniform enzymic make-up in the cells of the early embryo, the enzyme patterns of different tissues become progressively more differentiated as development into the mature organism proceeds.

enzyme electrode any electrode, incorporating an enzyme into its structure, that responds to the concentration of one of the substrates or products of the reaction catalysed by the enzyme. The enzyme is trapped within a gel matrix surrounding the electrode or is kept in contact with the electrode by a semipermeable membrane.

enzyme engineering *or* **enzyme technology** the branch of biomolecular engineering concerned with processes designed to produce, isolate, purify, and immobilize enzymes and to use them for the catalysis of specific chemical reactions.

enzyme immunoassay *or* **enzymoimmunoassay** *abbr*.: EIA; any **immunoassay** in which an enzyme-catalysed reaction is used as the indicator. *See also* **heterogeneous immunoassay**, **homogeneous immunoassay**.

enzyme induction the synthesis of an enzyme in a cell or organism at a markedly increased rate in response to the presence of an **inducer**. The inducer is thought to combine with a **repressor** thereby preventing the latter from blocking an **operator**, which controls the translation of the structural gene for the enzyme.

enzyme-inhibition immunoassay a variation of **enzyme immunoassay** in which the inhibition of an enzyme-catalysed reaction is used as the indicator.

enzyme labelling a method used to detect or locate (and sometimes estimate) an antigen in, e.g., a tissue section. The section is exposed to a complementary antibody that has been covalently linked to an enzyme; the antibody binds to the antigen, and its location (and its amount) is determined by an assay dependent on the catalytic activity of the linked enzyme. *See also* **enzyme immunoassay**.

enzyme-linked immunosorbent assay *abbr*.: ELISA; a form of quantitative **immunoassay** based on the use of antibodies (or antigens) that are linked to an insoluble carrier surface, which is then used to 'capture' the relevant antigen (or antibody) in the test solution. The antigen–antibody complex is then detected by measuring the activity of an appropriate enzyme that had previously been covalently attached to the antigen (or antibody).

enzyme membrane any (semipermeable) membrane to which an enzyme has been covalently bound. Such membranes are useful in constructing **enzyme electrodes**.

enzyme-multiplied immunoassay technique *abbr. and proprietary name*: EMIT; *an alternative name for* **homogeneous enzyme immunoassay**.

enzyme-paper graft an enzyme immobilized on (filter) paper, which is frequently impregnated with indicators. It is useful for making analytical devices.

enzyme reactor a device for using immobilized enzymes or enzyme systems for synthetic or other processing reactions, especially on an industrial scale.

enzyme recruitment the exploitation of substrate-ambiguous enzymes or transport proteins in the evolution of new biochemical pathways.

enzyme repression inhibition of the formation of an enzyme by a compound formed in or taken in by a cell or organism.

enzyme specificity *see* **specificity**.

enzyme–substrate complex *abbr*.: ES; the stoichiometric complex of an enzyme molecule and a substrate molecule bound at the enzyme's active site.

enzyme technology *an alternative term for* **enzyme engineering**.

enzyme unit *symbol*: U; *abbr*.: EU; a unit of activity of enzymes, defined as the amount of enzyme that will catalyse the transformation of one micromole of the substrate per minute under standard conditions. It is not recommended, having been superseded by the **katal**, but is still widely used: 1 kat = 6 × 10^7u; 1u = 16.7 nkat.

enzymic *or* **enzymatic** by, of, involving, or relating to an enzyme or enzymes; catalysed by an enzyme or by enzymes. —**enzymically** *or* **enzymatically** *adv.*

enzymic activity the rate of reaction of substrate that may be attributed to catalysis by an enzyme. The concept is now obsolete, having been superseded by **catalytic activity**. The unit of enzymic activity was initially the **enzyme unit** and subsequently the **katal** (as originally defined). The derived quantity concentration of enzymic activity was defined as activity divided by volume and was expressed as katals per litre. *See also* **catalytic activity concentration**, **molar (enzymic) activity**, **specific (enzymic) activity**.

enzymic cycling a form of **catalytic assay** in which there is no coupled indicator reaction; instead, the regenerating system is allowed to cycle for a set time, after which the reactions are stopped by destruction of all enzymes and the most easily determined product is measured in a separate assay. The coupled system thus acts as a chemical amplifier in the determination of the intermediate catalyst.

enzymo+ *comb. form* denoting an **enzyme** or enzymic activity.

enzymoimmunoassay *an alternative name for* **enzyme immunoassay**.

enzymology the science of the study of enzymes and enzyme-catalysed reactions. —**enzymological** *adj.*; **enzymologist** *n.*

enzymolysis the enzyme-catalysed splitting of a chemical compound into smaller ones. The term commonly refers to enzymic hydrolysis. —**enzymolytic** *adj.*

eobiogenesis the first occurrence of the formation of living matter from nonliving material.

eobiont any system showing some characteristics of living systems but not enough to be generally accepted as living.

eosin any of a number of similar red acidic dyes, derivatives of fluorescein, especially Eosin Y (yellowish), 2′,4′,5′,7′-tetrabromofluorescein disodium salt, Acid Red 87 (CI 45380), or Eosin B (bluish), 4′,5′-dibromo-2′,7′-dinitrofluorescein disodium salt, Acid Red 91 (CI 45400). They are widely used as stains in histology and hematology.



2′,4′,5′,7′-tetrabromofluorescein

eosinophil(e) **1** *or* **eosinophil leukocyte** *or* **eosinophilic leukocyte** a polymorphonuclear leukocyte, present in blood and other connective tissues, that has numerous large cytoplasmic granules that stain readily with eosin. The granules contain numerous hydrolytic enzymes including acid phosphatase, arylsulfatase, cathepsins, glucuronidase, peroxidase, and ribonuclease. The relative number of eosinophils in the blood, normally low, rises markedly in certain allergic conditions and parasitic infections but their function is poorly understood. **2** any cell whose cytoplasm stains readily with eosin, especially an eosinophilic cell of the anterior pituitary that secretes prolactin and somatotropin.

eosinophil cationic protein *abbr*.: ECP; a highly basic zinc-containing **ribonuclease** that binds avidly to negatively charged surfaces and is particularly effective at damaging the tegument of schistosomes.

eosinophilic having an affinity for **eosin**.

eosinotactic having an attractive or repulsive action on eosinophils. [A contraction of eosinophil + chemotactic.]

eosome the suggested primary particulate biogenetic precursor, via the **neosome**, of the **ribosome**. Eosomes of *Escherichia coli* have an average sedimentation coefficient of 14S.

eotaxin any chemokine that attracts eosinophils. An eotaxin receptor is present only in these leukocytes.

EPA *abbr. for* **1** eicosapentaenoic acid. Normally indicating the (all-*Z*)-5,8,11,14,17 isomer. **2** erythroid potentiating activity (*see* **TIMP**).

EpETrE *abbr. for* epoxyeicosatrienoate.

EPH a gene encoding a subfamily of protein tyrosine kinases. It is named from erythropoietin-producing hepatocellular carcinoma cell line, from which the probe used to isolate the gene was obtained. Related proteins are Elk (Eph-like kinase), Eek (Eph and Elk-related kinase), Eck (epithelial cell kinase), and Erk (Elk-related kinase). Overexpressed *Eph* has tumorigenic potential; the ligand of Eph is unknown.

ephedrine (1*R*,2*S*)-1-phenyl-1-hydroxy-2-methylaminopropane; an alkaloid obtained from several species of gymnosperm shrubs belonging to the genus *Ephedra*. A structural analogue of epinephrine, it mimics central and peripheral effects of noradrenergic and adrenergic neurons through direct and indirect actions, hence its CNS-stimulant effects and its use as a decongestant in upper respiratory tract infections.



ephexin a guanine nucleotide exchange factor (GEF) regulated by the **ephrin** class A receptors.

ephrin any axon guidance protein that is a membrane-bound ligand (analogous to the semaphorins) for the Eph family of receptor tyrosine kinases (*see* ***EPH***). Ephrins regulate cell migration, axon guidance, regionalization in the nervous system, and morphogenesis. Mammals produce 8 ephrins and 14 Eph receptors. Class A ephrins are GPI-anchored and bind Eph A receptors. Class B ephrins have one transmembrane segment, bind Eph B receptors in the nervous system, are important in development, and influence synapse assembly.

epi+ *or (before a vowel)* **ep+** *prefix* denoting **1** on, upon, above, over, beside, near, close to, in addition to. **2** a chemical compound or group related in some way to a specified chemical compound or group, e.g. an **epimer**. **3** a chemical compound or group distinguished from a specified chemical compound or group by having a bridge connection in the molecule, e.g. an **epoxide**.

epiallele any of two or more genetically identical alleles that are epigenetically distinct owing to methylation. –**epiallelic** *adj.*

epiarginase *see* **epiprotein**.

epichlorohydrin 3-chloropropylene oxide; chloromethyloxirane; 1-chloro-2,3-epoxypropane; a colourless liquid widely used in industry as a solvent and an intermediate in the manufacture of glycerol, glycerol ethers and epoxy resins. In the presence of potassium hydroxide it reacts with compounds containing alcoholic hydroxyl groups to form diethers of glycerol and hence finds application in the manufacture of cross-linked derivatives of polysaccharides such as the proprietary materials sephacel, sephadex, and sepharose.

epidemic **1** describing a disease that affects many persons simultaneously in a more or less restricted area. **2** the widespread occurrence of a disease in a human population. *Compare* **endemic**.

epidemiology the study of the nature and spread of a disease in a human population.

epidermal growth factor *abbr*.: EGF; any member of a group of heat-stable, hormonal, ≈6 kDa proteins that consist of a single polypeptide chain of 49–53 residues with three intrachain disulfide bonds; they are classified as **cytokines**. One form (mEGF), the tooth-lid factor, can be isolated from submaxillary glands of the male mouse (*see* **nerve growth factor**). A similar protein (hEGF), extracted from human pregnancy urine and named **urogastrone**, is highly homologous to EGF (37 of 53 residues identical, disulfide bonds preserved). EGF *in vivo* stimulates the growth of epidermal and epithelial cells, and inhibits the secretion of gastric acid. It also has a potent mitogenic action on many types of cultured mammalian cells and displays a number of insulin-like properties towards them (*see* **insulin-related growth factors**). It is synthesized as a large preprotein, EGF membrane glycoprotein precursor, which contains, as well as the mature EGF protein, nine EGF-like repeats and urogastrone. Many proteins have one or more EGF-like sequence repeats. The action of EGF is mediated by the **epidermal growth factor receptor**.

epidermal growth factor receptor *or* **EGF receptor** the mediator of the biological signal of **epidermal growth factor** (EGF) and also of **transforming growth factor-α** (TGF-α). It is a membrane protein with a single transmembrane domain, and a **tyrosine kinase** activity in the cytoplasmic domain; the extracellular domain, which binds EGF, is highly glycosylated. The v-*erbB* oncogene codes for a protein highly homologous to a truncated EGF receptor, and the gene for the receptor is the protooncogene c-*erbB* (*see* ***erbB***). Binding of EGF leads to the induction of tyrosine kinase activity, formation of dimers, and autophosphorylation; stimulation of cell DNA synthesis and cell proliferation follows. Internalization of the EGF–receptor complex leads to its degradation in lysosomes.

epidermis the outermost layer of cells of an animal or plant. —**epidermal** *adj.*

epienzymatic control a form of control of arginine metabolism, occurring in some *Saccharomyces* spp., in which arginases bind stoichiometrically to ornithine carbamoyltransferase (EC 2.1.3.3), inhibiting the latter's activity but without substantially modifying the arginase activity. *See also* **epiprotein**.

epigenesis the concept that an organism develops from an originally undifferentiated mass of living material through the appearance of structures and functions not originally present.

epigenetic describing any of the mechanisms regulating the expression and interaction of genes, particularly during the development process. These include changes that influence the phenotype but have arisen as a result of mechanisms such as inherited patterns of DNA methylation rather than differences in gene sequence: **imprinting** is an example of this.

epigenetics the study of factors that influence gene expression but do not alter genotype, such as chromatin methylation and acetylation involved in tissue-specific patterns of gene expression, or the parental imprinting of genes.

epigenomics a genomic approach to studying environmental or developmental epigenetic effects, primarily DNA methylation, on gene function. Thus, epigenomics focuses on those genes whose function is determined by external factors.

epiligrin an extracellular matrix protein, secreted by cultured epidermal keratinocytes. It is found in epithelial basement membranes, but not membranes of endothelia, nor in muscle or nerve cells. It is a ligand for cell adhesion via **integrins**, with three chains linked by disulfide bonds, and is also an adhesive ligand for T lymphocytes. *See also* **laminin**.

Epilim *a proprietary name for* sodium valproate (*see* **valproic acid**).

epimer *(in stereochemistry)* either of two **diastereoisomers** that differ in configuration at only one chiral centre. The term includes **anomer**.

epimerase any enzyme within subclass EC 5.1, that catalyses **epimerization** (note that subclass EC 5.1 also includes **racemases**). Some epimerases, e.g. UDParabinose 4-epimerase (EC 5.1.3.5), contain tightly bound NAD, which undergoes oxidation and reduction during the reaction.

epimeric of or relating to an epimer or the chiral centre that specifies an epimer.

epimerization *or* **epimerisation** the process of converting an epimer into its diastereoisomer by altering the configuration at the epimeric chiral centre. —**epimerize** or **epimerise** *vb.*

epimino+ *an alternative term for* **imino+** (def. 2).

epinephrine *or* **adrenaline** (–)-1-(3,4-dihydroxyphenyl)-2-(methylamino)ethanol; a hormone secreted by the adrenal medulla and a neurotransmitter secreted by neurons in the brainstem. It is synthesized by the methylation of **norepinephrine**. It is an agonist for **adrenoceptors**, through which it has powerful glycogenolytic and lipolytic effects (both of which are mediated by cyclic AMP) and also affects the activity of smooth muscle (notably of the cardiovascular system and bronchi) and glandular tissue. Its mode of action critically depends on whether it acts through α or β adrenoceptors. Chromaffinoma of the adrenal medulla or other chromaffin tissue is a rare cause of intermittent hypertension and other signs of catecholamine excess. The hormone was named adrenalin by Takamine in 1901.



epinephrine

epiphase the upper, less dense layer of a two-phase system. *Compare* **hypophase**. —**epiphasic** *adj.*

epiplasm a membrane skeleton of certain protists, that contributes to cell shape and patterning of the species-specific cortical architecture. This cytoskeleton contains proteins known as **articulins**.

epiprotein a specific protein, produced in certain circumstances in some *Saccharomyces cerevisiae* strains, that binds stoichiometrically to ornithine carbamoyltransferase (EC 2.1.3.3), thereby inhibiting its activity. It has subsequently been shown to have arginase activity and so is sometimes known as **epiarginase**. *See also* **epienzymatic control**.

episemantic molecule any molecule that is synthesized under the control of a tertiary **semantide**. All molecules built by enzymes in the absence of a template are included because, although they do not express extensively the information contained in the semantide, they are a product of this information. *See also* **asemantic molecule**.

episome 1 a genetic element that is sometimes found in cells, especially those of bacteria, and that can replicate either when integrated into or independently of the host chromosome. **2** any fragment of DNA that exists in a cell as an extrachromosomal element. This DNA may or may not be replicated and passed to daughter cells. The **plasmid** is an example of an episome. DNA elements that use transposases involved in phage lambda integration are also examples of episomes.

epistasis the interaction between two or more genes at different loci such that phenotypic expression of one depends on expression of another. For example, a mutation preventing an early step in a biochemical pathway is epistatic to a mutation that prevents a step later in the pathway, because mutation of the first gene would mask expression of the second gene. –**epistatic** *adj.* –**epistatically** *adv.*

epitempin a protein of unknown function that is produced mainly in brain and other nervous tissue. It contains three leucine-rich repeats in the N-terminal region and seven specific repeats in the C-terminal region. Mutations in the gene at 10q24 produce an autosomal dominant form of familial lateral temporal epilepsy.

epithelium 1 *(in animal anatomy)* a sheet of closely packed cells, arranged in one or more layers, that covers the outer surfaces of the body or lines any internal cavity or tube (except the blood vessels, heart, and serous cavities). *Compare* **endothelium**, **mesothelium**. **2** *(in plant anatomy)* any of certain layers of parenchymal cells that line an internal cavity or tube. — **epithelial** *adj.*

epithin a type II transmembrane serine protease of mouse that is the orthologue of human **MT-SP1**.

epitope any immunological determinant group of an antigen. —**epitopic** *adj.*

epitope tagging the practice of adding an epitope to the N- or C-terminus of proteins expressed in prokaryotic or eukaryotic cells. Antibodies to epitope tags such as 6xHis or c-myc can then be used to detect the intracellular location of the expressed protein, or to purify it and any other proteins that might be bound to it in immunoprecipitation experiments.

epitype any class or group of related epitopes.

EPO *abbr.* for **erythropoetin**

epoprostenol *international nonproprietary name for* prostaglandin I_2; *see* **prostacyclin**.

epothilone *see* **taxol**.

epoxidation the formation of an **epoxide** by addition of an oxygen atom as a bridge across the double bond of an alkene.

epoxide any compound where molecules contain an epoxy group attached to adjacent carbon atoms to form a saturated three-membered ring system.

epoxy+ *prefix (in chemical nomenclature)* indicating the presence in a molecule of an oxygen atom directly attached (by single covalent bonds) to two (adjacent or nonadjacent) carbon atoms of a carbon chain or ring system. Epoxy compounds are cyclic ethers.

epoxyeicosatrienoate *abbr.*: EpETrE *or (formerly)* EET; any of various metabolites of arachidonate that contain an epoxy group. They are formed by the action of cytochrome P450 – this occurs in numerous tissues and has a high degree of stereospecificity. The products are predominantly present esterified to membrane-bound phosphatidylcholine. They have a wide spectrum of biological activities, including stimulation of peptide hormone release, inhibition of Na^+,K^+-ATPase, mobilization of microsomal Ca^{2+}, and inhibition of prostaglandin-endoperoxide synthase. Examples are (all-*Z*)-5*S*,6*R*-epoxyeicosa-8,11,14-trien-1-oate and (all-*Z*)-11*S*,12*R*-epoxyeicosa-5,8,14-trien-1-oate. EpETrEs can be further metabolized to *vic*-diols, diepoxides, and other products.



(all-*Z*)-5*S*,6*R*-epoxyeicosa-8,11,14-trien-1-oate



(all-*Z*)-11*S*,12*R*-epoxyeicosa-5,8,14-trien-1-oate

epoxy resin *or* **epoxide resin** any of a class of synthetic resins, containing ether linkages and epoxy groups, formed by the copolymerization of an epoxide (e.g. 1-chloro-2,3-epoxypropane) and a polyphenol (e.g. 2,2-bis(4-hydroxyphenyl)propane). When mixed with certain accelerators, e.g. an amine or an anhydride, such resins produce hard, clear, resistant, thermosetting polymers that are used as adhesives and coatings and for embedding materials for microscopy, especially electron microscopy.

Eppendorf pipette any of a range of push-button, plunger-operated, precalibrated, dispensing micropipettes with disposable polypropylene tips. [After the name of the manufacturer.]

Eppendorf tube the first polypropylene microcentrifuge tube, introduced by the company that became Eppendorf AG.

EPPS *an alternative name for* **Hepps**.

EPR *or* **epr** *abbr. for* electron paramagnetic resonance spectroscopy.

epsilon *symbol*: ε (lower case) *or* E (upper case); the fifth letter of the Greek alphabet. For uses *see* **Appendix A**.

epsilon chain *or* **ε chain** the **heavy chain** of IgE **immunoglobulin** molecules.

epsin a protein involved in vesicle budding in the plasma membrane. It binds to clathrin, synaptojanin, and adaptor protein-2.

EPSP *abbr. for* 5-*enol*pyruvylshikimate phosphate; an intermediate in aromatic amino-acid biosynthesis by the shikimate pathway (*see* **shikimate**).

EPSP synthase *an alternative name for* **3-phosphoshikimate 1-carboxyvinyltransferase**. *See also* **shikimate**.

Epstein–Barr virus human (gamma) herpesvirus 4; a DNA virus, first isolated from specimens of tumour tissue obtained from African children affected by Burkitt's lymphoma, that causes infectious mononucleosis (glandular fever) in young adult humans. [After (Sir) Michael Anthony Epstein (1921–), British pathologist and immunologist, and Yvonne M. Barr.]

eq. *or* **Eq.** *abbr. for* equivalent (def. 4).

equation of state any equation connecting the pressure, volume, and temperature of a substance or a mixture.

equatorial 1 of, relating to, or being an equator; located at or near an equator. *Compare* **axial** (def. 1). **2** *(in stereochemistry) symbol*: e; *see* **conformation**.

equi+ *comb. form* denoting equal or equality.

equi-effective dose ratio *abbr*.: EDR; the ratio of the doses of test and reference substances that produce the same biological effect (whether activation or inhibition).

equi-effective molarity ratio *abbr*.: EMR; the ratio of the molarity of test and reference substances that produce the same biological effect (whether activation or inhibition).

equilenin *the trivial name for* 3-hydroxyestra-1,3,5,7,9-pentaen-17-one; a weakly estrogenic steroid hormone isolated from the urine of pregnant mares. *Compare* **equilin**.



equilibrate to bring to equilibrium, or cause (something) to be in equilibrium (with some other thing), especially with the environment or with a (specified) system. **—equilibration** *n.*

equilibrium 1 a state of balance between or among opposing forces or processes that results in the absence of net change. **2** *(in chemistry)* a state of dynamic balance in a reversible chemical reaction when the reaction velocities in both directions are equal.

equilibrium assay a type of **radioimmunoassay** in which the reagents used are allowed to reach thermodynamic equilibrium. *Compare* **disequilibrium assay**.

equilibrium constant *symbol*: *K*; an expression of the position of the **equilibrium** (def. 2) of a reversible chemical reaction under specified physical conditions (e.g. temperature, pressure, nature of solvent, ionic strength, etc.). For a reaction of the generalized form:

$$aA + bB + ... \rightleftharpoons mM + nN + ...$$

when the thermodynamic **activity** of each of the components A, B, M, N, etc. is written as (A), (B), (M), (N), etc., and *a*, *b*, *m*, *n*, etc. are the respective numbers of molecular entities participating in the reaction, the equilibrium constant is given by:

$$K = [(M)^m (N)^n ...]/[(A)^a (B)^b ...]$$

Frequently in biochemical systems it is not possible to evaluate the activities of all the components; the **concentration equilibrium constant** (*symbol*: K_a) rather than the true or **thermodynamic equilibrium constant** is then calculated, *K* being expressed in terms of the molarities of each of the components in place of their activities. When the specified concentration of a component includes more than one chemical species (e.g. ionized plus un-ionized forms, or chelated plus unchelated metal ion) in unknown proportions, an **apparent (concentration) equilibrium constant** (*symbol*: K') constrained with respect to certain variables (e.g. pH, or total concentration of metal ion), is written. *See also* **affinity constant**, **association constant**, **dissociation constant**, **p*K***.

equilibrium density-gradient centrifugation a method for the separation of cells, cell organelles, macromolecules, or other particles of different densities by centrifugation in a solution that increases in solute concentration, and hence in density, from the top to the bottom of the centrifuge tube. At equilibrium, particles of the same density are found as a band or zone in the density gradient. *Compare* **differential centrifugation**.

equilibrium dialysis a technique used to measure the binding of a **microsolute** or ions to a **macrosolute**. A solution of the macrosolute is placed inside a dialysis bag (through which the macromolecules will not pass); this represents phase α. The bag is suspended in a solution containing the microsolute (phase β). At equilibrium, any excess concentration of the microsolute in phase α is taken as evidence for binding. From a measurement of the excess concentration of the microsolute and knowledge of the concentration of the macrosolute the extent of the binding may be determined.

equilin *the trivial name for* 3-hydroxyestra-1,3,5(10),7-tetraen-17-one; a weakly estrogenic steroid hormone isolated from the urine of pregnant mares. *Compare* **equilenin**.

equimolar of equal **molarity**.

equimolecular containing equal numbers of molecular entities.

equinatoxin a pore-forming toxin, permitting passage of small molecules across membranes. It is produced by the sea anemone *Actinia tenebrosa*; it contains 150–250 amino acid residues. Equinatoxin is classified in the TC system under number 1.C.38.

equine of, relating to, or being a member of the family Equidae (horses, zebras, and asses); of, belonging to, characteristic of, obtained from, or relating to, a horse or horses; resembling a horse.

equiv. *abbr. for* equivalent (def. 3).

equivalence 1 the state of being equal, equivalent, or interchangeable. **2** **equivalency**. **3** the point or zone in a precipitin test at which antigen and antibody are present in optimal proportions for combination and precipitation.

equivalence factor *symbol* (for a chemical species X): $f_{eq}(X)$; a number pertaining to a given reacting component of a specified titrimetric reaction derived from consideration of the overall stoichiometry of the reaction. For a reaction of the following type: $\nu A + \nu B \rightarrow$ products, where νA and νB are the respective numbers of reacting entities, then the equivalence factor of species B is given by: $f_{eq}(B) = \nu B/\nu A$. When $\nu A > \nu B$ and $f_{eq}(A)$ is taken as unity, then $f_{eq}(B)$ is unity or less than unity. In the case of a reaction that can be clearly identified as acid–base or oxidation–reduction, the equivalence factor must be related to one entity of titratable hydrons or of transferable electrons, respectively.

equivalence point *or* **stoichiometric point** *or* **theoretical end point** the point in a titration at which the amount of titrant added is chemically equivalent to the amount of substance titrated.

equivalency *or* **equivalence** 1 the state of having equal valencies. **2** the state of having equal **equivalence factors**.

equivalent 1 equal or interchangeable in amount, importance, meaning, or value. **2** *(in chemistry)* having equal valencies. **3** something that is equivalent (to something else). **4** *(in chemistry)* **a** *abbr*.: equiv. *or* eq. *or* Eq.; a unit of amount of substance, defined as the entity of a chemical species that in a specified reaction would combine with, displace, or in any other appropriate way be equivalent to, one entity of titratable hydrons (in an acid–base reaction) or one entity of electrons (in an oxidation–reduction reaction). It is the arithmetic product of the **molar mass** of the chemical species and its **equivalence factor**. **b** *(formerly)* **equivalent weight**.

equivalent activity a measure of the radiation output of a real radiation source containing a particular radionuclide, defined as being equal to the **activity** (def. 1b) of a hypothetical point source of the same radionuclide that would give the same exposure rate at the same distance from the centre of the source. It is customarily used to express the strengths of most sources emitting high-energy gamma radiation.

equivalent ellipsoid of rotation the **ellipsoid of rotation** having the same volume as an actual hydrodynamic unit of a macromolecule in solution (which consists of the macromolecule and tightly bound solvent).

equivalent weight *abbr.*: equiv. wt.; an obsolete term defined as the weight in grams of an element, compound, or group that, in a specified reaction, will combine with or displace 8 grams of oxygen, or the equivalent weight of another chemical species. *See also* **equivalent** (def. 4).

ER *abbr. for* endoplasmic reticulum.

ERAD *abbr. for* ER-associated degradation; the process by which many structurally flawed proteins and orphan subunits are restricted from traversing the entire secretory pathway through the endoplasmic reticulum. Such proteins are degraded by proteasomes in the cytosol.

ER-associated degradation *see* **ERAD**.

erbA an oncogene (v-*erbA*) originally found in avian erythroblastosis virus; the corresponding protooncogene (c-*erbA*) encodes thyroid hormone receptor. The product of v-*erbA* requires the activity of other oncogenic agents for tumorigenesis. *See also* ***erbB***.

erbB an oncogene (v-*erbB*) from avian erythroblastosis virus; the corresponding protooncogene (c-*erbB*) encodes the **epidermal growth factor receptor**. In tumours the extracellular ligand-binding domain is deleted, contributing to a system with a constitutively active receptor protein. The transforming protein from the virus is a polyprotein product from *gag*, *erbA*, and *erbB*. erbB is a family of highly homologous genes that become oncogenic due to gene amplification or overexpression of the mRNA. Of the products, erbB1 is the epidermal growth factor receptor; erbB2 is also called HER2 (*abbr. for* heregulin receptor 2)/neu; and erbB3 and erbB4 are also called Her3 and HER4, respectively. erbB1 and erbB2 are overexpressed (probably from gene amplification) in 20–40% of breast cancers, and erbB2 in ≈10% of stomach cancers. erbB4, on glial cell surfaces, interacts with neuregulin and participates in glial-mediated neuronal migration. In mice, loss of any of these four genes results in embryonal death and defects in brain, heart, lung, and gastrointestinal tract, depending on which gene is affected.

ercalcidiol *or (formerly)* **25-hydroxyergocalciferol** *the recommended trivial name for* (5*Z*,7*E*,22*E*)-(3*S*)-9,10(19),22-ergostatetraene-3,25-diol; a secosteroid with **vitamin D** activity. It is formed in the liver from **ercalciol** and converted to **ercalcitriol** in the kidney.

ercalciol *or* **ergocalciferol** *the recommended trivial name for* calciferol, vitamin D_2, (5*Z*,7*E*,22*E*)-(3*S*)-9,10-seco-5,7,10(19),22-ergostatetraen-3-ol; a secosteroid with **vitamin D** activity, obtained synthetically by UV-irradiation of **ergosterol**. It is the form of vitamin D most commonly used as a dietary supplement and for treatment of vitamin D deficiency. *International nonproprietary name*: ergocalciferol.



ercalcitriol *or (formerly)* **1*α*,25-dihydroxyergocalciferol** *the recommended trivial name for* (5*Z*,7*E*,22*E*)-(1*S*,3*R*)-9,10-seco-5,7,10(19),22-ergostatetraene-1,3,25-triol; a secosteroid with **vitamin D** activity. It is the biologically active metabolite of **ercalcidiol** and **ercalciol**.



ERCC *abbr. for* excision repair cross complementing; any of 10 or so genes or their products that are involved in nucleotide excision repair. Mutation in any of them leads to xeroderma pigmentosum.

ERE *abbr. for* estrogen response element (*see* **response element**).

erepsin a once-supposed single enzyme secreted by the mucosa of the small intestine and thought to be responsible for completing the breakdown in the gut of partially digested proteins into amino acids. It is now known to be a mixture of **peptidases**.

erg the cgs unit of work, defined as the work done by a force of 1 dyne acting over a distance of 1 cm; equivalent to 10^{-7} J.

ERG a gene encoding a family of transcription factors and related to the protooncogene *ETS*; it is named from '*ets*-related gene'. It is expressed in some tumour-derived cell lines.

ergastoplasm *a term formerly applied to* the basophilic, fibrillar structures seen especially in pancreatic secretory cells; now termed rough **endoplasmic reticulum**.

+ergic *suffix (in pharmacology)* indicating agonist activity on a receptor in a neuron. *See*, e.g., **adrenergic**.

ergo+ *(comb. form)* **1** *or* (*before a vowel*) **erg**$_+$ denoting work. **2** *or* (*before a vowel*) **ergot**$_+$ denoting obtained from **ergot** or derived from a substance occurring naturally in ergot.

ergocalciferol *the alternative recommended trivial name and the international nonproprietary name for* **ercalciol**.

ergoflavin the major pigment from **ergot**.

ergometrine *see* **ergonovine**.

ergonovine D-lysergic acid L-2-propanolamide; ergometrine; an **ergot alkaloid** noted for inducing sustained uterine contractions and used in the treatment of postpartum hemorrhage.



ergosome *(sometimes)* a **polyribosome**.

ergosterol *trivial name for* (22*E*)-ergosta-5,7,22-trien-3*β*-ol; (22*E*)-(24*R*)-24-methylcholesta-5,7,22-trien-3*β*-ol; a sterol found in ergot, yeast, and moulds. It is usually obtained industrially from yeast, which synthesizes it from simple sugars. It is the most important of the provitamins D. On irradiation with ultraviolet light it is converted to ercalciol (vitamin D_2).



ergot *the common name for* the sclerotial phase of the fungus *Claviceps purpurea*, which parasitizes the ovaries of cereals such as rye, and other grasses, leading to ergot-contaminated seeds. Ergot yields various medically useful alkaloids, including ergotamine and ergometrine, and is a source of lysergic acid. However, ingestion of contaminated seeds by livestock or humans can result in poisoning (**ergotism**).

ergot alkaloid any of a group of about 30 indole alkaloids obtainable from **ergot**. All are derivatives of **lysergamide** and are biosynthesized from L-tryptophan.

ergotamine 12′-hydroxy-2′-methyl-5′α-(phenylmethyl)ergotaman-3′,6′,18-trione; an **ergot alkaloid** with vasoconstrictor activity, used in the treatment of migraine.



ERIC *abbr. for* enterobacterial repetitive intergenic consensus sequence; any of a number of highly conserved partly palindromic sequences. They are reminiscent of **REPs** but are longer (120 bp) and are in extragenic sites.

ERK *abbr. for* from extracellular signal-regulated kinase; any of a sub-subclass (EC 2.7.–), protein kinases, also (more frequently) known as **MAP kinases**. ERK1 (*or* insulin-stimulated MAP2 kinase) phosphorylates MAP2 and myelin basic protein. ERK2 (*or* mitogen-activated protein kinase 2 *or* MAP kinase 2) is similar, as is ERK3 (*or* MAP kinase isoform p63).

ER α-mannosidase I EC 3.2.1.113; *other names*: ER Class 1 α1,2-mannosidase *or* $Man_9GlcNAc_2$-specific processing α-mannosidase; an enzyme that acts in the first step in trimming a single mannose from $Man^9GlcNAc_2$ oligosaccharides in glycoproteins that are destined for transport through the secretory pathway.

erp60 *see* **calreticulin**.

ER-resident protein any protein that is retained by the endoplasmic reticulum. Their retention is regulated by the heterotetramer of a phosphoprotein (**calnexin**), a phosphoglycoprotein (*see* **Ssr** α), and two glycoproteins (*see* **Ssr** β). *See also* **KDEL**.

error catastrophe the threshold at which the rate of error accumulation becomes deleterious. For example, it may be the point at which mutation becomes harmful, or at which the error rate in databases becomes damaging.

'error catastrophe' hypothesis a hypothesis stating that since the protein synthetic machinery of the cell is itself made of protein, any imprecision in protein synthesis will lead to the formation of protein synthetic machinery of lowered accuracy, which will lead in turn to the production of even less precise machinery. If this positive feedback of error into the protein synthetic machinery is sufficiently high it will cause instability and an accelerating deterioration of the cell, resulting in cell death or loss of function.

error-prone repair the processes of DNA repair, following damage, that give rise to 'fixed' mutations. Whether or not a particular damaged site will eventually lead to a mutation is dependent both on the genetic constitution of the cell and on environmental factors. It has been suggested that such mutations are due to errors in filling gaps in daughter DNA strands.

erucic acid *the trivial name for* (*Z*)-docos-13-enoic acid (22:1 *n*-9). It is present in rapeseed oil. In rats, the incidence of myocardial lesions increases with the amount of the acid in the diet.

ERYF1 *see* **GATA-1**.

erythritol *i*-erythritol; *meso*-erythritol; *ms*-1,2,3,4-tetrahydroxybutane; *erythro*-1,2,3,4-butanetetrol; a polyol configurationally isomeric with (active) **threitol** but optically inactive through internal compensation. It occurs in certain fungi (where it appears to act as a storage carbohydrate), and is found also (as an ester of orsellinic acid) in some green algae and lichens. It is about twice as sweet as sucrose.

erythro- the configurational prefix to the systematic name of a polyhydric alcohol, especially of a monosaccharide, used to indicate the particular stereochemical configuration of a set of two contiguous CHOH groups that occurs in D- or L-erythrose; e.g. D-*erythro*-2-pentulose for D-ribulose. *Compare* ***threo-***.



D-erythrose



D-erythro

erythro+ *or (before a vowel)* **erythr+** *or (sometimes)* **eryth+** *comb. form* **1** indicating red-coloured. **2** pertaining to red blood cells.

erythroblast any of the nucleated red blood cells that are intermediates in the formation of a nonnucleated erythrocyte from a hemocytoblast. —**erythroblastic** *adj.*

erythrocruorin any of a group of respiratory pigments of invertebrates in the range of 0.4–6.7 MDa and containing 30–400 heme groups per molecule.

erythrocuprein *an alternative name for* Cu/Zn **superoxide dismutase**.

erythrocyte a mature red blood cell; in mammals it is non-nucleated and lacks mitochondria. Erythrocytes contain, but are no longer capable of synthesizing, **hemoglobin** and they function in the transport of oxygen. Mammalian erythrocytes obtain energy from anaerobic glycolysis and also metabolize glucose via the phosphogluconate pathway. —**erythrocytic** *adj.*

erythrocyte sedimentation rate *abbr.*: ESR; the rate at which erythrocytes sediment as measured under defined conditions. An increased ESR is almost always indicative of organic disease and is associated with an increased concentration of fibrinogen, γ-globulin, α_2-macroglobulin, or γ_1-macroglobulin in the plasma.

erythrodextrin any of the larger **dextrins** that give a red colour with diiodine.

erythrogenesis *an alternative term for* **erythropoiesis**.

***erythro*-β-hydroxyaspartic acid** an amino acid formed by PTM of an aspartyl residue at position 41 of the light chain of **protein C**.

erythroid **1** red or reddish in colour. **2** of or relating to **erythrocytes** or their precursors.

erythroid differentiation factor *see* **inhibin**.

erythrolabe *or* **erythropsin** *or* **porphyropsin** *See* **opsin**.

erythromycin any of several wide-spectrum macrolide antibiotics obtained from *Streptomyces erythreus*. Three components, A, B, and C, are produced during fermentation, the major component being erythromycin A. They inhibit protein synthesis in prokaryotes by binding to the 50S ribosomal subunit and inhibiting translocation. They are synthesized by multimodular nonribosomal peptide synthetases.

erythromycin resistance factor any of several proteins that confer resistance to the antibiotic **erythromycin**. There are three mechanisms of resistance: (1) erythromycin esterase (EC 3.1.1.), which is itself of two types (I and II); (2) a transmembrane export system (e.g., *erm* genes of *Arthrobacter* and certain Gram-positive bacteria); (3) rRNA (adenine-N^6-)-methyltransferase (EC 2.1.1.48), an enzyme that catalyses the reaction between *S*-adenosyl-L-methionine and rRNA to form *S*-adenosyl-L-homocysteine and rRNA containing N^6-methyladenine. For example, the protein from *Staphylococcus aureus* produces a dimethylation of the adenine residue at position 2058 in 23S rRNA, resulting in reduced affinity between ribosomes and all macrolide, lincosamide, and streptogramin B-type antibiotics.

erythron *a collective term for* the circulating **erythrocytes** and their precursors.

erythrophore a type of chromatophore, coloured red and found especially in some fishes and crustaceans. The pigment, a carotenoid, is contained in bright red granules, which normally are dispersed throughout the cytoplasm, but which aggregate rapidly in response to epinephrine leading to near discoloration of the cell.

erythropoiesis *or* **erythrogenesis** the formation of red blood cells, in bone marrow or elsewhere. —**erythropoietic** *or* **erythrogenetic** *adj.*

erythropoietic porphyria 1 *or* **congenital erythropoietic porphyria** an autosomal recessive abnormality of heme synthesis caused by deficiency of **uroporphyrinogen-III synthase**and characterized by excessive amounts of uroporphyrin I and coproporphyrin I in urine, and cutaneous photosensitivity. The onset and clinical severity are highly variable. Two cytosolic isoforms of the enzyme (each of 265 amino acids, called the 'housekeeping' and the 'erythroid-specific' isoforms) are derived from the gene (locus at 10q25.3) by alternative splicing. Many mutations lead to the deficiency. **2** an autosomal dominant disease caused by deficiency of the inner mitochondrial membrane enzyme **ferrochelatase**. It is characterized by excessive levels of protoporphyrin in erythrocytes, bone marrow, and plasma, cutaneous photosensitivity, and hepatobiliary complications. Many mutations in the gene (at 18q21.3) lead to the deficiency. *See* **porphyria**.

erythropoietin a 46 kDa mammalian glycoprotein **cytokine**, formed in the kidneys and liver of mammals, that stimulates cellular differentiation of bone-marrow stem cells at an early stage of erythropoiesis, accelerates the proliferation and maturation of terminally differentiating cells into erythrocytes, and maintains a physiological level of circulating erythrocyte mass. The protein is now prepared from cDNA expressed in CHO cells and other cells. It is now established as the accepted treatment of chronic renal failure. Its receptor is a type I membrane protein.

erythrose *the trivial name for* the aldotetrose *erythro*-tetrose; it has D and L enantiomers, which are respectively diastereoisomeric with those of threose. *See* ***erythro-*** for structure.

erythrosome an artificial membrane preparation in which detergent-extracted, glutaraldehyde-fixed erythrocyte ghosts are coated with phospholipid.

erythrulose *the trivial name for* the ketotetrose *glycero*-tetrulose; it has D and L enantiomers.

ES *abbr. for* enzyme–substrate complex.

esc a regulatory gene in *Drosophila* that controls expression of ***BX-C*** genes in embryos. It is named from extra sex combs.

ESCA *abbr. for* electron spectroscopy for chemical analysis. *See* **photoelectron spectroscopy**.

ES cell *abbr. for* embryonic stem cell.

Escherichia a genus of Gram-negative, rod-shaped, usually motile, chemoorganotrophic bacteria belonging to the family Enterobacteriaceae. It contains a single species, the colon bacillus, ***Escherichia coli***. [After Theodor Escherich (1857– 1911), German physician, who (in 1885) isolated the colon bacillus and gave it its original name of *Bacterium coli commune*.]

Escherichia coli *or* **colon bacillus** *abbr*.: *E. coli*; the sole member of the bacterial genus *Escherichia* and arguably the most widely used experimental cell system in biochemistry and molecular biology. The cells are straight, round-ended rods, commonly 0.5–1 µm × 1–4 µm, and usually occurring singly or in pairs. The organism is present in the intestinal tract of humans and other animals and is common in soil and water. The numerous strains, some of which are enteropathogenic, are commonly distinguished serologically by their O, K, and H antigens. Strain O157 is a life-threatening enteropathogen with genes seemingly derived (at least in part) from *Shigella* spp. It produces both hemolysin and enterotoxin. *E. coli* takes part in bacterial conjugation and other forms of genetic transfer, and can be infected with some bacteriophages and plasmids. *See also* **toxin**.

Eschweiler–Clarke reaction *see* **reductive amination**.

esculetin 6,7-dihydroxycoumarin; an agent that selectively inhibits 5- and 12-lipoxygenase, without inhibiting prostaglandin-endoperoxide synthase.



ESEEM *see* **electron spin-echo envelope modulation.**

E-selectin *see* **selectin**.

eserine *an alternative name for* **physostigmine**.

E-site the deacylated tRNA binding site in ribosomes; in bacteria this involves **ribosomal proteins** of the large subunit and 23S rRNA.

eskimo 1 an *Arabidopsis thaliana* mutant that is constitutively freeze-tolerant and accumulates sucrose and other sugars (as is usual in the development of tolerance to low temperatures) and also proline.

ESR *or* **esr** *abbr. for* **1** electron spin resonance. **2** erythrocyte sedimentation rate.

essential **1** of or being the essence of something; inherent. **2** absolutely necessary, basic, fundamental, indispensable, vitally important. **3** necessary for the normal growth of an organism but either not synthesized by that organism or synthesized at an inadequate rate. **4** *(in pathology)* describing a clinical condition or disorder that is not attributable to any discernible cause; **idiopathic** (def. 1). **5** relating to or derived from an extract of a plant, especially as an essence.

essential amino acid any amino acid that cannot be synthesized by a cell or an organism in an amount corresponding to need. The extent to which a particular amino acid is essential in any one species of organism depends on the stage of development of the subject and its physiological state. The following L-amino acids are nutritionally essential for the maintenance of nitrogen equilibrium in an adult human: isoleucine, leucine, lysine, methionine, phenylalanine, threonine, tryptophan, and valine. In addition, arginine and histidine are essential in growing children. The initial letters of the L-amino acids needed for optimal growth of infants or rats may be remembered using the mnemonic 'Many Very Hairy Little Pigs Live In The Torrid Argentine'. *Compare* **nonessential amino acid**.

essential fatty acid any polyunsaturated fatty acid that cannot be synthesized by a cell or an organism in an amount corresponding to need or from any dietary precursor. For mammals, linoleic acid (*see* **linoleate**) and (9,12,15)-linolenic acid (*formerly collectively known as* **vitamin F**) are nutritionally essential. *Compare* **nonessential fatty acid**.

essential fatty acid deficiency a condition that arises from the absence of **essential fatty acids** in the diet. A deficiency of fatty acids of the *n*-6 family (e.g. linoleic acid) in the diet of young animals results during growth in decreased body weight and, after some months, in increased skin permeability and capillary fragility, and dermatitis. If prolonged into adulthood, poor litter sizes (e.g. in rats) and infertility can result. Deficiency of fatty acids of the *n*-3 family, in the presence of *n*-6 fatty acids, does not result in such obvious manifestations, partly because these fatty acids are tenaciously retained in tissues, and partly because *n*-6 fatty acids (e.g. 22:5 *n*-6) not normally present in significant amounts are synthesized and appear to compensate for the deficiency of *n*-3 fatty acids of similar length and degree of unsaturation. That the effects of deficiency are not solely due to lack of substrates for prostanoid synthesis is indicated by the ability of **columbinic acid** to relieve some of the effects.

essential fructosuria a benign asymptomatic disorder in which hyperfructosemia and fructosuria follow the ingestion of nutrients that contain fructose or sucrose. It is caused by hepatic fructokinase deficiency, the result of mutation in the gene at 2p23.2. *See* **fructokinase** (def. 2).

essential oil any of a group of volatile, odorous, natural oils obtained from plants. Such oils are usually benzene derivatives or **terpenes**, and are useful as flavouring agents or perfumes.

essential pentosuria *see* **pentosuria**.

EST *abbr. for* expressed sequence tag.

EST1 a gene involved in telomere maintenance, possibly coding for **telomerase**. It is named from 'even shorter telomeres'. It encodes a DNA-binding protein with RNA-directed DNA polymerase activity.

established cell line cultured cells of a single origin that have the potential to be subcultured indefinitely whilst maintaining stable characteristics.

eSte *symbol for* the eleostearoyl group, $CH_3–[CH_2]_3–[CH=CH]_3–[CH_2]_7–CO–$.

ester any organic compound formed, either actually or formally, by the elimination of the elements of water between a hydroxyl group of an **oxoacid** (def. 1) and a hydroxyl group of either an alcohol or a phenol. Esters formed by condensation of one, two, or three molecular proportions of alcohol or phenol with one of a tribasic oxoacid may be termed monoesters, diesters, or triesters, respectively.

esterase any enzyme that catalyses the hydrolysis of an ester. Esterases form subclass EC 3.1 of the class EC 3, hydrolases, and are divided according to the nature of their substrates into the following sub-subclasses: EC 3.1.1, carboxylic ester hydrolases; EC 3.1.2, thiolester hydrolases; EC 3.1.3, phosphatases, phosphoric monoester hydrolases; EC 3.1.4, phosphodiesterases, phosphodiester hydrolases, phosphoric diester hydrolases (other than nucleases; see EC 3.1.11–3.1.31 below); EC 3.1.5; triphosphoric monoester hydrolases; EC 3.1.6, sulfatases, sulfuric ester hydrolases; EC 3.1.7, pyrophosphatases, diphosphoric monoester hydrolases; EC 3.1.8, phosphoric triester hydrolases; EC 3.1.11, exodeoxyribonucleases producing 5′-phosphomonoesters; EC 3.1.13, exoribonucleases producing 5′-phosphomonoesters; EC 3.1.14, exoribonucleases producing other than 5′-phosphomonoesters; EC 3.1.15, exonucleases active with either ribo- or deoxyribonucleic acids and producing 5′-phosphomonoesters; EC 3.1.16, exonucleases active with either ribo- or deoxyribonucleic acids and producing other than 5′-phosphomonoesters; EC 3.1.21, endodeoxyribonucleases producing 5′-phosphomonoesters; EC 3.1.22, endodeoxyribonucleases producing other than 5′-phosphomonoesters; EC 3.1.25, endodeoxyribonucleases specific for altered bases; EC 3.1.26, endoribonucleases producing 5′-phosphomonoesters; EC 3.1.27, endoribonucleases producing other than 5′-phosphomonoesters; EC 3.1.30, endonucleases active with either ribo- or deoxyribonucleic acids and producing 5′-phosphomonoesters; EC 3.1.31, endonucleases active with either ribo- or deoxyribonucleic acids and producing other than 5′-phosphomonoesters.

esteratic of, by means of, or having the activity of an esterase.

esterification the act or process of forming an ester from an oxoacid by condensing it with an alcohol or a phenol, or vice versa.

esterify to effect or to undergo esterification.

ester value *an alternative term for* **saponification number**.

17*β*-estradiol *or (esp. Brit.)* **17*β*-oestradiol** 1,3,5-estratriene-3,17*β*-diol; the most potent of the major **estrogens**. It is synthesized by the ovary, from which it is secreted directly into the circulation. Its formation depends on the presence of both **luteinizing hormone** and FSHRH; it is synthesized from testosterone by the aromatase complex, which is localized in ovarian granulosa cells, and is stimulated by follitropin; lutropin, on the other hand, stimulates production of testosterone, the aromatase substrate, by ovarian thecal cells. Apart from being important during development in inducing female characteristics, 17*β*-estradiol is important during the first half of the menstrual cycle (i.e. before ovulation) in stimulating proliferation of the epithelial and stromal layers of the endometrium in preparation for ovulation; it also stimulates production by the liver of proteins that bind steroids and thyroxine. During pregnancy, synthesis of estrogens is greatly increased, most of this increase being due to synthesis by the fetal adrenal gland of the precursors dehydroepiandrosterone and 16-hydroxydehydroepiandrosterone.



estramustine *or (esp. Brit.)* **oestramustine** estradiol 3-bis(2-chloroethyl)carbamate; an ester formed between estradiol and the carbonic-acid analogue of nitrogen mustard (mustine); it has antineoplastic activity.



estriol *or (esp. Brit.)* **oestriol** 16*α*-estradiol; 1,3,5-estratriene-3,16*α*,17*β*-triol; a relatively weak estrogen produced mainly during pregnancy. It is synthesized by the placenta from 16*α*-hydroxydehydroepiandrosterone sulfate, which is formed in fetal liver from dehydroepiandrosterone sulfate secreted by the fetal adrenal gland. Urinary estriol is measured to monitor fetal well-being in high-risk pregnancies. Low levels are also associated with the inherited X-linked disorder, placental sulfatase deficiency.



estrogen *or (esp. Brit.)* **oestrogen** any substance, natural or synthetic, that produces changes in the female sexual organs similar to those produced by 17*β*-estradiol, the principal hormone of the vertebrate ovary. Naturally occurring estrogens are C_{18}-steroid hormones; they are produced also by the placenta, adrenal cortex, and testis, as well as by many species of plants. *Compare* **androgen**. **—estrogenic** *or* **oestrogenic** *adj.*

estrone *or (esp. Brit.)* **oestrone** 1,3,5-estratrien-3-ol-17-one; a major estrogen, also called folliculin, synthesized and secreted by the ovary, in which it is formed from androstenedione by the aromatase complex. However, estrone is mainly synthesized in peripheral tissues, from androstenedione taken up from the circulation. Its actions are similar to those of **17*β*-estradiol**.



estrone sulfotransferase EC 2.8.2.4; an enzyme involved in the inactivation of estrogens. It catalyses the reaction of 3′-phosphoadenylylsulfate with estrone to form the inactive estrone 3-sulfate with release of adenosine 3′,5′-bisphosphate. Example from *Bos taurus*: SUOE_BOVIN, 295 amino acids (34.60 kDa).

estrophile *(sometimes)* estrogen receptor.

estrous cycle *or (esp. Brit.)* **oestrous cycle** the hormonally controlled cycle of activity of the reproductive organs of nonpregnant, sexually mature females of many species of mammal. It may be continuous or seasonal, depending on species. There are four principal phases. (1) **Follicular phase** *or* **estrus** – ovarian Graafian follicles mature, estrogen secretion by the ovary is at its highest, and the endometrium proliferates; the phase culminates in ovulation; in seasonal animals it is the time of sexual receptivity. (2) **Luteal phase** *or* **metestrus** – the corpus luteum develops in the ovary, estrogen secretion diminishes, and progesterone secretion reaches its maximum. (3) **Diestrus** – the corpus luteum and endometrium regress, new follicular growth begins, and progesterone secretion diminishes. (4) **Proestrus** – the corpora lutea involute, Graafian follicles re-emerge, and gonadal hormone secretion is at its lowest. The cycle then recommences.

estrus *or (esp. Brit.)* **oestrus** the first phase of the **estrous cycle**. **—estrous** *or (esp. Brit.)* **oestrous** *adj.*

esu *or* **ESU** *abbr. for* electrostatic unit.

Et *symbol for* the ethyl group, $CH_3–CH_2–$.

ET *abbr. for* endothelin.

eta 1 *symbol*: η (lower case) *or* H (upper case); the seventh letter of the Greek alphabet. For uses *see* **Appendix A**. **2** *(in chemical nomenclature) a less common alternative name for* **hapto**.

ET cloning a method for engineering DNA in *E. coli* using homologous recombination catalysed by RecE and RecT recombinases.

ETF *abbr. for* electron-transfer flavoprotein *or* electron-transferring flavoprotein.

ethambutol (+)-*N*,*N*′-bis(1-hydroxymethylpropyl)ethylenediamine; an antitubercular drug.

ethanol *or (formerly)* **ethyl alcohol** $CH_3–CH_2–OH$; a colourless, water-miscible, flammable liquid. It is produced by **alcoholic fermentation** and is thereby probably the single most important product of bioindustry in economic terms. However, most ethanol (not destined for human consumption) is now manufactured from ethylene as a by-product in the petroleum industry. Commonly known as alcohol.

ethanolamine-phosphate cytidylyltransferase EC 2.7.7.14; *other name*: phosphorylethanolamine transferase; an enzyme that catalyses the reaction of CTP and ethanolamine phosphate to form **CDPethanolamine** with release of pyrophosphate.

ethanolaminephosphotransferase EC 2.7.8.1; an enzyme of the pathway for *de novo* synthesis of phosphatidylethanolamines. It catalyses the reaction of CDPethanolamine with 1,2-diacylglycerol to form phosphatidylethanolamine with release of CMP. *Compare* **phosphatidylserine decarboxylase**.

ethanol fermentation *an alternative term for* **alcohol fermentation**.

ethanolic of, containing, or derived from ethanol; dissolved in pure or aqueous ethanol.

ethanol precipitation a common method for concentrating DNA from dilute solutions. Addition of two volumes of ethanol to a DNA solution containing 0.3 mol L^{-1} sodium acetate causes all the DNA to be precipitated.

ethanolysed cellulose a powdered and highly purified form of cellulose, formerly in use as a supporting medium in preparative zone electrophoresis of proteins, e.g. serum proteins. It is prepared by heating fibrous cotton (cotton wool) under reflux for approximately 24 h with acid-ethanol (absolute ethanol made 1 molar with respect to HCl either by introduction of dry hydrogen chloride gas or by reaction with acetyl chloride). By this means, partial alcoholysis of the cellulose occurs and acidic groups are neutralized by esterification, the cotton fibres being partially degraded into nonclumping particles; at the same time, light-absorbing and other interfering impurities are extracted from the cellulose.

ether 1 any anhydride, of general formula $R^1–O–R^2$, formed between two (identical or nonidentical) organic hydroxy compounds. **2** *the common name for* **diethyl ether** (*or* ethyl ether *or* ethoxyethane), $C_2H_5–O–C_2H_5$.

ethereal *(in chemistry)* of, containing, or dissolved in an ether, especially diethyl ether.

ethereal sulfate *an obsolete term for* any biogenic half-ester of sulfuric acid with an aromatic hydroxy compound. Ethereal sulfates are found in the urine as end products of sulfur metabolism and metabolism of some aromatic compounds.

ether lipid any lipid that contains (normally) one fatty alcohol in ether linkage to one of the carbon atoms (normally C-1) of glycerol. They are found in low concentrations in glycerophospholipid fractions, the constituent at C-2 of the glycerol moiety then being an acyl group. **Platelet-activating factor** is an important physiologically active ether glycerophospholipid. Ether linkages in neutral acylglycerols are known, and contain one fatty alcohol linked to glycerol by an ether linkage (usually at C-1), with fatty acids in ester linkage at the other two positions. The ether linkage resists hydrolysis, and typical hydrolysis products are the glyceryl ethers such as **batyl alcohol**, **chimyl alcohol**, and **selachyl alcohol**.

ethernet low-level protocols and associated hardware such as cabling for computer communication.

ethernet address *an alternative name for* **machine address**.

ethidium the 3,8-diamino-5-ethyl-6-phenylphenanthridinium cation, usually used as the bromide salt. It binds by **intercalation** to double-stranded regions of DNA and RNA molecules with marked enhancement of fluorescence. It is used as a trypanocide and to reveal double-stranded DNA and RNA in gel electrophoresis.



ethinylestradiol *the international nonproprietary name for* ethynylestradiol; 17*α*-ethynyl-1,3,5(10)-estratriene-3,17*β*-diol]; (17α)-19-norpregna-1,3,5(10)-trien-20-yne-3,17-diol; a synthetic steroid with potent estrogenic activity, commonly used in oral contraceptive preparations.

ethionine *S*-ethyl-L-homocysteine; a synthetic, carcinogenic analogue of methionine. Its toxicity is due to the fact that it competes with methionine for the enzyme **methionine adenosyltransferase**, with the result that *S*-adenosylmethionine is formed. This leads to a deficiency of ATP.

ethoxy *symbol*: OEt *or* Eto; the alkoxy group, $CH_3–CH_2–O–$, derived from ethanol by loss of a hydrogen atom.

ethyl *symbol*: Et; the $CH_3–CH_2–$ alkyl group, derived from ethane.

ethyl alcohol *the former name for* **ethanol**.

ethylene $CH_2{=}CH_2$; a colourless gas and the first member of the olefin (or alkene) series of hydrocarbons. It occurs naturally as a phytohormone, with a number of physiological effects, the most important being stimulation of ripening of fleshy fruit and stimulation of abscission of leaves. It is synthesized by the action of **ACC synthase**, which converts the *α*-aminobutyrate moiety of *S*-adenosylmethionine to 1-aminocyclopropane-1-carboxylic acid (ACC), followed by ACC oxidase (or **ethylene-forming enzyme**), which converts ACC to ethylene.

ethylenediaminetetraacetate *see* **EDTA**.

ethylene-forming enzyme *abbr.*: EFE; *see* **ACC oxidase**.

ethylene receptor 1 *abbr.*: ETR1; a single-pass transmembrane protein (75 kDa) of *Arabidopsis thaliana* that, as a dimer, binds ethylene and elicits its effects. Its intracellular C-terminal region is homologous to the bacterial two-component system hybrid kinase. Other receptors include: ethylene response sensor (ERS); never ripe

(Nr), which is developmentally regulated in tomato; and LeTae1 (a homologue of ETR1 of tomato), which is expressed during flower and fruit senescence.

ethylenic containing one or more aliphatic carbon–carbon double bonds, as in **ethylene**.

***N*-ethylmaleimide** *abbr*.: NEM; an agent that reacts irreversibly with thiol groups in proteins; it is useful as an inhibitor in transport studies and of thiol enzymes.



***N*-ethylmaleimide-sensitive fusion protein** *abbr*.: NSF protein; a homotetrameric cytoplasmic protein required for vesicle-mediated transport, and transport from the endoplasmic reticulum to the Golgi stack. *See also* **SNAP** (def. 3).

ethyne, C_2H_2, $CH_2{\equiv}CH_2$, former name acetylene. A substrate used in the assay of **nitrogenase**.

ethynylestradiol *see* **ethinylestradiol**.

ETI *see* **eicosatriynoic acid**.

etidronate any anion of etidronic acid, (1-hydroxyethylidene)bisphosphonic acid, an analogue of diphosphoric acid in which the latter's bridging oxy group is replaced by a 1-hydroxyethylidene group. Disodium etidronate is useful clinically for reducing the turnover rate of bone, e.g. in osteoporosis or in Paget's disease of bone.



$$HO-\overset{\overset{O}{\|}}{\underset{\underset{OH}{|}}{P}}-\overset{\overset{CH_3}{|}}{\underset{\underset{OH}{|}}{C}}-\overset{\overset{O}{\|}}{\underset{\underset{OH}{|}}{P}}-OH$$

etidronic acid

etiology *or (esp. Brit.)* **aetiology** the cause or causes of disease and their study.

Etn *symbol for* a residue of ethanolamine, $H_2N–CH_2–CH_2–O–$.

EtO *or* **OEt** *symbol for* the ethoxy group, $CH_3–CH_2–O–$.

ES cell *abbr. for* embryo-derived stem cell.

Etoposide a semisynthetic lignan derivative prepared from **podophyllotoxin**. It is useful as an antitumour agent in multidrug therapies, exerting its effect probably through interaction with topoisomerase II, which it inhibits; it also inhibits nucleoside transport in mammalian cells.



ETS *abbr. for* expression tagged site; a jargon phrase from genome mapping projects, etc. meaning a DNA database code (usually short) corresponding to an actively transcribed gene (i.e. cDNA from mRNA) of known sequence but, in general, of unknown function. Large ETS libraries are used in the human genome project and similar projects on other organisms.

ETS a protooncogene related to v-*ets*, one of the oncogenes of the acutely transforming avian erythroblastosis virus E26; is named from 'E twenty-six specific'. It encodes a family of transcription factors: Ets1 activates stromelysin and collagenase genes and binds to the enhancer sequence of the TCRα gene; it is expressed in tumours of the peripheral nervous system and in Ewing's sarcoma; Ets1 and Ets2 are kinase substrates.

ETYA 5,8,11,14-eicosatetraynoic acid (*see* **eicosatetraynoic acid**).

eu+ *prefix* **1** indicating well, pleasant, good. **2** indicating normal, true, typical. In medicine, sometimes used interchangeably with **normo+**.

e.u. *symbol for* entropy unit.

Eu *symbol for* europium.

EU *abbr. for* enzyme unit (obsolete).

Eubacteria *a name suggested for* one of three major lineages of cellular organisms, the others then being **Archaebacteria** and **eukaryotes**, defined when organisms are classified on the basis of sequence homologies of their ribosomal RNA. It comprised all typical bacteria, the major subdivisions being the cyanobacteria, the Gram-positive bacteria, and the Gram-negative bacteria. This classification has now been superseded: *see* **Archaea**, **Bacteria**, and **Eukarya**.

eucaryon *a variant spelling of* **eukaryon**.

eucell any cell of a **eukaryote**.

euchromatin the dispersed less dense form of **chromatin** in the interphase **nucleus**. About 10% is in the form of transcriptionally active chromatin, which is the least condensed, while the rest is inactive euchromatin which is more condensed than active chromatin but less condensed than **heterochromatin** which represents about 10% of the chromatin. *See* **nucleosome code**.

eucollagen **1** a highly modified form of **collagen** that can be easily and completely transformed into gelatin. **2** a hypothetical limiting structure for collagen in which Gly occurs at intervals of three residues and Hyp at intervals of ten residues; it is considered to be responsible for the 28.6 repeat distance in X-ray diffraction patterns.

eugenics *(functioning as sing.)* the study of methods of improving the hereditary characters of the human race, especially by selective breeding. **—eugenic** *adj.*

Euglena a genus of fusiform, photosynthetic protozoa (sometimes classified as algae) of the division Euglenophyta. They are useful in biochemical research as unicellular photosynthetic organisms.

euglobulin any 'true' globulin of blood plasma that is soluble in isotonic salt solutions, insoluble at low ionic strengths (or in pure water), and precipitated by addition of saturated ammonium sulfate solution to a final concentration of 33%. *Compare* **pseudoglobulin**.

euglycemia *or* **normoglycemia** the condition or state in which the blood glucose level is within the normal range. *See also* **glycemia**. **—euglycemic** *adj.*

eukarya one of the three major kingdoms of cellular organisms, the others being archaea and bacteria. The eukarya are characterized by the presence of a **eukaryon**.

eukaryon *or (sometimes)* **eucaryon** (*pl.* **eukarya** *or* **eucarya**) the type of cell nucleus bounded by a nuclear membrane and containing true chromosomes. It is characteristic of all multicellular and unicellular organisms except bacteria, actinomycetes, and cyanobacteria. *Compare* **prokaryon**. **—eukaryous** *or* **eucaryous** *adj.*

eukaryosis *or (sometimes)* **eucaryosis** the condition of possessing a **eukaryon**. **—eukaryotic** *or* **eucaryotic** *adj.*

eukaryote *or (sometimes)* **eucaryote** any organism whose cells contain a **eukaryon** (or eukarya) and undergo meiosis. *Compare* **prokaryote**.

eukaryotic porin *see* **porin**.

eumelanins *see* **melanin**.

eupeptide *a name suggested for* any physiologically active gastrointestinal polypeptide.

eupeptide bond *a name suggested for* a peptide bond formed specifically between C-1 of one amino-acid residue and N-2 of another. *Compare* **isopeptide bond**.

euploid having a chromosome number that is an exact multiple of the monoploid number; i.e. each chromosome of the set is present in the same number. *Compare* **aneuploid**. —**euploidy** *n.*

euthyroid having a normally functioning thyroid gland and normal levels of thyroid hormones.

eutopic binding *(sometimes) an alternative term for* **productive binding**.

eutrophic describing a habitat, esp. a lake or other mass of water, that contains abundant nutrients, both organic and inorganic, and hence favours excessive growth of aerobic plants and microorganisms. Such growth results in depletion of dissolved dioxygen and, ultimately, extinction of aerobic life. *Compare* **dystrophic** (def. 2), **oligotrophic**.

eutrophication the process of becoming or rendering eutrophic.

eV *symbol for* electronvolt.

e-value *abbr. for* expectation value.

E(var) *abbr. for* enhancing variegation; any of a group of genes in *Drosophila* and yeast that enhance euchromatin/heterochromatin variegation in the higher structure of chromatin. They include genes for components of ATP-dependent nucleosome remodelling complexes, such as SW1/SNF, and act in opposition to **Su(var)** gene products.

EVD *abbr. for* extreme value distribution.

event marker a feature of some chart recorders by means of which a mark is made on the chart to record the occurrence of a specifiable event or series of events, e.g. the stepwise operation of a fraction-collecting device.

EVH1 domain *abbr. for* enabled, VASP, Homer1 domain; a protein homology sequence present in the N-terminal region of *Drosophila* proteins enabled, VASP, Homer 1, and WASP. It is similar in structure, but not in sequence, to the pleckstrin homology domain, and interacts with a proline-rich motif frequently present in proteins involved in remodelling of the actin cytoskeleton.

evolution 1 *(in biology)* the process of cumulative change occurring in the form and mode of existence of a population of organisms in the course of successive generations related by descent. **2** *(in chemistry)* the liberation of a gas, or of heat, in the course of a chemical reaction. —**evolutionary** *or* **evolutional** *adj.*

evolve 1 to develop gradually; to cause to develop. **2** *(in biology)* to undergo **evolution** (def. 1). **3** *(in chemistry)* to give off a gas or heat.

ex+ 1 *prefix* indicating out of, away from, outside of; without, lacking; former. **2** *comb. form* a variant of **exo+** *(sometimes before a vowel)*.

exa *symbol*: E; the SI prefix denoting 10^{18} times.

EXAFS *abbr. for* extended X-ray absorption fine structure (spectroscopy).

excelsin a crystallizable globulin of ~290 kDa obtained from the seed of the brazil-nut tree, *Bertholettia excelsa*. Structurally, it resembles arechin, edestin, and glycinin.

exchange 1 to cause two different objects to change places with each other. **2** the act or process of exchanging. **3** *(in genetics)* the reciprocal exchange of chromatid segments between chromosomes at meiosis or mitosis that results in genetic recombination.

exchange diffusion the exchange of ions or molecules across a (biological) membrane; it can be by simple diffusion or be carrier-mediated.

exchange labelling the catalysed exchange of one nuclide for another radioactive or stable nuclide of the same element in a chemical compound in order to produce an isotopically labelled form. The procedure is useful esp. in the preparation of tritium-labelled compounds.

exchanger a substance upon which, or a device by which, an **exchange** (def. 2) can be effected; e.g. an ion exchanger, or a heat exchanger.

exchange reaction a chemical reaction that results in the production of a substance that is chemically identical with the starting material. It is not detectable by traditional chemical analysis but (often) is demonstrable with the help of (radio)isotopes.

excimer an adduct formed between a molecular entity that has been excited by a photon and an identical unexcited molecular entity; the adduct exists until it fluoresces by emission of a photon. An excimer is recognized by the production of a new fluorescent band at a longer wavelength than that of the usual emission spectrum. Its formation is distinguishable from resonance energy transfer in that the excitation spectrum is identical with that of the monomer.

excitation: $A + \text{photon} \rightarrow A^*$
excimer formation: $A^* + A \rightarrow D^*$
excimer fluorescence: $D^* \rightarrow A + A + \text{photon}$

excinuclease a DNA-repair endonuclease. An example is the ABC excision nuclease of *Escherichia coli*; this comprises three subunits, named from the corresponding ***uvr*** genes. UvrA is an ATPase and DNA-binding protein that preferentially binds single-stranded or UV-irradiated double-stranded DNA; it belongs to the **ABC transporter** family. UvrB stimulates the activities of UvrA. UvrC is a nuclease component.

excisase an enzyme involved in lambda phage induction. *See* **integrase**.

excise to cut out or remove, as of a tumour, organ, or part of a linear polymer.

excision 1 the act or process of excising, especially the enzymic removal of an oligonucleotide segment from a nucleic-acid molecule. **2** *(in genetics)* the separation of one or more replicons from a cointegrate.

excisionase *see* **Xis protein**.

excision repair one of the intracellular mechanisms for the repair of DNA lesions (single-strand breaks, damaged bases, etc.). It occurs in the following stages: (1) recognition of the damaged region; (2) removal of the damaged oligonucleotide by two enzymic nucleolytic reactions (excision); (3) synthesis by DNA polymerase of the excised oligonucleotide using the second (intact) DNA strand as template; and (4) covalent joining by DNA ligase of the newly synthesized segment to the existing ends of the originally damaged DNA strand. The process is light-independent. *Compare* **photoreactivation**, **post-replication repair**. *See also* **short-patch repair**.

excitability proteins *a collective name for* intrinsic membrane proteins that are ion channels, receptors, and ion pumps.

excitable capable of responding to a stimulus; used especially of a biological membrane, neuron, or other living matter. —**excitability** *n.*

excitable membrane any biological membrane capable of responding to a specific chemical or physical stimulus. Such membranes are commonly characterized by: (1) the presence of a highly specific, integral protein receptor; (2) the occurrence of a conformational change in the receptor in response to the specific stimulus with a consequential change in membrane permeability or in the activity of a membrane-bound enzyme; and (3) reversibility of the alterations in conformation of the receptor and functional activity of the membrane.

excitation–contraction coupling a general term often used to refer to the coupling of an excitatory stimulus to the contraction of muscle; the process by which the fibres of a muscle are caused to contract by the stimulation of a neuron.

excitation spectrum any **spectrum** of electromagnetic radiation that, when applied to a sample, causes the atoms and molecules of the sample to become excited by the absorption of energy and, when reverting to their normal energy levels, to emit radiation of different frequencies to that of the absorbed radiation. *Compare* **absorption spectrum**, **emission spectrum**.

excitatory able to excite; stimulatory.

excitatory amino-acid receptor a receptor for any excitatory amino-acid in the central nervous system. These comprise two main groups: ionotropic, regulating an intrinsic ion channel, or metabotropic, coupled to either the cAMP or inositol phospholipid second messenger systems. The three main types of ionotropic receptors all have four transmembrane domains and are characterized pharmacologically by selective agonists: *N*-methyl-D-aspartate (NMDA), α-amino-3-hydroxy-5-methyl-isoxazole (AMPA), and kainate. NMDA receptors have a further binding site for glycine, which modulates receptor activation. All such ionotropic receptors regulate Na^+ and K^+ conductance; NMDA receptors additionally regulate Ca^{2+} conductance. seven subtypes of **metabotropic** receptor have been cloned, all with seven transmembrane domains (mGlu1 to mGlu7): mGlu1 and mGlu5 modulate inositol phospholipid turnover while mGlu2, mGlu3, mGlu4, mGlu6, and mGlu7 are all negatively coupled to adenylate cyclase.

excite 1 to raise a molecular entity from its ground state to an excited state by the input of energy. **2** to cause an increase in activity or other response in an organism or part of an organism. —**excitation** *n.*

excited state any state of a molecular entity that has a higher energy level than its ground state.

exciter any device that excites, or raises a substance to an excited state.

exciton any nonconducting nonlocalized neutral entity that occurs in semicrystalline semiconductors, consisting of an excited electron bound to a positive hole, the combination forming a concentration of energy with certain properties characteristic of a particle.

exciton splitting the splitting of electronic absorption bands of a population of identical chromophores that are arranged in space such that sets of two or more are in close proximity. The splitting arises from electronic interactions between excited and nonexcited chromophores within the sets.

exclusion chromatography *an alternative name for* **permeation chromatography**.

exclusion limit an attribute of a specific gel used in **gel-permeation chromatography**. It is the relative molecular mass of the largest molecule of a particular shape that can be effectively fractionated by its use.

exclusion principle *see* **Pauli exclusion principle**.

exclusion reaction the reaction of a phage-infected bacterium that prevents the entry of additional phages. It is brought about by the strengthening of the bacterial cell envelope.

exclusion volume the volume of solvent retained by the column bed in **gel-permeation chromatography** that is outside the gel particles. *Compare* **void volume**.

excrete to eliminate waste materials (from a body or organism). —**excretion** *n.*; **excretive** *or* **excretory** *adj.*

exendin any of several peptides belonging to the glucagon family that have been isolated from *Heloderma* spp.: exendin-1 (*or* **helospectin I**), exendin-2 (*or* **helodermin**), and exendin-4 from *Heloderma suspectus*; and exendin-3 from *Heloderma horridus horridus*. They have biological activity similar to vasoactive intestinal peptide and secretin. Exendin-4 shares 53% similarity in its primary structure with glucagon-like peptide 1 (GLP-1) (7–36) amide; the latter binds to exendin receptors on pancreatic acinar cells. Exendin (9–39) (from exendin-3 or -4) is a GLP-1 receptor antagonist that blocks the inhibitory effect of GLP-1 on food intake of fasted rats. Exendin-4 is

HGEGTFTSDLSKQMEEEAVRLFIEWLKNGGPSSGAPPPS

Exendin-3 is similar except for residues 1–3, which are HSD.

exergonic describing any process or reaction that can produce work; i.e. one that, at constant pressure and temperature, results in a negative change in free energy content. *Compare* **endergonic**.

exhaustive methylation the maximal methylation of all groups in a substance that are capable of being methylated; it is useful in structural studies of carbohydrates, alkaloids, etc.

exhaustive tree search *(in phylogeny)* a method that systematically examines all possible relationships between taxa or sequences. Its time-consuming nature renders it infeasible for data sets much larger than ~10.

exo+ *or (sometimes before a vowel)* **ex+** *comb. form* indicating outside, external, outer. *Compare* **endo+**. *See also* **exo-**.

exo- *prefix (in stereochemistry) see* **conformation**.

exocellular describing cellular components that are external to the cell membrane but attached to its outer surface. *Compare* **extracellular**.

exocrine **1** describing or relating to a gland or other group of cells that discharges its secretion through a duct. **2** relating to a secretion of exocrine tissue. **3** a product of exocrine tissue. *Compare* **endocrine**.

exocytic **1** situated outside a living cell and not belonging to the cell itself; extracellular. **2** *an alternative term for* exocytotic (*see* **exocytosis**).

exocytose to effect exocytosis. —**exocytosed** *adj.*

exocytosis the discharge by a cell of intracellular materials to the exterior by **emiocytosis** or reverse **pinocytosis**. *Compare* **endocytosis**, **transcytosis**. *See also* **externalize**. —**exocytic** *or* **exocytotic** *adj.*

exodeoxyribonuclease *see* **deoxyribonuclease**.

exodeoxyribonuclease I EC 3.1.11.1; *other names*: exonuclease I; *Escherichia coli* exonuclease I. An enzyme that catalyses exonucleolytic cleavage of DNA in the 3′- to 5′-direction, releasing 5′-phosphomononucleotides. It shows a preference for single-stranded DNA.

exodeoxyribonuclease V EC 3.1.11.5; *other names*: exonuclease V; *Escherichia coli* exonuclease V; RecBC. An enzyme that catalyses exonucleolytic cleavage of DNA (in the presence of ATP), in either the 5′- to 3′- or the 3′- to 5′-direction, to yield 5′-phosphooligonucleotides. The subunits (products of genes *recA*, *recB*, and *recC*) are RecA, RecB, and RecC.

exodeoxyribonuclease VII EC 3.1.11.6; *other names*: exonuclease VII; *Escherichia coli* exonuclease VII. An enzyme that catalyses exonucleolytic cleavage of DNA, in either the 5′- to 3′- or the 3′- to 5′-direction, to yield 5′-phosphomononuc-leotides.

exodeoxyribonuclease (phage SP3-induced) EC 3.1.11.4; *other names*: phage SP3 DNase; DNA 5′-dinucleotidohydrolase. An enzyme that catalyses exonucleolytic cleavage of DNA in the 5′- to 3′-direction to yield 5′-phosphodinucleotides.

exoenzyme **1** any enzyme that occurs attached to the outer surface of a cell (i.e. an **ectoenzyme**) or in the periplasmic space, or one that is secreted by a cell into the medium. *Compare* **endoenzyme** (def. 1). **2** any enzyme that cleaves a linkage to the terminal residue of a biopolymer. *Compare* **endoenzyme** (def. 2).

exogenous originating outside an organism, tissue, or cell, e.g. nutrients; of or pertaining to external factors that affect an organism, e.g. light. —**exogenously** *adv.*

exomorphin *see* **casomorphin**.

exon any coding or messenger sequence of deoxynucleotides; i.e. any intragenic region of DNA in eukaryotes that will be expressed in (mature) mRNA or rRNA residues. An arrangement of exons alternating with **introns** constitutes a **transcriptional unit**. —**exonic** *adj.*

exon shuffling the recombination of different coding regions of eukaryotic structural genes (i.e. **exons**) through crossing-over, a mechanism proposed to explain the mosaic structure of eukaryotic genes. Such a mechanism is also responsible for the generation of, e.g., antibody diversity.

exonuclease any enzyme of sub-subclasses EC 3.1.11–16, that catalyses the hydrolysis of terminal diester linkages in polynucleotides to yield mononucleotides, the degradation of the chain occurring sequentially from one end. **Exonuclease III** (*abbr.*: ExoIII) catalyses the stepwise removal of mononucleotides from the 3′OH end of double-stranded DNA that is blunt-ended (the end recessed), or from nicks in one DNA strand. Overhangs of more than four nucleotides at the 3′ end are protected from ExoIII activity. *Compare* **endonuclease**. *See also* **deoxyribonuclease**, **nuclease**, **ribonuclease**.

exopeptidase any enzyme of subclass EC 3.4 that catalyses the hydrolysis of peptide bonds adjacent to the terminal amino or carboxyl group of an oligo- or polypeptide. Exopeptidases include: EC 3.4.11, aminopeptidases; EC 3.4.13, dipeptidases; EC 3.4.14, di- and tripeptidyl peptidases; EC 3.4.15, peptidyldipeptidases; EC 3.4.16, serine-type carboxypeptidases; EC 3.4.17, metallocarboxypeptidases; EC 3.4.18, cysteine-type carboxypeptidases; and EC 3.4.19, omega peptidases.

exophthalmic goitre *or* **Graves' disease** a form of hyperthyroidism characterized by enlargement of the thyroid gland and protrusion of the eyeballs.

exopolysaccharide any of a range of extracellular homo- or heteropolysaccharides produced by microorganisms, either as insoluble capsules or as soluble slimes. They serve for protection and possibly also in recognition by host organisms.

exoribonuclease *see* **ribonuclease**.

exorphin any peptide with morphine-like activity (*see* **opioid peptide**) that originates from outside the body. Such substances occur, e.g., in proteolytic digests of certain dietary proteins. *Compare* **endorphin**.

exo-α-sialidase EC 3.2.1.18; *other names*: sialidase; neuraminidase; *N*-acylneuraminate glycohydrolase; α-neuraminidase; an enzyme that catalyses the hydrolysis of *α*-2,3-, *α*-2,6-, and *α*-2,8-glycosidic linkages joining terminal nonreducing *N*- or *O*-acylneuraminyl residues to galactose, oligosaccharides, glycoproteins, or glycolipids.

exoskeleton any skeleton covering the outside of an organism or lying in the skin, such as the hard chitinous cuticle of an arthropod or the shell of a mollusc. *Compare* **endoskeleton**.

exosmosis the osmotic flow of water or of an aqueous solution from a cell, vessel, or organism into the surrounding aqueous medium. *Compare* **endosmosis**. **—exosmotic** *adj.*

exosome 1 a fragment of exogenous DNA that, when taken up by a cell, is not readily integrated into the chromosome but can replicate, and be expressed. **2** a multienzyme complex involved in turnover of RNA in yeast and probably in other eukaryotes. The exosome core consists of six phosphorolytic and two hydrolytic exoribonucleases (*see* **Rrp**) and another protein of undetermined function. In the cytoplasm, the core is also associated with four Ski proteins and degrades mRNA. In the nucleus it contains another hydrolytic ribonuclease (Rrp6p) and a DEAD-box RNA helicase, and is involved in processing rRNA precursors and a variety of snRNAs and snoRNAs. *Compare* **degradosome**.

exothermic describing a process or reaction that is accompanied by the evolution of heat; i.e. a process or reaction for which the change in enthalpy, ΔH, is negative at constant pressure and temperature. *Compare* **endothermic**.

exotic describing an introduced (i.e. foreign), nonendemic, nonacclimatized organism.

exotoxin any toxin formed by a microorganism and secreted into the surrounding medium. *Compare* **endotoxin**.

exp *(in mathematics) symbol for* exponential; *see* **exponential function**.

expansin any of a group of proteins, located within the cell walls of plants (both dicotyledons and grasses), that play an essential role in loosening cell walls during cell growth. They are hydrophobic, nonglycosylated proteins, M_r ~30 kDa.

expectation value *or* **expect value** *abbr.*: e-value; a statistical measure of the significance of an alignment obtained by searching a database with a query sequence. The e-value denotes the number of alignments with scores better than or equal to the obtained alignment score that are expected to occur by chance in a database of the same size and composition, using the same scoring system. The lower the e-value, the more significant the score, its value decreasing exponentially as the alignment score increases.

experiment *abbr.*: expt.; **1** any procedure or series of procedures, carried out in defined conditions and designed to obtain new information about substances, materials, organisms, or natural phenomena, or to test or confirm a hypothesis. **2** *an alternative term for* **experimentation**. **3** to carry out an experiment or experiments. **—experimenter** *n.*

experimental *abbr.*: exptl.; **1** of, relating to, or based on the results of, an experiment or experimentation. **2** describing a disease produced deliberately in laboratory plants or animals for the purposes of study or as a model for the natural disease condition. **3** any particular object or system in an experiment that includes, or is subjected to, one of the variables. *Compare* **control** (def. 1). **—experimentally** *adv.*

experimentation the act, process, or practice of carrying out an experiment or experiments.

explant 1 to transfer a piece of living tissue from its normal situation to a culture medium. **2** any piece of tissue treated in this way. **—explanted** *adj.*

exponent *or* **index** *(in mathematics)* any number (or expression, or symbol for a number) indicating the power to which another number (or expression or symbol) is raised; e.g., in the expression a^n , n is the exponent, indicating that a is multiplied by itself n times.

exponential *(in mathematics)* **1** of, containing, or involving one or more exponents, e.g. an exponential equation. **2** describing something approximately expressible by an exponential equation.

exponential function *(in mathematics)* any function of the type e^x or Ae^{ax} , where A and a are constants, e is an irrational number that is the base of natural logarithms, and x is a variable; e^x is sometimes written exp$x$.

exponential growth *an alternative term for* **logarithmic growth**.

exponential phase *an alternative term for* **logarithmic phase**.

export *informal term* describing a substance synthesized in, and then secreted from, a cell or type of cell in a multicellular organism; e.g. export protein.

exportins proteins that facilitate the export of a variety of different proteins, ribonucleoproteins and RNAs through the nuclear pore complex to the cytoplasm. Exportins bind their cargo cooperatively with RanGTP in the nucleus and release it following hydrolysis of RAN-bound GTP in the cytoplasm. CRM1/Exportin 1 has the broadest substrate range and often recognises a short leucine-rich nuclear export signal in the protein.

exposure 1 *(in photography or radiography)* the act or process of exposing sensitized photographic material, e.g. a film or plate, to light or to ionizing radiation. **2** *(in photography)* **a** a measure of the amount of light admitted into a photographic device expressed in terms of the lens aperture (f number) and time. **b** *or* **light exposure** *symbol*: H; a physical quantity equal to the product of the illuminance and the time, Δt, for which the area is exposed. The SI unit is the lux second. **3** *(in radiation dosimetry)* a measure of the amount of X- or gamma radiation to which a subject or object is exposed, expressed in terms of the quantity of electric charge of the ions of one sign produced when all the electrons of both signs liberated in a volume of air of unit mass are completely stopped. The SI unit is C kg^{-1}, which has replaced the **röntgen**. *Compare* **absorbed dose**.

express 1 *(in genetics)* **a** to allow or cause the information in a gene to become manifest. **b** to activate the cellular functions involved in **gene expression**. **c** *(in cDNA technology)* to effect the synthesis of protein from the corresponding cloned gene using an **expression vector** in an **expression system**. **2** to indicate by means of a symbol, formula, or equation. **3** to force or squeeze out a liquid from an object.

expressed sequence tag *abbr.*: EST; a partial sequence of a clone picked at random from a cDNA library and used in the identification of genes being expressed in a particular tissue. The technique exploits advances in automated DNA sequencing and sequence data handling, and a remarkably high number of ESTs turn out to represent previously unknown genes. These are identified by the predicted primary structure of the proteins that would be expressed and their relation to proteins of known structure. ESTs have proved extremely valuable in mapping the human genome, and there has been controversy surrounding attempts to patent them.

expression 1 the act or process of allowing information to become manifest. *See* **gene expression**, **expression vector**, **expression system**. **2** *(in mathematics)* a variable function or some combination of constants, variables, and/or functions. **3** the act or process of forcing or squeezing fluid from or out of something.

expression profile 1 the range of genes expressed at particular stages of cell development. **2** the level and duration of expression of one or more genes in a particular cell or tissue (detected, e.g., via sample sequencing, serial analysis, or microarray-based methods).

expression system a combination of an **expression vector** and a host cell both selected to enable the production of protein from a cloned gene. Ideally, it also contains the enzymes needed for post-translational modification of the synthesized protein. Expression in *Escherichia coli* or other bacterial cells may be inadequate for eukaryotic protein expression, but expression in mammalian cell lines may be inconvenient. Use of a baculovirus expression vector in insect cells is one technique that has been used successfully for eukaryotic protein expression.

expression tagged site *see* **ETS**.

expression vector any vector designed to enable the expression of a cloned gene. Vectors for expression in *Escherichia coli* may use the *lac* promoter, for example. Vectors for expression in mammalian cells are more complex; they may have the CMV (cytomegalovirus) promoter, which is active in a wide range of cell types, and other features such as termination sequences and sometimes an intron. *See also* **expression system**.

expressor a chemically undefined positive regulator of eukaryotic gene expression.

expt. *abbr. for* experiment (def. 1).

exptl. *abbr. for* experimental (def. 1, 2).

extein a peptide counterpart of an **exon**. *See* **intein**, **splicing**.

extended X-ray absorption fine structure (spectroscopy) *abbr.*: EXAFS (spectroscopy); a method for determining short-range order and local structure around specific atoms in noncrystalline materials. In this technique the X-ray absorption spectrum of the material is measured over an extended energy range near the absorption edge of one particular element in the material and structural details may be obtained from the observed modulation of the X-ray absorption on the high-energy side of the absorption edge. It is useful for elucidating the environment of metal ions in biological macromolecules.

extensin a glycoprotein found in plant cell walls in association with pectin. It resembles collagen of animal cells, being rich in *trans*-4-hydroxy-L-proline residues; it also contains L-arabinofuranose and D-galactopyranose residues attached in oligosaccharide units to the hydroxyl groups of the protein.

extension sequence a terminal sequence of amino-acid residues that is present in a nascent polypeptide as generated by translation of mRNA but is absent from any mature polypeptide or protein formed from it. An N-terminal extension sequence may be a signal sequence.

extensive property any of the properties of a substance or object that depend on the amount of the substance or the size of the object being considered, e.g. internal energy, mass, volume. *Compare* **intensive property**.

externalize *or* **externalise** to render external, especially to secrete a substance from a cell or organism. **—externalization** *or* **externalisation** *n.*

external standard any standard that is added to a sample at some point in an assay and serves as a reference by which the unknown being investigated can be quantified or identified.

external-standard method of quench correction *or* **external standardization** a method for correcting for quenching in **liquid scintillation counting** in which a source of gamma radiation external to the sample is brought into proximity with it after the sample has been counted and the sample is then counted again. The observed increase in count rate is correlated with that obtained using a set of differently quenched standards and the appropriate correction to the sample-count rate obtained. The method is simple and can be automated but on its own is less accurate than other methods. *Compare* **internal-standard method of quench correction**.

extinction *an older term (no longer recommended) for* **absorbance**.

extinction angle in **flow birefringence** between concentric cylinders, with polarizer and analyser at right angles, the angle between the **cross of isocline** and the cross formed by the polarizer and the analyser. It ranges from 45° (no orientation) to zero (complete orientation).

extinction coefficient *symbol E; an alternative term (no longer recommended) for* molar (decadic) absorption coefficient. *See* **absorption coefficient**.

extra+ *prefix* signifying outside or beyond.

extra arm *or* **variable arm** the base-paired segment of variable length in the cloverleaf model of some tRNA molecules. *See* **transfer RNA**.

extracellular present outside a cell, expelled from a cell, or happening outside a cell. *Compare* **exocellular**, **intracellular**.

extracellular fluid *abbr*.: ECF; the portion of the total liquid content that occurs outside the cells, esp. as distinct from **intracellular fluid**. In higher animals it comprises the **interstitial fluid**, the **lymph**, and the **blood plasma**. In a 70 kg man the volume of ECF is approximately 15.5 L and it represents approximately 22% of body mass. *Compare* **intracellular fluid**.

extracellular matrix a layer consisting mainly of proteins (especially collagen) and glycosaminoglycans (mostly as proteoglycans) that forms a sheet underlying cells such as endothelial and epithelial cells. The constituent substances are secreted by cells in the vicinity, especially fibroblasts.

extracellular space that part of a multicellular organism outside the cells proper – usually taken to be outside the plasma membranes – and occupied by fluid.

extrachromosomal describing structures, including DNA molecules, that are not part of a chromosome, or processes that proceed outside the chromosomes.

extrachromosomal inheritance inheritance controlled by extrachromosomal genes, such as those in mitochondrial or chloroplast DNA or in plasmids.

extract 1 to remove from or separate; to obtain a substance from a material, mixture, organism, or part of an organism by some chemical and/or physical process. **2** something extracted; a solution containing an active principle that has been extracted from plant or animal material.

extraction 1 the act or process of extracting. **2** something that has been extracted. *Compare* **extract** (def. 2).

extra piece *an alternative name for* **signal peptide**.

extrapolate *(in mathematics)* to estimate a value or the value of a function beyond the data values already obtained by either extending a graph or by calculation. *Compare* **interpolate**. **—extrapolation** *n.*

extreme value distribution *abbr*.: EVD; an asymmetric unimodal distribution whose righthand tail decays more gradually at high-than at low-score values. For example, in sequence analysis, local similarity scores of ungapped alignments follow the EVD, as a best local alignment has a score that is the maximum of a large number of random alignment scores.

extremophile an organism that requires extreme physicochemical conditions for its optimum growth and proliferation. Such organisms include **thermophiles** or **psychrophiles**, **halophiles**, **alkalophiles** or **acidophiles**, **osmophiles**, and **barophiles**, based on their growth at extremes of temperature, salt concentration, pH, osmolarity, or pressure, respectively.

extrinsic originating or acting from the outside. **—extrinsically** *adv.*

extrinsic factor *a former name for* **vitamin B$_{12}$**.

extrinsic fluorescence fluorescence caused by a molecule of a fluor of small molar mass attached by either chemical coupling or simple binding to a (macro)molecule under study.

extrinsic pathway (of blood coagulation) *see* **blood coagulation**.

extrinsic protein *an alternative name for* **peripheral (cell membrane) protein**.

extrude to squeeze or force out; used especially of a solid or semisolid material. **—extrusion** *n.*

extrusome an organelle excreted as an anterior vacuole by a parasitic protist. It contains substances used for penetration of host cells.

ex vivo describing any biological process, reaction, or experiment in which the nature or magnitude of a change occurring in living tissues in intact organisms is subsequently measured ***in vitro*** following the excision of affected tissues. *Compare* ***in vivo*** [*Latin*, meaning from life.]

eye *(in molecular biology)* a region of DNA undergoing replication, in which the separated strands give the appearance of an eye.

EYFP *abbr. for* enhanced yellow fluorescent protein.

***E/Z* convention** a convention of stereochemical descriptors for an unsaturated compound showing *cis–trans* isomerism that indicate unequivocally the steric relations around a (given) double bond. The **sequence rule** is applied in turn to the pair of atoms or groups attached to one of the doubly bonded atoms and to the pair attached to the other doubly bonded atom, and the order of preference in each case is established. If the two preferred atoms or groups are on opposite sides of the reference plane of the molecule the arrangement is called *E* [from German *entgegen*, opposite], and if they are on the same side of the plane it is called *Z* [from German *zusammen*, together]. For use as a prefix (in chemical nomenclature) the descriptor is placed in parentheses and connected with a hyphen, e.g. (*E*)-butenedioate and its stereoisomer (*Z*)-butenedioate (the respective systematic names for *trans*-1,2-ethylenedicarboxylate (= fumarate) and for *cis*-1,2-ethylenedicarboxylate (= maleate)). When a molecule of an unsaturated compound contains more than one double bond the prefix is composed of multiple symbols, each preceded if appropriate by the lower-numbered locant of the relevant double bond; e.g. (2*E*,4*Z*)-2,4-hexadienoate. The convention is now generally preferable to that using the structural prefixes *cis*- and *trans*-, especially for olefinic compounds having more than two substituents at a double bond (where it avoids possible ambiguity as to which pair of substituents is being designated). *See also* ***pro-E/pro-Z* convention**.

ezrin *or* **cytovillin** *or* **villin-2** *or* **P81** a protein involved in connections of major cytoskeletal structures to the plasma membrane, having domains in common with **talin**. It undergoes tyrosine phosphorylation after activation of specific growth factor receptors, and functions as a membrane-to-cytoskeleton linker that is involved in assembly of apical microvilli in parietal cells. It participates in the regulation of acid secretion.

Ff

f *symbol for* femto+ (SI prefix denoting 10^{-15} times).

f *symbol for* **1** frequency (alternative to ν). **2** activity coefficient referenced to Raoult's law. **3** fugacity (alternative to $\tilde{p}$). **4** frictional coefficient. **5** furanose form (added after the symbol for a monosaccharide, e.g. Ara*f* for arabinofuranose). **6** *(in mathematics)* function.

F *symbol for* **1** a residue of the α-amino acid L-phenylalanine (alternative to Phe). **2** fluorine. **3** the fluoro group in an organic compound. **4** *(in genetics)* filial generation. **5** farad. **6** Fick unit. **7** *abbr. for* fertility; *see* **F plasmid**. **8** *abbr. sometimes used* (not recommended) to designate **folate** or folic acid or their reduced derivatives.

F1, F2a1, F2a2, F2b, F2c, F3 *older nomenclature for* **histones**. F signifies fraction; in early work, the histones were extracted from the nuclei with sulfuric acid solutions, and separated according to their solubility.

F_{420} *see* **coenzyme F_{420}**.

F_{430} *see* **factor F_{430}**.

°F *symbol for* degree Fahrenheit. *see* **Fahrenheit temperature scale**.

F^+ *symbol for* a donor bacterial cell containing an **F plasmid**; F^- denotes a recipient bacterial cell lacking an F plasmid.

F *symbol for* **1** Faraday constant. **2** force (bold italic in vector equations). **3** fluence (alternative to *H*).

F9 a continuous line of mouse teratocarcinoma cells that retain the capacity for differentiation. They can give rise to chimeric mice when injected into the blastocoel of mouse blastocysts that are then allowed to complete the developmental process *in utero*.

FA *abbr. for* **1** fatty acid. **2** folic acid or folate (not recommended). **3** filtrable agent.

Fab fragment a ≈45 kDa protein fragment obtained (together with **Fc fragment** and **Fc′ fragment**) by papain hydrolysis of an **immunoglobulin** molecule. It consists of one intact light chain linked by a disulfide bond to the N-terminal part of the contiguous heavy chain (the **Fd fragment**). Two Fab fragments are obtained from each IgG antibody molecule; each fragment contains one antigen-binding site. The term Fab is derived from ['fragment antigen-binding']. *Compare* **$F(ab)_2$ fragment**. *See also* **Fv fragment**.

$F(ab')_2$ fragment a ≈90 kDa protein fragment obtained (together with **pFc′ fragment**) by pepsin hydrolysis of an **immunoglobulin** molecule. It consists of that part of the immunoglobulin molecule N-terminal to the site of pepsin attack and contains both **Fab fragments** held together by disulfide bonds in a short section of the **Fc fragment** (the hinge region). One $F(ab')_2$ fragment is obtained from each IgG antibody molecule; it contains two antigen-binding sites but not the site for complement fixation. *Compare* **Fab fragment**.

FABP *abbr. for* fatty acid binding protein; **albumin** is the major FABP of plasma, while a 40 kDa plasma membrane FABP of liver appears to be involved in uptake of oleate in an ATP- and Na^+-dependent manner. Small cytosolic FABPs (≈130 amino acids) have been characterized from liver, heart, skeletal muscle, intestine, and other tissues. The crystal structure of FABP from rat intestine shows 10 antiparallel beta strands in two sheets that form a hydrophobic binding pocket; four motifs are characteristic of this function.

Fabry's disease *or* **Fabry disease** an X-linked inborn error of human metabolism due to defective lysosomal α-D-galactosidase A activity. It is a **sphingolipidosis** or sphingolipid lysosomal storage disease. The enzyme defect leads to the progressive deposition in most visceral tissues of neutral glycosphingolipids with terminal α-D-galactosyl residues, principally globotriaosylceramide, Gal(α1-4)Gal(β1-4)Glc(β1-1)cer. [After Johannes Fabry (1860–1930), German physician.]

facilitated diffusion **diffusion** (def. 2) across a biological membrane through the participation of specific transporting agents (transporters) or carriers. The equilibrium distribution reached is the same as that achieved by **simple diffusion** but at any one site facilitated diffusion is mediated by a transport protein that exhibits specificity for the transported species. The existence of the transporter mediates passage across the membrane of molecules to which it would otherwise be impermeable. *Sometimes termed* **mediated transport** to distinguish it from **active transport**.

faciogenital dysplasia protein *see* **FGD1**.

FACIT *abbr. for* fibril-associated collagens with interrupted triplex helices; a group of collagens (types IX, XII and XIV) composed of triple-helical regions interrupted by non-triple-helical regions of 8–42 amino acids.

FACS *abbr. for* fluorescence-activated cell sorter.

F-actin the form of **actin** found in filaments.

factor **1** any component or cause that contributes to an effect or result; a term often used to denote an uncharacterized (or incompletely characterized) component of a biological system. **2** *(in mathematics)* any integer or polynomial that can be divided exactly into another integer or polynomial.

factor I to factor XIII, factor Va, etc. names of the **blood coagulation** factors.

factor B a component of **complement**.

factor $\bar{D}$ a component of **complement**.

factor F *an alternative name for* **initiation factor**.

factor F_{430} a nickel-containing tetrapyrrole compound, the prosthetic group of EC 2.8.4.1 coenzyme B sulfoethylthiotransferase (methyl **coenzyme M** reductase), which catalyses the terminal reductive step of methanogenesis in **methanogenic** bacteria, in which methane is formed from methyl-coenzyme M.



factor G *an alternative name for* **EF-G**; *see also* **elongation factor**.

factor H a component of **complement**.

factor I a component of **complement**.

factorial *symbol*: !; the product of all positive integers from 1 up to and including the integer in question, *n*; hence

$$n! = n(n-1)(n-2)(n-3)\ldots 3 \times 2 \times 1.$$

factor IF *an alternative name for* **initiation factor**.

factor R *an alternative name for* **release factor**.

factor S a tetrapeptide, of unknown structure, isolated from cerebrospinal fluid of goats, that slowly induces delta (slow wave) sleep in rats on infusion into the cerebral ventricles.

factor T *an alternative name for* **EF-T**; *see also* **elongation factor**.

facultative able to live under more than one set of environmental conditions.

facultative aerobe *see* **aerobe**.

facultative anaerobe *see* **anaerobe**.

FAD *abbr. for* flavin-adenine dinucleotide.

FADD *abbr. for* Fas-associated protein with death domain; *other name*: MORT1; a cytosolic adaptor protein that binds **Fas** (via the **death domain** on each) and procaspase 8 (via the death effector domain on each). The resulting complex forms part of the death-inducing signalling complex, or **DISC**

fade the waning of a response in the continued presence of an agonist. *Compare* **desensitization**.

FADH$_2$ *abbr. for* flavin-adenine dinucleotide (reduced).

F agent *see* **sex factor**.

Fahrenheit temperature scale a temperature scale in which 32°F is set equal to 273.15 K and 212 °F is set equal to 373.15 K. Thus 1 Fahrenheit degree = 5/9 × K, and Fahrenheit temperature (°F) = 9/5 × (Celsius temperature) + 32. [After G. D. Fahrenheit (1686–1736), German scientist.]

falcipain a cysteine protease of *Plasmodium falciparum*. It may be involved in host cell invasion by the parasite.

fall curve the curve describing the decrease in the colour intensity of a sample with time, obtained in a colorimetric analysis using an autoanalyser.

falling-drop method a method for the accurate determination of relative densities of liquids in which a drop of the liquid is allowed to fall to its equilibrium position in a column containing a defined density gradient of an immiscible liquid. It was formerly used for determination of the deuterium oxide content of samples of water.

falling-mercury electrode *an alternative term for* **dropping-mercury electrode**.

falling-sphere viscometer an instrument for measuring the viscosity of a liquid from the time taken for a solid sphere to fall through a given distance in a column of the liquid compared with the time taken for it to fall through the same distance in a liquid of known viscosity.

Fallopian tube an **oviduct** of a mammal.

false negative a true member of a data set that is not recognized by a discriminator for that data set.

false positive a match that is recognized by a discriminator for a given data set but is not a true member of that data set.

familial 1 of or pertaining to a given family. **2** describing something transmitted between members of a family, especially a familial character, condition, or disease.

familial betadysproteinemia *an alternative name for* **remnant hyperlipidemia**.

familial British dementia *see* **Abri**.

familial hypercholesterolemia a common autosomal dominant genetic condition resulting in elevated levels of low-density lipoprotein in blood. Fatty deposits accumulate in the arteries and skin, and the condition predisposes to coronary heart disease. It results from mutation of the **low-density lipoprotein receptor** gene resulting in haploinsufficiency in the heterozygous state.

familial hyperlysinemia an apparently benign genetic human disorder in which hyperlysinemia and hyperlysinuria result from decreased activity of the bifunctional enzyme **α-aminoadipic semialdehyde synthase**.

familial Mediterranean fever an autosomal recessive disorder characterized by periodic fever and systemic amyloidosis with renal involvement. Prominent in Sephardic Jews and Armenians, it is caused by many mutations in the gene (locus at 16p13) for a protein (781 amino acids) of unknown function called pyrin or marenostrin.

family 1 *(in taxonomy)* a taxonomic category of related organisms ranking below the **order** and above the **genus**. **2** *(in chemistry and biochemistry) an imprecise term for* a group of substances closely related structurally. *See also* **superfamily**. **3** *(in molecular biology) see* **protein family.**

FAN *abbr. for* factor associated with neutral sphingomyelinase activation; a protein of the **WD40** family that couples the p55 TNF receptor and the cannabinoid receptor to neutral sphingomyelinase to release ceramide as a signalling molecule from **sphingomyelin** on the inner leaflet of plasma membranes.

Fanconi anemia *or (esp. Brit.)* **Fanconi anaemia** a rare autosomal recessive, highly variable disorder, characterized by bone marrow failure, developmental abnormalities, and increased susceptibility to cancer. It usually proves fatal by the second decade of life. Cells from patients show increased susceptibility to crosslinking (alkylating) agents. Eight complementation groups are recognized: A, B, C, D1, D2, E, F, and G. The gene products for A, C, E, F, and G form a constitutive nuclear protein complex that is required for monoubiquitination and activation of D2 following DNA damage or during the S phase of the cell cycle. The activated D2 assembles with nuclear foci that contain BRCA1 and BRCA2. Mutations in any of these gene products leads to the disease. Cell lines from groups B and D1 contain truncated BRCA2 proteins. [After Guido Fanconi (1892–1979), Swiss paediatrician.]

Fanconi syndrome *or* **renal Fanconi syndrome** a human disorder characterized by generalized dysfunction of proximal renal tubules, manifested as glycosuria, amino aciduria, phosphaturia, acidosis, and vitamin D-resistant bone disease manifested as rickets in children or osteomalacia in adults. It may be acquired as a results of various toxic agents (including heavy metals or certain drugs) or be associated with a variety of inherited metabolic disorders. *See also* **renal rickets**.

farad *symbol*: F; the SI derived unit of electric capacitance. A capacitor has a capacitance of one farad when a charge of one coulomb raises the potential between its plates to one volt: i.e. 1F = 1CV^{-1}. [After Michael Faraday (1791–1867), British physicist.]

faradaic current an electric current flowing through an electrode that corresponds to the electrolytic oxidation or reduction of one or more chemical species.

Faraday constant *symbol*: *F*; a fundamental constant, defined as the quantity of electricity required to deposit one mole of a univalent ion from a solution of an electrolyte. It is the arithmetic product of the Avogadro constant, *L* (or N_A), and the elementary charge, *e*; hence

$$F = Le \text{ (or } F = N_A e) = 9.648\,530\,9(29) \times 10^4 \text{ C mol}^{-1}.$$

Faraday effect the rotation of the plane of vibration of polarized light, or of other polarized electromagnetic radiation, when passing through an isotropic, transparent medium in a magnetic field that has a component in the direction of the radiation.

Farber's disease *or* **Farber's lipogranulomatosis** *an alternative name for* **ceramidase** deficiency.

farnesoid X receptor (*abbr*.: FXR) or **bile acid receptor** an orphan receptor restricted to the enterohepatic system, kidney, and adrenal cortex. It forms an obligate heterodimer with retinoid X receptor (which binds 9-*cis*-retinoic acid), and the dimer binds to specific hormone response elements on DNA. Bile acids are the endogenous ligands for FXR.

farnesol *the trivial name for* any of four possible stereoisomers of 3,7,11-trimethyl-2,6,10-dodecatrien-1-ol; a sesquiterpene alcohol. The 2*E*,6*E*-isomer is found in many essential oils. The 2*Z*,6*E*-isomer is a minor constituent of some essential oils.



2*E*,6*E*-isomer

farnesyl the (2*E*,6*E*)-3,7,11-trimethyl-2,6,10-dodecatrien-1-yl group; the alkenyl group derived from the sesquiterpene alcohol **farnesol**. 2*E*,6*E*-Farnesyl diphosphate (= *trans,trans*-farnesyl diphosphate) is an intermediate in carotenoid, sesquiterpene, squalene, and sterol biosynthesis and is also a substrate in the addition of the farnesyl group to proteins (*see* **prenylation**).

farnesyltransferase EC 2.5.1.21; *recommended name*: farnesyldiphosphate farnesyltransferase; *systematic name*: farnesyl-diphosphate:farnesyl-diphosphate farnesyltransferase; *other name*: presqualene-diphosphate synthase. An enzyme that catalyses the formation of presqualene diphosphate from two molecules of farnesyl diphosphate with release of pyrophosphate. It occurs in the pathway for the synthesis of **squalene** and derivatives (cholesterol, sesquiterpenes). In eukaryotes it is a monomeric microsomal enzyme.

farnesyl*trans*transferase EC 2.5.1.29; *systematic name*: *trans*,*trans*-farnesyl-diphosphate:isopentenyl-diphosphate farnesyl*trans*transferase; *other name*: geranylgeranyl-diphosphate synthase. An enzyme that catalyses the formation of geranylgeranyl diphosphate from *trans*,*trans*-farnesyl diphosphate and isopentenyl diphosphate with the release of pyrophosphate. It occurs in the pathway for sesquiterpene and cholesterol synthesis and forms the **prenyl** derivative geranylgeranyl diphosphate. In some fungi and plants this activity is part of a multifunctional protein that also has the activities of geranylgeranyl-diphosphate synthase (*see* **dimethylallyl*trans*transferase**) and **geranyl*trans*transferase**.

farnoquinone *an alternative name for* menaquinone-6; *see* **menaquinone**.

Farr test a **radioimmunoassay** technique for measuring the absolute antigen-binding capacity of an antiserum. The antibody is allowed to react with radiolabelled antigen and the antigen–antibody complex is then precipitated by addition of saturated ammonium sulfate solution to a final concentration of 40 w/v. The antigen that has reacted can be determined in the precipitate.

far ultraviolet *see* **ultraviolet**.

far Western analysis a modification of **Western blotting** in which one of a complex mixture of proteins, separated by either denaturing or non-denaturing gel electrophoresis, is detected by its interaction with a bait protein. The bait protein may be provided with an **epitope tag** so that it can be readily detected with anti-tag antibody labelled with an enzyme.

Fas *or* **Apo-1** *or* **CD95** *or* **APT 1** *or* **apoptosis antigen 1** *or* **TNFRSF6** a transmembrane receptor protein of the TNF receptor superfamily that forms a homotrimer and is the receptor for the ligand **FasL**. The gene at 10q24.1 encodes a protein of 325 amino acids, expressed in many cell types including T lymphocytes. Fas has an N-terminal extracellular segment containing cysteine-rich repeats, and its C-terminal intracellular segment contains a **death domain**. On binding of FasL, the death domain of Fas binds to a homotypic domain present in **FADD** to promote apoptosis. Doxorubicin enhances expression of Fas in many tumours. Antibodies to a soluble N-terminal segment are present in some systemic lupus erythematosus patients. A deletion and other mutations in the Fas gene cause autoimmune lymphoproliferative syndrome (also called Canale–Smith syndrome).

Fas-associated protein with death domain *see* **FADD**.

fascicle *or* **fibre tract** a tight parallel bundle of nerve fibres that are either axons or dendrites. It is formed during the growth of nerves, and is mediated in part by cell **adhesion molecules**.

fasciclin any of the proteins of a related group that are involved in nerve **fascicles** (bundles). They include fasciclin I, a neuronal cell **adhesion molecule**, and fasciclin II, which is a neuronal recognition molecule related to NCAM (*see* **adhesion molecules**).

fascin a protein involved in the formation of actin bundles and actin polymerization.

FasL *or* **CD95 ligand** *or* **CD95L** *or* **TNFSF6** a transmembrane protein of the TNF receptor superfamily that is the ligand for **Fas**. Encoded by a gene at 1q23, it consists of an N-terminal extracellular region that contains cysteine-rich repeats, a transmembrane segment, and an intracellular C-terminal region. It forms a homotrimer and is expressed in epithelial cells, neurons, T lymphocytes, and various tumour cell lines. Binding to Fas activates membrane sphingomyelinase with release of ceramide, which activates a serine/threonine kinase that targets several proteins. Doxorubicin enhances expression of FasL in many tumours. Processing by membrane metalloproteases releases soluble FasL, raised levels of which are found in alcoholic hepatitis and malignant melanoma.

Fas ligand a homotrimeric protein on the cytotoxic T cell surface which binds to transmembrane receptor proteins on the target cell called Fas. The binding alters the the Fas proteins so that their clustered cytosolic tails recruit procaspase-8, which leads to **apoptosis** .

Fas ligand a homotrimeric protein on the cytotoxic T cell surface which binds to transmembrane receptor proteins on the target cell called Fas. The binding alters the the Fas proteins so that their clustered cytosolic tails recruit procaspase-8, which leads to **apoptosis** .

Fas receptor interacting protein *see* **RIP**.

fast 1 (*of a component of a mixture or specified substance*) one that migrates further or furthest from the origin in chromatography or electrophoresis. **2** uninfluenced by a specified agent, e.g. by light, acid, etc. *See also* **acid-fast bacilli**. **3** to abstain from, or to be prevented from, taking nourishment for at least 24 hours (in the case of laboratory animals). In clinical chemistry, the requirement is often for an overnight fast, normally at least 10 hours. **—fasted** *adj.*; **fasting** *n.*

FastA *see* **alignment algorithm**.

fast component an unusual component of a mixture, e.g. a hemoglobin variant, that moves in a specified buffer system more rapidly in chromatography or electrophoresis than does the normal component.

fast reaction any reaction, or step in a reaction sequence, that has a large rate constant and proceeds rapidly. In a reaction sequence, a fast reaction is not the rate-limiting step.

fat 1 any triacylglycerol or mixture of triacylglycerols that is solid below 20°C; those that are liquid at such temperatures are usually referred to as oils. **2** *an alternative name for* **lipid**. **3** *an alternative name for* adipose tissue; *see* **brown adipose tissue**, **white adipose tissue**.

fatal familial insomnia a rare inherited neurological disease, first described in 1986 among inhabitants of mountainous regions of Italy. It is characterized by intractable insomnia and other neurological abnormalities. It is one of three familial forms of human **prion** disease. Neuropathologically, there is neuronal loss with associated gliosis. It is associated with a pathogenic mutation of the prion gene at codon Asn^{178} (shared with Creutzfeldt–Jakob disease, but for unknown reasons of different phenotype) linked to codon Met^{129}, a site that exhibits Met/Val polylmorphism.

fat body any of the fat-containing cellular structures that serve as energy reserves in amphibians, insects, and reptiles.

fat cell *or* **fat-cell** *or* **lipocyte** *or* (*in animals*) **adipocyte** any living cell containing noticeable amounts of lipid, primarily as fat or oil.

fat index the mass of diethylether-extractable fat per unit mass of nonfat material (on a dry-weight basis) in, e.g., a foodstuff or tissue.

F_1-ATPase the globular catalytic domain of the **H^+-transporting ATP synthase**.

F_oATPase the intrinsic domain of the **H^+-transporting ATP synthase**. The ‘o’ originally referred to ‘oligomycin-sensitive’.

fat-soluble vitamin any of a diverse group of **vitamins** that are soluble in organic solvents and relatively insoluble in water. The group includes vitamins A, D, E, and K.

fat solvent any **lipid solvent** e.g. chloroform or diethylether, that will extract triacylglycerols from biological or other materials.

fatty derived from or containing fat.

fatty acid any of the aliphatic monocarboxylic acids that can be liberated by hydrolysis from naturally occurring fats and oils. Fatty acids are predominantly straight-chain acids of 4 to 24 carbon atoms, which may be saturated or unsaturated; branched fatty acids and hydroxy fatty acids also occur, and very long chain acids of over 30 carbons are found in waxes. *See also* **fatty-acid nomenclature**, **polyunsaturated fatty acid**.

fatty-acid activation the conversion of a fatty acid molecule to its fatty acyl-coenzyme A thioester, the first step in the reactions of **beta oxidation**. Fatty acyl-coenzyme A can be formed in a reaction catalysed by the acid-thiol ligases EC 6.2.1.1, 6.2.1.2, and 6.2.1.3, or by a CoA-transferase of sub-subclass EC 2.8.3.

fatty-acid nomenclature a system of symbols for describing fatty acids. The basic symbolism comprises the number of carbon atoms in the molecule, followed by the number of double bonds; the two numbers are separated by a colon. Thus, 16:0 represents palmitic acid, 16:1 palmitoleic acid, etc. To avoid ambiguity, double bond positions in unsaturated fatty acids should be indicated; 18:3 (9,12,15) represents α-linolenic acid, 18:3 (9,11,13) represents eleostearic acid. These symbols may also include the *E*/*Z* configurational descriptors (see ***E*/*Z* convention**). Although not now recommended, a still used system numbers the first double bond from the carboxyl group using the Greek letter Δ. Thus, oleic acid is 18:1 $\Delta 9$

or 18:1 Δ^9. This system persists in some enzyme names; e.g., the systematic name for linoleate isomerase (EC 5.2.1.5) is linoleate Δ^{12}-*cis*-Δ^{11}-*trans*-isomerase. *See also* **fatty acid oxidation complex**. Double bonds may also be designated from the end of the chain remote from the carboxyl group. If *n* is the total number of carbons, *n*-3 represents CH_3–CH_2–CH=CH–, etc. Since in many unsaturated fatty acids the double bonds are successively separated by methylene groups, only the position of the first double bond may be given. Thus linoleic acid [18:2 (9,12)] is also represented as 18:2 *n*-6. The Greek letter ω has also been used in the same way; e.g. for linoleic acid, 18:2 ω-6. However, it is not recommended that a double bond position, e.g. that of oleic acid, should be designated as ω9. *See also* **fish oil**, **linoleic family**, **linolenic family**, **oleic family**, **palmitoleic family**.

fatty-acid oxidation complex a bacterial multifunction protein complex that catalyses the **beta oxidation** of fatty acids. The example from *Escherichia coli* comprises α and β subunits. The α subunit contains **decenoyl-CoA *Δ*-isomerase**, **enoyl-CoA hydratase**, **3-hydroxyacyl-CoA dehydrogenase**, and 3-hydroxybutyryl-CoA epimerase. The β subunit contains 3-ketoacyl-CoA thiolase. For a mammalian system *see* **beta-oxidation system**.

fatty acid synthase complex a large multienzyme complex that catalyses a spiral set of reactions whereby fatty acids are synthesized from one molecule of acetyl coenzyme A and successive molecules of malonyl coenzyme A. In most bacteria (including *Escherichia coli*) and in chloroplasts the complex consists of six α subunits (each catalysing three activities) and six β subunits (each catalysing three activities and containing an ACP domain). In animals, the enzyme complex (EC 2.3.1.85) produces a long-chain fatty acid (typically palmitate), whereas in yeast the product is a long-chain-fatty-acyl-CoA. The synthase complex of yeast has a mass of 2300 kDa and appears in the electron microscope as an ellipsoid, 25 μm long and 21 μm in cross section. The yeast enzyme comprises α and β subunits. It is termed fatty-acyl-CoA synthase (EC 2.3.1.86), and catalyses the overall reaction:

$$\begin{gathered}\text{acetyl-CoA} + n\ \text{malonyl-CoA} + 2n\ \text{NADH} + 2n\ \text{NADPH} = \\ \text{a long-chain-acyl-CoA} + n\ \text{CoA} + n\ \mathrm{CO_2} + 2n\ \mathrm{NAD^+} + \\ 2n\ \mathrm{NADP^+};\end{gathered}$$

To synthesize palmitoyl-S-[ACP domain] requires seven repetitions of the following set of reactions, where X = -S-[ACP domain]:

$$\begin{gathered}(1)\ \mathrm{R{-}CH_2{-}CO{-}X + {}^{-}OOC{-}CH_2{-}CO{-}X \rightarrow} \\ \mathrm{R{-}CH_2{-}CO{-}CH_2{-}CO{-}X + CO_2 + H{-}X}\end{gathered}$$

$$\begin{gathered}(2)\ \mathrm{R{-}CH_2{-}CO{-}CH_2{-}CO{-}X + NADPH \rightarrow} \\ \mathrm{R{-}CH_2{-}CH(OH){-}CH_2{-}CO{-}X + NADP^+}\end{gathered}$$

$$\begin{gathered}(3)\ \mathrm{R{-}CH_2{-}CH(OH){-}CH_2{-}CO{-}X \rightarrow} \\ \mathrm{R{-}CH_2{-}CH{=}CH{-}CO{-}X + H_2O}\end{gathered}$$

$$\begin{gathered}(4)\ \mathrm{R{-}CH_2{-}CH{=}CH{-}CO{-}X + NADH \rightarrow} \\ \mathrm{R{-}CH_2{-}CH_2{-}CH_2{-}CO{-}X + NAD^+}\end{gathered}$$

The hydroxacyl product of reaction (2) has the 3*R* configuration and the enoylacyl product of reaction (3) has *E* configuration. Before the assembly begins, acetyl and malonyl units are transferred from their CoA derivatives to acyl carrier protein (ACP) by the activities of two transferases, EC 2.3.1.8 and EC 2.3.1.9. Representative enzyme activities for the four reactions are named as follows: reaction (1), EC 2.3.1.41, 3-oxoacyl-[ACP] synthase; reaction (2), EC 1.1.1.100, 3-oxoacyl-[ACP] reductase; reaction (3), EC 4.2.1.61, 3-hydroxypalmitoyl-[ACP] dehydratase; reaction (4), EC 1.3.1.9, enoyl-[ACP] reductase (NADH).

Similar enzymes with different chain length specificities may also be involved. For the first round, R = H, the two synthase substrates thus being acetyl-[ACP] and malonyl-[ACP]; the product is 3-oxobutanoyl-[ACP]. After seven repetitions of the four reactions, R = $C_{12}H_{25}$, and the product is palmitoyl-[ACP].

The vertebrate complex is a cytosolic dimer of identical subunits (260 kDa). Each human subunit contains 2504 amino acids. The sequence shows ≈80 identity with that of rat, and ≈63 identity with that of chicken. Since the product is palmitic acid itself a further enzyme is present: EC 3.1.2.14 (oleoyl-[ACP] hydrolase). Each polypeptide chain is folded into three domains: domain 1 contains the acyltransferase activities and catalyses reaction (1); domain 2 catalyses reactions (2), (3), and (4); domain 3 catalyses the hydrolysis of palmitoyl-[ACP] to palmitate. In liver, reaction (4) is catalysed by EC 1.3.1.39, **enoyl-[acyl-carrier-protein] reductase (NADPH,A-specific)**.

fatty-acid thiokinase *an alternative name for* **1** butyryl–CoA ligase (EC 6.2.1.2). **2** long-chain-fatty-acid–CoA ligase; *see* **fatty-acyl–CoA ligase**.

fatty-acyl-CoA dehydrogenase any of the acyl-CoA dehydrogenase components of the **beta-oxidation system**. Mammalian liver contains a family of these enzymes that are distinguished by their chain-length specificity into: very-long-chain (C_{20}–C_{14}), long-chain (C_{18}–C_{12}), medium-chain (C_{12}–C_4), and short-chain (C_6–C_4) acyl-CoA dehydrogenases. These share 30–40 sequence identity within a species, and 87–90 sequence identity for each enzyme between species. Several crystal structures have been solved.

fatty-acyl-CoA desaturase *see* **stearoyl-CoA desaturase**.

fatty-acyl–CoA ligase either of two enzymes involved in fatty-acid activation.

(1) Long-chain-fatty-acid–CoA ligase (EC 6.2.1.3); *other names*: acyl-activating enzyme; acyl-CoA synthetase; fatty acid thiokinase (long-chain); lignoceroyl-CoA synthase. It catalyses a reaction between ATP, a long-chain carboxylic acid, and CoA to form an acyl-CoA and pyrophosphate. In mammals there are tissue isoforms.

(2) Medium-chain-fatty-acid–CoA ligase (EC 6.2.1.–); *other name*: medium-chain-fatty-acid–CoA synthase. It catalyses the same reaction as above but with medium-chain fatty acids.

fatty-acyl-CoA synthase **1** the multifunctional protein responsible for the synthesis of long-chain fatty acyl moieties in some eukaryotes, e.g. yeast. *See* **fatty acid synthase complex**. **2** an enzyme of the endoplasmic reticulum, EC 6.2.1.3, long-chain-fatty-acid–CoA ligase, that carries out a reaction between ATP, CoA, and a long-chain fatty acid to form the corresponding fatty-acyl CoA, AMP, and pyrophosphate.

fatty-acyl group any acyl group derived from a fatty acid.

fatty alcohol *an alternative term for* **long-chain alcohol**.

fatty aldehyde:NAD$^+$ oxidoreductase an NAD$^+$-dependent long-chain-aldehyde dehydrogenase, EC 1.2.1.48, that catalyses conversion of fatty aldehydes (6C to 24C long) to the corresponding fatty acids. It is anchored to the membrane of the endoplasmic reticulum through its C-terminal region and accompanies fatty alcohol:NAD$^+$ oxidoreductase. Several isozymes occur, the longest containing 488 amino acids. Many mutations lead to enzyme deficiency and the Sjøgren–Larsson syndrome.

fatty degeneration *or* **fatty infiltration** the deterioration of a tissue due to the deposition of abnormally large amounts of fat, usually as globules, in its cells.

fatty liver a pathological condition of liver tissue that has undergone **fatty degeneration**. It results from administration of various poisons, especially chlorinated hydrocarbons, or as a result of a dietary deficiency of choline or threonine.

FATZ *abbr. for* filamin-, actinin-, and telethonin-binding protein of Z disc; any of three isoforms (FATZ1, 2, or 3) of a protein of the Z disc of skeletal muscle. It binds γ-filamin, α-actinin, telethonin, and calcineurin.

favism a disease of humans in which hemolysis is caused by eating fava beans (*Vicia faba*) or by certain drugs, e.g. sulfonamides, primaquine, and nitrofuran antibiotics. The basic defect is an inherited deficiency of glucose-6-phosphate dehydrogenase in the red blood cells; about 130 variants are known. *See also* **glucose-6-phosphate dehydrogenase deficiency**.

f1 bacteriophage a filamentous single-stranded DNA virus that infects only male strains of *Escherichia coli.*

***Fba*I** a type 2 **restriction endonuclease**; recognition sequence: T↑GATCA. *Bcl*I is an **isoschizomer**.

FBP *abbr. for* fructose 1,6-bisphosphate.

FBS *abbr.for* fetal bovine serum.

FCCP *abbr. for* carbonylcyanide *p*-trifluoromethoxyphenylhydrazone; an uncoupling agent.

F cell *a former name for* **PP cell**.

F_1-CF_0 the ε subunit of the **H$^+$-transporting ATP synthase** complex in the chloroplasts of *Chlamydomonas reinhardtii*, in which the subunit arrangement is different from that in higher plants.

Fc fragment a crystallizable protein fragment obtained (together with **Fab fragment**) by papain hydrolysis of an **immunoglobulin** molecule. That obtained from human IgG is a 50 kDa protein consisting of the C-terminal halves of two heavy chains linked by two disulfide bonds. The Fc fragment has no antigen-binding activity but carries sites for complement fixation. [Fc is from 'fragment-crystallizable'.] *Compare* **Fc′ fragment**, **Fd fragment**.

Fc′ fragment a protein fragment obtained in small amounts by papain hydrolysis of an **immunoglobulin** molecule, in addition to **Fab fragments** and **Fc fragment**. That obtained from human IgG is a 24 kDa protein; it forms noncovalently bonded dimers consisting of the C-terminal moieties of two Fc fragments minus their C-terminal tridecapeptide segments. It normally occurs in small quantities in human urine. *See also* **pFc′ fragment**.

Fc receptor any of a number of proteins that bind the Fc region of immunoglobulins A, E or G, and facilitate their recognition and uptake, especially by phagocytic cells (*see* **phagocyte**). Several types have been described; all of the proteins involved have a single transmembrane helical region. Fcγ receptor I (*abbr*.: FcγRI) *or* CD64, is a high affinity receptor for IgG, capable of binding monomeric antibody. It is a characteristic marker of mononuclear phagocytes, but may also be expressed on activated neutrophils. FcγRII *or* CD32 is a low affinity receptor for IgG present on monocytes, neutrophils, eosinophils, B cells and platelets. Crosslinking of the surface antibody and the receptor leads to downregulation of the B cell. Binding of immune complexes to this receptor leads to degranulation of platelets and release of inflammatory mediators. Another low affinity IgG receptor, FcγRIII *or* CD16 is found on macrophages, polymorphs, eosinophils and NK cells. On large granular lymphocytes it is a transmembrane glycoprotein that can link the cells to antibody-sensitized target cells, while on macrophages and neutrophils it has a **GPI anchor**. Two types of IgE receptor are known. (1) A high-affinity receptor, FcεRI, found on basophils and mast cells, which on activation leads to the release of histamine and the manifestation of allergy. It is a tetramer of one α chain, one β chain and two disulfide-linked γ chains. (2) A low-affinity receptor, FcεRII, found on lymphocytes and monocytes and involved in IgE production and differentiation of B cells. An IgA receptor is found on myeloid cells.

FCS *abbr. for* fetal calf serum.

Fd *symbol for* ferredoxin.

Fd_{540} *symbol for* a membrane-bound **ferredoxin** with a redox potential of –0.54V.

Fd_{590} *symbol for* a membrane-bound **ferredoxin** with a redox potential of –0.59V.

FDA *abbr. for* Food and Drug Administration (of the USA).

Fd fragment a protein fragment obtained by papain hydrolysis of an **immunoglobulin** molecule followed by reduction of the disulfide bonds. It consists of the part of the **heavy chain** N-terminal to the papain hydrolysis site. The N-terminal moiety is variable and forms part of the original antigen-combining site; the C-terminal moiety is constant. *Compare* **Fc fragment**.

FDNB *abbr. for* fluorodinitrobenzene; **Sanger's reagent**.

FDP *abbr. for* fructose 1,6-diphosphate (now named **fructose 1,6-bisphosphate**).

FdU *abbr. for* fluorodeoxyuridine (the symbol FdUrd is recommended).

FdUrd *symbol for* (a residue of) the deoxyribonucleotide fluorodeoxyuridine (*see* **flurouracil**).

Fe *symbol for* iron.

Fe(II) *symbol for* ferrous (divalent) iron.

Fe(III) *symbol for* ferric (trivalent) iron.

FEBS *abbr. for* Federation of European Biochemical Societies.

fecal fat fat in the feces; the output of fecal fat is normally below about 18 mmol 24 h^{-1} in the adult human. Tests that measure the fat content of feces may assist in diagnosis of generalized malabsorption syndrome; an alternative method is the **[^{14}C]triolein breath-test**.

fed batch process a process during which one or more nutrients are supplied to a bioreactor, usually without removing biomass and products. *See* **batch process**.

Federation of European Biochemical Societies *abbr*: FEBS; an international scientific organization founded in 1964 and now representing some 32 countries, including all those of mainland Europe plus Israel. FEBS is governed by a Council composed of one delegate from each of the adhering national biochemical societies plus the members of the Executive Committee. FEBS organizes an annual meeting, advanced courses, and supports fellowships and three annual prizes. It publishes two journals, *FEBS Letters* and *European Journal of Biochemistry*.

feedback **1** any feature of a system, e.g. of a metabolic pathway or of an electronic circuit, whereby information about the output of the system is used to influence the input to that system. Such feedback may increase the input to the system – **positive feedback** – or reduce the input to the system – **negative feedback**. A cyclic system of components participating in feedback forms a **feedback loop**, and the system is known as a **closed-loop system**. *Compare* **open-loop system**. **2** that part of the output of an electronic, mechanical, or other system that is returned to the input, so modifying its characteristics. *Compare* **feedforward**. **—feed back** *vb.*

feedback control control of the activity of any system by a mechanism involving **feedback**.

feedback inhibition *or* **retroinhibition** inhibition of the activity of an enzyme by the accumulation of a substance produced further along a metabolic pathway of which the enzyme is a constituent. *Compare* **enzyme repression**, **feedback repression**.

feedback repression an inhibitory feedback system in which the accumulation of a substance produced in a metabolic pathway represses the synthesis of an enzyme that is required at an earlier stage of the pathway. *Compare* **enzyme repression**, **feedback inhibition**.

feeder cell an irradiated cell that is capable of metabolizing but not of dividing. Such cells are sometimes added to cultures of unirradiated cells to help in the provision of nutrients.

feeder layer a layer of **feeder cells** in a cell culture.

feeder pathway any (minor) metabolic pathway that supplies metabolites to another (major) metabolic pathway.

feedforward **1** any feature of a system, e.g. a metabolic pathway, whereby information about the input to the system is used to influence the output of the system. *Compare* **feedback** (def. 1). **2** that part of the input of a system that influences the output of the system.

Fehling's solution a test reagent for glucose and other reducing substances. It is based on the reduction of copper(II) sulfate in alkaline solution. When boiled with a reducing substance a yellow or red precipitate of copper(I) oxide is formed. *Compare* **Benedict's solution**. [After Hermann Christian von Fehling (1812–85), German organic chemist.]

feline of, pertaining to, or resembling cats.

felix a protein designed for theoretical modelling studies, and expressed from a synthetic gene in *Escherichia coli*. [From four-helix bundle.]

female *symbol*: ♀; **1** of, pertaining to, or designating the sex that only produces gametes that can be fertilized by male gametes. **2** describing a flower that lacks stamens or has nonfunctional stamens.

female sex hormones any of the **estrogens** (estradiol-17*β*, estrone, and estriol) that are concerned with the normal growth and development of the mammalian female reproductive tract and, together with **progesterone**, control the estrous and reproductive cycles.

FeMo-co *abbr. for* iron–molybdenum cofactor (of component I of **nitrogenase**).

FeMo protein any iron–molybdenum-containing protein.

FEMS *abbr. for* Federation of European Microbiological Societies.

femto+ *symbol*: f; SI prefix denoting 10^{-15} times.

femtomolar *(informal)* describing a solution containing 10^{-15} mol dm^{-3} (of a specified solute).

femtomole *symbol*: fmol; one 10^{-15}th part of a mole (of a specified substance).

Fenton reaction the oxidation of α-hydroxy acids with hydrogen peroxide and ferrous salts (Fenton's reagent) to 2-oxo acids. The term is now used in descriptions of oxidative stress: iron-dependent decomposition of dihydrogen peroxide generates the highly reactive hydroxyl radical, probably via an oxoiron(IV) intermediate. Addition of a reducing agent such as ascorbate sets up a cycle that leads to damage to biomolecules. *Compare* **Haber–Weiss reaction**. [after H.J.H. Fenton]

F episome *an alternative name for* **F plasmid**.

Fe protein any iron-containing protein.

fer-1 *see* **otoferlin**.

feral wild; having escaped from cultivation or domestication and reverted to the wild state.

FERM domain *abbr. for* band F ezrin-radixin-moesin homology domain; a common membrane-binding module involved in localization of proteins to the plasma membrane. FERM domain-containing proteins include cytoskeletal proteins (*e.g.*, talin, the ezrin-radixin-moesin (ERM) protein family), several protein tyrosine kinases and phosphatases, and the neurofibromatosis 2 tumour suppressor protein, merlin. The ERM family proteins crosslink the actin filaments of cytoskeletal structures to the plasma membrane.

ferment **1** any agent or substance that causes fermentation. **2** *a former name for* **enzyme**. **3** *an alternative name for* **fermentation**. **4** to undergo or to effect **fermentation**. **—fermentable** *adj.*; **fermentability** *n.*

fermentation **1** (or ferment) the **anaerobic** decomposition of chemical substances, brought about by **ferments** (def. 1), resulting in the production of simpler substances and, often, of energy; an instance of this, especially the breakdown of glucose to lactate or ethanol. **2** *(in biotechnology)* the use of microorganisms or cultured cells to produce useful materials, such as antibiotics, beverages, enzymes, and some commodity chemicals.

fermenter **1** *or* **fermentor** *or* **biofermenter** an apparatus or a vessel in which to conduct **fermentation** under more or less controlled conditions. **2** a person or other agent that causes or is able to cause fermentation. **3** a genus, species, or strain of microorganism that ferments (or does not ferment) glucose or a specified sugar; e.g. **lactose fermenter**, **non-lactose fermenter**.

fermentor *a variant spelling of* **fermenter** (def. 1).

Fernández–Morán particle another name for **elementary particle** (def. 2), attached to the cristae of the mitochondrion.

ferralterin a soluble non-heme, iron–sulfur-containing chloroplast protein, mediating the light activation of chloroplast fructose 1,6-bisphosphatase.

ferredoxin *symbol*: Fd; any simple, non-enzymic **iron–sulfur protein** that is characterized by having equal numbers of atoms of iron and labile sulfur (releasable as hydrogen sulfide by acidification). The iron and sulfur atoms are present in one or two clusters of two or four atoms of each. Ferredoxins are of M_r 6000–24 000; many have a particularly low redox potential (E_o = –0.2 V to –0.6 V). They act as electron carriers in a variety of oxidation–reduction systems, and have been found in a wide range of microorganisms, in chloroplasts, and in mitochondria from adrenal cortex (*see* **adrenodoxin**) and heart muscle. *Compare* **rubredoxin**. *See also* **high-potential iron–sulfur protein**, **nitrogenase**.

ferredoxin-NADP$^+$ reductase *another name for* **NADPH:adrenodoxin oxidoreductase**.

ferredoxin–nitrite reductase *see* **nitrite reductase**.

ferri+ *comb. form* denoting containing ferric iron.

ferric of or containing trivalent iron, Fe^{3+} or Fe(III).

ferrichrome any of a group of growth-promoting Fe(III) chelates formed by various genera of microfungi, e.g. species of *Aspergillus*, *Neurospora*, and *Ustilago*. They are homodetic cyclic hexapeptides made up of a tripeptide of glycine (or other small neutral amino acids) and a tripeptide of an N^4-acyl-N^4-hydroxy-L-ornithine (e.g. the N^4-acetyl compound). They are thus **siderochromes** of the hydroxamic-acid-derivative category.

ferricytochrome any **cytochrome** in which the iron atom is in the ferric form.

ferriheme *or (esp. UK)* **ferrihaem** any Fe(III)–porphyrin coordination complex.

ferriheme chloride *another name for* **hemin**.

ferriheme hydroxide *another name for* **hematin**.

ferrihemochrome any **hemochrome** containing Fe(III).

ferrihemoglobin *or* **methemoglobin** (*abbr.*: MetHb) an oxidation product of hemoglobin in which all its four iron atoms are in the ferric, Fe(III), state, the sixth coordination valencies of which are occupied, in the acid form, by water molecules, or, in the alkaline form, by hydroxide ions; these two forms have characteristic absorption spectra. Unlike hemoglobin, it cannot bind and transport dioxygen. The 3-D structure is known (Brookhaven file 1HGB.PDB). *Compare* **ferrimyoglobin**.

ferrimyoglobin *or* **metmyoglobin** (*abbr.*: MetMb) an oxidation product of myoglobin in which its iron atom is in the ferric, Fe(III), state, the sixth coordination valency of which is occupied, in the acid form, by a water molecule, or, in the alkaline form, by a hydroxide ion. Unlike myoglobin, it cannot bind and store dioxygen. The 3D structure is known (Brookhaven file 1MBC.PDB). *Compare* **ferrihemoglobin**.

ferrioxamine *see* **desferrioxamine**.

ferritin any of a group of electron-dense, major iron-storage proteins that are widely distributed in animal and plant tissues; the iron is stored in a soluble, readily available form. Ferritins consist of a hollow protein shell; the functional molecule, called **apoferritin**, comprises 24 chains and is roughly spherical, with an external diameter of 12.4–13 nm and an internal diameter of 7–8 nm. The central cavity is able to accommodate a core of up to 4500 Fe(III) atoms, mainly as ferric hydroxide-phosphate, $(FeO(OH))_8$-$(FeO{\cdot}PO_4H_2)$. There are two types of ferritin subunit: L (light) and H (heavy); the major chain can be L or H, depending on species and tissue type. In clinical chemistry, low plasma ferritin is an indication of a decrease in the body's iron stores; a concentration of less than 12 μg L^{-1} indicates a complete absence of stored iron.

ferritin-labelling the use of **ferritin** as an electron-dense label by covalently linking ferritin molecules with the aim of making their position in microscopic specimens apparent by electron microscopy.

ferro+ *comb. form* denoting containing **ferrous** iron.

ferrochelatase EC 4.99.1.1; *systematic name*: protoheme ferro-lyase; *other names*: protoheme ferro-lyase; heme synthetase; an enzyme of the pathway for heme biosynthesis that is present on the matrix side of the inner mitochondrial membrane. It catalyses the formation of protoheme from protoporphyrin and Fe^{2+} with release of 2 H$^+$. The human enzyme (369 amino acids) shows 88 sequence identity with the murine enzyme, and 46 identity with the yeast enzyme. The mammalian enzymes contain a 2Fe-2S binding site at the C-terminus. Numerous mutations in the gene at 18q21.3 result in ferrochelatase deficiency and erythropoietic porphyria. In bacteria the enzyme is part of **siroheme synthase**.

ferrocytochrome any **cytochrome** in which the iron atom is in the Fe(II) state.

ferroheme *or* (*esp. Brit.*) **ferrohaem** **1** **heme**. **2** any Fe(II)–porphyrin coordination complex.

ferrohemochrome any **hemochrome** containing Fe(II).

ferromagnetism the property displayed by certain substances, typically metallic iron, that have a high magnetic susceptibility and that show increasing magnetization with increasing applied magnetic field strength. Some ferromagnetic materials retain their magnetization in the absence of an applied magnetic field, i.e. they become permanent magnets. Ferromagnetism is due to alignment, temporary or permanent, of the spins of the unpaired electrons in domains in the material. *Compare* **diamagnetism**, **paramagnetism**. **—ferromagnetic** *adj.*

ferroportin *or* **iron-regulated transporter** (*abbr.*: IREG); an integral membrane protein of the basolateral surface of mucosa of the upper small intestine. In association with **hephaestin** it transfers Fe^{2+} from cytosol to transferrin in portal blood. Rare mutations in its gene cause an autosomal dominant form of hemochromatosis.

ferroprotoporphyrin *see* **heme**.

ferrous of or containing divalent iron, Fe^{2+} or Fe(II).

ferroxamine *see* **desferrioxamine**.

ferroxidase *see* **ceruloplasmin**.

ferryl of or containing trivalent iron, Fe(IV)=O. This state is stabilized in iron-containing proteins such as peroxidases and some oxygenases.

fertile **1** capable of producing offspring; capable of producing gametes. **2** capable of undergoing growth and development, e.g. fertile seeds or fertile eggs.

fertilin a mouse sperm **ADAM**. Gene knockout results in sperm that are defective in binding the zona pellucida of oocytes.

fertility the state of being **fertile**.

fertility factor *an alternative name for* **F plasmid**.

fertility vitamin *a former name for* **vitamin E**.

fertilization *or* **fertilisation 1** the fusion of two gametes of opposite sex to form a zygote. **2** the act or process of fertilizing.

fertilize *or* **fertilise 1** to provide a female gamete with a male gamete to effect fertilization. **2** to supply soil or water with mineral and/or organic nutrients to assist the growth of plants.

fertilizer *or* **fertiliser 1** any substance or mixture of substances that is added to soil or water to assist the growth of plants. **2** any object or organism, e.g. an insect, that fertilizes an animal or plant.

fertilizin a mucopolysaccharide from the jelly-coat of the eggs of some species that plays a part in sperm recognition and attracts sperms of the same species.

ferulic acid 4-hydroxy-3-methoxycinnamic acid; 3-(4-hydroxy-3-methoxyphenyl)-2-propenoic acid; an aromatic acid widely distributed in plants. It is a component of **suberin**.

[2Fe-2S] an **iron-sulfur cluster** of two iron and two sulfide atoms, in an **iron-sulfur protein**. The oxidized and reduced states are written thus: [2Fe-2S]$^{2+}$ / [2Fe-2S]$^{+}$.

[4Fe-4S] an **iron-sulfur cluster** of four iron and four sulfide atoms, in an **iron-sulfur protein**.

FES/FPS a family of genes encoding nonreceptor tyrosine kinases; v-*fps* is an oncogene of Fujinami-PRCII sarcoma, while v-*fes* is a cognate gene of feline sarcoma virus. FES/FPS proteins contain an SH2 domain (*see* **SH domain**) adjacent to the kinase domain. Overexpression of c-*fes* transforms fibroblasts.

Fe–S protein *abbr. for* iron–sulfur protein.

fet+ *a variant form of* **feto+** (before a vowel).

fetal alcohol syndrome a combination of severe birth defects (low body weight, short length, facial defects, and microcephaly) affecting infants born to mothers who drink alcohol excessively, especially during the early part of their pregnancy. The offspring may also have defects in joints, heart, and muscle. Children that survive have low intelligence or are mentally retarded.

fetal bovine serum (*abbr*.: FBS) *or (sometimes)* **fetal calf serum** a serum prepared from the blood of a fetal calf, widely used in tissue culture media intended for the growth of mammalian cells.

fetal calf serum *abbr*.: FCS; *an alternative term for* **fetal bovine serum**.

fetal hemoglobin *an alternative name for* hemoglobin F (*see* **hemoglobin**).

fetal-lung maturity test a test for maturity of the fetal lung based on its content of dipalmitoylphosphatidylcholine (dipalmitoyllecithin). Dipalmitoyllecithin appears in lung surfactant in embryonic life only when the lung reaches maturity. Its concentration in amniotic fluid reflects its production in the lung and can be measured to determine lung maturity as a prenatal test to aid the decision when to induce labour. Formerly, the lecithin/sphingomyelin ratio was measured.

feto+ *or (before a vowel)* **fet+** *comb. form* denoting fetus.

fetomodulin *see* **β-thromboglobulin**.

α-fetoprotein *abbr*.: afp *or* AFP; a protein formed in fetal liver, and found in amniotic fluid. In humans, increased levels in the amniotic fluid between the 14th and 17th weeks of gestation reliably predict most cases of anencephaly and spina bifida cystica, and AFP determination is performed as an antenatal screening test for such defects. Increased serum levels may be found in adults with hepatoma and teratoma; AFP is a valuable marker for liver tumours, blood levels being elevated in about 70% of cases. The normal level in adult human plasma is <10 kU L^{-1}, but rises in normal pregnancy. It is similar to **albumin** (serum) and **vitamin D binding protein**.

fetuin *see* **α_2-HS-glycoprotein**.

fetus *or* **foetus** the embryo of a mammal in the later stages of development, from the time when the main characteristics of the mature animal can be recognized. In humans the products of conception are termed the fetus from the end of the eighth week of pregnancy until birth. —**fetal** *or* **foetal** *adj.*

Feulgen reaction a specific cytochemical reaction to indicate the presence of DNA. It is based on converting DNA, but not RNA, to apurinic acid by acid hydrolysis with release of the aldehyde functions; the aldehyde functions then give a magenta colour on treatment of the specimen with **Schiff reagent**. Tissue giving such a reaction is termed **Feulgen positive**, whereas the absence of such a reaction characterizes **Feulgen-negative** tissues. The reaction is not suitable for living cells. [After Robert Joachim Feulgen (1884–1955), German chemist.]

FFA *abbr. for* free fatty acid(s). *Compare* **NEFA**.

F factor *an alternative name for* **F plasmid**.

F′ factor *an alternative name for* **F′ plasmid**.

F$_0$F$_1$ complex *see* **H$^+$-transporting ATP synthase**.

(F$_1$ + F$_2$) fragment *see* **heavy meromyosin**.

F$_1$ fragment the separated globular head portion of a **myosin** molecule.

F$_2$ fragment the separated fibrous part of **heavy meromyosin**.

F$_3$ fragment *see* **light meromyosin**.

FGAM synthase *see* **phosphoribosylformylglycinamidine synthase**.

FGAR *abbr. for* formylglycinamide ribonucleotide; an intermediate in **purine biosynthesis**.

FGD1 *or* **faciogenital dysplasia protein** a polypeptide of 761 amino acids, encoded by a gene at Xp11.21, that acts as a guanine nucleotide exchange factor (GEF) for the cell-division cycle protein **Cdc42**. It contains an SH3 domain, a RhoGEF domain, a pleckstrin domain, and a **FYVE** domain, and is activated by binding to Cdc42. Inactivating mutations are the cause of faciogenital dysplasia, or **Aarskog–Scott syndrome**.

FGF *abbr. for* fibroblast growth factor.

FGR a gene encoding a nonreceptor tyrosine kinase and belonging to the ***src*** family; v-*fgr* is the oncogene of the feline sarcoma virus Gardner-Rasheed. *FGR* transforms most mammalian fibroblasts, but not epithelial cells.

FH$_2$ *abbr. (not recommended) for* dihydrofolate or dihydrofolic acid.

FH$_4$ *abbr. (not recommended) for* tetrahydrofolate or tetrahydrofolic acid.

FHA domain *abbr. for* forkhead-associated domain; a phosphopeptide- recognition domain found in many regulatory proteins. It is largely specific for phosphothreonine-containing epitopes, but also recognizes phosphotyrosine. It contains ~80-100 amino acid residues, folded into an 11-stranded β-sandwich, sometimes with small helical insertions between the connecting loops. The domain occurs in a range of eubacterial and eukaryotic proteins (*e.g.*, kinases, phosphatases, kinesins, transcription factors, RNA-binding proteins and metabolic enzymes) that mediate many different cellular processes, including DNA repair, signal transduction, vesicular transport, and protein degradation.

FHA domain *abbr. for* forkhead-associated domain; a phosphopeptide- recognition domain found in many regulatory proteins. It is largely specific for phosphothreonine-containing epitopes, but also recognises phosphotyrosine. It contains ~80-100 amino acid residues, folded into an 11-stranded β-sandwich, sometimes with small helical insertions between the connecting loops. The domain occurs in a range of eubacterial and eukaryotic proteins (*e.g.*, kinases, phosphatases, kinesins, transcription factors, RNA-binding proteins and metabolic enzymes) that mediate many different cellular processes, including DNA repair, signal transduction, vesicular transport, and protein degradation.

FIA *abbr. for* fluorescence immunoassay.

FIAU *abbr. for* 1-(2-deoxy-2-fluoro-*β*-D-arabinofuranosyl)-5-iodouracil; a drug used for the treatment of herpes virus infections.

fiber *the US spelling of* **fibre**.

fibre *or (US)* **fiber** any natural filamentous structure, typically pliable and often strong; by extension the term is applied to filamentous glass or filamentous synthetic polymeric materials. —**fibrous** *adj.*

fibre diagram the X-ray diffraction pattern obtained from a stretched, hence orientated, sample of an amorphous, solid, naturally occurring or synthetic fibrous linear polymer when analysed by the rotating crystal method.

fibre optics 1 a flexible glass or plastic fibre, or a bundle of such fibres, used as a light guide for the transmission of light, especially as images or digitized information. **2** the study of the optical properties of transparent fibres.

fibriform having the form of a fibre or fibres.

fibril any small thread or fibre, bundles of which may constitute a fibre. —**fibrillar, fibrilliform** *adj.*

fibrillar collagen *see* **collagen**.

fibrillarin a component of a nucleolar small nuclear ribonucleoprotein particle (snRNP) thought to participate in the first step in processing pre-rRNA, and associated with U3, U8, and U13 snRNP RNAs. It is the nucleolar scleroderma antigen, rich in N^G,N^G-dimethylarginine, and common to the major family of nucleolar snRNPs.

fibrillin a large glycoprotein isolated from fibroblast cell cultures. It is a structural Ca^{2+}-binding component of connective tissue microfibrils, and contains 34 six-cysteine (EGF-like) repeats and five eight-cysteine (TGF-β1 binding protein-like) repeats. Defects are associated with the autosomal dominant disorder, Marfan's syndrome.

β-fibrillosis *see* **amyloidosis**.

fibrin the product(s) formed from **fibrinogen** when blood plasma clots. The initial stage of this process is the formation of a **fibrin monomer** (~340 kDa) through the action of **thrombin**, which cleaves negatively charged **fibrinopeptides** A and B from fibrinogen. In intact fibrinogen, fibrinopeptides A and B prevent self-association of fibrinogen. Their removal allows the resultant molecule to self-associate readily in a staggered side-by-side arrangement, forming the fibrous **soluble fibrin polymer**. This in turn is converted into **insoluble fibrin polymer** (*see* **desmofibrin**) through the action of plasma transglutaminase (factor XIIIa, EC 2.3.2.13), which, in the presence of calcium ions, creates covalent cross-links between the monomers by transamidating glutamine residues with the amino groups of lysine side chains in other monomers. *See also* **blood coagulation**.

fibrinase *an alternative name for* **plasmin**.

fibrin monomer *see* **fibrin**.

fibrinogen *or* **factor I** a highly soluble, 340 kDa, elongated protein of blood plasma involved in clot formation. It is converted into **fibrin** monomer by the action of **thrombin**. Fibrinogen is a hexamer, 46 nm long and 9 nm maximal diameter, containing two sets of three non-identical chains (α, β, and *γ*), linked to each other by disulfide bonds. The N termini of all chains are contained in a central nodule, diverging from which are two three-chain coiled coils; these connect the central nodule to the distal nodules containing the distal domains; there are long C termini of the α chains. Thrombin cleaves four Arg–Gly bonds, releasing two each of **fibrinopeptides** A and B from the α and β chains, and forming fibrin monomer (the intact chains in fibrinogen being referred to as the Aα and Bβ chains). This exposes the N-terminal polymerization sites responsible for the formation of the soft clot, which is converted into the hard clot by **factor XIIIa**. This catalyses the *ε*-(*γ*-glutamyl) lysine cross-linking between *γ* chains (stronger) and between α chains (weaker) of different monomers. Fibrinogen also acts as a cofactor in platelet aggregation (a binding site on the *γ* chain participates). *See also* **blood coagulation**.

fibrinogenase *an alternative name for* **thrombin**.

fibrinolysin *an alternative name for* **plasmin**.

fibrinolysis the process of the dissolution of fibrin in blood clots resulting from the proteolytic action of **plasmin** or other enzymes, e.g. **streptokinase** or the proteases in snake venom. **—fibrinolytic** *adj.*

fibrinopeptide either of the types of negatively charged peptide cleaved off **fibrinogen** when it is converted to **fibrin** by the action of **thrombin**. Human **fibrinopeptide A** is a 16-residue peptide cleaved from each of the fibrinogen Aα chains; structure (human): ADSGEGDFLAEGGGVR; **fibrinopeptide B** is a 14-residue peptide cleaved from each of the Bβ chains; structure QGVNDNEEGFFSAR.

fibrin polymer *see* **fibrin**.

fibrin stabilizing factor *or* **fibrin stabilising factor** *abbr.*: FSF; *an alternative name for* factor XIIIa; *see* **blood coagulation**.

fibroblast *or* **fibrocyte** a flattened, irregular, branched, motile cell found distributed throughout vertebrate connective tissue. Such cells form, secrete, and maintain the extracellular collagen and mucopolysaccharide of this tissue. Similar cells occur in many invertebrates.

fibroblast growth factor *abbr.*: FGF; any of several growth factors that have high affinity for heparin and are mitogenic for mesodermal and neuroectodermal cells but not for endodermally derived cells. Two major subtypes are recognized: an acidic group (aFGFs) and a basic group (bFGFs). FGFs have angiogenic properties, may function as inducing agents during embryonic development, and are useful as a partial or total substitute for serum in tissue culture. Those of the acidic group, mainly from brain or retina, include acidic brain fibroblast growth factor (brain aFGF), astroglial growth factor-1 (AGF-1), retina-derived growth factor (RDGF), eye-derived growth factor-2 (EDGF-2), endothelial cell growth factor (ECGF), and heparin-binding growth factor (HGFα and HGFβ). Those of the basic group, isolated from brain, retina, and cartilage, include basic brain fibroblast growth factor (brain bFGF), eye-derived growth factor-1 (EDGF-1), astroglial growth factor-2 (AGF-2), and cartilage-derived growth factor (CDGF). FGF-3, so named because aFGF and bFGF had already been identified, is a monomer of 239 amino acids expressed during embryonic development and by mammary tumour epithelial cells; it is the product of the *int-2* oncogene. FGF-4 is the product of the *hst*/KS3 gene, comprises 205 amino acids, is expressed during development and by some tumours, is mitogenic for fibroblasts and endothelial cells, and is angiogenic *in vivo*. FGF-5 (identified by DNA probes in human bladder carcinoma, hepatoma, and endometrial carcinoma) is a monomer of 267 amino acids; it is expressed by fibroblasts, epithelium, some tumour cells, and during embryonic development, and is mitogenic for fibroblasts and endothelial cells. FGF-6 is the product of *hst-2* and is a monomer of 208 amino acids; it is expressed during embryonic development and in adult testis, heart, and skeletal muscle, and is mitogenic for fibroblasts but only weakly for endothelial cells. FGF-7 (keratinocyte growth factor) is a monomer of 194 amino acids; it is expressed by epithelial tissue and is mitogenic for epithelial cells but not for fibroblasts or endothelial cells. FGF-23 is present in normal plasma and is secreted in large amounts by human tumours that cause osteomalacia with hyperphosphaturia. It is also increased in patients with X-linked hypophosphatemia caused by mutations in the gene encoding PHEX (a putative endopeptidase). This suggests that PHEX may be responsible for degradative inactivation of FGF-23. An Na^+-phosphate cotransporter of renal tubules may mediate the action of FGF-23. Activating mutations in the gene for FGF-23 on 12p13 cause autosomal dominant hypophosphatemic rickets. *See also* ***KS*/*hst***.

fibroblast growth factor receptor *abbr.*: FGFR; any of the plasma membrane **tyrosine kinase** proteins that bind **fibroblast growth factors** and mediate their intracellular effects. All have a single transmembrane helical domain of 21 amino acids, an extracellular domain of about 350 amino acids with three immunoglobulin domains (but variants with fewer are known), and a cytoplasmic domain of about 410–425 amino acids within which is a tyrosine kinase domain which is activated by ligand binding. Six to nine potential N-linked glycosylation sites are present in the extracellular domain. FGFRs are classified into five types. FGFR1 was isolated as a partial cDNA clone encoding an *fms*-like gene (*flg*) and is also known as flg. Common variants have only two immunoglobulin (Ig) domains. FGFR2 was isolated as a tyrosine kinase gene encoding a bacterial expressed kinase (***bek***). Common variants of this also have deletion of the first Ig domain. FGFR3 is the product of *cek*2 (*see* **cek**). FGFR4 was isolated as a clone from human erythroleukemia cells. A fifth type of FGFR is known as flg-2. FGFR1 and 2 are expressed by a variety of species, tissues, and cell lines, but FGFR3, FGFR4 and flg-2 have been isolated from a limited number of sources. Heparan sulfate proteoglycans promote binding of FGFs to FGFRs. Binding of ligand to the extracellular domain of FGFRs induces oligomerization of receptors, autophosphorylation, and phosphorylation of intracellular proteins that associate with the activated receptor through their SH2 domains (*see* **SH domain**). Prominent among these is phospholipase C*γ*1 (*see* **phospholipase**).

fibroblast surface antigen *a variant form of* surface fibroblast antigen; *see* **fibronectin**.

fibrocyte *an alternative name for* **fibroblast**.

fibroglycan *see* **syndecan-2**.

fibroin *or* **silk fibroin** the protein of the silk fibres that are secreted by the posterior gland of the larva of the silk moth, *Bombyx mori*. It comprises two chains, heavy and light, linked by disulfide bond(s).

Both heavy and light chains, assembled as a mature protein, are needed for efficient intracellular transport and secretion of fibroin; the secondary structure is largely beta sheet.

fibronectin any of a group of related adhesive glycoproteins of high molecular mass found on the surface of animal cells, in connective tissue matrices, and in extracellular fluids. They bind to cell surfaces, collagen, fibrin, heparin, DNA, actin, etc. and are involved in cell adhesion, cell motility, opsonization, wound healing, and maintenance of cell shape. Fibronectin is a disulfide-bonded heterodimer. There are two immunologically cross-reacting forms: **plasma fibronectins** (*also called* cold-insoluble globulin *or* cell attachment protein *or* cell adhesion factor *or* cell spreading factor *or* anti-gelatin factor *or* opsonic α_2-SB-glycoprotein); and **cellular fibronectins** (*also called* cell surface protein *or* large external transformation sensitive (LETS) protein *or* surface fibroblast antigen *or* galactoprotein A *or* zeta protein). Plasma fibronectins are soluble dimers secreted by hepatocytes. Cellular fibronectin is secreted by fibroblasts, epithelial and other cells, and is deposited as multimeric crosslinked fibrils. It is greatly reduced or absent when cells are transformed by oncogenic viruses, chemical carcinogens, or temperature-sensitive viruses, and several changes associated with transformation can be partially reversed by addition of purified cellular fibronectin. A single human gene produces 20 isoforms by alternative splicing. These contain three types of fibronectin domain: I is ≈40 amino acids long and contains two disulfide bonds; II is ≈60 amino acids long and contains two disulfide bonds; and III is ≈90 amino acids long, lacks disulfide bonds, and forms a seven-stranded beta sheet. The longest isoform contains 12, 2, and 15, respectively, of these domains. The rare human disorder Ehlers–Danlos type X is associated with a defect in fibronectin. Fibronectin binds to **integrins** $\alpha_4\beta_1$, $\alpha_v\beta_1$, $\alpha_v\beta_3$, $\alpha_v\beta_5$, $\alpha_v\beta_6$, and $\alpha_4\beta_7$. [From Latin *fibra*, fibre and *necto*, to attach.]

fibrosome an artificial macromolecular complex of fibronectin layered on an agar-coated substrate.

fibrous protein any protein able to aggregate into fibres or filaments, and serving mainly as a structural protein. The polypeptide chains in such proteins are either extended or coiled in one dimension, and their structure is maintained largely by interchain hydrogen bonds.

fibulin a Ca^{2+}-binding glycoprotein of the extracellular matrix with nine EGF-like repeats. Four forms (A–D) differ only in their C-terminal region, and arise by alternative splicing.

ficain *or* **ficin** a cysteine endopeptidase, EC 3.4.22.3, from *Ficus* spp. with preferential cleavage at Lys-, Ala-, Tyr-, Gly-, Asn-, Leu-, and Val-. The name is also used for the crude dried latex from *Ficus* spp., but extracts of only a small proportion of these (in one study only 13 out of 43 species) contain proteolytic activity. Its action is similar to that of **papain**.

ficin *another name for* **ficain**.

Fick's first diffusion law a mathematical description of the physical process of solute diffusion; the flux (mass transferred) of particles, J, diffusing across a unit plane in unit time is given by:

$$J = -D(\partial c/\partial x),$$

where the mass concentration gradient at x is $\partial c/\partial x$ and D is the **diffusion coefficient** for the solute. [After Adolph Eugen Fick (1829–1901), German physiologist.]

Fick's second diffusion law a mathematical description of the rate of change in mass concentration, c, at point x of the diffusing particles with time, $(\partial c/\partial t)$, during solute diffusion, for unsteady conditions $(\partial c/\partial x \neq 0)$; it is given by:

$$(\partial c/\partial t) = D(\partial^2 c/\partial x^2),$$

where D is the **diffusion coefficient**, assumed to be independent of the concentration.

Fick unit *symbol*: F; a non-SI unit sometimes used to express a **diffusion coefficient**; it is equal to 10^{-7} cm^2 s^{-1}.

ficolin a multimeric protein, named after its fibrinogen- and collagen-like domains, originally isolated as a TGF-β1-binding protein. Recombinant ficolin-α and ficolin-β expressed from cDNA do not bind TGF-β1. Ficolin-α is expressed preferentially in uterus, lung, and placenta, whereas ficolin-β RNA is most abundant in skeletal muscle. The function is at present unknown.

Ficoll *or* **Ficoll 400** a synthetic copolymer of sucrose and epichlorhydrin. It has a branched structure, a high content of hydroxyl groups, which renders it very water-soluble (up to 50 w/v), and a mass average M_r of 400 000 ± 100 000. Solutions of Ficoll have low osmotic pressures and are useful in preparing density gradients; Ficoll is widely used in preparing continuous or discontinuous gradients for separating cell types. Ficoll 70, with an M_r of 70000, is useful in perfusion studies.

Ficoll-Paque *the proprietary name for* an aqueous solution of **Ficoll** and diatrizoate sodium with a density of 1.077 ± 0.001 g cm^{-3}. It is useful for the one-step separation of lymphocytes from a sample of anticoagulant-treated blood and for the preparation of other cell types by density-gradient centrifugation.

fidelity the degree to which the output of any system accurately describes or reflects the input to the system. The term is used especially of the processes of replication, translation, and transcription, and of electronic amplifiers.

field **1** a region of space in which a force is exerted on an object because of its charge (**electric field**), magnetic dipole (**magnetic field**), mass (**gravitational field**), or other attribute. **2** a region of space through which (ionizing) radiation is passing. **3** *or* **field of view** the area within which an object is observable with a microscope or other optical instrument.

Fieser's solution a solution for removing dioxygen from any other nonacidic, nonoxidizing gas. It contains potassium hydroxide, anthraquinone *β*-sulfonate, and sodium thiosulfate. Red when fresh, it becomes colourless when exhausted. [After Louis Frederick Fieser (1899–1977), US chemist.]

FIGLU *abbr. for* formiminoglutamate.

figure of merit the square of the efficiency divided by the background count for a given liquid scintillation system (*see* **liquid-scintillation counting**). It is useful for optimizing the scintillator composition and the discriminator settings for the counting channel(s).

filaggrin a protein that aggregates keratin intermediate filaments, and promotes disulfide-bond formation amongst them during terminal differentiation of mammalian epidermis. It is initially synthesized as a large, insoluble, highly phosphorylated precursor containing multiple tandem repeats of a 324-amino acid domain. The precursor is deposited as keratohyalin granules; during terminal differentiation, it is dephosphorylated and proteolytically cleaved.

filament any very thin, threadlike structure. *See also* **actin**, **microfilament**, **thick filament**, **thin filament**. **—filamentary** *or* **filamentous** *adj.*

filamentous phage any bacteriophage, such as f1, fd, and M13, that has a single-stranded DNA genome and is capable of infecting only male (F^+) strains of *Escherichia coli*. M13 particles are ≈900 nm long and have a diameter of 6.5 nm. The replicative form (RF) of the genome is a circular double-stranded DNA molecule that generates single-stranded copies by the rolling-circle mode of replication. These are packaged in capsid proteins and released from the cell. Infected cells are not lysed.

filamin a protein, extractable from smooth muscle and other tissues, that induces calcium-ion-insensitive gelation of actin. It promotes orthogonal branching of actin filaments, and links actin filaments to membrane glycoproteins. It exists as a homodimer, and contains an actin-binding domain.

filensin a membrane- and cytoskeleton-associated protein. It is an intermediate filament type III, unique to lens fibre cells. It has primary and secondary structural similarity to other intermediate filament proteins, and serves as an anchorage site for **vimentin** intermediate filaments.

filial generation *symbol*: F; any of the generations of living organisms following a particular parental generation. The generation resulting from a mating of the parents is the **first filial generation** *symbol*: (F_1), while that resulting from crossing of F_1 individuals is the **second filial generation** *symbol*: (F_2), and so on.

filipin a neutral polyene antibiotic from *Streptomyces filipinensis*. It is similar in action to **amphotericin B**.

film badge a masked photographic film worn by workers exposed to ionizing radiation to indicate the extent of their exposure to radiation.

filter **1** any piece or layer of material used or useful for (completely or partially) removing selected components, especially in suspension, from liquid or gaseous mixtures, e.g. a sheet of paper, a stratum of sand (or similar material), or a piece of porous ceramic or plastic. *See also* **membrane filter**, **ultrafilter**. **2** a device incorporating such a piece or layer of material. **3** a block or sheet of material for reducing the intensity of particulate radiation. **4** a screen for selectively absorbing or attenuating electromagnetic radiation or sound waves of some particular or all frequencies. **5** a passive electronic circuit or device that selectively attenuates or allows the passage of certain frequencies of an electrical signal. **6** to remove or separate (suspended particles, macromolecular solutes, selected frequencies of electrical signal or electromagnetic radiation, etc.) from (a heterogeneous or composite fluid, beam, signal, etc.) by means of a filter; to pass (something) through a filter. **7** *(as modifier)* containing or using a filter or filters, or used for filtering, as in a filter fluorometer or filter photometer.

filterable *or* **filtrable** capable of being filtered; able to pass through a (specified) filter.

filterable agent *a former name for* bacteriophage, virus, or other submicroscopic noncellular microorganism.

filterable virus *a former name for* a virus the particles of which are capable of passing through a filter that will retain bacteria and other cellular microorganisms.

filter membrane *an alternative term for* **membrane filter**.

filter paper porous, unsized paper used for filtration; a disk, piece, or sheet of such paper. Such paper may be chemically treated for special applications, e.g. for use in quantitative analysis; it is also used in **paper chromatography**.

filter press a device for effecting filtration, consisting of a series of (metal, plastic, or wooden) frames the two sides of which are covered with filter cloth. The frames are clamped together and the liquid to be filtered is pumped into them in such a way that the solid residue forms a cake between the cloths and the liquid filtrate is conducted away separately.

filter pump a type of vacuum pump used to assist filtration, in which a jet of water forced through a narrow orifice entraps air from the system being evacuated.

filtrable *a variant spelling of* **filterable**.

filtrate the liquid or gas that has passed through a **filter** (def. 1).

filtration the act or process of separating or (completely or partially) removing selected components (of a mixture) by means of a **filter** (def. 1), to produce a **filtrate**. The term includes **gel filtration**, **membrane filtration**, and **ultrafiltration**.

filtration enrichment a method for isolating fungal auxotrophs. Mutagenized spores are placed in a minimal medium in which only normal spores germinate and produce a mycelial network. This mycelial network is then removed by filtration and the remaining auxotrophic spores are provided with an enriched medium to allow their germination, growth, and propagation.

filtration fraction *(in physiology)* the fraction of the plasma that is filtered through the renal glomeruli. It is equal to the **glomerular filtration rate** divided by the renal plasma flow and is frequently taken to be equal to the ratio of the inulin clearance to *p*-aminohippurate clearance.

fimbria (*pl.* **fimbriae**) **1** *(in botany and zoology)* a fringe or fringelike edge or margin, e.g. especially at the opening of a fallopian tube. **2** *(in bacteriology) an alternative term for* **pilus** (especially a common pilus). **—fimbrial** *adj.*

fimbriate *or* **fimbriated** characterized by or possessing fimbriae; fringed at the edge or margin.

fimbrin an **actin-binding protein** involved in the development and maintenance of cell polarity.

fine structure *or* **microstructure** any structural detail observable in genetic material, microscopic specimens, spectra, etc. when examined at high magnification or resolution. *See also* **hyperfine structure**.

fingerprinting any pattern obtained by a variety of means that is characteristic of a biological entity, including **1** the electrophoretic or chromatographic pattern obtained after a process in which a protein is digested, usually enzymically, in defined conditions to produce a mixture of peptides, the nature of the mixture being dependent on the particular protein and the conditions of digestion. The distribution pattern of spots is rarely, if ever, duplicated if a different protein is used. **2** a set of one or more amino-acid **motifs** (def. 2) obtained by aligning conserved regions of proteins found in protein sequence databases to provide a sequence or set of sequences characteristic of a particular function e.g. the rat metabotropic glutamate receptor 2 precursor fingerprint has seven motifs, the first of which is the 22-residue

VGPVTIACLGALATLFVTVIFI.

The technique involves alignment followed by maximization of sequence information through iterative scanning, with multiple motifs, of a large composite database. The results are held in the ***PRINTS*** database. **3** the result of **genetic profiling**.

finished genome sequence a genome that has been sequenced 8–9 times (8–9-fold coverage) to reduce ambiguities in the draft sequence, to close gaps, and to allow for only a single error every 10 000 bases. *Compare* **draft genome sequence**.

firefly lantern *or* **lantern** the luminescent abdominal organ, or photophore, of the American firefly, *Photinus pyralis*, a common source of the enzyme **luciferase** and its luminogenic substrate **luciferin**.

firefly luciferase *see* **luciferase**.

firefly luciferin *see* **luciferin**.

first law of photochemistry *an alternative name for* **Grotthus and Draper law**.

first law of thermodynamics *see* **thermodynamics**.

first messenger *an alternative term* sometimes used for **hormone** to distinguish it from **second messenger**. *See also* **chemical messenger**, **pheromone**.

first-order kinetics the kinetics of a first-order reaction; *see* **order of reaction**.

first-order reaction *see* **order of reaction**.

first-pass clearance *or* **first-pass elimination** *or* **first-pass metabolism** the effect of passage of a drug administered by mouth through the liver before it reaches the systemic circulation. Some drugs, in spite of their rapid uptake through the gut mucosal membrane, appear in low concentration in the systemic circulation and hence more has to be administered by mouth than by intravenous injection. As little as 10–20% of the drug may reach the systemic circulation unchanged as a result of their metabolism, mainly by the liver. Some authors extend the term to include metabolism also by the cells of the gut mucosal membrane.

Fis1 a mitochondrial fission protein of yeast that forms an anchor on which **Dnm1** and **Mdv1** are recruited to form the contractile ring on the outer membrane.

Fischer conventions conventions used in the construction of plane projection formulas and first formulated by German organic chemist Emil Hermann Fischer (1852–1919). The first convention may be stated as 'All of the tetrahedral apices that connect asymmetric carbon atoms lie in a straight line in the plane of the paper. This line shall contain the lower edges of all these tetrahedra, their other apices being above the plane and on opposite sides of the line' (*see* **Fischer projection**). The second convention is the assumption of one specified configuration for (+)saccharic acid and hence for glucose. At the time of Fischer's work, absolute configurations were not known. Fortunately, he guessed the correct configuration for (+)glucose (now designated D-glucose).

Fischer ester *former name for* glyceraldehyde 3-phosphate (*see* **d-glyceraldehyde 3-phosphate**). [After Hermann Otto Laurenz Fischer (1888–1960), German organic chemist and son of Emil H. Fischer.]

Fischer projection a diagrammatic representation in two dimensions (as on paper) of the three-dimensional structure of an open-chain chiral molecule of the type R^1CHXR^2, useful particularly for monosaccharides (X = OH) and their derivatives and for amino acids ($X = NH_2$) and their derivatives. According to the first **Fischer convention**, the carbon chain is written vertically with the most highly oxidized carbon atom (number 1) at the top, the bonds between the carbon atoms being either in or below the plane of the paper; the hydrogen atoms and the X groups, written to the left and right of the carbon atoms to which they are attached, are considered as being in front of the plane of the paper. If X is on the right, the configuration at that carbon atom is designated by the prefix D- (from Latin *dexter*, turned to the right), whereas if X is on the left, the configuration is designated L- (from Latin *laevus*, turned to the left). *See also* **d/L** convention.

FISH *abbr. for* fluorescence *in situ* hybridization.

fish-odour syndrome a condition of humans characterized by an offensive odour of rotting fish, due to abnormal excretion of trimethylamine in the breath, urine, sweat, saliva, and vaginal secretions, especially after eating foods containing trimethylamine (e.g. sea fish) or choline. It results from a reduced ability to oxidize trimethylamine *N*-oxide, normally effected by liver microsomal monooxygenases.

fish oil oil obtained from the liver or flesh of fish; it is comparatively rich in fatty acids of the *n*-3 family (*see* **fatty-acid nomenclature**). Generally, the flesh of so-called oily fish, such as herring, mackerel, salmon, and trout, has a higher content of C_{20} and $C_{22}n$-3 acids than that of white fish such as cod or plaice. Recently, increasing the dietary content of long-chain *n*-3 fatty acids has been promoted as a prophylactic measure in the prevention of heart disease, though the mechanisms suggested are conjectural. *See also* **cod-liver oil**.

Fiske and SubbaRow method a colorimetric method for determination of inorganic phosphate, based on the production of a blue colour when the sample is treated with ammonium molybdate and 1-amino-2-naphthol-4-sulfonic acid. [After Cyrus Hartwell Fiske (1890–1978) and Yellapragrada SubbaRow (1896–1948).]

FISP-12 *another name for* mouse **connective tissue growth factor**.

fissile tending to undergo **fission**.

fission 1 *or* **nuclear fission** *(in physics)* a nuclear reaction in which a heavy atomic nucleus splits into two (or, rarely, three or four) approximately equally sized nuclides, with release of a considerable amount of energy. **2** *(in biology)* cleavage of cells or division of unicellular organisms into two (or more) parts.

fission product any of the stable or unstable nuclides resulting from **fission** (def. 1).

FITC *abbr. for* **1** fluorescein isothiocyanate. **2** the fluorescein isothiocarbamoyl group.

fitness *(in biology)* the survival value and the reproductive capability of a given genotype as compared with the average of the population or of other genotypes in the population.

fix 1 to render, or to become, stable, firm, or insoluble; to attach (to something). **2** *(in chemistry)* to convert a free element into one of its compounds; especially to convert atmospheric dinitrogen into nitrogen-containing substances (*see* **nitrogen fixation**); to convert a volatile or fluid substance into a nonvolatile or solid form; to combine an inorganic substance with an organic substance. **3** *(in biology)* to preserve (and harden) cells, tissues, or organisms for subsequent (microscopic) study. **4** *(in photography)* to treat a film or plate with fixer so as to render permanent the developed image. —**fixation** *n.*

fixative a protein-denaturing fluid, e.g. formaldehyde, that is used to **fix** (def. 3) biological material for (microscopic) study.

fixed antibody *see* **cell-bound antibody**. *Compare* **humoral antibody**.

fixed nitrogen any product of **nitrogen fixation**.

fixer *(in photography)* a chemical solution used to remove unexposed, hence unreduced, silver halide granules from a photographic emulsion after the image has been developed.

FiXeR an agonist or antagonist of the **farnesoid X receptor** (FXR).

FIZZ a family of cysteine-rich secreted proteins. FIZZ 1 is present in inflamed lung tissue, and FIZZ 3 is the same as **resistin**.

FK506 an immunosuppressant, isolated from *Streptomyces tsukubaensis*. It is a macrolide antibiotic of M_r 803, and binds to **FKBP**-binding proteins. It is a potent inhibitor of T-cell activation and prevents allograft rejection. The *in vivo* function of this **immunophilin** is not clear but in a complex with FKBP it blocks the action of **calcineurin** in the liver. It is also a powerful neuroprotective agent in a model of focal cerebral ischemia and may have clinical potential for the treatment of stroke. FK506 also reduces **nitric oxide** production by inhibiting the calcineurin-mediated dephosphorylation of **nitric-oxide synthase** (EC 1.14.13.39). One proprietary name is Tacrolimus.



FKBP *abbr. for* FK506-binding protein; any of an extensive family of small proteins to which the immunosuppressant **FK506** binds. They are found in many species, from bacteria to humans. Like **cyclophilin,** they possess **peptidyl–prolyl isomerase** activity (EC 5.2.1.8), but have no similarity in structure. Both types belong to the class of proteins termed **immunophilins**.

FLAG a proprietary synthetic epitope tag consisting of eight amino acids (Asp–Tyr–Lys–Asp–Asp–Asp–Asp–Lys) and readily detected using anti-FLAG antibodies.

flagella *the plural of* **flagellum**.

flagellate 1 describing unicellular organisms that have a **flagellum** or flagella. **2** resembling a flagellum. **3** an organism that propels itself by means of a flagellum or flagella, especially any member of the protozoan superclass Mastigophora.

flagellin any member of a group of similar monomeric soluble globular proteins that constitute the subunits of bacterial flagella. They also comprise the major antigens of several bacteria, including *Salmonella* spp., which alternate between the production of two antigenic forms of flagella, termed phase 1 and phase 2.

flagellum (*pl.* **flagella** *or* **flagellums**) **1** the specialized locomotory appendage of bacteria of certain taxonomic groups, consisting of a noncontractile, filiform extension through the cell surface, borne singly, in groups, or as a covering layer. It is commonly 3–20 μm long and 12–25 nm in diameter, is built up of several (often three) longitudinally arranged chains of **flagellin** subunits (often in a spiral), and is anchored to the cell envelope by a **basal body** (def. 1), which imparts rotatory motion to it. Bacterial flagella carry the H (or flagellar) antigens, which are useful in some instances, e.g. in *Salmonella* spp., for classification. **2** the specialized locomotory appendage of the motile cells of unicellular eukaryotes of certain taxonomic groups (e.g. some algae and protozoa) and also of the male gametes (spermatozoa) of most groups of animals. Usually borne singly or in small groups, it is a whiplike structure, similar to, but generally longer than a **cilium**, commonly about 40 μm long and 200–300 nm in diameter. It is built up of an outer membranous sheath, which is a continuation of the cell membrane, and an inner **axoneme**, which terminates within the cell at a **basal body** (def. 2). Eukaryotic flagella often exhibit undulatory motion, which in multiflagellate organisms can occur as coordinated beating. —**flagellar** *adj.*

flame emission spectrophotometry a type of **atomic emission spectrophotometry** in which excitation is produced by a flame.

flame ionization detector *or* **flame ionisation detector** a sensitive detector used in **gas chromatography** that depends on changes in the electrical conductivity of a flame (burning a mixture of dihydrogen and dinitrogen in air or dihydrogen and dioxygen), brought about by ionization of the vapours of organic substances emerging from the column.

flame photometer an instrument for **flame photometry**.

flame photometry an earlier and simpler, often direct-reading, version of atomic **emission spectrophotometry** in which isolation of the required emission line(s) is achieved by the use of an appropriate filter.

flame spectrophotometry any form of **atomic absorption spectrophotometry** or atomic **emission spectrophotometry** in which excitation is produced by a flame.

flanking marker (DNA) a DNA marker on either side of a locus; a DNA sequence on either side of a gene.

flash evaporation a technique for concentrating a solution at a relatively low temperature thus preventing denaturation of non-volatile solutes. The solution is placed in a round-bottomed flask or other vessel, which is then rapidly rotated and evacuated; the vapour removed from the solution is reliquefied in a condenser and retained in a cold trap. The rotation of the vessel causes the liquid to form a comparatively thin film, which increases its surface-to-volume ratio, thereby assisting evaporation.

flash evaporator an apparatus for **flash evaporation**.

flash photolysis a technique for investigating short-lived primary or subsequent intermediates, e.g. radicals, in a **photochemical reaction**. The sample is subjected to a brief but powerful flash of light of appropriate wavelength and the **photolysis** products are identified by their absorption or fluorescence spectra, using an independent source of radiation. The kinetics of very fast reactions can be investigated by this technique.

flash point the lowest temperature at which the vapour above a volatile combustible substance will ignite to produce a momentary flash when a small flame is applied under specified conditions.

flat-bed indicating that a technique is carried out in a horizontal plane, e.g. flat-bed chromatography.

flat-file a human-readable data file that has no structured interrelationships. It is a convenient format for data interchange or analysis; flat-files may be created as output from relational databases in a format suitable for loading into other databases or for access by analysis or query software.

flavan 2-phenylchroman; 2,3-dihydro-2-phenylbenzopyran; the parent ring structure on which the structures of flavanols, flavanones, flavones, flavonols, and other classes of aglycons of flavonoids are based.



flavanol any hydroxylated derivative of **flavan**. Glycosides of flavan-3-ol and of flavan-3,4-diol respectively form two of the classes of **flavonoid** (def. 1).

flavanone 1 2,3-dihydroflavone; 2-phenylchroman-4-one; 2,3-dihydro-2-phenylbenzopyran-4-one; it is the 4-oxo derivative of **flavan** and the 2,3-dihydro derivative of **flavone**. **2** any of a group of hydroxylated derivatives of flavanone. Flavanone glycosides are colourless; they are found in flowering plants and form one of the classes of **flavonoid** (def. 1).



flavin *or (formerly)* **flavine** *the stem name and trivial name for* any member of a group of yellow-coloured, 10-substituted derivatives of 7,8-dimethylisoalloxazine, as in **riboflavin**, **flavin-adenine dinucleotide**, etc.

flavin-adenine dinucleotide *abbr.*: FAD; adenosine diphosphate riboflavin; adenosine(5′)diphospho(5′)riboflavin; riboflavin 5′-(adenosine 5′-diphosphate); 7,8-dimethyl-10-[5-(adenosine(5′)-diphospho)-D-ribityl]isoalloxazine; an atypical dinucleotide, not only in that it contains, as does **nicotinamide-adenine dinucleotide**, a phosphoric anhydride linkage between the component mononucleotide units, which in this instance are **adenosine 5′-phosphate** and **flavin mononucleotide**, but also because the latter is not strictly a nucleotide in any case, although considered as one (*see* **nucleotide** (def. 3)). It forms the coenzyme or the prosthetic group of various flavoprotein oxidoreductase enzymes, in which it functions as an electron acceptor by being reversibly converted to **flavin-adenine dinucleotide (reduced)**. *See also* **riboflavin**.



flavin-adenine dinucleotide (reduced) *abbr.*: $FADH_2$; adenosine diphosphate dihydroriboflavin; 1,5-dihydro-7,8-dimethyl-10-[5-(adenosine(5′)diphospho)-D-ribityl]isoalloxazine. The reduction occurs at the two unprotonated nitrogen atoms at positions 1 and 5 of FAD. *see* **flavin-adenine dinucleotide**.

flavin coenzyme a general name sometimes used for a **flavin nucleotide** when not covalently linked to an apoenzyme.

flavin enzyme *see* **flavoenzyme.**

flavin mononucleotide *abbr.*: FMN; riboflavin 5′-phosphate, 7,8-dimethyl-10-(5-phospho-D-ribityl)isoalloxazine. Although not strictly a mononucleotide, since it contains an alditol moiety rather than a glycose moiety, it nevertheless is considered as one (*see* **nucleotide** (def. 3)), and as such is a component of **flavin-adenine dinucleotide**. It forms the coenzyme (or occasionally the prosthetic group) of various flavoprotein oxidoreductase enzymes, where it functions as an electron acceptor by being reversibly converted to **flavin mononucleotide (reduced)**. *See also* **riboflavin**.



flavin mononucleotide (reduced) *abbr.* $FMNH_2$; dihydroriboflavin 5′-phosphate, 1,5-dihydro-7,8-dimethyl-10-(5-phospho-D-ribityl)isoalloxazine. The reduction occurs at the two unprotonated nitrogen atoms at positions 1 and 5 of FMN. *See* **flavin mononucleotide**.

flavin nucleotide a general name sometimes used for flavin-adenine dinucleotide and flavin mononucleotide, and their reduced forms.

flavin reductase *(in luminescent bacteria)* the product of the *luxG* gene in several marine luminescent bacteria. It is presumed from sequence similarity to be an FAD/NAD(P) flavoprotein oxidoreductase.

flavo+ *comb. form* **1** yellow. **2** containing a **flavin nucleotide**.

flavocytochrome any protein that is both a **flavoprotein** and a **cytochrome.** Examples include: (1) yeast L-lactate dehydrogenase (cytochrome), (EC 1.1.2.3), also known as **cytochrome b_2**; and (2) *Bacillus megatherium* flavocytochrome P450 BM3, a fatty acid hydroxylase (119 kDa).

flavodoxin any of a group of small protein electron carriers, widely distributed in cyanobacteria and anaerobic- and photosynthetic bacteria, that contain covalently-linked flavin mononucleotide. They readily form stable blue semiquinones, and can substitute functionally for **ferredoxin**.

flavoenzyme *or* **flavin enzyme** any of a large group of yellow **flavoprotein** enzymes that contain FAD or FMN as cofactor. They frequently have an α/β barrel topology.

flavolans *see* **tannin**.

flavone **1** 2-phenylchromen-4-one; 2-phenyl-4*H*-1-benzopyran-4-one; a potent inhibitor of **prostaglandin-endoperoxide synthase**. **2** any of a group of hydroxylated derivatives of flavone. Flavone glycosides occur as pigments, usually yellow, in flowering plants and form one of the classes of **flavonoid** (def. 1). *Distinguish from* **flavanone**.



flavonoid **1** any of a very large and widespread group of water-soluble phenolic derivatives, often brightly coloured and usually found in the vacuoles of plant cells. They are glycosides with the structures of their aglycon moieties based on the **flavan** skeleton, and are classified according to the oxidation state of its pyran ring. Some 10–12 classes are recognized. **2** any flavone, isoflavone, or neoflavone, or any of their derivatives, including bioflavonoids. *See also* **apigenin**, **myricetin**, **quercetin**. **3** of, relating to, or resembling flavone, isoflavone, or neoflavone.

flavonol **1** 3-hydroxyflavone. **2** any of a group of hydroxylated derivatives of flavonol. Flavonol glycosides occur as pigments, usually yellow, in flowering plants, and form one of the classes of **flavonoid** (def. 1). *Distinguish from* **flavanol**.



flavopiridol a chlorinated flavone, which is a potential anti-cancer therapeutic agent. It inhibits Cdk1,Cdk2 and Cdk4. The drug docks in the ATP binding site. The crystal structure of the flavone attached to Cdk2 has been determined. The flavone is derived by chemical synthesis from a parent structure obtained from *Dysoxylum binectariferum* a plant native to India.

flavopiridol a chlorinated flavone, which is a potential anti-cancer therapeutic agent. It inhibits Cdk1,Cdk2 and Cdk4. The drug docks in the ATP binding site. The crystal structure of the flavone attached to Cdk2 has been determined. The flavone is derived by chemical synthesis from a parent structure obtained from *Dysoxylum binectariferum* a plant native to India.

flavoprotein *abbr.*: FP; any enzyme or other protein of which a flavin nucleotide is a coenzyme or prosthetic group. They occur in virtually all cells, where they act as oxidoreductases or as electron carriers in the terminal electron transport chains.

Fletcher factor *see* **plasma kallikrein**.

flexible linker a sequence of amino acids that is structurally flexible, allowing the domains either side of it to move relative to each other. Linker regions are often disordered in protein crystal structures.

flg *see* **fibroblast growth factor receptor**.

flickering cluster model a model for the structure of liquid water in which small, tetrahedrally coordinated, icelike regions, held together by hydrogen bonds, are thought to exist for short periods, continually breaking up and re-forming.

flightin the enzyme **glycerol 3-phosphate dehydrogenase (NAD^+)** obtained from certain insects. It is so called because this and mitochondrial **glycerol 3-phosphate oxidase** play a major role in the transfer of energy needed for flight in insects.

FLIM *abbr. for* fluorescence lifetime imaging microscopy; a technique that depends on the fact that each fluorescent dye has its own lifetime in the excited state, so that different dyes with the same fluorescent colour can be distinguished. Fluorescence lifetime is influenced by concentration and by molecular interactions such as occur in **FRET**.

FLIM-FRET a technique that makes it possible to measure the interaction between two proteins labelled with a pair of fluorescent dyes. **FRET** reduces the fluorescence lifetime of the donor fluorophore and therefore can be detected by donor fluorescence alone using **fluorescence lifetime imaging microscopy.** Experiments can be carried out with saturating amounts of acceptor molecules since acceptor fluorescence is not detected.

flip-flop **1** *(in electronics)* a circuit or device having two stable states and two inputs corresponding to these states. The device remains in either state until caused to change to the other state by application of an appropriate signal to the inputs. **2** *(in enzymology)* a mechanism in which a functional interrelationship between distinct active sites on identical monomers, which are parts of an oligomeric enzyme showing Michaelian kinetics, is mediated by a structural modification, the **flip-flop transition**. *Compare* **half-of-the-sites reactivity**. **3** *(in genetics) the informal name for* a reversible, reciprocal exchange between recombining segments of DNA in site-specific recombination systems in prokaryotes or eukaryotes. *See also* **transposable element**. **4** *(in lipid biochemistry)* the passage of phospholipid molecules from one leaflet of a membrane to the other.

flippase EC 3.6.3.1 a protein that binds a phospholipid molecule on one leaflet of a membrane and transports it to the other leaflet, with hydrolysis of ATP.

flipping **1** *a jargon term used in* **nuclear magnetic resonance spectroscopy** *for* the change in orientation of an atomic nucleus from an angle $\theta°$ to $(180 - \theta)°$, with respect to the direction of the magnetic field, caused by absorption of radiation energy of a specific radiofrequency. **2** The rotation of a protein with associated phospholipid from one leaflet of a membrane to the other.

flocculate to aggregate or cause to aggregate into ‘woolly’ clusters or masses.

flocculation **1** the act or process of flocculating (*see* **flocculate**). **2** the product of such an act or process.

flocculation reaction *or* **flocculation test** a **precipitin test** in which the precipitate appears as floccules.

floccule a small aggregated mass of flocculent material.

flocculent **1** having the appearance of wool or down. **2** *(in chemistry)* consisting of or occurring as small woolly or downy aggregates. 3 *(in biology)* covered with waxy flakes or tufts resembling wool.

flora 1 *collective term for* all the plants, or plant life, characteristic of a given place or period. 2 microbial flora; the microbial population of part of the body, e.g. of the gut, skin, etc. 3 a comprehensive treatise or list of all the plants or plant life of a particular region or period.

Florisil *the proprietary name for* a type of activated magnesium silicate. It is an adsorbent and is useful for column chromatographic separation of lipids.

flotation coefficient a name sometimes given to a negative **sedimentation coefficient**.

flotillin an integral membrane protein associated with caveolae and present primarily in the developing nervous system.

flow birefringence *or* **double refraction of flow** the **birefringence** induced in a fluid by shear, which causes orientation of any asymmetric molecules in the fluid.

flow cabinet another name for **safety cabinet**.

flow cell any **cell** (def. 2) so constructed that appropriate measurements (as of absorbance) may be made on a flowing fluid.

flow cytofluorimeter a **flow cytometer** in which fluorescence of the objects being counted is monitored.

flow cytometer an apparatus for **flow cytometry** in which cells, or subcellular components (e.g. isolated chromosomes), in aqueous suspension are made to flow at high speed, in single file, through a sensing region where optical or electric signals indicative of some important physical or chemical properties of the cells, or components, are generated. These signals are analysed and accumulated in a computer for quantitative evaluation. Typical flow rates that can be achieved are in the region of 1000 cells per second. *See also* **flow sorter**, **fluorescence-activated cell sorter**.

flow cytometry the technique for counting or measuring some property of cells, or subcellular components, using a **flow cytometer**, often after labelling with a fluorescent marker.

flow dichroism **dichroism** (def. 1) induced in a fluid by shear, which causes orientation of any asymmetric molecules in the fluid.

flower the reproductive structure of angiosperm plants. It consists generally of sepals, petals, and stamens and/or carpels. It is basically a highly modified leafy shoot.

flow-signal *an earlier term for* **rheoseme**.

flow sorter (for cells) a **flow cytometer** to which has been added a device for physically separating cells, or subcellular components, of desired characteristics in order to provide subpopulations of high homogeneity. Typically the cell suspension is forced out of an orifice, 50–100 μm in diameter, forming a high-speed liquid jet in air. Optical sensing of the jet takes place near the orifice and the jet is then broken up into uniform droplets by applied ultrasonic vibration. The droplets then traverse a region of high-intensity constant electric field where the decision-making and charging circuits, activated by the sensors, cause only droplets containing the wanted cells to be charged and deflected by the electric field into a separate collector.

FLP recombinase a yeast enzyme that catalyses site-specific recombination of double-stranded DNA at a 34-nt sequence called the FLP recombinase target (FRT) site. If two FRT sites are facing in the same direction the DNA between them is excised and the flanking sequences joined.

fluctuation test a method of statistical analysis used to determine whether selected variants, e.g. phage- or drug-resistant bacterial mutants, arose spontaneously prior to exposure to the selective agent or were caused by the agent.

fludrocortisone 9*α*-fluorohydrocortisone (11*β*)-9-fluoro-11,17,21-trihydroxypregn-4-ene-3,20-dione; a **corticosteroid** with about 10 times the glucocorticoid action of cortisol, but with 300–600 times greater mineralocorticoid action. It is used topically in ointments.



fludrocortisone

fluence *symbol*: *F or H*; *(in photochemistry)* the energy delivered in a given time interval, d*t*; $F = \int I\mathrm{d}t$ where *I* is the radiant intensity and *t* is time. It is expressed in $\mathrm{J\ m^{-2}}$.

fluence rate **fluence** per unit time; it is commonly referred to (strictly incorrectly) as **flux**.

fluid 1 any substance that can flow; any portion of matter in which the components (molecules or particles) continuously change their relative positions. In physics, the term comprehends any liquid or gas; in biology (and in common usage) it generally denotes only a liquid, especially one present in, or secreted by, a living organism. 2 able to flow or to change shape easily; not solid or rigid; liquid. 3 of, concerned with, or using fluid, a fluid, or fluids.

fluidity *(in physics)* the reciprocal of the **viscosity** of a fluid.

fluid mosaic model a model of cell-membrane structure in which the proteins that are integral to the membrane are considered as a heterologous set of globular molecules, each arranged in an amphipathic structure, i.e. with their ionic and highly polar groups protruding from the membrane into the aqueous phase and their nonpolar groups largely buried in the hydrophobic interior of the membrane. These globular molecules are partially embedded in a matrix of phospholipid, the bulk of which is organized as a discontinuous, fluid bilayer, although a small fraction of the lipid may interact specifically with the membrane proteins. Thus the fluid mosaic structure is formally analogous to a two-dimensional oriented solution of integral proteins (or lipoproteins) in a viscous phospholipid bilayer solvent.

Fluon *a proprietary name for* **polytetrafluorethylene**.

fluor *or* **lumiphor** *or* **scintillator** any substance that displays **fluorescence** when excited by electromagnetic or particulate radiation. Fluors are useful especially in **scintillation counters**.

fluor+ *a variant form of* **fluoro+** (sometimes before a vowel).

fluoracetate *see* **fluoroacetate**.

fluorenylmethoxycarbonyl *symbol*: Fmoc; *abbr.*: FMOC; fluoren-9-ylmethoxycarbonyl; a group used for linkage to amino groups for the purpose either of forming fluorescent amino-acid derivatives that can readily be detected after column chromatography, or to protect the amino groups of amino acids or nucleotides while other functional groups are undergoing reaction. Reagents useful for introducing the group are 9-fluorenylmethyl chloroformate and 9-fluorenylmethyl succinimidyl carbonate.



fluorescamine 4-phenylspiro[furan-2(3*H*),1′-(3′*H*)-isobenzofuran]-3,3′-dione; a nonfluorescent compound forming fluorescent structures on reaction with primary amines. *Proprietary name*: Fluram.



fluorescein 9-(2-carboxyphenyl)-6-hydroxy-3*H*-xanthen-3-one; Acid Yellow 73; CI 45350; an orange-red dye, the sodium salt of which is freely soluble in water to give a solution with yellowish-green fluorescence (to a dilution of 0.02 ppm) under UV light. Certain derivatives, e.g. fluorescein isothiocyanate, are useful for **fluorescein labelling** and others, e.g. the nonfluorescent fluorescein diacetate, are useful as substrates for the detection and assay of esterases.



fluorescein labelling the introduction of fluoresceinyl groups (*see* **fluorescein**) into biopolymers for fluorescence polarization studies and fluorescence immunoassay techniques.

fluorescence 1 a type of luminescence that consists of the emission by a substance of electromagnetic radiation, especially visible light, as a result of and immediately (10–100 ns) after the absorption of energy derived from exciting radiation of another, usually shorter, wavelength or from incident subatomic particles (especially electrons or alpha particles); the property of emitting such radiation. **2** the radiation emitted during **fluorescence** (def. 1). *Compare* **phosphorescence**. **—fluorescent**, **fluorescing** *adj.*; **fluoresce** *vb.*

fluorescence-activated cell sorter *or* **fluorescence-assisted cell sorter** *abbr.*: FACS; a type of **flow sorter** in which cells are characterized and sorted by the intensity of the fluorescence they emit when passing through an exciting laser beam.

fluorescence depolarization *or* **depolarization of fluorescence** the phenomenon occurring when fluorescence is excited by plane polarized radiation; the emitted radiation is always partially depolarized (*see* **fluorescence polarization**). The extent of such depolarization is due, *inter alia*, to the motion of the absorber (i.e. Brownian motion) and to energy transfer between like chromophores. Fluorescence depolarization can be used to follow the changes in the motion (rotation) of an entire macromolecule, or of a part of the molecule, to which fluorescent chromophores are attached; it can also be used to indicate the environment of a **fluorescent probe** in, e.g., a membrane – an environment that results from less tightly packed structures permits greater movement of the probe molecule, thus leading to greater depolarization. *See also* **photon counter**, **time-resolved fluorescence polarization**.

fluorescence energy transfer a process of energy transfer between two **fluorophors**, which can occur when the emission spectrum of the first fluorophor overlaps the absorption spectrum of the second fluorophor. **Quenching** of the emission from the first compound occurs but the excitation energy is absorbed by the second compound, which then emits its own characteristic fluorescence. If the two fluorophors are attached at different positions to a macromolecule, observations of fluorescence energy transfer between them may be used to determine the distance between the two attachment positions.

fluorescence enhancement *or* **enhancement of fluorescence** a phenomenon occurring with a number of **fluorophors** whose fluoresence is markedly dependent on the polarity of the medium, in which fluorescence is greatly enhanced in a nonpolar or rigid environment, but strongly quenched in an aqueous environment. Examples are 8-anilinonaphthalene sulfonate (**ANS**) when bound to an antibody or trapped in the hydrophobic environment within a protein; and ethidium when intercalated into double-helical regions of a nucleic acid.

fluorescence immunoassay *or* **fluorescent immunoassay** *or* **fluoroimmunoassay** *abbr.*: FIA; a method of assaying very small amounts of material that is similar in principle to **radioimmunoassay** but uses a fluorescent rather than a radioactive label for the antigen. Various techniques can be used for determination of the ratio of bound to free labelled antigen that do not necessitate a separation of the two; these may depend instead on **fluoresence energy transfer**, **fluorescence enhancement**, **fluorescence depolarization**, **fluorescence quenching**, or other phenomena.

fluorescence *in situ* hybridization *abbr.*: FISH; a procedure that involves the use of DNA probes to locate in a tissue section specific regions of DNA in the chromosomes. The probes are tagged with a selection of fluorescent molecules that are both excited by and emit light of different wavelengths and hence different colours. The structure and behaviour of individual chromosomes at all stages of the cell cycle can thereby be studied.

fluorescence lifetime imaging microscopy *see* **FLIM**.

fluorescence microscopy a type of light microscopy by means of which fluorescent substances in a specimen may be detected and examined. Exciting light, commonly UV and of appropriate wavelengths, is isolated by means of a suitable filter placed between the light source and the condenser, and emitted radiation is selected by a different filter placed between the objective lens and the eye-piece. The technique is useful for visualizing certain components that are difficult to see by direct light, for localizing fluorescent substances bound to specific components of the specimen, and for determining the orientation of a specimen using the **fluorescence depolarization** technique.

fluorescence photobleaching recovery *an alternative name for* **fluorescence redistribution after photobleaching**.

fluorescence polarization *or* **polarization of fluorescence** the phenomenon that the light emitted from a fluorescent molecules is always partially polarized. This is true whether or not the exciting radiation is plane polarized. In consequence, when plane polarized radiation is used to excite fluorescence, **fluorescence depolarization** occurs.

fluoresence probe *or* **fluorescent probe** any small molecule that undergoes changes in one or more of its fluorescence properties as a result of noncovalent interaction with a protein or other macromolecular structure. Such probes are useful for studying the properties and behaviour of macromolecules. *See* **probe** (def. 1).

fluorescence quantum yield in any fluorescent system, the ratio of the number of photons emitted to the number of photons absorbed; the fraction of excited singlets that become de-excited by fluorescence. *See also* **quantum yield** (def. 1).

fluorescence quenching the reduction in the **fluorescence quantum yield** of a system due to de-excitation of the fluorescent molecules by environmental factors such as collision or complex formation with quenchers in the system, or by **fluorescence energy transfer** to them. The phenomenon is useful in studies of the binding of small molecules to proteins and other macromolecules.

fluorescence redistribution after photobleaching *abbr.*: FRAP; a technique, also termed **fluorescence photobleaching recovery**, for measuring two-dimensional lateral mobility of fluorescent particles in small (≈10 μm^2) regions of a cell surface. A small spot on the surface is photobleached by a brief exposure to an intense, focused laser beam, and the subsequent recovery of fluorescence, due to replenishment of intact fluorophor in the bleached spot by lateral transport from the surrounding surface, is followed.

fluorescence resonance energy transfer *abbr.*: **FRET**; *see* **Forster transfer**.

fluorescence spectrophotometry the measurement, by means of a **spectrofluorometer**, of the wavelengths and the intensities of the light emitted from a fluorescent sample that is excited by more or less monochromatic exciting radiation.

fluorescence spectrum the **emission spectrum** of a fluorescent system that is excited by radiation of a given wavelength. *Compare* **excitation spectrum**.

fluorescent antibody technique an **immunofluorescence** technique in which antibody conjugated with a fluorophor is used to locate corresponding antigen in tissue sections or smears.

fluorescent immunoassay *a variant spelling of* **fluorescence immunoassay**.

fluorescent probe *a variant spelling of* **fluorescence probe**.

fluorescent screen a screen coated with a substance, e.g. zinc sulfide or calcium tungstate, that fluoresces when irradiated with electromagnetic radiation of certain wavelengths or with particulate radiation.

fluori+ *a variant form of (sometimes before a vowel)* **fluoro+**.

fluoridation the addition of up to approximately 1 ppm of fluoride ion to a drinking water supply with the object of reducing tooth decay in consumers of the water. —**fluoridate** *vb.*

fluorimeter *a variant spelling of* **fluorometer**.

fluorinate 1 to treat or react (a substance) with difluorine. **2** to introduce (one or more) fluorine atoms into (a molecule of an organic compound), whether by addition or by substitution. —**fluorinated** *adj.*; **fluorination** *n.*

fluoro+ *or (sometimes before a vowel)* **fluor+** *comb. form* **1** denoting a fluorine in organic linkage. **2** *or* **fluori+** indicating fluorescence.

fluoroacetate the anion of fluoroacetic acid (= fluoroethanoic acid); a toxic substance found in the leaves of *Dichapetalum cymosum* and other plants that in animals is converted enzymically into **fluorocitrate**. Fluoroacetate and fluoroacetamide have been used as rodenticides.

fluorochrome any substance exhibiting fluorescence, especially one used to impart fluorescence to another molecule or to a specific structure in a biological specimen.

fluorocitrate the trianion of 1-fluoro-2-hydroxy-1,2,3-propanetricarboxylic acid; an extremely toxic substance formed in animal tissues from fluoroacetate. Fluorocitrate is a potent inhibitor of aconitase; it is believed that the fluorine atom interacts strongly with the Fe^{2+} ion at the active centre of the enzyme thereby inhibiting its activity. *See also* **lethal synthesis**.

fluorodeoxyuridine *see* **fluorouracil**.

fluorodeoxyuridylate *see* **fluorouracil**.

fluorodinitrobenzene *see* **Sanger's reagent**.

fluorogen the nonfluorescent precursor of a **fluorophor**.

fluorogenic 1 producing fluorescence. **2** of or pertaining to a **fluorogen**; e.g. a fluorogenic substrate is a nonfluorescent material that can be acted on by an enzyme to produce a fluorescent substance.

fluorogram 1 *or (sometimes)* **autofluorogram** an autographic image derived by **fluorography** (def. 1). **2** *or* **fluorograph** a photographic image produced by **fluorography** (def. 2).

fluorography 1 *or* **autofluorography** *or* **scintillation autography** *or* **scintillation autoradiography** an elaboration of autoradiography that shows a considerable increase in the efficiency of detection of low-energy-beta-particle-emitting nuclides, e.g. carbon-14, sulfur-35, and (especially) tritium, in preparations such as thin-layer chromatograms, gel electrophoretograms, tissue or whole-body sections, etc. The otherwise poor response of autoradiography in these situations results from internal absorption of most of the emitted radiation by the specimen in question. In fluorography this effect is diminished by impregnating the specimen (which preferably should be translucent and colourless) with fluor(s) prior to placing it in contact with an appropriately sensitive photographic emulsion or film, which then responds both to direct emission of beta particles from the specimen and to emission of photons of UV light (scintillations) generated by beta particles, exciting the fluor within the specimen. **2** photography of a fluorescent body, especially of an image on a fluorescent screen. —**fluorograph** *n.*, *vb.*; **fluorographic** *adj.*

fluoroimmunoassay *abbr.*: FIA; *a variant spelling of* **fluorescence immunoassay**.

fluorometer *or* **fluorimeter 1** a device for measuring the intensity and duration of fluorescence. **2** a device that may be attached to a **fluoroscope** to enable the position of a sought object to be determined with precision. —**fluorometric** *or* **fluorimetric** *adj.*; **fluorometry** *or* **fluorimetry** *n.*

5-fluoroorotic acid *abbr.*: 5-FOA; a substrate for orotidine-5′-phosphate decarboxylase, which converts it to 5-fluorouracil, an inhibitor of DNA synthesis. In yeast genetics it is used to select for strains lacking a functional ***ura3*** gene.

fluorophor *or* **fluorophore 1** a group of atoms in a molecule that renders the latter fluorescent. **2** a fluorescent substance.

fluoroscope 1 a screen coated with a substance that fluoresces when excited by X-rays; it is used to view the X-ray image of an object. **2** a device used to compare the fluorescence of a solution with that of a standard.

fluorouracil *symbol*: FUra (*not* FU); 5-fluorouracil; 5-fluoro-2,4(1*H*,3*H*)-pyrimidinedione; a synthetic analogue of uracil that is enzymically converted via its β-D-ribofuranoside, fluorouridine (*symbol*: FUrd), to fluorodeoxyuridine (*symbol*: FdUrd) and then to fluorodeoxyuridylate, which is a potent inhibitor of **thymidylate synthase** and, hence, of DNA synthesis. Thus fluorouracil is a **suicide inactivator** of thymidylate synthase. Fluorouracil and fluorodeoxyuridine are anticancer drugs, commonly used in combination therapy against fast-growing tumours.

fluoxetine (±)-*N*-methyl-γ-[4-(trifluoromethyl)phenoxy]benzenepropanamine; a serotonin uptake inhibitor, used as an antidepressant, particularly as the hydrochloride (*proprietary name*: Prozac).



* = racemic

flush end *or* **blunt end** an end of a duplex DNA fragment in which the two strands are coextensive, i. e. terminate at the same point. Such ends may be formed by scission of duplex DNA with some types of endonucleases. *Compare* **cohesive end**. —**flush-ended** *adj.*

flux 1 the rate of passage of energy or matter (usually in crossing a given area or passing through a given volume) under steady-state conditions. *See* **diffusion coefficient**, **luminous flux**, **radiant power**. **2** the number of particles passing through unit cross-sectional area of beam per unit time. **3** the rate of (chemical or physical) transformation of a substance within a living cell or tissue; the rate of translocation of a substance within a living cell or tissue, especially across a cell membrane. Such processes are usually measured in moles per second. *See also* **metabolic flux**. **4** the strength of a field of force orthogonal to unit area. *See* **magnetic flux**. **5** *an alternative term for* **flux density** (def. 2).

flux control coefficient *symbol*: $C_{\mathrm{E}}{}^{J}$; in a metabolic sequence at steady state, the response, δ*J*, of the original system flux, *J*, to a small change, δE, in either the concentration or one of the kinetic parameters of a specified enzyme, E; it is given by:

$$C_{\mathrm{E}}^{J} = \left(\frac{\partial J/J}{\partial E/E}\right) p, q, r, \ldots$$

and similarly for every other enzyme in the system. This is the flux control coefficient of the enzyme E on the flux *J,* and is also called **sensitivity coefficient** or **control strength**. Similarly one can calculate a flux control coefficient for the substrate concentration, *S*, on the flux, *J* (this is also called **sensitivity** or **net sensitivity**) and a flux control coefficient of an effector concentration, *I*, on the flux, *J* (this is also called **control strength**).

flux density 1 (of energy or field strength) the **flux** per unit cross-sectional area; *see* **luminous flux density**, **magnetic flux density**. **2** *or (sometimes)* **flux** (of particulate radiation, including photons) the arithmetic product of the particle density and the mean velocity of the particles; **neutron flux (density)**.

fluxional describing a chemical species that undergoes rapid degenerate rearrangements, generally detectable by methods such as nuclear magnetic resonance or X-ray crystallography.

flux-ratio method a method for investigating the mechanisms of enzymic reactions in which simultaneous measurements are made of the rates of enzyme-catalysed isotopic transfers from one product to two substrates while the reaction system is in a steady state. It provides relatively unambiguous information about the order of binding of substrates.

FlyBase *see* **genome database**.

Fm *symbol for* fermium.

fMet *symbol for* a residue of the α-acylamino acid *N*-formyl-L-methionine.

FMN *abbr. for* flavin mononucleotide.

FMN adenylyltransferase EC 2.7.7.2; *other name*: FAD pyrophosphorylase; an enzyme of the pathway for biosynthesis of FAD. It catalyses the reaction of ATP with FMN to form FAD with release of pyrophosphate.

FMNH$_2$ *symbol for* flavin mononucleotide (reduced).

Fmoc *symbol for* the fluorenylmethyloxycarbonyl group.

FMOC *abbr. for* the fluorenylmethyloxycarbonyl group.

fmol *symbol for* femtomole (10^{-15} mole).

FMR1 *symbol for* fragile site mental retardation 1 gene; a genetic locus on the X chromosome (Xq27.3) involved in fragile X syndrome, the most common form of inherited mental retardation affecting males. Mutations take the form of expanded triplet repeats $(CGG)_n$, or $(CCG)_n$ on the complementary strand. *See also* **FMRP**.

FMRP *abbr. for* fragile X mental retardation protein; any isoform of a protein (the longest contains 655 amino acids) generated by alternative splicing of the product encoded by the gene at Xq27.3, which is associated with fragile X syndrome. Expressed mostly in brain and testis, FMRP contains RNA-binding sequences (called KH domains) and clusters of the tripeptide sequence RGG. It is localized mostly to ribosomes active in translation and appears to shuttle between cytoplasm and nucleus. In the syndrome the number of the CGG trinucleotide repeat in the 5′ untranslated region of the mRNA expands from <60 to >200.

FMS *symbol for* either the retroviral **oncogene**, v-*fms*, which is carried by the McDonough strain of feline sarcoma virus, or its related protooncogene, c-*fms*, which encodes the M-CSF-1 receptor precursor (*see* **colony stimulating factor**). The latter is a type I transmembrane protein of the immunoglobulin superfamily. It possesses intrinsic protein tyrosine kinase activity within its cytoplasmic domain, which is activated by the binding of CSF-1 (*see* **colony stimulating factor**) to the extracellular domain. Its transforming counterpart, v-*fms*, encodes a constitutively active receptor kinase that can transform both fibroblasts and hematopoietic cells in a CSF-1-independent manner. Mutations in the c-*fms* gene as well as a critical alteration of the 3′ coding sequences appear to be responsible for fully activating its latent transforming potential. In the v-*fms* protein product, 40 C-terminal amino acids of the normal CSF-1 receptor are replaced by 11 unrelated residues, suggesting that residues near the C terminus normally negatively regulate kinase activity in the absence of CSF-1.

f-number the numerical value of the relative aperture of a lens; it is the ratio of the focal length of a lens to its diameter.

foam **1** a dispersion in which a large proportion of gas by volume, in the form of gas bubbles usually >1 µm in diameter, is dispersed in a liquid, solid, or gel. **2** to produce or cause to produce such a foam.

foam fractionation a method of separation in which a component of the bulk liquid is preferentially adsorbed at the liquid/vapour interface and is removed by foaming.

foaming agent a **surfactant** that when present in small amounts facilitates the formation of a foam and/or stabilizes it.

focal adhesion kinase *abbr*.: FAK; a highly conserved, cytosolic, protein-tyrosine kinase involved in cell–cell and cell–matrix interaction and responsible for formation of the focal adhesion complex. It is widely expressed throughout development. FAK contains an N-terminal integrin-binding domain, a central kinase domain, two proline-rich sequences, and others for targeting to focal adhesions.

focal contact *or* **focal adhesion** any of the areas on the surface of fibroblasts or other cells that are anchored to extracellular matrix where actin-containing microfilaments terminate. The contact is mediated by transmembrane proteins such as integrins, which are then linked to actin microfilaments in the cytoplasm. The filaments are involved both in the attachment of the cells to the substrate and in cell movement.

fodrin *or* **brain spectrin** *or* **calspectin** a protein from bovine brain, immunologically related to **spectrin**, that is involved in secretion, interacts with calmodulin in a calcium-dependent manner, and thus is a candidate for the calcium-dependent movement of the cytoskeleton at the membrane. It contains 20 repeats of a 106-amino-acid domain.

foetal *a variant spelling of* fetal (*see* **fetus**).

foeto+ *a variant spelling of* **feto+**.

foetus *an etymologically misconceived variant spelling of* **fetus**.

FOG1 *abbr. for* friend of GATA-1; a transcription regulator protein that binds the erythroid gene-specific transcription factor GATA-1. It contains four C_2H_2 and five CCHC zinc fingers.

***Fok*I** a type 2 **restriction endonuclease**; recognition sequence: GGATGNNNNNNNNN↑.

folacin *a common name for* **folic acid**.

folate **1** *the recommended trivial name for* pteroylglutamate; *N*-[4-[(2-amino-3,4-dihydro-4-oxopteridin-6-yl)methyl]amino benzoyl]-L-glutamate; the anion of **folic acid** (def. 1). **2** any member of the family of pteroylglutamates, irrespective of the level of reduction of the pteridine ring, of the nature of any one-carbon substituent, and of the number of glutamate residues. *See also* **folic acid** (def. 2).



folate-binding protein *or* **folate receptor** (*abbr*.: FR); either of two GPI-anchored membrane glycoproteins that bind folate with high affinity. FRα and FRβ are encoded by a gene at 11q13.3-q13.5 and have similar coding regions. They provide entry into cells for folate by receptor-mediated endocytosis.

folate coenzyme any of various interconvertible tetrahydrofolates that bear a one-carbon substituent and function as coenzymes in metabolic reactions involving the transfer of one-carbon units. The substituent may be 5-formimino, 5-formyl, 10-formyl, 5,10-methenyl, 5-methyl, or 5,10-methylene.

folate receptor *an alternative term for* **folate-binding protein**.

Folch–Lees protein the most abundant type of protein that is extractable from central-nervous-system myelin by chloroform: methanol (2:1 v/v); it is of at least 150 kDa, and contains a high proportion of aliphatic amino acids. *Compare* **Wolfgram proteolipid protein**.

Folch method a method for the fractionation and isolation of lipids from either tissues or fluids. It involves extraction with various chloroform–methanol–water mixtures.

fold a qualitative decription of a protein tertiary structure; folds are classified using different criteria in various **structure classification databases**.

foldase an enzyme, such as peptidyl proline isomerase or disulfide isomerase, that catalyses isomerization of a polypeptide conformation or exchange of disulfide-bond partners, to facilitate protein folding.

foldback DNA *an alternative term for* hairpin DNA. *See* **hairpin**.

folding problem the problem of determining how a protein folds into its final 3D form given only the information encoded in its primary structure.

folding unit a locally ordered region within the core of a protein molecule, formed by 3-D interaction between two or three segments of secondary structure (α-helix and/or β-strand) that are near one another along the polypeptide chain. Examples are: (αα), (αβ), (βββ), (βαβ). *See also* **domain**.

fold recognition a method for predicting protein tertiary structure that detects 3D folds that are compatible with a particular sequence by comparing the probe sequence with known fold templates housed in a fold library. The most likely match is detected using statistical scoring functions (e.g. solvation potentials or pair potentials), predicted secondary structure, sequence profile information, and so on.

fold template a representative known protein fold stored in a library for use in **fold recognition**.

folic acid *abbr.*: (not recommended) FA *or* F; **1** *the recommended trivial name for* pteroylglutamic acid, the corresponding acid of **folate** (def. 1). **2** *or* **folacin** the name under which any **folate** (def. 2) is generally known in medicine, nutrition, etc. Folic acids are widely distributed members of the vitamin B complex, particularly plentiful in green leafy vegetables, liver, and yeast. Folates are essential for the synthesis of purines and pyrimidines, functioning as carriers of one-carbon units. A deficiency in humans results in megaloblastic anemia and in birth defects in children born to deficient mothers. Folic acids are also growth factors for certain microorganisms. *See also* **folinic acid**.

folic acid conjugate the corresponding acid of any **folate** (def. 2) containing two or more glutamyl residues.

folic acid reductase *an alternative name for* **dihydrofolate reductase**.

Folin–Ciocalteau reagent a phosphomolybdotungstic acid reagent that gives a blue colour with phenols. The reagent has been used in the determination of tryptophan and tyrosine in proteins and peptides. *See also* **Lowry method**.

folinic acid **1** *or (formerly)* **citrovorum factor** (*abbr.*: CF) *or (formerly)* **leucovorin** *or* **5-formyltetrahydrofolic acid** 5-formyl-5,6,7,8-tetrahydropteroyl-L-glutamic acid; the common name for the corresponding acid of **folinate** (5-formyltetrahydrofolate), a folate coenzyme discovered to be a growth factor for the bacterium *Leuconostoc citrovorum* (hence its former synonyms). Folinate is an intermediate in the metabolic conversion of formiminoglutamate pppnpn to glutamate, ammonium, and **active one-carbon**. The calcium salt, calcium folinate (*or formerly* calcium leucovorin), is useful therapeutically, e.g. as an antidote to doses of methotrexate or other folate antagonists. **2** *name sometimes used for* certain other folates, e.g. tetrahydrofolate, especially as growth factors for microorganisms.

Folin–Lowry method a sensitive method of protein assay in which protein reacts both with an alkaline copper tartrate solution and with the **Folin–Ciocalteu reagent** to give a blue colour, the absorbance of which is measured at 750 nm. *Compare* **Lowry method**.

Folin reaction a colorimetric reaction used for the determination of ammonia and amino-acid nitrogen in which a red colour is produced when an alkaline solution of amino acids is treated with 1,2-naphthoquinone-4-sulfonate. [After Otto Knute Olof Folin (1867–1934).]

Folin–Wu reagent a phosphomolybdic acid solution, containing a little tungstate, used in the determination of glucose. It gives a blue colour with the copper (I) oxide produced when the sample containing glucose is heated with an alkaline copper (II) solution. [After Otto Knute Olof Folin (1867–1934) and Hsien Wu (1893–1959).]

folliberin *the recommended name for* follicle-stimulating hormone releasing hormone (*abbr.*: FSH-RH or FRH). Luteinizing hormone releasing hormone (*abbr.*: LHRH) stimulates not only release of luteinizing hormone from the anterior pituitary but also release of follicle-stimulating hormone. This activity is commonly named **gonadotropin-releasing hormone**. There is, however, evidence that a specific FSH-RH may exist in addition.

follicle **1** any small cavity or recess. **2** a cavity that has a secretory or excretory function, e.g. the **Graafian follicle**.

follicle-stimulating hormone *abbr.*: FSH; *recommended name*: follitropin; one of two gonadotropic **glycoprotein hormones** secreted by the anterior pituitary; of 34 kDa (human), 33 kDa (ovine), or 29 kDa (porcine), it consists of α and β subunits, the α subunit being almost identical within a given species to that of other glycoprotein hormones and the β subunit conferring hormonal specificity; the carbohydrate content is 16 (human), 8–9 (ovine), or 7–8 (porcine). In the female it stimulates the growth of Graafian follicles in the ovaries, whereas in the male it stimulates the epithelium of the seminiferous tubules to increased spermatogenesis. Secretion of FSH is stimulated by activin and inhibited by inhibin. Mutation in the FSH β subunit causes delayed puberty in females. FSH acts via a G-protein-associated receptor and activation of adenylate cyclase. Mutation in the receptor causes primary gonadal failure in females.

follicle-stimulating hormone releasing factor (*abbr.*: FRF *or* FSH-RF) *or* **follicle-stimulating hormone releasing hormone** (*abbr.*: FRH *or* FSH-RH) *see* **gonadotropin-releasing hormone**.

follicular **1** like, pertaining to, consisting of, or provided with a follicle or follicles. **2** affecting or involving follicles.

follicular phase *see* **estrous cycle**.

folliculate(d) having or consisting of follicles.

follipsin a serine proteinase from pig ovarian fluid. It is a heterodimer, and cleaves Arg-|-Xaa bonds.

follistatin an **activin**-binding glycoprotein that regulates biosynthesis and secretion of **follicle-stimulating hormone**. Alternative isoforms are formed by alternative splicing.

follitropin *the recommended name for* **follicle-stimulating hormone**.

folyl *the trivial name for* pteroylglutamyl, the acyl group derived from **folic acid** (def. 1). Use of the name is no longer recommended.

fomecin any of several antibiotic substances produced by certain strains of the basidiomycetous fungus *Fomes juniperinus*, especially fomecin A, 2,3,4,-trihydroxy-6-(hydroxymethyl) benzaldehyde.

food any material that can be ingested by an organism and metabolized to provide energy and precursors for biosynthetic reactions.

foot and mouth disease virus the seven serotypes of foot-and-mouth disease (FMD) virus, together with equine rhinovirus 1 form the aphthovirus genus of the family *Picornaviridae*. The **virion** is non-enveloped, 25-30 nm in diameter, icosohedral shaped (5:3:2 symmetry), and contains an infectious single strand of positive sense RNA, approximately 8.4 kb in length. The viral capsid consists of 60 copies of the four structural proteins, 1A (VP4), 1B (VP2), 1C (VP3) and 1D (VP1). The genome also contains the genes of 8 non-structural proteins. Cattle, pigs, sheep, goats and all other cloven hoofed animals, and some other species such as rats, hedgehogs, and coypu are susceptible to FMD. The disease is characterized by fever and vesicles in the mouth and on the feet and mammary glands of adolescent and adult animals and sudden death in young animals of susceptible species. Transmission of the virus is usually by close contact between an infected and susceptible animal, but can be by consumption (usually by pigs) of animal products contaminated by live virus or mechanical transfer of virus by people or vehicles. Pigs infected with some strains of FMD virus can produce large amounts of aerosol virus which, depending on weather conditions and topography, can form discrete plumes over long distances. In 1981, cattle on the Isle of Wight in the UK were infected by aerosol virus produced by infected pigs in Brittany, France, a distance of approximately 250 km.

footprinting a technique for identifying sites where there is protein bound to DNA. Protein–DNA complexes are resistant to the action of nucleases, so that undegraded DNA (the ‘footprint’) remains after treatment with a nuclease.

For *symbol for* the formyl group, H–CO– (alternative to HCO).

Forbes’ disease *an alternative name for* type III **glycogen disease**. [After Gilbert Burnett Forbes (1915–), US physician.]

forbidden clone a hypothetical clone of immunologically competent cells with specificity for some autoantigen that, in accord with the clonal selection theory, has become suppressed in the fetus but may be reactivated in adult life and cause an autoimmune disease.

forbidden transition any transition between energy states in an atom or molecule that is forbidden by the selection rules of quantum mechanics (but can occur nevertheless!).

force *symbol*: *F (in physics)* a vector quantity, the external influence that changes or tends to change the state of rest or uniform motion of a body, or the shape of a fixed body. The SI derived unit of force is the **newton**.

forkhead *or* **winged helix/forkhead-like protein** any of a family of transcription factors related to the *Drosophila* developmental gene *forkhead*. These proteins are implicated in developmental control of many tissues, often in response to signalling by members of the transforming growth factor/bone morphogenetic protein (TGF/BMP) family. They bind to DNA through a domain (≈108 amino acids) that resembles a winged helix (a helix-turn-helix with two additional loops, or wings). The gene for human FKHL7 (forkhead homologue-like protein 7) at 6p25 encodes a protein of 553 residues. Several mutations in this gene result in Axenfeld–Rieger anomaly of the eye.

forkhead box protein *see* **FOXP**.

formaldehyde dismutase EC 1.2.99.4; *systematic name*: formaldehyde:formaldehyde oxidoreductase. An enzyme that catalyses a dismutation of two molecules of formaldehyde to formate and methanol. The enzyme functions to detoxify formaldehyde thus rendering the organism resistant to formaldehyde. Its synthesis is induced by addition of formaldehyde to the medium.

formaldehyde gel electrophoresis a modification of agarose gel electrophoresis in which formaldehyde is incorporated in the gel as a denaturing agent for RNA. When denatured in this way RNA molecules migrate as a function of molecular mass.

formaldehyde transketolase EC 2.2.1.3; *systematic name*: D-xylulose-5-phosphate:formaldehyde glycolaldehydetransferase; *other names*: dihydroxyacetone synthase; DHAS; glycerone synthase. An enzyme that catalyses a reaction between D-xylulose 5-phosphate and formaldehyde to form glyceraldehyde 3-phosphate and glycerone; thiamine diphosphate is a coenzyme. The enzyme is important in organisms (some fungi and many prokaryotes) that can utilize methanol as a carbon source in converting formaldehyde, produced by methanol oxidation, into carbohydrate, xylulose 5-phosphate acting as C_2 donor.

formalin *or* **formol** a 40 w/v aqueous solution of formaldehyde stabilized with approximately 12 v/v methanol. It is useful as a general disinfectant and for fixation and preservation of biological specimens.

formate **1** *trivial and preferred name for* **methanoate**, the anion, H–COO$^-$, derived from formic acid (methanoic acid). **2** any mixture of formic acid and its anion. It is useful as a buffer over the pH range 2.6–4.8; pK_a (25 °C) = 3.75. **3** any salt or ester of formic acid.

formate–dihydrofolate ligase EC 6.3.4.17; *systematic name*: formate dihydrofolate ligase (ADP-forming); an enzyme that catalyses the formation of 10-formyldihydrofolate from ATP, formate, and dihydrofolate with release of ADP and orthophosphate.

formate–tetrahydrofolate ligase EC 6.3.4.3; *systematic name*: formate:tetrahydrofolate ligase (ADP forming); *other name*: formyltetrahydrofolate synthetase; an enzyme involved in one of the transformations between **folate coenzymes**. It catalyses the formation of 10-formyltetrahydrofolate from ATP, formate, and tetrahydrofolate with release of ADP and orthophosphate. It is one of three enzymes (*see also* **methylenetetrahydrofolate dehydrogenase (NADP$^+$)** and **methenyltetrahydrofolate cyclohydrolase**) necessary for the biosynthesis of purines, thymidylate, methionine, histidine, pantothenate, and formyl tRNA-met. It is one activity of the trifunctional enzyme **C1-tetrahydrofolate synthase**. *See* **methylenetetrahydrofolate dehydrogenase (NADP$^+$)** for an example.

formation constant *an alternative name for* **stability constant**.

formation function *see* **Bjerrum formation function**.

formazan **1** the compound NH_2–N=CH–N=NH. **2** any substitution derivative of this compound. Many are brightly coloured and may be reversibly oxidized into the corresponding colourless tetrazolium compounds (*see also* **Blue Tetrazolium**). Formazans prepared by coupling the phenylhydrazones of acyclic aldoses with diazonium compounds are useful in characterizing such sugars.

formed elements of the blood a general term for the **erythrocytes**, **leukocytes**, and **platelets**.

formimidoyl the acyl group, CH(=NH)–, derived from (the hypothetical) formimidic acid; the latter may also be regarded as the imino tautomer, CH(=NH)–OH, of formamide; hence also known as **formimino**.

formimino *see* **formimidoyl**.

formiminoglutamate *abbr.*: FIGLU; *N*-formimidoyl-L-glutamate; formamidino-L-glutarate; an intermediate in the catabolism of histidine. Its formimino (= formimidoyl) group is transferred to tetrahydrofolate to produce **5-formiminotetrahydrofolate**. In folate (or vitamin B_{12}) deficiency FIGLU accumulates in the tissues and its excretion in the urine increases. Estimation of the level of FIGLU in the urine is useful in assessing the extent of folate (or vitamin B_{12}) deficiency.



5-formiminotetrahydrofolate a derivative of tetrahydrofolate that is an intermediate in the metabolism of one-carbon units. It is formed from tetrahydrofolate and **formiminoglutamate**, and with **cyclodeaminase** yields 5,10-methenyltetrahydrofolate.



formin one of several developmental nuclear phosphoproteins found in several tissue types. They are formed by alternative splicing of the mouse *ld* (limb deformity) gene. Mutations in this locus result in defects of growth and patterning of the limb and kidney during embryonic development.

formol *(formerly) a proprietary name for* **formalin**.

formolize *or* **formolise** to react the amino groups of amino acids, peptides, or proteins with formaldehyde.

formol titration the pH titration, with alkali, of amino acids, peptides, or proteins in the presence of formaldehyde. The formaldehyde reacts with the amino groups and lowers their apparent p*K* values, allowing identification of the region in the titration curve where they are being titrated.

formula (*pl.* **formulas** *or* **formulae**) **1** *(in chemistry)* a collection of symbols of atoms and numbers giving information about the composition and structure of a molecular chemical entity. **2** *(in mathematics)* a general relationship, principle, or rule expressed in symbols, frequently as an equation. **3** a recipe, or prescription, for the preparation of a medicine, food, etc. giving the constituents, their amounts, and the method to be used.

formula weight *a former name for* **relative formula mass**.

formycin either of two related **nucleoside antibiotics** synthesized by the actinomycete *Nocardia interforma* that display antitumour activity. **Formycin A**; 8-aza-9-deazaadenosine; 7-amino-3-(*β*-D-ribofuranosyl)-1*H*-pyrazolo[4,3-*d*]pyrimidine; an analogue of adenosine that inhibits *de novo* purine biosynthesis in tumour cells and is incorporated into RNA. It is deaminated in erythrocytes to **formycin B**, a competitive inhibitor of NAD$^+$ in the action of NAD$^+$ ADP-ribosyltransferase and an inhibitor of purine nucleoside phosphorylase.



formycin A

formyl *symbol*: For *or* HCO; the acyl group, H–CO–, derived from formic acid.

formylate to introduce (one or more) formyl groups into an organic compound. —**formylation** *n.*

***N*-formylmethionine** *symbol*: fMet; *codon*: AUG (when used as start codon for initiation) or GUG (when present as the first codon; within genes GUG encodes valine); a modified amino-acid residue which is found at the N terminus of nascent polypeptide chains in prokaryotes and bacteriophages. It is also present in the mitochondria and chloroplasts of eukaryotes, supporting the hypothesis that they are derived from prokaryotes.

formylmethionine deformylase EC 3.5.1.31; *systematic name*: *N*-formyl-L-methionine amidohydrolase; *other name*: **polypeptide deformylase**; an enzyme, found in prokaryotes, that removes the formyl group from the N-terminal *N*-formylmethionine of many polypeptides produced by translation of mRNA; example from *Escherichia coli*: DEF_ECOLI, 169 amino acids (19.33 kDa). *See also* **post-translational modification**.

5-formyltetrahydrofolate *see* **folinic acid**.

5-formyltetrahydrofolate cyclo-ligase EC 6.3.3.2; *other name*: 5,10-methenyltetrahydrofolate synthetase; an enzyme that catalyses the reaction between ATP and 5-formyltetrahydrofolate to form 5,10-methylenetetrahydrofolate with release of ADP and orthophosphate.

formyltetrahydrofolate synthetase *see* **formate–tetrahydrofolate ligase**.

5-formyltetrahydrofolic acid *an alternative name for* **folinic acid**.

forskolin colforsin; 7*β*-acetoxy-8,13-epoxy-1*α*,6*β*,9*α*-trihydroxylabd-14-en-11-one; a diterpene isolated from the roots of the Indian labiate plant *Coleus forskohlii*. It stimulates adenylate cyclase, has positive inotropic activity, and relaxes smooth muscle; at higher doses it is hypotensive and vasodilatory. The water-solubility of the active 7-*O*-hemisuccinyl-7-deacetyl- or (less potent) 7-deacetyl-6-(*N*-acetylglycyl)-derivatives is useful; the 1,9-dideoxy-derivative is inactive and can be used as a control.



Forssman antibody an antibody against **Forssman antigen**; it causes agglutination of sheep erythrocytes.

Forssman antigen *or* **Forssman hapten** *abbr.*: F antigen; a heterophil antigen, present on the tissue cells of many species, including horse, sheep, and mouse, but absent in human and rabbit. The glycolipid hapten (from horse) is a ceramide pentasaccharide, GalNAc(*α*1-3)GalNAc(*β*1-3)Gal(α1-4)Gal(*β*1-4)Glc(*β*1-1)Cer; when incorporated in liposomes the nonpolar ceramide end anchors the hapten in the bilayer leaving the polar pentasaccharide region accessible to Forssman antibodies.

Förster theory of fluorescence energy transfer a theory giving the rate of dipole–dipole energy transfer in fluorescence as:

$$k_T = 8.71 \times 10^{23}(r^{-6}K^2Jn^{-4}k_F)$$

and the efficiency of transfer as:

$$E = r^{-6}/(r^{-6} + R_0^{-6}),$$

where R_0, the distance at which transfer efficiency is 50· is given by:

$$R_0 = 9.71 \times 10^3\ (JK^2Q_0n^{-4})^{1/6}\text{Å},$$

in which r is the distance between the centres of donor and acceptor chromophore, K^2 is the orientation factor for a dipole– dipole interaction, J is the spectral overlap integral, n is the refractive index of the medium between the donor and acceptor, k_F is the rate constant for fluorescence emission by the energy donor, and Q_0 is the quantum yield of fluorescence of the energy donor in the absence of the acceptor. For energy transfer to be efficient the fluorescence emission spectrum of the donor must overlap the absorption spectrum of the acceptor, i.e. the donor and acceptor must be in resonance, as measured by the spectral overlap integral J, which, in cm^3M^{-1}, is:

$$J = (\int F(\lambda)\varepsilon(\lambda)\lambda^4\text{d}\lambda)/(\int F(\lambda)\text{d}\lambda),$$

where $F(\lambda)$ is the fluorescence intensity in arbitrary units of the energy donor at wavelength λ in cm, and $\varepsilon(\lambda)$ is the extinction coefficient of the energy acceptor in $\text{cm}^{-1}\text{M}^{-1}$. The orientation factor, K^2, is given by:

$$K^2 = (\cos\alpha - 3\cos\beta\cos\gamma)^2,$$

where α is the angle between the donor and acceptor transition moments and β and γ are the angles between the donor moment and the acceptor moment and the line joining the centres of the donor and acceptor, respectively. [After T. Førster.]

Førster transfer the nonradiative, resonant energy transfer that occurs when electronic excitation of one chromophore in a molecule, or other structure, elicits fluorescence from a different chromophore located up to 5–7 nm distant. For example, excitation of a tyrosine residue in a protein molecule can lead to fluorescence from a tryptophan residue in the same protein, and excitation of a tryptophan residue can cause fluorescence of dyes attached to the protein surface or to an embedded coenzyme. Resonant energy transfer is important in photosynthesis; many of the chlorophyll molecules in a chloroplast transfer the energy they have absorbed to other chlorophyll molecules at reaction centres.

fortimycin any of several aminoglycoside antibiotics from the actinomycete *Micromonospora olivoasterospora*.

Fortran *see* **programming language**. [Contraction of formula translator.]

forward mutation any gene mutation from wild-type to the mutant phenotype, as opposed to a **back mutation**.

forward scattering scattering of radiation in the direction of the beam of radiation, i.e. away from the radiation source.

FOS a gene family encoding nuclear transcription factors; v-*fos* is the oncogene of the FBJ and FBR murine osteosarcoma viruses and Fujinami (avian) sarcoma virus. *FOS* is rapidly (within 5 minutes) but transiently expressed following stimulation of cells by mitogens and also during the onset of differentiation and by wounding. The gene product, FOS, and JUN (from the related gene family *JUN*) form homo- and heterodimers that bind to DNA; the heterodimers bind to the AP-1 consensus site (*see* ***JUN***); FOS homodimers bind to the TPA response element (TRE) if Glu^{168} is substituted by Lys. The proteins are members of the **leucine zipper** and **helix-turn helix** superfamilies.

fosfomycin *another name for* **phosphonomycin**.

Fouchet's test a colour test for the presence of bilirubin in the urine. A green colour is produced when the sample is treated with iron (III) chloride solution and trichloroacetic acid.

founder effect *(in genetics)* a high frequency of a particular allele in a population resulting from the presence of the allele in one or more of a small number of individuals from whom the population is descended.

Fourier analysis the fitting of the terms of a **Fourier series** to a set of periodic data.

Fourier series the expression of any ordinary, single-valued (univalent) periodic function:

$$y = \mathrm{f}(x) \quad (1)$$

as the sum of an infinite number of sine waves of successively higher orders. Substituting $n\,\theta$ for x, to be appropriate to circular functions,

$$y = a_0 + a_1\cos\theta + a_2\cos2\theta + a_3\cos3\theta + \ldots + b_0 + b_1\sin\theta + b_2\sin2\theta + b_3\sin3\theta + \ldots \quad (2)$$

The coefficients a_n and b_n can be uniquely determined by equating equations (1) and (2) point by point for successive values of x and solving the simultaneous equations so found. [After Jean Baptiste Joseph Fourier (1768–1830), French mathematician.]

Fourier synthesis the process of computing the form of a function from the values of the coefficients of its **Fourier series**.

FOXP *abbr. for* forkhead box protein; any of a family of homologous proteins implicated in embryonal development. Each contains a forkhead-winged-helix domain of ≈108 amino acids. Mutations in the FOXP2 (715 amino acids) gene at 7q31 lead to speech and language disabilities. FOXP3 (or scurfin) is expressed preferentially in regulatory T lymphocytes and regulates immunity. Mutations in FOXP3 cause an X-linked multiorgan autoimmune and inflammatory syndrome in humans, and a similar condition called scurfy in mice.

FP *abbr. for* flavoprotein.

F6P *abbr. for* fructose 6-phosphate.

F-pilus a type of sex pilus, one or two of which may be present in each cell of 'male' strains of *Escherichia coli*. Each pilus is approximately 8 nm in diameter and up to 20 µm long. F-pili are consistently associated with the presence in the bacterium of the **F′ plasmid**, which directs their synthesis; they are believed to serve as conductors of nucleic acids in various circumstances, e.g. during bacterial conjugation.

F plasmid *or* **F factor** the prototype 'fertility factor' responsible for conjugation in the K-12 strains of *Escherichia coli* used in the early studies of bacterial mating. The letter F refers specifically to this plasmid and thus should not be used to refer to other naturally occurring **conjugative plasmids**.

F′ plasmid *or* **F' factor** an **F plasmid** derivative incorporating a segment of the bacterial chromosome. An organism in which an F' plasmid has arisen and that carries a chromosomal deletion corresponding to the segment incorporated by the plasmid is termed a **primary F'-containing strain**, and an organism into which an F' plasmid has been transferred is termed a **secondary F'-containing strain**.

FPS *see* ***FES/FPS***.

Fr *symbol for* francium.

FR *abbr. for* folate receptor. *See* **folate-binding protein**.

fraction 1 *(in chemistry)* any one of several portions of a mixture that can be separated by a fractional process, e.g. by fractional distillation or chromatography, and consisting either of a mixture or of a pure compound. **2** to separate or divide into portions; to **fractionate**.

fraction I–VI (of blood plasma) *see* **Cohn fractionation**.

fractional 1 of, relating to, or being a fraction. **2** of or denoting any process by which parts of a mixture are separated by exploiting differences in their physical properties, e.g. their boiling points, solubility, or chromatographic characteristics.

fractional centrifugation *an alternative name for* **differential centrifugation**.

fractional crystallization the separation of substances with nearly the same solubilities. It involves a series of recrystallizations at each stage of which the crystals will be enriched in one component and the mother liquor will be enriched in the other component.

fractional distillation the process of separating the components of a mixture by heating it and separately condensing portions of vapour at different temperatures, corresponding to the boiling points of the components of the mixture.

fractional precipitation the stepwise separation of substances, especially macromolecules, from a solution by exploiting differences in their solubilities in various conditions of pH, ionic strength, dielectric constant, etc. Changes in these conditions are effected by the addition of acid, alkali, salt (e.g. ammonium sulfate), ethanol, or other substances.

fractional sterilization *an alternative name for* **tyndallization**.

fractionate 1 to separate (a mixture) or cause (a mixture) to separate into portions or fractions, e.g. by distillation or crystallization. **2** to obtain (a part of a mixture) by a **fractional** process. **—fractionation** *n.*

fractionating column a vertical tube or hollow column frequently forming part of an apparatus for **fractional distillation** and usually filled with packing or intersected with perforated plates. An internal reflux takes place during distillation resulting in a gradual separation between the high-boiling-point fractions and the low-boiling-point fractions, the lowest-boiling-point fraction distilling over first.

fraction collector *or (sometimes)* **fraction cutter** an apparatus for the automatic collection of consecutive, commonly equal-sized, fractions of a flowing liquid, e.g. of the eluate from a chromatographic column. The size of the fractions may be predetermined by volume, mass, time, or number of drops.

fraction cutter 1 the device in a **fraction collector** that separates the flow of eluate into fractions of predetermined size, which then may be individually collected. **2** *(sometimes) an alternative name for* **fraction collector**.

fraction I protein *a former name for* RuBP carboxylase; *see* **ribulose bisphosphate carboxylase**.

fragile X mental retardation protein *see* **FMRP**.

fragile X syndrome an X-linked inherited disorder, with mental retardation and connective tissue abnormalities, arising from expansion of a **trinucleotide repeat** of CGG in the 5′ untranslated region of the mRNA for fragile X mental retardation protein (**FMRP**), which leads to nonexpression of that protein. In normal individuals the repeat number is 5–60, in the premutation 60–200, and in the full mutation >200. This is the most common form of inherited mental retardation. It is named for the folate-sensitive fragile site at Xq27.3. *See* ***FMR1***.

fragment-antigen binding *see* **Fab fragment**.

fragmentation 1 *(in cell biology)* **a** the separation of a small piece (i.e. a fragment) of a chromosome from the rest. **b** the division of a cell nucleus by simple splitting. **2** *(in chemistry)* the breakdown of a radical into a diamagnetic molecule and a smaller radical; the breakdown of a radical ion in a mass spectrometer to form an ion of lower molecular mass and a radical.

fragment-crystallizable *see* **Fc fragment**.

fragment ion *(in mass spectrometry)* any ion produced by the loss of one or more pieces from a parent **molecular ion** (or larger fragment ion).

fragmentography *see* **molecular fragmentography**.

fragmin a Ca^{2+}-sensitive protein, M_r 43 000, isolated from *Physarum polycephalum*, that regulates the length of actin filaments *in vitro*.

frame *short name for* **reading frame**.

frameshift an alteration in the reading sense of DNA resulting from an inserted or deleted base, such that the **reading frame** for subsequent codons is shifted according to the number of changes made. Frameshifts may arise, for example, via random mutations or errors in reading sequencing output.

frameshifting *(in ribosomal function) see* **programmed ribosomal frameshifting**.

frameshift mutagen any mutagen that is capable of causing **frameshift mutations**.

frameshift mutation *or* **phaseshift mutation** any mutation involving the addition or deletion of nucleotide residues in a DNA molecule that results in out-of-phase translation, at positions beyond the site of mutation, of the messenger RNA formed from it. Since the genetic code is read as unpunctuated base triplets, additions or deletions in the message that are not multiples of three bases result in a shift in the reading frame.

frameshift suppressor any of a class of external suppressor mutations that specifically suppress a frameshift mutation by changing (correcting) the phase of translation. Frameshift suppressors are genetic alterations outside the mutated cistron. Some give rise to altered tRNA molecules, **frameshift suppressor tRNAs**, that recognize a base quadruplet instead of a base triplet.

framework regions in **immunoglobulin G** the heavy and light chains contain in all six hypervariable regions of amino acid residues that form the antigen-binding site of the antibody molecule. The other domains exhibit far less variation and are named the **framework regions**. These form the basic beta-pleated sheet structure, which forms a scaffold for the hypervariable regions. The 3-D structure of the framework regions is very similar in all antibodies.

framework regions in **immunoglobulin G** the heavy and light chains contain in all six hypervariable regions of amino acid residues that form the antigen-binding site of the antibody molecule. The other domains exhibit far less variation and are named the **framework regions**. These form the basic beta-pleated sheet structure, which forms a scaffold for the hypervariable regions. The 3-D structure of the framework regions is very similar in all antibodies.

Franck–Condon principle the principle that the time taken for electronic transitions in molecules is very short in comparison with the period of vibration of the atomic nuclei, with the consequence that the nuclei do not appreciably alter their positions during the emission or absorption of a photon. [After James Franck (1882–1964) and Edward Uhler Condon (1902–74), US physicists.]

FRAP *see* **mTor**.

FRAT *abbr. and proprietary name for* free radical assay technique (*see* **spin immunoassay**).

frataxin a 210-residue protein identified from a mutation found in **Friedreich's ataxia** (*abbr*.: FRDA). Some FRDA patients have point mutations in the gene encoding frataxin, but the majority are homozygous for an unstable GAA trinucleotide expansion in the first intron. The protein is involved in iron storage and iron–sulfur cluster assembly in mitochondria.

fraudulent DNA a DNA molecule containing **fraudulent nucleotides**.

fraudulent nucleotide any (artificial) nucleotide that contains a non-naturally occurring base that is an analogue of a purine or pyrimidine found in natural DNA.

frayed end (of DNA) an end region of a double-stranded polynucleotide in which there is imperfect complementarity of the base pairs.

fredericamycin A an antibiotic produced by *Streptomyces griseus* that contains a *spiro* ring system and is active against Gram-positive bacteria and fungi. It is cytotoxic against some transplantable tumours.



fredericamycin A

free *(in chemistry)* not chemically combined (with another substance); not physically bound (to another substance).

free diffusion diffusion in a gas phase or across a boundary between two solutions (or between a solution and pure solvent), as distinct from diffusion across a membrane or some other porous barrier.

free-draining coil a model for polymer molecules in solution that are not well approximated by a solid particle. In this model the polymer is considered as a string of beads through which the solvent streams during viscous flow.

free electrophoresis *an alternative name for* **moving boundary electrophoresis** (def. 1).

free energy the thermodynamic potential of a system. For a change (such as a chemical reaction or series of reactions) to be feasible the change in free energy must be negative. Free energy contains contributions from energy and entropy terms. *See* **Gibbs energy**, **Helmholz free energy**.

free energy change *an alternative name for* **Gibbs free energy change**.

free fatty acid *abbr*.: FFA; a nonesterified fatty acid; the term is often used of such acids in the blood.

free-flow electrophoresis *an alternative name for* **moving boundary electrophoresis** (def. 1).

free radical *see* **radical** (def. 1).

free-radical scavenger *the former term for* **radical scavenger**.

free rotation sterically unhindered rotation of atoms or groups about a single covalent bond.

freeze-clamp to halt abruptly the metabolic processes in a piece of tissue, or other specimen, by clamping it into a thin, frozen wafer between two aluminium (or other metal) plates, previously cooled in liquid nitrogen. The frozen specimen then may be pulverized and treated with a protein precipitant, e.g. acetone at –70°C. The technique is useful in the determination of the concentrations of various metabolites that otherwise are rapidly consumed by enzymic action continuing during an investigation.

freeze-cleaving *an alternative term for* **freeze-fracturing**; *see also* **freeze-etching**.

freeze-dry to dry in a frozen state at very low pressure (i.e. in a high vacuum) so that ice, or other frozen solvent, sublimes rapidly, leaving a porous solid; to lyophilize. Used, e.g. in histochemistry, as frozen biological material can be preserved by removal of water under vacuum without damage to cell structures.

freeze-dryer any apparatus used for freeze-drying.

freeze-etching *or* **frozen replica method** a technique of preparing, for electron-microscopic examination, a surface that has been exposed by fracturing or cutting a deep-frozen specimen. The sample is rapidly frozen to about –150°C and placed in a vacuum, where it is cleaved or sliced with a cold knife – the process known as **freeze-fracturing**. Etching is then achieved by evaporation of some of the solvent from the surface in a vacuum at about –100°C to produce a textured field, in which nonvolatile macromolecules protrude from a frozen aqueous layer. A replica of the surface is then prepared by shadowing with carbon and/or a heavy metal while the sample is still in the vacuum. This replica is then lifted off, rinsed, and placed on an electron microscope grid for examination. *See also* **replica formation**.

freeze-fracturing *(in electron microscopy)* a method of visualizing the interior of cell membranes in which cells are frozen at the temperature of liquid nitrogen in the presence of antifreeze and then the frozen block is cracked with a knife blade. The fracture plane often passes through the hydrophobic middle of lipid bilayers, thereby exposing the interior of cell membranes. The resulting fracture faces are shadowed with platinum, the organic material is dissolved away and the replicas floated off for electron microscopy.

freeze-stop to stop a reaction rapidly by freezing the reaction mixture; to **freeze-clamp**.

freeze–thaw to disrupt cells in a suspension, or to disperse emulsions, by repeated freezing and thawing.

freezing **1** the change of a liquid into a solid by a lowering of temperature. **2** the stopping of a reaction or other process at a particular point, often by a lowering of temperature. **3** *or* **cryopreservation** the use of temperatures below 0°C in order to preserve biochemicals and foodstuffs, or to maintain viable populations of (micro)organisms.

freezing-microtome a microtome in which the tissue sample is frozen and maintained in a frozen state with liquid carbon dioxide. It is useful for (rapidly) obtaining sections of unfixed soft tissue. *Compare* **cryomicrotome**.

freezing point the temperature at which **freezing** (def. 1) occurs.

French chalk *see* **talc**.

French pressure cell a device to disrupt chloroplasts and bacteria, yeasts, or other cells. A cell or chloroplast suspension is placed in a cylinder fitted with a piston and a narrow outlet controlled by a needle valve. After removal of air, the piston is forced into the cylinder with a hydraulic press to the desired operating pressure (<20000 pound-force per square inch, 140 MPa). The valve is then opened. Extrusion through the narrow orifice together with the sudden release of pressure creates shear forces that break the suspended particles. *See also* **Hughes press**. [After Charles Stacy French (1907–), US plant physiologist.]

Freon *the proprietary name for* any of a group of fluorocarbon or chlorofluorocarbon compounds that are clear, colourless liquids, chemically inert, and of low toxicity. They are useful as refrigerants, aerosol propellants, cleaning fluids, and solvents. These substances have been shown to be important in the chemical removal of ozone by chlorine-catalysed cycles in the polar region during winter and spring. Nitric oxide and ice-clouds are formed in the polar stratosphere during winter. Heterogeneous chemical reactions take place on the surface of these particles, dramatically shifting the balance between inactive and active forms of chlorine and increasing the efficiency of chlorine in catalytic ozone removal. The use of Freon is being phased out in many countries; it is being replaced by substances such as tetrafluoroethane (ICI Trademark KLEA) which are claimed not to cause depletion of ozone.

frequency *symbol*: ν *or* f; the number of complete cycles of any periodic process occurring in unit time. The SI derived unit of frequency is the **hertz**. The frequency of a wave is equal to its velocity divided by its wavelength.

frequency distribution a table, graph, or histogram constructed from a series of measurements to show the classes into which the measurements are divided and the numbers in each of these classes.

fresnel a non-SI unit of frequency of electromagnetic radiation, equal to 10^{12} Hz.

Fresnel diffraction the diffraction occurring when electromagnetic radiation encounters abrupt discontinuities in refractive index, as in a **Fresnel lens** or in the examination of some specimens in (electron) microscopy. [After Augustin Jean Fresnel (1788–1827), French physicist.]

Fresnel lens a lens whose surface consists of a concentric series of lens sections (or one convex surface and one stepped surface). This arrangement allows a thin lens of short focal length and large diameter to be easily made, and finds application in searchlights, viewing devices, and overhead projectors.

fret a broad membrane-bound channel interconnecting the grana of **chloroplasts**.

FRET *abbr. for* fluorescence resonance energy transfer.

Freund's adjuvant a widely used immunological **adjuvant** (def. 1), used to produce water-in-oil emulsions with aqueous antigens or antigen preparations. It consists of a mixture of mineral oil and emulsifier (**incomplete Freund's adjuvant**) in which killed mycobacteria have been dispersed (**complete Freund's adjuvant**). Omission of mycobacteria may modify the duration, intensity, and nature of the responses. [After Jules Freund (1891–1960).]

Frey–Wyssling particle a double-membrane particle (4–6 µm in diameter) representing a minor component of rubber latex. [After Albert Frey-Wyssling (1900–).]

FRF *abbr. for* follicle-stimulating-hormone-releasing factor; *see* **gonadotropin-releasing hormone**.

FRH *abbr. for* follicle-stimulating hormone releasing hormone; *see* **gonadotropin-releasing hormone**.

friable easily crumbled or pulverized.

friction the resistance to the relative motion of one body sliding, rolling, or flowing over another body with which it is in contact. — **frictional** *adj.*

frictional coefficient *or* **frictional constant** *symbol*: f; the frictional force opposing the motion of a body in a fluid medium divided by the velocity of movement. It may be expressed in different ways. The **translational frictional coefficient**, f, for a rigid sphere of radius r moving at low velocity through a medium of viscosity η, is given by: $f = 6\pi\eta r$ (**Stokes' law of viscosity**). For particles of other shapes additional terms must be included. The **rotational frictional coefficient**, f_{rot}, is a parameter relating the velocity of rotation of a rigid sphere of volume V in a fluid medium of viscosity η. It is given by: $f_{\text{rot}} = 6\eta V$. *See also* **frictional ratio**.

frictional force the force exerted on a particle moving through a fluid medium as a result of friction. It is the product of the velocity, relative to the medium, of the particle and its **frictional coefficient**.

frictional ratio the ratio of the experimentally determined translational **frictional coefficient**, f, of a hydrated, anisotropic macromolecule to the calculated frictional coefficient, f_0, of a nonhydrated spherical macromolecule of the same molecular mass. The ratio f/f_0 gives some indication of the asymmetry of the macromolecule.

Friedreich's ataxia an autosomal recessive inherited disease that involves the central and peripheral nervous systems and the heart. It is the most common hereditary ataxia, and is associated with defects in the gene encoding **frataxin**. [After Nikolaus Friedreich (1825–1882), German neurologist.]

Friend cell a cell of a cultured cell line of leukemic mouse erythroblasts obtained by transformation with Friend leukemia virus. In such cells development is arrested before any globin synthesis occurs, but treatment with certain chemicals, e.g. dimethylsulfoxide, causes a resumption of development and hemoglobin synthesis.

Friend leukemia virus a strain of mouse type C oncovirus that specifically affects immature erythroid cells in mice to cause an erythroleukemia. [After Charlotte Friend (1921–).]

friend of GATA-1 *see* **FOG1**.

frit filter *or* **fritted filter** *or* **fritted glass filter** *an alternative name for* **sintered glass** filter.

Frizzled any of a family of G-protein-coupled plasma membrane receptors present throughout the animal kingdom. The N-terminal extracellular segment contains a cysteine-rich domain (called the FRZ domain) of ≈120 amino acids, which binds a Wnt protein. The domain also occurs in secreted Wnt antagonists such as WIF-1.

Fromm's method a kinetic approach for studying the mechanism of action of enzyme systems that utilize three substrates. Such systems may be divided into two groups on the basis of their initial rate expressions: the first group is made up of sequential pathways of enzyme and substrate interaction alone, the second is the ping-pong type. The mechanisms in each category may further be separated either by initial rate measurements or from studies with competitive inhibitors. [After Herbert Jerome Fromm (1929–), US biochemist.]

frontal analysis any analytical technique by which the progress of the separation of components of a mixture, as by frontal chromatography, moving boundary electrophoresis, or analytical ultracentrifugation, is followed, and the relative proportions of the components determined, by examination of the individual boundaries, or fronts, formed by each component with the solvent.

frontal chromatography a technique for chromatographic separation in which the sample (liquid or gas) is fed continuously into the chromatographic bed and only the component that emerges first is obtained in pure form.

fronting *(in chromatography)* the asymmetry of a peak such that, relative to the baseline, the front is less steep than the rear. In paper chromatography and thin-layer chromatography it refers to the distortion of a zone showing a diffuse region preceding the zone in the direction of flow.

frontside attack the mechanism of a chemical displacement reaction in which the configuration is retained.

frozen replica method *an alternative name for* **freeze-etching**.

FRS *abbr. for* Fellow of the Royal Society (of London).

FRSE *abbr. for* Fellow of the Royal Society of Edinburgh.

Fru *symbol for* a residue (or sometimes a molecule) of the ketohexose **fructose**. In the condensed system of symbolism of sugar residues, Fru signifies specifically a fructose residue with the common configuration and ring size, i.e. D-fructofuranose.

fructan any **glycan** composed only of D-fructose residues. Fructans occur commonly as food reserves in the roots, stems, leaves, and seeds of many plants, e.g. in tubers of dahlias and Jerusalem artichokes. There are two main types: (1) inulin-type, in which the fructofuranose residues are linked by $\beta2\rightarrow1$ glycosidic linkages; and (2) levan-type, in which the linkages are $\beta2\rightarrow6$, which were formerly referred to as **fructosans**.

β-fructofuranosidase EC 3.2.1.26; *other names*: invertase; saccharase; an enzyme that catalyses the hydrolysis of terminal nonreducing *β*-D-fructofuranoside residues in *β*-D-fructofuranosides, e.g. sucrose.

fructokinase **1** *the recommended name for* the enzyme ATP:D-fructose 6-phosphotransferase; EC 2.7.1.4; this catalyses the phosphorylation of D-fructose by ATP to form D-fructose 6-phosphate and ADP. The enzyme occurs in plants and in schistosomes, and is highly specific for D-fructose. In bacteria it is important in fructose utilization. Structurally it is similar to other carbohydrate kinases. **2** *an alternative name for* **ketohexokinase** (EC 2.7.1.3). This usage is misleading since ketohexokinase yields D-fructose 1-phosphate.

fructosaccharase *a trivial name for* any **saccharase** that attacks the fructose-containing end of appropriate oligosaccharides, liberating fructose.

fructosan **1** *(formerly) a trivial name for* 2,6-anhydrofructofuranose. **2** *an (older) incorrect name for* **fructan**.

fructose *symbol*: Fru; *the trivial name for* the ketohexose *arabino*-2-hexulose; there are two enantiomers. D-(–)-fructose (*symbol*: D-Fru), commonly known as fructose, and formerly known as **fruit sugar**, is levorotatory, hence formerly known also as **levulose** *or* (*esp. UK*) laevulose; it is the sweetest of the sugars. Aqueous solutions of D-fructose at room temperature contain an equilibrium mixture of *β*-D-fructopyranose, *β*-D-fructofuranose, *α*-D-fructofuranose, and the open-chain form, whereas in crystals the sugar is present entirely as *β*-D-fructopyranose. Combined D-fructose is almost invariably in the furanose form, however. D-fructose is found free in a large number of fruits, in honey, and (as the sole sugar) in bull and human semen. In combined form it occurs at one residue per molecule of the disaccharide **sucrose** and the trisaccharides **gentianose**, **melezitose**, and **raffinose**, and as the sole component of the polysaccharide **fructans**.



β-D-fructofuranose

fructose-bisphosphatase EC 3.1.3.11; *systematic name*: D-fructose-1,6-bisphosphate 1-phosphohydrolase; *other names*: hexosediphosphatase; *(formerly)* fructose-1,6-diphosphatase. A phosphoric monoester hydrolase that hydrolyses D-fructose 1,6-bisphosphate to D-fructose 6-phosphate and orthophosphate. It is important in **gluconeogenesis** and in regulation of the **reductive pentose phosphate cycle** in chloroplasts.

fructose-2,6-bisphosphatase an enzyme that hydrolyses fructose 2,6-bisphosphate to fructose 6-phosphate; it is the same protein as phosphofructokinase-2. *See* **phosphofructokinase** (def. 2).

fructose-1,6-bisphosphatase deficiency *see* **hereditary fructose-1,6-bisphosphatase deficiency**.

fructose 1,6-bisphosphate *or (formerly)* **fructose 1,6-diphosphate** *abbr.*: FBP; the D enantiomer is a metabolic intermediate in **glycolysis** and **gluconeogenesis**.

fructose 2,6-bisphosphate the D enantiomer is an important regulator of the **glycolytic** and **gluconeogenic pathways**. It inhibits fructose 1,6-bisphosphatase and activates phosphofructokinase, and its concentration is controlled by the **phosphofructokinase** (def. 2) and fructose 2,6-bisphosphatase activities of a 49 kDa protein.

fructose-bisphosphate aldolase *see* **aldolase** (def. 2).

fructose-2,6-bisphosphate 2-phosphatase EC 3.1.3.46; *other name*: fructose-2,6-bisphosphatase; an enzyme that catalyses the hydrolysis of D-fructose 2,6-bisphosphate to D-fructose 6-phosphate and orthophosphate, being part of the system for regulating the concentration of fructose 2,6-bisphosphate. This enzyme is the phosphorylated form of the protein. If dephosphorylated, it functions as a 2-kinase for fructose 6-phosphate. *See also* **phosphofructokinase** (def. 2).

fructose-1,6-diphosphatase *a former name for* **fructose-bisphosphatase**.

fructose 1,6-diphosphate *a former name for* **fructose 1,6-bisphosphate**.

fructose disease *see* **essential fructosuria**, **hereditary fructose intolerance**, **hereditary fructose-bisphosphatase deficiency**.

fructose intolerance *an alternative name for* **essential fructosuria**.

fructose 6-phosphate *abbr.*: F6P; the D enantiomer is an important intermediate in glycolysis, gluconeogenesis, and fructose metabolism.

fructosuria the presence of abnormal amounts of fructose in the urine. *See also* **essential fructosuria**.

Fru*f* *symbol for* a fructofuranose residue.

fruit the structure that develops from the fertilized ovary of a flowering plant and contains the ripening seed or seeds. It may be fleshy or dry; the term is often extended to include other associated parts such as a fleshy receptacle.

fruit fly a common name for species of flies belonging to the genus *Drosophila*.

fruit-ripening hormone *see* **ethylene**.

fruit sugar *a former name for* the D enantiomer of **fructose**.

***Fse*I** a type 2 **restriction endonuclease**; recognition sequence: GGCCGG↑CC.

FSF *abbr. for* fibrin-stabilizing factor (i.e. factor XIIIa); *see* **blood coagulation**.

FSH *abbr. for* follicle-stimulating hormone.

FSH-RF *abbr. for* follicle-stimulating hormone releasing factor; *see* **gonadotropin-releasing hormone**.

FSH-RH *abbr. for* follicle-stimulating hormone releasing hormone; *see* **gonadotropin-releasing hormone**.

F_1 sphere a submitochondrial structure containing the catalytic site for ATP synthesis.

F′-strain a bacterial strain containing an **F′ plasmid**.

FtsZ a bacterial GTPase that is crucial for assembly of the **Z ring** in the mid-region of the plasma membrane inner surface. It is the first protein to localize to the future site of cell division. Highly conserved in eubacteria and archaea, it also occurs in most groups of land plants and in many algae, and resembles eukaryotic tubulin. Its correct localization requires the Min system.

F-type pentose phosphate pathway *see* **pentose phosphate pathway**.

ftz the gene for Fushi Tazaru protein, a nuclear DNA-binding homeobox segmentation protein from *Drosophila melanogaster*.

FU *abbr. for* fluorouracil (use proscribed; the symbol FUra is recommended).

Fuc *symbol for* a residue (or sometimes a molecule) of the deoxyaldohexose **fucose**. In the condensed system of symbolism of sugar residues, Fuc signifies specifically a fucose residue with the common configuration and ring size, i.e. L-fucopyranose.

fucan a **glycan** composed only of fucose residues.

fucoidan *or* **fucoidin** any of a group of complex branched, sulfated heteropolysaccharides that are composed of residues of L-fucose (usually sulfated) together with small numbers of residues of various other monosaccharides. Fucoidans occur in the cell walls, intercellular matrix, and exuded mucilage of many (especially intertidal) species of marine algae, in which they appear to assist in water retention during periodic exposure.

fucosamine 2-amino-2,6-dideoxygalactose; an aminodeoxysugar, both enantiomers of which occur in lipopolysaccharides of *Salmonella* and other bacterial genera.

fucose *symbol*: Fuc; *the trivial name for* 6-deoxygalactose; there are two enantiomers. D-fucose (*symbol*: D-Fuc), 6-deoxy-D-galactose,



β-D-fucose

occurs in glycosides in various plants belonging to the Convolvulaceae. L-fucose (*symbol*: L-Fuc), 6-deoxy-L-galactose, occurs in polysaccharides (fucans) in seaweeds, especially *Fucus* spp., and in the cell wall matrix of higher plants. In animals fucosyl residues occur in a number of glycoproteins and glycolipids; the presence of *α*-1,4-linked L-fucosyl residues at specific positions in the highly branched oligosaccharides of human erythrocyte surface antigens is controlled by the *H* and *Le* blood-group genes.

fucose-1-phosphate guanylyltransferase EC 2.7.7.30; *other name*: GDPfucosepyrophosphorylase; an enzyme that catalyses the formation of GDP-L-fucose from GTP and L-fucose 1-phosphate with release of pyrophosphate.

***α*-fucosidase** any of several enzymes that hydrolyse α-fucosides. **1** α-fucosidase, EC 3.2.1.51; *systematic name*: *α*-L-fucoside fucohydrolase; it catalyses the hydrolysis of an *α*-L-fucoside to an alcohol and L-fucose. **2** 1,3-α-L-fucosidase, EC 3.2.1.111; *other names*: almond emulsin; fucosidase I; an enzyme that catalyses the hydrolysis of 1,3-linkages between *α*-L-fucose and *N*-acetylglucosamine residues in glycoproteins. **3** 1,6-α-L-fucosidase, EC 3.2.1.127; an enzyme that catalyses the hydrolysis of 1,6-linkages between *α*-L-fucose and *N*-acetyl-D-glucosamine in glycopeptides such as immunoglobulin G glycopeptide and fucosyl-asialo-agalacto-fetuin.

fucosidosis a rare autosomal recessive disorder characterized by progressive psychomotor and growth retardation; urinary excretion and lysosomal accumulation of glycolipids, glycopeptides, and oligosaccharides that contain terminal fucose moieties; and *α*-fucosidase deficiency. Mutations in the gene at 1p24 are responsible.

FUdR *or* **FUDR** *abbr. for* fluorodeoxyuridine (use deprecated; the symbol FdUrd is recommended).

fugu a teleost fish, *Takifugu rubripes,* used as a model experimental organism. Sequencing of the fugu genome has enabled valuable comparisons with other organisms. Fugu has a similar number of genes to mammals, but the fugu genome is much smaller at 390 Mbp, one-eighth the size of the human genome.

fugu toxin *see* **tetrodotoxin**.

fukuatin a protein (461 amino acids, gene at 9q31-q33) implicated in Fukuyama type congenital muscular dystrophy, which is associated with dysplasia of cerebral cortex, epilepsy, and severe mental retardation. Its localization and function are still unclear.

full agonist an **agonist** that is able to elicit the maximal response of a tissue even when the tissue has spare receptors. In such a situation, several different agonists may be able to elicit the same maximal response, albeit at different receptor occupancies. Moreover, a full agonist in one tissue may be a **partial agonist** in another.

fuller's earth a naturally occurring, porous, absorptive aluminium–magnesium silicate clay. It is useful for decolorizing oils and other liquids and as a filtering medium. It is so-called because it was originally used to full (i.e. cleanse and thicken) wool and woollen cloth.

full-shotgun coverage *see* **depth of coverage**.

fully overlapping code *see* **overlapping code**.

fumarase EC 4.2.1.2; *recommended name*: fumarate hydratase. An enzyme of the **tricarboxylic-acid cycle** that catalyses the reaction:

$$(S)\text{-malate} = \text{fumarate} + H_2O.$$

There are two different enzymes in facultative bacteria (e.g. *Escherichia coli*). In humans a cytosolic and a mitochondrial isoform are derived from the gene at 1q42.1. A missense mutation produces deficiency of both isoforms and results in neurological impairment and neuropathy, fumaric aciduria, and increased urinary excretion of succinate, 2-oxoglutarate, and citrate. Mutations are also associated with hereditary fibroids of skin and uterus, suggesting that the protein is a tumour suppressor.

fumarate 1 *the trivial name for trans*-1,2-ethylenedicarboxylate, (*E*)-butenedioate, the dianion of fumaric acid; the diastereoisomer of **maleate** and a key intermediate in metabolism. In the tricarboxylic-acid cycle it is formed from succinate by **succinate dehydrogenase**, and is converted to malate by **fumarase**. **2** any mixture of fumaric acid and its mono- and dianions. **3** any salt or ester of fumaric acid.



fumarate hydratase *see* **fumarase**.

fumarate reductase an enzyme in the respiratory chains of anaerobic bacteria that catalyses the reduction of fumarate by menaquinol to form succinate and menaquinone. *E. coli* fumarate reductase is an iron–sulfur flavoprotein (FAD), containing at least four different subunits: a flavoprotein, an iron–sulfur protein, and two hydrophobic anchor proteins.

fumaroyl the bivalent *trans*-acyl group, –CO–CH=CH–CO–, derived from fumaric acid.

fumaryl the univalent *trans*-acyl group, HOOC–CH=CH–CO–, derived from fumaric acid.

fumed silica a preparation of pure silicon dioxide as an extremely fine, white powder with an external surface area of up to 400 m^{2}g^{-1}. It is useful for thickening and forming thixotropic gels. Fumed silica is used as a suspending and gelling agent in liquid-scintillation counting; a 3–5 concentration in dioxan, toluene, or xylene-based liquid scintillators will form an almost transparent, rigid gel, capable of holding an insoluble solid sample in suspension. *Proprietary name*: Cab-O-Sil.

fume hood a work space contained under a hood from which air is extracted to remove harmful vapours.

function 1 *(in chemistry)* a **functional group**. **2** *(in mathematics)* **a** either of two variables so related to each other that for any value of one variable there is a corresponding value of the other. **b** a variable or expression that can take a set of values each of which is associated with the magnitude of an independent variable or variables. **3** *(in physiology)* the normal vital activity of a cell, organ, or tissue within an organism. **—functional** *adj.*

functional antagonism 1 antagonism arising by the antagonist's producing an opposite effect to the substance being antagonized through the antagonist's action at a different receptor. **2** antagonism arising when the antagonist interferes with events that follow receptor activation by the substance being antagonized.

functional cloning a cloning strategy in which knowledge of a gene's product (function) is used to clone the gene. An example is the gene for the β chain of hemoglobin responsible for sickle-cell anemia. This is in contrast to **structural cloning** where the function of the gene is not known. A common procedure would be to construct a DNA oligonucleotide based on the amino-acid sequence of the peptide and use this as a probe to isolate the gene from a DNA library. In cases where one protein is dominant in a cell, such as hemoglobin in the reticulocyte, the preparation of a cDNA from the mRNA also provides a useful probe for gene isolation.

functional genomics the systematic analysis of genes, their encoded proteins, and the relationships between gene activity and cell function at the level of whole genomes.

functional group *or* **function** *(in chemistry)* any **group** (def. 1) in a molecule of an organic compound that confers characteristic chemical and physical properties on the molecule and that may be considered to have replaced a hydrogen atom in a molecule of the corresponding hydrocarbon, e.g. the hydroxyl group in an alcohol.

functional polymer 1 a polymer that bears specified chemical groups. **2** a polymer that has specified physical, chemical, biological, pharmacological, or other uses. Examples of functions include: catalytic activity; selective binding of particular species; capture and transport of electric charge carriers or energy; and transport of drugs to a particular organ in which the drug is released.

fungicide any biological, chemical, or physical agent able to destroy fungi. **—fungicidal** *adj.*

fungistat any drug, antibiotic, or other agent that inhibits the growth and multiplication of fungi. **—fungistatic** *adj.*

fungus (*pl.* **fungi**) any member of the taxonomic kingdom Fungi, a group of diverse and widespread unicellular, multicellular, or cenocytic eukaryotic organisms that do not contain chlorophyll. Fungi may be parasitic, saprophytic, or symbiotic. They reproduce through spores. *See also* **microfungus**. **—fungal** *adj.*

FUR *abbr. for* fluorouridine (use proscribed; the symbol FUrd is recommended).

FUra *symbol for* (a residue of) the synthetic pyrimidine base **fluorouracil**.

Fura 2 1-[2-(5-carboxyoxazol-2-yl)-6-aminobenzofuran-5-oxyl]-2-(2′-amino-5′-methylphenoxy)-ethane-*N*,*N*,*N*′,*N*′-tetraacetic acid; a highly sensitive calcium ion chelator that exhibits a spectral shift on binding Ca^{2+}. Calcium ion concentration can be measured directly, independent of dye concentration, by measuring the ratio of fluorescence at 510 nm after excitation at 340 nm and then at 380 nm. It is frequently used as the acetoxymethyl ester (Fura 2/AM, Fura 2-pentakis(acetoxymethyl)ester), which is a membrane-permeable derivative that can enter cells, after which it is rapidly hydrolysed by cytoplasmic esterases to Fura 2, which remains trapped within the cell and can thus report the intracellular Ca^{2+} concentration. *See also* **Quin-2**.



furan *the trivial name for* oxa-2,4-cyclopentadiene, C_4H_4O. *See also* **furanose**.

furanoid furan-like, i.e. describing a molecular structure that consists of or contains a ring of four carbon atoms and one oxygen atom (as in furan).

furanose *symbol*: *f*; any monosaccharide or monosaccharide derivative whose molecule contains a furanoid ring. *Compare* **pyranose**, **septanose**.

furanoside any glycoside in which the sugar moiety is in the furanose form.

FUrd *symbol for* (a residue of) the ribonucleoside fluorouridine (*see* **fluorouracil**).

furin the mammalian counterpart of **kexin**.

furyl either 2-furyl or 3-furyl, the two oxa-2,4-cyclopentadienyl groups derived from a molecule of **furan** by loss of a hydrogen atom from C-2 and C-3 respectively.

fusaric acid 5-butylpyridine-2-carboxylic acid; an antibiotic originally isolated from the fungus *Fusarium heterosporium* and obtained also from *Gibberella fujikuroi*. It inhibits **dopamine *β*-hydroxylase** and has hypotensive activity.



fused ring *(in chemistry)* any ring of atoms in a molecule that is joined to another ring of atoms in such a way that two atoms are common to both rings.

fused rocket immunoelectrophoresis a modification of **rocket immunoelectrophoresis** designed to follow the distribution of proteins among the fractions obtained in a separation experiment. Small volumes of fractions obtained in the separation experiment are placed in a row of sample wells in an antibody-free agarose gel and the samples are allowed to diffuse into the gel for 30–60 min. The proteins are then forced at right angles into an antibody-containing gel by electrophoresis; the resulting precipitation lines (rockets) show the elution profiles for each individual protein in the separation experiment and the distance between the precipitation line and the corresponding well is proportional to the amount of antigen precipitated.

fusel oil a colourless, oily liquid of variable composition obtained as a by-product in the distillation of alcoholic fermentation liquors. It contains chiefly isopentanol, 2-methyl-1-butanol, isobutanol, and propanol. It is considerably more toxic than ethanol. [From German *fuseln*, to bungle.]

fusicoccin a toxin produced by the fungus *Fusicoccus amygdali* that infects peach and almond trees. Its receptor is a 14.3.3 protein that binds proteins containing a conserved sequence that includes a phosphorylated serine residue. It activates the plasma membrane H^+ ATPase in a variety of plant cell types, induces stomatal opening and consequent wilting of leaves, enhances growth rates, and breaks seed dormancy.

fusidic acid 3*α*,11*α*,16*β*-trihydroxy-4*α*,8,14-trimethyl-18-nor-5*α*,8*α*,9*β*,13*α*,14*β*-cholesta-17(20),24-dien-21-oic acid 16-acetate; a steroid antibiotic, structurally related to cephalosporin P (*see* **cephalosporin**) and isolated from the fermentation broth of *Fusidium coccineum*. Fusidic acid is active particularly against Gram-positive organisms, especially *Staphylococcus* spp. It prevents translocation during protein synthesis and inhibits the accumulation of ppGpp.



fusiform spindle-shaped; elongated and tapering at both ends.

fusin *or* **HIV entry cofactor**; a putative G-protein-coupled membrane receptor (352 amino acids) that cooperates with CD4 on immune cell surfaces and permits them to fuse with the HIV surface. It shows 37% sequence identity with the interleukin 8 (IL-8) receptor.

fusion **1** the act or process of melting. **2** the act or process of melting together or uniting. **3** the process whereby two membranes are joined together, as in **cell fusion**. **4** the process whereby nuclei of light elements are united to form nuclei of heavier elements with the release of energy: **nuclear fusion**. **5** the state of being fused. **6** something produced by fusion. **7** *(in molecular biology)* the act, process, or result of artificially linking genes that code for two different proteins, with the aim of generating a **fusion protein**.

fusion protein an expression product resulting from the fusion of two genes. Such a protein may be produced, e.g., in recombinant DNA expression studies or, naturally, in certain viral **oncogenes** in which the oncogene is fused to ***gag***. Their production sometimes results from the need to place a cloned eukaryotic gene under the control of a bacterial promoter for expression in a bacterial system; sequences of the bacterial system are then frequently expressed linked to the eukaryotic protein. Fusion proteins are used for the analysis of structure, purification, function, and expression of heterologous gene products.

fusogen any agent, or set of conditions, that gives rise to fusion of membranes, including cell membranes (and hence of cells). Killed Sendai virus was formerly much used for this purpose but now polyethylene glycol is commonly used as a fusogen particularly in the preparation of hybridomas for the production of monoclonal antibodies. —**fusogenic** *adj.*

futile cycle any metabolic cycle that, if not controlled, acts as an ATPase and hence converts chemical energy (stored as ATP) to heat. For example, a coupling of phosphofructokinase, which converts fructose 6-phosphate to fructose 1,6-bisphosphate at the expense of ATP, with fructose-bisphosphatase, which hydrolyses fructose 1,6-bisphosphate to fructose 6-phosphate and (inorganic) phosphate, can form a cyclic process whose net effect is merely the hydrolysis of ATP to ADP and phosphate. A futile cycle may be an important control mechanism in some physiological conditions.

fuzzy coat *or* **fuzzy layer** the indistinct layer seen on electron microscopy outside the cell coat of various eukaryotic cells, e.g. cells of mammalian intestinal epithelium and a number of single-celled amoebae. It is composed principally of glycoproteins.

fuzzy onions *abbr.*: fzo; a mutant of *Saccharomyces cerevisiae* in which mitochondria undergo abnormal fission with fragmentation.

Fv fragment the N-terminal part of the **Fab fragment** of an immunoglobulin molecule, consisting of the variable portions of one light chain and one heavy chain.

FXR *abbr. for* farnesoid X receptor.

FYN a gene family encoding nonreceptor tyrosine kinases of the Src family (*see* ***src***) that are implicated in the control of cell growth. The gene product, $p59^{fyn}$, associates with the p85 subunit of **1-phosphatidylinositol 3-kinase**. The proteins undergo myristoylation and phosphorylation on serine and tyrosine residues; overexpression transforms fibroblasts. The alternative gene symbols are *SYN* (from *src*/*yes*-related novel gene) and *SLK*.

FYVE a protein sequence of ≈70 amino acids that contains two zinc atoms coordinated by eight cysteine residues, the third cysteine being surrounded by a highly conserved basic sequence. It forms two pairs of antiparallel beta strands stabilized by coordination with the zinc atoms, termed the **FYVE finger**. The name is based on the first letters of four proteins containing this motif, although this is not found in all proteins of this type. The basic residues form a shallow groove that can accommodate the phosphate group of phosphatidylinositol 3-phosphate. It occurs in many proteins of numerous species (from yeast to mammals) and is involved in membrane trafficking. *See* **FGD1**.

Gg

g *symbol for* **1** gram. **2** gaseous state. **3** gluon.

g **1** *symbol for* acceleration of free fall (formerly known as acceleration due to gravity). **2** *abbr. for gauche*. **3** *symbol for* the electron g-value.

g_n *symbol for* standard acceleration of free fall, a fundamental physical constant equal by definition to 9.806 65 m s^{-2}.

g_N nuclear g-value; a constant for any nucleus that defines the energy of interaction with a magnetic field, e.g. in **NMR spectroscopy**.

G *symbol for* **1** giga+ (SI prefix denoting 10^9 times). **2** gauss (alternative to Gs). **3** a residue of the α-amino acid glycine (alternative to Gly). **4** a residue of the base guanine in a nucleic-acid sequence. **5** a residue of the ribonucleoside guanosine (alternative to Guo). **6** a residue of the monosaccharide glucose (alternative to Glc). **7** ganglioside.

G *symbol for* **1** Gibbs energy. **2** gravitational constant. **3** weight (alternative to *W* or *P*). **4** electric conductance.

G418 *a proprietary name for* the aminoglycoside antibiotic geneticin. Resistance to the antibiotic is conferred by the bacterial gene *neo*^{R}, which encodes aminoglycoside-3′-phosphotransferase,

Ga *symbol for* gallium.

Ga_2 *symbol for* galabiose (alternative to GaOse$_2$).

Ga_3 *symbol for* galatriaose (alternative to GaOse$_3$).

G_M *abbr.for* monosialoganglioside.

GA *abbr. (sometimes) for* **1** glyceric acid. **2** glutamic acid. **3** glucuronic acid.

GAA a codon in mRNA for L-glutamic acid.

GABA *abbr. for* γ-amino-*n*-butyric acid or γ-aminobutyrate.

GABAergic 1 describing a nerve or other cell that is acted upon by γ-aminobutyrate. **2** describing nerves that act by releasing γ-aminobutyrate.

GABA-gated channel *see* **GABA receptor**.

GABA-modulin a brain protein that down-regulates the high-affinity binding site for γ-amino-*n*-butyric acid (GABA) on synaptic membranes.

GABA receptor any of several membrane proteins that bind γ-aminobutyrate (GABA) and mediate its effects as an inhibitory neurotransmitter. GABA$_A$ receptors, known also as GABA-gated channels, function as a Cl$^-$ channel; GABA$_B$ receptors are G-protein-coupled receptors. **Baclofen** is a potent GABA mimetic that is selective for the GABA$_B$ receptor; **muscimol** is its counterpart for the GABA$_A$ receptor. The GABA$_A$ receptor is multimeric, with α (types α1–α6), β (types β1–β4), γ (types γ1–γ3), δ, and ρ subunits. Subunits α and β have four putative transmembrane segments that show some homology with those seen in the nicotinic acetylcholine receptor (nAChR) (*see* **cholinoceptor**). Increased Cl$^-$ ion flux brings about hyperpolarization of an excitatory neuron, which inhibits it from firing on receipt of a normal impulse. **Benzodiazepine** drugs interact with GABA$_A$ receptors at the γ subunit. GABA$_B$ receptors are coupled through G-proteins to stimulation of outward K$^+$ current, inhibition of inward Ca^{2+} channels, inhibition of adenylate cyclase, and stimulation of the phosphatidylinositol–Ca^{2+} system. *See also* **chloride channel**.

gabase *an informal name for* aminobutyrate aminotransferase (EC 2.6.1.19).

GABA shunt *abbr. for* γ-aminobutyrate shunt.

GABA transaminase *see* **4-aminobutyrate transaminase**.

GAC a codon in mRNA for L-aspartic acid.

G-actin the monomeric form of **actin**.

G_{M2}-activator protein a glycosylated protein (162 amino acids), encoded as a precursor by a gene at 5q32-q33, that is essential for hydrolysis by lysosomal β-hexosaminidase A (*see* **hexosaminidase**). Deficiency can result from any of four mutations, and is the cause of the AB variant of **Tay–Sachs disease**.

GADD *abbr. for* growth arrest and DNA damage; either of two proteins (GADD45 and GADD153) that are produced in response to oxidative stress, induce temporary arrest of the cell cycle, and may be involved in DNA repair. Expression of the GADD45 gene is modulated by p53.

Gaddum equation a relationship, suggested to replace the **Hill–Langmuir equation**, that describes the situation when two ligands, A and B, are in equilibrium with a common binding site. It is:

$$P_{AR} = [A]/K_A(1 + [B]/K_B) + [A],$$

where P_{AR} is the proportion of the binding sites occupied by ligand A; the square brackets indicate concentrations. *Compare* **Schild equation**. [After (Sir) John Henry Gaddum (1900– 67), British pharmacologist.]

gadelaidate *the trivial name for* (*E*)-eicos-9-enoate, CH$_3$–[CH$_2$]$_9$–CH=CH–[CH$_2$]$_7$–COO$^-$ (*trans* isomer), the anion derived from gadelaidic acid, (*E*)-eicos-9-enoic acid. *Compare* **gadoleate**.

gadoleate *the trivial name for* (*Z*)-eicos-9-enoate, CH$_3$–[CH$_2$]$_9$–CH=CH–[CH$_2$]$_7$–COO$^-$ (*cis* isomer), the anion derived from gadoleic acid, (*Z*)-eicos-9-enoic acid. *Compare* **gadelaidate**.

gag a gene that encodes the glucosaminoglycan core protein for a **retrovirus**. It is named from group-specific antigen gene, or glucosamino glycan gene. *See also* ***erbA***, ***erbB***.

GAG 1 a codon in mRNA for L-glutamic acid. **2** *abbr. for* glucosaminoglycan.

GAGA factor a DNA-sequence-specific transcription factor in *Drosophila* that binds to several (GA)$_n$ repeats in the promoter for the Hsp70 gene. It acts in concert with **NURF** to disrupt nucleosome spacing in the promoter region.

Gaia a theory of the role of biota in the maintenance of a climatic homeostasis, proposed by British biochemist James Lovelock (1919–) in 1979. The basic concept is that all of the living organisms that inhabit the earth can be regarded as a single vast organism capable of manipulating the atmosphere, geosphere, and hydrosphere to suit its needs. Lovelock named this organism Gaia, after the Greek goddess of the earth.

Gal *symbol for* a residue (or sometimes a molecule) of the aldohexose galactose. In the condensed system of symbolism of sugar residues, it signifies specifically a galactose residue with the common configuration and ring size, i.e. D-galactopyranose.

GAL4 a gene involved in the regulation of galactose utilization in yeast. The GAL4 protein has a zinc-finger motif for binding to its upstream activator sequence (UAS), which it then activates, and a site for binding the complex of the GAL80 protein – encoded by the *GAL80* gene – and galactose. When this is bound, activation by GAL4 protein is prevented.

GalA *symbol for* a residue (or sometimes a molecule) of the uronic acid galacturonic acid.

galabiose *symbol*: Ga$_2$ *or* GaOse$_2$; *the trivial name for* the disaccharide Gal(α1-4)Gal.

galactan any glycan composed solely of galactose residues. The galactans thus form a subgroup of plant hemicelluloses.

galactitol *or* ***meso*-galactitol** *or (formerly)* **dulcitol** *the trivial name for* the hexitol formally derived by reduction of the aldehyde group of either D- or L-galactose. It occurs widely especially in seaweeds and higher plants. It is excreted in human galactokinase deficiency and causes cataracts.

galacto- *prefix (in chemical nomenclature)* indicating a particular configuration of a set of (usually) four contiguous CHOH groups, as in the acyclic form of D- or L-galactose. *See* **monosaccharide**.

galactoceramide *see* **galactosylceramide**.

galactocerebroside *see* **galactosylceramide**.

galactokinase *abbr*.: GLK; EC 2.7.1.6; *systematic name*: ATP:D-galactose 1-phosphotransferase. An enzyme that catalyses the phosphorylation by ATP of D-galactose to D-galactose 1-phosphate, with release of ADP; this initiates the metabolism of galactose. There are two human galactokinases. GLK1, a monomer of 392 amino acids encoded at 17q24, is the major enzyme in various tissues. Mutations in its gene lead to galactokinase deficiency with galactosemia, urinary excretion of galactose and galactitol, and cataracts. GLK2 is encoded on chromosome 15 and shows 35% sequence homology with GLK1. Its metabolic role is unclear.

galactolipid any **glycolipid** containing one or more residues of galactose and/or *N*-acetylgalactosamine. The term includes **galactosylceramide** and **galactosyldiacylglycerol**.

galactomannan any heteroglycan containing D-galactose and D-mannose residues; the structures have not been fully elucidated. They occur in seeds of various plants and trees, probably as storage polysaccharide. *See also* **guaran**.

galactoprotein A *abbr.*: Gap A; *an alternative name for* **fibronectin**.

galactosaemia *a variant spelling* (*esp. Brit*) *of* **galactosemia**.

galactosamine *symbol*: Gal*p*N; *the trivial name for* the aminodeoxysugar 2-amino-2-deoxygalactopyranose; there are two enantiomers, D- and L-galactosamine. D-Galactosamine (*symbol*: D-Gal*p*N), formerly known as **chondrosamine**, is a constituent (commonly as its *N*-acetyl derivative) of some glycolipids and of chondroitin sulfate, dermatan sulfate, and many bacterial glycosaminoglycans.

galactose *symbol*: Gal; *the trivial name for* the aldohexose *galacto*-hexose; there are two enantiomers, D- and L-galactose. D-Galactose (*symbol*: D-Gal), commonly known as galactose, and formerly known as **brain sugar** or **cerebrose**, rarely occurs free but is widely distributed in combined form in plants, animals, and microorganisms as a constituent of many oligo- and polysaccharides; it occurs also in **galactolipids** and as its glucoside in **lactose** and **melibiose**. Residues of both D-galactose and 3,6-anhydro-L-galactose (*symbol*: 3,6An-L-Gal) occur in the disaccharide **agarobiose** and in polysaccharides such as **agaropectin** and **agarose**.



β-D-galactose

galactose/glucose binding protein a signal transducing protein for bacterial chemotaxis.

galactosemia *or* (*esp. Brit.*) **galactosaemia** comparatively rare condition in humans in which there is a supranormal concentration of D-galactose in the blood and a specific inability to metabolize galactose. It is caused either by (1) a hereditary autosomal recessive trait in which there is a virtual absence of **UDPglucose–hexose-1-phosphate uridylyltransferase** activity; or less frequently (2) an inherited autosomal recessive trait in which there is a deficiency in **galactokinase** activity.

galactose oxidase EC 1.1.3.9; a copper-containing enzyme that catalyses the oxidation by dioxygen of D-galactose to D-*galacto*-hexodialdose and H_2O_2.

galactose-1-phosphate uridylyltransferase *see* **UDPglucose–hexose-1-phosphate uridylyltransferase**.

galactose-6-sulfate sulfatase *see* ***N*-acetylgalactosamine-6-sulfatase**.

galactosialidosis a lysosomal storage disorder, transmitted as an autosomal recessive trait, that results from deficiency of three lysosomal enzymes: protective protein/cathepsin A (PPCA), β-galactosidase, and neuraminidase. This causes accumulations of sialooligosaccharides in lysosomes and their excretion in urine. Three clinical phenotypes are recognized on the basis of age of onset and clinical severity: early infantile; late infantile; and juvenile or adult. At least 12 point mutations in the gene at 20q13.1 for PPCA are resposnsible for the condition.

galactosidase either of two types of enzyme: α-galactosidase EC 3.2.1.22; *systematic name*: α-D-galactoside galactohydrolase; *other name*: melibiase. An enzyme that hydrolytically removes terminal nonreducing α-D-galactose residues in α-galactosides, including galactose oligosaccharides, galactomannans, and galactolipids. β-galactosidase EC 3.2.1.23; *systematic name*: β-D-galactoside galactohydrolase; *other name*: lactase. An enzyme that removes terminal β-D-galactose residues in β-galactosides by hydrolysis.

galactoside any **glycoside** in which the sugar moiety is galactose.

galactoside acetyltransferase EC 2.3.1.18; *recommended name*: galactoside *O*-acetyltransferase; *systematic name*: acetyl-CoA:β-D-galactoside 6-acetyltransferase; *other name*: thiogalactoside transacetylase. An enzyme that catalyses the acetylation by acetyl-CoA of β-D-galactoside to 6-acetyl-β-D-galactoside with release of GDP. Such an enzyme is the *lacA* gene product in *Escherichia coli* (*see* ***lac* operon**). Its function remains unclear.

galactoside 3(4)-L-fucosyltransferase EC 2.4.1.65; *systematic name*: GDP-L-fucose:β-D-galactosyl-*N*-acetyl-D-glucosaminyl-R 4-L-fucosyltransferase; *other name*: Lewis transferase. An enzyme that catalyses the transfer by GDP-L-fucose of fucose to 1,3-β-D-galactosyl-*N*-acetyl-D-glucosaminyl-R to form 1,3-β-D-galactosyl-(α-1,4-L-fucosyl)-*N*-acetyl-D-glucosaminyl-R with release of GDP; this forms the blood group determinant Le^a of **Lewis antigen**. The enzyme also acts on the corresponding 1,4-galactosyl derivative, forming 1,3-L-fucosyl links. It is a type II membrane glycoprotein, and a product of the Lewis blood group locus.

β-galactoside permease any of several transport proteins in bacteria that facilitate the uptake of β-galactosides. An example is melibiose carrier protein from *Klebsiella pneumoniae.* This is responsible for melibiose transport; it is capable of using hydrogen and lithium cations as coupling cations for cotransport, depending on the particular sugar transported (e.g. H^+-melibiose, Li^+-lactose), but cannot recognize Na^+ ions although it is an integral membrane protein of the sodium:galactoside symporter family. *See also* **lactose permease**.

galactosylceramidase EC 3.2.1.46; an enzyme that catalyses the hydrolysis of D-galactosyl-*N*-acylsphingosine to D-galactose and *N*-acylsphingosine.

galactosylceramide *the recommended term for* any D-galactosyl-*N*-acylsphingosine, i.e. any **cerebroside** in which the sugar moiety is D-galactose (less correctly termed **galactoceramide** or **galactocerebroside**).

galactosylceramide lipidosis *or* **Krabbe's disease** *or* **globoid cell leukodystrophy** one of a number of **sphingolipidoses** or sphingolipid lysosomal storage diseases. A rapidly progressive, invariably fatal, hereditary (autosomal recessive) disease of human infants caused by deficient activity of galactocerebroside β-galactosidase (galactosylceramidase; EC 3.2.1.46). Clinical symptoms usually start between the ages of 3 and 6 months and the condition is characterized by severe mental and motor deterioration and the presence of numerous globoid cells containing galactosylceramide in the white matter of the brain.

galactosylceramide sulfotransferase EC 2.8.2.11; an enzyme involved in **sulfatide** biosynthesis that catalyses the reaction between a galactosylceramide and 3′-phosphoadenylylsulfate to form galactosylceramide sulfate and adenosine 3′,5′-bisphosphate.

galactosyldiacylglycerol any of a class of lipids in which one or two galactose residues are in glycosidic linkage with a 1,2-diacylglycerol (loosely termed mono- and digalactosyldiacylglycerols), more specifically as, e.g., 1,2-diacyl-*sn*-glycerol 3-β-D-galactoside or (preferred, as glycosphingolipids are named this way) 1,2-diacyl-3-β-D-galactosyl-*sn*-glycerol. They are widely distributed in plants and are the main constituent lipids of chloroplasts, where they occur in the thylakoid membrane. They are also present in mitochondria.

β-1,3-galactosyl-*O*-glycosyl-glycoprotein β-1,6-*N*-acetylglucosaminyltransferase EC 2.4.1.102; *other names*: *O*-glycosyl-oligosaccharide-glycoprotein; *N*-acetylglucosaminyltransferase I; β^6-*N*-acetylglucosaminyltransferase; core debranching enzyme; an enzyme that catalyses the reaction between UDP-*N*-acetyl-D-glucosamine and β-D-galactosyl-1,3-*N*-acetyl-D-galactosaminyl-R to form β-D-galactosyl-1,3-(*N*-acetyl-β-D-glucosaminyl-1,6)-*N*-acetyl-D-galactosaminyl-R with release of UDP. It introduces branches into O-linked glycoprotein oligosaccharides.

galactosyltransferase any enzyme belonging to the sub-subclass hexosyltransferases, EC 2.4.1, for which the glycosyl group is galactosyl; the acceptor is typically another carbohydrate molecule or lipid. *See also* **B-transferase**, **lactose synthase**, **Lewis transferase**.

galactowaldenase *a former name for* **UDPglucose 4-epimerase**.

galacturonan *or (formerly)* **polygalacturonide** any glycan composed solely of galacturonic-acid residues; a specific kind of glycuronan.

galacturonate **1** the anion of galacturonic acid. **2** any salt or ester of galacturonic acid.

galacturonic acid *symbol*: GalA *or (formerly)* GalU *or* GalUA; the uronic acid formally derived from galactose by oxidation of the hydroxymethylene group at C-6 to a carboxyl group. There are two enantiomers, D- and L-galacturonic acid; D-galacturonic acid is a component of plant gums and bacterial cell walls.



β-D-galacturonic acid

galanin a biologically active neuropeptide, with wide distribution in the central neurons of several mammalian species. Human galanin has the 30-residue sequence

GWTLNSAGYLLGPHAVGNHRSFSDKNGLTS.

The peptide effects contraction of smooth muscle of the gastrointestinal and genitourinary tracts, and regulates somatotropin release; it may be involved in the control of adrenal secretion, and is also produced in the islets of Langerhans from stimulated intra-islet nerve terminals. Galanin inhibits insulin release *in vivo* and *in vitro*, and inhibits formation of cyclic AMP in cells stimulated by **glucagon-related peptide**. A fragment, GWTLNSAGYLLGPHAI, is an agonist at the hippocampal galanin receptor.

galaptin any of various proteinaceous, β-galactoside-specific, animal lectins of relatively low molecular mass, that are isolated from a number of developing and adult tissues, and are believed to mediate intercellular adhesion in some developmental systems.

galectin a secreted carbohydrate-binding protein that binds CD45 and inhibits its receptor tyrosine phosphatase activity.

gall **1** an abnormal swelling or growth produced by a plant in response to the activities of various fungi, mites, and insects, especially members of the Cynipidae and Cecidomyidae. Insect eggs and larvae are often found in galls. **2** *a former name for* **bile**.

gallate **1** the anion of gallic acid, 3,4,5-trihydroxybenzoic acid, a phenolic acid. **2** any salt or ester of gallic acid. The esters and polyesters are very widely distributed in angiosperms, usually as **gallotannins**.

gall bladder a hollow, muscular organ, found in many vertebrates, that receives dilute **bile** from the liver, concentrates and stores it, and discharges it into the duodenum. *See* **gall stone**.

gallotannic acid *see* **tannic acid**.

gallotannin *or* **hydrolysable tannin** any **tannin** consisting of a molecule of a polyhydric alcohol (usually glucose) esterified with several gallic-acid molecules, each of which may itself be esterified with a further gallic acid molecule, and so on.

gallstone *or* **cholelith**; a concretion that forms in the gall bladder. The most common type are light-coloured stones, usually multiple and multifaceted, consisting mostly of cholesterol with some protein and calcium bilirubinate. These usually form as a result of bile stasis, supersaturation with cholesterol, and/or presence of nucleation factors such as glycoprotein in mucus, bacteria, or epithelial cells. They occur in about 20% of women and about 5% of men between 50 and 65 years of age, are usually asymptomatic but may produce epigastric pain and obstructive jaundice. They are usually associated with obesity. Less common are brown or black gritty pigment stones consisting mostly of calcium bilirubinate. These are likely to be associated with chronic hemolytic anemia, and form at an earlier age.

Gal*p* *symbol for* a galactopyranose residue.

Gal*p*A *symbol for* a residue (or sometimes a molecule) of galactopyranuronic acid.

Gal*p*N *symbol for* a residue (or sometimes a molecule) of the aminodeoxysugar **galactosamine**.

Gal*p*NAc *symbol for* a residue (or sometimes a molecule) of the acetamidodeoxysugar *N*-acetylgalactosamine.

GalU *or* **GalUA** *former symbol* for **galacturonic acid** (GalA now recommended).

galvanic cell *an alternative name for* **cell** (def. 3).

gamete a mature reproductive cell whose nucleus (and often cytoplasm) fuses with that of another gamete of similar origin but of opposite sex to form a **zygote**, which develops into a new individual. Gametes are haploid and are differentiated into male (+) and female (–).

gamma *symbol*: γ (lower case) *or* Γ (upper case); the third letter of the Greek alphabet. For uses *see* **Appendix A**.

gamma chain *or* **γ chain** **1** the **heavy chain** of an IgG immunoglobulin molecule. **2** one of the two types of subunit in a human fetal hemoglobin (Hb F) molecule.

gamma globulin *or* **γ-globulin** any of a band of serum proteins that migrate most slowly on electrophoresis. In humans, this normally constitutes quantitatively the largest fraction of the total globulins. As the γ-globulins are predominantly antibodies, and are not synthesized in the liver as are virtually all the other serum proteins, the albumin/globulin ratio has traditionally been a useful indicator of liver function. The γ-globulins may be separated from the other serum globulins in pooled adult serum, and may then be used for administration by intramuscular injection to provide passive immunity in premature infants or for those in contact with cases of infectious hepatitis. Such γ-globulin preparations tend to form aggregates spontaneously; these can lead to severe anaphylactic reactions when administered intravenously, owing to their ability to aggregate platelets, and to activate complement and generate C3a and C5a anaphylatoxins. In certain diseases, such as Bruton's congenital agammaglobulinemia, the production of immunoglobulin in affected males is grossly depressed. In patients with myeloma, the γ-globulin band on electrophoresis of serum proteins is markedly more prominent, indicating the presence of a raised antibody against an unknown antigen. *See also* **globulin**.

galaptin any of various proteinaceous, β-galactoside-specific, animal lectins of relatively low molecular mass, that are isolated from a number of developing and adult tissues, and are believed to mediate intercellular adhesion in some developmental systems.

gamma helix *or* **γ-helix** a polypeptide chain conformation in which each amide group forms hydrogen bonds with the group's five residues away in each direction along the chain. It has 5.1 amino-acid residues per turn; the translation along the helical axis is 0.99 Å per residue, 5.03 Å per turn.

gamma-hydroxybutyrate *see* **γ-hydroxybutyrate**.

gamma-peptidase *see* **X-Pro dipeptidase**.

gamma radiation *or* **γ-radiation** electromagnetic radiation with wavelengths in the range 0.1–100 pm (frequencies 3–3000 EHz) emitted by some atomic nuclei during **transformation** (def. 3). Gamma rays have shorter wavelengths than X-rays and higher photon energies.

gammopathy any pathological increase in production of an immunoglobulin (usually IgM, IgA, or IgG) or Bence-Jones protein. Gammopathies may be monoclonal or polyclonal and are associated with increased immunoglobulin synthesis.

gamone any of a group of biological agents secreted by gametes that act on gametes of the opposite sex to initiate the processes leading to fertilization. They may be **gynogamones**, liberated from female gametes, or **androgamones**, liberated from male gametes.

ganciclovir *or* **gancyclovir** 9-[(1,3-dihydroxy-2-propoxy)methyl]-guanine; a nucleoside analogue of **acyclovir** that is more potent against cytomegalovirus. When phosphorylated by virally encoded thymidine kinase it inhibits DNA synthesis through inhibition of DNA polymerase.

ganglion (*pl.* **ganglia**) a cluster of nerve cells and associated glial cells located outside the central nervous system.

ganglioside any ceramide oligosaccharide carrying, in addition to other sugar residues, one or more sialic residues. Gangliosides were first isolated from ganglion cells (neurons) of the grey matter of the brain but are in fact widely distributed in vertebrate tissues. They are *N*-acetyl- (or *N*-glycoloyl-) neuraminosyl-(X)osylceramides, where (X) stands for the root name of the neutral oligosaccharide to which the sialosyl residue is attached; the acyl groups in the ceramide moiety are commonly stearoyl or lignoceroyl. Gangliosides are designated by G for ganglioside, plus subscript M, D, or T for mono-, di-, or trisialo, respectively, followed by a subscript arabic numeral to indicate the sequence of migration in thin-layer chromatograms. The principal gangliosides of human brain are:

(1) monosialogangliosides: G_{M1}, Gal(β1-3)GalNAc(β1-4)(NeuAc(α2-3))Gal(β1-4)Glcβ1Cer (G_{A1} denotes the asialo derivative of G_{M1}); G_{M2}, GalNAc(β1-4)(NeuAc(α2-3))Gal(β1-4)Glcβ1Cer (G_{A2} denotes the asialo derivative of G_{M2}); G_{M3}, NeuAc(α2-3)Gal(β1-4)Glcβ1Cer;

(2) disialogangliosides: G_{D1a}, NeuAc(α2-3)Gal(β1-3) GalNAc(β1-4)(NeuAc(α2-3))Gal(β1-4)Glcβ1Cer; G_{D1b}, Gal(β1-3)GalNAc(β1-4)(NeuAc(α2-8)NeuAc(α2-3))Gal(β1-4)Glcβ1Cer; G_{D3}, NeuAc(α2-8)NeuAc(α2-3)Gal(β1-4)Glcβ1Cer;

(3) trisialogangliosides: G_{T1a}, NeuAc(α2-8)NeuAc(α2-3)Gal(β1-3)GalNAc(β1-4)(NeuAc(α2-3))Gal(β1-4)Glcβ1Cer; G_{T1b}, NeuAc (α2-3)Gal(β1-3)GalNAc(β1-4)(NeuAc(α2-8)NeuAc(α2-3))Gal (β1-4)Glcβ1Cer.

ganglioside galactosyltransferase EC 2.4.1.62; *other name*: UDPgalactose–ceramide galactosyltransferase; an enzyme that catalyses the reaction between UDPgalactose and *N*-acetyl-D-galactosaminyl-(*N*-acetylneuraminyl)-D-galactosyl-D-glucosyl-*N*-acylsphingosine to form the **ganglioside** G_{M1}, with release of UDP.

gangliosidosis any of a group of inherited human diseases involving defects in **ganglioside** breakdown. They are characterized by: progressive mental and motor deterioration with fatal outcome; autosomal recessive inheritance; neuronal lipidosis secondary to storage of gangliosides and structurally related glycolipids, polysaccharides, or glycoproteins; and absence or severe deficiency of specific lysosomal glycohydrolases. The principal gangliosidoses are G_{M1} and G_{M2} gangliosidoses (the names indicating which ganglioside accumulates). G_{M1} gangliosidoses are due to a striking deficiency of *β*-galactosidase activity when tested using G_{M1} or galactose-containing glycoproteins as substrates. Type 1 or infantile G_{M1} gangliosidosis is a generalized gangliosidosis with bony involvement and onset of signs from birth or shortly after. Type 2 or juvenile G_{M1} gangliosidosis is of slower onset than type 1 and with milder bony abnormalities. There are three types of G_{M2} gangliosidosis. Type 1 G_{M2} gangliosidosis (*or* **Tay–Sachs disease**) is the commonest gangliosidosis, occurring especially in Ashkenazi Jews. It is caused by a severe deficiency of hexosaminidase A. Type 2 G_{M2} gangliosidosis (*or* **Sandhoff's disease**) occurs much less frequently than Tay–Sachs disease and is caused by severe deficiency of both hexosaminidases A and B; globoside accumulates in addition to G_{M2} in this disease. Type 3 or juvenile G_{M2} gangliosidosis is caused by either severe or partial deficiency of hexosaminidase A.

gangliotetraose *symbol*: Gg_4 *or* $GgOse_4$; *a trivial name for* the tetrasaccharide Gal(β1-3)GalNAc(β1-4)Gal(β1-4)Glc.

gangliotriaose *symbol*: Gg_3 *or* $GgOse_3$; *a trivial name for* the trisaccharide GalNAc(β1-4)Gal(β1-4)Glc.

$GaOse_2$ *symbol for* galabiose (alternative to Ga_2).

$GaOse_3$ *symbol for* galatriaose (alternative to Ga_3).

gap **1** a space introduced into the written form of a sequence of residues in a biopolymer to bring part of that sequence into register with a similar region of sequence in another polymer; typically used to effect protein or nucleotide sequence alignment. **2** a discontinuity in one of the two strands of duplex DNA resulting from enzymic elimination of one or more nucleotide residues. *Compare* **nick**.

GAP *abbr. for* **1** GnRH-associated peptide (*see* **gonadotropin-releasing hormone**). **2** *abbr. for* GTPase activating protein; a protein that activates the hydrolysis of GTP bound to certain monomeric proteins, especially $p21^{ras}$ (Ras, *see* **RAS**), but also for other Ras-related proteins, e.g. Rho (*see* **Rho protein**) and Ran (*see* **RAN**). Since GTP-bound Ras is the active form, binding to GAP inactivates it. The protein has SH2 and SH3 domains (*see* **SH domains**) and **pleckstrin homology domains**. RGS proteins are GAPs for the α subunit of certain trimeric G-proteins.

Gap a *abbr. for* galactoprotein A (i.e. plasma **fibronectin**).

GAPDH *abbr. for* glyceraldehyde-3-phosphate dehydrogenase. It is used as an internal standard in Northern blotting and PT-PCR because its mRNA is believed to be expressed constitutively in mammalian tissues.

gap gene any of at least six genes of *Drosophila* that act early in embryogenesis to define the coarsest subdivisions of the embryo. Mutations in these genes result in gaps in the segmentation pattern; the **Krüppel** and **hunchback** proteins are products of gap genes.

gap junction *or* **nexus** any specialized area of the plasma membranes of apposed vertebrate cells where the membranes are 2–4 nm apart and penetrated by a **connexon** that bridges the extracellular space and provides open means of communication between the cytoplasm of one cell and that of the other cell. *Compare* **tight junction**.

Gap1p *abbr. for* general amino acid permease protein 1; a membrane protein of *Saccharomyces cerevisiae* that permits uptake of amino acids. It is induced by nitrogen starvation. If the yeasts are given a nitrogen-rich source, Gap1p is targeted for degradation by polyubiquitination and its synthesis is repressed.

gap penalty a numerical cost for inserting a gap in a sequence alignment. Depending on the alignment algorithm used, there may be a single gap penalty, or an **affine gap penalty** containing separate costs for initiating and extending the gap. With affine gap penalties the extension penalty is usually much lower than the insertion penalty. This penalizes gap insertions while recognizing that, where insertions exist, they often span more than one residue (hence it costs more to open a gap than it does to extend it once the gap has been opened).

gap phase either of the two phases, designated G_1 and G_2, in the cell-division cycle during **interphase** in growing eukaryotic cells during which there is no DNA synthesis.

gap repair the process of repair of a **gap** (def. 2) in one strand of a duplex DNA molecule.

garosamine 3-deoxy-4-*C*-methyl-3-(methylamino)-L-arabinose; a component of **gentamicins**.

gas a substance whose physical state is such that it always occupies the whole of the space in which it is contained, irrespective of the amount present. *See also* **gas laws**; **ideal gas**.

gas chromatography *abbr.*: GC; any form of chromatography in which the mobile phase is a gas. The term commonly refers to **gas–liquid (partition) chromatography** in which the stationary phase is a liquid, normally deposited on a solid support in a coiled column of glass or stainless steel, or the wall of a capillary column, but it also includes **gas–solid chromatography**, in which the stationary phase is a solid. The column is normally heated in an oven.

gas chromatography/mass spectrometry *abbr.*: GC/MS; an analytical technique that combines the separation process of **gas chromatography** with the highly selective detection technique of **mass spectrometry**.

gas constant *symbol*: *R*; a fundamental physicochemical constant; $R = 8.314\,471 \pm 0.000\,014\ \mathrm{JK^{-1}mol^{-1}}$.

gas exchange *(in physiology)* the exchange of gases between an organism and its environment. It includes oxygen uptake and carbon dioxide elimination in the respiration of all aerobic organisms, including plants, and carbon dioxide uptake and oxygen release in photosynthetic processes.

gas flow counter any gas-filled radiation detector in which the gas filling is renewed continuously. It may be operated in either the Geiger or the proportional regions of the voltage– current curve. Such devices are especially useful for detection and counting of alpha and soft-beta emitters, as no window is present to absorb the radiation.

gas laws either of two laws describing the effects of changes in pressure, *p*, and thermodynamic temperature, *T*, on the volume, *V*, of an ideal gas. **Boyle's law** (*or* **Mariotte's law**) states that at constant temperature the volume of a given mass of gas is inversely proportional to the pressure; i.e. pV = a constant. **Charles's law** states that at constant pressure the volume of a given mass of gas is directly proportional to its thermodynamic temperature; i.e. V/T = a constant. These two laws may be combined in the expression: $pV \propto T$, or, for one mole of gas: $pV = RT$, where R is the **gas constant**.

gas–liquid (partition) chromatography an analytical method based on the partition chromatographic separation of the components of a mixture through the use of a stationary liquid phase held in place on a solid support and a mobile gas phase flowing over the liquid phase in a controlled manner. Typically, the column is heated to temperatures in the range 50–300°C and the technique is applicable to compounds that partition appreciably into the vapour phase in that range. Detection of the eluents is commonly by a **flame ionization detector**.

GASP *abbr. for* genome annotation assessment project; *see* **critical assessment competition**.

gas–solid chromatography *see* **gas chromatography**.

gastr+ *a variant form of* **gastro+** (before a vowel).

gastric of, pertaining to, or derived from the stomach.

gastric acid the hydrochloric acid that is secreted from parietal (or oxyntic) cells of the wall of the stomach and forms part of the **gastric juice**.

gastric inhibitory peptide *abbr.*: GIP; *or* **glucose-dependent insulinotropic peptide** *or* **glucose-dependent insulin-releasing peptide** a 42-residue polypeptide hormone produced by the K cells of the proximal small intestine in response to glucose in the intestine. It is structurally related to glucagon, secretin, and vasoactive intestinal polypeptide having the sequence (human) YAEGTFISDYSIAMD-KIHQQDFVNWLLAQKGKKNDWKHNITQ, porcine being similar but with Arg^{18} and Ser^{34}. It inhibits gastric secretion and motility (**enterogastrone effect**), and stimulates insulin release when administered during hyperglycemia (**insulinotropic effect**); in the latter action GIP may be synonymous with **incretin**.

gastric inhibitory peptide receptor *abbr.*: GIP receptor; any of the G-protein-associated membrane receptors that bind **gastric inhibitory peptide** (GIP) and activate adenylate cyclase. The rat protein consists of 455 amino acids (52.26 kDa), of which residues 1–18 are the signal peptide, and 19–455 are the receptor.

gastric juice the thin, clear, acidic fluid secreted by glands of the stomach mucosa in response to the ingestion of food. It contains mucus, intrinsic factor, hydrochloric acid (about 155 mm in humans) from the parietal cells, and **pepsinogen**, the precursor of pepsin proteolytic enzymes.

gastricsin EC 3.4.23.3; *other names*: pepsin C, pig parapepsin II; an enzyme of the pepsin family that appears to be present in the gastric juice of most vertebrates. It effects preferential cleavage at Tyr-|-Xaa bonds. It is a single-chain phosphoprotein formed by limited proteolysis of pepsinogen C with a more restricted specificity than pepsin A but high activity towards hemoglobin.

gastrin any of various members of a group of interrelated peptide hormones from the **G cells** of the pyloric antral mucosa of the stomach, and of the proximal duodenum, that strongly stimulate acid secretion by the stomach mucosa. There are three principal, biologically active forms: **big gastrin** (*or* G-34); **little gastrin**, (*or* G-17 *or* gastrin I); and **mini gastrin** (*or* G-14); these have 34, 17, and 14 amino-acid residues, respectively. The sequence of human big gastrin (gastrin I in parentheses, but with pE for the terminal Q) is

pELGPQGPPHLVADPSKK(QGPWLEEEEEA-YGWMDF-NH_2),

where pE indicates pyroglutamyl. Each has a counterpart, e.g. G-17S (*or* gastrin II), in which the tyrosyl residue is sulfated. There are other, larger immunoreactive forms, known as **big-big gastrins**, that elute from a gel column before G-34. The entire physiological activity is possessed by the C-terminal tetrapeptide amide sequence that ends in a phenylalaninamide residue. The C-terminal pentapeptide sequence of gastrin is the same as that of **cholecystokinin** and **cerulein**. *See also* **gastrinoma**, **pentagastrin**, **Zollinger–Ellison syndrome**.

gastrinoma a tumour of the gastrin-producing **G cells** of the pancreas, stomach, or duodenum. Gastrinomas are associated with high gastrin levels in the circulating blood, gastric hypersecretion, and fulminant gastroduodenojejunal ulcerations (**Zollinger–Ellison syndrome**).

gastrin receptor *see* **cholecystokinin receptor**.

gastrin-releasing protein a growth factor secreted by some small-cell lung cancers.

gastro+ *or (often before a vowel)* **gastr+** *comb. form* meaning stomach. [From Greek *gastēr*, belly.]

gastroenteric *an alternative term for* **gastrointestinal**.

gastrointestinal *or* **gastroenteric** of, or pertaining to, the stomach and intestines.

gastrointestinal hormone any member of a diverse group of peptides with hormone or hormone-like actions that occur in specific cells of the gastrointestinal tract, the pancreatic islets, and other locations. The best characterized include **cholecystokinin**, **gastric inhibitory polypeptide**, **gastrin**, **glucagon**, **insulin**, **motilin**, **neurotensin**, **pancreatic polypeptide**, **secretin**, **substance P**, and **vasoactive intestinal polypeptide**. *See also* **gut hormone**.

gastrula an early stage of development of an animal embryo, following the blastula, in which the cells are invaginating to form the rudiment of a gut cavity.

gas vacuole any membrane-bound, gas-containing, intracellular organelle. Gas vacuoles provide aquatic prokaryotes with buoyancy. *See also* **gas vesicle**.

gas vesicle the submicroscopic component of the gas vacuole in certain aquatic prokaryotes, especially cyanobacteria. It is constructed of molecules of a single protein (≈15 kDa), which form a monolayer enclosing a hollow space into which gases diffuse. Typically it is cylindrical with conical ends, 3–300 nm in diameter and 300–1000 nm in length.

GATA-1 *or* **ERYF1** *or* **GF-1** *or* **NF-E1** a transcriptional activator protein that serves as a general switch factor for erythroid development. It binds to DNA sites with the consensus sequence [A/T]GATA[A/G] within regulatory regions of globin genes and other genes expressed in erythroid cells. Other transcription factors with similar sequences are termed **GATA-type**. GATA-1 binds the zinc finger-rich transcription regulator FOG-1.

GATase *see* **glutamine amidotransferase**.

gate *(in electronics)* **1** a logic circuit that gives an output signal only in response to a combination of two or more input signals. **2** a signal that allows or controls the passage of another signal.

gated channel a channel in the membrane of a cell (especially an excitable cell) that allows entry of ions into the cell only under specific conditions. *See also* **ligand-gated**, **voltage-gated ion channel**.

gating the opening and closing of a gated channel.

gating current an electric current arising from the movement of charged groups in the protein of the sodium-ion channels of excitable nerve membranes, during the passage of an action potential, prior to the opening of the channel.

g-atom *abbr. for* gram-atom or gram-atomic weight.

GAU a codon in mRNA for L-aspartic acid.

gauche *abbr.*: *g*; *(in chemical nomenclature)* a conformational descriptor indicating a synclinal conformation. *See* **conformation**.

Gaucher activator *or* **saposin C**; a glycosylated polypeptide derived by appropriate proteolytic cleavage of prosaposin. It is an activator of lysosomal **glucosylceramidase**. Deficiency of prosaposin or saposin C, due to mutation in the prosaposin gene, produces a variant of Gaucher's disease type 3. *See* **saposin**.

Gaucher's disease an autosomal recessive lysosomal storage disease characterized by **glucosylceramide** accumulation, especially in macrophages in spleen, bone marrow, and liver, with splenomegaly and bone lesions. Type 1 is the commonest, does not affect the nervous system (i.e. is non-neuronopathic), and is frequently diagnosed in adulthood. Type 2 is acute, neuronopathic, and usually fatal in the first two years of life. Type 3 is subacute, neuronopathic, and associated with mental retardation. Numerous mutations in the gene at 1q31 result in various degrees of deficiency of **glucosylceramidase** (EC 3.2.1.45). Prosaposin or saposin C deficiency produces variants of the disease. *See also* **saposin**. [After Philippe Charles Ernest Gaucher (1854–1918), French physician.]

gauss *symbol*: G *or* Gs; the cgs unit of magnetic flux; it is equal to a magnetic flux density of one maxwell per cm^2, one line of magnetic induction per cm^2, or 10^{-4} tesla. It is not accepted for use with the SI.

GAUSSIAN a computer program, based on quantum mechanics, which calculates the energies, structures, and vibrational frequencies of molecules.

Gaussian distribution *an alternative name for* **normal distribution**.

gavage the administration of food or other material in liquid form through a tube directly into the stomach; forced feeding in this manner.

Gb_3 *symbol for* globotriaose (alternative to $GbOse_3$).

Gb_4 *symbol for* globotetraose (alternative to $GbOse_4$).

G-banding *or* **Giemsa banding** a commonly used procedure in which **Giemsa's stain** is used to identify chromosomal bands in a karyotype.

$GbOse_3$ *symbol for* globotriaose (alternative to Gb_3).

$GbOse_4$ *symbol for* globotetraose (alternative to Gb_4).

GBP *abbr. for* glucose bisphosphate (*formerly called* glucose diphosphate).

G-1,6-BP *abbr. for* glucose 1,6-bisphosphate (*formerly called* glucose 1,6-diphosphate).

Gc *symbol for* the glycoloyl group.

GC *abbr. for* gas chromatography.

GCA a codon in mRNA for L-alanine.

GCAP *abbr. for* guanylate cyclase activator protein; either of two Ca^{2+}-binding proteins (GCAP-1 and GCAP-2) of the calmodulin family that bind and activate retinal guanylyl cyclase protein (*see* **RETGC**) in the membrane of retinal cone cells.

GC box a nucleotide sequence element common in eukaryotic promoters: consensus GGGCGC.

GCC a codon in mRNA for L-alanine.

G cell a gastrin-producing cell found in the antrum of the stomach and to a lesser extent in the mucosa of the duodenum, though the distribution varies in different species. In humans, G cells are small and pyriform while in dogs they are larger and triangular in shape. They can be identified by immunofluorescence using a gastrin-specific antibody.

GCG 1 a codon in mRNA for L-alanine. **2** *abbr. for* Genetics Computer Group; *see* **sequence analysis package**.

GC/MS *abbr. for* gas chromatography/mass spectrometry.

GCN4 a gene for a yeast transcription factor that binds, as a dimer, to the sequence TGA[C/G]TCA. The protein has a **leucine zipper**, and resembles ***FOS*** and ***JUN***.

GCRDB *abbr. for* G protein-coupled receptor database; *see* **specialist database**.

G-CSF *abbr. for* granulocyte colony stimulating factor.

GCU a codon in mRNA for L-alanine.

Gd *symbol for* gadolinium.

GDC *abbr. for* Graves' disease carrier protein; it is similar in structure and some other properties to **ADP,ATP carrier protein**.

G4 DNA *abbr. for* DNA containing a **G-quartet**.

GDNF *abbr. for* glial cell line-derived neurotropic factor; a glycosylated, disulfide-bonded homodimer that promotes survival and morphological differentiation of dopaminergic neurons. Human and rat GDNFs share 93% similarity. *Compare* **brain-derived neurotropic factor**.

GDP *abbr. for* **1** guanosine diphosphate. **2** glucose diphosphate (now called glucose bisphosphate).

G-1,6-DP *abbr. for* glucose 1,6-diphosphate (now called glucose 1,6-bisphosphate).

GDP-fucosepyrophosphorylase *see* **fucose-1-phosphate guanylyltransferase**.

GDPM *or* **GDPmannose** *abbr. for* guanosinediphosphomannose.

GDPmannose 6-dehydrogenase EC 1.1.1.132; an enzyme that catalyses the reaction between GDP-D-mannose, 2 NAD^+ and H_2O to form GDP-D-mannuronate and 2 NADH. Example from *Pseudomonas aeruginosa*: ALGD_PSEAE, 436 amino acids (47.58 kDa).

GDPmannose 3,5-epimerase EC 5.1.3.18; an enzyme that catalyses the interconversion of GDP-D-mannose and GDP-L-galactose.

GDS *(in clinical chemistry) abbr. for* guanine deaminase.

Ge *symbol for* germanium.

Geiger counter *or* **Geiger–Müller counter** a device for detecting and measuring ionizing radiation (alpha or beta particles or gamma-ray photons). It consists of a glass envelope containing low-pressure gas and an anode and a cathode, between which a large electric-potential difference is maintained. The ions produced in the gas by the incoming ionizing radiation are accelerated towards their appropriate electrodes, causing a momentary drop in the potential between the latter. The voltage pulses so produced may be counted with a suitable electronic circuit. [After Hans Wilhelm Geiger (1882–1945), German physicist, and Erwin Wilhelm Müller (1911–77), German-born US physicist.]

Geiger region *or* **Geiger–Müller region** the part of the curve of applied voltage against number of ions collected for a given incoming radiation by a **Geiger counter**, where all possible ion-pairs, both primary and secondary, are collected; i.e. the signal is relatively independent of the applied voltage. *Compare* **proportional region**.

Gek *abbr. for* **Genghis Khan**.

gel 1 a colloidal system, with the semblance of a solid, in which a solid is dispersed in a liquid. A gel has a finite, usually rather small, yield stress. **2** to become, or cause to become, a gel.

gelatin a heterogeneous mixture of water-soluble proteins of high average M_r, derived from collagen by partial hydrolysis in either acid (type A) or alkali (type B). Collagen obtained by boiling skins, ligaments, tendons, etc. with water is also termed gelatin, as also is collagen denatured by heating for 15 minutes at 45 °C, used as a substrate for **gelatinase**. It is colourless, or slightly yellow, and transparent, and occurs as brittle sheets, flakes, or coarse powder; these swell in water to form gels below 35–40 °C, containing 5–10 times as much water as gelatin by weight. Nutritionally, gelatin is an incomplete protein, containing only small amounts of certain essential amino acids, especially tryptophan. It is widely used in foods, and in the manufacture of adhesives, photographic films and plates, and light filters.

gelatinase EC 3.4.24.24; *recommended name*: gelatinase A; *other names*: 72 kDa gelatinase; matrix metalloproteinase 2; type IV collagenase. An enzyme that catalyses the cleavage of **gelatin** and collagen types IV, V, VII, and X; it cleaves the collagen-like substrate sequence Pro-Gln-Gly-|-Ile-Ala-Gly-Gln; zinc and calcium are cofactors. It is a metallo (zinc) endopeptidase with **fibronectin** domains, and is produced by fibroblasts. The human precursor (660 amino acids) has a large pre-pro region; the enzyme starts at amino acid 110.

gelation 1 the (usually reversible) act or process of forming a **gel** (def. 1) from a **sol**. *Compare* **solation**. **2** the solidification of a liquid by cold. **—gelate** *vb.*

gel chromatography *see* **liquid–gel chromatography**.

gel diffusion *(in immunology)* a technique in which antibodies and antigens are allowed to diffuse independently through a gel, often of agar, and form a precipitate within the gel where homologous antigens and antibodies meet in optimal proportions.

gel electrophoresis a type of **zone electrophoresis** in which the supporting medium is a gel of uniform concentration, commonly of polyacrylamide, agarose, or starch. *See* **polyacrylamide (gel) electrophoresis**. *Compare* **gradient (acrylamide) gel electrophoresis**.

gel filtration *or* **gel-filtration chromatography** *see* **gel-permeation chromatography**.

gel-filtration chromatography *see* **gel-permeation chromatography**.

gel-filtration high-performance liquid chromatography a technique of **gel-permeation chromatography** that uses a support material of high mechanical strength and chemical inertness thereby enabling separations to be effected under the conditions, and with the advantages of **high-pressure liquid chromatography**.

gel fluorography the application of **fluorography** (def. 2) to the detection of substances separated in gels, as by gel electrophoresis.

gellify to cause to become a **gel** (def. 1); to become gel-like; to **gel** (def. 2).

gelonin *or* **ribosome-inactivating protein** *or* **rRNA *N*-glycosidase** EC 3.2.2.22; *recommended name*: rRNA *N*-glycosidase; an extremely stable, potent toxin extracted from seeds of *Gelonium multiflorum* (a plant of the spurge family). It is a glycoprotein of 28–30 kDa containing terminal mannose residues. It acts as a powerful inhibitor of protein synthesis in cell-free systems but not in intact cells; it inactivates the 60S ribosomal subunit but not the 40S subunit. It hydrolyses a specific N-glycosidic bond of an adenosine on the 28S rRNA. in cell-free protein-synthesizing systems gelonin acts like the A chains of **abrin**, **ricin**, and **modeccin**, suggesting that it lacks the ability to bind to cell surfaces and enter cells.

gel-permeation chromatography a method for the separation of substances in solution, *commonly known as* **gel filtration** *or* **gel-filtration chromatography**. The separation is based mainly on exclusion effects, such as differences in molecular size and/or shape or in charge, when the stationary phase is a swollen gel. The gel used is commonly a water-swollen insoluble carbohydrate polymer from which macromolecules are excluded and migrate without retention in the interstitial fluid. Substances of low or intermediate relative molecular mass penetrate into the gel particles to an extent that is, in most instances, determined by their molecular dimensions and the degree of cross-linking of the gel. The larger molecules therefore pass through the bed more rapidly than smaller molecules. The technique can be used to determine the relative molecular mass (M_r) of unknown materials, since, for a particular column, elution occurs at a volume determined by the equation

$$V_R/V_0 = 1 - \rho\log(M_r/M_{r0})$$

where V_R is the elution volume of the unknown, V_0 is the volume of the mobile phase in the column, M_r is the M_r of the unknown, M_{r0} is the M_r of the largest totally permeating molecule, and ρ is a factor that is a property of the column. Thus each column must be calibrated using standard proteins, and a plot made of the elution volumes against logM_r of the standards, from which the unknown M_r can be determined.

gel retardation assay *an alternative name for* **electrophoretic mobility shift assay**.

gelsolin a heat-labile, monomeric protein, of apparent M_r 90 000, isolated from macrophages, platelets, and plasma. It appears to promote the gel–sol transformation of **actin**, and may thereby be important in the control of locomotion, secretion, and endocytosis in these and other cells; β-actin has a similar action. There are two forms of gelsolin, plasma and cytoplasmic, generated by alternative splicing. The cytoplasmic, calcium- regulated, actin-modulating form binds to the barbed ends of actin monomers or filaments, preventing monomer exchange; it also promotes nucleation, and binds with high affinity to fibronectin.

gem- *prefix (in chemical nomenclature)* denoting the presence of **geminal** substituents.

gemeprost 16,16-dimethyl-*trans*-Δ^2-prostaglandin E_1 methyl ester; 11,15-dihydroxy-16,16-dimethyl-9-oxoprosta-2,13-dien-1-oic acid methyl ester; an analogue of **prostaglandin** E_1 with uterine stimulant activity.



gemfibrozil 2,2-dimethyl-5-(2,5-xylyloxy)valeric acid; an antihyperlipoproteinemic agent with actions similar to **clofibrate**.



gemin 3 a mammalian DEAD-box helicase associated with the SMN (survival of motor neuron) complex. Gemin 3, gemin 4, eIF2C2, and miRNA are present in this 15S ribonucleoprotein complex. This may be a mammalian RNA-induced silencing complex (RISC).

geminal *(in chemistry)* describing two like groups or atoms attached to the same atom in a molecule, i.e. the geminal groups or atoms are separated by two bonds attached to the same atom. The presence of geminal substituents is denoted by the prefix *gem-* attached to the name of the compound. *Compare* **vicinal** (def. 2).

geminate occurring in pairs; doubled, twin.

geminin a protein (35 kDa) of metazoan animals that is present in the cell nucleus from the S phase of the cell cycle to mitosis, being degraded on completion of mitosis. It binds and inhibits two proteins (65 kDa and 130 kDa) that are required for initiation of DNA replication.

geminivirus a plant virus in which the virion morphology is characterized by the possession of a pair of isometric particles, each containing circular or linear single-stranded DNA. Transmission occurs largely via leafhoppers or whitefly, but sometimes transmission is effected mechanically. Some geminiviruses cause economically important diseases in cultivated plants. [From Latin *gemini,* twins.]

+gen *or (after a consonant)* **+ogen** *comb. form* signifying producing or capable of producing (either directly or indirectly). In biological sciences it is used especially (1) with word-stems relating to physiological or pathological processes, states, conditions, etc., to denote a causative agent (e.g. antigen, lactogen, mutagen, estrogen); (2) with names of certain proteinases or blood components, to denote their inactive precursors or substances from which they can be derived by enzymic action (e.g. angiotensinogen, caseinogen, fibrinogen, trypsinogen) (*see also* **pro+** (def. 3), **zymogen**); (3) with names or name-roots of certain metabolites, to denote either a storage substance (e.g. glycogen, phosphagen) or a biosynthetic precursor (e.g. porphobilinogen); (4) with word-stems relating to physical properties (e.g. chromogen, luminogen). **—+genic** *or* **+genous** *adj. suffix.*

Genaminox KC *the proprietary name for* detergents similar to lauryldimethylamine oxide, but with different alkyl chain lengths (9–13).

Genapol *the proprietary name for* a series of nonionic polyoxyethylene detergents of the general formula $CH_3(CH_2)_x - O(CH_2CH_2O)_y$ –H; Genapol X-080 has x = 12, y = 8, CMC 0.06–0.15 mm; Genapol X-100 has x = 12, y = 10, aggregation number 88, CMC 0.15 mm. *Compare* **C_xE_y**, **Lubrol**, **Triton**, **Tween**.

GenBank *see* **sequence database**.

gene in classical genetics, a statistical entity that correlates with a particular phenotypic characteristic; the functional unit of heredity. Before their biochemical nature was understood, genes were defined in terms of units of mutation and/or recombination. Discovery of the role of DNA in genetic processes, followed by elaboration of the **central dogma** of protein synthesis, led to enunciation of the 'one gene–one enzyme' hypothesis, i.e. that a gene consisted of DNA that coded for a protein that performed the functions associated with the phenotypic expression of the gene. In current molecular genetics, the concept requires modification in a number of ways. First, the genomic DNA that codes for a polypeptide is associated with regulatory sequences such as promoters. Second, the polypeptide resulting from translation of mRNA may be subsequently split to give several polypeptides with different functions (*see* **polyprotein**). Third, the RNA transcribed may give rise to several different proteins as a result of **alternative splicing**. Three types of genes are now distinguished: those that are both transcribed into mRNA and translated into polypeptides (**structural genes**); those that are only transcribed into RNA (e.g. rRNA, tRNA); and those that function as regulators of the expression of the other two types (**regulator genes**). In diploid organisms a gene may occur in alternative forms (**alleles**). The term gene is sometimes used interchangeably with **cistron**.

gene amplification the selective, repeated replication of a certain gene or genes without a proportional increase in other genes in the genome. It occurs, e.g., in the DNA puffs of *Rhynchosciara* and some other flies and in the genes encoding ribosomal RNA (so-called ribosomal DNA) in amphibian oocytes. The mammalian dihydrofolate reductase gene is amplified in cells selected for resistance to increasing concentrations of methotrexate.

gene bank *an alternative name for* **gene library**.

GeneChip array a standardized, reproducible, proprietary technology for simultaneous measurement of the expression levels of large numbers of genes. The method involves *in situ* synthesis of DNA oligonucleotide probes on glass slides by means of photolithography, which allows several hundred thousand spots (with copies of specific DNA sequences) to be placed on a single slide. Single mRNA samples are then fluorescently labelled and hybridized to the chip, scanned with a fluorescent scanner, and the data collected and automatically analysed to quantify the relative amount of fluorescence and hence the relative levels of expression of each gene. *See also* **microarray**.

gene cloning *see* **molecular cloning**.

gene cluster *or* **gene complex** any group of two or more functionally related genes that are closely linked on a chromosome. The genes of a gene cluster are often structural genes coding for the enzymes that catalyse the various steps of a metabolic pathway.

gene complex *an alternative name for* **gene cluster**.

gene conversion a genetic event involving transfer of DNA between genes, usually as a result of unequal crossing over during meiosis. If the transferred material contains mutations, or if it disrupts the coding sequence of the gene, it may be a mechanism for mutation.

gene desert a region of a chromosome that contains few if any genes.

gene dosage the number of times a particular gene is present in the genome.

gene duplication the phenomenon, occurring in some higher organisms, in which there is duplication of the DNA sequences representing particular genes. This process is thought to have played a decisive part in the evolution of these organisms, through the occurrence of different mutations in the two duplicated genes.

gene expression the process by which the information carried by a gene or genes becomes manifest as the phenotype. It involves **transcription** of the gene into complementary RNA sequences and, for structural genes, subsequent **translation** of mRNA into polypeptide chains and their assembly into the ultimate protein products. Gene expression is tightly regulated by **promoters, enhancers**, and **transcription factors**.

gene expression array *see* **microarray**.

gene expression profile a characteristic pattern or inventory of gene expression from particular cell types, organs, or tissues, under particular physiological or disease conditions. Methods for analysing expression profiles depend on the technology used to measure expression intensities, but are usually classed as sequence tag counting – e.g. expressed sequence tags (ESTs), SAGE – or hybridization methods (e.g. microarrays).

gene family a group of closely related genes that encode similar protein products. Such genes tend to arise by duplication of an ancestral gene, and subsequently evolve independently via random mutational events. This results in independent genes, either clustered together on a chromosome or dispersed throughout the genome, that encode proteins with slightly different functions.

gene frequency a measure of the proportion of an allele in a given population, equal to the number of loci at which a given allele occurs, divided by the total number of loci at which it could occur.

gene fusion *or* **translational fusion** *or* **protein fusion** the joining of DNA from two genes as a result of translocation or inversion. It may give rise either to a chimeric protein product or to the misregulation of transcription of one gene by the *cis*-regulatory elements of the other.

gene identification *an alternative term for* **gene prediction**.

gene jungle a region of a chromosome that has a high gene density.

gene library *or* **cloned library** *or* **gene bank** *or* **shotgun collection** a random collection of DNA fragments cloned in a **vector** (def. 3), and which may include all the genetic information of a particular species. It may be prepared from a variety of sources, including an extract of mRNA, in contrast to a **genomic library** which is prepared from genomic DNA.

gene mutation any **mutation** (def. 1) occurring within a single gene.

gene ontology *abbr*.: GO; a controlled vocabulary (based on model eukaryotic organisms, including *Drosophila melanogaster, Saccharomyces cerevisiae, Mus musculus*, etc.) that has been developed on a community-wide basis to relate gene and protein names, functional groupings of genes and gene products, and location of action of these entities, into a coherent, standardized whole. The three organizing principles of GO are molecular function, biological process, and cellular component.

gene pool the sum of the genetic information in the reproductive members of a population of sexually reproducing organisms.

gene prediction *or* **gene identification** the prediction of genes in an uncharacterized nucleotide sequence based on its similarity to known gene sequences. *Compare* ***ab initio*** **gene prediction**.

gene product any of the types of RNA (transcription products) or any of the proteins or protein subunits (translation products) synthesized biochemically on the basis of the information encoded in a genome.

general acid-catalysis **homogeneous catalysis** in which the catalysts are various hydron donors (acids). *Compare* **specific acid-catalysis**.

general base-catalysis **homogeneous catalysis** in which the catalysts are various hydron acceptors (bases). *Compare* **specific base-catalysis**.

generally labelled describing the labelling of a molecule in such a way that a radionuclide may be present at any or all (but not necessarily all) possible positions. *Compare* **uniformly labelled**.

general transcription factor any of the proteins whose assembly around the **TATA box** is required for the initiation of transcription of most eukaryotic genes. Their activity is enhanced by transcription activators that bind at distal enhancer sites. *See* **promoter**.

generate *(in mathematics)* to conceive a point, line, or surface to be moving in a specified way so as to form a line, surface, or solid, respectively.

generation **1** the act or process of producing or reproducing, naturally or artificially. **2** the phase in a life cycle that extends from one to the immediately successive reproduction. **3** any group comprising all those members of a population who are equally removed from a common ancestor or from coeval ancestors.

generation of diversity *(in immunology)* the process by which a large number of variable regions are generated in the immunoglobulins. The **stem cell** genome contains multiple variants of L-chain V (variable) and J genes and of the H-chain V, J, and D (diversity) genes. As the stem cells differentiate, the maturing lymphocyte constructs particular L and H genes of virtually unique structure by a recombination process that randomly selects one out of each set of gene segments and assembles them, together with a C (for the constant region) gene into a mature H or L gene. This, combined with recombinational inaccuracies, somatic point mutations, and the varied combinations of l and h chains found in immunoglobulins results in a repertoire of millions of lymphocytes each with H and L genes encoding unique molecules. *See also* **immunoglobulin**.

generation time the time between division of a cell and that of its daughter cells, averaged over a whole cell population.

gene redundancy the presence in a cell of many copies of a single gene. The multiple copies may be inherited or result from selective **gene duplication** during development.

gene-regulatory protein any protein that binds to a specific DNA sequence to alter the expression of a gene.

+genesis *comb. form* denoting beginning or origin; development; generation. *See also* **+gen**. —**+genetic** *or* **+genic** *adj. comb. form.*

gene splicing biochemical and/or chemical manipulations with the object of attaching one DNA molecule to another. The neatest method is to cleave the DNA to be inserted (foreign DNA) with a **restriction endonuclease** that yields single-stranded ends that are complementary to each other. The **cloning vector** into which the foreign DNA is to be inserted is treated with the same endonuclease so that the complementary ends of the two DNAs specifically associate under annealing conditions and are subsequently covalently joined (spliced) through the action of **DNA ligase**. If the endonuclease produces fragments with 'blunt' or **flush ends** then a similar procedure is adopted. If the foreign DNA and the cloning vector have no common restriction sites then terminal **deoxynucleotidyl transferase** may be used which adds nucleotides to the 3′-terminal OH group of a DNA chain. For this purpose tails of poly(dT) and poly(dA) may be used. The transformed cells are then grown and those containing the spliced DNA are selected (cloning). The preferred method of splicing is one that allows the foreign DNA to be removed easily by means of a restriction endonuclease, preferably the same one that was initially used in splicing. By this means large amounts of the foreign DNA can be synthesized and used for many different purposes. Alternatively the cloned cells containing the foreign DNA can be used to permit the expression of a foreign protein which is then recovered.

gene therapy the treatment of disease by incorporating into a person's genome DNA that encodes a specific therapeutic protein or that corrects deficiency of a normal protein due to a gene mutation.

genetic *or* **genetical** of or pertaining to **genetics**, **genes**, or the origin of something. **—genetically** *adv.*

genetic ablation a method applied in transgenic organisms in which a tissue-specific promoter is used to enable the expression of a gene for a toxin, such as diphtheria toxin A (*dipA*), to cause destruction of the particular tissue during development.

genetic algorithm an algorithm that exploits evolutionary principles. Given an initial population of solutions, a genetic algorithm evaluates which have the best fit to some desired property as measured by a fitness function. More optimal solutions are then generated by a heuristic process that mimics genetic selection, employing, for example, crossover, mutation, and replication over a number of generations.

genetically engineered describing a cell, strain, or organism whose phenotype has been altered by manipulation of its genetic material. *See* **genetic engineering**.

genetically modified organism *abbr*.: GMO; an organism that has been modified by the addition (from the same or different species) or deletion of genetic material, or by some other genetic alteration, to enhance a natural characteristic or to provide one that it does not have naturally.

genetic block a reduction in the activity of a particular enzyme in a metabolic pathway as a result of gene mutation. A genetic block is termed **complete** when the particular enzyme activity is absent, or **incomplete** (*or* leaky) when the enzyme formed is defective and of limited activity.

genetic carrier *see* **carrier** (def. 9).

genetic code all the regularities in nucleotide sequence according to which genetic information for the sequences of all the polypeptides synthesized by transcription and translation is encoded in DNA (or RNA in some viruses). A sequence of three nucleotide residues (a codon) is required to code for one amino-acid residue, and since there are four different kinds of base in nucleic acids (apart from minor constituents), 4^3 i.e. 64 different nucleotide triplets can exist. But only 20 different amino-acid residues in polypeptides can be coded for; therefore the code is degenerate in that most amino acids can be specified by more than one codon. In terms of the sequence of nucleotides in mRNA, i.e. the nucleotides complementary to those in the genetic material, the genetic code, reading from the 5′ end to the 3′ end of each codon, is given in the table. (The letter A symbolizes a nucleotide residue containing adenine; G, guanine; C, cytosine; and U, uracil; each amino-acid residue is represented by its usual three-letter symbol.)

UUU: Phe	UCU: Ser	UAU: Tyr	UGU: Cys
UUC: Phe	UCC: Ser	UAC: Tyr	UGC: Cys
UUA: Leu	UCA: Ser	UAA: Ter†	UGA: Ter†
UUG: Leu	UCG: Ser	UAG: Ter†	UGG: Trp
CUU: Leu	CCU: Pro	CAU: His	CGU: Arg
CUC: Leu	CCC: Pro	CAC: His	CGC: Arg
CUA: Leu	CCA: Pro	CAA: Gln	CGA: Arg
CUG: Leu	CCG: Pro	CAG: Gln	CGG: Arg
AUU: Ile	ACU: Thr	AAU: Asn	AGU: Ser
AUC: Ile	ACC: Thr	AAC: Asn	AGC: Ser
AUA: Ile	ACA: Thr	AAA: Lys	AGA: Arg
AUG: Met‡	ACG: Thr	AAG: Lys	AGG: Arg
GUU: Val	GCU: Ala	GAU: Asp	GGU: Gly
GUC: Val	GCC: Ala	GAC: Asp	GGC: Gly
GUA: Val	GCA: Ala	GAA: Glu	GGA: Gly
GUG: Val	GCG: Ala	GAG: Glu	GGG: Gly

† termination codon. UAA was once called **ochre codon**; UAG, **amber codon**; UGA, **opal codon**.

‡ initiation codon. The methionine codon AUG is the most common starting point of translation of a genetic message but GUG sometimes serves.

The genetic code is almost universal but differences have been found in the DNA of mitochondria from a number of organisms. For example, in human mitochondria UGA codes for Trp and not for termination; AUA codes for Met and not for Ile; AGA and AGG are termination codons and do not code for Arg; AUA and possibly AUU act as initiation codons as well as AUG.

genetic colonization the introduction by a parasite of genetic information into a host such as to cause the host to synthesize products that only the parasite can use. This occurs in some plants, e.g., in cases of parasitism by *Agrobacterium* spp.

genetic complementation the phenomenon whereby two different mutations produce a wild-type phenotype in a double heterozygote. It thus provides evidence that the mutations do not affect the same gene.

genetic cross 1 any mating of two organisms that results in a **genetic recombinant**. **2** the offspring of two (or more) parent organisms produced by mating or other means.

genetic defect any alteration in the genetic information carried in an individual organism, the effect of which is to produce a phenotype that is at a disadvantage in competing with a normal organism of the same species or in meeting the challenges of its environment. *See also* **inborn error of metabolism**, **molecular disease**.

genetic disease any disease ultimately caused by a genetically determined biochemical defect. In the strict sense a genetic disease is only slightly influenced by environmental factors.

genetic drift 1 any change with time in gene frequency in a population. It may be either directed, **steady drift**, or undirected, **random drift**. **2** irregular, random fluctuations in gene frequency in a (relatively) small population caused by statistical effects.

genetic engineering the genetic manipulations used to produce individuals having a new combination of inherited properties. Such manipulation may be of two kinds: (1) cellular manipulation, involving the culturing of (haploid) cells and the hybridization of somatic cells (*see* **cell fusion**); and (2) molecular manipulation, involving the construction of artificial recombinant DNA molecules, their insertion into a **vector** (def. 3), and their establishment in a host cell or organism. The latter approach has been called **recombinant DNA technology**.

genetic erosion any natural or human-engendered process that, with time, results in loss of genetic diversity in populations of the same species, or reduction of the genetic base of a species, or loss of an entire species.

Geneticin *a proprietary name for* **G418**.

genetic information the information carried in a sequence of nucleotides in a molecule of DNA or RNA.

genetic locus *see* **locus**.

genetic map any diagram showing the linear order of, and the relative distances between, mutable sites on a chromosome as deduced from genetic recombination experiments.

genetic mapping any method that may be used to determine the positions of, and the relative distances between, genes of a linkage group or of sites within a gene (fine-scale mapping). In classical genetics, mapping relied on a study of recombination frequency and was measured in **morgans**. In molecular biology, mapping relies on the sequencing of DNA in a chromosome. Current work is aimed at mapping entire genomes. *See also* **genetic map**, **map unit**.

genetic marker 1 any genetically controlled phenotypic difference that can be used in analysing the genetic make-up of an organism. **2** any gene difference in either one or both alleles used in the detection of genetic recombination events.

genetic material the molecular carrier of primary genetic information that serves as a template for its own replication and provides the structural and regulatory information for the processes of protein synthesis and cell development. It consists of double-stranded DNA in higher organisms, bacteria, and most bacteriophages, single-stranded DNA in some bacteriophages, and RNA in the RNA viruses.

genetic pollution contamination of the genetic make-up of wild populations or species with foreign genes (usually as a result of genetic engineering).

genetic polymorphism the regular and simultaneous existence in the same population of two or more discontinuous variants or genotypes, at a frequency existing in more than 1% of the population, that cannot be due to recurrent mutations. The different human blood groups are an example.

genetic profiling *or* **DNA fingerprinting** a technique for providing profiles of DNA fragments (resulting from digestion with restriction enzymes) that characterize a genome. The human genome is scattered with minisatellites, regions of DNA consisting of tandem repeats of short base sequence which can show extensive variation in the number of repeats, leading to multi-allelic variation and high degrees of heterozygosity. This extreme level of variation renders minisatellite or VNTR (**variable number tandem repeats**) loci invaluable as genetic markers. The DNA is digested with a suitable restriction endonuclease and the fragments are electrophoresed through agarose gel and transferred by blotting to a nylon filter. Hybridization is with a minisatellite probe labelled with ^{32}P. The use of the polymerase chain reaction (**PCR**) to amplify hypervariable loci, including very short tandem-repetitive microsatellites, has greatly increased the sensitivity of DNA typing systems and the ability to type degraded human DNA. The method can be used to identify an individual's DNA and also to trace the parentage of an individual. The method is not confined to humans but has been applied to a wide range of species.

genetic recombinant any organism produced by **genetic recombination**.

genetic recombination the processes by which a new genotype is formed by reassortment of genes resulting in gene combinations different from those that were present in the parents. In eukaryotes genetic recombination can occur by chromosome assortment, intrachromosomal recombination, or nonreciprocal interchromosomal recombination. Intrachromosomal recombination occurs by **crossing over**. In bacteria it may occur by genetic transformation, conjugation, transduction, or F-duction. *See also* **Holliday junction**.

genetics 1 the branch of biology concerned with heredity and variation in organisms. It embraces the phenomenology and physiology of heredity; the nature of genetic information; the storage of genetic material; the replication, mutation, transmission, and recombination of genetic material; and the way it is translated into systems that control development and metabolism, and determine the reappearance of parental characters among progeny. **2** the genetic features and constitution of any single organism, species, or group of organisms. *See also* **reverse genetics**.

genetic screening the testing of individuals or groups of individuals for some specific gene product or resulting metabolite for the purpose of identifying genetic defects or diseases.

genetic signature *or* **genetic fingerprint 1** the nucleotide sequences that are specific to an individual. **2** a gene expression pattern characteristic of a particular cell type. **3** a genetic trait characteristic of an ethnic group.

genetic transformation *see* **transformation** (def. 1).

genetic variance that part of the phenotypic variance caused by the varying genotypes of the individuals within a population.

gene trap vector a DNA construct incorporating a selectable marker such as *neo*^{R}, a promoterless reporter such as *lacZ*, and an upstream splice acceptor site. The vector is used to transfect mouse ES cells or other cells by electroporation. If the vector is integrated into a functioning gene, expression of the reporter gene will occur. Flanking DNA can be recovered and sequenced to reveal the identity of the gene. *Compare* **enhancer trap vector**.

Genghis Khan *abbr*.: Gek; a protein serine/threonine kinase of *Drosophila* that is remarkably homologous to the human myotonic dystrophy protein kinase.

genic of, or relating to, a gene or genes.

genin 1 *the class name for* the noncarbohydrate residue of steroid glycosides. It is used as a suffix in forming trivial names of the naturally occurring glycoside precursors; e.g. digitogenin (from digitonin), sapogenin (from saponin). **2** *a former name for* spirostan, 16,22:22,26-diepoxycholestane.

genistein 4,5,7-trihydroxyisoflavone; 5,7-dihydroxy-3-(4-hydroxyphenyl)-4*H*-1-benzopyran-4-one; a yellow pigment of the broom plant *Genista tinctoria*. It inhibits protein-tyrosine kinases and other protein kinases, being a competitive inhibitor at the ATP binding site. *See* **isoflavanoid**.



genome the whole of the genetic information of an organism. It is contained as DNA in eukaryotes and prokaryotes, and as either DNA or RNA in viruses. A given organism has only one genome regardless of whether the organism is haploid, diploid, or polyploid. The term was originally used to denote one haploid set of chromosomes in a eukaryote organism. —**genomic** *adj.*

genome annotation software software that facilitates the creation and maintenance of genome sequence annotation. Examples include Artemis, which allows visualization and annotation especially of the compact genomes of bacteria, archaea, and lower eukaryotes; and Ensembl, which produces and maintains (within a database system) automatic annotation principally for the human genome, but also for the genomes of other vertebrates, with which it provides comparative views.

genome database a database that houses information specific to the genome of a particular organism. For example, ACeDB, FlyBase, and SGD, house information on the *Caenorhabditis elegans*, *Drosophila melanogaster,* and *Saccharomyces cerevisiae* genomes respectively.

genome mutation any **mutation** (def. 1) occurring by alteration of the number of chromosomes in the genome.

genome project an initiative (often via international collaboration) to map and sequence the entire genome of a particular organism. The first complete prokaryotic and eukaryotic genomes to be sequenced were those of *Haemophilus influenzae* in 1995 and *Saccharomyces cerevisiae* in 1997. The Human Genome Project was completed in 2003, but numerous other genome projects are currently underway. *See* **GOLD**.

genome-regulatory protein any site-specific protein involved in the regulation of transcription, such as a polymerase, repressor, or activator.

genomes online database *abbr*.: GOLD; a Web resource that monitors the status of worldwide genome sequencing efforts, giving access to information about both completed and ongoing projects.

genome survey sequence *abbr*.: GSS; a division of the GenBank database that is genomic in origin (as opposed to cDNA), and includes: single-pass genomic data, exon-trapped sequences, cosmid/BAC/YAC end sequences, and Alu PCR sequences.

genome walking a process in which one end of a genomic DNA clone is used to identify an overlapping clone from a genomic DNA library. Repetition of this procedure several times over results in the assembly of a series of overlapping cloned fragments, or contig.

genomic blotting *an alternative name for* **Southern blotting**.

genomic DNA all of the DNA comprising one genome.

genomic imprinting *see* **imprinting**.

genomic library a set of clones containing DNA fragments that *in toto* embrace an entire genome. It is prepared by firstly randomly cutting the genomic DNA to give fragments of varying length. The average fragment length is controllable by discrimination in the choice of restriction enzymes used for cutting, and is selected to optimize the length such that fragments will contain entire open reading frames without excessive lengths of additional DNA at either end. Secondly the DNA fragments thus obtained are ligated into a suitable **vector** (def. 3), which is cloned in a host of choice.

genomics the systematic sequencing and characterization of complete genomes. *See also* **comparative genomics**, **functional genomics**, **+omics**, **structural genomics**.

genophore the structural equivalent of a genetic **linkage group** in any organism. The term includes the linear chromosome of the (enveloped) eukaryon of all animal and plant cells, the circular chromosome of the (nonenveloped) prokaryon of cells of bacteria, the duplex DNA of mitochondria, chloroplasts, kinetoplasts, plasmids, and episomes, and the nucleic acid, whether DNA or RNA, single-stranded or double-stranded, of viruses.

genotoxin an agent that reacts with and interferes with the action of genetic DNA.

genotype 1 the total genetic constitution of an organism. It comprises the genetic information carried both in the chromosomes and extrachromosomally. *Compare* **phenotype**. **—genotypic** *adj.*

gentamicin *or* **gentamycin** any of a group of aminoglycoside antibiotics produced by fermentation of some *Micromonospora* spp. They are inhibitors of protein synthesis, and are particularly effective in the treatment of *Pseudomonas aeruginosa* infections.



gentamicin C_1

gentianose the trisaccharide, *O*-*β*-D-glucopyranosyl-(1→6)-*O*-*α*-D-glucopyranosyl-(1→2)-*β*-D-fructofuranoside. It is found in the rhizomes of many species of *Gentiana*.

gentiobiose *or (formerly)* **amygdalose** the disaccharide, *O*-*β*-D-glucopyranosyl-(1→6)-D-glucose. It is a component of some glycosides, e.g. **amygdalin**.



β-gentiobiose

gentosamine 3-deoxy-3-methylamino-D-xylose; a component of gentamicin A, one of the structural variants of **gentamicin**.



genus (*pl.* **genera**) *(in taxonomy)* a category used in biological classification consisting of species with a common phylogenetic origin that appear to be clearly differentiated from other species.

+geny *comb.form* denoting origin or mode of development. **—+genic** *adj.*

geometric isomer *or* **geometrical isomer** *an alternative term for* ***cis–trans*** **isomer**.

geometric isomerism *or* **geometrical isomerism** *an alternative term for* ***cis–trans*** **isomerism**.

geometric mean *or* **geometric average** for *n* positive numbers, the *n*th root of the product of the numbers. Thus for a set of positive numbers $x_1, x_2, x_3, \ldots x_n$, the geometric mean is $(x_1 \bullet x_2 \bullet x_3 \ldots x_n)^{1/n}$. *Compare* **mean**.

geotaxis the movement of an organism or a cell under the influence of a gravitational field. In **positive geotaxis** the organism moves in the same direction as the gravitational field, while in **negative geotaxis** the movement is in a direction opposite to the gravitational field. **—geotactic** *adj.*

gephryin a cytoplasmic protein that associates with microtubules, and is required for clustering of glycine receptors in spinal cord. It has a role in molybdoenzyme function in non-neuronal tissue.

g-equiv *abbr. for* gram-equivalent or gram-equivalent weight.

GERAD *abbr. for* glycoprotein ER-associated degradation; a disposal system for glycoproteins in the endoplasmic reticulum that is signalled by: (1) removal of the outermost mannose residue from the middle branch of an asparagine-linked oligosaccharide core; and (2) misfolding of the associated protein.

geraniol (2*E*)-3,7-dimethyl-2,6-octadien-1-ol, a monoterpene alcohol with a sweet rose odour, present in oil of rose and other essential oils.



geranyl the (2*E*)-3,7-dimethyl-2,6-octadien-1-yl group. The 1-diphosphate derivative is an intermediate in the synthesis of cholesterol and in the formation of **geranylgeranyl** diphosphate.



geranyl-diphosphate synthase *see* **dimethylallyl*trans*transferase**.

geranylgeranyl the (2*E*,6*E*,10*E*)-3,7,11,15-tetramethyl-2,6,10,14-hexadecatetraen-1-yl group. The 1-diphosphate derivative is a substrate for enzymes introducing the geranylgeranyl group into proteins. *See also* **prenylation**.



geranylgeranyl pyrophosphate synthetase *see* **farnesyl*trans*transferase**.

geranyl*trans*transferase EC 2.5.1.10; *systematic name*: geranyl-diphosphate:isopentenyl-diphosphate geranyl *trans*transferase; *other names*: farnesyl-diphosphate synthase; farnesyl pyrophosphate synthetase (*abbr.*: FPP synthetase). An enzyme of the pathway synthesizing **prenyl** groups, **sesquiterpenes**, and **cholesterol**. It catalyses the reaction between geranyl diphosphate and isopentenyl diphosphate to form *trans*,*trans*-farnesyl diphosphate with release of pyrophosphate.

Gerbich system *abbr.*: Ge; a blood-group system whose antigenic determinants are located on the extracellular, glycosylated domain of **glycophorins** C and D (GPC and GPD). The polypeptide sequences of these give rise to several Ge phenotypes: on GPD the antigenic site for Ge2 resides between residues 1 and 17, and that for Ge3 resides between residues 19 and 34; on GPC, the antigenic site for Ge4 is at the N terminus, and that for Ge3 between residues 40 and 55.

GERL *abbr. for* golgi, endoplasmic reticulum, lysosomes; a term formerly used to describe a specialized region of smooth **endoplasmic reticulum** with high levels of acid phosphatase and other acid hydrolase activities. It is thought to be a region where acid hydrolases are concentrated and packaged into lysosomes. It may also be concerned in packaging other materials, including epinephrine granules in the adrenal medulla, tyrosinase and other materials in premelanosomes in mouse melanomas, peroxidase, etc. in secretory granules in cells of parotid and submaxillary glands, and un-iodinated thyroglobulin in thyroid epithelial cells.

germ cell any cell of the **germ line**, including **gametes**.

germ-free describing any group of animals or plants that is bred and maintained in such conditions that they contain no microorganisms, either normal symbionts or abnormal, infective ones. *Compare* **gnotobiotic**.

germin a pepsin-resistant water-soluble glycoprotein of the walls of germinated plant embryos that may alter the properties of cell walls during germinative growth. Its synthesis coincides with the onset of growth in germination. The protein has oxalate oxidase activity.

germ line any line of cells that gives rise to gametes and is continuous through the generations.

Gerstmann–Straussler syndrome a transmissible **spongiform encephalopathy** of humans, usually familial, characterized by widespread degeneration of the nervous system. *See also* **prion**. [After Joseph Gerstmann (1887–1969), Austrian neurologist.]

GF-1 *see* **GATA-1**.

***g*-factor** or *g*-value, a parameter in EPR spectroscopy, which defines the field B_0 and frequency v position of resonance, according to the relation $hv = g\mu_B B_0$, where h is the Planck constant and μ_B the Bohr magneton.

GFP *abbr. for* **green fluorescent protein**.

GFR *abbr. for* (renal) glomerular filtration rate.

Gg_3 *symbol for* gangliotriaose (alternative to $GgOse_3$).

Gg_4 *symbol for* gangliotetraose (alternative to $GgOse_4$).

GGA a codon in mRNA for a glycine residue.

GGC a codon in mRNA for a glycine residue.

GGG a codon in mRNA for a glycine residue.

$GgOse_3$ *symbol for* gangliotriaose (alternative to Gg_3).

$GgOse_4$ *symbol for* gangliotetraose (alternative to Gg_4).

GGU a codon in mRNA for a glycine residue.

GH *abbr. for* **1** growth hormone (i.e. **somatotropin**). **2** glycohydrolase.

ghilanten *see* **antistasin**.

ghost an empty red-blood-cell membrane, usually obtained by lysis of red cells by the controlled reduction in the osmotic pressure of the suspending medium followed by restoration of normal osmotic conditions causing the membranes to reseal. Ghosts are extensively used in studies of the properties of membranes.

ghrelin a 28-residue acylated polypeptide hormone secreted by endocrine cells of the stomach and duodenum in the human and rat. It strongly stimulates appetite and secretion of somatotropin. Plasma levels rise shortly before and shortly after a meal. It is derived from a precursor protein, proghrelin, from which another appetite-suppressing hormone, **obestatin**, is derived. The two hormones activate distinct receptors. In humans the sequence is

GSSFLSPEHQRVQQRKESKKPPAKLQPR;

n-octanoylation at serine 3 is essential for activity.

GHRF *abbr. for* growth hormone releasing factor (*see* **GHRH**).

GHRH *abbr. for* growth hormone releasing hormone; *other names*: growth hormone releasing factor (*abbr.*: GHRF) *or* somatoliberin; any of a family of peptide hormones that act on the anterior pituitary to stimulate the secretion of growth hormone and exert a trophic effect on the gland. The bovine hormone, for example, consists of 44 amino acids (5.109 kDa), and is derived from a precursor protein. *See also* **GHRH receptor**.

GHRH receptor *abbr. for* growth hormone releasing hormone receptor; *other name*: growth hormone releasing factor receptor (*abbr.*: GRFR); any of a family of G-protein-associated membrane receptors that bind GHRH and stimulate adenylate cyclase. A defect in this receptor ($Asp^{60} \rightarrow Gly^{60}$) is associated with hypoplasia of the anterior pituitary in mice.

GH-RIH *abbr. for* growth hormone release inhibiting factor (i.e. **somatostatin**).

GHRp *abbr. for* **growth hormone-releasing peptide**.

giantin an integral membrane protein of the Golgi apparatus that contains a 376 kDa cytoplasmic domain consisting almost exclusively of heptad repeats for coiled-coil formation, and a C- terminal transmembrane segment.

gibberellin any of a widely distributed, multimembered group of highly modified C_{20} (and C_{19}) terpene plant hormones, the first of which was isolated from plants infected with the fungus *Gibberella fujikuroi*. The most important is gibberellin A_3, also known as **gibberellic acid**. Gibberellins accelerate shoot growth, and can actively stimulate RNA synthesis in dwarf mutant plants, making them grow like normal plants. Other physiological effects, e.g. overcoming the need for vernalization in long-day plants, have also been recorded.



gibberellic acid

Gibbs–Duhem equation an equation relating the chemical potential and concentration of a chemical species in a mixture at constant temperature and pressure. If n_i moles of species i, having chemical potential μ_i, are present in a mixture, then

$$\sum_i n_i d\mu_i = \sum_i x_i d\mu_i = 0$$

where $x_i = n_i/\sum_i n_i$ is the mole fraction and $d\mu_i$ is the change in chemical potential for dn_i, a small change in the amount of species i present, in moles. [After Josiah Willard Gibbs (1839–1903), US physical chemist, and Pierre Duhem (1861–1916), French physical chemist.]

Gibbs energy *or* **Gibbs free energy** *or* **Gibbs function** *symbol*: G; a thermodynamic property of a system; it is defined as $H - TS$, where H is the enthalpy, S the entropy, and T the temperature. For a molecule in solution, Gibbs energy is concentration-dependent. The Gibbs free energy (G_i) of the ith component is equal to the standard free energy of the component ($G^o{}_i$, the free energy at unit activity) plus a term to adjust for concentration. Thus

$$G_i = G^o{}_i + RT\ln a_i,$$

where R is the gas constant, and a_i the activity of the ith component. The molar free energy is referred to as the **chemical potential**. *See also* **Gibbs free energy change**.

Gibbs energy diagram *or* **Gibbs energy profile** for a chemical reaction, a diagram showing the relative standard Gibbs energies of reactants, transition states, reaction intermediates, and products in the same sequence as they occur in the reaction.

Gibbs energy of activation *or* **Gibbs free energy of activation** *symbol*: $\Delta^{\ddagger}G^o$; the standard Gibbs energy difference between the transition state of a chemical reaction (either elementary or stepwise) and reactants.

Gibbs free energy change the difference in Gibbs free energy (G) at any instant in time between the reactants and products of any reaction. Thus for a reaction $A + B \rightleftharpoons C + D$, at any particular concentration of reactants and products, the free energy change, ΔG, for that state is calculated as

$$G_C + G_D - G_A - G_B.$$

Since, for each substance,

$$G_X = G_X{}^o + RT\ln a_x$$

(*see* **Gibbs energy**), this leads to

$$\Delta G = \Delta G^{\mathrm{o}} + RT\,\ln a\{{}_{\mathrm{C}}a_{\mathrm{D}}/a_{\mathrm{A}}a_{\mathrm{B}}\};$$

$$\Delta G^{\mathrm{o}} = \Delta G^{\mathrm{o}}{}_{\mathrm{C}} + \Delta G^{\mathrm{o}}{}_{\mathrm{D}} - \Delta G^{\mathrm{o}}{}_{\mathrm{A}} - \Delta G^{\mathrm{o}}{}_{\mathrm{B}},$$

and is the **standard free energy change**. All chemical reactions proceed in the direction of negative free energy change until equilibrium is reached, at which point ΔG is zero. Since at equilibrium $a_{\mathrm{C}}a_{\mathrm{D}}/a_{\mathrm{A}}a_{\mathrm{B}}$ is the equilibrium constant K, it follows that the standard free energy change $\Delta G^{\mathrm{o}} = -RT\ln K^{\mathrm{o}}$ where K^{o} is the standard equilibrium constant.

Gibbs–Helmholtz equation an equation that may be expressed as

$$\Delta G - \Delta H = T[\delta\Delta G/\delta T]_P$$

where ΔG is the change in Gibbs energy during a reaction, ΔH the increase in enthalpy, P the pressure, and T the temperature.

Giemsa's stain a stain used for staining chromosomes, in which it reveals bands known as **G-bands** (from the name). These are rich in A–T nucleotide pairs. Other compounds, e.g. the antibiotic olivomycin, stain G–C-rich bands known as **R-bands** (because they give the 'reverse' of the G-bands). [After Gustav Giemsa (1867–1948), German parasitologist.]

GIF *abbr. for* growth hormone-inhibitory factor (i.e. **somatostatin**).

giga+ *symbol*: G; **1** the SI prefix denoting 10^9 times. **2** (*in computing*) *prefix* used to indicate a multiple of 2^{30}, e.g. gigabyte.

GIGANTEA a gene of *Arabidopsis thaliana* that is controlled by the circadian clock mechanism and regulates flowering. Its product is predicted to contain several transmembrane segments. It is a key link between clock genes and flowering genes.

gigantism a condition arising from the excessive release of **somatotropin** leading to an individual of excessive size. *Compare* **acromegaly**.

Gilbert syndrome a very mild form of jaundice in which there is increased bilirubin in plasma, predominantly in unconjugated form. Usually diagnosed in young adults, it is transmitted as an autosomal recessive trait. It is caused by an abnormality in the TATA box within the promoter region at 2q37 for UDPglucuronsyltransferase I, which results in reduced expression of the gene, and decreased conjugation of bilirubin as a glucuronoside. *See* **UDPglucuronsyltransferase**. [After Nicholas A. Gilbert (1858–1927), French physician.]

Gilson pipette *a proprietary name for* one of a range of piston-operated pipettes designed to function with disposable polypropylene tips. Individual pipettes are identified by the maximum volume in microlitres they are designed to deliver, for example P2, P20, P200, P1000. Precise volumes within each range can be delivered. [Named after the manufacturer, Gilson Inc.]

Gim complex *an alternative name for* **prefoldin**.

GIP *abbr. for* **1 gastric inhibitory peptide. 2** general insertion pore. *See* **TOM**.

GIPL *abbr. for* glycoinositolphospholipid (*see* **GPI anchor**).

GIRK *abbr. for* G-protein gated inward rectifier K^+.

GKRP *abbr. for* glucokinase regulatory protein.

Gla *symbol for* a residue of the *α*-amino acid L-4-carboxyglutamic acid.

Glanzmann thrombasthenia *see* **von Willebrand factor**.

glass electrode an electrode made of glass whose potential, when immersed in a solution, is a function of the hydrogen-ion activity, i.e. pH, of the solution. A common form of glass electrode consists of a thin glass bulb inside which is mounted a reference electrode, often a silver/silver chloride electrode, immersed in a solution of constant pH and containing the ion to which the inner reference electrode is reversible. A number of special glasses have been made in an effort to extend the range of pH over which the electrode responds linearly, to reduce errors caused by other ions in solution, to extend its useful temperature range, etc.

glassmilk an aqueous suspension of a proprietary silica matrix used in the purification of DNA.

glaucoma a group of heterogeneous diseases in which vision is impaired through damage to the optic nerve, and usually associated with increased intraocular pressure. It is the leading cause of irreversible blindness in the world. Depending on the mechanism impeding outflow of aqueous humor from the anterior chamber of the eye, glaucoma is classified into open-angle, closed-angle, or congenital forms. An autosomal dominant primary open-angle glaucoma results from mutations in the gene for **myocilin**. Primary congenital glaucoma is autosomal recessive and commonly caused by mutations in the gene for a cytochrome P450 designated CYP1B1.

Glc *symbol for* a residue (or sometimes a molecule) of the aldohexose **glucose**. In the condensed system of symbolism of sugar residues, Glc signifies specifically a glucose residue with the common configuration and ring size, i.e. D-glucopyranose. (*Note*: Glu is the symbol for a glutamic residue.)

GLC *or* **glc** *abbr. for* gas–liquid chromatography.

GlcA 1 *symbol for* a residue (or sometimes a molecule) of the uronic acid glucuronic acid. **2** *former symbol for* a residue (or sometimes a molecule) of the aldonic acid **gluconic acid** (no symbol now recommended).

Glc*f* *symbol for* a glucofuranose residue.

GlcN *symbol for* a residue (or sometimes a molecule) of the aminodeoxysugar **glucosamine**.

GlcNAc *symbol for* a residue (or sometimes a molecule) of the *N*-acetylated aminodeoxysugar ***N*-acetylglucosamine**.

Glc*p* *symbol for* a glucopyranose residue.

GlcU *or* **GlcUA** *former symbol for* glucuronic acid (GlcA now recommended).

Gleevec a drug approved for treatment of chronic myeloid leukemia. The drug inhibits a tyrosine kinase enzyme p210 produced by the BCR-ABL oncogene as a result of a translocation from chromosome 22 to 9. A single mutation in the p210 BCR-ABL gene is a source of resistance to Gleevec in blast crisis cells, which leads to reactivation of the enzyme.

Gli any of three vertebrate homologues of the *Drosophila* zinc-finger transcription factor **cubitus interruptus**. Mutations in the Gli3 gene (at 7p13) are associated with the multiple-malformation Pallister–Hall syndrome.

GLI *abbr. for* glucagon-like immunoreactant (or glucagon-like immunoreactivity).

glia *or* **neuroglia** the special connective tissue of the central nervous system constituting some 40% of the total volume of the brain and spinal cord. It has supportive and nutritive functions and is made up of **glial cells** – oligodendrocytes, astrocytes, ependymal cells, and microglial cells.

gliadin *or (formerly)* **gliadine** any of a group of proline-rich proteins (**prolamins**) found in the seeds of wheat and rye. All gliadins are mixtures of simple proteins of similar composition and properties. They are differentiated from **glutenin**, with which they are associated in gluten, by their solubility in 70% aqueous ethanol. With water, gliadins form a sticky mass, which binds flour into a dough. They constitute the major seed storage proteins in wheat. Gliadins fall into two groups: α/β gliadins (*also* prolamin *or* gliadin AI–V) are divided into five classes, by similarity; there are more than 100 copies of the gene per haploid genome; *γ*-gliadins are divided into three classes (BI–III). For both groups, sequence divergence between the respective classes is the result of single base substitutions, and of duplications or deletions within or near direct repeats. [French *gliadine*; from Greek *glia*, glue.]

glial cell-derived neurotrophic factor *abbr*.: GDNF; a homodimeric protein of the transforming growth factor β (TGFβ) family that is secreted in the nervous system and other tissues and promotes neuronal survival during development. Both subunits contain 134 residues and three disulfide bonds, and are derived from a 211-residue precursor. GDNF is structurally related to neurturin and persephin, and like these binds a specific GPI-anchored membrane protein that recruits and signals through **RET** and the adaptor protein GRB-10. Numerous inactivating mutations in RET and a few mutations in GDNF are associated with **Hirschsprung disease**.

glial cells *see* **glia**.

glial derived nexin a glycoprotein serine protease inhibitor, similar to **serpin**, that promotes neurite extension. *See also* **nexin**.

glial fibrillary acidic protein *abbr*.: GFAP; a class III **intermediate filament** and a cell-specific marker that, during the development of the central nervous system, distinguishes astrocytes from other glial cells. It is similar to other intermediate filament proteins.

glibenclamide *see* **glyburide**.

glicentin a peptide originally obtained as a component of porcine enteroglucagon, and known at first as **porcine gut GLII**. It reacts fully with antisera to the N-terminal moiety of glucagon from pancreas. The known amino-acid sequence includes the entire sequences of **glicentin-related pancreatic peptide** (at residues 1–30) and pancreatic **glucagon** (at residues 33–61), and is identical to the N-terminal moiety of the sequence of proglucagon. It was initially thought to comprise 100 amino-acid residues, hence the name.

glicentin-related pancreatic peptide *or* **glicentin-related pancreatic polypeptide** *abbr.*: GRPP; originally, any polypeptide material present in extracts of porcine pancreas and in the secretory granules of the pancreatic A cell that reacted with certain antisera to glicentin, but not with any antisera to glucagon. The term is now usually applied to a specific component of such material that is a 30-residue peptide identical in sequence to the N-terminal 30-residue sequence of **proglucagon**, is secreted by the pancreas concomitantly with glucagon, and thus is probably a cleavage product of proglucagon.

GLI-I *see* **glicentin**.

GLIMA38 *abbr. for* glycosylated islet-cell-membrane antigen 38 kDa; a cell surface antigen of B cells of pancreatic islets that, with **glutamate decarboxylase** (GAD65) and insulinoma antigen-2 (IA-2), elicits autoantibodies in the early phase of the autoimmune response in the development of diabetes mellitus type 1.

gliostatin *see* **platelet-derived endothelial cell growth factor**.

GLIP *abbr. for* glucagon-like insulinotropic peptide; a gastrointestinal peptide that potentiates release of insulin. It is released during a meal and after oral glucose administration. It is GLP-1^{7-37}. *See* **glucagon**.

Gln *symbol for* a residue of the α-amino acid L-**glutamine** (alternative to Q or Z).

global alignment *see* **alignment**.

global similarity similarity that spans the full extent of a pair or set of aligned sequences (i.e. within a global **alignment**).

globin the colourless and basic protein moiety (and biosynthetic precursor) of **hemoglobin** and **myoglobins**. In normal human adult hemoglobin, the globin component comprises two non-identical pairs of polypeptide chains, whereas in myoglobin there is only one polypeptide chain. Pharmaceutical globin is prepared by adding ox hemoglobin to acetone–HCl; this causes the heme groups to separate and remain in solution, while the globin precipitates. It is used in the preparation of globin–insulin, which is absorbed more slowly than soluble insulin, and has a prolonged action.

globo+ *prefix* for an oligosaccharide, signifying the core structure GalNAc(β1-3)Gal(α1-4)Gal(β1-4)Glc (I), present in **globoside** from which the term originated. Also, by derivation it signifies Gal(α1-4)Gal(β1-4)Glc, residues 2–4 of I. *Compare* **isoglobo+**.

globoside *or* **cytolipin K** *symbol*: GbOse_4Cer *or* Gb_4Cer; globotetraosylceramide; ceramide globotetraoside; the major neutral glycosphingolipid in normal kidney and erythrocytes. The name originated from the discovery of this lipid on red cells, and led to the use of **globo+** as a root signifying this core carbohydrate structure. *Compare* **globotriaosylceramide**. *See also* **globotetrasylceramide**, **P system**.

globotetraose *symbol*: GbOse_4 *or* Gb_4; the tetrasaccharide GalNAc(β1-3)Gal(α1-4)Gal(β1-4)Glc. *See also* **P system**, **globo+**.

globotetraosylceramide *symbol*: GbOse_4Cer *or* Gb_4Cer; a glycolipid having the structure

GalNAc(β1-3)Gal(α1-4)Gal(β1-4)GlcCer.

It is the P determinant in the **P system** of blood groups. *See also* **globo+**.

globotriaose *symbol*: GbOse_3 *or* Gb_3; the trisaccharide Gal(α1-4)Gal(β1-4)Glc. *See also* **globo+**.

globotriaosylceramide *symbol*: GbOse_3Cer *or* Gb_3Cer; a glycolipid **globoside** having the structure Gal(α1-4)Gal(β1-4)GlcCer. It is the major neutral glycosphingolipid in leukocytes, platelets, liver, spleen, and most other non-neural tissues. It is the P^k determinant in the **P system** of blood groups. *See also* **globo+**.

globular protein any protein whose polypeptide chain(s) are folded so as to give the whole molecule a rounded shape; the term is often used loosely to mean soluble as distinct from **membrane proteins**.

globulin any simple, globular protein that is insoluble or sparingly soluble in water, but soluble in dilute salt solutions, and can be precipitated from solution by half-saturating the solution with neutral ammonium sulfate. Globulins may be distinguished by, e.g., electrophoresis into α-, β-, and γ-globulins, or by ultracentrifugation into 7S globulins, 19S globulins, etc. *See also* **gamma globulin**, **immunoglobulin**.

Globus a freely available toolkit (but not limited to APIs) for grid computing.

glomerular filtrate the filtrate, free of cells and major plasma proteins, that passes from the blood through a renal glomerulus into the lumen of a nephron in the kidney.

glomerular filtration rate *abbr.*: GFR; the rate at which the **glomerular filtrate** is produced in the kidney(s). It is a measure of renal efficiency and is usually expressed in terms of the renal clearance of some substance, e.g. inulin, that is freely filterable by the glomerulus and is neither reabsorbed nor excreted by the renal tubules.

glomerulus (*pl.* **glomeruli**) **1** a knot of blood capillaries projecting into the capsular end of a nephron and from which the **glomerular filtrate** is formed. *See also* **Malpighian body**. **2** any compact tuft or tangled mass of processes, nerve fibres, or blood vessels. **—glomerular** *adj.*

glp a **regulon** of *Escherichia coli* encoding proteins required for the utilization of glycerol 3-phosphate and its precursors. Operons for enzymes of these pathways are controlled negatively by *glp* repressor and positively by the cyclic AMP–cyclic AMP receptor protein complex.

Glp *symbol for* a residue of the α-imino acid L-5-oxoproline (often known as pyroglutamic acid or pyrrolidinecarboxylic acid).

GLP *abbr. for* glucagon-like peptide (*see* **glucagon-related polypeptide**).

Glu *symbol for* a residue of the α-amino acid L-**glutamic acid** (alternative to E). (*Note*: Glc is the symbol for a glucose residue.)

gluc+ *a variant* (*sometimes, before a vowel*) *of* **gluco+**.

glucaemia *a variant spelling (esp. UK) of* glucemia; *see* **glycemia**.

glucagon a 29-residue polypeptide hormone synthesized in the A cells of pancreatic islets and mammalian (except human) gastric mucosa. Formerly known as hyperglycemic-glycogenolytic factor (*abbr.*: HGF), or hyperglycemic factor. The amino-acid sequence is identical in human and all other mammalian glucagons (except guinea-pig):

HSQGTFTSDYSKYLDSRRAQDFVQWLMNT;

It is secreted in response to falling blood glucose levels and raises the glucose concentration in the blood by either (1) stimulation of adenylate cyclase or (2) activation of inositolphospholipid-specific phospholipase C with increase in intracellular Ca^{2+} concentration. It stimulates glycogenolysis and gluconeogenesis in liver, increases lipolysis in adipose tissue, and increases insulin secretion. Three peptides (glucagon itself and glucagon-like peptides 1 and 2 (GLP-1 and -2)) are roughly 50% homologous in sequence. While GLP-1 is the major form in the pancreas, GLP-1^{7-36}-amide predominates in the intestine. This stimulates insulin secretion and inhibits gastric secretion. Exendin$^{9-39}$ is a GLP-1 receptor antagonist. GLP-1 injected into cerebral ventricles inhibits feeding in the starving rat. This effect is blocked by exendin$^{9-39}$. *See also* **enteroglucagon**, **glicentin**, **glucagon receptor**, **proglucagon**.

glucagon-37 *see* **enteroglucagon**.

glucagon-like immunoreactant *abbr.*: GLI; any member of a group of peptides found in extracts of mammalian gastrointestinal tract that react with N-terminal-specific anti-glucagon antibodies. A particular component of such material may be denoted by means of a suffixed roman numeral, e.g. GLI-I, and the relative molecular mass of the component in question may be indicated by a superscript, e.g. ^{8000}GLI. The principal molecular species recorded include one of ≈12 kDa (^{12000}GLI), a second of ≈8 kDa (^{8000}GLI), and a third of ≈4.5 kDa (^{4500}GLI), the first two being the predominant forms. All have glucagon-like biological activities; e.g. they bind to glucagon receptors of liver plasma membrane, activate hepatic adenylate cyclase, and cause the release of insulin. *See also* **glicentin**, **proglucagon**.

glucagon-like insulinotropic peptide *see* **GLIP**.

glucagon-like peptide receptor any of the membrane proteins that bind glucagon-like peptides (*abbr.*: GLPs) and mediate their intracellular effects. A receptor for GLP-1 has been characterized. It is a seven-transmembrane-segment protein that is coupled to a G-protein activating adenylate cyclase.

glucagonoma a **neoplasm** (benign or malignant), originating usually from the A cells of pancreatic islets, that autonomously secretes **glucagon** or **glucagon-like immunoreactant**, frequently with associated diabetes mellitus.

glucagon receptor any G-protein-associated membrane receptor that binds glucagon and activates adenylate cyclase and phospholipase C. A missense mutation in the gene at 17q25 has been found in a small fraction of diabetes mellitus type 2 patients.

glucagon-related polypeptide *or* **glucagon-like peptide** any peptide found, e.g. in gastrointestinal tissue and blood, that reacts with anti-glucagon antibodies and contains part or all of the amino-acid sequence of **glucagon**. Such peptides include: **enteroglucagon**, **glicentin**, **glucagon-like immunoreactant**, and **proglucagon**.

glucan any glycan composed solely of glucose residues. *See also* **dextran**.

glucan 1,4-*α*-glucosidase EC 3.2.1.3; *other names*: glucoamylase; amyloglucosidase; *α*-amylase; lysosomal *α*-glucosidase; acid maltase; exo-1,4-*α*-glucosidase. An enzyme that hydrolyses terminal 1,4-*α*-D-glucosidic bonds (at the nonreducing end) of polysaccharides, producing *β*-D-glucose with inversion of the configuration. It is less active towards oligosaccharides. Some examples have a raw-starch binding domain. That from *Aspergillus niger* is used commercially in production of glucose. The example from *Neurospora crassa* contains a **kex2** site. Mutations in the human lysosomal enzyme, a glycoprotein of 952 amino acids, cause type II glycogen storage disorder. *See also* **glucosidase**.

***α*-glucan phosphorylase** a **phosphorylase** with affinity for *α*-glucans.

glucarate 1 the dianion of glucaric acid, the **aldaric acid** derived from either glucose or gulose. There are two enantiomers L- and D-glucarate; D-glucarate, *formerly known as* **saccharate**, is derived from either D-glucose or L-gulose (and vice versa for L-glucarate). **2** any salt or ester of glucaric acid.



D-glucarate

glucemia *or (esp. UK)* **glucaemia** *an alternative term for* **glycemia**.

glucitol *see* **sorbitol**.

gluco+ *or (sometimes before a vowel)* **gluc+** *comb. form* indicating glucose. *See also* **glyco+** (def. 2).

gluco- *prefix (in chemical nomenclature)* indicating a particular configuration of a set of (usually) four contiguous CHOH groups as in the acyclic forms of D- or L-glucose. *See* **monosaccharide**.

glucoamylase *another name for* **glucan 1,4-*α*-glucosidase**. *See also* **glucoamylase complex**.

glucoamylase complex EC 3.2.1.20; an enzyme that splits 1,4-*α*-D-glucosidic bonds from the nonreducing end of amylose, amylopectin, glycogen, and oligosaccharides including maltose. The human complex is a homodimer (1857 amino acids per subunit), which may also associate with homodimers of sucrase-isomaltase. It shares 59% sequence identity with the latter, and is a type II membrane protein anchored into the small intestinal brush border membrane by an N-terminal transmembrane segment.

***β*-glucocerebrosidase** *see* **glucosylceramidase**.

glucoconjugate *a former term for* **glycoconjugate**.

glucocorticoid *or* **glucocorticosteroid** any natural or synthetic hormonal **corticosteroid** that acts primarily on carbohydrate and protein metabolism, e.g. by promoting hepatic glycogen deposition, and that has an anti-inflammatory effect. Glucocorticoids are produced in the middle layer (zona fasciculata) of the adrenal cortex, and include **cortisol**, **corticosterone**, and **cortisone**. In the rat, corticosterone is the major product; in humans and most other mammalian species, cortisol is the major product – in humans it is secreted at a rate of ≈8–25 mg per day, compared with corticosterone at 1–4 mg per day. Secretion of glucocorticoids is enhanced during stress, including hypoglycemia, hypotension, trauma (including surgery), and illness. Their main actions include stimulation of liver glucose output (by glycogenolysis and gluconeogenesis), inhibition of glucose utilization by tissues, mobilization of amino acids by breakdown of muscle protein, and mobilization of fatty acids from adipose tissue. Anti-inflammatory actions include stabilization of lysosomal membranes, preventing the release of degradative enzymes, depression of phagocytosis and suppression of **T-cell** activity, suppressing the synthesis of **interleukin-1**, and stimulating the synthesis of **lipocortin**. Glucocorticoid actions are mediated in large part through **glucocorticoid receptor** molecules, which regulate gene transcription. *Compare* **mineralocorticoid**.

glucocorticoid receptor a mammalian **transcription factor** involved in the regulation of eukaryotic gene expression and affecting cellular proliferation and differentiation in target tissues. It is a cytosolic, soluble glucocorticoid-binding protein (90 kDa) in a complex with heat-shock protein hsp90 (total mass ≈300 kDa). Binding of steroid induces DNA-binding function and translocation to the nucleus where the receptor–steroid complex interacts with DNA at a **glucocorticoid response element** to regulate gene transcription. The receptor contains a modulating N-terminal domain, two DNA-binding zinc fingers in the central region, and a glucocorticoid-binding domain in the C-terminal region. Two isoforms, α (777 residues) and β (742 residues), which differ only in the C-terminal region, are probably generated by alternative splicing of a single gene. The glucocorticoid receptor is similar to other steroid/thyroid/retinoic nuclear hormone receptors.

glucocorticoid response element *abbr.*: GRE; a specific regulatory DNA sequence that mediates the effects of glucocorticoids on gene transcription through interaction with the activated glucocorticoid receptor. It is located upstream of a particular gene. A consensus sequence for one such GRE is the almost palindromic structure GGTACAnnnTGTTCT.

glucocortin a protein, M_r 17 000, induced by glucocorticoids in adipocytes, liver, fibroblasts, and thymus, and common to all glucocorticoid target cells examined.

glucogenesis the production of glucose in an organism. This may be from glucose storage forms such as glycogen or starch, from interconversion of other hexoses, or from synthesis from noncarbohydrate precursors.

glucogenic describing a substance, some or all the carbon atoms of which can be used to produce glucose in an organism. A glucogenic amino acid is any amino acid that gives rise to increased urinary glucose excretion when fed to a diabetic animal.

glucokinase 1 *the recommended name for* the enzyme ATP: D-glucose 6-phosphotransferase (EC 2.7.1.2), which catalyses the phosphorylation by ATP of D-glucoseto D-glucose 6-phosphate with release of ADP. The enzyme occurs in invertebrates and microorganisms. Unlike **hexokinase**, which catalyses the same reaction, it is highly specific for D-glucose. **2** *a name frequently applied to* an isoenzyme of hexokinase (EC 2.7.1.1; hexokinase IV) that is characteristic of mammalian liver and pancreatic B cells. Numerous loss-of-function mutations in the gene for this isozyme result in the commonest form of maturity-onset diabetes of the young (MODY2). A rare activating mutation results in congenital hyperinsulinism.

glucokinase regulatory protein *abbr.*: GKRP; a protein that sequesters glucokinase in an inactive state in the cell nucleus.

glucon *or (formerly)* **glucone** any **glycon** in which the sugar involved is glucose.

gluconate 1 the anion of **gluconic acid**. **2** any salt or ester of gluconic acid.

gluconeogenesis the metabolic formation of carbohydrates from non-carbohydrate organic precursors in liver. An important source of precursor molecules is amino acid released from muscle protein during fasting. This is under hormonal control, especially by glucocorticoids. Alanine is an important precursor, and there is extensive conversion in muscle of other amino acids to alanine, which is then transported to the liver, where it undergoes transamination to form pyruvate. *See also* **gluconeogenic pathway**.

gluconeogenic pathway the pathway in liver by which non-carbohydrate precursors are converted to glucose 6-phosphate and thence to glucose or other carbohydrates. Precursor molecules must first be converted to pyruvate, thence successively to oxaloacetate, phosphoenolpyruvate, 2-phosphoglycerate, 3-phosphoglycerate, 1,3-bisphosphoglycerate, glyceraldehyde 3-phosphate plus glycerone phosphate, fructose 1,6-bisphosphate, fructose 6-phosphate, glucose 6-phosphate, and glucose (or other sugars). The enzymes involved are in many cases the same as those involved in the corresponding reverse step in the **glycolytic pathway**. The enzymes specific to the gluconeogenic pathway are pyruvate carboxylase, phospho*enol*pyruvate carboxykinase, fructose 1,6-bisphosphatase and glucose 6-phosphatase (see individual entries). The pathway is hormonally regulated, especially by glucagon, which increases cyclic AMP levels, thereby stimulating protein kinase activity. Control is effected by phosphorylation of liver pyruvate kinase, which inactivates the enzyme and thus restricts glycolysis, and phosphorylation of phosphofructokinase-2, which converts its action to that of a phosphatase which hydrolyses the 2-phosphate of fructose 2,6-bisphosphate, thereby inactivating phosphofructokinase.

gluconic acid the aldonic acid derived from glucose.

gluconolactone *the trivial name for* the γ-lactone (D-glucono-1,4-lactone) or δ-lactone (D-glucono-1,5-lactone) of D-gluconic acid.



D-glucono-1,5-lactone

glucophore the common structural feature postulated to be present in molecules of all substances that possess a sweet taste, and thus to confer sweetness on them. The essential components are considered to be a polarized bond A–H (e.g. O–H in a sugar or N–H in a sweet amino acid), an electronegative atom B (typically =O), and a polarizable hydrophobic group X (such as H or Cl). The approximate distances between them are: A–B, 260 pm; A–X, 350 pm; B–X, 550 pm. The groups A–H and B are considered to bind respectively to similar B and A–H groups in the receptor, and the group X to bind to the receptor by charge-transfer or dispersion bonding.

glucoprotein *a former name for* **glycoprotein**.

glucosaccharase *the trivial name for* any **saccharase** that attacks the glucose end of appropriate oligosaccharides, liberating glucose.

glucosamine *symbol*: Glc*p*N; *the trivial name for* the aminodeoxysugar 2-amino-2-deoxyglucopyranose; there are two enantiomers. D-Glucosamine (*symbol*: D-Glc*p*N), *formerly known as* **chitosamine**, occurs in combined form in chitin, in mucoproteins, and in mucopolysaccharides, and is one of the most abundant natural monosaccharides.

glucosamine *N*-acetyltransferase EC 2.3.1.3; *other name*: glucosamine acetylase; an enzyme forming *N*-acetyl-D-glucosamine from acetyl-CoA and D-glucosamine while releasing CoA.

glucosamine-6-phosphate isomerase EC 5.3.1.10; *systematic name*: D-glucosamine-6-phosphate ketol-isomerase (deaminating). An enzyme that catalyses the hydrolysis of D-glucosamine 6-phosphate to D-fructose 6-phosphate and NH_3. The amino-acid sequences of bacterial and fungal types are similar.

glucosaminic acid *the common biochemical name for* 2-amino-2-deoxygluconic acid.

glucosan **1** *an obsolete name for* **glucan**. **2** *an old trivial name* (established by usage but not recommended) *for* 1,6-anhydroglucopyranose.

glucose *symbol*: Glc; *the trivial name for* the aldohexose *gluco*-hexose; there are two enantiomers, D- and L-glucose. D-(+)-Glucose (symbol: D-Glu), commonly known as glucose, and formerly known as **grape sugar** or **corn sugar**, is dextrorotatory, hence also formerly (and sometimes still) known as **dextrose**; it is 0.74 times as sweet as sucrose. Aged aqueous solutions of D-glucose contain an equilibrium mixture of α-D-glucopyranose, β-D-glucopyranose, and the open-chain form (*see also* **mutarotation**), whereas in crystals α-D-glucopyranose monohydrate is the stable form below 50°C. Combined D-glucose may have either the α or the β configuration, but is invariably in the pyranose form. D-Glucose is an important source of energy for living organisms. It is found free in fruits and other parts of plants, in honey, and in animals, especially in the blood (≈5 mm in human blood). In combined form it occurs in many homo- and hetero-oligosaccharides and polysaccharides, especially in the animal storage polysaccharide glycogen and in the plant storage polysaccharides cellulose and starch.



β-D-glucose

glucose–alanine cycle *or* **alanine cycle** a metabolic cycle in which alanine is formed peripherally, e.g. in muscle, by transamination of glucose-derived pyruvate, and is transported to the liver where its carbon skeleton is reconverted to glucose.

glucose-assimilation coefficient *symbol*: *K*; *see* **glucose-tolerance test**.

glucose-dependent insulinotropic peptide *or* **glucose-dependent insulin-releasing peptide** *see* **gastric inhibitory peptide**.

glucose effect the ability of glucose in the growth medium to inhibit the synthesis of certain enzymes in bacteria growing on the medium. *See also* **catabolite repression**.

glucose fatty-acid cycle a concept to explain how changes in plasma levels of glucose and fatty acids influence one another to provide a homeostatic control mechanism. Its essential features are: (1) the release, for oxidation, of fatty acids from muscle or adipose tissue acylglycerols restricts glucose metabolism in muscle; and (2) glucose uptake by muscle or adipose tissue restricts the release of fatty acids from acylglycerols in these tissues. The cycle thus provides a hormone-independent mechanism tending to maintain a constant plasma glucose level in animals that feed intermittently. Insulin modifies this mechanism by enhancing glucose uptake by muscle and adipose tissue, inhibiting fatty-acid release by adipose tissue, and increasing fatty-acid esterification in both muscle and adipose tissue.

glucose-galactose malabsorption a rare autosomal recessive disorder caused by mutations in the gene for Na^+-glucose transporter 1. *See* **glucose transporter**.

glucose isomerase a bacterial enzyme preparation that catalyses the reaction:

D-glucose = D-fructose.

It is used on a large scale in industry to convert glucose-containing materials to the much sweeter mixture of glucose plus fructose. The enzymes are usually immobilized on a variety of supports. The product is known as **high-fructose corn syrup** and is widely used as a sweetening agent. No enzyme for which this is the main function has been isolated. EC 5.3.1.18 (glucose isomerase) is now a deleted entry.

glucose oxidase EC 1.1.3.4; *other names*: glucose oxyhydrase; notatin; *systematic name*: β-D-glucose:oxygen 1-oxidoreductase; a flavoprotein (FAD) enzyme that catalyses the oxidation by dioxygen of β-D-glucose to D-glucono-1,5-lactone and H_2O_2. It has application in the experimental determination of glucose concentration (e.g. in medicine) and has some industrial uses.

glucose-1-phosphatase EC 3.1.3.10; *systematic name*: D-glucose-1-phosphate phosphohydrolase. An enzyme that catalyses the hydrolysis of D-glucose 1-phosphate to D-glucose and orthophosphate.

glucose-6-phosphatase EC 3.1.3.9; *systematic name*: D-glucose-6-phosphate phosphohydrolase. An enzyme that catalyses the hydrolysis of D-glucose 6-phosphate to D-glucose and orthophosphate. It has rather wide specificity. It is the final enzyme in the **gluconeogenic pathway**. The human enzyme is an integral membrane protein (357 amino acids, nine transmembrane segments) of the endoplasmic reticulum (ER), particularly in liver, kidney, and pancreatic B cells. The active site is in the ER lumen. Its activity is increased by starvation and diabetes mellitus, and decreased by insulin. It forms part of a system that includes ER transporters for: glucose-6-phosphate (429 amino acids, 10 transmembrane segments), for glucose, and for phosphate. Deficiency of any of these four components leads to a specific form of type I glycogen storage disease.

glucose-6-phosphate dehydrogenase *abbr.*: G6PDH *or (in clinical chemistry)* GPD; EC 1.1.1.49; *recommended name*: glucose-6-phosphate 1-dehydrogenase; *systematic name*: D-glucose-6-phosphate:NADP$^+$ 1-oxidoreductase; *other name (obsolete)*: Zwischenferment. An enzyme that catalyses the conversion of D-glucose 6-phosphate and NADP$^+$ to D-glucono-1,5-lactone 6-phosphate and NADPH. This is an early step in the **pentose phosphate pathway** and the **Entner–Doudoroff pathway**, and thus in **heterolactic fermentation**. The enzyme has the greatest known variability of all enzymes in humans. Over 130 molecular variants that result in deficient activity are associated with a drug-induced hemolytic anemia, **favism**. This arises because the enzyme is involved in maintaining reduced glutathione in red cells. *See also* **glucose-6-phosphate dehydrogenase deficiency**.

glucose-6-phosphate dehydrogenase deficiency an X-linked deficiency of **glucose-6-phosphate dehydrogenase** that affects mostly males. It is associated with a hemolytic anemia, but also confers some protection against malaria, since the parasite is unable successfully to pass through the schizont stage in red cells lacking this enzyme activity; hence there is a particularly high incidence in tropical Africa and the Middle and Far East. Lack of the enzyme in red cells results in failure to reduce NADP$^+$ to NADPH in adequate amounts (the **pentose phosphate pathway** playing a major role in this in the red cell), as a result of which oxidized glutathione cannot be reduced by **glutathione reductase**. Consequently, there can be hemolysis, as hemoglobin is not maintained in the ferrous state and the peroxides produced as a result of drug action promote red-cell destruction. The antimalarial drug **primaquine** and related compounds generate oxidative stress. Over 130 mutations result in some degree of deficiency. *See also* **favism**.

glucose-6-phosphate isomerase *abbr. (in clinical chemistry)*: GPI; EC 5.3.1.9; *systematic name*: D-glucose-6-phosphate ketol-isomerase; *other names*: phosphoglucose isomerase; phosphohexose isomerase; phosphohexomutase; oxoisomerase; hexosephosphate isomerase; phosphosaccharomutase; phosphoglucoisomerase; phosphohexoisomerase. A homodimeric cytosolic enzyme of the glycolytic pathway that catalyses the interconversion of glucose 6-phosphate and fructose 6-phosphate. Loss-of-function mutations in the enzyme (558 amino acids) result in an autosomal recessive chronic hemolytic anemia that may be associated with mental retardation and myopathy. Monomeric GPI is identical with neuroleukin.

glucose-tolerance curve the curve relating blood glucose concentration to time that is obtained in a **glucose-tolerance test**, either oral or intravenous.

glucose-tolerance factor *abbr.*: GTF; *also called*: chromodulin. A water-soluble, relatively stable organic chromium complex of M_r ≈500 that is believed to be required in the diet for normal glucose tolerance in animals, including humans. It is a coordination complex between chromium (III) ions, nicotinate, glycine, glutamate, and cysteine or glutathione.

glucose-tolerance test any procedure designed to assess the response of an individual to a loading dose of glucose, widely used in the diagnosis of diabetes mellitus. The standard **oral glucose tolerance test** is performed in the morning after 12 hours of fasting following at least 3 days' unrestricted diet, physical activity, and freedom from medication. After collection of the fasting blood sample, 75 g (or 1.75 g per kg of body weight for children) glucose is ingested in 5 minutes in 200–500 mL water. Blood samples are then collected at 30-minute intervals for 2 hours, and urine samples are collected at 0, 1, and 2 hours. All samples are assayed for glucose. For capillary blood samples, a maximum glucose level below 10 mmol L^{-1} (180 mg/100 mL) and a 2-hour value less than 7.5 mmol L^{-1} (135 mg/100 mL) are the criteria for normality. If venous blood is used the corresponding values are 8.9 mmol L^{-1} (160 mg/100 mL) and 6.1 mmol L^{-1} (110 mg/100 mL). The urine samples should be glucose free. The **intravenous glucose tolerance test** may be used when abnormal carbohydrate absorption from the gut is suspected. A common procedure is to take a fasting blood sample and further samples at 10-minute intervals for 1 hour following intravenous injection of 50 mL of 50% w/v glucose solution over a period of 2 minutes. Glucose is assayed in the blood samples and the logarithms of the values are plotted against time. The slope of the resulting straight line, multiplied by 100, is the **glucose-assimilation coefficient**, *K*, which represents the percentage fall in blood glucose per minute. Values of *K* in excess of 1.1 per cent per minute are taken as normal.

glucose transporter any sugar-transport protein for which glucose is a substrate. Apart from certain ABC types (e.g., in *Escherichia coli*), many glucose transporters belong to the 12- helix superfamily of integral transmembrane proteins. They resemble one another and also the typically sugar–H$^+$ symport proteins of bacteria, even though the mammalian examples are usually facilitated-diffusion proteins. The human type 4 (insulin responsive, muscle and brown fat) glucose transporter is a candidate for the factor responsible for certain post-receptor defects in non-insulin- dependent diabetes mellitus. *See also* **sugar transporter**.

glucosidase any **glycosidase** that hydrolyses *O*-glucosyl-, *N*-glucosyl-, or *S*-glucosyl-compounds.

α-glucosidase EC 3.2.1.20; *systematic name:* α-D-glucoside glucohydrolase; *other names:* maltase; glucoinvertase; glucosidosucrase; maltase–glucoamylase. An enzyme that hydrolyses maltose and terminal (nonreducing end) 1,4-α-D-glucosidic bonds of oligosaccharides to yield α-D-glucose with retention of configuration. Maltases from some sources (especially intestine) act also on polysaccharides and may slowly hydrolyse (1→6)-α-D-glucosidic linkages as well. Most active with oligosaccharides, the enzyme catalyses the final step in the degradation of starch and is widely distributed in plants. *See also* **glucan 1,4-α-glucosidase**.

β-glucosidase EC 3.2.1.21; *systematic name*: β-D-glucoside glucohydrolase; *other names*: cellobiase; gentiobiase. An enzyme that hydrolyses terminal (nonreducing end) 1,4-β-D-glucosidic bonds to yield β-D-glucose with retention of configuration.

glucoside *or (formerly)* **glycoside** any **glycoside** (def. 1) in which the sugar moiety is a glucose residue.

glucosinolate a class of sulfur-containing glycosides produced by brassica plants and relatives as part of their defence against pathogens. Glucosinolates are grouped according to the nature of their side chains, which are derived from aliphatic, indolyl, or aralkyl α-amino acids. Tissue damage causes decompartmentation with release of the thioglycosidase myrosinase. This releases D-glucose and an unstable aglycone from the glucosinolates. The aglycone then forms toxic isothiocyanate, thiocyanate, or nitrile derivatives.

glucosuria the presence of glucose in the urine. It is sometimes loosely referred to by the older term **glycosuria**, which now strictly implies the presence of any type of sugar in urine. Glucosuria occurs in **diabetes mellitus** and is diagnostically important. It may also occur because of renal defects, as in **Fanconi syndrome**. *See also* **fructosuria**.

glucosyl any glycosyl group formed by detaching the anomeric hydroxyl group, on C-1, from a cyclic form (pyranose or furanose) of glucose or a glucose derivative.

glucosylated hemoglobin *a misnomer for* **glycated hemoglobin**.

glucosylation **glycosylation** with one or more glucosyl groups. — **glucosylated** *adj.*

glucosylceramidase EC 3.2.1.45; *other names*: *β*-glucocerebrosidase; acid *β*-glucosidase; *systematic name*: D-glucosyl-*N*-acylsphingosine glucohydrolase; a lysosomal glycoprotein enzyme that catalyses the hydrolysis of D-glucosyl-*N*-acylsphingosine to D-glucose and *N*-acylsphingosine. The enzyme requires saposin C for activity. A deficiency of this enzyme is the cause of **Gaucher's disease**, in which there is an accumulation of glucocerebroside. *See* **saposin**.

glucosylceramide *the recommended term for* any D-glucosyl-*N*-acylsphingosine, i.e. any **cerebroside** in which the sugar moiety is D-glucose.

glucosyloxy any of the glycosyloxy groups formed by detaching the hydrogen atom from the anomeric hydroxyl group, on C-1, from a cyclic form (pyranose or furanose) of glucose.

glucosyltransferase any hexosyltransferase enzyme (EC 2.4.1) for which the glycosyl group transferred is glucosyl. The acceptor may be orthophosphate (as for e.g. **phosphorylase**), but more often is another carbohydrate molecule (as for e.g. **glycogen synthase**) and sometimes a lipid (as in the synthesis of 3-D-glucosyl-1,2-diacylglycerol). *See* **D enzyme**. *See also* **B-transferase**, **lactose synthase**, **Lewis transferase**.

glucuronate **1** the anion of glucuronic acid. **2** any salt or ester of glucuronic acid.

glucuronate pathway *or* **glucuronate oxidation pathway** the metabolic pathway by which D-glucuronate is converted, via L-gulonate, L-xylulose, xylitol, and D-xylulose, to D-xylulose 5-phosphate, an intermediate in the pentose phosphate pathway. In **essential pentosuria** there is defective conversion of L-xylulose to xylitol. In a side branch of the pathway L-ascorbate is formed, via L-gulonolactone, from L-gluconate. Primates and the guinea pig lack the ability to convert L-gulonolactone to L-ascorbate (*see* **ascorbic acid**).

glucuronate reductase EC 1.1.1.19; *systematic name*: L-gulonate:NADP$^+$ 6-oxidoreductase. An enzyme that reduces the aldehyde group at C-1 of D-glucuronate thus forming L-gulonate. *See* **glucuronate pathway**.

glucuronic acid *abbr. (sometimes):* GA; *symbol*: GlcA (*or (formerly)* GlcU *or* GlcUA); the uronic acid formally derived from glucose by oxidation of the hydroxymethylene group at C-6 to a carboxyl group. There are two enantiomers; D-glucuronic acid is widely distributed in plants and animals, where it usually occurs as glucuronides.



β-D-glucuronic acid

***β*-glucuronidase** *abbr. (in clinical chemistry):* GRS; EC 3.2.1.31, an enzyme that catalyses the hydrolysis of a *β*-D-glucuronoside to D-glucuronate and the corresponding hydroxy compound, which may be an alcohol, a phenol, or a saccharide. Deficiency of *β*-glucuronidase occurs in human type VII mucopolysaccharidosis. It is a homotetramer, and a lysosomal enzyme.

glucuronide *former name for* **glucuronoside**.

glucuronoside *or (formerly)* **glucuronide** any compound formed by combination in (*α* or *β*) glycosidic linkage of a hydroxy compound with the anomeric carbon atom of glucuronate. The hydroxy compound may be a saccharide, an alcohol, or a phenol. *β*-D-Glucuronosides are formed in so-called **detoxication** reactions.

glucuronosyl the glycosyl group formed by removal of the anomeric hydroxyl group from glucuronic acid or glucuronate.

glucuronosyltransferase *another name for* **UDPglucuronosyltransferase**.

glucuronoyl the univalent acyl group derived from glucuronic acid.

glued *see* **dynactin**.

Glu(NH$_2$) *(formerly) symbol for* a residue of the *α*-amino acid L-glutamine (Gln or Q now recommended).

Glu-NH$_2$ *symbol for* a residue of the *α*-amino acid L-isoglutamine.

Glu(OEt) *symbol for* a residue of *γ*-ethyl glutamate; O^5-ethyl hydrogen glutamate.

Glu-OEt *symbol for* a residue of *α*-ethyl glutamate; O^1-ethyl hydrogen glutamate.

GluR receptor *see* **glutamate receptor**.

GLUT *an abbr. commonly used for* **glucose transporter**.

glutaconyl-CoA decarboxylase EC 4.1.1.70; an enzyme that catalyses the decarboxylation of glutaconyl-CoA (pent-2-enoyl-CoA) to but-2-enoyl-CoA, releasing CO_2. Biotin is a coenzyme. The enzyme is dependent on Na^+, and functions as a sodium pump in the bacterial membrane.

glutamate **1** *(in biochemistry)* glutamate(1–); glutamic-acid monoanion; hydrogen glutamate. In theory, the term denotes any ion, or mixture of ions, formed from **glutamic acid**, and having a net charge of –1, although the species $_{-}OOC–[CH_2]_2–CH(NH^{3+})–COO_{-}$ generally predominates in practice. **2** *(in chemistry) the systematic name for* glutamate(2–); glutamic-acid dianion. **3** any salt containing an anion of glutamic acid. **4** any ester of glutamic acid.

glutamate *N*-acetyltransferase EC 2.3.1.35; *other names*: ornithine acetyltransferase; ornithine transacetylase; an enzyme of the pathway in bacteria for the formation of ornithine from glutamate. It catalyses a reaction between N^2-acetyl-L-ornithine and L-glutamate to form L-ornithine and *N*-acetyl-L-glutamate (*abbr.*: AGA). AGA is then converted to *N*-acetylglutamate 5-semialdehyde, which undergoes transamination to N^2-acetylornithine. In *Bacillus stearothermophilus* it is a bifunctional enzyme (*other name*: AGS/OCTase) containing activities for this and also **amino-acid *N*-acetyl transferase**.

glutamate–ammonia ligase EC 6.3.1.2; *systematic name*: L-glutamate:ammonia ligase (ADP-forming); *other name*: glutamine synthetase. An enzyme that catalyses a reaction between ATP, L-glutamate, and NH_3 to form ADP, orthophosphate, and L-glutamine. This is the first step in the fixation of ammonia in plants, the ATP-dependent incorporation of NH_4^+ into the amide position of glutamine. The second step involves L-glutamate synthase (ferredoxin) and the combined effect of the two enzymes is to produce L-glutamate from 2-oxoglutarate and ammonium (NH_4^+), a major NH_4^+ assimilatory route. Glutamate–ammonia ligase has a molecular mass of 33 kDa and its eight monomers are arranged in two stacked tetramers. The protein from *Escherichia coli* consists of 12 subunits in two hexagons. The activity is controlled by adenylylation of a tyrosine residue in the presence of ATP by **[glutamate-ammonia-ligase] adenylyl transferase.** The fully adenylylated dodecamer is inactive; transcription is regulated by **nitrogen regulatory protein**.

[glutamate–ammonia-ligase] adenylyltransferase EC 2.7.7.42; *other name*: glutamine-synthetase adenylyltransferase; an enzyme that catalyses the adenylylation of [L-glutamate:ammonia ligase (ADP-forming)] by ATP to form adenylyl-[L-glutamate:ammonia ligase (ADP-forming)] with release of pyrophosphate. The adenylylation regulates enzyme activity (*see* **glutamate–ammonia ligase**).

glutamate/aspartate transporter any membrane protein that transports glutamate and aspartate. Two types are known. (1) A H^+-symport protein of the bacterial (inner) membrane; it is probably a 12-helix integral membrane protein. Although Na^+ is not involved, there is a sequence resemblance to the second type (below). (2) The sodium-dependent transporter of brain; it is similar to sodium-dicarboxylate symporters. Putatively, it is a glycosylated integral membrane protein of brain (high levels in Purkinje cell layer).

glutamate dehydrogenase (NADP$^+$) EC 1.4.1.4; *systematic name*: L-glutamate:NADP$^+$ oxidoreductase (deaminating). An enzyme that catalyses the oxidation by NADP$^+$ of L-glutamate to form 2-oxoglutarate, NH_3, and NADPH. Two forms exist: one is a homotetramer; the other form, found in bacteria and plants, mainly proceeds in the direction of glutamate synthesis, as an NH_3-assimilatory enzyme; it is the product of the *am* gene, and is a homohexamer. Isoforms of this enzyme provided the first demonstration of **interallelic complementation**.

glutamate–cysteine ligase EC 6.3.2.2; *other name*: γ-glutamylcysteine synthetase; the first cytosolic enzyme for the formation of glutathione. It catalyses the formation of γ-L-glutamyl-L-cysteine from ATP, L-glutamate, and L-cysteine with release of ADP and orthophosphate. The mammalian enzyme is a heterodimer. Deficiency in humans produces glutathione deficiency associated primarily with chronic hemolysis.

glutamate decarboxylase *abbr.*: GAD; EC 4.1.1.15; a decarboxylase enzyme necessary for the production of γ-amino-*n*-butyric acid (GABA) from glutamate, with pyridoxal phosphate as coenzyme. GAD65 (585 amino acids; gene at 10p11) is present in small vesicles in brain and in pancreatic islets. Autoantibodies to it occur early in the development of diabetes mellitus type 1, being present in the plasma in ≈90% of such patients. They are also present in ≈60% of patients with stiff-man syndrome. GAD65 shows sequence homology over 22 residues with a sequence in Coxsackie virus P2-C protein. The gene for GAD67 at 2q31 encodes 594 amino acids.

glutamate dehydrogenase EC 1.4.1.2; *systematic name*: L-glutamate:NAD$^+$ oxidoreductase (deaminating). An enzyme that catalyses the reaction:

$$\text{L-glutamate} + H_2O + NAD^+ = \\ \text{2-oxoglutarate} + NH_3 + NADH.$$

This oxidative removal of the amino group from glutamate avoids the need for an oxo-acid acceptor, and in **ureotelic** animals is a major route for the removal of nitrogen as NH_4^+, which is then converted to urea in the **ornithine–urea cycle**. *See also* **glutamate dehydrogenase (NADP+)**.

glutamate dehydrogenase (NADP+) EC 1.4.1.4; *systematic name*: L-glutamate:NADP$^+$ oxidoreductase (deaminating). An enzyme that catalyses the oxidation by NADP$^+$ of L-glutamate to form 2-oxoglutarate, NH_3, and NADPH. Two forms exist. One is a homotetramer. The other form, found in bacteria and plants, mainly proceeds in the direction of glutamate synthesis, as an NH_3-assimilatory enzyme. It is the product of the *am* gene, and is a homohexamer. Isoforms of this enzyme provided the first demonstration of **interallelic complementation**.

glutamate–oxaloacetate transaminase *see* **aminotransferase**.

glutamate–pyruvate transaminase *see* **aminotransferase**.

glutamate receptor *abbr.*: GluR; any membrane protein that binds glutamate and mediates its effects in neurotransmission. Over 20 genes encode human GluRs, which may be ionotropic and act as ligand-gated ion channels or metabotropic G-protein-associated membrane proteins. Some GluR gene products are subject to RNA editing. **Ionotropic GluR receptors** are subdivided into three classes, named after their agonists: (1) *N*-methyl-D-aspartate (NMDA) receptors, which play a key role in memory acquisition, learning, and neurological disorders and are the target for **conantokin-G**; (2) α-amino-3-hydroxy-5-methyl-4-isoxalone (**AMPA**) receptors, formerly designated quisqualate receptors; and (3) kainate receptors. Most of the fast excitatory synaptic transmission in the vertebrate central nervous system is mediated by GluR channels. Generally they have a broad ionic selectivity to monovalent ions; NMDA channels are also five to ten times more permeable to Ca^{2+} ions than to Na^+ or K^+ ions. Subunits (designated α, β, γ, δ, ε, and ζ) of these channels contain four putative transmembrane segments. The members of the α subfamily constitute AMPA-selective GluR channels; the β and γ subfamilies include the subunits of the kainate-selective GluR channel; NMDA receptor channels are composed of εζ heteromers. **Metabotropic GluR receptors** (mGluR) include mGluR$_1$, of which two alternatively spliced versions exist (1199 and 906 amino acids), and mGluR$_2$ (872 amino acids); both activate phospholipase C.

glutamate 1-semialdehyde glutamic α-semialdehyde; the L enantiomer, L-glutamate 1-semialdehyde, (*S*)-4-amino-5-oxopentanoate, is the precursor of 5-aminolevulinate (*see* **glutamate-1-semialdehyde 2,1-aminomutase**). It is synthesized in plants from glutamate bound to a specific tRNA; after reduction of the 1-carboxyl group, the tRNA is removed to yield glutamate 1-semialdehyde. *Compare* **glutamate 5-semialdehyde**.

glutamate 5-semialdehyde glutamic γ-semialdehyde; the L enantiomer, L-glutamate 5-semialdehyde, (*S*)-2-amino-5-oxopentanoate, is an intermediate in the synthesis of proline from ornithine. In plants and bacteria it is formed in a pathway in which L-glutamate is first converted to *N*-acetyl-L-glutamate, which is reduced to *N*-acetyl-L-glutamate 1-semialdehyde, from which the acetyl group is then removed. In animals it is formed from ornithine by transamination of the δ-amino group. *See* **proline**. *Compare* **glutamate 1-semialdehyde**.

glutamate-1-semialdehyde 2,1-aminomutase EC 5.4.3.8; *other name*: glutamate-1-semialdehyde aminotransferase. The enzyme synthesizing 5-aminolevulinate in plants; it catalyses the conversion of (*S*)-4-amino-5-oxopentanoate (i.e. **glutamate 1-semialdehyde**) to 5-aminolevulinate.

glutamate synthase (ferredoxin) EC 1.4.7.1; *systematic name*: L-glutamate:ferredoxin oxidoreductase (transaminating). An enzyme that catalyses the second step in the fixation of ammonia in plants, i.e. the transfer of the NH_2 group from the amide group of glutamine to 2-oxoglutarate to form L-glutamate. The reaction is between L-glutamine, 2-oxoglutarate, and two molecules of reduced ferredoxin; the products are two molecules of L-glutamate and two of oxidized ferredoxin. In plants the combination of the action of **glutamate–ammonia ligase** and this enzyme results in the production of one molecule of glutamate from one of 2-oxoglutarate and one of NH_4^+. *See also* **glutamate synthase (NADH)**, **glutamate synthase (NADPH)**.

glutamate synthase (NADH) EC 1.4.1.14; *systematic name*: L-glutamate:NAD$^+$ oxidoreductase (transaminating). An enzyme that catalyses a reaction between L-glutamine, 2-oxoglutarate, and NADH to form two molecules of L-glutamate and NAD$^+$. FMN is a cofactor.

glutamate synthase (NADPH) EC 1.4.1.13; *systematic name*: L-glutamate:NADP$^+$ oxidoreductase (transaminating). An enzyme that catalyses the formation of two molecules of L-glutamate and one of NADP$^+$ from L-glutamine, 2-oxoglutarate, and NADPH. It is an iron–sulfur flavoprotein. It brings together nitrogen and carbohydrate metabolism in bacteria, since in association with **glutamate–ammonia ligase** it functions as the second step in a major NH_3-assimilatory pathway. It exists as an aggregate of four heterodimers of large and small subunits; glutamine binds to the large subunit and transfers –NH_2 from its amido group to 2-oxoglutarate, which apparently binds to the small subunit.

glutamic *the general name for* a residue of glutamic acid, whether or not the γ-carboxyl group is protonated.

glutamic acid *abbr. (sometimes)*: GA; *the trivial name for* α-aminoglutaric acid; 2-aminopentanedioic acid; HOOC–$[CH_2]_2$–$CH(NH_2)$–COOH; a chiral α-amino acid. L-Glutamic acid (*symbol*: E *or* Glu), (*S*)-2-aminopentanedioic acid, is a coded α-amino acid found in peptide linkage in proteins; codon: GAA or GAG (anticodon: CUU). In mammals, it is a non-essential dietary amino acid, and is glucogenic. Residues of D-glutamic acid (*symbol*: D-Glu *or* DGlu), (*R*)-2-aminopentanedioic acid, are found in the cell-wall material of various bacterial species, and (as poly-D-glutamic acid) in the capsular substances of *Bacillus anthracis*, *B. subtilis*, and other bacteria. One residue of D-glutamic acid per molecule occurs in the antibiotic bacitracin A (*see* **bacitracin**) and also in **glutathione**.



L-glutamic acid

glutamic amide **1** glutamic 1-amide (i.e. **isoglutamine**). **2** glutamic 5-amide (i.e. **glutamine**).

glutaminase EC 3.5.1.2; *other and systematic name*: L-glutamine amidohydrolase; an enzyme that catalyses the hydrolysis of L-glutamine to L-glutamate and NH_3.

glutaminate **1** the glutamine anion; the anion, H_2N–CO–$[CH_2]_2$–$CH(NH_2)$–COO^-, derived from glutamine. **2** any salt containing glutamine anion. **3** any ester of glutamine.

glutamine *the trivial name for* the γ-amide of glutamic acid; glutamic 5-amide; α-aminoglutaramic acid; 2-amino-4-carbamoylbutanoic acid; $H_2N–CO–[CH_2]_2–CH(NH_2)–COOH$; a chiral α-amino acid. L-Glutamine (*symbol*: Q *or* Gln *or (formerly)* Glu(NH_2)), (*S*)-2-amino-4-carbamoylbutanoic acid, is a coded α-amino acid found in peptide linkage in proteins; codon: CAA or CAG (anticodon: GUU). In mammals, it is a non-essential *a*-amino acid, and is glucogenic. D-Glutamine (*symbol*: D-Gln *or* DGln), (*R*)-2-amino-4-carbamoylbutanoic acid, is not known to occur naturally. *Compare* **isoglutamine**.



L-glutamine

glutamine amidotransferase *abbr.*: GATase; *a nonsystematic name for* carbon–nitrogen ligases that employ glutamine as the amido-N-donor; i.e. members of the sub-subclass EC 6.3.5. These enzymes transfer the $–NH_2$ group from glutamine to another reactant, e.g. **GMP synthase**. The enzyme activity is also an activity associated with **CAD protein** in mammals. *See also* **glutamate synthase (ferredoxin)**, **glutamate synthase (NADH)**, **glutamate synthase (NADPH)**.

glutamine–pyruvate aminotransferase EC 2.6.1.15; *other names*: glutaminase II; glutamine–oxo-acid transaminase; glutamine transaminase L; an enzyme that catalyses the reaction:

L-glutamine + pyruvate = 2-oxoglutaramate + L-alanine.

Pyridoxal-phosphate is a cofactor. *See also* **transamination**.

glutamine repeat a protein sequence consisting exclusively of glutaminyl residues. Expansion of the length of the repeat in several proteins, for example ataxins, androgen receptor, and huntingtin, is associated with various forms of spinocerebellar ataxia, spinobulbar muscular atrophy, and Huntington's disease, respectively. The length expansion leads to protein misfolding and aggregation, formation of cellular inclusion bodies, and neurotoxicity.

glutamine synthetase *see* **glutamate–ammonia ligase**.

glutamine-synthetase adenylyltransferase *see* **[glutamate–ammonia-ligase] adenylyltransferase**.

glutamine transaminase L *see* **glutamine–pyruvate aminotransferase**.

glutamino **1** **N^2-glutamino** the alkylamino group, $H_2N–CO–[CH_2]_2–CH(COOH)–NH–$, derived from glutamine by loss of a hydrogen atom from its α-amino group. **2** **N^5-glutamino** the acylamino group, $H_2N–CH(COOH)–[CH_2]_2–CO–NH–$, derived from glutamine by loss of a hydrogen atom from its amide group.

glutaminyl the acyl group, $H_2N–CO–[CH_2]_2–CH(NH_2)–CO–$, derived from glutamine. *Compare* **isoglutaminyl**.

glutamo the alkylamino group, $HOOC–[CH_2]_2–CH(COOH)–NH–$, derived from glutamic acid.

glutamoyl the diacyl group, $–CO–[CH_2]_2–CH(NH_2)–CO–$, derived from glutamic acid.

α-glutamyl glutam-1-yl; the α-monoacyl group, $HOOC–[CH_2]_2–CH(NH_2)–CO–$, derived from glutamic acid.

γ-glutamyl *or (formerly)* isoglutamyl, glutam-5-yl; the γ-monoacyl group, $–CO–[CH_2]_2–CH(NH_2)–COOH$, derived from glutamic acid.

glutamyl aminopeptidase EC 3.4.11.7; *other names*: aminopeptidase A; angiotensinase A; differentiation antigen gp160; an enzyme that removes an N-terminal glutamyl residue from a peptide. It can also hydrolyse N-terminal aspartase, and can thus inactivate **angiotensin** II, being expressed in kidney, as well as on cells of the capillaries and intestine, and on lymphocytes.

γ-glutamyl cycle a cycle of chemical events that uses the γ-carboxyl group of glutamate to transport amino acids actively across (mammalian) cell membranes. Glutathione reacts by transpeptidation with the amino acid to be transported. The resulting γ-glutamylamino acid enters the cell, where it is split into the free amino acid and 5-oxoproline. The latter is then converted to glutamate in an ATP-dependent reaction. The cysteinylglycine is hydrolysed by a peptidase. Glutathione is then regenerated in two ATP-dependent steps. *See also* **glutamyltransferase**.

glutamyl endopeptidase γ-glutamylcysteine synthetase *see* **glutamate–cysteine ligase**.

glutamyl endopeptidase EC 3.4.21.19; *other names*: staphylococcal serine proteinase; V8 proteinase; protease V8; endoproteinase Glu-C. An enzyme that catalyses the preferential cleavage: Asp-|-Xaa, Glu-|-Xaa.

glutamyltransferase *abbr. (in clinical chemistry)*: GMT; EC 2.3.2.2; *recommended name*: γ-glutamyltransferase; *systematic name*: (5-L-glutamyl)-peptide:amino acid 5-glutamyltransferase; *other name*: γ-glutamyl transpeptidase. An ectoenzyme of plasma membrane that reversibly transfers a γ-L-glutamyl residue (linked to the substrate by an isopeptide bond) from the N terminus of a peptide, normally glutathione, to the amino group of an amino acid. It is present in high concentrations in liver, kidney, prostate, and pancreas, and is useful diagnostically in liver or biliary disease, levels being five times normal or more in cholestasis, hepatitis, and cirrhosis, and also in pancreatitis; it is also elevated in the plasma of alcoholics. The level in normal human (male) plasma is <60 IU L^{-1}. *See also* **γ-glutamyl cycle**.

glutaraldehyde pentanedial; a compound that is useful as a tissue fixative in electron microscopy, as a crosslinking agent for compounds containing amino groups, and as a sporicide.

glutaramic acid *the trivial name for* 4-carbamoylbutanoic acid; $H_2N–CO–[CH_2]_3–COOH$; the monoamide of glutaric acid (*see* **glutarate**).

glutarate **1** *trivial name for* propane-1,3-dicarboxylate; pentanedioate; $^{-}OOC–[CH_2]_3–COO^{-}$; the dianion of glutaric acid (pentanedioic acid). **2** any mixture of free glutaric acid and its mono- and dianions. **3** any (partial or full) salt or ester of glutaric acid.

glutaredoxin a monomeric polypeptide with a similar function to **thioredoxin**. It can replace thioredoxin, or may be the main reactant, in the pathway for nucleotide reduction.

glutaric acidemia *or (esp. Brit.)* **glutaric acidaemia** the abnormal elevation of levels of glutaric and hydroxyglutaric acids in plasma and their excessive excretion in urine. **Type I** glutaric acidemia is associated with severe infantile dyskinesia and dystonia, and results from numerous mutations that produce deficiency of **glutaryl-CoA dehydrogenase**. **Type II** is associated with metabolic acidosis and hypoglycemia, and results from mutations in **electron-transfer flavoprotein** or **electron-transferring flavoprotein dehydrogenase**.

glutaryl-CoA dehydrogenase EC 1.3.99.7; a flavoprotein decarboxylase that catalyses the reaction between glutaryl-CoA and electron transfer flavoprotein (ETF) to form crotonoyl-CoA, CO_2, and reduced ETF. *See* **glutaric acidemia**.

glutathione *abbr.*: GSH; *symbol*: Glu(-Cys-Gly); γ-glutamylcysteinylglycine, a tripeptide that is widely distributed in most if not all cells. It acts as a coenzyme for some enzymes and as an antioxidant in the protection of sulfhydryl groups in enzymes and other proteins; it has a specific role in the reduction of hydrogen peroxide and oxidized ascorbate, and it participates in the **γ-glutamyl cycle**. Oxidation links two molecules by a disulfide bond (represented as GSSG). For clarity, glutathione is sometimes termed **reduced glutathione** (*or* the reduced form of glutathione). It is involved in the synthesis of certain leukotrienes.



glutathione dehydrogenase (ascorbate) EC 1.8.5.1; an enzyme that catalyses the reduction by two molecules of glutathione of dehydroascorbate to form oxidized glutathione and ascorbate.

glutathione peroxidase EC 1.11.1.9; *systematic name*: glutathione:hydrogen-peroxide oxidoreductase. An enzyme that catalyses the reaction:

$$2 \text{ glutathione} + H_2O_2 = \text{oxidized glutathione} + 2H_2O.$$

It has a UGA-encoded selenocysteine residue at its active site. Its main role is to protect hemoglobin from oxidative breakdown: the oxidized glutathione is reduced by **glutathione reductase**, the system thus contributing to a reduction of peroxide levels in the cell.

glutathione reductase *abbr. (in clinical chemistry)*: GTD; EC 1.6.4.2; *recommended name*: glutathione reductase (NADPH); *systematic name*: NADPH:oxidized-glutathione oxidoreductase. A homodimeric enzyme that catalyses the reaction:

$$\text{NADPH} + \text{oxidized glutathione} = \text{NADP}^+ + 2 \text{ glutathione}.$$

It has FAD as cofactor, and is important in maintaining glutathione in the reduced state.

glutathione synthase EC 6.3.2.3; *other name*: glutathione synthetase; the second cytosolic enzyme of the formation of glutathione from ATP, γ-L-glutamyl-L-cysteine, and glycine with release of ADP and orthophosphate. The mammalian enzyme is a homodimer. Deficiency in humans produces glutathione deficiency, (5)-oxoprolinuria, hemolysis, and central nervous system symptoms.

glutathione transferase EC 2.5.1.18; *systematic name*: RX:glutathione R-transferase; *other names*: glutathione *S*-alkyltransferase; glutathione *S*-aryltransferase; *S*-(hydroxyalkyl)glutathione lyase; glutathione *S*-aralkyltransferase; glutathione *S*-transferase. Glutathione transferases catalyse various glutathione-dependent reactions:

(1) nucleophilic substitution, e.g.

$$RX + GSH \rightarrow RSG + HX$$

where RX is an aryl- or alkyl-halide (EC 2.5.1.18); (2) addition of GSH across activated unsaturated carbon–carbon or carbon–nitrogen bonds (often α,β-saturated ketones/ thiones) or oxirane, e.g.



$$\underbrace{R\text{–}CH\text{–}CH_2}_{O} + GSH = R\text{–}CHOH\text{–}CH_2SG;$$

(3) organic hydroperoxide reduction (selenium-independent GSH peroxidase):

$$ROOH + 2GSH \rightarrow ROH + GSSG + H_2O;$$

(4) organic nitrite reduction

$$RONO + GSH \rightarrow GSNO + ROH;$$

(5) isomerizations in which GSH acts as cofactor, e.g. conversion of prostaglandin H to prostaglandin D. The proteins also bind a variety of hydrophobic anions, e.g. hematin, fatty acid and steroid metabolites, and various xenobiotics/metabolites including the GSH conjugates which may be their catalytic products. Such binding is responsible for their retention by S-linked GSH-Sepharose, hence the widely used simple purification of **GST fusion proteins**. GSH transferases were originally identified as binding proteins (*see* **ligandin**) and are widely distributed, abundant dimeric soluble enzymes or trimeric membrane-bound forms. They are generally considered an important part of phase II metabolism of xenobiotics. Five classes of soluble GSH transferase subunits have been distinguished (α, μ, π, θ, and σ) and heterodimers occur at least within classes yielding, for example, about 20 different isoenzymes in the rat. Distinct soluble mitochondrial and bacterial forms also occur.

glutelin any member of a group of simple proteins found especially in the seeds of cereal plants. They are insoluble in water, dilute salt solutions, and ethanol, but are soluble in dilute acids or alkalis. The group includes the **glutenins** of wheat, the hordenins of barley, and the oryzemins of rice. They serve as storage proteins, and have Gln-rich domains. *Compare* **prolamin**.

gluten a proteinaceous fraction obtained from certain cereal seeds, especially wheat, consisting of a considerable number of proteins that are all either **glutelins** or **prolamins**. It forms a sticky mass when wet, and gives dough its characteristic consistency. *See also* **celiac disease**.

glutenin any **glutelin** of the endosperm of wheat seeds. Glutenins form aggregates of high molecular mass in which they are linked together by disulfide bridges; they are thought to be responsible for the viscoelastic properties of wheat dough. The sequences contain a central low-complexity region, rich in glutamine, proline, glycine, tyrosine, threonine, and serine residues; these cluster within several different types of repeating unit, but all sequences include QQPGQG and QQGYYPTS motifs. *Compare* **gliadin**.

Glx *general symbol for* a residue of any α-amino (or imino) acid that yields L-glutamic acid on acid hydrolysis. It was formerly used only for L-glutamic acid (*specific symbol*: Glu) or L-glutamine (*specific symbol*: Gln), but is now used to represent any such residues, including those of L-4-carboxyglutamic acid (*specific symbol*: Gla) and 5-oxoproline (= pyroglutamic acid) (*specific symbol*: Glp); (alternative to Z).

Gly *symbol for* a residue of the achiral (α-)amino acid glycine (alternative to G).

glyburide 1-[[*p*-[2-(chloro-*o*-anisamido)ethyl]phenyl]sulfonyl]-3-cyclohexylurea; glibenclamide; a sulfonylurea with oral hypoglycemic actions similar to **tolbutamide**.



glyc+ *a variant form of* **glyco+** (before a vowel).

glycaemia *a variant spelling (esp. UK) of* **glycemia**.

glycamine any ω-amino-ω-deoxyalditol, i.e. any compound formally derived from an **alditol** by replacement of a terminal hydroxyl group by an amino group.

glycan *or* **polysaccharide** any polymer consisting of more than about 10 monosaccharide (i.e. glycose) residues joined by glycosidic linkages. A **homoglycan** (*or* **homopolysaccharide**) contains only one type of monosaccharide residue, whereas a **heteroglycan** (*or* **heteropolysaccharide**) contains two or more different kinds of monosaccharide residue. A homoglycan is named, generally, after the constituent monosaccharide, with the +ose ending replaced by +an; hence, cellulose, dextran, dextrin, and starch are all glucans, since they consist of glucose. *Compare* **glycosan**.

glycaric acid *an obsolescent name for* **aldaric acid**.

glycated hemoglobin *or* **glycohemoglobin** any derivative of hemoglobin that is formed nonenzymically by reaction at the N terminus with glucose. In the normal adult human such derivatives constitute a few percent of the total erythrocyte hemoglobin, the most abundant being **hemoglobin A_{1c}**, which increases severalfold in concentration in diabetes mellitus, and is assayed to monitor control of diabetes. Glycation of other proteins such as lens crystallins, collagen and low-density lipoproteins has been implicated in the pathogenesis of diabetic complications. It is sometimes improperly termed **glucosylated hemoglobin** or **glycosylated hemoglobin**. *See also* **glycation**.

glycated proteins glycation is the post-translational modification of a protein by the covalent attachment of a sugar residue, resulting from the spontaneous amino–carbonyl reaction (the **Maillard reaction**) between these two moieties. The reaction occurs principally between the free amino groups of proteins and the carbonyl group of reducing sugars, as first described by Louis-Camille Maillard in 1912. The initial condensation to form a Schiff's base is a spontaneous, but reversible, reaction that is rapidly followed by a complex series of irreversible reactions, ultimately leading to generation of Amadori products of brown pigments, and cross-linking of the polypeptide chains involved. The importance of the Maillard reaction has long been recognized in the food industry, where it causes spoilage, and produces colour and off-flavour in cooked foods. In 1977, Cerami identified an Amadori product in variants of human hemoglobin. Glycation of various proteins has now been implicated in the etiology of various diseases, such as the development of Alzheimer-type pathology. *See* **Alzheimer's disease**. *See also* **glycation**.

glycation any chemical reaction, whether enzyme-catalysed or not, that links a glycose (i.e. a sugar) to a peptide or protein and thereby forms a glycopeptide or glycoprotein. The term thus includes (enzymic or nonenzymic) **glycosylation** (and hence **glucosylation**) of a peptide or protein. However, it is usefully applied in addition to any (nonenzymic) reaction of glucose (or another sugar) with a peptide or protein where the product is not a glycoside but results from condensation of the sugar with free amino groups to form a **Schiff base** which then undergoes an **Amadori rearrangement**. **—glycated** *adj.*

glycemia *or* **glucemia** *or (esp. UK)* **glycaemia** *or* **glucaemia** **1** the presence of glucose (strictly sugar) in the blood. **2** the concentration of (strictly) sugar but, in fact, glucose in the blood. When this concentration is within normal limits the condition of the blood (or of the corresponding individual) is termed **normoglycemia**. An abnormally elevated concentration, **hyperglycemia**, may result in thirst, whereas an abnormally depressed concentration, **hypoglycemia**, may produce sweating, trembling, hunger, irritability, and in extreme cases confusion or coma. *See also* **blood sugar**, **glucose-tolerance test**, **insulin-tolerance test**. **—glycemic** *or* **glycaemic** *or* **glucemic** *or* **glucaemic** *adj.*

glycemic index *or (esp. UK)* **glycaemic index** the area under the blood glucose response curve for a food expressed as a percentage of the area produced by ingesting the same amount of carbohydrate as glucose. It is usually determined as the mean for 5–10 individuals. Examples include: carrots 92 ± 20; bread (white) 69 ± 5; whole milk 34 ± 6; peas (blackeye) 33 ± 4; fructose 20 ± 5.

glyceral *an alternative name for* **glyceraldehyde**.

glyceraldehyde *symbol*: Gra; glyceral; 2,3-dihydroxypropanal; *formerly sometimes known as* **glyceric aldehyde**; *sometimes (not recommended) called* **glycerose**. It is the simplest chiral aldose and a constitutional isomer of **glycerone**. The naturally occurring form is D-glyceraldehyde, the absolute configuration of which is known and is taken as the configurational reference standard for the D-, and hence also for the L-, forms of monosaccharides.



$$\begin{array}{c} \mathrm{CHO} \\ | \\ \mathrm{H{-}C{-}OH} \\ | \\ \mathrm{CH_2OH} \end{array}$$

D-glyceraldehyde

D-glyceraldehyde 3-phosphate *abbr.*: D-glyceraldehyde-3-*P*; an important intermediate in glycolysis. It is isomeric with **glycerone phosphate**. (phosphorylating) (phosphorylating)

glyceraldehyde-3-phosphate dehydrogenase ($NADP^+$) (phosphorylating) EC 1.2.1.13; *other name*: triosephosphate dehydrogenase ($NADP^+$); an enzyme that catalyses the conversion of D-glyceraldehyde 3-phosphate, orthophosphate, and $NADP^+$ to 3-phospho-D-glyceroyl phosphate and NADPH.

glyceraldehyde-3-phosphate dehydrogenase (phosphorylating) *abbr.*: GAPDH; EC 1.2.1.12; *systematic name*: D-glyceraldehyde-3-phosphate:NAD^+ oxidoreductase (phosphorylating); *other name*: triosephosphate dehydrogenase. An homotetrameric enzyme that catalyses a reaction between D-glyceraldehyde 3-phosphate, orthophosphate, and NAD^+ to form 3-phospho-D-glyceroyl phosphate and NADH. It is important in the pathways of glycolysis and gluconeogenesis. GAPDH is used as an internal standard in Northern blotting and real-time polymerase chain reaction (RT-PCR) because its mRNA is expressed constitutively in mammalian tissues.

glycerate *symbol*: Gri; **1** 2,3-dihydroxypropanoate; $HOCH_2$–CH(OH)–COO^-; the anion derived from glyceric acid. The naturally occurring form is D-glycerate. **2** any salt or ester of glyceric acid.

glyceric aldehyde *former name for* **glyceraldehyde**.

glyceride *the former name for* **acylglycerol**; i.e. any ester of glycerol, especially the mono-, di-, or triesters of glycerol with fatty acids, formerly termed mono-, di-, or triglycerides respectively. These are now known as mono-, di-, or tri-*O*-acylglycerols.

glycerin(e) *see* **glycerol**.

glycero+ *prefix* or *infix (in chemical nomenclature)* **1** denoting a residue of glycerol. **2** denoting the acyl group derived from glyceric acid.

glycero- *prefix (in chemical nomenclature)* indicating the presence of a single CHOH group, in the D or L configuration as specified.

glycerokinase *see* **glycerol kinase**.

glycerol *symbol*: Gro; 1,2,3-propanetriol; a sweet, hygroscopic, viscous liquid, widely distributed in nature as a constituent of many lipids (*see* **acylglycerol**). The older name **glycerin(e)** is now obsolete except in non-technical usage and sometimes in pharmacy.

glycerol channel *or* **glycerol facilitator** (*abbr.*: GlpF) an integral membrane protein of bacteria and fungi that mediates facilitated diffusion of glycerol. The crystal structure shows eight transmembrane segments that form a channel lined with amphipathic and hydrophobic residues on one side and polar residues on the other, and that permits glycerol molecules to pass through it in single file.

glycerol kinase EC 2.7.1.30; *systematic name*: ATP:glycerol 3-phosphotransferase; *other name*: glycerokinase. An enzyme that catalyses the phosphoryation by ATP of glycerol to form *sn*-glycerol 3-phosphate with release of ADP. The amino-acid sequence is remarkably conserved from prokaryotes to mammals. In the latter, the enzyme is cytosolic and also bound to porin of the outer mitochondrial membrane. The enzyme is induced, e.g. in *Escherichia coli*, by *sn*-glycerol 3-phosphate; it is a homotetramer.

glycerol phosphate *or* **glycerophosphate** any of three isomeric phosphoric monoesters of glycerol; of these, two are chiral and form an enantiomeric pair, whereas the third is achiral. The earlier nomenclature of the chiral esters has been confusing; ambiguities are avoided by the adoption of **stereospecific numbering** (*symbol*: *sn*-). (1) *sn*-glycerol 3-phosphate *or* *sn*-glycero-3-phosphate *or* 3-phospho-*sn*-glycerol *or* 3-*O*-phosphono-*sn*-glycerol (*abbr.* *sn*-glycerol-3-*P*) are alternative recommended names for the chiral ester (*R*)-[glycerol 1-(dihydrogen phosphate)]; (*R*)-[2,3-dihydroxypropyl dihydrogen phosphate]. It was previously known as L-glycerol 3-phosphate or D-glycerol 1-phosphate, and originally named D-glycerol 1-phosphate *or* L-*a*-glycerophosphate *or* L-*a*-glycerophosphoric acid. It is a component of many phospholipids. The absolute configuration is illustrated. (2) *sn*-glycerol 1-phosphate *or* *sn*-glycero-1-phosphate *or* 1-phospho-*sn*-glycerol *or* 1-*O*-phosphono-*sn*-glycerol (*abbr.* *sn*-glycerol-1-*P*) are alternative recommended names for the chiral ester (*S)*-[glycerol 1-(dihydrogen phosphate)]; (*S*)-[2,3-dihydroxypropyl dihydrogen phosphate]. It was previously known as L-glycerol 1-phosphate *or* D-glycerol 3-phosphate, and originally named L-glycerol 1-phosphate *or* D-*a*-glycerophosphate *or* D-*a*-glycerophosphoric acid. This enantiomer is rarely encountered. (3) glycerol 2-phosphate *or* glycero-2-phosphate *or* 2-phosphoglycerol *or* 2-*O*-phosphonoglycerol are alternative names for the achiral ester glycerol 2-(dihydrogen phosphate); di(hydroxymethyl)methyl dihydrogen phosphate. It was originally named *β*-glycerophosphate *or* *β*-glycerophosphoric acid. It is an artefact occurring in hydrolysates of glycerophospholipids that arises by migration of the phosphate group from C-1 to C-2 of the glycerol moiety. *Distinguish from* **phosphoglycerate**.



$$\begin{array}{lll} & \mathrm{CH_2OH} & \\ & | & \\ \mathrm{HO{-}} & \mathrm{C{-}H} & \mathrm{O} \\ & | & \| \\ \mathrm{H_2} & \mathrm{C{-}O{-}} & \mathrm{P{-}OH} \\ & & | \\ & & \mathrm{OH} \end{array}$$

sn-glycerol 3-phosphate

glycerol-3-phosphate cycle *or* **glycerol-3-phosphate shuttle** *or* ***α*-glycerophosphate cycle** an intracellular metabolic cycle that can transfer reducing equivalents from the cytosol to the mitochondria.

In the cytosol NAD-linked **glycerol-3-phosphate dehydrogenase (NAD+)** catalyses the reduction of glycerone phosphate (formed together with glyceraldehyde 3-phosphate in glycolysis) to *sn*-glycerol 3-phosphate. The latter enters the mitochondria where it is oxidized to glycerone phosphate by the FAD-linked mitochondrial glycerol-3-phosphate dehydrogenase. The glycerone phosphate then returns to the cytosol to complete the cycle. The overall result is the oxidation of cytosolic NADH + H^+ to NAD^+ and the reduction of mitochondrial enzyme–FAD to enzyme–$FADH_2$.

glycerol-3-phosphate cytidylyltransferase EC 2.7.7.39; *other name*: CDPglycerol pyrophosphorylase; an enzyme that catalyses the formation of CDPglycerol from CTP and *sn*-glycerol 3-phosphate with release of pyrophosphate.

glycerol-3-phosphate dehydrogenase *abbr*.: G3PDH; EC 1.1.99.5; a flavoprotein enzyme that catalyses the oxidation by an electron acceptor of *sn*-glycerol 3-phosphate to glycerone phosphate. It is part of the **glycerol 3-phosphate cycle**. In *Escherichia coli* there are two unrelated enzymes: anaerobic G3PDH, which is an iron–sulfur flavoprotein comprising two subunits; and aerobic G3PDH.

glycerol-3-phosphate dehydrogenase (NAD⁺) EC 1.1.1.8; *systematic name*: *sn*-glycerol-3-phosphate:NAD^+ 2-oxidoreductase. An enzyme that catalyses the reaction:

$$sn\text{-glycerol 3-phosphate} + NAD^+ = \text{glycerone phosphate} + NADH.$$

Its role is especially important in the provision of glycerol 3-phosphate for lipid synthesis, using glycerone phosphate derived from glucose by the **glycolytic** pathway, and as a component of the **glycerol-3-phosphate cycle**. *See* **flightin.**

glycerol-3-phosphate *O*-acyltransferase EC 2.3.1.15; *systematic name*: acyl-CoA:*sn*-glycerol-3-phosphate 1-*O*-acyltransferase; it catalyses the acylation by acyl-CoA of glycerol 3-phosphate to form 1-acyl-*sn*-glycerol 3-phosphate (lysophosphatidic acid) with release of CoA. This is the first step in phospholipid biosynthesis and may be involved in regulation of membrane biogenesis. Plants exhibit oleate-selective acyltransferases; the enzyme from chilling-resistant plants discriminates against palmitic acid (a fatty acid with high transition temperature), and selects oleic acid (leading to more fluid membranes), whereas the acyltransferase from sensitive plants accepts both fatty acids.

glycerol-3-phosphate oxidase EC 1.1.3.21; *systematic name*: *sn*-glycerol-3-phosphate:oxygen 2-oxidoreductase. An enzyme that catalyses the oxidation by dioxygen of *sn*-glycerol 3-phosphate to glycerone phosphate and hydrogen peroxide; FAD is a cofactor. It is a mitochondrial protein. In insects it plays an important role in the transfer of energy for flight, along with **glycerol-3-phosphate dehydrogenase (NAD+)** (flightin).

glycerol trinitrate *see* **trinitroglycerine**.

glycerone *symbol*: Grn; *the currently recommended trivial name for* dihydroxyacetone; 1,3-dihydroxy-2-propanone. It is the simplest ketose, is achiral, and is a constitutional isomer of glyceraldehyde.

glycerone phosphate *the currently recommended trivial name for* dihydroxyacetone phosphate; 1,3-dihydroxy-2-propanone 1-phosphate; the monoester formed by phosphorylation of dihydroxyacetone, glycerone. Glycerone phosphate and D-glyceraldehyde 3-phosphate are together described as triose phosphates and are interconvertible by triose-phosphate isomerase, EC 5.3.1.1. They are important components of the glycolytic pathway. Glycerone phosphate is a precursor of the glycerol moiety of glycerolipids.

glycerone transferase *see* **transaldolase**.

glycerophosphate *an alternative name for* **glycerol phosphate**.

α-glycerophosphate cycle *an alternative name for* **glycerol-3-phosphate cycle**.

glycerophosphate phosphatidyltransferase EC 2.7.8.5; *recommended name*: CDPdiacylglycerol–glycerol-3-phosphate 3-phosphatidyltransferase. An enzyme that catalyses a reaction between CDPdiacylglycerol and *sn*-glycerol-3-phosphate to form 3-(3-*sn*-phosphatidyl)-*sn*-glycerol 1-phosphate, with release of CMP. It is a membrane protein of endoplasmic reticulum and component of the pathway for the biosynthesis of acidic phospholipids; its product loses phosphate to form phosphatidylglycerol from which **cardiolipin** is formed.

glycerophospholipid *general name for* any derivative of glycerophosphate that contains at least one *O*-acyl, *O*-alkyl, or *O*-alkenyl group attached to the glycerol residue. Formerly known as phosphoglyceride.

glycerophosphoric acid *see* **glycerol phosphate**.

glycerose *alternative name* (not recommended) *for* **glyceraldehyde**.

glyceroyl 2,3-dihydroxypropanoyl; the acyl group, $HOCH_2$–CH(OH)–CO–, derived from glyceric acid.

glyceryl any group derived from glycerol by replacing or removing one or more of its hydroxyl groups.

glycidol *the trivial name for* 3-hydroxypropylene oxide; 2,3-epoxy-1-propanol.



S(–)-glycidol

glycidoyl 2,3-epoxypropanoyl; the acyl group derived from glycidic acid.



(*R*)-glycidoyl group

glycidyl 2,3-epoxypropyl; the alkyl group: derived from glycidol by removal of its hydroxyl group.

glycinamide *the trivial name for* the amide of glycine, aminoacetamide; aminoethanamide; $H_2N–CH_2–CO–NH_2$. It is predominantly cationic at neutrality and is useful as a buffer substance; pK_a (20°C) = 8.20.

glycinamide ribonucleotide synthetase (*abbr*. GARS) *see* phosphoribosylamine–glycine ligase.

glycinamide ribotide *N*-glycyl-5-phosphoribosylamine; an early intermediate in the biosynthesis of purines.

glycinate **1** glycine anion; the anion, $NH_2–CH_2–COO^–$, derived from **glycine**. **2** any salt containing glycine anion. **3** any ester of glycine.

glycine *symbol*: G *or* Gly; *the trivial name for* aminoacetic acid; aminoethanoic acid; $H_2N–CH_2–COOH$; an achiral (α-)amino acid, and the simplest naturally occurring amino acid. It is a coded amino acid found in peptide linkage in proteins; codon: GGA, GGC, GGG, or GGU (anticodon: CCU). In mammals, it is a non-essential dietary amino acid, and is **glucogenic**. It is sweet-tasting, hence its name. [From **glyc(o)+** (def. 1) + **+ine** (def. 1)]

glycine amidinotransferase EC 2.1.4.1; an enzyme that catalyses the formation of guanidinoacetate, a precursor of **creatine**, from L-arginine and glycine, also forming L-ornithine.

glycine betaine *N*-trimethylglycine. *See* **betaine**.

glycine cleavage enzyme *or* **glycine oxidase** (when working in the reverse direction); a multienzyme complex that resembles the pyruvate dehydrogenase complex but contains the following elements: **P protein**, a pyridoxal phosphate-dependent glycine decarboxylase; **H protein**, a lipoamide-containing aminomethyltransferase; **T protein**, an N^5,N^{10}-methylene tetrahydrofolate synthesizing enzyme; and **L protein**, an NAD-dependent, FAD-requiring lipoamide dehydrogenase. It provides the major mechanism for glycine degradation in mammalian tissues.

glycine hydroxymethyltransferase EC 2.1.2.1; *systematic name*: 5,10-methylenetetrahydrofolate:glycine hydroxymethyltransferase;

other names: serine hydroxymethylase; threonine aldolase; serine aldolase. An enzyme that catalyses the reaction:

$$5,10\text{-methylenetetrahydrofolate} + \text{glycine} + H_2O = \text{tetrahydrofolate} + \text{L-serine}.$$

It is a pyridoxal phosphate-requiring enzyme that interconverts glycine and serine; it transfers a hydroxymethyl group from N^5,N^{10}-methylenetetrahydrofolate to a glycine-pyridoxal phosphate Schiff base or from a serine-pyridoxal phosphate Schiff base to tetrahydrofolate.

glycine receptor a complex of integral membrane proteins that binds glycine and mediates its effects as an inhibitory neurotransmitter in lower brain areas and spinal cord. It is a pentamer of α (four isoforms, α1–α4) and β subunits, and forms an intrinsic Cl^- channel, blocked by strychnine (distinguishing it from the $GABA_A$ Cl^- channel). All subunits have four transmembrane segments, M1–M4, M3 and M4 being separated by a cytoplasmic hydrophilic loop; this is comparable to nicotinic acetylcholine receptors (*see* **cholinoceptor**) and $GABA_A$ receptors (*see* **GABA receptor**), with which some sequence similarities also exist. Glycine also binds to a site on the NMDA (glutamate) receptor, which must be occupied by glycine to enable activation of the receptor by NMDA, and is also blocked by strychnine.

glycine-rich proteins *abbr*.: GRP; one of the four major groups of **plant cell-wall proteins**. Glycine-rich proteins can contain over 70% glycine residues, are predicted to form beta sheets, and are thought to form a platelike structure at the interface between the plasma membrane and cell wall, perhaps becoming crosslinked to the latter. They are not heavily glycosylated.

glycinin a 350 kDa **globulin** that is the chief protein constituent of the soya bean, *Glycine max*. Structurally, it resembles **arachin**, **edestin**, and **excelsin**.

glycinium glycine cation; the cation, $H_3N^+–CH_2–COOH$, derived from **glycine**.

glycino the alkylamino group, $HOOC–CH_2–NH–$, derived from **glycine**.

glycitol *an obsolescent name for* **alditol**.

glyco+ *or (before a vowel)* **glyc+** *comb. form* **1** indicating sweet-tasting. **2 a** indicating sugar. **b** (*in medicine*) indicating glucose. *See also* **gluco+**. **3** *(in chemical nomenclature)* indicating covalently linked to carbohydrate. **4** indicating combination with glycine; e.g. **glycocholate**, **glycocyamine**.

glycoamino acid any compound in which a saccharide is combined with an amino acid through any kind of covalent linkage. The term includes **glycosylamino acids**.

glycobiology the branch of biochemistry dealing with **glycoconjugates**, including their structure, analysis, function, and metabolism.

glycocalicin a carbohydrate-rich hydrophilic fragment, M_r 130 000, cleaved from the external portion of the α chain of **glycoprotein Ib** by protease action.

glycocalyx *or* **cell coat** a zone surrounding many plant and animal cells that is rich in glycoproteins and proteoglycans.

glycocholate 1 the anion of glycocholic acid; *N*-cholylglycine; a bile acid. The anions of similar glycine conjugates of other bile acids are known, e.g. glycochenodeoxycholate, **glycodeoxycholate**, glycolithocholate. **2** any salt of glycocholic acid. Sodium glycocholate is the chief **bile salt** in humans and herbivorous animals. It is useful as a detergent; aggregation number 2.1, CMC 7.1 mm.



glycocholic acid

glycocoll *an obsolete name for* **glycine**.

glycoconjugate *or (formerly)* **glucoconjugate** any large and complex biological molecule that contains a carbohydrate moiety. The term comprehends glycolipid, glycopeptide, glycoprotein, peptide glycan, proteoglycan, and heteroglycan. *See also* **glyco+** (def. 3), **conjugate** (def. 5).

glycoconjugate syndrome *an alternative name for* **carbohydrate-deficient glycoprotein syndrome**.

glycocyamine *an older name for N*-amidinoglycine; guanidinoacetic acid. In polychaete worms, the guanidine group can undergo phosphorylation to phosphoglycocyamine, which acts as a **phosphagen**.

glycodeoxycholate 1 glycodeoxycholic acid; *N*-deoxycholylglycine; a bile acid. **2** any salt of glycodeoxycholic acid; sodium glycodeoxycholate is useful as a detergent; aggregation number 2, CMC 2.1 mm.

glycoform any of several differently glycosylated variants of a specified glycoprotein. Glycoforms may vary in the type, number and/or position of the sugar residues, differ in their physiological properties (e.g., rate of action), and occur together in a given tissue.

glycogen a polydisperse, highly branched glucan or polyglucose, composed of chains of D-glucose residues in $\alpha(1\rightarrow4)$ glycosidic linkage, joined together by $\alpha(1\rightarrow6)$ glycosidic linkages; a small number of $\alpha(1\rightarrow3)$ glycosidic linkages and some cumulative $\alpha(1\rightarrow6)$ links also may occur. Its structure is similar to that of **amylopectin** but with more, though rather shorter, branches; those in glycogen variously contain 8 to 12 glucose residues. The size of the molecule varies greatly according to source and method of measurement, with average M_r values of 2.5×10^5 to upwards of 1.5×10^7 reported. Glycogen serves as a cellular store of glucose; it occurs, frequently as granules, in all animal tissues, especially liver and skeletal muscle, and also in some bacteria and yeasts. The glycogen molecule is linked to the protein **glycogenin** which is required for the *ab initio* synthesis of glycogen by **glycogen synthase**.

glycogenase *an alternative name for* either α- or β-**amylase**.

glycogen branching enzyme *see* **branching enzyme**.

glycogen disease *or* **glycogen storage disease** *or* **glycogenosis** any human disease in which there is an inherited abnormality in glycogen metabolism. Such diseases have been classified into eight types. Type I glycogen disease (*or* **von Gierke's disease**) involves a deficiency of hepatic **glucose-6-phosphatase** or of the endoplasmic reticulum (ER) transporter for glucose-6-phosphate, for glucose, or for phosphate. It is an autosomal recessive disease of infants, characterized by massive hepatomegaly, failure to thrive, severe hypoglycemia, and increased hepatic content of normal glycogen. Type II glycogen disease (*or* **Pompe's disease**) involves a generalized deficiency of lysosomal α-**glucosidase**. It is an autosomal recessive disease of infants, characterized by massive cardiomegaly, hypotonia, and an increased content of normal glycogen in virtually all tissues. Type III glycogen disease (*or* **limit dextrinosis** *or* **Cori's disease**) involves a generalized deficiency of amylo-1,6-glucosidase (debrancher enzyme) (EC 3.2.1.33). It is an autosomal recessive disease of infants that is similar to, but milder than, type I glycogen disease. It is characterized by an elevated content of glycogen in muscle, liver, and erythrocytes, the glycogen having abnormally short outer branches. A number of subtypes have been recognized. Type IV glycogen disease (*or* **amylopectinosis** *or* **Andersen's disease**) is a rare condition of infants in which there is a generalized deficiency of 1,4-α-glucan branching enzyme (EC 2.4.1.18). It is characterized by hepatic cirrhosis, hepatosplenomegaly, ascites, and glycogen with abnormally long outer branches; the glycogen may not accumulate excessively. Type V glycogen disease (*or* **McArdle's disease**) involves a deficiency of glycogen phosphorylase (EC 2.4.1.1) in voluntary muscle. The disease is probably autosomal recessive. It is characterized by myoglobinuria and painful cramps occurring during strenuous exercise, symptoms that do not usually appear until 20 years of age. There is no hypoglycemia but muscular exercise fails to elevate the blood lactate concentration. Type VI glycogen disease (*or* **Hers's disease**) involves an increased hepatic glycogen content and a lowered hepatic glycogen phosphorylase (EC 2.4.1.1) activity but a normal phosphorylase-activating system. The clinical course is mild. Type VII glycogen disease involves a deficiency of muscle 6-**phosphofructokinase**. The disease is probably autosomal recessive and is clinically identical to Type V glycogen disease. There are raised contents in muscles of normal glycogen, glucose 6-phosphate, and fructose 6-phosphate, together with a lower than normal concentration of fructose 1,6-bisphosphate. Type VIII glycogen disease involves a reduced **phosphorylase kinase** activity in the liver and in leukocytes. Thought to be inherited as an X-linked character, the disease is characterized by mild hepatomegaly, increased liver glycogen content, and mild hypoglycemia. Type IX glycogen disease results from phosphorylase kinase deficiency. There are several forms depending on which subunit (or isoform) is affected. At least five other types exist, but are very rare.

glycogenesis the metabolic formation of glycogen from sugar (i.e. glucose).

glycogenetic of or relating to the production of glycogen. (*Note*: The term is often used confusingly in the senses of **glycogenic** (def. 1, 2).)

glycogenic **1** of, relating to, or involving glycogen. **2** of or relating to the formation of sugar (i.e. glucose), especially in animals; glucogenic. (*Note*: the term is often used confusingly in the sense of **glycogenetic**.)

glycogenin EC 2.4.1.186; *recommended name*: glycogenin glucosyltransferase; a protein that is required for the initiation of glycogen synthesis by glycogen synthase. Glycogenin catalyses formation of a glycosidic link between a glucose and one of its own tyrosines (Tyr^{194} in human), and then catalyses addition of a further five glucose molecules. UDPglucose is the donor of the glucose units. This forms a primer, which is then extended with further glucose molecules by **glycogen synthase**. Glycogen synthase is only catalytically efficient when it is bound to glycogenin. This has two consequences: first, the number of glycogen granules is determined by the number of molecules of glycogenin, and second, elongation stops when the synthase is sterically prevented from contact with glycogenin, which forms the core of the particle. Hence, the glycogenin–synthase interaction limits the size of glycogen granules. Glycogenin is a monomeric glycoprotein (via its reactivity), tightly bound to the 86 kDa catalytic subunit of glycogen synthase.

glycogenolysis the breakdown of glycogen into glucose, either by hydrolysis or via glucose 1-phosphate and glucose 6-phosphate. The term is sometimes restricted to the phosphorolysis of glycogen to glucose 1-phosphate. **—glycogenolytic** *adj.*

glycogenosis *an alternative name for* **glycogen disease**.

glycogen phosphorylase *see* **phosphorylase**.

glycogen phosphorylase kinase EC 2.7.11.1; *recommended name*: ATP:phosphorylase-*b* phosphotransferase, other names glycogen phosphorylase kinase; PHK; phosphorylase *b* kinase. An enzyme that phosphorylates a specific serine residue in each of the subunits of the dimeric phosphorylase *b*. Requires Ca^{2+} and calmodulin for activity.

glycogen storage disease *an alternative term for* **glycogen disease**.

glycogen synthase EC 2.4.1.11; *recommended name* (example): glycogen (starch) synthase (the nature of the synthetic product should be included in the name); *systematic name*: UDPglucose:glycogen 4-α-D-glucosyltransferase; *other name*: UDPglucose–glycogen glucosyltransferase. An enzyme that catalyses the reaction between UDPglucose and (1,4-α-D-glucosyl)$_n$ to form (1,4-α-D-glucosyl)$_{n+1}$ with release of UDP. The mammalian enzyme requires glucosylated **glycogenin** as a primer (product of glycogenin glucosyltransferase, EC 2.4. 1.186), and is susceptible to allosteric activation by glucose 6-phosphate, and phosphorylation by a cyclic AMP-dependent kinase. *See also* **dependent form of glycogen synthase, glycogenin**, **starch synthase**.

[glycogen-synthase-D] phosphatase EC 3.1.3.42; an enzyme that hydrolyses phosphate from glycogen synthase D, thereby activating it.

glycogen synthase kinase-3 *abbr.* **GSK-3**; a cytosolic serine/threonine protein kinase that (like several other protein kinases) phosphorylates one or more of nine serine residues in each subunit of **glycogen synthase**. It may be regulated by inactivation by protein kinase B in response to insulin. It is an important component of **Wnt** protein signalling during embryonal patterning and development and also thereafter. Wnt signalling inactivates GSK-3 by targeting it (in a complex with APC protein, β-catenin, and axin) for ubiquitination and proteosomal degradation. Human GSK-3 (420 amino acids) is highly homologous to SHAGGY (514 amino acids) of *Drosophila*. *Arabidopsis thaliana* contains ten GSK-3/SHAGGY-like kinase genes.

glycogen synthase α kinase *see* **non-specific serine/threonine protein kinase**.

glycoglycerolipid any **glycolipid** containing one or more glycerol residues.

glycohemoglobin *or (esp. UK)* **glycohaemoglobin** *an alternative term for* **glycated hemoglobin**.

glycoinositolphospholipid *see* **GPI anchor**.

glycol **1** ethylene glycol; ethane-1,2-diol; $HOCH_2–CH_2OH$. **2** *or* **glychol** any dihydric alcohol, i.e. any compound in which two alcoholic hydroxyl groups are on different carbon atoms (which are usually but not necessarily adjacent).

glycolaldehyde hydroxyacetaldehyde; hydroxyethanal; $HOCH_2–CHO$.

glycolate *or (formerly)* **glycollate** **1** *the trivial name for* hydroxyacetate; hydroxyethanoate; the anion, $HOCH_2–COO^–$, derived from **glycolic acid**. It is an important metabolite in C_3 plants. **2** any mixture of glycolic acid and its anion. **3** any salt or ester of glycolic acid. It is formed from phosphogycolate, a product of **ribulose bisphosphate carboxylase** when this is acting as an oxidase. It is converted to glyoxylate by glycolate oxidase (*see* **2-hydroxy-acid oxidase**).

glycolate oxidase an FMN-containing enzyme that oxidizes glycolate to glyoxylate in plant peroxisomes. It is now included with **2-hydroxy-acid oxidase**.

glycolic acid *or (formerly)* **glycollic acid** hydroxyacetic acid; hydroxyethanoic acid; $HOCH_2–COOH$; a constituent of sugar-cane juice.

glycolipid any compound containing (usually) one to four linked glycose residues joined by a glycosyl linkage to a lipid moiety (e.g. to a mono- or diacylglycerol, to a long-chain base such as sphingosine, or to a ceramide) or (in a bacterial glycolipid) joined in ester linkage to one or more fatty-acid molecules. The term embraces **galactolipid**. *See also* **cerebroside**, **ganglioside**, **lipopolysaccharide**.

glycollate *an obsolete variant spelling of* **glycolate**.

glycoloyl *symbol*: Gc; the acyl group, $HOCH_2–CO–$, derived from **glycolic acid**.

glycolytic pathway *or* **Embden–Meyerhof(–Parnas) pathway** the widely distributed, cytosolic, metabolic pathway by which sugars, sugar phosphates, or their precursors are broken down with an overall negative free energy change favourable to formation of ATP; the pathway yields usually pyruvate aerobically or lactate anaerobically in animal tissues. By extension, the term is also used of similar processes in other organisms yielding, sometimes, other products, e.g. ethanol, glycerol, etc. Overall there is a net yield of 2 ATP for each glucose metabolized, since phosphorylation of the hexose substrates requires 2 ATP, but conversion to pyruvate of the two 3-carbon substrates formed yields 2 ATP for each. The pathway from glucose involves its conversion to glucose 6-phosphate, thence successively to fructose 6-phosphate, fructose 1,6-bisphosphate, glyceraldehyde 3-phosphate plus glycerone phosphate (which is converted to glyceraldehyde 3-phosphate in situations in which it is further degraded), 1,3-bisphosphoglycerate, 3-phosphoglycerate, 2-phosphoglycerate, phospho*enol*pyruvate, and pyruvate. The enzymes involved are hexokinase, glucose-6-phosphate isomerase, phosphofructokinase, fructose-bisphosphate aldolase, triose-phosphate isomerase, glyceraldehyde-3-phosphate dehydrogenase, phosphoglycerate kinase, phosphoglycerate mutase, enolase, and pyruvate kinase (*see* individual entries). Glycogen breakdown (**glycogenolysis**) by phosphorylase yields glucose 1-phosphate, which is converted by phosphoglucomutase to glucose 6-phosphate, which in muscle is then degraded by the pathway outlined above. The pathway is subject to hormonal regulation, especially by insulin, glucagon, and epinephrine. Flux through the pathway is under powerful regulation by phosphofructokinase, the main modulator of which is **fructose 2,6-bisphosphate**.

glycolytic oscillator any metabolic activity that produces periodic regular oscillations in the concentrations of intermediates of the **glycolytic pathway, as** observed in glycolysing yeast cells and extracts of skeletal muscle and heart. These oscillations reflect periodic changes in the activity of **phosphofructokinase** in response to changes in the levels of its activators and inhibitors.

glycome the full array of polysaccharide chains in a cell, tissue, organ, or organism. *Compare* **proteome**.

glycomics the study of all the carbohydrate molecules that are produced by an organism.

glycon *or (formerly)* **glycone** the carbohydrate moiety of any **glycoside** that also contains a noncarbohydrate component.

glyconeogenesis 1 *an alternative name for* **gluconeogenesis**. **2** *(sometimes)* the formation of glycogen from noncarbohydrate precursors.

glyconic acid *an obsolescent name for* **aldonic acid**.

glycopeptide any compound in which carbohydrate is covalently attached to an oligopeptide composed of residues of L- and/or D-amino acids. The term usually denotes a product of proteolytic degradation of a glycoprotein, but includes glycated peptide. It should be distinguished from **peptidoglycan**, for which it is sometimes considered to be a synonym.

glycophorin any of several type I membrane proteins of the erythrocyte membrane. They are carbohydrate-rich sialoglycoproteins (SGPs – hence the nomenclature for glycophorins: αSGP, etc.), and stain with periodic acid–Schiff (PAS) reagent (hence the nomenclature PAS 1, etc. for bands on electrophoresis). The glycosylated moiety serves as an antigenic determinant and as a receptor for viruses and plant agglutinins. A glycophorin was the first membrane protein to have its full sequence elucidated. There is a single membrane-spanning domain. **Glycophorin A** (*or* αSGP) is the major sialoglycoprotein of the human erythrocyte membrane. On electrophoresis, it occurs in PAS 1 (dimer). It has a molecular mass of ~31 kDa, contains 60% carbohydrate by weight, and consists of a 131- residue polypeptide chain that spans the cell membrane; all the carbohydrate is attached to the N-terminal half, and is exposed to the exterior of the cell. Glycophorin A displays either M or N blood group activity (*see* **MNSs system**), depending on which of two alternative pairs of amino-acid residues occurs at positions 1 and 5 in the sequence. It binds influenza virus. **Glycophorin B** (*or* δSGP), also from the human erythrocyte membrane, is a minor sialoglycoprotein, similar to glycophorins A and E. It occurs in PAS 3, and has an amino-acid sequence identical in its N-terminal segment to that of glycophorin A_N. It carries the immunodeterminants for the N and Ss antigens (*see* **MNSs system**). **Glycophorin C** (*or* βSGP) occurs in PAS 2, glycoconnectin; it is a minor sialoglycoprotein that probably contains blood group Gerbich antigens, and receptors for *Plasmodium falciparum* (malaria) merozoites. **Glycophorin E** is similar to glycophorins A and B.

glycoprotein a conjugated protein in which the non-protein group is a carbohydrate; the sugar moiety occurs most commonly as oligosaccharide or fairly small polysaccharide, but occasionally as monosaccharide. Glycoproteins are widespread in animals and in the primary cell walls of plants. The term includes glycated protein, and is now considered also to include **proteoglycan**. *Compare* **mucoprotein**.

glycoprotein hormone any of **follicle-stimulating hormone**, **luteinizing hormone**, and **thyroid-stimulating hormone** produced by the pituitary, and **chorionic gonadotropin**, produced by the placenta, all of which are heterodimers of glycosylated α and β subunits. In any given species, the amino-acid sequences of the α subunits are identical, or nearly so, whereas the β subunits have greater differences in amino-acid sequence and confer hormonal specificity on the molecules.

glycoprotein Ib *abbr*.: GP-Ib; a surface membrane protein of platelets that participates in the formation of platelet plugs by binding to von Willebrand factor. It is a disulfide-linked heterodimer of α and β subunits.

glycoprotein IIb/IIIa *abbr*.: GpIIb/IIIa; a major glycoprotein complex of the platelet surface. GpIIb consists of a heavy chain (containing seven homologous repeats that form a beta propeller and including four Ca^{2+}-binding sites) linked by a disulfide bond to a membrane-anchored light chain. Both chains are derived by cleavage from a precursor (1039 amino acids). GpIIIb (762 amino acids) contains five cysteine-rich regions and a transmembrane segment. On activation, e.g. by thrombin, the complex binds fibrinogen, fibronectin, and **von Willebrand factor**. Numerous mutations in GpIIb and in GpIIIa cause Glanzmann thrombasthenia.

glycoprotein *N*-palmitoyltransferase EC 2.3.1.96; an enzyme that catalyses a reaction between palmitoyl-CoA and a glycoprotein to give *N*-palmitoylglycoprotein with release of CoA.

glycosaemia *a variant spelling (esp. Brit) of* glycosemia (*see* **glycemia**).

glycosamine *an older name for* **aminodeoxysugar**, now restricted to some trivial names. *Distinguish from* **glycosylamine**.

glycosaminoglycan any glycan (i.e. polysaccharide) containing a substantial proportion of aminomonosaccharide residues.

glycosaminopeptide *an alternative name for* **peptidoglycan**.

glycosan *an old term (not recommended) for* any anhydrosugar whose formation involves its reducing group. *Distinguish from* **glycan**.

glycose 1 *a less frequently used term for* any monosaccharide. **2** *an obsolete name for* **glucose** (*see also* **glyco+** (def. 2)). **3** *(sometimes) an alternative name for* **corn syrup**.

glycosemia *or (esp. Brit)* **glycosaemia** *an alternative name for* **glycemia**.

glycosidase any hydrolase of subclass EC 3.2, enzymes that hydrolyse glycosidic linkages. Glycosidases are subdivided into those that hydrolyse *O*-glycosyl compounds (EC 3.2.1), *N*-glycosyl compounds (EC 3.2.2), or *S*-glycosyl compounds (EC 3.2.3). Some glycosidases can also transfer glycosyl residues to oligosaccharides, polysaccharides, or other acceptor alcohols. *See also* **(DNA) glycosylase**, **glucosidase**.

glycoside *or* **oside 1** any compound in which a **glycosyl** group is substituted into a hydroxyl group, a thiol group, or a selenol group in another compound; such a substance may be named, respectively, *O*-glycoside, *S*-glycoside (or thioglycoside), or *Se*-glycoside (or selenoglycoside). A glycoside is either a mixed acetal (if derived from a cyclic form of an aldose) or a mixed ketal (if derived from a cyclic form of a ketose). By extension, any compound formed by attachment of a glycosyl group to a hydrocarbyl group has been termed a *C*-glycoside and that by attachment of a glycosyl group to an amino or substituted amino group has been termed also *N*-glycoside (or nitrogen glycoside), but these terms are misnomers and should not be used; the preferred terms are ***C*-glycosyl compound** and **glycosylamine**, respectively. *See also* **cardiac glycoside**, **nucleoside**. **2** *an obsolete term for* **glucoside**.

glycosidic 1 of, pertaining to, or being a **glycoside**. **2** *an alternative term for* **anomeric** (def. 2).

glycosidic bond the covalent bond between the anomeric carbon atom of a saccharide and some other group or molecule with which it forms a glycoside.

glycosiduronate 1 the anion of a **glycosiduronic acid**. **2** any salt or ester of a glycuronic acid.

glycosiduronic acid *or (formerly)* **glycuronide** a glycoside of any **uronic acid**.

glycosome a microbody-like organelle present in *Trypanosoma brucei* and containing nine enzymes involved in glycolysis, and glycerol kinase.

glycosphingolipid any compound containing residues of a sphingoid and at least one monosaccharide. Glycosphingolipids are subdivided into: (1) neutral glycosphingolipids, comprising monoglycosyl- and oligoglycosylsphingoids and monoglycosyl- and oligoglycosylceramides; and (2) acidic glycosphingolipids, comprising sialosylglycosylsphingolipids (**gangliosides**) and sulfoglycosylsphingolipids (formerly known as sulfatides).

glycostatic maintaining a constant level of sugar, e.g. of glucose or glycogen. *Compare* **glycotropic**.

glycosuria the presence of abnormally high concentrations of glucose and/or other sugars in the urine. *See also* **glucosuria**, **fructosuria**.

glycosyl any chemical group formed by detaching the anomeric, i.e. glycosidic, hydroxyl group from the cyclic form of a monosaccharide or monosaccharide derivative, or (by extension) of a lower oligosaccharide or oligosaccharide derivative.

glycosylamine any compound formed by the replacement of the anomeric, i.e. glycosidic, hydroxyl group of a cyclic form of a monosaccharide or monosaccharide derivative by an amino group or a substituted amino group. (The term **nitrogen glycoside** (*or N*-glycoside) is a misnomer for glycosylamine and should not be used.) *Distinguish from* **glycosamine**.

glycosylamino acid any **glycoamino acid** in which the saccharide moiety is in glycosyl (*O*-, *N*- or *S*-) linkage to the amino-acid moiety. These are obtained by enzymic or chemical cleavage of glycoproteins, or by chemical or enzymic synthesis.

glycosylase *see* **(DNA) glycosylase**.

glycosylasparaginase *see* ***N*^{4}-(*β*-*N*-acetylglucosaminyl)-**L-asparaginase.

glycosylated hemoglobin *a misnomer for* **glycated hemoglobin**.

glycosylation substitution of one or more **glycosyl** groups into a chemical compound or group. *See also* **glycation**. **—glycosylated** *adj.*

***C*-glycosyl compound** any compound formed by the replacement of the anomeric, i.e. glycosidic, hydroxyl group of a cyclic form of a monosaccharide or monosaccharide derivative by an organyl group. The term *C*-glycoside is a misnomer for *C*-glycosyl compound and should not be used.

glycosyloxy any chemical group formed by detaching the hydrogen atom from the anomeric, i.e. glycosidic, hydroxyl group of the cyclic form of a monosaccharide or monosaccharide derivative.

glycosylphosphatidylinositol *see* **GPI anchor**.

glycosyltransferase *abbr.*: GT; any enzyme transferring a glycosyl group. Glycosyltransferases belong to subclass EC 2.4, which includes hexosyltransferases (EC 2.4.1.1 to 2.4.1.206); pentosyltransferases (EC 2.4.2.1 to 2.4.2.37); and enzymes transferring other glycosyl groups (EC 2.4.99.1 to 2.4.99.11).

glycotropic increasing the concentration of glucose in the blood. *Compare* **glycostatic**.

glycuronan *or (formerly)* **polyuronide** any glycan composed entirely of uronic-acid residues.

glycuronic acid *an obsolete term for* **uronic acid**.

glycuronide *the former term for* **glycosiduronic acid**.

glycyl the acyl group, NH$_2$–CH$_2$–CO–, derived from **glycine**.

glycyl chain *a name sometimes applied to* the **A chain** of any of those species of insulin whose amino-acid sequences were the first to be determined. It is so-called by virtue of the N-terminal glycine residue occurring in those instances.

glycylglycine a dipeptide useful for the preparation of buffers in the pH range around its pK_a (20 °C) of 8.40.

glycyrrhiza *also called* **liquorice** *or (esp. US)* **licorice**; a preparation obtained from the dried roots of the leguminous shrub, *Glycyrrhiza glabra*, with flavouring and medical uses.

glycyrrhizic acid 20*β*-carboxy-11-oxo-30-norolean-12-en-3*β*-yl-2-*O*-*β*-D-glucopyranuronosyl-*α*-D-glucopyranosiduronic acid; a glycosiduronic acid extracted from *glycyrrhiza (see* **glycyrrhiza** *)*; it has an intensely sweet taste.

glyoxal ethanedial; OHC–CHO; *also called* diformyl; the dialdehyde analogue of glycol and oxalic acid. It is sometimes used to replace formaldehyde in **denaturing agarose gel electrophoresis** of RNA. The basis of denaturation is the formation of an adduct with the imino groups of guanosine.

glyoxalase I EC 4.4.1.5; *recommended name*: lactoylglutathione lyase, *other name*: methylglyoxalase. An enzyme catalysing the reaction:

(*R*)-*S*-D-lactoylglutathione = glutathione + methylglyoxal.

glyoxalase II EC 3.1.2.6; *recommended name*: hydroxyacylglutathione hydrolase. An enzyme catalysing the reaction:

S-(2-hydroxyacyl)glutathione + H$_2$O =
glutathione + a 2-hydroxy-acid anion.

glyoxalate *a former name for* **glyoxylate**.

glyoxaline *an alternative name for* **imidazole**.

glyoxylate *or (formerly)* **glyoxalate** **1** the anion, OHC–COO$^-$, derived from glyoxylic acid. **2** any salt or ester of glyoxylic acid.

glyoxylate cycle *or* **glyoxylate pathway** a modification of the **tricarboxylic-acid cycle** occurring in some plants and microorganisms, in which isocitrate, instead of being dehydrogenated, is cleaved as described under **isocitrate lyase** to glyoxylate and succinate. This serves to generate glyoxylate from the acetyl moiety of acetyl-CoA. The glyoxylate can then react with another molecule of acetyl-CoA to form malate, a reaction catalysed by **malate synthase**. These two reactions taken together allow a four-carbon molecule, malate, and hence carbohydrate, to be formed from acetyl-CoA, which, in turn, may be formed from fatty acids. In some plants the enzymes of the glyoxylate pathway are present in **glyoxysomes**.

glyoxysome a cellular organelle, of density 1.25 gcm^{-3}, found in the organs of fatty seedlings where fat is being converted to carbohydrate. It contains the enzymes of the **glyoxylate cycle** and most of the particulate beta-oxidation activity.

glyphosate *N*-(phosphonomethyl)glycine; a potent, systemically acting, nonselective herbicide, present as its isopropylamine salt in some commercial weedkillers. It functions by inhibiting 5-*enol*pyruvylshikimate-3-phosphate (EPSP) synthase. *See also* **shikimate**. *Proprietary names* include Roundup and Tumbleweed.

glypiation the attachment or process of attachment of glycosylphosphatidylinositol to proteins. *See* **GPI anchor**.

glypican any of a family of heparan sulfate proteoglycans that are linked to the cell surface via a GPI anchor. Their core proteins (60–70 kDa) have attachment sites for heparan sulfate chains within the 50 C-terminal residues and, N-terminal to these sites, a conserved globular cysteine-rich domain. They are involved in development and morphogenesis. At least six members occur in mammals and two in *Drosophila*. Mutation in glypican-3 causes the X chromosome-linked Simpson–Golabi–Dahmel syndrome type 1, characterized by overgrowth, dysmorphism, and anomalies of the skeleton, heart, gastrointestinal tract, and central nervous system.

GM *or* **G-M** *abbr. for* Geiger–Müller (e.g. in **GM counter** for Geiger–Müller counter).

GM-CSF *abbr. for* granulocyte/macrophage colony stimulating factor. *See* **colony stimulating factor**.

GMD *(in clinical chemistry) abbr. for* **glutamate dehydrogenase (NAD(P)$^+$)**.

GMP *abbr. for* guanosine monophosphate i.e. guanosine phosphate.

GMP synthase EC 6.3.5.2; *recommended name*: GMP synthase (glutamine-hydrolysing); *systematic name*: xanthosine-5-phosphate:L-glutamine amido-ligase (AMP-forming); *other names*: GMP synthetase (glutamine-hydrolysing); glutamine amidotransferase. An enzyme that catalyses a reaction between ATP, xanthosine 5′-phosphate, L-glutamine, and H$_2$O to form AMP, pyrophosphate, guanosine monophosphate, and L-glutamate. It is inhibited by azaserine and 6-diazo-5-oxonorleucine, in common with other glutamine amidotransferases. It has four motifs and a region conserved in amidotransferases (one motif).

GMT *(in clinical chemistry) abbr. for* **glutamyltransferase**.

GNAT *abbr. for* GCN5-related N-acetyltransferase. The GNAT superfamily is one of five families of histone acetyltransferase, a class of enzyme that catalyses the transfer of an acetyl group from acetyl-CoA to the lysine *ε*-amino groups on the N-terminal tails of histones. GNATs share various functional domains (e.g., a variable-length N-terminal region, an acetyltransferase domain, a coactivator interaction region, and a C-terminal bromodomain) and are involved in transcription and DNA repair, and hence play important roles in the regulation of cell growth and development.

gnotobiotic describing an organism, especially a higher animal, or its environment, that has been deliberately rendered free of microorganisms and other organisms, including parasites, commensals, and symbionts, that it would normally harbour, or that harbours only a few, known, such organisms.

GnRH *abbr. for* gonadotropin-releasing hormone.

GNTR a transcriptional repressor for the gluconate (*gnt*) operon in *Bacillus subtilis*. The *gnt* operon is induced by gluconic acid *δ*-lactone; this was the first of a family of *gnt* repressors with **helix-turn-helix** motifs.

GNU *abbr. for* Gnu is Not Unix; a humorous recursive title for a very large open source software project that is an important source of academic software and the GNU Public Software License (known as 'copyleft', in contrast to copyright). This is widely used for free software distribution on terms that are well tested particularly under US jurisdiction.

GO *abbr. for* gene ontology.

goblin a protein of avian erythrocyte plasma membranes, M_r 260

000. It undergoes phosphorylation, and is highly similar to **ankyrin**, of which it is the avian equivalent.

GOD 1 *(sometimes) abbr. for* glucose oxidase. **2** *abbr. for* generation of diversity.

godnose a name proposed for ascorbic acid by A. Szent-Györgyi, as an alternative to **ignose**, before he knew its structure.

GOGAT *abbr. for* glutamine (amide):2-oxoglutarate aminotransferase (oxidoreductase NADP$^+$). It comprises two separate enzymes, named **glutamate synthase (ferredoxin)** and **glutamate–ammonia ligase**.

goitre *or (US)* **goiter** any swelling of the thyroid gland. Although common in areas where dietary iodine is insufficient, the condition is not related to thyroid state and patients with goitre may be euthyroid, hyperthyroid, or hypothyroid.

goitrogen any agent or factor causing goitre.

GOLD *abbr. for* genomes online database.

Gold book *informal name for* the IUPAC *Compendium of Chemical Terminology*, in recognition of the contribution of Victor Gold (1922–1985), who initiated work on the first edition.

Golgi apparatus *or* **Golgi body** *or* **Golgi complex** *or* **Golgi** a compound membranous cytoplasmic organelle of eukaryotic cells, consisting of flattened, ribosome-free vesicles arranged in a more or less regular stack. It differs from the endoplasmic reticulum in often having slightly thicker membranes, appearing in sections as a characteristic shallow semicircle so that the convex side (*cis* or entry face) abuts the endoplasmic reticulum, secretory granules emerging from the concave side (*trans* or exit face). In vertebrate cells there is usually one such organelle, while in invertebrates and plants, where they are known usually as **dictyosomes**, there may be several scattered in the cytoplasm. The Golgi apparatus processes proteins produced on the ribosomes of the rough endoplasmic reticulum; such processing includes modification of the core oligosaccharides of glycoproteins, and the sorting and packaging of proteins for transport to a variety of cellular locations, e.g. to storage granules, lysosomes, or secretory vesicles. The Golgi is a major site of synthesis of polysaccharides, including the **pectin** and hemicellulose of the plant cell wall and most of the glycosaminoglycans of the extracellular matrix in animals. Three different regions are recognized in terms of structure and function: *cis*, in the vicinity of the *cis* face, *trans*, in the vicinity of the *trans* face, and *medial*, lying between the *cis* and *trans* regions. While the **luminal proteins** of the endoplasmic reticulum leave it together with the proteins to be secreted, they are retrieved from the *cis* network and returned to the endoplasmic reticulum. Thus transport occurs in both directions. **Brefeldin A** blocks protein secretion through the Golgi but does not appear to block the return pathway. **Galactosyltransferase** is a marker enzyme for the *trans* membranes while ***N*-acetylglucosaminyltransferase** III serves this role for the medial membranes. [After Camillo Golgi (1843–1926), Italian anatomist, cytologist, neurologist, and pathologist, who, in 1898, was the first to describe it.]

Golgi mannosidase EC 3.2.1.114; *recommended name*: manno syl-oligosaccharide 1,3-1,6-α-mannosidase; *systematic name*: 1,3-(1,6-)mannosyl-oligosaccharide α-D-mannohydrolase; *other name*: mannosidase II. An enzyme that catalyses the hydrolysis of the terminal 1,3- and 1,6-linked α-D-mannose residues in the mannosyl-oligosaccharide Man$_5$GlcNAc$_3$. It is a type II membrane protein, and a glycosyl hydrolase enzyme in all tissues, mostly in adrenal and thymus. It belongs to a family of glycosyl hydrolases.

golgin any protein from the Golgi apparatus that is identified as an antigen in autoimmune conditions. The normal function of golgins may be to maintain the structure of the apparatus or to participate in membrane trafficking. *See* **giantin**.

golgiosome *an alternative name for* **dictyosome**.

GoLoco motif a 20-residue protein sequence in some proteins that regulate G-protein signalling via $G_{\alpha 0}$ and $G_{\alpha i}$. It is present in two proteins required for asymmetric spindle positioning in *Caenorhabditis elegans* embryos.

gonad any animal organ that produces gametes. In some species the gonads also produce hormones. —**gonadal** *adj.*

gonadoliberin *recommended name for* **gonadotropin-releasing hormone**.

gonadotropic hormone *or* **gonadotrophic hormone** *a former name for* **gonadotropin**.

gonadotropin *or (formerly)* **gonadotrophin** *or* **gonadotropic hormone** *or* **gonadotrophic hormone 1** any mammalian glycoprotein hormone that stimulates gonadal function. Strictly, gonadotropins comprise the adenohypophyseal hormones **follicle-stimulating hormone** (FSH) and **luteinizing** hormone (LH) together with the placental hormone **choriogonadotropin**, but the term is often extended to include also the adenohypophyseal hormone **prolactin** (which is not a glycoprotein but has gonadotropic activity). **2** any single substance having the combined activities of FSH and LH, such as choriogonadotropin or the gonadotropic hormones of cold-blooded vertebrates. **3** any impure hormonal preparation displaying the separate activities of FSH and LH, such as (human) menopausal gonadotropin (i.e. urogonadotropin) and **pregnant mare's serum gonadotropin**. —**gonadotropic** *adj.*

gonadotropin-releasing factor *abbr.*: GnRF; *another name for* **gonadotropin-releasing hormone**.

gonadotropin-releasing hormone (*abbr.*: GnRH) *or* **gonadoliberin** (recommended name) *or* **luteinizing hormone/follicle-stimulating hormone releasing factor** (*abbr.*: LH/FSH-RF) a family of decapeptide amides containing at least seven members and present in many vertebrate species from jawless fish (lamprey) to higher mammals. The structure is highly conserved; the sequence Glp-His-Trp-Ser-Tyr-Gly-Leu-Arg-Pro-Gly-NH$_2$ is common to all mammals; among other species, position 8 is most variable, positions 1, 2, 4, 9, and 10 being invariant. In mammals it is released by the hypothalamus, where it localizes with galanin, into the hypophyseal portal circulation in response to neural and/or chemical stimuli, and causes the release of FSH and LH by the anterior pituitary. It is also expressed in the placenta, and may act as a neurotransmitter, neuromodulator, or local hormone. It is derived from a larger precursor. For example, the rat precursor protein consists of 93 amino acids; residues 24–33 form GnRH and residues 37–92 form a peptide (GnRH-associated peptide, *abbr.*: GAP) that is poorly conserved and of unclear function. *See* **KAL**.

gonadotropin-releasing hormone receptor *abbr.*: GnRHR; any of a family of G-protein-associated membrane receptors that bind gonadotropin-releasing hormone (GnRH) and stimulate the phosphatidylinositol Ca^{2+} second messenger system. They are present in pituitary, ovary, testis, breast, and prostate.

gonane the parent 17-carbon tetracyclic hydrocarbon of steroids and bile acids.

gondoic acid *see* **eicosenoic acid**.

gonosome any motile animal germ cell, e.g. a spermatozoon.

Good buffer substance *or* **Good's buffer (substance)** any member of a collection of **zwitterionic buffer** substances selected or devised for suitability in experimental biological systems according to a number of predetermined criteria. These include: ease of preparation and purification; high solubility in water; low temperature coefficient of pK_a; and high transparency to light or ultraviolet light of wavelengths greater than 230 nm. The original lists included substances having the following trivial names (pK_a values at 20°C are in parentheses): **Mes** (6.15), **Ada** (6.6), **Pipes** (6.8), **Aces** (6.9), **Bes** (7.15), **Mops** (7.2), **Tes** (7.5), **Hepes** (7.55), **Hepps** (8.0), **Tricine** (8.15), **Bicine** (8.35), and **Taps** (8.4); **Ches** (9.3 at 25°C) and **Caps** (10.4) have similar properties. [After Norman Everett Good (1917–), US plant pathologist.]

gossypol a pigment found in cottonseed and containing two naphthalene rings with multiple –OH and other groups. It has antispermatogenic activity, and has been used (in China) as a male contraceptive. It is a potent inhibitor of contractions of strips of guinea-pig lung induced by platelet-activating factor or leukotriene, and it inhibits 5- and 12-lipoxygenase.

GOT *(in clinical chemistry) abbr. for* glutamate-oxaloacetate transaminase (AST preferred). *See* **transaminase**.

Goto-Kakizaki rat a strain of laboratory rats that have an inherited predisposition to develop diabetes. [Named after Y Goto and M Kakizaki, Tohoku University, Japan.]

gout a condition characterized by inflammation of the joints and cartilage due to hyperuricemia and consequent deposition of monosodium urate crystals in the joints, often within polymorphonuclear leukocytes. The hyperuricemia results from overproduction of uric acid, which may be due to elevated activity of ATP phosphoribosyltransferase (PRPP synthetase; EC 2.4.2.17), an abnormal **amidophosphoribosyltransferase**, or deficiency of hypoxanthine phosphoribosyltransferase (EC 2.4.2.8). **Allopurinol** is useful in treatment.

gp *abbr. for* glycoprotein used in conjunction with the relative molecular mass (e.g. gp115).

gp32 an envelope glycoprotein from HIV-related viruses, including **SIV** types. *See* **HIV protein**.

gp96 *abbr. for* glycoprotein of 96 kDa; *other name*: glucose-regulated protein of 94 kDa (*abbr*.: Grp94); an abundant molecular chaperone glycoprotein endoplasmic reticulum, and an orthologue of heat shock protein 90 (Hsp90).

G1P *or* **G-1-P** *abbr. for* glucose 1-phosphate.

G6P *or* **G-6-P** *abbr. for* glucose 6-phosphate.

G-patch a conserved protein sequence of ≈48 residues that contains six highly conserved glycine residues. It is present in some eukaryotic RNA-processing proteins and certain retroviral polyproteins. It usually occurs singly, and is often associated with other RNA-binding sequences.

GPCR *abbr. for* G-protein-coupled receptor.

GPD *(in clinical chemistry) abbr. for* glucose-6-phosphate dehydrogenase.

G_0 phase G-'zero' phase; a state of withdrawal from the eukaryotic **cell-division cycle**. It occurs if no stimulus for cell division occurs during G_1 phase, leaving the cell in a quiescent G_1 phase. It is often seen in differentiated cells.

G_1 phase Gap 1 phase; the phase of the eukaryotic **cell-division cycle** between the end of **cytokinesis** and the start of DNA synthesis, i.e. the gap between M phase and S phase.

G_2 phase Gap 2 phase; the phase of the eukaryotic **cell-division cycle**, between the end of DNA synthesis and the beginning of mitosis, i.e. the gap between S phase and M phase.

GPI *(in clinical chemistry) abbr. for* glucose-6-phosphate isomerase.

GPI anchor *abbr. for* glycosylphosphatidylinositol anchor; a molecular mechanism for attaching a membrane protein to the lipid bilayer of a cell membrane. Structurally it consists of a molecule of phosphatidylinositol (*abbr*.: PI) to which is linked, via the C-6 hydroxyl of the inositol, a carbohydrate chain. This chain is in turn linked to the protein through an ethanolamine phosphate moiety, the amino group of which is in amide linkage with the C-terminal carboxyl of the protein chain, the phosphate group being esterified to the C-6 hydroxyl of the terminal mannose of the core carbohydrate chain. The carbohydrate chain varies in composition between species, but invariably contains a core tetrasaccharide, the first component of which is a glucosamine residue in glycosidic linkage with the inositol C-6 hydroxyl. The tetrasaccharide has the structure Man(α1-2)Man(α1-6)Man(α1-4)GlcNH_2. Variation frequently occurs in the presence of additional α-mannose residues on the anchors of *Trypanosoma cruzi*, yeast, slime mould, and mammalian proteins. Anchors of *Trypanosoma brucei* have more elaborate carbohydrate side-chains containing galactose, glucosamine, and sialic-acid residues. In the case of metazoan eukaryotes, additional ethanolamine phosphate substituents may occur on mannose residues, and the inositol is often palmitoylated. Biosynthesis begins with attachment of the glucosamine moiety to phosphatidylinositol, followed by sequential addition of other sugars; the GPI moiety is attached to protein during processing in the endoplasmic reticulum, the signal being a hydrophobic sequence at the C terminus, which is removed during the attachment process. GPI-anchored proteins are released from membranes by PI-specific phospholipases. While the general function of the GPI anchor is to anchor the protein to the membrane, wider functions may include: location of the protein at specific sites, particularly the apical membrane of polarized epithelial cells; promotion of sequestration into membrane microdomains, these proteins being excluded from clathrin-associated regions but found in **caveolae**; anchoring of proteins of the glycocalyx, and cell signalling and cell recognition proteins. In addition to protein-linked GPIs, *Leishmania* spp. also synthesize two classes of free GPIs, the polydisperse **lipophosphoglycans** (LPGs) and the low molecular mass **glycoinositolphospholipids** (GIPLs). LPGs are restricted in occurrence (e.g. promastigote stage) but GIPLs are relatively abundant on the cell surface of promastigote and amastigote stages. GIPLs are also found on the surface of many other trypanosomatid parasites, e.g. *T. cruzi*, *Leptomonas*, *Herpetomonas*, and *Phytomonas*.

gp22-phox *see* **phagocyte NADPH oxidase**.

gp91-phox *see* **phagocyte NADPH oxidase**.

gp 43 processing protease *see* **oviductin**.

G protein guanine nucleotide binding protein; any heterotrimeric GTP-binding and hydrolysing protein belonging to a superfamily of GTPases that includes the monomeric proteins EF-Tu (*see* **EF-T**) and p21^{ras} (*see* **RAS**). G-proteins participate in activation or inhibition of **adenylate cyclase** and other **second messenger** systems, e.g. **phosphatidylinositol cycle**. They are associated with membrane receptors that contain seven transmembrane helices and bind hormones, growth factors, and cytokines. The system is unique to eukaryotes. G-proteins consist of three subunits; the α subunit (39–46 kDa) contains the guanine nucleotide binding site and possesses GTPase activity; the β (37 kDa) and γ (8 kDa) subunits are tightly associated and function as a βgamma; heterodimer. There are 23 types (including some splicing isoforms) of α subunits, 6 of β, and 11 of γ. The classes of G-protein and subunits are subscripted: thus the α subunit of G-protein S (which activates **adenylate cyclase**) is $G_{s\alpha}$; other G-proteins include G_i, which differs from G_S structurally (different type of α subunit) and inhibits **adenylate cyclase**; G_o, a G-protein detected by cDNA probes, of wide tissue distribution in mammals but of unclear role; G_p, a G-protein that activates phospholipase C (*see* **phospholipase**), release of Ca^{2+} and activation via **calmodulin** and **protein kinase C** (*see also* **phosphatidylinositol cycle**). Binding of $G_{\alpha\beta\gamma}$ to liganded receptor occurs when GDP bound to the G-protein (αβγ-GDP) exchanges for GTP, which causes the heterotrimer to dissociate into α-GTP and βgamma; units, either of which may interact with an effector. The GTPase activity of α yields α-GDP, which inactivates it. α-GDP has a high affinity for βgamma; thus reforming αβγ-GDP, which becomes available for association with an activated receptor. G_T, *see* **transducin**. In some tissues heterotrimeric G-proteins may be present in tight complexes that include: membrane receptor, adenylate cyclase, cAMP-dependent protein kinase, calcium channel, and a phosphoprotein phosphatase.

G protein-coupled receptor (*abbr*.: GPCR) *or* **G protein-associated receptor** *or* **G protein-linked receptor** member of a diverse family of cell-surface proteins that has adapted a common heptahelical framework to mediate a range of physiological processes (e.g., vision, olfaction, chemotaxis). Their functional diversity is achieved via interactions with a variety of ligands (e.g., peptides, glycoproteins, small molecule messenger molecules, vitamin derivatives), the effects of which stimulate a range of intracellular pathways through coupling to different G proteins. GPCRs are medically very important – they are involved in several major pathophysiological conditions (e.g., cardiovascular diesase, cancer, obesity), and are the targets of the majority of prescription drugs. *See* **G protein**.

gpt *symbol for* a prokaryotic gene for xanthine–guanine phosphoribosyltransferase. It is used as a dominant selectable marker in transfection of mammalian cells with exogenous DNA. Its expression enables mammalian cells to grow in the presence of **mycophenolic acid** in a medium supplemented with xanthine.

GPT *(in clinical chemistry) abbr. for* glutamate–pyruvate transaminase (EC 2.6.1.2) (ALT preferred).

G-quartet *or* **G-tetrad** a cyclic H-bonded array of guanines that can occur in both RNA and DNA to form a quadruple helix structure. Sequences that form such structures are found in telomeric sites, the switch regions of immunoglobulin heavy-chain genes, and elsewhere. *See* **KEM1**.

Gra *symbol for* a residue of **glyceraldehyde**.

Graafian follicle a spherical vesicle occurring in the mature mammalian ovary and in which the ovum develops. When the ovum matures it is discharged after rupture of the follicle, which is then transformed into a **corpus luteum**. [After Reijnier (Regnier) de Graaf (1641–73), Dutch physician and anatomist.]

grade 1 a degree or position in a scale, as of quality, size, etc., e.g.

analytical grade, commercial grade. **2** a unit of angle equal to one-hundredth of a right angle, i.e. 0.9°.

gradient the change in the value of a specified (chemical or physical) property or value per unit distance in a specified direction.

gradient elution a chromatographic elution procedure in which the concentration of a component of the eluent is increased continuously. The gradient may be linear, concave – i.e. increasing slowly at first and more rapidly as elution proceeds – or convex – i.e. increasing rapidly at first and more slowly as elution proceeds. More complex or discontinuous (stepped) elution gradients are sometimes used.

gradient former *or* **gradient mixer** any device for producing solutions of varying, but defined, composition containing one or more components.

gradient gel electrophoresis *or* **gradient acrylamide gel electrophoresis** *or* **polyacrylamide gradient gel electrophoresis** (*abbr*.: PAGE) a type of **zone electrophoresis** in which the supporting medium is a pore-gradient gel, i.e. one where an increasing concentration of polyacrylamide in the direction of electrophoretic mobility decreases the sizes of the pores in the gel in that direction to the point where molecules of more than a certain size are prevented from moving further in the electric field. The concentration gradient may be either discontinuous, i.e. stepped, or continuous. Advantages of the technique over electrophoresis in uniform gels (*see* **gel electrophoresis**) are sharper zones and an ability to resolve, on a single gel, mixtures of macromolecules of a wider range of sizes.

gradient layer *or* **gradient packing** a chromatographic layer, or column packing, incorporating a continuous change of some property that affects separations, e.g. a pH gradient or a pore gradient.

graft 1 any part of an organism, animal or plant, that is inserted into and unites with a larger part of another or the same organism. **2** to transplant (tissue) to another organism or to another site on the same organism.

graft versus host disease a condition where immunocompetent donor cells recognize and react against the recipient's tissues, because the recipient is immunosuppressed or cannot recognize the different genetic constitution of the donor cells.

Graham's law of diffusion a law stating that at equal temperatures and pressures the rates of diffusion of gases are inversely proportional to the square roots of their densities and hence to the square roots of their relative molecular masses (M_rs). Thus for two gases A and B,

$$J_A/J_B = \bar{v}_A/\bar{v}_B = M_{rB}{}^{1/2}/M_{rA}{}^{1/2},$$

where J_A and J_B, $\bar{v}_A$ and $\bar{v}_B$, and M_{rA} and M_{rB} are the fluxes, mean velocities, and relative molecular masses of A and B, respectively. [After Thomas Graham (1805–69), Scottish chemist.]

grain 1 any small, hard particle, e.g. a grain of sand. **2** any simple single-seeded indehiscent fruit in which the seed wall fuses with the carpel wall during development. Technically called a **caryopsis**, it is typical of the cereals and other grasses. **3** *(in photography)* any of the many particles of silver halide in a photographic emulsion. The resolution possible in the image is inversely proportional to the grain size in the emulsion. **4** any of the dried insect bodies present in dyes such as cochineal.

gram *symbol*: g; a unit of mass equal to a thousandth part of the **kilogram** in both the Système International (SI) and the metric system (cgs or mks) of units.

+gram *comb. form* indicating a drawing, something written or recorded; the record produced by an instrument, e.g. spectrogram; the visible result of a procedure, e.g. autoradiogram, chromatogram.

gram-atom *or* **gram-atomic weight** *abbr*.: g-atom; the atomic weight of an element expressed in grams; it has now been replaced by amount of substance, measured in **moles**.

gram-equivalent *or (formerly)* **gram-equivalent weight** *abbr*.: g-equiv; an **equivalent** (def. 3) expressed in grams.

gramicidin any of a group of linear polypeptide antibiotics that are active against Gram-positive microorganisms and are isolated from cultures of *Bacillus brevis*. The commercial material is a mixture of gramicidins A, B, C, and D, all of which consist of chains of 15 amino-acid residues in a pattern of alternating D- and L-forms; all have a formyl group at the N terminus and an ethanolamine residue at the C terminus. Gramicidins increase the permeability of biological membranes to protons and alkali-metal cations by forming transient dimeric ionophoric channels through the membrane. Gramicidins are classified in the TC syctem under number 1.D.1. *See also* **gramicidin S**.

gramicidin S a homodetic cyclic decapeptide antibiotic, *cyclo*(-Val-Orn-Leu-DPhe-Pro-Val-Orn-Leu-DPhe-Pro-), produced by a strain of *Bacillus brevis* and active against Gram-positive bacteria. Gramicidin S is more closely related to **tyrocidins** in its biological and chemical properties than to true **gramicidins**. Its biosynthesis occurs by a mechanism that is not dependent on the presence of ribosomes or mRNA. It was the first peptide antibiotic to be chemically synthesized, and is so named because it was first isolated in Soviet Russia, where it was widely used.

gram-molecule *or* **gram-molecular weight** *symbol*: g-mol; the molecular weight of a compound (or element) expressed in grams; it has now been replaced by the **mole**.

Gram-negative describing a bacterial cell that, during **Gram staining**, does not retain the basic dye in its cell wall. The walls of Gram-negative organisms are thin, about 10 nm across, but complex, having a lipopolysaccharide layer outside the peptidoglycan layer; they are also resistant to digestion by lysozyme. *Compare* **Gram-positive**.

Gram-positive describing a bacterial cell that, during **Gram staining**, retains the basic dye in its cell wall. The walls of Gram-positive organisms are relatively thick, 15–80 nm across, and consist of a network of peptidoglycan; they are readily digested by lysozyme. *Compare* **Gram-negative**.

Gram staining *or* **Gram stain** a staining procedure used for bacteria in which the cells are first heat-fixed and stained with a basic dye, e.g. Crystal Violet, then treated with I_2–KI solution to fix the stain, washed with ethanol or acetone, and finally counterstained with another dye, e.g. carbolfuchsin or safranin. Cells that retain the basic dye after this procedure are called **Gram-positive**; those that do not are called **Gram-negative**. [After Hans Christian Joachim Gram (1853–1938), Danish physician and bacteriologist, who described the method in 1884.]

grancalcin a Ca^{2+}-binding protein containing four **EF hands**, and abundant in neutrophils and monocytes. It shares strong similarity with **sorcin**. It is a homodimer.

β granin *see* **chromogranin**.

granular *or* **granulose** *or* **granulate** being composed of, or having the character of small particles or **grains** (def. 1).

granular endoplasmic reticulum *or* **rough endoplasmic reticulum** *see* **endoplasmic reticulum**.

granulate 1 to make (something) into **grains** (def. 1). **2** (of a wound, ulcer, etc.) to form **granulation tissue**. **3** *another word for* **granular**.

granulation 1 the act or process of subdividing a solid into small, usually rounded **grains** (def. 1). **2** the formation of one or more small, rounded lumps (grains (def. 1)) in a tissue. **3** the development of **granulation tissue**.

granulation tissue the mass of young connective tissue and blood vessels formed on the surface of a wound or ulcer in the early stages of healing.

granule any small **grain** (def. 1), especially any small intracellular particle containing stored material that can be seen by (electron) microscopy, e.g. insulin-containing β granules in the B cells of the islets of Langerhans, starch granules in potato tubers.

granulocyte a category of white blood cells distinguished by the presence of conspicuous cytoplasmic granules. Granulocytes include **neutrophils**, **basophils**, and **eosinophils**.

granulocyte-colony stimulating factor *see* **colony stimulating factor**.

granulose 1 *another word for* **granular**. **2** *an obsolete name for* **starch** or amylose.

granum (*pl.* **grana**) a stack of disclike **thylakoids** resembling a pile of coins. Grana occur in **chloroplasts**, especially in higher plants.

granzyme any of three related serine proteases (EC 3.4.21) that occur (with perforin) in cytoplasmic vesicles of killer T-lymphocytes and induce death in target cells.

granzyme A enzyme of sub-subclass EC 3.4.21; *other names*: cytotoxic T-lymphocyte protease 1; Hanukkah factor (HF); granzyme

1; CTL tryptase; fragmentin 1; trypsin-like serine protease. An enzyme necessary for target-cell lysis in cell-mediated immune responses; it cleaves on the carbonyl side of Lys or Arg. It occurs in cytoplasmic granules, and may be involved in **apoptosis**. The molecule is a disulfide-linked homodimer.

grape sugar *a former name for* D-glucose. *See* **glucose**.

graph 1 a diagram showing the relation between two variable quantities, or the relation between a mathematical function and different values of one of the variables in the function, usually plotted between axes at right angles to each other. **2** to plot or draw a graph.

+graph *comb. form* **1** denoting (something) drawn, recorded, or written (in the way specified), e.g. autoradiograph, photograph. **2** denoting an instrument or device that draws or records (observations), e.g. spectrograph. **3** denoting the act or process of producing such a drawing or record. *Compare* **+gram**. —**+graphic** *or* **+graphical** *adj. comb. form.*

graphics *(functioning as sing.)* **1** the use of diagrams in calculation. **2** the production of diagrams, representations of molecular structures, etc., often by computer.

+graphy *comb. form* denoting a method, process, or technique that produces a drawing or record, e.g. chromatography. *See* **+graph**.

grating *see* **diffraction grating**.

gratuitous inducer any compound that causes the induction of gene expression and is not itself metabolized by the enzymes so induced. A well-known example is the induction of the *lac* operon by isopropylthiogalactoside (IPTG).

Graves' disease *or* **Basedow's disease** a disease characterized by diffuse goitre, thyrotoxicosis, and exophthalmia. It is an autoimmune condition associated with serum antibodies against the thyrotropin receptor. [After Robert James Graves (1796–1853), Irish physician.]

Graves' disease carrier protein see **GDC**.

gravimetric analysis quantitative analysis of the chemical composition of substances or materials based on the separation of each component of interest and weighing either the purified compound or a derivative of it.

gravimetry measurement by weighing. —**gravimetric** *or* **gravimetrical** *adj.*

gravitation the attractive force that bodies exert on one another as a result of their mass; any process or result caused by such an attractive force. —**gravitational** *adj.*

gravitational constant *symbol*: G; the proportionality constant relating the attractive force, F, between two bodies of mass m_1 and m_2, and the distance between them, s, in Newton's law of gravitation:

$$G = Fs/m_1m_2 = 6.67259(85) \times 10^{-11}\ \mathrm{m^3kg^{-1}s^{-2}}.$$

gravitational field any **field** (def. 1) associated with a mass by which a force is exerted on a second mass placed in this field.

gravitational interaction any interaction between bodies or particles that results from their masses.

gravitational mass *see* **mass**.

gravity 1 the attractive force that moves or tends to move bodies towards the centre of any celestial body such as the earth or the moon. **2** the attribute of having weight. **3 specific gravity**.

gray *symbol*: Gy; the SI derived unit of **absorbed dose** of radiation, equal to one joule per kilogram of living tissue;

$$1\ \mathrm{Gy} = 1\ \mathrm{Jkg^{-1}} = 1\ \mathrm{m^2s^{-2}}.$$

Compare **sievert**. *See also* **rad**. [After Louis Harold Gray (1905–65), British physicist and radiobiologist.]

Grb2 growth factor receptor-bound protein 2; *also called* **Ash protein**; a cytosolic adaptor protein, related to sem-5 (*see* ***sem-5***), that participates in downstream signalling after activation of epidermal growth factor and platelet-derived growth factor receptors; it can also be recruited by G-protein-coupled receptors through tyrosine phosphorylation of Shc (*see* **SHC**). Grb2 binds to activated Shc and the complex then recruits Sos (*see* ***sos***). The Shc–Grb2–Sos complex binds to the plasma membrane where Sos catalyses **Ras** guanine nucleotide exchange, leading to MAP kinase activation. Grb-10 is activated by RET.

GRE *abbr. for* glucocorticoid response element.

green fluorescent protein *abbr.*: GFP; a protein isolated from the jellyfish, *Aequorea victoria,* that fluoresces when exposed to excitation light (there are several spectral variants, including yellow, cyan, blue, and red). GFP has important applications in research: the gene can be expressed in other living organisms, making it possible to create gene fusions and hence to visualize the localization of specific gene products inside living cells. GFP comprises 238 amino acids arranged in a helical basket motif, within which three amino acids form an annular structure that mediates its fluorescent properties. *See also* **enhanced green fluorescent protein**.

GRF *abbr. (sometimes) for* growth hormone releasing factor (i.e. **GHRH**).

Gri *symbol for* glyceric acid *or* glycerate.

grid 1 a framework made up of fine wires arranged in two sets at right angles to each other, especially a device for supporting the specimen in an electron microscope. **2** an electrode controlling the current flowing through a thermionic valve.

Grid the basis for the rapidly developing field of grid computing. It enables scalable virtual organizations (**VO**s), has some parallels with the World Wide Web, but differs in that the members of the VO can not only access data but also run applications on computers in the grid. The Grid has its own **protocol**s and **API**s and has enormous implications for bioinformatics.

Grim a protein of *Drosophila* that functions, like mammalian **Diablo**, in promoting apoptosis. It binds **IAP**, releasing any associated caspase, and thereby is essential for apoptosis.

griseofulvin [2*S*]-*trans*-7-chloro-2′,4,6-trimethoxy-6′-methylspiro[benzofuran-2(3*H*),1′-(2)cyclohexene]-3,4′-dione; a chlorine-containing **polyketide** metabolite of *Penicillium griseofulvum* and *P. janczewskii*. It has antifungal properties and is used therapeutically, e.g. for treatment of ringworm. It inhibits spindle formation in mitosis, microtubule function, and possibly nucleic-acid synthesis.



GRK *abbr. for* G-protein coupled receptor kinase; a widely expressed protein kinase that can phosphorylate many G-protein-coupled receptors. There are three isoforms: GRK2 and GRK3 contain an N-terminal RGS domain (*see* **RGS protein**), a central protein kinase domain, and a C-terminal pleckstrin homology (PH) domain. GRK1 lacks the PH domain.

Grn *symbol for* glycerone.

gRNA *abbr. for* guide RNA; small RNA molecules, 60–80 nucleotides long, that may be involved in editing of RNA by supplying information concerning nucleotide deletion or addition. *See also* **editosome**.

gro the symbol for any of a group of related genes found in bacteria (especially *Escherichia coli*), mutations in which affect the growth of phages.

Gro *symbol for* glycerol.

groEL symbol for any of a family of bacterial genes encoding **chaperonins**. Eukaryotic homologs are the hsp60 and Cpn60 proteins respectively of mitochondria and chloroplasts. Example of a *groEL* protein from *Escherichia coli*: oligomer of 14 subunits composed of two stacked rings of seven subunits; it has ATPase activity.

groES symbol for any of a family of bacterial genes encoding co**chaperonins** that functions with *groEL*. Eukaryotic homologs are the hsp 10 and Cpn 10 proteins respectively of mitochondria and chloroplasts, that cycle on and off the hsp60 or Cpn60 cylinder in response to its ATPase activity. Example of a *groES* protein product from *Escherichia coli*: seven subunits arranged in a ring. *See* **chaperonin**.

Grotthus and Draper law a law stating that only those radiations absorbed by a system are effective in producing chemical change in the system.

groundplasm *or* **cytoplasmic matrix** the sub-electron-microscopic material of the **cytoplasm**, excluding the cell organelles, cell particles, and other microscopically resolvable structures. It contains the cytoplasmic enzymes and metabolites together with components of the **cytoskeleton**.

ground state the state of lowest energy of any system.

ground substance *an alternative name for* the **matrix** (def. 2) of connective tissue.

ground tissue *a collective term for* plant tissue other than the epidermis or peridermis and vascular tissue.

group *(in chemistry) or* (*formerly*) **radical** **1** any defined continuously linked collection of atoms within a molecular entity. In organic chemical nomenclature the meaning within this general sense is restricted to any covalently bonded collection of atoms that behaves as a unit in chemical reactions; **functional group**, **substituent group**. **2** any of the columns of chemical elements in the **periodic table**. **3** a **blood group**.

group p*K* the **p*K*** of a specific group in a molecule with two or more acid groups. In general the term applies only to a particular ionic form of the molecule, because the p*K* of a group changes when any other group in the molecule changes its ionization state, and thus changes as the substance is titrated. *Compare* **molecular p*K*, titration p*K***.

group potential the tendency of a **group** (def. 1) to escape from a molecular entity.

group-transfer potential the Gibbs energy change (free energy change, ΔG) occurring when a **group** (def. 1) is transferred from a donor compound to the nucleophile water, i.e. when the group is removed by hydrolysis of the donor. It reflects the thermodynamic tendency for the group to be transferred.

group-transfer reaction any chemical reaction in which a **group** (def. 1) is transferred from a donor compound to an acceptor compound. Such reactions may be catalysed by a **transferase** enzyme of EC class 2.

group translocation any process in which a substance to be transported across a biological membrane undergoes covalent modification concomitant with crossing the membrane. The best-known example is the group of bacterial phosphotransferases, which catalyse phosphorylation of some mono- and disaccharides, and of sugar alcohols during their import into cells.

growth curve the change, as a function of time, in the number of cells of a growing culture or in some measure of the size of an organism.

growth factor **1** any specific substance that must be present in a culture medium for multiplication of the cultured cells to take place. **2** a specific substance that is a necessary constituent of the diet for the normal growth of a particular animal, or is required in the soil for the normal growth of a particular plant.

growth factor receptor-bound protein 2 *see* **Grb2**.

growth hormone *another name for* **somatotropin**.

growth hormone inhibitory factor *abbr.*: GHIF *or* GIF; *a former name for* **somatostatin**.

growth hormone release-inhibiting hormone *abbr.*: GH-RIH; *a former name for* **somatostatin**.

growth hormone releasing factor *abbr.*: GHRF *or* GRF; *another name for* **GHRH**.

growth hormone releasing hormone *see* **GHRH**.

growth hormone-releasing peptide *abbr* .: GHRp; a synthetic hexapeptide that stimulates release of somatotropin by binding to a highly conserved G-protein-coupled receptor in the pituitary for which the physiological ligand is unidentified.

Grp94 *an alternative term for* **gp96**.

GRP *see* **Grb2**.

GRP 75 *see* **mortalin**.

GRS *(in clinical chemistry) abbr. for* β-glucuronidase.

Grunstein–Hogness procedure *an alternative name for* **colony hybridization**.

GSH *abbr. for* glutathione.

GSK-3 *abbr. for* **glycogen synthase kinase-3**.

GSS *abbr. for* genome survey sequence.

GSSG *abbr. for* oxidized glutathione (*see* **glutathione**).

GST *abbr. for* glutathione S-transferase (*see* **glutathione transferase**).

GST fusion protein any protein that has been genetically engineered to have glutathione-*S*-transferase (GST) fused at its N-terminal end. A range of **pGEX vectors** are designed to facilitate such expression in *E. coli*. The fusion protein can be purified by affinity chromatography on columns of immobilized glutathione.

GT *abbr. for* glycosyltransferase.

GT–AG rule a rule stating that in RNA there is a requirement for a GT at the 5′ side of a splice junction and an AG at the 3′side.

GTBP *abbr. for* G/T binding protein; a human homologue (1292 amino acids) of *E. coli* **MutS** protein that is essential for DNA G/T mismatch recognition and binding. It forms a heterodimer with MutS homologue 2 (hMSH2). Mutations in GTBP are present in many hereditary, and some sporadic, colorectal cancers.

GTD *(in clinical chemistry) abbr. for* glutathione reductase.

G-tetrad *an alternative name for* **G-quartet**.

GTF *abbr. for* glucose-tolerance factor.

GTP *abbr. for* guanosine triphosphate.

GTPase any enzymic activity that hydrolyses GTP to GDP and orthophosphate. It is associated with **G-proteins**, **EF-Ts**, and **HIV protein**.

GTP-binding protein any of various proteins that bind GTP as a regulatory molecule; this binding is frequently associated with a **GTPase** activity. GTP-binding proteins include elongation and initiation factors (e.g., **EF-Tu**), **G proteins**, G25K GTP- binding protein, **Ras proteins**, and yeast CDC42 (*see* **CDC markers**). Binding of GTP normally activates the protein, an effect that is reversed by hydrolysis of the GTP to GDP.

GTP[S] *or* **GTPγS** *abbr. for* guanosine 5′-γ-thiotriphosphate.

GTR1 a representative 12-transmembrane domain transport protein that effects the facilitated diffusion of glucose in certain mammalian tissues.

GTT *abbr. for* glucose tolerance test.

Gu *symbol for* guanidine.

Gua *symbol for* a residue of the purine base guanine (alternative to G).

GUA a codon in mRNA for L-valine.

guanidine *symbol*: Gu; the strongly basic substance, iminourea; aminomethanamidine; $(H_2N)_2C{=}NH$.

guanidinium the cation, $[C(NH_2)_3]^+$, derived from guanidine by uptake of a hydron.

guanidinium isothiocyanate a powerful **chaotrope** used as a protein denaturant in the extraction of RNA from biological materials. Both the guanidinium cation and the isothiocyanate anion are strong chaotropic agents.

guanidino the amidinoimino group, $-HN-C(=NH)-NH_2$, derived from guanidine.

guanidinoacetate *N*-methyltransferase EC 2.1.1.2; an enzyme of the pathway for *de novo* synthesis of **creatine**, by reaction of *S*-adenosyl-L-methionine with guanidinoacetate releasing *S*-adenosyl-L-homocysteine.

guanine *symbol*: G *or* Gua; 2-amino-6-hydroxypurine; 2-amino-1,7-dihydro-6*H*-purin-6-one; a purine that is one of the five main bases found in nucleic acids and a component of a number of phosphorylated guanosine derivatives whose metabolic or regulatory functions are important.



guanine nucleotide binding protein *see* **GTP-binding protein**.

guanine nucleotide releasing protein *abbr.*: GNRP; *or* **guanine nucleotide releasing factor**, *abbr.*: GRF; a protein that binds to a Ras protein (*see* **Ras family of proteins**) or Ras-related **GTP-binding protein**, and activates it by stimulating it to release its bound GDP and to bind GTP in its place. The C-terminal 310 amino acids share similarity with Cdc25 (*see* **cdc gene**) and Sos, the product of **sos**.

guanosine *symbol*: G *or* Guo; guanine riboside; 9-β-D-ribofuranosylguanine; a **nucleoside** with a wide species distribution.



guanosine

guanosine 2′,3′-(cyclic)phosphate *see* **guanosine phosphate**.

guanosine 3′,5′-(cyclic)phosphate *or* **guanosine 3′,5′-cyclophosphate** *see* **guanosine 3′,5′-phosphate**.



guanosine 5′-diphosphate *symbol*: Guo5′*PP or* ppG; *the recommended name for* guanosine diphosphate (*abbr.*: GDP), 5′-diphosphoguanosine, 5′-guanylyl phosphate, guanosine 5′-(trihydrogen diphosphate), a universally distributed nucleotide that occurs in both the free state and as a component of **guanosinediphosphosugars**. It is a metabolic precursor of guanosine 5′-triphosphate, GTP, and is a substrate, a product, or a regulatory agent in many metabolic systems.

guanosine 3′-diphosphate 5′-diphosphate *symbol.*: ppGpp; *see* ***relA***, ***spoT***.

guanosinediphosphomannose *or* **guanosine(5′)diphospho(1)-α-D-mannose** *symbol*: Guo*PP*Man; *the alternative recommended names for* guanosine diphosphate mannose (*abbr.*: GDPM *or* GDP-mannose); guanosine 5′-(α-D-mannopyranosyl diphosphate); α-D-mannopyranosyl 5′-guanylyl phosphate; the most important **guanosinediphosphosugar**. It is synthesized from α-D-mannose 1-phosphate and guanosine 5′-triphosphate by the action of **mannose-1-phosphate guanylyltransferase** (EC 2.7.7.13). It is an intermediate in the synthesis of mannose-containing homo- and heteroglycans in plants. In animal cells GDPmannose is an intermediate in the incorporation of residues of both mannose and fucose into *N*-linked oligosaccharides of glycoproteins, its conversion to GDP-L-fucose having first taken place in the case of fucose.

guanosinediphosphosugar *or* **guanosine diphosphate sugar** *abbr.* GDPsugar; any of several **nucleosidediphosphosugars** in which the distal phosphoric residue of guanosine 5′-diphosphate is in glycosidic linkage with a monosaccharide (or a derivative of a monosaccharide). Included are GDP-L-fucose, GDP-D-glucose, GDP-L-guluronic acid, GDP-D-mannose (*see* **guanosinediphosphomannose**), and GDP-D-mannuronic acid.

guanosine 5′-[β,γ-imido]triphosphate *symbol*: Guo-*PP*[NH]*P or* p[NH]ppG; *the recommended name for β,γ*-imidoguanosine 5′-triphosphate (*abbr.*: GTP[*β, γ*-NH]), 5′-guanylyl imidodiphosphate (*abbr.*: GMP-PNP), 5′-guanylyl iminodiphosphonate, guanosine $(5'\to O^3)$-1,2-*μ*-imidotriphosphate, a synthetic nonhydrolysable analogue of guanosine triphosphate, GTP, in which the oxy group between the latter's intermediate and terminal phosphorus atoms is replaced by an imido group. It stimulates G-proteins and systems activated thereby.



guanosine 5′-[β,γ-methylene]triphosphate *symbol*: Guo*PP*-[CH$_2$]*P or* p[CH$_2$]ppG; *the recommended name for β,γ*-methyleneguanosine 5′-triphosphate, (*abbr.*: GTP[*β,γ*-CH$_2$]), 5′-guanylyl methylenediphosphonate (*abbr.*: GMP-PCP), guanosine $(5'\to O^3)$-1,2-*μ*-methylenetriphosphate, a synthetic nonhydrolysable analogue of guanosine 5′-triphosphate, GTP, in which the oxy group between the latter's intermediate and terminal phosphorus atoms is replaced by a methylene group. It is an effective activator of ADP-ribosylation factor but not of G$_S$ (*see* **G-protein**).



guanosine monophosphate *abbr.*: GMP; *an alternative name for* any guanosine phosphate, but in particular for **guanosine 5′-phosphate**, especially when its distinction from guanosine (5′-)diphosphate and guanosine (5′-)triphosphate requires emphasis.

guanosine phosphate *symbol*: Guo*P*; guanosine monophosphate (*abbr.*: GMP); any phosphoric monoester or diester of guanosine. There are three monoesters – guanosine 2′-phosphate, guanosine 3′-phosphate, and **guanosine 5′-phosphate** – and two diesters – guanosine 2′,3′-phosphate and **guanosine 3′,5′-phosphate** – although guanosine 5′-phosphate, guanylic acid is the ester commonly denoted (the locant being omitted if no ambiguity may arise). Guanosine 2′,3′-phosphate (*symbol*: Guo-2′,3′-*P*), also named guanosine 2′,3′-(cyclic)phosphate *or* cyclic guanosine 2′,3′-monophosphate (*abbr.*: 2′,3′-cyclic GMP), is formed as an intermediate during the alkaline hydrolysis of ribonucleic acid. This diester then readily hydrolyses to a mixture of the two monoesters guanosine 2′-phosphate (*symbol*: Guo2′*P*), also named guanosine 2′-monophosphate (*abbr.*: 2′GMP) *or* 2′-guanylic acid *or* guanylic acid a, and guanosine 3′-phosphate (*symbol*: Guo3′*P*), also named guanosine 3′-monophosphate (*abbr.*: 3′GMP) *or* 3′-guanylic acid *or* guanylic acid b.

guanosine 2′-phosphate *see* **guanosine phosphate**.

guanosine 2′,3′-phosphate *see* **guanosine phosphate**.

guanosine 3′-phosphate *see* **guanosine phosphate**.

guanosine 3′,5′-phosphate *symbol*: Guo-3′,5′-*P*; *the recommended name for* cyclic guanosine 3′,5′-monophosphate (*abbr.*: 3′,5′-cyclic GMP *or* cyclic GMP *or* cGMP), guanosine 3′,5′-cyclophosphate, guanosine 3′,5′-(cyclic) phosphate, a monophosphoric diester of guanosine found in practically all mammalian tissues. It is a cyclic nucleotide similar in structure and the regulation of its metabolism to **adenosine 3′,5′-phosphate**, cyclic AMP, but the levels in tissues are commonly less than 5 percent of those of cyclic AMP. Also like cyclic AMP, it acts as a **second messenger** in many systems, and it activates a number of distinct cyclic-GMP-dependent protein kinases that share some of their properties with their cyclic AMP counterparts; in some instances it antagonizes the action of cyclic AMP. Cyclic GMP is produced by the action of **guanylate cyclase** on guanosine 5′-triphosphate, GTP, and it mediates signal transduction for systems that activate this enzyme.

guanosine 5′-phosphate *or* **5′-guanylic acid** *or* **5′-phosphoguanosine** *or* **5′-*O*-phosphonoguanosine** *symbol*: Guo5′*P*; *alternative recommended names for* guanosine 5′-monophosphate (*abbr.*: 5′GMP), guanosine 5′-(dihydrogen phosphate), guanine (mono)ribonucleotide. (The locant is commonly omitted if there is no ambiguity as to the position of phosphorylation.) It is biosynthesized from inosine 5′-phosphate, 5′-inosinic acid, via xanthosine 5′-phosphate and also from free guanine by the **salvage pathway**.

guanosine 5′-*β*-thiodiphosphate *symbol*: Guo5′*PP*[S] *or* [S]ppG; *the recommended name for* guanosine 5′-[*β*-thio]diphosphate (*abbr.*: GDP*β*S), guanosine 5′-(2-thiodiphosphate) (*abbr.*: GDP[S]), guanosine ($5'\to O^2$)-1-thiodiphosphate, a synthetic nonhydrolysable analogue of guanosine 5′-diphosphate, GDP, in which an oxygen atom of its terminal phosphoric residue is replaced by a sulfur atom. It is a competitive inhibitor of the activation of G-proteins by guanosine 5′-triphosphate and of the stimulation of adenylate cyclase by guanosine 5′-triphosphate and fluoride.



guanosine 5′-*γ*-thiotriphosphate *symbol*: Guo*PPP*[S] *or* [S]pppG; *the recommended name for* guanosine 5′-[*γ*-thio] triphosphate (*abbr.*: GTP-*γ*-S), guanosine 5′-(3-thiophosphate) (*abbr.*: GTP[S]), guanosine ($5'\to O^3$)-1-thiotriphosphate, a synthetic nonhydrolysable analogue of guanosine 5′-triphosphate, GTP, in which an oxygen atom of its terminal phosphoric residue is replaced by a sulfur atom. It is used in membrane studies to stimulate G-proteins and in studies of DNA synthesis.

guanosinetriphosphatase a GTP-hydrolyzing enzyme belonging to group EC 3.6.1 and involved in transduction of information (EC 3.6.1.46, EC 3.6.1.49), protein synthesis (EC 3.6.1.48), and movement of intracellular particles (EC 3.6.1.47, EC 3.6.1.50, EC 3.6.1.51).

guanosine 5′-triphosphate *symbol*: Guo5′*PPP or* pppG; *the recommended name for* guanosine triphosphate (*abbr.*: GTP), 5′-triphosphoguanosine, 5′-guanylyl diphosphate, guanosine 5′-(tetrahydrogen triphosphate), an important coenzyme and enzyme regulator present in all cells. It is formed from guanosine 5′-diphosphate by substrate-level phosphorylation or by transfer of the terminal phosphoric residue from **adenosine 5′-triphosphate** through the action of nucleoside-diphosphate kinase (EC 2.7.4.6). Reactions in which GTP participates are often driven in the direction leading to hydrolysis, the free energy change then being utilized for energy-requiring purposes, e.g. microtubule assembly or protein biosynthesis. GTP also participates in various synthetic reactions by the transfer of a phosphoric residue to other metabolites, e.g. to oxaloacetate to form phospho*enol*pyruvate in gluconeogenesis.



guanosine triphosphate cyclohydrolase EC 3.5.4.16; the first enzyme in the biosynthesis of tetrahydrobiopterin. It catalyses the reaction:

$$GTP + 2H_2O = 7,8\text{-dihydroneopterin trisphosphate} + HCOOH.$$

The enzyme, whose subunits each contain 250 amino acids and form a stack of two pentamers, occurs mainly in monoaminergic neurons, adrenal medulla, and liver. Deficiency is rare and results from numerous mutations associated with dopa-sensitive dystonia. *See* **biopterin**.

guanosyl any chemical group formed by the loss of a 2′-, a 3′-, or a 5′-hydroxyl group from the ribose moiety of guanosine. *Compare* **guanylyl**.

guanyl *misnomer for* **1 guanylyl**. **2 guanylate**.

guanylate **1** the mono- or the di-anion of **guanylic acid**. **2** any mixture of guanylic acid and its anions. **3** any salt or ester of guanylic acid.

guanylate cyclase EC 4.6.1.2; *systematic name*: GTP pyrophosphate-lyase (cyclizing); *other names*: guanylyl cyclase (not recommended but often used); guanyl cyclase (incorrect). An enzyme that catalyses the elimination of pyrophosphate from guanosine 5′-triphosphate, GTP, by formation of guanosine 3′,5′-phosphate, cyclic GMP. There are two types: (1) a heterodimer of α and β chains; and (2) a membrane-bound form, typical of some receptors. A retina-specific receptor guanylate cyclase (retGC-1) is present in the outer segment of cone cells and is activated by retina-specific activator proteins. Many mutations in the gene for retGC-1 at 17p13.1 result in Leber's congenital amaurosis (a form of blindness). *See* **GCAP**.

guanyl cyclase *incorrect name for* **guanylate cyclase**.

guanylic acid *the trivial name for* any phosphoric monoester of guanosine. The position of the phosphoric residue on the ribose moiety of a given ester may be specified by a prefixed locant. *see* **guanosine phosphate**. However, 5′-guanylic acid is the ester commonly denoted, its locant usually being omitted if no ambiguity may arise. 5′-Guanylic acid is also an alternative recommended name for **guanosine 5′-phosphate**.

guanylin a pentadecapeptide paracrine hormone that contains four disulfide bonds and represents the C-terminal segment of preproguanylin (115 amino acids). It is secreted by enterochromaffin cells along the intestinal tract, secretory cells in bronchioles, and probably the kidney. Its receptor is a membrane receptor guanylate cyclase that also binds the heat-stable enterotoxin of several Gram-negative bacteria. It acts to increase secretion of NaCl.

guanylyl the guanosine[mono]phospho group; the acyl group derived from **guanylic acid**.

guanylylation the process of introducing guanylyl groups into a substance.

guanylyl cyclase *see* **guanylate cyclase**.

guaran a mucilaginous **galactomannan** of ≈220 kDa that serves as a storage polysaccharide in the seeds of guar and is the prime constituent of **guar gum**. It consists of long chains of (1→4)-linked *β*-D-mannopyranose residues, to every alternate one of which a single *α*-D-galactopyranose residue is attached in (1→6)-linkage.

guard cell either of a pair of crescent-shaped cells that surround a **stoma** in plants.

guard column a small column fitted in front of the main column as a device to prolong the life of columns in high-performance liquid chromatography by removing from the sample any particulate matter, aggressive agents, or components that bind irreversibly to the column packing.

guar gum a greyish-white powder consisting predominantly of the polysaccharide **guaran** and obtained by grinding the endosperm of the seeds of guar, an Indian leguminous plant, *Cyamopsis tetragonoloba* (*psoralioides*), also called cluster bean. It hydrates and disperses readily in cold water to give colloidal solutions of very high viscosity that are stable over a very wide pH range and have very good suspending and lubricating properties. It is used for sizing paper and textiles, and as a stabilizing, suspending, and thickening agent in the food and pharmaceutical industries, etc. It has also been suggested as a nonabsorbable dietary additive to improve glycemic control in diabetes mellitus, possibly by slowing the uptake of ingested absorbable carbohydrate.

GUC a codon in mRNA for L-valine.

guessmer an oligonucleotide probe assembled on the basis of partial protein sequence information coupled with intelligent guesswork guided by knowledge of codon usage. Such a probe is used to screen a cDNA library for the corresponding gene.

GUG a codon in mRNA for L-valine.

Guggenheim plot a procedure that makes it possible to obtain rate constants for first-order reactions when neither the initial nor the final reactant concentrations are known. Measurements of the concentration of the reactant (or of some physical quantity that measures it), c_1, c_2, c_3,...c_n, are made at times t_1, t_2, t_3,...t_n and also at times $(t_1 + \delta t)$, $(t_2 + \delta t)$, $(t_3 + \delta t)$,...$(t_n + \delta t)$, when the concentrations of the reactant are c_1', c_2', c_3',...c_n', where δt is a constant time difference, then

$$\ln(c_i - c_i') = \ln(c_0 - c_\infty)(1 - e^{-k\delta t}) - kt,$$

or

$$\ln(c_i - c_i') = \text{a constant} - kt_i,$$

hence a plot of $\ln(c_i - c_i')$ versus t_i has a slope of $-k$. [After Edward Armand Guggenheim (1901–70), British physical chemist.]

guide RNA *see* **gRNA**.

guinea pig any of several species of wild or domesticated hystricomorph rodents, or cavies, in the genus *Cavia*, especially *Cavia porcellus*, which is widely used in biomedical research and testing.

Guinier plot a method of plotting the results of small-angle X-ray scattering to obtain the radius of gyration of a molecule, r_G, in the absence of information about the relative molecular mass of the component in question. It can be shown that

$$\ln(I_\theta / I_0) = -(4\pi\, r_G \sin\theta / \lambda)^2/3,$$

where I_θ and I_0 are the intensities of the scattered radiation at angles θ and 0 respectively, and λ is the wavelength of the radiation; hence a plot of $\ln(I_\theta / I_0)$ versus $-(4\pi\sin\theta / \lambda)^2/3$ will yield r_G.

Gul *symbol for* a residue (or sometimes a molecule) of the aldohexose gulose.

GulA *symbol for* a residue (or sometimes a molecule) of the uronic acid guluronic acid.

gulo- *prefix (in chemical nomenclature)* indicating a particular configuration of a set of (usually) four contiguous >CHOH groups, as in the acyclic form of D- or L-gulose. *See* **monosaccharide**.

L-gulonolactone oxidase EC 1.1.3.8; *other name*: L-gulono-γ-lactone oxidase; a flavoprotein enzyme that catalyses the oxidation by dioxygen of L-gulono-1,4-lactone to L-*xylo*-hexulonolactone (I) and H_2O_2. I isomerizes spontaneously to L-ascorbate. The flavin is FAD. The enzyme is essential for the formation of ascorbate, and a deficiency of the enzyme, as in humans, results in dependency on a dietary supply of ascorbate (*see* **ascorbic acid**). Example from rat: GGLO_RAT, 439 amino acids (50.42 kDa).

gulose *symbol*: Gul; *the trivial name for* the aldohexose *gulo*-hexose; a stereoisomer of glucose in which the configurations at both C-3 and C-4 are inverted. There are two enantiomers. (Illustrated opposite.)



gulose (β-D-pyranose form)

guluronic acid *symbol*: GulA; the **uronic acid** resulting from the oxidation of the hydroxymethylene group at C-6 of gulose to a carboxyl group. L-Guluronic acid is a component of **alginic acid**.

gum any of numerous water-soluble or water-dispersible heteroglycans, frequently containing uronic acids, that are produced as exudates from certain plants, especially trees, following physical injury. Gums are tacky, slimy substances that harden when dry. *See also* **gum arabic**, **gum ghatti**.

gum arabic a **gum** exuded from trees of the genus *Acacia*. Structurally it is a heteroglycan containing D-galactose, L-arabinose, L-rhamnose, and D-glucuronic acid. It is used in industry, e.g. in the manufacture of thickening agents, emulsifiers, inks, and pills. It is also used in glues and pastes.

gum ghatti a **gum** from the tree *Anogeissus latifolia*. It has a complex structure and contains as major components D-mannose, D-galactose, and L-arabinose, the latter in both furanose and pyranose arrangement. Small amounts of D-xylose and D-glucuronic acid are also present.

GUN4 a nuclear-encoded protein (266 amino acids) of *Arabidopsis thaliana* chloroplasts that controls synthesis of Mg-protoporpyhrin IX through its action on Mg-chelatase. GUN4 binds the product and the substrate of Mg-chelatase and represses many nuclear genes that control plastid differentiation. The name derives from the chlorophyll-deficient mutant *gun4*. A similar protein is present in other plants.

Gunn rat any member of a mutant strain of Wistar rats with hereditary hyperbilirubinemia. The defect affects the rate of glucuronidation of a number of substrates, but not equally. [After C. H. Gunn.]

Güntelberg–Müller charging process a method of calculating the electrical energy of an ion. According to the process, only the ion under consideration is supposed to receive a charge; the surrounding ions are assumed to be already charged, and the only change that they undergo during the process is a gradual redistribution as the central ion receives its charge.

Guo *symbol for* a residue of the ribonucleoside guanosine (alternative to G).

Guo*P* *symbol for* guanosine phosphate.

Guo2′*P* *symbol for* guanosine 2′-phosphate; *see* **guanosine phosphate**.

guo-2′,3′-*P* *symbol for* guanosine 2′,3′-phosphate; *see* **guanosine phosphate**.

Guo3′*P* *symbol for* guanosine 3′-phosphate; *see* **guanosine phosphate**.

Guo-3′,5′-*P* *symbol for* guanosine 3′,5′-phosphate.

Guo5′*P* *symbol for* guanosine 5′-phosphate.

Guo5′*PP* *symbol for* guanosine diphosphate (alternative to ppG).

Guo*PP*[CH$_2$]*P* *symbol for* guanosine 5′-[β,γ-methylene] triphosphate (alternative to p[CH$_2$]ppG).

Guo*PP*Man *symbol for* guanosinediphosphomannose.

Guo*PP*[NH]*P* *symbol for* guanosine 5′-[β,γ-imido]triphosphate (alternative to p[NH]ppG).

Guo5′*PPP* *symbol for* guanosine 5′-triphosphate (alternative to pppG).

Guo5′*PPP*[S] *symbol for* guanosine 5′-γ-thiotriphosphate.

Guo5′*PP*[S] *symbol for* guanosine 5′-β-thiodiphosphate.

Gurken a transforming growth factor α-related protein produced in the dorsal region of *Drosophila* embryos, where it is involved in dorsoventral specification. It binds a membrane tyrosine kinase receptor that activates Ras.

gustducin a taste-cell-specific G protein α subunit closely related to the transducins, and comprising 354 amino acids.

gut a term variously used to describe the whole of the alimentary canal or only the intestine, i.e. the part from the stomach to the anus.

gut glucagon *(sometimes) an alternative term for* **enteroglucagon**.

gut hormone *a general, inaccurate, but widely used term for* all the various regulatory peptides of the gut. They are neither confined to the gut, nor are they exclusively hormones.

Guthrie test a microbiological test in which a strain of *Bacillus subtilis* that requires phenylalanine for growth is used to test for excessive levels of plasma phenylalanine in conditions such as **phenylketonuria**. [After R. Guthrie (1916–).]

gutta-percha a *trans*-1,4-polyisoprene derived by coagulation of the latex of various Malayan trees of the genus *Palaquium*. It has a lower molecular mass than rubber and is thermoplastic.

GUU a codon in mRNA for L-valine.

g-value *or* **g-factor** a factor that specifies the position at which the absorption of a paramagnetic species occurs in an **EPR** spectrum. For a free electron in a vacuum, g has the value 2.002 319 304 4…. In a paramagnetic molecule, the energy difference between the two states is afected by interaction of the unpaired electron spin with electron orbitals. For the purposes of EPR spectroscopy, these interactions are taken into account by allowing the g-value to be a spectroscopic variable. For a field B_O and frequency υ, resonance occurs when $h\upsilon = g\mu_B B_O$, where h is the Planck constant and μ_B is the Bohr magneton.

G value (in nuclear chemistry) the number of specified chemical events in an irradiated substance produced per 100 eV of energy absorbed from ionizing radiation.

Gy *symbol for* gray.

gynaminic acid *formerly, a name for* a constituent of human milk, now known to be identical with **sialic acid**.

gynogamone *see* **gamone**.

gyrase *see* type II **DNA topoisomerase**.

gyrate atrophy of choroid and retina *see* **OAT**.

gyrin any of several membrane proteins, including synaptogyrins 1 to 4, that occur as components of transport vesicles and neurotransmitter vesicles. They contain four transmembrane segments, have intracellular N- and C-termini, and resemble the physins in both their architecture and function. **Synaptogyrin 2** (*also called* cellugyrin) is also present in vesicles that contain glucose transporter 4 (GLUT4). Homologues occur in *Drosophila* and *Caenorhabditis*.

gyromagnetic ratio *or* **magnetogyric ratio** *symbol*: γ; the ratio of the magnetic moment, μ, of a given atomic particle to its angular momentum, L; i.e. $\gamma = \mu/L$. *See also* **proton magnetogyric ratio**.

Hh

h *symbol for* **1** hecto+ (SI prefix denoting 10^2 times). **2** hour (supersedes hr.).

h *symbol for* **1** Planck constant. **2** Hill coefficient (alternative to n_H). **3** height.

h+ *or (not recommended)* **H+** *prefix* to abbreviations for peptide hormone (names) denoting human, i.e. of (or as if of) human origin; e.g. hGH (for human growth hormone).

H *symbol for* **1** hydrogen; *see also* **protium**, **deuterium**, **tritium**. **2** a residue of the α-amino acid **histidine** (alternative to His). **3** a residue of an incompletely specified base in a nucleic-acid sequence that may be adenine, cytosine, or either thymine (in DNA) or uracil (in RNA).

4 henry. **5** histone. **6** histamine (*see* **histamine receptor**).

H+ *see* **h+**.

H1 a DNA-binding protein from *Escherichia coli* belonging to the **H-NS** family of proteins.

H7 1-(5-isoquinolinylsulfonyl)-2-methylpiperazine; an inhibitor of protein kinase C (K_i = 6.0 μM), protein kinase A (K_i = 3.0 μM), and cyclic GMP-dependent protein kinase (K_i = 5.8 μM).



H_2 *symbol for* **1** dihydrogen. **2** the prefix **dihydro+** in a trivial chemical name, e.g. H_2folate for dihydrofolate.

H_4 *symbol for* the prefix **tetrahydro+** in a trivial chemical name, e.g. H_4folate for tetrahydrofolate.

H *symbol for* **1** fluence (alternative to *F*). **2** enthalpy. **3** magnetic field strength (light italic in nonvector equations; bold italic in vector equations).

-*H* *conformational descriptor* designating the half-chair conformation of a six-membered ring form of a monosaccharide or monosaccharide derivative. Locants of ring atoms that lie on the side of the structure's reference plane from which the numbering appears clockwise are indicated by left superscripts and those that lie on the other side of the reference plane by right subscripts; e.g. methyl 2,3-anhydro-5-thio-β-L-lyxopyranoside-^5H_s. *See also* **conformation**.

H- *or (sometimes)* ***H*** *(in chemical nomenclature) symbol for* indicated hydrogen (at the position specified by a prefixed locant).

Habc domain *abbr. for* helix a, b, and c domain; a protein sequence in the N-terminal region of syntaxins that forms a triple alpha-helix bundle that folds back on the SNARE domain (which consists of heptads) and prevents it from forming complexes with other SNAREs.

Haber–Weiss reaction the iron-catalysed reaction of a superoxide anion with hydrogen peroxide to form oxygen, a hydroxyl radical, and a hydroxyl ion. It is thought to proceed as follows:

$$O_2^- + Fe^{3+} \rightarrow O_2 + Fe^{2+}$$

$$H_2O_2 + Fe^{2+} \rightarrow OH^{\bullet} + OH^- + Fe^{3+}$$

[After Fritz Haber (1868–1934), German chemist, and Joseph Weiss.]

HAc *abbr. for* acetic acid.

HACBP *see* **calreticulin**.

***Hae*II** a type 2 **restriction endonuclease**; recognition sequence: [AG]GCGC↑[TC].

***Hae*III** a type 2 **restriction endonuclease**; recognition sequence: GG↑CC. The M.*Hae*III modification site is C3.

haem *a variant spelling (esp. Brit.) of* **heme**.

haema+ *or (before a vowel)* **haem+** *variant spellings (esp. Brit.) of* **hema+**.

haemadin a 57-amino-acid anticoagulant peptide from the Indian leech, *Haemadipsa sylvestris*. It is a slow, tight-binding inhibitor of thrombin, but does not inhibit trypsin, chymotrypsin, factor Xa, or plasmin. .

haemato+ *or (before a vowel)* **haemat+** *variant spellings (esp. Brit.) of* **hemato+**.

haemo+ *a variant spelling (esp. Brit.) of* **hemo+**.

haemoglobin *a variant spelling (esp. Brit.) of* **hemoglobin**.

Hageman factor *an alternative name for* factor XII; *see* **blood coagulation**.

hairpin any part of a linear molecular structure, e.g. of a polynucleotide strand or a prostaglandin, in which two adjacent segments of the molecule are folded back one on the other and held in that conformation by secondary molecular forces such as hydrogen bonds or van der Waals interactions. **Hairpin DNA** (*or* foldback DNA *or* loopback DNA) contains **inverted repeats**; when denatured it renatures extremely rapidly by intrachain base-pairing between complementary sequences of the inverted repeat. Similar structures occur in large RNA molecules. The hairpin conformation of a prostaglandin molecule is thought to be necessary for expression of its hormonal activity; in this conformation the α and κ chains of each molecule are extended, parallel to one another, at van der Waals contact distance for their full lengths. *See also* **ribozyme**, **beta bend**.

hairy a **pair-rule gene** of *Drosophila*.

Hakai a protein belonging to the E3 ubiquitin ligase family that specifically binds to phosphotyrosyl residues on E-cadherin, targeting it for ubiquitination and endocytosis. [Japanese for 'destruction'.]

Haldane coefficient the difference, per bound dioxygen molecule, in the number of hydrons bound by oxy- and deoxyhemoglobin, at constant pH. [After John Scott Haldane (1860–1936), British physiologist.]

Haldane effect the observation that oxygenated blood absorbs less carbon dioxide than deoxygenated blood. It is the reciprocal of the **Bohr effect**.

Haldane gas-analysis apparatus an apparatus once used for the estimation of the carbon dioxide and dioxygen contents of a gas sample.

Haldane relation a relation for reversible enzyme reactions. In the single-substrate, essentially reversible reaction:

$$E + S \underset{k_{-1}}{\overset{k_1}{\rightleftharpoons}} ES \underset{k_{-2}}{\overset{k_2}{\rightleftharpoons}} EP \underset{k_{-3}}{\overset{k_3}{\rightleftharpoons}} E + P$$

the overall equilibrium constant,

$$K = C_P/C_S = k_1k_2k_3/k_{-1}k_{-2}k_{-3},$$

where C_S and C_P are the concentrations of substrate, S, and product, P, respectively. It can further be shown that

$$K = V_SK_{mP}/V_PK_{mS},$$

where V_S and V_P are the maximum velocities of the reactions S → P in the absence of P and of P → S in the absence of S, and K_{mS} and K_{mP} are the respective Michaelis constants for these reactions. [After John Burdon Sanderson Haldane (1892– 1964), British biochemist, physiologist, and geneticist.]

half-boat conformation either of the **conformations** of a nonplanar monounsaturated six-membered ring compound when the two ring atoms not directly bound to the doubly bonded atoms lie on the same side of the plane containing the other four (adjacent) atoms.

half-cell one half of an **electric cell**, consisting of one reversible electrode inserted into a solution. Electrical connection between this solution and that in another half-cell is required to complete the electric circuit.

half-chair conformation 1 either of the **conformations** of a nonplanar monounsaturated six-membered ring compound when the two ring atoms not directly bound to the doubly bonded atoms lie on opposite sides of the plane containing the other four (adjacent) atoms. **2** any conformation of the six-membered ring form of a monosaccharide or monosaccharide derivative when four adjacent ring atoms are coplanar and the other two lie on opposite sides of the plane. The conformational descriptor *-H* may be added to the name of such compounds.

half-cystine *or* **hemicystine** *symbol*: $\overset{|}{\text{Cys}}$ *or* $\underset{|}{\text{Cys}}$; the group formally derived by removal of a hydrogen atom from the thiol group on the side chain of cysteine (or of a cysteine residue), or by homolysis of the dithio linkage of cystine (or of a cystine residue). It is used to describe or depict the content or linear sequence of amino-acid residues in a polypeptide when it contains more than two apparent cysteine residues, and the positions of any dithio linkages between them are not known.

half-cystyl *or* **hemicystl** the acyl group, $\cdot$S–CH_2–CH(NH_2)–CO–, derived from the **half-cystine** group. *Compare* **cysteinyl**.

half-ester any monoester of a dibasic acid.

half-life 1 *symbol*: $t_{1/2}$ *or* $T_{1/2}$; the time for one half of the atoms of an amount of radionuclide to undergo radioactive decay. **2** a similar measure of the stability (i.e. rate of decay) of an excited atom or molecule, a radical, an unstable elementary particle, etc. **3** the time for one half of the amount of an administered substance to be metabolized or excreted. If the substance is radioactive, the time required for one half of the dose to be eliminated biochemically or physiologically is termed the **biological half-life** and that required for one half to disappear by radioactive decay as well as by the elimination is the **effective half-life**. **4** *or (sometimes)* **half-time** *symbol*: $t_{1/2}$; the time required for the concentration of a reactant in a chemical reaction to reach a value that is the arithmetic mean of its initial and final (equilibrium) values. **5** the time for one half of the number of cells in a tissue or organ to be replaced by new cells.

half-of-the-sites reactivity *or* **half-site reactivity** a phenomenon shown by many enzymes that exhibit **negative cooperativity**, in which the maximal stoichiometric yield of either an enzyme–substrate intermediate or a product in a single turnover amounts to only half the number of apparently equivalent active sites. This may be caused by the binding of substrate to one site of a dimeric enzyme, e.g., inducing a conformational change in the enzyme so as to abolish completely the binding affinity of the other site.

half-reaction either of the two coupled chemical changes that together constitute an oxidation–reduction reaction. In one half-reaction there is a gain of electrons and in the other half-reaction a corresponding loss of electrons.

half-shotgun coverage *see* **depth of coverage**.

half-site reactivity *an alternative name for* **half-of-the-sites reactivity**.

half-thickness the thickness of a piece of a specified material that will reduce the intensity of a beam of transmitted electromagnetic radiation to one half that of the incident beam.

half-time *an alternative name for* **half-life** (def. 4) for a first-order process.

half-time of exchange the time taken for one half of the exchangeable atoms (or molecules) to be exchanged in a reaction involving such an exchange.

half-transporter a member of the **ABC transporter** superfamily usually found in peroxisomal or in microbial membranes. It contains a membrane-spanning region (with six transmembrane segments) and a nucleotide-binding domain.

half-wave potential the electrical potential at the mid-point of the current–voltage curve in **polarography**.

halide *or* **halogenide** 1 an anion of any halogen. **2** a salt of any halogen acid (halogen hydride). **3** any compound containing halogen atoms in organic linkage.

Hallervorden–Spatz syndrome an early-onset neurodegenerative syndrome of parkinsonism, dystonia, and iron accumulation in the brain. It is caused by deficiency of **pantothenate kinase**. [After Julius Hallervorden (1882–1965) and Hugo Spatz (1888–1969), German neurologists.]

hallucinogen any drug or other substance that causes hallucinations. —**hallucinogenic** *adj.*

halo+ *or (sometimes before a vowel)* **hal+** *comb. form* **1** relating to or containing a halogen. **2** relating to the sea or salt.

halochromism the phenomenon or property of the formation of strongly coloured compounds on the addition of strong acids or certain metallic salts to colourless or faintly coloured substances.

halofantrine 1,3-dichloro-α-[2-(dibutylamino)-ethyl]-6-(trifluoromethyl)-9-phenanthrenemethanol; a derivative of 9-phenanthrenemethanol that is effective against chloroquine-resistant malarial infections.



halogen any of the monovalent chemical elements of group 17 of the IUPAC **periodic table**: fluorine, chlorine, bromine, iodine, and astatine.

halogenate to treat or react (a substance) with a halogen; to introduce one or more halo groups into an organic compound. —**halogenation** *n.*

halogenide *an alternative name for* **halide**.

haloperidol 4-[4-(4-chlorophenyl)-4-hydroxy-1-piperidinyl]-1-(4-fluorophenyl)-1-butanone; one of the butyrophenone group of **neuroleptic** drugs.



haloperoxidase one of a group of enzymes that halogenate organic substrates using hydrogen peroxide and a halide ion (Cl^-, Br^-, or I^-). Haloperoxidases contain either heme or vanadium.

halophile 1 an organism that grows in or tolerates saline conditions, especially concentrations of sodium chloride equal to or greater than that in sea water. **2** describing such an organism. —**halophilic** *adj.*

halorhodopsin a pigment identified in membranes of *Halobacterium halobium*. It is similar to **bacteriorhodopsin** and, upon absorption of a photon, catalyses inward transport of chloride ions.

halothane *the trivial name for* 2-bromo-2-chloro-1,1,1-trifluoroethane, a widely used, volatile, lipid-soluble general inhalational anesthetic agent.



hamamelose 2-*C*-(hydroxymethyl)-D-ribose; a substance found principally in **tannin** of witch hazel (*Hamamelis virginiana*).

hamartin a protein (1164 amino acids) that is widely expressed, contains a potential transmembrane segment and a predicted coiled-coil domain, and has no homology to any other protein. It may be a tumour suppressor, and forms a mainly cytosolic complex with **tuberin**. Many mutations in the gene at 9q34 produce the autosomal dominant tuberous sclerosis type 1 (TSC1).

Hamburger shift *an alternative name for* **chloride shift**. [Named after Hartog Jakob Hamburger (1859–1924), Dutch physiologist.]

Hamiltonian operator *symbol*: H; a function used to express the total energy of a system in joules: $H = T + V$, where T is the kinetic energy operator and V the potential energy operator. For a particle of mass m and momentum p,

$$H = p^2/2m + V.$$

[After William Rowan Hamilton (1805–65), Irish astronomer and mathematician.]

hamlet a protein that acts as a binary genetic switch between single- and multi-dendrite neuron morphology in *Drosophila* embryos. It is predicted to contain 990 amino acids, with six zinc fingers in the N-terminal half and three more towards the C-terminus. It may be a nuclear transcription factor.

hammerhead *see* **ribozyme**.

Ham's F10 medium, Ham's F12 medium formulations of culture media for the propagation of mammalian cells based on saline F. [Named after Richard G. Ham.]

handedness a form of terminology (based on the human left and right hands) for describing objects and compounds that are mirror images of each other and hence nonsuperimposable. A pair of **enantiomers** display molecular handedness. *See* **chirality**.

handle *a colloquial term for* any chemical group attached to a specified substance with the purpose of making it more easily identified, more reactive, or more easily operated upon, or one that may serve in targeting or specific binding. The attachment of a handle may be brought about chemically or metabolically.

handle technique a technique used to separate excess alkylating agents from products in peptide synthesis. For instance, the C terminus of a growing peptide chain can be protected with a basic function, e.g. by forming a 4-picolyl ester of the carboxyl group, thereby allowing separation of the products on cation-exchange resin columns or by extraction into aqueous acidic solutions.

Hanes plot *or* **Hanes–Woolf plot** a graphical method for treating enzyme kinetic data using the following form of the Michaelis equation (*see* **Michaelis kinetics**):

$$s/v = K_m/V + s/V$$

where s is the substrate concentration, v is the velocity of the reaction, and V is the limiting rate. If s/v is plotted against s, the slope of the resulting straight line is $1/V$, the intercept on the s/v axis is K_m/V, and the intercept on the s axis is $-K_m$. [After Charles Samuel Hanes (1903–90) and Barnet Woolf (1902–1983), British biochemists.]

hanging drop method a technique used in protein crystallization in which a droplet of protein solution, buffer, and precipitant is allowed to equilibrate with a reservoir of buffer and precipitant at higher concentration in a closed system. The name comes from the fact that the droplet hangs from a glass coverslip suspended over the reservoir.

Hanks' balanced salt solution *abbr.*: HBSS; a balanced salt solution used in tissue culture to provide a suitable ionic and osmotic environment for cell growth and development.

Hansch equation an equation relating the differences in the partitions of variously substituted compounds between an organic and an aqueous phase to the **hydrophobicity constant**, π, of the substituent. If P_0 is the ratio of the solubility of the parent compound in an organic phase to that in the aqueous phase, and P is the corresponding ratio for the substituted compound, then: $\pi = \log(P/P_0)$.

Hansenula *see* **methylotrophic yeasts**.

H antigen *see* **blood-group substance**.

***Hap*II** a type 2 **restriction endonuclease**; recognition sequence: C↑CGG. *Hpa*II and *Msp*I are **isoschizomers**. The M.*Hap*II modification site is C2; M.*Hpa*II is an isoschizomer.

haploid describing a cell, an organism or a nucleus of a cell having a single genome or a single set of homologous chromosomes; i.e. containing half the **diploid** number; having a **ploidy** of one. **—haploidy** *n.*

haplotype a set of genes located on a single chromosome; the term is used also to denote the characteristics dependent on those genes. In outbred populations the maternal and paternal chromosomes usually differ, so an individual has two haplotypes, one derived from each parent.

'happiness hormone' *a jocular name for* any **endorphin** or **enkephalin**, so-named because of the supposed ability of such substances to promote a sense of well-being.

hapt+ *a variant form of* **hapto+** (before a vowel).

hapten any, usually small, substance that can combine specifically with antibody but that is not immunogenic unless bound to a **carrier** (def. 8). Most haptens carry only one or two antigenic determinants. **—haptenic** *adj.*

hapten-inhibition test a serological test for characterizing an antigenic determinant. It involves the use of haptens of known structure to block the combining site of a particular antibody.

hapten-sandwich labelling a variant of the **sandwich technique** for amplification of an antigen–antibody reaction. In this modification, the primary antibody, specific for the antigen of interest, is combined with a number of residues of a hapten, e.g. *p*-azobenzene arsonate. The secondary (labelled or marked) antibody is a specific anti-hapten antibody; on reaction of secondary antibody molecules with a molecule of primary antibody, the hapten residues become sandwiched between the large molecules of antibody. By the use of different haptens and two or more non-cross-reactive anti-hapten antibodies bearing distinguishable markers, two or more antigens on the same or different cells may simultaneously be labelled.

hapticity *symbol*: η; the attribute of a ligand entity or group that combines with a central (usually metal) atom to form a coordination entity in which the central atom is bonded to two or more contiguous atoms of the ligand rather than to a specific atom. Such a coordination entity is frequently (but not exclusively) a **pi adduct**. *See also* **hapto**.

hapto *or (less commonly)* **eta** *(in chemical nomenclature)* the name by which to read the symbol η- (Greek eta), when prefixed to the name of the ligand group in a coordination entity (with added locants if appropriate) to indicate hapticity.

hapto+ *or (before a vowel)* **hapt+** *comb. form* indicating ability to bind or combine.

haptocorrin a blood cobalamin-binding glycoprotein that may prevent uptake of bacterial cobalamin analogues.

haptoglobin *abbr.*: Hp; any α_2 globulin of blood plasma that can combine with free oxyhemoglobin to form a stable, ~300 kDa, complex. Such combinations occur when hemoglobin is liberated in the blood, and the complexes so formed, which have weak peroxidase activity and cannot be filtered by the kidney, are rapidly removed and degraded in the tissues. Three human haptoglobin phenotypes are known, designated Hp 1-1, Hp 2-2, and Hp 2-1, each of which contains two pairs of non-identical polypeptide chains, α and β, joined by disulfide bonds. There are two kinds of α chain, α_1 of 84 amino-acid residues (9 kDa) and α_2 of 143 residues (17 kDa), and a single kind of β chain, of 244 residues (in human). The α_2 chain, found solely in human haptoglobin, is identical in sequence to that of residues 1–71 or 1–72 of an α_1 chain linked to residues 11 or 12 to 84. The basic subunit structure of Hp 1-1 is $(\alpha_1\beta)_2$, that of Hp 2-2, $(\alpha_2\beta)_2$, and that of Hp 2-1, $(\alpha_2\beta)(\alpha_1\beta)$. However, the α_2 chain has an odd number of half-cystine residues; consequently, larger oligomers of Hp 2-2 and Hp 2-1 may arise by formation of disulfide bonds with α_2 chains of other molecules or of $(\alpha_2\beta)$ half-molecules.

haptomer any substance (such as a lectin or the B fragment of diphtheria toxin) that can interact with the cell membrane and that binds or can be bound to an **effectomer** (such as gelonin or the A fragment of diphtheria toxin), thereby allowing the effectomer to exert its toxic action on intact cells. **—haptomeric** *adj.*

haptophore a term introduced by Ehrlich to denote the specific chemical group in a toxin (i.e. antigen) molecule that attaches it to an antitoxin (i.e. antibody) molecule. Unlike the **toxophore**, it is not destroyed on conversion of the toxin to a toxoid.

H^+(aq) *symbol for* the hydrated hydrogen ion, the normal state of the hydrogen ion in aqueous solutions, consisting of a hydron surrounded by a shell of water molecules held by ion–dipole interaction. *Compare* **oxonium** (def. 1).

hard *(in radiation physics)* describing corpuscular or electromagnetic ionizing radiation (especially beta particles or X- or gamma-radiation) having relatively high energy, hence high ionizing power and long-range or high penetrating power. Hard X- or gamma-radiation has short wavelengths. *Compare* **soft** (def. 1).

Harden–Young ester *a former name for* D-fructose 1,6-bisphosphate (before its chemical structure had been elucidated). [After (Sir) Arthur Harden (1865–1940) and William John Young (1878–1942), British biochemists.]

Hardy–Weinberg law a mathematical statement about the relation between gene frequencies and genotype frequencies within a population. If the genotypes are AA, Aa, and aa, and p is the frequency of allele A in the population, and q the frequency of allele a, so that $p + q = 1$, then the relative proportions of the three genotypes in the population, AA:Aa:aa, is given by $p^2{:}2pq{:}q^2$. [After Godfrey Harold Hardy (1877–1947), British mathematician, and Wilhelm Weinberg (1862–1937), German physician.]

Hardy–Weinberg population a population of randomly mating individuals in which there are no changes in allele frequencies from generation to generation. *See* **Hardy–Weinberg law**.

harmaline 4,9-dihydro-7-methoxy-1-methyl-3*H*-pyrido[3,4-*b*]indole; dihydroharmine; a cardioactive alkaloid from Syrian rue, *Peganum harmala* that also has hallucinogenic properties. *See also* **harmine**.



harmine 7-methoxy-1-methyl-9*H*-pyrido[3,4-*b*]indole; a *β*-carboline alkaloid found in, e.g., *Peganum harmala* (Syrian rue). It inhibits monoamine oxidase and is a central nervous system stimulant. *See also* **harmaline**.



harmonin a cytosolic protein, encoded by a gene at 11p15.1, mutations of which cause the autosomal recessive **Usher syndrome** type IC. It contains a common, highly conserved sequence of ≈90 residues (called a **PDZ domain**) that forms a hydrophobic pocket capable of binding the intracellular hydrophobic C-terminal residue of several transmembrane proteins and ion channels.

HART *abbr. for* hybrid-arrested translation.

Hartley filter funnel a development of the **Büchner funnel** comprising three pieces, the reservoir, a perforated plate to support the filter disk, and a conical piece to collect the filtrate. [After (Sir) Percival Hartley (1881–1957), British bacteriologist.]

Hartnup disorder a rare, autosomal recessive condition of humans in which there is a specific hyperaminoaciduria and indoluria, due to diminished renal reabsorption of monoamino-monocarboxylic acids, especially tryptophan. There may also be an impaired intestinal absorption of the same amino acids. It is often associated with a pellagra-like skin rash, which may be resolved by oral nicotinic acid. [After E. Hartnup, the first patient with the condition to be described.]

hashish a resinous extract obtained from the dried flower tops of the hemp plant (*Cannabis sativa*). The term may sometimes be used for various other extracts. *See* **cannabis**.

HAT *abbr. for* **1** hypoxanthine-aminopterin-thymidine (medium); a medium devised to select against cells deficient in hypoxanthine/guanine phosphoribosyltransferase (HGPRT$^-$ cells). Aminopterin blocks *de novo* synthesis of purines and HGPRT$^-$ cells are unable to utilize the salvage pathway, and hence are killed. It is of particular use in the production of **hybridomas**. **2** human airway trypsin-like protease; a serine protease type II transmembrane protein (418 amino acids) of the trachea. **3** histone acetyltransferase.

hatching enzyme *see* **envelysin**.

Hatch–Slack pathway *or* **C_4 cycle** *or* **C_4 pathway** a metabolic pathway for carbon-dioxide translocation occurring in **C_4 plants**. In the mesophyll cells **phospho*enol*pyruvate carboxylase** catalyses the condensation of CO_2 with phospho*enol*pyruvate to form oxaloacetate; this is then reduced to malate by light-generated NADPH. The malate passes into the bundle-sheath cells where it is oxidatively decarboxylated by the **malic enzyme** to pyruvate and CO_2; the pyruvate returns to the mesophyll cells and is reconverted to phospho*enol*pyruvate by ATP and pyruvate dikinase; the CO_2 remains in the bundle-sheath cells where it enters the **reductive pentose phosphate cycle**. The overall effect of the pathway is to carry CO_2 from the mesophyll cells, which are in contact with air, to the bundle-sheath cells, which are the major sites of photosynthesis.

Haworth representation a diagrammatic way of unambiguously representing the structural formulae of the cyclic forms of monosaccharides to show on a plane surface the relative configurational arrangements of the atoms and groups in space. Pyranoses are represented by a hexagon (five carbons and one oxygen) and furanoses by a pentagon (four carbons and one oxygen). A Haworth representation is derived from a **Fischer projection** as follows. The monosaccharide in question is depicted with the carbon-chain horizontal and in the plane of the paper, the potential carbonyl group being to the right. The oxygen bridge is then depicted as being formed behind the plane of the paper. The heterocyclic ring is therefore located in a plane approximately perpendicular to the plane of the paper and the groups attached to the carbon atoms of that ring are above and below the ring. The edge of the ring nearer the viewer is indicated by thickened lines. For clarity, the carbon atoms of the ring and their attached hydrogen atoms are not shown. Groups that, in the Fischer projection, appear to the right of the vertical chain then appear in the Haworth representation below the plane of the ring. However, at the asymmetric carbon atom involved via oxygen in ring formation (e.g. C-5 in glucopyranose, C-4 in glucofuranose), a rotation about the bond to the preceding carbon atom must be envisaged in order to bring that oxygen atom into the correct orientation to link to the carbon atom of the carbonyl group. Thus, if the hydroxyl group that is engaged in ring formation lies to the right in the Fischer projection, the group that lies below it must point upwards in the Haworth representation, whereas if it lies to the left, it must point down in the Haworth representation. In representing the *α* and *β* anomers in the Haworth convention, it should be noted that for the *α* anomer, the anomeric hydroxyl points in the opposite direction to the R group (see structure); for D-sugars, the R group points upwards, so the *α*-hydroxyl must point down; conversely, if the R group points down (as in *α*-L-glucose), the *α* anomeric hydroxyl must point upwards. The above rules only obtain if the ring is numbered clockwise from the anomeric carbon, as is frequently the case, and it is important to appreciate that Haworth representations, unlike Fischer projections, cannot be rotated in the plane of the paper but must be reorientated in space. [After (Sir) Walter Norman Haworth (1883–1950), British organic chemist.]



Haymann nephritis antigen *an alternative name for* **LRP2**.

Hb *abbr. and symbol for* hemoglobin; hence, e.g., HbO_2 symbolizes oxyhemoglobin, and HbCO symbolizes carbonmonoxyhemoglobin.

Hb A *abbr. for* adult hemoglobin.

H band *an alternative name for* H zone (*see* **sarcomere**).

HBD *(in clinical chemistry) abbr. for* α-hydroxybutyrate dehydrogenase, the LD_1 isoenzyme of **lactate dehydrogenase**, or 'heart-specific' lactate dehydrogenase, which is assayed using 2-hydroxybutanoate as substrate, a substance that does not occur naturally.

Hb F *abbr. for* fetal hemoglobin.

Hb S *abbr. for* sickle-cell hemoglobin; *see* **sickle cell**.

HBSS *abbr. for* Hanks' balanced salt solution.

hCG *or* **HCG** *abbr. for* human choriogonadotropin (*see* **choriogonadotropin**).

H chain *see* **heavy chain**.

HCO *symbol for* the formyl group (alternative to For).

HCR *abbr. for* host-cell reactivation.

Hcy *symbol for* a residue of the α-amino acid L-homocysteine.

HDAg *abbr. for* hepatitis delta antigen. *See* **hepatitis**.

HDEL a four-residue motif, His-Asp-Glu-Leu, of similar function to the **KDEL** motif.

HDH *abbr. for* **histidinol dehydrogenase**.

HDL *abbr. for* high-density lipoprotein.

HDP *abbr. for* helix-destabilizing protein.

He *symbol for* helium.

head 1 the foremost or uppermost part of the body of an animal; in vertebrates it comprises the skull containing the mouth, brain, and the organs of hearing, sight, smell, and taste. **2** the part of a molecular structure that bears a specific functional group or that is polar, reactive, bulky, or in some other characteristic way differs from the remainder of the molecule. **3** *a common name for* a centrifuge rotor.

headgroup of a polar lipid, that part of the molecule that expresses its polar character. For a phospholipid, this comprises the phosphate group together with any polar entity attached to it. For a glycolipid, it comprises the carbohydrate moiety.

headspace analysis a technique used in the identification of microorganisms involving gas-chromatographic analysis of the vapour in the headspace above the specimen or culture.

heat *symbol*: q or Q; the energy possessed by a system in the form of kinetic energy of atomic or molecular translation, rotation, or vibration. It is measured in joules or calories. Heat energy can be transferred from points of higher temperature to points of lower temperature by conduction, convection, or radiation. When the temperature of a system changes, its enthalpy (heat content) changes by an amount equal to the product of its mass, specific heat capacity, and its change in temperature.

heat capacity *symbol*: C; the amount of heat required to raise the temperature of a body or a system by 1 kelvin; it is usually measured in joules per kelvin. The **heat capacity at constant pressure**, C_p, is given by: $C_p = (\partial H/\partial T)_p$ J K^{-1} and the **heat capacity at constant volume**, C_v, is given by: $C_v = (\partial U/\partial T)_v$ J K^{-1} where H is the enthalpy, U the internal energy, and T the thermodynamic temperature.

heat content *another name for* **enthalpy**.

heat-labile describing molecules that decompose at elevated temperatures or that lose biological activity when heated to a moderate temperature, e.g. 50°C.

heat of activation the difference in heat content between a transition state and the state of its reactants.

heat of combustion the amount of heat evolved when a given amount, usually one mole, of a substance is completely burnt in dioxygen.

heat of evaporation *an alternative name for* **heat of vaporization**.

heat of formation the amount of heat absorbed or evolved when one mole of a substance is formed from its elements.

heat of fusion *or* **heat of melting** the amount of heat absorbed or evolved when a specified quantity of substance, usually one mole, is converted from the solid to the liquid state at a specified pressure and a specified temperature. If the pressure is 1 atm the temperature is the melting point of the substance.

heat of neutralization the amount of heat absorbed or evolved when one mole of an acid or base is completely neutralized.

heat of reaction the amount of heat absorbed or evolved in the course of a (bio)chemical reaction, usually expressed per mole of reacting substances.

heat of solution the amount of heat absorbed or evolved when one mole of a substance is dissolved in a large volume of specified solvent.

heat of vaporization *or* **heat of evaporation** the amount of heat absorbed or evolved when a specified amount of substance, usually 1 mole, is converted from the liquid to the vapour state at a specified pressure and a specified temperature. If the pressure is 1 atm the temperature is the boiling point.

heat-shock protein *abbr.*: hsp; any of a group of specific proteins that are synthesized by both prokaryotic and eukaryotic cells on exposure to temperatures that are higher than normal, or to other stresses, such as free-radical damage. Many members of the hsp family are not induced, but are normally present in all cells. Human cells in culture also produce heat-shock proteins, but induction of heat-shock proteins has not been clearly demonstrated in the body. Heat-shock proteins are classified, according to their size, into three types: Hsp60, Hsp70, and Hsp90. They are characterized by their role as molecular **chaperones**. A major chaperone in the lumen of the endoplasmic reticulum is **binding protein** (BiP), a member of the Hsp70 class. These proteins are highly conserved, those from *Escherichia coli* and humans being 50% identical in primary structure. The Hsp70 proteins possess ATPase and peptide-binding domains. The other members of the Hsp70 class are Grp75 in mitochondria, and **DnaK** in bacterial cytosol. Hsp60 is also found in the mitochondrial matrix; the prokaryotic orthologue of this class is GroEL (*see* ***groEl***).

heat-shock regulatory element *or* **heat-shock response element** *abbr.*: HSE; a base sequence in prokaryotic and eukaryotic genomes responsible for regulating gene expression in response to heat-shock and related stress situations.

heat-shock response element *an alternative name for* **heat-shock regulatory element**.

heat-stable describing something that retains its (bio)chemical activity when heated to a moderate temperature, e.g. 50°C.

heavy *(in physics)* of more than the usual mass. *Compare* **light** (def. 2).

heavy atom *or* **heavy isotope** *or* **heavy nuclide** an isotopic form of an atom that contains more than the common number of neutrons and is thus of greater relative atomic mass than the most abundant or most commonly observed isotope.

heavy carbon *see* **carbon-13**.

heavy chain *or* **H chain** the heavier of the two types of polypeptide chain found in **immunoglobulin** molecules. Each heavy chain is linked, usually by disulfide bonds, to a **light chain** and to another, identical heavy chain. Heavy chains differ in relative molecular mass according to the type of immunoglobulin: in humans the M_r is ≈50 000 in IgG and ≈70 000 in IgM. Each heavy chain consists of an **Fc fragment** and an **Fd fragment**. Heavy chains carry the antigenic determinants that differentiate the various immunoglobulin classes.

heavy-chain disease a rare disease of humans in which there are tumours of lymphoid tissue associated with the presence of free immunoglobulin fragments in plasma and urine.

heavy-chain switch *or* **H-chain switch** the change in the expression of the immunoglobulin **heavy chain** (H chain) gene system as manifested by the predominance of IgM (μ chain class) in the primary immune response and by the predominance of IgG (γ chain class) in the **secondary immune response**.

heavy hydrogen *an alternative name for* **deuterium**.

heavy meromyosin *abbr.*: H-meromyosin *or* HMM; a 350 kDa fragment produced when **myosin** is subjected to tryptic digestion. It contains part of the helical, rod-shaped tail and both globular heads of the original myosin molecule, and hence retains both the ATPase and the actin-binding activity of myosin.

heavy metal a term variously applied to the salts of certain metallic elements of atomic number greater than 11, usually referring to their toxicity and preference for covalent bonding (hence calcium and magnesium are omitted). There is no agreed and consistent definition of a heavy metal.

heavy nitrogen the stable nuclide $^{15}_{7}N$ (nitrogen-15); relative abundance in natural nitrogen 0.37 atom percent. It is used as a tracer in studies of nitrogen metabolism.

heavy oxygen the stable nuclide $^{18}_{8}O$ (oxygen-18), usually accompanied by the stable nuclide $^{17}_{8}\text{O}$ (oxygen-17); relative abundances in natural oxygen: $^{18}_{8}\text{O}$, 0.20 atom percent; $^{17}_{8}\text{O}$, 0.037 atom percent. $^{18}_{8}\text{O}$ is used as a tracer in studies of reaction mechanisms and of oxygen metabolism.

heavy strand *or* **H strand** **1** any polynucleotide chain labelled with a heavy isotope, e.g. nitrogen-15. **2** any naturally occurring chain in a polynucleotide duplex that is heavier or has a greater density than the complementary strand.

heavy water deuterium oxide; *symbol*: ^2H_2O *or* D_2O; water in which the hydrogen atoms in all of the molecules have been replaced by deuterium; or water in which the hydrogen is appreciably enriched in deuterium. The M_r of pure ^2H_2O is 20.028. Heavy water is prepared from natural water by exchange techniques or by fractional distillation or electrolysis. It is used as a tracer in metabolic studies, in investigation of reaction mechanisms, and as a solvent in resonance spectroscopy.

Hechtian stand a threadlike structure that connects protoplasts of plasmolysed plant cells to their cell wall. Hechtian stands are tubes of cytoplasm delineated by plasma membrane that retain tight contacts with the cell wall, possibly via integrin-type receptors or **WAK1**.

hect+ *see* **hecto+** (def. 2).

hecto+ **1** *symbol*: h; an SI prefix denoting 10^2 times. **2** *or (before a vowel)* **hect+** denoting 100 or 100 times.

hedgehog protein a transmembrane protein involved in segment polarity and cell-to-cell signalling during embryogenesis and metamorphosis in *Drosophila melanogaster*. *See also* **sonic hedgehog proteins**.

HEDTA *abbr. for N*-(2-hydroxyethyl)ethylenediamine triacetate, or its trisodium salt, or for its partially or fully protonated forms. It is a chelating agent, especially for ferric ions in the pH range 7.0–10.0.



height equivalent to an effective theoretical plate *abbr.*: HEETP; *symbol*: *H*; *(in chromatography)* the column length divided by the **effective theoretical plate number**.

height equivalent to a theoretical plate *or* **plate height** *abbr.*: HETP; *symbol*: *h*; *(in chromatography)* the column length divided by the **theoretical plate** number.

Heisenberg uncertainty principle the principle that the simultaneous precise determination of the velocity (or any related property, e.g. momentum or energy) of a material particle and its position is impossible; the smaller the particle the greater the degree of uncertainty. [After Werner Karl Heisenberg (1901–76), German physicist; Nobel Laureate in Physics (1932).]

HeLa cell an established tissue culture strain of human epidermoid carcinoma cells containing 70–80 chromosomes per cell (compared with 46 in normal cells). It is much used for biochemical work. HeLa cells have been in continuous culture since 8 February 1951, and were derived from tissue removed from a patient named Henrietta Lacks.

helical cross *a name sometimes given to* the X-shaped pattern of X-ray scattering from a continuous helical molecule.

helical wheel *(in protein sequence analysis)* a circular graph depicting five turns of helix (≈20 residues), around which residues in a protein sequence are plotted 100° apart (3.6 residues per 360° turn) for an alpha helix. Different parameters are used to depict helices with different pitches (e.g. 120° for a 3_{10} helix, 160° for beta strands). Helical wheels are particularly useful for depicting amphipathic character (recognized by the clustering of hydrophilic and hydrophobic residues in distinct polar and nonpolar arcs); however, they are not predictive.

helicase *a name sometimes given to* the protein (**repA**) that promotes the ATP-dependent unwinding of the parental DNA duplex during DNA replication. *See also* **DNA helicase**, **RNA helicase**.

Helicobacter pylori a Gram-negative bacterium that colonizes the human gastric mucosa and is acquired orally in infancy. There are several types and subtypes, with distinct geographical distributions. It is a common cause of gastric ulcer and gastric cancer. The major virulence factor in ulcer formation is the toxin Vac A, which, *in vitro*, disrupts gastric epithelial cell integrity in many ways. In the mouse, Vac A gastric injury is mediated by protein tyrosine phosphatase receptor z (Ptprz) of epithelial cells.

helicorubin a *b*-type cytochrome that occurs in the hepatopancreas of the snail *Helix pomatia* and related species.

helix (*pl.* **helices**) **1** a coiled or spiral structure, e.g. the thread of a bolt or a coil (tubular) spring. *See also* **alpha helix**, **beta helix**, **gamma helix**. **2** the curve traced on the surface of a cylinder or cone by a point crossing its right sections at a constant angle. **3** a space curve with turns of constant angle to the base and constant distance from the axis. **—helical** *adj.*; **helicity** *n.*

helix breaker an amino-acid residue that has a propensity to interrupt α-helical structures when it occurs in a polypeptide chain; e.g., proline (in globular proteins – in membrane proteins, proline introduces a distinctive kink, but does not break the helix), hydroxyproline. *Compare* **helix former**.

helix-destabilizing protein *abbr.*: HDP; any of a group of proteins that bind tightly and preferentially to single-stranded DNA. Theoretically, they: (1) lower the melting temperature, T_{m}, for thermally induced **helix-to-coil transition**; (2) lower the optimum temperature for duplex renaturation; (3) sterically hinder base pairing and degradation of single strands by nucleases; (4) induce a conformation for the single-stranded DNA that is optimal for its function in some processes, e.g. as a template in replication; and (5) interact with other proteins (enzymes) to potentiate processes involving single-stranded DNA and these proteins.

helix former an amino-acid residue that has a propensity to promote α-helical structures when it occurs in a polypeptide chain. *Compare* **helix breaker**.

helix-loop-helix *abbr.*: HLH; *an alternative term for* **helix-turn-helix**.

helix-to-coil transition the transition of a macromolecule (polypeptide or polynucleotide) from an ordered to a disordered structure; it is equivalent to **denaturation**. Helix-to-coil transitions are usually detected by monitoring a change in some physical property of the macromolecule such as intrinsic viscosity, optical absorbance, or sedimentation coefficient. *See also* **melting temperature**.

helix-turn-helix (*abbr.*: HTH) *or* **helix-loop-helix** (*abbr.*: HLH) a structural feature of several DNA-binding regulatory proteins consisting of two helices separated by a **beta turn**.

helix winding number *see* **supercoil**.

Helmholz free energy *or* **Helmholz function** *abbr.*: *F* or *A*; free energy at constant volume.

helodermin *see* **exendin**.

helospectin I *see* **exendin**.

helper cell *abbr.*: T_H cell; a **T lymphocyte**, carrying the surface markers CD4 and CD5 in the human (L3T4 and Ly1 in the mouse), that acts as an inducer of the effector cells for both **humoral** and **cell-mediated immunity**. Helper cells recognize and bind to antigen in combination with class II **major histocompatibility complex** molecules on the surface of antigen-presenting cells, and generate lymphokines that stimulate effector cytotoxic cells and B cells. Other cells of the helper phenotype, e.g. CD4$^+$ cells, are known as T-**suppressor** cells and are responsible for suppression, exerting negative feedback control on the helper cells.

helper peak-1 *abbr.*: HP-1; *a former name for* **interleukin 1**.

helper phage a bacteriophage that is capable of infecting *E. coli* cells and directing the synthesis of proteins necessary for phage replication but is itself unable to replicate owing to mutations it carries. Cloning vectors, such as lambda ZAP, which have an M13 origin of replication, can be induced to replicate in single-stranded form if the *E. coli* cells that harbour them are superinfected with helper phage.

helper virus any virus that supplies one or more of the functions that a **defective virus** is unable to perform. When a cell is infected with both a defective virus and a helper virus, the former is able to replicate, a property that can be exploited in various molecular biological techniques.

hem+ *or (esp. Brit.)* **haem+** *a variant form of* **hemo+** (before a vowel).

hema+ *or (esp. Brit.)* **haema+** *a variant form of* **hemo+**.

hemadsorption the adsorption of an agent or substance to or on the surface of a red blood cell.

hemagglutination *or (esp. Brit.)* **haemagglutination** the agglutination of red blood cells.

hemagglutinin *or (esp. Brit.)* **haemagglutinin** **1** any **agglutinin** of red blood cells. **2** any nonantibody substance, e.g. a lectin or a surface component of some virus particles, that can agglutinate red blood cells. **3** a viral envelope glycoprotein responsible for the attachment of virus to cell receptors and the initiation of infection.

hemat+ *or (esp. Brit.)* **haemat+** *a variant form of* **hemato+** (before a vowel).

hematin *or (esp. Brit.)* **haematin** **1** *or* **ferriheme hydroxide** *the trivial name for* ferriprotoporphyrin hydroxide (*formerly called* ferriprotoporphyrin IX hydroxide); hydroxo(protoporphyrinato) iron(III); hydroxoiron(III) protoporphyrinate. *Compare* **heme** (def. 1), **hemin** (def. 1). **2** *the generic name for* any hydroxo(porphyrinato)iron(III) coordination complex.



hemato+ *or (before a vowel)* **hemat+** *comb. form* denoting blood. *Also (esp. Brit.)*: **haemato+**, **haemat+**. *See also* **hemo+**.

hematocrit *or (esp. Brit.)* **haematocrit** **1** *or* **packed red cell volume** the proportion of the volume of a sample of blood that is represented by the red blood cells. **2** an apparatus, essentially a graduated centrifuge tube, used to determine the proportion of the volume of a sample of blood that is represented by the red blood cells.

hematocrit technique a method for the rapid isolation of mitochondria or other particles, in which they are separated from the medium by centrifugation through a layer of silicone fluid. The latter is immiscible with water, and of a density intermediate between that of the particles to be separated and that of the medium. A high-density aqueous 'fixative' beneath the silicone layer can be used to stabilize labile compounds in the mitochondria or other particles. *Compare* **hematocrit** (def. 2).

hematology *or (esp. Brit.)* **haematology** the branch of medicine concerned with diseases of the blood or of the blood-forming tissues.

hematolysis *or (esp. Brit.)* **haematolysis** *an alternative name for* **hemolysis**.

hematopoiesis *or (esp. Brit.)* **haematopoiesis** *an alternative name for* **hemopoiesis**.

hematoporphyrin *or (esp. Brit.)* **haematoporphyrin** *or (formerly)* **hematoporphyrin IX** *or* (*esp. Brit.*) **haematoporphyrin IX** *the trivial name for* 2,7,12,18-tetramethyl-3,8-bis(1-hydroxyethyl) porphyrin-13,17-dipropionic acid; the porphyrin formed from **heme** (def. 1) or a heme-containing protein on treatment with hydrogen bromide in glacial acetic acid.



hematoside *or (esp. Brit.)* **haematoside** a **ganglioside**, NeuAc(α2-3)Gal(β1-4)Glc(β1-1)Cer, found in red blood cells.

hematoxylin *or (esp. Brit.)* **haematoxylin** 7,11b-dihydrobenz[*b*]indeno[1,2-*d*]pyran-3,4,6*a*,9,10(6*H*)-pentol; a dye isolated from the heartwood of logwood, *Haematoxylon campechianum* L. Colourless or yellowish, it turns red on exposure to light, and is used as a stain in microscopy.



hematuria *or (esp. Brit.)* **haematuria** the presence of red blood cells in the urine. It can be due to lesions in the urinary tract, but also to glomerular disease of the kidney.

heme *or (esp. Brit.)* **haem** **1** *or* **ferroheme** *or* **ferrohaem** *or* **protoheme** *the trivial name for* **ferroprotoporphyrin** (*formerly called* ferroprotoporphyrin IX); 2,7,12,18-tetramethyl-3,8-divinylporphyrin- 13,17-dipropionic acid iron(II) coordination complex. It occurs free and as the prosthetic group of a number of hemoproteins, e.g. hemoglobins, erythrocruorins, myoglobins, some peroxidases, catalases, and cytochromes *b*. *Compare* **hematin** (def. 1), **hemin** (def. 1). **2** *the generic name for* any iron–porphyrin coordination complex irrespective of the valence state of the iron atom (which may be specified). The name of an individual heme is derived from that of the corresponding porphyrin; e.g., cytoheme, from cytoporphyrin, and ferroprotoheme, from protoporphyrin. For biosynthesis, *see* **tetrapyrrole**.



heme (def. 1)

heme–heme interaction *or (esp. Brit.)* **haem–haem interaction** the cooperative interaction between dioxygen binding sites that occurs when dioxygen binds to hemoglobin; as oxygenation proceeds, the combination of additional dioxygen molecules is made easier.

heme oxygenase *abbr.*: HO; EC 1.14.99.3; a microsomal enzyme, mostly of liver and spleen, that converts heme (in the presence of O_2) to α-hydroxyhemin, which converts noncatalytically to biliverdin and carbon monoxide. It requires NADPH and NADPH–hemoprotein reductase (EC 1.6.2.4). Three isozymes are known of which HO 1 is heme-inducible. Deficiency of HO 1 (encoded at 22q22.1) is very rare and is associated with severe anemia, high levels of circulating heme, enhanced endothelial cell damage, and early death.

heme pocket *or (esp. Brit.)* **haem pocket** a hydrophobic crevice in the tertiary structure of myoglobin, or hemoglobin subunit, into which the heme group fits. The non-polar vinyl side chains of the heme are buried in the interior of the pocket, while the hydrophilic propionate side-chains project out of the pocket towards the surface of the molecule.

heme protein *or (esp. Brit.)* **haem protein** *an alternative name for* **hemoprotein**.

hemerythrin *or (esp. Brit.)* **haemerythrin** an oxygen carrier found in a few groups of invertebrates, e.g. sipunculid worms, certain molluscs and crustaceans. It is a non-heme, iron-containing protein, the subunits of which each contain about 113 amino-acid residues. Each monomer has an active site containing two atoms of Fe(II), 0.34 nm apart, between which a dioxygen molecule is thought to fit. The molecule is a homooctamer.

heme synthetase *see* **ferrochelatase**.

heme–thiolate protein *or (esp. Brit.)* **haem–thiolate protein** *see* **P450**.

hemi+ *prefix* denoting half, or affecting one half. *Compare* **semi+**.

hemiacetal *see* **acetal**.

hemicellulose any or all of the cell-wall polysaccharides that are extractable from wood or other plant material with aqueous alkali (in which cellulose itself is insoluble). Hemicelluloses are chiefly xylans, but other homoglycans or heteroglycans containing hexose and/or pentose residues, uronic acid-containing xylans, and other **pectic substances** may also be present.

hemicystine *an alternative name for* **half-cystine**.

hemicystyl *an alternative name for* **half-cystyl**.

hemidesmosome a specialized cell junction between an epithelial cell and its underlying basal lamina. These resemble **desmosomes** morphologically but are chemically and functionally distinct. Between the cell membrane and the underlying connective tissue is a specialized mat of extracellular matrix sometimes known as the linker. The transmembrane linker proteins belong to the **integrin** family of extracellular matrix receptors rather than the **cadherin** family of cell–cell adhesion proteins found in desmosomes.

hemidiaphragm a muscle preparation widely used for metabolic studies *in vitro*, consisting of either of the two excised and separated left and right halves of the diaphragm, usually from a rat.

hemiketal *see* **acetal**.

Hemimetabola *or* **Exopterygota** one of the two divisions of the subclass Pterygota, comprising those insects, e.g. cockroaches, locusts, and grasshoppers, in which the juvenile forms resemble the adults, except for their lack of fully developed wings. Such insects undergo incomplete metamorphosis. *Compare* **Holometabola**.

hemin *or (esp. Brit.)* **haemin 1** *or* **ferriheme chloride** *or* **protohemin** *the trivial name for* ferriprotoporphyrin chloride (*formerly called* ferriprotoporphyrin IX chloride); chloro(protoporphyrinato) iron(III); chloroiron(III) protoporphyrinate. *Compare* **heme** (def. 1), **hematin** (def. 1). **2** *the generic name for* any chloro(porphyrinato)-iron(III) coordination complex.

hemiplegic migraine a rare familial autosomal dominant form of migraine that is marked by transient hemiplegia during the aura. It is caused by several point mutations in a gene at 19p13 for the α1A subunit (CACNA1A, calcium channel alpha subunit 1A) of a voltage-gated calcium channel present in neurons. The protein contains 2261 amino acids, with four repeated domains each containing four transmembrane segments, and a polyglutamine tract in the C-terminal region. Expansion of this tract leads to episodic ataxia and to spinocerebellar ataxia type 6.

hemiport a model of translocation of solutes across membranes, based on the possibility that there is interaction through the membrane between superficially disposed protein subunits. These subunits are envisaged as being embedded within the bimolecular lipid layer, anchored to the aqueous phase, and perhaps mobile in the plane of each face of the membrane. The subunits bind the solute in question and, when associated with the symmetrical protein at the opposite face of the membrane, transfer the solute across the membrane.

hemithioacetal *see* **acetal**.

hemithioketal *see* **acetal**.

hemizygous describing an organism in which a gene is present only once in a genotype, as a gene in a haploid cell or organism, a sex-linked gene in the heterogametic sex, or a gene in a segment of chromosome in a diploid cell or organism where its partner segment has been deleted. **—hemizygosity** *n.*

hemo+ *or* **hema+** *or (before a vowel)* **hem+** *comb. form* denoting blood. *Also (esp. Brit.)*: **haemo+**, **haema+**, **haem+**. *See also* **hemato+**.

hemochromatosis *or (esp. Brit.)* **haemochromatosis** an iron overload disease of humans characterized by widespread, massive accumulation of tissue iron and pathological changes of tissue structure and function. **Primary hemochromatosis** results from increased absorption of iron from a normal diet. This is usually caused by autosomal recessive mutations in the gene for HFE, an HLA-type protein (321 amino acids) that binds β_2-microglobulin and associates with the transferrin receptor in the gastrointestinal tract. About 10% of persons of European descent are heterozygotes for such mutations. More rarely, mutations in the transferrin receptor, or autosomal dominant mutations in the genes for ferritin H subunit or ferroportin, are the cause. **Secondary hemochromatosis** results from an increased intake and accumulation of iron secondary to other causes. *Compare* **hemosiderosis**.

hemochrome *or (esp. Brit.)* **haemochrome** any iron–porphyrin coordination complex with one or more strong-field axial ligands (e.g., pyridine).

hemochromogen *or (esp. Brit.)* **haemochromogen** any compound of heme with a nitrogenous base, such as a protein (whether native or denatured) or pyridine, typically with two absorption bands in the green part of the visible spectrum. *See also* **chromogen**.

hemocuprein *or (esp. Brit.)* **haemocuprein** *an alternative name for* **superoxide dismutase**.

hemocyanin *or (esp. Brit.)* **haemocyanin** a blue, copper-containing oxygen carrier present in many molluscs and arthropods. It is a non-heme protein that binds one dioxygen molecule for two Cu(I) atoms; the dioxygen molecule is thought to form a bridge between the two copper atoms. The oxygenated compound is bright blue, with an intensity of light absorption 5–10 times that of other known copper complexes. For example, hemocyanin from lobster, *Panulirus interruptus,* is a hexamer of a number of different chains, of which A, B (88% identity between these two), and C have been identified.

hemocyte *or (esp. Brit.)* **haemocyte** any blood cell, especially of an invertebrate animal.

hemocytometer *or (esp. Brit.)* **haemocytometer** an apparatus for counting the number of cells in a known volume of blood. It consists of a slide with a chamber of known depth; the base of the chamber is ruled with a graticule over which the cells can be enumerated under a microscope.

hemodialysis *or (esp. Brit.)* **haemodialysis** the process of separating low-molecular-mass solutes from blood by **dialysis** through a semipermeable membrane, as in an artificial kidney machine.

hemoglobin *or (esp. Brit.)* **haemoglobin** *symbol*: Hb; any of a group of red, iron-containing, oxygen-carrying pigments of the blood of vertebrates and some invertebrates; hemoglobin also occurs in the root nodules of leguminous plants. All vertebrate hemoglobins consist of two pairs of associated **globin** polypeptide chains, each chain carrying a heme prosthetic group bound non-covalently, the iron atom of which is in the ferrous state and forms a coordination complex with the pyrrole nitrogens. All normal human hemoglobins contain one pair of 15.7 kDa α chains, of 141 amino-acid residues, and a pair of varying 16.5 kDa polypeptide chains, of 146 amino-acid residues and of similar amino-acid sequence. In adult human blood, 98% of the total hemoglobin is Hb A (or Hb A_1), containing a pair of β chains (i.e., it has composition $\alpha_2\beta_2$) and 2% is Hb A_2, containing a pair of δ chains (i.e., $\alpha_2\delta_2$). In fetal blood, from about 10 to 30 weeks of gestation, >90% of the hemoglobin is Hb F, containing a pair of γ chains (i.e., $\alpha_2\gamma_2$). In embryonic blood, the second pair of chains are ε chains (i.e., the structure is $\alpha_2\varepsilon_2$). Each of the four heme groups in a hemoglobin molecule is able to combine reversibly with one dioxygen molecule; the oxygen-saturation curve of hemoglobin is sigmoidal, showing that there is positive cooperativity between the subunits. The hemoglobin molecule has a two-fold axis of symmetry, each half containing one α chain and one non-α chain; the overall shape of the molecule is globular, with the heme groups buried in pockets in the polypeptide chains. There are eight helical regions, designated A to G. The histidine at position F8 (i.e., the eighth residue in helix F) is the fifth ligand of the heme Fe(II). Upon oxygenation, dioxygen becomes the sixth ligand of Fe(II), and is also hydrogen bonded to HisE7, with an accompanying conformational change. In the absence of the correct bonding with the globin side chains, Fe(II) autooxidizes to Fe(III) and can no longer bind dioxygen. Among human α chain variants are Luxembourg, Ann Arbor, and Hirosaki. Among the **hemoglobinopathies** associated with β-chain variants is **sickle-cell anemia**. In those invertebrates that have hemoglobin (not **hemocyanin**), the protein is polymeric: *e.g.*, in earthworm hemoglobin, 12 subunits are arranged in a hexagonal bilayer structure of 3.8 MDa, each subunit of which is composed primarily of disulfide-linked trimers (chains A, B, and C) and monomers (chain D). *See also* **hemoglobin A_{1c}**.

hemoglobin A_{1c} *or (esp. Brit.)* **haemoglobin A_{1c}** *abbr.*: Hb A_{1c}; the most abundant of the **glycated hemoglobins**, which are present in normal adult hemoglobin as minor components (together, they represent 3–5% of the total hemoglobin of the erythrocyte). Hb A_{1c} is formed from Hb A_1 subsequent to biosynthesis by glycosylation of one of the two β chains, by a non-enzymic mechanism involving formation of an N-substituted aldimine (Schiff's base) between the amino group of the peptide chain and the aldehyde group of glucose, followed by an **Amadori rearrangement** to the corresponding N-substituted ketoimine (aminodeoxyfructose derivative) (*see also* **Maillard reaction**). In inadequately controlled **diabetes mellitus**, the steady-state concentration of Hb A_{1c} in serum is 2–3 times higher than normal, possibly reflecting an abnormally high mean blood glucose concentration during the preceding few months. Other glycosylated hemoglobins change very little in concentration in diabetes; thus, measurement of serum levels of Hb A_{1c} is considered to be useful in assessing the degree of control of the condition.

hemoglobinopathy *or (esp. Brit.)* **haemoglobinopathy** any genetic disorder involving globin, the protein moiety of **hemoglobin**. These are classified into **thalassemia** syndromes, caused by defective synthesis of the component polypeptides of globin, and conditions that arise from mutations leading to amino-acid substitutions in the polypeptide chains. Of the latter there are over 850 known variants, including the classically important **sickle cell** hemoglobin. Many changes lead to increased oxygen affinity, e.g. Hb Rainier (β-145, Tyr → Cys), while in others decreased oxygen affinity occurs, e.g. Hb Kansas (β-102, Asn → Thr). Many substitutions lead to an unstable hemoglobin molecule, as in Hb Hammersmith (β-42, Phe → Ser) where the important heme contact of the phenylalanine is lost, leading to the formation of **ferrihemoglobin**, or in Hb Bristol (β-67, Val → Asp) where replacement of the nonpolar valine by aspartic acid causes distortion of the E helix. Some substitutions lead to congenital methemoglobinemia, as in Hb MBoston (α-58, His → Tyr) and Hb MSaskatoon (β-63, His → Tyr). Some variant globins are elongated whereas others are shortened.

hemolin *or (esp. Brit.)* **haemolin** an insect hemolymph protein of the immunoglobulin superfamily, containing four internal immunoglobulin-type repeats. It is induced by bacteria.

hemolymph *or (esp. Brit.)* **haemolymph** a fluid occurring in the secondary body cavity (coelom) of some invertebrates, considered as functionally equivalent to the blood and lymph of higher animals.

hemolysate *or (esp. Brit.)* **haemolysate** a preparation obtained by lysis of erythrocytes.

hemolysin *or (esp. Brit.)* **haemolysin** **1** any substance, e.g. an antibody, that causes hemolysis. **2** any bacterial exotoxin that ruptures blood-cell membranes. In hemolytic *Escherichia coli* strains that cause predominantly nongastrointestinal (e.g. urinary tract) infections, four genes are involved: *hlyA* encodes hemolysin (Ca^{2+}-binding toxin); *hlyB* encodes an **ABC transporter** for HlyA export; *hlyC* encodes a protein involved in hemolysin export; and *hlyD* encodes a transmembrane protein component of the HlyA export system. *Staphylococcus aureus* secretes **α-hemolysin**, a protein (293 amino acids) that binds erythrocytes and some other cells. It forms a mushroom-shaped homoheptameric channel to which each subunit contributes two antiparallel beta strands. It is responsible for the hemolysis seen around colonies grown on blood agar plates.

hemolysis *or (esp. Brit.)* **haemolysis** the lysis of red blood cells, either *in vivo* or *in vitro*. —**hemolyse** *or* **haemolyse** *vb.*

hemolytic *or (esp. Brit.)* **haemolytic** **1** of, or pertaining to **hemolysis**. **2** an agent or condition that causes hemolysis.

hemopexin *or (esp. Brit.)* **haemopexin** a 57 kDa β_1-glycoprotein of human blood serum with one high-affinity binding site for **heme** (def. 1). The heme complex can be reduced with dithionite to give a three-band absorption spectrum characteristic of ferrohemochrome. Hemopexin may be necessary for heme to be taken up and degraded in the liver.

hemophilia *or (esp. Brit.)* **haemophilia** any of various hereditary disorders in which there is a deficiency or defect in certain of the **blood coagulation** factors resulting in prolonged bleeding following injury. Classical hemophilia, or **hemophilia A**, is a condition in which the blood has a prolonged clotting time due to an abnormally slow conversion of prothrombin to thrombin. It is caused by a functional deficiency of antihemophilic factor (factor VIII), inherited as an X-linked recessive trait. Other deficiencies in the blood coagulation system, e.g. **Christmas disease**, or **hemophilia B**, due to a deficiency of factor IX, produce similar clinical pictures.

hemopoiesis *or* **hematopoiesis** the process of blood formation, especially the formation of blood cells, occurring mainly in bone marrow. *Also (esp. Brit.)*: **haemopoiesis**, **haematopoiesis**. —**hemopoietic**, **hematopoietic** *or* **haemopoietic**, **haematopoietic** *adj.*

hemoprotein *or* **heme protein** any protein to which an iron–porphyrin compound is linked in a stoichiometric manner. Hemoproteins include hemoglobins, myoglobins, cytochromes, catalase, and some peroxidases. *Also (esp. Brit.)*: **haemoprotein**, **haem protein**.

hemorphin *or (esp. Brit.)* **haemorphin** any of a group of hemoglobin- derived peptides with affinity for opioid receptors.

hemorrhage *or (esp. Brit.)* **haemorrhage** bleeding; the escape of blood from a ruptured blood vessel, either externally or internally. —**hemorrhagic** *or (esp. Brit.)* **haemorrhagic** *adj.*

hemorrhagic toxin C and D *see* **atrolysin C**.

hemosiderin *or (esp. Brit.)* **haemosiderin** an insoluble, granular, ill-defined complex formed by the denaturation of **ferritin**, with associated loss of apoferritin and micellar aggregation; about one third of its mass is iron. Hemosiderin occurs in liver, spleen, and red bone marrow, its amount increasing with increased iron content of the body. It is responsible for the histochemical staining of tissue by the Prussian Blue reaction, a deep-blue ferric ferrocyanide ($Fe_{III}[Fe_{II}(CN)_6]$). The distribution of stored iron is shifted from ferritin to hemosiderin in direct correlation with ascorbic acid deficiency. *See* **iron overload**.

hemosiderosis *or (esp. Brit.)* **haemosiderosis** an abnormal increase in tissue iron content due to some defect in the control of iron turnover in the body or to increased iron ingestion. In a rare pulmonary form, recurrent bleeding into the lungs loads the macrophages with hemosiderin and produses diffuse fibrosis. Hepatic hemosiderosis is common in alcoholic cirrhosis. *Compare* **hemochromatosis**.

hemostasis *or (esp. Brit.)* **haemostasis** **1** the stopping of bleeding or the arrest of the circulation to an organ or part. **2** the stagnation of blood in an organ or part.

hemostat *or (esp. Brit.)* **haemostat** a device or a chemical agent that stops or retards bleeding.

hemostatic *or (esp. Brit.)* **haemostatic** **1** of, relating to, or functioning to cause **hemostasis** (def. 1). **2** a drug or other agent that retards or stops bleeding.

Henderson–Hasselbalch equation an equation relating pH to the composition of buffer solutions:

$$pH = pK_A + \log([\text{conjugate base}]/[\text{acid}]),$$

where pK_A is the common logarithm of the acid dissociation constant of the buffer acid. The following approximation is often used:

$$pH = pK_A + \log([\text{salt}]/[\text{acid}]).$$

[After Lawrence Joseph Henderson (1878–1942), US physician and biochemist, and Karl A. Hasselbalch (1874–), Danish biochemist, who together formulated the equation in 1910.]

henna a preparation obtained from the dried and powdered leaves of *Lawsonia alba*, *L. inermis*, or *L. spinosa*, widely used for dyeing hair and fingernails. The active ingredient is **lawsone**.

henry (*pl.* **henrys** *or* **henries**) *symbol*: H; the SI derived unit of inductance, equal to the inductance of a closed circuit with a **magnetic flux** of 1 weber per ampere of current,

$$H = Wb\,A^{-1}\,s = m^2\,kg\,s^{-2}\,A^{-2}$$

[After Joseph Henry (1797–1878), US physicist.]

Henry's function a function used in the theoretical treatment of the electrophoretic mobility of macromolecules that is dependent on the radius of the macromolecule, r, and its reciprocal ion-atmosphere radius, κ (derived from **Debye–Hückel theory**). It varies between 1.0 and 1.5 as κr goes from zero to infinity.

Henry's law the principle that the concentration of a gas in solution, at constant temperature, is directly proportional to the partial pressure of the gas in the vapour phase in equilibrium with that solution. It holds with high precision for gases of low solubility at pressures below approximately 10^5 Pa. It may be expressed by: $c_G = kp_G$, where c_G is the molar concentration of the gas in solution, p_G is the partial pressure of the gas in the gas phase, and k is a proportionality constant. [After William Henry (1774–1836), British chemist.]

HEPA filter a high-efficiency particulate air filter used, for example, in removing bacteria and other particulates from air in safety cabinets.

heparan any polysaccharide derived by desulfation of **heparan sulfate** or **heparin**.

heparan sulfate any member of a group of glycosaminoglycans that have repeat units consisting of alternating $\alpha 1 \rightarrow 4$-linked hexuronic acid and glucosamine residues, the former being a mixture of sulfated and nonsulfated D-glucuronic and L-iduronic acids, and the latter being either sulfated or acetylated on its amino group as well as sulfated on one of its hydroxyl groups. They usually occur attached to protein to form proteoglycans, the mode of attachment being through a xylose residue as in **chondroitin sulfates**. Heparan sulfate accumulates in a number of the mucopolysaccharidoses, e.g. Hunter syndrome, Hurler syndrome, and Sanfilippo syndrome. *See* **mucopolysaccharidosis**. *See also* **heparin**.

heparan sulfate proteoglycan core protein *abbr.*: HSPG core protein; any of a group of modular heparan sulfate proteoglycan proteins with three heparan sulfate chains. Also known as **perlecans**, they contain domains that share similarity with the low-density lipoprotein receptor, epidermal growth factor, laminin and neural cell adhesion molecule, and have 15 immunoglobulin-like domains.

heparin any glycosaminoglycan found mainly in mast cells. Heparins are similar to **heparan sulfates** but somewhat larger (6–20 kDa) and with fewer *N*-acetyl groups and more *N*-sulfate and *O*-sulfate groups; they are proteoglycans. They consist predominantly of alternating $\alpha 1 \rightarrow 4$-linked D-galactose and *N*-acetyl-*D*-glucosamine-6-sulfate residues. Heparins are secreted into the bloodstream by the mast cells of liver, lung, and other tissues; they act as inhibitors of blood clotting by activating **antithrombin III**. Commercial heparins are protein-free.

heparin cofactor II a plasma glycoprotein that is homologous with **antithrombin III** but, of the proteases involved in coagulation, only inhibits thrombin. Its physiological role is obscure, but its activity is stimulated by dermatan sulfate and by heparin. The gene at 22q11 encodes 480 amino acids.

heparinize *or* **heparinise** to treat with a preparation of **heparin**, usually as its sodium or lithium salt, in order to prevent clotting, either *in vivo* or *in vitro*, of blood or blood plasma. **—heparinization** *or* **heparinisation** *n.*

hepat+ *a variant form of* **hepato+** (before a vowel).

hepatectomy surgical removal of the liver. In **partial hepatectomy**, only some of the lobes of the liver are removed; this causes the remaining lobes to regenerate so that the liver *in toto* regains its former weight. **—hepatectomize** *or* **hepatectomise** *vb.*

hepatic of, or pertaining to, the liver.

hepatic lipase EC 3.1.1.3; an enzyme that hydrolyses triacylglycerols and phosphoproteins present in chylomicron and very-low-density lipoprotein remnants. It is a glycoprotein synthesized and secreted by hepatocytes, and binds to proteoglycans on hepatocyte surfaces and on sinusoidal endothelial cells. It also binds LDP (LDL receptor-like protein). The gene at 15q21 encodes 499 amino acids. Rare inactivating mutations in the gene result in an autosomal recessive syndrome of hepatic lipase deficiency.

hepatitis any inflammatory disease of the liver. In humans the most common cause is infection with a virus or an amoeba. Hepatitis A is caused by a single-stranded RNA **picornavirus**, for which there is a killed virus vaccine, virus having been grown in tissue culture. Hepatitis B is caused by a double-stranded DNA virus of the Hepadnaviridae family forming a spherical virion often referred to as the **Dane particle**. It is especially virulent and is associated with the development of primary liver tumours – the incidence of these is particularly high in China. The antigens may be in the form of spherical particles designated HBsAg; principal components include gp27, which is a glycosylated form of p24, and a 42 kDa protein. HBsAg is produced in recombinant yeast, the particles being similar to those found in the plasma of infected individuals and providing a very effective vaccine. Hepatitis C, formerly called 'non-A non-B', is caused by a single-stranded RNA virus, for which there is no vaccine. Hepatitis D virus is a satellite virus of hepatitis B virus and contains a circular single-stranded RNA genome (≈1700 nt). Its replication requires the antigen HDAg – the only protein encoded by the virus – and RNA polymerase II. HDAg-S (195 amino acids) activates replication of the virus. HDAg-L is the former with a 19-residue C-terminal extension; it inhibits replication and directs assembly of the virion. HDAg-S shares 21% sequence identity with NELF-A. Other forms are hepatitis E, F, and G.

hepato+ *or (before a vowel)* **hepat+** *comb. form* denoting of or pertaining to the liver.

hepatocarcinogen any **carcinogen** that acts specifically or primarily on liver.

hepatocellular of, or pertaining to **hepatocytes**.

hepatocyte *or (formerly)* **parenchymal liver cell** the major (but not the only) cell type of the liver. They are arranged in folded sheets facing blood-filled spaces called sinusoids. Hepatocytes are responsible for the synthesis, degradation, and storage of a wide range of substances. They are the site of synthesis of all the plasma proteins, except for antibody, and are the site of storage of **glycogen**.

hepatocyte growth factor *abbr.*: HGF; *other name*: scatter factor; a **cytokine** produced by platelets, fibroblasts, macrophages, endothelial cells, and smooth muscle cells that is a potent **mitogen** for hepatocytes, epithelial cells, keratinocytes, melanocytes, and hematopoietic precursor cells. It is a glycoprotein, with four **kringle** domains and no known protease activity. The molecule is a disulfide-linked dimer of α (463 amino acids) and β (234 amino acids) subunits, which are derived from a common precursor.

hepatocyte growth factor receptor a type I membrane protein that binds **hepatocyte growth factor** and mediates its intracellular action by a protein tyrosine kinase (EC 2.7.1.112) activity on its intracellular domain. It is encoded by the *MET* protooncogene, and comprises a dimer of two subunits, α and β. *See also* ***tpr-met***.

hepatocyte nuclear factor *abbr.*: HNF; any of several transcription factors involved in activation of numerous liver-specific genes. Some are also present in pancreatic islet cells. **HNF-1α** is a homeobox transcription factor that requires dimerization cofactor (DCoH; *see* **pterin-4α-carbinolamine dehydratase**) for dimerization and stabilization. Numerous mutations in HNF-1α are associated with maturity-onset diabetes of the young (MODY) type 3. **HNF-**

1β is homologous with HNF-1α, and also requires DCoH for dimerization and stabilization. Several mutations are associated with MODY type 5. **HNF-4α** belongs to the nuclear receptor superfamily, and is a major regulator of hepatic gene expression and of HNF-1α. Mutations are associated with MODY type 1.

hepatoflavin *or* **hepatoflavine** *a former name for* **riboflavin**.

hepatolenticular degeneration *an alternative name for* **Wilson's disease**.

hepatoma any **carcinoma** derived from liver cells.

hepatopancreas a digestive gland, found in many invertebrates, that performs functions similar to those of the liver and the pancreas in vertebrates.

hepatosis any noninflammatory disease of the liver.

hepatotoxin any toxin that acts specifically or primarily on the liver.

hepcidin a peptide hormone with antimicrobial activity that regulates uptake and storage of iron. Elevated levels of hepcidin are associated with iron deficiency.

Hepes *or* **HEPES** *abbr. for (and trivial name of)* 4-(2-hydroxyethyl)-1-piperazine-ethanesulfonic acid; a **Good buffer substance**, pK_a (20°C) = 7.55.



HepG2 a cell line derived from a patient with primary liver cancer.

hephaestin a membrane-bound homologue of ceruloplasm that is required, with **ferroportin**, for the transport of iron across the basolateral plasma membrane of mucosal cells of the upper small intestine. It appears to act as a ferroxidase ($Fe^{2+} \rightarrow Fe^{3+}$) in the process. A hereditary sex-linked anemia occurs in mice in which the gene is mutated.

HEPN domain *abbr. for* higher eukaryotes and prokaryotes nucleotide-binding domain; a protein sequence (≈110 amino acids) whose prototype is in the C-terminal region of **sacsin**. It is present in proteins from several vertebrates and many eubacteria and archaea. Because it is similar to a domain present in many kanamycin nucleotidyltransferases it is thought to mediate nucleotide binding.

hepoxilin *abbr.*: Hx; any of various epoxyhydroxy metabolites of 12-hydroperoxyeicosatetraenoate, e.g. 13-hydroxy-14,15-epoxyeicosatetraenoate. A number of sites of formation have been reported, with activities including modulation of neurotransmission in brain and release of insulin in pancreatic islets.

hepoxilin-epoxide hydrolase EC 3.3.2.7; an enzyme that converts (5*Z*,9*E*,14*Z*)-(8ζ,11*R*,12*S*)-11,12-epoxy-8-hydroxyeicosa-5,9,14-trienoate (**hepoxilin** A_3) to the trioxilin, (5*Z*,9*E*,14*Z*)-(8ζ,11ζ,12*S*)-8,11,12-trihydroxyeicosa-5,9,14-trienoate (trioxilin A_3).

Hepps *or* **HEPPS** *or* **EPPS** *abbr. for (and trivial name of)* 4-(2-hydroxyethyl)-1-piperazinepropanesulfonic acid; a **Good buffer substance**, pK_a (20°C) = 8.0.



Heppso *or* **HEPPSO** *abbr. for (and trivial name of)* 4-(2-hydroxyethyl)-1-piperazine-(2-hydroxypropanesulfonic acid); a **Good buffer substance**, pK_a (25°C) = 7.8.



hepsin EC 3.4.21.–; a serine protease, similar to other trypsin-like enzymes, that is a type II membrane protein. It is required for growth and maintenance of cell morphology in many tissues.

hepta+ *or (before a vowel)* **hept+** *comb. form* denoting seven.

heptad a seven-residue pseudorepeat in an alpha-helical segment of a polypeptide. In coiled coils, positions a and d of the heptad contain nonpolar residues. In leucine zippers, position g contains leucine.

heptanoate 1 the anion, $CH_3–[CH_2]_5–COO^–$, derived from heptanoic acid (formerly enanthic acid). **2** any salt or ester of heptanoic acid.

heptanoyl *symbol*: Hpo; the univalent acyl group, $CH_3–[CH_2]_5–CO–$, derived from heptanoic acid.

heptitol any **alditol** having a chain of seven carbon atoms in the molecule.

heptose any **aldose** having a chain of seven carbon atoms in the molecule.

heptulose any **ketose** having a chain of seven carbon atoms in the molecule.

heptyl *symbol*: Hp; the alkyl group, $CH_3–[CH_2]_5–CH_2–$, derived from heptane.

heptyl glucoside *n*-heptyl *β*-D-glucopyranoside; a nonionic detergent, CMC 79 mM.

heptyl thioglucoside *n*-heptyl 1-thio-*β*-D-glucopyranoside; a nonionic detergent; the CMC, 30 mM, remains unchanged between 1 and 20°C.

HER2 *see* ***neu***.

herbicide any chemical substance that destroys plants or inhibits their growth, especially one used to control weeds.

hereditary of, pertaining to, or caused by **heredity**; inherited.

hereditary angioedema *or* **angioneurotic edema** *or* **C1 inhibitor deficiency** an autosomal dominant condition characterized by episodes of swelling, primarily of the face, extremities, larynx, or abdomen. The attacks may be triggered by emotional stress and can prove fatal. It is caused by deficiency of **C1 inhibitor**, which may be absent (in type I disease) or some 30% of normal (in type II). The C1 inhibitor gene at 11q11 contains 17 Alu sequences, which mediate the gene deletions responsible for most type I cases. Mutations that lead to a dysfunctional protein are common in type II disease.

hereditary disease any pathological condition that is caused by the presence in the organism of an abnormal gene.

hereditary fructose-bisphosphatase deficiency an inherited autosomal recessive condition in humans characterized by less than 20% of normal activity of **fructose-bisphosphatase** (EC 3.1.3.11). It is characterized in infants by episodic spells of hyperventilation, apnoea, hypoglycemia, ketosis, and lactic acidosis. Surviving infants appear to become normal, but gluconeogenesis in their livers is severely impaired, and when glycogen stores are depleted, amino acids, lactate, and ketones accumulate. Subjects are not sensitive to fructose intake. *Compare* **hereditary fructose intolerance**.

hereditary fructose intolerance a condition in humans, inherited as an autosomal recessive character, in which there is a deficiency of the aldolase-B isoenzyme of **fructose-bisphosphate aldolase** (EC 4.1.2.13) (there is less than 15% normal activity with fructose 1-phosphate as substrate but activity is less depressed with fructose 1,6-bisphosphate as substrate) while the levels of aldolases A and C are normal (*see* **aldolase** (def. 2)). The condition is characterized by severe hypoglycemia and vomiting shortly after fructose intake. In this condition prolonged fructose ingestion in infants leads to poor feeding, vomiting, hepatomegaly, jaundice, hemorrhage, proximal-renal-tubule syndrome, and death. The hypoglycemia ensuing after fructose ingestion is caused by fructose 1-phosphate inhibition of glycogenolysis at the phosphorylase level and of gluconeogenesis at the mutant aldolase level. *Compare* **hereditary fructose-bisphosphatase deficiency**.

hereditary hemorrhagic telangiectasia *see* **activin receptor-like kinase 1**.

hereditary multiple exostoses *abbr.*: HME; *other names:* multiple osteochondromata; osteochondromatosis; diaphyseal aclasis; familial bony spurs. An inherited disease in which numerous exostoses (bony spurs) develop (usually around the knee, but also at the shoulder, wrist, and on the ribs) as a result of a disorder of the growth plate.

hereditary persistence fetal hemoglobin a benign condition in which there is continued production of hemoglobin F in adults. Some cases are caused by deletion of the β- and δ-globin loci. Nondeletion phenotypes are characterized by point mutations in the promoter region of one or the other γ-globin genes.

heredity 1 the transmission from one generation to another of genetic factors that determine the characteristics of an organism. 2 all of the inherited factors in an organism or all the characteristics determined by them.

heregulin *abbr*.: HRG; one of several glycoproteins that bind to the transmembrane tyrosine kinase ErbB2 p185, and stimulate its activity. They are secreted by human breast cancer cells in culture.

hermone *an alternative term for* **hormone** (suggested by E. Schäfer in 1913 as better expressing the concept of chemical messengers).

heroin *see* **diacetylmorphine**, **morphine**.

herpes virus any of a family (Herpesviridae) of enveloped, icosahedral, double-stranded DNA viruses, many of which infect animals. The family includes human herpesviruses types 1 and 2, Epstein–Barr virus, zoster (varicella) virus, pseudorabies virus, cytomegalovirus, Lucke virus, and Marek's disease virus.

herring any marine fish of the family Clupeidae, the flesh of which is comparatively rich in oils with a high content of long-chain *n*-3 **fatty acids**; typical composition (range of major fatty acids, expressed as % of total fatty acids): 16:0, 12–18%; 16:1(*n*-7), 6–8%; 18:1(*n*-9), 11–25%; 20:1(*n*-9), 7–19%; 20:5(*n*-3), 11–15%; 22:6(*n*-3), 5–8%.

Hershey–Chase experiment a seminal experiment, reported in 1952, in which it was demonstrated that when an *Escherichia coli* cell is infected with T2 bacteriophage, the phage DNA is injected into the cell whereas the phage coat protein remains on the outside of the infected bacterial cell. This was shown by demonstrating that most of the ^{35}S-labelled phage protein could be removed from the surface of the bacterial cells by application of a shearing force without removing the ^{32}P-labelled nucleic acid and without interfering with the course of productive infection. The phage nucleic acid could be shown to have moved into the bacterial cell. It was therefore concluded that only the phage DNA was required for infection, indicating that DNA must be the hereditary material. This confirmed earlier experiments in 1944 by Avery and colleagues (*see* **transforming principle**), but was somewhat more readily accepted when Watson and Crick deduced the structure of DNA. [After Alfred Day Hershey (1908–97), US geneticist, and Martha Chase (1927–).]

Hershey circle a circular duplex DNA structure in which each strand contains one interruption and in which the interruptions are not opposite each other. It is formed by some linear, double-stranded DNA molecules (e.g. from *Escherichia coli* phage λ) containing short, complementary single strands (cohesive ends) at each end when these cohesive ends base-pair with each other.

Hers's disease *an alternative name for* type VI **glycogen disease**.

hertz *symbol*: Hz; the SI derived unit of **frequency** of a periodic phenomenon, equal to 1 cycle per second; i.e. 1 Hz = 1 s^{-1}. [After Heinrich Hertz (1857–94), German physicist.]

Hess's law of constant heat summation the statement that the enthalpy change in a chemical reaction is the same whether the reaction takes place in one stage or in more than one stage. [After Germain Henri Hess (1802–50), Genevese-born Russian chemist; known in Russia as German Ivanovich Gess.]

HETE *abbr. for* hydroxyeicosatetraenoate; *see also* **dihydroxyeicosatetraenoate**.

hetero+ *comb. form* 1 other, different, unusual. *Compare* **allo+** (def. 1), **homo+** (def. 1), **iso+** (def. 1), **xeno+** (def. 1). 2 for, from, or directed towards a different species. *Compare* **allo+** (def. 2), **homo+** (def. 2), **iso+** (def. 2), **xeno+** (def. 2). 3 containing atoms, groups, linkages, residues, or subunits of different kinds. 4 being or pertaining to an atom other than the predominant or significant one, especially of a nitrogen, oxygen, or sulfur atom in a ring containing mainly carbon atoms. *Compare* **homo+** (def. 4).

heteroantibody any antibody (including any autoantibody) that is able to react with an antigen derived from another species. *Compare* **isoantibody**.

heteroantigen any antigen derived from one species that is able to stimulate an immune response in another species. *Compare* **isoantigen**.

heteroatom any atom in the chain or ring of an organic compound that is not a carbon atom. —**heteroatomic** *adj.*

heterobifunctional describing any reagent that carries two differing reactive groups. *Compare* **homobifunctional**.

heterocaryon *a variant spelling of* **heterokaryon**.

heterochromatic 1 relating to or possessing more than one colour; relating to light or other electromagnetic radiation of more than one frequency. *Compare* **monochromatic**. 2 of, relating to, or possessing **heterochromatin**.

heterochromatin a condensed form of **chromatin**, occurring in the nucleus at interphase, that stains strongly with basophilic dyes. The DNA of heterochromatin is replicated at a later stage in the cell-division cycle than **euchromatin**. 'Satellite' DNA is associated with heterochromatin, and the sex chromosomes of animals, especially the Y chromosome, contain large regions of heterochromatin. *Compare* **euchromatin**.

heteroconjugation the association between a base and the conjugate acid of a different base through a hydrogen bond. *See* **conjugate acid–base pair**. *Compare* **homoconjugation**.

heterocycle any compound or molecular structure that is **heterocyclic** (def. 1); a **heterocyclic** (def. 2).

heterocyclic 1 describing any cyclic molecular structure containing atoms of at least two different elements in the ring or rings; describing any compound having such a structure. *Compare* **carbocyclic** (def. 1), **homocyclic** (def. 1). 2 *or* **heterocycle** any such compound.

heterocyst any of the clear cells that occur at intervals on the filaments of certain cyanobacteria. They are usually the sites of nitrogen fixation in species that carry out the reaction. They have thickened cell walls and lack photosystem II and oxygenic photosynthesis.

heterodetic describing a cyclic peptide in which the ring consists of amino-acid residues only, but the linkages forming the ring are not solely eupeptide bonds; one (or, if non-proximate, more than one) is an isopeptide, disulfide, ester, or other bond. *Compare* **homodetic**.

heterodimer any molecular structure in which two nonidentical subunits are associated. *Compare* **dimer**, **homodimer**.

heteroduplex 1 any double-stranded DNA in which the two strands do not have completely complementary base sequences. In a **mutational heteroduplex** a mutational event has occurred in one of the polynucleotide chains; such a molecule does not produce uniform progeny on replication. A **recombinational heteroduplex** is a double-stranded DNA molecule that gives rise to one parental and one recombinant molecule of DNA in the reproductive cycle that immediately follows its production. Heteroduplex DNA may also arise from annealing DNA single strands *in vitro*. 2 a DNA–RNA hybrid. *Compare* **homoduplex**.

heteroduplex analysis a method of detecting mutations by the formation of heteroduplex DNA from complementary but nonidentical DNA strands. When a single-stranded DNA molecule anneals to one in which there is a mismatch at one or more base pairs, the resultant heteroduplex has an electrophoretic mobility that is lower than those of homoduplexes formed from the wild-type or the mutant sequences.

heteroduplex mapping the physical mapping of the base sequence homology of two DNA molecules. It is accomplished after the *in vitro* formation of a hybrid double-stranded molecule, in which one polynucleotide strand is from one of the DNA molecules and the complementary polynucleotide strand is from the other. Unpaired single-stranded regions are located and measured by electron microscopy.

heterogametic describing the sex whose cell nuclei contain a pair of dissimilar **sex chromosomes**. The heterogametic sex is usually male in mammals but is female in the Lepidoptera, birds, reptiles, some amphibians and fishes, and a few plants. *Compare* **homogametic**.

heterogeneous 1 differing in kind, as in a heterogeneous population. 2 describing a group of molecules that is not uniform with respect to size, charge, structure, or other property. 3 describing a system consisting of two or more phases. *Compare* **heterogenous**. —**heterogeneity** *n.*

heterogeneous catalysis any catalytic system in which the catalyst constitutes a different phase from that of the reactants. *Compare* **homogeneous catalysis**.

heterogeneous immunoassay any form of **immunoassay** that involves physical separation, at some stage of the procedure, of antibody-bound antigen from remaining free antigen. It includes **radioimmunoassay**. *Compare* **homogeneous immunoassay**.

heterogeneous nuclear ribonucleoprotein *abbr.*: hnRNP; particulate complexes of **heterogeneous nuclear RNA** (hnRNA) with proteins, which are cell-specific and themselves heterogeneous. The protein component may play a role in the processing of the hnRNA to mRNA.

heterogeneous nuclear RNA *abbr.*: hnRNA *or* HnRNA *or* H-RNA; a heterogeneous mixture of RNA molecules of high M_r with a rapid turnover rate that occurs in cell nuclei during protein synthesis. It is the form of RNA synthesized in eukaryotes by RNA polymerase II, i.e. that which is translated into protein. It represents the transcription products of both the exons and the introns of a gene or genes and is processed to form mRNA by the removal of the nontranslated portions (corresponding to the introns in the DNA). So-named because heterogeneity in size was one of the first characteristics used to distinguish it from other forms of nuclear RNA.

heterogenesis the production of offspring having different characteristics in successive generations; e.g. the alternation between generations that produce gametes and those that reproduce through agametes or by parthenogenesis.

heterogenetic describing chromosome pairing during meiosis when the pairing partners are derived from different original ancestors. *Compare* **homogenetic**.

heterogenic 1 describing a population or a gamete containing more than one allele of a particular gene. **2** describing two genetic elements that are not known to have a common ancestry. **3** *an alternative word for* **heterogenous**. *Compare* **homogenic**.

heterogenize *or* **xenogenize** to introduce a foreign, especially a more potent, antigen into a cell surface in order to enhance the response by T lymphocytes to other cell-surface antigens. **—heterogenization** *n.*

heterogenous *or* **heterogenic** not originating within the organism in question; of foreign origin. *Compare* **heterogeneous**.

heteroglycan *or* **heteropolysaccharide** any polysaccharide (i.e. glycan) that contains residues of two or more kinds of monosaccharide (i.e. glycose) molecule. *Compare* **homoglycan**.

heterograft *or* **heterologous graft** *an alternative name for* **xenograft**. *Compare* **homograft**.

heteroimmune describing a pair of bacteriophages in which each is sensitive to its own repressor but not to that of the other.

heterokaryon *or* **heterocaryon** any cell with more than one nucleus, in which the nuclei are not all of the same genetic constitution, or a tissue composed of such cells. *Compare* **homokaryon**. **—heterokaryotic** *or* **heterocaryotic** *adj.*

heterokaryosis *or* **heterocaryosis** the association of genetically different nuclei in a common cytoplasm.

heterolactic fermentation a type of fermentation of glucose in which the products include lactate, acetate and/or ethanol, and carbon dioxide. A key enzyme in the pathway is **phosphoketolase**, which cleaves xylulose 5-phosphate (produced by the pentose phosphate pathway) to D-glyceraldehyde 3-phosphate and acetyl phosphate, the former being then converted to lactate while the latter can form acetate and/or ethanol. Organisms that ferment in this manner include *Leuconostoc* spp. and some species of *Lactobacillus*; some produce D(–)-lactate while others produce DL-lactate. *Compare* **homolactic fermentation**.

heterolipid *a former name for* any complex lipid.

heterologous 1 consisting of different elements or of like elements in different proportions. **2** *or* **heterospecific** derived from another species, e.g. heterologous serum or tissue. *Compare* **homologous**, **isologous**.

heterologous association describing any association between two **protomers** in which the **domain of bonding** is made up of two different **binding sets**. *Compare* **isologous**.

heterologous desensitization *see* **desensitization**.

heterologous graft *or* **heterograft** *an alternative name for* **xenograft**.

heterolysin any antibody or other hemolysin formed in response to the introduction of erythrocytes from another species into the bloodstream of an animal. *Compare* **autolysin**, **homolysin**.

heterolysis 1 *(in chemistry)* the cleavage of a bond in such a manner that both bonding electrons remain within one of the two fragments between which the bond is broken; e.g. $A–B \rightarrow A^+ + B^-$. *Compare* **homolysis**. **2** *(in biochemistry)* the lysis of cells or tissues by the action of exogenous agents, e.g. enzymes, detergents, or lysins. *Compare* **autolysis**. **—heterolytic** *adj.*

heterolysosome any early **secondary lysosome** concerned with the digestion of exogenous material (i.e. **heterophagy**). *See* **heterophagosome**.

heteromorphic *or* **heteromorphous 1** differing from the normal form, e.g. in size, shape, or function. **2** describing the members of any pair of homologous chromosomes that differ from each other in size or shape. **3** *(especially of insects)* having differing forms at different stages of the life cycle. **4** *an alternative term for* **polymorphic**. *Compare* **isomorphic**. **—heteromorphism** *or* **heteromorphy** *n.*

heteronuclear NMR a form of **nuclear magnetic resonance spectroscopy** that exploits the spin–spin interactions between different nuclear spins in a molecule. For determination of structures of proteins, the isotopes ^{13}C, ^{15}N are introduced into the sample, and the interactions between the spins of these nuclei and ^{1}H are probed by sequences of pulses at the appropriate frequencies.

heterooligomer any **oligomer** made up of two or more kinds of constitutional repeating unit. **—heterooligomeric** *adj.*

heterophagosome any **phagosome** containing material exogenous to the cell. Fusion with a lysosome leads to the formation of a heterolysosome. *Compare* **autophagosome**.

heterophagy the process by which cells digest exogenous material that they have taken up. *Compare* **autophagy**. **—heterophagic** *adj.*

heterophilic binding *(of adhesion molecules)* binding of an adhesion molecule in one cell to a non-identical adhesion molecule in an adjacent cell. *Compare* **homophilic binding**.

heteroplasmy the presence of more than one type of mitochondrial DNA in a cell. A mutant mitochondrial DNA may be present in varying amounts so that phenotypic variation between cells is possible.

heteroploid describing a cell that contains any number of chromosomes except the **haploid** or **diploid** number. The term includes all **aneuploid** or **polyploid** numbers of chromosomes.

heteropolymer any polymer made up of two or more kinds of constitutional repeating unit. Proteins are typical heteropolymers. **—heteropolymeric** *adj.*

heteropolysaccharide *an alternative term for* **heteroglycan**.

heteroside *a former name for* any glycoside containing a noncarbohydrate moiety (aglycon).

heterospecific having specificity for or derived from a different species; **heterologous** (def. 2).

heterotetramer any molecular structure that can be dissociated into four (or two pairs of) nonidentical monomers. **—heterotetrameric** *adj.*

heterotope any of two or more chemical elements having atoms of different atomic number and occupying different places in the periodic table. The term includes **isobar** (def. 1). *Compare* **isotope**.

heterotopia *or* **heterotopy** the displacement, or unusual position, of a cell, organ, tissue graft, etc.

heterotopic 1 *(in chemistry)* of, relating to, or being a **heterotope** or heterotopes. *Compare* **isotopic**. **2** *(in biology and medicine) or* **heterotopous** displaced or in an unusual anatomical position.

heterotopic transplant any tissue graft that is transplanted from its normal position to another in the same organism. *Compare* **orthotopic transplant**.

heterotopous *a variant form of* **heterotopic** (def. 2).

heterotopy *a variant form of* **heterotopia**.

heterotrimer any molecular structure that is dissociable into three nonidentical monomers. **—heterotrimeric** *adj.*

heterotroph *or* **heterotrophe** *or* **organotroph** any organism whose nutritional requirements are not satisfied solely by simple inorganic substances and for which a supply of organic carbon is required for the synthesis of cellular constituents. Heterotrophs may be subdivided into **chemoheterotrophs** (or chemoorganotrophs) and **photoheterotrophs** (or photoorganotrophs) according, respectively, to whether they are **chemotrophs** or **phototrophs**. *Compare* **autotroph**. —**heterotrophic** *adj.*; **heterotrophy** *n.*

heterotropic 1 describing an **allosteric** effect in which interaction occurs between nonidentical ligands; the effect may be either cooperative or antagonistic. The term is applied also to such an interaction, to an allosteric enzyme for which different substances act as the substrate and the effector, to the regulation of such an allosteric system, etc. *Compare* **homotropic**. **2** describing a chromosome that does not pair with another at meiosis, especially a sex chromosome in the heterogametic sex.

heterotypic pertaining to, or being the first, reductive division in **meiosis**. *Compare* **homeotypic**.

heterozygosis 1 the union of genetically different gametes to form a **heterozygote**. **2** *or* **heterozygosity** the state or condition of being a heterozygote. *Compare* **homozygosis**.

heterozygosity *an alternative term for* **heterozygosis** (def. 2).

heterozygote any cell or organism having two different genes (alleles) at one or more corresponding loci on homologous chromosomes. With respect to such loci a heterozygote will produce two different types of gametes. *Compare* **homozygote**.

heterozygous *or* **heterozygotic** of, pertaining to, or being a **heterozygote**; hybrid.

HETP *abbr. for* height equivalent to a theoretical plate.

heuristic describing any method for solving mathematical or other problems for which no **algorithm** (or closed method) exists. It involves narrowing down the field of search for a solution by inductive reasoning from past experience of similar problems. *Compare* **stochastic**.

HEV *abbr. for* high-walled endothelium of the post-capillary venules.

hevein an *N*-acetyl-D-glucosamine- and *N*-acetyl-D-neuraminic acid-binding lectin; it is present in the latex of the rubber tree, *Hevea brasiliensis*, and shares 56% similarity with wheat germ agglutinin.

hexa+ *or (before a vowel)* **hex+** *comb. form* denoting six, sixfold, six times.

hexabrachion a six-armed structure, characteristic of the **tenascin** molecule. Regions of the protein radiate outwards like spokes of a wheel. [From L. *brachium* arm.]

hexadecadienoic acid any straight-chain fatty acid having sixteen carbon atoms and two double bonds per molecule. (*all-Z*)-Hexadeca-6,9-dienoic acid is found in small amounts in some animal lipids.

hexadecanoic acid *the systematic name for* palmitic acid; *see* **palmitate**.

hexadecenoic acid any straight-chain fatty acid having sixteen carbon atoms and one double bond per molecule. The most common are the 9*Z*-isomer (palmitoleic acid; *see* **palmitoleate**) and the 11*Z*-isomer, but the 3*E*-, 6*E*-, 6*Z*-, 9*E*-, and 10*Z*-isomers are also variously found in animals or plants; the 9*E*-isomer (i.e. palmitelaidic acid) is a pheromone.

hexaethyleneglycol mono-*n*-decyl ether a nonionic detergent; *see* **C_xE_y**.

hexaethyleneglycol mono-*n*-dodecyl ether a nonionic detergent; *see* **C_xE_y**.

hexagonal phase (of phospholipids) a phase in which the polar headgroups are orientated towards the interior of a phospholipid aggregate, with the fatty acyl carbon chains pointing outwards; a form of inverted micelle. It can occur in lipid bilayers, especially at higher temperatures. Certain phospholipids, such as phosphatidylethanolamine, have a greater tendency to adopt this phase than, e.g., phosphatidylcholine. A hexagonal phase with the polar headgroups oriented towards the exterior of the micelle can also exist. *See also* **liquid-crystalline phase**, **phase transition**.

hexakisphosphate *see* **multiplying prefix**.

hexamer 1 any oligomer consisting of six monomers. **2** the group of six capsomeres in an icosahedral virus capsid.

hexanoate *or* **caproate 1** the anion, $CH_3–[CH_2]_4–COO^-$, derived from hexanoic acid. **2** any salt or ester of hexanoic acid.

hexanolamino-PAF 1-*O*-hexadecyl-2-*O*-acetyl-*sn*-glycero-3-phospho-(*N*,*N*,*N*-trimethyl)-hexanolamine; a substance that inhibits the effects induced by **platelet activating factor**, including: platelet aggregation, secretion, and inositol phospholipid turnover; superoxide ion and H_2O_2 release from macrophages; hepatic glycogenolysis; and vasoconstriction.

hexanoyl *or (formerly)* **caproyl** *symbol*: Hxo; the univalent acyl group, $CH_3–[CH_2]_4–CO–$, derived from hexanoic acid. *See* **caproyl** (def. 2).

hexaric acid an **aldaric** acid formally derived from a hexose by oxidation at both C-1 and C-6.

hexitol any **alditol** having a chain of six carbon atoms in the molecule.

hexokinase EC 2.7.1.1; *systematic name*: ATP:D-hexose 6-phosphotransferase; *other name* (used for hexokinase IV): glucokinase; the phosphotransferase enzyme that catalyses the phosphorylation by ATP of D-hexose to form D-hexose 6-phosphate and ADP. In vertebrates there are four major isoenzymes, types I–IV, or A–D. All are relatively nonspecific with respect to sugar, and phosphorylate a number of hexoses such as glucose, fructose, and mannose. Thus the name glucokinase for type IV may mislead. Types I–III all have $M_r \approx 100$ kDa and are sensitive to glucose 6-phosphate (*abbr.*: Glc-6-*P*). They differ from yeast hexokinases (≈50 kDa), which are not inhibited by Glc-6-*P*. Type III is inhibited by excess glucose. Type IV is a monomer associated with cytoskeletal actin filaments and shows cooperativity with respect to glucose. In hepatocytes, at less than 5 mM glucose it is inactive, being bound to a regulatory protein; a glucose concentration of 15 mM causes translocation and activation of the enzyme in the nucleus, where it regulates expression of several genes. For example, hexokinase type IV from human mitochondrial outer membrane has a sequence with similar N-terminal and C-terminal halves. The regulatory function is associated with the N-terminal half. Type II is the major isoenzyme of skeletal muscle and adipose tissue. There are strong sequence similarities between the different types. Mutations in glucokinase produce maturity-onset diabetes of the young (MODY).

hexon a **capsomere** that is surrounded by six other capsomeres in an icosahedral virus capsid.

hexonic acid any monocarboxylic acid (i.e. aldonic acid) formally derived from a hexose by oxidation at C-1.

hexosamine any aminodeoxysugar with six carbon atoms.

hexosaminidase EC 3.2.1.52; *recommended name*: *β-N*-acetylhexosaminidase; *systematic name*: *β-N*-acetyl-D-hexosaminide *N*-acetylhexosaminohydrolase; *other name*: *β*-hexosaminidase. An enzyme that catalyses the hydrolysis of terminal nonreducing *N*-acetyl-D-hexosamine residues in *N*-acetyl-*β*-D-hexosaminides. It is a lysosomal enzyme in mammals. In humans there are two precursors, α and β. The α chain, a glycoprotein, comprises amino acids 109–529 of its precursor. The β precursor gives rise to three glycoproteins (all similar to α): β (amino acids 122–556), β-B (amino acids 122–311), and β-A (amino acids 315–556). There are three forms of the enzyme: form A, responsible for degradation of GM_2 gangliosides, is a trimer composed of one α chain, one β-A chain, and one β-B chain; form B is a tetramer of two β-A and two β-B chains; form S is a homodimer of two α chains. **Tay–Sachs disease** is due to defects of the α chain and Sandoff disease due to defects of the β chain.

hexosan *a former name for* any of a class of polysaccharides that yield only hexoses on hydrolysis.

hexose any **aldose** having a chain of six carbon atoms in the molecule.

hexose diphosphate pathway *an alternative name for* **Embden–Meyerhof pathway**.

hexose monophosphate pathway *or* **hexose monophosphate shunt** *an alternative name for* **pentose phosphate pathway**.

hexose phosphate transport protein an integral membrane transport protein responsible for sugar phosphate uptake in bacteria.

hexose-1-phosphate uridylyltransferase *see* **UDP-glucose–hexose-1-phosphate uridylyltransferase**.

hexulose any **ketose** having a chain of six carbon atoms in the molecule.

hexuronic acid 1 any monocarboxylic acid (i.e. uronic acid) formally derived from a hexose by oxidation at C-6. **2** *a historical name originally used for* ascorbic acid.

hexyl *symbol*: Hx; the alkyl group, $CH_3–[CH_2]_4–CH_2–$, derived from hexane.

hexyl glucoside hexyl *β*-D-glucopyranoside; a mild nonionic detergent, CMC 250 mM.

Hf *symbol for* hafnium.

HFBA *abbr. for* heptafluorobutyric acid; a reagent used in automatic peptide sequence analysis. It renders the action of cyanogen bromide specific to the cleavage of tryptophanyl peptide bonds.

HFCS *abbr. for* high fructose corn syrup.

Hfr *abbr. for* high-frequency recombinant.

HFT *abbr. for* high-frequency transduction.

Hg *symbol for* mercury.

HGF *abbr. for* **1** hepatocyte growth factor. **2** hyperglycemic-glycogenolytic factor; *see* **glucagon**.

HGF receptor *see* **hepatocyte growth factor receptor**.

HGG *abbr. for* human gamma-globulin.

hGH *or* **HGH** *abbr. for* human growth hormone (i.e. human **somatotropin**).

HGI *abbr. for* human gene index.

HGPRT *abbr. for* hypoxanthine/guanine **phosphoribosyltransferase. S*ee*** **hypoxanthine phosphoribosyltransferase**.

***Hha*I** a type 2 **restriction endonuclease**; recognition sequence: GCG↑C.

HHH syndrome *see* **ornithine transporter 1**.

HHT *abbr. for* hydroxyheptadecatrienoic acid.

5-HIAA *abbr. for* 5-hydroxyindoleacetic acid.

Hid a proapoptotic protein of *Drosophila* and a functional homologue of mammalian **Diablo**. It binds and inactivates **IAP** thereby releasing any associated caspase. *See* **apoptosis**.

hidden (immunological) determinant *or* **cryptodeterminant** any antigenic determinant so positioned that it is cryptic, i.e. normally not accessible for recognition by lymphocytes or antibody, but that becomes accessible after some stereochemical change occurs, e.g. by breakage, decomposition, or denaturation of the antigen. *See also* **cryptotope**.

hidden Markov model *abbr*.: HMM; (*in sequence alignment*) a probabilistic model that encodes the residue conservation within an aligned domain, used to provide a diagnostic signature for that domain. HMMs are linear chains of "states" in which a match state allows a sequence to match a conserved column in an alignment; an insert state allows insertions relative to match states; and delete states allow match positions to be skipped (i.e. denote deletions in a sequence relative to the alignment). HMMs form the basis of **Pfam** (*see* **pattern database**). *Compare* **profile**.

hide the skin of an animal, especially the tough, thick skin of larger mammals. Powdered, dried hide is used in assays of some proteinases.

HIDS *abbr. for* hyper-IgD syndrome.

HIF *abbr. for* hypoxia-inducible factor; a transcription factor that is stable under conditions of oxygen deficiency but is targeted for degradation in the presence of oxygen. **HIFα** contains an oxygen-dependent degradation domain in which a specific prolyl residue becomes modified by a HIF prolyl-4-hydroxylase. It forms a heterodimer with **HIFβ** (i.e. ARNT) and binds a 5 bp response element in hypoxia-inducible genes responsible for increasing oxygen delivery or facilitating adjustment to hypoxic stress. *See* **HIF-PH**.

HIF-PH *abbr. for* hypoxia-inducible factor prolyl hydroxylase; a prolyl-4-hydroxylase enzyme that hydroxylates a specific proline residue in the HIFα subunit (*see* **HIF**) in the presence of O_2. The reaction promotes binding of HIF to the tumour suppressor VHL protein and thereby polyubiquitination and degradation of HIF by proteasomes.

high-density lipoprotein *abbr*.: HDL; one of the classes of lipoprotein found in blood plasma in many animals (data normally relate to humans). They are also known as α lipoproteins, from having the highest electrophoretic mobility of the lipoproteins. HDL particles are the smallest of the blood lipoproteins: diameter 7.5–10 nm; solvent density for isolation 1.063–1.21 g mL^{-1}; hydrated density 1.21 g mL^{-1}. Their approximate composition (% by weight) is 6% unesterified cholesterol, 13% esterified cholesterol, 28% phospholipid, 3% triacylglycerol, 50% protein. Their apolipoprotein composition (% by weight total apolipoprotein) is 67% A-I, 22% A-II, 5–11% C-I + C-II + C-III, 1–2% E-II + E-III + E-IV, trace of D. They are synthesized in liver as precursor molecules, which undergo modification in plasma to the mature molecules, especially as a result of the action of **lecithin-cholesterol acyltransferase**. They appear to function in reverse transport of cholesterol from tissues to liver. *See also* **apolipoprotein** for individual apolipoproteins.

high-energy bond *symbol*: ~; *a term formerly sometimes used by biochemists for* a chemical bond whose hydrolysis is accompanied by an unusually large (>20 kJ mol^{-1}) negative standard free energy change. Although long used, the term has been recognized as incorrect and misleading, since it suggests that such a bond actually contains an unusually large amount of energy and fails to take into account the various factors that contribute to the large negative free energy change.

high-energy compound *a term formerly sometimes applied by biochemists to* any compound containing one or more so-called **high-energy bonds**, e.g. ATP, phospho*enol*pyruvate, acetyl-coenzyme A, etc.

high-frequency recombinant any bacterial strain that has a high frequency of recombination because the **F plasmid** has become incorporated into the bacterial chromosome. *See also* **Hfr**.

high-frequency transduction *abbr*.: HFT; any **transduction** in which the transducing phage(s) constitute a large proportion of the total phage population.

high-fructose corn syrup *abbr*.: HFCS; a mixture of fructose and glucose used as a sweetener in soft drinks, etc.; it is sometimes called **high fructose syrup** or, especially in Europe, **isoglucose**. The breakdown of corn starch to glucose (plus oligosaccharides) is followed by the action of **glucose isomerase** yielding a mixture consisting mainly of fructose and glucose. The product thus manifests the greater sweetness of fructose compared with glucose. The content is typically 42% fructose, 51% glucose, 5% maltose, and 2% other oligosaccharides.

highly conserved *see* **conserved**.

highly repetitive DNA a form of DNA that consists of short tandemly repeated sequences. It is found outside coding regions, and its role is unknown. Such DNA forms a significant proportion of most mammalian genomes.

high mobility group proteins *abbr*.: HMG proteins; small nuclear proteins that bind to nucleosomal DNA, and probably maintain genes in a transcribable conformation. The name derives from their behaviour on electrophoresis.

high-performance capillary electrophoresis electrophoresis through a long coiled capillary column that gives very high resolution of e.g. peptides. *See also* **capillary electrophoresis**.

high-performance liquid affinity chromatography *abbr*.: HPLAC; a technique that combines the use of bioaffinity supports and **high-pressure liquid chromatography**.

high-performance liquid chromatography *abbr*.: HPLC; *an alternative name for* **high-pressure liquid chromatography**.

high-potential iron–sulfur protein *abbr*.: Hipip *or* HiPIP; a type of **ferredoxin**, originally found in the photosynthetic bacterium *Chromatium vinosum*, that has a very much higher redox potential (E_o ~0.3 V) and different magnetic properties compared with other ferredoxins. It contains a [4Fe-4S] cluster that can be oxidized to the 3+ oxidation state. Other proteins, to which the term has been mistakenly applied, contain [3Fe-4S] clusters; like the *Chromatium* protein, they are able to achieve a paramagnetic higher oxidation level, but do not have high redox potentials.

high-pressure liquid chromatography *or* **high-performance liquid chromatography** *abbr*.: HPLC; a technique of **column chromatography** that is rapid and provides high resolution. It can be used with the various modes of liquid chromatography, the liquid being forced at high pressure, normally up to 420 kg cm^{-2} (6000 psi), through the column (which is usually of stainless steel) and thence through a detector into a fraction collector. Because of the ability to use high pressures, the particles of the support materials used for the stationary phase can be of very small diameter (3–10 μm), which greatly improves resolution.

high-scoring segment pair *abbr*.: HSP; in BLAST searches, an ungapped local pairwise alignment between arbitrary but equal-length fragments of a query and a database sequence that scores above a user-defined threshold. HSPs are the fundamental unit of BLAST output. *See* **alignment algorithm**.

high-speed supernatant *a jargon term for* the supernatant resulting from high-speed centrifugation (≈100 000 *g*).

high-spin complex any of the complex transition-metal ions having a maximal number of unpaired electrons in the d- or f-shell. This state occurs when pairing energy is higher than the crystal field splitting energy. *Compare* **low-spin complex**.

high-throughput describing a process that is scaled up, usually via increased levels of automation using robots. For instance, **high-throughput screening** refers to the rapid *in vitro* screening of large numbers of compound libraries (of tens to hundreds of thousands of compounds), using robotic screening assays. **High-throughput sequencing** involves the application of rapid sequencing technology at the scale of whole genomes.

high-throughput genomic sequence *abbr*.: HTG; a division of the GenBank database that provides access to unfinished genomic sequence. Its records might typically contain all of the first-pass sequence data generated from a single cosmid, BAC, YAC, or P1 clone.

high-throughput screening *see* **high throughput**.

high-throughput sequencing *see* **high throughput**.

high-voltage electron microscope a type of electron microscope that employs accelerating voltages of 1 MeV, ten times that of previous instruments, enabling images of thick sections and even intact cells to be produced without significant loss of resolution.

high-voltage electrophoresis *abbr*.: HVE; a technique of paper or thin-layer electrophoresis that results in better and more rapid separations (10–60 min) than the standard technique, which suffers from minimal diffusion of low-M_r components. The high-voltage technique employs currents of up to 500 mA and potential gradients of up to 200 V cm^{-1}. The high field strength requires cooling of the support and adequate protection devices to be incorporated into the apparatus.

Hildebrand solubility parameter *symbol*: δ; a measure of the polarity of a solvent; nonpolar solvents have low δ values while polar solvents have large values. In liquid–liquid chromatography the Hildebrand parameter indicates the relative position of a solvent in an eluotropic series. The parameter is the sum of a number of factors:

$$\delta = \delta_d + \delta_o + \delta_a + \delta_h,$$

where δ_d quantifies interactions due to **dispersion forces**, δ_o quantifies interactions due to dipole interactions, δ_a quantifies the ability of the solvent to interact as a hydrogen acceptor, and δ_h quantifies its interactions as a hydrogen donor. [After Joel Henry Hildebrand (1881–1983), US chemist.]

Hill coefficient *or* **Hill constant** *symbol*: *h* or n_H; *see* **Hill equation** and **Hill plot**.

Hill equation **1** an equation,

$$y = K[x]^h/(1 + K[x]^h),$$

used to express the binding of a ligand to a (macro)molecule. It may be rearranged to give:

$$\log[y/(1 - y)] = -\log K + h\log[x],$$

where *y*, the **fractional saturation**, is the fraction of the total number of binding sites occupied by ligand, [*x*] is the free (unbound) ligand concentration, *K* is a constant, and *h* is the Hill coefficient. **2** *(in pharmacology)* an equation derived from the above relating the effect of a drug to its concentration. For an effect, *E*, produced when an agent, A, is applied at a concentration [*A*], then the relationship between *E* and [*A*] may often be described empirically by the equation

$$E/E_{\max} = [A]^h/([A]_{50}{}^h + [A]^h),$$

where $E_{\max}$ is the maximal value of *E* and $[A]_{50}$ is the concentration that produces an effect that is 50% of $E_{\max}$. [After (Sir) Archibald Vivian Hill (1886–1977), British physiologist and biophysicist.]

Hill–Langmuir equation *(in pharmacology)* a variation of the **Langmuir absorption isotherm**; for a ligand, L, binding to a receptor, R, according to the equilibrium

$$\mathrm{L} + \mathrm{R} \overset{K_L}{\rightleftharpoons} \mathrm{LR},$$

$$p_{LR} = [\mathrm{L}]/(K_L + [\mathrm{L}]),$$

where p_{LR} is the fraction (proportion) of binding sites occupied by a ligand at equilibrium and K_L is the dissociation equilibrium constant.

Hill plot a plot of the **Hill equation** in the form log[*y*/(1 – *y*)] against log[*x*], where *y* is the fractional saturation with ligand and [*x*] is the free (unbound) ligand concentration. The slope at any one point, *h*, is the Hill coefficient at that value of *y*. The values of *h* along the plot, which usually do not exceed the number of binding sites on each molecule and which tend to unity as *y* tends to 0 or 1, give an indication of the nature and degree of cooperativity (interaction) between the various binding sites on the molecule. [After (Sir) Archibald Vivian Hill (1886–1977), British physiologist and biophysicist.]

Hill reaction the phenomenon in which isolated chloroplasts evolve dioxygen when illuminated in the presence of a suitable electron acceptor, e.g. ferricyanide or ferrioxalate, with a concomitant reduction of the electron acceptor. [After Robert ('Robin') Hill (1899–1991), British plant biochemist.]

Hill reagent any electron acceptor that functions in a **Hill reaction**, e.g. ferrioxalate or ferricyanide.

***Hinc*II** a type 2 **restriction endonuclease**; recognition sequence: GT[TC]↑[AG]AC. *Hind*II is an **isoschizomer**.

***Hind*III** a type 2 **restriction endonuclease**; recognition sequence: A↑AGCTT. The M.*Hind*III modification site is C1.

***Hinf*I** a type 2 **restriction endonuclease**; recognition sequence: G↑ANTC.

hinge region **1** a flexible, proline-rich region of an **immunoglobulin** molecule, adjacent to the two disulfide bonds linking the two heavy chains together. It probably acts as a hinge on which the **Fab fragments** can rotate allowing the immunoglobulin molecule to take up a Y-shape when it reacts with antigen. The hinge region is near the sites of action of papain and pepsin. **2** the region in the helical, rod-shaped part of a **myosin** molecule that is susceptible to cleavage by trypsin to give light meromyosin and heavy meromyosin. **3** a region in any protein about which rigid body motions occur.

***Hin*II** a type 2 **restriction endonuclease**; recognition sequence: G[AG]↑CG[TC]C. *Acy*I and *Bbi*II are **isoschizomers**.

Hipip *or* **HiPIP** *abbr. for* high-potential iron–sulfur protein.

hippocalcin a neuron-specific Ca^{2+}-binding protein with **EF-hands**, similar to recoverin. It is expressed exclusively in the pyramidal layer of the hippocampus.

Hirschsprung disease a congenital megacolon that may occur alone or be part of a syndrome. *See* **glial cell-derived neurotrophic factor**. [After Harald Hirschsprung (1830–1916), Danish physician.]

hirudin a dried extract obtained from leeches, and possessing anticoagulant activity. The name is also applied to the purified active component, a 65-amino-acid polypeptide with three disulfide bridges; this has highly specific antithrombin properties, inactivating thrombin by blocking substrate-binding groups.

hirudisin a recombinant **hirudin** variant engineered to inhibit α-thrombin and exhibit **disintegrin** activity. Hirudisins have antiplatelet aggregation activity. Replacement of the hirudin sequence Ser-Asp-Gly-Glu (residues 32–35) by Arg-Gly-Asp-Ser (RGDS) yields hirudisin, or by Lys-Gly-Asp-Ser yields hirudisin-1. The integrin-binding RGD motif of hirudisin is implicated in its antiplatelet action.

hirulog any synthetic peptide based on **hirudin** and designed as an inhibitor of the thrombin catalytic site, and exhibiting specificity for the anion-binding site of thrombin.

hirustasin an **antistasin**-like serine proteinase inhibitor isolated from the medicinal leech, *Hirudo medicinalis*.

His *symbol for* a residue of the α-amino acid L-**histidine** (alternative to H).

hist+ *a variant form of* **histo+** (before a vowel).

His-tag *abbr. for* histidine tag; a short sequence of six histidine residues placed at either the N- or C-terminus of recombinant proteins expressed in bacteria or mammalian cells. Proteins tagged in this way can be purified by Ni^{2+} chelate chromatography.

His-tag antibody a preparation of monoclonal or polyclonal antibodies raised to 6 × His sequences used in the immunodetection and immunoprecipitation of His-tagged proteins. *See* **His-tag**.

histaminase *see* **amine oxidase (copper-containing)**.

histamine 2-(4-imidazolyl)ethylamine, formed by the decarboxylation of L-histidine and present in many mammalian tissues, including the brain and spinal cord, with especially high concentrations in lung, skin, and intestine; it is stored in the granules of tissue mast cells and circulating basophil cells. Histamine is a potent vasodilator, increases capillary permeability, causes contraction of smooth muscle, regulates gastric secretion, and mediates allergic and anaphylactic conditions.



histamine receptor any membrane receptor in mammalian tissues that binds specifically with **histamine**. **H1 receptors** mediate the stimulating effects of histamine on smooth muscle in the gut and bronchi and most of the depressor effects on blood pressure. They are G-protein-associated receptors that activate phospholipase C, and are antagonized by such classical **antihistamines** as pyrilamine (mepyramine) and promethazine. **H2 receptors** mediate the stimulation of gastric acid secretion, the increase in the contraction frequency of cardiac muscle, the increase in cyclic AMP stores in basophil and mast cells, the inhibition of release of histamine by mast cells, and some depressor effects on blood pressure. They are G-protein-associated receptors that stimulate adenylate cyclase, and are antagonized by, e.g., **cimetidine**. **H3 receptors** are G-protein-associated receptors linked to Ca^{2+} channels. They occur predominantly in presynaptic nerve terminals, attenuate the release of neurotransmitters (e.g. histamine, acetylcholine, and norepinephrine), and are antagonized, e.g., by thioperamide and clobenpropit.

histamine-releasing factor *abbr*.: HRF; a protein (172 amino acids) produced by the lymphocytes of atopic children and present in the blood of allergic individuals. It causes the release of histamine only from basophilic cells that have IgE bound to them, and may have an important role in chronic allergic diseases.

histatin any member of a family of histidine-rich peptides found in human saliva and having antibacterial and antifungal activity.

histidase *an alternative name for* **histidine ammonia-lyase**.

histidinal α-amino-β-4-imidazolepropionaldehyde; 2-amino-3-(1*H*-imidazol-4-yl)propanal; $(C_3H_3N_2)CH_2–CH(NH_2)–CHO$; the α-amino-aldehyde analogue of histidine. It is the immediate biosynthetic precursor of histidine.

histidinase *an alternative name for* **histidine ammonia-lyase**.

histidinate 1 histidine anion; the anion, $(C_3H_3N_2)CH_2–CH(NH_2)–COO^–$, derived from histidine. **2** any salt of histidine anion. **3** any ester of histidine.

histidine *the trivial name for* β-4-imidazolylalanine; α-amino-β-imidazole- 4-propionic acid; 2-amino-3-(1*H*-imidazol-4-yl)propanoic acid; $(C_3H_3N_2)CH_2–CH(NH_2)–COOH$; a chiral α-amino acid. L-Histidine (*symbol*: H *or* His), (*S*)-2-amino-3-(1*H*-imidazol-4-yl)-propanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: CAC or CAU (anticodon: GUG). It is also a component of the isopeptide **carnosine**. In mammals, it is an essential dietary amino acid, and is glucogenic. D-Histidine (*symbol*: D-His *or* DHis), (*R*)-2- amino-3-(1*H*-imidazol-4-yl)propanoic acid, is not known to occur naturally. N-1 and N-3 of the imidazole ring are designated τ and π respectively.



L-histidine

histidine ammonia-lyase EC 4.3.1.3; *systematic name*: L-histidine ammonia-lyase; *other names*: histidase; histidine α-deaminase; histidinase. An ammonia-lyase (deaminase) enzyme of liver and (in some mammals) skin that catalyses the deamination of L-histidine to urocanate. It is unusual in having dehydroalanine, probably derived from a serine residue, in its active site. It is widely distributed in animals, plants, and microorganisms; in plants it is present in **glyoxysomes**. The rat, mouse, and human enzymes each contain 657 amino acids. The activity of this enzyme is defective in **histidinemia**.

histidine (base) a histidine residue in which the imidazole group is unprotonated.

histidine decarboxylase *abbr*.: HDC; EC 4.1.1.22; *systematic name*: L-histidine carboxy-lyase. A pyridoxal phosphate homodimeric enzyme that catalyses the decarboxylation of L-histidine to histamine. It is present in mast cells, enterochromaffin-like cells, and histaminergic neurons that project from the posterior hypothalamus to most parts of the brain and spinal cord. It is similar to dopa and glutamate decarboxylases.

histidine kinase *abbr*.: HK; any member of a superfamily of protein kinases specific for histidine residues. In prokaryotes and lower eukaryotes they are involved in two-component signal transduction. Most are integral membrane homodimeric proteins that contain a periplasmic N-terminal sensing domain of variable sequence, and a highly conserved cytoplasmic C-terminal kinase domain. They usually autophosphorylate (using ATP as the phosphoryl group donor) one of their own histidine residues and then transfer the group to an aspartate residue of a response regulator (RR) protein. **Hybrid histidine kinases** contain an RR – or histidine-containing phosphotransfer (HPt) – domain as part of their own structure. HKs belong to a structural class distinct from that of serine/threonine and tyrosine kinases.

histidinemia *or (esp. Brit.)* **histidinaemia** a rare, autosomal recessive, generally benign metabolic disorder in which abnormally high levels of histidine are present in the blood and urine. It is due to deficient activity of **histidine ammonia-lyase**.

histidine tail a sequence of about six histidine residues that is deliberately introduced at the C terminus of certain recombinant proteins to allow purification of the recombinant product by a type of affinity chromatography using a nickel chelating resin. Only the histidine-tailed proteins are retained by the column and these may then be eluted using a buffer containing imidazole.

histidinium 1 *a term normally used to mean* histidinium(1+); the (imidazolinium) monocation of histidine. In theory, the term denotes any ion, or mixture of ions, formed from histidine, and having a net charge of +1, although the species $(C_3H_4N_2{}^+)CH_2–CH(NH_3{}^+)–COO^–$ generally predominates in practice. **2** *the systematic name for* histidinium(2+); the dication of histidine.

histidino 1 N^2-histidino; the alkylamino group, $(C_3H_3N_2)CH_2–CH(COOH)–NH–$, derived from histidine by loss of a hydrogen atom from its α-amino group. **2** either of the two possible groups, N^π-histidino or N^τ-histidino, $HOOC–CH(NH_2)–CH_2–(C_3H_2N_2)–$, derived from histidine by loss of a hydrogen atom from its position on one or other of the nitrogen atoms of the imidazole ring.

histidinol 4-(2-amino-3-hydroxypropyl)imidazole; 2-amino-3-(1*H*-imidazol-4-yl)propanol; $(C_3H_3N_2)CH_2–CH(NH_2)–CH_2OH$; the α-amino-alcohol analogue of histidine. It is an intermediate, together with its phosphate ester, in the biosynthesis of histidine, and a powerful reversible inhibitor of protein synthesis.

histidinol dehydrogenase *abbr*.: HDH; EC 1.1.1.23; L-histidinol:NAD^+ oxidoreductase. A homodimeric enzyme that catalyses the reaction:

$$\text{L-histidinol} + 2NAD^+ = \text{L-histidine} + 2NADH$$

this being the last step in the biosynthesis of histidine. The *his* operon of *Salmonella typhimurium* encodes a bifunctional protein that also has an aldehyde dehydrogenase site, histidinol being an intermediate. *See also* ***Salmonella*** **mutagenicity test**.

histidyl the acyl group, $(C_3H_3N_2)–CH_2–CH(NH_2)–CO–$, derived from histidine.

histo+ *or (before a vowel)* **hist+** *comb. form* denoting tissue.

histochemistry the chemistry of the tissues, as studied with a combination of the methods of chemistry and histology.

histocompatibility the extent to which an organism will tolerate a graft of a foreign tissue. —**histocompatible** *adj.*

histocompatibility antigen any of the genetically determined **isoantigens** present on the surface of many animal cells that determine the immune reactions to tissue grafts. If tissue is grafted onto a recipient of the same species that does not carry the same histocompatibility antigens as the graft material, an immune response may be provoked in the recipient leading to graft rejection. *See also* **HLA histocompatibility system**, **major histocompatibility complex**.

histocompatibility gene any gene determining the formation of a **histocompatibility antigen**. *See* **HLA histocompatibility system**, **major histocompatibility complex**.

histoelectrofocusing a technique in which an unfixed frozen section of tissue, 25–40 μm thick, is applied to a support gel and then subjected to **electrofocusing**. The proteins and enzymes present in the tissue move into the gel and may be revealed by staining or zymographic techniques.

histogram a diagram representing a frequency distribution. It consists of a number of contiguous rectangles whose widths are proportional to the class interval under consideration and whose heights are proportional to the frequency associated with each class.

histohematin *or (esp. Brit.)* **histohaematin** a term first used in 1884 by Charles Alexander MacMunn (1852–1911) for the pigments now known as **cytochromes**. It included **myohematin**.

histone any of a group of evolutionarily highly conserved basic proteins, molecular mass 11–21 kDa, that constitute about half the mass of the chromosomes of all eukaryotic cells, except spermatozoa. They comprise single polypeptide chains with a lysine-plus-arginine content of about 25%, and are concerned in the packing of DNA in **chromatin**. The principal histones may be classified into five types, as shown in the table.

Type	Other names	Lys/Arg ratio	M_r	Location
H1	F1,Ia	20.0	21 000	linker
H2A	F2a2,IIb1	1.25	14 500	core
H2B	F2b,IIb2	2.25	13 800	core
H3	F3,III	0.72	15 300	core
H4	F2a1,IV	0.79	11 300	core

The octomer $(\mathrm{H2A,H2B,H3,H4})_2$ forms the **nucleosome** core. H1 is associated with nucleosomes, especially the linking DNA. *See also* **H-NS**.

histone acetyltransferase EC 2.3.1.48; an enzyme that transfers an acetyl group from acetyl-CoA to a lysine residue in the N-terminal region of a core histone in a nucleosome. Type A enzymes are cytosolic and acetylate freshly synthesized histones before they enter the nucleus. Type B are nuclear and reside in large multiprotein complexes, being recruited by, and acting as cofactors for, many DNA sequence-specific transcription factors. Examples include p300/CBP (which targets histones H2A, H2B, H3, and H4) and **PCAF** (which targets histones H3 and H4).

histone code the hypothesis that the pattern of acetylation, methylation, phosphorylation, and ubiquitination of the N-terminal regions of core histones within nucleosomes is recognized by proteins (or complexes) that control chromatin modelling and transcriptional regulation. This is considered to extend the potential of the genetic code.

histone deacetylase *abbr.* HDAc; an enzyme that catalyses the hydrolysis of acetyl groups from histones, and thereby regulates DNA-protein interactions. Histone deacetylases are part of transcriptional corepressor complexes. Inhibitors of histone deacetylases induce hyperacetylation of histones that modulate chromatin structure and gene expression, and induce growth arrest, cell differentiation, and apoptosis of tumor cells.

histone fold the interaction motif involved in homodimerization of the core histones (H2A and H2B, H3 and H4) and their assembly into an octomer. It comprises three alpha helices linked by two loops. The surface residues mediate octomer formation and interaction with the DNA that wraps around the octomer. The fold also occurs in many transcription factors and in the chromatin accessibility complex (**CHRAC**).

histone modification the post-translational enzymatic modification of the N-terminal region of the core histones H2A, H2B, H3, and H4 by acetylation, methylation, phosphorylation, or ubiquitination. The extent and pattern of modification regulates chromosome condensation and is the basis of the **histone code** and the **nucleosome code**.

hit-and-run mutagenesis a form of mutagenesis by homologous recombination in mammalian cells in which a vector carrying the mutated homologous DNA sequence is inserted into the gene of interest thereby duplicating part of it. In a second step, intrachromosomal recombination between the native and homologous mutated sequences results in introduction of the mutation at the desired location.

hitchhiking **1** *a jargon term for* the sequence of events in which a genetic element (or **transposon**) inserts into an active secondary site on a replicon, which is then transferred to a recipient, the transposon then coming immediately to occupy its normal primary site in the DNA of the recipient organism. **2** the spread of a neutral allele through a population due to its linkage with a beneficial allele that is subject to selection.

HIV *abbr. for* human immunodeficiency virus; a **retrovirus**, the causative agent of **AIDS**. HIV-1 is found worldwide; HIV-2 is found mainly in West Africa. The gene structures of the **viral envelope sequences** (*see* **HIV protein**) of HIV-1 and HIV-2 are not closely related. HIV-2 is closely related to a **simian immunodeficiency virus** (SIV) common in sooty mangabeys and probably originated there. HIV-1, which probably originated from a non-human primate in Africa, is closely related to SIV from chimpanzees. However, it is not clear that chimpanzees represent the natural host of these viruses. The reverse transcriptase enzyme of HIV is highly error-prone, leading to a high mutation rate. Thus these viruses evolve very quickly even within single patients, and drug-resistant mutations appear rapidly. For HIV-1 to enter its target cells, it must bind to the cell-surface protein **CD4** and to one or more chemokine receptors. One of these, named CCR5, is effective in the early stages of infection. Patients with defective CCR5 cannot be infected with HIV-1. During the later stages of infection, another chemokine receptor, CXCR4 (*former name*: fusin) dominates.

HIV entry cofactor *an alternative term for* **fusin**.

HIV-1 protease an aspartyl protease that is a homodimer of two subunits each containing 99 amino acids, with cysteines at positions 67 and 95. Its proteolytic function is essential for the life cycle of human immunodeficiency virus (HIV) and is, therefore, a target for the design of inhibitors as therapeutic drugs, several examples of which are in use.

HIV protein any of the proteins encoded by the human immunodeficiency virus (HIV). The HIV-1 genome (9.5 kb) is transcribed to give 12 different mRNAs, generated by alternative splicing. The proteins are conventionally named for the gene and/or their size (kDa), with the convention that p = protein and gp = glycoprotein. The primary translation products are: Gag precursor (p53); Pol precursor; Env precursor (gp160); Nef (p27; negative regulator); Vif (p23); Tat (p14; regulatory protein); Rev (p19; regulatory protein); Vpr (p18); and Vpu (p15). The Gag precursor is cleaved to myristoylated Gag protein (p17), structural protein (p24), and p15; p15 is the precursor for RNA-binding protein (p7) and proline-rich protein (p9). The Pol precursor is cleaved to protease (p10), reverse transcriptase (p51), and endonuclease (p32). The Env precursor is cleaved to extracellular protein (gp120) and transmembrane protein (gp41). Protease, reverse transcriptase, and endonuclease are synthesized as part of a polyprotein. *See also* **retrovirus**.

HK *abbr. for* **histidine kinase**.

HKD catalytic motif *see* **PhD enzyme**.

HL-60 a continuous line of promyelocytic cells that can be made to differentiate into macrophage-like cells by treatment with the phorbol ester TPA or into granulocytes by treatment with dimethylsulfoxide (DMSO) or all-*trans* retinoic acid.

HLA *abbr. for* human leukocyte-associated antigen. *See also* **histocompatibility antigen**, **major histocompatibility complex**.

HLA histocompatibility system a family of histocompatibility antigens encoded by the complex of genetic loci known as the **major histocompatibility complex** (MHC). It is the major histocompatibility system in humans, equivalent to the H-2 histocompatibility system in mice. The MHC genes control the presence of HLA **isoantigens** on cell surfaces. These antigens are of primary importance in tissue grafting since HLA-incompatible grafts are more likely to be rejected than incompatible grafts of other isoantigen groups.

HLH *abbr. for* helix-loop-helix (*see* **helix-turn-helix**).

***hly* genes** *see* **hemolysin**.

HMC *abbr. for* 5-hydroxymethylcytosine.

H-meromyosin *abbr. for* heavy meromyosin.

hMG *or* **HMG** *abbr. for* human menopausal gonadotropin (i.e. human urogonadotropin).

HMG 1 *abbr. for* 2-hydroxy-2-methylglutaryl. **2** *abbr. for* high mobility group of nuclear proteins. **3** *see* **hMG**.

HMG-CoA *abbr. for* hydroxymethylglutaryl-CoA.

HMG-CoA lyase *abbr. for* hydroxymethylglutaryl-CoA lyase.

HMG-CoA reductase *abbr. for* hydroxymethylglutaryl-CoA reductase.

HMG-CoA synthase *abbr. for* hydroxymethylglutaryl-CoA synthase.

HMM *abbr. for* **1** heavy meromyosin. **2** hidden Markov model.

HMMA *abbr. for* hydroxymethoxymandelate.

HMP *abbr. for* hexose monophosphate.

HMP pathway *or* **HMP shunt** *abbr. for* hexose monophosphate pathway (shunt) (i.e. **pentose phosphate pathway**).

HNF *abbr. for* hepatocyte nuclear factor.

HNPCC *abbr. for* hereditary nonpolyposis colon cancer; an autosomal dominant disease associated with mutations in several genes encoding proteins (e.g. MutL, MutS, GTBP) that may normally take part in mismatch repair of DNA.

hnRNA *or* **HnRNA** *abbr. for* heterogeneous nuclear RNA (alternatives to H-RNA).

hnRNP *abbr. for* heterogeneous nuclear ribonucleoprotein.

hnRNP particles *abbr. for* heterogeneous nuclear ribonucleoprotein particles; particles in the nucleus containing **hnRNA** bound to protein.

H-NS basic DNA-binding proteins of several bacterial families, characterized by an N-terminal tetrapeptide, consensus Ser-Glu-Xaa-Leu . Although their precise role remains unclear, they may be the prokaryotic counterparts of **histones** in eukaryotic chromatin. They have the ability to bind to curved DNA, and may have a role in transcriptional regulation. The name derives from an isolation procedure extracting them from the 30S ribosomal native subunit.

Ho *symbol for* holmium.

HO *abbr. for* **heme oxygenase**.

Hoechst 33342 *see* **bisbenzimide**.

Hoechst 33258 a bis-benzimidazole fluorescent dye used for measuring DNA concentration. *See* **bisbenzimide**.

Hoff *see* **van't Hoff**.

Hofmeister series *or* **lyotropic series** an arrangement of either the simple anions or the simple cations (or of the salts of such ions) in order of their ability to remove lyophilic substances from colloidal solutions. Each series is an index of, *inter alia*, the relative abilities of the ions to salt-out proteins from solution. The order for anions is: citrate^{3-} > tartrate^{2-} > acetate^{-} > NO_3^- > ClO_4^- > CNS^{-}, and that for cations is: $Mg^{2+} > Ca^{2+} > Sr^{2+} > Ba^{2+} > Li^+ > Na^+ > K^+ > Rb^+ > Cs^+$. [After Franz Hofmeister (1850–1922).]

Hofstee plot *see* **Eadie–Hofstee plot**.

Hogness box *an alternative name for* **TATA box**.

hol+ *a variant form of* (before a vowel) **holo+**.

holandric inherited solely in the male line. *Compare* **hologynic**.

holdback agent *or* **holdback carrier** any nonradioactive substance that is added to a sample to prevent either coprecipitation or adsorption of some soluble radioactive substance.

hold-up volume *symbol*: V_M; *(in chromatography)* the volume of eluent required to elute a component whose concentration in the stationary phase is negligible relative to that in the mobile phase. In gas chromatography, the volume of carrier gas (eluent) is specified at the same temperature and pressure as the total retention volume.

hole *(in physics)* the absence of an electron in a normally filled valency structure of a crystalline **semiconductor** that behaves as a carrier of charge and is mathematically equivalent to a positron.

holin a protein encoded by dsDNA bacteriophages that permeabilizes the plasma membrane of host cells to permit exit of the enzyme **endolysin** that degrades the murein matrix to enable the release of progeny phage. Holins constitute a subclass of transport proteins of the TC system, designated 1.E. They contain between 45 (TC 1.E.6) and 250 (TC 1.E.8) amino acid residues.

Holliday junction *or* **Holliday structure** one of the junctions between four strands of DNA that are important intermediates in **genetic recombination**. They are part of the mechanism for **crossing over** during the long prophase of meiotic cell division I, when four strands of DNA are aligned. The process involves breaking the DNA double helix in a maternal chromatid and in a homologous paternal chromatid and then exchanging fragments between the two non-sister chromatids in a reciprocal fashion. At this point, in each four strands, a paternal strand links across to a maternal strand, forming the junction known by the name of its proposer. [After Robin Holliday (1932–), British biologist.]

hollow-cathode discharge lamp a radiation source used in **atomic absorption spectrophotometry** to produce a spectrum of radiation specific to the element being assayed. A sample of the element in question is held in a metal cup-shaped cathode, which, together with a tungsten anode, is enclosed in a glass or quartz envelope filled with argon at low pressure. A high voltage is used to produce an arc spectrum of the element.

hollow-fibre technique a technique in which bundles of semipermeable, hollow fibres with pores of controlled dimensions that function as molecular sieves are used for concentrating, desalting, dialysing, and fractionating macromolecules in solution. *Compare* **capillary filtration**.

holo+ *or (before a vowel)* **hol+** *comb. form* whole, entire, complete; wholly, entirely, completely.

holocarboxylase synthetase an enzyme that biotinylates the ε-amino group of lysine residues to form **biocytin** at the active site of biotin carboxylases (*see* **acetyl-CoA carboxylase**). In humans, numerous mutations of the gene at 21q22.1 (which encodes 726 residues) are associated with neonatal multiple carboxylase deficiency, which is clinically similar to biotinidase deficiency.

holocellulose the complex mixture of polysaccharides remaining after the removal of lignin from tree-wood by treatment with sodium chlorite solution. It consists of a mixture of **cellulose** and **hemicellulose**.

holocrine 1 describing a type of secretion that involves disintegration of the entire secretory cell to release the secretory products. **2** describing a gland made up of such cells. *Compare* **apocrine**, **eccrine**, **merocrine**.

holoenzyme a catalytically active complex comprising the protein part of an enzyme (**apoenzyme**) combined with the appropriate cofactor or cofactors.

hologram 1 the pattern produced when light, or other electromagnetic radiation, that has been reflected, diffracted, or transmitted by an object placed in a coherent beam, interferes with a reference beam related in phase to the first beam. **2** a photograph of such a pattern.

holograph 1 to make a **hologram** (def. 1, 2). **2** any book or other document handwritten by its author.

holography the process of making and using **holograms** (def. 1, 2). —**holographic** *adj.*

hologynic inherited solely in the female line. *Compare* **holandric**.

Holometabola *or* **Endopterygota** one of the two divisions of the subclass Pterygota, comprising those insects, e.g. butterflies, moths, flies, and beetles, in which the juvenile forms (larvae) are very different from the adults. Such insects undergo complete metamorphosis during a resting stage (pupa). *Compare* **Hemimetabola**.

holoprosencephaly *see* **hedgehog protein**.

holoprotein the functional form of a protein containing a protein part (**apoprotein**) together with any appropriate ligand or ligands.

holorepressor a functional repressor protein consisting of an **aporepressor** plus **corepressor** complex.

homeo+ *or* **homoeo+** *or* **homoio+** *comb. form* denoting like or similar.

homeobox a short (180 bp) conserved DNA sequence that encodes a DNA-binding motif famous for its presence in genes that are involved in orchestrating the development of a wide range of organisms. *See also* **homeotic gene**.

homeodomain the DNA-binding motif of 60 amino acids encoded by a **homeobox**.

homeomorphism *or* **homoeomorphism** *(in chemistry)* the property shown by certain substances of having the same crystal form but different compositions. **—homeomorphic, homeomorphous**, *or* **homoeomorphic, homoeomorphous** *adj.*

homeostasis *or* **homoeostasis** the maintenance of a relatively constant internal environment in the bodies of higher animals by means of a series of interacting physiological and biochemical processes. **—homeostatic** *or* **homoeostatic** *adj.*

homeotic gene *or* **homeodomain-encoding gene** *or* **homeobox-encoding gene** *or* ***Hox*** **gene** any of the genes that are allelic for mutations resulting in the conversion of one body part into another. Homeotic genes were first discovered in *Drosophila*; a mutation in such a gene could, e.g., result in a leg replacing an antenna. While *Drosophila* has only two *Hox* clusters, in nematodes there is one, and in vertebrates four clusters of 9 to 11 genes each located on a separate chromosome and spanning more than 100 kb. The vertebrate *Hox* genes are expressed in specific patterns and at particular stages in embryogenesis. They are activated by **retinoic acid** and **sonic hedgehog protein**. In the limb these are active in concert with **fibroblast growth factor**. The homeobox portion of the *Hox* genes in different species is remarkably conserved. The structure of some homeodomains has been determined, as has their interaction with DNA.

homeothermic *the usual US spelling of* **homoiothermic**.

homeotic selector any of a family of genes in *Drosophila* that select the expression of **homeotic genes**. They encode homologous regulatory proteins that contain a **homeobox** sequence.

homeotypic pertaining to, or being the second, reductive division in **meiosis**. *Compare* **heterotypic**.

Homer any protein belonging to a family whose members have an N-terminal EVH1 homology sequence that interacts with a proline-rich sequence motif (called Homer ligand), which is present in some metabotropic glutamate receptors (mGluRs) and on the cytosolic region of the inositol trisphosphate (IP_3) receptor. It also contains a C-terminal coiled-coil region for homodimer formation. Homer helps localize mGluRs to synapses and mediates their effects on IP_3 receptors.

Homer ligand *see* **Homer**.

homo+ *comb. form* **1** the same, similar, alike. *Compare* **allo+** (def. 1); **hetero+** (def. 1); **iso+** (def. 1); **xeno+** (def. 1). **2** from, or directed towards, the same species. *Compare* **allo+** (def. 2); **hetero+** (def. 2); **iso+** (def. 2); **xeno+** (def. 2). **3** containing atoms, groups, linkages, residues, or subunits of the same kind. *Compare* **hetero+** (def. 3). **4** denoting the next higher homologue of a specified chemical compound, especially one whose molecules contain, in a hydrocarbon chain or ring, one more methylene, $–CH_2–$, than those of of the parent compound, e.g. homocysteine, homoserine, homo-5α-pregnane. *Compare* **nor+** (def. 2).

Homo a genus of primates that includes modern man (*Homo sapiens*) and a number of more primitive, fossil species.

homoarginine (*sometimes*) *a trivial name for* N^6-amidino lysine.

homobifunctional describing a chemical reagent that carries two identical reactive groups. *Compare* **heterobifunctional**.

homocarnosine (*sometimes*) *a trivial name for* N^{α}-(4-aminobutyryl)histidine. It is present in brain but its function is unclear.

homochromatic *a less common term for* **monochromatic** (def.1).

homochromatography a chromatographic technique for the separation of labelled oligonucleotides, in which a mixture of unlabelled oligonucleotides is used to displace the labelled components according to differences in size.

homocitrate 2-hydroxybutane-1,2,4-tricarboxylate; the (*R*) enantiomer is a component of the **aminoadipic pathway** and is formed by **homocitrate synthase**.



homocitrate synthase EC 4.1.3.21; *systematic name*: 2-hydroxybutane-1,2,4-tricarboxylate 2-oxoglutarate-lyase (CoA-acetylating). An enzyme that catalyses the formation of **homocitrate** from 2-oxoglutarate and acetyl-CoA and H_2O. *See also* **aminoadipic pathway**.

homoconjugation the association between a base and its conjugate acid through a hydrogen bond. *See* **conjugate acid–base pair**. *Compare* **heteroconjugation**.

homocyclic 1 describing any cyclic molecular structure containing atoms of a single element in the ring or rings; describing any compound having such a structure. The term is preferred to its synonym **isocyclic**; it includes **carbocyclic** (def. 1). *Compare* **heterocyclic** (def. 1). **2** any such compound.

homocysteine *symbol*: Hcy; α-amino-γ-mercaptobutyric acid; 2-amino-4-mercaptobutanoic acid; an important intermediate in the metabolic reactions of its *S*-methyl derivative, methionine. Its concentration in human serum is raised after stroke.



L-homocysteine

homocysteine methyltransferase one of several enzymes, e.g. the two alternative forms of enzyme synthesizing methionine: (1) 5-methyltetrahydrofolate–homocysteine *S*-methyltransferase. (EC 2.1.1.13); *other name*: tetrahydropteroylglutamate methyltransferase; it catalyses a reaction between 5-methyltetrahydrofolate and L-homocysteine to form tetrahydrofolate and L-methionine; cobalamin is a cofactor. (2) 5-methyltetrahydropteroyltriglutamate–homocysteine *S*-methyltransferase (EC 2.1.1.14); *other name*: tetrahydropteroyltriglutamate methyltransferase; it catalyses a reaction between 5-methyltetrahydropteroyltri-L-glutamate and L-homocysteine to form tetrahydropteroyltri-L-glutamate and L-methionine.

homocystine 2,2′-diamino-4,4′-dithiobis(butanoic acid); the disulfide oxidation product of **homocysteine**.

homocystinemia *or (esp. Brit.)* **homocystinaemia** a usually inherited biochemical abnormality of humans, characterized by an abnormally high concentration of homocystine in the blood and in the urine (**homocystinuria**). The condition may be due to: (1) a deficiency of cystathionine β-synthase (EC 4.2.1.22) activity; (2) a deficiency of methylene tetrahydrofolate reductase; or (3) a deficiency of cobalamin. Homocystinemia is an independent risk factor for thromboembolic events.

homodetic describing a cyclic peptide in which the ring consists solely of amino-acid residues in eupeptide linkage. *Compare* **heterodetic**.

homodimer any macromolecular structure in which two identical subunits (monomers or protomers) are noncovalently associated. *See also* **dimer**. *Compare* **heterodimer**.

homoduplex hybrid DNA involving two strands that are complementary. *Compare* **heteroduplex**.

homoeo+ *a variant form of* **homeo+**.

homogametic describing the sex whose cell nuclei contain a pair of similar **sex chromosomes**. The homogametic sex is usually female, but is male in the Lepidoptera, birds, some amphibians and fishes, and a few plants. *Compare* **heterogametic**.

homogenate any disrupted tissue preparation in which cell disruption is maximal while the destruction of intracellular organelles is kept to the minimum.

homogeneic *an alternative term for* **allogeneic**. *Compare* **heterogeneic**.

homogeneous **1** being uniform in kind, as in a homogeneous population. **2** *(describing a group of molecules)* uniform in structure or composition. **3** *(describing a system)* consisting of only a single chemical phase. *Compare* **heterogeneous**, **homogenous**. **—homogeneity** *n.*

homogeneous catalysis any catalytic action or process in which the catalyst is uniformly distributed in the same chemical phase as the reactants. *Compare* **heterogeneous catalysis**.

homogeneous enzyme immunoassay *or* **enzyme-multiplied immunoassay technique** (*abbr.*: EMIT) a technique of **homogeneous immunoassay** in which an enzyme is covalently coupled to the substance to be assayed. The enzymic activity of the complex is inhibited by an antiserum specific for the substance and this inhibition is relieved by the presence of free molecules of the substance to be assayed. The enzyme acts as a molecular amplifier.

homogeneous immunoassay any **immunoassay** that does not involve physical separation of antibody-bound antigen from antigen molecules that remain free. Labels that may be attached to the antigen include: enzymes, cofactors, prosthetic groups or substrates of enzymes, chemiluminescent or fluorescent molecules, stable free radicals. *Compare* **heterogeneous immunoassay**.

homogeneously staining region a region in a chromosome that stains homogeneously, rather than with the banding pattern normally seen. The region contains massively amplified numbers of copies of a small segment of the genome. The amplified DNA may often consist of multidrug resistance gene DNA (*see* **MDR**).

homogenesis the production of offspring having the same characteristics in successive generations. *Compare* **heterogenesis**.

homogenetic describing chromosome pairing during meiosis when the pairing partners are derived from one of the original ancestors. *Compare* **heterogenetic**.

homogenic *or* **congenic** **1** describing a gamete that contains only one allele of a particular gene. **2** describing two genetic elements that are descended from a common ancestor by a known sequence of steps. **3** *an alternative word for* **homogeneous**. *Compare* **heterogenic**.

homogenize *or* **homogenise** produce a **homogenate**. **—homogenization** *or* **homogenisation** *n.*

homogenizer *or* **homogeniser** any apparatus for producing a **homogenate**.

homogenous **1** of, pertaining to, or exhibiting **homogeny**. **2** *an alternative word for* **homogeneous**.

homogentisate *or (formerly)* **alcapton** 2,5-dihydroxyphenylacetate; an intermediate in the catabolism of tyrosine and in the biosynthesis of plastoquinone and tocopherol. It is excreted in abnormally large quantities in the urine in **alcaptonuria**. *See also* **homogentisate 1,2-dioxygenase**.

homogentisate 1,2-dioxygenase EC 1.13.11.5; *systematic name*: homogentisate:oxygen 1,2-oxidoreductase (decyclizing); *other names*: homogentisicase; homogentisate oxygenase; homogentisic acid oxidase. An enzyme with highest activity in liver that catalyses the oxidation by dioxygen of homogentisate to 4-maleylacetoacetate; iron(II) is a cofactor. In the catabolism of L-tyrosine, **homogentisate** is formed from 4-hydroxyphenylpyruvate; maleylacetoacetate is converted to fumarylacetoacetate, which is split to fumarate and acetoacetate. Mutations in the gene result in enzyme deficiency and the rare metabolic disorder alkaptonuria.

homogeny *(in biology)* similarity in the structure of organisms or parts of organisms because of common ancestry.

homoglycan *or* **homopolysaccharide** any polysaccharide (i.e. glycan) that contains residues of only one kind of monosaccharide (i.e. glycose) molecule. *Compare* **heteroglycan**.

homograft *an old term for* **allograft**. *Compare* **heterograft**.

homoio+ *a variant form of* **homeo+**.

homoiosmotic describing organisms with a constant internal osmotic pressure. *Compare* **poikilosmotic**.

homoiothermic *or* **homoiothermal** *or (esp. US)* **homeothermic** *or* **homeothermal** describing an organism (**homoiotherm**) that sustains a relatively constant body temperature, usually higher than that of its surroundings. *Compare* **poikilothermic**. **—homoiothermy** *or (esp. US)* **homeothermy** *n.*

homokaryon *or* **homocaryon** any cell with more than one nucleus, and in which the nuclei are all of the same genetic constitution; a tissue composed of such cells. *Compare* **heterokaryon**. **—homokaryotic** *or* **homocaryotic** *adj.*

homokaryosis *or* **homocaryosis** the condition of having a **homokaryon** or homokaryons. *Compare* **heterokaryosis**.

homolactic fermentation a type of fermentation of glucose to lactate via the **Embden–Meyerhof pathway**. *Compare* **heterolactic fermentation**.

homolog *(sometimes) the US spelling of* **homologue**.

homologous **1** having a related or similar position, structure, etc.; corresponding; exhibiting **homology**. **2** *(in chemistry)* describing compounds that form a series with successive constant differences in composition. **3** *(in biology)* of common ancestry; especially of organs and tissues that have a similar anatomical position and structure in different species by virtue of their common evolutionary origin, even though their functions may have come to differ; e.g. the wing of a bird and the forelimb of a reptile. *Compare* **analogous**. **4** *(in genetics)* describing chromosomes that pair during meiosis, each member of a homologous pair being a duplicate of one of the chromosomes contributed at syngamy by the mother or the father. **5** *(in biochemistry)* **a** (of sequences of residues in encoded macromolecules) having the same or similar residues at corresponding positions (*see also* **conserved**). With respect to proteins the term is used to imply a common evolutionary origin. Specifically this requires evidence based on gene structure and not merely a similarity of protein structure. **b** (of proteins from different species) having identical or similar functions. *Compare* **heterologous**. **—homology** *n.*

homologous antibody the antibody elicited by a specified antigen.

homologous antigen the antigen that has elicited a specified antibody.

homologous desensitization *see* **desensitization**.

homologous recombination **genetic recombination** between two DNA molecules of identical or nearly identical sequence when contained in the same cell. It occurs naturally during meiosis, and is exploited when performing gene knockouts in yeast, embryonic stem cells, and other cells.

homologue *or (sometimes) US* **homolog** **1** (something) exhibiting homology. **2** *(in chemistry)* any member of a **homologous** (def. 2) series of compounds. **3** *(in biology)* any one of a series of **homologous** (def. 3) organs or structures. **4** *(in genetics)* **a** either members of a pair of **homologous** (def. 4) chromosomes. **b** either one of two genes in corresponding loci in homologous chromosomes. **5** (*in sequence analysis*) any of two or more nucleotide or protein sequences that are evolutionarily related to each other by descent from a common ancestor. Homologous sequences may be orthologues or paralogues.

homology domain any of the regions in an immunoglobulin involved in forming the **immunoglobulin fold**.

homology modelling a computational method for predicting protein structure based on similarity to a sequence of known structure. The accuracy of homology-derived models depends on the level of similarity between the target and model sequences, and hence on the quality of their alignment: the greater the similarity, the better the alignment and the better the model is likely to be. The resolution of structures modelled in this way is generally low.

homolysis *(in chemistry)* the cleavage of a covalent bond in such a manner that each of the fragments between which the bond is broken retains one of the bonding electrons; e.g. A–B → A• + B•. **—homolytic** *adj.*

homooligomer any **oligomer** made up of only one kind of constitutional repeating unit. **—homooligomeric** *adj.*

homophilic binding *(of adhesion molecules)* binding of an adhesion molecule in one cell to an identical molecule in an adjacent cell. *Compare* **heterophilic binding**.

homoplasy *(in phylogeny)* the occurrence of similar characters, independently of lineage, via parallel or convergent evolution (sometimes these processes are distinguished, sometimes the difference is considered irrelevant) or reversion. Such characters cannot therefore be used to construct phylogenetic trees.

homopolymer any polymer made up of only one kind of constitutional repeating unit. For example, cellulose contains only glucose as the monomeric unit. —**homopolymeric** *adj.*

homopolymer tailing *a jargon term for* a procedure useful in joining two types of duplex DNA molecules to form mixed dimeric circular DNA. In this procedure, homopolymer sequences of one type, e.g. poly(dA), are added to the 3′-ends of one of the populations of DNA molecules, while complementary homopolymer sequences, e.g. poly(dT), are added to the 3′-ends of the other population of DNA molecules. The two types of molecules are then annealed to form mixed dimeric circles.

homopolysaccharide *an alternative name for* **homoglycan**.

homoserine *symbol*: Hse; α-amino-γ-hydroxybutyric acid; an intermediate in the biosynthesis of cystathionine, threonine, and methionine. It also occurs in bacterial peptidoglycans and, as its *O*-guanidino derivative, in canavanine. The term normally implies the L enantiomer.

homoserine deaminase *see* **cystathionine γ-lyase**.

homoserine dehydratase *see* **cystathionine γ-lyase**.

homoserine dehydrogenase EC 1.1.1.3; *systematic name*: L-homoserine:NAD(P)$^+$ oxidoreductase; an enzyme of methionine and threonine biosynthesis. It catalyses the formation of L-homoserine and NAD(P)$^+$ from L-aspartate 4-semialdehyde and NAD(P)H. *Escherichia coli* has a homotetrameric bifunctional enzyme consisting of 820 amino acids. Residues 1–249 form the aspartokinase I domain, 250–470 form a large 'interface', and 471–820 form homoserine dehydrogenase; regulation is by L-Thr. *See also* **aspartokinase/homoserine dehydrogenase**.

homoserine lactone *symbol*: Hsl; α-amino-γ-butyrolactone; a substance formed by the cleavage of methionine-containing peptides by cyanogen bromide.

homosterism *or* **homostery** the phenomenon in which a second molecule of normal substrate, or a structurally similar compound, combines at the catalytic site of an enzyme leading to a modification in the reaction of the bound intermediate. *Compare* **allosterism**. —**homosteric** *adj.*

homostery *an alternative term for* **homosterism**.

homothallic describing species, e.g. of certain fungi and algae, in which a sexual spore can result from the fusion of nuclei that are genetically distinct (i.e. not necessarily homozygous), but are derived from the same thallus; thus the species is self-fertile.

homothallic switching endonuclease a sequence-specific endonuclease, with a site on yeast chromosome III, that is involved in mating-type switching. It is a **zinc finger** protein.

homotherm *an alternative word for* **homoiotherm**.

homotope any residue that can take the place of another residue in a particular position in a polymer; e.g., the serine and glycine residues at position 9 of the A chain of bovine and ovine insulin, respectively, are homotopes.

homotransplant **1** *an alternative term for* **homograft**. **2** to effect such a transplant.

homotropic describing an **allosteric** effect in which interaction occurs between identical ligands; the effect appears to be always cooperative. The term is applied also to such an interaction in the case of an allosteric enzyme for which the same substance acts as both the substrate and the allosteric effector, etc. *Compare* **heterotropic** (def. 1).

homovanillic acid *abbr.*: HVA; 4-hydroxy-3-methoxyphenylacetic acid; a metabolite of catecholamine metabolism, found in human urine. It is the principal urinary metabolite of dopa and dopamine. It is used as a reagent in the fluorometric determination of glucose oxidase and other oxidases.



homozygosis **1** the union of gametes identical for one or more pairs of genes to form a **homozygote**. **2** *or* **homozygosity** the state or condition of being a homozygote. *Compare* **heterozygosis**.

homozygosity *an alternative term for* **homozygosis** (def. 2).

homozygote any cell or organism having identical genes (alleles) at one or more corresponding loci on homologous chromosomes. With respect to such loci, a homozygote will produce two identical gametes. *Compare* **heterozygote**. — **homozygotic** *or* **homozygous** *adj.*

Hoogsteen base pair a nucleic-acid base pair that differs from the Watson–Crick base pair. In the Hoogsteen adenine– thymine base pair the 6-NH$_2$ and N-7 of the adenine are hydrogen bonded respectively to the 4-O and H-1 of the thymine. The Hoogsteen guanine–cytosine pair requires that N-1 of the cytosine is protonated. In this base pair the 6-O and N-7 of the guanine are hydrogen bonded respectively to the 4-NH$_2$ and the protonated N-1 of cytosine. In Watson–Crick base pairs the glycosidic bond of both nucleotides has the *anti* conformation, but in the Hoogsteen pairs the glycosidic bond of the purine nucleotide has the *syn* conformation. Hoogsteen base pairs are particularly important in the structure of DNA triple helices, where the third strand forms Hoogsteen pairs to bases in the DNA duplex. [After Karst Hoogsteen (1923–), Dutch–American biochemist, who first described it.]

hopane the pentacyclic triterpene hydrocarbon parent of hopanone and derivatives found in plant resins. *See also* **hopanoids**.



hopanoids pentacyclic sterol-like molecules based on the **hopane** nucleus. They are found in bacteria, some plants and lichens, and in sediments and crude oils, and are said to be the most abundant organic molecules in the biosphere (estimated total biomass 10^{11} to 10^{12} tonnes), thus outranking **cellulose**.

Hopkins–Cole reaction a colour reaction for free or combined tryptophan, in which a violet colour is produced when a solution containing tryptophan is treated with glyoxylic acid (present in impure glacial acetic acid) and subsequently layered onto a solution of pure, concentrated sulfuric acid. [After (Sir) Frederick Gowland Hopkins (1861–1947), British biochemist, and Sydney William Cole (1877–1951).]

HOQNO *or* **HQNO** *abbr. for* 2-*n*-heptyl-4-hydroxyquinoline *N*-oxide; an inhibitor of the mitochondrial respiratory chain at cytochrome bc_1 and of photosynthetic electron flow immediately before cytochrome b_{559}LP.



hordein a type of **glutelin** found in barley.

horizontal gene transfer the transfer of genes from one organism to another (as distinct from vertical gene transfer, i.e. from parent to offspring).

hormone any substance formed in very small amounts in one specialized organ or group of cells and carried (sometimes in the bloodstream) to another organ or group of cells, in the same organism, upon which it has a specific regulatory action; an **endocrine** (def. 2). The term was originally applied to agents with a stimulatory physiological action in vertebrate animals (as opposed to a **chalone**, which has a depressant action). Usage is now extended to regulatory compounds in lower animals and plants, and to synthetic substances having comparable effects. *Compare* **autacoid**, **hermone**. *See also* **secretin**. —**hormonal** *adj.*

hormone cascade *see* **cascade sequence**.

hormone receptor any protein of the plasma membrane, or present intracellularly, that binds a hormone and mediates its physiological effects. Hydrophilic hormones (i.e. those that are proteins, peptides, or other amino acid derivatives) are ligands of plasma membrane receptors, which modulate the activity of intracellular intermediaries. Hydrophobic hormones (e.g. steroids, thyroid hormones, vitamin D derivatives) are ligands of cytosolic or nuclear receptors, which modulate the activity of responsive genes by binding to their **hormone response elements**. Examples include the **glucocorticoid receptor** and **insulin receptor**.

hormone resistance the state of decreased or absent sensitivity to a hormone. It may be primary and due to a defect in a specific receptor (e.g. for glucocorticoids, androgens, estrogens, vitamin D derivatives, thyroid hormones, thyroid stimulating hormone, parathyroid hormone, antidiuretic hormone, insulin) or due to post-receptor defects (e.g. in diabetes mellitus type 2). Acquired resistance may result from damage to a target tissue, in the course of therapy with the hormone, or by immunological mechanisms.

hormone response element *abbr.*: HRE; a specific nucleotide sequence in the promoter region of a structural gene that binds to the DNA-binding domain of a nuclear hormone receptor. The HRE usually consists of two hexanucleotide sequences that are contiguous or separated by three nucleotides, and may be in tandem or in palindromic arrangement.

hormone-sensitive lipase any enzyme of the sub-subclass EC 3.1.1 that, when activated in adipose tissue, catalyses the mobilization of fatty acids into the circulation. Such enzymes are activated by cyclic AMP-dependent phosphorylation under the influence of catecholamines, and are inactivated by insulin-dependent dephosphorylation.

hormonotoxin any conjugate of a peptide hormone and a peptide toxin, e.g. ovine luteinizing hormone–gelonin.

horse radish peroxidase *abbr.*: HRP; a hemoprotein enzyme that is widely used to label antibodies and other proteins in enzyme immunoassays and related procedures such as immunodetection following Western blotting.

host 1 any organism in which another organism, especially a **parasite** or **symbiont**, spends part or all of its life cycle and from which it obtains nourishment and/or protection. **2** any organism that harbours a pathogenic or nonpathogenic infectious agent. **3** the recipient of a transplanted tissue or organ graft. **4** a cell or organism that contains recombinant DNA.

host cell any cell whose metabolism is used for the growth and reproduction of a virus.

host-cell reactivation *abbr.*: HCR; the restoration of activity in a UV-damaged DNA bacteriophage by the excision-repair mechanisms of the host cell in which it multiplies.

host-controlled modification *or* **host-controlled variation** *or* **host-induced modification** *or* **host-induced variation** any nonheritable change in the properties of a DNA bacteriophage resulting from the phage DNA assuming the DNA **modification** pattern characteristic of the host bacterium. It is usually recognized by **restriction** in the efficiency of plating of the newly modified phage on its former host strain. Similar phenomena have been described for viruses infecting eukaryotic cells.

host-induced modification *or* **host-induced variation** *see* **host-controlled modification**.

host–guest chemistry a branch of chemistry in which a larger and structually concave organic molecule (the host) selectively binds to a smaller molecule or ion (the guest). This may mimic a biological effect, or prevent a biological interaction.

host range the spectrum of host organisms that can be infected by a specified infectious agent or parasite.

host–vector system a compatible combination of host and **vector** (def. 3) that allows propagation of DNA.

hot *(in physics) an informal term* describing a substance or material that contains a radionuclide, especially if **carrier-free** or at a dangerously high activity or specific activity. *Compare* **cold**.

hot laboratory *or* **hot lab** *an informal term for* a laboratory reserved and equipped for the manipulation of radioactive substances or materials of (dangerously) high activity.

hot room 1 a room (or laboratory) maintained at a constant, higher-than-ambient temperature. **2** *an informal term for* a room (or laboratory) that is specially equipped to deal with high levels of radioactivity.

hot spot any site at which mutations are observed with an unusually high frequency. Such sites have a highly enhanced, inherent susceptibility to mutation that cannot be ascribed to the type of base pair involved, the way in which it is altered, or the resulting change in any protein encoded by the DNA molecule.

hot start PCR a type of polymerase chain reaction (PCR) designed to minimize nonspecific amplification. Reagents are heated to a temperature that does not permit hybridization between oligonucleotides and the target sequence before the addition of a thermostable DNA polymerase to start the reaction.

hour *symbol*: h *or* hr; a non-SI unit of time equal to 3600 s.

housekeeping genes *see* **constitutive genes**.

Houssay animal a pancreatectomized animal which has also undergone **hypophysectomy**. The latter ameliorates the diabetic state that results from pancreatectomy by abolishing the secretion of **somatotropin**. [After Bernardo Alberto Houssay (1887–1971), Argentinian physiologist and endocrinologist.]

***Hox* gene** *see* **homeotic gene**.

Hp 1 *symbol for* the heptyl group, $CH_3–[CH_2]_5–CH_2–$. **2** *abbr. for* haptoglobin.

HP-1 *abbr. for* helper peak-1 (now called **interleukin 1**).

***Hpa*I** a type 2 **restriction endonuclease**; recognition sequence: GTT↑AAC.

***Hpa*II** a restriction endonuclease that cuts at the sequence CCGG when the first C is unmethylated. ***Msp*I** is unaffected by methylation at this position. Comparison of restriction digests with both enzymes is informative about the methylation of DNA.

HPCE *abbr. for* high performance capillary electrophoresis.

HpETE *abbr. for* hydroperoxyeicosatetraenoate.

hPL *or* HPL *abbr. for* human placental lactogen.

HPLAC *abbr. for* high-performance liquid affinity chromatography.

HPLC *abbr. for* high-pressure liquid chromatography *or* high-performance liquid chromatography.

Hpo *symbol for* the heptanoyl group, $CH_3–[CH_2]_5–CO–$.

HpODE *abbr. for* hydroperoxyoctadecadienoate.

HPR *abbr. for* H protein; a low-M_r, heat-stable, cytoplasmic phosphocarrier protein found in some bacterial species, and concerned in the phospho*enol*pyruvate (PEP)-hexose transferase system for the transport of hexoses across the cell membrane. The phosphate of PEP is transferred transiently to HPR. *See* **enzyme I**, **enzyme II**.

HPRD *abbr. for* human protein reference database; *see* **pathway database**.

H protein *see* **glycine cleavage enzyme**.

HPRT *abbr. for* hypoxanthine phosphoribosyltransferase.

H^+ pump *see* **hydrogen ion pump**.

HQNO *see* **HOQNO**.

hr *abbr. for* hour (now superseded by h).

Hrb a Rab protein (*see* ***RAB***) that is essential for formation of the acrosome of mouse spermatozoa. It is associated with the cytosolic surface of proacrosomic vesicles that fuse to create a single large acrosome, and is required for docking and/or fusion of these vesicles.

HRE *abbr. for* hormone response element.

H1, H2, H3 receptors *see* **histamine receptor**.

H-RNA *abbr. for* heterogeneous nuclear RNA (alternative to hnRNA or HnRNA).

HRP *abbr. for* horse radish peroxidase.

HRT *abbr. for* hybrid-released translation.

HSA *abbr. for* human serum albumin.

Hse *symbol for* a residue of the α-amino acid L-homoserine.

HSE *abbr. for* heat-shock regulatory element or heat-shock response element.

α_2-HS-glycoprotein *or* **fetuin** an α-globulin found in fetal calf serum, where it accounts for up to 45% of the total protein. It has a low isoelectric point and contains up to 35% carbohydrate, having three oligosaccharide chains, each of M_r 3400; it comprises various glycoproteins that differ in M_r. It is a growth factor for a variety of cell types; it also promotes endocytosis, possesses opsonic properties, and influences the mineral phase of bone. The amino-acid sequence has **cystatin** features; two peptides are cleaved from a precursor to form chains held together by a single disulfide bond.

Hsl *symbol for* a residue of the α-amino lactone L-homoserine lactone.

HSL *abbr. for* hormone-sensitive lipase.

hsp *or* **Hsp** *abbr. for* heat-shock protein.

HSP *abbr. for* **1** heat-shock protein. **2** high-scoring segment pair.

Hsp90 a highly conserved molecular chaperone. Other family members are Grp94/gp96 in the endoplasmic reticulum and HtpG in the prokaryotic cytosol. Unlike Hsp70, which promiscuously recognizes a large number of proteins, Hsp90 is characterized by the specific nature of its protein-protein associations. The majority of Hsp90 substrates (usually referred to as 'client' proteins) are involved in regulatory processes, the classical examples being signalling kinases and steroid hormone receptors. Maintenance of the biochemical activity of the clients is entirely dependent on continued interaction with Hsp90..

HSPG core protein *abbr. for* heparan sulfate proteoglycan core protein. *See also* **syndecan**.

HSSP *abbr. for* homology-derived secondary structure prediction; *see* **structure database**.

hst/KS *see* ***KS/hst***.

H strand *abbr. for* heavy strand.

HSV *abbr.for* herpes simplex virus.

5-HT *abbr. for* 5-hydroxytryptamine (i.e. **serotonin**).

HTG *abbr. for* high-throughput genomic sequence.

HTH *abbr. for* helix-turn-helix.

HTLV *abbr. for* human T-cell lymphotropic virus; a **retrovirus** that causes a rare leukemia.

HTML *abbr. for* hypertext markup language; *see* **markup language**.

Htr either of two transmembrane proteins (HtrI or HtrII) that extend far into the cytoplasm of halobacteria and mediate phototaxis signalling from a sensory rhodopsin (SRI or SRII, respectively) to the flagellar motor.

H^+-transporting ATP synthase EC 3.6.1.34; *systematic name*: ATP phosphohydrolase (H^+-transporting); *other names*: H^+-transporting ATPase; mitochondrial ATPase; chloroplast ATPase; coupling factors $F_0{\bullet}F_1$, $C_0{\bullet}F_1$. The enzyme that is responsible for the phosphorylation of ADP to ATP in mitochondria, during **oxidative phosphorylation**. *In vitro* it can function as an ATPase. The 3-D structure is known for the major components of bovine heart mitochondrial enzyme. The enzyme comprises an intrinsic membrane domain, F_0, linked by a stalk to a globular catalytic domain, F_1, and is hence sometimes termed the F_0F_1 complex. Energy released by hydron flux through F_0 leads to ATP synthesis by F_1; the stoichiometry is approximately $3H^+$ per ADP phosphorylated. F_1 (371 kDa) has the subunit composition: $3\alpha,3\beta,\gamma,\delta,\varepsilon$. The ε and γ subunits form a shaft inserted at one end into F_0 and at the other into F_1. The α and β (catalytic) subunits are arranged round it alternately; the three β subunits have different conformations during the synthesis cycle. The N- and C-terminal regions of γ form an antiparallel coiled coil; the α and β proteins are essentially beta barrels. There are several proteins in the F_0 component, the main subunits of which in eukaryotes are named A to G. Twelve C subunits form a channel within the membrane. The C chain is the protein that accumulates in ceroid lipofuscinosis (**Batten's disease**). It is a proteolipid encoded by two genes which code for two precursor proteins, P_1 and P_2, having different signal peptides for locating the proteins in mitochondria, but the same structure in the mature protein. Two B subunits are anchored, with an A subunit, into the membrane, and through a δ subunit bind F_1. The complex formed by $AB_2\delta\alpha_3\beta_3$ is called the stator; that formed by $C_{12}\varepsilon\gamma$ is called the rotor, because it rotates during the flow of hydrons through the F_0 channel.

H^+-transporting pyrophosphatase an integral membrane protein (80 kDa) that contains 16 transmembrane segments and is ubiquitous in vacuolar membranes in plants. It is also present in some species of archaea. In the presence of K^+ it hydrolyses dimagnesium pyrophosphate of the cytosol and transports H^+ into the vacuole. Ca^{2+} is a potent inhibitor, as is aminomethylenediphosphonate. In immature tissues it is more active than the V-type H^+ ATPase, the opposite being true in mature tissues.

huangosome *a colloquial term for* a bilayered **liposome**. *Compare* **bangasome**.

Hudson's convention a convention, no longer used, for designating anomeric configurations in monosaccharides. The anomer in the D-series with the highest positive rotation (or lowest negative rotation) was designated the α form and the anomer with the lowest positive rotation was called the β form. The reverse applied in the L-series, the anomer with the lowest positive rotation (or the highest negative rotation) being designated the α form. The α and β descriptors now refer to the absolute structural relationships. *See* **anomer**, **Haworth representation**.

Hughes press a device to disrupt microorganisms. It consists of a steel cylinder in which a paste of the microorganisms in question, mixed with abrasives, is subjected to sudden blows by a steel piston driven by a fly-press; the piston forces the crushed material out of the cylinder into a reservoir. At temperatures below –20°C no abrasives are needed, ice crystals taking their place. *See also* **French pressure cell**. [After D. E. Hughes (1922–), who published the design in 1951.]

HUGO *abbr. for* Human Genome Organization; an international organization of scientists involved in the **Human Genome Project**, the global initiative directed at mapping and sequencing the human genome. It was established in 1989, and carries out a coordinating role, supporting data collection for constructing genetic and physical maps of the human genome, organizing the Single Chromosome Workshops and other workshops and promoting consideration of ethical, legal, social, and intellectual property issues. It fosters exchange of data and biomaterials. The Human Genome Project is, however, not under the central control or direction of any individual, group, or organizing committee, the work being done in many countries and coordinated by the scientists carrying out the work.

human *abbr. (in bionomenclature)*: h *or (formerly)* H; of, relating to, characteristic of, obtained from, or being a member of the species *Homo sapiens*. For names of substances or products beginning with the word human (e.g. human choriogonadotropin, human serum albumin) see at the corresponding general entry.

human gene index *abbr.*: HGI; a database of The Institute for Genome Research (TIGR) that integrates data from international human gene research projects, including gene expression patterns, cellular roles, functions, and evolutionary relationships.

Human Genome Project *see* **HUGO**

human immunodeficiency virus *see* **HIV**.

humanize to produce chimeric monoclonal antibodies that, by use of recombinant DNA technology, contain sequences translated from components of human immunoglobulin genes.

humanized antibody a modified antibody; since human monoclonal antibodies cannot be generated in the same way as in mice, and the body reacts to a mouse antibody the 6 complementary determining regions of a high affinity rodent monoclonal antibody are grafted on to a completely human IgG framework without loss of specific activity.

human T-cell lymphotropic virus *see* **HTLV**.

humectant **1** producing moisture. **2** any substance added to another substance or material to keep it moist.

humic acid any of the mixture of complex macromolecules having polymeric phenolic structures and extractable from soils and peat. It is produced by the oxidative degradation of lignin and has the ability to chelate metals, especially iron.

humidity cabinet *or* **humidity chamber** an enclosure in which the humidity is maintained at a constant, often high level. It is useful for keeping experimental samples or materials moist or at a predetermined moisture content.

humin the very dark-brown or black insoluble material that is produced when carbohydrate-containing proteins are subjected to acid hydrolysis.

humor *the US spelling of* **humour**.

humoral of, contained in, or involving the blood or other body fluid; consisting of, relating to, or involving some chemical agent or substance contained in a body fluid, especially the blood.

humoral immunity any specific immunity mediated by antibodies (i.e. **humoral antibodies**) present in blood plasma, lymph, and tissue fluids, and that may also become attached to cells.

humour *or (US)* **humor** *a former name for* any of the body fluids, e.g. blood, lymph.

humulin 1 human insulin made using cDNA technology. **2** the bitter aromatic principle of hops (lupulin).

humus the dark-brown or black complex mixture of colloidal organic material that results from the decomposition of plant and animal material in the soil. It is of great importance for plant growth.

hunchback a segmentation protein in insects. Similar to **ikaros**, it is a zinc-finger protein and is encoded by a **gap gene**. *Compare* **Krüppel**.

Hunter syndrome *an alternative name for* mucopolysaccharidosis II. *See* **mucopolysaccharidosis**. [After Charles Hunter (1872–1955), British physician.]

huntingtin *see* **Huntington's disease**.

Huntington's disease *or* **Huntington's chorea** an autosomal dominant genetic disease characterized by involuntary (choreic) movements and dementia over a 10–20 year course. It is inevitably fatal. Linking studies using a variety of RFLPs have localized the defective gene to a site on the short arm of chromosome 4. There is a selective loss of a group of neurons; the biochemical basis for their loss is unknown. The gene, which encodes a 3145-residue product, **huntingtin**, of unknown function, contains a polymorphic trinucleotide repeat of the codon for glutamine, CAG, within the coding sequence. Normals have 35–37 of these repeats. In no case has any individual with more than 41 repeats been found to be free of the disease. [After George Huntington (1850–1916), US physician.]

HU protein an abundant bacterial histone-like protein that has the ability to wrap and bend DNA *in vitro*, and is thought to play a role in chromosome DNA topology, probably by facilitating the action of gyrase. *See* **DNA topoisomerase** type II.

Hurler–Scheie compound syndrome *an alternative name for* **mucopolysaccharidosis I H/S**.

Hurler syndrome *an alternative name for* mucopolysaccharidosis I H; *see* **mucopolysaccharidosis**. [After Gertrude Hurler (1889–1965), Austrian physician.]

HUT *(in clinical chemistry) abbr. for* UDPglucose-hexose-1-phosphate uridylyl transferase (EC 2.7.7.12).

Hutchinson–Gilford syndrome a rare form of premature ageing characteristic of children and associated with truncation of **lamin** A. [After Jonathan Hutchinson (1828–1913), British surgeon, and Hastings Gilford (1861–1941), British physician.]

HVA *abbr. for* homovanillic acid.

HVE *abbr. for* high-voltage electrophoresis.

Hvidt–Nielsen mechanism a proposed mechanism to account for the kinetics of hydrogen exchange between protein molecules in solution and solvent water molecules. It is considered that protein molecules exist in solution in more than one conformational state and that hydrogen atoms in the interior of the protein molecule in the most stable conformational state are inaccessible to exchange; these hydrogen atoms may become transiently externalized, and hence accessible to exchange, in one or more of the other conformational states. [After Aasa Hvidt and S. O. Nielsen.]

Hx *abbr. for* hepoxilin.

Hx^c *symbol for* the cyclohexyl group (alternative to cHx).

hyal+ *a variant form of* **hyalo+** (before a vowel).

hyaladherin *a name sometimes used for* proteins in the **extracellular matrix** that bind to **hyaluronate**.

hyaline clear, transparent; with no inclusions.

hyalo+ *or (before a vowel)* **hyal+** *comb. form* denoting glassy, transparent.

hyaluronan *an alternative name for* **hyaluronate**.

hyaluronate *or* **hyaluronan** the naturally occurring anionic form of hyaluronic acid; any member of a group of glycosaminoglycans, the repeat units of which consist of $\beta 1 \rightarrow 4$-linked D-glucuronyl-($\beta 1 \rightarrow 3$)-*N*-acetyl-D-glucosamine. Most preparations contain 1–2% by mass of protein, and have M_r values in the range 5×10^4 to 8×10^6 depending on source and methods of preparation and determination. Hyaluronates are widely distributed in many tissues, especially in the vitreous humour of the eye, synovial fluid, and umbilical cord. They have an important role in the formation of proteoglycan aggregates. Hyaluronates form very viscous solutions and gels in water, a property that may be important in protecting animal organisms against invasion by bacteria.

hyaluronidase *or* **mucinase** *or* **spreading factor** *a trivial name for* either of the glycosidases hyaluronoglucosaminidase (EC 3.2.1.35) and hyaluronoglucuronidase (EC 3.2.1.36), and for the carbon–oxygen lyase hyaluronate lyase (EC 4.2.2.1). These enzymes have in common the ability to depolymerize hyaluronidate by cleavage of glycosidic bonds; e.g. hyaluronoglucosaminidase catalyses the random hydrolysis of 1,4-linkages between *N*-acetyl-*β*-D-glucosamine and D-glucuronate residues in hyaluronate. Hyaluronidases occur in certain animal tissues, e.g. sperm acrosome, and in some bacteria, e.g. *Clostridium* spp., and enhance the penetration of various substances and pathogens through the extracellular matrix (hence the name 'spreading factor').

hyaluronidase deficiency *an alternative name for* **mucopolysaccharidosis IX**.

hyamine hydroxide methylbenzethonium hydroxide; a water-soluble organic base, useful biochemically because it and some of its salts are soluble in organic solvents such as chloroform and toluene. It is therefore used to absorb radioactive CO_2 released during metabolic incubations; the resultant hyamine carbonate can then be dissolved in a scintillation cocktail for counting. It is also used as a topical anti-infective agent.



hybrid 1 something derived from heterogeneous sources or composed of different or incongruous elements. **2** *(in genetics)* the offspring of two animals or plants of different species, or (less strictly) different varieties. **3** *(in chemistry)* a bond or valence orbital obtained by the linear combination of two or more different atomic orbitals.

hybrid antibody any artificially produced immunoglobulin molecule in which the combining sites are of different specificities.

hybrid-arrested translation *abbr.*: HART; a method for analysing the relationship between a DNA sequence, its corresponding messenger RNA (mRNA), and the protein for which it codes, based on the observation that mRNA when hybridized with its complementary DNA is not translated in eukaryotic cell-free systems whereas heat-induced dissociation of the hybrid completely restores translational activity. The method has been used to map precisely specific protein-coding regions in **restriction fragments** of DNA. *See also* **hybrid-released translation**.

hybrid cell any cell containing the nuclei and cytoplasms from differing cells, formed artificially by **cell fusion**.

hybrid DNA 1 artificial duplex DNA produced by collinear (i.e. covalent) union of two (or more) fragments of duplex DNA (i.e. **recombinant DNA**; *see also* **plasmid chimera**). **2** artificial duplex DNA produced by collateral (hydrogen bonded) union of two incompletely complementary, single strands of DNA. *Compare* **DNA–RNA hybrid**.

hybridization *or* **hybridisation 1** the act or process of forming a genetic **hybrid** (def. 2) by cross-breeding, or other unnatural recombination. **2** the act or process of forming a macromolecular **hybrid** (def. 1) by the artificial recombination of subunits, e.g. of polynucleotide strands or polypeptide chains. **3** the mathematical combination of atomic orbitals to form an orbital **hybrid** (def. 3).

hybridization analysis a method of testing for complementarity in the base sequences of two polynucleotides from different sources, based on the ability of complementary single-stranded DNA molecules to form duplex DNA molecules on being annealed together, and the ability of single strands of DNA and RNA similarly to form **DNA–RNA hybrids**.

hybridization probe *see* **probe** (def. 3).

hybrid myeloma *see* **hybridoma**.

hybridoma any permanent **cell line** derived from an artificial **somatic cell hybrid** formed between a cultured neoplastic lymphocyte and a normal primed B or T lymphocyte, all the cells of which express the specific immune potential of the normal parental cell. The term is derived from a contraction of 'hybrid' and 'myeloma'. Hybridomas are produced by the technique of **cell fusion**, using, e.g., a suspension of mouse myeloma or thymoma cells from a selected established cell line to which is added a preparation of spleen cells (predominantly normal lymphocytes) from mice or other animals that have been immunized against a specified antigen. After cell fusion, selection is aided by the use of **HAT** medium, which kills HGPRT$^-$ myeloma cells, and lymphocytes that have not fused do not survive in culture. This treatment thus selects for the immortalized hybridoma cells that retain the lymphocyte HGPRT. Such hybrid cells are both permanently adapted to growth in culture and capable of forming specific antibody-producing tumours *in vivo*. A B-cell hybridoma continuously secretes pure **monoclonal antibody** of a predetermined specificity and may thus be used for the facile large-scale production of such antibody.

hybrid-released translation *abbr.*: HRT; a method in which cloned DNA is bound to a nitrocellulose filter and hybridized with unfractionated mRNA, or even total cellular RNA. After washing the filter, any mRNA that has hybridized with the DNA is eluted and translated in a cell-free translation system, thus revealing the product that is encoded by the DNA. *See also* **hybrid-arrested translation**.

hydantoin *generic name for* 2,4-imidazolidinedione or its derivatives. A hydantoin is formed by the reaction of an isocyanate, commonly phenylisocyanate, with the free amino group of an amino acid, and the cyclization of the hydantoic acid derivative initially formed. When an isocyanate reacts with the N-terminal amino group of a peptide, the corresponding hydantoin is formed, with simultaneous cleavage of the substituted N-terminal amino-acid residue from the peptide.

hydr+ *a variant form of* **hydro+** (sometimes before a vowel).

hydrase *an obsolete term for* **hydratase**.

hydratase *see* **dehydratase**.

hydrate **1** any adduct of water with another compound or element, usually in definite molecular proportions. **2** to form a **hydrate** (def. 1); to undergo **hydration**. **3** to cause to take up or to combine with water. **4** to maintain or restore the normal proportion of water in the body (of someone or something). —**hydrated** *adj.*

hydration **1** the act or process by which water molecules surround and bind to molecular entities. **2** the addition of H and OH to a chemical species. **3** the formation of a **hydrate** (def. 1). **4** the quality or state of being hydrated. **5** the introduction of additional water into the body (of something or someone). *Compare* **anhydrous**, **dehydration**, **solvation**.

hydration shell the layer of water molecules surrounding an ion or molecule in aqueous solution.

hydraulic **1** operated by pressure transmitted through a liquid, e.g. through water or oil. **2** of or concerning hydraulics (i.e. fluid mechanics).

hydrazine $H_2N–NH_2$; an oily liquid, fuming in air, that is very toxic and possibly a carcinogen. It is available as a hydrate and as various salts. *See also* **hydrazinolysis**.

hydrazinolysis the cleavage of amide and peptide bonds by heating at 100°C with **hydrazine** in anhydrous conditions to form the corresponding acyl hydrazides. This reaction is useful in the determination of C-terminal amino-acid residues in peptides and proteins as all the other amino-acid residues will be converted to their hydrazides and only the C-terminal amino acid will be set free in an underivatized form.

hydrazone any condensation product of the type R′R″C=N–NHR, formed between carbonyl compounds (R′R″=CO) and hydrazine or a substituted hydrazine. *See also* **osazone**, **phenylhydrazone**.

hydride **1** the ion H^-, hydrogen anion. It has an independent existence only in the salt-like hydrides formed by strongly electropositive elements (*see* def. 2) but is also sometimes regarded as participating in the formation of complex hydrides (*see* def. 4) and in certain oxidation–reduction reactions (*see* **hydride-ion transfer**). **2** any stoichiometric binary compound of hydrogen with one of many (but not all) of the elements in groups 1, 2, and 3 of the IUPAC **periodic table**, e.g. NaH or CaH_2. Such hydrides are salt-like ionic compounds, are solids at ambient temperatures, and on fusion can be electrolysed (dihydrogen then being liberated at the anode). They are readily decomposed by water and are potent reducing agents. **3** Any stoichiometric compound of hydrogen with one (or sometimes more than one) of many of the elements in other groups of the periodic table, and also with boron. Such hydrides are volatile covalent compounds containing one atom of the element per molecule, e.g. PbH_4, or sometimes more than one, e.g. Si_3H_8; in the latter type certain of the hydrogen atoms may be present as bridges, as in B_2H_6. **4** any salt-like compound containing a complex anion that may be considered as formed by coordination of a hydride ion to an uncharged hydride, e.g. KBH_4 (*see* **borohydride**) or $LiAlH_4$; such compounds are widely used in organic chemistry as reducing agents or for introduction of tritium, ^3H. **5** any (frequently nonstoichiometric) product formed by uptake of dihydrogen by certain transition metals, especially palladium.

hydride-ion transfer *term conventionally often applied to* a chemical or enzyme-catalysed oxidation–reduction reaction involving the transfer from one molecule to another of a hydrogen atom together with its associated pair of bonding electrons. Such a reaction may notionally be considered to involve the transfer of a hydride ion without such an ion ever existing as a free entity. Examples include the **Cannizzaro reaction** and reactions of the general type

$$\mathrm{NADH + M + H^+ \rightleftharpoons NAD^+ + MH_2},$$

where M is a substrate molecule undergoing enzymic reduction, to which a hydride ion is transferred from NADH.

hydrindantin the reduced form of **ninhydrin**. It is sometimes used in conjunction with ninhydrin in the chromogenic determination or visualization of amino or imino groups.

hydrion *a former name for* **hydrogen ion**.

hydro+ *or (sometimes before a vowel)* **hydr+** *comb. form* **1** indicating or denoting water, liquid, or fluid. **2** indicating the presence of hydrogen in a compound.

hydrocarbon **1** any organic compound composed exclusively of hydrogen and carbon. **2** of, pertaining to, or being a **hydrocarbon** (def. 1) or a chemical group or side chain composed of hydrogen and carbon only.

hydrocarbyl any univalent group formed from a hydrocarbon by removal of a hydrogen atom; e.g. methyl (from methane).

hydrocolloid any colloidal substance for which the dispersing liquid is water or an aqueous solution.

hydrocortisone *an alternative name for* **cortisol**.

hydrodynamic **1** of or concerned with the mechanical properties of fluids. **2** of, pertaining to, or concerned with **hydrodynamics**.

hydrodynamic particle the entity formed by any (macro)molecule in solution together with its solvation shell.

hydrodynamic radius the radius of a (macro)molecule or other particle in solution as determined by a hydrodynamic method, e.g. sedimentation equilibrium.

hydrodynamics the branch of physics concerned with the forces acting on or exerted by fluids.

hydrodynamic shear the microscopic shear force caused by the motion of different layers in a fluid, where the layers move at different velocities. This acts to break any molecule sufficiently long to bridge the layers, e.g. DNA.

hydrodynamic volume *(of a molecule in solution)* the sum of the time-average of the molecular volume and the volume of the solvent molecules associated with it.

hydrogel any **gel** (def. 1) in which water is the liquid component. *Compare* **hydrosol**.

hydrogen *symbol*: H; the lightest of the elements and the most abundant in the universe. It exists as an odourless, colourless, flammable diatomic gas, dihydrogen, H_2, and forms compounds with most of the elements, being present in water and all organic compounds. There are two naturally occurring isotopes, hydrogen-1 (**protium**) and hydrogen-2 (**deuterium**), and one artificial isotope, hydrogen-3 (**tritium**), which is radioactive.

hydrogenase an enzyme that catalyses the production or consumption of dihydrogen. Hydrogen is produced by hydrogenases during the photosynthetic cleavage of water, and by fermentation processes in many anaerobic organisms. Hydrogen is also produced by **nitrogenase** as a by-product of the nitrogen-reducing reaction, but this enzyme not defined as a hydrogenase. Hydrogen is consumed by hydrogen-uptake hydrogenases in many bacteria, with the concomitant reduction of compounds such as oxygen, which is reduced to water, sulfate to sulfide, or carbon monoxide to methane. One of the most common hydrogen-consuming hydrogenases is hydrogen:quinone oxidoreductase, EC 1.12.7.2; in nitrogen-fixing bacteria, this enzyme recycles H_2 produced by nitrogenase to increase the production of ATP and to protect nitrogenase against inhibition or damage by O_2. In order to react with other electron carriers the hydrogenases employ various cosubstrates. Hydrogen dehydrogenase, EC 1.12.1.2, catalyses the reaction: H_2 + NAD^+ = H+ + NADH and contains FMN. This enzyme is structurally related to mitochondrial Complex I. EC 1.12.1.3 is similar, but reduces $NADP^+$. Cytochrome-C_3 hydrogenase, EC 1.12.2.1 is used by sulfate-reducing bacteria. Almost all hydrogenases are iron–sulfur proteins. The defining characteristic is an active site containing iron that has carbonyl and usually cyanide ligands. Two main nonhomologous classes are recognized: (1) hydrogenases containing an H cluster comprising a dimer of iron atoms linked to a [4Fe-4S] cluster,known as [Fe]- or [FeFe]-hydrogenases (*see* **iron hydrogenase**), and those containing nickel and iron (*see* **nickel–iron-hydrogenase**). In addition there is a third type, containing iron and no iron–sulfur clusters, of which the only example known so far is 5,10-methenyltetrahydromethanopterin hydrogenase (EC 1.12.98.2).

hydrogenate to undergo or cause to undergo reduction by addition of the hydrogen atoms of dihydrogen, usually with the aid of a catalyst such as finely divided forms of nickel, palladium, or platinum. The process is of industrial importance in petroleum refining, the petrochemical industry and the hardening of fats. **—hydrogenated** *adj.*; **hydrogenation** *n.*

hydrogen bond an association between an electronegative atom, e.g. fluorine, oxygen, nitrogen, or sulfur, and a hydrogen atom attached to another such electronegative atom. Although **hydrogen bonding** is due to interaction between dipoles, the force of attraction is large enough to permit formation of aggregates of small molecules or to stabilize the conformation of many macromolecules. The spatial relation of the donor and acceptor atoms is such that the hydrogen atom lies very close to the straight line between them.

hydrogen carrier *a name sometimes used for* any electron carrier that undergoes oxidation–reduction reactions by the loss or gain of hydrogen atoms, e.g. NADH, FADH.

hydrogen dehydrogenase *the recommended name for* the enzyme, EC 1.12.1.2, *also known as* **hydrogenase**, that catalyses the reaction:

$$H_2 + NAD^+ = H^+ + NADH.$$

It is a flavoprotein; iron and nickel are cofactors; the molecule is heterotetrameric. It may form part of a system involving **hydrogenase** (def. 1). For example, in *Alcaligenes eutrophus*, the α and γ subunits form one dimer (FMN, 4Fe–4S cluster, NADH oxidoreductase); and the β and δ subunits form the other dimer, which exhibits **hydrogenase** activity with artificial electron acceptors.

hydrogen–deuterium exchange *see* **hydrogen exchange**.

hydrogen electrode an electrode that is reversible to hydrogen ions and dihydrogen molecules. It is formed by bubbling pure dihydrogen gas over a metal wire or a piece of foil whose surface is able to catalyse the reaction:

$$0.5H_2(g) = H^+ + e \qquad (1)$$

where e represents an electron. The most useful catalyst is platinum black on a platinum substrate. Hence the catalyst establishes an equilibrium between dihydrogen molecules (or hydrogen atoms) and the hydrogen ions (i.e. hydrons) in the solution in which the metal electrode is immersed. If the partial pressure (in atm) of dihydrogen gas at the electrode is p_{H2}, the half-cell potential, E_H, of reaction (1) is given by:

$$E_H = E^o{}_H - (RT/F)\ln(a_{H^+}/p_{H_2}) \qquad (2)$$

where R is the gas constant, F the faraday constant, T the thermodynamic temperature, and a_{H^+} the hydrogen-ion activity. $E^o{}_H$, the standard potential of the hydrogen electrode, is, by convention, zero at all temperatures, hence at $p_{H_2} = 1$, the usual standard state, equation (2) becomes:

$$E_H = -(RT/F)\ln a_{H^+}.$$

Thus the hydrogen electrode is the ultimate reference electrode for the determination of pH values. It should be noted that the potential of any single electrode cannot be determined by itself; another electrode must be connected to the solution.

hydrogen exchange *or* **hydrogen–deuterium exchange** a technique useful for demonstrating conformational differences between samples of the same protein and for providing insight into the dynamics of protein conformations in solution. It can be observed using nuclear magnetic resonance spectroscopy. The method is based on observation of the kinetics of the noncatalysed exchange of hydrogen atoms in peptides and proteins with protons or other hydron isotopes in aqueous solutions and the effects of pH (or p^2H), temperature, etc. on the process.

hydrogen ion *or (formerly)* **hydrion** the cation, H^+, derived from the hydrogen atom. In aqueous solution it is mostly in the hydrated form, oxonium (H_3O^+). In nonaqueous solution it is likely, by analogy, that it is attached particularly to one solvent molecule, e.g. ROH_2^+ in an alcohol, R_2COH^+ in a ketone, RNH_3^+ in an amine, etc. *See also* **hydron**, **proton** (defs 1, 2).

hydrogen-ion concentration *see* **pH**.

hydrogen-ion pump any of a number of membrane proteins that transport hydrogen ions through membranes. The H^+- transporting ATPase of fungi and plants (EC 3.6.1.35) has an action similar to that of the **H^+-transporting ATP synthase** of mitochondria, but without coupling factors; it is an integral membrane glycoprotein. The proton gradient it generates drives the active transport of nutrients by H^+-symport. The **vacuolar ATPase** is another type.

hydrogen lamp *or* **hydrogen discharge lamp** a high-voltage discharge tube with a quartz window and containing dihydrogen at low pressure, in which the glow produced by excitation of the dihydrogen molecules is concentrated in a long capillary tube joining the two electrodes; this arrangement gives increased intensity. It produces a continuous emission spectrum over the range 180–350 nm. *See also* **deuterium (discharge) lamp**.

hydrogenlyase *see* **hydrogenase** (def. 1).

hydrogenosome an organelle with a double membrane occurring in the cytoplasm of some anaerobic flagellate protozoans. They are chromatic granules of high density containing enzymes, including hydrogenase, that catalyse the conversion of pyruvate to acetate, CO_2, and H_2. These organelles may substitute for mitochondria (which are absent from such organisms).

hydrogen peroxide H_2O_2; the product of reactions catalysed by NADPH oxidase of phagocytes, cytochrome oxidase of mitochondria, acyl-CoA dehydrogenase of peroxisomes, glycolate oxidase of glyoxysomes, and xanthine oxidase of liver and plasma. It is rapidly eliminated by catalase, glutathione peroxidase, and thioredoxin-linked reactions. Although H_2O_2 is poorly reactive, it is rapidly converted into the highly reactive hydroxyl radical (–OH) by transition metal ions, especially iron, and by ultraviolet light. In some plants it is a second messenger in the response to hormones, pathogenic infection, and abiotic stress. .

hydrolase any enzyme of class EC 3 that catalyses the hydrolysis of various bonds, e.g. C–O, C–N, C–C, phosphoric anhydride bonds, etc. Often the name of a hydrolase is formed from the name of the substrate and the suffix '-ase'.

hydrolysate *or (sometimes US)* **hydrolyzate** any substance or mixture of substances produced by hydrolysis.

hydrolyse *or (US)* **hydrolyze** to subject to, to undergo, or to effect **hydrolysis**. —**hydrolysable** *or (US)* **hydrolyzable** *adj.*; **hydrolysation** *or (US)* **hydrolyzation** *n.*

hydrolysis (*pl.* **hydrolyses**) the rupture of one or more chemical bonds by reaction with, and involving the addition of, the elements of water; **solvolysis** by water.

hydrolytic of, pertaining to, producing, or produced by **hydrolysis**.

hydrolyzate *an alternative US spelling of* **hydrolysate**.

hydrolyze *an alternative US spelling of* **hydrolyse**.

hydrometer an instrument used to measure the **density**, or **relative density**, of a liquid. It usually consists of a glass (or plastic) bulb, weighted at the bottom so that it floats upright, and fitted with a stem carrying a scale. The point on the scale that is level with the surface of the liquid indicates the (relative) density of the liquid.

hydron *symbol*: H^+; *the recommended name for* the cation derived from an atom of hydrogen in its natural isotopic abundance. *See also* **hydrogen ion**, **proton** (defs 1, 2).

hydronate to combine with a **hydron** or hydrons. —**hydronation** *n.*

hydronium ion *an alternative name (now disfavoured) for* **oxonium** (def. 1).

hydropathy a measure of hydrophobicity. *See* **hydrophobic**. –**hydropathic** *adj.*

hydropathy profile a graphical representation of the hydropathic nature of a protein sequence. Within a profile, hydropathy values are calculated in a sliding window and plotted for each residue in the sequence. Resulting graphs show characteristic peaks and troughs, corresponding to the most hydrophobic and hydrophilic regions of the sequence respectively. They are most frequently used to predict the presence of **transmembrane domains**.

hydroperoxide any organic compound in which one hydrogen atom of a hydrocarbon is replaced by the –O–OH group.

hydroperoxyeicosatetraenoate *abbr.*: HpETE; any of various related products of the action of **lipoxygenase** on arachidonate, (all-*Z*)-eicosa-5,8,11,14-tetraenoate. The most notable are 5(*S*)-HpETE, (6*E*,8*Z*,11*Z*,14*Z*)-(5*S*)-5-hydroperoxyeicosa-6,8,11,14-tetraenoate; 12(*S*)-HpETE, (5*Z*,8*Z*,10*E*,14*Z*)-(12*S*)-12-hydroperoxyeicosa-5,8,10,14-tetraenoate; and 15(*S*)-HpETE, (5*Z*,8*Z*,11*Z*,13*E*)-(*S*)-15-hydroperoxy-5,8,11,13-eicosatetraenoate. Their species distribution follows that of the lipoxygenases. HpETEs function as precursors of hydroxyeicosatetraenoates, leukotrienes, dihydroxyeicosatetraenoates, hepoxilins, and lipoxins, but they also have biological activity in their own right, e.g. regulation of electrolyte flux, release of histamine, regulation of eicosanoid and corticosterone synthesis, and regulation of oocyte maturation. 12-HpETE inhibits platelet thromboxane synthase and prostaglandin-endoperoxide synthase, and acts as a second messenger in *Aplysia* sensory neurons.



5(*S*)-HpETE



12(*S*)-HpETE

hydroperoxyoctadecadienoate *abbr.*: HpODE; any of various related products of the action of **lipoxygenase** on linoleate, (all-*Z*)-octadeca-9,12-dienoate. The most notable are 9(*S*)-HpODE, (10*E*,12*Z*)-(9*S*)-octadeca-10,12-dienoate; and 13(*S*)-HpODE, (9*Z*,11*E*)-(13*S*)-octadeca-9,11-dienoate.

hydrophilic 1 tending to dissolve in water; having a strong affinity for water; readily mixing with or wetted by water. *See also* **lyophilic**. **2 polar**. *Compare* **hydrophobic**. —**hydrophilicity** *n.*

hydrophobic 1 tending not to dissolve in water; having a low affinity for water; not readily mixing with or wetted by water. **2 nonpolar**. *Compare* **hydrophilic**. *See also* **lyophobic**. —**hydrophobicity** *n.*

hydrophobic bond *a term sometimes used incorrectly for* a **hydrophobic interaction**.

hydrophobic chromatography *or* **hydrophobic affinity chromatography** *or* **hydrophobic interaction chromatography** a technique for the separation and purification of proteins and other substances by **adsorption chromatography** on polysaccharide or other gels containing lipophilic substituents (which may or may not bear terminal ionizable groups). These hydrophobic centres on the gel interact with nonpolar amino-acid residues exposed on the surface of the protein molecules being separated.

hydrophobic interaction *or (discouraged)* **apolar bond** the tendency of hydrocarbons (or of lipophilic hydrocarbon-like groups in solutes) to form intermolecular or intramolecular aggregates in polar solvents. *See also* **apolar interaction**.

hydrophobic pocket *(in a protein)* a binding site (crevice, pocket) that contains mostly hydrophobic amino acids. For example, the binding site for the aromatic side chains of the specific substrates in **chymotrypsin** is a hydrophobic pocket, consisting of a groove in the enzyme, 100–120 nm deep, and 35–40 nm by 55–65 nm in cross section, lined with non-polar amino-acid side chains. *See also* **heme pocket**.

hydrophobic residue any building block of a polymer, the residue of which in that polymer is hydrophobic. The term is applied especially to amino-acid residues exhibiting such properties in polypeptides (e.g., valine, leucine, phenylalanine).

hydrophobin any of a family of membrane proteins present in some fungi that are involved in cell adhesion and morphogenesis. They have a characteristic domain that contains eight cysteine residues.

hydroquinone 1 1,4-benzenediol; *p*-dihydroxybenzene; quinol. *Compare* ***p*-benzoquinone**, **pyrocatechol**. *See also* **quinhydrone**. **2** any member of a class of aromatic *p*-diols derivable from *p*-quinones (*see* **quinone** (def. 2)) by reduction of two CO groups to COH groups with any necessary rearrangement of double bonds; any compound containing a quinol nucleus. *See also* **quinol** (def. 2), **semiquinone**. *Compare* **catechol** (def. 2).

hydrosol any **sol** in which water is the liquid component. *Compare* **hydrogel**.

hydrous *(of a chemical compound)* containing combined water (usually in stoichiometric proportions).

hydroxide 1 *or (formerly)* **hydroxyl** the ion OH^-. **2** any inorganic or organic compound containing or dissociating to give this ion. Hydroxides that are soluble in water, and can dissociate, give aqueous solutions with an alkaline reaction ($\text{pH} > 7$).

hydroxo+ *comb. form* indicating the presence of a OH^- ligand in a coordination compound.

hydroxocobalamin *or* **vitamin** $\mathbf{B_{12b}}$ a form of vitamin B_{12} in which a hydroxide ion is in coordinate linkage to the sixth (i.e. β) position on the cobalt atom in a molecule of **cobalamin**; the conjugate base of aquacobalamin.

hydroxonium ion *an alternative name (now disfavoured) for* **oxonium** (def. 1).

hydroxy denoting the presence in a compound of one or more **hydroxyl** groups.

hydroxy+ *comb. form (in chemical nomenclature)* denoting the presence of one or more **hydroxyl** groups; the number of hydroxyl groups may be specified, e.g. dihydroxy+ (two), trihydroxy+ (three), etc.

hydroxy acid any organic acid containing one or more **hydroxyl** groups.

2-hydroxy-acid oxidase EC 1.1.3.15; *systematic name*: (*S*)-2-hydroxy-acid:oxygen 2-oxidoreductase; *other name*: glycolate oxidase; an enzyme that catalyses the oxidation by dioxygen of (*S*)-2-hydroxy-acid to 2-oxo-acid and H_2O_2. It is a peroxisomal enzyme in plants that is involved in the conversion of glycolate to glycine in **photorespiration**. The coenzyme is FMN.

3-hydroxyacyl-CoA dehydrogenase EC 1.1.1.35; *systematic name*: (*S*)-3-hydroxyacyl-CoA:NAD$^+$ oxidoreductase; *other names*: *β*-hydroxyacyl dehydrogenase; *β*-keto-reductase; an enzyme of the **beta-oxidation system**. It catalyses the oxidation by NAD$^+$ of *s*-3-hydroxyacyl-CoA to 3-oxoacyl-CoA with formation of NADH. *See also* **fatty-acid oxidation complex, peroxisomal bifunctional enzyme**.

hydroxyallysine 5-hydroxy-6-oxonorleucine; 2-amino-5-hydroxyadipaldehyde. An *α*-amino acid not normally found in proteins, but enzymically formed from 5-hydroxylysine *in situ* as an intermediate in the creation of covalent cross-links between adjacent polypeptide strands during the maturation of certain connective tissue proteins, e.g. collagen, elastin. *See also* **allysine**.



11*β*-hydroxy-4-androstene-3,17-dione 4-androsten-11*β*-ol-3,17-dione; a 17-oxo steroid formed from androstenedione by steroid 11*β*-monooxygenase (EC 1.14.15.4).



hydroxyapatite *or* **hydroxylapatite** a crystallized form of calcium orthophosphate hydroxide, $Ca_{10}(PO_4)_6(OH)_2$, virtually insoluble in water and in many aqueous solvents; it occurs as a mineral in phosphate rock. The main mineral component of bone, cartilage, and tooth approximates in composition to hydroxyapatite, small proportions of Ca^{2+} and OH^- being replaced respectively by Mg^{2+} and F^-; trace amounts of other ions may be present as well. Hydroxyapatite may also occur in granules in mitochondria. Chemically prepared hydroxyapatite is useful in the separation of proteins or nucleic acids by **adsorption chromatography**. It is used in orthopedic and dental prostheses and in the prevention of osteoporosis.

N^{ω}-hydroxy-L-arginine *abbr.*: L-NHA; a derivative of L-arginine in which one of the guanidine nitrogens is oxidized to an *N*-hydroxy group. It is an intermediate in the formation of nitric oxide from L-arginine; it may function as an intercellular NO carrier, and as a vasodilator in its own right.



***p*-hydroxybenzoic acid** 4-hydroxybenzoic acid; an intermediate in the synthesis of **ubiquinone** from tyrosine in mammals.

***γ*-hydroxybutyrate** *or* **gamma-hydroxybutyrate** a rapid-acting central nervous depressant. It is abused because it produces euphoric and hallucinogenic states and is alleged to produce muscle growth. It is one of the 'date rape' drugs.

3-hydroxybutyrate cycle *or* **3-hydroxybutyrate shuttle** an intracellular metabolic cycle that can transfer reducing equivalents from the cytosol to the mitochondria in liver. Extramitochondrial NADH is oxidized to NAD$^+$ by acetoacetate, which is reduced to D(–)-3-hydroxybutyrate; the latter then passes into the mitochondria where it is reoxidized to acetoacetate by intramitochondrial NAD$^+$. The acetoacetate passes out into the cytosol thereby completing the cycle.

3-hydroxybutyrate dehydrogenase EC 1.1.1.30; *other name*: D-*β*-hydroxybutyrate dehydrogenase; an enzyme that catalyses the reaction:

(*R*)-3-hydroxybutanoate + NAD$^+$ = acetoacetate + NADH.

***α*-hydroxybutyrate (2-hydroxybutanoate) dehydrogenase** *an alternative name for* the LD$_1$ isoenzyme of **lactate dehydrogenase** (EC 1.1.1.27).

4-hydroxybutyric aciduria an autosomal recessive disorder caused by mutation in the gene for succinic-semialdehyde dehydrogenase. The excess succinic semialdehyde is reduced by 4-hydroxybutyrate dehydrogenase (EC 1.1.1.61) and the product is excreted in urine.

hydroxyeicosatetraenoate *abbr.*: HETE *or* mono-HETE; any of various related products arising, either spontaneously or by the action of glutathione peroxidases, from reduction of **hydroperoxyeicosatetraenoates**. The main forms are the 5-, 12-, and 15-HETEs, resulting from the action of 5-, 12-, and 15-**lipoxygenase** enzymes, but 8-, 9-, 11-, 16-, 17-, 18-, 19-, and 20-HETEs are known. The hydroxy group in most HETEs is of the *S* configuration, but those of *R* configuration are known, e.g. 12(*R*)-HETE from psoriatic lesions; 12(*R*)-HETE and 11(*R*)-HETE are found in sea-urchin eggs. The three main HETEs are: (6*E*,8*Z*,11*Z*,14*Z*)-(5*S*)-5-hydroxyeicosa-6,8,11,14-tetraen-1-oate, 5(*S*)-HETE; (5*Z*,8*Z*,10*E*,14*Z*)-(12*S*)-12-hydroxyeicosa-5,8,10,14-tetraen-1-oate, 12(*S*)-HETE; and (5*Z*,8*Z*,11*Z*,13*E*)-(15*S*)-15-hydroxyeicosa-5,8,11,13-tetraen-1-oate, 15(*S*)-HETE. Their tissue distribution follows that of **lipoxygenases**. 15(*S*)-HETE can act as a precursor for 5(*S*),15(*S*)-dihydroxyeicosatetraenoate and **lipoxins**. 5-HETE and 12-HETE are chemoattractants, 12(*R*) being more potent than 12(*S*), but 5(*S*) being more potent than 5(*R*); 8(*R*)-HETE, synthesized by starfish oocytes, is orders of magnitude more potent than 8(*S*)-HETE in inducing oocyte maturation.



5(*S*)-HETE



12(*S*)-HETE



15(*S*)-HETE

hydroxy fatty acid any member of a class of fatty acids having a hydroxyl group, usually at the 2- or 3-position. 2-D(–)-hydroxy fatty acids are widespread minor constituents of plant and some animal (wool, skin) lipids; 3-L(+)-hydroxy fatty acids are found in low amounts in plant and bacterial lipids (e.g. in **mycolic acids**). Mid-chain hydroxy acids and polyhydroxy acids also occur in plant lipids.

5-hydroxyindoleacetaldehyde *see* **5-hydroxyindole metabolism**.

5-hydroxyindoleacetic acid *abbr.*: 5-HIAA; a metabolite of **5-hydroxytryptamine**, produced by oxidative deamination catalysed by the enzyme **monoamine oxidase**, followed by oxidation to 5-HIAA. *See also* **5-hydroxyindole metabolism**.

5-hydroxyindole metabolism the metabolism of 5-hydroxytryptophan and its derivatives; it is of particular interest because it is concerned with the synthesis and degradation of the neurotransmitter 5-hydroxytryptamine (i.e. **serotonin**). Serotonin is converted to 5-hydroxy-3-indoleacetaldehyde by **monoamine oxidase**, and thence to either 5-hydroxytryptophol (3%) or 5-hydroxy-3-indoleacetic acid (5-HIAA) (97%), and these are excreted in the urine. Urinary 5-HIAA is measured as a diagnostic aid in cases of carcinoid syndrome, as the tumour converts large amounts of dietary tryptophan to serotonin.

hydroxyl **1** the (covalently linked) –OH group in any chemical compound. **2** *a former name for* the hydroxide ion; *see* **hydroxide** (def. 1).

hydroxylamine **1** NH_2–OH; a chemical mutagen that causes the deamination of cytosine residues in DNA so that, during subsequent replication of the DNA, the altered cytosine pairs with adenine rather than with guanine, causing G–C to A–T transitions. Hydroxylamine is an intermediate in the oxidation of ammonium in nitrifying bacteria, and in the reverse reaction in denitrifying bacteria. It may be used to cleave specifically Asp-|-Gly bonds in peptides. **2** any organic compound of the type RNH–OH.

hydroxylapatite *an alternative name for* **hydroxyapatite**.

hydroxylase *the common name for* many monooxygenase and a few **dioxygenase** enzymes that catalyse hydroxylation reactions.

hydroxylate to introduce one or more **hydroxyl** (def. 1) groups into a compound, often by the replacement of hydrogen atom(s). —**hydroxylation** *n.*

hydroxylation-induced migration *an alternative name for* **NIH shift**.

hydroxylysine *the trivial name for* δ-hydroxylysine; δ-hydroxy-α, ε-diaminocaproic acid; 5-hydroxy-2,6-diaminohexanoic acid; H_2N–CH_2–CHOH–$[CH_2]_2$–$CH(NH_2)$–COOH; a chiral α-amino acid. Because the molecule of hydroxylysine possesses two chiral centres, four isomeric forms are possible, comprising an enantiomeric (D_s and L_s) pair of each of two (*erythro* and *threo*) diastereoisomers (the pair of *threo* enantiomers are sometimes known as **allohydroxylysine**). L-Hydroxylysine (*symbol*: 5Hyl *or* Hyl *or* Lys(5-OH) *or (formerly)* Hylys), *erythro*-5-hydroxy-L_s-lysine, is a **noncoded amino acid** found in peptide linkage in proteins (mainly collagen). In collagen, 15–20% of the lysine residues are enzymically converted to hydroxylysine residues while the growing peptide chains are still attached to ribosomes; some of the hydroxyl groups of the hydroxylysine side chains are subsequently glycosylated.



L-hydroxylysine



L-allohydroxylysine

hydroxy-methoxymandelate *abbr.*: HMMA; 4-hydroxy-3-methoxymandelate; *often (incorrectly) known as* vanillylmandelate (*abbr.*: VMA); the L enantiomer is the end product of **catecholamine** catabolism, and is excreted in the urine. In clinical chemistry the measurement of HMMA in urine is used to detect excessive biosynthesis of catecholamines, as, e.g., in **pheochromocytoma**.



hydroxymethylbilane synthase EC 4.3.1.8; *systematic name*: porphobilinogen ammonia-lyase (polymerizing); *other names*: porphobilinogen deaminase; pre-uroporphyrinogen synthase. An enzyme that catalyses the conversion of four molecules of porphobilinogen to hydroxymethylbilane and four molecules of ammonia; dipyrromethane is a cofactor. Together with **uroporphyrinogen-III synthase** it is responsible for the step in heme biosynthesis in which four porphobilinogen molecules are condensed to form uroporphyrinogen III.

5-hydroxymethylcytosine *abbr.*: HMC; a minor base occurring in some types of DNA, e.g. in T4 bacteriophage.

hydroxymethylglutaric aciduria an autosomal recessive disease characterized by hypoglycemia, metabolic acidosis, hyperammonemia, and excessive urinary excretion of hydroxymethylglutarate. It can lead to coma and death in infancy. It is caused by inactivating mutations in the gene (at 1p35.1) for hydroxymethylglutaryl-CoA lyase.

hydroxymethylglutaryl-CoA *abbr.*: HMG-CoA; β-hydroxy-β-methylglutaryl-CoA; (*S*)-3-hydroxy-3-methylglutaryl-CoA; an important intermediate in the synthesis of cholesterol, farnesyl and geranyl derivatives, and ketone bodies, and in the catabolism of leucine. *See also* **hydroxymethylglutaryl-CoA reductase**, **hydroxymethylglutaryl-CoA lyase**.



hydroxymethylglutaryl-CoA lyase *abbr.*: HMG-CoA lyase; EC 4.1.3.4; *systematic name*: (*S*)-3-hydroxy-3-methylglutaryl-CoA acetoacetate lyase. An enzyme that catalyses the formation of acetyl-CoA and acetoacetate from (*S*)-3-hydroxy-3-methylglutaryl-CoA. It requires Mg^{2+} or Mn^{2+} for activity. In mammals it is a homodimer (each subunit in humans contains 298 amino acids) mostly of mitochondrial matrix but also present in peroxisomes that converts hydroxymethylglutaryl-CoA to acetoacetate in the synthesis of **ketone bodies**. Deficiency leads to hydroxymethylglutaric aciduria.

hydroxymethylglutaryl-CoA reductase (NADPH) *abbr.*: HMG-CoA reductase; EC 1.1.1.34; *systematic name*: (*R*)-mevalonate:NADP$^+$ oxidoreductase (CoA-acylating). An enzyme that catalyses a reaction between (*S*)-3-hydroxy-3-methylglutaryl-CoA and two molecules of NADPH to form (*R*)-mevalonate, CoA, and two molecules of NADP$^+$. Its function is to reduce HMG-CoA to (*R*)-mevalonate. In mammals it is an integral membrane glycoprotein of endoplasmic reticulum and peroxisomes. It catalyses a rate-limiting step and is an important regulatory enzyme in pathways for the synthesis of cholesterol and other sterols. It is the target for therapeutic strategies for reducing plasma cholesterol. *See also* **dephospho-[reductase kinase] kinase**.

[hydroxymethylglutaryl-CoA reductase (NADPH)] kinase EC 2.7.1.109; *other name*: reductase kinase; an enzyme that catalyses the phosphorylation by ATP of [3-hydroxy-3-methylglutaryl-CoA reductase (NADPH)] with release of ADP. It thereby inactivates the latter enzyme.

[hydroxymethylglutaryl-CoA reductase (NADPH)]-phos-

phatase EC 3.1.3.47; *other name*: reductase phosphatase; an enzyme that hydrolyses phosphate from [hydroxymethylglutaryl-CoA reductase (NADPH)] phosphate. It thereby activates the latter enzyme.

hydroxymethylglutaryl-CoA synthase *abbr.*: HMG-CoA synthase; EC 4.1.3.5; *systematic name*: (*S*)-3-hydroxy-3-methylglutaryl-CoA acetoacetyl-CoA-lyase (CoA-acetylating). A mostly hepatic enzyme that catalyses the reaction:

acetoacetyl-CoA + acetyl-CoA + H_2O → hydroxymethylglutaryl-CoA + CoA.

5-hydroxynorleucine *an older name (no longer recommended) for* 2-amino-5-hydroxyhexanoic acid; a non-protein (non-coded) amino acid found in plants, e.g. *Crotolaria juncea.*



(*R*)-4-hydroxyphenyllactate dehydrogenase EC 1.1.1.222; *other name*: (*R*)-aromatic lactate dehydrogenase; an enzyme that catalyses the reaction:

(*R*)-3-(4-hydroxyphenyl)lactate + NAD(P)$^+$ =
3-(4-hydroxyphenyl)pyruvate + NAD(P)H.

hydroxyphenylpyruvate reductase EC 1.1.1.237; an enzyme that catalyses the reaction:

3-(4-hydroxyphenyl)lactate + NAD$^+$ =
3-(4-hydroxyphenyl)pyruvate + NADH.

17*α*-hydroxypregnenolone 3*β*,17-dihydroxy-5-en-20-one; an intermediate in the synthesis of androgens, estrogens, and glucocorticoid hormones from cholesterol in the adrenal cortex. It is formed from **pregnenolone** by steroid 17*α*-monooxygenase (EC 1.14.99.9).



17*α*-hydroxyprogesterone 17-hydroxypregn-4-one; an intermediate in the synthesis of androgens, estrogens, and glucocorticoid hormones from cholesterol in the adrenal cortex. It is formed from **progesterone** by steroid 17*α*-monooxygenase (EC 1.14.99.9).



hydroxyproline *symbol*: Hyp *or (formerly)* Hypro; either of the two constitutional isomers 3-hydroxyproline and 4-hydroxyproline, HO–(C_4H_6NH)–COOH, both of which are chiral cyclic N-alkylated *α*-amino acids. Each constitutional isomer possesses two chiral centres; each can therefore exist as an enantiomeric (D and L) pair of each of two (*cis* and *trans*) diastereoisomers, making eight possible isomeric structures for hydroxyproline in all. Both *trans*-3-hydroxy-L-proline (*symbol*: 3Hyp *or* Pro(3-OH)), (2*S*,3*S*)-3-hydroxypyrrolidine-2-carboxylic acid, and *trans*-4-hydroxy-L-proline (*symbol*: 4Hyp *or* Pro(4-OH)), (2*S*,4*R*)-4-hydroxypyrrolidine-2-carboxylic acid, are **noncoded amino acids** found in peptide linkage in proteins. In collagen, nearly 50% of the proline residues are hydroxylated to 4Hyp, and a small proportion to 3Hyp; hydroxyproline residues are also found in elastin, enamel of the teeth, in the C1a moiety of the C1 component of **complement**, and in **extensin**. In collagen formation, enzymic hydroxylation of proline residues occurs while the growing peptide chains are still attached to ribosomes. Residues of both the *cis*-(2*S*,3*R*)- and the *trans*-(2*S*,3*S*)-isomers of 3-hydroxy-L-proline, one of each per molecule, occur in the peptide antibiotic telomycin. One residue per molecule of *cis*-4-hydroxy-L-proline, the (2*S*,4*S*)-isomer, occurs in every member of the **amatoxin** group of toxic fungal octapeptides. None of the D series of isomers is known to occur naturally.



trans-(2*S*,3*S*)-3-hydroxy-L-proline



trans-(2*S*,4*R*)-4-hydroxy-L-proline



cis-(2*S*,4*S*)-4-hydroxy-L-proline

hydroxyprolinemia *or* **hyperhydroxyprolinemia** a metabolic disorder of humans characterized by high levels of free 4-hydroxyproline in the blood plasma and urine. It is of no clinical consequence and is probably due to a deficiency in the activity of so-called hydroxyproline oxidase, i.e. the enzyme 4-oxoproline reductase (EC 1.1.1.104).

hydroxyproline-rich glycoproteins *abbr.*: HPRG; one of the four major types of **plant cell-wall proteins**. The best studied example is **extensin**, which is extensively glycosylated and forms a polyproline type of rodlike structure.

15-hydroxyprostaglandin dehydrogenase (NAD$^+$) EC 1.1.1.141; an enzyme involved in the inactivation of prostaglandins E_2, $F_{2\alpha}$, and B_1, by oxidizing the 15-hydroxyl group to a keto group. It catalyses a reaction between (5*Z*,13*E*)-(15*S*)-11*α*,15-dihydroxy-9-oxoprost-5,13-dienoate and NAD$^+$ to form (5*Z*,13*E*)-11*α*-hydroxy-9,15-dioxoprost-5,13-dienoate (15-keto PGE_2) and NADH.

3*β*-hydroxysteroid dehydrogenase an enzyme that converts the 3*β*-OH group of the substrate to a 3-keto group and isomerizes the C5,6 double bond to the C4,5 position in the following reactions on C_{21} and C_{19} steroids:

(1) pregnenolone + NAD$^+$ = progesterone + NADH;
(2) 17-hydroxypregnenolone + NAD$^+$ = 17-hydroxyprogesterone + NADH;
(3) dehydroepiandrosterone + NAD$^+$ = androstenedione + NADH.

It is the only steroidogenic enzyme of the endoplasmic reticulum that is not a cytochrome P450. In humans, two genes at 1p13 result in two isozymes: type 1 is expressed in nonsteroidogenic tissues, e.g. liver, breast, prostate, and skin; type 2 is expressed in steroidogenic tissues, i.e. adrenal cortex and gonads. Mutations in the gene for the type 2 isozyme are a rare cause of a salt-losing congenital adrenal hyperplasia in which there is deficiency of aldosterone, cortisol, and adrenal androgens (the three final products of the above reactions, respectively).

17β-hydroxysteroid oxidoreductase an enzyme of the endoplasmic reticulum that catalyses the reaction:

$$\text{androstenedione} + \text{NADP}^+ = \text{testosterone} + \text{NADPH}.$$

There are three homologous human isozymes of which type 3 (gene locus at 9q22) is expressed predominantly in the testes. Inactivating mutations in this gene result in enzyme deficiency, which leads to testosterone deficiency and male pseudohermaphroditism.

3β-hydroxysteroid-Δ^5-oxidoreductase/isomerase an enzyme of liver and fibroblasts that catalyses the reaction:

$$7\alpha\text{-hydroxycholesterol} + \text{NAD}^+ = \text{testosterone} + \text{NADH}.$$

It differs from the **3β-hydroxysteroid dehydrogenase**, for which the substrates are C_{21} and C_{19} steroids. A very rare deficiency produces a syndrome of jaundice, hepatosplenomegaly, pale stools, and dark urine (from abnormal bile acid excretion). If untreated the condition progresses to hepatic cirrhosis.

***N*-hydroxysuccinimide ester** *or* **NHS ester** any compound in which *N*-hydroxysuccinimide (NHS) has reacted with a carboxy group to form an ester. NHS esters react under mild conditions (>pH 7) with primary amino groups such as those at the N-terminus of proteins or ε-amino groups of lysine to form amide bonds with the release of NHS. NHS esters are used for labelling proteins with fluorescent tags or for crosslinking two molecules (often proteins) by covalent bonds.

5-hydroxytryptamine *abbr.*: 5-HT; *an alternative name for* **serotonin**.

5-hydroxytryptamine receptor any membrane protein that binds 5-hydroxytryptamine (i.e. **serotonin**) and mediates its intracellular effects. The receptors belong to seven families. Members of the 5-HT_1 family are G-protein-associated receptors and inhibit adenylate cyclase, but the 5-HT_{1A} receptor also increases K^+ conductance. Those of the 5-HT_2 family are G-protein-associated receptors and stimulate phospholipase C. 5-HT_3 opens a Cl^- channel; 5-HT_4 has four transmembrane segments and activates adenylate cyclase; 5-HT_5 is G-protein-associated but its effector is unknown. 5-HT_6 and 5-HT_7 are G-protein-associated receptors that activate adenylate cyclase.

5-hydroxytryptophan a non-protein amino acid found in plants; it is formed in legumes by hydroxylation of tryptophan. It is also formed in animals. *See also* **serotonin**.

hydroxyurea $NH_2CONHOH$; an analogue of **urea** with antineoplastic activity, possibly through inhibition of DNA synthesis.

hygro+ *comb. form* denoting moisture, especially that due to water.

hygrometer any instrument for measuring the relative humidity of a gas.

hygromycin B an aminoglycoside antibiotic from *Streptomyces hygroscopicus*. It kills bacterial, fungal, and higher eukaryotic cells by inhibiting protein synthesis. The inclusion of genes conferring resistance to hygromycin B in certain fungal recombinant DNA vectors allows selection of recombinants when these are plated out on medium containing this antibiotic.

hygromycin B phosphotransferase an enzyme from *Streptomyces hygroscopicus* that confers resistance to the toxic effects of hygromycin B. It is used as a dominant selectable marker in eukaryotic cells transfected with DNA constructs that incorporate the gene.

hygroscopic *(of a substance)* tending to absorb water from the surrounding atmosphere. *Compare* **deliquescent**.

Hyl *or (formerly)* **Hylys** *symbol for* a residue of any of the hydroxy derivatives of the α-amino acid L-lysine, especially 5-hydroxy-L-lysine. *See* **hydroxylysine**.

5Hyl *symbol for* a residue of the α-amino acid 5-hydroxy-L-lysine *(preferred alternative to* Lys(5-OH) or Hyl). *See* **hydroxylysine**.

Hylys *former symbol for* a residue of (5-)hydroxy-L-lysine (5Hyl or Hyl now recommended).

hyoscine *or* **scopolamine** an alkaloid found, e.g., in *Datura stramonium* (thorn apple) and related to **atropine** in its structure and effects; it is a tertiary ammonium compound noted for its actions as a **muscarinic receptor** antagonist. It has found use as a sedative and preanesthetic and for prevention of motion sickness.



hyoscyamine 3α-tropanyl S-(–)-tropate; an anticholinergic material obtained from *Atropa belladonna* and other plants. It undergoes partial racemization on isolation; this process is completed by alkali treatment, and the racemic mixture is known as atropine.



(–)-hyoscyamine

hyp+ *a variant form of* **hypo+** *(before a vowel)*.

Hyp **1** *or (formerly)* **Hypro** *symbol for* a residue of either the 3-hydroxy or the 4-hydroxy derivative of the α-amino (strictly, α-imino) acid L-proline, usually 4-hydroxy-L-proline. *See* **hydroxyproline**. *See also* **3Hyp**, **4Hyp**. **2** *symbol for* a residue of the purine base **hypoxanthine**.

3Hyp *symbol for* a residue of the α-amino acid 3-hydroxy-L-proline (*preferred alternative to* Pro(3-OH) or Hyp). *See* **hydroxyproline**.

4Hyp *symbol for* a residue of the α-amino acid 4-hydroxy-L-proline (*preferred alternative to* Pro(4-OH) or Hyp). *See* **hydroxyproline**.

hypelcin A a 20-residue peptide of microbial origin containing 10 α-aminoisobutyric acid residues. The N terminus is acylated and the C terminus amidated with **leucinol**. It modifies the permeability of phospholipid bilayers.

hyper+ *prefix* indicating over, beyond, excessive, or in excess; above the normal range. *Compare* **hypo+**, **normo+**.

hyperaldosteronism an elevated level of **aldosterone** in the blood. In primary aldosteronism, there is overproduction of aldosterone due to an adrenal tumour, as in Conn's syndrome or hyperplasia of the zona glomerulosa. In secondary aldosteronism the overproduction is caused by excessive levels of stimulatory hormones, especially increased renin secretion.

hyperammonemia *or (esp. Brit.)* **hyperammonaemia** the presence of excess ammonia in the blood (the normal range is 10–47 μmol L^{-1}). It occurs in inherited disorders of the urea cycle, organic acidemias, liver disease, and severe systemic illness. It is accompanied by cerebral edema with clouding of consciousness that may lead to coma and death. In these conditions it may be precipitated or aggravated by high protein intake. *See also* **ornithine–urea cycle**.

hyperbaric of, relating to, or operating at higher than normal pressures.

hyperbilirubinemia *or (esp. Brit.)* **hyperbilirubinaemia** the presence of higher than normal concentrations of **bilirubin** in the blood;

it may involve unconjugated or conjugated bilirubin. It occurs in liver disease or biliary obstruction, and is characteristic of neonatal hemolytic **jaundice**, where the bilirubin is mainly unconjugated. —**hyperbilirubinemic** *or* **hyperbilirubinaemic** *adj.*

hyperbola one of the conic sections; a plane curve in which the focal distance of any point bears to its distance from the directrix a constant ratio greater than unity. It has two foci and two asymptotes. *Compare* **rectangular hyperbola**. —**hyperbolic** *adj.*

hyperbolic function any one of a group of functions of an angle, analogous to the trigonometric functions, expressed as a relationship between the distances of a point on a hyperbola to the origin and to the coordinate axes. The group includes sinh (hyperbolic sine), defined as $\sinh x = (e^{x} - e^{-x})/2$; cosh (hyperbolic cosine), defined as $\cosh x = (e^{x} + e^{-x})/2$; and tanh (hyperbolic tangent), defined as $\tanh x = (\sinh x)/(\cosh x)$. The corresponding reciprocal functions are cosech (hyperbolic cosecant), sech (hyperbolic secant), and coth (hyperbolic cotangent), respectively.

hyperbolic kinetics curve *a description sometimes used of* the $v/[S]$ plot obtained for enzymes exhibiting **Michaelis–Menten kinetics**. The axes of the plot are not those of the rectangular hyperbola that results, but are rotated 45° (and displaced) from the true axes of the hyperbola.

hypercalcemia *or (esp. Brit.)* **hypercalcaemia** the presence of higher than normal concentrations of **calcium** in the blood. Clinical features include tiredness, muscle weakness, anorexia, weight loss, cardiac arrhythmia, and hypertension. It arises from a multiplicity of causes including malignancy, primary hyperparathyroidism, hyperthyroidism, acute adrenal insufficiency, familial hypocalciuric hypercalcemia, vitamin D or A overdose, or sarcoidosis. —**hypercalcemic** *or* **hypercalcaemic** *adj.*

hypercapnia *or* **hypercarbia** the presence of greater than normal amounts of carbon dioxide in a vertebrate or in its blood. *Compare* **hypocapnia**. —**hypercapnic** *or* **hypercarbic** *adj.*

hyperchlorhydria the presence of greater than normal amounts of hydrochloric acid in the gastric juice. —**hyperchlorhydric** *adj.*

hypercholesterolemia *or (esp. Brit.)* **hypercholesterolaemia** the presence of higher than normal concentrations of cholesterol in the blood. *See also* **hyperlipidemia.** —**hypercholesterolemic** *or* **hypercholesterolaemic** *adj.*

hyperchromatic **1** of, relating to, or exhibiting **hyperchromatism**. **2** *an alternative word for* **hyperchromic** (def. 1).

hyperchromatism the condition or property (of a cell or cell organelle) of staining more intensely than normal; the presence of a greater than normal amount of chromatin.

hyperchromic **1** *or* **hyperchromatic** more highly coloured than normal; intensely coloured. **2** of, pertaining to, exhibiting, or resulting from **hyperchromism**. **3** *(of a substance)* displaying a **hyperchromic effect**. **4** describing erythrocytes that contain, or appear to contain, more hemoglobin than normal.

hyperchromic effect the large increase in absorption of ultraviolet light, usually measured at 260 nm, shown by a solution of any natural or synthetic polynucleotide with a hydrogen-bonded structure when it is denatured or degraded. The effect is due to alterations in the electronic interactions between the initially stacked and hydrogen-bonded bases.

hyperchromicity a measure of the increase in absorption of electromagnetic radiation at a specific wavelength, usually that of the absorption maximum, due to **hyperchromism**, or to the **hyperchromic effect**. It is equal to the reciprocal of the **hypochromicity** minus unity.

hyperchromism the increased absorption of electromagnetic radiation exhibited by an ordered structure above that predicted on the basis of its constitution.

hyperfine splitting the splitting of a spectral line into multiplets of closely spaced lines. In electron spin resonance spectra hyperfine splitting is due to the interaction of unpaired electrons with neighbouring nuclei and can be used to determine the structure of a free radical or to identify the ligands of a paramagnetic ion and to measure the degree of covalent binding that exists between them. In nuclear magnetic resonance spectra, hyperfine splitting, sometimes called **spin–spin splitting**, is due to the interaction of the nuclear magnetic moment with those of neighbouring nuclei and can be used to assign particular nuclear resonances and to determine molecular conformations.

hyperfine structure the presence in a spectrum of multiplets of closely spaced lines resulting from **hyperfine splitting**.

hyperforin the major active ingredient of the herb St John's wort, which is used as a herbal in a variety of ailments. It binds to a transcription factor (pregnane X receptor) and enhances expression of cytochrome P4503A4, which degrades certain drugs (e.g. cyclosporin and the HIV protease inhibitor indinavir).

hyperglycemia *or (esp. Brit.)* **hyperglycaemia** an abnormally high blood glucose concentration, especially in relation to the fasting value. *See also* **glycemia**. —**hyperglycemic** *or* **hyperglycaemic** *adj.*

hyperglycemic factor *or* **hyperglycemic-glycogenolytic factor** *a former name for* **glucagon**.

hyperhydroxyprolinemia *see* **hydroxyprolinemia**.

hyper-IgD syndrome *abbr.*: HIDS; a rare autosomal recessive disease in which recurrent bouts of fever are associated with increased plasma levels of IgD and mevalonic aciduria. Activity of the enzyme mevalonate kinase is 5–15% of normal.

hyper-IgM syndrome a condition in which recurrent respiratory infections in early childhood are associated with very low concentrations of IgG, IgA, and IgE but normal or elevated concentrations of IgM in serum. It may be due to X-linked and autosomal recessive traits. *See* **activation-induced cytidine deaminase**.

hyperimmune describing the state of an animal in which very high concentrations of specific antibody are present in the serum, brought about by **hyperimmunization**.

hyperimmunization *or* **hyperimmunisation** any method of immunization designed to stimulate the production in the animal immunized of very large quantities of specific antibody. It typically involves the repeated administration of immunogen, often in increasing amounts.

hyperinsulinemia syndrome *or* **(metabolic) syndrome X** a syndrome of impaired glucose tolerance, fasting hyperinsulinemia, hypertriglyceridemia, hypertension, and increased predisposition to atherosclerosis. If untreated it often leads to diabetes mellitus type 2. *See* **insulin resistance**.

hyperkalemia *or (esp. Brit.)* **hyperkalaemia** the presence in the blood of an abnormally high concentration of **potassium**. There are many causes including excessive K^+ intake (infusion, transfusion), increased transcellular movement (tissue damage, systemic acidosis), and decreased K^+ loss (renal failure, mineralocorticoid deficiency). —**hyperkalemic** *or* **hyperkalaemic** *adj.*

hyperlactatemia *or (esp. Brit.)* **hyperlactataemia** a persistent raised blood lactate concentration, usually below 5 mmol L^{-1}, and not accompanied by a lowered blood pH. The normal range is between 0.5 and 2.2 mmol L^{-1}. *Compare* **lactic acidosis**. —**hyperlactatemic** *or* **hyperlactataemic** *adj.*

hyperlipidemia *or* **hyperlipemia** *or (esp. Brit.)* **hyperlipidaemia** *or* **hyperlipaemia** the presence in the blood of an abnormally high concentration of fats (or lipids). Hyperlipidemias have been classified into various types according to which lipoprotein class is found to be elevated in the blood. The Fredrickson classification scheme designates: type I, elevated chylomicrons; type II, elevated low-density lipoprotein; type III, elevated intermediate-density lipoprotein; type IV, elevated very-low-density lipoprotein; type V, elevated chylomicrons and very-low-density lipoprotein. A simpler distinction, of use in treatment, is between elevated cholesterol levels (type II, **hypercholesterolemia**) and elevated triacylglycerol levels (types I, III–V, **hypertriglyceridemia**, an older term still often used). Hyperlipidemia may be secondary to other conditions; several drugs cause or exacerbate hyperlipidemia, including thiazides, **beta blockers** lacking intrinsic sympathomimetic activity, and **corticosteroids**. Estrogens may lower hypercholesterolemia, but may cause or exacerbate hypertriglyceridemia; hypothyroidism is commonly associated with hypercholesterolemia; high alcohol intake causes hypertriglyceridemia, but modest alcohol intake may have a beneficial effect on cholesterol status, as it tends to increase **high-density lipoprotein** concentration. —**hyperlipidemic**, **hyperlipemic** *or* **hyperlipidaemic**, **hyperlipaemic** *adj.*

hypermodified base any extensively modified nucleic-acid base occurring adjacent to the 3′ end of the anticodon in many tRNA molecules. Examples are N^6-(δ_2-isopentenyl)adenosine (*symbol*: iA) and N^6-(threonylcarbamoyl)adenosine (*symbol*: tA). Hypermodified bases are thought to be important for proper binding of tRNA molecules to ribosomes.

hypernatremia *or (esp. Brit.)* **hypernatraemia** the presence in the blood of an abnormally high concentration of sodium. It may be associated with conditions in which body water is depleted. **—hypernatremic** *or* **hypernatraemic** *adj.*

hyperornithinemia *see* **OAT**.

hyperoxaluria the presence of oxalate in the urine in abnormally high amounts. It is associated with the formation of renal calculi. Type 1, the commonest, results from overproduction of oxalate from glyoxylate because of deficiency of alanine–glyoxylate aminotransferase (EC 2.4.1.44) activity. Type 2 results from deficiency of D-glycerate dehydrogenase/glyoxylate reductase (EC 1.1.1.29). Type 3 results from a poorly characterized increased absorption of oxalate from the intestine.

hyperoxia the presence of greater than normal amounts of dioxygen in a vertebrate or in its blood. *Compare* **hypoxia**. **—hyperoxic** *adj.*

hyperparathyroidism the increased production of **parathyroid hormone**. It may be primary, as a result of a tumour of the parathyroid gland, or secondary, as a result of a disturbance in calcium metabolism.

hyperphosphatemia *or (esp. Brit.)* **hyperphosphataemia** an excessive level of phosphate in the blood. It occurs most commonly in renal insufficiency, but may also accompany hypoparathyroidism, vitamin D intoxication, or excessive administration of phosphate. **—hyperphosphatemic** *or* **hyperphosphataemic** *adj.*

hyperplasia the increase in size of a tissue or organ resulting from an increase in the total number of cells present. The part thus affected retains its normal form. *Compare* **hypertrophy**. **—hyperplastic** *adj.*

hyperprolactinemia *or (esp. Brit.)* **hyperprolactinaemia** the presence in the blood of abnormally high levels of **prolactin**, due to excessive secretion of the hormone. The most common example of pituitary hyperfunction, it results from pituitary adenoma, and also from treatment with dopamine receptor blockers. It can be treated with dopamine agonists, e.g. **bromocriptine**. **—hyperprolactinemic** *or* **hyperprolactinaemic** *adj.*

hypersecretion excessive secretion by any endocrine or exocrine gland.

hypersensitive having an abnormally great sensitivity, especially to an allergen, drug, or other agonist.

hypersensitive sites regions of chromatin that are unprotected by histones and other DNA-binding proteins and are sites of active transcription in the genome. The presence of such sites is revealed by treating intact nuclei with DNase I and analysing the resulting fragments of DNA.

hypersensitivity **1** the state or condition of being **hypersensitive**. **2** *(in immunology)* an immune response that occurs in an exaggerated or inappropriate form. Such responses may result from agents including pollen or drugs, or from genuine pathogens. Also of importance are the different kinds of tissue damage seen in autoimmune diseases. In general terms the reactions may be classified into four types, although they do not occur in isolation from each other: type I, **immediate hypersensitivity**; type II, **antibody-mediated hypersensitivity**; type III, **immune complex-mediated hypersensitivity**; and type IV, **delayed hypersensitivity**.

hypersensitivity mapping a method for identifying sites in chromatin at which active transcription is taking place. Cloning and sequencing of DNA flanking DNase I **hypersensitive sites** permits the identification of genes being transcribed.

hypersharpening the formation of a 'sharper' boundary in sedimentation and moving boundary electrophoresis experiments than would be expected as a result of diffusion-broadening, because molecules in the trailing portion of the boundary tend to move at a greater velocity per unit field than molecules on the leading edge or in the plateau region.

hypertension the state or condition of having a higher than normal arterial blood pressure. **—hypertensive** *adj.*

hyperthermophile an organism growing at a temperature above 80°C. Almost all thermophiles belong to the kingdom **Archaea**. *Compare* **thermophile**.

hyperthyroidism *or* **thyrotoxicosis** a clinical state resulting from excessive secretion of thyroid hormones. The most common cause is Graves' disease; other causes include goitre and solitary toxic adenoma. The associated nervousness, irritability, fatigue, heat intolerance, and (not in all) exophthalmia derive from exaggeration of normal responses to thyroid hormones. *See also* **thyroxine**. **—hyperthyroid** *adj.*

hypertonic **1** *(of a solution)* having a higher osmotic pressure than that of some given solution, especially that of the fluid in or surrounding a given type of cell or a body fluid. **2** *(of a muscle)* showing or characterized by excessive tone or tension. *Compare* **hypotonic**. **—hypertonicity** *n.*

hypertriglyceridemia *or (esp. Brit.)* **hypertriglyceridaemia** *see* **hyperlipidaemia**.

hypertrophy the increase in the size of a tissue or organ resulting from an increase in the size of the cells present. *Compare* **hyperplasia**. **—hypertrophic** *adj.*

hyperuricemia *or (esp. Brit.)* **hyperuricaemia** the presence of elevated amounts of uric acid in the blood. This may be due to increased purine synthesis arising from a metabolic disorder, inherited or otherwise, or to reduced excretion – e.g. renal disease, the effect of drugs (e.g. salicylates), or the presence of organic acids (e.g. lactate) that competitively inhibit urate excretion. Hyperuricemia is associated with **gout**.

hypervariable region *an alternative name for* complementarity-determining region.

hypo *a common name for* sodium thiosulfate, especially when used in photographic processing.

hypo+ *or (before a vowel)* **hyp+** *prefix* denoting under, beneath, below, less than, or in deficit; below the normal range. *Compare* **hyper+**, **normo+**.

hypoalphalipoproteinemia *see* **hypolipoproteinemia**.

hypobaric of, relating to, or operating at pressures lower than normal.

hypobetalipoproteinemia *see* **hypolipoproteinemia**.

hypocalcemia *or (esp. Brit.)* **hypocalcaemia** the presence of a lower than normal concentration of **calcium** in the blood. It may be associated with disorders of vitamin D metabolism, **hypoparathyroidism**, magnesium deficiency, or pancreatitis. Clinical features include behavioural disturbances, stupor, numbness, paresthesia, muscle cramps or spasms, and convulsions. **—hypocalcemic** *or* **hypocalcaemic** *adj.*

hypocapnia *or* **hypocarbia** the presence of less than the normal amount of carbon dioxide in a vertebrate or in its blood. *Compare* **hypercapnia**. **—hypocapnic** *or* **hypocarbic** *adj.*

hypochlorhydria the presence of less than the normal amount of hydrochloric acid in the gastric juice. **—hypochlorhydric** *adj.*

hypochlorous acid HOCl; a strong oxidizing and halogenating agent and bactericide, used as the active ingredient of bleach. It is generated by the enzyme **myeloperoxidase** in azurophilic granules of neutrophils and lysosomes of monocytes, in response to the entry of bacteria.

hypocholesterolemia *or (esp. Brit.)* **hypocholesterolaemia** the presence of a lower than normal concentration of cholesterol in the blood. **—hypocholesterolemic** *or* **hypocholesterolaemic** *adj.*

hypochondroplasia *see* **achondroplasia**.

hypochromatic **1** of, relating to, or exhibiting **hypochromatism**. **2** *an alternative word for* **hypochromic** (def. 1).

hypochromatism the condition or property (of a cell or cell organelle) of staining less intensely than normal; the presence of an abnormally low amount of chromatin.

hypochromic **1** *or* **hypochromatic** less highly coloured than normal; weakly coloured. **2** of, pertaining to, exhibiting, or resulting from **hypochromism**. **3** *(of a substance)* displaying a **hypochromic effect**. **4** describing erythrocytes that contain, or appear to contain, less hemoglobin than normal.

hypochromic effect the observed decrease in absorption of certain frequencies of electromagnetic radiation by solutions of some macromolecules when the structure of the molecules becomes more ordered.

hypochromicity a measure of the decrease in absorption of electromagnetic radiation at a specific wavelength, usually that of the absorption maximum, due to **hypochromism**.

hypochromism the decreased absorption of electromagnetic radiation exhibited by an ordered structure below that predicted on the basis of its constitution.

hypocretin *or* **orexin** either of two polypeptides (of 39 and 29 amino acids) that occur in the lateral hypothalamus and increase food intake. They arise from the same precursor by differential cleavage and act on G-protein-coupled membrane receptors that regulate feeding behaviour.

hypoglycemia *or (esp. Brit.)* **hypoglycaemia** the presence of an abnormally low blood glucose concentration, especially in relation to the fasting value. *See also* **glycemia**. —**hypoglycemic** *or* **hypoglycaemic** *adj.*

hypoglycin *or* **hypoglycine A** β-(methylenecyclopropyl)alanine; 2-amino-3-(methylenecyclopropane)propanoic acid. A nonprotein α-amino acid identified as the hypoglycemic and toxic principle of the unripe fruit of the **ackee** (*Blighia sapida*), where it is present both in the fleshy aril and in the seeds. In the latter it occurs also as the *N*-L-glutamyl derivative, **hypoglycin B**. Certain other fruits also contain hypoglycin. It is degraded in animals to methylenecyclopropylacetate, either free or conjugated to glycine or coenzyme A. Methylenecyclopropylacetyl-CoA is a potent and specific inhibitor of the oxidation of short-chain acyl-CoAs, particularly of butyryl-CoA and glutaryl-CoA. In hypoglycin poisoning butyrate and glutarate accumulate in the blood and lead to metabolic acidosis and excessive urinary excretion of these compounds. *See also* **Jamaican vomiting sickness**.

Hyp(3-OH) *symbol for* a residue of the α-amino acid 3-hydroxy-L-proline (alternative to 3Hyp or Hyp). *See* **hydroxyproline**.

Hyp(4-OH) *symbol for* a residue of the α-amino acid 4-hydroxy-L-proline (alternative to 4Hyp or Hyp). *See* **hydroxyproline**.

hypokalemia *or (esp. Brit.)* **hypokalaemia** the presence in the blood of an abnormally low concentration of potassium. It may result from alkalosis, insulin administration, primary or secondary aldosteronism, or administration of drugs that are aldosterone antagonists. —**hypokalemic** *or* **hypokalaemic** *adj.*

hypolipoproteinemia the partial or total absence of any lipoprotein, or the presence of a defective lipoprotein, in the plasma. Several types of this condition are recognized. **Hypobetalipoproteinemia** is arbitrarily defined as a low-density lipoprotein (LDL) cholesterol level below the fifth percentile for a given sex- and age-matched population. Such patients also have low triacylglycerol levels. In this condition, LDL cholesterol is always detectable, in contrast to homozygous **abetalipoproteinemia**, in which it is entirely absent. Hypobetalipoproteinemia appears to be due to a low rate of synthesis of LDL from very-low-density lipoprotein. Abetalipoproteinemia is a rare autosomal recessive disorder. It probably results from an abnormality in the synthesis or secretion of apo B, and it is accompanied by fat malabsorption, as chylomicron formation requires apo B. In the homozygote, levels of triacylglycerols, cholesterol, and phospholipids are extremely low. Heterozygotes may present with hypobetalipoproteinemia. **Hypoalphalipoproteinemia** is in some cases familial, and may result from defective apo A-I. In another disorder, known as fish-eye disease (due to severe corneal opacity), the structure of apo A-I is normal, but high-density lipoprotein (HDL) levels are only 10% of normal. In analphalipoproteinemia, or **Tangier disease**, HDL is virtually absent.

hyponatremia *or (esp. Brit.)* **hyponatraemia** the presence in the blood of an abnormally low concentration of sodium. It can occur as a result of incorrect administration of fluid intravenously or in parenteral feeding, after administration of diuretics, in congestive heart failure, or in protein imbalance. —**hyponatremic** *or* **hyponatraemic** *adj.*

hypoparathyroidism underactivity of the **parathyroid glands**.

hypophase the lower layer of a two-phase system. *Compare* **epiphase**. —**hypophasic** *adj.*

hypophosphatasia *see* **alkaline phosphatase**.

hypophosphatemia *or (esp. Brit.)* **hypophosphataemia** the presence of an abnormally low level of phosphate in the blood. It occurs in vitamin D deficiency, primary **hyperparathyroidism**, incorrect parenteral nutrition, during recovery from diabetic ketoacidosis, and in hereditary defects of uptake of renal phosphate. *See* **fibroblast growth factor-23**, **PHEX**.

hypophysectomy surgical removal of the pituitary gland (i.e. hypophysis). —**hypophysectomize** *or* **hypophysectomise** *vb.*

hypophysiotropic factor *or* **hypophysiotropic hormone** *an alternative name for* **hypothalamic (regulatory) factor**.

hypophysis *or* **hypophysis cerebri** *an alternative name for* **pituitary gland**. *See also* **adenohypophysis**, **neurohypophysis**. —**hypophyseal** *or* **hypophysial** *adj.*

hypopituitarism total or (more often) partial loss of pituitary function, usually due to destructive lesions of the pituitary.

hypoplasia underdevelopment or defective formation of an organ or tissue. —**hypoplastic** *adj.*

hypoprothrombinemia *or (esp. Brit.)* **hypoprothrombinaemia** an abnormally low (inadequate) level of plasma prothrombin (factor II), commonly caused by vitamin K deficiency.

hyposecretion lesser than normal secretion by any endocrine or exocrine gland.

hypotension the state or condition of having a lower than normal arterial blood pressure. —**hypotensive** *adj.*

hypothalamic (regulatory) factor *or* **hypothalamic hormone** *or* **hypophysiotropic factor** *or* **hypophysiotropic hormone** any peptidic substance that is synthesized in the mammalian hypothalamus and released into the hypophyseal–portal circulation in response to neural and/or chemical stimuli, and that regulates the secretion (and perhaps also the synthesis) of a specific polypeptide hormone by the anterior lobe of the pituitary gland (i.e. adenohypophysis). These specific factors may be either releasing or release-inhibiting factors (or hormones); their recommended names are now formed by replacing the word-ending 'tropin' (or '-in' in prolactin) in the name of the corresponding pituitary hormone by the word-ending '-liberin' (for a releasing factor) or '-statin' (for a release-inhibiting factor).

hypothalamus (*pl.* **hypothalami**) the region of the vertebrate brain lying below the thalamus and around the floor of the third ventricle, just posterior to the attachment of the cerebral hemispheres. It lies just above the **pituitary gland**, to which it supplies various **hypothalamic (regulatory) factors**. —**hypothalamic** *adj.*

hypothetical protein a translation product that cannot be related (e.g. by means of database similarity searches) to any previously characterized protein.

hypothyroidism deficient secretion by the thyroid gland. In infants it leads to cretinism; in adults the consequences include low metabolic rate, lethargy, menstrual disorders, and in extreme cases **myxedema**. —**hypothyroid** *adj.*

hypotonic 1 (of a solution) having a lower osmotic pressure than that of some given solution, particularly the fluid in or surrounding a given type of cell or a body fluid. **2** (of a muscle) showing or characterized by diminished tone or tension. *Compare* **hypertonic**. —**hypotonicity** *n.*

hypovolemia *or (esp. Brit.)* **hypovolaemia** a reduction in the volume of circulating blood. It may be due to hemorrhage or to redistribution of fluid from the plasma to the extravascular tissues and spaces.

hypox *abbr. for* hypophysectomized. *See* **hypophysectomy**.

hypoxanthine *symbol*: Hyp; purin-6(1*H*)-one; 6-hydroxy purine; an intermediate in the degradation of adenylate. Its ribonucleoside is known as **inosine** and its ribonucleotide as **inosinate**. *Compare* **xanthine**. *See also* **hypoxanthine phosphoribosyltransferase**.

hypoxanthine/guanine phosphoribosyltransferase *abbr.*: HGPRT; *see* **hypoxanthine phosphoribosyltransferase** .

hypoxanthine phosphoribosyltransferase EC 2.4.2.8; *systematic name*: IMP:pyrophosphate phospho-D-ribosyltransferase; *other names*: hypoxanthine/guanine phosphoribosyltransferase (*abbr.*: HGPRT); IMP pyrophosphorylase. An enzyme that catalyses a reaction between 5-phospho-α-D-ribose 1-diphosphate and either hypoxanthine or guanine to form IMP or GMP respectively, with release of pyrophosphate. It is important for the metabolic activation of purines, e.g. 6-mercaptopurine, and forms part of the purine salvage pathway. Partial deficiency is associated with **Lesch–Nyhan syndrome** and **gout**.

hypoxia the presence of less than normal amounts of dioxygen in a vertebrate or in its blood. *See* **ARNT**, **HIF**. *Compare* **hyperoxia**. —**hypoxic** *adj.*

hypoxia-inducible factor *See* **HIF**.

Hypro *(formerly) symbol for* a residue of (4-)hydroxy-L-proline (4Hyp or Hyp now recommended).

hypsochromic describing the shift of an absorption band in the direction of shorter wavelengths. *Compare* **bathochromic**.

hypusine N^{ε}-[4-amino-2-hydroxybutyl]lysine; an amino acid uniquely formed by post-translational modification of one of the lysyl residues of eukaryotic translation initiation factor 5A (eIF-5A). It is formed by deoxyhypusine synthase, an enzyme that transfers the butylamine portion of spermidine to the ε-NH_2 group of a specific lysine of the eIF-5A precursor, followed by addition of the hydroxyl group by deoxyhypusine hydroxylase.



hysteresis the delay between the effect on a system and the cause producing the effect. —**hysteretic** *adj.*

hysteretic enzyme any enzyme that responds slowly (in terms of some kinetic characteristic) to a rapid change in ligand (either substrate or modifier) concentration. Such slow changes, defined in terms of their rates relative to the overall catalytic reaction, result in a lag in the response of the enzyme to changes in the ligand level.

Hz *symbol for* hertz.

H zone *see* **sarcomere**.

Ii

i *symbol for* **1** iso (def. 3); (as a prefix or superscript in symbols and abbreviations for iso compounds or groups; e.g. isopropyl can be symbolized as iPr or Pr^i). **2** the chemical group 2-isopentenyl; 3,3-dimethylallyl (as a prefix to a single-letter symbol for a nucleoside residue to designate substitution of the base, as in **iA**). **3** the square root of –1.

i *symbol for* **1** electric current (alternative to *I*). **2** van't Hoff factor.

I *symbol for* **1** iodine. **2** an iodo group in an organic compound. **3** a residue of the *α*-amino acid L-isoleucine (alternative to Ile). **4** a residue of the ribonucleoside inosine (alternative to Ino).

I *symbol for* **1** electric current (preferred alternative to *i*). **2** intensity; the subscripts e (for energetic), p (for photon), or v (for visible) may be added to distinguish between radiant intensity, photon intensity, and luminous intensity, respectively. **3** ionic strength; the subscripts c or m may be added to indicate whether it is expressed based on concentration or molality respectively. **4** the inductive effect of a particular chemical group in an organic compound.

iA *symbol for* N^6-(2-isopentenyl)adenosine, a **hypermodified base**.

IAA *abbr. for* indole-3-acetic acid *or* **indoleacetate**.

IAN *abbr. for* indoleacetonitrile.

IAP *abbr. for* **1** islet-activating protein; *see* **pertussis toxin**. **2** inhibitor of apoptosis protein; *other name*: apoptosis inhibitory protein (*abbr*.: AIP); any of a group of proteins that inhibit apoptosis. They bind tumour necrosis factor (TNF) receptor-associated proteins 1 and 2. Mutations in a neuronal IAP (*abbr*.: NIAP), a 294-residue protein encoded at 5q12.2-q13.3, cause various forms of spinal muscular atrophy. *See* **TNF receptor-associated protein 2**.

iatrogenic describing a condition or disease induced unintentionally by a physician through his or her diagnosis, manner, or therapy. —**iatrogenicity** *n.*

IκB *abbr. for* inhibitor of NF-κB; a cytosolic protein that binds and inhibits **NF-κB** in most cell types. It is released from binding following phosphorylation by the **IκB kinase** complex in response to binding of tumour necrosis factor α and interleukin-1 to their receptors. The phosphorylation targets IκB for ubiquitination and degradation by proteasomes.

I-band *abbr. for* isotropic band. The I-bands of striated muscle contain the **thin filaments** and correspond to the light bands. The name derives from the fact that they are isotropic in polarized light. *See also* **sarcomere**.

IκB kinase a heterotrimeric complex (≈700 kDa) that acts on **IκB** to release NF-κB and target IκB for ubiquitination and degradation by proteasomes. It consists of two catalytic subunits (α and β), which share ≈50% sequence identity, and a regulatory subunit (γ). It is activated by phosphorylation via multiple signalling pathways, including tumour necrosis factor α and interleukin-1.

IBMX *abbr. for* isobutylmethylxanthine.

ibuprofen 2-(4-isobutylphenyl)propionic acid; a nonsteroidal anti-inflammatory agent of the substituted propionic acid type; others of this type are flurbiprofen, **ketoprofen**, and naproxen. They inhibit the cyclooxygenase activity of **prostaglandin-endoperoxide synthase**, reversibly over short time intervals, followed by time-dependent irreversible inactivation, due probably to conformational rather than covalent changes. The racemic mixture is present in many over-the-counter drugs, but the (*S*)-enantiomer is the active form. *Proprietary names include*: Advil; Brufen; Motrin.



(*S*)-ibuprofen

ic *or* **i.c.** *abbr. for* intracutaneous or intracutaneously.

IC *abbr. for* internal conversion.

$\mathbf{IC_{50}}$ **1** the median inhibitory concentration (in mol L^{-1}) of an antagonist, i.e. the concentration that reduces a specified response to 50% of its former value; *compare* $\mathbf{EC_{50}}$. **2** the median inhibitory concentration (in mol L^{-1}) of an agent (agonist or antagonist), i.e. the concentration that causes a 50% reduction in the specific binding of a radioligand.

ICAM *abbr. for* intercellular adhesion molecule; any of several type I membrane glycoproteins of the immunoglobulin superfamily. They are ligands for leukocyte adhesion to target cells, in conjunction with **LFA-1**; in fact LFA-1–ICAM links mediate adhesion between many cell types. **ICAM-1** (*or* CD54), of 90–115 kDa, are expressed on B and T lymphocytes, endothelial, epithelial, and dendritic cells, fibroblasts, keratinocytes, and chondrocytes. They are inducible in 12–24 hours by cytokines such as gamma interferon, interleukin-1β, and tumour necrosis factor-α. **ICAM-2** (*or* CD102), of 55–65 kDa, are constitutively expressed on endothelial cells, some lymphocytes, monocytes, and dendritic cells. **ICAM-3** (*or* CD50), of 116–140 kDa, are constitutively expressed on monocytes, granulocytes, and lymphocytes; and on stimulation are rapidly and transiently phosphorylated on serine residues.

ICAT *abbr. for* **isotopically coded affinity tag**.

ICD *(in clinical chemistry) abbr. for* isocitrate dehydrogenase (EC 1.1.1.41).

ice the solid form of water that can exist at temperatures below the triple point of water (273.16 K at 101 325 Pa).

ICE *abbr. for* **1** imprint control element; a CpG rich region of genomic DNA that attracts *de novo* methylation in one parental gamete and avoids methylation in the other parental gamete. It is necessary for imprinted expression: when unmethylated it silences mRNA and activates non-coding RNA (ncRNA); it is inactive when methylated. An example is the 3.7 kb element within the *Igf2r* gene responsible for paternal-specific gene silencing of *Igf2r, Slc22a2*, and *Slc22a3* genes on mouse chromosome 17. **2** interleukin 1β convertase.

iceberg a metaphor used to describe an interpretation of the anomalous entropies of solution of noble gases and other nonpolar substances in water, suggesting that water tends to organize itself into quasi-solid supramolecular structures around the molecules of such substances. In the case of alkyl compounds, this tendency increases markedly with the length of the alkyl chain.

Iceberg a human protein of the CARD family that binds caspase-1 tightly. It inhibits the generation of interleukin 1β.

ICE-like protease any of a family of endopeptidases that structurally resemble **interleukin-1 β convertase** (ICE). They are involved in **apoptosis**, being implicated in the proteolysis that causes cell death.

I cell 1 *or* **CCK cell** any of a group of cells, widely distributed in the duodenal and jejunal mucosa, that produce **cholecystokinin**. So named because their histological features are intermediate between those of **S cells** and **L cells**. **2** *abbr. for* inclusion cell. *See also* **I-cell disease**.

I-cell disease *or* **inclusion-cell disease** *or* **mucolipidosis II** an autosomal recessive disease in which most of the lysosomes in the connective tissue (fibroblasts) contain large inclusions of glycoaminoglycans and glycolipids as a result of the absence of several lysosomal hydrolases. These enzymes, which are synthesized in the endoplasmic reticulum, are secreted into the extracellular medium rather than being directed to the lysosomes. This is due to the absence of a mannose 6-phosphate marker on the carbohydrate moieties of these hydrolases because of a deficiency in an enzyme required for mannose phosphorylation. The failure of the phosphorylation in the *cis* Golgi network means that the enzymes are not segregated by the **mannose 6-phosphate receptors** into the appropriate transport vesicles in the *trans* Golgi network. The patients have an abnormally high level of lysosomal enzymes in their sera and body fluids. A milder form of I-cell disease is pseudo-Hurler polydystrophy.

ice point the temperature at which ice melts. It is taken as the temperature (273.15 K) at which ice and water are in equilibrium at standard pressure (101 325 Pa). It was used as a reference temperature on the Celsius scale, but the kelvin is based instead on the temperature at the **triple point** of water (273.16 K).

ICF *abbr. for* intracellular fluid.

ichthyosis a human condition in which the skin is thickened and scaly, as a result of a disorder of keratinization in the outer layers of the epidermis. An X chromosome-linked form is caused by mutations that produce deficiency of **steryl-sulfatase**. An autosomal dominant form results from mutations in the genes for keratin 1 or keratin 10. An autosomal recessive form is caused by deficiency of transglutaminase K. –**ichthyotic** *adj.*

ichthyotocin *an alternative name for* **isotocin**.

I-clip any intramembrane-cleaving protease, which may be a metalloprotease, serine protease, or aspartate protease.

icosa+ *or (before a vowel)* **icos+** *comb. form* recommended for denoting twenty or twenty times. *Also (formerly)*: **eicosa+**, **eicos+**. (*Note*: the eicos(a)+ variant is still always used for the C_{20} fatty acids and skeletally related compounds, e.g. the eicosanoids.)

icosadeltahedron (*pl.* **icosadeltahedra**) any solid geometrical figure obtained by dividing the triangular faces of an **icosahedron** into smaller triangles. If divided into more than four smaller triangles, the original faces will not be flat, in which case the 12 pentameric vertices will be supplemented by hexameric vertices. —**icosadeltahedral** *adj.*

icosahedral symmetry a form of **cubic symmetry**, being the crystallographic symmetry displayed by an **icosahedron** and by the capsid of some types of virus.

icosahedron (*pl.* **icosahedra**) any solid geometrical figure having 20 triangular faces, 30 edges, and 12 pentameric vertices. A regular icosahedron has faces that are congruent plane equilateral triangles; there is twofold rotational symmetry about an axis through the midpoint of each edge, threefold rotational symmetry about an axis through the centre of each face, and fivefold rotational symmetry about an axis through each vertex. —**icosahedral** *adj.*

icosanoate *or (formerly)* **eicosanoate** *the systematic name for* **arachidate**.

icosanoid *the recommended name for* **eicosanoid**, but not generally used.

ICRO *abbr. for* International Cell Research Organization.

ICSH *abbr. for* interstitial cell-stimulating hormone (i.e. **luteinizing hormone**).

ICSU *abbr. for* International Council of Scientific Unions.

icterus *(in pathology) an alternative name for* **jaundice**.

icterogenic causing **jaundice**.

id *or* **i.d.** *abbr. for* **1** intradermal, or intradermally (alternative to ID). **2** inside diameter.

Id *abbr. for* inhibitor of differentiation; any of four mammalian helix-loop-helix (HLH) proteins (ID1 to ID4) that are negative regulators of cell differentiation. They form heterodimers, which do not bind to DNA, with certain ubiquitously expressed basic HLH proteins, and regulate tissue-specific gene expression.

ID *abbr. for* **1** *(in clinical chemistry)* iditol dehydrogenase (EC 1.1.1.14). **2** intradermal, or intradermally (alternative to id).

ID_{50} *or* **ID50** *abbr. for* median infectious dose.

idaric acid the **aldaric acid** derived from idose.

IDDM *abbr. for* insulin-dependent diabetes mellitus (*see* **diabetes mellitus**).

+ide *suffix (in chemical nomenclature)* denoting a **lactide**. It replaces the terminal '+ic acid' of the trivial name of the parent hydroxy acid, and a multiplying prefix indicates the number of molecules of hydroxy acid involved; e.g. dilactide (formed from two molecules of lactic acid).

ideal describing any object, process, or system that is perfect, or that behaves exactly in accordance with some simple law or theory. *See also* **ideal gas**, **ideal solution**. —**ideality** *n.*

ideal gas any gas whose behaviour is accurately described by the **gas laws**.

ideal solution any solution in which, for each component,

$$d\mu_i = RT\,d\ln x_i,$$

where μ_i is the chemical potential of the *i*th component and x_i is its mole fraction, R is the universal gas constant, and T is the thermodynamic temperature. Integration of the above equation gives:

$$\mu_i = \mu_i^{o} + RT\ln x_i,$$

where μ_i^{o} is the standard chemical potential of the *i*th component.

identity *(in sequence analysis)* the extent to which compared sequences have identical bases or residues at equivalent positions, usually expressed as a percentage.

identity matrix *or* **unitary matrix** *see* **scoring matrix**.

idio+ *comb. form* denoting **1** peculiar, distinct, one's own, separate. **2** self-produced, arising within.

idiogram *or* **karyogram** a diagrammatic representation of the **karyotype** of a cell, based on measurement of the chromosomes in several or in many cells.

idiom *(in immunology)* the group of **idiotypes** to which the **epitopes** carried by components of one individual animal belong.

idiopathic **1** *(in pathology)* describing a disease arising by itself, not consequent upon, or symptomatic of, another disease; of the nature of a primary morbid state; essential. **2** of the nature of a particular affection or susceptibility. —**idiopathy** *n.*

idiopathic autonomic neuropathy a severe subacute disorder caused by autoantibodies to ganglionic acetylcholine receptors (i.e. not those of neuromuscular junctions as in **myasthenia gravis**).

idiopathic pentosuria *see* **pentosuria** (def. 1).

idiotope **1** the group of **epitopes** carried by components of one individual animal. **2** as originally defined by Danish immunologist Niels Jerne (1911–94), an individual determinant (i.e. site) on an antibody molecule; together, the idiotopes constitute the idiotype.

idiotype **1** an antigenic specificity, particularly of antibodies directed against a single antigen. **2** any class or group of related antigenic characteristics or **idiotopes**; an **epitype** that is characteristic of a particular animal. —**idiotypic** *adj.*

iditol the hexitol derived formally by reduction of the aldehyde group of idose. L-Iditol is a rare natural product accompanying sorbitol in the fermented juice of berries of mountain ash (*Sorbus aucuparia*).

IDL *abbr. for* intermediate-density lipoprotein.

iDNA *abbr. for* intercalary DNA.

IDNPAP *abbr. for* isethionyl-3-(*N*-2,4-dinitrophenyl)amino propioimidate; a reagent useful in the isolation of plasma membranes. It reacts with, but does not penetrate, the membranes and leaves the net charge on the proteins unaltered.

ido- *prefix (in chemical nomenclature)* indicating a particular configuration of a set of four (usually) contiguous >CHOH groups, as in the acyclic form of D- or L-idose. *See* **monosaccharide**.

Ido *symbol for* a residue (or sometimes a molecule) of the aldohexose idose.

IdoA *symbol for* a residue of iduronic acid.

idose *symbol*: Ido; *ido*-hexose; an aldohexose whose D- and L-enantiomers are epimeric at C-2, C-3, and C-4 with D- and L-glucose, respectively.



β-D-idose

idoxuridine 5-iodo-2′-deoxyuridine; a pyrimidine nucleoside analogue, metabolized to the triphosphate, that inhibits DNA replication by substituting for thymidine in viral and mammalian DNA incorporation. It is used as an antiviral agent.



IDP *abbr. for* **1** the ribonucleotide inosine (5′-)diphosphate. **2** isopentenyl diphosphate (*formerly called* Δ^3-isopentenyl pyrophosphate).

IDU *abbr. for* 5-iodo-2′-deoxyuridine (*see* **idoxuridine**).

IdUrd *symbol for* 5-iodo-2′-deoxyuridine (*see* **idoxuridine**) (preferred to IDU, IUdR, or IUDR).

iduronate **1** the anion of **iduronic acid**. **2** any salt or ester of iduronic acid.

iduronate-2-sulfatase EC 3.1.6.13; *other name*: chondroitin sulfatase; an enzyme that hydrolyses the 2-sulfate groups of the L-iduronate 2-sulfate units of dermatan sulfate, heparan sulfate, and heparin.

iduronic acid *symbol*: IdoA; the **uronic acid** formally derived from idose by oxidation to a carboxyl group of the hydroxymethylene group at position 6. In nature *α*-linked L-iduronic-acid residues, sulfated at position 2, occur in terminal positions in dermatan sulfate and heparan sulfate; these iduronic-acid residues are formed by epimerization of the configuration at C-5 of D-glucuronic-acid residues in these heteropolysaccharides.

L-iduronidase EC 3.2.1.76; an enzyme that hydrolyses *α*-L-iduronosidic linkages in desulfated dermatan. Deficiency leads to mucopolysaccharidosis I H.

iduronosyl the glycosyl group formed by removal of the anomeric hydroxyl group from **iduronic acid** or iduronate.

IE *abbr. for* **1** immunoelectrophoresis (alternative to IEP). **2** information extraction.

IEC *abbr. for* ion-exchange cellulose.

IED *abbr. for* individual effective dose. IED$_{50}$ denotes the median of the IEDs within a group of subjects.

IEF *abbr. for* isoelectric focusing.

IEP *abbr. for* **1** immunoelectrophoresis (alternative to IE). **2** *or* **i.e.p.** isoelectric point (pI preferred).

IF *abbr. for* initiation factor. Suffixed numerals are added to designate individual factors, e.g. **IF-1**, **IF-2**, IF-2a, **IF-3**. Eukaryotic initiation factors are generally denoted by the prefix ‘e’, e.g. eIF-2, eIF-3.

IF-1 an *Escherichia coli* **initiation factor**.

IF-2 an *Escherichia coli* **initiation factor**.

IF-3 an *Escherichia coli* **initiation factor**.

IFCC *abbr. for* International Federation of Clinical Chemistry.

IFN *abbr. for* interferon. Suffixed Greek letters are added to differentiate the main classes, e.g. IFN-α, IFN-β, IFN-γ.

Ig *symbol for* immunoglobulin.

IgA *symbol for* immunoglobulin A.

IgA nephropathy a form of primary glomerulonephritis that is common throughout the world. There is reduced hepatic clearance of IgA, which deposits in the renal glomeruli.

IgA protease *another name for* **IgA-specific serine endopeptidase**.

IgA-specific serine endopeptidase EC 3.4.21.72; *other name*: IgA protease; a secreted bacterial serine protease that catalyses the cleavage of immunoglobulin A molecules at certain Pro-|-Xaa bonds in the hinge region. A signal peptide guides the enzyme precursor to the periplasmic space, and the C-terminal helper domain forms a pore in the outer membrane for exit of the protease domain. The helper domain is then released by autoproteolysis.

IG cell *abbr. for* intestinal gastrin cell; a small, granulated, gastrin-producing cell of the human upper small intestine. IG cells are smaller than, and ultrastructurally different from, CCK-producing **I cells**, gastrin-producing **G cells** of the gastric pylorus, and **TG cells**.

IgD *symbol for* immunoglobulin D.

IgE *symbol for* immunoglobulin E.

igensin a neutral cytosolic serine proteinease, activated by sodium dodecyl sulfate and found in a number of mammalian tissues.

IGF *abbr. for* insulin-like growth factor.

IGFBP *abbr. for* insulin-like growth factor binding protein.

IgG *symbol for* immunoglobulin G. Suffixed numerals are added to designate individual subclasses, e.g. IgG1, IgG2, IgG3, IgG4.

Ig-Hepta a rat glycoprotein (1389 amino acids) that is a G-protein-coupled membrane receptor with a long N-terminal extracellular region containing two C2-type Ig-homology units. It occurs on lung cell surfaces, and probably functions in cell adhesion and intracellular signalling. It defines a subgroup of G-protein-coupled receptors designated **LNB-TM7**.

Ig-like domain *see* **immunoglobulin fold**.

IgM *symbol for* immunoglobulin M.

β IG-M1 *see* **connective tissue growth factor**.

β IG-M2 *see* **connective tissue growth factor**.

ignose the name first proposed for ascorbic acid by A. Szent-Györgyi, before he knew its structure. *See also* **godnose**, .

IGT *abbr. for* impaired glucose tolerance.

Ii *see* **invariant chain**.

Ii system a blood group system in which the antigenic determinant is an oligosaccharide related to the ABH system (*see* **ABH antigens**). Anti-I and anti-i are the major **cold autoantibodies**; the former occur in the transient anemia accompanying viral or *Mycoplasma pneumoniae* infections; the latter are characteristic of the chronic cold agglutinin disease, accompanying chronic lymphoproliferative diseases of the non-Hodgkin type. The structures of the determinants are: i determinant, GlcNAc(*β*1-3)Gal(*β*1-4)GlcNAc*β*1-R; I determinant, Gal(*β*1-4)[Gal(*β*1-4)GlcNAc(*β*1-6)]GlcNAc(*β*1-3)-Gal(*β*1-4)GlcNAc*β*1-R.

ikaros a protein that binds and activates the **enhancer** of a gene *CD3-*δ involved in T-lymphocyte specification and maturation. Similar to **hunchback**, it is a zinc-finger protein.

IL *abbr. for* interleukin. Various interleukins are distinguished by suffixed numerals, e.g. IL-1, IL-2, IL-3, etc.

ILA *abbr. for* insulin-like activity.

Ile *symbol for* a residue of the *α*-amino acid L-isoleucine (alternative to I).

ileum the lower part of the small intestine, extending from the jejunum to the large intestine. —**ileal** *adj.*

illegitimate transcription transcription at a low level of a normally tissue-specific transcribing gene in nonspecific cells.

Im *abbr. for* immunity protein.

IM *or* **i.m.** *abbr. for* intramuscular, or intramuscularly.

image analysis analysis of a digital image, characterizing its content in terms of, e.g., physical measurements, anomalous features, tagged pixels, or 2D or 3D representations suitable for computer graphics rendering.

imaging the production of an image of all or part of the body using techniques such as X-radiography, ultrasound scanning, nuclear magnetic resonance scanning, radionuclide scanning, or thermography and particularly used for gene expression and proteomic data. *Compare* **tomography**.

imidate **1** any salt or ester of an **imidic acid**. **2** to convert an oxo diacid into its corresponding **imide**. —**imidation** *n.*

imidazole *or (formerly)* **glyoxaline** *or* **iminazole** 1,3-diazole; 1,3-diaza-2,3-cyclopentadiene; a weak base, pK_a ~6.95, used as a **buffer** (def. 1). The numbering and tautomerism of the imidazole ring are described at **histidine**.



imidazole 4-acetate a product of histamine metabolism; it results from the action of monoamine oxidase on histamine to form imidazole 4-acetaldehyde, which is then oxidized by an NAD^+-dependent aldehyde dehydrogenase to imidazole 4-acetate. *See also* **histidine**.

imidazoline receptor any mitochondrial or plasma membrane binding site for compounds from the generic groups imidazoles, imidazolines, imidazolidines, guanidines, and oxazolines, and having a putative endogenous ligand, **agmatine**. Imidazoline receptors occur throughout the brain, being possibly associated with glial cells, and in peripheral tissues. **I_1 receptors** have high affinity for *p*-aminoclonidine and are localized in plasma membranes. **I_2 receptors** have high affinity for idazoxan and are localized in mitochondrial membranes. The latter are known alternatively as nonadrenergic imidazoline binding sites (NAIBSs). Photoaffinity labelling to at least three proteins occurs: two, of 55 kDa and 61 kDa, respectively, are found in rat liver and differ in their affinity for the guanidium, amiloride; a third, of 61 kDa, is found in PC-12 cells and has high affinity for amiloride but low affinity for idazoxan. These proteins may represent different I_2 receptors. Subtypes of I_2 receptors are also suggested pharmacologically. The function of imidazoline receptors is not known, but many effects of imidazoline compounds, formerly attributed to their binding to α_2 receptors (e.g. hypotension), are now attributed to NAIBSs.

imidazolium **1** the cation formed by addition of a proton (hydron) to a molecule of **imidazole**. **2** the cationic chemical group formed by addition of a proton (hydron) to an **imidazolyl** group.

imidazolyl the chemical group derived formally by removal of one hydrogen atom from **imidazole**. The position from which the hydrogen atom has been removed may be indicated, e.g. 2-imidazolyl. The imidazolyl group is present in **histidine** and its derivatives.

imide any secondary organic amide (i.e., any diacyl derivative of ammonia or a primary amine), especially any that is a cyclic compound in which both of the acyl groups (which may be the same or different) are derived formally or actually from a diacid. (*Note*: non-cyclic symmetrical secondary organic amides are generically termed **diacylamines**.)

+imide *suffix* designating any organic compound that is an **imide**. The nitrogen atom may be substituted with a named alkyl or other group. An example is succinimide:



succinimide

imidic acid any derivative of a carboxylic acid in which the carbonyl oxygen atom of the carboxyl group has been replaced by an **imino** (def. 1) or alkylimino group; i.e., any containing the –C(=NR)–OH group. *Distinguish from* **imino acid**.

imido+ *comb. form* designating any inorganic oxo acid (including the anions, salts, and esters) in which =O has been replaced by =NH or =NR (where R is a named substituent), or any derived di-, tri-, etc. acid in which a bridging oxygen atom, –O–, has similarly been replaced by –NH– or –NR–; e.g., **adenosine 5′-[β,γ-imido]triphosphate**.

imidodipeptiduria *or* **prolidase deficiency** the presence in urine of peptides of structure X-Pro or X-Hyp in which X is frequently glycine. It results from deficiency of X-Pro dipeptidase and is accompanied by severe ulcers, mostly of the feet and hands, and frequently by mental retardation.

Imigran *see* **sumatriptan**.

iminazole *a former name for* **imidazole**.

imine **1** any organic compound containing one or more **imino** groups or substituted imino groups. **2** *an obsolete term for* azacycloalkene.

iminium the bivalent quaternary nitrogen-containing cationic group $=^+NR_2$ attached to carbon in a chemical compound, where the R groups may each be hydrogen or any hydrocarbyl group.

imino the bivalent group =NH attached to carbon in a chemical compound.

imino+ *comb. form* denoting the presence in a chemical compound of one or more **imino** groups; the number of imino groups in the molecule may be specified, e.g. diimino+.

imino acid any carboxylic acid in which an imino substituent replaces two hydrogen atoms. In biochemistry, the term is commonly applied also to certain cyclic alkylamino (especially α-alkylamino) derivatives of aliphatic carboxylic acids, e.g. **proline**, although such compounds are now preferably classed as azacycloalkane carboxylic acids. *Compare* **imidic acid**.

iminodipeptidase *see* **Pro-X dipeptidase**.

iminoglycinuria the secretion in urine of excessive amounts of glycine, proline, and hydroxyproline, due to a defect in their shared transport in renal tubules. The condition is clinically benign.

imipenem a carbapenem β-lactam antibiotic that is a semisynthetic derivative of thienamycin produced by *Streptomyces cattleya*. Its broad-spectrum antibiotic actions resemble those of penicillins, i.e. inhibition of bacterial peptidoglycan synthesis.



immediate gene *or* **immediate-early gene** *see* **early gene**.

immediate hypersensitivity *or* **type I hypersensitivity** a type of **hypersensitivity** responsible for asthma, hayfever, and some types of eczema. It occurs within minutes of exposure to antigen and depends on activation of **mast cells** and the release of mediators of acute inflammation. The mast cells bind **immunoglobulin E** (IgE) at their surface **Fc receptors** and when antigen cross-links the IgE, the mast cells degranulate releasing vasoactive amines that mediate the symptoms.

immobilize *or* **immobilise** to render any agent, whether a micro- or macrosolute, a particle, or an intact cell, nondispersible in an aqueous medium with retention of its specific ligating, antigenic, catalytic, or other properties. Immobilization may be achieved by, e.g., encapsulation, entrapment in a small-pore gel, adsorption on, or covalent linkage to, an insoluble supporting material (matrix), or through formation of aggregates by cross-linkage.

immobilized enzyme *see* **solid-phase technique**.

immortalization *or* **immortalisation** the **transformation** of a cell population with a finite life span to one possessing an infinite life span. It is a characteristic of cancer cells, and is of practical importance in, e.g., the creation of **monoclonal antibodies**. Immortalization of eukaryotic cells may be effected experimentally by infection with certain viruses, or by fusion of the cell with a neoplastic cell to form a **hybridoma**. **—immortalize** *or* **immortalise** *vb.*

immotile cilia syndrome a genetically heterogeneous human disease characterized by impaired mobility or complete immobility of the cilia of airways and elsewhere and of sperm tails. Electron microscopy of such ciliated cells usually shows a lack of dynein arms between the longitudinal microtubular doublets, but other abnormalities may also be present.

immune **1** relating to or possessing **immunity**. **2** regarding or describing an animal that has been immunized. **3** *an alternative word for* **immunological**.

immune adherence the **complement**-dependent adherence of antibody–antigen complexes, or of antibody-coated bacteria (or other particles), to primate erythrocytes, causing the agglutination of the latter.

immune clearance *an alternative term for* **immune elimination**.

immune complex *an alternative term for* **antigen–antibody complex**.

immune complex-mediated hypersensitivity *or* **type III hypersensitivity** a type of **hypersensitivity** caused by the deposition of antigen–antibody complexes in tissue and blood vessels. The complexes activate **complement** and attract polymorphs and macrophages to the site.

immune cytolysis the **complement**-dependent lysis of cells by antibody molecules. When the cells concerned are erythrocytes the process is termed **immune hemolysis**.

immune elimination *or* **immune clearance** the accelerated, exponential removal of antigen from an immune animal as a result of complexing with antibody molecules.

immune globulin *(sometimes) an alternative name for* **immunoglobulin**.

immune hemolysis *see* **immune cytolysis**.

immune response the total immunological reaction of an animal to an immunogenic stimulus. It includes antibody formation, the development of hypersensitivity, and immunological tolerance.

immune serum *an alternative term for* **antiserum**.

immunity freedom and protection from 'infection'. Two forms of immunity can be recognized: (1) innate, meaning non-specific antimicrobial systems (e.g. phagocytosis) that are innate in that they are not intrinsically affected by prior contact with the infectious agent; and (2) the state of an animal that has an enhanced ability, above the nonimmune state, to respond to some (specific) antigen in which the antigen is bound and rendered inactive or eliminated from the body. *See also* **active immunity**, **passive immunity**.

immunity protein *abbr*.: Im; a protein, cosynthesized in *E. coli* with **colicin**, that binds to the nuclease domain of the colicin and inhibits its activity. Ims specific for RNase domains contain 84 amino acids, which form mostly beta strands. Those specific for DNase domains contain 86 amino acids and form four alpha helices.

immunization *or* **immunisation** any procedure carried out on an animal, e.g. the administration of antigen or antibody, that leads to an increased reactivity of the animal's immune system towards an antigen or antigens. **—immunize** or **immunise** *vb.*

immuno+ *comb. form* indicating immune or immunity.

immunoadsorbent any insoluble preparation of an antigen (or antibody) suitable for use in **immunoadsorption**. *See also* **immunosorbent**.

immunoadsorption the use of an insoluble antigen (or antibody) to remove specifically unwanted antibodies (or antigens) from a mixture so as to make the antibody (or antigen) more specific. *Compare* **adsorption** (def. 2). *See also* **immunosorption**.

immunoaffinity chromatography a type of **affinity chromatography** in which one of the two components of an antigen–antibody system is coupled to an insoluble matrix and used for the separation and purification of the other component.

immunoaffinity column a chromatographic column used in **immunoaffinity chromatography**.

immunoassay 1 any technique for the measurement of specific biochemical substances, commonly at low concentrations and in complex mixtures such as biological fluids, that depends upon the specificity and high affinity shown by suitably prepared and selected antibodies for their complementary antigens. A substance to be measured must be antigenic – either an immunogenic macromolecule or a haptenic small molecule. To each sample a known, limited amount of specific antibody is added and the fraction of the antigen combining with it, often expressed as the bound:free ratio, is estimated, using as indicator a form of the antigen labelled with a radioisotope (**radioimmunoassay**), fluorescent molecule (**fluoroimmunoassay**), stable free radical (**spin immunoassay**), enzyme (**enzyme immunoassay**), or other readily distinguishable label. The amount of the antigen in the sample is found by comparison with standards containing known amounts. *See also* **heterogeneous immunoassay**, **homogeneous immunoassay**, **saturation analysis**. **2** *an alternative name for* **radioimmunoassay**. **3** to carry out or to estimate (something) by an **immunoassay** (def. 1, 2).

immunobiology the branch of biology dealing with the activities of the cells of the immune system and their relationship to each other and to their environment. **—immunobiological** *adj.*

immunoblotting a technique for the detection of specific polypeptides separated by **polyacrylamide gel electrophoresis** (PAGE). The bands are transferred from the gel to a nylon or nitrocellulose membrane by Western blotting, followed by immunological detection of the immobilized antigen.

immunochemical 1 of or relating to **immunochemistry**. **2** any specific immunological reagent that consists of or incorporates an antigen or an antibody, especially one of commerce.

immunochemistry the branch of biochemistry dealing with the chemical nature of antigens, antibodies, and their interactions, and with the chemical methods and concepts as applied to immunology.

immunochromatogram the pattern of precipitation bands formed in **immunochromatography**.

immunochromatography any of various techniques for separating and identifying soluble antigens. In one method, analogous to **immunoelectrophoresis**, the antigens are first fractionated through a thin-layer chromatogram, e.g. of Sephadex; the fractions are then diffused against a trough containing a solution of antibodies (antiserum). In another method a small drop of antigen–antiserum mixture is applied to filter paper, or resin-impregnated paper, and the chromatogram developed with buffer; any antigen–antibody complex remains at the point of application and can be detected with a protein stain, while the other proteins are washed away from the origin.

immunocompetent cell an immunologically competent cell.

immunocyte any **immunologically competent cell**.

immunocytochemistry **cytochemistry** using appropriately labelled antibody preparations to detect specific cellular components. **—immunocytochemical** *adj.*

immunodeficiency any condition in which there is a deficiency in the production of humoral and/or cell-mediated immunity. **—immunodeficient** *adj.*

immunodeterminant *an alternative name for* **antigenic determinant**.

immunodiagnosis the diagnosis of disease by immunological methods.

immunodiagnostic 1 of or relating to **immunodiagnosis**. **2** any specific immunological reagent used in diagnosis.

immunodiffusion any of various analytical methods by which components of soluble antigen or antibody mixtures may be distinguished. Essentially, the antigens and antibodies are allowed to diffuse towards each other in a translucent gel, wherein they react to gives lines or bands of precipitation in characteristic positions. Such methods include: **double immunodiffusion**, **electroimmunodiffusion**, **immunochromatography**, **immunoelectrophoresis**, immunorheophoresis, and **single radial immunodiffusion**. **—immunodiffuse** *vb.*

immunodominance the attribute of a part of an **epitope** that contributes a disproportionately great portion of the binding energy; e.g. the immunodominance shown by a monosaccharide residue in determining the antigenic specificity of a polysaccharide. **—immunodominant** *adj.*

immunoelectrofocusing *or* **immunoisoelectric focusing** a technique that is analogous to **immunoelectrophoresis** but with the preliminary fractionation of one of the reactants being effected by electrofocusing instead of electrophoresis.

immunoelectron microscopy a form of electron microscopy in which structures are stained with specific antibodies labelled with an electron-dense material.

immunoelectropherogram *(sometimes)* the record of an immunoelectrophoresis experiment, either the electrophoretic support itself or a tracing derived therefrom.

immunoelectrophoresis *abbr*.: IE *or* IEP; a technique for separating and identifying soluble antigens. It consists of **zone electrophoresis**, in a reasonably transparent gel, in one direction followed by **immunodiffusion** against a solution of antibodies (antiserum) placed in a trough parallel to the direction of electrophoresis. In suitable conditions each antigen shows up as an arc of precipitation in a characteristic position. **—immunoelectrophoretic**, **immunoelectrophoretical** *adj.*

immunoenzymatic of or pertaining to the particular techniques used in **immunoenzymology**.

immunoenzymology the subspeciality of immunochemistry in which the activity of enzymes coupled to antigens or antibodies is utilized as a molecular amplifier of antigen–antibody reactions.

immunofixation *or* **immunofixation electrophoresis** a variant of **immunoelectrophoresis**, or **immunoelectrofocusing**, in which proteins of a single immunological species are anchored to the support by treatment with monospecific antibodies, allowing the other proteins to be washed out of the support. It is useful in the identification of proteins in complex mixtures or of minor proteins obscured in electrophoretic patterns.

immunofluorescence *or* **immunofluorescence microscopy** a technique in which an antigen or antibody is made fluorescent by conjugation to a fluorescent dye and then allowed to react with the complementary antibody or antigen in a tissue section or smear. The location of the antigen or antibody can then be determined by observing the fluorescence by microscopy under ultraviolet light. **—immunofluorescent** *adj.*

immunogelfiltration a variant of **radial single immunodiffusion** in which antigen is first fractionated according to its molecular size by permeation, in a buffer solution, into a thin layer of an appropriate cross-linked dextran gel. The dextran layer is then covered with a layer of agarose gel containing antibody. Rings or spots of antigen–antibody precipitate develop in the agarose gel over the complementary antigens.

immunogen **1** any substance that, when introduced into the body, elicits humoral or cell-mediated immunity, but not immunological tolerance. **2** any substance that is able to stimulate an immune response, as distinct from substances (antigens) that can combine with antibody. **3** any substance that is able to stimulate protective immunity against a pathogen, as distinct from an immune response that is of no intrinsic value to the animal immunized. **—immunogenic** *adj.*

immunogenetics *(functioning as sing.)* the branch of biology that combines immunology and genetics. It includes the use of immunological methods and knowledge in the study of genetics, and the use of genetics in the study of immunological phenomena and substances. **—immunogenetic** *adj.*

immunogenicity *an alternative term for* **antigenicity**.

immunoglobulin *symbol*: Ig; any protein occurring in higher animals as a major component of the immune system. Immunoglobulins are produced by lymphocytes, and virtually all possess specific antibody activity. Each immunoglobulin comprises four polypeptide chains, two identical **heavy chains** and two identical **light chains**, linked together by disulfide bonds; all contain in addition differing amounts of attached oligosaccharide. There are five classes, IgA, IgD, IgE, IgG, and IgM. The primary structures of the heavy chains differ among the various classes, being designated α, δ, ε, γ, and μ, respectively, and there are two types of light chain, κ and λ. IgA and IgM molecules contain multiples of the four-chain unit. The homology units form a characteristic structure, the **immunoglobulin fold**. *See also* **immunoglobulin A**, **immunoglobulin D**, **immunoglobulin E**, **immunoglobulin G**, **immunoglobulin M**.

immunoglobulin A *symbol*: IgA; an **immunoglobulin** found in human plasma, mostly as a 170 kDa monomer of the basic four-chain immunoglobulin structure or, as a 400 kDa dimer, together with an extra 15 kDa polypeptide, the **J chain**, linked to **secretory piece**. It is the major immunoglobulin of seromucous secretions, in which it protects external body surfaces against attack by microorganisms. It has the structure $(\alpha_2 l_2)_n$ J, where α is the heavy chain, l is the light chain (κ or λ), J is the J chain, and *n* is 1 or 2. *See also* **IgA-specific serine endopeptidase**.

immunoglobulin amyloidosis the commonest form of systemic **amyloidosis** in humans. The amyloid fibrils consist of λ and κ Ig light chains that are overproduced by a clone of B lymphocytes.

immunoglobulin D *symbol*: IgD; a 185 kDa **immunoglobulin** that is very susceptible to proteolytic degradation and has a very short half-life in plasma. It is found in an integral membrane protein form, together with immunoglobulin M, on the surface of B lymphocytes, where both function as antigen receptors and control lymphocyte activation and suppression. It has the structure $\delta_2 l_2$ where δ is the heavy chain and l is a light chain (κ or λ). *See* **hyper-IgD syndrome**.

immunoglobulin E *symbol*: IgE; a 200 kDa **immunoglobulin** of high carbohydrate content, normally found in very low concentrations in plasma, although its concentration there is elevated in allergic conditions. IgE is synthesized mainly in lymphoid tissue of gut and respiratory tract. It binds strongly to mast cells and contact with antigen leads to degranulation of the mast cells and release of inflammatory mediators. It has the structure $\varepsilon_2 l_2$ where ε is a heavy chain and l is a light chain (κ or λ).

immunoglobulin fold a series of β strands, arranged as two antiparallel β sheets packed tightly against each other, that is highly characteristic of immunoglobulin homology units. In the constant region, the two β sheets consist of four and three β strands respectively. In the variable region there are nine β strands (five and four). This type of structure is found in many other proteins, especially cell surface receptors, and is often referred to as an **Ig-like domain**.

immunoglobulin G *symbol*: IgG; the principal **immunoglobulin** of human plasma and other internal body fluids. It is a 150 kDa protein and is the major immunoglobulin synthesized during the secondary response to an antigen. In the tissue fluids it neutralizes bacterial toxins and binds to microorganisms thereby enhancing their phagocytosis. Complexes of IgG with microorganisms activate **complement** by the classical pathway. IgG binds to macrophages and polymorphonuclear leukocytes and can cross the placenta. It has the structure $\gamma_2 l_2$ where γ is a heavy chain and l is a light chain (κ or λ). There are subclasses of IgG depending on different types of γ chain.

immunoglobulin M *symbol*: IgM; a 900 kDa **immunoglobulin** consisting of a star-shaped polymer of five basic four-chain structures, each heavy chain bearing an extra constant domain. Polymerization is dependent on the presence of **J chain**, which may act to stabilize the sulfhydryl groups in the constant portion of the heavy chains during IgM synthesis. IgM is produced early in the immune response and is mainly found intravascularly. Because of its high antigen-combining valency it is very effective in binding microorganisms and mediating **complement**-dependent cytolysis. It has the structure $(\mu_2 l_2)_5$J where μ is a heavy chain, l is a light chain (κ or λ), and J is a J chain. Virgin B lymphocytes have a transmembrane sequence at the C terminus of μ and the switch is effected by alternative splicing. In **heavy chain disease** the protein has no C and C_H1 regions due to deletion. *See* **hyper-IgM syndrome**.

immunoglobulin superfamily a superfamily of proteins that have similarities of sequence and structure to immunoglobulins. There are three sets, based on immunoglobulin domains: one with variable-like domains, the V set, and two with variants of the constant-like domains, the C1 and C2 sets.

immunogold labelling a method of labelling specific molecules in electron-microscopic thin sections using electron-dense gold particles attached to specific antibody molecules.

immunogram *(sometimes)* the pattern of bands or lines of precipitation formed in a gel by **immunodiffusion**.

immunohistochemistry a form of **histochemistry** in which appropriately labelled antibody preparations are used to detect specific structures in tissues. **—immunohistochemical** *adj.*

immunoliposome a **liposome** bearing a chemically coupled monoclonal antibody.

immunolocalization *or* **immunolocalisation** the use of appropriately labelled antibody (or antigen) preparations to detect the position of specific structures or components that contain or are the complementary antigens (or antibodies).

immunological *or (esp. US)* **immunologic** of, concerned with, or pertaining to immunity or immunology. **—immunologically** *adv.*

immunologically competent (of cells, tissues, etc.) qualified for and capable of giving an **immune response**.

immunological paralysis *an alternative name for* **acquired tolerance**.

immunological rejection the destruction, by a specific immune reaction, of foreign cells or tissues transplanted or inoculated into a recipient animal from a donor animal.

immunological response any specific response to an antigen. It includes **cell-mediated immunity**, **humoral immunity**, and **immunological tolerance**.

immunological surveillance the postulated monitoring of the cells of large, long-lived animals by their immunological systems so that aberrant cells arising from somatic mutations, and so containing new antigens, are destroyed.

immunological tolerance a type of immunological response in which there develops a specific nonreactivity of the lymphoid tissues towards a given antigen, one that in other circumstances is able to induce cell-mediated or humoral immunity. Immunological tolerance may follow contact with the antigen in fetal or early postnatal life or the administration of the antigen to adults (**acquired tolerance**). The reaction towards other, unrelated antigens is unaffected.

immunology the study of **immunity** and related phenomena. The science of immunology grew out of the study of resistance to infectious disease, and now encompasses the study of antigens, antibodies, and their interactions both *in vivo* and *in vitro*, and the cellular phenomena of recognition of, and responsiveness to, foreign substances. Related disciplines include **immunobiology** and **immunochemistry**.

immunometry the measurement of amounts of substances by the use of specific antigen–antibody reactions. **—immunometric** *adj.*; **immunometrically** *adv.*

immunomodulation the alteration of an immune response by an agent other than the antigen.

immunomodulator any agent that alters the extent of the immune response to an antigen, by altering the antigenicity of the antigen or by altering in a nonspecific manner the specific reactivity or the nonspecific effector mechanisms of the host. Immunomodulators include adjuvants, immunostimulants, and immunosuppressants.

immunoosmophoresis *an alternative term for* **counter(immuno)electrophoresis**.

immunophenotyping the **typing** of cells with immunological markers such as monoclonal antibodies.

immunophilin one of a conserved group of proteins that bind the immunosuppressant drugs cyclosporin A, FK506, and rapamycin. All have peptidylprolyl isomerase activity and play major roles in protein folding and trafficking within cells. Cyclosporin A binds to a cyclophilin, while FK506 and rapamycin bind to FK506-binding proteins (FKBPs). Immunophilins inhibit S6 kinase and several cyclin-dependent kinases. They also bind to the Hsp90 component of unliganded steroid hormone receptors. *See* **mTor**.

immunoprecipitate 1 the precipitate formed in an antigen–antibody reaction. **2** to precipitate (something) by reaction with a specific antibody or antigen. **—immunoprecipitation** *n.*

immunoradiometric assay *abbr.*: IRMA; an alternative method to **radioimmunoassay** for the measurement of very small amounts of nonradioactive material. An excess amount of a specific antibody labelled with a radioactive isotope is added to the sample containing the substance to be assayed. After equilibration, unreacted antibody is removed and the amount of radioactive material remaining is measured.

immunoreactive capable of reacting with a specific antibody. The term is used especially of substances that react with an antibody directed against a particular peptide hormone (or part of such a hormone) but that do not necessarily exhibit the expected physiological or pharmacological activity. **—immunoreactivity** *n.*

immunosorbent any sorbent used in, or useful for, **immunosorption**. *See also* **immunoadsorbent**.

immunosorption the use of antigens (or antibodies) immobilized on a solid matrix to remove specifically the complementary antibodies (or antigens) from a mixture and their subsequent elution from the solid phase. It is used in, and is useful for, purification of antibodies (or antigens). *See also* **immunoadsorption**.

immunostimulant any agent that nonspecifically enhances the immunologically specific reactivity of an animal to an antigen and also the animal's nonspecific effector mechanisms. **—immunostimulatory** *adj.*

immunosuppressant *or (sometimes)* **immunosuppressive** any agent that causes **immunosuppression**.

immunosuppressed describing an organism that is incapable of showing an immune response to an antigen.

immunosuppression the suppression of immune responses to antigens. This can be achieved by various means, including physical (e.g. X-irradiation), chemical (e.g. antimetabolic drugs), or biological (e.g. antilymphocyte serum). After transplant surgery **azathioprine** is commonly used. This drug has a preferential effect on T-cell-mediated reactions. It is degraded in the body first to mercatopurine and is then converted to the active agent, the ribotide, which inhibits nucleic-acid synthesis. **Methotrexate**, cyclophosphamide, **cyclosporin A**, and **FK506** are also highly effective immunosuppressants, the latter two being used extensively. Infection by HIV-1 eventually leads to a reduction in the population of helper T-cells and macrophages. This immunosuppression of the system is associated with occurrence of **Kaposi's sarcoma** and allows infection by agents such as *Pneumocystis carini*, cytomegalovirus, and tuberculosis. *Compare* **immunodeficiency**. *See also* **suppressor cell**.

immunosuppressive 1 able to cause **immunosuppression**. **2** *an alternative term for* **immunosuppressant**.

immunosympathectomy the destruction of some or all of the neurons of the sympathetic nervous system by injections into a newborn animal of an antiserum to the appropriate **nerve growth factor**.

immunotoxin any of a class of therapeutic drugs consisting of a monoclonal antibody linked to a toxic protein (e.g. ricin, diphtheria toxin).

IMP *abbr. for* **1** inosine monophosphate; i.e. inosine phosphate. **2** ion-moderated partition.

impaired glucose tolerance *abbr.*: IGT; the term recommended to denote a clinical state or condition of humans that is intermediate between the normal one and the overtly diabetic. Characteristically, in a standard oral **glucose-tolerance test** in non-pregnant adults, the glucose concentration in capillary whole blood or venous plasma taken at 2 hours is in the range 8–11 mmol L^{-1} (1.4–2.0 gL^{-1}); the corresponding values for venous whole blood are 7–10 mmol L^{-1} (1.2–1.8 gL^{-1}). In addition, the fasting plasma glucose must be below 8 mmol L^{-1}, and plasma glucose during the test must be greater than 11 mmol L^{-1} at 30, 60, and 90 min.

IMP cyclohydrolase EC 3.5.4.10; *other names*: IMP synthetase; inosinicase; an enzyme of the pathway for *de novo* purine biosynthesis that cyclizes 5-formamido-1-(5′-phosphoribosyl)imidazole-4-carboxamide to IMP with elimination of H_2O. For an example, *see* **phosphoribosylaminoimidazolecarboxamide formyltransferase**.

IMP dehydrogenase EC 1.1.1.205; *other name*: inosine-5′-monophosphate dehydrogenase; an enzyme that catalyses the conversion of inosine 5′-phosphate, NAD^+, and H_2O to xanthosine 5′-phosphate and NADH. The reaction involves the introduction of an oxo group at the purine C-2. Xanthosine 5′-phosphate is then converted to guanosine 5′-phosphate by **GMP synthase** (glutamine hydrolysing). In humans there are two isoenzymes.

impedance *symbol*: Z; the quality determining the amplitude of the current flowing in a circuit for a given applied alternating electric potential. It depends upon the electric resistance, self-inductance, and capacitance of the circuit.

impeller 1 the vaned, rotating disk of a centrifugal pump. **2** any device incorporating an **impeller** (def. 1).

impermeable (of a substance or structure) not permitting the passage through it of a fluid or of a particular solute in a fluid; not permeable. **—impermeability** *n.*

impermeant (of a fluid or a solute in a fluid) incapable of passing through a particular substance or structure.

importin *or* **karyopherin** a heterodimeric protein essential for the import of proteins from the cytoplasm to the nucleus. The α subunit binds the nuclear localization signal of the cargo protein, and the β subunit binds to nucleoporins of the nuclear pore. Entry into the nucleus is mediated by the GTPase Ran, and the α and β subunits subsequently exit the nucleus separately. Importin is also involved in aster formation during cell division.

imprinting *(in genetics)* the phenomenon whereby the expression of genes is determined by the parent who contributed them. For example, the onset of Huntington's disease is earlier if the defective allele is inherited from the father rather than the mother. A maternal allele can be expressed exclusively because the paternal allele is silenced by methylation or other modification, or vice versa. Some 70 imprinted genes have so far been discovered in both mouse and human, and of these roughly half are maternally imprinted and half paternally.

impulse 1 *(in physics)* a vector quantity equal to the integral of the force, $\boldsymbol{F}$, acting on a body with respect to the time, t, over which the force acts: $\int \boldsymbol{F} \mathrm{d}t$. If the force is constant the expression reduces to the product $\boldsymbol{F}t$. It also equals the total change of momentum of the body induced by the applied force. **2** *(in physics)* an electrical surge of unidirectional polarity. **3** *(in physiology) or* **nerve impulse** an all-or-none signal propagated along the axons of neurons by which information is transmitted rapidly and precisely through the nervous system. It consists of a sequence of changes in ionic permeability of the neuronal membrane that gives rise to ionic currents and associated changes in transmembrane electrical potential.

impure not pure, lacking purity; (of a substance or material) containing contaminants.

impurity 1 the state or quality of being impure. **2** any or all of the admixed components in an impure substance or material.

impurity quenching **chemical quenching** due to an **impurity** (def. 2).

In *symbol for* indium.

inappropriate secretion a clinical syndrome in which the secretion of a specified hormone, commonly **antidiuretic hormone**, is abnormally high relative to the state of the normal regulatory mechanisms. It is so termed because it results from an unknown or unmistakably abnormal cause and serves no recognizable homeostatic function.

inborn error of metabolism any genetically determined biochemical variation occurring in humans. Such variations are highly specific and represent many diverse metabolic phenomena, resulting in very varied effects on the viability of the individual. The first such errors were publicized in 1909 by the British physician Archibald Garrod (1857–1936) in his book *Inborn Errors of Metabolism*.

inbred strain *or* **inbred line** a group of organisms obtained by repeated inbreeding over several successive generations, e.g. by self-pollination in plants or by repeated brother × sister matings in animals. Eventually, all individuals will possess identical sets of **autosomes**, and all the chromosome pairs will become homozygous.

INCHI *abbr. for* International chemical identifier.

inclusion *(in cytology)* **1** any discrete body or particle within a cell, especially a passive product of cell activity such as a starch or volutin granule. **2** *an alternative (less common) name for* **inclusion body**.

inclusion body *or* **inclusion 1** any discrete assembly of virions and/or viral particles that may be visualized in virus-infected cells, either in the nucleus or in the cytoplasm. **2** *(in bacteriology)* **a** any one of a number of bodies found within bacterial cells, such as storage granules (e.g. of glycogen, poly-*β*-hydroxybutyrate, polyphosphate, or sulphur), gas vacuoles, carboxysomes, and magnetosomes. **b** an insoluble complex of protein stored within the cytoplasm of bacterial cells and resulting from the overexpression of a foreign protein.

inclusion cell *abbr*.: I cell; a type of cell that is seen in tissues from patients with mucolipidosis II **(I-cell disease)** and that contains inclusions consisting of very large lysosomes whose contents are heterogeneous, comprising mucopolysaccharide, whorls of membrane, and other material.

inclusion-cell disease *or* **mucolipidosis II** *see* **I-cell disease**.

inclusion complex *or* **inclusion compound** any chemical complex in which one component (the host molecule) forms a crystal lattice containing tunnel- or channel-shaped spaces in which molecular entities of a second species (the guest molecule) are located. There is no bonding between the host and the guest molecules.

incompatibility 1 a criterion for classifying bacterial **plasmids**; two plasmids of the same incompatibility group cannot coexist in one host cell. The molecular basis is that the incompatible plasmids share sites during plasmid **segregation** (def. 3). **2** *(in phylogeny) an alternative name for* **incongruence**. **3** the state of being **incompatible**.

incompatibility group a group to which plasmids are said to belong if they cannot coexist in the same bacterial host over several generations without selection.

incompatible 1 *(in immunology)* having antigenic nonidentity between a donor and a recipient, e.g. in blood transfusion or tissue transplantation. **2** *(in therapeutics)* (of two drugs) incapable of being used together or combined; antagonistic.

incomplete antibody 1 any antibody whose activity in an agglutination test can only be demonstrated indirectly, e.g. by an antiglobulin test. **2** *(sometimes)* a univalent antibody fragment produced enzymically, e.g. a **Fab fragment**.

incomplete Freund's adjuvant *see* **Freund's adjuvant**.

incongruence *or* **incompatibility** *(in phylogeny)* difference of characters or trees suggesting different groups of relationships, owing to the presence of **homoplasy**.

incorporation 1 the act or process of including (something) as a part of a whole. **2** *(in biochemistry)* the inclusion of (isotopically labelled) metabolites, by covalent linkage, into biopolymers by living cells or cell-free preparations; often taken as an index of biosynthesis. **—incorporate** *vb.*

incretin a putative insulinogenic principle secreted from the duodenum and jejunum in response to the presence of glucose. Its effects are now generally considered to be attributable to **glucose-dependent insulinotropic peptide**.

incubate 1 to maintain at an appropriate temperature so as to favour growth, development, or continued survival (e.g. of cells); by extension, to maintain under specified conditions in a controlled or artificial environment (e.g. in studies of enzymic or antigen–antibody reactions), especially at a particular ambient temperature (which may be above or below that of the environment). **2** a material or preparation that has been incubated. **—incubation** *n.*

incubation mixture any reaction mixture that is maintained at a controlled temperature and/or in a controlled, artificial environment.

incubation period 1 *(in pathology)* the time interval between the invasion of an organism by a pathogenic virus or microorganism and the overt manifestation of disease. **2** *(in microbiology)* the period of development of a culture of bacteria or other microorganisms.

incubator any closable, heat-insulated cabinet that is maintained at a constant internal temperature (and, sometimes, humidity and/or atmosphere) and that is used for the growth or maintenance of cells, cultures, tissues, or organisms, or for the hatching of eggs.

indel an inserted or deleted position within a DNA or protein sequence **alignment**. The term reflects the difficulty in knowing whether the base or residue represents an insertion in one sequence or a deletion in the other relative to an ancestral sequence.

Inderal *see* **propranolol**.

index (*pl.* **indices** *or* **indexes**) (*in informatics*) a table of relations (or addresses) between or within data sets that enables rapid file searching. Searches are directed only to specific data subsets, obviating the need to search the data set serially. For example, SRS (Sequence Retrieval System) operates by searching indexed flat-file databases. *See* **information retrieval software**.

index of refraction *see* **refractive index**.

Indian tobacco *see* **lobelia**.

indican 1 metabolic indican indol-3-yl hydrogensulfate; 3-indoxylsulfuric acid; a so-called ethereal sulfate, formed in the gut by bacterial action on tryptophan and excreted in the urine, where its level may be taken as an index of intestinal stagnation. **2 plant indican** indol-3-yl-*β*-D-glucopyranoside; indoxyl-*β*-D-glucoside; a substance isolated from *Indigofera* spp., members of the Leguminosae, and *Polygonium tinctorium*. The glucoside is hydrolysed during extraction by water or dilute acid, and the indoxyl is liberated spontaneously, oxidizing to the blue dye indigo.

indicated hydrogen *symbol*: *H*- *(or sometimes H)* (with a prefixed locant); *(in chemical nomenclature)* an atom of hydrogen whose position in the molecular structure of an unsaturated cyclic organic compound or group requires to be explicitly stated in order to make the name of the compound or group specific to a particular structural isomer (or tautomer) if otherwise the name would apply equally to two or more isomers (or tautomers). The compound or group in question commonly consists of or is derived from a condensed ring system with the maximum number of non-cumulative double bonds, although the notation is applied also to certain monocyclic systems. The symbol (with its locant) ordinarily precedes the name or the relevant part of the name, e.g. 1*H*-purin-6-amine or 6-amino-1*H*-purine (alternative semisystematic names for one of the tautomers of adenine); however, where the insertion of a substituent into a cyclic structure has necessitated the addition of a hydrogen atom at another position the symbol is placed in parentheses after the locant for the substituent, e.g. purin-6(1*H*)-one (*a semisystematic name for* one of the tautomers of hypoxanthine).

indicator 1 any substance used in a chemical operation to indicate by a colour change the completion of a reaction or the attainment of a desired state. **2** any substance that by a characteristic colour change indicates the presence of another particular substance. **3** (*in* **saturation analysis**) the labelled substance whose distribution between the reactants of the system is used to determine the amount of analyte present. **4** an isotope, often a radioactive one, that is used as a tracer.

indicator enzyme *an alternative name for* **marker enzyme**.

indicator organism *or* **indicator species** any species of organism whose presence or population characteristics in a particular habitat are used to provide information about the nature of that habitat, especially regarding its degree of pollution.

indicator yellow *the original name for N*-retinylidene opsin. It was so called because its colour changes between yellow and orange according to the pH of its aqueous solution. It spontaneously hydrolyses into opsin and (all-*trans*-)retinal. *See* **rhodopsin**.

indigo a blue dye prepared from the same plants as plant **indican**. Its major blue component is **indigotin**.

indigotin [$\Delta^{2,2'}$-biindoline]-3,3′-dione; the major blue component of **indigo**.



indirect antagonism a form of **antagonism** (def. 2) arising as a consequence of competition by the antagonist for the binding site of an intermediate that links receptor activation to the observed effect.

INDO-1 1-[2-amino-5-(6-carboxyindol-2-yl)phenoxy]-2-(2-amino-5-methylphenoxy)ethane-*N*,*N*,*N*′,*N*′-tetraacetic acid; a fluorescent calcium chelator, named from the indolyl moiety, that can be used as an indicator of Ca^{2+} concentration; it has a large shift in fluorescence emission, from 480 to 400 nm, on binding Ca^{2+}.

indole 2,3-benzopyrrole; in plants and microorganisms, a precursor in the biosynthesis of tryptophan. In animals it is formed by the degradation of tryptophan by bacteria in the intestinal tract.



indoleacetate *abbr*.: IAA; the anion of indole-3-acetic acid. Formed from L-tryptophan, it is a plant hormone, and the main **auxin** of higher plants.

indoleacetonitrile *abbr*.: IAN; an **auxin**, second in abundance to indoleacetate.

indole-3-glycerol-phosphate synthase *see* ***trp*** **genes**.

indole test a test used for the identification of certain microorganisms, e.g. members of the Enterobacteriaceae. It determines the ability of the organism to produce indole from tryptophan.

indolicidin a bactericidal and fungicidal 13-residue peptide amide from the cytoplasmic granules of bovine neutrophils. It contains five tryptophan residues, hence its name. Some therapeutic success has been achieved in animals against the fungus, *Aspergillus fumigatus*, using liposomally encapsulated indolicidin, indicating that neutrophil-derived antimicrobial peptides may have therapeutic value.

indoluria the presence in (human) urine of compounds containing an indole ring.

indomethacin 1-(*p*-chlorobenzoyl)-5-methoxy-2-methylindole-3-acetic acid; an inhibitor of **prostaglandin-endoperoxide synthase**. It is useful as an anti-inflammatory drug.



INDOR *abbr. for* internuclear double resonance spectrometry.

induced enzyme *or* **inducible enzyme** any enzyme that is synthesized in a cell only in very small amounts except when induced by the presence of its substrate or a closely related compound. *Compare* **constitutive enzyme**.

induced-fit theory an explanation, first proposed by D. E. Koshland, of enzyme specificity. It holds that reaction between an enzyme and its substrate occurs only following a change in the enzyme's structure, induced by the substrate. It proposes that: (1) a precise orientation of catalytic groups is required for enzyme action; (2) the substrate may cause a change in the three-dimensional relationship of the amino-acid residues at the active site; and (3) the changes in enzyme structure will bring the catalytic groups into the proper orientation for reaction, whereas a nonsubstrate will not. *Compare* **lock-and-key model**.

inducer *(in genetics)* a molecule, generally small, that acts by binding either to an activator or to a repressor protein to stimulate gene expression.

inducible capable of being induced.

inducible enzyme *an alternative name for* **induced enzyme**.

induction 1 *see* **Jacob–Monod model**. **2** *(in physics)* any physical effect brought about (i.e. induced) in an object by the action of a field without any direct physical contact with the inducer. It may be electrostatic, magnetic, or electromagnetic. *See also* **induced enzyme**. **3** *(in genetics)* the mechanism whereby a bacteriophage in the lysogenic state is prompted to enter the lytic mode of replication. Induction occurs under adverse nutritional conditions and classically by exposure of the lysogen to ultraviolet irradiation.

induction coil a device for producing a rapid succession of large pulses of induced emf in a secondary coil from an intermittent low emf in a primary coil.

induction motor an electric motor in which an alternating current is supplied to the winding of the stator, arranged in such a manner as to produce in effect a rotating magnetic field. This in turn induces electric currents in the winding of the rotor, and interaction between these currents and the magnetic flux exerts a torque on the rotor. Induction motors are useful in situations where sparks caused by moving electric contacts are undesirable.

inductive effect *(in chemistry) symbol*: *I*; an experimentally observable effect (on reaction rates, etc.) caused by the transmission of charge through a chain of atoms by electrostatic induction. It is symbolized by $+I$ or $-I$, according to whether the group in question is left with a small positive or a small negative charge.

+ine *suffix* designating **1** an organic compound that is either an amine (including any monoamino monocarboxylic acid other than tryptophan), or a nitrogen-containing heterocycle other than one containing four or five atoms in the ring. **2** a halogen. **3** any of a group of certain inorganic binary hydrogen compounds, namely arsine, bismuthine, phosphine, and stibine; also hydrazine.

inert 1 having little or no ability to react chemically or physiologically. **2** having no inherent ability to move or resist being moved. **—inertness** *n.*

inertia 1 *(in physics)* the tendency of an object to resist changes to its state of rest or uniform motion; by analogy extended to other physical qualities that resist change. **2** the state of being inert or inactive. **—inertial** *adj.*

inertial mass *see* **mass**.

infantile Refsum disease *see* **Refsum disease**.

infantile sialic acid storage disease *abbr*.: ISSD; the fulminant form of **Salla disease** and, like it, caused by mutations in sialin.

infect 1 to cause infection in (an organism, wound, etc.), especially with pathogenic microorganisms. **2** to affect or become affected with a communicable disease.

infection 1 the invasion of a cell or organism by other (especially pathogenic) organisms. **2** the act or process of infecting; the state of being infected. **3** any agent or process that infects.

infectious 1 *(of a disease)* caused by pathogenic (micro)organisms. **2** causing or transmitting infection. **3** *(of a disease)* capable of being transmitted to another organism. **—infectiously** *adv.*; **infectiousness** *n.*

infectious mononucleosis *see* **Epstein–Barr virus**.

infectious viral nucleic acid a purified viral nucleic acid that, when it infects a host cell, causes the production of progeny viral particles.

infective **1** capable of causing infection. **2** *an alternative (less common) word for* **infectious**. **—infectively** *adv.*; **infectiveness** *or* **infectivity** *n.*

infinite having no limits in extent, magnitude, space, or time; immeasurably numerous or great. **—infiniteness** *n.*; **infinitely** *adv.*

infinite dilution a hypothetical state (of a solution) in which the solute concentration is considered to be zero and the activity coefficient unity.

infinitely thick *(of a radioactive sample)* having a thickness no less than **infinite thickness** for the particular radionuclide to be measured.

infinitely thin *(of a radioactive sample)* having a thickness no greater than **infinite thinness** for the particular radionuclide to be measured.

infinite thickness the thickness of a sample containing a particular radionuclide, especially a soft beta-emitter, beyond which, because of self-absorption, any increase results in no further increase in recordable disintegrations. Under these conditions the (radio)activity is proportional to the specific (radio)activity of the substance.

infinite thinness the thickness of a sample containing a particular radionuclide at or below which self-absorption is negligible. Under these conditions the (radio)activity is proportional to the amount of the radionuclide present.

inflammable very liable to catch fire and produce flame; flammable.

inflammation the immediate defensive reaction of vertebrate tissue to infection or to injury by chemical or physical agents. The part affected is characterized by pain, heat, redness, swelling, and loss of function; there is local vasodilatation, extravasation of plasma into the intercellular spaces, and accumulation of white blood cells and other macrophages in the injured part. Plasma enzyme systems are important sources of inflammatory mediators. These include the **complement**, **blood coagulation**, fibrinolytic, and **kinin** systems. Also active are the mediators released by mast cells, basophils, and platelets, as well as the eicosanoids generated by many cells at inflammatory sites. **—inflame** *vb.*

influenza virus any one of several orthomyxoviruses that cause respiratory disease in warm-blooded vertebrates. Influenza viruses are negative strand RNA viruses with segmented genomes comprising eight RNA molecules per virion. Influenza viruses are characterized by their antigenic properties. The matrix serotypes are referred to as A, B, and C. Influenza B and C types are only found in the human species whereas type A viruses infect serveral species and some can cross a species barrier. They are conventionally sub-typed according to their haemagglutinin (H) and neuraminidase (N) antigens. A complete designation is, for example, A.Hong Kong/1/68 (H3N2) meaning it is a type A, isolated in Hong Kong, was the first such virus isolated there in 1968, and is H3N2.

informatics **1** the science concerned with the structure and properties of scientific information, its theory, history, methodology, and organization. **2** the application of computational and statistical techniques to the management and analysis of information. For example, bioinformatics relates to the management and analysis of biological information; medical informatics to medical information; neuroinformatics to neurobiological data; and chemoinformatics to chemical entities. **—informatical** *adj.*; **informatician** *n.*

informatin *see* **informofer**.

information **1** communicated or communicable factual knowledge; data; news. **2** **genetic information**. **3** *(in computing)* the results obtained by processing raw data according to programmed instructions.

informational **1** of, pertaining to, giving, or carrying information. **2** *(in biochemistry)* describing any biological macromolecule that contains or transmits **genetic information** in the form of specific sequences of nucleotides or amino acids.

information extraction *abbr.*: IE; (*in text mining*) a method for identifying specific query terms (words or phrases), and the relationships between them, within a passage of text, a complete document, or within sets of retrieved documents. By recognizing explicit concepts and relationships, and relating specific parts of a document to the subject of interest, IE sheds light on the semantic structure of the text. *Compare* **information retrieval**.

information retrieval *abbr.*: IR; (*in text mining*) a method for identifying from a large set of documents those that relate to user-specified query terms (the method does not identify the query terms within those texts). *Compare* **information extraction**.

information retrieval software software that retrieves information relevant to a user query from unstructured text, such as occurs in the literature or in databases. For example, PubMed is a Web-based information retrieval service for NCBI's MEDLINE bibliographic database; Entrez retrieves information from an integrated set of NCBI databases; SRS (Sequence Retrieval System) is a commercial product that can be customized to search any user-defined **flat-file** databases.

information theory the quantitative theory of the coding and transmission of signals and information.

informofer a specific, 30S particle consisting of the protein **informatin**. Informofers are present in the cell nucleus, tightly packed along molecules of **heterogeneous nuclear RNA**.

informosome a cytoplasmic mRNA-carrying ribonucleoprotein particle of relatively low buoyant density. Informosomes are believed to function in the protection of mRNA from nuclease attack and in the transport of mRNA from the nucleus to the cytoplasm.

infra+ *prefix* denoting below, beneath, coming after, within. *Compare* **sub+**, **supra+**, **ultra+** (def. 1).

infradian describing any biological activity that occurs, or varies cyclically, more often than once every 24 hours. *Compare* **circadian**, **ultradian**.

infranatant **1** lying below. **2** a solid or liquid lying below a **supernatant** liquid. *Compare* **subnatant**.

infrared of, pertaining to, or being **infrared radiation**.

infrared dichroism the **dichroism** of polarized infrared radiation. It is used in studies of polypeptide structure.

infrared radiation *abbr.*: IR *or* i.r.; electromagnetic radiation of wavelengths in the range 730 nm to 1 mm (frequencies 300 GHz to 410 THz). This range lies between those of visible light and microwaves.

infrared spectrophotometer any instrument for **infrared spectrophotometry**.

infrared spectrophotometry the measurement of the absorption or emission of infrared radiation at particular wavelengths or frequencies. *See* **infrared spectrum**.

infrared spectrum any absorption spectrum or emission spectrum of infrared radiation. It includes photons that are absorbed or emitted during vibrational and rotational transitions in a molecule. Infrared spectra are widely used in organic chemistry to identify particular groups of atoms by their characteristic vibrational frequencies.

infuse **1** to introduce gradually, as of a solution into a vein or body cavity. **2** to make an **infusion** (def. 2).

infusion **1** the process of infusing. **2** an extract, e.g. of meat or leaves, obtained by soaking in water.

ingest to take material, e.g. food or liquid, into a cell or organism. **—ingestible** *adj.*; **ingestion** *n.*; **ingestive** *adj.*

inhibin either of the glycoproteins inhibin or **activin** of the transforming growth factor β family and secreted by the gonads. They participate in differentiation and growth of diverse cell types. Inhibin inhibits secretion of **follicle-stimulating hormone** by the pituitary, whereas activin stimulates its secretion. Inhibin is present in seminal plasma and follicular fluid. It consists of two subunits crosslinked by disulfide bridges. Inhibin A is a dimer of α and β_A subunits, and inhibin B is a dimer of α and β_B subunits. The β_A and β_B subunits are also constituents of activin. Their precursors are isoforms derived from the same gene. Inhibin is normally secreted throughout the menstrual cycle and during pregnancy, but not after the menopause. Plasma levels increase in certain ovarian cancers.

inhibit **1** to restrain or hinder. **2** to stop, prevent, or reduce the rate of (some process, e.g. the growth or functioning of an organism or part of an organism, or a chemical or enzymic reaction).

inhibition constant *symbol*: K_i; the equilibrium (dissociation) constant for the reaction: $\mathrm{EI} \rightleftharpoons \mathrm{E} + \mathrm{I}$. It is given by $K_i = [\mathrm{E}][\mathrm{I}]/[\mathrm{EI}]$, where E is the enzyme and I the inhibitor, the square brackets indicating concentrations.

inhibition index an inverse measure of the potency of an antimetabolite. It is the ratio of the concentration of antimetabolite that is required to inhibit the biological effect of unit concentration of corresponding metabolite.

inhibitor **1** any agent that inhibits. **2** *(in biochemistry)* any substance that inhibits an enzymic reaction. *See also* **competitive inhibition**, **noncompetitive inhibition**, **uncompetitive inhibition**.

inhibitor of apoptosis protein *see* **IAP**.

inhibitor of differentiation *see* **Id**.

initial velocity *or* **initial steady-state rate** *symbol*: v_o *or* v; the reaction velocity in the earliest stage of an enzyme-catalysed reaction. It is given by the tangent at the origin to the curve of reaction velocity as a function of time. In practice it is often measured over the period when the initial substrate concentration has diminished by <5%.

initiation **1** the formation of **initiation complex(es)** at the start of ribosome-mediated translation of mRNA into polypeptide. **2** the first stage in carcinogenesis, in which a normal cell is converted to a precancerous one. **3** the first step in a chain reaction. **—initiate** *vb.*; **initiatory** *adj.*

initiation codon *or* **initiator codon** the codon AUG (or, sometimes in prokaryotes, GUG) that binds *N*-formylmethionyl-$\text{tRNA}_\text{f}^\text{Met}$ in prokaryotes or initiator methionyl-$\text{tRNA}_\text{f}^\text{Met}$ in eukaryotes, and serves as a signal for the start of polypeptide synthesis at the ribosome.

initiation complex any of the complexes formed at the start of ribosome-mediated translation of mRNA into polypeptide. They contain mRNA, initiation factors, initiator fMet-tRNA_f or Met-$\text{tRNA}_\text{f}^\text{Met}$, one or two ribosomal subunits, and sometimes GTP. *See* **initiation factor**.

initiation factor *abbr.*: IF (in prokaryotes) *or* eIF (in eukaryotes); any soluble protein that functions in the initiation of ribosome-mediated translation of mRNA into polypeptide. *Escherichia coli* has three principal initiation factors, each consisting of a single polypeptide chain. **IF-1** is a basic protein (9 kDa) that is a stimulator of IF-2 and IF-3. There are two forms of **IF-2**: IF-2a, which is acidic, unstable, and of 115 kDa; and IF-2b, formed by limited proteolysis of IF-2a. It is a GTP-binding protein, protects formylmethionyl-$\text{tRNA}_\text{f}^\text{Met}$ from spontaneous hydrolysis, and promotes its binding to the 30S ribosomal subunits; it is also involved, with hydrolysis of GTP, in the formation of the 70S ribosomal complex. By using alternative initiation codons in the same reading frame, the eIF-2b gene is translated into three isozymes, α, β, and β′, having different N termini. **IF-3** is a basic, stable protein of 22 kDa. It binds to the 30S ribosomal subunit and shifts the equilibrium between 70S ribosomes and their subunits in favour of the free subunits, thus enhancing the availability of 30S subunits. It is also a translational repressor of its own gene. IF-1, IF-2, and IF-3 bind cooperatively to a 30S ribosomal subunit to form a 30S•IF-1•IF-2•IF-3 particle in which the three IFs are bound contiguously near the 3′ end of 16S RNA in a 30S ribosomal subunit. This particle subsequently binds mRNA at a site that includes the initiation codon AUG (or GUG), initiator fMet-$\text{tRNA}_\text{f}^\text{Met}$, and GTP with concomitant release of IF-3 to form a 30S initiation complex, 30S•IF-1•IF-2•mRNA•GTP•fMet-$\text{tRNA}_\text{f}^\text{Met}$. Joining of a 50S ribosomal subunit with concomitant release of IF-1, IF-2, GDP, and P_i forms a 70S initiation complex, mRNA•70S• fMet-$\text{tRNA}_\text{f}^\text{Met}$.

Eukaryotes have more initiation factors. Many have been characterized in lysates of rabbit reticulocytes. They include: eIF-1, a monomer of 15 kDa; eIF-2, a heterotrimer of 150 kDa; eIF-3, a nonamer of 700 kDa; eIF-4A, a monomer of 49 kDa; eIF-4B, a monomer of 80 kDa; eIF-4C, a monomer of 17.5 kDa; eIF-4D, a monomer of 16.5 kDa; eIF-5, a monomer of 190 kDa; Co.eIF-2, a monomer of 22 kDa; and cap-binding protein, a monomer of 24 kDa. eIF-2, initiator Met-$\text{tRNA}_\text{f}^\text{Met}$, and GTP form a ternary complex; eIF-3 promotes ribosomal dissociation and stabilizes binding of ternary complex to a 40S ribosomal subunit to form the complex 40S•eIF-2•eIF-3•Met-$\text{tRNA}_\text{f}^\text{Met}$•GTP. Then eIF-1, eIF-4A, eIF-4B, eIF-4C, and cap-binding protein promote binding of mRNA and ATP-dependent formation of a **40S initiation complex**, 40S•eIF-2•eIF-3•Met-$\text{tRNA}_\text{f}^\text{Met}$•mRNA. Factor eIF-5 is required for formation of an **80S initiation complex**, 80S•Met-$\text{tRNA}_\text{f}^\text{Met}$•mRNA, from a 40S complex, together with hydrolysis of the bound GTP and release of initiation factors. Co.eIF-2 stimulates ternary complex formation.

initiation signal **1** any of the purine-rich regions of mRNA on the 5′ side of the initiation codon that serve to distinguish the latter from other similar codons. **2** any of the promoter regions of DNA on the 5′ side of the start of transcription to form mRNA.

initiation switch *see* **ISWI**.

initiator **1** a gene product that interacts specifically with the replicator site on a replicon resulting in the initiation of a new round of DNA replication. **2** a starting point for either nucleic-acid transcription or translation. **3** a carcinogen that initiates the first stage of carcinogenesis. **4** any compound that, when added to monomer, initiates a polymerization reaction.

initiator codon *see* **initiation codon**.

initiator transfer RNA *abbr.*: $\text{tRNA}_\text{f}^\text{Met}$; any of the tRNA molecules that, when aminoacylated, specifically binds to an initiation codon (usually AUG) in mRNA at the start of ribosome-mediated translation of mRNA into polypeptide. In prokaryotes it is *N*-formylmethionyl-$\text{tRNA}_\text{f}^\text{Met}$, and in eukaryotes it is methionyl-$\text{tRNA}_\text{f}^\text{Met}$; neither is able to promote the insertion of methionine residues at internal sites.

INK4 *or* **CDI with 4 ankyrin repeats** any of four structurally related proteins (i.e. p15, p16, p18, and p19), each of which contains four **ankyrin** repeats. Each is a specific inhibitor of Cdk4 and Cdk6. Somatic inactivating mutations in the gene at 9p21 for CDIp16 occur in sporadic melanomas, whereas germline mutations increase the risk of melanoma and possibly other neoplasms.

innate being an essential characteristic of an organism or thing; inborn.

innate immunity an immune response in both vertebrates and invertebrates to a **pathogen** that involves the pre-existing defences of the body – the **innate immune system** – such as barriers formed by skin and mucosa, antimicrobial molecules and **phagocytes**. Such a response is not specific for the pathogen. The agents are either small proteins or peptides many of which have been detected in insects, which lack the immune system of higher animals. Examples are **cecropin** and **attracin** of the moth *Cecropia*, which kill *E.coli*. **Drosocin** kills fungi present in the fruit fly. Mammals make similar peptides called **defensins**.

innervation the nerve supply to an organ or part.

Ino *symbol for* a residue of the ribonucleoside inosine (alternative to I).

inoculate **1** to introduce cells, microorganisms, or viruses into or onto a culture medium. **2** to introduce causative agents of disease (alive, dead, or attenuated) into an animal or person for the purpose of immunization. **—inoculation, inoculator** *n.*; **inoculative** *adj.*

inoculum (*pl.* **inocula**) a quantity or suspension of cells, microorganisms, or viruses used to start a new culture or to infect another culture; something used to inoculate.

Ino-3′,5′-*P* *symbol for* inosine 3′,5′-phosphate.

Ino5′*P* *symbol for* inosine 5′-phosphate.

Ino5′*PP* *symbol for* inosine 5′-diphosphate (alternative to ppI).

Ino5′*PPP* *symbol for* inosine 5′-triphosphate (alternative to pppI).

inorganic not having the characteristics of living organisms; not **organic**.

inorganic biochemistry the branch of biochemistry concerned with the role of inorganic substances in biochemical systems. *Compare* **bioinorganic chemistry**.

inorganic chemistry the branch of chemistry dealing with the elements and all their compounds other than ones containing carbon, except for carbon itself and some simple compounds of carbon, e.g. oxides, sulfides, and cyanides.

inorganic diphosphate *symbol*: PP_i; any of the anions formed from diphosphoric acid, $(HO)_2PO–O–PO(OH)_2$, or any mixture of the acid and its anions. The older term **inorganic pyrophosphate** is less preferable.

inorganic phosphate *or* **inorganic orthophosphate** *symbol*: P_i; any of the anions formed from [ortho]phosphoric acid, $PO(OH)_3$, or any mixture of the acid and its anions.

inorganic pyrophosphatase an enzyme, EC 3.6.1.1, often less precisely termed pyrophosphatase; *systematic name*: pyrophosphate phosphohydrolase. It catalyses the hydrolysis of pyrophosphate to two molecules of orthophosphate.

inorganic pyrophosphate *a less preferred term for* **inorganic diphosphate**.

iNOS *see* **nitric-oxide synthase**.

inosinate **1** either the mono- and/or the di-anion of **inosinic acid**. **2** any mixture of the acid and its anions. **3** any salt or ester of inosinic acid.

inosine *symbol*: I *or* Ino; hypoxanthosine; hypoxanthine riboside; 9-*β*-D-ribofuranosylhypoxanthine; a nucleoside found free, especially in meat, sugar beet, and yeast, and in the anticodons of some transfer RNAs. It may be formed by the action of adenosine deaminase (EC 3.5.4.4) in the first step of the breakdown of adenosine to uric acid, and it occurs as an intermediate in the recycling of adenosine and inosine 5′-phosphate by **salvage pathways**.



inosine 3′,5′-(cyclic)phosphate *or* **inosine 3′,5′-cyclophosphate** *see* **inosine 3′,5′-phosphate**.

inosine 5′-diphosphate *symbol*: Ino5′*PP* *or* ppI; *recommended name for* inosine diphosphate (*abbr.*: IDP), 5′-diphosphoinosine, 5′-inosinyl phosphate, inosine 5′-(trihydrogen diphosphate). It is an intermediate in the formation of inosine 5′-triphosphate from inosine 5′-phosphate.

inosine monophosphate *abbr.*: IMP; *an alternative name for* any **inosine phosphate**, but particularly for **inosine 5′-phosphate**, especially when its distinction from inosine (5′-)diphosphate and inosine (5′-)triphosphate requires emphasis.

inosine-5′-monophosphate dehydrogenase *see* **IMP dehydrogenase**.

inosine phosphate inosine monophosphate (*abbr.*: IMP); any phosphoric monoester or diester of inosine. Of the three possible monoesters – the 2′-phosphate, the 3′-phosphate, and the 5′-phosphate – only **inosine 5′-phosphate** is of any importance (the locant being omitted if no ambiguity may arise). The only diester of significance is **inosine 3′,5′-phosphate**.

inosine 3′,5′-phosphate *symbol*: Ino-3′,5′-*P*; *the recommended name for* cyclic inosine 3′,5′-monophosphate (*abbr.*: 3′,5′-cyclic IMP *or* cyclic IMP *or* cIMP), inosine 3′,5′-cyclophosphate, inosine 3′,5′-(cyclic)phosphate; a monophosphoric diester of inosine. It is a cyclic nucleotide similar in structure and metabolism to **adenosine 3′,5′-phosphate** (i.e. cyclic AMP) but only rarely encountered.

inosine 5′-phosphate *or* **5′-inosinic acid** *or* **5′-phosphoinosine** *or* **5′-*O*-phosphonoinosine** *symbol*: Ino5′*P*; *alternative recommended names for* inosine monophosphate (*abbr.*: IMP), inosine 5′-(dihydrogen phosphate), hypoxanthine ribonucleotide. (The locant is commonly omitted if there is no ambiguity as to the position of phosphorylation.) It is the initial biosynthetic product containing an intact purine nucleus, its immediate precursor being 4-carbamoyl-5-formamidoimidazole riboside 5′-phosphate. Hence IMP is a key intermediate in the biosynthesis of all other purine nucleotides and in the formation of purine nucleosides and free purines. In addition, resynthesis of IMP from hypoxanthine can be effected via a **salvage pathway** by the action of hypoxanthine phosphoribosyltransferase (EC 2.4.2.8) (*see* **phosphoribosyltransferase**).

inosine 5′-triphosphate *symbol*: Ino5′*PPP* *or* pppI; *the recommended name for* inosine triphosphate (*abbr.*: ITP), 5′-triphosphoinosine, 5′-inosinyl diphosphate, inosine 5′-(tetrahydrogen triphosphate). ITP can substitute for adenosine 5′-triphosphate or guanosine 5′-triphosphate in certain enzymic reactions. It is formed from inosine 5′-diphosphate by transfer of the terminal phosphoric residue from adenosine 5′-triphosphate through the action of nucleoside-diphosphate kinase (EC 2.7.4.6).

inosinic acid *the trivial name for* any phosphoric monoester of inosine. The position of the phosphoric residue on the ribose moiety of a given ester may be specified by a prefixed locant (*see* **inosine phosphate**). However, 5′-inosinic acid is the ester commonly denoted, its locant usually being omitted if no ambiguity may arise. 5′-Inosinic acid is also an alternative recommended name for **inosine 5′-phosphate**.

inosinyl the inosine [mono]phospho group; the acyl group derived from **inosinic acid**.

inositol **1** *symbol*: Ins; *the common name for* the cyclitol *myo*-inositol (*formerly called meso*-inositol *or* *i*-inositol *or* bios I *or* muscle sugar); 1,2,3,5/4,6-cyclohexanehexol; a growth factor for some animals and microorganisms, widely distributed in nature. Inositol occurs free, as various phosphates, or as a constituent of certain phospholipids (*see* **phosphatidylinositol**); in plants it also occurs as its hexaphosphate phytate. Note: whereas *myo*-inositol itself is achiral, its phosphorylated derivatives are chiral and the numbering of their carbon atoms can be confusing. For a proposed solution of the problem, *see* **Agranoff's turtle**. **2** *generic name for* any member of a subclass of cyclitols comprising the nine possible 1,2,3,4,5,6-cyclohexanehexols, of which inositol (def. 1) is the most prevalent and most important.



inositol-1,3-bisphosphate 3-phosphatase EC 3.1.3.65; an enzyme that hydrolyses D-*myo*-inositol 1,3-bisphosphate to D-*myo*-inositol 1-monophosphate and orthophosphate.

inositol-1,4-bisphosphate 1-phosphatase EC 3.1.3.57; *systematic name*: D-*myo*-inositol-1,4-bisphosphate 1-phosphohydrolase; *other name*: inositol polyphosphate 1-phosphatase; an enzyme that hydrolyses D-*myo*-inositol 1,4-bisphosphate to D-*myo*-inositol 4-phosphate and orthophosphate.

inositol glycan any compound that consists of inositol linked to a glycan. The best known is the one that forms part of the membrane anchor of PIG-tailed proteins. It is rapidly released by insulin-sensitive cells *in vitro* in response to insulin and by the action of phosphoinositol-specific phospholipase C. Its physiological role is unclear.

inositol phosphate any phosphoric ester of an inositol, but normally referring to the esters of *myo*-inositol (*abbr.*: Ins). Of particular interest are those formed by the hydrolysis of membrane phosphoinositides following activation of phosphoinositide-specific phospholipase C (*see* **phospholipase**). The generalized abbreviation for phosphorylated *myo*-inositols follows the convention Ins(numbers of the carbons bearing phosphorylated hydroxyls)P_x, where P_x indicates the number of phosphates. They include inositol 1,4,5-trisphosphate (*abbr.*: Ins(1,4,5)P_3), formed by phospholipase C action on phosphatidylinositol 4,5-bisphosphate. Ins(1,4,5)P_3 is important in the **phosphatidylinositol cycle**. It can be phosphorylated to Ins(1,3,4,5)P_4, which is also physiologically active in calcium metabolism. Other inositol phosphates are intermediates in the degradation of Ins(1,4,5)P_3 and Ins(1,3,4,5)P_4. Ins(1,4,5)P_3 is hydrolysed to Ins(1,4)P_2, which is hydrolysed to Ins(4)P and thence to Ins. Ins(1,3,4,5)P_4 is hydrolysed to Ins(1,3,4)P_3, which is hydrolysed to either Ins(1,3)P_2 or Ins(3,4)P_2, these being hydrolysed to Ins(1)P or Ins(3)P respectively and thence to Ins.

inositol-1,3,4,5-tetrakisphosphate 3-phosphatase EC 3.1.3.62; an enzyme that hydrolyses D-*myo*-inositol 1,3,4,5-tetrakisphosphate to D-*myo*-inositol 1,4,5-trisphosphate and orthophosphate.

inositol-1,4,5-trisphosphate 1-phosphatase EC 3.1.3.61; an enzyme that hydrolyses D-*myo*-inositol 1,4,5-trisphosphate to D-*myo*-inositol 4,5-bisphosphate and orthophosphate.

inositol-1,4,5-trisphosphate 5-phosphatase EC 3.1.3.56; *systematic name*: D-*myo*-inositol-1,4,5-trisphosphate 5-phosphohydrolase; *other names*: inositol trisphosphate phosphomonoesterase; inositol polyphosphate 5-phosphatase; 5PTase; an enzyme that hydrolyses D-*myo*-inositol 1,4,5-trisphosphate to D-*myo*-inositol 1,4-bisphosphate and orthophosphate. The enzyme has two types; type I (but not type II) hydrolyses inositol 1,3,4,5-tetrakisphosphate to inositol 1,3,4-trisphosphate; neither enzyme acts on the latter or on inositol 1,4-bisphosphate.

inositol trisphosphate receptor *see* **IP_3 receptor**.

inosyl any chemical group formed by the loss of a 2′-, 3′-, or 5′-hydroxyl group from the ribose moiety of **inosine**.

inotropic influencing contractility of muscles, especially cardiac muscle.

Ins *symbol for* a residue of the cyclitol 1-D-*myo*-inositol (*see* **inositol** (def. 1)).

Inscuteable a protein of *Drosophila* that is involved in differentiation of a neuroblast into a ganglion mother cell. It is present in the apical cortical crescent and is essential for correct segregation of the basal cortical crescent from the former into the latter cell.

INSD *abbr. for* International Nucleotide Sequence Database; *see* **composite database**.

insect any small air-breathing arthropod of the class Insecta, typically having a segmented body with an external, chitinous covering, three pairs of legs, and in most groups two pairs of wings.

insecticide any substance or agent that kills insects. **—insecticidal** *adj.*

(insect) moulting hormone *(or US)* **(insect) molting hormone** *a common name for* **ecdysterone**.

insectorubin any red or red-brown eye pigment of insects derived from oxidation products of tryptophan. *See also* **ommin**.

insectoverdin any green pigment of insects formed of mixtures of carotenoids and biliverdin.

insert *(in genetics)* a fragment of DNA that has been linked into a cloning vector. The term can also be used as a modifier as, e.g., in **insert DNA**.

insertional inactivation the inactivation of a gene in a plasmid or other cloning vector by insertion of foreign DNA at an endonuclease site. If the gene is *lacZ* its inactivation can be detected by the inability of bacterial colonies containing the recombinant plasmid to hydrolyse **X-gal**. Such colonies remain white whereas plasmids religated without an insert give blue colonies.

insertional mutagenesis the induction of a mutation by the insertion of DNA into a gene using recombinant DNA techniques. One approach, known as restriction enzyme-mediated integration (REMI), utilizes a plasmid that is cut with a restriction enzyme. Then the cut plasmid, together with the restriction enzyme, is introduced into cells (e.g. *Dictyostelium*) by electroporation. The restriction enzyme cuts the genomic DNA at sites into which the plasmid can integrate through its **sticky ends**. If the plasmid contains a suitable marker, transformants can be isolated. The gene affected can be identified because it is effectively tagged with the plasmid. If the plasmid also contains an additional marker conferring drug resistance, the gene from the transformant can be readily cloned.

insertion mutation any mutation caused by insertion of an extranumerary nucleotide residue between two successive nucleotide residues in a DNA molecule.

insertion sequence *abbr.*: IS; *see* **signal sequence**, **transposon**.

insertion vector *(in recombinant DNA technology)* any **vector** (def. 3) that has been cut with a restriction enzyme having a single target site in the centre of the vector, so that two 'arms' are generated between which foreign DNA may be inserted.

insertosome an 800–1400 bp stretch of DNA that can insert itself randomly into the chromosome of *Escherichia coli*, thereby causing polar mutations analogous to those caused by phage Mu-1.

inside-out vesicle any vesicle formed from disrupted cell or other membranes that has sealed up so that the face of the membrane that was originally on the outside is now on the inside.

in silico *Latin (of any biological process, reaction, or experiment)* made to occur by means of a computer (e.g. a simulation in the e-cell). Literally, it means 'in silicon'. *Compare* ***in vitro***, ***in vivo***.

***in silico* screening** *an alternative name for* **combinatorial chemistry**.

in situ *Latin* in the normal, natural, original, or appropriate position.

in situ* hybridization** *or* **hybridization *in situ a technique that uses labelled nucleic acid probes to reveal the location of genes on chromosomes, or of specific mRNA molecules within tissue sections, small organisms, or embryos. *See* **fluorescence *in situ* hybridization**, **hybridization analysis**.

insolubilize *or* **insolubilise** to render **insoluble** (def. 1), especially by coupling covalently to an insoluble matrix. **—insolubilization** *or* **insolubilisation** *n.*

insoluble 1 incapable of being dissolved (in water unless otherwise specified); of extremely low solubility. **2** incapable of being solved; having no solution.

Ins(3,4)P_2 *symbol for* 1D-*myo*-inositol 3,4-bisphosphate.

Ins(1,3,4)P_3 *symbol for* 1D-*myo*-inositol 1,3,4-trisphosphate.

Ins(1,4,5)P_3 *symbol for* 1D-*myo*-inositol 1,4,5-trisphosphate.

Ins(1,3,4,5)P_4 *symbol for* 1D-*myo*-inositol 1,3,4,5-tetrakisphosphate.

instructive theory of immunity a theory ascribing to an antigen the function in immunity of instructing or directing uncommitted cells to form new antibodies that reflect the nature of the antigen itself. *Compare* **selective theory of immunity**.

insulate to prevent, or reduce, the passage of electricity, heat, or sound to or from (something) by interposition of a (relevant) nonconducting material.

insulaxin a synthetic porcine insulin that instead of the A chain Ile^{10}, and B chain Ser^9, His^{10}, and Glu^{13} contains, respectively, Gly, Arg, Glu, and Arg, as in porcine **relaxin**. Unlike the native insulin, it binds to the porcine relaxin receptor.

insulin *or (formerly)* **insuline** the hypoglycemic, antidiabetic, and anabolic polypeptide hormone of the endocrine portion of the mammalian pancreas or of homologous organs of lower vertebrates. In mammals, it is elaborated in the B cells of the islets of Langerhans and stored within them in the B granules prior to release by exocytosis. Insulin is a slightly acidic protein that readily aggregates to form dimers, hexamers, and higher multimers. It is very poorly soluble in aqueous media around its isoelectric point (pH ≈ 5.4), especially in the presence of certain divalent metal ions, typically Zn^{2+}, with which it can form crystals, usually containing two or four metal ions per insulin hexamer, depending on conditions. It does, however, dissolve without denaturation in organic solvents in an acid medium, a property that can be exploited in its isolation. The monomer of insulin is one of the smallest known proteins, with M_r values such as 5733 (bovine), 5777 (porcine), or 5807 (human). Bovine insulin was the first protein to have its primary sequence determined, by British biochemist Frederick Sanger (1918–), in 1955. The sequences of a large number of insulins are now known, all of which consist of two polypeptide chains, commonly termed the **A chain** and the **B chain**, with three disulfide bridges formed between half-cystine residues; two of these bridges are interchain, forming A7–B7 and A19–B20 links, and the third is intrachain, linking positions A6 and A11 to form a heterodetic ring in the A chain. The numbers of amino-acid residues vary slightly with the species of origin, commonly being 21 and 30 in the A and B chains, respectively; six amide groups are present per molecule of the monomer if insulin is carefully isolated. The three-dimensional structure is known: chains A and B have two motifs each. Insulin is structurally related to **relaxin** and **insulin-like growth factor**. Insulin is biosynthesized by post-translational modification of its single-chain precursor **preproinsulin**. In preproinsulin, residues 1–24 are the signal sequence. When this is removed, proinsulin is formed. In the Golgi apparatus, prohormone convertases PC2 and PC3 cleave proinsulin on the carboxyl side of a pair of basic amino-acid residues (Arg^{55}-Arg^{56} and Lys^{88}-Arg^{89}). This excises the C peptide (residues 57–87), leaving the A and B chains (two Arg residues (55 and 56) must first be cleaved from the B chain by carboxypeptidase H for the mature B chain to be formed). Residues 55–87 are known as the connecting peptide. Human insulin consists of 110 amino acids; the A chain is derived from residues 90–110, and the B chain from residues 25–54.

Insulin stimulates glucose uptake by muscle and adipose tissue, and promotes glycogenesis, lipogenesis, and synthesis of protein and nucleic acid. Deficiencies in the secretion or action of insulin in humans result in the overproduction and increased urinary excretion of glucose (*see* **glucose-tolerance test**, **diabetes mellitus**); continuing therapeutic administration of insulin is necessary in type I (insulin-dependent) diabetes mellitus. Commercial insulin for therapeutic use is extracted mostly from bovine or porcine pancreas; human insulin is now also being made by recombinant DNA technology. The international unit for insulin is defined as the activity contained in 0.041 67 mg of the Fourth International Standard for Insulin, Bovine and Porcine, for Bioassay (which is defined as crystalline zinc insulin derived from a mixture of 52% bovine insulin and 48% porcine insulin).

insulinase EC 3.4.99.45; *other names*: insulin-degrading enzyme; insulin protease; insulysin. An enzyme that progressively cleaves a number of peptide bonds in insulin, but only Arg^{17}-|-Arg^{18} in glucagon and some other unrelated hormones and cytokines. It is a zinc thioendopeptidase of the inverzincin family and is widely expressed in mammalian tissues (including some that are not insulin-sensitive). It shows little sequence homology with classical metallo or cysteine proteases.

insulin-dependent diabetes mellitus *abbr.*: IDDM; *see* **diabetes mellitus**.

insulin-like growth factor *abbr.*: IGF; any member of a group of polypeptides that are structurally homologous to **insulin** and share many of its biological activities but are immunologically distinct from it; they are mitogens of the insulin/relaxin family. They include substances now named insulin-like growth factor-I (IGF-I), which is a monomer of 70 amino acids, and insulin-like growth factor-II (IGF-II), which is a monomer of 67 amino acids; together these were formerly known as **nonsuppressible insulin-like activity** (NSILA). The insulin-like growth factors also include **somatomedin** C, which is IGF-I, and possibly also somatomedins A_1 and A_2, and **multiplication-stimulating activity**. They appear to be more potent than insulin as growth-promoting factors but less potent in stimulating glucose utilization. Brain IGF is a truncated form of IGF-I, in which the N-terminal tripeptide sequence is lacking. *See also* **insulin-related growth factor**, **somatomedin**.

insulin-like growth factor binding protein *abbr.*: IGFBP; any of several proteins that bind insulin-like growth factors (IGFs), and are found in serum, amniotic, and other body fluids, and in conditioned media from a variety of cell types. They are believed to prolong the half-life, and regulate the endocrine effects, of IGFs. Six IGFBPs (IGFBP-1 to -6) have been identified in humans, their complementary DNA having been cloned and sequenced. IGFBP-1 was originally identified as a placental protein, placental protein-12 (PP-12) and as α-1 pregnancy-associated globulin; it is a non-glycosylated protein, M_r 25 000; IGFBP-2 has been identified in human and rat central nervous systems; it is a non-glycosylated protein, M_r 31 000. IGFBP-1 and IGFBP-2 both have the RGD motif, a recognition site for **integrins**. IGFBP-3 is the principal IGFBP in human serum; it is a glycoprotein, M_r 28 500, and circulates as a complex with IGF peptide (γ subunit). For IGFBP-5, *see* **skeletal growth factor**.

insulin-like growth factor receptor an integral membrane protein that binds and mediates the effects of **insulin-like growth factor** (IGF). **IGF-I receptor** is a glycoprotein of composition $\alpha_2\beta_2$, the subunits being linked by disulfide bonds. It has an extracellular ligand-binding domain and a cytoplasmic protein tyrosine kinase domain. It is widely expressed in embryonic but not in adult tissues. **IGF-II receptor** is the cation-independent **mannose-6-phosphate receptor**. It mediates endocytosis and degradation of excess IGFII. The insulin receptor is the main receptor for IGFII.

insulinogenesis the formation of **insulin**.

insulinogenic resulting from the administration of **insulin**.

insulinoma any neoplasm originating in the B cells of the pancreatic islets (or sometimes from nonislet tissue), that autonomously secretes insulin and/or biosynthetic precursors of insulin. Such lesions are frequently recognized by their metabolic consequences.

insulinotropic stimulating **insulin** secretion.

insulinotropic effect *see* **gastric inhibitory peptide**.

insulinotropin a peptide containing residues 7–37 of glucagon-like peptide I, present with glucagon in preproglucagon. It is a potent stimulator of insulin release from the perfused rat pancreas. *See* **glucagon-like insulinotropic peptide**.

insulin receptor a type I membrane protein with tyrosine kinase (EC 2.7.1.112) activity. The protein is derived from a precursor; after being transported from the endoplasmic reticulum to the Golgi apparatus, the single glycosylated precursor is further glycosylated and then cleaved to α and β chains. In the plasma membrane the receptor is a disulfide-bonded heterotetramer, $\alpha_2\beta_2$; the α chains are entirely extracellular, while each β chain has one transmembrane domain. The ligand binds to the α-subunit extracellular domain and the kinase is associated with the β-subunit intracellular domain; it is partly regulated by autophosphorylation. Associated diseases include various forms of insulin resistance, including type 2 **diabetes mellitus** and **leprechaunism**. The human precursor protein consists of 1382 amino acids; amino acids 28–762 form the α subunit, while 763–1382 form the β subunit.

insulin receptor substrate *abbr.*: IRS; any of four proteins (IRS-1, -2, -3, and -4) that bind the activated tyrosine kinase domain of the insulin receptor and become phosphorylated by it. They share certain structural features: in the N-terminal region, a **plekstrin** homology region (≈100 residues that bind phosphatidylinositides) and a phosphotyrosine binding region (also ≈100 residues); and in the C-terminal region multiple tyrosine phosphorylation sites. All contain binding sites for SH2 domains in other proteins. Two polymorphisms in IRS-1 (1242 residues) are associated with a subset of diabetes mellitus type 2 patients. Mouse knockouts of IRS-1 and IRS-2 develop insulin resistance.

insulin-related growth factor *(sometimes)* any vertebrate and invertebrate protein or polypeptide hormone or growth factor (including **relaxin**, **nerve growth factor**, **insulin-like growth factors**, silkworm prothoracicotropic hormone, and possibly others) that shares with insulin certain features of primary and three-dimensional structure and may also display some similarities to insulin as a regulator of growth and/or metabolism.

insulin resistance a decreased ability of insulin to produce its biological effects across a wide range of concentrations. It is usually associated with hyperinsulinemia and is promoted by obesity, a sedentary lifestyle, hyperlipidemia, hypertension, and increasing age. In the majority of cases its molecular basis is largely unknown. It is usually reversed by exercise, weight loss, and diet. *See* **hyperinsulinemia syndrome**.

insulin-tolerance test a sensitive and accurate test of the integrity of the hypothalamic–pituitary–adrenal axis and its ability to respond to stress, and also of somatotropin responsiveness. The test is performed after an overnight fast with measurement of plasma cortisol, glucose, and somatotropin levels before and periodically after intravenous administration of insulin. The hypoglycemia induced by insulin elicits a potent stress response via the central nervous system, stimulating the release of **corticotropin releasing hormone** and consequently, of **corticotropin**.

Int the product of phage gene *int*, involved in the integration of phage DNA into host DNA during transition from the lytic to the lysogenic states. *Compare* ***Int-2***. *See also* **retroregulation**.

Int-2 an oncogene first identified following the integration of mouse mammary tumour virus into the mouse DNA. Its product is a **fibroblast growth factor** (FGF3). *Compare* **Int**.

integer any rational whole number.

integral 1 of, or being an essential part of a whole; entire, complete. **2** *(in mathematics)* of, or denoted by, an **integer**; of or involving an **integral** (def. 3). **3** *(in mathematics)* the sum of a large number of infinitesimally small quantities, denoted ∫, summed either between specified limits (**definite integral**) or within indeterminate limits (**indefinite integral**).

integral (cell membrane) protein *or* **intrinsic protein** any protein that can only be dissociated from a cell membrane by drastic treatment with a reagent such as detergent, bile salt, protein denaturant, or organic solvent. Such proteins have one or more domains that traverse the cell membrane. *Compare* **peripheral (cell membrane) protein**.

integrase a protein of lambdoid phages that catalyses integration of phage DNA during establishment, probably by forming a transient DNA–protein link. The same enzyme is one subunit of the **excisase** activity that reverses this; the other subunit is the Xis protein, known as **excisionase**.

integrate 1 to combine or be combined into a whole; to complete (something imperfect) by the addition of parts. **2** *(in mathematics)* to find the **integral** (def. 3) of (quantities, expression, etc.). **—integrable, integrative** *adj.*; **integrability** *n.*

integrated rate equation a general expression for the interpretation of a single enzyme-catalysed reaction. The expression for the velocity of a reaction at time *t* is:

$$v = \mathrm{d[P]/d}t = V([\mathrm{S}]_0 - [\mathrm{P}]_t)/\{K_\mathrm{m}+([\mathrm{S}]_0 - [\mathrm{P}]_t)\}.$$

This can be integrated with respect to time to give:

$$Vt = [\mathrm{P}]_t + K_\mathrm{m}\ln\{[\mathrm{S}]_0/([\mathrm{S}]_0 - [\mathrm{P}]_t)\},$$

or

$$\ln\{[\mathrm{S}]_0/([\mathrm{S}]_0 - [\mathrm{P}]_t)\}/t = V/K_\mathrm{m} - [\mathrm{P}]_t/K_\mathrm{m}t,$$

where [S] and [P] are the concentrations of substrate and product, *v* is the velocity of the reaction, *V* is the limiting rate, and K_m is the Michaelis constant. The subscripts indicate the concentrations at zero time and at time *t*. A plot of $\ln\{[\mathrm{S}]_0/([\mathrm{S}]_0 - [\mathrm{P}]_t)\}/t$ against $[\mathrm{P}]_t/t$ will have a slope of $-1/K_\mathrm{m}$ and an intercept of V/K_m.

integration 1 the act or process of uniting or adding parts to make a whole. **2** the process of determining and/or indicating the mean value or total sum of (some physical quantity, area, etc.). **3** *(in mathematics)* the process of determining the **integral** (def. 3) of a function or a variable. *Compare* **differentiation**. **4** *(in genetics)* the act or process of forming a **cointegrate**.

integrative genomics the study of complex interactions between genes, organisms, and the environment.

integrator any device (mechanical or electronic) or any person that determines the value of an **integral** (def. 3).

integrin any member of the large family of transmembrane proteins that act as receptors for **cell-adhesion molecules**. Integrins are heterodimeric molecules in which the α and β subunits are noncovalently bonded. The subunits are named from α_1 to α_8, α_L (for **LFA-1**), α_M (for **Mac-1**), α_v (for **vitronectin** receptor), and from β_1 to β_7. Both subunits penetrate the cell-membrane lipid bilayer; the α subunit has four Ca^{2+}-binding domains on its extracellular chain, and the β subunit bears a number of cysteine-rich domains extracellularly. The integrins are grouped into families: the VLA family, having the β_1 subunit; the LEUCAM family, which includes LFA-1 and Mac-1, having the β_2 subunit; and a group of other integrins having subunits β_3–β_8. The type of integrin expressed on the cell surface determines which adhesion molecules (and thus which other cells) the cell will bind, and can be varied in different circumstances. For example, transforming growth factor-β increases expression of $\alpha_1\beta_1$, $\alpha_2\beta_1$, $\alpha_3\beta_1$, and $\alpha_5\beta_1$ integrins on fibroblasts and the $\alpha_\mathrm{v}\beta_3$ integrin on fibroblasts and osteosarcoma cells; interleukin-1β enhances β_1 expression on osteosarcoma cells; and in response to wounding, the keratinocyte, which normally expresses integrin $\alpha_6\beta_4$, will express $\alpha_5\beta_1$ (VLA-1, the fibronectin receptor) so that the keratinocyte will then migrate over fibronectin in the cell matrix, thus covering the wound. *See also* **adhesion molecules** (for details of the integrins to which they bind).

intein an internal peptide sequence of a protein precursor that is spliced out by transpeptidation during processing to form the mature protein. The peptide sequences that are spliced together are termed **exteins**. The terms are derived, respectively, by analogy from **introns** and **exons**.

intensify *(in photography)* to increase the opacity (of a film or plate). **—intensification**, **intensifier** *n.*

intensifying screens thin sheets of calcium tungstate used in autoradiographic detection of strong beta-emitting nuclides such as ^{32}P. Strong beta-particles pass through X-ray film and cause the screen to emit blue light, which is captured by silver halide grains in the film. Sensitivity of detection is increased fivefold when the film is exposed at –70°C because the decay of the latent image is decreased.

intensity *(in physics)* the magnitude of an energy flux, field strength, or force. *See* **luminous intensity**, **radiant intensity**.

intensity millicurie *an obsolete name for* **sievert** (def. 2).

intensive property any of the properties of a substance or object that describe a specific characteristic of the substance or object in a given state. Intensive properties are independent of the amount of the substance or the size of the object being considered, e.g. density, specific volume, temperature, etc. *Compare* **extensive property**. *See also* **intensive**.

inter+ *comb. form* signifying between, within, or among. *Compare* **intra+**

interaction 1 any reciprocal or mutual action or effect. **2** *(in physics)* the transfer of energy between elementary particles, between particles and a field, or between two or more fields. **—interact** *vb.*

interaction broadening the concentration-dependent broadening of lines in an electron spin resonance spectrum caused by magnetic interactions between paramagnetic molecular or atomic species.

interactive *(of two or more forces, fields, processes, etc.)* acting reciprocally or in close and/or continuing relation with each other; interacting.

interallelic complementation interaction between products of two mutant alleles to form a functional protein. It can occur in the case of multimeric proteins, for which subunits are encoded by two alleles. If products from only one mutant allele compose the protein, an inactive protein results, but in certain cases, if the products from the two alleles (each of which codes for an inactive protein) are combined in the protein, an active protein results. This was first shown in *in vitro* experiments by taking two inactive proteins of alleles encoding glutamate dehydrogenase (NADP^+), and recombining them by freezing and thawing in the presence of NaCl to form an active enzyme. There is some evidence that it can also occur *in vivo*.

interband any DNA-poor region between two (DNA-rich) bands in a polytene chromosome.

intercalary deletion *see* **deletion**.

intercalary DNA *abbr.*: iDNA; moderately repetitive DNA sequences occurring between structural genes in chromosomal DNA.

intercalation *(in molecular biology)* the insertion of additional material between the parts of an existing series, especially the insertion of molecules of antibiotic substances (e.g. actinomycin D) or acridine dyes (e.g. proflavine) between adjacent base pairs in a DNA duplex, thereby interfering with replication, etc. **—intercalate** *vb*; **intercalation** *n.*; **intercalary** *or* **intercalative** *adj.*

intercalator *or* **intercalating agent** *(in molecular biology)* any substance capable of being intercalated.

intercellular between cells. *Compare* **intracellular**.

intercept *(in mathematics)* a point at which two figures intersect; the point at which a line, curve, or surface cuts a coordinate axis.

interchain *(of any interaction or linkage)* between two chains of a biopolymer.

interconvertible enzyme any enzyme that exists in at least two well-defined reversibly convertible forms, produced by covalent modifications of amino-acid side chains under biological conditions (covalent modifications occurring as intermediates in the catalytic process are excluded). *Compare* **isoenzyme**.

intercrine *an alternative name for* **chemokine**.

interface 1 any surface forming a common boundary between two bodies, molecules, liquids, or phases. **2** any device, instrument, or method connecting two systems or processes; used especially of connections between computer systems. **3** to connect with or by an **interface** (def. 2). **—interfacial** *adj.*

interfacial tension the surface tension occurring at the interface between two mutually saturated liquids that tends to contract the area of the interface.

interference 1 *(in physics)* the process in which two or more wave trains of the same frequency and phase are superimposed to form a wave train in which there are alternate bands (called **interference fringes**) of no energy (due to **destructive interference**) or higher energy than that of the individual wave trains (due to **constructive interference**). **2** *(in virology)* the partial or complete prevention of the replication of one virus in a cell or tissue by the concomitant interaction between the given cell or tissue and another virus.

interference (light) filter a type of (light) filter with which a transmitted band-width of 10–20 nm can be obtained with a peak transmission of about 40%. It is possible to make interference filters in which the position of the centre of the transmittted band can be set within 1–2 nm.

interference fringe *see* **interference** (def. 1).

interference optics a system of optics, based on the Rayleigh interferometer, that is sometimes fitted to analytical ultracentrifuges. A double-sector ultracentrifuge cell is used, one sector containing only solvent and the other the solution being examined. The pattern of interference fringes produced by light passing through both sectors is a function of the refractive index at each point in the cell, each fringe tracing a curve of the refractive index against distance. Interference optics allows smaller changes in concentration to be detected than is possible by the **Schlieren method**.

interfering RNA *see* **RNA interference.**

interferogram a photographic record of a pattern of interference fringes.

interferometer an instrument that divides a beam of electromagnetic radiation into a number of beams and reunites them to produce **interference** fringes. It is useful for accurate measurement of the wavelength of the radiation, examination of the hyperfine structure of spectral lines, the testing of the flatness of surfaces, etc. **—interferometric** *adj.*; **interferometrically** *adv.*; **interferometry** *n.*

interferon *abbr.*: IFN; any member of a group of proteins that form a closely related group of non-viral proteins, M_r in the range 15 000 to 30 000, that are produced and liberated by animal cells following exposure to a variety of inducing agents; they are not normally present in uninduced cells. They exert non-specific, antiviral activity, at least in homologous cells, through cellular metabolic processes involving the synthesis of both RNA and protein. Viruses are the most potent inducing agents, but interferons can also be induced by exposure of cells to a wide variety of microorganisms, bacterial endotoxins, phytohemagglutinins, and other substances. Interferons do not prevent viral penetration into cells, but induce within the cells a complex of inhibitors of protein synthesis that block translation of viral mRNA, but not the cell's own mRNA. Among the interferon inhibitors are a protein kinase, which phosphorylates an initiation factor in protein synthesis, and an oligonucleotide synthetase, which catalyses the synthesis of pppA2′p5′A2′p5′A (*abbr.*: 2,5-A) – this trinucleotide activates a latent cellular endonuclease that degrades the viral mRNA. Interferons are classified into three types. **IFN-α** (*formerly* leukocyte interferon) comprises many examples; they are produced by macrophages, have antiviral activities, and stimulate production of two enzymes: a protein kinase and an oligoadenylate synthetase; they exist as monomers. **IFN-β** (*formerly* fibroblast interferon) has antiviral, antibacterial, and anticancer activities. It is related to the α family. **IFN-*γ*** (*formerly* immune interferon) is produced by lymphocytes activated by specific antigens or mitogens. In addition to antiviral activity, it has important immunoregulatory functions: it is a potent activator of macrophages, it has antiproliferative effects on transformed cells, and can potentiate the antiviral and antitumour effects of the type I interferons (α and β). It is a glycoprotein and exists as a homodimer. Interferons are produced commercially either by *in vitro* culture of human leukocytes or by recombinant DNA or RNA technology, *γ* interferon requiring a system that effects glycosylation.

interferon-γ receptor *abbr.*: Iγ-R; a widely expressed membrane receptor that consists of two single-pass transmembrane subunits that dimerize on binding of interferon γ (IFN-γ). One (Iγ-R1) is a glycoprotein of 472 amino acids, binds IFN-γ, becomes phosphorylated intracellularly, and activates JAK1 and STAT 1. The other (Iγ-R2) activates JAK2. Ligand binding also stimulates membrane sphingomyelinase to release ceramide. Several mutations in Iγ-R1 result in a rare autosomal recessive susceptibility to weakly pathogenic mycobacteria.

intergenic DNA regions of chromosomes between contiguous genes, whether or not they are encoded on the same or complementary strands of the duplex.

intergenic suppression *see* **suppression**.

interjacent RNA a 26S single-stranded RNA found in cells infected with certain togaviruses, e.g. Semliki forest virus. It codes for all the virus coat proteins.

interleukin *abbr.*: IL; any member of a heterogeneous group of **cytokines** that have the ability to act as signalling molecules between different populations of leukocytes. Several classes have been defined; each is designated by a suffixed arabic numeral: e.g., **interleukin 1** (IL-1), **interleukin 2** (IL-2), etc.

interleukin 1 *abbr.*: IL-1; *former names*: lymphocyte-activating factor (LAF); mitogenic protein (MP); helper-peak-1 (HP-1); T-cell-replacing factors III and m (TRF-III; TRF-m); B-cell-activating/differentiation factor (BAF; BDF). An interleukin of M_r 12 000–18 000, produced mainly by activated macrophages. It is not able to promote and maintain *in vitro* long-term cultures of T cells, but stimulates thymocyte proliferation by inducing **interleukin 2** release. It is involved in the inflammatory response, and is identified as an endogenous pyrogen.

interleukin 2 *abbr.*: IL-2; *other names*: thymocyte-stimulating factor (TSF); thymocyte mitogenic factor (TMF); T-cell growth factor (TCGF); co-stimulator; killer-cell helper factor (KHF); secondary cytotoxic T-cell-inducing factor (SCIF). An interleukin of M_r 30 000–35 000, produced by T cells in response to antigenic or mitogenic stimulation. Translocation involving the IL-2 gene causes one form of acute lymphoblastic leukemia. IL-2 promotes and maintains *in vitro* long-term cultures of T cells.

interleukin 3 *abbr.*: IL-3; *other names*: multipotential colony-stimulating factor; hematopoietic growth factor; P-cell-stimulating factor; mast-cell growth factor. A class of interleukins that are granulocyte/macrophage colony-stimulating cytokines; they act in hematopoiesis by controlling the production, differentiation and function of granulocytes and monocytes/macrophages. They are glycoprotein monomers.

interleukin 4 *abbr.*: IL-4; *other names*: B-cell stimulatory factor 1; lymphocyte stimulatory factor 1. An interleukin that participates in several B-cell activation processes, as well as those of other cell types. It is a co-stimulator of DNA synthesis, and is a glycoprotein.

interleukin 5 *abbr.*: IL-5; *other names*: T-cell-replacing factor; eosinophil differentiation factor. An interleukin that induces terminal differentiation of late-developing B cells to immunoglobulin- secreting cells. It is a homodimer, with subunits linked by a disulfide bond.

interleukin 6 *abbr.*: IL-6; *other names*: B-cell stimulatory factor 2; interferon β-2; hybridoma growth factor. An interleukin that induces myeloma and plasmacytoma growth, and nerve-cell differentiation. In hepatocytes, it induces acute-phase reactants. It is a glycoprotein.

interleukin 7 *abbr.*: IL-7; *other name*: hematopoietic growth factor. An interleukin that stimulates proliferation of lymphoid progenitor cells. It is produced by monocytes, T cells, and NK cells.

interleukin 8 *abbr.*: IL-8; *other names*: monocyte-derived neutrophil chemotactic factor (MDNCF); T-cell chemotactic factor; neutrophil-activating protein 1 (NAP-1); lymphocyte-derived neutrophil-activating factor; protein 3-10C. An interleukin that acts as a chemotactic factor, attracting neutrophils, basophils, and T cells, but not monocytes. It is released from several cell types in response to inflammatory stimuli.

interleukin 9 *abbr.*: IL-9; *other names*: T-cell growth factor; p40 precursor. An interleukin that supports IL-2/IL-4-independent growth of helper T cells.

interleukin 10 *abbr.*: IL-10; *other names*: cytokine synthesis inhibitory factor (CSIF); cytokine glycoprotein. An interleukin that appears to be a suppressor factor for Th1 immune responses.

interleukin 11 *abbr.*: IL-11; *other name*: adipogenesis inhibitory factor (AGIF). An interleukin that acts as both cytokine and growth factor. It stimulates plasmacytoma proliferation, and the T-cell-dependent development of immunoglobulin- producing B cells.

interleukin 12 *abbr.*: IL-12; *other name*: cytotoxic lymphocyte maturation factor. An interleukin that can act as a growth factor for activated T and natural killer (NK) cells, enhance the lytic activity of NK/lymphokine-activated killer cells, and stimulate the production of interferon-γ by resting PMBC. It is a disulfide- linked heterodimer of 35 kDa (α) and 40 kDa (β) subunits. NK stimulatory factor (NKSF) is essentially a complex of cytokine and soluble receptor. Both subunits are glycoproteins; α has some similarity to **interleukin 6**; β has an immunoglobulin-like domain.

interleukin 13 *abbr.*: IL-13; an interleukin that inhibits inflammatory cytokine production. It synergizes with **interleukin 2** in regulating interferon-γ synthesis.

interleukin 15 *abbr.*: IL-15; an interleukin produced in various tissues that has biological functions similar to those of **interleukin 2**. Its receptor consists of an α subunit that activates JAK1 (*see* **JAK**), and a γ subunit of interleukin 2 receptor (IL-2R) that activates JAK3.

interleukin 16 *abbr.*: IL-16; an interleukin that binds T lymphocytes through **CD4**.

interleukin 1β convertase EC 3.4.22.36; *other name*: interleukin-1β converting enzyme (*abbr.*: ICE); a proteolytic enzyme that cleaves the interleukin-1β precursor specifically at Asp^{116}-|-Ala^{117} and Asp^{27}-|-Gly^{28} in the precursor, producing the mature cytokine. It is a cysteine endopeptidase.

intermediary metabolism the chemical pathways by which molecules and structures found in living cells are synthesized from molecules that are taken into the cells, and subsequently broken down to molecules that are eliminated from the cells.

intermediate 1 occurring, or situated between two things in time, place, or order. 2 *(in chemistry or biochemistry)* any compound that takes part in a reaction, or sequence of reactions, occurring between the starting materials and the products. In metabolism, intermediates occur between the nutrients taken in and cellular material synthesized, or between cellular material and excretory products.

intermediate body *a former name for* **amboceptor**.

intermediate-density lipoprotein *abbr.*: IDL; one of the classes of lipoprotein found in blood plasma in many animals (data normally relate to humans). These lipoprotein particles have diameter 19.6–22.7 nm, solvent density for isolation (g mL^{-1}) 1.006–1.019, hydrated density (g mL^{-1}) 1.003. Their approximate composition (% by weight) is 8% unesterified cholesterol, 22% esterified cholesterol, 25% phospholipid, 30% triacylglycerol, 15% protein. Their apolipoprotein composition (% by weight total apolipoprotein) is 50–70% B-100, 5–10% C-I + C-II + C-III, 10–20% E-II + E-III + E-IV. They are formed in the plasma from very-low-density lipoproteins as a result of the action of **lipoprotein lipase**, and represent an intermediate stage in the conversion of very-low-density lipoproteins to low-density lipoproteins. *See also* **apolipoprotein** for individual apolipoproteins.

intermediate filament a distinct elongated structure, characteristically 10 nm in diameter, that occurs in the cytoplasm of higher eukaryotic cells. Intermediate filaments form a fibrous system, composed of chemically heterogeneous subunits and involved in mechanically integrating the various components of the cytoplasmic space. Intermediate filaments may be divided into five chemically distinct classes: **keratin** filaments of mammalian epithelial cells; **desmin** filaments found in cells of muscles of all types; **vimentin** filaments found in mesenchymal cells; neurofilaments of neurons; and glial filaments found in all types of glial cells. *Compare* **microfilament**, **microtuble**.

intermediate lobe *or* **intermediate part** *or* **pars intermedia (hypophyseos)** the part of the **pituitary gland** lying between the anterior and the posterior lobes. It is absent in adult humans but is present in fetal humans and in certain other species.

intermedin *a former name for* β-melanocyte-stimulating hormone (so-called because of its occurrence in the intermediate lobe of the pituitary gland). *See* **melanocyte-stimulating hormone**.

internal compensation the phenomenon of the existence of **internally compensated** molecular entities in general, or the property of such a molecular entity in a particular instance.

internal conversion *abbr.*: IC; a mode of radioactive decay of an excited atomic nucleus (formed by a nuclear transformation) in which, in a proportion of instances, excess energy released from the nucleus is not radiated from the atom as a quantum of low-energy gamma radiation but is imparted to one of the inner orbital electrons, which is thereupon ejected as a **conversion electron**; the electron emission is homoenergetic. The filling of the vacant orbital in the resultant excited ion causes emission also of either an Auger electron or a quantum of the characteristic X-radiation of the daughter atom.

internal energy *symbol*: *U or E*; a function of state that describes the sum of the kinetic and potential energy of a system. For closed systems, a change in internal energy, ΔU, usually results in a transfer of work or heat between the system and the surroundings. Thus $\Delta U = q + w$, where q is the heat gained by the system and w is the work done on the system.

internalin a surface protein of invasive forms of *Listeria monocytogenes*. It belongs to the invasin family, contains leucine-rich repeats, and binds to the epithelial transmembrane protein E-cadherin.

internal indicator any indicator substance used to follow a reaction, or other process, that is placed in the reaction mixture, or system.

internalize *or* **internalise** to render internal; especially to take a substance into a cell or organism. —**internalization** *or* **internalisation** *n.*

internally compensated describing any molecular entity that possesses equal numbers of structurally identical groups of opposite chirality. If no other chiral groups are present the overall entity is achiral and is designated by the prefix *meso*+.

internal ribosomal entry *abbr.*: IRE; the initiation of protein synthesis by certain viral and cellular mRNAs (e.g. those for cMyc, Apaf1, and Xiap) by a mechanism that is independent of recognition of the 5′ cap of the mRNA by the initiation factor eIF4E.

internal secretion *a former name for* **endocrine** (def. 2).

internal standard any standard used as a reference in an assay that is added to the samples and subjected to the whole of the procedures applied to them.

internal-standard method (of quench correction) *or* **internal standardization** a method of correcting for quenching in **liquid scintillation counting**. After the sample has been counted a measured small amount of a (nonquenching) standard preparation, of known activity, of the radionuclide in question is added to it and the sample is recounted. From the increment in the count rate the counting efficiency within the sample, and hence the degree of quenching, may be calculated. The method is simple and reliable and corrects adequately for all types of quenching but is more time-consuming than the **external-standard method** and has other disadvantages.

International Biological Standard any of the numerous internationally agreed standards of activity or potency of antisera, hormones, vitamins, antibiotics, and other biologicals. Each has been defined in terms of a mass of an appropriate standard preparation, prepared and stored under specified conditions.

International chemical identifier *abbr.*: INCHI; a unique, computer-readable identifier for a chemical compound. It consists of an alphanumeric string that describes the chemical structure.

International Practical Temperature Scale *abbr.*: IPTS; *see* **temperature**.

International System of Units the English translation of Système International d'Unités; *see* **SI**.

International Unit *abbr.*: IU (preferred) *or* i.u. *or* u; any unit of activity or potency of an antiserum, hormone, vitamin, antibiotic, or other biological defined in terms of the activity of an appropriate **International Biological Standard** or International Biological Reference Preparation. International Units are useful for quantifying a specific biological activity of a material before the chemical nature of the substance responsible for the activity has been fully characterized, or before pure preparations with reproducible activity are available.

Internet a protocol for allowing communication between computers, including those at distant sites. More loosely 'the internet' is used to refer to the worldwide network of such computers, including the providers of database services, discussion forums, and other communication media.

α-internexin *see* **peripherin**.

internuclear double resonance spectrometry *abbr.*: INDOR; a technique used in **nuclear magnetic resonance spectrometry** as an aid to assignment of resonances. It involves monitoring a single frequency, f_1 (usually one corresponding to a single transition), while sweeping a perturbing (decoupling) frequency, f_2, through a selected range of frequencies. Signals, negative or positive, will only appear in the INDOR spectrum when f_2 passes through a transition that has an energy level in common with the transition at f_2, making it possible to determine otherwise inaccessible chemical shifts and coupling constants.

interoperability *(in computing)* the ability of different computers, networks, operating systems, and applications to communicate with one another seamlessly (i.e. without technological barriers).

interphase the state of a eukaryotic cell when not undergoing mitosis or meiosis. It covers the G_1, S, and G_2 phases of the **cell-division cycle**.

interpolate *(in mathematics)* to estimate a value of a function between data values already obtained or known either graphically or by calculation. *Compare* **extrapolate**. **—interpolation** *n.*

InterPro *see* **derived database**.

intersectin a protein partner of dynamin in the endocytosis machinery.

intersegment transfer a proposed mechanism for the transfer of a repressor of gene expression in a nonspecifically bound state to its target site. It involves the rapid and direct transfer of repressor from one segment of a DNA molecule to another as a consequence of the relative diffusion of these segments within the domain of the molecule.

interstice any minute space or crevice that intervenes between structures, e.g. between cells, organs, or tissues, or between atoms in a crystal lattice. **—interstitial** *adj.*

interstitial cell a connective tissue cell lying in the interstices between other cells in a tissue and serving to bind the tissue cells. Examples include the neuroglial cells, and the testosterone-producing Leydig cells lying between the seminiferous tubules in the testis of vertebrates.

interstitial cell-stimulating hormone *abbr.*: ICSH; *a former name for* **luteinizing hormone**.

interstitial collagenase EC 3.4.24.7; *other names*: vertebrate collagenase; matrix metalloproteinase 1; an enzyme that cleaves preferentially one bond in native collagen and catalyses the cleavage of the triple helix of collagen at about three-quarters of the length of the molecule from the N terminus, at Gly^{775}-|-Ile^{776} in the α-1(I) chain. It cleaves synthetic substrates and α-macroglobulins at bonds where P1′ is a hydrophobic residue. Zinc is a cofactor.

interstitial deletion the loss of DNA or part of a chromosome that occupies an interstitial (i.e. nonterminal) position.

interstitial fluid the portion of the **extracellular fluid**, consisting mainly of water, that occurs outside the blood vessels and the lymphatics. In a 70 kg man its volume is approximately 12 L and it represents approximately 17% of body mass. It has a higher content of sodium, chloride, and bicarbonate and a lower content of potassium, magnesium, sulfate, and phosphate than **intracellular fluid**.

intertrabecular space the space within cells lying between the elements of the **microtrabecular lattice**.

intervening sequence *an alternative name for* **intron**.

intimin an actin-polymerization-inducing protein produced by enteropathogenic and enterohemorrhagic strains of enteric bacteria. It is an outer membrane protein of *Escherichia coli*, necessary for attachment of the bacterium to epithelial cells.

intoxication 1 any metabolic process that converts a nontoxic **xenobiotic** to a toxic product. **2** poisoning, especially with ethanol, manifested in behavioural change of the subject.

intra+ *prefix* signifying within, on the inside, or during. *See also* **endo+**. *Compare* **inter+**.

intracellular within a cell or cells.

intracellular fluid *abbr.*: ICF; the portion of the total fluid content of a multicellular organism that occurs within the cells, especially as distinct from **extracellular fluid**. In a 70 kg man the volume of ICF is approximately 26.5 L, and it represents approximately 38% of body mass. It has a higher content of potassium, magnesium, sulfate, and phosphate, and a lower content of sodium, chloride, and bicarbonate than **interstitial fluid**.

intrachain *(of any interaction or linkage)* between different parts of a single chain of a biopolymer.

intradermal *abbr. (in medicine)*: ID *or* i.d.; within the layers of the skin.

intragenic suppression *see* **suppression**.

intramolecular within the same molecule.

intramolecular chaperone a domain within a protein that mediates conformational change of that protein (i.e., exercises a **chaperone** function). **Trypsinogen**, e.g., contains such a domain.

intramuscular *abbr. (in medicine)*: IM *or* i.m.; within a muscle or muscles; used especially of an injection.

intranet a computer network isolated from the Internet, often by means of a firewall, that offers typical Internet facilities to the local community (e.g. Web servers, email, bulletin boards).

intraperitoneal *abbr.*: IP *or* i.p.; within the peritoneum; used especially of an injection, infusion, or aspiration.

intrapleural within the pleura or pleurae; used especially of an injection or aspiration.

intrathecal within the intradural or subarachnoid space; used especially of an injection or aspiration.

intravenous *abbr. (in medicine)*: IV *or* i.v.; within a vein; used especially of an injection, infusion, transfusion, or aspiration.

intrinsic 1 of or pertaining to the essential nature of something; inherent. **2** *(in morphology)* peculiar to, or situated in a part. **—intrinsically** *adv.*

intrinsic activity *an alternative name for* **maximal agonist effect**.

intrinsically unstructured describing a protein or protein domain that lacks a folded structure but instead displays a highly flexible, random-coil-like conformation under physiological conditions. Examples include **calpastatin**, **casein**, and **tau**.

intrinsic association constant *or* **intrinsic binding constant** *see* **intrinsic constant**.

intrinsic birefringence the optical anisotropy of an individual molecule.

intrinsic constant any association, binding, or dissociation constant that describes the association, binding, or dissociation of a ligand to (or from) a particular site on a polyvalent molecule, when all the sites of this type are identical, present in the same molecule, and noninteracting.

intrinsic dissociation constant *see* **intrinsic constant**.

intrinsic efficacy *symbol*: ε; an expression introduced by Furchgott that denotes the notional efficacy of a drug associated with a single receptor. It is given by $\varepsilon = e/[\mathrm{R_t}]$, where e is the **efficacy** and $[\mathrm{R_t}]$ indicates the total concentration of active receptors of a certain type.

intrinsic factor *abbr.*: IF; a glycoprotein, secreted by the parietal cells of the gastric mucosa, that is necessary for the adequate absorption of dietary **cobalamins**. Intrinsic factor binds cobalamins in the intestinal lumen to form a complex that is subsequently bound by cubulin on the mucosa of the ileum. Cubulin is associated with LRP2 in the ileal mucosa and together they cause endocytosis of the IF–cobalamin complex. Cobalamin is bound to transcobalamin II in the portal blood. Congenital pernicious anemia is caused by absence of IF, a defect in cubulin, or deficiency in transcobalamin II of intrinsic factor.

intrinsic pathway (of blood coagulation) *see* **blood coagulation**.

intrinsic protein *less common term for* **integral (cell membrane) protein**.

intrinsic viscosity *symbol*: η_{int}; the limiting value of the **specific viscosity**, η_{sp}, of a solution as the concentration of the solute tends to zero. The units are $\text{cm}^3\ \text{g}^{-1}$. Its value depends on the specific volume of the (solvated) solute, V, and on a shape-dependent factor, ν, as follows: $\eta_{\text{int}} = \nu V$. The value of ν is 2.5 for a sphere and its value increases for solutes of other shapes. The name **limiting viscosity number** has been recommended for this attribute.

intron *or* **intervening sequence** any intragenic region of DNA in eukaryotes that is not expressed in a mature RNA molecule. Such regions occur between coding sequences (**exons**); this arrangement of introns alternating with exons constitutes a **transcription unit**. By customary usage, the term is extended to the corresponding regions of the **primary transcript** of RNA. In RNA, four general types of introns are distinguishable: (1) yeast nuclear tRNA; (2) group I introns; (3)

group II introns; and (4) nuclear mRNA precursor. Group I and II introns were first described for fungal mitochondrial genes; group I introns are characterized by a lack of conserved sequences at splicing junctions but have short conserved sequences internally, while group II introns have conserved sequences at the splicing junctions. The introns of different RNA types are spliced by different mechanisms (*see* **splicing**). It has been customary to describe introns as 'junk DNA', i.e. DNA for which no function can be found, but this concept must be modified. Many 'self-splicing introns' in the pre-rRNA of *Tetrahymena* double as mRNAs from which proteins are expressed that assist self-splicing and/or mediate intron translocation to new DNA sites. In the expression of a gene coding for small, stable RNAs that accumulate in the nucleolus, certainly of humans and mouse, it is the introns that give rise to RNA rather than the exons. Hence the terms intron and exon should simply signify RNA sequences that become physically separated during the process of RNA splicing. **—intronic** *adj.*

inulin a slightly soluble polysaccharide, of ≈6 kDa, found in members of the Compositae and Campanulaceae, in which it partially or completely replaces starch as a reserve carbohydrate. It is a linear glycan composed of about 35 (β2→1)-linked D-fructofuranose residues terminating in an (α1→2)-D-glucopyranosyl residue. Inulin is useful in the measurement of renal clearance, as inulin is neither reabsorbed nor secreted by the renal tubular cells. It is also useful in the measurement of extracellular fluid volume (**inulin space**), since it can pass through the blood capillary walls but is not taken up by cells.

inulobiose the disaccharide 2-*O*-β-D-fructofuranosyl-D-fructose.

inulosucrase EC 2.4.1.9; an enzyme that participates in inulin biosynthesis. *See also* **sucrase** (def. 3).

in utero *Latin* within the uterus.

in vacuo *Latin* in a vacuum.

invaginate 1 to infold, especially to form a sheathlike or saclike enclosure. **2** describing an organ or part that is folded back upon itself. **—invagination** *n.*

invariant chain *or* **CD74** *or* **Ii** a protein (31 kDa) of the endoplasmic reticulum (ER) lumen that binds newly formed class III MHC heterodimeric proteins so as to prevent binding of endogenous peptides to their groove. It acts as a chaperone for these molecules until they leave the Golgi apparatus and enter the endosome pathway. It is degraded proteolytically but leaves a fragment (called CLIP) bound within the groove. In acid vesicles, after leaving the Golgi apparatus, CLIP exchanges with peptides derived from exogenous antigens.

invariant residue any amino-acid residue that always occurs in equivalent positions in the polypeptide chains of homologous proteins from different species, or in genetic variants of the protein from a given species.

invasin 1 *an alternative name for* **hyaluronidase**. **2** any of a family of surface proteins of various intracellular bacterial pathogens by which the bacteria invade nonphagocytotic host cells (e.g. those of the gut epithelia). All contain leucine-rich repeats. *See* **internalin**.

invasive *(in pathology)* tending to penetrate into healthy tissue and grow within the host away from the site of entry or origin. It is used especially of a pathogenic organism, cell, or group of cells, e.g. cancer cells. **—invasiveness** *n.*

inverse agonist any ligand that by binding to receptors reduces the fraction of them in an active conformation, thereby having biological effects opposite to those produced by an **agonist** (as in **benzodiazepine inverse agonist**). This can occur if some of the receptors are in the active form even in the absence of a conventional agonist. *Compare* **partial inverse agonist**.

inverse PCR a variant form of **polymerase chain reaction** (PCR) in which DNA of unknown sequence but flanking a known sequence can be amplified. Digestion of the DNA with a restriction enzyme followed by ligation at low DNA concentrations favours the formation of closed circular molecules. PCR primers based on the known sequence are designed so that their 5′ ends are adjacent on the two strands of the duplex. The PCR product is a linear DNA molecule containing known sequence at each end with unknown sequence between.

inverse-square law a law according to which the magnitude of a physical quantity, e.g. the intensity of electromagnetic or other radiation, is proportional to the reciprocal of the square of the distance from the source of the property.

inversion 1 configurational inversion the process of changing the **configuration** about a chiral centre into that with the opposite configuration. *See also* **Walden inversion**. **2** the hydrolysis of sucrose to an equimolar mixture of glucose and fructose. It is so-called because of the accompanying reversal of direction of optical rotation by the solution. **3 chromosomal inversion** the excision of a chromosomal segment followed by its reinsertion at the same position after having been turned through 180°. **Paracentric inversions** are confined to one or other arms of the chromosome, whereas **pericentric inversions** span the centromere. Both types create changes in gene order, and sometimes cause disordered meiosis, genetic abnormalities, and reduced fertility.

inversion isomer *an alternative name for* **invertomer**.

invert 1 to turn or cause to turn inward, or upside down. **2** to reverse in direction, sequence, effect, etc. *See also* **inversion**.

invertase *or* **saccharase** EC 3.2.1.26; *recommended name*: β-fructofuranosidase; *systematic name*: β-D-fructofuranoside fructohydrolase. An enzyme from yeast and other sources that catalyses the **inversion** (def. 2) of sucrose. *See also* **saccharase**.

invertebrate 1 any animal lacking a vertebral column (backbone) and internal skeleton. **2** of, pertaining to, or designating any such animal.

inverted repeat *or* **indirect repeat** *abbr.*: IR; either of a pair of sequences in duplex DNA that exhibit two-fold rotational symmetry around a centre, the two sequences being complementary to each other. The sequence of the two repeats together is called a **palindrome**, e.g.

GGTACC
CCATGG.

The repeats need not be contiguous, e.g.

GGTNNACC
CCANNTGG.

Inverted repeats promote the formation of **cruciform** structures. Their function is unknown. However, they are found flanking transposable elements, which may indicate an associated role. *See also* **cruciform**, **dyad symmetry**, **hairpin**.

invertin an enzyme preparation from yeast. The major component is an α-glucosidase activity. *See also* **emulsin**.

invertomer *or* **inversion isomer** either of two **conformers** that interconvert by inversion at an atom possessing a nonbonding electron pair.

invert sugar an equimolar mixture of D-glucose and D-fructose formed by the hydrolysis, i.e. **inversion** (def. 2), of sucrose. It is sweeter than its parent disaccharide. *See also* **high-fructose corn syrup**.

inverzincin a family of conserved metalloproteases that contain an inverted zinc-binding site (i.e. His–Xaa–Xaa–Glu–His). Examples include insulinase and *E. coli* protease III.

in vitro *Latin (of any biological process, reaction, or experiment)* occurring or made to occur outside an organism, e.g. in extracts or cultures; literally it means 'in glass'. *Compare* ***in vivo***.

***in vitro* packaging** the assembly of head and tail proteins of bacteriophages with recombinant bacteriophage DNA to generate infectious phage particles.

***in vitro* transcription** the generation of a sense or antisense RNA copy of a cDNA molecule usually carried in a plasmid or other vector. This is accomplished by using an RNA polymerase from T3, T7, or SP6 phage that initiates transcription from a cognate promoter situated upstream from the cloned DNA insert.

***in vitro* translation** the generation of a polypeptide whose sequence is specified by mRNA added to extracts of reticulocytes or wheatgerm. Such extracts have all the components necessary for translation, including ribosomes, tRNAs, and amino acids. One or more of the amino acids can be radioactively labelled. This method is sometimes combined with *in vitro* transcription in the same reaction mixture.

in vivo *Latin (of any biological process, reaction, or experiment)* occurring or made to occur within a living organism; literally it means ‘in life’. *Compare* **in vitro**.

involucrin a protein of keratinocytes and other stratified squamous epithelia that first appears in the cell cytosol, but ultimately becomes cross-linked to membrane proteins by the action of transglutaminase.

involute 1 involved, intricate. **2** spiral, having whorls wound closely around the axis. **3** having edges that roll under or inwards. **4** to be subjected to a process involving the inward rolling of the surrounding tissue

iod+ *a variant form of* **iodo+** (sometimes before a vowel).

iodate 1 the anion, IO_3^-, derived from iodic(V) acid. **2** any salt of iodic(V) acid.

iodide 1 the anion, I^-, of the element iodine. **2** any salt of hydriodic acid. **3** any compound containing an iodine atom in organic linkage.

iodide-chloride transporter *or* **Pendrin** a human integral membrane protein (780 amino acids) predicted to contain 11 transmembrane segments. It may be the iodide transporter on the colloid surface of thyroid follicle cells. More than 30 mutations in the gene lead to the Pendred syndrome of thyroid goitre with congenital deafness, or simple, isolated deafness.

iodide pump *or* **Na^+/I^- symporter** (*abbr*.: NIS) an integral membrane protein that cotransports Na^+ and I^- into the thyroid follicles. It is dependent on sodium/potassium ATPase activity, and is stimulated by thyroliberin. It contains 643 amino acids and is predicted to contain 12, 13, or 14 transmembrane segments. It is also present in salivary glands, gastric mucosa, choroid plexus, and mammary glands, and shares 30% sequence homology with the Na^+/glucose transporter 1. Several mutations lead to congenital hypothyroidism as a result of a defect in entry of iodide into cells of thyroid follicle.

iodide trapping defect *see* **iodide pump**.

iodimetry a volumetric method of analysis applicable to substances with a redox potential appreciably lower than that of the iodine–iodide system (E^o = +0.535 V at 25°C). Such substances are oxidized by iodine and may therefore be titrated in acid solution with a standard solution of iodine. *Compare* **iodometry**. **—iodimetric** *adj.*; **iodimetrically** *adv.*

iodinatable capable of being converted into an iodo derivative. The term may be used of an organic compound or a particular part of one, such as a residue in a peptide.

iodinate 1 to treat or react (a substance) with iodine. **2** to introduce one or more iodo groups into (an organic compound), whether by addition or substitution. **—iodination** *n.*

iodine 1 *symbol*: I; a nonmetallic element of group 17 of the IUPAC **periodic table** and one of the halogens; proton number 53; it exists naturally as a single stable nuclide, **iodine-127**, of relative atomic mass 126.904. It is widely distributed in nature, although never found as the free element, and is an essential dietary element. Numerous (about 29 unstable and seven metastable) artificial radioactive nuclides are known. Of these, the most widely used in biochemistry and molecular biology are **iodine-125** and **iodine-131**. **2** *symbol*: I_2; *the common name for* the substance correctly known as diiodine, a bluish-black solid that sublimes at room temperature into a violet-coloured irritating vapour. An ethanolic solution is useful as a mild topical antiseptic.

iodine-125 the artificial radioactive nuclide $^{125}_{53}I$. It decays to the stable nuclide tellurium-125 by capture to the nucleus of an orbital electron from the K (i.e. innermost) shell, emitting low-energy gamma radiation (35.5 keV, 7% emitted and 93% internally converted) and characteristic tellurium K X-radiation (27–32 keV, 140%), but no beta radiation. It has a half-life of 59.6 days.

iodine-127 the stable nuclide $^{127}_{53}I$. Its relative abundance in natural iodine is 100 atom percent.

iodine-131 the artificial radioactive nuclide $^{131}_{53}I$. It decays to the stable nuclide xenon-131, emitting a moderate-energy electron or beta particle of various energies (0.25–0.81 MeV max., mainly 0.61 MeV max.) plus gamma radiation of various energies (0.08–0.72 MeV, mainly 0.36 MeV), 1.3% of nuclides decaying via the metastable nuclide xenon-131m. It has a half-life of 8.04 days.

iodine-labelling a widely used procedure for labelling a compound or material by introducing into it, directly or indirectly, one or more atoms per molecule of iodine, especially radioactive isotopes (i.e. radioiodine). *See also* **radioiodinate**.

iodine number *or* **iodine value** a measure of the degree of unsaturation of a fat or fatty acid, defined as the number of grams of iodine capable of reacting with 100 g of the sample. It is usually determined indirectly by measuring the amount of an iodine-containing reagent, e.g. iodine monobromide, that remains after excess has been added and reaction is complete. The iodine number of saturated fatty acids is zero, that of oleic acid is 90, of linoleic acid 181, and of linolenic acid 274.

iodo of, relating to, or describing a compound that contains an iodine atom in organic linkage.

iodo+ *or (sometimes before a vowel)* **iod+** *comb. form* denoting **1** an iodine atom in organic linkage. **2** violet-coloured. *See also* **iodo**.

iodoacetamide $I–CH_2–CONH_2$; a compound that acts as an inhibitor of an enzyme containing –SH groups, Enz–SH, by reacting irreversibly to give $Enz–S–CH_2–CONH_2$, with elimination of HI.

Iodo-Gen *a proprietary name for* 1,3,4,6-tetrachloro-3*α*,6*α*-diphenylglycouril; a solid-phase reagent that oxidizes low concentrations of inorganic iodide to iodine and hence is useful for the rapid and efficient labelling of proteins with radioactive iodine. Being very stable and virtually insoluble in water, it can be used in the form of a prior coating on the walls of a reaction vessel containing aqueous solutions of iodide ion and protein.



iodogorgoic acid *a former name for* 3,5-**diiodotyrosine**.

iodometry a volumetric method of analysis applicable to substances with a redox potential appreciably higher than that of the iodine–iodide system ($E^{o\prime}$ = +0.535 V at 25°C). Such substances are reduced by iodide, which is added in excess to acidified solutions and the liberated iodine titrated with a standard solution of thiosulfate. *Compare* **iodimetry**. **—iodimetric** *adj.*; **iodimetrically** *adv.*

iodopsin any of three light-sensitive visual pigments in the cone cells of the retinas of vertebrates, other than freshwater and migratory fishes, and some amphibians. They consist of different cone-type opsins combined (as Schiff’s bases) with 11-*cis*-**retinal**. Each individual cone cell contains one of the three pigments, which have absorption maxima at ~430 nm, ~540 nm, and ~575 nm. The iodopsins were once thought to be a single pigment, termed visual purple or visual violet. *See also* **cyanopsin**, **retinal**.

iodotyrosine deiodinase an NADPH-dependent flavoprotein enzyme that deiodinates monoiodotyrosine and diiodotyrosine derived from proteolytic degradation of thyroglobulin within lysosomes of thyroid follicle cells. The released iodide (I^-) is recycled by the thyroperoxidase of those cells. Enzyme deficiency leads to excessive loss of the iodotyrosines and to congenital goitre and hypothyroidism.

ion any atom or other molecular entity that has acquired an electric charge by loss or gain of one or more electrons. An anion is negatively charged, and a cation is positively charged.

ion atmosphere the region surrounding a charged molecular entity in which there is a statistical preference for ions of opposite charge.

ion chamber *another name for* **ionization chamber**.

ion channel any channel in cell membranes that allows the passage of specific inorganic ions through the membrane. Ion channels may be **ligand-gated**, **voltage-gated**, or **mechanically gated channels**. For ligand-gated channels, the ligand may be extracellular such as a neurotransmitter (**transmitter-gated channel**), or intracellular such as an ion (**ion-gated channel**), or a nucleotide. Ion channels are common direct or indirect targets for the action of drugs, which may either potentiate or inhibit channel opening.

ion exchange the process in which ions of like charge, which may be the same or different chemically, are exchanged between two phases, such as two solutions separated by a semipermeable membrane or a solution and an insoluble material, e.g. a resin.

ion-exchange cellulose *abbr.*: IEC; any derivatized cellulose containing cationic or anionic substituents used in **ion exchange**, especially for the separation of charged biopolymers.

ion-exchange chromatography any form of chromatography that depends on the process of **ion exchange** to effect the separation.

ion-exchange polymer an insoluble polymer that has ionic groups and is able to exchange counterions with the ionic components of a solution. Cation exchangers carry anionic groups such as sulfonate or carboxyl, whereas anion exchangers carry cationic groups such as primary or quaternary ammonium groups. An ion-exchange polymer in ionized form may also be referred to as a **polyanion** or a **polycation**.

ion exchanger any **anion exchanger** or **cation exchanger**.

ion-exchange resin *a former term (now discouraged) for* **ion-exchange polymer**.

ion-exclusion chromatography a chromatographic technique by which strong electrolytes can be separated from nonelectrolytes and weak electrolytes by passage of the mixture through an ion-exchange resin in a buffer of ionic strength and pH that can be varied in the course of the separation. At low salt concentrations particularly, ionic repulsive forces tend to exclude from the resin those ions that have the same charge as the functional groups on the resin so that these ions, together with an equivalent number of counterions, pass rapidly through the column while nonelectrolytes and weak electrolytes enter the resin and thus pass more slowly through the column at a rate determined in part by the pK of their ionizable groups.

ion-gated channel *see* **ion channel**.

ionic 1 of, pertaining to, existing as, or characterized by **ions**. **2** using or operated by ions.

ionic atmosphere the cloud of ions of one charge type that tend to accumulate by interionic attraction around an ion of the other charge type in a solution of an electrolyte. The cloud is symmetrical about the charge on the central ion unless the solution is subjected to a shearing force conducive to flow or is exposed to an applied electric field. In the latter event the central ion and its surrounding counterions migrate in opposite directions, the resultant asymmetric disposition of the ionic atmosphere effecting retardation of the central ion in a concentration-dependent manner.

ionic bond any bond formed by attraction between a positively and a negatively charged group on different parts of the same molecule or on different molecules.

ionic conduction the passage of electricity due to the movement of ions.

ionic detergent any **anionic detergent** or **cationic detergent**. *Compare* **nonionic detergent**.

ionic double layer the region surrounding a charged molecular entity together with the layer of **counterions** that surrounds it.

ionic mobility a measure of the velocity at which an ion moves through a liquid under the influence of an applied electric potential.

ionic product *see* **ion product**.

ionic strength *symbol*: I *or* I_m (molality basis) *or* I_c (concentration basis); a physical quantity equal to half the summation over all ions in a solution of the concentration of each ion multiplied by the square of its charge. Hence,

$$I_\mathrm{m} = 0.5(\Sigma m_i z_i^2)$$

and

$$I_\mathrm{c} = 0.5(\Sigma c_i z_i^2),$$

where m_i and c_i are the molal and molar concentrations of the ith ion, respectively, and z_i is its charge.

ionizable group *or* **ionisable group** any uncharged group in a molecular entity that is capable of dissociating by yielding an ion (usually an H^+ ion) or an electron and itself becoming oppositely charged, or of associating with an ion (usually an H^+ ion) and itself assuming the ion's charge. The extent to which an ionizable group becomes an ionizing group depends on the constitution of the molecular entity and upon the environment.

ionization *or* **ionisation** any of the processes by which one or more ions are generated. It may occur, e.g., by loss or gain of a hydron by a solute in response to changes in pH, or by the loss of an electron from a neutral chemical species by unimolecular heterolysis of such a species into two or more ions. Further, a gas may become ionized by the passage through it of fast charged particles or electromagnetic radiation.

ionization chamber *or* **ionisation chamber** *or* **ion chamber** a chamber containing a gas and two electrodes between which an electric potential difference is maintained. It is used to detect ionizing particles or electromagnetic radiation by virtue of the current that flows following ionization of the gas.

ionization constant *or* **ionisation constant** the **dissociation constant** for a reversible reaction in which the products are ionic.

ionization energy *or* **ionisation energy** *symbol*: E_I; the minimum energy (enthalpy) required to remove an electron from an isolated molecular entity (in its vibrational ground state) in the gaseous phase. It was formerly, and misleadingly, termed ionization potential.

ionization potential *or* **ionisation potential** *a former term for* **ionization energy**.

ionize *or* **ionise** to convert, or to become converted, wholly or in part, into ions; to cause **ionization** of (something). —**ionizable** *adj.*

ionizing particle *or* **ionising particle** any charged particle of sufficient energy to enable it to dislodge an orbital electron from an atom or other molecular entity. *See* **ionizing radiation**.

ionizing power *or* **ionising power** *or (sometimes)* **polarity** a qualitative term used to denote the tendency of a particular solvent to promote ionization of an uncharged solute.

ionizing radiation *or* **ionising radiation** any radiation, corpuscular or electromagnetic, that is capable of causing **ionization** (directly or indirectly) of matter through which it passes. For ionization to occur, the kinetic or photon energy, respectively, must be greater than the **ionization energy** of the irradiated substance. Ultraviolet radiation, X-radiation, alpha particles, and high-energy electrons (including beta particles) are more effective than gamma radiation or neutrons. It is commonly known simply as radiation.

ionogen 1 any compound that can dissociate into ions in a suitable environment; an electrolyte. **2** any atom or group that is capable of becoming ionized chemically. —**ionogenic** *adj.*

ionography *an alternative name for* **zone electrophoresis**.

ionomycin a nonfluorescent antibiotic ionophore derived from *Streptomyces conglobatus*. It is highly specific for divalent cations and exhibits greater selectivity for Ca^{2+} over Mg^{2+} than **A23187** (calcimycin). It complexes with Ca^{2+} between pH 7 and 9.5 with intense UV absorption, and thus may be used as a carrier of Ca^{2+} and for measurement of cytoplasmic Ca^{2+} concentration.

ionone either of two terpene compounds, α-ionone and β-ionone, found in a number of plants. β-Ionone is an intermediate in the synthesis of vitamin A; its odour is reminiscent of cedarwood or, in dilute alcohol solution, of violets.



α-ionone



β-ionone

ionophore *or* **ionophorous agent** any member of a varied group of both natural and synthetic substances, cyclic or linear and of greatly differing relative molecular masses, that are capable of binding metal ions in solution and transporting them across lipid barriers in natural or artificial membranes. They may be classed as **cage carriers**, when the ionophore surrounds the metal ion during transport, or as **channel carriers**, when the ionophore forms an ion-conducting pore in the membrane. —**ionophorous** *or* **ionophoric** *adj.*

ionophoresis **electrophoresis**, especially of relatively small ions. *See also* **iontophoresis**.

ionotropic describing a type of receptor that mediates its effects by regulating ion channels, in distinction from receptors that act by regulating enzymes such as adenylate cyclase or inositide-specific phospholipase C. *Compare* **metabotropic**. *See also* **excitatory amino-acid receptor**.

ion pair a pair of oppositely charged ions held together by coulombic attraction. *See also* **ionic bond**.

ion product *or (sometimes)* **ionic product** *symbol*: K_i; a measure of the tendency of an amphiprotic solvent, XH, to take up or to lose a hydron in the reaction:

$$\mathrm{XH + XH = XH_2^+ + X^-}.$$

In such a reaction, $K_\mathrm{i} = a_{\mathrm{XH_2^+}} \times a_{\mathrm{X^-}}$ where $a_{\mathrm{XH_2^+}}$ and $a_{\mathrm{X^-}}$ are the activities of $\mathrm{XH_2^+}$ and $\mathrm{X^-}$, respectively. The ion product of water, K_W, is given by

$$K_\mathrm{W} = a_{\mathrm{H_3O^+}} \times a_{\mathrm{OH^-}}; K_\mathrm{W} \approx 1 \times 10^{-14}\ \mathrm{mol^2\ dm^{-6}}\ \text{at } 25°\mathrm{C}.$$

It has a large positive temperature coefficient.

ion pump a **transporter** that actively transports ions across a membrane against an **electrochemical potential**. *See* **active transport**.

ion-selective electrode *or* **ion-selective microelectrode** any electrode (or microelectrode) whose potential responds in a reproducible manner to changes in the concentration (strictly, in the activity) of a specific kind of ion in the solution in which the electrode is immersed and that is insensitive, or essentially so, to changes in the concentrations (strictly, in the activities) of all other kinds of ion in the solution. The electrode has at its surface a thin membrane of electrically conducting material, separating the internal and external solutions, across which an electric potential difference develops. The membrane consists of or contains an electroactive material responsive to the ions to be determined.

iontophoresis **1** the introduction of drugs and other substances through plasma membranes of cultured cells by the transfer of ions brought about by the application of a small electrical potential through electrodes placed on the membrane. **2** *a less common word for* **ionophoresis**.

iota *symbol*: ι (lower case) *or* Ι (upper case); the ninth letter of the Greek alphabet. For uses *see* **Appendix A**.

iotatoxin any of a family of peptidic pore-forming toxins of 150–800 amino acid residues, permitting the passage of small molecules across membranes. Iotatoxins are produced by *Clostridium perfringens*. They belong to the TC 1.C.42 family.

IP **1** *or* **i.p.** *abbr. for* intraperitoneal *or* intraperitoneally. **2** *abbr. for* Internet protocal. *See* **protocol**.

IP$_2$ *abbr. for* 1D-*myo*-inositol 3,4-bisphosphate.

IP$_3$ *abbr. for* 1D-*myo*-inositol 1,3,4- (or 1,4,5-) trisphosphate.

IP$_4$ *abbr. for* 1D-*myo*-inositol 1,3,4,5-tetrakisphosphate.

IP address a unique software address for an Internet computer. Although actually a binary number it is usually represented in dotted decimal notation, e.g. '130.88.203.71'. Associated with this is a 'named' version (e.g. www.oup.co.uk corresponding to the dotted decimal address above at the time of writing). The conventions for named addresses include a two-letter abbreviation for a country (e.g. uk for the United Kingdom, ca for Canada, in for India, de for Germany) except for addresses in the USA: because IP is American, the default country is the USA. The 'co' in the example above stands for 'commercial'; other possibilities include ac (academic), gov (government), or org (organization). In the USA the corresponding abbreviations are all of three letters (com for commercial, edu for educational, mil for military; org and gov are also used in the USA). Some countries (e.g. Germany) do not usually have this field.

ipecacuanha *or* **ipecac** the dried root of the South American shrub, *Cephaelis ipecacuanha*; it contains the alkaloids **cephaeline** and **emetine**. Ipecacuanha preparations are used as emetics and expectorants.

IPP *abbr. for* Δ^3-isopentenyl pyrophosphate. This compound is now preferably called isopentenyl diphosphate (*abbr.*: IDP).

iPr *symbol for* the isopropyl group, $\mathrm{(CH_3)_2CH}$– (alternative to $\mathrm{Pr^i}$).

IP$_3$ receptor a receptor/$\mathrm{Ca^{2+}}$ channel of the endoplasmic reticulum (ER). On binding of inositol 1,4,5-trisphosphate ($\mathrm{IP_3}$), released by the action of phospholipase C from phosphatidyl inositol 3,4-bisphosphate on the inner leaflet of the plasma membrane, the channel opens to release $\mathrm{Ca^{2+}}$ ions from the ER lumen into the cytosol. The receptor's subunits each contain six transmembrane segments. Homer1 mediates the effect of ligand binding to metabotropic glutamate receptors on the $\mathrm{IP_3}$ receptor.

iproniazid 1-isonicotinoyl-2-isopropylhydrazine; a derivative of **isoniazid** that is a **monoamine oxidase** inhibitor.



Ips *symbol for* the pipsyl group.

IPTG *abbr. for* isopropyl *β*-D-thiogalactoside; a gratuitous inducer of the *lac* operon in *E. coli*.

IPTS *abbr. for* International Practical Temperature Scale.

Ir *symbol for* iridium.

IR **1** *or* **i.r.** *abbr. for* infrared (radiation). **2** *abbr. for* inverted repeat. **3** *abbr. for* information retrieval.

IRAK *abbr. for* IL-1 receptor-associated kinase; a human cytosolic serine/threonine protein kinase of 752 amino acids that binds to liganded interleukin 1 (IL-1) receptor. Its function is unknown.

IRE *abbr. for* iron response element.

I$_1$, I$_2$ receptors *see* **imidazoline receptor**.

IREG *abbr. for* iron-regulated transporter. *See* **ferroportin**.

IRES *abbr. for* internal ribosome entry site; a sequence found immediately upstream from a cistron in polycistronic mRNA – such as produced by transcription of encephalomyocarditis and other viral genomes – that allows ribosomes to initiate translation from a secondary site within the transcript rather than assembling at the 5′ cap, as is usual with the translation of eukaryotic mRNAs.

IRG *abbr. for* immunoreactive glucagon.

Ir genes the genes, including those within the **MHC**, that together determine the overall level of immune response to a given **antigen**.

IRMA *abbr. for* immunoradiometric assay.

iron *symbol*: Fe; a metallic element of group 8 of the IUPAC **periodic table**; proton number 26; natural iron has a relative atomic mass of 55.847 and is a mixture of stable nuclides of nucleon numbers 54 (5.8 atom per cent), 56 (91.7 atom per cent), 57 (2.2 atom per cent), and 58 (0.3 atom per cent). About 12 artificial radioactive nuclides are known; of these, **iron-59** is the one most widely used in biochemistry and molecular biology. Iron is a **transition element** and hence forms ionic salts and numerous complexes in the oxidation states +2, i.e. iron(II) (ferrous iron), or +3, i.e. iron(III) (ferric iron). Iron is one of the most important elements in biology; it is essential in substantial quantities to all cellular organisms from bacteria to mammals, particularly for the synthesis of hemoproteins such as **cytochromes**, **hemoglobins** and related proteins, **myoglobin**, **catalase**, and some **peroxidases**. Important iron-transport proteins include **ferritin** and **transferrin**; iron is taken up into mammalian cells, bound to transferrin, by the **transferrin receptor**. There is no physiological excretory mechanism for iron, but it is lost from females during menstruation.

iron-59 the artificial radioactive nuclide $^{59}_{26}\mathrm{Fe}$. It decays to the stable nuclide cobalt-59 with emission of a beta particle (i.e. an electron) in two moderate-energy ranges (0.27 MeV max., 48%, and 0.48

MeV max., 51%) plus gamma radiation of various energies (mainly 1.10 MeV, 56%, and 1.29 MeV, 43%). It has a half-life of 44.5 days.

iron hydrogenase *abbr*.: [Fe]- or [FeFe]-hydrogenase; any of a family of hydrogenases (EC 1.12.) present in some bacteria, anaerobic fungi, ciliates, flagellates, and green algae, within the cytosol, the cell membrane, or in hydrogenosomes. Two nonhomologous classes are recognized: (1) hydrogenases containing an H cluster comprising a dimer of iron atoms linked to a [4Fe-4S] cluster; and (2) hydrogenases containing a single iron atom.

iron–molybdenum cofactor *abbr*.: FeMo-co; *see* ***nif***, **nitrogenase**.

iron overload a condition of humans in which iron is taken up in excess over a prolonged period. As there is no excretory mechanism for iron, it accumulates in Kupffer cells in the liver as **hemosiderin**, a form of **ferritin** complexed with other proteins and iron. The condition is known as **hemosiderosis**. It also occurs as a result of repeated blood transfusions, e.g. in treatment for the hemoglobinopathies. A form of the condition is referred to as **Bantu siderosis**, being very prevalent in the Bantu people of southern Africa; it was formerly thought to be always caused by use of cast-iron vessels for cooking, but in some families a hereditary susceptibility has been found.

iron-regulated transporter *abbr*.: IREG; *an alternative name for* **ferroportin**.

iron regulatory protein *abbr*.: IRP; a cytoplasmic protein that binds an iron-response element present in mRNAs for proteins involved in iron metabolism.

iron response element *or* **iron regulatory element** *abbr*.: IRE; a base sequence in eukaryotic 5′ or 3′ untranslated regions of mRNAs, that either blocks translation or enhances stability of the mRNA for proteins involved in iron metabolism (e.g. ferritin, transferrin receptor). The IRE is modulated by an iron regulatory protein that binds to it.

iron–sulfur cluster a unit comprising two or more iron atoms and bridging sulfide ligands in an **iron–sulfur protein**. The recommended designation of a cluster consists of the iron and sulfide content, in square brackets, for example [2Fe–2S], [3Fe–4S]. The possible oxidation levels are indicated by the net charge excluding the ligands, for example: a $[4Fe–4S]^{2+}$; $[4Fe–4S]^{1+}$ (or $[4Fe–4S]^{2+;1+}$) cluster.

iron–sulfur protein *abbr*.: Fe–S protein; any member of a group of proteins to which iron is bound via sulfur-containing ligands (excluding hemoproteins containing iron linked only through axial sulfur ligands). Iron–sulfur proteins are characterized by the possession of non-heme bound iron, as well as one or more of the following: (1) acid-labile sulfur; (2) absorption bands between 300 and 600 nm; (3) the capability of transferring electrons at low redox potential; and (4) paramagnetism in one or more oxidation states. They may be classified as **simple** if they contain one or more Fe–S clusters only (*see* **ferredoxin**, **rubredoxin**), and **complex** where additional active groups, such as flavin, heme, or another metal, are present.

IRP *abbr. for* iron regulatory protein.

irradiate to subject to or treat with electromagnetic radiation or beams of particles. **—irradiation** *n.*

irreversible competitive antagonist *(in pharmacology)* an antagonist for which the dissociation rate is so low that antagonist molecules cannot be replaced by increasing the concentration of an agonist for the same receptor.

irreversible process any process occurring in an isothermal system without change of internal energy but with an increase in entropy.

IRS *abbr. for* insulin receptor substrate.

IS *abbr. for* insertion sequence.

ischemia *or (esp. Brit.)* **ischaemia** a disorder of function caused by insufficient blood flow. Resumption of the blood supply may lead to **ischemia-reperfusion injury** due to the formation of reactive oxygen species.

islet any small group of cells that is structurally distinct from the surrounding tissue, especially the **islets of Langerhans**.

islet-1 *abbr*.: ISL-1; *other name*: insulin-related protein; a transcription factor that is expressed during vertebrate embryogenesis in several neuronal and other cell types (including pancreatic B cells). It contains a homology region of 50–60 amino acids, called LIM, that is also present in Lin-II ISL-1, and Mec-3 of *Caenorhabditis elegans*. It forms a double zinc finger and may be involved in protein, rather than DNA, binding.

islet-activating protein *abbr*.: IAP; *a former name for* **pertussis toxin** (so-called because it stimulates release of insulin from the islets of Langerhans).

islets of Langerhans *or (sometimes)* **islands of Langerhans** *or* **pancreatic islets** the numerous small, spherical or oval, highly vascular clusters of endocrine cells that lie scattered throughout the acinar (i.e. exocrine) tissue of the pancreas of gnathostome (i.e. jaw-bearing) vertebrates and are readily distinguishable microscopically from it. The normal adult human pancreas contains about 2 million islets, which together comprise under 2% of its total volume. Islets commonly consist of three main types of cells, all granule-containing: the glucagon-secreting **A cells**; the insulin-secreting **B cells**; and the somatostatin-secreting **D cells**. Some other types of hormone-secreting cells may be present also. [After Paul Langerhans (1847–88), German physician and anatomist, who first described such clusters of cells (1869).]

iso+ *or (sometimes before a vowel)* **is+** *comb. form* **1** equal, the same, uniform, homogeneous. *Compare* **allo+** (def. 1), **homo+** (def. 1), **hetero+** (def. 1), **xeno+** (def. 1). **2** *(in immunology and genetics)* **a** in or of some individual or ones that are genetically identical (e.g. **isogenic**). **b** in or of another, genetically differing individual of the same species (e.g. **isoantigen**); **allo+** (def. 2) is now usually preferred. **c** in or of all normal individuals of the same species (e.g. **isotypic**). *Compare* **allo+** (def. 2), **hetero+** (def. 2), **homo+** (def. 2), **xeno+** (def. 2). **3** *(in chemical nomenclature)* **a** signifying isomer of (formerly 'iso' was italicized and often hyphenated). **b** *symbol*: i (as a prefix or superscript); signifying the isomer of a straight-chain alkane or alkane derivative that differs only in having a terminal $(CH_3)_2CH–$ group (leucine and isoleucine are exceptions). *Compare* **allo+** (def. 3), **nor+** (def. 1). **4** *(in names of certain classes of macromolecules)* signifying irrespective of location or origin, one of two or more structural variants with the same specificity of activity or action (e.g. **isoacceptor tRNA**, **isohormone**; *see also* **isoenzyme**).

ISO *abbr. for* International Standards Organization.

isoacceptor tRNA *or* **isoaccepting tRNA** any transfer RNA species obtainable from a given organism that can be acylated by the same amino acid; they may differ in their anticodons.

isoagglutinin *other names*: isohemagglutinin; isoantibody; a naturally occurring IgM antibody that is specific for one of the ABO blood group antigens on human erythrocytes. Type O blood has antibodies to A and B antigens; type A has antibodies to B antigen; type B has antibodies to A antigens; and type AB has neither anti-A nor anti-B antibodies.The presence of isoagglutinins in blood explains the disastrous effect of incompatible blood transfusions.

isoalloxazine benzo[*g*]pteridine-2,4(1H,3H)dione; the hypothetical tricyclic parent compound of any N^{10}-substituted alloxazine in riboflavin, flavin mononucleotide, or flavin-adenine dinucleotide.



isoamylase EC 3.2.1.68; *other name*: debranching enzyme; an enzyme that catalyses the hydrolysis of 1,6-α-D-glucosidic branch linkages in glycogen, amylopectin, and their *β*-limit dextrins. It does not attack pullulan, and is limited in action on *α*-limit dextrins.

isoantibody any antibody formed in one individual in response to an antigen derived from another individual of the same species. *See also* **isoagglutinin**.

isoantigen any antigen occurring in an individual that is capable of eliciting an immune response in genetically different individuals of the same species but not in the individual itself.

isoasparagine *the trivial name for* the *α*-amide of aspartic acid, aspartic 1-amide; *β*-aminosuccinamic acid; 3-amino-3-carbamoylpropanoic acid; H_2N–CO–CH(NH_2)–CH_2–COOH; a chiral α-aminoacylamide. L-Isoasparagine (*symbol*: Asp-NH_2) can occur as an N-terminal amidated residue of proteins. *Compare* **asparagine**.

isoasparaginyl the acyl group, H_2N–CO–CH(NH_2)– CH_2–CO–, derived from **isoasparagine**. *Compare* **asparaginyl**.

isoaspartyl *the former name for* **β-aspartyl**.

isobar **1** any of two or more nuclides having the same mass number (nucleon number) but different atomic numbers (proton numbers) and hence of differing chemical properties. *See also* **heterotope**. **2** any curve or equation relating quantities measured at the same pressure; any line joining points on a graph or map that have equal pressures. **—isobaric** *adj.*

isobutylmethylxanthine *abbr.*: IBMX; 3-isobutyl-1-methylxanthine; an inhibitor of **cyclic AMP phosphodiesterase**; it raises cyclic AMP levels in cells and tissues.



isocaloric *(of foodstuffs)* having the same **calorific value**.

isochore a stretch of DNA that is over 300 kb long and has a relatively homogeneous GC composition.

isochorismate 5-[(1-carboxylatoethenyl)oxy]-6-hydroxy-1,3-cyclohexadiene-1-carboxylate; the dianion of isochorismic acid; an isomer of **chorismate** and an important precursor to some compounds in the **shikimate pathway**.



isochorismic acid

isochromosome any chromosome having homologous, genetically identical arms. It results from abnormal splitting of a chromosome at the centrosome during mitosis so that one arm is lost and the other becomes duplicated.

isocitrate **1** any of the anionic forms of isocitric acid, 1-hydroxy-1,2,3-propanetricarboxylic acid. (1*R*,2*S*)-1-hydroxypropane-1,2,3-tricarboxylate (*also termed* (2*R*,3*S*)-isocitrate or *threo*-D_s-isocitrate) is an important intermediate in the **tricarboxylic-acid cycle** and the **glyoxylate cycle**. **2** any mixture of free isocitric acid and its ionized forms. **3** any (partial or full) salt or ester of isocitric acid.



(1*R*,2*S*)-1-hydroxypropane-1,2,3-tricarboxylate

isocitrate dehydrogenase **1 isocitrate dehydrogenase (NAD$^+$)** EC 1.1.1.41; *other names*: isocitric dehydrogenase; β-ketoglutaric-isocitric carboxylase; an enzyme that catalyses the oxidation of isocitrate to 2-oxoglutarate and CO_2, with reduction of NAD$^+$ to NADH. The isomer of isocitrate involved is (1*R*,2*S*)-1-hydroxypropane-1,2,3-tricarboxylate. In mammalian tissues, this enzyme is localized exclusively in the mitochondria. **2 Isocitrate dehydrogenase (NADP$^+$)** (EC 1.1.1.42); an enzyme that is localized in both mitochondria and cytosol.

[isocitrate dehydrogenase (NADP$^+$)] kinase EC 2.7.1.116; *other names*: isocitrate dehydrogenase kinase/phosphatase (*abbr.*: IDH kinase/phosphatase); an enzyme that catalyses the phosphorylation by ATP of isocitrate dehydrogenase (NADP$^+$) with formation of ADP. The phosphorylated protein is inactive. In *Escherichia coli* a bifunctional enzyme contains this and isocitrate dehydrogenase kinase/phosphatase (EC 3.1.3.–) activities.

isocitrate lyase EC 4.1.3.1; *systematic name*: isocitrate glyoxalate-lyase; an enzyme, present in the glyoxysomes of seeds, that converts (1*R*,2*S*)-1-hydroxypropane-1,2,3-tricarboxylate (the isomer of isocitrate involved) to succinate and glyoxylate. *See* **glyoxylate cycle**.

isocratic *(in chemistry)* describing any chromatographic procedure or separation in which the composition of the eluent is maintained constant. *Compare* **gradient elution**.

isocyanate any organic compound containing the univalent group –N=C=O. *Compare* **cyanate**, **isothiocyanate**.

isocyclic see **homocyclic** (def. 1).

isodalt a type of very-high-resolution two-dimensional electrophoresis system for the analysis of small (1–2 mg) samples of complex mixtures of proteins. It employs isoelectric focusing in cylindrical gels in the first dimension, followed by slab-gel electrophoresis in the presence of sodium dodecyl sulfate in the second dimension. Such systems are considered to be capable of resolving mixtures containing 10^4 or more individual proteins within the range 10–200 kDa.

isodesmosine the 2-(4-amino-4-carboxybutyl)-1-(5-amino- 5-carboxypentyl)-3,5-bis(3-amino-3-carboxypropyl)pyridinium ion; a tetra(α-amino acid) isolated from hydrolysates of the fibrous protein elastin. *See* **desmosine**.



isodiametric **1** *(of cells)* having similar diameters in all planes. **2** *(of a crystal)* having three equal axes.

isodynamic *(in physics)* having equal force or strength.

isoelectric **1** having the same electrical potential; containing or indicating no potential difference. **2** *(of particles or molecular entities)* having no net electric charge.

isoelectric focusing *or* **electrofocusing** *abbr.*: IEF; a technique in which solutes of different isoelectric points are caused to form stationary bands in an electric field, which is superimposed on a (stable) pH gradient, the pH increasing from the anode to the cathode. In practice the pH gradient is most conveniently formed by electrolysing a solution containing a mixture of **carrier ampholytes** of low molecular mass and slightly differing isoelectric points, each of which will move to its isoelectric region in the electric field and remain there.

isoelectric-focusing electrophoresis a separation technique in which electrophoresis is effected in a gel slab at right angles to a preformed, stationary pH gradient generated by isoelectrically focused carrier ampholytes (*see* **isoelectric focusing**).

isoelectric fractionation any technique for fractionating proteins or other ampholytes using **isoelectric focusing**.

isoelectric pH *an alternative term for* **isoelectric point**.

isoelectric point *or* **isoelectric pH** *abbr.*: IEP *or* i.e.p.; *symbol*: pI; the pH of the solution in which a protein or other ampholyte has zero mobility in an electric field; hence the pH at which the protein or other ampholyte has zero net charge, i.e. no charges or an equal number of positive and negative charges including those due to any extraneous ions bound to the ampholyte molecule. The pH value of the isoelectric point may depend on other ions, except hydrogen and hydroxide ions, present in the solution. *Compare* **isoionic point**.

isoelectric precipitation the precipitation of a protein at its **isoelectric point**, at which proteins are generally least soluble. It is useful in the fractionation of mixtures of proteins.

isoelectronic describing two or more chemical entities having the same number of electrons, especially valence electrons. *Compare* **isosteric**.

isoenergetic taking place at constant energy.

isoenzyme *or* **isozyme** any one of the multiple forms of an enzyme arising from a genetically determined difference in primary structure. Isoenzyme is an operational term to denote any one of a group of enzyme proteins with similar catalytic properties but separable by suitable methods, e.g. by electrophoresis, where knowledge of the nature of the multiplicity may be lacking. If the different enzyme proteins are derived from a common gene, then the term 'multiple forms' rather than 'isoenzymes' should be used. The term embraces **allelozyme** and **multilocus enzyme**. *Compare* **interconvertible enzyme**.

isoflavone 7-*O*-glucosyltransferase EC 2.4.1.170; an enzyme that catalyses the reaction between UDPglucose and isoflavone to form isoflavone 7-*O*-*β*-D-glucoside and UDP.

isoflavonoid any of various yellow- or orange-coloured hydroxyl or alkoxyl derivatives of isoflavanone. They are plant pigments, present as glycosides or esters with tannic acid, have no recognized nutritional function, and are rapidly excreted in urine after ingestion. An example is genistein.

isoflurane 2-chloro-2-(difluoromethoxy)-1,1,1-trifluoroethane; a widely used nonflammable volatile anesthetic agent.

isoform any of several multiple forms of the same protein that differ in their primary structure, but retain the same function. They can be produced by different genes or by **alternative splicing** of RNA transcripts from the same gene.

isogeneic *or* **isogenic** describing two or more individuals that possess exactly the same genotype. *See also* **syngeneic**.

isoglucose *see* **high-fructose corn syrup**.

isoglutamine *a trivial name for* the *α*-amide of glutamic acid; glutamic 1-amide; *γ*-aminoglutaramic acid; 4-amino-4-carbamoylbutanoic acid; $H_2N–CO–CH(NH_2)–[CH_2]_2–COOH$; a chiral *α*-amino acylamide. L-Isoglutamine (*symbol*: Glu-NH_2) can occur as an N-terminal amidated residue of proteins. Residues of D-isoglutamine (*symbol*: D-Glu–NH_2) are found in *Staphylococcus aureus* peptidoglycan. *Compare* **glutamine**.

isoglutaminyl the acyl group, $H_2N–CO–CH(NH_2)–[CH_2]_2–CO–$, derived from **isoglutamine**. *Compare* **glutaminyl**.

isoglutamyl *a former name for* **γ-glutamyl**.

isograft *an alternative term for* **syngenic graft**.

isohormone any of two or more structural variants of a polypeptide hormone that have the same hormonal action and are produced within the same organism, or at least within the same species of organism. **—isohormonal** *adj.*

isohydric describing solutions that have the same hydrogen-ion concentration, hydrogen-ion activity, or pH.

isohydric shift the opposing and counterbalancing changes in hydrogen-ion concentration occurring in peripheral tissues when dioxygen leaves the blood and carbon dioxide enters it. The hydration of CO_2 to H_2CO_3, catalysed by erythrocyte carbonic anhydrase, has a tendency to lower the blood pH. This tendency is counteracted in some degree by the simultaneous deoxygenation of hemoglobin; deoxyhemoglobin binds hydrogen ions more strongly than oxyhemoglobin, thus tending to raise the blood pH.

isoionic pH *an alternative name for* **isoionic point**.

isoionic point *or* **isoionic pH** the pH of a solution of a protein or other ampholyte from which all other ions have been removed, except hydrogen and hydroxide ions formed by dissociation of water or of the protein or ampholyte itself. *Compare* **isoelectric point**.

isoionic solution any solution of a protein or other ampholyte that contains no other ions except those arising from dissociation of the solute and the solvent.

isokinetic gradient any concentration and viscosity gradient used in centrifugation that allows particles (molecules) of the same density to sediment at a constant velocity at all distances from the centre of rotation.

isolate 1 to separate (a pure substance, a cell type, or a sample of a subcellular component) from a mixture or from naturally occurring material and then (usually) to characterize it; to separate and put into pure culture (a particular species or strain of a microorganism) from a mixture, sample, or biological specimen. **2** to remove a viable tissue or organ for the purpose of study or experiment. **3** *(in physics)* to disconnect (part of a circuit), or to prevent interaction between (circuits or components). **4** a group of similar microorganisms, especially a pure culture, obtained by isolation for study, experiment, or as an aid to diagnosis; something isolated. **—isolable** *or* **isolatable** *adj.*; **isolability, isolator** *n.*

isolectin any of two or more molecular forms of lectin, of the same origin, apparently with the same biological properties, and of very similar molecular masses, but of differing electrophoretic mobilities. They may be the products of closely related genes, or formed prior to or during isolation. In glycoprotein lectins, their differences may lie in the carbohydrate side chains.

isoleucinate 1 isoleucine anion; the anion, $CH_3–CH_2–CH(CH_3)–CH(NH_2)–COO^–$, derived from **isoleucine**. **2** any salt containing isoleucine anion. **3** any ester of isoleucine.

isoleucine *the trivial name for* *α*-amino-*β*-methylvaleric acid; (2*R**,3*R**)-2-amino-3-methylpentanoic acid; $CH_3–CH_2–CH(CH_3)–CH(NH_2)–COOH$; an *α*-amino acid with two chiral centres. Because molecules of isoleucine possess a second chiral centre, at C-3, in addition to the chiral centre at C-2 common to all *α*-amino acids other than glycine, the enantiomers L-isoleucine, (2*S*,3*S*)-2-amino-3-methylpentanoic acid (*symbol*: I *or* Ile), and D-isoleucine, (2*R*,3*R*)-2-amino-3-methylpentanoic acid (*symbol*: D-Ile *or* DIle), are diastereoisomeric with those of **alloisoleucine**, (2*R**,3*S**)-2-amino-3-methylpentanoic acid. L-isoleucine is a coded amino acid found in peptide linkage in proteins; codon: AUA (not in mitochondria of fruit fly, mammals, or yeast) (anticodon: UAU); AUC or AUU (anticodon: UAG). In mammals, it is an essential dietary amino acid, and is both glucogenic and ketogenic. D-Isoleucine is not known to occur naturally.



L-isoleucine

isoleucine biosynthesis a pathway that commences with formation of *α*-aceto-*α*-hydroxybutyrate (I) from pyruvate and *α*-ketobutyrate (2-oxobutanoate, formed by removal of ammonia from threonine by serine dehydratase). I is converted via *α*,*β*-dihydroxy-*β*-methylvalerate to *α*-keto-*β*-methylvalerate (II). Isoleucine is then formed from II as a result of transamination with glutamate.

isoleucinium isoleucine cation; the cation, $CH_3–CH_2–CH(CH_3)–CH(NH_3^+)–COOH$, derived from **isoleucine**.

isoleucino the alkylamino group, $CH_3–CH_2–CH(CH_3)–CH(COOH)–NH–$, derived from **isoleucine**.

isoleucyl the acyl group, $CH_3–CH_2–CH(CH_3)–CH(NH_2)–CO–$, derived from **isoleucine**.

isoliquivitigenin *see* **chalcone**.

isolog *the US spelling of* **isologue**.

isologous 1 of, relating to, or being two or more closely related chemical compounds in a series whose successive members differ in composition in a regular manner, other than by a difference of one methylene group. The term is now applied especially to compounds that have different atoms of the same valency at one or more positions in the molecule but are otherwise structurally identical, e.g. methionine and selenomethionine. **2** *an alternative term for* **isogeneic**.

isologous association *or* **isologous binding** any association between two identical protein subunits (i.e., **protomers**) in which the **domain of bonding** comprises two identical **binding sets**.

isologue *or (US)* **isolog** any of two or more **isologous** (def. 1) compounds.

isology the state or condition of being **isologous** (def. 1); chemical kinship among molecules or compounds.

isomaltase EC 3.2.1.10; *recommended name*: oligo-1,6-glucosidase; *systematic name*: dextrin 6-*α*-D-glucanohydrolase. An enzyme that hydrolyses 1,6-α-D-glucosidic bonds in dextrins and isomaltose produced after α-amylase degradation of starch and glycogen. The enzyme from intestinal mucosa also catalyses the reaction of EC 3.2.1.48 (*see* **sucrase**).

isomaltose the disaccharide 6-*O*-*α*-D-glucopyranosyl-D-glucose; it exists as the branching unit in **amylopectin**, **glycogen**, and some bacterial **dextrans**. *Compare* **maltose**.



isomaltulose the disaccharide 6-*O*-*α*-D-glucopyranosyl-D-fructofuranose.

isomer 1 *(in chemistry)* **molecular isomer** any of two or more compounds that have identical molecular formulas but differ in the nature of bonding of their atoms (**constitutional isomers**) or in the arrangement of their atoms in space (**stereoisomers**). **2** *(in physics)* **nuclear isomer** any of two or more nuclides that have the same proton number and the same mass (nucleon) number but different energy states.

isomerase any enzyme of EC class 5 that catalyses geometric or structural changes within one molecule. According to the type of isomeric change they catalyse, they may be called racemases or epimerases (EC subclass 5.1); *cis–trans*-isomerases (EC subclass 5.2); intramolecular oxidoreductases (EC subclass 5.3); intramolecular transferases (mutases) (EC subclass 5.4); or intramolecular lyases (EC subclass 5.5); other isomerases are placed in EC subclass 5.99.

isomeric of or pertaining to an **isomer**; pertaining to the phenomenon of, or displaying, **isomerism**.

isomeric state any of the states of an atomic nucleus having a different energy and observable half-life from those of other states of the same nucleus; the condition of being an **isomer** (def. 2).

isomeric transition *abbr.*: IT; the change of one nuclear isomer (*see* **isomer** (def. 2)) into another without change in either proton number (atomic number) or nucleon number (mass number), energy being lost in the form of gamma radiation; e.g. the decay of the metastable nuclide technetium-99m (half-life 6 h) to the unstable nuclide technetium-99 (half-life 2.1 × 10^5 years), which in turn decays to ruthenium-99 with emission of an electron.

isomerism the phenomenon of the existence of **isomers** in general, or the occurrence of molecular or nuclear isomers in a particular instance.

isomerization *or* **isomerisation** the act of changing or the process of change of one molecular isomer into another one. —**isomerize** *or* **isomerise** *vb.*

isometric 1 having identical dimensions. **2** *(in physiology)* of or pertaining to a contraction of a muscle that does not cause shortening of the muscle. **3** *(in crystallography)* having three mutually perpendicular axes of equal length; cubic.

isomorph a substance or organism that is **isomorphic** (def. 1) to another substance or organism.

isomorphic 1 *or* **isomorphous** of identical or similar form, shape, or structure. **2** describing a type of alternation of generations in which morphologically identical generations occur in both diploid and haploid phases. It occurs mainly in algae. *Compare* **heteromorphic**.

isomorphism 1 *(in biology)* similarity of form in organisms of different ancestry. **2** *(in chemistry)* similarity of crystalline form and structure between substances of similar composition or substances that can form a more or less continuous series of solid solutions.

isomorphous 1 *an alternative term for* **isomorphic** (def. 1). **2** displaying **isomorphism** (esp. def. 2).

isomorphous replacement method a method used to solve the phase problem in **X-ray diffraction** analysis of macromolecular structures. It involves combining one or more **heavy atoms** (def. 2) (which are strong scatterers) in a specific manner with the macromolecule in question and investigating their effects on the diffraction pattern. The heavy atom must not modify either the conformation or the crystal form of the macromolecule, i.e. the replacement must be isomorphous.

isoniazid 4-pyridinecarboxylic acid hydrazide; an antitubercular drug that may act by inhibiting the synthesis of the mycolic acids that are vital for the construction of the cell wall of the pathogen, *Mycobacterium tuberculosis*. Like related hydrazides it is highly hepatotoxic and no longer used. Its euphoric side effects led to the discovery of monoamine oxidase inhibitors.



isoosmotic *a variant spelling of* **isosmotic**.

isopartitive *(in chromatography)* describing two or more solvents that bring about similar partitions of a given substance between the solvent and the stationary phase and hence result in R_f values that are the same or nearly so.

isopentenyl *the trivial name for* 3-methylbut-3-enyl, $CH_2{=}C(CH_3)–CH_2–CH_2–$, the alkenyl group formally derived from isopentenyl alcohol (i.e. 3-methylbut-3-en-1-ol) by loss of its hydroxyl group. *Compare* **prenyl**.

isopentenyl diphosphate *abbr.*: IDP; *formerly called* Δ^3-isopentenyl pyrophosphate (*abbr.*: IPP); an isomer of dimethylallyl diphosphate and the key precursor of all **isoprenoids** (def. 2). *See also* **dimethylallyl*trans*transferase**, **isopentenyl-diphosphate *Δ*-isomerase**, **isoprene rule**.



isopentenyl-diphosphate *Δ*-isomerase EC 5.3.3.2; *systematic name*: isopentenyl diphosphate Δ^3–Δ^2-isomerase; *other name*: IPP isomerase. An enzyme in the pathway for the synthesis of cholesterol, terpenes, and prenyl groups; it catalyses the reversible reaction:

isopentenyl diphosphate = dimethylallyl diphosphate.

isopeptidase any peptidase catalysing the cleavage of an **isopeptide bond**.

isopeptide bond any peptide bond other than a **eupeptide bond**, i.e. any amide bond formed between a carboxyl group of one amino-acid molecule or residue and an amino group of another, where either group occupies a position other than *α* (or both do so). Examples include peptide bonds formed from the *β*-carboxyl group of aspartic acid, the *γ*-carboxyl group of glutamate from the *ε*-amino group of lysine, and from either the carboxyl group or the amino group of *β*-alanine.

isopiestic of, pertaining to, or characterized by equal pressures.

isopiestic vapour pressure method a method for the determination of the activity of water in a solution of a nonvolatile solute. The solution in question is equilibrated with a reference solution containing a nonvolatile solute for which the activity of water at different solute concentrations has been determined with high precision. The two solutions are placed in an enclosure at constant temperature until their vapour pressures are equal, i.e. the activity of water in both solutions is equal. They are then analysed for their solute contents, from which the activity of water in both of them can be calculated.

isoprenaline *an alternative name for* **isoproterenol**.

isoprene 2-methylbuta-1,3-diene; $CH_2{=}C(CH_3){-}CH{=}CH_2$; a liquid hydrocarbon hemiterpene isolated from products of the pyrolysis of natural rubber, turpentine, etc., and widespread in plants although generally found only in extremely small amounts.

isoprene residue the branched-chain bivalent group, 3-methyl-2-butenylene; 3-methylbut-2-en-1,4-diyl; $-CH_2{-}C(CH_3){=}CH{-}CH_2{-}$. It is formally derived by bond rearrangement from **isoprene** and constitutes the repeating unit of the molecular structures of prenols and many other isoprenoids.

isoprene rule a rule, formulated by Wallach in 1887, that stated that many natural products are built up from isoprene carbon skeletons. It was modified to the **biogenetic isoprene rule** by Croatian-born Swiss chemist Leopold Ružička (1887–1976), who proposed that all terpenoids, steroids, etc. are synthesized from a precursor called 'active isoprene'. This precursor is now known to be **isopentenyl diphosphate**.

isoprene unit *(in an isoprenoid)* an **isoprene residue** or any branched five-carbon-atom moiety formally derived from an isoprene residue by chemical modification, e.g. by hydrogenation, hydroxylation, etc. It represents isopentenyl alcohol (i.e. 3-methylbut-3-en-1-ol), the diphosphate of which is the universal biogenetic precursor of isoprenoids.

isoprenoid 1 of, pertaining to, or being **isoprene** and its chemical relatives; having a molecular structure composed of, containing, or derived from linked **isoprene residues**. 2 any isoprenoid compound. Isoprenoids comprise a large and varied family of natural products, including carotenoids, phytol, prenols, rubber, steroids, terpenoids, and tocopherols. Many substances contain both isoprenoid and nonisoprenoid components, e.g. the vitamins K.

isoprenyltransferase any of the enzymes within subclass EC 2.5.1, existing as α–β heterodimers, that add C_{15} or C_{20} carbon chains by **prenylation** near the carboxyl terminus of proteins. Examples include the nuclear lamins and Ras.

isopropyl *symbol*: iPr *or* Pr^i; the alkyl group $(CH_3)_2CH-$, derived from propane. *Compare* **propyl**.

isopropylmalate either of the isomeric substances 2-isopropylmalate (i.e. 3-carboxy-3-hydroxy-4-methylpentanoate) or 3-isopropylmalate (i.e. 3-carboxy-2-hydroxy-4-methylpentanoate); they are enzymatically interconvertible intermediates in the biosynthesis of leucine in plants. *See also* **3-isopropylmalate dehydratase**.



(2*R*,3*S*)-3-isopropylmalic acid

3-isopropylmalate dehydratase EC 4.2.1.33; *systematic name*: 3-isopropylmalate hydro-lyase; an iron–sulfur protein, containing a [4Fe-4S] cluster, that catalyses the isomerization of 3-isopropylmalate to 2-isopropylmalate, by dehydration to 2-isopropylmaleate and rehydration to generate the isomer, in the pathway of L-leucine biosynthesis in plants. *See* **leucine and valine biosynthesis**.

3-isopropylmalate dehydrogenase EC 1.1.1.85; *systematic name*: 3-carboxy-2-hydroxy-4-methylpentanoate:NAD$^+$ oxidoreductase; an enzyme that catalyses the oxidation of 3-**isopropylmalate** by NAD$^+$ (followed by loss of CO_2) to 4-methyl-2-oxopentanoate, in the pathway of L-leucine biosynthesis in plants. *See* **leucine and valine biosynthesis**.

2-isopropylmalate synthase EC 4.1.3.12; *systematic name*: 3-carboxy-3-hydroxy-4-methylpentanoate 3-methyl-2-oxobutanoate-lyase (CoA-acetylating); an enzyme that condenses acetyl-CoA with 3-methyl-2-oxobutanoate to form 2-isopropylmalate, in the pathway of L-leucine biosynthesis in plants. *See* **leucine and valine biosynthesis**.

isopropyl *β*-thiogalactoside *abbr.*: IPTG; isopropyl *β*-D-1-thiogalactopyranoside; an inducer of *β*-galactosidase in bacteria; it also induces the *lac* operon by binding and inactivating the *lac* repressor. It is used in cloning techniques to enhance expression of DNA cloned into vectors containing the *lac* operon.



isoproterenol *or* **isoprenaline** 3,4-dihydroxy-*α*-[(isopropylamino)methyl]benzyl alcohol; the synthetic isopropyl analogue of epinephrine. It is a selective agonist of β adrenoceptors, but does not discriminate between $β_1$ and $β_2$ subtypes.



isopycnic of, pertaining to, or characterized by equal densities.

isopycnic banding the formation during **isopycnic centrifugation** of one or more bands composed of molecules that have the same density as that of the solvent at that position in the gradient; the process of separating or purifying substances by forming such bands.

isopycnic centrifugation *or* **band centrifugation** *or* **density-gradient centrifugation** *or* **density-gradient sedimentation equilibrium** a separation technique in which macromolecules are subjected to a centrifugal field in a solvent containing a density gradient. The macromolecules will sediment or float and arrange themselves in bands (isopycnic bands) in the column of solvent where the density of the solvent is the same as that of the particular macromolecule. *Compare* **isokinetic gradient**.

isoquinoline 2-benzazine; benzo[*c*]pyridine; a bicyclic, aromatic, nitrogen-containing compound. Many alkaloids contain an isoquinoline ring system.



isoquinolinesulfonylmethylpiperazine *see* **H7**.

isosbestic point any wavelength at which the molar **absorption coefficients** of two or more particular chemical species are equal, i.e. their absorption spectra intersect. All mixtures (or solutions) of two or more such species, having the same total concentration, will then exhibit absorption spectra that pass through the isosbestic point, provided the species do not interact.

isoschizomer any of two or more restriction endonucleases from different sources that recognize the same sequence in a DNA molecule and display identical specificity of cleavage within that sequence. The term is sometimes extended to include those enzymes that cleave at different sites within the sequence recognized, or that respond to methyl groups on different bases in the sequence. Examples are *Msp*I and *Hpa*II, both of which cleave the unmethylated sequence CCGG. **—isoschizomeric** *adj.*

isosemantic substitution the incorporation of an amino-acid residue into its normal position in a polypeptide chain in response to a mutated but synonymous codon.

isosmotic *or* **isoosmotic** *(of two or more solutions)* having equal osmotic pressure; having the same osmotic pressure as another solution. *See also* **isotonic** (def. 2).

isostere *or* **isoster** any of two or more **isosteric** chemical species.

isosteric *(of two or more chemical species)* having the same, or similar, shape and size, e.g. L-threonine and L-valine; having the same number of valence electrons arranged in a similar manner. *Compare* **isoelectronic**. **—isosterism** *n.*

isotachophoresis *or* **isotachoelectrophoresis** *or* **displacement electrophoresis** a method for separating ion species in which all ions under observation are given the same migration velocity; moreover, they all have the same sign and a common counterion. The sample ions are introduced as a zone between a leading electrolyte, whose ions have a higher mobility than any of the sample ions, and a terminating electrolyte, whose ions have a lower mobility than any of the sample ions.

isotactic of, relating to, or having stereochemical regularity in the repeating units of a polymer. *Compare* **syndyotactic**.

isotherm *or* **isothermal** any line on a graph, or diagram, that connects points of equal temperature.

isothermal 1 *(of a process or reaction)* occurring at constant temperature. **2** of or pertaining to an isotherm. **3** *an alternative name for* isotherm.

isothiocyanate any organic compound containing the monovalent group –N=C=S. *Compare* **thiocyanate**.

isotocin *or (formerly)* **isotocine** [Ser^4,Ile^8]oxytocin; the somewhat less potent structural variant of **oxytocin**. It is present in many bony fish in place of oxytocin, hence it is sometimes known as **ichthyotocin**. *See also* **mesotocin**.

isotone any of two or more nuclides having the same number of neutrons but, usually, different numbers of protons and therefore differing in atomic number.

isotonic 1 of, or having the same tension; used especially of muscular contraction occurring in the absence of significant resistance and accompanied by marked shortening of the muscle fibres. *Compare* **isometric** (def. 2). **2** having the same osmotic pressure as some particular solution, especially one in a cell or body fluid; **isosmotic**. *Compare* **hypertonic**, **hypotonic**. **3** of, relating to, or being an **isotone** or isotones.

isotonically under **isotonic** (def. 1) conditions.

isotonicity the state or quality of being **isotonic** (def. 2); the degree of osmotic pressure.

isotope any of two or more **nuclides** that have the same **proton number**, i.e. that are nuclides of the same chemical element and thus display qualitatively the same chemical properties (for quantitative differences, *see* **isotope effect**). Isotopes with a given proton number usually have different **nucleon numbers** and thus characteristically usually have different relative atomic masses. In some instances, however, two isotopes of an element are isomeric, i.e. they have the same nucleon number (and hence the same relative atomic mass) but differ instead in their nuclear energy levels, the isotope with the higher level being **metastable** (def. 3). For the majority of elements, isotopes occur naturally and at more or less constant relative abundances; additional isotopes can be produced artificially. In general, any given element possesses both stable and unstable isotopes, although there are no stable ones for elements of high proton number; conversely, the naturally occurring isotopes of elements of lower proton number are, with a few exceptions, all stable. Metastable and unstable isotopes undergo radiative decay and are collectively termed radioactive isotopes, or radioisotopes. (*Note*: In common parlance the term isotope is often used loosely as a synonym of nuclide irrespective of its proton number.) *Compare* **heterotope**, **isobar**, **isotone**. **—isotopic**, *adj.*

isotope abundance the number of atoms of a particular isotope in a mixture of the isotopes of an element in a sample, expressed as a percentage of all the atoms of that element in the sample. *Compare* **isotope ratio**.

isotope dilution analysis an accurate method for measuring the concentration of an element, or a compound of that element, in a system by adding a known amount of a different isotope, or a labelled compound, and then measuring its concentration in a sample withdrawn from the system after mixing.

isotope effect any variation in some chemical, physicochemical, or biochemical property of a molecular entity that is detectable on isotopic substitution of an atom or atoms of the entity, e.g. variation in reaction rate, in chromatographic mobility, or in binding to macromolecules. For a given pair of isotopes, 'light' and 'heavy', the effect may be expressed quantitatively either (in the **kinetic isotope effect**) as the ratio of the rate constants, $k_{\text{light}}/k_{\text{heavy}}$, or (in the **equilibrium isotope effect**) as the ratio of the equilibrium constants, $K_{\text{light}}/K_{\text{heavy}}$, for two chemical reactions that differ only in the isotopic composition of one or more of their otherwise chemically identical components. The magnitude of the effect depends on the relative difference in atomic mass of the isotopes in question; thus it is the greatest by far for isotopes of hydrogen.

isotope exchange any chemical reaction in which the reactants and products are chemically identical but of different isotopic composition. In such a reaction the isotope distribution tends towards equilibrium.

isotope farming *an informal term sometimes used to describe* biological techniques for the large-scale preparation, usually for sale, of radioisotope-labelled biochemicals, especially when a number of such compounds are obtainable in the same operation, e.g. the simultaneous preparation of a number of ^{14}C-labelled compounds from $^{14}CO_2$ by photosynthesis in whole leaves or whole plants.

isotope ratio *or* **isotopic ratio** the ratio between the numbers of atoms of any two isotopes of a given element in a particular preparation, sample, or substance. *Compare* **isotope abundance**.

isotope-ratio mass spectrometer a **mass spectrometer** designed specifically for the determination of **isotope ratios**.

isotopic 1 of, relating to, or being an **isotope** or isotopes. **2** being or containing a less common or artificial isotope, especially as a label or tracer. **3** *(especially of techniques)* using or depending on isotopes. **—isotopically** *adv.*

isotopically coded affinity tag *abbr.*: ICAT; a reagent used for quantitation of differential protein expression. The proteins in two samples to be compared are labelled with a reagent containing a thiol-specific reactive group that binds to the side chain of reduced cysteines, with a linker group that is either deuterated or nondeuterated, and a group such as biotin that allows affinity isolation of the ICAT-labelled peptides from complex mixtures using affinity chromatography. The isolated and tagged peptides are analysed by mass spectrometry.

isotopy the phenomenon of the existence of isotopes in general; or the fact or condition of being isotopic in a particular instance.

isotropic *or* **isotropous 1** *(in physics)*: exhibiting uniform properties when measured along axes in all directions. *Compare* **anisotropic**. **2** *(in biology)* not having predetermined axes of growth. **—isotropically** *adv.*; **isotropy** *or* **isotropism** *n.*

isotropic band *or* **I-band** *see* **sarcomere**.

isotropic motion the random tumbling of a chemical species about its three axes.

isotropous *an alternative word for* **isotropic**.

isotypic specificity any antigenic specificity that is the same in a given protein in all normal individuals of the same animal species. For example anti-rabbit gamma globulins prepared in another animal species do not distinguish between gamma globulins from different rabbits.

isotypic variation structural variability of any one antigen that is common to all members of the same species.

isovaleric acidemia a hereditary metabolic disease of humans, due to various mutations in **isovaleryl-CoA dehydrogenase.** Of variable severity, it is characterized by metabolic acidosis and excessive urinary excretion of isovaleric acid or isovaleryl conjugates.

isovaleryl-CoA dehydrogenase *abbr.*: IVD; EC 1.3.99.10; a mitochondrial matrix flavoprotein enzyme of the pathway for degradation of leucine. It catalyses the oxidation of 3-methylbutanoyl-CoA to 3-methylbut-2-enoyl-CoA. The flavin is FAD.

isozyme *an alternative word for* **isoenzyme**.

isozymogen any precursor of an isozyme.

ISSD *abbr. for* infantile sialic acid storage disease.

ISWI *abbr. for* initiation switch; an ATPase protein component of **NURF** that with GAGA factor initiates expression of the Hsp70 gene in *Drosophila*.

IT *abbr. for* isometric transition.

itaconate methylenesuccinate; methylenebutanedioate; the dianion $^{-}OOC–CH_2–C(=CH_2)–COO^{-}$; a constitutional isomer of **citraconate**. It is a metabolite of strains of *Aspergillus terreus*, which can yield it in large amounts by decarboxylation of *cis*-aconitate. It is a comparatively reactive compound, with properties useful in the manufacture of synthetic resins and plastics.

ITAM *abbr. for* immunoreceptor tyrosine-based activation motif; a consensus sequence for src-family tyrosine kinases. ITAMs are found in the cytoplasmic domains of several signalling molecules including the signal transduction units of lymphocyte antigen receptors and of Fc receptors.

iterative process a process in which a set of steps or instructions is repeatedly executed until a predefined or natural end point is reached. For example, in sequence analysis PSI-BLAST (position-specific iterated-BLAST) runs the BLAST program multiple times until no further matches are identified above a significance threshold.

iteron any sequence of nucleotides in the duplex DNA of certain lambdoid phages that is reiterated several times with only minor changes. These repeated sequences, of 13–19 base pairs, are usually separated by short spacer sequences, each having internal dyad symmetry.

ITF *abbr. for* intestinal trefoil factor.

ITIM *abbr. for* immunoreceptor tyrosine-based inhibitory motif; any of various sequences that are present in the cytoplasmic domains of certain cell surface molecules e.g. Fcγ, inhibiting **NK cell** receptors that mediate inhibitory signals.

+itis *suffix forming nouns* denoting inflammation of the (specified) organ, tissue, etc.

ITP *abbr. for* **1** inosine (5′-)triphosphate. **2** isotachophoresis.

itraconazole a complex derivative of triazole, useful as an antimycotic. It inhibits cytochrome P450-dependent enzymes, thereby impairing the synthesis of ergosterol.

+ity *suffix forming nouns* meaning a property of a substance; e.g. absorptivity, density, solubility.

IU *abbr. for* International Unit *(preferred alternative to* **i.u.** *or* **u** *).*

IUB *abbr. for* International Union of Biochemistry; renamed (1992) International Union of Biochemistry and Molecular Biology (IUBMB).

IUBMB *abbr. for* International Union of Biochemistry and Molecular Biology.

IUdR *or* IUDR *abbr. for* 5-iododeoxyuridine (IdUrd preferred).

IUPAB *abbr. for* International Union of Pure and Applied Biophysics.

IUPAC *abbr. for* International Union of Pure and Applied Chemistry.

iupaciubin alanyl-lysyl-glutamyl-tyrosyl-leucine; a pentapeptide containing one residue each of the five main types of amino acid found in peptides and proteins, i.e. small neutral, basic, acidic, aromatic, and lipophilic. It exists only on paper, and was designed as a model to illustrate nomenclature recommendations relating to the modification of named peptides. Its name symbolizes the cooperation between IUPAC and IUB.

IUPAP *abbr. for* International Union of Pure and Applied Physics.

IUPHAR *abbr. for* International Union of Basic and Clinical Pharmacology.

IV *or* **i.v.** *abbr. for* intravenous or intravenously.

IVD *abbr. for* isovaleryl-CoA dehydrogenase.

ivermectin 22,23-dihydroabamectin; 22,23-dihydroavermectin B_1; a semisynthetic material derived from **abamectin** and used as an anthelmintic in both clinical and veterinary practice, especially against onchocerciasis. It is used extensively as a once-a-month pill against heartworm in dogs.



component B_{1a}, R = C_2H_5
component B_{1b}, R = CH_3

ivermectin

iVI *symbol for* the isovaleryl group, $(CH_3)_2CH–CH_2–CO–$ (alternative to Vl^{i}).

Jj

j *symbol for* electric current density (alternative to *J*).

J *symbol for* **1** joule. **2** J chain (of an immunoglobulin).

J *symbol for* **1** coupling constant. **2** flux (def. 2). **3** electric current density (preferred alternative to *j*).

jack bean **1** an annual tropical American leguminous plant, *Canavalia ensiformis*, grown in the USA for forage. **2** the seed of this plant. It is the source of the globulin **canavalin**, the toxic amino acid L-canavanine, the lectin **concanavalin A**, and the enzyme **urease**.

jack-knife *(in phylogeny)* a statistical method for assessing confidence levels of inferred phylogenetic relationships and the variance of estimated evolutionary parameters, in which values are iteratively and randomly removed, each new data set being used to recalculate the relationships. A **consensus tree** is built after multiple repetitions, and the degree of variance of the sample is determined by comparing each branch of the original tree with the number of times it was found by the jack-knife process.

Jacob–Monod model a model of genetic regulation of protein synthesis in prokaryotes whereby the structural genes that determine the organization of the proteins are controlled by other regions of DNA upstream from the structural genes. The latter consist of a regulator gene and a **control site**, which comprises the **promotor** (*p*) and **operator** (*o*). The regulator gene produces a **repressor** (*r*), which interacts with the operator. The operator and its associated genes are called an **operon**. The structural genes are transcribed into a single mRNA coding for the several proteins. An mRNA coding for more than one protein is known as a **polygenic** or **polycistronic** transcript. The first example was the ***lac* operon** but the model has been used to elucidate many other such phenomena, e.g. the **tryptophan** and **arabinose** operons. The repressor can be either inactivated (**induction**) or activated (**repression**) by specific metabolites. While the model has been helpful in explaining the mode of expression of genes in eukaryotes, operons have not been described in them. [After François Jacob (1920–) and Jacques Monod (1910–76), French molecular biologists.]

Jagged-1 *see* **Alagille syndrome**.

JAK *abbr. for* Janus kinase; any of three cytosolic protein tyrosine kinases that bind the intracellular domains of certain membrane receptors. **JAK1** is activated by binding on the non-γ polypeptide of receptors for the interleukins IL-2, IL-4, IL-7, IL-9, and IL-15. It phosphorylates **STAT** proteins other than STAT 5a and 5b. **JAK2** is activated on binding receptors for somatotropin, several cytokines, and leptin. It then phosphorylates STAT proteins, which dimerize and enter the nucleus to activate specific genes. **JAK3** is activated on binding the γ polypeptide of receptors for IL-2, IL-4, IL-7, IL-9, and IL-15. It phosphorylates STAT 5a and 5b. Several mutations in the gene at 19p13 for JAK2 account for ≈7% of patients with severe combined immunodeficiency (SCID).

JalView *see* **alignment editor**.

Jamaican vomiting sickness a syndrome of sickness, vomiting, and poisoning of the nervous system, associated with profound hypoglycemia, metabolic acidosis, and excessive urinary excretion of butyrate and glutarate, induced by consumption of the unripe fruit of the **ackee**, the toxic principle of which is **hypoglycin**.

Janus kinase *see* **JAK**.

jasmonic acid a plant hormone that consists of a $C_{12:1}$ fatty acid that is unsaturated between C-9 and C-10 and contains a 6-oxocyclopentane ring formed by C-3 to C-7. Derived metabolically from α-linolenic acid, it inhibits growth processes in many tissues, modulates genes involved in development, and plays a role in plant resistance to insects and disease. It is metabolized by hydroxylation and conjugation to the branched chain *α*-amino acids. As methyl jasmonate and the structurally related *cis*-jasmone, it is the fragrant component of oil of jasmine, derived from jasmine plants (*Jasminum* spp.).

jaundice *or* **icterus** a yellowing of the skin and/or of the whites of the eyes indicating an excess of bilirubin in the blood. Jaundice may be classified into three types depending on cause: **obstructive jaundice**, in which the passage of bile from the liver to the intestine is obstructed; **hepatocellular jaundice**, in which there is disease and/or inflammation of liver cells thus diminishing their ability to secrete bile pigments into the bile passages; and **hemolytic jaundice**, in which there is an excessive breakdown of erythrocytes in the body and hence an excess of bile pigments.

Java *see* **programming language**.

javascript *see* **programming language**.

JCBN *abbr. for* (IUPAC–IUB *or* IUPAC–IUBMB) Joint Commission on Biochemical Nomenclature. *See also* **CBN**.

J chain *or* **J piece** *abbr. for* joining chain *or* joining piece; a 15 kDa, cysteine-rich polypeptide occurring in **immunoglobulin A** (IgA) and **immunoglobulin M** (IgM) molecules. It cross-links the monomeric immunoglobulin moieties to form a dimer or pentamer in IgA and IgM, respectively. It is not to be confused with the J segment of an immunoglobulin gene (*see* **joining gene**).

jejunum the part of the small intestine of mammals between the duodenum and the ileum. **—jejunal** *adj.*

jekyll a zebrafish mutant phenotype that shows defective initiation of heart-valve formation. The mutation involves a homologue of the *Drosophila sugarless* gene that encodes a UDP-glucose dehydrogenase required for production of heparan sulfate, chondroitin sulfate, and hyaluronic acid.

jelly roll a protein fold consisting of two antiparallel β-sheets placed one above the other to form a sandwich structure. The polypeptide chain follows a route in which successive β-strands alternate between the two sheets. If the β-strands are numbered β_1, β_2, etc., and the β-sheets numbered in parentheses, as (1), (2), etc., the structure of the motif can be represented as loop-β_1(1)-loop-β_2(2)-loop-β_3(1)-loop-β_4(2)- loop-β_5(1), etc. The jelly-roll fold was first observed in viral coat proteins, but has since been found in other proteins.

Jerne's theory of immunity *an alternative name for* **natural-selection theory of immunity**.

jervine a steroidal alkaloid, found in plants of the genus *Veratrum*, that inhibits cholesterol biosynthesis. Pregnant ewes that ingest these plants give birth to lambs with congenital malformations.

J gene *abbr. for* joining gene.

JIP *abbr. for* JNK-interacting protein; *other name*: kinesin-binding protein; any of three proteins (JIP1 to JIP3) that form part of the **JNK** signalling pathway and are present in cells and organisms that contain **kinesin** light chains (KLC). JIP1 and JIP2 are highly homologous and interact through their C-terminal regions with tetratricosapeptide sequences of KLC. JIP3 is not homologous with the others and interacts through internal sequences with the same sequences in KLC as the others. They are adaptor molecules between kinesins and their cargo. They also bind MAP kinase, MAP kinase kinase, and MAP kinase kinase kinase.

JIPID *abbr. for* Japan International Protein Information Database; *see* **sequence database**.

JIT *abbr. for* Just In Time (compiler); a program that converts **Java** to local machine code at runtime.

JM101 one of a series of *E. coli* strains that support the growth of bacteriophage M13 vectors. The F′ episome carries *lacZM15* making them suitable for alpha-complementation with plasmids encoding the N-terminal peptide of *β*-galactosidase.

JM109 an *E. coli* strain from the same series as **JM101** that carries *recA1* and *endA1* mutations.

JmjC the C-terminal domain of jumonji protein. *See* ***jumonji***.

JmjN the N-terminal domain of jumonji protein. *See* ***jumonji***.

JNK *abbr. for* c-Jun N-terminal kinase; *other name*: stress-associated protein kinase (*abbr.*: SAPK); a nuclear protein serine/threonine kinase, belonging to the **MAP kinase** family, that phosphorylates residues on the N-terminal region of the transcription factor c-Jun (also known as AP1). It is activated by binding to **Cdc42** and regulates cell growth and differentiation, and apoptosis. It is also activated by UV light, thermal stress, and tumour necrosis factor α.

JNK-interacting protein *see* **JIP**.

Job's method *an alternative name for* **continuous variation**.

Johnston–Ogston effect a phenomenon occurring in sedimentation velocity experiments when two or more solutes are present in a mixture and their sedimentation coefficients are mutually concentration-dependent. It follows that the sedimentation coefficient of the more slowly sedimenting component is less in the plateau region containing both species than it is in the plateau region between the boundaries, resulting in a higher concentration of the more slowly moving component in the plateau region between the boundaries. As a consequence, the apparent concentration of the faster moving species, based on the concentration difference between the two plateaus, is too low, while the apparent concentration of the more slowly moving species is too high. [After Alexander George Ogston (1911–96) and Joseph Percy Johnston (1923–76), British biochemists.]

joinase *or* **joining enzyme** *a former name for* DNA ligase (ATP) and DNA ligase (NAD^+). *See* **DNA ligase**.

joining gene *or* **J segment** *abbr.*: J gene; any of approximately five germ-line genes concerned in coding for **immunoglobulin** synthesis. The J genes code for the fourth framework region of both light and heavy immunoglobulin chains and for part of the third hypervariable region of the light chain. *Compare* **J chain**.

joining peptide an acidic, 18-residue peptide situated between γ_3-MSH and ACTH in **proopiomelanocortin**.

Jones–Mote sensitivity a weak, delayed-type hypersensitivity of the skin seen on challenge a few days after priming with soluble protein in aqueous solution or in incomplete Freund's adjuvant. The cells infiltrating the lesion characteristically include a high proportion of basophils.

joule *symbol*: J; the SI derived unit of energy, work, or heat, equal to a force of one newton acting over a distance of one metre; i.e. 1 J = 1 N m = 1 W s. The joule is equivalent to 10^7 ergs and is the energy dissipated by one watt in one second. [After James Prescott Joule (1818–89), British physicist.]

J piece *an alternative name for* **J chain**.

J segment *an alternative name for* **joining gene**.

jumonji a gene of mice and humans that is required for neural-tube formation. The protein contains an N-terminal JmjN domain, a dead ringer domain, and a C-terminal JmjC domain. The two Jmj domains form a functional unit. The JmjC domain also occurs alone in hairless, retinoblastoma protein-binding protein 2, and several putative chromatin-binding proteins. In the mouse, mutations in *jumonji* cause embryonic lethality.

jumping gene *an informal term for* **transposon**.

JUN a gene family encoding nuclear transcription factors; v-*jun* is the oncogene from avian sarcoma virus ASV17 (named from *junana*, Japanese for seventeen). *JUN* encodes transcription factor AP1; it belongs to the *fos/jun* family, and is rapidly and transiently expressed on stimulation of cells by mitogens. The product, Jun, forms heterodimers with Fos, and these, together with Jun homodimers, bind to the AP1 consensus site. Jun is a leucine zipper protein, which also contains basic sequences essential for DNA binding. In resting cells Jun is phosphorylated on four serines and one threonine; removal of one or more of these phosphates leads to increased binding to the AP1 promoter site. Jun has five motifs.

junction potential *see* **liquid-junction potential**.

'junk' DNA *see* **selfish DNA hypothesis**.

juvenile hormone *or* **neotenin** any insect hormone, produced in the corpora allata glands, that functions to keep the insect in the larval (juvenile) stage. At least three are known; all are derivatives of farnesoic acid. They have potential as insect control agents.

juvenile-hormone esterase *see* **methylesterase**.

juvenile macular degeneration *an alternative name for* **Stargardt macular dystrophy**.

juxtacrine stimulation a mode of intercellular communication established by the binding of a membrane-anchored growth factor on one cell to its receptor on an adjacent cell, e.g. in the case of pro-transforming growth factor-α (*see* **transforming growth factor**). Unlike endocrine, paracrine, or autocrine modes there is no diffusible factor.

Kk

k *symbol for* kilo+ (SI prefix denoting 10^3).

k *symbol for* **1** rate constant; the various associated terms are distinguished by subscripts and/or superscripts (see individual entries below). **2** **Boltzmann constant**. *See also* ***k*(*T*)**.

$\tilde{k}$ *symbol for* pH-independent value of the rate constant *k*.

k_0 *symbol for* catalytic constant (of an enzyme); alternative to k_{cat}.

k_A, k_B *symbols for* the specificity constants of substances A and B.

k_{app} *symbol for* the apparent value of the rate constant *k*.

k_{cat} *symbol for* catalytic constant (of an enzyme); alternative to k_0.

k_i, k_{-i} *symbols for* the forward and reverse rate constants, respectively, for the *i*th step in an enzyme reaction.

k_{ij} *symbol for* the rate constant for the step from E_i to E_j in an enzyme reaction.

K *symbol for* **1** potassium. **2** kelvin. **3** a residue of the α-amino acid L-lysine (alternative to Lys). **4** a residue of an incompletely specified base in a nucleic-acid sequence that may be guanine, or either thymine (in DNA) or uracil (in RNA). **5** phylloquinone. **6** *(in computing)* indicating multiplied by 1024 (= 2^{10}).

K562 an erythromegakaryoblastic leukemia cell line. Cells in culture can be induced into erythroid development by treating them with sodium butyrate.

K *symbol for* **1** (thermodynamic) equilibrium constant (of a chemical reaction); the various associated terms are distinguished by subscripts and/or superscripts (see individual entries below). **2** kinetic energy. **3** kerma (kinetic energy released in matter). **4** luminous efficacy.

K' *symbol for* apparent (concentration) equilibrium constant.

K° *or* $K^{\ominus}$ *symbol for* standard equilibrium constant.

K_1, K_2, ... K_n *symbols for* the first, second, ... *n*th equilibrium (dissociation or association) constants, respectively, of the same substance.

K_a, K'_a *symbols for* the thermodynamic and apparent **acid dissociation constants**, respectively.

K_A *symbol for* activator constant.

K_b, K'_b *symbols for* the thermodynamic and apparent **basic dissociation constants**, respectively.

K_c *symbol for* equilibrium constant with respect to concentration (concentration equilibrium constant).

K_i *symbol for* inhibition constant (inhibition type unspecified); the reactant to which it relates may be indicated by an appropriate subscript, e.g. K_{iA}.

K_{ic} *symbol for* competitive inhibition constant.

K_{iu} *symbol for* uncompetitive inhibition constant.

K_m *symbol for* Michaelis constant (*also called* **Michaelis concentration** *or, more appropriately* **Michaelis–Menten constant**); the reactant to which it relates may be indicated by an appropriate subscript, e.g. K_{mA}.

K_s *symbol for* substrate dissociation constant; the reactant to which it relates may be indicated by an appropriate subscript, e.g. K_{sA}.

K_s' *symbol for* salting out constant.

K_w *symbol for* the ion product of water.

kainate receptor a type of neuroexcitatory membrane receptor characterized by its specific agonist ligand, kainate (*see* **glutamate receptor**), and for which glutamate may be the endogenous ligand. The receptor is coupled to Na^+/K^+ channels in the cell membrane, which are opened when activated by agonist.

kainic acid (2*S*,3*S*,4*S*)-2-carboxy-4-(1-methylethenyl)-3-pyrrolidineacetic acid; digenic acid; a cyclic analogue of L-glutamic acid obtained from *Digenea simplex* (a red alga). It is an amino-acid agonist for the **kainate receptor**, is a neurotoxin, and has anthelmintic properties.



kairomone any of a heterogeneous group of chemical messengers that are emitted by organisms of one species but benefit members of another species; they are commonly nonadaptive or maladaptive to the emitter. They include attractants, phagostimulants, and other substances that mediate the positive responses of, e.g., predators to their prey, herbivores to their food plants, and parasites to their hosts. *Compare* **allomone**, **pheromone**.

KAL a human X-chromosome gene that when mutated produces Kallmann syndrome of hypogonadotropic hypogonadism and anosmia. It encodes a glycoprotein (680 amino acids) of the extracellular matrix that is responsible for migration of gonadotropin-releasing hormone (GnRH)-producing neurons and of olfactory neurons. It contains an N-terminal four-disulfide-bond core domain, similar to that of some protease inhibitors, and in the C-terminal region two fibronectin domains (type III) similar to those present in a variety of N-CAMs.

kalata B a uterotonic circular peptide of 29 amino acids extracted from the African plant *Oldenlandia affinis* and several members of the Rubiaceae and Violaceae families. It contains three disulfide bonds and forms only beta strands.

kalinin **1** *another name for* laminin 5 (*see* **laminin**). **2** a filament-associated protein of the **laminin** family, e.g. (precursor) human kalinin B1, also known as nicein B1 or (most commonly) laminin B1k.

kalirin a multidomain cytoskeletal protein that functions as a guanine nucleotide exchange factor. It contains 2959 amino acids, which form 87 spectrin repeats, two Dbl and two pleckstrin homology regions, two Ig-like regions, two SH3 regions, and a kinase domain.

kallidin *an alternative name for* lysylbradykinin; *see* **bradykinin**.

kallikrein any of two groups of serine endopeptidases that are widely distributed in mammalian tissues and body fluids, including blood. **Plasma kallikrein** (EC 3.4.21.34; *also called* kininogenin *or* Fletcher factor *or* serum kallikrein) cleaves Arg-|-Xaa and Lys-|-Xaa bonds, including Lys-|-Arg and Arg-|-Ser bonds in kininogen to produce bradykinin, and activates blood coagulation factors XII and VII; it is formed from prekallikrein by factor XIIa. **Tissue kallikrein** (EC 3.4.21.35; *other names*: glandular kallikrein; kininogenin) catalyses the preferential cleavage of Arg-|-Xaa bonds in small molecule substrates. Its highly selective action to release kallidin (lysyl-bradykinin) from **kininogen** involves hydrolysis of Met-|-Xaa or Leu-|-Xaa. The rat enzyme is unusual in liberating bradykinin directly from autologous kininogens by cleavage at two Arg-|-Xaa bonds.

kallistatin *or* **protease inhibitor 4** an acidic protein (in plasma) of the **serpin** family, expressed widely in human tissues. It inhibits tissue **kallikrein**, forming a 1:1 complex with it.

Kallmann syndrome *see* ***KAL***.

kanamycin an aminoglycoside antibiotic complex produced by *Streptomyces kanamyceticus*. It is made up of three components: kanamycin A (in which $R_1 = NH_2$, $R_2 = OH$; see structure), the major component, often designated as kanamycin; and two minor congeners, kanamycin B (R_1 and $R_2 = NH_2$) and kanamycin C ($R_1 = OH$, $R_2 = NH_2$). Kanamycin causes misreading during protein synthesis in bacteria, but its target site on the ribosome is apparently different from that of streptomycin. *See also* **kanosamine**.

kanosamine 3-amino-3-deoxy-D-glucose; an amino sugar present in **kanamycin** and other antibiotics, and as free carbohydrate in fermentation broths of *Bacillus aminoglucosidicus*.

K antigen *see* **capsular antigen**.

kaolin *or* **china clay** a finely powdered hydrated aluminium silicate; it is useful as an adsorbent.

Kaposi's sarcoma a skin cancer endemic to equatorial Africa and often occurring in AIDS patients. [After Moritz Kaposi (1837–1902), Austrian dermatologist.]



kanamycin

kappa *symbol*: κ (lower case) *or* K (upper case); the tenth letter of the Greek alphabet. For uses *see* **Appendix A**.

kappa B *or* **κB** an element common in eukaryotic promoters. The consensus sequence is GGRNNYYCC, e.g. GGGGACTTTCC in mouse and human.

kappa chain *or* **κ chain** *symbol*: κ; one of the two types of **light chain** found in human immunoglobulins, the other type being a lambda chain. *See also* **Bence-Jones protein**.

kappa convention a way of denoting single ligating atom attachments of a polyatomic ligand to a coordination centre such as a metal ion. Ligands are indicated by the italic element symbol preceded by a Greek kappa, κ. A right superscript numerical index indicates the number of such attachments. *See* **donor atom symbol**.

kappa factor a protein that causes termination of transcription of various bacteriophage DNAs, including those of T4, T5, and T7, by *Escherichia coli* DNA-dependent RNA polymerase in a DNA site-specific manner. It is a dimer of two apparently identical 17 kDa peptide chains.

kappa particle a cell of any of several species of *Caedibacter* present in the cytoplasm of killer strains of *Paramecium aurelia*. (*Caedibacter* is a genus of Gram-negative bacterial obligate endosymbionts of this protozoan.) When kappa particles (and/or toxic constituents or products of them) are released by killer paramecia they may be lethal to sensitive paramecia (which lack both the endosymbiont and a protective genetic factor).

Karplus curve a curve describing the relation of the nuclear magnetic resonance spin–spin coupling constant and the dihedral angle. [After Martin Karplus (1930–).]

Karplus relation an equation describing the relation between the magnitude of the nuclear magnetic resonance spin–spin coupling constant, J, across three bonds and the dihedral angle, Θ, about the central bond. It is:

$$J = A + B\cos\Theta + C\cos^2\Theta,$$

where A, B, and C are coefficients that depend on the electronegativity of the substituents.

karyo+ *or* **caryo+** *comb. form* denoting the nucleus of a cell.

karyogram *an alternative name for* **idiogram**.

karyoid *an alternative name for* **nucleoid** (def. 1).

karyokinesis **1** *an alternative name for* **mitosis**. **2** division of the cell nucleus during mitosis. *Compare* **cytokinesis**.

karyon *or* **caryon** the **nucleus** of a cell.

karyopherin *an alternative name for* **importin**.

karyophilic proteins soluble proteins that accumulate in the nucleus on microinjection into the cytoplasm of amphibian oocytes.They are not bound to chromatin or other nuclear structures. They include **nucleoplasmin** and the acidic nuclear proteins N1 to N4 of the *Xenopus* oocyte nucleus.

karyosome a compartment, located on the nucleolus of some plant species, that may support the rRNA genes as they extend from the nucleolar organizer region.

karyotype the visual appearance of the set of chromosomes of a typical somatic eukaryotic cell of a given species, individual, or cell strain. It is expressed in terms of chromosomal sizes, shapes, and number. —**karyotypic** *adj.*

kasugamine 2,4-diamino-2,3,4,6-tetradeoxy-D-*arabino*-hexose; a component of **kasugamycin** and other antibiotics.

kasugamycin an aminoglycoside antibiotic produced by a strain of *Streptomyces kasugaensis* and containing **kasugamine**. It interacts stoichiometrically with the 30S ribosomal subunit, preventing initiation of protein biosynthesis in prokaryotes; it also blocks translation in fungal systems.

kat *symbol for* katal.

katabolism *a variant spelling of* **catabolism**. —**katabolic** *adj.*

katacalcin a 21-residue peptide derived from the protein precursor of calcitonin, in which it flanks calcitonin on the C-terminal side. It is potent in lowering plasma calcium levels. It is present in normal plasma in concentrations equimolar with calcitonin, and is released rapidly by calcium infusion.

katal *symbol*: kat; a derived coherent unit for expression of enzyme activities, defined as that **catalytic activity** of an enzyme that will raise the rate of conversion of a specified chemical reaction by one mole per second in a specified assay system. There are several important points regarding usage. (1) This definition supersedes a version expressed in terms of the intensive quantity 'rate of reaction' rather than the extensive quantity 'rate of conversion', as well as earlier versions in which catalytic activity was identified with the overall rate of reaction (including the spontaneous rate) rather than with the increase in rate. (2) The katal was adopted as a derived SI unit in 1999. (3) The katal is not used to express rates of conversion themselves (for which the unit is mol s^{-1}). (4) The katal is independent of assay conditions (although the measured catalytic activity of a given system depends on assay conditions). (5) *Compare* **enzyme unit**; 1 kat $\approx 6 \times 10^7$ U; 1 U $\approx$ 16.7 nkat).

katanin a microtubule-stimulated ATPase that severs and disassembles microtubules to tubulin dimers.

Kat.f. an obsolete unit for expressing the specific activity of catalase preparations, originally defined as the rate constant for the catalysed reaction under certain conditions divided by the number of grams of enzyme in the total test volume. The rate constant is calculated from the standard equation for a unimolecular reaction using decadic logarithms and is expressed per minute. Later (apparently unintended) variations of this definition sometimes were used. [From the German *Katalasefähigkeit*, catalase capability.]

katharometer an apparatus used to determine the composition of a gas mixture by measuring its thermal conductivity.

kathode *a variant spelling* of **cathode**. —**kathodic** *adj.*

kation *a variant spelling of* **cation**.

KATP *abbr. for* ATP-dependent K^+ channel; *other name*: Kir 6.2; a K^+ inward rectifier channel of pancreatic B cells that is regulated by the ATP-binding sulfonylurea receptor.

Kauffmann–White scheme a classification scheme for the many serotypes of the bacterial genus *Salmonella*, defined in terms of their somatic (surface) antigens and, where appropriate, their capsular and flagellar antigens.

Kautsky effect the characteristic changes with time in the fluorescence emission of chlorophyll *a* that occur when dark-adapted cells or isolated chloroplasts are illuminated. The changes may be distinguished into a fast change lasting only a few seconds, and a slower change lasting a few minutes. [After Hans Kautsky (1891–1966).]

kayser a unit of **wave number** expressed as the number of wavelengths of electromagnetic radiation in 1 cm.

Kazal inhibitor an electrophoretically heterogeneous proteinaceous trypsin inhibitor and anticoagulant found in the pancreas and in pancreatic juice of a number of mammalian species. *Compare* **pancreatic trypsin inhibitor**. [After Louis Anthony Kazal (1912–), US physiologist.]

kb *symbol for* kilobase.

K capture *see* **electron capture**.

K cell **1** an immunocytochemically distinguishable, granule-containing cell, found in the duodenum and jejunum, that produces **glucose-dependent insulinotropic peptide**. **2** *or* **killer cell** a type of large granular mononuclear lymphocyte that can kill target cells sensitized with antibody. The K cells engage the antibody via their **Fc receptors**. They are probably identical with natural killer (NK) cells.

K chromophore any **chromophore** that gives rise to high-intensity absorption bands due to π–π conjugation. *Compare* **R chromophore**.

KCNE1 the gene at 21q22.1-q22.2 for a cardiac K channel β subunit. It encodes minK, a protein of 129 amino acids, including one transmembrane segment. Numerous loss-of-function mutations are associated with the **long QT syndrome**. *See also* **KVLQT1**.

KCNQ *abbr. for* voltage-gated K$^+$ channel.

kDa *symbol for* kilodalton.

KDEL a tetrapeptide sequence (in the single-letter amino-acid code) at the C terminus of proteins that are to be retained in the endoplasmic reticulum (ER). An equivalent sequence is HDEL, especially in plants. KDEL binds the **KDEL receptor**, and retention is thought to be mediated by continual retrieval from a post-ER compartment. *See also* **luminal proteins**.

KDEL receptor a transmembrane protein of the endoplasmic reticulum that binds the **KDEL sequence**, which constitutes the C terminus of proteins destined to be retained in the endoplasmic reticulum. Such receptors are seven-transmembrane-helix proteins. An equivalent receptor in yeast for the HDEL sequence is a product of the gene *ERD2*.

KDO *abbr. for* ketodeoxyoctanoate.

ke- *abbr. for keto-*.

Kearns–Sayre syndrome (*abbr*.: KSS) *or* **chronic external ophthalmoplegia** (*abbr*.: CPEO) a mitochondrial disease of humans in which ptosis and paralysis of the external eye muscles may be accompanied by myopathy. It is frequently due to a large deletion (5 kbp) in mitochondrial DNA (mtDNA), and less commonly to point mutations in mtDNA for isoleucyl-, asparaginyl-, or leucyl-tRNA. [After Thomas Kearns (1922–) and George Pomeroy Sayre (1911–), US ophthalmologists.]

KEGG *abbr. for* Kyoto Encyclopedia of Genes and Genomes; *see* **pathway database**.

Keilin–Hartree heart-muscle preparation a preparation of submitochondrial particles from bovine heart muscle that is capable of catalysing the reoxidation by dioxygen of NADH and succinate. [After D. Keilin (1887–1963) and E. F. Hartree (1910–94).]

Kell system a blood-group system whose antigenic determinant is part of an erythrocyte membrane glycoprotein of 93 kDa that has an extracellular C-terminal domain with 15 cysteine residues, an N-terminal cytoplasmic domain, and a zinc binding site of the type found in neutral endopeptidases.

kelvin *symbol*: K; the SI base unit of thermodynamic temperature, defined as the fraction 1/273.16 of the thermodynamic temperature of the triple point of water. The symbol K is used both for thermodynamic temperature and for thermodynamic temperature interval, and supersedes °K (degree Kelvin). [After William Thomson, Lord Kelvin (1824–1907), British mathematician, physicist, and inventor, who first defined the absolute scale of temperature.]

KEM1 the symbol of a gene of yeast that encodes a nuclease specific for **G-quartets**.

Kendall's compounds a series of naturally occurring steroids of the adrenal cortex and their metabolites; they were provisionally designated by US physiological chemist Edward Calvin Kendall (1886–1972), using letters of the alphabet, before elucidation of their structures. They are: Kendall's compound A, 11-dehydrocorticosterone; Kendall's compound B (Reichstein's substance H), corticosterone; Kendall's compound C (Reichstein's substance C), 5*α*-pregnane-3*α*,11*β*,17*α*,21-tetrol-20-one; Kendall's compound D (Reichstein's substance A), 5*α*-pregnane-3*β*,11*β*,17*α*,20*β*,21-pentol; Kendall's compound E (Reichstein's substance Fa), cortisone; Kendall's compound F (Reichstein's substance M), cortisol; Kendall's compound G (Reichstein's substance D), 5*α*-pregnane-3*β*,17*α*,21-triol-11,20-dione; Kendall's compound H (Reichstein's substance N), 5*α*-pregnane-3*β*,21-diol-11,20-dione; Kendall's desoxy compound B (Reichstein's substance Q), cortexone, 11-deoxycorticosterone.

Kennedy's disease *an alternative name for* **spinal and bulbar muscular dystrophy**.

kephalin *a variant spelling of* **cephalin**.

kerasin *or* **cerasin** a **cerebroside** in which the fatty acyl moiety is lignoceroyl.

keratan sulfate *or (formerly)* **keratosulfate** any member of a group of glycosaminoglycans with repeat units consisting of (*β*1→3)-linked D-galactopyranosyl-(*β*1→4)-*N*-acetyl-D-glucosamine 6-sulfate and containing variable amounts of fucose, sialic acid, and mannose units. In keratan sulfate I, isolated from cornea, the carbohydrate is attached to the polypeptide backbone through *N*-acetylglucosaminyl–asparaginyl linkages, while in keratan sulfate II, isolated from cartilage and bone, the carbohydrate appears to be attached to the polypeptide backbone through *N*-acetylgalactosamine in *O*-glycosidic linkage to either serine or threonine residues. The keratan sulfates are often attached to the same polypeptide backbone as the chondroitin sulfates.

keratein the soluble product formed by reductive scission of disulfide cross-links in wool keratin on treatment with sulfhydryl compounds, such as thioglycolate.

keratin any member of a class of structural fibrous scleroproteins that occur in vertebrate skin and in various specialized epidermal structures, e.g. feathers, nails, hair, hooves, horns, and quills, as well as in the cytoskeleton. They are classified into **hard keratins**, specific to hair, nails, and feathers, and **cytokeratins**, which form part of the cell cytoskeleton. The hard keratins are typically sulfur-rich proteins cross-linked by disulfide bonds, having M_r in the region of 6000–20 000; the cytokeratins are larger (40 000–56 000) low-sulfur proteins. The hard keratins of mammals are largely α helical ('α keratins'), whereas those of birds and reptiles are largely β-sheet ('β keratins'). However, α keratin can be converted to a β-sheet conformation by reduction and heating (as in hairdressing). Cytokeratins are intermediate- filament proteins (similar to other intermediate-filament proteins), and are of two types: I (acidic) and II (neutral to basic) (40–55 and 56–70 kDa respectively); these form microfibrillar filaments in epithelial cells. Cytokeratin is composed of complexes formed by the aggregation of at least one of each type.

keratinization *or* **keratinisation 1** the process by which epidermal cells synthesize keratin. **2** the elaboration of structures containing keratin, especially in skin. **—keratinize** *or* **keratinise** *vb.*

keratinocyte *or* **keratocyte** any epidermal cell that produces keratin.

keratohyalin a material seen in microscopic sections in granular cells of the skin. It is thought to consist mainly of **filaggrin**.

keratosulfate *a former name for* **keratan sulfate**.

kernicterus an encephalopathy associated with degeneration and yellow pigmentation of basal ganglia and other nerve cells in the spinal cord and brain, caused by the severe unconjugated bilirubinemia occurring in newborn infants and occasionally in older children with hereditary unconjugated hyperbilirubinemia.

kerosene *or* **kerosine** *an alternative name (esp. US) for* **paraffin** (def. 2).

Kerr effect *an alternative name for* **electric birefringence**. [After John Kerr (1824–1907), Scottish physician.]

kestose 1 *or (sometimes)* **6-kestose** *O*-*β*-D-fructofuranosyl-(2→6)-*O*-*β*-D-fructofuranosyl-(2→1)-*α*-D-glucopyranose; a trisaccharide widely distributed in plants, especially in the bulbs and tubers of monocotyledons, and formed artificially when yeast invertase is incubated with a 50% solution of sucrose. The name is derived from the fact that it was discovered at the Tate and Lyle research laboratories, then at Keston, Kent, UK. **2** *or* **1-kestose** isokestose; inulobiosyl glucose; *O*-*β*-D-fructofuranosyl-(2→1)-*O*-*β*-D-fructofuranosyl-(2→1)-*α*-D-glucopyranose; an isomer and congener of 6-kestose. *See also* **neokestose**.

ket+ *a variant form of* **keto+** (sometimes before a vowel).

ketal *see* **acetal**.

ketamine (±)-2-(2-chlorophenyl)-2-(methylamino)cyclohexanone; a dissociative anesthetic with cataleptic and analgesic effects, possibly through acting as an *N*-methyl-D-aspartate (excitatory amino acid) receptor antagonist.



ketanserin 3-[2-[4-(4-fluorobenzoyl)-1-piperidinyl]ethyl]-2,4[1*H*,3*H*]-quinazolinedione; an antagonist to α_1 **adrenoceptors**, H_1 **histamine receptors**, and 5-HT_2 **5-hydroxytryptamine receptors**. A clinically effective hypotensive agent, it differentiates between 5-HT_1 and 5-HT_2 receptors with high specificity; within adrenoceptors and histamine receptors it is less specific.



ketene 1 ethenone; $CH_2=C=O$. **2** any substituted **ketene** (def. 1).

ketimine any **imine** that is an analogue of a ketone; the general structure is $R_2C=NR'$ where R is any organyl group and R′ may be any organyl group or H. *Compare* **aldimine**.

keto 1 carbonyl group, =CO, in any ketone. **2** describing a class of chemical compounds of the general formula R–CO–R′ (where R, R′ are not H). The term is often used to distinguish such compounds from isomeric compounds of another class, e.g. keto sugar. **3** a nonpreferred term, often still used, to denote the presence of a substituent in an organic compound of a double-bonded oxygen atom that is part of a ketonic structure. The recommended term is **oxo**.

keto+ 1 *or (sometimes before a vowel)* **ket+** *comb. form* indicating ketonic or derived from a ketone; e.g. ketal, ketoaldose, ketol. **2** *or (sometimes before a vowel)* **keton+** *comb. form* denoting of or pertaining to a **ketone body** or bodies; e.g. ketoacidosis, ketogenesis, ketonuria. **3** *prefix (in chemical nomenclature)* denoting a ketonic derivative of an indicated organic compound; **oxo** now recommended.

keto- *abbr.*: *ke-*; an optional prefix to the (semi)systematic name of a monosaccharide or monosaccharide derivative containing an uncyclized ketonic carbonyl group, used to stress its acyclic nature. *Compare* ***aldehydo-***, **keto**, **keto+**.

keto acid any organic (carboxylic) acid containing a **keto** (def. 3) group; the recommended term is an oxo acid.

ketoacidosis a type of **acidosis** caused by enhanced production of **ketone bodies** by the ketogenic pathway. This excessive production lowers blood pH and promotes excretion of K^+ and Na^+ by the kidney, leading to cation depletion. It results most often from hormonal imbalance, especially insulin deficiency, when fatty acids are mobilized from adipose tissue, transported to the liver, and converted to ketone bodies. In humans, a plasma level of up to 8 mmol L^{-1} is considered safe and may be beneficial, but in disease states levels may reach up to 20 mmol L^{-1}, contributing to life-threatening situations. *See* **ketogenesis**. **—ketoacidotic** *adj.*

2-ketoadipic acid dehydrogenase EC 1.2.4.1; an enzyme of mitochondrial matrix that catalyses the reaction:

$$\text{2-ketoadipic acid} + \text{CoA} + \text{NAD}^+ = \text{glutaryl-CoA} + \text{NADH} + \text{H}^+ + \text{CO}_2.$$

It is believed to be similar to the pyruvate dehydrogenase complex. Deficient activity gives rise to 2-**ketoadipic acidemia**.

2-ketoadipic acidemia *or (esp. Brit.)* **2-ketoadipic acidaemia** a rare, largely benign condition in which 2-keto, 2-amino, and 2-hydroxy derivatives of adipic acid accumulate and are excreted in excessive amounts in urine. These metabolites are derived from catabolism of lysine, hydroxylysine, and tryptophan. The defect is considered to involve some component of the 2-**ketoadipic acid dehydrogenase** complex.

ketoaldonic acid any monosaccharide formally derived from an aldonic acid by oxidation of a secondary alcoholic hydroxyl group to an oxo group.

ketoaldose any monosaccharide containing both an aldehydic and a ketonic carbonyl group.

ketoconazole a complex derivative of imidazole, clinically useful as an antimycotic. It impairs ergosterol synthesis in fungal cell membranes, thereby increasing their permeability.

ketodeoxyoctanoate *abbr.*: KDO; 2-keto-3-deoxy-D-octanoate; 3-deoxy-D-*manno*-2-octulosonate; an acid present in lipopolysaccharides of the outer membranes of certain Gram-negative bacteria.

keto–enol tautomerism a type of **tautomerism** in which the keto and enol forms of a compound are in equilibrium, the change corresponding to the migration of a hydron and a shift of bonding electrons. *Compare* **amino–imino tautomerism**.

ketofuranose any **ketose** in the **furanose** form.

ketogenesis the metabolic production of **ketone bodies**. The pathway starts with the formation of acetoacetyl-CoA (I) from two molecules of acetyl-CoA by **acetyl-CoA *C*-acetyltransferase** (EC 2.3.1.9); I then reacts with a further molecule of acetyl-CoA, in a reaction catalysed by **hydroxymethylglutaryl-CoA synthase**, to form (*S*)-3-hydroxy-3-methylglutaryl-CoA (II); II is then cleaved to acetoacetate and acetyl-CoA by **hydroxymethylglutaryl-CoA lyase**. These reactions occur in higher animals and are localized entirely in mitochondria; the liver is the main site of synthesis, but kidney, and possibly also small intestine, and adipose tissue may play a part in some situations.

ketogenic forming, or having the quality of being convertible into ketone bodies by metabolic processes.

***α*-ketoglutarate** *a nonpreferred (though often used) name for* 2-oxoglutarate; 2-oxo-1,5-pentanedioate; a compound that has important roles in carbohydrate and amino-acid metabolism, especially in transamination reactions and as a component of the **tricarboxylic-acid cycle**.

***α*-ketoglutaric dehydrogenase** *see* **oxoglutarate dehydrogenase (lipoamide)**.

2-keto-L-gulonate *or (preferably)* **2-oxo-L-gulonate** L-*xylo*-2-hexulosonate; a compound obtained from sorbitol and an important intermediate in the manufacture of **ascorbic acid**.

ketoheptose any **ketose** having a chain of seven carbon atoms in the molecule. Eight enantiomeric pairs of such compounds are possible.

ketohexokinase EC 2.7.1.3; *systematic name*: ATP:D-fructose 1-phosphotransferase; *other name*: hepatic fructokinase. An enzyme that catalyses the phosphorylation by ATP of D-fructose to D-fructose-1-phosphate with release of ADP. The enzyme occurs in cytosol of liver cells, in muscle, intestine, and renal cortex, and in bacteria. It also phosphorylates some other ketoses (e.g. 5-dehydro-D-fructose, D-sorbose, D-tagatose). ‘Fructokinase’ is the recommended name for the enzyme EC 2.7.1.4, which forms D-fructose 6-phosphate (*see* **fructokinase**). In mammals, some fructose can be phosphorylated to fructose 6-phosphate by **hexokinase**. The rat liver enzyme consists of 299 amino acids. Two human isoforms are derived by alternative splicing from one gene. Inactivating mutations lead to hepatic fructokinase deficiency (also called essential fructosuria).

ketohexose any **ketose** having a chain of six atoms in the molecule. Four enantiomeric pairs of such compounds are possible, these being the D and L isomers of fructose, psicose, sorbose, and tagatose.

***α*-ketoisocaproate** *or (preferably)* ***α*-oxoisocaproate** 2-methyl-2-oxopentanoate; an intermediate in the biosynthesis of L-leucine. *See* **leucine and valine biosynthesis**.

***α*-ketoisovalerate** *or (preferably)* ***α*-oxoisovalerate** 3-methyl-2-oxobutanoate; an intermediate in the biosynthesis of L-leucine, L-valine, and pantothenic acid. *See* **leucine and valine biosynthesis**.

ketol 1 any organic compound that is both a ketone and an alcohol, especially an *α*-ketol (i.e. acyloin), one in which the two functions are adjacent. **2** the strongly reducing group, HO–CH_2–CO–, that is characteristic of an *α*-ketol. It is present, e.g., in ketoses and certain corticosteroids.

ketol-acid reductoisomerase EC 1.1.1.86; *systematic name*: *(R)*-2,3-dihydroxy-3-methylbutanoate:$NADP^+$ oxidoreductase (isomerizing); *other names*: dihydroxyisovalerate dehydrogenase (isomerizing); acetohydroxy-acid isomeroreductase. An enzyme of chloroplasts that catalyses the reaction:

(R)-2,3-dihydroxy-3-methylbutanoate + NADP$^+$ =
(S)-2-hydroxy-2-methyl-3-oxobutanoate + NADPH.

It is a component of the pathways for isoleucine and valine biosynthesis. The protein from *Spinacia oleracea* (spinach), for example, is a tetramer of similar but nonidentical chains.

ketol condensation the enzyme-catalysed formation of certain **ketols** (def. 1) by addition of an acyl moiety of one α-oxo acid to another α-oxo acid to form an α-hydroxy-β-oxo acid. It occurs, e.g., in the condensations catalysed by acetolactate synthase (EC 4.1.3.18); these involve either two molecules of pyruvate condensing to form α-acetolactate and CO$_2$, or one molecule of pyruvate and one of α-oxobutyrate condensing to form α-aceto-α-hydroxybutyrate and CO$_2$. The main products are biosynthetic precursors of valine and leucine, and of isoleucine, respectively.

ketolysis *a term sometimes used to* describe the oxidation, for energy production, of ketone bodies by extrahepatic tissues.

α-keto-β-methylvalerate *or (preferably)* **α-oxo-β-methylvalerate** 3-methyl-2-oxopentanoate; the biosynthetic precursor of, and catabolic product of, L-isoleucine.

keton+ *a variant form of* **keto+** (def. 2) (sometimes before a vowel).

ketone 1 any compound containing a carbonyl group, >C=O, joined to two carbon atoms. **2** *the functional class name for* any **ketone** (def. 1) that does not have a trivial name, e.g. ethyl methyl ketone.

ketone body any of the three substances: (1) acetoacetate, formed enzymically from acetyl-CoA; (2) D-3-hydroxybutyrate (β-hydroxybutyrate), formed by liver mitochondrial 3-hydroxybutyrate dehydrogenase (EC 1.1.1.30) from acetoacetate; or (3) acetone, formed by spontaneous decarboxylation of acetoacetate. Ketone bodies may accumulate in the body in starvation, diabetes mellitus, or in other defects of carbohydrate metabolism. They are formed in the post-absorptive state and during more prolonged fasting, and can be used as an alternative energy source to glucose, sparing glucose and thus indirectly muscle protein, since the carbon source for glucose synthesis under such conditions derives from muscle amino acids. Biosynthesis involves the formation of **hydroxymethylglutaryl-CoA**, which is cleaved to acetoacetate and acetyl-CoA by **hydroxymethylglutaryl-CoA lyase**; it occurs largely in the liver, but to a small extent also in kidney. Utilization of ketone bodies in peripheral tissues involves conversion by **3-oxo-acid CoA-transferase** of acetoacetate to acetoacetyl-CoA, which is then converted to two molecules of acetyl-CoA by **acetyl-CoA *C*-acetyltransferase**. 3-Hydroxybutyrate is classed as a ketone body because it exists in an equilibrium with acetoacetate that depends on the redox state in the liver mitochondria.

ketonemia *or (esp. Brit.)* **ketonaemia** an abnormally high concentration of **ketone bodies** in the blood.

ketonic of, relating to, or having the properties of a **ketone** or a **keto** (def. 1) group.

ketonize *or* **ketonise** to convert into or become converted into a ketone. —**ketonization** *or* **ketonisation** *n.*

ketonuria a condition in which there is an abnormally large excretion of ketone bodies in the urine.

ketopentose any **ketose** having a chain of five carbon atoms in the molecule. Two enantiomeric pairs of such compounds are possible, these being the D and L isomers of ribulose and xylulose.

ketoprofen 2-(3-benzoylphenyl)propionic acid; a nonsteroidal anti-inflammatory agent; it inhibits prostaglandin-endoperoxide synthase (EC 1.14.99.1). *See also* **ibuprofen**.



(*S*)-ketoprofen

ketopyranose any **ketose** in the **pyranose** form.

ketose any monosaccharide in the acyclic form of which the actual or potential carbonyl group is nonterminal, i.e. ketonic. The systematic names and many of the trivial names of ketoses have the ending '+ulose'. The position of the (potential) carbonyl group is indicated by a prefixed locant (e.g. 3-ketose, 5-nonulose), which may be omitted from the name of a 2-ketose when no ambiguity can arise. The term is frequently modified by an infix indicating the number of carbon atoms in a chain in the molecule; thus **ketopentose**, **ketotetrose**, etc. *Compare* **aldose**.

ketosis any clinical condition in which there are abnormally high concentrations of **ketone bodies** in the tissues. The condition is usually accompanied by acidosis. *See also* **ketogenesis**. —**ketotic** *adj.*

ketosteroid *a former name for* **oxosteroid**.

keto sugar *a common name for* any **ketose**.

ketotetrose either of two **ketoses** having a chain of four carbon atoms in the molecule, these being the enantiomeric pair D- and L-*glycero*-tetrulose.

β-ketothiolase *see* **acetyl-CoA *C*-acyltransferase**.

ketotriose the single achiral **ketose** having a chain of three carbon atoms in the molecule and known as dihydroxyacetone, or glycerone.

kettin a 500–700 kDa protein of *Drosophila* muscle. Its N-terminal region lies in the Z disk and binds α-actinin. It contains Ig-like regions through which it binds to the thin filaments.

kex2 a structural gene for pre-pro-alpha mating type polypeptide in *Saccharomyces cerevisiae*. It gives rise to the designation Kex2 site, a cleavage site (Arg-|-Arg or Lys-|-Arg) for **kexin** in the processing of the mating polypeptide and several extracellular fungal proteins.

kexin EC 3.4.21.61; *other names*: yeast Kex2 protease; proteinase YSCF; prohormone-processing endoprotease; paired-basic endopeptidase. An enzyme that catalyses the cleavage of Lys-Arg-|-Xaa and Arg-Arg-|-Xaa bonds to process yeast α-factor pheromone and killer toxin precursors. The human enzyme with the same specificity (and EC number) is neuroendocrine convertase 1. *See also* **furin**, ***kex2***, **proopiomelanocortin**.

keyhole limpet hemocyanin *or (esp. Brit.)* **keyhole limpet haemocyanin** *abbr.*: KLH; a respiratory protein from *Megathura crenulata* that elicits a strong T-cell immune response. It is frequently used as a carrier protein to which peptides or other haptens are coupled in order to induce an immune response when used as an immunogen.

kg *symbol for* kilogram.

KH domain *abbr. for* ribonucleoprotein K homology domain; a peptide sequence (40–60 amino acids) present in proteins believed to bind RNA. It consists of several invariant hydrophobic regions (containing Ile, Leu, Met, and Gly) and is highly conserved in the three proteins encoded by *FMR1* gene family members, each of which contains two KH domains. The protein **vigilin**, found in domestic fowl, contains 14 KH domains.

KHF *abbr. for* killer cell helper factor (i.e. **interleukin 2**).

kicksorter a multichannel pulse-height analyser, especially one used to distinguish between radioisotopes by sorting them according to the energies (i.e. 'kicks') of their emitted radiations.

kidney either of a pair of organs of vertebrates concerned with osmoregulation and the elimination of nitrogenous waste products. Kidneys of different species vary in structure according to the animal's mode of life, but their basic design and function is the same. Each kidney is enclosed in a capsule and is made up of an outer cortex and an inner medulla, and contains numerous **nephrons** and their associated blood supply. The nephrons filter constituents from the blood to form urine, which is discharged from the kidney via the ureter.

kieselguhr *an alternative name for* **diatomaceous earth**.

kifnensine an alkaloid produced by the actinomycete *Kitasatospora kifunense* that inhibits **ER α-mannosidase I**.

killed vaccine any suspension of killed (or otherwise inactivated) microorganisms or virus used as an antigen to produce immunity.

killer cell any cell that is cytotoxic to *in vitro* cell cultures, e.g. killer T-lymphocytes and macrophages. Antibody-dependent cell-mediated cytotoxicity may be displayed by a number of cell types, e.g. by human monocytes or interferon-activated neutrophils, which can kill antibody-coated tumour cells, and by **NK cells**, which kill hybridoma cells through the NK cell FcγRII receptor. *See also* **K cell**.

killer-cell helper factor *abbr.*: KHF; *an alternative name for* **interleukin 2**.

killer factor an RNA molecule responsible for the lethal property of **killer strains** of yeast.

killer strain any strain of cells that is able to kill sensitive cells of the same species, e.g. some strains of yeast and *Paramecium*. *See also* **kappa particle**, **killer factor**.

killer T-lymphocyte any T lymphocyte that is able to kill target cells. Killer T-lymphocytes are produced in response to viral infection or an allogeneic tissue graft, and are specifically cytotoxic to host cells infected with virus or to grafted cells carrying the major histocompatibility antigens of the donor, respectively.

kilo+ *symbol*: k; an SI prefix denoting 10^3 times.

kilobase *symbol*: kb; a unit of length of a polynucleotide equal either to 1000 base residues in a single-stranded polynucleotide or to 1000 base pairs in a double-stranded polynucleotide.

kilocalorie *or* **kilogram calorie** *or (esp. in nutrition)* **Calorie** a non-SI unit of heat or energy equal to 10^3 cal_{IT}. *See* **calorie**.

kilodalton *symbol*: kDa; a unit of molecular mass equal to 10^3 **daltons**.

kilogram *symbol*: kg; the SI base unit of mass, and also the fundamental unit of mass in the metric system; it is equal to the mass of the International Prototype of the Kilogram, a cylinder of 90% platinum, 10% iridium, which is kept at the BIPH. It is the only base SI unit that is still defined in terms of an artifact.

kilogram calorie *an alternative name for* **kilocalorie**.

kinase any phosphotransferase enzyme that transfers a phosphate group, usually from ATP. Kinases are divided into EC sub-subclasses according to the nature of the phosphate-accepting group: EC 2.7.1 – phosphotransferases with an alcohol group as acceptor; EC 2.7.2 – phosphotransferases with a carboxyl group as acceptor; EC 2.7.3 – phosphotransferases with a nitrogenous group as acceptor; EC 2.7.4 – phosphotransferases with a phosphate group as acceptor. The name is also used for enzymes that transfer a phosphate group from other nucleoside triphosphates. *Compare* **dikinase**, **pyrophosphokinase**, **thiokinase**.

+kinase *suffix (in the trivial name of an enzyme)* **1** designating a **kinase** or, by extension in certain instances, one that transfers some other inorganic oxo-acid group, e.g. **sulfokinase**. **2** designating an enzyme that activates a zymogen by proteolysis, e.g. **enterokinase**, **streptokinase**, **thrombokinase**.

kinasing *a jargon term for* the act or process of labelling the 5′ end of a nucleic-acid molecule or fragment with phosphorus-32 by reaction with adenosine 5′-[α-^{32}P]triphosphate and the enzyme T4 polynucleotide kinase. This is a step in the **chemical cleavage method** for sequencing DNA and RNA.

kinectin a kinesin-binding protein (1356 amino acids) of endoplasmic reticulum and various other organelles. It contains an N-terminal transmembrane segment and an extensive region for coiled-coil formation in the C-terminal region. Its central region binds RhoGTPase.

kinematic viscosity *symbol*: ν; the dynamic viscosity, η, of a fluid divided by its density, ρ, i.e. $\nu = \eta/\rho$.

kinesin microtubular motor protein, composed of two heavy chains and several light chains, that uses the energy of ATP hydrolysis (ATPase activity in the head of the heavy chain) to move along microtubules, mostly to the plus end, but in some cases to the minus end (e.g., in *Drosophila*). Kinesins are involved in organelle transport, and in mitosis and meiosis. *See also* **dynein**.

kinesin-binding protein *an alternative name for* JNK-interacting protein. *See* **JIP**.

kinetensin *or* **neurotensin-related peptide** (*abbr.*: NRP) the nonapeptide Ile-Ala-Arg-Arg-His-Pro-Tyr-Phe-Leu; it has **neurotensin**-like immunoreactivity, and is isolated from human, bovine, and canine plasma.

kinetic **1** of or relating to the motions of material bodies and the forces and energies associated therewith; of or relating to motion. **2** of or relating to the rate(s) of change of physical or chemical systems. **3** of or relating to **kinetics**.

kinetic energy *symbol*: E_k *or* T *or* K; the energy possessed by a material body by virtue of its motion, determined by the work necessary to bring it to rest.

kinetic proofreading a suggested mechanism of twice using the same Michaelis kinetic ability of an enzyme system to distinguish between two substrates C and D. The essential features of the mechanism are contained in the following reaction scheme, shown for substrate C, but identical in form if substrate C is replaced by D.

$$\begin{tikzcd} C + E \arrow[r, shift left, "k_1"] & EC \arrow[l, shift left, "k_{-1}"] \arrow[r, dashed] & EC^* \arrow[r, "k_3"] \arrow[d, shift right, "k_4"'] & E + \text{product} \\ & & E + C^* \arrow[u, shift right, "k_{-4}"'] \arrow[r, "k_5"'] & C \end{tikzcd}$$

The second step is enzymically coupled to an energy source, typically the hydrolysis of a nucleoside triphosphate, and is strongly enough driven to be essentially irreversible. EC*, a high-energy intermediate, may *either* react to give free enzyme plus product *or* diffuse into the solution where it decomposes to free enzyme plus the nonproduct C*, which can further decompose to C. According to kinetic proofreading, the incorrect intermediate, ED*, diffuses into the solution and decomposes faster than it reacts to give the wrong product, i.e. for ED* $k_3 << k_{-4}$, while for EC* $k_3 > k_{-4}$. In this way, the better binding of C is used twice, once in the formation of EC and again in the binding of the intermediate EC*. If the discrimination in the formation of the initial complex is f, a second factor of f may theoretically be attained, giving a total discrimination of f^2.

kinetics **1** the branch of chemistry concerned with studying rates of chemical reactions. **2** the branch of mechanics concerned with the effects of forces on the motions of material bodies.

kinetin 6-furfurylaminopurine; N^6-furfuryladenine; an artefactual compound formed by autoclaving DNA. It exhibits **cytokinin** activity in plants and was originally thought to be a naturally occurring substance. *Compare* **Kinetin**.

Kinetin *a proprietary name for* **hyaluronidase**. *Compare* **kinetin**.

kinetochore a specialized assembly of proteins that bind to the **centromere** and also attach to **microtubules** growing out from **centrosomes** during mitosis. They are involved in the separation of chromosomes into the daughter cells. They are composed of **centromere-binding proteins**.

kinetochore microtubule *see* **mitotic spindle**, **prometaphase**.

kinetoplast a DNA-rich organelle located within an expanded region of a mitochondrion lying close to the **basal body** in members of the order **Kinetoplastida**. The kinetoplast is self-replicating and divides before the nucleus in cell division.

Kinetoplastida an order of protozoans whose members are characterized by the presence of a **kinetoplast** in the mitochondrion. It includes the genera *Trypanosoma*, *Leishmania*, and *Crithidia*.

kinetosome *an alternative name for* **basal body**.

King–Altman method a general method for obtaining steady-state expressions for enzymic mechanisms with n enzyme-containing intermediates EX_1 ... EX_n. First, a simple geometrical pattern describing the mechanism is drawn. Second, all possible patterns, consisting of $(n - 1)$ lines, that interconnect the possible enzyme forms are drawn; closed loops are forbidden. In general there will be $m!/(n - 1)!(m - n + 1)!$ patterns, where m is the number of interconversion steps. Third, n expressions for $(d[EX_i]/dt[E_{tot}]) = 0$ in terms of the rate constants are set out and solved by determinant methods, using the fact that

$$\sum_{i=1}^{n} ([EX_i]/[E_{tot}]) = 1$$

where $[E_{tot}]$ is the total enzyme concentration. [After E. L. King and C. Altman, who described it in 1956.]

kingdom the highest level of taxonomic classification. All organisms fall into one of three currently accepted kingdoms, each of which has unique and unifying characteristics: eukaryotes, prokaryotes, and archaea.

kinin **1** *or* **kinin-hormone** any member of a varied group of linear polypeptides that constitute a class of so-called tissue or local hormones. Each is locally released from diffuse stores in the body, not having specialized glands of secretion, and is rapidly inactivated at the site of release. Among the most important are **angiotensins**, **bradykinin**, **substance P**, colostrokinin, urinary kinins, and **secretin**. **2** **kinin-9** *an alternative name (sometimes) for* **bradykinin**. **3** **kinin-10** *an alternative name (sometimes) for* kallidin (lysylbradykinin). *See* **bradykinin**. **4** *an alternative name for* **cytokinin**.

kininase any enzyme concerned in the natural breakdown of a **kinin** (def. 1). Included are kininase I (*or* lysine carboxypeptidase, EC 3.4.17.3), a carboxypeptidase circulating in plasma that inactivates bradykinin and possibly also kallidin, and kininase II (peptidyldipeptidase A, EC 3.4.15.1), *also known as* **angiotensin-converting enzyme**.

kininogen any inactive precursor of a **kinin** (def. 1).

kininogenin *an alternative name for* **kallikrein**.

kinked-helix model of duplex DNA a speculative model of the structure of double-stranded DNA in chromatin, proposed in 1975 by British molecular biologists Francis Crick (1916–2004) and Aaron Klug (1926–) to account for the high degree of folding of the DNA (to about one seventh of its length). In this model, based on the B form of duplex DNA, all the base pairs of the double helix remain intact but a sharp turn, or kink, of 95–100° occurs every 20 base pairs along the duplex. At this point one base pair has become unstacked from an adjacent pair through change of the conformation of the deoxyfuranose ring of a nucleotide residue from one of its possible staggered conformations to another. It was suggested that a kink might render several base pairs more easily available for specific interaction with a protein, and that a similar type of folding might occur in double-stranded DNA in other situations, especially when closely associated with protein.

kinomere *an alternative term for* **centromere**.

Kirkwood–Riseman theory of hydrodynamic properties of complex structures a theory providing an approximate method for computing the friction of a structure made up of identical subunits. A linear or coiled polymer is approximated as a string of beads, each with identical hydrodynamic properties, while an oligomeric protein is modelled as a cluster of identical subunits each with identical hydrodynamic properties.

Kirkwood theory of dielectric polarization of polar liquids an extension of the Onsager theory in which the dielectric constant of the central molecule and its first shell of neighbours is considered to differ from its macroscopic value. [After John Gamble Kirkwood (1907–59).]

Kirkwood theory of ion–dipole interactions a model in which the electrical contribution to the chemical potential of an ion having an arbitrary charge distribution is calculated with the aid of the Debye–Hückel theory and in which the Born relation between the free energy of solvation of a spherical ion and the dielectric constant of the solvent is generalized to include ions of arbitrary charge distribution.

Kirkwood–Westheimer theory of electrostatic effects on acid dissociation constants an extension and amplification of the Bjerrum theory of the influence of substituents on acid dissociation constants, the molecules and ions entering into ionization equilibria being treated as cavities of low dielectric constant. [After John Gamble Kirkwood (1907–59) and Frank Henry Westheimer (1912–), US biochemist.]

KIRs killer cell immunoglobulin-like receptors; receptors that are found on **NK cells**, and some γδ and αβ **T-cells**. They recognize **MHC class I** molecules and, like the C-type **lectin** receptors also found in these cells, can either inhibit or activate the killer cells. If **ITIM** sequences are present in their cytoplasmic domain they are inhibitory. KIRs lacking ITIMs can associate with ITAM-containing adaptor molecules in which case they can activate the killer cell.

kirromycin *or* **mocimycin** an antibacterial antibiotic isolated from *Streptomyces collinus* and others. It specifically interacts with **elongation factor** EF-Tu (*see* **EF-T**) and prevents the release of EF-Tu from the bacterial ribosome after GTP hydrolysis. In the absence of ribosomes, the antibiotic induces an EF-Tu-dependent hydrolysis of GTP.

kis- *see* **multiplying prefix**.

kistrin a protein isolated from the venom of the Malayan pit viper, *Agkistrodon rhodostoma*. It contains the **RGD** sequence, and binds to a platelet adhesion site. It is a potent platelet aggregation inhibitor and antagonist of a family of glycoproteins that mediate aggregation. *For example, see* **disintegrin**.

kit a commercially available collection of biochemical reagents and apparatus to carry out a procedure, such as an assay.

KIT a family of genes encoding plasma membrane class III receptor tyrosine kinases. The viral gene, v-*kit*, is the oncogene of the Hardy–Zuckerman 4 strain of acutely transforming feline sarcoma virus. The product of the protooncogene c-*kit* has five immunoglobulin-like loops in the extracellular domain; the cytoplasmic region contains a tyrosine kinase domain with an insert region, and is myristoylated. Interaction with its ligand, steel factor (*see* **stem cell factor**), brings about dimerization, leading to enhanced autophosphorylation and binding of phosphatidylinositol 3-kinase and phospholipase Cγ. Kit and its ligand are highly expressed in small-cell lung cancer and a significant proportion of testicular germ cell tumours.

Kjeldahl flask a small pear-shaped glass flask with a long neck, as used in the **Kjeldahl method**.

Kjeldahl method a method for the determination of the total nitrogen in an organic compound or mixture of compounds. The sample, in a **Kjeldahl flask**, is digested in hot, concentrated sulfuric acid with a catalyst, usually one containing mercury, copper, or selenium; the nitrogen in the sample is thereby converted to ammonium hydrogen sulfate. The ammonium formed may be estimated by neutralization and steam distillation of the resultant ammonia into a known amount of acid, the residual acid being determined by titration, or it may be estimated by **nesslerization** or with an ammonium electrode. [After Johan Kjeldahl (1849–1900), Danish chemist.]

Kleinschmidt technique a technique for preparing monolayers of DNA for electron microscopy in which the DNA molecules are bound to a film of denatured basic protein, e.g. cytochrome *c*, on the surface of an aqueous solution. The DNA molecules are consequently brought from a three-dimensional conformation to a two-dimensional one by adsorption to the protein layer. The DNA–protein complex is then transferred to a solid surface, e.g. an electron microscope grid or collodion film, dried, and contrasted with heavy metals by shadowing or staining. The tendency of **ssDNA** to fold back on itself with the formation of intramolecular base pairs can be overcome by using formamide (which denatures short base-paired regions) or by replacing cytochrome *c* with DNA-unwinding proteins, which have high affinity for ssDNA. The method may also be applied to RNA. [After Albrecht K. Kleinschmidt (1916–), German microbiologist.]

Klenow enzyme *or* **Klenow fragment** the larger (75 kDa) of the two fragments formed by the treatment of *Escherichia coli* DNA polymerase I with subtilisin in the presence of DNA. It retains the polymerase activity and the single-strand-specific 3′→5′ exonuclease activities but lacks the 5′→3′ exonuclease activity of DNA polymerase I. It is useful in sequencing single-stranded DNA. [After Hans Klenow (1923–), Danish biochemist.]

KLF *abbr. for* Krüppel-like factor.

KLH *abbr. for* keyhole limpet hemocyanin.

Klinefelter syndrome a genetic condition in which males have an extra X chromosome (XXY). It occurs as frequently as 1–2 per 1000 male births, and the chief sign is infertility caused by androgen deficiency and absence of sperm. Stature is also often affected, with long limbs and above-average height, and secondary sexual characteristics can be underdeveloped. The term **XXY male** is preferred because many are otherwise normal individuals who do not have the syndrome as originally described. [After Harry F. Klinefelter (1912–), US physician.]

Klotz plot *a name sometimes given to* a plot of the reciprocal form of an equation describing ligand binding at multiple independent sites on, e.g., a macromolecule. It has the form:

$$1/\bar{v} = (1/nk)(1/[\mathrm{A}]) + 1/n,$$

where $\bar{v}$ is the average number of ligand molecules bound per molecule of the macromolecule, n is the number of binding sites per macromolecule, [A] is the molar concentration of free ligand molecules, and k is the intrinsic association constant. If the equation correctly describes the equilibria involved, a plot of $1/\bar{v}$ versus 1/[A] gives a straight line of slope $(1/nk)$ and with an intercept on the $1/\bar{v}$ axis of $1/n$ and on the 1/[A] axis of $-1/k$. [After Irving Myron Klotz (1916–), US biochemist.]

***k*-means clustering** an algorithm for clustering data that allows generation of user-specified numbers of clusters from a given data set based on distance metrics for similarity. The method is dependent both on the specified value of *k*, which determines the number of clusters that are created, and on the distance measure employed. It is widely used in the analysis of microarray data.

KMEF group *abbr. for* keratin-myosin-epidermin-fibrinogen group; a group of proteins that have in common an α-type X-ray diffraction pattern. Some of these may show a β-type pattern in some conditions. Silk fibroin, which normally occurs with a β structure, is often included in the KMEF group.

knallgas bacteria *or* **hydrogen bacteria** any of a number of bacterial species that can obtain energy from the **knallgas reaction**, i.e. the oxidation of dihydrogen to water by dioxygen. They include some *Alcaligenes* and *Pseudomonas* spp. and *Paracoccus denitrificans*. [From the German, *Knallgas*, an explosive mixture of hydrogen and oxygen.]

knallgas reaction the energy-yielding direct oxidation of dihydrogen by dioxygen occurring in certain bacteria (*see* **knallgas bacteria**). The reaction is:

$$2\,H_2 + O_2 \rightarrow 2\,H_2O + \text{energy}.$$

knockdown in gene expression the experimental reduction in the amount of a specific gene product. It is usually achieved by the use of siRNA to decrease the abundance of its mRNA or inhibit its translation. *Compare* **knockout**.

knockin denoting an animal in which a gene function has been introduced by genetic engineering techniques. [Opposite to 'knockout'.]

knockout indicating an animal in which function of a gene has been deleted by genetic engineering techniques.

Knoop's hypothesis the hypothesis that fatty acids are metabolically oxidized by the successive removal of two-carbon fragments as acetic acid. *See also* **beta oxidation**. [After Franz Knoop (1875–1946), German physiologist and biochemist.]

Knop solution an aqueous solution containing the major inorganic constituents required for the growth of cells of higher plants, namely calcium nitrate, potassium nitrate, magnesium sulfate, potassium dihydrogen phosphate, and potassium chloride. [After J. A. L. W. Knop (1817–1901), German chemist.]

Knox plot *(in high-performance liquid chromatography)* a plot of relative separation efficiency versus flow rate, useful in determining the optimal conditions for a desired separation. [After John H. Knox.]

Knudson's hypothesis (**two-hit hypothesis**) the hypothesis, formulated in the early 1970s, that hereditary retinoblastoma results from the inheritance of one mutant copy of the *RB1* gene and mutation of the second normal allele during the life of the patient. Such a situation, in which somatic mutation occurs alongside one inherited mutant allele, is known as loss of heterozygosity (LOH). [After Alfred Knudson (1922–), US geneticist.]

Koch phenomenon a cell-mediated hypersensitivity reaction in which inflammation of guinea-pig skin, when injected with living or dead *Mycobacterium tuberculosis*, is very much greater in animals actively infected with the organism than in uninfected animals injected with dead organisms. [After (Heinrich Hermann) Robert Koch (1843–1910), German bacteriologist, who isolated the bacillus in 1882.]

kojibiose the disaccharide 2-*O*-*α*-D-glucopyranosyl-D-glucopyranose.

kojic acid 5-hydroxy-2-(hydroxymethyl)-4*H*-pyran-4-one; a metabolite from *Aspergillus oryzae* and *A. terreus*. It can be obtained in large amounts and has some industrial application.



Kok effect the sharp difference in yield of photosynthesis above and below the compensation point. Below compensation, where respiration can supply intermediates at a greater rate than the rate of photosynthesis, the yield is about twice as great as above compensation, where CO_2 has presumably to be drawn into the process. [After Bessel Kok (1918–81) Dutch-born US plant physiologist.]

Kornberg enzyme *an alternative name for* DNA polymerase I. *See* **DNA polymerase**. [After Arthur Kornberg (1918–), US biochemist.]

Korrigan cellulase a subunit of the **cellulose synthase** complex found in plasma membranes of plant cells. It cleaves off the glucan chain from cellodextrin with release of the sitosterol *β*-glucoside primer and the glucan chain, which then forms the microfibrils of cellulose.

Korsakoff's psychosis *see* **Wernicke–Korsakoff syndrome**.

Koshland model *see* **induced-fit theory**.

Kozak sequence a consensus sequence (optimally CCA/GCCAUGG) located around the **translation start site** and involved in its recognition by the ribosome.

***Kpn*I** a type 2 **restriction endonuclease**; recognition sequence: GGTAC↑C.

Kr *symbol for* krypton.

Krabbe's disease *an alternative name for* **galactosylceramide lipidosis**. [After Knudd Haraldsen Krabbe (1885–1961), Danish physician.]

KRB *abbr. for* Krebs Ringer bicarbonate; *see* **Krebs mammalian Ringer**.

Krebs–Cohen dismutation The anaerobic reaction summarized as:

$$\begin{gathered}\text{2-oxoglutarate} + NH_4^+ \rightarrow \\ \text{succinate} + \text{glutamate} + CO_2 + H^+.\end{gathered}$$

It has been shown to occur in pigeon heart and breast muscle, rat and guinea-pig renal cortex, and rat-liver mitochondria. It is the sum of two reactions:

$$\begin{gathered}\text{2-oxoglutarate} + H_2O + NAD^+ \rightarrow \\ \text{succinate} + CO_2 + NADH + H^+,\end{gathered}$$

and

$$\begin{gathered}\text{2-oxoglutarate} + NADH + NH_4^+ \rightarrow \\ \text{glutamate} + NAD^+ + H_2O.\end{gathered}$$

[After (Sir) Hans Adolf Krebs (1900–81), German-born British biochemist, and Philip Pacy Cohen (1908–93), US biochemist.]

Krebs cycle *an alternative name (sometimes) for* **1 tricarboxylic-acid cycle**. **2 ornithine–urea cycle**.

Krebs–Henseleit cycle *an alternative name for* the **ornithine–urea cycle**. [After (Sir) Hans Adolf Krebs (1900–81), German-born British biochemist, and Kurt Henseleit (1908–73).]

Krebs–Henseleit Ringer bicarbonate *see* **Krebs mammalian Ringer**.

Krebs–Kornberg cycle *an alternative name for* **glyoxylate cycle**. [After (Sir) Hans Adolf Krebs (1900–81) and Hans Leo Kornberg (1928–), German-born British biochemists.]

Krebs mammalian Ringer any of several media devised for the suspension of mammalian tissues. In the first version (1932), **Krebs–Henseleit Ringer bicarbonate**, the buffer was bicarbonate-CO_2, while in the second (1933), **Krebs original Ringer phosphate**, it was phosphate. In improved versions (1950), often referred to respectively as **Krebs Ringer bicarbonate** (*abbr.*: KRB) and (calcium-free) **Krebs Ringer phosphate** (*abbr.*: KRP), a mixture of organic acids and glucose was substituted for part of the NaCl in the first two versions, to resemble as closely as possible the state of the tissues in the intact animal. Also, an additional medium, low in phosphate, bicarbonate, and CO_2, was devised. *See also* **Ringer's solution**.

Krebs' manometer fluid a solution containing 44 g NaBr, 0.3 g Triton X-100, and 0.3 g Evans' Blue in 1000 mL of water; D = 1.033. The standard pressure (760 mmHg) in mm of manometer fluid is 10 000. Other detergents may be substituted for the Triton X-100 in equivalent proportions.

K region a region in a carcinogenic polycyclic aromatic hydrocarbon molecule in which there is a carbon–carbon bond having ordinary double-bond rather than aromatic character and that takes part in addition reactions; e.g. the bond between atoms C-9 and C-10 in phenanthrene. It has been suggested that carcinogenicity in such molecules is determined by the existence in them of an active K region. *Compare* **L region**.

kringle a protein module of about 85 amino-acid residues that is held in a characteristic 3-D conformation by three internal disulfide bridges. It is so-named because its 2-D representation resembles that of the kringle, a Scandinavian pastry of characteristic shape. It was first described in prothrombin, but has since been found in plasminogen and (both tissue-type and urokinase-type) plasminogen activators.

Kronig–Kramers transform any of a set of mathematical relations describing the response of a system to a perturbation such as light. These relations allow the calculation of optical rotary dispersion from circular dichroism (ellipticity) and vice versa, and describe the relationship between dispersion and absorption. [After R. de L. Kronig and Hendrik Anthony Kramers (1894–1952), Dutch physicist, who independently devised them in 1926 and 1927, respectively.]

KRP *abbr. for* Krebs Ringer phosphate; *see* **Krebs mammalian Ringer**.

Krüppel a protein involved in the segmentation of the embryo and in the differentiation of the malpighian tubules in insects (e.g., *Drosophila*). It is a nuclear, chromatin-associated protein, encoded by a **gap gene**, and is a member of a subfamily of C_2H_2-type zinc-finger proteins. Mutant *krüppel* larvae lack eight body segments. [From German *Krüppel*, cripple.]

Krüppel-like factor *abbr.*: KLF; any DNA-binding transcriptional regulator that is homologous to **Krüppel** protein of *Drosophila*. At least 15 human KLFs are recognized.

KS/hst a human oncogene, with no known viral counterpart, whose product is related to **fibroblast growth factor** and is expressed in **Kaposi's sarcoma**.

k(T) *symbol for* rate constant (alternative to *k*, used when distinction of a rate constant from the Boltzmann constant is necessary).

K-tup *an alternative term for* **K-tuple**.

K-tuple *or* **K-tup** the number of sequence characters that are considered as an indivisible unit (or word) by database search algorithms such as FastA.

Ku the dsDNA-binding component of **DNA-PK**.

Kunitz and Northrop inhibitor *see* **pancreatic trypsin inhibitor**.

Kunitz inhibitor the best known of the three **soybean trypsin inhibitors**. The term refers to any type of protease inhibitor that contains consensus sequences known as **Kunitz domains**. These include some serine protease inhibitors. Such domains have also been identified in some α-amyloid precursor protein isoforms.

Kunitz (tryptic) unit a measure of tryptic activity based on the extent to which trypsin-containing samples can digest casein under standard conditions, often used to determine the relative amounts of Kunitz and Bowman–Birk type trypsin inhibitors present in samples, comparison being made between tryptic activity and chymotryptic activity. Crystalline trypsin has an activity of 6 Kunitz units per mg.

Kupffer cell a type of nonmotile, mononuclear phagocytic cell. Such cells line the sinusoids of the liver. [After Karl Wilhelm von Kupffer (1829–1903), German anatomist.]

kuru a transmissible **spongiform encephalopathy** of humans, characterized by degeneration of the nervous system and found among the Fore people of Papua New Guinea. It is a **prion** disease, transmitted through funerary practices thought to have involved endocannibalism. The brains of victims of this and **Gerstmann–Sträussler syndrome** contain so-called kuru plaques, which have been shown to stain positively with antibodies against prion protein in patients with Gerstmann–Sträussler syndrome. It has become extremely rare since cannibalism ceased in the late 1950s.

KVLQT1 the gene at 11q15.5 for a cardiac K voltage-gated channel α subunit. It encodes 676 amino acids, including six transmembrane segments and extensive intracellular N- and C-terminal domains. Numerous loss-of-function mutations are associated with the **long QT syndrome**. *See also* **KCNE1**.

kwashiorkor a form of severe malnutrition of children occurring in tropical or near-tropical regions. It is generally believed to be caused by a dietary deficiency of protein, but not of other energy-producing foodstuffs. The condition commonly develops when, after prolonged breast feeding, the child is weaned onto a diet inadequate in protein. *Compare* **marasmus**.

kynurenate 4-hydroxyquinaldate; 4-hydroxy-2-quinoline carboxylate; the anion of kynurenic acid and an intermediate in the conversion of **kynurenine** to quinaldate.



kynureninase EC 3.7.1.3; *systematic name*: L-kynurenine hydrolase; a pyridoxal-phosphate-containing enzyme that hydrolyses L-kynurenine to anthranilate and L-alanine. It also acts on 3′-hydroxykynurenine and some other (3-arylcarbonyl)-alanines.

kynurenine 3-anthraniloylalanine; L-kynurenine is a metabolite on the degradative pathway of tryptophan, is found in the urine especially in pyridoxal (vitamin B_6) deficiency, and is an intermediate in the synthesis of nicotinic acid from tryptophan.



kyotorphin the analgesic dipeptide, L-Tyr-L-Arg, isolated from bovine brain; D-kyotorphin is L-Tyr-D-Arg.

Ll

l *symbol for* **1** litre (alternative to L). **2** liquid.

l *symbol for* length (alternative to *L*).

***l*-** *prefix (in chemical nomenclature)* denoting levorotatory; now obsolete, use (–)-; *see* **optical isomerism**.

L *symbol for* **1** litre (alternative to l). **2** a residue of the *α*-amino acid L-leucine (alternative to Leu). **3** an atom of hydrogen that may be one of *either* protium *or* deuterium. **4** linking number. **5** light chain (def. 1) (of an immunoglobulin).

L *symbol for* **1** Avogadro constant (alternative to N_A). **2** latent heat. **3** radiance.

L- a configurational prefix used in designating the absolute configuration of chiral compounds of certain classes; *see* **D/L convention**.

La *symbol for* lanthanum.

label 1 *or (sometimes informally)* **tag** any (radioactive or stable) isotope substituted in a proportion of the molecules of a particular compound so that the translocation and/or the chemical or biochemical transformation of the compound may be followed. *See also* **tracer**. **2** *or (sometimes)* **marker** an easily recognizable chemical group (which can be radioactive) attached to a molecule or incorporated within a structure. **3** to attach or apply such a label. The following particular uses of the terms label or labelled have individual entries (*see also* the list at **labelling**): **affinity label**, **electron-dense label**, **immunoassay**, **mixed labelled**, **multiply labelled**, **nonselectively labelled**, **photoaffinity label**, **radioactive label**, **selectively labelled**, **singly labelled**, **specifically labelled**, **spin label**, **uniformly labelled**.

labelled compound *or (US, usually)* **labeled compound** a compound bearing a **label** (def. 1, 2). An isotopically labelled compound is a compound in which one or more atoms of a proportion of the molecules have been replaced by a (radioactive or stable) isotope; i.e. it is a mixture of an isotopically unmodified compound with one or more analogous isotopically substituted compound(s). In some cases, the amount of isotopically unmodified compound may be small. This is particularly the case for ^{2}H compounds, when near 100% replacement is possible. *See also* **carrier-free**.

labelling *or (US, usually)* **labeling 1** the attribute of being labelled. **2** the act or process of chemically introducing a **label** (def. 1, 2) into a compound either by substitution or by synthesis, or of incorporating such a label into a material or structure. The following particular uses of the term labelling have individual entries (*see also* the list at **label**): **conjugation labelling**, **double labelling**, **enzyme labelling**, **ferritin labelling**, **fluorescein labelling**, **generally labelled**, **hapten-sandwich labelling**, **iodine labelling**.

labile 1 describing a chemical compound that is prone to spontaneous change or decomposition; relatively unstable. **2** describing an atomic or molecular grouping in a chemical compound that usually readily dissociates from the compound; loosely attached. **3** describing a chemical bond that very easily ruptures or is ruptured. **—lability** *n.*

labile factor *an alternative name for* factor V; *see* **blood coagulation**.

labile phosphate the amount or proportion of any phosphate that is readily liberated from a phosphate-containing compound by hydrolysis in 1 M HCl at 100°C within 7–10 min (*hence also sometimes known as* **seven-minute phosphate** *or* **ten-minute phosphate**). These conditions were selected originally for estimating the two terminal phosphate groups of ATP. The following compounds are included in the group (percentage hydrolysis in parentheses): phosphocreatine (100), ATP (67), ADP (50), aldose 1-phosphate (100), pyrophosphate (100).

labilize *or* **labilise** to render **labile** (*esp.* def. 3). **—labilization** *or* **labilisation**, **labilizer** *or* **labiliser** *n.*

lac any of various resinous substances secreted by certain plants or insects, used in the manufacture of lacquers.

lac *symbol for* the genetic system of *Escherichia coli* that controls the organism's ability (*lac*$^+$) or inability (*lac*$^-$) to metabolize **lactose**. *See also* ***lac* operon**, ***lac* repressor**.

laccase any of a group of copper–protein enzymes (EC 1.10.3.2) of low specificity, that catalyse the oxidation of both *o*- and *p*-quinols by dioxygen to form the corresponding semiquinones and two molecules of water. They are so-called because such an enzyme was first found in the lac (or lacquer) tree (*Rhus verniciflua*); however, they are now known to be widely distributed in plants and fungi.

lacI the structural gene for ***lac* repressor**, the repressor of the *lac* operon.

***lacI*^{q}** a mutation in the promoter of the *lacI* gene of *E. coli* that results in increased transcription and higher levels of ***lac* repressor** within cells.

***lac* operon** *or* **lactose operon** a genetic system, or **operon**, of *Escherichia coli* that controls the synthesis of the inducible enzyme *β*-D-galactosidase (*see* **galactosidase**). It is probably the most intensively studied group of *E. coli* genes. It consists of a linear sequence (5′ end to 3′ end of the coding strand) of two control sites, designated *p* and *o*, followed by three structural genes, designated *z*, *y*, and *a*; *p* is the promoter (concerned with RNA-polymerase binding), *o* is the operator (binding site for repressor), *z* is the gene for *β*-galactosidase, *y* is the gene for the **permease**, and *a* is the gene for thiogalactoside transacetylase (an enzyme of uncertain physiological function). Immediately preceding the *p* site is a regulatory gene designated *i* (concerned with synthesis of ***lac* repressor**).

***lac* repressor** a protein encoded by the *lacI* gene, that controls the expression of structural genes coding for enzymes involved in lactose metabolism in the *Escherichia coli* genome; in the absence of inducer it binds with high affinity to the operator site of the ***lac* operon**. It is a homotetramer and specifically recognizes a 23 base-pair DNA sequence in the *lac* operator by means of its four N-terminal domains (headpieces), each of 51 amino-acid residues; each subunit also has one allosteric binding site for an inducer. The repressor is a typical **helix-turn-helix** protein and gives its name to a subfamily.

lact+ *a variant form of* **lacto+** *(before a vowel)*.

lactacin any of a family of pore-forming peptidic toxins with approximately 75 + 65 amino acid residues, permitting passage of small solutes, including water. They are produced by *Lactobacillus johnsonii* and are classified in the TC system under number 1.A.26.

lactadherin a protein produced by smooth muscle cells of the aorta and the precursor of the polypeptide **medin**.

lactalbumin 1 the fraction of (normally cow's) milk proteins remaining after removal of casein. It consists principally of **beta-lactoglobulin** and α-lactalbumin. **2 *α*-lactalbumin** a Ca^{2+}- binding protein that occurs as a minor constituent of milk of many mammals; its 123 amino-acid sequence is highly similar to that of lysozyme. It is a non-catalytic regulatory protein whose presence is required for **lactose synthase** to transfer a galactose residue from UDPgalactose to D-glucose; hence it is also known as B protein of lactose synthase. It causes the substrate for *N*-acetyllactosamine synthase to change from *N*-acetylglucosamine to glucose, to give lactose and UDP. Protein B had, therefore, been called a **'specifier' protein**. The genes for lysozyme and α lactalbumin arose evolutionarily from a common ancestral gene.

lactam any intramolecular cyclic amide produced by the formal removal of a molecule of water between the amino and the carboxyl groups of an amino acid, other than an *α*-amino acid. A prefix (as in *β*-lactam) may be used to designate the position of the amino group in the parent compound. A lactam commonly exists in tautomeric equilibrium with its corresponding **lactim**.

***β*-lactam antibiotic** any member of a class of natural or semisynthetic antibiotics whose characteristic feature is a strained, four-membered *β*-lactam ring (*see* **lactam**). They include the **penicillins** and many of the **cephalosporins**.

***β*-lactamase** any member of a group of constitutive or inducible enzymes (EC 3.5.2.6); *systematic name*: *β*-lactamhydrolase. They are produced by certain strains of various bacterial species and can catalyse the hydrolysis of the **lactam** linkage in one or more *β*-lactam antibiotics, leaving a substituted *β*-amino acid; they thereby inactivate the antibiotic. The enzymes are of varying specificity, some acting more rapidly on penicillins (**penicillinases**), some more rapidly on cephalosporins (**cephalosporinases**); the latter were formerly classified separately as EC 3.5.2.8. The *β*-lactamases can be inhibited by various substances, such as **clavulanic acid**. There are several classes: class A (or type I) enzymes have seven motifs; class B (or type II) enzymes have a zinc cofactor. For example, the class A Men-1 from *Escherichia coli* has a broad spectrum of activity, hydrolysing penicillins and many cephalosporins.

lactam–lactim tautomerism a form of **tautomerism** occurring in lactam–lactim interconversion as a result of migration of a hydron between the nitrogen atom and the oxygen atom. It represents a special case of amide–imidol tautomerism.



lactase *a trivial name for* any *β*-D-**galactosidase**. Some lactases hydrolyse other glycosides, including *α*-L-arabinosides, *β*-D-fucosides, and *β*-D-glucosides.

lactase deficiency a condition of humans in which there is a congenital or acquired deficiency of lactase (i.e. *β*-**galactosidase**) in the mucosa of the small intestine leading to failure to digest lactose and to **lactose intolerance**. The condition is more common in healthy adolescents and adults, and its frequency varies considerably: it is more prevalent in native populations of Australia and Oceania, east and south-east Asia, tropical Africa, and the Americas (45–95%) than in those of central and northern European ancestry (<25%).

lactate 1 *α*-hydroxypropionate; 2-hydroxypropanoate; the anion, $CH_3–CH(OH)–COO^–$, derived from **lactic acid**. It occurs naturally as D(–)-lactate (i.e. (*R*)-2-hydroxypropanoate) and L(+)-lactate (i.e. (*S*)-2-hydroxypropanoate). L(+)-lactate is formed by anaerobic glycolysis in animal tissues, and DL-lactate is found in sour milk, molasses, and certain fruit juices. Bacterial **lactic-acid fermentations** produce either the D(–) or L(+) enantiomer or the racemate (DL) depending on the individual organism. **2** any salt or carboxylic ester of lactic acid. **3** to secrete milk; *see* **lactation**.

lactate dehydrogenase any enzyme that interconverts **lactate** and pyruvate. **L-lactate dehydrogenase** (EC 1.1.1.27; *abbr*.: LD *or* LDH) acts on L-lactate and NAD^+. It occurs as homotetramers or heterotetramers of the heart muscle (H) and skeletal muscle (M) forms (the five isoenzymes are: LD_1, H_4; LD_2, H_3M; LD_3, H_2M_2; LD_4, HM_3; and LD_5, M_4). In clinical chemistry the assay of LD_1 (*known also as α*-hydroxybutyrate dehydrogenase *or* HBD) can be of use in diagnosing myocardial infarction, in which it peaks at 2–3 days after the infarct, and in hemolytic crisis of sickle-cell anemia, since this isoenzyme is the predominant form in cardiac muscle and red cells. **D-lactate dehydrogenase** (EC 1.1.1.28) acts on D-lactate and NAD^+. **L-lactate dehydrogenase (cytochrome)** (EC 1.1.2.3) acts on L-lactate and ferricytochrome *c* and is a flavohemoprotein (FMN is coenzyme). **D-lactate dehydrogenase (cytochrome)** (EC 1.1.2.4) acts on D-lactate and ferricytochrome *c* and is a flavoprotein (FAD is coenzyme). **D-lactate dehydrogenase (cytochrome *c*-553)** (EC 1.1.2.5) acts on D-lactate and ferricytochrome *c*-553 and is present in *Desulfovibrio vulgaris*. These enzymes are very widely distributed.

lactation 1 the secretion of milk by the mammary gland. **2** a complete period of milk secretion from about the time of parturition to that of weaning. *See also* **lactate** (def. 3).

lacteal 1 of, relating to, or resembling milk; milky. **2** (of lymph vessels) containing or conveying **chyle**. **3** any blind-ended lymph vessel that carries chyle from a villus of the small intestine to the thoracic duct.

lactic pertaining to, or derived from, milk.

lactic acid *α*-hydroxypropionic acid; 2-hydroxypropanoic acid; a reasonably strong acid ($pK_a = 3.86$ at 25°C). In biological systems it normally exists largely as its anion, **lactate** (def. 1). It is also useful as a preservative of foodstuffs.



$$\begin{array}{c} COOH \\ | \\ HO—C—H \\ | \\ CH_3 \end{array}$$

lactic-acid bacterium any bacterium in which lactate is the main metabolic product. Such bacteria belong chiefly to the genera *Lactobacillus* and *Streptococcus*, and some are of commercial importance, e.g. in the manufacture of fermented foods.

lactic-acid cycle *an alternative name for* **Cori cycle**.

lactic-acid fermentation *a general name for* **heterolactic fermentation** and/or **homolactic fermentation**.

lactic acidosis a clinical condition of persistent raised blood lactate concentration, usually above 5 mmol $L^{–1}$, with a lowered blood pH. It may be caused by severe exercise, cardiovascular insufficiency, hypoxia, shock, drug intoxication, and some inborn errors of metabolism. *Compare* **hyperlactatemia**.

lacticin any of a family of pore-forming peptidic toxins with about 50 amino acid residues, permitting passage of small solutes, including water. They are produced by *Lactobacillus lactis* and are classified in the TC system under number 1.A.27.

lactide any intermolecular cyclic ester formed by self-esterification from two (or more) molecules of a hydroxy carboxylic acid. *Compare* **lactone**.

lactifer a special cell, found in the bark of the rubber tree (*Hevea*), in which rubber latex accumulates.

lactim any intramolecular cyclic carboximidic acid produced by the formal removal of a molecule of water between the amino and the carboxyl groups of an amino carboxylic acid other than an *α*-amino acid. A prefix (as in *β*-lactim) may be used to designate the position of the amino group in the parent compound. A lactim commonly exists in tautomeric equilibrium with its corresponding **lactam**.

lactitol 4-*O*-*β*-D-galactopyranosyl-D-glucitol; a disaccharide used as a sweetener.

lacto+ *or (before a vowel)* **lact+** *comb. form* indicating milk.

lactobacillic acid (1*R*-*cis*)-2-hexylcyclopropanedecanoic acid; 11,12-methyleneoctadecanoic acid; a lipid constituent of various microorganisms, including *Lactobacillus arabinosus*.

Lactobacillus a genus of Gram-positive, anaerobic or facultatively aerobic, straight or curved bacilli or coccobacilli. Their metabolism is fermentative and all species form lactate as the major end product of glucose fermentation. Various species of lactobacilli are important in the preparation of certain fermented foods, e.g. cheese, yoghurt, sauerkraut.

***Lactobacillus bulgaricus* factor** *an alternative name for* **pantetheine**.

***Lactobacillus casei* factor** *an alternative name for* **folic acid**.

lactobionic acid the **aldonic acid** obtained by the oxidation of lactose.

lactochrome *a former name for* **riboflavin**.

lactocin any of a family of pore-forming peptidic toxins with about 25 amino acid residues, permitting passage of small solutes, including water. They are produced by *Lactobacillus sake* and are classified in the TC system under number 1.A.23.

lactococcin designation of three different families of peptidic pore-forming toxins, produced by Gram-positive bacteria; they contain 65–75 amino acid residues (lactococcin A family, TC 1.C.22), or 40+35 amino acid residues (lactococcin G family, TC 1.C.25) or 50–100 amino acid residues (lactococcin 972 family, TC 1.C.37).

lactoferrin *or* **lactotransferrin** a **transferrin** present in milk. Its level in human plasma may be elevated in pancreatitis.

lactoflavin *or* **lactoflavine** *a former name for* **riboflavin**.

lactogen 1 any agent that stimulates the secretion of milk. **2 placental lactogen** *an alternative name for* **choriomammotropin**. **—lactogenic** *adj.*

lactogenic hormone *an alternative name for* **prolactin**.

β-lactoglobulin *see* **beta lactoglobulin**.

lactonase 1 EC 3.1.1.17; *recommended name*: gluconolactonase; *sys-*

tematic name: D-glucono-1,5-lactone lactonohydrolase; *other name*: aldonolactonase. An enzyme that catalyses the reaction:

D-glucono-1,5-lactone + H_2O = D-gluconate;

it also acts on a wide range of hexono-1,4-lactones. **2** **1,4-lactonase** *or* **γ-lactonase** EC 3.1.1.25; an enzyme that specifically hydrolyses 1,4-lactones having 4–8 carbon atoms to the corresponding 4-hydroxyacids.

lactone any intramolecular cyclic ester produced by the formal removal of a molecule of water between the hydroxyl and the carboxyl groups of a molecule of a hydroxy carboxylic acid other than an *α*-hydroxy acid. A prefix (as in *β*-lactone) may be used to designate the position of the hydroxyl group in the parent compound. *Compare* **lactide**.

lactoperoxidase *a special name for* **peroxidase** (def. 2) from milk. It also catalyses the oxidation of iodide to iodine, hence it is useful in radioiodine labelling of proteins and other biological materials under mild conditions.

lactose *or (formerly)* **milk sugar** *the trivial name for* the **disaccharide** 4-*O*-*β*-D-galactopyranosyl-D-glucose. It constitutes roughly 5% of the milk of almost all mammals (human milk 6.7%; cow's milk 4.5%). It occurs rarely in plants, e.g. in the anthers of *Forsythia* spp. *See also* **allolactose**.



lactose fermenter *jargon term for* any genus, species, or strain of microorganism that ferments lactose.

lactose intolerance a syndrome occurring in humans with congenital or acquired intestinal **lactase deficiency** in response to the ingestion of lactose (in milk). The failure to hydrolyse lactose leads to its accumulation in the intestine and consequent osmotically induced net fluid secretion into the gut, rapid intestinal transit, and acid stools due to bacterial fermentation of lactose. The condition is particularly prevalent in the Orient.

lactose operon *see* ***lac***.

lactose permease an H^+–lactose symporter in *Escherichia coli*. It has 12 transmembrane helices but is not very closely related to most other members of the superfamily.

lactose synthase EC 2.4.1.22; *systematic name* UDPgalactose:D-glucose 4-*β*-D-galactotransferase; *other name*: UDPgalactose–glucose galactosyltransferase. An enzyme that catalyses the reaction:

UDPgalactose + D-glucose = UDP + lactose.

In mammary gland the protein comprises *N*-acetyllactosamine synthase, the A protein, and α-lactalbumin (*see* **lactalbumin**), the B protein, both of which are required for lactose synthesis.

lactose-tolerance test a procedure used in the investigation of suspected **lactase deficiency**. Blood-glucose concentrations are estimated before an oral dose of lactose (1 g per kg body mass) and thereafter at 30-min intervals for 2 h. In normal individuals an increase of at least 30 mg per 100 ml (0.167 mM) in the blood-glucose concentration above the fasting value is observed.

lactosuria the presence of lactose in the urine. It is not uncommon during late pregnancy and lactation, or if the flow of milk is prevented.

lactosyl either of the glycosyl groups formed from lactose by detaching the anomeric (*α* or *β*) hydroxyl group on C-1.

lactotransferrin *an alternative name for* **lactoferrin**.

lactotroph any of a class of irregular, granulated, acidophilic cells of the anterior pituitary gland that secrete prolactin. Their number increases greatly during pregnancy.

lactotrophic describing any agent that induces normal growth and development of the mammary gland and sustains it.

lactotropic describing any agent that acts on the mammary gland to induce changes in its metabolism.

lactotropic hormone *an alternative name for* **prolactin**.

lactotropin *an alternative name for* **prolactin**.

lactoyl the acyl group, CH_3–CH(OH)–CO–, derived from lactic acid.

lactulose *the trivial name for* 4-*O*-*β*-D-galactopyranosyl-D-fructofuranose; a semisynthetic disaccharide, prepared from lactose, that is sweeter than lactose but less sweet than sucrose. Concentrated solutions of lactulose are useful clinically as an osmotic laxative.

lactyl *a former term for* **lactoyl**.

lacY a gene in *Escherichia coli* for **lactose permease**.

lacZ a gene in the *lac* operon of *E. coli* encoding β-galactosidase, it is widely used as a reporter gene.

***lacZ*delta M15** a mutant form of the *E. coli* β-galactosidase gene in which the sequence encoding the N-terminal region corresponding with the α-peptide is deleted. *E. coli* strains carrying this deletion are used to test for a-complementation.

LAD *abbr. for* **leukocyte adhesion deficiency**.

ladder *informal*, one of many types of DNA molecular size markers, an example is the 1kb ladder.

L1 adhesion molecule a type I membrane glycoprotein involved in neuron–neuron adhesion, neurite fasciculation, outgrowth of neurites, etc. It is a member of the immunoglobulin superfamily, and has fibronectin domains.

Laetrile *see* **amygdalin**.

laevo- *a variant spelling (esp. Brit.) of* **levo-**.

laevo+ *a variant spelling (esp. Brit.) of* **levo+**.

laevodopa *a variant spelling (esp. Brit.) of* **levodopa**.

laevorotation *a variant spelling (esp. Brit.) of* **levorotation**.

laevulose *a variant spelling (esp. Brit.) of* **levulose**.

LAF *abbr. for* lymphocyte-activating factor (i.e. **interleukin 1**).

laforin a protein-tyrosine phosphatase present in many tissues. Mutations lead to Lafora disease, a progressive myoclonus epilepsy with intellectual decline, accumulation of glycogen in brain, skin, and liver, and early death.

lagging strand the DNA strand that is synthesized by the joining together of short **Okazaki fragments**, giving the effect of continuous 3′ to 5′ synthesis in the direction of fork movement during the discontinuous replication of duplex DNA. *Compare* **leading strand**.

lag phase **1** the initial phase of the growth of a bacterial culture during which the rate of increase of cell numbers remains static, before rising to a value determined by environmental conditions. The extent of the lag phase is determined by the cultural history of the cells of the inoculum and the chemical and physical conditions of the medium into which they are placed. **2** a period of comparatively low activity after the start of an enzymic reaction that involves enzymes that act at a surface, e.g. phospholipases. It is due to the slow formation of the complex between the enzyme and the substrate interface. Once this has been formed the reaction accelerates.

lake to lyse erythrocytes, especially by suspending them in a hypotonic medium.

Laki–Lorand factor *abbr.*: LLF *or* L-L factor; *an alternative name for* factor XIII; *see* **blood coagulation**.

lambda *symbol*: λ (lower case) *or* Λ (upper case); the eleventh letter of the Greek alphabet. For uses *see* **Appendix A**.

lambda chain *or* **λ chain** *symbol*: λ; one of the two types of **light chain** of human immunoglobulins, the other type being a kappa chain.

lambda DASH a proprietary bacteriophage λ replacement vector used for cloning DNA fragments of up to 20 kb.

lambda FIX a proprietary bacteriophage λ replacement vector used for cloning DNA fragments of up to 20 kb.

lambda gt10 a bacteriophage λ insertion vector used for cloning DNA fragments of up to 8 kb.

lambda gt11 a bacteriophage λ insertion vector used for cloning DNA fragments of up to 8 kb and designed to allow expression of proteins encoded by DNA inserts.

lambda insertion vector one of a number of bacteriophage λ cloning vectors in which the cloned sequence is inserted into a single restriction endonuclease site. The size constraints on packaging bacteriophage λ recombinant DNA limits the size of insert to <8 kb, consequently making them most suitable for cloning cDNA.

lambda phage *or* **λ phage** a **temperate phage** that infects *Escherichia coli* and contains linear duplex DNA, which circularizes during infection; the genome is 48 514 bp. Important gene clusters include those for the head and tail genes, recombination (*att*, *int*, *xis*, *α*, *β*, *γ*), lysis, and regulatory genes. Of the regulatory genes (*c*III, *N*, *c*I, *cro*, *c*II, *O*, *P*, *Q*), two are immediate-early genes, *cro* and *N*; *cro* prevents synthesis of the repressor (*see* **prophage**) and turns off expression of immediate-early genes, including itself, after its product, cro, binds to *O*. Lambda phage is an example of the antitermination mechanism of phage control (*see* **antiterminator**); *N* codes for an antitermination factor that allows transcription to proceed through the terminator to the delayed-early genes, *c*II and *c*III, and *Q* codes for an antitermination factor that allows host RNA polymerase to proceed to the late (lytic) genes. The lytic cycle is repressed by expression of *c*I, the product of which acts at the operator *O* to prevent use of the promoter *P*. Lambda phage has been widely used as a vector in cDNA technology; foreign DNA can be inserted into the chromosome, and some foreign genes can be expressed using the lambda promoters. The linear DNA has cohesive ends that, when the DNA circularizes, associate to form the ***cos* site** (cohesive end site), which is important in packaging. The *cos* site has been exploited in the formation of **cosmids**.

lambda pipette *colloquial term for* a pipette used for the transfer of volumes in the microlitre range.

lambda replacement vector one of a number of bacteriophage λ cloning vectors designed for the cloning of DNA inserts of up to 20kb. The size constraints on packaging bacteriophage λ recombinant DNA necessitates the removal of a 'stuffer fragment' located between a pair of identical restriction endonuclease sites before the insertion of the DNA to be cloned. They are used for cloning fragments of genomic DNA.

lambda repressor *or* **λ repressor** the product of gene *c*I; it is responsible for maintenance of phage λ **prophage**. Its product binds to the operator associated with the RNA polymerase promoter, thus preventing RNA polymerase from initiating transcription. The phage genome then cannot enter the lytic cycle. Mutants in this gene cannot maintain **lysogeny**.

lambda ZAP a proprietary bacteriophage λ insertion vector in which DNA fragments of up to 8 kb are cloned into the multiple cloning site of the pBluescript plasmid incorporated between the left and right arms of the λ vector. The vector permits the excision of the plasmid with its insert in the form of bacteriophage M13 when *E. coli* strains infected with λZAP are superinfected with M13 helper phage.

Lambert–Beer law *another name for* **Beer–Lambert law**.

Lambert's law (of absorption) a physical law in which **Bouger's law** was re-expressed; put into modern terms, it states that the fraction of monochromatic light (or other electromagnetic radiation) absorbed by a system is independent of the incident **radiant power**, Φ_0. The law holds only if Φ_0 is small and other factors such as reflection, scattering, and photochemical reactions are negligible. *See also* **Beer–Lambert law**. [After Johann Heinrich Lambert (1728–77), German mathematician and physicist who stated it in 1760.]

lamella (*pl.* **lamellae**) any thin layer, membrane, or platelike structure, e.g. one of the series of double membranes that carry the photosynthetic pigments in chloroplasts, one of the thin layers of calcified bone matrix, or one of the spore-bearing gills of the fruiting bodies of mushrooms or related fungi. —**lamellar** *or* **lamellate** *adj.*

lamellar phase one type of **liquid-crystalline phase**.

lamin any of a group of intermediate-filament proteins that form the fibrous matrix (**nuclear lamina**) on the inner surface of the nuclear envelope. They are classified as lamins A, B, and C. *See also* **gliadin**.

lamina (*pl.* **laminae**) **1** any thin plate or layer, e.g. of bone or mineral. **2** *(in botany)* **a** the blade of a leaf or petal. **b** the flattened part of the thallus of certain algae. *See also* **basal lamina**, **nuclear lamina**. —**laminar** *adj.*

laminar flow a form of nonturbulent flow of a fluid in which parallel layers (laminae) of the fluid are moving in the same direction but with different velocities.

laminar-flow cabinet *another name for* **safety cabinet**.

laminaribiose the disaccharide, 3-*O*-*β*-D-glucopyranosyl-D-glucose; a unit of the seaweed polysaccharide **laminarin**.



pyranose form

laminarin a *β*-1,3-glucan reserve polysaccharide in some brown algae (*Laminaria* spp.). It contains **laminaribiose**.

laminin a glycoprotein that is the major constituent of basement membranes. It consists of three chains, bound to each other by disulfide bonds into a cross-shaped molecule having the appearance of one long and three short arms, with globules at each end (the three chains are wound together in a helical conformation for two thirds of their length, but diverge at the N-terminal end into the three arms that form the apex and side arms of a cross). The molecule interacts with procollagen type IV. Laminin mediates the attachment, migration and organization of cells into tissues during embryonic development by interacting with other extracellular-matrix components. Laminins of varying composition and sequence have been categorized as laminins 1 to 5. Laminin 5 is also known as **kalinin**.

laminin receptor any protein, especially an **integrin** (*see also* **VLA**), that binds laminin, interacting with it to promote cell adhesion and migration.

Lamm equation a general hydrodynamic equation describing the mass transport of a two-component system during ultracentrifugation. It is:

$$dc_2/dt = (1/x)\,d\{x[D(dc_2/dx) - c_2 s\,\omega^2 x]\}/dx,$$

where c_2 is the concentration of solute molecules at distance x from the axis of rotation, D is the translational diffusion constant, ω is the angular velocity, and s is the sedimentation coefficient.

LAMP *abbr. for* **1** lysosomal-associated membrane protein. One of three membrane glycoproteins that shuttle between lysosomes, endosomes and the plasma membrane. They are heavily glycosylated and are thought to protect lysosomal membranes from attack by lysosomal enzymes. LAMP-1 deficient mice have a mild phenotype but LAMP-2 deficient mice have severe symptoms arising from the accumulation of autophagic vesicles in numerous tissues. LAMP-2 deficiency is the primary defect in Danon disease, a lysosomal glycogen storage disease with normal acid maltase activity. LAMP-3 is CD63 a member of the **tetraspanin** superfamily. **2** Linux Apache MySQL PHP; a popular software raft for a WWW server, relational database, and interrogatory software.

lampbrush chromosome any of the large diplotene chromosomes found in the oocytes of many animals. They are up to 1mm long and are covered with loops projecting in pairs from most chromomeres; each loop has a core of DNA and is the site of active gene expression.

lamprin a self-aggregating extracellular cartilage protein of lampreys, aggregates of which form fibres rich in beta structure. It is a major structural protein isolated from the annular cartilage of the lamprey, similar in amino-acid composition to **elastin**, but it does not contain desmosine or isodesmosine.

Lan *symbol for* lanthionine.

lan+ *comb. form* indicating wool. [From Latin *lana*, wool.]

Landsteiner–Weiner antigen *abbr.*: LW antigen; *see* **Rhesus factor**.

lane any of a set of parallel tracks resulting from the simultaneous separation of similar samples by one-dimensional zone electrophoresis or chromatography in thin-layer media.

Langendorff perfused heart a nonworking rodent heart preparation maintained *in vitro* by perfusion into the aorta with an oxygenated fluid so that the fluid circulates primarily into the coronary arteries. It is useful for studying the metabolism of heart muscle. A number of improvements of the original preparation have been made since its introduction. [After O. Langendorff (1853–1909), German physiologist.]

Lang–Levy pipette a type of constriction micropipette (5–500 μL) that is self-adjusting and very reproducible.

Langmuir adsorption isotherm an equation describing the fraction of the surface of an adsorbent covered with a monomolecular layer of an adsorbed gas, arrived at from a consideration of the number of gas molecules striking and leaving the surface in a given time. It is:

$$V/V_m = k_1p/(1 + k_2p),$$

where V is the volume of gas adsorbed, V_m is the volume of gas required to cover the whole surface, p is the gas pressure, and k_1 and k_2 are constants for the system. *Compare* **Hill–Langmuir equation**. [After Irving Langmuir (1881–1957), US physical chemist and inventor.]

Langmuir–Blodgett multilayer a thin film of oriented amphiphilic molecules, consisting of superposed monolayers built up by successive dipping and withdrawing of a solid substrate, e.g. a glass slide, through an insoluble monolayer of an appropriate amphiphilic substance (or mixture of such substances) spread on the surface of an aqueous solution and kept at constant pressure. [After Irving Langmuir and Katharine B. Blodgett (1898–1979).]

Langmuir trough an apparatus for measuring the dependence of the surface force exerted by a film of a substance (of low vapour pressure), floating on a liquid with which it is immiscible, on the area of the film. The apparatus consists of a rectangular tank containing the subnatant liquid, e.g. water, on which a known amount of the immiscible substance, e.g. an oil or a higher fatty acid, is spread between two parallel barriers to form a film. One of the barriers is fixed and the other may be moved so as to compress the film to a predetermined area. The force exerted on the film to achieve any given area is measured by a system of levers and either a torsion wire or balancing masses.

lanolin *or* **wool fat** the fatlike secretion of the sebaceous glands of sheep that is deposited onto the wool fibres. It is a wax consisting of esters and polyesters of over 30 aliphatic, steroid, and triterpenoid alcohols and a similar number of fatty acids. Lanolin normally contains 25–30% water and is widely used as an ointment base. *See also* **lan+**.

lanosterol kryptosterol; lanosta-8,24-dien-3*β*-ol; a steroid alcohol (triterpene) originally obtained from **lanolin**. It occurs in the biosynthetic pathway from squalene 2,3-epoxide to cholesterol in animals and fungi, but not in photosynthetic tissues, where it is replaced by **cycloartenol**. *See also* **lanosterol synthase**.



lanosterol synthase EC 5.4.99.7; *other names*: 2,3-epoxysqualene–lanosterol cyclase; oxidosqualene–lanosterol cyclase (*abbr.*: OSC); an enzyme of the pathway for the synthesis of sterols. It catalyses the cyclization of (*S*)-2,3-epoxysqualene to lanosterol.

lantern *see* **firefly lantern**.

lanthanoid *or* **lanthanide** *or* (*formerly*) **lanthanon** any member of the series of 15 metallic elements with atomic numbers 57 (lanthanum) to 71 (lutecium) inclusive that occur together in group 3 and period 6 of the IUPAC **periodic table**; sometimes the term is restricted to the 14 elements following lanthanum. Lanthanoid is now the preferred name. Together with the elements scandium and yttrium, the lanthanoids are known also as **rare-earth elements** *or* (*more loosely*) **rare earths** (the latter term referring strictly to their oxides). They mostly occur widely in nature, albeit in small amounts. Apart from the element of atomic number 61 (promethium), all lanthanoids have at least one stable nuclide and occur naturally, the principal source being the mixed phosphate ore monazite. All nuclides of promethium, however, are radioactive, and (except for traces possibly occurring as a fission product of natural uranium) all are artificial. The lanthanoids are strongly electropositive, and their chemical properties are similar, due usually to the filling of an inner electron subshell (4f) progressively across the series. Like the **actinoids**, they thus represent a series of inner transition elements within the series of **transition elements** embraced by groups 3 to 11 inclusive. Some paramagnetic lanthanoid ions induce strong shifts in the positions of many NMR spectral peaks and have been used as relaxation and shift probes in structural studies employing NMR spectroscopy.

lanthionine (2*S*,6*R*)-lanthionine, *meso*-lanthionine, *S*-(alanin-3-yl)-L-cysteine, 2,2′-diamino-3,3′-thiobis(propionic acid); *symbol* (recommended):

$$\begin{array}{c}\text{Ala}\\ |\\ \text{Cys}\end{array}$$

or Lan; a di(*α*-amino acid) found in **lantibiotic** polypeptides. It is formed as a post-translational modification, the first step involving dehydration of a Ser to the *α*,*β*-unsaturated amino-acid residue, 2,3-didehydroalanine. A bond is then formed between the $=CH_2$ group thus formed and the sulfur atom of a cysteine, inversion of configuration of the *α* carbon of the Ser-derived moiety occurring in the process. Chick embryo protein contains the (2*R*,6*R*) diastereoisomer. Lanthionine is also formed artefactually by the mild alkaline treatment of wool, hence its name (*see* **lan+**).



(2*S*,6*R*)-lanthionine

lantibiotic any of a number of polypeptides, of 1.89–4.63 kDa, that contain **lanthionine** or methyllanthionine (*threo*-*β*-methyllanthionine, (2*S*,3*S*,6*R*)-3-methyllanthionine), and have antibiotic action. They are produced by, and primarily act on, Gram-positive bacteria. In addition to lanthionines, they contain the amino acids 2,3-didehydroalanine (*abbr.*: Dha) and 2,3-didehydrobutyrine (2-aminocrotonic acid, (*Z*)-2-aminobut- 2-enoic acid, *abbr.*: Dhb), resulting from dehydration of serine and threonine residues respectively. These amino acids are formed post-translationally from normally-coded amino acids. Lantibiotics are broadly divided into type A, elongated amphiphilic peptides, and type B, compact globular peptides. Type-A peptides kill bacterial cells by forming pores in the cytoplasmic membrane, type-B peptides possibly acting by enzyme inhibition.

LAP *abbr. for* **1** lamin-associated protein; any of the integral proteins of the inner nuclear membrane that bind to **lamins**. LAPs include several isoforms of LAP1 and LAP2, lamin B receptor, and emerin. **2** *(in clinical chemistry)* leucine aminopeptidase (LAS preferred).

LA-PF4 *abbr. for* low-affinity platelet factor 4; *other name*: connective-tissue activating peptide III (*abbr.*: CTAP-III). A protein (83 amino acids) derived from **platelet basic protein precursor** (94 amino acids). It stimulates DNA synthesis, mitosis, glycolysis, intracellular cyclic AMP accumulation, prostaglandin E_2 secretion, and synthesis of hyaluronic acid and sulfated glycosaminoglycan.

Laplace transform method a method that enables solutions of linear differential equations with constant coefficients to be found by reference to tables of Laplace transform pairs, with a minimum of mathematical work. The Laplace transform of a function $y = F(t)$ is defined by:

$$F(s) = \int_0^\infty e^{-st}F(t)\mathrm{d}t$$

in which s is usually a complex quantity and must have a positive real term, so that e^{-st} will be zero when $t = \infty$. [After Pierre Simon, Marquis de Laplace (1749–1827), French astronomer and mathematician.]

Largactil *see* **chlorpromazine**.

large calorie *an alternative name for* **kilocalorie** *or* (*in nutrition*) **Calorie**.

large-patch repair (of DNA) *a name sometimes given to* the process of excision repair of duplex DNA in some mutant organisms, e.g. *polA⁻ Escherichia coli*, in which the newly synthesized polynucleotide 'patch' is considerably larger than in the wild type.

large T-antigen *see* **T antigen** (def. 1).

lariat a lasso-shaped structure formed from the fragment of RNA to be excised during the process of splicing out the introns in the primary transcript of eukaryotic genes.

lariat debranching enzyme an enzyme that cleaves the 2′,5′-phosphodiester bond formed during pre-mRNA splicing between the 5′-terminal guanylyl residue of the intron and an adenylyl residue near the 3′ splice site, at the branch point of excised intron lariats. It is involved in the turnover of excised introns.

Larmor frequency the angular frequency of **Larmor precession** of an atomic electron.

Larmor precession the **precession** of a charged particle moving under the influence of a central force, e.g. of an orbiting electron in an atom, when acted on by an external magnetic field. [After Joseph Larmor (1847–1942), Irish-born physicist.]

LAS *(in clinical chemistry) abbr. for* leucine aminopeptidase (preferred alternative to LAP).

lasalocid *or* **X-537A** any of five closely related lipophilic antibiotics, lasalocids A–E, isolated from cultures of *Streptomyces lasaliensis*. Lasalocid A ($M_r = 591$) is a carboxylic ionophore for virtually every known cation, but transports monovalent cations about ten times more effectively than divalent cations.

lased light *an imprecise term for* laser light; *see* **laser** (def. 2).

laser 1 any device for producing an intense, coherent, monochromatic, parallel beam of light (or other electromagnetic radiation) by stimulated emission. A laser consists of an optically transparent cylinder containing an active medium bounded by a full mirror at one end and by a partial mirror at the other end. Some chemical species of the medium are excited above their ground state by application of electromagnetic radiation from an external source; the excited species revert to their ground state with the emission of a photon, which in turn can collide with other excited species to produce stimulated emission of other photons. **2** having the characteristic quality of, being, or using, light emitted by a **laser** (def. 1), as in laser densitometry, laser ionization (micro) mass spectrometry, laser light, laser microprobe mass analysis, laser nephelometry, laser photolysis, laser (light) scattering, laser spectrophotometry, and laser velocimetry. [Acronym from light amplification by stimulated emission of radiation.]

Latapie mincer a device for mincing tissues for metabolic studies in which both the rate of rotation of the cutting disks and the rate at which the tissue is forced against these disks may be controlled by varying the rates at which two cranks are turned, thus enabling minces of different degrees of fineness to be obtained. Sterile conditions may be maintained during the mincing if desired.

late enzyme *see* **late gene**.

late gene any gene of a bacteriophage or other viral genome that is expressed significantly, as a **late enzyme** or other **late protein**, only after replication of the genome has started. *Compare* **early gene**.

latency 1 *or* **crypticity** the state or quality of being **latent**. **2** *an alternative term for* **latent period**.

latent 1 existing in a potential, dormant, or suppressed form but usually capable of being expressed or evoked. **2** *(in pathology)* (of an infection or disease) not yet manifest or apparent.

latent enzyme any enzyme whose activity only becomes manifest when the conditions are changed. The term is used especially of a particulate enzyme that becomes active when the particles are disrupted.

latent heat *symbol*: L; the change in the heat content of a (given amount of) substance when it changes phase without change in its temperature.

latent image *(in photography)* the invisible image produced by the action of light, etc. on the photosensitive emulsion that is made visible by development.

latent period *or* **latency 1** the time between the arrival of a stimulus at an irritable tissue and the beginning of the appropriate response. **2** the time between the adsorption of virulent bacteriophage onto a bacterium and lysis with liberation of newly formed virions.

late protein *see* **late gene**.

lateral gene transfer *or* **horizontal gene transfer** the transfer of genes between species, e.g. for antibiotic resistance in bacteria.

lateral phase separation the phenomenon of coexistence of solid and liquid regions in a lipid bilayer at temperatures between the **pretransition temperature** and the **transition temperature**.

lathyrism any abnormal state that results from ingesting any of several toxins found in plants of the genus *Lathyrus*. In humans one kind is characterized by a spastic paraplegia of the lower extremities associated with degenerative changes in the lateral pyramidal tracts of the spinal cord. It is caused by ingestion of neurotoxins, e.g. β-cyano-L-alanine and L-α,γ-diaminobutyric acid. These are also present in the common vetch (*Vicia sativa*). In experimental animals a defect of cross-linking of collagen is caused by feeding sweet pea (*Lathyrus odoratus*) seeds; the toxic substance was identified as β-(γ-L-glutamyl)aminopropionitrile but β-aminopropionitrile alone is fully active. Turkeys fed *L. odoratus* died of hemorrhage from rupture of the aorta.

lathyrogen any substance that on ingestion induces the disease **lathyrism**.

Latin square *(in statistics)* a square array of *n* columns and *n* rows containing *n* different elements and in which no element occurs more than once in any row or column. It is used as a basis of experimental procedures when it is desired to allow for two sources of variability while investigating a third.

LATS *abbr. for* long-acting thyroid stimulator.

lattice 1 any regular array of objects or points in two or three dimensions. **2** *(in crystallography)* any regular, three-dimensional array of fixed points about which atoms, ions, or molecules vibrate in a crystal. **3** *(in immunology)* the three-dimensional aggregate suggested to be built up in an antigen–antibody reaction (*see* **lattice hypothesis**).

lattice energy (of a crystal) the energy that would be required to separate the ions of a crystal to an infinite distance from each other.

lattice hypothesis a hypothesis describing antigen–antibody reactions in terms of the building up of large antigen–antibody aggregates or three-dimensional lattices. The hypothesis requires both antigen and antibody to have valencies greater than one.

Lau *symbol for* the dodecanoyl (i.e. **lauroyl**) group.

Laue equation any of a set of three equations describing the occurrence, positions, and intensities of X-ray beams after diffraction by a crystal. For three crystal axes, *x*, *y*, and *z*, with separations of chemical entities along them of *a*, *b*, and *c*, respectively, the equations are:

$$a(\cos\alpha - \cos\alpha_0) = h\lambda,$$

$$b(\cos\beta - \cos\beta_0) = k\lambda,$$

and

$$c(\cos\gamma - \cos\gamma_0) = l\lambda,$$

where α_0, β_0, and γ_0 are the angles that the incident beam makes with the *x*, *y*, and *z*, axes, respectively, and α, β, and γ are the corresponding angles for the diffracted beam; λ is the wavelength of the radiation and *h*, *k*, and *l* are integers corresponding to the **Miller indices** of the planes considered to be diffracting the radiation. *See also* **Bragg's law**. [After Max Theodor Felix von Laue (1879–1960), German physicist.]

Laue photograph *or* **Laue pattern** the spot diagram produced when a heterogeneous beam of X-rays is diffracted by passage through a crystal.

laurate 1 *the trivial name for* dodecanoate, $CH_3–[CH_2]_{10}–COO^-$, the anion derived from lauric acid (i.e. dodecanoic acid), a saturated straight-chain higher fatty acid. **2** any mixture of free lauric acid and its anion. **3** any salt or ester of lauric acid. Dodecyl laurate is one of the main components of laurel oil, the oil obtained from berries of the laurel plant, *Laurus nobilis*. Laurate is present in appreciable amounts in hydrolysates of phosphoglycerides of plants and animals.

Laurell technique *an alternative name for* **rocket immunoelectrophoresis**. [After C.-B. Laurell, Swedish biochemist.]

lauroyl *or (formerly)* **lauryl** *symbol*: Lau; *the trivial name for* dodecanoyl, $CH_3-[CH_2]_{10}-CO-$, the acyl group derived from lauric acid (i.e. dodecanoic acid). It occurs in natural lipids, mainly as acylglycerols.

lauryl 1 *symbol*: Dod; *a common name for* dodecyl, $CH_3-[CH_2]_{10}-CH_2-$, the alkyl group derived from dodecane; use deprecated. **2** *a former trivial name for* dodecanoyl (lauroyl now used).

lauryldimethylamine oxide *abbr*.: LDAO; *N*,*N*-dimethyl-*N*-dodecylamine oxide; a water-soluble, zwitterionic (at pH 7 or above) detergent, aggregation number 76, CMC 1–2 mM.



$$CH_3(CH_2)_{11}-\underset{\underset{CH_3}{|}}{\overset{\overset{O}{\uparrow}}{N}}-CH_3$$

lauryl sulfate, sodium salt *an alternative name for* **sodium dodecyl sulfate**.

lavendustin any substituted amino salicylic acid that is used as a protein tyrosine kinase inhibitor. Lavendustin A is 5-amino-[(*N*-2,5-dihydroxybenzyl)-*N′*-2-hydroxybenzyl]aminosalicylic acid and lavendustin C is 5-(*N*-2,5-dihydroxybenzyl)aminosalicylic acid. Lavendustin A inhibits protein-tyrosine kinase activity with little effect on cyclic AMP-dependent kinase or protein kinase C. Lavendustin C is similar but also inhibits Ca^{2+}/calmodulin kinase II.



lavendustin A

lawn a layer of microorganisms uniformly distributed in or over the surface of a solid culture medium.

law of conservation of energy *see* **thermodynamics, laws of**.

law of independent assortment *see* **Mendel's laws of heredity**.

law of mass action *see* **mass action**.

laws of thermodynamics *see* **thermodynamics**.

lawsone 2-hydroxy-1,4-naphthoquinone; the active dyeing compound of **henna**.



layer line one of the parallel lines of spots obtained on the photographic plate in the rotating crystal method of X-ray diffraction analysis.

lb *symbol for* pound.

LB *abbr. for* Luria-Bertani medium a synthetic culture medium commonly used for the growth of bacteria.

LBF *abbr. for Lactobacillus bulgaricus* factor (*see* **pantetheine**).

L-bifunctional enzyme *see* **peroxisomal bifunctional enzyme**.

LC *abbr. for* liquid chromatography.

LCAD *abbr. for* long-chain acyl-CoA dehydrogenase; *see* **beta-oxidation system**.

LCAT *abbr. for* lecithin–cholesterol acyl transferase.

LCD *abbr. for* liquid-crystal display.

L cell *an alternative name for* **EG cell**.

L chain *see* **light chain** (def. 1).

LCK a gene family encoding nonreceptor tyrosine kinases (e.g. p56^{lck} *or* lymphocyte-specific protein-tyrosine kinase) of the Src family (*see* ***src***), first detected in the LSTRA murine lymphoma cell line. The product is lymphocyte-specific and is activated by binding to the intracellular domains of CD3 and CD4 in T lymphocytes. The mitogen-activated protein (MAP) kinase is a substrate for p56^{lck} , which is a myristoylated protein with SH2 and SH3 domains. A rare mutation in the gene at 1p35-p34.3 leads to Lck deficiency and a form of severe combined immunodeficiency.

LCR *abbr. for* **1** locus control region. **2** ligase chain reaction.

LD *abbr. for* **1** lethal dose. **2** *(in clinical chemistry)* L-lactate dehydrogenase (alternative to LDH); *see also* **HBD**. **3** low density.

LD$_{50}$ *abbr. for* median lethal dose.

LDH *abbr. for* L-lactate dehydrogenase (alternative to LD).

LDL *abbr. for* low-density lipoprotein.

LDL receptor a cell-surface receptor that binds apolipoprotein B and so internalizes **low-density lipoprotein** (LDL) from the plasma, leading to processing that regulates cholesterol and LDL synthesis, and thence plasma cholesterol concentration. It is a type I membrane protein. The number of LDL receptors on liver cells is regulated by cholesterol synthesis: when cholesterol levels rise, the number of receptors falls. Defects in this receptor are associated with certain forms of type II **hyperlipidemia**. The amino end of the extracellular domain contains seven or eight 40-residue repeats; each repeat has about six Cys residues, all of which are involved in disulfide bonds; following these repeats is a region of about 350 residues that is homologous with part of the epidermal growth factor precursor.

LDL receptor-related protein *see* **LRP**.

Le *abbr. for* Lewis antigen.

LE392 a strain of *E. coli* favoured for the propagation of bacteriophage lambda.

leaching (microbial) a process for the solubilization of metals, mostly from poor ores, by lithotrophic bacteria. *See also* **lithotroph**.

lead *symbol*: Pb; a very soft, bluish-white metallic element of group 14 of the IUPAC **periodic table**. It has a low melting point and high relative density; proton number 82; relative atomic mass 207.2. It is commonly used for shielding from ionizing radiation.

lead compound **1** *(in pharmacology)* a molecule that serves as the starting point for development of a drug, typically by variations in structure for optimal efficacity. **2** *(in chemistry)* a compound of lead (Pb).

leader peptidase EC 3.4.99.36; *other name*: signal peptidase I, phage-procoat-leader peptidase; an enzyme that catalyses the cleavage of N-terminal leader sequences from secreted proteins.

leader peptide *an alternative name for* **signal peptide**.

leader sequence *or* **lead sequence** *an alternative name for* signal sequence (*see* **signal peptide**).

leading strand the DNA strand that is synthesized continuously, in the 5′ to 3′ direction, towards the replication fork during the discontinuous replication of duplex DNA. *Compare* **lagging strand**.

lead screw a threaded rod the rotation of which is used to drive the tool carriage of a lathe, the plunger of a syringe, etc.

leaf (*pl.* **leaves**) **1** the principal organ of photosynthesis and transpiration in higher plants. It typically consists of a flattened bladelike lamina, often relatively broad, attached to the plant stem directly or by a stalk. **2** any thin, flattened object that resembles a leaf. **3** *or* **terminal tip** *(in phylogeny)* the end of a terminal branch of a phylogenetic tree. Collectively the leaves represent the contemporary taxa in a data set. *See also* **leaflet**.

leaflet **1 a** any small or young **leaf** (def. 1). **b** an individual segment of a compound leaf. **2** any small, thin, flattened object or structure that resembles the leaf of a plant, especially a lipid bilayer or a portion of a biological membrane.

leak a cellular process whereby ions or other compounds escape though a membrane, dissipating a chemical potential.

leakage *see* **leak**.

leaky *(in genetics)* describing any mutation that fails to shut off completely the activity of a gene so that some residual expression of the gene remains.

Le antigen *symbol for* Lewis antigen.

LEA protein *abbr. for* late embryogenesis abundant protein; any of the proteins expressed in seeds during maturation and desiccation. Five families have been described. These proteins are hydrophilic, cytoplasmic, and rich in glycine and alanine but lacking in cysteine and tryptophan. Their concentration increases in vegetative parts of plants exposed to water deficit. In rice, overexpression increases resistance to such stress.

least squares a statistical method for determining the 'best' value of an unknown quantity relating one or more sets of measurements or observations. It is based on minimizing the sum of the squares of the deviations of the experimentally determined values from the calculated values, and is used especially to find a curve that best fits a given set of data.

leaving group any atom or group, charged or uncharged, that departs during a substitution or displacement reaction from what is regarded as the residual or main part of the substrate of the reaction.

Lebedev-Saft *or* **Lebedev juice** an aqueous extract of air-dried yeast. It will ferment glycerone (dihydroxyacetone) and, in the presence of phosphate, produces a hexose phosphate. [After Alexander Nikolaevich Lebedev (1881–1938), Russian botanist who described the preparation in 1911.]

Leber's hereditary optic neuropathy *abbr*.: LHON; a mitochondrial disease of humans manifested as painless, subacute, bilateral visual loss with abnormal colour vision. It is associated with at least eight genes in mitochondrial DNA for components of certain complexes of the electron transport chain. [After Theodor Leber (1840–1917), German ophthalmologist.]

Le Chatelier principle *or* **Le Chatelier–Braun principle** a principle stating that when a system in equilibrium is subject to stress, i.e. to a change in its conditions, the system will adjust itself to annul, as far as possible, the effect of the stress. [First formulated (in 1885) by Henry (Louis) Le Chatelier (1850– 1936), French chemist, and independently in 1886 by Karl Ferdinand Braun (1850–1918), German physicist.]

lecithin *an old trivial name*, *still in frequent use, for* any 3-*sn*-**phosphatidylcholine**.

lecithinase any of a number of distinct enzymes acting on lecithins that are now usually considered among the **phospholipases**.

lecithin–cholesterol acyl transferase *abbr*.: LCAT; EC 2.3.1.43; *recommended name*: phosphatidylcholine–sterol *O*-acyltransferase; *other name*: phospholipid–cholesterol acyltransferase. An enzyme glycoprotein, secreted into plasma by the liver, that catalyses a reaction between phosphatidylcholine and cholesterol to form a cholesteryl ester and 1-acylglycerophosphocholine. This enzyme is central to the extracellular metabolism of plasma lipoproteins; it acts on free cholesterol in the high-density lipoprotein (HDL) precursor, transferring a fatty acyl group to cholesterol, thus contributing to the altered class composition of the mature HDL; some of the resulting cholesterol esters are partly taken up by low-density lipoprotein. It is activated by apolipoprotein A1, and is deficient in Norum and fish-eye diseases.

lectin any of a group of specific agglutinins and other antibody-like (glyco)proteins of non-immune origin, defined (by IUBMB) as 'sugar-binding protein or glycoprotein of non-immune origin that agglutinates cells and/or precipitates glycoconjugates'. Lectins are widely distributed in nature, being found mainly in seeds, but also in other parts of certain plants, and in many other organisms, from bacteria to mammals. Lectins bear at least two sugar-binding sites; they bind specific sugars, and thereby precipitate certain polysaccharides, glycoproteins, and glycolipids, and/or agglutinate animal and plant cells. Some can distinguish between normal and malignant cells, and many, e.g. phytohemagglutinin, are mitogenic. They are widely used experimentally, especially **concanavalin A**, as tools in carbohydrate biochemistry, for studying cell surfaces and for inducing **transformation** (def. 3) of lymphocytes. Plant lectins are also known as **phytoagglutinins**.

LED *abbr. for* light-emitting diode.

leeching a form of blood letting in which blood is removed by leeches. *Compare* **leaching**.

leghemoglobin *or (esp. Brit.)* **leghaemoglobin** a hemoglobin-like red pigment found in the root nodules of leguminous plants. An autoxidizable hemoprotein, it sequesters dioxygen to prevent inhibition of **nitrogenase** in the bacteroids. It is thus essential for symbiotic nitrogen fixation.

legumain EC 3.4.22.34; *other names*: bean endopeptidase; vicilin peptidohydrolase; phaseolin; an endopeptidase from legumes that hydrolyses Asn-|-Xaa bonds in small molecule substrates such as Boc-Asn-|-OPhNO_2.

legumin a major storage protein of the seeds of both leguminous and non-leguminous plants. It consists of two chains, derived from a common precursor: an acidic α chain and a basic β chain – these are linked by a single disulfide bond.

Leigh syndrome *or* **necrotizing encephalopathy** a devastating heterogeneous neurodegenerative disease with severe lactic acidosis. It is commonly associated with nuclear mutations in protein components of **complex I, II, III, IV**, and with a mitochondrial mutation in subunit 6 of the F_0F_1 complex of the inner mitochondrial membrane (*see* **H^+-transporting ATP synthase**). Mutations in other proteins of the mitochondrion (e.g. pyruvate dehydrogenase complex, pyruvate carboxylase) produce a very similar clinical state. [After Denis Leigh (1915–), British psychiatrist.]

LEM *abbr. for* light-effect mediator.

length *symbol*: *l or L*; a scalar physical quantity indicating linear extent; one of the seven SI base physical quantities. The SI base unit of length is the **metre**.

lens 1 a piece of glass or other transparent and refracting material, or two or more such pieces joined together, for converging or diverging a beam of light in order to form optical images. **2** any electrostatic or electromagnetic device for focusing or otherwise altering the direction of movement of a beam of electrons or other elementary charged particles; any similar device acting on sound waves. **3** *(in zoology)* any of various transparent structures responsible for focusing light onto photoreceptors. The **crystalline lens** of vertebrates is a near-spherical structure in the eye, lying in the aqueous humour behind the pupil. It focuses or assists in focusing light rays onto the retina. Enclosed within a collagenous capsule, it consists largely of cells containing proteins called **crystallins**.

lenticular 1 having the shape of a biconvex **lens** (def. 1). **2** of or pertaining to a **lens**.

lentinan a polysaccharide isolated from the edible mushroom *Lentinus edodes*. It is a β-1,3-glucan, having for every five β-1,3 linear linkages, two glucopyranoside units in β-1,6 linkage.

lentinarin *see* **callose**.

lentropin a protein, present in the vitreous humour of the eye, that stimulates lens-fibre differentiation. It is related to **insulin-like growth factors**.

Lepidoptera a large order of insects that includes butterflies, skippers, and moths. The adults are characterized by a prominent coiled proboscis and two pairs of large, scaly, membranous wings. The larvae are caterpillars. —**lepidopteran** *adj.*

leporine of, pertaining to, or resembling a rabbit or hare.

leprachaunism an autosomal recessive inherited disease characterized by small stature and elfin-like appearance, with motor and mental retardation and severe failure to thrive. Most patients die in early childhood, though a few, who are compound heterozygotes for two different alleles, survive childhood. The condition can be caused by any of a number of mutations in the gene encoding the insulin receptor.

leptin a protein encoded by a gene, *ob*, first identified as the *obese* mutation (*see* **ob/ ob**) in mice. Leptin may act as a signal in the regulation of adipose mass, possibly by regulating appetite and energy expenditure. It appears to be expressed exclusively in white adipose tissue. The sequence is largely hydrophilic, and has structural features indicative of a secreted protein. *See also* **leptin receptor**.

leptin receptor any member of a widely expressed single-pass transmembrane receptor family that binds **leptin** and exert its effects through the JAK/STAT signalling pathway. It is expressed at high levels in the hypothalamus relative to other tissues. Mutations in the receptor are responsible for *db* mice, corpulent mice, and Zucker rats, all of which are grossly obese. *See also* **diabetes mutation**, ***ob/ob***.

leptocene the first phase of prophase I in **meiosis**.

leptotene *see* **meiosis**.

Lesch–Nyhan syndrome an X-chromosome-linked, inherited disorder of male humans in which there is an almost complete deficiency of **hypoxanthine phosphoribosyltransferase** (EC 2.4.2.8), a key enzyme of the **salvage pathway** of purine metabolism. The condition is characterized by hyperuricemia, excessive uric-acid biosynthesis, and certain neurological features including self-mutilation, spasticity, and mental retardation. Over 200 mutations in the gene for **HGPRT** cause the syndrome. Death usually occurs in the second or third decade of life. [After M. Lesch (1939–), US paediatrician, and William Leo Nyhan (1926–), US physician and biochemist.]

lesion 1 *(in pathology)* a zone of tissue with impaired function resulting from damage by disease or wounding. **2** *(in biochemistry)* any deleterious disturbance of a metabolic pathway resulting from chemical interference or genetic abnormality.

+less *suffix forming adjectives and adverbs* without, lacking; unable to do or to be done. In biochemistry it is used especially of auxotrophic mutants to indicate the substance they cannot synthesize, e.g. thymineless mutant.

let23 a gene in *Caenorhabditis elegans* for a receptor **tyrosine kinase** of the epidermal growth factor family. It is probably activated by the ***lin3* product**. The product of *let23* is a type I membrane glycoprotein.

lethal dose *abbr.*: LD; the amount of a drug or other agent that when administered to an organism causes the organism's death. *See also* **median lethal dose**.

lethal factor any **lethal mutation**.

lethal gene any gene carrying a **lethal mutation**. Such mutations may only be fatal in the homozygous state.

lethal mutant any organism carrying a **lethal mutation**.

lethal mutation any **mutation** that may bring about the death of the organism before its maturity. The consequences of such a mutation may depend on whether the organism is homozygous or heterozygous for the gene in question, and possibly also on the conditions (*see* **conditional lethal mutation**).

lethal synthesis any process by which a highly toxic compound is synthesized in an organism from a nontoxic precursor. The classic example is the formation of **fluorocitrate** when e.g. kidney homogenates are incubated with **fluoroacetate**. The fluorocitrate thus formed inhibits **aconitase**.

LETS protein *abbr. for* large external transformation sensitive (glyco)protein (i.e. cellular **fibronectin**).

Leu *symbol for* a residue of the α-amino acid L-leucine (alternative to L).

leuc+ *a variant spelling of* **leuk+**. *See* **leuko+**.

leucinate 1 leucine anion; the anion, $(CH_3)_2CH–CH_2–CH(NH_2)–COO^–$, derived from **leucine**. **2** any salt containing leucine anion. **3** any ester of leucine.

leucine *the trivial name for* α-aminoisocaproic acid; α-amino-γ-methylvaleric acid; 2-amino-4-methylpentanoic acid; $(CH_3)_2CH–CH_2–CH(NH_2)–COOH$; a chiral α-amino acid. L-leucine (*symbol*: L *or* Leu), (*S*)-2-amino-4-methylpentanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: CUA, CUC, CUG, or CUU; UUA or UUG. In mammals, it is an essential amino acid, and is ketogenic. Residues of D-leucine (*symbol*: D-Leu *or* DLeu), (*R*)-2-amino- 4-methylpentanoic acid, occur in a number of peptide antibiotics, e.g. gramicidins A, B, C, and D, and polymixins D_1, D_2, E_1, and E_2.



L-leucine

leucine aminopeptidase *abbr. (in clinical chemistry)*: LAP (preferred) *or* LAS. *See* **leucyl aminopeptidase**.

leucine and valine biosynthesis the biosynthesis of leucine and valine initially follows a common pathway that commences with the formation of acetolactate from two molecules of pyruvate, a reaction catalysed by acetolactate synthase. Acetolactate is converted via α,β-dihydroxyisovalerate (2,3-dihydroxy-3-methylbutanoate) to α-ketoisovalerate (2-oxo-3-methylbutanoate). At this point the pathway branches. α-Ketoisovalerate can be converted by transamination with glutamate to valine. Alternatively, it can be converted successively to α-isopropylmalate (2-isopropylmalate), β-isopropylmalate (3-isopropylmalate), and α-ketoisocaproate (4-methyl-2-oxopentanoate), and thence by transamination with glutamate to leucine. *See also* **3-isopropylmalate dehydratase**, **3-isopropylmalate dehydrogenase**.

[5-leucine]enkephalin *abbr.*: [Leu^5]enkephalin *or* [Leu]enkephalin; *the recommended trivial name for* the pentapeptide Tyr-Gly-Gly-Phe-Leu. *See* **enkephalin**.

leucine-rich repeat *abbr.*: LRR; short sequence motif in proteins, of average length 24 residues, containing a high proportion of leucines, typically five to seven at positions 2, 5, 7, 12, 16, 21, and 24 within the repeat. Such arrays form an amphipathic sequence, with leucine as the predominant hydrophobic residue. They are believed to participate in protein–protein or protein–lipid interactions. LRRs form elongated non-globular structures, often flanked by cysteine-rich domains. They were first described in α_2-glycoprotein, but they have since been found in other proteins. The number of repeats can vary from one, in platelet glycoprotein Ibβ, to 30, in, e.g., **chaoptin**. The 3-D structure of ribonuclease inhibitor has been shown to contain 15 repeats, and has revealed LRRs to represent a new class of alpha/beta fold.

leucine zipper a domain in a protein structure in which two alpha helices containing leucines (normally four or five) repeating every seventh amino-acid residue, interdigitate in zipper fashion to stabilize the structure. Such an arrangement was originally found in DNA-binding proteins, but it is now known to occur also in other proteins, especially adjacent to proposed transmembrane regions, mediating dimerization. The abbreviation ZIP is used, e.g., in designating the **bZIP** family of proteins. *See also* **potassium channels**.

leucinium leucine cation; the cation, $(CH_3)_2CH–CH_2–CH(NH_3^+)–COOH$, derived from **leucine**.

leucino the alkylamino group, $(CH_3)_2CH–CH_2–CH(COOH)–NH–$, derived from **leucine**.

leuco+ *a variant spelling of* **leuko+**.

leucocyte *a variant spelling of* **leukocyte**.

leucyl the acyl group, $(CH_3)_2CH–CH_2–CH(NH_2)–CO–$, derived from **leucine**.

leucyl aminopeptidase EC 3.4.11.1; *other names*: leucine aminopeptidase; peptidase *S*; cytosol aminopeptidase; an enzyme that catalyses the hydrolysis of an aminoacyl-peptide to an amino acid and the residual peptide. Its action is most rapid when the N-terminal amino acid is leucine; it liberates other residues at varying rates, and acts poorly at an Xaa-Pro bond. It requires zinc, and is widely distributed in animal tissues, its level in the serum being useful clinically in monitoring hepatobiliary disease processes and placental well-being.

[Leu^5]enkephalin *or* **[Leu]enkephalin** *abbr. for* [5-leucine]-enkephalin.

leuk+ *a variant form of* **leuko+** (before a vowel).

leukemia *or (esp. Brit.)* **leukaemia** *or (sometimes)* **leukosis** any of a group of neoplastic diseases of the leukocytes, usually involving increase in the number of leukocytes in the blood. Leukemias are classified according to the type of leukocyte affected and whether the disease is acute or chronic.

leukemia inhibitory factor *abbr.*: LIF; *also called* **differentiating-stimulating factor** *or* **differentiation-inducing factor**; a **cytokine** produced by fibroblasts, T cells, and macrophages. It is a monomer of 179 amino acids that maintains the pluripotent phenotype of embryonic stem cells, and potentiates interleukin-3-dependent proliferation of hemopoietic progenitors.

leuko *or* **leuco** describing the colourless derivative formed reversibly from a coloured substance, often by reduction; e.g. leuko compound, leuko dye.

leuko+ *or* **leuco+** *or (before a vowel)* **leuk+** *or* **leuc+ 1** white or colourless. **2** denoting of, pertaining to, or acting upon a leukocyte or leukocytes.

leukocidal *or* **leucocidal** describing an agent that kills leukocytes.

leukocidin *or* **leucocidin** any extracellular bacterial product that can kill leukocytes of certain animal species and that may also be toxic or lytic towards other cell types. Leukocidins are produced by pathogenic strains of *Staphylococcus* and *Streptococcus*.

leukocyte any white blood cell, i.e. one not containing an oxygen-transporting pigment such as hemoglobin. Vertebrate leukocytes include the **polymorphonuclear leukocytes**, **lymphocytes**, and **monocytes**; they are distinguished by size, shape, and staining characteristics. —**leukocytic** *or* **leucocytic** *adj.*

leukocyte adhesion deficiency (*abbr.*: LAD) *or* **leucocyte adhesion deficiency** a condition of severe leukocytosis and recurrent infections in which leukocytes show defective migration and phagocytosis. **LAD I** is associated with mutations in a locus at 21q22.3 that cause lack of or dysfunction of **integrins** containing the β subunit (also called CD18). **LAD II** is accompanied by unusual facial appearance, short stature, and encephalopathy, and is a form of carbohydrate-deficient glycoprotein syndrome that results from defective import of GDP-fucose into the Golgi body.

leukocytosis *or* **leucocytosis** a gross increase in the number of leukocytes in the blood. It often occurs as a response to an infection. *See also* **leukemia**.

leukokinin *or* **leucokinin** a specific cytophilic immunoglobulin G (IgG) that constitutes about 2% of the total IgG. It binds specifically and reversibly to autologous polymorphonuclear leukocytes, causing 2- to 2.5-fold stimulation of their phagocytic activity. A proteinase, **leukokininase**, cleaves from leukokinin a tetrapeptide, **tuftsin**, which is thought to bear all the activity.

leukopenia *or* **leucopenia** an abnormal decrease or deficiency of leukocytes circulating in the blood. *Also (esp. Brit.)* **leukopaenia** *or* **leucopaenia**.

leukoplast *or* **leucoplast** *or* **leukoplastid** *or* **leucoplastid** any of the colourless **plastids** found in plant cells. They include **aleuroplasts**, **amyloplasts**, and **elaioplasts**. Leukoplasts may develop into **chloroplasts**.

leukopoiesis *or* **leucopoiesis** the processes by which leukocytes are formed in the body. —**leukopoietic** *or* **leucopoietic** *adj.*

leukosis *or* **leucosis** **1** a condition in which there is an abnormal proliferation of one or other of the leukocyte-forming tissues. **2** *an alternative name for* **leukemia**.

leukosulfakinin a sulfated myotropic 11-residue peptide isolated from head extracts of the cockroach. It is a homologue of human gastrin II and cholecystokinin.

leukotaxin *or* **leucotaxin** a nitrogen-containing material, found in injured tissue, that when injected into an animal causes increased capillary permeability and migration of leukocytes to the site of injection.

leukotoxin *or* **leucotoxin** **1** any compound toxic to leukocytes. **2** cytochrome P450-derived linoleic acid peroxide; any of a group of substances observed in high concentrations in burned skin samples that may have a bacteriocidal function. **Leukotoxin A** is (12*Z*)-9,10-epoxyoctadec-12-enoic acid, and **leukotoxin B** is (9*Z*)-12,13-epoxyoctadec-9-enoic acid (*abbr.*: EpODE) or, its methyl ester (*abbr.*: EpOME).

leukotriene *abbr.*: LT; any member of a family of biologically active substances derived from polyunsaturated fatty acids, notably arachidonic acid, some of which contain a peptide moiety based on cysteine. Leukotrienes are synthesized in response to specific stimuli, are formally derived from eicosanoic acid, and contain a set of three conjugated double bonds (hence 'triene'); one or two additional double bonds, not conjugated to the others, may also be present – a subscript numeral after the abbreviation indicates the total number of double bonds, depending on the polyunsaturated fatty acid from which each is derived, e.g. LTA$_4$ from arachidonic acid, LTB$_5$ from eicosapentaenoic acid. They are products of the 5-lipoxygenase pathway. LTC$_4$ consists of glutathione linked to an eicosanoid; loss of glutamic acid from this leads to LTD$_4$, and loss of glycine then leads to LTE$_4$. These three, sometimes collectively known as **peptidoleukotrienes**, are potent spasmogenic agents that make up the active components of **slow-reacting substance of anaphylaxis** (SRS-A). Leukotrienes exert their effects by binding to G-protein-associated membrane receptors. *See also* individual entries below.

leukotriene A *abbr.*: LTA; any of a group of **leukotrienes** characterized as unstable 5,6-epoxides. Leukotriene A$_4$ (*abbr.*: LTA$_4$) is (7*E*,9*E*,11*Z*,14*Z*)-(5*S*,6*S*)-5,6-epoxyeicosa-7,9,11,14-tetraen-1-oate. Leukotriene A$_3$ (*abbr.*: LTA$_3$) is similar, but lacks the double bond at the C-14, while leukotriene A$_5$ (*abbr.*: LTA$_5$) has an additional, 17*Z*, double bond. LTA$_4$ is derived from arachidonate via 5-hydroperoxyeicosatetraenoate, and is the precursor either of leukotriene B$_4$ (*see* **leukotriene B**) by the action of highly specific **leukotriene-A$_4$ hydrolase** (EC 3.3.2.6), or of **leukotriene C$_4$** by the action of leukotriene-C$_4$ synthase (EC 2.5.1.37).



leukotriene A$_4$

leukotriene-A$_4$ hydrolase *abbr.*: LTA$_4$ hydrolase; EC 3.3.2.6; an enzyme that converts (7*E*,9*E*,11*Z*,14*Z*)-(5*S*,6*S*)-5,6-epoxyeicosa-7,9,11,14-tetraenoate (LTA$_4$) to (6*Z*,8*E*,10*E*,14*Z*)-(5*S*,12*R*)-5,12-dihydroxyeicosa-6,8,10,14-tetraenoate (LTB$_4$).

leukotriene B *abbr.*: LTB; any of a group of **leukotrienes** characterized as (5*S*,12*R*)-5,12-dihydroxy polyunsaturated acids. Leukotriene B$_4$ (LTB$_4$) is (6*Z*,8*E*,10*E*,14*Z*)-(5*S*,12*R*)-5,12-dihydroxyeicosa-6,8,10,14-tetraen-1-oate. Leukotriene B$_5$ (LTB$_5$) has an additional, 17*Z*, double bond. LTB$_4$ is a product of leukotriene-A$_4$ hydrolase (*see* **leukotriene A**); it is a major product of the 5-lipoxygenase pathway, and is a potent aggregatory, chemokinetic, and chemotactic agent for polymorphonuclear leukocytes (PMNLs) *in vitro* and induces increased vascular permeability and PMNL infiltration *in vivo*.



leukotriene B$_4$

leukotriene C$_4$ *abbr.*: LTC$_4$; a **leukotriene** comprising a glutathione moiety linked through its thio group to C-6 of an eicosanoid. LTC$_4$ is formed from LTA$_4$ and glutathione by leukotriene-C$_4$ synthase (EC 2.5.1.37). It is a potent mediator of smooth muscle contractility, and of vascular tone and permeability, being a potent vasoconstrictor in a variety of vascular beds including the coronary and cerebral circulations. It is the predominant leukotriene in the central nervous system.



leukotriene D$_4$ *abbr.*: LTD$_4$; a **leukotriene** comprising a cysteinylglycine moiety linked through its thio group to an eicosanoid moiety. It is a metabolite of **leukotriene C$_4$** (LTC$_4$), resulting from the action of membrane-bound γ-glutamyl transferase, which removes glutamic acid. Its actions are similar to those of LTC$_4$.

leukotriene E$_4$ *abbr.*: LTE$_4$; a **leukotriene** comprising a cysteine moiety linked to an eicosanoid moiety. It is derived metabolically from **leukotriene D$_4$** (LTD$_4$) by the action of specific membrane-bound dipeptidases, which remove glycine. It has a somewhat longer metabolic half-life than LD$_4$, but is metabolized to more polar products, notably those in which the terminal methyl group of the eicosanoid moiety is oxidized to a carboxyl group. It activates receptors in human airways and has been implicated in airway hyper-responsiveness in humans.

leukovirus *or* **leucovirus** any tumorigenic **retrovirus**.

leukovorin *or* **leucovorin** *see* **folinic acid**.

leumorphin an endogenous 29-amino-acid opioid peptide that corresponds to residues 228–256 of preproenkephalin B; the N-terminal 13 residues correspond to rimorphin (dynorphin B), and the N-terminal five to Leu-enkephalin (*see* **enkephalin**).

leupeptin any modified tripeptide protease inhibitor produced by various actinomycetes. Commonly *N*-acetyl-Leu-Leu-argininal is used in the laboratory; other variants have propionyl in place of acetyl, and valine or isoleucine in place of one or both leucines.

Leu-prolide an analogue of **gonadotropin-releasing hormone** in which residues 5 and 10 (glycine and glycinamide) are replaced by D-Leu and ethylamine respectively.

levan *a common name for* any (2→6)-*β*-D-fructofuranan; such compounds are produced mostly by bacteria. As in **inulin** each chain terminates in a (1→2)-*α*-D-glucopyranosyl residue, but it may also contain (2→1)-*β* branch points.

levansucrase *the recommended name for* sucrose 1-fructosyl transferase, EC 2.4.1.10; an enzyme that catalyses the reaction:

$$\text{sucrose} + (2,6\text{-}\beta\text{-D-fructosyl})_n = \text{glucose} + (2,6\text{-}\beta\text{-D-fructosyl})_{n+1}.$$

See also **sucrase** (def. 3).

levarterenol *see* **norepinephrine**.

levigate *(in chemistry)* **1** to grind (something) into a smooth powder or paste. **2** to separate fine from coarse particles by grinding and suspending them in a fluid. **—levigation** *n.*

levo- *or (esp. Brit.)* **laevo-** *symbol*: *l*-; a prefix, no longer used, to denote a compound that is **levorotatory**; the levorotatory enantiomer of compound A is now designated as (–)-A.

levo+ *or (before a vowel)* **lev+** *comb. form* denoting on or towards the left. *Also (esp. Brit.)* **laevo+, laev+.** *Compare* **dextro+**.

levodopa *or (Brit.)* **laevodopa** (–)-3-hydroxy-L-tyrosine; a naturally occurring amino acid that has been used in the treatment of **Parkinson's disease** easing symptoms such as rigidity, postural problems, and slowness of movement. *See* **3,4-dihydroxyphenylalanine**.

levorotatory *or (esp. Brit.)* **laevorotatory 1** *symbol*: (–)- *or (formerly) l*-; describing a chemical compound that rotates the plane of polarization of a transmitted beam of plane-polarized light or other electromagnetic radiation to the left, i.e. in an anticlockwise direction as viewed by the observer looking towards the light source. **2** describing any leftwards or anticlockwise rotation. *Compare* **dextrorotatory**. **—levorotation** *or* **laevorotation** *n.*

levorphanol 17-methylmorphinan-3-ol; a synthetic analogue of morphine. It is an orally active analgesic that binds stereospecifically with high affinity to opioid receptors (K_d 10^{-9} M). Five to six times more active than morphine, it is a controlled substance under the US Code of Federal Regulations. **Dextrorphan**, the dextrorotatory form, does not bind to opioid receptors, is not analgesic, but is a very effective antitussive.



levulose *or (esp. Brit.)* **laevulose** *an old name, still sometimes used in pharmacy, for* D-(–)-fructose, the levorotatory component of invert sugar. *Compare* **dextrose**.

Lewis acid any chemical species that is able to accept an electron pair and is thus able to react with a **Lewis base** to form an adduct (i.e. Lewis adduct). For example:

$$(CH_3)_3B + :NH_3 \rightarrow (CH_3)_3B^{-}N^{+}H_3$$

or

$$(CH_3)_3C^{+} + Cl^{-} \rightarrow (CH_3)_3C\text{–}Cl;$$

i.e.

$$\text{Lewis acid} + \text{Lewis base} \rightarrow \text{Lewis adduct}.$$

[After Gilbert Newton Lewis (1875–1946), US chemist.]

Lewis adduct the adduct formed between a **Lewis acid** and a **Lewis base**.

Lewis antigen *abbr.*: Le antigen; *symbol*: Le; one of the human **blood-group substances**. Lewis specificities are carried on glycosphingolipids and glycoproteins. Primarily a system of soluble antigens in secretions (e.g. saliva) and plasma, the Lewis antigens on red cells are adsorbed passively from plasma, which must be constantly present for them to be maintained. Three Lewis phenotypes are common amongst Caucasians, namely Le(a^{+}b^{-}), Le(a^{-}b^{+}), and Le(a^{-}b^{-}); the very rare Le(a^{+}b^{+}) is detected in Polynesians and Orientals. The carbohydrate structures providing Le^{a} and Le^{b} specificity are shown below; these partial structures are linked through other carbohydrate moieties to a **ceramide**, thus forming a glycosphingolipid, or to a protein, thus forming a glycoprotein.

Le^{a} Gal(*β*1-3)[Fuc(α1-4)]GlcNAc(*β*1-3)Gal...

Le^{b} Fuc(*α*1-2)Gal(*β*1-3)[Fuc(*α*1-4)]GlcNAc(*β*1-3)Gal...

The structures of the Le^{c}, Le^{d}, Le^{x}, and Le^{y} determinants are also known. The Lewis antigens are named after a Mrs H. D. G. Lewis, in whom they were first identified. *See also* **galactoside 3(4)-L-fucosyltransferase**.

Lewis base any chemical species that is able to supply an electron pair and is thus able to react with a **Lewis acid** to form an adduct (i.e. Lewis adduct).

Lewis formula *or* **Lewis structure** a depiction of molecular structure in which the valency electrons are shown as dots so placed that each pair of dots represents two electrons. When placed between two atoms each pair of dots also represents a single covalent bond, whereas dots placed adjacent to only one atom represent the nonbonded outer-shell electrons considered to be associated with that atom alone. (e.g. H:C̤̈l:). A double bond is represented by two pairs of dots (e.g. Ö̤: :Ö̤), and so on. Formal charges are attached to atoms as appropriate.

Lewis transferase *see* **galactoside 3(4)-**L-fucosyltransferase.

Lewy body an aggregate of fibrillar ubiquitinated α-**synuclein** occurring in the substantia nigra in Parkinson's disease. Fibril formation is inhibited *in vitro* by dopamine. [After Frederic H. Lewy (1885–1950), German-born US neurologist.]

lexA a gene in *Escherichia coli* encoding a repressor that regulates the genes induced by **SOS repair**. In the latter, following DNA damage, the *lexA* product, LexA, is hydrolysed by RecA protein (*see* ***recA***), thereby allowing the SOS genes to be activated. *lexA* is itself regulated autogenously. LexA binds to operators as a dimer.

Leydig cell a type of steroid-secreting, interstitial cell that occurs in large numbers between the seminiferous tubules of the testis. The cells secrete androgens, especially testosterone, and this activity is stimulated by luteinizing hormone, for which the cells have specific receptors. [After Franz von Leydig (1821–1908), German anatomist and zoologist.]

LFA 1 a leukocyte cell-surface glycoprotein involved in the adhesion of leukocytes to target cells and thus in a variety of immune phenomena, including leukocyte–endothelial cell interaction, cytotoxic T-cell-mediated killing, and antibody-dependent killing by granulocytes and monocytes. It binds to **ICAM**. LFA 1 is a type I membrane glycoprotein belonging to the LEUCAM family of **integrins**; it is a dimer of the α_L and β_2 subunits.

L form (of a bacterium) a defective bacterial cell, of indefinite or spherical shape, in which the cell wall is defective or absent. L forms may develop spontaneously or in response to a variety of stimuli, e.g. thermal or osmotic shock, or the presence of antibiotics that inhibit cell-wall synthesis. They may revert to their original condition on removal of the stimulus or they may reproduce as L forms. On solid media, L forms have a characteristic colonial appearance resembling that of **mycoplasmas** (with which they were originally confused).

LFS *abbr. for* **Li–Fraumeni syndrome**.

lg *symbol for* decadic, or common or Briggsian, **logarithms** (alternative to $\log_{10}$).

LH *abbr. for* luteinizing hormone.

LHC *abbr. for* light-harvesting complex.

LHCP *abbr. for* light-harvesting chlorophyll protein.

LH/FSH-RF *abbr. for* luteinizing hormone/follicle-stimulating hormone releasing factor (i.e. **gonadotropin releasing hormone**).

LHRF *or* **LH-RF** *abbr. for* luteinizing hormone releasing factor (*see* **gonadotropin-releasing hormone**).

LHRH *or* **LH-RH** *abbr. for* luteinizing hormone releasing hormone (*see* **gonadotropin releasing hormone**).

Li *symbol for* lithium.

+liberin *word ending* denoting a hypothalamic factor (or hormone) that promotes the release (and perhaps also the biosynthesis) of the particular pituitary hormone indicated; e.g. luliberin, thyroliberin. *Compare* **+statin**.

library of genes *see* **gene library**.

librate to oscillate about an equilibrium position. **—libration** *n.*

Librium *see* **chlordiazepoxide**.

licensing factor *see* **MCM protein.**

licorice *see* **glycyrrhiza**.

Liddle syndrome a rare autosomal dominant disease characterized by early and severe hypertension, hypokalemic metabolic alkalosis, and decreased secretion of aldosterone. It results from mutations that remove the C-terminal tails of β or γ subunits of **ENaC**. [Named after Grant Liddle, US physician who described it in 1963.]

Liebermann–Burchard reaction the reaction of acetic anhydride in chloroform with unsaturated steroids (e.g. cholesterol) or triterpenes in the presence of concentrated sulfuric acid to produce a blue-green colour. It is used especially in the estimation of cholesterol.

LIF *abbr. for* leukemia inhibitory factor.

life cycle the totality of functional and morphological stages through which any organism passes between any one developmental stage and the identical stage in the next generation. Less commonly it refers to the totality of the various stages through which an individual organism passes between birth and death.

Li–Fraumeni syndrome *abbr*.: LFS; a rare familial predisposition to cancer characterized by presence of a bone or soft-tissue sarcoma before 45 years of age in the proband, and of a cancer or sarcoma in at least one first- or second-degree relative also before the age of 45 years. Germline mutations in the gene for **p53** at 17p13.1 are inherited in an autosomal dominant manner in the majority of LFS families. [After Frederick P. Li and Joseph F. Fraumeni (1933–), US physicians.]

Lig *symbol for* the lignoceroyl group, $CH_3–[CH_2]_{22}–CO–$.

ligancy *a less common alternative name for* **coordination number**.

ligand 1 (in a simple inorganic compound) any individual atom, group, or molecule that is attached covalently to the characteristic or central atom or moiety. **2** (in an organic compound) any individual atom or chemical group that is attached covalently to a specified carbon atom; *see also* **point ligand**. **3** (in a coordination entity) **a** any individual atom, ion, or molecule that is attached coordinately to one central metal atom (**unidentate ligand**). **b** an ion, molecule, or molecular grouping that has more than one coordinating group (**bi-**, **tri-**, or **multidentate ligand**). In both cases the ligand is an electron donor in the formation of one or more coordinate bonds. **4** an ion of either sign that can associate reversibly with one or more (charged or uncharged) atoms or characteristic molecular groupings in another (usually larger) molecule (as in the hydronation of a conjugate base, the coordination of a metal cation by a protein, etc.). **5** a molecule (or a class of molecules) that has become linked covalently to another molecule to form a conjugate, whether in a single-step reaction or by stepwise addition of its components (e.g. an oligosaccharide moiety in a glycoprotein). **6** a molecule (or part of one) that is bound or is able to bind selectively and stoichiometrically, whether covalently or not, to one or more specific sites on another molecule (as in the combination of antigen with antibody, of hormone with receptor, of substrate with enzyme, etc.).

liganded bound by or as a ligand or ligands; ligated; *see* **ligate** (def. 2).

ligand exchange (chromatography) a column-chromatographic technique in which a cation-exchange resin is loaded with a complexable metal ion and the resulting loaded resin, which retains the capability of the metal ion to coordinate to an appropriate complexing agent or ligand, is used for the sorption of that ligand from a solution or a gas phase. Elution is then effected by displacement with, i.e. exchange for, another ligand. The resin is commonly a chelating resin (e.g. a styrene–divinylbenzene copolymer to which iminodiacetate groups are attached) and the ion is usually of a transition metal (e.g. copper or nickel), such ions tending to be bound strongly to these resins. Separation of components of mixtures occurs by virtue of the differences in the stabilities of the various metal–ligand complexes formed.

ligand-field theory *(in inorganic chemistry)* a theory, closely related to the valence-bond theory, that deals with the effects of ligands on the energy levels of the central atom or ion in complexes and crystals. It is especially useful in interpretation of the spectra of inorganic complexes.

ligand-gated describing an ion channel in a cell membrane that is caused to open by the action of an agonist binding to the receptor that governs the channel. Channel opening can be direct, when the receptor acts as an ionophore, or indirect, involving a second messenger regulated by a G-protein.

ligandin *a name formerly given to* a basic dimeric protein of ~25 kDa per dimeric subunit (*see* **gluthathione transferase**). It is abundant in rat and human liver, kidney, and small intestine. It binds with high affinity to heme, bilirubin and other organic anions, polycyclic aromatic carcinogens, and various metabolites. Its presence in the urine, **ligandinuria,** has been used to follow the evolution of various forms of kidney injury, while its presence in serum provides a sensitive indicator in liver injury. Also variously called Y protein, organic anion binding protein, basic azo-dye binding protein, cortisol metabolite binding protein (binder protein I), glutathionetransferase B.

liganding binding by or as a ligand or ligands; ligating; *see* **ligate** (def. 2).

ligandinuria *see* **ligandin**.

ligand-mediated chromatography *a variant of* **affinity chromatography** that employs an additional component, the affinity ligand, which is a ligand both for the reactive component attached to the insoluble matrix and for the substance to be purified.

ligand–receptor assay a form of **saturation analysis** for a hormone or other agonist wherein the specific binding agent used is an isolated preparation of the naturally occurring cellular receptor substance for the agonist. An advantage of the assay is that the values obtained are considered to be a direct reflection of the biological properties of the substance assayed.

ligase 1 *or (formerly)* **synthetase** *the systematic class name for* enzymes of class EC 6, all of which catalyse the ligation of molecules of two substances with concomitant breaking of a diphosphate linkage in a nucleoside triphosphate. The recommended names of particular ligases are formed in some instances, especially those of enzymes of subclass EC 6.4, by using the generic name carboxylase, e.g. pyruvate carboxylase, EC 6.4.1.1. In the remaining instances the generic names ligase (def. 2) or synthase are used, according to whether the name of an individual enzyme is to be based on the names of the reactants or on the name of the product, respectively. **2** *a generic name for* many enzymes of class EC 6 (*see* **ligase** (def. 1)); when added to the names of the two reactants whose ligation is catalysed by a particular enzyme it forms the recommended name of that enzyme; e.g. tyrosine–tRNA ligase (EC 6.1.1.1), acetate–CoA ligase (EC 6.2.1.1). *See also* **synthetase** (def. 2). **3** *see* **DNA ligase**.

ligase chain reaction *abbr.* LCR. a method of detecting single base mutations based on thermal cycling and involving a thermostable DNA ligase. Two contiguous oligonucleotides annealed to a single stranded DNA molecule are ligated if there is perfect complementarity between them and the template. When performed with two pairs of complementary oligonucleotides, one pair for each strand of the DNA duplex, the ligated oligonucleotides act as templates in the next and subsequent cycles of melting, annealing, and ligation leading to amplification in a manner similar to PCR. The small size of the products makes them suitable for rapid analysis by capillary electrophoresis.

ligate **1** to join together, especially with a ligature. **2** *(in chemistry)* to join (molecules or molecular fragments) together with a bond; to coordinate. **3** to bind as or to a **ligand** or ligands. **4** *(in surgery)* to tie off (a blood vessel or duct) with a ligature so as to occlude. **—ligation** *n.*; **ligatable** *adj.*; **ligative** *adj.*

ligatin a filamentous plasma membrane protein for the attachment of peripheral glycoproteins to the external cell surface. It acts as a trafficking receptor for phosphoglycoproteins, localizing them, after internalization, within endosomes.

light **1** electromagnetic radiation capable of producing a visual sensation in the eye. It comprises wavelengths in the range 380–780 nm (frequencies 385–789 THz), although the term is sometimes loosely extended to include some ultraviolet and infrared radiation in adjacent parts of the spectrum. **2** *(in chemistry)* describing any (especially metallic) element whose density is relatively small (usually <5000 kg m^{-3}). **3** *(in physics)* of less than the usual mass. *Compare* **heavy**.

light band a region of a muscle **sarcomere** that stains less densely in light microscopy and low-magnification electron microscopy relative to the **dark bands**; together, these differentially staining bands give the striated appearance of skeletal muscle. The light bands are relatively isotropic in polarized light; they represent the regions occupied by **thin filaments**. *See also* **thick filament**, **Z line**.

light chain **1** *or* **L chain** *or (formerly)* **B chain** *symbol*: L; the shorter of the two main types of polypeptide chain of an **immunoglobulin** of any class. Of ≈22 kDa (human), each light chain is linked at its C-terminal cysteine residue by a disulfide bond to the constant region of a **heavy chain**. In any given animal species, light chains may be distinguished serologically into two types, κ and λ, which occur in immunoglobulin molecules of every class in proportions that vary only with the species (about 65% κ in the human), and which have different but homologous sequences. The C-terminal half of each type of light chain consists of a **constant region** and the N-terminal half is a **variable region** possibly related to the antibody-combining site. *See also* **Bence-Jones protein**. **2** any of the four 15–27 kDa polypeptide chains that, with two heavy chains of ≈200 kDa, constitute a molecule of **myosin**.

LightCycler proprietary name for an instrument used for real-time PCR. Monitoring DNA abundance in each cycle is made possible by measuring the intensity of fluorescence yielded by an intercalating dye such as Sybr Green.

light-effect mediator *abbr.*: LEM; any of a number of substances that, following their light-induced reduction, activate some of the enzymes of the Calvin cycle (*see* **reductive pentose phosphate cycle**) in photosynthesis. Not all of these mediators have been identified, but it is thought that they are cyst(e)ine-containing proteins that become oxidized in the dark and reduced again in the light. An important member of the group is **thioredoxin**.

light-harvesting chlorophyll protein *or* **light-harvesting chlorophyll-binding protein** *abbr.*: LHCP; a chlorophyll-binding protein that is abundant in green plants, particularly in those grown at low light intensities. It consists of a 25 kDa polypeptide, encoded by a nuclear gene and synthesized in the cytoplasm, to which is bound most of the chlorophyll *b* and xanthophylls, together with some of the chlorophyll *a*. It appears to be capable of transferring the energy of absorbed light photons to both photosystem I and photosystem II. *See also* **light-harvesting complex**.

light-harvesting complex *abbr.*: LHC; a **thylakoid** membrane complex of chlorophylls *a* and *b* together with chlorophyll *a-b* binding proteins. LHCs contain a number of other proteins, the function of which is speculative, and accessory pigments. The LHCs capture and transfer energy to photosystems I and II, and are regulated by phosphorylation on threonine residues. *See also* **light-harvesting chlorophyll protein**.

light meromyosin *abbr.*: L meromyosin *or* LMM; the smaller, 120 kDa, fragment, also called F3 fragment, produced when **myosin** is subjected to brief treatment with trypsin or certain other peptidases. It contains much of the helical, rod-shaped tail (>90% α helical) and forms large, ordered aggregates at low ionic strength. Light meromyosin has no ATPase activity and cannot bind actin.

light path **1** the path followed by a beam of light when passing through an optical device or a particular part of one. **2** *or* **path length** the length of such a path.

light pen an input/output device for use with a computer that, when pointed at a spot on a visual display unit, can sense whether or not the spot is illuminated; the output current from the light pen can then be used to control the operations of the computer.

light reactions of photosynthesis *or* **light phase of photosynthesis** those reactions of **photosynthesis** in higher plants and algae in which light energy is used to generate NADPH and ATP.

light repair *an alternative name for* **photoreactivation**.

light-scattering a technique used for the determination of the relative molecular mass, M_r, in solution of a macromolecule whose size is large relative to the wavelength of the light used. The value of M_r of the macromolecule can be calculated from the wavelength of the incident light, the angle and intensity of the scattered light, the refractive indices of the solvent and solute, and the concentration of the solute. *See also* **Rayleigh scattering**.

light strand *or* **L strand** **1** a polynucleotide strand not labelled with heavy isotope. **2** the strand in a naturally occurring polynucleotide duplex that is of a lower density than its complementary strand. *Compare* **heavy strand**.

light trapping **1** the process of capturing the energy of incident light in a photosynthetic pigment system. **2** the act or process of using focused light in a liquid medium so arranged as to trap phototactic organisms in a restricted part of that medium.

lignan any member of a class of phenylpropanoid dimers in which the phenylpropane units are linked tail-to-tail and thus have a 2,3-dibenzylbutane skeleton (*compare* **neolignan**). Lignans occur in higher plants, and in humans and other mammals as products of the action of gut flora on dietary lignans of plant origin. Guaiaretic acid is structurally one of the simplest; **podophyllotoxin** and more particularly its semisynthetic derivatives **Etoposide** and **Teniposide** have defined actions in clinical medicine, with antitumour and possibly antiviral actions. *See also* **lignin**.

lignify to make or become woody; to accumulate or deposit lignin in the cell walls (of plant tissues). **—lignification** *n.*

lignin any random phenylpropanoid polymer formed in higher plants by the dehydrogenative radical polymerization of various 4-hydroxycinnamyl alcohols, in which the residues are joined in differing proportions and by several different linkages, some of which are nonhydrolysable. Lignin is insoluble in water, and occurs in the cell walls of vascular plants (especially of the supporting and conducting tissues), on which it confers strength, rigidity, and resistance to degradation. It is one of the most abundant biopolymers. *See also* **lignan**.

ligninase an enzyme that catalyses breakdown of lignin using hydrogen peroxide formed from **oxygenases** to cleave carbon–carbon bonds – i.e. **lignin peroxidases**. An example is diarylpropane peroxidase, EC 1.11.1.14; *systematic name*: diarylpropane:oxygen,hydrogen peroxide oxidoreductase (C–C-bond-cleaving); *other name*: ligninase I. It is a hemoprotein that catalyses a reaction between 1,2-bis(3,4-dimethoxyphenyl)propane-1,3-diol and H_2O_2 to form 3,4-dimethoxybenzaldehyde, 1-(3,4-dimethylphenyl)ethane-1,2-diol, and $4H_2O$.

lignin peroxidase *see* **ligninase**.

lignocellulose a covalent adduct of **lignin** and **cellulose**, found in the walls of xylem cells in woody tissues of plants. **—lignocellulosic** *adj.*, *n.*

lignocerate **1** *the trivial name for* tetracosanoate, $CH_3–[CH_2]_{22}–COO^–$, the anion derived from lignoceric acid (i.e. tetracosanoic acid), a saturated straight-chain higher fatty acid. **2** any mixture of lignoceric acid and its anion. **3** any salt or ester of lignoceric acid.

lignoceroyl *symbol*: Lig; *the trivial name for* tetracosanoyl, $CH_3–[CH_2]_{22}–CO–$, the acyl group derived from lignoceric acid (i.e. tetracosanoic acid). It occurs naturally as acylglycerols in peanut and rapeseed oils, and in certain sphingomyelins.

lignoceroyl-CoA synthase *see* **long-chain-fatty-acid–CoA ligase**.

LIM domain *see* **islet-1**.

limit *(in mathematics)* a value to which a function or the sum of a series approaches as an independent variable approaches a specified value or infinity.

limit dextrin the highly branched core that remains after exhaustive treatment of amylopectin or glycogen with α- and/or β-amylases. It is formed because these enzymes cannot hydrolyse the (1→6) glycosidic linkages present.

limit dextrinase *see* **α-dextrin endo-1,6-α-glucosidase**, **oligo-1,6-glucosidase**.

limit dextrinosis *an alternative name for* type III **glycogen disease**.

limit digest a digest in which no further degradation can occur under the particular conditions adopted.

limiting current *(in polarography)* the maximal value of the current reached in circumstances when the steady-state current/potential characteristic has a positive slope.

limiting rate *symbol*: V; *the recommended name for* the extrapolated rate of an enzyme-catalysed reaction when the enzyme is saturated with substrate(s). It is equal to the product of the stoichiometric concentration of active centres, $[E]_0$, and the catalytic constant, k_0. It can be determined by a number of methods, including graphical methods such as the **Lineweaver–Burk plot**. *Other names*: maximum rate; maximal rate; maximum velocity; maximal velocity.

limiting viscosity number *the recommended name for* **intrinsic viscosity**.

LIM kinase *abbr.*: LIMK; a family of protein serine/threonine kinases that contain two N-terminal LIM domains (*see* **islet-1**). They are strongly expressed in neuronal tissues.

limonene *p*-mentha-1,8-diene; a compound that occurs in many essential oils (e.g. oils of lemon, orange, and dill); both enantiomers and the racemic mixture (i.e. dipentene) occur naturally.



(*R*)-(+) form

LIMS *abbr. for* laboratory information management systems; normally, systems involving automatic electronic data capture and computerized manipulation of data.

Lin *symbol for* the linoleoyl group, $CH_3–[CH_2]_3–[CH_2CH{=}CH]_2–[CH_2]_7–CO–$ (*all-Z* isomer).

lin3 a gene in *Caenorhabditis elegans* that encodes an **epidermal growth factor**-like type I membrane protein. The protein has two isoforms, produced by alternative splicing, and is essential for vulval development.

lin14 a gene involved in embryonic development in *Caenorhabditis elegans* that codes for a nuclear protein. Regulatory sequences in the 3′ untranslated region generate a temporal switch during development. There are three forms of the product: A (537 amino acids); B1 (539 amino acids); and B2 (515 amino acids).

linalool 3,7-dimethyl-1,6-octadien-3-ol; a compound that occurs in linaloe oil and other essential oils; both enantiomers occur naturally. It is used in perfumery.

lincomycin an antibiotic produced by *Streptomyces lincolnensis*. It consists of an amide formed between a substituted pyrrolidine-2-carboxylic acid and methyl 1-thio-α-lincosamine. Lincomycin is active mainly against Gram-positive bacteria; it inhibits protein synthesis by interacting with the 50S ribosomal subunit, inhibiting the early steps of peptide bond formation prior to the formation of polysomes.

lincosamides *generic name for* a group of antibiotics structurally related to **lincomycin**.



lincomycin

lincosamine 6-amino-6,8-dideoxy-D-*erythro*-D-*galacto*-octose; the carbohydrate component of **lincomycin**.



line 1 *(in spectroscopy)* a very narrow band of frequencies of electromagnetic radiation that is noticeably more intense or less intense than adjacent parts of the spectrum; the image of such a line in a spectrogram. **2** *(in biology)* several generations of a family. *See also* **cell line**, **lineage**. —**lineal** *or* **linear** *adj.*

LINE *abbr. for* long interspersed nucleotide element (or sequence or repeat); part of the moderately repetitive DNA of mammalian genomes. Any highly repeated DNA sequence interspersed in a mammalian genome and characteristically several kilobases in length. LINEs are **retroposons** resulting from the action of RNA polymerase II (*see* **RNA polymerase**). Mammalian genomes may contain 10^4 to 10^5 copies of particular LINEs. They are regarded as processed **pseudogenes**. The function of LINEs is unknown. *Compare* **SINE**. *See also* **Alu sequence**.

lineage lineal descent, especially from a common ancestor.

linear accelerator a device for producing high-energy particles, in which charged particles are accelerated in a straight line along a long evacuated tube by potential differences applied to a series of circular electrodes along the tube.

linear chain a chain of atoms in a molecule, or a chain of residues in a macromolecule, that is neither branched nor covalently closed.

linear correlation any relationship between two variables such that a graphical plot of one variable against the other is a straight line.

linear density gradient a gradient of linearly and continuously increasing density.

linear dichroism the **dichroism** (def. 1) occurring when linearly polarized light is absorbed by a sample containing partially or completely oriented anisotropic molecules.

linear equation any equation containing any number of variables that is of the first degree, i.e. one in which the variables are all raised to the power of one.

linear growth the growth of a culture such that the number of cells (or the cell mass) increases in direct proportion to the duration of growth.

linearity the condition of being in a straight line.

linearize *or* **linearise 1** to make linear, i.e. into a straight line. **2** to convert a branched or cyclic form of a (macro)molecule to a linear form, i.e. one with only two ends. —**linearization** *or* **linearisation** *n.*

linearly polarized *or* **plane-polarized** describing light (or other electromagnetic radiation) in which the electric vectors of the vibrations all lie in a given plane containing the light beam. *See* **polarized light**.

line formula a two-dimensional representation of a molecular entity in which atomic symbols are joined by lines representing single bonds, without any indication or implication of stereochemistry.

line immunoelectrophoresis a one-dimensional single **electroimmunodiffusion** technique, useful for the qualitative and quantitative comparison of the antibody spectra of different polyvalent antisera.

line spectrum any spectrum consisting of discrete spectral lines.

Lineweaver–Burk plot a method of plotting enzyme kinetic data. The Michaelis equation is rearranged to give:

$$1/v = K_m/V[S] + 1/V,$$

where K_m is the Michaelis constant, [S] the concentration of the substrate S, v the (initial) rate of reaction at a given value of [S], and V the limiting rate of reaction at infinite [S]. If the Michaelis equation holds for the system, a plot of $1/v$ against $1/[S]$ gives a straight line of slope K_m/V, with intercepts on the $1/v$ axis at $1/V$ and on the $1/[S]$ axis at $-1/K_m$. *See* **Michaelis kinetics**. [After Hans Lineweaver and Dean Burk.]

linewidth the width of a spectral line, usually taken as the distance, in terms of wavelength, frequency, or magnetic flux difference, between the two points of half-peak intensity (half-maximum height).

link *(in chemistry) an informal term for* **bond** (def. 1). *See also* **linkage** (def. 2).

linkage 1 *(in genetics)* an association of two or more nonallelic genes so that they do not show independent **assortment**; i.e. they tend to be transmitted together usually due to physical association on the same chromosome. **2** *(in chemistry) an informal term for* **bond** (def. 1). *See also* **link**.

linkage disequilibrium the preferential association of linked genes/DNA markers in a population; i.e. the tendency for some alleles at a locus to be associated with certain alleles at another locus on the same chromosome with frequencies greater than would be expected by chance alone.

linkage group any group of genes whose members show a marked tendency to segregate as a unit. *See also* **genophore**.

linkage map a map of a chromosome showing in linear order the relative positions of the known genes on that chromosome.

linked genes genes that exhibit **linkage** (def. 1).

linker 1 any small synthetic single-chain oligodeoxynucleotide that is six or more residues long and has a self-complementary base sequence. When self-annealed it forms a stable duplex with blunt ends and containing a **restriction site**. Such linkers are useful for gene splicing. **2** *see* **cross-link**.

linker DNA *see* **chromatin**, **nucleosome**

linking number *symbol*: L; a topological property of closed circular duplex DNA, defined as the number of turns one strand makes about the other. It must be an integer, and is positive if the turns are right-handed and negative if they are left-handed. It can change only when one or both strands are nicked. It comprises the sum of the **writhing number** (W) and the **twist number** (T), so that a change (ΔL) in the linking number (L) is equal to $\Delta W + \Delta T$.

linoleate 1 *the trivial name for* (*all-Z*)-octadeca-9,12-dienoate, $\mathrm{CH_3-[CH_2]_3-[CH_2-CH{=}CH]_2-[CH_2]_7-COO^-}$, (*all-Z* isomer) the anion derived from linoleic acid, (*all-Z*)-octadeca-9,12-dienoic acid, a diunsaturated straight-chain higher fatty acid essential in the diet of mammals. It occurs naturally as acylglycerols in many vegetable oils and in the lipids of many animal tissues. **2** any mixture of free linoleic acid and its anion. **3** any salt or ester of linoleic acid. *See also* **linoleic family**.

linoleate synthase *see* **phosphatidylcholine desaturase**.

linoleic family (of polyunsaturated fatty acids) a series of polyenoic acids occurring in mammals, in which the hydrocarbon chain terminates with the alkenyl grouping, $\mathrm{CH_3-[CH_2]_4-CH{=}CH-}$ (as in linoleic acid; *see* **linoleate**) and that are synthesized from linoleic acid by chain elongation and/or further desaturation (but which in mammals cannot be synthesized from the corresponding saturated acids or from (9,12,15)-linolenic, oleic, or palmitoleic acids – the latter represent three other series of polyenoic acids). The linoleic family is also known as the ω6, or n-6, family because of the position of the double bond nearest the terminal methyl group. The series includes (6,9,12)-linolenic acid, eicosa-11,14-dienoic acid, eicosa-5,11,14-trienoic acid, eicosa-8,11,14-trienoic acid, and arachidonic acid.

linolenate 1 *or* **(9,12,15)-linolenate** *or (formerly)* **α-linolenate** *the alternative trivial names for* (*all-Z*)-octadeca-9,12,15-trienoate; $\mathrm{CH_3-[CH_2-CH{=}CH]_3-[CH_2]_7-COO^-}$ (*all-Z* isomer); the anion derived from (9,12,15)-linolenic acid, (*all-Z*)-octadeca-9,12,15-trienoic acid, a triunsaturated straight-chain higher fatty acid synthesized by plants (notably found in linseed oil) but essential in the diet of mammals (*see* **linolenic family**). The name equally refers to any mixture of (*all-Z*)-octadeca-9,12,15-trienoic acid and its anion, or any salt or ester of this acid. **2 (6,9,12)-linolenate** *or (formerly)* **γ-linolenate** *the trivial name for* (*all-Z*)-octadeca-6,9,12-trienoate; $\mathrm{CH_3-[CH_2]_3-[CH_2-CH{=}CH]_3-[CH_2]_4-COO^-}$ (*all-Z* isomer), the anion derived from (6,9,12)-linolenic acid (*all-Z*)-octadeca-6,9,12-trienoic acid, a triunsaturated straight-chain higher fatty acid belonging to the **linoleic family**. It occurs naturally as acylglycerols in certain plant-seed oils, especially that of the evening primrose (*Oenothera* spp.), and also in small amounts in the lipids of many animal tissues, especially human breast milk. It is the biosynthetic precursor of arachidonate and the prostaglandins. The name refers equally to any mixture of (*all-Z*)-octadeca-6,9,12-trienoic acid and its anion or any salt or ester of the acid.

linolenic family (of polyunsaturated fatty acids) a series of polyenoic acids occurring in mammals, in which the hydrocarbon chain terminates with the alkenyl grouping $\mathrm{CH_3-CH_2-\ CH{=}CH-}$ (as in (9,12,15)-linolenic acid; *see* **linolenate**). The linolenic family is also known as the ω3 or n-3 family because of the position of the terminal double bond three carbon atoms from the methyl end. The longer-chain members can be synthesized in mammals only from dietary (9,12,15)-linolenic acid by chain elongation and/or further desaturation (but not from the corresponding saturated acids or from linoleic, oleic, or palmitoleic acids – the latter represent the other three series of polyenoic acids). If animals are deprived of these fatty acids, certain tissues, such as the eye, retain existing stores of these fatty acids tenaciously, even in offspring of such animals when the restricted diet is continued for more than one generation. Under these conditions, long-chain acids of the **linoleic family**, e.g. (4,7,10,13,16,)-docosapentaenoic (C22:5 n-6) acid, are synthesized in appreciable amounts and presumably partially support the function supplied by long-chain ω3 acids, though the nature of this is unknown. The series includes eicosapentaenoic (C20:5 ω3) and docosahexaenoic (C22:6 ω3) acids, which are found in high concentration in fish oils; these ω3 acids may have value in protecting against heart disease, but in amounts that greatly exceed those needed to fulfil their role as essential fatty acids.

linolenoyl 1 *or* **(9,12,15)-linolenoyl** *or (formerly)* **α-linolenoyl** *symbol*: αLnn *or (sometimes)* Lnn; *the alternative trivial names for* (*all-Z*)-octadeca-9,12,15-trienoyl; $\mathrm{CH_3-[CH_2-CH{=}CH]_3-[CH_2]_7-CO-}$ (*all-Z* isomer); the acyl group derived from (*all-Z*)-octadeca-9,12,15-trienoic acid. **2 (6,9,12)-linolenoyl** *or (formerly)* **γ-linolenoyl** *symbol*: γLnn; *the trivial names for* (*all-Z*)-octadeca-6,9,12-trienoyl; $\mathrm{CH_3-[CH_2]_3-[CH_2-CH{=}CH]_3-[CH_2]_4-CO-}$ (*all-Z* isomer); the acyl group derived from (*all-Z*)-octadeca-6,9,12-trienoic acid. *See* **linolenate**.

linoleoyl *symbol*: Lin; *the trivial name for* (*all-Z*)-octadeca-9,12-dienoyl; $\mathrm{CH_3-[CH_2]_3-[CH_2-CH{=}CH]_2-[CH_2]_7-CO-}$ (*all-Z* isomer); the acyl group derived from linoleic acid. *See* **linoleate**.

Linux a widely used open-source free operating system similar to UNIX and incorporating UNIX commands and much software from the **GNU** project. The word Linux is constructed in part from the name of the original author, Linus Torvalds, and there is disagreement about the pronunciation of Linux. The original author's family comes from the Swedish-speaking minority in Finland, and Linus is pronounced 'Leenus', of which Linus with a short i (as in 'bit') is the nearest English equivalent. This is favoured by Linus Torvalds himself, but there are those who point out that the name Linus in English has the first syllable sounding like 'line' (e.g. Linus Pauling) and insist on the pronunciation 'line-ux'.

liothyronine *a pharmaceutical name for* L-3,5,3′**-triiodothyronine**.

lip+ *a variant form of* **lipo+** (before a vowel).

lipaemia *a variant spelling (esp. Brit.) of* **lipemia**.

lipase 1 *a general term for* any acylglycerol carboxylic ester hydrolase, of EC sub-subclass 3.1.1. The term may be incorporated in the enzyme name as the suffix '+lipase'. **2** *abbr. (in clinical chemistry)*: LPS; *an alternative name for* **triacylglycerol lipase**. *See also* **hormone-sensitive lipase**, **lipoprotein lipase**, **pancreatic lipase**.

lipemia *or* **lipidemia** the condition when there is a greater than normal content of lipid in the blood, e.g. after a fatty meal or in certain pathological states. *Also (esp. Brit.)* **lipaemia**, **lipidaemia**.

lipid *or (formerly)* **lipide** *or* **lipoid** *or* **lipin(e) 1** any member of a large and diverse group of oils, fats, and fatlike substances that occur in living organisms and that characteristically are soluble in **lipid solvents** but only sparingly soluble in aqueous solvents. Lipids constitute one of the four major classes of compounds found in living tissues (the others being carbohydrates, proteins, and nucleic acids) and they include: (1) fatty acids; (2) neutral fats (i.e. triacylglycerols), other fatty-acid esters, and soaps; (3) long-chain (or fatty) alcohols and waxes; (4) sphingoids and other long-chain bases; (5) glycolipids, phospholipids, and sphingolipids; and (6) carotenes, polyprenols, sterols (and related compounds), terpenes, and other isoprenoids. See individual entries for details. **2** any oily, fatty, or fatlike material that occurs in living organisms. **3** of, concerned with, for, or relating to **lipid** (def. 2); consisting of or containing **lipid** (def. 1, 2); **lipoid** (def. 1) or lipoidal. **—lipidic** *adj.*

lipid A the glycolipid moiety of bacterial **lipopolysaccharide**.

lipidaemia *a variant spelling (esp. Brit.) of* lipidemia; *see* **lipemia**.

lipid bilayer any layer, two molecules thick, of amphipathic lipid molecules. If it is surrounded by a polar environment, the polar parts of the lipid molecules are oriented outwards towards the environment and the nonpolar parts inwards into the interior of the bilayer. The two layers of lipid are referred to as **leaflets**, e.g. the inner and outer leaflets of the bilayer. *See also* **black lipid membrane**.

lipide *a variant spelling of* **lipid**.

lipidemia *an alternative term for* **lipemia**.

lipidosis *or* **lipoidosis** (*pl.* **lipidoses** *or* **lipoidoses**) any clinical disorder, *also called* **lipid storage disease**, that results in the excessive deposition within specific tissues of particular types of lipids. Many lipidoses are inherited disorders of galactosphingolipid metabolism.

lipid raft a type of lipid microdomain in the plasma membrane of cells that sequesters signalling proteins of certain receptors such as those expressed by **T** and **B lymphocytes** that move into the outer leaflet of the **plasma membrane** lipid bilayer. **Caveolae** are a subset of lipid rafts.

lipid-soluble *a vague term applied to* various classes of nonpolar substances, e.g. sterols, certain vitamins, carotenoids, and polyprenoids, that are commonly present in small amounts in association with the major lipid.

lipid solvent any relatively nonpolar solvent that can be used to extract lipids from tissues or other materials.

lipid storage disease *an alternative term for* **lipidosis**.

lipid transport protein any of the small proteins that transport lipids and facilitate their exchange between membranes. In plants they are located in the cell wall space and transfer wax and cutin monomers from the plasma membrane to the cell surface.

lipin *or* **lipine** *a former term for* **lipid** (def. 1), especially one containing nitrogen and/or phosphorus.

lipo+ *or (before a vowel)* **lip+** *comb. form* denoting lipid, lipid-containing, or lipid-like.

lipoamide *or (sometimes)* **lipoyllysine** a **lipoyl** group when in amide linkage to the ε-amino group of a specific lysine residue in dihydrolipoamide acetyltransferase (EC 2.3.1.12) and dihydrolipoamide succinyl transferase (EC 2.3.1.61), which form, respectively, parts of the **pyruvate dehydrogenase complex** and the **2-oxoglutarate dehydrogenase complex**.

lipoamide reductase (NADH) EC 1.8.1.4; *recommended name*: dihydrolipoamide dehydrogenase; *other names*: E3 component of *α*-ketoacid dehydrogenase complexes; lipoyl dehydrogenase; dihydrolipoyl dehydrogenase; diaphorase. An enzyme that catalyses the oxidation by NAD$^+$ of dihydrolipoamide to form lipoamide and NADH. FAD is a coenzyme. It is typically a homodimer, occurring in the mitochondrial matrix (in eukaryotes), with a redox-active S–S bond similar to glutathione reductase.

lipoate 1 1,2-dithiolane-3-pentanoate, the anion derived from **lipoic acid** (i.e. thioctic acid). **2** any salt or ester of lipoic acid.

lipocaic a substance extractable from the pancreas that was said to be lipotropic in pancreatectomized animals.

lipocalin any of a large group of chiefly extracellular ligand-binding proteins, particularly one that binds hydrophobic ligands, e.g. biliverdin. The family includes retinol-binding protein, α-microglobulin, insect bilin-binding proteins, and **beta lactoglobulin**. The ligand is enclosed by the protein as a flower is enclosed by the calyx (i.e. the sepals), hence the name. Lipocalins have an eight-stranded beta-barrel structure; different ligand-binding properties are determined by loops on the periphery.

lipochrome *a former name for* any of various lipid-soluble biological pigments.

lipocortin *see* **annexin**.

lipofection a lipid-mediated DNA-transfection technique that makes use of unilamellar liposomes that contain a cationic lipid and spontaneously react with DNA.

lipofuscin any of various brownish lipid-soluble pigments that are deposited in animal cells, especially in senility.

lipogenesis the formation of fat. The term is applied especially to the processes by which higher fatty acids are synthesized from nonlipid sources. **—lipogenic** *adj.*

lipogenic amino acid any amino acid that can provide carbon atoms for the biosynthesis of higher fatty acids.

lipoic acid *or* ***α*-lipoic acid** *symbol*: Lip(S_2); 1,2-dithiolane-3-pentanoic acid; thioctic acid; the naturally occurring form is the (*R*)-(+)-enantiomer. Lipoic acid provides the reversibly reducible moiety, **lipoyl**, of **lipoamide** and is a growth factor for certain microorganisms. The reduced form is dihydrolipoic acid, $HS–CH_2–CH_2–CH(SH)–[CH_2]_4–COOH$ (*symbol*: Lip($SH)_2$); the redox potential of the system is –0.29 V at pH7. Lipoic acid is an essential component of the α-ketoacid dehydrogenase complexes. *See* **pyruvate dehydrogenase complex**, **2-oxoglutarate dehydrogenase complex**.



lipoid 1 *or* **lipoidal** being or resembling an oil or a fat; oily, fatty. **2** *a former term for* **lipid** (def. 1, 2).

lipolysis the breakdown of lipids, especially the (enzymic) hydrolysis of acylglycerols. **—lipolytic** *adj.*

lipolytic hormone *an alternative name for* **lipotropin**.

lipomodulin *or* **annexin I** a 40 kDa regulatory protein isolated from rabbit neutrophils that, in its nonphosphorylated form, is an inhibitor of phospholipase A_2 and that on phosphorylation by a cyclic-AMP-dependent protein kinase loses this inhibitory property. It has been suggested that lipomodulin thereby regulates the release of arachidonate from leukoytes, or other cells, that may occur in response to chemoattractants and other external stimuli.

lipophilic tending to dissolve in, having a strong affinity for, or readily mixing with lipids or substances of low polarity. *See also* **hydrophilic**, **lyophilic**. **—lipophilicity** *n.*

lipophilin *another name for* myelin proteolipid. *See* **myelin protein**.

lipophorin any member of the major class of lipid-transporting proteins found in the hemolymph of insects. In locusts, the apoprotein is synthesized in the fat body as an 85 kDa polypeptide. *See also* **apolipophorin**.

lipophosphoglycans *see* **GPI anchor**.

lipopolysaccharide *abbr.*: LPS; any of a group of related, 10 kDa, structurally complex components of the outer leaflet of the outer membrane of Gram-negative bacteria. Lipopolysaccharide molecules consist of three covalently linked regions: lipid A, core oligosaccharide, and an O side chain. The innermost layer, lipid A, which is responsible for the toxicity of the lipopolysaccharide, consists of six fatty acyl chains (sometimes hydroxylated) linked in various ways to two glucosamine residues. The branched core oligosaccharide contains ten saccharide residues, several of them unusual, and has a structure that appears to be similar in closely related bacterial strains. The outermost O side chain, which is highly variable and determines the antigenic specificity of the organism, is made up of many (≈50) repeating units of a branched tetrasaccharide containing further unusual sugar residues.

lipopolysaccharide *N*-acetylglucosaminyltransferase EC 2.4.1.56; an enzyme of the lipopolysaccharide core biosynthetic pathway in enteric bacteria; it catalyses a reaction between UDP-*N*-acetyl-D-glucosamine and lipopolysaccharide to form UDP and *N*-acetyl-D-glucosaminyllipopolysaccharide. *See also* **glycolipid**.

lipopolysaccharide-binding protein a plasma protein that binds bacterial lipopolysaccharide and is homologous with phospholipid transfer protein and cholesterol ester transfer protein. *See* **plasma lipid transfer protein**.

lipoprotein any conjugated, water-soluble protein in which the nonprotein moiety consists of a lipid or lipids. The lipid may be triacylglycerol, cholesterol, or phospholipid, or a combination of these. *Compare* **proteolipid**.

lipoprotein(a) one or two molecules of apolipoprotein(a) linked by a disulfide bridge to **apolipoprotein B**-100; it may be a physiological inhibitor of plasminogen activation. Levels in human plasma (which range from undetectable to 100 mg dL^{-3}) show correlation with the incidence of atherosclerosis.

lipoprotein-associated phospholipase A2 *or* **platelet-activating factor acetylhydrolase** (*abbr*.: PAF-AH); EC 3.1.1.47; an enzyme that is mainly associated with plasma low-density lipoprotein (LDL) particles and is released by a varietyof leukocytes. It catalyses hydrolytic removal of the 2-acetyl moiety of platelet-activating factor (PAF). Deficiency of plasma PAF-AH activity is associated with atherosclerotic occlusive disease in Japan.

lipoprotein lipase EC 3.1.1.34; *abbr*.: LPL; *other names*: clearing factor lipase; diglyceride lipase; diacylglycerol lipase. An enzyme that catalyses the hydrolysis of triacylglycerol to diacylglycerol and fatty-acid anion. Its function, after uptake of dietary lipid, is to hydrolyse triacylglycerols in chylomicrons and very-low-density lipoproteins, to diacylglycerols and fatty-acid anions; the fatty acids are then taken into peripheral tissues for futher metabolism; it will also hydrolyse diacylglycerols. It acts in the presence of apolipoprotein C-II on the luminal surface of vascular endothelium. It is a **GPI-anchor** dimer, and is released by heparin, etc.

lipoprotein signal peptidase *see* **premurein-leader peptidase**.

liposome 1 a natural lipid globule suspended in the cytoplasm of some cells. **2** any small, roughly spherical, artificial vesicle consisting of a continuous bilayer or multibilayer of complex lipids enclosing some of the suspending medium. Liposomes are formed by allowing complex lipids to 'swell' in aqueous solution sometimes with the aid of sonication. They are used experimentally as models of biological membranes and therapeutically for entrapment of drugs, enzymes, or other agents with a view to their more effective delivery to target cells. Originally, such a structure was termed a cellule (when bilayered), smectic mesophase, spherule, or spherulite. *See also* **liquid crystal**.

lipotaurine the 7,13-dihydroxy-2-*trans*-octadecenoyl amide of taurine. It is found in the lipid fraction of *Tetrahymena thermophila*.

lipoteichoic acid any of a group of **teichoic acids** that contain lipid, are present in the membranes of all species of Gram-positive bacteria so far examined, and, unlike wall teichoic acids, are extractable with hot water or phenol.

lipotropic *or* **lipotrophic** tending to prevent the accumulation of, or to remove, abnormal amounts of lipid (in a tissue or organ, e.g. adipose tissue, liver).

lipotropic agent *or* **lipotropic substance** any substance capable of preventing or correcting fatty infiltration of the liver caused by choline deficiency.

lipotropic hormone *or* **lipotrophic hormone** *a former name for* **lipotropin**.

lipotropin *or* **lipotropic hormone** (*abbr*.: LPH) either of two polypeptides, β- and γ-lipotropin, of the anterior and intermediary lobes of mammalian pituitary glands, that elicit lipolysis in adipose tissue. β-Lipotropin corresponds in sequence to the 91 C-terminal amino-acid residues of **proopiomelanocortin**, and γ-lipotropin corresponds to the 58 N-terminal residues of β-lipotropin. In fact, they are of no greater lipotropic potency than corticotropin and α-melanotropin, and whether they have any intrinsic physiological function is still uncertain. Both β- and γ-lipotropins are found in normal human blood. *Other names*: lipolytic hormone; adipokinetic hormone; *former names*: lipotrophin; lipotrophic hormone.

lipotropism the state or quality of being lipotropic.

lipovitellin a ~135 kDa phospholipoprotein that, together with phosvitin, constitutes the bulk of the yolk proteins of the eggs of oviparous vertebrates. These two proteins are synthesized and secreted by the liver as a single large molecule, **vitellogenin**, which is taken up by the ovary and split into the two components.

lipoxin *abbr*.: LX; any of a group of eicosanoids containing a conjugated tetraene structure and having three hydroxyl groups. They are generated by the action of **lipoxygenase** enzymes on polyunsaturated fatty acids (arachidonate and eicosapentaenoate). The major lipoxins, A_4 and B_4, are derived from arachidonate; lipoxin A_4 (LXA_4) is (7*E*,9*E*,11*Z*,13*E*)-(5*S*,6*R*,15*S*)-5,6,15-trihydroxy-eicosa-7,9,11,13-tetraen-1-oate; lipoxin B_4 (LXB_4) is (6*E*,8*Z*,10*E*,12*E*)-(5*S*,14*R*,15*S*)-5,14,15-trihydroxy-eicosa-6,8,10,12-tetraen-1-oate. LXA_4 causes contraction of guinea-pig lung strips, but not ileum; LXA_4 and LXB_4 cause dilation of arterioles.



lipoxin A_4



lipoxin B_4

lipoxygenase 1 EC 1.13.11.12; *systematic name*: linoleate:oxygen 13-oxidoreductase; *other names*: lipoxidase; carotene oxidase. An enzyme that catalyses the oxidation by dioxygen of linoleate to (9*Z*,11*E*)-(13*S*)-13-hydroperoxyoctadeca-9,11-dienoate (*abbr*.: 13(*S*)-HpODE); iron is a cofactor. **2** any dioxygenase enzyme that catalyses the oxidation of polyunsaturated fatty acids to a particular corresponding hydroperoxide. Such enzymes are widely distributed in plants and animals, and occur in leukocytes, mast cells, platelets, and lung, their positional specificities varying from tissue to tissue; notably a 12-lipoxygenase predominates in platelets, and a 5-lipoxygenase in neutrophils. They are important in the conversion of arachidonate to 5- and 12-hydroperoxyeicosatetraenoates (the 5-hydroperoxy compound being the biosynthetic precursor of the leukotrienes). 5-lipoxygenase (EC 1.13.11.34) is important in yielding precursors for **leukotriene** biosynthesis; 15-lipoxygenase (EC 1.13.11.33) yields precursors for the **lipoxins**. All three, however, are involved in the synthesis of hydroperoxy- and dihydroxy-eicosatetraenoates. Compounds that inhibit both lipoxygenase and prostaglandin-endoperoxide synthase include **curcumin**, **eicosatetraynoic acid**, and phenidone (1-phenyl-3-pyrazolidinone). Compounds that selectively inhibit lipoxygenases without inhibiting prostaglandin-endoperoxide synthase include **eicosatriynoic acid** and **esculetin**. *See also* **dihydroxyeicosatetraenoate, hydroperoxyeicosatetraenoate**, **hydroperoxyoctadecadienoate**, **hydroxyeicosatetraenoate**.

lipoyl the acyl group, 1,2-dithiolane-3-pentanoyl, derived from **lipoic acid**. It provides the reversibly reducible moiety of **lipoamide**.

lipoyllysine *an alternative name for* **lipoamide**.

Lip(S_2) *symbol for* a residue of (the oxidized form of) **lipoic acid**.

Lip(SH)$_2$ *symbol for* a residue of dihydrolipoic acid, the reduced form of **lipoic acid**.

lipstatin an irreversible inhibitor of several lipases, e.g. pancreatic, gastric, carboxyl ester, or bile-stimulated lipase of milk, isolated from *Streptomyces toxytricini*. It blocks fat absorption selectively.

lipuria the presence of lipid or oily droplets in the urine.

liquefy *or* **liquify** to become, or cause to become, liquid. —**liquefaction** *or* **liquifaction** *n.*

liquid 1 a state of matter, intermediate between a solid and a gas, in which the molecules are relatively free to move with respect to each other but are restricted by intermolecular forces strong enough to prevent spontaneous expansion or significant compression. **2** any substance that is liquid at normal room temperature and pressure. **3** of, pertaining to, being, or behaving as a liquid. *Compare* **fluid**.

liquid chromatography *abbr*.: LC; any form of **chromatography** in which a liquid is used as the mobile phase.

liquid crystal *or* **mesomorphic state** *or* **mesophase** any new phase, resembling both liquid and solid phases, that appears when certain pure liquids are cooled, or pure solids are heated. These new phases have a translucent or cloudy appearance. In liquids of asymmetric molecules the molecular axes are arranged at random. In liquid crystals, however, there is some alignment, which occurs in three main distinguishable modes (certain such mesomorphic substances displaying more than one). In **nematic liquid crystals** the long axes of the molecules are aligned parallel to each other but the molecules are not arranged in layers. These scatter light strongly and appear translucent. In **cholesteric liquid crystals** the molecular axes are aligned and the molecules are arranged in layers but the orientation of the axes changes in a regular way on going from one layer to the next. Because the distance between any two layers with the same molecular orientation is of the order of the wavelength of visible light such crystals display vivid iridescence. **Smectic liquid crystals** are formed by certain molecules that have chemically dissimilar parts, e.g. polar and nonpolar; the chemically similar parts attract one another and the molecules form layers and align themselves in one direction. *See also* **liquid-crystalline phase**.

liquid-crystal display *abbr*.: LCD; any display of characters or numbers in a calculator, clock, or other device, based on **liquid crystal** cells whose reflectivity is changed by application of an electric field

liquid-crystalline phase any of several types of phase adopted by polar lipids at moderately elevated temperatures. Two major types exist, the lamellar and hexagonal phases. In the lamellar phase, also known as the L_α phase, the lipids form sheets of bilayers with the polar groups oriented outwards and the fatty-acyl moieties oriented into the hydrophobic core between the two bilayers. Such a phase is likely to include many such bilayers stacked on top of each other, with their polar groups apposed. In the hexagonal phase, the lipids form a spherical aggregate, in which the polar headgroups may be oriented either into the centre of the sphere, when this is known as the H_1 phase, or towards the surface of the sphere, the H_2 phase. In liquid-crystalline phase, the lipid adopts a looser packing, with greater mobility of the fatty-acyl chains than in the crystalline state. At low temperatures, in the absence of water, lipids exist in a crystalline state. If the lipid is heated to a point that attains the **transition temperature**, a temperature characteristic of each pure compound, the lipid undergoes a transition to one of the liquid-crystalline phases. On further heating, it melts completely. Addition of water at low temperature to the crystalline state causes formation of a gel phase, with water layers between the apposed polar headgroups. This gel phase will, on heating to the transition temperature, undergo transition to a liquid-crystalline phase similar to those described above.

liquid-gel chromatography a type of liquid chromatography in which the stationary phase is a gel. It includes **gel-permeation chromatography** and **ion-exchange chromatography**.

liquid glucose *an alternative name for* **corn syrup**.

liquid-junction potential the electric potential, not experimentally measurable, that arises across the boundary of two solutions of different compositions, e.g. between two half-cells. It is a complex function of the activities and transference numbers of the several ions in the transition layer.

liquid–liquid chromatography *abbr*.: LLC; a type of liquid chromatography in which the stationary phase is a liquid supported on a solid.

liquid medium any liquid **culture medium**.

liquid nitrogen nitrogen in the liquid state. It has a b.p. of –195.79°C (77.36 K), and is useful as a cooling and freezing agent.

liquid oxygen oxygen in the liquid state. It has a b.p. of –182.96°C (90.19 K).

liquid paraffin a colourless, odourless fraction of higher liquid hydrocarbons obtained from petroleum. Light liquid paraffin has a density of 0.83–0.86 g mL^{-1} and heavy liquid paraffin has a density of 0.86–0.89 g mL^{-1}. It is used for (hot) oil baths, and the purified material is used as a suspending medium in infrared spectroscopy.

liquid-scintillation counting *abbr*.: LSC; a technique for counting particulate radiation. The (radioactive) sample is dissolved or suspended in, or placed in close approximation to, a solvent containing one or more substances that are fluorescent and emit a pulse of light (scintillation) when excited by an incident ionizing particle or photon. The light is detected by photomultipliers, in a liquid-scintillation counter.

liquid-scintillation spectrometry **liquid-scintillation counting** of particulate radiation of one or more selected ranges of energies.

liquid-solid chromatography *abbr*.: LSC; a type of liquid chromatography in which the mobile phase is a liquid and the stationary phase a solid.

liquor 1 *(in pharmacy)* a (usually aqueous) solution of a pure substance. **2** a solution in a chemical manufacturing process. **3** the water used in brewing.

liquorice *or (esp. US)* **licorice** *see* **glycyrrhiza**.

Lisp *see* **programming language**. [Acronym from 'list processing'.]

liter *the US spelling of* **litre**.

lithiasis *(in pathology)* the presence of calculi (stones), e.g. in the biliary or urinary tracts.

lithium *symbol*: Li; an element of group 1 of the IUPAC **periodic table**; atomic number 3; relative atomic mass 6.939. It is a soft, silvery white, alkali metal of such high reactivity that it must be stored in an inert atmosphere or under oil. It is not found free in nature, occurring in the minerals spodumene and lepidolite. Lithium carbonate, Li_2CO_3 (commonly referred to as 'lithium') is used to control the symptoms of manic-depressive illness. Li^+ inhibits inositol phosphate phosphatase, thereby inhibiting the recycling of inositol, and reducing its availability for phosphatidylinositol synthesis.

lithogenesis *(in pathology)* the processes leading to formation of calculi (stones). —**lithogenic** *adj.*

lithotroph any member of the chemoautotrophs (*see* **chemotroph**) or **photolithotrophs** that uses CO_2 as a carbon source.

litre *or (US)* **liter** *symbol*: L *or* l; a non-SI unit of volume, now identical to the cubic decimetre; i.e. 1 L = 1 dm^3 = 10^{-3} m^3.

little gastrin *see* **gastrin**.

liver one of the largest organs of the vertebrate body, situated in the abdominal cavity and formed as a diverticulum of the gut. It is highly vascular; venous blood carrying the products of digestion enters via the hepatic portal vein, while arterial blood enters via the hepatic artery. Blood leaves via the hepatic vein. The liver functions as a gland by secreting **bile** and is an important site of metabolism of carbohydrates, proteins, and fats; it stores carbohydrate as **glycogen**, is active in **gluconeogenesis**, and is important in the regulation of the blood glucose level. It is also an important site for the synthesis of **urea** and **ketone bodies**. The liver synthesizes **fibrinogen**, **prothrombin**, **serum albumin**, and other blood proteins and plays an important part in **detoxication**. The major cells in the liver are the **hepatocytes**. The liver also contains **Kupffer cells** of the reticuloendothelial system, cells derived from the bile duct cannaliculae, and fibroblasts, which are particularly important in the pathogenesis of liver cirrhosis. *See also* **regeneration** (def. 2).

liver X receptor *abbr*.: LXR; *an alternative name for* **oxysterol receptor**.

livin *or* **melanoma inhibitor of apoptosis protein** (*abbr*.: ML-IAP); a protein expressed in melanoma cells that inhibits apoptosis. Livin α is not expressed in fetal tissues, whereas livin β is. They bind and inactivate caspases 3, 7, and 9.

LLC *abbr. for* liquid–liquid chromatography.

LLD factor *abbr. for Lactobacillus lactis* Dorner factor; a growth factor for this organism, identical to **vitamin B_{12}**.

LLF *or* **L-L factor** *abbr. for* Laki–Lorand factor, i.e. factor XIII (*see* **blood coagulation**).

lm *symbol for* **lumen** (def. 1).

L meromyosin *abbr. for* light meromyosin.

LMM *abbr. for* light meromyosin.

ln *symbol for* natural, or Napierian, **logarithm** (alternative to log$_e$).

L-NAME *abbr. for N*-ω-nitro-L-arginine methylester; an analogue of L-arginine that is a competitive inhibitor of this amino acid on NO synthase.

LNB-TM7 *abbr. for* long N-terminal of group B transmembrane 7; a subgroup of the G-protein-coupled membrane receptor family. Its members share a stalk region (consisting of ≈20% serine and threonine residues) and a characteristic sequence, containing four conserved cysteine residues, that is located immediately N-terminal to the first transmembrane segment. Several members also contain other homology regions in the extracellular region. *See* **Ig-Hepta**.

αLnn *or (sometimes)* **Lnn** *symbol for* the linolenoyl *or* (9,12,15)-linolenoyl *or (formerly) α*-linolenoyl group; *see* **linolenoyl** (def. 1).

γLnn *symbol for* the (6,9,12)-linolenoyl *or (formerly) γ*-linolenoyl group; *see* **linolenoyl** (def. 2).

lnRNA *abbr. for* low-molecular-weight nuclear RNA (*see* **small nuclear RNAs**).

load *(in metabolic studies)* the amount (of a specified substance) given in a metabolic test.

loading test *or* **load test** a metabolic test in which the subject is given a dose of a specific substance and the concentration in blood and/or urine of the substance, or of some related metabolite, is determined as a function of time. Such a test is useful for determining the capacity of a particular metabolic pathway in the subject.

lobelia 1 any plant of the genus *Lobelia*. **2** *or* **Indian tobacco** the dried leaves, shoot tips, and seeds of *Lobelia inflata*, which contain the alkaloid **lobeline**.

lobeline 2-[6-(*β*-hydroxyphenethyl)-1-methyl-2-piperidyl]acetophenone; an alkaloid derived from **lobelia** (def. 2) with actions on the central and peripheral nervous systems that resemble those of **nicotine**. It is responsible for some of the properties of herbal cigarettes.



(–)-lobeline

Lobry de Bruyn–van Ekenstein transformation a nonenzymic transformation occurring in carbohydrates, usually in alkaline conditions, that includes epimerization of both aldoses and ketoses and aldose–ketose isomerization. [After Cornelius Adrian Lobry de Bruyn and W. Alberda van Ekenstein (1857–1937), who first described it in 1895.]

local alignment *see* **alignment**.

localized melting the (reversible) destabilization of tertiary structure in a limited region of an ordered biopolymer through interaction with a specific agent, e.g. an enzyme.

local similarity similarity that spans only short regions of a pair or set of aligned sequences (i.e. within a local alignment). *See* **alignment**.

locant a prefix or infix used in organic chemical nomenclature to identify the position of a substituent in a parent structure or of an isotopic modification to a compound. Locants are commonly Arabic numerals, but Greek letters and italicized symbols of heteroatoms are also used. In isotopically modified compounds the italicized name of the function containing the modification may be used if it has no number, e.g. in [*methyl*-^{14}C]methionine.

loci *the plural of* **locus**.

lock-and-key model a model for the mechanism of an enzyme–substrate combination, of a hormone–receptor interaction, or of an antibody–antigen reaction. In this model, which is based on the analogy of the complementarity of a lock and its key, one reactant is envisaged binding to the other on a site to which it is structurally complementary.

Locke's solution *or* **Locke solution** *or* **Ringer–Locke solution** any one of several balanced salt solutions modified from **Ringer's solution**, initially for the perfusion of mammalian heart and other tissues in physiological experiments. Such solutions have usually contained (in grams per litre, approx.) NaCl (9.0–9.5), KCl (0.20–0.42), $CaCl_2$ (anhydrous, 0.20–0.24), $NaHCO_3$ (0.1–0.3), and glucose (1.0–2.5). [After Frank Spiller Locke (1871–1949), British physiologist, who devised them in 1894 and 1900.]

lock-washer structure a putative intermediate structure formed during the assembly of subunits of the coat protein of tobacco mosaic virus into the helically organized structure of the fully formed virion. It is believed to arise after the primary sub-assembly, a two-layered disk with 17 subunits per layer, has self-aggregated into a cylinder; a dislocation in each disk then occurs so that it becomes a two-turn flattened protohelix, of similar shape to a lock washer of the sprung type.

Loco a protein of *Drosophila* that is homologous to the mammalian RGS12, which regulates G-protein signalling via $G_{\alpha 0}$ and $G_{\alpha i}$.

loco disease *see* **locoweed**.

locoweed any of various plants belonging to the genera *Astragalus* or *Oxytropis*, found mainly in western USA. They contain L-2-amino-3-(methylseleno)propionic acid (methylselenocysteine), a nonprotein amino acid, and may cause poisoning (**loco disease**) when ingested by livestock. [From Spanish *loco*, mad.]

locus (*pl.* **loci**) **1** *(in genetics)* the specific position, in all homologous chromosomes, of a particular gene or one of its alleles. **2** *(in mathematics)* the curve or line traced by a point moving so as to satisfy a particular set of conditions.

locus control region *abbr*.: LCR; a group of five regions upstream of the structural genes for the β chain of hemoglobin in human and mouse. These regions are essential for the expression of all the genes of the β-like gene cluster.

lod score *abbr. for* log of the odds score; a statistical test to determine whether a set of linkage data indicates linkage or not, the log$_{10}$ of the odds favouring linkage. For genetic disorders that are not X-linked, a lod score of +3 (1000:1 odds of linkage) indicates linkage, whilst a score of –2 is odds of 100:1 against linkage.

log 1 *symbol for* logarithm. **2** *abbr. for* logarithmic.

logarithm *abbr. and symbol*: log; the power to which a fixed number (the base) must be raised in order to produce a specified number; i.e. in the expression $a = b^n$, a is the specified number, b is the base, and n is the logarithm. In **decadic (common),** or **Briggsian**, **logarithms** the base is 10; the common logarithm of a is written as $\log_{10}a$, or lg a. In **natural**, or **Napierian**, **logarithms** the base is e (= 2.718 28...); the natural logarithm of a is written as $\log_e a$ or ln a. In **binary logarithms** the base is 2, and the binary logarithm of a is written as $\log_2 a$ or lb a. In converting between them, $\log_e a = 2.303 \times \log_{10}a$, and $\log_2 a = 3.322 \times \log_{10}a$.

logarithmic *or* **logarithmical** *abbr*.: log; **1** of, pertaining to, using, or containing **logarithms** of numbers or variables. **2** describing a relationship in which one variable is proportional to the logarithm of another.

logarithmic growth a type of growth pattern shown by bacteria or other cells in which the number of cells, or the cell mass, increases logarithmically (exponentially) with time. The rate of increase at any time is proportional to the number of cells, or the cell mass, present.

logarithmic phase *abbr*.: log phase; the phase of growth of bacterial or other cells during which they undergo **logarithmic growth**.

logarithmic plot *abbr*.: log plot; a graph in which one axis has a **logarithmic** (def. 1) scale and the other a linear scale.

logical operation an operation on **binary** numbers or statements used in computing and also in applications such as databases and library searches. There are three common binary operators (AND, OR, XOR) and one **unary operator** (NOT).

log–log plot double logarithmic plot; a graph on which both variables are plotted logarithmically.

log-odds score a score calculated as the logarithm of the likelihood of an event relative to its likelihood under a null model. Positive log-odds scores indicate that the event is more likely than it would be under the null model.

LOH *abbr. for* **loss of heterozygosity**.

Lohmann reaction *a name sometimes given to* the reversible reaction, catalysed by **creatine kinase**, in which ATP and creatine are formed from ADP and phosphocreatine. [After Karl Lohmann (1898–1978), German biochemist.]

Lohmann's enzyme *an alternative name for* **creatine kinase**.

lombricine the 2-guanidoethanol phosphoester of phosphoserine. In earthworms, the guanidine group can undergo phosphorylation to phospholombricine, which acts as a **phosphagen**.

lomustine 1-(2-chloroethyl)-3-cyclohexyl-1-nitrosourea; a chloroethylnitrosourea derivative with actions resembling **carmustine**.



London forces *see* **dispersion forces**.

lone pair *or* **nonbonding electrons** a pair of electrons of opposite spins occupying the same orbital in the valence shell of an atom.

long-acting thyroid stimulator *abbr*.: LATS; an IgG immunoglobulin found in the serum of a large proportion of thyrotoxic patients. It binds competitively with thyrotropin to thyrotropin receptors in thyroid plasma membrane, stimulates membrane adenylate cyclase, and causes longer-lasting stimulation of thyroid-hormone secretion than thyrotropin itself.

long-chain describing an aliphatic compound of any type with a chain length greater than ten carbon atoms (i.e. C_{10}).

long-chain alcohol *or* **fatty alcohol** any aliphatic compound with a chain length greater than C_{10} that possesses a terminal hydroxymethyl group. They are components of **ether lipids**, and esterified with long-chain fatty acids they form wax esters, often major components of plant cuticular waxes.

long-chain-alcohol *O*-fatty-acyltransferase EC 2.3.1.75; *other name*: wax synthase; an enzyme that catalyses the formation of a long-chain fatty acyl ester, i.e. a wax, from acyl-CoA and a long-chain alcohol with release of CoA.

long-chain base any aliphatic compound with a chain length greater than C_{10} that possesses a terminal basic group.

long-chain fatty acid any aliphatic compound with a chain length greater than C_{10} that possesses a terminal carboxyl group.

long-chain-fatty-acid–CoA ligase EC 6.2.1.3; *other names*: acyl-activating enzyme; acyl-CoA synthetase; fatty acid thiokinase (long-chain); lignoceroyl-CoA synthase; an enzyme that catalyses the reaction between ATP and a long-chain carboxylic acid and CoA to form an acyl-CoA with release of AMP and pyrophosphate. It activates free fatty acids formed, e.g., by phospholipase action for further metabolism.

long-chain-3-hydroxyacyl-CoA dehydrogenase EC 1.1.1.211; *other name*: *β*-hydroxyacyl-CoA dehydrogenase; an enzyme of the **beta-oxidation system** that catalyses the oxidation by NAD^+ of (*S*)-3-hydroxyacyl-CoA to 3-oxoacyl-CoA with the formation of NADH. It forms part of a trifunctional protein. *See* **3-hydroxyacyl-CoA dehydrogenase**.

longitudinal relaxation or **spin-lattice relaxation**, a process in magnetic resonance spectroscopy, such as EPR and NMR, that describes the return of the z component of longitudinal (z-) magnetization to its equilibrium value. The characteristic spin-lattice relaxation time is given the symbol T_1. Its reciprocal is the spin-lattice relaxation rate.

longitudinal relaxation time *an alternative name for* **spin-lattice relaxation time**.

long-patch repair *see* **short-patch repair**.

long PCR a form of PCR designed for the amplification of DNA molecules of >10kb or longer and using a mixture of proofreading and non-proofreading thermostable DNA polymerases such as Pfu and Taq.

long QT syndrome a syndrome of prolongation of the QT interval on surface electrocardiogram, recurrent fainting, episodic tachyarrhythmia, and sudden (or aborted sudden) death. It is associated with numerous loss-of-function mutations in several genes, including: *SCN5A* (encoding the α subunit of cardiac Na channel); *HERG* (encoding the α subunit of cardiac K channel I_{Kr}); *KCNE1* (encoding the β subunit of cardiac K channel I_{Ks}); and *KVLQT1* (encoding the α subunit of cardiac K channel I_{Ks}). *SCN5A* (at 3p21-p24) encodes a protein of 2016 amino acids containing four regions, each of which has six transmembrane segments. Gain-of-function mutations are associated with idiopathic ventricular tachycardia. *HERG* (for human ether-a-go-go-related gene) is at 7q35-q36 and encodes 1159 amino acids, including six transmembrane segments and extensive intracellular N- and C-terminal domains. *See also* ***KCNE1***, ***KVLQT1***.

long-range interaction describing an interaction between residues that are situated relatively far apart in a polypeptide or polynucleotide sequence.

long terminal repeat *abbr*.: LTR; a double-stranded DNA sequence, generally several hundred base pairs long, that is repeated at the two ends of the DNA of retroviruses and retrotransposons.

loop 1 the round or oval figure produced by a line, wire, thread, etc. that curves round to cross (or nearly cross) itself. **2** *(in electronics)* any closed electric or magnetic circuit through which a signal can circulate. **3** *(in computing)* any set of instructions in a program that is carried out repeatedly until some specified condition is satisfied.

loopback DNA *an alternative name for* hairpin DNA; *see* **hairpin**.

loop injector a device for introducing samples into a high-pressure liquid chromatographic column without interruption of the solvent flow to the column. It consists of a loop of metal tubing of small volume, which is filled with the sample; this can then, by an appropriate valve, be flushed by eluent directly onto the column.

loop of Henle *or* **Henle's loop** the U-shaped part of a nephron lying in the renal medulla. It comprises a thin descending tubule and an ascending tubule formed of both a thin and a thick segment. It plays a role in the selective reabsorption of fluid and solutes. [After Friedrich Gustav Jakob Henle (1809–85), German anatomist and pathologist.]

lophotoxin a cyclic diterpenoid, isolated from Pacific gorgonians (sea fans and whips) of the genus *Lophogorgia*, that irreversibly inactivates the nicotinic acetylcholine receptor on intact BC3H-1 cells.

Lorentz correction factor a correction factor for the effect of solvent polarizability on optical rotation by solutions of proteins or other macromolecules. It is given by: $3/(n^2 + 2)$, where n is the refractive index of the solvent. [After Hendrik Antoon Lorentz (1853–1928).]

Lorentzian lineshape function an equation for the lineshape of a nuclear magnetic resonance absorption signal:

$$g(\omega) = T_2/[1 + (\omega - \omega_0)^2 T_2^2],$$

where $g(\omega)$ is a measure of the intensity of the resonance at a frequency ω, ω_0 is the actual Larmor frequency of the resonating nucleus, and T_2 is the spin–spin relaxation time.

loricrin the major protein of the cornified cell envelope of terminally differentiated epidermal keratinocytes. It is a substrate for transglutaminase, and exists as monomers cross-linked by disulfide and *N*-(*γ*-glutamyl)lysine isodipeptide bonds.

losartan 2-butyl-4-chloro-1-(*p*-(*O*-1*H*-tetrazol-5-ylphenyl)benzyl)-imidazol-5-methanol; an antihyperactive drug that blocks the binding of angiotensin II (*see* **angiotensin**)to the AT_1 receptor. Affinity for this receptor is much greater than for the AT_2 receptor. It is oxidized by a cytochrome P450 to a carboxylic-acid metabolite that is largely responsible for most of its angiotensin II antagonistic effects.

Loschmidt constant *symbol*: N_L; the number of molecular entities in unit volume of an ideal gas at 1 atm and 273.15 K. It is equal to the **Avogadro constant** divided by the molar volume, and has the value 2.686 763 × 10^{25} m^{-3}. [After Josef Loschmidt (1821–95), Austrian physicist.]

Loschmidt number *or* **Loschmidt's number** the numerical value of the **Loschmidt constant**.

loss of heterozygosity *abbr*.: LOH; in genetics, the situation where one of the mutant alleles of an autosomal gene is inherited, and the mutation of the other allele arises by somatic mutation. Cells with the somatic mutation at that locus have lost heterozygosity as they now have two mutant alleles. LOH in tumor supressor genes such as *RB1* and *p53* is of importance in cancer genetics.

lovastatin *or* **mevinolin** 6α-methylcompactin; a metabolite from some fungi (e.g. *Monascus ruber*, *Aspergillus terreus*) that is a potent inhibitor of **hydroxymethylglutaryl-CoA reductase**. It is useful clinically as an antihypercholesterolemic; it reduces plasma levels of total low-density-lipoprotein (LDL), and very-low-density-lipoprotein cholesterol, but it can increase high-density-lipoprotein cholesterol. Its effects result in the induction of up-regulation of LDL receptors on hepatocytes. Two proprietary names are: Mevacor; Mevinacor.



low-complexity region a region in the amino-acid sequence of a protein in which a particular amino acid, or a small number of different amino acids, are enriched. *See*, for example, **leucine zipper**.

low-density lipoprotein *abbr*.: LDL; one of the classes of lipoprotein found in blood plasma in many animals (data normally relate to humans). LDLs are also known as β lipoproteins, owing to their electrophoretic mobility intermediate between high-density or α lipoprotein, and the origin. LDL particles have diameter 19.6–22.7 nm, solvent density for isolation (g mL^{-1}) 1.019–1.063, hydrated density (g mL^{-1}) 1.034. Their approximate composition (% by weight) is 13% unesterified cholesterol, 39% esterified cholesterol, 17% phospholipid, 11% triacylglycerol, 20% protein. Their apolipoprotein composition (% by weight total apolipoprotein) is 98% B-100, with traces of different C and E apolipoproteins. They are synthesized in plasma from very-low-density lipoproteins and intermediate density lipoproteins through the action of lipoprotein lipase; they transport cholesterol to peripheral tissues. They have the highest content of cholesterol of any plasma lipoprotein, and have been linked to the incidence of coronary heart disease in epidemiological studies. *See also* **apolipoprotein** (for individual apolipoproteins) and **LDL receptor**.

low-density-lipoprotein receptor *see* **LDL receptor**.

low-energy compound a name sometimes applied improperly to certain compounds that undergo reaction leading to release or transfer of, e.g., phosphate, where the standard free energy change for the hydrolysis of the bond is <20 kJ mol^{-1}. It is used especially in making a distinction from a **high-energy compound**. The use of the term does not meet the highest standards of thermodynamic correctness.

low-lipid lipoprotein *(sometimes) an alternative name for* **high-density lipoprotein**.

Lowry method a colorimetric method for the estimation of small amounts (down to 10 μg) of protein. It is a combination of the **biuret reaction** for peptide bonds and the colour formed by reaction of **Folin–Ciocalteau reagent** with tyrosine and tryptophan residues in the protein. [After Oliver Howe Lowry (1910–1996), US pharmacologist and biochemist.]

low-spin complex any of the ligand complexes of transition-metal ions having a maximal number of paired *d*- or *f*-shell electrons in the lower energy levels. This state occurs when the pairing energy is less than the crystal-field splitting energy. *Compare* **high-spin complex**.

Lozenge a protein of *Drosophila* that is involved in the determination of photoreceptor identity during eye development. Its DNA-binding domain is homologous with that of Runt (of *Drosophila*) and AML1 (of human).

LPG *abbr. for* lipophosphoglycan (*see* **GPI anchor**).

LPH *abbr. for* lipotropic hormone (i.e. **lipotropin**).

LPL *abbr. for* lipoprotein lipase.

L protein *see* **glycine cleavage enzyme**.

LPS *abbr. for* **1** lipopolysaccharide. **2** lipase (def. 2).

LPS-binding protein *see* **BPI protein**.

Lr *symbol for* lawrencium.

L region any region in a (carcinogenic) polycyclic aromatic hydrocarbon that consists of two *para*-carbon atoms, e.g. the *meso*-9,10-carbon atoms of anthracene, which display the highest free-valence indices. The lack of such a region has been suggested to correlate with a lack of carcinogenicity of some hydrocarbons. *Compare* **K region**.

LRF *abbr. for* luteinizing hormone releasing factor (*see* **gonadotropin-releasing hormone**).

LRH *abbr. for* luteinizing hormone releasing hormone (*see* **gonadotropin-releasing hormone**).

LRP *abbr. for* LDL receptor-related protein; *other names*: apoE/α_2-macroglobulin receptor; E/α_2-M receptor. A multifunctional plasma membrane receptor primarily of hepatocytes. It is a transmembrane protein of 4525 residues that is homologous to **LDL receptor**. Its extracellular domain contains 31 cysteine-rich repeats and 22 EGF repeats (versus 7 and 3, respectively, in LDL receptor). It binds chylomicron remnants, hepatic lipase, α_2-macroglobulin, plasminogen activator-inhibitor complexes, lactoferrin, and *Pseudomonas* exotoxin A. *See also* **LRP2**.

LRP2 *abbr. for* LDL receptor-related protein 2; *other names*: megalin; gp330; Haymann nephritis antigen. A large transmembrane glycoprotein of 4635 residues that is homologous with LRP and binds most of the latter's ligands. It is abundant in renal glomeruli and proximal tubules but also occurs in other tissues. It appears to be a drug receptor that mediates uptake of aminoglycosides, polymixin B, and gentamicin. *See also* **LRP**.

LRr *abbr. for* leucine-rich repeat.

LSC *abbr. for* **1** liquid-scintillation counting. **2** liquid–solid chromatography.

LSD *abbr. for* lysergic acid diethylamide; *see* **lysergic acid**.

L7/L12 site a component of EF-Tu translocase (*see* **EF-T**) activity involving in bacteria the **ribosomal proteins** L7 and L12.

L strand *abbr. for* light strand.

LT *abbr. for* **1** leukotriene; the subtype may be indicated by a third letter, as in LTA (leukotriene A). **2** lymphotoxin.

LTQ *abbr. for* lysine tyrosylquinone; a quinone cofactor derived by post-translational linking of a lysine residue with a topaquinone in some quinoproteins. It is the cofactor of lysyl oxidase.

LTR *abbr. for* long terminal repeat.

LTRPC *abbr. for* long transient receptor potential channel. *See* **TRP channel**.

LTRPC2 *see* **TRP channel**.

LTRPC7 *see* **TRP channel**.

L-type pentose pathway *see* **pentose phosphate pathway**.

Lu *symbol for* lutetium.

Lubrol *a proprietary name for* a polyoxyethylene nonionic detergent; the structure of Lubrol PX is the same as $C_{12}E_9$ (see $\mathbf{C_x E_y}$). It is useful for solubilizing membrane-bound enzymes such as adenylate cyclase.

LUCA *abbr. for* last universal common ancestor.

LUCA 15 a multidomain RNA-binding protein that is generally conserved in eukaryotes and is deleted in certain human lung cancers. It contains two N-terminal RNA-recognition sequences, a C2H2 zinc finger, and a C-terminal glycine-rich sequence. The rat homologue is associated with hnRNPs.

luciferase any member of a group of monooxygenase enzymes that catalyse bioluminescent reactions. **Firefly luciferase** (EC 1.13.12.7; *recommended name*: *Photinus* luciferin 4-monooxygenase (ATP hydrolysing)) occurs in the lantern of the American firefly, *Photinus pyralis*, and may be used with firefly **luciferin** for estimation of low concentrations (10^{-6}–10^{-10} mol L^{-1}) of ATP. It catalyses a reaction between *Photinus* luciferin, O_2, and ATP to form oxidized *Photinus* luciferin, CO_2, H_2O, AMP, pyrophosphate, and $h\nu$; magnesium is a cofactor. It covalently binds the adenylyl group (AMP) after reaction with ATP and release of pyrophosphate. It is a peroxisomal enzyme. **Renilla luciferase** (EC 1.13.12.5; *recommended name*: *Renilla*-luciferin:oxygen 2-oxidoreductase (decarboxylating)) occurs in the sea pansy *Renilla reniformis* and catalyses the reaction between *Renilla* luciferin (2,8-dibenzyl-6-(4-hydroxyphenyl)imidazo[1,2-*a*]pyrazin-3(7*H*)-one) and O_2 to form oxidized *Renilla* luciferin, CO_2, and *hν*. Luciferin is bound to a luciferin-binding protein (BP-LH2). Bioluminescence is triggered by calcium ions, and the excited state transfers energy to an accessory protein, *Renilla* green fluorescent protein, which emits green light. **Bacterial luciferase** (EC 1.14.14.3; *recommended name*: alkanal monooxygenase (FMN-linked)) occurs in *Photobacterium fischeri* and catalyses a reaction between RCHO, reduced FMN, and O_2 to form RCOOH, FMN,H_2O, and $h\nu$. It may be used together with NAD(P)H dehydrogenase (FMN), EC 1.6.8.1, from luminescent bacteria for estimation of low concentrations (10^{-7}–10^{-9} mol L^{-1}) of NAD(P)H. *See also* **lux proteins**.

luciferin any bioluminescent substance that is a substrate for a **luciferase** enzyme. Luciferins from different sources often bear no structural resemblance to one another. Firefly luciferin, obtained from the lantern of the American firefly, *Photinus pyralis*, is D-(–)-4,5-dihydro-2-(6-hydroxy-2-benzothiazoloyl)-4-thiazolecarboxylic acid.



Lucifer Yellow one of several dyes based on the structure 6-amino-2,3-dihydro-1,3-dioxo-benz[*d*,*e*]isoquinoline-5,8-disulfonic acid. Lucifer Yellow CH has been used as a marker for movement between cells, and for ultrastructure tracing; Lucifer Yellow VS covalently labels proteins rapidly under mild conditions.



Lucifer Yellow CH



Lucifer Yellow VS

Lucite *a proprietary name for* **poly(methyl methacrylate)**.

lufenuron *N*-[2,5-dichloro-4-(1,1,2,3,3,3-hexafluoropropoxy)-phenylaminocarbonyl]-2,6-difluorobenzamide; an inhibitor of insect development, used as a once-per-month pill to control flea populations on domestic dogs, by inhibiting egg development.



luffin a type I **ribosome-inactivating protein**.

luliberin *the recommended name for* a hypothalamic decapeptide amide now known to be identical with **gonadotropin-releasing hormone**.

lumen 1 (*pl.* **lumens**) *symbol*: lm; the SI derived unit of **luminous flux**, equal to the quantity of visible electromagnetic radiation emitted per second in a cone of unit solid angle (one steradian, sr) by a uniform point source of unit luminous intensity (one candela, cd); i.e. 1 lm = 1 cd sr. **2** (*pl.* **lumina**) the cavity or passageway of a tubular organ, such as a blood vessel, duct, or length of gut. **3** the volume enclosed within the membranes of a mitochondrion or of the endoplasmic reticulum, or of microsomes prepared from cells. **4** the space enclosed by the walls of a plant cell that no longer contains a protoplast. **5** the bore of a catheter, hollow needle, or other tubular device. —**luminal** *adj.*

lumichrome 7,8-dimethylalloxazine; a compound showing a blue fluorescence, formed by the photolysis of riboflavin in acid or neutral solution.



lumiflavin 7,8,10-trimethylisoalloxazine; a compound showing a yellow-green fluorescence, formed by the photolysis of riboflavin in alkaline solution.



lumigenic substrate any substrate capable of emitting light when acted on by an appropriate enzyme.

lumina *the plural of* **lumen** (def. 2).

luminal protein *or (sometimes)* **ER-resident protein** any protein that is retained within the cisternae of the **rough endoplasmic reticulum**, e.g. protein disulfide isomerase. Such proteins possess at their C terminus the tetrapeptide sequence Lys-Asp-Glu-Leu (**KDEL**) in animal cells and His-Asp-Glu-Leu (**HDEL**) in yeast. The proteins move to the Golgi and are returned to the endoplasmic reticulum.

luminescence the production of visible light by any mechanism that does not depend upon the system having a temperature appreciably above the ambient. It comprises **fluorescence** and **phosphorescence**. —**luminescent** *adj.*

luminogenic 1 producing **luminescence**. **2** of or pertaining to a non-luminescent material that can be acted on by an enzyme to produce a luminescent substance.

luminol 5-amino-2,3-dihydro-1,4-phthalazinedione; a substance useful in the detection or determination of trace amounts of oxidizing agents by virtue of the intense bluish luminescence it emits on oxidation in alkaline solution.



luminometer an instrument for measuring **luminescence**. Given appropriate conditions, it may be used also to measure the concentrations of enzymes, substrates, etc. that participate in, or can be coupled to, light-producing reactions.

luminometry the measurement of **luminescence** with a luminometer. —**luminometric** *adj.*

luminophore **1** any luminescent substance, whether a fluor or a phosphor. **2** a molecular grouping responsible, or thought to be responsible, for the **luminescence** of a larger molecule; a luminescent chromophore.

luminous **1** emitting visible light; bright, shining. **2** *(in photometry)* (of a physical quantity relating to light) evaluated by the visual sensation of brightness to the eye of an observer rather than by an absolute measurement of radiant energy.

luminous flux *symbol*: Φ_v *or* Φ *or* P_v *or* P; a measure of the rate of flow of radiant energy within the visible region of the electromagnetic spectrum. The SI derived physical quantity is the arithmetic product of the **luminous intensity** of a source of visible light and the solid angle, expressed in steradians, into which the light is emitted. The SI derived unit of luminous flux is the **lumen** (def. 1).

luminous flux density the **luminous flux** per unit cross-sectional area of a beam of light.

luminous intensity *symbol*: I_v *or* I; one of the seven SI base physical quantities, defined as the amount of visible light emitted per second per steradian by a point source in a given direction. The SI base unit of luminous intensity is the **candela**.

lumirhodopsin an intermediate in the light-induced modification of **rhodopsin** prior to its breakdown into opsin and all-*trans*-retinal. It has an absorption maximum at 497 nm.

lumisome a membrane-bound particle, ≈200 nm in diameter and present in homogenates of various species of luminescent marine coelenterates, that contains all the proteins necessary for the production of the typical green bioluminescence observable *in vivo*. It is probably the cytoplasmic organelle responsible for emission of light by such organisms.

lumisterol 9*β*,10*α*-ergosta-5,7,22-trien-3*β*-ol; a compound produced by the UV irradiation of **ergosterol**, from which it differs in the spatial arrangement of the methyl group at C-10.



Lundh test a test for pancreatic function in which the pancreas is stimulated by a test meal (corn oil, milk powder, and glucose), after which trypsin activity is measured in duodenal juice.

lupus erythematosus an autoimmune disease characterized by recurrent red patches on the skin, usually accompanied by episodes of inflammation of joints, tendons, and other connective tissues and organs. Antinuclear and various other antibodies are usually present in serum.

luteal of, relating to, or characterized by the development of a corpus luteum or corpora lutea.

luteal phase *see* **estrous cycle**.

lutein 3,3′-dihydroxy-*α*-carotene, one of the most widespread naturally occurring xanthophylls (i.e. carotene alcohols; *see* **carotenoid**), found in many higher plants, some algae, egg yolk, and corpora lutea. It is an antioxidant.



luteinize *or* **luteinise** to cause the formation of corpora lutea in; to undergo transformation into a corpus luteum. —**luteinization** *or* **luteinisation** *n.*

luteinizing hormone *or* **luteinising hormone** *abbr.*: LH; *recommended name*: lutropin; *former name*: interstitial cell-stimulating hormone (*abbr.*: ICSH). One of the two gonadotropic **glycoprotein hormones** secreted by the anterior pituitary. The human hormone (28.5 kDa) consists of an α subunit that is almost identical to that of other glycoprotein hormones, and a β subunit that confers hormonal specificity; the carbohydrate content is 15.5%. In the female it promotes ovulation and luteinization of the ovarian follicle, where it stimulates the conversion of progesterone to pregnenolone, thereby increasing the formation of further progesterone. In the male it stimulates testicular interstitial (Leydig) cell function by promoting the production of androgens, especially testosterone. LH binds to a G-protein-associated membrane receptor. Mutations in the receptor lead to hypogonadism or to precocious puberty in males. Mutations in the β subunit of LH also lead to hypogonadism in males.

luteinizing hormone/follicle-stimulating hormone releasing factor *abbr.*: LH/FSH-RF *see* **gonadotropin-releasing hormone**.

luteinizing hormone releasing factor *abbr.*: LHRF *see* **gonadotropin-releasing hormone**.

luteinizing hormone releasing hormone *abbr.*: LHRH *or* LH-RH *or* LRH; *see* **gonadotropin-releasing hormone**.

luteo+ *comb. form* indicating **1** yellow. **2** of the **corpus luteum**.

luteolin a flavone that is present in alfalfa and induces *nod* gene expression in some *Rhizobium* species.

luteolysin *an alternative name for* **prostaglandin** $F_{2\alpha}$.

luteolysis degeneration or regression of the **corpus luteum**. —**luteolytic** *adj.*

luteotropic hormone *or* **luteotrophic hormone** *abbr.*: LTH; *a former name for* **prolactin**.

luteotropin *or* **luteotrophin** *a former name for* **prolactin**.

lutropin *the recommended name for* **luteinizing hormone**.

lutropin receptor a G-protein-coupled membrane receptor that mediates the effects of lutropin via activation of adenylate cyclase. It has a long extracellular N-terminal region (≈340 amino acids) that is glycosylated.

lux *symbol*: lx; the SI derived unit of illuminance, equal to 1 lumen per square metre; i.e. 1 lx = 1 l mm^{-2}.

Lux proteins the counterpart in marine bacteria of the **luciferase** system. They mediate bioluminescence, and are products of genes regulated by the *lux* operon. In *Vibrio* spp., LuxA (catalytic subunit) and LuxB constitute bacterial luciferase (EC 1.14.14.3); it catalyses a reaction between reduced FMN, RCHO, and O_2 to form FMN, RCOOH, H_2O, and $h\nu$. LuxC is an **acyl-CoA reductase** required to form the ‘RCHO’ above. LuxD is an acyl transferase component of the fatty acid reductase system required for aldehyde biosynthesis (EC 2.3.1.–). LuxE is an acyl-protein synthetase (EC 6.2.1.19) that activates tetradecanoic acid. LuxG is the flavin reductase. LuxI and LuxJ are part of the regulatory system; they are required for the synthesis of OHHL (*N*-(3-oxohexanoyl)-L-homoserine lactone), an autoinducer molecule that binds to LuxR. LuxR is the transcriptional activator.

LVP *abbr. for* lysine vasopressin.

LW antigen *abbr. for* Landsteiner–Weiner antigen. *See* **Rhesus factor**.

lx *symbol for* lux.

LX *abbr. for* lipoxin.

LXR *abbr. for* liver X receptor. *See* **oxysterol receptor**.

lyase **1** *the systematic name for* any enzyme of EC class 4 that catalyses the cleavage of C–C, C–O, C–N, and other bonds, leaving double bonds, or conversely adding a group to a double bond. **2** **17,20-lyase** *the common name for* 17α-hydroxyprogesterone aldolase (EC 4.1.2.30).

lyate ion the anion produced by the autoprotolysis of a protogenic solvent; e.g. the hydroxide ion is the lyate ion of water.

lycopene the characteristic red pigment of tomatoes and some other ripe fruit. It is an acyclic carotenoid, and the biosynthetic precursor of the cyclic carotenes in plants.



lycopodium **1** any clubmoss of the genus *Lycopodium*. **2** the spores of various clubmosses, e.g. *L. clavatum*. They are used as a covering for pills and suppositories, in pyrotechnics, and in foundry work.

lymph **1** the pale-yellow, clear, or cloudy fluid that is contained within the vessels of the **lymphatic system**. It contains a little protein, and derives from the interstitial fluid, which is drained by the lymphatic vessels and ultimately discharged into the bloodstream, e.g. via the thoracic duct. The composition of lymph varies in different parts of the body, that from the liver and intestine containing more protein, and the latter more fat in the form of chylomicrons. Lymph also contains varying numbers of cells, mostly small lymphocytes, and coagulation factors. **2** the exudation from a sore.

lymphatic **1** of, pertaining to, or containing lymph; of or pertaining to the lymphatic system. **2** a lymphatic vessel.

lymphatic system the extensive network of capillary-like lymphatic vessels in vertebrates that convey the lymph from the peripheral tissues to the venous system. **Lymph nodes** occur at various points along the vessels.

lymph node *or* **lymph gland** any of numerous small swellings distributed throughout the lymphatic system of vertebrates. Each node consists largely of lymphocytes, together with macrophages and dendritic cells held together in a loose reticulum. Lymph nodes receive lymph from the peripheral tissues via afferent lymphatic vessels and pass it on via efferent vessels to more centrally placed lymph nodes, and ultimately to the thoracic duct. The lymph nodes act as filters through which the lymph must pass and where foreign material comes into intimate contact with macrophages and lymphocytes. They are active centres for phagocytosis and the site of initiation of humoral and cell-mediated immune reactions.

lympho+ *or (before a vowel)* **lymph+** *comb. form* indicating lymph or the lymphatic system.

lymphoblast any **blast cell** of the **lymphoid cell series**. **—lymphoblastic** *adj.*

lymphocyte a type of **leukocyte** found in vertebrates and having various functions in specific immunity. It is a spherical cell, 7–12 μm in diameter, with a large, round nucleus, often indented when seen by electron microscopy, and scanty cytoplasm containing scattered ribosomes but little endoplasmic reticulum and few other organelles. Lymphocytes occur in lymph nodes, other tissues, lymph, and blood, and they circulate between these tissues. Mature, differentiated lymphocytes comprise two main classes, **B lymphocytes** and **T lymphocytes**. Lymphocytes without the characteristics of either of these classes are termed **null lymphocytes**.

lymphocyte-activating factor *abbr.*: LAF; *an alternative name for* **interleukin 1**.

lymphocyte-specific protein-tyrosine kinase *see* **Lck**.

lymphocyte transformation *see* **transformation** (def. 3).

lymphocytosis an abnormal increase in the number of lymphocytes, especially in blood.

lymphoid of or resembling lymph, or lymphatic tissue.

lymphoid cell series a cell series comprising all cells that morphologically resemble **lymphocytes**, their precursors (e.g. lymphoblasts), and cells that may be derived from them (e.g. plasma cells).

lymphoid tissue any vertebrate tissue that is made up predominantly of **lymphocytes**, e.g. lymph, lymph nodes, spleen, thymus, Peyer's patches, adenoids, pharyngeal tonsils, and, in birds, bursa of Fabricius and cecal tonsils.

lymphokine any soluble nonimmunoglobulin released by primed lymphocytes on a second interaction with the specific activator (which may be a soluble antigen, a cell-associated antigen, or a mitogen). They modulate **cell-mediated immunity** by modulating the behaviour of other types of cell within the same organism (e.g. macrophages, polymorphonuclear leukocytes), and are recognized as a subgroup of the **cytokines**. Specific lymphokines include: chemotactic factor for macrophages, lymphotactin, lymphotoxin (i.e. **tumour necrosis factor** β), macrophage-activating factor (MAF), macrophage migration enhancement factor, **macrophage migration inhibitory factor** (MIF), (antigen-independent) mitogenic factor, skin-reactive factor, and **transfer factor**. Lymphokines that can act between different populations of leukocytes are known also as **interleukins**. *See also* **colony-stimulating factor**.

lymphoma any malignant tumour, or condition allied to a tumour, arising from some or all of the cells of lymphoid tissue. The term includes lymphatic leukemias, Hodgkin's disease, and reticuloses.

lymphoreticular tissue *an old general term for* tissues consisting largely of lymphocytes and macrophages.

lymphotoxin *abbr.*: LT; *an alternative name for* **tumour necrosis factor** β; *see also* **lymphokine**.

lyn a protooncogene encoding a **tyrosine kinase** belonging to the ***src*** family.

Lynx a very powerful free open-source text-only **browser** originally designed for use with character-cell, nongraphics terminals but of great value in rapid access to HTML pages and for checking such pages for compliance with guidelines for visually impaired users.

lyo+ *comb. form* indicating looseness, dispersion, or dissolution.

lyochrome *a former name for* **flavin**.

lyocytosis cell lysis by extracellular digestion, e.g. during insect metamorphosis.

lyoenzyme *an old term for* any enzyme existing in the cell in soluble form.

lyoglycogen *an old name for* the fraction of a sample of glycogen that is extractable by water on a steam bath.

lyolysis *an alternative term for* **solvolysis**.

Lyon hypothesis *(in genetics)* the hypothesis that gene dosage compensation in mammals is accomplished by random inactivation of one of the two X chromosomes in all somatic cells of females. The first inactivation occurs early in embryogenesis. [After Mary Francis Lyon (1925–), British geneticist.]

lyonium ion any cation produced by the protonation of a solvent molecule, e.g. H_3O^+, $CH_3OH_2^+$.

lyophile **1** *(in chemistry)* a **lyophilic** compound. **2** having lyophilic properties.

lyophilic *or* **lyophile** (of a substance or surface) solvent preferring; easily wetted or solvated by the solvent present; the term comprehends **hydrophilic** when the solvent is water. *Compare* **lyophobic**.

lyophilic sol any sol in which the disperse phase has an attraction for the continuous phase.

lyophilization *or* **lyophilisation** strictly, the process of rendering lyophile or lyophilic. The term is now usually specifically applied to freeze-drying in which, by use of a vacuum, water is removed from ice by sublimation. This use bears little relationship to the true meaning of lyophile, except in so far as it maintains proteins subjected to it in a lyophilic state. **—lyophilize** *or* **lyophilise** *vb.*

lyophilizer *or* **lyophiliser** an apparatus for effecting lyophilization; a freeze-drier.

lyophobic *or* **lyophobe** (of a substance or surface) solvent rejecting; resistant to being wetted or solvated by the solvent present; the term comprehends **hydrophobic** when the solvent is water. *Compare* **lyophilic**.

lyophobic sol any sol in which the disperse phase has no attraction for the continuous phase. Lyophobic sols cannot be formed by spontaneous dispersion in the medium.

lyotropic *or* **lyotrope** of or associated with the difference between the internal pressure of a solution compared with that of the solvent caused by the solute.

lyotropic mesophase any mesophase (i.e. **liquid crystal**) whose phase transitions are readily effected by changes in concentration.

lyotropic series *or* **Hofmeister series** a series of ions arranged in order of their **lyotropic** effects, especially their ability to cause precipitation of a lyophilic sol (to salt-out).

lypressin *see* **[8-lysine]vasopressin**.

Lys *symbol for* a residue of the α-amino acid L-lysine (alternative to K).

lys+ *a variant form of* **lyso+** (before a vowel).

lysate any solution or other preparation containing the products of **lysis** of cells. The term is applied especially to lysed bacterial or blood cells.

+lysate *comb. form* denoting a mixture resulting from decomposition, breakdown, or lysis (of or by something indicated); e.g. autolysate, cytolysate, hemolysate, hydrolysate.

Lys-bradykinin *abbr. for* lysylbradykinin (i.e. kallidin); *see* **bradykinin**.

lyse to effect **lysis** (of a cell, etc.); to undergo lysis.

+lyse *comb. form* denoting decompose, breakdown, or lyse (of or by something indicated); e.g. autolyse, cytolyse, electrolyse, hemolyse, hydrolyse.

lysenin any of a family of pore-forming peptidic toxins with about 300 amino acid residues, permitting passage of small solutes, including water. They are produced by *Eisenia foetida* and are classified in the TC system under number 1.A.43.

lysergamide lysergic acid amide. All known **ergot alkaloids** are derivatives of D-lysergamide, the simplest being **ergonovine**.

lysergic acid 9,10-didehydro-6-methylargoline-8β-carboxylic acid; an alkaloid obtained from **ergot**; it is a tetracyclic indole derivative. Lysergic acid diethylamide (*abbr*.: LSD) is a powerful hallucinogenic substance.



lysigeny *(in botany)* the disintegration of cells that occurs when new structures (e.g. aerenchyma or oil glands) are differentiating.

lysin any agent, such as an antibody, enzyme, toxin, etc., that is able to lyse cells.

+lysin *comb. form* denoting an (indicated) agent that effects, or can effect, lysis, specifically the lysis of cells (cytolysis).

lysinate 1 lysine anion; the anion, $H_2N–[CH_2]_4–CH(NH_2)–COO^-$, derived from **lysine**. **2** any salt containing lysine anion. **3** any ester of lysine.

lysine *the trivial name for* α,ε-diaminocaproic acid; 2,6-diaminohexanoic acid; $H_2N–[CH_2]_4–CH(NH_2)–COOH$; a chiral α-amino acid. L-Lysine (*symbol*: K *or* Lys), (*S*)-2,6-diaminohexanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: AAA or AAG. In mammals, it is an essential dietary amino acid, and is ketogenic. D-Lysine (*symbol*: DLys *or* D-Lys), (*R*)-2,6-diaminohexanoic acid, is a substrate for **lysine racemase** and D-lysine 5,6-aminomutase. The conversion of D-lysine to L-pipecolic acid, and of the latter to L-lysine, occurs in *Nicotiana glauca* and in *Neurospora crassa*.



L-lysine

D-lysine 5,6-aminomutase EC 5.4.3.4; *other name*: D-α-lysine mutase; an enzyme that catalyses the reaction:

D-lysine = 2,5-diaminohexanoate;

cobalamin is a cofactor.

lysine(arginine) carboxypeptidase EC 3.4.17.3; *other names*: carboxypeptidase N; arginine carboxypeptidase; kininase I; anaphylotoxin inactivator; an enzyme that hydrolyses peptidyl-L-lysine (or L-arginine) to peptide and L-lysine (or L-arginine). It inactivates bradykinin complement components, C3a and C5a, by removal of the C-terminal Arg.

lysine (base) a lysine residue when the ε-amino group is unprotonated.

lysine hydroxylase *see* **procollagen-lysine 5-dioxygenase**.

lysine 6-monooxygenase *see* **monooxygenase**.

lysine-2-oxoglutarate reductase *an alternative name for* **saccharopine dehydrogenase (NAD⁺, L-lysine forming)**

lysine racemase EC 5.1.1.5; an enzyme catalysing the reaction:

L-lysine = D-lysine.

lysine tyrosylquinone *see* **LTQ**.

lysine vasopressin *see* **[8-lysine]vasopressin**.

[8-lysine]vasopressin *abbr*.: [Lys^8]vasopressin; *nonproprietary name*: lypressin; the molecular form of **vasopressin** in which the variable eighth position in its amino-acid sequence is occupied by a lysine residue. This is the form of the hormone present in pigs and a few other related mammals. It is sometimes incorrectly designated as lysine vasopressin.

lysinium 1 *the usual term for* lysinium(1+); the monocation of **lysine**. In theory, the term denotes any ion, or mixture of ions, formed from lysine, and having a net charge of +1, although the species $H_3N^+–[CH_2]_4–CH(NH_3^+)–COO^-$ generally predominates in practice. **2** *the systematic name for* lysinium(2+); the dication of lysine.

lysino 1 ***N*²-lysino** the alkylamino group, $H_2N–[CH_2]_4–CH(COOH)–NH–$, derived from lysine by loss of a hydrogen atom from its α-amino group. **2** ***N*⁶-lysino** the alkylamino group, $HOOC–CH(NH_2)–[CH_2]_4–NH–$, derived from lysine by loss of a hydrogen atom from its ε-amino group.

lysinuric protein intolerance a genetically determined metabolic defect of humans in which the ingestion of relatively large amounts of lysine (in protein) causes hyperlysinemia, hyperammonemia, and coma. The defect is probably in a cationic amino-acid transporter.

lysis 1 *(in chemistry)* the breaking down of a substance by the splitting of its molecules into two parts; the rupture of a covalent bond. **2** *(in biology)* the disintegration of cells or cell organelles by rupture of their outer membranes. **3** *(in medicine)* the gradual diminution in the severity of the symptoms of a disease; remission.

+lysis *comb. form* denoting breaking down, decomposition, disintegration, or dissolution. The first element of the word may indicate: (1) the agent, e.g. electrolysis, hydrogenolysis, biolysis; (2) the substance or object affected, e.g. glycolysis, lipolysis; or (3) some other characteristic, e.g. autolysis, catalysis, heterolysis, homolysis. **—+lytic** *adj.*

lyso+ *or (before a vowel)* **lys+ 1** *comb. form* indicating a dissolving or loosening; denoting lysis or the products of lysis. **2** *prefix* (to the name of a phospholipid) denoting removal of one of its two acyl groups; a locant may be used to designate the site of (hydro)lysis, e.g. 2-lyso designates deacylation at position 2. The term originated from the fact that such compounds are hemolytic, but it is now used to indicate a limited deacylation.

lysochrome any substance that will dissolve in lipids and colour them.

lysogen 1 any **lysogenic bacterium**. **2** any antigen that stimulates **lysin** production.

lysogenesis 1 *an alternative term for* **lysogeny**. 2 the production of a lysin or lysis.

lysogenic 1 pertaining to, or capable of producing or undergoing **lysis** (def. 1). 2 of, or relating to **lysogeny**. —**lysogenicity** *n.*

lysogenic bacterium any bacterium carrying a temperate bacteriophage as a **prophage** integrated into the bacterial genome. It has the potential to produce and release infective bacteriophages as a stable, heritable trait, which may become activated spontaneously or in response to certain stimuli. Moreover, it is immune to lytic infection by the same or closely related phages.

lysogenic conversion *see* **bacteriophage conversion**.

lysogenic virus any virus capable of becoming a **prophage**.

lysogenize *or* **lysogenise** to convert a nonlysogenic bacterial strain into a lysogenic strain by infection with a temperate bacteriophage, with resultant incorporation of the phage into the bacterial genome. —**lysogenization** *or* **lysogenisation** *n.*

lysogeny *or* **lysogenesis** the state created in a bacterial cell when the prophage of a temperate bacteriophage is incorporated into the bacterial genome as a stable, heritable character. Such a cell can be activated to produce and release mature phage, with accompanying cell lysis. *See also* **lysogenic bacterium**.

Lys(5-OH) *symbol for* a residue of the α-amino acid 5-hydroxy-L-lysine (less-preferred alternative to Hyl or 5Hyl).

Lysol *the proprietary name for* a disinfectant consisting of a mixture of *o*-, *m*-, and *p*-cresols solubilized with an excess of a potassium soap.

lysolecithin *a former name for* **lysophosphatidylcholine**.

lysolecithin acyltransferase *see* **1-acylglycerophosphocholine O-acyltransferase**.

lysophosphatidic acid any **phosphatidic acid** deacylated at positions 1 or 2.

lysophosphatidyl any **phosphatidyl** group deacylated at positions 1 or 2.

lysophosphatidylcholine *or (formerly)* **lysolecithin** any **phosphatidylcholine** (i.e. lecithin) deacylated at positions 1 or 2.

lysophospholipid any **phospholipid** deacylated at positions 1 or 2.

lysoplasmenic acid any derivative of *sn*-glycero-3-phosphate that has an *O*-(1-alkenyl) residue on carbon-1, the hydroxyl group in position 2 being unsubstituted.

lysoplasmenyl any **plasmenyl** group in which the hydroxyl group in position 2 is unsubstituted.

lysosomal carboxypeptidase B *see* **cysteine-type carboxypeptidase**.

lysosomal carboxypeptidase C *see* **lysine pro-X carboxypeptidase**.

lysosomal Pro-X carboxypeptidase EC 3.4.16.2; *other names*: proline carboxypeptidase; angiotensinase C; lysosomal carboxypeptidase C; an enzyme that catalyses the cleavage of a Pro-|-Xaa bond to release a C-terminal amino acid.

lysosomal storage disease any of a group of hereditary diseases, with widely varying manifestations, in which there is deficiency of a single lysosomal enzyme associated with abnormal deposits (of substrate) within membrane-bound vesicles. The group is subdivided into the following classes: type II **glycogen disease**, **mucopolysaccharidoses**, sphingolipidoses, **mucolipidoses**, and a few others.

lysosome any of a group of related cytoplasmic, membrane-bound organelles that are found in most animal cells and that contain a variety of hydrolases, most of which have their maximal activities in the pH range 5–6. The contained enzymes display latency if properly isolated. About 40 different lysosomal hydrolases are known and lysosomes have a great variety of morphologies and functions. —**lysosomal** *adj.*

lysostaphin EC 3.5.1.–; an enzyme that hydrolyses polyglycine links in peptidoglycans. Zinc is a cofactor. Its physiological role is likely to be in the remodelling of the bacterial sacculus during growth. The C terminus has some similarity to **autolysin**.

lysozyme EC 3.2.1.17; *systematic name*: peptidoglycan *N*-acetylmuramoylhydrolase; *other name*: muramidase. An enzyme that hydrolyses β-1,4-linkages between *N*-acetylmuramic acid and 2-acetamido-2-deoxy-D-glucose residues in peptidoglycan heteropolymers (mucopolysaccharide or muropeptide) of prokaryote cell walls. It occurs in tears, other exocrine secretions, and in very large amounts in the white of eggs of birds. The antibacterial action of lysozyme depends on the cleavage of the β(1–>4)glycosidic linkage between alternating units of *N*-acetylmuramic acid and *N*-acetylglucosamine that form long-chain mucopolysaccharides in the cell walls of bacteria such as *Micrococcus luteus*. There are a number of types of lysozyme, designated A–G. Lysozyme was the first enzyme whose 3-D structure was determined.

[Lys^8]vasopressin *abbr. for* [8-lysine]vasopressin.

lysyl the acyl group, $H_2N–[CH_2]_4–CH(NH_2)–CO–$, derived from **lysine**.

lysylbradykinin *or* **Lys-bradykinin** *an alternative name for* kallidin; *see* **bradykinin**.

lysyl endopeptidase EC 3.4.21.50; *other names*: *Achromobacter* proteinase I; lysyl bond specific proteinase. An extracellular bacterial serine proteinase that preferentially cleaves at Lys-|-Xaa, including Lys-|-Pro.

lysyl oxidase EC 1.4.3.13; *recommended name*: protein-lysine 6-oxidase; *systematic name*: protein-L-lysine:oxygen 6-oxidoreductase (deaminating). A quinoprotein enzyme that catalyses a reaction between peptidyl-L-lysyl-peptide, H_2O and dioxygen to form peptidyl-allysyl-peptide, NH_3, and H_2O_2. It contains lysine tyrosylquinone as a cofactor. *See also* **allysine**.

+lyte *comb. form* indicating a substance that can be decomposed, broken down, or lysed.

lytic 1 of, pertaining to, or resulting from **lysis**. 2 of, or pertaining to a **lysin**.

+lytic *see* **+lysis**.

lyticase *a jargon term for* a combination of enzymes, with minimal amounts of nucleases, that displays two major activities: β-1,3-glucanase and a highly specific alkaline protease. It is prepared from *Oerskovia xanthineolytica* and is useful in removing cell walls from yeasts and fungi, causing extremely rapid cell lysis.

lytic cycle the sequence of events occurring when a sensitive bacterium is infected by a virulent bacteriophage. The phage diverts the metabolism of the cell to the exclusive production of progeny phage, resulting in the lysis of the host cell with liberation of phage.

α-lytic endopeptidase EC 3.4.21.12; a bacterial serine proteinase, a homologue of chymotrypsin, that hydrolyses proteins, especially at bonds adjacent to L-Ala and L-Val residues in bacterial cell walls, elastin, and other proteins.

lytic virus any virus including bacteriophages whose multiplication in a host cell leads to lysis of that cell.

Lyx *symbol for* a residue (or sometimes a molecule) of the aldopentose **lyxose**.

***lyxo*+** *prefix (in chemical nomenclature)* indicating a particular configuration of a set of three (usually) contiguous >CHOH groups, as in the acyclic forms of D- or L-lyxose. *See* **monosaccharide**.

lyxose *symbol*: Lyx; *a trivial name for* the aldopentose, *lyxo*-pentose; the C-2 epimer of **xylose**, rare in nature.

Mm

m *symbol for* **1** metre. **2** milli+ (SI prefix denoting 10^{-3} times).

m+ *prefix (in peptide hormone nomenclature)* denoting mouse, murine; derived, or as if derived, from a mouse.

m_r *symbol for* relative electrophoretic mobility.

m *symbol for* **1** mass; the various associated terms are distinguished by subscripts: m_e, *symbol for* electron rest mass; m_n, *symbol for* neutron rest mass; m_p, *symbol for* proton rest mass; m_u, *symbol for* atomic mass constant. **2** molality (alternative to *b*). **3** (bold italic) magnetic moment.

m- *prefix (in chemical nomenclature)* denoting ***meta-***. *Compare* ***o-***, ***p-***.

M *symbol for* **1** mega+ (SI prefix denoting 10^6 times). **2** a residue of the α-amino acid L-methionine (alternative to Met). **3** a residue of an incompletely specified base in a nucleic-acid sequence that may be either adenine or cytosine. **4** mesomeric effect. **5** a metal (in chemical formulae). **6** molar (concentration), i.e. moles per litre (alternative to M or *M*; mol dm^{-3} is recommended). **6** 6-mercaptopurine ribonucleoside, 6-thioinosine.

M *symbol for* molar (concentration), i.e. moles per litre (alternative to M or *M*; mol dm^{-3} is the recommended form).

α_2-M *abbr. for* α_2-macroglobulin.

M *symbol for* **1** mass, especially molar mass; related terms are designated by subscripts: M_m, *symbol for* mass-average molar mass (*see* **average molar mass**); M_n, *symbol for* number-average molar mass (*see* **average molar mass**); M_o, *symbol for* mean relative residue mass; M_r, *symbol for* relative molecular mass; M_w, symbol for weight-average molar mass; M_z, *symbol for* Z-average molar mass (*see* **average molar mass**). **2** molar (concentration), i.e. moles per litre (alternative to M or M; no longer recommended; use mol dm^{-3}). **3** (*or* M_v) luminous exitance. **4** (*or* M_e) radiant exitance. **5** (bold italic) magnetization. **6** (bold italic) moment of a force.

M. *abbr. for* the **modification enzyme** associated with a type 2 **restriction endonuclease**. For example, M.*Hin*dIII is the enzyme associated with ***Hin*dIII**.

M9 a solution of inorganic salts used as the basis of minimal growth media for bacteria.

MAA *abbr. for* macroaggregated (human serum) albumin.

Mab *abbr. for* monoclonal antibody.

Mabthera *a proprietary name for* **Rituximab.**

MAC *abbr. for* **1** membrane attack complex. **MAC 1** is a cell-surface glycoprotein of monocytes, macrophages, and granulocytes that is implicated in adhesive interactions of these cells and in mediating the uptake of complement-coated particles. It probably recognizes the RGD peptide in **complement** component C3b. It is a heterodimer of α_M and β_2 chains (*see* **integrin**). **2** mammalian artificial chromosome.

machine address a binary number unique to a computer (more exactly its network hardware) that is used by a **DNS** (domain name server). It should be transparent to the average end-user. The number is usually represented as a colon-delimited hexadecimal, for example 00:01:02:1a:45:66.

machine language *see* **programming language**.

MACIF *abbr. for* membrane attack complex inhibition factor.

Mac-IP *abbr. for* Mac-inhibitory protein (i.e. **CD59**).

mackerel any marine fish of the subfamily Scombroidei. These fish are of importance as food fish, and their flesh is rich in oils with a relatively high content of *n*-3 **fatty acids**; typical composition (major fatty acids, expressed as percentage of total fatty acids): 14:0, 8%; 16:0, 16%; 18:0, 2%; 16:1 (*n*-7) 8%; 18:1 (*n*-9), 8%; 18:1 (*n*-7), 4%; 18:4 (*n*-3), 2%; 20:1 (*n*-9), 11%; 20:5 (*n*-3), 8%; 22:1 (*n*-11), 13%; 22:6 (*n*-3), 8%.

maconha *see* **cannabis**.

macro+ *or (before a vowel)* **macr+** *comb. form* **1** denoting large, long, or great in size or duration; large-scale. **2** denoting larger than normal, overdeveloped. *Compare* **micro+**.

macroaggregate any macromolecular aggregate large enough to be visible to the unassisted eye.

macrocycle any **macrocyclic** compound.

macrocyclic 1 *(in chemistry)* describing any compound containing a ring structure consisting of a large number (usually 15 or more) atoms. **2** *(in biology)* having a long life cycle.

macrocytic anemia anemia in which the circulating erythrocytes are larger than normal. It is often due to deficiency of vitamin B_{12} (cobalamin) or folic acid.

macroglobulin any plasma globulin of >400 kDa. Macroglobulins include **immunoglobulin M**, **α_2-macroglobulin** and many lipoproteins.

α_2-macroglobulin *abbr*.: α_2-M; a glycoprotein found in vertebrate plasma that strongly inhibits proteases of all classes. In humans, it constitutes about one third of the α_2-globulins; its synthesis is enhanced in hypoalbuminemia, when it constitutes a major proportion of the increased α_2-globulin band on electrophoresis strips. Human α_2-M is a 726 kDa molecule comprising two pairs of disulfide-linked, identical 185 kDa subunits, which also contain heterodetic peptide rings containing reactive thiol ester linkages, each formed between the γ-carboxyl group of a glutamic residue and the thiol group of a cysteine residue in the same peptide chain. It can inhibit all four classes of **proteinase** by a mechanism involving a **bait region**. This contains specific sites, cleavage of which induces a conformational change that results in trapping of the protease: following cleavage in the bait region, a thiol-ester bond is hydrolysed, and mediates the covalent binding of the protein to the protease; subsequently, ε-amino groups of the protease react with the thiol-ester linkages in the inhibitor to form stable amide links. The entrapped protease is then able to act on substrates of low molar mass only.

macroglobulinemia *or (esp. Brit.)* **macroglobulinaemia** a condition in humans in which there is an increase in the concentration of macroglobulins, especially immunoglobulin M, in the blood. It is often associated with lymphocyte tumours.

macro histone 2A *abbr*.: macro H2Aa; the counterpart of histone H2A that replaces this in certain nucleosomes, with an implied role in nucleosome positioning.

macroion an ion of a macromolecule, especially one that does not pass through a dialysis membrane.

macrolide any antibiotic produced by *Streptomyces* spp. that contains a large lactone ring (*see* **+olide**) with few or no double bonds and no nitrogen atoms, linked to one or more sugar moieties. The macrolides include the carbomycins, the **erythromycins**, oleandomycin, **oligomycins**, and the spiramycins. They are active mainly against Gram-positive bacteria and they inhibit the early stages of protein synthesis.

macroligand any macromolecular ligand.

macrometabolite any metabolite present in a system in reasonably high concentration, especially as opposed to a trace metabolite, i.e. one present in extremely small concentrations.

macromolecule any molecule composed of a very large number of atoms, operationally defined as any molecule of mass greater than about 10 kDa (and ranging up to 10^2 MDa or more) that is incapable of passing through the pores of dialysis tubing as generally used. The term includes nucleic acids and most polysaccharides and proteins. *Compare* **micromolecule**. **—macromolecular** *adj.*

macronutrient any element that is required by living organisms in relatively large quantities for normal growth. *Compare* **micronutrient**.

macrophage any cell of the **mononuclear phagocyte system** that is characterized by its ability to phagocytose foreign particulate and colloidal material. Macrophages occur in connective tissue, liver (Kupffer cells), lung, spleen, lymph nodes, and other tissues. They contain prominent lysosomes, stain with vital dyes, and play an important part in nonspecific immune reactions.

macrophage-activating factor *abbr*.: MAF; *see* **lymphokine**.

macrophage-colony stimulating factor *see* **colony stimulating factor**.

macrophage inflammatory protein *abbr*.: MIP; a cytokine produced by B and T cells, monocytes, mast cells, and fibroblasts. MIP 1α is a chemoattractant for monocytes, T cells, and eosinophils; it also inhibits hematopoietic stem cell production. MIP 1β is a chemoattractant for monocytes and T cells and is an adhesion molecule, binding to β_1 (**VLA** family) **integrins.**

macrophage migration enhancement factor *see* **lymphokine**.

macrophage migration inhibitory factor *abbr.*: MIF; *other name*: delayed early response protein 6; a **lymphokine** that is released by primed lymphocytes on incubation with the priming antigen. It inhibits the migration of macrophages out of macrophage-rich tissue such as spleen, and is probably a mediator of macrophage participation in inflammation.

macrophage scavenger receptor **1** a glycoprotein membrane receptor of macrophages and sinusoidal endothelial cells that binds and mediates uptake of oxidized low-density lipoproteins (LDL). It is implicated in deposition of cholesterol into arterial walls during atherogenesis. **2** a membrane receptor of hepatocytes and steroid hormone-producing cells that binds high-density lipoproteins (HDL), selectively removes cholesterol, and mediates its uptake.

macrophage system *see* **mononuclear phagocyte system**.

macropipette (*sometimes*) a pipette of similar construction to a standard plunger-type micropipette but of capacity in the range 0.25–5 mL.

macropore any pore (in a gel or porous solid) whose width is greater than about 50 nm. *Compare* **mesopore**, **micropore**. **—macroporous** *adj.*

macroreticular describing a three-dimensional polymer with a very open structure, the cross links being widely spaced.

macroscopic **1** of a size that is visible to the unaided eye. *Compare* **microscopic** (def. 1). **2** concerned with large units. *Compare* **microscopic** (def. 2). **3** relating to the behaviour of atoms or molecules in bulk. *Compare* **microscopic** (def. 3). **—macroscopically** *adv.*

macroscopic equilibrium constant any constant describing the overall equilibrium between two chemical entities that may be interconverted through two or more alternative intermediates. *Compare* **microscopic equilibrium constant**.

macrosolute *an operational term describing* any solute of a size larger than will pass through a membrane of a specified pore size or permeability limit.

macrotetrolide *or* **macrotetralide** any antibiotic that contains a 32-membered ring built up of four hydroxy-acid residues and containing four ether and four ester bonds; the group includes **nonactin** and related antibiotics. Some similar compounds have an open-chain structure, e.g. **monensin** and **nigericin**.

macula adherens *an alternative term for* **desmosome**.

MAD **1** a basic helix-loop-helix transcription factor capable of forming dimers with MYC and MAX. **2** *abbr. for* **multi-wavelength anomalous dispersion**.

MAD2 a protein in yeast that is an essential component of the spindle checkpoint during mitosis and determines the fidelity of chromosome distribution. Mutation leads to a large increase in the rate of chromosome misaggregation during meiosis.

MadCAM *abbr. for* mucosal addressin cell adhesion molecule; MadCAM 1, M_r 58–66 kDa, is a member of the immunoglobulin superfamily of **adhesion molecules**. It is constitutively expressed on endothelial cells of post-capillary venules. It mediates lymphocyte homing to mucosal lymphoid organs and lamina propria venules, and binds **L-selectin** and **integrin** $\alpha_4\beta_7$.

mad cow disease *an informal name for* **bovine spongiform encephalopathy**.

madder the ground root of *Rubia tinctoria*, used as a plant dyestuff; the principal component is **ruberythric acid**.

MADS box a highly conserved amino acid sequence (≈56 amino acids) present in the floral 'homeotic' transcription factors APETALA1, APETALA3, PISTILLATA, and AGAMOUS of *Arabidopsis thaliana* and in many other proteins expressed in flowers of other plant species. *See* **ABC model.**

MAF *abbr. for* macrophage-activating factor; *see* **lymphokine**.

magainin any antibiotic peptide from *Xenopus* skin whose pore-forming activity (*see* **PFP**) results in the permeabilization of bacterial membranes. Magainins have a wide spectrum of action against bacteria, protozoa, and fungi. Magainin I has the sequence

GIGKFLHSAGKFGKAFVGEIMKS;

magainin II is (Lys^{10},Asn^{22})-magainin I. An analogue with greater antibiotic potency is ($Ala^{8,13,18}$)-magainin II amide. Magainins are classified in the TC system under number 1.C.16. *Compare* **dermaseptin**.

MAGE *see* **visualization software**.

magic spot I *see* **magic spot (compound)**, **ppGpp**.

magic spot II *see* **magic spot (compound)**, **pppGpp**.

magic spot (compound) *abbr.*: MS; either of the guanosine polyphosphates produced when stringent strains of *Escherichia coli* are starved of an amino acid required for protein synthesis. MS I is guanosine 5′-diphosphate 2′-(or 3′)-diphosphate (*symbol*: ppGpp); MS II is guanosine 5′-triphosphate 2′-(or 3′)-diphosphate (*symbol*: pppGpp).

magnesium *symbol*: Mg; a metallic element – an alkaline earth metal – of group 2 of the IUPAC **periodic table**; atomic number 12; relative atomic mass 24.305. It occurs naturally only in the combined state and is a mixture of stable nuclides of mass 24, 25, and 26. Magnesium is one of the most abundant elements of the Earth's crust (2.1%) and an essential component of all living material. It forms a divalent cation, Mg^{2+}, which is a component of chlorophyll, occurs in bone, and is an essential cofactor for many enzymes, including the majority of enzymes utilizing ATP. It is a major biological cation, the fourth most abundant cation in the human, much of it being in the skeleton; the range in normal human plasma is 0.8–1.2 mmol L^{-1}. An excretion mechanism in the kidney is partly regulated by parathyroid hormone. *See also* **magnesium-28**.

magnesium-28 the artificial radioactive nuclide of magnesium, $^{28}_{12}Mg$, of half-life 21.2 h. It emits a moderate-energy beta particle (i.e. electron) (0.46 MeV max.) and gamma radiation of various energies (1.35, 0.95, 0.40, and 0031 MeV).

magnesium porphyrin *a general term for* **chlorophyll**.

magnet any body that can produce an appreciable **magnetic field** external to itself. Magnets may be either permanent or temporary. **—magnetic** *adj.*

magnetic beads microscopic synthetic polymer beads incorporating a magnetite core and chemically modified to enable the covalent attachment of proteins such as antibodies. Beads coated with streptavidin will bind proteins or DNA labelled with biotin. Such beads can be concentrated from suspension by exposing them to a magnetic field thereby providing an alternative to centrifugation.

magnetic circular dichroism spectroscopy measurement of circular dichroism of a coloured material which is induced by a magnetic field applied parallel to the direction of the measuring light beam. Even achiral materials exhibit MCD (the Faraday effect). Variable-temperature MCD is used for identifying and assigning electronic transitions originating from paramagnetic *chromophores*.

magnetic constant *symbol*: μ_0; *an alternative name for* **permeability of vacuum**.

magnetic dipole moment *symbol*: $\boldsymbol{m}$ or $\boldsymbol{\mu}$ (italic bold); a vector quantity indicating the strength of a magnet: the product of a magnet's dipole moment and the ambient **magnetic flux density** gives the torque on the magnet. The SI unit is the A m^2 (ampere square metre = joule per tesla (J T^{-1})).

magnetic field **1** a field of force existing in the neighbourhood of either a permanent magnet or a circuit carrying an electric current. Another magnet will experience a couple when placed in a magnetic field. **2** *an alternative name for* **magnetic field strength**.

magnetic field strength *or* **magnetic field** *or (formerly)* **magnetic intensity** *symbol*: $\boldsymbol{H}$ (italic bold); a vector quantity, the magnetizing force at any point in a medium. It is measured by a couple that would act on a small magnet of unit moment placed at that point with its axis at right angles to the direction of the magnetic field. It is the **magnetic flux density**, $\boldsymbol{B}$, divided by the **permeability**, μ; i.e. $\boldsymbol{H} = \boldsymbol{B}/\mu$. The SI derived unit $\boldsymbol{H}$ = A m^{-1}.

magnetic flux *symbol*: Φ; a measure of the total strength of a magnetic field, defined as the scalar product of the magnetic flux density and the area. The SI derived unit is the **weber**.

magnetic flux density *or* **magnetic induction** *symbol*: $\boldsymbol{B}$ (italic bold); a pseudovector quantity, the **magnetic flux** passing through unit area of a magnetic field orthogonal to the magnetic force. The SI derived unit is the **tesla**.

magnetic force the force exerted by a magnetic field on a magnetic pole or a moving electric charge. It may be either attractive or repulsive.

magnetic immunoassay *abbr*.: MAIA; a variant of **radioimmunoassay** in which the antibody is bound to a particulate, inert, magnetic support material – e.g. cellulose containing embedded grains of iron oxide, Fe_3O_4 – and separation of antigen–antibody complexes from free antigen is effected with the aid of a powerful magnet.

magnetic induction *an alternative term for* **magnetic flux density**.

magnetic intensity *a former name for* **magnetic field strength**.

magnetic lens *an alternative name for* a magnetic **electron lens**.

magnetic moment 1 *symbol*: μ; a property of a charged particle arising from its spin; $\mu = e\boldsymbol{L}/2mc$, where c is the velocity of light, $\boldsymbol{L}$ is the angular momentum of the particle, e is its charge, and m is its mass. The SI unit is joule per tesla. The **electron magnetic moment** (*symbol*: μ_e) is equal to $9.284\ 7701 \times 10^{-24}$ J T^{-1}. **The proton magnetic moment** (*symbol*: μ_p) is equal to $1.410\ 607\ 61 \times 10^{-26}$ J T^{-1}. **2** *an alternative name for* **magnetic dipole moment**.

magnetic permeability *see* **permeability**, **permeability of vacuum**.

magnetic pole either of the two regions of a magnet into which the lines of force of the magnetic field converge or from which they diverge. They are designated north (or north-seeking) and south (or south-seeking) according to whether they are attracted to the Earth's north or south pole.

magnetic resonance *see* **electron-spin resonance spectroscopy**, **nuclear magnetic resonance**, **electron paramagnetic resonance spectroscopy**.

magnetic resonance imaging *abbr*.: MRI; an imaging technique that uses **nuclear magnetic resonance** (NMR) to investigate the state of tissues in the intact body; it is so-called to avoid the use of the term 'nuclear' in the treatment of patients. It has the advantage that it is non-invasive. A magnet large enough to surround a part of the body is used in conjunction with computer analysis to provide an image resulting from the NMR signals. The technique can distinguish extracellular water from that inside cells on the basis of protein spin relaxation rates; this distinction is used to reveal certain types of tissue damage.

magnetic shielding 1 protection from the effects of an external magnetic field. **2** (in **nuclear magnetic resonance spectroscopy**) the reduction of the applied magnetic field at an atomic nucleus (as compared with that applied to the whole sample) brought about by the electron cloud of the molecule.

magnetic stirrer any apparatus for stirring a liquid in which a follower – usually a small bar magnet coated in glass or plastic – may be caused to oscillate or rotate within the liquid under the influence of a more powerful magnet outside the container. Motion of the external magnet is controlled by a variable-speed electric motor. The term is sometimes applied specifically to the follower.

magnetic susceptibility *symbol*: X *or (sometimes)* X_m *or* K; the ratio of the magnetization, $\boldsymbol{M}$, produced in a substance to the magnetic field strength, $\boldsymbol{H}$, applied to it, i.e.

$$X = \boldsymbol{M}/\boldsymbol{H} = \mu_r - 1,$$

where μ_r is the relative permeability of a vacuum. Paramagnetic materials have positive magnetic susceptibilities, diamagnetic materials have negative magnetic susceptibilities. (Note: the symbol μ_m is reserved for molar magnetic susceptibility.)

magnetism 1 the property of producing, or being affected by, magnetic flux. **2** the branch of physics concerned with magnets and magnetic phenomena.

magnetite *or* **magnetic iron oxide** *or* **black iron oxide** ferrosoferric oxide; iron(II)–diiron(III) oxide; Fe_3O_4; a strongly magnetic black mineral form of iron oxide.

magnetization *or* **magnetisation 1** the act or process of magnetizing. **2** *symbol*: $\boldsymbol{M}$ (italic bold); the magnetic moment per unit volume of a magnetized body; i.e. the difference between the ratio of the **magnetic flux** to the **permeability of vacuum** and the **magnetic field strength**. The SI unit is the ampere per metre.

magnetization-transfer nuclear magnetic resonance spectroscopy a procedure in **nuclear magnetic resonance spectroscopy** in which one of the resonances is saturated by a strong radiofrequency field, and the changes in the other resonances are observed. It is useful in measuring the rates of chemical exchange processes.

magnetize *or* **magnetise** to induce a magnetic flux density in (something); to cause (something) to exhibit **magnetism** (def. 1).

magnetogyric ratio *see* **gyromagnetic ratio**.

magneton a unit of magnetic moment. The **Bohr magneton** (*symbol*: μ_B) refers to an electron of mass m_e; the **nuclear magneton** (*symbol*: μ_N) refers to a proton of mass m_p. They are related by the equation: $\mu_N = (m_e/m_p)\mu_B$.

magnetophoresis the movement of magnetizable particles through a fluid under the action of a magnetic field. It is useful for separating of dispersed cells to which ferromagnetic microspheres have been conjugated. **—magnetophoretic** *adj.*

magnetotactic referring to bacterial cells that align along a magnetic field. They contain crystals of magnetite.

magnification *(in microscopy)* the apparent linear enlargement of an object when viewed through a lens, system of lenses (as in a microscope, telescope, etc.), or other instrument. It is given by the ratio of the apparent diameter of the object, as seen using the lens, to its real diameter, as seen unaided.

Magnogel *a proprietary name for* a bead-form support material useful in immunosorption and related procedures. It is similar to **Ultrogel** but contains embedded particles of iron oxide, Fe_3O_4, that enable the beads to be drawn to and held on the walls of the container by magnetism.

MAIA *abbr. for* magnetic immunoassay.

Maillard reaction a nonenzymic reaction in which a reducing sugar combines at its anomeric carbon atom with an amino group of an amino acid, peptide, or protein to form first a Schiff base and then, by an **Amadori rearrangement**, the corresponding ketoamine. It is the first of a series of reactions that may occur during the processing and/or storage of food, resulting in a loss of nutritive value and the formation of a brown coloration; hence it is also known as the **browning reaction**. It may also be the reaction leading to the formation of hemoglobin A_{1c} in the erythrocyte. [After Louis Camille Maillard (1878–1936).]

main protease the protease that cleaves the polyprotein encoded in the RNA genome of coronaviruses. The human virus's main protease (305 amino acids) contains two six-stranded beta barrels and a cluster of five alpha helices. It cleaves on the carboxyl side of glutamine at about a dozen sites that contain Leu–Gln–Ala/Ser/Gly sequences.

major facilitator superfamily *abbr.* MFS, one of the two largest families of membrane transporters (the other being the ABC transporters). Transporters of this family are present ubiquitously in bacteria, archaea, and eukarya. They transport a wide range of metabolites and drugs, including sugars, amino acids, nucleosides, and a large variety of anions and cations. All permeases of the MFS possess 12–14 putative transmembrane α-helical regions, and exhibit a well-conserved motif present between transmembrane regions 2 and 3.

major groove the larger and deeper of the two spiral grooves on the surface of a double-helical b-DNA molecule. *Compare* **minor groove**.

major histocompatibility complex *abbr*.: MHC; a complex of genetic loci occurring in higher vertebrates that encodes a family of cellular antigens, known in mice as **histocompatibility-2 antigens** (*abbr*.: H-2 antigens; *see* **histocompatibility antigen**) and in humans as human leukocyte-associated antigens (*abbr*.: HLA antigens; *see* **HLA histocompatibility system**). The MHC antigens are cell-surface glycoproteins and may be divided into two classes, designated I and II. In transplantation reactions, cytotoxic T lymphocytes respond mainly against foreign MHC glycoproteins of class I together with antigen, while the response against class II and antigen is mainly by helper T lymphocytes.

Class I MHC antigens (*or* transplantation antigens) are on the surface of most nucleated somatic cells and enable the immune system to distinguish self from foreign cells. They are encoded by three separate loci (H-2K, H-2D, and H-2L in mice; HLA-A, HLA-B, and HLA-C in humans). The antigenic activity resides in a transmembrane polypeptide chain, the α subunit, of ≈45 kDa (roughly 345 amino acids), which has a short hydrophilic C-terminal segment inside the cell and a large glycosylated N-terminal segment. The latter is folded into three separate domains (two of which contain an intrachain disulfide bond) and exposed to the cell exterior, where it is noncovalently linked with the β subunit (of 11.5 kDa and also called β_2 microglobulin), which is homologous with a single Ig-like domain (*see* **immunoglobulin fold**). In humans, these proteins are also referred to as **HLA class I**.

Class II MHC antigens are found on the surface of most B lymphocytes, some T lymphocytes, and some macrophages and macrophage-like cells. They are encoded by murine I-region (*abbr*.: Ir) genes and human HLA-D genes, and contain a ≈33 kDa α chain and a 28 kDa β chain; the C-terminal regions of both subunits have transmembrane and intracellular domains. Celiac disease is due to an allelic variant in one class-II gene.

majority-rule consensus tree (*in phylogenetics*) a tree in which groups of taxa that appear in 50% or more of the component trees are shown. *Compare* **consensus tree**.

major tranquillizer *a term, now deprecated, for* any drug used to treat major psychosis, e.g. schizophrenia or mania; the term **neuroleptic** is now recommended.

MAK *abbr. for* methylated albumin-kieselguhr; a substance used as a medium for chromatography.

Makefile a file read by the UNIX utility make. It includes instructions for the computer and is used largely, but not exclusively, for compiling programs from source code. The advantage of make is that instructions on files that have not been altered since the last use of make are not repeated.

Mal **1** (when linked to one other group) *symbol for* the univalent maleyl group. **2** (when linked to two other groups) *symbol for* the bivalent maleoyl group.

malate **1** *a trivial name for* hydroxysuccinate; hydroxybutanedioate; $^{-}OOC–CH_2–CH(OH)–COO^{-}$; the dianion of malic acid, a chiral hydroxydicarboxylic acid. The (+)-enantiomer, (*S*)-malate (also designated L-malate), is an important intermediate in metabolism as a component of both the tricarboxylic-acid cycle and the glyoxylate cycle. **2** any mixture of free malic acid and its mono- and dianions. **3** any salt or ester of malic acid.



(*S*)-malate

malate–aspartate cycle *or* **malate cycle** an intracellular metabolic cycle, also known as the malate–aspartate shuttle or malate shuttle, that can transfer reducing equivalents from the cytosol to the mitochondria in liver and other tissues. Oxaloacetate formed inside the mitochondria is there converted by a transaminase into aspartate, which passes through the mitochondrial membrane on a specific carrier; a similar transaminase in the cytosol converts this aspartate back into oxaloacetate, which then reacts with cytosolic NADH, in a reaction catalysed by cytosolic **malate dehydrogenase**, to form (*S*)-malate and NAD^+. The malate thereupon passes back into the mitochondria, where it is dehydrogenated again to oxaloacetate, with concomitant reduction of mitochondrial NAD^+ to NADH and completion of the cycle.

malate dehydrogenase **1** *abbr*.: MDH *or (in clinical chemistry)* MD; EC 1.1.1.37; *recommended name*: malate dehydrogenase; *systematic name*: (*S*)-malate:NAD^+ oxidoreductase; *other name*: malic dehydrogenase. A widespread enzyme that interconverts malate and oxaloacetate according to the reaction:

$$(S)\text{-malate} + NAD^+ = \text{oxaloacetate} + NADH.$$

In yeast, e.g., there are three isoenzymes: cytosolic, glyoxysomal, and of the mitochondrial matrix. **2** EC 1.1.1.82; *recommended name*: malate dehydrogenase ($NADP^+$); *systematic name*: (*S*)-malate:$NADP^+$ oxidoreductase. A chloroplast enzyme required for both C_3 and C_4 pathways (*see* **reductive pentose phosphate cycle**, **Hatch–Slack pathway**) to allow plants to circumvent the problem of photorespiration. It catalyses the reaction:

$$(S)\text{-malate} + NADP^+ = \text{oxaloacetate} + NADPH.$$

See also **malate dehydrogenase (decarboxylating)**.

malate dehydrogenase (decarboxylating) any enzyme that brings about the oxidation of malate with simultaneous decarboxylation of the product to pyruvate. Such enzymes include: (1) Malate dehydrogenase (oxaloacetate decarboxylating), EC 1.1.1.38; *systematic name*: (*S*)-malate:NAD^+ oxidoreductase (oxaloacetate decarboxylating); *other names*: malic enzyme; pyruvic–malic carboxylase; malate oxidoreductase; it catalyses the reversible reaction:

$$(S)\text{-malate} + NAD^+ = \text{pyruvate} + CO_2 + NADH.$$

(2) Malate dehydrogenase (decarboxylating), EC 1.1.1.39; *systematic name*: (*S*)-malate:NAD^+ oxidoreductase (decarboxylating); *other names*: malic enzyme; pyruvic–malic carboxylase; it catalyses a reaction between (*S*)-malate and NAD^+ to form pyruvate, CO_2, and NADH. (3) Malate dehydrogenase (oxaloacetate decarboxylating) ($NADP^+$), EC 1.1.1.40; *systematic name*: (*S*)-malate:$NADP^+$ oxidoreductase (oxaloacetate decarboxylating); *other names*: malic enzyme; pyruvic–malic carboxylase; it catalyses a reaction between (*S*)-malate and $NADP^+$ to form pyruvate, CO_2, and NADPH. It is important in generating NADPH in the cytosol of mammals. Thus types 1 and 2 utilize NAD^+, while only types 1 and 3 decarboxylate added oxaloacetate, which leads to three activities being distinguished. (4) D-Malate dehydrogenase (decarboxylating), EC 1.1.1.83; *systematic name*: (*R*)-malate:NAD^+ oxidoreductase (decarboxylating); it catalyses a reaction between (*R*)-malate and NAD^+ to form pyruvate, CO_2, and NADH.

malate synthase EC 4.1.3.2; *systematic name*: L-malate glyoxylate-lyase (CoA-acetylating); *other names*: malate synthetase; malate condensing enzyme; glyoxylate transacetylase. An enzyme that catalyses the formation of L-malate and CoA from acetyl-CoA, H_2O, and glyoxylate. This is the second step in the glyoxylate bypass, an alternative to the complete tricarboxylic-acid cycle (in bacteria and plants).

MALDI *abbr. for* matrix-assisted laser desorption/ionization; *see* **tandem mass spectrometry**.

maleate **1** *the trivial name for cis*-1,2-ethylenedicarboxylate; (*Z*)-butenedioate; the dianion of maleic acid, the diastereoisomer of fumarate. **2** any mixture of maleic acid and its mono- and dianions. **3** any salt or ester of maleic acid.



maleoyl *symbol*: Mal; the bivalent *cis*-acyl group, –CO–CH=CH–CO–, derived from maleic acid.

maleyl *symbol*: Mal; the univalent *cis*-acyl group, HOOC–CH=CH–CO–, derived from maleic acid.

maleylation the introduction of one or more **maleyl** groups into a substance by acylation, e.g. with maleic anhydride. Maleylation of a protein with maleic anhydride is used to acylate its free lysine (and other) amino groups in order to change their charge at neutral pH from positive to negative and to render the adjacent peptide bonds resistant to hydrolysis by trypsin; it can also lead to disaggregation of a multimeric protein. The reaction occurs at pH 8.5 (usually at 2°C) and the maleyl groups can be removed at pH 3.5 (usually at 60°C). Maleylation of thiol groups may also occur. *Compare* **citraconylation**, **succinylation**. **—maleylate** *vb.*

malformin A a cyclic pentapeptide from *Aspergillus niger* that causes curvature and malformations of various plants. The structure contains D-enantiomers of cysteine and leucine.



malic enzyme *or* **pyruvic–malic carboxylase** *a trivial name applied to* any of three enzymes, found in most organisms, that catalyse the oxidative decarboxylation of (*S*)-malate with concomitant production of pyruvate. *See* **malate dehydrogenase (decarboxylating)**.

malignant *(in pathology)* **1** (of a tumour) invasive, spreading, resistant to therapy. **2** (of a disorder) becoming progressively more serious if not treated.

malignant hyperthermia a genetic disorder of humans and pigs that manifests as a fulminant episode of muscle rigidity, high fever, and acidosis, which is frequently fatal. In humans there is an autosomal dominant predisposition, with general anesthesia (frequently involving halothane inhalation) as the trigger. Most cases are associated with hyperexcitability of the ryanodine receptor. In pigs, the predisposition is autosomal recessive with stress as the trigger, and is associated with a point mutation in the same receptor.

malnutrition any imbalance, usually a deficiency, between the nutrients taken in by an organism and the amounts necessary to maintain that organism's normal development and health.

malonate 1 *the trivial name for* propanedioate; methanedicarboxylate; $^{-}OOC–CH_2–COO^{-}$, the dianion of malonic acid. It is a potent competitive inhibitor of **succinate dehydrogenase**. **2** any mixture of free malonic acid and its mono- and dianions. **3** any salt or ester of malonic acid.

malonate semialdehyde *the recommended trivial name for* malonate semialdehyde; formylethanoate; $OHC–CH_2–COO^{-}$. It is an intermediate in the oxidation of propionyl-CoA to acetyl-CoA in the terminal stages of the beta oxidation of fatty acids with an odd number of carbon atoms in plants.

malondialdehyde a compound produced by oxidation of unsaturated fatty acids. *See* **TBARS**.



malonyl 1 *(in biochemistry)* the univalent acyl group, $HOOC–CH_2–CO–$, derived from malonic acid by loss of one hydroxyl group. **2** *(in chemistry)* the bivalent acyl group, $–CO–CH_2–CO–$, derived from malonic acid by loss of both hydroxyl groups.

malonyl-CoA a key intermediate in fatty-acid biosynthesis, formed by reaction of carbon dioxide with acetyl-CoA, with hydrolysis of ATP to ADP and inorganic phosphate. This is catalysed by **acetyl-CoA carboxylase**; biotin is an essential cofactor. The plant enzyme also carboxylates propanoyl-CoA and butanoyl-CoA.

malonyl-CoA–acyl carrier protein transacylase EC 2.3.1.39; *recommended name*: [acyl-carrier-protein] *S*-malonyltransferase; *systematic name*: malonyl-CoA:[acyl-carrier-protein] *S*-malonyltransferase. An enzyme that catalyses a reaction between malonyl-CoA and ACP to form CoA and malonyl-ACP. It is a component of fatty-acid synthase in bacteria (*see* **fatty-acid synthase complex**).

maloyl the bivalent acyl group, $–OC–CH(OH)–CH_2–CO–$, derived from malic acid by loss of the hydroxyl groups from both of its carboxyl groups.

Malpighian body *or* **Malpighian corpuscle** *or* **renal corpuscle** the part of a nephron comprising a cluster of blood capillaries (i.e. the renal glomerulus) together with the enclosing **Bowman's capsule**. [After Marcello Malpighi (1628–1694), Italian anatomist.]

malt 1 barley or other cereal grain that has been soaked in water, allowed to germinate, and then dried. In this process the starch of the cereal is largely degraded to maltose and other oligosaccharides. **2** to make into or become malt; to make or treat (something) with malt or an extract of malt.

maltase *a trivial name for* α-glucosidase; *see* **glucosidase** (def. 2).

malto+ *comb. form (in chemical nomenclature)* designating an oligosaccharide or polysaccharide (e.g. maltose, maltotriose, maltoheptaose) consisting of D-glucopyranose residues in (α1→4)-linkage (as in maltose).

maltol 3-hydroxy-2-methyl-4-pyrone; a flavour enhancer and modifier with a characteristic smell of candyfloss or burnt bread. Ferric(III) trimaltol is effective in the treatment of iron deficiency anemia.

maltoporin a bacterial outer membrane transmembrane protein, with possibly 16 helices, having two roles in *Escherichia coli*: it transports maltodextrins (including maltose) into the cell, and acts as a receptor for lambda and some other phages.

maltose *or (formerly)* **malt sugar** *the trivial name for* the disaccharide 4-*O*-α-D-glucopyranosyl-D-glucopyranose. It is an intermediate in the enzymic breakdown of glycogen and starch.



maltotriose the trisaccharide Glc(α1-4)Glc(α1-4)Glc; it is formed by the action of α-amylase on starch.

malt sugar *a former name for* **maltose**.

malyl either of the isomeric univalent acyl groups, $HOOC–CH(OH)–CH_2–CO–$ or $HOOC–CH_2–CH(OH)–CO–$, derived from malic acid by loss of a hydroxyl group from one or the other of the carboxyl groups.

MAML *abbr. for* microarray markup language; *see* **markup language**.

mamma (*pl.* **mammae**) a mammary gland. —**mammary** *adj.*

mammal any animal of the Mammalia, a large class of warm-blooded tetrapod vertebrates characterized by the possession of sweat glands in the skin and, generally, an insulating layer of hair. Female mammals characteristically suckle their young at modified sweat glands – mammary glands – that secrete milk. Like birds, mammals possess a four-chambered heart, but their thoracic diaphragm is a uniquely mammalian feature. —**mammalian** *adj.*

mammalian artificial chromosome *abbr.*: MAC; a still hypothetical mammalian counterpart of a **yeast artificial chromosome** (YAC).

mammalian target of rapamycin *see* **mTor**.

mammary gland *or* **mamma** the milk-secreting organ of a mature female mammal. The mammary glands occur in one or more pairs on the ventral surface.

mammotropic *or* **mammotrophic** *an alternative term for* **lactotropic**.

mammotropic hormone *or* **mammotrophic hormone** *an older name for* **prolactin**.

mammotropin *or* **mammotrophin** *an older name for* **prolactin**.

Man *symbol for* a residue (or a molecule) of the aldohexose mannose. In the condensed system of symbolism of sugar residues it signifies specifically a mannose residue with the common configuration and ring size, i.e. D-mannopyranose.

manaoic acid *see* **cyclic fatty acid**.

Mancini technique *see* **single radial immunodiffusion**.

mandelate α-hydroxybenzeneacetate; the anion, $C_6H_5–CH(OH)–COO^{-}$, derived from mandelic acid, the α-carbon atom of which is chiral. **2** any salt or carboxylic ester of mandelic acid.



L-(*S*)-(+)-form

mandelonitrile α-hydroxybenzeneacetonitrile; benzaldehyde cyanohydrin; a compound that occurs free and as β-glucosides of (+)-, (–)-, and (±)-mandelonitrile.



manganese *symbol*: Mn; a ferromagnetic, metallic transition element of group 7 of the IUPAC **periodic table**; atomic number 25; relative atomic mass 54.938. There is one stable nuclide of mass number 55. Manganese is widely distributed and abundant in the Earth's crust and is an essential component of all living material. It forms manganese(II) (manganous) and less stable manganese(III) (manganic) compounds, including ionic compounds, and complexes; it can also exist in higher oxidation states. Mn^{2+} ions act as activators of various enzymes. A number of artificial radioactive isotopes are known.

manifold a vessel or tube with a number of inlets or outlets used to collect or distribute gases or liquids in an apparatus.

manna a sweet-tasting, white to yellow dried exudate of the manna ash tree (*Fraxinus ornus*) and other plants. *See also* **manninotriose**.

mannan the main **hemicellulose** of soft (coniferous) wood, made up of D-mannose, D-glucose, and D-galactose in the ratio of 3:1:1. Glucomannans occur in ferns and in certain higher plants and algae where they may function as the main structural component of the cell wall. Highly branched mannans can be extracted from the cell walls of some yeasts.

mannanase *or* **mannase** *see* **mannosidase** (def. 2).

Mannich reaction any chemical reaction in which an imminium ion of the type $CR'_2{=}N^+R_2$ reacts with a nucleophilic carbon atom, such as that of an enolate anion derived from a ketone or that of an activated double bond as in a phenol, aryl ether, pyrrole, or indole. Mannich reactions are believed to occur widely in biosynthetic pathways of polycyclic compounds, especially alkaloids and porphyrins. [After Carl Mannich (1877–1947).]

manninotriose the trisaccharide Gal(α1-6)Gal(α1-6)Glc; a component of **stachyose**, it also occurs free in **manna** from ash trees.

mannite *a former name for* **mannitol** (use deprecated).

D-mannitol the alditol derived from D-mannose by reduction of the –CHO group. It is widespread in higher plants, plant exudates, and algae, and is obtained from the manna ash (*Fraxinus ornus*) and seaweeds. Mannitol is metabolized by a number of bacteria including many strains of *Escherichia coli* and *Salmonella* spp. Clinically it is administered intravenously as an osmotic diuretic.

manno+ *comb. form* of mannose.

manno- *prefix (in chemical nomenclature)* indicating a particular configuration of a set of (usually) four contiguous >CHOH groups, as in the acyclic forms of D- or L-mannose. *See* **monosaccharide**.

mannobiose the disaccharide Man(β1-4)Man; a constituent of D-gluco-D-mannans isolated from hardwoods, and of polysaccharides from iris, orchid, and lily families.



mannoheptulose *manno*-2-heptulose; the D enantiomer (formerly known as D-*manno*-ketoheptose) occurs in the avocado.

mannokinase EC 2.7.1.7; an enzyme that catalyses the phosphorylation by ATP of D-mannose to D-mannose 6-phosphate with release of ADP. It initiates the further metabolism of mannose, e.g. after uptake by bacteria. Hexokinase has a wide specificity for sugars and catalyses this reaction, e.g., in mammalian liver.

mannosamine *symbol*: ManN; *a trivial name for* 2-amino-2-deoxymannose.

mannose *symbol*: Man; *a trivial name for* the aldohexose *manno*-hexose, the C-2 epimer of **glucose**. The D-(+)-form is widely distributed in mannans and hemicelluloses and is of major importance in the core oligosaccharide of N-linked oligosaccharides of glycoproteins, especially at branch points. A commonly occurring structure is Man(α1-6)[Man(α1-3)]Man(β1-4)GlcNAc(β1-4)GlcNAc-Asn.

mannose-binding protein (*abbr.*: MBP) *or* **mannose-binding lectin** a **collectin** secreted by hepatocytes as an acute-phase response protein into human plasma. The clusters of **lectin** domains bind mannose residues on microbial and fungal surfaces in a Ca^{2+}-dependent manner. It activates (in the third pathway) the C3 component of **complement** after binding to C1q receptors, and its structure resembles that of C1q. It acts through the serine protease **MASP** associated with it. Macrophages have a membrane-bound MBP. Hereditary deficiency or dysfunction results in increased frequency of bacterial infections in infants and children, and is a frequent finding in lupus erythematosus and rheumatoid arthritis patients.

mannose 6-phosphate an intermediate in **mannose** metabolism, formed from mannose by **mannokinase** or from fructose 6-phosphate by **mannose-6-phosphate isomerase**. Apart from acting as a precursor in GDPmannose formation, it is a component of lysosomal enzymes, playing an important role in sorting the enzymes into lysosomes. *See also* **I-cell disease**, **mannose 6-phosphate receptor**.

mannose-1-phosphate guanylyltransferase EC 2.7.7.13; *other name*: GTP–mannose-1-phosphate guanylyltransferase; an enzyme that catalyses the reaction between GTP and α-D-mannose 1-phosphate to form GDPmannose with release of pyrophosphate.

mannose-1-phosphate guanylyltransferase (GDP) EC 2.7.7.22; *systematic name*: GDP:D-mannose-1-phosphate guanylyltransferase. An enzyme involved in M-antigen biosynthesis in salmonellae; it catalyses a reaction between GDP and D-mannose 1-phosphate to form orthophosphate and GDPmannose. This protein belongs to the **mannose-6-phosphate isomerase** family 2.

mannose-6-phosphate isomerase EC 5.3.1.8; *systematic name*: D-mannose-6-phosphate ketol-isomerase; *other names*: phosphomannose isomerase; phosphohexoisomerase; phosphohexomutase. An enzyme that catalyses the reaction:

D-mannose 6-phosphate = D-fructose 6-phosphate;

zinc is a cofactor. The sequences belong to two families. Most enzymes (including human) belong to family 1. Family 2 is represented by an enzyme involved in alginate metabolism. *See also* **mannose-1-phosphate guanylyltransferase**.

mannose 6-phosphate receptor a protein on the surface of membranes in the Golgi apparatus and late endosomes that recognizes mannose 6-phosphate residues on lysosomal enzymes and is responsible for sorting them into late endosomes, which then become lysosomes. Lysosomal enzymes bearing phosphomannosyl residues bind specifically to mannose-6-phosphate receptors in the Golgi apparatus, and the resulting receptor–ligand complex is transported to an acidic prelysosomal compartment where the low pH mediates dissociation. There are two types of receptor protein. (1) The cation-dependent type, or M6P receptor, is a type I membrane glycoprotein homodimer involved in transport of phosphorylated lysosomal enzymes from the Golgi apparatus and the cell surface to lysosomes. It binds one molecule of M6P, does not bind insulin-like growth factor II (IGFII), and has an N-terminal region homologous to the repeats of the second type. (2) The cation-independent type, or M6P/IGFII receptor, is a type I glycoprotein membrane receptor that binds two molecules of M6P, and at a different site, IGFII. Its N-terminal region contains 15 homologous repeats (each of ≈145 amino acids) homologous to that in the N terminus of the first type. *See also* **I-cell disease**.

mannosidase **1** α-mannosidase; EC 3.2.1.24; *systematic name*: α-D-mannoside mannohydrolase; an enzyme that catalyses hydrolytic removal of terminal, nonreducing residues in α-D-mannosides. **2** β-mannosidase EC 3.2.1.25; *systematic name*: β-D-mannoside mannohydrolase; *other names*: mannanase; mannase; an enzyme that catalyses hydrolytic removal of terminal, nonreducing residues in β-D-mannosides.

Both enzymes function in lysosomes at an acid pH, in the degradation of glycoproteins. Deficiency of either activity leads to a form of mannosidosis. *See also* **ER mannosidase**, **Golgi mannosidase**.

mannoside any **glycoside** in which the sugar moiety is a **mannose** residue.

α-mannosidosis a genetic disorder of humans characterized by abnormal storage and urinary excretion of mannose-rich oligosaccharides due to deficiency of lysosomal **α-mannosidase** activity. Type 1 is a severe or infantile form. Type 2 is milder and appears in juveniles and adults.

β-mannosidosis a genetic disorder of humans, less frequent than α-mannosidosis, characterized by abnormal accumulation and urinary excretion of the disaccharide Manβ-1,4-*N*-acetylglucosamine, due to deficiency of lysosomal β-mannosidase.

mannosyl any of the glycosyl ligands formed by detaching the anomeric (*α*- or *β*-) hydroxyl group, on C-1, from a cyclic form (pyranose or furanose) of mannose.

***α*-1,3-mannosyl-glycoprotein *β*-1,2-*N*-acetylglucosaminyltransferase** EC 2.4.1.101; *other name*: *N*-glycosyl-oligosaccharide-glycoprotein *N*-acetylglucosaminyltransferase I (*abbr*.: GlcNAc-TI *or* GNT-I); an enzyme involved in the synthesis of oligosaccharides, particularly those that are N-linked in glycoproteins. It catalyses the reaction between UDP-*N*-acetyl-D-glucosamine and *α*-D-mannosyl-1,3-(R)-*β*-D-mannosyl-R′ to form *N*-acetyl-*β*-D-glucosaminyl-1,2-*α*-D-mannosyl-1,3-(R)-*β*-D-mannosyl-R′ with release of UDP.

mannuronate **1** the anion of mannuronic acid, the compound formed by oxidation of the C-6 hydroxymethylene group of mannose to a carboxyl group. **2** any salt or ester of mannuronic acid. D-Mannuronic acid is a component of **alginic acid**.



β-D-pyranose form

manoalide a naturally occurring marine sesterterpenoid. It is an irreversible inhibitor of phospholipases A_2 and C, and a potent inhibitor of Ca^{2+} mobilization.

manometer an instrument for measuring pressure differences. The simplest type consists of a U-tube filled with a suitable liquid (often mercury), and compares a pressure delivered to one side with atmospheric pressure on the other, open, side of the tube. The difference in the level of liquid in the two arms of the tube gives a measure of the unknown pressure. In biochemistry the term is often used to mean a manometric **respirometer**.

manometer constant a predetermined factor, calculated for each individual constant-volume manometric **respirometer**, that when multipled by the manometer reading immediately gives the volume of gas evolved in cubic millimetres at **standard** temperature and pressure. The factor is itself dependent upon temperature, liquid volume, density of the manometer fluid, and nature of the gas phase.

manometer fluid any fluid used to fill a **manometer**. In biochemistry this usually refers to the fluid used to fill the manometer of a respirometer. Such fluids are generally easily visible, wet the glass walls of the manometer, have a density that will give an easily calculated manometer constant, and have a low vapour pressure. Examples include **Brodie's fluid**, and **Krebs' manometer fluid**.

manometric **1** of, pertaining to, or measured with a **manometer**. **2** *(in biochemistry)* of, or pertaining to, a manometric respirometer. —**manometrically** *adv.*

manometry **1** the measurement of gas pressure by means of a manometer. **2** *(in biochemistry)* the use of manometric respirometers in studies of chemical and biochemical reactions.

Man*p* *symbol for* a mannopyranose residue.

mantissa the fractional part of any **logarithm**.

MAO *abbr. for* monoamine oxidase.

MAO inhibitor *abbr. for* monoamine oxidase inhibitor.

map **1** any representation of the surface features of an object, especially the spatial relationships of physical or chemical landmarks, as in **electron-density map**, **genetic map**, and **restriction map**. By extension the term is applied to certain two-dimensional patterns obtained in analysis, e.g. **peptide map**. **2** to make a **map** (def. 1). **3** to occur, or be placed, at a specific position on a **map** (def. 1).

MAP *abbr. for* microtubule-associated protein.

map distance *(in genetics)* the distance, in terms of percentages of crossing-over (i.e. 100 × no. of recombinants/total no. of progeny), between particular linked genes. *See also* **map unit**.

MAP kinase *abbr. for* mitogen-activated protein kinase; a family of protein kinases that perform a crucial step in relaying signals from the plasma membrane to the nucleus. They are turned on by a wide range of proliferation- or differentiation-inducing signals. For example, the MAP kinase FUS3 of *Saccharomyces cerevisiae* is required for the transition from mitosis into conjugation. The name does not indicate that this is a kinase for MAPs – rather that it is a protein kinase that is mitogen-activated. Nevertheless, some MAPs can be substrates for this enzyme. *See also* **ERK**.

MAP kinase kinase *abbr*.: MAPKK; EC 2.7.1.–; a dual-specificity mitogen-activated protein kinase kinase; *other names*: erk activator kinase; extracellular signal-regulated kinase; an enzyme that catalyses the concomitant phosphorylation of threonine (T) and tyrosine (Y) residues in a TEY sequence in **MAP kinases**. It requires activation by the serine/threonine kinase, MAP kinase kinase kinase (*see* ***RAF***).

maple-syrup urine disease *or* **branched-chain ketonuria** an autosomal recessive disease of humans characterized by neurological signs and the onset of feeding problems in the first week of life, and associated with a maple-syrup odour of the urine. The concentrations of branched-chain amino acids and branched-chain keto acids are elevated in the blood of patients, due to deficiency of the enzyme responsible for the oxidative decarboxylation of branched-chain keto acids.

MAPTAM 1,2-bis-(2-amino-5-methylphenoxy)ethane-*N,N,N′,N′*-tetraacetic acid tetraacetoxymethyl ester; a substance that readily penetrates cell membranes and undergoes intracellular hydrolysis with the formation intracellularly of the 5-methyl form of **BAPTA**. It is useful as an indicator of intracellular calcium concentrations.



map unit *or* **Morgan's unit** a unit of genetic length along a chromosome and defined in terms of recombination frequency, expressed as a percentage; a recombination frequency of 1 per cent (that is one recombinant individual in a hundred progeny) equals one map unit. 1 map unit = 1 centimorgan. *Compare* **morgan**.

maquette a protein designed *de novo*, to investigate properties such as electron transfer.

MAR **1** *abbr. for* matrix attachment region. **2** *abbr. for* matrix-associated region; a region of DNA that binds to the nuclear protein network and segregates chromosomal subdomains.

marasmus a wasting away of the body, especially of infants, caused by chronic deficiency of intake of energy-producing foodstuffs. *Compare* **kwashiorkor**.

marcks *abbr. for* myristoylated alanine-rich C kinase substrate; a filamentous (F) actin cross-linking protein and the most prominent substrate for protein kinase C. It also binds calmodulin, actin, and synapsin and is displaced from the membrane by phosphorylation by protein kinase C.

Marcus theory a set of equations that describe the rates of electron transfer between molecules, also applicable to transfer between electron carriers within a protein. The rate depends on the energy barrier to electron transfer, which involves reorganization of the structures so that the potentials of donor and acceptor are equal. The theory leads to the counterintuitive conclusion that above a certain driving force (the inverted region) a greater driving force leads to a decreased rate of electron transfer. [After Rudolph A. Marcus, winner of the 1992 Nobel Prize in Chemistry for his contributions to the theory of electron transfer reactions in chemical systems.]

marenostrin *an alternative name for* pyrin. *See* **familial Mediterranean fever**.

margarine a processed fat used as a substitute for butter. Modern margarines are prepared from hydrogenated natural fats, the trend in recent years having been to preserve a high content of nutritionally desirable **polyunsaturated fatty acids**. Apart from the oil or fat content, margarine contains a water phase that is 16–20% of content and includes water, cream, whole milk, skim milk (powder), whey, and buttermilk in various ratios; flavouring, which may include diacetyl, fatty acids, and ketones; colouring agents, mainly based on carotenes; additional vitamins A and D; and **antioxidants** such as di-*tert*-butyl *p*-cresol. The process was invented in 1869 by H. Mège-Mouriès on the order of Napoleon III to produce a cheap stable butter substitute. Mège-Mouriès churned a beef tallow fraction, known as **oleomargarine**, with cream.

marijuana *see* **cannabis**.

Mariotte bottle *or* **Mariotte flask** a device for providing a flow of liquid maintained at a constant pressure head; it is used, e.g., in column chromatography. It consists of a sealed flask, closed to the atmosphere, with an outlet at or near the bottom and an air inlet tube open to the atmosphere. The height of the bottom of the inlet tube is adjustable. When the flask is filled with liquid to a level above the bottom of the inlet tube the pressure of the liquid flowing from the flask is determined by the height of the bottom of the inlet tube above the outlet point. [After Abbé Edmé Mariotte (1620–84), French physicist.]

Mariotte's law *an alternative name (esp. Fr.) for* Boyle's law (*see* **gas laws**).

marker 1 an appropriate reference substance or material included in a sample being subjected to a separation procedure such as chromatography, electrophoresis, or density-gradient centrifugation. **2** *see* **biochemical marker**. **3** *see* **genetic marker**. **4** *an alternative term for* **label** (def. 3).

marker enzyme any enzyme of known intracellular location that can be assayed as an aid in following the isolation and purification of subcellular fractions.

marker gene any gene of known function and known location on a chromosome. *Compare* **genetic marker**.

marker rescue a process whereby one or more genetic markers from a UV-irradiated virus are integrated into an unirradiated helper virus in infected bacteria; such genes are thereby 'rescued' by recombination.

Markham still a simple, all-glass, steam-jacketed apparatus for the rapid and efficient steam distillation of a succession of small samples of volatile substances. It was designed especially for the distillation of ammonia as part of the micro-Kjeldahl procedure for the determination of nitrogen, but has been found to be prone to carry-over from one sample to the next. [After Roy Markham (1916–79), British biochemist.]

Markovnikov('s) rule a generalization stating that when a molecule of water, or a hydrogen halide, or some other polar substance, is added heterolytically across an asymmetrically substituted carbon–carbon multiple bond, the hydrogen atom or other more electropositive part of the molecule becomes attached usually to that carbon atom carrying the larger number of hydrogen atoms while the hydroxyl, halo, or other more electronegative part of the molecule becomes attached to that carbon atom carrying the smaller number of hydrogen atoms. [After Vladimir Vasilyevich Markovnikov (1838–1904), Russian chemist, who formulated the rule on empirical grounds (1870).]

markup language a language used to structure and label documents in a logical fashion. The labels may provide format information on how the data should be presented visually (e.g. by a Web browser) or semantic information concerning the kind of data being represented. Markup languages facilitate text-based data exchange and can be understood by humans and machines. Examples include HTML (hypertext markup language), XML (extensible markup language), UML (universal markup language), and MAML (microarray markup language).

Markush structure a chemical structure in which multiple 'functionally equivalent' chemical entities are allowed in one or more parts of the compound. Markush structures are used for example in patents to protect an invention of related compounds, without requiring the inventor to prepare and test every possible compound. [After Eugene A. Markush, the first inventor to include them successfully in a U.S. patent, in 1924.]

Maroteaux–Lamy syndrome *an alternative name for* **mucopolysaccharidosis VI**.

marsh gas *another name for* **methane**.

MAS a human transforming gene that encodes a neuronal-type angiotensin III receptor. The latter is a G-protein-associated membrane receptor that activates phospholipase C.

maser a device for producing intense beams of microwave radiation of defined frequency. *Compare* **laser**. [From microwave amplification by stimulated emission of radiation.]

Mash *abbr. for* mammalian Achaete-Scute homologue; either of two mammalian genes that encode basic helix-loop-helix transcription factors and are related to the *Drosophila Achaete–Scute* genes. Mash-1 is expressed in precursor cells for the central and autonomic nervous systems and olfactory epithelium. Mash-2 is expressed in oocytes, preimplantation embryos, and placenta. *See* **AS-C protein**.

mask (*in sequence analysis*) to remove repeated or low-complexity regions from a sequence in order to improve the sensitivity of database-search programs. *See* **sequence filter**.

masked residue any residue in a biopolymer that is not accessible to, and cannot react with, a reagent specific for that type of residue, either because of the position of the residue or because of the nature of its immediate environment.

maskin a protein of *Xenopus laevis* that is involved in regulating the translation of mRNA during embryonal development. It interacts with cytoplasmic polyadenylation-element binding protein bound to the polyadenylation element at the 3′ untranslated region of mRNA.

MASP *abbr. for* MBP-associated serine protease; a serine protease (100 kDa) that is associated with **mannose-binding protein** (MBP). It shares ≈39% homology with C1r and C1s of **complement**. Binding of MBP to microbial polysaccharides enhances activation of MASP.

maspin a **serpin**-like tumour suppressor of epithelial cells.

mass 1 *symbol*: *m* or *M*; one of the seven SI base physical quantities; the SI base unit of mass is the **kilogram**. **2** *a general term for* the quantity of matter in a body, a characteristic that is both a measure of the resistance of the body to changes in its velocity, i.e. **inertial mass**, and a measure of the force experienced by the body in a gravitational field, i.e. **gravitational mass**. Mass is commonly confused with weight. According to the theory of relativity, inertial and gravitational masses are equal, mass increases with velocity, and mass and energy are interconvertible.

mass action, law of a law stating that, for a homogeneous system, the rate of reaction of a chemical reaction is proportional to the active masses of the reacting substances; i.e. the rate is proportional to the product of the activities of the reactants, each raised to a power equal to the number of reactant molecules of that type that participate in the reaction.

mass-average molar mass *see* **average molar mass**.

mass concentration *see* **concentration** (def. 1a).

mass density *see* **concentration** (def. 1a).

mass fraction *symbol*: *w*; the mass of a specified component of a system divided by the mass of the system; it is dimensionless.

mass fragmentography *a common but less rigorous name for* **selected-ion monitoring**.

mass number *an older name for* **nucleon number**.

mass spec. *abbr. (colloquial) for* mass spectrometer, mass-spectrometric, or mass spectrometry.

mass spectrograph a **mass spectrometer** in which the ions fall on a photographic plate.

mass spectrometer *abbr.*: MS *or (colloquial)* mass spec.; any instrument for **mass spectrometry**.

mass spectrometry *abbr.*: MS *or (colloquial)* mass spec.; an analytical method for determining the relative masses and relative abundances of components of a beam of ionized molecules or molecular fragments produced from a sample in a high vacuum. It is applicable to any sample that is gaseous or volatile at low pressure, or that can be so rendered by derivatization. In the commonest version, the ions, generated usually by electron bombardment of the sample, are formed into a beam and then accelerated to a uniform velocity by means of an arrangement of electrically charged slits. The beam is then dispersed into a spectrum of particles of different mass-to-charge ratios, m/e, by application of a suitably disposed magnetic field. The ions of any particular m/e value may be focused on a collecting electrode by appropriate adjustment of the accelerating potential or magnetic field and the resulting ion currents measured electrometrically. With a suitably designed mass spectrometer the method can be used to determine the relative abundances of isotopes of an element or the relative molecular masses of two or more compounds, or used to aid the identification of a complex compound by the mass spectrum of the fragments generated from it on electron bombardment. *See also* **gas chromatography/mass spectrometry**, **selected-ion monitoring**. **—mass-spectrometric** *adj.*

mass spectrum a tracing, photographic record, or diagram of the relative numbers of different ions (representing molecules or molecular fragments) obtained (from a specimen) by **mass spectrometry**, ranked in order of their mass-to-charge ratios.

mass-to-charge ratio *(in mass spectrometry)* the ratio of the mass, m, of an ion to the charge, e, on the ion. *See also* **mass spectrometry**.

mass transfer the spontaneous and irreversible process of transfer of mass across nonhomogeneous fields, e.g. between liquid phases, or from one side of a membrane to another.

mass unit *see* **atomic mass unit**, **dalton**.

mast cell a type of leukocyte, of the subclass granulocyte; it is characterized by having numerous cytoplasmic basophilic granules rich in histamine together with 5-hydroxytryptamine and heparin. Degranulation of mast cells, with release of the vasoactive amines, occurs by reaction, through a specialized region of the Fc piece, of antigen with homocytotropic antibody (reagin) bound to the cell. This leads to an immediate hypersensitivity reaction.

mast cell degranulating peptide *abbr.*: MCDP; a major neurotoxic 22-residue peptide of bee venom: IKCNCKRHVIKPHICRKICGKN–NH_2. It stimulates degranulation of mast cells, and selectively blocks the neuronal Ca^{2+}-dependent K^+ channel.

mast cell growth factor *see* **stem cell factor**.

mastoparan a tetradecapeptide neurotoxin from wasp venom: Ile-Asn-Leu-Lys-Ala-Leu-Ala-Ala-Leu-Ala-Lys-Lys-Ile-Leu-NH_2. It functions like **melittin** and **mast cell degranulating peptide**, in generating ion channels in membranes. It is classified in the TC system under number 1.C.16.

MATα2 yeast mating-type protein α-2 repressor; a regulatory DNA-binding protein that acts as a master switch in yeast differentiation by controlling gene expression in a cell-type-specific fashion. In α haploids and **a**/α diploids (*see* **mating type**) it represses the transcription of α-cell-specific genes. In **a**/α diploids it also forms a complex with MATα1 protein that represses haploid-specific gene expression.

matchmaker proteins *see* **molecular matchmakers**.

maternal-effect gene any gene expressed in females whose mRNA transcript is found in the egg. Notable examples from *Drosophila* are *oskar* and *bicoid* (*see* **bicoid protein**), which determine egg polarity.

maternal imprinting the epigenetic silencing of an allele inherited from the mother. *See* **imprinting**.

Math 1 a basic helix-loop-helix transcription factor that determines epithelial cell commitment in the mouse intestine. It is a downstream target in the notch signalling pathway, and is also involved in cell fate determination in the nervous system.

mathematics **1** *functioning as sing.* the group of related sciences concerned with number, space, shape, and quantity, and their interrelationships. **2** *functioning as sing. or pl.* the use of mathematical processes or operations in calculations or the solution of problems.

mating type one of the two types of *Saccharomyces cerevisiae*, α and **a**, that are necessary for mating, a process in which two haploid cells fuse. The resulting diploid cell, **a**/α, cannot mate, but can produce spores, giving rise to haploid cells by meiosis. The mating type of the haploid cell is determined by a single locus, the mating-type (*MAT*) locus. In **a** cells, this encodes a regulatory protein **a**1, and in an α cell it encodes two such proteins, α1 and α2. In the **a**/α cell, the regulatory proteins **a**1 and α2 combine to generate a completely new pattern of gene expression. *See also* **MATα2**.

matricin *an alternative name for* **matrix metalloprotease**.

matrilysin EC 3.4.24.23; *other names*: matrin; uterine metalloendopeptidase; matrix metalloproteinase 7 (*abbr.*: MMP7); putative (or punctuated) metalloproteinase-1 (*abbr.*: PUMP-1); an enzyme that catalyses the cleavage of Ala^{14}-|-Leu^{15} and Tyr^{16}-|-Leu^{17} in the B chain of insulin. It has no action on collagen types I, II, IV, or V. It cleaves casein and fibronectin and shows preference for gelatin chain α-2(I) over α-1(I). It is secreted as the precursor, promatrilysin, and is activated by autocatalytic cleavage at Glu^{77}-|-Tyr^{78}. Zinc and calcium are cofactors.

matrin *or* **DNA-binding protein F/G** a **zinc-finger** DNA-binding protein of the fibrogranular areas of the nucleus. Matrins comprise a family of eight major polypeptides of nuclear matrices of rat liver and tissue culture cells, highly conserved between humans and mouse. The name has sometimes been used as a synonym for **matrilysin** and matrin F/G is therefore used to avoid confusion.

matripsin *or* **matrix-type serine protease 1** (*abbr.*: MT-SP1) EC 3.4.21; a type 2 transmembrane serine protease of gastrointestinal tract, spleen, and prostate. The mouse orthologue shares 81% sequence identity with the human enzyme (855 amino acids).

matriptase *an alternative name for* membrane type-serine protease 1. *See* **MT-SP1**.

matrix (*pl.* **matrices** *or* **matrixes**) **1** a medium or place wherein something is formed, develops, or is embedded or enclosed. **2** the medium that forms, or supports, the stationary phase in certain separative procedures, as in chromatography or zone electrophoresis; the material that forms, or is used to form, the substratum of an immobilized reagent in affinity chromatography. **3** *(in animal histology) see* **extracellular matrix**. **4** *(in plant histology)* the meshwork of soluble substances, largely polysaccharide in nature, occurring in cell walls and in which insoluble microfibrils of cellulose are embedded. **5** *see* **mitochondrial matrix**. **6** cytoplasmic matrix; *see* **groundplasm**. **7** the substratum, living or nonliving, in or on which a fungus or lichen grows. **8** *(in mathematics)* any rectangular array of numbers or symbols manipulable algebraically as a single entity and used according to specific rules to facilitate solving of certain kinds of problems, e.g. a set of simultaneous linear equations.

matrix attachment region *abbr.*: MAR; an AT-rich, ≈200-bp sequence of DNA that binds to the nuclear scaffold (the site of RNA synthesis) in the interphase nucleus. MARs anchor genes near the nuclear membrane; they are believed to help regulate transcription by controlling the chromatin state of DNA, mediating chromatin unfolding prior to expression.

matrix Gla protein a protein that mediates association of the organic matrix of bone and cartilage. It contains γ-carboxyglutamate (Gla) residues, formation of which is vitamin-K-dependent.

matrix metalloproteinase *abbr.*: MMP; any proteolytic enzyme associated with the **extracellular matrix**. The group includes: MMP1, interstitial collagenase; MMP2, gelatinase A; MMP3, stromelysin-1; MMP8, neutrophil collagenase; MMP10, stromelysin-2; MMP12, metalloelastase. They have been implicated in facilitating cell migration, and in the ability of malignant cells to invade tissues and metastasize. They convert tumour necrosis factor (TNF) precursor into active TNF and may be implicated in other diseases such as rheumatoid arthritis or osteoarthritis. For these reasons, there is current interest in matrix metalloproteinase inhibitors (*abbr.*: MMPIs) as potential drugs. *See also* **TIMP**.

matrix metalloproteinase inhibitor *see* **MMPI**.

matrix processing peptidase *abbr.*: MPP; *an alternative term for* **mitochondrial processing peptidase**.

matrix protein **1** the major protein component of the outer membrane of *Escherichia coli*. It is a transmembrane protein that forms hydrophilic pores permitting the passage of microsolutes; in association with **lipopolysaccharide** (def. 4) it forms a receptor for phages. It is a member of the **porin** family, and is a product of the gene *DMPC*. **2** any of a class of proteins that coat the inside of the lipid bilayer in the envelope of some groups of enveloped viruses.

matrix space *or* **(mitochondrial) lumen** the innermost compartment of a mitochondrion, containing the **mitochondrial matrix**.

matrix vesicle any of the minute, membrane-bound, extracellular particles (≈100 nm in diameter) occurring in the interstitial matrix of calcifying cartilage. The vesicles contain a number of enzymes involved with local calcification mechanisms.

maturation **1** the process of coming to full development, ripening, or becoming mature. **2** *or* **maturation division** the processes of formation of gametes (sperm or ova) from primary gametocytes involving meiosis of the nucleus with reduction of chromosome number from diploid to haploid. **3** *(in virology)* the overall process leading to the incorporation of a viral genome into a capsid and the development of a complete virion.

maturation-promoting factor *an alternative name for* **M-phase-promoting factor**.

maturation protein *or* **A protein** one of the three proteins encoded by certain single-stranded RNA bacteriophages, one molecule of which is necessary for proper encapsulation of the RNA and for binding of the phage to a pilus on the host cell.

mature mRNA the functional form of **messenger RNA** (mRNA) that results from capping, splicing, and polyadenylation of the primary transcript.

maturity-onset diabetes *a former name for* type 2 **diabetes mellitus**.

maturity-onset diabetes of the young *abbr*.: MODY; an autosomal dominant form of type 2 (non-insulin-dependent) diabetes mellitus that has early onset. Mutations of six genes have been implicated: MODY 1, HNF-4α (locus 12q24.31); MODY 2, glucokinase (locus 7p13); MODY 3, HNF-1α (locus 20q13.12); MODY 4, IPF-1 (locus 13q12.2); MODY 5, TCF2 (locus 17cen-q21.3); MODY 6, NEUROD1 (locus 2q32). MODY 3 and MODY 2, the most prevalent forms, account for more than 80% of Caucasian patients.

max *abbr. for* maximal or maximum.

MAX a gene family coding for DNA-binding proteins that function in cell growth control. The product, Max, forms heterodimers with Myc (*see* ***MYC***) that bind specifically to CACGTG; it also forms homodimers of similar specificity. Max contains **helix-turn-helix** and heptad repeats.

Maxam–Gilbert method (for DNA sequencing) *see* **chemical cleavage method**.

maxicell *or* **maxi cell** a bacterial cell that has been heavily irradiated with UV light and in which the chromosomal DNA is extensively degraded. Any plasmid(s) present usually escape damage and the genes they encode can be expressed.

maxicircle DNA any large, closed circular DNA molecule, as in the **kinetoplast** of *Leishmania tarantolae*.

maxima a plural of **maximum** (def. 1).

maximal *abbr*.: max; of, pertaining to, or reaching a maximum; being the greatest possible in size, duration, etc.; **maximum** (def. 2). —**maximally** *adv.*

maximal agonist effect *or* **intrinsic activity** *symbol*: α; the maximal effect that an agonist, whether conventional or inverse, can elicit in a given tissue under particular experimental conditions, expressed as a fraction of that produced by a full agonist acting through the same receptors under the same conditions.

maximal rate *or* **maximum rate** *another name for* **limiting rate**. Symbol V (recommended) or V_{max}. *See* **Michaelis kinetics**.

maximal velocity *or* **maximum velocity** *an older name for* **limiting rate**.

maximum *abbr*.: max; **1** (*pl.* **maxima** *or* **maximums**) the highest or greatest possible amount, degree, etc.; the highest value of a variable quantity. *Compare* **minimum**. **2** of, being, or exhibiting a maximum or maxima; **maximal**.

maximum likelihood a statistical method for parameter estimation using a prespecified model and a set of empirical data. The parameter values are chosen to maximize the probability of observing the data, given the hypothesis. In phylogeny, the method is used to find the tree topology with maximum likelihood, given the data and the model of sequence evolution, and to estimate branch lengths and other evolutionary parameters.

maximum parsimony the principle that a simpler solution is preferred to a more complex one. For example, in phylogenetics, a tree that requires the fewest evolutionary events to explain the data is preferable to a tree that requires more events.

maximum-scoring segment pair *abbr*.: MSP; the highest scoring of high-scoring segment pairs (HSPs) that result from the alignment-extension step in BLAST. *See* **alignment algorithm**.

Maxwell relation a relation between the dielectric constant, ε, and the refractive index, n, of a nonabsorbing, nonmagnetic material such that $\varepsilon = n^2$. [After James Clerk Maxwell (1831–79), British physicist.]

Mb **1** *abbr. for* myoglobin; hence $\mathrm{MbO_2}$, oxymyoglobin; MbCO, carbonmonoxymyoglobin; etc. **2** *symbol for* megabase, i.e. $= 10^6$ bases. **3** *(in computing) abbr. for* megabyte (i.e. 2^{20} bytes; alternative to MB).

MBOAT *abbr. for* membrane-bound *O*-acyltransferase.

***Mbo*I** a type 2 **restriction endonuclease**; recognition sequence: ↑GATC. *Sau*3AI is an **isoschizomer**.

***Mbo*II** a type 2 **restriction endonuclease**; recognition sequence: GAAGANNNNNNNN↑.

MBP *abbr. for* mannose-binding protein.

MBP-associated serine protease *see* **MASP**.

MBS *abbr. for* *meta*-maleimidobenzoyl-*N*-hydroxysuccinimide ester; a heterobifunctional reagent useful, *inter alia*, for coupling an enzyme to an antibody, without appreciable loss of either activity.



MBSA *abbr. for* methylated bovine serum albumin.

mc *(formerly) abbr. for* millicurie (mCi now used).

$\mathbf{Mc_3}$ *symbol for* mucotriaose ($\mathrm{McOse_3}$ preferred if space permits).

$\mathbf{Mc_4}$ *symbol for* mucotetraose ($\mathrm{McOse_4}$ preferred if space permits).

MCAD *abbr. for* medium chain acyl-CoA dehydrogenase; *see* **beta-oxidation system**.

McArdle's disease *an alternative name for* type V **glycogen disease**.

MCC the symbol for a gene (standing for 'mutated in colorectal cancer') that is closely linked to the *APC* gene at 5q21 in humans. It encodes a protein (829 amino acids) that may be a tumour suppressor. Somatic mutations of *MCC* occur in 5–10% of colorectal cancers.

MCD *abbr. for* **1** magnetic circular dichroism. **2** mean corpuscular (erythrocyte) diameter.

MCDP *abbr. for* mast cell degranulating peptide.

M cell *or* **microfold cell** a type of epithelial cell of intestinal mucosa that overlies patches of lymphoid tissue (Peyer's patches). M cells have an invaginated base in which lymphocytes and macrophages can aggregate. The cells present bacterial and viral protein antigens to the underlying lymphocytes, inducing proliferation of the latter and the secretory immune response.

McFarlane's method a method for the radioiodination of proteins with high efficiency in which the protein to be labelled is reacted with iodine monochloride that has been previously equilibrated with radioiodide. The extent of substitution can be precisely controlled by use of an appropriate quantity of iodine monochloride. [After Arthur Sproul McFarlane (1905–78), British biophysicist.]

MCH *abbr. for* melanin concentrating hormone.

mCi *symbol for* millicurie.

McIlwain chopper *or* **McIlwain–Buddle chopper** a hand- or motor-driven machine for rapidly cutting a piece of animal tissue into slices of uniform, preselected thickness (≥0.07 mm) and then, if desired, into prisms by making a second series of cuts. Such prisms can yield easily dispensed suspensions that retain those metabolic characteristics that tend to be lost on homogenization of tissue. [After Henry McIlwain (1912–92), British biochemist, and H. L. Buddle.]

McIntosh and Fildes jar *see* **anaerobic jar**.

McLeod gauge a mercury-in-glass vacuum pressure gauge that is capable of measuring down to 10^{-5} mmHg (1.33×10^{-3} Pa). A known large volume of gas is compressed into a small volume, in which the now much larger pressure is measured.

MCM protein any of six related ATPase proteins in budding yeast that are essential for initiation of replication. They assemble into a large ring complex around the DNA at the origin of replication complex (**ORC**), being stabilized by Cdc45. They appear in the nucleus during G_1 phase of the cell cycle, and are exported into the cytoplasm from S to G_2 phases. They are considered to function as a **licensing factor**, permitting one round of replication to occur per cell cycle. Mutants of the MCM homologue PROLIFERA in *Arabidopsis* are lethal.

McOse$_3$ *symbol for* mucotriaose (preferred alternative to Mc$_3$).

McOse$_4$ *symbol for* mucotetraose (preferred alternative to Mc$_4$).

MCP *abbr. for* methyl-accepting chemotaxis protein.

MCS *abbr. for* multiple cloning site.

Md *symbol for* mendelevium.

MD *(in clinical chemistry) abbr. for* **malate dehydrogenase** (def. 1).

MDa *abbr. for* megadalton.

MDCK cell *abbr. for* Madin–Darby canine kidney cell; a cell of a heteroploid cell line.

MDH *abbr. for* **malate dehydrogenase** (def. 1).

Mdm2 *or* **MDM2** *abbr. for* murine double minute chromosome protein 2; a protein, present mainly in mammalian cell nuclei, that is an E3 ubiquitin-protein ligase. It binds to **p53** and targets it to ubiquitin-mediated degradation in proteasomes.

MDMA *abbr. for* 3,4-methylenedioxymethamphetamine.

MDP *abbr. for* muramyl-dipeptide.

MDR *abbr. for* multiple drug resistance *or* multidrug resistance; the acquired simultaneous resistance of tumour cells or pathogenic organisms to a wide spectrum of drugs arising from the administration, typically over long periods, of one or a limited number of drugs. Such resistance may extend to drugs with little structural or even functional similarity to the original drug(s), and results in reduced efficacy of all the drugs concerned. In long-term chemotherapy of cancer patients it is due to the induced expression of plasma membrane glycoproteins known as P-glycoproteins, or **MDR proteins**. In bacteria it is due to induction of multidrug transporters. *See* **BmrR**.

MDR protein any transmembrane glycoprotein that is involved in (multiple) drug resistance (*see* **MDR**). MDR proteins belong to the ATP-binding cassette (ABC) class of the multidrug transporter superfamily, and are ATP-dependent. MDR1 (or P-glycoprotein 1) occurs in polarized epithelia of intestine, kidney, liver, and blood–brain barrier. MDR2 (or P-glycoprotein 2) is the phosphatidylcholine translocator of the bile canaliculi. MDR3 (or P-glycoprotein 3) is an efflux pump that is not capable of conferring drug resistance by itself. However, its absence leads to severe liver disease. MDR-associated protein participates in the active transport of drugs into subcellular organelles. MDR protein (or P-glycoprotein) of *Leishmania tarentolae* is a protein responsible for acquired methotrexate resistance, and is encoded by a gene located in the 'H-circle', a 68 kb duplex DNA circle containing a 30 kb inverted repeat.

Mdv1 a dynamin-like protein of yeast that contains WD repeats and is required, with Fis1 and Dnm1, in forming the contractile ring around the outer mitochondrial membrane that brings about fission of the organelle.

Me *symbol for* the methyl group, CH_3–.

Mead acid *a name sometimes given to* (*all-Z*)-eicosa-5,8,11-trienoic acid. It can be synthesized *de novo* by mammals via palmitate and oleate, and is thought to substitute partially for the long-chain polyunsaturated fatty acids lacking in essential fatty acid deficiency. [After J. F. Mead, who first identified it as an acid found in elevated concentrations in mammals during essential fatty acid deficiency.]

mean *or* **arithmetic mean** *or* **average** the quotient of the arithmetic sum of any set of two or more numbers, measurements, values, etc. and the number of components of the set. *See also* **geometric mean**. *Compare* **median** (def. 1).

mean deviation the arithmetic average of the absolute values of the differences between the individual values of a set of numbers, values, etc. from their mean.

mean free path the average distance travelled by a molecular entity between collisions. In a gas, the mean free path between molecular entities is inversely proportional to the pressure of the gas.

mean ionic activity coefficient *symbol*: $\gamma_\pm$; the average rational activity coefficient of the ions of an electrolyte that dissociates in solution into cations of charge z^+ and anions of charge z^-, given, according to the limiting law of the Debye–Hückel theory, by:

$$-\log\gamma_\pm = z^+z^-AI^{0.5},$$

where A is a constant whose magnitude depends on temperature, dielectric constant, etc., having a value near 0.5, and I is the ionic strength of the solution.

mean life *or* **average life** *abbr*.: τ; the mean of the lengths of time required for the disintegration of all atoms of a given radionuclide. It is related to the **half-life**, $t_{½}$, and to the **disintegration constant**, λ, of the radionuclide by the expressions:

$$\tau = t_{½}/\ln 2 = 1.443t_{½},$$

and

$$\tau = 1/\lambda.$$

mean relative residue mass *or (formerly)* **mean residue weight** *symbol*: M_o; the quotient of the relative molecular mass of a polymer and the number of residues it contains.

mean residue rotation the average molar optical rotation for a residue in a polymer. It is obtained by substituting the mean relative residue mass, M_o, for the relative molecular mass, M_r, of the polymer in the equation defining **molar optical rotation**.

mean residue weight *a former name for* **mean relative residue mass**.

Mec *abbr. for* the 4-methylcoumarin-7-yl group.

mechanical concerned with, executed or operated by, or as by, a machine; relating to mechanics. **—mechanically** *adv.*

mechanically gated channel *see* **ion channel**.

mechanics 1 the science concerned with the equilibrium or motion of bodies in a given frame of reference. **2** the science of machines and/or machinery.

mechanism 1 the chain of events in a particular process; the action or process by which an effect is produced or an action performed. **2** *(in chemistry)* the detailed description of the pathway leading from reactants to products of a reaction, including where possible a characterization of the composition, structure, and other properties of any reaction intermediates and transition states. **3** any system or structure of moving parts that performs some function; a machine.

mechanistic of, pertaining to, or explained by mechanics; of, pertaining to, or resembling a mechanism. *Compare* **stochastic**.

mechanochemical coupling the coupling of a chemical process with a mechanical process in the same structure. *See also* **motor protein**.

mechanotransduction the activation of an intracellular effector pathway by a mechanical force, as in stretch receptors in the walls of the heart and blood vessels.

meconium antigen *see* **carcinoembryonic antigen**.

MECP2 *abbr. for* methylCpG-binding protein 2.

media 1 a plural of **medium**. **2** *(in morphology) or* **tunica media** the middle layer of the wall of a blood or lymph vessel.

medial 1 of, situated in, or towards the middle. **2** of, or pertaining to, a **media** (def. 2).

median 1 *(in statistics)* the centre value of any series of numbers, measurements, values, etc. when these are arranged in order from the lowest value to the highest value (with an even-numbered series, the mean of the two central values is taken); i.e. half the members of the series have values greater than that of the median and half have values smaller than that of the median. *Compare* **mean**. **2** of, pertaining to, situated in, or pointing towards the middle. **3** *(in biology)* of or pertaining to the plane that divides an organism, organ, etc. into two symmetrical parts.

median effective dose *abbr*.: ED$_{50}$ *or* ED50; the dose of a drug, agonist, or other agent that is effective in 50% of the test objects.

median infectious dose *abbr*.: ID$_{50}$ *or* ID50; the dose of bacteria, viruses, or other infective agents that produces infection in 50% of the test objects.

median lethal dose *abbr*.: LD$_{50}$ *or* LD50; the dose of bacteria, viruses, toxic substances, or other agents that causes death of 50% of the test objects.

mediated diffusion *or, somethimes,* **facilitated diffusion** a specific membrane transport process on a transporter (carrier) that does not require coupling with energy and, in the case of nonelectrolytes, that leads to equal concentrations of the transported substance on both sides of the membrane.

mediated transport the transport of a substance across a (biological) membrane that requires the participation of one or more transporting agents (or **carriers** (def. 3)). *See also* **facilitated diffusion**.

mediator *or* **MED** a multiprotein complex (20–30 polypeptides, ≈2 MDa) that acts as a transcriptional coactivator of yeast. It bridges general initiation factors that bind to promoters of protein genes, and the C-terminal domain of the largest subunit of RNA polymerase II. The complex is distinct from that composed of general transcriptional activators, or of upstream stimulatory activity (USA) factors. Several mammalian complexes that have mediator-like transcriptional activity have been characterized. The human equivalents are **TRAP** and **SMCC**.

medical of, or pertaining to, the science or practice of medicine.

medical informatics *see* **informatics**.

medical subject headings *abbr*.: MeSH; the National Library of Medicine's controlled vocabulary of medical and scientific terms used to index articles in the bibliographic database MEDLINE. MeSH terms provide a consistent method of information retrieval when different terminology has been applied to the same concepts.

medicinal pertaining to or possessing therapeutic properties.

medicine 1 the science or practice of preventing, diagnosing, alleviating, and curing disease. **2** *a common term for* a pharmaceutical substance or mixture.

medin a 50-residue polypeptide, derived from the protein lactadherin, that is produced by aortic smooth muscle cells. It is the commonest form of human amyloid protein but unlike other amyloidogenic peptides it is not degraded by insulinase.

medium (*pl.* **media** *or* **mediums**) **1** the surrounding substance in which organisms or cells are studied or preserved. **2** the continuum in which particular chemical entities and their reactions are studied, commonly the solvent together with any nonreacting solutes. **3** any of the materials in which a chromatographic or an electrophoretic separation is effected. **4** the continuum through which electromagnetic radiation is considered to be transmitted. **5** *see* **culture medium**.

medium-chain acyl-CoA dehydrogenase deficiency the most common defect of mitochondrial beta oxidation in humans, due to deficiency of acyl-CoA dehydrogenase (*see* **beta-oxidation system**). It is characterized by hypoglycemic coma provoked by fasting, hepatic dysfunction, and sudden death. There is abnormal accumulation and urinary excretion of C_6–C_{12} fatty acids and their dicarboxylic acids. Many mutations at the locus 1p31 cause the deficiency.

MEDLINE *see* **bibliographic database**.

medulla (*pl.* **medullas** *or* **medullae**) the innermost part of an organ, tissue, or structure; marrow, pith. —**medullary** *adj.*

MEF *abbr. for* myocyte enhancement factor.

mega+ 1 *symbol*: M; an SI prefix denoting 10^6 times. **2** a prefix used in computing to indicate a multiple of 2^{20} (i.e. 1 048 576), as in megabyte. **3** *a general prefix* denoting large size.

Mega-8 *or* **Omega** the octanoyl amide of *N*-methylglucamine (i.e. 1-methylamino-1-deoxy-D-glucitol); a water-soluble, nondenaturing detergent (CMC = 58 mM) useful for membrane research. It is one of a series, which also comprises Mega-9, the nonanoyl derivative (CMC = 19–25 mM), and Mega-10, the decanoyl derivative (CMC = 6–7 mM).



Mega-8 *n* = 6
Mega-9 *n* = 7
Mega-10 *n* = 8

megabase *symbol*: Mb; a unit of length of a polynucleotide equal to 10^6 base residues in a single-stranded polynucleotide or 10^6 base pairs in a double-stranded polynucleotide.

megadalton *symbol*: MDa; a unit of mass equal to 10^6 **daltons**.

megakaryocyte a large (diameter 40–150 μm), polyploid cell that gives rise to the blood platelets by budding of its cytoplasm. It contains, on average, four times the diploid number of chromosomes in a large, usually lobulated nucleus. Megakaryocytes are found in bone marrow, lung, and to a lesser extent in other tissues.

megalin *an alternative name for* **LRP2**.

megaloblastic anemia any of a group of disorders characterized by an abnormality of red cell development in the bone marrow. There is an accumulation of primitive cells, with failure of nuclear development, while cytoplasmic development, including hemoglobinization, continues; oval macrocytes appear in the blood. Vitamin B$_{12}$ or folate deficiency, or abnormality of vitamin B$_{12}$ or folate metabolism, is a frequent cause, but drug treatment (with antifolates, e.g. methotrexate, or drugs that interfere with DNA synthesis, e.g. cytarabine (β-cytosine arabinoside), hydroxyurea, AZT) or certain leukemias may also be causes.

megatomic acid *see* **tetradecadienoic acids**.

meiosis *or* **reduction division** a process by which the nucleus of a diploid cell divides twice with the formation of four daughter haploid cells, each containing half the number of chromosomes of the parent nucleus. Meiosis occurs during the formation of gametes from diploid cells and at the beginning of haplophase in those organisms that exhibit alternation of generations. Meiosis involves two rounds of cell division. Prophase in the first division proceeds as follows. Chromosomes first become visible as elongated threads during **leptotene**; by this time each chromosome has already replicated to form two identical sister chromatids. During **zygotene** each chromosome pairs with its homologue; the two become aligned and the **synaptonemal complex** develops between them. When synapsis is complete **pachytene** is said to have begun; it is during this stage that **crossing over** occurs between a chromatid in one partner and another chromatid in the homologous chromosome. The points of crossing over, or **chiasmata**, first become visible as the two chromosomes begin to separate in **diplotene**, when the synaptonemal complex dissolves. The final phase of prophase I, **diakinesis**, is the transition into metaphase I, which is analogous to mitotic metaphase and is followed by anaphase I and telophase I, producing two daughter cells each with one copy of each chromosome (each still made up of two sister chromatids). A second division quickly follows, comprising an interphase (without chromosome replication), and mitosis-like prophase II, metaphase II, anaphase II, and telophase II to separate the two chromatids in each chromosome. *Compare* **mitosis**. —**meiotic** *adj.*

MEK *abbr. for* **1** methyl ethyl ketone. **2** mitogen-activated ERK-activating kinase; a protein kinase with dual specificity for threonine and tyrosine. During intracellular signalling by insulin it phosphorylates these residues in MAP kinases (*see* **ERK**).

Mel-18 *or* ***Zfp144*** a gene, first identified in a melanoma, that encodes a nuclear RING finger protein. It is related to *Polycomb* of *Drosophila*, which controls expression of homeotic genes. The gene is widely expressed during mouse embryogenesis.

melanin any of the black or brown pigments of high molecular mass formed by the action of oxidase enzymes on phenols. They are widely distributed in plants and animals, are derived from tyrosine, and are usually bound to protein. Plant melanins are called **catechol melanins** because they yield catechol on alkali fusion; animal melanins, termed **eumelanins**, arise from the formal polymerization of indole-5,6-quinone and thus, in contrast to plant melanins, contain nitrogen. **Pheomelanin** is red and/or yellow and is derived from tyrosine and cysteine, as an alternative to eumelanin production in melanosomes. **—melanic** *adj.*

melanin concentrating hormone *abbr*.: MCH; a neuropeptide (19 amino acids, one disulfide bond) of the intermediate lobe of the pituitary gland of teleost fishes and of the lateral hypothalamus of mammals. Infused into mice it stimulates feeding behaviour. The precursor of mammalian MCH also contains a 13-residue peptide homologous to CRH, and a 19-residue peptide homologous to GHRH. The physiological role of MCH is unclear. It acts on a G-protein-coupled membrane receptor that activates phospholipase C.

melanocortin *a generic term for* either of the peptide hormones **melanotropin** or **corticotropin**, derived from their common precursor **proopiomelanocortin.** Although they have distinct functions (melanotropin in control of melanocyte growth and pigment formation, corticotropin in stimulating the adrenal cortex to produce glucocorticoids and aldosterone), they also share functions in, e.g., immunomodulation and antipyretic activity; because corticotropin can regulate melanocyte function, it is possible also to regard it as a melanotropin.

melanocortin receptor any of a family of G-protein-associated membrane receptors that on binding of ligand activate adenylate cyclase. Several types of receptor have been identified. **Melanocortin-1 receptor** (*other names*: melanocyte-stimulating hormone receptor; melanotropin receptor) and **melanocortin-2 receptor** (*other name*: adrenocorticotropic hormone receptor) are both located on melanocytes and adrenocortical tissue. **Melanocortin-3 receptor** and **melanocortin-4 receptor** are both located on brain, placental, and gut tissue, whereas **melanocortin-5 receptor** is expressed in brain but not melanocytes. Human ACTH receptor is 39% identical with the human MSH receptor. Receptors 1–3 and 5 respond to α-, β-, and γ-MSH and ACTH, melanocortin-4 receptor being specific to a common heptapeptide core sequence MGHFRWG. However, despite similarities in structure and action on melanocortin receptors, physiologically MSH has no ACTH-like activity. These are more closely related to the Δ^9-tetrahydrocannabinol receptor (*see* **cannabinoid receptor**) than to other peptide and amine G-protein-associated receptors. Mutations that lead to deficiency of melanocortin-4 receptor lead to severe obesity in childhood.

melanocyte a type of pigmented cell that can synthesize and store **melanin** in melanosomes. Melanocytes occur in the skin and in the pigmented layer of the eye. *See also* **melanophore**.

melanocyte regulatory factor *an alternative name for* **melanotropin regulatory factor**.

melanocyte-stimulating hormone *abbr*.: MSH; any of three peptide hormones, α-MSH, β-MSH, and γ-MSH, produced primarily by the intermediate lobe of the pituitary gland, that cause dispersal of melanosomes in **melanophores** of poikilothermic vertebrates, but whose physiological function in mammals is not understood. Their sequences are all contained within that of **proopiomelanocortin** (the common precursor of corticotropin and β lipotropin). α-MSH is a tridecapeptide amide (usually acetylated on the N-terminal serine residue) that corresponds to residues 1–13 of corticotropin and has the same sequence in almost all animals studied. β-MSH (*formerly called* **intermedin**), not believed to be present in humans, corresponds to residues 41–58 of β lipotropin and shows greater structural variability. γ-MSH, a putative hormone, is a peptide of variable length that corresponds to part of the so-called cryptic region of proopiomelanocortin. *See also* **melanotropin**.

melanocyte-stimulating hormone receptor *see* **melanotropin receptor**.

melanocyte-stimulating-hormone regulatory factor *or* **melanocyte-stimulating-hormone regulatory hormone** *an alternative name for* **melanotropin-regulatory factor**.

melanocyte-stimulating-hormone release-inhibiting factor (*abbr*.: MSHIF *or* MSHRIF) *or* **melanocyte-stimulating-hormone release-inhibiting hormone** (*abbr*.: MSHIH *or* MSHRIH) *an older name for* **melanostatin**.

melanocyte-stimulating-hormone releasing factor (*abbr*.: MSHRF) *or* **melanocyte-stimulating-hormone releasing hormone** (*abbr*.: MSHRH). *See* **MSHRH**.

melanoliberin *the recommended name for* melanocyte-stimulating-hormone releasing hormone (*see* **MSHRH**).

melanophilin a protein found on the inner surface of the plasma membrane of melanocytes that, with the small GTPase Rab27a, forms a receptor for myosin-Va and mediates movement of melanosomes.

melanophore a type of **melanocyte** that occurs especially in the skin of poikilothermic vertebrates. The cell's contractile properties allow rapid internal translocation of melanosomes, thereby bringing about rapid adaptive changes in the skin coloration of such creatures.

melanopsin an opsin-based photopigment present in retinal ganglion cells of various animals (frog, mouse, rat). It colocalizes with pituitary adenylyl cyclase-activating peptide (PAPEP), and is a component of the photoreceptive system for circadian rhythms.

melanosome a type of cell organelle that occurs in **melanocytes** and contains tyrosinase and other enzymes required for synthesis of melanin. Melanosomes are specialized lysosomes, sharing with them many proteins unrelated to melanin synthesis.

melanostatin a peptide that inhibits release of melanotropin, and is identical with **neuropeptide Y**. *Other names*: melanotropin release-inhibiting factor (*abbr*.: MIF *or* MRIF); melanotropin release-inhibiting hormone (*abbr*.: MIH *or* MRIH); melanocyte-stimulating-hormone release-inhibiting factor (*abbr*.: MSHIF *or* MSHRIF); melanocyte-stimulating-hormone release-inhibiting hormone (*abbr*.: MSHIH *or* MSHRIH).

melanotransferrin *see* **transferrin**.

melanotropic *or* **melanotrophic** describing any agent that causes dispersal of melanosomes within **melanophores**.

melanotropin *or (formerly)* **melanotrophin** *a generic term for* any melanotropic hormone of the anterior pituitary that is derived from **proopiomelanocortin**. The term embraces α, β, and γ **melanocyte-stimulating hormones**. *See also* **melanocortin**.

melanotropin receptor any of a family of receptors that bind **melanotropins**. *See also* **melanocortin receptor**.

melanotropin-regulatory factor *or* **melanotropin-regulatory hormone** *an older generic name for* either **MSHRH** or **melanostatin**. *Other names*: melanocyte-regulatory factor; melanocyte-stimulating-hormone regulatory factor; melanocyte-stimulating-hormone regulatory hormone.

melanotropin release-inhibiting factor (*abbr*.: MIF *or* MRIF) *or* **melanotropin release-inhibiting hormone** (*abbr*.: MIH *or* MRIH) *an older name for* **melanostatin**.

melanotropin-releasing factor (*abbr*.: MRF) *or* **melanotropin-releasing hormone** (*abbr*.: MRH) *see* **MSHRH**.

MELAS *abbr. for* mitochondrial encephalomyopathy, lactic acidosis, and strokelike episodes; a mitochondrial disease of humans commonly associated with point mutations in mitochondrial DNA encoding a leucyl-tRNA.

melatonin *N*-acetyl-5-methoxytryptamine; a neuroendocrine tryptophan derivative synthesized in the pineal gland from 5-hydroxytryptamine; its synthesis exhibits a circadian photoperiodism. In amphibia, it has an action opposite to that of **melanocyte-stimulating hormone**. It stimulates the aggregation of melanosomes in melanophores, thus lightening the skin. In mammals it seems to regulate circadian rhythms, sleep, and mood, and may have effects on the reproductive system. It acts through G-protein-associated membrane receptors of which type 1 inhibit adenylate cyclase, and type 2 activate phospholipase C. It is inactivated by 6-hydroxylation and is excreted in conjugated form. When used as a drug it is reputed to control jet lag.



melezitose the trisaccharide, *O*-*α*-D-glucopyranosyl-(1→3)-*O*-*β*-D-fructofuranosyl-(2→1)-*α*-D-glucopyranoside; a component of the sweet exudations from many plants and of the leaves of some trees after insect attack.

melibiase *see* **glucosidase**.

melibiose the disaccharide, 6-*O*-*α*-D-galactopyranosyl-D-glucose; it occurs as a constituent of the trisaccharide, **raffinose**, and in the exudates and nectaries of a number of plants.



melissyl *an alternative name for* **myricyl**.

melitriose *see* **raffinose**.

melittin a strongly basic, sulfur-free, hemolytic, 26-residue peptide amide, often formylated on its N-terminal glycine residue. It comprises 40–50% of the dry mass of the venom of the honey bee, *Apis mellifera*. The hemolytic activity of melittin appears to be related to the ordering of its amino-acid residues, which renders the polypeptide markedly surface active.

melting **1** the (reversible) act or process of liquefaction of a solid through the action of heat (or change in pressure). **2** the increase (reversible and usually fairly abrupt) of molecular mobility of lipids in a biological membrane or artificial lipid bilayer with increase of temperature above the transition temperature. **3** *or* **thermal denaturation** the transition (usually fairly abrupt but not necessarily reversible) of a biopolymer from a highly ordered to a less highly ordered state with increase in temperature. Examples are the heat-induced change from a helical to a random coil structure in a protein or a duplex nuleic acid. *See also* **localized melting**, **melting temperature**.

melting curve *an alternative name for* **thermal denaturation profile**.

melting point *abbr*.: m.p.; the temperature at which the solid and liquid phases of a substance are in equilibrium at a given pressure. Melting points are usually given for standard atmospheric pressure, i.e. 101 325 Pa.

melting temperature *symbol*: T_m *or* t_m *or* Θ_m; the temperature at which a conformational transition brought about by change in temperature (e.g. of a macromolecule in solution) is 50% complete. For example, it is the temperature (°C) at which 50% of a target DNA sequence is hybridized to oligonucleotides present in molar excess. It follows therefore that $T_\mathrm{m} = \Delta H_\mathrm{ot}/\Delta S_\mathrm{ot}$, where ΔH_ot and ΔS_ot are, respectively, the standard enthalpy difference and the standard entropy difference for the transition. In the denaturation of DNA the melting temperature is taken as the midpoint of the **helix-to-coil transition**.

MEM *abbr. for* **1** minimum essential medium. **2** minimum Eagle's medium.

memapsin2 *see* **secretase**.

membrane any thin sheet or layer, often separating two compartments. Membranes may be natural or artificial, and are sometimes soft and pliable. *See also* **cell membrane**, **semipermeable membrane**, **unit membrane**. **—membranous** *adj.*

membrane attack complex *see* **MAC** (def. 1).

membrane attack complex inhibition factor (*abbr*.: MACIF) *or* **CD59 glycoprotein precursor**; *other names*: MAC-inhibitory protein, protectin, membrane inhibitor of reactive lysis (*abbr*.: MIRL); a surface antigen of T cells that potently inhibits the membrane attack complex (*see* **MAC**). It is complexed with a GPI anchor.

membrane-bound describing any component that is not readily dissociable from preparations of cellular membranes *in vitro* and/or that appears to be an integral part of a membrane in an intact cell.

membrane-bound *O*-acyltransferase *abbr*.: MBOAT; a widely distributed superfamily of integral membrane proteins that have *O*-acyltransferase activity. They typically have 8–10 transmembrane segments and transfer organic acids (especially fatty acids) to the hydroxyl group of a membrane-embedded acceptor. MBOATs share a region of conserved polar residues within and adjacent to the membrane, and an invariant histidine within a hydrophobic sequence. Examples include **sterol *O*-acyltransferase** (yeast and human), **diacylglycerol *O*-acyltransferase** (mouse and *Arabidopsis*), and porcupine protein (*Drosophila*).

membrane channel a protein complex that specifically facilitates the passive diffusion of small molecules through a membrane; particularly applied to **ion channels**.

membrane electrode any electrode that incorporates a membrane in its structure, e.g. a glass electrode, an ion-exchange electrode, or an oxygen electrode.

membrane filter *or* **filter membrane** any membrane consisting of a thin polymeric structure with pores of a defined and very uniform size that is used for filtration; a disk or piece of such membrane.

membrane filtration the act or process of separating suspended particles from a liquid, or of separating macromolecules from their solvent, with a **membrane filter**.

membrane-intrusive describing a peptide loop, situated between two neighbouring transmembrane segments of an integral membrane protein, that is forced back into the membrane but without penetrating it. An example is the **P domain** of shaker-type subunits of ion channels.

membrane-organizing spike protein *see* **moesin**.

membrane osmometer *see* **osmometer**.

membrane potential the electric potential existing across any membrane arising from charges in the membrane itself and from the charges present in the media on either side of the membrane. Plant and animal plasma membranes maintain a potential, the cell interior being more negative than the exterior. In plants this arises mainly from the activity of electrogenic pumps, whereas in animals passive ion movements predominate in creating this potential. The resting potential varies from –20 mV to –200 mV according to cell type; for a neuron it is about –70 mV. In plants, **H^+-transporting ATPases** pump protons out of the cell, thus maintaining a pH gradient across the plasma membrane. This is involved in symport of carbohydrates and amino acids into the cell. In animals, the Na^+,K^+-ATPase exchanges intracellular Na^+ for extracellular K^+, maintaining the high intracellular K^+ concentration and low intracellular Na^+ concentration. K^+-leak channels in the plasma membrane allow K^+ to escape until counteracted by the electrical potential and excess of intracellular negative charge that results. An electrochemical gradient across the mitochondrial inner membrane is created by proton-pumping cytochromes. *See also* **chemiosmotic coupling hypothesis**, **Nernst equation**.

membrane protein any protein that is normally closely associated with a cell membrane, owing to the properties of the protein and the method by which it is synthesized. **Integral proteins** contain hydrophobic regions that traverse the lipid bilayer; in some cases, the protein has only one such region, with hydrophilic domains on either side of the membrane; in other cases, where several such regions are present, a polypeptide may traverse the membrane several times (*see* **seven-transmembrane-domain proteins**). Other proteins are bound to the membrane by a **gpi anchor**, and others by the hydrophobic moiety of a fatty-acyl group (*see* **myristoylation**) or a prenyl group (*see* **prenylation**). Other proteins may be more loosely attached, mainly by ionic forces (peripheral proteins).

Type I membrane proteins have a single (monotopic) transmembrane domain, with the C terminus on the cytoplasmic side. **Type II membrane proteins** have a single transmembrane domain with an N terminus that is cytoplasmic. **Type III membrane proteins** traverse the membrane several times (polytopic). **Type IV membrane proteins** are multimers of subunits that when assembled make a transmembrane channel. Proteins attached to the membrane only by covalently bound lipids are classified as **type V**, and those that are anchored by one or more transmembrane domains and also by a GPI anchor are designated **type VI**. The structures of only a few membrane proteins have been solved at high resolution (7 Å or better). Except for these it is not known whether the transmembrane domain is helical.

membrane receptor any protein, situated in or on a cell membrane, that binds extracellular signalling molecules (e.g. hormones, growth factors) and transduces the signal to produce intracellular effects.

membrane skeleton the protein network of an erythrocyte membrane, defined operationally as the insoluble residue that remains after extraction of either intact red cells or their isolated membranes with the nonionic detergent Triton X-100.

membrane teichoic acid any **teichoic acid** found in the protoplast of a bacterial cell as opposed to any found exclusively in the cell wall or in capsular material. Such substances commonly are glycerol teichoic acids, and they occur, covalently attached to lipid, in the cell membrane and probably also in mesosomes.

membrane transport any movement of substances across a (biological) membrane.

membrane type-serine protease 1 *see* **MT-SP1**.

memory cell any of a population of long-lived **T** or **B lymphocytes** that have previously been stimulated by antigen, and make an accelerated response to that antigen if they encounter it again. Memory B cells carry surface immunoglobulin G as their antigen receptor; this is of higher affinity than on virgin lymphocytes. Memory T cells may be distinguishable by high expression of CD44.

MEN *abbr. for* multiple endocrine neoplasia; any of two distinct genetic syndromes in which multiple endocrine neoplasias occur. MEN1 is due to numerous loss-of-function mutations in the nuclear protein **menin**, with usually benign tumours of anterior pituitary, parathyroid, and enteropancreatic neuroendocrine cells. MEN2 is due to gain-of-function mutations in the *ret* protooncogene, which is expressed as a cell surface glycoprotein that is a member of the receptor protein kinase family. It usually presents as medullary thyroid carcinoma, often associated with pheochromocytoma or parathyroid adenoma.

menadione 2-methyl-1,4-naphthalenedione; 2-methyl-1,4-naphthoquinone; vitamin K_3; a synthetic naphthoquinone derivative possessing the physiological properties of **vitamin K**.



menaquinone *abbr.*: MK; *the class name for* a series of 2-methyl-3-all-*trans*-polyprenyl-1,4-naphthoquinones, also known as vitamins K_2 (*see* **vitamin K** for function). They are antihemorrhagic vitamins, present in bacteria, and possess 1–13 prenyl residues, the number of prenyl residues being indicated by a suffixed Arabic number, e.g. menaquinone-6 (MK-6; *also known as* **farnoquinone**). [From methyl naphthaquinone.]



menaquinone

Mendelian **1** of or relating to Gregor Johann Mendel (1822–84), Austrian monk and botanist, or following his laws of heredity. **2** one who adheres to or supports **Mendel's laws of heredity**.

Mendelian population a community of sexually interbreeding individuals.

Mendel's laws of heredity the principles of heredity proposed by Gregor Johann Mendel (1822–84), Austrian monk and botanist, on the basis of his researches on hybridization of peas to explain the behaviour of factors (now called genes) that govern the transmission of inherited characters from generation to generation. On the basis of modern knowledge, Mendel's first law, the **law of segregation**, states that every somatic cell carries a pair of allelic genes for each character and that the two genes in each pair separate during meiosis so that each gamete carries only one gene from each pair. Mendel's second law, the **law of independent assortment**, states that the separation of members of any pair of allelic genes occurs independently of every other pair provided they are not linked.

menin a ubiquitously expressed nuclear protein (human, 610 amino acids) that contains two nuclear localization signals at the C-terminus. It binds and inhibits the transcription factor JunD and may be a tumour suppressor. Numerous mutations are associated with the autosomal dominant multiple endocrine neoplasia type 1 (MEN1). *See* **MEN**.

meniscus (*pl.* **menisci**) the curved upper surface of a liquid column that is concave when the containing walls are wetted by the liquid (contact angle <90°) or convex when not (contact angle >90°), sometimes extended to include a flat surface (contact angle = 90°). **—meniscoid** *adj.*

meniscus depletion (sedimentation equilibrium) method *or* **Yphantis method** a variant of the sedimentation equilibrium method for determining the relative molecular mass of a macromolecule in which centrifugation is effected at a speed high enough to render the concentration of the solute at the meniscus essentially zero; the concentrations of solute along the length of the cell are proportional to the difference in refractive index at any point from that at the meniscus. The method is especially useful for monodisperse systems.

Menkes ATPase *see* **Menkes disease**.

Menkes disease *or* **kinky-hair syndrome** *or* **steely-hair syndrome** a rare X-linked disorder characterized by cerebral and cerebellar degeneration, abnormalities of connective tissue, and kinky hair. It results from mutations in the gene for the Menkes ATPase, a copper transporter involved in the intestinal absorption of copper. [After John H. Menkes (1928–), US neurologist.]

menopausal gonadotropin *or* **human menopausal gonadotropin** (*abbr.*: hMG *or* HMG) *another name for* **menotropin**.

menotropin *or* **menotrophin** *other name*: human menopausal gonadotropin; *abbr.*: hMG *or* HMG; a gonadotropin with **follicle-stimulating hormone** and **luteinizing hormone** activity, isolated from the urine of postmenopausal women and used to stimulate ovulation in infertility. One proprietary name is Pergonal.

MEP *abbr. for* major excreted protease; *see* **cathepsin L**.

meprin A EC 3.4.24.18; *other names*: endopeptidase-2; endopeptidase MEP-1; a type 2 transmembrane serine protease of kidney and intestinal brush borders. Zinc is a cofactor. It catalyses the hydrolysis of proteins and peptides on the C-terminal side of hydrophobic residues, and is a homotetramer of α or β subunits.

meq *or* **mEq** *symbol for* milliequivalent (use deprecated, mmol recommended).

mer *or* **constitutional unit** the repeating unit of a polymeric molecule.

+mer *suffix forming nouns (in chemical nomenclature)* denoting specific kinds or classes of polymer (e.g. hexamer, oligomer) or isomer (e.g. enantiomer, epimer, tautomer). **—+meric** *adj.*; **+merism** *n.*

mer the symbol for genes of the *mer* operon whose products confer (or regulate) mercury resistance. For example, the bacterium *Serratia marcescens* has several *mer* products. (1) MerA is mercury(II) reductase (EC 1.16.1.1); *systematic name*: Hg:NADP$^+$ oxidoreductase; one of the very rare enzymes with metal substrates, it catalyses the reduction by NADPH of Hg^{2+} to form Hg and NADP$^+$. It is a flavoprotein (FAD) with redox-active disulfide bonds, and is responsible for volatilizing mercury as Hg(0). (2) MerB is alkylmercury lyase (EC 4.99.1.2); *systematic name*: alkylmercury mercuric-lyase; it catalyses a reaction between RHg$^+$ and H$^+$ to form RH and Hg^{2+}. This enzyme cleaves the carbon–mercury bond of organomercurials and the Hg^{2+} product is detoxified by MerA. (3) MerR is a **helix-turn-helix** regulatory protein. In the absence of mercury, MerR represses transcription by binding tightly to the *mer* operator region; when mercury is present the dimeric complex binds a single ion and becomes a potent transcriptional activator, while remaining bound to the *mer* site. *mer* operons are encoded by a number of plasmids that have been cloned into *Escherichia coli,* e.g. Tn21 of *Shigella flexneri*, Tn501 from *Pseudomonas aeruginosa* (these two lack the organomercury lyase gene and so confer resistance only against inorganic mercury salts), and pDU1358 from *S. marcescens* (which includes *merB* and thus encodes a broad-spectrum *mer* operon).

mer+ *prefix (in coordination compound nomenclature)* denoting a **meridional** (def. 2) arrangement of ligands.

MER *abbr. for* medium reiteration frequency repeat; *other usage*: medium reiteration frequency interspersed repetitive elements (*abbr*.: MER elements). They consist of repeated base sequences in eukaryotic genomes. More than fifty human repetitive families are known, of which most represent MERs. The latter have copy numbers per genome ranging from hundreds to thousands, and length ranging from tens to a few hundred base pairs. They are of unknown function, but some may play a role in regulation of gene expression and others may affect genome stability and gene rearrangements.

mercapt+ *a variant form of* **mercapto+** *(sometimes before a vowel).*

mercaptan *an old name for* **thiol**.

mercapto+ *or (sometimes before a vowel)* **mercapt+** *comb. form (in chemical nomenclature)* indicating the presence of an unsubstituted thio group, –SH.

2-mercaptoethanol HO–CH$_2$–CH$_2$–SH; 2-hydroxyethylmercaptan; a sulfhydryl reducing agent often used in buffers to maintain protein sulfhydryl groups in the reduced state.

mercaptopurine *or* **6-mercaptopurine** *abbr*.: 6-MP; *symbol*: Shy; thiohypoxanthine; 6-purinethiol; an immunosuppressive and antineoplastic drug useful in organ transplantation and in the treatment of some leukemias. It is a substrate for guanine-hypoxanthine phosphoribosyltransferase, which converts it to **6-mercaptopurine ribonucleoside** (or 6-thioinosine; *symbol*: Sno *or* M *or* sI).

mercapturic acid any *S*-alkyl- or *S*-aryl-*N*-acetylcysteine; such compounds are formed as detoxification products in mammals. The initial reaction involves conjugation with the thiol group of glutathione catalysed by a **glutathione transferase** to form the *S*-radyl-glutathione (*see* **radyl**). Glutamic acid and glycine are then removed in the kidney, and the resulting mercapturic acid is excreted in the urine.

mercurate to treat or mix with mercury; to introduce mercury into an organic compound. **—mercuration** *n.*

mercurial **1** of, containing, like, or pertaining to mercury. **2** any compound containing mercury, especially one used in medicine and/or agriculture; *see also* **organomercurial**.

mercuric perchlorate Hg(ClO$_4$)$_2$; a substance used in solution to trap ethylene.

mercury II reductase EC 1.16.1.1; product of the *Serratia marcescens merA* gene (*see* ***mer***).

mercury-vapour lamp *or* **mercury-discharge lamp** *or (informally)* **mercury lamp** a lamp that emits bluish-green light rich in ultraviolet radiation, produced by passing an electric discharge through mercury vapour, often at low pressure. It is useful for provoking or investigating fluorescence, as a light source for a **polarimeter**, and as a source of sterilizing radiation.

meridian **1** any line on the surface of a sphere or spheroid that is orthogonal to its equator, or any corresponding line in a projection of part of the surface of a sphere or spheroid onto a planar or cylindrical surface. **2** in a fibre diagram produced by X-ray diffraction, the vertical axis on the film that corresponds to the *z* axis in reciprocal space.

meridional **1** of, along, pertaining to, or resembling a meridian. **2** describing the geometrical isomer of a coordination compound of octahedral configuration in which three ligands in the coordination sphere are in such a relationship that one is *cis* to the two others, which are themselves *trans*. Such an isomer is designated by prefixing *mer*- to the chemical name.

meristem a region of tissue in a plant that is composed of one or more undifferentiated cells that are capable of undergoing mitosis and differentiation, and thereby of effecting growth and development of a plant by giving rise either to more meristem or to specialized tissue. In vascular plants, meristems may be apical (located at the tips of growing roots and shoots) or lateral (arranged circumferentially and constituting the cambium). **—meristematic** *adj.*

merlin *or* **neurofibromatosis type 2 (tumour suppressor)** (*abbr*.: NF2) *or* **Schwannomin** a membrane-stabilizing protein from fetal brain and other tissues, such as kidney, lung, and breast. It is similar to **ezrin** and **talin**. It is a tumour suppressor of the **TERM** family. In humans, it is encoded by a gene on chromosome 22q12.

mero+ *comb. form* denoting part, partly, or partial.

merocrine **1** describing a type of secretion that does not entail disintegration of the secretory cell. **2** describing a gland made up of such cells. *Compare* **apocrine**, **eccrine**, **holocrine**.

merodiploid a haploid organism that is diploid for a small region of the chromosome, i.e. a partial diploid.

meromyosin either of the two fragments, **heavy meromyosin** and **light meromyosin**, produced by brief treatment of myosin with trypsin or certain other proteases.

MEROPS *see* **specialist database**.

mero-receptor the smallest subunit of a receptor for a (steroid) hormone that contains an intact hormone-binding site. The biological significance of mero-receptors is unclear; they may be artefacts of experimental cellular disruption or products formed by proteolysis associated with the termination of (steroid) hormone action.

merosin a tissue-specific-basement-membrane protein, and the M chain of **laminin**. It is covalently associated with laminin B chains and, like laminin, is cruciform. It shares similarity with the C-terminal part of the laminin A chain.

merozygote any bacterial cell that is partly diploid and partly haploid, formed by conjugation, transduction, or transformation. It contains one complete genome, that of the recipient organism, and a fragment of a second genome, derived from the donor.

MERRF *abbr. for* myoclonus epilepsy with ragged-red fibres; a mitochondrial disease of humans characterized by abnormally shaped mitochondria (which sometimes contain paracrystalline inclusions) in skeletal muscle fibres. It is commonly associated with point mutations in the mitochondrial DNA for lysyl-tRNA.

Merrifield method *an alternative name for* **solid-phase peptide synthesis**. [After Robert Bruce Merrifield (1921–), US peptide chemist and biochemist.]

Merrifield resin a beaded reactive synthetic resin designed for use in the Merrifield method (i.e. **solid-phase peptide synthesis**).

mersalyl *pharmaceutical name of* sodium *o*- [3-(hydroxymercuri)-2-methoxypropyl]carbamoyl phenoxyacetate; a mercury-containing derivative of salicylamide. It is a diuretic drug useful as an inhibitor of the exchange of phosphate and hydroxide ions across the inner mitochondrial membrane.



mes+ *a variant form of* **meso+** *(sometimes before a vowel).*

Mes *or* **MES** *abbr. for* and *trivial name of* 2-(*N*-morpholino)ethanesulfonic acid; a **Good buffer substance**, pK_a (20°C) = 6.15.

mesaconic acid (*E*)-2-methyl-2-butenedioic acid; methylfumaric acid; an intermediate in the fermentation of glutamate to acetyl-CoA by *Clostridium tetanomorphum.*

mescaline 3,4,5-trimethoxyphenylethylamine; a hallucinogenic and sympathomimetic drug isolated from the flowering heads of the mescal cactus (*Lophophora williamsii*), also known as peyotle or peyote.

Meselson–Stahl experiment a landmark experiment, reported by Meselson and Stahl in 1958, that provided convincing evidence for semiconservative replication of DNA in bacteria. Cultures of *Escherichia coli* were grown in a medium containing $^{15}NH_4Cl$ (96.5% isotopic purity) as sole nitrogen source for many generations so as to label the DNA with heavy nitrogen. The cells were then transferred to a medium containing $^{14}NH_4Cl$ and the culture sampled for several subsequent generations. Cell lysates were subjected to density-gradient centrifugation and the positions of the DNA bands in the gradients located by UV absorption. Initially the DNA appeared as a single band corresponding to DNA containing heavy nitrogen; subsequently a second band of DNA, containing equal amounts of heavy and light nitrogen, appeared, and one generation after transfer to natural ammonium chloride all the DNA was this hybrid form. After two generations only hybrid and natural DNA was present. Furthermore, the separated strands of this hybrid DNA proved to contain all heavy nitrogen or all normal nitrogen only. [After Matthews Meselson (b. 1930), US molecular biologist, and Franklin William Stahl (b. 1929), US geneticist.]

mesenchyme immature, unspecialized connective tissue found in the early embryo of animals. It consists of cells embedded in a tenuous extracellular matrix. **—mesenchymal** *adj.*

mesentery **1** the double-layer fold of peritoneum serving to hold the abdominal viscera in position. **2** any of the muscular partitions extending inwards from the body wall in coelenterates. **—mesenteric** *adj.*

MeSH *abbr. for* medical subject headings.

Me_3Si *symbol for* the trimethylsilyl group.

meso describing a bridging atom or group between two rings in a polycyclic molecule.

meso+ *or (sometimes before a vowel)* **mes+** *comb. form* denoting middle, or intermediate.

meso- *abbr.*: *ms-*; *prefix* (*in chemical nomenclature*) designating a substance whose individual molecules contain equal numbers of enantiomeric groups, identically linked, but no other chiral group; i.e. a substance whose molecules are optically inactive because of internal compensation; e.g. *meso*-compound, *meso*-cystine. *Compare* ***racemo-***.

***meso*-carbon atom** *a term suggested for* any prochiral carbon atom in an organic molecule whose valence bonds are linked to two identical groups, *a*, and to two other dissimilar groups, *b* and *d*. The resulting molecule, C*aabd*, has a plane of symmetry and thus the carbon atom is not chiral; however, the two *a* groups are not geometrically equivalent but bear a mirror-image relationship to each other, and they may react at different rates with chiral reagents or in enzymic reactions. The term is now obsolete. See **prochiral**.

mesoderm the middle of the three primary germ layers of a triploblastic animal embryo, lying between the ectoderm and endoderm. It is the source of bone, muscle, connective tissue, the inner layer of the skin, and other structures. **—mesodermal** *adj.*

***meso*-inositol** *a former name for* ***myo*-inositol**.

mesomeric effect *(in chemistry)* an experimentally observable effect (on reaction rates, etc.) of a substituent caused by the overlap of its p- or π-orbitals with the p- or π-orbitals of the rest of the molecular entity, **resonance** (def. 2) (or mesomerism) being thereby introduced into, or extended within, the molecular entity in question. *Compare* **inductive effect**.

mesomerism *(in chemistry)* a term used to imply that the correct representation of the structure of a particular molecular entity is intermediate between two or more formal valence-bond representations (known as **contributing structures**); **resonance** (def. 2). **—mesomeric** *adj.*

mesomorphic **1** *(in chemistry)* existing in, designating, or pertaining to an intermediate state between a true liquid and a true solid that exists in a **liquid crystal**. **2** *(in biology)* having a form, size, or structure that is average, normal, or intermediate between extremes.

mesophase any phase of matter intermediate between a true liquid and a true solid that exists in a **liquid crystal**.

mesophil *or* **mesophile** any organism that thrives at moderate temperatures, between 20 and 40°C. **—mesophil, mesophile,** *or* **mesophilic** *adj.*

mesophyll the internal parenchyma of a foliage leaf between the two epidermal layers; it is usually photosynthetic. **—mesophyllic** *adj.*

mesophyte any plant requiring moderate amounts of water for optimum growth. **—mesophytic** *adj.*

mesopore any pore (in a gel or porous solid) intermediate in size between a micropore and a macropore, i.e. of width in the range roughly 2.0–50 nm. **—mesoporous** *adj.*

mesosecrin a glycoprotein, M_r 46 000, secreted by human mesoderm-derived and endothelial cells in culture.

mesosome an intracellular, often complex, membranous structure found in many bacteria and probably formed by invagination of the plasma membrane. It is more complex and larger in Gram-positive organisms than in Gram-negative ones. Its function is unclear. **—mesosomal** *adj.*

mesothelium (*pl.* **mesothelia**) a layer of flat cells derived from mesoderm and found lining various body cavities. **—mesothelial** *adj.*

mesotocin [Ile^8]oxytocin; a neurohypophyseal hormone present in some nonmammalian vertebrates, so-named because it is intermediate in structure between **isotocin** and **oxytocin**. It may represent an ancestral molecule, which has been preserved in these groups of vertebrates but has undergone a single residue replacement in mammals.

mesotrophic describing an environment providing a moderate amount of nutrients.

message **1** a specific piece of information, or something containing information, that is transmitted from a donor to a recipient by some means or agent. **2** a jargon term used, sometimes without an article, as the name of a substance, to denote the particular **messenger RNA** (mRNA) of interest in a specified context, or any preparation containing that mRNA. **3** the segment of mRNA (or any particular segment of a polycistronic mRNA) that consists of a sequence of codons carrying the information determining the sequence of amino-acid residues of a specific polypeptide to be synthesized at a ribosome. **4** the part of the information contained within the amino-acid sequence of a hormonal polypeptide, or of its biosynthetic precursors, that elicits a specific physiological response to the hormone. *Compare* **address** (def. 2).

message-dependent (of a partially purified, cell-free, protein-synthesizing system) capable of a significant response to added mRNA.

message sequence *or* **message region** the segment (or segments) of the complete sequence of amino-acid residues of a molecule of a hormonal or prohormonal polypeptide in which the **message** (def. 4) resides. *Compare* **address sequence**.

messenger **1** something, or someone, that bears or carries a **message** (def. 1), or that is able to do so. **2** a molecule or substance that carries genetic information; *see* **messenger RNA**. **3** a molecule or substance that carries physiological instructions; a **rheoseme**. *See also* **chemical messenger**, **first messenger**, **second messenger**.

messenger ribonucleoprotein *abbr.*: mRNP; any complex of messenger RNA (mRNA) and protein. Included are: nuclear ribonucleoprotein that contains mRNA sequences; cytoplasmic ribonucleoprotein that is associated with polyribosomes; and free cytoplasmic ribonucleoprotein particles, also known as **informosomes**.

messenger RNA *or* **template RNA** *abbr*.: mRNA; a class of naturally occurring RNA molecules that carry the information embodied in the genes of DNA to the ribosomes, where they direct protein synthesis. Molecules of mRNA are single-stranded, relatively short-lived, and formed by the process of **transcription** from the template strand of genomic DNA. They carry genetic information in the form of a succession of **codons**. Mature eukaryotic mRNAs contain a 5′ cap and a 3′ poly(A) tail. At the ribosomes, by the process of **translation**, they orchestrate the synthesis of the corresponding polypeptide(s). The plus strand of certain RNA viruses can act as messenger RNA without transcription, as can a synthetic polyribonucleotide. The primary transcript of DNA is often referred to as **hnRNA**, which contains the **introns** that have to be removed by excising and splicing together the **exons** to form the mature mRNA. mRNA may also undergo 'editing' whereby some bases are changed. *See also* **mRNA binding site**, **splicing**.

messenger-RNA-interfering complementary RNA *abbr*.: micRNA; *an alternative name for* **antisense RNA**.

Messing vector any one of certain cloning vectors derived from bacteriophage M13 by insertion of a synthetic multipurpose cloning site and which are especially suitable for the cloning and rapid sequence determination of small (≈500 base pair) fragments of DNA. These have developed into the **pUC vectors**. [After Joachim Messing (1946–).]

met+ *a variant form of* **meta+** (usually before a vowel or letter h).

Met *symbol for* a residue of the α-amino acid L-methionine (alternative to M).

MET a gene, first identified in an *N*-methyl-*N*′-nitrosoguanidine-treated cell line, that encodes a receptor tyrosine kinase with disulfide-linked α and β subunits. The receptor binds **hepatocyte growth factor** and undergoes autophosphorylation of the cytoplasmic domain. Cells co-transfected with *MET* and *HGF* are highly tumorigenic. Germ-line missense mutations lead to a familial form of renal cancer. *See also* **hepatocyte growth factor receptor**.

meta+ *or (before a vowel or letter h)* **met+** *prefix* **1** indicating alteration, alternation, or change of condition or position; after, distal to, behind, beyond; more highly specialized form of. **2** *(in inorganic chemistry)* denoting the least hydrated acid of a series of oxoacids formed from any one of certain anhydrides, or the anion or a salt formed from such an acid; *Compare* **ortho+** (def. 2), **pyro+** (def. 2). It is now approved only for the polymeric acids: metaboric acid, $(HBO_2)_n$, metaphosphoric acid, $(HPO_3)_n$, and metasilicic acid, $(HSiO_3)_n$; and for anions and salts of these acids (*but see* **metabisulfite**). **3** *(in organic chemistry)* distinguishing a particular polymeric form of the substance named, e.g. metaldehyde, metaformaldehyde.

meta- *symbol*: *m*-; *prefix* (*in organic chemical nomenclature*) denoting the isomer of a disubstituted monocyclic aromatic compound in which the substituents are separated by one intervening unsubstituted ring-carbon atom. *Compare* ***ortho-***, ***para-***.

meta-analysis a quantitative systematic review in which the results of many studies dealing with the same topic are combined. It is used in the study of multifactorial diseases.

metabisulfite *an old name, still frequently used, esp. in commerce, for* inorganic salts of the general formula $M_2S_2O_5$, where M is a monovalent metallic element.

metabolic of, pertaining to, occurring in, produced by, or liberated during **metabolism**. **—metabolically** *adv.*

metabolic acidosis any clinical condition in which hydrogen ions accumulate in the blood plasma through an excessive production of acidic metabolites (as in ketoacidosis or lactic acidosis), the excessive ingestion of acids, or a defect in the excretion of hydrogen ions by the kidneys.

metabolic activation **bioactivation**, usually with particular reference to the conversion of procarcinogens to carcinogens in the body.

metabolic alkalosis any clinical condition in which there is a deficiency of hydrogen ions in the blood plasma caused by the excessive ingestion of alkalis, extrarenal loss of acid (as with vomiting), or therapy with diuretic agents.

metabolic balance *see* **balance** (def. 1).

metabolic block the complete or partial interruption of a specific reaction in a metabolic pathway caused by the absence or greatly reduced activity of the enzyme catalysing that reaction (for genetic reasons or due to the action of a specific agonist). The consequences of a metabolic block include: (1) the complete or partial absence of the final product of the pathway; (2) the accumulation of a metabolic intermediate of the pathway before the block, for which no significant alternative pathway exists; (3) the accumulation of products of an alternative, normally minor, metabolic pathway. *See also* **inborn error of metabolism**.

metabolic code a model for the evolution of biological regulation and the origin of hormone-mediated intercellular communication. It is characterized by a set of symbols and their corresponding domains. A **symbol** is an intracellular molecule, e.g. a hormone or other messenger, that indicates to the cell the existence of a particular state of the environment, e.g. lack of glucose or of amino acids. The symbol regulates a diverse set of biochemical events and reactions in the cell, the nature and number of which are the **domain** of that symbol.

metabolic compartmentation *or* **metabolic compartmentalization** the concept that certain metabolic reactions occur in separate compartments of the cell (or organism) and are therefore not necessarily in equilibrium with each other.

metabolic control *an alternative term for* **metabolic regulation**.

metabolic cycle any closed sequence of metabolic reactions in which an end product is a reactant in the initiation of the cycle, e.g. the **tricarboxylic-acid cycle**.

metabolic disease any disease caused by a recognizable abnormality of metabolism.

metabolic flux the rate of passage of material, or of a specified substance or molecular fragment, through a given metabolic pathway.

metabolic map a diagram representing the sequence and relationships of enzyme-catalysed reactions in metabolism. It typically consists of the names and/or structures of metabolites, connected by arrows representing enzyme-catalysed reactions.

metabolic pathway any series of connected (enzymic or other) reactions occurring in a cell or organism, whether anabolic, catabolic, or amphibolic.

metabolic pool the sum total of all the different amounts of a given substance, group of similar substances, or specified molecular fragment, irrespective of their distribution in a cell, organ, tissue, or organism, that are in complete equilibrium with each other in regard to participation in a specified set of metabolic reactions.

metabolic quotient *symbol*: Q_x ; a measure of the rate at which a given substance (*x*) is taken up by, or discharged from, a cell, organ, tissue, or organism.

metabolic rate the rate of metabolism of an animal measured under given conditions. It may be determined from the dioxygen consumption and carbon dioxide (and urinary nitrogen) excretion, or from the total energy output of the animal. *Compare* **basal metabolic rate**.

metabolic reconstruction the process of modelling the metabolism of an organism (e.g. using biochemical, sequence, and phenotypic data) in order to identify which pathways are present and which genes are involved in which functional roles.

metabolic regulation the coordinated action of the many systems that control the activity of metabolic pathways. The systems embrace gene regulation and control of protein biosynthesis, as well as the control of the rate of enzyme reactions by phosphorylation of the enzyme protein or by the action of allosteric effectors. The action of second messengers is important in the transduction of signals from outside a cell to the interior.

metabolic state (of mitochondria) *an alternative term for* **respiratory state**.

metabolic turnover the continual exchange of cellular components by degradation and synthesis. Even for cell components for which the content and composition remain relatively constant, a continuous breakdown and resynthesis of individual molecules is occuring.

metabolism 1 the totality of the chemical reactions and physical changes that occur in living organisms, comprising **anabolism** and **catabolism**. 2 the totality of the chemical reactions and physical processes undergone by a particular substance, or class of substances, in a living organism.

metabolite any substance, either endogenous or exogenous, that is formed or changed by metabolism. *See also* **primary metabolite**, **secondary metabolite**.

metabolize *or* **metabolise** 1 to affect by metabolism. 2 to effect metabolism. —**metabolizable** *or* **metabolisable** *adj.*

metabolome the universe of low-molecular-weight metabolites present in cells in a particular physiological or developmental state.

metabolomics the quantitative analysis of all the small-molecular-weight metabolites present inside a cell (or other sample).

metabolon a supramolecular complex of consecutively acting metabolic enzymes and cellular structural elements.

metabotropic describing a type of receptor (e.g. certain **glutamate receptors**) that mediates its effects by activation of enzymes, especially **adenylate cyclase** or the **phosphatidylinositol cycle**, in distinction from receptors that regulate ion channels. *Compare* **ionotropic**. *See also* **excitatory amino-acid receptor**.

metachromasia *or* **metachromasy** *or* **metachromatism** 1 the property exhibited by certain cationic (i.e. basic) dyes of shifting their absorption spectra towards shorter wavelengths in the presence of substances with appropriately arranged anionic groups. 2 the property exhibited by some biological structures or materials, when treated with certain cationic (basic) dyes, of staining with a different colour from that of the dye used. Biological materials showing metachromasia include heparin, chondroitin sulfate, sulfatides, gangliosides, and polyphosphates. —**metachromatic** *adj.*; **metachromatically** *adv.*

metachromatic granule any cytoplasmic granule that exhibits **metachromasia** (def. 2). **Volutin granules** are an example.

metachromatic leukodystrophy any of a group of hereditary diseases of humans characterized by disintegration of myelin and the accumulation of **metachromatic lipid** – galactosyl sulfatide (cerebroside sulfate) – in the white matter of the central nervous system, in peripheral nerves, and in some visceral organs. It is mainly caused by mutations in the gene for the lysosomal enzyme arylsulfatase A (locus 22q13.31-qter). The disorder is characterized clinically by progressive paralysis and dementia, usually in the first few years of life, and is transmitted as an autosomal recessive trait. *See also* **saposin**.

metachromism *see* **metachromasia**.

metadrenaline *an alternative name for* **metanephrine**.

metagon a stable, virus-like RNA particle postulated to occur in certain mate-killer strains of *Paramecium aurelia*, in which it acts like messenger RNA.

metahalone any of a class of metaphase inhibitors having the general formula 5-halopyridine-2-one. [From meta(phase) halone.]

metakentrin *an obsolete name for* **luteinizing hormone**.

metal 1 any of a large class of chemical elements that, with certain exceptions, are ductile, malleable solids with a characteristic lustre, are good conductors of electricity and heat, and generally form simple cations. 2 any substance or material consisting entirely or predominantly of one or more **metals** (def. 1). 3 consisting or made of metal. —**metallic** *adj.*

metal-chelate affinity chromatography a form of **affinity chromatography** in which immobilized weak bases such as imidazole coordinated with ions such as Ni^{2+} are used to concentrate recombinant proteins bearing **His-tags**.

metal-ion buffer a **buffer** (def. 1, 2) for metal ions. It comprises a solution of a metal salt, with a suitable complexing agent. The concentration of free metal ions is maintained by the equilibrium with an excess of the complexed form.

metallo+ *comb. form* denoting metal, or characterized by the presence of metal.

metalloantigen any metal-labelled antigen for use in a **metalloimmunoassay**.

metallocarboxypeptidase *recommended generic name for* any **carboxypeptidase** of the sub-subclass EC 3.4.17, for which a bivalent cation is an essential component of the catalytic mechanism.

metallocene *the generic name for* π-bonded bis(η-cyclopentadienyl) coordination compounds of certain metals, e.g. ferrocene, bis(η-cyclopentadienyl)iron, $[Fe(C_5H_5)_2]$.

metallochaperone any of a family of homologous proteins that bind and transport specific metals in the cytoplasm to their sites of utilization. They contain a metal-binding Cys–X–X–Cys motif within a four-stranded antiparallel beta sheet below two alpha helices. Six copies of this motif are present in the N-terminal region of Menkes and Wilson ATPases of the *trans* Golgi network. In yeast and human cells three metallochaperones are required to deliver copper to the Golgi apparatus, mitochondria, and cytosol respectively.

metallochromic describing a dye, indicator, or stain that exhibits a distinctive colour change when complexed with metal ions; the colour change is often specific for a particular metal.

metalloendopeptidase *recommended generic name for* any **endopeptidase** of the sub-subclass EC 3.4.24, for which a bivalent cation is an essential part of the catalytic mechanism.

metalloenzyme any enzyme that is a **metalloprotein**.

metallohapten any metal-labelled hapten for use in a **metalloimmunoassay**.

metalloimmunoassay a form of **immunoassay** in which ions of an appropriate transition metal, tightly complexed to the antigen or hapten in question, are used as the distinguishable label. The amount of metal present in the free and antibody-bound forms is determined by a suitable analytical method such as emission, absorption, or fluorescence spectrometry.

metallopeptidase *see* **metallocarboxypeptidase**, **metalloendopeptidase**.

metalloporphyrin any compound formed by chelation of a porphyrin with a metal ion, e.g. hemoglobins (with iron), cytochromes (with iron), and chlorophylls (with magnesium).

metalloprotease *a former name for* metalloendoproteinase (*see also* **metallocarboxypeptidase**, **matrix metalloproteinase**).

metalloprotein any protein containing one or more molecular proportions of a metal bound to it, either directly or as part of a prosthetic group.

metalloproteinase *see* **metallocarboxypeptidase**, **metalloendopeptidase**.

metalloselenonein a synthetic analogue of the copper metallothionein peptide of *Neurospora crassa* that contains selenocysteine residues in place of cysteine.

metallothionein any of a group of small proteins with extraordinarily high contents both of one or more metals (cadmium, copper, zinc) and of cysteine. They occur widely, from microorganisms to humans, and have highly conserved structures. Mammalian metallothioneins are of 6.8 kDa, consist of 61 amino-acid residues, including 20 cysteine residues, and contain about 7 g atoms of metal per molecule. The apoprotein may be termed **thionein**.

metaprotein *an old term for* the products formed by acid or alkaline hydrolysis of proteins that are soluble in weak acids or alkalis, but insoluble in neutral solutions.

metal proteinase *a former name for* metalloproteinase (*see* **metallocarboxypeptidase**, **metalloendopeptidase**).

metal response element *abbr*.: MRE; a sequence in the promoter region of metallothionein genes that respond to the presence of metals. *See also* **response element**.

metal response element binding protein *abbr*.: MREBP; a mammalian protein that activates basal and heavy metal-induced transcription of metallothionein genes by binding to the metal response element in their promoter regions. MREBP1 contains a DNA-binding region of six C2H2 zinc fingers and three functional activation domains. Knockout of the mouse gene results in death of embryos with variable degrees of liver damage.

metamer *(in chemistry) a former term for* any one of two or more **constitutional isomers** that are of the same chemical class, e.g. ethylamine, CH_3–CH_2–NH_2, and dimethylamine, CH_3–NH–CH_3.

metamere *(in morphology)* any of the linearly arranged similar body segments in animals that exhibit **metamerism** (def. 2); a somite.

metameric 1 *(in chemistry)* of or pertaining to a **metamer**; pertaining to the phenomenon of, or displaying **metamerism** (def. 1). 2 *(in morphology)* of, or pertaining to, a **metamere**; consisting of metameres; segmented; of, or pertaining to, **metamerism** (def. 2).

metamerism 1 *(in chemistry)* the occurrence as **metamers** of two or more chemical substances of the same molecular formula. 2 *(in morphology)* the condition of an animal body characterized by the presence of a series of similar segments or **metameres**; segmentation.

metameter a quantity derived from an observation, and independent of all parameters, that conveys the magnitude of the phenomenon observed. A metameter is frequently used to simplify the expression or analysis of dose–response relationships.

metamorphosis 1 a complete change in physical form; a structural transformation. 2 *(in zoology)*: the rapid, postembryonic, structural transformation from a larva into an adult that occurs in certain animals, e.g. the change from a tadpole to a frog. —**metamorphose** *vb.*; **metamorphic** *adj.*

metanephrine *or* **metadrenaline** 3-*O*-methylepinephrine; an inactive metabolite of epinephrine, produced by the action of **catechol *O*-methyltransferase**. Small quantities are normally found in the urine, and larger amounts occur in the urine of patients with catecholamine-secreting tumours.

metaphase the stage in **mitosis**, following **prometaphase**, during which the chromosomes become arranged so that their centromeres all lie in one plane and their longitudinal axes are at right angles to the spindle axis; the corresponding phases in **meiosis**.

metaphosphatase *an alternative name for* 1 endopolyphosphatase (EC 3.6.1.10). 2 exopolyphosphatase (EC 3.6.1.11).

metaphosphate *the traditional name for* any anion or any (partial or full) salt or ester derived from the condensed acid metaphosphoric acid, polytrioxophosphoric(v) acid, $(HPO_3)_n$, where n is a small integer, commonly 3, 4, or 6. Metaphosphoric acid and its derivatives are thought not to exist in the monomeric state, although they are often represented as such for convenience. *See also* **polyphosphate**.

metaprotein *an old term for* the products formed by acid or alkaline hydrolysis of proteins that are soluble in weak acids or alkalis but insoluble in neutral solutions.

metarhodopsin either of two intermediates, metarhodopsin I (absorption maximum 480 nm) and metarhodopsin II (absorption maximum 380 nm), formed during the photolysis of **rhodopsin**.

metastable 1 **a** describing any body or system existing in a state of apparent equilibrium when undisturbed, or subject to very small perturbation, but capable of passing to a more stable state when subjected to greater perturbation. **b** describing such a state or such an equilibrium. 2 describing an excited state of an atom, ion, nucleus, or other quantum-mechanical system that is relatively long-lived because the transitions to a lower energy state are forbidden transitions. 3 *symbol*: m; describing any comparatively stable excited state of a radioisotope that decays to a more stable state by isomeric transition, with the emission of gamma radiation, e.g. the metastable nuclide ${}^{99\mathrm{m}}_{43}\mathrm{Tc}$, which is formed by decay of ${}^{99}_{42}\mathrm{Mo}$ and which in turn decays by transition to its nuclear isomer ${}^{99}_{43}\mathrm{Tc}$ with a half-life of 6 h and emission of one quantum of gamma radiation.

metastasis (*pl.* **metastases**) the transfer of disease, especially tumour cells, from one part of the body to another by way of the natural passages (blood vessels, lymphatics) or by direct continuity. —**metastasize** *or* **metastasise** *vb.*; **metastatic** *adj.*

metazoa the plural of **metazoan** (def. 1) *or* **metazoon**.

Metazoa a subkingdom of animals consisting of multicellular animals whose cells are organized into tissues and their activities coordinated by a nervous system. The group includes all animals except the Protozoa and Parazoa.

metazoal *a variant form of* **metazoan** (def. 2).

metazoan 1 *or* **metazoon** (*pl.* **metazoa**) any animal of the subkingdom Metazoa. 2 *or* **metazoal** *or* **metazoic** of, characteristic of, or belonging to the Metazoa.

metazoic *a variant form of* **metazoan** (def. 2).

metazoon (*pl.* **metazoa**) *an alternative term for* **metazoan** (def. 1).

[Met^5]enkephalin *or* **[Met]enkephalin** *abbr. for* [5-methionine]enkephalin.

meter 1 an instrument or device for measuring (and recording) the quantity of something (either instantaneously or cumulatively). 2 to measure (something) by means of a **meter** (def. 1). 3 to supply (something) in a measured or regulated amount. 4 *the US spelling of* **metre**.

+meter *comb. form* denoting an instrument or device for measuring (something indicated or specified). —**+metric** *adj.*

metestrus *see* **estrous cycle**.

meth+ *a variant form of* **metho+** *(before a vowel)*.

methadone (hydrochloride) 6-dimethylamino-4,4-diphenyl-3-heptanone hydrochloride; a narcotic analgesic used in cases of opioid dependence.



R-(–)-enantiomer

methaemoglobin *a variant spelling (esp. Brit.) of* **methemoglobin**.

methaemoglobinaemia *a variant spelling (esp. Brit.) of* **methemoglobinemia**.

methane *or* **marsh gas** a colourless, odourless, flammable gas, CH_4; it is the simplest alkane and is the principal constituent of natural gas found in association with mineral oil. It is formed by the anaerobic decay of vegetable matter and in large amounts by ruminants and other herbivores.

methano+ *comb. form.* 1 indicating methane. 2 *(in chemical nomenclature)* denoting the presence of a –CH_2– bridge in a polycyclic hydrocarbon. 3 indicating organisms or compounds involved in metabolism of methane, e.g. **methanotroph**, methanopterin.

methanoate *see* **formate**.

methanogen any microorganism that produces methane. —**methanogenic** *adj.*

methanogenesis the microbial production of methane by anaerobic breakdown of carbon-containing compounds.

methanogenic the ability to form methane from CO_2, a property of some anaerobic bacteria. The pathway involves the coenzyme **tetrahydromethanopterin** (*abbr.*: $\mathrm{H_4MPT}$), and involves formation of 5-formyl-$\mathrm{H_4MPT}$, from which successively methenyl-$\mathrm{H_4MPT}$, methylene-$\mathrm{H_4MPT}$, and methyl-$\mathrm{H_4MPT}$ are formed in reactions analogous to those for **folate coenzymes**. From the last of these, methyl is transferred to **coenzyme M** to form methyl-coenzyme M, from which methane is formed in a reductive step involving **factor F_{430}**. *See also* **coenzyme F_{420}**.

methanol methyl alcohol; CH_3–OH; the lowest member of the alkanols. It is a colourless, flammable, mobile, poisonous liquid, widely used as a solvent. Numerous esters and ethers of methanol occur naturally, especially in plants. *Other names*: wood alcohol; wood spirit; carbinol. —**methanolic** *adj.*

methanol oxidase *see* **alcohol oxidase**.

methanolysis alcoholysis using methanol.

MetHb *abbr. for* methemoglobin (i.e. **ferrihemoglobin**).

methemalbumin *or (esp. Brit.)* **methaemalbumin** a complex of metheme with albumin, which imparts a brownish colouring to plasma. It is formed as the result of *in vitro* hemolysis.

methemoglobin *or (esp. Brit.)* **methaemoglobin** *abbr.*: MetHb; *an older name for* **ferrihemoglobin**.

methemoglobinemia *or (esp. Brit.)* **methaemoglobinaemia** any clinical condition characterized by an excess of **ferrihemoglobin** (i.e. methemoglobin) in the erythrocytes. It accompanies a number of **hemoglobinopathies**, and also results from administration of large amounts of sulfonamides. A hereditary enzymopenic methemoglobinemia is caused by mutations in the gene for cytochrome b_5 reductase. Ferrihemoglobin imparts a brown colour to urine.

methene *an old name, still commonly used in biochemistry, for* the trivalent diatomic group, =CH–, attached to two other groups in an organic molecule. The name now recommended is **methyne**.

methene bridge the **methene** group that links consecutive pyrrole rings in the molecular structure of tetrapyrroles and related compounds.

methenyl+ *prefix (to a trivial biochemical name)* denoting substitution of a **methene** group into the indicated parent compound (at the positions specified by appropriate locants); e.g. 5,10-methenyltetrahydrofolate. *Compare* **methylene+**.

methenyltetrahydrofolate cyclohydrolase EC 3.5.4.9; *systematic name*: 5,10-methenyltetrahydrofolate 5-hydrolase (decyclizing); one of the enzymes involved in transformations between **folate coenzymes**. It catalyses the hydrolysis of 5,10-methenyltetrahydrofolate to form 10-formyltetrahydrofolate. One of three enzymes (*see also* **methylenetetrahydrofolate dehydrogenase (NADP$^+$)** and **formate–tetrahydrofolate ligase**) necessary for the biosynthesis of purines, thymidylate, methionine, histidine, pantothenate, and formyl tRNA-Met.

5,10-methenyltetrahydrofolate synthetase *see* **5-formyltetrahydrofolate cyclo-ligase**.

MeTHFA *abbr. for* 5-methyltetrahydrofolate.

methicillin *see* **meticillin (sodium)**.

methine *a former name for* **methyne**.

methioninate **1** methionine anion; the anion, $CH_3–S–[CH_2]_2–CH(NH_2)–COO^-$, derived from **methionine**. **2** any salt containing methionine anion. **3** any ester of methionine.

methionine *the trivial name for* α-amino-γ-methylmercaptobutyric acid; 2-amino-4-(methylthio)butanoic acid; $CH_3–S–[CH_2]_2–CH(NH_2)–COOH$; a chiral α-amino acid. L-Methionine (*symbol*: M *or* Met), (*S*)-2-amino-4-(methylthio)butanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: AUG (or also AUA in various species of mitochondria). D-Methionine (*symbol*: D-Met *or* DMet) is not known to occur naturally. In mammals, methionine is glucogenic, and is an essential dietary amino acid, although either enantiomer will serve (the D-form being oxidatively deaminated to the α-oxo acid, which is then reaminated with inversion).



L-methionine

methionine adenosyltransferase *abbr.* MAT; EC 2.5.1.6; *other names*: *S*-adenosylmethionine synthetase; AdoMet synthetase; an enzyme that catalyses the reactions:

$$\text{L-methionine} + \text{ATP} = S\text{-adenosyl-L-methionine} + \text{PP}_i$$

$$\text{PPP}_i = \text{PP}_i + \text{P}_i$$

Three isozymes (MATT–III) are formed by the two genes whose products are α1 (395 amino acids) and α2 (394 amino acids), which share 84% sequence identity. MATI is $(\alpha1)_4$, while MATIII is $(\alpha1)_2$, both being present in adult liver. MATII is present in many tissues and in fetal (but not adult) liver. Mutations in the α1 gene lead to isolated hypermethioninemia.

methionine cycle *see* **methionine salvage pathway.**

methionine dioxide *symbol*: $MetO_2$; methionine *S*,*S*-dioxide; $CH_3–SO_2–[CH_2]_2–CH(NH_2)–COOH$; an oxidation product of methionine, *formerly known (incorrectly) as* **methionine sulfone**.

[5-methionine]enkephalin *abbr.*: [Met]enkephalin *or* [Met^5]enkephalin; the recommended designation for the trivial name of the pentapeptide Tyr-Gly-Gly-Phe-Met. *See* **enkephalin**.

methionine oxide *symbol*: MetO; methionine *S*-oxide; $CH_3–SO–[CH_2]_2–CH(NH_2)–COOH$; an oxidation product of methionine and an intermediate in the formation of **methionine dioxide**. *It was formerly known (incorrectly) as* **methionine sulfoxide**.

methionine salvage pathway *or* **methionine cycle** *or* **Yang cycle** a metabolic cycle occurring in plant cells in which methionine is synthesized from carbons originating in the ribose of ATP, the sulfur atom being conserved throughout the cycle. In outline, the cycle consists of reactions in which, starting with L-methionine, ***S*-adenosylmethionine** (I) is formed in a reaction with ATP. I is then converted by 1-aminocyclopropane-1-carboxylate synthase, EC 4.4.1.14, to 5′-methylthioadenosine (II) and 1-aminocyclopropane-1-carboxylate, a precursor of ethylene (*see* **ethylene-forming enzyme**). 5′-Methylthioadenosine is also produced during synthesis of polyamines. Adenine is then cleaved from methylthioadenosine to form 5-methylthioribose from which 5-methylthioribose-1-phosphate (III) is formed by reaction with ATP. III is then converted through a series of intermediates to 2-keto-4-methylthiobutyrate from which methionine is formed by a transamination reaction. [After S.F. Yang.]

methionine sulfone *an old (incorrect) name for* **methionine dioxide**.

methionine sulfoxide *an old (incorrect) name for* **methionine oxide**.

methionine sulfoximine [3-amino-3-carboxypropyl]methyl sulfoximine; an inhibitor of glutamine synthetase (**glutamate–ammonia ligase**) in plants, and identified as the toxic agent in flour treated with the bleaching agent NCl_3 (agene, hence the term **agenized flour**). It interferes with the action of γ-amino-*n*-butyric acid in the brain. This is associated with the ability of methionine sulfoximine to cause fits in a wide variety of animals – ferrets are particularly susceptible. Although methionine sulfoximine has not been clearly proven to be toxic to humans, agene is no longer used for bleaching flour.

methionine synthase *see* **homocysteine methyltransferase**.

methioninium methionine cation; the cation, $CH_3–S–[CH_2]_2–CH(NH_3^+)–COOH$, derived from **methionine**.

methionino the alkylamino group, $CH_3–S–[CH_2]_2–CH(COOH)–NH–$, derived from **methionine**.

methionyl the acyl group, $CH_3–S–[CH_2]_2–CH(NH_2)–CO–$, derived from **methionine**.

methionyllysylbradykinin *or* **Met-Lys-bradykinin** *see* **bradykinin**.

methionyl-tRNA formyltransferase EC 2.1.2.9; *systematic name*: 10-formyltetrahydrofolate:L-methionyl-tRNA *N*-formyltransferase. An enzyme that catalyses a reaction between 10-formyltetrahydrofolate, L-methionyl-tRNA, and H_2O to form tetrahydrofolate and *N*-formylmethionyl-tRNA. *N*-formylmethionyl-tRNA is involved in the initiation of prokaryote **translation**.

metho+ *or (before a vowel)* **meth+** *(comb. form) a variant of* **methyl+** in the names of certain chemical compounds.

methotrexate 4-amino-10-methylfolic acid; *other name*: amethopterin; a folic acid analogue that is a potent competitive inhibitor ($K_i < 10^{-9}$ M) of **dihydrofolate reductase**. It is useful in the treatment of acute leukemia and choriocarcinoma. It acts by blocking nucleotide synthesis and thus also DNA synthesis and has similar activity to **aminopterin**. The crystal structure of a complex of methotrexate and dihydrofolate reductase from *Lactobacillus casei* is known.



methoxatin *or* **pyrroloquinoline quinone** 4,5-dihydro-4,5-dioxo-1*H*-pyrrolo-[2,3-*f*]quinoline-2,7,9-tricarboxylic acid; a heat-stable fluorescent cofactor implicated in the action of primary alcohol dehydrogenases in methylotrophic bacteria and possibly more generally associated with the oxidation of single-carbon compounds. *See* **quinoprotein**.



methoxy *symbol*: OMe *or* MeO; the alkoxy group, CH$_3$–O–, derived from methanol by loss of a hydrogen atom.

3-methoxy-4-hydroxymandelate acid *see* **hydroxymethoxymandelate**.

5-methoxypsoralen an intercalating reagent for DNA; it forms covalent cross-links on irradiation. *See also* **psoralen**.



methoxyvinylglycine *abbr*.: MVG; L-2-amino-4-methoxy-*trans*-3-butenoic acid; an inhibitor of ethylene biosynthesis in plants.

methuselah a gene of *Drosophila* for a long N-terminal type B G-protein-coupled membrane receptor that regulates the ageing process. Its reduced expression increases resistance to various types of stress (e.g. starvation, high temperature, dietary toxins) and increases lifespan by 35%, but null mutations are lethal to embryos.

methyl *symbol*: Me; the alkyl group, CH$_3$–, derived from methane.

methyl- *prefix (in chemical nomenclature)* used as a locant to indicate in or at a methyl group.

methyl-accepting chemotaxis protein *abbr*.: MCP; any of several similar integral plasma membrane proteins that may be present in the cell membranes of particular strains of certain motile bacteria, e.g. *Escherichia coli* and *Salmonella typhimurium*, and appear to mediate their responses to corresponding classes of chemotactic agent by undergoing enzymic methylation/demethylation of the γ-carboxylate group(s) of one or more glutamic residues (for the enzymes responsible *see* ***che***). The type of ligand determines the reaction, which in turn determines the action of the receptor on the bacterial flagellar motor, so that the effect can be either attractant or repellent. The following examples are from *E. coli*. MCP1 is a receptor for attractants such as L-serine and other amino acids and is also responsible for avoidance of a wide range of repellents, including leucine, indole, and weak acids. MCP2 is a receptor for L-aspartate, dicarboxylic acids, and maltose (via interaction with a periplasmic maltose-binding protein), and is also responsible for avoidance of cobalt and nickel. MCP3 interacts with periplasmic ribose- or galactose-binding proteins and mediates movement towards these sugars. MCP4 interacts with periplasmic dipeptide-binding proteins and mediates movement towards such peptides.

***N*^{6}-methyladenine** a methylated base of DNA; this and **5-methylcytosine** are the only modified bases in the DNA of cellular organisms.

methyl alcohol *a common name for* **methanol**.

methylase *a common name for* **methyltransferase**.

methylaspartase *see* **methylaspartate mutase**.

***N*-methyl-D-aspartate** *abbr*.: NMDA; an excitatory amino acid and a neurotransmitter. It acts as agonist for the *N*-methyl-D-aspartate receptor, a subclass of glutamate ionotropic receptors (*see* **glutamate receptor**).

methylaspartate ammonia-lyase *recommended name for* methylaspartase; *see* **methylaspartate mutase**.

methylaspartate mutase EC 5.4.99.1; *systematic name*: L-*threo*-3-methylaspartate carboxy-aminomethylmutase; *other name*: glutamate mutase. An enzyme that catalyses the reaction:

L-*threo*-3-methylaspartate = L-glutamate.

This is the first step of the glutamate-fermentation pathway of the anaerobic bacteria *Clostridium cochlearium*, *C. tetanomorphum*, and others. The product, (2*S*,3*S*)-3-methylaspartate, is converted to mesaconate by the enzyme methylaspartate ammonia-lyase (EC 4.3.1.2). Methylaspartate mutase requires a cobamide coenzyme and has been studied as an example of such a reaction. The enzyme has two subunits (large and small, sometimes called E and S).

methylate 1 to introduce (one or more) methyl groups into (a substance). **2** *(in commerce)* to mix or adulterate with methanol. *See also* **methylation of DNA**. **—methylation** *n.*

methylated-DNA–protein-cysteine *S*-methyltransferase EC 2.1.1.63; *other names*: 6-*O*-methylguanine-DNA methyltransferase; *O*^{6}-methylguanine-DNA-alkyltransferase. It catalyses the reaction between DNA (containing 6-*O*-methylguanine) and protein L-cysteine to form DNA (without 6-*O*-methylguanine) and protein *S*-methyl-L-cysteine. As the acceptor is in the enzyme itself this is a 'suicidal' reaction. Bacterial and mammalian enzymes have common motifs.

methylation of DNA the occurrence in vertebrate DNA of varying amounts of 5-methylcytosine which arises from methylation of cytosine bases where they occur in the sequence CpG. The methylation status of DNA correlates with its functional activity: inactive genes are more heavily methylated. *See also* **CpG islands**.

3-methylcholanthrene a carcinogenic hydrocarbon, found in coal tar. It induces synthesis of cytochrome P450 mRNA.

methyl-coenzyme M reductase EC 2.8.4.1; coenzyme-B sulfoethylthiotransferase; a nickel-containing enzyme that catalyses the methane-releasing reaction in methanogenic bacteria. Severe enzyme deficiency from many mutations leads to developmental delay, seizures, and psychiatric manifestations, hyperhomocystinemia and homocystinuria, premature atherosclerosis, and demyelination. *See* **factor F$_{430}$**.

methyl CoM reductase coenzyme-B sulfoethylthiotransferase, EC 2.8.4.1, an enzyme in methanogenic archaea that catalyses the final reaction of methanogenesis: the reaction of methyl coenzyme M and coenzyme B, with the formation of the mixed disulfide and release of methane. Contains the nickel-containing **factor F$_{430}$**.

methylCpG-binding protein 2 *abbr*.: MECP2; a ubiquitously expressed, very abundant nuclear protein (486 amino acids) of human tissues that is associated with 5-methylcytosine-rich heterochromatin. It helps recruit histone deacetylases and other proteins. Mutations result in an X-chromosome-linked neurodegenerative disorder of girls that starts 6–18 months after birth and is called Rett syndrome.

methylcrotonyl-CoA carboxylase EC 6.4.1.4; an enzyme of the pathway for the degradation of leucine. It catalyses the formation of 3-methylglutaconyl-CoA from ATP, 3-methylcrotonyl-CoA, and HCO$_3^-$ with release of ADP and orthophosphate. Biotin is a cofactor. The 3-methylglutaconyl-CoA is then converted to 3-hydroxy-3-methylglutaryl-CoA.

5-methylcytosine a methylated base of DNA; this and ***N*^{6}-methyladenine** are the only modified bases in the DNA of cellular organisms. In T-even phages all the C residues of DNA are 5-hydroxymethylcytosine.

methyldopa L-2-amino-2-methyl-3-(3,4-dihydroxyphenyl)propionic acid; a compound used as an antihypertensive. It is a competitive inhibitor of **aromatic L-amino acid decarboxylase** (dopa decarboxylase), but its effects on blood pressure may result from its metabolism to α-methylnorepinephrine, which stimulates presynaptic α$_2$ receptors, thus decreasing norepinephrine release.



methylene 1 *the recommended name for* the bivalent triatomic group CH$_2$ in a molecule, whether attached to two other atoms by single bonds or to one other atom by a double bond. **2** *a former name for* **carbene** (def. 1).

methylene+ *prefix (to a trivial chemical name)* denoting substitution of a **methylene** group into the indicated parent compound (at the positions specified by appropriate locants); e.g. 5,10-methylenetetrahydrofolate (which may be shortened to 5,10-CH_2-H_4folate). *Compare* **methenyl+**.

***N,N*¹-methylenebisacrylamide** $(CH_2{:}CHCONH_2)_2CH_2$; a cross-linking agent used in a ratio (w/w) of between 1:49 and 1:19 with acrylamide in the preparation of polyacrylamide gels.

Methylene Blue *or* **Swiss Blue** *or* **Basic Blue 9** CI 52015; tetramethylthionine chloride; 3,7-bis(dimethylamino)phenothiazinium chloride; a water- and ethanol-soluble blue dye; $A_{\max}$ (in water) at 663–667 nm. It is reducible to a leuko (i.e. colourless) compound, which is reoxidizable by dioxygen, and hence is useful as a redox indicator; $E^{o\prime}$ (pH 7.0, 30°C) = +0.011 V. It is useful also as a stain in bacteriology and histology, e.g. being preferentially taken up by melanin-containing cells, and can be used to target therapeutic agents to such cells.

3,4-methylenedioxymethamphetamine *abbr*.: MDMA; a phenethylamine derivative and analogue of **mescaline** and **amphetamine** that is a potent CNS stimulant and hallucinogen; *popularly known as* **ecstasy**. A controlled substance in the US Code of Federal Regulations.



S-(+)-enantiomer

2-methyleneglutarate mutase EC 5.4.99.4; *systematic name*: 2-methyleneglutarate carboxy-methylenemethylmutase. An enzyme that catalyses the reaction:

2-methyleneglutarate = 2-methylene-3-methylsuccinate.

It is a key enzyme in the fermentation of nicotinate to ammonia, propionate, acetate, and CO_2 by the strict anaerobe *Clostridium barkeri*, but has been much investigated as an example of an enzyme mechanism based on the adenosylcobalamin coenzyme. 2-Methylene-3-methylsuccinate is converted to 2,3-dimethylmaleate by methylitaconate Δ-isomerase (EC 5.3.3.6). The enzyme is a homotetramer of 70 kDa subunits.

methylene-interrupted double bonds double bonds separated by one methylene group. The term is used especially to describe the double bonds in naturally occurring long-chain fatty acids; in many cases these are all of the *Z* configuration, with each pair separated by one methylene group.

methylenetetrahydrofolate dehydrogenase (NADP⁺) EC 1.5.1.5; *systematic name*: 5,10-methylenetetrahydrofolate: $NADP^+$ oxidoreductase. *other name*: C1-tetrahydrofolate synthase, cytosolic; an enzyme involved in the interconversion of folate coenzymes that catalyses the reaction:

$$\text{5,10-methylenetetrahydrofolate} + NADP^+ = \text{5,10-methenyltetrahydrofolate} + NADPH.$$

One of three enzymes (*see also* **methenyltetrahydrofolate cyclohydrolase**, and **formate–tetrahydrofolate ligase**) necessary for the biosynthesis of purines, thymidylate, methionine, histidine, pantothenate, and formyl tRNA-Met. The human enzyme is a cytosolic trifunctional homodimer of 934 amino acids; the N-terminal domain (amino acids 1–304) has methylenetetrahydrofolate dehydrogenase and cyclohydrolase activity; the C-terminal section (305–934) forms the formyltetrahydrofolate synthetase domain (*other names*: mitochondrial (precursor) NAD-dependent methylenetetrahydrofolate dehydrogenase (EC 1.5.1.5); methenyltetrahydrofolate cyclohydrolase (EC 3.5.4.9)).

methylesterase any of various enzymes that catalyse the hydrolysis of methyl esters. For example, **juvenile-hormone esterase** (EC 3.1.1.59) of insects, *other name*: JH-esterase, catalyses the hydrolysis of methyl (2*E*,6*E*)-(10*R*,11*S*)-10,11-epoxy-3,7,11-trimethyltrideca-2,6-dienoate to form (2*E*,6*E*)-(10*R*,11*S*)-10,11-epoxy-3,7,11-trimethyltrideca-2,6-dienoate and methanol; i.e. it demethylates the insect juvenile hormones JH_1 and JH_2. It is similar to certain other carboxylesterases and lipases. The **protein-glutamate methylesterase** of *Escherichia coli* is involved in chemotaxis in this organism (*see* ***che***).

methylglucosamine *N*-methyl-L-glucosamine; 2-deoxy-2-(methylamino)-L-glucose; a component of **streptomycin**.

3-methylglutaconic aciduria any condition in which there is excess 3-methylglutaconic acid in urine. Type I is due to deficiency of a specific hydratase that converts 3-methylglutaconyl-CoA to 3-hydroxy-3-methylglutaryl-CoA in mitochondria during catabolism of leucine. Type II (*see* **Barth syndrome**) is due to mutations in **tafazzin**, and like types III and IV is associated with normal 3-methylglutaconyl-CoA hydratase activity.

***O*⁶-methylguanine** a modified and, in principle, highly mutagenic base in DNA (it base pairs with T). It has a special repair enzyme, **methylated-DNA–protein-cysteine *S*-methyltransferase**.

7-methylguanine a modified base found in transfer RNA. *See* **guanine** (for numbering), **7-methylguanosine**.



7-methylguanosine a modified nucleoside that forms a **cap** at the 5′-terminus of eukaryotic mRNA. *See also* **7-methylguanine**.

methylidyne *the recommended name for* the trivalent diatomic group CH≡ attached to a single other group in a molecule of an organic compound. *Compare* **methine**.

methylmalonate $CH_3CH(COO^-)_2$; isosuccinate 2-methylpropanedioate; the dianion of methylmalonic acid; as **methylmalonyl-CoA** it is an intermediate in the conversion of propionyl-CoA to succinyl-CoA. Note: methylmalonate should be distinguished from methyl malonate (two words), which is propanedioic acid dimethyl ester.

methylmalonic acidemia *or* **methylmalonic aciduria** any autosomal recessive disease in which abnormally large amounts of methylmalonate occur in the blood and urine. The condition may be caused by abnormalities in either **methylmalonyl-CoA epimerase** or **methylmalonyl-CoA mutase** apoenzymes, or by three different abnormalities in adenosylcobalamin synthesis.

methylmalonyl-CoA 2-carboxypropanoyl-CoA; it can exist as the enantioners (*R*)- and (*S*)-methylmalonyl-CoA; (*S*)-methylmalonyl-CoA is an intermediate in the **beta oxidation** of odd-numbered fatty acids in animals. Propionyl-CoA is the major end product; for further metabolism, this is converted to succinyl-CoA by, first, carboxylation to (*S*)-methylmalonyl-CoA, which is converted by **methylmalonyl-CoA epimerase** to (*R*)-methylmalonyl-CoA, which is then converted to succinyl-CoA by **methylmalonyl-CoA mutase**.

methylmalonyl-CoA epimerase EC 5.1.99.1; an enzyme that interconverts (*R*)-methylmalonyl-CoA to (*S*)-methylmalonyl-CoA. It is sometimes incorrectly referred to as methylmalonyl-CoA racemase (chiral centres in the CoA moiety are not affected).

methylmalonyl-CoA mutase EC 5.4.99.2; *systematic name*: (*R*)-2-methyl-3-oxopropanoyl-CoA CoA-carbonylmutase; an enzyme that converts (*R*)-methylmalonyl-CoA to succinyl-CoA; adenosylcobalamin is a cofactor. This mitochondrial matrix enzyme is required for degradation of several amino acids, odd-chain fatty acids, and cholesterol via propionyl-CoA to the tricarboxylic-acid cycle; deficiency results in **methylmalonic acidemia**. In some bacteria the enzyme is a heterodimer; both subunits have homology with the human protein. Its role is in the synthesis of propionate from tricarboxylic-acid-cycle intermediates.

methylmercuric hydroxide a powerful reagent used for the denaturation of the secondary structure of RNA molecules, but limited in its use owing to its toxicity.

2-methyl-1,4-naphthalenedione 2-methyl-1,4-naphthoquinone; *see* **menadione**.

Methyl Orange a dye used as an indicator, changing from red to orange-yellow over the pH range 3.1–4.4.



methylotroph any organism that can use certain single-carbon compounds, in a lower oxidation state than CO_2, as sole carbon source. —**methylotrophic** *adj.*; **methylotrophy** *n.*

methylotrophic yeast any yeast belonging to either of the genera *Hansenula* or *Pichia*. They are potentially valuable recombinant-DNA expression hosts as certain oxidase genes (*MOX* and *AOX*) are vastly overexpressed and their promoters are suitable for the expression of foreign proteins. *See also* **alcohol oxidase**, **methylotroph**.

3-methyl-2-oxobutanoate dehydrogenase (lipoamide) EC 1.2.4.4; *other names*: 2-oxoisovalerate dehydrogenase; branched-chain α-keto-acid dehydrogenase; branched-chain α-keto-acid decarboxylase; an enzyme present in a complex that catalyses the oxidative decarboxylation of oxo acids derived from branched-chain amino acids. It is similar in mechanism to the **pyruvate dehydrogenase complex**. The E_1 component of the complex, it catalyses the release of CO_2 from the oxo acid and transfer of the resulting acyl group to lipoamide. Thus, for the oxo acid from valine, it catalyses the reaction of 3-methyl-2-oxobutanoate with lipoamide to form *S*-(2-methylpropanoyl)dihydrolipoamide with release of CO_2. Thiamine diphosphate is a coenzyme. *See also* **[3-methyl-2-oxobutanoate dehydrogenase (lipoamide)] kinase**.

[3-methyl-2-oxobutanoate dehydrogenase (lipoamide)] kinase EC 2.7.1.115; *other name*: branched-chain α-keto-acid dehydrogenase kinase; an enzyme that catalyses the phosphorylation by ATP of [3-methyl-2-oxobutanoate dehydrogenase (lipoamide)] with release of ADP, thereby inactivating the enzyme complex.

[3-methyl-2-oxobutanoate dehydrogenase (lipoamide)]-phosphatase EC 3.1.3.52; *other name*: branched-chain oxo-acid dehydrogenase phosphatase; an enzyme that catalyses the hydrolysis of phosphate from [3-methyl-2-oxobutanoate dehydrogenase (lipoamide)] phosphate.

Methyl Red a dye used as an indicator, changing from red to yellow over the pH range 4.2–6.3.



methylsulfonyl nitrophenyl carbonate 2-(methylsulfonyl)ethyl 4-nitrophenyl carbonate; a reagent used for the introduction of the **MSOC** amino-protecting group.

methylsulfonyl succinimidyl carbonate 2-(methylsulfonyl)ethyl *N*-succinimidyl carbonate; a reagent used for the introduction of the **MSOC** amino-protecting group.



5-methyltetrahydrofolate *abbr.*: MeTHFA *or* 5-CH_3-H_4folate; a member of the tetrahydrofolate group of coenzymes. It is an intermediate in the methylation of vitamin B_{12}, which can then react with homocysteine to form methionine. The methyl group of MeTHFA is derived from C-3 of serine via 5,10-methylene H_4folate.



methyltetrahydrofolate trap hypothesis a hypothesis to explain the accumulation of 5-methyltetrahydrofolate (5-CH_3-H_4folate) in the sera of patients with vitamin B_{12} deficiency. It suggests that, because the only route by which 5-CH_3-H_4folate can be converted to H_4folate (required for single-carbon transfer reactions) is by the vitamin B_{12}-dependent 5-methyltetrahydrofolate–homocysteine *S*-methyltransferase (EC 2.1.1.13) reaction, a large proportion of the body's available folate becomes trapped as 5-CH_3-H_4folate, leading to folate deprivation.

methylthioribose 5-methylthio-D-ribose; an intermediate in the **methionine salvage pathway**.

methyltransferase any enzyme of sub-subclass EC 2.1.1, members of which catalyse the transfer of a methyl group. *See also* ***che***, ***O*^{6}-methylguanine**.

4-methylumbelliferyl *abbr.*: MU; a group that is attached in glycosidic linkage to various sugars to form substrates useful in the assay of glycosidases. The highly fluorescent 4-methylumbelliferone is released on enzyme action, and can be measured in alkaline solution by its fluorescence (max. 448 nm, excitation at 364 nm), which is quenched in the glycosidic substrate. *See also* **MUG**.



4-methylumbelliferone

methyne *or (formerly)* **methine** *the name now recommended for* the trivalent diatomic group, =CH–, attached to two other groups in an organic molecule. Such a group is commonly still known in biochemistry as **methene**. *Compare* **methylidyne**.

meticillin (sodium) *or* **methicillin** a semisynthetic antibiotic of the **penicillin** type that is lactamase resistant.



metJ the gene for the repressor (co-repressor is *S*-adenosylmethionine) of the methionine biosynthetic operon, and also *metJ* itself, in *Escherichia coli*. The repressor protein undergoes dimeric binding to DNA by a motif other than a helix-turn-helix.

Met-Lys-bradykinin *a short name for* methionyllysylbradykinin; *see* **bradykinin**.

MetMb *abbr. for* metmyoglobin (i.e. **ferrimyoglobin**).

metmyoglobin *abbr.*: MetMb; *an old name for* **ferrimyoglobin**.

'me too drug' a drug that uses the same therapeutic mechanism as an existing drug, offering no significant additional benefit. Notwithstanding the negative connotations of the term 'me too', such products compete directly with those currently on the market, and hence may help to push prices down.

metre *or (US)* **meter** *symbol*: m; the SI base unit of length, equal to the length of the path travelled by light in a vacuum during a time interval of 1/299 792 458 of a second.

metre–kilogram–second system (of electrical units) *abbr.*: mks system *or* MKS system; a system of electrical (physical) units based on the metre, kilogram, and second as fundamental units of measurement. It has now been superseded by the **SI** system of units.

metric 1 of, or relating to, the metre or the metric system. **2** quantitative.

+metric *see* **+meter**, **+metry**.

metric system a system of weights and measures, devised in France (1793–95), based on the principle that each of the physical quantities length, volume, and mass should be defined in terms of one unit whose multiples and submultiples are related by powers of ten and that all three units should be simply interrelated. The units were, respectively, the metre, the litre (one cubic decimetre), and the gram (the mass of one cubic centimetre of water at its maximum density). It has now been supplanted by the International System of Units (*see* **SI**).

metridin 1 a 36-amino acid, 3.97 kDa toxin from *Metridium senile* (brown sea anemone). **2** *or* **metridium proteinase A** EC 3.4.21.3; *other name*: sea anemone protease A; an enzyme that catalyses the preferential cleavage: Tyr-|-Xaa > Phe-|-Xaa > Leu-|-Xaa; it has little action on Trp-|-Xaa.

metridium proteinase A *see* **metridin** (def. 2).

metrizamide *the trivial name for* 2-[3-acetamido-5-(*N*-methylacetamido)-2,4,6-triiodobenzamido]-2-deoxy-D-glucose; a dense, synthetic, nonionic substance, highly soluble in water, that is capable of forming (nonautoclavable) aqueous solutions of densities up to 1.3 g cm^{-3}, useful as media for **isopycnic centrifugation** of biological particles.



metrizoate *the trivial name for* the 3-acetamido-5-(*N*-methylacetamido)-2,4,6-triiodobenzoate anion; a dense, synthetic substance used primarily as its sodium salt, which is highly soluble in water and capable of forming autoclavable aqueous solutions of densities up to 1.4 g cm^{-3}, or more, such solutions being useful as media for **isopycnic centrifugation** of biological particles.



metronidazole 2-methyl-5-nitroimidazole-1-ethanol; an antibiotic used to treat a variety of bacterial and parasitic infections, such as amebiasis, trichomoniasis, and giardiasis. It is a prodrug, which is converted by reduction to a cytotoxic radical.



metronidazole radical

+metry *comb. form* denoting the process or science of measuring (something indicated or specified). —**+metric** *adj.*

metyrapone 2-methyl-1,2-di(3-pyridyl)propan-1-one; an inhibitor of the enzyme 11*β*-hydroxylase (steroid 11*β*-monooxygenase; EC 1.14.15.4); this enzyme is involved in the synthesis of cortisone, cortisol and aldosterone, its inhibition causing a rise in **corticotropin** secretion as a result of release from negative feedback on the pituitary by cortisol. Metyrapone is used in **challenge** tests of hypothalamic-pituitary function and sometimes in the treatment of **Cushing's syndrome**.



MeV *symbol for* megaelectronvolt (i.e. 10^6 electronvolts).

Mevacor *a proprietary name for* **lovastatin**.

mevaldate 1 the anion $OHC–CH_2–C(CH_3)(OH)–CH_2–COO^-$ derived from mevaldic acid; its (*R*)-enantiomer occurs as an enzyme-bound intermediate during the conversion of hydroxymethylglutaryl-coenzyme A to mevalonate in the biosynthesis of polyprenyl compounds. **2** any salt or ester of mevaldic acid.

mevalonate 1 the anion, $HO–[CH_2]_2–C(CH_3)(OH)–CH_2–COO^-$, derived from mevalonic acid; its (*R*)-enantiomer is a strategic intermediate derived from hydroxymethylglutaryl-CoA in the biosynthesis of polyprenyl compounds. **2** any salt or ester of mevalonic acid.



(*R*)-mevalonate

mevalonate kinase a hepatic peroxisomal enzyme (396 and 395 amino acids in human and rat, respectively) that phosphorylates mevalonate to form mevalonic acid-5-phosphate in the metabolic pathway that leads to cholesterol and other isoprenoid compounds. Severe deficiency of the enzyme leads to **mevalonic aciduria**. Less severe deficiency (5–15% of normal activity) leads to **hyper-IgD syndrome**.

mevalonic aciduria a rare, severe, autosomal recessive disease with increased plasma levels of mevalonate and pronounced mevalonic aciduria, and characterized by dysmorphic features, hepatosplenomegaly, and severe developmental delay. It is caused by several mutations in the gene at 12q24 for **mevalonate kinase** that lead to severe deficiency of this enzyme. *Compare* **hyper-IgD syndrome**.

mevalonolactone mevalonic acid lactone; it is hydrolysed in cells to mevalonate, and is often the form in which mevalonate is administered to animals or cells, either radioactively or non-radioactively as a metabolic precursor.



mevalonoyl the acyl group, HO–$[CH_2]_2$–$C(CH_3)(OH)$–CH_2–CO–, derived from mevalonic acid.

mevastatin *or* **compactin** 6-demethylmevinolin; a substance isolated from *Penicillium citrinum*; it is a potent inhibitor of **HMG-CoA reductase** with actions similar to **lovastatin**.



Mevinacor *a proprietary name for* **lovastatin**.

mevinolin *an alternative name for* **lovastatin**.

Meyerhof pathway *see* **Embden–Meyerhof pathway**.

Meyerhof quotient an index of the effect of the presence or absence of dioxygen on glycolysis or fermentation. It is: [(rate of anaerobic fermentation) – (rate of aerobic fermentation)]/(rate of dioxygen uptake). Assuming 6 mol ATP are formed per mol dioxygen used, a Meyerhof quotient of 6 would mean that aerobic and anaerobic energy supply are the same; a lower value indicates an increase in ATP-supplying and ATP-requiring processes on transition from anaerobic to aerobic conditions. [After Otto Fritz Meyerhof (1884–1951), German physiologist and biochemist.]

mfd *abbr. for* microfarad.

***Mfl*I** a type 2 **restriction endonuclease**; recognition sequence: [AG]↑GATC[TC]. *Xho*II is an **isoschizomer**.

mg *symbol for* milligram (i.e. 10^{-3} gram).

Mg *symbol for* magnesium.

Mgm1 a yeast dynamin-like protein that forms a ring on the outer surface of the inner mitochondrial membrane to bring about fission of the organelle. Homologues occur in animals and plants.

MHC *abbr. for* major histocompatibility complex.

MHC class II deficiency the deficiency or absence of MHC class II antigens on lymphocytes and macrophages, which leads to abnormal susceptibility of humans to infections. It results from mutations in any component of the heterotrimeric **RFX** complex, which binds a part of the response element in the promoter region of MHC class II genes. *See* **major histocompatibility complex**.

mho a practical unit of electric conductance equal to the reciprocal of the impedance measured in ohms. For circuits containing only noninductive resistance the **siemens** is the preferred unit.

MHS *abbr. for* major histocompatibility system (i.e. **major histocompatibility complex**).

MIC *abbr. for* minimum inhibitory concentration.

mica substrate technique a technique used in preparing specimens of macromolecules for electron microscopic examination. Freshly cleaved mica is used to support the specimen during shadowing with a metal; a backing film of carbon is then applied by evaporation normal to the shadowed surface, and both films are transferred to the grid.

micelle 1 an aggregate, of colloidal dimensions, of oriented molecules of amphipathic substances existing in equilibrium in solution with the chemical species from which it is formed; micelles are generally electrically charged. In aqueous solution the individual molecules of the micellar aggregate are oriented with their polar groups pointing towards the aqueous medium and their hydrophobic moiety directed into the centre of the micelle. **2** a hypothetical ordered region in a natural fibre such as cellulose. **—micellar** *adj.*

micellization *or* **micellisation** transformation into micelles.

micF a regulatory gene in the osmoregulatory system in *Escherichia coli*; *micF* RNA and *ompF* mRNA (omp = outer membrane protein) are induced by interaction of *ompR* with a common divergent, central promoter region. *micF* RNA is partly complementary to the Shine–Dalgarno region of *ompC* and thus represses its expression by translational control.

Michaelian of, relating to, or described by **Michaelis kinetics**.

Michaelis kinetics *or* **Michaelis–Menten kinetics** *or* **Henri–Michaelis–Menten kinetics** a model to explain the kinetics of an enzyme-catalysed reaction,

$$E + S \underset{k_{-1}}{\overset{k_{+1}}{\rightleftharpoons}} ES \xrightarrow{k_{cat}} E + P$$

where E is enzyme, S is substrate, ES is an intermediate complex (the **Michaelis complex**), and P is product. The initial velocity of the reaction, v, when $[P] = 0$, is given by the **Michaelis equation** (or **Michaelis–Menten equation** or **Henri–Michaelis–Menton equation**):

$$v = V[S]/(K_m + [S]) = d[P]/dt$$

in which V is the limiting or maximal reaction rate (i.e. that occurring when the enzyme is saturated with substrate), and the **Michaelis constant**, K_m, is given by:

$$K_m = (k_{-1} + k_{cat})/k_{+1}.$$

If $k_{cat} << k_{+1}$, then K_m approximates to K_s, the enzyme–substrate dissociation constant (usually known as the **substrate dissociation constant**). K_m and V are known as the **Michaelis parameters**. *Compare* **Dalziel coefficient**. [After V. Henri (1872–1940), French physical chemist; Leonor Michaelis (1875–1949), German physician and biochemist; and Maude Menten (1879–1960), Canadian physician and biochemist.]

Michaelis pH function any one of a set of functions relating hydron concentration, $[H^+]$, to the acid dissociation constants for different stages of dissociation of a given polybasic acid.

Consider first the simplest example, that of a symmetrical dibasic acid, AH_2 (e.g. succinic acid). This can exist in three stages of dissociation, represented by the equilibria

$$AH_2 \overset{K_1}{\rightleftharpoons} AH^- \overset{K_2}{\rightleftharpoons} A^{2-}$$

where K_1 and K_2 are the acid dissociation constants for the respective stages of dissociation. For such a dissociation there are three Michaelis pH functions, f_0, f_1, and f_2, which are defined thus:

$$f_0 = 1 + K_1/[H^+] + K_1K_2/[H^+]^2$$

$$f_1 = 1 + [H^+]/K_1 + K_2/[H^+]$$

$$f_2 = 1 + [H^+]/K_2 + [H^+]^2/K_1K_2$$

The total concentration of acid of all forms, $[A]_t$, is given by

$$[A]_t = [AH_2] + [AH^-] + [A^{2-}];$$

by substitution for K_1 and K_2 it can be shown that

$$[\mathrm{A}]_t = f_0[\mathrm{AH}_2] = f_1[\mathrm{AH}^-] = f_2[\mathrm{A}^{2-}]$$

Hence it will be apparent that the reciprocals of the respective pH functions give the fractional concentrations of the various ionic forms of the acid at a given pH value. The theory of pH functions is independent of the chemical nature of the ionizing groups: the functions apply equally to molecules with identical ionizing groups (e.g. dicarboxylic acids, as above), to ampholytes (e.g. amino acids), and to molecules or parts of molecules in which the nature of the ionizing groups may not be known (e.g. the active centres of enzymes). For an unsymmetrical dibasic acid there are potentially four ionic forms, four dissociation constants, and thus four pH functions, but these are important in practice only if the p*K* values of the two dissociating groups are fairly close, as could be the situation at an active centre of an enzyme. If, on the other hand, the p*K* values are widely separated, as is the case with a typical amino acid, then there is effectively only one intermediate form and a set of three pH functions as above may be considered to apply.

micr+ *see* **micro+** (def. 2).

micra a plural of **micron**.

micRNA *abbr. for* messenger-RNA-interfering complementary RNA (i.e. **antisense RNA**).

micro **1** (concerning something) very small (e.g. micro method). **2** short for a microcomputer.

micro+ **1** *symbol*: μ; the SI prefix denoting 10^{-6} times. **2** *or (sometimes before a vowel)* **micr+** denoting very small or concerned with very small things (e.g. microbiology, microsome); abnormally small, underdeveloped (e.g. microcyte); on a small scale or concerned with small quantities (e.g. microanalysis, microbalance); of a small area or volume, or small part of a larger one (e.g. microenvironment). *Compare* **macro+**. **3** indicating amplification or magnification of something very small (e.g. microphone, microscope). **4** involving the use of a microscope (e.g. micrograph).

microaerophilic **1** describing an aerobic environment with a lower partial pressure of dioxygen than that under normal atmospheric conditions. **2** describing an organism whose maximal rate of growth occurs in such an environment.

microalbuminuria the excretion of plasma albumin in the urine at a rate above the normal range of values (5–20 μg min^{-1}) but below the threshold level (300 μg min^{-1}) for detection by routine dipstick methods and measurable only by radioimmunoassay (or other techniques of comparable sensitivity). The condition is associated with a general increase in vascular permeability and forms a sensitive indicator of diabetic nephropathy.

microanalysis any technique whereby very small amounts of substance may be analysed qualitatively or quantitatively. The term was originally used to indicate analysis of substances in the range 1–10 mg. —**microanalytic** *or* **microanalytical** *adj.*

microarray *or* **DNA chip** *or* **DNA microarray** *or* **gene expression array** a glass slide or bead whose surface bears numerous microscopic samples of DNA or other reagent in an orderly pattern. Microarrays are most commonly used for the simultaneous measurement of the expression levels of large numbers of genes. For example, entire cloned cDNA sequences or oligonucleotides can be bound to the slide, either by means of a robotic spotter or by direct synthesis on the array. A single slide may contain tens of thousands of spots, or addresses, each containing a copy of a specific DNA sequence. cDNA samples that have been reverse transcribed from a cellular RNA extract are then fluorescently labelled and hybridized to the array. The array is scanned with a fluorescent scanner, and the data collected and automatically analysed to quantify the relative amount of fluorescence and hence the relative levels of expression of each gene. *See also* **GeneChip array**.

microassay any technique whereby very small amounts of substance may be assayed. *Compare* **microanalysis**.

microbalance any balance designed to weigh very small quantities, typically between 1 μg and 1 mg.

microbe *a common term for* a microorganism, especially a pathogenic bacterium. —**microbial** *adj.*

microbial collagenase EC 3.4.24.3; *other names*: *Clostridium histolyticum* collagenase; clostridiopeptidase A; collagenase A; collagenase I; an enzyme that catalyses the digestion of native collagen in the triple-helical region at Xaa-|-Gly bonds. Some preference is shown for Gly at P3 and P1′, Pro and Ala at P2 and P2′, and hydroxyproline, Ala, or Arg at P3′ (*see* **peptidase P-sites**).

microbiological of, pertaining to, or concerned with microbiology; effected by microorganisms.

microbiological assay any assay for a substance, especially an amino acid or vitamin, that is based on the extent of growth of a microorganism for which the analyte in question is an essential growth factor.

microbiology the science concerned with microorganisms, and with their interactions with other organisms and the environment. —**microbiologist** *n.*

microbody a cytoplasmic organelle, spherical or oval in shape, and 0.1–1.5 nm across, that is bounded by a single membrane and contains oxidative enzymes, especially those utilizing H_2O_2. Microbodies include **glyoxysomes** and **peroxisomes**.

microbore high-pressure liquid chromatography *or* **microbore HPLC** *a variant of* **high-pressure liquid chromatography** in which a column of only about 1 mm diameter is used. The advantages of the technique include greater sensitivity and a much reduced solvent consumption.

microcalorimeter a **calorimeter** designed to measure continuous power outputs down to 1 μW, or heat pulses down to 200 μJ. —**microcalorimetry** *n.*; **microcalorimetric** *adj.*

microcapsule any very small thin-walled capsule of plastic, wax, etc., containing a liquid, powder, etc., from which the contents may be released (by heat, impact, radiation, dissolution, or other means) in order to fulfil some specific function. *See also* **microencapsulation**.

microcarrier any of a number of preparations of finely particulate, nontoxic, nonrigid, usually transparent material of density close to unity, e.g. dextran-based beads, that enable the growth of animal cells in suspension culture, especially on a large scale. Microcarriers permit the growth of anchorage-dependent cells as a monolayer on the surface of the particles. Generally, the cells may be easily harvested, e.g. by allowing the particles to settle and then treating with a proteinase such as trypsin.

microcell **1** a small, experimentally produced eukaryotic cell-like structure in which a limited amount of genetic material is contained in a micronucleus surrounded by a rim of cytoplasm and an intact cell membrane. It is useful as a vector for the transfer of a small number of chromosomes into a normal cell by virus-induced cell fusion. **2** any small **cell** (def. 2), commonly with a capacity less than 1 mL.

microchemistry chemistry on a very small scale, commonly handling less than 1 mg or 1 mL of material and often requiring special small apparatus. —**microchemical** *adj.*

microcin any of a number of microbial peptide toxins that have antibiotic action. They are of diverse structure and action. Examples include microcin E492, a 6 kDa polypeptide antibiotic. It forms cation-selective channels in planar phospholipid bilayers, leading to a loss of membrane potential. Another example is microcin B17 from *E. coli*. This is a glycine-rich peptide that inhibits DNA gyrase (*see* **(DNA) topoisomerase** type II). Microcin is classified in the TC system under number 1.C.58.

micrococcal of, pertaining to, or produced by micrococci; being a member of the genus ***Micrococcus***.

Micrococcus a genus of Gram-positive, strictly aerobic, usually nonmotile coccoid bacteria of the family Micrococcaceae. The cells are commonly 1–2 μm in diameter.

microconcentrator a commercial device for the concentration and desalting of ‘small’ volumes (i.e. ≤2 mL) of biological samples.

microcrystal any very small crystal, especially one that is visible only under a microscope. —**microcrystalline** *adj.*

microcurie *symbol*: μCi *or (formerly)* μc; a unit of (radio)activity or of radioactive material equal to 10^{-6} **curie** or 3.7×10^4 becquerel.

microdeletion a DNA/chromosomal deletion that is not detectable by conventional techniques such as **Southern blotting** or microscopy.

microdensitometry the measurement of **absorbance** (i.e. optical density) over a very small finite area, such as that viewed by an optical microscope. —**microdensitometric** *adj.*; **microdensitometer** *n.*

microdialyser *or (sometimes, esp. US)* **microdialyzer** a device for

microdialysis, especially one designed to minimize loss and dilution of samples.

microdialysis dialysis of a sample of small volume (commonly of less than 1 mL).

microdiffusion analysis *see* **Conway microdiffusion method**.

microdissection the dissection of small organisms or parts of organisms by means of mechanically controlled instruments viewed through an optical microscope.

microelectrode any electrode in which the sensitive element is very small and also often needle-like. It is useful for investigation of electrical phenomena in individual cells or in very small volumes.

microencapsulation the act or process of enclosing substances, solutions, etc. in **microcapsules**.

microenvironment a very small domain of the environment, such as that surrounding a single molecule or a functional group of a molecule, a single cell or organism, or a small group of cells or organisms. The term is used especially to distinguish zones of local difference in the overall environment.

microfarad *abbr*.: mfd; *symbol*: µF; a unit of capacitance equal to 10^{-6} **farad**.

microfibre *or (US)* **microfiber** any fibre having a diameter in the range 0.1–1 µm, such as used in making glass microfibre filters.

microfibril any small fibril occurring in biological material that is distinguishable only by electron microscopy, especially one of a set that make up a fibril, e.g. in cellulose. **—microfibrillar** *adj.*

microfibrillar polysaccharide one of three groups of cell-wall polysaccharides characterized by solubility differences: the main component in the plant kingdom is **cellulose** but **chitin** is found in some fungi, β-1,4-mannans in some green algae (e.g. Codiaceae), and β-1,3-xylans in other green algae (e.g. Bryopsidaceae).

microfilament a type of **actin filament** that contributes to the cytoskeleton of eukaryotic cells. Microfilaments are elongated structures consisting of two strands of globular **actin** monomers twisted into a helix with 13.5 molecules per turn. Microfilaments form the major component of the cell's contractile machinery and are implicated in cell division, cell movement, muscle contraction, nerve outgrowth, tubular gland formation, gastrulation, and neurulation. *Compare* **intermediate filament**, **microtubule**.

microfilter 1 any small filter, especially as used in microchemistry. **2** *see* **microporous filter**.

microfiltration filtration with a **microporous filter**.

microflora 1 *a collective name for* very small plants. **2** the flora of a **microhabitat**. **3** *a collective name for* all the microorganisms of a tissue or organ of an animal.

microfluorimeter an instrument for **microfluorimetry**.

microfluorimetry the measurement of intensity of fluorescence over a very small finite area, such as a single cell viewed under an optical microscope. **—microfluorimetric** *adj.*

microfold cell *see* **M cell**.

microforge a device by means of which micropipettes, very small glass tools, etc. can be made while being viewed under a low-power microscope.

microfungus (*pl.* **microfungi**) any fungus whose vegetative thallus or fruiting body is too small to be seen easily with the unaided eye. *Compare* **mould**.

microglobulin 1 any plasma **globulin** molecule or globulin fragment of less than ≈40 kDa, e.g. **Bence-Jones protein**, **β$_2$-microglobulin**. **2** *a term sometimes used to refer to* 7S immunoglobulins such as IgG. *Compare* **macroglobulin**.

β$_2$-microglobulin *or* **betamicroglobulin** a human plasma protein, of 11.8 kDa and containing 99 amino-acid residues, that in size, primary structure, and tertiary structure strongly resembles a single domain of the constant region of immunoglobulin molecules: it is a constituent of class I **major histocompatibility complexes**. Plasma levels may be elevated in hepatobiliary disease, chronic active hepatitis, and alcohol-induced liver cirrhosis.

microgram 1 *symbol*: µg *or (esp. in pharmacy)* mcg; a unit of mass equal to 10^{-9} kilogram or 10^{-6} gram; *formerly called* gamma (*symbol*: γ). **2** *an alternative name (sometimes) for* **micrograph**.

micrograph *or (sometimes)* **microgram** a graphic reproduction of the image of an object as seen through a microscope.

microhabitat any habitat that is small or limited in extent and differs in character from a larger, surrounding habitat.

microheterogeneous describing a preparation of a biopolymer that superficially appears to be homogeneous but that, on refined analysis, shows slight differences in size, sequence, charge, state of aggregation, or other properties of its molecules. Such differences are believed, at least in some instances, to be attributable either to artefactual changes or to genetic differences. **—microheterogeneity** *n.*

microincineration a technique for examining the distribution of minerals in tissue sections or microorganisms. The specimen is placed on a slide, the organic material burned away in a furnace, and the nature and position of the mineral ash determined by microscopy.

microinject to inject liquid into a single cell or nerve fibre using a micropipette. **—microinjection** *n.*

microiontophoresis **iontophoresis** (def. 2) applied to very small areas of tissue.

micro-Kjeldahl method an adaptation of the **Kjeldahl method** for determining small amounts of nitrogen, in the range 0.1–1.0 mg. A correspondingly small flask, commonly known as a **micro-Kjeldahl flask**, is used for the digestion, and a **Markham still** may be used for the steam distillation.

microlitre *or (esp. US)* **microliter** *symbol*: µL *or* µl; a unit of volume equal to 10^{-6} litre; *formerly called* **lambda** (*symbol*: λ).

micromanipulation the techniques and practice of performing very delicate operations, such as microdissection, microinjection, or the isolation of single cells, under an optical microscope, usually with the aid of a **micromanipulator**.

micromanipulator an instrument used in conjunction with an optical microscope for holding and manipulating very small instruments and specimens in the field of view.

micrometer 1 any instrument or device for measuring very small distances or angles. **2** *or* **micrometer gauge** a device for measuring small distances, thicknesses, diameters, etc. with great accuracy. **3** *the US spelling of* **micrometre**.

micrometer burette a **micrometer syringe** adapted for use as a burette.

micrometer pipette a **micrometer syringe** adapted for use as a pipette.

micrometer screw a screw with a fine thread of accurate and consistent pitch.

micrometer syringe a syringe for the accurate delivery of small volumes of liquid in which the plunger of the syringe is driven by a calibrated micrometer screw.

micrometre *or (US)* **micrometer** *symbol*: µm; a unit of length equal to 10^{-6} metre; *formerly called* **micron** (*symbol*: µ).

micromicro+ *symbol*: µµ *a former name for* **pico+**.

micromodification alteration of the covalent structure of a macromolecule, especially a histone, by the addition of various groups, e.g. acetyl, methyl, phosphate, after the initial biosynthetic process is terminated.

micromolar *symbol*: µM *or* µM; describing a solution containing one micromole of solute per litre of solution, or a specified multiple or fraction thereof; used also of an amount-of-substance concentration similarly expressed.

micromole *symbol*: µmol; a unit of amount of substance equal to 10^{-6} mole.

micromolecule any (type of) molecule composed of a relatively small number of atoms. In practice the term is usually taken to mean any (type of) molecule that is capable of passing through the pores of dialysis tubing (as generally used) and that thus has a mass less than about 10 kDa. **—micromolecular** *adj.*

micron (*pl.* **microns** *or* **micra**) *symbol*: µ; *a former term for* **micrometre**.

micronucleus a eukaryotic cell nucleus with less than the normal complement of chromosomes, produced experimentally by incubation of a cell with colchicine. **—micronuclear** *adj.*

micronutrient any chemical element that is required by living organisms in tiny quantities only, also known as **trace element**. The term is often extended to include organic compounds such as vitamins.

microorganism any noncellular or unicellular (including colonial) organism, most of which are too small to be seen with the unaided eye. Microorganisms comprise bacteria (including cyanobacteria), lichens, microfungi, protozoa, rickettsiae, virinos, viroids, and viruses, and also some algae; all prokaryotes are included. *See also* **microbe**.

microperoxisome *(sometimes)* a type of small **peroxisome**, 150–250 nm in diameter, found in all mammalian cells.

microphthalmia transcription factor *see* **MITF**.

micropinocytosis *(sometimes)* a form of **pinocytosis** occurring in higher animals, especially in the transfer of dissolved macromolecules from the blood to the cytoplasm of cells, in which the pinosomes formed are very small (**micropinosomes**) and can only be observed in the electron microscope.

micropipette *or (US)* **micropipet** any pipette calibrated to contain or deliver a volume in the range 5–500 μL.

micropore any pore (in a gel or porous solid) whose width does not exceed about 2.0 nm. *Compare* **macropore**, **mesopore**. **—microporous** *adj.*

microprocessor a single integrated electronic circuit designed to carry out a specific set of operations, e.g. as the central processor of a computer or a control system.

Microprocessor the smaller of two nuclear complexes containing **Drosha** and **Pasha** and involved in processing **pri-miRNA** to **pre-miRNA**.

microRNA *see* **miRNA**.

microsatellite a repeating DNA segment that is similar to a **minisatellite** except that the overall range of size is smaller and the base core repeat unit involves a two or four nucleotide pair repeat motif. They are so named because of their resemblance to **satellite DNA** in having tandem repeats. The number of copies of the repeats varies not only between individuals but also between the two chromosomes of a pair. Their highly polymorphic nature has made them invaluable for analysis of pedigrees and in linkage analysis.

microscope an instrument consisting of a lens or a combination of lenses that uses light or other electromagnetic radiation to make enlarged images of objects that are invisible to, or not easily seen by, the unaided eye. *See also* **electron microscope**, **phase-contrast microscopy**.

microscopic **1** of a size that is not visible (in detail) to the unaided eye. **2** concerned with small units. **3** relating to the behaviour of individual molecular entities. **4** *or* **microscopical** of, pertaining to, or using a microscope. *Compare* **macroscopic**. **—microscopically** *adv.*

microscopic equilibrium constant any constant describing the equilibrium of the interconversion of two particular molecular entities. *Compare* **intrinsic constant**, **macroscopic equilibrium constant**.

microscopic reversibility a thermodynamic principle requiring that at equilibrium the reaction pathway for the reverse of any particular chemical reaction is the exact opposite of the pathway for the forward reaction, i.e. both forward and backward reactions must pass through the same transition states or intermediates and occur with equal frequency.

microscopy the art and practice of using a microscope; investigation with a microscope.

microsecond *symbol*: μs; a unit of time equal to 10^{-6} second.

microsequenator an apparatus for microsequencing (*see* **microsequence**).

microsequence to **sequence** (def. 3) a biopolymer using a very small sample, e.g. 5–100 pmol of a protein.

microsolute *an operational term used to describe* any diffusible solute in a solution that also contains nondiffusible macromolecular solute(s).

microsomal of, pertaining to, or containing **microsomes**; being in the **microsomal fraction** of a homogenate of a cell or tissue.

microsomal fraction *an operational term for* the subcellular fraction of a homogenate of a eukaryotic cell or tissue that, on differential centrifugation, is sedimented at 10^5 *g*; the fraction from some tissues, such as liver, although consisting largely of microsomes, commonly also contains free ribosomes and fragments of the plasma membrane, of the Golgi apparatus, of mitochondria, and of other subcellular structures. The morphological constituents differ according to the tissue from which the fraction was derived.

microsomal triglyceride transfer protein a protein of the endoplasmic reticulum involved in the assembly and secretion of apolipoprotein B-containing plasma lipoproteins in intestinal mucosa and liver. It is a heterodimer of an 88 kDa subunit and a protein disulfide isomerase. Mutations in the gene for the first subunit, at 4q22-q24 (which encodes an 894-residue protein), are associated with **abetalipoproteinemia**.

microsome any of the small, heterogeneous, artefactual, vesicular particles, 50–150 nm in diameter, that are formed when some eukaryotic cells are homogenized and that sediment on centrifugation at 10^5 *g*. Microsomes are formed mostly from disrupted endoplasmic reticulum membranes but some arise from the plasma membrane. Those formed from rough endoplasmic reticulum are studded with ribosomes on the outside (**rough microsomes**); those formed from smooth endoplasmic reticulum and from plasma membrane have no adhering ribosomes (**smooth microsomes**).

microspectrophotometer an instrument, consisting of a microscope and a spectrophotometer, used for measuring light of selected frequencies passing through, or reflected from, a very small specimen, e.g. a cell or a subcellular structure.

microspectrophotometry **spectrophotometry** applied to a very small specimen, using a microspectrophotometer. **—microspectrophotometric** *adj.*

microsphere one of a preparation of spherical particles of known and uniform size, usually in the range 10–40 μm in diameter, and prepared from, e.g., serum albumin or an ion-exchange resin, that may be labelled with an appropriate radionuclide and used in studies of the circulation of the blood in health or disease.

microspore the smaller of the two types of spores produced by the heterosporous plants. In seed plants the microspore is the cell from which the pollen grain develops. **—microsporous** *adj.*

microstructure *an alternative term for* **fine structure**.

microsyringe a syringe for delivering volumes of gases or liquids in the range 0.1–500 μL.

microtitre plate *or (esp. US)* **microtiter plate** any rectangular plate usually made of polycarbonate and containing wells in a gridlike pattern. Most usually the plate has 96 wells arranged in the form of eight rows of 12 columns, each well having a capacity of a few hundred microlitres. They are commonly used for **enzyme-linked immunosorbent assay** (ELISA) or other immunological reactions, or for the growth of small cultures of microorganisms or eukaryotic cells.

microtome an instrument for cutting thin sections of objects, e.g. tissues or cells, preparatory to microscopic observation.

microtrabecular lattice an irregular, three-dimensional lattice of very fine strands, up to 15 nm in diameter, sometimes termed **microtrabeculae**, that can be visualized in the cytoplasmic ground substance of eukaryotic cells by high-voltage electron microscopy. It forms part of the cytoskeleton.

microtubule any of the long, generally straight, hollow tubes of internal diameter 12–15 nm and external diameter 24 nm found in a wide variety of eukaryotic cells. Each consists (usually) of 13 protofilaments of polymeric **tubulin**, staggered in such a manner that the tubulin monomers are arranged in a characteristic helical pattern on the surface, and with the α/β axes of the tubulin parallel to the long axis of the tubule. Microtubules exist in equilibrium with a pool of tubulin monomers in the cytoplasm and can be rapidly assembled and disassembled in response to various physiological stimuli; there are also a number of **microtubule-associated proteins**. Most microtubules in a cell appear to be initiated at **microtubule-organizing centres** and some may also become attached to the **kinetochores**. Microtubules are involved in force generation in cilia and flagella, where they exist in a characteristic 9 + 2 array (a ring of nine doublet microtubules with two single microtubules in the centre), and the integrity of the microtubule network appears to be necessary for certain aspects of mitotic spindle function and for the saltatory movement of cell organelles. Taxol prevents depolymerization of microtubules, and is thus antimitotic. *Compare* **intermediate filament**, **microfilament**.

microtubule-associated protein *abbr.*: MAP; any protein that binds to **microtubules**, and modifies their properties, including proteins that induce polymerization of purified tubulin and become associated with the newly formed microtubules. Many different kinds have been found, including structural proteins and motor proteins. MAP 1 is a structural protein involved in the filamentous cross-bridging between microtubules and other skeletal elements. The role of MAP2 is unclear; in neuronal cells, it is confined to the cell body and dendrites. It changes structurally during development by alternative splicing mechanisms. **Dynein** is an example of a motor protein MAP. *Compare* **tau protein**. *See also* **MAP kinase**.

microtubule-organizing centre a region near the centre of a eukaryotic cell consisting typically of two **centrioles** at right angles to each other and surrounded by a complex of associated proteins. The centrioles and their satellite proteins serve as initiating sites for the assembly of microtubules.

microvillin a protein of the microvilli of rat mammary cells, M_r 200 000.

microvillus (*pl.* **microvilli**) any of the very small, finger-like projections that occur on the exposed surfaces of epithelial cells, especially where cellular function requires a maximal surface area for absorption or secretion, as in the proximal renal tubule and the small intestine, where they constitute the brush border. The projections are about 1–2 μm long and 100 nm in diameter. The core of a microvillus contains a bundle of about 40 actin filaments of uniform polarity with their 'barbed' (+) ends anchored in a cap of ill-defined amorphous material in the microvillar tip. At the base the actin filaments extend into the perpendicular network, also made up largely of actin, known as the terminal web. In the core the actin filaments are bound together by the actin-binding proteins fimbrin and villin. The renal and intestinal microvilli contain a wide range of hydrolases that are integral membrane proteins; their hydrophilic domains, containing the catalytic sites, face outwards from the cell. —**microvillar** *adj.*

microvolume a very small volume, commonly in the range 1–100 μL.

microwave radiation electromagnetic radiation of wavelengths in the range 1–300 mm (frequencies 1–300 GHz), lying between infrared radiation and most radiofrequency radiation.

Midas *abbr. for* metal-ion-dependent adhesion site; a region that binds Ca^{2+} in the N-terminal region of the β chain of some **integrins**.

middle molecule *a term sometimes used for* any compound in the range 350–2000 Da that accumulates in the body fluids of persons with uremia.

middle T antigen *see* **T antigen** (def. 1).

midkine *other names*: neurite outgrowth-promoting protein; midgestation and kidney protein; amphiregulin-associated protein (*abbr.*: ARAP); a heparin-binding growth/differentiation factor with neurite-promoting activity. It is a cell-surface or basement-membrane protein, induced by retinoic acid and similar to **pleiotrophin**. The midkine gene product is primarily detected in the embryonic period, whereas pleiotrophin is expressed most strongly in the early neonatal period.

midnight zone *(in sequence analysis)* a region of identity where sequence comparisons fail completely to detect structural similarity. Falling in the lower reaches of the **twilight zone**, it represents the theoretical limit of sequence-based comparison methods.

midpoint 1 the point on a line, or a graph, that is equidistant from either end of the line or from two inflections in the graph. **2** a point in time that is half way between the beginning and the end of an event, or a series of events.

midpoint potential the **electrode potential**, at a given pH and temperature and 1 atm H_2, at the midpoint of a redox titration when the activities of the reductant and the oxidant are equal.

MIF *abbr. for* **1** (macrophage) migration inhibition factor. **2** melanotropin release-inhibiting factor (i.e. **melanostatin**). **3** Müllerian inhibitory factor.

mifepristone *see* **RU-486**.

migratase *an old name for* **mutase**; e.g. lysolecithin migratase is an old name for lysolecithin acylmutase (EC 5.4.1.1).

migrate *(in chemistry)* (of atoms, ions, or molecules) to move from one region of a solution to another, or from a solution in one compartment to a solution in another compartment, under the influence of an electric or a centrifugal field or by diffusion. —**migration** *n.*

migration inhibition factor *abbr.*: MIF; *see* **(macrophage) migration inhibition factor**.

MIH *abbr. for* melanotropin release-inhibiting hormone (i.e. **melanostatin**).

MIL the avian homologue of ***RAF***; v-*mil* is the oncogene of the avian retrovirus Mill-Hill-2, which also carries v-*myc*. It codes for a serine/threonine kinase of the *RAF*/*MOS* subfamily of unknown function but exhibiting homology with Src and related proteins (*see* ***src***).

milieu (*pl.* **milieus** *or* **milieux**) environment or setting.

milieu intérieur *(French)* the internal environment of a multicellular organism that surrounds the tissues and cells.

milk 1 the white liquid produced and secreted by the mammary glands of mature female mammals for the nourishment of their young. The milk of certain mammals, especially cows, is used as a food by humans, either as liquid milk or in the production of butter, cheese, etc. **2** any of various natural or manufactured liquids that have the appearance or consistency of milk, e.g. coconut milk, milk of magnesia. **3** to squeeze or draw milk from; to yield milk. —**milky** *adj.*

milk factor *an alternative name for* **Bittner factor**.

milk sugar *an old name for* ᴅ-**lactose**.

Miller index *(in crystallography)* any of a set of three integers that determine the position of a face, or internal plane, of a crystal in relation to three crystallographic axes. They are determined on the basis of the reciprocals of the intercepts of the face or plane on the crystallographic axes. [After W. H. Miller (1801–80).]

milli+ 1 *symbol*: m; an SI prefix denoting 10^{-3} times. **2** *prefix* denoting one-thousandth.

millicurie *symbol*: mCi *or (formerly)* mc; a unit of (radio)activity or of radioactive material equal to 10^{-3} **curie** or 3×10^7 becquerel.

milliequivalent *symbol*: mequiv *or* meq *or* mEq; a unit of amount of substance equal to 10^{-3} **equivalent** (def. 3); (mmol recommended).

milligram *symbol*: mg; a unit of mass equal to 10^{-6} **kilogram** or 10^{-3} gram.

millilitre *or (US)* **milliliter** *symbol*: mL *or* ml; a unit of volume equal to 10^{-3} **litre**. It is now identical to the cubic centimetre; i.e. 1 mL = 1 $cm^3 = 10^{-6}$ m^3.

millimetre *or (US)* **millimeter** *symbol*: mm; a unit of length equal to 10^{-3} **metre**.

millimetre of mercury *symbol*: mmHg; a non-SI unit of pressure defined as the pressure exerted by a column exactly 1 mm high of a fluid of density that is exactly 13.5951 g cm^{-3} in a place where the acceleration of free fall is exactly 980.665 cm s^{-2}. Its use is deprecated. 1 mmHg = 1 torr = 133.32 pascal.

millimicro+ *a former name for* **nano+**.

millimicron (*pl.* **millimicrons** *or* **millimicra**) *symbol*: mμ; *a former name for* **nanometre**.

millimolar *symbol*: mᴍ *or* mM; describing a solution containing one millimole per litre of solution, or a specified multiple or fraction thereof; the term is also used of an amount-of-substance concentration similarly expressed.

millimole *symbol*: mmol; a unit of amount of substance equal to 10^{-3} **mole**.

Millipore 1 *the proprietary name for* a range of microporous and other types of membrane filters manufactured by the Millipore Corporation. **2** a water purification system, manufactured by the same company and based on reverse osmosis.

millisecond *symbol*: ms; a unit of time equal to 10^{-3} **second**.

Millon's reaction the formation of red complexes when compounds containing the hydroxybenzene group are heated with **Millon's reagent**. The reaction is given by proteins that contain one or more tyrosine residues. [After Auguste Millon (1812–67), French chemist.]

Millon's reagent a 15% solution of mercuric sulfate in 15% sulfuric acid. This is added to the test sample solution, which is then heated in a boiling water bath for 10 min. After cooling, a 1% aqueous solution of sodium nitrite is added to the cooled reaction mixture. It gives **Millon's reaction** with compounds containing the hydroxybenzene group.

Mills perspective representation *or* **Mills representation** a diagrammatic way of unambiguously representing the structural formulae of carbohydrates and their polycyclic derivatives to show on a plane surface the relative configurational arrangements of substituents and bridges. It is particularly useful in instances where the **Haworth representation** is inconvenient, e.g. for depicting saccharides with substituents that bridge two positions on the ring. The carbohydrate in question, or its derivative, is drawn with single rings and fused rings in the plane of the surface, and with bonds to substituents or bridges above or below the plane of the rings drawn with dark lines (often wedge-shaped) or broken lines, respectively (as is customary in representations of steroids and terpenes). Hydrogen atoms in the angular positions at ring junctions are always shown but those at points of substitution may be omitted. Like **Fischer projections**, but unlike Haworth representations, Mills representations may be rotated in the plane of the paper without alteration of their significance. It was proposed primarily for carbohydrate structures, but resembles systems used for other types of molecule, e.g. steroids.



β-D-glucose

milrinone 1,2-dihydro-6-methyl-2-oxo-5-(4-pyridinyl)nicotinonitrile; a phosphodiesterase inhibitor with vasodilating and cardiostimulant activity.



mimetic imitating closely.

+mimetic *suffix (esp. in pharmacology)* denoting having a similar effect to the substance or action indicated.

min *symbol for* minute.

Min *abbr. for* Minute; a system of bacterial proteins responsible for correct localization of the **Z ring** to the mid-cell region of the plasma membrane inner surface in preparation for cell division. MinC and MinD form a complex on the inner cell-membrane surface and inhibit Z ring assembly. MinE relieves this inhibition in the mid-cell region.

mince 1 to disrupt tissue with a **tissue grinder** to the level at which there is extensive, but incomplete, rupture of cells. **2** the preparation resulting from the action of a coarse tissue grinder.

mineral 1 any naturally occurring inorganic substance of a type often obtained by mining, e.g. coal, stone, petroleum. **2** any of a class of naturally occurring inorganic substances, of definite chemical composition and physical properties and often crystalline in character. **3** of, pertaining to, or being a **mineral** (def. 1, 2).

mineralize *or* **mineralise** (of an organic material) to convert into, or impregnate with, a mineral or minerals. **—mineralization** *or* **mineralisation** *n.*

mineralocorticoid *or* **mineralocorticosteroid** any naturally occurring or synthetic hormonal **corticosteroid** that acts primarily on water and electrolyte balance by promoting the renal retention of sodium ions and excretion of potassium ions. Mineralocorticoids are produced in the outer layer (zona glomerulosa) of the adrenal cortex. **Aldosterone** is the most potent of the naturally occurring mineralocorticoids. *Compare* **glucocorticoid**.

mineralocorticoid receptor a nuclear receptor (984 amino acids) of the steroid hormone type that binds and mediates the biological effects of aldosterone. Loss-of-function mutations result in pseudohypoaldosteronism type 1. Gain-of-function mutations lead to an early-onset type of hypertension that is exacerbated by pregnancy.

mini+ *comb. form* denoting miniature; of smaller than usual dimensions.

miniature inverted-repeat transposable element *abbr.*: MITE; a transposable element containing almost identical sequences of ≈400 bp flanked by characteristic inverted repeats of ≈15 bp. MITEs are too small to encode protein; they are ubiquitous in genome sequences, accounting for 5% or more of some genomes (e.g. rice).

minicell 1 a small cell-like body arising from a polar region of a rod-shaped bacterium by aberrant cell division. It is spherical or near-spherical in shape and devoid of chromosomal DNA; hence it does not grow or divide and is normally unable to synthesize nucleic acid or protein (but may do so if a plasmid is introduced). **2** an experimentally produced eukaryotic cell in which an intact cell nucleus is surrounded by scant cytoplasm and a cell membrane. It is prepared by enucleation of a normal mononucleate cell.

miniexon a small exon, as found in the troponin T gene.

minigastrin a form of the peptide hormone **gastrin** that contains 14 amino-acid residues. It has been isolated from tumour tissue and corresponds to residues 5–17 of human gastrin 1, having the sequence LEEEEEAYGWLDFH-amide.

minima a plural of **minimum**.

minimal of, being, or constituting the minimum; the least possible.

minimal medium a (synthetic) culture medium containing only those compounds essential for the growth of a wild-type organism and that is not able to support growth of an auxotroph.

minimum (*pl.* **minimums** *or* **minima**) **1** the least quantity, degree, or value possible or permissible. **2** *(in mathematics)* a value of a function that is less than that of any neighbouring value. **3** of, or pertaining to, a minimum or minimums.

minimum evolution a principle of phylogenetic reconstruction based on minimization of the sum of the lengths of tree branches. From all possible tree topologies over a defined set of taxa, the minimum evolution topology is the one that requires the shortest overall branch lengths.

minimum inhibitory concentration *abbr.*: MIC; the lowest concentration of a drug, or other substance, that just inhibits the growth of a given test organism (bacterium, etc.) in defined conditions.

minimum lethal dose *abbr.*: MLD; the minimum dose of a toxic substance, or organism, that will kill, within a specified time, all the animals in a test group to which it is administered.

minimum (relative) molecular mass *or (formerly)* **minimum molecular weight** the (relative) molecular mass of a compound as determined by the assay of one of its structural elements, e.g. a metal atom, a ligand, a terminal residue, etc., assuming that there must be at least one such structural element in each molecule of the compound.

minisatellite a repeat DNA segment comprising short head-to-tail tandem repeats giving **variable number tandem repeat**-type polymorphisms, with approximate size between 1 and 30 kb. The name derives from the fact that repeat DNA segments were originally found in **satellite DNA**, but the overall size of the minisatellite segments and the length of individual repeats are smaller, and satellite peaks are not seen on centrifugation.

minivial a very small vial, especially a low-capacity container that can be inserted into a normal-sized sample vial used in liquid scintillation counting, to enable the (radio)activity of small-volume samples to be determined more efficiently.

minor base *see* **minor nucleoside**.

minor groove the smaller and shallower of the two grooves on the surface of a double-helical DNA molecule. *Compare* **major groove**.

minor nucleoside a nucleoside containing any of a group of purine or pyrimidine bases that occur in small amounts in most nucleic acids but in relatively large amounts in **transfer RNA** molecules from all organisms; they are sometimes known as '**odd bases**'. The modifications range from the simple methylation of bases or ribose sugar residues to very complex substitutions, take place after transcription of the transfer RNA genes, and are thought to be related to the stability of the tertiary structure. A typical modified nucleoside is **pseudouridine**. *See also* **wyosine**.

minoxidil 6-(1-piperidinyl)-2,4-pyrimidinediamine-3-oxide; an antihypertensive agent and hair growth promoter. It is activated by sulfate conjugation to the active metabolite minoxidil sulfate.



minoxidil sulfate

minuend *(in mathematics)* the number (or quantity) from which another number (or quantity), the subtrahend, is to be subtracted.

minus end the end of a microtubule or actin filament at which the addition of monomers occurs least readily; the 'slow-growing' end of a microtubule or actin filament. The minus end of an actin filament is also known as the pointed end. *Compare* **plus end**.

minus 10 region and **minus 35 region** regions in the **promoter** defined by the number of nucleotides 5′ from the first nucleotide transcribed, i.e. on the **coding strand**. The first nucleotide (the start site) of a transcribed DNA sequence is denoted as +1, the second +2; the nucleotide preceding the start site is denoted as –1. The most conserved sequence upstream (towards the 5′ terminus) of DNA in *Escherichia coli* is a hexamer centred at the –10 position (*see* **Pribnow box**). It has a consensus sequence of TATAAT in which the leading TA and final T are highly conserved. –35 is the centre point of a consensus sequence involved in RNA polymerase recognition, TTGACA.

minus strand 1 the complementary strand to the parental polynucleotide strand – the **plus strand** (def. 1) – in bacteriophages whose genomes consist of duplex RNA. **2** any polynucleotide strand (RNA or DNA) in a viral genome that is complementary to the virus-specified mRNA – the **plus strand** (def. 2). **3** *(sometimes) an alternative term for* **coding strand** (of genetic duplex DNA).

minute 1 *symbol*: min; a non-SI unit of time equal to 60 seconds. **2** *symbol*: ′ ; a unit of plane angle equal to (π/10 800) radians, or 0.291 milliradians. There are 60 seconds (of arc) in one minute (of arc), and 60 minutes in one degree (of arc). **3** *(in genetics)* an empirical unit of distance between genes in a bacterial chromosome, being a measure of the time taken, in minutes, for the transfer of a particular gene during bacterial conjugation relative to an arbitrarily standardized selected origin.

7-minute phosphate *or* **10-minute phosphate** *see* **labile phosphate**.

MIP *abbr. for* macrophage inflammatory protein.

mi protein a basic helix-loop-helix leucine-zipper protein that, as a homodimer, binds promoter regions of melanocyte-specific genes (e.g. tyrosinase). Mouse and human proteins (both ≈415 amino acids) share 95% sequence homology. At least a dozen mutations cause a type of Waardenburg syndrome that includes white forelock, heterochromia iridis, and congenital hearing loss. The protein is named after the microphthalmia-associated transcription factor of mouse.

miRNA *abbr. for* microRNA; *other name*: tiny RNA; any of various RNA species that are 21–25 nt long and may be single- or double-stranded. They have been found in animals, including *Drosophila* and *Caenorhabditis elegans*, and in plants. The term encompasses small interfering RNA (**siRNA**) and small temporal RNA (**stRNA**), as well as miRNA proper. miRNAs are transcribed as parts of longer RNA molecules and processed in the nucleus by the **dsRNA** ribonuclease **Drosha** to hairpin structures 70–100 nucleotides long. These are transported to the cytoplasm where they are digested to 21–23-mers by the dsRNA ribonuclease **Dicer**. Single-stranded miRNAs bind to complementary sequences in mRNA thereby inhibiting translation. Over 100 miRNA species have been found in *Arabidopsis thaliana*, of which some 16 are similar to species characterized from animals. They exhibit diverse developmental and tissue-specific expression profiles and are involved in a wide range of gene regulatory processes.

mirror (*in informatics*) an exact copy of a server made at a different location, to spread the load of traffic and hence facilitate access to that server. Busy servers may have many mirrors (e.g. ExPASy).

misacylate *or* **mischarge** to acylate (a transfer RNA molecule) with an aminoacyl group other than the specific one. **—misacylation** *n.*

mischarge *an alternative term for* **misacylate**.

miscible (of two or more particular liquids) capable of being mixed together to give a homogeneous liquid. Particular liquids may be completely miscible or miscible only in certain proportions. *See also* **proofreading**. **—miscibility** *n.*

mismatch repair a system for the correction of errors introduced during DNA replication when an incorrect base, which cannot form hydrogen bonds with the corresponding base in the parent strand, is incorporated into the daughter strand. **Excinucleases** recognize a pair of non-hydrogen-bonded bases and cause a segment of polynucleotide chain to be excised from the (less methylated) daughter strand, thereby removing the mismatched base. The resulting gap is then filled by the actions of DNA polymerase I and DNA ligase.

mispairing the occurrence of a base in one polynucleotide strand of duplex DNA that is not complementary to the corresponding base in the other strand.

missense codon a particular codon that has been altered so that it codes for an amino-acid residue different from the one for which it normally codes.

missense mutation any mutation causing a base substitution in a gene that results in the incorporation of an incorrect amino-acid residue at a specific position in the polypeptide gene product. *Compare* **nonsense mutation**, **samesense mutation**.

mistranslation the insertion at a specific position in a polypeptide chain of an amino-acid residue that is not indicated by the corresponding codon in the mRNA molecule.

MIT *abbr. for* (3-)monoiodotyrosine.

Mitchell hypothesis the hypothesis, formulated principally by the British biochemist Peter Dennis Mitchell (1920–92), that mitochondrial systems can be driven by proton and electrical gradients that build up across membranes, a mechanism now referred to as **chemiosmotic coupling**.

MITE *abbr. for* miniature inverted-repeat transposable element.

MITF *abbr. for* microphthalmia transcription factor; a protein (419 amino acids) that shows 91% sequence homology in mouse and human. It is a basic helix-loop-helix leucine zipper transcription factor expressed in the neural crest, eye, and ear during development. Mutations lead to microphthalmia in mouse, and to Waardenburg syndrome type 2 in human.

mitochondria the plural of **mitochondrion**.

mitochondriac a biochemist with a chronic and unusually intense interest in mitochondria.

mitochondrial carrier any of a family of at least 13 metabolite transporters of the inner mitochondrial membrane. They consist of ≈300 amino acids organized into three homologous repeats, each of ≈100 residues and containing two transmembrane segments. They probably function as homodimers and serve as antiporters (e.g. for oxaloacetate/citrate, glutamate/aspartate, malate/2-oxoglutarate, citrulline/ornithine, and ATP/ADP pairs). *See also* **mitochondrial carrier protein**.

mitochondrial carrier protein any of various proteins involved in the translocation of small molecules across the mitochondrial inner membrane. Many are translocases using an **antiport** mechanism, and include carriers for pyruvate (antiport molecule is OH^-), phosphate (malate), citrate (malate), phosphate (OH^-), ADP (ATP), aspartate (glutamate), and malate (2-oxoglutarate); e.g., ADP/ATP translocase 1 of yeast; this is an integral inner membrane protein, with a tripartite structure, each repeated segment comprising ~100 residues and containing two transmembrane domains, one if which is more hydrophobic than the other. *See also* **OGCP**.

mitochondrial disease any disease that results from a mutation in mitochondrial DNA. Such diseases are transmitted maternally, are usually of early onset and rapidly progressive, and may involve organs that are seemingly unrelated embryologically or physiologically. Common clinical features include blindness, deafness, myopathy, cardiomyopathy, encephalopathy, diabetes mellitus, renal dysfunction, or liver disease. Among the best characterized are:

MELAS (mitochondrial encephalomyopathy, lactic acidosis, and strokelike episodes); MERFF (myoclonus epilepsy with ragged-red fibres); **Leber's hereditary optic neuropathy**; **Kearns–Sayre syndrome**; **Leigh syndrome**; aminoglycoside-induced deafness; and diabetes mellitus and deafness. The genetic causes of some of these are heterogeneous.

mitochondrial DNA *abbr*.: mtDNA; DNA that is contained, replicated, and expressed in mitochondria. mtDNA is double-stranded in almost all organisms studied; that from mammals has a contour length of ≈5 µm, about 15 kilobases, while that from protozoa and fungi is about five times larger. Human mtDNA (16 569 bp) codes for two types of rRNA molecules, 22 types of tRNA molecules, and 13 proteins. mtDNA is transmitted maternally, i.e. with the mitochondria of oocytes. The code in mtDNA differs in some respects from that in nuclear DNA (*see* **genetic code**). *See* **mitochondrial disease**.

mitochondrial fission protein any protein involved in fission of mitochondria in eukaryotes. In yeast, three proteins (Fis1, Dnm1, and Mdv1) form the constriction ring around the outer membrane, while one protein (Mgm1) forms a ring on the outer surface of the inner membrane.

mitochondrial fraction *an operational term* for the more rapidly sedimenting components (for example 10 000–15 000 *g* for 30 min) of the **cytoplasmic fraction** of a homogenate of eukaryotic cells or tissue. It generally consists predominantly of mitochondria but may also contain varying numbers of secretion granules, lysosomes, microbodies, or other intracellular organelles.

mitochondrial plasmid DNA a distinct class of genetic elements, found in certain wild-type strains of *Neurospora*, that show virtually no sequence homology with standard mitochondrial DNA (mtDNA) in DNA–DNA hybridization experiments and achieve high copy number without suppressive behaviour towards wild-type mtDNA.

mitochondrial matrix the gel-like material, with considerable fine structure, that lies in the matrix space, or lumen, of a **mitochondrion**. It contains many enzymes, including ones involved in fatty-acid oxidation and enzymes of the tricarboxylic-acid cycle, amino-acid metabolism, urea cycle, and porphyrin synthesis.

mitochondrial processing peptidase EC 3.4.99.41; an enzyme that catalyses the cleavage of the leader peptide from precursor proteins imported into the mitochondrion, typically ones with Arg in position P2 (*see* **peptidase P-sites**). These enzymes resemble in sequence **premurein-leader peptidase**. In *Neurospora crassa* the enzyme consists of a catalytic subunit and an enhancer subunit. Both are transmembrane proteins. The enzyme requires the presence of divalent cations for activity.

mitochondrial RNA *abbr*.: mtRNA; any RNA molecules that are complementary to genes in mitochondrial DNA.

mitochondrial state *see* **respiratory state (of mitochondria)**.

mitochondrial trifunctional protein *see* **acyl-CoA dehydrogenase**.

mitochondrion (*pl.* **mitochondria**) a semiautonomous, self-replicating organelle that occurs in varying numbers, shapes, and sizes in the cytoplasm of virtually all eukaryotic cells. It is the site of tissue respiration (*see* **respiratory chain**, **oxidative phosphorylation**). Conventionally, mitochondria are represented as elongated cylinders with a diameter of 0.5–1.0 µm; however, in living cells they show great mobility and plasticity, in some cells forming long, moving chains while in others being fixed in position near sites of high ATP consumption; e.g. in cardiac muscle they are packed between the myofibrils while in a sperm they are tightly wrapped around the flagellum. Mammalian hepatocytes each contain 1000–2000 mitochondria, roughly 20% of the cell volume. A mitochondrion has two functionally distinct membrane systems, the outer one completely surrounding the whole organelle and the inner one being infolded into **cristae**. These membrane systems define two compartments: the mitochondrial matrix and the intermembrane space. The matrix contains enzymes for the oxidation of pyruvate and fatty acids and for the tricarboxylic-acid cycle; it also contains the mitochondrial DNA and the enzymes and structures necessary for expression of the mitochondrial genes. The inner membrane contains the enzymes of the respiratory chain, ATP synthetase, and specific transport proteins. The intermembrane space contains a number of kinases. The outer membrane, which is permeable to molecules of up to 10 kDa, contains monoamine oxidase, cytochrome b_5, a number of transferases, and a fatty-acid elongation system. The mitochondrion was formerly known as a **chondriosome** and by numerous other names. *See also* **cercidosome**. **—mitochondrial** *adj.*

mitochrome a chromoprotein, or mixture of chromoproteins, released from mitochondria *in vitro* after ageing or other degradative processes. They are hemoproteins of ~105 kDa, with 1 atom of Fe per molecule, and are thought to inhibit *in vitro* oxidative phosphorylation.

mitogen any substance or agent that induces or stimulates **mitosis**. **—mitogenic** *or* **mitogenetic** *adj.*

mitogenic protein *abbr*.: MP; *an alternative name for* **interleukin 1**.

mitogillin EC 3.1.27.–; *other names*: allergen I/A; IgE-binding ribotoxin; a purine-specific ribonuclease that attacks 28S rRNA. The protein is a powerful allergen, an inhibitor of eukaryotic protein synthesis, and has anti-tumour activity. Its action is similar to **restrictocin** and ribonuclease U2.

mitomycin C a 334 Da antibiotic and the principal member of the aziridine antibiotics (mitomycins) produced by *Streptomyces caespitosus*. It is toxic to bacteria and mammalian cells and possesses antineoplastic activity. When administered, mitomycin C undergoes intramolecular rearrangement and reduction within cells to form a bifunctional alkylating agent that irreversibly cross-links the two strands of duplex DNA molecules, thereby inhibiting DNA synthesis.



mitoplast a structure consisting of the inner membrane and the matrix of a **mitochondrion**. It is formed by removing the outer membrane and the intermembrane material by treatment of a mitochondrion with nonionic detergents under defined conditions.

mitoribosome any of the **ribosomes** found in mitochondria. They resemble those of bacteria and are sensitive to chloramphenicol.

mitosis *or* **karyokinesis** the division of a eukaryotic cell nucleus to produce two daughter nuclei that contain identical numbers of chromosomes and that are identical genetically to the parent nucleus except where crossing over or mutation has occurred. It is divided into five main stages: **prophase**, **prometaphase**, **metaphase**, **anaphase**, and **telophase**. Mitosis is normally accompanied by **cytokinesis** leading to division of the cell. *Compare* **meiosis**. **—mitotic** *adj.*

mitotic coefficient *or* **mitotic index** the proportion of cells in a population that are in **mitosis** at a given time.

mitotic recombination *or* **somatic crossing over** crossing over between homologous chromosomes during mitotic division of a diploid somatic cell. The result of such a recombination will be imperceptible if the cell is homozygous at the loci exchanged but may produce a marked effect if the dividing cell is heterozygous at these loci. *See also* **Holliday junction recombination**.

mitotic spindle *see* **spindle**.

mixed acid fermentation a particular mode of bacterial fermentation of glucose that is characteristic of many members of the Enterobacteriaceae, e.g. *Escherichia*, *Salmonella*, and *Shigella*. It yields, as principal products, acetic, formic, lactic, and succinic acids, in varying proportions according to the organism and growth conditions.

mixed anhydride any **acid anhydride** formed between two different acids.

mixed-bed deionizer an apparatus for removing electrolytes from impure water (or an aqueous solution) and containing an intimate mixture of anion- and cation-exchange resins. It is frequently fitted with a device for measuring the electrolytic conductivity of the effluent.

mixed-bed resin *a common but imprecise term for* an intimate mixture of anion- and cation-exchange resins as used in a mixed-bed deionizer.

mixed-function oxidase *or* **mixed-function oxygenase** *an older term for* **monooxygenase**.

mixed indicator **1** a mixture, in definite proportions, of two acid–base indicators, or of an indicator and a dye, chosen so as to produce a sharp colour change over a narrow range of pH values. **2** a mixture, in definite proportions, of two or more acid–base indicators chosen so as to produce a series of colour changes over an extended range of pH values.

mixed inhibition *or* **mixed-type inhibition** inhibition of the activity of an enzyme that yields complex kinetic data that cannot be clearly categorized as either competitive or non-competitive. This can result e.g. when the enzyme–substrate– inhibitor complex undergoes the catalytic process slowly, or where binding of the inhibitor changes both k_{cat} and K_{m}.

mixed inhibitor *or* **mixed-type inhibitor** any inhibitor that produces **mixed inhibition** of the activity of an enzyme.

mixed labelled describing a specifically isotopically labelled compound that has more than one type of modified atom, e.g. $[^{13}\mathrm{C}]\mathrm{H}_3\text{–}\mathrm{CH}_2[^{18}\mathrm{O}]\mathrm{H}$.

mixed-lymphocyte reaction *or* **mixed-leukocyte reaction** the reaction that occurs when leukocytes from two genetically differing individuals are cultured together. Small lymphocytes are transformed into immature blast cells, with synthesis of DNA, to an extent that is related to the degree of disparity between the histocompatibility antigens of the cell donors. This reaction forms the basis of a test for the acceptability of an allograft.

mixed triacylglycerol *or (formerly)* **mixed triglyceride** any **triacylglycerol** that contains three types of acyl residue.

mixed-type inhibition *an alternative term for* **mixed inhibition**.

mixed-type inhibitor *an alternative term for* **mixed inhibitor**.

mixed valency describes coordination compounds and clusters in which a metal is present in more than one level of oxidation. In metal clusters the valence electrons are often completely delocalized, allowing efficient electron-transfer processes.

mixotropic series a series of solvents arranged on the basis of their ability to form hydrogen bonds. It is based on the extent to which two given solvents in this series will mix; near neighbours in the series are **isopartitive**.

mixture *(in chemistry)* homogeneous or heterogeneous material in any physical state that consists of two or more chemical components that have no firm chemical bonding between them and that are physically separable.

MK *abbr. for* menaquinone.

mks system *or* **MKS system** *abbr. for* metre–kilogram–second system (of electrical units).

mL *or* **ml** *symbol for* millilitre.

MLD *abbr. for* minimum lethal dose.

M line *see* **sarcomere**.

***Mlu*I** a type 2 **restriction endonuclease**; recognition sequence: A↑CGCGT.

mM *or* **mM** *symbol for* millimolar.

M macroglobulin a paraprotein of IgM type that is produced by individuals with Waldenström's macroglobulinemia.

MMDB *abbr. for* molecular modelling database; *see* **structure database**.

mmHg *symbol for* the conventional **millimetre of mercury**.

MMLV *abbr.for* Moloney murine leukemia virus; a virus that encodes a reverse transcriptase with high processivity used in the generation of cDNA.

mmol *symbol for* millimole.

MMP *abbr. for* matrix metalloproteinase.

MMPI *abbr. for* matrix metalloproteinase inhibitor.

MMTV *abbr. for* mouse mammary tumour virus.

Mn *symbol for* manganese.

mnemonic enzyme mechanism *or* **mnemonical enzyme mechanism** an enzyme mechanism proposed to explain cooperativity towards substrate shown by monomeric enzymes with only one substrate-binding site. In this mechanism free enzyme is considered to exist in two conformations, I and II, that are only relatively slowly interconvertible and that differ in their substrate-binding affinities; the binding of substrate induces a change of the enzyme to a third conformation, III, which reverts to conformation I when product is released. The behaviour of the system depends on the rate of interconversion of I and II and on the relative rates at which these forms can bind substrate. If the binding by I is more rapid than that by II, the system will show positive cooperativity, i.e. the enzyme has 'remembered' the catalytically more effective conformation; if the converse, the system will show negative cooperativity.

MNSs system one of the blood-group systems of humans, in which the antigens are the **glycophorins** of the erythrocytes. It was the second human-blood-group system to be discovered, the first being the ABH system (*see* **ABH antigens**). The M and N antigenic sites are poorly immunogenic and antibodies to M and N antigens do not normally occur in the blood. The determinants are located at the N terminus of glycophorins A and B (GPA and GPB); polymorphism between M and N antigens on GPA is attributed to amino-acid substitutions at residues 1 (Ser/Leu) and 5 (Gly/Glu), but the N-terminal Ser^1 and Leu^1 are the primary determinants for the M and N antigens respectively. GPB carries 'N' (N-like activity), S/s, and U blood-group antigens; 'N' activity resides at the N terminus of GPB, the sequences of GPA and GPB between residues 1 and 26 being identical; the S/s antigenic determinants arise from Met/Thr polymorphism at residue 29 of GPB; and the U antigen, present in all Caucasians and most Blacks, resides between residues 33 and 39.

Mo *symbol for* molybdenum.

mob the genetic notation for genes involved in the mobilization of a **plasmid** from cell to cell.

mobile element *an alternative term for* **transposon**.

mobile phase the phase that moves in a chromatographic system; it can include the portion of the starting sample present in this phase at any given time.

mobility **1** the property of being mobile. **2** *see* **electrophoretic mobility**.

mobilization *or* **mobilisation** **1** the act or process of mobilizing. **2** the process by which a conjugative plasmid brings about the transfer from one cell to another of DNA to which it is not stably and covalently linked.

mobilize *or* **mobilise** to bring (resources or reserves) into use for a particular purpose, e.g. to mobilize fat by lipolysis or glycogen by glycogenolysis.

mobilizing plasmid *or* **mobilising plasmid** *an alternative name for* **conjugative plasmid**.

Möbius strip *or* **Moebius strip** any one-sided continuous surface with a single bounding curve made by twisting a ribbon through 180° and joining the ends together. When divided lengthwise it forms another Möbius strip of double the length, and is a model for the replicative behaviour of a circular chromosome that contains a single twist. [After its inventor, August Ferdinand Möbius (1790–1868), German mathematician.]

Mo cell a relatively small cell, containing round, osmophilic granules, that is believed to produce **motilin**. Mo cells occur in the upper small intestine of humans, mainly in the crypts; they are sparse in the lower small intestine.

MoCo *abbr. for* **molybdenum cofactor**.

modal class *(in a statistical distribution)* the class that contains the **mode** (def. 2).

mode **1** any particular way or manner of existing or of doing something. **2** *(in a statistical distribution)* the value of the variable occurring with greatest frequency. **3** any of the several wave frequencies that an oscillator can generate, or to which a resonator can be tuned to respond. **—modal** *adj.*; **modality** *n.*

modeccin a 57 kDa lectin present in the turnip-like root of the southern African plant, *Modecca digitata*. It is highly toxic to animals, its prime action being on the liver, and to animal cells in culture. It consists of two polypeptide subunits in disulfide linkage, the A (smaller) subunit being biologically indistinguishable from the A subunits of ricin and abrin. *See also* **ribosome-inactivating protein**.

model **1** a three-dimensional representation of an object, structure, etc., sized to be conveniently seen, handled, and studied. **2** a conceptual representation of a particular phenomenon, system, or set of experimental observations as an aid to understanding and as an object for test or for further experimentation. **3** an animal that, often as a result of mutation, mimics a pathological condition and can be used to study the pathogenesis of the condition. *See also* **transgenic**. **4** a mathematical representation of a particular phenomenon, system, or set of experimental observations as an aid to calculation and prediction. **5** to construct or create a **model** (def. 1, 2, 3). —**modelled** *or (sometimes US)* **modeled** *adj.*; —**modelling** *or (sometimes US)* **modeling** *n.*

model organism an organism used in research to exemplify its type and to represent more complex organisms in which similar phenomena are thought to or do occur. Examples include the bacterium *Escherichia coli*, the yeast *Saccharomyces cerevisiae*, the worm *Caenorhabditis elegans*, the fruit fly *Drosophila melanogaster*, the flowering plant *Arabidopsis thaliana*, and the rodent *Mus musculus*.

model system any biological or biochemical system that is used for study because it is considered to be representative of one or more other (often more complex) systems in which similar phenomena occur or are believed to occur.

moderator *or* **modulator** any substance that changes the rate of an enzymic or other reaction, either positively or negatively.

modification 1 *(in biochemistry) see* **covalent modification**. **2** *(in genetics)* any nonheritable change in the phenotype of an organism in response to variation of its environment; it includes **host-controlled modification**. *Compare* **mutation**.

modification enzyme any enzyme that effects **covalent modification**, and specifically the DNA methylase component of the **restriction-modification system**. Such methylases are conventionally named in the same way as **restriction endonuclease**s with a prefix 'M' and in this dictionary they are listed, where appropriate, under the corresponding nuclease (e.g. M.*Alu*I appears under ***Alu*I**).

modification gene *see* **restriction–modification system**.

modification methylase *a common name for* any of the enzymes that methylate specific sites on a DNA molecule.

modification–restriction system *an alternative name for* **restriction–modification system**.

modified LDL a low-density lipoprotein (LDL) particle that has been modified *in vitro* by acetylation, treatment with malondialdehyde, cigarette smoke, or oxidation by copper. Similar changes *in vivo* have been implicated in atherogenesis. Such particles bind to a modified LDL (or scavenger) receptor on macrophages and are internalized, thereby transforming the macrophages into foam cells.

modifier *an alternative term for* **effector**.

modifier gene *or* **modifying gene** any gene that affects the phenotypic expression of a gene or genes at other loci.

modify 1 to alter the structure, character, activity, etc. of (something). **2** to convert a chemical compound into an analogue, especially by substitution. *See also* **modification**.

modular primer an unligated tandem arrangement of **primers** (usually two or three) used for the **polymerase chain reaction** and related experiments.

modulating codon any codon that controls the frequency with which a **cistron** or cistrons are transcribed.

modulation 1 adjustment or regulation of the degree or activity of something. **2** regulation of the frequency with which a **cistron** or cistrons is transcribed. **3** control of the activity of a regulatory enzyme by an effector. **4** *(in physics)* the process of changing the amplitude, frequency, or phase of a wave by combination with another wave.

modulator 1 something that modulates or brings about modulation. **2** any molecule that acts as an **effector**. **3** *(in pharmacology)* a ligand that increases or decreases the action of an agonist by combining with a distinct (allosteric) site on the receptor macromolecule. **4** *an alternative name for* **moderator**.

modulator protein *an alternative name for* **calmodulin**.

module a standardized or self-contained part or unit of construction, especially one that can be used in alternative combinations with others; e.g. one of a set of such assemblies of electronic components that comprise a larger piece of equipment or one of a number of autonomous protein folding units (or building blocks) that are often used to confer a variety of complex functions on a parent protein, either by multiple combinations of the same unit or by combinations of different units to form mosaics; the spread of protein modules is believed to involve genetic shuffling mechanisms (e.g. a **kringle** or SH3 domain). —**modular** *adj.*

MODY *abbr. for* maturity-onset diabetes of the young.

moesin *abbr. for* membrane-organizing extension spike protein; a protein, isolated from bovine uteri, containing a domain similar to one in **ezrin**, band 4.1 and related proteins. Moesin occurs in many cell types and tissues, and is involved in connections of major cytoskeletal structures to the plasma membrane.

Moffitt–Yang equation *or* **Moffitt equation** a phenomenological equation, related to the **Drude equation**, that describes the anomalous variation of optical rotatory dispersion with wavelength shown by polypeptides containing helical sections. It is used to provide an estimate of the alpha-helical content of polypeptides and proteins. If λ is the wavelength of observation and $[m']_\lambda$ is the reduced **mean residue rotation** at that wavelength,

$$[m']_\lambda = \{a_0\lambda_0^2/(\lambda^2 - \lambda_0^2)\} + \{b_0\lambda_0^4/(\lambda^2 - \lambda_0^2)^2\},$$

where a_0, b_0, and λ_0 are empirical constants; a_0 is a function of contributions to the optical rotation from both the helix and the residue side-chains, as well as from the solvent, and b_0 and λ_0 are related principally to the amount of helical structure in the molecule. A value of λ_0 is chosen to give the best straight line when $[m'](\lambda^2 - \lambda_0^2)$ is plotted against $1/(\lambda^2 - \lambda_0^2)$, a good fit usually being obtained if $\lambda_0 = 212$ nm when $\lambda = 350$–600 nm. The slope of this line, $b_0\lambda_0^4$, gives a value of b_0, whence, by reference to the values found for non-helical and fully helical synthetic polypeptides an estimate may be made of the alpha-helical content of a polypeptide or protein under investigation. [After W. Moffitt and Jen Tsi Yang (1922–).]

Mohr pipette a cylindrical pipette calibrated for delivery from the zero mark to a particular chosen graduation mark. [After Carl Friedrich Mohr (1806–1879), German chemist.]

Mohr's salt ammonium ferrous sulfate; di-ammonium iron(II) sulfate hexahydrate; $(NH_4)_2SO_4{\bullet}FeSO_4{\bullet}6H_2O$.

m.o.i. *abbr. for* multiplicity of infection; the ratio of viral particles to organisms or cells exposed to infection.

moiety either of two, usually distinctive, component parts of a complex molecule; e.g. the steroid and saccharide moieties of a cardiac glycoside.

mol *symbol for* mole.

mol. *abbr. for* **1** molecular. **2** molecule.

µmol *symbol for* micromole.

molal 1 denoting the concentration of a solute (or a solution as a whole) expressed as the amount of substance of the solute divided by the mass of solvent. It is measured in moles per kilogram. **2** denoting an amount-of-substance **concentration** measured in such terms. *Compare* **molar**.

molality *symbol*: *m or b*; a measure of concentration expressed as the number of moles (of a specified solute) per kilogram of solvent. Molality is independent of temperature. *See also* **molal**.

molar 1 denoting an extensive physical quantity that is measured per mole (of a specified substance). It is usually denoted by the subscript m in the symbol; e.g. **molar volume** is the volume of one mole of a substance, and the symbol is V_m. *Compare* **specific**. **2** denoting an intensive physical quantity that is measured per mole (of a specified substance); i.e. divided by concentration. Use of the term molar in this sense is no longer recommended, except in the terms **molar absorption coefficient** and **molar conductivity**. **3** denoting the concentration of a solute (or a solution as a whole), expressed as the amount of substance of the solute divided by the mass of the solution. The recommended units are moles per litre but the convenient symbols M and ᴍ are frequently used. *Compare* **molal**.

molar absorbancy index *a former name for* **molar absorption coefficient**.

molar absorption coefficient either the **molar decadic absorption coefficient** (*symbol*: ε) or the **molar Napierian absorption coefficient** (*symbol*: κ); these are, respectively, the decadic **absorbance** or the Napierian absorbance of a substance, or of a solute in solution, (at a specified wavelength (or frequency) and temperature) divided by the optical path length (in cm) of the medium and by the amount-of-substance concentration of the substance; i.e. the decadic or Napierian absorption coefficients of a medium whose concentration is expressed in moles per litre. *Former names*: molar absorbancy index; molar absorptivity; molar extinction coefficient; molecular extinction coefficient. *See also* **absorption coefficient**.

molar absorptivity *a former name for* **molar absorption coefficient**.

molar activity an **activity** (def. 1) of a substance or material divided by its amount of substance (in moles). *Compare* **specific activity**.

molar catalytic activity the **catalytic activity** of an enzyme, under specified conditions, divided by the amount of substance (in moles), either of enzyme catalytic centres or of multi-centre molecules; in the latter case it is important to specify whether the measurements refer to catalytic centres or to molecules. It may be expressed in katals per mole of enzyme. If the conditions specified are such that the enzyme is saturated with substrate, the expression (which then replaces the obsolete term turnover number) will be numerically equal to the **catalytic constant**, in s^{-1}, for decomposition of the enzyme–substrate complex into enzyme and products, although its interpretation may be complex. *Compare* **molar enzymic activity**, **specific catalytic activity**.

molar concentration *an old but now incorrect term for* **amount-of-substance concentration** measured in moles per litre. *See* **molar** (def. 2).

molar conductivity *symbol*: Λ ;the **electrolytic conductivity** of a (specified) electrolyte divided by its amount-of-substance concentration. The SI derived unit is the S m^2 mol^{-1}.

molar decadic absorption coefficient *symbol*: ε; *see* **molar absorption coefficient**.

molar ellipticity *or (formerly)* **molecular ellipticity** *symbol*: $[\Theta]$; an expression of circular dichroism, $\Delta\varepsilon$, at a specified wavelength, λ. It is given by the relation: $[\Theta]_\lambda = 3299\ \Delta\varepsilon_\lambda$.

molar enzymic activity *(obsolete)* the phenomenological coefficient relating the **enzymic activity** (under specified conditions) to the molar amount of enzyme substance; it is expressed in katals per mole of enzyme. It has now been superseded by **molar catalytic activity**.

molar extinction coefficient *a former name for* **molar absorption coefficient**.

molarity *an older (still widely used) term for* **amount-of-substance concentration** expressed in mol dm^{-3} or mol L^{-1}. *See* **concentration** (def. 1b), **molar** (def. 3).

molar mass the mass of a substance divided by its **amount of substance**; it is commonly expressed in grams (sometimes kilograms) per mole. *Compare* **molecular mass**, **relative molecular mass**.

molar Napierian absorption coeffient *symbol*: κ; *see* **molar absorption coefficient**.

molar optical rotation *symbol*: $[m]$ *or* $[M]$; the observed optical rotation, α_{obs}, of a substance, or of a solute in solution, (at a specified wavelength (or frequency) and temperature) divided by the optical path length (in dm), l, of the medium and by its amount-of-substance concentration (in mol dm^{-3}), c. It is given by:

$$[m] = \alpha_{obs}/cl = [\alpha]_\lambda^\theta M_r/100$$

in deg dm^2 g^{-1}, where $[\alpha]_\lambda^\theta$ is the **specific optical rotation**.

molar optical rotatory power *symbol*: α_m; it is given by the relation $\alpha_m = \alpha/cl$ in rad m^2 mol^{-1}, where α is the observed rotation in radians, c is the amount-of-substance concentration in mol dm^{-3}, and l is the optical path length of the sample in m. *See also* **specific optical rotatory power**.

molar volume *symbol*: V_m; the volume occupied by a substance, under specified conditions of temperature and pressure, divided by its **amount of substance**; it is commonly expressed in litres per mole.

mold *the US spelling of* **mould**.

mole *symbol*: mol; the SI base unit of **amount of substance**, defined as the amount of substance of a system that contains as many elementary entities as there are atoms in 0.012 kilogram of carbon-12; the elementary entities must be specified and may be atoms, molecules, ions, electrons, other particles, or specified groups of such particles. One mole of a compound has a mass equal to its **relative molecular mass** in grams.

molecular **1** of or pertaining to a molecule or molecules. **2** consisting of or existing as molecules; (especially of certain gaseous elements) present or reacting as intact molecules rather than as atoms, ions, etc., e.g. molecular oxygen (i.e. dioxygen). **3** of dimensions comparable to those of molecules. **4** *(in physical chemistry) an obsolete term meaning* divided by molecular weight or expressed per gram-molecule; **molar** now used. **5** considered in terms of or at the level of molecules, or in terms of chemical substances or structures and their interconversions; e.g. molecular biology, molecular medicine.

+molecular *comb. form* indicating the **molecularity** of a chemical reaction (when qualified by a multiplicative prefix), e.g. unimolecular, bimolecular, termolecular.

molecular beacon *or* **molecular platform** a protein that contains a variety of domains for specific proteins and serves as a platform for the assembly of specific proteins that mediate a particular function. *See* **REST**.

molecular biology the science that studies the chemical and physical basis of biological specificity and variation, especially with regard to the structure, replication, and expression of genes, and to the structure, interaction, and physiological function of gene products. **—molecular biologist** *n.*

molecular chaperone *see* **chaperone**.

molecular clock the principle that the relationship between evolutionary distance as determined from macromolecular sequences and time is approximately linear, a concept consistent with the neutral theory of evolution in the presence of more or less constant functional constraints.

molecular cloning *or* **DNA cloning** the isolation in a bacterial cell of a fragment of any heterologous DNA in covalent linkage with a replicon (plasmid, phage, etc.) in order to obtain a homogeneous population (i.e. clone) of DNA molecules from the progeny of such a cell. The DNA to be cloned may be a fragment of genomic DNA obtained by restriction endonuclease digestion, or a complementary DNA (cDNA). The foreign DNA is inserted into the **cloning vector**, which has been cleaved with a restriction enzyme; the gaps between vector and insert DNA are sealed with DNA ligase. In cloning using plasmid vectors, plasmids are then reintroduced into host cells by **transformation**; markers on the cloning vector allow selection of plasmid-containing cells and identification of those cells that contain recombinant plasmids (rather than 'empty' vectors). To identify clones containing particular sequences, DNA from individual colonies may be screened with a labelled DNA probe by **colony hybridization**. In cloning using bacteriophage vectors, the ligated insert and vector are packaged into phage capsids *in vitro,* and then these are used to infect host bacteria.

molecular disease any disease caused by an abnormality in a single protein, usually an enzyme. This may have an abnormal structure that makes it functionally less efficient or harmful to the organism, or it may have a normal structure but be present in reduced amount. Examples are the many inborn errors of metabolism and **sickle-cell anemia**. Overproduction of proteins, e.g. of oncogene products, may also lead to a pathological situation.

molecular distillation distillation at very low pressures (at or below 1.3 N m^{-2}) when the mean free path of the molecules is of the same order as the distance between the surface of the liquid being distilled and the distillate; the molecules can therefore travel rapidly from the liquid to the distillate with relatively few collisions, and with a reduced risk of thermal denaturation or decomposition. The technique is useful in the separation and purification of fat-soluble vitamins and other natural products.

molecular drive *or* **concerted evolution** a theory to explain the observed greater homogeneity of members of a multigene family within a species compared with their homologous counterparts in a sister species. It holds that unequal crossing over and other mechanisms of molecular turnover between homologous chromosomes spread a particular variant of a gene in a multigene family from one chromosome to the next. The variant gene is spread through the population by sexual reproduction until it reaches fixation.

molecular dynamics the study of the relative intramolecular differences in the motions of the components of (macro)molecules.

molecular ellipticity *a former term for* **molar ellipticity**.

molecular endocrinology endocrinology at the molecular level.

molecular entity any chemically or isotopically distinct atom, molecule, ion, ion pair, radical, radical ion, complex, conformer, etc., capable of existence as a separately distinguishable entity.

molecular enzymology *(sometimes)* the aspects of enzymology concerned with kinetics and mechanisms.

molecular evolution the process whereby changes in DNA or RNA accumulate over time via a range of different mechanisms, giving rise to changes in, for example, genes, gene products, gene expression, or the frequency of genes within populations.

molecular exclusion chromatography *a less common name for* **gel-permeation chromatography**.

molecular extinction coefficient *a former name for* **molar absorption coefficient**.

molecular formula a chemical formula giving the kinds and number of atoms in one molecule of a specified substance.

molecular fragmentography *an alternative (less satisfactory) name for* **selected-ion monitoring**.

molecular genetics the branch of genetics that attempts to describe genetic events in molecular terms.

molecular graphics *functioning as sing.* the use of computer programs for visualizing (macro)molecules, refining structures and molecular design, protein engineering, etc. Suites of programs that are commonly used include Insight, Ribbons, Midas, and O.

molecular hybridization *an alternative name for* **hybridization analysis**.

molecular ion any ion produced, especially in a mass spectrometer, when a molecule loses or gains an electron, forming a molecular cation or molecular anion, respectively.

molecularity the number of molecular entities involved in a simple, one-step, chemical reaction (it is not used to describe an overall reaction with more than one step). In the two-step reaction: $A + B \rightarrow C \rightarrow D$, the molecularity of the first step is two, i.e. it is bimolecular, and the molecularity of the second step is one, i.e. it is unimolecular.

molecular mass the mass of one molecule of a specified substance expressed in (unified) atomic mass units or daltons. *Compare* **relative molecular mass**, **molecular weight**.

molecular matchmaker any of a class of proteins, also called matchmaker proteins, that cause a conformational change in one or both components of a DNA–protein binding pair to promote formation of a metastable DNA–protein complex. ATP hydrolysis occurs in the process. Such matchmaking is used extensively in repair, replication, and transcription of DNA.

molecular medicine *(sometimes)* the branch of medicine concerned with the biochemical mechanisms of disease processes and therapy.

molecular mimicry 1 in the context of ligand receptor binding (*see* **ligand (def. 6)**) a molecule, unrelated to the ligand that by accident binds to the receptor. **2** in the etiology of autoimmune diseases, the hypothesis that molecules from a microorganism mimic those in an animal host, leading to activation of self-reactive lymphocytes.

molecular motor a protein or protein complex that generates force upon hydrolysis of ATP. Such motors include **myosins**, **kinesins**, **dyneins**, and **DNA helicases**.

molecular orbital a wave equation for one electron describing its movement in the effective field provided by the nuclei and all other electrons of a molecular entity of more than one atom.

molecular pathology the use of techniques of molecular biology to enhance the understanding, diagnosis, and therapy of disease (mainly with respect to humans).

molecular pharmacology the use of techniques of molecular biology to enhance the understanding of the mechanism of action of existing drugs, and with the help of molecular graphics to predict the structure of novel drugs, especially compounds that might bind to proteins of known structure.

molecular p*K* any one of the **p*K*** values of an acid with two or more dissociations. *Compare* **group p*K***, **titration p*K***.

molecular recognition the specific **recognition** of one molecule by another; it often includes **chiral recognition**.

molecular ruler 1 any rigid oligoproline crosslinking reagent of defined length. Such reagents are useful in probing the structures of biological macromolecules in solution. **2** any molecule that regulates length, e.g. **nebulin**.

molecular sieve any of a class of substances or materials, whether naturally occurring or artificial, that contain pores of molecular dimensions and of a closely defined range of diameters. They are useful for the separation of substances within a particular range of molecular dimensions on the basis of selective exclusion.

molecular-sieve chromatography any form of chromatography in which a separation is based mainly upon differences in molecular size and/or shape of the substances being separated. It includes **gel-permeation chromatography** and separations using **zeolites**.

molecular-sieve electrophoresis *(sometimes) an alternative term for* **polyacrylamide gel electrophoresis**.

molecular switch a protein that can change from an active to an inactive form by altering its conformation as a result of binding to a specific ligand or of chemical modification.

molecular tinkering the evolutionary process of transforming preexisting genes or parts of genes to produce new roles or functions, or of combining molecular systems to give new, often more complex, systems. For example, in mammals, lysozyme, an ancient hydrolytic enzyme that destroys bacterial cell walls, has been recruited as the milk protein α-lactalbumin. Similarly, in birds and reptiles, the ancestral ornithine-urea cycle enzyme argininosuccinate lyase has been recruited as a water-soluble eye-lens structural protein, δ-crystallin.

molecular weight *abbr.*: mol. wt. *or* M.W.; *a former name for* **relative molecular mass**.

molecular weight cut-off *or* **cut-off** *a jargon term for* the nominal maximal value of the relative molecular mass of a macrosolute that can pass through an ultrafiltration membrane of a particular grade.

molecular weight marker *or* **molecular weight standard** a *jargon term for* any soluble polymer of accurately known relative molecular mass that serves as a reference in estimations of M_r values of polymers by techniques such as gel permeation chromatography or gel electrophoresis. Generally a set of such substances, covering a range of M_r values, is used.

molecule a structural unit of matter consisting of one or more atoms; the smallest discrete part of a specified element or compound that retains its chemical identity and exhibits all its chemical properties.

mole fraction *an alternative name for* amount-of-substance fraction. *See* **concentration**.

mole percent the quantity mole fraction multiplied by 10^{-2}; usage no longer recommended.

Molisch test a qualitative test for free or combined aldohexoses. It depends on the formation of a purple colour when the furfural derivatives, formed when aldohexoses are heated with strong acids (e.g. H_2SO_4), react with sulfonated 1-naphthol. [After Hans Molisch (1856–1937), Austrian chemist.]

mollicute *see* **mycoplasma**.

Molscript a computer program, written by Per Kraulis, for displaying molecular 3D structures such as proteins.

molt *the US spelling of* **moult**.

molting hormone *the US spelling of* moulting hormone (i.e. **ecdysterone**).

mol. wt. *abbr. for* molecular weight (alternative to M.W.).

molybdate 1 the bivalent anion, MoO_4^{2-}, derived from molybdic acid. **2** any salt of molybdic acid.

molybdenum *symbol*: Mo; a metallic transition element of group 6 of the (IUPAC) **periodic table**; atomic number 42; relative atomic mass 95.94. It consists of a mixture of eight stable nuclides of which the commonest is that of mass number 98. It forms molybdates (molybdenum(VI)) and can also exist in various lower oxidation states. Molybdenum is of low abundance in the Earth's crust and is an essential trace component of living material, where it participates in numerous redox reactions. It is a constituent of component I (or molybdoferredoxin) of the **nitrogenase** (EC 1.18.6.1) complex from legume nodule bacteria (bacteroids), which converts nitrogen into ammonia. There are many artificial radionuclides of molybdenum, of which the most widely used is molybdenum-99.

molybdenum cofactor a cofactor of **molybdoenzymes** of human cells. It consists of a molybdenum atom complexed by vicinal sulfhydryl groups on a unique pterin species called **molybdopterin**. In some bacteria it is present as a dinucleotide. Synthesis of the cofactor starts with GTP and proceeds by a pathway independent from that for folate or biopterin synthesis. It has been well studied in *E. coli* but homologous genes have been found in the human genome.

molybdenum cofactor deficiency a severe autosomal disease of humans in which activity of the three **molybdoenzymes** is lacking and leads to accumulation and increased excretion of sulfite, thiosulfate, *S*-sulfocysteine, taurine, xanthine, and hypoxanthine. Clinically the presentation is very similar to that of sulfite oxidase deficiency. It is caused by a defect in the synthesis of **molybdenum cofactor**.

molybdo+ *comb. form* denoting containing molybdenum, e.g. molybdoprotein.

molybdoenzyme any enzyme that contains tightly bound **molybdenum cofactor**. Examples from human cells are aldehyde oxidase (EC 1.2.3.1), sulfite oxidase (EC 1.8.2.1), and xanthine dehydrogenase (EC 1.17.1.4). A very rare combined deficiency of these three enzymes presents as xanthinuria.

molybdoferredoxin *an alternative name for* component I of **nitrogenase**.

molybdophosphoric acid *or* **phosphomolybdic acid** a heteropolyacid of approximate formula $24MoO_3{\bullet}P_2O_5{\bullet}xH_2O$, where x is approximately 50. It is useful in reagents for alkaloids, xanthine, uric acid, creatinine, etc.

molybdopterin *or* **pyranopterin** a pterin derivative that binds molybdenum or tungsten in enzymes. *See* **molybdenum cofactor**.

mon+ *a variant form of* **mono+** (sometimes before a vowel).

Mon *symbol for* the montanoyl group.

monactin *see* **nonactin**.

monatomic *or* **monoatomic** (of a molecular entity) composed of only one atom.

monellin an ~11 kDa protein consisting of two polypeptide chains, linked non-covalently, isolated from the fresh fruits of the African shrub, *Dioscoreophyllum cumminsii*, known as serendipity berry. It is intensely sweet-tasting, being 3000 times sweeter than sucrose on a mass basis, and has sequence similarities with **thaumatin**.

monensin a 671 Da, open-chain macrotetrolide-like antibiotic, with many chiral centres, isolated from *Streptomyces cinnamonensis*. It forms stable complexes with monovalent cations, especially with Na^+, and exhibits high Na^+/K^+ selectivity. These complexes are soluble in organic solvents and thus monensin can act as an **ionophore** for monovalent cations. It is used as a digestion-modifying feed additive in ruminants.



Monera the kingdom containing all prokaryotic organisms (i.e. bacteria and cyanobacteria) in the five-kingdom system of classification. —**moneran** *adj., n.*

mongolism *an older name for* **Down's syndrome**.

monitor 1 any instrument or device for checking, controlling, measuring, or keeping a record of some varying biological activity or chemical or physical property, e.g. absorbance, (radio)activity, concentration, pH, respiration. **2** to serve as a monitor of (some activity or property); to use a monitor.

mono+ *or (sometimes before a vowel)* **mon+** *comb. form* **1** denoting one, single, onefold, once, alone; **uni+**. **2** *(in adjectives describing physical attributes)* homogeneous; e.g. monochromatic, monodisperse, monoenergetic. **3** *(in generic names of chemical compounds)* denoting that member of a series (a) having only one specified substituent or other chemical modification, e.g. monoacylglycerol, monoamine; or (b) comprised of only one constitutional unit, e.g. monomer, monosaccharide. **4** *informal term (in specific names of chemical compounds)* indicating or emphasizing the presence in a molecule of a single specified atom, group, or residue; e.g. monoiodotyrosine, adenosine monophosphate, monosodium dihydrogen phosphate. **5** *(in adjectives describing compounds or substances)* having a single function of the kind specified; e.g. monoacidic, monobasic, monodentate, monohydric. **6** *(in names of processes or enzymes)* concerned with or acting on, one or only one chemical group of the kind specified; e.g. monoiodination, monoesterase.

monoacidic (of a **base** (def. 1)) able to accept only one proton per molecule in solution.

monoacylglycerol *or (formerly)* **monoglyceride** any ester of glycerol in which any one of its hydroxyl groups has been acylated with a fatty acid, the others being non-esterified.

monoacylglycerol pathway a pathway in which diacylglycerols and triacylglycerols are formed by sequential acylation of monoacylglycerol by acyl-CoA. It is important during fat absorption since monoacylglycerol is extensively absorbed from the gut; however, it is also present in a large number of other mammalian tissues. There is little evidence for this pathway in plants.

monoamine oxidase *abbr*.: MAO; *a common name for* amine oxidase (flavin-containing), EC 1.4.3.4; an enzyme, widely distributed in animal tissues, that catalyses the oxidative deamination of primary amines by a reaction between dioxygen and $R{-}CH_2{-}NH_2$ to form R–CHO, NH_3, and H_2O_2. It also acts on secondary and tertiary amines. It is important in the catabolism of neuroactive amines, e.g. epinephrine, norepinephrine, serotonin (5-hydroxytryptamine), and tyramine. Mammals have two genes for MAO, both on the X chromosome and near the Norrie disease gene. MAO-A (human, 520 amino acids) contains FAD and is a transmembrane protein of the outer mitochondrial membrane in most tissues. It shares 70% sequence identity with MAO-B (527 amino acids). Deficiency of either or both can be associated with deletion of the Norrie disease gene. *See* **Norrin**.

monoamine oxidase inhibitor any compound that inhibits **monoamine oxidase** (*abbr*.: MAO) and is useful as a thymoleptic (antidepressant) drug. MAO inhibitors act by increasing the concentrations of **norepinephrine** and **serotonin**, which, because of the block on their metabolism, accumulate in the synaptic gap and exert an increased postsynaptic effect. They were discovered as a result of the euphoric side effect of the antitubercular drug **isoniazid**. There are two main groups: (1) the **cyclopropylamines**, including tranylcypromine (*trans*-phenyl-cyclopropylamine); and (2) the **propargylamines**, including pargyline (*N*-benzyl-*N*-methyl-2-propynylamine. **Harmine** and related carboline alkaloids are reversible MAO inhibitors but are not used therapeutically.

monoatomic *a variant spelling of* **monatomic**.

monobactam any of a family of *N*-sulfonated monocyclic *β*-lactam antibiotics produced by a range of bacterial species.

monobasic 1 (of an acid) able to yield only one hydrogen ion per molecule in solution. **2** (of a salt or ester of a polybasic acid) derived by the replacement of only one of its dissociable hydrogen atoms per molecule.

monochromatic 1 *or* **homochromatic** involving, possessing, or relating to a single colour; consisting of, relating to, or emitting light (or other electromagnetic radiation) of a single frequency or wavelength. **2** *an alternative term for* **monoenergetic**. *Compare* **heterochromatic** (def. 1), **polychromatic**.

monochromator a device used for producing light (or other electromagnetic radiation) of essentially one frequency or wavelength, which may be fixed or selectable.

monocistronic containing as much genetic information as is contained in a single **cistron**.

monocistronic messenger RNA any messenger RNA molecule that carries one initiation site and encodes the synthesis of one polypeptide chain. It is characteristic of eukaryotes, which do not possess **polycistronic messenger RNA**.

monoclonal 1 of, pertaining to, being, formed by, or derived from a single **clone** (def. 1). **2** *(sometimes) an informal name for* **monoclonal antibody**.

monoclonal antibody *or (informal)* **monoclonal** an immunoglobulin secreted by a single clone of antibody-producing cells, either *in vivo* or in culture. Such antibodies are **monospecific;** they can thus be useful as immunochemical reagents for the detection or assay of particular antigens, or used in therapy. *See also* **humanize**, **hybridoma**.

monocomponent insulin a commercial preparation of natural insulin that has been highly purified by chromatography and is thus made essentially free of proinsulin, intermediates in the conversion of proinsulin to insulin, and breakdown products of insulin, as well as any unrelated contaminants.

monocotyledon *or* **monocot** any flowering plant having a single cotyledon (seed leaf) in the embryo. Such plants comprise the class Monocotyledonae.

monocyclic having a single ring of atoms in the molecule.

monocyte a large leukocyte of the **mononuclear phagocyte system**, 16–22 μm in diameter (in humans), with pale-staining cytoplasm and a reniform or horseshoe-shaped nucleus. Found in bone marrow and the bloodstream, monocytes are derived from pluripotent stem cells and become macrophages when they enter the tissues.

monodisperse describing a colloidal system in which the dispersed phase consists of particles all of (nearly) the same size. **—monodispersity** *n.*

Monod–Wyman–Changeux model (for allosteric interactions) *abbr*.: MWC model; a model describing the nature of **allosteric** interactions in proteins. It requires an allosteric protein to be an oligomer, the protomers of which are associated in such a way that they all occupy equivalent positions. Each protomer has only one stereospecific binding site for each ligand. The protein can exist in either of two conformational states, the T form (**tense form**), the predominant form when unligated, and the R form (**relaxed form**); these states are in equilibrium. The affinity of the R form for ligand is higher than that of the T form. All binding sites in each state are deemed to be equivalent and to have identical dissociation constants, K_R and K_T for the R and T forms, respectively. The sigmoidal binding curve for any allosteric protein and a given ligand can be calculated from the allosteric constant, *L*, equal to the ratio [T form]/[R form] for the unligated states and the two dissociation constants. [After Jacques Lucien Monod (1910–76), French microbiologist and molecular biologist, Jeffries Wyman (1901–95), US biochemist, and Jean-Pierre Changeux (1936–), French biochemist.] *See also* **mnemonic enzyme mechanism**.

monoenergetic *or* **monochromatic** (of moving particles and sometimes also photons) all having the same kinetic energy.

monoenoic denoting any alkenyl carboxylic acid containing one carbon–carbon double bond per molecule.

monoester any simple ester; i.e. any **ester** formed by condensation of one molecular proportion of an alcohol or phenol with one of an oxoacid.

monoesterase *see* **phosphomonoesterase**.

monofunctional having only one function or one reactive chemical group.

monoglyceride *a former name for* **monoacylglycerol**; its use is discouraged as it does not convey the intended meaning.

monognotobiotic *an alternative term for* **axenic**.

monohydric *or* **monohydroxy** describing any chemical compound containing one hydroxyl group per molecule. It is used especially of alcohols.

monoiodinated reacted with or containing only one atom of iodine per molecule.

monokine *an alternative name for* a **cytokine** produced by monocytes.

monolayer 1 *an alternative name for* **monomolecular layer**. **2** a single layer of cells grown or growing in culture.

monomer 1 any substance that can provide one or more (in number or species) of the monomeric units of an **oligomer** (def. 1) or of a **polymer** (def. 1); a molecule of such a substance. **2** *a loose term for* any of the component molecules (identical or non-identical) formed by the complete dissociation of a macromolecule with quaternary structure. **3** *(in molecular biology)* **a** any protein that is made up of non-identical structural units. **b** any of the structural units formed by dissociation of an oligomeric protein, and corresponding to a **protomer** in the undissociated protein. **—monomeric** *adj.*

monomeric unit a group of atoms, derived from a molecule of a given **monomer** (def. 1), that comprises any one species of constitutional unit of a polymer.

monomolecular 1 relating to, consisting of, or involving a singular **molecular entity**. **2** (of a reaction) having a **molecularity** of one; unimolecular.

monomolecular layer *or* **monolayer** a layer of a substance or substances that is one molecule thick.

mononuclear 1 (of a cell) having one nucleus. **2** (of a metal-ion–ligand complex) containing a single central metal atom.

mononuclear phagocyte system a cell system in higher animals that comprises all the highly phagocytic mononuclear cells and their precursors. It includes the free macrophages, precursor cells and promonocytes of the bone marrow, monocytes of the bone marrow and the blood, and the tissue macrophages. The term is a replacement for **reticuloendothelial system**, now held to lack precision.

mononucleosis *see* **Epstein–Barr virus**.

mononucleotide any **nucleotide** (def. 1); the term is used especially as the generic name of the constitutional repeating unit of all oligonucleotides, polynucleotides, and nucleic acids. A mononucleotide consists of the (3′- or 5′-)phosphate of a single ribonucleoside or deoxyribonucleoside. The term is extended generally to include: (1) nucleoside oligophosphates, e.g. adenosine 5′-triphosphate (ATP); (2) nucleoside diphosphate sugars, e.g. uridine 5′-diphosphate glucose (UDPG); (3) nucleoside 2′,3′- and 3′,5′-(cyclic)phosphates, e.g. adenosine 3′,5′-phosphate (cyclic AMP); (4) nucleoside phosphates derived from artificial heterocyclic bases, e.g. 5-iodo-2′-deoxycytidine 5′-triphosphate, or from ones that do not occur naturally in nucleic acids, e.g. inosine 5′-phosphate (i.e. inosinic acid; hypoxanthine riboside 5′-phosphate; IMP); and (5) certain analogous compounds such as those containing, in place of a residue of ribose or deoxyribose, a residue of ribitol, e.g. flavin mononucleotide (i.e. riboflavin 5′-phosphate; FMN), of dideoxyribose, e.g. 2′,3′-dideoxyadenosine 5′-triphosphate (i.e. ddATP), or of another pentose, e.g. cytosine arabinoside 5′-triphosphate (i.e. *ara*-CTP). *Compare* **oligonucleotide**, **polynucleotide**.

monooxygenase any oxidoreductase enzyme that brings about the incorporation of one atom of oxygen from dioxygen into the donor, and catalyses reactions of the type:

$$\text{substrate} + O_2 =$$
$$\text{oxidized substrate} + H_2O\ (+\ CO_2 \text{ in many cases}).$$

The following are examples. (1) Lysine 2-monooxygenase; EC 1.13.12.2; it catalyses the oxidation by dioxygen of L-lysine to 5-aminopentanamide, CO_2, and H_2O; FAD is a coenzyme. (2) Lysine 6-monooxygenase; EC 1.13.12.10; it catalyses the oxidation by dioxygen of L-lysine to N^6-hydroxy-L-lysine and H_2O. (3) Tryptophan 2-monooxygenase; EC 1.13.12.3; it catalyses the oxidation by dioxygen of L-tryptophan to indole-3-acetamide, CO_2, and H_2O. (4) *myo*-Inositol oxygenase; EC 1.13.99.1; it catalyses the oxidation by dioxygen of *myo*-inositol to D-glucuronate and H_2O; iron is a cofactor. (5) Phenol 2-monooxygenase; EC 1.14.13.7; *other name*: phenol hydroxylase; it catalyses a reaction between phenol, NADPH, and O_2 to form catechol, $NADP^+$, and H_2O; FAD is a coenzyme. It is an enzyme of bacterial aromatic substrate utilization. (6) *trans*-Cinnamate 4-monooxygenase; EC 1.14.13.11; *other names*: cinnamic acid 4-hydroxylase; cinnamate 4-hydroxylase; CA4H; it catalyses a reaction between *trans*-cinnamate, NADPH, and O_2 to form 4-hydroxycinnamate, $NADP^+$, and H_2O. It is a cytochrome P450–thiolate enzyme. *See also* **monophenol monooxygenase**.

monophenol monooxygenase EC 1.14.18.1; *other names*: tyrosinase; phenolase; monophenol oxidase; cresolase. An enzyme involved in the formation of melanins and other polyphenolic pigments, etc. It catalyses a reaction between L-tyrosine, L-dopa, and O_2 to form L-dopa, dopaquinone, and H_2O; copper is a cofactor. It has four motifs, three for the Cu site.

monophosphatidyl glycerol any [1,2-diacyl-*sn*-glycero-3-(phospho-1-*sn*-glycerol)] lipid present in chloroplasts of higher plants.

monophyletic group a group of species (or nodes in a phylogenetic tree) that share a common ancestor that is exclusive to those species (or nodes). For example, a clade is a monophyletic group.

monoploid (of cells or individuals) having a single set of chromosomes; i.e. in a polyploid series, having the fundamental **haploid** chromosome number; true haploid.

monosaccharide *the generic name of* the simplest carbohydrates. Monosaccharides cannot be hydrolysed to give smaller carbohydrates. They are polyhydric alcohols containing either (in **aldoses**) an aldehyde group or (in **ketoses**) a keto group and with from three to ten or more carbon atoms. Monosaccharides form the constitutional repeating units of oligo- and polysaccharides. The names and structures of the common aldoses (from triose to hexose) form the basis for prefixes used to describe other compounds containing a set of >CHOH groups. For structures, see illustration (note that if X = CHO and Y = CH_2OH these structures also depict the common D aldoses). An example of prefix use is the ketoheptonic acid phosphate, DAHP, **3-deoxy-D-*arabino*-(2)-heptulosonate 7-phosphate**. By extension the stereochemical relationships are applied to substituents other than OH, e.g. in **threonine**. *See also* **glycose** (def. 1), **heptose**, **hexose**, **pentose**, **tetrose**, **triose**.

monose *an obsolete term for* **monosaccharide**.

monosodium glutamate *abbr*.: MSG; the monosodium salt of L-glutamic acid, widely used as a flavouring agent for its meaty taste, and the most active component of soy sauce. Consumption by adults of more than about 3.0 g can cause **Chinese restaurant syndrome**, characterized by a feeling of tightness, facial pressure, burning sensation, and headache. The D-enantiomer does not have the characteristic taste and up to 7.0 g can be consumed without ill effect.

monosome 1 any chromosome in a functionally diploid chromosome set that lacks a homologue. **2** a structure consisting of a single ribosome bound to a molecule of messenger RNA.

monosomic (of cells, tissues, or individuals) having one or more **monosomes** (def. 1).

monospecific (of an antibody or an antiserum) only able to react with a single specified antigen or antigenic determinant.

monoterpene any **terpene** containing or derived from two isoprene units and thus containing ten carbon atoms. Monoterpenes may be acyclic or mono- or dicyclic.

monotonic (of a mathematical function) varying in such a manner that it continuously either increases or decreases as the independent variable increases. —**monotonically** *adv.*

monotopic an integral membrane protein that crosses the membrane once. *Compare* **polytopic**.

monovalent *an alternative term for* **univalent**.

monoxenic *see* **synxenic**.

monozygotic 1 (of twins, triplets, etc.) derived from a single fertilized ovum. **2** any one of a set of monozygotic individuals. *Compare* **dizygotic**.

montanate 1 *the trivial name for* octacosanoate, $CH_3–[CH_2]_{26}–COO^–$, the anion derived from montanic acid (i.e. octacosanoic acid), a saturated straight-chain higher fatty acid. **2** any mixture of free montanic acid and its anion. **3** any salt or ester of montanic acid. Montanate esters of long-chain alcohols occur in montan wax, beeswax, and some other natural waxes.

montanoyl *symbol*: Mon; *the trivial name for* octacosanoyl,


D-*glycero*


D-*erythro*


D-*threo*


D-*arabino*


D-*lyxo*


D-*ribo*


D-*xylo*


D-*allo*


D-*altro*


D-*galacto*


D-*gluco*


D-*gulo*


D-*ido*


D-*manno*


D-*talo*

CH_3–$[CH_2]_{26}$–CO–, the acyl group derived from montanic acid (i.e. octacosanoic acid).

Monte Carlo method a way of solving a mathematical problem by sampling methods. The procedure involves the construction of a stochastic model of the mathematical process and the performance of sampling experiments upon it. Such methods have application in molecular graphics aimed at extracting the fundamental principles of macromolecular conformation. [After the resort in Monaco famous for its casino.]

Mops *or* **MOPS** *abbr. for* 3-(*N*-morpholino)propanesulfonic acid; a **Good buffer substance**, pK_a (20°C) = 7.2.



morgan a unit of genetic length along a chromosome, defined as the distance between two loci that show, on average, one crossover per meiotic event; it is equal to 100 **map units** (or Morgan's units). [After Thomas Hunt Morgan (1866–1945), US geneticist and zoologist.]

Morgan's unit *an alternative name for* map unit. *Compare* **morgan**.

Mörner's test a qualitative test for tyrosine in which a green coloration is produced when a tyrosine-containing sample is boiled in a solution of formaldehyde in strong sulfuric acid. [After K.A.H. Mörner (1855–1917), Swedish chemist.]

morph+ *a variant form of* **morpho+** (before a vowel).

+morph *comb. form* indicating of a specified form, shape, or structure. —**+morphic** *or* **+morphous** *adj.*; **+morphy** *n.*

morphiceptin a tetrapeptide amide fragment of the milk protein β-casein, structure Tyr-Pro-Phe-Pro–NH_2, and the N-terminal tetrapeptide of casomorphin. It is a potent and specific agonist for μ-opiate receptors, its effects on the receptor being blocked by naloxone.

morphine 7,8-didehydro-4,5-epoxy-17-methylmorphinan-3,6-diol; an opiate and the most important opium alkaloid; it is a powerful, habit-forming narcotic analgesic. In the opium poppy, *Papaver somniferum*, it is derived from two molecules of tyrosine via (*S*)-reticuline as intermediate. Many enzymes, equivalent to those involved in its biosynthesis, have been found in mammalian liver. The diacetate ester, diacetylmorphine, is known as **diamorphine** or **heroin**. This is strongly habit forming and its manufacture, importation, and use are controlled in a number of countries. *See* **opioid receptor**.



morpho+ *or (before a vowel)* **morph+** *comb. form* indicating form or structure.

morphogen a diffusible substance responsible for some aspect of generation of form or structure during development of an organism. Its effects are concentration-dependent. A good example is retinoic acid.

morphogenesis the ensemble of the processes of development of a part, organ, or organism. —**morphogenetic** *or* **morphogenic** *adj.*

morpholine tetrahydro-1,4-oxazine; a heterocyclic compound with a six-membered oxygen- and nitrogen-containing ring. A number of *N*-substituted morpholines are useful as biological buffers, e.g. **Mes**, **Mops**.



morpholine

morpholino antisense oligonucleotide a nonionic DNA analogue with an altered backbone that is resistant to nucleases. Such nucleotides can base pair with mRNA and can block gene expression and produce phenotypic effects in early development when injected into zebrafish, sea urchin, or *Xenopus* embryos.

morphology the branch of biology concerned with the outer form and inner structure of living organisms.

Morquio syndrome *another name for* mucopolysaccharidosis IV. *See* **mucopolysaccharidosis**.

MORT1 *see* **FADD**.

mortalin *other name*: 75 kDa glucose-regulated protein (*abbr.*: GRP 75); a protein that resembles **heat-shock proteins** in sequence, and may be a **chaperone**. It is a member of the heat-shock protein 70 family, which functions as a mortality marker in fibroblasts. Mortal fibroblasts contain a protein, MOT-1, uniformly distributed in the cytosol, while, in immortal fibroblasts, another form of the protein, MOT-2, is concentrated in perinuclear or juxtanuclear regions. In MOT-2, there are differences at residues 618 (Val to Met) and 624 (Arg to Gly). The cytosolic form induces cellular senescence; the perinuclear form does not.

MOS a gene family encoding serine/threonine kinases, e.g. the human and mouse protein pp39^{mos}; v-*mos* is the oncogene of the acutely transforming murine Moloney sarcoma virus (hence 'mos' from mo + s). *MOS* mRNA is detectable only in germ cells in testes and ovaries, and is implicated in meiosis; directly or indirectly it stabilizes **M-phase promoting factor** and activates **MAP kinase**. The protein has homology with Src (*see* **src**).

mosaic **1** a design or pattern on a surface, made up of numerous separate pieces of more or less the same area but differing in some characteristic, e.g. colour, shape, texture. **2** *an alternative name for* **chimera** (used especially of animals). **3** a protein comprising a number of different **modules**. —**mosaicism** *n.*

mosaic evolution within a population of organisms, the phenomenon of varying rates of evolution in different functional systems. For example, in hominid evolution, the dental, locomotor, and neurological systems have evolved at markedly different rates.

mosaic model *see* **fluid-mosaic model**.

Mössbauer spectroscopy a spectroscopic technique specific to particular atomic nuclei. The basis of the Mössbauer effect is the recoilless resonance absorption of γ-rays. For biochemical studies the relevant isotope for study is the stable isotope ^{57}Fe. Gamma rays are produced by a radioactive source of ^{57}Co, and the energy of the γ-rays emitted by the radioactive source is shifted by the Doppler shift obtained by moving the source with respect to the absorber. A more recent variation of the method uses synchrotron radiation. Parameters derived from the Mössbauer spectrum, which provide information on the chemical state of the iron are the isomer shift, the nuclear quadrupole shift and the nuclear hyperfine splitting due to interaction with unpaired electrons. [After Rudolf Mössbauer (1929–), co-winner of the Nobel Prize for Physics 1961 for his researches concerning the resonance absorption of gamma radiation.]

most parsimonious reconstruction (*in phylogeny*) for a given character in a data set, the branching order that requires the fewest mutational events to explain the contemporary sequences. *Compare* **most parsimonious tree**.

most parsimonious tree (*in phylogeny*) for all sequences in a data set, the branching order that requires the fewest evolutionary events to explain the contemporary sequences. *Compare* **most parsimonious reconstruction**.

MOT-1, MOT-2 *see* **mortalin**.

mother liquor the liquid remaining after a substance has been crystallized or precipitated from a solution.

motif 1 (*in relation to protein structure*) a locally ordered region within the core of a protein molecule, formed by 3-D interaction between two or three segments of the secondary structure (α-helix and/or β-strand) that are near one another along the polypeptide chain. The most important types are: (αα), (αβ), (βββ), and (βαβ). *See also* **domain**. **2** (*in relation to protein sequences or sequence alignments*) a contiguous, conserved region, typically 10-20 amino acids in length, usually denoting a key structural or functional unit within a protein, or group of proteins, and often used to diagnose related sequences using pattern-recognition methods (such as fingerprinting). *Alternative name* **block**.

motile (of organisms or cells) capable of independent locomotion; (of cilia, flagella, etc.) capable of spontaneous movement. —**motility** *n.*

motilin a 22-residue peptide produced by **Mo cells** of the mucosa of the upper small intestine, and having putative hormonal activity. Its plasma level rises when food or alkali are placed in the duodenum; it stimulates contractions of the stomach and secretion of pepsin, but its effects show marked species variation.

motor *(in biology)* pertaining to movement of an organ or part; pertaining to nerves or neurons involved in muscular activity.

motor protein a protein, e.g. **dynein**, **kinesin**, **myosin**, that propels itself along a filament or polymeric molecule. Nucleoside triphosphate hydrolysis is usually necessarily involved. A similar process is thought to be involved in the action of elongation factor G (*see* **EF-G**). These processes are referred to as **chemical–mechanical coupling** (or mechanochemical coupling).

Motrin *a proprietary name for* **ibuprofen**.

mould *or (US)* **mold 1** any **microfungus** having a distinctive mycelium; *the common name for* any superficial growth of fungal mycelium. **2** a matrix for shaping a cast.

moult *or (US)* **molt 1** to cast off periodically an outer covering of cuticle, feathers, hair, horns, skin, etc. **2** the act, process, or condition of moulting; in invertebrates it is known as ecdysis.

moulting hormone *or (US)* **molting hormone** *a common name for* **ecdysterone**.

mouse-convulsion method a sensitive method for the detection and biological assay of insulin, used primarily to control the strength of pharmaceutical preparations of insulin. It is based on the finding that small doses of insulin injected into mice (0.1–1.0 µg per animal) cause convulsions. When the method is used for assay, large equal numbers of animals are injected with either of two dilutions of the test solution or of a standard and the results are analysed statistically.

mouse mammary tumour virus *abbr.*: MMTV; a DNA virus that causes breast cancer in mice. It contains a powerful enhancer DNA sequence in the terminal repeats of the genome. This activates an oncogene called *wnt-1* (formerly called *int-1*), which is closely homologous to the *Drosophila* gene ***wingless***. MMTV is often used as an **expression vector** especially in transgenic mice.

moving-boundary electrophoresis an analytical method of electrophoresis carried out using a **Tiselius apparatus**, formerly used for measuring electrophoretic mobility directly.

MOX *abbr. for* methanol oxidase (*see* **alcohol oxidase**).

m.p. *abbr. for* melting point.

MP *abbr. for* mitogenic protein (i.e. **interleukin 1**).

6-MP *abbr. for* 6-mercaptopurine.

MPF *abbr. for* M-phase-promoting factor.

M phase the period of mitosis and cytokinesis in the eukaryotic **cell-division cycle**. During this phase the nucleus and cytoplasm divide.

M-phase-promoting factor *or* **maturation-promoting factor** *or* **p34**^{cdc} *abbr.*: MPF; a protein complex, containing **cyclin** and a protein kinase, that triggers a cell to enter M phase of the **cell-division cycle**.

MPP *abbr. for* mitochondrial processing peptidase.

M6P receptor *abbr. for* **mannose 6-phosphate receptor**.

M protein 1 a structural protein that occurs in the M lines of myofibrils of striated muscle. **2** *an alternative name for* galactoside permease of *Escherichia coli*. **3** a cell-surface protein of Gram-positive cocci, associated with virulence; it renders the organism resistant to phagocytosis. It is a cell-wall component, consisting of a coiled coil with a membrane anchor.

MPTP *abbr. for* 1-methyl-4-phenyl-1,2,3,6-tetrahydropyridine; a toxic by-product of the synthesis of heroin; it produces severe and permanent parkinsonism in primates, resulting from its oxidation by monoamine oxidase to the quaternary 1-methyl-4-phenyl-pyridinium (MPP$^+$) ion. The latter is a potent inhibitor of complex I of the mitochondrial electron-transport chain and a selective neurotoxin for dopaminergic neurons, by which it is taken up in the substantia nigra via the normal neuronal dopamine re-uptake system.



MRC *abbr. for* Medical Research Council (of the UK).

MRCK *abbr. for* myotonic dystrophy kinase-related Cdc42-binding kinase; a protein-serine/threonine kinase that has sequence homology to **myotonic dystrophy protein kinase** and is activated by **Cdc42**.

MRE *abbr. for* metal response element; *see also* **response element**.

MREBP *abbr. for* metal response element binding protein.

MRF *abbr. for* melanotropin-releasing factor (*see* **MSHRH**).

MRF4 *abbr. for* muscle specific regulatory factor 4; *other name*: myogenic factor 6; a DNA-binding, probably **helix-turn-helix**, protein of the ***MYC*** family. It induces fibroblasts to differentiate into myoblasts.

MRH *abbr. for* melanotropin-releasing hormone (*see* **MSHRH**).

MRI *abbr. for* magnetic resonance imaging.

MRIF *abbr. for* melanotropin release-inhibiting factor (i.e. **melanostatin**).

MRIH *abbr. for* melanotropin-release inhibiting hormone (i.e. **melanostatin**).

mRNA *abbr. for* messenger RNA.

mRNA binding site (ribosome) a ribosomal binding region for mRNA. In bacteria this involves **ribosomal proteins** S1, S3, S4, S5, S12, S18, S21, and the 3′ end of 16S rRNA.

mRNA splicing the process in which excision of **introns** from the primary transcript of **messenger RNA** (mRNA) is followed by ligation of the two **exon** termini exposed by removal of each intron, so that mRNA consisting only of the joined exons is produced. *See* **splicing** (def. 2).

mRNA surveillance the process occurring in the cytosol of eukaryotic cells whereby mRNA that contains a premature stop codon is detected and submitted to selective degradation by nonsense-mediated mRNA decay. It involves assembly of a surveillance complex on the mRNA about 24 nt upstream of exon–exon junctions. If translation terminates because of an upstream stop codon, translation release factors bind to the surveillance complex and trigger mRNA degradation.

mRNP *abbr. for* messenger ribonucleoprotein.

MRSA *abbr. for* **methicillin**-resistant *Staphylococcus aureus*, an organism resistant to antibiotics owing to the inability of penicillins to enter the cell (and not directly to ***β*-lactamase**). *Compare* **VRE**.

ms- *abbr. for meso-*.

MS *abbr. for* **1** mass spectrometer or mass spectrometry. **2** magic spot (compound). **3** multiple sclerosis.

MSA *abbr. for* multiplication-stimulating activity.

MSD *abbr. for* macromolecular structure database; *see* **structure database**.

msDNA *abbr. for* multicopy single-strand DNA.

MSEL-neurophysin *see* **neurophysin II**.

MSG *abbr. for* monosodium glutamate.

MSH *abbr. for* melanocyte-stimulating hormone.

MSHIF *abbr. for* melanocyte-stimulating-hormone release-inhibiting factor (i.e. **melanostatin**).

MSHIH *abbr. for* melanocyte-stimulating-hormone release-inhibiting hormone (i.e. **melanostatin**).

MSHRF *abbr. for* melanocyte-stimulating-hormone releasing factor (i.e. **MSHRH**).

MSHRH *abbr. for* melanocyte-stimulating-hormone releasing hormone; a pentapeptide, possibly identical to the N-terminal moiety of **oxytocin**, that is produced in the hypothalamus. In animals that show an unambiguous response of their melanophores to **melanotropin** this regulating factor is believed to promote melanotropin release. *Recommended name*: melanoliberin; *other names*: melanotropin-releasing factor (*abbr.*: MRF); melanotropin-releasing hormone (*abbr.*: MRH); melanocyte-stimulating-hormone releasing factor (*abbr.*: MSHRF).

MSHRIF *abbr. for* melanocyte-stimulating-hormone release-inhibiting factor (i.e. **melanostatin**).

MSHRIH *abbr. for* melanocyte-stimulating-hormone release-inhibiting hormone (i.e. **melanostatin**).

MS/MS *abbr. for* tandem mass spectrometry.

MSOC *abbr. for* the *N*-(2-methanesulfonyl)ethoxycarbonyl group; it is used as an amino-protecting group, its stability to acid, lability to alkali, and resistance to hydrogenation contributing to its usefulness. It is introduced using such reagents as **methylsulfonyl nitrophenyl carbonate** and **methylsulfonyl succinimidyl carbonate**.



Msp-300 a protein (8204 amino acids) of *Drosophila* that is probably involved in tethering nuclei to the cytoskeleton. Homologous with ANC-1 of *Caenorhabditis elegans* and mammalian Syne proteins, it contains two actin-binding domains, large central domains composed of spectrin repeats, and a C-terminal nuclear envelope transmembrane domain.

MSP *abbr. for* maximum-scoring segment pair.

***Msp*I** a type 2 **restriction endonuclease**; recognition sequence: C↑CGG. *Hpa*II and *Hap*II are **isoschizomers**. *Msp*I is insensitive to methylation of the 5′C. *Compare* **HpaII**.

Mst1 *abbr. for* mammalian sterile twenty; a protein serine/threonine kinase that phosphorylates Ser14 of histone H2B. This phosphorylation correlates with the onset of apoptosis. Activity of the kinase is regulated by caspase-3.

MSX-1 *or* **Hox-7** a **homeobox** protein.

mtDNA *abbr. for* mitochondrial DNA.

MTOC *abbr. for* microtubule organizing centre.

mTor *abbr. for* mammalian target of rapamycin; *other name*: FKBP12-rapamycin-associated protein (*abbr.*: FRAP); a protein serine/threonine kinase that is inhibited by FKBP12-rapamycin. mTor phosphorylates the initiation factor eIF-4E and regulates S6 kinase and translation of mRNAs for ribosomal proteins and other components of the translation machinery. Its function is influenced by the intracellular concentration of ATP.

mtRNA *abbr. for* mitochondrial RNA.

MT-SP1 membrane type-serine protease 1; *other name*: matriptase; a human type II transmembrane serine protease (855 amino acids) that is present in the gastrointestinal tract, liver, spleen, thymus, and placenta.

mu *symbol*: μ (lower case) *or* M (upper case); the twelfth letter of the Greek alphabet. For uses *see* **Appendix A**.

MU *abbr. for* 4-methylumbelliferyl.

mu chain *or* **μ chain** the heavy chain characterizing **immunoglobulins** belonging to the class IgM.

mucic acid *an old name for* galactaric acid, the *meso*-aldaric acid derived from both D- and L-galactose.

mucilage any of numerous proteoheteroglycans, frequently containing uronic acids, that occur widely in plants, especially in seed coats. Mucilages are hard when dry; in water, they swell, but do not dissolve, to form slimy masses with adhesive properties. *Compare* **gum**. **—mucilaginous** *adj.*

mucin any of a group of widely distributed glycoproteins of high M_r that are secreted by various animal mucous cells and glands; they occur, e.g., in saliva, gastric juice, and intestinal juice. Mucins form viscous solutions that act as lubricants and protectants of the linings of body cavities and of the skin.

mucinase *an alternative name for* **hyaluronidase**.

mucin domain *other name*: PTS region; a proline and threonine/serine-rich peptide sequence present in an apomucin. It contains 8–169 amino acids, is poorly conserved, and frequently tandemly repeated. It provides the sites for *O*-glycosylation. *See* **mucin**.

muco+ *comb. form* of mucus or mucin; mucoid.

mucoid 1 any **mucin**-like substance or mucoprotein. **2** of the nature of, or resembling, **mucus**. **3** describing a bacterial colony that has a gummy consistency, resulting from the abundant synthesis of capsular material.

mucolipid *an alternative name for* **ganglioside**.

mucolipidosis (*pl.* **mucolipidoses**) any of a group of inherited autosomal recessive diseases of humans characterized by deficiency of a variety of lysosomal hydrolases in connective tissue cells of patients, and in fibroblasts cultured from them. Mucolipidosis I, commonly known as **sialidosis**, is due to a deficiency of neuraminidase that leads to accumulation of sialyl oligosaccharides, and excretion of these in the urine. In mucolipidosis II, the cytoplasm of cultured cells from affected patients contains numerous highly refractile inclusions, visible by phase-contrast microscopy. These are very large lysosomes containing heterogeneous material, mucopolysaccharides, glycolipids, and whorls of membranes, giving this the name **I-cell** (inclusion cell) **disease**. Mucolipidosis III is due to a deficiency of N-acetylglucosamine 1-phosphotransferase.

mucolytic having the ability to disrupt mucus.

muconate *a trivial name for* any one of the three stereoisomers (*cis*,*cis*, *cis*,*trans*, or *trans*,*trans*) of 2,4-hexadienedioate; 1,3-butadiene-1,4-dicarboxylate; $^{-}$OOC–CH=CH–CH=CH–COO^{-}, the dianion derived from muconic acid. The *cis*,*cis* isomer is an intermediate in the degradation of catechol by microorganisms.

muconolactone *Δ*-isomerase EC 5.3.3.4; an enzyme that catalyses the reaction:

2,5-dihydro-5-oxofuran-2-acetate =
3,4-dihydro-5-oxofuran-2-acetate

in the pathway for the degradation of catechol to acetyl-CoA.

mucopeptide *(sometimes) an alternative name for* **peptidoglycan**.

mucopolysaccharide any of a group of acid heteroglycans built up of characteristic repeating disaccharide units each consisting of an *N*-acylated hexosamine residue and a uronic-acid residue; many mucopolysaccharides also contain sulfate. The group includes hyaluronic acid (*see* **hyaluronate**), **chondroitin sulfate**, **dermatan sulfate**, **keratan sulfate**, **heparin**, and some **blood-group substances**.

mucopolysaccharide storage disease any of a group of clinically progressive, hereditary diseases of humans characterized by the accumulation of mucopolysaccharides in various tissues. They include the **mucopolysaccharidoses** and the **mucolipidoses**.

mucopolysaccharidosis (*pl.* **mucopolysaccharidoses**) any of a group of clinically progressive, hereditary diseases of humans each of which is characterized by the deficiency of a single lysosomal hydrolase concerned in the degradation of mucopolysaccharides. They have been classified into a number of types. *See* individual entries below.

mucopolysaccharidosis IH *or* **Hurler syndrome** a **mucopolysaccharidosis** caused by a deficiency in lysosomal L-iduronidase (EC 3.2.1.76) that affects the degradation of both dermatan sulfate and heparan sulfate. It is inherited as an autosomal recessive disorder. Subjects excrete excessive amounts of both dermatan sulfate and heparan sulfate in the urine in the ratio of approximately 7:3. The biochemical lesion is the same as in mucopolysaccharidoses IH/S and IS, from which differentiation can only be made by clinical criteria.

mucopolysaccharidosis IH/S *or* **Hurler–Scheie compound syndrome** a **mucopolysaccharidosis** caused by the same deficiency in lysosomal L-iduronidase (EC 3.2.1.76) as is found in mucopolysaccharidoses IH and IS. It is inherited as an autosomal recessive disorder and it is believed to be a phenotype intermediate between these two syndromes, one mutant allele being inherited from the father and a different mutant allele from the mother. The condition can only be differentiated from mucopolysaccharidoses IH and IS by clinical criteria.

mucopolysaccharidosis IS *or* **Scheie syndrome** *or (formerly)* **mucopolysaccharidosis V** a **mucopolysaccharidosis** caused by the same deficiency in lysosomal L-iduronidase (EC 3.2.1.76) as is found in mucopolysaccharidoses IH and IH/S. It is inherited as an autosomal recessive disorder and it has a milder clinical course than mucopolysaccharidoses IH and IH/S, from which it can be differentiated only by clinical criteria.

mucopolysaccharidosis II *or* **Hunter syndrome** a **mucopolysaccharidosis** caused by a deficiency in iduronate sulfatase that affects the degradation of both dermatan sulfate and heparan sulfate. It is inherited as an X-linked recessive disorder, and several different mutations of the same X-chromosome locus probably account for the different severities of the disease seen in various families. Subjects excrete excessive and roughly equal amounts of both dermatan sulfate and heparan sulfate in the urine.

mucopolysaccharidosis IIIA *or* **Sanfilippo syndrome A** a **mucopolysaccharidosis** caused by a deficiency in heparan *N*-sulfatase that affects the degradation of heparan sulfate. It is inherited as an autosomal recessive disorder and is indistinguishable clinically from mucopolysaccharidosis IIIB. Subjects excrete excessive amounts of heparan sulfate in the urine.

mucopolysaccharidosis IIIB *or* **Sanfilippo syndrome B** a **mucopolysaccharidosis** caused by deficiency in α-*N*-acetyl-D-glucosaminidase (EC 3.2.1.50) that affects the degradation of heparan sulfate. It is inherited as an autosomal recessive disorder and is indistinguishable clinically from mucopolysaccharidosis IIIA. Subjects excrete excessive amounts of heparan sulfate in the urine.

mucopolysaccharidosis IIIC (*abbr.*: MPS IIIC) *or* **Sanfilippo syndrome C** a mucopolysaccharidosis (MPS) that is clinically similar to MPS IIIA, IIIB, and IIID but caused by deficiency of lysosomal acetyl-CoA:α-glucosaminidine acetyl transferase, which affects the degradation of heparan sulfate. Subjects excrete excessive amounts of heparan sulfate in urine.

mucopolysaccharidosis IIID (*abbr.*: MPS IIID) *or* **Sanfilippo syndrome D** a mucopolysaccharidosis (MPS) that is clinically similar to MPS IIIA, IIIB, and IIIC, but caused by deficiency of *N*-acetyl glucosamine 6-sulfatase, which affects the degradation of heparan sulfate. Subjects excrete excessive amounts of heparan sulfate in urine.

mucopolysaccharidosis IVA (*or* **IVa**) *or* **Morquio A disease** a mucopolysaccharidosis caused by a deficiency of lysosomal *N*-acetylgalactosamine-6-sulfatase, leading to an accumulation of keratan sulfate and chondroitin 6-sulfate. It is inherited as an autosomal recessive disorder.

mucopolysaccharidosis IVB (*or* **IVb**) *or* **Morquio B disease** a mucopolysaccharidosis caused by a deficiency of β-galactosidase leading to accumulation of keratan sulfate. It is inherited as an autosomal recessive disorder.

mucopolysaccharidosis V *a former name for* **mucopolysaccharidosis I S**.

mucopolysaccharidosis VI *or* **Maroteaux–Lamy syndrome** a **mucopolysaccharidosis** caused by a deficiency of lysosomal *N*-acetylgalactosamine 4-sulfatase that affects the degradation of dermatan sulfate. Three clinically distinguishable forms are known: severe, intermediate, and mild; all are inherited as autosomal recessive disorders, with probably two or more mutant alleles at the mucopolysaccharidosis VI locus, one of which produces the severe form when homozygous and the other the mild form. Subjects excrete excessive amounts of dermatan sulfate in the urine.

mucopolysaccharidosis VII a **mucopolysaccharidosis** caused by a deficiency of lysosomal β-D-glucuronidase (EC 3.2.1.31) that affects the degradation of both dermatan sulfate and heparan sulfate. It is inherited as an autosomal recessive disorder.

mucopolysaccharidosis IX (*abbr.*: MPS IX) *or* **hyaluronidase deficiency** a rare mucopolysaccharidosis caused by deficiency of lysosomal endohexosaminidase (hyaluronoglucosaminidase; EC 3.2.1.35), which is responsible for degradation of hyaluronates primarily to a tetrasaccharide. Subjects excrete excessive amounts of hyaluronate in urine. The gene for the enzyme is at 3p21.2-p21.3.

mucoprotein any glycoprotein containing relatively large amounts of acidic polysaccharide.

mucosa (*pl.* **mucosae**) *or* **mucous membrane** any of the moist membranes that line the alimentary canal, the glandular ducts, and the respiratory, urinary, and genital passages; it may be smooth, corrugated, or covered with villi. Mucous membranes consist of a surface layer of epithelium containing mucus-secreting glands, and an underlying layer of connective and muscular tissue. *Compare* **serosa**. —**mucosal** *adj.*

mucotetraose *symbol*: $McOse_4$ *or* Mc_4 (if space is limited); the tetrasaccharide Gal(β1-3)Gal(β1-4)Gal(β1-4)Glc.

mucotriaose *symbol*: $McOse_3$ *or* Mc_3 (if space is limited); the trisaccharide Gal(β1-4)Gal(β1-4)Glc.

mucous relating to, resembling, or secreting **mucus**.

mucous cell any cell that secretes **mucus**.

mucous gland any exocrine gland consisting predominantly of **mucus**-secreting cells.

mucous membrane *an alternative name for* **mucosa**. *Compare* **serous membrane**. —**mucomembranous** *adj.*

mucus the slimy, sticky, viscous secretion, consisting predominantly of **mucins**, that is secreted by mucous cells of the mucosae and of the external body surface of some animals.

MUG *abbr. for* **1** either 4-methylumbelliferyl-glucuronide or 4-methylumbelliferyl-β-D-galactopyranoside. Both compounds are fluorogenic enzyme substrates that yield 4-methylumbelliferone. *See also* 4-**methylumbelliferyl**. **2** murinoglobulin.

MUGal *abbr. for* 4-methylumbelliferyl-β-D-galactopyranoside (alternative to MUG).

mugineic acid a phytosiderophore secreted by the roots of barley plants. It is derived from the α-aminobutyrate moieties of three molecules of *S*-adenosylmethionine by the action of nicotinamine synthase.

mull a suspension of very finely ground solid in an inert liquid, especially paraffin or **Nujol**, that is used in infrared spectroscopy of the solid.

Müllerian inhibiting factor *an alternative name for* **anti-Müllerian hormone**.

multi+ *comb. form* denoting more than one, several. *See also* **poly+**.

multicatalytic endopeptidase complex *see* **proteosome**.

multicellular having, or consisting of, several or many cells.

multichain (*of a protein*) consisting of two or more polypeptide chains connected by non-peptide links.

multichannel analyser any instrument or device for sorting a heterogeneous input into a number of ranges, e.g. of frequency or energy, and determining the relative proportions in each range.

multichannel pipette a plunger-operated pipette used for dispensing fluids in the microlitre range that is designed to deliver 4–8 samples of the same volume in parallel. The tips of the pipette have the same spatial separation as the wells on a **microtitre plate**.

multicopy single-strand DNA *abbr.*: msDNA; DNA generated by bacterial reverse transcriptase and found in certain Gram-negative bacteria. The molecules are unique in being the only known naturally occurring examples of nucleic acids containing an RNA–DNA covalent link.

multidentate (of a ligand) having two or more groups through which it can be attached to a central atom. Such a ligand is able to form a bridge or a chelate.

multidimensional chromatography a technique in which a single component separated from a mixture by chromatography on one type of column may be automatically transferred, as a sample, for chromatography on another type of column in order to effect further resolution.

multidrug resistance *see* **MDR**.

multidrug transporter a superfamily of integral membrane proteins found in nearly all cells. They bind to structurally and chemically diverse compounds and remove them from cells using energy derived from ATP or protonmotive force. First discovered in mammalian cells (*see* **MDR**) they also occur in bacteria and yeast. There are four classes: (1) ATP-binding cassette (ABC) transporters; (2) major facilitator (MRF) transporters; (3) small multidrug-resistance (SMR) transporters; and (4) resistance-nodulation (RND) transporters. The first class is ATP-dependent, the other three classes are proton-dependent.

multienzyme *the recommended class name for* any protein that possesses two or more autonomous catalytic functions due to separate catalytic domains (*see* **domain**, def. 3), whether contributed by distinct subunits (*see* **multienzyme complex**), by distinct parts of an individual polypeptide chain (*see* **multienzyme polypeptide**), or by both.

Excluded is any enzyme that can catalyse different reactions at the same catalytic centre. *Compare* **enzyme complex**, **multienzyme system**.

multienzyme cluster *see* **enzyme cluster**.

multienzyme complex *the recommended subclass name for* any multienzyme in which catalytic domains occur on more than one type of polypeptide chain. A multienzyme complex may itself contain a **multienzyme polypeptide**.

multienzyme polypeptide *the recommended subclass name for* any multienzyme in which at least two demonstrably distinct catalytic domains of different types occur on a single polypeptide chain and are encoded by a single gene. A multienzyme polypeptide may itself be a component of a multienzyme complex. *Compare* **multifunctional protein**.

multienzyme system *an operational term for* any system of two or more enzymes functioning sequentially to catalyse the reactions of a metabolic pathway, so that the product of the first enzyme becomes the substrate of the second and so on. Three levels of organization of multienzyme systems may be discerned. First, the individual enzymes are independently in solution in a compartment within a cell and are not directly associated with each other when acting. Second, the individual enzymes are physically associated and function together as an **enzyme complex**, or they occur as a **multienzyme**. Third and most highly organized, the individual enzymes are associated with large, supramolecular structures such as membranes or ribosomes. *See also* **enzyme cluster**, **metabolon**.

multifactorial 1 involving or dependent on more than one factor or causes. **2** *(in genetics)* inheritance depending on more than one gene.

multifunctional protein any protein that combines two or more autonomous functions on one polypeptide chain, the functions being both independently measurable and assignable to separate domains of the protein. Such functions may or may not be catalytic (*compare* **multifunctional protein ade2**). Excluded are allosteric enzymes, proenzymes, and enzymes that can catalyse different reactions at a single reaction centre.

multifunctional protein ade2 a protein that contains **phosphoribosylaminoimidazolesuccinocarboxamide synthase** and **phosphoribosylaminoimidazole carboxylase** and is involved in the sixth and seventh steps in *de novo* purine biosynthesis. The human enzyme consists of 425 amino acids; the synthase domain resides in residues 1–260, the carboxylase domain in residues 261–425.

multigenic describing a phenotype that results either from the inheritance of more than one mutant allele, or the interaction of a number of genes and environmental factors.

multiiodinated describing any compound that has been reacted so as to contain two or more atoms of iodine per molecule.

multilamellar occurring as, or made up of, several discrete layers.

multilayered film analyser a device for the rapid determination of any of a range of components present in small volumes of biological fluids. It depends on a single-use reagent slide on which the various chemicals required are present in dry form as a series of thin films. These consist successively of an indicator layer, a semipermeable layer, a reagent layer, and a spreading layer, all mounted between two transparent supports. Typically, a 10 μL sample is applied to the spreading layer, a chemical or enzymatic reaction occurs in the reagent layer, and the semipermeable layer withholds macromolecular substances from the indicator layer, where usually a dye combines with a product of the reaction to form a coloured compound. The intensity of the colour, which is proportional to the quantity of the analyte in the specimen, is measured by reflectance spectrophotometry. The concept has been extended to the use of potentiometry for the measurement of sodium and potassium.

multilocus enzyme any of a set of enzymes, with similar catalytic properties and existing in the same organism, whose amino-acid sequences are encoded in nonallelic structural genes at two or more separate loci. There may be marked variations in the expression of the individual loci in different tissues. A class of **isoenzyme**.

multimer any specific aggregate of (identical or nonidentical) molecular entities held together by noncovalent bonds. **—multimeric** *adj.*; **multimerize** *or* **multimerise** *vb.*; **multimerization** *or* **multimerisation** *n.*

multinucleate *or* **multinuclear** (of a cell) containing several or many nuclei.

multipass (*in protein biochemistry*) describing an integral membrane protein that contains more than one transmembrane segment. *Compare* **single-pass**.

multiphase having several phases; polyphase.

multiple alignment *see* **alignment**.

multiple alignment program *(in sequence analysis)* software for aligning more than two sequences of biopolymers. Evolutionarily rigorous multiple alignment is computationally intractable, and is therefore most often effected by means of heuristic techniques that progressively align pairs of aligned sequences: e.g. Clustal, T-Coffee. *See* **alignment**.

multiple cloning site a short DNA sequence in a cloning vector that incorporates recognition sites for a number of restriction endonucleases, which cut the vector only at this point. Their presence affords a choice of individual sites for cloning DNA or, by using two different sites, the possibility of cloning a DNA fragment in a desired orientation with respect to the vector. Also known as a **polylinker**.

multiple codon recognition the recognition by a single tRNA molecule of more than one type of codon in mRNA.

multiple development technique a chromatographic technique in which the chromatogram is developed more than once with either the same solvent system or a different one with the aim of improving the separation.

multiple drug resistance *see* **MDR**.

multiple forms (of an enzyme) *the recommended collective term to describe* all proteins that possess the same (specified) enzymic activity and occur naturally in a single species. It includes, but is not limited to, **isoenzymes**; the term isoenzyme should be applied only to multiple forms that arise from genetically determined differences in primary structure, and some limit this to those arising from a single gene locus.

multiple myeloma *or* **multiple myelomatosis** *see* **myeloma**.

multiple osteochondromata *an alternative name for* **hereditary multiple exostoses**.

multiple sclerosis *abbr.*: MS; a chronic and usually progressive disease of the nervous system, also known as disseminated sclerosis, in which the myelin sheaths surrounding the axons in the central nervous system are lost. The cause is unknown. It is generally considered to be a T-lymphocyte-mediated autoimmune disorder targeted at myelin-specific components. A major antigen during the inflammatory phase is αB-crystallin. It is accompanied by formation of plaques, microscopic to macroscopic in size and containing activated lymphocytes and monocytes. The disease is characterized by a course of relapses and remissions over a number of years.

multiplet any group of two or more associated spectral lines. In electronic spectra the lines of a multiplet are very closely spaced and appear at low resolution as a single line, whereas in nuclear magnetic resonance spectra the separation may be considerable.

multiplicand *(in mathematics)* a number to be multiplied by another number – the multiplier – in an arithmetic multiplication.

multiplication-stimulating activity *abbr.*: MSA; an activity found in mammalian serum and produced by some animal cells that is required for the multiplication of animal cells in culture.

multiplicity *(in physics)* the number of components in a **multiplet**.

multiplicity of infection the ratio of the number of virus particles to the number of susceptible cells in a given system.

multiplicity reactivation the reconstruction of viable genomes in a cell that is multiply infected with otherwise nonviable viruses.

multiplier 1 *(in mathematics)* any number by which another number – the multiplicand – is multiplied. **2** any instrument or device for multiplying an effect, e.g. photomultiplier.

multiplying prefix a prefix to denote the presence of several identical substituents in a molecule, at different positions. The prefix ‘bis’ indicates two substituents, for example fructose-1,6-bisphosphate; by contrast the prefix ‘di’ indicates that both substituents are linked at the same position, e.g. adenosine diphosphate. ‘tris’ corresponds to three substituents, and subsequently the names are formed by adding the ending ‘kis’ to the basic multiplying prefix ending in ‘a’, e.g. ‘tetrakis’, ‘pentakis’, ‘hexakis’.

multiply labelled describing an isotopically substituted compound that has more than one modified atom of the same element at the same position or at different positions.

multipotent (of a cell or tissue) capable of giving rise to several kinds of cells, tissues, or structures. *Compare* **pluripotent** (def. 2).

multisubstrate enzyme any enzyme that requires two or more substrates in order to catalyse a particular reaction.

multiubiquitin *see* **polyubiquitin**.

multivalent *an alternative term for* **polyvalent**.

multivalent phosphorylation the phosphorylation of any hormonally regulated enzyme at a plurality of sites by two or more distinct kinase enzymes, with a resultant increase in the regulatory potential of the enzyme.

multivesicular body an intracellular structure that is lined by a single membrane and contains a number of inner vesicles that are approximately 50 nm in diameter. It is a form of secondary **lysosome**.

multi-wavelength anomalous dispersion *abbr*.: MAD; a method for solving macromolecular structures containing different elements by X-ray crystallography, in which the phases are resolved by diffraction at X-ray wavelengths near to an absorption edge of the element.

***Mun*I** a type 2 **restriction endonuclease**; recognition sequence: C↑AATTG. *Mfe*I is an **isoschizomer**.

mupirocin a substance produced by *Pseudomonas fluorescens* and active against Gram-negative bacteria. It is used to treat impetigo and skin infections. It inhibits protein synthesis by reversibly and specifically binding to isoleucine transfer-RNA ligase (*see* **transfer RNA**).

Mur *symbol for* a residue (or sometimes a molecule) of **muramic acid**.

muramic acid *symbol*: Mur; 3-*O*-*α*-carboxyethyl-D-glucosamine; the 3-*O*-D-lactyl ether derivative of D-glucosamine. It occurs naturally in peptidoglycan of bacterial cell walls.



muramidase *an alternative name for* **lysozyme**.

muramyl the acyl group derived from **muramic acid**.

muramyl-dipeptide *abbr*.: MDP; *N*-acetyl-muramyl-D-alanyl-D-isoglutamine; a synthetic, water-soluble, **peptidoglycan** derivative that is capable of replacing whole mycobacteria in complete **Freund's adjuvant**. It is highly active in stimulating antibody production against an antigen injected simultaneously.

murein *an alternative name for* **peptidoglycan**.

murexide ammonium purpurate; 5,5′-nitrilodibarbituric acid monoammonium salt; a compound that forms a purple-red solution in water. It is useful as an indicator in complexometric titration of calcium, nickel, cobalt, copper, etc. with EDTA.



murexide test a colour test for uric acid and some other purines. The (solid) sample is first treated with conc. nitric acid, which is slowly evaporated away; subsequent addition of ammonia solution gives a purple colour if uric acid was present, due to formation of murexide, or a yellow colour that turns to red on heating if xanthine was present.

murine of, belonging to, characteristic of, affecting, transmitted by, or being a member of the Muridae, a family of small rodents that includes mice and rats; of or relating to the mouse genus, *Mus*.

murine toxin *or* ***Yersinia*** **murine toxin** the product of the *Ymt* gene on a plasmid of *Yersinia pestis* (the causative agent of bubonic plague). It belongs to the phospholipase D family of enzymes and causes hypotension and vascular failure as a result of release from lysing bacteria during the terminal stages of septicemic plague. It is required for survival of the *Yersinia* bacteria in the midgut of the rat flea *Xenopsylla cheopis*.

murinoglobulin *abbr*.: MUG; a monomeric protease inhibitor found in blood plasma of vertebrates and invertebrates, and in egg white of birds and reptiles. It has a characteristic **bait region**. *Compare* **α_2 macroglobulin**.

muropeptide *an alternative name for* **peptidoglycan**.

muscarine a toxic alkaloid (quaternary ammonium base) found in the red variety of *Amanita muscaria* (fly agaric) and some other gill fungi. It is an agonist for one type of **cholinoceptor**.



(+)-enantiomer

muscarinic receptor *see* **cholinoceptor**.

muscimol 5-aminomethyl-3-hydroxyisoxazole; an isoxazole isolated from the fungus *Amanita muscaria*. A hallucinogen and potent CNS depressant, it is a selective agonist of GABA$_A$ receptors.



muscle 1 a tissue made up of various elongated cells that are specialized to contract and thus to produce movement and mechanical work. **2** an organ consisting principally of muscle tissue. *See* **cardiac muscle**, **smooth muscle**, **striated muscle**. —**muscular** *adj.*

muscle contraction *see* **sliding filament model**.

muscle hemoglobin *a former name for* **myoglobin**.

muscle sugar *a former name for* **inositol** (def. 1).

muscular dystrophy any genetically determined disease of humans in which there is progressive muscular weakness and evidence of muscle degeneration. All are characterized by creatinuria, and serum creatine phosphokinase activity is elevated in several of them. *See also* **dystrophin**.

musculin *see* **capsulin.**

mushroom sugar *a former name for* **trehalose**.

Musk *abbr. for* muscle-specific kinase; a skeletal muscle-specific receptor-tyrosine kinase found at neuromuscular junctions. It may be involved in clustering of acetylcholine receptors and dystroglycans.

mustard gas sulfur mustard; bis(2-chloroethyl)sulfide; a colourless oily liquid with a very low vapour pressure. It is a powerful vesicant and also a mutagen and carcinogen. *See also* **nitrogen mustard**.

mustard oil any alkyl isothiocyanate, of general formula R–N=C=S. Such compounds have a pungent mustard-like smell and are present in the tissues of a number of plants, either free or as thioglycosides.

mut any of a family of genes whose products are involved in **mismatch repair**. All the following examples are from *Escherichia coli*. The product of *mutH* is a repair endonuclease that is specific for unmethylated GATC sequences. The protein encoded by *mutL* is also involved in repair of mismatches in DNA and is required for activity of the *dam* product. The protein encoded by *mutS*, again involved in mismatch repair (possibly the recognition step), has weak ATPase activity.

mutable able or tending to undergo change or **mutation**. **—mutability** *n.*

mutable gene any gene that spontaneously mutates at a high rate.

mutable site any site on a chromosome at which mutations can occur.

mutagen any physical or chemical agent that is capable of increasing the frequency of **mutation** above the spontaneous, background level. **—mutagenic** *adj.*; **mutagenicity** *n.*

mutagenesis the production of mutations.

mutagenize *or* **mutagenise** to treat (cells or organisms) with a mutagen. **—mutagenized** *or* **mutagenised** *adj.*

mutant 1 a any organism that has arisen by or has undergone **mutation**, or one that carries a mutant gene that is expressed in the phenotype of that organism. **b** a mutant gene. **2** produced by or following a mutation; having the attributes of a **mutant** (def. 1).

mutarotation the spontaneous change in the optical rotation of a freshly prepared solution of a pure stereoisomer, especially a carbohydrate, that is caused by epimerization, or some other structural change.

mutase any enzyme that catalyses (or apparently catalyses) an intramolecular transfer of a chemical group. Such enzymes belong to one of the following EC sub-subclasses: EC 5.4.1, transferring acyl groups; EC 5.4.2, transferring phosphoryl groups; EC 5.4.3, transferring amino groups; EC 5.4.99, transferring other groups.

mutate to undergo or cause to undergo mutation.

mutation 1 the process by which genetic material undergoes a detectable and heritable structural change, or the result of such a change. Three categories are recognized: **genome mutations**, in which addition or subtraction of one or more whole chromosomes occurs; **chromosome mutations**, in which the structure of one or more chromosomes is affected; and **gene mutations**, in which the structure of a gene is altered at the molecular level. **2** any modified gene arising from a **mutation** (def. 1). **3** a **mutant** (def. 1). *See also* **deletion**, **inversion** (def. 4), **point mutation**, **translocation** (def. 2).

mutational heteroduplex *see* **heteroduplex**.

mutation bias bias in the mutation frequencies of different codons, affecting the synonymous to nonsynonymous rate ratio. Mutation bias results in an accelerated rate of amino acid replacement in functionally less constrained regions.

mutation frequency the frequency at which a mutation occurs in a population. It may or may not reflect the **mutation rate**, with which it is sometimes used interchangeably.

mutation frequency decline the significant and irreversible reduction in the frequency of some UV-induced mutations in bacteria during the temporary post-irradiation inhibition of protein synthesis.

mutation matrix *an alternative name for* **substitution matrix**.

mutation pressure the continued production of an allele by mutation that tends to increase the allele's frequency in the gene pool.

mutation rate 1 the probability that a particular mutation will occur per virus, cell, or organism during a reproductive cycle. **2** the frequency at which any mutation or mutational class occurs in a given population; **mutation frequency**.

mutator gene any gene that produces an increase in spontaneous mutation rates. Their action may be limited to certain alleles or to certain mutational pathways.

mutein a mutant protein produced by site-specific mutagenesis or other recombinant DNA technique.

MutH a protein of *E. coli* that is involved, with **MutS** and **MutL**, in DNA mismatch repair. No homologue appears to have been found in eukaryotic cells. It functions as a site-specific endonuclease.

MutL a protein of *E. coli* that is involved, with **MutS** and **MutH**, in DNA mismatch repair. MutL homologues (*abbr*.: MLH) are present in all eukaryotic cells. Mutations in the human homologue (hMLH) are common in hereditary nonpolyposis colon cancer.

muton the smallest unit of genetic material whose alteration may give rise to a mutation; commonly supposed to be a single nucleotide (pair).

MutS a homodimeric mismatch-binding protein of *E. coli* that is involved, with **MutH** and **MutL**, in DNA mismatch repair. MutS homologues (*abbr*.: MSH) exist in all eukaryotic cells. In yeast they are called MSH1 and MSH2. Mutations in the human homologue (hMSH2) are common in hereditary nonpolyposis colon cancer.

MVA *abbr. for* mevalonic acid (use discouraged).

***Mva*I** a type 2 **restriction endonuclease**; recognition sequence: CC↑[AT]GG. *Eco*RII is an **isoschizomer**.

M13 vector a DNA cloning vector based on the genome of the filamentous bacteriophage M13. In some **phagemids** only the M13 origin of replication is used.

MVG *abbr. for* methoxyvinylglycine.

MVP *abbr. for* major vault protein. *See* **vault**.

M.W. *abbr. for* molecular weight (alternative to mol. wt.).

MWC model *abbr. for* Monod–Wyman–Changeux model.

my+ *a variant form of* **myo+** (before a vowel).

MYB a gene family that encodes DNA-binding proteins; v-*myb* is the oncogene of the acutely transforming avian myeloblastosis virus. It is highly conserved between mammalian species. The product, Myb, contains DNA-binding, transcriptional activation, and negative regulatory domains; it recognizes YAAC(G/T)G. It is notably associated with cells of the hemopoietic lineage and is essential for normal hemopoiesis. It is expressed in some human malignant tumours. [From 'myeloblastosis'.]

MYC a family of genes encoding short-lived nuclear regulatory proteins that act as transcription factors, e.g. pp64/pp67 (based on expressed mass). The oncogene, v-*myc*, was originally identified in avian myelocytomatosis virus, MC29, but is also carried by the avian retroviruses CM11 and OK-10. The protooncogene, c-*myc*, is a member of a family of at least seven related genes: *myc*, B-*myc*, N-*myc*, L-*myc*, P-*myc*, R-*myc*, and S-*myc*; B-Myc lacks the basic helix-loop-helix leucine zipper (bHLHLZ) domains of other Myc proteins. The product of c-*myc* binds nonselectively to DNA and (with higher affinity) to CAC[GA]TG. In normal cells *myc* expression is strictly dependent on mitogenic stimuli and is required for cell proliferation as well as to prevent cell differentiation. Induction of c-*myc* in the absence of growth factors is sufficient to drive rodent fibroblasts into the cell cycle but concomitantly induces apoptosis unless specific survival cytokines are present. Structurally, the product Myc contains an N-terminal transactivation domain that activates transcription of the gene with which it interacts, and a C-terminal bHLHLZ motif, which is known to mediate Myc dimerization and sequence-specific DNA binding. Although Myc–Myc dimers can form in solution, Myc homodimers are not detected *in vivo*, dimers forming with other partners, e.g. Max, which has a bHLHLZ motif but no transactivation domain (*see* ***MAX***). *In vitro*, Myc–Max (and Myc–Myc) dimers have been found to bind DNA with a core sequence of CACGTG. Unlike Myc, Max is a stable protein expressed constitutively in growing, resting, and differentiating cells, and is capable of binding further proteins, e.g. Mad and Mxii, which compete with Myc for binding. The *myc* gene may be activated to become a transforming gene by proviral insertion, chromosomal translocation, or gene amplification, but generally protein structure is not affected; **Philadelphia chromosome** is one example. The *myc* gene has been implicated in various neoplasms in birds, mice, and humans, oncogenic activation occurring mainly through constitutive and elevated expression of the Myc protein. [From 'myelocytomatosis'.]

myc+ *a variant form of* **myco+** (before a vowel).

mycarose 2,6-dideoxy-3-*C*-methyl-L-*ribo*-hexose; a component of several **macrolide** antibiotics.

mycelia the plural of **mycelium**.

mycelium (*pl.* **mycelia**) the network or mass of discrete hyphae that forms the body (thallus) of a fungus. **—mycelial** *adj.*

myceto+ *or (before a vowel)* **mycet+** *comb. form* denoting fungus.

myco+ *or (before a vowel)* **myc+** *comb. form* denoting fungus.

mycobacterium (*pl.* **mycobacteria**) any bacterium belonging to the genus ***Mycobacterium***.

Mycobacterium a genus of Gram-positive, aerobic, nonmotile, non-spore-forming, acid-fast bacteria of the family Mycobacteriaceae. The cells are rodlike and can form filaments or branched structures; their cell walls characteristically contain **mycolic acid**.

Some species are pathogenic to humans and/or other animals, e.g. *M. tuberculosis* (the tubercle bacillus) and *M. leprae* (the leprosy bacillus).

mycobactin any of a family of **siderochromes** of the hydroxamic acid-derivative category, produced by various species of *Mycobacterium*. At least nine have been characterized.

mycolic acid any of a family of α-substituted β-hydroxylated very-long-chain fatty acids of general formula R_2–CH(OH)–CHR_1–COOH, where R_1 is a C_{20}–C_{24} linear alkyl group and R_2 is a complex C_{30}–C_{60} group of very variable structure. They occur naturally as esters of arabinose in the cell walls of *Mycobacterium* spp., *Nocardia* spp., and *Corynebacterium* spp. and as esters of trehalose in **cord factor**. *See also* **cyclic fatty acids**.

mycology the scientific study of fungi. **—mycological** *or* **mycologic** *adj.*; **mycologist** *n.*

mycolyl *the generic name for* acyl groups derived from **mycolic acids**.

mycophenolic acid 6-(1,3-dihydro-4-hydroxy-6-methoxy-7-methyl-3-oxo-5-isobenzofuranyl)-4-methyl-4-hexenoic acid; an antibiotic and antitumour material from *Penicillium brevi-compactum*. It was first isolated in 1896, and said by the Australian physiologist Howard Florey (1898–1968) to be 'the first antibiotic produced by a mould to be crystallized'. As the morpholinoethyl ester (mycophenolate mofetil) it is an approved immunosuppressant in renal transplantation. Transformed mammalian cells expressing *E. coli* guanine phosphoribosyltransferase (GPT) are resistant to mycophenolic acid if grown in a medium supplemented with xanthine.



mycoplasma *or (formerly)* **pleuropneumonia-like organism** (*abbr*.: PPLO) any member of the Mycoplasmatales, an order of minute, Gram-negative, prokaryotic microorganisms that are the smallest known free-living organisms. They have no cell walls (except for some saprophytic species), are variable in form, and can pass through bacteria-retaining filters. Some are saprophytic while others are pathogenic to humans, other animals, and plants. Mycoplasmas frequently infect tissue cultures. They were once thought to be the same as **L forms**. A newer classification replaces mycoplasma as a trivial name for members of the entire class by the term **mollicute**, and the class is called Mollicutes. The trivial name 'mycoplasma' is then restricted to members of the genus *Mycoplasma*.

Mycoplasma the main genus of **mycoplasmas**.

mycoprotein a commercially produced protein-containing foodstuff derived from moulds grown on carbohydrate substrates.

mycosamine 3-amino-3-deoxy-D-rhamnose; 3,6-dideoxy-3-amino-D-mannose; an amino sugar that contributes the nitrogen-containing moiety of the polyene antibiotics **amphotericin B** and **nystatin**.



mycose *a common name for* **trehalose**.

mycostatic describing any agent that inhibits the growth of fungi; fungistatic.

mycothiol 1-*O*-(2-[*N*-acetyl-L-cysteinyl]amido-2-deoxy-α-D-glucopyranosyl)-D-*myo*-inositol, the major low-molecular-mass thiol in mycobacteria; it is associated with the protection of *Mycobacterium tuberculosis* from oxidants and antibiotics.



mycotoxin any poisonous substance produced by a fungus that is not a mushroom. Examples include aflatoxin, ochratoxin, and patulin.

myel+ *a variant form of* **myelo+** (before a vowel).

myelin the material that constitutes the **myelin sheaths** surrounding vertebrate nerve axons. It is rich in lipid, particularly in glycolipid. *See also* **myelin protein**.

myelination the process by which a nerve axon acquires a **myelin sheath**.

myelin protein any of the proteins that form part of the **myelin sheath**. In the following descriptions, all examples are of human precursor sequences. **Myelin-associated glycoprotein**, a cell adhesion molecule for postnatal neural development, is a member of the immunoglobulin superfamily; it is an integral membrane protein. **Myelin basic protein**, a protein of the cytoplasmic face of the myelin membrane, is a major protein component of normal myelin of the central nervous system (CNS). Very basic in nature (pI > 10.5), it is a single-chain protein with little structure. Administration of myelin basic protein in complete **Freund's adjuvant** in various experimental animals elicits experimental allergic encephalitis, owing to induction of delayed hypersensitivity to the protein, which is thought to have an important role in causing demyelinating diseases in humans. Three forms are produced by alternative splicing. **P2** is probably a lipid transport protein; it is found in Schwann cells, associated with myelin basic protein. **P0** is an immunoglobulin-like membrane protein of Schwann cells of the peripheral nervous system; it is associated with a hereditary polyneuropathy (Charcot–Marie–Tooth disease type 1b). **Myelin proteolipid protein** (PLP *or* **lipophilin**) is the major myelin protein from the CNS, playing an important role in the formation, or maintenance, of the multilamellar structure of myelin; it is an integral membrane protein. Alternative splicing leads to a shorter variant. Mutations are associated with Pelizaeus–Merzbacher disease, and other mutations result in dysmyelination, e.g. *jimpy* and *rumpshaker* (mouse), and MD (rat). *See also* **Folch-Lees protein**, **Wolfgram proteolipid protein**.

myelin-proteolipid *O*-palmitoyltransferase EC 2.3.1.100; *other names*: myelin PLP acyltransferase; acyl-protein synthase; an enzyme that catalyses a reaction between palmitoyl-CoA and [myelin proteolipid] to form [myelin proteolipid] *O*-palmitoylprotein and CoA.

myelin sheath the sheath that surrounds the axons of vertebrate nerves. It is formed by Schwann cells in peripheral nerves and by oligodendrocytes in the central nervous system; these cells wrap up to 100 concentric layers of their plasma membrane in a tight spiral around the axons. Myelin sheaths prevent almost all electric current leakage across the covered portion of the axon membrane, thereby contributing to the rapid transmission of nerve impulses along the axons. *See also* **myelin**, **myelin protein**.

myelo+ *or (before a vowel)* **myel+** *comb. form* **1** denoting bone marrow. **2** denoting the spinal cord. **3** denoting **myelin**.

myeloblast a cell of the bone marrow that is the precursor of the **myelocyte**.

myelocyte a nucleated cell of the bone marrow that is a precursor of the **granulocytes** of the blood.

myeloid **1** of or pertaining to bone marrow. **2** of or pertaining to the spinal cord. **3** of or resembling myelocytes.

myeloma *or* **myelomatosis** a tumour caused by the uncontrolled proliferation of a clone of immunoglobulin-producing plasma cells. It leads to multiple deposits of tumour cells in the bone marrow and an excessive production of a single type of (i.e. monoclonal) immunoglobulin molecule, which may belong to any of the major classes of immunoglobulins. In some cases either the light or the heavy chains may be produced in excess or exclusively. *See also* **Bence-Jones protein**, **Waldenström's macroglobulinemia**.

myeloma protein an immunoglobulin that is overproduced by a **myeloma**. They are single immunoglobulin types and form the basis of monoclonal antibody technology. Human examples include **Bence-Jones protein**. *See also* **hybridoma**.

myeloperoxidase *a special name for* **peroxidase** (def. 2), so named following its isolation from the blood of patients with myeloid leukemia, and originally named **verdoperoxidase** on account of its green colour. It is present in phagosomes of neutrophils and monocytes, where it catalyses the reaction:

$$H_2O_2 + 2Cl^- = 2HOCl.$$

The reaction product is strongly bactericidal. The enzyme is a heterotetramer of two α subunits (59 kDa) linked by disulfide bonds, and two β subunits (13 kDa). Each α subunit contains a heme group and a Ca^{2+}-binding region. Both subunits are derived from the same precursor. Several isozymes are produced by alternative splicing. Myeloperoxidase deficiency, resulting from mutation in the gene at 17q22, is not rare. It is frequently asymptomatic but may be accompanied by repeated infection.

Mylar *the proprietary name for* a type of polyethylene terephthalate polyester that forms very strong films of good transparency and high electrical resistance.

myo+ *or (before a vowel)* **my+** *comb. form* denoting muscle.

myo- *prefix* used to distinguish common **inositol**, 1,2,3,5/4,6-cyclohexanehexol (*formerly meso*-inositol), from the other eight possible inositol stereoisomers.

myoadenylate deaminase *see* **adenylate deaminase**.

myoblast any of the mononucleate precursor cells that fuse to form a multinucleate skeletal muscle cell.

myocardin a transcription factor expressed exclusively in myocardium after birth.

myocardium the middle, muscular, layer of the heart wall. **—myocardial** *adj.*

myocilin *or* **TIGR** a protein (504 amino acids) expressed in many tissues but having no known function. It contains an N-terminal hydrophobic region, a leucine zipper region, and a region of homology with myosin heavy chain. Mutations in the gene at 1q23 are responsible for autosomal dominant open-angle glaucoma.

myocyte 1 a muscle cell of any type. **2** any contractile cell.

myocyte enhancement factor *abbr*.: MEF; a transcription factor that binds an AT-rich DNA sequence in the promoter region of many muscle-specific genes. There are at least four MEF genes in vertebrates, which are nearly identical in coding N-terminal regions that serve for dimerization and DNA binding.

myoD the gene for myoblast determination protein, a basic helix-loop-helix transcription factor related to ***MYC***; the human equivalent is *MYF3*. It is expressed after **myogenin**.

myofibre *or (esp. US)* **myofiber** a skeletal muscle fibre; it consists of a single, long, multinucleate cell, composed predominantly of a large number of myofibrils (typically 1000 or more).

myofibril any of the long, cylindrical, contractile elements, 1–2 µm in diameter, that comprise the major component of the cytoplasm of the **myofibre** and extend for its entire length. Each myofibril is composed in turn of numerous **myofilaments**. **—microfibrillar** *adj.*

myofilament either of two kinds of thin, contractile, threadlike, interdigitating structures within the myofibrils of **striated muscle**. The so-called thick filaments are about 15 nm in diameter and 1.6 µm in length, and the so-called thin filaments are about 8 nm in diameter and 1.0 µm in length.

myogen *a name sometimes used for* a number of different protein mixtures extractable with water from skeletal muscle of various species of animal. **Myogen A** is a crystallizable complex of **aldolase** and **glycerol-3-phosphate dehydrogenase** that can be prepared from rabbit muscle.

myogenic factor any of various proteins involved in muscle differentiation. They are normally produced only in muscle cells, but have been shown to activate muscle differentiation mechanisms when introduced into other cells. They include MyoD (*see* **myoD**), Myf5, and **myogenin**.

myogenin a protein involved in muscle differentiation (i.e., a **myogenic factor**) that induces fibroblasts to differentiate into myoblasts. It is probably a sequence-specific DNA-binding protein, similar to other members of the Myc family of **helix-turn- helix** transcription factors (*see* ***MYC***).

myoglobin *or (formerly)* **muscle hemoglobin** *or* **myohemoglobin** *abbr*.: Mb; a 17.5 kDa oxygen-carrying hemoprotein that occurs in muscle, particularly in red fibres, and consists of a single polypeptide chain of 153 amino-acid residues, to which a single ferroheme prosthetic group is non-covalently bound. Myoglobin binds dioxygen non-cooperatively, with an affinity between that of hemoglobin and of cytochrome oxidase. It can thus accept dioxygen from hemoglobin, and store it in the muscle cell for release to cytochrome oxidase when the supply becomes limiting. It also assists the direct transfer of dioxygen from the surface of the myocyte to the mitochondria. Sperm-whale myoglobin was the first protein whose 3-D stucture was determined by X-ray crystallography.

myoglobinuria the excretion of myoglobin in the urine.

myohaematin *a historical term*, used by MacMunn for the 'histohaematin' (i.e. the cytochromes) of striated muscle.

myo*-inositol** *an alternative name for* **inositol** (def. 1) (*formerly known as* **muscle sugar**). *See also* ***myo-.

1D-*myo*-inositol-trisphosphate 3-kinase EC 2.7.1.127; an enzyme that catalyses a reaction between ATP and 1D-*myo*-inositol 1,4,5-trisphosphate to form 1D-*myo*-inositol 1,3,4,5-tetrakisphosphate with release of ADP. The enzyme requires calcium. *See also* **inositol phosphates**.

myokinase *an alternative name for* **adenylate kinase**.

MyoR *see* **capsulin.**

myosin any of a group of related proteins with ATPase activity that occur in the contractile apparatus of both muscle and non-muscle cells; the myosin of striated muscle is the major component of the thick filaments. Individual myosin molecules consist of two identical **heavy chains** of ~200 kDa and two pairs of light chains (*see* **light chain** (def. 2)) with distinct masses that vary within the range 15–27 kDa according to the source. The N-terminal region of each heavy chain consists of a globular head with which the light chains are associated; the remaining three-quarters of each heavy chain consists predominantly of an alpha helix, which intertwines with its partner to form a long tail. The head region contains binding sites for actin and for ATP, while aggregation with other myosin molecules to form filaments occurs at the tail region. For example, human muscle protein is a hexamer of two heavy chains and four light chains. Different isoforms exist for different muscle types. Light chain 1, the skeletal muscle isoform, contains an **EF hand** motif. Some early preparations of myosin were denoted by letters. Thus, myosin A and myosin B were actin-poor and actin-rich preparations respectively, while myosin T and L-myosin were among the first actin-free preparations. The name myosin was originally given by F. W. Kühne, in 1859, to the substance in muscle press juice that, on standing at room temperature, set to a gel.

myosin-binding C protein a protein that is arranged transversely in seven to nine strips in the A bands of muscle **sarcomeres**. It binds the coiled-coil portion of myosin heavy chains to titin. A gene at 11p11.2 encodes the cardiac isoform, a protein of ≈1200 amino acids that contains immunoglobulin-like and fibronectin repeats. Various mutations cause hypertrophic cardiomyopathy.

myosin-heavy-chain kinase EC 2.7.1.129; an enzyme that catalyses the phosphorylation by ATP of specific threonines of myosin heavy chain with release of ADP, during chemotaxis of *Dictyostelium discoideum* (slime mould). It inhibits myosin thick filament formation.

myosin-light-chain kinase EC 2.7.1.117; *other names*: myosin kinase; smooth-muscle-myosin-light-chain kinase; an enzyme that catalyses the phosphorylation by ATP of myosin light chain with release of ADP. It was one of the first Ca^{2+}/calmodulin-dependent protein kinases to be discovered. Its specificity is restricted to myosin light chain. In skeletal muscle, light-chain phosphorylation modulates tension during contraction. In smooth muscle, it initiates contraction.

myosin-light-chain-phosphatase EC 3.1.3.53; *other names*: myosin light chain kinase phosphatase; myosin phosphatase; an enzyme that catalyses the hydrolysis of phosphate from myosin light-chain phosphate.

myostatin a protein of the transfoming growth factor β superfamily that is expressed in cells of skeletal muscle lineage. Gene knockout in mice, and deficiency in cattle, cause dramatic and widespread increase in skeletal muscle mass. Overexpression or prolonged injection in mice lead to severe loss of muscle and adipose tissue. Myostatins from many vertebrate species have an identical, biologically active C-terminal region. Mutations in cattle produce double-muscling.

myotonia any genetically distinct hereditary disease characterized by muscle hyperexcitability, hypertrophy, and stiffness. Myotonia congenita results from numerous mutations in the gene for the sarcolemmal voltage-gated chloride channel, which normally forms multimeric subunits each of which contains ≈13 transmembrane segments.

myotonia congenita *see* **myotonia**.

myotonic dystrophy a common hereditary muscular dystrophy in which muscle wasting and weakness (i.e. dystrophy) are associated with stiffness (i.e. myotonia). Type 1 is due to expansion of a CTG trinucleotide repeat in the 3′ untranslated region of the gene (at 19q13.2) for muscular dystrophy protein kinase. Type 2 is due to expansion of a CCTG tetranucleotide repeat in intron 1 of the gene (at 3q21) for **ZNF9**.

myotonic dystrophy protein kinase a cytosolic protein-serine/threonine kinase found predominantly in heart, skeletal muscle, brain, and eye. The gene at 19q13.2-q13.3 encodes a protein of 585 amino acids. In persons affected by myotonic dystrophy type 1, the 3′ untranslated region contains 50 to several thousand repeats of the trinucleotide CTG. Normal subjects have less than 37 such repeats, whereas healthy genetic carriers of the disorder have 50 to 100 repeats.

myotrophin a 12 kDa protein of hypertrophied myocardium of spontaneously hypertensive rats that stimulates protein synthesis in cultured adult rat myocytes *in vitro*. It contains **ankyrin** repeats, and binds to **NF-λB**.

myotube the multinucleate structure formed by the fusion of proliferating myoblasts in culture under certain conditions. It is characterized by the presence of certain muscle-specific proteins that are not found in the myoblast and may represent a stage in the development of skeletal muscle cells.

myotubularin a protein encoded by a gene at Xq28, mutations of which cause X-chromosome-linked myotubular myopathy. The protein contains ≈621 amino acids, which include a sequence that corresponds exactly with the consensus sequence for tyrosine phosphatases. It is expressed in skeletal muscle and testes, but not in fetal tissues (e.g. brain, liver, kidney).

Myr *symbol for* the **myristoyl group**.

myricetin 3,3′,4′,5,5′,7-hexahydroxyflavone; a **flavone** that is widely distributed in plants. The name originates from *Myrica*, a genus of shrubs. Myricetin inhibits a number of enzymes, including *α*-glucosidase, xanthine oxidase, and glyoxalase.



myricyl *or* **melissyl** *the common name for* triacontyl, CH_3–$[CH_2]_{28}$–CH_2–, the alkyl group derived from the C_{30} straight-chain alkane, triacontane. Myricyl palmitate is the major component of beeswax.

myristate **1** *the trivial name for* tetradecanoate, CH_3–$[CH_2]_{12}$–COO^-, the anion derived from myristic acid (i.e. tetradecanoic acid), a saturated straight-chain higher fatty acid and a major component of many plant and animal fats. **2** any mixture of free myristic acid and its anion. **3** any salt or ester of myristic acid.

myristin *an old name for* any of the glyceryl esters of myristic acid, especially the triester, **trimyristin**, or trimyristoylglycerol.

myristoleic acid *see* **tetradecenoic acid**.

myristoyl *or (formerly)* **myristyl** *symbol*: Myr; *the trivial name for* tetradecanoyl, CH_3–$[CH_2]_{12}$–CO–, the acyl group derived from myristic acid (i.e. tetradecanoic acid). It occurs in most animal and plant fats and oils as acylglycerols and in phospholipids. The oils of the seeds of nutmeg (*Myristica fragrans*) and other members of the Myristicaceae are particularly rich sources. *Compare* **myristyl**.

myristoylation the introduction of one or more **myristoyl** groups into an organic compound. Protein *N*-myristoylation refers to the covalent attachment of a **myristoyl** group via an amide bond to the N-terminal Gly residue of a nascent polypeptide. This **post-translational modification** has only been observed in eukaryotes and is irreversible. The *N*-myristoyl proteins are numerous with diverse functions. In some cases the modification is essential for the biological role of the protein, while in other cases it is not essential. The process is catalysed by glycylpeptide *N*-tetradecanoyltransferase (EC 2.3.1.97).

myristyl **1** *the common name for* tetradecyl, CH_3–$[CH_2]_{12}$–CH_2–, the alkyl group derived from tetradecane; use deprecated. **2** *a former trivial name for* tetradecanoyl (**myristoyl** now used).

myrosinase *an alternative name for* **thioglucosidase**.

MySQL *see* **relational database management system**.

myt5 the gene for bacteriophage T5 5′-exodeoxynuclease (EC 3.1.11.3). It performs exonucleolytic cleavage in the 5′ to 3′ direction to yield 5′-phosphomononucleotides. *See also* **deoxyribonuclease**.

myxamoeba *or (esp. US)* **myxameba** a free-living haploid amoeboid cell occurring in the life cycles of the cellular slime moulds and the myxomycetes. In the former they aggregate to form a slug and in the latter a plasmodium.

myxedema *or (esp. Brit.)* **myxoedema** the syndrome caused by hypothyroidism in adults. It is characterized by mucoid infiltration and coarsening of the skin, weight gain, intolerance to cold, and mental sluggishness.

myxo+ *or (usually before a vowel)* **myx+** *comb. form* indicating mucoid, mucus, or slime.

Myxobacterales the myxobacteria; an order of Gram-negative bacteria that bear extracellular slime and have a characteristic swarming habit that leads to the formation of stalked fruiting bodies. A more recent classification has suggested replacement of Myxobacterales by Myxococcales.

myxobacteria bacteria belonging to the order **Myxobacterales**.

myxoedema *a variant spelling (esp. Brit.) of* **myxedema**.

myxomatosis a highly contagious disease of rabbits, caused by a myxoma virus, part of a subgenus of poxvirus. It is characterized by proliferative changes in the connective tissues.

Myxomycetes a large class of very primitive organisms, also known as the true or acellular slime moulds, found living saprophytically in damp conditions. Their major vegetative stage is a multinucleate migratory mass of protoplasm, from which (usually macroscopic) fruiting bodies arise.

myxothiazol an inhibitor of complex III of the mitochondrial electron transport chain, used as an antifungal agent.

myxovirus any of a group of negative-strand RNA animal viruses, now divided into **orthomyxoviruses** and **paramyxoviruses**.

Nn

n *symbol for* **1** nano+ (SI prefix denoting 10^{-9} times). **2** neutron; may be written as n^0 to indicate its charge.

n *symbol for* **1** any (unknown or unspecified) number, especially an integer. **2** amount of substance; the substance in question may be indicated as a suffix in parentheses or by a subscript. **3** refractive index (of a nonabsorbing material); n_D*symbol for* refractive index measured with light of the sodium D-lines (589.0 and 589.5 nm). **4** order of reaction. **5** order of reflection. **6** haploid number of chromosomes. **7** number density.

n- *prefix* indicating normal (isomer); no longer used.

n_H *symbol for* Hill coefficient (alternative to *h*).

N *symbol for* **1** nitrogen. **2** newton. **3** a residue of the α-amino acid L-asparagine (alternative to Asn). **4** a residue of an incompletely specified base in a nucleic-acid sequence that may be adenine, cytosine, guanine, or either thymine (in DNA) or uracil (in RNA). **5** an undetermined, unidentified, or unspecified nucleoside residue (alternative to Nuc). **6** (when suffixed to the symbol for a sugar molecule or residue) aminodeoxy+; e.g. GlcN is the symbol for 2-amino-2-deoxy-D-glucose (i.e. D-glucosamine). **7** normal (def. 1).

N *symbol for* **1** the SI derived physical quantity named number of entities (e.g. molecules, atoms, ions, formula units). **2** neutron number. **3** Avogadro constant (N_A or *L* now recommended). **4** the total number of receptors per unit area of membrane, per cell, or per unit mass of protein.

N- *prefix (in chemical nomenclature)* indicating substitution on nitrogen; a particular nitrogen atom may be specified by a right superscript.

N_A *symbol for* Avogadro constant (alternative to *L*).

N_L *symbol for* Loschmidt constant.

Na *symbol for* sodium.

NA *abbr. for* **1** nicotinic acid. **2** noradrenaline (i.e. **norepinephrine**). **3** nucleic acid. **4** numerical aperture.

NAA *abbr. for N*-**acetylaspartate**.

NAADP *abbr. for* nicotinic acid adenine dinucleotide phosphate; the form of NADP in which the nicotinamide moiety has been exchanged for nicotinic acid in a reaction catalysed by ADP-ribosylcyclase. In sea urchin eggs, plant cells, and some mammalian tissues – e.g. brain (especially medulla, thalamus, and midbrain), pancreatic acini, and heart – it mobilizes intracellular Ca^{2+} stores via receptors that are distinct from, but which interact with, those for inositol trisphosphate and for ryanodine/cyclic ADP-ribose. It is rapidly degraded within the aforementioned cells.

NAc *symbol for* (when suffixed to the symbol for a sugar molecule or residue) an acetylated **aminodeoxy sugar**; e.g. GlcNAc is the symbol for *N*-acetylglucosamine or 2-acetamido-2-deoxy-D-glucose.

NAC *abbr. for* nascent chain-associated complex; a dimer of α (33 kDa) and β (22 kDa) subunits that associates with nascent polypeptide chains and their ribosomes, and dissociates from both after chain release from the ribosome. It is present in eukaryotic cytosol and lacks peptidylprolyl isomerase activity. *See* **trigger factor**.

nactin any of a group of **macrotetrolide** antibiotics produced by various strains of *Actinomyces*. The group includes **nonactin**, monactin, dinactin, and trinactin.

NAD *abbr. for* nicotinamide-adenine dinucleotide (when its oxidation state is unknown or unspecified). Besides being a coenzyme, NAD is a precursor of NADP, of mono- and poly-ADP-ribosylation of some proteins, and of cADP-ribose. *See also* **NAD$^+$**, **NADH**, **NADP**, **NAD(P)**.

NAD$^+$ *abbr. for* oxidized nicotinamide-adenine dinucleotide. The positive charge refers to the nicotinamide ring; the overall charge is negative, owing to the two phosphate groups, which are negatively charged at neutral pH.

NAD$^+$ ADP-ribosyltransferase *see* **poly(ADP)-ribosyl transferase**.

NADH *abbr. for* nicotinamide-adenine dinucleotide (reduced). The corresponding oxidized state is NAD$^+$.

NADH$_2$ *alternative name for* nicotinamide-adenine dinucleotide (reduced), the oxidized form being NAD. NADH is preferred except in cases where the use of the charge on NAD$^+$ would be misleading.

NADH dehydrogenase EC 1.6.99.3; *systematic name*: NADH:(acceptor) oxidoreductase; *other names*: cytochrome *c* reductase; type I dehydrogenase. An enzyme, associated with a respiratory chain, that catalyses a reaction between NADH and an acceptor to form NAD$^+$ and a reduced acceptor; FMN or, in plant mitochondrin, FAD,is a prosthetic group.

NADH dehydrogenase (ubiquinone) EC 1.6.5.3; *other names*: ubiquinone reductase; type I dehydrogenase; complex I dehydrogenase; a flavoprotein enzyme that catalyses the reaction:

$$\text{NADH + ubiquinone = NAD}^+ \text{ + ubiquinol.}$$

The flavin is FMN, and the complex also contains at least nine iron–sulfur proteins. This is the catalytic activity of mitochondrial **complex I**.

NADH kinase EC 2.7.1.86; an enzyme that catalyses the formation of NADPH from ATP and NADH with release of ADP.

Nadi reagent a mixture of 1-naphthol and *N*,*N*-dimethyl-*p*-phenylene diamine that can be oxidized by cytochrome oxidase to form indophenol blue.

NAD$^+$ kinase EC 2.7.1.23; an enzyme that catalyses the formation of NADP$^+$ from ATP and NAD$^+$ with release of ADP.

NADP *abbr. for* nicotinamide-adenine dinucleotide phosphate (when its oxidation state is unknown or unspecified). Besides being a coenzyme, NADP is a precursor of NADP. *See also* **NAD**, **NADP$^+$**, **NAD(P)**, **NADPH**.

NADP$^+$ *abbr. for* oxidized nicotinamide-adenine dinucleotide. The positive charge refers to the nicotinamide ring; the overall charge is negtive, owing to the two phosphate groups, which are negatively charged at neutral pH.

NAD(P) *abbr. for* a coenzyme that may be NAD or NADP.

NAD(P)$^+$ *abbr. for* a coenzyme that may be NAD$^+$ or NADP$^+$.

NAD(P)$^+$–arginine ADP-ribosyltransferase EC 2.4.2.31; *other names*: ADP-ribosyltransferase; mono(ADP-ribosyl) transferase; a sarcoplasmic reticulum enzyme that catalyses the formation of N^2-(ADP-D-ribosyl)-L-arginine from NAD$^+$ and L-arginine with release of nicotinamide. It couples poly(ADP-ribose) to arginine residues in proteins.

NADPH *abbr. for* nicotinamide-adenine dinucleotide phosphate (reduced). The corresponding oxidized state is NADP$^+$.

NADPH$_2$ *alternative name for* nicotinamide-adenine dinucleotide phosphate (reduced), the oxidized form being NADP. NADPH is preferred except in cases where the use of the charge on NADP$^+$ would be misleading.

NAD(P)H *abbr. for* a coenzyme that may be either NADH or NADPH. Use of NAD(P)H_2 to represent NAD(P)H is not recommended.

NADPH:adrenodoxin oxidoreductase EC 1.18.1.2; *other names*: adrenodoxin reductase; *recommended name*: ferredoxin-NADP$^+$ reductase; a flavoprotein enzyme that catalyses the reaction:

$$\begin{array}{l}\text{reduced ferredoxin + NADP}^+ = \\ \text{oxidized ferredoxin + NADPH.}\end{array}$$

The flavin is FAD.

NAD(P)$^+$ stereospecificity in oxidation–reduction reactions involving the nicotinamide coenzymes, NAD$^+$ and NADP$^+$ reversibly accept hydrogen at the 4 position of the nicotinamide ring. In NADH and NADPH this position is **prochiral**, and the faces of the nicotinamide ring and the c-4 hydrogens of the dihydronicotinamide ring may be labelled according to the *Re*/*Si* and *pro-R*/*pro-S* conventions, respectively. Then, if the ring is drawn with the –CONH$_2$ group pointing to the right, the hydrogen projecting out from the plane of the paper is the *pro-R* hydrogen (*or* H_R) and that projecting back the *pro-S* hydrogen (*or* H_S). Alcohol dehydrogenases (EC 1.1.1.1) transfer to the *Re* face (i.e. that from which H_R

points out) and use H_R . In biochemistry the *pro-R* hydrogen region is also labelled as H_A, and the *pro-S* hydrogen as H_B . Enzymes that use the *pro-R* hydrogen (H_A) are described as A-specific, while those that use the *pro-S* hydrogen (H_B) are called B-specific. *See also* **pro-*R*/pro-*S* convention**, ***Re*/*Si* convention**.

NAD(P)$^+$ transhydrogenase (AB-specific) EC 1.6.1.2; *other names*: pyridine nucleotide transhydrogenase; transhydrogenase. An enzyme that catalyses the same reaction as **NAD(P)$^+$ transhydrogenase (B-specific)**; however, preparations from heart mitochondria are A-specific with respect to NAD$^+$ and B-specific with respect to NADP$^+$. *See also* **NAD(P)$^+$ stereospecificity**.

NAD(P)$^+$ transhydrogenase (B-specific) EC 1.6.1.1; *other names*: pyridine nucleotide transhydrogenase; nicotinamide nucleotide transhydrogenase; a flavoprotein enzyme that catalyses the reaction

$$\text{NADPH} + \text{NAD}^+ = \text{NADP}^+ + \text{NADH}$$

(with specificity for H_B of NADPH and NADH). The flavin is FAD. The enzyme is coupled to respiration and acts as a **hydrogen-ion pump**. *See also* **NAD(P)$^+$ stereospecificity**.

NAD+ pyrophosphorylase *see* **nicotinamide-nucleotide adenylyltransferase**.

NAD$^+$ synthase EC 6.3.1.5; *other name*: NAD$^+$ synthetase; an enzyme that catalyses the formation of NAD$^+$ from deamido-NAD$^+$, ATP, and NH_3 with release of AMP and pyrophosphate. *See also* **NAD$^+$ synthase (glutamine-hydrolysing)**; **nicotinamide–nucleotide adenylyltransferase**.

NAD$^+$ synthase (glutamine-hydrolysing) EC 6.3.5.1; *other name*: NAD$^+$ synthetase (glutamine-hydrolysing); an enzyme that catalyses the formation of NAD$^+$ from deamido-NAD$^+$, L-glutamine, ATP, and H_2O with release of AMP, pyrophosphate, and L-glutamate. *See also* **nicotinamide– nucleotide adenylyltransferase**.

***Nae*I** a type 2 **restriction endonuclease** recognition sequence: GCC↑GGC.

NAF *abbr. for* Neu-activating factor (*see* **neu**).

NAG *abbr. for* **1** *N*-acetylglucosamine. **2** *(esp. in clinical chemstry) N*-acetylglucosaminidase; *see β-N*-**acetylhexosaminidase**.

NAGA *abbr. for N*-acetylgalactosamine.

Nagarse (proteinase) *another name for* a species variant of **subtilisin**, EC 3.4.21.62, from *Bacillus subtilis*; an endopeptidase with a broad spectrum of proteolytic activity.

Nagase *a pseudoacronym for β-N*-acetylglucosaminidase (formerly EC 3.2.1.30). This enzyme is now included with EC 3.2.1.52, *β-N*-acetyl-hexosaminidase.

NAIBS *abbr. for* nonadrenergic imidazoline binding site; *see* **imidazoline receptors**.

Na$^+$/I$^-$ symporter (*abbr*.: NIS) *an alternative name for* **iodide pump**.

Naka *an alternative name for* **CD36**.

Na$^+$,K$^+$-ATPase *see* **sodium/potassium ATPase**.

nalidixic acid 1-ethyl-7-methyl-1,8-naphthyridin-4-one-3-carboxylic acid; a synthetic **4-quinolone antibiotic** that is active against many Gram-negative bacteria. It specifically inhibits bacterial DNA gyrase thereby interfering with DNA synthesis. It has no apparent effect on eukaryotic DNA synthesis.



naloxone 1-*N*-allyl-7,8-dihydro-14-hydroxynormorphinone; one of the most effective opiate antagonists. It binds tightly to opiate receptors in the nervous system, its action depending on the 3-carbon side-chain substitution on the nitrogen. It is used as an antidote to overdosage of narcotics.



naloxone

naltrexone 1-*N*-cyclopropylmethyl-7,8-dihydro-14-hydroxynormorphinone; the cyclopropylmethyl analogue of **naloxone**; it has similar properties but is longer acting.



NANA *abbr. for N*-acetylneuraminic acid (i.e. **sialic acid**).

nano+ *symbol*: n; SI prefix denoting 10^{-9} times. It was formerly known as millimicro (*symbol*: mμ).

nanogram *symbol*: ng; a unit of mass equal to 10^{-9} gram, or 10^{-12} kilogram.

nanometre *or (US)* **nanometer** *symbol*: nm; a unit of length equal to 10^{-9} metre. It was formerly known as millimicron (*symbol*: mμ).

nanomolar *symbol*: nm *or* nM; describing a solution containing one **nanomole** per litre of solution, or a specified multiple or fraction thereof; describing an amount-of-substance concentration similarly expressed.

nanomole *symbol*: nmol; a unit of amount of substance equal to 10^{-9} mole.

Nanos an RNA-binding protein of *Drosophila* that, with **Pumilio**, keeps mRNA for Hunchback and cyclin B translationally repressed in the posterior thoracic region of the early syncytial embryo.

nanosecond *symbol*: ns; a unit of time equal to 10^{-9} second.

nanotechnology the creation and control of objects on nanometre scales. –**nanotechnological** *adj*. –**nanotechnologist** *n*.

NAP1 *abbr. for* nuclear assembly protein 1; a protein (≈12.5 kDa), widely distributed among eukaryotes, that is responsible for chaperoning histones H2A and H2B to DNA during DNA replication. *See also* **CAF1**.

NAP-2 *abbr. for* neutrophil activating peptide 2; one of several peptides derived from **platelet basic protein precursor**. It consists of **LA-PF4** without the first 15 N-terminal amino acids. It is a potent chemoattractant and activator for neutrophils.

NAP cell adhesion a cell adhesion system comprising nectin, afadin, ponsin, and possibly other proteins. It occurs in **adherens junctions** and **tight junctions**.

Naphthalene Black *or* **Naphthol Blue Black** *or* **Amido Black** a dye used for staining protein on cellulose acetate or on starch or agarose gels.



Naphthol Blue Black *an alternative name for* **Naphthalene Black**.

Napierian logarithm *symbol*: $\log_e$ *or* ln; *an alternative name for* natural **logarithm**. [After John Napier (1550–1617), Scots mathematician who invented logarithms.]

narcosis a state of partial or complete loss of consciousness induced by a drug or drugs that have a depressant action on the central nervous system.

narcotic **1** any of a heterogeneous group of drugs that is capable of inducing narcosis and noted for their analgesic action. **2** *(esp. US) the trivial name for* any illegal drug or abused drug. **3** of, or relating to, narcosis; of, relating to, or denoting a narcotic drug.

naringenin 4′,5,7-trihydroxyflavanone; the aglycon of **naringin**, and an inducer of *nod* genes in some *Rhizobium* species.



S-(–)-enantiomer

naringin naringenin-7-rhamnoglucoside; a compound that occurs in the flowers, fruit, and rind of the grapefruit, and is the main bitter component of grapefruit juice. *See also* **naringenin**.



NARP *abbr. for* neuropathy, ataxia, and retinitis pigmentosa; a mitochondrial disease that includes developmental delay, retinitis pigmentosa, ataxia, and other neurological symptoms. It is associated with two point mutations in the mitochondrial gene for a subunit of F_0F_1 ATPase.

NAS *abbr. for* **nonsense-mediated alternative splicing**.

nascent just formed or in the process of being formed, especially in a chemical or biochemical reaction.

nascent chain-associated complex *see* **NAC**.

native *(of a biopolymer)* undenatured, i.e. having the structure and biological activity possessed in living material.

native state of a protein or nucleic acid, the form in which it occurs in the intact cell, its three-dimensional structure depending on formation of the appropriate hydrogen bonds.

natriuresis the excretion of sodium ions in the urine.

natriuretic **1** describing any agent that promotes the excretion of sodium ions in the urine. **2** such an agent.

natriuretic hormone any peptide present in plasma or urine that is capable of stimulating sodium excretion by the kidney and of inhibiting membrane Na^+,K^+-ATPase in cells from kidney and some other tissues. *See* **natriuretic peptide**.

natriuretic peptide any of several peptides, secreted by various tissues, that stimulate natriuresis. The first of the group to be identified was **atrial natriuretic peptide** (*or* atrial natriuretic factor) (*abbr.*: ANP; *other name*: type A natriuretic peptide; *former names*: atriopeptin; vasoactive peptide). Its discovery arose from the observation that extracts of atrial granules could bring about **natriuresis**. Subsequently, **brain natriuretic peptide** (*abbr.*: BNP; *other name*: type B natriuretic peptide) and **type C natriuretic peptide** (CNP) were identified. Members of this family share many common features; they are produced primarily in the heart and specialized areas of the central nervous system, and induce diuresis, natriuresis, and vasorelaxation. The natriuretic effect results from direct inhibition of sodium absorption in the collecting duct, increased glomerular filtration, and inhibition of aldosterone production and secretion. The major constituent of atrial granules, ANP, is synthesized from a precursor, prepronatriodilatin (152 amino acids), which is cleaved to proANP (126 amino acids). The latter is strikingly similar between many species; proANP is cleaved into an N-terminal fragment, amino-acid residues 1–98, and the biologically active hormone, residues 99–126; the amino-acid sequence of ANP (proANP 99–126) is identical in all mammalian species, except at residue 12 (110 of proANP), which is methionine in humans, dogs, and cows, but isoleucine in rats, mice, and rabbits. There are two genes for the precursor (prepronatriodilatin); cleavage of the latter leads to two peptides, ANP:

SLRRSSCFGGRMDRIGAQSGLGCNSFRY

and cardiodilatin-related peptide (CDP):

NPMYNAVSNADLMDFKNLLDHLEEKMPLED.

The synthesis of BNP follows a similar course. In humans and pig, a 32-amino-acid hormone is the circulating form of BNP, sequence (human)

SPKMVQGSGCFGRKMDRISSSSGLGCKVLRRH;

in rodents BNP contains 45 amino acids and is known as iso-ANP. A 17-member ring, formed by a disulfide bridge between the two cysteine residues, is essential for biological activity of ANP and BNP. *See also* **natriuretic-peptide receptor**.

natriuretic-peptide receptor any type 1 membrane glycoprotein that binds **natriuretic peptides** and mediates their intracellular effects. Three receptors have been identified: ANP_A (previously known as GC-A, ANP-R_1, or ANP_B); ANP_B (previously known as GC-B); and ANP_C. Human ANP_A and ANP_B each have one transmembrane domain and intrinsic guanylate cyclase activity in an intracellular domain, which is highly conserved (88% identity). At the ANP_A receptor, atrial natriuretic peptide is about ten times more potent than brain natriuretic peptide, whereas type C natriuretic peptide is 50–500 times more potent than other agonists at the ANP_B receptor. ANP_C is a disulfide-linked homodimer with one transmembrane domain and no guanylate cyclase domain; it acts through other second messenger systems.

natural abundance the number of atoms of a given nuclide in any naturally occurring mixture of the nuclides of a particular element, expressed as a percentage or fraction of the total number.

natural killer cell *see* **NK cell**.

natural language processing *abbr.*: NLP; the computational analysis and interpretation of human language. NLP is used in software that provides automatic translations of text from one language to another, in robotic systems that use human-language-type commands, and in text-mining tools (e.g. to provide summaries or abstracts of large volumes of text).

natural logarithm *or* **Napierian logarithm** *symbol*: $\log_e$ *or* ln; *see* **logarithm**.

natural product any organic substance of biological origin, as opposed to one obtainable only by chemical synthesis. In practice the term is often restricted to mean **secondary metabolite**.

natural selection the principle that the best competitors in any given population of organisms have the best chance of breeding success and thus of transmitting their characteristics to subsequent generations. The members of any population show individual differences – anatomical, physiological, or metabolic – that affect their functional efficiency in a given environment. The less efficient members tend to die out or produce fewer offspring than the more efficient members, which are better adapted to compete for food or other resources, and so produce relatively more offspring. The principle is fundamental to modern concepts of evolution, and was first articulated, independently, by the British naturalists Alfred Russel Wallace (in 1858) and Charles Darwin (in 1859).

natural-selection theory of immunity *or* **Jerne's theory of immunity** a theory of antibody production that postulates the spontaneous presence, in the blood of an animal, of small numbers of antibody molecules against all antigens to which the animal can respond, and delegates to the antigen the sole role of carrying such specific globulin molecules from the bloodstream into cells in which these molecules can induce proliferation of a particular antibody.

Nb *symbol for* niobium.

NBPC *abbr. for* 1-[(*m*-nitrobenzyloxy)methyl]pyridinium chloride; a reagent useful for the immobilization of single-stranded nucleic acids on cellulose.



NBS *abbr. for* **1** National Bureau of Standards (of the USA) (now National Institute for Standards and Technology). **2** *N*-bromosuccinimide.

NCAM *abbr. for* neural cell adhesion molecule.

NCBI *abbr. for* National Center for Biotechnology Information; *see* **bioinformatics institute**.

NCE *abbr. for* novel chemical entity.

N cell a type of cell, found mainly in the upper small intestine in humans, that contains round, homogeneous granules in which **neurotensin** is stored. Such cells are sparse in the lower small intestine.

NC–IUB *abbr. for* Nomenclature Committee of the International Union of Biochemistry; redesignated (in 1992) **NC–IUBMB**.

NC–IUBMB *abbr. for* Nomenclature Committee of the International Union of Biochemistry and Molecular Biology. *Compare* **JCBN**.

***Nco*I** a type 2 **restriction endonuclease**; recognition sequence: C↑CATGG.

NCoR *abbr. for* nuclear hormone corepressor; a protein that, with **SMRT**, causes transcriptional repression by recruiting the histone deacetylase complex Sin 3-HDAC. The NCoR–SMRT dimer binds unliganded retinoic acid and thyroid hormone receptors.

ncRNA *abbr. for* noncoding RNA; strictly, any RNA that is not mRNA, but the term also commonly excludes tRNA and rRNA. The term is used predominantly in relation to eukaryotes, with sRNA (small RNA) being used in relation to prokaryotes. It encompasses many varieties of RNA that have specific, but noncoding, functions. Examples are: **miRNA** (micro RNA; 21–25 nt), which modulates development in many eukaryotes; sRNA (≈100–200 nt), which are translation regulators in bacteria; 7S RNA (300 nt) of the **signal recognition particle**; U-snRNA (100–215 nt), which are involved in **spliceosomes** in eukaryotes; and RNAs (>10 000 nt) that are involved in gene silencing in higher eukaryotes (*see* **Xist**).

NCS *the proprietary name for* a 0.6 m solution in toluene of a mixture of quaternary ammonium compounds of general formula $[(CH_3)_2R'R''N]^+OY^-$, where R' and R'' are unbranched alkyl groups containing 6 to 20 carbon atoms and Y is a hydrogen atom or a lower alkyl group. It is useful for solubilizing a wide range of specimens of biological origin in organic solvents for liquid scintillation counting.

Nd *symbol for* neodymium.

***Nde*I** a type 2 **restriction endonuclease**; recognition sequence: CA↑TATG.

nDNA *abbr. for* nuclear DNA.

NDP *abbr. for* any (unknown or unspecified) nucleoside diphosphate in which the diphosphate moiety is esterified at the 5′ position of the glycose.

Ne *symbol for* neon.

NE *abbr. for* norepinephrine.

nearest-neighbour sequence analysis a technique that employs a 5′-^{32}P-labelled deoxyribonucleotide substrate in the enzymic synthesis of DNA followed by enzymic degradation of the DNA specifically to 3′-deoxyribonucleotides. From knowledge of the labelled substrate used and of the labelled degradation products formed, the **nearest neighbour frequency**, i.e. the frequency with which a particular nucleotide is found next to a specific neighbour nucleotide in the polynucleotide chain, can be calculated.

near ultraviolet radiation **ultraviolet radiation** in the wavelength range 200–400 nm.

nebulette a 107 kDa filamentous protein specific for cardiac muscle. The C-terminal 30 kDa region is integrated in the Z disc, and is highly homologous with that of nebulin. Defects in nebulette can cause cardiomyopathy.

nebulin a giant protein (800 kDa) that is specific for the skeletal muscle of vertebrates; it acts possibly as a 'molecular ruler' for length regulation of the thin filament. The protein appears to have small repeats of approximately 35 amino acids.

nebulize *or* **nebulise** to convert a liquid into a mist or a spray of fine droplets. —**nebulization** *or* **nebulisation** *n.*

nebulizer *or* **nebuliser** a device for nebulizing a liquid (*see* **nebulize**); an atomizer.

necrobiosis the death of a cell or a group of cells within a tissue, whether a normal occurrence or due to a pathological process.

necropsy *another name for* **autopsy**.

necrosis the death of a portion of a tissue as a result of disease or injury. The cells swell, their plasma membranes become disrupted, and the cell contents are released into the extracellular space, where they often trigger an inflammatory response. The process is unregulated and should be distinguished from **apoptosis**.

necrotizing encephalopathy *an alternative name for* **Leigh syndrome**.

nectary a gland that secretes the sugary fluid called nectar. Nectaries occur in many animal-pollinated flowers, to attract insects, birds, and other pollinating agents.

nectin-1 a transmembrane cell-cell adhesion molecule forming part of the **NAP cell adhesion** system in adherens and tight junctions. The nectin-1 gene is mutated in cases of **cleft lip/palate**-ectodermal dysplasia syndrome. It is the main cell surface receptor for alpha-herpes viruses.

Nedd *abbr. for* NPC-expressed, developmentally down-regulated genes (NPC is an abbreviation of neural precursor cells). These genes are down-regulated during mouse brain development. The products are proteins presumed to be involved in embryonic development and differentiation of the nervous system. Nedd-2 protein is a cysteine endopeptidase that may be involved in controlling cell death. Nedd-4 is ubiquitously expressed in mammals. It contains multiple WW domains, which bind with great affinity to the β and γ subunits of epithelial Na channel (ENaC), and a ubiquitin-ligase domain. Nedd-8 (called Rub 1 in yeast) is a ubiquitin-like molecule in mammals that becomes conjugated with cullin 1 and promotes its degradation in proteasomes.

neddylation the process whereby Nedd-8 (or Rub 1 of yeast), a ubiquitin-like protein conjugate to some proteins to target them for degradation by proteasomes or for deneddylation by COP signalosomes. It is important in controlling the auxin response pathway in plants.

Needleman–Wunsch alignment algorithm a dynamic programming algorithm used in sequence alignment that employs a 2D search matrix, such that its speed and storage requirements are of the order $N \times M$ when sequences of length N and M are aligned. The algorithm has large memory requirements owing to its traceback step, where the matches of the optimal alignment are reconstructed, making it too slow for routine database searches. *See* **alignment algorithm**. *See also* **Smith–Waterman alignment algorithm**.

NEFA *abbr. for* nonesterified fatty acid. *Compare* **FFA**.

negative **1** (of an electric charge) having the same polarity as an electron. **2** (of a chemical entity) having a negative electric charge; having an excess of electrons. **3** (of a point in an electric circuit) having a lower potential than some other point to which a potential of zero is assigned. **4** *(in photography)* an exposed and developed photographic film or plate showing an image in reversed tones, or complementary colours, to those of the object photographed. **5** a quantity less than zero. —**negativeness** *or* **negativity** *n.*

negative chromatography *a term sometimes used to denote* methods of purification of substances by **affinity chromatography** in which a specific contaminant in a sample interacts with and is selectively retained by the adsorbent, especially as opposed to **positive chromatography**.

negative-contrast technique a technique used in preparing specimens for electron microscopic examination in which the specimen is mixed with an electron-dense material that penetrates the interstices of the specimen but not the material of the specimen itself. The specimen thus appears transparent against an opaque background. It is commonly called **negative staining**.

negative control the prevention of some biological activity caused by the presence of a specific chemical entity.

negative cooperativity a form of **cooperative ligand binding** in which binding of one ligand to one site on a (macro)molecule decreases the affinity at other sites for the subsequent binding of other ligands.

negative effector *see* **effector**.

negative elongation factor *see* **NELF**.

negative feedback *see* **feedback** (def. 1).

negative-ion mass spectrometry a version of **mass spectrometry** in which negative rather than positive ions, generated from the sample by chemical ionization, are separated and measured in an appropriate instrument.

negative staining *see* **negative-contrast technique**.

negative strand *another name for* **minus strand** (def. 2); in some RNA viruses, RNA is a minus strand which does not directly code for protein. Such viruses have a replicase packaged into the capsid to enable them to synthesize the plus strands necessary for replication.

negative-strand virus *or* **negative-stranded virus** any RNA virus in which the genome consists of single-stranded RNA (i.e. minus strand) of base sequence complementary to that of the virus-specified mRNA (which is the positive, or plus, strand). Such viruses, which comprise class V in the **Baltimore classification**, must make a positive RNA strand before making viral proteins. *See also* **minus strand** (def. 2), **plus strand** (def. 2).

neighbour-joining a method for inferring phylogenetic trees based on the principle of **minimum evolution**. The method resolves the phylogeny in a stepwise fashion by selectively joining pairs of taxa that minimize the sum of branch lengths. Neighbour joining is computationally efficient and is an appropriate reconstruction approach where evolution has not proceeded in a strictly clocklike manner.

NELF *abbr. for* negative elongation factor; a protein complex that inhibits transcriptional elongation by binding to RNA polymerase. It consists of five subunits (NELF-A to NELF-E). NELF-A (66 kDa, 528 amino acids) and shares 21% sequence identity with hepatitis delta antigen (HDAg-S). NELF-E (46 kDa) is identical with a putative RNA-binding protein.

NEM *abbr. for* **1** *N*-ethylmaleimide. **2** nemaline myopathy.

nemaline myopathy *abbr*.: NEM; a slowly progressing myopathy characterized by rodlike structures, composed largely of α-actinin and actin, in skeletal muscle fibres. Nem1 (gene locus at 1q22-q23) is an autosomal dominant disease and is associated with a missense mutation in α-tropomyosin. NEM2 (gene locus at 2q22) is an autosomal recessive disease whose gene locus is that for nebulin.

nematic (of a substance) being in or having a mesophilic state in which the molecules are arranged as in a series of parallel threads but not in layers. The molecules can rotate about their axes and can move in the plane orthogonal to the line of the thread. *Compare* **smectic**. *See also* **liquid crystal**.

Nembutal *a proprietary name for* pentobarbitone sodium; pentobarbital sodium.

NEMO *abbr. for* nuclear factor κB essential modulator; a 48 kDa zinc finger protein that is the regulatory subunit of the IκB kinase complex, which is essential for NF-κB signalling.

N-end rule a rule stating that the *in vivo* half-life of a protein is a function of its N-terminal residues.

neo *abbr. for* neomycin.

neo+ *comb. form* **1** denoting new, recent. **2** *(in chemistry)* denoting an isomer of new (and therefore initially unknown) structure.

neo^R *abbr.for* neomycin resistance.

neo-Darwinism the reworking of evolutionary theory in the light of discoveries about genetics as a result of the work of Fisher, Haldane, Sewall Wright, and others. The behaviour of genes in natural populations is understood in terms of the four fundamental evolutionary forces: **natural selection**, **genetic drift**, gene flow, and **mutations**.

neoendorphin any of a small group of [Leu^5]enkephalin-related peptides. α Neoendorphin is the decapeptide [Leu^5]enkephalinyl-Arg-Lys-Tyr-Pro-Lys, and β neoendorphin is the nonapeptide [Leu^5]enkephalinyl-Arg-Lys-Tyr-Pro; both are hypothalamic opioid peptides. *See also* **proenkephalin**.

neoflavone any of a group of 4-phenyl-1,2-benzopyrones found in certain plants. Their occurrence is probably restricted to the Guttiferae and Leguminosae. **—neoflavonoid** *n.*

neoglycoprotein *a generic name for* any originally carbohydrate-free protein that has been chemically derivatized by covalent attachment of carbohydrate.

neokestose *O*-*β*-D-fructofuranosyl-(2→6)-*α*-D-glucopyranosyl-*β*-D-fructofuranoside; an isomer of **kestose** isolated from the sap of the sugar maple and produced artificially, together with kestose, by the action of yeast or mould invertase preparations on sucrose.

neolignan any of a class of phenylpropanoid dimers in which the phenylpropane units are linked head-to-tail instead of tail-to-tail as in **lignans**; e.g. eusiderin from the heartwood of members of the Magnoliaceae.

neomycin an aminocyclitol antibiotic complex produced by *Streptomyces fradiae*. It consists of: neomycin A (*or* **neamine**; a degradation product of neomycin B and neomycin C), neomycin B, and neomycin C. Neomycin causes misreading during protein synthesis in bacteria but its target site on the ribosome is apparently different from that of streptomycin. **Neomycin resistance** is conferred by the enzyme aminoglycoside 3′-phosphotransferase. *See also* **neosamine C**.

neonatal of, relating to, or affecting a newborn animal. For human infants the neonatal period is considered to be the first month after birth.

neonatal jaundice a physiological predominantly unconjugated hyperbilirubinemia with clinical jaundice, affecting about half of all human neonates during the first five days of life. It results from increased bilirubin production and delayed maturation of liver **UDP-glucuronosyltransferase** activity. Maternal–fetal Rh blood group incompatibility and hereditary hyperbilirubinemia syndromes exaggerate the condition, which, if untreated, can lead to kernicterus and brain damage.

neonate any newborn animal.

neoplasia **1** the formation of a **neoplasm** or neoplasms. **2** the formation of new tissue.

neoplasm any new and morbid formation of tissue; a tumour.

neoplastic of, or relating to, neoplasia or to a neoplasm.

neoprene poly(2-chloro-1,3-butadiene); a synthetic rubber that is resistant to oils and organic solvents and is useful for the manufacture of flexible tubing, washers, etc. for laboratory and many other uses.

neopterin the D-*erythro* enantiomer of **biopterin**; its biosynthetic precursor.



neosamine C 2,6-diamino-2,6-dideoxy-D-glucose; a constituent of **neomycin** C and some other antibiotics including **kanamycin**.

neosome the suggested secondary particulate biogenic precursor of the ribosome, intermediate between the **eosome** and the completed ribosome. Neosomes in *Escherichia coli* are particles with sedimentation coefficients of 43S and 30S.

neotenin *an alternative name for* **juvenile hormone**.

neoxanthin a carotenoid **xanthophyll** present in the leaves of all higher plants.



neoxanthine

nephelometry a technique in which the light dispersed by a suspension is measured orthogonally to the direction of the incident light; the amount of scattered light is dependent on the number and size of the particles in the light path. *Compare* **turbidimetry**. —**nephelometric** *adj.*; **nephelometrically** *adv.*

nephr+ *a variant form of* **nephro+** *(before a vowel)*.

nephrectomy the surgical removal of one or both kidneys. —**nephrectomize** *vb.*

nephro+ *or (before a vowel)* **nephr+** *comb. form* denoting kidney or kidneys.

nephrocalcin *or* **osteocalcin-related protein precursor** a calcium-binding protein found in bone. It is expressed only in kidney; in humans and other mammals, it is also found as a urinary acidic glycoprotein that strongly inhibits formation of calcium oxalate crystals in renal tubules. It contains γ-carboxyglutamic acid residues; a modified protein lacking these is found in patients with calcium oxalate renal calculi.

nephrogenic diabetes insipidus a rare X-linked recessive genetic disorder involving renal insensitivity to vasopressin resulting in polyuria and polydipsia; it can also be acquired as a result of toxic damage to the tubules. The genetic form is associated with mutations in the V_2 receptor (*see* **vasopressin receptor**), two examples being substitution of Asp for Ala at position 132 and a frameshift mutation at position 246 leading to a premature stop codon and a truncated receptor.

nephron any of the structural and functional urine-secreting units that occur in the kidney. Typically each nephron is made up of a glomerulus, a proximal convoluted tubule, a loop of Henle, and a distal convoluted tubule.

nephropontin *see* **osteopontin**.

neplanocin A a cyclopentenyl analogue of adenosine; a natural antibiotic that inhibits *S*-adenosylhomocysteine hydrolase and vaccinia virus multiplication.



neprilysin EC 3.4.24.11; *other names*: neutral endopeptidase; endopeptidase 24.11; enkephalinase; a member of the zinc metalloendopeptidase family. It is an integral plasma membrane enzyme and is involved in the metabolism of a number of regulatory peptides including enkephalins, tachykinins, and natriuretic and chemotactic peptides.

Ner *symbol for* the nervonoyl (i.e. (*Z*)-tetracos-15-enoyl) group.

NER *abbr. for* nucleotide excision repair.

Nernst distribution law when, at a constant temperature, a solute distributes itself between two immiscible phases, then the ratio of its concentrations in the two phases is constant, and is described by the relation $C_1/C_2 = K$, where C_1 and C_2 are, respectively, the amount-of-substance concentrations of the solute in phases 1 and 2 at equilibrium, and K is the distribution constant. The law only applies in dilute solution. [After Walther Hermann Nernst (1864–1941), German physical chemist.]

Nernst equation **a** the potential, E, of an electrode reversible to one ion in a solution containing that ion is given by:

$$E = E^{\ominus} + (RT/zF)\ln a,$$

where $E^{\ominus}$ is the standard potential of the electrode (relative to the standard hydrogen electrode), a is the activity of the ion to which the electrode is reversible, z is the charge number of the ion, R is the (molar) gas constant, F is the Faraday constant, and T is the thermodynamic temperature. This equation can be extended to the e.m.f. of an electrolytic cell. **b** For a redox reaction, the potential of an electrode (usually platinum or gold) immersed in a redox solution, E_h, is given by:

$$E_h = E^{\ominus} + (RT/nF)\ln(a_{ox}/a_{red}),$$

where $E^{\ominus}$ is the standard redox potential of the system at a given pH (usually pH 7.0), n is the number of electrons transferred in the reaction, and a_{ox} and a_{red} are respectively the activities of the oxidized and reduced species in the solution. **c** If two solutions are separated by a membrane permeable to only one of two (or more) ions and the activities of the ions are different on either side of the membrane then a membrane potential, E_A, will be generated where

$$E_A = (RT/zF)\ln(a_L/a_R),$$

where a_L and a_R are the activities respectively of the permeable ion on the left and right sides of the membrane.

Nernst heat theorem *another name for* a particular formulation of the third law of thermodynamics (*see* **thermodynamics**).

nerolidol peruviol; 3,7,11-trimethyl-1,6,10-dodecatrien-3-ol; a widespread acyclic sesquiterpene.



(*S*)-(+)-(*Z*)-enantiomer

nerve any of the cordlike bundles, consisting of **nerve fibres** and **glia** encased in a connective-tissue sheath, that connect the central nervous system to other parts of the body. They may be motor, sensory, or of mixed function.

nerve cell *an alternative name for* **neuron**.

nerve fibre the axonal process of a **neuron** together with its covering sheath. Bundles of nerve fibres running together make up a **nerve**.

nerve gas any of various poisonous gases or volatile liquids that act by inhibiting the passage of impulses through the nervous system and neuromuscular junctions. They are commonly irreversible inhibitors of **acetylcholinesterase**.

nerve growth factor **1** any of a number of polypeptides that exert a trophic effect on neurons. They play a part in the development and maintenance of sensory neurons in dorsal root ganglia and sympathetic neurons in peripheral sympathetic ganglia. **2** *abbr.*: NGF; the first known member of a family of polypeptides that act as growth factors for neurons. In addition to the general properties of such nerve growth factors, it also stimulates growth and differentiation of B lymphocytes, and stimulates histamine release from mast cells. The biologically active form of NGF contains two identical polypeptide chains of 120 amino-acid residues and known sequence and exerts its action through specific receptors in the neuronal plasma membrane. It is produced by neurons, astrocytes, and Schwann cells, but also by fibroblasts, epithelial cells, activated macrophages, and smooth muscle cells. It exists as an inactive complex of two α subunits, two β subunits, and two γ subunits. The active form consists of the two β subunits, and is known as βNGF. Related proteins subsequently discovered include **brain-derived neurotrophic factor** and **neurotrophins**.

nerve growth factor receptor any of a family of plasma membrane integral proteins that bind nerve growth factors. Low-affinity and high-affinity binding is observed; high affinity binding, and action on effector systems, requires the presence of both the ***trk*** protooncogene product ($p140^{\mathrm{prototrk}}$) and a 75 kDa low-affinity receptor glycoprotein ($p75^{\mathrm{NGFR}}$). The latter can bind **nerve growth factor** (def. 2), **brain-derived neurotrophic factor**, and **neurotrophins** 3 and 4, but it is apparent that considerable specificity exists in transduction of the signal depending on which member of the nerve growth factor family and which cell type is involved.

nerve impulse *see* **impulse** (def. 3).

nervon *or* **nervone** the **galactocerebroside** in which the acyl group is **nervonoyl**. It was originally isolated from nervous tissue.

nervonate **1** *numerical symbol*: 24:1 (15); *the trivial name for* (*Z*)-tetracos-15-enoate, $CH_3–[CH_2]_7–CH=CH–[CH_2]_{13}–COO^–$ (*cis* isomer), the anion derived from nervonic acid, (*Z*)-tetracos-15-enoic acid a monounsaturated straight-chain higher fatty acid. **2** any mixture of free nervonic acid and its anion. **3** any salt or ester of nervonic acid. *See also* **nervonoyl**.

nervonoyl *symbol*: Ner; *the trivial name for* (*Z*)-tetracos-15-enoyl, $CH_3–[CH_2]_7–CH=CH–[CH_2]_{13}–CO–$ (*cis* isomer), the acyl group derived from nervonic acid, (*Z*)-tetracos-15-enoic acid. It occurs as the acyl moiety of the cerebroside **nervon** in brain, as a major constituent of milk phosphatidylcholines and sphingolipids in, e.g., pig and human, and in sphingolipids of other tissues.

nervous of, pertaining to, mediated by, or containing nerves; neural.

nervous system the extensive network of cells specialized to carry information, in the form of nerve impulses, to and from all parts of the body. Nervous systems occur in all orders of multicellular animals other than sponges.

nervous tissue tissue from any part of the nervous system.

nesidioblast a precursor cell of a pancreatic islet cell.

nesidioblastoma a tumour of nesidioblasts.

nesidioblastosis a pathological condition in which individual blastic pancreatic duct cells differentiate abnormally into islet cells scattered among the exocrine tissue. The condition is sometimes associated with severe infantile hyperinsulinism and hypoglycemia.

nesslerize *or* **Nesslerize** to treat (a sample) with **Nessler's reagent**; to test for or estimate (ammonia) by such means. *Also*: **nesslerise, Nesslerise**. **—nesslerization** *or* **nesslerisation** *n.*

Nessler's reagent an alkaline aqueous solution of potassium tetraiodomercurate(ii). It gives a yellow or brown colour or precipitate when added to solutions containing ammonia or ammonium ions and is useful in the detection and quantitative estimation of microgram quantities of ammonia in aqueous solution. [After Julius Nessler (1827–1905), German agricultural chemist.]

nested deletion the systematic truncation of a DNA molecule from one end to produce a series of fragments that have an identical sequence at one end and different sequences at the other.

nested PCR primers a set of oligonucleotide primers used for the amplification of DNA by the polymerase chain reaction (PCR) in which the outermost 5′ and 3′ pair are used in the first phase of amplification and a second pair is designed to prime within that PCR product to produce a shorter amplified sequence. Greater specificity of amplification is expected from this use of two pairs of primers.

nestin an intermediate-filament protein whose name derives from neuroepithelial stem cells, in which it is specifically expressed. It shares significant similarity with other intermediate-filament proteins, including a set of heptad repeats.

netrin any of a family of proteins first isolated from chick brain as diffusible chemoattractants that guide commissural axons to their targets during development. Netrin 1 is expressed at high levels in the floor plate during the period when commissural axons are growing towards the floor plate, while netrin 2 is similarly expressed at lower levels in the ventral two-thirds of the spinal chord. D nectrin is a *Drosophila* homologue, expressed in midline cells of the central nervous system when commissures are forming. The proteins are related to Unc proteins (e.g., *see* **unc-86**) of *Caenorhabditis elegans*.

netropsin a *Streptomyces*-derived basic peptide antibiotic that selectively binds to A–T base pairs in the small groove of right-handed B conformations of DNA. It induces A to B conformational changes in DNA.

Netscape a popular **browser** available for a variety of computers and operating systems.

net sensitivity *see* **flux control coefficient**.

net synthesis increase in the total mass (of a reaction product), as opposed to any apparent increase estimated by incorporation of labelled precursor (which may arise from exchange).

neu an oncogene first described in association with a neuroblastoma after treatment of rats with ethylnitrosourea. The *neu* protooncogene (also known as c-*erbB2*, *NGL*, and *HER2*) encodes a 185 kDa transmembrane glycoprotein with tyrosine kinase activity, related to but distinct from the **epidermal growth factor receptor** (EGFR). The *neu* gene product, Neu, possesses a cysteine-rich extracellular domain, a transmembrane domain, and an intracellular tyrosine kinase domain. EGF does not bind to Neu, but a factor known as **Neu-activating factor** (NAF) binds specifically to Neu and will bind to EGFR. Neu was originally identified in brain, and may play a critical role in neurogenesis. The rat *neu* oncogene is activated constitutively by a point mutation in the transmembrane domain. The association of *neu* with human cancer through gene amplification, or overexpression of the protein product, has been supported by work with breast and ovarian cancer.

Neu **1** *symbol for* a residue (or sometimes a molecule) of **neuraminic acid**. **2** the product of the ***neu*** gene.

NeuAc *or (formerly)* **AcNeu** *symbol for* a residue (or sometimes a molecule) of any isomer of acetylneuraminic acid, i.e. **sialic acid**. *See also* **NeuNAc**, **NeuOAc**, **neuraminic acid**.

Neu-activating factor *see* ***neu***.

Neuberg ester *an old name for* D-fructose 6-phosphate. *See* **fructose 6-phosphate**.

Neuberg's first form of fermentation the normal anaerobic **alcoholic fermentation** of carbohydrate by yeast to yield two moles each of ethanol and carbon dioxide per mole of glucose fermented. [After Carl Alexander Neuberg (1877–1956); German biochemist.]

Neuberg's second form of fermentation the anaerobic fermentation of carbohydrate by yeast in the presence of sodium hydrogen sulfite. the acetaldehyde formed normally, which would act as a hydrogen acceptor for the reoxidation of NADH, is trapped as its bisulfite addition product, and its place is taken by dihydroxyacetone phosphate (i.e. glycerone phosphate), which is reduced to *sn*-glycerol 3-phosphate; this is then dephosphorylated to glycerol. Thus one mole each of glycerol, acetaldehyde–bisulfite complex, and carbon dioxide is formed per mole of glucose fermented.

Neuberg's third form of fermentation the anaerobic fermentation of carbohydrate by yeast in alkaline conditions. The acetaldehyde formed normally, which would act as a hydrogen acceptor for the reoxidation of NADH, undergoes a **Cannizzaro reaction** to form acetic acid and ethanol, and its place is taken by dihydroxyacetone phosphate (e.g. glycerone phosphate), which is reduced to *sn*-glycerol 3-phosphate; this is then dephosphorylated to glycerol. Thus one mole each of glycerol and carbon dioxide, and one half mole each of ethanol and acetic acid, are formed per mole of glucose fermented.

NeuGc *symbol for* a residue (or sometimes a molecule) of *N*-glycoloylneuraminic acid. *See also* **sialic acid**.

NeuNAc *or* **Neu5Ac** *symbol for* a residue (or molecule) of *N*-acetylneuraminic acid (i.e. **sialic acid**). It accumulates in lysosomes in Salla disease and infantile sialic acid storage disease, and in cell cytosol in sialuria.

NeuOAc *symbol for* a residue (or molecule) of *O*-acetylneuraminic acid. *See* **sialic acid**.

neur+ *a variant form of* **neuro+** *(before a vowel)*.

neural of, or pertaining to, a nerve or nerves, or to the nervous system.

neural cell adhesion molecule *abbr.*: NCAM; any type I membrane glycoprotein of the immunoglobulin superfamily that is involved in neuron–neuron adhesion, neurite fasciculation, outgrowth of neurites, etc. NCAMs have poly-α2,8-sialic acid as a post-translational modification. The human protein NCAM-L1 shows strong homology with a *Drosophila* protein, **neuroglian**.

neural crest a group of embryonic cells, derived from the roof of the neural tube, that migrate to different locations and give rise to various types of adult cells.

neural network *or* **artificial neural network** a general class of machine-learning algorithms, inspired by the neural structure of the brain, in which multiple simple processing units are connected by adaptive weights.

neuraminate **1** the anion derived from **neuraminic acid**. **2** any salt or ester of neuraminic acid.

neuraminic acid *symbol*: Neu; the monosaccharide 5-amino-3,5-dideoxy-D-*glycero*-D-*galacto*-nonulosonic acid; it may be regarded as the aldol-condensation product of pyruvic acid and *N*-acetyl-D-mannosamine. It is not found free in nature, but is the parent structure of a family of aminodeoxysugars containing nine or more carbon atoms that occur widely, especially in glycoproteins and gangliosides; they include the **sialic acids**.



α-anomer

neuraminidase *a former name for* **sialidase**.

neuraminosyl *a trivial name for* the glycosyl group derived from **neuraminic acid** by removal of the hydroxyl group from the anomeric carbon atom of the cyclic structure.

neuraminoyl *a trivial name for* the acyl group derived from **neuraminic acid** by removal of the hydroxyl group from the carboxyl group.

neuregulin any member of a family of closely related proteins implicated as regulators of neural and muscle development, and differentiation and oncogenic transformation of mammalian epithelia. They include the Neu differentiation factor (*see* **neu**) and the **heregulins**. They exert their effects through binding to, and activating, receptors of the ErbB2/Neu receptor family. Neuregulins stimulate proliferation of Schwann cells, increase the rate of synthesis of acetylcholine receptors in cultured muscle cells, and are concentrated at nerve–muscle synapses.

neurexin any of a family of cell-surface receptors expressed from three genes in the brain and concentrated in neurons. They are implicated in axon guidance and synaptogenesis. Some are probably signalling molecules. They are highly polymorphic from alternative splicing, and include secreted variants. They contain single transmembrane regions and extracellular domains with repeat sequences similar to those in the globular C-terminal region of laminin A (*see* **laminin**) and **agrin**. Each gene contains two independent promoters so that transcription produces two classes of mRNA, which encode proteins with different N termini, the larger being referred to as α-neurexins and the shorter as β-neurexins. The former contain three epidermal growth factor domains, an O-linked sugar domain, a transmembrane domain, and a short cytoplasmic tail. The α- and β-neurexins differ in their N-terminal sequences but have identical C termini, including the sugar-rich, transmembrane, and cytoplasmic domains. The crystal structure of the laminin A-like sequence ($\approx$200 residues) of neurexin I is similar to that of the pentraxins and some lectins, being a beta sandwich consisting of 14 beta strands.

neurilemma *or* **neurolemma** the thin outer sheath of cells surrounding the axon (and myelin sheath) of larger peripheral nerves or surrounding the axoplasm of unmyelinated nerves.

neurite *a general term for* a dendrite or an axon.

neuritic plaque an extracellular mass of β-amyloid filaments that is associated with dystrophic axons and dendrites, microglia, and astrocytes. In **Alzheimer's disease** such plaques occur in areas of the brain that serve cognition and memory.

neuro+ *or (before a vowel)* **neur+** *comb. form* denoting a nerve or the nervous system.

neuroactive (of an agonist or antagonist) having an effect on the nervous system.

neurocalcin an **EF-hand** Ca^{2+}-binding protein found in retina and brain neurons, involved in the calcium-dependent regulation of rhodopsin phosphorylation.

neurocan a chondroitin sulfate proteoglycan of brain (rat protein: 1235 amino acids). It is developmentally regulated with regard to mass, concentration, carbohydrate composition, sulfation, and localization.

neurochemistry the study of the chemical composition of, and the chemical reactions occurring in, nervous tissue. —**neurochemical** *adj.*

neurocrine **1** describing or relating to a neuron that secretes an agonist into a synapse with another neuron; describing or relating to such an agonist. **2** such an agonist, e.g. a **neurotransmitter**.

NeuroD1 *abbr. for* neurogenic differentiation factor 1; *other name*: BETA 2; a transcription factor, required for normal development of pancreatic islets, that regulates the insulin gene. Mutations are associated with type 6 maturity-onset diabetes of the young.

neuroendocrine **1** describing or relating to a neuron that secretes an agonist into the bloodstream; describing or relating to such an agonist. **2** such an agonist; a **neurohormone**.

neuroendocrine convertase EC 3.4.21.93; *abbr.*: NEC; *other name* prohormone convertase. Any of the enzymes that act at paired dibasic amino acids in precursors of hormones and other **polyproteins**, to cleave the precursor into individual mature proteins. The catalytic activity depends on the Asp-His-Ser **charge-relay system**. Substrates for NEC1 include **proopiomelanocortin**, **renin**, **enkephalin**, **dynorphin**, **somatostatin**, and **insulin**. NEC2 and NEC3 have also been described.

neuroendocrinology the study of the interrelations between the nervous system and the endocrine system. —**neuroendocrinological** *adj.*

neurofascin a chick neurite-associated glycoprotein implicated in axon extension; it is an axonal surface recognition molecule of the immunoglobulin superfamily. At the N terminus, it has six immunoglobulin-like motifs, followed by four fibronectin type III motifs, a proline-alanine-threonine-rich region, a transmembrane domain, and a 113-residue cytoplasmic domain.

neurofibril any of the very fine fibres, visible by light microscopy, that occur in the cell bodies, axons, and dendrites of neurons.

neurofibrillary tangle an intraneuronal inclusion composed of bundles of paired helical filaments consisting mainly of **tau protein**. Neurofibrillary tangles are present in the cerebral cortex of virtually all patients with Alzheimer's disease.

neurofibromatosis any of a number of disorders associated with the presence of multiple **neurofibromas**, benign tumours consisting of a mixture of Schwann cells and fibroblasts. Type 1 is a common autosomal dominant disorder that results from mutations in **neurofibromin**. Type 2 is also autosomal dominant but rare and results from mutations in merlin (also called schwannomin).

neurofibromin *other name*: neurofibromatosis-related protein (NF-I); a GTPase activating protein (*see* **GAP** (def. 2)), the product of the *Nf1* tumour-suppressor gene, that stimulates the GAPase activity of the ***RAS*** oncogene product, thus inactivating it. It appears to be implicated in the pathogenesis of **neurofibromatosis**.

neurofilament a type of **intermediate filament** found in neurons.

neurogenin a transcription factor that promotes neuronal differentiation by inducing neuron-specific genes and by repressing glial cell-specific genes.

neuroglia *an alternative name for* **glia**.

neuroglian a probable cell-adhesion molecule, with structural similarities to **neural cell-adhesion molecule** L1. It is found in neurons and glia of the developing nervous system. It has a single transmembrane domain, with extracellular immunoglobulin-like and fibronectin-type domains.

neuroglobin an oxygen-binding protein of vertebrate brain that may be neuroprotective against ischemia. In mouse retina (which has a very high oxygen demand) its concentration is a hundred times higher than in the brain.

neurohormone any organic compound produced by neurons and released into the circulation to act as a chemical messenger; the term is sometimes extended to all **neurotransmitters** whether released or not. **—neurohormonal** *adj.*

neurohumour *or (US)* **neurohumor** a neurohormone or a neurotransmitter. **—neurohumoral** *adj.*

neurohypophysis (*pl.* **neurohypophyses**) the posterior lobe of the pituitary gland, *also called* **neural lobe** *or* **pars nervosa**. It secretes the peptide hormones oxytocin and vasopressin, and also possibly some others. *Compare* **adenohypophysis**. **—neurohypophyseal** *or* **neurohypophysial** *adj.*

neuroinformatics *see* **informatics**.

neurokinin A *or* **neuromedin L** *or* **substance K** the peptide hormone

His-Lys-Thr-Asp-Ser-Phe-Val-Gly-Leu-Met

derived from **protachykinin β precursor**. It is a member of the **tachykinin** family and is a potent bronchoconstrictor. The related peptide [βAla^8]neurokinin A 4–10,

H-Asp-Ser-Phe-Val-βAla-Leu-Met-NH_2,

is a potent and selective **substance K receptor** agonist.

neurokinin B *or* **neuromedin K** a member of the **tachykinin** family that has neuroendocrine and neuroexcitatory functions, especially in the olofactory, gustatory, and visceral systems. It is a potent bronchioconstrictor. It has the sequence

Asp-Met-His-Asp-Phe-Phe-Val-Gly-Leu-Met-Nh_2

Neurokinin B acts through a G-protein-coupled receptor, known as NK-3, linked to the phosphatidylinositol cycle.

neurolemma *a variant spelling of* **neurilemma**.

neuroleptic any drug used to treat major psychosis, e.g. schizophrenia or mania. Such drugs include phenothiazines, e.g. **chlorpromazine**, and butyrophenones, e.g. **haloperidol**.

neuroleukin a protein produced by activated T lymphocytes that induces immunoglobulin secretion and is a neurotrophic factor. It is identical with monomeric **glucose-6-phosphate isomerase**.

neurolysin EC 3.4.24.16; *other name*: neurotensin endopeptidase; an enzyme that catalyses the preferential cleavage in neurotensin of Pro^{10}-|-Tyr^{11}.

neuromedin B a decapeptide first isolated from porcine spinal cord. Its structure,

Gly-Asn-Leu-Trp-Ala-Thr-Gly-His-Phe-Met,

has close sequence homology to **bombesin**, with which it shares mitogenic and growth-promoting properties. In rat brain its concentration is highest in the olfactory bulb, but is also high in the hypothalamus, hippocampus, and spinal cord. The B in its name indicates its similarity to bombesin.

neuromedin C a neuropeptide similar in its structure,

Gly-Asn-His-Trp-Ala-Val-Gly-His-Leu-Met,

and in its actions to **neuromedin B** and **bombesin**.

neuromedin L *an alternative name for* **neurokinin A**.

neuromedin N a hexapeptide whose C-terminal tetrapeptide is identical to that of **neurotensin**.

neuromodulator any endogenous agent that influences the function of a **neurotransmitter** but has no direct excitatory or inhibitory postsynaptic actions. The term usually implies long-latency and long-lasting effects (i.e. seconds to days).

neuromuscular of, pertaining to, or affecting both nervous and muscular tissue.

neuromuscular junction the place of contact between the motor end-plate of the fibre of a motor neuron and the membrane of a muscle fibre supplied by the neuron. Impulses are transmitted across the gap by diffusion of a neurotransmitter. *Compare* **synapse**.

neuron *or* **neurone** *or* **nerve cell** a cell that is specialized for the transmission of nerve impulses. Neurons are the structural and functional units of the nervous system. Each consists of an enlarged portion, the cell body or perikaryon, containing the nucleus and from which project a variable number of threadlike processes. Of these the short branched dendrites convey impulses towards the cell body, while a longer single nerve fibre, or axon, conveys impulses away from the cell body. The axon is unbranched except at the nerve ending. **—neuronal** *adj.*

neuronal PAS domain protein 2 *see* **NPAS2**.

neuronatin a protein that is highly expressed in neonate mammalian brain, and may be involved in terminal brain differentiation.

neuropeptide *(sometimes)* any peptide with neuroendocrine activity.

neuropeptide K a polypeptide hormone, DADSSIEKQVALLKALYGHGQISHKRHKTDSFVGLM–NH_2, derived from **protachykinin β precursor**. It exhibits a wide spectrum of activities overlapping those of other members of the **tachykinin** family, with which it shares the C-terminal sequence FXLM-NH_2.

neuropeptide Y *or (formerly)* **melanostatin** *abbr.*: NPY; a 36-residue peptide neurotransmitter, structure YPSKPDNPGE DAPAEDMARYYSALRHYINLITRQRY–amide (human, porcine has Leu^{17}), found in the autonomic nervous system and in relatively high concentrations in adrenal glands, brain, and heart. It is a potent stimulator of feeding; leptin inhibits NPY gene expression and release. NPY also regulates secretion of **gonadotropin releasing hormone**. It shows considerable sequence homology with **peptide YY** and **pancreatic polypeptide**. [Leu^{31}, Pro^{34}]NPY is a selective agonist for a Y_1 receptor subclass. *See also* **neuropeptide-Y receptor**.

neuropeptide-Y receptor *abbr.*: NPY receptor *or* Y receptor; a G-protein-associated membrane receptor that binds **neuropeptide Y** (NPY) and inhibits adenylate cyclase and Ca^{2+} channels. Four types have been recognized. A fifth type, Y5, is suggested to mediate the effects of NPY on feeding.

neurophysin any cystine-rich, single-chain polypeptide present in the neurohypophysis. Neurophysin I binds **oxytocin, with which it** shares a common precursor. For example, in rat the precursor protein consists of 125 amino acids, of which residues 1–19 are the signal peptide, 20–28 are oxytocin, and 32–125 are neurophysin I. Neurophysin II binds **vasopressin,** and again shares a common precursor. *See also* **vasopressin-neurophysin 2-copeptin precursor**.

neurophysin II *another name for* **MSEL-neurophysin**.

neuropilin *abbr.*: NP; an integral membrane protein that, like **plexin**, is a coreceptor for some semaphorins.

neuroscience any of the sciences dealing with the nervous system; such sciences collectively.

neurosecretion 1 the process of secretion of a substance by a (specially adapted) nerve cell. **2** a product of such a secretion; a **neurocrine** (def. 2) or **neuroendocrine** (def. 2). **—neurosecretory** *adj.*

neuroserpin a **serpin** that is closely homologous to α_1-antitrypsin and is secreted by neurons, particularly during their growth phase.

neurosome *(sometimes)* a mitochondrion of a nerve cell.

Neurospora a genus of ascomycete microfungi. The species *N. crassa* has been widely used in biochemical and genetic studies. It is commonly found as a mould on bread that has been kept for too long.

neurotensin a tridecapeptide, Glp-Leu-Tyr-Glu-Asn-Lys-Pro- Arg-Arg-Pro-Tyr-Ile-Leu-OH, found in mammalian brain and gut, especially in **N cells**, packaged within secretory vesicles. It is released from the hypothalamus into the circulation. Although initially shown to induce hypotension, it is now known to have a wide variety of pharmacological actions, including muscle contraction. The precursor gives rise to neurotensin and two other derivatives, neuromedin and neuromedin N.

neurotensin endopeptidase *see* **neurolysin**.

neurotoxin any toxin that acts specifically or primarily on nervous tissue. **—neurotoxic** *adj.*

neurotransmission the transmission of nerve impulses from a neuron to another excitable cell via a neurotransmitter.

neurotransmitter any chemical substance released at the distal end of the axon of a neuron in response to the arrival of a nerve impulse that, by diffusing across a **synapse** or other junction, is capable of transmitting the impulse to another neuron, to a muscle cell, or to another excitable cell or, in the case of inhibitory neurotransmitters, of inhibiting the transmission. The neurotransmitter is stored in synaptic vesicles in the axon terminal; it is released into the synaptic cleft on arrival of the action potential and diffuses to and stimulates receptors in the membrane of the post-synaptic cell. An essential component of the mechanism is a means to inactivate the neurotransmitter, e.g. by acetylcholinesterase action on acetylcholine. Both excitatory (*see* **cholinoceptor**, **purinoceptor**, and **glutamate receptor**) and inhibitory (*see* **GABA receptor** and **glycine receptor**) neurotransmitters are known.

neurotrophic factor *see* **brain-derived neurotrophic factor**.

neurotrophin *abbr.*: NT; any of a group of growth factors, similar to **nerve growth factor** but with different tissue specificities. The first to be discovered was named neurotrophin 3, as two proteins with neurotrophic properties had already been discovered (nerve growth factor and **brain-derived neurotrophic factor**). Neurotrophins have properties similar to these latter. Neutrophins 3 to 6 have been described.

neurotropic having a particular affinity for, or affecting nervous tissue.

neurotrypsin a serine protease (875 amino acids) present in presynaptic nerve endings and expressed mainly in cerebral cortex and motor nuclei of the brainstem. It appears at 7–15 weeks of human fetal life. A truncating mutation is associated with a nonsyndromic form of mental retardation.

neurturin a secreted protein that is structurally related to glial cell-derived neurotrophic factor and persephin, and, like them, binds a specific GPI-anchored membrane protein that recruits and signals through RET.

neutral **1** being neither acidic nor basic (or alkaline). **2** having no net charge or electric potential.

neutral amino acid any amino acid containing equal numbers of potentially anionic and cationic groups, as distinct from acidic and basic amino acids.

neutral density filter *an alternative term for* **neutral filter**.

neutral fat *see* **neutral lipid**.

neutral filter *or* **neutral density filter** *(in photography and photometry)* a filter that attenuates all frequencies of light uniformly so that the relative spectral energy distribution of the transmitted light is the same as that of the incident light.

neutrality the condition, quality, or state of being **neutral** (def. 1, 2) or intermediate.

neutralize *or* **neutralise** to render **neutral** (def. 1, 2) or ineffective; to counteract. —**neutralization** *or* **neutralisation** *n.*

neutral lipid *an operational term for* any lipid that is soluble only in solvents of very low polarity. Neutral lipids are divided into two main groups: (1) acylglycerols (glycerides), i.e. fatty-acid esters of glycerol; and (2) waxes, i.e. fatty-acid esters of long-chain monohydroxy alcohols.

Neutral Red an indicator dye that changes colour from red to orange-brown over the pH range 6.8–8.0.



neutral solution any aqueous solution in which the activities of the hydrogen and hydroxide ions are equal. Such a solution in which water is the sole solvent has a pH of 7.00 at 25° C.

neutron *symbol*: n; an elementary particle of zero charge; nucleon number 1; rest mass 1.6749×10^{-27} kg (1.0086 Da); spin 1/2. Neutrons are present in the nuclei of all atoms (except the hydrogen atom), where they are stable; when free, a neutron has a mean life of 932 s, decaying to a proton and an electron.

neutron activation analysis *an alternative name for* **radioactivation analysis**.

neutron diffraction a technique that is similar in principle to **X-ray diffraction** by a crystal, and is applicable particularly to biopolymers and particulate structures. Because hydrogen atoms make a much more substantial contribution to the scattering of neutrons than to X-ray scattering the technique is useful for refining partially determined structures obtained by the use of X-rays. In rare cases it has been used for determination of absolute configuration.

neutron flux (density) the number of free neutrons passing through unit volume multiplied by their mean velocity.

neutron number *symbol*: *N*; a dimensionless physical quantity, having an integral value for any given nuclide, equal to the number of neutrons contained in the nucleus of an atom of the nuclide. Hence, it is equal to the arithmetical difference between the **nucleon number**, *A*, of the nuclide and the **proton number**, *Z*, of the relevant chemical element; i.e. $N = A - Z$.

neutron scattering *see* **small-angle scattering**.

neutrophil *or* **neutrophil leukocyte** *or* **neutrophilic leukocyte** the most numerous **polymorphonuclear leukocyte** found in the blood; a phagocytic cell of the myeloid series that is distinguished by the presence of cytoplasmic azurophil granules and other granules that take up neither acidic nor basic dyes. It plays a major role in the inflammatory response, undergoing chemotaxis towards sites of infection or wounding.

Newman projection a two-dimensional representation of a molecule in which the atoms are arranged as they would be seen if the molecule were viewed from one end along the carbon– carbon bond nearest to the observer. *See also* **conformation**.

newton *symbol*: N; the SI derived unit of force, defined as the force required to give a mass of one kilogram an acceleration of one metre per second per second; i.e. $1\ \mathrm{N} = 1\ \mathrm{kg\ m\ s^{-2}} = 1\ \mathrm{J\ m^{-1}}$ ($= 10^5$ dynes).

Newtonian flow the type of flow displayed by a **Newtonian fluid**.

Newtonian fluid any fluid whose (coefficient of) viscosity is independent of flow rate, conforming to **Newton's law of viscosity**. [After (Sir) Isaac Newton (1642–1727), English astronomer, mathematician, philosopher, and physicist.]

Newton's law of viscosity a law, derived by Isaac Newton, that describes the flow of almost all fluids of low relative molecular mass and also that of some solutions of macromolecules. A fluid moving between two parallel plates, in the *x* direction with a velocity *v*, is thought of as a number of infinitesimal layers, each of which slides along the adjacent one, the frictional resistance between adjacent layers generating an orthogonal velocity gradient, in the *y* direction. The frictional force, *f*, between the fluid layers is then proportional to the area, *A*, of the layers and to the velocity gradient between them, such that:

$$f = \eta A(\mathrm{d}v/\mathrm{d}y),$$

where the constant η is known as the **coefficient of viscosity** (or **viscosity** for short) at the temperature of measurement; its reciprocal, $1/\eta$, is the **fluidity**.

new yellow enzyme *an obsolete name for* the enzyme D-amino-acid oxidase (EC 1.4.3.3), a yellow flavoprotein (FAD) with wide specificity for D-amino acids and acting also on glycine. It was so-named to distinguish it from **old yellow enzyme**. *See* **amino-acid oxidase**.

New Zealand obese mouse *abbr.*: NZO mouse; one of a number of strains of genetically obese mice that are used in metabolic and endocrine research. The obesity is moderate in character and there is an associated hyperinsulinemia and hyperglycemia.

nexin a protein found in the **axoneme** of eukaryotic cilia and flagella. It forms interconnections between the microtubule outer doublets that surround the inner central pair of microtubules. *See also* **glial-derived nexin**.

nexin 1 *other names*: protease nexin I (*abbr.*: PN-I); a glycoprotein that promotes neurite extension, and is an extracellular **serpin**-like serine protease inhibitor.

nexin 2 the secreted isoform of the Alzheimer's amyloid β-protein precursor (*see* **β-amyloid peptide**). *See also* **Alzheimer's disease**.

nexus *(in cytology) an alternative name for* **gap junction**.

NF-1 *see* **CTF**, **neurofibromin**.

NF2 *abbr. for* neurofibromatosis type-2 tumour suppressor; *see* **merlin**.

NF-AT *abbr. for* nuclear factor of activated T cells; a transcription factor complex that activates promoters of the genes for interleukins 2 and 4. It consists of cytoplasmic and nuclear components. The cytoplasmic component, made up of four subunits (NF-ATc1 to NF-ATc4), binds to and is dephosphorylated by calcineurin, then enters the nucleus where it meets the nuclear component (NF-ATn, or NF-AT interacting protein).

NF-κ B a transcription factor for eukaryotic RNA polymerase II promoters. In humans the active protein is a heterodimer of two DNA-binding subunits (p50) which belong to the same family as the **dorsal protein**. It is found in cytoplasm as an inactive complex with an inhibitory subunit, IκB; activation of NF-κB involves its release from its inhibitory subunit. A 105 kDa protein is the precursor of the p50 subunits. These bind to the **kappa-B** consensus sequence, GGRNNYYCC, e.g. GGGGACTTTCC in mouse and human.

NF-E1 *see* **GATA-1**.

ng *symbol for* nanogram.

NGF *abbr. for* nerve growth factor.

L-NHA *abbr. for* N^{G}-hydroxy-L-arginine.

***Nhe*I** a type 2 **restriction endonuclease**; recognition sequence: G↑CTAGC.

NHS *abbr. for* *N*-hydroxysuccinimide.

Ni *symbol for* nickel.

niacin *an alternative name for* **nicotinic acid**.

niacinamide *an alternative name for* **nicotinamide**.

NIAP *abbr. for* neuronal inhibitor of apoptosis protein. *See* **IAP**.

nibrin a protein that is missing in cell lysates from persons suffering from **Nijmegen breakage syndrome**. It is phosphorylated by ATM, a protein kinase whose deficiency due to mutation is the cause of **ataxia telangiectasia**.

nicastrin a type 1 transmembrane glycoprotein (709 amino acids) that associates with presenilins 1 and 2 and modulates the release of β-amyloid peptide from β-amyloid precursor protein.

NICE element *abbr. for* nodule infected cell expression element, a name given to an AT-rich element in *Sesbania rostrata* leghemoglobin glb3.

NICER elements *a name suggested for* a family of genes that are nerve growth factor-inducible, cyclic AMP-extinguishable, and retrovirus-like, hence the acronym.

nick 1 an interruption in the covalent continuity of one strand of a double-stranded nucleic-acid molecule. **2** to produce a nick in a nucleic-acid molecule. *See also* **nick translation**.

nickase an endodeoxyribonuclease present in phage-infected *Escherichia coli* cells that gives rise to single-strand breaks (nicks) in duplex DNA.

nickel *symbol*: Ni; it is a ferromagnetic, metallic transition element of group 10 of the IUPAC **periodic table**; atomic number 28; relative atomic mass 58.69. It consists of a mixture of five stable nuclides of which the two most abundant are those of mass numbers 58 and 60; its commonest valence is ii. Nickel's abundance in the earth's crust is 0.018% and it is an essential trace element for living organisms. Several artificial radionuclides of nickel are known, including nickel-56 (γ-emitter; half-life 6.1 days) and nickel-63 (emits β^- radiation, 0.066 MeV; half-life 100 years).

nickel–iron hydrogenase any of a family of hydrogenases (EC 1.12..) present in some bacteria, which have an active site comprising a nickel and an iron atom, the iron being bound by two cyanide and one carbonyl ligands. They also contain other iron–sulfur clusters, and in some cases flavin.

nicking–closing enzyme *or* **nicking-and-closing enzyme** *see* type I **DNA topoisomerase**.

nick translation a procedure for preparing radioactively labelled DNA, especially for use as probes in hybridization experiments. Single-stranded nicks are introduced into unlabelled DNA, usually by limited treatment with deoxyribonuclease I, exposing 3′-hydroxyl termini. *Escherichia coli* DNA polymerase I (at low temperature, ≈15°C) is then used successively to incorporate radioactive nucleotides (present as dNTPs in the reaction mixture) to form a new, radioactively labelled polynucleotide strand while the 5′→3′ exonuclease activity of the polymerase concomitantly hydrolyses the 5′ termini ahead of the growing strand, liberating 5′-mononucleotides. The reaction thus progressively replaces nucleotide residues by their labelled counterparts in a DNA duplex, which is otherwise unchanged except for the translation of the nick, i.e. its progressive displacement towards the 3′ end of the strand. (The word 'translation' in the name may be misleading as the function involved is replication.)

Nicol prism an optical device constructed of two prisms of calcite cemented together with Canada balsam, used for producing plane polarized light and/or determining its orientation. It has now largely been superseded by Polaroid filters, etc. [After William Nicol (1768–1851), British physicist.]

nicotianamine the metabolic precursor of the phytosiderophores avenic acid (of oats) and mugineic acid (of barley). It is derived from the *α*-aminobutyrate moieties of *S*-adenosylmethionine.

nicotinamide *the recommended trivial name for* pyridine-3-carboxamide, the amide of **nicotinic acid**; *also called* **niacinamide**. It is a member of the B complex of vitamins, and is nutritionally equivalent to nicotinic acid. It occurs widely in living organisms, usually in combined form.



nicotinamide-adenine dinucleotide *abbr.*: NAD$^+$ *or* NAD; if the oxidation state is not to be specified; nicotinamide(1)-*β*-D-riboside(5′)diphospho(5′)adenosine; an atypical dinucleotide containing a phosphoric anhydride linkage in place of the usual phosphodiester linkage between the component mononucleotide units, i.e. between nicotinamide mononucleotide and adenylic acid. It is the specific coenzyme in numerous oxidoreductase enzyme reactions, although in a number it functions interchangeably with **nicotinamide-adenine dinucleotide phosphate**. In these reactions it stereospecifically accepts a hydrogen atom at position 4 of the pyridine ring, plus an electron, to form **nicotinamide-adenine dinucleotide (reduced)**. It acts also as a donor in the ADP-ribosylation of some eukaryotic and prokaryotic proteins. The *α* anomer is inactive as a coenzyme. *Former names*: codehydrogenase I; coenzyme I (Co I); cozymase; diphosphopyridine nucleotide (DPN). *See also* **nicotinamide-adenine dinucleotide (reduced)**.



nicotinamide-adeninedinucleotidephosphate *abbr.*: NADP$^+$; nicotinamide(1)-*β*-D-riboside(5′)diphospho(5′)adenosine 2′-phosphate; a coenzyme with a structure and coenzymic mechanism related to those of **nicotinamide-adenine dinucleotide**, although it functions as the sole coenzyme for fewer oxidoreductases and tends to be involved more in synthetic than in energy-yielding reactions. *Former names*: codehydrogenase II; coenzyme II (Co II); phosphocozymase; triphosphopyridine nucleotide (TPN). *See also* **nicotinamide-adenine dinucleotide phosphate (reduced)**.



nicotinamide-adenine dinucleotide phosphate (reduced) *abbr*.: NADPH; 3-aminocarbonyl-1,4-dihydropyridine(1)-*β*-D-riboside (5′)diphospho(5′)adenosine 2′-phosphate; the reduced form of the coenzyme **nictoinamide-adenine dinucleotide phosphate**. As in **nicotinamide-adenine dinucleotide (reduced)** the carbon atom at position 4 of the 1,4-dihydropyridine ring is prochiral. *See also* **NAD(P)$^+$ stereospecificity**. *Former names*: reduced codehydrogenase II; reduced coenzyme II (Co IIH_2); reduced phosphocozymase; reduced triphosphopyridine nucleotide (TPNH).

nicotinamide-adenine dinucleotide (reduced) *abbr*.: NADH; 3-aminocarbonyl-1,4-dihydropyridine(1)-*β*-D-riboside(5′)diphospho(5′)adenosine; the reduced form of the coenzyme **nicotinamide-adenine dinucleotide**. The carbon atom at position 4 of the dihydropyridine ring is prochiral; removal of one of the two hydrogen atoms from position 4 (or introduction of a hydrogen atom at this position into the oxidized form) through the agency of an NAD-linked oxidoreductase is stereospecific, the two hydrogen atoms being designated *pro-R* (or H_A) or *pro-S* (or H_B), and the two corresponding aspects of the (dihydro)pyridine ring frequently being known as the *A* face and the *B* face. The *α* anomer is inactive as a coenzyme. *Former names*: reduced codehydrogenase I; reduced coenzyme I (Co IH_2); reduced cozymase; reduced diphosphopyridine nucleotide (DPNH). *See also* **NAD(P)$^+$ stereospecificity**.

nicotinamide mononucleotide *symbol*: NMN; nicotinamide(1)-*β*-D-riboside 5′-phosphate; the mononucleotide produced when **nicotinamide-adenine dinucleotide** acts as a donor of an adenylyl group in the activation of DNA ligase.



nicotinamide nucleotide any nucleotide that contains combined nicotinamide, e.g. nicotinamide-adenine dinucleotide (reduced), nicotinamide-adenine dinucleotide phosphate (reduced).

nicotinamide–nucleotide adenylyltransferase EC 2.7.7.1; *other name*: NAD^+ pyrophosphorylase; an enzyme that catalyses the formation of NAD^+ from ATP and nicotinamide ribonucleotide with release of pyrophosphate and NAD^+. *See also* **NAD^+ synthase**, **NAD^+ synthase (glutamine-hydrolysing)**.

nicotinate pyridine 3-carboxylate; the anion derived from **nicotinic acid**.

nicotinate mononucleotide 3-carboxylatopyridine(1)-*β*-D-riboside 5′-phosphate; an intermediate in the biosynthesis of nicotinamide-adenine dinucleotide. It reacts with ATP to form desamido-NAD, which is subsequently converted to NAD by a glutamine-dependent amidation of the carboxyl group.

nicotine (*S*)(–)-3-(1-methyl-2-pyrrolidinyl)pyridine; the principal example of a number of related very poisonous and addictive alkaloids extractable from the dried leaves of various species of tobacco, especially *Nicotiana tabacum*. It is an agonist of the nicotinic class of **cholinoceptors**. —**nicotinic** *adj.*

nicotinic acetylcholine receptor *see* **cholinoceptor**.

nicotinic acid *abbr.*: NA; *the recommended trivial name for* pyridine 3-carboxylic acid, *also known as* niacin. It is a member of the B complex of vitamins, nutritionally equivalent to **nicotinamide**. At physiological pH values it exists virtually exclusively as the nicotinate anion.



nidogen *or* **entactin** a sulfated glycoprotein that is widely distributed in basement membranes, and tightly associated with **laminin**.

Niemann–Pick disease *an alternative name for* **sphingomyelin lipidosis**. [After Albert Niemann (1880–1920), German physician.]

Niemann–Pick protein C a membrane protein of late endosomes and the *trans* Golgi network that when mutated causes Niemann–Pick disease types C and D (*see* **sphingomyelin lipidosis**). The gene at 18q11 encodes a protein of 1278 amino acids, which contains 13 transmembrane segments and a leucine-zipper domain. Five of the transmembrane segments have significant homology with the sterol-sensing domain of **SCAP**, HMG-CoA reductase, and Patched.

nif the symbol for any gene controlling bacterial nitrogen fixation; individual genes are distinguished by suffixed capital letters, e.g. *nifB*, *nifQ*. In *Klebsiella pneumoniae* the *nif* cluster has at least 18 genes, arranged in seven distinct operons with no other interspersed genes; the total length of the *nif* region is ≈24 kb. The two polypeptide subunits of component I of **nitrogenase** and the polypeptide subunit of component II are each controlled by a single *nif* gene; the production and insertion of iron–molybdenum cofactor (FeMo-co) into component I appears to require three to six genes; the production of mature component II is controlled by two to four genes; two electron-transporting proteins are coded for by one gene each; and three or more genes are concerned with regulating expression of others. Six genes are required for the production and insertion of iron–molybdenum cofactor (Fe-Mo-co) into component I. Two genes, *nifS* and *nifU*, are required for the assembly of iron–sulfur clusters; *nifS* is a cystein desulfurase, EC 2.8.1.7, which provides the sulfide, and *nifU* provides a scaffold for assembly of the clusters.

nifedipine 1,4-dihydro-2,6-dimethyl-4-(2-nitrophenyl)-3,5-pyridinedicarboxylic acid dimethyl ester; one of the dihydropyridine calcium antagonists. It is a calcium channel blocking agent inhibiting the cellular influx of calcium associated with the plateau phase of



the action potential. It acts as a vasodilator, reducing blood pressure and increasing coronary blood flow.

nigericin a 725 Da, open-chain macrotetrolide-like antibiotic, with many chiral centres, isolated from *Streptomyces hygroscopicus*. It forms stable complexes with monovalent cations, especially with K^+; these complexes are soluble in organic solvents, and thus nigericin can act as an ionophore for monovalent cations. It has some structural resemblance to **monensin**.

nigerose the disaccharide 3-*O*-α-D-glucopyranosyl-D-glucose.



night blindness *or* **nyctalopia** the inability to see in dim light or at night. It is due to deficiency of vitamin A or to degeneration of the **rod cells** in the retina of the eye, which primarily mediate vision in dim light.

NIH *abbr. for* National Institutes of Health (of the USA).

NIH shift *or* **hydroxylation-induced migration** an intramolecular migration that often occurs in the hydroxylation reactions of alkylaromatic compounds catalysed by certain mono- or dioxygenases, whereby a hydrogen atom or a substituent atom or group at the position of hydroxylation moves to an adjacent carbon atom in the aromatic ring. For example, in the hydroxylation of phenylalanine to tyrosine, catalysed by phenylalanine 4-monooxygenase (EC 1.14.16.1), the hydrogen atom at C-4 in the ring can be shown by tritium labelling to migrate to C-3. [After NIH, i.e. National Institutes of Health, where the discoverers were based.]

NIH-3T3 a continuous cell line established from NIH Swiss mouse embryo cultures. These cells are adherent, have fibroblast morphology, and are useful for DNA transfection and transformation studies.

Nijmegen breakage syndrome a human syndrome of mental retardation, increased susceptibility to cancer, immunodeficiency, and chromosomal instability. It is due to mutation in the gene (at 8q11) for **nibrin**, which is missing in cell lysates from patients. It is sometimes considered to be a variant of **ataxia telangiectasia**. [Named after Nijmegen, a city in the Netherlands where it was first indentified.]

NIMR *abbr. for* National Institute for Medical Research (of the UK).

ninein *see* **centrosome**.

ninhydrin *the trivial name of* triketohydrindene hydrate; 2,2-dihydroxy-1,3-indanedione; a pale-yellow crystalline substance, useful as a sensitive chromogenic reagent for the detection and quantification of compounds containing free amino or imino groups. The common amino acids (and the free amino groups of peptides and proteins, and various other amino compounds) give a red, violet, or blue coloration, the shade depending somewhat on conditions, whereas the imino acids proline and hydroxyproline give a yellow colour. The partially reduced ninhydrin derivative, hydrindantin, is often added to the reagent solution, as it reacts with free ammonia that is formed as a side product, and in combination with ninhydrin forms the coloured product, thus enhancing the sensitivity of the reaction.



NIPK *abbr. for* neuronal cell death-inducible protein kinase; *other name*: tribbles homologue protein 3 (*abbr.*: TRB3). One of three mammalian homologues of the *Drosophila* protein **tribbles**. It contains 354 amino acids, inhibits Akt/PKB – a key component of insulin receptor signalling – and its expression in liver is increased by fasting. TRB1, TRB2, and TRB3 share 45% amino acid sequence homology and strongly resemble tribbles.

Nir *symbol for* the ribonucleoside ribosylnicotinamide.

NIS *abbr. for* Na^+/I^- symporter. *See* **iodide pump**.

nisin a pore-forming toxin produced by the bacterium *Lactococcus lactis*. It has a molar mass of 5.8–6.3 kDa and creates opening in the affected membrane that permit passage of small solutes. It is used commercially for protection of foods against bacterial infection. In the TC system it has number 1.C.20.

Nissl substance *a collective term for* the dense regions of granular endoplasmic reticulum and free polysomes observable by microscopy within the cytoplasm of the cell body of vertebrate neurons. [After Franz Nissl (1860–1919), German neuropathologist, who first observed it.]

NIT domain *abbr. for* nitrate- and nitrite-sensing domain; a protein domain (≈250 amino acids, with several conserved charged residues) that is present in various receptor components of signal-transducing pathways in a variety of bacterial species. It may be intracellular or extracellular and lies between two transmembrane segments. It is predicted to form 10 alpha helices.

nitrate **1** the NO_3^- ion, derived from nitric acid. **2** any salt or ester of nitric acid.

nitrate assimilation *an alternative term for* assimilatory nitrate reduction; *see* **nitrate reduction**.

nitrate dissimilation *an alternative term for* dissimilatory nitrate reduction; *see* **nitrate reduction**.

nitrate reductase **1** any of the enzymes **nitrate reductase (NADH)** (EC 1.6.6.1), **nitrate reductase (NAD(P)H)** (EC 1.6.6.2), or **nitrate reductase (NADPH)** (EC 1.6.6.3) that reduce nitrate to nitrite coupled to the oxidation of the coenzymes indicated. They are widespread among plants and microorganisms, where they participate in assimilatory nitrate reduction. All are flavoproteins, usually containing one atom of molybdenum per molecule. **2** the microbial enzyme, nitrate reductase (EC 1.7.99.4), that reduces nitrate to nitrite coupled to the oxidation of various electron donors in dissimilatory nitrate reduction. **3** the microbial enzyme, **nitrate reductase (cytochrome)** (EC 1.9.6.1), that reduces nitrate to nitrite coupled to the oxidation of a ferrocytochrome to the corresponding ferricytochrome. *See also* **nitrate reduction**.

nitrate reduction any reaction or sequence of reactions in which nitrate ion is converted to other less highly oxidized inorganic nitrogenous substances, e.g. to nitrite ion, nitrous oxide, dinitrogen, ammonium ion, or amino acids. In enzymology the term is restricted to the enzymic reduction of nitrate ion to nitrite ion, catalysed by a **nitrate reductase** enzyme. In biology, nitrate reduction is of two types, distinguishable by the purposes served and by the enzymes involved. **assimilatory nitrate reduction** is the process occurring in higher plants, algae, and fungi, in which nitrogen from nitrate is converted into organic nitrogen-containing compounds, via the probable reaction sequence: nitrate → nitrite → [hyponitrite] → hydroxylamine → ammonium → amide group of glutamine → amino acids, etc. **dissimilatory nitrate reduction** or **nitrate respiration** is the process occurring in some microorganisms under anaerobic conditions in which nitrate functions as a terminal electron acceptor in respiratory metabolism. The nitrogen may either be converted to ammonium (which is not assimilated), a process designated **ammonification of nitrate**, or be converted to various gaseous compounds such as nitric oxide, nitrous oxide, and/or dinitrogen, a process designated **denitrification**. *Compare* **nitrification**.

nitrene the chemical entity NH or any of its substitution derivatives. It contains an electrically neutral mono-coordinate nitrogen atom with four nonbonding electrons; two of these electrons are paired while the other two have spins that may be either antiparallel (singlet state) or parallel (triplet state). *Other names*: azacarbene; azene; imene; imine radical.

nitric oxide nitrogen monoxide; NO; a colourless gas, only slightly soluble in water, that reacts readily with O_2 to form nitrogen dioxide, NO_2; it can form the stable cation NO^+. It accounts for the action of endothelium-derived relaxing factor (EDRF). Nitric oxide is a biogenic messenger with potent actions including vasodilation, inhibition of platelet aggregation, and reduction of endothelium adhesion; it also has anticoagulant and fibrinolytic actions. It is formed biosynthetically from L-arginine by **nitric-oxide synthase** in most mammalian tissues in varying amounts, including vascular endothelial cells, the central and peripheral nervous system, immune cells, lung, or liver. It activates guanylate cyclase, producing cyclic GMP. It is oxidized to nitrite, then to nitrate, which is present in the blood.

nitric-oxide synthase EC 1.14.13.39; *abbr.*: NOS; *systematic name*: L-arginine,NADPH:oxygen oxidoreductase (nitric-oxide-forming). An enzyme that catalyses a reaction between L-arginine, NADPH, and O_2 in which citrulline, $NADP^+$, and nitric oxide are formed; heme, FAD, FMN, and tetrahydrobiopterin are required as cofactors; the heme centre has the spectral properties of a cytochrome P450; N^{ω}-hydroxy-L-arginine is an intermediate, and acts as a substrate for the enzyme. Three isoforms are known: **nNOS**, of neuronal tissues, and **eNOS**, of vascular endothelial cells, are both expressed constitutively and are Ca^{2+}-dependent; **iNOS**, inducible in macrophages and liver cells, is not Ca^{2+}-dependent, but binds calmodulin with extremely high efficiency. All have consensus sequences for the binding of NADPH, FAD, FMN, and calmodulin, and a phosphorylation site for cyclic-AMP-dependent protein kinase A; eNOS has an N-terminal consensus sequence for myristoylation. Inhibitors include L-N^5-(1-iminoethyl)ornithine, N^G-monomethyl-L-arginine, N^G-nitro-L-arginine.

nitrification the process by which certain soil bacteria (nitrifying bacteria) oxidize ammonium ions in decomposing organic material into nitrate ions. *Nitrosomonas* spp. first convert ammonium to nitrite, and *Nitrobacter* spp. then oxidize nitrite to nitrate. Most higher plants can assimilate nitrate much more readily than they can ammonium. *Compare* **denitrification**.

nitrify **1** (of nitrifying bacteria) to oxidize ammonium to nitrate. **2** to treat (soil) with nitrates. **—nitrified** *or* **nitrifying** *adj.*

nitrifying bacteria obligately aerobic bacteria that are capable of oxidizing ammonia to nitrite, and nitrite to nitrate. *See* **nitrification**. *Compare* **denitrifying bacteria**.

nitrite **1** the NO_2^- ion, derived from nitrous acid. **2** any salt or ester of nitrous acid.

nitrite reductase **1** the enzyme **nitrite reductase (NAD(P)H)** (EC 1.6.6.4) that reduces nitrite to ammonium coupled to the oxidation of either NADH or NADPH. It is a flavin-dependent enzyme that also contains **siroheme**; it participates in assimilatory **nitrate reduction** in higher plants, algae, fungi and bacteria. **2** the enzyme **nitrite reductase (cytochrome)** (EC 1.7.2.1) that reduces nitrite to nitric oxide coupled to the oxidation of ferrocytochrome *c* to ferricytochrome *c*. It is a cuproprotein and participates in denitrification processes in some microorganisms. **3** the enzyme **ferredoxin–nitrite reductase** (EC 1.7.7.1) that reduces nitrite to ammonium coupled to the oxidation of reduced ferredoxin; the enzyme in spinach leaves contains one molecule of siroheme and one iron–sulfur [2Fe-2S] cluster per molecule. It participates in assimilatory nitrate reduction, the reduced ferredoxin being derived from the light reactions of photosynthesis. **4** the microbial enzyme, nitrite reductase (EC 1.7.99.3), that reduces nitrite to nitric oxide coupled to the oxidation of various electron donors in dissimilatory nitrate reduction; the enzymes from *Achromobacter cycloclastes* and *Pseudomonas denitrificans* contain copper.

nitro the chemical group $-NO_2$ in a molecule of an organic compound.

nitro+ *prefix (in chemical nomenclature)* **1** indicating the presence of a **nitro** group in an organic compound. **2** *(in chemical technology)* indicating that a chemical compound is a nitrate ester.

Nitroblue Tetrazolium *see* **Nitrotetrazolium Blue**.

nitrogen **1** *symbol*: N; a nonmetallic element of group 15 of the IUPAC **periodic table**; atomic number 7; relative atomic mass 14.0067. There are two natural stable nuclides of relative masses 14 (99.635 atom percent) and 15 (*see* **nitrogen-15**); its commonest valences are iii and iv. Nitrogen occurs naturally in the form of diatomic molecules of the gas dinitrogen (see below) and in combined form in numberless organic molecules in all forms of life. *See also* **nitrogen-13**. **2** **dinitrogen** *or* **molecular nitrogen** *symbol*: N_2; a diatomic nonflammable gas. It constitutes 75.5% by mass, or 75.06% by volume, of the Earth's atmosphere, and undergoes exchange with organically combined nitrogen via the processes of the **nitrogen cycle**. Liquid nitrogen, b.p. 77.36 K, is commonly used as a coolant or freezing agent.

nitrogen-13 the artificial radioactive nitrogen nuclide ${}^{13}_{7}N$. It emits a positron (β^+-particle) (1.19 MeV max.) and no gamma radiation; it has a half-life of 9.96 min.

nitrogen-15 heavy nitrogen; the stable, naturally occurring nitrogen nuclide${}^{15}_{7}N$; relative abundance in nitrogen 0.365 atom percent. It is extensively used as a tracer in studies of nitrogen metabolism and in **nuclear magnetic resonance**.

nitrogenase an enzyme complex that catalyses the ATP-dependent fixation of atmospheric nitrogen, summarized by the equation:

$$N_2 + 10H^+ + 8e^- + 16ATP \rightarrow 2NH_4^+. + H_2 + 16ADP.$$

Depending on the bacterial species, the electrons may be donated either by reduced ferredoxin (this enzyme is EC 1.18.6.1) or flavodoxin (EC 1.19.6.1). For each molecule of nitrogen reduced, at least one molecule of hydrogen is released. Either type of nitrogenase will use ferredoxin or flavodoxin as donor *in vitro*. Nitrogenase consists of two oxygen-sensitive components, known as MoFe protein (*other names*: component I; dinitrogenase; molybdoferredoxin) and Fe protein; (*other names*: component II, dinitrogenase reductase; azoferredoxin). Component I is a tetramer made up of two polypeptide chains of about 50 and 60 kDa, each present twice; the tetramer contains two P-clusters (Fe_8S_7) and two Fe-Mo cofactors *(abbr.*: FeMo-co). The Fe-Mo cofactor has the formula Fe_7MoS_9. The Mo is coordinated by 3 sulfide ions, a histidine N and 2 oxygen atoms of homocitrate. The extremely oxygen-sensitive component II is a dimer of identical, ~30 kDa, polypeptide chains; each binding a molecule of ATP. The two subunits of the dimer are bridged by a single [4Fe-4S] cluster. Electrons from a donor, such as NADPH, are transferred, via reduced ferredoxin or flavodoxin, to component II. Then, in the presence of Mg^{2+} they are passed to component I, with concomitant hydrolysis of 4–5 molecules of ATP per two electrons transferred. Eventually they are used to reduce dinitrogen to ammonium. Nitrogenase also catalyses ATP-dependent partial reductions of some other small-molecules that are isoelectronic with dinitrogen, e.g. ethyne, azide, cyanide, and dinitrogen monoxide. The reduction of ethyne to ethene, which can be measured by gas chromatography is used as a convenient assay for nitrogenase activity. Alternative nitrogenases are known that contain vanadium instead of molybdenum, or just iron as the only transition metal; these appear to be structurally and functionally analogous to the molybdenum-containing nitrogenase although they produce more H_2 per N_2 reduced.

nitrogenase reductase *another name for* dinitrogenase reductase; i.e. component II of **nitrogenase**.

nitrogen balance **1** *(in physiology)* the **balance** (def. 1) of the nitrogen content of the nutrients and the excretory products of an organism. **2** *(in agriculture)* the net loss or gain of the nitrogen content of soil that results from removal of nitrogen by cropping, leaching, etc. and addition of nitrogen by nitrogen fixation or addition of nitrogenous fertilizers.

nitrogen base *an alternative term for* **nitrogenous base**.

nitrogen cavitation *an alternative name for* **pressure homogenization**.

nitrogen cycle the series of chemical processes by which various inorganic and organic nitrogenous compounds are interconverted and maintained in equilibrium in the biosphere. It consists essentially of **nitrogen fixation**, **nitrification**, and **denitrification**, together with assimilatory and dissimilatory **nitrate reduction** and the interconversion of nitrogenous organic matter and ammonium. Individual reactions may be effected by microorganisms, plants, or animals, with contributions from nonbiological processes such as manufacture of nitrogenous fertilizers, the action of lightning, and emission of combustion products.

nitrogen equilibrium the state of **nitrogen balance** (def. 1) when nitrogen intake equals nitrogen excretion.

nitrogen fixation any biological or nonbiological process that converts atmospheric dinitrogen into inorganic nitrogenous compounds; the meaning is often extended to include the biological assimilation of ammonium so produced. Biological nitrogen fixation occurs by the action of the enzyme **nitrogenase**, found in certain species of bacteria – the nitrogen-fixing bacteria.

nitrogen mustard any of a group of bis(2-chloroalkyl)amines, as typified by the volatile base bis(2-chloroethyl)ethylamine, $\mathrm{CH_3–CH_2–N(CH_2–CH_2Cl)_2}$, a nitrogen-containing analogue of **mustard gas**. They are potent alkylating agents, vesicants, and mutagens. They cross-link DNA chains and have been used as immunosuppressive and antineoplastic agents.

nitrogenous 1 of or relating to **nitrogen**. **2** of or relating to any substance containing nitrogen in combined form.

nitrogenous base *or* **nitrogen base** *a generic term for* ammonia or any trivalent compound of nitrogen that can be regarded as a derivative of ammonia; all except quaternary ammonium compounds are weakly basic in character. In biochemistry, the term usually denotes any purine or pyrimidine; now generally shortened to base.

nitrogen regulatory protein *abbr.*: NR protein; any of several proteins of a regulatory system for transcriptional control of the glutamine-ammonia ligase, and for its regulation at the structural level. Transcriptional regulation is mediated by the proteins $\mathrm{NR_I}$ and $\mathrm{NR_{II}}$: $\mathrm{NR_I}$, when phosphorylated, acts as a transcriptional activator of the gene *glnA*; $\mathrm{NR_{II}}$ is a kinase that converts $\mathrm{NR_I}$ to $\mathrm{NR_I}$-P, the phosphorylated, active form. Another protein, $\mathrm{P_{II}}$, prevents this phosphorylation, thereby preventing transcriptional activation. $\mathrm{P_{II}}$ can be uridylylated at $\mathrm{Tyr^{51}}$ to $\mathrm{P_{II}}$-UMP by a **uridylyl transferase**, and then does not inhibit $\mathrm{NR_I}$ phosphorylation, so activating transcription. This occurs when the level of nitrogen is low. Regulation of glutamate–ammonia ligase at the structural level involves adenylylation by adenylyl transferase, which inactivates it. Adenylyl transferase is activated by $\mathrm{P_{II}}$. In the presence of $\mathrm{P_{II}}$-UMP, adenylyl transferase is inactivated, and glutamate–ammonia ligase reverts to a non-adenylylated, active form. Uridylylation of $\mathrm{P_{II}}$ thus results in activation of transcription of glutamate–ammonia ligase, and its activation at the structural level.

nitroglycerin 1,2,3-propanetriol trinitrate; a compound that is used industrially in the manufacture of dynamite, and pharmacologically as an antianginal and coronary vasodilator. Its action in the latter case results from its conversion to **nitric oxide**.

nitrophenyl a group that is linked to a variety of compounds to form artificial substrates for enzymes. The nitrophenol released by the enzyme action can then be measured spectrophotometrically at 400 nm (4-nitrophenol) or 420 nm (2-nitrophenol) to follow the enzyme reaction, the esterified form having a maximal absorption at a much lower wavelength. Typical substrates are 4-nitrophenylacetate (for carboxylesterase, lipase), 4-nitrophenyl-*N*-acetylgalactosaminide (galactosaminidase), 4-nitrophenyl-*N*-acetylglucosaminide (glucosaminidase), and 2-nitrophenylbutyrate (cholinesterase).

nitrophorin *abbr.*: NP; a monomeric hemoprotein (≈20 kDa) secreted in saliva of the blood-sucking reduviid bug *Rhodnius prolixus*. There are four nitrophorins (NP 1 to 4), which are homologous and contain a conserved eight-stranded beta barrel. They carry nitric oxide, which causes smooth muscle relaxation and vasodilation in the host. They also bind histamine and reduce the inflammatory and immune responses in the host. **NP2** (also called prolixin-S) inhibits activation of clotting factor X.

nitroprusside test a test for free thiol groups based on the red coloration given on reaction of thiol-containing compounds with ammoniacal sodium nitroprusside, sodium nitrosopentacyanoferrate(iii), $\mathrm{Na_2[Fe(CN)_5NO]}$. Nitroprusside also reacts with ketones and is used in tests for ketone bodies in urine. The proprietary Acetest tablets contain a mixture of glycine, sodium nitroprusside, disodium phosphate, and lactose. In the presence of glycine, acetoacetate or acetone forms a blue– purple colour. A positive reaction indicates the presence of ≥5 mg $\mathrm{dL^{-1}}$ and 10 mg $\mathrm{dL^{-1}}$ for urine and blood respectively.

nitros+ *a variant form of* **nitroso+** (before a vowel).

***N*-nitrosamide** any organic compound in which a **nitroso** group is attached to an amide nitrogen, e.g. *N*-methyl-*N*-nitrosourea. *See also* ***N*-nitrosamine**.

***N*-nitrosamidine** any organic compound in which a **nitroso** group is attached to an amidine nitrogen, e.g. *N*-methyl-*N′*-nitro-*N*-nitrosoguanidine. *See also* ***N*-nitrosamine**.

***N*-nitrosamine** any organic compound of general formula $\mathrm{R_1R_2NNO}$. They are stable compounds formed by the action of nitrous acid on secondary amines with concurrent monodealkylation, and also on some tertiary amines. Most nitrosamines are strongly carcinogenic and their metabolites are strong mutagens. ***N*-nitrosamides** and ***N*-nitrosamidines** are unstable nitroso compounds that decompose in neutral or alkaline conditions to produce powerful alkylating agents. They are widely used as experimental mutagens. They are carcinogenic in any tissue with which they come into contact.

nitroso the chemical group –NO in a chemical compound.

nitroso+ *or (before a vowel)* **nitros+** *prefix (in chemical nomenclature)* indicating the presence of a **nitroso** group in a chemical compound; in *C*-nitroso compounds the –NO is attached to carbon (e.g. nitrosobenzene) and in *N*-nitroso compounds it is attached to nitrogen.

***S*-nitroso-*N*-acetylpenicillamine** *abbr.*: SNAP; an *S*-nitrosothiol reagent that stimulates guanylate cyclase and mimics the action of nitric oxide.



S-nitroso-*N*-acetyl-d-penicillamine

***S*-nitrosoglutathione** a nitrosating reagent that breaks down to nitric oxide and a glutathione radical. It induces the cellular effects of nitric oxide, including smooth muscle relaxation and inhibition of platelet aggregation.

Nitrotetrazolium Blue *or* **Nitroblue Tetrazolium** a dye very similar in structure to Tetrazolium Blue (*see* **tetrazolium salt**), differing only in that each of the two tetrazolium groups has a nitrophenyl group in place of a phenyl group.

nitrous acid the very unstable monobasic acid $\mathrm{HNO_2}$. It reacts with amines, including purine and pyrimidine amines, to form the corresponding hydroxy compounds, and is thus mutagenic.

nitroxide the divalent group $\mathrm{=N–O^{\bullet}}$ in a molecule of an organic compound. It has an unpaired electron, and is useful in spin-labelling, its derivatives being stable free radicals.

NK cell *abbr. for* natural killer cell; a large granular lymphocyte that recognizes structures on the surface of virally infected cells, which it kills, probably through the mediation of a **perforin**.

NKSF *abbr. for* NK stimulating factor. *See* **interleukin 12**.

Nle *symbol for* the α-amino acid norleucine (now known as 2-aminohexanoic acid, *symbol*: Ahx).

NLM *abbr. for* National Library of Medicine.

NLP *abbr. for* natural language processing.

NLS *abbr. for* nuclear localization signal.

nm *symbol for* nanometre.

nM *symbol for* nanomolar.

NMD *abbr. for* nonsense-mediated decay.

NMDA *abbr. for* *N*-methyl-D-aspartate.

NMDA receptor *see* **glutamate receptor**.

NMN *abbr. for* nicotinamide mononucleotide.

nmol *symbol for* nanomole.

NMP *abbr. for* any (unknown or unspecified) nucleoside monophosphate in which the phosphate group is esterified at the 5′ position of the glycose moiety.

NMR *or* **nmr** *abbr. for* nuclear magnetic resonance.

Nn *symbol for* the nonyl group.

Nno *symbol for* the nonanoyl group.

nNOS *see* **nitric-oxide synthase**.

NNRTI *abbr. for* non-nucleoside reverse transcriptase inhibitor.

No *symbol for* nobelium.

nociceptin *an alternative name for* **orphanin FQ**.

nociceptive causing pain or injury; reacting to a painful stimulus.

nociceptor any receptor that reacts to painful (i.e. nociceptive) stimuli; a pain-sense organ.

Nod a family of human intracellular proteins involved in detection of invasive bacteria and activation of the NF-κB transcription factor pathway. In epithelial cells, Nod1 is essential for sensing intracellular Gram-negative bacteria through a tripeptide motif in the bacterial peptidoglycan.

NodD a transcription factor of *Rhizobium* bacteria that, on binding an inducer secreted by infected root cells in a host plant, induces *nod* genes in the bacterium.

node 1 a knob, lump, or swelling; a constriction, especially when serially repeated (along the length of something). **2** *(in botany)* the point on a stem to which a leaf or a lateral branch is attached. **3** *(in physics)* a point of zero or minimum displacement in a standing wave or a system of such waves. *See also* **node of Ranvier**. **—nodal** *adj.*

node of Ranvier any of the constrictions in the myelin sheath that occur at regular intervals along the length of a myelinated nerve fibre. [After Louis Antoine Ranvier (1835–1922), French pathologist.]

Nod factor any bacterial product, made by enzymes encoded in *nod* genes of *Rhizobium* species, that directs nodulation in the host plant. Nod factors are lipopolysaccharides consisting of a short linear backbone of β1-4-linked *N*-acetylglucosamine residues, the first of which is usually *N*-acylated by a C_{16}, C_{18}, or C_{20} fatty acid of varying levels of unsaturation. The factors cause rapid cell division in infected root cortical cells of legumes to form the nodules involved in nitrogen fixation.

***nod* gene** any gene in *Rhizobium* bacteria that is responsible for early nodule formation in nitrogen-fixing plants. The expression of *nod* genes depends on an inducer (e.g. genistein or daidzein) from the host and an endogenous transcription factor (NodD) in the bacterium that is a receptor for the inducer. Many *nod* genes encode enzymes that direct the synthesis of bacterial **Nod factors** responsible for inducing nodulation in the host.

NOD mice *abbr. for* nonobese diabetic mice.

nodoc *a name sometimes used for* **anticodon** (formed by reversing the letters of the word codon).

nodulation factor a lipooligosaccharide secreted by *Rhizobium* species as an extracellular signal that induces nodule formation in the roots of a host legume plant. It consists of a linear chain of 3–6 (usually 5) *N*-acetylglucosamine residues joined β1-4 and with a (usually C_{18}) fatty acid attached to the N atom of C2 of the nonreducing end.

nodule bacterium *or* **nodule-forming bacterium** *a common name for* any bacterium of the genus *Rhizobium*, found as endosymbionts in root nodules. The bacterium specifically infects root cells of Leguminosae, and causes the development of **root nodules**, in which it loses its outer membrane and becomes dependent on plant metabolism. It is then morphologically differentiated from the free-living form and known as a bacteroid. In return it fixes nitrogen for the plant. *See* **nitrogenase**.

nodulin any protein that is produced within root nodules of nitrogen-fixing plants in response to **Nod factors** secreted by *Rhizobium* bacteria in infected cells. Their roles include acting as membrane channels for transport across the symbiosome membrane; as enzymes involved in metabolism of carbon and nitrogen; or in establishing a low-oxygen environment (e.g. leghemoglobin). Nodulins are described as early or late depending on when they are expressed during nodule formation.

NOE *abbr. for* nuclear Overhauser effect.

NOESY *abbr. for* nuclear Overhauser effect spectroscopy. *See* **NMR**.

nogalamycin an antitumour antibiotic material obtained from *Streptomyces nogalater*. It contains the carbohydrate component **nogalose**.

nogalose 6-deoxy-3-*C*-methyl-L-mannose 2,3,4-trimethyl ether; a carbohydrate component of **nogalamycin**.



noggin a dorsalizing factor localized to **Spemann's organizer** in *Xenopus laevis* embryos.

Nogo an abundant **myelin protein** that is produced by oligodendrocytes in the central nervous system. Like myelin-associated glycoprotein it inhibits neuronal regeneration. It has two transmembrane segments and an extracellular loop of 66 residues (sometimes called Nogo-66) that binds to the **Nogo receptor**.

Nogo receptor a phosphatidylinositol (PI)-anchored peripheral cell surface protein of neurons in the central nervous system. It binds the 66-residue extracellular loop of **Nogo**, and also myelin-associated glycoprotein and oligodendrocyte myelin glycoprotein. *See* **myelin protein**.

noise any undesired disturbance in the signal from an instrument, or other system, that degrades the amount of useful information extractable. *Compare* **signal-to-noise ratio**.

noise analysis the technique whereby the amplitude and frequency of random fluctuations in the membrane potential of an excitable cell are used to investigate changes in conductance of single ion channels induced, e.g., by a drug or neurotransmitter.

nojirimycin any of a group of carbohydrate-like alkaloids or imino sugars originally found in a *Streptomyces* filtrate but also found in plants such as *Morus alba* and *Angylocalyx pynaertii*. Nojirimycins are inhibitors of glycosidases and glycosyltransferases. Derivatives such as *N*-butyldeoxynojirimycin inhibit: (1) α-glucosidase, involved in the processing of N-linked glycoprotein chains; and (2) glucosylceramide transferase, which catalyses the first step in one of the biosynthetic pathways leading to glycosphingolipids and gangliosides.



nominal describing an approximate value assigned to some quantity as a guide to its real value (which may vary according to circumstances).

nomogram *or* **nomograph** any chart or diagram consisting of scaled lines and used for facilitating calculations, especially one consisting of three lines scaled for different related variables such that a straight line joining chosen values of two variables will intersect the third scale line at the related value of the third variable. **—nomography** *n.*; **nomographic** *adj.*

non+ 1 *prefix* denoting negation; absence of; opposite or reverse of; e.g. nonabsorbable, nonacylated, nonconductor, noncyclic, nonmetal, nonspecific. **2** *a variant form of* **nona+** *(sometimes before a vowel)*.

nona+ *or (sometimes before a vowel)* **non+** *comb. form* denoting nine, ninefold, nine times.

nonacosa+ *comb. form* denoting twenty-nine, twenty-nine fold, twenty-nine times.

nonacosane a linear C_{29} hydrocarbon, $CH_3–[CH_2]_{27}–CH_3$.

nonactin a neutral macrotetrolide antibiotic produced by several *Streptomyces* spp. It transports alkali cations through membranes with high selectivity for K^+, but also for NH_4^+. It is one of a related series including monactin, dinactin, and trinactin.

nonadeca+ *comb. form* denoting nineteen, nineteen fold, nineteen times.

nonaethyleneglycol mono-*n*-dodecyl ether a nonionic $C_{12}E_9$ detergent; *see* **$C_x E_y$**.

nonanoate *or* **pelargonoate** **1** the anion $CH_3–[CH_2]_7–COO^–$, derived from nonanoic acid (i.e. pelargonic acid). **2** any salt or ester of nonanoic acid.

nonanoyl *or* **pelargonoyl** *symbol*: Nno; the univalent acyl group $CH_3–[CH_2]_7–CO–$, derived from nonanoic acid (i.e. pelargonic acid).

nonaqueous lacking water; applied especially to solvents whether polar or nonpolar.

nonbonding electrons *an alternative name for* **lone pair**.

noncoded amino acid *or* **uncoded amino acid** any α-amino-acid residue occurring in a polypeptide or protein for which no codon exists: e.g., γ-carboxyglutamic acid, hydroxylysine, hydroxyproline, oxyproline. Residues of these amino acids are formed from residues of the corresponding coded amino acids by post-translational modification of the polypeptide chain.

noncoding region *or* **noncoding sequence** any segment of a nucleic-acid molecule for which there is no recognized gene product; it may sometimes play a structural role in the organization of the molecule. *See also* **intron**.

noncoding strand *or* **template strand** a term that is variously, and confusingly, applied to either of the two strands of genomic duplex DNA. It is now the term recommended for denoting the strand that is complementary in its sequence of bases to messenger RNA (mRNA) transcribed from the DNA; it thus functions as the template for synthesis of mRNA, which then contains the sequence present in the **coding strand** of duplex DNA (except for uracil in RNA serving in place of thymine in DNA). In some bacteria and viruses, alternate segments of both strands of duplex DNA may be noncoding. *Other names*: antisense DNA; antisense strand; complementary strand; minus strand; transcribing strand. *Compare* **complementary DNA**.

noncompetitive antagonism *(in pharmacology)* the phenomenon occurring when agonist and antagonist can be bound simultaneously, in which antagonist binding reduces or prevents the action of the agonist; e.g. channel block of the nicotinic receptor, or inhibition by adrenoceptor antagonists of the response to tyramine.

noncompetitive inhibition inhibition of an enzyme in which inhibition results from binding of the inhibitor at a different site on the enzyme surface from that at which the substrate binds, without interference with substrate binding.

nonconjugative plasmid any plasmid that cannot bring about transfer of DNA by **conjugation**.

nonconservative replication of DNA *or* **dispersive replication of DNA** *see* **replication of DNA**.

noncoupled solute translocation the translocation of a solute across a membrane that is not coupled to the translocation of another solute, in either the same or the opposite direction. *See* **facilitated diffusion**, **uniport**.

noncovalent describing an interaction between atoms and/or molecules that does not involve the formation of a covalent bond between them.

noncyclic electron flow *(in photosynthesis) see* **photophosphorylation**.

noncyclic photophosphorylation *see* **photophosphorylation**.

nondiffusible material material that is not diffusible in the restricted sense of its being incapable of passing through a diffusion barrier, especially through a semipermeable membrane used in dialysis. *Alternative terms recommended by IUPAC*: retentate, dialysis residue, or residue.

nondisjunction *(in genetics)* failure of a chromosome pair to separate at the first meiotic division or for two chromatids to separate at the second meiotic division, so that both daughter chromatids pass into the same daughter cell. Autosomal trisomies are thought to originate from fertilization of eggs with two daughter chromatids.

nondissymmetric *a term formerly used to describe* an achiral molecule that possesses an alternating axis of symmetry but that (unlike a symmetric molecule) lacks a simple axis of symmetry; the converse of **dissymmetric**. An important example is **citric acid**, which has a one-fold alternating axis but no simple axis; thus its pair of carboxymethyl groups on carbon-3 are not geometrically equivalent. *See also* **prochiral**.

nonelectrolyte any substance that is neither an electrolyte nor a conductor of electrons.

nonessential amino acid any amino acid that can be synthesized in the body in an amount corresponding to need, and hence for which there is not an absolute dietary requirement. The extent to which a particular amino acid is non-essential in any one species depends on the stage of development and physiological state of the subject. The following L-amino acids are non-essential for the maintenance of nitrogen equilibrium in an adult human: alanine, arginine, asparagine, aspartic acid, cysteine, glutamic acid, glutamine, glycine, histidine, hydroxyproline, proline, serine, and tyrosine. Arginine and histidine are, however, essential in growing children.

nonesterified fatty acid *abbr.*: NEFA; **1** *an alternative name for* **free fatty acid**. **2** *a collective term for* the total of free fatty acids in a sample, especially of blood.

nonheme iron *or (esp. Brit.)* **nonhaem iron** any iron in a biological sample or structure that is not chelated in heme groups. In nonheme-iron proteins, the iron is often present in iron–sulfur clusters.

nonhistone protein *or* **nonhistone chromosome protein** any member of a highly heterogeneous group of 10–150 kDa tissue- specific proteins associated with DNA in cell nuclei. They are thought to play a part in the control of gene expression. *See also* **high mobility group proteins**.

nonhomologous (of chromosomes or chromosome segments) not **homologous** (def. 4).

nonideal describing any gas or solution that does not behave like an ideal gas or ideal solution, respectively. **—nonideality** *n.*

Nonidet P-40 *the proprietary name for* a nonionic detergent, (octylphenoxy)-polyethoxyethanol, used for solubilizing membrane proteins. It is no longer commercially available but can be replaced with IGEPAL CA-630, which is chemically identical. *Compare* **Triton**.

non-insulin-dependent diabetes *an alternative name for* type 2 **diabetes mellitus**.

noninvasive **1** not **invasive**. **2** *(of a clinical investigative technique or procedure)* carried out without penetrating the skin.

nonionic having or yielding no ions; the term is used especially of **nonionic detergents**.

nonionic detergent any detergent whose molecules cannot ionize.

non-lactose-fermenter *a jargon term for* any genus, species, or strain of microorganism that does not ferment lactose.

nonmediated transport *an alternative name for* **unmediated transport**.

non-Newtonian fluid any fluid that does not conform to **Newton's law of viscosity**, i.e. one whose (coefficient of) viscosity is not independent of flow rate.

non-nucleoside reverse transcriptase inhibitor *abbr.*: NNRTI; an antiretroviral drug, used in AIDS therapy, that binds to the catalytic site of the HIV-1 reverse transcriptase, preventing RNA conversion to DNA. Owing to the rapid development of resistance, it is often used in combination with other drugs. NNRTIs have no activity against HIV-2. *Compare* **nucleoside reverse transcriptase inhibitor**.

nonoate A compound of structure $R_1R_2NN(O){=}NOR_3$, which releases nitric oxide in water. Different derivatives have different rates of NO release e.g. DETA NONOate, (*Z*)-1-[2-(2-aminoethyl)-*N*-(2-ammonioethyl)amino]diazel-1-ium-1,2-diolate.



nonorthologous gene displacement during evolution, the displacement of a particular gene by an unrelated (i.e. nonorthologous) but functionally analogous gene.

nonose any **aldose** having a chain of nine carbon atoms in the molecule.

nonoverlapping code *see* **overlapping code**.

nonpenetrance *(in genetics)* the lack of the expected phenotype in individuals who are heterozygous for an autosomal dominant gene.

nonpermissive restrictive; not **permissive**.

nonpermissive cell any cell that does not support infection by a particular lytic virus; in a small percentage of instances the virus may transform a nonpermissive cell.

nonpolar **1** lacking polarity. **2** *or* **apolar** *(of a chemical group or substance)* lacking a significant permanent dipole moment.

nonpolar bond **1** any covalent bond that is not appreciably polarized. **2** *(sometimes) an alternative term for* **hydrophobic interaction**.

nonpolar solvent *a loose term denoting* any solvent with low ionizing power and hence low solvating power.

nonproductive binding *or* **dystopic binding** the binding of a substrate in an unreactive mode at the active site of an enzyme, leading to the formation of a nonproductive, or **abortive complex**.

nonproductive complex *an alternative name for* **abortive complex**.

nonprotein amino acid any amino acid that does not naturally occur as a constituent residue of proteins. Over 200 such amino acids are known to be produced in higher plants; although they often contribute to the nitrogen pool of the plants, their specific function is unknown. Non-protein amino acids also occur in animals, but to much less extent, the most prominent examples being **argininosuccinate**, **citrulline**, and **ornithine**.

nonprotein nitrogen *abbr.*: NPN; the part of the nitrogen content of a substance (or fluid) that is not contained in the proteins present. The term is used especially of blood or serum, wherein urea accounts for about half the total NPN.

nonradioactive having no radioactivity; in practice the term is often used to refer to substances having a normal or natural nuclidic composition, ignoring any contribution from minimal proportions of naturally occurring radionuclides such as the carbon-14 content of natural organic materials.

nonradioactive labelling any method for coupling a distinctive and detectable molecular entity to a DNA, RNA, protein, or other molecule, that permits detection of this molecule by nonradioactive means. Such labelling might involve, for example, the introduction of haptens that can subsequently be detected by anti-hapten antibodies coupled to an enzyme that can be detected by colorimetric, fluorimetric, or chemiluminescent methods.

nonradioactive tracer *(sometimes)* a labelled substance that can be detected and estimated by virtue of some property other than radioactivity (such as colour, fluorescence, or a difference in stable-isotope ratio).

nonreducing end the end of a linear oligosaccharide or polysaccharide that does not carry a potential hemiacetal or hemiketal (i.e. reducing) group.

nonribosomal peptide synthesis *abbr.*: NRPS; the type of peptide synthesis employed by actinomycetes, bacilli, and filamentous fungi in manufacturing complex peptide antibiotics, such as cyclosporin, gramicidin, erythromycin, and vancomycin. No mRNA, tRNA, or ribosomes are required. Instead, a multimodular nonribosomal peptide synthetase determines the composition and sequence of the peptide to be synthesized.

nonsecretor *see* **secretor gene**.

nonselectively labelled describing a labelled compound in which the position(s) and the number of the labelling nuclide(s) are both undefined.

nonsense codon *or* **nonsense triplet** any one of the nucleotide triplets UAA (ochre), UAG (amber), and UGA (opal) that signal termination of translation and release of the polypeptide chain from the site of synthesis. A codon that is nonsense in one strain of an organism may nevertheless code for an amino acid in another strain containing an appropriate suppressor gene (*see* **nonsense suppressor**). UGA sometimes codes for selenocysteine and, in mitochondria, for Trp. In mitochondria AGA is a nonsense codon rather than UGA. *Compare* **missense codon**.

nonsense-mediated alternative splicing *abbr.*: NAS; a form of alternative splicing of a pre-mRNA containing a nonsense(i.e. stop) mutation in an internal exon, in which alternative splicing occurs so as to produce a stable mRNA that lacks the mutation. *Compare* **nonsense-mediated decay**.

nonsense-mediated decay the selective degradation in cytoplasm of eukaryotic mRNA that contains a premature stop codon. This reduces the production of abnormally truncated and potentially harmful proteins. The decay is triggered by a surveillance complex. *See* **mRNA surveillance**.

nonsense mutation any mutation in a DNA molecule that results in an alteration of a sense codon to a **nonsense codon** in the mRNA transcript, the translation of which leads to the formation of a truncated polypeptide gene product. *Compare* **missense mutation**.

nonsense suppressor any tRNA molecule that is able to insert an amino-acid residue into a growing polypeptide chain at a nonsense codon in an mRNA molecule. It has an altered anticodon, produced as a result of a **suppressor mutation**.

nonshivering thermogenesis *abbr.*: NST; a mechanism of rapid heat production in response to cold that does not involve muscular contractions. It is important during the neonatal period, during cold adaptation of a number of small mammals, and during the arousal period of animals that hibernate. Heat is produced in the mitochondria of brown adipose tissue in response to the presence in the inner mitochondrial membrane of a specific 32 kDa protein. This protein uncouples the respiratory chain and is inducible by norepinephrine. It is known as **brown fat uncoupling protein**.

nonspecific serine/threonine protein kinase EC 2.7.11.1 a serine/threonine kinase that catalyses phosphorylation of several proteins, using ATP; other names glycogen synthase *a* kinase; cAMP-dependent protein kinase; calcium-dependent protein kinase C. It is activated by phosphorylation by cyclic AMP-dependent protein kinase.

nonsuppressible insulin-like activity *abbr.*: NSILA; **insulin-like activity** that is not suppressible by specific antisera to insulin. The activity is now attributed to **insulin-like growth factors**.

nonsynonymous mutation a nucleotide substitution in a protein-coding gene that results in an amino acid substitution in the translation product. The ratio of nonsynonymous to synonymous substitutions may be used to detect positive Darwinian selection.

nontranscribing strand (of duplex DNA) *see* **coding strand**.

nonulose any **ketose** having a chain of nine carbon atoms in the molecule.

nonyl *symbol*: Nn; the alkyl group $CH_3[CH_2]_7CH_2$–, derived from nonane.

nonyl glucoside *n*-nonyl-*β*-D-glucopyranoside; a mild, nonionic detergent, CMC 6.5 mm. *Compare* **heptyl glucoside**, **hexyl glucoside**, **octyl glucoside**.

Noonan syndrome *or* **cardiofaciocutaneous syndrome** an autosomal dominant disorder in which cardiac anomalies are associated with short stature, facial abnormalitiy, and webbed neck. It is associated with mutations in PTNP11 (protein tyrosine phosphatase 11). [After Jacqueline Noonan (1921–), US cardiologist.]

nopaline *N*-(1-carboxy-4-guanidinobutyl)glutamic acid; N^2- (1,3-dicarboxypropyl)arginine; a rare amino-acid derivative that is produced by a certain type of crown-gall tissue (*see* **crown-gall disease**); one of a group of **opines**. The genes responsible for the synthesis of nopaline are part of the **T-DNA** from a **Ti-plasmid**.



nopalinic acid *or* **ornaline** *N*-(1-carboxy-4-aminobutyl)glutamic acid; N^2-(1,3-dicarboxypropyl)ornithine; one of a group of **opines** found in plant tumours occurring in **crown-gall disease**.



nopalinic acid

nor+ *prefix (in chemical nomenclature)* denoting **1** replacement of one side-chain methyl group by a hydrogen atom, e.g. norepinephrine, 19-nortestosterone. Replacement of two or three methyl groups is denoted by the prefix dinor+ or trinor+, respectively (in terpene nomenclature the prefix nor+ formerly denoted removal of all replaceable methyl groups; hence, e.g., 8,9,10-trinorbornane was formerly known as norbornane). **2** elimination of one methylene group from a chain or ring of carbon atoms; it is used especially for steroids, e.g. 23-nor-5*β*-cholanoic acid, A-nor-5*β*-androstane, norophthalmic acid. Elimination of two or three methylene groups is denoted by the prefix dinor+ or trinor+, respectively. **3** an isomer with an unbranched hydrocarbon chain, e.g. norleucine, norvaline; use discouraged.

noradrenaline *an alternative name for* **norepinephrine**.

noradrenergic *(sometimes)* **1** an (adrenergic) nerve cell that itself liberates noradrenaline (i.e. **norepinephrine**). **2** a cell or receptor that is stimulated preferentially by norepinephrine. **—noradrenergically** *adv.*

norepinephrine *or* **noradrenaline** *or* **levarterenol** (–)-(3,4-dihydroxyphenyl)-2-aminoethanol; a hormone secreted by the adrenal medulla, and a neurotransmitter in the sympathetic peripheral nervous system and in some tracts in the central nervous system. It is also the demethylated biosynthetic precursor of epinephrine in the adrenal medulla. It has a powerful lipolytic action, mediated by cyclic AMP, and is an agonist for **adrenoceptors**, inducing arteriolar constriction and raised systolic and diastolic arterial blood pressure.



R-(–)-enantiomer

norepinephrine transporter *or* **noradrenaline transporter** an integral membrane protein of neuronal synapses that contains 12 transmembrane segments and is responsible for reuptake of most of the norepinephrine released at synapses. It is inhibited by cocaine, amphetamines, and tricyclic antidepressants, all of which cause features of **orthostatic intolerance**.

Norit *the proprietary name for* a commercially produced activated carbon, useful as an adsorbent.

norleucine *symbol*: Ahx *or (formerly)* Nle; 2-aminohexanoic acid; a non-protein *α*-amino acid. *See also* **nor+** (def. 3).

norm+ *a variant form of* **normo+** *(before a vowel)*.

normal **1** not deviating from an established pattern; approximating to an average, or within the usual range (of values). **2** *(in organic chemistry) symbol*: n; (of a solution) containing one **equivalent** (def. 4) of a specified substance (of specified equivalence factor) in one litre of solution. Use now not recommended. **3** *(in organic chemistry)* a chemical compound that has an unbranched chain of carbon atoms; the names of such compounds may be prefixed by '*n*', as in *n*-butane. However, this is not the currently recommended terminology. **4** *(in biology)* not diseased or not having been exposed to an experimental procedure. **5** *(in mathematics)* (of a straight line or plane) at a right angle (to another straight line or plane).

normal distribution *or* **Gaussian distribution** any continuous frequency distribution of events, observations, etc. characterized by a symmetrical bell-shaped curve of the frequency of *x*, f(*x*), against the value of *x*, that is represented by the equation:

$$f(x) = [1/\sigma(2\pi)^{0.5}]e^{-(x-\mu)^2/2\sigma^2}$$

where μ is the mean and σ is the standard deviation.

normality *(in chemistry)* the chemical concentration of a solution expressed as the number of **equivalents** (def. 4) of a specified substance (of specified equivalence factor) per litre. Use now not recommended.

normalize *or (esp Brit.)* **normalise** **1** (*for a relational database*) to organize data into tables in such a way as to minimize duplication and hence increase efficiency. **2** (*for a probability distribution*) to divide all probabilities by a constant factor so that their sum over all possible alternatives is 1. **3** (*for microarray data*) to adjust the measured intensities to correct for experimental bias. **4** (*for a cDNA library*) to generate a library such that all the genes in the library are represented at the same frequency. **–normalized** *adj.*; **–normalization** *n.*

normalized library *see* **normalize**.

normal range *(in clinical chemistry)* the range of values of a particular characteristic within which 95 percent of observations made on presumed normal healthy individuals fall. It is useful as a reference in the investigation of disease.

normal saline *an alternative and less suitable name for* **physiological saline**.

normal solution a solution in which the amount-of-substance concentration of the **equivalent** (def. 3) of the reagent is one mole per litre; the equivalence factor of the reagent should be specified. Not now recommended. *See also* **normal** (def. 2).

normal temperature and pressure *abbr.*: NTP *or* N.T.P. *or* ntp; *a former term for* **standard temperature and pressure**.

normetadrenaline *an alternative name for* **normetanephrine**.

normetanephrine *or* **normetadrenaline** 3-*O*-methylnorepinephrine; an inactive metabolite of norepinephrine produced by the action of **catechol *O*-methyltransferase**.

normo+ *or (before a vowel)* **norm+** *comb. form* denoting normal; used especially in biology and medicine to indicate within the normal range. *See also* **eu+**.

normoblast a normal precursor cell to an erythrocyte, characterized by condensation of the nucleus into a homogeneous densely staining body. Normoblasts are normally found only in hemopoietic tissue. **—normoblastic** *adj.*

normocyte an erythrocyte of normal colour, shape, and size. **—normocytic** *adj.*

normoglycemia *or (esp. Brit.)* **normoglycaemia** *an alternative term for* **euglycemia**. **—normoglycemic** *or (esp. Brit.)* **normoglycaemic** *adj.*

normotensive having an arterial blood pressure within the normal range for the particular group to which the subject belongs.

Norrie disease *see* **Norrin**.

Norrin the protein (133 amino acids) encoded by the gene associated with the X-chromosome-linked Norrie disease. The human protein is highly expressed in retina, cerebellum, and olfactory epithelia, and shares 94% sequence identity with the mouse homologue. The secreted portion (residues 25–133) contains a cysteine-rich C-terminal domain. Numerous mutations result in congenital blindness, frequently associated with mental retardation and deafness, and occasionally with hypogonadism and microcephaly.

norsteroid any steroid that, relative to a parent compound, lacks either one axial methyl group or one methylene group in a side chain, or that has one ring contracted by one carbon atom. *See also* **nor+**.

Northern blotting *or* **Northern transfer** any **blotting** in which the primary electrophoresis is performed with RNA, which is subsequently hybridized to radioactive DNA. The term was coined to distinguish the process from **Southern blotting**, which is performed with DNA.

norvaline *symbol*: Avl (from aminovaleric) *or* Ape (from aminopentanoic) *or (formerly)* Nva; 2-aminovaleric acid (now the preferred trivial name); 2-aminopentanoic acid; a non-protein *α*-amino acid. *See also* **nor+** (def. 3).

NOS *abbr. for* **nitric-oxide synthase** .

noso+ *or (before a vowel)* **nos+** *comb. form* indicating disease.

nosocomial **1** associated with a hospital. **2** a disorder (e.g. an infection) acquired during a hospital stay that is unrelated to the primary condition of the patient. A nosocomial infection can refer to hospital workers as well.

nosogenesis *an alternative term for* **pathogenesis**. **—nosogenic** *or* **nosogenetic** *adj.*

nosography a written systematic classification and description of diseases.

nosology the branch of medicine dealing with the classification of diseases.

notatin *a name sometimes still used for* glucose oxidase. Notatin was so called because it is produced in considerable quantity by some microfungi, e.g. *Penicillium notatum*.

notch a gene, found in *Drosophila*, that encodes a protein essential for the proper differentiation of ectoderm. Expression of the *notch* gene is under the control of neurogenic genes. The gene product is a transmembrane protein (2703 amino acids) with 36 EGF-like repeats.

notexin a **phospholipase** A_2 (EC 3.1.1.4) from snake venom that acts as a presynaptic neurotoxin. The reaction is Ca^{2+}-dependent.

***Not*I** a type 2 **restriction endonuclease**; recognition sequence: GC↑GGCCGC.

novel chemical entity *abbr.*: NCE; a molecule with a novel structure that is newly identified as a potential drug (and hence has not been described before in the literature).

noviose 6-deoxy-5-*C*-methyl-L-*lyxo*-hexose 4-methyl ether; a carbohydrate component of **novobiocin**.



novobiocin an antibiotic produced by *Streptomyces spheroides*, *S. niveus*, and certain other species; it is active against Gram-positive and some Gram-negative bacteria. In susceptible organisms it is a specific inhibitor of **(DNA) gyrase**, interacting with the B subunit, and thereby interfering with DNA synthesis.



noxa (*pl.* **noxae**) anything that is harmful to living organisms. **—noxious** *adj.*

Np *symbol for* neptunium.

NP *abbr. for* **1 neuropilin**. **2** nitrophorin.

NP-40 polyethyleneglycol-*p*-isooctylphenyl ether; a polyoxyethylene nonionic detergent, CMC 0.05–0.3 mm. *Proprietary name*: Nonidet P40.

NPAS2 *abbr. for* neuronal PAS domain protein 2; a basic helix-loop-helix transcription factor that has two **PAS domains**, each of which contains a heme group. It forms a dimer with **BMAL1** through which it binds to a specific DNA motif and directs transcription of over a hundred genes, including those for **period** and cryptochrome proteins. NPAS2 is homologous with **clock** and like it controls circadian activity and is regulated by the redox state of NAD(P). It has the same role in the forebrain as clock has in the hypothalamus. CO binds the heme of NPAS2 and prevents it from dimerizing with BMAL1.

NPC *abbr. for* neural precursor cell (*see* **Nedd**).

NPN *abbr. for* nonprotein nitrogen.

NPY *abbr. for* neuropeptide Y.

Nramp1 *abbr. for* natural resistance-associated protein 1; a transmembrane protein characteristic of macrophages and associated with natural resistance to intracellular parasites (e.g. *Leishmania*, some mycobacteria) in mice. The human homologue is **NRAMP1**, in which structural variation is associated with susceptibility to pulmonary tuberculosis and possibly leprosy. NRAMP1 is homologous with **NRAMP2**, a proton-coupled divalent-metal transporter for Fe^{2+} in the brush border of the proximal small intestine. Mutations in Nramp2 cause microcytic anemia in mice and the Belgrade rat (which is anemic). Mutation in human NRAMP2 causes hemochromatosis in a subset of such patients.

nrdb *abbr. for* nonredundant database; *see* **composite database**.

N repeat *an alternative name for* **asparagine repeat**.

nRNA *abbr. for* nuclear RNA.

NR protein *abbr. for* nitrogen regulatory protein.

NRPS *abbr. for* nonribosomal peptide synthesis.

NRSF *abbr. for* neuronal restricted silencing factor. *See* **REST**.

NRTI *abbr. for* nucleoside reverse transcriptase inhibitor.

***Nru*I** a type 2 **restriction endonuclease**; recognition sequence: TCG↑CGA.

ns *symbol for* nanosecond (i.e. 10^{-9} s).

NSF *abbr. for* National Science Foundation (of the USA).

NSF protein *abbr. for N*-ethylmaleimide-sensitive fusion protein.

NSILA *abbr. for* nonsuppressible insulin-like activity.

NS-1 myeloma cells a cell line used for the production of monoclonal antibodies by fusion with splenocytes. NS-1 cells are deficient in the gene for **HGPRT** (HPRT) and are killed in the presence of aminopterin. In hybridomas the lack of HGPRT in NS-1 cells is genetically complemented by the gene from mouse splenocytes, and as a consequence they survive selection in culture medium containing **HAT**.

NSP *abbr. for N*-succinimidyl propionate, a propionylating agent.



NST *abbr. for* nonshivering thermogenesis.

NT *abbr. for* neurotrophin.

N terminus *or sometimes* **N terminal** the end of any peptide chain in any (poly)peptide or protein at which the 2-amino function of a constituent α-amino acid (or the 2-imino function of an α-imino carboxylic acid) is not attached in peptide linkage to another amino-acid residue. This function may bear an acyl group or other function in non-peptide linkage; when it is a free amino group (and also protonated and positively charged at neutral or acidic pH values), the chain end may then be alternatively termed the **amino terminus** (*or* NH_2 terminus) or **amino terminal** (*or* NH_2 terminal). However, 'amino terminus' is often used loosely for any N terminus. *Compare* **C terminus**. **—N-terminal** *adj.*

NTP **1** *abbr. for* any (unknown or unspecified) nucleoside (5′-) triphosphate. **2** *(in clinical biochemistry) abbr. for* 5′-nucleotidase (EC 3.1.3.5). **3** *or* N.T.P. *or* ntp; *abbr. for* normal temperature and pressure; stp (i.e. standard temperature and pressure) now used.

NTPase *abbr. for* nucleoside triphosphatase.

NTP polymerase *see* **polynucleotide adenylyltransferase**.

nu *symbol*: ν (lower case) *or* N (upper case); the thirteenth letter of the Greek alphabet. For uses *see* **Appendix A**.

nu body *or* **ν body** *or* **deoxyribosome** a type of spheroid particle seen on electron-microscopic examination of chromatin; now thought to be the same as a **nucleosome**.

Nuc *symbol for* an undetermined, unidentified, or unspecified nucleoside residue; alternative to N.

nucle+ *a variant for of* **nucleo+** *(before a vowel)*.

nuclear **1** of, pertaining to, or contained within the nucleus of a cell. **2** of, pertaining to, or concerning an atomic nucleus. **3** of, pertaining to, or operated by energy derived from fission or fusion of atomic nuclei.

nuclear area *an alternative name for* **nucleoid** (def. 2).

nuclear assembly protein 1 *see* **NAP1**.

nuclear atom *or* **central atom** (of a coordination entity) the atom to which all other atoms are directly attached.

nuclear body (*abbr*.: NB) *or* **PML nuclear body** *or* **PML oncogenetic domain** a spatial domain or subcompartment in the mammalian nucleus that contains **PML** bound to several other proteins. It becomes disrupted in acute promyelocytic leukemia, associated with formation of the PML-RARα fusion protein, and by some viruses, neoplasia, and inflammation. There is some evidence that nuclear bodies are sites for protein degradation.

nuclear division *or* **nuclear fission** the division of the nucleus of a cell, especially by **mitosis** or **meiosis**.

nuclear emulsion a fine-grained photographic emulsion designed for recording the tracks of subatomic particles within it.

nuclear envelope *or* **nuclear membrane** the membrane that surrounds the nucleus of a eukaryotic cell. It is a double membrane composed of two lipid bilayers separated by a gap of width 20–40 nm (the perinuclear space). The outer nuclear membrane is continuous with the endoplasmic reticulum of the cell and is sometimes studded with ribosomes. At specialized regions (**nuclear pores**) the outer nuclear membrane is connected to the inner nuclear membrane.

nuclear filament-related protein *abbr*.: NUF1; an essential component of the nucleoskeleton, with a role in cross-linking filaments or anchoring other molecules.

nuclear fission **1** *(in biology) an alternative term for* **nuclear division**. **2** *(in physics) see* **fission** (def. 1).

nuclear fraction *an operational term for* the material deposited by low-speed centrifugation of a homogenate of eukaryotic cells or tissue. It consists predominantly of nuclei together with unbroken cells.

nuclear fusion **1** *(in biology)* the **fusion** (def. 3) of the nuclei of a heterokaryon leading to the formation of a hybrid cell. **2** *(in physics) see* **fusion** (def. 4).

nuclear *g*-factor *symbol* g_N or nuclear g-value, a parameter that defines the energy of interaction of a nuclear spin with an applied magnetic field.

nuclear *g*-value alternative term for nuclear g-factor. Compare **G-value**.

nuclear isomer *(in physics) see* **isomer** (def. 2).

nuclear lamina the electron-dense layer lying on the nucleoplasmic side of the inner membrane of a cell nucleus. The polypeptides of the lamina are thought to be concerned in the dissolution of the nuclear envelope and its re-formation during mitosis.

nuclear localization signal *abbr*.: NLS; a sequence of amino acids seven to nine residues long within a protein, normally at sites away from the N or C terminus, that acts as a signal for the localization of the protein within the nucleus. Characteristically, NLSs are rich in basic residues, but include also one or more prolines.

nuclear magnetic resonance *abbr*.: NMR *or* nmr; the phenomenon that occurs when atomic nuclei that possess a magnetic moment are placed in a constant magnetic field of high intensity and are simultaneously exposed to electromagnetic radiation of an appropriate frequency in the radiofrequency region, whereby the nuclei are caused to change from a low-energy to a high-energy state with the absorption of energy. Nuclei that display this phenomenon include those of the nuclides protium, tritium, carbon-13, nitrogen-15, fluorine-19, and phosphorus-31; all these nuclei have nonzero spins and, therefore, magnetic moments. *See also* **nuclear magnetic resonance spectroscopy**.

nuclear magnetic resonance spectroscopy *abbr*.: NMR spectroscopy *or* nmr spectroscopy; absorption spectroscopy in the radiofrequency region based on the phenomenon of **nuclear magnetic resonance**. Unless otherwise qualified the term usually denotes nuclear magnetic resonance spectroscopy of protium atoms, also known as proton magnetic resonance spectroscopy (*abbr*.: pmr spectroscopy). Nuclei of the same nuclide in different chemical environments give rise to distinguishable spectral lines, the positions, intensities, widths, and multiplicities of which give considerable information about the structure of complicated molecules containing such nuclei. The technique is also useful for determination of the concentrations of particular substances in complex environments, including that of an intact mammal. *Compare* **electron spin resonance spectroscopy**, **magnetic resonance imaging**.

nuclear magneton *symbol*: μ_N; a quantity of magnetic moment, given by $\mu_N = eh/4\pi m_p = (m_e/m_p)\mu_B$, where e is the elementary charge, h is the Planck constant, m_e and m_p are the rest masses of an electron and a proton respectively, and μ_B is the **Bohr magneton**. It is a fundamental physical constant, of value 5.050 786 6(17) × 10^{-27} J T^{-1}.

nuclear matrin *see* **matrin**.

nuclear matrix *or* **nuclear scaffold** the insoluble protein material left in the nucleus after a series of extraction procedures.

nuclear medicine the branch of medicine concerned with the use of radioactive nuclides for diagnosis or treatment of disease, or for medical research.

nuclear membrane *an alternative name for* **nuclear envelope**.

nuclear mitotic apparatus protein *abbr*.: NuMA; one of a family of abundant coiled-coil nuclear proteins located in the nucleus during interphase, but rapidly redistributes to the developing spindle poles when the nuclear envelope disassembles in prometaphase.

nuclear Overhauser effect *or* **nuclear Overhauser enhancement** *abbr*.: NOE; in nuclear magnetic resonance spectroscopy, a phenomenon in which saturation of the resonance of a nucleus or electron by the simultaneous application of a radiofrequency field causes, under appropriate conditions, a considerable increase in the polarization of the interacting nuclei and hence in the NMR signal produced.

nuclear Overhauser effect spectroscopy *abbr*.: NOESY; in **nuclear magnetic resonance spectroscopy** advantage can be taken of the fact that the energy states of the spins of two nuclei subject to the **nuclear Overhauser effect** (NOE) are slightly perturbed by the mutual dipolar coupling (the effects of J-coupling are ignored). A perturbation of the populations of the states of one of the spins will lead to a transfer of the populations between the upper and lower energy states of the second spin, thereby modifying the resonance intensity. The NOE can be either positive or negative depending on the nuclei involved and the rapidity of the relative motions of the two spins. The strength of the dipolar coupling is distance dependent. Thus measurements of the NOE between two nuclei can lead to the estimation of the distance between them. Conversely, if the distance between the two nuclei is fixed (e.g. in a bond), then the NOE measurement can yield an indication of the dynamic motions in the molecule. Two-dimensional spectroscopy, known as 2D NOESY, is used to elucidate dipolar coupling networks present in complex biomolecules, using the NOEs between individual ^{1}H nuclei in the molecule. The network of NOEs obtained provides a basis for the determination of the three-dimensional structure in solution. Applications include the structures of small proteins and nucleic acids as well as protein–drug and protein–nucleic acid complexes.

nuclear pore any opening in the **nuclear envelope** of a eukaryotic cell, where the inner and outer nuclear membranes are joined. The nuclear pores are the central feature of a complex in higher eukaryotes and are estimated to contain about 100 different polypeptides. The complex constitutes a diffusion channel about 9 nm in diameter through which proteins enter the nucleus and ribonucleoproteins leave. Small proteins enter freely but the entry of larger proteins is controlled by their containing one or more clusters of basic amino acids which comprise the nuclear localization sequence (*abbr*.: NLS). This involves binding to the nuclear envelope, followed by energy-dependent transit through the complex. Four soluble proteins have been shown to assist in the process: karyopherin α, *other name*: importin α (the NLS receptor), karyopherin β, *other name*: importin β (which mediates binding to the nuclear pore complex), a small guanosine triphosphatase (*abbr*.: GTPase), Ran, and p10/NTF2 (a protein that may coordinate the Ran-dependent association and disassociation reaction). Ran cycles between a GDP- and GTP-bound form, which might account for the consumption of energy for the protein import. The exchange factor for Ran (RCC1) is located inside the nucleus whereas its GTPase-activating protein (Rab-GAP1 or RAN1) is cytoplasmic. Much less is known about the mechanism whereby the export of ribonucleoprotein is controlled. RNA itself does not seem to leave the nucleus.

nuclear quadrupole moment a parameter, given the symbol eQ, describing the effective shape of the ellipsoid of electric charge distribution of an atomic nucleus with spin greater than ½. The nuclear electric quadrupole interacts with the electric field gradient eq at the nucleus, and its influence is observed in NMR, ENDOR, and Mössbauer spectroscopy.

nuclear receptor any intracellular protein that is specific for a ligand and elicits a response by binding to nuclear DNA without mediation of a second messenger. Some 48 are encoded in the human genome. They all contain a poorly conserved ligand-independent activation domain, a highly conserved DNA-binding domain that contains two zinc finger motifs, and a ligand-specific activation domain. They fall into three classes: (1) classic endocrine receptors (with high affinity for glucocorticoid, mineralocorticoid, steroid sex hormones, or thyroid hormones, and for 1,25-dihydroxy vitamin D); (2) adopted orphan receptors (e.g. those for retinoic acid and bile acids); and (3) orphan receptors that have no known physiological ligand.

nuclear remodelling factor *see* **NURF**.

nuclear rest *see* **nucleoid** (def. 4).

nuclear run-on *or* **nuclear run-off** a method in which nuclei isolated from cells are allowed to complete transcription of genes in the presence of radioactively labelled ribonucleotide triphosphates. Specific transcripts can be detected, and quantified, by hybridization with immobilized cDNA probes by dot blotting.

nuclear transformation transformation of a nuclide; the change of one nuclide into another.

nuclease any enzyme within subclass EC3.1, that catalyses the hydrolysis of ester linkages in nucleic acids. Nucleases with sugar specificity are referred to as ribonucleases or deoxyribonucleases; **endonucleases** create internal breaks, while 5′- and 3′-**exonucleases** remove nucleotide residues from the indicated end. Some nucleases are specific for double- or single-stranded nucleic acids.

nucleate 1 *or* **nucleated** possessing a nucleus. **2** to form, to act as, or to provide with, a nucleus or nuclei. **3** any salt of a nucleic acid.

nucleation 1 the act or process of nucleating or forming a nucleus. **2** *(in chemistry)* **a** the aggregation of molecules to form a polymer or a new phase within a medium. **b** (*also known as* **seeding**) the addition of a small quantity of finely divided crystalline material to a supersaturated solution in order to promote crystallization.

nuclei the plural of **nucleus**.

nucleic acid *abbr.*: NA; any single- or double-stranded polynucleotide of molar mass in the range 20 kDa to 40 GDa or more. Nucleic acids are either **deoxyribonucleic acids** (DNA) or **ribonucleic acids** (RNA). The phosphoric residue linking any constituent mononucleotide residue to the next bears one free hydroxyl group, which is weakly acidic. They are universal constituents of living matter and are concerned with the storage, transmission, and transfer of genetic information.

nucleics *an informal collective term sometimes used for* nucleotides, nucleosides, and nucleobases, whether constituents of nucleic acids or compounds of low M_r, and including their metabolic relatives and synthetic analogues.

nuclein the name given by J. F. Miescher (1844–95) to an unusual phosphorus-containing material that he isolated from the nuclei of pus cells, now known to have been **nucleoprotein**.

nucleinase *a name once proposed to designate* the enzymes now known as **nucleases**.

nucleo+ *or (before a vowel)* **nucle+** *comb. form* denoting **1** nucleus or nuclear. **2** nucleic acid.

nucleobase any nitrogenous base that is a constituent of a nucleoside, nucleotide, or nucleic acid.

nucleobindin a DNA-binding protein containing a signal peptide, leucine zipper, and basic amino-acid-rich regions. It was derived from a cell line from the lupus erythematosus-prone mouse MRL/T.

nucleocapsid the structure within a virus that comprises the proteinaceous capsid and the genomic nucleic acid. In enveloped viruses the nucleocapsid is surrounded by an envelope.

nucleocidin 4′-*C*-fluoroadenosine 5′-sulfamate; an analogue of adenylate produced by *Streptomyces calvus*, and the first naturally occurring derivative of a fluorosugar to be described. It has antibiotic activity against trypanosomes and inhibits translation in both eukaryotic and prokaryotic systems.

nucleocytoplasmic (of a structure or process) occurring between the nucleus and the cytoplasm; (of a property) relating the nucleus to the cytoplasm.

nucleodisome a structure consisting of two **nucleosomes** and isolable under certain conditions from some forms of chromatin.

nucleohistone any nucleoprotein consisting of DNA and histone(s).

nucleoid 1 resembling a nucleus. **2** the part or parts of a prokaryotic cell containing the genome and functionally equivalent to the nucleus of a eukaryotic cell. The meaning is sometimes extended to include the electron-dense inner zone observable in certain viruses. *Other names*: bacterial nucleus; chromatinic body; karyoid; nuclear area; nuclear body; nucleoid body; prokaryon. **3** the nucleus-like structure liberated from a eukaryotic cell by mild lysis. It contains histone-free supercoiled DNA within a flexible cage of RNA and protein. **4** *or* **nuclear rest** the nuclear residue sometimes observable in an erythrocyte. **5** the very dense core of a **microbody**.

nucleolar DNA *or* **ribosomal DNA** the DNA comprising the **nucleolar organizer(s)**.

nucleolar organizer *or* **nucleolus organizer** the portion of the genome of a eukaryotic cell that is associated with the **nucleolus** and contains the genes from which 45S ribosomal-precursor RNA is transcribed.

nucleolar phosphoprotein B23 *or* **nucleophosmin** *or* **numatrin** a monomeric, or, under some conditions, disulfide-linked dimeric, nucleolar protein that binds to single-stranded nucleic acids, and may be bound to rRNA in the nucleolus.

nucleolin *or* **protein C23** the major nucleolar protein of growing eukaryotic cells believed to function in pre-rRNA processing and ribosome assembly. It is a phosphoprotein found associated with intranucleolar chromatin and peri-ribosomal particles.

nucleolus (*pl.* **nucleoli**) a small, dense body one or more of which are present in the nucleus of eukaryotic cells. It is rich in RNA and protein, is not bounded by a limiting membrane, and is not seen during mitosis. Its prime function is the transcription of the nucleolar DNA into 45S ribosomal-precursor RNA, the processing of this RNA into 5.8S, 18S, and 28S components of ribosomal RNA, and the association of these components with 5S RNA and proteins synthesized outside the nucleolus. This association results in the formation of ribonucleoprotein precursors; these pass into the cytoplasm and mature into the 40S and 60S subunits of the ribosome. —**nucleolar** *adj.*

nucleolytic capable of causing hydrolysis of nucleic acid.

nucleon a neutron or a proton.

nucleonics the branch of physics concerned with the practical applications of nuclear phenomena.

nucleon number *or* **mass number** *symbol*: A; a dimensionless physical quantity, having an integral value for any given nuclide, equal to the total number of nucleons (i.e. protons and neutrons) contained in the nucleus of an atom of the nuclide; it also is the integer nearest to the numerical value of the relative atomic mass of that nuclide and is equal to the arithmetical sum of the **neutron number**, N, of the nuclide and the **proton number**, Z, of the relevant chemical element: i.e. $A = N + Z$. The nucleon number may be attached to the symbol for the chemical element as a left superscript, or to the name of the element as a suffix; e.g. ^{14}C, or carbon-14.

nucleophile or **nucleophilic reagent** any reagent that is preferentially attracted to a region of low electron density in a chemical reaction. *Compare* **electrophile**.

nucleophilic 1 of, pertaining to, or being a **nucleophile**; having or involving an affinity for regions of low electron density in a chemical reactant. **2** describing a chemical reaction in which a nucleophilic reagent participates.

nucleophilic catalysis catalysis by a **Lewis base**, which donates an electron pair to the reactant.

nucleophilic displacement *an alternative term for* **nucleophilic substitution reaction**.

nucleophilicity the relative reactivity of a nucleophile, measured in terms of the relative rate constants of different nucleophiles towards a common reactant.

nucleophilic reagent *an alternative term for* **nucleophile**.

nucleophilic substitution reaction *or* **nucleophilic displacement** a chemical reaction in which a **nucleophile** effects heterolytic substitution in another reactant, both bonding electrons being supplied by the nucleophile.

nucleophosmin *see* **nucleolar phosphoprotein B23**.

nucleoplasm all the protoplasm contained within the nuclear envelope of a living cell. —**nucleoplasmic** *adj.*

nucleoplasmin a heat-stable acidic protein present in the nucleoplasm of many cell types. It forms complexes with histones, and functions in the assembly of nucleosomes in the formation of chromatin.

nucleoporin any protein that is a component of the nuclear pore complex. *See* **nuclear pore**.

nucleoprotamine any nucleoprotein consisting of DNA and protamine(s).

nucleoprotein any complex of a protein with a deoxyribonucleic acid (**deoxyribonucleoprotein**) or a ribonucleic acid (**ribonucleoprotein**).

nucleosidase any enzyme that hydrolyses the *N*-glycosidic bond in a **nucleoside** (or in a nucleotide or some other derivative of a nucleoside). Such enzymes are classified within the sub-subclass EC 3.2.2, i.e. enzymes that hydrolyse *N*-glycosyl compounds.

nucleoside 1 *symbol* (for a residue of an undetermined, unknown, or unspecified nucleoside): N *or* Nuc; any **glycosylamine** that is a component of a nucleic acid and that consists of a nitrogenous base linked either to *β*-D-ribofuranose (forming a ribonucleoside, as in RNA) or to 2-deoxy-*β*-D-ribofuranose (forming a deoxyribonucleoside, as in DNA). The base is either a purine (linked at N-9) or a pyrimidine (linked at N-1, or in the case of pseudouridine at C-5). **2** any compound that is a glycosylated heterocyclic nitrogenous base; the glycose moiety commonly is ribose, but is sometimes a different sugar or a modified sugar; e.g. cytarabine (1-*β*-D-arabinofuranosylcytosine).

nucleoside antibiotic any of a group of **nucleosides** (def. 2) that are not components of nucleic acids but are produced by various microorganisms and fungi (especially *Streptomyces* spp.), and have antibiotic activity. They contain unusual nitrogenous bases and/or unusual sugars (or sugar derivatives), and may also contain one or more additional components. Examples include **cordycepin**, **nucleocidin**, **puromycin**, and **showdomycin**.

nucleoside cyclic phosphate *or* **cyclic nucleotide** any nucleotide that consists of a nucleoside doubly esterified with one [ortho]phosphate molecule on its glycose moiety (usually at the 3′ and 5′positions, but sometimes at the 2′- and 3′-positions) e.g. cyclic AMP.

nucleoside diphosphatase EC 3.6.1.6; *systematic name*: nucleoside diphosphatase phosphohydrolase; an unspecific enzyme that hydrolyses a number of nucleoside diphosphates to a nucleoside monophosphate and orthophosphate. Substrates include IDP, GDP, UDP, and D-ribose 5-phosphate. There is also the more specific **guanosine-diphosphatase**, EC 3.6.1.42; *systematic name*: GDP phosphohydrolase, which hydrolyses guanosine diphosphate to guanylic acid and orthophosphate.

nucleoside diphosphate any nucleotide that consists of a nucleoside esterified with diphosphate on its glycose moiety (usually at the 5′ position, when the symbol is NDP).

nucleoside diphosphate reductase EC 1.17.4.1; *recommended name*: ribonucleoside-diphosphate reductase; *systematic name*: 2′-deoxyribonucleoside-diphosphate:oxidized thioredoxin 2′-oxidoreductase; *other name*: ribonucleotide reductase. A nucleotide reductase enzyme, present in most organisms, that catalyses the formation of a 2′-deoxyribonucleoside diphosphate, oxidized thioredoxin, and H_2O from a ribonucleoside diphosphate and reduced thioredoxin. It requires iron and ATP. The enzyme from *Escherichia coli* is formed from B2 protein (dimer of β chains; Fe-binding subunit, 3-D structure known) and B1 (dimer of α chains), which contains a disulfide/sulfhydryl redox system; it is the enzyme responsible for the biosynthesis of deoxyribonucleotides from ribonucleotides, e.g. in *de novo* biosynthesis. The B2 dimer contains two Fe(iii) ions (one on each monomer) that form a Fe^{3+}–O–Fe^{3+} group. This forms a free radical centre (involving an enzyme tyrosyl residue) that abstracts a hydrogen from the ribose (ultimately from the 2′ position, but the mechanism is complex). This leads to loss of the 2′–OH. Hydride ions are lost from enzyme sulfhydryl groups to react with these OH• groups to form water, resulting in formation of disulfide groups. The hydrogen abstracted by the free radical centre is returned to what now becomes 2′-deoxyribose. The enzyme's disulfide groups are reduced in turn by thioredoxin. There is an allosteric site on the B1 subunit dimer; ATP acts at this site as an activator and dATP as an inhibitor, in a complex interaction with a second site that determines the specificity of the enzyme towards different nucleotides. A **nucleoside triphosphate reductase** is produced when the organisms are growing anaerobically.

nucleosidediphosphosugar *or* **nucleoside diphosphate sugar** *or* **nucleotide sugar** any **nucleotide** (def. 2) in which the distal phosphoric residue of a nucleoside 5′-diphosphate is in glycosidic linkage with a monosaccharide (or a derivative of a monosaccharide).

nucleoside monophosphate *see* **nucleoside phosphate**.

nucleoside phosphate *or* **nucleoside monophosphate** any nucleotide that consists of a nucleoside esterified with [ortho]phosphate on its glycose moiety (usually at the 5′-position, when the symbol is NMP).

nucleoside reverse transcriptase inhibitor *abbr.*: NRTI; a modified natural nucleoside used as an antiretroviral drug in AIDS therapy. It suppresses retrovirus replication by interfering with the viral reverse transcriptase, causing premature chain termination during DNA synthesis. It is often used in combination with other drugs. *Compare* **non-nucleoside reverse transcriptase inhibitor**.

nucleoside-triphosphatase *abbr.*: NTPase; EC 3.6.1.15; an unspecific diphosphate phosphohydrolase enzyme that catalyses the hydrolysis of the distal diphosphate bond in various nucleoside triphosphates, with formation of [ortho]phosphate and the corresponding nucleoside diphosphate. It acts also on certain other diphospho-compounds.

nucleoside triphosphate any nucleotide that consists of a nucleoside esterified with triphosphate on its glycose moiety (usually at the 5′-position, when the symbol is NTP).

nucleoside triphosphate reductase EC 1.17.4.2; *recommended name*: ribonucleoside-triphosphate reductase; *systematic name*: 2′-deoxyribonucleoside-triphosphate:oxidized thioredoxin 2′-oxidoreductase. A nucleotide reductase enzyme found in *Lactobacillus leichmannii* (and presumably related organisms). It catalyses the formation of a 2′-deoxyribonucleoside triphosphate, oxidized thioredoxin, and H_2O from a ribonucleoside triphosphate and reduced thioredoxin. It requires cobalt and ATP.

nucleosomal remodelling and histone deacetylase *see* **NURD**.

nucleosome a particle that forms the primary packing unit of DNA in chromatin. Nucleosomes give electron micrographs of decondensed chromatin a 'beads-on-a-string' appearance, and are released on mild digestion of eukaryotic nuclei with micrococcal endonuclease. Each consists of a segment of duplex DNA, 160–240 base pairs long, with associated **histone**; about 146 base pairs of the DNA comprise a **core particle** and the remainder form the linker DNA. The core particle is a disklike structure, 11 nm in diameter and 5.7 nm thick, consisting of two molecules each of histones H2A, H2B, H3, and H4 with approximately two superhelical turns of double-stranded DNA wound round it. In the intact nucleosome, an average of one molecule of histone H1 is on the exterior of each core particle and appears to mediate the packing together of adjacent nucleosomes in condensed chromatin. *See also* **nu body**.

nucleosome code the hypothesis that the local concentration and combination of differentially modified core histones of nucleosomes determines the euchromatin or heterochromatin state of DNA. *See* **histone code**.

nucleosome remodelling factor *see* **NURF**.

nucleotidase any phosphoric monoester hydrolase enzyme that catalyses the hydrolysis of a **nucleotide** (def. 1, 2) to yield a nucleoside and orthophosphate. The principal ones are classified under three EC numbers (1) EC 3.1.3.31; *recommended name*: nucleotidase; enzymes having a wide specificity for 2′-, 3′-, and 5′-nucleotides, and that also hydrolyse glycerol phosphate and 4-nitrophenyl phosphate; (2) EC 3.1.3.6; *recommended name*: 3′-nucleotidase; an enzyme having a wide specificity for 3′-ribonucleotides; these enzymes hydrolyse a 3′-ribonucleotide to a ribonucleoside and orthophosphate. Some such enzymes are not sugar specific. (3) EC 3.1.3.5; *recommended name*: 5′-nucleotidase; an enzyme having a wide specificity for 5′-ribonucleotides. These enzymes hydrolyse a 5′-ribonucleotide to a ribonucleoside and orthophosphate.

nucleotide 1 *or* **mononucleotide** *or* **nucleoside [mono]phosphate** any compound that consists of a **nucleoside** (def. 1) esterified with [ortho]phosphate at either the 3′- or the 5′-hydroxyl group of its glycose moiety (ribonucleosides giving **ribonucleotides**, and deoxyribonucleosides giving **deoxyribonucleotides**). Nucleotides are the constitutional units into which nucleic acids are broken down by partial hydrolysis and from which they are considered to be built up. **2** any compound consisting of a **nucleoside** (def. 2) that is esterified with [ortho]phosphate or an oligophosphate at any hydroxyl group on its glycose moiety. In this sense the term includes **nucleoside cyclic phosphate**, **nucleoside diphosphate**, **nucleoside diphosphosugar**, **nucleoside triphosphate**, and pyridine nucleotide. **3** any compound containing a moiety of a nucleotide (def. 1, 2). Included are: any carrying an additional phosphoric group at another position on the glycose moiety; any formed (actually or conceptually) from two or more such nucleotides, whether the same or not, joined together in phosphoric-ester linkage (to form an **oligonucleotide** or a **polynucleotide**); and, in certain instances, any formed from such a nucleotide joined through a phosphoric anhydride link either to a second nucleotide or to some other phosphate ester. Exceptionally, the term includes also certain analogous compounds (especially flavin mononucleotide, and hence also flavin-adenine dinucleotide) that, being derivatives of ribitol, are not true nucleoside phosphates or else are not formed exclusively from them.

nucleotide-binding fold *or* **nucleotide-binding pocket** a common structural feature of numerous dehydrogenase enzymes utilizing either of the nucleotide coenzymes NAD or NADP as the acceptor. The coenzyme fits in a pocket made by the folding of the polypeptide chain. Many such enzymes combine specifically with **blue agarose** owing to putative structural similarity of the bound dye (Reactive Blue 2) to the coenzyme, a property that can be exploited in the separation and purification of these enzymes by affinity chromatography. A similar property is shown by some other nucleotide-binding enzymes (and also by certain other proteins that do not bind nucleotides).

nucleotide coenzyme any **nucleotide** (def. 2, 3) that is either (1) a coenzyme (e.g. nicotinamide-adenine dinucleotide), or (2) a substrate-carrier in an anabolic reaction (e.g. uridine diphosphate glucose).

nucleotide excision repair *abbr*.: NER; the form of DNA repair in which ultraviolet light-induced photoproducts (e.g. pyrimidine dimers), chemical adducts (e.g. induced by carcinogens such as benzpyrene), or interstrand crosslinks are removed and the defect is repaired. This involves excision of an oligonucleotide that contains the lesion and filling of the resulting single-strand gap. In *E. coli*, the repair is effected by UvrABC excinuclease, the excised oligonucleotide being ≈12 nt long. In eukaryotes, some 16 gene products are required, and the excised oligonucleotide is 24–32 nt long. Defective NER is the cause of xeroderma pigmentosum and of Cockayne syndrome. *See also* **excision repair**.

nucleotide-gated channel *see* **ion channel**.

nucleotide reductase *see* **nucleoside diphosphate reductase**, **nucleoside triphosphate reductase**.

nucleotide sugar *an alternative name for* **nucleoside diphosphate sugar**.

nucleotide unit the repeating unit of a polynucleotide chain, defined typically by the sequence of atoms from the phosphorus atom at the 5′ end of any one of its component glycose residues to the oxygen atom at the 3′ end of the same residue and including all the atoms of the glycose residue and its attached phosphoric residue and nucleobase; atypically, the nucleotide unit at the 5′ end of a chain may lack a phosphate group. Nucleotide units in a given chain are numbered sequentially from the chain's 5′ end irrespective of the presence or absence of a phosphate group on the 5′-terminal unit.

nucleotidyl the acyl group formed from a nucleoside [mono]phosphate by removal of a hydroxyl group from its phosphoric group.

nucleotidyltransferase an enzyme of subclass EC 2.7.7; such enzymes transfer a nucleotidyl group to a reactant. Possession of such activity is a common mechanism of drug resistance (especially to **aminoglycoside antibiotics**) in bacteria. An example is gentamicin 2″-nucleotidyltransferase (EC 2.7.7.46); *systematic name*: NTP:gentamicin 2″-nucleotidyltransferase; *other name*: 2″-aminoglycoside nucleotidyltransferase. It catalyses a reaction between NTP and gentamicin to form pyrophosphate and 2″-nucleotidylgentamicin. This enzyme can be isolated from *Escherichia coli* and *Klebsiella pneumoniae* plasmids, and confers resistance to kanamycin, gentamicin, dibekacin, sisomicin, neomycin, and tobramycin by adenylating the 2″-OH group of these antibiotics.

nucleus (*pl.* **nuclei**) **1** *(in biology)* the most conspicuous organelle of a eukaryotic cell; it contains the chromosomes and (except for mitochondria and chloroplasts) is the sole site of DNA replication and of RNA synthesis in the cell. Usually a spheroidal body, it is separated from the cytoplasm by the nuclear envelope. **2** *(in physics)* **atomic nucleus** the positively charged central part of an atom, with which is associated almost the whole of the mass of the atom but only a very small part of its volume. It is composed of nucleons, i.e. protons and neutrons. **3** *(in organic chemistry)* a characteristic arrangement of atoms, especially a ring structure, that occurs in a series of related organic compounds; e.g. the benzene nucleus. **4** a particle on which a crystal, droplet, or bubble forms in a fluid.

nuclide any individual species of atom, whether stable, metastable, or unstable, that is characterized by the constitution of its nucleus and by its **nucleon number**, **proton number**, and nuclear energy state; its mean life must be long enough for the species to be observable. Nuclides having the same proton number but different nucleon numbers or different nuclear energy states are termed isotopic nuclides, or **isotopes**. Nuclides having the same nucleon number but different proton numbers are termed isobaric nuclides, or **isobars**. Nuclides having the same neutron number but different proton numbers are termed isotonic nuclides, or **isotones**. A given nuclide may be specified by attaching its nucleon number either to the name of the relevant chemical element as a suffix, or to the symbol for the chemical element as a left superscript; the proton number may be attached to the symbol as a left subscript; e.g. carbon-14, ^{14}C, or $^{14}_{6}C$. A metastable nuclide (i.e. one with an elevated nuclear energy state) may be differentiated from its counterpart with the same nucleon number by attaching the suffix m to the nucleon number; e.g. technetium-99m or $^{99m}_{43}Tc$. (Absence of a nucleon number attached to its name or symbol implies the presence of all isotopes of the element in natural abundance.) —**nuclidic** *adj.*

nude a mutant strain of mouse or rat that lacks a **thymus gland** and hence is devoid of **T lymphocytes** and is hairless. It is caused by a mutation in the *nude* gene, which encodes a transcription factor of the winged helix type. *See* **forkhead**.

NUF1 *abbr. for* nuclear filament-related protein.

Nujol *a proprietary name for* a high-boiling-point fraction of liquid paraffin widely used for making mulls for infrared spectroscopy. It is also used medicinally as a laxative, and was referred to by the poet e. e. cummings in *Poem, or Beauty hurts Mr. Vinal*: '...little liver pill-/hearted-Nujol-needing-There's-A-Reason...'.

null a minimum or zero value, especially of an electric current.

null cell *an alternative term for* **null lymphocyte**.

nullisomic **1** describing a cell, organism, strain, etc. that lacks one or more pairs of homologous chromosomes. **2** such a cell, organism, strain, etc.

null lymphocyte *or* **null cell** a **lymphocyte** that is not recognizable as either a B lymphocyte or a T lymphocyte.

null method *or* **zero method** a method of measurement in which a zero reading in a sensitive, but not necessarily calibrated instrument, e.g. a galvanometer, enables an unknown value of some property to be deduced by comparison with reference values.

NuMA *abbr. for* **nuclear mitotic apparatus protein**.

numatrin *another name for* **nucleolar phosphoprotein B23**.

number **1** a concept or expression of quantity reckoned in ones or units; a particular value of such a quantity (which may be integral or zero). **2** the symbol or group of symbols used to represent a number (def. 1); numeral; figure. **3** a numeral or string of numerals used for identification (of something, especially a member of a sequence). **4** to assign numbers to (members of a series); to label with a number or numbers.

number-average molar mass *see* **average molar mass**.

number-average relative molecular mass *or (formerly)* **number-average molecular weight** *see* **average relative molecular mass**.

number concentration *symbol*: *C*; *see* **concentration** (def. 1d).

number fraction *symbol*: *δ*; the number of defined particles or elementary entities of a specified component of a system divided by the total number of defined particles in the system.

numerical aperture *(in optics) abbr.*: NA; the arithmetic product of the refractive index of the medium in which the objective (lens) of a microscope is situated and the sine of half the angle of view of the objective. The resolving power of the lens is proportional to its numerical aperture.

NURD *abbr. for* nucleosomal remodelling and histone deacetylase; a protein complex found in *Xenopus* and mammals and involved in nucleosome remodelling by some as yet unknown mechanism. It contains histone deacetylases (HDAC1 and HDAC2), retinoblastoma-associated proteins (RbAp48 and RbAp46), metastasis-associated proteins (MTA1 and MTA2), and a subunit (MBD3) that contains a methyl-CpG-binding domain. The largest component (Mi2) contains two chromodomains, a zinc finger, and a distinctive helicase/ATPase domain.

NURF *abbr. for* nucleosome remodelling factor; a tetrameric protein complex of *Drosophila* that acts with **GAGA factor** to disrupt nucleosome spacing near the promoter of the Hsp70 gene. One component of NURF is an ATPase protein called initiation switch (**ISWI**).

Nurr 1 an orphan nuclear receptor expressed almost exclusively in the central nervous system, where it is confined to dopaminergic neurons. In mice, it seems to be absolutely required for generation of these neurons.

nurse cell a cell that is connected by cytoplasmic bridges to an oocyte and thereby conveys macromolecules to the growing oocyte.

nus any of three *Escherichia coli* genes that are involved in transcriptional termination. The product NusA binds to RNA polymerase, RNA, **rho**, and the antitermination protein pN, the product of the *N* gene. It may also bind to NusB. It participates in both the termination and antitermination of transcription. NusB is involved in the transcription termination process at certain sites during normal bacterial growth and is essential for the function of pN. NusG is involved in transcription antitermination.

NutraSweet *a proprietary name for* **aspartame**.

nutrient 1 any chemical substance that can be used by an organism to sustain its metabolic activities. **2** serving as or conveying nourishment. **3** *(in microbiology)* describing a solid or liquid medium that is able to support the growth of a range of nutritionally undemanding chemoorganotrophs.

nutrition 1 the supply of substances (i.e. nutrients) required by an organism, directly or indirectly, for its metabolic activities, i.e. for the provision of energy, for growth, and/or for the renewal of degraded components. **2** the act or process of supplying or receiving nutrients. **3** the scientific study of the nutrient requirements of particular organisms and of the supply of those nutrients. —**nutritional** *adj.*

nutritional mutant a mutant strain of a microorganism (alga, bacterium, or fungus) that requires a supply of one or more growth factors in addition to those required by the wild type, i.e. a mutation in a **prototroph** to form an **autotroph**.

nutritive 1 containing nutrient(s). **2** of, concerned in, or promoting nutrition.

nux vomica the dried seeds of the Indian tree, *Strychnos nux-vomica*. They are a source of **strychnine**, **brucine**, and other poisonous alkaloids.

Nva *symbol for* the *α*-amino acid **norvaline** (now known as 2- aminovaleric acid, *symbol*: Avl).

Nycodenz *the proprietary name for N*,*N′*-bis(2,3-dihydroxypropyl)-5-[*N*-(2,3-dihydroxypropyl)acetamido]-2,4,6-triiodoisophthalamide; a dense, synthetic, nonionic substance, highly soluble in water, that is capable of forming (autoclavable) aqueous solutions of densities up to 2.1 g mL^{-1}. It is one of several synthetic water-soluble triiodobenzene derivatives designed for use as intensifiers in radiology that have found use in isopycnic gradient fractionation of biological particles.



nyctalopia *the medical term for* **night blindness**.

nylon any of a class of synthetic thermoplastic substances, characterized chemically as long-chain polyamides and formed by condensation polymerization of dicarboxylic acids with diamines. They have high melting points, are insoluble, tough, resistant to fracture, and exhibit low friction. Hence they are useful in the manufacture of laboratory apparatus for which these properties are advantageous. Nylon can be formed into fibres or sheets and used for coatings, fabrics, and many other products. It is also used as an alternative to nitrocellulose in hybridization membranes.

nystatin a **mycosamine**-containing polyene antifungal antibiotic complex (three components) produced by *Streptomyces noursei* and other *Streptomyces* spp. It is very similar to **amphotericin B** in its properties and mechanism. Two proprietary names are Fungicidin and Mycostatin.



nystatin A_1

N-Z amines a proprietary enzymic hydrolysate of casein, used in bacterial growth media.

NZCYM a culture medium for the growth of *E. coli* and suitable for the propagation of bacteriophage lambda. It contains **N-Z amines**, casamino acids, yeast extract, $MgSO_4$, and NaCl.

NZM a culture medium for the growth of *E. coli* that contains **N-Z amines**, $MgSO_4$, and NaCl.

NZO mouse *abbr. for* New Zealand obese mouse.

NZY a culture medium for the growth of *E. coli* that contains **N-Z amines**, yeast extract, and NaCl.

Oo

o+ *prefix (in peptide hormone nomenclature)* denoting ovine.

o- *prefix (in chemical nomenclature)* denoting ***ortho-***. *Compare* ***m-***, ***p-***.

O *symbol for* **1** oxygen. **2** a residue of the ribonucleoside orotidine (alternative to Ord).

O- *prefix (in chemical nomenclature)* indicating substitution on oxygen; a particular oxygen atom in a molecule may be specified by suffixing an appropriate superscript.

OA *abbr. for* ovalbumin.

OAA *abbr. for* oxaloacetic acid, or oxaloacetate.

OAADPr *abbr. for* 1-*O*-acetyl-ADP-ribose.

OAG *abbr. for* 1-oleoyl-2-acetyl-glycerol.

Oakley–Fulthorpe technique a simple double immunodiffusion method that can be used for quantitative determination of antigen concentrations; it is essentially a development of the **Oudin technique**. The antiserum in 1 agar is placed at the bottom of a cylindrical tube above which is placed a layer of 1 agar gel in 1 saline, and 0.5 *o*-cresol (as a preservative). Subsequently a bacterial filtrate (containing antigen) is layered onto the agar–saline gel and the tube then incubated at 37 °C. Disks or lines of flocculation of antigen–antibody complexes are produced in the agar–saline gel, from whose positions the concentration of antigen(s) may be determined. [After C. L. Oakley and A. J. Fulthorpe, who described the technique in 1953.]

O antigen **1** any of the lipopolysaccharide–protein somatic antigens of the cell walls of Gram-negative bacteria, especially those of the Enterobacteriaceae. They are useful in the serological classification of *Salmonella*, *Shigella*, and other bacteria. **2** *(sometimes) an alternative name for* H antigen (present on erythrocytes of blood group O); *see* **blood-group substance**.

OAT *abbr. for* ornithine-δ-aminotransferase; EC 2.6.1.13; an enzyme that uses pyridoxal phosphate as coenzyme to catalyse the reaction:

ornithine + 2-oxoglutarate = pyrroline-5-carboxylate + glutamate.

It is widespread in mammalian tissues and especially active in liver, kidney, and small intestinal mucosa. It is a homohexamer of the mitochondrial matrix. The crystal structure of the human enzyme (each subunit contains 439 amino acids) comprises a total of 12 alpha helices and 14 beta strands, with a central domain that contains 8 alpha helices and 7 beta strands. Numerous mutations lead to enzyme deficiency and gyrate atrophy of the choroid and retina with hyperornithinemia and hyperornithinuria.

+oate *suffix (in chemical nomenclature)* denoting the carboxylate group, –COO$^-$.

ob *see* ***ob/ob***.

obelin a luminescent protein obtained from the jellyfish, *Obelia geniculata*. It is similar to **aequorin** in properties and use.

obese having an excessive amount of body fat. Obesity is the second largest cause of preventable death in the developed world and a major risk factor for vascular disease, diabetes mellitus type 2, and some cancers. **—obesity** *n.*

obestatin a peptide encoded by the **ghrelin** gene that opposes ghrelin's effects on food intake. The 23-residue peptide, has the structure FNAPFDVGIKLSGAQYQQHGRAL-amide in the rat. Treatment of rats with the peptide depresses food intake, inhibits jejunal contraction and results in decreased body weight gain. Ghrelin and obestatin are both derived from the ghrelin gene propeptide by posttranslational cleavage and modification. Obestatin binds to the orphan **G-protein-coupled receptor** GPR39.

OB fold *abbr. for* oligonucleotide/oligosaccharide binding fold; a protein sequence (≈110 residues) present in most prokaryotic and eukaryotic ssDNA-binding proteins. It does not have a definite sequence motif but forms a highly curved five-stranded beta sheet that closes in on itself to form a beta barrel. The BRCA2 protein contains three OB folds.

objective *(in optics)* the lens or system of lenses in an optical instrument (especially a compound microscope) that is positioned nearest to the object to be viewed.

object-oriented database *abbr.*: OODB; a database in which data are stored as abstract objects, with abstract relationships between them. The data representations are flexible (e.g. including character strings, digitized images, tables) and objects may be grouped together.

oblate **1** having an equatorial diameter longer than the polar diameter. **2** describing an **ellipsoid of rotation** (including a spheroid) generated by rotation of an ellipse about its minor axis. **3** describing any protein of **oblate** (def. 1) dimensions, as observed in hydrodynamic measurements. *Compare* **prolate**.

obligate by necessity, or without option; used especially of the nature of the environment or of the mode of life of an organism; e.g. obligate aerobe (*see* **aerobe**), obligate anaerobe (*see* **anaerobe**). *Compare* **facultative**.

obligate heterozygote an individual in a family who is proven to carry one copy of a recessive allele by having had affected progeny who inherited two copies of the mutant allele, one from each parent.

O blood-group substance *see* **ABO system**.

ob/ob *the genotype symbol for* any strain of mouse with an inherited form of severe obesity, due to a homozygous autosomal recessive mutation on chromosome 6. Such animals display marked hyperglycemia and insulin resistance. A protein named **leptin**, or OB protein, has been implicated in the control of fat mass and is a product of the *ob* mutant gene, being deficient in *ob*/*ob* mice.

obscurin a protein of the Z band of skeletal muscle that interacts with titin.

obtuse angle any plane angle greater than 0.5π rad or 90° and less than π rad or 180°.

Oc *symbol for* the octyl group.

ocatin a storage protein that constitutes over 60% of the soluble protein of oca tubers (*Oxalis tuberosa*). It is homologous with a group of pathogenesis-related proteins and has antibacterial and antifungal activity.

Occam's razor *a variant spelling of* **Ockham's razor**.

occlude **1** to block or obstruct (a passage, tube, opening, etc.). **2** *(in chemistry)* to take up and retain something in the interstices of a solid; e.g. to absorb a gas into a metal or to entrap liquid within crystals during their formation. **—occlusion** *n.*

occludin an integral membrane protein that localizes in tight junctions in chick liver; four putative transmembrane domains reside in the N-terminal half of the protein.

occult concealed or hidden; not apparent to the unaided eye.

occult blood blood that is present in a sample in such small quantities, e.g. in feces, that it can only be detected by chemical testing or by microscopy.

occult virus a virus whose presence in a host is inferred but whose isolation or detection cannot be achieved.

occupancy **1** the state or condition of being filled or occupied. **2** the number of similar sites occupied, usually expressed as a fraction or percentage of the total number available. It can refer, e.g., to the number of receptors on a cell surface occupied by a particular agonist or to the number of atomic orbitals of a particular subshell filled by electrons.

occupation theory of agonist action a theory stating that the magnitude of the response to an agonist is directly proportional to the fraction of specific receptors occupied by molecules of the agonist; it assumes that the binding of agonist to receptor is reversible. According to this theory the response will increase to a maximal value when all the receptors are occupied. *Compare* **rate theory of agonist action**.

ochratoxin any one of several **mycotoxins** produced by the fungus *Aspergillus ochraceus*, other *Aspergillus* spp., and *Penicillium* spp.; the major component, ochratoxin A, is a complex, chlorine-containing derivative of L-phenylalanine that inhibits phosphoenolpyruvate carboxykinase (EC 4.1.1.49) and may cause fatty liver. These toxins may occur on contaminated foodstuffs such as corn (maize), peanuts, storage grains, etc.



ochratoxin A

ochre codon or **ochre triplet** *symbol*: UAA; one of the three terminator codons or **nonsense codons** found in messenger RNA.

ochre mutant any cell or virus carrying an **ochre mutation**.

ochre mutation a mutation that gives rise to an **ochre codon** at an abnormal position in a messenger RNA molecule.

ochre suppressor any of a number of mutations in *E. coli* resulting in changed anticodons of tRNAs that suppress an **ochre codon** (UAA) in mRNA. This allows insertion of one of several alternative amino acids into a polypeptide at that site. Examples are *supC* (Tyr) and *supG* (Lys). Some ochre suppressors (*supC* and *supG*) also suppress **amber codons**.

ochronosis the presence of brown-black pigment in the skin, cartilage, and other tissues due to **alcaptonuria**.

OCIF *abbr. for* osteogenic inhibitory factor. *See* **osteoprotegerin**.

Ockham's razor *or* **Occam's razor** a maxim stating that when explaining something there should be a minimal number of assumptions. *Entia non sunt multiplicanda praeter necessitatem* (entities should not be multiplied except from necessity). [After William of Ockham (1285–1349), English philosopher.]

Oco *symbol for* the octanoyl group.

OCS *the proprietary name for* a commercial xylene–fluor mixture suited to the liquid-scintillation counting of a wide range of toluene- and xylene-soluble organic samples, especially specimens solubilized in **NCS**.

oct+ *a variant form of* **octa+** (sometimes before a vowel).

OCT *(in clinical chemistry) abbr. for* ornithine carbamoyltransferase.

OCT a family of genes encoding transcription factors for eukaryotic RNA polymerase II promoters. The proteins contain a **POU domain** and contribute to the naming of that domain. They are leucine zipper proteins and bind to **octamer** sequences.

octa+ *or* **octo+** *or (sometimes before a vowel)* **oct+** *comb. form* denoting eight, eightfold, eight times.

octacosa+ *comb. form* denoting twenty-eight, twenty-eightfold, twenty-eight times.

octacosanoate *see* **montanate**.

octacosanoyl *see* **montanoyl**.

octadeca+ *comb. form* denoting eighteen, eighteenfold, eighteen times.

octadecadienoic acid any straight-chain fatty acid having eighteen carbon atoms and two double bonds per molecule. Linoleic acid (*see* **linoleate**) is the *all-Z*-(9,12)-isomer and is a constituent of most vegetable oils and animal fats. The *all-E*-isomer of this acid is linolelaidic acid, a constituent of the seeds of *Chilopsis linearis*, which also contain the *all-E*-(10,12)-isomer. A number of other isomers have been synthesized chemically.

octadecanoic acid *the systematic name for* stearic acid; *see* **stearate**.

octadecapentaenoic acid any straight-chain fatty acid having eighteen carbon atoms and five double bonds per molecule. The *all-Z*-(3,6,9,12,15)-isomer occurs naturally in dinoflagellates.

octadecatetraenoic acid any straight-chain fatty acid having eighteen carbon atoms and four double bonds per molecule. Several isomers occur naturally, including the 3*E*,9*Z*,12*Z*,15*Z*-isomer, found in seed oil, and the *all-Z*-(6,9,12,15)-isomer, found in fish oil. The 9*Z*,11*E*,13*E*,15*Z*-isomer and the *all-E*-(9,11,13,15)-isomer are *α*- and *β*-parinaric acid respectively, from *Parinarium laurinum*; both isomers are used as fluorescent probes.

octadecatrienoic acid any straight-chain fatty acid having eighteen carbon atoms and three double bonds per molecule. A number of isomers occur naturally, the most prominent being the *all-Z*-(9,12,15)-isomer, (9,12,15)-linolenic acid; the *all-Z*-(6,9,12)-isomer is (6,9,12)-linolenic acid (*see* **linolenate**). *See also* **columbinic acid**, **eleostearate**.

octadecenoic acid any straight-chain fatty acid having eighteen carbon atoms and one double bond per molecule. (*Z*)-Octadec-9-enoic acid (i.e. oleic acid; *see* **oleate**) is the isomer found widely, often in high proportion, in plant and animal lipids, especially in olive oil. The 5*E*- and 6*Z*- (petroselenic acid; *see* **petroselenate**) isomers are found in seed oils; the 6*E*- isomer is named **petroselaidic acid**, and the 9*E*-isomer is elaidic acid, a common constituent of fats and oils (*see* **elaidate**). The 11*E*- and 11*Z*-isomers are, respectively, *trans*- and *cis*-vaccenic acid (*see* **vaccenate**).

octaethyleneglycol mono-*n*-decyl ether a nonionic $C_{10}E_8$ detergent (*see* $\mathbf{C_xE_y}$).

octaethyleneglycol mono-*n*-dodecyl ether a nonionic $C_{12}E_8$ detergent (*see* $\mathbf{C_xE_y}$).

octahedral coordination coordination in which six ligands are disposed about a central atom as if at the vertices of an octahedron enclosing that atom.

octahedron (*pl.* **octahedra**) any solid geometrical figure having eight plane triangular faces, 12 edges, and six tetrameric vertices. In a regular octahedron the faces are congruent equilateral triangles and may be considered to consist of two equal pyramids opposing each other on the same square base. —**octahedral** *adj.*

octamer 1 an eight-base sequence element that is common in eukaryotic **promoters**. The consensus sequence is ATTTGCAT. It binds a number of transcription factors (*see* **OCT**). **2** any polymer of a protein having eight subunits, e.g. *β*-lactoglobulin at pH 4.7 below 4°C. **3** an assembly of eight **histones** containing two each of H2A, H2B, H3, and H4, that forms the histone core of the nucleosome.

octanoate *or (formerly)* **caprylate 1** *systematic and preferred name for* the anion, $CH_3–[CH_2]_6–COO^–$, derived from octanoic acid (formerly known as caprylic acid). **2** any mixture of octanoic acid and its anion. **3** any salt or ester of octanoic acid.

octanoyl *or (formerly)* **capryloyl** *or* **caprylyl** *symbol*: Oco; the univalent acyl group, $CH_3–[CH_2]_6–CO–$, derived from octanoic acid (formerly known as caprylic acid).

octet 1 any group of eight. **2** *(in chemistry)* (esp. valency) a stable group of eight electrons constituting an electron shell of an atom.

octo+ *a variant form of* **octa+**.

octonic acid any monocarboxylic **aldonic** acid formally derived from an octose by oxidation at C-1.

octopamine *β*-hydroxytyramine; 1-(*p*-hydroxyphenyl)-2-aminoethanol; the D(–)-enantiomer is a biogenic amine, about one-tenth as active as norepinephrine, formed by the *β*-hydroxylation of tyramine by dopamine *β*-hydroxylase. It is found in the salivary glands of *Octopus* spp. and of *Eledone moschata*.



R-(–)-enantiomer

octopine 1 *N*-(1-carboxy-4-guanidinobutyl)-L-alanine; N^2-(1-carboxyethyl)-L-arginine; D-octopine (i.e., N^2-(D-1-carboxyethyl)-L-arginine) is an **opine** found in the tumours of crown-gall disease in plants and in the muscles of certain invertebrates. The genes responsible for the synthesis of octopine are part of the **T-DNA** from a **Ti-plasmid**. **2** any opine that, like octopine itself, is an *N*-substituted derivative of alanine. Octopine was first isolated from the muscles of *Octopus*, but is found in other cephalopod species and lamellibranchs. The guanidine group can undergo phosphorylation to phosphooctopine, which acts as a **phosphagen**. *Compare* **octopinic acid**.



D-octopine

octopinic acid *N*-(1-carboxy-4-aminobutyl)-L-alanine; N^2-(1-carboxyethyl)-L-ornithine; D-octopinic acid (i.e., N^2-(D-1-carboxyethyl)- L-ornithine) is an **opine** found in the tumours of crown-gall disease of plants; it is a member of the **octopine** (def. 2) family.

octose any **aldose** having a chain of eight carbon atoms in the molecule.

octreotide a synthetic octapeptide analogue of somatostatin, with which it shares four residues essential for activity. It has a much longer half-life *in vivo* (1–2 h) than somatostatin (1–2 min) and has been used in the therapy of breast, ovarian, prostatic, gut, endocrine, and pituitary tumours.

octulose any **ketose** having a chain of eight carbon atoms in the molecule.

octyl *symbol*: Oc; the alkyl group, $CH_3–[CH_2]_6–CH_2–$, derived from octane.

octyl glucoside *n*-octyl *β*-D-glucopyranoside; a mild nonionic detergent, aggregation number 84, CMC 20–25 mm. The *α*-glucoside isomer has also been used, e.g. for crystallization of membrane proteins. The lack of absorbance at 228 nm is an advantage in the use of these compounds. *Compare* **heptyl glucoside**, **hexyl glucoside**, **nonyl glucoside**, **octyl maltoside**.

octyl maltoside *n*-octyl *β*-D-maltopyranoside; a mild nonionic detergent, CMC 23 mm. *Compare* **octyl glucoside**.

octyl thioglucoside *n*-octyl 1-thio-*β*-D-glucopyranoside; a mild nonionic detergent, CMC 9 mm, with properties similar to other alkyl glucosides.



ocular 1 of or concerned with the eye or vision. **2** *or* **eyepiece** the lens or system of lenses in an optical instrument (especially a compound microscope) that is positioned nearest to the eye.

ocytocin *(sometimes) a variant spelling of* **oxytocin**.

od *or* **o.d.** *abbr. for* outside diameter.

OD *or* **O.D.** *abbr. for* optical density (now called **absorbance**).

odorant-binding protein any of a family of some 10 proteins that bind and transport odorant molecules across the mucus layer that covers odour receptors in the nasal mucosa. They are homodimers that contain an odorant-binding domain and a dimerization region.

odorant receptor any G-protein-coupled membrane receptor that binds and elicits the biological response of an odorant molecule. Several hundred genes for such receptors are present in the human genome. The receptors function through $G_{\alpha olf}$, which activates adenylate cyclase, or $G_{\alpha P}$, which activates phospholipase C. They are present in cells of the olfactory system and also outside it (there are over 50 different receptors in spermatogenic cells).

Oe *symbol for* oersted.

oedema *an alternative spelling (esp. Brit.) of* **edema**.

oenanthate *an alternative spelling (esp. Brit.) of* enanthate (*see* **heptanoate**).

oenology *an alternative spelling (esp. Brit.) of* **enology**.

oersted *symbol*: Oe; the cgs unit of magnetizing force or magnetic field strength;

$$1 \text{ oersted} = 10^3/4\pi \text{ amperes per metre } (= 79.58 \text{ A m}^{-1}).$$

[After Hans Christian Oersted (1777–1851), Danish physicist and chemist who discovered the phenomenon of electromagnetism.]

17*β*-oestradiol *an alternative spelling (esp. Brit.) of* **17*β*-estradiol**.

OEt *symbol for* the ethoxy group, $CH_3–CH_2–O–$ (alternative to EtO).

OFAGE *abbr. for* orthogonal field alternating gel electrophoresis; a type of **pulsed field gel electrophoresis** used for separating megabase-sized DNA molecules.

off-rate the constant, k_{-1}, for the dissociation step in any binding equilibrium, e.g. LB → L + B in the equilibrium L + B = LB, where L represents ligand and B the molecule it binds; the rate of dissociation of a ligand from the bound complex. The dimensions of k_{-1} are time^{-1}. *Compare* **dissociation constant**, **on-rate**.

OGCP *abbr. for* oxoglutarate/malate carrier protein; a mitochondrial inner membrane integral protein that plays an important role in several processes, including the malate– aspartate shuttle, gluconeogenesis from lactate, and nitrogen metabolism. *See also* **mitochondrial carrier proteins**.

+ogen *a variant form of* **+gen** (after a consonant).

Ogston concept *or* **three-point attachment hypothesis** a concept formulated to explain the inherent differing reactivities, often expressed in an enzymic reaction, of identical chemical groups in a **prochiral** molecule. It states that there must be at least three points of attachment of a substrate molecule to the active site of an enzyme. It is similar to the **Easson–Stedman model**. [After Alexander George Ogston (1911–96), British biophysicist who formulated it in 1948.]

Oguchi disease *see* **arrestin**.

25-OHD$_3$ *abbr. for* 25-hydroxycholecalciferol; calcidiol; use not recommended.

1,25-(OH)$_2$D$_3$ *abbr. for* 1,25-dihydroxycholecalciferol; **calcitriol**; use not recommended.

24,25-(OH)$_2$D$_3$ *abbr. for* 24(*R*),25-dihydroxycholecalciferol; (24*R*)-hydroxycalcidiol; use not recommended.

25,26-(OH)$_2$D$_3$ *abbr. for* 25,26-dihydroxycholecalciferol; 26-hydroxycalcidiol; use not recommended.

1,24,25-(OH)$_3$D$_3$ *abbr. for* 1,24(*R*),25-trihydroxycholecalciferol; **calcitetrol**; use not recommended.

OHHL *abbr. for* *N*-(3-oxohexanoyl)-L-homoserine lactone.



ohm *symbol*: Ω; the SI derived unit of electric resistance, defined as the resistance between two points on a conductor through which a current of one ampere flows as the result of a potential difference of one volt applied between the points, the conductor not being the source of any electromotive force; i.e. 1 Ω = 1 VA^{-1}. [After Georg Simon Ohm (1787–1854), German physicist.]

Ohm's law a law stating that under constant conditions the current, *I*, flowing through a given conductor is proportional to the potential difference, *U*, applied across it. The law is often expressed in the form $U = IR$, where the proportionality constant, *R*, is the resistance of the conductor.

+oic *suffix (in chemical nomenclature)* denoting the carboxyl group, –COOH. It is added to the systematic name of an unbranched alkane (or substituted alkane) to denote its modification to the corresponding alkanoic (i.e. carboxylic) acid by formal conversion of a methyl group to a carboxy group; e.g. hexanoic acid, $CH_3–[CH_2]_4–$

COOH, formally derived from hexane, $CH_3–[CH_2]_4–CH_3$. It is used also in the trivial names of certain carbocyclic and heterocyclic carboxylic acids; e.g. benzoic acid, furoic acid.

+oid *suffix forming adjectives and (associated) nouns* **1** denoting likeness to, or having the form of (something specified); e.g. colloid (i.e. gluelike substance). **2** generated by rotation of (the geometrical figure specified); e.g. ellipsoid (i.e. solid figure derived from an ellipse). **3** belonging to the class or group represented by (the type member specified); e.g. steroid (i.e. compound belonging to the same chemical family as sterols). —**+oidal** *adj.*

oil any neutral, flammable substance that is liquid at room temperature and is characteristically soluble in relatively nonpolar solvents but only sparingly soluble in aqueous solvents. There are three main groups: (1) animal and vegetable oils, which usually consist predominantly of triacylglycerols but may contain varying amounts of fatty-acid esters of other alcohols; (2) mineral oils, derived from petroleum, coal, shale, etc., which consist predominantly of hydrocarbons; and (3) **essential oils**.

oil body *an alternative name for* **spherosome**.

oil-immersion objective an objective lens in a light microscope designed to be used with a layer of a special oil between the object (or its coverslip) and the lens. The oil is of the same refractive index as the glass of the lens. This arrangement maximizes the numerical aperture and hence the resolving power of the lens.

Oil Red O a stain for lipid it is widely used for staining lipoproteins on cellulose acetate electrophoretic strips.



oilseed rape *or* **colza** *or* **canola** *the common name for Brassica campestris*, a species of rape grown as a source of rapeseed oil.

okadaic acid a polyether fatty acid, $M_r = 804.9$, that is a potent inhibitor of **protein phosphatases**, especially the PP-1 and PP-2A types. It is a tumour promoter, and is implicated as the causative agent of diarrhetic shellfish poisoning. Its name derives from *Hilichondria okadaii*, a marine sponge that feeds on *Prorocentrum lima*, a dinoflagellate from which it is isolated. See structure below.

Okazaki fragment *or* **Okazaki piece** *or* **Okazaki segment** any of the relatively short polydeoxyribonucleotides that are formed, concomitantly with the continuous replication of one of the two strands of a duplex DNA molecule, as intermediates during the discontinuous replication of the other strand. Such fragments are synthesized from mononucleotides in a direction opposite to that of the movement of the replication fork; then, as replication proceeds, they are covalently joined through the action of a polynucleotide ligase to form a long daughter polynucleotide chain, the lagging strand. These fragments appear to be 1000–2000 residues long in *Escherichia coli* and 100–200 residues long in mammalian cells; a proportion of them may have RNA primer attached. [After Reiji Okazaki (1930–1975), Japanese molecular biologist.]

OK cell *abbr. for* opossum kidney cell; any cell of a culture derived from this organ and used to study α_{2C} adrenoceptors.

+ol *suffix (in chemical nomenclature)* indicating the presence of a hydroxyl group attached to a carbon atom.

OLA *abbr. for* oligonucleotide ligation assay.

+olate *suffix* used as an alternative to **+oxide** (def. 1).

old yellow enzyme *an obsolete name for* the enzyme NADPH dehydrogenase (EC 1.6.99.1), a yellow flavoprotein (FMN in yeast, FAD in plants). *Compare* **new yellow enzyme**.

Ole *symbol for* the oleoyl (i.e. (*Z*)-octaden-9-enoyl) group.

oleandrose 2,6-dideoxy-3-*O*-methyl-*arabino*-hexose; the L enantiomer is a component of some **cardiac glycosides**.



L-oleandrose

oleate 1 *numerical symbol*: 18:1(9); *the trivial name for Z*-octadec-9-enoate, $CH_3–[CH_2]_7–CH=CH–[CH_2]_7–COO^-$ (*cis* isomer), the anion derived from oleic acid (i.e. *Z*-octadec-9-enoic acid), a monounsaturated straight-chain higher fatty acid. *See also* **octadecenoic acid**, **oleic family**.**2** any mixture of free oleic acid and its anion. **3** any salt or ester of oleic acid. *Compare* **elaidate**, **vaccenate**.

oleate desaturase *see* **phosphatidylcholine desaturase**.

olefin *an older name for* an alkene. —**olefinic** *adj.*

oleic family (of polyunsaturated fatty acids) a series of polyenoic acids in which the hydrocarbon chain terminates with the alkenyl grouping $CH_3–[CH_2]_7–CH=CH–$ (as in oleic acid); there are three other series, i.e. the **linoleic family**, **linolenic family**, and **palmitoleic family**. The oleic family can be synthesized from acetyl-CoA: palmitoyl-CoA is first synthesized by the fatty-acid synthase (*see* **fatty-acid synthase complex**); next, by chain elongation and action of **desaturases**, stearoyl-CoA, oleoyl-CoA, and longer chain fatty acyl-CoA compounds are synthesized; then from their respective CoA derivatives, the cognate fatty acids are formed. The series includes (*all-Z*)-eicosa-5,8,11-trienoic acid. In **essential fatty acid deficiency** in mammals, longer chain polyunsaturated fatty acids of the oleic family are synthesized, and partially substitute for long-chain polyunsaturated fatty acids of the linoleic family. *See also* **eicosenoic acid**, **eicosatrienoic acid**, **Mead acid**.

olein *an old name for* any of the glyceryl esters of oleic acid (*see* **oleate**), especially the triester, **triolein** (i.e. trioleoylglycerol).

oleo *(US) abbr. for* oleomargarine.

oleomargarine *an alternative name (esp. US) for* **margarine**.

oleosin any of a family of integral membrane proteins (15–25 kDa) of the endoplasmic reticulum in cells of oilseeds that define the accumulation of triacylglycerols and formation of oil bodies (or spherosomes). Oleosins each consist of a conserved central hydrophobic region (70–80 residues) flanked by hydrophobic termini.

oleosome *an alternative name for* **spherosome**.

oleoyl *or (formerly)* **oleyl** *symbol*: Ole; *the trivial name for* (*Z*)-octadec-9-enoyl, $CH_3–[CH_2]_7–CH=CH–[CH_2]_7–CO–$ (*cis* isomer), the acyl group derived from oleic acid (i.e. (*Z*)-octadec-9-enoic acid). It occurs very widely in natural lipids. *Compare* **elaidoyl**, **vaccenoyl**. *See also* **oleic family**.

1-oleoyl-2-acetylglycerol *abbr.*: OAG; an activator of protein kinase C.

oleum fuming sulfuric acid; a solution of SO_3 in concentrated $H_2SO_4 \rightarrow H_2S_2O_7$.

oleyl 1 *a common name for Z*-octadec-9-enyl, $CH_3–[CH_2]_7–CH=CH–[CH_2]_8–$ (*cis* isomer), the monoalkenyl group derived from *Z*-octadec-9-ene; use deprecated. **2** *an old and misleading trivial name for Z*-octadec-9-enoyl; oleoyl now used.

olfactomedin a major glycoprotein component of the extracellular matrix of olfactory neuroepithelium.

olfactory receptor any integral membrane protein thought to be involved in effecting the sense of smell. They are G-protein-associated receptors, and the human genome contains several hundred genes for such receptors.

+olide *suffix* (to the chemical name of an aliphatic hydrocarbon) denoting conversion to a lactone having the same number of carbon atoms as the parent hydrocarbon.

oligo *abbr. (colloquial) for* **oligonucleotide**.

oligo+ *or (before a vowel)* **olig+** *comb form* denoting **1** few, little, not much, or not many. **2** *(in chemistry and biochemistry)* a small number of (the component specified); e.g. **oligopeptide**. **3** *(in pathology)* deficiency or insufficiency of (some thing or some attribute); e.g. **oliguria**. *Compare* **multi+**, **poly+**.

oligo-2′,5′-adenylate synthetase an enzyme of the sub-subclass EC 2.7.7 that binds double-stranded RNA and polymerizes ATP into pppA(2′p5′A)$_n$ oligomers; the latter activate the latent RNase L causing it to cleave single-stranded RNAs. The enzyme is induced by **interferons**. It is a homotetramer, associated with many different subcellular fractions. In humans, two forms, E16 and E18, are produced by alternative splicing of the same gene.

oligodendrocyte a type of glial cell that forms and supports the myelin sheath around axons in the central nervous system of vertebrates. In contrast to the **Schwann cell**, which performs this role in peripheral neurons for a single axon, one oligodendrocyte is involved in the myelination of several axons.

oligo dT *or* **oligo(dT)** a short single-stranded sequence of deoxythymine (dT), 12–18 nucleotides or longer, used for priming reactions catalysed by reverse transcriptase. The transcript is primed in the poly(A) tail of mRNA molecules.

oligo dT cellulose *or* **oligo(dT)-cellulose** short single-stranded sequences of deoxythymine (oligo dT) immobilized on cellulose particles and used as an affinity chromatography matrix for the purification of poly(A)$^+$ RNA.

oligo-1,6-glucosidase (EC 3.2.1.10), *other names*: sucrase-isomaltase; limit dextrinase; isomaltase; an enzyme that catalyses the hydrolysis of 1,6-α-D-glucoside linkages in isomaltose and dextrins produced from starch and glycogen by α-amylase. A similar enzyme (EC 3.2.1.48) is a type 2 transmembrane protein of the human intestinal brush border. This contains two catalytic domains that share 40 homology. Congenital sucrase-isomaltase deficiency is rare and is genetically heterogeneous.

oligohistidine the homopolypeptide of histidine; the term is used in referring to a **histidine tail**.

oligomer 1 *(in chemistry and biochemistry)* any substance or type of substance that is composed of molecules containing a small number – typically two to about ten – of constitutional units in repetitive covalent linkage; the units may be of one or of more than one species. Depending on the branch of chemistry concerned, an oligomer may or may not be considered to be a variety of **polymer**. **2** *(in molecular biology and enzymology)* any multimeric protein that contains a finite, relatively small, number of identical subunits (i.e. protomers) that are not in covalent linkage but in a state of reversible association with each other; the protomers may themselves each consist either of single polypeptide chains (i.e. monomers) or of two or more reversibly associated (identical or nonidentical) monomers. This definition is based exclusively on the identity of the subunits and does not restrict the number of polypeptide chains each identical subunit may contain. **—oligomeric** *adj.*; **oligomerize** *or* **oligomerise** *vb.*; **oligomerization** *or* **oligomerisation** *n.*

oligomycin any **macrolide** antibiotic produced by an actinomycete similar to *Streptomyces diastatochromogenes*. Oligomycin B is an inhibitor of oxidative phosphorylation in mitochondria, interfering with the passage of hydrons through the F$_0$ component of **H$^+$-transporting ATP synthase**, and of photophosphorylation in chloroplasts. Oligomycin D (**rutamycin**) is useful as an antifungal agent.

oligomycin sensitivity-conferring protein *abbr.*: OSCP; a protein component of mitochondrial ATP synthase that is required for the binding of the F$_1$ component to the F$_0$ component of the enzyme system. *See also* **H$^+$-transporting ATP synthase**.



oligomycin A
oligomycin B: 28-oxo
oligomycin C: 12-deoxy
oligomycin D: 26-demethyl

oligonucleotide *abbr. (colloquial)*: oligo; any molecule that contains a small number of nucleotide units connected by phosphodiester linkages between (usually) the 3′ position on the glycose moiety of one nucleotide and the 5′ position of the glycose moiety of the adjacent one. The number of nucleotide units in these small single-stranded nucleic acids (usually DNA) is variable but often in the range of 6 to 24 (hexamer to 24mer), although for some purposes it might be as long as 50mer. They are widely used as primers for reactions catalysed by DNA polymerases.

oligonucleotide-directed mutagenesis a method for introducing a mutation into a cloned gene in which the desired sequence alteration is incorporated into an oligonucleotide. The mutant oligonucleotide is annealed to its complementary sequence in the cloned gene, where it acts as a primer for DNA polymerase-catalysed transcription of a complementary strand of the gene of interest, and the plasmid in which it is cloned. A number of methods have been developed to ensure that the nonmutagenized strands of the original duplex are not propagated when used to transform *E. coli* cells.

oligonucleotide ligation assay *abbr.*: OLA; a method for detecting genetic variants that differ at only one base pair. A pair of oligonucleotides are designed so that they are contiguous when annealed to the template DNA strand and with the innermost 3′ end of one oligonucleotide in register with the point of sequence variation. Oligonucleotides designed to detect the normal sequence are then ligated by the action of a thermostable DNA ligase. Another pair of oligonucleotides are designed to be ligated when annealed to the mutant or polymorphic sequence. There will be a mismatch be-



okadaic acid

tween the innermost 3′ end of the 'normal' oligonucleotide and the mutant sequence, and between the 'mutant' oligonucleotide and the normal sequence so that in either case they will not be ligated to the contiguous oligonucleotide of the pair. Biotin at the outer 3′ end of the oligonucleotide pair and a hapten at the outermost 5′ end of the oligonucleotide pair are covalently linked if ligation takes place. Reaction products are immobilized by transferring them to streptavidin coated microtitre plates, washed and probed with anti-hapten antibody coupled to an enzyme such as alkaline phosphatase. A positive enzyme-catalysed reaction gives evidence of ligation of a particular oligonucleotide pair and hence for the cognate DNA sequence.

oligopeptide any molecule that contains a small number (2 to about 20) of amino-acid residues connected by peptide linkages.

oligophosphate **1** any ion or salt of an **oligophosphoric acid** — an acid containing commonly two or three, but sometimes four or more, phosphoric residues connected by anhydride linkages. **2** any mixture of a free oligophosphoric acid and its various anions. **3** *or* **oligophosphoric ester** any ester of an oligophosphoric acid.

oligophrenin-1 the protein product of a human gene associated with a form of X-chromosome-linked mental retardation.

oligosaccharide any molecule that contains 2 to about 20 monosaccharide residues connected by glycosidic linkages.

oligosaccharin any of a group of regulatory oligosaccharides, including a fungal heptaglucoside and a plant oligogalacturonide, that are released from cell walls and control functions such as growth, development, reproduction, and defence against disease. They also include xyloglucans.

***N*-oligosaccharyltransferase** an enzyme that transfers an oligosaccharide with high mannose content from a lipid-linked oligosaccharide donor to an asparagine acceptor site on newly synthesized polypeptides to form glycoproteins. It has three subunits: **ribophorins** I and II, and a 48 kDa subunit.

oligotrophic describing a habitat, especially a lake or other mass of water, that is poor in nutrients capable of supporting the growth of aerobic plants and microorganisms, and (in the case of a lake, etc.) that hence contains abundant dissolved dioxygen at all depths.

olivomycin one of several related components of a complex of antibiotics produced by *Streptomyces olivoreticuli.* It has been investigated for antineoplastic activity. It is used as a dye specific for G–C base pairs, and stains the R bands first demonstrated in Giemsa staining.

+oma (*pl.* **+omas** *or* **+omata**) *suffix* denoting a tumour.

+ome *suffix forming nouns* **1** denoting an inclusive class of cellular constituents (e.g. metabolome, proteome, transcriptome) by analogy with genome. **2** denoting an entire set or a whole sphere of activity; universal. *See also* **+omics**. **–+omic** *adj.*; **–+omically** *adv.*

OMe *symbol for* the methoxy group, CH_3–O– (alternative to MeO).

omega *symbol*: ω (lower case) *or* Ω (upper case); the twenty-fourth and last letter of the Greek alphabet. For uses *see* **Appendix A**.

Omega *an alternative name for* **Mega-8**.

omega-oxidation *or* **ω-oxidation** a minor oxidative metabolic pathway of fatty acids, particularly those of medium chain-length, in which the terminal methyl group of such an acid is oxidized first to a hydroxymethyl group and ultimately to another carboxyl group.

omega protein *or* **ω-protein** *an alternative name for* type I **DNA topoisomerase**.

omeprazole *the nonproprietary pharmaceutical name for* 5-methoxy-2- [(4-methoxy-3,5-dimethyl-2-pyridinyl)methyl]sulfinyl-1*H*-benzimidazole, a gastric proton-pump inhibitor. It blocks both basal and stimulated secretion of acid in the stomach by reversibly inhibiting H^+/K^+-transporting ATPase (EC 3.6.1.36) in the plasma membranes of parietal cells within the oxyntic glands of the gastric mucosa. It is useful clinically in the treatment of erosive reflux esophagitis, benign peptic ulcer, and Zollinger–Ellison syndrome. *Proprietary name*: Losec.



omepraxole

omicron *symbol*: ο (lower case) *or* O (upper case); the fifteenth letter of the Greek alphabet.

+omics *suffix forming nouns* used to denote rigorous, systematic analyses of the omes: e.g., proteomics, analysis of the proteome using 2D gel electrophoresis and mass spectrometry to separate, identify and characterize all the constituent proteins; metabolomics, quantitative analysis of all the small molecular weight metabolites present inside a cell (or other sample); pharmacogenomics, analysis of drug responses with respect to genomic information (e.g., polymorphisms), aiming to customize therapies and reduce adverse drug reactions; toxicogenomics, analysis of the toxic effects of potential new drugs on gene expression patterns in target cells or tissues, aiming both to prioritize compound pipelines (to eliminate expensive failures in drug development), and to reveal genetic signatures that may predict toxicity in these compounds. *See* **ome**.

OMIM *abbr. for* Online Mendelian Inheritance in Man; *see* **specialist database**.

ommatidium any of many identical structural units of the compound eye found in many invertebrates. In *Drosophila*, each consists of eight photoreceptor cells and 12 accessory cells. In sevenless and bride-of-sevenless mutants, one of the photoreceptor cells fails to develop.

ommatin a type of **ommochrome**.

ommatochrome *an alternative name for* **ommochrome**.

ommin a type of **ommochrome**.

ommochrome *or* **ommatochrome** any yellow, brown, red, or violet natural polycyclic pigment especially common in the Arthropoda, particularly in the ommatidia of the compound eye. Ommochromes contain a phenoxazine nucleus and are formed biologically from tryptophan via kynurenine. They are divided into two groups: **ommatins**, which are alkali-labile, of low relative molecular mass, and rather weakly coloured; and **ommins**, which are alkali-stable, of higher relative molecular mass, and more strongly coloured than the ommatins.

OMP *abbr. for* orotidine monophosphate; *see* **orotidine phosphate**.

OMP decarboxylase *abbr. for* orotidine-5′-phosphate decarboxylase, a catalytic activity present in a domain of the multifunctional enzyme **uridine 5′-monophosphate synthase**.

+onate *noun suffix* denoting the anion, a salt, or an ester of an aldonic acid. *See also* **uronate**.

onco+ *comb. form* denoting **1** tumour. **2** volume.

oncofetal parvalbumin *see* **oncomodulin**.

oncogen any agent that causes **oncogenesis**; the term embraces **carcinogen**.

oncogene any gene associated with the causation of cancer. The first oncogenes were isolated from acutely transforming **retroviruses**; the retroviral oncogenes (v-*onc*) were then found to be related to, and probably derived from, normal cellular genes (c-*onc*), which came to be termed **protooncogenes**; these in most cases are involved with intrauterine growth control. Protooncogenes become oncogenes as a result of (1) deletions of portions of the protooncogene; (2) mutation of the protooncogene resulting in a protein that is constitutively active; (3) translocation of the protooncogene or a part of it to produce a hybrid gene and a hybrid protein with aberrant function; or (4) amplification of the gene resulting in inappropriate expression of the product. Protooncogenes function in normal cells in growth and differentiation pathways. Some have products that act as growth factors (e.g. *sis*, *int-2*) or growth-factor receptors (e.g. *fms*, *neu*, *kit*). Others encode signal-transduction molecules normally activated by growth-factor receptors (e.g. *ras*, *raf*, *mos*, and *src* family members). Others encode proteins that function in the nucleus (e.g. *myc*, *myb*, *fos*, *jun*) where they influence the expression of other genes. For further details see under individual oncogenes. Strictly speaking, those genes carried by DNA tumour viruses, such as **SV40** and **adenoviruses**, should also be construed as oncogenes. Unlike the retroviral genes, however, they appear to have no cellular counterparts but instead operate by subverting the actions of cellular genes (such as protooncogenes) that normally function to control cell growth. *See also* ***FMS***, ***FOS***, ***int-2***, ***JUN***, ***KIT***, ***MOS***, ***MYB***, ***MYC***, ***neu***, ***RAF***, ***RAS***, ***sis***, ***src***.

oncogenesis the production or formation of a neoplastic tumour, whether benign or malignant; the term embraces **carcinogenesis**.

oncogenic (of an agent) causing the formation of a neoplastic tumour or tumours; of or pertaining to **oncogenesis**; the term embraces carcinogenic. **—oncogenicity** *n.*

oncology the branch of medicine concerned with the study and treatment of neoplastic tumours. **—oncological** *adj.*; **oncologist** *n.*

oncolysis the destruction of neoplastic tumours or tumour cells, whether spontaneous or in response to treatment. **—oncolytic** *adj.*

oncomodulin *other names*: parvalbumin beta; oncofetal parvalbumin; an **EF-hand** Ca^{2+}-binding protein that may function in a similar manner to **calmodulin**. Expression is limited to early embryonic stages, the placental cytotrophoblasts and neoplastic tissues.

oncoprotein any protein that is the product of an **oncogene**. There are some 100 potential oncogenes in the human genome, and their products have various functions. These include growth-factor-related functions; as protein tyrosine kinases (receptor, membrane-associated, or cytosolic); as nonprotein tyrosine kinase receptors; as membrane-associated G proteins; as cytosolic protein serine/threonine kinases; as cell-cycle regulators; as transcription factors; in DNA repair; or mitochondrial-membrane related.

oncornavirus *an old name for* a group of RNA tumour viruses now classified in the subfamily Oncovirinae. *See* **retrovirus**.

oncostatin M *abbr*.: OSM; a polypeptide cytokine, produced by activated T cells and PMA-treated monocytes, that inhibits the growth of a variety of cancer cells, but stimulates growth of AIDS-Kaposi's sarcoma-derived cells and normal fibroblasts. It is a member of the **interleukin 6** subfamily. It exists as a monomer.

oncotic pressure the **colloid osmotic pressure** of plasma proteins; it is important as an index of the flow of water between the blood and the fluid in the tissues.

+one *noun suffix* denoting ketone.

one-carbon compound *an alternative name for* **C_1 compound**.

one cistron–one polypeptide hypothesis *an alternative name for* the **one gene–one polypeptide hypothesis**.

one gene–one antigen hypothesis a hypothesis stating that each of the genes in a tissue transplant governing the host's reaction to it is responsible for the manufacture of a particular transplantation antigen and for that antigen alone. It was first formulated by the US geneticist George Wells Beadle (1903–89) and US microbiologist Edward Lawrie Tatum (1909–75).

one gene–one enzyme hypothesis a hypothesis stating that every enzyme is synthesized under the control of a specific gene. It was subsequently refined into the **one gene–one polypeptide hypothesis**.

one gene–one polypeptide hypothesis *or* **one cistron–one polypeptide hypothesis** a hypothesis stating that each naturally occurring polypeptide is synthesized biologically under the control of a specific gene, which is transcribed into a unique species of messenger RNA.

one gene–one reaction hypothesis a hypothesis stating that every specific biochemical reaction is under the ultimate control of a different gene. It was later redefined as the **one gene–one enzyme hypothesis**.

+onic *suffix* denoting the formal conversion of an aldose to the corresponding aldonic acid; e.g. glucose gives rise to gluconic acid.

+onium *noun suffix* denoting a cationic molecular entity in which a heteroatom is bonded to one more univalent ligand than is normal for a neutral molecule containing that heteroatom and therefore bears a formal positive charge; e.g. ammonium, H_4N^+; dimethylammonium, $(CH_3)_2H_2N^+$; diphenyliodonium, $(C_6H_5)_2I^+$; trialkylsulfonium, R_3S^+ (where R = alkyl). *See also* **carbonium ion** (def. 2).

ONPG *abbr. for ortho*-nitrophenyl-β-D-galactopyranoside; a chromogenic substrate used for the detection and assay of β-galactosidase activity.



on-rate the constant, k_{+1}, for the association step L + B → LB in the equilibrium L + B = LB, where L represents ligand and B the molecule it binds; the rate of association of ligand to form a complex. The dimensions of k_{+1} are time^{-1}. *Compare* **association constant**, **off-rate**.

Onsager theory an extension of the **Debye–Hückel theory** of dielectrics. *See also* **Kirkwood theory**. [After Lars Onsager (1903–76), Norwegian-born US physical chemist.]

ontogeny *or* **ontogenesis** the sequence of events in the development of an individual organism during its lifetime. *Compare* **phylogeny**. **—ontogenic** *or* **ontogenetic** *adj.*

ontology *(in logic)* the formal specification of the terms and concepts used in a field or domain of knowledge providing definitions of those terms and of the relationships between them. **–ontological** *adj.*; **–ontologically** *adv.*

oo+ *comb. form* denoting ovum or egg.

oocyte *(in zoology)* a cell of an animal ovary that undergoes meiosis to form an ovum. A **primary oocyte** is formed by differentiation of an oogonium and then undergoes the first division of meiosis to form a polar body and a secondary oocyte. Following fertilization of the egg, the **secondary oocyte** undergoes the second meiotic division to form the mature ovum and a second polar body.

OODB *abbr. for* object-oriented database.

oogenesis the complete process of formation and maturation of an ovum from a primordial female germ cell. **—oogenetic** *adj.*

oogonium (*pl.* **oogonia**) **1** *(in zoology)* a cell of an animal ovary that undergoes repeated mitosis, eventually forming **oocytes**. **2** *(in botany)* the female reproductive organ in certain algae and fungi. **—oogonial** *adj.*

OP *abbr. for* organophosphorus. *See* **organophosphate**.

opal codon *or* **opal triplet** *symbol*: UGA; one of the three terminator codons or **nonsense codons** in a molecule of messenger RNA.

opalescence a milky iridescence, similar to that of opal. In some solutions it is due to the reflection of light by very fine suspended particles. **—opalescent** *adj.*; **opalesce** *vb.*

opal mutant any cell or virus carrying an **opal mutation**.

opal mutation a mutation that gives rise to an **opal codon** in a molecule of messenger RNA.

opal suppressor a mutation, *supU* (Trp), in *E. coli* that codes for an altered tRNA so that its anticodon can recognize the **opal codon** (UGA) in mRNA thereby allowing insertion of tyrosine into a polypeptide chain at that site.

open chain *(in chemistry)* **1** a chain of atoms in a molecule that is not formed into a ring, i.e. one that has two (or more) free ends. **2** **open-chain** *an alternative term for* **acyclic**.

open circle any circular duplex DNA structure containing one or more single-stranded nicks. Such a structure will dissociate at high pH into two (or more) single-stranded structures.

open circuit *(in physics)* an incomplete electrical circuit, i.e. one with infinite impedance.

open-loop system a type of system, e.g. a metabolic pathway or an electrical circuit, in which control is not exerted by feedback, each operation or activity being affected only by those earlier in the sequence. *Compare* **closed-loop system**.

open reading frame *abbr.*: ORF; a series of codon triplets, deduced from a DNA sequence, that include a 5′ **initiation codon** running through to a **termination codon**, and representing a putative or known gene. For a stretch of DNA to represent a gene it must, apart from including appropriately placed initiation and termination codons, be of a suitable length and should fulfil certain criteria indicating that the correct **reading frame** has been selected. Methods for checking this include the **RYN method**.

open system *(in thermodynamics)* any geometrically defined volume that can exchange both energy (e.g. heat or work) and matter with its surroundings. *Compare* **adiabatic system**, **closed system**.

open tetrapyrrole *see* **phycobilin**.

operand a quantity or function on which a mathematical operation is to be performed.

operator 1 *(in genetics)* a DNA sequence within an **operon** (under negative promoter control) to which a specific repressor protein can bind, thereby regulating the functioning of a **structural gene** or group of genes. **2** *(in mathematics)* a symbol (i.e. an alphabetic character, term, or special symbol) representing a particular operation to be performed on an operand or operands; e.g. Σ (= sum of), d/dx (= differentiate with respect to the variable x), + (= add to).

operon a unit of coordinated and regulated gene activity found in prokaryotes, by means of which the control of the synthesis of a protein or a group of (usually functionally associated) proteins is determined. It consists of a segment of genomic DNA containing a **structural gene** or a linear sequence of structural genes (which are transcribed as a single unit), together with one or more regulatory regions such as an **operator** (def. 1). *See also* **Jacob-Monod model**, ***lac* operon**.

ophidin *a trivial name for* 2-methylcarnosine; N^{α}-(β-alanyl)-2-methylhistidine; a constituent of snake muscle.

ophiobolin a class of sesterterpene produced only by fungi; there are six types based on the ophiobolane structure shown.



ophthalmic of, or pertaining to, the eye.

ophthalmic acid N-[N-(γ-glutamyl)-α-aminobutyryl]glycine; an analogue of glutathione in which the thiol group is replaced by a methyl group. It was originally isolated from the lens of the eye.



opiate 1 any of a group of narcotic drugs structurally related to and including **morphine** all of which are derived from opium. The group includes **codeine**, **papaverine**, and **thebaine**. The term is sometimes extended to include the **opioids** (def. 1) and any other naturally occurring, semisynthetic, or synthetic narcotic substance with similar properties and whose effects may be reversed by recognized morphine antagonists. **2** consisting of or containing **opium**; having narcotic properties similar to those of opium.

opiate receptor a membrane receptor for opiates (*see* **opioid receptor**.)

opine any of a class of unusual derivatives of basic amino acids not found in normal plant tissue, but found in plant tissue that has been transformed by oncogenic plasmids from agrobacteria. The class includes the **nopaline** and **octopine** families.

opiocortin *an alternative name for* **opiomelanocortin**.

opioid 1 any nonalkaloid having **opiate**-like pharmacological effects that can be reversed by **naloxone** or other recognized morphine antagonists. **2** describing any substance having such properties.

opioid peptide any naturally occurring peptide that is an **opioid** (def. 1). Five main groups are recognized: (1) [Leu]enkephalin and [Met]enkephalin; (2) dynorphin, α and β neoendorphin, and several other peptides that arise (or are presumed to arise) from **enkephalin** precursors; (3) α, β, γ and δ **endorphins**, all of which are formed from β lipotropin; (4) various pronase-resistant peptides present in body fluids, e.g. β **casomorphin** (in bovine milk); (5) sundry other peptides whose opiate-like action appears to be indirect. [*Note*: in the past, the terms ‘endorphin’ and ‘opioid peptide’ were often used synonymously; it is now recommended that the former should be restricted to those opioid peptides that are derived from β lipotropin.]

opioid receptor any G-protein-associated membrane receptor that interacts in a highly selective manner with an opiate or an **opioid** (def. 1) and that mediates its prime pharmacological action; types μ, δ, and κ, and possibly σ have been distinguished on the basis of their response to β endorphin (End), dynorphin A (Dyn), [Met]enkephalin (Met), and [Leu]enkephalin (Leu); the potency being, for μ: End > Dyn > Met > Leu; for δ: End = Leu = Met > Dyn; and for κ: Dyn >> End >> Leu = Met. Morphine and its analogues are primarily μ agonists, but also have activity on δ and κ receptors. μ and δ depress cyclic AMP levels and open a G-protein-modulated K^+ channel, κ inhibits a G-protein-modulated Ca^{2+} channel. Some opioids also bind to other receptors known as σ, but morphine has a very low affinity for these receptors and naloxone does not block its action.

opiomelanocortin *or* **opiocortin** a polypeptide, present in the intermediate lobe of the pituitary gland, that includes within it the entire sequences of the peptide hormones **corticotropin**, α and β melanocyte stimulating hormone, β and γ **lipotropin**, and β **endorphin**. It is formed from **proopiomelanocortin**.

opium the milky, air-dried exudate from incised, unripe seed capsules of the opium poppy, *Papaver somniferum*, and some other species. Opium contains approximately 20 alkaloids, the most significant of which are **codeine**, **morphine**, **papaverine**, and **thebaine**.

OPLC *abbr. for* overpressure(d) layer chromatography.

OPRTase *see* **orotate phosphoribosyltransferase**.

opsin 1 any of a group of hydrophobic glycoproteins that occur in the visual pigments of vertebrates in equimolecular combination (as Schiff's bases) either with 11-*cis*-retinal – in **iodopsin** and **rhodopsin** – or with 3,4-didehydro-11-*cis*-retinal – in **cyanopsin** and **porphyropsin**. These opsins are of ~35–40 kDa, and consist of single-chain polypeptides glycosylated with two branched oligosaccharides. *See also* **photopsin**, **scotopsin**. **2** any of a group of proteins of ~25 kDa that occur in combination with retinal in the purple-membrane pigments present in some strains of *Halobacterium halobium*; e.g., bacterioopsin (in bacteriorhodopsin), haloopsin (in halorhodopsin), and slow-opsin (in slow-cycling rhodopsin).

opsonify *a less common word for* **opsonize**.

opsonin any blood-serum protein that, when combined with microorganisms or other particulate material (e.g., foreign erythrocytes), increases the latter's susceptibility to phagocytosis. The two main classes are immunoglobulin G antibodies, and the C3b and IC3b fragments formed from the C3 component of **complement**; other classes include **fibronectin** and the soluble mannose-binding protein of serum. An opsonin molecule acts by linking the surface of the particulate matter to a specific receptor on the surface of a phagocytic cell; commonly, this receptor is either an Fc receptor (recognizing the Fc domain of an IgG immunoglobulin molecule) or a CR3 receptor (recognizing the IC3b fragment of complement). **—opsonic** *adj.*

opsonize *or* **opsonise** *or (less commonly)* **opsonify** to render (microorganisms or other particulate material) more susceptible to phagocytosis by coating with **opsonin**. **—opsonization** *or* **opsonisation** *or* **opsonification** *n.*

optic 1 *or* **optical** of or pertaining to the eye or the sense of sight; aiding vision. **2** *a less common word for* **optical** (def. 1, 2).

optical 1 *or* **optic** of, pertaining to, or involving light. **2** *or* **optic** of or pertaining to **optics**. **3** *a less common word for* **optic** (def. 1).

optical activity the ability (of chiral substances or their solutions, and chiral crystals) to rotate the plane of polarization of a transmitted beam of plane-polarized light. There is usually a correspondence between **chirality** of molecules and optical activity. *See also* **chiroptical**.

optical antipode *an older term for* **enantiomer**.

optical density *a term (no longer recommended) for* **absorbance**.

optical isomer *an older term for* **enantiomer**.

optical isomerism *an older term for* **enantiomerism**.

optically active having or displaying optical activity; the term is often used interchangeably with **chiral**.

optically inactive lacking optical activity (through being either **achiral** or **racemic**).

optical purity the ratio (usually expressed as a percentage) of the **specific optical rotation** of a sample of an enantiomeric substance to the specific optical rotation of a pure single enantiomer of the substance. *Compare* **enantiomeric purity**.

optical rotation *or* **rotation 1** the phenomenon of rotation of the plane of polarization of plane-polarized light on its transmission by (solutions of) chiral substances, and by chiral crystals. By convention, optical rotation is designated as rightwards, or positive – and termed **dextrorotation** – when it is clockwise as seen by an observer looking towards the light source, and designated as leftwards, or negative – and termed **levorotation** – when it is anticlockwise. **2** *or* **optical rotatory power** the ability of (a solution of) a chiral substance to effect such rotation, an effect that is normally associated with **optical activity**. **3** *symbol*: α; any measure, expressed in angular degrees, of such ability under specified conditions; *see* **molar optical rotation**, **specific optical rotation**.

optical rotatory dispersion *abbr.*: ORD; the variation of **optical rotation** with the wavelength or frequency of the transmitted light. The shape of an optical rotatory dispersion spectrum of a solution of a macromolecule often gives useful information about the conformation of the solute. *See also* **circular dichroism**, **Cotton effect**.

optical rotatory power *an alternative term for* **optical rotation** (def. 2).

optical system any arrangement of diffraction gratings, lenses, mirrors, prisms, etc., frequently within a specific instrument and used for a specific purpose.

optical tweezers a technique for trapping small particles or macromolecules in a strongly focused laser beam. It is used for examination of individual molecules or cellular components, such as contractile proteins, and the forces they produce.

optics 1 *(functioning as sing.)* the branch of physics concerned with the nature, properties, and behaviour of (visible) light and with the characteristics of optical devices, instruments, and systems. The term is extended to other kinds of electromagnetic or particulate radiation in so far as they have similar properties to light. **2** *a collective term for* an arrangement of optical components (in an instrument); the optical properties of such an arrangement.

optineurin a 66 kDa protein of unknown function that is expressed in retina, brain, and various other tissues, and is present in the aqueous humour of eyes of many vertebrate species. It interacts with huntingtin, Rab8 (a Ran-associated protein), and transcription factor IIIA (*see* **TFIII**). It is thought to be neuroprotective in the eye and optic nerve. Several mutations are associated with an autosomal dominant adult-onset glaucoma. [From optic neuropathy-inducing protein.]

OPTLC *abbr. for* overpressured thin-layer chromatography. *See* **overpressure(d) layer chromatography**.

Oracle *see* **relational database management system**.

oral of or pertaining to the mouth; adminstered by mouth.

Orb the *Drosophila* homologue of CPEB of *Xenopus laevis*. It is required for translation of the mRNA for oskar in oocytes. *See* **cytoplasmic polyadenylation element**.

orbit 1 a closed circular or near-circular course taken by a moving body (often around something). **2** the depression in the skull that contains the eye. **3** to move in or as if in an **orbit** (def. 1). *See also* **orbital**.

orbital 1 any **wave function**, Ψ, of an electron in a molecular entity. It is characterized by a particular energy value and a unique set of three quantum numbers; the counterpart in wave mechanical theory of an electron orbit in Niels Bohr's concept of atomic structure. Any particular orbital may be occupied either by one electron or by two electrons of opposed spins, or it may be unoccupied. The square of the value of Ψ at any point can be interpreted as the probability of the electron being located at that point, or as the average fractional charge density at that point. *See also* **atomic orbital**, **molecular orbital**, **pi orbital**, **sigma orbital**. **2** of, relating to, occupying, or moving in or as if in an **orbit** (def. 1). **3** belonging to the **orbit** (def. 2).

orbital shaker a device designed to impart an orbital motion to flasks, tubes, etc. with the purpose of mixing their contents and facilitating the transfer of gases from the gaseous to the liquid phase. It is useful especially for growing cultures of cells.

ORC *abbr. for* origin of replication complex *or* origin recognition complex; *other name*: prereplication complex. A protein complex in eukaryotes, comprising a hexamer of subunits ORI1 to ORI6, that recognizes and binds to the **origin of replication** region of chromosomal DNA to initiate replication. A replisome is assembled on it. It is regulated by several proteins involved in control of the cell cycle.

orcinol test *or* **Bial's test** a colorimetric test specific for aldopentoses. The sample is heated with strong acid to convert any aldopentose present to furfural (i.e. 2-furaldehyde), which is then reacted with orcinol (i.e. 5-methyl-1,3-benzenediol) in the presence of ferric chloride to give a blue-green compound extractable into amyl alcohol. The test is used for the determination of RNA and the detection of **pentosuria**. [After Manfred Bial (1870–1908), German physician.]

ORD *abbr. for* optical rotatory dispersion.

Ord *symbol for* a residue of the ribonucleoside orotidine (alternative to O).

order 1 *(in chemistry)* sequence (of residues in a polymer). **2 order of reaction**. **3** *(in taxonomy)* a category consisting of a number of similar families (sometimes only one family). One or more orders make up a class. **4** *(in mathematics)* the number of times a function must be differentiated to obtain a particular derivative. **5** *(in mathematics)* the number of columns or rows in a determinant or a square matrix. **6 order of magnitude**.

ordered mechanism *or* **ordered pathway** (for an enzymic reaction involving two substrates, A + B $\rightleftharpoons$ C) a mechanism in which the enzyme, E, must necessarily first bind to one substrate, e.g. E + A $\rightleftharpoons$ EA, and then to the second substrate, thus EA + B $\rightleftharpoons$ EAB, this ternary complex then reacting to form the product, EAB $\rightleftharpoons$ E + C. *Compare* **random mechanism**.

order of magnitude 1 a tenfold range of magnitude extending from a particular value either upwards or downwards. **2** a magnitude expressed to the nearest power of ten.

order of reaction *symbol*: n; the sum of the exponents of the concentration terms in the rate equation for an elementary chemical reaction considered in one direction only. It may also be applied to certain composite reactions.

order of reflection *symbol*: n; the integer, n, in the equation of **Bragg's law**.

ordinate the vertical, or y, coordinate in a plane rectangular (Cartesian) coordinate system. *Compare* **abscissa**.

ORESTES *an alternative name for* **ORF ESTs**.

orexin *an alternative name for* **hypocretin**.

ORF *abbr. for* open reading frame.

ORF ESTs *or* **ORESTES** *abbr. for* open reading frame expressed sequence tags; expressed sequence tags (ESTs) that provide sequence information along the whole length of a transcript, rather than just its ends. The method involves low-stringency polymerase chain reaction (PCR) to produce cDNA libraries, samples of which are then sequenced.

organ any part of the body of a multicellular organism that is adapted and/or specialized for the performance of one or more vital functions. The term is sometimes extended to include organelles of unicellular organisms.

organ culture a category of **tissue culture**, in which an organ, part of an organ, or an organ primordium, after removal from an animal or plant, is maintained *in vitro* in a nutrient medium with retention of its structure and/or function.

organelle any discrete structure in a unicellular organism, or in an individual cell of a multicellular organism, that is adapted and/or specialized for the performance of one or more vital functions.

organic **1** of, pertaining to, or derived from an organism or organisms. **2** of, pertaining to, or affecting an organ or organs. **3** of, relating to, or being a compound of carbon, whether or not of natural origin. **4** of any element contained in an organic compound. **5** any organic compound.

organic chemistry the branch of chemistry concerned with the compounds of carbon in covalent linkage, whether natural or artefactual, including most compounds of biological origin but excluding some simple carbon compounds, e.g. oxides, sulfides, and cyanides. *See also* **organic compound**.

organic compound any compound containing carbon in covalent linkage; various simple carbon compounds, especially carbon dioxide, carbonic acid, and salts and ions of carbonic acid, are usually excluded.

organification defect a defect in the iodination of tyrosine residues in thyroglobulin and in their coupling to produce thyroid hormones. It causes a congenital form of hypothyroidism. The reactions are catalysed by thyroperoxidase.

organiser *a variant spelling of* **organizer**.

organism any unicellular or multicellular prokaryote or eukaryote, usually extended to include various noncellular nucleic-acid-containing infective agents such as viruses.

organizer *or* **organiser** *(in embryology)* any part of an embryo that, through substances produced by it, stimulates the morphological development and differentiation of other parts.

organo+ *comb. form* denoting **organic** (def. 1, 2, 3).

organogenesis the formation and development of organs in an organism. **—organogenetic** *adj.*

organoleptic affecting, involving, or making use of the sense organs, especially those of smell and taste.

organomercurial **1** *or* **organomercury** of, pertaining to, or being an organic compound containing mercury, especially one in which a mercury atom is linked directly to one or more carbon atoms. **2** *or* **organomercury compound** any such compound.

organometallic **1** *or* **organometal** of, pertaining to, or being a metal-containing organic compound, especially one in which a metal atom is linked directly to one or more carbon atoms. **2** *or* **organometal compound** any such compound.

organophosphate any organic compound containing a phosphoric (including fluorophosphoric, thiophosphoric, etc.) residue in amide, anhydride, ester, or thioester linkage. The best known is diisopropylphosphofluoridate, which inhibits serine proteases (including acetylcholinesterase, crucial for nerve transmission) by blocking an essential serine residue. Organophosphorus compounds were originally developed as nerve gases, and later used as agricultural insecticides and as anthelmintics. *See also* **aminoethylbenzenesulfonylfluoride**, **diisopropyl fluorophosphonate**, **phenylmethylsulfonyl fluoride**.

organotroph *an alternative term for* **heterotroph(e)**.

organotrophic **1** heterotrophic; *see* **heterotroph(e)**. **2** of, pertaining to, or influencing the formation or nourishment of bodily organs.

organyl any organic substituent group, regardless of functional type, that has a single free valence at a carbon atom; e.g. ethyl, CH_3CH_2–; glycyl, $H_2NCH_2C(=0)$–; ribosyl, $C_5H_9O_4$–.

ORI *abbr. for* origin of replication.

oriC an AT-rich region of 245 bp on the *E. coli* chromosome where DNA replication is initiated. Elements of the sequence are highly conserved among Gram-negative bacteria. A complex of DNA proteins (up to 30 subunits) binds to *oriC* causing the duplex DNA to melt using energy released by ATP hydrolysis.

origin *(in mathematics)* the point of intersection of a set of (usually two or three) coordinate axes; the point whose coordinates are all zero. **—original** *adj.*

origin of replication *abbr.*: ORI; a site on DNA at which DNA replication begins. Eukaryotic chromosomes contain many such sites, whereas prokaryotic chromosomes, mitochondrial DNA, and chloroplast DNA contain only one. ORIs are AT-rich. Most contain repetitive nucleotide sequence motifs that vary in sequence, length, and distribution in different organisms; most also contain inverted repeats of various sizes. *See* **replication of DNA**.

origin of replication complex *see* **ORC**.

origin recognition complex *see* **ORC**.

O-ring a toroidal ring, usually of circular cross-section, made of neoprene or similar material and useful as a fluid- or gas-tight seal between particular parts of a device while permitting relative movement between them.

Orlistat *another name for* **Xenical**.

Orn *symbol for* a residue of the α-amino acid L-ornithine.

ornaline *an alternative name for* **nopalinic acid**.

ornithine *symbol*: Orn; α,δ-diaminovaleric acid; 2,5-diaminopentanoic acid; an amino acid only rarely found in proteins. L-Ornithine is an intermediate in the biosynthesis of arginine (*see* **ornithine–urea cycle**) and, in plants, of pyrrolidine and tropane alkaloids; it was first found as its dibenzoyl conjugate, **ornithuric acid**. D-ornithine is a component of **bacitracin** A.

ornithine acetyltransferase *see* **glutamate *N*-acetyltransferase**.

ornithine-δ-aminotransferase *see* **OAT**.

ornithine carbamoyltransferase *abbr. (in clinical chemistry)*: OCT; EC 2.1.3.3; *systematic name*: carbamoyl-phosphate:L-ornithine carbamoyltransferase; *other names*: ornithine transcarbamylase; citrulline phosphorylase. An enzyme of the **ornithine–urea cycle** that catalyses a reaction between carbamoyl phosphate and L-ornithine to form L-citrulline and orthophosphate. It is a homotrimer of the mitochondrial matrix. More than a hundred point mutations and gene deletions cause an X chromosome-linked enzyme deficiency in male humans and congenital **hyperammonemia**. Crystal structures of *E. coli* and human enzymes are nearly isomorphous and contain a total of 14 alpha helices and 9 beta strands organized into two domains.

ornithine decarboxylase EC 4.1.1.17; *systematic name*: L-ornithine carboxy-lyase; an enzyme that catalyses the decarboxylation of L-ornithine to putrescine and CO_2; pyridoxal-phosphate is a coenzyme. It is the first enzyme of polyamine biosynthesis; its activity increases in response to many agonists, especially those stimulating cell growth. *See* **antizyme**.

ornithine transacetylase *see* **glutamate *N*-acetyltransferase**.

ornithine transporter 1 a member of the mitochondrial carrier family of transport proteins that reside in the inner mitochondrial membrane. The human protein (301 amino acids) consists of three homologous repeats, each of ≈100 residues and containing two transmembrane segments. Several mutations of ornithine transporter 1 are associated with the HHH syndrome (hyperammonemia, hyperornithinemia, and homocitrullinuria).

ornithine–urea cycle *or* **ornithine cycle** *or* **arginine–urea cycle** *or* **urea cycle** a cyclic metabolic pathway, present in mammals and other ureotelic animals, that converts waste nitrogen, in the form of highly toxic ammonium, to essentially nontoxic urea, which may then be excreted. Urea is formed by hydrolysis of L-arginine to L-ornithine, the cycle being completed by conversion of ornithine to L-citrulline by carbamoylation with carbamoyl phosphate (previously formed by enzymic combination of carbon dioxide and ammonium with phosphate from ATP), reaction of the citrulline with L-aspartate to form L-argininosuccinate, and cleavage of this to produce fumarate and regenerate arginine. Two enzymes of the cycle (carbamoylphosphate synthetase and ornithine carbamoyltransferase) reside in the mitochondrial matrix, the rest being cytosolic. Deficiency of any enzyme of the cycle leads to hyperammonemia. The cycle is also sometimes called the **Krebs urea cycle** or the **Krebs–Henseleit cycle**, after its discoverers. The role of argininosuccinate was revealed by the US biochemist, Sarah Ratner (1903–99), in 1954.

ornithuric acid *N,N′*-dibenzoylornithine; a detoxication product of benzoic acid found in the excreta of birds.



Oro *symbol for* a residue of the pyrimidine base orotate.

orosomucoid *or* **α_1-acid glycoprotein** a ≈40 kDa, water-soluble plasma protein; it consists of a single polypeptide chain, with two intrachain disulfide bonds and carrying five branched, highly sialylated oligosaccharide units attached to the *β*-carboxyl groups of asparagine residues. Certain alleles of the gene encoding this protein have been found to be significantly increased in patients with different types of carcinoma.

orotate **1** *symbol*: Oro; uracil-6-carboxylate; 1,2,3,6-tetrahydro-2,6-dioxo-4-pyrimidine carboxylate; the anion of orotic acid (i.e. uracil-6-carboxylic acid). It is an intermediate in the biosynthesis of pyrimidine nucleotides from aspartate. **2** any mixture of orotic acid and its anion. **3** any salt or ester of orotic acid.



orotate phosphoribosyltransferase *abbr*.: OPRTase; EC 2.4.2.10; *other names*: orotidylic acid phosphorylase; orotidine-5′-phosphate pyrophosphorylase; an enzyme of the pathway for *de novo* biosynthesis of pyrimidines. It catalyses the formation of orotidine 5′-phosphate from orotate and 5-phospho-*α*-D-ribose 1-diphosphate, releasing pyrophosphate. Orotidine 5′-phosphate is decarboxylated to uridine 5′-phosphate by **orotidine-5′-phosphate decarboxylase**. The human protein consists of 480 amino acids and contains domains for OPRTase (residues 1–214) and orotidine 5′-phosphate decarboxylase (residues 221–480). Deficiency causes the recessive disease **orotic aciduria** type 1.

orotic aciduria a rare hereditary disorder of pyrimidine synthesis in humans that is characterized by retarded growth, hyperchromic anemia unresponsive to the usual hematinics, and an excessive excretion of orotate in the urine. It is due to deficiency of activity in the bifunctional **orotate phosphoribosyltransferase** (EC 2.4.2.10) and **orotidine-5′-phosphate decarboxylase** (EC 4.1.1.23), now called uridine 5′-monophosphate synthase. This protein is bicatalytic in mammals, but the two activities occur on separate proteins in prokaryotes and some eukaryotes. The condition results in the subject being a ‘pyrimidine auxotroph’ and can be effectively treated by administration of uracil, which both rectifies the pyrimidine deficiency and indirectly leads, through the effect of cytidine triphosphate on aspartate transcarbamoylase, to inhibition of orotate synthesis.

orotidine *symbol*: O *or* Ord; 6-carboxylatouridine; orotate riboside; 1-*β*-D-ribofuranosylorotate; a ribonucleoside occurring primarily as its 5′-phosphate, orotidylic acid but produced by certain mutants of *Neurospora crassa* and excreted in relatively large amounts in the urine of cancer patients treated with 6-azauridine. It is not known to be a component of ribonucleic acid.

orotidine monophosphate *abbr*.: OMP; *an alternative name for* any **orotidine phosphate**, but in particular for orotidine 5′-phosphate.

orotidine phosphate orotidine monophosphate (*abbr*.: OMP); any phosphoric monoester or diester of orotidine. Of the three possible monoesters – the 2′-phosphate, the 3′-phosphate, and the 5′-phosphate – and the two possible diesters – the 2′,3′-phosphate and the 3′,5′-phosphate – only **orotidine 5′-phosphate** is known to occur naturally (the locant therefore being omitted if no ambiguity may arise).

orotidine 5′-phosphate *or* **5′-orotidylic acid** *or* **5′-phosphoorotidine** *or* **5′-*O*-phosphonoorotidine** *symbol*: Ord5′*P*; *alternative recommended names for* orotidine monophosphate (*abbr*.: OMP), orotidine 5′-(dihydrogen phosphate), orotate ribonucleotide. (The locant is commonly omitted if there is no ambiguity as to the position of phosphorylation.) It is the immediate biosynthetic precursor of uridine monophosphate, uridylic acid, UMP, to which it is converted by decarboxylation. Thus it is important also as an intermediate in the biosynthesis of other pyrimidine nucleotides from UMP.

orotidine-5′-phosphate decarboxylase EC 4.1.1.23; *other name*: orotidylic decarboxylase; an enzyme that catalyses the decarboxylation of orotidine 5′-phosphate to UMP a reaction carried out by the multifunctional enzyme **5′-monophosphate synthase**.

orotidine-5′-phosphate pyrophosphorylase *see* **orotate phosphoribosyltransferase**.

orotidylate **1** either the monoanion or the dianion of orotidylic acid. **2** any mixture of orotidylic acid and its anions. **3** any salt or ester of orotidylic acid.

orotidylic acid *the trivial name for* any phosphoric monoester of orotidine. The position of the phosphoric residue on the ribose moiety of a given ester may be specified by a prefixed locant – *see* **orotidine phosphate**. However, 5′-orotidylic acid is the ester commonly denoted, its locant usually being omitted if no ambiguity may arise. 5′-Orotidylic acid is also an alternative recommended name for **orotidine 5′-phosphate**.



orotidylic acid phosphorylase *see* **orotate phosphoribosyltransferase**.

orotidylic decarboxylase *see* **orotidine-5′-phosphate decarboxylase**.

orphanin FQ *or* **nociceptin** an endogenous heptadecapeptide with an N-terminal phenylalanine and a C-terminal glutamine residue. It is derived from a precursor protein (186 amino acids) homologous to preprodynorphin and to preproenkephalin. It binds to a G-protein-coupled membrane receptor related to the opioid receptors. When injected into the cerebral ventricles of mice it produces hyperalgesia and inhibits locomotor activity.

orphan receptor a receptor whose physiological ligand is unknown.

ortho (*followed by* to) at a position in a benzene ring adjacent to a particular (specified) substituent.

ortho- *abbr*.: *o*-; *prefix (in chemical nomenclature)* denoting an isomer of a disubstituted monocyclic aromatic compound in which the substituents are attached at positions 1 and 2 of the ring. *Compare* ***meta-***, ***para-***.

ortho+ *or (before a vowel)* **orth+** *comb. form* **1** straight or upright; perpendicular (to) or at a right angle (to); correct. **2 a** *(in inorganic chemistry)* denoting the most hydrated acid of a series of oxoacids formed from any one of certain anhydrides, or the anion or a salt formed from such an acid. The term is now approved only for orthoboric acid, H_3BO_3; orthosilicic acid, H_4SiO_4; orthophosphoric acid, H_3PO_4; orthoperiodic acid, H_5IO_6; and orthotelluric acid, H_6TeO_6. *Compare* **meta+** (def. 2), **pyro+**. **b** *(in organic chemistry)* similarly denoting hypothetical acids of general formula $RC(OH)_3$ or $C(OH)_4$ or real esters of such acids, e.g. trimethyl orthoacetate, $CH_3–C(OCH_3)_3$; tetramethyl orthocarbonate, $C(OCH_3)_4$.

***ortho-* and *peri*-fused** describing a polycyclic compound in which one ring contains two, and only two, atoms in common with each of two or more rings of a contiguous series of ***ortho*-fused** rings. Such compounds have *n* common faces and <2*n* common atoms.

orthochromatic **1** (of a dye or stain) imparting, or capable of imparting, its own colour to a structure. **2** (of a structure) assuming, or capable of assuming, the same colour as that of a dye or stain with which it is treated. *Compare* **metachromatic**. **—orthochromatically** *adv.*

orthodox conformation the conformation adopted by a mitochondrion in the resting state when the [ATP]/[ADP] ratio is high. This is the usual conformation of mitochondria seen in electron micrographs of thin sections of intact tissue.

***ortho*-fused** describing a polycyclic compound in which any two adjacent rings contain two, and only two, atoms in common. Such compounds have *n* common faces and 2*n* common atoms.

orthogonal **1** (of axes, lines, planes, surfaces, etc.) mutually at right angles; perpendicular to one another. **2** *(in statistics)* (of a set of variates) being, or regarded as being, statistically independent.

orthograde *see* **anterograde**.

orthologue *or (esp. US)* **ortholog** a gene, protein, or biopolymeric sequence that is evolutionarily related to another by descent from a common ancestor, having diverged as a result of a speciation event. Orthologues usually perform the same or highly similar functions in their different host species; e.g., human and bovine rhodopsins. **–orthologous** *adj.*

orthomyxovirus any of a group of RNA animal viruses, in class V of the **Baltimore classification**, consisting of enveloped, pleomorphic particles 80–120 nm in diameter. The nucleocapsids are helical, 6–9 nm in diameter, and of variable length, and contain segmented RNA (minus strand); this is transcribed by a virion polymerase into complementary RNA molecules, which act as messengers. The group includes the influenza A, B, and C viruses.

orthophosphate *an alternative name for* **phosphate** (used especially to distinguish from **metaphosphate** or **pyrophosphate**). *See also* **ortho+** (def. 2a).

orthostatic intolerance the combination of lightheadedness, fatigue, altered mentation, and fainting with postural tachycardia and excessive plasma norepinephrine concentration. The symptoms may be produced by cocaine, amphetamines, or tricyclic antidepressants, or by an autosomal dominant loss-of-function mutation in the **norepinephrine transporter**.

orthotopic transplant any tissue graft transplanted into the normal position of that tissue in the body of the recipient. *Compare* **heterotopic transplant**.

oryzain a group of proteases expressed during seed germination in rice. Three types (α, β, and γ) have been identified. γ-Oryzain (362 amino acids) is homologous with aleurain of barley, and with SAG (senescence-associated gene)-encoded cysteine proteases of *Arabidopsis*, maize, and *Brassica* species.

Os *symbol for* osmium.

osamine *an alternative name for* **aminodeoxysugar**.

osazone any 1,2-bis(arylhydrazone); i.e., any condensation product of the type RNH–N=CR–CR′=N–NHR formed between an α-dicarbonyl compound (e.g., a 2-ketoaldose) and hydrazine, or a substituted hydrazine. α-Hydroxy- and α-amino-carbonyl compounds will also form osazones through oxidation of the corresponding [mono]hydrazones initially formed. *See also* **phenylosazone**.

oscillator an instrument or device for producing oscillations, especially an electronic device that produces an alternating output of known frequency.

oscillin a 33 kDa protein identified in sperm that induces oscillations in intracellular Ca^{2+} concentrations in mammalian eggs. It is considered to be involved in Ca^{2+} oscillations that serve as the essential trigger for egg activation and early development of the embryo.

oscillograph an instrument for producing a graphical record of an oscillating value.

oscilloscope an instrument for producing a temporary visual record of an oscillating value. A **cathode-ray oscilloscope**, based on the **cathode-ray tube**, provides a visual image of electrical signals, in the form of a graph of the signal over time.

OSCP *abbr. for* oligomycin sensitivity-conferring protein.

+ose *noun suffix* **1** originally indicating related to glucose, as either an isomer (e.g. galactose) or a polymer (e.g. cellulose, maltose), now also extended to other sugars (e.g. arabinose, fructose, sucrose) or classes of sugars (e.g. aldose, furanose, ketose, hexose, pentose, pyranose). **2** indicating the primary products of hydrolysis of a biopolymer; e.g. proteose, peptose.

Ose *(in glycolipid nomenclature) symbol for* a monosaccharide residue. A numerical subscript denotes the number of connected monosaccharide units in the oligosaccharide component, and a prefix of two or three characters represents the trivial name of the oligosaccharide; e.g. $GbOse_3$ (i.e. globatriaose), $nLcOse_4$ (i.e. neolactotetraose), $McOse_3Cer$ (i.e. mucotriosylceramide).

oside *an alternative term for* **glycoside**.

+oside *noun suffix* denoting **glycoside**.

+osis *noun suffix* denoting **1** a process or state (e.g. metamorphosis, narcosis, necrosis, osmosis). **2** a diseased condition (e.g. nephrosis, tuberculosis). **3** an increase or excess (of something) (e.g. glycogenosis, leukocytosis). *See also* **+otic**.

oskar one of the **maternal effect genes** in *Drosophila melanogaster*. It organizes the germplasm and directs localization of the germ-cell determinants. Oskar protein is required to keep *oskar* RNA and *staufen* (another maternal effect gene) protein at the posterior pole. Three other genes (*capu*, *spir*, and *stau*) are required for the initial localization of the *oskar* product to the posterior pole of the oocyte.

osM *or* osm *symbol for* osmolar (osmol L^{-1} now recommended).

OSM *abbr. for* oncostatin M.

osmiophilic (of a structure or substance) having an affinity for, or staining readily with, osmium tetroxide; e.g. osmiophilic globules (plastoglobuli) in plastids.

osmium tetroxide osmium(viii) oxide; OsO_4; a volatile, evil-smelling, moderately water-soluble, electron-dense substance used for fixing specimens for microscopy, especially electron microscopy, and used chemically in the hydroxylation of alkenes. The vapour is highly poisonous.

osmo+ *comb. form* denoting **1** **osmosis**. **2** smell, odour.

osmoceptor *see* **osmoreceptor**.

osmol *symbol for* osmole.

osmolal **1** describing a solution that contains one **osmole** (of a specified solute), or an indicated number of osmoles, per kilogram of solvent; used also of a specified solute in such a solution. **2** describing an amount-of-substance concentration expressed in osmoles (of a specified solute) per kilogram of solvent. *Compare* **osmolar**. *See also* **osmolality**.

osmolality the concentration of osmotically active particles in an aqueous solution expressed in **osmoles** per kilogram of solvent. For a nondissociating substance the osmolality is equal to the **molality**, whereas for a substance that dissociates in aqueous solution the osmolality is greater than the molality to an extent dependent on the number of particles into which the substance dissociates and on the position of the equilibrium. *Compare* **osmolarity**.

osmolar **1** describing a solution that contains one **osmole** (of a specified solute), or an indicated number of osmoles, per litre of solution; used also of a specified solute in such a solution. **2** *abbr.*: osM or osm; describing an amount-of-substance concentration expressed in osmoles (of a specified solute) per litre of solution. *Compare* **osmolal**. *See also* **osmolarity**.

osmolarity the concentration of osmotically active particles in an aqueous solution expressed in **osmoles** per litre of solution. For a nondissociating substance the osmolarity is equal to the molarity, whereas for a substance that dissociates in aqueous solution the osmolarity is greater than the molarity to an extent dependent both on the number of particles into which the substance dissociates and on the position of the equilibrium. *Compare* **osmolality**.

osmole *symbol*: osmol; the amount of substance that contains, or gives rise to, one mole of osmotically active particles when in aqueous solution.

osmometer **1** *or* **membrane osmometer** any device for demonstrating the phenomena of osmosis and osmotic pressure; any instrument for measuring osmotic pressure. **2** an apparatus for measuring the acuteness of the sense of smell. **—osmometric** *adj.*; **osmometry** *n.*

osmophile any organism that grows preferentially (or only) in media of relatively high osmotic pressure, such as ones with a high salt or sugar content. —**osmophilic** *adj.*

osmoreceptor *or* **osmoceptor** a sensory cell, or group of such cells, that is specialized to react to changes in environmental osmotic pressure, e.g. of blood plasma or of a tissue fluid. Osmoreceptors are located in the hypothalamus, in the main arteries, and at other sites.

osmoregulation the sum of the processes by which organisms regulate their internal contents of water and solutes. —**osmoregulatory** *adj.*

osmosis the spontaneous net flow of solvent by diffusion through a semipermeable membrane from a phase where the solvent has a higher chemical potential to one where the solvent has a lower chemical potential. The flow continues until the chemical potential of the solvent becomes the same on both sides of the membrane or until it is countered by a difference in hydrostatic pressure either generated or applied. —**osmotic** *adj.*; **osmotically** *adv.*; **osmose** *vb.*

osmotic coefficient *symbol*: ϕ_m (on a molality basis) *or* ϕ_x (on a mole fraction basis); the ratio of the actual to the ideal osmotic pressure of a given solution at a specified temperature; i.e. a representation of the departure of the solution from ideality.

osmotic pressure *symbol*: Π; the excess hydrostatic pressure that must be applied to a solution in order to reduce to zero the net flow of pure solvent into it by osmosis. The osmotic pressure of a dilute solution is equal to the pressure the solute would exert if it could exist as a gas at the same temperature, T, and the same amount-of-substance concentration, c; thus it may be expressed by a relation analogous to the gas equation, i.e. $\Pi = \nu cRT$ where ν is the (average) number of particles into which one solute molecule is dissociated under the given conditions, and R is the gas constant. Osmotic pressure is a **colligative property** of a solution. *See also* **colloid osmotic pressure**, **oncotic pressure**.

osmotic shock any disruption or other disturbance caused to suspended cells or cell organelles by a sudden change in the osmotic pressure of their suspending medium.

osmotin a basic protein abundant in tobacco cells grown in a salt-rich medium. The 26 kDa mature protein accumulates in the cell vacuole in response to biotic stimuli (i.e. phytohormones, viral or fungal infection) and abiotic stimuli (i.e. water deprivation, cold, UV irradiation, wounding).

osmotolerant describing a cell or organism that is tolerant to a wide range of osmotic pressures in its environment.

osone any 2-ketoaldose; use not recommended.

ossein the organic material, consisting mainly of collagen, that remains after treatment of bone with dilute acid to dissolve out the inorganic components.

ossify to make into bone or to become bone. —**ossification** *n.*

osteo+ *or (before a vowel)* **oste+** *or (sometimes)* **ost+** *comb. form* denoting bone.

osteoblast a mesenchymal cell that secretes the organic matrix of bone (i.e. osteoid, consisting chiefly of collagen); as the matrix becomes calcified the osteoblast becomes trapped and is known as an osteocyte.

osteocalcin *other names*: γ-carboxyglutamic acid-containing protein; bone GLA-protein (*abbr.*: BGP); a protein that binds Ca^{2+} and apatite; the binding depends on γ-carboxyglutamic acid residues (three per molecule) formed by vitamin K-dependent carboxylation.

osteochondrodysplasia a very heterogeneous disorder of skeletal development that is frequently associated with dwarfism, spinal deformity, and joint abnormalities. There are numerous forms, of which many arise from mutations in collagen types II, IX, X, and XI; in receptors for somatotropin and fibroblast growth factors; or in sulfate transport protein.

osteochondromatosis *an alternative name for* **hereditary multiple exostoses**.

osteoclast a large, multinucleate **macrophage** that erodes bone matrix and is able to tunnel deep into the substance of compact bone. Osteoclasts are formed by the fusion of blood monocytes and play an important role in the remodelling of bone and the removal of dead bone.

osteocyte an osteoblast when it has become trapped in a lacuna of the bone matrix and is no longer able to divide or secrete appreciable amounts of new matrix. Osteocytes are connected by fine cellular processes that pass through the bone canaliculi.

osteogenesis the processes of bone formation; ossification.

osteogenesis imperfecta *or* **'blue eyes-broken bones disease'** *or* **brittle bone disease** a genetically heterogeneous group of human diseases distinguished by the severity of bone fragility, scleral coloration, hearing loss, abnormal dentition, and soft-tissue dysplasia involved. Four autosomal dominant phenotypes are recognized: type1 (mild) has blue sclerae and bone fragility; type 2 (prenatal lethal) has dark sclerae, severe bone fragility, and bone deformity; type 3 (deforming) has light sclerae, bone fragility, progressive deformity, imperfect dentition, and short stature; type 4 (mild deforming) has light sclerae, imperfect dentition, and mild short stature. Over 200 mutations in type I collagen genes are responsible. Those that abolish synthesis of pro-α-1 (I) or pro-α-2 (I) can produce most phenotypes, while splice junctions in either gene produce different phenotypes depending on their position. Partial deletions in either gene usually result in type 4.

osteoid **1** the unmineralized bone matrix secreted by osteoblasts; it consists chiefly of collagen. **2** resembling bone.

osteolysis the breakdown and dissolution of bone, especially through disease. —**osteolytic** *adj.*

osteomalacia a clinical condition of adults characterized by softening and deformation of the bones due to a failure to maintain their mineralization. It has a wide variety of possible causes, of which dietary deficiencies of vitamin D, calcium, or phosphate are the commonest.

osteonectin *see* **SPARC**.

osteopetrosis *or* **osteosclerosis** *or* **marble bone disease** a rare, heterogeneous disorder in which there is decreased osteoclastic resorption of bone and widespread expansion of bone mass. *Compare* **osteoporosis**.

osteopontin *other names*: bone sialoprotein 1; urinary stone protein; secreted phosphoprotein 1 (*abbr.*: SPP-1); nephropontin; uropontin; a bone-specific sialoprotein produced by cells in osteoid matrix, but independently discovered from several different functions. It can form a bridge between cells and the mineral in the matrix, and is found at high concentrations on the cement lines, where bone formation follows resorption. It is also found in the kidney, and plays a major role in urinary stone formation. In arterial smooth muscle cells, its level increases in atherosclerotic plaques. It is secreted, binds calcium, and binds covalently to fibronectin. It has an **RGD** integrin-binding sequence, and is one of the major ligands for the vitronectin receptor. It is phosphorylated on serine, and is an *O*- and *N*-glycosylated protein. There are four forms from alternative splicing.

osteoporosis a condition characterized by a general or local reduction in bone mass with little alteration in gross composition. This causes the affected bones to become porous, brittle, and liable to fracture. Recognized forms include: (1) postmenopausal; (2) senile; (3) secondary – to other conditions or to drugs (e.g. corticosteroids, barbiturates, anticonvulsants), chronic alcoholism, and cigarette smoking; (4) idiopathic juvenile. *Compare* **osteopetrosis**.

osteoprotegerin *or* **osteogenic inhibitory factor** (*abbr.*: OCIF) a protein belonging to the tumour necrosis factor (TNF) superfamily that is present on, or secreted by, osteoblasts. It binds **RANKL** and prevents this from binding to **RANK** on osteoclasts, thereby preventing bone resorption. Overexpression of osteoprotegerin in mice leads to **osteopetrosis**, with excessive calcification of bone.

osteostatin a polypeptide that consists of residues 107–139 of **parathyroid hormone-related protein**. It has effects on bone resorption and on brain, although its physiological role is unclear.

Ostwald dilution law a relationship, deduced in 1888 by the Russian-born German chemist Friedrich Wilhelm Ostwald (1853—1932), between the amount-of-substance concentration, c, and the degree of dissociation, α, of a weak electrolyte. It is given by:

$$\alpha^2 c/(1-\alpha) = K,$$

where K is the apparent dissociation constant of the electrolyte.

Ostwald pipette a pipette for measuring small volumes of liquids, especially viscous liquids. It features a capillary stem and delivery jet and a shoulderless bulb near the jet. Various modifications have been described.

Ostwald viscometer a simple **capillary viscometer**.

+osyl *suffix* indicating a **glycosyl** group.

+otic *suffix forming adjectives and nouns* **1** affected by (e.g. necrotic) or relating to (e.g. osmotic). **2** causing (e.g. mitotic, narcotic). —**+otically** *adv.*

otoferlin a protein that is homologous with spermatogenesis factor (fer-1) of *Caenorhabditis elegans*, and is related to dysferlin and myoferlin of humans. It consists of 1977 amino acids, with a transmembrane segment close to the C-terminus, the rest being intracellular. Several mutations cause an isolated profound deafness.

otogelin the product of a candidate gene for an autosomal recessive form of deafness. It is predicted to be a secreted glycoprotein (2910 amino acids) that, like α-tectorin, is specific to acellular membranes of the inner ear. It consists of a central region that is rich in threonine, serine, and proline residues, flanked on the N-terminal side by four vWF domains, and on the C-terminal side by several vWF-like domains.

ouabain *or* **G-strophanthin** a **cardiac glycoside** whose carbohydrate moiety is L-rhamnose, obtained from the seeds of *Strophanthus gratus*. It is a specific inhibitor of the membrane-bound sodium pump Na$^+$,K$^+$-ATPase (*see* **sodium/potassium ATPase**) of animal cells.



Ouchterlony technique a development of **double immunodiffusion**, effected in two dimensions so that comparisons can be made between two or more antigen-containing samples in their reaction with one antiserum. The particular pattern of precipitation lines or arcs formed enables conclusions to be drawn regarding the identity, partial identity, or nonidentity of antigens in the various samples examined. [After O. Ouchterlony, French immunologist.]

Oudin technique a simple, single immunodiffusion technique, effected in one dimension, in which a solution of an antigen-containing sample is placed above a column of antiserum incorporated in a gel in a tube; antigen diffuses into the gel, where it reacts with antibody to form one or more precipitation bands. [After Jacques Oudin (1923–).]

ounce *symbol*: oz; a unit of mass, equal in the avoirdupois system to one-sixteenth of a pound (= 28.3495 grams). This must be distinguished from the **troy ounce** (equal to 480 grains, 31.1035 grams).

outer membrane **1** *(in eukaryotes)* the more external of the two membranes that surround a chloroplast, a mitochondrion, or a nucleus. **2** *(in prokaryotes)* the layer of lipopolysaccharide, lipoprotein, and protein that lies external to the peptidoglycan in the cell wall of a Gram-negative bacterium.

outer membrane protein P68 *see* **pertactin**.

outlier *(in statistics)* a data point that falls far outside the values of others in a data set. The nature of outliers should be understood prior to further analysis: those arising from measurement errors will distort the statistics and hence interpretation of the data; those that are genuine, however, may point to unexpected and hence highly interesting results.

ov+ *a variant form of* **ovi+** (before a vowel).

ova the plural of **ovum**.

ovalbumin *abbr.*: OA; a ≈44.5 kDa glycoprotein, also called egg albumin, that is the major protein of egg white from hens' eggs. Each molecule consists of a single polypeptide chain, and carries a single oligosaccharide chain containing only mannose and *N*-acetylglucosamine residues. It is included in the **serpin** family. It is synthesized by the oviduct under hormonal control. Although a secreted protein, it has no N-terminal signal peptide.

ovalocytosis an abnormality of erythrocytes that makes them oval or elliptical rather than circular. Southeast-Asian ovalocytosis, which is common in Melanesia, Indonesia, Papua New Guinea, and Philippines, is caused by mutations in band 3 protein (*see* **band protein**).

ovarian hormone any of the numerous steroid hormones secreted by the ovary.

ovary **1** *(in zoology)* the gonad of a female animal; vertebrates have a pair of ovaries. The ovary contains oocytes from which ova are produced, and it also secretes various steroid hormones. Its activity is cyclical and is controlled by gonadotropin(s). **2** *(in botany)* the enlarged basal part of a carpel or a syncarpous gynecium of a flower that contains one or more ovules. —**ovarian** *adj.*

overgrowth **1** excessive growth; hyperplasia. **2** a later but more vigorous growth by another strain or species of organism that supplants one already existing.

Overhauser effect *or* **Overhauser enhancement** *see* **nuclear Overhauser effect**.

overlap peptide a fragment, produced by partial hydrolysis of a polypeptide or protein, that contains both the C-terminal part of the sequence of another peptide fragment and the N-terminal part of a further fragment, allowing those two to be placed in the correct position in the overall sequence of the parent compound during protein sequencing procedures.

overlapping code a code in which one element of a code-word forms part of an adjacent code-word in an encoded piece of information. A triplet code (such as the **genetic code**, where the code-words are codons) may be either: a **fully overlapping code**, in which one code-word consists of the elements at positions *n*, (*n*+1), (*n*+2), and the next code-word consists of the elements at positions (*n*+1), (*n*+2), (*n*+3); or a **partially overlapping code**, in which adjacent code-words comprise elements at *n*, (*n*+1), (*n*+2), and those at (*n*+2), (*n*+3), (*n*+4). In a **nonoverlapping code**, such as the genetic code proved to be, no element of one code-word forms part of an adjacent code-word.

overlapping gene any gene whose polynucleotide sequence overlaps, wholly or in part, that of another gene in the same stretch of a genome. The codons may or may not be in the same **reading frame**. In mitochondria and some viruses, some mRNAs are synthesized by the transcription of the same DNA using different reading frames.

overpressure(d) layer chromatography *abbr.*: OPLC; a chromatographic technique that gives some of the advantages of **high-pressure liquid chromatography** to **thin-layer chromatography**, with resultant increases in both speed and efficiency of separation. The sorbent layer is completely covered by a flexible membrane under external pressure and the solvent is pumped continuously through the sorbent layer.

overshoot the extent to which a control system causes the variable being controlled to go initially beyond its final equilibrium position.

ovi+ *or* **ovo+** *or (before a vowel)* **ov+** *comb. form* denoting ovum or egg.

oviduct *(in zoology)* the tube through which ova are conveyed from the ovary to the exterior or to some intermediate organ such as the uterus. In mammals it is known more commonly as the **Fallopian tube** or **uterine tube**.

oviductin *other name*: gp43 processing protease; a high molecular weight glycoprotein that is secreted by the non-ciliated secretory cells of the oviduct, and later transferred to the zona pellucida of the oocyte during oviductal transit. It processes a 43 kDa glycoprotein of the oocyte envelope during its transit through the duct.

ovine *abbr.*: o *or (formerly)* O; of, belonging to, characteristic of, obtained from, or being sheep or a sheep; resembling a sheep, sheeplike.

ovo+ *a variant form of* **ovi+**.

ovoflavin *or* **oviflavine** *a former name for* **riboflavin**.

ovoinhibitor a contaminant of crude **ovomucoid** that, unlike pure ovomucoid, inhibits chymotrypsin as well as trypsin.

ovomucoid a glycoprotein found in egg white from hens' eggs; it is an inhibitor of trypsin.

ovothiol a novel thiohistidine compound from sea-urchin eggs that confers NAD(P)H-O_2 oxidoreductase activity on ovoperoxidase.

ovotransferrin *an alternative name for* **conalbumin**.

ovulate to discharge an egg or eggs from an ovary. **—ovulation** *n.*

ovule **1** *(in botany)* a structure in the ovary of a seed plant that develops into a seed after fertilization of the egg cell within it. **2** *(in zoology)* a small, especially immature, ovum or egg.

ovum (*pl.* **ova**) *(in zoology)* strictly, an unfertilized egg cell, i.e. female gamete, which contains a haploid nucleus and which on fertilization has the unique ability to develop into a new individual. In many animals, mammals included, **oogenesis** is arrested and meiosis is not completed until after fertilization of the secondary **oocyte**, hence in these animals an ovum in the strict sense cannot exist. However, the term is often applied instead either to the secondary oocyte or to the product resulting from the second meiotic division after fertilization.

oxa+ *or (sometimes before a vowel)* **ox+** *prefix (in chemical nomenclature)* denoting replacement of a methylene group in a specified acyclic or monocyclic hydrocarbon by an oxygen atom. For certain natural products, (e.g. tetrapyrroles), the meaning is extended to denote replacement of a noncarbon atom (with any attached hydrogen atoms) by an oxygen atom.

oxalacetate *an alternative name for* **oxaloacetate**.

oxalate **1** *the trivial name for* ethanedioate, $^{-}OOC–COO^{-}$, the dianion of oxalic acid, i.e. ethanedioic acid. It occurs in many plants, especially sorrels of the genera *Oxalis* and *Rumex*, and is highly toxic to animals. Normally, small amounts are formed in humans and excreted in the urine; larger amounts occur in patients with **hyperoxaluria**. The calcium salt is virtually insoluble in water, a property that is valuable in the determination of calcium and in the use of oxalate *in vitro* as an anticoagulant. **2** any mixture of free oxalic acid and its mono-ions and dianions. **3** any salt or ester of oxalic acid.

oxalo the univalent acyl group, HOOC–CO–, derived from oxalic acid by loss of one hydroxyl group. *See also* **oxalyl** (def. 1).

oxalo+ *prefix* indicating the presence of an **oxalo** group.

oxaloacetate *or (rarely)* **oxalacetate** *abbr.*: OAA; **1** *the trivial name for* oxosuccinate (*formerly* ketosuccinate); oxobutanedioate; $^{-}ooC–cO–CH_2–COO^{-}$ (keto form) or $^{-}ooC–c(OH)= CH–COO^{-}$ (enol form); the dianion of oxaloacetic acid. It is an important intermediate in metabolism, especially as a component of the **tricarboxylic-acid cycle**. The stereochemistry of the **citrate (*Si*)-synthase** reaction is shown below. **2** any mixture of free oxaloacetic acid and its mono- and dianions. **3** any salt or ester of oxaloacetic acid.



oxalosis the renal and extrarenal deposition of calcium oxalate (*see* **oxalate**) seen in patients with **hyperoxaluria**.

oxalosuccinate **1** *the trivial name for* 2-oxotricarballylate *(formerly* α-ketotricarballylate); 1-oxopropane-1,2,3-tricarboxylate; $^{-}OOC–CO–CH(COO^{-})–CH_2–COO^{-}$; the trianion of oxalosuccinic acid. It is an enzyme-bound intermediate in the conversion of isocitrate to 2-oxoglutarate by **isocitrate dehydrogenase (NAD$^+$)** in the **tricarboxylic-acid cycle**. **2** any mixture of free oxalosuccinic acid and its mono- and dianions. **3** any salt or ester of oxalosuccinic acid.

oxaluria *an alternative name for* **hyperoxaluria**.

oxalyl **1** *(in biochemistry) (sometimes) an alternative name for* **oxalo**. **2** *(in chemistry)* the divalent diacyl group, –CO–CO–, derived from oxalic acid by loss of both hydroxyl groups.

OXBOX a 13 bp sequence (present in the region –123 to –674 bp) of the heart and skeletal muscle gene for the adenine nucleotide translocator and also in the promoter region of the gene for human ATP synthase β subunit. It appears to be a positive translational element.

oxene a reactive species of oxygen involved in the hydroxylation reaction catalysed by cytochrome P450; it is iron-bound oxygen which is electron deficient but electrically neutral $–P450–Fe^{3+}–O$. It reacts with the bound substrate to release the hydroxylated substrate with the regeneration of $P450–Fe^{3+}$.

oxidant the chemical species that accepts one or more electrons in a redox reaction; i.e. the species that undergoes reduction in such a reaction. *Compare* **reductant**.

oxidase any **oxidoreductase** that catalyses a reaction in which dioxygen is the electron acceptor (i.e. **oxidant**).

oxidase test a test for the presence of cytochrome *c* oxidase in bacteria that depends on the oxidation of tetramethyl-*p*-phenylenediamine to a violet-coloured product. It is useful for primary characterization, especially of Gram-negative organisms.

oxidation **1** the action or process of reacting with oxygen, especially the addition of oxygen to a substance. **2** the loss or removal of hydrogen from a substance. **3** the loss or removal of one or more electrons from a molecular entity, with or without concomitant loss or removal of a proton or protons. In this sense, oxidation is the opposite of, and is always coupled to, **reduction**. **4** the increase to a more positive value of the **oxidation number** of an atom, whether the atom is uncharged or charged, and whether free or covalently bound. **—oxidative** *adj.*

***α*-oxidation** *see* **alpha-oxidation**.

***β*-oxidation** *see* **beta-oxidation**.

***ω*-oxidation** *see* **omega-oxidation**.

oxidation level *or* **oxidation state** the status of an organic compound in terms of whether it can be considered to undergo oxidation or reduction (or neither) upon conversion to a related compound. If conversion involves oxidation, the parent compound is said to have a higher oxidation level than the product; if conversion involves reduction, the parent compound is said to have a lower oxidation level. The term is thus used in a relative rather than an absolute sense. *See also* **oxidation number**.

oxidation number *or* **oxidation state** a number assigned to a particular atom in a molecular entity that represents, actually or notionally, the charge on that atom. Thus, atoms of pure elements have an oxidation number of zero; in molecules of simple electrovalent compounds the oxidation number of each component atom is equal to the charge on the respective ion; and in molecules of covalent compounds the notional charge on a particular atom is derived by assigning electrons to the more electronegative partner in each bond involving the atom in question. By convention, hydrogen is considered to have an oxidation number of +1 when in combination with nonmetals. The oxidation number of a carbon atom can range from –4 (e.g. in CH_4) through zero (e.g. in CH_2O or solid C) to +4 (e.g. in CO_2). The oxidation number of an atom may be indicated by a Roman numeral; e.g. iron(III) oxide, ferric oxide, Fe_2O_3. The algebraic sum of the oxidation numbers of all the atoms in any molecular entity must equal the charge on that entity.

oxidation potential a measure of the tendency of a substance to oxidize spontaneously through loss of electrons. It is the standard potential of the half-reaction: $A \rightarrow A^{n+} + ne$ and is equal to the **reduction potential** but of opposite sign.

oxidation–reduction *an alternative term for* **redox**.

oxidation–reduction indicator *an alternative term for* **redox indicator**.

oxidation–reduction potential *an alternative term for* **redox potential**.

oxidation state **1** *an alternative term for* **oxidation number**. **2** *an alternative term for* **oxidation level** (less preferred).

oxidative deamination deamination with concomitant oxidation, as in the enzymic conversion, regardless of the nature of the electron acceptor, of an α-amino acid to an α-oxo acid. *Compare* **reductive amination**.

oxidative decarboxylation decarboxylation with concomitant oxidation, as in the enzymic conversion, regardless of the nature of the electron acceptor, of an α-oxo acid (actually or formally) to a carboxylic acid containing one less carbon atom.

oxidative metabolism *an alternative term for* **respiration** (def. 1).

oxidative pentose phosphate pathway *or* **hexose monophosphate shunt** a route additional to glycolysis in plants that generates: (1) NADPH when it is not being formed by photosynthesis; (2) ribose 5-phosphate required in the biosynthesis of nucleosides; and (3) erythrose 4-phosphate required for biosynthesis of shikimic acid, a key intermediate in the formation of aromatic rings. *See also* **pentose phosphate pathway**.

oxidative phosphorylation *or* **respiratory-chain phosphorylation** the phosphorylation of ADP to ATP that accompanies the oxidation of a metabolite through the operation of the **respiratory chain**. The overall reaction may be summarized by the equation:

$$AH_2 + 0.5O_2 + xP_i + xADP \rightarrow A + (x+1)H_2O + xATP$$

where AH_2 is an oxidizable metabolite, A is the product of the oxidation, P_i is inorganic orthophosphate, and x has a value between 1 and 3 depending on the nature of AH_2 and the functional state of the respiratory chain. The proton gradient built up across the inner mitochondrial membrane by the proton pumps of the respiratory chain drives ATP synthesis by the **H^+-transporting ATP synthase**. *See also* **chemiosmotic coupling hypothesis**.

oxidative stress a state of metabolic imbalance within cells that favours pro-oxidant substances (e.g. superoxide, hydrogen peroxide, hypochlorous acid, nitric oxide, peroxynitrite) rather than antioxidants (e.g. glutathione, ascorbic acid) and antioxidant enzyme systems (e.g. superoxide dismutases, catalase). This leads to oxidative damage to all classes of the major biomolecules. Depending on the degree of imbalance, a cell may die or it might survive in a changed state. Such stress can be important in causing a wide variety of degenerative states, including atherosclerosis, ischemia/reperfusion injury in heart and brain, mutagenesis, and chronic inflammatory disease.

oxide 1 *(in inorganic chemistry)* any binary compound of oxygen and some other element. **2** *an alternative generic name for* any cyclic ether that is an **oxirane**; such a compound is named as the oxide of the alkene from which it may be formed through addition of an atom of oxygen across the double bond; e.g. ethylene oxide, C_2H_4O. **3** *a term used in some languages for* **ether**. **4** any compound in which an oxygen atom has been attached to a heteroatom of a precursor compound. This definition includes compounds of general formulae: $RC{\equiv}NO$ (nitrile oxides; e.g. benzonitrile oxide), $>C{=}N(O)R$ or $R,R',R''NO$ (*N*-oxides, amine oxides; e.g. trimethylamine oxide); and $R,R'SO$ (*S*-oxides, sulfoxides; e.g. methionine *S*-oxide; dimethyl sulfoxide).

+oxide *or* **+olate** *suffix* denoting **1** an anion formed by loss of a proton from the hydroxyl group of an alcohol or phenol; e.g. ethoxide ion, $C_2H_5O^-$. **2** a compound of such an anion with a cation; e.g. sodium phenoxide (i.e. sodium phenolate), C_6H_5ONa. *See also* **epoxide**, **hydroperoxide**, **hydroxide**, **nitroxide**, **peroxide**, **sulfoxide**, **superoxide**.

oxidize *or* **oxidise 1** to undergo or effect **oxidation**. **2** to form or cause to form a superficial layer of oxide on a metal. *Compare* **reduce**. —**oxidization** *or* **oxidisation** *n.*

oxidizer *or* **oxidiser 1** *a less common name for* **oxidizing agent**. **2** a device for effecting a particular oxidation.

oxidizing agent *or* **oxidising agent** any substance or mixture used for effecting **oxidation**.

oxidoreductase *the systematic name for* any enzyme of class EC 1. These enzymes catalyse oxidation–reduction (i.e. **redox**) reactions and the class comprises **dehydrogenases**, **oxidases**, and **reductases**.

oxidoreduction *an alternative term for* **redox**.

oximeter any photometric device for (continuously) measuring the oxyhemoglobin/hemoglobin ratio in blood, either *in vivo* or *in vitro*.

oxine *the trivial name for* 8-hydroxyquinoline; 8-quinolinol. With many species of metal ion this compound forms water-insoluble chelate complexes and thereby is useful in analysis. It is also a disinfectant, and, as the copper chelate, is an effective fungicide.

oxirane 1 *the class name for* any compound containing a three-membered saturated ring comprising two carbon atoms and one oxygen atom. **2** *the systematic name for* the type member of this class, known commonly as ethylene oxide, C_2H_4O.

oxo 1 the chemical group consisting of an oxygen atom, =O, doubly bonded to another atom (often of carbon) in a molecular structure. When bonded to a carbon atom it forms the carbonyl group, $>C{=}O$. *Compare* **oxy**. **2** *or (formerly)* **oxo+** modifying the class-name of a chemical compound to indicate the presence of an oxo group as a substituent in place of two hydrogen atoms; e.g. **oxocarboxylic acid**. The position of substitution may be specified by a predfixed locant; e.g. 17-oxo-steroid. *See also* **keto** (def. 3). *Compare* **oxo** (def. 1).

oxo+ *or (sometimes before a vowel)* **ox+ 1** *prefix (in chemical nomenclature)* indicating substitution of a doubly bonded oxygen atom into a specified compound or group by the (formal or actual) oxidation of a methylene group, $>CH_2$, to a keto group, $>C{=}O$, or of a methyl group, $-CH_3$, to a formyl group, $-CH{=}O$, with the production of a ketone or an aldehyde respectively; e.g. oxoglutaric acid (*see* **oxoglutarate**), 3,6-dioxohexanoic acid (*or* 5-formyl-3-oxopentanoic acid). *Compare* **oxo** (def. 2). **2** *comb. form* denoting presence of one or more (singly or doubly bonded) oxygen atoms in a molecular structure; e.g. **oxoacid**, **oxonium**.

oxoacid 1 *the recommended term for* any compound whose molecular structure contains oxygen, at least one other element, and at least one atom of hydrogen bound to oxygen, and also that yields a conjugate base (*see* **oxoanion**) by loss of a hydron. Examples include: hypochlorous acid, ClOH; sulfurous acid, $O{=}S(OH)_2$; nitric acid, $(O{=})NOH$; [ortho]phosphoric acid, $O{=}P(OH)_3$; and also any phosphonic acid, $RP({=}O)(OH)_2$, and any carboxylic acid, $RC({=}O)OH$ (where R = H or hydrocarbyl). *See also* oxocarboxylic acid. **2** *or* **oxo acid** *or* **oxyacid** *or* **oxy-acid** *the traditional name, now obsolete, for* any acid having oxygen in its acidic function, as opposed to a ‘hydracid’ where oxygen is lacking (e.g. hydrochloric acid, HCl).

oxo acid 1 *see* **oxocarboxylic acid**. **2** *a variant of* **oxoacid** (def. 2).

3-oxoacid CoA-transferase EC 2.8.3.5; *other name*: succinyl-CoA:3-ketoacid-CoA transferase; an enzyme that catalyses the reaction:

succinyl-CoA + 3-oxo acid = succinate + 3-oxoacyl-CoA.

In mammals it converts plasma acetoacetate that has been taken up by tissues into acetoacetyl-CoA for further metabolism.

3-oxoacyl-[acyl-carrier protein] reductase (NADH) EC 1.1.1.212; an enzyme that catalyses the reduction by NADH of 3-oxoacyl-[acyl-carrier protein] to (3*R*)-3-hydroxyacyl-[acyl-carrier protein] with formation of NAD^+. This is one of the steps of fatty acid synthesis in plants. *Compare* **fatty acid synthase complex**.

oxoanion *or (formerly)* **oxo anion** *or* **oxyanion** *or* **oxy-anion** any of the possible anions formable from a molecule of an **oxoacid** (def. 1) by loss of one or more hydrons.

oxobutanedioate *see* **oxaloacetate**.

oxocarboxylic acid *the recommended name for* any **carboxylic acid** that contains an aldehydic group attached to, or/and one or more ketonic groups contained in, its principal chain or parent ring system, i.e. any into which one or more oxo groups have been substituted. The term is commonly shortened to **oxo acid**, but the full name should be used wherever confusion with **oxoacid** is possible. The older term keto acid is often still used (*see* **keto** (def. 3)).

17-oxogenic steroid *or (formerly)* **17-ketogenic steroid** any urinary corticosteroid or its metabolites that can be estimated by the **Zimmermann reaction** after oxidation to the corresponding 17-oxo steroid.

oxoglutarate *or (formerly)* **ketoglutarate**; **1** 2-oxoglutarate *or* α-oxoglutarate 2-oxopentanedioate; $^-OOC{-}[CH_2]_2{-}CO{-}COO^-$; the dianion of 2-oxoglutaric acid (i.e. 2-oxopentanedioic acid), an α-oxo (carboxylic) acid. It is a key constituent of the tricarboxylic-acid cycle and a key intermediate in amino-acid metabolism. In the cycle it is formed by oxidative decarboxylation of isocitrate and converted into a further oxidative decarboxylation reaction to succinyl-coenzyme A. It may also be formed from or converted into glutamate (and thus several other amino acids indirectly) by transamination, or formed by degradation of lysine via glutarate and 2-hydroxyglutarate. The older name **α-ketoglutarate** is often still used. **2** 3-oxoglutarate *or* *β*-oxoglutarate acetonedicarboxylate; 3-oxopentanedioate; $^{-}OOC–CH_2–CO–CH_2–COO^{-}$; the dianion of 3-oxoglutaric acid (i.e. 3-oxopentanedioic acid), a *β*-oxo (carboxylic) acid. It is a product of the action of the mould *Aspergillus niger* on citrate.

oxoglutarate decarboxylase *see* **oxoglutarate dehydrogenase (lipoamide)**.

oxoglutarate dehydrogenase complex an enzyme complex, closely analogous in mechanism to the **pyruvate dehydrogenase complex**. It accomplishes the overall reaction:

$$\text{2-oxoglutarate} + \text{CoA} + \text{NAD}^+ = \text{succinyl-CoA} + \text{CO}_2 + \text{NADH}.$$

It consists of three activities: **oxoglutarate dehydrogenase (lipoamide)**, the E_1 component; **dihydrolipoamide *S*-succinyltransferase**, the E_2 component; and **dihydrolipoamide dehydrogenase**, the E_3 component (this being identical to the E_3 component of the pyruvate dehydrogenase complex).

oxoglutarate dehydrogenase (lipoamide) EC 1.2.4.2; *other names*: oxoglutarate decarboxylase; *α*-ketoglutaric dehydrogenase; an enzyme that catalyses the reaction between 2-oxoglutarate and lipoamide to form *S*-succinyldihydrolipoamide with release of CO_2. This is the E_1 component of the **oxoglutarate dehydrogenase complex**. Thiamine diphosphate is a coenzyme.

oxoglutarate/malate carrier protein *see* **OGCP**.

2-oxoisovalerate dehydrogenase *see* **3-methyl-2-oxobutanoate dehydrogenase (lipoamide)**.

oxolinicacid 5-ethyl-5,8-dihydro-8-oxo-1,3-dioxolo[4,5-*g*]quinoline-7-carboxylic acid; a **4-quinolone antibiotic** with antibacterial activity through inhibition of bacterial DNA gyrase.

oxonium **1** *or (formerly)* **hydronium** *or* **hydroxonium** the ion, H_3O^+, formed by covalent linkage of a hydron to a single water molecule. *Compare* **H⁺(aq)**. **2** any organic entity in which an oxygen atom is linked to three groups (one or two of which may be –H) and bears a formal single positive charge.

5-oxoprolinase an enzyme of microorganisms, plants, and most mammalian tissues that catalyses the reaction:

$$\text{5-oxoproline} + \text{ATP} = \text{glutamate} + \text{ADP} + \text{P}_i.$$

A rare enzyme deficiency in humans produces excessive 5-oxoprolinuria but no other significant symptoms or signs.

(5-)oxoproline *symbol*: Glp *or* <Glu; *the recommended trivial name for* pyroglutamic acid; pyrrolidone carboxylic acid; 5-oxopyrrolidine-2-carboxylic acid; a **noncoded amino acid**. It occurs at the N terminus of certain peptide hormones, and is an intermediate in the *γ*-glutamyl cycle. *Compare* **oxyproline**.

oxo steroid *or* **keto steroid** any steroid having an oxo substituent in its molecular structure, whether in the ring system (as part of a ketonic group) or in a side chain (as part of either a ketonic or an aldehydic group). The position of substitution may be specified by a prefixed locant. The term **17-oxo steroid** (or 17-keto steroid) usually refers specifically to any of a group of androgens and their metabolites that are present in urine and that can be extracted and estimated by the **Zimmermann reaction**. The amount of steroids excreted in the urine has been used as an index of androgen production in the body.

oxosuccinate *see* **oxaloacetate**.

oxphos *a colloquial term for* **oxidative phosphorylation**.

OXT *abbr. for* oxytocin.

oxy the chemical group consisting of an oxygen atom, –O–, singly bonded to two carbon atoms in a molecular structure, e.g. of an epoxide, an ester, or an ether. *Compare* **oxo**.

oxy+ *prefix* denoting **1** *(in organic chemical nomenclature)* the presence of an oxygen atom directly attached (by single covalent bonds) to two moieties of the same indicated parent compound, with formation of a symmetrical ether, where there is a functional group or substituent in the parent compound that has priority over 'ether' for citation as the principal characteristic group; e.g. 3,3′-oxydipropanoic acid (*not* bis(3-carboxypropyl) ether). *See also* **epoxy+**. **2** *(obsolete in organic chemical nomenclature but retained in pharmaceutical nomenclature)* substitution of a hydroxyl group for a hydrogen atom; e.g. oxyproline (*now* hydroxyproline), oxytetracycline. **3** *(in inorganic chemical nomenclature)* formation of a 'basic' (i.e. double) salt containing the oxide anion, O^{2-}, and a specified second anion; e.g. bismuth oxychloride (i.e. bismuth chloride oxide). **4** *or* **oxy-** presence of oxygen in the acidic function of an acid or in the corresponding moiety of a derived anion (obsolete; *see* **oxoacid** (def. 2), **oxoanion**). *comb. form* indicating. **5** dioxygen; e.g. oxybiotic, oxyhemoglobin, oxyhydrogen. **6** oxidation; e.g. oxycellulose. **7** acid; e.g. **oxyntic**.

oxyacid *or* **oxy-acid** *a variant of* **oxoacid** (def. 2).

oxyanion *or* **oxy-anion** *(formerly) a variant of* **oxoanion**.

oxybiontic *or* **oxybiotic** living in the presence of oxygen; aerobic.

oxycellulose any of the various materials obtained by the oxidation of cellulose. Such materials are useful as cation-exchangers or for fabrication into lint and gauzes.

oxygen **1** *symbol*: O; a nonmetallic element of group 16 of the (IUPAC) **periodic table**; atomic number 8; relative atomic mass 15.9994. Naturally occurring oxygen consists of a mixture of three stable nuclides of relative masses 16 (99.759 atom percent), 17 (0.037 atom percent), and 18 (0.204 atom percent). The latter, commonly known as **heavy oxygen**, is useful as a tracer in studies of chemical and biochemical reaction mechanisms. The commonest valence is two. Oxygen is the most abundant element in the biosphere: in the atmosphere it occurs elementally in the form of molecules of the diatomic gas dioxygen, which comprises 20.95 by volume of dry air, and as traces of the gas **ozone** (i.e. trioxygen). The atmosphere also contains small amounts of the oxygen compounds carbon dioxide and water (vapour); almost half by weight of the surface of the Earth consists of oxygen in combined form, principally as water and silicates. **2** *or* **molecular oxygen** *symbol*: O_2; *the common name for* the gas correctly known as **dioxygen**.

oxygen-15 the radioactive nuclide of oxygen, $^{15}_{8}O$. It is prepared in a cyclotron by bombarding $^{17}_{7}N$ with deuterons, the products being $^{15}_{8}O$ and neutrons. It emits a positron, β^+ (0.511 MeV), and has a half-life of 2 min; it is used in positron emission **tomography**.

oxygenase an enzyme that catalyses a reaction in which molecular oxygen is incorporated into an organic compound (the donor). Monooxygenases (EC class 1.13) act upon single donors, and dioxygenases (EC class 1.14) act upon paired donors.

oxygenate **1** to mix, supply, or treat with dioxygen; to saturate a fluid, especially blood, culture medium, etc., with dioxygen. **2** to cause the combination of an oxygen-carrying or oxygen-storing protein with dioxygen; to undergo such a reaction. **—oxygenation** *n.*

oxygenator an apparatus for oxygenation, especially of blood.

oxygen cycle the sum total of the processes via which atmospheric dioxygen is exchanged with the oxygen combined in organic compounds and carbon dioxide. Photosynthetic organisms, using solar energy, generate dioxygen from water and liberate it into the atmosphere, while heterotrophic cells take up atmospheric dioxygen to oxidize organic compounds and thereby provide energy. *Compare* **carbon cycle**.

oxygen debt the oxygen deficit that develops when a normally aerobic organism or tissue cannot increase its oxygen uptake sufficiently to match a temporarily increased energy requirement, as in muscular exercise. After the increased energy requirement ceases, this deficit has to be made good by a continuing increased rate of oxygen uptake until normal aerobic metabolism is restored.

oxygen demand *see* **biochemical oxygen demand**, **chemical oxygen demand**.

oxygen electrode a device for measuring dioxygen activity in a liquid or gas. It consists essentially of a silver–silver chloride anode in saturated potassium chloride solution and a platinum or gold cathode. When an electric potential is applied between these electrodes dioxygen is electrolytically reduced at the cathode, the current flowing being proportional to the dioxygen activity when the applied potential is 0.5–0.8 V. The electrodes are either directly exposed to the sample or, in the **Clark electrode**, separated from it by a thin dioxygen-permeable membrane in order to prevent deposition of interfering substances on the cathode.

oxygen-evolving complex *abbr.*: OEC; a protein-bound complex of manganese and calcium in photosystem II that is responsible for splitting water to oxygen and reducing equivalents. *See* **photosystem**.

oxygen quotient *(sometimes)* the **metabolic quotient** with respect to dioxygen, *symbol*: Q_{02} .

oxygen toxicity toxicity resulting from excessive exposure to gaseous dioxygen. An atmosphere containing 100% oxygen is toxic to animals and cultured animal cells, bacteria, fungi, and plants. In humans, breathing 80–100% oxygen for 8 hours or more causes irritation of the respiratory passages, and after 24–48 hours it causes lung damage. In infants it causes bronchopulmonary dysplasia and retrolental fibroplasia (replacement of the retina by fibrous tissue). Hyperbaric oxygen is toxic to the central nervous system.

oxyhemoglobin *symbol*: HbO_2; the fully oxygenated form of **hemoglobin**. It is bright red in colour, and has a characteristic absorption spectrum.

oxyhydrogen reaction *an alternative name for* **knallgas reaction**.

oxymyoglobin *symbol*: MbO_2; the fully oxygenated form of **myoglobin**. It is bright red in colour, and has a characteristic absorption spectrum.

oxyntic acid-secreting; applied especially to the hydrochloric acid-secreting parietal cells of the gastric mucosa.

oxyntomodulin *an alternative name for* glucagon-37; *see* **enteroglucagon**.

oxyproline *an older name for* **hydroxyproline**. *Compare* **5-oxoproline**.

oxysome *an alternative name for* **elementary particle** (def. 2).

oxysterol receptor *or* **liver X receptor** (*abbr*.: LXR) either of two orphan receptors, LXRα and LXRβ, whose endogenous ligands are oxysterols. Both occur in the enterohepatic system, with LXRα also present in adipose tissues and LXRβ being more widely distributed. Both form obligate heterodimers with **retinoid X receptor** (which binds 9-*cis*-retinoic acid), and the dimer binds to specific hormone response elements on DNA.

oxytetracycline 5-hydroxytetracycline; an antibiotic that is similar in action to **tetracycline**. Proprietary names include Terramycin.

oxytocin *or (sometimes)* **ocytocin** *abbr*.: OXT; a heterodetic cyclic nonapeptide amide,

$$Cys^1\text{-Tyr-Ile-Gln-Asn-}Cys^6\text{-Pro-Leu-Gly-}NH_2$$

(Cys^1 and Cys^6 form a disulfide bond). It is one of the two (or possibly more) hormones secreted by the neurohypophysis of the pituitary gland. It facilitates the ejection of milk by stimulating the myoepithelial cells in the mammary gland, and it may also aid parturition by stimulating contraction of the uterus. It is synthesized as a polypeptide precursor that is cleaved to oxytocin and neurophysin 1 (*see* **neurophysin**). Oxytocin was the first peptide hormone to be chemically synthesized. [*Note*: the spelling ocytocin is preferred on etymological grounds, the name being derived from the Greek *okytokos*, fast birth, rather than from the Greek *oxys*, acid, sharp; however, the spelling oxytocin is in wide use, esp. in the English language.] *See also* **vasopressin**.

oxytocin receptor any of a number of membrane proteins that bind oxytocin, and mediate its intracellular effects. Structurally, they are of the **7TM** type, characteristic of G protein-coupled receptors, and activate the **phosphatidylinositol cycle**.

+oyl *suffix (in chemical nomenclature)* denoting conversion (of a mono- or dicarboxylic acid) to the corresponding mono- or divalent acyl group by removal of hydroxyl from the carboxyl group; e.g. the univalent acyl group, hexanoyl, CH_3–$[CH_2]_4$– CO–, is derived from hexanoic acid, CH_3–$[CH_2]_4$–COOH. It is used also when the carbonyl oxygen atom of the acyl group has been replaced by =NH, =N–NH_2, =N–OH, or =S. *See also* **+yl**.

oz *symbol for* ounce.

ozone *symbol*: O_3; trioxygen; a colourless, highly reactive gas present in the stratosphere, where it is formed under the influence of short-wavelength ultraviolet radiation. It is also normally present in trace amounts in air, and is formed by the action of sunlight on hydrocarbons and nitrogen oxides – present in vehicle emissions. The latter process can lead to harmful accumulations of ozone at or near ground level. In contrast, stratospheric ozone protects the biosphere from highly damaging ultraviolet radiation, especially UV-C. Ozone is also produced by antigen-specific or monoclonal antibodies from excited dioxygen released by phagocytes or generated during inflammation. No enzyme is known that catabolizes ozone.

ozonolysis a method used for locating a double bond in an alkene. The alkene is treated with ozone, and the resulting ozonide is then cleaved to form two carbonyl compounds, one from each moiety of the parent compound.

Pp

p *symbol for* **1** pico+ (SI prefix denoting 10^{-12} times). **2** the negative logarithm .to the base ten, as in pH, p*K*. **3** proton; it may be written as p^+ to indicate its charge. **4** a phosphoric residue (alternative to *P*). **5** the protein product of a gene; it is prefixed to the product's molecular mass to designate a particular entity, e.g. **p53**. **6** (*in atomic spectroscopy*) electron state $l = 1$.

p21 a protein (21 kDa) inhibitor of cyclin-dependent kinases of the G_1 phase of the cell-division cycle. It is induced by **p53** and is believed to contribute to cell-cycle arrest in the presence of damaged DNA, and to facilitate withdrawal from the cell cycle of cells undergoing terminal differentiation.

p53 a 53 kDa nuclear phosphoprotein originally discovered attached to large T-antigen in cells transformed with **simian virus 40**. It is a probable human cell cycle regulator and *trans*-activator (*see* ***trans*-acting**) that acts negatively to regulate cellular division by controlling a set of genes required for this process; one of the genes activated is an inhibitor of **cyclin-dependent protein kinases**. p53 acts as a tumour suppressor in some (not all) tissues; mutations in the p53 gene are the most common genetic alterations in human cancers. Wild-type p53 can suppress or inhibit the transformation of cells in culture either by viral or cellular oncogenes, and introduction of wild-type cDNA into a transformed cell in culture stops growth. Hence the p53 gene is classed as a **tumour-suppressor gene**. Three functional domains of p53 have been defined: an N-terminal transcriptional activation domain (residues 1–42), a central DNA-binding domain (residues 120–290), and a C-terminal regulatory domain (residues 311–393). The DNA-binding domain recognizes a Dna motif in genes that are activated by p53, and mutations in p53 that are associated with human cancers generally cluster in its DNA-binding domain.

p56 *see* **Lck**.

p *symbol for* **1** pressure (alternative to *P*). **2** partial pressure of a gas. The gas may be specified by a subscript or in parentheses; e.g. p_{O2} or $p(\mathrm{O_2})$. **3** pyranose form (in monosaccharide symbolism); e.g. Glc*p*, glucopyranose; Gal*p*A, galactopyranuronic acid. **4** pitch height (of a helix). **5** (bold italic) (electric) dipole moment (of a molecule), alternative to μ (bold italic). **6** (bold italic) momentum. **7** probability (alternative to *P*).

***p*-** *prefix (in chemical nomenclature)* denoting ***para*-**. *Compare* ***m*-**, ***o*-**.

***p*$_{50}$** *symbol for* the partial pressure of a gas at which a binding protein is 50% saturated with it.

***p*$_{LR}$** *symbol for* the proportion of receptors or binding sites occupied by ligand L.

***p*$_{LR*}$** *symbol for* the proportion of receptors in which ligand L occupies its binding site(s), and which are in an active state.

***p*$_{R}$** *symbol for* the proportion of receptors or binding sites free of ligand.

P *symbol for* **1** peta+ (SI prefix denoting 10^{15} times). **2** poise. **3** phosphorus. **4** a residue of the α-amino (strictly, cyclic α-alkylamino) acid proline (alternative to Pro). *abbr. for* **5** phosphate or a phosphoric group, as in ATP. **6** *(in genetics)* parental generation. **7** a site near a peptidase cleavage site (*see* **peptidase P-site**).

P$_i$ *symbol for* inorganic phosphate.

P0 a **myelin protein**.

P1 a temperate bacteriophage whose natural hosts are *Shigella* spp. but which was used formerly for generalized transduction in *Escherichia coli* and is currently used as the basis for the **P1 cloning vector**, which can carry up to 100 kbp insert DNA. P1 prophage is a plasmid.

P2 a **myelin protein**.

P65 *see* **synaptotagmin**.

P81 *see* **ezrin**.

P450 *or* **P-450** any of a group of widely occurring heme-containing proteins that embraces various separately classified enzymes. They are named from the location of the Soret band (*see* **cytochrome absorption bands**) of the reduced CO complex at 450 nm. The group includes unspecific monooxygenase (EC 1.14.14.1), camphor 5-monooxygenase (EC 1.14.15.1), alkane 1-monooxygenase (EC 1.14.15.3), steroid 11β-monooxygenase (EC 1.14.15.4), **cholesterol monooxygenase (side-chain-cleaving)** (EC 1.14.15.6), prostacyclin synthase (EC 5.3.99.4), **thromboxane-A synthase** (EC 5.3.99.5), and probably chloride peroxidase (EC 1.11.1.10). This type of enzyme is also known as **cytochrome P450** (see this for more detail), and considered as a *b*-type **cytochrome**. The name heme-thiolate protein has been proposed on the grounds of a thiolate ligand at the heme being responsible for the group's unusual spectral and catalytic properties.

P680 *or* **pigment 680** a type of chlorophyll *a*, having an absorption maximum at 680 nm, that constitutes the reaction centre of **photosystem** II in most species. It has a redox potential of >+0.81 V; the oxidized form, P680$^+$, is a powerful oxidant that can abstract electrons from water with the evolution of dioxygen. *See also* **chlorophyll**.

P700 *or* **pigment 700** a type of chlorophyll *a*, having an absorption maximum at 700 nm, that constitutes the reaction centre of **photosystem** I. It has a redox potential of approximately +0.5 V, its electron being used ultimately to reduce NADP via ferredoxin. *See also* **chlorophyll**.

P870 the special pair of bacteriochlorophyll *a* in the **photosynthetic reaction centre** of bacteria, so named because they have an absorption maximum of 870 nm.

P960 the special pair of bacteriochlorophyll *b* in the **photosynthetic reaction centre** of bacteria, so named because they have an absorption maximum of 960 nm.

P *symbol for* **1** pressure (alternative to *p*). **2** radiant power (alternative to Φ). **3** probability (alternative to *p*). **4** parity (of a wave function).

Pa *symbol for* pascal.

pA$_2$ the negative logarithm to the base 10 of the molar concentration of antagonist that makes it necessary to double the concentration of agonist needed to elicit the original submaximal response.

p[A]$_{50}$ the negative logarithm to the base 10 of the $[A]_{50}$ of an agonist. pEC$_{50}$ is the corresponding term for the **EC$_{50}$** of an agonist (often used interchangeably with $[A]_{50}$).

PAB *or* **PABA** *abbr. for para*-aminobenzoate; *para*-aminobenzoic acid. *See* ***p*-aminobenzoic acid**.

PABA test an indirect test of pancreatic function in which the synthetic peptide *N*-benzoyl-L-tyrosyl-*p*-aminobenzoic acid (BT-PABA) is administered orally, usually with a small amount of [^{14}C]-*p*-aminobenzoic acid (PABA). Normally the peptide is hydrolysed by chymotrypsin to PABA, which is absorbed and excreted in the urine, but in pancreatic insufficiency hydrolysis is much reduced.

PABP-2 *abbr. for* polyadenylation binding protein 2; a nuclear protein present in all tissues, but especially in skeletal muscle, that is needed for elongation of the poly(A) tail at the 3′ untranslated region of eukaryotic mRNA. The human gene contains a (GCG) repeat for a polyalanine stretch at the N-terminus of the protein. The repeat number is increased in oculopharyngeal muscular dystrophy.

PACAP *abbr. for* pituitary adenylate cyclase-activating polypeptide; a preganglionic neuropeptide that stimulates expression of genes for chromogranins A and B (all of which have a cAMP response element in their promoter) in neuroendocrine cells. When released by melanopsin-containing retinal axons it transmits photic information.

pacemaker reaction any metabolic reaction whose rate depends on factors other than the amounts of enzyme or substrate. An enzyme catalysing such a reaction may be termed a **pacemaker enzyme**.

pachyman *see* **callose**.

pachytene the third phase of prophase I in **meiosis**.

package 1 *(in cell biology)* to surround (one or a number of macromolecules) with a membrane in the formation of a mature secretory granule. **2** *(in virology)* to enclose the nucleic-acid core of a virus particle with a protein shell (the capsid) to form a mature virion; to encapsidate.

packaging cell line any mammalian cell line modified for the production of recombinant retroviruses. They express essential viral genes that are lacking in the recombinant retroviral vector.

packaging extract a lysate of *E. coli* in which all but one of the capsid and tail proteins of bacteriophage lambda have been expressed. A mixture of two such lysates lacking different proteins is capable of packaging recombinant lambda genomes with high efficiency *in vitro*.

packing *(in chromatography)* the material (whether active solid, liquid held on solid support, or swollen gel) that is introduced into a column and that consists of or contains what is to become the stationary phase during a chromatographic separation.

packing density the ratio of the minimum (or actual) volume of an object, such as a molecule in a crystal or in solution, to the total volume it occupies. For a macromolecule or region of a macromolecule, it is the ratio of the volume enclosed by the van der Waals envelope of all atoms in the molecule or region to the total volume of the molecule or region. Theoretical values are 0.74 for close-packed spheres, 0.91 for infinite cylinders, and 1.0 for a continuous solid.

packing fraction the ratio of the relative atomic mass of a particular nuclide minus its nucleon number divided by its nucleon number. It is positive for the lightest and heaviest nuclides and negative for nuclides of intermediate mass.

Paclitaxel *a proprietary name for* **taxol**.

p21-activated protein kinase *see* **PAK**.

PAF *abbr. for* platelet-activating factor.

PAF-AH *abbr. for* platelet-activating factor acetylhydrolase. *See* **lipoprotein-associated phospholipase A2**.

PAGE *abbr. for* polyacrylamide gel electrophoresis.

PAGIF *abbr. for* polyacrylamide gel isoelectric focusing. *See* **polyacrylamide gel electrophoresis**.

PAH *abbr. for para*-aminohippurate; *para*-aminohippuric acid.

pair *see* **base pair**.

paired the gene for a sequence-specific DNA-binding homeobox segmentation protein in *Drosophila melanogaster*. It is one of a number of **pair-rule genes**, each of which specifies a simple alternation with a repeat distance of two segments. Their protein products are characterized by a paired-box DNA-binding domain of ≈128 amino acids, which consists of two subdomains each resembling a homeobox domain.

paired box *see* ***paired***, ***Pax*** **genes**.

pair-rule gene any of the eight genes in *Drosophila* that regulate the segment polarity genes. Examples are *hairy*, *runt,* and *paired.*

pairwise alignment *see* **alignment**.

pairwise alignment algorithm *see* **alignment algorithm**.

PaJaMa experiment *the nickname for* a bacterial mating experiment carried out at l'Institut Pasteur, Paris, that showed that induction and repression of the enzyme β-galactosidase in *Escherichia coli* are regulated by two closely linked genes, one of which produces a cytoplasmic repressing substance that blocks the expression of the other. [From the names of the experimenters: Pardee, and French molecular biologists François Jacob (1920–) and Jacques Monod (1910–76).]

PAK *abbr. for* p21-activated protein kinase; any of a family of protein serine/threonine kinases activated by p21 and Cdc42/Rac (a Rho GTPase involved in regulation of the actin cytoskeleton), that are differentially expressed in mammalian cells. PAKs are upstream modulators of protein kinase cascades involved in regulation of apoptosis and in morphogenesis. They have an N-terminal p21-Cdc42/Rac-binding domain and a C-terminal catalytic domain. PAK1 localizes with actin filaments of the cytoskeleton. PAK2 is cleaved into its two domains by certain caspases. A mutation in PAK3 results in an X-chromosome-linked form of mental retardation.

palindrome 1 any linear arrangement of symbols, such as letters or digits, that has the same sequence from either end; e.g. noon, radar; 75311357; 'Madam, in Eden I'm Adam'. **2** *(in molecular biology)* **palindromic sequence** a DNA sequence with a twofold rotational axis of symmetry (**dyad symmetry**). Confusingly the term is used in at least two senses: (1) to describe a region of local twofold rotational symmetry in duplex DNA, e.g.

5′-GAATTC-3′ 3′-CTTAAG-5′

and (2) to describe a sequence in a single polynucleotide strand that contains an inverted repeat, e.g. 5′-TGA-AGT-3′. It is also applied to a region of a single- or a double-stranded polynucleotide that is capable of forming one or more **hairpins** containing palindromes of the first type; an example is shown at **cruciform**. Examples of palindromes are **operators** and **restriction sites** but, in general, any stem–loop in RNA must have a corresponding palindrome in the DNA from which the RNA was transcribed. —**palindromic** *adj.*

pallidin any of a group of endogenous carbohydrate-binding proteins (**lectins**) produced by cells of the slime mould *Polysphondylium pallidum* during differentiation. Similar to **discoidin**, they may be involved in cell adhesion.

palmitate 1 *numerical symbol*: 16:0; *the trivial name for* hexadecanoate, CH_3–$[CH_2]_{14}$–COO^-, the anion derived from palmitic acid (i.e. hexadecanoic acid), a saturated straight-chain higher fatty acid. **2** any mixture of free palmitic acid and its anion. **3** any salt or ester of hexadecanoic acid. *See also* **palmitoyl**.

palmitate synthase *see* **fatty-acid synthase complex**.

palmitic acid hexadecanoic acid; a saturated straight-chain fatty acid having sixteen carbon atoms per molecule, and a major component of plant and animal fats. *See* **palmitate**.

palmitoleate 1 *numerical symbol*: 16:1(9); *the trivial name for* (*Z*)-hexadec-9-enoate, CH_3–$[CH_2]_5$–CH=CH–$[CH_2]_7$–COO^-, the anion derived from palmitoleic acid, (*Z*)-hexadec-9-enoic acid, a monounsaturated straight-chain higher fatty acid. **2** any mixture of free palmitoleic acid and its anion. **3** any salt or ester of 9-hexadecenoic acid. *See also* **palmitoleoyl**.

palmitoleic family (of polyunsaturated fatty acids) a series of polyenoic acids in which the hydrocarbon chain terminates with the alkenyl grouping CH_3–$[CH_2]_5$–CH=CH– (as in palmitoleic acid (*see* **palmitoleate**)); there are three other series of such acids, i.e. the **linoleic family**, **linolenic family**, and **oleic family**. Members of the palmitoleic family can be synthesized from palmitic acid via palmitoleic acid by chain elongation and/or desaturation, but in mammals not from linoleic, (9,12,15)-linolenic, or oleic acids; the series includes *cis*-vaccenic acid.

palmitoleoyl *symbol*: ΔPam; *the trivial name for* (*Z*)-hexadec-9-enoyl, CH_3–$[CH_2]_5$–CH=CH–$[CH_2]_7$–CO– (*cis* isomer), the acyl group derived from palmitoleic acid (i.e. (*Z*)-hexadec-9-enoic acid). It is a relatively minor component of plant and animal lipids. The chain is synthesized metabolically by the action of a Δ^9-desaturase on palmitoyl-CoA.

palmitoyl *symbol*: Pam; *the trivial name for* hexadecanoyl, CH_3–$[CH_2]_{14}$–CO–, the acyl group derived from palmitic acid (i.e. hexadecanoic acid). This is one of the major fatty-acid components of plant and animal lipids; together with stearic acid it represents a high proportion (often around 30%) of the fatty-acid content of dietary and other lipids. It acts as a precursor in mammals for a family of unsaturated fatty acids in which all double bonds are nine or more carbons from the methyl terminus. The chain is synthesized metabolically from acetyl-CoA as palmitate (in mammals) or palmitoyl-CoA (in yeast), the product of fatty-acid synthase. See **fatty-acid synthase complex**.

palmitoyl-protein thioesterase EC 3.1.2.22. a lysosomal enzyme that cleaves the thioester linkage formed by a palmitoyl moiety with a cysteine side chain near a transmembrane segment of an integral membrane protein. Mutations in this gene on 1p32 cause infantile neuronal lipofuscinosis and progressive myoclonic epilepsy.

palmityl 1 *or* **cetyl** *a common name for* hexadecyl, CH_3–$[CH_2]_{14}$–CH_2–, the alkyl group derived from hexadecane. **2** *a former name (now incorrect) for* **palmitoyl**.

palytoxin any of a group of structurally very similar potent neurotoxins isolated from the marine zoanthid *Palythoa toxica* or other *Palythoa* spp. Each consists of a single carbon chain of 115 carbon atoms containing 64 chiral centres and seven double bonds, and terminating in nitrogen-containing groups; there are 128 carbons in all and a further double bond in a methylene group. The chain bears numerous hydroxyl groups and a number of methyl groups, and in several places it is folded and formed into pyran rings. Palytoxin is the most deadly nonproteinaceous material isolated, having 50 times the toxicity of **tetrodotoxin** in mice. The number of stereoisomers is 2^{64} = 18446744073709551620 (not including possible *E*/*Z* variations at the double bonds!).

Pam *symbol for* **palmitoyl** (i.e. hexadecanoyl).

PAM *abbr. for* **1** point accepted mutation. *See* **PAM matrix**. **2** peptidylglycine *α*-amidating monooxygenase. *See* **peptide amidation**.

PAM matrix *abbr. for* point accepted mutation matrix; *see* **point accepted mutation**, **substitution matrix**.

pancreas a compound gland, occurring in the abdominal cavity of most vertebrates, that has both exocrine and endocrine functions. The major (exocrine) part consists of acinar tissue, which secretes **pancreatic juice** into the upper part of the gut (duodenum in mammals). Within this acinar tissue are scattered numerous (endocrine) **islets of Langerhans**, containing notably A cells, secreting **glucagon**, B cells, secreting **insulin**, and D cells, secreting **somatostatin**. —**pancreatic** *adj.*

pancreastatin a 49-residue peptide hormone that inhibits glucose-induced insulin release and exocrine pancreatic secretion. It was originally isolated from porcine pancreas, where it is colocalized with insulin, glucagon and somatostatin, but it is part of the sequence of **chromogranin** A and is thus found in tissues where the chromogranin gene is expressed, including most endocrine cells.

pancreatic cholera *an alternative name for* **Verner–Morrison syndrome**.

pancreatic diabetes *an older term for* insulin-dependent **diabetes mellitus**.

pancreatic DNase I *an alternative name for* **deoxyribonuclease I**.

pancreatic hormone *or* **pancreatic polypeptide** *abbr.*: PP; a polypeptide present in the **PP cells** of the pancreas. Avian pancreatic polypeptide, known as aPP (from chicken and turkey pancreas), and bovine, human, ovine, and porcine homologues, known as bPP, hPP, oPP, and pPP, respectively, have been identified. All contain 36 amino-acid residues with C-terminal tyrosinamide and show considerable sequence homology. The plasma PP level rises rapidly after feeding, especially with protein foods, and with fasting, exercise, and hypoglycemia. The hormone decreases food absorption and pancreatic exocrine secretion. The sequence of human PP is: APLEPVYPGDNATPEQMAQYAADLRRYINMLTRPRY(NH_2).

pancreatic islet *an alternative name for* **islet of Langerhans**.

pancreatic juice a slightly alkaline digestive juice secreted by the exocrine pancreas into the upper part of the small intestine. It contains numerous enzymes and inactive enzyme precursors including **α-amylase**, chymotrypsinogen, **lipase**, procarboxypeptidase, proelastase, prophospholipase A_2, ribonuclease, and trypsinogen. Its high concentration of hydrogencarbonate ions helps to neutralize the acid digesta from the stomach.

pancreatic lipase a Ca^{2+}-requiring triacylglycerol lipase (EC 3.1.1.3) that is secreted into the intestine by the exocrine pancreas when this is stimulated by cholecystokinin in response to ingestion of food. It degrades triacylglycerols, partially or completely, to fatty acids and glycerol in the intestine; it acts at an ester–water interface. It is a glycoprotein with sequence similarity with other lipases.

pancreatic polypeptide *abbr.*: PP; *another name for* **pancreatic hormone**.

pancreatic ribonuclease see **ribonuclease**.

pancreatic thread protein *or* **pancreatic stone protein** (*abbr.*: PSP); a C-type lectin that may inhibit spontaneous calcium carbonate precipitation, and one of the major secretory proteins of the human exocrine pancreas. It is found in acinar cells of pancreas and (in smaller amounts) in the brain. It is a major soluble protein of human pancreatic calculi, and a Ca^{2+}- binding phosphoprotein present in zymogen granules of pancreatic acinar cells, and secreted in pancreatic juice of normal subjects and calculus formers. It inhibits calcium carbonate precipitation from the juice. The protein is rich in aromatic amino acids. Between pH 5.4 and 9.2, it undergoes reversible fibril formation. It is also typically characteristic of infant brains. There is increased expression of PSP-like proteins in Down's syndrome and Alzheimer's disease.

pancreatic trypsin inhibitor *abbr.*: PTI; a serine proteinase inhibitor, *correctly known as* **pancreatic secretory trypsin inhibitor**. A protein isolated from bovine pancreas, it forms a crystalline complex with trypsin and is relatively heat-stable in trichloroacetic acid solution. It controls trypsin activation of zymogens. The bovine protein has the sequence: NILGREAKCTNEVNGCPRIYNPVCGTDGVTYSNECLLCMENKERQTPVLIQKSGPC. The 3-D structure is also known, and it is a favoured model for testing protein-folding algorithms. It was also formerly known as **Kunitz and Northrop inhibitor**.

pancreozymin *abbr.*: PZ; a hormone having secretagogic activity on the exocrine pancreas and extractable from duodenal mucosa. It is identical with **cholecystokinin**.

PANK *abbr. for* pantothenate kinase.

panning *(in cell biology)* a method for enriching a population of cells, or phages, displaying peptides or fragments of antibodies by allowing them to bind to ligands immobilized on a solid surface such as that of a **microtitre plate**. Washing the wells of the plate removes nonadherent or weakly adherent cells or phages, leaving those adhering as a result of stronger interactions, to be collected for further study. Several cycles of enrichment are used.

panose an oligosaccharide, Glc(*α*1-6)Glc(*α*1-4)Glc; it is found in the fungus *Aspergillus niger*.



panose

pantetheine *N*-pantothenylcysteamine; the D-enantiomer is a growth factor for *Lactobacillus bulgaricus*, and is an intermediate in the pathway for the biosynthesis of coenzyme A in mammalian liver and some microorganisms.



pantoate **1** the anion, HO–CH_2–$C(CH_3)_2$–CH(OH)–COO^-, derived from pantoic acid (i.e. (*R*)-2,4-dihydroxy-3,3-dimethylbutyric acid). **2** any salt or ester of pantoic acid.



pantoic acid

pantophysin a member of the **physin** family of proteins. It is ubiquitously expressed, is homologous with synaptophysin, and is present in constitutive transport vehicles.

pantothenate **1** the anion, $HO–CH_2–C(CH_3)_2–CH(OH)–CO–NH–CH_2–CH_2–COO^–$ (i.e. *N*-pantoyl-*β*-alanine anion), derived from pantothenic acid, a B vitamin complex; only the D-(*R*)-enantiomer is biologically active. **2** any salt of pantothenic acid.



pantothenic acid

pantothenate kinase *abbr*.: PANK. EC 2.7.1.33; a kinase enzyme that is specific for phosphorylation of pantothenate to 4′-phosphopantothenate, being the first reaction in the biosynthesis of coenzyme A. Many mutations in the gene for PANK2 (locus at 20p13) produce enzyme deficiency and Hallervorden–Spatz syndrome, a neurodegenerative disease involving accumulation of iron in the brain.

pantothenyl the acyl group, $HO–CH_2–C(CH_3)_2–CH(OH)–CO–NH–CH_2–CH_2–CO–$, derived from pantothenic acid; coenzyme A is a D-(*R*)-pantothenyl derivative.

pantoyl **1** the acyl group, $HO–CH_2–C(CH_3)_2–CH(OH)–CO–$, derived from pantoic acid, 2,4-dihydroxy-3,3-dimethylbutyric acid.

PaO *abbr. for* pheophorbide *a* oxygenase.

PAP *abbr. for* peroxidase–antiperoxidase.

papain *or* **papaya peptidase I** EC 3.4.22.2; a cysteine endopeptidase obtained from the latex, leaves, and unripe fruit of the papaya (or pawpaw) tree, *Carica papaya*. It will preferentially hydrolyse peptide bonds at the carbonyl end of Arg, Lys, and Phe residues (but never Val), with preference for large hydrophobic residues at the P2 position. It also has esterase, thiolesterase, transamidase, and transesterase activity. Papain is unusually stable to elevated temperatures and to denaturing agents, and consists of a single polypeptide chain of 212 amino-acid residues.

papaverine 1-[(3,4-dimethoxyphenyl)methyl]-6,7-dimethoxyisoquinoline; a constituent of **opium** that acts as a smooth muscle relaxant; this action is thought to be due to phosphodiesterase inhibitory activity and blockade of membrane calcium channels. Like codeine and morphine it is a metabolic derivative of (*S*)-reticuline.



paper chromatogram the visible result of a chromatographic separation effected on paper.

paper chromatography *abbr*.: PC; a technique of **chromatography**, applicable to microgram quantities of soluble substances, in which specially prepared filter paper, **chromatography paper**, forms the support for the stationary phase. The latter is commonly a film of water held by adsorption on the cellulose fibres of the paper and in equilibrium with a water-immiscible liquid or liquid mixture, which forms the mobile phase. A solution of a sample is applied near one end of a strip of paper, allowed to dry, and the mobile phase allowed to flow over the strip from that end. If the sample consists of only one component, development using an appropriate method of detection will reveal a single spot at a characteristic distance from the origin relative to that travelled by the mobile phase; in general, a mixture will give rise to a number of spots each occupying a different and characteristic position. Separations occur essentially by partition between the mobile and stationary phases, with some contribution, under certain conditions, attributable to adsorption or ion-exchange onto the paper support. An elaboration of the technique uses a square of paper on which two successive separations are effected at right-angles using mobile phases of differing separatory powers to produce a two-dimensional pattern of spots on the paper. With suitable treatment of the paper and an appropriate choice of the composition of the two phases, reversed-phase partition chromatography on paper may be effected. Since cellulose is chiral, some enantiomer separations are possible.

paper electrophoresis a type of **zone electrophoresis** on (filter) paper.

Papovaviridae a family of DNA viruses, most or all of which are, under suitable conditions, oncogenic in vertebrate hosts. The virion, 45–55 nm in diameter, consists of a nonenveloped icosahedral capsid with 72 capsomeres, and contains a circular DNA genome.

papovavirus any virus belonging to the family **Papovaviridae**. The name derives from papilloma, polyoma, and vacuolating agent, an early name for **simian virus 40**.

PAPP-A *abbr. for* pregnancy-associated plasma protein A; a plasma protein first found in the serum of pregnant women but also present in men. It is a zinc metalloprotease secreted by fibroblasts and cleaves **insulin-like growth factor binding protein** (IGFBP)-4 to release insulin-like growth factor (IGF).

PAPS *abbr. for* 3′-phosphoadenosine-5′-phosphosulfate; i.e. adenosine 3′-phosphate 5′-phosphosulfate.

par+ *a variant form of* **para+** (before a vowel).

PAR *abbr. for* protease-activated G-protein-coupled receptor; any G-protein-coupled membrane receptor of platelets and endothelial cells that becomes activated on binding thrombin and cleavage of the extracellular segment of the receptor. Most mouse embryos that lack PAR1 die in mid-gestation.

para **1** characterized by or relating to (substitution at) two ring-carbon atoms separated by two others in a monocyclic aromatic compound. **2** (*followed by* to) at a position in a benzene ring next but two to a particular (specified) substituent. *See also* ***para-***.

para+ *or (before a vowel)* **par+** *prefix* indicating beside or near; beyond; resembling; defective or abnormal.

para- *abbr*.: *p*-; *prefix (in chemical nomenclature)* denoting an isomer of a disubstituted monocyclic aromatic compound in which the substituents are attached at positions 1 and 4 of the ring. *Compare* ***meta-***, ***ortho-***.

parabiont either individual of a pair united in **parabiosis**.

parabiosis the state or condition of two individual animals being functionally united, either naturally, as in Siamese twins, or as a result of an experimental procedure. —**parabiotic** *adj.*

paracasein *an alternative name (esp. US) for* **casein** (def. 2).

paracentric *(in cytogenetics)* describing an inversion of part of a chromosome that does not span the centromere, and is thus confined to one arm of the chromosome. *Compare* **pericentric**.

paracetamol *see* **acetaminophen**.

paracrine **1** describing or relating to a regulatory cell that secretes an agonist into intercellular spaces in which it diffuses to a target cell other than that which produces it; describing or relating to such an agonist. **2** such an agonist; a **paramone**. *Compare* **endocrine**, **neurocrine**, **neuroendocrine**.

paracrystal any assemblage of molecules or particles having a certain degree of order but one that is insufficient for it to be considered a true crystal. —**paracrystalline** *adj.*; **paracrystallinity** *n.*

paradaxin *or* **pardaxin** any of several ichthyotoxic, neurotoxic peptides, isolated from the defence secretion of the Red Sea Moses sole fish, *Paradachirus marmoratus*, or the Pacific sole, *Paradachirus pavoninus*, that act as a shark repellent. Each consists of 33 amino acids, with hydrophilic C-terminal and hydrophobic N-terminal regions, and with physical and pharmacological similarities to **melittin,** but no sequence similarity.

paraffin 1 *an obsolete term for* **alkane**. 2 *or* **paraffin oil** *or* **kerosene** *or* **kerosine** any liquid mixture, consisting mainly of alkanes, with a boiling point range of 150–300 °C and relative density range of 0.78–0.82. 3 *an alternative name for* **paraffin wax**. *Compare* **liquid paraffin**.

paraffin wax any waxy mixture of higher alkanes, obtained as a residue from the distillation of petroleum, with a relative density of ≈0.9 and a melting point range of 45–65 °C.

Parafilm *the proprietary name for* a flexible, moisture-proof, thermoplastic tissue useful for temporarily sealing small containers.

parafollicular cell *an alternative name for* **C cell** (when found in the thyroid gland).

parafusin an evolutionarily conserved phosphoglycoprotein involved in exocytosis. It is rapidly dephosphorylated via a Ca^{2+}-dependent process when secretagogues induce exocytosis in competent cells.

parahematin *or (esp. Brit.)* **parahaematin** *a former name for* **ferrihemochrome**.

parahemophilia a bleeding disorder due to deficiency of factor V. *See* **blood coagulation**.

parallel 1 *(in biochemistry)* describing a pair of linear structures, such as two polynucleotide or polypeptide chains, that are polarized or asymmetric in the same direction. 2 *(in physical chemistry)* denoting the spins of a pair of electrons, occupying the same atomic or molecular orbital, that are described by the same spin quantum number. *Compare* **antiparallel**. 3 *(in electricity)* describing an electrical component that is connected to the same two points in a circuit as another component; describing two or more components that are so connected.

parallel dichroism *see* **dichroic ratio**.

parallelism the quality or state of being parallel; similarity in corresponding details or in evolutionary pattern.

paralogue *or (esp. US)* **paralog** a gene, protein, or biopolymeric sequence that is evolutionarily related to another by descent from a common ancestor, having diverged as a result of a gene duplication event within an organism. Paralogues usually perform different but related functions within that organism as, for instance, human red and green opsins. **–paralogous** *adj.*

paramagnetism the property displayed by substances that have a positive but small magnetic susceptibility, due to the presence in them of atoms with permanent magnetic dipoles caused by unpaired electron spins (with a contribution from the orbital motion of the electrons). These dipoles tend to align themselves in the direction of an applied magnetic field but no permanent magnetism is conferred on such substances. *Compare* **diamagnetism**, **ferromagnetism**. **—paramagnetic** *adj.*

paramecium (*pl.* **paramecia**) any freshwater protozoan belonging to the genus *Paramecium*. Typically 50–300 µm in length, they are ovoid and uniformly ciliated. *See also* **kappa particle**.

parameter 1 *(in mathematics)* an unknown quantity that is a constant in a particular context but that may have different values in other (similar) contexts; e.g. the coefficient b in the general equation, $y = bx + c$, representing a family of straight lines. 2 *(in statistics)* a numerical characteristic of a population (as opposed to that of a sample of such a population). 3 any distinguishing characteristic of something, especially one to which a measured value is or can be ascribed. **—parametric** *adj.*

paramomycin an aminoglycoside antibiotic produced by *Streptomyces paromomycinus*. Its actions are similar to those of **neomycin**.

paramone *a proposed name for* **paracrine** agonist, derived as a contraction of ‘paracrine hormone’.

paramylon a storage polysaccharide occurring in *Euglena gracilis*. It comprises a backbone of $\beta1\rightarrow3$-glucopyranose units with side chains joined by $\alpha1\rightarrow6$ linkages.

paramyosin a two-chain, coiled-coil, α-helical ~200 kDa protein that forms the core protein of the thick filaments of a number of invertebrate muscles.

paramyxovirus any RNA animal virus of the family Paramyxoviridae (distinguish from the genus Paramyxovirus), in class V of the **Baltimore classification. Paramyxoviruses** consist of enveloped, pleomorphic particles ≈150 nm in diameter with helical nucleocapsids, 1000 nm long and 18 nm in diameter. They contain single-stranded RNA (minus strand) of 7 MDa plus virion polymerase. The group includes viruses causing mumps, measles, Newcastle disease of chickens, and distemper of dogs, and the morbilliviruses, pneumoviruses, and parainfluenza viruses.

paranemic describing the nature of the coiling of a double-stranded helix in which the two strands are not intertwined, i.e. they may be separated without uncoiling. *Compare* **plectonemic**.

paraoxonase aryldialkylphosphatase, EC 3.1.8.1; an enzyme that hydrolyses organophosphates. The name derives from its ability to hydrolyse paraoxon, diethyl-p-nitrophenyl phosphate, a cholinesterase inhibitor that is used as a pesticide. The enzyme has antioxidant properties and its physiological substrates are probably the products of lipid peroxidation.

parapepsin I *an alternative name for* **pepsin B**.

parapepsin II *an alternative name for* porcine **gastricsin** (i.e. pepsin C).

paraplegin a mitochondrial **AAA protease** (88 kDa) that is highly homologous with yeast metalloproteases and has proteolytic and chaperone functions at the inner mitochondrial membrane. It is encoded on nuclear DNA. Mutated paraplegin results in hereditary spastic paraplegia and respiratory chain defects.

paraprotein *name originally given to* any plasma protein that gave an abnormal band on electrophoresis, derived from **para+** + protein. Usually, such a protein is a monoclonal immunoglobulin derived from neoplastic plasma cells, and present at abnormally high concentration in the blood plasma. Such proteins are seen as a discrete band in the gamma-globulin region, but they may appear elsewhere if the paraprotein is IgA or IgM. Examples are proteins characteristic of a **myeloma**, e.g. **Bence-Jones protein**, amyloid proteins, **Waldenstrom's macroglobulinemia**, or cryoglobulins. Some paraproteins are not abnormal, e.g. the immunoglobulin that arises as a result of a severe bacterial infection.

paraproteinemia *or (esp. Brit.)* **paraproteinaemia** the presence in blood plasma of **paraprotein**.

Paraquat methyl viologen; 1,1′-dimethyl-4,4′-bipyridynium dichloride; a nonselective herbicide whose action requires direct contact with the plant. It is highly toxic to humans and other animals if ingested in undiluted form.

parasite any organism that spends all or part of its life cycle in (**endoparasite**) or on (**ectoparasite**) another living organism of a different species (its **host**), from which it obtains nourishment and/or protection, and to which it is usually detrimental. *Compare* **symbiont**.

parastatin a 73-amino-acid peptide hormone, M_r 11000, that inhibits **parathyrin** secretion. Porcine parastatin has the amino-acid sequence:

LSFRAPAYGFRGPGLQLRRGWRPSSREDSVEAGLPL-
QVRXYLEEKKEEEGSANRPEDQELESLSAIEAELEK.

Activity resides in a 19-amino-acid N-terminal fragment; that from rat has the sequence: LSFRARAYGFRDPGPQLRR. It is synthesized as part of the sequence of **chromogranin** A.

paratartaric acid *an old name for* racemic DL-tartaric acid. The resolution of this acid into the D- and L-enantiomers by Pasteur was a landmark experiment in stereochemistry. *See* **tartaric acid**.

parathion *O*,*O*-diethyl *O*-*p*-nitrophenyl phosphorothioate; a compound that acts as an inhibitor of cholinesterase through covalent bonding to the esteratic site of the enzyme. It is used as a chemical warfare agent and insecticide.



Parathormone *a proprietary name for* **parathyrin**.

parathyrin *or* **parathyroid hormone** (*abbr*.: PTH); a 9.5 kDa polypeptide hormone of 83 amino-acid residues (bovine). It is derived from a 12.5 kDa precursor. Parathyrin acts in conjunction with **calcitonin** and other hormones to control calcium and phosphate metabolism; it elevates the blood calcium level by dissolving the salts in bone and preventing their renal excretion. Its effects are mediated by a G-protein-associated membrane receptor. Several mutations in the receptor cause a rare form of short-limbed dwarfism (or metaphyseal chondrodysplasia). Mutations that lead to absence or dysfunction of the $G_{S\alpha}$ subunit cause pseudohypoparathyroidism type 1a, in which there is also resistance to a wide variety of other hormones whose effects are mediated by this subunit. *Proprietary name*: Parathormone.

parathyroid **1** situated near the thyroid gland. **2** of, pertaining to, or produced by the parathyroid gland. **3** the parathyroid gland.

parathyroid gland an endocrine gland of higher vertebrates; there are typically two pairs, located near or within the thyroid. They develop from the gill pouches, and secrete **parathyrin**.

parathyroid hormone *abbr*.: PTH; *an alternative name for* **parathyrin**.

parathyroid hormone-related protein *abbr*.: PHRP; a protein (141 amino acids) that is homologous in the N-terminal region with parathyroid hormone, has effects similar to this, and binds the same receptor. It is present in breast and milk, kidney, brain, and other tissues, especially during intrauterine life, and seems to function largely in paracrine fashion. It is secreted by many tumours and is the major cause of malignancy-associated hypercalcemia. It may be a polyhormone because residues 1–36 are parathyroid hormone-like, residues 38–94 effect calcium transport in the placenta and bicarbonate transport in the kidney, and residues 107–139 constitute **osteostatin**. Homozygous gene knockout in mice is often lethal during embryogenesis or produces abnormalities throughout the skeleton.

paratope the part of an antibody, formed by the hypervariable loops of the **variable regions**, that binds to an **epitope**.

paratose 3,6-dideoxy-D-glucose; 3,6-dideoxy-D-*ribo*-hexose; a monosaccharide that occurs in type A O-antigen chains of the lipopolysaccharide on the outer membrane of certain species of *Salmonella*.

Parazoa a subkingdom of multicellular invertebrate animals comprising the sponges (phylum Porifera).

parenchyma **1** *(in botany)* in higher plants, any soft tissue consisting of thin-walled, relatively undifferentiated living cells. **2** *(in zoology)* the tissue constituting the essential or specialized part of an organ, as distinct from supportive tissue, blood vessels, etc. —**parenchymal** *adj.*; **parenchymatous** *adj.*

parenchymal liver cell *see* **hepatocyte**.

parent **1** any organism that has given rise to another such organism, whether sexually or asexually. **2** a precursor of some derived entity; applied, e.g., to a cell, a virus, a chromosome or molecule of DNA, or a radionuclide. **3** **parent compound** *(in chemical nomenclature)* the member of a group of related compounds that has the simplest chemical structure and that forms the basis for naming the others. —**parental** *adj.*

parental imprinting *see* **imprinting**.

parenteral **1** located or occurring outside the intestine. **2** any route other than via the gastrointestinal tract, especially by injection. —**parenterally** *adv.*

PARG *abbr. for* poly(ADP-ribose) glycohydrolase.

parietal **1** of, pertaining to, or forming part of the wall of a body cavity or similar structure; e.g. the hydrochloric-acid-secreting **parietal cells** of the gastric mucosa, also known as oxyntic cells. **2** of or relating to the parietal bones of the skull.

parietal layer *see* **serous membrane**.

parinaric acid any octadeca-9,11,13,15-tetraenoic acid; two isomers are found in *Parinarium laurinum*, namely the (9*Z*,11*E*,13*E*,15*Z*)-isomer (α- or *cis*-parinaric acid) and the (9*E*,11*E*,13*E*,15*Z*)-isomer (β- or *trans*-parinaric acid). Both are useful as probes in membrane studies, *trans*-parinaric acid especially, as it partitions preferentially into the less fluid regions of membrane lipids with increased quantum yield. They inhibit neutrophil elastase.



α-parinaric acid



β-parinaric acid

parkin a **ubiquitin–protein ligase** whose substrate is a glycosylated form of α-**synuclein** (α-Sp22). The substrate accumulates in parkin-deficient brain. The parkin gene at 6q25.2-q27 encodes a protein (465 residues) whose N-terminal 76 residues are homologous with ubiquitin and whose C-terminal region contains two **RING fingers**. Mutations in the gene are associated with an autosomal recessive form of **Parkinson's disease**.

Parkinson's disease *or* **parkinsonism** a progressive disorder of the central nervous system characterized by tremor and impaired muscular coordination, thought to be due to defective dopaminergic transmission in some parts of the brain. There is a loss of dopaminergic neurons connecting the substantia nigra with the striatum, resulting in loss of dopaminergic inhibition in the striatum, with resulting cholinergic hyperactivity. Therapy is aimed at replacement of dopamine, achieved by administration of L-**dopa**, which is converted to dopamine within the brain (dopamine itself does not cross the blood–brain barrier). *See also* **MPTP**. [After James Parkinson (1755–1824), British palaeontologist and surgeon, who first described the disease in 1817.]

Park nucleotide UDP-*N*-acetylmuramyl pentapeptide; an intermediate in the biosynthesis of peptidoglycan in the cell walls of most bacteria. [After James Theodore Park (1922–).]

P450 arom *an alternative name for* **aromatase**.

paromomycin an antibiotic that, like streptomycin, increases the error rate of translation by binding to the 30S ribosomal subunit of prokaryotes and distorting their A site.

parotid gland either of a pair of **salivary glands** situated near each ear in mammals. The duct runs forwards and empties into the oral cavity.

paroxysmal nocturnal hemoglobinuria an acquired hemolytic anemia in which a clone of erythrocytes, derived from a hemopoietic stem cell that has acquired a somatic mutation, undergoes complement-mediated chronic intravascular hemolysis with consequent hemoglobinuria. It arises following any of numerous mutations in the gene at Xp22.1 for the enzyme that attaches the glucosamine moiety to phosphatidylinositol in the production of GPI-anchored proteins. This causes a lack on erythrocytes of CD55 and CD59, which normally protect the erythrocytes against the action of complement. Deficiency of CD55 alone is a rare cause of the disorder.

PARP *abbr. for* **1** procyclin. **2** proline/arginine-rich protein.

PARP-1 *abbr. for* poly(ADP-ribose) polymerase 1; in mammals, a highly conserved protein (113 kDa) that is strongly activated by DNA strand breaks, and participates in modulating DNA base excision repair, apoptosis, and necrosis. It includes a DNA-binding domain with 23 zinc finger motifs, and a poly(ADP-ribose) polymerase catalytic domain. Mouse gene knockouts for this protein are remarkably resistant to myocardial infarction, stroke, shock, diabetes mellitus, and neurodegeneration. *See also* **PARP-2**.

PARP-2 *abbr. for* poly(ADP-ribose) polymerase 2; in mammals, a 62 kDa protein that catalyses poly(ADP-ribose) formation, being activated by DNA strand breaks. Its activity supplements that of **PARP-1** in mouse gene knockouts for this protein.

parse to analyse amino acid sequences or nucleotide base sequences during the construction of multiple sequence alignments when determining homology.

parsimony 1 *(in computing)* an algorithm used for determining sequence relationships in macromolecules. 2 *(in genetics)* the construction of evolutionary trees from protein and nucleic-acid sequences. It maximizes the genetic likeness associated with common ancestry, whilst minimizing the incidence of convergent mutation, and provides a way to find the best genealogical hypothesis from sequence data.

parthenocarpy the formation of fruit without the setting of seeds. It occurs naturally, but can be induced by spraying flowers with gibberellic acid (*see* **gibberellin**) to produce crops of seedless fruit.

parthenogenesis the development of a new individual from an unfertilized female gamete. —**parthenogenetic** *adj.*; **parthenogenetically** *adv.*

partial agonist an agonist that is unable to evoke the maximal response of a biological system, even at a concentrations sufficient to saturate the specific receptors.

partial derivative *(in mathematics)* the derivative of an expression containing two or more independent variables that is obtained by differentiating the expression with respect to only one of them, the remaining variable or variables being considered constant.

partial hydrolysate any mixture of monomers and oligomers resulting from a limited degree of chemical hydrolysis of a biopolymer or from its exposure to a specific hydrolytic enzyme.

partial inhibition a type of nonlinear enzyme inhibition in which saturation of the enzyme with inhibitor does not decrease the rate of the enzyme-catalysed reaction to zero.

partial inverse agonist an **inverse agonist** that evokes a submaximal response in a biological system, even at a concentration sufficient to saturate the specific receptors. At high concentrations it will diminish the actions of a full inverse agonist. *Compare* **antagonist**, **partial agonist**.

partially overlapping code *see* **overlapping code**.

partially overlapping gene *see* **overlapping gene**.

partial molar quantity a function of any particular extensive property (e.g. enthalpy, entropy, Gibbs energy, heat capacity, internal energy, volume) of a specified component of a single-phase multicomponent system that describes how that property varies, at constant pressure and temperature, with variation of the concentration of the component when the change in the property is expressed per mole of the component. Partial molar Gibbs energy is more usually known as **chemical potential**. *Compare* **partial specific quantity**.

partial pressure *symbol*: p_{B} *or* $p(\mathrm{B})$ (for a gas B); the pressure exerted by one particular gas in a mixture of nonreacting gases. It is defined as the pressure the gas would exert if it alone were present and occupied the whole volume of the mixture at the same temperature, and is equal to the product of the amount-of-substance fraction of the gaseous component in question and the total pressure of the gaseous system. *Compare* **tension**. *See also* $\boldsymbol{p_{50}}$.

partial pressures, law of *see* **Dalton's law of partial pressures**.

partial specific quantity a function of any particular extensive property (e.g. enthalpy, entropy, Gibbs energy, heat capacity, internal energy, volume) of a specified component of a single-phase multicomponent system that describes how that property varies, at constant pressure and temperature, with variation of the concentration of the component when the change in the property is expressed per unit mass of the component. *Compare* **partial molar quantity**.

partial specific volume (of a solute) *symbol*: $\bar{v}_{\mathrm{B}}$; an instance of a **partial specific quantity**, defined as the change in volume of a solution on addition of a small amount of a solute B, expressed per unit mass of added solute and extrapolated to infinite dilution. The cgs unit (in which values are often listed) is $\mathrm{cm^3\ g^{-1}}$ and the SI unit is $\mathrm{m^3\ kg^{-1}}$.

particle 1 an extremely small piece or portion of (esp. solid or colloidal) matter. 2 **elementary particle**. —**particulate** *adj.*

particulate enzyme any enzyme that is bound to an insoluble cellular or subcellular structure or that has been artefactually or artificially attached to particulate material.

particulate radiation any form of radiation consisting of a stream of particles, especially alpha radiation, beta radiation, or neutron radiation emanating from a radioactive source.

partition 1 *(in chemistry) or* **distribution** the equilibration of a solute between two phases (usually of differing composition); the result of such a process. 2 *(in genetics)* the events that lead to the separation of chromosomes or to the segregation of plasmids into daughter cells in prokaryotic organisms.

partition chromatography any form of chromatography in which separation of the components of a mixture is based mainly on differences between the solubilities of the components in the stationary phase (in gas chromatography) or on differences between the solubilities of the components in the mobile and stationary phases (in liquid chromatography).

partition coefficient *or* **distribution coefficient** *symbol*: α *or* K_{d}; the ratio of the equilibrium concentrations of a pure substance dissolved in two phases that are in contact, at a specified temperature. The partition coefficient is independent of the concentrations provided that no chemical interaction occurs with either (or both) of the phases and that the presence of the solute does not affect their immiscibility.

partition function *symbol*: Z; a dimensionless mathematical function, derived by the application of statistical mechanical theory, that can be used to derive the average distribution of the internal energy of a system in terms of its partition between all its molecular inhabitants.

partition law *or* **distribution law** the principle that a solute, when added to a system consisting of two phases, will, at a given temperature, distribute itself between the two phases in proportion to its solubility in each of the two phases separately. **Henry's law** is a particular case of the partition law. *See also* **Nernst distribution law**.

partonomy (*in an ontology*) a 'parts' hierarchy into which the components of discrete objects are organized, often expressed as 'has a' relationships: e.g. apolipoprotein A has 38 kringle domains.

parturition the act or process of giving birth to offspring.

parvalbumin any of a group of closely related ~12 kDa muscle proteins that bind calcium ions. Parvalbumin α is a muscle **EF-hand** $\mathrm{Ca^{2+}}$-binding protein that may be involved in muscle relaxation. Parvalbumin β is known as **oncomodulin**.

parvovirus any of a group of small, animal viruses, in class II of the **Baltimore classification**, consisting of a naked capsid, 20–25 nm in diameter, and containing linear, single-stranded DNA of 1.2–1.8 MDa. Parvoviruses are highly resistant to chemical and physical agents.

parvulin a **peptidylprolyl isomerase** isolated from *Escherichia coli.* It does not have any function as an **immunophilin**.

PAS *abbr. for* 1 *p*-aminosalicylic acid. 2 periodic acid–Schiff; *see* **periodic acid–Schiff reaction**.

pascal *symbol*: Pa; the SI derived unit of pressure or stress. It is equal to a force of one newton per square metre; i.e.

$$1\ \mathrm{Pa} = 1\ \mathrm{N\ m^{-2}} = 1\ \mathrm{J\ m^{-3}}.$$

[After Blaise Pascal (1623–62), French mathematician and philosopher, who discovered the relationship between barometric pressure and altitude.]

PASCAL 1 *see* **bibliographic database**. 2 *see* **programming language**.

PAS domain a structural domain of ≈130 residues that occurs in proteins that respond to stimuli such as light, redox potential, $\mathrm{O_2}$, or small aromatic molecules. It is found in archaea, bacteria and eukaryotes, and named after the proteins in which they occur (period circadian protein, Ah receptor nuclear translocator protein and single-minded protein), PAS domains act as signal sensors in many signalling proteins. Several PAS domain-containing proteins detect their signal by means of an associated cofactor (e.g., haem, flavin, a 4-hydroxycinnamyl chromophore). PAS domains are often associated with PAC domains, with which they are directly linked, together forming the PAS fold. The linking region between these domains is highly divergent; in human PAS kinase, this region is flexible, adopting different conformations depending on the bound ligand.

Pasha (Partner of Drosha) a dsRNA-binding protein which interacts with **Drosha** in the **Microprocessor** complex to initiate miRNA production in the nucleus. Also named DGCR8 (**Di George syndrome** chromosomal region 8).

passage *(in biology)* the action or process of (serially) subculturing cells or microorganisms, especially with a view to adapting them to a changed environment.

passage number *(in cell culture)* the number of subcultures performed after the original isolation of the cells from a primary source.

passenger *or* **passenger DNA** any specific DNA fragment introduced into a **cloning vector** or other cloning vehicle.

passive diffusion *an alternative name for* **simple diffusion** (used especially to emphasize its distinction from **active transport**). *Compare* **facilitated diffusion**.

passive immunity immunity in an individual due to the presence of antibody or primed lymphocytes derived from another, already immune, individual.

Pasteur effect *or (formerly)* **Pasteur–Meyerhof effect** either the phenomenon that occurs in facultatively anaerobic cells whereby oxygen inhibits glycolysis or fermentation, or its converse whereby the rate of glycolysis or fermentation increases when oxygen is excluded. *Compare* **Crabtree effect**. [After Louis Pasteur (1822–95), French chemist, microbiologist, and immunologist.]

pasteurization *or* **pasteurisation** a method of heat-treating milk or similar fluids to improve storage qualities and destroy pathogenic bacteria, without markedly altering taste and nutritional characteristics. Pasteurization of milk involves heating to 65°C for 30 minutes or to 72°C for 15 minutes followed by rapid cooling to below 10 °C. **—pasteurize** *or* **pasteurise** *vb.*

Pasteur pipette *or* **pasteur pipette** a simple, disposable, ungraduated, dropping or transfer pipette constructed by drawing out a short length of narrow glass tubing to form a long fine tip and operated commonly by means of an attached rubber or PVC bulb or teat. Analogous devices are available moulded in low-density polyethylene, with integral bulb and sometimes calibrated. *Also (esp. US)*: **Pasteur pipet**, **pasteur pipet**.

Pasteur reaction the putative chemical reaction once considered to link fermentation and respiration and to account for the **Pasteur effect**.

patatin any of a family of glycoproteins that form 40% of the soluble protein of potato tubers. They serve as potato somatic storage proteins, and also have enzyme activity involved in host resistance. They have lipid acylhydrolase activity.

patch an intermediate stage in the formation of a **cap** (def. 2) on the surface of a cell, e.g. of a lymphocyte.

patch-clamp technique a technique whereby the conductance change of a single ion channel of an excitable membrane is measured directly. A very small electrode tip is sealed onto a patch of cell membrane, thereby making it possible to record the flow of current through individual ion channels in the patch. *See also* **Neher**, **Sakmann**.

Patched a human protein encoded by a homologue of the segment polarity gene *patched* of *Drosophila*. It is a multipass transmembrane receptor for **sonic hedgehog** (or Shh), with a covalently linked C-terminal cholesterol molecule and a palmitoylated N-terminal cysteine residue. Patched functions through a neighboring G-protein receptor-like protein called smoothened. In the absence of Shh, Patched inhibits smoothened and thus inhibits transcription of genes for Patched, transforming growth factor β, and Wnt proteins. The Patched gene at 9q22.3 encodes a protein of 1296 amino acids. Mutations, mostly of the nonsense variety, cause an autosomal dominant naevoid basal cell carcinoma syndrome, and are also associated with some sporadic medulloblastomas.

paternal imprinting the epigenetic silencing of an allele inherited from the father. *See* **imprinting**.

path *see* **light path**.

+pathic *see* **+pathy**.

patho+ *or (before a vowel)* **path+** *comb. form* denoting disease or clinical disorder.

pathobiochemistry 1 the study of the biochemical processes associated with disease. **2** the processes themselves.

pathogen any agent, especially any living organism, that can cause disease.

pathogenesis the generation and production, or the origin and development, of a disease. **—pathogenetic** *adj.*

pathogenesis-related proteins proteins synthesized in plants in response to attack by fungal or bacterial pathogens, presumably involved in the plant defence mechanism. They belong to an evolutionarily related family of small, eukaryotic, extracellular proteins, dubbed CRISP (cysteine-rich secretory proteins).

pathogenic (capable of) causing or producing disease. **—pathogenicity** *n.*

pathogenicity island a region of a bacterial genome containing clusters of genes linked to its pathogenic behaviour. For example, the *Escherichia coli* LEE pathogenicity island contains genes for gut wall attachment. Such islands are not usually present in all strains of a given bacterial species and are thought to have been acquired by horizontal transfer.

pathological *or* **pathologic 1** of, or pertaining to, pathology. **2** causing, relating to, involving, or caused by disease.

pathology 1 the branch of medical science concerned with the causes and nature of disease and with the effects of disease on the structure and functioning of the organism. **2** the sum of the changes that occur in an organism as the result of a specific disease. **—pathologist** *n.*

pathophysiology 1 the study of the physiological processes associated with disease. **2** the processes themselves.

pathway 1 the chain of reactions undergone by a given molecular entity or class of such entities in a particular ecosystem. **2 metabolic pathway**.

pathway database a database that links gene products and compounds in the cells of an organism to components on particular pathways. Such databases are used to facilitate gene function assignment and metabolic reconstruction. Examples include: BIND, which stores information on biomolecular interactions, molecular complexes, and pathways; EcoCyc, which houses metabolic, regulation, and signal transduction data on *Escherichia coli*; KEGG (Kyoto Encyclopedia of Genes and Genomes), which links human genes with networks of interacting molecules in the cell; WIT (what is there?), which houses metabolic, gene function, and phylogenetic data from multiple genomes; and HPRD (human protein reference database), an integrated pathway database of human reference proteins that contains domain architectures, PTMs, interaction networks, and disease associations for the human proteome.

pathway engineering the use of **genetic engineering** to change either the kinetics or the products of a metabolic pathway.

+pathy *comb. form* denoting **1** feeling, sensitivity. **2** disease of a (specified) part or kind. **3** a method of treating disease. **—pathic** *adj.*

pattern *or* **signature** an abstract representation of conserved features of a multiple sequence alignment that can be used to provide a diagnostic signature for related sequences that share the same or similar features. Examples of patterns are a regular expression, profile, hidden Markov model (HMM), fingerprint, and block. The term is also sometimes used confusingly as a synonym for regular expression.

pattern database *or* **secondary database** *or* **signature database** (*in sequence analysis*) a database that houses diagnostic patterns, or signatures, usually derived from conserved regions of multiple sequence alignments of protein families or domains. Areas of conservation are encoded, for example, in the form of regular expressions, fingerprints, blocks, or hidden Markov models (HMMs). Examples of such databases include PROSITE, PRINTS, Blocks, and Pfam. They tend to include varying levels of annotation describing the protein families they encode and technical details concerning how the pattern was derived.

pattern hit initiated-BLAST *abbr.*: PHI-BLAST; *see* **database-search program**.

pattern recognition 1 (*in sequence analysis*) the recognition of characteristic patterns of conservation in sequences using some form of predefined signature or discriminator – e.g. a regular expression, fingerprint, or hidden Markov model (HMM). **2** (*in data mining*) the discovery of unknown patterns in large data sets, for example by using principal component analysis, partial least squares, or neural network approaches.

patulin 4-hydroxy-4*H*-furo[3,2-*c*]pyran-2(6*H*)-one; a carcinogenic metabolite with antibiotic activity isolated from several fungi, particularly *Aspergillus* and *Penicillium* spp.



pauci+ *comb. form* indicating few.

paucidisperse describing a colloidal system whose dispersed phase consists of particles of only a few sizes. —**paucidispersity** *n.*

Pauli exclusion principle *or* **exclusion principle** *or* **Pauli principle** the principle that no two electrons in an atom can be described by the same set of four quantum numbers. [After Wolfgang Pauli (1900–58), Austrian-born US physicist.]

Paulus filtration method a method for studying the binding of a ligand microsolute to a macrosolute. It is applicable to small amounts of material and is particularly useful for a system having a relatively low binding constant. It involves equilibration of a series of mixtures of macrosolute and ligand in a suitable solvent, then separation of unbound ligand from macrosolute-plus-bound-ligand by ultrafiltration through anisotropic membrane filters of an appropriate retentivity. The amount of microsolute retained with the macrosolute on each filter is then estimated by, e.g., radioactivity measurement or another sensitive technique. [After H. Paulus.]

Pauly's reagent a chromogenic reagent for imidazoles and phenols, consisting of a freshly prepared solution of diazotized sulfanilic acid (or other aromatic amine). In the presence of alkali, this reacts with histidine to give a red colour and with tyrosine to give an orange colour. It is useful for the identification of these amino acids on paper chromatograms.

PAUP *abbr. for* phylogenetic analysis using parsimony; s*ee* **phylogeny package**.

Pavlovian conditioning the modification of behaviour, whereby a previously neutral stimulus becomes associated with an already existing reflex, so that it will, by itself, evoke a response. This new reflex is said to be conditional. After Ivan P. Pavlov (1849–1936), Russian physiologist and experimental psychologist, who described the effect experiments on dogs. He showed that reflex responses, like salivation, became conditional upon specific previous experiences of the animal, such as light or a tone (but probably not a bell).

Pax *abbr. for* paired box; one of a family of transcriptional regulators that contain a paired-box domain and are specifically expressed during the development of a wide range of structures and organs. There are nine *Pax* genes in mouse and in human. They are expressed primarily in the neural tube and brain in the early embryo. *Pax1* and *Pax9* are closed related, as are the groups *Pax3* and *Pax7*, and *Pax2*, *Pax5*, and *Pax8*. PAX2 protein (392 amino acids) is also expressed in the eye and kidney; mutations cause the renal-coloboma syndrome. PAX3 (836 amino acids) controls MyoD expression in limb buds; numerous mutations cause Waardenburg syndrome. PAX6 (422 amino acids) is identical in sequence in mouse and in human, and contains a homeobox domain and a C-terminal region rich in proline, serine, and threonine. It is also expressed in eye and pancreatic islet cells. Numerous mutations cause aniridia. PAX8 is implicated in embryonic development of the thyroid gland; mutations cause thyroid dysgenesis and congenital hypothyroidism.

paxillin an adhesion protein, associated with **vinculin,** that becomes phosphorylated in response to a number of stimuli, phosphorylation being associated with focal adhesion. It is also associated with dysfunction of **cadherin**-dependent cell–cell contacts, and cell spreading.

Pb *symbol for* lead.

PBD *see* **biphenylylphenyloxadiazole**.

PBG *abbr. for* porphobilinogen.

PBI *abbr. for* protein-bound iodine.

pBluescript *a proprietary name for* a phagemid cloning vector incorporating the bacteriophage f1 origin of replication. It has 21 unique restriction sites in a multiple cloning sequence (MCS) flanked by promoters for T3 and T7 RNA polymerases.

P body *abbr. for* processing body; any of a few discrete cytoplasmic foci in yeast cells that contain proteins that activate or catalyse decapping of mRNA, mRNA degradation products, and a 5′→3′ mRNA exonuclease. P bodies are essential for metabolism of mRNA and are also present in mammalian cells.

PBP *abbr. for* pencillin-binding protein.

pBR322 a **cloning vector**.

PBS *abbr. for* phosphate-buffered saline.

PC *abbr. for* **1** paper chromatography. **2** phosphocreatine. **3** phosphatidylcholine. **4** personal computer.

pCa *symbol for* the negative logarithm of the concentration (or strictly the activity) of calcium ions in a specified solution.

PCA *abbr. for* perchloric acid.

P-cadherin placental **cadherin**.

PCAF *abbr. for* p300/CBP-associated factor; a **histone acetyltransferase** that associates with p300/CBP and acetylates lysine residues in the N-terminal region of histone H3 and H4.

PCB *abbr. for* **1** pyruvate carboxylase. **2** polychlorinated biphenyl.

p300/CBP-associated factor *see* **PCAF**.

PCCase *abbr. for* propionyl-CoA carboxylase.

pcDNA 3.1 a proprietary vector designed for the expression of genes in mammalian cells using the cytomegalovirus promoter. It has the SV40 origin of replication and carries the gene for neomycin resistance (neo^{R}).

P cluster an iron-sulfur cluster, comprising a [4Fe-4S] cluster linked to a [4Fe-3S] cluster, that is present in each αβ dimer of component 1 of nitrogenase.

PCM1 *or* **pericentriolar material** a protein of the **centrosome** that recruits centrin, pericentrin, ninein, and dynactin just before centrosomal duplication.

PCMB *abbr. for* *p*-chloromercuribenzoate, or *p*-chloromercuribenzoic acid.

PCMBS *abbr. for* *p*-chloromercuribenzenesulfonate, or *p*-chloromercuribenzenesulfonic acid.

pCMV-Script *a proprietary name for* a phagemid vector designed for the expression of proteins in mammalian cells under the control of the cytomegalovirus immediate early promoter. It has both Col E1 and SV40 origins of replication and confers resistance to neomycin and kanamycin.

pCMV-SPORT any of a series of proprietary phagemid vectors used for expression of proteins in mammalian cells under the control of the cytomegalovirus promoter. The multiple cloning sequence is flanked by T7 and SP6 promoters.

PCNA *abbr. for* proliferating cell nuclear antigen; *other names*: processivity clamp; sliding clamp. A protein subunit (261 amino acids) of prokaryotic **DNA polymerase**-δ. It forms a homotrimer that surrounds DNA and functions as a sliding clamp in a **replisome**. Each subunit contains two similar structural domains – each consisting of a beta sandwich and two alpha helices at the inner edge – that interact with DNA. The structure is very similar to that of the β subunit of the *E.coli* DNA polymerase III holoenzyme. PCNA is also required in the gap-filling step of DNA synthesis in nucleotide excision repair. It binds and is inhibited by p21.

PCP *abbr. for* 1-(1-phenylcyclohexyl)piperidine (*see* **phencyclidine**).

PCR *abbr. for* polymerase chain reaction.

p.d. *abbr. for* (electric) potential difference.

Pd *symbol for* palladium.

PDB *abbr. for* protein data bank; *see* **structure database**.

PDBj *abbr. for* protein data bank Japan; *see* **structure database**.

PDBsum *abbr. for* protein data bank summary; *see* **specialist database**.

PDBu *abbr. for* phorbol 12,13-dibutyrate, a **phorbol ester**.

PDD *abbr. for* phorbol 12,13-didecanoate, a **phorbol ester**.

PD-ECGF *abbr. for* platelet-derived endothelial cell growth factor.

PDGF *abbr. for* platelet-derived growth factor.

PDI *abbr. for* protein disulfide isomerase.

pDNA *abbr. for* plasmid DNA.

P domain *or* **trefoil domain** a domain of highly conserved cysteine residues, disulfide-bonded in the pattern 1–5, 2–4, 3–6, associated with highly conserved alanine, glycine, and tryptophan residues. Such domains are found in secretory polypeptides from animals.

PDS *abbr. for* postsynaptic density.

Pdx1 *abbr. for* pancreatic duodenal homeobox 1; a mammalian homologue of a homeobox gene first described in *Xenopus*. It is expressed in all pancreatic cell types during early development, but only in pancreatic islet B cells and duodenal mucosa in adults. The protein activates promoters of insulin and somatostatin genes. Homozygous gene knockout in mice leads to neonatal death and lack of a pancreas.

PDZ domain a common homologous sequence of ~90 amino acid residues that was first detected in mammalian postsynaptic protein (PSD-95), Drosophila discs-large (Dlg), and mammalian tight junction protein (Z0-1), from which the acronym is derived. It forms a beta-sandwich containing 5–6 beta strands and two alpha helices and binds C-terminal protein sequences. From 1 to 13 copies may be present in a protein.

Pe *symbol for* the pentyl group.

PE *abbr. for* **1** phosphatidylethanolamine. **2** potential energy.

peak 1 a sharp increase followed by a sharp decrease in a physical quantity that varies with distance, frequency, time, etc. **2** *(in chromatography)* the portion of a differential chromatogram recording the changes in detector response or eluate concentration while a given component of the applied mixture emerges from a chromatographic column. **3** the maximum value of a **peak** (def. 1, 2).

pEC$_{50}$ *see* **p[A]$_{50}$**.

PEC-60 a 60-amino-acid regulatory polypeptide abundant in intestinal tissue and also found in the central nervous system. It inhibits the formation of cyclic AMP and activates Na^+,K^+-ATPase. It is structurally related to pancreatic trypsin inhibitor and inhibits insulin secretion.

PECAM *abbr. for* platelet endothelial cell adhesion molecule; a class of **adhesion molecules** represented by PECAM-1 (*or* CD31), a member of the immunoglobulin superfamily. It is constitutively expressed on endothelial cells, platelets, granulocytes, monocytes, and T cells, and participates in homophilic binding (i.e. binding to itself). It is required for transmigration of leukocytes across the endothelium during extravasation.

pectate any salt or ester of **pectic acid**.

pectic acid the form of **pectin** (def. 1) that is essentially free of methyl ester groups.

pectic substance *an alternative name for* **pectin** (def. 1).

pectin 1 *or* **pectic substance** any mixture of complex, colloidal, macromolecular plant **galacturonans** containing a large proportion of D-galactopyranosyluronic acid residues in (α1→4) linkage, the carboxyl groups of which may be esterified to varying degrees by methyl groups or be partially or completely converted to salts; some D-arabinose and D-galactose residues are present, and other sugars are sometimes present. M_r is usually in the range 1×10^4–4×10^5. Pectins are important matrix polysaccharides of plant cell walls, especially those of higher plants, sometimes constituting as much as one-third of the dry matter; they also occur in some plant juices. Certain fruits are particularly rich in pectin. **2** *(in commerce)* a whitish, water-soluble powder prepared from the rind of citrus fruits or apple **pomace** by extraction with dilute acid and consisting essentially of **pectin** (def. 1). It is used *inter alia* in the preparation of jams because of its ability to form gels in the presence of sucrose at high concentrations.

pectinase *see* **polygalacturonase**.

pectinesterase EC 3.1.1.11; *other names*: pectin methylesterase, pectin methoxylase; an enzyme that hydrolyses pectin to methanol and **pectic acid**. Found in plant cell walls, it may be concerned with cell-wall metabolism during fruit ripening.

pectinic acid the form of **pectin** (def. 1) in which a high proportion of the carboxyl groups are esterified with methanol.

pectin lyase EC 4.2.2.10; an enzyme that catalyses a *trans* elimination to convert pectin to oligosaccharides with unsaturated (C-4, C-5) terminal residues. Although often described as 4-deoxy-6-methyl-α-D-galact-4-enuronosyl groups, they are more accurately termed 4-deoxy-6-methyl-β-L-*threo*-hex-4-enopyranouronosyl groups.

pectin sugar *an old name for* L-arabinose.

pedigree the biological relationships of the members of a family often extending over several generations. In medical genetics it consists of a diagram of a family history showing the status of individuals with respect to a particular hereditary condition.

PEG *abbr. for* polyethylene glycol.

PEGylation *or* **pegylation** the process of modifying a protein by treatment with polyethylene glycol (PEG). *Compare* **PIGylation**.

PEI *abbr. for* the poly(ethyleneimine) group,

pelargonate *another name for* **nonanoate**.

pelargonidin *see* **anthocyanidin.**

pelargonoyl *another name for* **nonanoyl**.

pellagra a disease of animals, including humans, arising from a dietary deficiency of **nicotinic acid**, especially in the absence of sufficient dietary tryptophan to generate adequate amounts of nicotinamide coenzymes metabolically. This situation can occur when the diet consists largely of maize (corn). Pellagra is characterized by scaly dermatitis on exposed skin surfaces, diarrhoea, and depression.

pellagra-preventative factor *abbr.*: PP factor *or* PPF; *a former name for* **nicotinic acid** or nicotinamide.

pellet a small compressed mass of material, especially such a mass deposited at the bottom of a tube by centrifugation of a suspension.

pellicle a thin skin, membrane, or film.

pellicular 1 of, relating to, or being in the form of a pellicle. **2** describing a type of column packing, used in high-pressure liquid chromatography, in which the stationary phase is present as a thin layer on the surface of tiny glass beads.

Peltier effect the phenomenon whereby heat is given out, or absorbed, when an electric current passes across a junction between two dissimilar materials. *See* **thermocouple**. *Compare* **Seebeck effect**. [After Jean Peltier (1785–1845), French physicist.]

penatin *an obsolete name for* **glucose oxidase**.

pendrin *an alternative name for* **iodide-chloride transporter**.

penetrance *(in genetics)* the degree to which a particular genotype is expressed as the phenotype. If every individual carrying a dominant mutant gene shows the mutant phenotype, the gene is said to show complete penetrance. Penetrance can be related to age so that the mutant allele might show low penetrance in the young but increasing penetrance in older individuals.

penetratin *or* **Trojan peptide** a natural or synthetic polypeptide that is rich in basic amino acids and mediates uptake of nucleic acids, bioactive peptides, phage particles, and liposomes into mammalian cells. Examples include the HIV Tat protein and *Drosophila* Antennapedia protein.

penicillamine 3-mercapto-D-valine; β,β-dimethylcysteine; 2-amino-3-methyl-3-mercaptobutyric acid; the D-enantiomer is a characteristic degradation product of penicillin-type antibiotics. A potent chelator of heavy metal ions, it is used clinically in the treatment of **Wilson's disease** and of poisoning by metals such as copper, lead, and mercury.



penicillicacid 3-methoxy-5-methyl-4-oxo-2,5-hexadienoic acid (exists in equilibrium with lactone form); a toxic antibiotic metabolite obtained from several fungi. It bears no relationship to penicillin or its degradation products. (Illustrated opposite.)

penicillin 1 *the generic name for* a range of related antibiotics, whether produced naturally during the growth of various microfungi of the genera *Penicillium* and *Aspergillus* or of semisynthetic origin, that contain the condensed β-lactam– thiazolidine ring system:



where R is any of a variety of acyl groups such as: phenylacetyl, $C_6H_5–CH_2–CO–$ (in **penicillin G**, **penicillin II**, **benzylpenicillin**); phenoxyacetyl, $C_6H_5–O–CH_2–CO–$ (in **penicillin V**); and D-adipyl, $HOOC–CH(NH_2)–[CH_2]_3–CO–$ (in **penicillin N**, *also called* **cephalosporin N**). Only those enantiomers having the D-configuration at C-2 of the thiazolidine ring show antibiotic activity. The parent substance, **6-aminopenicillanic acid**, in which R is H, has little intrinsic antibiotic activity but is the naturally occurring substrate for the semisynthesis of artificial penicillins, e.g. **ampicillin**, in which R is aminophenylacetyl, $C_6H_5–CH(NH_2)–CO–$. All penicillins are readily inactivated by chemical or enzymic hydrolysis of the strained four-membered *β*-lactam ring, cold dilute acid yielding **penicillamine**, and alkali or penicillinases and other *β*-lactamases forming the corresponding substituted **penicilloic acids**. The penicillins generally have extremely low toxicity to animals and high antibacterial activity, especially against Gram-positive organisms, the spectrum of activity varying somewhat with the nature of the group R. They inhibit cross-linking of peptidoglycan in the cell wall of growing bacterial cells, and render the cells sensitive to osmotic lysis. **2** the (hypothetical) substance 6-formamidopenicillanic acid, used only in combination in trivial names of certain **penicillins** (def. 1), e.g. benzylpenicillin.

penicillin acylase EC 3.5.1.11; *recommended name*: penicillin amidase; an enzyme that catalyses the hydrolysis of penicillin to a fatty-acid anion and 6-aminopenicillinate. Several enzymes differ in specificity for the fatty acid. For example, **penicillin V acylase** (*or* penicillin V amidase) is a homotetramer of 338 amino acids from *Bacillus sphaericus*. **Penicillin G acylase** (*or* penicillin G amidohydrolase) from *Escherichia coli* consists of 846 amino acids. This forms a periplasmic protein that consists of α and β subunits, representing residues 27–235 and 290–846, respectively. *See also* **6-aminopenicillanic acid**.

penicillin amidase *the recommended name for* **penicillin acylase**.

penicillinase *a trivial name for* any *β*-**lactamase** that acts preferentially on penicillins.



penicillin-binding protein *abbr*.: PBP; any of various bacterial proteins that are capable of binding penicillin(s) covalently. Such proteins appear to be located predominantly, if not solely, in the cytoplasmic membrane of all species of bacteria in which peptidoglycan occurs in the cell wall. These proteins are believed to catalyse reactions in the later stages of cell-wall synthesis, and there is a strong presumption that at least one of them catalyses the insertion of nascent peptidoglycan into the cell wall. In Gram-negative bacteria, some penicillin-binding proteins are known to be involved in the maintenance of cell shape or in cell elongation or septation. The low molecular weight penicillin-binding proteins belong to a family of serine-type D-alanyl-D-alanine carboxypeptidases.

penicillin G acylase *see* **penicillin acylase**.

penicillin V acylase *see* **penicillin acylase**.

penicilloic acid any compound of structure:



and produced by cleavage of the *β*-lactam ring of **penicillins** (def. 1) by enzymic or alkaline hydrolysis.

penta+ *or (before a vowel)* **pent+** *comb. form* denoting five, fivefold, five times.

pentacosa+ *comb. form* denoting 25, 25-fold, 25 times.

pentadeca+ *comb. form* denoting 15, 15-fold, 15 times.

pentafunctional arom polypeptide a polypeptide that catalyses five consecutive enzymatic reactions in prechorismate polyaromatic amino-acid biosynthesis, i.e the second to sixth steps in the biosynthesis from chorismate of the aromatic amino acids (the **shikimate pathway**). It occurs in some yeasts and other fungi and in *Euglena gracilis*. It contains: **3-dehydroquinate synthase**, **3-dehydroquinate dehydratase**, **shikimate 5-dehydrogenase**, **shikimate kinase**, and **EPSP synthase**. In yeast the complete protein consists of 1588 amino acids; residues 1–392 = 3-dehydroquinate synthase; residues 404–866 = EPSP synthase; residues 887–1060 = shikimate kinase; residues 1061–1293 = 3-dehydroquinate dehydrogenase; and residues 1306–1588 = shikimate dehydrogenase.

pentagastrin *the trivial name for* (*N*-*tert*-butyloxycarbonyl-*β*-alanyl)-L-tryptophanyl-L-methionyl-L-aspartyl-L-phenylalaninamide; a synthetic analogue of **gastrin** that consists of the latter's C-terminal tetrapeptide amide sequence with an added protected N-terminal *β*-alanyl residue. It is used in the **pentagastrin test** as a gastrin analogue to stimulate gastric-acid secretion, which is then measured. The test results are too variable to be of great use in diagnosis. *See also* **calcitonin**.

pentakisphosphate *see* **multiplying prefix**.

pentamer **1** any oligomer consisting of or derived from five monomers. **2** the group of five capsomeres in an icosahedral virus capsid.

pentanoate *another name for* **valerate**.

pentanoyl *another name for* **valeryl**.

pentaose a pentasaccharide in which all the residues are of one type and uniform linkage. *Compare* **pentose**.

pentaric acid any **aldaric acid** obtained by oxidation of a **pentose** at C-1 and C-5.

pentasaccharide any oligosaccharide composed of five monosaccharide units. Pentasaccharides occur in small amounts in plants, e.g. **verbascose** in soybeans.

penta-snRNP the preassembled **spliceosome** complex that contains the five small nuclear RNAs (snRNA).

pentatricopeptide repeat a peptide of 35 amino acids found in multiple copies in some proteins. Their function is unknown but might be involved with RNA stabilization. The repeat seems to be greatly expanded in plants.

pentaxin *or* **pentraxin** any of a family of proteins with a discoid appearance under electron microscopy, having five non-covalently bound subunits. The family includes **C-reactive protein**, serum amyloid P-component, and neuronal pentaxins.

pentitol any **alditol** having a chain of five carbon atoms in the molecule.

pentobarbital 5-ethyl-5-(1-methylbutyl)barbiturate; a major barbiturate drug. *One proprietary name* is Nembutal.

pentolinium test a test in which **pentolinium**, a sympathetic ganglion blocking drug, is used to reduce catecholamine secretion; failure to achieve reduction may indicate a **pheochromocytoma**.

penton a capsomere that is surrounded by five other capsomeres in an icosahedral virus capsid.

pentonic acid any monocarboxylic acid (aldonic acid) formally derived from a pentose by oxidation at C-1.

pentosan a **glycan** that yields only pentoses on hydrolysis.

pentose any **aldose** having a chain of five carbon atoms in the molecule. *Compare* **pentaose**.

pentose cycle *an alternative name for* **pentose phosphate pathway**.

pentose nucleic acid *abbr*.: PNA; *a former term for* **ribonucleic acid**.

pentose phosphate pathway *or* **hexose monophosphate pathway** a complex series of cytosolic metabolic reactions by which glucose 6-phosphate is oxidized with formation of carbon dioxide, ribulose 5-phosphate, and reduced NADP, the ribulose 5-phosphate then entering a series of reactions in which a number of sugar phosphates containing between three and seven (or eight) carbon atoms are successively interconverted. One consequence of these interconversions is the nonoxidative regeneration of glucose 6-phosphate, which then can enter the pathway for another cycle of oxidative decarboxylation and skeletal rearrangement, the eventual result being the complete oxidation of one molecule of glucose with the formation of six molecules of carbon dioxide and 12 molecules of NADPH. The pathway thus provides (in some organisms or tissues) an alternative route to (or shunt of) part of the glycolytic pathway; it also provides ribose 5-phosphate for nucleotide synthesis and (in some organisms) other intermediates for biosynthesis. Of special importance is D-erythrose 4-phosphate, required for the biosynthesis of aromatic amino acids and many other materials by the **shikimate** pathway. In higher plants many of the pathway enzymes function in the reverse direction as part of the **reductive pentose phosphate cycle**. *Other names*: hexose monophosphate shunt; pentose cycle; phosphogluconate (oxidative) pathway; Warburg–Dickens pathway; Warburg–Dickens–Horecker pathway. *See also* **glucose-6-phosphate dehydrogenase**, **phosphogluconate**, **phosphogluconate dehydrogenase (decarboxylating)**, **transaldolase**, **transketolase**.

pentosuria the presence of excessive amounts of pentose in the urine. In **essential pentosuria**, daily excretion of 1–4 g L-xylulose (normal <60 mg) occurs because of deficiency of L-xylulose reductase (EC 1.1.1.10), an enzyme of the glucuronate pathway that converts L-xylulose to xylitol. In **alimentary pentosuria** excretion of up to 100 mg of L-arabinose or L-xylose occurs following ingestion of unusually large amounts of such fruits as cherries, grapes, and plums. Both forms are clinically benign.

pentraxin *see* **pentaxin**.

pentulose any **ketose** having a chain of five carbon atoms in the molecule. There are two enantiomeric pairs of pentuloses having the carbonyl group at C-2, these being the D- and L-isomers of ribulose, *erythro*-2-pentulose, and of xylulose, *threo*-2-pentulose.

pentyl *symbol*: Pe; the alkyl group, CH_3–[CH_2]$_3$–CH_2–, derived from pentane.

Pep-1 a synthetic 21-amino-acid peptide used experimentally for protein delivery into cells. It contains a tryptophan-rich region for hydrophobic interaction and a lysine-rich region that improves delivery and solubility of the vector. The Pep-1–protein complex dissociates on entry into a cell.

PEP *abbr. for* phospho*enol*pyruvate.

PEPCK *abbr. for* phospho*enol*pyruvate carboxykinase.

pepinase a pepstatin-insensitive lysosomal protease (547 amino acids) that also has carboxypeptidase activity. Deficiency of this enzyme results in a late-onset form of neuronal lipofuscinosis.

peplomer a virus-coded proteinaceous knob or spike, numbers of which project from the peplos (i.e., **envelope** (def. 3)) of an enveloped virus particle. Peplomers may have cell-receptor, hemagglutinating, or neuramidinase activity.

peplos *an alternative name for* **envelope** (def. 3).

pepsin 1 any of the closely related aspartic proteinase enzymes of 31–36 kDa that constitute the principal proteinase activity of gastric juice of vertebrates. The family includes **pepsin A**, **pepsin B**, pepsin C (i.e. **gastricsin**), and **pepsin D**. Pepsins have maximal activity at pH 2–3; they preferentially catalyse hydrolysis of peptide bonds formed from hydrophobic amino-acid residues, the detailed specificity varying somewhat between the different pepsins. **2** *an alternative name for* **pepsin A**.

pepsin A *or* **pepsin** *the recommended name for* the predominant enzyme (EC 3.4.23.1) of the **pepsin** family. It is a phosphoprotein (in pig, 327 amino acids) formed by limited proteolysis of pepsinogen A. It preferentially cleaves peptide bonds flanked on either side by hydrophobic amino acids; for example, in the B chain of insulin it cleaves Phe^{1}-|-Val^{2}, Gln^{4}-|-His^{5}, Glu^{13}-|-Ala^{14}, Ala^{14}-|-Leu^{15}, Leu^{15}-|-Tyr^{16}, Tyr^{16}-|-Leu^{17}, Gly^{23}-|-Phe^{24}, Phe^{24}-|-Phe^{25}, and Phe^{25}-|-Tyr^{26} bonds (*compare* **pepsin B**). The unphosphorylated form of porcine pepsin A is called pepsin D.

pepsin B *or* **parapepsin I** a pig enzyme (EC 3.4.23.2) of the **pepsin** family. It is a phosphoprotein (332 amino acids) formed by limited proteolysis of pepsinogen B. It has little activity towards hemoglobin as substrate (*compare* **gastricsin**), but degrades gelatin. Its specificity on the B chain of insulin is more restricted than **pepsin A**; it does not cleave Phe^{1}-|-Val^{2}, Gln^{4}-|-His^{5}, or Gly^{23}-|-Phe^{24}.

pepsin C *an alternative name for* **gastricsin**.

pepsin D unphosphorylated pig **pepsin A**.

pepsinogen a precursor of a **pepsin** enzyme; pepsinogens A, B, and C give rise to **pepsin A**, **pepsin B**, and pepsin C (i.e. **gastricsin**) respectively. Pepsinogens are secreted by the chief cells of the gastric mucosa of vertebrates. Their active site is masked at neutral pH, and exposed as the pH falls after secretion into the stomach. The first bond breakage causes the release of residues 1–16, leaving **pseudopepsin**. A further 28 residues are removed in stages to form the active enzyme. Pepsinogen C is also secreted by the mucosa of the proximal duodenum. Human pepsinogen A consists of 388 amino acids; residues 63–388 are pepsin.

pepstatin A *N*-isovaleryl-L-valyl-L-valyl-3-hydroxy-6-methyl-4-aminoheptanoyl-L-alanyl-3-hydroxy-6-methyl-4-aminoheptanoic acid; a peptide, isolated from broth cultures of *Streptomyces* spp., that inhibits pepsin and other aspartic proteases, notably cathepsin D, renin, and fungal acid proteases.

peptaibophol *or* **peptaibol** any peptide amide antibiotic, 15–24 residues long and containing up to 40% α-aminoisobutyric acid residues. The group includes emerimicin, zervamicin IIA, antiamoebin I, sizukacillin A, and **alamethicin**, all of which alter the permeability of phospholipid bilayers. The N termini are acylated and the C-terminal carboxyl groups are in amide linkage with phenylalaninol.

peptic 1 of, pertaining to, caused by, or containing **pepsin**. **2** of, pertaining to, or promoting digestion.

peptidase *or* **peptide hydrolase** *or* **protease** any enzyme that hydrolyses peptide bonds. The group includes the **exopeptidases**, such as the aminopeptidases and carboxypeptidases, (sub-subclasses EC 3.4.11–19) and the **endopeptidases** (sub-subclasses EC 3.4.21–99). The 1992 revision of *Enzyme Nomenclature* (published for IUBMB by Academic Press) should be consulted for more detail.

peptidase P-sites sites adjacent to or near the cleaved site in peptidase substrates; in describing the specificity of peptidases, it is useful to have a convention for identifying the residues on either side of the cleaved bond; the following model is often followed (the cleaved, or scissile bond is indicated as -|-, and the N terminus is as usual to the left):

-P3-P2-P1-|-P1′-P2′-P3′-.

Compare **peptidyl site**.

peptide any compound containing two or more amino-acid residues joined by amide bond(s) (*see* **peptide bond**) formed from the carboxyl group of one amino acid (residue) and the amino group of the next. The term peptide usually applies to compounds in which the amide bond(s) are formed between C-1 of one α-amino acid (residue) and N-2 of another, but it includes compounds in which the residues are linked by other amide bonds. *See also* **oligopeptide**, **polypeptide**. **—peptidic** *adj.*

peptide amidation a post-translational modification in which the amido group of a glycine residue is cleaved so as to produce the amide group on the carboxyl end of the preceding residue. The reaction requires two enzymes: (1) peptidylglycine α-amidating monooxygenase (*abbr*.: PAM; EC 1.14.17.3), which is a copper-containing membrane protein that changes the glycine to a hydroxyglycine residue, in a reaction requiring O_2 and ascorbate; and (2) peptidylglycine α-amidating lyase, EC 4.3.2.5, which produces the peptidylamine and glyoxylate. Many bioactive peptides and peptide hormones exhibit full biological activity only when their C-terminal group is amidated. *See* **thyrotropin-releasing hormone**.

peptide antibiotic any antibiotic containing amino-acid residues, some of which are often of the D-form, linked to one another by peptide bonds, to hydroxy acids by depsipeptide bonds, and frequently also to additional components; the structure is often cyclic. The group includes the **bacitracins**, **gramicidins**, **polymyxins**, and **tyrocidins**.

peptide bond *or* **peptide linkage** any amide bond formed between two amino acids (or amino-acid residues). The term usually denotes the amide bond (sometimes called the **eupeptide bond**) formed between an α-amino group of one amino acid and an α-carboxyl group of another amino acid, but it also includes any amide bond (sometimes called an **isopeptide bond**) formed from an amino group and a carboxyl group, either or both of which are in other positions in the contributing amino acids. The peptide bond is planar. *See also* **Ramachandran plot**.

peptide chain *or* **polypeptide chain** any discrete linear sequence of amino-acid residues linked by eupeptide bonds, especially in a larger molecular structure. *See* **peptide bond**.

peptide HI *abbr*.: PHI; *other name*: PHI-27; a 27-residue peptide amide found in intestinal tissue, brain, respiratory tract, and pancreas. It stimulates insulin and pancreatic exocrine secretion, causes vasodilation, increases intestinal fluid transport, relaxes smooth muscle, and is a potent prolactin-releasing factor. It shows sequence homology with gastric inhibitory polypeptide, glucagon, secretin, and vasoactive intestinal polypeptide; human PHI has the sequence

$$\mathrm{HADGVFTSDFSKLLGQLSAKKYLESLM\text{-}NH_2}$$

(porcine PHI has Arg^{12} and Ile^{27}; bovine has Tyr^{10}, Arg^{12}, and Ile^{27}). It is named for the histidine and isoleucine residues (single-letter codes H and I) at the N and C termini, respectively, of the porcine and bovine peptides.

peptide histidine valine 42 *abbr*.: PHV 42; a peptide with N-terminal histidine and C-terminal valine, derived from residues 81–122 of prepro-vasoactive intestinal peptide.

peptide hormone *or* **polypeptide hormone** any peptide with hormonal activity in animals, whether endocrine, neuroendocrine, or paracrine. Such substances form a very diverse group physiologically, and the boundary between peptide hormones and protein hormones is somewhat indistinct.

peptide hydrolase *another name for* **peptidase**.

peptide library an assembly of peptides with different sequences, that have many applications in testing for interactions with proteins such as antibodies, peptidases, and protein kinases, nucleic acids, or other ligands. The peptides may be synthesised by combinatorial chemistry, or by phage display. They are typically arranged in an array for testing with fluorescent markers. Applications include epitope mapping, bioactivity screening, and other biochemical studies.

peptide linkage 1 *an alternative name for* **peptide bond**. **2** chemical linkage between structural components of a molecule by means of peptide bonds.

peptide map a pattern, characteristic of a particular polypeptide or protein, produced by partial hydrolysis, followed by two-dimensional fractionation of the resultant peptides (and amino acids) by chromatography and/or electrophoresis.

peptide nucleic acid a synthetic DNA analogue with an *N*-(2-aminoethyl)glycine backbone that mimics DNA in forming a **heteroduplex**.

peptidergic 1 describing any nerve that is activated by a peptide agonist. **2** describing any nerve that acts by releasing a peptide agonist from its nerve endings, whether into a synapse with another neuron, into intercellular fluid, or directly into the bloodstream.

peptide synthesis 1 *(in biology) see* **protein and peptide biosynthesis**. **2** *(in chemistry)* the synthesis, by chemical means, of peptides. The first step is the protection, in the amino-acid reactants, of reactive groups not involved in peptide bond formation (*see* **protecting groups**); peptide-bond formation is then achieved by activation of the carboxyl group, which is reacted with the free α-amino group of another amino acid. A method frequently used for activation of the carboxyl group is to react it with *N*-hydroxysuccinimide or a derivative to form an acyl succinimido ester, which reacts under mild conditions with free amino groups. Normally, and always in automated methods, the carboxyl group of the first amino acid is attached to a resin, by a bond that is easily detached later, so that the desired product, the growing peptide chain, remains attached to the resin which facilitates its purification; this technique, called **solid-phase peptide synthesis**, was pioneered by **Merrifield**.

peptide unit *(in crystallography)* any sequence of atoms in a peptide chain that may be represented by the general formula –CHR–CO–NH–, where R denotes the side chain of an amino-acid residue. *Compare* **amino-acid residue**.

peptide YY *abbr*.: PYY; a 36-residue peptide amide originally found in porcine upper small intestinal tissue. It is a gut hormone that inhibits exocrine pancreatic secretion. Members of this family regulate numerous physiological processes, including appetite, gastrointestinal transit, anxiety, and blood pressure. It shares sequence similarity with **neurotensin** and **pancreatic hormone**, having the amino-acid sequence:

$$\mathrm{YPIKPEAPGEDASPEELNRYYASLRHYLNLVTRQRYNH_2}$$

It is named after the single-letter code, Y, for the tyrosine residue at its N terminus and the tyrosine amide at its C terminus.

peptido+ *comb. form* indicating the presence of peptide linked to some other (specified) component(s).

peptidoglycan *or* **murein** any glycoconjugate found only in bacterial cell walls and consisting of strands of glycosaminoglycan cross-linked by oligopeptides to form a huge and rigid network. There are characteristic differences between peptidoglycans of eubacteria and those of archaebacteria. The glycosaminoglycan strands are formed of alternating residues, usually *N*-acetylated or *N*-glycoloylated, of D-glucosamine and either muramic acid (in Bacteria) or L-talosaminouronic acid (in archaea); the carboxyl groups of the muramic-acid residues are commonly joined in amide linkage to oligopeptides containing residues of both L- and D-amino acids whereas those of the L-talosaminouronic-acid residues are linked to peptides consisting of L-amino acids only. The peptide side-chains of adjacent polysaccharide strands are sometimes crosslinked between a carboxyl group of one peptide moiety and an amino group of another, either directly by a peptide bond or indirectly by an interpeptide bridge consisting of one to several amino-acid residues.

peptidomimetic describing a substance that imitates a peptide. It is used of drugs (e.g. ritonavir and saquinavir) that inhibit HIV protease because they resemble its natural substrate.

peptidyl the acyl group formed from a peptide by removal of the hydroxyl group from its C-terminal carboxyl group.

peptidylglycine α-amidating monooxygenase *abbr*.: PAM. *See* **peptide amidation**.

peptidyl α-hydroxyglycine α-amidating lyase an enzyme of the Golgi complex that catalyses the conversion in a polypeptide of an α-hydroxyglycine residue into a peptidyl amine and glyoxylate. This is the second reaction of C-terminal **peptide amidation**.

peptidylprolyl isomerase *abbr*.: PPIase; EC 5.2.1.8; *systematic name*: peptidylproline *cis–trans*-isomerase; an enzyme that irreversibly converts prolyl residues within a polypeptide chain from a *trans* to a *cis* configuration. It accelerates protein folding. At least two families are known. One is identical to **cyclophilin.** Another class of immunophilins that exhibit isomerase activity are the FK506-binding proteins (*see* **FKBP**). The physiological role of these proteins is unresolved. The peptide Ala-Pro inhibits the reaction.

peptidyl site *or* **P-site** *or (more correctly)* **peptidyl-tRNA site** the ribosomal site to which a newly elongated peptidyl-tRNA molecule is transferred from the aminoacyl site during the sequence of polypeptide biosynthesis reactions, and at which it displaces the tRNA molecule remaining from the previous elongation step. *Compare* **peptidase P-site**. *See also* **ribosome**.

peptidyltransferase EC 2.3.2.12; the ribosomal enzyme that catalyses the elongation step in polypeptide synthesis:

$$\text{peptidyl-tRNA}_1 + \text{aminoacyl-tRNA}_2 = \\ \text{tRNA}_1 + \text{peptidyl-aminoacyl-tRNA}_2.$$

It is an activity of the large ribosomal subunit involving, in bacteria,

ribosomal proteins L2, L3, L4, L15, and L16, and especially 23S rRNA, which is therefore a ribozyme. The activity of the 23S rRNA is removed by ricin. *See also* **peptidyl site**.

peptidyl-tRNA the form in which a growing polypeptide chain is held to a ribosome during polypeptide biosynthesis. The polypeptide is esterified through its C-terminal carboxyl group to the 3′-hydroxyl of the adenosine residue at the 3′ end of a tRNA. *See* **protein synthesis**.

peptize *or* **peptise** to disperse (an aggregate) to form a colloidally stable suspension or emulsion; especially to convert (a gel) into a sol. —**peptization** *or* **peptisation** *n.*

peptolide *(sometimes)* any naturally occurring cyclodepsipeptide; *see* **depsipeptide**.

peptone any soluble mixture of products, 0.6–3 kDa, of the partial enzymic (or acid) hydrolysis of proteinaceous material. It is used as a constituent of many microbiological culture media.

peptonize *or* **peptonise** **1** to convert (proteinaceous material) into **peptone**. **2** to combine with peptone; e.g., peptonized iron. —**peptonization** *or* **peptonisation** *n.*

per+ *comb. form* denoting **1** through, throughout, beyond; e.g. perennial. **2** *(in chemistry)* **a** (of an indicated element) being in a higher than usual state of oxidation; e.g. periodate. *See also* **peracid** (def. 1). **b** containing a higher than normal proportion of (an indicated element); e.g. **peroxide**. *See also* **peroxoacid**, **peroxy acid**. **c** (in the trivial names performic, peracetic, and perbenzoic acids) **peroxy+**. **d** exhaustive replacement of hydrogen (except any in a characteristic group) in an organic compound by (an indicated halogen); e.g. perfluoropentane, C_5F_{12}. *See also* **perhydro**.

PER *abbr. for* **period**.

peracid *or* **per-acid** **1** *a common name for* any inorganic acid in which the central element of the acid is in its highest state of oxidation. **2** *a common name for* **peroxoacid**. **3** *a common name for* **peroxy acid**.

per cent *or* **percent** *symbol*: %; containing or consisting of a specified numerical proportion (of some component in relation to a whole) expressed as a number fraction multiplied by 100; bearing a specified numerical relationship (to some quantity) similarly expressed. When the term per cent or the symbol % is applied to a solution, one of the designations w/w, w/v, or v/v may be appended according as the units used are mass per mass, mass per volume, or volume per volume, respectively.

percentage proportionality expressed per cent; it is used especially to qualify a substantive, e.g. percentage error.

perchloric acid *abbr.*: PCA; chloric(vii) acid, $HClO_4$; a compound used in chemical analysis as an oxidizing agent.

Percoll *the proprietary name for* a polydisperse preparation of colloidal silica particles rendered nontoxic to cells by a coating of polyvinylpyrrollidone. Aqueous dispersions of the material can be used to generate density gradients for the separation of cells, viruses, or cell organelles by sedimentation.

percutaneous through the skin; used especially of the route of administration of drugs applied to the skin.

perforin a lymphocyte pore-forming protein; it is produced by cytotoxic T cells when these are in contact with target cells, being stored in secretory vesicles, and released by local exocytosis. With Ca^{2+}, it polymerizes into transmembrane tubules that form pores in the target-cell membrane, and is thus capable of lysing non-specifically a variety of target cells.

performic acid *the trivial name for* peroxyformic acid, H–C(=O)–O–OH; a strong oxidizing agent, useful in protein chemistry for cleavage of any disulfide bond, R–S–S–R′, to the corresponding pair of sulfonic acid groups, $R–SO_3H + R'–SO_3H$, e.g. of a cystine residue to two cysteic-acid residues. Tryptophan residues are also oxidized, and methionine residues are converted to methionine *S*,*S*-dioxide residues.

perfusate any fluid used for a perfusion.

perfuse to pass fluid through an organ or tissue, especially artificially. —**perfusion** *n.*

perhydro+ *prefix (in chemical nomenclature)* signifying conversion of the indicated unsaturated organic compound to the corresponding fully hydrogenated compound; used especially where the parent compound is markedly unsaturated; e.g. perhydroanthracene, $C_{14}H_{24}$ (formed from anthracene, $C_{14}H_{10}$).

peri+ *comb. form* enclosing, surrounding; near.

periaxin a PDZ domain-containing protein that when mutated causes a severe demyelinating peripheral neuropathy called Dejerine–Sottas syndrome.

pericellular surrounding a cell or cells.

pericentric describing an inversion of part of a chromosome that spans the centromere, with breakpoints in both the arms. *Compare* **paracentric**.

pericentrin *see* **centrosome**.

pericentriolar material *see* **PCM1**.

perifusate any fluid used for a perifusion (*see* **perifuse**).

perifuse to pass a fluid around isolated cells or cell clusters in suspension. —**perifusion** *n.*

***peri*-fused** *see* ***ortho*- and *peri*-fused**.

perikaryon *or* **cell body** the cytoplasm immediately surrounding the nucleus of a neuron.

perilipin a protein found in adipocytes, exclusively at the surface of the lipid storage droplets that serves as the major A-kinase substrate. It is a major hormonally regulated adipocyte-specific phosphoprotein.

perinuclear space the zone, 20–40 nm wide, between the two lipid bilayers of the **nuclear envelope** of a eukaryotic cell.

period **1** a specified or defined length of time, especially the time occupied by one complete cycle of some regularly recurring phenomenon or event. **2** *(in chemistry)* any of the horizontal rows of chemical elements in the **periodic table**. **3** *abbr.*: PER; either of two **PAS domain**-containing proteins (PER1 and PER2) involved in regulating circadian rhythms. They are induced by the clock-BMAL1 dimer in the suprachiasmatic nucleus in hypothalamus, and by the NPAS2-BMAL1 dimer in forebrain nuclei. Their activity is regulated by a protein-serine/threonine kinase, and they act as negative regulators of the circadian control system, which was discovered in *Drosophila* mutants with abnormal circadian cycles. Homologues occur in other organisms including humans. *See also* **BMAL1**, **clock**, **NPAS2**.

periodate **1** any anion derived from a **periodic acid**, especially the anion, IO_4, derived from metaperiodic acid. **2** any salt of a periodic acid, especially of metaperiodic acid or orthoperiodic acid.

periodate oxidation a method for the investigation of the structure of organic molecules, based upon the ability of aqueous periodate (or periodic acid) to cleave specifically and quantitatively any carbon–carbon single bond where one carbon atom carries a hydroxyl group and the other carries an amino, carbonyl, carboxyl, or hydroxyl group, these groups being oxidized and the periodate reduced to iodate. The method is particularly useful in the structural analysis of carbohydrates. *See also* **periodic acid–Schiff reaction**.

periodic **1** of, relating to, or resembling a **period** (def. 1 or 2); happening or occurring in periods; intermittent; cyclical. **2** *(in chemistry)* denoting any of several oxoacids of iodine containing a greater proportion of oxygen than iodic acid. *See* **per+** (def. 2a), **periodic acid**. — **periodically** *adv.*

periodic acid any of a number of iodic(vii) acids formed by the combination of iodine heptoxide, I_2O_7, with water in different molecular proportions, especially **orthoperiodic acid** (formerly known as paraperiodic acid), H_5IO_6; **metaperiodic acid**, HIO_4, exists mainly as its salts. These acids and their salts are strong oxidizing agents.

periodic acid–Schiff reaction *abbr.*: PAS reaction; a chromogenic reaction used as a sensitive test for carbohydrate, either histochemically or in chromatography. It is based on the periodate oxidation of *vicinal* –CHOH– groups to –CHO groups and the subsequent reaction of these with **Schiff reagent** to give a characteristic magenta colour.

periodic classification *see* **periodic system**.

periodicity the recurrence (of some phenomenon or event) at constant intervals in space or time; a measure of the frequency of such recurrence.

periodic law *or* **Mendeleev's law** the principle that the properties of the chemical elements are a periodic function of their atomic numbers (originally, of their atomic weights).

periodic system *or* **periodic classification** any classification of the chemical elements on the basis of the **periodic law**.

periodic table a mode of representing the **periodic system**; it is a tabular arrangement of the chemical elements in horizontal rows and vertical columns in order of increasing proton number row by row, each row, or **period**, consisting of those elements from an alkali metal to the rare gas of next highest proton number (except for the last, incomplete, period) and each column, or **group**, consisting of a family or set of those elements with similar chemical properties. Over the years, numerous versions of such a tabular arrangement have been proposed and used, the three commonest formats having 8, 18, or 32 columns of elements. Of these, the ones most widely adopted latterly have been variations of the so-called long periodic table, in which there are 18 columns. The particular version of the long table illustrated on the endpapers is the one currently recommended by IUPAC and adopted for use elsewhere in this dictionary. In this IUPAC periodic table, as similarly in other versions of the long table, the 15 elements of proton numbers 57 to 71, the **lanthanoids**, occupy a single position in period 6 of group 3, and those of numbers 89 to 103, the **actinoids**, a single position in period 7 of group 3, practical considerations requiring these elements to be listed separately at the bottom of the table.

In previous versions of the long table it was usual for 14 of the columns to be formed into seven groups, numbered I to VII and each divided into A and B subgroups. However, these subgroup designations were not always applied the same way round, with the consequence that two alternative conventions for the long table have concurrently had widespread support – one commonly in Europe (and hitherto followed in principle by IUPAC), the other in North America and elsewhere. Furthermore, the three columns containing the elements iron, cobalt, and nickel, originally designated together as group VIII, and the eighteenth column, containing the noble gases and originally designated as group O, have sometimes been labelled group VIIIA and group VIIIB respectively in the European version of the table, whereas in the North-American version the noble gases have in recent years been assigned usually to group VIIIA. The resultant confusion led IUPAC to recommend in 1990 that the columns of the long periodic table now be serially numbered as groups 1 to 18. The correspondence of the group designations in the new IUPAC periodic table with those of the European and North-American conventions in recent use is also shown in the endpapers.

peripheral (cell-membrane) protein *or* **extrinsic protein** *an operational term for* any protein that can be dissociated unchanged from a cell membrane by a mild treatment, such as increase in ionic strength of the medium, or addition of a chelating agent to it. Such proteins are presumed to be loosely attached to one or other surface of the cell membrane. *Compare* **integral (cell-membrane) protein**.

peripheral nervous system the part of an animal's nervous system other than the **central nervous system**, and generally located in the peripheral, or outer, parts of the body. It comprises the cranial nerves and spinal nerves and their branches, and includes the **autonomic nervous system**. It serves to link effector organs and sensory receptors with the central nervous system.

peripherin a glycoprotein, named from 'peripheral vision', that is essential for eye-disk morphogenesis; it is probably an adhesion molecule. Dysfunctional forms of peripherin precipitate retinopathies such as **retinitis pigmentosa**.

peripherin/RDS *see* **peripherin**.

periplasm *or* **periplasmic space** the region in a bacterial cell between the cell membrane and the cell wall.

peristalsis a wavelike sequence of involuntary muscular contraction and relaxation that passes along a tubelike structure, such as the intestine, impelling the contents onwards. —**peristaltic** *adj.*

peristaltic pump a pump that functions, by analogy with the action of **peristalsis**, by the repeated compression of a length of elastic tubing in such a way as to cause the contents of the tubing to move in one direction in a pulsating fashion but with an overall flow rate that is constant and regulated by the rate of pulsation and the tubing diameter.

peritoneum the thin translucent membrane, consisting of a single layer of flattened mesothelial cells and fibrous connective tissue, that lines the abdominal cavity and covers most of the viscera. —**peritoneal** *adj.*; **peritoneally** *adv.*

PERK *abbr. for* perturbed folding-activated kinase; *other names*: pancreatic ER-stress kinase; eIF-2 kinase. A protein serine/threonine kinase of the endoplasmic reticulum (ER) membrane, found especially in pancreatic cells. Its luminal regulatory domain normally binds BiP (*see* **binding protein**), which inhibits the cytosolic catalytic domain. When unfolded proteins accumulate in the lumen (i.e. under ER stress), BiP is released and the catalytic domain is activated. One substrate is the initiation factor eIF-2, which on phosphorylation suppresses protein synthesis. PERK-deficient mice develop marked hyperglycemia soon after birth. Inactivating mutations in humans result in a form of diabetes mellitus type I, which is associated with multiple epiphyseal abnormalities, called Wolcott–Rallison syndrome.

Perl *see* **programming language**.

perlecan *another name for* **heparan sulfate proteoglycan core protein**. *See also* **syndecan**.

permeability 1 the quality or degree of being permeable or porous. **2** *or* **magnetic permeability** (of a substance) *symbol*: μ; the ratio of the **magnetic induction**, B, to the magnetic field strength, H, at any point within the substance, i.e. $\mu = B/H$. The SI unit is the henry per metre or newton per square metre.

permeability coefficient a measure of the ability of a specified permeant to diffuse across a permeability barrier. It is expressed as the amount of substance of the permeant passing through a unit area of the barrier in a unit time when a unit difference in amount-of-substance concentration is applied across it.

permeability of vacuum *symbol*: μ_0; a fundamental physical constant, of value $4\pi \times 10^{-7}$ H m^{-1} exactly.

permeability transition pore a pore believed to form at sites of contact between the inner and outer mitochondrial membranes. It probably consists of the voltage-dependent anion channel (VDAC) of the outer membrane, the adenine nucleotide translocator of the inner membrane, and cyclophilin D of the matrix. When open the channel is permeable to particles of <1500 Da. Its opening probably dissipates the H$^+$ gradient and uncouples oxidative phosphorylation.

permeabilize *or* **permeabilise** to render permeable. In cell biology, agents such as **saponin**, streptolysin O (*see* **streptolysin**), or an applied electric field are used to open holes in the plasma membrane of cells. —**permeabilization** *or* **permeabilisation** *n.*

permeable capable of being permeated; pervious.

permeant 1 able to permeate or to diffuse into or through. **2** a substance having such properties.

permease a historical designation of some specific transport proteins; **transporter** is preferable.

permeate to pass through, or cause to pass through, by diffusion; to pervade. —**permeation** *n.*

permeation chromatography any form of chromatography in which a permeable stationary phase is used and in which separation of the components of a mixture is based mainly upon selective exclusion effects, such as differences in molecular size and/or shape (in **molecular-sieve chromatography**) or differences in charge (in **ion-exclusion chromatography**). *See also* **gel-permeation chromatography**.

permissible allowable. —**permissibility** *n.*; **permissibly** *adv.*

permissive 1 allowing; tolerant. **2** *(in virology)* describing a line or strain of cells that allows replication of a specified infecting virus with consequent cell lysis. **3** *(in genetics)* describing a condition, e.g. temperature, or set of conditions that permits the growth of a conditional lethal mutant (*see* **conditional lethal mutation**). —**permissiveness** *n.*; **permissively** *adv.*

permissive temperature *see* **temperature-sensitive mutation**.

permittivity *see* **relative permittivity**.

permselective selectively permeable to certain (classes of) molecular entities.

permutation 1 the process or act of permuting. **2** any of the possible arrangements of the members of a specified set of conditions, numbers, residues, etc.

permute to change the sequence or arrangement of.

Permutit *a proprietary name for* ion-exchange materials and equipment utilizing **permutites**.

permutite any of a class of artificial zeolite ion-exchangers.

pernicious anemia *or (esp. Brit.)* **pernicious anaemia** a form of macrocytic anemia characterized by defective production of erythrocytes and the presence of megaloblasts in the bone marrow, and sometimes accompanied by neurological changes. It is caused by a deficiency of vitamin B_{12} due to either a dietary deficiency of the vitamin or a failure of production of **intrinsic factor**.

per os *Latin* by mouth; used especially to denote the administration of drugs, etc. by the oral route.

peroxidase **1** any oxidoreductase enzyme of the sub-subclass EC 1.11.1. These act on hydrogen peroxide as (electron) acceptor with the formation of water. **2** *the recommended name of* the enzyme EC 1.11.1.7, a hemoprotein that catalyses the reaction of hydrogen peroxide with a wide variety of donors, i.e.

$$\text{donor} + H_2O_2 = \text{oxidized donor} + 2\ H_2O.$$

Apart from removing H_2O_2, it participates in the oxidation of toxic reductants and in lignin metabolism. In plants there are isoforms in different tissues. **—peroxidatic** *adj.*

peroxidase–antiperoxidase *abbr.*: PAP; a soluble complex of horseradish **peroxidase** (def. 2) and an antibody to this peroxidase, used in immunochemical procedures in conjunction with specific primary and bridging second antibodies to give a sensitive method of detecting complementary antigens enzymatically.

peroxide **1** *(in inorganic chemistry)* **a** the O_2^{2-} ion. **b** any member of a class of metallic oxides, such as sodium peroxide, Na_2O_2, that contain the peroxide ion and generate hydrogen peroxide on acidification. The name is sometimes used erroneously for certain higher oxides that do not contain the O_2^{2-} ion; e.g. lead peroxide (lead(iv) oxide, PbO_2), manganese peroxide (manganese(iv) oxide, MnO_2), nitrogen peroxide (nitrogen(iv) oxide, NO_2 or N_2O_4). **c** *short for* hydrogen peroxide, H_2O_2; an oxidizing agent. **2** *(in organic chemistry)* **a** any compound of general formula R'–O–O–R'', where the groups R' and R'' are two chains, two rings, or a ring and a chain, and including cases when R' = R''; e.g. ethyl phenyl peroxide, benzoyl (strictly, dibenzoyl) peroxide. In hydrogen peroxide, R' = R'' = H. **b** *see* **hydroperoxide**.

peroxin *or* **PEX protein** any protein in yeast or mammalian cells that mediates the import of peroxisomal integral membrane and matrix proteins and is necessary for peroxisome biogenesis. Fifteen PEX genes are known in humans. They encode receptors for the two peroxisome target signals, plus cytosolic and peroxisomal proteins. Mutations in several of the genes lead to **Zellweger's syndrome** and infantile **Refsum's disease**. *See* **peroxisome targeting sequence**.

peroxiredoxin (*abbr.*: Prx) *or* **thioredoxin peroxidase** *or* **alkyl peroxide reductase** any member of an abundant and widespread family of antioxidant enzymes, capable of removing hydrogen peroxide and alkyl hydroperoxides from cells. The enzymes contain an active-site cysteine, which is oxidized by peroxide to a sulfenate, which is subsequently reduced by a thiol-containing protein such as thioredoxin.

peroxisomal bifunctional enzyme a monomeric peroxisomal enzyme (mainly in kidney and liver) with the activities of three steps in the **beta-oxidation system**, i.e. **enoyl-CoA hydratase**, **3,2- trans-enoyl-CoA isomerase**, and **3-hydroxyacyl-CoA dehydrogenase** activities.

peroxisomal disorder any disorder in which peroxisomes are absent or severely reduced in number, are incapable of importing a group of resident proteins, or lack a particular resident enzyme activity. Examples include **Zellweger's syndrome**, and adult and infantile forms of **Refsum's disease**.

peroxisome a type of eukaryotic cell organelle that is rich in enzymes that act on or generate hydrogen peroxide, especially the enzymes catalase, (*S*)-2-hydroxy-acid oxidase, and D-amino-acid oxidase. Peroxisomes occur in mammalian kidney and liver, and in yeasts and certain protozoans. They contain over 50 matrix enzymes involved in degradation of very-long-chain, branched, or polyunsaturated fatty acids, in the conversion of cholesterol to bile acids, and in biosynthesis of other phospholipids and isoprene compounds. They are particularly numerous in leaf photosynthetic cells of plants, photosynthesizing via the Calvin (C_3) pathway; in plants they are closely associated with chloroplasts and mitochondria, which is consistent with their function in **photorespiration**. **—peroxisomal** *adj.*

peroxisome proliferator-activated receptor *see* **PPAR**.

peroxisome targeting sequence *abbr.*: PTS; either of two highly conserved peptide sequences that target proteins to the peroxisomal matrix. PTS1 is the C-terminal sequence –Ser–Lys–Leu. It is present in the majority of such proteins and is recognized by PEX5, which contains six or seven tetratricosapeptide repeats in its C-terminal half. PTS2 is the N-terminal consensus sequence –Arg–Leu–Xaa$_5$–His–Leu–. It is present in a small minority and is recognized by PEX7, which contains six WD40 repeats. *See* **peroxin**.

peroxo+ *prefix (in inorganic chemical nomenclature)* indicating substitution (in the corresponding acid) of an –OH group by the –O–OH group; e.g. peroxomonosulfuric acid, HO–SO_2–O–OH.

peroxoacid *(in inorganic chemistry)* any acid that contains the –O–OH group. *Compare* **peroxy acid**.

peroxonitrite *the recommended term for* the anion of peroxynitrous acid, O=N–OO$^-$; a highly reactive oxidizing species formed by reaction of nitrogen monoxide (NO) with superoxide, or nitroxyl ion with O_2. It has been implicated in cellular damage resulting from the **respiratory burst**.

peroxy+ *prefix or infix (in carboxylic-acid nomenclature)* indicating substitution of the –OH group in the carboxyl group by the –O–OH group; e.g. peroxypropionic acid, CH_3–CH_2– CO–O–OH. *See also* **per+** (def. 2c).

peroxy acid *(in organic chemistry)* any acid that contains the –CO–O–OH group. *Compare* **peroxoacid**.

peroxyformic acid *see* **performic acid**.

peroxynitrite *see* **peroxonitrite**.

perpendicular dichroism *see* **dichroic ratio**.

persalt any salt of a **peroxoacid** or a **peroxy acid**.

perseitol D-*glycero*-D-*galacto*-heptitol; a substance found in avocado and the alligator pear.

persephin a secreted protein that is structurally related to **glial cell-derived neurotrophic factor** and neurturin and like these binds a specific GPI-anchored membrane protein that recruits and signals through **RET**.

perspective formula a type of **projection formula** in which the bonds of (a part of) a molecule tend to be depicted with increasing boldness according to their nearness to the viewpoint, and vice versa, in order to give an impression of perspective. *See* **Haworth representation**, **Mills perspective representation**.

Perspex *a proprietary name for* **poly(methyl methacrylate)**.

pertactin *other name*: outer membrane protein P68; an agglutinogen of *Bordetella* spp. that binds to eukaryotic cells, and is involved in the pathogenicity in whooping cough. It contains the **RGD** sequence motif.

perturb to cause a selective and measurable change in the state of equilibrium of a system, or in its associated properties, through the action or influence of a specific external agent; to undergo perturbation. **—perturbable** *adj.*

perturbant an agent (capable of) causing perturbation.

perturbation **1** the action or process of perturbing; an instance of this. **2** the condition of being perturbed. **3** a cause or factor of disturbance; perturbant.

pertussis toxin a toxic protein complex produced by *Bordetella pertussis*, the bacterium responsible for whooping cough in young children. The toxin causes inactivation of the iα subunit of the **G-protein** through catalysing ADP-ribosylation of a cysteine residue that is the NAD-dependent ADP ribosyltransferase (EC 2.4.2.–). The toxin consists of five proteins (S1–S5) organized in two functional subunits, A and B. Subunit A comprises S1, which has the enzymic activity, and irreversibly uncouples the GTP-binding proteins $G_{i\alpha}$ and **transducin** from their membrane receptors. Subunit B binds to the membrane receptors; it has the composition S2S3S5S4$_2$, dimers S2S4 and S3S4 being held together by S5.

pervaporate to vaporize a liquid from one side of a semipermeable membrane with which it is in contact on the other side, as a means of concentrating a solution or suspension in that liquid. **—pervaporation** *n.*

pervious permeable.

PEST hypothesis the hypothesis that the presence of one or more regions rich in proline (P), glutamic acid (E), serine (S), and threonine (T) in the primary structure of a protein confers susceptibility to rapid intracellular proteolysis.

pesticide any substance, natural or artificial, used to kill pests.

PET *abbr. for* positron emission tomography; *see* **tomography**.

peta+ *symbol*: P; SI prefix denoting 10^{15} times.

PETG *abbr. for* polyethyleneterephthalate glycol; a plastic developed as an alternative to PVC for use in packaging; in contrast to PVC it does not produce chloride fumes when burned, giving off only CO_2 and H_2O. Flexible, clear, robust, and light, it is also suitable for contact with food, since no plasticizers or stabilizers are used in its manufacture.

petite **1** describing a strain of yeast (or other) cells derived from a spontaneous mutant in which certain respiratory enzymes are defective or deficient, with consequent very slow growth and formation of unusually small colonies. **2** describing such a colony or mutant.

Petri dish *or* **Petri plate** a shallow, flat-bottomed, circular dish, usually of glass or transparent plastic and 5–15 cm in diameter, with a loosely fitting, overlapping cover. It is used especially for plate cultures of bacteria and moulds on solid (gelled) media, and for tissue culture. [After Richard Julius Petri (1852–1921), German bacteriologist.]

petroselaidic acid *see* **octadecenoic acids**.

petroselenate *numerical symbol*: 18:1(6); *the trivial name for* *Z*-octadec-6-enoate; a component of the fatty-acid hydrolysate of umbelliferous seed oils.

petroselenic acid *see* **octadecenoic acids**.

pET vector a plasmid vector designed for the overexpression of cloned genes in *E. coli*. Expressed proteins are fused to a **His-tag** or other fusion partner incorporated to facilitate purification. Expression is under the control of the bacteriophage T7 promoter and is caused by inducing the T7 RNA polymerase in the host cell, often **BL21** (DE3), with **isopropyl *β*-thiogalactoside** (IPTG).

PEX5 *see* **peroxin**; **peroxisome targeting sequence**.

PEX7 *see* **peroxin**; **peroxisome targeting sequence**.

PEX protein *an alternative name for* **peroxin**.

pEX vector a plasmid vector designed for overexpression of cloned genes in *E. coli*. Sequences are cloned at the 3′ end of ***lacZ*** and the product is a fusion protein with *β*-galactosidase at the N-terminus. Some proteins expressed in this way are less susceptible to intracellular proteolysis.

Peyer's patch any of numerous subepithelial aggregates of lymphoid tissue found in the intestinal mucosa. The M cells that overlie them transmit bacterial and viral protein antigens, which induce proliferation of the lymphoid cells and the secretory immune response. [After Johann Peyer (1653–1712), Swiss anatomist.]

Pfam *see* **pattern database**.

pFc′ fragment a protein fragment obtained (together with **$F(ab')_2$ fragment**) by pepsin hydrolysis of an immunoglobulin molecule. That from human IgG is a 27 kDa protein, which is a non-covalently bonded dimer consisting of the C-terminal moieties of the heavy chains, and resembles the **Fc fragment** without the residues containing the linking disulfide bond.

PFGE *abbr. for* **pulsed field gel electrophoresis**.

PFP *abbr. for* pore-forming peptide *or* pore-forming protein; the term embraces cytotoxic peptides such as staphylococcal δ-toxin, **alamethicin**, **magainins**, and **cecropins**; pore-forming proteins include staphylococcal α-toxin, **streptolysin**-O, cnidarian toxins, **perforin**, and **aerolysin**.

PFK *abbr. for* phosphofructokinase.

pfu *abbr. for* plaque-forming unit; a measure of the abundance of viruses or bacteriophages based on their ability to form zones of infection (plaques) on a monolayer of host cells.

***Pfu* polymerase** a thermostable DNA polymerase from *Pyrococcus furiosus* valued for its 3′→5′ exonuclease activity that imparts a **proofreading** function. Transcripts produced with *Pfu* polymerase have a lower error rate than can be obtained with enzymes such as *Taq* polymerase, which lack 3′→5′ exonuclease activity.

pg *symbol for* picogram (i.e. 10^{-12} gram).

p*G* *symbol for* titration p*K*.

PG *abbr. for* **1** phosphatidylglycerol. **2** prostaglandin. **3** protegrin.

PGA *abbr. for* **1** phosphoglyceric acid. **2** pteroylglutamic acid. **3** prostaglandin A; *see* **prostaglandin**.

$PGAH_4$ *abbr. for* tetrahydropteroylglutamic acid.

PGAM *abbr. for* phosphoglycerate mutase.

PGB *abbr. for* prostaglandin B; *see* **prostaglandin**.

PGD *abbr. for* **1** phosphogluconate dehydrogenase (EC 1.1.1.43). **2** prostaglandin D (*see* **prostaglandin**).

PGE *abbr. for* prostaglandin E; *see* **prostaglandin**.

pGEM vector a proprietary plasmid vector used for cloning polymerase chain reaction (PCR) products. Some DNA polymerases (such as *Taq* polymerase) add a single deoxyadenosine 5′ phosphate to the 3′ ends of amplified fragments and these can be ligated to the single 3′ thymidine overhangs of the linear pGEM vector.

pGEX vector any of various proprietary plasmid vectors used for the expression of foreign proteins in *E. coli*. Genes of interest are cloned downstream, and in the same reading frame, from the gene for glutathione-*S*-transferase (GST), and the product is a fusion protein with GST at the N-terminus. The presence of GST facilitates purification of the fusion protein by affinity chromatography on columns of immobilized glutathione, and its immunodetection using anti-GST antisera. Immediately downstream from GST and upstream from the protein of interest is a short stretch of sequence containing a motif recognized by thrombin (factor Xa). Proteolytic digestion of the fusion protein cleaves the protein of interest from GST. Expression of GST fusion proteins is under the control of the *tac* promoter and is induced with **isopropyl *β*-thiogalactoside** (IPTG).

PGF *abbr. for* prostaglandin F; *see* **prostaglandin**.

PGF synthase *abbr. for* prostaglandin-F synthase.

PGG *abbr. for* prostaglandin G (*see* **prostaglandin**).

PGH *abbr. for* prostaglandin H (*see* **prostaglandin**).

PGH synthase *see* **prostaglandin-endoperoxide synthase**.

PGI *abbr. for* prostaglandin I (i.e. **prostacyclin**).

PGK *abbr. for* phosphoglycerate kinase.

pGL vector any of a number of proprietary plasmid vectors used for the analysis of promoter or enhancer function. The putative promoter is cloned upstream from the firefly luciferase gene, whose expression can be detected with great sensitivity if the promoter is active in mammalian cells transfected with the pGL construct.

P glycoprotein *or* **MDR protein 1** a glycoprotein associated with drug resistance; it is a transmembrane ATP-dependent transporter that pumps hydrophobic substances out of cells. Drug-resistant cells demonstrate increased expression of the P-glycoprotein gene as one mechanism for their resistance to, e.g., chemotherapeutic anticancer drugs. *See also* **MDR**.

PGT *(in clinical chemistry) abbr. for* phosphoglucomutase.

pH a dimensionless quantity notionally defined as the negative decadic logarithm of the molal activity of hydrogen ions in a solution. Since the activity of a single species of ion is not measurable, pH is defined operationally according to the equation:

$$\mathrm{pH(X)} = \mathrm{pH(S)} + (E_s - E_x)F/(RT\ln 10)$$

where pH(S) and pH(X) are the pH values of a standard solution, S, and of the test solution, X, respectively; *F* is the Faraday constant, *R* the gas constant, and *T* the thermodynamic temperature; and E_s and E_x are, respectively, the electromotive forces of the two galvanic cells:

reference electrode | KCl (conc.) || soln. S | H_2(g) | Pt,

and

reference electrode | KCl (conc.) || soln. X | H_2(g) | Pt,

both cells being at the same temperature, with identical reference electrodes and bridge solutions, KCl (aq, $m \geq 3.5$ mol kg^{-1}). A **pH standard** solution, S, is chosen from a set of five covering the range pH 3.5 to pH 9, an assigned value of pH(S) at the required temperature being obtained from published tables. To a good approximation, the hydrogen electrodes in the two cells may be replaced by other hydrogen-ion-responsive electrodes, such as glass or quinhydrone electrodes. Originally pH was considered as the negative decadic logarithm of the molar concentration of hydrogen ions, a practice retained to the present day as representing a convenient approximation.

pH* *a notation commonly used to denote* the apparent pH of a solution containing ^2H_2O (i.e. D_2O), as measured electrometrically using a glass electrode without correction for the isotope effect on the electrode.

Ph *symbol for* the phenyl group.

PH-30 *or* **PH30** a sperm surface protein, with **disintegrin** and metalloprotease domains; that from *Cavia cobaya* consists of two subunits, α and β.

PHA *abbr. for* phytohemagglutinin (def. 1).

pH-activity profile *or* **pH profile** a plot of enzyme activity against pH, over a range in which the activity is reversibly affected by pH.

phaeo+ *an alternative spelling (esp. Brit.) of* **pheo+**.

phaeochromocytoma *an alternative spelling (esp. Brit.) of* **pheochromocytoma**.

phaeofarnesin *an alternative spelling (esp. Brit.) of* **pheofarnesin**.

phaeomelanin *an alternative spelling (esp. Brit.) of* **pheomelanin**.

phaeophorbide *an alternative spelling (esp. Brit.) of* **pheophorbide**.

phaeophytin *an alternative spelling (esp. Brit.) of* **pheophytin**.

phage *abbr. for* bacteriophage.

phage conversion *an alternative name for* **bacteriophage conversion**.

phage display library a special example of a gene library encoding fusion proteins of a foreign polypeptide sequence and a coat protein of phage M13 or (more usually) the closely related phage fd. When cloned, the phage is then said to display the foreign protein (in the coat proteins). There are two common versions of the technique. In one, the library consists of random oligonucleotides (e.g. 7-mers). Clones expressing oligopeptides that react with a specific antibody can then be selected using the antibody. In the other version, the library consists of oligonucleotides encoding a range of single-chain variable-domain antibodies. This approach is used where an antibody is required for an oligopeptide, which can thus be used to detect appropriate clones.

phage immunity the immunity conferred on a **lysogenic bacterium** by the presence of a **prophage** and a consequence of the expression of a gene such as *c*I in **lambda phage**.

phage induction *or* **prophage induction** the stimulation of prophage in lysogenic bacteria to enter the vegetative state. It is accomplished by the action of UV light, X-rays, nitrogen mustards, etc.

phage lambda *see* **lambda phage**.

phagemid a chimeric phage–plasmid **cloning vector** containing origins of both double-stranded and single-stranded replication. *See also* **phasmid**.

phage T4 an icosahedral DNA-containing **bacteriophage** that infects *Escherichia coli.* Its single molecule of double-stranded DNA is 174 kb in length. Various enzymes prepared from this phage are commonly used in genetic engineering; these include ligase, polymerase, and polynucleotide kinase.

phage typing a procedure for classifying bacteria according to their susceptibility to various bacteriophages.

phagocyte any cell that characteristically engulfs particles from its surroundings into its cytoplasm by **phagocytosis**. **—phagocytic** *adj.*

phagocyte NADPH oxidase *abbr.*: phox; a phagosomal and plasma membrane complex that transfers electrons from NADPH, via FAD and heme, to O_2 to produce superoxide (O_2^-) and other microbicidal reactive species. The process constitutes the **respiratory burst**. The complex assembles and becomes active when phagocytes are activated in response to inflammatory stimuli. It consists of membrane components (gp91-phox and p22-phox, together called **cytochrome** b_{245}) and cytosolic components (p47-phox, p67-phox, and a Ras-related GTPase). Deficiency or dysfunction of any of the four phox proteins causes chronic granulomatous disease. Examples: human p47-phox, 390 amino acids; p67-phox, 526 amino acids.

phagocytosis a type of endocytosis whereby certain cells – phagocytes – can engulf external particulate material by extension and fusion of pseudopods around each particle. The particles are initially contained within phagocytic vacuoles (**phagosomes**), which then fuse with primary lysosomes to effect digestion of the particles. Phagocytosis is employed by certain cells of the immune system, notably macrophages and neutrophils, to engulf and destroy target cells, tissue debris, and other particles, and by amoeboid protozoans. *Compare* **pinocytosis**.

phagolysosome an organelle formed by the fusion of a **phagosome** and a **lysosome**. Immediately after fusion there is a brief rise in the pH of the phagolysosome and neutral proteases and cationic proteins are active. Subsequently the pH falls and acid proteases become active. Indigestible substances remain in the phagolysosomes forming residual bodies.

phagosome an inclusion in a eukaryotic cell that arises from the ingestion of particulate material by **phagocytosis**. The phagosomes subsequently fuse with **lysosomes** to form a **phagolysosome**.

phalloidin *see* **phallotoxin**.

phallotoxin any bicyclic heptapeptide present in the highly poisonous agaric fungus, *Amanita phalloides*, commonly called the death-cap fungus or deadly agaric, and in some related species; **phalloidin** is the best-known member. All phallotoxins but one are toxic, though not as intensely so as the congeneric and much more slowly acting **amatoxins**; high doses of phalloidin in mice or rats cause death in a few hours. The common elements include residues of *cis*-4-hydroxy-L-proline, a D-amino acid (which is either threonine or *β*-hydroxyaspartic acid), and L-tryptathionine (which forms a thioether bridge across the molecule). The majority of phallotoxins bind specifically to F actin and so prevent its depolymerization to G actin, thereby blocking the turnover of microfilaments and inhibiting cell movement.

phane nomenclature a method for naming organic structures by assembling names that describe component parts of a complex structure. A relatively simple skeleton for a parent hydride structure is modified by 'amplification', a process that replaces one or more special atoms (superatoms) of the simplified skeleton by multiatomic structure(s).

phantom indel a spurious insertion or deletion that arises when physical irregularities in a sequencing gel cause the reading software either to call a base too soon, or to miss a base altogether.

pharmaceutic *an alternative name for* **pharmaceutical** (def. 2).

pharmaceutical 1 of, or pertaining to, drugs or pharmacy. **2** *or* **pharmaceutic** any medicinal substance, mixture, or formulation. **—pharmaceutically** *adv.*

pharmaceutics *an alternative name for* **pharmacy** (def. 1).

pharmaco+ *comb. form* indicating a drug or drugs.

pharmacodynamics *functioning as sing.* the branch of pharmacology dealing with the effects of drugs on the body, i.e. with the physiological, therapeutic, and toxicological responses to drugs with particular regard to the extent and time course of such effects. **—pharmacodynamic** *adj.*; **pharmacodynamically** *adv.*

pharmacogenetics *functioning as sing.* the branch of pharmacology dealing with the genetic mechanisms underlying individual differences in responses to drugs. **—pharmacogenetic** *adj.*; **pharmacogenetically** *adv.*

pharmacogenomics the analysis of drug responses with respect to genomic information (e.g. polymorphisms), aiming to customize therapies and reduce adverse drug reactions.

pharmacognosy the study of crude drugs of natural origins. **—pharmacognostic** *adj.*

pharmacokinetics *functioning as sing.* the branch of pharmacology dealing quantitatively with the movement of drugs within the body, i.e. with the absorption, distribution, metabolism, and elimination of drugs. **—pharmacokinetic** *adj.*; **pharmacokinetically** *adv.*

pharmacological *or (esp. US)* **pharmacologic 1** of, pertaining to, or used in pharmacology. **2** (of an effect of a naturally occurring agonist) caused by an unphysiological concentration; (of a concentration or dose of a naturally occurring agonist) having an unphysiological effect. **—pharmacologically** *adv.*

pharmacology the science or study of drugs – their origin, characteristics, identification, biological effects, and modes of action. *Distinguish from* **pharmacy**.

pharmacophore the cluster of atoms in a drug that endows it with its pharmacological properties.

pharmacopoeia *or (US, sometimes)* **pharmacopeia 1** an authoritative book, often an official one, containing descriptions of medicinal drugs with their uses, preparation, methods of assay, formulae, dosages, etc. **2** the whole range of medicinal drugs in use or available. **—pharmacopoeial** *or* **pharmacopoeic** *adj.*

pharmacy 1 *or* **pharmaceutics** the practice of preparing and dispensing drugs. 2 a dispensary (for drugs). *Distinguish from* **pharmacology**.

pharming the production of medicinally active substances by genetic manipulation of farm animals or plants. [From a combination of 'pharmaceutical' and 'farming'.]

phase 1 any distinct or characteristic period or stage in a sequence of events, occurrences, or processes, whether cyclical or unidirectional; e.g. the phases in the life cycle of an organism or the phases of the **cell-division cycle** (*see also* **anaphase**, **gap phase**, **metaphase**, **prophase**, **telophase**). 2 *(in physical science)* **a** the totality of those parts of a heterogeneous material system that are identical in chemical composition and physical state, and that are separated by an interface from the rest of the system; e.g. solid, liquid, or vapour phases, or the discrete phases into which immiscible liquids separate after mixing, etc. *See also* **epiphase**, **hypophase, liquid-crystalline phase**, **phase transition**. **b** a particular stage in the cycle of a periodic phenomenon, process, or quantity; the fraction of such a cycle that has been completed at a specific reference time, expressed in circular measure (or its equivalent in angular degrees). Two or more waveforms (or two or more similar sequences of events, etc.) that are in corresponding phases at the same time are described as 'in phase', while ones not exhibiting such correspondence are described as 'out of phase'. —**phasic** *adj.*

phase-contrast microscopy *or* **phase microscopy** a form of light microscopy in which a colourless object having a different refractive index from that of the medium is viewed by converting differences in refractive index into visible differences in light intensity. The technique takes advantage of the quarter-wave retardation of the illuminating light that occurs on its diffraction by the object, imposes a similar change of phase on the undiffracted light, and forms an image by interference between the two beams of light.

phaseolin 1 a crystallizable globulin found in seeds of the kidney bean, or French bean, *Phaseolus vulgaris*, and the lima bean, *Phaseolus lunatus*. It is a major seed-storage protein. α and β types are known. 2 *a former name for* **phaseollin**. 3 *an alternative name for* **legumain**.



phase rule a generalization, valuable in the study of equilibria between **phases** (def. 2), expressed by the equation:

$$F = C - P + 2$$

where C is the number of chemically distinguishable components present, P is the number of phases in equilibrium, and F is the number of degrees of freedom of the system, i.e. the number of independently variable intensive properties that must be specified in order to describe completely the state of the system.

phaseshift mutation *an alternative term for* **frameshift mutation**.

phase transition (of lipids) the transition of a lipid between any of the various phases it can adopt. The transition is dependent on factors such as temperature, purity of the lipid, state of hydration, and, if not pure, the composition of the mixture. In the nonhydrated state, a crystalline polar lipid can on heating, prior to a complete melting, adopt a **liquid-crystalline phase**, in which the polar groups are still associated in sheets, so that the overall structure consists of lipid bilayers, but the fatty-acyl chains undergo increased thermal vibrations leading to considerable disorder; the temperature at which this transition occurs is known as the **phase-transition temperature**. In the presence of water, below the phase-transition temperature, phospholipids adopt a gel phase, in which water penetrates between the sheets of polar headgroups, but the fatty-acyl chains are highly ordered. On increasing the temperature through the phase-transition temperature, the lipid adopts a hydrated liquid-crystalline phase with disordered fatty-acyl chains. The term **fluidity** has been used to provide a qualitative description of these changes, the bilayer being said to become more fluid as the temperature increases. *See also* **hexagonal phase**.

phase variation (*of flagellin*) *see* **flagellin**.

phasmid 1 a gene-cloning vector consisting of an artificial combination of a plasmid with a phage such that its genome contains functional origins of replication of both; it may thus be propagated either as a plasmid or as a phage in appropriate host strains. A phasmid is formed by insertion of one or more plasmid molecules into a phage genome. *Compare* **cosmid**, **phagemid**. 2 either of a pair of lateral caudal organs characteristic of parasitic nematodes of the class Phasmidia; they are thought to function as chemoreceptors. 3 any plant-eating insect of the order Phasmida, which includes leaf insects and stick insects.

PhD enzyme a phospholipase D enzyme belonging to a family characterized by the HKD catalytic motif (i.e. HXKX$_4$DX$_6$GG/S, using the single-letter code for amino acids). PhD enzymes are present in certain viruses and in bacteria, fungi, plants, and animals.

PHD finger *abbr. for* plant homeodomain zinc finger; a particular type of zinc finger, widely distributed in eukaryotes and found in many chromatin regulatory factors. It is characterized by a C4HC3-type motif, and adopts a dimetal(zinc)-bound α+β fold. This fold is highly similar to that found in another class of zinc finger domains, which function in membrane recruitment of cytosolic proteins by binding to phosphatidylinositol 3-phosphate.

PH domain *abbr. for* pleckstrin homology domain.

Phe *symbol for* a residue of the *α*-amino acid L-phenylalanine (alternative to F).

phenazine methosulfate *abbr.*: PMS; *N*-methylphenazonium methosulfate; 5-methylphenazinium methyl sulfate; $[C_{13}H_{11}N_2]^+$ $[CH_3SO_4]^-$; an artificial electron carrier, $E^{o'} = +0.080$ V, useful in the study of redox enzyme systems.



phencyclidine 1-(1-phenylcyclohexyl)piperidine (*abbr.*: PCP); a potent psychotomimetic agent, known to drug users as angel dust, with analgesic and anesthetic actions. It acts as a ligand for the **sigma receptor** and is a blocker of the NMDA-receptor ionophore (*see* **glutamate receptor**). A controlled substance in the US Code of Federal Regulations.

phene any phenotypic character under genetic control.

phenelzine *β*-phenylethylhydrazine, (2-phenethyl)hydrazine; a nonselective monoamine oxidase inhibitor used as an antidepressant.

phenobarbital 5-ethyl-5-phenylbarbiturate; a major **barbiturate** drug.

phenocopy a nonhereditary modification of the phenotype of an organism, induced by nutritional or other environmental factors, that mimics a phenotype controlled by a specific gene.

phenol 1 *the common and trivial name for* hydroxybenzene, C_6H_5OH. 2 any compound containing one or more hydroxyl groups directly attached to an aromatic carbocycle. Unlike hydroxyalkyl compounds, phenols are weakly acidic.

phenolase 1 *an alternative name for* **catechol oxidase** (EC 1.10.3.1). 2 *an alternative name for* **monophenol monooxidase** (EC 1.14.18.1). 3 more loosely, any enzyme of the sub-subclass 1.10.3. Such enzymes cause browning of damaged plant tissues when they come into contact with flavonoids, as **catechins** are converted into polymerized brown products.

phenol-chloroform extraction a method for the efficient extraction of nucleic acids free from contaminating proteins. Phenol saturated with Tris-EDTA buffer is mixed with an equal volume of chloroform (or sometimes a 24:24:1 v/v/v mixture with isoamyl alcohol) and is shaken to form an emulsion with the solution containing nucleic acids. On phase separation the nucleic acids occupy the upper aqueous phase and denatured protein occurs at the interface.

phenolic 1 of, containing, derived from, or having the character of phenol or a phenol. 2 describing a hydroxyl group linked to an aromatic carbocycle.

phenol 2-monooxygenase *see* **monooxygenase**.

phenolphthalein an indicator dye that changes from colourless to red over the pH range 8.3–10.0. The *β*-D-glucuronide (λ_{max} = 420 nm) is used as a substrate for the assay of *β*-glucuronidase, hydrolysis leading to release of phenolphthalein, which can be measured in alkaline solution by its red colour (λ_{max} = 550 nm).



Phenol Red an indicator dye that changes colour from yellow to red over the pH range 6.8–8.4.



phenome the whole of the phenotypic characteristics of an organism. *Compare* **genome**. —**phenomic** *adj.*

phenomenology a branch of a science dealing with the description and classification of natural phenomena rather than with their explanation or cause. —**phenomenological** *adj.*

phenon any set of organisms grouped together by the methods of numerical taxonomy.

phenothiazine 1 a chemical structure that forms the basis, by *N*-substitution, of a group of **neuroleptics**, such as **chlorpromazine**. 2 any of the group of drugs based on the phenothiazine structure. The neuroleptic effects are those now most commonly exploited, but antiemetic, antihistamine and anthelmintic effects have also been of use.

phenotype 1 the totality of the observable functional and structural characteristics of an organism as determined by interaction of the genotype of the organism with the environment in which it exists. 2 any particular characteristic or set of characteristics of an organism so determined. 3 a group of organisms exhibiting the same set of such characteristics. *Compare* **genotype**. —**phenotypic** *adj.*

phenoxide 1 the anion, $C_6H_5O^-$, derived from phenol by the loss of a proton. 2 any salt of phenol.

phenoxy *symbol*: OPh *or* PhO; the C_6H_5O– group, derived from phenol by the loss of a hydrogen atom.

phentolamine an antagonist for both α_1 and α_2 adrenoceptors. It is an antihypertensive agent and vasodilator.

phenyl *symbol*: Ph; the aromatic carbocyclic group C_6H_5–, derived from benzene.

phenylacetaldehyde dehydrogenase EC 1.2.1.39; an enzyme of the pathway of phenylalanine degradation. It catalyses the oxidation by NAD^+ of phenylacetaldehyde to phenylacetate with formation of NADH.

phenylalaninate 1 phenylalanine anion; the anion, C_6H_5–CH_2–$CH(NH_2)$–COO^-, derived from **phenylalanine**. 2 any salt containing phenylalanine anion. 3 any ester of phenylalanine.



phentolamine

phenylalanine *the trivial name for β*-phenylalanine; *α*-aminohydrocinnamic acid; *α*-amino-*β*-phenylpropionic acid; 2-amino-3-phenylpropanoic acid; C_6H_5–CH_2–$CH(NH_2)$–COOH; a chiral *α*-amino acid. L-phenylalanine (*symbol*: F *or* Phe), (*S*)-2-amino-3-phenylpropanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: UUC or UUU. In mammals, it is an essential dietary amino acid, and is both glucogenic and ketogenic. Residues of D-phenylalanine (*symbol*: D-Phe *or* DPhe), (*R*)-2-amino-3-phenylpropanoic acid, occur in a number of peptide antibiotics, e.g. bacitracin A, gramicidin S, polymyxins B_1 and B_2, and tyrocidins A, B, and C.



L-phenylalanine

L-phenylalanine ammonia-lyase EC 4.3.1.5; *systematic name*: L-phenylalanine ammonia-lyase; an enzyme, widely distributed in plants, that deaminates L-phenylalanine to *trans*-cinnamic acid, which is rapidly converted to **lignin**, a major polymer of the plant cell wall.

phenylalanine hydroxylase *see* **phenylalanine 4-monooxygenase**.

phenylalanine 4-monooxygenase EC 1.14.16.1; *systematic name*: L-phenylalanine,tetrahydrobiopterin:oxygen oxidoreductase (4-hydroxylating); *other names*: phenylalanine 4-hydroxylase; phenylalaninase. An iron-containing enzyme that catalyses a reaction between L-phenylalanine, tetrahydrobiopterin, and dioxygen to form L-tyrosine, dihydrobiopterin, and H_2O. It is thus of major importance for the provision of L-tyrosine. Over 400 mutations result in enzyme deficiency in humans and consequent **phenylketonuria**.

phenylalaninium phenylalanine cation; the cation, C_6H_5–CH_2–$CH(NH_3^+)$–COOH, derived from phenylalanine.

phenylalanino the alkylamino group, C_6H_5–CH_2–CH(COOH)–NH–, derived from phenylalanine.

phenylalanyl the acyl group, C_6H_5–CH_2–$CH(NH_2)$–CO–, derived from phenylalanine.

phenylalanyl chain *(sometimes)* the **B chain** of any of those species of insulin whose amino-acid sequences were the first to be determined. It was so called by virtue of the N-terminal phenylalanine residue occurring in those instances.

phenylephrine (*R*)-(–)-1-(3-hydroxyphenyl)-2-methylaminoethanol; a highly selective α_1 adrenergic agonist. It is a vasoconstrictor, used in treating hypotension; it also acts as a decongestant.



R-(–)-enantiomer

R-(–)-enantiomer

phenylethanolamine *N*-methyl transferase *abbr*.: PNMT; EC 2.1.1.28; an enzyme catalysing *N*-methylation of norepinephrine in the synthesis of epinephrine. *s*-adenosyl methionine is the methyl donor.

phenylhydrazone any condensation product of the type R R″C=N-NHC$_6$H$_5$, formed between carbonyl compounds of the general formula R R″C=O and phenylhydrazine. Phenylhydrazones, in particular 2,4-dinitrophenylhydrazones, are useful in the characterization of aldehydes and ketones. *See also* **phenylosazone**.

phenylketonuria (*abbr*.: PKU) *or* **phenylpyruvic oligophrenia** an autosomal recessive inherited disorder of phenylalanine metabolism characterized by the presence of phenylpyruvate in the urine and excessively high levels of phenylalanine and its metabolites in the blood and tissues. It can be treated by restricting the amount of phenylalanine in the diet. If untreated in young children, severe mental retardation occurs. This form, **classical phenylketonuria**, is due to the absence or deficiency of **phenylalanine 4-monooxygenase**, an enzyme that uses tetrahydrobiopterin as second donor. Hyperphenylalaninemia also results from deficiency in dihydropteridine reductase (EC 1.6.99.7) or phenylalanine(histidine) aminotransferase (EC 2.6.1.58).

phenylmethylsulfonyl fluoride *or* **phenylmethanesulfonyl fluoride** *abbr*.: PMSF; an inhibitor of serine proteases; it is highly toxic, but less so than diisopropylphosphofluoridate. PMSF is insoluble and unstable in aqueous solutions, so is usually dissolved in dioxan. It inhibits trypsin and chymotrypsin irreversibly, sulfonylating the active-site histidine, but does not inhibit cholinesterase. *See also* **aminoethylbenzenesulfonyl fluoride**.



phenylosazone any 1,2-bis(phenylhydrazone); i.e., any condensation product of the type C$_6$H$_5$NH–N=CR′–CR′=N–NH–C$_6$H$_5$ formed between an α-dicarbonyl compound of the general formula R′–CO–CO–R′ and phenylhydrazine; α-hydroxy- and α-aminocarbonyl compounds will also form phenylosazones through oxidation of the corresponding [mono]phenylhydrazones initially formed. Phenylosazones, in particular 2,4-dinitrophenylosazones, are useful in the characterization of aldehydes and ketones, especially monosaccharides. *See also* **phenylhydrazone**.

phenylpropanoid any substance in plants derived from phenylpropane units variously linked and interlinked to form polymers of high molecular mass, especially **lignins**.

phenylpyruvate decarboxylase EC 4.1.1.43; an enzyme of the pathway of phenylalanine degradation. It catalyses the formation of phenylacetaldehyde from phenylpyruvate with release of CO$_2$.

phenylpyruvic oligophrenia *an alternative name for* **phenylketonuria**.

pH 5 enzyme a protein fraction from rat liver, soluble at pH 7 and isolated by precipitation at pH 5, that was used in early studies of protein biosynthesis *in vitro*. It is now known to be a mixture of amino acid–tRNA ligases.

pheo+ *or (esp. Brit.)* **phaeo+** *comb. form* denoting dark-coloured.

pheochromocytoma *or (esp. Brit.)* **phaeochromocytoma** *or* **chromaffinoma** a tumour of tissues derived from embryological neuroectoderm, often of the adrenal medulla. It is characterized by its ability to synthesize and secrete catecholamines, often in excessive amounts. The tumour cells commonly show a strong **chromaffin** (*or* pheochrome) reaction.

pheofarnesin *or (esp. Brit.)* **phaeofarnesin** any pigment derived by demetallation of a chlorophyll in which the 17-propionic-acid group is esterified with farnesol.

pheomelanin *or (esp. Brit.)* **phaeomelanin** a red and/or yellow pigment produced in mammalian melanocytes from tyrosine and cysteine. It is formed as an alternative to eumelanin by switching of the melanogenesis pathway at the dopaquinone stage. How the switch operates is unclear.

pheophorbide *or (esp. Brit.)* **phaeophorbide** any pigment derived by removal of metal from a chlorophyll in which the 17-acrylic-acid or 17-propionic-acid group is unesterified or has been de-esterified.

pheophytin *or (esp. Brit.)* **phaeophytin** any pigment derived by removal of metal from a chlorophyll in which the 17-propionic-acid group is esterified with phytol.

pheromone a substance, or characteristic mixture of substances, that is secreted and released by an organism and detected by a second organism of the same or a closely related species, in which it causes a specific reaction, such as a definite behavioural reaction or a developmental process; a type of **ectocrine**. The mating pheromones of fungi and insects are examples. *Compare* **allomone**, **kairomone**.

pheromone-binding protein any of a group of insect proteins that bind to, and thus solubilize, **pheromones**, which are typically hydrophobic.

pheromone receptor a fungal transmembrane G protein-coupled receptor.

PHEX *abbr. for* phosphate-regulating gene with homologies to endopeptidases on the X chromosome; a putative endopeptidase that is mutated in X-linked hypophosphatemia. *See* **fibroblast growth factor**-23.

PHHI *see* **sulfonylurea receptor**.

phi *symbol*: φ *or* ϕ (lower case) *or* Φ (upper case); the twenty-first letter of the Greek alphabet. For uses *see* **Appendix A**.

PHI *or* **PHI-27** *abbr. for* peptide HI.

PHI-BLAST *abbr. for* pattern hit initiated-BLAST; *see* **database-search program**.

Philadelphia chromosome (Ph^1) a specific chromosomal abnormality in the blood cells of patients with chronic myeloid leukemia. It usually results from a fusion of ***bcr*** on chromosome 22 with c-*myc* (*see* ***MYC***) on chromosome 9 leading to expression of the latter. The Philadelphia chromosome is a very small chromosome consisting of the short arm and a small piece of the long arm of chromosome 22 fused to a short piece from the end of the long arm of chromosome 9 (the modified chromosome 9 that results being called 9q$^+$). It is named after the city in which it was first recorded. *See also* ***abl***.

philosin a pore-forming toxin with approximately 100 amino acid residues, produced by the ant *Myrmecia pilosula*. It is classified in the TC system under number 1.C.51.

pH indicator *see* **indicator** (def. 3), **mixed indicator**.

phi X174 *or* **φX174** a single-stranded DNA bacteriophage that infects *Escherichia coli*. It contains 5386 nt and was the first DNA to be sequenced, by British biochemist Frederick Sanger (1918–) in 1976.

phloem the main food-conducting tissue of plants, via which nutrients and photosynthate are conveyed between different sites. Phloem comprises two types of cells: sieve-tube elements, which are joined end-to-end to form sieve tubes; and adjacent companion cells. *Compare* **xylem**.

phloretin 3-(4-hydroxyphenyl)-1-(2,4,6-trihydroxyphenyl)-1-propanone; the aglycon of **phlorizin**, with which it shares many biochemical and pharmacological properties.



phlorizin *or* **phlorhizin** *or* **phloridzin** *or* **phlorrhizin** phloretin-2′-β-glucoside; a dihydrochalcone glucoside occurring in all parts of the apple tree except the mature fruit. It inhibits intestinal and renal glucose–Na$^+$ cotransporters, the mediated transport of glucose into erythrocytes and hepatocytes, the glucose 6-phosphate transporter in hepatocytes, and photophosphorylation. It is used experimentally to produce glucosuria.

phloroglucinol 1,3,5-trihydroxybenzene; 1,3,5-benzenetriol; a compound that is useful as a reagent for the qualitative detection of pentoses and pentosans; when these are boiled with a solution of phloroglucinol in hydrochloric acid, a cherry-red colour is produced. Galactose also reacts in this way.

phlorrhizin *a variant spelling of* **phlorizin**.

pH meter any instrument for determining pH potentiometrically, usually with a glass electrode plus a calomel reference electrode, or with a combination electrode.

phoA the gene for *E. coli* alkaline phosphatase. The signal sequence of PhoA may be incorporated in expression vectors used for secretion of foreign proteins into the periplasmic space of *E. coli*.

phorbol a complex tetracyclic compound, $C_{20}H_{28}O_6$, based on a cyclopropabenzazulene skeleton. Various **phorbol esters** occur in croton oil (from *Croton tiglium*, of the family Euphorbiaceae, hence the name) and act as potent **cocarcinogens**.



phorbol ester any esterified form of **phorbol**. Several phorbol esters possess activity as tumour promoters and activate the mechanisms associated with cell growth. These actions have been widely attributed to the activation of protein kinase C, probably by substituting for diacylglycerol. A much-studied ester is phorbol 12-myristate 13-acetate (PMA; *or* 12-*O*-tetradecanoyl-phorbol-13-acetate, TPA); other active esters include phorbol 12,13-dibutyrate (PDBu) and phorbol 12,13-didecanoate (PDD). Activity depends on the *β*-configuration of the hydroxyl at C-4. Several 4*α*-phorbol esters have been utilized in control studies.

+phore *noun suffix* denoting something, especially a chemical substance or group, that carries or produces; e.g. ionophore, chromophore.

+phoresis *noun suffix* denoting carriage of molecular entities by some agency; e.g. electrophoresis, ionophoresis.

phosducin a protein that binds the β and γ subunits of **transducin** in outer and inner segments of retinal rod cells. Light-induced changes in cyclic nucleotide levels modulate the phosphorylation of phosducin by cyclic AMP kinase.

+phosph+ *a variant form of* **+phospho+** (sometimes before a vowel).

phosphacan a chondroitin sulfate proteoglycan of brain that interacts with neurons and neural cell-adhesion molecules. It is an extracellular variant of a receptor-type protein tyrosine phosphatase.

phosphagen any of a group of guanidine phosphates that occur in muscle, and can be used to regenerate ATP from ADP during muscular contraction by a reaction catalysed by **creatine kinase**, or by an analogous enzyme of sub-subclass EC 2.7.3. Included in the group are phosphoagmatine (*see* **agmatine**), **phosphoarginine**, **phosphocreatine**, phosphoglycocyamine (*see* **glycocyamine**), phospholombricine (*see* **lombricine**), phosphooctopine (*see* **octopine**), and phosphotaurocyamine (*see* **taurocyamine**).

phosphataemia *a variant spelling (esp. Brit.) of* **phosphatemia**.

phosphatase *or* **phosphomonoesterase** any phosphoric monoester hydrolase of sub-subclass EC 3.1.3. Some phosphatases are very specific while others are relatively unspecific. *See also* **acid phosphatase**, **acylphosphatase**, **alkaline phosphatase**, **fructose-bisphosphatase**, **glucose-1-phosphatase**, **glucose-6-phosphatase**, **inorganic pyrophosphatase, protein phosphatase**.

phosphatased *a jargon term* indicating dephosphorylated by treatment with a **phosphatase**.

phosphatase inhibitor protein an inhibitor of protein phosphatase 1 (*see* **protein phosphatase**) involved in the regulation of glycolysis; it is itself a phosphoprotein.

phosphate **1** the trivalent anion, PO_4^{3-}, derived from phosphoric acid; orthophosphoric acid; tetraoxophosphoric(v) acid; $PO(OH)_3$. **2** any mixture of [ortho]phosphoric acid and its anions. Once widely used in the laboratory as a buffer in the physiological range of pH values; pK_{a2} (37°C, 0.05 mol L^{-1}) = 6.84. **3** any (partial or full) salt or ester of [ortho]phosphoric acid. Phosphate salts and esters play key roles in the structure and function of all forms of life. **4** any anion or salt of a mixed anhydride of [ortho]phosphoric acid with another acid; e.g. acetyl phosphate (i.e. acetic phosphoric anhydride). **5** the univalent group $-O-P(O)(OH)_2$ (irrespective of its state of ionization). *See also* **diphosphate**, **inorganic phosphate**, **metaphosphate**, **pyrophosphate**, **triphosphate**.

phosphate bond **1** an ester linkage in a phospho[mono]ester, phosphodiester, or phosphotriester. **2** an anhydride linkage in a phosphoric anhydride. **3** the connecting phosphoric residue in a phosphodiester.

phosphate bond energy *a term formerly and incorrectly used for* the **bond energy** (def. 2) of a **phosphate bond** (def. 1, 2).

phosphatemia *or (esp. Brit.)* **phosphataemia** the level of **phosphate** (def. 2) in the blood; in human plasma its normal range is 0.8–1.4 mmol L^{-1}. The level is regulated by **calcitriol**, which stimulates absorption of dietary phosphate as well as calcium, and by **parathyrin**, which decreases phosphate resorption by the kidney. Calcitriol also stimulates bone resorption, which tends to lower the plasma phosphate level, but in states of hypervitaminosis D the effect on the gut predominates and the plasma level is increased. *See also* **hyperphosphatemia**, **hypophosphatemia**.

phosphate potential the concentration of ATP in any system divided by the product of the concentrations of ADP and inorganic phosphate in that system. *Compare* **adenylate energy charge**.

phosphatidal *a former term for* **plasmenyl**.

phosphatidate any anion, salt, or ester of a **phosphatidic acid**.

phosphatidate cytidylyltransferase EC 2.7.7.41; *systematic name*: CTP:phosphatidate cytidylyl transferase; *other names*: CDP-diglyceride synthetase; CDPdiglyceride pyrophosphorylase. An enzyme that catalyses a reaction between CTP and phosphatidate to form pyrophosphate and CDPdiacylglycerol. It is an integral membrane protein of the endoplasmic reticulum; it forms the intermediate involved in the synthesis of, e.g., phosphatidylinositol, by reaction with inositol, or phosphatidylserine, by reaction with serine.

phosphatidate phosphatase EC 3.1.3.4; *systematic name*: 3-*sn*-phosphatidate phosphohydrolase; an enzyme that removes phosphate from phosphatidic acid to yield an *sn*-1,2-diacylglycerol.

phosphatide *an old term, no longer recommended for* **glycerophospholipid**.

phosphatidic acid any derivative of glycerol phosphate in which both the remaining hydroxyl groups of the glycerol moiety are esterified with fatty acids; the commonest are derivatives of *sn*-glycerol 3-phosphate.

phosphatidyl *symbol*: Ptd; an acyl group derived from a **phosphatidic acid**.

phosphatidylcholine *abbr.*: PC; any glycerophospholipid in which a phosphatidyl group is esterified to the hydroxyl group of **choline**. Phosphatidylcholines are important constituents of cell membranes and lipoproteins.

phosphatidylcholine desaturase EC 1.3.1.35; *other names*: oleate desaturase; linoleate synthase; an enzyme in plants that catalyses the reaction:

1-acyl-2-oleoyl-*sn*-glycero-3-phosphocholine + NAD^+ =
1-acyl-2-linoleoyl-*sn*-glycero-3-phosphocholine + NADH.

phosphatidylcholine–dolichol *O*-acyltransferase *see* **lecithin–cholesterol acyl transferase**.

phosphatidylcholine–sterol *O*-acyltransferase EC 2.3.1.43; *other names*: lecithin–cholesterol acyltransferase (*abbr.*: LCAT); phospholipid–cholesterol acyltransferase; a plasma enzyme that catalyses the transfer of a fatty-acyl group from phosphatidylcholine to a sterol to form a sterol ester and 1-acylglycerophosphocholine. In mammals it is important in plasma lipoprotein metabolism, particularly in esterifying cholesterol, which is then transferred to very-low-density lipoprotein as cholesteryl ester. *Compare* **sterol *O*-acyltransferase**.

phosphatidylethanolamine *abbr.*: PE; any glycerophospholipid in which a phosphatidyl group is esterified to the hydroxyl group of **ethanolamine**. Phosphatidylethanolamines are important constituents of cell membranes.

phosphatidylinositol *abbr*.: PI; *symbol*: PtdIns; 1-(3-*sn*-phosphatidyl)-1d-*myo*-inositol; *the recommended name for* any glycerophospholipid in which its *sn*-glycerol 3-phosphate residue is esterified to the 1-hydroxyl group of 1d-*myo*-inositol. The older term **phosphoinositide** is now used as a generic term for any inositol-containing glycerophospholipid. The corresponding names for the monophosphorylated and diphosphorylated derivatives of phosphatidylinositol are **phosphatidylinositol 4-phosphate** and **phosphatidylinositol 4,5-bisphosphate**, respectively. The older names diphosphoinositide and triphosphoinositide for these derivatives are no longer used.

phosphatidylinositol 4,5-bisphosphate *or (formerly)* **triphosphoinositide** *abbr*.: PIP$_2$ *or* PI-4,5-P$_2$; *symbol*: PtdIns(4,5)P_2 *or* PtdIns-4,5-P_2; 1-(3-*sn*-phosphatidyl)-1d-*myo*-inositol 4,5-bisphosphate; any glycerophospholipid in which a phosphatidyl group is esterified to the 1-hydroxyl group of 1d-*myo*-inositol 4,5-bisphosphate.

1-phosphatidylinositol-4,5-bisphosphate phosphodiesterase *see* **phospholipase**.

phosphatidylinositol cycle *or (formerly)* **phosphoinositide cycle** a metabolic cycle that mediates the actions of various hormones and other effectors at the membranes of mammalian cells. Binding of an effector to its specific receptor at the membrane causes a G-protein-coupled stimulation of a phospholipase C, called 1-phosphatidylinositol-4,5-bisphosphate phosphodiesterase. This causes hydrolysis of phosphatidylinositol 4,5-bisphosphate, I, to produce the two intracellular messengers inositol 1,4,5-trisphosphate, II, which causes release of calcium ions from intracellular stores, and *sn*-1,2-diacylglycerol, III, which activates protein kinase C. III is then converted via phosphatidate (under the action of **diacylglycerolkinase** and **phosphatidate cytidylyltransferase**) to **CDPdiacylglycerol**, IV, while II is converted via inositol bisphosphate and inositol monophosphate to inositol. Inositol and IV then react together (enzyme is **CDPdiacylglycerol-inositol 3-phosphatidyltransferase**) to form phosphatidylinositol, from which I is regenerated by stepwise phosphorylation by specific kinases to complete the cycle. Alternatively, II may be converted to another messenger, inositol 1,3,4,5-tetrakisphosphate, V, which may be implicated in the influx of extracellular calcium ions; V is then degraded to inositol via inositol 1,3,4-trisphosphate, which is inactive.

phosphatidylinositolglycan the compound in which phosphatidylinositol is linked (6-1*α*) to the core glycan GlcN4-1*α*Man6-1*α*Man2-1*α*Man6-P-ethanolamine. Other groups may be attached to the core glycan. It forms the membrane anchor for **PIG-tailed proteins**, in which the protein's C-terminus forms an amide linkage with the phosphoethanolamine moiety. *See* **paroxysmal nocturnal hemoglobinuria**.

phosphatidylinositol glycan protein *abbr*.: PIG protein; *N*-acetylglucosaminyl-phosphatidylinositol biosynthetic protein; a protein required for synthesis of *N*-acetylglucosaminylphosphatidylinositol, the very early intermediate in the biosynthesis of the **GPI anchor**. Another protein required for this synthesis is PIG-F.

1-phosphatidylinositol 3-kinase EC 2.7.1.137; *systematic name*: ATP:1-phosphatidyl-1d-*myo*-inositol 3-phosphotransferase. An enzyme that catalyses the phosphorylation by ATp of 1-phosphatidyl-1d-*myo*-inositol to form 1-phosphatidyl-1d-*myo*-inositol 3-phosphate with release of ADP. It forms part of the complex that associates on activation of certain growth factor (e.g. PDGF) receptors, binding via SH2 domains (*see* **SH domain**). The molecule consists of a catalytic subunit (p110) and a regulatory subunit (p85: two forms, α and β, in mammals). p85 mediates association of p110 to the plasma membrane.

1-phosphatidylinositol 4-kinase EC 2.7.1.67; an enzyme involved in the biosynthesis of membrane **phosphoinositides**. It catalyses the phosphorylation by ATP of 1-phosphatidyl-1d-*myo*-inositol to form 1-phosphatidyl-1d-*myo*-inositol 4-phosphate with release of ADP.

phosphatidylinositol-3-phosphatase EC 3.1.3.64; an enzyme that catalyses the hydrolysis of the 3-phosphate from phosphatidylinositol-3-phosphate, forming phosphatidylinositol and orthophosphate.

phosphatidylinositol 4-phosphate *or (formerly)* **diphosphoinositide** *abbr*.: PIP *or* PI 4-P; *symbol*: PtdIns4*P* *or* PtdIns-4-*P*; 1-(3-*sn*-phosphatidyl)-1d-*myo*-inositol 4-phosphate; any glycerophospholipid in which a phosphatidyl group is esterified to the 1-hydroxyl group of 1d-*myo*-inositol 4-phosphate.

1-phosphatidylinositol-4-phosphate kinase EC 2.7.1.68; *other name*: diphosphoinositide kinase; an enzyme of the pathway for the biosynthesis of membrane **phosphoinositides**. It catalyses the phosphorylation by ATP of 1-phosphatidyl-1d-*myo*-inositol 4-phosphate to form 1-phosphatidyl-1d-*myo*-inositol 4,5-bisphosphate with release of ADP.

1-phosphatidylinositol phosphodiesterase *see* **phospholipase**.

phosphatidylinositol synthase *see* **CDP-diacylglycerol–inositol 3-phosphatidyltransferase**.

phosphatidylserine any glycerophospholipid in which a phosphatidyl group is esterified to the hydroxyl group of L-serine. Phosphatidylserines are important constituents of cell membranes.

phosphatidylserine decarboxylase EC 4.1.1.65; an enzyme that converts phosphatidylserine to phosphatidylethanolamine, of major importance in the synthesis of that phospholipid. It consists of an α and β chain, formed by cleavage of a proenzyme.

phosphatidylserine synthase *an alternative name for* **CDPdiacylglycerol-serine *O*-phosphatidyltransferase**.

phosphatonin a heat-labile, trypsin-sensitive factor that is presumed to be secreted by some tumours and to increase phosphaturia and produce phosphate wasting.

phosphinothricin *abbr*.: PPT; CH$_3$PO$_2$CH$_2$CH$_2$CHNH$_2$COOH; a glutamate analogue herbicide that is relatively nontoxic for animals.

phosphite **1** any anionic form of phosphorous acid; trioxophosphoric(III) acid; P(OH)$_3$. **2** any mixture of phosphorous acid and its ionized forms. **3** any (partial or full) salt or ester of phosphorous acid.

phosphite-triester method a method for the chemical synthesis of oligonucleotides in which a suitably protected phosphite diester of general formula Nuc-3′–O–P(OR)X, where R is a methyl or another alkyl group, X is a reactive group such as chloro, dimethylamino, or morpholino, and Nuc is a residue of an appropriate nucleoside, is first condensed with the 5′-hydroxyl of a protected nucleoside (usually anchored through its 3′-hydroxyl to an insoluble support) to form a phosphite triester. Sequential addition of further nucleoside units is then carried out in the same way, the phosphite triester formed at each stage being oxidized to the corresponding phosphate triester before the next cycle of reactions. Protecting groups are removed by hydrolysis at the completion of the synthesis.

+phospho+ *or (sometimes before a vowel)* **+phosph+** *(in chemical nomenclature) prefix or infix* denoting a phosphoric residue linked to one, two, or three heteroatoms in an organic compound. *See also* **phosphono+**.

phosphoacetylglucosamine mutase EC 5.4.2.3; *systematic name*: *N*-acetyl-D-glucosamine 1,6-phosphomutase; *other name*: acetylglucosamine phosphomutase. An enzyme that catalyses the reaction:

N-acetyl-D-glucosamine 1-phosphate =
N-acetyl-D-glucosamine 6-phosphate.

It participates in the formation of UDP-*N*-acetylglucosamine: glucosamine 6-phosphate → *N*-acetylglucosamine-6-phosphate →*N*-acetylglucosamine-1-phosphate, thence by reaction with UTP to UDP-*N*-acetylglucosamine + pyrophosphate, thence also to sialic acid.

3′-phosphoadenosine 5′-phosphosulfate *an alternative recommended name for* **adenosine 3′-phosphate 5′-phosphosulfate**.

3′-phosphoadenylyl sulfate *symbol*: *P*Ado*PS*; *abbr*.: PAPS; *alternative recommended names for* active sulfate; adenosine 3′-phosphate 5′-phosphosulfate; adenosine 3′-phosphate 5′-*P*-phosphatosulfate; 3′-phospho-5′-adenylic sulfuric monoanhydride; a naturally occuring mixed anhydride. It is synthesized from **adenosine 5′-phosphosulfate** by phosphorylation with ATP through the action of adenylylsulfate kinase (EC 2.7.1.25). It is an intermediate in the formation of a variety of sulfo compounds in biological systems. For example, in animals it is involved in sulfate transfer in the formation of sulfatides and in the synthesis of chondroitin sulfate and other sulfated polysaccharides, while in bacteria, by a process analogous to that involving adenosine 5′-phosphosulfate. In plants, it is reduced by phosphoadenylyl-sulfate reductase (thioredoxin), EC 1.8.4.8 to yield adenosine 3′,5′ bis(phosphate) and sulfite. The latter can then undergo further reduction by sulfite reductase to sulfide, from which cysteine may be synthesized.

phosphoamino acid any phosphorylated amino acid. The term often refers to *O*-phosphate esters of residues in proteins, e.g. those of serine, threonine, or tyrosine, that are released as phosphoamino acids on hydrolysis. Phosphohistidine can be formed as part of an enzyme mechanism (e.g., **phosphoglycerate mutase**), and phosphohomoserine is an intermediate in threonine biosynthesis. The guanidine group can also be phosphorylated to form a phosphono derivative (*see* **phosphagen**).

phosphoarginine *the recommended trivial name for* **N^{ω}-phosphonoarginine**; the commonest **phosphagen** in invertebrates. The older name, arginine phosphate, is not recommended.



phosphocreatine *abbr*.: PC; *the recommended trivial name for* **N^{ω}-phosphonocreatine**; the commonest **phosphagen** in vertebrates. The older name, creatine phosphate, is not recommended.



phosphodiester any diester of phosphoric acid; i.e. any phosphoric ester containing the bridging group –PO(OH)– between two oxygen atoms in other groups (which may be the same or different) or at different positions in the same group. Examples include cyclic nucleotides, glycerophospholipids, and nucleic acids.

phosphodiesterase any esterase that catalyses the hydrolysis of either (but not both) of the ester linkages in a phosphodiester, each linkage being hydrolysed only by an enzyme specific for that linkage. Such enzymes are classified in various sub-subclasses within the subclass EC 3.1, hydrolases, especially in the sub-subclass EC 3.1.4, phosphoric diester hydrolases. The term is often applied to **nucleases** without sugar specificity. *See also* **cyclic AMP phosphodiesterase**, **phosphodiesterase I**, **phospholipase** C. —**phosphodiesteratic** *adj.*

phosphodiesterase I *the recommended name for* an enzyme, EC 3.1.4.1, that catalyses the hydrolytic removal of 5′-nucleotides successively from the (nonphosphorylated) 3′ end of an oligonucleotide; *other name*: 5′-exonuclease.

phosphodiesterase II an enzyme, *now named* **spleen exonuclease** (EC 3.1.16.1; previously EC 3.1.4.18), that catalyses the hydrolytic removal of 3′-nucleotides successively from the (nonphosphorylated) 5′ end of a (preferably single-stranded) ribonucleic or deoxyribonucleic acid; *other names*: 3′-exonuclease; spleen phosphodiesterase.

phosphodiester method a method for the chemical synthesis of oligonucleotides in which, essentially, a 5′-phosphate of an appropriate [mono]nucleotide, after suitable protection of other functional groups, is condensed with the 3′-hydroxyl of a protected nucleoside, [mono]nucleotide, or previously formed oligonucleotide, using dicyclohexylcarbodiimide or an arylsulfonyl chloride as a coupling agent. The reaction sequence is then repeated with another nucleotide 5′-phosphate. This method is being superseded by the **phosphite-triester method** and **phosphotriester method**.

phospho*enol*pyruvate *abbr*.: PEP *or P-enol*pyruvate; 2-hydroxy-2-propenoate phosphate (ester); 2-(phosphonooxy)-2-propenoate; the phosphate ester formed from the hydroxy group of the enol tautomer of pyruvate. Its hydrolysis to pyruvate gives a particularly large negative change in standard free energy ($-\Delta G^{o} = 62$ kJ mol^{-1} at pH 7). It is a key intermediate in glycolysis and gluconeogenesis, and in the biosynthesis of aromatic amino acids.



phospho*enol*pyruvate carboxykinase *abbr*.: PEPCK; any enzyme that catalyses the reaction:

$$X–P + \text{oxaloacetate} = X + \text{phospho}\textit{enol}\text{pyruvate} + CO_2,$$

where X–P, depending on source, can be GTP or ITP (in EC 4.1.1.32), ATP (in EC 4.1.1.49), or pyrophosphate (in EC 4.1.1.38). (1) **Phospho***enol*pyruvate carboxykinase (GTP), EC 4.1.1.32; *systematic name*: GTP:oxaloacetate carboxy-lyase (transphosphorylating); *other names*: phospho*enol*pyruvate carboxylase; phosphopyruvate carboxylase; the rate-limiting gluconeogenic enzyme in eukaryotes. It has different forms in cytosol and mitochondria. It catalyses a reaction between GTP and oxaloacetate to form GDP, phospho*enol*pyruvate, and CO_2. (2) **Phospho***enol*pyruvate carboxykinase (ATP), EC 4.1.1.49; *systematic name*: ATP:oxaloacetate carboxy-lyase (transphosphorylating); *other names*: phospho*enol*pyruvate carboxylase; phosphopyruvate carboxylase (ATP); it catalyses a similar reaction to (1) but with ATP/ADP not GTP/GDP. In many bacteria it is a Ca^{2+}-regulated rate-limiting gluconeogenic enzyme. *See also* **gluconeogenesis**.

phospho*enol*pyruvate carboxylase EC 4.1.1.31; *systematic name*: orthophosphate:oxaloacetate carboxy-lyase (phosphorylating); an enzyme that catalyses a reaction between orthophosphate and oxaloacetate to form phospho*enol*pyruvate, H_2O, and CO_2. It is an allosteric homotetramer associated with the **tricarboxylic-acid cycle** in plants; effectors include fatty acids, acetyl-CoA, and fructose 1,6-bisphosphate. It forms oxaloacetate for metabolism by this cycle in plants. system system

phospho*enol*pyruvate-dependent sugar phosphotransferase system *abbr*.: PTS; a system for bacterial sugar transport; it comprises two main components: **protein-N^{p}-phosphohistidine–sugar phosphotransferase** and **phospho*enol*pyruvate–protein phosphotransferase**. It also functions also as a chemoreceptor monitoring the environment for changes in sugar concentration.

phospho*enol*pyruvate mutase EC 5.4.2.9; *systematic name*: phospho*enol*pyruvate 2,3-phosphonomutase; *other name*: phospho*enol*pyruvate phosphomutase. An enzyme that catalyses the conversion of phospho*enol*pyruvate to 3-phosphonopyruvate.

phospho*enol*pyruvate–protein phosphotransferase EC 2.7.3.9; *systematic name*: phospho*enol*pyruvate:protein-L-histidine N^{π}-phosphotransferase; *other name* enzyme I of the **phospho*enol*pyruvate-dependent sugar phosphotransferase system**; a soluble bacterial enzyme, part of a system for the transport of hexoses across the cell membrane, that catalyses the phosphorylation by phospho*enol*pyruvate of a low-M_r, heat-stable protein, **HPr**.

phosphoester any [mono]ester of phosphoric acid; i.e. any phosphoric ester containing the group $–PO(OH)_2$ linked to an oxygen atom in a single other group.

phosphofructokinase 1 *abbr*.: PFK; EC 2.7.1.11; *recommended name*: 6-phosphofructokinase; *other names*: phosphofructokinase 1; phosphohexokinase. An enzyme that catalyses the phosphorylation of D-fructose 6-phosphate to D-fructose 1,6-bisphosphate at the expense of ATP, CTP, ITP, or UTP.

Phosphofructokinase 1 is an allosteric homotetrameric enzyme of glycolysis. There are three genes for human subunits: M (muscle – 799 amino acids), L (liver – 799 amino acids), and P (platelet). Erythrocytes contain five isoenzymes. Mutations in the M or L gene cause the rare glycogen disease type VII (Tarui disease). *E. coli* has two entirely unrelated isoenzymes, I and II, presumably of independent evolution. **2** *or* **phosphofructokinase 2** EC 2.7.1.105; *recommended name*: 6-phosphofructo-2-kinase; an enzyme that catalyses the phosphorylation of D-fructose 6-phosphate to D-fructose 2,6-bisphosphate at the expense of ATP. Phosphofructokinase 2 is part of the same bifunctional protein as **fructose-2,6-bisphosphatase; phosphorylation** inhibits the kinase activity. **3** *or* **fructose-1-phosphate kinase** EC 2.7.1.56; *recommended name*: 1-phosphofructokinase; an enzyme that catalyses the phosphorylation of D-fructose 1-phosphate to D-fructose 1,6-bisphosphate at the expense of ATP, GTP, ITP, or UTP.

phosphoglucoisomerase *an alternative name for* **glucose-6-phosphate isomerase**.

phosphoglucomutase *abbr. (in clinical chemistry)*: PGT; EC 5.4.2.2; *systematic name*: α-D-glucose 1,6-phosphomutase; *other name*: glucose phosphomutase. A **phosphotransferase** enzyme that catalyses the interconversion of *α*-D-glucose 1-phosphate and *α*-D-glucose 6-phosphate; *α*-D-glucose 1,6-bisphosphate is an intermediate, formed by phosphoryl transfer from the enzyme. It links the metabolism of polysaccharides to glycolysis. There are three isoenzymes in humans.

phosphogluconate 6-phospho-D-gluconate; an intermediate in the **Entner–Doudoroff pathway** and in the **pentose phosphate pathway**. It is a product of the combined action of **glucose-6-phosphate dehydrogenase** and **6-phosphogluconolactonase**, and is a substrate for **phosphogluconate dehydrogenase (decarboxylating)**.



phosphogluconate dehydrogenase (decarboxylating) *abbr.*: 6PGD; EC 1.1.1.44; *systematic name*: 6-phospho-D-gluconate:NADP$^+$ 2-oxidoreductase (decarboxylating); *other names*: phosphogluconic acid dehydrogenase; 6-phosphogluconic dehydrogenase; 6-phosphogluconic carboxylase. An enzyme that catalyses a reaction between 6-phospho-D-gluconate and NADP$^+$ to form D-ribulose 5-phosphate, CO_2, and NADPH. It participates in the **pentose phosphate pathway**, and is significant in maintaining NADP$^+$ in the reduced state.

phosphogluconate (oxidative) pathway *an alternative name for* **pentose phosphate pathway**.

6-phosphogluconolactonase EC 3.1.1.31; *systematic name*: 6-phospho-D-glucono-1,5-lactone lactonohydrolase; an enzyme of the **pentose phosphate pathway** that catalyses the hydrolysis of 6-phosphogluconolactone to 6-phosphogluconic acid.

phosphoglycerate **1** 2-phospho-D-glycerate; D-glycerate 2-phosphate; (*R*)-2,3-dihydroxypropanoate 2-(dihydrogen phosphate). **2** 3-phospho-D-glycerate; D-glycerate 3-phosphate; (*R*)-2,3-dihydroxypropanoate 3-(dihydrogen phosphate). Both are important intermediates in glycolysis. 3-Phosphoglycerate is a precursor in serine biosynthesis. *Compare* **glycerophosphate**, **phosphoglyceride**. *See also* **phosphoglycerate mutase**.

phosphoglycerate dehydrogenase EC 1.1.1.95; *systematic name*: 3-phosphoglycerate:NAD$^+$ 2-oxidoreductase; an enzyme that converts 3-phospho-D-glycerate to 3-phosphohydroxypyruvate in the presence of NAD$^+$. It participates in the synthesis of serine from 3-phosphoglycerate.

phosphoglycerate kinase *abbr.*: PGK; EC 2.7.2.3; *systematic name*: ATP:3-phospho-D-glycerate 1-phosphotransferase; an enzyme that catalyses reaction:

1,3-bisphosphoglycerate + ADP = 3-phosphoglycerate +ATP.

The forward reaction is the first one to generate ATP during glycolysis; the reverse reaction participates in CO_2 assimilation during photosynthesis in chloroplasts. It exists in tissue-specific or (in protozoa, etc.) organelle-specific isoforms. Enzyme deficiency in humans results in chronic hemolytic anemia, neurological dysfunction, and myopathy.

phosphoglycerate mutase *abbr.*: PGAM; EC 5.4.2.1; *systematic name*: D-phosphoglycerate 2,3-phosphomutase; *other names*: phosphoglycerate phosphomutase; phosphoglyceromutase. An enzyme of the glycolytic and gluconeogenic pathways that catalyses the reaction:

2-phospho-D-glycerate = 3-phospho-D-glycerate

(the forward direction, as written, being the direction in which the enzyme functions in gluconeogenesis). A phosphotransferase enzyme for which 2,3-bisphospho-D-glycerate acts as a reaction primer. The active enzyme has a phosphoryl group active site (histidine is phosphorylated as part of the mechanism) and transfers phosphoryl to the substrate. *See also* **phosphohistidine**.

phosphoglycerate phosphomutase *another name for* **phosphoglycerate mutase**.

3-phospho-D-glyceric phosphoric monoanhydride *see* **3-phospho-D-glyceroyl phosphate**.

phosphoglyceride *another (less correct) name for* **glycerophospholipid**.

3-phospho-D-glyceroyl phosphate *abbr.*: D-glyceric-1,3-P_2; *one of the recommended names for* (*R*)-[2,3-dihydroxypropanoyl dihydrogen phosphate 3-(dihydrogen phosphate)], a key intermediate in the glycolytic pathway, commonly but incorrectly known as 1,3-diphosphoglycerate or 1,3-bisphosphoglycerate. *Alternative recommended names*: 3-phospho-D-glyceric phosphoric monoanhydride; (D-glyceroyl phosphate) 3-phosphate. This compound should be distinguished from **2,3-bisphospho-D-glycerate**.

phosphohexose isomerase *an alternative name for* **glucose-6-phosphate isomerase**.

phosphohistidine N^{π}-phosphohistidine; it is formed as a residue in certain proteins, being an intermediate in the **phosphoglycerate mutase** reaction and the **phospho*enol*pyruvatedependent sugar phosphotransferase system**.

phosphoinositide *another old term, no longer recommended, for* **phosphatidylinositol** but now much used to denote all phosphatidylinositol derivatives as a class.

phosphoinositide cycle *another term for* **phosphatidylinositol cycle**.

phosphoketolase EC 4.1.2.9; a thiamine diphosphate-protein of the phosphoketolase pathway that catalyses phosphorolysis of D-xylulose 5-phosphate and orthophosphate to acetyl phosphate and D-glyceraldehyde 3-phosphate.

phosphoketolase pathway any metabolic pathway, usually in a microorganism, that involves the enzyme **phosphoketolase**, e.g. in **heterolactic fermentation** or in the fermentation of glucose by *Bifidobacterium* spp.

phosphokinase *a former term for* **kinase**.

phospholamban a homopentameric sarcoplasmic reticulum membrane protein that regulates the calcium pump of cardiac, slow-twitch skeletal, and smooth muscle. It is phosphorylated by protein kinase A in response to β-adrenergic stimulation. The phosphorylated protein increases the rate of the sarcoplasmic reticulum Ca^{2+}-ATPase.

phospholemman a 72-residue cell-membrane protein that forms a chloride-selective ion channel. It is a substrate for both protein kinase C and cyclic AMP-dependent protein kinase. It is rapidly phosphorylated after β-adrenergic and α-adrenergic stimulation of the heart, and in response to insulin in muscle. It has a single transmembrane domain.

phospholipase any enzyme that is a lipase and that catalyses the hydrolysis of a glycerophospholipid. Phospholipases have been subdivided as follows.

Phospholipase A1 EC 3.1.1.32; *the recommended name for* any carboxylic ester hydrolase that removes the acyl residue at C-1 of the glycerol moiety.

Phospholipase A2 *the recommended name for* any carboxylic ester hydrolase that removes the acyl residue at C-2 of the glycerol moiety; e.g. EC 3.1.1.4; *systematic name*: phosphatidylcholine 2-acylhydrolase; *other names*: lecithinase A; phosphatidase; phosphatidolipase. The enzyme requires calcium. Snake-venom enzymes have been much studied and have broad specificity for phosphoglyceride classes. In mammals there are two such enzymes: (1) a pancreatic enzyme, which is released from the exocrine pancreas on stimulation by cholecystokinin, has broad specificity for phosphoglycerides, and hydrolyses phospholipids of digested food in the intestine in conjunction with the action of bile salts to form micelles; and (2) a membrane-bound enzyme, which releases arachidonate for prostanoid synthesis, and is in many cases stimulated by activated hormone and growth-factor receptors.

Phospholipase B EC 3.1.1.5; *recommended name*: lysophospholipase; *other names*: lecithinase B; lysolecithinase. These are enzymes that remove the acyl group from a lysoglycerophospholipid.

Phospholipase C *abbr.*: PLC; *the recommended name for* any phosphoric diester hydrolase that splits the bond between the phosphorus atom and the oxygen atom at C-1 of the glycerol moiety; *other names*: lipophosphodiesterase I; lecithinase C; *Clostridium welchii* α-toxin. Two major types have been studied. both occur in bacteria and animals: (1) one type acts on phosphatidylcholine, releasing diacylglycerol (EC 3.1.4.3); (2) the other is **1-phosphatidylinositol phosphodiesterase** (EC 3.1.4.10), which acts on phosphoinositides; it catalyses the conversion of 1-phosphatidyl-D-*myo*-inositol to D-*myo*-inositol 1,2-cyclic phosphate (which is hydrolysed in animals but not bacteria to inositol 1-phosphate) and diacylglycerol. **1-Phosphatidylinositol-4,5-bisphosphate phosphodiesterase** (EC 3.1.4.11; *other names*: triphosphoinositide phosphodiesterase; phosphoinositide-specific phospholipase C) catalyses the hydrolysis of 1-phosphatidyl-D-*myo*-inositol 4,5-bisphosphate to D-*myo*-inositol 1,4,5-trisphosphate and diacylglycerol. These enzymes play a role in signal transduction. There are at least six forms of the latter, which is required for production of the second messenger molecules **diacylglycerol** and **inositol 1,4,5-trisphosphate**. The activation involves a G_α **G-protein** subunit.

Phospholipase D EC 3.1.4.4; *the recommended name for* any phosphoric diester hydrolase that splits the bond between the phosphorus atom of a glycerophospholipid and the oxygen atom of the nitrogenous base; *other names*: lipophosphodiesterase II; lecithinase D; choline phosphatase.

phospholipid *or (formerly)* **phospholipide** any lipid containing phosphoric acid as mono- or diester.

phospholipid–cholesterol acyltransferase *see* **phosphatidylcholine–sterol *O*-acyltransferase**.

phospholipid exchange protein any of a number of cytosolic proteins that bind phospholipids, and transport them within the cell. Each type of protein exhibits a degree of specificity for the phospholipid bound, and each protein molecule carries one or two phospholipid molecules. These proteins function to exchange phospholipid classes between different intracellular membrane sites.

phospholipid-hydroperoxide glutathione peroxidase an enzyme, EC 1.11.1.12, containing selenocysteine, which catalyses the reduction of lipid hydroperoxides, such as those produced by lipoxygenase.

phospholipid transfer protein *abbr.*: PLTP; a plasma protein (human: 476 amino acids) that mediates transfer of phospholipid and cholesterol from triacylglycerol-rich lipoproteins to high-density lipoproteins (HDL). It is expressed in many tissues (including liver) and is homologous with cholesterol ester transfer protein (CETP) and lipopolysaccharide-binding protein.

phospholipid translocase a protein that accelerates the transfer of phospholipid (*see* **flip-flop**) between the inner and outer lipid leaflets of the plasma membrane bilayer.

phosphomannomutase EC 5.4.2.8; *systematic name*: D-mannose 1,6-phosphomutase; an enzyme that catalyses the reaction:

D-mannose 1-phosphate = D-mannose 6-phosphate.

One of its functions is to convert mannose 6-phosphate to mannose 1-phosphate, from which GDPmannose is synthesized; this is a precursor of **fucose**, and is an intermediate in the synthesis of the **mannose** core of oligosaccharides.

phosphomonoester any monoester of phosphoric acid.

phosphomonoesterase 1 *an alternative name for* **phosphatase**. **2** *an alternative name for* either **acid phosphatase** or **alkaline phosphatase**.

phosphonic acid *see* **phosphono+**.

phosphono+ *comb. form* denoting a phosphonic residue, $-PO(OH)_2$, derived from **phosphonic acid**, $HPO(OH)_2$. In biochemical usage this name is usually reserved for the $-PO(OH)_2$ group attached to a carbon atom, as in **phosphonoacetate**, $(HO)_2OP-CH_2COO^-$; and **2-phosphonoethylamine**, or **ciliatine**, $(HO)_2OP-CH_2CH_2NH_2$; the group is commonly termed phospho+ when linked to a heteroatom, as in phosphocreatine and phosphogluconate.

***N*^ω-phosphonoarginine** *see* **phosphoarginine**.

***N*^ω-phosphonocreatine** *see* **phosphocreatine**.

phosphonomycin *or* **fosfomycin** (1*R*,2*S*)-(1,2-epoxypropyl)phosphonate; an antibiotic produced by *Streptomyces* and *Pseudomonas* strains. It binds irreversibly to UDP-*N*-acetylglucosamine 1-carboxyvinyl transferase (EC 2.5.1.7), an enzyme catalysing the first stage in the synthesis of bacterial cell-wall peptidoglycan from UDP-*N*-acetylglucosamine, which it thereby inhibits. It penetrates the cell by utilizing the L-*α*-glycerophosphate transport system. Loss of this system is a primary reason that resistant strains emerge.



phosphonopeptide any of a series of oligopeptide derivatives, designed as inhibitors of bacterial cell-wall biosynthesis, that have a C-terminal residue of L-1-aminoethylphosphonic acid (a phosphorus-containing analogue of L-alanine).

phosphopentomutase EC 5.4.2.7; *systematic name*: D-ribose 1,5-phosphomutase; *other name*: phosphodeoxyribomutase. An enzyme that catalyses the reaction:

D-ribose 1-phosphate = D-ribose 5-phosphate.

phosphoprotein any protein containing one or more phosphoric residues directly attached, usually by ester linkage, to amino-acid residues.

phosphoprotein phosphatase 1 EC 3.1.3.16; *systematic name*: phosphoprotein phosphohydrolase; any enzyme that removes a phosphate group from a protein by hydrolysis. Many different enzymes have been identified with varying specificity with respect to the primary structure of the substrate protein. *See* **protein phosphatase**. **2** *another name for* **serine/threonine-specific protein phosphatase**.

phosphor any substance (capable of) exhibiting **phosphorescence** (def. 1).

phosphor+ *a variant form of* **phosphoro+** (before a vowel).

phosphoramidate *or* **amidophosphate** *or* **phosphoric amide 1** any ion, salt, or ester of phosphoramidic acid; amidophosphoric acid; $(OH)_2PO-NH_2$. **2** any compound containing the group $(OH)_2PO-NH-$ or $(OH)_2PO-N<$.

phosphoramidite any compound having the general structure $R_3R_4NP(R_2)-O-R_1$. Phosphoramidites are useful in the synthesis of oligonucleotides or for the addition of groups to the 5′-phosphate of nucleotides or oligonucleotides. R_1 is often cyanoethyl-; R_3 and R_4 are often isopropyl with R_2 in 3′-nucleotide linkage.

phosphoramidon *N*-(*α*-L-rhamnopyranosyl-oxyphospho)-L-leucyl-L-tryptophan; a specific inhibitor of **thermolysin**. It is an inhibitor of the metalloendopeptidase, EC 3.4.24.11, that is responsible for cleaving and inactivating **natriuretic peptide**, with corresponding pharmacological effects.

phosphoresce to exhibit **phosphorescence** (def. 1).

phosphorescence 1 a type of luminescence consisting of the emission by a substance of electromagnetic radiation, especially visible light, as a result of the absorption of energy derived from exciting radiation of shorter wavelength or from incident subatomic particles (especially electrons or alpha particles), and that persists for more than approximately 10 ns after excitation ceases, the persistence being a consequence of the excited electrons decaying via a **metastable** (def. 2) state; the property of emitting such radiation. **2** the radiation so emitted. **3** *a common but erroneous term for* **bioluminescence** (which occurs in the absence of exciting radiation). *Compare* **fluorescence**. **—phosphorescent** *adj.*

phosphorescence spectrophotometry measurement of the wavelengths and the intensities of the light emitted from a phosphorescent sample that is excited by monochromatic (or nearly so) exciting radiation.

phosphori+ *a variant form of* **phosphoro+** (def. 3).

phosphoriboisomerase *see* **ribose-5-phosphate epimerase**.

phosphoribosylamine–glycine ligase EC 6.3.4.13; *other names*: phosphoribosylglycinamide synthetase; glycinamide ribonucleotide synthetase (*abbr*.: GARS); an enzyme of *de novo* purine biosynthesis that catalyses the reaction between ATP, 5′-phosphoribosylamine, and glycine to form 5′-phosphoribosylglycinamide (glycinamide ribotide, *abbr*.: GAR) with release of ADP and orthophosphate. The human protein (1010 amino acids) is multifunctional, with domains for three catalytic activities required for purine biosynthesis (amino-acid numbers in brackets): GARS (1–433), **phosphoribosylformylglycinamidine cyclo-ligase** (434–809), and **phosphoribosylglycinamideformyl-transferase** (810–1010), although variations with only one or two of the domains occur through alternative splicing.

phosphoribosylaminoimidazolecarboxamide formyltransferase EC 2.1.2.3; *other name*: AICAR transformylase; inosinicase; IMP synthetase; an enzyme of *de novo* **purine biosynthesis** that catalyses the formation of 5′-phosphoribosyl-5-formamido-4-imidazolecarboxamide from 10-formyltetrahydrofolate and 5′-phosphoribosyl-5-amino-4-imidazolecarboxamide (5-aminoimidazole-4-carboxamide ribotide; *abbr*.: AICAR) forming also tetrahydrofolate. In chicken the protein (593 amino acids) is multifunctional, having activities for AICAR transformylase and **IMP cyclohydrolase;** the latter resides in the C-terminal region.

phosphoribosylaminoimidazole carboxylase EC 4.1.1.21; *other name*: AIR carboxylase; an enzyme of the pathway for *de novo* purine biosynthesis that catalyses the formation of 1-(5′-phosphoribosyl)-5-amino-4-imidazolecarboxylate from 1-(5′-phosphoribosyl)-5-aminoimidazole (5′-aminoimidazole ribotide, *abbr*.: AIR) and CO_2. The reaction requires neither biotin nor ATP. For an example, *see* **multifunctional protein ade2**.

phosphoribosylaminoimidazolesuccinocarboxamide synthase EC 6.3.2.6; *other name*: SAICAR synthetase; an enzyme that catalyses the formation of 1-(5′-phosphoribosyl)-4-(*N*-succinocarboxamide)-5-aminoimidazole(*N*-succinylo-5-aminoimidazole-4-carboxamide ribonucleotide; *abbr*.: SAICAR) from ATP, 1-(5′-phosphoribosyl)-4-carboxy-5-aminoimidazole and L-aspartate with release of ADP and orthophosphate. The reaction forms part of the pathway for the *de novo* synthesis of purines. For an example, *see* **multifunctional protein ade2**.

(5-)phospho(-α-D-)ribosyl diphosphate *symbol*: *P*Rib*P or P*Rib*PP*; 5-phospho-α-D-ribofuranosyl diphosphate; α-D-ribose 1-diphosphate 5-phosphate; a compound that is essential in the biosynthesis of various nitrogen-containing ring compounds or their derivatives, especially of histidine, and of purines and pyrimidines as their nucleotides. It is commonly but incorrectly known as phosphoribosyl pyrophosphate (*abbr. (not recommended)*: PRPP).



phosphoribosylformylglycinamidine cyclo-ligase EC 6.3.3.1; *other name*: phosphoribosyliminoamidazole synthetase; an enzyme of *de novo* synthesis of purines that catalyses the reaction between ATP and 2-formamido-N^1-(5-phosphoribosyl)acetamidine to form 1-(5-phosphoribosyl)-5-aminoimidazole with release of ADP and orthophosphate.

phosphoribosylformylglycinamidine synthase EC 6.3.5.3; *other names*: phosphoribosylformylglycinamidine synthetase; FGAM synthase; an enzyme of the pathway for *de novo* purine biosynthesis that catalyses the formation of 5′-phosphoribosylformylglycinamidine from ATP, 5′-phosphoribosylformylglycinamide, L-glutamine, and H_2O with release of ADP, orthophosphate, and L-glutamate.

phosphoribosylglycinamide formyltransferase EC 2.1.2.2; *other names*: 5′-phosphoribosylglycinamide transformylase; GAR transformylase (*abbr*.: GART); an enzyme of *de novo* purine biosynthesis that catalyses the formation of 5′-phosphoribosyl-*N*-formylglycinamide (formylglycinamide ribotide; *abbr*.: FGAR) from 10-formyltetrahydrofolate, 5′-phosphoribosylglycinamide (glycinamide ribotide, *abbr*.: GAR), and tetrahydrofolate. In chicken there is a multifunctional protein with activities for **phosphoribosylamine–glycine ligase** (GARS)/**phosphoribosylformylglycinamidine cyclo-ligase** (AIRS)/GART.

phosphoribosyl pyrophosphate *abbr*.: PRPP; *a common name for* **(5-)phospho(-α-D-)ribosyl diphosphate**.

phosphoribosyl pyrophosphate synthetase (*abbr.* PRS) *see* **ribose-phosphate pyrophosphokinase**.

phosphoribosyltransferase EC 2.4.2.7–2.4.2.12, 2.4.2.17; any enzyme that catalyses the biosynthesis of a mononucleotide from 5-phospho-α-D-ribosyl diphosphate (PRPP) in a **purine salvage pathway** for nucleoside biosynthesis. Phosphoribosyltransferases catalyse a reaction between a base and 5-phospho-α-D-ribosyl diphosphate to form a D-ribonucleotide and pyrophosphate; the base may be (number indicates no. in sub-subclass EC 2.4.2) adenine (7), hypoxanthine (8), uracil (9), orotate (10), nicotinate (11), nicotinamide (12), or ATP (17). Examples include: hypoxanthine/guanine phosphoribosyltransferase (**HGPRT**) from human; and ATP phosphoribosyltransferase, involved in histidine biosynthesis, from *Escherichia coli.* Other phosphoribosyltransferases of sub-subclass EC 2.4.2 involve the following (no. in sub-subclass EC 2.4.2): anthranilate (18), dioxotetrahydropyrimidine (20), and xanthine (22).

phosphoric *symbol*: *P or* (in the one-letter convention for nucleotides) p; *the general name for* a residue of [ortho]phosphoric acid – i.e. tetraoxophosphoric(v) acid, $PO(OH)_3$ – whether singly, doubly, or triply attached to other groups and whether or not any residual hydroxyl groups are deprotonated.

phosphorimaging a technique for recording a radioactive or chemiluminescent image such as is produced in Southern, Northern, or Western blotting. The image is captured electronically and can be viewed on a computer screen. It is ten times more sensitive than using X-ray film for autoradiography.

phosphorimetry the measurement of **phosphorescence**.

phosphoro+ *or (before a vowel)* **phosphor+** *comb. form* **1** phosphorus. **2** [ortho]phosphoric acid. **3** *or* **phosphori+** phosphorescence.

phosphoroclastic describing a chemical reaction in which a carbon–carbon bond is split apparently by the action of inorganic phosphate with attachment of a phosphoric group to one of the resulting fragments.

phosphorolysis any reversible lytic process or reaction undergone by an acyl compound (I) or glycosyl compound (II) in which nucleophilic displacement by phosphate (anion) occurs, with formation of the corresponding acyl or sugar phosphate and uptake of a hydron by the other moiety of the original compound, as in the generalized equations:

$$\text{(I) R–CO–OR'} + PO_4H_2^- + H^+ = \text{R–CO–O–}PO_3H_2 + \text{HOR'}$$

or

$$\text{(II) R–O–R'} + PO_4H_2^- + H^+ = \text{R–O–}PO_3H_2 + \text{HOR'}.$$

phosphorolytic of, or relating to, phosphorolysis; capable of undergoing phosphorolysis.

phosphorothiolate linkage an analogue of a phosphodiester linkage between nucleotides in which one of the nonbridging oxygens is replaced with a sulphur atom. DNA strands containing phosphorothiolate linkages can be more resistant to the action of nucleases.

phosphorous **1** of, containing, or resembling phosphorus. **2** a residue of phosphorous acid – i.e. trioxophosphoric(iii) acid, $P(OH)_3$ – whether singly or doubly attached to other groups and whether or not any residual hydroxyl groups are deprotonated.

phosphorus *symbol*: P; a nonmetallic element of group 15 of the (IUPAC) **periodic table**; atomic number 15; relative atomic mass 30.974; it exists naturally as a single stable nuclide, **phosphorus-31**. Phosphorus occurs only in the combined state, almost exclusively as phosphates. Its commonest covalencies are iii and v. Phosphorus compounds are vital components of all living materials. *See also* **phosphorus-32**, **phosphorus-33**.

phosphorus-31 the stable nuclide ${}^{31}_{15}P$; its relative abundance in natural phosphorus is 100 atom percent.

phosphorus-32 the artificial radioactive nuclide ${}^{32}_{15}P$. It emits a relatively high-energy electron or β^- particle (1.709 MeV max.) and no gamma radiation. It has a half-life of 14.3 days.

phosphorus-33 the artificial radioactive nuclide ${}^{33}_{15}P$. It emits a moderate-energy electron or β^- particle (0.249 MeV max.) and no gamma radiation. It has a half-life of 25.4 days.

phosphorus:oxygen ratio *abbr.*: P:O ratio; the number of atoms of inorganic phosphorus (as phosphate) incorporated into organic compounds (usually ATP) per atom of dioxygen consumed during **oxidative phosphorylation**. The value observed depends on the nature of the substrate being oxidized and the state of preservation of mitochondrial function. If the latter is high, a P:O ratio near 3 is observed during the oxidation of NADH, near 2 for succinate, fatty acyl CoA, 3-phosphoglycerate. *See also* **chemiosmotic coupling hypothesis**, **tight coupling**.

phosphoryl 1 the trivalent group –P(O)= derived from phosphoric acid. **2** *a name used frequently for* the univalent group $-P(O)(OH)_2$; this usage is not recommended; a phosphoric ester may be named, e.g., choline *O*-(dihydrogenphosphate) or *O*-phosphonocholine. However, phosphoryl is accepted except in derived terms such as the names of enzymes (e.g. phosphorylase) or processes (e.g. phosphorylation). *See also* **phosphono+**.

phosphorylase 1 *the name recommended for* any enzyme, classified as EC 2.4.1.1, that catalyses the phosphorolytic removal of the nonreducing terminal glucose residue from a glucan according to the general reaction:

$$\mathrm{Glc}\alpha1\text{-}[4\mathrm{Glc}\alpha1\text{-}]_n\,4\mathrm{Glc} + \text{orthophosphate} =$$
$$\mathrm{Glc}\alpha1\text{-}[4\mathrm{Glc}\alpha1\text{-}]_{n-1}\text{-}4\mathrm{Glc} + \mathrm{Glc}\alpha1\text{-phosphate}.$$

These enzymes vary somewhat in regard to their preferred substrate; the name should be qualified in each instance by prefixing to it the name of the natural substrate (e.g. starch phosphorylase). In humans, glycogen phosphorylase exists as three isoenzymes – of liver, muscle, and brain – all of which contain pyridoxal phosphate. There are two forms: **phosphorylase** *a,* the more active, phosphorylated form; and **phosphorylase** *b* (*or* dephosphophosphorylase), the less active, unphosphorylated form. The conversion of *b* to *a* is effected with ATP by the enzyme **phosphorylase kinase**, and the conversion of *a* to *b* is brought about by the enzyme **phosphorylase phosphatase** (EC 3.1.3.17). Muscle phosphorylase deficiency results in glycogen disease type V (McArdle disease), and liver phosphorylase deficiency results in glycogen disease type VI (Hers disease). **2** *a generic name recommended for* those glycosyltransferase enzymes within subclass EC 2.4 that utilize orthophosphate as acceptor. Some appear to be specific, e.g. maltose phosphorylase (EC 2.4.1.8) or uridine phosphorylase (EC 2.4.2.3), others less so, e.g. 1,3-*β*-oligoglucan phosphorylase (EC 2.4.1.30). *See also* ***α*-glucan phosphorylase**.

phosphorylase kinase *see* glycogen phosphorylase kinase.

phosphorylase-limit dextrin the polysaccharide produced by the action of starch phosphorylase on the branched polysaccharide **amylopectin**.

phosphorylase phosphatase EC 3.1.3.17; an enzyme that catalyses the hydrolysis of phosphorylase *a* to two molecules of the less active phosphorylase *b* and four of orthophosphate. *See also* **protein phosphatase**.

phosphorylate to effect **phosphorylation**.

phosphorylation the act or process of introducing a **phosphoric** group into a molecule, usually with the formation of a phosphoric ester, a phosphoric anhydride, or a phosphoric amide. Biochemical phosphorylation reactions are important in the trapping of energy, the formation of biosynthetic intermediates during metabolic processes, and in the control of numerous enzymes and other proteins. *See also* **oxidative phosphorylation**, **photophosphorylation**, **substrate-level phosphorylation**.

phosphorylation state ratio *symbol*: R_p; a measure of the phosphorylating power of the adenylate system within cells. It is given by:

$$R_p = [\mathrm{ATP}]/[\mathrm{ADP}][\mathrm{P_i}].$$

Compare **(adenylate) energy charge**.

phosphorylcholine–glyceride transferase *see* **diacylglycerol cholinephosphotransferase**.

phosphorylcholine transferase *see* **cholinephosphate cytidylyltransferase**.

phosphorylethanolamine transferase *see* **ethanolamine-phosphate cytidylyltransferase**.

phosphoryn the major phosphate-rich protein of **dentine**. It contains about 40 residue % of phosphoserine and 35 residue % of aspartic acid. It is isolated from incisors, and is involved in bone mineralization. Soluble forms, and a form complexed with collagen in dentine, are known.

phosphoserine *O*-phospho-L-serine; a phosphoamino acid found in peptide linkage in proteins. Phosphorylation of serine and threonine residues is catalysed by protein kinases specific for serine or threonine residues, and phosphorylation and dephosphorylation mechanisms have a regulatory role in the protein function. *See also* **protein kinase**, **protein phosphatase**.

3-phosphoshikimate 1-carboxyvinyltransferase EC 2.5.1.19; *systematic name*: phospho*enol*pyruvate:3-phosphoshikimate 5-*O*-(1-carboxyvinyl)-transferase; *other name*: 5-*enol*pyruvyl shikimate-3-phosphate (EPSP) synthase; an enzyme of the **shikimate pathway** that catalyses the formation of O^5-(1-carboxyvinyl)-3-phosphoshikimate (5-*enol*pyruvyl shikimate 5-phosphate) from phospho*enol*pyruvate and 3-phosphoshikimate with release of orthophosphate. *See* **pentafunctional arom polypeptide**.

phosphosphingolipid *see* **sphingolipid**.

phosphothreonine *O*-phospho-L-threonine; a phosphoamino acid found in peptide linkage in proteins. Phosphorylation of serine and threonine residues is catalysed by protein kinases specific for serine or threonine residues, and phosphorylation and dephosphorylation mechanisms have a regulatory role in the protein function. *See also* **protein kinase**, **protein phosphatase**.

phosphotransferase any enzyme of sub-subclasses EC 2.7.1 to 2.7.4, and EC 2.7.9; phosphotransferases catalyse transfer of a phosphate group from a donor to an acceptor, and are classified according to whether the transfer is to an alcohol group (EC 2.7.1), a carboxyl group (EC 2.7.2), a nitrogenous group (EC 2.7.3), a phosphate group (EC 2.7.4) or to paired acceptors (EC 2.7.9 – only two of these are currently classified, transferring phosphate from ATP to both pyruvate and orthophosphate in one case and to pyruvate and water in the other, yielding AMP in both instances). Enzymes of sub-subclass EC 2.7.6 that transfer diphosphate are classified as **diphosphotransferases**.

phosphotransferase system a system for transferring substrates into bacteria (*see* **phospho*enol*pyruvate-dependent sugar phosphotransferase system**).

phosphotriester any triester of phosphoric acid.

phosphotriester method (of oligonucleotide synthesis) a method for the chemical synthesis of oligonucleotides in which a suitably protected phosphodiester of general formula Nuc–3′–O–P(O)(OR)OH, where R is an aryl group and Nuc is a residue of an appropriate nucleoside, is first condensed with the 5′-hydroxyl group of another nucleoside (usually anchored through its 3′-hydroxyl group to an insoluble support) to form a phosphotriester. Sequential addition of further nucleoside units is then carried out in the same way, the 5′-protecting group being removed at each stage before the next cycle of reactions. All remaining protecting groups are removed at the completion of the synthesis.

phosphotyrosine *O*-phospho-L-tyrosine; a phosphoamino acid found in peptide linkage in proteins, especially in proteins involved in effector mechanisms in growth stimulation, including growth-factor receptors. *See also* **protein kinase**, **protein phosphatase**.

phosphotyrosine antibodies *or* **antiphosphotyrosine antibodies** antibodies used in cell-signalling research to detect proteins in which tyrosines are phosphorylated by the action of tyrosine kinases.

phosphovitin *or* **phosvitin** a phosphoprotein (subunit size 25 kDa) that, together with **lipovitellin**, constitutes the major part of the mass of the egg-yolk proteins in oviparous vertebrates. It has the highest phosphorus content of all known phosphoproteins (10% P), and approximately half of its amino-acid residues are serine, all of which are *O*-phosphorylated. Phosphovitin and lipovitellin are derived from a common precursor protein, **vitellogenin**.

phot the cgs unit of illuminance, equal to one lumen per square centimetre; 1 phot = 10^4 lux.

phot+ *a variant form of* **photo+** (sometimes before a vowel).

photagogikon (*pl.* **photagogika**) the light-emitting compound of any luminescent system regardless of binding of the compound or of its state of ionization. *See also* **photogen**.

photic **1** of, or relating to, light. **2** of, or relating to, the reaction to light of, or the production of light by, living organisms. **3** describing the uppermost zone in a body of water that receives sufficient light to permit photosynthesis. **—photically** *adv.*

photo+ *or (sometimes before a vowel)* **phot+** *comb. form* denoting **1** of, pertaining to, produced by, or responding to light. **2** involving a photographic process.

photoactivate to render active or reactive by means of light. **—photoactivation** *n.*; **photoactivatable** *or* **photoactivable** *adj.*

photoactive *(of a substance)* capable of giving a physical or chemical response to light or other electromagnetic radiation.

photoactive yellow protein a blue light photoreceptor, containing FAD as chromophore, implicated in a negative phototactic response in photosynthetic bacteria.

photoaddition any chemical addition reaction promoted by light or other electromagnetic radiation.

photoaffinity label *or* **photolabel** an **affinity label** carrying a separate photoactivatable group that on illumination reacts with the protein being labelled to form a covalent link.

photoautotroph *or* **photolithotroph** any organism that is both an **autotroph** and a **phototroph**. **—photoautotrophic** *adj.*; **photoautotrophy** *n.*

photobiochemistry the photochemistry of biochemical processes. **—photobiochemical** *adj.*; **photobiochemically** *adv.*; **photobiochemist** *n.*

photobiology the study of the effects of radiation, mainly of visible and ultraviolet light, on living organisms. **—photobiological** *adj.*; **photobiologist** *n.*

photobleaching the loss of colour or fluorescence through the action of incident visible or near-ultraviolet radiation.

photocatalysis **1** the acceleration of a chemical reaction by light. **2** the catalysis of a photochemical reaction. **—photocatalytic** *adj.*; **photocatalytically** *adv.*

photocathode *(in an electronic device)* a cathode from which electrons are emitted when exposed to electromagnetic radiation of suitable frequency.

photocell *or* **photoelectric cell** any type of transducer capable of converting incident electromagnetic radiation to an electric signal of corresponding magnitude. It may function by generating a potential difference or a current, or by changing its conductance.

photochemical action spectrum the relationship between the efficiency of a **photochemical reaction** and the frequency of the illuminating light.

photochemical reaction any chemical reaction that is initiated or accelerated by the absorption of visible or near-ultraviolet radiation.

photochemistry the branch of chemistry concerned with the effect of electromagnetic, especially visible and ultraviolet, radiation on chemical processes and with the uptake or production of photons during chemical reactions. **—photochemical** *adj.*; **photochemically** *adv.*

photochromism *or* **phototropy** the property possessed by certain substances of changing colour reversibly when exposed to electromagnetic radiation of appropriate frequency. *Compare* **electrochromism**, **thermochromism**. **—photochromic** *adj.*

photoconductive describing an electrical device that is capable of changing its conductance on exposure to light or other electromagnetic radiation. **—photoconductivity** *n.*

photodamage deleterious chemical change caused by the action of light, especially ultraviolet light.

photodensitometer *see* **densitometer** (def. 1).

photodetector a device, e.g. a **photocell**, that responds to incident light.

photodimerization *or* **photodimerisation** the formation of dimers by a photochemical reaction. It is of particular importance in the formation of **pyrimidine dimers** in DNA. **—photodimerize** *or* **photodimerise** *vb.*

photodiode any semiconductor **diode** (def. 1) that generates a potential difference or changes its conductivity when exposed to light.

photodissociation the splitting of a molecule into smaller molecules, radicals, or atoms on absorption of a quantum of electromagnetic radiation.

photodynamic involving, causing, or promoting a deleterious reaction to light, particularly ultraviolet light. Such reactions usually involve oxidation. Damage is caused by **singlet oxygen** produced, e.g., by illumination of chlorophyll in chloroplasts. Normally the singlet oxygen is quenched by the carotenoid pigments coexisting with the chlorophylls in chloroplasts. Hence, any mutation that deletes carotenoids from chloroplasts is lethal, because the chlorophylls are destroyed by singlet oxygen.

photoelectric of, pertaining to, or concerned with electric or electronic effects caused by electromagnetic radiation, especially light.

photoelectric cell *an alternative name for* **photocell**.

photoelectron an electron that is ejected from an atom on interaction of the atom with a photon of sufficient energy.

photoelectron micrograph any photograph of an object taken by **photoelectron microscopy**.

photoelectron microscopy an electron-microscopic technique in which **photoelectrons** emitted from a specimen exposed to ultraviolet radiation are accelerated and focused to produce an image. It is the counterpart in the electron microscope of fluorescence microscopy in the light microscope, the resolution being correspondingly enhanced.

photoelectron spectroscopy a technique in which a specimen (a gas sample or the surface of a solid or a liquid) is exposed to monochromatic electromagnetic radiation in the ultraviolet or X-ray regions and the energy spectrum of the emitted **photoelectrons** recorded. This provides information about the atomic composition of the specimen and also about the types of orbitals to which the constituent electrons of its atoms and molecules are assigned.

photoemission the emission of electrons from a surface as a result of bombardment by photons.

photoexcitation the act or process of raising an atom or molecule to a higher energy state by interaction with a photon.

photogen **1** *an older term for* **photagogikon**. **2** *a term proposed for* the specific biochemical precursor of a photagogikon.

photographic emulsion *or* **emulsion** any medium that is sensitive to light or other electromagnetic radiation, used for preparing photographic film, paper, etc., and consisting usually of a suspension of a silver salt (especially the bromide or chloride) in gelatin; a coating of such a suspension applied to a substrate.

photoheterotroph *or* **photoorganotroph** any organism that is both a **heterotroph** and a **phototroph**. **—photoheterotrophic** *adj.*; **photoheterotrophy** *n.*

photoinactivation the irreversible abolition of specific biological activity by the action of light.

photoinhibition the reversible abolition of specific biological activity by the action of light.

photoionization *or* **photoionisation** the ionization of a molecular entity by the loss of an electron on interaction of the entity with a photon of sufficient energy.

photokinesis any change in the undirected movement of an organism in response to variation in light intensity. **—photokinetic** *adj.*

photolabel *an alternative term for* **photoaffinity label**.

photolabile (of a substance) unstable in the presence of light.

photolithotroph *an alternative term for* **photoautotroph**. —**photolithotrophic** *adj.*; **photolithotrophy** *n.*

photoluminescence luminescence as a result of absorption of electromagnetic radiation. The emitted light is always of lower frequency than that of the incident radiation. —**photoluminescent** *adj.*; **photoluminesce** *vb.*

photolyase *see* **photoreactivation**.

photolyse *or (sometimes, US)* **photolyze** to subject to or to undergo **photolysis**.

photolysis the cleavage of one or more covalent bonds in a molecular entity resulting from absorption of energy from light or other electromagnetic radiation; any photochemical process in which such a cleavage is an essential part, e.g. laser photolysis; flash photolysis. —**photolytic** *adj.*; **photolytically** *adv.*

photolyze *a US spelling of* **photolyse**.

photometer any instrument used to measure the intensity of light or other electromagnetic radiation; includes **spectrophotometer**.

photometry the measurement of the intensity of light or other electromagnetic radiation; it includes spectrophotometry (*see* **spectrophotometer**). —**photometric** *adj.*; **photometrically** *adv.*

photomicrograph a photograph taken through a light microscope; it is sometimes, incorrectly, termed a microphotograph. —**photomicrographic** *adj.*; **photomicrographically** *adv.*; **photomicrography** *n.*

photomultiplier a photocell consisting of a **photocathode** linked to an **electron multiplier**. Photons striking the photocathode cause the emission of electrons, which are then amplified by the electron multiplier to give an enhanced signal.

photon *symbol (in nuclear reactions, etc.)*: γ; a quantum of light (or other electromagnetic radiation) considered as a particle with zero rest mass, zero charge, and energy $h\nu$ joule, where h is the Planck constant and ν the frequency of the radiation in hertz.

photon counter a device, consisting of a photomultiplier and an associated scaler, that is capable of responding to and recording individual photons.

photonicking photolysis of a nucleic-acid molecule with production of a **nick**.

photoorganotroph *an alternative term for* **photoheterotroph**. —**photoorganotrophic** *adj.*; **photoorganotrophy** *n.*

photooxidize *or* **photooxidise** to oxidize by the use of, or as a result of, radiation in the visible and ultraviolet wavelengths. —**photooxidizable** *or* **photooxidisable** *adj.*

photoperiod 1 the length of daylight in a 24-hour period. 2 the duration of daily exposure of an organism to illumination; the length of this period that favours optimum functioning. —**photoperiodic** *adj.*; **photoperiodically** *adv.*

photoperiodism *or* **photoperiodicity** the response of an organism to the relative durations of light and dark in a 24-hour period.

photophore any light-emitting organ of an animal.

photophosphorylation *or* **photosynthetic photophosphorylation** the metabolic processes by which photosynthetic organisms use light energy to convert ADP to ATP without the concomitant reduction of dioxygen to water that occurs in oxidative phosphorylation (*see* **photosynthesis**). There are two distinct electron transport mechanisms: in **noncyclic photophosphorylation**, which involves both photosystems I and II, ATP synthesis is linked to the transport of electrons from water to $NADP^+$, with production of NADPH and dioxygen; in **cyclic photophosphorylation**, which involves only photosystem I, ATP synthesis is driven by a proton gradient generated across the thylakoid membrane.

photopia adjustment of the eye to vision in light of moderate or high intensity, permitting perception of colour; it is considered to involve mainly the **cone cells** of the retina. *Compare* **scotopia**. —**photopic** *adj.*

photopigment any pigment whose chemical state depends on the intensity of the light falling on it.

photopolymerize *or* **photopolymerise** to effect polymerization by the action of light. —**photopolymerization** *or* **photopolymerisation** *n.*

(6–4)photoproduct a type of **pyrimidine dimer**.

photoprotein any protein actively involved in the emission of light by a living organism.

photopsin an **opsin** that is the apoprotein of an **iodopsin**.

photoreactivating enzyme *see* **DNA photolyase**, **photoreactivation**.

photoreactivation the process by which genetic damage caused to organisms by ultraviolet radiation can be reversed by subsequent illumination with visible or near-ultraviolet light. The pyrimidine dimers formed in DNA by the action of ultraviolet light bind **DNA photolyase**, which absorbs light, maximally at 380 nm, and catalyses the restoration of two pyrimidine residues in the DNA.

photoreactive (of a substance or reagent) reactive in a photochemical reaction. —**photoreactivity** *n.*

photoreceptor any biological structure that responds to incident electromagnetic radiation, particularly visible light. It especially refers to a cell that, on absorbing light, generates a nerve impulse or impulses.

photoreduction 1 chemical reduction brought about by electromagnetic radiation, especially visible light. 2 a process occurring at low light intensities in certain algae whereby dihydrogen functions in place of water as an electron donor for the reduction of carbon dioxide and oxygen is not evolved; at higher light intensities normal photosynthesis takes place. 3 reduction in size photographically.

photorespiration a light-dependent catabolic process occurring concomitantly with photosynthesis in plants (especially **C_3 plants**) whereby dioxygen is consumed and carbon dioxide is evolved. The substrate is glycolate formed in large quantities in chloroplasts from 2-phosphoglycolate generated from ribulose 1,5-bisphosphate by the action of **ribulose-bisphosphate carboxylase**; the glycolate enters the peroxisomes where it is converted by **glycolate oxidase** to glyoxylate which undergoes transamination to glycine. This then passes into the mitochondria where it is decarboxylated. C_3 plants may lose 20–40% of photosynthetically fixed carbon by photorespiration, whereas **C_4 plants** lose relatively little. C_4 plants defeat photorespiration in two ways. First, they recapture released CO_2 in the cytoplasm using **phospho*enol*pyruvate carboxylase** which has a very high affinity for CO_2. Although this does not directly affect photorespiration, it prevents loss of CO_2. Second, they concentrate CO_2 near ribulose-biphosphate carboxylase, and this increases the CO_2:O_2 ratio, which has the effect of inhibiting the oxygenase activity. —**photorespiratory** *adj.*

photosensitivity 1 the property of being reactive or unusually reactive to incident photons, especially to those of visible light. 2 *(in medicine)* an abnormal, local or generalized reaction to sunlight, due to the accumulation in the skin of **photodynamic** substances, either endogenous or exogenous. —**photosensitive** *adj.*

photosensitize *or* **photosensitise** 1 to render photosensitive; *see* **photosensitivity**. 2 to render a target molecule more reactive (e.g. more easily oxidized) by the addition to it of a second type of molecule, often a dye, that absorbs light energy and transfers it to the target molecule. —**photosensitization** *or* **photosensitisation** *n.*

photosensitizer *or* **photosensitiser** any substance that photosensitizes or is photodynamic.

photosuicide inhibitor a type of **suicide inhibitor** that, after reaction with an enzyme or other appropriate protein, is capable of being selectively photodecomposed to a highly reactive species that can irreversibly modify the protein in the neighbourhood of its active site.

photosynthate any product of the dark reactions of photosynthesis.

photosynthesis 1 *(in biology)* the synthesis by organisms of organic chemical compounds, esp. carbohydrates, from carbon dioxide using energy obtained from light rather than from the oxidation of chemical compounds (*compare* **chemosynthesis**). In higher plants, green algae, and cyanobacteria, water is the electron donor and dioxygen is evolved; in other photosynthetic bacteria, however, various other simple substances (e.g. H_2S) may act as electron donors, dioxygen is not formed, and the photosynthetic pathway is simpler. Photosynthesis comprises two separate processes: the light reactions and the dark reactions of photosynthesis. The system in higher plants, green algae, and cyanobacteria brings about an overall reaction in which electrons are released from water molecules and are transferred through complexes of chlorophylls, cytochromes, proteins, and small molecules to $NADP^+$, reducing it to NADPH. Protons are released from water and form a chemiosmotic gradient that results in the formation of ATP by a process similar to that operating in mitochondria (*see* **chemiosmotic coupling hypothesis**). These are the **light reactions**. The NADPH and ATP formed by these reactions then drive the **dark reactions** i.e. the **reductive pentose phosphate cycle**. The electrons and protons are released from water by the oxygen-evolving complex (*abbr*.: OEC), and dioxygen is formed in the process. The sequence of reactions involves the OEC, from which electrons pass to photosystem II (*see* **photosystem**), thence to **plastoquinone** reducing it to a quinol which then reduces the cytochrome b_6–f complex. This in turn reduces **plastocyanin** which passes electrons to photosystem I (*see* **photosystem**) which then reduces NADP$^+$ to NADPH. In photosynthetic bacteria, a simpler system exists, in which water is not split, dioxygen is not evolved, and NADP$^+$ is not reduced directly. In this system, photons excite molecules of bacteriochlorophyll *b* in a **photosynthetic reaction centre** to transfer electrons through a cyclic electron-transfer system. Cyclic electron flow can also occur under some conditions in plants, and involves only photosystem I, electrons being released by photon activation from photosystem I and returned to it through cytochrome b_6–f and plastocyanin, with pumping of protons to generate ATP. Under these conditions there is no reduction of NADP$^+$. **2** *(in chemistry)* any synthesis by a photochemical reaction. **—photosynthetic** *adj.*; **photosynthetically** *adv.*

photosynthetic phosphorylation *an alternative term for* **photophosphorylation**.

photosynthetic quotient a ratio of the rate of dioxygen evolution by a cell or organism capable of photosynthesis to that of carbon dioxide uptake. It is an index of photosynthetic activity relative to respiration (including photorespiration).

photosynthetic reaction centre the photosynthetic complex in bacteria, consisting essentially of a transmembrane protein of three subunits, denoted L, M, and H. Collectively the three subunits generate 11 transmembrane helices. Although the L and M helices (which have binding sites for the many prosthetic groups) are different, the groups themselves are arranged with near twofold symmetry because of similarities in the folds of the subunits. The L and M subunits bear bacteriochlorophyll, bacteriopheophytin, ubiquinone, and menaquinone molecules. The bacteriochlorophylls will be either *a* or *b* types, as will be the bacteriopheophytins. Here we describe a system with *b* types. Of the four bacteriochlorophyll *b* molecules, two constitute a ‘special pair’ with an Mg^{2+}–Mg^{2+} distance of 7 Å and in hydrophobic environments; other prosthetic groups are **bacteriopheophytin** *b* (two molecules), one nonheme Fe(ii), one **ubiquinone**, and one **menaquinone**. There is cyclic electron flow through a cytochrome bc_1 complex, cytochrome *c*, and the bacteriochlorophyll–bacteriopheophytin complex, protons being pumped from the bacterial cytosol to the periplasmic space, and then returning to the cytosol through an ATP synthase with synthesis of ATP. The system differs from that in plants in that there is only one type of reaction centre, no splitting of water, and no direct reduction of NADP$^+$. Its essential features are that photons excite electrons in the ‘special pair’ and these excited electrons then flow through the bacteriochlorophyll–bacteriopheophytin complex, ubiquinone, and menaquinone, dissipating energy in bringing about protein pumping to form the chemiosmotic gradient that results in ATP formation. They then return to the ‘special pair’ via cytochromes bc_1 and *c*. This protein (and the complex from *Rhodopseudomonas viridis*) represents the first transmembrane protein to have its 3-D structure determined in atomic detail by X-ray crystallography – by J. Deisenhofer, German biophysicist Hartmut **Michel** (1948–), and German biochemist Robert **Huber** (1937–). *See also* **P870**, **P960**, **photosystem** (def. 2).

photosystem 1 either of the two functionally distinct but cooperating systems, designated photosystem I (*abbr*.: PSI) and photosystem II (*abbr*.: PSII), between which are distributed the various molecules that effect the light reactions of **photosynthesis**; photosystems are located in the **thylakoid** membranes of the chloroplasts of higher plants and green algae or in the free thylakoid membranes of cyanobacteria. Photosystem I consists of a transmembrane multisubunit complex, of about 10 subunits in all, consisting of a heterodimer complex of PsaA and PsaB which binds P700, together with the chlorophyll acceptor A_0, the phylloquinone acceptor A_1, and Fx, a 4Fe–4S centre. PsaC, which is bound to this complex, contains two additional 4Fe–4S centres required for ferredoxin reduction. PsaC of pea is similar to bacterial-type 4Fe–4S **ferredoxins**. Other subunits are involved in binding soluble ferredoxin, ferredoxin-NADP oxidoreductase and regulation of electron flow. Approximately 100 chlorophyll *a* molecules are bound to the minimal heterodimer unit. Photosystem II is formed from a heterodimer of the D_1 and D_2 proteins which bind P680, together with the pheophytin acceptor, two plastoquinone acceptors Q_a and Q_b, and a non-heme iron atom. The minimal purified unit contains about six chlorophyll *a* molecules. **Cytochrome b_{559}** is always associated with PSII. A large number of other subunits including light-harvesting chlorophyll-protein complexes, proteins involved in stabilizing the Mn complex, and regulatory subunits are required to form a functional photosystem II. **2** any functionally analogous but simpler single photosystem present in photosynthetic bacteria. That from *Rhodopseudomonas viridis* contains three hydrophobic subunits, a special pair of bacteriochlorophyll *b* (the reaction-centre bacteriochlorophyll P960), two molecules of bacteriopheophytin *b* (*see* **bacteriopheophytin**), a bound iron atom and one molecule each of **ubiquinone** and a **menaquinone**. There are four heme *c*-type cytochromes in this case (but not in all). The complete structure has been determined by X-ray crystallography. *See also* **photosynthetic reaction centre**.

phototaxis the movement of a motile cell or organism towards (**positive phototaxis**) or away from (**negative phototaxis**) a source of light. **—phototactic** *adj.*

phototoxic able to cause physiological damage by making the skin abnormally sensitive to light. **—phototoxicity** *n.*

phototransistor a type of junction transistor that responds to incident light or other electromagnetic radiation by the generation of an electric current, which is then amplified.

phototroph *or* **phototrophe** any organism whose principal or only source of primary energy is sunlight. The great majority of such organisms are **photoautotrophs** (*or* **photolithotrophs**), which use light energy to synthesize their organic requirements solely from inorganic precursors; these include all green plants and algae, cyanobacteria, and green and purple sulfur bacteria. Relatively few phototrophs are **photoheterotrophs** (*or* **photoorganotrophs**), which require a supply of organic precursors to manufacture their own organic components; examples include certain purple nonsulfur bacteria. *Compare* **chemotroph**. **—phototrophic** *adj.*; **phototrophy** *n.*

phototropic 1 involving or showing **phototropism**. **2** involving or showing phototropy (i.e. **photochromism**).

phototropin a blue-light receptor protein, containing FMN as chromophore, that regulates different aspects of growth and development in plants.

phototropism the orientation or growth of a cell or (a part of) an organism in relation to a source of light. The term is used especially of plants or plant organs.

phototropy *an alternative term for* **photochromism**.

phototube a type of photocell consisting of a vacuum tube or gas-filled tube in which a photocathode responds to incident light or other electromagnetic radiation by emission of electrons.

phox *abbr. for* phagocyte NADPH oxidase.

php *see* **programming language**.

pH paper absorbent paper, usually in strip form, that is impregnated with a colour-changing pH indicator dye. It is useful for estimating the approximate pH of a solution.

pH profile *see* **pH-activity profile**.

phragmoplast a structure formed in the developing plant cell wall from the endoplasmic reticulum and spindle fibres. It is observed during **cytokinesis** in plant cells as a cylindrical structure, composed of microtubules, between the two sets of daughter chromosomes. The microtubules are those of the two sets of polar microtubules of the **spindle**. These microtubules transport small Golgi-derived vesicles to the equatorial (or central) region, which fuse there to form the early **cell plate**, which then grows out to join up with the cell wall.

PHRAP *see* **sequence assembly software**.

PHRED *see* **sequence assembly software**.

phrenosin a **cerebroside** in which the acyl constituent is cerebronate. *See* **lignocerate**, of which cerebronate is the 2-hydroxy derivative.

PHRP *abbr. for* parathyroid hormone-related protein.

pH standard any of a set of six standard solutions which may be used as primary pH standards; they are: potassium hydrogen tartrate, saturated at 25°C, pH 3.557 at 25°C; 0.1 mol/kg potassium dihydrogen citrate, pH 3.776 at 25°C; 0.025 mol/kg KH_2PO_4 + 0.025 mol/kg Na_2HPO_4, pH 6.865 at 25°C; 0.008695 mol/kg KH_2PO_4 + 0.03043 mol/kg Na_2HPO_4, pH 7.413 at 25°C; 0.01 mol/kg disodium tetraborate, pH 9.180 at 25°C; 0.025 mol/kg $NaHCO_3$ + 0.025 mol/kg Na_2CO_3, pH 10.012 at 24°C.

pH-stat an instrument for maintaining a constant pH in an aqueous liquid mixture in which hydrogen ions are being liberated or taken up. It is frequently arranged to measure the amount of reagent, as a function of time, that has to be added to maintain a predetermined pH.

Pht< *or* **–Pht–** *symbol for* the (divalent) phthaloyl group.

Pht– *symbol for* the (univalent) phthalyl group.

phthalate 1 *the trivial name for* 1,2-benzene dicarboxylate, the dianion of phthalic acid. **2** any mixture of phthalic acid and its mono- and dianions. **3** any salt or ester of phthalic acid.

phthaloyl *symbol*: Pht< *or* –Pht–; the divalent acyl group, $-OC-C_6H_4-CO-$, derived from phthalic acid.

phthalyl *symbol*: Pht–; the univalent acyl group, $HOOC-C_6H_4-CO-$, derived from phthalic acid.

pH unit the difference between any two successive integral values of pH.

phyco+ *comb. form* denoting seaweed or other algae.

phycobilin any **bilin** found in **phycobiliproteins**. The two most common are **phycocyanobilin** and **phycoerythrobilin**. They are linear tetrapyrroles or **open tetrapyrroles**, i.e. chains of four pyrroles, the terminal pyrroles not being linked to each other to form the cyclic tetrapyrrole structure. The structure of phycocyanobilin is shown; phycoerythrobilin is similar, except that the ethyl group on ring A is $-CH=CH_2$, and the methyne group between rings A and B is a methylene group.

phycobiliprotein *or* **biliprotein** any phycobilin–protein conjugate found in algae of the phyla Cryptophyta and Rhodophyta, and in cyanobacteria. Phycobiliproteins are intensely coloured, fluorescent, water-soluble globular proteins. The two most common types, **phycocyanin** and **phycoerythrin**, are composed of two kinds of subunit, α (10–20 kDa) and β (14–30 kDa), each of which carries about three molecules of covalently bound **phycobilin** (phycocyanobilin in phycocyanin, phycoerythrobilin in phycoerythrin), and is present *in vivo* most commonly as aggregates of formula $(\alpha,\beta)_n$, where *n* is 3 or 6. Phycocyanin (blue: A_{max} at 618 nm) predominates in Cyanophyta, and phycoerythrin (red: A_{max} at 545 nm) predominates in Rhodophyta. A third type, **allophycocyanin** (pale blue: A_{max} at 650 nm), present in small amounts in both Cyanophyta and Rhodophyta, has only one type of protein subunit (~15.5 kDa), carries one molecule of covalently bound phycocyanobilin, and is present *in vivo* as aggregates of six subunits. It is a heterodimer of α and β chains. *See also* **phycobilisome**.

phycobilisome any of the granules, approximately 32 nm × 48 nm, consisting of highly aggregated **phycobiliproteins**, that are attached in arrays to the external face of a **thylakoid** membrane in algae of the phyla Cyanophyta and Rhodophyta, where they function as light-harvesting devices in photosynthesis. Excitation energy in the phycobilisome flows in the sequence:

$$\text{phycoerythrin} \rightarrow \text{phycocyanin} \rightarrow \text{allophycocyanin},$$

whence it passes to the antenna chlorophyll of photosystem II. In Cyanophyta it is also known as a **cyanosome**.

phycocyanin a blue phycobilin; *see* **phycobiliprotein**.

phycocyanobilin a type of **phycobilin**; *see also* **phycobiliprotein**.

phycoerythrin a red phycobilin; *see* **phycobiliprotein**.

phycoerythrobilin a type of **phycobilin**; *see also* **phycobiliprotein**.

phycofluor any artificial conjugate of a **phycobiliprotein** with a molecule conferring biological specificity (e.g., avidin, immunoglobulin, protein A). Such conjugates are useful in fluorescence immunoassay and fluorescence-activated cell sorting, by virtue of the distinctive and intense fluorescence of the phycobiliprotein moiety.

phycotoxin any poisonous substance produced by algae.

phyl+ *a variant form of* **phylo+** (sometimes before a vowel).

phyla the plural of **phylum**.

PHYLIP *abbr. for* phylogeny inference package; *see* **phylogeny package**.

phyllo+ *or (before a vowel)* **phyll+** *comb. form* denoting leaf.

phyllocerulein *or (esp. Brit.)* **phyllocaerulein** *see* **cerulein**.

phylloquinone *abbr.*: K; *the recommended name for* vitamin K_1; 2-methyl-3-phytyl-1,4-naphthoquinone. *See* **vitamin K**.

phylo+ *or (sometimes before a vowel)* **phyl+** *comb. form* denoting race or tribe.

phylogenetic analysis study of the evolutionary relationships between genes, populations, species, etc., usually by constructing **phylogenetic trees**. Phylogenetic analysis may also be applied to individual characters, in order to chart the evolution of particular traits or conditions.

phylogenetic tree a graphical representation of the (putative) evolutionary relationships of a group of organisms.

phylogenomic analysis the application of phylogenetic analysis methods at the level of whole genomes. It is used, for example, to chart the evolutionary history of individual genes (and their products), of genome segments, or of complete genomes.

phylogeny the evolutionary history of an organism or group of related organisms. In biochemistry, such evolutionary relationships are based on similarities and differences in nucleic acid or protein sequences. —**phylogenetic** *or* **phylogenic** *adj.*

phylogeny package a software suite for phylogenetic analysis, which typically includes parsimony, maximum-likelihood, and distance methods, together with various tree-drawing tools. Examples include PAUP (phylogenetic analysis using parsimony) and PHYLIP (phylogeny inference package).

phylogram a phylogenetic tree that indicates the relationships between taxa and also conveys a sense of time or rate of evolution.

phylum (*pl.* **phyla**) a primary taxon of animals or plants (in plants also termed division). It consists of a number of classes (or sometimes a single class).

physalaemin Glp-Ala-Asp-Pro-Asn-Lys-Phe-Tyr-Gly-Leu-Met-NH_2; an 11-residue peptide amide **tachykinin** from the skin of the amphibian *Physalaemus fuscumaculatus*. It is more potent than **eledoisin** and **substance P** in some assay systems, and is useful in the study of receptors for substance P.

physeteric acid *see* **tetradecenoic acid**.

physical 1 of, or pertaining to, matter and energy; of material things. **2** of, or relating to, natural science, especially of nonliving systems. *Compare* **biological**. **3** having reference to or used in physics. —**physically** *adv.*

physical adsorption *an alternative term for* **physisorption**.

physical biochemistry the application of physical chemistry to biochemical substances, structures, and systems. Often used synonymously with **biophysical chemistry**.

physical chemistry the branch of chemistry concerned with the relationship between the physical properties of substances and their chemical properties, reactions, and structures.

physical map a map that identifies the physical location of genes on a chromosome, in contrast to a **linkage map**, which is generated by measuring recombination frequencies. Physical length can be measured in base pairs, kilobases, or megabases. Such maps are obtained using a variety of methods, e.g. pulsed field gel electrophoresis, fluorescence *in situ* hybridization, contig mapping using polymorphic markers, and by sequencing entire genomes.

physico+ *comb. form* denoting physical or of physics.

physicochemical of, pertaining to, or using the methods of physical chemistry. —**physicochemically** *adv.*

physics *functioning as sing.* the branch of science concerned with the properties of matter and of energy, and with the interactions and interconversions between matter and energy.

physin any of various membrane proteins that have similar architecture to, and are homologous with, the **gyrin** family. They occur in several types of transport vesicle. Examples include pantophysin, synaptophysin, and synaptobrevin.

physiological 1 of, pertaining to, or used in physiology. **2 normal** (def. 4); not **pathological** (def. 2) or **pharmacological** (def. 2). —**physiologically** *adv.*

physiological antagonist a drug that produces the opposite effect to a specified agonist by an action that is unrelated to that of the agonist.

physiological chemistry *an older term for* **biochemistry** (especially that of humans and higher animals).

physiological conditions environmental conditions simulating those under which the (normal) functions of a cell, organ, or tissue can be expressed.

physiological saline *or (sometimes)* **normal saline** a (sterile) solution of 0.9% w/v (0.154 mol L^{-1}) sodium chloride in water. It is approximately isotonic with mammalian blood and lymph, and is useful in the temporary maintenance of living cells and tissues, and as a vehicle for injections.

physiology the science dealing with the functioning of cells, tissues, organs, and organisms, and with the chemical and physical phenomena concerned.

physisorption *or* **physical adsorption** *or* **van der Waals adsorption** the type of **adsorption** (def. 1) in which only van der Waals forces are involved and hence in which no significant changes occur in the electronic orbital patterns of the interacting substances. *Compare* **chemisorption**.

physostigmine *or* **eserine** a toxic alkaloid extracted from Calabar beans (*Physostigma venenosum*). It inhibits **cholinesterase** by binding to the anionic site of the enzyme, forming a carbamoyl ester of the serine hydroxyl, which is only slowly hydrolysed. It has been used in West Africa in witch ordeals.

phyt+ *a variant form of* **phyto+** (before a vowel).

phytanic acid 3,7,11,15-tetramethylhexadecoanoic acid; a branched-chain fatty acid that is formed metabolically from **phytol**, a constituent of chlorophyll, by bacteria in the ruminant stomach. In humans it is derived from dairy products, meat, ruminant fat, fish, and free phytol. Its oxidation in animals depends on the **alpha oxidation** pathway, since the methyl group on C-3 (the beta carbon) blocks beta oxidation. After alpha oxidation this methyl group is on C-2 of the product, so that beta oxidation can occur, releasing propionyl-CoA as a product. It accumulates secondarily in various peroxisome biogenesis disorders (e.g. **Zellweger syndrome**) and primarily in **Refsum disease** (classical or adult).

phytanoyl-CoA hydroxylase EC 1.14.11.18; an enzyme of liver peroxisomes that catalyses the reaction:

$$\text{phytanoyl-CoA} + O_2 + \text{2-oxoglutarate} =$$
$$\text{2-hydroxyphytanoyl-CoA} + CO_2 + \text{succinate.}$$

The reaction requires Fe^{2+} and ascorbate, and is the first step in the catabolism of **phytanic acid**. Enzyme deficiency results in classical or adult **Refsum's disease**.

phytase either of the two enzymes, designated 3-phytase (EC 3.1.3.8) and 6-phytase (EC 3.1.3.26), that catalyse the hydrolytic removal of a phosphoric residue from **phytate** at the 3-position or the 6-position, respectively; most commonly it signifies 6-phytase.

phytate any anion of **phytic acid**, any mixture of free phytic acid and its ionized forms, or any salt of phytic acid. It is the major phosphorus compound in plants and is important for phosphate storage in cereal grains, especially as its calcium–magnesium salt, **phytin**. In higher animals phytin binds dietary Ca^{2+} and Mg^{2+}, making them less available.

+phyte *noun suffix* denoting **1** plant (of the habitat or type specified). **2** pathological outgrowth. **—+phytic** *adj.*

phytic acid *the trivial name for myo-*inositol hexakis(dihydrogen phosphate). *See* **phytate**.



phytin *see* **phytate**.

phyto+ *or (before a vowel)* **phyt+** *comb. form* denoting plant.

phytoagglutinin *or (rarely)* **phytohemagglutinin** any plant **lectin**. The majority are glycoproteins, although some, e.g. **concanavalin A**, contain no carbohydrate. They accumulate mainly in seeds, in cytoplasm of cotyledons and embryonic cells, although they are synthesized in leaves.

phytoalexin any substance with antibiotic activity that is produced by plant tissues in response to infection, especially with a fungus. A variety of substance are regarded as phytoalexins. They include compounds as divergent as **phaseollin**, some sesquiterpenes and long-chain acetylenic alcohols.

phytochelatin any of a group of peptides that bind heavy metals (Cd, Zn, Cu, Pb, Hg) in thiolate coordination complexes, and can be isolated from plant cell suspension cultures. The structure is of the type (γ-glutamyl-cysteinyl)$_n$-glycine, where *n* is 2 to 11.



phytochelatin synthase EC 2.3.2.15; *recommended name*: γ-Glu-Cys-dipeptidyltransferase; an enzyme that catalyses the reaction:

$$n\text{GSH} = (\gamma\text{-Glu–Cys})_n\text{Gly} + \text{glycine}_{(n-1)}$$

where *n* = 2–11. It is induced by, and active only in the presence of, heavy metals (e.g. Cd, Cu, Hg, As), and is present in plants, some microorganisms, and the nematode *Caenorhabditis elegans*. Examples: *Arabidopsis thaliana* (485 amino acids); *Schizosaccharomyces pombe* (414 amino acids); *C. elegans* (371 amino acids); and *Dictyostelium discoideum* (626 amino acids). All are rich in cysteine and show 40–50% sequence identity in their N-terminal regions.

phytochemistry the branch of chemistry concerned with plants, especially with **secondary metabolites**.

phytochrome a chromoprotein present in trace amounts in all higher plants, involved in regulating light-dependent processes, such as leaf development and flowering. It consists of a **phycobilin**-related chromophore covalently linked to a polypeptide of ~124 kDa. Phytochrome exists in two forms, P$_R$ (A_{max} at 666 nm) and P$_{FR}$ (A_{max} at 730 nm), which are indefinitely interconvertible on absorption of light in the red and far-red regions of the spectrum, respectively. The spectral changes are the result of *cis–trans* isomerization in the phycobilin. The active form, P$_{FR}$, plays a central role in light-promoted modulation of gene expression, which is of importance in plant growth and development in every phase of the life cycle; conversion of P$_{FR}$to P$_R$ cancels these responses. The phytochromes are homodimeric proteins, with a linear tetrapyrrole chromophore covalently linked to a polypeptide.

phytoecdysone *(sometimes)* any **ecdysteroid** found in plants.

phytoene a C$_{40}$ carotenoid, derived by head-to-head combination of two molecules of geranylgeranyldiphosphate catalysed by phytoene synthase within the plastids of leaves of many plant species. It is the precursor of ζ-carotene, lycopene, β-carotene, and various xanthophylls.

phytoferritin a protein, similar to **ferritin** of animals, that occurs almost exclusively in plastids, especially in those of plant storage organs.

phytoglycogen plant glycogen; a highly branched polymer of D-glucose, with a structure similar to that of animal **glycogen**, found in fungi, corn (maize), and rice. A similar substance is found in bacteria and cyanobacteria.

phytohemagglutinin *or (esp. Brit.)* **phytohaemagglutinin 1** *abbr.*:

PHA; *or* **phytomitogen** the **lectin** from the red kidney bean, *Phaseolus vulgaris*; a potent mitogen. **2** *a rare alternative name for* **phytoagglutinin**.

phytohormone *or* **plant hormone** any plant growth factor or similar substance that regulates plant development. The group includes **abscisic acid**, **auxins**, **ethylene**, **cytokinins**, and **gibberellins**.

phytokinin *an alternative term for* **cytokinin**.

phytol *a trivial name for trans-* (or *E*-) (7*R*,11*R*)-3,7,11,15-tetramethyl-2-hexadecen-1-ol; the pure substance is a colourless oily liquid. Phytol occurs in combined form in chlorophyll and vitamin K_1. In animals it is oxidized to **phytanic acid**, which then undergoes alpha oxidation. *See also* **phytyl**.

phytolysosome a **lysosome** of plant cells.

phytomitogen *an alternative name for* **phytohemagglutinin** (def. 1).

phytoplankton plant plankton; consisting of diatoms, dinoflagellates, and other microscopic algae.

phytoporphyrin any plant **porphyrin**.

phytosiderophore any of various organic iron-chelating molecules secreted by the roots of different species of the grass family (including oat, barley, wheat, and rice). The iron–phytosiderophore complex enters the roots through an iron transporter in the plasma membrane. The two that have been characterized are the nonprotein amino acids mugineic acid (of barley) and avenic acid (of oats). Both are derived from the α-aminobutyrate moieties of three *S*-adenosylmethionine molecules by the action of nicotianamine synthase.

phytosphingosine 2*S*,3*S*,4*R*-2-amino-1,3,4-octadecanetriol; a constituent of many plant sphingolipids.

phytosterol any sterol occurring in higher plants; they differ from animal sterols in having C_1 or C_2 residues at C-24 and/or a double bond at C-22.

phytotoxic toxic to a plant.

phytotoxin **1** any toxin produced by a plant. **2** any substance that is toxic to a plant or plants.

phytotron a laboratory where plants can be grown and studied under a variety of controlled conditions.

phytyl the alkyl group, $(CH_3)_2$–CH–$[CH_2]_3$–CH(CH_3)–$[CH_2]_3$–CH(CH_3)–$[CH_2]_3$–C(CH_3)=CH–CH_2–, (*E*)-(7*R*,11*R*)-3,7,11,15-tetramethyl-2-hexadecenyl, derived from **phytol**.

pi **1** *symbol*: π (lower case) *or* Π (upper case); the sixteenth letter of the Greek alphabet. For uses *see* **Appendix A**. **2** *(in mathematics) symbol*: π; a transcendental number that is the ratio of the circumference of a circle to its diameter. It has the approximate value 3.141 592 653 59.

pI *symbol for* isoelectric point.

PI *abbr. for* phosphatidylinositol.

pi adduct *or* **π adduct** any adduct formed by coordination and involving donation of an electron pair from a **pi orbital** into a **sigma orbital**, from a sigma orbital into a pi orbital, or from a pi orbital into a pi orbital. It is also known, less correctly, as a **pi complex**.

PIAS *abbr. for* protein inhibitor of activation by STAT; a human nuclear protein that inhibits transcriptional activation by STAT3 (*see* **STAT**). It contains a SAP (DNA-binding) domain and a zinc finger domain. Orthologues are present in other vertebrates.

pi bond *or* **π bond** the type of covalent bond formed between atoms by electrons occupying a **pi orbital**.

picein (wax) an unreactive thermoplastic material, composed of a mixture of hydrocarbons of very low vapour pressure, that adheres well to glass and metal. It is useful as a sealing substance in the assembly of vacuum systems.

Pichia *see* **methylotrophic yeasts**.

picket-fence (porphyrin) complex any synthetic iron–porphyrin complex in which the porphyrin has been derivatized with four large groups attached to one side of the porphyrin ring, to each of the inter-pyrrole carbon atoms, so as to form a protective enclosure for the binding of a dioxygen molecule as in **myoglobin** or **hemoglobin**.

pico+ *symbol*: p; SI prefix denoting 10^{-12} times.

picogram *symbol*: pg; a unit of mass equal to 10^{-15} kilogram or 10^{-12} gram.

picometre *or (US)* **picometer** *symbol*: pm; a unit of length equal to 10^{-12} metre.

picomolar *symbol*: pm *or* pM; describing a solution containing one picomole of solute per litre of solution, or a specified multiple or fraction thereof; used also of a substance concentration similarly expressed.

picomole *symbol*: pmol; a unit of amount of substance equal to 10^{-12} mole.

pi complex *or* **π complex** *a less suitable name for* **pi adduct**.

picoplankton plankton having cell dimensions of between 0.2 and 2 μm and including bacteria, cyanobacteria, some algae, and certain microscopic protozoans. Picoplankton appears to be ubiquitous in open waters of lakes and seas and probably exceeds in total biomass any other group of pelagic organisms.

picornavirus any RNA animal virus consisting of naked, icosahedral 27 nm capsids with single-stranded infectious RNA (plus strand) of 2.7 MDa. The group includes human poliovirus, some common-cold viruses, and foot-and-mouth disease virus (of cattle and other cloven-footed mammals).

picosecond *symbol*: ps; a unit of time equal to 10^{-12} second.

4-pi counter any type of radiation counter that detects radiation emitted through a solid angle of 4π steradians, i.e. in all directions from a source.

picrotoxin *or* **cocculin** a preparation containing an equimolar mixture of **picrotoxinin** ($C_{15}H_{16}O_6$) and **picrotin** ($C_{15}H_{18}O_7$) obtained from the seeds of *Anamirta cocculus* (fishberries). It contains a potent ligand for the chloride ionophore of the $GABA_A$ receptor, binding to the channel protein and inhibiting Cl^- transport without displacing GABA; this endows it with potent convulsant activity. It can thus also act as an antidote to barbiturates, which enhance GABA binding. It is displaced from its binding site by anticonvulsants.

piebaldism *see* **KIT**.

pi electron *or* **π electron** an electron in a **pi orbital**.

piericidin A an antibiotic that is a structural analogue of **ubiquinone** and a classical inhibitor of mitochondrial electron transport similar in action to **rotenone**. It is a potent inhibitor of NADH:ubiquinone oxidoreductase (*see* **NADH dehydrogenase**), acting at or near the ubiquinone catalytic site.



pig **1** any nonruminant, omnivorous ungulate mammal of the family Suidae, especially the domestic pig, *Sus scrofa*. **2** *informal* short for **guinea pig**.

PIG *abbr. for* phosphatidylinositolglycan.

PIG-A *abbr. for* phosphatidylinositol glycan protein class A.

pigeon any stout-bodied bird of the family Columbidae, especially the domesticated or feral pigeon, *Columba livia*. Pigeon-breast muscle has been extensively used as a convenient tissue for the study of oxidative metabolism.

pigment **1** any general or particular colouring matter in living organisms. **2** any natural or artificial substance used to impart colour. **3** to colour with pigment.

pigment 680 *see* **P680**.

pigment 700 *see* **P700**.

pigmentation **1** natural coloration of organisms. **2** an increase in such coloration.

pigment system *an alternative name for* **photosystem**.

pigmenturia the presence of a component that imparts an abnormal colour to urine. The pigment may be endogenous (e.g. bilirubin diglucuronide, porphyrin, myoglobin, hemoglobin, blood, homogentisic acid) or exogenous (e.g. beet, cascare, senna, levodopa, riboflavin, methylene blue).

PI-G-tailed proteins proteins that are anchored to the membrane through linkage to phosphatidylinositol-glycan.

PIGylation the biosynthetic process whereby **PIG-tailed** proteins are produced.

pili the plural of **pilus**.

pilin any protein subunit of a bacterial **pilus**.

pilocarpine an alkaloid extracted from *Pilocarpus jaborandi*; it has muscarinic cholinomimetic activity.



pilosulin any of a family of peptidic channel-forming toxins, with about 100 amino acid residues, produced by various animals, particularly ants. Pilosulin is classified in the TC system under number 1.C.51.

pilot plant a prototype apparatus set up to develop and scale up a new manufacturing process.

pilus (*pl.* **pili**) a hairlike appendage, about 25 nm in diameter and 10–12 μm long, present sometimes on cells of certain Gram-negative bacteria, especially members of the Enterobacteriaceae and *Pseudomonas* spp., in addition to any flagella. The two main types, distinguishable morphologically and antigenically, are **common pilus** and **sex pilus**, both of which may be present on the same cell. Up to several hundred common pili per cell may be present, either distributed over the entire surface or concentrated at a pole; their function is not known. Only one or two sex pili commonly are present; they appear to be required for bacterial **conjugation**. Both types of pili are thought to be tubes or tubelike structures formed from one or two helically wound strands, each of which consists of a linear arrangement of molecules of the protein pilin. The term pilus is often used interchangeably with **fimbria**, but may be used specifically to mean sex pilus (in which case fimbria then denotes common pilus).

PIM a gene family encoding serine/threonine kinases of unknown function named from proviral integration site MuLV-induced murine T-cell lymphomas. They are highly conserved between human and mouse, and are expressed at high levels in hemopoietic tissues, testes and ovaries, and embryonic stem cells.

pI marker an **isoelectric point marker**; *see* **isoelectric point**.

PIN *abbr. for* protein inhibitor of neuronal nitric oxide synthase; a highly conserved 10 kDa protein from rat hippocampus that inhibits neuronal nitric oxide synthase.

pineal body *or* **pineal gland** a small, pine-cone-shaped structure situated deep between the cerebral hemispheres of the mammalian brain. It elaborates and secretes **melatonin**.

pineal hormone *an older name for* **melatonin**.

ping-pong mechanism *an alternative name for* **double-displacement (enzyme) mechanism**.

pinocytic *an alternative term for* pinocytotic (*see* **pinocytosis**).

pinocytic vesicle *an alternative term for* **pinocytotic vesicle**.

pinocytosis the process whereby cells take in liquid material from their external environment; literally ‘cell drinking’. Liquid is enclosed in vesicles, formed by invagination of the plasma membrane. These vesicles then move into the cell and pass their contents to endosomes. Pinocytosis is the type of **endocytosis** occurring in most types of cells; hence the term is often applied interchangeably with endocytosis to such cells (*compare* **phagocytosis**). —**pinocytotic** *or* **pinocytic** *adj.*

pinocytotic vesicle *or* **pinocytic vesicle** a cellular vesicle serving **pinocytosis**; an alternative term to **endocytotic vesicle** when containing nonparticulate material.

pinosome *an alternative name for* **endosome** (def. 1) (when containing nonparticulate material).

pi orbital *or* **π orbital** a bonding molecular orbital formed by the in-phase, sideways-on overlap of parallel p atomic orbitals, one from each of two atoms, to produce a charge-density distribution that is mainly between the atomic nuclei but maximal in two zones, one on either side of and parallel to the internuclear axis. When occupied by two electrons of opposed spins it becomes the second bond in a double covalent bond (two such occupied orbitals, mutually orthogonal, providing the second and third bonds of a triple bond).

PIP *or* **PI 4-P** *abbr. for* phosphatidylinositol 4-phosphate.

PIP$_2$ *or* **PI 4,5-P$_2$** *abbr. for* phosphatidylinositol 4,5-bisphosphate.

Pipes *or* **PIPES** *abbr. for* 1,4-piperazinediethanesulfonic acid; a **Good buffer substance**; pK_a (20°C) = 6.8.



pipette *or (US)* **pipet 1** any device for transferring or delivering (usually measured) volumes of liquid and commonly consisting of a slender, calibrated glass or plastic tube with a finely drawn-out delivery tip and (for larger volumes) a centrally placed bulb. It may be filled by applied suction or by capillarity (according to its bore), and emptied by drainage or by applied pressure. **2** to transfer or deliver a (usually measured) volume of liquid with a **pipette** (def. 1). —**pipettable** *adj.*

pipettor any device for the rapid, repetitive dispensing of a predetermined volume of a liquid.

pipsyl *symbol*: Ips; *p*-iodophenylsulfonyl; I-C_6H_4-SO_2; a chemical group with which free amino groups may be derivatized by reaction with pipsyl chloride, *p*-iodophenylsulfonyl chloride. *Compare* **tosyl**.

pipsylate to convert (an amino compound) to a **pipsyl** derivative. —**pipsylation** *n.*

Pirani gauge an electric gauge for low gas pressures that functions over the range 10^{-2} to 10^{-5} mm Hg. It depends on the principle that an electrically heated wire loses heat by conductivity, and thus varies in electric resistance, to an extent empirically dependent on the pressure of the surrounding gas.

PIR-PSD *abbr. for* protein identification resource-protein sequence database; *see* **sequence database**.

piscine of, relating to, or being a fish.

pitch height (of a helix) *symbol*: *p*; the linear displacement along the axis of a helix corresponding to one complete turn of the helix.

PIT any of three closely related homeobox genes for positive transcription factors (Pit). Pit-1 activates the genes for somatotropin, prolactin, and the β subunit of thyrotropin, binding specifically to the consensus sequence 5′-TAAAT-3′. It contains a **POU domain** and contributes to the naming of the domain. Deficiency of Pit-1 leads to a syndrome caused by combined lack of somatotropin, prolactin, and thyrotropin. PITX2 (271 amino acids) and PITX3 (302 amino acids) are homologous with Pit-1. Mutations in either result in ocular defects.

Pitocin *a proprietary name for* (a solution of) **oxytocin**.

Pitressin *a proprietary name for* (a solution of) **vasopressin**.

pituitary 1 pertaining to or produced by the **pituitary gland**. **2** the pituitary gland.

pituitary adenylate cyclase-activating polypeptide *see* **PACAP**.

pituitary function *see* **combined test of pituitary function**.

pituitary gland *or* **hypophysis (cerebri)** the most important endocrine gland of vertebrates. It is situated below the brain, to which it is attached by a stalk, and measures about 8 mm by 12 mm in an adult human. It consists of two parts: the anterior lobe, or **adenohypophysis**, and the posterior lobe, or **neurohypophysis**; both lobes secrete a range of hormones.

Pituitrin *a proprietary name for* an aqueous extract of bovine neurohypophysis; it contains both oxytocin and vasopressin.

PIVKA *abbr. for* protein induced by vitamin K absence; examples are the abnormal proteins produced in vitamin K-deficient animals, corresponding to coagulation factors II, VII, IX, and X (*see* **blood**

coagulation) in which some glutamate residues have not been carboxylated to γ-carboxyglutamate residues.

pixel one of the very small units that make up the image on a cathode-ray tube. [From 'pix' (i.e. pictures) + el(ement).]

p*K* *symbol for* the decadic logarithm of the reciprocal of a (thermodynamic) dissociation constant, K; i.e.

$$pK = \log 1/K = -\log_{10}K.$$

The type of constant may be indicated by a subscript: e.g. **pK_a**, a dissociation constant of an acid; **pK_b**, a dissociation constant of a base; **pK_2**, a second dissociation constant. For the dissociation of an acid, HA, to its ions, H^+ and A^-,

$$K = [H^+][A^-]/[HA].$$

Thus when $[A^-] = [HA]$, i.e. when the acid is half-dissociated, $K = [H^+]$, and hence pK is then equal to pH. Formerly symbolized as p_k. *See also* **group p*K*, Henderson–Hasselbalch equation**, **molecular p*K*, titration p*K***.

p*K*′ *symbol for* the decadic logarithm of the reciprocal of an apparent (concentration) dissociation constant, K'.

pK_2 *see* **p*K***.

pK_a *see* **p*K***.

pK_b *see* **p*K***.

pK_w *symbol for* the decadic logarithm of the reciprocal of the ion product of water, K_w.

PK *(in clinical chemistry) abbr. for* pyruvate kinase.

PKB *abbr. for* **protein kinase B**.

PKC *abbr. for* protein kinase C.

PKD 1 repeat a protein sequence (80–90 amino acids) that occurs 15 times in the N-terminal extracellular region of polycystin 1. It forms seven beta strands organized in two sheets with a well-defined hydrophobic core.

PKR *abbr. for* RNA-activated protein kinase; a protein kinase that contains two dsRNA-binding motifs and is activated by binding dsRNA and by homodimerization. It is induced by interferon, and it phosphorylates the α subunit of the initiation factor eIF-2, the regulatory IκB subunit of the NF-κB transcription factor, and the tumour suppressor p53.

PKU *abbr. for* phenylketonuria.

PL *abbr. for* **1** placental lactogen (i.e. **choriomammotropin**). **2** pyridoxal.

placebo (*pl.* **placebos** *or* **placeboes**) a tablet, capsule, or liquid medicine devoid of any specific pharmacological activity, but appearing identical to a preparation containing a biologically active substance. Placebos are used in human medicine for their psychological effects, and as controls in experimental therapeutics for elucidating the clinical actions of a drug.

placenta (*pl.* **placentas** *or* **placentae**) a highly vascularized organ within the uterus of a pregnant animal by which the embryo is attached to the uterine wall and through which the embryo can exchange solutes with the maternal circulation. The placenta also functions as an endocrine gland, secreting *inter alia* **choriogonadotropin**, **choriomammotropin**, and certain steroid hormones. —**placental** *adj.*

placental lactogen *abbr.*: PL; *an alternative name for* **choriomammotropin**.

placental ribonuclease inhibitor *or* **placental ribonuclease/angiogenin inhibitor** a 15 kDa protein with 15 leucine-rich repeats found in mammalian tissues and conveniently extracted from placenta. It binds with a very high affinity to many RNases thereby inhibiting them. It is used in experiments with purified RNA to minimize degradation by contaminating RNases. It also inhibits angiogenin.

plakoglobin *or* **desmoplakin III** a protein of **cell junctions**. It is thought to play a central role in the function of desmosomes and intermediate junctions.

planar **1** of, or pertaining to, a **plane**. **2** lying in one plane; flat.

planchet *or* **planchette** a small, shallow dish used to contain a specimen for determination of its radioactivity with an end-window or windowless counter.

Planck constant *symbol*: h; a fundamental constant of proportionality between the frequency, ν, of electromagnetic radiation and the energy, E, of a quantum of the radiation; i.e. $h = E/\nu$. It has a value of $6.626\,075\,5(40) \times 10^{-34}$ J s. [After Max Karl Ernst Ludwig Planck (1858–1947), German physicist.]

plane **1** a surface in which a straight line joining any two contained points lies entirely within the surface; a flat surface. **2** an imaginary surface of such a kind within a real structure or lying conceptually in space. **3** lying wholly in one plane; flat or level; planar.

plane of polarization *or* **plane of polarisation** (of linearly **polarized light** or other electromagnetic radiation) the plane containing the electric vectors of the vibrations.

plane of symmetry a plane through a three-dimensional structure, e.g. a crystal or molecule, that divides the object into two parts that are mirror images of each other.

plane-polarized *or* **plane-polarised** *an alternative term for* **linearly polarized**. *See* **polarized light**.

planimeter a mechanical integrating instrument for measuring the area of an irregular plane figure. It consists of a moveable tracing arm, which is made to follow the boundary of the figure, and a dial on which the arm's motion is recorded. —**planimetry** *n.*

plankton *the collective term for* the small or microscopic plants (**phytoplankton**) and animals (**zooplankton**), that drift freely in the surface waters of lakes, seas, and oceans.

plant any organism of the kingdom Plantae. Plants are characterized by their ability to effect photosynthesis and the possession of rigid cell walls that contain cellulose.

plant cell-wall protein any of four major classes of proteins that form networks in plant cell walls. They are: **hydroxyproline-rich glycoproteins** (HPRG); **proline-rich proteins** (PRP); **glycine-rich proteins** (GRP); and arabinogalactan proteins (AGP).

planteobiose the disaccharide, 6-*O*-α-D-galactopyranosyl-D-fructose; a unit of the trisaccharide **planteose**.



α-anomer

planteose *O*-α-D-galactopyranosyl-(1→6)-*O*-β-D-fructofuranosyl-(2→1)-α-D-glucopyranoside; a trisaccharide isolated from defatted seeds of *Plantago ovata*.

plant glucosyltransferase *an alternative name for* **D-enzyme.**

plant hormone *an alternative term for* **phytohormone**.

plantibody a human antibody produced by genetically engineered tobacco plants.

plaque **1** any small disk-like object, patch, or zone. **2** a macroscopic or microscopic rounded clear zone in a layer of cells or bacterial lawn that results from the killing or lysis of adjacent cells by the action of a virus or other agent. **3 a** (a patch of) fibrous or lipid material on the inner surface of an artery. **b** an area of tissue degeneration with distinctive histological features characteristic of certain (especially neurological) diseases, e.g. **kuru**, **multiple sclerosis**. **c** a deposit of β-amyloid, numbers of which are typically found in the brains of patients with Alzheimer's disease. **4** (a patch of) deposit closely adherent to the surface of a tooth that contains a mixed microbial flora and is composed largely of extracellular bacterial polysaccharide.

plaque-forming unit *see* **pfu**.

plaque-lift a technique used in recombinant DNA technology for screening DNA libraries constructed in bacteriophages such as lambda. Plaques of recombinant phage are allowed to form on a lawn of bacteria spread on a nutrient agar plate. Then a nitrocellulose (or nylon) membrane is pressed against the surface thereby adsorbing phage from the plaques in a replica pattern. The membrane can then be screened with a DNA probe, or antibody for an expressed protein if appropriate, and the desired clones identified.

+plasia *or* **+plasy** *comb. form* indicating development or growth. —**+plastic** *adj.*

plasm+ *a variant form of* **plasmo+** (before a vowel).

+plasm *comb. form* denoting the colloidal material of which living cells are composed. —**+plasmic** *adj.*

plasma 1 the proteinaceous fluid in which the cells of blood or lymph are suspended; the meaning is sometimes extended to include also the analogous fluid in which the fat droplets of milk are suspended. *See also* **blood plasma**. **2** *a less common word for* **protoplasm**. **3** *(in physics)* any region of highly ionized gas (as in a gas-discharge tube, a hot flame, or a thermonuclear reaction) containing approximately equal numbers of electrons and positively charged ions. It differs from ordinary gas in being a good conductor of electricity and being affected by a magnetic field. —**plasmatic** *or* **plasmic** *adj.*

plasma albumin *an alternative name for* **serum albumin**.

plasma cell *or* **plasmacyte** *or* **plasmocyte** a fully mature antibody-secreting B lymphocyte, found in lymphoid tissue and in connective tissue liable to encounter foreign material. It has an eccentrically placed nucleus, basophilic cytoplasm, and an unusually large amount of rough endoplasmic reticulum.

plasma cholesterol *(in medical biochemistry)* the concentration of cholesterol in blood plasma. In human blood, cholesterol occurs as a component of all plasma lipoproteins, but especially **very-low-density lipoprotein**, **low-density lipoprotein**, and **high-density lipoprotein**. A correlation exists between the level of plasma cholesterol and the occurrence of **atheroma** and heart attacks; this is associated with the role of low-density lipoprotein, which has the highest concentration of cholesterol and distributes cholesterol to the tissues. However, the ratio of high-density lipoprotein cholesterol to low-density lipoprotein cholesterol must be taken into account, as the former is thought to have a protective function in cycling cholesterol from peripheral tissues back to the liver. The circulating level of cholesterol may be altered by diabetes, thyroid hormone imbalance, diet, and drugs. It is thought that the level of circulating total cholesterol should be maintained below about 5 mmol L^{-1}.

plasma clearance *see* **clearance** (def. 2).

plasmacyte *an alternative name for* **plasma cell**.

plasmacytoma a tumour of plasma cells; most such tumours secrete myeloma proteins belonging to the same category as monoclonal antibodies.

plasma kallikrein *see* **kallikrein**.

plasmalemma *an alternative term for* **cell membrane**.

plasma lipid transfer protein a plasma protein that mediates transfer and exchange of lipids (i.e phospholipid, cholesterol ester, triacylglycerol) between plasma lipoproteins. **Phospholipid transfer protein** and **cholesterol ester transfer protein** belong to this group; they are homologous with each other and with **lipopolysaccharide-binding protein**.

plasmalogen any glycerophospholipid in which the glycerol moiety bears an *O*-(1-alkenyl) group at position 1. The term embraces **plasmenic acid**.

plasmalogen synthase EC 2.3.1.25; an enzyme that catalyses the formation of plasmenylcholine from acyl-CoA and 1-*O*-alk-1-enyl-*sn*-glycero-3-phosphocholine with release of CoA.

plasma membrane *an alternative term for* **cell membrane**.

plasmanic acid a derivative of *sn*-glycerol 3-phosphate in which the glycerol moiety is etherified with an alkyl (or alkenyl other than 1-alkenyl) group at position 1 and esterified with an acyl group at position 2; i.e. any 2-acyl-1-*O*-R-*sn*-glycerol 3-phosphate where R = alkyl or *n*-alkenyl when $n > 1$. *Compare* **plasmenic acid**.

plasmanyl *the trivial name for* any phosphoric acyl group derived from a **plasmanic acid**. The term is useful for naming phosphoric diesters of plasmanic acid, e.g. plasmanylethanolamine, 2-acyl-1-*O*-alkyl-*sn*-glycerol 3-phosphoethanolamine. *Compare* **plasmenyl**.

plasmapheresis *or* **plasmaphoresis** *or* **plasmapharesis** *or* **plasmaphaeresis** a technique for decreasing the protein content of blood plasma circulating in the body by withdrawing blood, separating the cells by centrifugation, and then returning them to the circulation as a suspension in a suitable protein-free medium.

plasma protein 1 any of the numerous proteins present in or derived from blood plasma. **2** such proteins collectively. In mammalian plasma the concentration of plasma protein is 60–80 g L^{-1}; of this, ≈60% is serum albumin, ≈18% is immunoglobulin G, ≈9% is β_1-lipoprotein, and ≈4% is fibrinogen.

plasma thromboplastin antecedent *an alternative name for* factor XI; *see* **blood coagulation**.

plasmenic acid a derivative of *sn*-glycerol 3-phosphate in which the glycerol moiety is etherified with a 1-alkenyl group at position 1 and esterified with an acyl group at position 2; i.e. any 2-acyl-1-*O*-(1-alkenyl)-*sn*-glycerol 3-phosphate. *Compare* **plasmanic acid**, **plasmalogen**. [Contraction of plasmalogenic acid.]

plasmenyl *or (formerly)* **phosphatidal** *the trivial name for* any phosphoric acyl group derived from a **plasmenic acid**. The term is useful for naming phosphoric diesters of plasmenic acid, e.g. plasmenylethanolamine, 2-acyl-1-*O*-(1-alkenyl)-*sn*-glycerol 3-phosphoethanolamine. *Compare* **plasmanyl**.

plasmid strictly any extrachromosomal genetic element; however, mitochondrial and chloroplast DNA, yeast killer, and other cases are commonly excluded, hence the term plasmid generally refers to an extrachromosomal covalently continuous double-stranded DNA molecule that occurs in bacteria and (rarely) other microorganisms. Natural plasmids vary from <5 kb to over 100 kb in size. They are classified in a number of different ways: the **copy number** describes the ratio of plasmid/chromosome molecules, and is greatly influenced by the nature of the origin of replication. Plasmids under stringent control have a copy number of one and those under relaxed control may have copy numbers of hundreds per cell. The **host range** describes the variety of species that can act as host (*see also* **incompatibility**). Plasmids capable of transfer are said to be conjugal; wide host-range, conjugal plasmids are described as promiscuous. Plasmid genes include drug resistance (**resistance plasmids**), genes for catabolic enzymes (catabolic plasmids), genes for antibiotic synthesis, and genes for toxin production. Plasmids are popular choices for **cloning vectors**. and is greatly influenced by the nature of the origin of replication. Plasmids under stringent control have a copy number of one and those under relaxed control may have copy numbers of hundreds per cell. The **host range** describes the variety of species that can act as host (*see also* **incompatibility**). Plasmids capable of transfer are said to be conjugal; wide-host-range conjugal plasmids are described as promiscuous. Plasmid genes include drug resistance (**resistance plasmids**), genes for catabolic enzymes (**catabolic plasmids**), genes for antibiotic synthesis, and genes for toxin production. Plasmids are popular choices for **cloning vectors**.

plasmid chimera a hybrid DNA molecule that has been constructed *in vitro* by joining fragments of separate plasmids and that forms a new, biologically functional replicon when inserted into a cell.

plasmid curing the elimination of a plasmid from a cell culture by treatment with **Acridine Orange** at a concentration insufficient to inhibit chromosome replication but sufficient to inhibit plasmid replication.

plasmid engineering genetic engineering when a plasmid is used as a cloning vector.

plasmid incompatibility *see* **incompatibility**.

plasmid segregation *see* **segregation** (def. 3).

plasmid transconjugant *see* **transconjugant**.

plasmid vector *see* **cloning vector**.

plasmin *or* **fibrinolysin** *or* **fibrinase** EC 3.4.21.7; a serine proteinase that converts the insoluble fibrin of a blood clot into soluble products. It is formed from **plasminogen** by proteolysis, the heavier A chain being derived from the N-terminal part of plasminogen and linked by a disulfide bond with the lighter B chain, which contains the enzymically active site. It exhibits preferential cleavage at Lys-|-Xaa > Arg-|-Xaa bonds, with a higher selectivity than trypsin. *See also* **blood coagulation**.

plasminogen *or* **profibrinolysin** a ≈90 kDa, single-polypeptide glycoprotein found in blood plasma. It is the inactive precursor of **plasmin**, into which it may be converted by hydrolysis of one peptide bond (Arg^{560}-|-Val^{561}) brought about, e.g., by the action of **plasminogen activator** or **streptokinase**. *See also* **blood coagulation**.

plasminogen activator any serine proteinase that converts **plas-**

minogen into plasmin. Numerous variants occur in different tissues, and can be classified immunologically into **urokinase-type** and **tissue-type** plasminogen activators (*abbr.*: UPA and TPA, respectively). Example 1, urokinase-type (EC 3.4.21.73); this cleaves the Arg^{560}-|-Val^{561} bond in plasminogen to form plasmin. It is found in urine, and is used clinically for therapy of thrombotic disorders. Example 2, tissue-type (EC 3.4.21.68); this cleaves the Arg^{560}-|-Val^{561} bond in plasminogen to form plasmin. Cleavage after Arg^{310} by plasmin or trypsin results in a two-chain form of the molecule; the two halves are held together by one or more disulfide bonds. TPA is active in tissue remodelling and destruction, in fibrinolysis, and in cell migration. Example 3, found in certain pathogens, is the activator EC 3.4.21.–, *also known as* coagulase/fibrinolysin precursor; it is a homopentamer occurring in the outer membrane. *See also* **urokinase**.

plasmo+ *or (before a vowel)* **plasm+** *comb. form* denoting of, pertaining to, related to, or derived from plasma.

plasmocyte *an alternative name for* **plasma cell**.

plasmodesma (*pl.* **plasmodesmata** *or* **plasmodesmas**) a fine cytoplasmic channel, found in all higher plants, that connects the cytoplasm of one cell to that of an adjacent cell. It is a roughly cylindrical, membrane-lined channel of diameter 20–40 nm, through the centre of which runs a narrower cylindrical **desmotubule**; the latter appears to be continuous with elements of the endoplasmic reticulum membrane of each of the connected cells. The function of plasmodesmata appears to be similar to that of **gap junctions** between animal cells. They permit passage of molecules of M_r less than about 800.

plasmodium (*pl.* **plasmodia**) **1** any member of the protozoan genus *Plasmodium*. Certain species parasitize humans causing malaria, while others parasitize other mammals. Their life cycle is complex, requiring, at different stages, an insect host and a mammalian host. **2** the motile multinucleate mass of protoplasm formed by the true **slime moulds** (Myxomycetes).

plasmolipin a protein of the myelin and lymphocyte (MAL) family of **tetraspanins**. It may be involved in vesicle trafficking and membrane linking.

plasmolysis temporary shrinkage of the protoplasm of a plant or bacterial cell away from the cell wall, caused by the withdrawal of water from the cell. —**plasmolyse** *vb.*

plasmon 1 the sum total of the extrachromosomal hereditary determinants in a cell. **2** in physics, a quasi-particle resulting from the quantization of plasma oscillations in a conducting material such as a metal. A surface plasmon occurs at the interface of a metal with material such as a protein, and interacts strongly with light. Plasmons are exploited as a way of observing binding of macromolecules to metal surfaces in **surface plasmon resonance**.

plasmoptysis the localized extrusion of cytoplasm through the cell wall of a bacterium.

plasmosome *an alternative name for* **nucleolus**.

+plast *comb. form* denoting an organized subcellular particle from a living organism.

plastein a gel that may be formed on treating a partial hydrolysate of a protein with an endopeptidase. It was once thought to be a demonstration of the synthetic capability of proteases.

plastic 1 any of a large and diverse group of polymeric materials, either synthetic or semisynthetic, that may be obtained following moulding, extrusion, etc. at a stage in their manufacture when soft or liquid. **2** made of or containing plastic; of the nature of plastic. **3** (of a material) capable of being formed or moulded. **4** *(in biology)* of or pertaining to an ability to adapt to the environment; able to change, develop, or grow. —**plasticity** *n.*

+plastic *see* **+plasia**.

plasticity-related gene-1 *see* ***PRG-1***.

plasticizer *or* **plasticiser** any substance added to another to render the latter less brittle and/or more mouldable and flexible.

plastid any of the organelles found in the cytoplasm of eukaryotic plants that contain DNA, are bounded by a double membrane, and develop from a common type, the **proplastid**. Plastids also contain pigments and/or storage materials. They include **aleuroplasts**, **amyloplasts**, **chloroplasts**, **chromoplasts**, **elaioplasts**, and etioplasts.

plastidome the total complement of **plastids** of a cell.

plastocyanin a soluble protein of eukaryotic plants that contains one atom of copper per molecule, and is blue in its oxidized form. It occurs in the chloroplast at a molar concentration equal to that of P700, where it functions as a one-electron carrier (E'_o = +0.43 V) between the cytochrome b_6–f and P700 of photosystem I. It is loosely bound to the inner thylakoid membrane surface.

plastogene any of the hereditary determinants of plastids.

plastoglobuli droplets, 50–220 nm in diameter, that occur close to thylakoid membranes in chloroplasts of senescing leaves. Rich in lipids, particularly **plastoquinone**, they are particularly numerous when thylakoids are disrupting, and appear to be liberated therefrom.

plastome *or* **plastom** the total complement of the **plastogenes** of a cell.

plastoquinol *abbr.*: PQH$_2$; any hydroquinone derived from the corresponding plastoquinone by a two-electron reduction.

plastoquinone *abbr.*: PQ; any 2,3-dimethyl-5-multiprenylbenzoquinone; plastoquinones occur mainly in plants; intact prenyl units in the side chain (commonly nine in the plastoquinone of higher plants) may be designated by a suffixed numeral, e.g. plastoquinone-9 (*abbr.*: PQ-9). The plastoquinone–plastoquinol redox system ($E'_o \approx$ +0.1 V) functions in the electron-transport system, transferring electrons from photosystem II to the cytochrome b_6–f complex.

plate 1 *(in biology)* a Petri dish or other shallow vessel containing so-called solid or semisolid culture medium; a culture grown on this. **2** *(in chemistry)* any one of the horizontal perforated plates that comprise the fractionating component of a **plate column** for fractional distillation, or the theoretical equivalent of such a plate. *See also* **theoretical plate**. **3** *(in biology) or* **plate out** to inoculate a **plate** (def. 1) with microbial or other cells, or with material (suspected of) containing such cells. **4** to coat (a metal or other substrate) with a thin layer of (other) metal.

plateau (*pl.* **plateaux** *or* **plateaus**) **1** a part of a graph in which the value of the ordinate shows little or no change with increasing value of the abscissa. **2** a period of (relative) stability in the course of a progression. **3** to reach or pass through a plateau.

plate column *see* **plate** (def. 2).

plate height *see* **height equivalent to a theoretical plate**.

platelet *or* **thrombocyte** the smallest of the blood cells. It is an anucleate biconvex disk, 2–3 µm in diameter, formed by division of the cytoplasm of a megakaryocyte. Platelets have an exterior coat rich in glycoprotein, a normal cell membrane, and a well-developed system of microtubules some of which are arranged as an equatorial ring. Their main functions are in hemostasis, by (1) adhering to damaged blood vessels and aggregating to form a plug; (2) releasing various vasoconstrictive agonists, e.g. **epinephrine**, **serotonin**, and **thromboxane A$_2$**; (3) activating or binding certain coagulation factors; and (4) releasing factor XIII, **platelet-derived growth factor**, and **platelet factor IV**; blood clotting then occurs around the aggregated platelets. *See* **blood coagulation**.

platelet-activating factor *abbr.*: PAF *or* PAF-acether; 1-*O*-alkyl-2-acetyl-*sn*-glycerol 3-phosphocholine, where 'alkyl' may be hexadecyl or octadecyl; a potent general inflammatory mediator released from a variety of cells in response to a number of stimuli, and causing aggregation of platelets, activation of polymorphonuclear leukocytes, monocytes, and macrophages, mediation of increased vascular permeation, hypotension, decreased cardiac output, and stimulation of uterine contraction. It is synthesized in the cell in either of two ways: (1) from 1-*O*-alkyl-*sn*-glycerol-3-phosphate by addition of an acetyl group and release of phosphate, forming 1-alkyl-2-acetyl-*sn*-glycerol, which then reacts with CDPcholine to form PAF and CMP; or (2) by a remodelling pathway, in which the 2-fatty acyl group is removed from a phosphatidylcholine by phospholipase A$_2$ and replaced with acetyl. A number of analogues act as PAF agonists, e.g. the stable analogues in which the 2-acetyl group is replaced by an ethyl, methyl, or benzyl ether group; replacement of the choline moiety by (*N*-methylpyrrolidino)-ethanolamine greatly increases its effect. PAF antagonists include gossypol, hexanolamino-PAF, *bis*(methylthio)gliotoxin, and 2,5-*bis*(3,4,5-trimethoxyphenyl)-1,3-dioxolane.

platelet-activating factor acetylhydrolase (*abbr.*: PAF-AH) *an alternative name for* **lipoprotein-associated phospholipase A2**.

platelet basic protein precursor *abbr.*: PBP; the precursor of several peptides generated by alternative processing. For example, the human protein contains a signal, platelet basic protein, **LA-PF4**, **β-thromboglobulin** and **NAP-2**.

platelet-derived endothelial cell growth factor *abbr.*: PD-ECGF; a **cytokine** produced by platelets, fibroblasts, and smooth muscle cells. It is a monomer of 471 amino acids. A related protein, **gliostatin**, is produced by astrocytes. Both proteins stimulate growth of endothelial cells *in vitro* and angiogenesis *in vivo*, and promote survival and differentiation of CNS neurons; they inhibit the growth of astrocytes and glial cells. PD-ECGF proteins initiate thymidine phosphorylase activity.

platelet-derived growth factor *abbr.*: PDGF; a **cytokine** of ~30 kDa, composed of two disulfide-bonded polypeptide chains, denoted A and B, which are non-identical but homologous. It is believed that human PDGF is an AB heterodimer, but pig PDGF is a homodimer of B chains. PDGF is a potent mitogen for cells of mesenchymal origin (endothelial cells, epithelial cells, some fibroblasts, smooth muscle cells) and for glial cells; it has chemotactic properties. It is released by platelets on wounding, and stimulates nearby cells to grow and repair the wound; it is also produced by endothelial cells, fibroblasts, monocytes, macrophages, smooth muscle cells, and neurons. PDGF-like proteins are produced by numerous human tumour cell lines, and the B chain is almost identical to part of the transforming protein produced by simian sarcoma virus (*see* **sis**). Homodimers of A and B chains (both can bind to the receptor) are implicated in transformation processes. *See also* **platelet-derived growth factor receptor**.

platelet-derived growth factor receptor *or* **PDGF receptor** a **tyrosine kinase** dimer, of αα, ββ, or αβ subunits, belonging to the immunoglobulin superfamily. It is a transmembrane cell surface receptor, the intracellular kinase sequence being split by an inserted sequence. Binding of platelet-derived growth factor (PDGF) stimulates tyrosine-kinase activity, which leads to phosphorylation of tyrosine residues.

platelet endothelial cell adhesion molecule *see* **PECAM**.

platelet factor IV a polypeptide secreted by platelets when they adhere at a site of injury. It is a **chemokine** that binds heparin strongly, and is a powerful attractant for neutrophils and monocytes.

platform protein *an alternative name for* **molecular beacon**.

plating *see* **plate** (def. 3, 4).

platysome *(sometimes)* the core particle of a **nucleosome**.

PLC *abbr. for* **1** preparative-layer chromatography. **2** phospholipase C; *see* **phospholipase**.

pleated sheet *see* **beta-pleated sheet**.

pleckstrin *other name*: platelet p47 protein; a platelet protein that is the major substrate for Ser/Thr phosphorylation by protein kinase C. Its function is not known. *See also* **pleckstrin homology domain**.

pleckstrin homology domain *abbr.*: PH domain; a domain, first noted in the platelet protein **pleckstrin**, containing about 100 residues. Its function is unknown, but it has since been found in many (more than 60) proteins, especially those associated with intracellular signal transduction downstream of cell-surface receptors. It binds inositol-1,4,5-triphosphate.

plectin a coiled-coil protein that links intermediate filaments to hemidesmosomes. It is expressed in epidermis and skeletal muscle and is very similar in sequence to bullous pemphigoid antigen 1e. Null mutations in the gene are associated with epidermolysis bullosa with muscular dystrophy.

plectonemic coiling a type of coiling of a double-stranded helix in which the two strands are intertwined, i.e. they may not be separated without uncoiling.

pleiotropin *or* **pleiotrophin** *other name*: heparin-binding growth factor 8; a heparin-binding mitogenic protein with neurite extension activity for osteoblasts and brain cells.

pleiotropism *or* **pleiotropy** the phenomenon in which a single gene is responsible for producing multiple, distinct, apparently unrelated phenotypic effects; an instance of such a phenomenon. The meaning is sometimes extended to include multiple, distinct, unrelated actions or effects of a single polypeptide agonist. —**pleiotropic** *adj.*

pleiotypic relating to the process by which a single stimulus to a living cell elicits multiple, unrelated responses.

pleomorphism *or* **pleomorphy** the quality of occurring in, or exhibiting more than one distinct form. *Compare* **polymorphism**. —**pleomorphic** *adj.*

pleuropneumonia-like organism *abbr.*: PPLO; *an obsolete name for* **mycoplasma** or mollicute.

Plexiglas *or* **Plexiglass** *a proprietary name for* **poly(methyl methacrylate)**.

plexin any of a family of transmembrane proteins that form part of **semaphorin** receptor complexes. Their intracellular region binds directly to **RhoGTPases** and to Rho guanine nucleotide-exchange factors. Plexins are widespread in embryonal and adult tissues. They regulate axonal pathfinding in the developing nervous system. In *Drosophila*, plexin A is a receptor for semaphorin 1A. In vertebrates, plexin A is a receptor for secreted semaphorin 3, whereas plexins B, C, and D bind other semaphorins. Their extracellular N-terminal ≈500 residues are homologous with the same region of semaphorin and hepatocyte growth factor receptors, but their intracellular ≈600 residues show no known homology and might bind a cytosolic protein-tyrosine kinase.

PLI *abbr. for* pulsed laser interferometry.

+ploid *adj. and n. comb. form* indicating the specific multiple of homologous sets of chromosomes in cell. —**+ploidy** *n.*

ploidy the number of homologous sets of chromosomes in a cell, or in each cell of an organism.

P-loop *see* **Walker motif**.

plot **1** a diagram showing the relationship between two or more variables. **2** to construct such a plot.

plotter an instrument for automatically making a **plot** (def. 1).

PLP *abbr. for* **1** pyridoxal phosphate. **2** proteolipid protein; *see* **myelin proteins**.

PLTP *abbr. for* phospholipid transfer protein.

plug flow a type of flow of fluids in which there is no mixing in the direction of flow.

plumper a disposable, nonscratching plastic device for adding a small volume (5–50 μL) of a reagent to, and mixing it with, a liquid in a small container such as a spectrophotometer cuvette.

pluripoietin granulocyte colony stimulating factor (G-CSF) precursor. Pluripoietin α is a second human hemopoietic colony stimulating factor produced by the human bladder carcinoma cell line 5637. *See* **colony stimulating factor**.

pluripotent **1** (of a biomolecule) capable of being converted (biologically) into more than one active product. **2** (of a cell) capable of differentiating into more than one alternative type of mature cell.

plus and minus screening a strategy used previously for isolating genes for gene products that are present in one type of cell and absent in another. It involves comparing the results of plaque or **colony hybridization** of replicate plates of a cDNA clone library from the first cell type with cDNA probes derived from the mRNAs of both cell types used independently. Any plaque or colony that hybridizes to one probe and not the other is a candidate of interest. The objective can now be achieved more conveniently using subtractive PCR methods.

plus end the end of a microtubule or actin filament at which addition of monomers occurs most readily; the ‘fast-growing’ end of a microtubule or actin filament. The plus end of an actin filament is also known as the **barbed end**.

plus strand **1** the parental polynucleotide strand in bacteriophages whose genomes consist of duplex RNA. It is the template used for the production of the complementary minus strand. **2** virus-specified messenger RNA, or any given strand of nucleic acid (RNA or DNA) whose base sequence is equivalent to that of virus-specified mRNA. Any strand having a base sequence complementary to virus-specified mRNA is described as a minus strand. **3** *(sometimes) an alternative term for* **coding strand** (of genomic duplex DNA). *Compare* **minus strand**.

PLZF *abbr. for* promyelocytic leukemia zinc finger protein; a transcription factor that is expressed in many tissues during development and may be involved in hemopoietic cell differentiation. It contains an N-terminal domain for protein–protein interaction and nine C-terminal zinc fingers, Krüppel-type (i.e. C_2H_2). The N-terminal domain binds the nuclear receptors RAR and RXR and inhibits their binding to DNA. Translocation of the PLZF gene at

11q23.1 with that for RARα results in a PLZF-RARα fusion protein in some acute promyelocytic leukemia patients.

pM *or* **pm** *symbol for* picomolar.

Pm *symbol for* promethium.

PMA *abbr. for* phorbol 12-myristate 13-acetate; *see* **phorbol ester**.

***Pma*CI** a type 2 **restriction endonuclease**; recognition sequence: CAC↑GTG.

pMAL vector any of a range of plasmid vectors used for the expression of foreign proteins in *E. coli*. Genes are cloned downstream from the gene for the *E. coli* maltose binding protein (MBP) *malE* and in the same reading frame. The resulting fusion protein can be purified on columns of cross-linked amylose. The leader sequence of MalE facilitates export to the periplasm. A short sequence motif at the point of fusion is recognized by factor Xa, which can be used to cleave the protein of interest from MBP.

pMB1 a plasmid replicon widely used in its original or modified form in the construction of synthetic plasmids used in molecular biology. Plasmids with pMB1 have copy numbers of 15–30.

pMC9 a plasmid encoding the *lac* repressor I^q and the gene for resistance to ampicillin. It is carried by *E. coli* strains such as Y1090 to control the expression of foreign genes cloned in bacteriophage lambda vectors and transcribed from *lac* or *tac* promoters.

PMF *abbr. for* protonmotive force, *or sometimes (facetiously), after its discoverer,* Peter **Mitchell** force. [After Peter Dennis Mitchell (1920–92), British biochemist.]

PML *abbr. for* promyelocytic leukemia protein; a protein that occurs free in nucleoplasm and in association with other proteins in **nuclear bodies**. The gene at 15q21 encodes a protein that contains a RING finger and a coiled-coil domain, and resembles **COP1** in structure, cell distribution, and dynamics. A translocation between the PML gene and the RARα gene produces the fusion protein PML-RARα and disrupts the nuclear bodies. Cytoplasmic aggregates of PML occur in virally infected, neoplastic, or inflamed tissue.

PML nuclear body *see* **nuclear body**.

PMN *abbr. for* **1** pyridine mononucleotide. **2** polymorphonuclear (leukocyte).

pmol *symbol for* picomole.

PMR *or* **pmr** *abbr. for* proton magnetic resonance; *see* **nuclear magnetic resonance spectroscopy**.

PMS *abbr. for* **1** phenazine methosulfate. **2** pregnant mares' serum.

PMSF *abbr. for* phenylmethylsulfonyl fluoride.

PMSG *abbr. for* pregnant mares' serum gonadotropin.

PN-1 *see* **nexin 1**.

PNA *abbr. for* pentose nucleic acid (i.e. ribonucleic acid).

PNAD *abbr. for* protein NH_2-terminal arginine deamidase; an enzyme, discovered in the pig, that catalyses deamidation of N-terminal arginine residues in peptides.

pneumo+ *or* **pneumono+** *or (before a vowel)* **pneum+** *or* **pneumon+** *comb. form* of or pertaining to a lung or lungs; respiratory.

pneumococcus (*pl.* **pneumococci**) any strain of bacterium belonging to the species *Streptococcus pneumoniae*. —**pneumococcal** *adj.*

pneumococcus capsule swelling reaction *an alternative name for* **Quellung reaction**.

p[NH]ppA *symbol for* adenosine 5′-[β,γ-imido]triphosphate (alternative to Ado*PP*[NH]*P*).

PNK *abbr. for* polynucleotide kinase.

PNMT *abbr. for* phenylethanolamine *N*-methyltransferase.

PNP *abbr. for* **1** *para*-nitrophenol. **2** purine-nucleoside phosphorylase.

Po *symbol for* polonium.

pocket *(in molecular biology)* a cavity or hollow in a three-dimensional structure, e.g. a substrate pocket of an enzyme.

podocalyxin a sialated glycoprotein that is prominently expressed on renal glomerular epithelial cells and found in patients with glomerulonephritis.

podophyllotoxin a **lignan** found in the May apple, or American mandrake (*Podophyllum peltatum*). It is known in folk medicine as a cathartic and poison, and is useful in topical treatment of warts, including venereal warts; it may have antiviral action. In mammalian cells it inhibits assembly of tubulin into microtubules, and also nucleoside transport. It is used in the synthesis of **Etoposide** and **Teniposide**.



podophyllotoxin

+poiesis *noun comb. form* indicating an act or process of making (something specified), e.g. erythropoiesis, hemopoiesis. —**+poietic** *adj.*

poikilo+ *comb. form* indicating various, variable.

poikilocyte an erythrocyte that is distorted in shape and usually larger than normal, found in the blood of persons with pernicious anemia and some other anemias.

poikilosmotic describing an organism whose internal osmotic pressure varies with that of its environment. *Compare* **homoiosmotic**.

poikilothermic *or* **poikilothermal** describing an organism whose body temperature varies with that of the environment. *Compare* **homoiothermic**. —**poikilotherm** *n.*

point **1** *(in mathematics)* **a** any dimensionless geometric element whose position in space is defined by its coordinates. **b** a location or position, especially on a diagram, graph, etc. **2** a decimal point. **3** a **point of inflection**.

point accepted mutation *symbol*: PAM; a unit that quantifies the amount of evolutionary change in a protein sequence. 1PAM marks the evolutionary distance in which 1% of amino acids in a protein sequence have changed; 250PAMs represents 80% change.

point group **1** a notation used in describing the geometrical arrangement of the symmetry of globular oligomeric proteins. Such molecules may belong to any of the three point groups having **cyclic symmetry**, **dihedral symmetry**, or **cubic symmetry**. **2** *(in crystallography)* a group of symmetry operations that leave unmoved at least one point within the object to which they apply. It can describe single molecules or actual crystals.

point ligand any of two or more individual atoms or groups linked covalently to a specified carbon atom in an organic compound. Point ligands may be identical or nonidentical, but they may not occupy the same position in space.

point mutation any **mutation** (def. 1) involving a single base change. *See also* **transition**, **transversion**.

point of inflection any point on a graph where the direction of curvature changes.

poise *symbol*: P; the cgs unit of dynamic viscosity; it has the dimensions of g s^{-1} cm^{-1}; 1 P = 0.1 N s m^{-2}. [After Jean-Louis Marie Poiseuille (1799–1869), French physician and physicist.]

Poiseuille's equation an equation describing the behaviour of a liquid flowing under pressure through a capillary tube of length l and radius r. The volume flowing per second, $\mathrm{d}V/\mathrm{d}t$, is given by:

$$\mathrm{d}V/\mathrm{d}t = \pi P r^4/8\eta\, l,$$

where η is the viscosity of the liquid and P is the pressure difference of the liquid along the tube over a distance l. [After Jean-Louis Marie Poiseuille (*see* **poise**).]

poison **1** *(in toxicology)* any substance that, in relatively small amounts, can impair the functioning of, or cause structural damage to a cell or organism. **2** *(in chemistry)* any substance that, at relatively low concentrations, inhibits a chemical reaction or inactivates a catalyst. **3** to add or administer poison to (a cell, organism, catalyst, etc.).

pokeweed mitogen *abbr.*: PWM; a plant lectin (phytoagglutinin) extractable from the roots of pokeweed, *Phytolacca americana*, a North American plant. It is used in immunology and cell biology, has an affinity for *N*-acetyl-*β*-D-glucosamine oligomers, and agglutinates leukocytes and erythrocytes (of all ABO blood groups). It also has mitogenic properties, which appear to reside in five (or more) separable components; one of these activates both T and B lymphocytes, and the others are specific for T lymphocytes.

***poky* mutant** a mutant strain of *Neurospora* with a lower rate of growth than that of wild-type strains, due to absence or deficiency of certain components of the respiratory chain. The *poky* gene resides in mitochondrial DNA and is transmitted to sexually derived progeny only when the female parent exhibits the poky phenotype.

pol **1** a retroviral gene that encodes a polyprotein containing **retropepsin**, **reverse transcriptase**, and ribonuclease H (*see* **ribonuclease**). **2** as *polA*, *polB*, *polC*, genes that encode DNA polymerases I to III.

Pol the gene product of **polA**.

polA the structural gene in *Escherichia coli* for DNA polymerase I (Pol or Pol I; *see* **DNA polymerase**), which serves as a repair polymerase and as an exonuclease in the generation of **Okazaki fragments**. The enzyme belongs to family A of DNA polymerases and has three characteristic domains: 5′-exonuclease (amino acids 1–323), 3′-exonuclease (amino acids 324–517), and polymerase (amino acids 521–928). Klenow polymerase (amino acids 324–928) contains the latter two domains. *See* **Klenow enzyme**.

polar **1** pertaining to, or possessing, a **pole** or poles. **2** *(in chemistry)* (of a group or a molecular entity) having an uneven distribution of electrons and hence a permanent dipole moment. *See also* **polarity**.

polar body *(in biology)* either of the two small cells that form as a result of meiosis of a primary oocyte during its development to a mature ovum. One is formed in the first division, and the other in the second division. At each division, the cytoplasm divides unequally, the polar body being much smaller than the developing oocyte. At the second division the polar body and the developing oocyte each contains a haploid set of chromosomes. The polar bodies eventually degenerate.

polar bond **1** a covalent bond in which the electron pair(s) of the bond are held with greater force by one of the two bonded atoms leading to the existence of a permanent dipole moment in the group or molecular entity in question. **2** an ionizable bond between two oppositely charged ions of a salt.

polar coordinate *(in mathematics)* either of two numbers that locate a point in a plane, one being the distance along a line to the point from the origin and the other being the angle this line makes with a fixed line passing through the origin.

polar group *see* **polar** (def. 2).

polarimeter **1** an instrument for measuring the degree of polarization of light. **2** an instrument for measuring the rotation of the plane of vibration of linearly polarized light as a result of passing through a given length of optically active material. **—polarimetric** *adj.*; **polarimetry** *n.*

polarity **1** the state, or condition, of having **poles**. **2** having a differential distribution of a property or properties along an axis; *see* **polar**. **3** having opposing physical properties at different points, e.g. north and south magnetic poles, positive and negative electric charges, hydrophobic and hydrophilic regions. **4** the state of being electrically either positive or negative. **5** (of a solvent) **ionizing power**. **6** (of an organism) the tendency to develop differentially along an axis; e.g. plants exhibit polarity in developing roots downwards and stems upwards.

polarity gradient *(in genetics)* the quantitative effect of a **polar mutation** in one gene on the expression of later genes in the operon.

polarity mutant a mutant gene formed by a **polar mutation**.

polarizability *or* **polarisability** the quality of being able to be polarized.

polarization *or* **polarisation** **1** inducing polarity. **2** the quality of being or becoming polarized.

polarization microscope *or* **polarisation microscope** *an alternative name for* **polarizing microscope**.

polarize *or* **polarise** **1** to acquire or cause to acquire **polarity**. **2** to cause the polarization of light or other electromagnetic radiation; *see* **polarized light**. **3** to cause the electrical resistance of an electric cell to increase through the accumulation of electrolysis products at an electrode.

polarized light *or* **polarised light** light (or other electromagnetic radiation) in which the angular orientations of the electric vectors of its transverse vibrations are nonrandom. In **linearly** (or **plane-**) **polarized light** the electric vectors all lie in a given plane containing the light beam; to an observer looking along the light beam the vectors appear as a straight line through the axis of propagation. In **circularly polarized light** the angular orientations of the electric vectors are such that a given point on the vectors generates a (left-handed or right-handed) helix whose axis is the direction of the beam; to an observer looking along the light beam this point appears to describe the circumference of a circle, the light being defined as right or left circularly polarized depending on whether the point appears to the observer looking towards the source to be rotating clockwise or anticlockwise, respectively. Circularly polarized light may be considered to consist of two superimposed linearly polarized waves of equal amplitude but differing in phase by an odd number of quarter-wavelengths and having their electric vectors mutually at right angles; conversely, if right and left circularly polarized waves of equal amplitude are superimposed the resultant is a linearly polarized wave. In **elliptically polarized light** the angular orientations of the electric vectors are such that a given point on the vectors generates a (left-handed or right-handed) flattened helix whose axis is the direction of the beam; to an observer looking along the light beam this point appears to describe the perimeter of an ellipse, the degree of such polarization being characterized by the **ellipticity** and by the angular orientation of the major axis of the ellipse. Elliptically polarized light may be considered to result from the superimposition of two linearly polarized waves of equal amplitude and having their electric vectors mutually at right angles but where the phase difference is neither zero nor exactly an even or odd number of quarter-wavelengths; alternatively, it may be considered to result from the superimposition of right and left circularly polarized waves of differing amplitude.

polarizer *or* **polariser** an optical device for producing linearly polarized light, e.g. a **Nicol prism** or a sheet of **Polaroid** (def. 1).

polarizing microscope *or* **polarization microscope** a microscope that is useful for examining the birefringence properties of small objects, or for visualizing objects by virtue of their birefringence properties. *Also*: polarising microscope, polarisation microscope.

polar microtubule *see* **mitotic spindle**, **prometaphase**.

polar molecule a molecule in which there is a polarized distribution of positive and negative charges due to an uneven distribution of electrons. Polar molecules are likely to be soluble in water.

polar mutation a mutation in one gene that reduces the expression of genes further from the promoter in the same operon.

polarogram the current–voltage diagram obtained by **polarography**.

polarograph **1** an instrument used for **polarography**. **2** to subject (a sample) to analysis by polarography.

polarography a method for quantitative or qualitative determination of small concentrations of reducible or oxidizable substances based on the nature of the current–voltage curve obtained when a test solution is subjected to electrolysis with a steadily increasing voltage between, e.g., a dropping mercury cathode and a pool of mercury serving as anode. The current–voltage curve obtained (called a **polarographic wave**) is sigmoidal; the potential at the midpoint (called the **half-wave potential**) is characteristic of the substance being oxidized or reduced and the limiting current is related to its concentration. **—polarographic** *adj.*

Polaroid *a proprietary name for* **1** a thin, transparent material that linearly polarizes light transmitted by it (*see* **polarized light**). It consists of oriented, doubly refracting microcrystals of herapathite (quinine iodosulfate) in a matrix of cellulose acetate. **2** a photographic process or camera producing a nearly instantaneous, permanent photograph.

polar solvent any solvent of relatively high **ionizing power**.

polar zipper a motif in proteins that is considered to promote binding between protein subunits, or between proteins, as a result of interactions between polar residues, which are aligned in the form of a ‘zip fastener’. The polar groups may consist of repeats of glutamines, Asp–Arg or Glu–Arg repeats, or repeats of glutamates and either lysines or histidines. The concept derives from the previously coined term **leucine zipper**.

pole 1 either end of an axis of rotation of a sphere or spheroid body, especially of the Earth. **2** *(in biology)* **a** either of the differentiated zones at opposite ends of an axis in a cell, organ, or organism. **b** *(in mitosis or meiosis)* either of the opposite ends of the **spindle**. **3** *(in physics)* **a** any of the zones in a magnetized body, commonly two in number and near its extremities, where the lines of magnetic flux appear to originate (**north pole**) or end (**south pole**). **b** either of the (positively or negatively charged) terminals of an electric battery, or of the corresponding terminals of a d.c. electric generator; either of two points, positions, or regions carrying opposite electric charges in a piece of material, system, or (polar or polarized) molecular entity. *Compare* **dipole**. *See also* **polar**.

policeman a device used for detaching adherent particles of precipitate, cells, etc. from the wall of a vessel and consisting commonly of a glass stirring-rod with a short piece of rubber tubing fitting tightly over one end, but sometimes of a small snipe feather cemented into the end of a capillary tube.

polio virus a member of the *Picornaviridae* genus *Enterovirus.* which has 60 copies each of four subunits as coat proteins, VP1,2,3,4,produced synthesized as a polyprotein. They are arranged with the symmetry of an icosahedron. The genome is a positive sense RNA. The polymerase used in the replication of the virus is a multisubunit enzyme of four subunits only one of which is virus specific, the other subunits being provided by the host. Two kinds of vaccine have been used, killed virus, Salk, and attentuated live, Sabin. The latter sometimes can revert to the wild strain in the gut.

poly+ *comb. form* **1** denoting more than one; many or much; more than the usual number or amount; often used interchangeably with **multi+**. **2** indicating heterogeneity of a physical attribute e.g. polychromatic, polydisperse. *Compare* **mono+** (def. 2). **3** *(in chemistry and biochemistry)* **a** denoting more than one of a specified component or substituent, e.g. polyamine, polyene, polyester; in names of large molecules, usually denoting more than 10–20 of the component specified, especially in contrast to **oligo+** (def. 2), e.g. polynucleotide, polypeptide, polysaccharide. *Compare* **mono+** (def. 3). **b** denoting polymer of a specified substance, e.g. polyglycine, polystyrene. **c** indicating more than one function of the kind specified, e.g. polyacidic, polybasic, polydentate, polyhydric. *Compare* **mono+** (def. 5).

poly(A) *abbr. for* polyadenylate.

polyacidic (of a **base** (def. 1)) able to accept more than one proton per molecule in solution.

polyacrylamide (gel) *a common name for* any hydrogel containing a 3-D matrix of randomly cross-linked polymers of acrylamide (2-propenamide; CH$_2$=CH–CO–NH$_2$). The cross-linking agent commonly used is *N,N′*-methylene bisacrylamide, (CH$_2$=CH–CO–NH)$_2$CH$_2$, polymerization being initiated by various alternative methods for generating free radicals. The pore size and rigidity of the gel depend on the concentration of acrylamide, and the proportion of cross-linking agent used.

polyacrylamide gel electrophoresis *abbr.*: PAGE; a technique of **zone electrophoresis** that uses polyacrylamide gel as supporting medium. It is especially useful for the separation of biopolymers and fragments thereof. A two-dimensional electrophoresis has been used to resolve as many as 1000 proteins: in the first step the polypeptides are separated by **isoelectric focusing electrophoresis** and in the second step by **SDS (polyacrylamide) gel electrophoresis**. The 2-D process was devised by P. H. O'Farrell, after whom it is often named.

polyacrylamide gradient gel electrophoresis *an alternative name for* **gradient gel electrophoresis**.

polyadenylate 1 *abbr.*: poly(A); any homopolymer of adenylate (i.e. adenosine 5′-monophosphate). Most eukaryotic mRNAs are terminated at the 3′ end by a tract of poly(A) 80–250 residues long (*see* **poly(A) tail**). **2** to add a stretch of polyadenylate to a molecule. —**polyadenylation** *n.*

polyadenylation binding protein *see* **PABP-2**.

polyadenylation element a nucleotide sequence in the 3′ untranslated region of eukaryotic mRNA that contains a highly conserved AAUAAA followed by 10–30 nucleotides from where cleavage occurs and poly(A) formation starts. It is recognized by a complex that contains **cleavage and polyadenylation specificity factor** (CPSF), **poly(A) polymerase**, and **PABP-2**

poly(ADP-ribose) glycohydrolase *abbr.*: PARG; an enzyme that hydrolyses poly(ADP-ribose) to ADP-ribose units. Highly conserved in mammals, it contains an N-terminal putative regulatory domain, a central nuclear localization signal, and a C-terminal catalytic domain. There are multiple isoforms derived from a single gene.

poly(ADP-ribose) polymerase *see* **PARP-1**; **PARP-2**.

poly(ADP-ribosyl) a structure found attached to histones H1 and H2B, to other eukaryotic chromosomal proteins, and to some mitochondrial proteins. It consists of a polymer of 20–50 ADP-D-ribosyl units linked by glycosidic bonds; linkage is formed by transfer of the ADP-ribosyl unit of NAD$^+$, linking its ribosyl C-1 position to the C-2′ position of the ribosyl of the terminal ADP-ribose of the growing chain. The attachment to protein appears, at least in some instances, to be through an ester linkage between the terminal ribose group and certain free carboxyl groups in the protein. *See also* **ADP-ribosylation**; **NAD(P)$^+$–arginine ADP-ribosyltransferase**.

poly(ADP-ribosyl) transferase EC 2.4.2.30; *recommended name*: NAD$^+$ADP-ribosyltransferase; *systematic name*: NAD$^+$:poly(adenine-diphosphate-D-ribosyl)-acceptor ADP-D-ribosyl-transferase; *other names*: poly(ADP-ribose) polymerase; poly(adenosine diphosphate ribose) polymerase; ADP-ribosyltransferase (polymerizing); poly(ADP-ribose) synthetase. An enzyme responsible for ADP-ribosylation of acceptors; it catalyses a reaction between NAD$^+$ and (ADP-D-ribosyl)$_n$-acceptor to form nicotinamide and (ADP-D-ribosyl)$_{n+1}$-acceptor. It often has zinc as cofactor (as in example); the acceptor is a histone, a transcription factor, a DNA repair protein, or the enzyme itself. The modification is dependent on DNA and is involved in the regulation of cellular processes such as differentiation, proliferation, and tumour transformation and also in the regulation of the molecular events involved in the recovery of a cell from DNA damage. Mammals have four homologues (PARP-1, PARP-2, V-PARP, and tankyrase). In *Drosophila*, application of a heat-shock stimulus causes PARP to accumulate and become active at heat-shock genes. Ecdysone also causes accumulation of PARP at chromosome puffs. *See also* **NAD(P)$^+$–arginine ADP-ribosyltransferase**. *Compare* **ADP-ribosylation**.

polyamide any polymer in which the constitutional units are joined by amide or thioamide links. *Compare* **nylon**, **polypeptide**.

polyamine any organic compound containing two or more amino groups. **Putrescine**, **spermine**, and **spermidine** are important animal polyamines. Polyamines are synthesized by various routes. In animals, **putrescine** is the decarboxylation product of **ornithine**. Decarboxylated *S*-adenosylmethionine (*see* **S-adenosylmethionine decarboxylase**) is a substrate in a reaction in which propylamine is transferred to putrescine, to form spermidine, and again to spermidine to form spermine. *See also* **ornithine decarboxylase**.

poly(amino acid) any homopolymer, or mixture of homopolymers, of a particular (specified) amino acid.

polyampholyte any amphoteric **polyelectrolyte**.

polyanion any macromolecular ion that carries multiple negative charges.

poly(A) polymerase *abbr.*: PAP; *the recommended name for* **polynucleotide adenylyltransferase**.

poly(A) tail a sequence of adenylyl residues at the 3′ end of eukaryotic mRNA. Almost all mature eukaryotic mRNAs have 3′-poly(A) tails of 40–250 nucleotides, those of histones being a notable exception. The primary transcript is first cleaved 10–30 nucleotides past a highly conserved AAUAAA sequence, then the poly(A) tail is generated from ATP through the action of **polynucleotide adenylyltransferase and several other proteins**. In practical terms the poly(A) tail on mRNA facilitates its ready isolation from total cellular RNA by affinity chromatography on oligo(dT)-cellulose.

polyatomic (of a molecular entity) composed of two or more atoms.

polybasic (of an **acid** (def. 1)) able to give up more than one proton per molecule in solution.

Polybrene *a proprietary name for* 1,5-dimethyl-1,5-diazaundecamethylene polymethobromide; *other name*: hexadimethrine bromide; a positively charged polymer with coagulant properties. It causes nonspecific agglutination of red blood cells and has been used in the transfection of eukaryotic cells.

poly(C) *abbr. for* polycytidylate.

polycarbonate any polymer in which the structural units are linked by carbonate ester groups, usually formed by the polymerization of diphenylols with phosgene (i.e. carbonyl chloride). Such polymers are tough thermoplastic resins.

polycation any macromolecular ion that carries multiple positive charges.

polychlorinated biphenyl *abbr.*: PCB; any of various compounds that are based on the biphenyl ring structure and chlorinated at various positions. PCBs were formerly used in industrial and commercial applications such as transformers and hydraulic equipment, and as plasticizers in paints, plastics, and rubber products. They persist in the environment. Manufacture in the USA ceased in 1977.

polychromatic 1 relating to, or possessing, various or varying colours; consisting of, relating to, or emitting light (or other electromagnetic radiation) of two or more frequencies or wavelengths. **2** of, relating to, or showing **polychromatophilia**.

polychromatophilia the quality of being stainable by more than one type of dye, especially by both acid and basic dyes.

polycistronic messenger RNA *or* **multicistronic messenger RNA** *or* **polygenic messenger RNA** any messenger RNA molecule that carries more than one initiation site and encodes the synthesis of two or more (usually related) gene products. It is formed by transcription of a single operon and is characteristic of prokaryotes.

polyclonal of, pertaining to, being formed by, or derived from two or more **clones** (def. 1).

polyclonal antibody an antibody that arises from the immune response to an immunogen. Each **epitope** on the immunogen has the potential for causing the formation of a clone of **B lymphocytes** each capable of synthesizing an antibody specific to the particular epitope.

Polycomb one of a group of proteins in *Drosophila* that regulate the expression patterns of many developmental genes. Polycomb group proteins are involved in chromatin-based gene silencing and enable established patterns of gene expression to be transmitted over multiple rounds of cell division. *Compare* **trithorax**.

Polycomb a family of genes in *Drosophila* that select which homeotic selector genes should not be expressed. They encode homologous regulatory proteins that bind to the chromatin of the genes they control.

polycyclic having more than one ring of atoms in the molecule; used especially of molecules with condensed ring systems.

polycystin either of two proteins produced by different genes for autosomal dominant polycystic kidney disease (PKD). **Polycystin 1** is a membrane-associated glycoprotein (4303 amino acids) involved in cell–extracellular matrix interactions, and expressed in fetal, adult, and polycystic kidney. It consists of an extracellular N-terminal region of ≈3000 residues (containing 16 PKD1 repeats), 11 transmembrane helices, and a C-terminal coiled-coil region and sites for phosphorylation of serine/threonine and tyrosine. It shows ≈30% homology with polycystin 2. More than 60 mutations result in PKD type 1, which affects infants and is severe. **Polycystin 2** is an integral membrane protein (968 amino acids) that contains six transmembrane helices and intracellular N- and C-termini. The N-terminal region contains a coiled-coil region and an EF hand for Ca^{2+} binding. Polycystin 2 is more closely related to voltage-gated calcium channels than to polycystin 1. It is expressed ubiquitously but especially in fetal kidney and lung. More than 50 mutations cause PKD type 2, which affects adults.

polydentate *an alternative term for* **multidentate**.

polydeoxynucleotide *or* **polydeoxyribonucleotide** any **polynucleotide** composed solely of **deoxynucleotide** residues.

polydisperse describing a colloidal system whose disperse phase consists of particles of many different sizes. —**polydispersity** *n.*

polyelectrolyte any macromolecular substance that, on dissolution in water or another ionizing solvent, dissociates to give polyanions or polycations together with an equivalent of oppositely charged ions, which may be simple ions or themselves polyions.

polyene any unsaturated organic compound containing two or more carbon–carbon double bonds.

polyene antibiotic any member of a group of structurally related antibiotics produced by *Streptomyces* spp. They possess a large lactone ring containing 4–7 conjugated double bonds (generally all-*trans*) and substituted by aliphatic groups, by a residue of **mycosamine** or another amino sugar, and by numerous hydroxyl groups. The polyene antibiotics include **amphotericin B** and **nystatin**; they interact with sterols in cell membranes and hence have antifungal but not antibacterial activity and tend to be toxic to mammals. *Compare* **macrolide**.

polyenoic acid any alkenyl carboxylic acid containing two or more double bonds per molecule.

polyester any synthetic polymer in which the constitutional units are joined by ester bonds; proprietary materials include Dacron and Mylar. Polyesters are extensively used in textiles, ropes, etc.

polyethylene *an alternative name (esp. US) for* **polythene**. *See also* **polyethylene glycol**.

polyethylene glycol *abbr.*: PEG; any polymer of general formula $H(OCH_2CH_2)_n$ OH, where $n \geq 4$; a suffixed number may be used as a guide to the average relative molecular mass, e.g. polyethylene glycol 4000. Polyethylene glycols are clear viscous liquids or white solids, useful as embedding media for microscopy, as bases for ointments, and in radioimmunoassays. Treatment of proteins with PEG increases their functional stability and decreases their clearance and immunogenicity when injected in therapy.

poly(ethyleneimine) a water-soluble synthetic linear polymer of ethyleneimine (i.e. aziridine) of 30–40 kDa. It is useful for the selective precipitation of proteins and nucleic acids. It is also used as a substituent in hydroxylated chromatographic support matrices, as in PEI-cellulose, to form anion exchangers. *Proprietary name*: Polymin P.

polyfructosan *former term for* **fructan**.

poly(G) *abbr. for* polyguanylate.

polygalactan *former term for* **galactan**.

polygalacturonase EC 3.2.1.15; *other name*: pectinase; an enzyme that hydrolyses 1,4-α-D-galactosiduronate linkages in pectin and other galacturonans in a random fashion. It participates in cell-wall degradation in plants.

polygene any one of a group of genes, each of which individually exerts a small effect on the phenotype but that together control a quantitative character such as stature.

polygenic describing a character or trait that is controlled by polygenes. **Polygenic diseases** result from the interaction of multiple genes and include common diseases such as diabetes mellitus, coronary heart disease, and hypertension. Some genes can have major effects whereas others might have relatively minor effects. *Compare* **multigenic**.

polyglucosan *a former term for* **glucan**.

polyglutamine *or (sometimes)* **polyglutamine tract** a stretch of amino acids in a protein that is entirely composed of glutamine. Gene sequences giving rise to this structure may have $(CAG)_n$ repeats and can be subject to replication slippage. A consequence is expansion of polyglutamine tracts in succeeding generations eventually causing symptoms of disease. Huntingtin is a well-known example. *See* **Huntington's disease**.

polyglutamine disease any disease of humans caused by the expansion of a CAG trinucleotide repeat in a gene. On expression, the region that contains the elongated stretch of glutamine repeats misfolds and forms antiparallel beta strands, with consequent production of nuclear and cytoplasmic inclusions. Examples include Huntington's disease, spinobulbar muscular atrophy, and various forms of spinocerebellar ataxia.

polygon any closed plane figure bounded by three or more (nonintersecting) straight lines. —**polygonal** *adj.*

polyhedron (*pl.* **polyhedrons** *or* **polyhedra**) any solid figure bounded by four or more plane faces, each of which is a polygon. —**polyhedral** *adj.*

polyhormone a polypeptide that is a precursor to more than one biologically active peptide; an example is **proopiomelanocortin**.

polyhydric describing any chemical compound containing two or more hydroxyl groups per molecule; used especially of alcohols.

poly(hydroxybutyrate) a linear polymer of approximately 1500 (*R*)-3-hydroxybutyrate residues held together in ester linkage. It is found in the cells of a number of prokaryotic genera where it occurs in membrane-bound granules and acts as a storage material.

poly(I) *abbr. for* polyinosinate.

polyion any macromolecular ion that carries multiple charges.

polykaryocyte a multinucleate cell. —**polykaryotic** *adj.*

polyketide *or (sometimes)* **acetogenin** any natural product synthesized via linear poly-β-ketones, which are themselves formed by repetitive head-to-tail addition of acetyl (or substituted acetyl) units indirectly derived from acetate (or a substituted acetate) by a mechanism similar to that for fatty-acid biosynthesis but without the intermediate reductive steps. In many cases, acetyl-CoA functions as the starter unit and malonyl-CoA as the extending unit. Various molecules other than acetyl-CoA may be used as starter, often with methylmalonyl-CoA as the extending unit. The poly-β-ketones so formed may undergo modification by alkylation, cyclization, glycosylation, oxidation, or reduction. Polyketides include: coniine (of hemlock) and orsellinate (of lichens) – acetyl-CoA; flavanoids and stilbenes – cinnamoyl-CoA; tetracyclines – amide of malonyl-CoA; urushiols (of poison-ivy) – palmitoleoyl-CoA; erythronolides – propionyl-CoA and methylmalonyl-CoA as extender. Polyketide synthases are large multidomain proteins that contain phosphopantetheine.

polylabelling labelling where more than one atom of a molecule has been isotopically substituted.

polylinker any **linker** containing multiple restriction sites. *See* **multiple cloning site**.

poly-L-lysine any polypeptide composed entirely of L-lysine. Solutions of poly-L-lysine are used to coat microscope slides to improve the adhesion of tissue sections, or to improve adhesion of oligonucleotides in the preparation of microarrays for gene expression profiling. The attachment and spreading of some mammalian cell types in culture is promoted by coating surfaces with poly-L-lysine.

polymannan *a former term for* **mannan**.

polymer 1 *(in chemistry and biochemistry)* any substance that is composed of molecules containing a large number of constitutional units (or 'mers') that are in repetitive covalent linkage and that may be of one or more than one species. Polymers are generally considered to comprise at least ten mers, although sometimes the term is taken to imply simply 'more than one' mer. Hence 'polymer' may or may not embrace **oligomer**, depending on the branch of chemistry or biochemistry concerned. **2** *(in molecular biology and enzymology) (sometimes) an alternative term for* **multimer**. *See also* **heteropolymer**, **homopolymer**. —**polymeric** *adj.*; **polymerize** *or* **polymerise** *vb.*; **polymerization** *or* **polymerisation** *n.*

polymerase *a general name for* any transferase enzyme that catalyses the formation of biological **polymers** (def. 1), especially of polynucleotides. *See* **DNA polymerase**, **RNA polymerase**.

polymerase accessory protein any of a group of proteins that are associated with **DNA polymerases**. Examples include DNA polymerase α binding factor from yeast, and phage T4 accessory proteins.

polymerase chain reaction *abbr.*: PCR; a method whereby a specific sequence of nucleotides within a double-stranded DNA is amplified. The sequence is identified by the use of short synthetic oligonucleotide primers that are complementary to the two terminal regions of the DNA sequence to be amplified; these oligonucleotides are extended by the thermostable *Taq* DNA polymerase on the DNA template. The effect is that the new chains span the region delimited by the two chosen termini. There are three phases in a single cycle of a PCR reaction: the nascent chains are heat denatured at 94°C; the temperature is then decreased to allow annealing of the primers to the template strands; and then the temperature is increased to 72°C for extension. The theoretical yield of amplified product is 2^n where n is the number of cycles. More than a 10^9-fold **amplification** of the DNA stretch required may be obtained. The method was first described by Kary B. Mullis in 1984. The use of the thermostable *Taq* (or other) polymerase from a thermophilic bacterium avoids the need to add more polymerase at each cycle because the enzyme is not inactivated at the temperature of denaturation of the DNA. PCR amplification has become an indispensable tool in a great variety of applications. Clinically it may be used for the rapid diagnosis of infectious diseases and the detection of rare mutations associated with cancer. Forensically, the DNA from even a single hair or sperm can be used to identify the donor. RNA may be amplified by first converting it to cDNA through the use of reverse transcriptase. *See also* **hot start PCR**, **inverse PCR**, **touchdown PCR**, **whole genome PCR**.

polymer drug a polymer that contains either chemically bonded drug molecules or pharmacologically active moieties. Polymer drugs are typically used to provide targeted drug delivery to an organ and controlled release of an active drug at the target organ.

polymer functionalization the introduction of chemical groups into a polymer to exert specific chemical, physical, biological, pharmacological, or other functions. *See* **functional polymer**.

polymetaphosphate *(sometimes) an alternative name for* **polyphosphate**.

poly(methyl methacrylate) a clear, easily worked, relatively nontoxic thermoplastic, useful as a substitute for glass and in the construction of many pieces of scientific apparatus. *Proprietary names*: Lucite, Perspex, Plexiglass, etc.

Polymin P *a proprietary name for* **poly(ethyleneimine)**.

polymorph *see* **polymorphonuclear leukocyte**.

polymorphic *or* **polymorphous** having, assuming, or passing through various different forms or styles; exhibiting or undergoing **polymorphism**.

polymorphism 1 *(in biology)* **a** the occurrence of two or more distinct kinds of individual (**morphs**) belonging to the same species within a population that is interbreeding freely. **b genetic polymorphism**. **2** *(in chemistry)* the existence of the same substance in two or more different crystalline forms. *See also* **enantiomorph**.

polymorphonuclear 1 describing a cell whose nucleus is multipartite or **polymorphic**. **2** a **polymorphonuclear leukocyte**.

polymorphonuclear leukocyte *or* **polymorphonuclear** *or* **polymorph** *abbr.*: PMN; any white blood cell of the myeloid series that in its mature form has a lobed and variably shaped nucleus and granular cytoplasm; included are basophil leukocyte, eosinophil leukocyte, and neutrophil leukocyte. The term is often used erroneously for neutrophil leukocyte solely.

polymorphous *a variant form of* **polymorphic**.

polymyxin any of a family of antibiotics isolated from cultures of *Bacillus polymyxa* and active against most Gram-negative bacteria. Individual polymyxins are designated by suffixed letters, e.g. polymyxin B. All are decapeptides containing five or six residues of L-2,4-diaminobutyric acid. Their biosynthesis does not involve ribosomes (*see* **protein and peptide biosynthesis**). The sequence of seven residues at the C-terminal end is formed into a heterodetic ring through an isopeptide link to one of the diaminobutyric acid residues, while the N-terminal residue is acylated with a 6-methylheptanoyl or 6-methyloctanoyl group. Polymyxins bind to the plasma membrane of sensitive organisms, causing leakage of cytoplasmic components; however, they also attack the cell membranes of eukaryotic cells and therefore have limited clinical usefulness; they are used in antibiotic ointments. Polymyxin B inhibits protein kinase C. *See also* **colistin**.



polymyxin B1
DAB = diaminobutyric acid

polynucleate *or* **polynuclear** (of a cell) containing several or many nuclei; **multinucleate**.

polynucleotidase *an alternative name for* **polynucleotide phosphatase**.

polynucleotide any one-stranded homo- or heteropolymer of at least about ten **nucleotide units** connected by phosphodiester linkages between (usually) the 3′ position on the glycose moiety of one nucleotide unit and the 5′ position on the glycose moiety of the adjacent one, or any two-stranded molecule comprised of two such one-stranded molecules held together by hydrogen bonds. Comprehends the term **nucleic acid**.

polynucleotide adenylyltransferase EC 2.7.7.19; *other names*: NTP polymerase; RNA adenylating enzyme; poly(A) polymerase (*abbr.*: PAP); an enzyme that adds the **poly(A) tail** to mRNA. It catalyses a reaction of the type:

$$n\ \text{ATP} + (\text{nucleotide})_m = n\ \text{pyrophosphate} + (\text{nucleotide})_{m+n}\,.$$

PAP I and II contain an RNA-binding domain, a catalytic region, two nuclear localization signals, and a C-terminal serine/threonine-rich region. Clones of truncated forms have been obtained, some of which are expressed in tissues. The enzyme from *Escherichia coli* is also known as **plasmid copy number protein.** *See also* **polyadenylate**.

polynucleotide kinase *abbr.*: PNK; any enzyme belonging to subclass EC.2.7 that phosphorylates the 5′ end of nucleic acids. The reaction is between ATP and the 5′-OH of RNA or DNA to form ADP and RNA or DNA-5′-phosphate.

polynucleotide ligase *an alternative name for* DNA ligase (ATP); *see* **DNA ligase**.

polynucleotide ligase (NAD⁺) *an alternative name for* DNA ligase (NAD$^+$); *see* **DNA ligase**.

polynucleotide phosphatase *or* **polynucleotidase** either of the enzymes polynucleotide 3′-phosphatase (EC 3.1.3.32) or polynucleotide 5′-phosphatase (EC 3.1.3.33).

polynucleotide phosphorylase *an alternative name for* polyribonucleotide nucleotidyltransferase (EC 2.7.7.8).

polyol any polyhydric alcohol.

polyol pathway *(sometimes)* a metabolic pathway by which nonphosphorylated sugars and sugar alcohols are interconverted.

polyomavirus any member of a genus (*Polyomavirus*) of mouse viruses of the Papovaviridae family. They are widely distributed and may be oncogenic under appropriate conditions.

polyose *an obsolete term for* any polymer consisting of an unknown or unspecified number of covalently linked monose residues.

polypeptide **1** any peptide comprising more than about 10–20 amino-acid residues connected by peptide linkages. Unlike a **protein**, it usually lacks appreciable tertiary structure in solution and is not liable to irreversible denaturation. **2** *(loosely) an alternative term for* **protein**. **3** describing another entity of a polypeptide nature, e.g. polypeptide chain, polypeptide hormone.

polypeptide hormone *an alternative term for* **peptide hormone**.

polyphase *or* **polyphasic** **1** (of matter) consisting of two or more phases. **2** *or* **multiphase** (of an electrical system or device) having, generating, or using two or more alternating electric voltages of the same frequency but differing from each other in phase. **3** (of a process) consisting of or occurring in a number of separate stages.

polyphenol oxidase EC 1.10.3.1; *recommended name* catechol oxidase; any copper-containing oxidoreductase that catalyses the oxidation of mono and *o*-diphenols to *o*-diquinones. These enzymes are found in plants, localized in membranes of plastids, but their function is unknown. However, they are responsible for brown discoloration (‘browning’) in fruit and vegetables on storage, as their products give rise, probably nonenzymatically, to polyphenolic melanin-like compounds. Their gene sequences in different plants are very similar, but in relation to bacterial, fungal, or animal enzymes (*see* **monophenol monooxygenase**) only the putative copper-binding sites are conserved.

polyphosphate *or (sometimes)* **polymetaphosphate** **1** any ionic form of polyphosphoric acid, $H_{n+2}P_n\,O_{3n+1}$ (where *n* is an unknown or unspecified integer greater than 1), or any mixture of polyphosphoric acid and its ionized forms. Polyphosphate occurs in the **volutin granules** observed in many microorganisms, where it is synthesized by the action of the enzyme **polyphosphate kinase** and is believed to serve as a phosphate store. **2** any (partial or full) salt or ester of polyphosphoric acid. *See also* **metaphosphate**.

polyphosphate kinase EC 2.7.4.1; a microbial enzyme that catalyses the synthesis of **polyphosphate** by transfer of the terminal phosphoric residue of ATP to diphosphate (i.e. pyrophosphate) or to a polyphosphate one residue smaller than the product.

polyphosphoinositide *or* **polyphosphatidylinositide** *a former inappropriate general name for* any [mono]phosphate, bisphosphate, trisphosphate, or tetrakisphosphate of phosphatidylinositol; use not recommended.

polyploid describing a cell (or organism) that has three, four, five, or more times the haploid number of chromosomes in its nucleus. —**polyploidy** *n.*

polyprenol *a recommended term for* any **prenol** in which there are more than four isoprene residues; the isoprene units may be all-*trans* or a mixture of *cis* and *trans*. The number of such units in a particular polyprenol may be indicated by a multiplicative prefix, e.g. undecaprenol. Polyprenols and their derivatives are widely distributed in living organisms. *See also* **dolichol**.

polyprenyl the univalent alkyl group derived from a **polyprenol** by loss of its hydroxyl group. The number of isoprene residues in a particular polyprenyl derivative may be indicated by a multiplicative prefix, e.g. undecaprenyl diphosphate.

polyprotein any polypeptide that, on cleavage, gives rise to two or more biologically active proteins, e.g. **proopiomelanocortin**.

polyQ *an alternative term for* **glutamine repeat**.

polyribonucleotide any polynucleotide composed solely of ribonucleotide residues.

polyribonucleotide nucleotidyltransferase EC 2.7.7.8; *other name*: polynucleotide phosphorylase. An enzyme that degrades mRNA, phosphorylating single nucleotides successively from the 3′ end to yield a nucleoside diphosphate and a shortened mRNA.

polyribonucleotide synthase (ATP) *see* **RNA ligase (ATP)**.

polyribosome *an alternative name for* **polysome**.

polysaccharide *an alternative name for* **glycan**; i.e. any linear or branched polymer consisting of monosaccharide residues. Important polysaccharides include glycogen, starch, hyaluronic acid, and cellulose.

poly-α2,8-sialic acid a linear homopolymer ($n \approx 100$) of α2,8-linked sialic acid molecules present mainly on **neural cell adhesion molecules** (NCAMs). Its biosynthesis is mediated by polysialyl transferase, which uses CMP-sialic acid as substrate. It is abundant in fetal brain during development, and in adult brain in areas of synaptic plasticity, and is a marker for several tumours.

polysome *or* **ergosome** *or* **polyribosome** any structure consisting of two or more ribosomes attached to different points on the same strand of messenger RNA. Hence, a polysome is a complex involved in the cellular synthesis of the polypeptide specified in the message. Polysomes effect the synthesis of all proteins, but in the case of secretory proteins they become attached to the **rough endoplasmic reticulum**.

polysomic **1** describing a cell or organism that has one or more normal chromosomes in excess of the usual diploid or polyploid complement; being such a chromosome. **2** a polysomic organism. —**polysomy** *n.*

polystyrene phenylethene homopolymer; a clear, brittle, rigid thermoplastic with high electrical resistivity. A proportion of divinylbenzene may be added as a cross-linking agent during polymerization in order to produce polystyrene resins of various porosities for use in the preparation of polystyrene ion-exchange resins.

polysubstituted having more than one chemical substituent. —**polysubstitution** *n.*

poly(T) *abbr. for* polythymidylate.

polytene chromosome a type of chromosome in a **polyploid** cell, formed when multiple copies of homologous chromosomes are aligned side by side to give a giant chromosome in which distinct chromosome bands are readily visible.

polyteny *an alternative name for* **endomitosis**. —**polytene** *adj.*

polytetrafluoroethylene *abbr.*: PTFE; tetrafluoroethene homopolymer; a polymer consisting of chains of (≈2000) linked $-CF_2-$ units prepared by polymerization of tetrafluoroethylene, $F_2C{=}CF_2$. It is a nonflammable thermoplastic, extremely chemically resistant, of high electrical resistivity, and with an extremely low coefficient of friction. It is useful as tubing and sheeting in chemical laboratory work, as a lining to reaction vessels, as gasket material, and as packing for pumps and bearings. *Proprietary names*: Fluon, Teflon, etc.

polythene *or (esp. US)* **polyethylene** ethene homopolymer; a versatile thermoplastic polymer of ≈1.5–100 kDa, prepared by polymerization of ethylene. **High-density polyethylene**, a linear polymer, is fairly rigid and crystalline, while **low-density polyethylene**, a branched polymer, is softer and more flexible; both forms are chemically resistant and have high electrical resistivity.

polytopic describing an integral membrane protein that completely traverses the membrane two or more times.

polytrioxophosphate(v) *the recommended name for* **metaphosphate**.

poly(U) *abbr. for* polyuridylate.

polyUb *abbr. for* polyubiquitin. *See* **multiubiquitin**.

polyubiquitin **1** the form in which **ubiquitin** (def. 1) is synthesized, a precursor with a number of head-to-tail repeats. **2** *an alternative name for* **multiubiquitin**.

polyUb recognition factor a protein subunit of the 19S proteasome that binds multiubiquitin (polyubiquitin) chains tightly. When tested individually only one subunit (called S5a) qualified for the role.

polyunsaturated describing a substance containing more than one carbon–carbon multiple bond per molecular entity or residue; applied especially to a fatty acid containing more than one multiple bond in the hydrocarbon chain of its molecular structure, and to a fat or oil derived from one or more such fatty acids. *See also* **polyunsaturated fatty acid**. —**polyunsaturation** *n.*

polyunsaturated fatty acid *abbr.*: PUFA; any fatty acid that is **polyunsaturated**; the multiple bonds are most frequently all ethylenic and usually methylene-interrupted, the configuration of their substituents generally being *Z* (i.e. *cis*); more rarely is an acetylenic bond present. In animal metabolism, polyunsaturated fatty acids belong to families denoted by the position of the double bond nearest to the methyl group and often also by the name of the fatty acid from which the remainder can be derived; hence **linoleic family**, **linolenic family**, **oleic family**, and **palmitoleic family**. In recent years, emphasis has been placed on a role of some polyunsaturated fatty acids in lowering plasma cholesterol, and potentially reducing the risk of heart disease. Foremost among these have been those of the *n*-6 family such as linoleic acid. A recommendation has been made that the diet should contain these polyunsaturated fats in a ratio of 2:1 to saturated fats. *See also* **essential fatty acid**, **fatty-acid nomenclature**, **fish oil**.

polyuria the passing of large volumes of urine.

polyuronide *an old term for* **glycuronan**.

polyvalent *or* **multivalent** **1** *(in chemistry)* **a** having a numerical valency greater than unity. **b** capable of exhibiting more than one valency value. **2** *(in immunology)* **a** (of an antibody molecule or fragment) having at least two combining sites. **b** (of an antiserum or other antibody preparation) capable of combining with two or more different antigens. **c** (of a vaccine) capable of eliciting immunity to more than one (strain of) microorganism, toxin, or other antigenic agent.

polyvinyl acetate *abbr.* PVA; ethenoic acid homopolymer; a synthetic polymer obtained from ethyne and acetic acid, used in adhesives and paints and in the manufacture of polyvinyl alcohol.

polyvinyl alcohol *abbr.*: PVA; ethenol homopolymer; a polymer prepared from polyvinyl acetates by replacement of the acetate groups by hydroxyl groups; the commercial products have differing contents of residual acetyl groups and hence differing physical characteristics. Polyvinyl alcohols are used in adhesives and can also be compounded into elastomers, which are useful in the manufacture of artificial sponges, hydrocarbon-resistant tubing, etc.

polyvinyl chloride *abbr.*: PVC; chloroethene homopolymer; a plastic solid, soluble in many organic solvents, that discolours on exposure to light or heat unless containing stabilizers. It is useful for the manufacture of rubber substitutes and electric wire coverings.

polyvinylidine fluoride *abbr.*: PVDF; a synthetic polymer, $(CH_2–CF_2)_n$; membranes made of PVDF are used to bind proteins in Western blotting, protein sequencing, peptide mapping, and in analysis of amino acid composition.

polyvinyl pyrollidone *abbr.*: PVP; 1-ethenyl-2-pyrridinone homopolymer; commercial preparations are ≈10 kDa to ≈700 kDa; it is soluble in water to give colloidal solutions. PVP is used in the preparation of enzymes from plants; it removes phenolic compounds that can destroy enzyme activity.

polyxenic *see* **synxenic**.

pomace the pulpy residue remaining after extraction of juice from fruits such as apples, or after extraction of oil from seeds, nuts, or similar materials.

POMC *abbr. for* proopiomelanocortin.

Pompe's disease *an alternative name for* type II glycogen (storage) disease; *see* **glycogen disease**.

Ponceau S *or* **Fast Ponceau 2B** a dye used for staining protein, especially on cellulose acetate strips.



pontal (of an atom or group) bridging.

ponticulin an F-actin-binding transmembrane glycoprotein of plasma membranes of the cellular slime mould *Dictyostelium discoideum*. It is a major membrane protein of this organism, and a protein of the major high-affinity actin–membrane link. It is directly involved in actin polymerization.

pool *see* **metabolic pool**.

POPOP 1,4-bis(5-phenyloxazol-2-yl)benzene; a secondary fluor used in liquid scintillation counting, originally as a wavelength shifter and more recently to decrease sensitivity to the action of quenching agents.



population **1** *(in biology)* any group of individual organisms of the same species inhabiting a given area; the number of such individual organisms. **2** *(in statistics) or* **universe** any finite or infinite collection of individuals or items from which a sample has been drawn.

population genetics the study of the distribution of genes (alleles) in populations and the factors that change the frequency of genes and genotypes from generation to generation. It is based on the concept of the **Hardy–Weinberg law**.

population standard deviation *see* **standard deviation**.

P:O ratio *abbr. for* phosphorus:oxygen ratio.

porcine *abbr. (in compound abbrs.)* p *or (formerly)* P; of, characteristic of, or relating to a pig or pigs; resembling a pig.

porcupine a segment-polarity gene of *Drosophila* that encodes a member of the membrane-bound *O*-acyltransferase superfamily and is involved in Wingless signalling. The protein appears to be localized in endoplasmic reticulum.

pore an opening in a membrane that allows nonselective diffusional passage of small solutes across the membrane. In addition to pores formed spontaneously by thermal and electrical movement of lipid molecules there are the effects of extraneous (frequently toxic) substances that form pores.

pore-forming toxins subclass of transport proteins of the TC system, designated 1.C. It contains nearly 60 families, including **colicins**, **δ-endotoxins**, **α-hemolysins**, **aerolysins**, diphtheria, tetanus and botulinum toxins, **cytohemolysins**, **magainins**, **cecropin**, **melittin**, **defensins**, **nisins**, **mastoparans**, **pilosulins**, and **dermaseptins**. They are produced by bacterial, animal, and plant cells and make irreversible openings or lesions in the membranes of other cells.

porin **1** any member of a class of similar proteins of ~15 kDa (monomer) that can be isolated from the outer membranes of certain Gram-negative bacteria. Trimers of these proteins are thought to make these membranes porous to hydrophilic substances of ≤600 Da by forming in them water-filled channels that allow transmembrane diffusion of uncharged small solutes. The proteins are usually homotrimers, typically with β-barrel folds and including short α-helical domains. **2** any of the transmembrane proteins typically of the mitochondrial outer membrane in eukaryotes that form aqueous channels through the lipid bilayer, allowing passage of small molecules. These constitute a structural family, with high β structure content. Human mitochondrial membrane porin (voltage-dependent anion-selective channel protein) allows diffusion of small hydrophilic molecules; the channel adopts an open conformation at low or zero membrane potential, and a closed conformation at potentials above 30–40 mV.

porosity **1** the state or quality of being **porous**. **2** the degree to which a material or substance is porous.

porosome nuclear pore complex.

porous having pores; allowing the passage or uptake of gases and/or liquids, especially by diffusion rather than by bulk flow.

porphin *or* **porphine** *an alternative name for* **porphyrin** (def. 1).

porphobilinogen *abbr.*: PBG; 5-(aminomethyl)-4-(carboxymethyl)-1*H*-pyrrole-3-propanoic acid; the biosynthetic precursor of all porphyrins. It is excreted in relatively large amounts in the urine in some porphyrias.



porphobilinogen deaminase *see* **hydroxymethylbilane synthase**.

porphobilinogen synthase EC 4.2.1.24; *systematic name*: 5-aminolevulinate hydro-lyase (adding 5-aminolevulinate and cyclizing); *other names*: *δ*-aminolevulinic acid dehydratase (*abbr.*: ALAD); aminolevulinate dehydratase. An enzyme that catalyses the conversion of two moles of 5-aminolevulinate to one mole of porphobilinogen + 2 H_2O in the pathway for the synthesis of **porphyrins.** It is an abundant cytosolic homooctamer in mammalian cells. Each subunit contains a sulfhydryl group and a Zn atom. The crystal structure of the yeast enzyme consists of a TIM barrel. ALAD is identical with the 24 kDa proteasome inhibitor. Enzyme deficiency leads to a rare form of neurovisceral porphyria.

porphyr+ *a variant form of* **porphyro+** (before a vowel).

porphyria any metabolic disorder characterized by the excretion of abnormally large amounts of various porphyrins and/or their biosynthetic precursors. Porphyrias are currently classified as primary (if inherited) or secondary (if acquired). The primary disorders fall into two broad categories: (a) the neurological/psychiatric forms and (b) the forms associated with cutaneous photosensitivity, though these two types of symptoms may in some cases overlap. The acquired disorders are much more common. There is no clear-cut association of enzyme defects with specific porphyrias. Elevated blood levels of intermediates in porphyrin biosynthesis are normally present during attacks. Elevated intermediates that are found, together with (in parentheses) associated enzymes and conditions are (1) aminolevulinic acid (or ALA) (porphobilinogen (PBG) synthase: PBG synthase deficiency porphyria; *also called*: ALA dehydratase: ALA dehydratase deficiency); (2) ALA and PBG (PBG deaminase; acute intermittent porphyria, variegate porphyria); (3) uroporphyrin (uroporphyrinogen decarboxylase; porphyria cutanea tarda, acute intermittent porphyria) (4) coproporphyrin (coproporphyrinogen oxidase; variegate porphyria, hereditary coproporphyria). Acquired porphyria may be due to lead exposure, some malignancies, and chronic ethanol exposure. It has been suggested that the British king, George III, suffered from a form of porphyria leading to psychiatric symptoms. *See* **erythropoietic porphyria**.

porphyrin **1** *the systematic name for* the fundamental skeleton, $C_{20}H_{14}N_4$, of the macrocyclic **tetrapyrroles**; *often known also as* **porphin** *or* **porphine**. It consists of a ring of four pyrrole nuclei linked each to the next at their α positions (i.e. those adjacent to their nitrogen atoms) through a methine group, –CH= (*compare* **corrin**). The structure is aromatic and tautomeric, two hydrogen atoms being associated with any two of its four nitrogen atoms (though for the purposes of nomenclature the name ‘porphyrin’ implies that the saturated nitrogen atoms are at positions 21 and 23 in the molecule unless there is a specific indication otherwise). Many di- or trivalent metal ions are chelated by porphyrin through these four central nitrogen atoms. [*Note*: It was recommended in 1986 that the widely used Fischer system of (incomplete) numeration for the porphyrin ring be discontinued in favour of one in which all the atoms are numbered, the C atoms 1 to 20 and the N atoms 21 to 24.] The systems for numbering tetrapyrrole carbons are shown at **bacteriochlorophyll**. Porphyrin itself is a synthetic substance, deep purple in colour. **2** any member of a large group of naturally occurring or synthetic derivatives or analogues of porphyrin (def. 1), of which **protoporphyrin IX** and its derivatives, especially the chlorophylls and hemes, are the most important.



porphyrinogen **1** 5,10,15,20,22,24-hexahydroporphyrin; *see* **porphyrin**. **2** *a general name for* the corresponding hexahydro derivative of any **porphyrin** (def. 2).

porphyrinuria the excretion of abnormally large amounts of porphyrins in the urine. *See also* **porphyria**.

porphyro+ *or (before a vowel)* **porphyr+** *comb. form* denoting purple.

porphyropsin a purple, light-sensitive, visual pigment in the rod cells of the retinas of freshwater and migratory fishes, and some amphibians, consisting of a rod-type **opsin** combined (as a Schiff’s base) with 3,4-didehydro-11-*cis*-retinal. It has an absorption maximum at ~522 nm, and is analogous in function to **rhodopsin** in other vertebrates.

portable *(in molecular biology)* describing DNA sequences that can be inserted into recombinant molecules for the purposes of gene expression; e.g. portable promoter, portable Shine–Dalgarno sequence, etc.

portal **1** relating to a blood vessel, or system of blood vessels, that carries blood from one capillary bed to another, especially the hepatic portal vein. **2** relating to a porta, such as the hepatic porta (porta hepatis). **3** the route of entry into the body of a drug, microorganism, beam of radiation, etc. (or sometimes of its exit therefrom).

porter any transporter of solutes between aqueous phases on either side of a lipid membrane. The term includes **antiporter**, **symporter**, and uniporter (*see* **uniport**).

positional cloning a strategy for the identification of a gene of unknown function responsible for a genetic disease. The phenotype is correlated with a chromosomal site, the DNA of that region is cloned and compared with that in normal individuals. If a single gene is involved, it is sequenced, and the protein structure deduced. An example is the discovery of the genetic basis of cystic fibrosis and the identification of the **cystic fibrosis transmembrane conductance regulator** (CFTR).

positional information information supplied to or possessed by cells according to their position in a multicellular organism.

positional isomer any of two or more constitutional isomers that differ in the position of a particular substituent or group.

position-specific iterated-BLAST *abbr*.: PSI-BLAST; *see* **database-search program**.

position-specific scoring matrix *abbr*.: PSSM; *(in sequence analysis)* a position-specific scoring table that encapsulates the residue information within sets of aligned sequences. The scores may be simply the observed residue frequencies, or they may be the log-odds scores for finding a particular amino acid in a target sequence at a particular position.

positive 1 having a value greater than zero. **2** *(in mathematics)* of the same value but of opposite sense to that regarded as negative. **3** (of the results of a test) indicating the presence of the material or condition tested for. **4** (of an electric charge) having the opposite polarity to the charge of an electron. **5** (of a molecular entity) having a positive electric charge; having a deficiency of electrons. **6** (of a point in an electric circuit) having a higher potential than some other point to which a potential of zero is assigned. **7** *(in biology)* signifying growth or movement towards a (specified) stimulus. **8** *(in photography)* an exposed and developed photographic film, plate, or print showing an image in colours or tones corresponding to those of the object photographed. *Compare* **negative**. **—positiveness** *n.*; **positivity** *n.*

positive chromatography *(sometimes)* any method of purification of substances by affinity chromatography in which a substance of interest in a sample interacts with and is selectively retained by the adsorbent, especially as opposed to **negative chromatography**.

positive control the initiation or enhancement of some biological activity by the presence of a specific molecular entity.

positive cooperativity cooperative ligand binding in which binding of one ligand to one site on a macromolecule increases the affinity at other sites for the subsequent binding of the same or ligands.

positive correlation *see* **correlation** (def. 2).

positive Darwinian selection the relatively rare phenomenon whereby selective pressure favours change. A commonly used statistical test for positive Darwinian selection is comparison of the rate of synonymous with nonsynonymous substitutions: where nonsynonymous substitutions occur more frequently than synonymous substitutions, this is evidence that natural selection has favoured amino acid change.

positive effector *see* **effector**.

positive electron *an alternative name for* **positron**.

positive feedback *see* **feedback** (def. 1).

positive-negative selection a strategy used in making gene knockouts designed to enrich for homologous recombinants and select against random integration of the targeting vector. Cells transfected with the targeting vector incorporating two **selectable markers** are first selected for their resistance to an antibiotic such as G418 (positive selection) and then for the loss of a second marker, such as HSV thymidine kinase (HSV*tk*), which confers sensitivity to ganciclovir (negative selection). HSV*tk* placed at one end of the linear targeting vector is lost on homologous recombination but is retained on random integration.

positive staining a technique used for preparing specimens for electron microscopic examination in which charged biological macromolecules or structures are rendered electron-dense by allowing heavy-metal ions of opposite charge to bind to them. *Compare* **negative-contrast technique**.

positron *or* **positive electron** *symbol*: β^+; an elementary particle that is the antiparticle of the electron. It has the same mass as an electron and a numerically equal but positive electric charge.

positron emission tomography *see* **tomography**.

post+ *or (sometimes)* **post-** *prefix* denoting after in time or sequence; behind, posterior to.

postabsorptive describing the period immediately after absorption of food.

posterior after in position, sequence, or time; behind; following.

posterior lobe the posterior lobe of the pituitary gland; i.e. the **neurohypophysis**.

postgreSQL *see* **relational database management system**.

postlysosome a degenerate **telolysosome** that has lost its enzymes.

postmitochondrial fraction *or* **postmitochondrial supernatant** *or* **supernatant fraction** *an operational term for* the part of a homogenate of eukaryotic cells or tissue remaining after sedimentation of the mitochondrial fraction by centrifugation. It consists essentially of the **microsomal fraction** and the cytosol.

post-mortem 1 occurring after death. **2** a post-mortem examination; necropsy, or **autopsy**.

postnatal describing the period after birth or giving birth.

postpartum describing the period immediately after birth or giving birth.

postprandial describing the period immediately after intake of food.

postreplication repair *see* **recombinational repair**, **mismatch repair**.

postreplicative describing the period following replication of a cell or of a nucleic-acid molecule.

postribosomal fraction *or* **postribosomal supernatant** *or* **supernatant fraction** *an operational term for* the part of a homogenate of eukaryotic cells or tissue remaining after sedimentation of the ribosomal (microsomal) fraction by centrifugation. It consists essentially of the cytosol.

postsynaptic 1 describing a neuron or a neuronal membrane that is on the efferent side of a synapse. **2** describing the membrane of a muscle cell at a motor end-plate.

postsynaptic density *abbr*.: PDS; a structure, visible on microscopy, that is associated with a postsynaptic membrane. It consists of a variety of scaffolding proteins and signalling enzymes, such as neuronal nitric oxide synthase, Src, Ca^{2+}-calmodulin-dependent protein kinase, and calcineurin. The protein PDS-95 also couples NMDA receptors to some of these enzymes.

postsynaptic membrane *see* **synapse**.

post-transcriptional describing any phenomenon or process occurring after completion of transcription of genomic nucleic acid. **—post-transcriptionally** *adv.*

post-transcriptional gene silencing *an alternative term for* **RNA silencing**.

post-translational describing any phenomenon or process occurring after completion of translation of messenger RNA into polypeptide; postsynthetic. **—post-translationally** *adv.*

post-translational modification *or* **post-translational processing** *abbr.* PTM; any enzyme-catalysed change to a protein made after it is synthesized by the translation of messenger RNA. Examples are proteolytic cleavage and C-terminal peptide amidation. **glycosylation**, **methylation**, **phosphorylation**, and **prenylation**.

Pot-1 *abbr. for* protection of telomeres-1; a protein, widely distributed in eukaryotes, that binds to the G-rich DNA of telomeres.

potash 1 *the common name for* potassium hydroxide or potassium carbonate. **2** *the name for* potassium in the common names of certain of its salts.

potassium *or (in scientific and medical Latin)* **kalium** *symbol*: K; a soft, silvery white, highly reactive, metallic element of group 1 of the (IUPAC) **periodic table**; atomic number 19; relative atomic mass 39.0983. Natural potassium is a mixture of stable nuclides of mass numbers 39 (93.2 atom percent) and 41 (6.7 atom percent) together with a minute proportion of the radionuclide of mass number 40 (0.012 atom percent). Potassium is widely distributed in all living organisms, besides occurring in various minerals; it is one of the most abundant elements of the Earth's crust. It forms a monovalent cation, K$^+$. Several artificial radioactive isotopes are known. In the body, potassium is a major intracellular cation, with little in the extracellular compartment; the range in normal human plasma is

3.6–5.0 mmol L^{-1}, with serum 0.2–0.3 mmol L^{-1} higher due to release from platelets on clotting. The cellular uptake of potassium is stimulated by insulin, and its excretion by the kidney is indirectly controlled by aldosterone, which stimulates sodium reabsorption in the distal tubules, potassium being excreted by passive transfer due to the electrochemical gradient thereby created. It is actively pumped into cells by **sodium/potassium-ATPase**. *See also* **hyperkalemia**, **hypokalemia**.

potassium-40 the naturally occurring radioactive nuclide $^{40}_{19}$K. It has a half-life of 1.28 × 10^9 years, emitting beta particles (i.e. electrons) of 1.34 MeV max. and gamma radiation of 1.46 MeV.

potassium-42 the artificial radioactive nuclide $^{42}_{19}$K. It has a half-life of 12.36 h, emitting high-energy beta particles (i.e. electrons) of 3.52 MeV max. (82%) and 1.97 MeV max. (18%), together with gamma radiation of 1.52 MeV (18%) and 0.31 MeV (0.15%).

potassium channel *or* **K^+ channel** any type of structure that permits controlled (gated) passage of potassium ions, predominantly efflux, through membranes. In excitable cells the role of potassium channels is to set the resting potential, participate in restoring it after depolarization, and attenuate and regulate potentials generated by other excitatory inputs. They are classified into: (1) those primarily responding to membrane polarization, termed voltage-dependent, voltage-gated, or delayed rectifier (*see* **rectification**) K^+ channels; transmembrane (typically six transmembrane domains, designated S1 to S6) proteins; (2) Ca^{2+}-activated K^+ channels, which are activated by increase of intracellular Ca^{2+} concentration; (3) receptor-coupled channels, which may be activated or inhibited by receptor occupancy; these may have an intrinsic ion channel as part of the receptor, or act through a G-protein that activates an independent channel; and (4) ATP-sensitive K^+ channels that close in response to increased intracellular ATP/ADP ratios generated by increased metabolic flux. Types 3 and 4 are known as inward rectifier channels, in that they favour inward movement of K^+. Such channels have two transmembrane domains rather than the six of voltage-gated channels. However, all K^+ channels have a loop known as the H5 or P region, which is thought to line the conducting pore. In voltage-gated channels, this lies between segments S5 and S6, and in inward rectifier channels between the two transmembrane domains.

potency *(in pharmacology)* an expression of the activity of a drug or other agent, in terms of either the concentration or the amount needed to produce a defined effect. It is an imprecise term that should always be further defined. *Compare* **EC_{50}**, **IC_{50}**.

potential *(in physics)* **1** the work done in bringing unit positive charge, unit positive pole, or unit mass from infinity to a specified point in an electric, magnetic, or gravitational field, respectively. **2** **electric potential**. **3** **electric potential difference**.

potential difference *abbr.*: p.d.; **1** generally, the difference in **potential** (def. 1) between any two points. **2** *see* **electric potential difference**.

potential divider a chain of resistors (or inductors or capacitors) connected in series, across which an electric potential may be applied and from which a desired fraction of the potential may then be obtained from a contact suitably placed in the chain. *See also* **potentiometer** (def. 3).

potential energy *abbr.*: PE; *symbol*: E_p *or* V *or* Φ; the energy of a body or system consequent upon its physical state or its position in an electric, magnetic, or gravitational field. It is expressed as the work necessary to bring it to its present state or position from a reference state or position, to which a potential energy value of zero is assigned.

potential energy barrier *or* **energy barrier** **1** the difference between the bond energy at which a molecule dissociates and the energy of that molecule in the ground state. **2** the difference between the energy of the ground state of an enzymically activated reaction complex and the sum of the energies of the ground states of the reactants forming the activated complex.

potential gradient **1** the potential difference per unit distance between a point of higher and one of lower (electric) potential; the algebraic differential of this at a particular point. **2** (in cell biology) the difference in chemical and/or electrostatic potential across a membrane.

potentiate to cause to be (more) potent, especially to increase the potency of a drug or other agent. **—potentiation** *n.*

potentiometer **1** a precision instrument for measuring an electric potential difference of constant polarity without drawing current from the circuit being examined. In its simplest form, it consists of a length of wire of uniform resistance and across which a constant potential is applied. By means of a sliding contact the proportion of this applied potential is found that will balance the potential being measured as determined by a null reading on a galvanometer. **2** a direct-reading electronic device for measuring electric potential difference or electromotive force without drawing appreciable current. **3** *or (informal)* **pot** a development of a potential divider consisting of a resistor with a movable contact and used, especially in electronics, either as a potential divider or as a variable resistor. **—potentiometry** *n.*; **potentiometric** *adj.*; **potentiometrically** *adv.*

potentiometric titration *or (sometimes)* **electrometric titration** titration in which an electrode reversible to one of the ionic components of the analyte or titrant is immersed in the analyte solution and the electric potential of the electrode (relative to that of an inert reference electrode) is measured during addition of titrant. Because the potential of an electrode is a logarithmic function of the activity of the ion to which the electrode is reversible, an abrupt change in its potential is observable as an equivalence point is approached.

potocytosis a mechanism for small molecule transport across eukaryotic cell membranes that uses **caveolae** rather than clathrin-coated pits.

Potter–Elvehjem homogenizer a device for preparing small quantities of cell or tissue homogenates. It consists of a cylindrical pestle (of glass, Perspex, or Teflon) that fits closely into a hard-glass test tube. Cells or small pieces of tissue in a suspending medium are placed in the tube and the pestle is rotated by means of an electric motor while the tube is slowly moved up and down by hand, a shear thereby being imparted to the contents of the tube. [After van Rensselaer Potter (1911–2001), US biochemist, and Conrad Arnold Elvehjem (1901–62).]

POU domain a bipartite DNA-binding domain composed of a POU-specific domain (POU_s, ≈75 amino acids) and a POU-homeodomain (POU_h, 60 amino acids) that are highly conserved, are joined by a hypervariable linker sequence, and form helix-turn-helix structural motifs. It occurs in many **transcription factors, and** was first recognized in three families of transcriptional regulators, Pit (*see* **PIT**), **Oct**, and Unc (*see*, e.g., **unc-86**). POU domain genes include the Brn family and others. The recognition sequences are A/T-rich, including the highly conserved **octamer** sequence 5′-ATGCAAAT-3′. The domain is also involved in protein–protein binding. Mutations in two POU-domain proteins (POU3F4 and POU4F3) result in isolated deafness.

pound *symbol*: lb; the avoirdupois unit of mass, now defined as 0.453592338 kg exactly.

powder pattern *or* **powder diagram** a diffraction pattern obtained from a specimen of a crystalline material in finely divided form. The specimen is rotated in a parallel beam of monochromatic X-rays, electrons, neutrons, etc. so that all planes of the crystals assume all possible orientations with respect to the incident beam.

power **1** *symbol*: P; a measure of the rate of doing work, expressed as energy divided by time. The derived SI unit of power is the **watt**. **2** *(in optics)* a measure of the ability of a lens or mirror to magnify, expressed as the reciprocal of the focal length of the lens or mirror in metres. **3** *(in mathematics)* **a** *an alternative name for* **exponent** or index; e.g. 2 to the power 3 = 2^3). **b** one more than the cardinal number of times that a number or expression has to be multiplied by itself to give a required number; e.g. 2 to the power 3 = 2 × 2 × 2. **c** one more than the ordinal number of times that a particular number has to be multipled by itself to give a required number; e.g. the third power of 2 is 8 = 2 × 2 × 2.

power calculation a statistical test used to assess how many samples have to be analysed to maximize success in answering a hypothesis, while minimizing the use of resources. Power calculations are used in genetic association studies.

poxvirus any member of the Poxviridae, a family of large, double-stranded DNA viruses, in class I of the **Baltimore classification**. They consist of a single molecule of DNA of 130–240 MDa together with

30 or more structural proteins, a number of enzymes, and lipid. Their hosts range from insects to mammals; examples include the viruses of variola (smallpox) and vaccinia (cowpox) – but not of varicella (chickenpox) – in humans, and the virus of myxomatosis in rabbits.

Pp *symbol for* the propionyl group.

PP *abbr. for* pancreatic polypeptide.

PP$_\mathrm{i}$ *symbol for* inorganic pyrophosphate. *See* **diphosphate**.

PPAR *abbr. for* peroxisome proliferator-activated receptor; any of a subfamily of nuclear receptors for hormones. Mice produce three isoforms. **PPARα** predominates in liver, kidney, and heart. It binds leukotriene B_4 and heterodimerizes with retinoid receptor (RXR) to activate numerous genes. PPARα and PPARγ are activated by the hypolipidemic agent tetradecylthioacetic acid. **PPARγ** is the dominant transcription factor of adipocyte precursors. It binds thiazolidinediones (synthetic antidiabetic agents). When phosphorylated by MAP kinase, PPARγ inhibits adipogenesis. The ligand binding site of PPAR is homologous to that of the human estrogen receptor. In rats, but not in humans, clofibrate causes peroxisomal proliferation.

P particle a liberated, mature **kappa particle**.

ppb *or* **p.p.b.** *abbr. for* parts per billion, i.e. parts per 10^9.

PPCA *abbr. for* **protective protein/cathepsin C**.

PP cell *or (formerly)* **F cell** a type of cell containing granules that store pancreatic polypeptide (**pancreatic hormone**). In adult humans such cells are located exclusively in the pancreas (79% in the islets, 19% in the acini, and 2% in the ducts).

pp[CH$_2$]pA *symbol for* adenosine 5′-[*α*,*β*-methylene]triphosphate; an analogue of ATP in which the *α*,*β*-bridging oxygen atom has been replaced by a methylene group.

PPF *or* **PP factor** *abbr. for* pellagra-preventative factor; an early name for **nicotinic acid** or **nicotinamide**.

ppGpp *symbol for* guanosine 3′-diphosphate 5′-diphosphate (*also known as* **magic spot I**). *See* ***relA***, ***spoT***.

p22-phox *see* **phagocyte NADPH oxidase**.

p47-phox *see* **phagocyte NADPH oxidase**.

p67-phox *see* **phagocyte NADPH oxidase**.

PPIase *abbr. for* peptidylprolyl isomerase.

PPLO *abbr. for* pleuropneumonia-like organism (i.e. **mycoplasma**).

ppm *or* **p.p.m.** *abbr. for* parts per million, i.e. parts per 10^6.

PPO *abbr. for* 2,5-diphenyloxazole; a substance useful as a primary fluor in liquid scintillation counting.

pppGpp *symbol for* guanosine 3′-diphosphate 5′-triphosphate (*also known as* **magic spot II**). *See* ***relA***.

PPRibP *symbol for* (5-)phospho(-*α*-D-)ribosyl diphosphate.

P protein a membrane protein of **melanosomes** that functions in ion transport into the melanosome and in maintaining its acidic pH. The protein consists of 838 amino acids and contains 12 putative transmembrane sequences. Its gene is at 15q11.12, and numerous mutations are associated with a form of oculocutaneous **albinism**.

P-protein *abbr. for* phloem protein; any structural protein of phloem, the principal food-conducting tissue of vascular plants. P-proteins are present usually at low concentration in phloem exudates, when they are called **sieve tube exudate proteins** (STEPs).

P-protein body any crystalline or amorphous accumulation of protein that may be present during sieve element differentiation in vascular plants. The bodies may be in equilibrium with soluble monomeric proteins.

PPS *(in clinical chemistry) abbr. for* pepsin A.

ppt 1 *or* **ppt.**; *abbr. for* precipitate. **2** *or* **p.p.t.** *abbr. for* parts per trillion, i.e. parts per 10^{12}.

PPT *abbr. for* **1** preprotachykinin (*see* **protachykinin β precursor**, **tachykinin**). **2** phosphinothricin.

PQ *abbr. for* plastoquinone.

PQH$_2$ *abbr. for* dihydroplastoquinone (i.e. **plastoquinol**).

PQQ *abbr. for* pyrroloquinoline quinone (i.e. **methoxatin**). *See* **quinoprotein**.

Pr *symbol for* **1** praseodymium. **2** the propyl group.

Pr$^\mathrm{i}$ *symbol for* the isopropyl group, $(CH_3)_2CH$–.

prazosin *or* **furazosin** a quinazoline antagonist of α_1 adrenoceptors; it has anti-hypertensive properties.

pre+ *or* **pre-** *prefix* **1** before in time, position, sequence, rank, etc.; *compare* **pro+** (def. 1). **2** denoting a substance that moves faster (or further) than a specified substance in a separative procedure (e.g. prealbumin). Usage in this sense for naming proteins is now deprecated in order to avoid confusion with def. 3. **3** denoting a (usually metabolic) precursor, whether endogenous (e.g. prehormone, prekallikrein, pre-messenger RNA, preprotein, pretyrosine) or exogenous (e.g. precarcinogen), of the (class of) substance specified; *Compare* **pro+** (def. 3); *see also* **prepro+**.

PRE *abbr. for* proton relaxation enhancement.

prealbumin *an operational (and confusing) term for* either of two protein-containing zones observed to migrate more rapidly towards the anode than does serum albumin on zone electrophoresis of serum at pH 8.6 by some techniques. The faster-moving of these zones is now known to be **transthyretin**, and the other to be acidic α_1-glycoprotein (i.e., **orosomucoid**).

prebiotic of or relating to the period before the appearance of living organisms on Earth.

precancerous describing a tissue or condition that is not yet malignant but is expected to form a cancer.

precarcinogen *(sometimes)* a chemical carcinogen that can be converted by metabolism into another of no less potency. *Compare* **proximate carcinogen**.

precarcinomatous describing a tissue that is expected to form a **carcinoma**.

P receptor *see* **purinoceptor**.

precerebellin a cerebellum-specific protein that is the precursor of cerebellin (a 16-residue peptide flanked by Val-Arg and Glu-Pro), which is a protein of the postsynaptic structures of Purkinje cells. Concentrations of cerebellin are low at birth, and (in humans) peak at days 5–15. Its sequence is conserved in mammals and birds.

precess to undergo, or cause to undergo, **precession**.

precession (slow) gyration of the axis of rotation of a spinning body caused by application of a torque such that the axis of rotation generates a cone.

precipitant an agent or a reagent that induces the formation of a precipitate.

precipitate 1 to (cause to) come out of solution or suspension. **2** substance or material that is precipitated. —**precipitation** *n.*

precipitating antibody *an alternative name for* **precipitin**.

precipitin *or* **precipitating antibody** an antibody that is capable of reacting with a soluble antigen with the formation of an insoluble antigen–antibody complex.

precipitin reaction the reaction together of antigen and antibody near their equivalence point to form a cross-linked precipitate. Quantitative analysis of this interaction gives both the antibody content of an immune serum and an indication of the valency of the antigen. If the reaction occurs in a gel then the reactants form precipitin arcs.

precision 1 a measure of the sharpness (or certainty) of a measurement – a precise measurement may nevertheless be inaccurate (e.g. if there are unrecognized errors in the measurement). **2** *or* **selectivity** (*in informatics*) the proportion of the predictions made by an algorithm that are correct (i.e. discrimination of true matches from false): true positives/(true positives + false positives).

precision-bore (of tubing or a tubular object) having a lumen whose diameter varies only within extremely narrow limits.

prednisolone 1,4-pregnadiene-11*β*,17*α*,21-triol-3,20-dione; a semisynthetic steroid with glucocorticoid action. *Compare* **prednisone**.



prednisolone

prednisone 1,4-pregnadiene-17*α*,21-diol-3,11,20-trione; a synthetic steroid with glucocorticoid action. *Compare* **prednisolone**.



preelectrophoresis a preliminary treatment of an electrophoresis gel in which a potential difference is applied in order to remove undesirable substances such as excess polymerization reagents.

preflashing the hypersensitization of photographic emulsion by a preliminary exposure to a brief (≈1 ms) flash of light in order to increase its sensitivity to low levels of radiation and to render its response more nearly linear. It is useful especially in fluorography and (auto)radiography.

prefoldin *or* **Gim complex** (*abbr. for* genes involved in microtubule synthesis complex) a chaperone that cooperates in the proper folding of actin and tubulin by binding to their nascent polypeptide chains. In eukaryotic cytosol it is a ≈90 kDa complex of two α and four β subunits. Its structure is that of six alpha-helical coiled-coil tentacles arising from a beta-barrel body. It does not associate with the ribosome synthesizing the nascent chain and operates in an ATP-independent manner.

pregnancy-associated *α*2-glycoprotein *see* **pregnancy zone protein**.

pregnancy-associated plasma protein A *see* **PAPP-A**.

pregnancy zone protein *abbr*.: PZP; *other names*: pregnancy-associated α_2-glycoprotein; α_2-pregnoglobulin; a homotetrameric disulfide-linked proteinase inhibitor of the α_2-macroglobulin family that inhibits all four classes of proteinase by a 'bait-and-trapping' mechanism (*see* **bait region**). One of the major human pregnancy-associated plasma proteins, it may reach levels of 1.0–1.4 g L^{-1} just before term. It has extensive homology with human α_2-macroglobulin. In the sequence (example below) amino acids 1–24 form the signal, 26–1482 are the pregnancy zone protein, and 685–735 the bait region.

pregnane a C_{21} steroid to which **pregnanediol** is related.



5*β*-pregnane

pregnanediol *a common name for* the steroid 5*β*-pregnane-3*α*,20*α*-diol; (20*S*)-5*β*-pregnane-3*α*,20-diol; the principal urinary metabolite of progesterone, occurring mainly as its 3-glucuronide. Its level in the urine increases during the luteal phase of the menstrual cycle and especially in the latter part of pregnancy, the excretion rate being a convenient (if approximate) index of the functional state of the corpus luteum and placenta.

pregnant mares' serum gonadotropin *abbr*.: PMSG; a clinically useful impure gonadotropin preparation extracted from the serum of pregnant mares – such serum has high activities of both follicle-stimulating hormone and luteinizing hormone. *Compare* **urogonadotropin**.



pregnanediol

pregnenolone *a common name for* the steroid Δ^5-pregnen-3*β*-ol-20-one; 3*β*-hydroxypregn-5-en-20-one; a key intermediate on the biosynthetic route from cholesterol to progesterone. It has glucocorticoid activity and has been used in the treatment of rheumatoid arthritis. It is the product of **cholesterol monooxygenase (side-chain-cleaving)**.



***α*2-pregnoglobulin** *see* **pregnancy zone protein**.

prehybridization a procedure used for the treatment of nitrocellulose or nylon membranes following Northern or Southern transfer and before the use of labelled nucleic acid probes to detect specific sequences on the blot. The intention is to block the surface of the membrane to decrease non-specific binding of the probe. A variety of blocking agents can be used.

preincubate to bring a reaction mixture or a cell or tissue preparation to (chemical, metabolic, thermal, etc.) equilibrium before starting the reaction to be investigated. —**preincubation** *n.*

pre-initiation complex the complex formed on a gene promoter by RNA polymerase II and the general transcription factors, especially TFII, before initiation of transcription of the gene.

prekallikrein a plasma glycoprotein of 88 kDa (bovine), and a **blood coagulation** factor. It is the precursor of the protease **kallikrein**, to which it is converted by the action of factor XIIa. The protein contains four **apple domains**. The active site contains His, Asp, and Ser residues characteristic of a **charge-relay system**.

prelysosomal vacuole *or* **prelysosome** *a former name for* **endosome** (def. 1).

pre-messenger RNA *abbr*.: pre-mRNA; the class of primary gene transcripts from which the corresponding messenger RNA molecules are subsequently formed by post-transcriptional processing; any member of this class. It comprises a substantial part of **heterogeneous nuclear RNA**.

pre-miRNA the product of **Drosha** activity on **pri-miRNA** and a substrate for **Dicer**.

pre-mRNA *abbr. for* pre-messenger RNA.

pre-mRNA processing protein (*abbr*.: PRP protein) *or* **pre-mRNA splicing factor** any of the proteins involved in processing the primary transcript RNA. Many of them function as components of a **spliceosome**. Most are components of snRNP particles, which are numbered U1, U2, etc. The following examples are mostly from yeast (*Saccharomyces cerevisiae*): PRP2 is an ATP-binding RNA helicase required for the first cleavage ligation reaction; PRP5 is an ATP-binding RNA helicase required for unwinding of pre-mRNA, and is part of the spliceosome, a so-called **DEAD-box** helicase; PRP8 is a U5 snRNP protein; PRP9 is required for U2 snRNP to bind to pre-mRNA; PRP15 is an RNA-dependent ATPase required for branch-point recognition; PRP16 is an RNA helicase (another DEAD-box helicase); PRP18 is a component of the U4/U5/U6 snRNP, and is a homodimer; PRP19 is a U2-binding protein of unknown function; PRP21 is probably involved in retention of pre-mRNA in the nucleus; PRP22 is a DEAD-box helicase involved in release of spliced mRNA from the spliceosome; PRP28 is a DEAD-box helicase involved in U4/U5/U6 SnRNA; PRP38 is involved in maintenance of U6 snRNA; PRP39 facilitates interaction between U1 snRNP and the 5′-splice site.

premurein-leader peptidase EC 3.4.99.35; *other names*: prolipoprotein-signal peptidase; signal peptidase II; SPase II. An enzyme that cleaves a single bond between Gly^{20} and alkylated Cys^{21} in a bacterial lipoprotein, detaching the leader peptide.

premutation an expanded triplet repeat region of intermediate size in a gene, that does not of itself cause a disease. However, it is likely to increase in length during meiosis and to cause the disease in subsequent generations. In **fragile X syndrome** the $(CGG)_n$ repeat may increase in length during meiosis in the mother, more so than in the father. The risk that there will be expansion is proportional to the number of repeats and is 99% for repeat lengths of greater than 90. *See* **anticipation**.

prenol *the recommended name for* any **isoprenoid** of general formula $H–[CH_2–C(CH_3)=CH–CH_2–]_n$ –OH; i.e. any primary monohydroxy alcohol whose carbon skeleton consists of two or more isoprene residues linked head to tail. *See also* **polyprenol**.

prenyl the univalent alkyl group derived from a **prenol** by loss of its hydroxyl group. *See also* **polyprenyl**. *Compare* **isopentenyl**.

prenylation the enzymic addition of **prenyl** moieties to proteins as a post-translational modification; **geranyl**, **farnesyl**, or **geranylgeranyl** groups may be added. The process involves reaction of a prenyl diphosphate with a cysteinyl sulfhydryl group near the C terminus of the protein, to give a prenyl–S–Cys moiety. Characteristically a Cys-ali-ali-Xaa sequence is recognized by the transferase that mediates the reaction, where Cys is cysteine, ali is an aliphatic amino acid, and Xaa is any amino acid. When Xaa is serine, alanine, or methionine the protein is farnesylated; when Xaa is leucine it is geranylgeranylated, but this is variable; for example, in the case of Rab 3A (*see* ***RAB***), the Cys-Xaa-Cys motif leads to geranylgeranylation on both cysteine residues and methyl esterification of the terminal carboxyl, while in other members of the Rab family Cys-Cys directs geranylgeranylation without esterification. The function of the process appears often to be regulation of protein–protein and protein–membrane interaction.

prenyltransferase *see* **dimethylallyl*trans*transferase**.

PR-enzyme *an old name for* **1** **phosphorylase phosphatase** (EC 3.1.3.17). [PR stood originally for prosthetic-group removing, later for phosphorylase rupturing, and later still for phosphate removing.] **2** deoxyribodipyrimidine photo-lyase (EC 4.1.99.3). [PR stood for photoreactivating.]

preparative ultracentrifuge any ultracentrifuge designed for preparation or purification of tangible quantities of macromolecular substances, subcellular fractions, etc.

pre-part *or* **pre-peptide** *an alternative name for* **signal peptide**.

prephenate *a trivial name for* 2-oxo-3(1-carboxylato-4-hydroxy-2,5-cyclohexadiene-1)-propanoate; a nonaromatic intermediate in the branched biosynthetic pathway (the **prephenate pathway**) from chorismate to phenylalanine or tyrosine in most autotrophic organisms. *See also* **arogenate**.

prephenate dehydratase EC 4.2.1.51; *systematic name*: prephenate hydrolyase (decarboxylating); an enzyme that catalyses the formation of phenylpyruvate from prephenate with release of H_2O and CO_2 in a pathway for the biosynthesis of phenylalanine. In other cases (e.g. *Escherichia coli*) the activity is in the N-terminal domain of a bifunctional enzyme that also contains **chorismate mutase** (another enzyme of the phenylalanine biosynthetic pathway). *See also* **arogenate**.

prephenate dehydrogenase any enzyme that converts prephenate to 4-hydroxyphenylpyruvate with release of CO_2 and reduction of either NAD^+ or $NADP^+$. They function in the pathway for the biosynthesis of aromatic amino acids, to initiate the branch leading to tyrosine biosynthesis. They include prephenate dehydrogenase, EC 1.3.1.12; *systematic name*: prephenate:NAD^+ oxidoreductase (decarboxylating); *other name*: hydroxyphenylpyruvate synthase; an enzyme that also has **chorismate mutase** activity, so can convert chorismate to hydroxyphenylpyruvate. There is also prephenate dehydrogenase ($NADP^+$), EC 1.3.1.13; *systematic name*: prephenate:$NADP^+$ oxidoreductase (decarboxylating).

prephenate pathway a pathway for the synthesis of phenylalanine and tyrosine from chorismate, utilizing prephenate as an intermediate. Prephenate is formed from chorismate by **chorismate mutase**. It is converted by **prephenate dehydrogenase** to 4-hydroxyphenylpyruvate, from which tyrosine is formed by transamination with glutamate as the amino-group donor. For the synthesis of phenylalanine, phenylpyruvate is formed by **prephenate dehydratase**, and is then converted to phenylalanine by transamination, glutamate again acting as amino-group donor. *See also* **arogenate**.

pre-piece *an alternative name for* **signal peptide**.

prepolypeptide *or* **presecretory polypeptide** the transient, primary translation product of a eukaryotic messenger RNA for any polypeptide destined to be secreted by a cell, irrespective of whether an intermediary **propolypeptide** is formed; the polypeptide counterpart of **preprotein**. *See also* **prepropolypeptide**.

prepro+ *or* **prepro-** *compound prefix* denoting the presence in a secretory polypeptide or protein of the N-terminal signal sequence and any other sequence than the polypeptide or protein of interest.

preprocessing enzymic conversion of a preproprotein (or prepropolypeptide) to a proprotein (or propolypeptide).

preprohormone the presecretory precursor of a polypeptide or protein hormone, which contains the N-terminal signal sequence, the sequence of the hormone of interest, and any other sequence. Examples are: preproglucagon, preproinsulin, preproparathyrin, prepro-VIP.

preprophase band a dense band of microtubules, 1–3 μm wide, that appears just beneath the cell membrane before prophase of cell division in higher plants. It disappears as mitosis begins, yet it somehow determines the plane of orientation of the new cell plate forming in late telophase and marks the zone of the parental cell wall where fusion with the growing cell plate ultimately occurs.

prepropolypeptide the prepolypeptide of any propolypeptide: e.g., preproenkephalin and prepromelittin.

preproprotein the preprotein of any proprotein: e.g., preproalbumin (serum) and prepro-von Willebrand factor. Note that preprolactin is not a preproprotein, as prolactin is not a proprotein.

preprotachykinin *abbr.*: PPT; *see* **protachykinin β precursor**.

preprotein the transient, primary translation product of a eukaryotic messenger RNA for any protein destined to be secreted by a cell, irrespective of whether an intermediary **proprotein** is formed. It is detectable only in a cell-free protein-synthesis system, as in an intact cell its N-terminal presequence (i.e., **signal peptide**) is cleaved off before translation has been completed. *See also* **prepolypeptide**, **preproprotein**.

prereplication complex *another name for* origin of replication complex. *See* **ORC**.

presecretory polypeptide *an alternative name for* **prepolypeptide**.

presenilin either of two multipass transmembrane proteins, mutation of which results in familial **Alzheimer's disease**.

presequence *an alternative name for* **1** **signal peptide**. **2** transport sequence (of a protein imported into mitochondria), especially in those instances where the sequence is not removed by proteolytic cleavage prior to translocation through the membrane, but is removed at its final destination.

pressor *(in physiology)* **1** of, relating to, or bringing about an increase in arterial blood pressure. **2** any drug or other agent that has a pressor effect.

pressure *symbol*: *p or P*; the force per unit area acting on a surface; i.e. $p = F/A$. The pressure at a point in a fluid is equal to the force per unit area on an infinitesimal plane situated at that point, and in a fluid at rest it is the same in all directions. The SI derived unit of pressure is the **pascal**; the **bar** is also acceptable (*see* **standard atmosphere**). *See also* **millimetre of mercury**, **torr**.

pressure dialysis dialysis in which a hydrostatic pressure is applied to the material being dialysed in order to minimize its initial dilution by solvent entering by osmosis.

pressure homogenization *or* **nitrogen cavitation** a method of disrupting cells that depends on equilibrating a cell suspension with a gas, e.g. nitrogen, at high pressure (up to 7 MPa) and then suddenly reducing the pressure, whereupon the gas dissolved in the cytoplasm is explosively released.

pressure-jump method a relaxation technique in which change of pressure is the disturbing factor. *See* **relaxation kinetics**.

pre-steady-state kinetics *or* **transient-phase kinetics** the kinetics of a catalysed reaction during the phase in which the concentration of the catalyst–reactant complex rises from zero to its steady-state value. For an enzyme-catalysed reaction this phase usually occupies a very brief period of time (from a second to a microsecond or less) and special techniques are required for its study. *See also* **rapid reaction kinetics**.

prestin an integral membrane motor protein responsible for the electromotility of outer hair cells of the mammalian cochlea. It contains 12 transmembrane segments and is located in the basolateral membrane, where it undergoes structural rearrangement in response to transmembrane voltage changes. Intracellular chloride and bicarbonate ions bind to prestin and trigger the structural change.

pre-swollen describing a commercial gel preparation that has already been equilibrated with water or another liquid phase.

presynaptic **1** *(in anatomy)* **a** designating a neuron that transmits an impulse directly to a synapse. **b** of or pertaining to that part of such a neuron close to the synapse. **2** *(in cytology)* prior to meiotic **synapsis**.

presynaptic membrane *see* **synapse**.

presynaptic nerve ending *see* **synapse**.

pre-transfer RNA *abbr.*: pre-tRNA; the class of primary gene transcripts from which the corresponding transfer RNA molecules are subsequently formed by post-transcriptional processing; any member of this class.

pretransition temperature the specific temperature at which a lipid bilayer being heated shows the first signs of **melting** (def. 2), before it reaches its transition temperature. Special techniques (e.g. employing spin-labelled or fluorescent probes) are required for its detection and study.

pretyrosine *an obsolete name for* **arogenate**.

previtamin *a less common word for* **provitamin**.

PRF *abbr. for* Protein Research Foundation; *see* **sequence database**.

PRG-1 *abbr. for* plasticity-related gene-1; a gene expressed in rat hippocampal neurons during active axonal outgrowth. It encodes a membrane-associated phospholipid phosphatase that modulates the extracellular phospholipid concentration and regulates axonal outgrowth.

Pribnow box a promoter site in *Escherichia coli* and phage genes that specifically binds **RNA polymerase**. The Pribnow box has the consensus sequence TATAAT and is centred at –10 (ten nucleotides on the 5′ side of the first nucleotide transcribed, which is designated +1).

P*Rib*PP *symbol for* (5-)phospho(-α-D-)ribosyl diphosphate.

primaeval soup *a variant spelling of* primeval soup; *see* **primordial soup**.

primapterin *or* **7-biopterin** the 7-isomer of **biopterin** that is formed nonenzymatically from tetrahydrobiopterin. The reaction is prevented by a bifunctional protein (103 amino acids) that has **pterin-4α-carbinolamine dehydratase** (PCD) activity and is also the dimerization cofactor for hepatocyte nuclear factor 1α (DCoH). Several mutations in PCD result in hyperphenylalaninemia and primapterinuria.

primaquine one of several 8-aminoquinoline antimalarial drugs. It is active against the exo-erythrocytic form of the parasite, and can effect radical cures as well as serving as a preventive medicine. Primaquine sensitivity is a hemolytic anemia that occurs in persons deficient in glucose 6-phosphate dehydrogenase.



primary *(in chemistry)* **1 a** describing an alkyl compound (e.g. an alkanol) in which the functional group (e.g. a hydroxyl group) is attached to a carbon atom linked to only one other. **b** describing the carbon atom bearing the functional group in such a compound. **2** describing an amide or an amine in which a single appropriate group is attached to a nitrogen atom. **3** describing a salt formed by replacing only one of the ionizable hydrogen atoms of a tribasic acid by another cation. *Compare* **secondary**, **tertiary**.

primary cell wall the outer layer of the wall of a plant cell. It is produced by deposition of cellulose microfibrils against the cell plate separating two daughter cells newly formed by division. When cell extension is complete, it is supplemented by deposition of the secondary cell wall (*see* **secondary cell wall deposition**).

primary culture a culture of cells (or tissue) that have been obtained directly from their place of origin.

primary database *an alternative name for* **sequence database**.

primary electron an electron incident on a surface that causes **secondary electrons** to be emitted.

primary F′-containing strain *see* **F′ plasmid**.

primary fluor *or* **primary scintillator** *or* **primary solute** *(in liquid scintillation counting)* the fluorescent substance to which radiation energy is directly tranferred from excited molecules of the solvent. *Compare* **secondary fluor**.

primary granule *an alternative name for* **azurophil granule**.

primary hormone *a term proposed to embrace* any hormone that acts rapidly and uses a cyclic nucleotide as second messenger.

primary immune response the response produced in an animal when it is first exposed to an antigen. It consists characteristically of a slow production of antibody molecules and the priming of lymphoid tissue in readiness for the production of a **secondary immune response** on subsequent challenge with the same antigen.

primary kinetic isotope effect an **isotope effect** on a reaction rate that is attributable to isotopic substitution of an atom to which a bond is made or broken in the rate-limiting step or in a pre-equilibrium step of a specified reaction.

primary lysosome *or* **protolysosome** a **lysosome** that is a precursor of a **secondary lysosome**.

primary metabolism the ensemble of metabolic activities that are common to most if not all living cells and are necessary for growth, maintenance, and survival. *Compare* **secondary metabolism**.

primary metabolite any intermediate in, or product of, **primary metabolism**.

primary response *see* **primary immune response**.

primary scintillator *an alternative name for* **primary fluor**.

primary solute *an alternative name for* **primary fluor**.

primary solvent *(in liquid scintillation counting using mixed solvents)* the solvent to which energy of the radiation emitted by the specimen is first transferred as excitation energy.

primary standard **1** any standard of measurement of nationally or internationally agreed and specified value that is used as the basis of a unit of measurement. **2** a specimen of a particular substance that is of extremely high purity and stability and that serves as an ultimate reference to which may be compared the purity of any secondary standard used in analysis.

primary structure the first order of complexity of structural organization exhibited by polypeptide and protein molecules, and by polynucleotide and nucleic-acid molecules. When applied to a segment of a polypeptide chain, or to a polypeptide or protein molecule, it refers to the linear sequence of the amino-acid residues of the polypeptide chain(s), without regard to spatial arrangement, apart from configuration at the α-carbon atoms (and excluding the positions of any disulfide bonds). When applied to a segment of a polynucleotide chain, or to a polynucleotide or nucleic-acid molecule, it refers to the linear sequence of the nucleotide residues of the polynucleotide chain(s), without regard to spatial arrangement. *Compare* **secondary structure**, **tertiary structure**, **quaternary structure**.

primary transcript the RNA as synthesized by RNA polymerase directly from a gene, unaltered by any further modification, such as **splicing**, that it may undergo.

primase **1** any RNA polymerase that synthesizes an RNA primer needed for the initiation of DNA synthesis. Such enzymes vary greatly in structure, specificity, and mode of regulation. **2** *or* **DNA primase** the DNA-directed **RNA polymerase** (EC 2.7.7.–) of the bacterial **primosome**. In *Escherichia coli*, primase is the product of the *dnaG* gene while in T4 phage the primase is the product of gene 61. In either case, the primase is only active in the presence of other proteins which create a complex called a **primosome**. The complex participates in the unwinding of parental DNA strands ahead of the replication fork, and synthesizes short RNA primers for the **Okazaki fragments**.

primate any member of the Primates, an order of placental mammals. Primates are characterized by flexible pentadactyl limbs, opposable first digits, good stereoscopic vision, and, in the higher apes, highly developed brains. Included are lemurs, tarsiers, monkeys, apes, and humans.

prime **1** the printer's character, ′, used (singly, doubly, etc.) as a mark to discriminate between characters or symbols representing things that are or would otherwise be indistinguishable. In chemical nomenclature it is used to distinguish between (1) identical locants referring to different moieties of the same molecule; or (2) two or more unspecified but differing univalent groups represented by the same symbol R. In physical chemistry it is used to differentiate the symbol for a quantity measured under arbitrary conditions from that for the corresponding quantity referred to the (thermodynamic) standard state; e.g. K', apparent equilibrium constant, from K, thermodynamic equilibrium constant; E_o', standard redox potential at a specified pH, from E_o, standard redox potential at a hydron activity of unity. **2** *(in biochemistry)* to provide a metabolic reaction with a primer; to bring about activation of a process or substrate. **3** *(in immunology)* to induce a **primary immune response** in an animal; to activate a cell specifically with respect to a given antigen. **4** *(in mathematics)* **a** having no other integral factor than itself and one. **b** **prime number**.

prime number any integer that possesses no integral factors and hence is divisible only by itself and 1.

primer **1** something used to **prime** (def. 2, 3). **2** an oligonucleotide required as the starting point for the stepwise synthesis of a polynucleotide from mononucleoside triphosphates by the action of a nucleotidyltransferase. **3** a short-chain fatty acyl-CoA, e.g. acetyl-CoA or butyryl-CoA, required for the initiation of the stepwise enzymic synthesis, from two-carbon units, of long-chain fatty acids as their CoA derivatives. *See also* **glycogenin**.

primer extension a technique used to map the 5′ ends of mRNA transcripts and thereby identify the exact position of the transcription start site in the sequence of a gene. A labelled antisense oligonucleotide primer is hybridized to mRNA close to the 5′ end and extended by the action of reverse transcriptase. The length of the resulting cDNA reflects the distance between the labelled oligonucleotide and the 5′ end of the mRNA template.

primeval soup *or (esp. Brit.)* **primaeval soup** *an alternative name for* **primordial soup**.

primeverose 6-*O*-*β*-D-xylosyl-D-glucose; a disaccharide occurring in **madder**.



pri-miRNA *abbr. for* primary transcript **miRNA**, a substrate for **Drosha**.

primordia *the plural of* **primordium**.

primordial existing at or from the beginning, primeval; earliest formed, primitive.

primordial soup *or* **primordial slime** *or* **primeval soup** *or (esp. Brit.)* **primaeval soup** the aqueous solution of organic compounds that is considered to have been the environment in which the synthesis of macromolecules first occurred and cellular life originated. *See also* **coacervate droplet**.

primordium (*pl.* **primordia**) an organ or part at the earliest stage of its development; a rudiment.

primosome a protein complex that is essential for the activity of the **primase** responsible for the synthesis of RNA primers in the replication of DNA in *Escherichia coli. See* **replication complex**, **replication of DNA**.

PRINTS *see* **pattern database**.

prion a protein originally identified as the transmissible pathogenic agent responsible for prion diseases, such as **scrapie**, **kuru**, **bovine spongiform encephalopathy**, **Creutzfeld–Jakob disease**, and **Gerstmann–Sträussler syndrome**. The agent is now widely accepted to be a variant of the normal **prion protein**; it is believed that the variant folds abnormally, and induces the normal protein also to fold abnormally, typically into beta conformations that form aggregates. *See also* **fatal familial insomnia**.

prion protein *abbr.*: PrP^C; a membrane protein of 33–35 kDa that is encoded in the mammalian genome; it contains, in humans, 253 amino-acid residues (near the same number in other species), and has a glycosylinositol phospholipid anchor. A variant, termed PrP^{Sc}, with the same amino-acid sequence, is found in the brains of sheep and other mammals affected by **spongiform encephalopathy**. PrP^C is rich in α-helix, while PrP^{Sc} contains much β-sheet. PrP^{Sc} associates to form aggregates ('rods') in the central nervous system; such aggregates are seen in many manifestations of spongiform encephalopathy. Polymorphism, e.g. at position 171, occurs in several species and in subgroups in one species, and may be important with respect to disease susceptibility.

prism **1** any polyhedron of which two faces are polygons in parallel planes and the other faces are parallelograms. **2** a crystal form of which three or more faces are parallel to one axis. **3** a solid, bounded in part by two nonparallel plane faces and made of material transparent in the relevant region of the spectrum, that is used in optics to invert an image or to disperse or deviate a beam of light.

PRKAG3 *abbr. for* protein kinase AMP-dependent gamma chain 3. *See* **AMPK.**.

PRL *abbr. for* prolactin.

pro+ *or* **pro-** *prefix* **1** before in time or position; anterior; projecting; *compare* **pre+** (def. 1). **2** for, on behalf of, substituting for, favouring, encouraging, etc. **3** *(in biochemistry)* denoting (inactive or less active) biosynthetic precursor of the (class of) proteinaceous agent specified, to which it is convertible by proteolytic cleavage in a specific manner. Examples are: proalbumin, prohormone, proinsulin, proprotein, and prothrombin (but not prolactin!). *Compare* **pre+** (def. 3). *See also* **+gen**.

Pro *symbol for* a residue of the *α*-amino (strictly, cyclic *α*-alkylamino) acid L-proline (alternative to P).

pro- *prefix* in symbols designating prochirality; *see* ***pro-R/pro-S*** **convention**.

proaccelerin *an alternative name for* factor V; *see* **blood coagulation**.

probability *(in statistics) symbol*: *p or P*; a measure of the likelihood of the occurrence of a given event, expressed as the ratio of the number of times it occurs in a series of observations to the total number of observations, or as its decimal equivalent.

probable error an older measure of sampling variability such that one-half of the events, observations, etc. in a **normal distribution** lie between the mean value minus the probable error and the mean value plus the probable error. The probable error is equal to the standard error multiplied by 0.6745.

proband *an alternative term for* **propositus**.

probe **1** something that searches into, examines, or tests; e.g. an instrument or tube used for exploring a cavity or sampling a fluid, or an electric conductor introduced into an electric circuit or a cavity resonator to provide electric coupling to an external circuit. **2** *(in biochemistry)* a chemical species, or a chemical group attached to a carrier molecule, used to investigate the chemical nature of some other particular chemical species or the physical nature of a particular environment, especially within an intact cell; a **reporter group**. Typically some measurable physical property of the probe (e.g. fluorescence, electron spin resonance) alters in a way that can be correlated with changes in the environment or in the macromolecule. Examples are a group having paramagnetic properties, for detection using electron spin resonance (*see*, e.g., **TEMPO**), and a fluorescent lipid molecule used to report membrane fluidity (*see*, e.g., **parinaric acid**). **3** *(in molecular biology) or* **gene probe** *or* **hybridization probe** an oligo- or polynucleotide that is complementary to an oligonucleotide or nucleic-acid sequence under investigation. The probe is normally labelled in a way that permits its ready detection, e.g. with a radioactive isotope or a fluorescent constituent. Hybridization of the probe to the oligonucleotide sequence under investigation allows that sequence to be detected. The technique finds much use in screening gene libraries, detecting oligonucleotides on blots of electrophoresis gels, and in other associated technologies. **4** to examine with or as with a probe.

procainamide a local anaesthetic similar in action to **procaine** but having a less easily hydrolysed amide linkage, which gives it longer duration of action.



procainamide azide a local anaesthetic; it binds the 43 kDa postsynaptic protein (μ chain *or* rapsyn) of the nicotinic **cholinoceptor** and is useful as a photoaffinity label.

procaine *or* **novocaine** the prototype injectable local anaesthetic. It brings about changes in the physical properties of the lipid bilayer towards a more fluid state, decreasing ordering of the fatty-acyl side chains.



procapsid a precursor of the virion of certain viruses, consisting of a viral capsid without its specific nucleic acid.

procarboxypeptidase component III a protein, resembling **elastase** but without enzyme activity, found in the pancreatic juice of ruminants in noncovalent association with zymogens, carboxypeptidse A, etc. It probably prevents denaturation of the latter in the acid of the duodenum.

procaryon *a variant spelling of* **prokaryon**.

procaryote *a variant spelling of* **prokaryote**.

process *(in anatomy)* a thin prominence or protuberance of a structure, or an extension or outgrowth of a cell.

processed gene a **pseudogene** that lacks the intervening sequence or sequences of the homologous functional gene. It usually contains a short segment consisting entirely or almost entirely of adenine nucleotides, attached near the 3′ end, and is thought to originate by reverse transcription of an mRNA template with incorporation of the cDNA so formed into genomic DNA. A processed gene is sometimes called a **retrogene**.

processing *(in molecular biology)* **covalent modification** either of the primary transcription product (i.e. RNA) of a DNA or of the primary translation product (i.e. polypeptide) of a messenger RNA. *See also* **post-translational modification**.

processing body *see* **P body.**

processive *(in molecular biology) or* **nondistributive** describing (the action of) any enzyme or catalytic complex that progressively synthesizes or degrades a biopolymer by effecting several or many cycles of the same type of reaction or reaction sequence without dissociating from the template or intermediate product (as appropriate) between catalytic events. *Compare* **distributive**.

processivity (of a nucleic acid polymerase) the average number of nucleotides inserted before the enzyme dissociates from its template. In the case of DNA polymerases, repair enzymes (such as Pol I in *Escherichia coli*) have low processivity replication enzymes (such as Pol II and its associated proteins in *E. coli*) have high processivity.

processivity clamp *an alternative name for* proliferating cell nuclear antigen. *See* **PCNA**.

processosome a hypothetical ribonucleoprotein associated with processing of pre-RNA in the nucleolus.

prochiral describing a molecule, or a centre or axis in a molecule, that in itself is achiral but is capable of becoming **chiral** by a replacement reaction. In general, a prochiral molecule has a structure *Caabc*, where the '*a*' groups (or atoms) are identical. Replacement of one '*a*' by another group or atom, '*d*', leads to a chiral molecule. Thus, in ethanol, replacement of one ^{1}H of the methylene group by ^{2}H leads to a chiral structure which can be shown to be optically active. In a prochiral molecule *Caabc*, the chemically like '*a*' groups may be differentiated one from another in a reaction with a chiral molecule, especially an enzyme. An achiral molecule containing a double bond or a planar cyclic ring system is also prochiral if separate addition of an achiral reagent to each face leads to two enantiomeric products. *See also* ***meso*-carbon atom**, ***pro-R/pro-S* convention**. —**prochirality** *n.*

procholecystokinin precursor a member of the gastrin/ cholecystokinin family, and a precursor for five different **cholecystokinins**.

prochromacin the sequence that comprises residues 79–439 of human chromogranin A. It is bacteriostatic and antifungal by forming membrane ion channels, and is the precursor of four active peptides: chromacin (residues 176–197), pancreastatin (250–301), catestatin (352–372), and parastatin (357–428). *See* **chromogranin**.

Procion *the proprietary name for* a range of reactive dyes that includes Procion Blue H-B, Procion Red H-E3B, as well as a number of other dyes useful in biochemistry, especially in **dye-ligand chromatography**.

procoagulant *(sometimes)* any of factor V, factor VII, or factor VIII, each of which acts to accelerate the conversion of prothrombin to thrombin during **blood coagulation**.

procollagen an ~150 kDa triple-helical protein that is an intermediate in the biosynthesis of **tropocollagen**, into which it is converted proteolytically by removal of the additional sequences at both the N and the C termini of each of the three peptide chains. *Compare* **protocollagen**.

procollagen C-endopeptidase *an alternative name for* bone morphogenetic protein 1.

procollagen *N*-endopeptidase EC 3.4.24.14; *other name*: procollagen *N*-proteinase; an enzyme that catalyses the cleavage of the *N*-propeptide of collagen chain α-1(I) at Pro-|-Gln and of chain α-2(II) at Ala-|-Gln. Mutations at these sites lead to Ehlers–Danlos syndrome type VII. Inactivating mutations in the enzyme lead to dermatosparaxis of cattle.

procollagen-lysine 5-dioxygenase EC 1.14.11.4; *other names*: procollagen-lysine,2-oxoglutarate 5-dioxygenase (*abbr.*: PLOD); lysine hydroxylase; lysine,2-oxoglutarate 5-dioxygenase; an enzyme that catalyses the formation of hydroxylysine residues in collagen. The reaction is between dioxygen, procollagen L-lysine, and 2-oxoglutarate to form procollagen 5-hydroxy-L-lysine, succinate, and CO_2. Iron and **ascorbic acid** are cofactors. There are three genes for PLOD in humans. Several inactivating mutations in PLOD1 cause Ehlers–Danlos syndrome type VI. *See also* **procollagen-proline dioxygenase**.

procollagen-proline 4-dioxygenase EC 1.14.11.2; *systematic name*: procollagen-L-proline,2-oxoglutarate:oxygen oxidoreductase (4-hydroxylating); *other names*: proline,2-oxoglutarate-4-dioxygenase; protocollagen hydroxylase; proline hydroxylase; prolyl 4-hydroxylase. An enzyme that catalyses a reaction between dioxygen, procollagen L-proline, and 2-oxoglutarate to form procollagen *trans*-4-hydroxy-L-proline, succinate and CO_2. Hydroxylation only occurs during translation. **Ascorbic acid** and Fe^{3+} are also required as cofactors, and the reaction is one of the few well-defined roles for ascorbic acid; it seems likely that scurvy, as a result of vitamin C deficiency, is due to defective activity of this enzyme, which plays a key role in collagen synthesis. The enzyme contains two α chains and two β chains; the β chain is the multifunctional **protein disulfide isomerase** and hence has microsomal triacylglycerol transfer protein activity. It resides in the endoplasmic reticulum lumen. Two forms of the α subunit are produced by alternative splicing from the same gene. See also **procollagen-lysine 5-dioxygenase**.

proconvertin *an alternative name for* factor VII; *see* **blood coagulation**.

procorticotropin *or* **procortin** *an alternative name for* **proopiomelanocortin**.

procyclin *or* PARP a major surface antigen of procyclic forms of trypanosomes. It is GPI-anchored.

ProDom *see* **cluster database**.

prodrug a drug that is inert but has pharmacological effects after **bioactivation**. An example is **ganciclovir**.

produce *(in mathematics)* to extend a line or a plane.

product **1** *(in biochemistry and chemistry)* something formed in a reaction. **2** *(in mathematics)* the result of multiplying together two or more numbers, quantities, or expressions.

product inhibition the inhibition of an enzymic reaction caused by increased concentration of one or more products of that reaction.

productive (capable of) yielding a product, result, or benefit.

productive binding *or* **eutopic binding** the binding of a substrate in a reactive mode at the active site of an enzyme. *Compare* **nonproductive binding**.

productive complex any enzyme–substrate complex in which the substrate is bound to the enzyme in a manner that renders catalysis possible so that products can be formed. *Compare* **abortive complex**.

productivity *(in biotechnology) symbol*: *r*; the mass of product formed per unit reactor volume per unit time; often per unit of enzyme or biomass. It is measured typically in kg m^{-3} h^{-1}.

prodynorphin *see* **dynorphin**.

proenkephalin a protein precursor for several neuropeptides, including various **enkephalins** formed in brain and adrenal medulla. For example, in the human, proenkephalin A precursor yields four copies of [Met]enkephalin (100–104; 107–111; 136–140, 210–214) and single copies of each of [Leu]enkephalin (230–234), [Met]enkephalin–Arg–Gly–Leu (octapeptide) (186–193), and [Met]enkephalin–Arg–Phe (heptapeptide) (261–267), which arise by enzymatic cleavage of the gene product by cleavage at paired basic amino acids. Another human protein, proenkephalin B precursor (*other name*: β-neoendorphin–dynorphin precursor) yields single copies of α-neoendorphin, dynorphin, [Leu]enkephalin, rimorphin, and leumorphin, also by cleavage at paired basic amino acids.

proenzyme *an alternative name for* **zymogen**.

***pro-E*/*pro-Z* convention** if the two chemically-like hydrogen atoms of *ab*C=CH_2 are separately replaced by the achiral, *d*, an achirotopic stereogenic element is generated and two (diastereoisomeric) alkenes, *ab*C=CH*d* are fomed that are *E* and *Z* stereoisomers (*see* ***E*/*Z* convention**). The replacement has converted a prostereogenic element into which one which is stereogenic; the situation is comparable to the change, prochiral → chiral, although a chiral element is not involved. The two chemically-like hydrogen atoms are designated as *pro-E* and *pro-Z*, and are abbreviated as H_e and H_z . Replacement of a *pro-E* hydrogen with ^{2}H yields an *E* diastereoisomer and the similar replacement of a *pro-Z* hydrogen yields the *Z* form. Example: the two hydrogen atoms of phospho*enol*pyruvate; that on the same side of the double bond as the COOH group is H_E, that on the same side as the OPO_3H_2 group is H_Z . Replacement of ^1H_E by ^{2}H yields (*E*)-[3-$^2H_1$]phospho*enol*pyruvate; the *Z* diastereoisomer results if ^1H_Z is replaced by ^{2}H. A similar situation is found in the side chain of **chorismic acid**.

proestrus *see* **estrous cycle**.

profibrinolysin *an alternative name for* **plasminogen**.

profile (*in sequence analysis*) a scoring table that encodes the residue conservation within an aligned domain, used to provide a diagnostic signature for that domain. Profiles provide differential scores/penalties for matches, deletions, or insertions, and for transitions between these states. They are included as a supplement to the regular expressions in the PROSITE database. *Compare* **hidden Markov model**.

profilin any of a family of globular proteins (123–139 amino acids) that prevent the polymerization of actin. Profilins are ubiquitous in eukaryotes and consist of a five-stranded beta sheet and three small alpha helices. They bind dynamin and clathrin and localize with them in axons and dendrites, and bind diaphanous in hair cells of the inner ear. They compete with cofilin for ADP-actin, and promote exchange of the ADP for ATP. In mice profilin is essential for life. Profilin binds PtdInsP_2 and inhibits the γ isoform of phospholipase C (*see* **phospholipase**), an inhibition that is overcome by receptor kinase-dependent tyrosine phosphorylation.

proflavin 3,6-diaminoacridine; an **acridine** dye that intercalates between adjacent base pairs in duplex DNA. It is useful as an antibacterial agent, by inhibiting the biosynthesis of both DNA and RNA, possibly through intercalation into preexisting DNA, and as a frameshift mutagen for bacteriophages.



progeria any of two rare hereditary syndromes characterized by premature ageing in children (*see* **Hutchinson–Gilford syndrome**) or in adults (*see* **Werner syndrome**).

progesterone *the common name for* pregn-4-ene-3,20-dione; the principal steroid hormone of the corpus luteum, secreted during the latter half of the estrous cycle and acting upon the endometrium to prepare it for embryo implantation. During pregnancy, secretion occurs also from the placenta, increasing markedly as pregnancy proceeds, when it acts to maintain the uterus, inhibit further release of ova, and promote proliferation of acini within the mammary gland. Progesterone occurs also in the adrenal cortex and testis, and in some plants, e.g. *Hollatrhena floribunda*. It is synthesized from **pregnenolone** by 3β-hydroxy-Δ^5-steroid dehydrogenase, EC 1.1.1.145, and is an intermediate in the formation of androgens, estrogens, glucocorticoids, and mineralocorticoids.



progestin **1** *an alternative name for* **progestogen**. **2** natural **progesterone**, especially in unpurified form.

progestin receptor **1** a nuclear receptor of the steroid hormone type that binds and mediates the biological effects of progesterone. **2** a G-protein-coupled membrane protein that inhibits adenylate cyclase and mediates the effects of progesterone that are too rapid to be produced via transcription. The α isoform of animals occurs in reproductive tissues, while the β isoform occurs in brain.

progestogen *or* **progestagen** *or* **progestin** any natural or synthetic compound with the hormonal activity of progesterone. In oral contraception regimes, a progestogen is normally combined with an estrogen. The effect is to inhibit ovulation. A preferred method is to use a gestagen, which acts by an effect on the endometrium; these have fewer side effects than progestogens.

proglucagon the prohormone of **glucagon** and **enteroglucagon**. In mammals it consists of ≈170 residues, which contain the entire 29-residue sequence of glucagon in the N-terminal region, and two glucagon-like peptides, designated GLP-1 and GLP-2, of 37 and 35 residues respectively, within the C-terminal region. The 69-residue N-terminal portion, containing the glucagon sequence, is identical with **glicentin.** Angler-fish proglucagon is similar but smaller, and exists in two forms: a 14 kDa form (lacking GLP-2 and a 13-residue connecting peptide) and a 12 kDa form (of unknown sequence).

program **1** a sequence of coded instructions for controlling a computer or other electrical or electromechanical device, especially for enabling a computer to manipulate data in a predetermined way; an equivalent of this in an electronic or magnetic storage medium. **2** to constrain to function or operate in a particular way, especially by providing with a program or other (set of) instructions. **3** to write (and test) a computer program for a specific application. **—programmable** *or sometimes (esp. US)* **programable** *adj.*

programmable messenger *a term proposed for* a cytosolic protein messenger molecule in a hypothesis advanced to explain the multiple actions on their target cells of hormones whose cellular receptors are linked to oligomeric GTP-regulatory proteins in cell membranes. According to this concept, the activation of GTP-regulatory proteins (by GTP and the respective hormones) causes release of their α subunits from the membranes as cytosolic proteins, which become the primary messengers of hormone action and which thereupon are transformed by various protein-modifying enzymes (e.g. kinases and proteases) to yield new structures with selective affinities for different effectors, each responsive to its specific activating system. A variety of responses of the target cells thus may be elicited: accordingly, these messengers are considered programmable.

programmed ribosomal frameshifting a mechanism whereby different proteins may result from a single mRNA molecule, due to the presence of alternative sites within the mRNA that are recognized for initiation and termination of translation.

programming language a technical language in which computer programs are written. Different languages have evolved for different applications. Low-level languages tell the computer directly what operations to execute (e.g. machine and assembly languages); higher-level languages are used for scientific computation, business data processing, computer science education, symbol processing, and systems processing (e.g. Fortran, Cobol, Pascal, Lisp, and C, respectively); high-level scripting languages include awk, javascript, perl, php, python, sh, and tcl; object-oriented programming languages facilitate modular software design, and include Visual Basic, Java, and C++.

progress curve a graph showing the change with time in the concentration or amount of an analyte as a chemical reaction proceeds.

progressive alignment *see* **multiple alignment program**.

prohibitin any member of a family of highly conserved integral membrane proteins of the inner mitochondrial membrane that modulate the action of m-**AAA proteases**. Prohibitins contain a domain that is also present in stomatin and flotillin.

prohormone a natural (poly)peptide or protein precursor of a hormone.

prohormone convertase *or* **prohormone converting enzyme** any member of a family of endopeptidases that cleave prohormones within **dibasic cleavage sites** to form active polypeptides. They reside in acidic secretory vesicles. The C-terminal basic residue that remains is then removed by a carboxypeptidase. As EC 3.4.23.17 its *recommended name* is proopiomelanocortin converting enzyme. *See also* **neuroendocrine convertase**.

prohormone converting enzyme *another name for* **prohormone convertase**.

proinsulin the prohormone of **insulin**; it is a single-chain polypeptide of ≈9 kDa with three intrachain disulfide bridges, the number of amino-acid residues varying somewhat with species (78 in dog, 81 in cattle and sheep, 84 in cod and pig, 86 in horse, human, and rat). It is cleaved into insulin and C (or connecting)-peptide. Synthesized in the pancreatic B cells, it is normally present at about 5% of the concentration of insulin, and is secreted in small amounts into the blood.

projection formula any two-dimensional diagrammatic representation of the (three-dimensional) structural formula of a molecule (or part thereof) as if seen by projection onto a plane surface from a particular viewpoint in space. Bonds with different spatial orientations relative to the observer may be depicted distinctively. The term includes **conformational formula**, **Fischer projection**, **Newman projection**, and **perspective formula**.

prokaryon *or* **procaryon** (*pl.* **prokarya** *or* **procarya**) a primitive nucleus; i.e. genomic DNA in a defined structure, but lacking a nuclear membrane or other nuclear inclusions. Such an arrangement is found in bacteria (including actinomycetes) and cyanobacteria. *See also* **nucleoid** (def. 2). **—prokaryous** *or* **procaryous** *adj.*; **prokaryosis** *or* **procaryosis** *n.*

prokaryosis the condition of possessing a prokaryon or prokarya.

prokaryote *or* **procaryote** any organism in which the genomic DNA is not enclosed by a nuclear membrane within the cells; i.e. any organism whose cells possess a **prokaryon**. The prokaryotes comprise the bacteria, cyanobacteria, and archaea and are classified in their own kingdom, variously named Monera or Procaryotae. *Compare* **eukaryote**. **—prokaryotic** *or* **procaryotic** *adj.*

prolactin *abbr.*: PRL; a hormone secreted by the anterior pituitary that stimulates lactation. Human prolactin (hPRL) is a 199-residue protein, 23 kDa in its monomeric form (**little prolactin**), although dimeric (**big prolactin**, 48–56 kDa) and polymeric (>100 kDa) forms circulate in blood. The prolactin gene belongs to a family of genes, along with those encoding placental lactogen and human growth hormone (*see* **somatotropin**). Secretion is episodic; it is inhibited by dopamine, which binds to lactotrope D_2 receptor (*see* **dopamine receptor**) to inhibit adenylate cyclase, and is probably stimulated by **thyrotropin-releasing hormone** and **vasoactive intestinal peptide**. Prolactin synthesis is positively regulated by estrogen acting at the level of the prolactin gene. Receptors for prolactin are located in breast, liver, ovary, testis, and prostate, but its main site of action is the mammary gland, which is stimulated to develop by estrogen, progesterone, prolactin, and placental mammotropic hormones. Lactation is stimulated by prolactin but is prevented during pregnancy by the inhibitory action of estrogen and progesterone, the levels of which fall after parturition, allowing prolactin to initiate lactation. *See also* **prolactin receptor**, **proliferin**.

prolactin receptor a membrane protein of the cytokine receptor family. The prolactin receptor is associated with a small protein **calcyclin**.

prolamin *or (formerly)* **prolamine** any of a group of simple proline-rich proteins, found especially in the seeds of cereal plants, that are insoluble in water, neutral salt solutions, and absolute ethanol, but soluble in dilute acid or alkali, and in 70–80% aqueous ethanol. The group includes the **gliadins** of wheat and rye, **hordein** of barley, and **zein** of maize. *Compare* **glutelin**.

prolate **1** having a polar diameter longer than the equatorial diameter. **2** describing an **ellipsoid of rotation** generated by the rotation of an ellipse about its major axis. *Compare* **oblate**.

prolidase *another name for* **X-Pro dipeptidase**. *Distinguish from* **prolinase**.

proliferating cell nuclear antigen *see* **PCNA**.

proliferin *or* **mitogen-regulated protein** a prolactin-related protein, the mRNA of which appears in several murine cell lines during growth. One of several proteins of the somatotropin/prolactin family that provide a growth stimulus to target cells in maternal and fetal tissues during the development of the embryo. The mRNA occurs in placenta, which secretes proliferin as a glycoprotein distinct from placental lactogen.

prolinase *the recommended name for* **Pro-X dipeptidase**. *Distinguish from* **prolidase**.

prolinate **1** proline anion; the anion, $(C_4H_7NH)–COO^-$, derived from **proline**. **2** any salt containing proline anion. **3** any ester of proline.

proline *the trivial name for* pyrrolidine-2-carboxylic acid, $(C_4H_7NH)–COOH$; a chiral cyclic *N*-alkylated *α*-amino acid. L-proline (*symbol*: P *or* Pro), (*S*)-pyrrolidine-2-carboxylic acid, is a coded amino acid found in peptide linkage in proteins; codon: CCA, CCC, CCG, or CCU; by virtue of its more constrained molecular structure relative to most other *α*-amino acids, it usually does not participate in α-helix formation in globular proteins, but does occur in transmembrane helices, in which it introduces a pronounced kink. In mammals, it is a non-essential dietary amino acid, and is glucogenic. It is formed from **glutamate 5-semialdehyde** by reduction by NADPH. D-Proline (*symbol*: D-Pro *or* DPro), (*R*)-pyrrolidine-2-carboxylic acid, is not known to occur naturally. *See also* **hydroxyproline**.



L-proline

proline/arginine-rich protein *abbr.*: PARP; a 24 kDa proline- and arginine-rich protein from bovine cartilage, closely related to the N-terminal domain of collagen α1 (XI).

proline dehydrogenase EC 1.5.99.8; *other name*: proline oxidase; a flavoprotein enzyme that catalyses the reaction:

L-proline + acceptor + H_2O =
(*S*)-1-pyrroline-5-carboxylate + reduced acceptor.

The flavin is FAD. In *Escherichia coli* the enzyme is bifunctional, having the activities of both proline dehydrogenase and **1-pyrroline-5-carboxylate dehydrogenase.** In humans, the enzyme (516 amino acids) is located with the inner mitochondrial membrane and is present in liver, kidney, and brain. Enzyme deficiency results in hyperprolinemia type 1.

proline dipeptidase *see* **X-Pro dipeptidase**.

proline hydroxylase *see* **procollagen-proline dioxygenase**.

proline-rich proteins *abbr.*: PRP; one of the four major classes of **plant cell-wall proteins**. They contain proline-rich repeat sequences (Pro–Pro–Val–Tyr–Lys in soybean), are poorly glycosylated, and are thought to form rodlike molecules.

prolinium proline cation; the cation, $(C_4H_7NH_2^+)$–COOH, derived from proline.

prolino the pyrrolidino group, HOOC–(C_4H_7N)–, derived from proline.

prolixin-S *an alternative name for* **nitrophorin** 2.

prolyl the acyl group, (C_4H_7NH)–CO–, derived from proline.

prolyl dipeptidase *see* **Pro-X dipeptidase**.

L-prolylglycine dipeptidase *see* **Pro-X dipeptidase**.

prolyl hydroxylase *see* **procollagen-proline dioxygenase**.

prolyl oligopeptidase EC 3.4.21.26; *other names*: prolyl endopeptidase; post-proline cleaving enzyme; post-proline endopeptidase. An enzyme that catalyses the hydrolysis of Pro-|-Xaa >> Ala-|-Xaa in oligopeptides. It is a cytoplasmic (in eukaryotes) serine endopeptidase, also found in some bacteria.

prometaphase the stage in **mitosis** or **meiosis**, following **prophase**, during which the nuclear envelope is disrupted and breaks into membrane vesicles, and the spindle microtubules enter the nuclear region. **Kinetochores** mature on each **centromere** and attach to some of the spindle microtubules; these are then called **kinetochore microtubules** while those to which kinetochores do not attach are called **polar microtubules**; microtubules outside the spindle are called **astral microtubules**. Kinetochore microtubules begin the process of aligning chromosomes in one plane halfway between the poles.

promiscuous DNA any DNA sequence that occurs in more than one of the genetic systems (i.e. nuclear, mitochondrial, or plastid) of eukaryotic cells. Many such DNA segments have been found in yeast, fungi, plants, and animals.

promoter *symbol*: *P*; a DNA sequence located 5′ to a gene that indicates the site for the initiation of transcription. It may influence the amount of mRNA produced and the tissue specificity of expression. The symbol may be subscripted to indicate particular promoters, e.g. P_{RM}, a promoter for the *c*I gene, RM standing for repressor maintenance. In prokaryotes consensus sequences centred at –10 (i.e. **Pribnow box**) and –35 nucleotides upstream from the transcription start site are recognized by **RNA polymerase**. Eukaryotic promoters have sequence elements that are recognized by general transcription factors such as TFIIA, TFIIB, TFIIC, TFIID (i.e. **TATA-binding protein**), TFIIE, TFIIH, and TFIIJ that form a transcription initiation complex with RNA polymerase II. **TATA boxes** (–25), **CAAT boxes** (–100), and **GC boxes** are often found in the promoters of housekeeping genes. In addition, eukaryotic promoters may have binding sites (**response elements**) for transcription factors found in only some cell types. Promoters for genes transcribed by RNA polymerase III may be downstream from the start site.

promoter escape *or* **promoter clearance** the melting of dsDNA downstream of the promoter region effected by a subunit of transcription factor TFIIH that is an ATPase and acts as a molecular wrench that twists the two strands apart.

promoter ligand an additional ligand that is included in the loading buffer in **affinity chromatography**, to promote specific binding to the immobilized ligand.

promoter melting the denaturation or separation of the two strands of DNA of the promoter region on binding a 3′→5′ DNA helicase subunit of transcription factor TFIIH.

promutagen any substance that, when acted upon by the cell's metabolism, becomes a **mutagen**.

promyelocytic leukemia protein *see* **PML**.

promyelocytic leukemia zinc finger protein *see* **PLZF**.

Pronase *a proprietary name for* a mixture of various exo- and endopeptidases, obtained from *Streptomyces griseus*, that is able to hydrolyse virtually any protein almost completely to free amino acids. It is used for hydrolysis of many proteins, for digestion of mucins, in isolation of intact DNA or RNA from cells or viruses, and in dispersal of certain types of mammalian tissue cells, e.g. chondrocytes.

pronucleus (*pl.* **pronuclei**) the nucleus of either the ovum or the spermatozoon following fertilization. Thus, in the fertilized ovum, there are two pronuclei, one originating from the ovum, the other from the spermatozoon that brought about fertilization; they approach each other, but do not fuse until just before the first cleavage, when each pronucleus loses its membrane to release its contents. **—pronuclear** *adj.*

proof a standard by which the strength of distilled alcoholic solutions (or vinegars) is judged. In the UK it is the strength of a mixture of alcohol and water having a specific gravity of 0.91984, and containing 0.495 of its weight or 0.5727 of its volume of absolute alcohol. Degrees of proof express the percentage of proof spirit present; hence 70° proof spirit contains 0.7 × 57.27% alcohol. In the US, proof is a number that is twice the percentage (by volume) of alcohol present; hence 70° proof spirit contains 0.5 × 70% alcohol.

proofreading *(in genetics)* verification of the exact nature of a sequence of bases in DNA or amino-acid residues in a protein. Proofreading of DNA sequence occurs in transcription, during the action of DNA polymerase, when incorporation of an incorrect nucleotide causes mismatch in pairing with the complementary base on the template strand; this leads to immediate excision of the incorrect nucleotide, retreat of the enzyme to the previous position, and another attempt to insert the correct nucleotide. During translation, charging of the tRNA with its aminoacyl group is verified by its fit in the binding site; if incorrect, the aminoacyl-tRNA is hydrolysed to tRNA and amino acid and the whole process is repeated until successful. Examples of such proofreading during translation include rejection of threonine by valine–tRNA ligase, and of valine by isoleucine–tRNA ligase. *See also* **mismatch repair**.

Pro(3-OH) *symbol for* a residue of the α-amino acid (*trans*-)3-hydroxy-L-proline (alternative to 3Hyp).

Pro(4-OH) *symbol for* a residue of the α-amino acid (*trans*-)4-hydroxy-L-proline (alternative to 4Hyp).

proopiomelanocortin *abbr.*: POMC; a 241-residue prohormone protein, *also called* **corticotropin–lipotropin precursor**, synthesized in the intermediate and anterior lobes of the pituitary. POMC is cleaved in the anterior pituitary by a **prohormone convertase**, PC1 to yield an N-terminal peptide (residues 1–80), **corticotropin** (residues 110–148) and β **lipotropin** (β-LPH, residues 148–241). The segment 83–107 is known as **joining peptide**. Prohormone convertase, PC2, then cleaves corticotropin to yield α-**melanocyte-stimulating hormone** (α-**MSH**; residues 110–122), and cleaves β-LPH to yield γ-LPH (residues 151–208) and β **endorphin** (residues 211–241). Derived hormones (cleavage points and some sizes differ from porcine above): corticotropin, 39 amino acids; **corticotropin-like intermediate lobe peptide**, 21 amino acids; β endorphin, 31 amino acids; lipotropins β-LPH (89 amino acids) and γ-LPH (56 amino acids); melanocyte-stimulating hormones α-MSH (13 amino acids), β-MSH (18 amino acids), and γ-MSH (11 amino acids); [Met]enkephalin (*see* **enkephalin**), 5 amino acids. In the intermediate lobe, POMC synthesis is regulated mainly by dopamine and serotonin; in the anterior lobe by glucocorticoids and corticotropin-releasing hormone. The prohormone convertases are related to **furin** and **kexin**.

proopiomelanocortin converting enzyme EC 3.4.23.17; *the recommended name for* **prohormone convertase**.

propargylamine *see* **monoamine oxidase inhibitors**.

propellant *or* **propellent** any substance that through pressure or combustion or other means causes propulsion, as, e.g., the use of compressed gases in spray cans.

propeptide that part of a peptide chain that follows the signal sequence, and is cleaved off in formation of the mature protein.

properdin *see* **complement**.

prophage a form of the genome of a bacteriophage in which the nucleic acid is integrated into the genome of the phage's bacterial host, a state known as **lysogeny**. **Induction** to produce mature phage can occur, with accompanying lysis of the bacterium. For example, in **lambda phage**, transcription of the prophage is repressed by the *cI* gene product, the repressor, which binds to the O_L and O_R operators thereby preventing use of the P_L and P_R promoters. The product of the *cII* gene, CII, is crucial in determining the choice between lysogeny and lysis; if CII is active lysogeny is favoured, but if CII is not active (due to breakdown by host proteases) lysis is favoured.

prophage induction *see* **phage induction**.

prophage-mediated conversion *another name for* **bacteriophage conversion**.

prophage reactivation the phenomenon in which the survival of UV-irradiated **lambda phage** is higher in a host carrying a homologous heteroimmune prophage than in a host that is nonlysogenic or is lysogenic with a nonhomologous prophage.

prophase the initial stage of **mitosis** or **meiosis** in which the chromosomes are condensed, becoming apparent within the nucleus, but are not yet attached to a mitotic spindle. By early prophase, the single centrosome contains two centriole pairs; at late prophase, the centrosome divides and the two asters move apart. In meiosis, the chromosomes come together in homologous pairs, and undergo crossing-over. This occurs during the first of the two meiotic cell divisions, and is divided into several stages. In the first, zygotene, a complex structure develops between the two sister chromatids of each pair, which may play a part in **recombination**. They remain in the complex during a stage known as pachytene, then separate at the diplotene stage.

propheromone convertase Y a protease present in yeast with specificity towards paired basic residues (-Lys-Arg-, -Arg-Arg-, or -Arg-Lys-) and no activity towards single basic residues.

propidium iodide a phenanthridine derivative (λ_{max} excitation 536 nm, emission 617 nm) whose fluorescence intensity increases greatly when intercalated in the DNA double helix. It is widely used in flow cytometry in the analysis of ploidy.

propionate the anion, $CH_3–CH_2–COO^−$, derived from propionic acid, in any salt; designation for the **propionyl** radical in naming an ester.

propionibacteria bacteria belonging to the genus *Propionibacterium*. They are characterized by their activity in fermenting glucose or lactic acid to propionic acid; acetic acid is also a major product. *See also* **propionic-acid fermentation**.

propionic acid propanoic acid; $CH_3–CH_2–COOH$; a carboxylic acid, important in the energy metabolism of ruminants, in which it is formed by rumen bacteria. It is the basis of a series of nonsteroidal anti-inflammatory agents, known as substituted propionic acids; *see* **ibuprofen**.

propionic-acid fermentation fermentation of glucose or lactate by *Propionibacterium* spp. (*see* **propionibacteria**) to either propionate or acetate; pyruvate is a common intermediate for both transformations. In propionate formation, pyruvate first reacts with methylmalonyl-CoA to form propionyl-CoA and oxaloacetate. The latter is converted by reactions of the tricarboxylic-acid cycle to succinate, which then reacts with the propionyl-CoA to form propionate and succinyl-CoA. The succinyl-CoA is converted to methylmalonyl-CoA, which is then available to react with a further molecule of pyruvate. Conversion of pyruvate to acetic acid involves oxidative decarboxylation to acetyl-CoA, reaction of this with orthophosphate to form acetyl phosphate, and reaction of the latter with ADP to form ATP and acetic acid. When lactate is the initial substrate, this is first converted to pyruvate by lactate dehydrogenase. This enzyme is a flavoprotein, that is oxidized by a cytochrome *b*.

propionyl *symbol*: Pp; *the trivial name for* propanoyl, $CH_3–CH_2–CO–$, the univalent acyl group derived from propionic (i.e. propanoic) acid. *Compare* **propyl**.

propionyl-CoA carboxylase *abbr.*: PCCase; EC 6.4.1.3; an enzyme that catalyses a reaction between ATP, propanoyl-CoA, and $HCO_3^−$ to form (*S*)-methylmalonyl-CoA, ADP, and orthophosphate; biotin is a coenzyme. It is an enzyme in the catabolic pathways of odd-chain fatty acids and isoleucine, occurring in the mitochondrial matrix. Defects cause propionic acidemia, which is inherited as a recessive trait. The human enzyme consists of six α chains (biotin binding) and six β chains.

proplastid the precursor of a **plastid**.

propolypeptide the inactive form in which some polypeptide hormones, or other agonists, are produced; it is activated by removal of part of the sequence by a protease.

proportional counter any device for measuring radioactive disintegrations by means of a gas-filled ionization chamber, e.g. Geiger counter, operating in the **proportional region**.

proportional region a range of voltages applied to a gas-filled ionization chamber (e.g. Geiger counter) over which the gas amplification is greater than unity. In radioactive counters of this type, measurement depends on ionization of the gas in the ionization chamber by emitted radiation. Up to a certain applied voltage, ion production and thus the current through the chamber depends solely on collisions between emitted radiation and gas molecules; at higher voltages, the current is enhanced by additional collisions, so that sensitivity is increased, but the current remains proportional (hence the name proportional region) to the rate of emission of radiation. *Compare* **Geiger region**.

propositus *or (fem.)* **proposita** (*pl.* **propositi**) *or* **proband** the first individual to present as a patient, in a series of cases related (usually) to a heritable disorder, and from whom the line of descent is traced.

propranolol an important β-adrenoceptor antagonist; the (*S*) form is the active structure. It is used therapeutically as an antihypertensive, anti-anginal, and anti-arrhythmic. *One proprietary name*: Inderal (as hydrochloride).



(*S*)-form

propressophysin the polypeptide precursor of **vasopressin** and **neurophysin** (*see* **vasopressin–neurophysin 2–copeptin precursor**). Mutation of the gene is associated with familial neurogenic diabetes insipidus.

proprotein an inactive form of a protein, having an additional sequence that is removed by a protease to yield the active protein; a classic example is **proinsulin**. A **zymogen** is a form of proprotein, sometimes referred to as a proenzyme.

propyl *symbol*: Pr; *n*-propyl; the alkyl group, $CH_3–CH_2–CH_2–$, derived from propane. *Compare* **isopropyl**, **propionyl**.

***pro-R/pro-S* convention** stereochemical descriptors for paired, chemically-like ligands at a prochiral centre; they derive from an extension of the **sequence rule** used to assign *R*,*S* descriptors to a chiral centre. In the prochiral (but achiral) structure, *Caabc*, the chemically-like ligands are the two atoms (or groups of atoms), *a*. For the sake of example assume that the sequence rule gives the priority sequence, $a > b > c$. In the molecular model (or projection formula) arbitrarily label the *a* groups as a' and a'' and arbitrarily assign higher priority to one of them, e.g., $a' > a''$. The modified priority sequence, $a' > a'' > b > c$, is then considered with the model viewed from the side remote from *c*. If this gives a right-handed ordering for $a' \rightarrow a'' \rightarrow b$, thus leading to *R* chirality for the arbitrarily created chiral element, the promoted a' is designated the *pro-R* group; conversely, if the arbitrarily created chiral element reveals an *S* ordering, the promoted group is *pro-S*. Example: glycerol, $HOCH_2$–CHOH–CH_2OH, contains two chemically-like CH_2OH groups, and the normal priority sequence is OH > CH_2OH > H. In the **Fischer projection** formula with the central carbon atom having the OH group to the right and H to the left, arbitrarily assign the top $C'H_2OH$ group priority over that at the bottom, $C''H_2OH$, giving the modified sequence, OH > $C'H_2OH$ (top) > $C''H_2OH$ (bottom) > H. When the model is viewed from the side remote from the lowest priority atom (H) the ordering, OH → $C'H_2OH$ (top) → CH_2OH (bottom) is right-handed so that the arbitrarily created chiral element has *R* chirality; hence the top $C'H_2OH$ is the *pro-R* group. Subscript letters *R* and *S* can be used to indicate whether an atom or group of atoms is *pro-R* or *pro-S*. This is most commonly done for the two hydrogens of a methylene group, with H_R indicating the *pro-R* hydrogen and H_S the *pro-S* hydrogen. For a methylene group, replacement of ^1H_R by ^2H or ^3H gives a centre with *R* chirality; similar replacement of ^1H_S gives a centre with *S* chirality. *See also* **enantiotopic**.

pros a designator of position of a nitrogen in the histidine imidazole ring, being that nitrogen nearest to the side chain; often abbreviated to π, as in N^{π}. *Compare* **tele**.

prosaposin the polyprotein precursor (524 amino acids) of the **saposins**. A mutation in the translation initiation codon leads to a very rare prosaposin deficiency (and thus deficiency of all saposins), which is rapidly fatal in infancy.

PROSITE *see* **pattern database**.

prosolin *see* **stathmin**.

prosome *another name for* **proteasome**.

Prospero a transcription factor localized in the basal cortical crescent of *Drosophila* neuroblasts that enters the nucleus after cell division to activate ganglion mother cell genes, repress neuroblast-specific genes, and cause differentiation into neurons.

prostacyclin *or* **prostaglandin I** (*abbr.*: PGI) any of a group of prostanoids synthesized by **prostaglandin-I synthase** (EC 5.3.99.4) from prostaglandin H – which itself is the product of **prostaglandin-endoperoxide synthase** – as prostaglandin I_2, I_1, or I_3, depending on whether the substrate for the enzyme is arachidonate, dihomo-(6,9,12)-linolenate, or eicosa-5,8,11,14,17-pentaenoate respectively. PGI_2 is the major product *in vivo*; it is produced by endothelial cells of blood-vessel walls, has potent platelet anti-aggregatory properties resulting from stimulation of adenylate cyclase, and induces vasodilation. It has a normal half-life of 2 min, being degraded by hydrolysis to 6-oxo-prostaglandin $F_{1\alpha}$; this is then converted to the 6,15-dioxo-13,14-dihydro-$PGF_{1\alpha}$, and follows a similar degradative path to other prostaglandins. More stable but still active analogues have been synthesized, e.g. carbacyclin. (*S*)-15-hydroperoxyeicosatetraenoate inhibits prostaglandin-I synthase. *See also* **prostaglandin**.



prostaglandin I_2

prostacyclin synthase *see* **prostaglandin-I synthase**.

prostaglandin *abbr.*: PG; any of a group of biologically active metabolites of arachidonate (PG_2 series), dihomo-γ-linolenate (PG_1 series), or eicosa-5,8,11,14,17-pentaenoate (PG_3 series). They characteristically contain a cyclopentane ring due to formation of a bond between C-18 and C-12 of the fatty acid; hydroxy or oxo substitution at positions 9 and 11 is a major distinguishing feature between prostaglandin classes. They possess a protean array of highly potent biological activities that defy simplification. Their pharmacological effects include: vasodilation (PGE_2 and **prostacyclin**) which is short-acting, and vasoconstriction ($PGF_{2\alpha}$ and **thromboxane** A_2); oxytocic activity ($PGF_{2\alpha}$ can be used to terminate pregnancy in the second trimester and PGE_2 induces labour at term); bronchodilation (PGE series) and constriction (PGF series). They are involved in inflammatory reactions, and the enzymes that synthesize them are targets for antiinflammatory agents such as aspirin and non-steroidal antiinflammatory drugs such as ibuprofen. They are also involved in the regulation of cell proliferation in normal and neoplastically transformed cells. Prostaglandins are formed from the precursors prostaglandin G_1, G_2, or G_3, the intermediate products of **prostaglandin-endoperoxide synthase**, depending on the substrate fatty acid; the same enzyme converts these to prostaglandins H, from which other enzymes form prostaglandins D, E, and F, and also **prostacyclins** (or prostaglandins I). These are the bioactive products of the system, but they have a half-life of minutes, being rapidly converted to metabolites with much weaker, or often inhibitory properties. The initial metabolites are the 15-oxo-13,14-dihydroprostaglandins, produced by the sequential actions of 15-hydroxyprostaglandin dehydrogenases (e.g. EC 1.1.1.196 and 1.1.1.197) and 15-oxoprostaglandin 13-reductase (EC 1.3.1.48); these are further degraded by beta oxidation and omega oxidation to urinary metabolites such as 7α-hydroxy-5,11-dioxotetranorprostane-1,16-dioate (from PGE_2) and 5,7-dihydroxy-11-oxotetranorprostane-1,16-dioate. The structures of prostanoic acid, with its carbon numbering, and of PGG_2, PGH_2, PGD_2, PGE_2 and $PGF_{2\alpha}$ are shown.



prostaglandin D_2



prostaglandin E_2



prostaglandin $F_{2\alpha}$



prostaglandin G_2



prostaglandin H_2



prostanoic acid

prostaglandin-D synthase *abbr*.: PGD synthase; EC 5.3.99.2; *other name*: prostaglandin-H_2 D-isomerase; an enzyme that catalyses the conversion of (5*Z*,13*E*)-(15*S*)-9α,11α-epidioxy-15-hydroxyprosta-5,13-dienoate to (5*Z*,13*E*)-(15*S*)-9α,15-dihydroxy-11-oxoprosta-5,13-dienoate (prostaglandin D). Glutathione is a cofactor in some cases.

prostaglandin-endoperoxide synthase EC 1.14.99.1; *other names*: prostaglandin synthase; prostaglandin G/H synthase. An enzyme whose reaction embraces the activity formerly called **cyclooxygenase**; it catalyses a reaction between dioxygen, arachidonate and two molecules of reduced glutathione (GSH) to form prostaglandin H_2, oxidized glutathione (GSSG), and H_2O. The enzyme acts as both a dioxygenase and as a peroxidase. It catalyses the formation of the precursor, prostaglandin G_2 (PGG_2), for the biosynthesis of all prostanoid compounds, by forming an endoperoxide bridge between C-9 and C-11, simultaneously bonding C-8 and C-12 to form the cyclopentane ring, and also forming the hydroperoxide at C-15. The latter is reduced by a reduced glutathione (GSH)-dependent peroxidase activity of the enzyme to a hydroxyl group to form prostaglandin H_2; these, and their further metabolites, prostaglandins D, E and F, are highly potent bioactive compounds with a great diversity of actions (*see* **prostaglandin**). The enzyme can also act on dihomo-(6,9,12)-linolenic acid, to form a series of prostaglandins (denoted by a subscript 1, e.g. PGE_1) lacking the C-5 double bond, and on eicosa-5,8,11,14,17-pentaenoic acid, to form the 3 series of prostaglandins (e.g. PGE_3), with the additional double bond at C-17. Two isoenzymes, COX-1, constitutively expressed, and COX-2, inducible in inflammation by cytokines, are highly homologous membrane proteins, but selective inhibition of COX-2 is possible due to its larger inhibitor-binding site. Aspirin acetylates an active-site serine residue in both, the IC_{50} being 10 to 100 times lower for COX-1 than for COX-2. Its inhibiton of COX-1 is the basis of its antithrombotic effects. *See also* **prostacyclin**, **thromboxane**.

prostaglandin-E_2 9-reductase EC 1.1.1.189; an enzyme that catalyses the reduction by NADPH of (5*Z*,13*E*)-(15*S*)-11α,15-dihydroxy-9-oxoprosta-5,13-dienoate (PGE_2) to (5*Z*,13*E*)-(15*S*)-9α,11α,15-trihydroxyprosta-5,13-dienoate ($PGF_{2\alpha}$) with formation of $NADP^+$. The monomeric cytoplasmic human enzyme catalyses reduction of many carbonyl compounds. In addition to the activity of prostaglandin-E_2 9-reductase (also termed prostaglandin 9-ketoreductase), it also contains two other activities: carbonyl reductase (NADPH) EC 1.1.1.184, and 15-hydroxyprostaglandin dehydrogenase ($NADP^+$), EC 1.1.1.197.

prostaglandin-E synthase EC 5.3.99.3; *other names*: prostaglandin-H_2 E-isomerase; endoperoxide isomerase; an enzyme that catalyses the conversion of (5*Z*,13*E*)-(15*S*)-9α,11α-epidioxy-15-hydroxyprosta-5,13-dienoate to (5*z*,13*e*)-(15*s*)-11α,15-dihydroxy-9-oxoprosta-5,13-dienoate (PGE_2). Glutathione is a cofactor.

prostaglandin-F synthase EC 1.1.1.188; *other name*: prostaglandin-D_2 11-reductase; an enzyme that catalyses the formation of (5*Z*,13*E*)-(15*S*)-9α,11α,15-trihydroxyprosta-5,13-dienoate and $NADP^+$ from (5*Z*,13*E*)-(15*S*)-9α,15-dihydroxy-11-oxoprosta-5,13-dienoate and NADPH.

prostaglandin-I synthase EC 5.3.99.4; *other name*: prostacyclin synthase; an enzyme that catalyses the conversion of (5*Z*,13*E*)-(15*S*)-9α,11α-epidioxy-15-hydroxyprosta-5,13-dienoate to (5*Z*,13*E*)-(15*S*)-6,9α-epoxy-11α,15-dihydroxyprosta-5,13-dienoate (PGI_2, prostacyclin). This is a heme-thiolate protein.

prostanoate the anion of prostanoic acid, 2-octylcyclopentaneheptanoic acid; the 8*S*,12*S* form is the parent compound for prostanoid nomenclature. For structure, *see* **prostaglandin**.

prostanoid any compound based on or derived from the **prostanoate** structure, including the **prostaglandins**, **prostacyclins**, and **thromboxanes**.

prostasin a serine protease with trypsin-like activity, found in human seminal fluid.

prostate-specific antigen *abbr*.: PSA; a serine endopeptidase belonging to the family of glandular **kallikreins** with a His-Asp-Ser **charge-relay system**. It is virtually prostate specific. Levels may be elevated in prostate hypertrophy but the release from prostate cancer is higher than from normal tissue. It is a much better marker than **acid phosphatase**, being elevated at an earlier stage of the tumour. Its physiological substrate is the predominant protein of the seminal vesicle coagulum.

prostatic of, pertaining to, or related to the prostate gland.

prosthetic group a non-protein group that is combined specifically with a protein, in stoichiometric proportion.

prostin a prostatic serine endopeptidase that is not related to the kallikreins. *Compare* **prostate-specific antigen**.

protachykinin β precursor a preproprotein from which certain polypeptide hormones are cleaved, not all by the same processing pathway. For example, from the human precursor, the derived peptides are **substance P**, **neurokinin A**, and **neuropeptide K**. *See also* **tachykinin**.

protamine any of a group of small peptides, containing arginine, alanine, and serine, that are isolated from the sperm of fish (e.g., salmon, herring, sturgeon, trout, and mackerel), but are present in the sperm of all animals. They have a histone-like function in the chromatin of sperm, compacting sperm DNA into a condensed complex.

protamine sulfate a sulfated derivative of a **protamine**. Protamine sulfates combine with, and inactivate, **heparin**, and are used to prevent bleeding in heparin overdose.

protease any enzyme that catalyses the hydrolysis of peptide bonds in a protein or polypeptide. The specific names **endopeptidase**, **aminopeptidase**, and **carboxypeptidase** are recommended. *See also* **proteinase**.

protease-activated G-protein-coupled receptor *see* **PAR**.

protease inhibitor 4 *see* **kallistatin**.

protease nexin I *see* **nexin 1**.

proteasome *or* **proteosome** EC 3.4.99.46 *recommended name*: multicatalytic endopeptidase complex; *other names*: multicatalytic proteinase (complex); ingensin; macropain; prosome; lens neutral proteinase. Proteasomes are large multi-subunit protease complexes that selectively degrade intracellular proteins that are tagged for destruction by ubiquitination. They control cellular processes, such as metabolism and the cell cycle, through signal-mediated proteolysis of key enzymes and regulatory proteins. They also operate in the stress response, by removing abnormal proteins, and in the immune response, by generating antigenic peptides. The proteolytic activity is due to a 26S protease (a 2 MDa complex), whose ability to degrade proteins generally depends on both the ubiquitination of the substrate and the presence of ATP. At the core is a 20S particle that carries the catalytic activity. When first isolated, it was called ‘multicatalytic proteinase’ because of its ability to cleave peptide bonds carboxy-terminal to basic, hydrophobic, and acidic residues. The 20S particle does not require ATP for activity. The crystal structure of this core from the archaean *Thermoplasma acidophilum* has been determined. The core alone is inactive because it requires two specific subunits of a 19S particle to mediate recognition of ubiquitin–protein conjugates. The core subunits are arranged in four heptameric rings, stacked to form a hollow cylinder with the protease activity on the inside. The active site nucleophile is threonine. The protein substrate first must be unfolded and the disulfide bonds reduced before entry into the cylinder. In *Thermoplasma*, the two outer rings are composed of seven α subunits, and each inner ring contains seven β subunits. The enzyme catalyses the cleavage at Xaa-|- bonds in which Xaa carries a hydrophobic, basic, or acidic side chain. Components of the human proteasome include: c2, c3, c5, c7, c8, c9, β chain, c13, δ chain, ε chain, mecl-1, τ chain, and ζ chain.

protectin *see* **CD59**.

protecting group *or* **protective group** *or* **blocking group** any chemical group added to a reactive centre of a molecule to prevent it from reacting during chemical treatments in which it is not intended to participate. Such groups are commonly used during chemical synthesis of macromolecules or shorter polymers of amino acids or nucleotides. Reagents contributing protecting groups should react readily under mild conditions, with high specificity, and lead to addition of a group that can be removed highly specifically under mild conditions. For protein or amino-acid protecting groups *see* **aminoethyl**, **Boc**, **citraconylation**, **DABITC**, **dabsyl**, **dansyl**, **Fmoc**, **maleylation**, **pipsyl**, **silylation**, **succinylation**, **tosyl**, **triphenylmethyl group**.

protection of telomeres-1 *see* **Pot-1**.

protective protein/cathepsin C *abbr*.: PPCA; a lysosomal multifunctional protein that has separate protective properties (for lysosomal *β*-galactosidase and neuraminidase) and catalytic properties (being a serine protease). The gene at 20q13.1 encodes a glycoprotein of 480 residues, which is processed to form a 32 kDa polypeptide joined by a disulfide bridge to another of 20 kDa. A serine on the heavy chain, and a histidine and an aspartate on the light chain constitute the catalytic triad. It is active as cathepsin A at acid pH, and as an amidase (e.g. for substance P, endothelin I, and neurokinin) and an esterase at neutral pH. At least a dozen point mutations in the gene are known to cause **galactosialidosis**, in which there is a triple enzyme deficiency.

protegrin *abbr*.: PG; any of a group of leukocyte antimicrobial peptides, denoted PG-1 to PG-5, that are active against *Escherichia coli*, *Listeria monocytogenes*, and *Candida albicans in vitro*. Like **tachyplesins**, they contain two intramolecular cystine disulfide bonds, and share similarity with **defensins**.

protein any of a large group of organic compounds found as major macromolecular constituents of living organisms. All enzymes are proteins, although catalytic activity is shown by some nucleic-acid molecules (*see* **ribozyme**). A protein is a linear polymer of **amino acids** linked by peptide bonds in a specific sequence. In the biosynthesis of the polypeptide chain, any of 20 different amino acids may be incorporated, according to the genetic instructions of the cell (*see* **protein and peptide biosynthesis**). The amino-acid residues may subsequently be modified so that the chains may contain a much wider variety of residues, amounting to nearly 200. The modifications may involve the covalent attachment of various groups, such as carbohydrates and phosphate; these are the simple proteins. Other substances may be more loosely associated with the polypeptide chains, such as heme or lipid, giving rise to **conjugated proteins**. Four hierarchies of structure have been defined for polypeptide chains, termed **primary structure**, **secondary structure**, **tertiary structure**, and **quaternary structure**. Four classes of protein have been recognized, which differ according to their content of **alpha helices** and **beta sheets**: all-alpha; all-beta; alpha/beta; and alpha + beta. Some important protein types are listed separately in this dictionary, and many others are listed individually: e.g., contractile proteins (**actin**, **myosin**, **tropomyosin**, **tubulin**), **heat-shock proteins**, **hemoproteins** (**cytochromes**, **hemoglobin**, **myoglobin**), **lipoproteins**, **membrane proteins** (**ATPases**, **ion channels**, **rhodopsin**), non-heme proteins (**blood coagulation** factors, **serum albumin**, **serum globulin**), nuclear proteins (**histones**), **plasma proteins**, and structural proteins (**collagen**, **crystallin**, **keratin**). Nutritional aspects of protein metabolism include the fact that higher animals cannot synthesize certain of the amino acids required for protein synthesis; these are referred to as **essential amino acids**. Plants and most microorganisms can synthesize all of the amino acids required for protein synthesis, and many others. The nutritional value of different proteins depends on their composition. Some proteins are of poor nutritional value, owing to lack of essential amino acids, e.g. gliadin, which lacks lysine, and zein, which lacks lysine and tryptophan. —**proteinaceous** *adj.*

14-3-3 protein any of a highly conserved family of proteins, widespread in higher eukaryotes, that seem to act as regulators in signal transduction or phosphorylation. The name derives from the migration position on DEAE–cellulose columns, and on starch-gel electrophoresis, of certain brain proteins that were the first members of the family to be studied. Members of this family have been implicated in regulation of **protein kinase C**, transcriptional regulation in plants, exocytosis, cell-cycle regulation, and interaction with **Raf** in the **MAP kinase** cascade. For example, 14-3-3 protein β (*other name*: protein kinase C inhibitor protein-1) from sheep activates tyrosine and tryptophan hydroxylases in the presence of Ca^{2+}/calmodulin-dependent protein kinase II. The bovine equivalent has an identical sequence: it is a homodimer.

protein A a bacterial cell-wall protein, found in many strains of *Staphylococcus aureus*, that can bind, without masking the antigen-binding site, to the Fc region of IgG. It binds weakly to human IgA, IgE, and IgM, but fails to bind to human IgG_3 and IgD; it does not bind to cell Fc receptors. The purified protein, or a preparation of cells of *S. aureus* that carry protein A, is widely used as an immunochemical reagent, often in an immobilized form on affinity columns, for isolation and purification of immunoglobulins and, by forming ternary complexes, of antigens and immune complexes. It is also used as a binding reagent in enzyme-linked immunoassay, in histochemistry, and in blotting techniques.

protein and peptide biosynthesis the biochemical synthesis of proteins. The synthesis of most peptides in living cells depends on the presence of **ribosomes**. This includes the small peptide hormones, such as **oxytocin** and **vasopressin**, which are synthesized as precursor proteins. Other peptides are not synthesized by means of ribosomes. Thus **glutathione** is synthesized by soluble enzymes in two steps. Many biologically active peptides, especially cyclic structures, are products of microorganisms. These include such antibiotic peptides as **gramicidin S**, the **tyrocidines**, and the **polymyxins, which are synthesized by** interacting multienzymes in which activated aminoacyl groups are transferred onto –SH groups to form intermediate thioesters. The multienzymes are unusual in size, ranging from 120 to 1700 kDa. They consist of repeating modules, each responsible for the incorporation of one amino-acid residue. The genes are arranged in clusters associated with genes encoding auxiliary proteins for the synthesis of precursors, modifying enzymes, exporting proteins, and regulatory systems. In addition to the amino acids and ATP, *S*-adenosylmethionine is required as methyl group donor if *N*-methylated bonds are involved. Due to their complexity (cyclosporin synthase for example, integrates 40 reactions on one polypeptide chain), the multienzyme systems have low turnover numbers. Cell-free systems for the production of various peptides and their analogues have been developed.

For synthesis involving ribosomes the first step is the activation of the amino acids to form amino-acid **adenylates**. The amino acids then become attached by an ester linkage to **transfer RNA** (tRNA). The template is **messenger RNA** (mRNA), which associates with the ribosomes themselves. The **translation** of the triplet codons in mRNA to provide a polypeptide involves three steps: chain initiation, chain elongation (*see* **elongation factor**), and chain termination (*see* **release factor**). Chain initiation normally starts with the codon for methionine, **AUG, and involves** a unique initiator tRNA. Many protein factors play a part in the three processes and five molecules of ATP and GTP participate. The ribosomes participate in a cycle during which they subdivide into their two subunits only to reassemble. Hence the synthesis of a peptide bond is a surprisingly expensive process in terms of energy. The targeting of the newly synthesized proteins to their final destination is termed **protein kinesis**. The mechanism of ribosomal protein synthesis is very similar in all types of cell but there are subtle differences in the number and properties of the soluble factors, particularly concerning chain initiation: in prokaryotes this is by way of formylmethionine while in eukaryotes, apart from mitochondria, this involves methionine.

proteinase an enzyme that catalyses the hydrolysis of peptide bonds more readily in an intact protein than in small peptides. **Endopeptidase** is now recommended.

proteinase K EC 3.4.21.64; *recommended name*: endopeptidase K; *other name*: *Tritirachium* alkaline proteinase. A serine proteinase enzyme that catalyses the hydrolysis of keratin, and of other proteins with subtilisin-like specificity.

protein A-Sepharose an affinity chromatography medium for the purification or precipitation of immunoglobulins made by covalent coupling of **protein A** to agarose beads.

proteinase V8 *see* **glutamyl endopeptidase**.

protein B a cell-surface protein of group B *Streptococcus* species that binds specifically to the Fc region of human IgA, without affecting its antigen-binding capacity, but not to other immunoglobulins or serum proteins. It is used in enzyme- linked immunoassay and blotting techniques.

protein biosynthesis *see* **protein and peptide biosynthesis**.

protein body a membrane-delimited aggregate of prolamins that accumulates within regions of the endoplasmic reticulum in the endosperm of cereals (barley, maize, oats, wheat, etc.). The membrane surface often contains trapped polysomes as a result of the nascent prolamin molecules aggregating with those already stored. *Compare* **protein storage vacuole**.

protein-bound iodine *abbr*.: PBI; that fraction of iodinated molecules bound to protein in serum. It is due largely to thyroxine (T_4), 99.97% of which in human serum is present bound to the binding proteins T_4-binding globulin, T_4-binding prealbumin and albumin, but also to T_3, 99.7% of which is bound to the same proteins. Determination of PBI (now replaced by immunoassay) was used for estimation of blood thyroid hormones as a basis for assessment of thyroid function.

protein C a **vitamin K**-dependent glycoprotein that is the **zymogen** of a serine endopeptidase in normal blood plasma; M_r 62 000 (human), 54 300 (bovine). It is formed from a precursor, autoprothrombin IIA, which is cleaved into a light chain and a heavy chain, held together by a disulfide bond to form protein C. Thrombin cleaves a tetradecapeptide from the amino end of the heavy chain; this reaction, which occurs at the surface of endothelial cells, is strongly promoted by thrombomodulin; protein C then becomes the enzyme protein C (activated), EC 3.4.21.69. This activated form specifically hydrolyses factors Va and VIIIa to inactive forms (in a reaction requiring phospholipid, calcium, and **protein S**), thereby acting as a potent anticoagulation factor; it contains 10–12 γ-carboxyglutamyl residues in the N-terminal 40 residues. A congenital deficiency of protein C (usually autosomal dominant) is often not compatible with survival, or leads to hemorrhagic disease of the newborn. Protein C is so named because it eluted from columns as the third of four peaks labelled A, B, C and D.

protein C23 *see* **nucleolin**.

protein C-binding protein *see* **apolipoprotein H**.

protein degradation the hydrolytic catabolism of proteins that occurs in the intestinal tract during digestion or intracellularly as part of regular turnover or apoptosis. Eukaryotic cells contain several proteolytic systems. The **vacuolar pathway** involves **endosomes** and **lysosomes** for the breakdown of extracellular proteins that enter cells by endocytosis. Lysosomes also degrade membrane proteins and proteins with long half-lives. In well-nourished organisms the lysosomes are nonselective but in some organs (e.g. liver and kidney) after prolonged fasting they are selective for cytosolic proteins that contain the pentapeptide sequence –KFERQ– or a related one. The **cytosolic system** is largely ubiquitin- and ATP-dependent and is mediated by **proteasomes**. Cytosolic **procaspases** are activated early during apoptosis. **Calpains** are also cytosolic. In the lumen of the endoplasmic reticulum, misfolded or unfolded proteins are degraded by proteases that function at high Ca^{2+} concentrations. Bacteria, mitochondria, and chloroplasts contain **AAA proteases** that degrade nonintegrated membrane proteins. *See* **PETS hypothesis**; **N-end rule**.

protein disulfide-isomerase *abbr*.: PDI; EC 5.3.4.1; *other name*: disulfide rearrangase; an enzyme that enhances the rate of interchange in the groups attached to two or more intrachain or interchain disulfide bonds in a protein. First described by Anfinsen in 1966 in connection with the reversible denaturation of ribonuclease and called 'rearrangase', it is a homodimer of the endoplasmic reticulum lumen and contains two domains homologous to **thioredoxin** of *Escherichia coli*. It is also the triacylglycerol transfer protein (MTP) that facilitates the incorporation of lipids into newly synthesized core **lipoproteins** within the endoplasmic reticulum. It serves as the β subunit of **procollagen-proline dioxygenase**.

protein engineering the process whereby a protein of any desired primary structure can (in principle) be created by the use of recombinant DNA technology. The ability to express DNA in a bacterium such as *Escherichia coli* creates the potential to synthesize a protein with the desired primary structure. Bacteria cannot effect post-translational modifications so if these also are required a eukaryotic host cell such as yeast must be employed. In principle there are no problems with the proteins of bacterial cells but **introns** present in the genome of eukaryotic cells present a potential problem. This can be overcome by preparing complementary DNA, **cDNA**, which is synthesized by the use of the **mRNA** as template and the enzyme **reverse transcriptase**. There are several ways whereby the DNA for the required protein may be prepared by modification of the base sequence of the natural DNA. DNA may be used that contains inserts of synthetic oligonucleotides, or stretches replaced by these. Oligonucleotide-directed mutagenesis may be used to modify a single base to produce a protein with a single amino-acid replacement. This is done by preparing an oligonucleotide primer with the modified sequence which will base pair with the natural DNA around the site to be altered; a single base substitution still permits satisfactory pairing. The primer is elongated by DNA polymerase and the double-stranded circle closed by **DNA ligase**. A specific deletion can be obtained by cleaving a plasmid at two sites with a restriction enzyme and religating to form a smaller circle. A smaller deletion can be obtained by cutting a plasmid at a single site. The ends of the linear DNA are then digested with an exonuclease that removes nucleotides from both strands and the shortened piece of DNA is religated.

protein expression map a map of protein expression in particular tissues or species, under particular conditions, generated from 2D electrophoresis data. Such maps are often used to compare samples exposed to different conditions, and hence to identify groups of proteins that have related functions or whose expression is interdependent. As 2D gels can reveal PTMs, the resulting maps can provide more relevant information about cellular dynamics than corresponding expression maps at the mRNA level.

protein family a set of proteins that share a common evolutionary history, often arising via duplication of an ancestral gene. Families, which tend to be defined via their sequence, functional, and/or structural relationships, can be arranged hierarchically, whereby closely related proteins with a recent common ancestor comprise subfamilies, and larger groups of distant homologues comprise superfamilies.

protein folding the process by which a polypeptide chain assumes its 3D conformation.

protein folding disease any disease that results from the abnormal folding of a protein. **Prion** diseases are examples of such diseases that can be inherited or acquired; **Alzheimer's disease** is a different type of disease, caused by alternative folding of proteins derived from the amyloid precursor.

protein fusion *an alternative name for* **gene fusion**.

protein G a bacterial cell-wall protein isolated from group G streptococci. Its properties and uses are similar to those of **protein A**, but it does not bind to IgM, IgD, or IgA; it does bind to all subclasses of human IgG, and animal immunoglobulins, with which protein A does not react well.

protein gene product any one of the proteins, or protein subunits, synthesized biochemically on the basis of information encoded in a genome, whether generated at **translation** or by **post-translational modification**; the pattern of protein gene products formed, or capable of being formed, by an organism is unique to any one genotype. Individual proteins are often referred to using the symbol p, followed by the relative molecular mass, e.g. p53. The protein may be further identified by adding an indication of its origin as a superscript, e.g. $p21_{ras}$. A protein gene product may also be referred to by the name of the gene that encodes it, but normal font is used instead of italics, with a capital initial followed by lower case characters, e.g. Src protein encoded by *SRC* gene.

protein-glutamate methylesterase a chemotaxis protein encoded by *cheB* (*see* ***che***).

protein–glutamine *γ*-glutamyltransferase the product of one gene in invertebrates, but any of nine in vertebrates. The best known is **factor XIIIa** (EC 2.3.2.13) (*see* **blood coagulation**). It forms inter- and intramolecular links between a γ-carboxyl group of a glutamine residue of a protein and the ε-amino group of a lysine residue, releasing ammonium ion. Its natural substrate is the **fibrin** monomer, and its function is to link these into polymers.

Transglutaminase K *other names*: transglutaminase 1; keratinocyte transglutaminase; an enzyme that catalyses formation of cross-linkages in the cell envelope (*see* **involucrin**) that replaces the plasma membrane of fully differentiated keratinocytes where it is anchored to the inner surface of the membrane. Several mutations at 14q11.2 are responsible for an autosomal recessive form of ichthyosis.

Transglutaminase 2 *other name*: tissue transglutaminase; a constitutive enzyme in endothelial and smooth muscle cells, and inducible (e.g. by retinoic acid) in other cell types. It is localized to plasma membrane, cytoskeleton, and nucleus. The human enzyme (686 amino acids) is a G-protein (called Gh/TG2) that mediates transmembrane signalling by stimulating phospholipase C, and cell-surface adhesion following externalization by cells. It is involved in generating stimulatory gluten peptides in celiac disease.

protein intron *see* **intein**; **splicing** (def. 3).

protein kinase any of a number of enzymes that phosphorylate one or more hydroxyl or phenolic groups in proteins, ATP being the phosphoryl-group donor. Two classes are recognized: those that phosphorylate seryl or threonyl hydroxyls, and those that phosphorylate tyrosyl phenolic groups. The first class contains enzymes that were classically identified as regulating pathways of intermediary metabolism (e.g. glycogen **phosphorylase kinase**); subsequently, protein kinase A (**cyclic-AMP-dependent protein kinase**) and **protein kinase C** were recognized in this class. Enzyme activity of the second class is found in some cytokine receptors such as **platelet-derived growth factor receptor** and **epidermal growth factor receptor** and in oncogene products such as that of *SRC*. Over 110 unique gene products are known to make up the protein kinase superfamily; important motifs include GXGXXG...AHK and APE...DXWSXG, which are common to both serine/threonine- and tyrosine-specific activities. The tyrosine-specific kinase activity associated with the cytoplasmic domains of certain cytokine receptors forms part of an important signal-transduction mechanism implicated in cell growth (*see* **tyrosine kinase**).

protein kinase A *an alternative name for* **cyclic-AMP-dependent protein kinase**.

protein kinase B (*abbr.*: PKB) *or* **Akt** a cytosolic protein-serine/threonine kinase that plays a significant role in insulin and growth factor signalling, cellular survival, and transformation. It contains a pleckstrin homology domain for binding phosphatidylinositides, and is a major target for phosphatidylinositol trisphosphate kinase and for phosphatidylinositide-dependent protein kinase. The activities of these enzymes are provoked by various tyrosine kinase receptors for growth factors (e.g. those for platelet-derived growth factor, epidermal growth factor, fibroblast growth factor, and insulin). There are three isozymes (Akt 1, 2, and 3) in humans and rodents. Akt 2 (PKBβ) is enriched in insulin-responsive tissues. Mice deficient in Akt 2 are insulin-resistant and develop a diabetes mellitus-like syndrome. Substrates for Akt 2 include: **GSK-3**, ribosomal S6 kinase, several transcription factors (including those of the forkhead family), and APC protein (*see* ***APC***).

protein kinase C *abbr.*: PKC; any **protein kinase** enzyme that requires anionic phospholipid for activity, and is regulated by diacylglycerol and Ca^{2+}. Such enzymes phosphorylate serine and threonine residues. Several isoforms have now been characterized: α, β_1, β_2, γ, δ, ε, ζ, θ, η, ι, and μ. Four conserved regions are recognized, C_1, C_2, C_3, and C_4; C_3 and C_4 comprise the C-terminal half of the molecule and bear the active site, including the ATP-binding sequence GXGXXG...K. PKC-ε is Ca^{2+}-independent, and δ, ε, and ζ lack the homologous C_2 region. Activation of PKC occurs when plasma membrane receptors coupled to phospholipase C are themselves activated, releasing diacylglycerol. Phorbol ester tumour promoters can substitute for diacylglycerol in enzyme activation, which may indicate their mechanism of action, and much evidence points to PKC activation being involved in cell-growth stimulation. Inhibitors of PKC attract considerable interest, and include **bisindolylmaleimide**, 1-O-hexadecyl-2-O-methylglycerol, **melittin**, **phloretin**, **polymyxin** B, and **staurosporine**.

protein kinesis the directed movement of proteins from their site of synthesis to specific targets within cells and the modulation by proteins of interactions among intracellular organelles. It is a factor in generating subcellular compartments and determining the way in which reactions are compartmentalized to control metabolic processes. It embraces the mechanisms for ensuring that proteins reach their site of action and that the amounts and locations of particular proteins are controlled during development, during the cell-division cycle, in combating pathological states of the cell, and during apoptosis.

protein mapping the resolution of a mixture of proteins into a two-dimensional pattern (i.e. map) by successive use of two differing separative procedures, as in isoelectric focusing followed by gradient gel electrophoresis, the pattern being rendered visible by an appropriate detection method.

protein phosphatase any enzyme that hydrolyses phosphate groups from proteins. With protein kinases, these enzymes provide an important mechanism for regulating cellular activity. Protein phosphatases fall into three groups. **Class I enzymes** are mainly specific for seryl- or threonyl-phosphate. Phosphatase 1 is ATP,Mg^{2+}-dependent (AMD phosphatase); it consists of a catalytic subunit of 38 kDa and a regulatory (or glycogen-binding) subunit of 126 kDa, which on phosphorylation activates the phosphatase. Phosphatase 2A is polycation-stimulated (PCS), being directly stimulated by protamine, polylysine, or histone H1; it constitutes a subclass of several enzymes activated by different histones and polylysine. These have a very high affinity for the tumour promoter **okadaic acid**. Human phosphatase 2A has a catalytic subunit of 309 amino acids. This enzyme can modulate the activities of phosphorylase kinase *b*, casein kinase 2, mitogen-stimulated S6 kinase, and MAP-2 kinase. It is a cytoplasmic enzyme that exists in several oligomeric forms, all of which contain a catalytic (C) subunit (36–38 kDa) associated with one or both of two putatively regulatory subunits, the A subunit (61–65 kDa) and the B subunit (51–55 kDa). Phosphatase 2B (or **calcineurin**) consists of a subunit of 61 kDa, which contains the catalytic site and a high-affinity calmodulin-binding site, and a Ca^{2+}-binding subunit of 19 kDa. Phosphatase 2C is a Mg^{2+}-dependent monomeric 43 kDa protein; it has been purified as myosin light chain phosphatase, but is active against the phosphorylated forms of glycogen synthase, 6-phosphofructo-1-kinase, pyruvate kinase, fructose 1,6-bisphosphatase, and 6-phosphofructo-2-kinase. **Class II enzymes** hydrolyse tyrosylphosphates, and are generally designated ‘phosphatase 3’. Some are cytoplasmic, and others are membrane-bound and may have receptor properties. **Class III enzymes** have dual specificity.

protein-N^{π}-phosphohistidine–sugar phosphotransferase EC 2.7.1.69; *systematic name*: protein-N^{π}-phosphohistidine:sugar N^{π}-phosphotransferase; *other name* enzyme II; any membrane-bound bacterial enzyme that forms part of the **phospho*enol*pyruvate-dependent sugar phosphotransferase system** for the transport of hexoses across the cell membrane. It involves phosphorylation of a protein substrate (9.5 kDa), a phosphocarrier known as HPr. Individual enzymes are specific for a range of sugars. They catalyse the reaction:

$$\text{protein } N^{\pi}\text{-phosphohistidine (HPr) + sugar =}$$
$$\text{protein histidine + sugar phosphate.}$$

protein S a single-chain glycoprotein occurring in blood, M_r 69 000. It is a vitamin K-dependent protein (not a protease) that promotes the binding of **protein C** to platelets, and functions as a cofactor for the anticoagulant activity of activated protein C. It is named after Seattle, where it was discovered.

protein sorting the secretory and endocytic processes by which proteins are directed to specific locations inside or outside the cell.

protein sorting signal a motif in the sequence of a protein which determines the compartment to which it is directed in the cell.

protein splicing *see* **splicing**.

protein storage vacuole *or* **vacuolar protein body** a specialized vacuole in the reserve tissue of seeds that contains 7S (vicilin-type) or 11S (legumin-type) globulins. The proteins are synthesized on the endoplasmic reticulum and transported to storage vacuoles via the Golgi apparatus, where the 7S type are glycosylated but the 11S rarely so. Protein deposition occurs during seed maturation, whereas breakdown occurs during germination to provide amino acids to the new seedling. The vacuoles also contain other proteins such as lectins and enzyme inhibitors. *Compare* **protein body**.

protein synthesis 1 *(in cell biology) see* **protein and peptide biosynthesis**. **2** *(in chemistry) see* **peptide synthesis** (def. 2).

protein targeting to glycogen *see* **PTG**.

protein thiotemplate mechanism *see* **thiotemplate mechanism**.

protein truncation test *abbr*.: PTT; a method for the detection of mutations that lead to the premature termination of translation and hence a truncated protein product. Preferably mRNA is the template for amplification by reverse transcription-polymerase chain reaction (RT-PCR) using a forward primer that incorporates the promoter for T7 RNA polymerase and a **Kozak** translation initiation sequence. The product is used in a transcription and translation system *in vitro* to produce a radiolabelled polypeptide that can be detected by autoradiography following SDS-PAGE. Alternatively, a c-*myc* epitope tag can be encoded in the forward primer enabling the detection of the protein product by anti-MYC antibodies following Western blotting. The sizes of the wild-type and mutant gene products can be compared alongside each other on the gel.

proteinuria the presence of protein in urine. Normal excretion of protein in human urine is less than 0.1 mg every 24h, about half of which is **Tamm–Horsfall glycoprotein**, and about 20% is albumin. Protein may appear in urine due to extrarenal factors such as fever, strenuous exercise, or burns; direct involvement of the kidney occurs in the nephrotic syndrome, which may arise from several causes, such as diabetic nephropathy, cancer of the kidney, or various forms of glomerulonephritis of unknown etiology.

protein Z a major protein of barley endosperm albumin. It is structurally similar to a **serpin**, but its main role is as a storage protein, being especially rich in lysine.

proteoclastic *an obsolete term for* **proteolytic**.

proteoglycan a molecule consisting of one or more **glycosaminoglycan** chains attached to a core protein.

proteolipid *a term variously applied to describe* certain hydrophobic membrane proteins, or any other protein, that has a lipid moiety covalently bound to one or more of its constituent amino acids. Many such proteins are soluble in chloroform–methanol, a property that was significant in their first identification.

proteoliposome a **liposome** into which a specific protein, or group of proteins, has been incorporated.

proteolysis degradation of a protein, usually by hydrolysis at one or more of its peptide bonds. —**proteolytic** *adj.*

proteolytic enzyme *see* **peptidase**.

proteome *see* **'ome**.

proteomics *see* **'omics**.

proteosome *a variant spelling of* **proteasome**.

prothrombin *an alternative name for* factor II; *see* **blood coagulation**.

prothymosin *see* **thymosin**.

protide 1 *symbol*: ${}^{1}\mathrm{H}^{-}$; a **hydride** (def. 1) ion derived from an atom of **protium**. **2** any **hydride** (def. 2) formed from protium. **3** *or* **protid** *a generic name embracing* protein, peptide, or amino acid, suggested by analogy with glucide and lipid(e). Its use in English is largely restricted to translations or abstracts from French. —**protidic** *adj.*

protio+ *comb. form* indicating that one or more atoms of hydrogen in a hydrogen-containing chemical compound consists exclusively of **protium**.

Protista a taxonomic grouping of eukaryotic organisms that are unicellular, coenocytic, or multicellular but that are not classified as fungi, animals, or embryophytes.

protium *symbol*: ${}^{1}\mathrm{H}$; hydrogen-1, the nuclide of hydrogen, ${}^{1}_{1}\mathrm{H}$, of relative atomic mass 1.008. It is a stable isotope, having a relative abundance in natural hydrogen of 99.98 atom percent. The name is used especially when distinction from **deuterium** or **tritium** is required.

protoalkaloid an alkaloid that does not contain a heterocyclic ring, e.g. **damascenine** in *Nigella* spp.

protobiont one of the postulated first precursors of cells, supposed to have arisen when a boundary or membrane formed around one or more macromolecules possessing catalytic properties. *Compare* **coacervate droplet**.

protochlorophyllide Mg^{2+}-vinylpheoporphyrin A_5 methyl ether; an intermediate in the synthesis of chlorophyll, it is formed from Mg^{2+}-protoprophyrin, and converted to **chlorophyllide** by NADPH:protochlorophyllide oxidoreductase (EC 1.3.1.33). Protochlorophyllides may be suffixed with the letter of the related chlorophyll, e.g. protochlorophyllide *a*.



protochlorophyllide holochrome a pigment protein complex that carries out a light-catalysed reduction of **protochlorophyllide** to **chlorophyllide** with an external hydrogen donor, which is probably strongly bound NADPH. The enzyme involved in regenerating NADPH is **NADPH-photochlorophyllide oxidoreductase**; it is a single polypeptide, M_r 36000, and is only one component of the complex protein entity of the holochrome.

protocol a set of rules governing the way data are exchanged between computers. Computers with very different hardware and operating systems can communicate provided the same protocol is implemented on each. Whereas **APIs** ensure portability, protocols ensure interoperability.

protocollagen **collagen** chains in which proline and lysine residues have not been hydroxylated. Protocollagens may be produced by experimental inhibition of the relevant hydroxylases, either by use of a chelating agent or by imposed anaerobiosis. *Compare* **procollagen**.

protoheme *or (esp. Brit.)* **protohaem** the iron–porphyrin prosthetic group of the **cytochromes *b***.

protohemin *see* **hemin**.

protokaryon *an obsolete term for* **prokaryon**.

protokaryote *an obsolete term for* **prokaryote**.

protolysosome *see* **primary lysosome**.

protomer any of the subunits of an oligomeric protein that are identical. *See also* **monomer**, **oligomer**. —**protomeric** *adj.*

proton 1 *symbol*: ${}^{1}\mathrm{H}^{+}$; the cation derived from an atom of **protium**; a hydrogen ion of nucleon number unity; used in this sense especially when distinction between ${}^{1}\mathrm{H}^{+}$, ${}^{2}\mathrm{H}^{+}$ (i.e. deuteron), and ${}^{3}\mathrm{H}^{+}$ (i.e. triton) is needed; any solvated species is included. **2** *symbol*: H^{+}; *commonly used term for* the cation derived from any atom of natural **hydrogen** (of which a small proportion is **deuterium**) by loss of its orbital electron; any solvated species is included. *See also* **hydrogen ion**, **hydron**. **3** *symbol*: p; a nuclear particle of nucleon number unity, having a charge equal and opposite to that of an **electron** and having a mass of 1.007 276 470 (12) Da. —**protonic** *adj.*

proton magnetic resonance *abbr.*: PMR *or* pmr; *see* **nuclear magnetic resonance spectroscopy**.

proton magnetogyric ratio *symbol*: γ_p; a fundamental physical constant, of value 2.675 221 28(81) × 10^8 s^{-1} T^{-1}. *See also* **gyromagnetic ratio**.

protonmotive indicating, or related to an ability to transport protons (i.e. hydrons).

protonmotive force the driving force that leads to a gradient of protons (hydrons) across a membrane, for example of the mitochondrial inner membrane or the chloroplast thylakoid membrane. The protonmotive force was named by P.D. Mitchell, by analogy with electromotive force, and is conventionally given the symbol, $\Delta m_{\mathrm{H}}+$ and expressed in volts. It comprises two components, the electrostatic potential $\Delta\psi$ and the pH gradient, ΔpH. It may be produced by coupling to electron transfer reactions, or to the hydrolysis of ATP.

protonmotive Q cycle a hypothetical mechanism put forward to explain the **protonmotive** and **redox** properties of certain components of the **respiratory chain** in the **coupling membrane** of bacteria, mitochondria, and chloroplasts. The **Q cycle** applies to the part of the respiratory chain involving passage of electrons through cytochrome *b*. Essentially, the cycle accepts two hydride ions from a reduced flavoprotein (e.g. of complex I or complex II of the respiratory chain; *see* **complex I**, **II**, **III**, **IV**) passes electrons singly to cytochrome c_1 and releases the two hydrons to the intermembrane space. **Ubiquinone** is the molecule that accepts the hydride ions, and releases the electrons and hydrons. Cytochromes b_{566} and b_{562} are involved in shuttling electrons between different oxidation states of ubiquinone during the cycle. The property of ubiquinone that it can exist as a **semiquinone** is important in the switch from two-electron to one-electron transfer.

proton number *or* **atomic number** *symbol*: *Z*; a dimensionless physical quantity, with a unique integral value for each chemical element, that is equal to the number of protons contained in the nucleus of each atom of the element irrespective of the mass of any particular atom. It also is equal to the number of unit positive charges on the nucleus of each atom of a given chemical element, to the number of orbital electrons surrounding the nucleus of an unionized atom of that element, and, for a specific nuclide of that element, to the arithmetical difference between the nuclide's **nucleon number**, *A*, and its **neutron number**, *N*; i.e. $Z = N - A$. The proton number of an element determines the position of the element in the periodic table. It may be attached to the symbol for the element as a left subscript, e.g. ${}_6C$.

proton pump *another term (esp. in pharmacology) for* **hydrogen-ion pump**.

proton relaxation enhancement *abbr.*: PRE; a technique that yields information concerning (macro)molecular motion. It depends on the enhancement of the solvent water-proton relaxation rates on addition of a macromolecule.

protooncogene a normal gene, usually concerned with the regulation of cell proliferation, that can be converted into a cancer-promoting **oncogene** by mutation. For example, in the case of the Rous sarcoma virus the viral oncogene is v-*src* (*see* ***src***). This is closely related to a normal gene, c-*src*. The appearance of v-*src* is believed to have followed the acquisition of a copy of c-*src* by an ancestor of the Rous sarcoma virus. Through many generations this ancestral gene was mutated and became dominant. Protooncogenes encode proteins involved in all aspects of controlling cell proliferation, including growth factors, growth-factor receptors, nuclear factors regulating gene expression proteins that generate second messengers, and protein kinases.

protoplasm the living contents of a cell; i.e. the matter contained within (and including) the plasma membrane, usually taken to exclude large vacuoles and masses of secretory or ingested material. In eukaryotes it includes the **nucleus** and **cytoplasm**.

protoplast a spherical, osmotically sensitive plant cell without its cell wall but retaining an intact cell membrane. The cell wall is degraded by digestion with different hydrolytic enzymes, as a mixture or sequentially, e.g. cellulase, hemicellulase. Protoplasts are used to create hybrid cells via protoplast fusion. In some cases they are totipotent, and are thus capable of yielding plants. Such protoplasts can be used in plant transformation.

protoporphyrin IX the specific substrate for the enzyme **ferrochelatase**, which catalyses the insertion of iron to form **protoheme**. It is also probably the substrate for the insertion of magnesium in the formation of chlorophylls in plants.

prototroph any strain of a microorganism (alga, bacterium, or fungus) that does not require any substances in its nutrition additional to those required by the wild type. *Compare* **auxotroph**. —**prototrophic** *adj.*

Protozoa a phylum or subkingdom comprising single-celled eukaryotic microscopic organisms, usually classified as animals. *Compare* **Metazoa**, **Parazoa**.

provirus a virus, e.g. a **retrovirus**, that is integrated into the chromosome of its host cell and can be transmitted through the generations without causing lysis of the host cell.

provitamin a compound which is converted to an active vitamin in the body. In practice the term is only applied to **carotenes**.

Pro-X dipeptidase EC 3.4.13.8; *recommended name*: prolinase; *other names*: prolyl dipeptidase; iminodipeptidase; prolinase; L-prolylglycine dipeptidase; an enzyme that catalyses the hydrolysis of Pro-|-Xaa dipeptides. It also acts on hydroxyprolyl analogues.

proximal protein any protein that binds early in the assembly of complex structures, such as ribosomes. Their presence in the partially assembled structure is required for the binding of **distal proteins**.

proximate carcinogen *or* **proximate carcinogenic metabolite** any metabolite of a **chemical carcinogen** that is itself carcinogenic; the term may embrace **ultimate carcinogen**.

Prozac *see* **fluoxetine**.

PrP *abbr. for* prion protein.

PRP protein *abbr. for* **pre-mRNA processing protein**.

PRPP *abbr. (not recommended) for* phosphoribosyl pyrophosphate (*see* **(5-)phospho(-α-D-)ribosyl diphosphate**).

PRPP synthetase *another name for* **ribose-phosphate pyrophosphokinase**.

PR protein *abbr. for* pathogenesis-related protein.

pRSETA one of a family of phagemid vectors designed for high levels of expression of proteins in *E. coli*. The gene of interest is cloned downstream from the promoter for T7 RNA polymerase. When propagated in BL21 (DE3) cells the expression of T7 RNA polymerase can be induced with isopropyl *β*-thiogalactoside (IPTG), which then transcribes the cloned gene.

prunasin (–)-(*R*)-mandelonitrile *β*-D-glucoside; a **cyanogenic** glycoside.



ps *symbol for* picosecond.

P-selectin *see* **selectin**.

pseudoachondroplasia *see* **achondroplasia**.

pseudoalkaloid any **alkaloid** in which the skeleton is partly derived from a terpene.

pseudoallele any of two (or more) mutations that are allelic functionally but not structurally. *See* **allele**.

pseudoaxial *(in chemistry) abbr.*: a′; *see* **conformation**.

pseudocholinesterase EC 3.1.1.8; *recommended name*: cholinesterase; *other name*: choline esterase II. An enzyme, found in blood and other tissues, that catalyses the hydrolysis of a variety of choline esters and a few other compounds. *Compare* **acetylcholinesterase**.

pseudoequatorial *(in chemistry) abbr.*: e′; *see* **conformation**.

pseudoexon a portion of an **exon** that is duplicated in an adjacent **intron**.

pseudogene *symbol*: ψ; a sequence in DNA that is related to a functional gene but cannot be transcribed. This may be due to mutational changes that preclude it from being expressed in the form of functional products or the lack of some flanking control region in the promoter. Pseudogenes may or may not contain the introns of the functional gene. Examples include pseudogenes for α, β, and ζ globulins in several species, V_κ chains of immunoglobulins, actin, and tubulin. **Processed pseudogenes**, or LINES (*see* **LINE**), occur in a genome somewhere other than the normal position of the corresponding functional gene and so cannot be expressed because of alterations in regulatory DNA sequences, or coding sequences, or both.

pseudoglobulin a globulin that is soluble in solutions of low ionic strength, or in pure water. *Compare* **euglobulin**.

pseudohypoaldosteronism type II *see* **WNK**.

pseudointron an **intron** that contains 5′ and 3′ splice sites that are appropriate but not utilized in the excision of the intron.

pseudoisoenzyme any one of the epigenetically derived multiple forms of an enzyme.

pseudo-operator a functional **operator** element within a structural protein-coding region of DNA.

pseudopepsin *see* **pepsinogen**.

pseudoplasmodium *see* ***Dictyostelium discoideum***.

pseudopodium (*pl.* **pseudopodia**) a temporary protrusion or retractile process of a cell, associated with flowing movements of the protoplasm and serving for locomotion and feeding. —**pseudopodial** *adj.*

pseudouridine *symbol*: Ψ; 5-*β*-D-ribofuranosyluracil; a component of **transfer RNA** (tRNA) containing a C–C bond between the ribose (C-1) and uracil (C-5). Typical of the **minor nucleosides** present in tRNA, it is formed by modification of uridine in the original transcript; the chemistry of this process is unclear. When pseudouridine occurs in the anticodon of transfer RNA it base pairs with adenine. Mutation in the gene for dyskerin, a putative pseudouridine synthase, results in dyskeratosis congenita. *Compare* **uridine**.



pseudouridine synthase E.C.4.2.1.70; *other name*: pseudouridylate synthase; any of the enzymes (e.g. ψS1, PUS1) that catalyse the conversion of uridine residues in RNA to pseudouridine. They include the dyskeratosis congenita gene product, **dyskerin**. Members of the family differ in their specificity for RNA substrates.

pseudoxanthoma elasticum a hereditary disorder of connective tissue that affects skin, retina, and blood vessels. There is accumulation of calcium in these and in other tissues, with the formation of yellowish lumps in the skin. Several mutations in an ABC transporter (ABCC6) cause the disorder.

***Psh*AI** a type 2 **restriction endonuclease**; recognition sequence: GACNN↑NNGTC.

***Psh*BI** a type 2 **restriction endonuclease**; recognition sequence: AT↑TAAT. *Vsp*I is an **isoschizomer**.

psi 1 *symbol*: ψ (lower case) *or* Ψ (upper case); the twenty-third letter of the Greek alphabet. For uses *see* **Appendix A**. **2** *or* **p.s.i.** *abbr. for* pounds per square inch (a unit of pressure in the Imperial and US systems of units).

PSI *abbr. for* photosystem I (*see* **photosystem**).

PSI-BLAST *abbr. for* position-specific iterated-BLAST; *see* **database-search program**.

psicofuranine 6-amino-9-D-psicofuranosylpurine; an antibiotic produced by *Streptomyces hygroscopicus*, found to have antitumour activity. *See also* **D-psicose**.

D-psicose *a nonsystematic name for* the keto-hexose D-*ribo*-2-hexulose. The hydroxyl at C-3 has the opposite configuration to that of D-fructose. It is a component of **psicofuranine**.



α-D-pyranose form

PSII *abbr. for* photosystem II (*see* **photosystem**).

psilocin 3-[2-(dimethylamino)ethyl]-1*H*-indol-4-ol; a hallucinogenic alkaloid extracted from the mushroom *Psilocybe mexicana*.



P-site *abbr. for* a peptidyl-tRNA binding site of **ribosome**; in bacteria this involves the **ribosomal proteins** L2, L14, L18, L24, L27, and L33, and a region close to the 3′ end of 16S rRNA.

psoralen 6-hydroxy-5-benzofuranacrylic acid *δ*-lactone; a furocoumarin present as a **phytoalexin** in many plants. It has photosensitizing and phototoxic effects in humans and animals, and is used in photochemistry, intercalating into DNA and forming cross-links on irradiation. *See also* **methoxypsoralen**.



PSP *abbr. for* pancreatic stone protein (*see* **pancreatic thread protein**).

***Psp*1406I** a type 2 **restriction endonuclease**; recognition sequence: AA↑CGTT. *Acl*I is an **isoschizomer**.

pSPORT 1 one of a proprietary series of vectors for cloning cDNA in *E. coli*.

PSSM *(usually pronounced 'possum') abbr. for* position-specific scoring matrix.

***Pst*I** a type 2 **restriction endonuclease**; recognition sequence: CTGCA↑G.

pSV vector a plasmid vector designed for the expression of cloned sequences in mammalian cells driven by the SV40 early promoter and enchancer.

psychosine 1-*O*-*β*-D-galactosylsphingosine; it is formed from UDP-galactose and sphingosine by sphingosine *β*-galactosyltransferase, EC 2.4.1.23. It is acylated to a cerebroside by reaction with a long-chain acyl-CoA.

psychrometer *or* **wet-and-dry bulb hygrometer** a type of hygrometer consisting of two thermometers, one with a wet bulb and one with a dry bulb. The cooling effect of evaporation from the wet bulb creates a temperature difference between the two thermometers, from which the relative humidity can be calculated.

psychrophile an organism that grows best at low temperatures (below about 20 °C). —**psychrophilic** *adj.*

P system a system of blood groups in which the antigenic determinants are oligosaccharides. The antigens are detected on erythrocytes, erythroblasts, platelets, megakaryocytes, fibroblasts, and endothelial cells; they are designated P^k, P, and P$_1$. The common phenotypes are P$_1$ (antigens P$_1$ and P positive) and P$_2$ (P antigen positive); P^k phenotypes are rare. Individuals with the p phenotype lack all of the above determinants, having only the core structure lactosylceramide, and have anti-P and anti-P^k antibodies. The determinants are:

Pk (Gb$_3$Cer): Gal(*α*1-4)Gal(*β*1-4)GlcCer
Pk (Gb$_4$Cer): GalNAc(*β*1-3)Gal(*α*1-4)Gal(*β*1-4)GlcCer
P1 : Gal(*α*1-4)Gal(*β*1-4)GlcNAc(*β*1-3) Gal(*β*1-4)GlcCer.

Pt *symbol for* platinum.

PTA *abbr. for* plasma thromboplastin antecedent (i.e. factor XI); *see* **blood coagulation**.

PTB domain *abbr. for* phosphotyrosine-binding domain. *See* **SH2 domain**.

PTC *abbr. for* **1** plasma thromboplastin component (i.e. factor IX); *see* **blood coagulation**. **2** phenylthiocarbamoyl.

Ptd *symbol for* the phosphatidyl group.

PtdIns *symbol for* phosphatidylinositol.

PtdIns4*P* *or* **PtdIns-4-*P*** *symbol for* phosphatidylinositol 4-phosphate.

PtdIns(4,5)P_2 *or* **PtdIns-4,5-P_2** *symbol for* phosphatidylinositol 4,5-bisphosphate.

pteridine pyrazino[2,3-*d*]pyrimidine; the parent structure of pterins and the **pteroyl** group. *See also* **xanthopterin**.



pterin-4*α*-carbinolamine dehydratase *abbr.*: PCD. EC 4.2.1.96; an enzyme activity of liver and other tissues that is part of a bifunctional protein (*abbr.*: PCD/DCoH; 103 amino acids) that also acts as the dimerization cofactor for hepatocyte nuclear factor 1α (*abbr.*: DCoH). The enzyme converts 4*α*-carbinolamine tetrahydrobiopterin (formed during the conversion of phenylalanine to tyrosine) to quinonoid dihydrobiopterin by elimination of water. It also prevents nonenzymatic conversion of tetrahydrobiopterin to **primapterin**. Several mutations in the protein lead to deficiency of PCD activity, with consequent hyperphenylalaninemia and primapterinuria. *See* **biopterin**.

pteroyl 4-[[(2-amino-1,4-dihydro-4-oxo-6-pteridinyl)methyl]amino]-benzoyl; the acyl group of pteroic acid, and the structural basis of **folate** and its derivatives.



PTFE *abbr. for* polytetrafluoroethylene.

PTG *abbr. for* protein targeting to glycogen; a protein (294 amino acids), expressed predominantly in insulin-sensitive tissues, that binds to the catalytic subunit of **protein phosphatase** 1 and localizes it to glycogen. It also forms complexes with phosphorylase kinase, phosphorylase *a* (*see* **phosphorylase**), and **glycogen synthase**.

PTGS *abbr. for* post-transcriptional gene silencing. *See* **RNA silencing**.

PTH *abbr. for* **1** parathyroid hormone (i.e. **parathyrin**). **2** phenylthiohydantoin; as in PTH-amino acid (i.e. the phenylhydantoin derivative of an amino acid).

PTI *abbr. for* pancreatic trypsin inhibitor.

PTM *abbr. for* post-translational modification.

PTNP11 *abbr. for* protein tyrosine phosphatase noinreceptor type 11. *See* **Noonan syndrome.** .

Ptprz *abbr. for* protein tyrosine phosphatase receptor z. *See* ***Helicobacter pylori***.

pTriEX a proprietary plasmid vector that enables the expression of genes in bacterial, insect, and mammalian cells from a single plasmid.

PTS *abbr. for* **1** phospho*enol*pyruvate-dependent sugar phosphotransferase system. **2** peroxisome targeting sequence.

PTS receptor either of two proteins that recognize a **peroxisome targeting sequence** (PTS) in targeting proteins to the peroxisomal matrix. Both are PEX proteins (*see* **peroxin**); PEX5 binds PTS1, while PEX7 binds PTS2.

PTT *abbr. for* protein truncation test.

ptyalin a substance in saliva, identified as ***α*-amylase**.

P-type transporter a member of a family of membrane transport proteins, found in bacteria, archaea and eukaryotes, that catalyse cation uptake and/or efflux driven by ATP hydrolysis. Most are multisubunit complexes with a large subunit serving the primary ATPase and ion translocation functions. Distinct bacterial enzymes specific for K$^+$ or Mg^{2+} (uptake), Ca^{2+}, Ag$^+$, Zn^{2+}, Co^{2+}, Pb^{2+}, Ni^{2+}, and/or Cd^{2+} (efflux) and Cu^{2+} or Cu$^+$ (uptake or efflux, depending on the system) have been characterized.

Pu *symbol for* plutonium.

PubMed *see* **information retrieval software**.

pUC vector any of a series of plasmid cloning vectors having an ampicillin resistance gene and part of the *lacZ* gene encoding the **α-peptide** containing a multiple cloning site (MCS). Different members of the series (e.g. pUC18, pUC19) differ in the orientation of the MCS. They are high copy number plasmids and so can be purified by rapid, small-scale methods of isolation. A related series of bacteriophage M13 vectors, the M13mp vectors, contain the same MCS and are useful for DNA sequencing. *See also* **Messing vector**.

PUFA *abbr. for* polyunsaturated fatty acid.

puff any discrete, localized expansion occurring at specific sites in polytene chromosomes, e.g. the giant salivary gland chromosomes in Diptera. Typically a few micrometres long, they are believed to be a gene or group of genes that are actively synthesizing RNA, which accounts for a considerable part of the mass of the puff. *See also* **Balbiani ring**.

puffer fish *see* **Fugu**.

pulldown technique a method for investigating protein–protein interactions in which a protein of interest is expressed as a fusion protein with glutathione-*S*-transferase (GST) or an epitope tag such as 6 × His or c-Myc. This is used to explore previously unknown interactions with other proteins in a mixture such as a cell extract. Protein complexes formed with the fusion protein are precipitated either with specific antibodies or with a suitable affinity adsorbent, and the nature of the bound proteins is identified by gel electrophoresis and mass spectrometry.

'pull' model *a nickname for* the **Monod–Wyman–Changeux model** (for ligand-induced changes in protein conformation) because, in this model, ligands influence the equilibrium between enzyme states by sequestering the enzyme in ligand-bound forms. *Compare* **'push' model**.

pullulan an extracellular **glucan** elaborated by *Aureobasidium pullulans* (yeast form) and formed by other fungi. It is a linear structure with both (1→4)-*α*-D- and (1→6)-*α*-D-linkages. Pullulan is used as a non-caloric material, a water-retention agent, and as a film and fibre former.

pullulanase **1** **isopullulanase** EC 3.2.1.57; an enzyme that catalyses the hydrolysis of **pullulan** to isopanose (i.e. 6-*α*-maltosylglucose). **2** **neopullulanase** EC 3.2.1.135; an enzyme that catalyses the hydrolysis of pullulan to panose (i.e. 6-*α*-D-glucosylmaltose). **3** *see* ***α*-dextrin endo-1,6-α-glucosidase**.

pulmonary surfactant a secretion, produced by type II cells of alveoli and bronchial mucosa, that forms a monolayer at the alveolar air–water interface to lower the surface tension. It consists primarily of dipalmitoyllecithin, unsaturated lecithin and phosphatidylglycerol, and surfactant proteins B and C. The surfactant's components are essential at birth to convert a fluid-filled lung to one filled with air. They are cleared by the type II cells and macrophages for recycling or degradation. Secretion and clearance are increased by exercise.

pulse-chase experiment a technique whereby cells growing in culture are exposed for a short period (pulse) to a radiolabelled molecule such as an amino acid and then transferred to a medium containing an excess of the nonlabelled substance for a longer period (chase). By removing samples at intervals the fate of intracellular components labelled during the pulse can be ascertained.

pulsed field gel electrophoresis *abbr.*: PFGE; a type of **gel electrophoresis** in which fragments of DNA in the megabase size range can be separated by continuously altering the angle at which the electric current is applied.

pulse radiolysis a technique whereby reactive chemical species are generated by pulses of high-energy radiation and the subsequent reactions of these species are followed spectrophotometrically as a function of time.

Pumilio a protein of *Drosophila* that binds the Nanos response elements in the 3′ untranslated region of the *hunchback* mRNA and recruits the proteins Nanos and Brain tumor to suppress its translation. It contains eight repeats of a ≈36 residue trihelical sequence that assemble into an arched structure. Through its concave surface this arch binds the RNA motifs, which have a core UGU trinucleotide sequence; while through the outer surface of repeats 7 and 8 it binds with Nanos and Brain tumor, respectively. A homologue in *Xenopus*, called XPum, is present throughout oogenesis. There is also a human homologue.

pump *(in cell biology)* any transmembrane protein that drives the active transport of ions and small molecules across the lipid bilayer. *See also* **hydrogen-ion pump**, **sodium pump**.

PUMP-1 *see* **matrilysin**.

pump-1 protease *see* **matrilysin**.

Punnett square a matrix showing all possible combinations of alleles in a genetic cross. [After Reginald Punnett (1875–1967), British geneticist.]

purine 1 1*H*-purine; 7*H*-imidazo[4,5-*d*]pyrimidine; an organic nitrogenous base, sparingly soluble in water. **2** any of a class of derivatives of 1*H*-purine; these form one of the two classes of nitrogen-containing ring compounds found in DNA and RNA, which include **adenine** and **guanine**. *See also* **purine biosynthesis**.



purine biosynthesis the biosynthesis of purine ribonucleotides. The pathway begins with the formation of 5-phospho-α-D-ribosyl diphosphate (5-phosphoribosyl-α-D-pyrophosphate, *common abbr.*: PRPP) by ribose-phosphate pyrophosphokinase, EC 2.7.6.1. This is converted to β-5-phosphoribosylamine (i) by reaction with glutamine, catalysed by amidophosphoribosyltransferase, EC 2.4.2.14; reaction of I with glycine, with hydrolysis of ATP to ADP and P$_i$, catalysed by **phosphoribosylamine–glycine ligase**, EC 6.3.4.13 (glycinamide ribonucleotide synthetase, *common abbr.*: GAR synthetase), brings about the formation of N^1-(5-phospho-D-ribosyl)glycinamide (II, glycinamide ribotide, *common abbr.*: GAR); II reacts with 10-formyltetrahydrofolate to form 5′-phosphoribosyl-*N*-formylglycinamide (III, *common abbr.*: FGAR), the enzyme being **phosphoribosylglycinamide formyltransferase**, EC 2.1.2.2 (GAR transformylase); III is converted to 5′-phosphoribosylformylglycinamidine (IV, formylglycinamidine ribotide, *common abbr.*: FGAM) by **phosphoribosylformylglycinamidine synthase**, EC 6.3.5.3 (*common abbr.*: FGAM synthetase) by reaction with glutamine with ATP hydrolysis to ADP and P$_i$. IV is converted to 1-(5-phosphoribosyl)-5-aminoimidazole (V, 5-aminoimidazole ribotide, *common abbr.*: AIR), with hydrolysis of ATP to ADP and P$_i$, by **phosphoribosylformylglycinamidine cyclo-ligase**, EC 6.3.3.1 (*common abbr.*: AIR synthetase); V is carboxylated to 1-(5-phosphoribosyl)-5-amino-4-imidazolecarboxylate (VI, carboxyaminoimidazole carboxamide, *common abbr.*: CAIR), by **phosphoribosylaminoimidazole carboxylase**, EC 4.1.1.21 (*common abbr.*: AIR carboxylase); VI reacts with L-aspartate, with hydrolysis of ATP to ADP and P$_i$, to form 1-(5-phosphoribosyl)-5-amino-4-(*N*-succinocarboxamide)-imidazole (VII, 4-(*N*-succinylocarboxamide)-aminoimidazole ribotide, *common abbr.*: SACAIR) catalysed by **phosphoribosylaminoimidazolesuccinocarboxamide synthase**, EC 6.3.2.6 (*common abbr.*: SACAIR synthetase); VII is converted, with loss of fumarate, to 1-(5-phosphoribosyl)-4-carboxamide-5-aminoimidazole (VIII, aminoimidazolecarboxamide ribotide, *common abbr.*: AICAR) by adenylosuccinate lyase, EC 4.3.2.2 (VII is an alternative substrate for this enzyme); VIII reacts with 10-formyltetrahydrofolate to form 5′-phosphoribosyl-5-formamido-4-imidazolecarboxamide (IX, formaminoimidazolecarboxamide ribotide, *common abbr.*: FAICAR), catalysed by **phosphoribosylaminoimidazolecarboxamide formyltransferase**, EC 2.1.2.3 (*common abbr.*: AICAR transformylase); IX undergoes ring closure catalysed by IMP cyclohydrolase, EC 3.5.4.10, to form inosine monophosphate (IMP), from which other purine nucleoside monophosphates are formed. Thus it is converted to AMP via adenylosuccinate, in steps catalysed by adenylosuccinate synthase, EC 6.3.4.4, and adenylosuccinate lyase, EC 4.3.2.2. It is converted to GMP via xanthosine monophosphate, in steps catalysed by **IMP dehydrogenase**, EC 1.1.1.205, and **GMP synthase**, EC 6.3.4.1. A **salvage pathway** converts purine bases released during nucleic-acid degradation to nucleoside monophosphates. The enzymes adenine phosphoribosyltransferase and hypoxanthine–guanine phosphoribosyltransferase are responsible for these reactions.

purine-nucleoside phosphorylase *abbr.*: PNP; EC 2.4.2.1; *systematic name*: purine-nucleoside:orthophosphate ribosyltransferase; *other name*: inosine phosphorylase. An enzyme that catalyses the phosphorolysis of a purine nucleoside to a purine and α-D-ribose 1-phosphate. It functions in the degradation of purines; decreased activity leads to accumulation of dGTP, which affects DNA replication. Enzyme deficiency is associated with moderate immunodeficiency.

purinergic describing a type of nerve in which synaptic transmission is brought about by purine-like transmitter substances. *See* **purinoceptor**. *Compare* **adrenergic**, **cholinergic**.

purine salvage pathway a pathway by which the purine bases arising from degradation of RNA are used for the biosynthesis of nucleotides. Two **phosphoribosyltransferases** are involved, one for adenine (adenine phosphoribosyltransferase, APRT) and one for guanine or hypoxanthine (hypoxanthine/guanine phosphoribosyltransferase, HGPRT). *See also* **hypoxanthine phosphoribosyltransferase**.

purinoceptor *or* **purinergic receptor** a family of receptors (P$_1$, P$_{2X}$, P$_{2Y}$, P$_{2Z}$, P$_{2T}$, and P$_{2U}$) classified according to the relative potency of purine nucleotides – ATP, ADP, AMP, and UTP – in stimulating them and by their response to either adenosine (P$_1$) or ATP (P$_2$). P$_{2Y}$ and P$_{2U}$ are G-protein-associated membrane receptors that regulate turnover of phosphoinositides. P$_{2X}$, P$_{2Z}$, and P$_{2T}$ modulate the opening of an intrinsic cation channel but P$_{2T}$ also stimulates release of intracellular Ca^{2+} and reduces synthesis of cyclic AMP.

puromycin a nucleoside antibiotic produced by the soil actinomycete *Streptomyces alboniger*. It interrupts protein synthesis by virtue of its structural similarity to the 3′ end of aminoacyl-tRNA: it enters the A-site (*see* **aminoacyl site**) on the ribosome, and is incorporated into the growing polypeptide chain, thereby causing premature release of the puromycinyl polypeptide from the ribosome.

purothionin any of a group of basic peptides, isolated from grain and of M_r ~5000, that contain a large number of cysteine residues, and are toxic to bacteria and fungi by inhibiting DNA transcription and RNA translation.

purple membrane part of the cell membrane of *Halobacterium halobium* containing **bacteriorhodopsin**.

'push' model *a nickname for* the **Koshland model** (for ligand-induced changes in protein conformation) because, in this model, binding of the ligands results in a conformational change, and does not simply select a pre-existing state. *Compare* **'pull model'**.

putidaredoxin a ferredoxin, isolated from *Pseudomonas putida*, that is an electron carrier in a hydroxylase system acting on camphor and closely related monoterpenes. *Compare* **adrenodoxin**.



puromycin

putrescine 1,4-diaminobutane; the polyamine formed by decarboxylation of **ornithine** and the metabolic precursor of **spermidine** and **spermine**.

PVA *abbr. for* **1** polyvinyl alcohol. **2** polyvinyl acetate.

p-value (*in sequence analysis*) a statistical measure of the significance of a match obtained by searching a database with a query sequence. The p-value denotes the probability of a match occurring with a score better than or equal to the score of the retrieved match, relative to the expected distribution of scores that result when random sequences of the same length and composition as the query are compared with the database. The closer the p-value to 0, the more significant the match.

PVC *abbr. for* polyvinyl chloride.

PVDF *abbr. for* polyvinylidine fluoride.

PVP *abbr. for* polyvinyl pyrrolidone.

***Pvu*I** a type 2 **restriction endonuclease**; recognition sequence: CGAT↑CG.

***Pvu*II** a type 2 **restriction endonuclease**; recognition sequence: CAG↑CTG.

PWM *abbr. for* pokeweed mitogen.

pYAC4 a yeast artificial chromosome vector for cloning *Eco*RI fragments of 50–100 kb.

pycnodysostosis a disorder of bone matrix remodelling caused by **cathepsin K** deficiency in osteoclast lysosomes, which accumulate partially degraded collagen type I fibrils. The syndrome is characterized by short stature, dysmorphism, osteosclerosis of long and of flat bones, hypoplasia of craniofacial bones and phalanges, pathological fractures, and dental abnormalities. Several point mutations in the cathepsin K gene are responsible.

pycnometer an apparatus for measuring the density of liquids, and also sometimes of solids. It consists of a container whose volume can be accurately measured, and that can be filled with great precision, so that when filled with the liquid in question it can be weighed to determine the density. —**pycnometric** *adj.*

pYD1 a proprietary yeast vector designed to target and display recombinant proteins at the surface of *Saccharomyces cerevisiae* as a fusion protein with the α-agglutinin subunit AGA2.

Pyd *symbol for* a residue of an unspecified pyrimidine nucleoside (alternative to Y).

pyr-1 the symbol for the pyrimidine 1 gene, which encodes **CAD protein** in several eukaryotes.

pyran *the trivial name for* either of the hypothetical isomers α-pyran, 2*H*-pyran, oxacyclohexa-3,5-diene, or γ-pyran, 4*H*-pyran, oxacyclohexa-2,5-diene, c_5H_6o. These pyrans are not known as such, but are the parent structures of various known pyranoid compounds such as dihydropyran, α- and γ-pyrones, and pyranoses.

pyranoid pyran-like, i.e. describing a molecular structure that consists of or contains a ring of five carbon atoms and one oxygen atom (as in **pyran**).

pyranopterin *preferred name for* the pterin component of the molybdenum and tungsten cofactors.



pyranose *symbol*: *p*; any monosaccharide or monosaccharide derivative whose molecule contains a **pyranoid** ring. *Compare* **furanose**, **septanose**.

pyridine-nucleotide coenzyme any coenzyme containing a nicotinamide nucleotide residue, e.g. nicotinamide-adenine dinucleotide (NAD$^+$); now known as **nicotinamide-nucleotide coenzymes**.

pyridoxal *abbr.*: PL; 3-hydroxy-5-(hydroxymethyl)-2-methyl-4-pyridine carboxaldehyde; a compound with **vitamin B$_6$** activity.



pyridoxal kinase EC 2.7.1.35; an enzyme that catalyses the formation of pyridoxal 5′-phosphate from ATP and pyridoxal with release of ADP.

pyrimidine **1** 1,3-diazine; an organic nitrogenous base, sparingly soluble in water. **2** any of a class of derivatives of pyrimidine (def. 1); these form oPZP ne of the two categories of nitrogen-containing ring compounds found in DNA and RNA, which include **cytosine**, **thymine**, and **uracil**. *See also* **pyrimidine biosynthesis**.



pyrimidine biosynthesis *or* **pyrimidine ribonucleotide biosynthesis** pyrimidines are formed from carbamoyl phosphate (*see* **carbamoyl-phosphate synthase**) after conversion to carbamoyl aspartate in a reaction with L-aspartate catalysed by **aspartate transcarbamylase**, EC 2.1.3.2. Carbamoyl aspartate is converted to orotate via dihydroorotate, in steps catalysed by **dihydroorotase**, EC 3.5.2.3, and dihydroorotate dehydrogenase, EC 1.3.99.11. Orotate is phosphorylated to orotidine monophosphate (OMP) in a reaction with 5-phospho-α-D-ribosyl diphosphate catalysed by **orotate phosphoribosyltransferase**, EC 2.4.2.10. OMP is converted to uridine monophosphate by **orotidine 5′-phosphate decarboxylase**, EC 4.1.1.23.

pyrimidine dimer any structure formed within a strand of DNA from two neighbouring pyrimidine residues through covalent cross-linking induced by ultraviolet irradiation. Two types are known. (1) Addition of one pyrimidine ring to the other at each end of their respective 5,6-double bonds generates a **cyclobutadipyrimidine**, a fully substituted cyclobutane. Such a dimer is formed most readily from two thymine residues (*see* **thymine dimer**), but may be formed also from two cytosine residues, or from one cytosine and one thymine residue. For each of these varieties there are four possible configurational isomers: if the pyrimidine rings have become linked in a parallel manner, i.e. by 5–5′ and 6–6′ bonds, the configuration is designated by the prefix *syn*-, but if they are linked in an antiparallel manner, i.e. by 5–6′ and 6–5′ bonds, it is designated by *anti*-; further, if the pyrimidine rings are both on the same side of the plane of the cyclobutane ring, the dimer is described as being in the '**doghouse configuration**', designated by the prefix *cis*-, but if the rings are on opposite sides of the cyclobutane plane, the dimer is said to be in the '**chair configuration**', designated by *trans*-. The presence of a cyclobutadipyrimidine in a DNA strand causes a local distortion of the DNA duplex and blocks the action of DNA polymerase, thus preventing replication; cell death may ensue unless repair is effected by **photoreactivation**. (2) Alternatively, addition may take place between position 6 of one pyrimidine residue and position 4 of an adjacent one, with creation of a single covalent link and generation of a **(6–4)photoproduct**. Such a dimer is usually formed between position 6 of a cytosine or thymine residue on the 5′ side of a dinucleotide segment and position 4 of a cytosine residue on its 3′ side. The (6–4)photoproduct is thought to be the main type of lesion in DNA responsible for mutations; it is not susceptible to photoreactivation, but can be eliminated by other DNA-repair mechanisms, e.g. **excision repair**.

pyrimidine-nucleoside phosphorylase 1 **uridine phosphorylase** EC 2.4.2.3; an enzyme that catalyses the phosphorolysis of uridine to uracil and α-D-ribose 1-phosphate. 2 **thymidine phosphorylase** EC 2.4.2.4; an enzyme that catalyses the phosphorolysis of thymidine to thymine and 2-deoxy-D-ribose 1-phosphate.

pyrin *see* **familial Mediterranean fever**.

pyro+ *or (before a vowel)* **pyr+** *comb. form* **1** of, relating to, caused, or produced by fire. **2** *(in chemistry)* indicating material derived by the action of heat; it often indicates an acid formed by loss of a molecule of water in a heating process, and hence also some anhydrides, e.g. pyrophosphate.

pyrocatechol *or* **pyrocatechin** *or (formerly)* **catechol** 1,2-benzenediol; *o*-dihydroxybenzene. *Compare* **catecholamine**, ***o*-benzoquinone**, **hydroquinone**.

pyrolysis the decomposition or dissociation of a chemical compound by the application of heat. *See also* **thermolysis**. **—pyrolytic** *adj.*; **pyrolyse** *or (sometimes, US)* **pyrolyze** *vb.*

pyrophosphatase **1** *an imprecise name for* **inorganic pyrophosphatase**. **2** *the generic name for* any enzyme within sub-subclass EC 3.6.1 (enzymes acting on diphosphate bonds); e.g. ATP pyrophosphatase (EC 3.6.1.8).

pyrophosphate *an older name for* **diphosphate** (def. 1–5) (use no longer recommended although it is still used as an alternative in such terms as inorganic pyrophosphate, pyrophosphatase, etc.). *See also* **inorganic diphosphate**.

pyrophosphokinase *the general name for* any enzyme belonging to the sub-subclass EC 2.7.6, diphosphotransferases, which transfer a diphosphate group from ATP to a named substrate; e.g. GTP pyrophosphokinase (EC 2.7.6.5), which converts guanosine 5′-triphosphate, GTP to guanosine 3′-phosphate 5′-triphosphate, pppGpp.

pyrrolidonecarboxylic acid *symbol*: <Glp; pyroglutamic acid; 5-oxoproline; pyrrolid-2-one-5-carboxylic acid. *See* **thyrotropin-releasing hormone**.



L-form

1-pyrroline-5-carboxylate dehydrogenase EC 1.5.1.12; an enzyme that catalyses a reaction between 1-pyrroline-5-carboxylate (*abbr.*: P5C), NAD$^+$, and H_2O to form L-glutamate and NADH. P5C is an intermediate in the conversion of glutamate, proline, and ornithine. In *Escherichia coli* the protein also has **proline dehydrogenase** activity.

pyrroloquinoline–quinone *abbr.*: PQQ; *an alternative name for* **methoxatin**.

pyruvate *trivial name for* 2-oxopropanoate, CH_3COCOO^-; it is found in virtually every type of cell and species, being an important intermediate in many pathways including the catabolism of glucose, and the biosynthesis of amino acids and carbohydrates.

pyruvate carboxylase *abbr.*: PCB; EC 6.4.1.1; *systematic name*: pyruvate:carbon dioxide ligase (ADP-forming); *other name*: pyruvic carboxylase; an enzyme of mitochondrial matrix that catalyses a reaction between ATP, pyruvate, and HCO_3^- to form oxaloacetate, ADP, and orthophosphate; biotin and manganese or zinc are cofactors. It requires acetyl-CoA as an allosteric activator. Enzyme deficiency results in lactic acidosis, which may be severe and lethal in infancy, or less severe and lead to delayed development.

pyruvate decarboxylase EC 4.1.1.1; *systematic name*: 2-oxo-acid carboxy-lyase; *other names*: α-carboxylase, pyruvic decaboxylase; α-ketoacid carboxylase. An enzyme that catalyses the decarboxylation of a 2-oxo acid to an aldehyde and $CO_{2;}$ thiamine diphosphate is a coenzyme.

pyruvate decarboxylase kinase *or* **pyruvate dehydrogenase kinase** a subunit of the mammalian **pyruvate dehydrogenase complex**. It phosphorylates three serine residues on pyruvate dehydrogenase (lipoamide) resulting in loss of activity, and is stimulated by elevated levels of acetyl-CoA and NADH.

pyruvate dehydrogenase complex an enzyme complex that catalyses the overall reaction between pyruvate, NAD$^+$, and coenzyme A to form acetyl-CoA, NADH, and CO_2. The complex consists of four activities: (1) **pyruvate dehydrogenase (lipoamide)**, designated E_1, catalysing a reaction between pyruvate and lipoamide to form *S*-acetyldihydrolipoamide and CO_2; (2) **dihydrolipoamide *S*-acetyltransferase**, designated E_2, catalysing a reaction between *S*-acetyldihydrolipoamide and coenzyme A to form acetyl-CoA and dihydrolipoamide; (3) **dihydrolipoamide dehydrogenase**, designated E_3, which oxidizes dihydrolipoamide to lipoamide; and (4) a lipoyl-containing catalytic **protein X**, which can also effect acyl transfer and which binds E_2 and E_3. The complex is regulated by the phosphorylation and dephosphorylation of the E_1 component, phosphorylation being catalysed by **pyruvate decarboxylase kinase** and dephosphorylation being catalysed by **[pyruvate dehydrogenase (lipoamide)] phosphatase** (or pyruvate decarboxylase phosphatase), EC 3.1.3.43. Elevated levels of NADH and acetyl-CoA inhibit the complex by stimulating the kinase. Defects in E_1, E_2, E_3, and protein X or the phosphatase result in lactic acidosis, which may be fatal early after birth, produce profound psychomotor retardation, or carbohydrate-induced episodic ataxia, depending on the locus of the defect.

pyruvate dehydrogenase (lipoamide) EC 1.2.4.1; *systematic name*: pyruvate:lipoamide 2-oxidoreductase (decarboxylating and acceptor-acetylating); *other names*: pyruvate decarboxylase; pyruvate dehydrogenase; pyruvic dehydrogenase. A component enzyme of the **pyruvate dehydrogenase complex**. It catalyses a reaction between pyruvate and lipoamide to form *S*-acetyldihydrolipoamide and CO_2; thiamine diphosphate is a coenzyme. The enzyme in humans consists of two α (41 kDa each) and two β (36 kDa each) subunits. The α subunit is catalytic and binds the pyrophosphate end of the thiamine pyrophosphate, while the β subunit binds the thiazolidine ring of the coenzyme. Numerous mutations (mostly derived *de novo* in the gene on the X chromosome) in the α subunit result in enzyme deficiency and severe lactic acidosis.

[pyruvate dehydrogenase (lipoamide)]-phosphatase EC 3.1.3.43; an enzyme that catalyses the hydrolysis of phosphate from [pyruvate dehydrogenase (lipoamide)] phosphate. This hydrolysis activates the enzyme activity. Enzyme deficiency leads to inactivation of the α subunit of the appropriate dehydrogenase and consequent lactic acidosis.

pyruvate kinase EC 2.7.1.40; *systematic name*: ATP:pyruvate 2-*O*-phosphotransferase; *other names*: phospho*enol*pyruvate kinase; phospho*enol* transphosphorylase. An enzyme that catalyses the formation of pyruvate and ATP from phospho*enol*pyruvate and ADP; it requires Mg^{2+} and K^+. In the glycolytic pathway, it effects the second phosphorylation of ADP to ATP. In many cases the enzyme is a homotetramer. In humans there are two genes for the enzyme: PKLR, which is expressed in liver and erythrocytes, and PKM, which is expressed in muscle and other tissues. Numerous mutations in PKLR result in an autosomal recessive form of hemolytic anemia.

[pyruvate kinase]-phosphatase EC 3.1.3.49; an enzyme that catalyses the hydrolysis of phosphate from [pyruvate kinase] phosphate in order to activate pyruvate kinase.

pyruvate–malate cycle a metabolic cycle involving malate dehydrogenase (oxaloacetate-decarboxylating) (the **malic enzyme**) that occurs during fatty-acid biosynthesis. In this situation, acetyl-CoA is transported into the cytoplasm as citrate, formed by mitochondrial citrate synthase; the citrate is cleaved in the cytoplasmic compartment to acetyl-CoA, which participates in fatty-acid synthesis, and oxaloacetate. No transport system exists for taking this oxaloacetate back into the mitochondrion; however, it can be reduced to malate by cytoplasmic NAD$^+$-linked malate dehydrogenase, and the malate so formed can be converted to pyruvate by malic enzyme, EC 1.1.1.38; the pyruvate can then be transported into the mitochondrion, to be carboxylated to oxaloacetate by **pyruvate carboxylase**.

pyruvic–malic carboxylase *an alternative name for* **malic enzyme**.

python *see* **programming language**.

PYY *abbr. for* peptide YY.

PZ *abbr. for* pancreozymin.

PZP *abbr. for* pregnancy zone protein.

Qq

q *symbol for* quartet (in nuclear magnetic resonance spectroscopy).

q *symbol for* **1** heat (alternative to Q). **2** partition function (individual entity). **3** specific humidity.

Q *symbol for* **1** a residue of the α-amino acid L-glutamine (alternative to Gln). **2** a residue of the ribonucleoside **pseudouridine** (replacing Ψ for computer work). **3** coenzyme Q (i.e. **ubiquinone**); not recommended. The number of prenyl residues may be indicated by a suffixed arabic number, e.g. Q-10. **4** queuosine.

Q *symbol for* **1** heat (alternative to q). **2** electric charge. **3** radiant energy (alternative to W). **4** *or* Q_v quantity of light. **5** partition function (whole system).

Q_{10} *symbol for* temperature coefficient of a reaction.

Q_{CO2} *symbol for* metabolic quotient in respect of discharge of carbon dioxide; it is expressed in terms of microlitres CO_2 evolved per milligram dry mass of material per hour.

Q_{O2} *symbol for* metabolic quotient in respect of uptake of dioxygen; it is expressed in terms of microlitres O_2 absorbed per milligram dry mass of material per hour.

Q_S *symbol for* a measure of the activity of an enzyme, especially a respiratory enzyme, defined as the number of microlitres (at stp) of gaseous substrate S used up per hour per milligram enzyme. It could be extended to nongaseous substrates by taking 1 µmol as equivalent to 22.4 µL.

QAE *abbr. for* the quaternized aminoethyl; denoting the group diethyl-(2-hydroxypropyl)aminoethyl; $(C_2H_5)_2(CH_3–CHOH–CH_2)N^+–CH_2–CH_2–$; a strongly basic substituent sometimes used in hydroxylated chromatographic support matrices, as in QAE-Sephadex, to form anion exchangers. *Compare* **DEAE**.

Q cycle *an alternative name for* **protonmotive Q cycle**.

Q enzyme *an alternative name for* amylopectin branching enzyme; *see* **branching enzyme**.

Q gas a mixture of 98.7% helium and 1.3% butane, used as filling for gas-flow Geiger counters.

QH• *symbol for* ubisemiquinone.

QH_2 *symbol for* ubiquinol.

Q repeat *an alternative name for* **glutamine repeat**.

QTL *abbr. for* quantitative trait locus.

quad denoting four kinetically important substrates or products in an enzyme mechanism. *See* **reactancy of enzymes**.

quadri+ *or (sometimes)* **quadru+** *or (before a vowel)* **quadr+** *comb. form* four; fourth or one-fourth; square.

quadruplex DNA *another name for* **tetraplex DNA**.

quadrupole mass spectrometer A type of **mass spectrometer** in which the molecular ions are separated by mass filter comprising four metal rods with an alternating high frequency voltage (quadrupole field).

quadrupole, nuclear electric *see* **nuclear quadrupole moment**.

quality factor *or (formerly)* **relative biological effectiveness** an index of the ability of a given type of ionizing radiation to cause biological damage, depending on the density of the ionization produced relative to that produced by gamma radiation. For all X- (and gamma) radiation and beta particles (+ or –) likely to be encountered in the use of radioisotopes it is assigned a value of unity, for thermal neutrons usually a value of 3, and for all alpha particles a value of 10. *See also* **dose equivalent**.

quanta the plural of **quantum**.

quantal 1 of, pertaining to, or being a **quantum** or something that is quantized; of or pertaining to the quantum theory. **2** of a biological effect or response in which there are only two categories, conditions, or states (e.g. all or none, alive or dead). **—quantally** *adv.*

quantitative electrophoresis *(sometimes) an alternative name for* **crossed immunoelectrophoresis**.

quantitative trait locus *abbr*.: QTL; a region of a chromosome containing genes that are believed to make a significant contribution to the expression of a complex phenotypic trait. Quantitative traits (QTs) are typically affected by more than one gene and by the environment, and include several medically significant traits (e.g. blood pressure, obesity). Once mapped to small chromosomal regions (e.g. using linkage maps), specific genes can be isolated by other molecular methods.

quantity *or* **physical quantity** *(in systems of measurement)* any property whose value can be expressed as the product of a numerical value and a unit. In the International System of Units (*see* **SI**) there are seven **base quantities**, physical quantities regarded as being dimensionally independent; these are: length, mass, time, electric current, thermodynamic temperature, amount of substance, and luminous intensity; all are arbitrarily defined. **Derived units** are expressed algebraically in terms of the base units. Symbols for physical quantities are printed in italic type; they are generally single Roman or Greek letters, and may be lower case or capital.

quantity of electricity *an alternative name for* **electric charge**.

quantize *or* **quantise** to restrict (a physical quantity) to a set of discrete values, characterized by quantum numbers. A quantized physical quantity cannot vary continuously but must change in steps.

—quantization *or* **quantisation** *n.*

quantum (*pl.* **quanta**) **1** a (specific) quantity or amount of something. **2** a unit amount of a physical quantity, especially of electromagnetic energy, such that all other amounts are integral multiples of it. According to the **quantum theory**, a quantum of energy released during radiation emission or taken up during radiation absorption is equal to $h\nu$, where h is the Planck constant and ν the frequency of the radiation in hertz. A quantum of light (or other electromagnetic energy) is termed a **photon**.

quantum efficiency 1 *(in a luminescent system)* the fraction of the molecules in a particular excited state that emit luminescence. **2** *(in biochemistry) an alternative term for* **quantum yield** (def. 1).

quantum mechanics a mathematical theory developed from the quantum theory (*see* **quantum**) as a replacement for classical mechanics in order to explain satisfactorily the behaviour of atoms, molecules, and elementary particles in terms of observable quantities such as the intensities and frequencies of spectral lines.

quantum number any of a set of small integral or half-integral numbers that give the various possible values of a quantized property of a system. Quantum numbers are used especially in describing the properties of elementary particles, such as their charge (values of 0, +1, or –1) or spin (values of +1/2, or –1/2), and in specifying the energy states of electrons in atomic orbitals (each of which is characterized by a unique set of four quantum numbers).

quantum requirement *(in photosynthesis)* the inverse of **quantum yield** (def. 2); i.e. the number of quanta of light energy required to bring about the release of one molecule of dioxygen. The theoretical value is eight, but the value observed in an experimental system is generally somewhat higher, depending on conditions.

quantum theory *see* **quantum**.

quantum yield 1 *abbr*.: Q; *(in a luminescent system)* the probability of luminescence occurring in given conditions, expressed by the ratio of the number of photons, i.e. quanta of light, emitted by the luminescing species to the number absorbed. *Compare* **quantum efficiency**. The measurement of Q requires the counting of photons, because

$$Q = \text{photons emitted/photons absorbed.}$$

It requires highly specialized instrumentation, but a less rigorous method may be employed in which the fluorescence of a fluor is compared with that of a fluor of known Q. Then

$$Q_x = [I_x Q_s A_s]/[I_s A_x]$$

where Q_s is the quantum yield of the standard, I_s and I_x are the fluorescence intensities of the sample and standard and A_s and A_x are the percentage of absorption of each solution at the exciting wavelength. **2** *(in photosynthesis)* the inverse of **quantum requirement**; i.e. the fractional number of molecules of carbon dioxide reduced per photon absorbed.

quartz a colourless, often transparent, glassy form of silica, SiO_2, used in optical devices and cuvettes because of its transparency to near-ultraviolet radiation. It is enantiomorphous, the right- and left-handed forms rotating the plane of polarized light in opposite directions.

quasi-species (*in virology*) the population of closely related but different viral genomes that evolves over time through spontaneous mutations within an individual infected with a single genotype. Diversification through the emergence of quasi-species is one mechanism by which viruses evade the host immune response.

quaternary **1** consisting of four (items, parts, etc.); by or in fours. **2** *(in chemistry)* consisting of or containing an atom bound to four atoms or groups. **3** of the fourth order; fourth in a series or hierarchy.

quaternary ammonium compound any compound that can be regarded as derived from ammonium hydroxide or an ammonium salt by replacement of all four hydrogen atoms of the NH_4^+ ion by organic groups. Certain compounds of this class – ones in which one of the organic groups is a long-chain (C_8–C_{18}) alkyl group and the other three are shorter-chain alkyl or other groups – have the properties of cationic detergents and are powerful antimicrobial agents. They are bacteriostatic at low concentrations and bactericidal at higher concentrations, being generally more active against Gram-positive than Gram-negative organisms. They display relatively low toxicity to higher animals and humans, and hence are widely used as antiseptics and disinfectants.

quaternary structure the fourth order of complexity of structural organization exhibited by protein, nucleic acid, and nucleoprotein molecules. It refers to the arrangement in space of the subunits of a multimeric macromolecule, and the ensemble of its intersubunit contacts and interactions, without regard to the internal geometry of the subunits. Hence, it is possessed only when the molecule in question is made up of at least two (identical or non-identical) subunits that are (at least potentially) separable, i.e. are not linked by covalent bonds.

Quellung reaction *or* **Neufeld Quellung reaction** *or* **pneumococcus capsule swelling reaction** the swelling of the capsule observed when specific antibody is mixed with suitable bacterial cells (e.g. pneumococci). It is probably due to deposition of antibody on the outside of the capsule, making the latter clearly visible. [From the German, *Quellung*, swelling; described by Ferdinand Neufeld (1869–1945), German bacteriologist, in 1902.]

quench correction *(in liquid-scintillation counting)* a correction to be applied to an observed count rate to allow for losses resulting from **quenching** (def. 2).

quenched flow *see* **rapid-reaction kinetics**.

quencher a substance capable of reducing or destroying luminescence through deactivation of an excited chemical species. In biological systems this usually occurs by chemical reaction (e.g. complex formation), by exchange of energy on collision, or by resonance energy transfer.

quenching **1** the reduction or destruction of luminescence, especially fluorescence, of a sample by addition or inclusion of a **quencher**. Fluorescence quenching is the basis of a useful technique for studying the binding of small molecules to proteins or other macromolecules. **2** the reduction by whatever means of the efficiency of energy transfer from beta particles to the photomultiplier(s) in a liquid-scintillation counter. Such means include: (1) **dilution quenching** – reduction of the probability of scintillation occurring through dilution of the scintillator by the sample; (2) **chemical** (or **impurity**) **quenching** – absorption by a component of the sample of some of the energy of the beta particles without emitting photons, or (without fluorescing and in competition with the primary fluor) of some of the photons emitted by excited solvent molecules; and (3) **colour quenching** – absorption by a coloured component of the sample of some of the photons emitted by the secondary fluor. **3** the termination of a chemical or enzymic reaction by addition of another reagent or sudden change of the conditions.

quercetin 3,3′,4′,5,7-pentahydroxyflavone; a member of the **flavonoids**, or **flavones**, widely distributed in plants, often as **glycosides**; it is the aglycon of **quercitrin**, **rutin**, and other materials. Known in folk medicine for its anti-inflammatory properties, it inhibits the **lipoxygenase** pathway, has some antiplatelet and antithrombotic activity *in vivo*, inhibits mast-cell degranulation, and possesses anti-asthmatic activity. It inhibits many enzymes, including protein kinases, and also inhibits DNA, RNA, and protein synthesis. A number of its actions may reflect its property as a nucleoside antagonist.



quercitrin quercetin-3-L-rhamnoside. *See also* **quercetin**.

query sequence *(in bioinformatics)* a sequence used as a probe to search a database.

queuosine *symbol*: Q; any one of a series of nucleosides found in tRNA and having an additional pentenyl ring added via an NH group to the methyl group of 7-methylguanosine. The pentenyl ring may carry other substituents.

Qui *symbol for* a residue (or sometimes a molecule) of the deoxyaldohexose **quinovose**.

Quin-2 *abbr. for* 2-[(2-amino-5-methylphenoxy)methyl]-6-methoxy-8-aminoquinoline-*N*,*N*,*N*′,*N*′-tetraacetic acid; a molecule functionally related to the Ca^{2+}-chelating agent **EGTA**, but containing fluorescent groups. The quantum yield of fluorescence is greatly enhanced on binding Ca^{2+}, leading to its use as a quantitative indicator of Ca^{2+} concentration. It is normally used as its tetraacetoxy ester, which readily crosses the plasma membrane and is then hydrolysed within the cell by esterases to Quin-2, the polar nature of which causes it to be retained as an intracellular indicator. *See also* **Fura-2**, **INDO-1**.



quinacrine *or* **mepacrine** *or* **atebrine** 6-chloro-9-(4-diethylamino-1-methylbutylamino)-2-methoxyacridine; a derivative of **acridine**, formerly used as an antimalarial and anthelmintic. It fluoresces powerfully in UV light and can be used as a fluorochrome to label DNA in chromosomes.



quinacrine mustard a compound derived by chloro-substitution of the terminal methyls of **quinacrine** ethylamino groups, and possessing properties of an alkylating agent; this enhances its value as a DNA-labelling agent.

quinhydrone an addition compound of one mole each of hydroquinone and *p*-benzoquinone. It is a reddish-brown crystalline substance with a dark-green lustre, useful as an antioxidant, in photography, and as a redox system in the **quinhydrone electrode**.

quinhydrone electrode a half-cell consisting of a bright platinum (or sometimes gold) electrode immersed in a test solution to which has been added a little **quinhydrone**. It has an electric potential related to the pH value of the solution and thus is useful as a secondary hydrogen electrode for the electrometric measurement of pH.

quinic acid the D enantiomer ($1\alpha,3\alpha,4\alpha,5\beta$)-1,3,4,5-tetrahydroxycyclohexanecarboxylic acid occurs commonly in plants, either free or as esters (e.g. **chlorogenic acid**), and may make up as much as 2–10% of the dry weight of leaves. It may be formed by the **shikimate pathway**. Its catabolism to protocatechuic acid has been extensively studied in *Aspergillus nidulans* and *Neurospora crassa*.

quinidine *β*-quinine; 6′-methoxycinchonan-9-ol; a stereoisomer of **quinine** noted for its cardiac anti-arrhythmic effects.



quinine 6′-methoxycinchonan-9-ol; a bitter-tasting alkaloid obtained especially from the bark of cinchona, any of a number of trees or shrubs of the tropical genus *Cinchona* (especially the Javan species *C. lidgeriana* and various South American species). It was formerly much used (and sometimes is still needed) for the prevention and treatment of malaria. It binds to the DNA of the malarial parasite *Plasmodium* spp., and is thought thereby to inhibit biosynthesis of the parasite's nucleic acids. Quinine and drinks containing it (e.g. tonic water) help to prevent cramp. *Compare* **quinidine**.



quinoid *or* **quinonoid** of, derived from, or resembling a **quinone** (def. 2).

quinol *an alternative name for* **hydroquinone**.

quinolinic acid *or* **pyridine dicarboxylic acid** a degradation product of tryptophan that, as the substrate for quinolate phosphoribosyltransferase, is the precursor of nicotinate mononucleotide in the biosynthesis of the coenzymes NAD and NADP.

4-quinolone antibiotic *a generic term for* any of a wide range of synthetic antibacterial compounds whose molecular structures contain a 4-oxo-1,4-dihydroquinoline or a 4-oxo-1,4-dihydrocinnoline nucleus; e.g. **cinoxacin**, **ciprofloxacin**, **nalidixic acid**, **oxolinic acid**. Their antibiotic activity derives from interaction with the A subunit of bacterial DNA gyrase (*see* type II **DNA topoisomerase**); this results in trapping of bacterial DNA in the complex it forms with the A subunit. Rejoining of the DNA strands broken by the enzyme is thereby arrested.

quinone **1** *a common name for* ***p*-benzoquinone**. **2** any member of a class of diketones derivable from aromatic compounds by conversion of two CH groups into CO groups with any necessary rearrangement of double bonds. Simple quinones are usually *p*-quinones, i.e. derivatives of *p*-benzoquinone (*compare* **hydroquinone** (def. 2)), but they may also be *o*-quinones, i.e. derivatives of ***o*-benzoquinone** (*compare* **catechol** (def. 2)). Naturally occurring quinones form a large, varied, and widespread group of compounds; they include numerous pigments, various electron carriers (e.g. **plastoquinone**, **ubiquinone**), and vitamins K. *See also* **semiquinone**.

+quinone *comb. form* denoting a **quinone** (def. 2); e.g. benzoquinone, anthroquinone, naphthoquinone.

quinone cofactor *see* **quinoprotein**.

quinonoid *an alternative term for* **quinoid**.

quinoprotein *other name*: quinoenzyme; any enzyme protein that contains a **quinone cofactor**, i.e. the freely dissociable pyrroloquinoline quinone (PQQ) or methoxantin, or the covalent species topaquinone (TPQ), tryptophan tryptophylquinone (TTQ), or lysine tyrosylquinone (LTQ) that are derived by post-translational modification of certain proteins. PQQ is characteristic of oxidoreductase enzymes within the sub-subclass EC 1.1.99, which includes alcohol dehydrogenase (acceptor) (EC 1.1.99.8) of methylotrophic bacteria, glucose dehydrogenase (pyrroloquinoline-quinone) (EC 1.1.99.17), and a number of dehydrogenases acting on other specified (types of) alcohols or polyols. TPQ occurs in bovine serum copper amine oxidase, TTQ in bacterial amine dehydrogenase, and LTQ in bovine aorta lysyl oxidase (EC 1.4.3.13).

quinovosamine 2-amino-2,6-dideoxy-D-glucose; an amino derivative of **quinovose** present in bacterial polysaccharides.

quinovose *symbol*: Qui; *a trivial name for* 6-deoxy-D-glucose. *α*-Quinovose occurs, e.g., as its 6-sulfo derivative (6-deoxy-*α*-D-glucopyranosyl 6-*C*-sulfate) in the sulfoquinovosyl diacylglycerols, which form one of the two major groups of the glycerolipids of chloroplasts. The sulfoquinovosyl derivative also occurs in some **cardiac glycosides**.

quinternary structure the arrangement of separate molecules in macromolecular complexes, such as in protein–protein or protein–nucleic acid interactions.

quisqualate receptor *see* ***α*-amino-3-hydroxy-5-methyl-isoxazolepropionic acid receptor**.

quorum sensing the process by which bacteria detect their population cell density and use the information to regulate gene expression accordingly.

Rr

r **1** *symbol for* **ribo+** (def. 1); it is used as a prefix in (one- or three-letter) symbols for ribonucleosides for emphasis or clarity, especially to distinguish from 2′-deoxyribonucleosides. **2** *symbol for* reaction. **3** *abbr. for* rat (as a prefix to an abbreviation for the name of a peptide hormone); denoting derived (or as if derived) from a rat or rats; e.g. rGH.

r *symbol for* **1** concentration ratio. **2** rate of concentration change. **3** radius. **4** interatomic distance.

R *symbol for* **1** a residue of the α-amino acid L-arginine (alternative to Arg). **2** a residue of an incompletely specified base in a nucleic-acid sequence that may be either adenine or guanine. **3** a residue of an unspecified purine nucleoside (alternative to Puo). **4** an unspecified univalent group in a formula of an organic compound. The group must be attached by means of carbon and derived from an aliphatic, carbocyclic, or heterocyclic compound. Up to three such groups, when different, may be designated R, R', and R'', or R^1, R^2, and R^3; for more than three such groups, superscript numerals only should be used. **5** röntgen (a non-SI unit of radiation exposure). **6** resonance effect (in electron displacement).

R *symbol for* **1** electric resistance. **2** thermal resistance. **3** gas constant. **4** molar refraction.

R *stereochemical descriptor* denoting *rectus*; i.e. the absolute configuration of a chiral compound in which the priority (obtained using the Cahn–Ingold–Prelog sequence rules) of the substituent groups on the chiral centre decreases in a clockwise (right-handed) direction. For use as a prefix in chemical nomenclature, the descriptor is placed in parentheses and connected with a hyphen, e.g.(*R*)-alanine. For chiral compounds in which the relative but not the absolute configuration is known, *rectus* configuration is denoted by the prefix (*R**)-. *See* **sequence rule**. *Compare* ***S***.

R_B *symbol for* R_B value.

R_f *or* **R_F** *symbol for* R_f value.

R_p *symbol for* phosphorylation state ratio.

R_s *symbol for* saturation ratio.

RAB a gene encoding a Rab protein – any of a family of GTP-binding proteins similar to Ras proteins (*see* ***RAS***) and probably involved in membrane traffic, etc. Rab proteins contain dicysteine motifs near their C termini to receive a geranylgeranylyl moiety.

rabbit aorta-contracting substance *abbr*.: RCS; a name given (in 1969) to an unstable factor released from guinea-pig lung that caused contraction of isolated strips of rabbit aorta. The activity was probably due to the presence of thromboxane A_2 (*see* **thromboxane**).

rabbit reticulocyte system a cell-free system, from lysed rabbit reticulocytes, that translates added eukaryote mRNAs from a wide variety of heterologous sources. Endogenous mRNA is destroyed using a Ca^{2+}-dependent ribonuclease, micrococcal endonuclease; this enzyme is inactivated by adding EGTA. Heterologous mRNA is then added and is translated by the system.

rac- *abbr. for* racemo-.

Rac either of two **RhoGTPases** that are cytosolic components of the **phagocyte NADPH oxidase** system, Rac 1 and Rac 2, which show 92% homology. They are involved in activation of MAP kinase and JNK kinases by integrins.

RacA *abbr. for* remodelling and anchoring of chromosome A; a protein of *Bacillus subtilis* and related spore-forming species that anchors the origin of replication regions of sister chromosomes to the cell poles during sporulation.

RACE *abbr. for* rapid amplification of cDNA ends; a variation on the **polymerase chain reaction** designed for amplification of sequence corresponding with the 5′ or 3′ ends of specific mRNAs. The former is important for the location of the transcription start site as well as providing full-length cDNA sequences.

racemase any enzyme that interconverts the two enantiomers of a chiral compound; such enzymes are categorized in subclass EC 5.1 (which also includes **epimerases**). If more than one chiral centre is present, a racemase must invert configuration of all the chiral centres. Thus, the name methylmalonyl-CoA racemase, sometimes used for methylmalonyl-CoA epimerase (EC 5.1.99.1), is incorrect – the enzyme does not change configurations of the chiral centres of the CoA moiety.

racemate any homogeneous phase containing equimolar amounts of enantiomeric molecules.

racemic *symbol*: (±)- *or (formerly) dl-*; denoting the presence of equimolar amounts of the dextrorotatory and levorotatory enantiomers of a compound, regardless of whether the (optically inactive) product formed is crystalline, liquid, or gaseous. A homogeneous solid phase composed of equimolar amounts of enantiomeric molecules is termed a **racemic compound**, and a mixture of equimolar amounts of enantiomeric molecules present as separate solid phases is termed a **racemic mixture**; *see also* **racemate**. A (±)-product may be resolved into its (+)- and (–)-components. The term is derived from **racemic acid** [from Latin *racemus*, bunch of grapes], the optically inactive mixture of (+)- and (–)-tartaric acids sometimes found during the manufacture of wine. By extension, the term is applied to DL- and (*RS*)-mixtures. *See* **D/L convention**, **optical isomerism**, **sequence rule**. *See also* ***racemo-***.

racemize *or* **racemise** to induce the formation of a mixture of the two possible enantiomers from one of the pure isomers of a chiral compound. **—racemization** *or* **racemisation** *n.*

racemo- *abbr*.: *rac-*; *prefix (in chemical nomenclature)* designating a racemate. It may be used as an alternative to the symbol (±)- or (for certain classes of racemic compounds) the symbol DL-. *Compare* ***meso-***.

rachitic of, pertaining to, or afflicted with **rickets**.

rachitis *an alternative name for* **rickets**.

rachitogenic tending to cause **rickets**.

rad **1** *symbol for* radian. **2** *symbol*: rad *or* (to avoid possible confusion with **rad** (def. 1)) rd; the cgs unit of absorbed dose of ionizing radiation, equivalent to an absorption of 0.01 joule of energy per kilogram (= 100 ergs per gram) of irradiated material. Whereas the rad represents, in practice, about the same amount of energy as the **röntgen** (the exact equivalence depending on the material irradiated), it applies to any type of ionizing radiation in any medium. 1 rad = 0.01 Gy. **3** *abbr. for* radiation.

radial **1** of, resembling, or relating to a radius or ray; in rays. **2** emanating from the centre of a circle or a common central point. **3** spreading out uniformly in all directions on a surface. **—radially** *adv.*

radian *symbol*: rad; the SI supplementary unit of plane angle. One radian is equal to the angle subtended at the centre of a circle by an arc whose length is equal to the radius. It is dimensionless. There are 2π radians in a circle; 1 rad ≈ 57.295 78°.

radiant energy *symbol*: *Q or W*; the energy of any form of electromagnetic radiation. The SI derived unit is the **joule**.

radiant intensity *symbol*: *I*; the **radiant power** of radiation from a point source per unit of solid angle; i.e. $I = \mathrm{d}\Phi/\mathrm{d}\Omega$, where Φ is the radiant power and Ω is the solid angle measured in steradians. The SI unit is the watt per steradian (Wsr^{-1}).

radiant power *or* **radiant flux** *symbol*: *P or Φ*; the rate of flow of energy of radiation; i.e. $\Phi = \mathrm{d}Q/\mathrm{d}t$, where Q is the radiant energy. The SI derived unit is the watt.

radiation **1** the emission of energy from a source and its transmission as particles, rays, or waves, especially as electromagnetic rays or waves, sound waves, or streams of subatomic particles. **2** energy so transmitted, especially the corpuscular and electromagnetic rays emitted in the decay of radionuclides. **3** **ionizing radiation**. **4** divergence from a common point, especially radially from a central point or source.

radiation absorbed dose *see* **absorbed dose**, **rad** (def. 2).

radiation biology *an alternative name for* **radiobiology**.

radiation-chemical reaction any chemical reaction that is initiated by the absorption of radiation but is distinguishable from a **photochemical reaction** by its lack of specificity (i.e. by giving rise to a variety of reaction products) and by occurring at higher radiation energies (i.e. by absorption either of electromagnetic radiation from the mid-ultraviolet region onwards or of high-energy particulate radiation) and thus by resulting always in the formation of detectable ions.

radiation chemistry the branch of chemistry concerned with **radiation-chemical reactions**. *Compare* **radiochemistry**.

radiation damage the totality of the harmful changes induced in a cell or tissue by radiation. The harmful effects may include formation of **thymine dimers** in DNA or of radicals from polyunsaturated acyl groups in lipids.

radiation dose equivalent *see* **dose equivalent**.

radiation hybrid map *abbr*.: RH map; a map of irradiated chromosomal sites derived from hybrid cells containing fragments of irradiated chromosomes. RH maps provide important markers, allowing the construction of precise sequence-tagged site (STS) maps (with the STSs positioned according to their frequency of separation by radiation-induced breaks). These are useful in ordering genetic loci along chromosomes and in studying multifactorial diseases.

radiation inactivation method a technique, based on **target theory**, that enables the size of the functional unit of a biologically active macromolecule (or of its complexes with other molecules) to be estimated; it can be used on unpurified (e.g. membrane-bound) material. Determinations are made of the biological activity remaining in a sample after exposure to various large doses of ionizing radiation (electrons or X- or gamma radiation of at least 1 MeV), and the value, D_{37}, of the radiation dose, expressed in Mrad, required to reduce the activity to 37% of (i.e. e^{-1} times) its original value is obtained; the relative molecular mass, M_r, of such a macromolecule may then be found from the empirical relationship $M_r = 6.4 \times 10^5/D_{37}$, where D_{37} is determined at 30°C.

radiation source a quantity of radioactive material used as a source of ionizing radiation.

radical *(in chemistry)* **1** any molecular entity, charged or uncharged, that possesses an unpaired electron (but normally excluding any paramagnetic metal ion); often formed by homolysis of a covalent bond. Radical character is indicated in a formula by a centred dot symbolizing the unpaired electron and placed (if possible) beside the symbol for the atom of highest spin density; e.g. HOO•, •CH_3. The term **free radical** is now preferably restricted to any radical that does not form part of a **radical pair**. **2** *a former name for* **group** (def. 2).

radical anion *see* **radical ion**.

radical cation *see* **radical ion**.

radical centre the atom in any polyatomic **radical** (def. 1) on which the unpaired electron is largely localized.

radical ion any **radical** (def. 1) that carries an electric charge. One carrying a negative charge is termed a **radical anion** (e.g. the benzene radical anion, C_6H_6 •$^-$); one carrying a positive charge is termed a **radical cation** (e.g. the benzene radical cation, C_6H_6 •$^+$).

radical pair 1 any two **radicals** (def. 1) in close proximity in liquid solution, with a solvent cage. They may have been formed simultaneously, e.g. by homolysis, or have come together by diffusion. Whilst together, correlation of their unpaired electron spins occurs and manifests itself as a distortion of nuclear magnetic resonance spectra. **2** a cation and anion radical produced transiently in the primary photochemical process of photosynthesis. *See* **photosystem**.

radical SAM refers to enzymes that bind S-adenosyl-L-methionine (SAM) next to a [4Fe-4S] cluster to generate a reactive free-radical species.

radical scavenger any substance that can react readily with, and thereby eliminate, radicals. In biological systems or materials, radical scavengers may function as **antioxidants** or may protect from damage by ionizing radiation. Among the important radical scavengers that function in animal tissues at physiological concentrations are the water-soluble substances ascorbate, glutathione, and the purine bases, and the fat-soluble substances tocopherols, the retinols, the carotenes, and the ubiquinones.

radioactivate to convert a stable nucleus into one undergoing radioactive decay by bombardment with high speed particles, including protons, alpha particles, neutrons, and deuterons. These are formed in a cyclotron or synchrotron from a radioactive source, and accelerated through a potential difference of a few thousand volts by a magnetic field before being focused on the substance to be converted.

radioactivation analysis *or* **activation analysis** a method for the qualitative and/or quantitative estimation of the chemical elements in a sample. It depends on the identification and determination of the radionuclides formed when the sample is bombarded with neutrons or other particles.

radioactive having the properties associated with a **radioactive isotope**.

radioactive concentration the **activity** (def. 2) per unit quantity of any material in which a **radionuclide** occurs. *See also* **specific activity**.

radioactive decay *see* **decay** (def. 1b).

radioactive isotope *or* **radioisotope** any isotope of a chemical element whose nucleus is unstable and emits alpha, beta, or gamma rays. The product is another element, which may be stable or unstable; if the latter, it decays further. Thus, the principal isotope of uranium, ^{238}U, emits an alpha particle and decays to ^{234}Th, which emits a beta particle forming ^{234}Pa; this chain continues to the formation of ^{206}Pb, which is stable.

radioactive label *or* **radiolabel** a **radioactive isotope** incorporated into a molecule to confer on it the property of radioactivity.

radioactive tracer *or* **radiotracer** a radioactive substance that is added to a metabolic system in quantities (mass) too small to perturb the system, in order to follow, by isolating the radioactive intermediates formed, the sequence of transformations undergone normally by the same (nonradioactive) molecule under similar conditions.

radioactivity 1 the emission of radiation from certain **nuclides** by the spontaneous transformation of their **nuclei**. **2** *(loosely)* the radioactive material itself or its emitted radiation. *See* **activity** (def. 2).

radioallergosorbent test *abbr*.: RAST; a test used primarily for quantifying the levels of antigen-specific immunoglobulin E (IgE) in serum. A specific allergen, which has been covalently coupled to an insoluble **Sephadex** carrier, is incubated with serum containing the unknown amount of IgE. The carriers are then washed and further incubated with radiolabelled antibodies to IgE, the amount of radioactivity bound being a measure of the amount of IgE. The advantage of this method over the **radioimmunosorbent test** is that IgE specific to a particular antigen can be selectively quantified.

radioassay any type of **assay** in which a radioactive isotope is used in the measurement. The term embraces, e.g., **immunoradiometric assay**, **radioimmunoassay**, and competitive protein-binding assay.

radioautogram *or* **radioautograph** *or* **autoradiogram** the pattern formed after development of an X-ray film that has been exposed to a paper, gel, or thin-layer chromatogram containing radioactive compounds.

radioautograph 1 *an alternative term for* **radioautogram**. **2** to prepare a radioautogram. **—radioautography** *n.*

radiobiology *or* **radiation biology** the study of the interaction between radiation and biological material.

radiocarbon any radioactive isotope of carbon, usually carbon-11 or carbon-14.

radiochemical purity *abbr*.: RCP; the proportion of the total **activity** (def. 2) that is present in the stated chemical form in a radioactive material.

radiochemistry the branch of chemistry concerned with the compounds of radioactive nuclides. *Compare* **radiation chemistry**.

radiochromatogram a chromatogram of substances some or all of which contain a radioactive isotope.

radiofrequency radiation electromagnetic radiation encompassing wavelengths in the region 1 mm (300 GHz) to 30 km (10 kHz) (frequencies in parentheses). This range includes microwave radiation and lies above that of infrared radiation.

radiography the use of X-rays to examine the internal structures of a body. An X-ray film is placed behind the body, through which X-rays are passed. After exposure, there are areas of the film in which development has not occurred due to absorption of the X-rays by structures of the body, thus yielding a pattern of these structures. **—radiographer** *n.*; **radiographic** *adj.*; **radiographically** *adv.*

radioimmunoassay *abbr*.: RIA; a highly sensitive method of assay of nonradioactive material. A known amount of antibody (Ab) directed against the substance (antigen, Ag) to be assayed is saturated with a mixture of Ag and radioactive Ag (Ag*), so that total Ag (Ag + Ag*) is in excess. When nonradioactive Ag is added to Ab along with Ag*, Ag and Ag* compete for binding to Ab, so that less Ag* will be found in the antibody–antigen complex as the ratio Ag:Ag* increases. If the antibody–antigen complex is then separated from free antigen, the total amount of antigen (the substance being assayed) can be calculated from the ratio Ab-Ag*:Ag* and the known **titre** of antibody. It is often convenient to attach the antigen to plates so that the amount of ligand bound to the plate is proportional to the amount of test antibody.

radioimmunosorbent test *abbr*.: RIST; a test used primarily for quantifying total serum immunoglobulin E (IgE) levels. Antibodies specific for IgE, covalently linked to an insoluble dextran, are incubated first with a known amount of radiolabelled IgE and then with the serum containing the unknown amount of IgE. From the decrease in the amount of radiolabel bound to the immobilized antibodies, due to competition by the unlabelled IgE in the serum, the total amount of IgE in the serum can be estimated.

radioiodinate to incorporate one or more atoms of **radioiodine** (usually iodine-125 or iodine-131) into a molecule.

radioiodine any radioactive isotope of **iodine**, notably iodine-125 (half-life 60 days) and iodine-131 (half-life 8 days).

radioisotope a **radioactive isotope**.

radiolabel **1** a **radioactive label**. **2** to incorporate a radiolabel.

radioligand any **ligand** containing a radioactive isotope; *see also* **Scatchard plot**.

radiology the study and use of radiation and radioactive substances, especially in the diagnosis and treatment of disease. It includes the use of diagnostic X-rays in **radiography**, the therapeutic use of ionizing radiation to treat disease (**radiotherapy**), and the experimental and diagnostic use of radioisotopes introduced into the body. **—radiological** *adj.*; **radiologically** *adv.*; **radiologist** *n.*

radiolysis the cleavage of chemical bonds by high-energy radiation. **—radiolytic** *adj.*; **radiolyse** *vb.*

radiometer **1** any instrument used to measure radiant energy. **2** **Crookes radiometer** a specific type of radiometer in which the different behaviour of a polished surface, which reflects energy, and a blackened surface, which absorbs it, is utilized to cause a rotor to turn at a rate related to the intensity of radiation. [After William Crookes (1832–1919), British chemist and physicist.] **—radiometric** *adj.*; **radiometry** *n.*

radiomimetic **1** describing any drug or other chemical substance, typically an alkylating agent, whose effects in living systems (e.g. carcinogenic, immunosuppressive, mutagenic) resemble those produced by **ionizing radiation**; more loosely, describing any such agent able to cause gene and chromosome mutations. **2** a radiomimetic (def. 1) substance or agent.

radionuclide a radioactive **nuclide**. **—radionuclidic** *adj.*

radionuclidic impurity any radionuclide, other than the nuclide that should be present, in a radioactive material.

radionuclidic purity *or* **radiopurity** (of a radioactive material) the proportion of the total **activity** (def. 2) that is in the form of the stated **radionuclide**.

radiotherapy *see* **radiology**.

radiotracer *an alternative name for* **radioactive tracer**.

radixin a protein of the erythrocyte band 4.1 family present in a variety of eukaryotic cells; it shares about 75% similarity with human **ezrin**. It is an actin barbed-end capping protein, highly concentrated in the undercoat of the cell-to-cell **adherens junction** and the cleavage furrow in the interphase and mitotic phase.

radyl *(in chemical nomenclature)* a term used to indicate any acyl, alkyl, or alkenyl group where this cannot be specified in detail.

RAF any gene encoding a Raf protein, of which there are at least three: Raf-1, A-Raf, and B-Raf. These are protooncogene cytoplasmic serine/threonine protein kinases (EC 2.7.1.–) of the Ras/Mos family; they are homologous with members of the protein kinase C family in both their conserved C-terminal catalytic and regulatory N-terminal domains. Human Raf-1 has binding domains for ATP, phorbol ester, and diacylglycerol. This protein is involved in transduction of mitogenic signals from the cell membrane to the nucleus. In the mouse, *raf* is the transforming gene of the mouse sarcoma virus, 3611, v-Raf having a truncated regulatory domain that causes constitutive activation of kinase activity. The c-Raf-1 protein kinase, a 74 kDa protein, has been found in many mammalian cell types. Raf-1 is an important mediator of signals involving cell growth, transformation, and differentiation and is activated by a wide variety of extracellular stimuli. It has **MAP kinase** activity. In many cell types, Raf functions immediately downstream of the G-protein Ras (*see* ***RAS***) in the activation pathway; Ras mediates translocation of Raf-1 to plasma membrane, where it is activated. In some cells Raf may be phosphorylated and activated by a protein kinase C. The physiological substrate for Raf kinase is a protein kinase (MEK) of yeast that is required for meiotic recombination and which on phosphorylation can activate MAP kinase.

raffinose *or* **gossypose** *or* **melitose** *or* **melitriose** the **trisaccharide** *O*-α-D-galactopyranosyl-(1→6)-*O*-α-D-glucopyranosyl-(1→2)-β-D-fructofuranoside; it occurs in plants almost as commonly as sucrose, being present, e.g., in cereal grains, cotton seeds, and many legumes. It is the first member of a series in which galactosyl residues are attached to sucrose, others being the tetrasaccharide **stachyose** and the pentasaccharide **verbascose**; these are all synthesized from sucrose by transfer reactions in which an α-D-galactopyranoside of *myo*-inositol (i.e. galactinol) is the donor of the galactosyl residues.

raft a sphingolipid- and cholesterol-rich microdomain in a plasma membrane. Rafts are similar in composition to caveolae, but lack caveolin, and are present in all cell types. They segregate and concentrate GPI-anchored, doubly acylated peripheral membrane proteins and transmembrane proteins. They may be precursors of caveolae.

RAG *abbr. for* recombination-activating gene; either of two genes (locus at 11p13) that encode the lymphocyte-specific RAG1 and RAG2 proteins. RAG1 is a zinc finger protein that forms heterotetramers with RAG2. In cooperation, they bring together recombination signal sequences on the genes for V(D)J segments of the immunoglobulins. Rare inactivating mutations in either gene lead to T and B lymphocyte deficiency and severe combined immunodeficiency (SCID).

ragged-red fibers aerobic skeletal muscle fibers that accumulate enlarged and abnormal mitochondria containing highly-ordered inclusions when they are ischemic or anoxic. The mitochondrial aggregates appear red on staining with Gomori modified Trichrome. They are usually associated with mitochondrial disease. *See* **MERRF**.

Raji a lymphoblastoid cell line derived from an African patient with Burkitt's lymphoma.

r.a.m. *abbr. for* relative atomic mass.

ram *abbr. for* **ribosomal ambiguity**.

Ramachandran plot *or* **conformational map** a plot that shows the ranges of bond angles that are permissible and the main types of structure adopted by a polypeptide chain (e.g., α-helix, β-sheet). As the peptide bond, –C′O–NH–, is planar, a polypeptide chain has only two degrees of freedom per residue, the twist about the C^{α}–N bond axis, ϕ, and that about the C^{α}–C′ axis, ψ. Some conformations will be easily achieved; others will be impossible, because they would bring neighbouring unbonded atoms or groups within van der Waals contact distances. The Ramachandran plot shows the permitted range within a plot of ϕ against ψ. [After G. N. Ramachandran (1922–).]

Raman scattering the inelastic scattering of a photon by a molecule, producing in the scattered light weak radiation of frequencies not present in the incident light. The sample does not have an absorption band at the wavelength of the incident light (*compare* **fluorescence**) and the frequency differences between the weak Raman lines in the spectrum and the exciting line are characteristic of the scattering substance and independent of the frequency of the exciting line. [After Chandrasekhara Venkata Raman (1888–1970), Indian physicist.]

Raman spectrum a plot of **Raman scattering** over a range of frequencies.

Ramos a lymphoblast cell line derived from a Caucasian patient with Burkitt's lymphoma.

RAMP *abbr. for* receptor activity modifying protein.

Ran a small nuclear G-protein involved with **karyopherins** that exists in two conformational states depending on whether it binds GTP (RanGTP) or GDP (RanGDP). RanGTP causes disassembly of complexes of cargo plus **importin-β** but is required for assembly of cargo-**exportin** complexes. RanGTP concentrations are higher in the nucleus than the cytoplasm thus favouring disassembly of import complexes and formation of export complexes. *See also* ***RAN***.

RAN a gene encoding a small nuclear G-protein, first identified as a well-conserved gene distantly related to *H-RAS*. Its product, Ran, interacts with **RCC1**, and the complex is involved in regulating cell-cycle progression and messenger RNA transport. In the absence of RCC1, GDP–Ran predominates and this results in activation of **M-phase-promoting factor** and chromatin condensation. The presence of RCC1 activates nucleotide exchange on Ran, increasing the amount of GTP–Ran and preventing premature chromatin condensation. *See also* **nuclear pore**, **Ran**.

random coil the condition in solution of a linear polymer that exhibits little side group interaction, or resistance to rotation about the bonds in its chain. There are no preferred conformations. Quantitative expressions have been developed for the average radius of gyration. The term has formerly been incorrectly applied to various states of protein chains.

random copolymer a polymer of more than one species of monomer, in which the sequence of species within the polymer is not predetermined by controlled steps during synthesis, but depends only on random collisions between the reactant molecules. An example is the sequence of bases in RNA synthesized from nucleoside diphosphates by **polynucleotidephosphorylase**.

randomization *or* **randomisation** *(in experimental design)* the generation of data sets with different arrangements of the data, within the constraints of the experimental design. Randomization obviates the possibility of a systematic relationship between the data and any measurable characteristic of the procedure by which the data were sampled.

random mechanism *or* **random pathway** (for an enzymic reaction involving two substrates, $A + B \rightleftharpoons C$) a mechanism in which the enzyme, E, may first react with either substrate and the resulting enzyme–substrate complex then reacts with the second substrate, e.g. $A + E \rightleftharpoons EA$ then $EA + B \rightleftharpoons EAB$, or, $B + E \rightleftharpoons EB$ then $EB + A \rightleftharpoons EAB$, subsequently $EAB \rightleftharpoons E + C$. *Compare* **ordered mechanism**.

random priming a technique in which a mixture of short (typically 6 bp) oligonucleotides primes reactions catalysed by DNA polymerases. It is used in the synthesis of labelled DNA probes and is one of the options when priming cDNA synthesis catalysed by reverse transcriptase. Because all combinations of six nucleotides are present in the mixture of hexamers, priming is ensured at some point in the template sequence without prior need for specific sequence information.

random sample a selection of part of a population made in such a way that no individual is favoured over any other individual. *See also* **sample**, **statistical sample**.

ranitidine a competitive antagonist at histamine H_2 receptors, being the major and pharmacologically more selective analogue of the imidazole derivative, **cimetidine**. It inhibits histamine- and pentagastrin-evoked gastric acid secretion and cardiac stimulation and also inhibits gastric secretion evoked by physiological stimuli, agonists at muscarinic cholinoceptors, and gastrin. It is used in the treatment of gastric and duodenal ulcers. *One proprietary name*: Zantac (hydrochloride).



RANK *abbr. for* receptor activator of NF-κB; a member of the tumour necrosis factor receptor family that is present on osteoclasts and is the receptor for **RANKL**, which is present on osteoblasts and their precursor cells. The interaction of RANK with RANKL causes osteoclasts to differentiate and become active unless osteoprotegerin (which also binds RANKL) is present. Mutations in RANK cause familial expansile osteolysis.

RANKL *abbr. for* RANK ligand; *other names*: osteoprotegerin ligand; TNF-related activation-induced cytokine (*abbr.*: TRANCE). RANKL is released from its transmembrane precursor present on osteoblasts and their precursor cells, and the transmembrane precursor of RANKL, which is released by the action of an ADAM metalloprotease. It is the ligand for RANK on osteoclasts.

RANTES *abbr. for* regulated upon activation, normal T-cell expressed and secreted chemokine; *other names*: small inducible cytokine A5; a chemokine secreted by T cells and macrophages on stimulation by mitogens, that acts as a chemoattractant, and stimulates basophils and eosinophils.

ranunculeic acid *another name for* **columbinic acid**.

rapamycin an immunosuppressant (and antifungal agent) from *Streptomyces hygroscopicus*; it is used to reduce rejection of organ transplants. Unlike cyclosporin A it is antiangiogenic and thus anticancer. It is a lipid-soluble macrocyclic lactone, with the unusual feature of a cyclohexane ring. It competes with **FK506** for a common binding site on **FKBP**. Moreover, it inhibits the signalling pathway of interleukin 2 and certain other cytokines, and also **mTor**. *See also* **cyclosporin**.



RAPD PCR *abbr. for* random polymorphic DNA PCR; a variation of the **polymerase chain reaction** in which many short (≈10 nucleotide) primers are used. The products of the reaction from different sources can lead to recognition of polymorphisms and physical maps.

rape *or* **colza** a herbaceous plant, *Brassica napus*, of the mustard family, Cruciferae; it resembles a turnip, and the seeds yield valuable **rapeseed oil**.

rapeseed oil oil derived from the seed of **rape**; it is widely used as a lubricant and cooking fuel, and for the manufacture of animal foodstuffs, soap, and synthetic rubber. It contains **erucic acid**, which has cardiotoxic effects varying with species; rape varieties of low erucic acid content have recently been developed.

rapid-reaction kinetics the kinetic analysis of an enzyme reaction before the steady state is reached. The **stopped-flow method** is commonly used, in which two independent sources of substrate and enzyme are mixed immediately before flow through a spectrophotometer cell. An opposing syringe stops the flow immediately before activating the detection and recording system, such that reaction times of a few milliseconds can be achieved. Characteristically, reaction rates may be appreciably faster than during the steady state. In the **quenched flow** modification of the method, a further reagent is added to stop the reaction immediately before detection and recording. *See also* **relaxation kinetics**.

Rapoport–Lübering shunt a unique feature of erythrocyte glycolysis in which the glycolytic intermediate 3-phosphoglyceroyl phosphate is converted by bisphosphoglycerate mutase to 2,3-bisphosphoglycerate, which is in turn converted to 3-phosphoglycerate and inorganic phosphate by bisphosphoglycerate phosphatase, both reactions being catalysed by a single enzyme molecule. The shunt bypasses the near equilibrium phosphoglycerate kinase reaction, one of the two ATP-generating reactions of glycolysis. Since 2,3-bisphosphoglycerate is an important intracellular modulator of hemoglobin function, regulation of the Rapoport–Lübering shunt balances the energy needs and oxygen-transporting function of the red cell. [After Samuel Mitja Rapoport (1912–2004) and J. Lübering.]

RAR *abbr. for* retinoic acid receptor.

rare cutter any of a class of restriction endonucleases that cleave infrequently within human DNA and then mostly at sites that contain a CpG dinucleotide within the recognition sequence.

rare earth *(strictly)* an oxide of a **rare earth metal**, *or (more loosely)*, a rare earth metal itself.

rare earth metal *or* **rare earth element** scandium, yttrium, or a **lanthanoid**.

RAS an oncogene (v-*ras*) discovered in the retroviruses Harvey and Kirsten rat sarcoma viruses. There are three closely related (85% homology) oncogenes, Ha-*ras*, Ki-*ras*, and N-*ras*. Their cellular counterparts encode 21 kDa guanine nucleotide-binding proteins that regulate growth and differentiation in nearly every eukaryotic cell studied. There are two subfamilies, the Rho and Rac proteins (involved in relaying signals from the cell-surface receptors to the actin cytoskeleton) and the Rab family (involved in regulating the traffic of intracellular transport vesicles). Ras proteins undergo modification of the N and C termini that localize them to the plasma membrane. Ras is considered active in the GTP-bound form and inactive in the GDP-bound form. The intrinsic rate of nucleotide exchange and GTPase activity is very slow. Ras•GDP predominates in resting cells, but when Ras is activated by occupied receptors, specific guanine nucleotide exchange factors (GEFs), e.g. **Sos**, enhance nucleotide exchange leading to Ras•GTP, GTP exceeding GDP in cytoplasm. Ras•GTP then activates downstream effector proteins such as Raf-1 (*see* ***raf***). Activated GTPase activating protein (GAP) causes the formation of inactive Ras•GDP. The retroviral oncogene, v-*ras*, encodes a protein that differs from the c-*ras* product in a single residue. If this affects amino acids 12, 13, 59, 61, or 63 the protein fails to hydrolyse its bound GTP and so persists abnormally in its active state, constitutively transmitting an intracellular signal for cell proliferation. Alternatively, some transforming mutations increase the rate at which Ras can exchange guanine nucleotides, e.g. when amino acids 116, 117, 119, or 146 are affected, again increasing the amount of Ras•GTP. Activated *ras* oncogenes occur in up to 30% of all human tumours, with the most common mutations being at codons for amino acids 12 and 13. In some types of malignancy, the figure is nearly 100%. Two genes corresponding to H-*ras* occur in yeast; they encode **G-proteins** that inhibit **adenylate cyclase**.

rasiRNA *abbr. for* repeat-associated siRNA. Transcription from opposing promoters found in repetitive DNA elements leads to the formation of long dsRNAs. These are cleaved by **Dicer** into siRNAs which are unwound and used in the RNA-induced transcriptional silencing complex (RITS) which directs silencing of chromatin in the region from which the dsRNA was transcribed. Silencing is thought to involve methylation of lysine 9 of histone H3.

RasMol *see* **visualization software**.

RAST *abbr. for* radioallergosorbent test.

rate coefficient *see* **rate constant**.

rate constant *or* **rate coefficient** *symbol*: k; a constant relating the concentration of a reactive species to the velocity of a reaction; thus for a first order reaction (*see* **order of reaction**) such as: $EA \rightarrow E + A$, the rate of reaction, v, is proportional to the concentration of the reactant EA, so $v = k[EA]$, where k is the first-order rate constant. For a second order reaction, e.g. $E + A \rightarrow EA$, the rate is proportional to the product of the reactant concentrations, i.e. $v = k[E][A]$, where k is the **second-order rate constant**.

rate-determining step *see* **rate-limiting step**.

rate-limiting step the slowest step in a reaction sequence; i.e. the step with the smallest rate constant.

rate of consumption *see* **rate of reaction**.

rate of conversion *symbol*: $\dot{\xi}$; for a specified chemical reaction, the rate of increase of the extent of reaction at any moment in time, regardless of the conditions under which the reaction is carried out: $\dot{\xi} = d\xi/dt$, where ξ is the extent of reaction and t is time. In the case of a reaction with one-to-one stoichiometry, such as a typical simple enzyme-catalysed reaction, the extent of reaction is equal to the amount of a reactant consumed or the amount of a product formed. Rate of conversion is an extensive quantity (*see* **extensive property**), its dimensions are (amount of substance) divided by time, and it is expressed in mol s^{-1} (*compare* **rate of reaction**). It is therefore independent of the volume of the system. Where this volume remains constant, as during a typical enzyme-catalysed reaction, the rate of conversion is equal to the rate of reaction multiplied by the volume: $\dot{\xi} = vV$. The term was formerly known in physical chemistry as rate of reaction. *See also* **catalytic activity**.

rate of formation *see* **rate of reaction**.

rate of reaction *or* **velocity of reaction** *or (sometimes)* **reaction rate** **1** *symbol*: v; for a specified enzyme-catalysed reaction of a typical kind (i.e. one involving a single substrate, S, a single product, P, one-to-one stoichiometry between them, and constant-volume conditions), the **rate of consumption** of substrate or the **rate of formation** of product at any moment in time is given by:

$$v = -\mathrm{d}[S]/\mathrm{d}t = \mathrm{d}[P]/\mathrm{d}t,$$

where [S] and [P] are respectively the concentrations of substrate and product, and t is time. A similar set of relationships applies where there are several reactants in one-to-one stoichiometry, but if the overall stoichiometry is not one-to-one – a situation rarely arising in enzyme kinetics – the relationships are more complicated. Where intermediates are formed in amounts comparable to those of the reactants, there is time-dependent stoichiometry and a rate of reaction for the complete reaction cannot be specified. Rate of reaction is an intensive quantity (*see* **intensive property**), its dimensions are (amount-of-substance concentration) divided by time, and it is expressed in mol L^{-1} s^{-1} (*compare* **rate of conversion**). *See also* **initial velocity**, **limiting rate**. **2** *(formerly, in physical chemistry)* the extensive quantity now termed **rate of conversion**.

rate theory of agonist action a theory of agonist action stating that the response to an agonist is proportional to the number of receptor–agonist associations per unit time, i.e. to the rate of receptor occupation, the binding of agonist to receptor being reversible. The response is therefore maximal at time zero and falls exponentially to an equilibrium value.

rational drug design the design of drug molecules based on the 3D structure of the target molecule. Owing to its complexity, the approach has had only limited success, but it has worked for some targets where the molecular mechanism of activation or inactivation is well understood (e.g. some enzymes), or where structural modifications are readily engineered (e.g. antibodies).

raw sequence *(in bioinformatics)* in the early stages of the sequencing process, sequence reads that are unassembled and carry no annotation.

Rayleigh ratio *symbol*: R; the ratio of the intensity of light scattered by particles (molecules) in solution at an angle θ from the incident beam, I_θ, multiplied by the square of the distance, r, from the particle to the detector, divided by the intensity of the incident light, I_o, i.e. $R = I_\theta r^2/I_o$. The **reduced Rayleigh ratio**, $R_\theta = I_\theta r^2/I_o(1 + \cos^2\theta)$. Many literature references do not distinguished between these two. *See also* **Rayleigh scattering**. [After John William Strutt, Lord Rayleigh (1842–1919), British mathematician and physicist.]

Rayleigh scattering the elastic scattering of photons of light by molecules or atoms of the substance through which the light is passing. When light passes through a liquid or gas, atoms or molecules are polarized by the electric vector of the light, thus inducing a rapidly fluctuating dipole in the atoms or molecules in the light path. The fluctuating dipole leads to the emission of electromagnetic waves in various directions of the same frequency as the incident radiation, and this emission is seen as scattered light. *See also* **Rayleigh ratio**.

Rb *symbol for* rubidium.

RB a human **tumour suppressor gene** that encodes a nuclear phosphoprotein, **retinoblastoma protein**. Inactivation or loss of *RB* on both copies of the chromosome (13q14) leads to **retinoblastoma**.

R band *see* **Giemsa's stain**.

RbAp *abbr. for* retinoblastoma-associated protein. *See* **Sin 3-HDAC**.

rBAT *abbr. for* related to basic amino acid transporter. *See* **cystinuria**.

RBC *or* **rbc** *or* **r.b.c.** *abbr. for* red blood cell. *See* **erythrocyte**.

Rbe *abbr. for* relative biological effectiveness (i.e. **quality factor**).

R-binder *an alternative name for* **haptocorrin**.

RBS *abbr. for* Réné Borghgraef solution; *the proprietary name for* any of a range of general-purpose surfactants and decontaminating agents, especially for laboratory use, that have combined detergent and chelating properties. They are identified with a number or other designation, e.g. RBS 25, RBS 35, RBS solid.

RCC1 a chromatin-bound guanine nucleotide release (or exchange) factor. Its function is required for the normal coupling of the completion of DNA synthesis and the initiation of mitosis. It is also necessary for RNA export from the nucleus, spindle formation, and formation of the nuclear envelope during cell division. It binds to and acts on the nuclear G-protein, **Ran**. [From regulator of chromosome condensation.]

RCF *abbr. for* relative centrifugal force.

R chromophore a **chromophore** that gives rise to low-intensity absorption bands at long wavelengths. *Compare* **K chromophore**. [From German *Radikal*.]

RCP *abbr. for* radiochemical purity.

RCS *abbr. for* rabbit aorta-contracting substance.

RCSB *abbr. for* Research Collaboratory for Structural Bioinformatics; *see* **structure database**.

rd *symbol for* rad (def. 2) (alternative to rad).

Rd *abbr. for* rubredoxin.

RDBMS *abbr. for* relational database management system.

rDNA **1** *abbr. for* ribosomal DNA. **2** *(sometimes) abbr. for* recombinant DNA; use not recommended because of possible confusion with ribosomal DNA.

re- *prefix (in chemical nomenclature)* denoting *rectus* (i.e. right, or clockwise) configuration of a face of a trigonal atom. *See* ***re/si*** **convention**.

Re *symbol for* rhenium.

Re *symbol for* Reynolds number.

RE *abbr. for* (eukaryotic) response element.

reactancy of enzymes the number of reactants involved in an enzyme-catalysed reaction in a given direction. The numbers of kinetically important substrates or products in an enzyme mechanism are designated by Uni (1), Bi (2), Ter (3), or Quad (4). Thus, e.g., UniUni indicates one substrate and one product, and Ter Bi indicates three substrates and two products.

reactant any material participating in a chemical reaction in a given direction.

reaction *(in chemistry)* any process in which molecules interact with one another, leading to chemical or physical change.

reaction centre *see* **photosystem**. *Compare* **photosynthetic reaction centre**.

reaction intermediate a transient chemical species, with a lifetime appreciably longer than a molecular vibration time, formed directly or indirectly from the reactants of a chemical (often enzymic) reaction, and that further reacts (directly or indirectly) to give the reaction products.

reaction rate *(sometimes) an alternative term for* **rate of reaction**.

reaction time *an alternative name for* **latent period** (def. 1).

reactivate to restore activity to any enzymic or cellular system.

reactive describing any molecular entity or centre that is capable of reacting readily. Thus, a **reactive centre** is the point in the molecule at which electron configurations favour a reaction.

reactive oxygen species *abbr.*: ROS; a highly active oxygen species, such as **superoxide** ion, hydroxyl radical, hydrogen peroxide (H_2O_2), or peroxynitrite. Most ROS are generated as toxic by-products of oxidative phosphorylation in mitochondria. H_2O_2 is also produced by various reactions in peroxisomes, and by phagocyte NADPH oxidase, thyroperoxidase, and xanthine oxidase in specific cell types. Cells protect themselves through the superoxide dismutase, glutathione peroxidase, and catalase activities, and the antioxidants (e.g. glutathione, carotene) they contain. Chronic exposure to ROS causes oxidative damage to mitochondrial and cellular proteins, lipids, and nucleic acids. *See* **oxidative stress**.

reactivity the degree to which a molecule or centre is reactive.

reading *(in molecular biology)* the process of one-way linear decoding of a nucleotide sequence during, e.g., **transcription** or **translation**.

reading frame any sequence of bases in DNA that codes for the synthesis of either a protein or a component polypeptide. The point of initiation of reading determines the frame, i.e. the way in which the bases will be grouped in triplets as required by the genetic code. For example, the sequence

–ATGGTCA–

could be grouped

–A,TGG,TCA–

or

–AT,GGT,CA–

or

–ATG,GTC,A–

depending on the point at which the reading frame begins. In double-stranded DNA there six potential reading frames. *See also* **open reading frame**.

readthrough the continuation of DNA transcription beyond a normal termination sequence, due to a failure of RNA polymerase to recognize the termination signal. Readthrough may also occur in translation, where a mutation has caused a termination codon to be converted to a codon for an amino acid (a sense codon); this is the underlying etiology of several **hemoglobinopathies**. *See also* **readthrough protein**.

readthrough protein a product formed by translation of a messenger RNA when one of its termination codons is misread, or is recognized by a **suppressor tRNA**. Polypeptide-chain synthesis then continues until the next termination codon is reached, resulting in the production of a variant protein with a C-terminal extension.

reagent **1** any chemical substance that reacts or participates in or is necessary for a reaction. **2** a substance used for the detection or determination of another substance by chemical or microscopical means, usually in solution; e.g. the **Folin–Ciocalteu reagent**.

reagent grade a level of purity of a chemical; chemicals of this quality conform to the specifications established by the Committee on Analytical Reagents of the American Chemical Society and may often be sufficiently pure to use as primary standards in an analytical laboratory, with information concerning the actual percentage of impurities or at least the maximum limit of impurities being given on the label.

reagin **1** a heat-labile antibody-like substance in the serum of many people suffering from atopic allergies, and identical with immunoglobulin E (IgE). The **immediate hypersensitivity** (type I) generated by the binding of IgE to its specific antigen on the surface of mast cells involves the release of cell mediators via the reaginic or anaphylactic mechanism. **2** a special kind of antibody response produced by syphilitics that has specificity for **cardiolipin** antigens.

real-time *(in computing)* indicating that a computer monitors a process continuously as it occurs, in distinction to the analysis of recorded data.

real-time PCR a variant of the **polymerase chain reaction** (PCR) in which the quantity of amplified DNA is recorded in each cycle by monitoring the fluorescence intensity of a DNA-binding dye such as **SYBR Green**. An advantage is that the kinetics of the reaction can be monitored and, with reference to the behaviour of standards, the amount of PCR product quantified. The abbreviation RT-PCR for real-time PCR is to be deprecated. Real-time PCR is frequently used for quantitation of reverse transcriptase PCR in which case real-time RT-PCR is the appropriate terminology. *See* **RT-PCR**.

rearrangase *or* **S–S rearrangase** *an alternative name for* **protein disulfide isomerase**.

rearrangement reaction a reaction in which molecular bonds are rearranged without the loss of any atom from the molecule, e.g. as in the conversion of glucose 6-phosphate to fructose 6-phosphate.

recA a gene in *Escherichia coli* encoding a protein, RecA, involved in **genetic recombination** and in the SOS response for DNA repair (*see*

SOS repair). The protein has two activities: (1) a DNA-dependent ATPase in the presence of single-stranded DNA that catalyses the ATP-dependent uptake of single-stranded DNA to form the heteroduplex required in recombination. (2) In the presence of DNA fragments it becomes a protease (RecA*; EC 3.4.99.37) that cleaves a specific Ala-|-Gly bond in certain repressor molecules, including its own repressor (*see* ***lexA***). This allows all the SOS genes to be activated. *See also* **exodeoxyribonuclease V**, **recombinational repair**, **recombinase**.

recalcitrance *or* **persistence** the ability of a substance to remain in a particular environment in an unchanged form.

recall *or* **sensitivity** (*in informatics*) the proportion of the true members of a set that are correctly identified by a prediction algorithm: true positives/(true positives + false negatives).

recBC a gene in *Escherichia coli* for **exodeoxynuclease V**, an ATP-dependent nuclease specific for double-stranded DNA; it mediates **genetic recombination**.

recDNA *(sometimes) abbr. for* recombinant DNA.

receiver operating characteristic *or* **receiver operator characteristic** *abbr*.: ROC; (*in signal detection theory*) a graphical representation of the relationship between true and false hits for a binary classifier system as its discrimination threshold is varied. ROC curves are used, for example, in bioinformatics to evaluate prediction algorithms: results in the top left of the plot denote 100% sensitivity (all true positives found) and 100% specificity (no false positives found); completely random results lie on a straight line at 45° from the origin, indicating that, as the threshold is raised, equal numbers of true and false positives are matched.

receptor any cellular macromolecule that binds a hormone, neurotransmitter, drug, other agonist, or intracellular messenger to initiate a change in cell function. Receptors are concerned directly and specifically in chemical signalling between and within cells. Cell-surface receptors, e.g. the **acetylcholine receptor** and the **insulin receptor**, are located in the plasma membrane, with their ligand-binding site exposed to the external medium. Receptors may also be present in membranes of the sarcoplasmic reticulum (e.g. ryanodine receptor), T tubule (e.g. dihydropyridine receptor), or endoplasmic reticulum (e.g. inositol trisphosphate, or IP_3 receptor). Intracellular receptors (e.g. steroid-hormone receptors) bind ligands that enter the cell across the plasma membrane. These can be located in the cytosol or nucleus. Receptors can be catalytic, enzyme-associated, or G-protein-associated.

receptor activator of NF-κB *see* **RANK**.

receptor activity modifying protein *abbr*.: RAMP; a single-transmembrane-domain protein required for expression of calcitonin gene-related peptide or adrenomedullin receptor phenotypes from the calcitonin receptor-like receptor gene (CRLR). For full activity, CRLR forms heteromers with RAMP and receptor component protein.

receptor assay 1 the determination of receptor numbers and the dissociation constant of receptor–ligand binding. The binding at various concentrations of ligand is measured, often by use of a radioactive ligand, and is analysed by means of a **Scatchard plot**. **2** the determination of the concentration of a ligand by utilizing a purified receptor in a manner similar to that used in **radioimmunoassay**; in this case the receptor, rather than an antibody, performs the role of specific binding agent.

receptor cross-talk interaction between two receptors such that one receptor, when activated, modulates the action of the other. This type of interaction often involves the production by the first receptor of a **second messenger**, which then modulates the action of the second receptor.

receptor-destroying enzyme an enzyme that brings about chemical change in a (usually membrane-bound) receptor, leading to inactivation of the receptor. Knowledge of the specificity of the enzyme provides information about the nature of the groups or linkages exposed to enzyme attack, and thus to receptor structure or orientation in the membrane. Examples are **sialidase** and **trypsin**.

receptor–effector complex the complex that results when an occupied receptor binds to another protein (the **effector**), the activation of which by the occupied receptor leads to signal transduction.

receptor-mediated describing a response that requires the intermediary action of a receptor, especially one located in a membrane.

receptor-mediated endocytosis a form of **endocytosis** involving the internalization (i.e. passage into the cell interior) of stretches of membrane into which receptors have clustered after binding of ligand. The cytoplasmic surfaces of these stretches of membrane are coated with **clathrin** and are termed **coated pits**. *See also* **endosome**.

receptor transformation *see* **transformation** (def. 3).

recessive describing an **allele** that lacks effect when accompanied in the same diploid by a **dominant** form of the same gene. Most (not all) defective mutant genes are recessive to their normal functional counterparts. **—recessivity** *n.*

RecET a **recombinase** from the Rac prophage of *E. coli* consisting of *recE*-encoded exonuclease VIII and the RecT protein. Together they catalyse recombination between linear duplex DNA and homologous circular single-stranded DNA. RecET is used for **recombineering**.

RecG an *E. coli* helicase involved in DNA recombination, acting with RuvC to resolve **Holliday junctions**.

recipient bacterium *see* **bacterial conjugation**.

reciprocal 1 expressed in the reverse direction, in response to an initial application of any force or stimulus. **2** *(in mathematics)* the inverse value, obtained when the values of numerator and denominator are reversed; the reciprocal of x is obtained by evaluating $1/x$.

reciprocal plot a plot in which the units of both the ordinate and the abscissa are reciprocals of the values that have been determined. *Compare* **Lineweaver–Burk plot**.

reciprocal translocation a chromosomal rearrangement in which the ends of, usually, two nonhomologous chromosomes are exchanged. If the reciprocal translocation is balanced there is no loss or gain of genetic material after the exchange.

recircularization *or* **recircularisation** the restoration of circularity to a plasmid vector following the insertion of recombinant DNA. The plasmid used for gene cloning is a small circular molecule. This is cut with a **restriction endonuclease** to create linear DNA molecules. The foreign DNA fragment with the same cohesive ends is then annealed to the cut plasmid to form a recombinant DNA circle. The DNA molecule containing the foreign DNA insert is then covalently sealed with **DNA ligase**. Recircularization also occurs during the replication of some DNA phages by a **rolling circle** replication mechanism.

recognition any specific binding interaction between molecules. Such interaction between two molecules is based on the existence of **recognition sites**, one (or more) on each of the interacting molecules, that are tailored to fit in such a way that highly specific binding occurs; i.e. the two molecules uniquely ‘recognize’ each other. *See also* **chiral recognition**, **molecular recognition**.

recognition sequence the part of the sequence of a macromolecule that is able to recognize and bind to a particular sequence in another macromolecule.

recognition site 1 *(in proteins)* a site for **recognition** of another protein, involving a specific sequence of amino acids; the latter may be in a single chain (e.g., a target site for protein phosphorylation), or may involve amino acids in separate chains brought into juxtaposition by quaternary structure. **2** *(in nucleic acids)* a site for recognition of a protein, involving a specific sequence of bases; *see* **restriction endonuclease**. **3** *(in pharmacology)* a region of a receptor macromolecule to which an endogenous agonist binds.

recombinant clone a population of bacteria or other host derived from a single cell into which a vector containing **recombinant DNA** has been introduced.

recombinant DNA a fragment of deoxyribonucleic acid (DNA) that has been inserted into a cloning vector, thereby leading to its use in the isolation of a clone of cells characterized by the presence of the fragment. The term is derived from the concept that insertion into the vector is a form of **genetic recombination**. [*Note*: The abbreviation rDNA has sometimes been applied to recombinant DNA, but this use is discouraged (rDNA having been pre-empted for ribosomal DNA); while alternatives such as recDNA or rtDNA have been suggested, IUBMB considers a standard abbreviation unnecessary.] *See also* **recombinant DNA technology**.

recombinant DNA technology an area of biotechnology concerned with the manipulation of **recombinant DNA**. It has many important applications, including (1) DNA sequencing, which may lead to the ability to predict the primary structure of a protein where this is the product of a cloned gene, (2) the synthesis of recombinant protein by a suitable expression system, and (3) the production of DNA **probes** (def. 3) for use in hybridization techniques. The technology has led, e.g., to the production of human insulin for the treatment of diabetics, human growth hormone for administration to children with growth defects, and a vaccine for hepatitis B. DNA probes are essential for the detection of aberrant genes which are the cause of numerous diseases and the technique has the potential for gene therapy. *See also* **genetic engineering**.

recombinant protein a protein encoded by a gene – **recombinant DNA** – that has been cloned in a system that supports expression of the gene and translation of messenger RNA (*see* **expression system**). Modification of the gene by recombinant DNA technology can lead to expression of a mutant protein. Proteins coexpressed in bacteria will not possess post-translational modifications, e.g. phosphorylation or glycosylation; eukaryotic expression systems are needed for this (see, e.g., **baculovirus**).

recombinase 1 an enzyme that recognizes specific sites involved in the joining of V-region gene segments in L- and H-chain gene segment pools in the generation of antibody. **2** RecA protein (*see* ***recA***) is also a recombinase, the activity of which is increased in *Escherichia coli* following damage to DNA. RecA binds to a region of single-stranded DNA and catalyses the formation of duplex DNA; hydrolysis of ATP is involved. A recombinase recognizes and binds to each of two recombinant sites on different DNA molecules or within the same DNA. One DNA strand in each site is cleaved at a specific point within the site, and the recombinase becomes covalently linked to the DNA at the cleavage site through a phosphotyrosine (sometimes a phosphoserine) bond. The transient protein–DNA linkage preserves the phosphodiester bond lost in cleaving the DNA; cofactors such as ATP are unnecessary in subsequent steps. The cleaved DNA strands are rejoined to new partners, with new phosphodiester bonds created at the expense of the protein–DNA linkage. The result of the initial breakage and rejoining process is the **Holliday junction**. To complete the reaction, the process must be repeated at a second point within each of the two recombination sites. In summary the recombinase can be viewed as a site-specific endonuclease and ligase in one package.

recombination *see* **genetic recombination**, **recombinant DNA**, **immunoglobulin synthesis**.

recombination activating gene *see* RAG.

recombinational heteroduplex *see* **heteroduplex**.

recombinational repair a mechanism to restore the integrity of DNA when replication of DNA stops at a **thymine dimer** but resumes after the dimer is passed, creating a gap. The undamaged parental strand recombines into the gap, a process promoted by RecA protein (*see* ***recA***). The new gap in the parental strand is filled by the action of **DNA polymerase** and **DNA ligase**. The thymine dimer itself is not repaired in this process but time is allowed for the excision system to repair this damage later.

recombineering *or* **recombination-mediated genetic engineering** a method for manipulating large DNA molecules such as **BAC**s by promoting homologous recombination with linear DNA (such as products of the polymerase chain reaction). *E. coli* strains carrying recombinases such as **RecET** or bacteriophage lambda Red functions are used (*see* **Red recombination system**).

recoverin an **EF-hand** Ca^{2+}-binding protein, apparent molecular mass 26 kDa; *also known as* **cancer-associated retinopathy protein**. It selectively localizes to the retina and pineal gland, and is implicated in the activation of retinal rod guanylate cyclase by rhodopsin, possibly being involved in the blocking of the phosphorylation of rhodopsin, by forming an inhibitory complex with rhodopsin kinase. It has been identified as an autoantigen in cancer-associated retinopathy, a putative autoimmune process.

recovery the portion of material or activity that remains after any extraction or purification, usually expressed as a percentage of the amount that was present as starting material.

RecQ-like protein 2 *an alternative name for* **BLM protein**.

recruitment the action by any cell, cell constituent, or molecule that brings about the cooperation of any other component in performance of any function.

recrystallize *or* **recrystallise** to dissolve a crystalline substance and subsequently crystallize it from the solution, usually to increase the purity of the substance. —**recrystallization** *or* **recrystallisation** *n.*

rectangular hyperbola a **hyperbola** whose asymptotes are at right angles. It is sometimes said that, for enzymes that follow so-called **Michaelis kinetics**, the plot of initial rate against substrate concentration has the shape of the curve of a rectangular hyperbola. It is true that the Michaelis–Menten equation does yield a curve that is part of a rectangular hyperbola, but the axes of the hyperbola must be rotated through 45°, and displaced, if they are to coincide with the axes of the Michaelis–Menten plot.

rectification 1 *(in physics)* the process of obtaining a direct current from an alternating electrical supply. **2** *(in physiology)* the regulation of membrane conductance by the voltage across the membrane; strong rectification implies that ionic channels carrying current are open at some membrane potentials and shut at others. Conductance is low at very negative membrane potentials, but increases as the potential becomes less negative. **3** *(in chemistry)* the process of purifying a liquid by distillation.

rectus *Latin* right; used to describe the right, or clockwise, configuration of one of the two faces of a compound containing a trigonal carbon atom. It is designated by the prefix *re*-. *Compare* ***sinister***. *See also* ***re/si*** **convention**.

recycle to pass again through a system one or more times after return to a starting condition or state.

RED *abbr. for* RNA-dependent deaminase. *See* **RNA editing enzyme**.

red drop a phenomenon in photosynthesis, in which the **quantum yield** is relatively constant in light of wavelengths between 500 and 600 nm, but drops dramatically at longer wavelengths.

redistil *or (US)* **redistill** to distil again that which has already been distilled, usually as an aid to purification of liquids.

red marrow *see* **bone marrow**.

red muscle dark, skeletal, voluntary muscle that is relatively rich in myoglobin and cytochromes, and derives energy for contraction from a high oxidative capacity, in contrast to **white muscle**, which has a high glycolytic capacity. The distinction between muscle types should more strictly be based on muscle-fibre types. Type I fibres have a high oxidative capacity based on a high activity of tricarboxylic-acid cycle and respiratory chain enzymes. Type IIA fibres have high oxidative and high glycolytic capacity. Type IIB fibres have low oxidative and high glycolytic capacity. The proportions of these fibres vary in different muscle types, and can be changed by training in athletes.

redox *abbr. for* reduction–oxidation; *see* **oxidation–reduction**.

redox balance the ratio of the number of reductions to the number of oxidations in a given metabolic pathway. *Compare* **redox state**.

redox couple the oxidized (electron acceptor) and the reduced (electron donor) forms of the species of a given **redox reaction**; e.g. NAD$^+$ and (NADH + H$^+$). The potential of any redox couple in solution can be measured against a reference electrode, and a table of relative potentials constructed. *See* **redox potential**.

redox hypothesis a now discounted model for the **Pasteur effect** in glycolysing muscle extracts. Addition of redox indicators that changed the redox state in the direction of oxidation decreased the rate of lactate formation; it was therefore suggested that the effect of oxygen might be connected with a change of the redox state in the same direction.

redox indicator *see* **indicator** (def. 3).

redox potential *or* **oxidation–reduction potential** *symbol*: E_o; for a particular **redox couple** at a given pH and temperature, the potential of an electrode (usually bright platinum) immersed in a solution containing 1 M oxidant and 1 M reductant, relative to a standard **hydrogen electrode**. The more 'reducing' the couple, the more negative is E_o; the convention in biochemistry is that the more 'oxidizing', the more positive is E_o. Some standard potentials, measured against the hydrogen electrode at pH 7, are: NAD$^+$/NADH + H$^+$, –0.32 V; fumarate/succinate, +0.032 V; cytochrome *c*(Fe^{3+})/cytochrome *c*(Fe^{2+}), +0.25 V; O$_2$ + 2H$^+$/H$_2$, +0.82 V.

redox reaction a chemical reaction in which the oxidation of one reactant is coupled to the reduction of a second reactant, electrons being transferred from the reactant being oxidized to that being reduced.

redox state the ratio of the concentration of the oxidized member of a **redox couple** to the concentration of the reduced member; e.g. [NAD^+]/[NADH] or [Fe^{3+}]/[Fe^{2+}]. The term should only be applied to a particular redox system and not to a heterogeneous system.

Red recombination system a bacteriophage lambda-encoded recombination system. Full recombination potential requires the products of three genes: *exo*, *bet,* and *gam*. *See* **recombineering**.

red shift any shift of the peaks of a spectrum to longer wavelengths (i.e. towards the red end of the spectrum), including a shift from the red to infrared. *Compare* **blue shift**.

red tide a bloom of the dinoflagellate *Ptychodicus brevis* (*Gymnopodium breve*), an organism that produces **brevetoxins** and causes epidemics of food poisoning.

reduce to cause or undergo **reduction**.

reduced folate carrier *abbr*.: RFC; any of several homologous membrane-associated glycoproteins that bind reduced folates and methotrexate with low affinity. The gene at 21q22.2 has multiple promoters and produces several isoforms, including the putative intestinal folate transporter.

reduced Rayleigh ratio *see* **Rayleigh ratio**.

reducing agent any substance acting as a **reductant**. *Compare* **oxidizing agent**.

reducing end the end of an oligo- or polysaccharide molecule that carries a potential hemiacetal or hemiketal (reducing) group.

reducing sugar any **sugar** that will reduce heated alkaline solutions of cupric salts, such as **Fehling's** or **Benedict's solutions**, due to the presence of a hemiacetal or hemiketal group.

reductant the chemical species that donates an electron in an **oxidation–reduction reaction**; i.e. the species that undergoes **oxidation** in such a reaction. *Compare* **oxidant**.

reductase a donor:acceptor oxidoreductase enzyme (EC class 1) when named after the more oxidized alternative substrate and when O_2 is not a substrate. *See* **oxidoreductase**.

reduction the chemical process by which oxygen is withdrawn from, hydrogen is added to, or (more generally) an electron is added to (with or without addition of a proton) a molecular entity. *Compare* **oxidation**. —**reductive** *adj.*; **reduce** *vb.*

reduction division the first division of **meiosis**.

reduction potential the electrode potential that measures the tendency of one half of a **redox reaction** to proceed so as to gain electrons. *See* **oxidation potential**, **redox potential**.

reductive alkylation the reaction of amino groups with an alkyl carbonyl group, followed by reduction of the resulting **Schiff base** with a reducing agent such as sodium borohydride. *See* **reductive amination**.

reductive amination the process whereby ammonia or a primary or secondary amine reacts with ketones and aldehydes in the presence of reducing agents such as H_2 and a metal catalyst, or more conveniently, $NaBH_4$ or its derivative $NaBH_3CN$, to produce primary, secondary, or tertiary amines. In a formal sense, the amine is alkylated in this reaction while the carbonyl group is reduced, hence the term reductive amination, or alternatively **reductive alkylation**. Amino acids have been made from oxo acids by this process. A variation of reductive amination, termed the **Eschweiler–Clarke reaction**, involves the methylation of an amine to the tertiary amine stage using formic acid as the reducing agent and formaldehyde as the methylating reagent.

reductive carboxylic-acid cycle *or* **reductive tricarboxylic-acid cycle** a metabolic cycle used by members of the Chlorobiaceae for CO_2 fixation. The usual operation of the tricarboxylic-acid cycle is reversed, with three enzyme replacements, and other supplementary reactions are used. Initially one CO_2 reacts with succinyl-CoA to form oxoglutarate; oxoglutarate synthase (EC 1.2.7.3) replaces the usual **oxoglutarate dehydrogenase complex**. A second CO_2 converts oxoglutarate to isocitrate with use of **isocitrate dehydrogenase**, and isocitrate proceeds to citrate. Citrate is then cleaved by ATP citrate *(pro-S)* lyase to acetyl-CoA and oxaloacetate; the latter recycles to succinyl-CoA with fumarate reductase (NADH) replacing succinate dehydrogenase. These operations convert two CO_2 to acetyl-CoA. A net gain of oxaloacetate is possible by conversion of acetyl CoA and one CO_2 to pyruvate (pyruvate synthase), pyruvate to phospho*enol*pyruvate (phospho*enol*pyruvate synthase) and **phospho*enol*pyruvate** and one CO_2 to oxaloacetate (**phospho*enol*pyruvate carboxylase**). The overall result is that four CO_2 yield a net gain of the four-carbon oxaloacetate.

reductive methylation a specific form of **reductive alkylation**, in which the alkyl group is methyl. Formaldehyde is often used as a reagent in this case.

reductive pentose-phosphate cycle *or* **Calvin cycle** *other names*: carbon reduction cycle; C_3 cycle/pathway; more appropriately, Calvin–Bassham cycle; the cyclic set of reactions, occurring in chloroplasts in the majority of higher plants (**C_3 plants**), that results in the fixation of CO_2 as glucose using the ATP and the NADPH formed in the light reactions of photosynthesis. Briefly, CO_2 reacts with ribulose 1,5-bisphosphate under the action of **ribulose-bisphosphate carboxylase** (Rubisco), EC 4.1.1.39, to form two molecules of 3-phosphoglycerate; these are phosphorylated (by ATP) to 1,3-bisphosphoglycerate, which in turn is reduced (by NADPH) to glyceraldehyde 3-phosphate. This is then converted by aldolase, transketolase, and other enzymes to fructose 6-phosphate and ribulose 5-phosphate; the latter being phosphorylated (ATP) to ribulose 1,5-biphosphate, completing the cycle. *See also* **Hatch– Slack pathway**.

reductone any reducing substance with a chemical structure containing the stabilized enediol –C(OH)=C(OH)–. Reductones are generated when monosaccharides are heated for prolonged periods with strong alkali, whereby the enols originally produced are broken down to strongly reducing fragments. Another notable example is ascorbic acid, and in some contexts reductones are described as '**apparent ascorbate**', i.e. the reductive acids that are present in certain processed foods and react similarly to ascorbate, interfering with its determination.

reelin a large extracellular matrix protein encoded by the gene that, when defective in mouse, produces the neurological mutant called reeler. It is a serine protease that degrades fibronectin, laminin, and collagen, and is secreted by the earliest neurons during development. It binds receptors (e.g. for ApoE and for very low-density lipoproteins) on adjacent neurons to govern the overall patterning of cortical neurons into layers and to control neuronal migration.

re-entrant loop a segment of a membrane protein that loops between two neighbouring transmembrane helices and is partly outside and partly inside the membrane. It may be extracellular or intracellular.

Re-face (of an atom or molecule) *see* ***Re*/*Si* convention**.

reference something that acts as a standard in relation to quality, quantity, or type against which other values or characteristics can be compared; e.g. reference spectrum.

reference electrode any electrode, selected by convention, against which the electronegativity of compounds is measured. The standard biochemical reference is the **hydrogen electrode**, normally a platinum electrode in hydrochloric acid through which hydrogen gas is passed. A cell is constructed such that another electrode is immersed in a test solution and the potential difference between these two half-cells is measured. For convenience, however, the reference electrode is often a **calomel electrode**, and after measurements have been made against this, the electronegativity against the hydrogen electrode can be calculated from the known difference between this and the hydrogen electrode.

reflect to change the path of electromagnetic radiation, when it meets a surface, such that it returns partially or completely in a direction on the same side of the surface as the source.

reflectometer *see* **densitometer** (def. 1).

reflex *(in physiology)* an automatic or involuntary response of the nervous system to a stimulus. A reflex may be a monosynaptic spinal reflex (e.g. a simple motor response to a sensory stimulus), involving transmission through the spinal cord only, or polysynaptic and involving synaptic transmission in the brain. A **conditioned reflex** is one that is learned through repeated association of a stimulus with either rewarding (e.g. food) or aversive (e.g. punishment) events.

refolding (*for proteins*) the restoration of 3-D structure in a manner that may or may not achieve a full return to the native state following **denaturation**.

refraction the change in direction undergone by a wave of electromagnetic radiation on passing through a boundary between two media in which its velocity differs. **Snell's law** states that $n_1\sin\theta_1 = n_2\sin\theta_2$, where n_1 and n_2 are the **refractive indices** of the two media, and θ_1 and θ_2 are the angles between the radiation and the normal to the boundary in the corresponding media. [After Willebrord Snell (1591–1696), Dutch astronomer and mathematician.]

refractive index *abbr*.: RI; *symbol*: *n*; for a given medium, a measure of the degree of **refraction** induced by the medium when light or other electromagnetic radiation passes through it. The refractive index of a medium is the ratio of the speed of light in a vacuum, c_0, to the speed of light in the medium, *c*; i.e. $n = c_0/c$. For many practical purposes the speed of light in air may be used instead of that in a vacuum.

refractivity a measure of the extent to which a medium will cause the deviation of a ray of light or other electromagnetic radiation entering its surface. If the **refractive index** of a medium is *n*, its refractivity is $(n - 1)$. The **specific refractivity** is given by $(n - 1)/\rho$, where ρ is the density of the medium. The **molecular refractivity** is the specific refractivity multiplied by the relative molecular mass.

refractometer an instrument for measuring **refractive index**.

refractory **1** (of a clinical condition) resistant to treatment. **2** (of a cell or tissue) resistant to stimulation, as by a drug, hormone, or nerve impulse, especially during a period following previous stimulation. *See also* **tachyphylaxis**. **3** (of a substance or material) resistant to heat, corrosion, mechanical deformation, or other aggressive agents causing alteration. **4** a substance or material having such resistance.

Refsum's disease (classical) *or* **Refsum's disease (adult)** *other name*: phytanic acid storage disease; a rare autosomal recessive inherited disease starting in adulthood with neurological symptoms, including retinitis pigmentosa, peripheral neuropathy, cerebellar ataxia, and nerve deafness. It is caused by several mutations that lead to deficiency of peroxisomal phytanoyl-CoA hydroxylase, with consequent accumulation of phytanic acid in tissues and serum of patients. The symptoms are reduced by restriction of dietary dairy products and meat from ruminants, which contain phytanic acid. Infantile Refsum's disease is a form of **Zellweger syndrome** and results from mutations in the PEX1, 2, 5, or 12 genes. *See* **alpha oxidation**.

Regan isozyme *or* **Regan isoenzyme** *other name*: carcino-placental alkaline phosphatase; an isoenzyme of alkaline phosphatase that is occasionally present in the plasma of patients with malignant tumours.

regeneration **1** *(in chemistry)* the process of restoring to a state of preparedness for use, as in the case of an ion-exchange resin washed with acid or alkali to restore it to the H$^+$ or OH$^-$ form. **2** *(in biology)* the growth of new tissues or organs to replace ones lost or damaged, e.g. through injury or surgery. In some tissues, such as liver, epithelial tissue, or pancreas, regeneration occurs by simple duplication of cells, with the **regeneration time** varying from one week to a year. In other systems, such as epidermis, renewal is from specialized **stem cells**. Regenerating liver can be used as a model in which systems involved in proliferation are more highly activated than in normal liver. It is a unique property of liver that it is possible to remove two thirds of the organ yet it regenerates to form an organ of similar total weight to the original, albeit with somewhat different organization of the lobes. Many plants can regenerate a complete plant from a shoot segment or a single leaf or from tissue culture cells.

regeneration time the time taken for a tissue or organ to regain its former size or weight following damage or removal. For example, if two-thirds of the liver of a rat is removed surgically the liver regains its former weight in about two weeks. The proliferation of cells can be measured by the use of [^{3}H]thymidine to label the cells synthesizing DNA.

regex *abbr. for* regular expression.

regio+ *comb. form* denoting, or relating to, an area or site.

regioselective pertaining to a chemical change that occurs with greater frequency at one site than at a number of other possible sites of similar type, usually involving a structural or positional isomer.

regiospecific describing a chemical reaction that occurs specifically in only one of two possible ways, but not including stereospecificity (*see* **stereospecific**).

registration peptide one of the postulated extensions of the α chains of **tropocollagen**, when synthesis has just been completed; two α1 extensions and one α2 extension interact to form a stable assembly with the correct chains brought together into register.

regression coefficient *see* **regression line**.

regression line a line fitted to a series of two variable quantities, *x* and *y*, so as to minimize the sum of the squares of the distances parallel to the *y* axis of the observations from the line. The regression line of *y* on *x* has the equation (**regression equation**): $y = a + bx$ where $a = \sum y - b\sum x/n$ and *b*, the **regression coefficient**, is the slope of the line and is given by:

$$b = (n\sum xy - \sum x\sum y)/(n\sum x^2 - (\sum x)^2)$$

where *n* is the number of pairs of observations. In an analogous manner a regression equation, line, and coefficient may be obtained for *x* on *y*.

regucalcin a hepatic Ca^{2+}-binding protein, and also a GTP-binding protein, that modulates the hormonal regulation of plasma membrane Ca^{2+},Mg^{2+}-ATPase.

regular expression *abbr*.: regex; a shorthand representation of the conservation in an aligned sequence motif. For proteins, the single-letter code is used to denote allowed or forbidden residues (or residue groups) at each position; wildcards (x) denote positions that are not conserved. For example, a regex that detects possible sites of *N*-glycosylation is N-**P**-[S,T]-{P}, which means that Asn is completely conserved at the first position, Pro is forbidden at the second and fourth, and Ser or Thr are allowed at the third. Regexs can provide characteristic signatures for protein families; they form the basis of the PROSITE and eMOTIF databases. *See also* **rule**.

regulation *(in metabolism)* control of the rate of a metabolic system, especially in intact organs and cells, as a result of interaction from components of related systems. A distinction is sometimes made between **control** and regulation, with the latter described as the maintenance of a variable (e.g. rate or concentration) at a constant value over time, in spite of fluctuations in external conditions. It is therefore linked to homeostasis. **—regulatory** *adj.*

regulator gene *or* **regulatory gene** any gene that does not contribute structural information to the proteins whose synthesis it controls, but that determines the production of a specific cytoplasmic substance, a **repressor**, that inhibits information transfer from a **structural gene** (or genes) to protein. It may control the synthesis of several different proteins, which are determined by a coordinated group of structural genes (*see* **operon**). Although, when it was put forward, the concept of the regulatory gene was helpful, it is now realized that the genome codes for many different proteins that control the transcription of the structural genes (*see*, e.g., **attenuators**, **transcription factors**), and that can be classed as gene-activator proteins; these will possess two domains, one to recognize a specific regulatory DNA sequence, the other to contact the transcription machinery.

regulator of G-protein signalling protein *see* **RGS protein**.

regulator-site hypothesis a hypothesis to explain the control of insulin release from pancreatic islet B cells by glucose. It postulates that the glucoreceptor is an enzyme that is activated (or inhibited) by glucose and catalyses the production from a precursor of an activator, which controls the release process. *Compare* **substrate-site hypothesis**.

regulatory enzyme an enzyme that regulates the rate of a metabolic pathway; under regulating conditions, it is the enzyme of lowest activity in the pathway. Commonly, the rate is altered either by variation in the amount of regulatory enzyme (as a result of increased or decreased synthesis or degradation), or by variation in its activity by covalent modification (often by phosphorylation or dephosphorylation by kinases or phosphatases) or by allosteric modifiers. Classic examples are **phosphofructokinase** and glycogen phosphorylase (*see* **phosphorylase**).

regulatory factor for X box *see* **RFX**.

regulatory gene *see* **regulator gene**.

regulatory sequence a sequence in a DNA molecule concerned with regulating the expression of a gene; e.g. a **promoter** or **operator**.

regulatory site a specific site on an enzyme that is distinct from the substrate-binding site and that binds a feedback inhibitor or other regulatory molecule. *Compare* **allosteric site**.

regulatory subunit any of the subunits of a heteromultimeric enzyme that has a regulatory rather than a catalytic function.

regulon a group of genes, whether linked in clusters or unlinked, that respond to a common regulatory signal.

rehydrate to restore water to material that has been lyophilized (*see* **freeze-dry**) or otherwise dehydrated.

reiterated describing nucleotide sequences that occur many times within a genome. These occur especially in higher organisms. *See also* **repetitive sequences**.

REL a gene family encoding transcription factors of the κB family; v-*rel* is the oncogene of avian reticuloendothelial virus strain T (REV-T), encoding p69$^{v\text{-}rel}$. Rel and v-Rel form homo- or heterodimers that bind to **NF-κB** motifs. v-Rel has lost two N-terminal amino acids and 118 C-terminal residues compared with Rel.

relA a gene in *Escherichia coli*, mutations in which can lead to a 'relaxed' phenotype in which amino-acid starvation fails to switch off ribosomal RNA biosynthesis. The gene product is an enzyme active in the presence of ribosomes and uncharged tRNA, and called GTP pyrophosphokinase, EC 2.7.6.5; *systematic name*: ATP:GTP 3′-pyrophosphotransferase; *other names*: pppGpp synthetase I; **stringent factor**; guanosine 3′,5′-polyphosphate synthase; it catalyses a reaction between ATP and GTP to form guanosine 3′-diphosphate 5′-triphosphate and AMP. The product is referred to as pppGpp and is converted to ppGpp (guanosine 3′-diphosphate 5′-diphosphate), which is the active nucleotide in evoking the **stringent response**.

relational database a database in which data are stored in tables. Different aspects or properties of the data are embodied in different tables, but tables may contain overlapping information.

relational database management system *abbr*.: RDBMS; software that manages a **relational database**, and is optimized for rapid and flexible retrieval of data (e.g. MySQL, postgreSQL, Oracle).

relative atomic mass *or (formerly)* **atomic weight** *abbr*.: r.a.m.; *symbol*: A_r. **1** (of an atom) the ratio of the mass, m_a, of the atom in question, to the atomic mass constant, m_u, which is one-twelfth of the mass of the nuclide ^{12}c; i.e. $A_r = m_a/m_u$. A_r is a mass ratio, a pure number with no units. **2** (of an element) the ratio of the average mass, $\bar{m}_a$, of the atoms in a specified sample of the element in question, E, to the atomic mass constant, m_u; i.e. $A_r(E) = \bar{m}_a(E)/m_u$. Since, in general, elements are mixtures of isotopes of differing nucleon numbers (mass numbers), an average mass of the atoms is required in this definition. Furthermore, the isotopic composition of many elements can vary with the origin of the sample and its treatments. Hence there are limits to the precision with which the values of the relative atomic masses of many elements can be given.

relative band rate *or* **relative band speed** *see* **R_B value**.

relative biological effectiveness *abbr*.: RBE; *an alternative term for* **quality factor**.

relative centrifugal force *symbol*: *G*; the force acting on a particle in a centrifugal field expressed in multiples of the acceleration due to gravity, *g*. $G = \omega^2 r$, where ω is the angular velocity in rad s^{-1} and *r* the radial distance from the axis of rotation in m. ($G = 1440 \times \pi^2\omega^2 r$ where ω is in revolutions per minute and *r* in cm.)

relative density *symbol*: *d*; the ratio of the mass density of a substance, ρ, at a given temperature, to the mass density of a reference substance (usually water), ρ^o at a reference temperature (usually 4°C); i.e. $d = \rho/\rho^o$.

relative formula mass the relative molecular mass as calculated from the formula of a compound.

relative molecular mass *or* **relative molar mass** *or* **molecular weight** *abbr*.: r.m.m.; *symbol*: M_r; the ratio of the mass of a molecule, m_f, to the atomic mass constant, m_u, which is one-twelfth of the mass of the nuclide ^{12}C; i.e. $M_r = m_f/m_u$. M_r is a mass ratio, a pure number with no units. The convention for indicating the size of a protein is thus 'M_r' followed by a number without units, e.g. M_r 10000; the equivalent **molecular mass**, i.e. its mass in daltons, would be 10 kDa. *See also* **dalton**, **relative atomic mass**, **unified atomic mass unit**.

relative permittivity *symbol*: ε_r; *formerly called* **dielectric constant**, the ratio of the permittivity of a substance, ε, to the permittivity of vacuum, ε_0, i.e. $\varepsilon_r = \varepsilon/\varepsilon_0$.

relaxation *(in chemistry)* the process of self-adjustment of a molecular system to a new state of minimum free energy following a disturbance.

relaxation kinetics a technique used to study rapid reactions in which a mixture at equilibrium is rapidly adjusted to a new set of conditions. The system is then observed as it approaches its new equilibrium, a process known as **relaxation**. The temperature-jump method is often used, whereby an electric discharge is used to increase the temperature by several degrees in a period of about 1 µs. *See also* **rapid-reaction kinetics**.

relaxation spectrometry the use of spectrometry to follow the kinetics of a reaction undergoing relaxation from a perturbation. *See* **relaxation kinetics**.

relaxed control a mechanism of control of plasmid replication in which replication of plasmids greatly exceeds that of the chromosome. *Compare* **stringent control**.

relaxed DNA circular DNA that is not supercoiled (*see* **supercoil**), and instead has an unwound loop. The supercoiled form is energetically favoured over the relaxed form. Since the supercoiled DNA is more compact it moves faster when centrifuged or upon electrophoresis, and so the two forms of DNA can be separated.

relaxed form *abbr*.: R form; one of two alternative quaternary structures of a protein, the other being the **tense form** (or taut form, *abbr*.: T form). These forms derive from the concept of two conformational states of a protein, which differ in their affinities for a ligand. Factors affecting the conformational equilibrium also influence the affinity of ligand-binding, and vice versa. Such factors may include the ligand itself, which could enhance or reduce the affinity of the protein, giving rise to **positive cooperativity** or **negative cooperativity** of binding respectively. The T form has a lower affinity for the substrate. For example, oxyhemoglobin is R, and deoxyhemoglobin is T; the binding of O_2 to the heme group causes the iron atom to move with respect to the heme plane, and this favours the move from T to R. *See also* **allosteric constant**, **Monod–Wyman–Changeux model (for allosteric compounds)**.

relaxed mutant a bacterial mutant that lacks the *rel* (*relaxed*) gene, which exerts a critical control over the **stringent response**. The *rel*$^-$ mutant is unresponsive to amino-acid starvation, so that rates of RNA synthesis, for example, continue as before. *See also* ***relA***.

relaxin a protein hormone (M_r ~5600) that is responsible in most mammals (including humans) for dilation of the symphysis pubis, softening of the cervix, and various other physiological changes prior to parturition. It is synthesized and stored in the corpus luteum. Like **insulin**, the hormone consists of two polypeptide chains linked by two disulfide bonds, with an intrachain disulfide bridge also present. Although otherwise dissimilar in primary structure, the two proteins have very similar tertiary structures. As with insulin, synthesis is thought to occur via an inactive, single-chain precursor, in this case **prorelaxin**, and storage is as granules in vesicles. *See also* **insulin-related growth factors**.

relaxin-like factor a protein, homologous with **relaxin**, that is synthesized by Leydig cells in the testis and by theca cells of ovarian follicles. It binds one of the G-protein-coupled membrane receptors for relaxin. Its physiological role is unclear.

release factor *abbr*.: RF *or (formerly)* R factor; a protein that participates in the release of a nascent polypeptide chain from a ribosome. There are two classes of release factor, one codon-specific and the other non-codon-specific. In bacteria, two codon-specific factors have been identified: RF-1, specific for UAG/UAA; and RF-2, specific for UGA/UAA. In eukaryotes, one such factor has been found, eRF-1. These factors act at the ribosomal A-site, and require polypeptidyl-tRNA at the P-site. In bacteria, the actions of RF-1 and RF-2 are aided by the non-codon-specific RF-3, which binds to guanine nucleotides. In eukaryotes, a similar factor, eRF-3, has been identified. The genes encoding RF-1 (*prfA*) and RF-2 (*prfB*) have been identified. Mutations in these genes often cause misreading of termination signals, increased frameshifting, and temperature- sensitive growth of the cells. *See also* **ribosome recycling factor**.

release-inhibiting factor *or* **release-inhibiting hormone** any polypeptide that inhibits the release of a hormone or hormones. An example is **somatostatin**.

releasing hormone *or* **releasing factor** any neuropeptide synthesized in the hypothalamus that is carried to the anterior pituitary where it regulates the production and secretion of the tropic hormones, e.g. thyrotropin, somatotropin, or the gonadotropins. In the anterior pituitary releasing hormones act via the **adenylate cyclase** system and are then degraded by proteolysis.

Relish an NF-κB type of transcription factor of *Drosophila* that activates genes for antibacterial peptides. REL-110 is cleaved into an N-terminal REL-68, which enters the nucleus, and a C-terminal REL-49, which remains in the cytoplasm.

rem *symbol*: rem; a non-SI unit of (radiation) **dose equivalent**, equal to 0.01 j kg^{-1} of irradiated human (or other mammalian) tissue. It is being superseded by the **sievert**; 1 rem = 10^{-2} sievert. [Acronym for röntgen equivalent man (or mammal).]

REMI *abbr. for* restriction enzyme-mediated integration (*see* **insertional mutagenesis**).

remnant a fragment of a molecule, or other entity, remaining after partial degradation, especially **chylomicron** remnant.

remnant hyperlipidemia *or* **type III hyperlipidemia** *or* **familial betadysproteinemia** a combined hypercholesterolemia and hypertriglyceridemia due to excessive chylomicron and very-low-density lipoprotein (VLDL) remnants in plasma. It is often associated with cutaneous xanthomas and premature vascular disease. Hypothyroidism, obesity, and diabetes mellitus are frequently associated with the condition. Homozygosity for apoE-2 is a predisposing factor, and rare point mutations in apoE are the cause of an autosomal dominant form. *See* **hyperlipidemia**.

renal pertaining to, or of, the kidney.

renal rickets a condition occurring in older children and characterized by the skeletal changes of **rickets**, due to impairment of renal function allowing excessive loss of calcium and phosphate into the urine.

renaturation the return of denatured macromolecules (protein, DNA, etc.) to the conformation they maintained before denaturation. In the case of proteins, reversible denaturation may be brought about by disulfide reducing agents and urea; for nucleic acids, by heat or salts. *See also* **native state**.

renewal (of tissue) *see* **regeneration** (def. 2).

Renilla reniformis a species of soft coral, or sea pansy, that contains a **luciferase** enzyme (also found in the related species *R. mullerei*) responsible for producing a characteristic green fluorescence. The luciferase catalyses the oxidative decarboxylation of coelenterazine to produce coelenteramide and light emission with a spectral peak at 480 nm. The luciferase is used as a reporter gene in vectors for promoter assays.

renin *or* **angiotensin-forming enzyme** *or* **angiotensinogenase** EC 3.4.23.15; a glycoprotein aspartyl proteinase formed from prorenin in plasma and kidney. It is also produced by the submaxillary gland of certain strains of mice. It is highly specific for the Leu-|-Leu bond in **angiotensinogen**, which it cleaves to generate angiotensin I. In humans, renin is derived from a 406-amino-acid **preproprotein**; residues 1–23 are the signal peptide, and 24–66 are the propeptide. *Compare* **rennin**.

renin–angiotensin system a system involved in the control of blood pressure. **Renin**, secreted into the blood by the kidney in response to osmotic changes, anoxia, or kidney trauma, acts on angiotensinogen to release angiotensin I (AI) (*see* **angiotensin**). **Angiotensin-converting enzyme** forms angiotensin II (AII) from AI by release of His–Leu from the C-terminal end. AII stimulates release of the mineralocorticoid **aldosterone** from the glomerulosa cells of the adrenal cortex. Various nonapeptide analogues of AI inhibit converting enzyme and are used in the treatment of renin-dependent hypertension. *See also* **captopril**.

rennet an extract obtained from the stomachs of young mammals living on milk. It contains rennin (i.e. **chymosin**), an enzyme that clots milk and is used in cheese-making.

rennin *an alternative name for* **chymosin** (which is preferred because of possible confusion with **renin**). *See also* **rennet**.

R-enzyme *or* **starch debranching enzyme** an enzyme in plants that catalyses hydrolysis of α1-6-glucan branch points in starch, in the reaction: branched α1-4(α1-6)-glucan + H_2O = linear α1-4-glucans. The α1-6 linkage acted on carries an α1-4-glucan chain about four residues long that cannot be cleaved by starch phosphorylase. These short chains become substrates for **D-enzyme**.

Reoviridae a family of double-stranded RNA viruses (class III in the **Baltimore classification**) with a segmented genome, infecting vertebrates, arthropods, and plants. The virion consists of a nonenveloped icosahedral particle, 60–80 nm across, and containing 10–12 segments of RNA together with **RNA-directed RNA polymerase**; the latter serves to transcribe the negative strand of each RNA molecule into mRNA. This family comprises six groups: the orthoreoviruses, orbiviruses, rotaviruses, cytoviruses, phytoreoviruses, and Fijiviruses. No pathology is associated with the orthoreoviruses infecting humans, but rotaviruses cause gastroenteritis, and orbiviruses cause the disease blue tongue in sheep.

reovirus *see* **Reoviridae**.

rep an obsolete unit of **absorbed dose** of **ionizing radiation** of any kind, equal to the dose of radiation that, upon absorption by a given mass of living tissue, causes the same energy deposition as 1 röntgen of X- or gamma radiation, i.e. about 96 ergs per gram (0.0096 J kg^{-1}) of tissue. *See also* **rad**, **rem**. [Acronym for röntgen equivalent physical.]

Rep *abbr. for* Rab escort protein; either of two proteins (Rep-1 and Rep-2) that are ubiquitously expressed, mediate binding of Rab proteins (*see* ***RAB***), and are involved in membrane trafficking. Rep-1 (95 kDa) is a subunit of the heterotrimeric geranylgeranyl transferase that prenylates Rab proteins (*see* **prenylation**). Deficiency arises from many mutations and causes choroideremia. Rep-2 (658 amino acids) is produced by an intronless gene and is homologous with Rep-1.

REP *abbr. for* repetitive extragenic palindromic sequence.

RepA the protein product of the *Escherichia coli* gene *repA,* which has a role in the replication of DNA in *E. coli*. Although the principal **DNA helicase** in *E. coli* is DnaB helicase, there is also a different 68 kDa monomeric protein, which has some helicase activity during certain life-cycle stages of the replication of single-stranded phages. The contribution of RepA protein to the host cell is less clear, but the rate at which *E. coli* replication forks propagate is reduced in *rep*$^-$ mutants.

repairase an enzyme concerned in the repair of an interrupted polynucleotide chain.

repair enzyme any enzyme responsible for the excision of **pyrimidine dimers,** which are formed on exposure of DNA to ultraviolet light, when adjacent pyrimidine residues on a DNA strand become covalently linked. Three enzymic activities are essential for the repair: (1) the complex of three proteins encoded by the *uvrABC* genes (*see* ***uvr***) that detects the distortion produced by the pyrimidine dimer: (2) the UvrABC enzyme complex also has another activity, described as a specific excinuclease of the UvrABC complex, which cuts the damaged DNA strand eight nucleotides away from the dimer on the 5′ side and four nucleotides away on the 3′ side; (3) DNA polymerase I enters the gap to effect repair synthesis. Gaps are finally sealed by **DNA ligase**. *See also* **DNA repair enzyme**, **excision repair**, **recombinational repair**, **mismatch repair**.

repairosome the nucleotide excision repair (NER) complex of yeast that contains the majority of NER proteins.

repeated genes *see* **repetitive sequences**.

repeat-induced point (mutation) *see* **RIP**.

repeat sequence *or* **repeat** **1** *(in DNA) see* **repetitive sequences**. **2** *(in proteins)* any sequence of the same amino-acid residue, or group of amino-acid residues, that is repeated in a polypeptide: e.g., the protein huntingtin, involved in **Huntington's disease**, contains a poly- glutamine tract, which can vary in size from 11–86 repeat units; and the primary structure of **collagen** is characterized by a G-x-P repeat unit. **3** the repeats of sugar residues often found in complex polysaccharides.

repeat unit a major periodicity in the structure of a molecule as deduced from X-ray diffraction patterns.

repetitive extragenic palindromic sequences *or* **palindromic units** palindromic sequences in repetitive DNA in *Escherichia coli* and *Salmonella typhimurium*. These are never found within a coding sequence. They are topoisomerase substrates and potential transcription terminators.

repetitive sequence a repeated sequence of nucleotides found in the DNA of eukaryotes. There are various types. (1) **Satellite DNA** typically consists of tandem (head-to-tail) repeats of a few hundred nucleotides. It is so called because those first discovered had an unusual ratio of bases that made it possible to separate the satellite DNA from the bulk of the cell DNA in a centrifuge. (2) **Minisatellite** DNA consists of shorter tandem repeats. The **restriction fragment length polymorphisms** linked to many genes have short sequences of bases in common. rDNA (*see* **ribosomal DNA**) probes for these sequences are useful in the preparation of a profile of the genome of an individual (fingerprinting). (3) **Transposons** (transposable elements) also contain repeated sequences, often numbering several hundred copies. Primate DNA has large numbers of two types of transposable elements, L1 transposable elements and **Alu sequences**, which comprise about 300 bases. (4) **Repeated genes** for rRNA and histones, so that cells can synthesize large amounts of these vital products. In many cases repetitive sequences seem to be maintained solely by their ability to replicate within the genome (the '**selfish DNA hypothesis**'). Rather than conferring benefits their behaviour can sometimes result in loss of fitness to the host, as in some human genetic diseases; mutations can arise due to insertion of transposable elements, to chromosomal rearrangements induced by recombination between repeated sequences, or to amplification of microsatellite sequences.

replacement vector a **cloning vector** in which part of the normal genome is replaced by foreign DNA. For example, the lambda phage EMBL4 contains only two *Bam*HI cleavage sites and so the middle segment, or stuffer fragment, of the DNA can be removed leaving 72% of the normal genome. A suitably long DNA replacement between the two arms of lambda DNA enables such a recombinant DNA molecule to be packaged into a lambda particle. It contrasts with an **insertion vector** where the foreign DNA is incorporated at a single restriction site.

replica *(in electron microscopy)* a reproduction of the surface of an object. There are various ways by which the surface of an object, e.g. membrane of an organelle, may be examined by transmission electron microscopy by means of a replica. Such a replica may be obtained by evaporating a thin film of a heavy metal such as platinum on to the dried specimen. The metal is sprayed from an oblique angle in order to deposit a coating of uneven thickness because a shadow effect is created that gives the image a three-dimensional appearance. The organic material may be dissolved away to provide a replica of the surface of the specimen. Two other methods, **freeze-etching** and **freeze-fracturing**, employ frozen sections.

replica plating a technique for the production of identical patterns of bacterial colonies on a series of agar plates. The method uses velveteen or other fabric stretched on a pad, which is then pressed onto a plate of bacterial cultures so that some bacteria from each colony are transferred to the pad, preserving the spatial pattern of the colonies (in mirror image). If this pad is then pressed lightly onto a fresh culture plate, it will transfer colonies in the same formation to the new plate. This new plate may be prepared using media that will be selective for certain mutants, fermentation reactions, or antibiotic sensitivity. A similar technique can be used in the screening of **hybridomas** for antibody production.

replicase *a loose term for* certain polymerase enzymes; e.g. certain viral **RNA-directed RNA polymerases** can be referred to as RNA replicases.

replicate 1 to make an exact copy of something, as in the **replication of DNA**. **2** *(in electron microscopy)* to make a **replica**.

replication bubble *or* **replication eye** *an alternative term for* **theta structure**.

replication complex the complex of replication proteins that are linked together as a single large unit, of total mass 10^6 daltons, that moves rapidly along the DNA during **replication of DNA**. It allows DNA to be synthesized on both sides of the replication fork in a coordinated and efficient manner. That part of the complex that contains **DNA primase** and **DNA helicase** is known as the **primosome**.

replication-error mutation a mutation that arises during DNA replication as a result of the incorrect copying of the sequence of nucleotides in the parent DNA. Probably fewer than one mistake occurs in 10^9 nucleotides added.

replication fork *or* **replicating fork** the Y-shaped region of a replicating DNA molecule or chromosome, resulting from separation of the DNA strands and in which synthesis of new strands takes place. The process requires the participation of **helicases** that open the duplex.

replication of DNA the means whereby new strands of deoxypolynucleotides are synthesized. The structure of DNA, i.e. two strands of complementary base pairs, led Watson and Crick to propose that the two strands could unwind and each act as the template for a new strand, thus forming two helices, each containing one parental strand and one new one. The elegant **Meselson–Stahl experiment** demonstrated that DNA replication was indeed semiconservative. Unwinding of parental DNA requires more than 20 proteins in a complex known as a **primosome**. All DNA-dependent DNA polymerases synthesize the new strands in the direction 5′ to 3′ using as substrates deoxynucleoside triphosphates with the production of pyrophosphate. The new strands are antiparallel to the parental template strand. One strand, the **leading strand** (*or* continuous strand), is synthesized in a continuous fashion whereas the other strand, the **lagging strand** (*or* discontinuous strand), is synthesized discontinuously to give **Okazaki fragments** (1000–2000 nucleotides long in prokaryotes and 100–200 nucleotides long in eukaryotes) which are eventually joined by **DNA ligase**. The DNA polymerases cannot start a chain and must rely on a priming device; this is provided by RNA **primase,** which again synthesizes an RNA primer in the direction 5′ to 3′ using nucleoside triphosphates as substrate. The continuous strand needs to be primed only once whereas the discontinuous strand must be primed repeatedly. Three principal **DNApolymerases** for *Escherichia coli* were discovered in the laboratory of US biochemist Arthur **Kornberg (1918–)**. **DNA polymerase I**, in addition to possessing synthetic activity *in vitro*, is also a 3′–5′ **exonuclease** which gives it an editing function. It also has 5′–3′ nuclease activity. **DNA polymerase II** participates in DNA repair but is not required for replication. **DNA polymerase III** is the predominant polymerase for replication of *E. coli* DNA *in vivo.* Eukaryotic cells have at least four DNA polymerases.

replicative able to be replicated. *See also* **replicative form**.

replicative form *abbr*.: RF; the intracellular form of viral nucleic acid that is active in replication. A single-stranded viral nucleic acid, be it RNA or DNA, is first converted into a double-stranded form – the **replicative intermediate** – to enable the viral strand to be replicated preferentially. In the case of a **retrovirus** a hybrid of RNA and DNA is formed.

replicative intermediate *see* **replicative form**.

replicon 1 a structural gene that controls the initiation and replication of DNA. **2** by association, the whole DNA sequence (such as the bacterial chromosome) that is replicated under the influence of a single replicon system.

replisome a multiprotein complex that includes two DNA polymerase molecules for synthesis of the leading and lagging strands at the site of origin of DNA replication. *See* **replication of DNA**.

replitase a particulate fraction that can be isolated from the nuclei of **S phase** Chinese hamster embryo fibroblasts and containing some of the enzyme activities required for DNA synthesis.

reporter gene a gene used to disclose the function of potential regulatory sequences. The sequences are placed in plasmids, upstream of the reporter gene; these chimeric plasmids are then introduced into cells and the expression of the reporter gene is measured as an index of the function of the regulatory sequences under the conditions being investigated. The *lacZ* (***β*-galactosidase**) gene, the *CAT* gene (*see* **chloramphenicol *O*-acetyltransferase**), and the gene encoding firefly **luciferase** have been used in this way.

reporter group a chemical group that acts as a **probe**.

repress to check or restrain; the effect may be partial or total. *See* **repression**, **repressor**.

repressible describing a metabolic reaction that is capable of undergoing **repression**.

repression *(in genetics)* the act of inhibiting gene expression. An example is **catabolite repression** of the *lac* operon by glucose, mediated through binding of cyclic AMP to **catabolite (gene) activator protein** (CAP). By extension, the gene product itself (enzyme or other protein) and thus any associated metabolic reaction is said to be repressed. *See also* **repressor**.

repressor *(in genetics)* a molecule that specifically prevents the transcription of regulatory genes under control of an **operator**. When the repressor binds the operator, transcription cannot occur. An inducer induces transcription by binding to the repressor to form a complex that has a low affinity for the operator. The classic example is the lactose repressor protein, which controls the expression of the **_lac_ operon** in *Escherichia coli*. The protein binds to a specific sequence of 21 nucleotide pairs (called the operator) that overlaps an adjacent RNA polymerase binding site (the promoter) at which RNA synthesis begins. In the presence of lactose, allolactose is formed, which binds to the repressor. This induces a conformational change that causes the repressor to loosen its hold on the DNA so that the gene is derepressed. In other examples, the binding of a signalling molecule may increase the affinity with which the repressor binds to the DNA; e.g. the *trp* operon, encoding enzymes that produce tryptophan in *E. coli* (*see* **trp gene**). *See also* **repression**.

reproducibility the ability to carry out a series of identical experiments to yield results that fall within a small range of error derived by statistical analysis (*see* **standard deviation**, **standard error of the mean**). The limits of error that are acceptable depend on the limitations of experimental technique and the inherent variability of the system under investigation.

reproduction *(in biology)* the production by an organism of new individuals that are more or less similar to itself. Reproductive strategies can be divided broadly into two categories: sexual reproduction, which requires the participation of male and female **gametes** and gives rise to genetic variation among the offspring; and asexual reproduction, which does not involve gametes and leads to the formation of offspring that are genetically identical to the parent. The latter takes various forms; examples include **budding**, **fragmentation**, **parthenogenesis**, **spore** formation, and **vegetative reproduction**.

reptation a term invoked to rationalize the movement and thermodynamics of linear polymers, dividing the chain conceptually into sections (**reptons**), which form the basis for statistical mechanical calculations of the relaxation time of the polymer and viscosity of polymer solutions. Large DNA molecules move through the pores of agarose gels by reptation.

repton *see* **reptation**.

RER *abbr. for* rough endoplasmic reticulum.

reseal to join again the ends of ruptured components, as in, e.g., the resealing of plasma membranes after whole cells have been rendered permeable by various techniques, or of fractionated membrane fragments, which may reseal to form closed vesicles. The term can also refer to ligation of the cut ends of DNA after insertion of foreign DNA into a vector.

reserpine (3*β*,16*β*,17*α*,18*β*,20*α*)-11,17-dimethoxy-18[(3,4,5-trimethoxybenzoyl)oxy]yohimban-16-carboxylic acid methyl ester; an alkaloid isolated from the roots of certain species of *Rauwolfia* and noted for its antihypertensive and CNS depressant actions. These arise from its inhibition of the intraneuronal Na^+, Mg^{2+}-ATPase pump, which maintains the neuronal vesicular stores of biogenic monoamines (**dopamine**, **norepinephrine**, and **serotonin**).



reserve polysaccharide any polysaccharide that is stored to provide an energy source at times of need. Examples are starch granules in plants, and glycogen granules in animals.

***Re/Si* convention** a nomenclatural system for specifying the **stereoheterotopic** faces of a trigonal atom using the **sequence rule** in two dimensions. This is used to establish a priority sequence for the three ligands, e.g. of C*abc*. The plane containing C and the first atoms of the ligands is then inspected from an arbitrarily chosen side. Starting with the highest priority ligand, it is determined whether the priority sequence is clockwise, hence *re* (from Latin *rectus*, right), or counterclockwise, hence *si* (from Latin *sinister*, left); e.g. for acetaldehyde, CH_3CHO, if the face inspected shows a clockwise ordering, $O \rightarrow CH_3 \rightarrow H$, that face is designated *Re*. There are a number of extensions of this general principle, and the specialist literature should be consulted for details.

residence time the averaged time that a site is occupied by any designated molecule.

resident protein *see* **luminal protein**.

residual body a membrane-lined cytoplasmic inclusion characterized by undigested residues (e.g. membrane fragments or whorls, ferritin-like particles). The term embraces **telolysosome** and (hypothetical) **post-lysosome**.

residue **1** any of the incorporated amino-acid moieties in a peptide or protein. **2** material that remains after any procedure to remove something.

residue mass the relative molecular mass of a residue; i.e. the sum of the **relative atomic masses** of all the atoms composing the residue.

residue weight the molecular weight of a residue; i.e. the sum of the **atomic weights** of all the atoms composing the residue. **Residue mass** is the preferred term.

resin **1** *or* **rosin** any of a group of naturally occurring amorphous solids or semisolids, typically light yellow to dark brown, brittle, and insoluble in water. They are found as plant exudates, often on trees such as pines and firs. **2** the polymer base of certain ion-exchange materials used in chromatography. *See* **ion-exchange polymer**.

resistance **1** the ability of a living organism, particularly a bacterium, to resist the effect of a disadvantageous environment or substance, especially an antibiotic. A bacterium may possess one or more resistance plasmids. **2** *see* **electric resistance**.

resistance donor a strain of an organism, usually a bacterium, that is capable of transferring resistance, usually by conjugation, to a suitable recipient.

resistance factor *abbr*.: R factor; *an alternative name for* **resistance plasmid**.

resistance plasmid *abbr*.: R plasmid; a **plasmid** that carries genetic information for resistance to antibiotics or other antibacterial drugs. *Other name*: resistance factor (*abbr*.: R factor).

resistin *or* **FIZZ 3** a protein, related to FIZZ 1, that is secreted by white adipose tissue into the bloodstream. The mouse protein contains two identical subunits (each of 114 amino acids) joined by a disulfide bond. There are three murine and two human homologues, which show ≈53% sequence identity. In obese mice, serum levels of FIZZ 3 are high and are decreased by thiazolidinedione drugs, which increase sensitivity to insulin in various tissues. Antibodies to resistin lower blood glucose levels and improve insulin sensitivity in these mice. *See* **FIZZ**.

resolution **1** the degree of separation between two compounds being subjected to a transport method such as chromatography or sedimentation equilibrium (i.e. being resolved); complete resolution yields two compounds each uncontaminated by the other. **2** *(in physics and biophysics)* the extent to which closely juxtaposed objects can be distinguished as separate objects using an optical instrument, e.g. a microscope. The degree of resolution is dependent on the **resolving power** of the system. The fineness of detail with which objects can be seen is limited by the wavelength of light used. Only those objects similar in dimensions to the wavelength of the light (or larger) can be resolved. The wavelength of X-rays is from about 10^{-8} m to 10^{-11} m and they can thus be used to resolve structures at the atomic level. Thus a structure can be said to have been determined at 3 Å resolution, 7 Å resolution, etc.

resolvase an enzyme that, together with **transposase**, is involved in the replicative transposition of genetic elements in *Escherichia coli*. The 3′ ends of the target chromosome, after the first cutting and splicing, serve as replicative primers for copying both the gaps and the two strands of the transposable element (which contains transposase) itself. Ligase action generates a cointegrate, a large circular structure containing both donor and target chromosomes with two freshly replicated copies of the transposable element. Resolvase now catalyses the site-specific recombination between the two elements, resulting in one copy of the transposable element inserted in each of the two chromosomes.

resolving power 1 *(in chromatography)* the power to resolve individual compounds (*see* **resolution**(def. 1)). It depends on (1) the efficiency of the system employed; for columns this is given by the **theoretical plate** number; and (2) the relative affinities of different compounds for the stationary and mobile phases. **2** *(in physics)* **a** the ability of an optical instrument, e.g. a microscope or telescope, to produce separate images of objects placed close together. **b** the ability of a spectrometer to separate adjacent peaks in a spectrum.

resonance 1 *(in physics)* the induction or amplification of one vibration by another vibration of a periodicity equal to the natural oscillation frequency of the first, which is then said to resound. In an electronic circuit, resonance occurs when an applied emf equals the natural frequency of oscillation of the circuit (used, e.g., in tuning a radio receiver). **2** *(in chemistry)* a phenomenon shown by any molecular entity to which more than one **contributing structure** can be assigned, when these structures are of similar energy and differ only in the distribution of the valence electrons; the entity then oscillates between the two structures and adopts, in effect, an intermediate state. Resonance always results in a different distribution of electrons than would be the case if there were no resonance. *See also* **resonance energy**, **resonance hybrid**. **3** *see* **electron spin resonance spectroscopy**, **nuclear magnetic resonance**. **—resonant** *adj.*; **resonate** *vb.*

resonance energy the difference in energy of an actual molecule and the **contributing structure** of lowest energy.

resonance hybrid the structure that results when a chemical entity exhibits **resonance** (def. 2), such as occurs by the sharing of one or more electrons over several bonds. It has a lower energy than any of the possible formal nonresonance **contributing structures**, giving additional stability of which the so-called **resonance energy** is a measure. A classic example is carbon dioxide, which may be represented by the **Lewis formula** for each as $\underset{\cdot\cdot}{\ddot{\mathrm{O}}}::\mathrm{OC}::\underset{\cdot\cdot}{\ddot{\mathrm{O}}}$, $\overset{-}{:}\underset{\cdot\cdot}{\ddot{\mathrm{O}}}:\mathrm{C}:::\mathrm{O}\overset{+}{:}$, and $+:\mathrm{O}:::\mathrm{C}:\underset{\cdot\cdot}{\ddot{\mathrm{O}}}:-$. *Compare* **mesomerism**.

resonance Raman spectroscopy a spectroscopic technique for characterization and assignment of vibrations directly connected with a **chromophore**, as well for the assignment of the chromophore. The excitation frequency is applied close to the absorption maximum of the chromophore.

resonance stabilization *or* **resonance stabilisation** stabilization of molecular structure by resonance; *see also* **resonance hybrid**.

resonate *see* **resonance**.

resorb to absorb again. **—resorbent** *adj.*; **resorption** *n.*; **resorptive** *adj.*

resorcinol *m*-dihydroxybenzene; a compound used in the **Seliwanoff test** for ketoses.

resorption *see* **resorb**.

RESOURCERER a database for annotating commonly available microarray resources.

respiration 1 the process of gaseous exchange between an organism and its environment. In plants, microorganisms, and many small animals, air or water makes direct contact with the organism's cells or tissue fluids, and the processes of diffusion supply the organism with dioxygen and remove carbon dioxide. In larger animals the efficiency of gaseous exchange is improved by specialized respiratory organs, such as lungs and gills, which are ventilated by breathing mechanisms. These organs possess respiratory surfaces, across which gases are exchanged with the blood or other transport medium. This then carries dioxygen to the body tissues, and removes carbon dioxide. **2** *or* **oxidative metabolism** the various energy-yielding reactions of cells or organisms that require oxygen as the final electron acceptor. *See* **respiratory chain**. **—respiratory** *adj.*

respiratory burst a phase of elevated oxygen consumption that occurs in neutrophils, monocytes, and macrophages shortly after phagocytosing material. This is associated with increased activity of the hexose monophosphate shunt and production of **NADPH** (*see* **pentose phosphate pathway**). An NADPH oxidase complex passes electrons from the NADPH to O_2 creating the reactive superoxide (O_2^-) ion and H_2O_2 in the vacuole. Patients with chronic granulomatous disease never produce a respiratory burst. The patients suffer an accumulation of mononuclear cells at sites of chronic inflammation, forming granulomas. *See* **phagocyte NADPH oxidase**.

respiratory chain *or* **electron-transport chain** the sequence of enzymes and other proteins within the mitochondrion and prokaryotic cell membranes by which substrates, including NADH and succinate, are oxidized by dioxygen. It is fundamental to tissue **respiration** (def. 2) which has the function of maintaining tissue metabolism through **oxidative phosphorylation**. The chain can be separated into a number of particles (*see* **respiratory complex**) each of which contains individual elements of the chain. The mechanism involves, in the case of NADH, removal by NADH dehydrogenase of a proton plus two electrons. In the case of succinate, there is a transfer of two hydride ions (i.e. two protons plus two electrons) by succinate dehydrogenase to ubiquinone; other flavoproteins can similarly oxidize fatty acyl-CoA or β-hydroxybutyrate or α-glycerophosphate. The protons are initially released to the intermembrane space, and the electrons are transferred by the appropriate flavoprotein to ubiquinone, from which they are transferred singly in sequence to cytochrome *b*, cytochrome c_1, cytochrome *c*, and cytochrome a/a_3 at which point they reduce molecular oxygen to promote formation of water with the protons that were formed earlier. Many other components are also involved. In tightly coupled mitochondria, the protons released to the intermembrane space reach the mitochondrial matrix (the space in which they react with molecular oxygen) by transfer through the inner mitochondrial membrane by the F_0F_1 complex of the mitochondrial ATPase (*see* **H^+-transporting ATP synthase**), with concomitant phosphorylation of ADP to ATP. *See also* **chemiosmotic coupling hypothesis**.

respiratory complex any of several groups of physically associated components of the **respiratory chain**. The concept arose during experiments to purify individual components, when it was found that membrane particles could be isolated each with a consistently characteristic composition. Four main complexes have been identified: complex I, which contains primarily NADH dehydrogenase; complex II, which contains succinate dehydrogenase; complex III, which contains cytochromes *b* and c_1; and complex IV, which contains cytochrome a/a_3 together with copper-containing proteins. Complexes I, II, and III all contain additionally a number of proteins rich in iron and sulfur. The F_o and F_1 subunits of the ATPase associated with the respiratory chain have been termed complex V (*see* **H^+-transporting ATP synthase**). *See also* **complex I, II, III, IV**.

respiratory control the regulation, in coupled mitochondria, of the rate of oxidative phosphorylation by the level of ADP. As the ADP level increases, and the ATP level falls, electron flow through the **respiratory chain** and coupled ATP synthesis are enhanced. The **respiratory control ratio**, or **respiratory control index**, represents the ratio of the rate of oxygen consumption of mitochondria in the presence of both substrate and ADP to the rate in the presence of substrate but the absence of ADP; i.e. the ratio of the rate in respiratory state 3 to respiratory state 4 (*see* **respiratory state**).

respiratory pigment any of a number of pigmented proteins, associated with respiratory processes, that derive their colour from a prosthetic group, usually heme in red proteins such as cytochrome *c*, or flavin nucleotides in flavoprotein dehydrogenases, which are yellow.

respiratory quotient *or* **respiratory ratio** *abbr*.: RQ; a ratio of the rate of carbon dioxide evolution by any cell, tissue, or organism to its rate of dioxygen uptake.

respiratory state *or* **state of the respiratory chain** any one of the possible steady states of the phosphorylating **respiratory chain** in mitochondria. In state 1 both ADP and respiratory substrates are lacking. State 2 is a 'standard state' in which ADP has been added to exhaust the endogenous respiratory substrate; in state 2′ substrate has been added to exhaust the endogenous ADP. In state 3, the 'active' state of rapid respiration, all required components are present and the respiratory chain itself is the rate-limiting factor. State 4, an anaerobic 'resting' state, is characterized by a low respiration rate. In state 5, only oxygen is lacking, the respiration rate then being at zero.

State	$[O_2]$	[ADP]	Substrate level	Respiration rate	Rate-limiting factor
1	>0	low	low	slow	ADP
2	>0	high	0	slow	substrate
2′	>0	low	high	slow	ADP
3	>0	high	high	fast	respiratory chain
4	>0	low	high	slow	ADP
5	0	high	high	0	O_2

respirometer an instrument for measuring the uptake of oxygen during incubation experiments. The **Barcroft apparatus** and the **Warburg apparatus** were examples of this type of instrument.

response the events brought about by a **stimulus**, especially in a cell, tissue, or organism. *See* **stimulus–response coupling**, **sensitization**, **desensitization**.

response coefficient *symbol*: *R*; an overall measure of the control exercised by a specific enzyme inhibitor, at its concentration, *I*, on the overall flux, *F*, of a multienzyme system. Hence,

$$R_I^F = (\partial F/F)/(\partial I/I)$$

or

R = fractional change in flux/fractional change in inhibitor.

A response coefficient can also be determined for the effect of *I* on the concentration of a metabolite *S*. Thus

$$R_I^S = (\partial S/S)/(\partial I/I)$$

It is the product of the **elasticity coefficient** and the **flux control coefficient**.

response element *abbr*.: RE; a DNA sequence (sometimes called a 'module') that is common to promoters/enhancers of genes whose expression is coordinately regulated (*see* **coordinate induction/repression**). Examples: the **estrogen response element** (ERE) has the consensus sequence GGTCANNNTG[A/T]CC; the glucocorticoid response element (GRE) has the consensus sequence TGGTACAAATGTTCT; the **heat-shock response element** (HSE) has the consensus sequence GNNGAANNTCCNNG; the **metal response element** (MRE) has the consensus sequence CGNCCCGGNCNC; the **serum response element** (SRE) has the consensus sequence CATATTAGG; and the **thyroid response element** (TRE), which is common to several enhancers, has the consensus sequence TGACTCA. RE-1 (*or* NRSE) is a conserved 21–23 bp response element present in neuron-specific genes. *See* **REST**.

response regulator part of a **two-component signal transduction system**. Response regulators of bacterial sensory transduction systems generally comprise a receiver module domain covalently linked to an effector domains. In the presence of an effector molecule, a **histidine sensor kinase** phosphorylates an aspartate residue in the receiver module. Effector domains include DNA binding and/or catalytic units that are regulated by phosphorylation of the receiver module.

response time the interval between initiation of a process and the commencement of the action that it induces.

responsiveness *(in physiology)* the ability of a cell, tissue, or organ to undergo a response. Maximal response normally corresponds to the healthy *in vivo* state, so that the degree of response is an indication of the integrity of the preparation. However, negative regulators may be removed during tissue preparation, thus giving enhanced activity *in vitro*.

REST *abbr. for* response element RE-1 silencing transcription factor; *other name*: neuronal restricted silencing factor (*abbr*.: NRSF). A transcription factor (116 kDa) that contains a central DNA-binding domain comprising eight zinc fingers and flanked by two repressor domains. It binds a 21–23 bp conserved response element called response element-1 (RE-1), or neuronal restricted silencing element (NRSE). This element is present in neuron-specific genes, and binding of REST represses the expression of such genes. The N-terminal domain of REST associates with a histone deacetylase and other proteins (depending on the genetic context). The C-terminal domain associates with a corepressor (called CoREST), which serves as a **molecular beacon** for the assembly of other components of the repressor machinery.

restin Reed–Sternberg cell intermediate filament-associated protein; *other name*: cytoplasmic linker protein-170 α-2 (*abbr*.: CLIP-170); a protein that is highly expressed in such cells in Hodgkin's lymphoma, and having a large coiled-coil α-helical domain similar to those in myosins.

resting potential the potential difference across the membrane of a cell in the unstimulated state. *See also* **membrane potential**.

resting state an inactive or unstimulated state, especially of a cell. *See also* **cell-division cycle**.

restricted DNA DNA that has been cut by a **restriction endonuclease** within a bacterium; bacteria are protected from the propagation within them of foreign DNA, usually viral DNA, by the possession of restriction endonucleases which degrade the invading DNA. Each nuclease recognizes a specific sequence of 4–8 nucleotides in the DNA. The cleaved sequences, where they occur in the genome of the bacterium itself, are protected from cleavage by methylation at the amino group of an adenine, or either the 5 position of a cytosine or the amino group of a cytosine. The newly replicated strand of the bacterial host DNA, which is protected from degradation by the methylated parent strand with which it forms a duplex, is modified before the next cycle of replication (*see* **restriction–modification system**). Such sequences in the viral DNA are usually not so methylated and hence are degraded first by the restriction enzymes and then by bacterial exonucleases. Invading DNAs are only rarely modified and enabled to reproduce in their new host. Its progeny are, however, no longer modified in the way that permits them to propagate. *See also* **host-controlled modification**.

restricted phage *or* **restricted bacteriophage** *see* **restricted virus**.

restricted virus a virus whose host range is limited by **host-controlled modification** so that when it infects a related but nonidentical host cell its DNA is degraded by the new host cell's **restriction endonucleases**.

restriction *(in molecular biology)* the action or use of **restriction endonucleases**. *See also* **restrictive**.

restriction analysis *another term for* **restriction mapping**.

restriction endonuclease *or* **restriction enzyme** *or* **restriction nuclease** any of a group of enzymes, produced by bacteria, that cleave molecules of DNA internally at specific base sequences. They therefore act to 'restrict' the replication of foreign, usually viral, DNA entering the bacterial cell (*see* **restricted DNA**). Some of them also methylate the host bacterial DNA to protect it from degradation. There are three known types of restriction enzymes. Types I and III each carry activity for both the endonuclease and methylase function whereas type II enzymes do not carry the methylase activity. Type I enzymes cleave the DNA at a random site located at least 1000 bp from the recognition sequence, type III do so 24–26 bp distant from the recognition site. In contrast, type II enzymes cleave DNA at specific sites within the recognition sequence. This makes type II enzymes indispensable for DNA manipulation. Around 2500 species of type II restriction enzymes with some 200 differing sequence specificities have been characterized. A restriction endonuclease is named by a three-letter abbreviation of the species from which it was originally isolated, followed by letters and/or numerals indicating the strain or characteristic, e.g. *Eco*RI is derived from a strain of *Escherichia coli* with an R (drug resistance) marker and is enzyme I thus described.

Type I (EC 3.1.21.3) restriction and modification enzymes are complex multifunctional systems that require ATP, *S*-adenosylmethionine, and Mg^{2+} as cofactors; in addition to their endonucleolytic and methylase activities, they are potent DNA-dependent ATPases. The subunit composition, comprising three subunits designated R, M, and S, is similar to that of ATPases. They catalyse the endonucleolytic cleavage of DNA to give random double-stranded fragments with terminal 5′-phosphates; ATP is simultaneously hydrolysed.

Type II enzymes have activity as site-specific deoxyribonucleases (EC 3.1.21.4), which catalyse the endonucleolytic cleavage of DNA to give specific double-stranded fragments with terminal 5′-phosphates; Mg^{2+} is a cofactor. Such enzymes are the basis of **restriction mapping**.

Type III enzymes have activity as site-specific deoxyribonucleases (EC 3.1.21.5). The protein has two subunits, products of the *res* (from 'restriction') and *mod* (from 'modification') genes; these are, respectively, responsible for binding the system-specific DNA recognition site and the methylation of one of the adenosyl residues in the recognition site. The more widely used restriction enzymes appear in the body of the dictionary and their activity is indicated by the following convention. As an example *AatII* has the recognition sequence GACGT↑C meaning that the sequence on one strand is 5′-GACGTC-3′and that the cleavage site is on the 3′ side of the T preceding the ↑ symbol. This is thus an example of an enzyme that will result in restriction fragments with a 3′ 'sticky end'. Some enzymes have an ambiguous recognition sequence, e.g. *Acc*I, and for these this dictionary uses a convention of square brackets. Thus the sequence in this example is GT↑[AC][GT]AC meaning that the third nucleotide is either A or C and the fourth is either G or T. A different type of ambiguity is illustrated by Bgl.

restriction enzyme *an alternative name for* **restriction endonuclease**.

restriction fragment a fragment of DNA produced by the action of a **restriction endonuclease**. It usually refers to the product of a type II enzyme that recognizes specific base sequences in double-helical DNA and cleaves both strands of the duplex at specific sites.

restriction fragment length polymorphism *abbr*.: RFLP; **polymorphism** within a population of organisms of the size of the fragments of DNA produced by the action of a type II **restriction endonuclease**. It results from a corresponding polymorphism of **restriction sites** in the genome, due to slight differences in base sequence between individual members of the population. RFLP is exploited in constructing physical maps of the genome, and widely used for localizing specific genes and detecting genetic differences between closely related individuals. Such polymorphisms can be detected by Southern blotting using a DNA probe for a particular locus to reveal differences in the sizes of fragments produced by a particular endonuclease. The analysis of restriction fragments can reveal the presence of a mutation that may itself cause disease or be closely linked to one that does; for example, genetic diseases such as sickle-cell anemia, cystic fibrosis, and Huntington disease can be detected by RFLP analyses. *See* **restriction mapping**.

restriction map a pattern obtained as the result of **restriction mapping**.

restriction mapping the use of type II **restriction endonucleases** to cleave genomic or other DNA to produce a characteristic pattern of fragments. The fragments are resolved by gel electrophoresis and visualized. Every DNA molecule produces a unique pattern, which accords with the specificity of the particular restriction enzyme. By comparing the patterns obtained from two or more different DNAs, differences between closely similar DNA molecules, such as arise from mutations, may be detected. The use of DNA probes, such as cDNA, to identify particular fragments may often be of value. By using restriction enzymes singly and in pairs it is possible to deduce from the sizes of resulting fragments the order of the restriction sites on the DNA and the distances between them.

restriction–modification system any system whereby host DNA is methylated to render it resistant to the action of the cell's **restriction endonucleases** (*see* **restricted DNA**); methylation involves the adenine or cytosine residues at the restriction sites. Several enzymes are implicated: (1) EC 2.1.1.72; *recommended name*: site-specific DNA-methyltransferase (adenine-specific); *other names*: N-6 adenine-specific DNA methylase; modification methylase; it catalyses a reaction between *S*-adenosyl-L-methionine and DNA adenine to form S-adenosyl-L-homocysteine and DNA 6-methylaminopurine. (2) EC 2.1.1.73; *recommended name*: site-specific DNA-methyltransferase (cytosine-specific); *other names*: C-5 cytosine-specific DNA methylase; modification methylase; it catalyses a reaction between *S*-adenosyl-L-methionine and DNA cytosine to form S-adenosyl-L-homocysteine and DNA 5-methylcytosine.

restriction negative describing an organism that does not contain any **restriction endonuclease**.

restriction site a sequence of bases in a DNA molecule that is recognized by a **restriction endonuclease**.

restrictive 1 describing a strain or line of cells that does not permit the replication of a particular viral DNA, and is thus resistant to infection. **2** describing a set of conditions, such as a temperature range, in which a mutant phenotype is expressed, thus limiting the growth of the organism or causing its death. *Compare* **permissive**. *See also* **conditional lethal mutation**, **temperature-sensitive mutation**.

restrictive conditions *see* **conditional lethal mutation**.

restrictive temperature *see* **temperature-sensitive mutation**.

restrictocin an antitumour polypeptide (16 kDa) from *Aspergillus* spp. It cleaves the large RNA of the eukaryotic 60S ribosomal subunit and inhibits protein synthesis in picornavirus-infected cells.

resveratrol a stilbene **phytoalexin** produced by the grapevine and present in the skin of red grapes, red wine, and other plant sources. It is a potent antioxidant and claims have been made for its antitumour activity.

RET *abbr. for* rearranged during transfection; a human transforming oncogene derived through fibroblast transfection with T-cell lymphoma DNA. It encodes a receptor-tyrosine kinase present in the central and peripheral nervous systems. Several isoforms are produced by alternative splicing. RET is recruited by GPI-anchored membrane proteins specific for the structurally related secreted proteins glial cell-derived neurotrophic factor, neurturin, and persephin. It signals through the adaptor protein GRB-19. Activating mutations in RET are associated with multiple endocrine dysplasia, and inactivating mutations with Hirschsprung disease.

retentate *or* **dialysis residue** *or* **residue** *(in* **dialysis***)* the moiety of the dialysed material that has not traversed the membrane; the liquid containing this moiety (which may or may not still be entirely in solution). Some authorities prefer the term **nondiffusible material**.

retention coefficient *(in column chromatography)* the ratio of the **void volume** to the **elution volume** for a specific solute. It is a measure of the partition of the solute between the column material and the solvent, and is independent of column size.

retention time the time taken by a compound to traverse the length of a **gas–liquid chromatography** column. The retention time is a characteristic of each compound under defined conditions. It can be used to aid in identification within a series of homologues, e.g. fatty acids, which are characterized by their **carbon number** derived from the retention time.

retention volume a parameter of liquid chromatography, related to the volume at which each compound elutes under defined conditions.

retGC-1 *abbr. for* retinal guanylate cyclase 1. *See* **guanylate cyclase**.

RETGC protein *abbr. for* retinal guanylyl cyclase protein; *other name*: photoreceptor-specific membrane protein; either of two type I integral membrane proteins (RETGC1 and RETGC 2) of the retina that contain an N-terminal ligand-binding region, a transmembrane helix, an intracellular protein kinase homology domain, and a guanylyl cyclase domain. They form heterodimers, do not bind natriuretic peptides, but are activated by retinal guanylyl cyclase activator proteins (GCAP1 and GCAP2) that belong to the calmodulin family. Mutations in the RETGC1 gene cause Leber's congenital amaurosis.

reticulate 1 *or* **reticular** resembling a net; in the form of a network. **2** to create in the form of a net or network. **—reticulation** *n.*

(*S*)-reticuline a benzoisoquinoline that is the metabolic precursor of several tetrahydrobenzylisoquinoline alkaloids including (from *Papaver somniferum*): codeine, noscapine, papaverine, and morphine. It is derived from two molecules of tyrosine and three molecules of *S*-adenosylmethionine, which contribute their methyl groups.

reticulocalbin a Ca^{2+}-binding luminal protein of the endoplasmic reticulum. It has six **EF-hands**, a 20-residue N-terminal **signal sequence**, and the C-terminal sequence **HDEL**.

reticulocyte an immature **erythrocyte** that can synthesize protein, ≈90% being hemoglobin. It retains intracellular organelles, including mitochondria, and histologically stains for the presence of ribosomes. The name derives from the reticulate appearance of the stained cells.

reticulocyte lysate the preparation obtained by suspending **reticulocytes** in distilled water so that the cells are lysed by osmotic shock.

The reticulocytes are usually obtained from rabbits in which **reticulocytosis** has been induced by the administration of phenylhydrazine. The residual RNA is usually removed by the addition of a ribonuclease that is calcium-dependent and is thereby inactivated by the addition of EDTA. Such a lysate is often used for the *in vitro* translation of added mRNA.

reticulocytosis enhanced levels of reticulocytes in the blood, often due to experimentally-induced increased production. *See also* **reticulocyte lysate**.

reticuloendothelial system *a former name for* **mononuclear phagocyte system**.

reticulum 1 the **endoplasmic reticulum**, a netlike structure of membranes found in the cytoplasm. **2** the most anterior chamber of the ruminant stomach.

retina the light-sensitive layer lining the inside of the posterior wall of the eye in vertebrates and some classes of molluscs. The inner nervous layer of the vertebrate retina is transparent and contains photoreceptive **cone cells** and/or **rod cells** together with their associated nerve cells and fibres, glia, and blood vessels; the outer layer, next to the choroid, is darkly pigmented and prevents back-reflection of light.

retinal 1 pertaining to the retina. **2** *the recommended trivial name for* (2*E*,4*E*,6*E*,8*E*)-3,7-dimethyl-9-(2,6,6-trimethylcyclohex-1-en-1-yl)nona-2,4,6,8-tetraen-1-al; *other names*: retinal$_1$; retinaldehyde; vitamin A aldehyde; retinene. A compound that plays an important role in the visual process in most vertebrates (*compare* **3,4-didehydroretinal**). In the retina this (all-*E*)-isomer, all-*trans*-retinal, is converted by **retinal isomerase** to its (2*E*,4*Z*,6*E*,8*E*)-stereoisomer, 11-*cis*-retinal, which then combines (as a Schiff's base) with an opsin to form (in cone cells) **iodopsin, porphyropsin, or cyanopsin,** or (in rod cells) **rhodopsin**. Interaction with a photon brings about dissociation of the retinal from the opsin to produce all-*trans*-retinal, thereby completing the visual cycle. Retinal is formed in the retina by enzymic oxidation of **retinol**; in addition, most vertebrates can convert dietary *α*-, *β*-, and *γ*-carotenes to retinal by oxidative cleavage of the polyprenyl chain at its midpoint. [*Note*: (1) The numbering system of the systematic name is different from that of the trivial name, the latter following the rules used for carotenoids. (2) The fuller name **retinaldehyde** is recommended if confusion with def. 1 may occur.]



all-*trans*-retinal

retinal$_1$ *(sometimes) an alternative name for* **retinal** (def. 2) (especially to distinguish it from **retinal$_2$**; not recommended).

retinal$_2$ *(sometimes) an alternative name for* **3,4-didehydroretinal** (especially to distinguish it from **retinal$_1$**; not recommended).

retinal cone *see* **cone cell**.

retinaldehyde *see* **retinal**.

retinal isomerase EC 5.2.1.3; *systematic name*: *all-trans*-retinal 11-*cis-trans*-isomerase; *other name*: retinene isomerase; an enzyme that catalyses the conversion of all-*trans*-retinal to 11-*cis*-retinal. *See also* **retinal** (def. 2).

retinal rod *see* **rod cell**.

retinene *or* **retinene$_1$** *an alternative name for* **retinal** (def. 2) (not recommended).

retinene$_2$ *an alternative name for* **3,4-didehydroretinal** (not recommended).

retinene isomerase *an alternative name for* **retinal isomerase**.

retinitis pigmentosa a relatively common genetic disorder which in humans affects 1 in 4000 people and is caused by the premature death of photoreceptors. The result is progressive night blindness, contraction of the visual field and finally complete loss of sight. One form of autosomal dominant disease results from an abnormality on chromosome 3. In this, there is a single amino-acid substitution in the **rhodopsin** molecule caused by a base transversion of C to A, which results in the change of a proline to a histidine residue at position 23 in the **opsin** molecule, causing the characteristic retinal degeneration. Another severe form of the disease, affecting up to around 20% of some populations, is X-linked; it usually becomes manifest within the first two decades of life and progresses to blindness within 10–20 years. The gene, named *RPGR*, for this form has now been found on the short arm of the X-chromosome. The predicted 90 kDa protein product of the *RPGR* gene bears significant homology to the **RCC1 family**.

retinoate 1 the anion of **retinoic acid**. **2** any salt or ester of retinoic acid.

retinoblastoma a childhood cancer of the developing retina. The offspring of surviving victims have a high incidence of this disease as well as several other types of malignancies. Retinoblastoma is associated with the inheritance of a copy of chromosome-13 from which a particular segment has been deleted. It develops through a mutation in a retinoblast (a retinal precursor cell). The affected chromosomal segment contains the ***RB*** gene which specifies a factor that restrains uninhibited cell proliferation. Thus the *RB* gene is a **tumour suppressor gene**. *See also* **retinoblastoma protein**.

retinoblastoma protein *abbr.*: pRb; the product of the retinoblastoma gene, **RB**. pRb is a 105 kDa DNA-binding protein that is localized in the nucleus of normal retinal cells, but absent in **retinoblastoma** cells. The protein is phosphorylated in the cell cycle by protein kinase **CDC2**. It appears that the interaction of pRb with various **transcription factors** suppresses cellular proliferation.

retinoic acid *the recommended trivial name for* (2*E*,4*E*,6*E*,8*E*)-3,7-dimethyl-9-(2,6,6-trimethylcyclohex-1-en-1-yl)nona-2,4,6,8-tetraenoic acid; *other names*: **tretinoin**; vitamin A acid; it is formed from **retinal** by enzymic oxidation in kidney and other tissues, and is active in preventing some of the symptoms of vitamin A deficiency. It is a morphogen and regulator of differentiation during embryogenesis. *See* **retinoic acid receptor**, **vitamin A**.



all-*trans* form

retinoic acid orphan receptor *an alternative name for* **retinoid receptor**.

retinoic acid receptor a nuclear receptor for **retinoic acid** that mediates its effects on cells. These receptors bind retinoic acid and directly regulate gene expression. The proteins belong to the steroid/thyroid/retinoic acid family of nuclear receptors for hormones. The ligand-binding domain is in the C-terminal region, the zinc-finger DNA-binding domain in a central region, and a function-modulating domain in the N-terminal region. Binding of hormone induces changes in receptor conformation that control transcriptional activation and repression, and also regulates homo- or heterodimerization. In the absence of ligand, these receptors repress basal gene expression, probably through co-repressor proteins. α, *β*, *γ* and *δ* types of receptor are known.

retinoid any isoprenoid, whether naturally occurring or not, that contains or is derived from four prenyl groups linked in a head-to-tail manner. All retinoids may formally be derived from a monocyclic parent compound with 20 carbon atoms containing five carbon–carbon double bonds and a functional group at the terminus of its acyclic moiety.

retinoid receptor (*abbr.*: RXR) *or* **retinoic acid orphan receptor** a nuclear receptor that binds more tightly to other retinoids than to retinoic acid. Three isoforms (α, β, and γ) are known. Phytanic acid binds to all three. Retinoid receptors form heterodimers with **RAR** or with **PPARs**, and are widely distributed in brain and spinal cord.

retinol *the recommended trivial name for* (2*E*,4*E*,6*E*,8*E*)-3,7-dimethyl-9-(2,6,6-trimethylcyclohex-1-en-1-yl)nona-2,4,6,8-tetraen-1-ol; *other names*: vitamin A; vitamin A alcohol; axerophthol. The predominant form of **vitamin A** in higher vertebrates and marine fishes (*compare* **3,4-didehydroretinol**). It is stored primarily in the liver, mostly as the ester, retinyl palmitate.



all-*trans* form

retinol-binding protein a protein, secreted by liver, that binds retinol and as a homodimer forms a complex with transthyretin in plasma. The crystal structure shows eight antiparallel beta strands, which form a retinol-binding pocket.

retinoyl the acyl group formally derived from **retinoic acid**.

retinyl the alkyl group formally derived from **retinol** by loss of its hydroxyl group.

retro+ *prefix* signifying backwards, or in the reverse direction.

retroendocytosis the process by which some particles, e.g. low-density lipoproteins, are released, after receptor-binding and endocytosis, back into the medium rather than being degraded within lysosomes.

retrogene a segment of DNA that has arisen by reverse transcription of the genetic material in an RNA virus (**retrovirus**) and incorporation of the DNA so formed into the host cell's genomic DNA.

retrogradation the spontaneous irreversible change of a liquid colloidal solution to an insoluble or gelled state. The term is used especially of aqueous amylose solutions in which microcrystalline precipitates of aligned, hydrogen-bonded amylose molecules occur on standing.

retrograde **1** moving backwards; reverse or inverse; tending towards a former state or condition; deteriorating. **2** to move backwards or in reverse, as in retrograde transport.

retrogress to move backwards or in a less favourable direction; to deteriorate or degenerate. —**retrogression** *n.*; **retrogressive** *adj.*

retroinhibition *an alternative name for* **feedback inhibition**.

retropepsin EC 3.4.23.16; a **pepsin**-type endopeptidase from **HIV** that catalyses the hydrolysis of Xaa-|-Xbb bonds, where Xaa is a hydrophobic residue, and Xbb is variable, but often is Pro. It is part of the polyprotein product of the ***pol*** gene.

retroposon *or* **retrotransposon** a **transposable element** that uses a mechanism indistinguishable from part of a retroviral life cycle. Retroposons are present in many organisms, such as yeast, *Drosophila*, and mammals. A good example is the Ty1 element of yeast: after the formation of a double-stranded DNA by **reverse transcriptase** it is integrated into a random site on the chromosome.

retroregulation the regulation of translation of messenger RNA (mRNA) by a sequence that is downstream of the region undergoing translation. For example, an mRNA of phage lambda carrying the sequence of gene *int* is not normally translated; mutation in a site called *sib*, located downstream of the *int* coding sequence, allows translation of the *int* mRNA.

retrotransposon *an alternative name for* **retroposon**.

Retrovir *see* **zidovudine**.

retroviral oncogene *see* **oncogene**, **retrovirus**.

retrovirus *or* **ribodeoxyvirus** *or* **RNA–DNA virus** any virus belonging to the family Retroviridae. This comprises single-stranded RNA animal viruses whose genome is diploid, consisting of two copies of the RNA, which is transcribed by the virion-associated enzyme **reverse transcriptase** into DNA. This double-stranded DNA, or **provirus**, can then integrate into the host genome and be passed from parent cell to progeny cell as a component of the host genome. The virion is an enveloped, roundish particle, ≈100 nm in diameter, with a helical nucleocapsid containing 6 MDa of RNA (in two identical molecules) joined to their 5′ ends and hydrogen-bonded into loops (70S RNA), plus small (45S) RNA from the host. The genome is flanked by long terminal repeat sequences and comprises at least three genes: *gag*, which encodes the inner capsid protein; *pol*, which codes for a polyprotein containing **retropepsin**, ribonuclease H (*see* **ribonuclease**), and **reverse transcriptase**; and *env*, which codes for the spikes on the envelope. A subfamily of retroviruses, known as the Oncovirinae (or the RNA tumour viruses), contain an additional **oncogene**, which confers the ability to form tumours in the host. These oncoviruses include the Rous sarcoma virus and other leukosis viruses of birds, and viruses causing leukemia in various mammals (not in humans). They have also been called **oncornaviruses**, **rousviruses**, and **leukoviruses**. Other subfamilies include the Spumavirinae (spumaviruses) and the Lentivirinae (lentiviruses); **HIV** is a member of the latter. The retroviruses are in class VI of the **Baltimore classification**.

Rett syndrome *see* **methylCpG-binding protein 2**.

reversal an evolutionary change that results in a derived character state reverting to its ancestral state.

reverse cholesterol transport the efflux of cholesterol (usually paralleled by efflux of phospholipid) from cells. It occurs, via a specific ABC transporter (which is defective in Tangier disease), onto high-density lipoprotein (HDL) particles bound to the cell surface. The cholesterol is eventually delivered to the liver. The process accounts for the antiatherogenic properties of HDL.

reverse dialysis a technique for the concentration of macromolecules in solution. The (dilute) solution is placed in a bag made of a semipermeable material, through which the macromolecules cannot pass but water and other small molecules can. The bag is placed in a bed of dry water-soluble polymer (which cannot enter the membrane) such as polyethylene glycol. Water, together with other small molecules, is then drawn out of the bag into the external phase until equilibrium is reached, thereby concentrating the solution of macromolecules in the bag. *Compare* **dialysis**.

reversed phase *or* **reverse phase** a system used in **adsorption chromatography** (often thin-layer or high-pressure liquid chromatography), in which the **stationary phase** consists of a material with a hydrophobic surface. In such a system, molecules migrate in order of polarity, the most polar migrating fastest. In column chromatography, mobile phases are used in a sequence commencing with more polar solvents and proceeding in decreasing order of polarity, the reverse of the sequence used in normal phase chromatography. The stationary phase often consists of silicic acid in which all hydrophilic groups are masked by silanization.

reversed rocket immunoelectrophoresis a variant of **rocket immunoelectrophoresis** in which antibodies are forced by electrophoresis through antigen-containing agarose gel, the heights of the 'rockets' so formed being related to the antibody concentrations. It is useful for titre determinations in large series of antibody samples.

reverse genetics *another name for* **positional cloning.** A term coined to describe the study of the biological consequences to an organism of artificial alteration of its DNA. The changes may be either gross (e.g. deletion, insertion, or transposition of segments of DNA effected by recombinant DNA technology) or limited to specific loci (e.g. base substitution through site-directed mutagenesis).

reverse gyrase an ATPase enzyme with a **DNA helicase**-like domain and a type-I **(DNA) topoisomerase** in the same protein. It is able to induce positive supercoiling into DNA, a property of DNA that is found only in bacteria that express this enzyme.

reverse mutation *or* **back mutation** a heritable change in a mutant gene that restores a nucleotide sequence to that which obtained prior to mutation. *Compare* **reversion**.

reverse osmosis the pressure-induced flow of solvent through a semipermeable membrane in a direction that enhances any existing difference in the activities (or concentrations) of the nonpermeant solutes on the two sides of the membrane (*compare* **osmosis**). The principle can be used in the preparation of purified water from tap water or sea water.

reverse phase *see* **reversed phase**.

reverse pinocytosis *see* **exocytosis**.

reverse transcriptase EC 2.7.7.49; *recommended name*: RNA-directed DNA polymerase; *systematic name*: deoxynucleoside-triphosphate:DNA deoxynucleotidyltransferase (RNA-directed); *other names*: DNA nucleotidyltransferase (RNA-directed); revertase. A DNA polymerase enzyme, found particularly in retroviruses and possibly in normal animal cells, that uses either DNA or RNA as a template. It catalyses a reaction between a deoxynucleoside triphosphate and DNA_n to form pyrophosphate and DNA_{n+1}; this protein also has ribonuclease H (RNase H) activity. When the single-stranded RNA of the retrovirus enters a cell, the enzyme first makes a DNA copy of one of the **long terminal repeats** of the viral genomic RNA strand using a tRNA as a primer. The stretch of RNA used as a template is then digested by the RNase H activity of the enzyme, releasing the newly synthesized stretch of DNA, which then pairs with a complementary stretch of viral RNA to form a DNA–RNA hybrid. This heteroduplex is then used by the same enzyme to make a double-stranded DNA, which circularizes and integrates into a host cell chromosome. Reverse transcriptase lacks a proofreading exonuclease function and is highly error prone. It can thus evolve even within a single patient, and this interferes with long-term therapy. Reverse transcriptase is used *in vitro* to make cDNA from mRNA in a reaction requiring deoxynucleoside triphosphates (dNTPs) and a primer such as **oligo dT**(12–18). Enzymes from avian myeloblastosis virus (AMV) and Moloney murine leukemia virus (MMLV) are suitable for this purpose. **Telomerase** is a template-bearing reverse transcriptase.

reverse transcription the process carried out by **reverse transcriptase**. *See also* **transcription**.

reverse turn *(in protein structure)* a structural feature that allows the polypeptide chain to turn back through about 180°. *See also* **beta bend.**

reversible competitive antagonist *(in pharmacology)* an antagonist for which the rate of dissociation from its receptor is relatively high, such that by increasing the concentration of an agonist the receptor **occupancy** (def. 2) of the antagonist falls. At sufficiently high concentrations of agonist a maximal tissue response can be obtained, even in the presence of the antagonist, such that the extent of antagonism is determined by the relative concentrations of agonist and antagonist.

reversible inhibition (of an enzyme or other system) a type of inhibition that occurs when the equilibrium between free inhibitor and the inhibitor–enzyme (or system) complex lies sufficiently far towards the free inhibitor state for the inhibitor to be readily removed, leaving an active enzyme (or system).

reversible reaction a reaction in which the **equilibrium constant** is such that the reaction can be made to proceed at a detectable rate in either direction under appropriate conditions.

reversion the restoration, by a second mutation, of the genomic base sequence of a mutant virus or organism to that of the parental strain. Less strictly, any return to the original **phenotype**. *See also* **back mutation**, **reverse mutation**.

reversion frequency the proportion of the total number of cells in a population that undergo **reversion**.

reversion spectroscope a **spectroscope** in which two spectra alongside each other, one of which is reversed by optical means, are formed by the entering light. The two spectra may be moved longitudinally relative to each other by moving a micrometer screw. If two absorption bands are aligned when a particular substance, e.g. oxyhemoglobin, is viewed, the amount by which the screw has to be turned to align the same band when a mixture of the same substance and another with a similar absorption spectrum, e.g. carbonmonoxyhemoglobin, is viewed is related to the proportion of the second substance present.

revertant **1** a mutant that has partially or completely regained the wild-type phenotype. **2** a gene that has undergone **reversion**.

revertase *an alternative name for* **reverse transcriptase**.

rexinoid a synthetic agonist of **retinoid X receptors**.

Reye syndrome an acute noninflammatory encephalopathy in children that is associated with fatty degeneration of the liver and hyperammonemia. Many cases are caused by inborn errors of fatty acid oxidation. There is strong epidemiological evidence for an association with salicylate ingestion and influenza B virus infection. [After R.D.K. Reye (1912–77), Australian pathologist.]

Reynolds number *symbol*: *Re*; a nondimensional parameter of fluid motion through a cylindrical tube or past an obstruction. It is given by the expression vl/ν, where l has the dimensions of length, v is the fluid's velocity, and ν is the kinematic viscosity. In general, low Reynolds numbers show that viscous forces predominate in controlling the flow, while high Reynolds numbers indicate that inertial forces are more important. [After Osborne Reynolds (1842–1912), Irish physicist and engineer.]

RF *abbr. for* **1** release factor. **2** replicative form.

R factor **1** *abbr. for* resistance factor (*see* **resistance plasmid**). **2** *(formerly) abbr. for* release factor.

RFC *abbr. for* reduced folate carrier.

rfDNA *see* **DNA**.

RFLP *abbr. for* restriction fragment length polymorphism.

R form **1** *abbr. for* relaxed form (of a protein). **2** **R-form** (hyphenated) *abbr. for* rough form; describing bacterial colonies with a jagged perimeter.

RFX *abbr. for* regulatory factor for X box; a DNA-binding heterotrimeric protein complex that binds the X box (a nucleotide sequence within the 150 bp response element) of the promoters of MHC class II genes. The three subunits are RFX5 (75 kDa), RFXAP (36 kDa), and **RFXANK**, and the protein forms higher-order complexes with proteins that bind other regions within the response element. Mutations in any component of the RFX complex cause MHC class II deficiency in humans.

RFXANK a 33 kDa protein component of the **RFX** complex. It contains three ankyrin repeats and is required for efficient DNA-binding and transcriptional activation of MHC class II gene promoters by the RFX complex.

RGD the tripeptide Arg–Gly–Asp, which is present in **fibronectin** and some other extracellular matrix proteins and is recognized by some **integrins.**

R gene *abbr. for* resistance gene; any gene in plants that imparts resistance against viruses, bacteria, fungi, aphids, or nematodes. Examples are known in potato, tobacco, flax, tomato, maize, barley, and sugar beet, among others. Many of the proteins (**R proteins**) they encode contain leucine-rich repeats, which mediate protein–protein interactions. Some also contain leucine zipper, coiled-coil, or other sequences. Many R proteins are cytoplasmic, and some are transmembrane.

RGG box a peptide sequence (20–25 amino acids) present in some proteins, often in association with the RNA-binding domains found in FMR1. It contains repeats of Arg–Gly–Gly, often interspersed with aromatic residues.

RGK-2 *see* **tonin**.

RGS protein *abbr. for* regulator of G-protein signalling protein; any protein containing a conserved sequence (≈120 amino acids) that binds the α subunit of a trimeric **G-protein** and enhances its GTPase activity; i.e. they are GTPase-activating proteins (GAPs). There are over 25 in mammals. They frequently contain other homology domains that increase the range of proteins that they bind. RGS-PX1 regulates $G_{S\alpha}$, RGS7 putatively binds the C-terminal region of polycystin-1, RGS9 regulates $G_{T\alpha}$ (**transducin**), and RGS12 regulates $G_{O\alpha}$.

rH the negative logarithm of the concentration (expressed as pressure in atmospheres) of hydrogen gas in equilibrium with a redox system; i.e.

$$\mathrm{rH} = -\log[\mathrm{H_2}].$$

Also,

$$\mathrm{rH} = 2(E_hF)/(RT\ln 10) + \mathrm{pH},$$

where F is the Faraday constant, R the gas constant, T the thermodynamic temperature, and E_h the **redox potential** at the pH of the system under study.

Rh **1** *abbr. for* Rhesus factor. **2** *symbol for* rhodium.

Rha *symbol for* rhamnose.

Rhabdoviridae a family of single-stranded RNA viruses infecting vertebrates, arthropods, amoebae, and plants. The virions are 70–80 nm elongated particles, with a lipid envelope. They contain negative-strand RNA together with RNA-dependent RNA polymerase, which transcribes the genome directly to mRNA – they are class IV viruses in the **Baltimore classification**. Rhabdoviruses are usually transmitted by arthropods; they include the plant rhabdoviruses, the vesiculoviruses (e.g. the vesicular stomatitis virus of cattle), the lyssaviruses, which include the rabies virus, and sigma virus of *Drosophila*. [From Greek *rhabdos*, rod.]

rhabdovirus *see* **Rhabdoviridae**.

L-rhamnosamine 2-amino-2,6-dideoxy-L-mannose; an amino sugar that occurs in some bacterial lipopolysaccharides.

rhamnose *symbol*: Rha; 6-deoxy-L-mannose; a monosaccharide (hexose) that occurs commonly in plant glycosides, in polysaccharides of gums and mucilages, and in bacterial polysaccharides; it also occurs in some plant cell-wall polysaccharides, and in flavonoids. Free rhamnose is found in some plants. The D-enantiomer occurs in some bacterial capsular polysaccharides. *See also* **L-rhamnose isomerase**.

L-rhamnose isomerase EC 5.3.1.14; *systematic name*: L-rhamnose ketol-isomerase; an enzyme that catalyses the interconversion of L-rhamnose and L-rhamnulose. It initiates the catabolism of rhamnose.

rhamnulose 6-deoxyfructose; it is formed by **L-rhamnose isomerase**.

rheology the science concerning the deformation and flow of matter. —**rheological** *adj.*

rheoseme *or* **flow signal** a chemical messenger or transmitter substance (other than a neurotransmitter) carried from a site of generation to site of action within a cell (e.g. a neuron) by cytoplasmic flow; a translocated **bioseme** or **second messenger**.

rheostat a device in which a controllable resistance is introduced into an electrical circuit to vary the output to permit an apparatus to be regulated within desired limits.

Rhesus factor *abbr.*: Rh; a protein associated with the rhesus (Rh) system of blood groups in humans. The system was so designated as a result of the finding that rabbit and guinea-pig antibodies raised against erythrocytes from *Macacus rhesus* monkeys agglutinated erythrocytes from 85% of the random human population. Initially, an antigen, designated D, was isolated from the erythrocytes of Rh-positive individuals; those lacking D were classified Rh-negative. Subsequently, another antigen, LW (Landsteiner-Weiner), was identified, which, although phenotypically similar to D, is encoded by a gene that segregates independently from *Rh*. C and E antigens have also been found. The antigenic determinant is associated with the protein structure. In hemolytic disease of the newborn resulting from rhesus incompatibility, antibodies from a Rh-negative mother, often formed during the birth of a previous Rh-positive child whose blood has entered the mother's bloodstream, pass across the placenta and cause destruction of fetal red cells.

rheumatoid factors **autoantibodies** to the IgG Fc region, also known as antiglobulins, that are the hallmark of patients with rheumatoid **arthritis**.

rhinovirus any small RNA virus belonging to the Picornaviridae family, members of which are responsible for the common cold in humans, and foot-and-mouth disease in cattle.

Rhizobium a genus of soil bacteria whose members reside symbiotically in specialized root nodules of leguminous plants. The bacteria are active in **nitrogen fixation** providing the plant with organic nitrogen and obtaining carbon compounds in return. Many *Rhizobium* species contain plasmids that enable them to colonize their host plant species.

rhizomorph a stout, rootlike mass of hyphae, produced by some fungi, that serves to generate vegetative spread.

RH map *abbr. for* radiation hybrid map.

rho *symbol*: ρ (lower case) *or* P (upper case); the seventeenth letter of the Greek alphabet. For uses *see* **Appendix A**. *See also* **rho protein**, **Rho protein**.

Rhodamine any of a series of dyes based on 9-(2-carboxyphenyl)xanthine. Rhodamine 6G, *N*-[9-(2-carboxyethylphenyl)-6-(diethylamino)-3*H*-xanthen-3-ylidene]ethylethanamine, is used as a spray to reveal lipids as pink fluorescent spots after thin-layer chromatography, and as the isothiocyanate derivative as a label for proteins and nucleotides. Rhodamine 6G has λ_{max} excitation 525 nm and emission 555 nm.



Rhodamine 6G

rhodanese EC 2.8.1.1; *recommended name*: thiosulfate sulfur-transferase; *systematic name*: thiosulfate:cyanide sulfur-transferase; *other names*: thiosulfate cyanide transsulfurase; thiosulfate thiotransferase. An enzyme that catalyses the displacement of sulfite from thiosulfate by cyanide ion, forming sulfite and thiocyanate and thus detoxifying cyanide. It has two domains of closely similar conformation yet very different sequence. [From the use of rhodanate as a name for thiocyanate.]

rhodanid any **thiocyanate** produced by the metabolism of mustard-oil glycosides (glycosinolates) in damaged leaf tissues.

rhodium *symbol*: Rh; a silvery-white metallic transition element of group VIII of the (IUPAC) **periodic table**; atomic number 45; relative atomic mass 102.9. It occurs mainly in oxidation state III. A rare member of the platinum metals, it is resistant to nitric acid and aqua regia.

rhodniin a thrombin inhibitor found in the saliva of the blood-sucking reduviid bug *Rhodnius prolixus*.

rhodo+ *or (before a vowel)* **rhod+** *comb. form* indicating a red colour, or the odour of a rose. [From Greek *rhodos*, rose.]

rhodopsin *or* **visual purple** a brilliant purplish-red, light-sensitive visual pigment found in the rod cells of the retinas of most vertebrates (exceptions being freshwater and migratory fish, and some amphibians). It is a **7TM protein** similar to other members of the G protein-coupled receptor family. It consists of a rod-type **opsin** combined (as a Schiff's base) with 11-*cis*-retinal (*see* **retinal**). It has an absorption maximum at ~500 nm. *Compare* **porphyropsin**. A single amino-acid substitution in the rhodopsin molecule causes one form of **retinitis pigmentosa** in humans. *See also* **bacteriorhodopsin**, **halorhodopsin**, **slow-cycling rhodopsin**.

rho factor *an alternative name for* **rho protein**.

RhoGEF *abbr. for* Rho guanine nucleotide exchange factor; a protein that enhances the exchange of GDP for GTP in a **Rho protein** and contains a GEF domain (≈200 amino acids) followed by a pleckstrin homology domain. **FGD1 protein** is a RhoGEF for Cdc42.

RhoGTPase any of a subfamily of Ras-related GTPases that are involved in the assembly of actin microfilaments into stress fibres and in formation of the contractile ring during cell division. They have crucial roles in metazoan development because they regulate cell shape, adhesion, and migration. There are at least ten mammalian RhoGTPases (RhoA to RhoE; Rac1, Rac2, and RacE; Cdc42 and TC10), which share ≈50% homology and become prenylated at the C-terminal CAAX motif. They cycle between (active) RhoGTP and (inactive) RhoGDP forms, the relative proportions being regulated by **Rho guanine nucleotide-exchange factors** (RhoGEFs).

Rho guanine nucleotide exchange factor *see* **RhoGEF**.

rho protein *or (sometimes)* **rho factor** a bacterial ATP-dependent helicase that facilitates transcription termination. Binding of rho to the nascent RNA is followed by activation of rho's RNA-dependent ATPase activity, and release of the mRNA from the DNA template; it recognizes and binds to C-rich regions of the RNA transcript. In *Escherichia coli*, this protein is the site of action of the antibiotic bicyclomycin, which binds to rho protein and inhibits its ATPase activity. *Compare* **Rho protein**.

Rho protein a samll Ras-related GTPase (*see* **RAS**), involved in controlling the polymerization of actin into filaments, and subsequent organization. *RHOB* is an early response gene transiently induced in fibroblasts by platelet-derived growth factor, or epidermal growth factor; its over-expression can be tumorigenic. *Compare* **rho protein**.

RI *abbr. for* **1** refractive index. **2** ribonuclease inhibitor.

RIA *abbr. for* radioimmunoassay.

Rib *symbol for* ribose.

ribaric acid one of the **pentaric acids**. *See also* **aldaric acid**.

ribavarin A guanosine nucleotide analogue, 1-β-D-ribofuranosyl-1,2,4-triazole-3-carboxamide.Mainly used against syncytial virus in young children but also effective with **α-interferon** against **hepatitis C**. It is probable that the antiviral action is due to the monophosphate derivative competitively inhibiting inosine-5′-monophosphate dehydrogenase.

ribitol *or* **adonitol** a **pentitol** derived formally by reduction of the –CHO group of D- or L-ribose. It is a *meso* compound and does not require a D or L configurational descriptor. It occurs free in some plants and is a component of **riboflavin**.

ribitol teichoic acid a complex polymer of **ribitol** residues linked by phosphate groups, substituted by glucosyl or acetylglucosamine residues and ester-linked to D-alanine. It is found in the walls of Gram-positive bacteria.

ribo+ *comb. form* **1** of, relating to, or containing **ribose**, especially as opposed to deoxyribose. **2** containing a ribose residue linked through its anomeric carbon. It is used in **riboflavin**, inappropriately, for a ribitol residue.

ribo- *prefix (in chemical nomenclature)* indicating a particular configuration of three contiguous >CHOH groups (as found in the acyclic form of D- or L-ribose). *See also* **monosaccharide**.

ribocharin an acidic protein specifically associated with the granular component of the nucleolus and nucleoplasmic 65S particles. These particles contain the nuclear 28S rRNA, and may represent the precursor to the large ribosomal subunit.

ribodeoxyvirus any RNA virus that replicates via DNA; such viruses are usually known as **retroviruses**. *Compare* **deoxyribovirus**.

riboflavin *an alternative name for* **vitamin B_2**.

ribofuranosyl *an alternative term for* **ribosyl**.

ribonuclease *abbr.*: RNase *or (sometimes)* RNAase; any of a group of nuclease enzymes that cleave phosphodiester bonds in RNA. With the exception of RNase P, which is a **ribozyme**, they are all proteins. RNAses are classified into **exoribonucleases**, catalysing sequential cleavage of mononucleotides from either a free 5′ or 3′ terminus, or both, or **endonucleases**, cleaving bonds within the polyribonucleotide chain. Endonucleases, which can also cleave circular molecules of RNA, fall into further categories according to their specificity: EC 3.1.13, exoribonucleases producing 5′-phosphomonoesters; EC 3.1.14, exoribonucleases producing other than 5′-phosphomonoesters; EC 3.1.15, exonucleases active with either ribo- or deoxyribonucleic acids and producing 5′-phosphomonoesters; EC 3.1.16, exonucleases active with either ribo- or deoxyribonucleic acids and producing other than 5′-phosphomonoesters; EC 3.1.26, endoribonucleases producing 5′-phosphomonoesters; EC 3.1.27, endoribonucleases producing other than 5′-phosphomonoesters; EC 3.1.30, endonucleases active with either ribo- or deoxyribonucleic acids and producing 5′-phosphomonoesters; and EC 3.1.31, endonucleases active with either ribo- or deoxyribonucleic acids and producing other than 5′-phosphomonoesters. Ribonucleases include enzymes having mechanisms of (A) phosphotransferases, (B) phosphodiesterases, or (C) phosphorylases. In group C are polynucleotide phosphorylase and polynucleotide pyrophosphorylase. The feature of group A is the involvement of the 2′-OH group in an intramolecular attack at the adjacent phosphodiester bond, in addition to conferring specificity for one or more of the four bases. The nucleoside 2′:3′-cyclic phosphates are obligate intermediate products. In group B, a direct attack of water on the 3′:5′-phosphodiester bond is catalysed, so that this group includes the enzymes that hydrolyse both RNA and DNA and those that cleave diester bridges to form only 5′-nucleotide products. Thus group A may be classed as cyclizing and group B as non-cyclizing enzymes. The group A enzymes do not depend for their activity on divalent cations whereas the group B enzymes require Mg^{2+} or Ca^{2+}. Within each group there are many types, as described below.

Exoribonuclease II EC 3.1.13.1; *other name*: ribonuclease II; reaction: exonucleolytic cleavage in the 3′- to 5′-direction to yield 5′-phosphomononucleotides. **Exoribonuclease H** EC 3.1.13.2; reaction: exonucleolytic cleavage to 5′-phosphomonoester oligonucleotides in both 5′- to 3′- and 3′- to 5′-directions. **Poly(A)-specific ribonuclease** EC 3.1.13.4; reaction: exonucleolytic cleavage of poly(A) to 5′-AMP. **Yeast ribonuclease** EC 3.1.14.1; reaction: exonucleolytic cleavage to 3′-phosphomononucleotides.

Endoribonucleases cleave the polynucleotide internally. This first group (sub-subclass EC 3.1.26) produce exclusively 5′-phosphomonoesters. *Physarum polycephalum* ribonuclease EC 3.1.26.1; reaction: endonucleolytic cleavage to 5′-phosphomonoester. **Ribonuclease alpha** EC 3.1.26.2; reaction: endonucleolytic cleavage to 5′-phosphomonoester. **ribonuclease III** EC 3.1.26.3; *other names:* RNase O; RNase D; reaction: endonucleolytic cleavage to 5′-phosphomonoester. **Ribonuclease H** EC 3.1.26.4; *other names:* endoribonuclease H (calf thymus); calf thymus ribonuclease H; reaction: endonucleolytic cleavage to 5′-phosphomonoester; it acts on RNA–DNA hybrids (hence the H in the name) and is required for removing RNA from **Okazaki fragments**; *see also* **RNA-directed DNA polymerase**. **Ribonuclease P** EC 3.1.26.5; reaction: endonucleolytic cleavage of RNA, removing 5′-sequence of extra nucleotides from tRNA precursor; it is a **ribozyme**; *see* **RNase P**. **Ribonuclease IV** EC 3.1.26.6; *other names:* endoribonuclease IV; poly(A)-specific ribonuclease; reaction: endonucleolytic cleavage of poly(A) to fragments terminated by 3′-hydroxyl and 5′-phosphate groups. **Ribonuclease P4** EC 3.1.26.7; reaction: endonucleolytic cleavage of RNA, removing 3′-sequence of extra nucleotides from tRNA precursor. **Ribonuclease M5** EC 3.1.26.8; *other name*: 5S rRNA maturation nuclease; reaction: endonucleolytic cleavage of RNA, removing 21 and 42 nucleotides, respectively, from the 5′- and 3′-termini of a 5S rRNA precursor. **Ribonuclease M16** cleaves the 5′ and 3′ termini of a 16S rRNA precursor. **Ribonuclease M23** cleaves the 5′ and 3′ termini of a 23S rRNA precursor. **Ribonuclease (poly(U)-specific)** EC 3.1.26.9; reaction: endonucleolytic cleavage of poly(U) to fragments terminated by 3′-hydroxyl and 5′-phosphate groups. **Ribonuclease IX** EC 3.1.26.10; reaction: endonucleolytic cleavage of poly(U) or poly(C) to fragments terminated by 3′-hydroxyl and 5′-phosphate groups (*see* **Rrp**).

The second group of endoribonucleases (sub-subclass EC 3.1.27) yield products other than 5′-phosphomonoesters. **Ribonuclease T2** EC 3.1.27.1; *other name*: ribonuclease II; reaction: two-stage endonucleolytic cleavage to 3′-phosphomononucleotides and 3′-phosphooligonucleotides with 2′,3′-cyclic phosphate intermediates. *Bacillus subtilis* ribonuclease EC 3.1.27.2; reaction: endonucleolytic cleavage to 2′,3′-cyclic nucleotides. **Ribonuclease T1** EC 3.1.27.3; *other names:* guanyloribonuclease; *Aspergillus oryzae* ribonuclease; ribonuclease N1; ribonuclease N2; reaction: two-stage endonucleolytic cleavage to 3′-phosphomononucleotides and 3′-phosphooligonucleotides ending in G-p with 2′,3′-cyclic phosphate intermediates. **Ribonuclease U2** EC 3.1.27.4; reaction: two-stage endonucleolytic cleavage to 3′-phosphomononucleotides and 3′-phosphooligonucleotides ending in Ap or Gp with 2′,3′-cyclic phosphate intermediates. **Pancreatic ribonuclease** EC 3.1.27.5; *other names:* ribonuclease; ribonuclease I; ribonuclease A; a notably thermostable enzyme that catalyses the reaction: endonucleolytic cleavage to 3′-phosphomononucleotides and 3′-phosphooligonucleotides ending in Cp or Up with 2′,3′-cyclic phosphate intermediates. A glycosylated form, **ribonuclease B**, has the same specificity. *Enterobacter* ribonuclease EC 3.1.27.6; reaction: endonucleolytic cleavage to 3′-phosphomononucleotides and 3′-phosphooligonucleotides with 2′,3′-cyclic phosphate intermediates. **Ribonuclease F** EC 3.1.27.7; reaction: endonucleolytic cleavage of RNA precursor into two, leaving 5′-hydroxyl and 3′-phosphate groups. **Ribonuclease V** EC 3.1.27.8; *other name*: endoribonuclease V; reaction: hydrolysis of poly(A), forming oligoribonucleotides and ultimately 3′-AMP. *Compare* **deoxyribonuclease**.

ribonuclease inhibitor *abbr.*: RI; a porcine protein that inhibits pancreatic nuclease. It contains 17 leucine-rich repeats (each ≈24 residues) that form hydrophobic beta strands. The crystal structure is available.

ribonuclease protection assay a method for measuring the abundance of a specific mRNA in which a short (~100 nucleotide) radioactively labelled antisense RNA probe is hybridized with a population of RNA molecules. Treatment with ribonucleases A and T1 digests all single-stranded RNA leaving double-stranded RNA intact. Autoradiography or phosphorimaging of acrylamide electrophoresis gels, on which the digestion products are run, can provide quantitative information about mRNA abundance.

ribonucleate 1 *abbr*.: RNA; any anionic form of ribonucleic acid. **2** any salt of ribonucleic acid.

ribonucleic acid *abbr*.: RNA; pentose nucleic acid (*abbr*.: PNA); ribose nucleic acid; yeast nucleic acid. *See* **RNA**.

ribonucleoprotein *abbr*.: RNP; any conjugated protein that contains RNA as the non-protein moiety. Various specific kinds of RNP are listed with their abbreviations at **RNP**.

ribonucleoside any **nucleoside** (def. 1) in which the glycose moiety is β-D-ribofuranose. The link is from C-1 of ribose to N-9 of a purine or to N-1 of a pyrimidine. To distinguish between the numbering systems of the base and sugar, the numbers of the sugar atoms are characterized by the addition of 'prime', i.e. 1′ to 5′. The various products have trivial names, e.g. adenosine, guanosine, cytidine, and uridine. Strictly, the term ribonucleoside should be confined to structures occurring in nucleic acids, but it can be used for any base–ribose compound. By extension, it can be applied to **pseudouridine** (which occurs in tRNA) with a C–C link between ribose and uracil.

ribonucleoside-diphosphate reductase *the recommended name for* **nucleoside-diphosphate reductase**.

ribonucleoside-triphosphate reductase *the recommended name for* **nucleoside-triphosphate reductase**.

ribonucleotide any ribonucleoside in ester linkage to phosphate, commonly at the 5′ position of the ribose moiety, although some 2′- and 3′-esters and some (cyclic) 2′,3′-, or 3′,5′-diesters are known. The 5′-ribonucleotides are metabolically important; they may be esters of [mono]phosphate, diphosphate, or triphosphate, e.g. guanosine 5′-[mono]phosphate, cytidine 5′-diphosphate, adenosine 5′-triphosphate. *See* **nucleotide**.

ribonucleotide reductase any enzyme that catalyses the reduction of ribonucleotides to deoxyribonucleotides during biosynthesis. *See* **nucleoside-diphosphate reductase**, **nucleoside-triphosphate reductase**.

ribophorin either of two type I single-pass transmembrane glycoproteins, ribophorins I and II, that form two subunits of ***N*-oligosaccharyltransferase**. They were first isolated bound to ribosomes on the rough endoplasmic reticulum. They form part of the ribosome receptor.

riboprobe any labelled RNA molecule used as a hybridization probe. Riboprobes are conveniently produced by ***in vitro* transcription** and are particularly useful for detecting specific mRNAs by hybridization *in situ*, and for ribonuclease protection assays.

ribose *symbol*: Rib; *ribo*-pentose. The D enantiomer, as β-D-ribofuranose, forms the glycose moiety of all ribonucleosides, ribonucleotides, and ribonucleic acids, and of ribose phosphates, various glycosides, some coenzymes, and some forms of vitamin B_{12}.



β-D-ribofuranose

ribose nucleic acid *a former name for* **ribonucleic acid**.

ribose-5-phosphate epimerase EC 5.3.1.6; *systematic name*: D-ribose-5-phosphate ketol-isomerase; *other names*: phosphopentoisomerase; phosphoriboisomerase. An enzyme that catalyses the reaction:

D-ribose 5-phosphate = D-ribulose 5-phosphate.

It functions in pentose metabolism, especially the **pentose phosphate pathway**.

ribose-phosphate pyrophosphokinase EC 2.7.6.1; *other name*: phosphoribosyl pyrophosphate synthetase (*abbr*.: PRS); a conserved enzyme that catalyses the formation of 5-phospho-α-D-ribose-1-diphosphate (*abbr*.: PRPP; *other name*: phosphoribosyl pyrophosphate) from ATP and D-ribose 5-phosphate with release of AMP; it is Mg^{2+}-dependent. PRPP is an intermediate in the biosynthesis of histidine and tryptophan, and in the *de novo* biosynthesis of purines and pyrimidines.

riboside the product of the formation of a glycosidic bond between ribose and another group, either through the nitrogen of an amine or a hydroxyl group, i.e. via *N*- or *O*-glycosidic linkages. *See also* **pseudouridine**. *Compare* **ribonucleoside**.

ribosomal ambiguity *abbr*.: ram; the effect of any mutation (e.g. in ribosomal protein S4 or S5) in bacterial genomes that affects selection of aminoacyl-tRNA species during protein biosynthesis.

ribosomal DNA *abbr*.: rDNA; the genetic DNA coding for ribosomal RNA (*see* **ribosome**).

ribosomal protein *abbr*.: r-protein; any of the protein components of the ribosomal subunits. They are typically small, and some are basic. Ribosomal proteins are referred to as S (small subunit) proteins and L (large subunit) proteins; in *Escherichia coli,* there are 21 S proteins, designated S1–S21, and 34 L proteins, designated L1–L34. In eukaryotes (e.g., in rat liver), there are 33 S proteins and 49 L proteins. *See also* **ribosome**.

ribosomal protein S6 kinase *see* **RSK**.

ribosomal RNA *abbr*.: rRNA; *see* **ribosome**.

ribosomal RNA processing *see* **Rrp**.

ribosome an intracellular organelle, about 200 Å in diameter, consisting of RNA and protein. It is the site of protein biosynthesis resulting from translation of messenger RNA (mRNA). It consists of one large and one small subunit, each containing only protein and RNA. Ribosomes and their subunits are characterized by their sedimentation coefficients, expressed in **Svedberg units** (*symbol*: S). The prokaryotic ribosome (70S) comprises a large (50S) and a small (30S) subunit, while the eukaryotic ribosome (80S) comprises a large (60S) subunit and a small (40S) subunit. Several ribosomes may bind to one mRNA to form a **polysome**. Two sites on the large subunit are involved in translation, namely the **aminoacyl site** (A site) and **peptidyl site** (P site). Ribosomes from prokaryotes, eukaryotes, mitochondria, and chloroplasts have distinct **ribosomal proteins**. Prokaryotic ribosomes contain 35–45% protein, while eukaryotic ribosomes contain 50% protein. **Ribosomal RNA** (rRNA) is the RNA part of a ribosome. In prokaryotes, a 30S subunit contains one 16S RNA molecule with associated proteins, while a 50S subunit contains one 5S and one 23S RNA molecule. In eukaryotes, the 60S subunit contains one 28S, one 5.8S, and one 5S RNA molecule, while the 40S subunit contains one 18S RNA molecule. The structures are known. In *Escherichia coli*, the rRNAs form part of a large transcript containing transfer RNA (tRNA) molecules, which is then cleaved during processing. In eukaryotes, the genes for the 5.8S, 18S, and 28S molecules reside in the **nucleolus**, and code for a 40S transcript, which is then cleaved during processing; this includes splicing that occurs in the absence of protein. The gene for the 5S rRNA is a separate transcription unit outside the nucleolus. *See also* **mRNA binding site**, **protein biosynthesis**.

ribosome-inactivating protein *abbr*.: RIP; any of a group of proteins, obtained from plants, that inactivate eukaryotic ribosomes. They are of two types. Type I proteins include agrostin, dianthrin, **dodecandrin**, **gelonin**, **luffin**, nomordin, **saporin-2**, and **tritin**. They are enzymes, EC 3.2.2.22, that catalyse endohydrolysis of the *N*-glycosidic bond at one specific adenosine on 28S rRNA. They are plant protein toxins, and possibly have antiviral activity. Type II ribosome-inactivating proteins are enzymes with a similar action to the type I proteins, but have an additional covalently bound chain with lectin properties. They include **abrin**, **modeccin**, **ricin**, viscumin, and **volkensin**.

ribosome receptor the binding site on the endoplasmic reticulum (ER) membrane for ribosomes bearing nascent polypeptides destined for secretion or incorporation into ER, Golgi apparatus, or plasma membrane. It consists of several proteins (including the ribophorins) oriented with their C-terminal segments on the cytoplasmic ER surface. The proteins bind directly to the large ribosomal subunit, and may also function in translocation of the nascent polypeptide into the ER lumen.

ribosome recycling factor *abbr.*: RRF; *other name*: ribosome releasing factor; a factor required by bacteria for the recycling of ribosomes. It dissociates the termination complex after the polypeptide has been released from the peptidyl-tRNA by release factor.

riboswitch any part of an mRNA molecule (but usually in the 5′ untranslated region) that can change its tertiary structure by interacting with some ligand and so inhibit translation.

ribosyl *or* **ribofuranosyl** any **glycosyl** group formally derivable from the *α*- or the *β*-furanose forms of D- or L-ribose. (The pyranose forms of ribose are exhibited only by the uncombined sugar.)

ribosylate to add a ribosyl residue. *Compare* **ADP-ribosylation**.

ribosylthymine *an alternative name for* **ribothymidine**.

ribosylthymine monophosphate *an alternative name for* **ribothymidine monophosphate**.

ribosylthymine phosphate *an alternative name for* **ribothymidine phosphate**.

ribothymidine *or* **ribosylthymine** *symbol*: T *or* Thd; 5-methyluridine; thymine riboside; 1-*β*-D-ribofuranosyl-5-methyluracil; a rare ribonucleoside, found as a minor component of many species of transfer RNA, where it is present as a residue of its 5′-phosphate. *See also* **ribothymidine 5′-phosphate**. *Compare* **thymidine**.

ribothymidine monophosphate *or* **ribosylthymine monophosphate** *abbr.*: TMP; *the common name for* any ribothymidine phosphate, particularly for ribothymidine 5′-phosphate.

ribothymidine phosphate *or* **ribosylthymine phosphate** ribothymidine monophosphate *or* ribosylthymine monophosphate (*abbr.*: TMP); any phosphoric monoester or diester of ribothymidine. Of the three possible monoesters – the 2′-phosphate, the 3′-phosphate, and the 5′-phosphate – and the two possible diesters – the 2′,3′-phosphate and the 3′,5′-phosphate – only **ribothymidine 5′-phosphate** is of any significance (the locant therefore being omitted if no ambiguity may arise).

ribothymidine 5′-phosphate *or* **ribosylthymine 5′-phosphate** *or* **5′-ribothymidylic acid** *symbol*: Thd5′*P* *or* pT; *the alternative recommended names for* ribothymidine monophosphate or ribosylthymine monophosphate (*abbr.*: TMP); 5′-ribothymidylyl phosphate; thymine riboside 5′-(dihydrogen diphosphate); thymine (mono)ribonucleotide. (The locant is commonly omitted if there is no ambiguity as to the position of phosphorylation.) A residue of ribothymidylic acid occurs in many species of transfer RNA, where it is formed *in situ* by methylation of the uracil moiety of an existing uridylic acid residue. This modification is effected by tRNA (uracil-5-)-methyltransferase (EC 2.1.1.35), the methyl group being derived from *S*-adenosyl-L-methionine.

ribothymidylate **1** either the monoanion or the dianion of **ribothymidylic acid**. **2** any mixture of ribothymidylic acid and its anions. **3** any salt or ester of ribothymidylic acid.

ribothymidylic acid *the trivial name for* any phosphoric monoester of ribothymidine. The position of the phosphoric residue on the ribose moiety of a given ester may be specified by a prefixed locant – *see* **ribothymidine phosphate**. However, 5′-ribothymidylic acid is the ester commonly denoted, its locant usually being omitted if no ambiguity may arise. 5′-ribothymidylic acid is also an alternative recommended name for ribothymidine 5′-phosphate.

ribothymidylyl the ribothymidine[mono]phospho group; the acyl group derived from **ribothymidylic acid**.

ribovirus *an alternative name for* **viroid**.

ribozyme an RNA molecule with catalytic activity. Such activity was first demonstrated in 1981 by Canadian-born US biochemist Sidney **Altman** (1939–) for **RNase P**. In 1982 the US biochemist Thomas R. **Cech** (1947–) discovered the catalysis by RNA of the reactions involved in the **splicing** of ribosomal RNA from *Tetrahymena*. In this process a 414-nucleotide **intron** is removed from a 6.4 kb precursor to yield the mature 26S rRNA. A guanine nucleotide is essential in the reaction, binding to the RNA and then attacking the 5′ splice site to form a phosphodiester bond with the 5′ end of the intron. The 414-nucleotide intron is then released and undergoes further splicing reactions to produce a linear RNA of 395 nucleotides which has lost 19 nucleotides and is named L19. L19 is catalytically active and acts both as a nuclease and a polymerase. The rate of conversion of a pentacytidylate into longer and shorter oligomers is about 10^{10} times the uncatalysed rate. Mg^{2+} plays an essential role. Much smaller ribozymes have been demonstrated, e.g. the **viroids** which infect plants and undergo self-splicing after replication. Comparisons of nucleotide sequences in the vicinity of specific cleavage sites suggest that the active site has a **hammerhead** secondary structure consisting of three helical regions radiating from a central core of unpaired nucleotides. mRNA precursors in the mitochondria of yeast and fungi also undergo self-splicing as do some RNA precursors in chloroplasts. Such reactions can be classified according to the nature of the unit that attacks the upstream splice site. Group I are mediated by a guanosine cofactor. In group II the attacking moiety is the 2′-OH of a specific adenylate of the intron. Such reactions resemble those that occur in the **spliceosomes**. Ribozymes are especially interesting in respect of theories on the origin of life because of the popular idea that the first macromolecules were composed of RNA. *See also* **ribonuclease**.

(Rib5)ppA *symbol for* adenosinediphosphoribose (alternative to Ado*PP*Rib *or* A5′pp5Rib).

D-ribulose *a nonsystematic name for* the ketopentose D-*erythro*-2-pentulose.



α-D-furanose form

D-ribulose 1,5-bisphosphate *abbr.*: RBP or RuBP; *former name*: ribulose diphosphate (*abbr.*: RDP or RuDP); a key metabolite of the **reductive pentose phosphate cycle**. It is formed in a reaction in which ribulose 5-phosphate is phosphorylated by ATP, catalysed by phosphoribulokinase, EC 2.7.1.19, and is a substrate of **ribulose-bisphosphate carboxylase**.

ribulose-bisphosphate carboxylase EC 4.1.1.39; *systematic name*: 3-phospho-D-glycerate carboxy-lyase (dimerizing); *other names*: ribulose-bisphosphate carboxylase/oxygenase (*abbr.*: Rubisco); the key enzyme in the fixation of CO_2 in the **reductive pentose phosphate cycle**; a copper protein. One molecule of D-ribulose 1,5-bisphosphate reacts with one molecule of CO_2 to yield two molecules of 3-phospho-D-glycerate, which can be converted into a hexose product (fructose 6-phosphate). If, as is possible, D-ribulose 1,5-biphosphate reacts with O_2 instead of CO_2, the products are one molecule each of 3-phospho-D-glycerate and 2-phosphoglycolate. This enzyme comprises up to 50% of leaf proteins and is the most abundant protein in the biosphere.

D-ribulose 5-phosphate the 5-phosphate ester of D-ribulose; it is a component of the **pentose phosphate pathway**, the product of 6-phosphogluconate dehydrogenase. It is converted to ribulose 1,5-bisphosphate in the **reductive pentose phosphate cycle** of photosynthesis.

L-ribulose-phosphate 4-epimerase EC 5.1.3.4; an enzyme that catalyses the reaction:

L-ribulose 5-phosphate = D-xylulose 5-phosphate.

Richner–Ranhart syndrome *see* **tyrosine transaminase**.

ricin a highly toxic lectin obtained from the seeds of the castor oil plant, *Ricinus communis*. It is a 493 amino-acid glycoprotein dimer comprising an A chain (M_r 66000) and a B chain (M_r 34000) linked by a disulfide bond. Ricin binds to the cell via interaction between the B chain and galactose groups on cell-surface receptors; then the disulfide bond is cleaved allowing the A chain to enter the cell. The A chain then binds to the 60S ribosomal subunit and, acting as an *N*-glycosidase, causes depurination of a specific adenosine residue in the 28S rRNA that is essential for peptidyltransferase activity, thereby halting protein translation. *See also* **abrin**, **ribosome-inactivating protein**.

rickets *or* **rachitis** a disturbance of calcium (and phosphate) metabolism in young growing animals (including humans), resulting from a deficiency of **vitamin D** or of its activation. It is characterized by softening of the bones and skeletal deformities, particularly bowing of the legs. — **rachitic** *adj.*

RID *abbr. for* radial immunodiffusion.

RIEP *abbr. for* rocket immunoelectrophoresis.

Rieske protein EC 1.10.99.1; *recommended name*: plastoquinol-plastocyanin reductase; *systematic name*: plastoquinol: oxidized-plastocyanin oxidoreductase; one of the four subunits of the cytochrome b_6–*f* complex. An enzyme that catalyses a reaction between plastoquinol-1 and two molecules of oxidized plastocyanin to form plastoquinone and two molecules of reduced plastocyanin. It is a high-potential 2Fe–2S protein. Apart from the Rieske protein, the subunits of the b_6–*f* complex consist of **cytochromes *b*$_6$** and ***f***, and a 17 kDa peptide; it is similar to other iron–sulfur proteins (e.g., in mitochondria).

rifampicin *or* **rifampin** an antibiotic, M_r 823, obtained as a semisynthetic derivative of rifamycin B, differing only in the substituents on the ring marked X in the structure for that compound. It inhibits bacterial transcription in sensitive bacteria (*see* **rifamycin**) at extremely low concentrations (0.01 µg ml^{-1}) while having no effect on eukaryotic transcription at 10^4 times that dose. Mitochondrial and chloroplast transcription may be affected at higher doses. It has application in molecular biology for removing plasmids from bacteria in a process known as **plasmid curing**.

rifamycin any anti-transcription antibiotic produced by *Streptomyces mediterranei* that is active against Gram-positive bacteria and *Mycobacterium tuberculosis* but much less effective against Gram-negative organisms. With the **streptovaricins** they are referred to as **ansamycins** – which contain a chromophoric naphthohydroquinone nucleus spanned by a long aliphatic bridge. They inhibit bacterial but not eukaryotic RNA synthesis via binding to the β subunit of bacterial DNA-dependent RNA polymerase and prevention of chain initiation; chain elongation is not affected once the initiation of RNA chain synthesis progresses beyond the third diester bond.



rifamycin B

rigid *(in lipid biochemistry)* a term sometimes used to describe the ordered phase of a lipid bilayer below the phase transition temperature. *See* **phase transition (of lipids)**.

rimorphin a 13-residue peptide that is a major Leu-enkephalin-containing peptide in tissues that contain **dynorphin** and α-neo-dynorphin. It yields three **enkephalin** sequences.

rim protein *see* **ABCR**.

Rim protein *an alternative name for* ABC transporter retina. *See* **Stargardt macular dystrophy**.

ring chromosome an intrachromosomal rearrangement in which either the chromosome is circularized by joining of the telomere ends, or the ends of the p and q arms break off with subsequent formation of a ring and the consequent loss of genetic material. Ring chromosomes can behave in one of three ways at cell division, the outcome depending on the numbers of sister chromatid exchanges (SCE). An even number of SCEs in the same direction, or none, results in symmetrical segregation of chromatids. An even number of SCEs in different directions will lead to interlocked rings. An odd number of SCEs will lead to the formation of a continuous ring from two parallel chromatids that is twice the size of the original rings.

ring closure the formation of a covalent bond that converts a linear molecule into a ring structure.

Ringer–Locke solution *a less common name for* **Locke's solution**.

Ringer's solution *or* **Ringer solution** any of a number of aqueous solutions of mixed inorganic salts, of composition determined empirically by the British physician and physiologist Sydney Ringer (1835–1910), or adapted therefrom, that have been useful as fluid replacements *in vivo* or in place of serum as perfusing or suspending media for organs, tissues, or cells *in vitro*. Ringer's own mixtures (reported over the period 1882–87) were devised mostly for maintaining normal contractility of perfused isolated frog heart. One of the most effective solutions contained (in g L^{-1}, approx.) NaCl (7.0), KCl (0.04), $CaCl_2$ (anhydrous, 0.09), and $NaHCO_3$ (0.5). *See also* **Krebs' mammalian Ringer**, **Locke's solution**, **Tyrode's solution**.

Ringer–Tyrode solution *a less common name for* **Tyrode's solution**.

RING finger a **zinc finger** motif defined as

$$CX_2CX_{9\text{–}27}CXHX_2CX_2CX_{6\text{–}17}CX_2C$$

and present in a family of nuclear proteins. RING is an acronym for 'really interesting new gene'.



ring opening the breaking of a bond that converts a ring structure to an open-chain form.

RIP *abbr. for* **1** repeat-induced point (mutation); a phenomenon found in *Neurospora*; when more than one copy of a DNA sequence is present in a haploid genome that goes through a cross, both ectopic and endogenous copies are subject to point mutation at a high rate. RIP occurs in the dikaryotic ascogenous hyphae. Because transformation of *Neurospora* typically leads to gene amplification, RIP provides a highly efficient and selective method of introducing mutations *in vivo* in any gene cloned *in vitro*. **2** ribosome-inactivating protein. **3** Fas receptor interacting protein; a cytosolic protein kinase that contains a **death domain** and participates in the activation of NF-κB and in promoting apoptosis.

RISBASES proteins that share sequence similarity with members of the ribonuclease family, but are thought not to function as ribonucleases. Examples are bovine seminal RNase and **angiogenin**. [From ribonuclease with special biological action.]

RISC *abbr. for* RNA-induced silencing complex; a ribonucleoprotein complex that targets its perfectly (or partially) complementary mRNA for either cleavage or translational repression. Short interfering RISC (siRISC) is programmed by siRNA, and micro RISC (miRISC) by miRNA. Both siRISC and miRISC are of two types, cleaving and noncleaving. It is likely that this specificity is determined by one of the **argonaute** proteins.

RIST *abbr. for* radioimmunosorbent test.

ristocetin a glycopeptide antibiotic complex from *Nocardia lurida*. Ristocetin A, M_r 2066, acts primarily on Gram-positive bacteria by inhibiting the biosynthesis of peptidoglycans of cell walls. It is particularly useful against infections of the gut when administered by injection, but not when taken orally, and has toxic side effects including kidney damage.

RITS *abbr. for* RNA-induced transcriptional gene silencing *or* RNA-induced initiation of gene silencing.

Rittenberg tube an evacuable two-legged tube provided with a stopcock and used for the conversion of ^{15}N-labelled ammonium salts into dinitrogen prior to mass-spectrometric analysis. It has been jocularly known, especially in Israel, as **Rittenberg's trousers**. [After David Rittenberg (1906–70), US biochemist.]

Rituximab a monoclonal antibody active against non-Hodgkin's lymphona (NHL). In some cases of NHL there is present a chemokine CD20, which arises due to the translocation of a gene from chromosome 14 to 18. The oncogene is *BCL2*, which is responsible for the overexpression of CD20. Thus rituximab is an anti-CD20 agent. The higher the grade of NHL the less likely it is to have CD20 receptors. The proprietary name is Mabthera.

R loop the structure formed when an RNA of complementary sequence stably base pairs with one of the DNA strands of double-stranded DNA, as happens at the start of **transcription**.

r.m.m. *abbr. for* relative molecular mass.

RMS *abbr. for* root mean square.

RMSD *abbr. for* root mean square deviation.

Rn *symbol for* radon.

RNA *abbr. and common name for* **ribonucleate** (def. 1) or **ribonucleic acid**; one of the two main types of **nucleic acid**, consisting of a long, unbranched macromolecule formed from ribonucleotides, the 3′-phosphate group of each constituent ribonucleotide (except the last) being joined in 3′,5′-phosphodiester linkage to the 5′-hydroxyl group on each ribose moiety of the next one. The presence of a free 2′-hydroxyl group on each ribose moiety renders these phosphodiester bonds susceptible to hydrolytic attack by alkali, in contrast to those of **DNA**. The RNA chain has polarity, with one **5′ end** and one **3′ end**. Two purines, adenine and guanine, and two pyrimidines, cytosine and uracil, are the major bases usually present. In addition, **minor bases** may occur; **transfer RNA**, however, contains unusual bases in relatively large amounts. The sequence of bases carries information, whereas the sugar and phosphate groups play a structural role. RNA is fundamental to **protein biosynthesis** in all living cells. **Messenger RNA** (mRNA) is responsible for carrying the coded genetic 'message', transcribed from DNA, to sites of protein assembly at the **ribosomes**. The latter are composed of **ribosomal RNA** (rRNA) plus proteins. A third species, transfer RNA (tRNA), is instrumental in importing amino acids to the assembly site, according to instructions carried by mRNA. In some viruses, RNA is the genetic material instead of DNA. Specific forms, functions, molecules, or preparations of RNA may be designated by prefixes or suffixes, thus: A-RNA *or* RNA-A, **A-form** of RNA; cRNA, **complementary RNA**; dsRNA, double-strand(ed) RNA; hnRNA *or* H-RNA *or* HnRNA, **heterogeneous nuclear RNA**; mRNA, **messenger RNA**; micRNA, **messenger-RNA-interfering complementary RNA**; mtRNA, **mitochondrial RNA**; nRNA, nuclear RNA; rRNA, **ribosomal RNA**; sRNA *or* S-RNA, **soluble RNA**; scRNA, small cytoplasmic RNA; snRNA, **small nuclear RNA**; snoRNA, **small nucleolar RNA**; ssRNA, single-strand(ed) RNA; tRNA, **transfer RNA**; tcRNA, **translational-control RNA**; *Z*-RNA *or* RNA-Z, **Z-form** of RNA.

RNA I a short 108 nucleotide plasmid-encoded transcript that is antisense to the 5′ end of RNA II, with which it forms a duplex. It acts as a negative regulator of plasmid replication as it inhibits the action of RNase H on **RNA II**. Pairing between RNA I and RNA II is facilitated by the Rop protein.

RNA II a plasmid-encoded transcript that initiates 555 bp upstream from the Col E1 origin of replication. Its cleavage by RNase H leaves a primer with a 3′-hydroxy end that is used for initiating DNA synthesis during plasmid replication.

RNA-activated protein kinase *see* **PKR**.

RNA adenylating enzyme *see* **polynucleotide adenylyltransferase**.

RNAase *(sometimes) abbr. for* ribonuclease; RNase is more usual.

RNA-dependent DNA polymerase *another name for* RNA-directed DNA polymerase (*see* **reverse transcriptase**).

RNA-dependent RNA replicase *see* **RNA-directed RNA polymerase**.

RNA-directed RNA polymerase EC 2.7.7.48; *other name*: RNA nucleotidyltransferase (RNA-directed); an enzyme that catalyses a reaction between a nucleoside triphosphate and RNA_n to form RNA_{n+1} and pyrophosphates; it is required for the replication of RNA viruses; in the case of eukaryotic viruses, the enzyme normally comprises several subunits.

RNA–DNA virus *a former name for* **retrovirus**.

RNA editing *see* **editing** (def. 2).

RNA editing enzyme *or* **RNA-dependent deaminase** (*abbr*.: RED); any enzyme that catalyses deamination of a nucleotide base (e.g. cytosine to uracil; adenine to inosine) at a specific site in RNA. *See* **APOBEC1**.

RNA helicase an ATP-dependent enzyme that is similar to **DNA helicase** except that its substrate is RNA. An example is the *dbpA* gene product from *Escherichia coli*, which is specific for 23S rRNA.

RNAi *abbr. for* RNA interference.

RNA-induced silencing complex *see* **RISC**.

RNA-interacting module any peptide sequence in a polypeptide that binds RNA, e.g. G-patch and some zinc fingers (of C2H2 and C4 types).

RNA interference (*abbr*.: RNAi) *or* **post-transcriptional gene silencing** a general mechanism for silencing the transcript of an active gene in many organisms. The interference is initiated by **siRNA** (as part of an RNA-induced silencing complex; *see* **RISC**) that is specific for the nucleotide sequence of the target transcript. There is no evidence that this type of silencing occurs in normally growing animals, but it has been demonstrated in *Caenorhabditis elegans* and is used by plants to combat virus infection.

RNA ligase (ATP) EC 6.5.1.3; *other name*: polyribonucleotide synthase (ATP); an enzyme from bacteriophage T4 that catalyses ATP-dependent ligation of single-stranded RNA or DNA onto the 5′-phosphate terminus of single-stranded RNA or DNA molecules:

$$\text{ATP} + (\text{ribonucleotide})_n + (\text{ribonucleotide})_m = \text{ADP} + \text{pyrophosphate} + (\text{ribonucleotide})_{m+n}\,.$$

RNA polymerase any enzyme that utilizes ATP, GTP, CTP, and UTP to synthesize RNA from a DNA or RNA template. DNA-dependent RNA polymerases include (i) the enzymes responsible for transcription of DNA and (ii) **primases**, which synthesize the RNA primers required for replication of DNA. An **RNA-directed RNA polymerase** (replicase or RNA synthetase) is involved in the replication of RNA viruses.

DNA-dependent (or DNA-directed) RNA polymerase (EC 2.7.7.6); *other name*: RNA nucleotidyltransferase (DNA-directed); it catalyses a reaction between a nucleoside triphosphate and RNA_n to form RNA_{n+1} and pyrophosphate. This EC class number includes the following examples.

In prokaryotes one DNA-dependent RNA polymerase transcribes all classes of DNA. The core *Escherichia coli* enzyme consists of three types of subunit, α, β, and β′, and has the composition $\alpha_2\beta\beta'$; the holoenzyme contains an additional σ subunit or sigma factor. **Sigma factors** are responsible for specific promoter recognition and transcription initiation. Following transcription initiation, the sigma factor dissociates from the core enzyme. The β subunit is probably involved in binding ribonucleotide substrates; it is the target for **rifamycin** and **streptolydigin** antibiotics. The β′ subunit may bind template DNA.

Phage RNA polymerases are much smaller and simpler than bacterial ones: the polymerases from phage T3 and T7 RNA, e.g., are single polypeptide chains of <100 kDa.

Eukaryotes have three types of DNA-dependent RNA polymerase in the nucleus, each producing a different type of RNA. RNA polymerase I, located in the nucleolus, synthesizes precursors of most ribosomal RNAs; RNA polymerase II, located in the nucleoplasm, synthesizes messenger RNA precursors; and RNA polymerase III, also located in the nucleoplasm, synthesizes the precursors of 5S rRNA, the transfer RNAs, and other small RNAs. These enzymes can be distinguished by their sensitivity to α-amanitin (*see* **amanitin**); class I enzymes are not inhibited by this octapeptide, whereas class II enzymes are rapidly inhibited by low concentrations; the sensitivity of class III enzymes varies depending on species. **RNA polymerase I** has 13 subunits totalling over 600 kDa; it recognizes a single type of promoter and requires at least two ancillary factors, UBF1 and SL1; it accounts for 50–70% of the RNA polymerase activity in eukaryotic cells. **RNA polymerase II** from all sources contains two large subunits of 215 and 139 kDa and several smaller polypeptides. The 215 kDa subunit has homology with the prokaryotic β′ subunit and contains a C-terminal domain (CTD) with multiple repeats of the consensus sequence YSPTSPS; the CTD is involved in initiation. The 139 kDa subunit has homology with the bacterial β subunit; the third largest subunit is related to the bacterial α subunit. Three of the remaining subunits are common to RNA polymerases I, II, and III. Most promoters used by RNA polymerase II contain the **TATA box**, which is recognized by the TATA-binding protein (TBP), a component of the **transcription factor** TFIID. Several other accessory factors are required for transcription by RNA polymerase II. **RNA polymerase III** has 14 subunits totalling 700 kDa. The promoters it uses may be upstream of the transcribed gene (for snRNAs) or within the gene (for tRNAs and 5S RNA). Three accessory factors, TFIIIA (a **zinc-finger** protein), TFIIIB, and TFIIIC, are involved in transcription from internal promoters.

Mitochondria and chloroplasts also contain RNA polymerase activity that synthesizes the RNAs required for protein synthesis in these organelles. These polymerases are smaller than the nuclear enzymes and more like prokaryotic RNA polymerases.

[RNA-polymerase]-subunit kinase EC 2.7.1.141; *other name*: CTD kinase (*abbr*. for C-terminal domain kinase); an enzyme that catalyses a reaction between ATP and [DNA-directed RNA polymerase] to form phospho-[DNA-directed RNA polymerase] and ADP.

RNA primer a segment of RNA (60 nt long in prokaryotes, depending on species) that is complementary to a segment of the template DNA and is formed by DNA **primase** during the initiation of DNA replication. *See* **replication of DNA**.

RNA processing the splicing, 5′-capping, and 3′-polyadenylation by which eukaryotic pre-mRNA is converted into mature mRNA. All three processes are associated with the C-terminal domain of the largest subunit of the **RNA polymerase** II complex. *See* **cap**; **poly(A) tail**; **splicing** (def. 2).

RNase *usual abbr. for* ribonuclease; *compare* **RNAase**.

RNase III a dsRNase such as **Dicer** and **Drosha** involved in the production of siRNA and miRNA respectively. *See also* **ribonuclease**.

RNase A *abbr. for* ribonuclease A (pancreatic ribonuclease). *See* **ribonuclease**.

RNase B *abbr. for* ribonuclease B; a glycosylated form of ribonuclease A with the same specificity. *See* **ribonuclease**.

RNase H *abbr. for* ribonuclease H. *See* **ribonuclease**.

RNase MRP a site-specific endoribonuclease for mitochondrial RNA processing (hence ‘MRP’). It contains an essential RNA component and cleaves mitochondrial RNA (mtRNA) transcripts that are complementary to the D-loop region of vertebrate mtDNA.

RNase ONE *a proprietary name for* RNase I from *E. coli* that catalyses hydrolysis of phosphodiester bonds after all four ribonucleotides.

RNase OUT *a proprietary name for* a formulation for removing RNase and DNase from laboratory surfaces.

RNase P *abbr. for* ribonuclease P. *See* **ribonuclease**.

RNase T1 *abbr. for* ribonuclease T1; a single-stranded RNA (or DNA) endonuclease from *Aspergillus* that cleaves after guanine residues. *See* **ribonuclease**.

RNA silencing *or* **cosuppression** *or* **post-transcriptional gene silencing** (*abbr*.: PTGS); **RNA interference** in plants that is induced by viruses as a general antiviral defence mechanism. Many plant viruses encode proteins that are suppressors of silencing. When triggered locally, it can spread via a mobile silencing signal.

RNasin a proprietary recombinant ribonuclease inhibitor, similar to human placental RNase inhibitor, that acts by forming stable noncovalent complexes with ribonuclease.

RNA synthetase an RNA-directed **RNA polymerase**.

RNA tumour virus a common designation for **retrovirus**, as this is the only group of RNA viruses known to cause cancer.

RNP *abbr. for* ribonucleoprotein. Specific kinds of RNP may be designated by prefixes, thus: hnRNP, **heterogeneous nuclear ribonucleoprotein**; scRNP, **small cytoplasmic ribonucleoprotein**; snRNP, **small nuclear ribonucleoprotein**.

RNPase *or* **RNP disruptase** a putative enzyme that disrupts RNA–protein interactions.

RNP disruptase *an alternative name for* **RNPase**.

Ro an RNA-binding protein and autoantigen in human systemic lupus erythematosus (SLE). Mice that lack Ro develop antibodies against ribosomes and chromatin and have glomerulonephritis and skin photosensitivity as in SLE. Ro also enables the nematode *Caenorhabditis elegans* to withstand environmental stress, and some bacteria to withstand UV irradiation.

Robertsonian translocation any translocation in which the long arms of two acrocentric chromosomes fuse at the centromere. In humans, chromosomes 13, 14, 15, 2, and 22 are most commonly involved, especially 13 and 14. Robertsonian fusion of the long arms of chromosomes 21 and 14 is responsible for about 4% of Down syndrome cases. [After W.R.B. Robertson (1881–1941), US geneticist.]

Robison ester *an old name for* D-glucose 6-phosphate. *Compare* **Neuberg ester**. [After R. Robison, British chemist (1883–1941).]

Robo *or* **roundabout** any of a conserved family of receptors present on the growth cones of *Drosophila* axons that do not cross the midline. They consist, in sequence, of five immunoglobulin-like domains, three fibronectin repeats, one transmembrane segment, and four cytoplasmic motifs. On binding to a slit protein they regulate intracellular GTPase-activating proteins (GAPs). In zebrafish Robo2 is called astray.

robot any device for performing computational or physical tasks automatically. For example, in computing, a robot is a program that trawls the Web for information, indexing it, say, for a search engine. In biology, robot machines execute the numerous mundane, repetitive tasks associated with high-throughput technologies (e.g. genome sequencing, drug screening). **–robotic** *adj*.; **–robotism** *or* **robotry** *n.*

robotics the automation of laboratory procedures in which there are a number of repetitive operations. In genomics and proteomics such operations may be performed by a robotics workstation.

ROC *abbr. for* receiver operating characteristic.

Rochelle salt potassium sodium tartrate tetrahydrate; it is used as a constituent of **Fehling's solution**. [After La Rochelle, French port.]

rocket immunoelectrophoresis *abbr*.: RIEP; a one-dimensional **electroimmunodiffusion**, *also known as* **electroimmunoassay**, used for quantitative analysis of proteins. Exact volumes of protein (antigen) solution are applied in an agarose gel of uniform thickness containing the corresponding antibody. An electric field causes the migration of both antigen and antibody. They react to form elongated curved precipitation lines, known as rockets because of shape, which are proportional in size to the amount of antigen. *See also* **crossed immunoelectrophoresis**.

rod cell *or* **rod** a rod-shaped light-sensitive cell of the vertebrate retina. Rod cells contain **rhodopsin** or (in freshwater and migratory fish and some amphibians) **porphyropsin**, and are responsible for vision in dim light. They occupy all of the margin of the retina and are absent from the fovea. Each is a highly specialized cell with an outer and inner segment, a cell body, and a synaptic region where the rod passes a chemical signal to retinal nerve cells. Phototransduction occurs in the outer segment, which contains a stack of rhodopsin-rich membrane disks. The plasma membrane of the outer segment contains cyclic-GMP-gated Na^+ channels. These are kept open in the dark by cyclic GMP molecules bound to the channels. Metarhodopsin II, i.e. rhodopsin activated by a photon, activates **transducin**, a **G-protein**, which then activates a cyclic GMP phosphodiesterase, reducing the cellular level of cyclic GMP to initiate a nerve impulse in the optic nerve. *Compare* **cone cell**.

rod gel a gel used in a form of polyacrylamide gel electrophoresis, in which the gel is cast in cylindrical glass tubes. Now largely superseded by slab-gel electrophoresis.

roentgen *a variant spelling of* **röntgen**.

Rohypnol *proprietary name for* flunitrazepam, a **benzodiazepine** central nervous system depressant administered to treat insomnia. It is used in drug-facilitated rape (‘date rape’).

roller bottle a cylindrical container used for the culture of monolayers of adherent cells. *See* **roller culture**.

roller culture a method of cell culture using roller bottles in which adherent cells are bathed with culture medium as the bottle is rotated. This method of culture is used when large numbers of cells are required.

rolling circle a mechanism for the replication of circular double-stranded DNA. One strand is nicked, then, using the unbroken strand as a template, the DNA is replicated around the circle. Replication does not cease when one circumference has been replicated, but continues around the circumference several more times (hence the name 'rolling'). Consequently, multimers of the replicon are produced in a long single strand with the appearance of a tail; this may then be cut into unit replicons, or into multimers containing tandemly repeated copies of the original unit; these may remain as single strands or be transcribed to yield a complementary strand.

röntgen *or* **roentgen** *symbol* R; the unit of **exposure** (def. 3) to X- or gamma radiation, expressed in terms of the amount of ionization caused in air. Defined originally (1928, 1937) as that quantity of radiation having a corpuscular emission per 0.001293 gram of air (equivalent of 1 cm^3 of dry air at stp) producing, in air, ions carrying one electrostatic unit quantity of electricity of either sign. Expressed in SI units, 1 R causes the production in air of ions (of one sign) carrying a charge of 2.58×10^4 C kg^{-1}; this corresponds to the formation of 1.61×10^{15} ion-pairs per kg of air and to an absorption of energy by air equal to 0.00869 J kg^{-1}. The energy absorption by water or tissue from 1 R of x- or gamma-radiation is about 0.0096 J kg^{-1}. Prior to 1956, the röntgen was used in clinical work to express both exposure and **absorbed dose**. *See also* **rad** (def. 2), **rem**, **rep**. [After Wilhelm Konrad von Röntgen (1845–1923), German physicist, discoverer of X-rays.]

röntgen equivalent man *or* **röntgen equivalent man** *see* **rem**.

röntgen equivalent physical *see* **rep**.

röntgen rays *a former name for* **X-rays**.

room temperature ambient temperature, often used for reactions that can be carried out on the bench without devices to maintain constant temperature. Normally within several degrees of 20 °C.

root effect the lowering of ligand affinity and of cooperativity of ligand binding (in hemoglobin) brought about by a low pH. [After R. W. Root who reported it in 1931.]

root mean square *abbr*. RMS; the positive square root of the mean of the squares of a series of values of x_i:

$$\text{RMS value} = \sqrt{\left(\frac{x_1^2+x_2^2+\ldots x_n^2}{n}\right)}$$

Compare **standard deviation**.

root mean square deviation *abbr.*: RMSD; the square root of the sum of squared deviations of the observed values from the mean, divided by the number of observations. The RMSD gives a measure of the dispersion of points in a data set, or, in molecular structure determination, a measure of the similarity of two molecular conformations.

Rop *abbr. for* Rho-like protein of plants.

ROS *abbr. for* **1** rod outer segment; *see* **rod cell**. **2** reactive oxygen species.

ROS a gene family encoding receptor-tyrosine kinases of unknown function; v-*ros* is the oncogene of the acutely transforming avian sarcoma virus UR2 (named after the University of Rochester). The vertebrate gene product, Ros, is similar to the *Drosophila* **sevenless protein**; it appears to be associated with a phosphoinositide response (*see* **phosphatidylinositol cycle**); Ros-1 is a member of the Src family.

rosetting a method of isolating cells by allowing them to associate with red blood cells. For example, lymphocytes become surrounded with red cells, forming a 'rosette', and may then be isolated by sedimentation through **Ficoll** gradients.

Rossmann fold a super-secondary motif in protein structure comprising two adjacent β-α-β units, creating a β-α-β-α-β domain, and often containing a hydrophobic core between the closely packed sheet and helices. The Rossmann fold occurs in a variety of proteins, but was first described as the NAD(P)-binding domain in a family of dehydrogenases.

rota-evaporate to evaporate a solution in a rotating round-bottomed flask in a temperature-controlled water bath, using an apparatus that can at the same time apply a vacuum to the flask interior. **—rota-evaporation** *n.*

rotamer *see* **rotational isomer**.

rotary evaporator an apparatus used for **flash evaporation**; *see also* **rota-evaporate**.

rotational correlation time *see* **correlation time**.

rotational diffusion rotation of a solute molecule around its centre of mass as a result of **Brownian movement**.

rotational frictional coefficient *see* **frictional coefficient**.

rotational isomer molecules of identical **configuration** may be distinguished as having different **conformations** after rotation about a bond. If an assembly of atoms X–A–B–Y (X and Y not being collinear with A–B) is viewed along the axis A–B, the X–A and B–Y bonds will make an angle with each other which may be 0° (superposition), 180° or some intermediate angle. This angle is termed the torsion angle, designated θ or ψ. Conformations are then described as synperiplanar (*sp*), synclinal (*sc*), anticlinal (*ac*) or antiperiplanar (*ap*) according as the torsion angle is within ± 30° of 0°, ± 60°, ± 120°, or ± 180°, respectively. Formerly, the terms *cis*, *gauche* and *trans* were in use for synperiplanar, synclinal and antiperiplanar respectively.

rotational strength *or* **rotatory strength** *symbol*: *R*; an index of the degree to which an **absorption band** exhibited by an optically active solute displays **circular dichroism**. It may be evaluated for the absorption band in question by means of the expression:

$$R = 2.296 \times 10^{-44} \int \left(\frac{\Delta\varepsilon_\lambda}{\lambda}\right) d\lambda$$

where λ is a wavelength of observation and Δe_k is the difference between the molar (decadic) absorption coefficients of the left and right circularly polarized light beams at that wavelength. Rotational strength is thus essentially the absorption coefficient difference integrated over the entire absorption band.

rotation axis a crystal or an oligomeric protein molecule is said to possess an *n*-fold rotation axis if it presents exactly the same appearance after a rotation about that axis of 360°/*n*. *Compare* **screw axis**.

rotation–reflection axis *see* **symmetry**.

rotenone an insecticide and the active principle in derris. It is present in plants of the genera *Derris*, *Lonchocarpus*, *Tephrosia*, and *Mundulea,* used by indigenous peoples as fish poisons (*Derris* in Asia, *Lonchocarpus* in South America, and *Tephrosia* more extensively). Rotenone inhibits mitochondrial respiration on the oxygen side of the nonheme iron of NADH dehydrogenase. Extracts of rotenone-containing plants are used as insecticidal sprays and dusts (derris dust). *Compare* **piericidin A**.



rotor **1** the part of a centrifuge that holds the material to be subjected to centrifugal force. It generally has compartments that house tubes or bottles, and these may either be set at a fixed angle with respect to the axis of rotation, or designed to allow the containers to swing out into a horizontal position during centrifugation. Centrifugal force is generated by rotating the rotor about its axis. **2** the part of the **H^+-transporting ATP synthase** that rotates during flow of hydrons through the F_0 part of the complex. *Compare* **stator**.

Rotor syndrome a rare autosomal recessive benign predominantly conjugated hyperbilirubinemia. Unlike **Dubin–Johnson syndrome** it shows no liver pigmentation. A defect (of unknown nature) in canalicular multiorganic anion transporter (cMOAT) is thought to be responsible. [After Arturo Belleza Rotor (1907–88), Philippine physician.]

Rot value *or* **R_0t value** a measure of the kinetic complexity of RNA based on its hybridization ability. The notation is a modification of R_0t, where R_0 is the initial RNA concentration and *t* is time. It is analogous to the Cot value (*see* **C_0t**) for DNA. $R_0t_{1/2}$ is the value corresponding to half complete association between complementary polynucleotides.

roughanic acid all-*cis*-7,10,13-hexadecatrienoic acid; a plant fatty acid present in storage lipids.

rough endoplasmic reticulum *abbr*.: RER; a region of the **endoplasmic reticulum** associated with ribosomes and involved in the synthesis of secreted and membrane-bound proteins. The nascent protein destined for secretion with its **signal peptide** associates with a receptor for the **signal recognition particle** and then translocates through the RER lipid bilayer by means of proteins, including **TRAM,** which form a **translocon.** The signal peptide is removed by the **signal peptidase**. The process is aided by **heat-shock proteins**, which serve as **chaperones**.

roundabout *an alternative name for* **Robo**.

Round-up *see* **glyphosate**.

rousvirus *see* **retrovirus**.

rP the negative decadic logarithm of the molar concentration of inorganic phosphate; i.e. rP = –log[P$_i$]. If, for the equilibrium

$$X + P_i = XP,$$

$$K = [X][P_i]/[XP]$$

then

$$rP = -\log K - \log([XP]/[X]).$$

RP-HPLC *abbr. for* reversed phase high-pressure liquid chromatography; *see* **reversed phase**.

R plasmid *abbr. for* resistance plasmid.

RPM *abbr. for* Redhat Package Manager; a utility designed by the authors of the Redhat distribution of **Linux** but also implemented by other distributors of Linux. RPM files are compressed and can be found in certain **software archives**.

RPMI *abbr. for* Roswell Park Memorial Institute (Buffalo, USA).

r-protein *abbr. for* ribosomal protein.

R protein *see* **R gene.**

RP-TLC *abbr. for* reversed phase thin-layer chromatography; *see* **reversed phase**.

RQ *abbr. for* respiratory quotient.

RRM *abbr. for* RNA recognition motif; a conserved 80-amino-acid sequence present in a family of proteins that bind RNA. It has a β-α-β-β-α-β structure.

rRNA *abbr. for* ribosomal RNA; *see* **ribosome**.

Rrp *abbr. for* ribosomal RNA processing; any of a group of exonucleases that are involved in processing of RNA precursors in yeast, where they form part of the exosome core in the cytoplasm. Some Rrps catalyse a phosphorylase reaction (Rrp41p, Rrp42p, Rrp43p, Rrp45p, and Rrp46p), while others catalyse a hydrolase reaction (Rrp4p, Rrp40p, and, in the nucleus, Rrp6p).

(*RS*)- *prefix (in chemical nomenclature)* denoting a racemate containing a single chiral centre. *See* **sequence rule**.

***R*/*S* convention** the system of configuration specification of chiral compounds based on the **sequence rule**.

R segment *abbr. for* repeat segment; part of retroviral RNA consisting of direct repeats, i.e. repeats having the same orientation; the size of the repeat varies in different strains of virus, from 80 to 100 nucleotides.

RSK *abbr. for* ribosomal protein S6 kinase; any of a family of protein serine/threonine kinases that, on binding of certain growth factors to their tyrosine-kinase receptors, translocate from cytoplasm (where they may phosphorylate ribosomal protein S6) to the nucleus (where they phosphorylate several transcription factors). RSK2 is the same as CREB (protein) kinase.

RSKG-5 *see* **tonin**.

R state *see* **R form**.

rtDNA *(sometimes) abbr. for* **recombinant DNA**; use not recommended.

RTP *symbol for* any unspecified purine nucleoside 5′-triphosphate.

RT-PCR **1** *abbr. for* reverse transcriptase-polymerase chain reaction *or* reverse transcription-polymerase chain reaction; a quantitative technique for amplifying DNA transcripts of cellular mRNA. **2** *sometimes abbr. for* **real-time PCR**; use not recommended.

rtTA *abbr. for* reverse tetracycline-controlled *trans*-activator; a chimeric transcriptional activator based on a modified DNA-binding domain of the tetracycline controlled *trans*-activator fused to the *trans*-activator domain of VP16 and used in the **Tet-On** system.

rTth a proprietary recombinant thermostable DNA polymerase originally from *Thermus thermophilus*. It has proofreading activity and is used in the generation of long (>4 kb) polymerase chain reaction (PCR) products. It also has efficient reverse transcriptase activity in the presence of manganese.

Ru *symbol for* ruthenium.

RU-486 *or* **RU-38486** mifepristone; 11*β*-(4-dimethylaminophenyl)-17*β*-hydroxy-17*α*-prop-1-ynylestra-4, 9-dien-3-one; a steroidal progesterone-receptor antagonist that prevents implantation of a fertilized ovum in the uterus. It is an effective contraceptive even when taken after coitus.

rubber a *cis*-1,4-polyisoprene with M_r varying from about 1×10^5 to 1×10^6, representing polymers of about 1500 to 60000 **isoprene** residues. It is found in the latex of about 300 different flowering plants, but only *Hevea brasiliensis* is a commercial source. A nonelastic rubber from *Manilkara bidentata* latex is known as **balata**. It is a *trans*-1,4-polyisoprene.

ruberythric acid the glycoside; 2-alizarin *β*-D-primeveroside, a major component of the plant dyestuff madder.



Rub 1 homologue of Nedd-8 *see* **Nedd**.

rubidium *symbol*: Rb; a silvery-white metallic element of group 1 of the IUPAC **periodic table**; atomic number 37; relative atomic mass 85.48. Highly reactive, it must be stored in an inert atmosphere. Rb$^+$ may be used experimentally as a K$^+$ analogue (sometimes as substitute, other times as competitor).

Rubinstein–Taybi syndrome *see* **CBP/p300**.

Rubisco *abbr. for* ribulose-bisphosphate carboxylase/oxygenase. It has **ribulose bisphosphate carboxylase** activity, and in a side-reaction with dioxygen it produces 2-phosphoglycolate (*see* **photorespiration**).

RuBP *abbr. for* ribulose 1,5-bisphosphate.

rubredoxin *abbr*.: Rd; any of a group of bacterial **iron–sulfur proteins** that are small, highly conserved, contain non-heme iron, and are non-enzymic. They lack acid-labile sulfur, and are characterized by having either one or two iron atoms each entirely in mercaptide coordination, i.e. surrounded by four cysteine residues or sulfur-containing ligands. They are electron acceptors for, e.g., hydrogenase-linked redox processes and hydroxylase systems. Rubredoxins of M_r 6 000–19 000 have been found in a number of bacteria. The ferric form is intense red; the ferrous form is colourless. *Compare* **ferredoxin**.

rudimentary a gene that in *Drosophila* is the equivalent of ***pyr-1*** in a number of other eukaryotes. It encodes a **CAD protein**.

ruffled edge *or* **ruffling** the appearance of the leading edge of a moving cell in culture, caused by the extension of microspikes and lamellipodia, which when not attached to the substratum have the appearance of ruffles in flimsy dress fabric.

rule *(in sequence analysis)* a short regular expression (typically 4–6 residues in length) used to identify generic (non-family-specific) patterns in protein sequences. Rules tend to be used to encode particular functional sites (e.g. sugar attachment sites, phosphorylation sites, glycosylation sites). Their small size means that they do not provide good discrimination, and can only indicate that a certain functional site *might* exist in a sequence.

Runt a protein of *Drosophila* that is involved in sex determination, segmentation, and neurogenesis. Its DNA-binding domain is homologous with that of Lozenge (of *Drosophila*) and AML1 (of human). Several Runt-related proteins occur in mammals.

RUNT domain *or* **runt homology domain** (*abbr*.: RHD) a 128-amino-acid DNA-binding domain occurring in **Runt** and other proteins required for the formation of hematopoietic, skeletal, gastrointestinal, and nervous systems in a variety of organisms. RHD proteins form a complex with core binding factor β (CBFβ).

***runt* gene** a *Drosophila* **pair-rule gene** encoding a transcription factor involved in segmentation.

Russell's viper venom the venom of Russell's viper, *Vipera russellii*, a snake of SE Asia. It is a source of enzymes especially phospholipases, proteases, and ribonucleases.

rusticyanin a blue, copper-containing, single-chain polypeptide obtained from a thiobacillus. It undergoes reduction during oxidation of Fe^{2+} with dioxygen. It is stable in acid, labile in alkali, and contains no arginine.

rutamycin *or* **oligomycin D** 26-demethyloligomycin A; an agent that is strongly inhibitory to a limited number of yeast and other fungal species. It inhibits mitochondrial ATPase F_1, preventing phosphoryl group transfer, but has no effect on isolated F_1 units. *See also* **oligomycin**.



rutamycin

ruthenium red ruthenium oxychloride ammoniated; $[(NH_3)_5–Ru–O–(NH_3)_4–O–Ru–(NH_3)_5]Cl_6•4H_2O$. A brownish-red, water-soluble inorganic compound, used in microscopy and electron microscopy as a stain for acid mucopolysaccharides. It inhibits the influx of Ca^{2+} ions into mitochondria at extremely low concentrations.

rutinose the disaccharide, 6-*O*-*β*-L-rhamnosyl-D-glucose; it occurs in rutin, the 3′-rutinoside of **quercetin**.



Ruv any of a family of three proteins involved in branch migration of a **Holliday junction**. In *E. coli*, Ruv A (209 amino acids) forms a homotetramer that binds the junction. Its crystal structure resembles a four-petalled flower and has four negatively charged projections at the centre. The junction fits in the concave face and is pierced at its centre by the projections. Ruv B (37 kDa) is a DNA-dependent ATPase that forms a homohexameric ring that binds dsDNA on each side of the Ruv A tetramer. Ruv C (19 kDa) is a nuclease that cleaves the crossover strands of the junction.

R_B value *or* **relative band rate** *or* **relative band speed** *(in chromatography) symbol*: R_B; the ratio of the distance travelled by a zone of the substance of interest to the distance simultaneously travelled by a reference substance B. *See also* **R_f value**.

R_f value *or* **R_F value** *or* **band rate** *or* **band speed** *symbol*: R_f *or* R_F ; *(in chromatography)* the ratio of the distance travelled by the centre of a zone of the substance of interest to the distance simultaneously travelled by the mobile phase. In paper and thin-layer chromatography, it is generally determined from the distance travelled by the substance from the origin and the distance travelled by the eluent front from the same point. [From 'rate relative to front'.]

RXR *abbr. for* **retinoid receptor**.

ryanodine a toxic alkaloid with insecticidal activity, isolated from *Ryania speciosa*. *See also* **ryanodine receptor**.



ryanodine receptor *abbr.*: RYR; any of a group of receptor proteins that bind **ryanodine**. Although first discovered in muscle, they occur in other cell types, and function as intracellular ligand-gated Ca^{2+}-release channels. In muscle, they provide communication between transverse tubules (**T-tubules**) and sarcoplasmic reticulum (SR); contraction of skeletal muscle is triggered by release of Ca^{2+} from SR following depolarization of T-tubules. The Ca^{2+} channel is modulated by Ca^{2+}, Mg^{2+}, and calmodulin. Three types are known: RYR1, the skeletal muscle type; RYR2, the cardiac muscle type; and RYR3, a highly truncated protein found in some nonmuscle cells. Cyclic ADP-ribose activates the RYR2 but not the RYR1 receptor. In muscle the receptors are tetrameric integral transmembrane glycoproteins. The C-terminal region is on the SR lumen side and contains four transmembrane helices per subunit; the N-terminal region (the major part of the molecule for RYR1 and 2) protrudes into the cytosol, where it forms a foot region in close proximity to the voltage-gated dihydropyridine receptors in T tubules. Deficiency is associated with malignant hyperthermia.

Ryk *abbr. for* related-to-tyrosine-kinase; a subfamily of the receptor tyrosine kinase superfamily. Members of Ryk have a short extracellular region that is related to the WIF domain. Homologues occur in *Drosophila*, *Caenorhabditis elegans*, and in most mammalian tissues.

RYN method a method for determining the plausibility of an **open reading frame**. A computational analysis of the sequence determines the frequency of the favoured codons R (purine), Y (pyrimidine), and N (anything). If these are found to be in the proportions expected from that normally found, it lends support to the fact that the correct **reading frame** has been selected, and that the open reading frame is correct.

RYR *abbr. for* ryanodine receptor.

Ss

s *symbol for* **1** second (def. 1). **2** solid state (in a chemical equation). **3** atomic orbital corresponding to an orbital angular momentum quantum number (l) = 0. **4** singlet (in nuclear magnetic resonance spectroscopy). **5** strong absorption (in infrared spectroscopy).

s *symbol for* **1** sedimentation coefficient. **2** solubility. **3** *(in monosaccharide nomenclature)* the **septanose** form; it is suffixed to the symbol for the corresponding monosaccharide; e.g. glucoseptanose is symbolized as Glc*s*. **4** specific entropy (i.e. **entropy**/mass). **5** spin quantum number.

s- *abbr.: for* ***sec-***.

S *symbol for* **1** sulfur. **2** siemens. **3** Svedberg unit ($S_{W,20}$ is the symbol under standard conditions). **4** a residue of the α-amino acid L-serine (alternative to Ser). **5** a residue of an incompletely specified base in a nucleic-acid sequence that may be either cytosine or guanine. **6** a residue of the ribonucleoside **thiouridine** when the position of the thiol group in its thiouracil moiety is unknown or unspecified (alternative to sU *or* Srd). **7** substitution (reaction mechanism).

^{2}S *symbol for* a residue of the ribonucleoside 2-thiouridine (alternative to s^2U); *see* **thiouridine**.

^{4}S *symbol for* a residue of the ribonucleoside 4-thiouridine (alternative to s^4U); *see* **thiouridine**.

S_N1 *abbr. for* unimolecular nucleophilic substitution.

S_N2 *abbr. for* bimolecular nucleophilic substitution.

$S_{W,20}$ *see* **S** (def. 3).

S *symbol for* **1** entropy. **2** spin quantum number (of a system). **3** strangeness quantum number. **4** area (alternative to *A*).

S *stereochemical descriptor* denoting *sinister*; i.e. the absolute configuration of a chiral compound in which the priority (obtained using the Cahn–Ingold–Prelog sequence rules) of the substituent groups on the chiral centre decreases in an anticlockwise (left-handed) direction. For use as a prefix in chemical nomenclature, the descriptor is placed in parentheses and connected with a hyphen; e.g. (*S*)-alanine. For chiral compounds in which the relative but not the absolute configuration is known, *sinister* configuration is denoted by the prefix (*S**)-. *See* **sequence rule**. *Compare* ***R***.

S- *prefix (in chemical nomenclature)* denoting substitution on a sulfur atom in a compound; a particular sulfur atom may be specified by a right superscript.

-S *conformational descriptor* designating the **skew conformation** of a six-membered ring form of a monosaccharide or monosaccharide derivative. Locants of ring atoms that lie on the side of the structure's reference plane from which the numbering appears clockwise are indicated by superscripts preceding the letter, and those that lie on the other side of the reference plane by subscripts following the letter; e.g. 1,2-*O*-ethylidene-α-D-glucopyranose-$^1S_3$. *See also* **conformation**.

s.a. *abbr. for* specific activity.

SAA *abbr. for* serum amyloid A; *see* **amyloid A protein**.

SABP *abbr. for* secretory actin-binding protein.

saccharase any hydrolase that hydrolyses the fructose (**fructosaccharases**) or glucose (**glucosaccharases**) end of appropriate oligosaccharides, liberating fructose or glucose respectively. The term is also used for **invertase** (which is both a fructosaccharase and a glucosaccharase).

saccharate *see* **glucarate**.

saccharic acid **1** *an old name for* **aldaric acid**. **2** *an old name for* glucaric acid; *see* **glucarate**.

saccharide any carbohydrate, especially a simple sugar, i.e. a **monosaccharide**, **disaccharide**, or short-chain **oligosaccharide**. *See also* **polysaccharide**.

saccharification the hydrolysis of sugar derivatives or complex carbohydrates to soluble, fermentable sugars.

saccharimeter an instrument for measuring the amount of sugar in a solution, especially a **polarimeter** used for such a purpose. *Compare* **saccharometer**.

saccharin 2,3-dihydro-3-oxobenzisosulfonazole; *O*-sulfobenzimide; an artificial, nonnutritive sweetener that is several hundred times sweeter than sucrose. Rats receiving high doses produce tumours of the urinary tract but there is no clear-cut evidence of such an effect in humans.



saccharogenesis the process of producing soluble, fermentable sugars from a complex carbohydrate. —**saccharogenic** *adj.*

saccharogenic method a method for assaying amylase and similar enzymes that hydrolyse polysaccharides, based on determination of the amount of simple sugar product formed by the enzyme.

saccharometer an instrument for measuring the amount of sugar in a solution, especially a **hydrometer** specially calibrated for the purpose. *Compare* **saccharimeter**.

Saccharomyces a genus of budding yeasts that reproduce asexually by budding or sexually by conjugation. They are used especially as simple model organisms in the study of eukaryotic cell biology, and in genetic engineering. *Saccharomyces cerevisiae* is used in bread-making and in the production of alcoholic beverages and industrial alcohol. It divides vegetatively in either the haploid or diploid phase. This permits the isolation of recessive mutations in the haploids and complementation testing in the diploids. Transformation procedures that permit DNA uptake by either **protoplasts** or whole yeast cells have been developed and cloning vectors constructed. In cases where a recombinant **glycoprotein** is desired, yeast has proved very useful since it can, unlike bacteria, effect post-translational **glycosylation**. It has been used for the production of a vaccine for hepatitis B.

saccharopine N^6-[1,3-dicarboxypropyl]-L-lysine; an intermediate in the **aminoadipic pathway** for lysine biosynthesis (e.g. in *Saccharomyces* spp., hence the name) and for lysine catabolism (e.g. in mammalian liver). The reactions involved are:

lysine + 2-oxoglutarate ⇌ saccharopine ⇌ glutamate +
2-aminoadipate 6-semialdehyde;

they are catalysed by **saccharopine dehydrogenases**, which are characterized as lysine-forming or glutamate-forming, and require either NAD^+/NADH or $NADP^+$/NADPH as coenzyme; *see* **saccharopine dehydrogenase (NAD^+,** L-glutamate-forming) and **saccharopine dehydrogenase (NAD^+,** L-lysine forming). The latter is also called lysine-2-oxoglutarate reductase. In mammals both are part of the bifunctional **aminoadipic semialdehyde synthase**. *See* **familial hyperlysinemia**.



saccharopine dehydrogenase (NAD^+, L-glutamate-forming) EC 1.5.1.9; an enzyme involved in the synthesis and degradation of lysine. It catalyses the oxidation by NAD^+ of N^6-(L-1,3-dicarboxypropyl)-L-lysine to L-glutamate and 2-aminoadipate 6-semialdehyde with formation of NADH. In bovine and human liver, this activity, with that of lysine-2-oxoglutarate reductase, forms part of the bifunctional aminoadipic semialdehyde synthase. Another saccharopine dehydrogenase uses the same reaction mechanism, in which the coenzyme is $NADP^+$: EC 1.5.1.10, saccharopine dehydrogenase ($NADP^+$: L-glutamate-forming).

saccharopine dehydrogenase (NAD^+, L-lysine-forming) *or* **lysine–2-oxoglutarate reductase** EC 1.5.1.7; an enzyme involved in the synthesis and degradation of lysine. It catalyses the reaction between L-lysine, 2-oxoglutarate, and NADH to form N^6-(L-1,3-dicarboxypropyl)-L-lysine (**saccharopine**), NAD$^+$, and H_2O. In mammals this activity, with that of saccharopine dehydrogenase (NAD$^+$, L-glutamate forming), is part of the bifunctional aminoadipic semialdehyde synthase safety cabinet.

saccharopinuria a rare, autosomal recessive, generally benign condition in which **saccharopine** excretion in urine is prominent. It is a variant of **familial hyperlysinemia**.

saccharose *an old name for* **sucrose**.

Sac1p a single-pass transmembrane protein (623 amino acids) of yeast that is a polyphosphoinositide phosphatase.

SACS *abbr. for* **spastic ataxia of Charlevoix-Saguenay**.

sacsin a protein encoded by the single-exon gene (12 794 bp) for **spastic ataxia of Charlevoix-Saguenay**. A homologue is present in mouse. It contains two copies of a ubiquitous ATPase domain, a histidine kinase A domain, and Hsp70 DNAJ domain, and at residues 3701–3817 a domain (*see* **HEPN domain**) for which sacsin is the prototype.

Saethre–Chotzen syndrome the most common autosomal dominant craniosynostosis disorder in humans. Many mutations in **TWIST** protein cause the craniofacial and limb abnormalities.

SAF *abbr. for* scaffold attachment factor.

safety cabinet a cabinet providing an area at bench level in which pathogenic agents may be handled or stored while preventing their entry into the atmosphere outside the cabinet; at the same time, sterility within the cabinet is normally ensured. Usually the cabinet is ventilated with a stream of air, which is extracted through a **HEPA filter** system that traps any pathogens. Cabinets are classified according to the level of protection they offer. **Class I** cabinets have an inward flow of air through the front aperture providing protection for personnel and the environment. **Class II** cabinets are ventilated by a downward flow of filtered air; this is extracted so as to ensure also an inward flow through the front aperture, the extracted air being recirculated through the filter and providing protection for personnel, sample, and environment. **Class III** cabinets are for more potentially hazardous materials; there is no front aperture, the operator manipulating the interior components using gloves mechanically sealed into the front of the cabinet. They provide absolute personal, environmental, and sample protection.

SAG *abbr. for* senescence-associated gene.

SAGA complex a histone acetyltransferase complex (≈2 MDa) that can be recruited by transcription activators in yeast and in mammals. It preferentially acetylates histone H3 and contains at least 14 subunits.

SAGE *abbr. for* **serial analysis of gene expression**.

SAH *abbr. for* *S*-adenosyl-L-homocysteine; *see* ***S*-adenosylhomocysteine**.

SAICAR *or* **SACAIR** *abbr. for* 1-(5-phosphoribosyl)-5-amino-4-(*N*-succinocarboxamide)-imidazole.

SAICAR synthetase *see* **phosphoribosylaminoimidazole-succinocarboxamide synthase**.

Sakaguchi test a test for guanidines, i.e arginine and peptides that contain it; in alkaline solution they give a red colour with the **Sakaguchi reagent**, which contains α-naphthol and sodium hypochlorite.

salbutamol *other name*: albuterol; 4-hydroxy-3-hydroxymethyl-α-[*tert*-butylamino)methyl]-benzyl alcohol, α^1-[[1,1-dimethylethyl)-amino]methyl]-4-hydroxy-1,3-benzenedimethanol; a β-adrenergic agonist whose β_2-**adrenoceptor** activity is about 60 times that of **isoproterenol**.



salicylic acid 2-hydroxybenzoic acid; a water-soluble derivative of phenylalanine in plants, where it is formed by hydroxylation of benzoic acid. It initiates thermogenesis in the voodoo lily (in which process it has been called calorigen) and is associated with resistance to infection by fungi, bacteria, and viruses by inducing pathogenesis-related proteins. It is the active ingredient (as methylsalicylate, saligenin, or their glycosides) responsible for the analgesic action of plants such as willow, poplar, and meadowsweet, which have been used for this purpose for over two millennia. It is the active ingredient of the very versatile drug acetylsalicylic acid (*see* **aspirin**).

saline 1 of, concerned with, or containing common salt (sodium chloride). **2** of, or containing, salts of alkali metals or magnesium. **3** an aqueous solution of sodium chloride and (sometimes) other salts, of defined osmolarity, prepared for intravenous injection or perfusion; usually 0.9% w/v sodium chloride. *See also* **physiological saline**.

saliva the mixed secretions of the salivary glands and of the mucous membrane of the mouth. It contains an α-**amylase** (ptyalin), mucin, various inorganic ions, urea, buffers, lysozyme, etc., and has a pH near 7. It is secreted in response to food, which it moistens and lubricates; the amylase may also hydrolyse ingested starch. *See also* **sialic**. —**salivary** *adj.*

salivary gland any of the various glands that discharge **saliva** into the mouth. In humans there are three pairs: the parotid, sublingual, and submaxillary glands. In snakes they include the venom glands.

salivary juice the collective secretions of the salivary glands; i.e. **saliva**. Its secretion was studied by the Russian physiologist Ivan Pavlov (1849–1936), and led him to the discovery of the conditioned reflex.

Salkowski test a test for cholesterol. When concentrated sulfuric acid is added to a chloroform solution of cholesterol, the chloroform layer shows a red to blue colour and the acid layer shows a green fluorescence. [After Ernst Leopold Salkowski (1844–1923), German physiological chemist.]

Salla disease an autosomal recessive disorder, rather frequent in Finland, in which a variable degree of psychomotor retardation accompanies accumulation of free sialic acid (and glucuronic acid) in lysosomes and excessive excretion of sialic acid in urine. Patients have a near normal lifespan. It is caused by mutations in the gene for **sialin**, and is a milder form of infantile sialic acid storage disease.

salmine a 6–7 kDa **protamine**, found in salmon sperm.

salmon any of various fish of the family Salmonidae, which live in coastal waters of the North Atlantic and North Pacific and breed in rivers. Their flesh is comparatively rich in oils with a high content of long-chain *n*-3 **fatty acids**; typical composition (major fatty acids, expressed as % of total fatty acids): 16:0, 10; 16:1(*n*-7), 5; 18:0, 4; 18:1 (*n*-9), 24; 18:2(*n*-6), 5; 18:3(*n*-3), 5; 20:1(*n*-9), 1; 20:4(*n*-6), 5; 20:5(*n*-3), 5; 22:6(*n*-3), 17.

Salmonella a genus of rod-shaped, motile, aerobic bacteria including the agents responsible for typhoid fever (*S. typhi*), some types of food poisoning, and other enteric diseases.

***Salmonella* mutagenesis test** *or* **Ames test** a method of screening chemicals for carcinogenicity by their mutagenic effect on selected strains of *Salmonella typhimurium* – there being a high correlation between mutagenicity and carcinogenicity. The strains normally used are those that require histidine. They are plated out on histidine-deficient medium after being mixed with the potential mutagen. Mutations induced by the test substance that restore the ability to synthesize histidine are revealed by colonies growing on the plate.

salmon sperm DNA a preparation of DNA used for prehybridization, and hybridization, of membranes used for Northern or Southern blotting of mammalian RNA and DNA. It is chosen because its evolutionary distance from mammals makes it unlikely to bind DNA probes under the conditions of hybridization.

salt 1 any member of a class of compounds formed, together with water, by reaction of an acid with a base (most commonly an inorganic acid and metallic base). **2** *or* **common salt** sodium chloride.

saltation 1 the action of jumping or leaping. **2** proceeding in a discontinuous manner by leaps interspersed by periods of rest. **3** an irreversible and inherited change in a cell or organism due to mutation. —**saltatory** *adj.*

saltatory conduction the passage of a nerve impulse across a gap, as between the nodes of Ranvier in a myelinated nerve fibre.

saltatory evolution evolution by sudden changes or by periods of active change with intervening inactive periods.

saltatory replication a hypothetical, sudden lateral replication of DNA thought to be responsible for the production of families of similar nucleotide sequences.

salt bridge **1** a tube, usually closed with porous plugs, that is filled with a solution of a salt (often potassium chloride, commonly saturated) and used to obtain electrical contact between two electrolytic half-cells without intermingling of their respective electrolytes. **2** any electrostatic bond, between positively and negatively charged groups on amino-acid residues of a protein, that contributes to the stability of the protein structure.

salt fractionation the differential precipitation of proteins, or nucleic acids, from solution by the addition of neutral salts, often ammonium sulfate. *Compare* **salting out**.

salting in the increase in the solubility of certain proteins (e.g., globulins) and dipolar ions (e.g., cystine), produced in solutions of low ionic strength by an increase in the concentration of neutral salts.

salting out the decrease in the solubility of proteins, gases, uncharged molecules, and, in sufficiently concentrated solutions, electrolytes, produced in solutions of high ionic strength by an increase in the concentration of neutral salts.

salting-out chromatography a method of chromatography whereby water-soluble organic compounds are separated by ion-exchange chromatography by use of an aqueous salt solution as eluent.

salting-out constant *symbol*: K'_S; the slope of the straight line relating the logarithm of the solubility of a substance in neutral salt solutions and the ionic strength. It is given by

$$K'_S = -[\log(s/s^*)]/I,$$

where s is the solubility in mol dm^{-3} at ionic strength I, and s^* is the hypothetical solubility at zero ionic strength.

salt link *or* **salt linkage** an **ionic bond**.

salvage pathway any metabolic pathway that utilizes for biosynthetic purposes compounds formed in catabolism. Thus, free purine and pyrimidine bases may be converted to the corresponding ribonucleotides. In the case of purines, the ribose phosphate moiety of 5-phospho-α-D-ribosyl diphosphate (I) is transferred to the purine; thus

$$\text{adenine} + \text{I} = \text{adenylate} + \text{PP}_i.$$

See also **purine biosynthesis**.

SAM *abbr. for S*-adenosylmethionine.

SAMase *abbr. for S*-adenosylmethionine cleaving enzyme (*S*-adenosylmethionine hydrolase; EC 3.3.1.2).

same-sense mutation *an alternative name for* **silent mutation**.

sample a small, separated portion of the whole. In experimentation it is often essential that the sample be fully representative of the characteristics of the whole (and always so for a **statistical sample**).

sample applicator a device to aid application of samples to chromatography plates, etc.

sample well a hole cut in an electrophoresis gel in which the sample to be analysed is placed.

sampling error *(in statistical analysis)* the chance difference between a measurement obtained from a **sample** and the corresponding measurement obtained from the whole population.

Sandhoff's disease *see* **gangliosidosis**.

sandwich assay *or* **sandwich technique** a type of immunoassay in which antibody against the antigen to be assayed is bound to a solid surface (e.g. plastic). After addition of solution containing antigen the fixed antigen is washed. A second antibody, which is radioactive or fluorescent, is added, sandwiching the antigen; after removal of excess, the amount of bound label is determined. The second antibody may be specific for a different epitope on the antigen, thus enhancing overall specificity, or for the first antibody bound to an antigen.

sandwich complex a 2:1 macrocycle:cation complex in which the metal ion is held between two parallel macrocyclic **complexones**.

sandwich technique *an alternative name for* **sandwich assay**.

sandwich test an immunohistochemical procedure employing a **sandwich assay** to detect an antibody within a cell.

Sanfilippo syndrome A *an alternative name for* **mucopolysaccharidosis type IIIA**.

Sanfilippo syndrome B *an alternative name for* **mucopolysaccharidosis type IIIB**.

Sanfilippo syndrome C *the alternative name for* **mucopolysaccharidosis IIIC**.

Sanfilippo syndrome D *the alternative name for* **mucopolysaccharidosis IIID**.

Sanger method **1** (for identifying and estimating N-terminal amino-acid residues of polypeptides) a method in which free unprotonated amino groups react with 1-fluoro-2,4-dinitrobenzene (FDNB). The dinitrophenylamino groups formed are stable to the acid used to hydrolyse the peptide bonds; the yellow arylated (DNP-) amino acids so released can then be identified by chromatography and estimated spectrophotometrically. **2** (for polypeptide sequencing) a general method for deriving the primary sequence of a polypeptide chain, based on selective hydrolytic degradation of the chain into smaller peptides. The sequence of each smaller peptide may then be found by use of FDNB to label its N-terminal amino acid, together with total hydrolysis to give the amino-acid composition and further stepwise degradation by use of carboxypeptidase or by **Edman degradation**. By selection of degradation procedures to ensure overlap of sequences between the various smaller peptides, the overall sequence of the starting material may be determined. **3** (for DNA sequencing) *an alternative name for* **chain-termination method**. [After Frederick Sanger (1918–), British biochemist.]

Sanger's reagent 2,4-dinitrofluorobenzene (*abbr.*: DNFB); 1-fluoro-2,4-dinitrobenzene (*abbr.*: FDNB); a substance used in structural protein chemistry to arylate free amino groups. *See* **Sanger's method** (def. 1, 2).



sanitizer a substance that significantly reduces the bacterial population in the inanimate environment but does not destroy or eliminate all microorganisms. *Compare* **disinfectant**, **sterilant**.

SAP *abbr. for* **1** Sin 3-associated protein; *see* **Sin 3-HDAC**. **2** serum amyloid P-component. **3** sphingolipid activator protein. **4** *see* **SAP domain**.

SAP domain *abbr. for* SAF-A/B, Acinus, and PIAS domain; a peptide sequence (35 amino acids) predicted to form two DNA-binding amphipathic alpha helices and present in proteins involved in chromosomal organization (e.g. SAF-A/B, **Acinus**, and **PIAS**).

sapecin an insect **defensin** that is active against (mainly Gram-positive) bacteria. It has a high affinity for **cardiolipin**.

SAPK *abbr. for* stress-activated (*or* stress-associated) protein kinase.

sapogenin any of the **aglycon** moieties of **saponins**; they may be steroids or triterpenes.

saponifiable fraction the portion of total lipid that, after treatment with hot alkali, is soluble in water and insoluble in ether.

saponifiable lipid any **lipid** that can be hydrolysed with alkali to give soap (fatty-acid salts) as one product; they include any **glycolipid**, **cholesteryl ester**, or **sphingolipid**.

saponification the hydrolysis of an **ester** by an alkali to give the alcohol and salt of the acid. Originally the term meant the hydrolysis of a neutral fat by alkali (e.g. potassium hydroxide) into glycerol and a soap. —**saponify** *vb.*

saponification equivalent the amount in grams of an ester that consumes one gram-equivalent of alkali in **saponification**. *Compare* **saponification number**.

saponification number the number of milligrams of potassium hydroxide consumed in the complete **saponification** of one gram of any particular fat, oil, or wax. *Compare* **saponification equivalent**.

saponin any of the glycosides, widely distributed in plants, that are powerful **surfactants**. Each saponin consists of an aglycon moiety (i.e. **sapogenin**), which may be a steroid or a triterpene, and a sugar moiety, which may be glucose, galactose, a pentose or methylpentose, or an oligosaccharide. All saponins foam strongly when shaken with water. They are membrane-active, powerful hemolytic agents and are used at low concentrations to **permeabilize** cells. They are highly toxic on injection, but not on ingestion as they are not absorbed through the gut. *See also* **digitonin**.

saponin detoxifying enzyme an enzyme that prevents activity of antifungal **saponin**s.

sapor that which is sensed by taste; any quality relating to taste or savour. —**saporific** *or* **saporous** *adj.*

saporin a type I **ribosome-inactivating protein**, EC 3.2.2.22, from the soapwort, *Saponaria officinalis*.

saposin *or* **sphingolipid activator protein** any of a group of peptide cofactors of enzymes for the lysosomal degradation of sphingolipids. They stimulate various enzymes, including glucosylceramidase, galactosylceramidase, cerebroside-sulfatase, *α*-galactosidase, *β*-galactosidase, and sphingomyelin phosphodiesterase. Saposins A to D are known. Deficiency of any may cause a mild form of a **sphingolipidosis** that normally results from deficiency of an enzyme the saposin activates. They contain characteristic domains, known as saposin A-type or B-type domains. As examples, from the human precursor, saposin A and saposin C together stimulate hydrolysis of glucosylceramide by *β*-glucosylceramidase (EC 3.2.1.45) and of galactosylceramide by *β*-galactosylceramidase (EC 3.2.1.46). Saposin C deficiency causes a variant of **Gaucher's disease**. Saposin B is a homodimer, and forms a solubilizing complex with the substrates of the sphingolipid hydrolases; deficiency causes a variant of **metachromatic leukodystrophy**. Saposin D is a specific activator of sphingomyelin phosphodiesterase (EC 3.1.4.12), and deficiency causes a variant of **Tay–Sachs disease** (G_{M2} gangliosidosis). *See also* **swaposin**.

saprophyte any plant, fungus, or microorganism that lives on dead or decaying organic matter. —**saprophytic** *adj.*

saquinavir a peptidomimetic antiviral drug that contains phenyl and other bulky groups and inhibits HIV protease by binding to its active site.

SAR *abbr. for* scaffold-associated region; *other name*: matrix-associated region (*abbr.*: MAR). A DNA sequence of interphase chromosomes that binds them to the nuclear matrix.

SARA *abbr. for* Smad anchor for receptor activation; a protein that recruits Smad2 to transforming growth factor β receptors for phosphorylation by their protein serine/threonine kinase. *See* **Smad**.

sarafotoxin any of the toxic peptides from the burrowing asp, *Atractaspis engaddensis*. They cause cardiac arrest when injected into mice, and are strong vasoconstrictors. All have 21 amino acids, with four cysteine residues in identical positions and tryptophan at the C terminus. They are homologous with **endothelins** and have endothelin receptor agonist action. Sarafotoxin S6D has the sequence

CTCKDMTDKECLYFCHQDIIW.

See also **bibrotoxin**.

Saran Wrap *proprietary name for* a vinylidene chloride copolymer cling-film used for gel drying, food storage, etc.

α-sarcin a cytotoxin produced by *Aspergillus giganteus*. It has ribonuclease activity, specific for purines in both single-stranded and double-stranded RNA. It inhibits protein synthesis, cleaving a single phosphodiester linkage between guanosine and adenosine residues in 28S rRNA in the 60S' subunit of the eukaryotic ribosome, resulting in loss of 393 nucleotides from the 3′ end of 28S rRNA. This single site of action in the intact ribosome contrasts with its action on purified 28S rRNA, in which it causes extensive degradation, cutting on the 3′ side of every adenine or guanine.

sarcoglycan a complex of proteins found in skeletal and cardiac muscle, associated with the dystrophin glycoprotein complex but of unknown function. It consists of four type I transmembrane proteins: α, (50 kDa), also known as adhalin; β (43 kDa); γ (35 kDa); and δ (35 kDa). The α, γ, and δ proteins are expressed exclusively in muscle, whereas the β protein occurs predominantly in muscle. Mutation in any of them causes limb-girdle muscular dystrophy.

sarcolemma the outer membrane of a muscle fibre. It consists of the plasma membrane, a covering basement membrane (about 100 nm thick and sometimes common to more than one fibre), and the associated loose network of collagen fibres. The term was first used to designate the line visibly marking the outer fibre edge.

sarcoma a malignant tumour of connective tissue or of its derivatives. —**sarcomatous** *adj.*

sarcomere the functional unit of a myofibril of vertebrate muscle, about 2.3 μm long. In **striated muscle** the sarcomeres of many parallel myofibrils are positioned such that myosin **thick filaments** are aligned in register across the myofibril (having a dense appearance in microscopic preparations), as also are the actin **thin filaments** (which have a lighter appearance), resulting in the alternation of light, isotropic bands known as **I bands**, and dark, anisotropic bands known as **A bands**; the I band is bisected by a very dense, narrow **Z line**, while the central, less dense region of the A band is known as the **H zone**, which in turn is bisected by the dark **M line**, or midline, the location of specific proteins that link adjacent thick filaments to each other. The Z lines are due to attachment sites for thin filaments.

sarcoplasm all of the contents of a muscle fibre except nuclei. The sarcoplasm is pervaded by the **sarcoplasmic reticulum**. *Compare* **cytoplasm**. —**sarcoplasmic** *adj.*

sarcoplasmic reticulum *abbr.*: SR; a fine reticular membranous network that pervades the **sarcoplasm** of a muscle fibre. Like the endoplasmic reticulum the SR is continuous over large portions of the cell, it has a large surface-to-volume ratio, and is continuous with and/or homologous to the nuclear envelope. At the level of the I band (*see* **sarcomere**), the SR forms dilated sacs, or cisternae. Opposite the I bands and Z lines of every sarcomere two SR terminal sacs face each other across a narrow space, through which run **T tubules**. At the level of the A–I junction longitudinally orientated SR sacs run along the fibril, forming a pallisade around the A band. The SR contains a Ca^{2+}-translocating ATPase that moves Ca^{2+} into the SR during ATP hydrolysis; ATP resynthesis is associated with movement of Ca^{2+} out of the SR vesicles.

sarcosine *N*-methylglycine; an intermediate in the conversion of choline, via betaine and dimethylglycine, to glycine, and in the synthesis of choline from glycine. *See also* **sarcosinemia**.

sarcosine dehydrogenase EC 1.5.99.1; a mitochondrial flavoprotein enzyme that catalyses the reaction:

$$\text{sarcosine} + \text{acceptor} + H_2O = \\ \text{glycine} + \text{formaldehyde} + \text{reduced acceptor}.$$

The flavin is FAD. The acceptor is electron-transfer flavoprotein.

sarcosinemia *or* (*esp. Brit.*) **sarcosinaemia** a rare inherited metabolic disease of humans, also found in ethylnitrosourea-induced mutants of mice, giving elevated plasma and urine levels of **sarcosine**. Primary sarcosinemia results from deficiency of **sarcosine dehydrogenase** (EC 1.5.99.1). Sarcosinemia may also be caused by folate deficiency (*see* **folic acid**) in humans, and occur in glutaric aciduria type II, but in primary sarcosinemia elevated levels of other organic acids are not found. Inheritance is probably autosomal recessive.

sarcosome a subcellular organelle found in muscle tissue with similar biochemical properties as a **mitochondrion** in other tissues. In muscles that are largely anaerobic, such as skeletal muscles of vertebrates and invertebrates, sarcosomes are found near the I bands (*see* **sarcomere**). In predominantly aerobic muscles, such as bird and insect flight muscles and vertebrate heart muscle, sarcosomes are found near the A bands.

sarcotubule *another name for* **T tubule**.

sarin methylphosphonofluoridic acid 1-methylethyl ester; an **organophosphate** (def. 2) that inhibits acetylcholinesterase and other serine esterases. It is a nerve gas but is useful in the treatment of leprosy and has some effect on AIDS.

Sarkosyl sodium lauroyl sarcosinate; a mild anionic surfactant used for solubilizing membrane proteins.

D-sarmentose 2,6-dideoxy-3-*O*-methyl-D-*xylo*-hexose; a substance found as a component of some **cardiac glycosides**.



SARS *abbr. for* severe acute respiratory syndrome. *See* **coronavirus.**.

satellite colony any of numerous small bacterial colonies that can surround a large antibiotic-resistant colony when grown on nutrient agar plates. When the antibiotic is ampicillin the secretion of β-lactamase by the resistant colony depletes the antibiotic in the surrounding medium thereby permitting nonresistant bacteria to grow in that zone.

satellite DNA a fraction of DNA, amounting to 10% or more of total DNA in most eukaryotic cells, with a highly repetitive nucleotide sequence. Its base composition gives rise to a 'satellite' band having a different buoyant density when DNA preparations, following **shear** force degradation, are centrifuged in cesium chloride density gradients. Mouse satellite DNA contains about a million copies of a sequence of 300 bp with a lower (G+C) content than that of the moderately repetitive and unique DNA sequences. *See also* **minisatellite**.

satellite RNA small RNAs (≈350 bases) also called **virusoids**, found in plants; they are **encapsidated** by some plant viruses. *See also* **ribozyme**.

satellite virus a small virus that occurs in association with another virus, upon which it is dependent. **Satellite tobacco mosaic virus** (STMV) is a 172 Å diameter particle containing a 1059 nt RNA that encodes only two proteins, the 159-residue viral coat protein and a 58-residue protein of unknown function. STMV can only multiply in cells coinfected with tobacco mosaic virus.

saturable capable of undergoing **saturation** (def. 5). **—saturability** *n.*

saturated fatty acid any **fatty acid** in which the carbon–carbon bonds of the alkyl chain are exclusively single bonds. The predominant natural ones are **palmitate** and **stearate**; others include **laurate**, **myristate**, arachidate (*see* **arachidic acid**), behenate (*see* **behenoyl**), **lignocerate**, and cerotate (*see* **ceretoyl**). They can all be derived metabolically from acetyl-CoA, in animals and plants. *See also* **fatty-acid nomenclature**.

saturates *an informal term for* **saturated fatty acids**.

saturation 1 (of a chemical compound) the point at which all the valence bonds of the component atoms are satisfied, especially the state of an organic compound that contains only single carbon–carbon bonds. **2** (of a solution) the state in which it has the greatest concentration of the solute that can remain in stable equilibrium with undissolved solute at a given temperature and pressure. **3** (of a gas) the state in which there is the greatest concentration of the vapour associated with a liquid or solid that can remain in stable equilibrium with unvaporized liquid or solid, respectively, at a given temperature and pressure. **4** (of an active site of an enzyme or transporter) the point at which the site is fully occupied with ligand. Saturable enzyme or receptor systems exhibit hyperboliform or sigmoid curves of activity versus concentration (*see* **saturation kinetics**). **5** the act or process of bringing to or towards saturation; especially the addition of hydrogen to triple and double bonds.

saturation analysis *or* **binding assay** a development of **isotope dilution analysis** used for the measurement of very low concentrations of biologically active substances in small samples of complex mixtures such as biological fluids. The essential steps are: (1) the substance, S, is allowed to react with a fixed amount of a specific binding agent under conditions such that the latter is always fully saturated with S; (2) the partitioning of S between the free and bound states is determined by the use of an indicator and by physical separation of the free from the bound form; and (3) the distribution of the indicator is compared with distributions obtained using a series of known amounts of S. The indicator is a form of pure S labelled with a radioisotope of high specific activity; alternatively, fluorescent, enzymic, or other labels may be used if they give the required sensitivity. The specific binding agent is generally an antibody, as in **enzyme immunoassay**, **fluoroimmunoassay**, or **radioimmunoassay**, or a naturally occurring macromolecular carrier or cellular receptor, as in **competitive protein-binding assay**.

saturation fraction *symbol*: *y*; the ratio of the concentration of bound ligand to the total concentration of the binding agent. Hence, in a binding reaction where a compound P binds X to form PX, then $y = [PX]/[P_{total}]$. A plot of *y* against [X] is known as the **adsorption isotherm** for this system.

saturation kinetics the kinetics of a reaction (or of **mediated transport**) when the velocity of the reaction (or of the transport) increases to a maximal value (plateau) as the concentration of the reactant (or of a component being transported) is increased.

saturation ratio *or* **cooperativity index** *symbol*: R_s; (of an allosteric protein) the ratio of the concentration of the substrate (or other small molecule) necessary to produce 90% to that required to produce 10% saturation of the specific sites on a protein. It is a convenient measure of the extent of cooperativity. *See also* **cooperative ligand binding**.

saxiphilin a protein, derived from the bullfrog, that is related to transferrin and binds saxitoxin with great affinity.

saxitoxin *abbr.*: STX; a paralytic poison, produced by the marine dinoflagellates *Gonyaulax catenalla* and *G. excavata*. It can be accumulated by shellfish, making them toxic when eaten. Its action is similar to that of **tetrodotoxin**, with which it competes for sodium channels.

Sb *symbol for* antimony.

SBH *abbr. for* sequencing by hybridization; a hypothetical method yet to be implemented for the very rapid sequencing of DNA. It is based on the idea of having all possible octamers (there are 63536) on a small hybridization screen called a DNA chip. As the octamers form nested arrays, a DNA fragment (of a few hundred bases) would only hybridize to some of these and the sequence could be deduced computationally.

SBP2 *abbr. for* SECIS-binding protein 2; a mammalian protein (≈94 kDa) that binds the selonocysteine insertion sequence (**SECIS**) of mRNA for selenoproteins and is required for selenocysteine insertion into the latter. It binds through a 32-amino acid sequence that it shares with several ribosomal proteins. SBP2 also binds the mRNA at a region 5′ to the SecUDA codon. *See also* **SelB**.

SBS model *or* SBS *abbr. for* side-by-side model.

sc *abbr. for* synclinal (def. 2).

s.c. *abbr. for* subcutaneous.

Sc 1 *symbol for* scandium. **2** *abbr. for* secretory component (*see* **secretory piece**).

SCAD *abbr. for* short-chain acyl-CoA dehydrogenase *or* butyryl-CoA dehydrogenase; *see* **beta-oxidation system**.

SCAF *abbr. for* SR-like CTD-associated factor; *other name*: CTD-associated SR-like protein (*abbr.*: CASP); any protein that is homologous with splicing regulatory (SR) proteins and binds to the C-terminal domain (CTD) of the largest subunit of RNA polymerase II. *See* **SR protein**.

scaffold *(in gene sequencing)* an ordered set of **contigs** that are in the right order but do not necessarily form a contiguous stretch of sequence.

scaffold attachment factor *abbr.*: SAF; either of two nuclear proteins (SAF-A and SAF-B) of humans that bind AT-rich chromosomal regions termed scaffold attachment regions. They bind DNA through an N-terminal **SAP domain**. SAF-A also binds ATP and is a target for cleavge by caspase during apoptosis. SAF-B (or SAF-145) also contains a conserved domain seen in proteins involved in splicing of pre-mRNA.

scaffolding protein any of a group of proteins that have specific binding sites for, and are instrumental in determining the structure and assembly of, large 3-D structures, such as viruses. Such proteins are integral to the **self-assembly doctrine** elaborated by Caspar and Klug.

scalar 1 a physical quantity, such as mass or time, that is characterized only by its magnitude and does not contain any concept of direction. **2** describable by a number representing a point on a scale undirected in space. *Compare* **tensor**, **vector** (def. 1).

scaler an electronic circuit or device that counts electrical pulses by aggregating the pulses and giving one output pulse for a predetermined number of input pulses.

scalloped the DNA-binding component of the selector complex for wing formation in *Drosophila*.

SCAM *abbr. for* substitute cysteine accessibility method; a method used in studying integral membrane proteins, in which specific amino acids are mutated to cysteine and their accessibility is then tested by thiol-reacting chemicals.

SCAMP *abbr. for* secretory carrier membrane protein; a Ca^{2+}-binding protein with leucine zipper and zinc finger. SCAMPs are components of post-Golgi membranes, and function in recycling proteins between the Golgi and the cell surface.

scanner an instrument or device used to measure or sample the distribution of some quantity or condition in a particular system, area, or region, e.g. to measure the distribution of colour or radioactivity on a chromatogram or electrophoretogram, or to measure the radial distribution of light absorbance in a cell in an ultracentrifuge.

scanning electron microscope *abbr*.: SEM; *see* **electron microscope**.

scanning proton microprobe an instrument in which a sample is bombarded by a high-energy (1–4 MeV) proton beam, causing emission of X-rays that can be characteristically attributed to certain elements. The technique permits the detection of elements down to about 1 ppm.

SCAP *abbr. for* SREBP-cleavage activating protein; a membrane protein of the endoplasmic reticulum and Golgi apparatus that regulates cleavage and release of the transcriptional domain of **SREBP** by **S1P** and **S2P** acting in sequence. It consists of N-terminal transmembrane segments (of which five constitute a sterol-sensing domain), and a cytoplasmic C-terminal region that contains five **WD40** repeats and interacts with the regulatory domain of SREBP. Cholesterol and polyunsaturated fatty acids, acting via the sterol-sensing domain, inhibit cleavage of SREBP and release of its transcriptional domain.

Scatchard plot a method of analysis of the binding of ligand to a macromolecule (or receptor), based on the **Scatchard equation**, $\bar{v}/[\mathrm{L}] = (n - \bar{v})K$, where $\bar{v}$ is the average number of ligand molecules bound per binding macromolecule, [L] is the free ligand concentration, n is the number of binding sites on the macromolecule and K is the intrinsic association constant. A plot is made of $\bar{v}/[\mathrm{L}]$ on the y-axis and $\bar{v}$ on the x-axis. If the binding sites are identical and independent, a straight line is obtained of slope $-K$ with intercepts on the x-axis of n and on the y-axis of Kn. If there is interaction between the binding sites, or there are several classes of independent sites, the plot is not linear. [After George Scatchard (1892–1973), US physical chemist.]

scatter to disperse in random direction(s) by impact or other interaction, especially light, electrons, neutrons, or X-rays. The measurement of scattered rays or particles may lead to useful analysis, as in **light scattering**.

scatter diagram a graph upon which two measured characteristics of each individual of a population are represented by one dot.

scatter factor *an alternative name for* **hepatocyte growth factor**.

scavenger *(in chemistry)* a substance that reacts with or binds a trace component, such as a trace metal ion, or that traps a reactive **reaction intermediate**.

Scc *abbr. for* separase cysteine cleaved; any of a small family of proteins that are cleaved by **separases**. Scc1 and Scc3 are components of the **cohesin** complex.

SCF *abbr. for* stem cell factor.

Schardinger dextrin *an alternative name for* **cyclodextrin**. [After Franz Schardinger (1853–1920), who first described such compounds in 1908.]

Schardinger enzyme *an alternative name for* **xanthine oxidase**.

Schardinger reaction the decolorization of methylene blue by milk in the presence of formaldehyde; the reaction is catalysed by **xanthine oxidase** (or Schardinger enzyme) in the milk.

Scheie syndrome *an alternative name for* **mucopolysaccharidosis I S**. [After Harold G. Scheie (1909– 1990).]

schema *pl.* **schemata** *(in informatics)* **1** a specification or description of the types of data represented in a database, the attributes they possess, and the relationships between them. **2** a diagram representing this specification.

Schiff base *or* **Schiff's base** any **imine** having the more limited general structure $R_2C{=}NR'$ where R may be any organyl group or H and R′ is any organyl group. It may be formed by condensation of the carbonyl group of an aldehyde or ketone with the amino group of a primary amine according to the equation:

$$R_2C{=}O + H_2NR' = R_2C{=}NR' + H_2O$$

Often considered to be synonymous with **azomethine**. [After Hugo Schiff (1834–1915), German chemist.]

Schiff reagent a solution of leucofuchsin – fuchsin bleached with sulfurous acid – that produces a red colour when reacted with an aldehyde. The reagent is used in the **Feulgen reaction** and the **periodic acid–Schiff reaction**.

Schiff test 1 (for aldehydes) a test based on the red colour produced when aldehydes react with **Schiff reagent**. **2** (for uric acid) a test based on the reduction of silver ions (silver nitrate solution) to metallic silver by uric acid in sodium carbonate solution. **3** (for urea) a test based on the formation of a purple colour when urea is treated with a concentrated solution of furfural in concentrated hydrochloric acid solution. Allantoin, but not uric acid, also gives a positive test.

Schild equation the expected relationship between the **concentration ratio**, r, and the concentration of a reversible competitive antagonist, B. It is given by $r = [\mathrm{B}]/K_\mathrm{B} + 1$, where K_B is the dissociation equilibrium constant for the combination of B with the receptor. *Compare* **Gaddum equation**. [After Heinz Otto Schild (1906–84), Austrian-born British pharmacologist.]

Schild plot a plot of log (**concentration ratio** – 1) versus log concentration of antagonist. For a reversible competitive antagonist the plot has a gradient of 1. The intercept on the abscissa then defines the concentration of antagonist required to reduce the response of the target tissue (or organism) by half (the dissociation equilibrium constant: $-\log K_\mathrm{B} = \mathrm{p}A_2$ when the slope is exactly unity and there are no complicating factors; *see* **pA_2**).

Schilling test a test for cobalamin (vitamin B_{12}) malabsorption that depends on the oral administration of ^{57}Co- or ^{58}Co-labelled **cyanocobalamin** and measurement of the urinary excretion of the radioactive label during the ensuing 24 hours. [After Robert Frederick Schilling (1919–), US hematologist and nutritionist.]

Schindler disease *see* **α-*N*-acetylgalactosaminidase deficiency**.

schizencephaly a rare disorder of human brain development that produces seizures, mental retardation, and blindness or speech defects. One or both cerebral hemispheres contain a full-thickness cleft and missing portions. It results from mutation in the homeodomain protein **EMX2**. –**schizencephalic** *adj.*

schizogeny (*in botany*) the separation of cells that occurs when new structures (e.g. aerenchyma or oil glands) are differentiating.

schizolysigeny (*in botany*) a combination of **schizogeny** and **lysigeny**.

schizophrenia any mental disorder characterized by a special type of personality disintegration, random thought processes, and impaired relation to reality. Antipsychotic (neuroleptic) drugs such as **chlorpromazine**, widely used in the symptomatic treatment of all forms of schizophrenia, are considered to act by blocking postsynaptic dopamine D_2 receptors, though most are not totally selective in this action. —**schizophrenic** *adj.*, *n.*

Schizosaccharomyces pombe the fission yeast that is used to brew the African beer called *pombe*. The rod-shaped cells grow by elongation, and the spores germinate and divide as haploids. The membranous organelles, e.g. the Golgi apparatus, are closely similar to those of higher eukaryotes, in marked contrast to those of budding yeast. It is suitable for analysing the relationship between cell size and the cell cycle because: (1) the cells divide symmetrically, unlike budding yeast; and (2) the yeast grows in length but not in diameter.

Schlesinger test a qualitative test for **urobilin** in urine. The urobilinogen in the urine is first oxidized by iodine to urobilin, then a zinc–urobilin complex is formed by addition of zinc acetate in ethanol; the complex has a yellow-green fluorescence and an absorption band at 507 nm.

Schlieren method an optical method of exhibiting inhomogeneities in refractive index in transparent media, dependent on the deflection of a ray of light from its undisturbed path when it passes through a medium in which there is a solute inducing a gradient of refractive index normal to the ray. The curvature of the ray is proportional to the refractive-index gradient in the direction normal to the ray. It is used in biochemistry particularly in measurements of diffusion, sedimentation, and electrophoretic mobility of proteins and other substances. [From German *Schliere*, streak.]

Schmidt–Thannhauser procedure a method for the extraction and determination of DNA, RNA, and phosphoproteins. Material insoluble in dilute, cold trichloroacetic acid is dried, digested with alkali, and subsequently precipitated with a strong acid. The total phosphorus in the precipitate represents DNA, the soluble inorganic phosphorus represents the phosphoproteins, and the soluble organic phosphorus represents the RNA. [After Gerhard Schmidt (1901–81) and Siegfried Joseph Thannhauser (1885–1962), German-born US biochemist.]

Schultz–Dale reaction an *in vitro* anaphylactic reaction in which the uterus or ileum of a sensitized animal (guinea pig) contracts specifically when a small amount of the sensitizing antigen is added to the bathing medium. The reaction is caused by histamine and similar substances that are released when the antigen combines with cellular antibody. [After H. H. **Dale**.]

Schütz–Borrisow rule *or* **Schütz law** an empirical rule according to which the velocity of an enzyme reaction is proportional to the square root of the enzyme concentration. It was first developed for pepsin but applies only to the crude enzyme under certain limited conditions; similar results have been obtained with some other proteinases. The effect is due to the presence of a reversibly dissociating pepsin inhibitor in crude pepsin preparations.

Schwann cell a uninucleate cell of the **neurilemma** surrounding a myelinated neuronal axon that is responsible for the formation and maintenance of the **myelin sheath** in peripheral myelinated neurons. [After Theodor Schwann (1810–82), German anatomist and physiologist.]

Schwannomin *see* **merlin**.

SCID *abbr. for* severe combined immunodeficiency; a heterogeneous group of primary immunodeficiency disorders that result from profound functional impairment of B and T lymphocytes. It presents with severe or repeated infections (especially by opportunistic microorganisms). About 50–60% of patients are boys, the disorder being X-linked and caused by numerous mutations in the gene for interleukin 2 receptor γ chain (IL-2Rγ) at Xp13.1 (*see* **interleukin 2**). Autosomal recessive forms are due to deficiency of adenosine deaminase, purine nucleoside phosphorylase, JAK3, IL-7Rα, RAG1, RAG2, ZAP-70, or Lck. *See* **adenosine deaminase deficiency**.

SCIF *abbr. for* secondary cytotoxic T-cell-inducing factor (i.e. **interleukin 2**).

scillabiose the disaccharide 4-*O*-*β*-D-glucopyranosyl-L-rhamnose, found in a **glycoside** of *Scilla maritima.*



scinderin *or* **adseverin** a Ca^{2+}-dependent cytosolic actin filament-severing protein present in chromaffin cells, platelets, and a variety of secretory cells.

scintillant 1 (of a phosphor) exhibiting scintillation. **2** *a jargon term for* **scintillator**.

scintillate 1 to give off sparks, to sparkle. **2** (of a phosphor) to emit quanta of light discontinuously, by fluorescence, when struck by a charged particle or a high-energy photon.

scintillation 1 the act of scintillating. **2** the flash of light produced in a phosphor when it is struck by a charged particle or a high-energy photon.

scintillation autoradiography *an alternative term for* **fluorography** (def. 2).

scintillation cocktail *or* **scintillation fluid** any mixture, containing a **scintillator**, to which **beta emitters** can be added for the purpose of **scintillation counting**; the radiation excites the scintillator to emit light. Many scintillation cocktails are based on hydrophobic solvents, since for the most part scintillators sparingly soluble in aqueous solutions have been used. The first scintillator to be widely used was 2,5-diphenyloxazole (PPO), often with 1,4-bis(5-phenyl-2-oxazolyl)benzene (PoPoP), which is excited by the light emitted by PPO to emit light of a higher wavelength more suitable for measurement. Many other scintillators, especially biodegradable compounds and others more compatible with water, have been developed. *See also* **biphenylylphenyloxadiazole**, **bismethylstyrylbenzene**.

scintillation counter an instrument for the detection and measurement of the intensity of high-energy radiation. Instruments for detecting gamma radiation contain a detector, normally a crystal of sodium iodide containing a small amount of thallium, and this is encased in a metal 'top hat' lined with a white reflector, the open end being sealed with Perspex. When the sodium iodide absorbs γ rays it emits a flash of light. For the counting of β^- emissions, the radioactive substance is dissolved or suspended in a **scintillation cocktail** contained in a glass or plastic vial, which is inserted into a chamber in the counter. Sometimes a solid scintillant is used for this also, e.g, for the effluent from chromatography columns. In the case of both types of instrument, the flashes of light produced are detected by a photomultiplier and converted into pulses of electric current which may be counted by an electronic counter.

scintillation fluid *an alternative term for* **scintillation cocktail**.

scintillation spectrometer *another name for* **scintillation counter**.

scintillator *or* **scintillant** any phosphor that fluoresces when struck by a charged particle or a high-energy photon. *See* **scintillation cocktail**.

scintillon a subcellular, crystal-like structure, found in bioluminescent organisms, that emits light on acidification in the presence of oxygen.

scissile capable of being split easily or cut smoothly, especially of an easily cleaved chemical bond.

scission a division or splitting; an act of dividing a nonisometric object orthogonally to its longest axis, especially a chemical bond or a fibrous molecule; **cleavage** (def. 2).

scleral pertaining to the sclera, the fibrous outer layer of the eyeball.

scleroderma *or* **systemic sclerosis** a chronic autoimmune disease in which skin, subcutaneous tissues, and various internal organs accumulate several types of collagen in the extracellular matrix. Autoantibodies to nuclear antigens are present in the serum.

scleroprotein any of a group of simple, generally fibrous, proteins that are insoluble in aqueous solutions; examples include **keratin** and silk **fibroin**.

sclerosis hardening of a tissue as a sequel to inflammation; especially an increase of connective tissue in the nervous system. *See also* **arteriosclerosis**. **—sclerotic** *adj.*

SCOP *abbr. for* structural classification of proteins; *see* **structure classification database**.

scopolamine *see* **hyoscine**.

scorbutic of, pertaining to, or affected with **scurvy**.

scoring matrix *or* **weight matrix** *(in sequence analysis)* a table of all possible pairwise relationships between nucleotide or amino acid symbols, used by database search and sequence alignment programs to quantify the similarity between sequences. The simplest scoring matrix is an identity or unitary matrix, in which only pairwise identities receive a positive score (nonidentical characters receive zero score). *Compare* **substitution matrix**.

scotophobin a 15-residue peptide that accumulates in the brains of rats trained to avoid the dark; administration is said to elicit a similar response in untrained animals. It is thought to be the first memory-directing substance isolated and identified.

scotopia adaptation to darkness; the adjustment of the eye to vision in dim light or the dark. It is considered to involve mainly retinal **rod cells**. *Compare* **photopia**. **—scotopic** *adj.*

scotopsin an **opsin** that is the apoprotein of a **rhodopsin**.

SCP *abbr. for* **1** single-cell protein. **2** sterol carrier protein.

SCP2 *abbr. for* sterol carrier protein 2.

SCPx *or* **SCP2/3-ketothiolase** a protein (547 amino acids) of the peroxisomal matrix that is processed therein into 3-ketothiolase (residues 1–404) and to **sterol carrier protein 2** (SCP2; the remaining residues). It is essential for beta oxidation of pristanic acid by catalysing the final step.

scrambalase a membrane protein that acts as a procoagulant by prompting Ca^{2+}-dependent migration of phosphatidylserine across the membrane bilayer of activated platelets. A defect in the protein may be associated with a bleeding disorder.

scrapie a **spongiform encephalopathy** of sheep and goats, and the first to be identified of a group once thought to be 'slow virus' infections occurring naturally and caused by an unconventional agent. Scrapie has similarities to two other animal diseases, transmissible mink encephalopathy and **bovine spongiform encephalopathy**, and three transmissible human dementias, **kuru**, **Creutzfeldt–Jakob disease**, and **Gerstmann–Sträussler syndrome**. All these diseases are now accepted as being caused by alterations in the **prion proteins** in the nervous system. The disease has been known since its first reported occurrence in merino sheep in Spain in 1732, which was rapidly followed by reports of other cases in Britain and Germany. The incubation period for the scrapie agent is usually 1–3 years. Different breeds of sheep exhibit markedly different susceptibilities to scrapie. As many as 20 different strains of scrapie agent, each with distinct properties in terms of incubation period in a given host and location of damage within the brain have been identified and transferred to mice. It would appear that the strains are passed to the progeny, so any explanation of the nature of the infective agent and process must take this into account.

screen **1** to protect from; esp. from harmful agents or radioactivity using sheets of lead, glass, or plastic; or from radiofrequency interference using a copper sheath or wire net. **2** to sift data, often using a limited or general assay, for selection of a particular phenomenon or result; samples selected by preliminary screening can be isolated for more detailed study. **3** *(in clinical chemistry)* to carry out any diagnostic procedure on a large cohort of patients with a view to detecting hitherto asymptomatic disease; *see also* **genetic screening**. **4** any device or material that acts to screen.

screw axis a crystal or an oligomeric protein molecule is said to possess an *n*-fold screw axis if it presents exactly the same appearance after rotation about that axis of 360°/*n*, coupled with a translation parallel to the axis. *Compare* **rotation axis**.

scRNA *abbr. for* small cytoplasmic RNA.

scRNP *abbr. for* small cytoplasmic ribonucleoprotein.

SCU *abbr. for* synonymous codon usage.

scurfin *an alternative name for* **FOXP3**

scurfy an X-linked disease of mice caused by mutations in **FOXP3** and resulting in a multiorgan autoimmune and inflammatory syndrome.

scurvy avitaminosis C; a deficiency disease caused by lack of **ascorbic acid** (vitamin C) in the diet. It is characterized by anemia, sponginess and ulceration of the gums, hemorrhages into the skin and subcutaneous tissues, and delayed wound healing.

scute a gene in *Drosophila* for **AS-C protein**.

scutelarin EC 3.4.21.60; *other name*: taipan activator (being from the venom of the taipan (snake), *Oxyuranus scutellatus*). An enzyme that catalyses (like factor Xa of blood coagulation) the cleavage of Arg-|-Thr and Arg-|-Ile in prothrombin to form **thrombin** and two inactive fragments. *Compare* **scutellarein**.

scutellarein 4′,5,6,7-tetrahydroxyflavone; the aglycon of **scutellarin**. *Compare* **scutelarin**.



scutellarin the glucuronide of **scutellarein**, from *Scutellaria* spp. *Compare* **scutelarin**.

scyrp *colloquialism for* scRNP (i.e. **small cytoplasmic ribonucleoprotein**).

SD *abbr. for* standard deviation.

SDS *abbr. for* sodium dodecyl sulfate.

SD sequence *abbr. for* Shine–Dalgarno sequence.

SDS–PAGE *abbr. for* SDS–polyacrylamide gel electrophoresis.

SDS–polyacrylamide gel electrophoresis *or* **SDS gel electrophoresis** *or* **detergent gel electrophoresis** *abbr.*: SDS–PAGE; a rapid method for resolving a protein into its subunits and determining their relative molecular masses, based on the ability of **sodium dodecyl sulfate** to cause dissociation of oligomeric proteins and to bind to the subunits to form complexes of constant charge-to-mass ratio. On **zone electrophoresis** in polyacrylamide gel, such complexes often have mobilities directly related to their M_r values, which may thus be obtained by comparison with standards.

Se *symbol for* selenium.

SE *abbr. for* standard error; *see* **standard error of estimate of the mean**.

SEA a family of genes for membrane receptor tyrosine kinases homologous with the **insulin receptor** family. The acutely transforming virus, avian erythroblastosis virus (*abbr.*: AEV) strain 13, contains the oncogene v-*sea*; this transforms fibroblasts and erythroblasts, but not avian myeloid cells. Sea, the product of c-*sea*, the cellular homologue of v-*sea*, phosphorylates Shc (*see* ***SHC***) on tyrosine residues.

sealase *a former name for* DNA ligase (ATP); *see* **DNA ligase**.

search engines Internet sites that have facilities for text searching. Depending on the way they work they are variously referred to as Web crawlers, spiders, robots, etc. For general purposes the search engine http://www.google.com or one of its mirrors such as http://www.google.co.uk is an excellent starting point.

sea-urchin-hatching proteinase *see* **envelysin**.

sebaceous gland any of the single or branched glands in the skin that secrete **sebum** into the hair follicles.

sebum the oily secretion of the sebaceous glands in the skin. It contains lipids such as waxes, squalene, and triacylglycerols; the triacylglycerols are broken down by anaerobic bacteria during secretion to form fatty acids. Sebum helps to form an effective barrier against water loss.

sec *symbol for* **secant** (def. 1).

sec. *abbr.* and *obsolete symbol for* **second** (def. 1).

sec- *abbr.*: *s*-; *prefix (in chemical nomenclature)* signifying **secondary** (def. 1a).

Sec *symbol for* a residue of the α-amino acid L-selenocysteine.

secant **1** *abbr. and symbol*: sec; the reciprocal of the **cosine** of an angle. **2** a straight line cutting a curve at two or more points.

SECIS *abbr. for* selenocysteine insertion sequence; a putative stem-loop nucleotide sequence required for decoding the SecUGA codon of eukaryotic mRNA for selenoproteins. It is located in the 3′ untranslated region of the mRNA that binds **SBP2** and **SelB**

seco- *prefix (in chemical nomenclature)* denoting cleavage of a ring with addition of one or more hydrogen atoms at each terminal group thus created. The numbering of the skeletal atoms of the parent molecule is retained.

seco-carotenoid a **carotenoid** in which a ring has been opened by breakage of a carbon–carbon bond; e.g. semi-*β*-carotenone (5,6-seco-*β*-*β*-carotene-5,6-dione).

second **1** *symbol*: s; the SI base unit of time, equal to the duration of 9 192 631 770 periods of the radiation corresponding to the transition between the two hyperfine levels of the ground state of the caesium-133 atom. **2** *symbol*: ″ a unit of plane angle equal to 1/60 of a minute; i.e. 4.84814 microradian (π/648000 rad). *See* **angle** (def. 1).

secondary *(in chemistry)* **1** **a** *prefix*: *sec*- (*abbr.*: *s*-); describing an alkyl compound (e.g. an alkanol) in which the functional group (e.g. a hydroxyl group) is attached to a carbon atom linked to two others. **b** describing the carbon atom bearing the functional group in such a compound. **2** describing an amide or amine in which two appropriate groups are attached to a nitrogen atom. **3** describing a salt formed by replacing two of the ionizable hydrogen atoms of a tribasic acid by one or two other cations of appropriate valency. *Compare* **primary**, **tertiary**.

secondary bond any of the weak attractive forces between atoms and/or molecules, especially when these stabilize a three-dimensional structure. It includes **hydrogen bonds**, **hydrophobic interactions**, and **van der Waals forces**.

secondary cell wall *(in plants)* the microfibrils and noncellulosic polysaccharides deposited on the primary cell wall. It provides additional conducting and supporting tissue and often makes up the greater part of the mature cell wall.

secondary charge effect an effect seen in the hydrodynamic study of charged macromolecules when the positive and negative ions of the supporting electrolyte have different sedimentation (or diffusion) coefficients, leading to the establishment of local electric fields due to charge separation. These local fields act as an additional force on the macromolecules, either accelerating or retarding their movement.

secondary cytotoxic T cell-inducing factor *abbr*.: SCIF; *an alternative name for* **interleukin 2**.

secondary database *an alternative name for* **pattern database**.

secondary deficiency a nutritional deficiency occurring when the dietary content of some essential nutrient is known to be adequate in normal conditions. It may be caused by malabsorption from the gut due to disease, diminished synthesis of a vitamin by the intestinal flora during treatment with an antibacterial agent, or increased requirement, e.g. in pregnancy.

secondary electron an electron emitted from a solid as a result of the impact of another electron. If the energy of the incident primary electron is sufficient, more than one secondary electron may be emitted, an effect exploited in an **electron multiplier**. *See also* **photomultiplier**.

secondary emission the emission of **secondary electrons**.

secondary F′-containing strain *see* **F′ plasmid**.

secondary fluor a second fluorescent agent that absorbs the fluorescent light emitted by a **primary fluor** and is thus excited to emit light at a higher wavelength, which may be more convenient for detection.

secondary hyperlipidemia *see* **hyperlipidemia**.

secondary immune response a response to an **immunogen** to which an animal has previously been exposed. It is characterized by the rapid production of large amounts of **antibody** over a few days, followed by an exponential decline. *Compare* **primary immune response**.

secondary lysosome *or* **phagolysosome** a **lysosome** that results from fusion of a **primary lysosome** with a **phagosome** or a vesicle containing endocytosed matter. *Compare* **telolysosome**.

secondary messenger *a variant form of* **second messenger**.

secondary metabolism the formation of end products of metabolism – **secondary metabolites** – that often have no readily apparent use in the producing organism.

secondary metabolite any of a group of very diverse natural products that have a restricted taxonomic distribution, usually possess no obvious function in cell growth, and are often synthesized by cells that have stopped dividing; they usually belong to closely related chemical families, usually of $M_r < 1500$, but some bacterial toxins are considerably larger. An example of a secondary metabolite is penicillin.

secondary response *see* **secondary immune response**.

secondary structure 1 (*of a protein*) the arrangement of the polypeptide primary structure into locally-organised, hydrogen-bonded structures, in particular α-helices and β-sheets; *see* **alpha helix**, **beta sheet**. **2** (*of a nucleic acid*) the arrangement of one or two polynucleotide chains in bihelical structures, stabilized by hydrogen bonds between complementary bases (*see* **complementary base sequence**); *compare* **clover-leaf structure**. *See also* **primary structure**, **quaternary structure**, **tertiary structure**.

second law of thermodynamics *see* **thermodynamics**.

second messenger *or* **secondary messenger** a mediator that is caused to accumulate in an effector (target) cell by the action of a **hormone**, **growth factor**, or other agonist, and that brings about the action of that agonist on the cell. The major second messenger systems include: synthesis of cyclic AMP by **adenylate cyclase** (the first of such systems to be discovered); synthesis of cyclic GMP by **guanylate cyclase**; opening of **ion channels**; the phosphoinositide system, (*see* **phosphatidylinositol cycle**) involving activation of phosphoinositide-specific phospholipase C (*see* **phospholipase**), or **1-phosphatidylinositol 3-kinase**; the release of ceramide from sphingolipids by sphingomyelinase; and protein phosphorylation by serine/threonine-specific or tyrosine-specific **protein kinases**. An important component in several of these involves coupling of activated receptor to the effector system through a **G-protein**.

second-order rate constant *see* **rate constant**.

second-order reaction *see* **order of reaction**.

seco-steroid a **steroid** in which a ring has been opened by breakage of a carbon–carbon bond.

secretagogue *or* **secretogogue** an agent that stimulates secretion (usually of a hormone, juice, or other glandular product). *See also* **+agogue**.

secretase an enzyme that cleaves the extracellular domain of type I or II transmembrane proteins, releasing that part of the protein into the circulation. Cleavage normally occurs near the extracellular face of the membrane. Substrates for secretases include Alzheimer's amyloid precursor protein (APP), angiotensin-converting enzyme, transforming growth factor-α, and the tumour necrosis factor ligand and receptor superfamilies. α-Secretase is a zinc-dependent protease; β-secretase (*also called* memapsin 2; BACE2) is a type I transmembrane protein with an aspartyl protease domain; γ-secretase requires senilins for activity and cleaves the transmembrane segment of APP. All three cleave APP but only β- and γ-secretases are required for release of β-amyloid peptide.

α-secretase *see* **ADAM-10**.

secrete to elaborate and emit a **secretion** from a cell or, particularly, from a gland.

secretin an intestinal hormone, discovered in 1902 by William Maddock Bayliss (1860–1924, British biologist) and Ernest Henry Starling (1866–1927, British physiologist) (the first hormone to be discovered). It has the sequence (human):

$$\mathrm{HSDGTFTSELSRLREGARLQRLLQGLV\text{-}NH_2}$$

(3.04 kDa), and is formed from a precursor synthesized in the S cells of the small intestinal mucosa. It stimulates the release of bicarbonate, enzymes, and potassium ions from the pancreas and stimulates the secretion of enzymes and electrolytes in the gut; it also inhibits HCl production by the stomach. Secretin lends its name to a superfamily that includes **gastric inhibitory peptide**, **GHRH**, **glucagon**, **peptide HI**, and **vasoactive intestinal polypeptide**.

secretin receptor any G-protein-associated membrane receptor that binds **secretin** and mediates its intracellular effects by activating adenylate cyclase. Secretin receptors are not structurally related to other G-protein-coupled receptors.

secretion 1 the process of elaborating, segregating, and emitting a substance or juice from a cell, organ, or organism; e.g. insulin by the B cells of the islets of Langerhans, or urine by the kidneys. There are three basic types of secretion: **apocrine**, **holocrine**, and **merocrine**. **2** a product of **secretion** (def. 1) from a cell, organ, or organism.

secretogogue *a variant spelling of* **secretagogue**.

secretogranin I *another name for* chromogranin B (*see* **chromogranin**).

secretor any person who secretes water-soluble glycoproteins with A, B, or H blood-group specificities into their mucous secretions, e.g. saliva and gastric juices. Over 80% of humans are secretors, having a **secretor gene** in their genomes.

secretor gene a gene determining **secretor** phenotype in humans. Secretor status is determined by a pair of allelic genes, *Se* and *se*. Secretors are either *Se*/*Se* or *Se*/*se* while nonsecretors are *se*/*se*. These alleles occur at a different locus from the ABO locus and do not affect the A, B, and H specificities of the red blood cells.

secretory describing a molecule or molecular fragment destined for secretion from a cell, such as secretory protein, polypeptide, etc.

secretory actin-binding protein *abbr*.: SABP; *also called* prolactin-inducible protein; gross cystic disease fluid protein 15; a glycoprotein that has been isolated in several different studies (as the alternative names indicate), but whose function remains unknown. As the prolactin-inducible protein, it was identified as a highly specific and sensitive marker of primary and metastatic breast cancer.

secretory component *another name for* **secretory piece**.

secretory granule a membrane-bound subcellular vesicle that is formed from the Golgi apparatus and contains a protein destined for secretion. The membrane of the granule fuses with the plasma membrane, and its protein load is exteriorized. Processing of the contained protein may take place in secretory granules. *Compare* **zymogen granule**.

secretory piece (*abbr.*: SP) *or* **secretory component** (*abbr.*: Sc) the 58 kDa polypeptide that joins the two identical monomers comprising the secretory form of **immunoglobulin A**. It has strong affinity for mucus, thus prolonging retention of IgA on mucous surfaces, and may protect the IgA against proteolytic destruction in the digestive tract. *Other names*: T chain; transport piece.

secretory protein I *abbr.*: SP-I; a glycoprotein of the parathyroid gland that is co-secreted *in vitro* with **parathyrin**. It consists of at least two homologous glycoproteins of similar size (M_r 72 000 and 70 000), related to chromogranin A (*see* **chromogranin**).

sector any portion of a circle bounded by two radii and the included arc. —**sectoral** *adj.*

sector cell *or* **sector-shaped cell** a cell used in an analytical ultracentrifuge to contain the sample. It is sector-shaped when viewed parallel to the rotation axis. Since the accelerating force is radial, sedimenting molecules move along radii and this cell shape minimizes the collision of sedimenting molecules with the cell walls.

securin a protein that binds to the N- and C-terminal regions of **separase** and inhibits its protease activity. Mutations in the securin gene are associated with defects in the separation of sister chromatids during anaphase of cell division.

sediment **1** to undergo **sedimentation**. **2** the accumulation of material resulting from sedimentation.

sedimentation the setting of solid particles (or solute) through a liquid (or solution) under the influence of a gravitational or centrifugal field.

sedimentation coefficient symbol: s; the rate of sedimentation of a particle in an ultracentrifuge or other system. For a particle or solute sedimenting in a system at constant applied field, temperature, and pressure, $s = v/a$, where a is the acceleration of free fall or centrifugation and v is the velocity of sedimentation. In centrifugation $s = v/\omega^2 r$, where ω is the angular velocity in rad s^{-1} and r is the distance of the particle or solute from the axis of rotation. It has the dimensions of time. The sedimentation coefficients of macromolecules and cellular particles are often expressed in **svedbergs**.

sedimentation equilibrium a technique in which compounds of interest are centrifuged for a period sufficiently long for the system to come to equilibrium. The technique has a number of applications. In one, used for molecules that have a density greater than the solvent, centrifugation is carried out at relatively slow speeds so that sedimentation of the molecule is slow enough to be counterbalanced by diffusion. At equilibrium, the concentration is lower at the meniscus and higher at the bottom of the cell, but is unchanging. The relative molecular mass, M_r, of the compound in question, often a protein, can be calculated from the expression:

$$m_r = 2RT\ln(c_2/c_1)/\omega^2(1 - v\rho)(r_2^2 - r_1^2),$$

where R is the gas constant, T is the thermodynamic temperature, v is the specific volume of the component, ρ is the density of the solution, ω is the angular velocity of the rotor, and c_1 and c_2 are the concentrations of the component at distances r_1 and r_2 from the centre of rotation. Ideally, determinations should be done at several concentrations and extrapolated to zero concentration.

sedoheptulose *a nonsystematic name for* D-*altro*-2-heptulose.



α-D-pyranose form

sedoheptulose-bisphosphatase EC 3.1.3.37; a chloroplast enzyme of the **reductive pentose phosphate cycle** that catalyses the reaction:

sedoheptulose 1,7-bisphosphate + H_2O =
sedoheptulose 7-phosphate + orthophosphate.

sedoheptulose 7-phosphate the 7-phosphate ester of **sedoheptulose**; it is a component of the **pentose phosphate pathway**.

SEE1 a cysteine protease (360 amino acids) of senescing leaves of maize. It is homologous to aleurain (of barley) and γ-oryzain (of rice).

Seebeck effect the phenomenon whereby an electromotive force is generated in a circuit containing junctions between dissimilar metals if these junctions are not all at the same temperature. *See* **thermocouple**. *Compare* **Peltier effect**. [After Thomas Johann Seebeck (1770–1831), Estonian-born German physicist.]

SEG *see* **sequence filter**.

Segawa syndrome *an alternative name for* **dopamine-responsive dystonia**.

segmentation **1** (of an ovum) *see* **cleavage** (def. 3). **2** (of an animal's body) *see* **metamerism**.

segmentation genes any of the 15 genes that are active during early development of *Drosophila* whose products are involved in dividing the embryo into a series of segments. There are three categories: segment polarity genes; pair-rule genes; and gap genes.

segment polarity gene any of the 16 or so genes in *Drosophila* that define the anterior and posterior compartments of segments. Examples are *engrailed*, *wingless,* and *hedgehog*.

segregation *(in genetics)* **1** the separation of homologous genetic elements (i.e. allele pairs) during meiosis in diploid cells. **2** the separation of sister chromatids during mitosis; by extension, the separation of any two independent genetic elements during cell division in prokaryotes. **3** (of plasmids) the partitioning of plasmids into daughter cells at cell division. Naturally occurring plasmids contain a partitioning function, *par*, which ensures correct partitioning into the two daughter cells.

segresome a membrane-bound, cytoplasmic aggregate of a dye, formed either by passage of the dye into a pre-existing **phagosome** or **lysosome**, or by the *de novo* formation of a membrane around the dye aggregate.

Seitz filter a filtration apparatus that removes microorganisms from a liquid. It formerly consisted of a flat pad of asbestos, or asbestos and cellulose, suitably mounted between the sample container and the receiving flask, filtration being assisted by reducing the pressure in the receiving flask. It has now been superseded by a sintered-glass filter. [After Seitz-Filter-Werke, T. and G. Seitz Gmbh & Co., Bad Kreuznach, Germany.]

selachyl alcohol 3-(octadec-9-enyloxy)-1,2-propanediol; a 1-octadec-9-enyl ether of glycerol, and a hydrolysis product of **ether lipids**.

SelB *or* **eEFsec** a specific eukaryotic elongation factor that conveys selenocysteine tRNA (Sec-tRNAsec) to the ribosome and binds the selenocysteine insertion sequence (**SECIS**) of the mRNA for a selenoprotein. Mouse SelB (583 amino acids) contains four GTP-binding sites in the N-terminal portion, which also binds the tRNA. It functions with **SBP2**. In eubacteria SelB and SBP2 form part of a bifunctional protein.

SELDI *abbr. for* surface-enhanced laser desorption and ionization; a commercial mass spectrometry technique for capturing peptides and proteins on an affinity surface (either chemical or biological) and subsequently quantifying and identifying the proteins. *See also* **tandem mass spectrometry**.

selectable marker a gene whose expression confers selective advantage on a cell or organism when exposed to an antibiotic. The marker is often an enzyme whose action modifies the antibiotic thereby making it inactive. Markers for use in eukaryotes are usually derived from bacteria and have no eukaryotic counterparts.

selected-ion monitoring *or* **mass fragmentography** *or* **molecular fragmentography** a type of **gas chromatography/mass spectrometry** in which the intensities of one or more molecular or fragment ions selected from the mass spectrum of a particular compound are monitored continuously as a means of quantifying that compound.

selectin any of a group of leukocyte surface molecules that act as leukocyte adhesion molecules; they are classed as CD62 in the **CD marker** system. All have **lectin** family carbohydrate-binding domains and EGF-repeats, with four motifs. They are expressed on the surface of platelets and endothelial cells as well as leukocytes. **E selectin** (CD62E), M_r 107–115 000 in various glycosylated forms, is expressed on endothelial cells, being induced by cytokines such as interleukin 1β and tumour necrosis factor α in 3–6 hours. It mediates endothelial cell binding to neutrophils, monocytes, and some memory T cells. **L selectin** (*or* lymph node homing receptor; CD62L), M_r 74 000 (on lymphocytes), is constitutively expressed on monocytes, lymphocytes (thymocytes, NK cells), neutrophils, eosinophils, and basophils. It mediates the adherence of lymphocytes, neutrophils, and monocytes to endothelium, including that of lymphocytes to endothelial cells of high endothelial venules in peripheral lymph nodes. It binds to **MadCAM** and CD34. **P-selectin** (*or* PADGEM; *abbr. for* platelet activation dependent granule external membrane protein), M_r 140 000, is expressed at the surface of activated platelets and endothelial cells, and is inducible within minutes by thrombin, histamine, or peroxides from α granules of platelets or Weibel–Palade bodies of neutrophils. It mediates the adhesion of neutrophils and monocytes to platelets and endothelial cells.

selection *(in microbiology)* a laboratory method in which a mixture of microorganisms is cultured under particular growth conditions that permit only cells with certain characteristics to survive, thereby enabling their isolation.

selection pressure the intensity with which natural selection operates; it is often measured by the change in **gene frequency** per generation due to the effects of natural selection.

selectively labelled indicating an isotopically labelled molecule in which the position(s) of the labelling is known, but the number of labelling nuclides at that (those) position(s) is not known; e.g. selectively labelled ethanol is designated as [1,2-^{2}H]CH_3–CH_2–OH, which indicates that some, or all, of the hydrogen atoms on carbon atoms 1 and 2 are ^{2}H atoms.

selective medium a culture medium designed either to encourage or to inhibit the growth of certain types of organisms, especially microorganisms.

selective theory of immunity *or* **elective theory of immunity** any theory that ascribes to antigens a selective function in immunity by which antigens select cells genetically prepared to respond specifically and cause them to multiply and differentiate. They include the **clonal-selection theory** and the **natural-selection theory of immunity**. *Compare* **instructive theory of immunity**.

selectivity *(in informatics) an alternative name for* **precision** (def. 2).

selector a gene whose product controls the formation and identity of a discrete set of cells in an embryo that forms a particular structure (e.g. eye, leg, or wing). One type includes the *Hox* genes, whose products differentiate between homologous morphological fields; another type consists of field-specific genes (e.g. *eyeless* or *Distalless* in *Drosophila*), which direct the formation of entire complex structures.

selector gene any of a class of genes encoding transcription factors that specify cell type and tissue, organ, and regional identity in animals such as *Drosophila,* in which they were first described.

selenium *symbol*: Se; a metalloid element of group 16 of the (IUPAC) **periodic table**; atomic number 34; relative atomic mass 78.96. Its main oxidation states are –2, +2, +4, and +6, with properties similar to those of sulfur, but more metallic. It occurs in various allotropic forms (grey, red, black); the grey form shows some electrical conductivity, which is enhanced by light, and it is used in 'selenium cells' to measure light intensity. The most abundant isotope is selenium-80 (mass 79.916; relative abundance 49.8%); others are selenium-74 (0.9%), selenium-76 (9.0%), selenium-77 (7.6%), selenium-78 (23.5%), and selenium-82 (9.4%). Radioactive isotopes are **selenium-72**, **selenium-73**, **selenium-75**, and **selenium-79**. Selenium is an essential trace element, required for the formation of **selenoproteins**, notably **glutathione peroxidase**. Gut absorption is poor, but selenium deficiency is rare (seen, e.g., in some parts of China with low soil selenium), and manifests as myopathy (especially cardiomyopathy). Measurement of red-cell glutathione peroxidase activity gives an index of selenium status.

selenium-72 a radioactive nuclide of selenium, $^{72}_{34}$Se, mass 71.927; it emits gamma radiation (0.046 Mev) and has a half-life of 8.4 days.

selenium-73 a radioactive nuclide of selenium, $^{73}_{34}$Se, mass 72.927; it emits a β^+ particle (1.32 Mev) and gamma radiation (0.361 Mev) and has a half-life of 7.1 h.

selenium-75 a radionuclide of selenium, $^{75}_{34}$Se, mass 74.923; it emits gamma radiation (0.481 Mev) and has a half-life of 118.5 days.

selenium-79 a radionuclide of selenium, $^{79}_{34}$Se, mass 78.918; it emits an electron (β^- particle, 0.16 Mev), no gamma radiation, and has a half-life of 6.5×10^4 years.

selenoamino acid an amino acid in which selenium replaces a sulfur atom; *see* **selenocysteine**, **selenomethionine**.

selenocysteine *symbol*: U or Sec; H–Se–CH_2–CH(NH_2)–COOH; an essential component of glutathione peroxidase and some other proteins (*see* **selenoprotein**). For its synthesis, a special tRNA, charged with serine, responds to a UGA codon. The serine is converted to selenocysteine just before its use on the ribosome. It is assumed that the neighbouring base sequence indicates a special sense for this codon, which is normally a 'stop' codon.

selenocysteine insertion complex *abbr.*: SIC; the complex of requirements for recoding an in-frame UGA codon as selenocysteine (Sec) in the mRNA for a selenoprotein. It comprises: a Sec codon UGA; a selenocysteine insertion sequence (**SECIS**) in the 3′ untranslated region of the mRNA; the selenocysteine tRNA (Sec-tRNAsec); the elongation factor **SelB**; and the SECIS-binding protein **SBP2**.

selenomethionine CH_3–Se–$[CH_2]_2$–CH(NH_2)–COOH; (*symbol*: Sem) a selenoamino acid used as an antimetabolite, competing with methionine; it is also found in proteins; *see* **selenoprotein**. For the solution of the phases in x-ray crystallography by single-wavelength anomalous dispersion (SAD), it is introduced into proteins by growth of bacteria on medium containing selenomethionine instead of methionine.

selenoprotein a protein containing selenium, almost invariably as **selenocysteine**, although **selenomethionine** can occur, apparently as a random substitute for methionine. Well-known selenoproteins include the mammalian **glutathione peroxidases** and tetraiodothyronine 5′-deiodinase, and bacterial formate dehydrogenases and glycine reductase.

selenoprotein P a plasma glycoprotein (42 kDa) of mammals that is rich in Lys and His residues and contains 10 selenocysteine residues per monomer. Its function is unknown.

selenoprotein W a protein (10 kDa) of skeletal and cardiac muscle that contains one selenocysteine residue per monomer. Its function is unknown.

SELEX *abbr. for* systematic evolution of ligands by exponential enrichment.

self 1 the individuality of a person or thing; the totality of components intrinsic to an individual or thing. **2** *(in immunology)* the components of an individual's own tissues that can be distinguished from foreign substances by the individual's immune system, and towards which **immunological tolerance** is shown.

self-absorption the absorption of any emission by the emitting molecules.

self antigen any (potentially) antigenic molecule originating in an individual that is recognized as nonforeign by the individual's immune system, and towards which **immunological tolerance** is normally shown. *See also* **autoimmunity**, **self-tolerance**.

self-assembly the formation of a complex entity from more simple, identical units without intervention from any external agency.

self-assembly doctrine a doctrine elaborated by Aaron Klug (1926–), Lithuanian-born British molecular biologist, and Caspar to explain the assembly of small viruses and subcellular organelles. It is postulated that the structure assembles as a result of specific binding sites on proteins that interact to form a scaffold on which other components form.

self-catabolite repression **repression** of gene expression by a **catabolite** formed within the same organism.

self-cloning the cloning of a gene within the species from which it was derived, a technique that in some countries attracts less stringent government restrictions than when a gene is cloned in another species, being considered the less hazardous of the two approaches with respect to the genetic environment.

self determinant a **determinant** originating from the tissue of an organism and thus treated as **self** (def. 2) by the immune system of that organism (except in the case of autoimmune pathology; *see* **autoimmunity**).

self-fertilization the union of male and female gametes of the same organism.

self-hybridization hybridization between nucleic acids that exhibit complementarity.

selfing *(in microbiology)* the production of wild-type 'transductants' by infection of an auxotrophic strain with a transducing phage grown on the same auxotroph as the donor.

selfish DNA hypothesis a hypothesis that accounts for the presence in eukaryotic genomes of large amounts of repetitive DNA(*see* **repetitive sequences**). Because there is no evidence that such DNA serves any useful purpose for its host, it has been termed **selfish DNA** or **junk DNA**, and is suggested to be a molecular parasite that has disseminated itself throughout the genome. It is a mystery why natural selection has not eliminated 'selfish DNA'.

self tolerance the state in which the immune system of an individual lacks reactivity against potentially antigenic molecules originating within that individual. Self tolerance develops during perinatal life. *See also* **acquired tolerance**, **autoimmunity**, **immunological tolerance**.

Seliwanoff test a test for ketohexoses based on the production of a red colour when the sample is boiled with a solution of 0.05% w/v resorcinol in 3 m hydrochloric acid. The test relies on the fact that ketoses are dehydrated more rapidly than aldoses to yield furfural products. [After Feodor Feodorowitsch Seliwanoff (1859–1938), Russian chemist.]

Sem *symbol for* a residue of L-selenomethionine.

SEM *or* **S.E.M.** **1** *abbr. for* standard error of estimate of mean. **2** *abbr. for* scanning electron microscope; *see* **electron microscope**.

sem-5 the gene for Sem-5, sex muscle abnormal protein 5, in *Caenorhabditis elegans*. Sem-5 acts in vulval induction and sex myoblast migration, contains SH2 and SH3 domains (*see* **SH domain**), and is phosphorylated by some tyrosine kinase receptors. Mutations of the *sem-5* gene block its function in the worm.

Sema *abbr. for* **semaphorin**.

semantide *or* **semantophoretic molecule** *or* **informational macromolecule** any of the macromolecules that carry the information of the genes or a transcript (or a translation) thereof. The genes themselves are **primary semantides**, messenger RNA molecules are **secondary semantides**, and most polypeptides are **tertiary semantides**.

semantophoretic molecule *an alternative name for* **semantide**.

semaphorin (*abbr*.: Sema) *or* **collapsin** any of a family of secreted or membrane-bound proteins (≈750 residues) that are expressed in various embryonal and adult tissues. In the developing nervous system they are released by cells that surround the paths of axon migration and can repel (e.g. Sema 3A and Sema 3F) or attract growing axons. They may also have non-neuronal functions. Their extracellular N-terminal regions (≈500 residues) are homologous to those of hepatocyte growth factor receptors and of **plexins**. Semaphorins are overexpressed during invasive or metastatic progression of tumours. Plexins are components of semaphorin receptor complexes.

semen the fecundating fluid of male higher animals, consisting of spermatozoa suspended in seminal plasma – secretions of the accessory glands.

semenogelin one of two major gel-forming proteins of semen. These proteins have 80% of their amino-acid residues in common, and their genes are localized to the long arm of chromosome 20. They are hydrolysed by a **kallikrein**-like protease.

semi+ *prefix* **1** half. **2** partial or partially; intermediate.

SEMI *abbr. for* specific endogenous mitotic inhibitor; *see* **chalone**.

semialdehyde any organic compound formed by the reduction of one carboxyl group of a dicarboxylic acid to an aldehyde group, as in glutamic semialdehyde.

semiconductor any material, e.g. germanium or silicon, whose electrical conductivity lies between that of conductors and insulators and increases with increasing temperature. Its crystal structure has atomic bonds that allow the conduction of electric current by either positive or negative carriers when the appropriate additives (dopants) are present.

semiconservative replication of DNA *see* **replication of DNA**.

semiconstitutive mutant a mutant in which negative regulation is partially lost, so that a gene is expressed in the absence of inducer, but at a lower level than in the fully constitutive mutation, yet in the presence of inducer the expression reaches the fully constitutive level. *See also* **constitutive mutation**.

semi-micro **1** describing or concerning something moderately small; applied to a scale of operation, an item of equipment, a quantity of material, etc. **2** *(in analytical chemistry)* denoting the analysis of amounts of substance in the range 10–100 mg. *Compare* **micro** (def. 1). *See also* **microanalysis**.

seminal **1** **a** pertaining to seed. **b** of, or relating to, semen. **2** germinating new concepts; fundamentally original.

seminal plasma the suspending fluid in which semen is ejaculated.

seminalplasmin *another name for* **caltrin**.

seminolipid 1-*O*-alkyl-2-*O*-acyl-3(β-3′-sulfogalactosyl) glycerol; the major sulfogalactoglycerolipid of mammalian testes and sperm.

semiochemical any chemical substance that delivers a message or signal between two organisms. There are two classes: (1) **pheromones**, in which information transfer is intraspecific; and (2) allelochemics, in which information transfer is interspecific. *See also* **allomone**, **kairomone**.

semiotics *functioning as sing.* **1** the practice of symptomatology; a term that became obsolescent, but has been reintroduced in connection with CT, NMR, and other imaging techniques. **2** the philosophical theory of signs and symbols, having three branches: syntactics, semantics, and pragmatics.

semipermeable membrane a membrane that allows the passage of only certain solutes, usually small molecules, but is freely permeable to solvent.

semipolar double bond *an alternative name for* **dipolar bond**.

semiquinone any free radical derived from a quinone or quinoid compound by removal of a single hydrogen atom. *Compare* **quinone**.

semisolid medium *(in cell culture)* a medium of consistency between those of a solution and a full gel.

semisynthesis the partial synthesis of a chemical compound by chemical or/and enzymic modification of one isolated from natural sources or produced biotechnologically (e.g. by fermentation). The procedure has been used successfully in the manufacture of artificial penicillins and cephalosporins. **—semisynthetic** *adj.*

semisystematic name *or* **semitrivial name** *(in organic chemistry)* a name of a molecule in which only a part is used in a systematic sense; e.g. (meth)ane, (but)ene, (calci)diol (in each of which only the part of the name outside the parentheses is systematic). Most names in organic chemistry are of this type. *Compare* **systematic name**, **trivial name**.

senescence the process of ageing. **—senescent** *adj.*

senescence-associated gene *abbr*.: SAG; any gene expressed during leaf senescence, fruit ripening, death of floral parts or unpollinated fruit tissues, and in seeds of germinating plants. Their products include cysteine proteases, aspartic proteases, other enzymes, polyubiquitin, metallothioneins, and pathogenesis-related proteins. They may be expressed early or late in senescence, in an organ-specific manner, or show enhanced expression due to stress (e.g. drought). Some respond to ethylene, others respond to abscisic acid.

senile aged, to a point of severely decreased capability. **—senility** *n.*

senna a preparation of the dried leaves of *Cassia angustifolia* or *C. senna* used as a laxative. It contains glycosides of hydroxyanthracene (sennoside B), which are metabolized to purgative anthraquinones by colonic bacteria.

sense DNA *see* **coding strand**.

sense strand (of duplex DNA) *see* **coding strand**.

sensitivity **1** an index of the ability of any analytical method or other detection procedure to make quantitative determinations at very low levels. **2** *(in metabolic control theory)* the susceptibility of flux through a pathway to change in response to change in the level of one of the component enzymes, expressed quantitatively in terms of the **flux control coefficient**. An alternative meaning arises when an allosteric ligand acts at several points in a pathway, where a plot of the fractional modification in flux versus ligand concentration yields a sigmoidal curve for a positive effector; the sensitivity in this case can be derived from the slope of the sigmoidal curve. **3** *(in informatics) an alternative name for* **recall**.

sensitivity coefficient *former name for* **flux control coefficient**.

sensitization *or* **sensitisation** **1** enhanced reactivity to any treatment (such as exposure to an agonist) of any tissue, cell, or molecular system resulting from prior experience or treatment (often by the same agonist). **2** the conditioning of an animal by antigen in such a way that **hypersensitivity** reactions occur on subsequent exposure to the antigen. **3** the attachment of antibody to sheep red blood cells to make them susceptible to lysis by complement in the **complement-fixation test**. Red blood cells treated in such a way are commonly referred to as **sensitized cells**. **—sensitize** *or* **sensitise** *vb.*

sensitizer *or* **sensitiser** *see* **allergen**.

sensor any device that records the level of a substance of interest or under investigation, using physical parameters (heat, conductivity) or chemical methods. Sensors are often applied to continuous monitoring in flow systems; **biosensors** utilize the reactions of enzymes immobilized on a probe and often coupled with a second substrate that yields a coloured or fluorescent product.

sensor kinase *abbr*.: SK; a histidine kinase that forms one element of the **two-component regulatory systems** that perform signal transduction in microorganisms and plants. Sensor kinases are often membrane proteins that respond to environmental changes.

sensory rhodopsin either of two phototaxis proteins (SRI or SRII) of plasma membranes of halobacteria, similar in structure to the light-driven proton pump bacteriorhodopsin, that influence bacterial migration via signals to the flagellar motor. Their action is mediated by integral membrane proteins (HtrI and HtrII respectively) that extend far into the cytoplasm.

sensory transducer any component of bacterial systems involved in signal transduction. An example is the *ntrB*/*ntrC* system, which occurs in several bacteria. In *Escherichia coli* under nitrogen limitation the product of the *ntrB* gene, NtrB (EC 2.7.1.–), activates NtrC – the *ntrC* gene product – by phosphorylating it; in nitrogen excess it reverses this. NtrC contains an ATP-binding domain that interacts with **sigma factor** σ^{54}. Another example is sensory rhodopsin I transducer from archaebacteria. This is a typical seven-transmembrane-domain **opsin**-type protein used for sensing light. *See also* ***che***.

sentrin *an alternative name for* **SUMO**.

sepacin *see* **separase**.

separase a cysteine peptidase, EC 3.4.22.49, that cleaves Sec1 of the **cohesin** complex to cause sister chromatid separation at the anaphase stage of the cell cycle. Most separases are large molecules (180–250 kDa) that have a catalytic domain homologous to that of the **caspases**, and a highly conserved C-terminal region. Separases are inhibited by binding to **securin**.

separation *(in genetics)* the break-up of a cointegrate into two or more **replicons** of similar sizes. *Compare* **excision**.

Sephacel *proprietary name for* a gel-filtration medium based on **cellulose** cross-linked using **epichlorohydrin** so that a mesh results, the size of the apertures in the mesh being determined by the extent of cross-linking.

Sephacryl *proprietary name for* a gel-filtration medium prepared from allyldextran covalently cross-linked using *N*,*N*-methylene bisacrylamide, to yield a mesh; the size of the apertures in the mesh depend on the degree of cross-linking.

Sephadex *proprietary name for* a gel-filtration medium based on **dextran** cross-linked using **epichlorohydrin** so that a mesh results, the size of the apertures in the mesh being determined by the extent of cross-linking.

Sepharose *proprietary name for a* gel-filtration medium based on **agarose** cross-linked using **epichlorohydrin** to form a mesh, the size of the interspaces being determined by the extent of cross-linking.

septanose the form of any **monosaccharide**, or monosaccharide derivative, that contains a ring consisting of six carbon atoms and one oxygen atom. In monosaccharide symbolism the septanose form may be indicated by the suffix *s*; e.g. Glc*s* symbolizes glucoseptanose. *Compare* **furanose**, **heptose**, **pyranose**.

septate divided by, or involving, a **septum** or septa.

septation the process of forming the **septum** that cuts a cell into two at the end of the **cell cycle** in bacteria.

septic shock the clinical state of hypotension and multiorgan dysfunction that results from systemic infection by Gram-negative bacteria. Bacterial lipopolysaccharide endotoxins stimulate the host's immune system, causing the secretion of **tumour necrosis factor-**α (cachectin) and other factors.

septum **1** *(in anatomy)* a wall of tissue, sheet of cells, or other membrane-like structure that partitions two compartments. **2** a disk of silicone rubber, PTFE, or similar material used in any apparatus to seal an injection port. A syringe needle can pierce the septum for the purpose of injection, and on withdrawal the elasticity of the septum ensures that the hole reseals.

Sequenase *proprietary name for* a chemically modified T7 DNA polymerase with high **processivity**. It is the usual choice for DNA sequencing by the **chain-termination method**. *See also* **ThermoSequenase**.

sequenator an apparatus for determining the sequence of monomeric residues (e.g. amino acids) in an ordered linear polymer (e.g. an oligopeptide) by repeating a chemical process.

sequence **1** the ordinal arrangement of the constituent parts of a biopolymer, e.g. the order of amino-acid residues in a polypeptide chain, or of the nucleotide residues in a polynucleotide chain; the known arrangement of such units in any biopolymer or fragment. **2** any particular segment, occurring in, or derived from, a biopolymer, having a known order of its constituent parts; a synthetic polymer composed of parts equivalent to those occurring naturally, and present in a particular known order. **3** to determine the order of residues in a biopolymer or fragment. **—sequential** *adj.*

sequence analysis package a suite of programs for the computational analysis of protein and/or nucleic acid sequences, including, for example, tools for fragment assembly, mapping, translation, automatic and manual sequence alignment, phylogenetic analysis, database searching, pattern recognition, property visualization, composition analysis, and RNA secondary structure plotting. One of the first academic packages was GCG, which then became a commercial product; a freely available alternative is EMBOSS, the European Molecular Biology Open Software Suite.

sequence assembly *or* **assembly** the process by which the overlapping DNA sequence readings from a single sequencing experiment (usually fragments ~500–800bp in length) are correctly ordered along the genome. *See also* **sequence assembly software**.

sequence assembly software software for computational **sequence assembly**, including programs for base calling from sequencing gels (e.g. PHRED) and for ordering the resulting overlapping DNA sequence fragments (e.g. PHRAP).

sequence compression *see* **band compression**.

sequence database *or (sometimes)* **primary database** a database that houses biomolecular sequences (nucleotide or protein) and associated annotation (relating to organism, species, function, mutations linked to particular diseases, functional or structural features, bibliographic references, etc.): e.g. EMBL, GenBank, and DDBJ are the primary nucleotide sequence databases; PIR-PSD, Swiss-Prot, TrEMBL, JIPID, and PRF are primary protein sequence databases.

sequence filter *(in bioinformatics)* a program that masks regions of local compositional bias in biological sequences, usually as a preprocessing step for database-search programs to reduce the number of spurious matches and thereby increase the likelihood that the highest scoring matches are the result of common descent. Examples include SEG, DUST, and XNU.

sequence hypothesis the hypothesis, formulated by F. H. C. **Crick** in 1958, that 'the specificity of a piece of nucleic acid is expressed solely by the sequence of its bases, and that this sequence is a (simple) code for the amino-acid sequence of a particular protein.'

sequence ladder the ladder-like bands of separated components occurring in the electrophoresis gel that result from DNA sequencing experiments.

sequencer an apparatus for automatically determining the sequence of monomeric residues in an ordered linear polymer.

sequence rule *or* **Cahn–Ingold–Prelog rule** *or* ***R S* convention** (of configuration specification) a system for specifying the absolute molecular chirality of a chemical compound. This system considers the sequence of the proton numbers of the atoms directly attached to a chiral centre(*see* **chirality**); if two or more of these atoms have the same proton number, their substituents are then taken into account, the group with substituents of highest proton number taking precedence. When a multiple bond to a substituent is present, the substituent is arbitrarily considered to occur twice, or thrice; an isotope of higher nucleon number takes precedence over one of lower number. For a tetrahedral centre (e.g. a carbon atom) the substituent with the lowest priority is placed away from the observer (behind the chiral atom) with the other three projecting towards the observer; if these three substituents lie in a clockwise (right-handed) array of decreasing priority, then the chiral centre is designated with the stereochemical descriptor *R*, denoting Latin *rectus*, right; if the substituents lie in an anticlockwise (left-handed) array of decreasing priority, then the chiral centre is designated with the stereochemical descriptor *S*, denoting Latin *sinister*, left. For the name of a compound consisting of molecules with a single chiral centre the descriptor *R* or *S*, with a preceding locant if needed, is formed into a prefix by placing it in parentheses and adding a linking hyphen; a racemate with a single chiral centre in its molecules is labelled with the prefix (*RS*)-. When a molecule contains more than one chiral centre the prefix to the name is composed of multiple descriptors, each preceded by an appropriate locant; e.g. (2*R*,3*R*)-2,3-dihydroxybutanedioic acid (= $\mathrm{L_g}$-tartaric acid). If only the relative, but not the absolute, configurations of two or more chiral centres in a molecule are known, these centres may be designated with the descriptors *R** and *S** (spoken as *R* star, *S* star), preceded when necessary by appropriate locants, on the arbitrary assumption that the chiral centre first cited (which usually is the one with the lowest locant) has an *R* configuration; for examples, compare the systematic names of **allothreonine** and **threonine**. *See also* **D/**L convention. Extensions of the sequence rule are the ***E*/*Z* convention**, the **pro-*E*/pro-*Z* convention**, the **pro-*R*/pro-*S* convention** and the ***Re*/*Si* convention**. [After Robert Sidney Cahn (1899–1981), British natural-products chemist, editor, and scientific semanticist, (Sir) Christopher Kelk Ingold (1893–1970), British physical organic chemist, and Vladimir **Prelog** (1906–98), Bosnian-born Swiss organic chemist, who jointly developed the system and described it in a series of three papers published in 1951, 1956, and 1966.]

sequence-tagged site *abbr*.: STS; a unique short, single-copy DNA sequence that characterizes a mapping landmark on the genome. Such sequences provide unambiguous identification of DNA markers generated by the Human Genome Project (*see* **HUGO**). STSs bind to **YACs**. If two YACs contain the same STS they must overlap. The YACs can be built up into an overlapping series of clones (a **contig**) covering an entire gene.

sequencing the act, or process, of determining the **sequence** (def. 1) of proteins or nucleic acids. *See* **chain-termination method**, **chemical cleavage method**, **solid-phase technique**.

sequencing by hybridization *see* **SBH**.

sequencing centre a research institute that provides a major focus for genome mapping and sequencing, often also providing genome analysis software for free use by the community. Notable examples include the Sanger Institute in the UK, and The Institute for Genome Research (TIGR) and the Whitehead Institute for Biomedical Research (WIBR) in the USA.

sequencing gel a polyacrylamide gel run to resolve oligonucleotides produced in a DNA sequencing procedure. *See* **chain-termination method**, **chemical cleavage method**.

sequential analysis the analysis of a protein or nucleic-acid **sequence** (def. 1).

sequential mechanism an enzyme reaction involving two or more substrates in such a way that all the substrates must be bound to the enzyme to form the central complex before any products can be released. A sequential mechanism may be an **ordered mechanism** or a **random mechanism**.

sequestering agent *see* **chelating agent**.

sequestration **1** the process of removal or separation. **2** *(in chemistry)* the effective removal of ions from solution by **coordination** with another kind of ion or molecule to form a firm complex molecule with different properties from the original ion. *Compare* **chelation**. **3** *(in cell biology)* the intracellular enclosing of material in an organelle. **—sequester** *vb.*

Ser *symbol for* a residue of the α-amino acid L-serine (alternative to S).

SER *abbr. for* smooth endoplasmic reticulum (*see* **endoplasmic reticulum**).

sera a plural of **serum**.

SERCA *abbr. for* sarcoplasmic/endoplasmic reticulum **calcium-transporting ATPase**, EC 3.6.1.38; a family of Ca^{2+} pump integral membrane protein isoforms of sarcoplasmic or endoplasmic reticulum. They catalyse the hydrolysis of ATP coupled with Ca^{2+} transport from the cytosol.

serglycin a proteoglycan of secretory vesicles of leukocytes. In rat, the core protein (104 amino acids) contains a central domain of 49 alternating Ser and Gly residues. Some 15 chondroitin sulfate/dermatan sulfate chains are linked to the Ser residues in this domain.

serial analysis of gene expression *abbr*.: SAGE; a method for detecting and quantifying gene expression. Short sequence tags (10–14bp), each serving as a unique marker for its transcript, are extracted from defined locations at the 3′ end of cDNAs, concatenated, inserted into vectors, and cloned in bacteria. The concatemers are sequenced and the tags counted. The relative numbers of each tag provide an estimate of the expression level of the corresponding transcript. Also, tags are matched with their corresponding genes where the gene sequences are known. SAGE projects usually generate an order of magnitude more tags than expressed sequence tag (EST) sequencing projects, allowing statistically more accurate and more sensitive expression estimates to be made.

serial dilution a method of achieving dilution of a liquid by sequentially transferring a sample of predetermined volume into another, empty, vessel (usually a tube), which is then made up with diluent to the same total volume as the first. The overall dilution achieved is $(v/s)^x$ -fold, where *v* is the chosen total volume in each tube, *s* is the size of the sample, and *x* is the number of times the procedure is repeated.

serinate **1** serine anion; the anion, $HO–CH_2–CH(NH_2)–COO^–$, derived from **serine**. **2** any salt containing serine anion. **3** any ester of serine.

serine *the trivial name for* α-amino-β-hydroxypropionic acid; 2-amino-3-hydroxypropanoic acid; $HO–CH_2–CH(NH_2)–COOH$; a chiral α-amino acid. L-Serine (*symbol*: S *or* Ser), (*S*)- 2-amino-3-hydroxypropanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: AGC or AGU; UCA, UCC, UCG, or UCU. In mammals, it is a non-essential dietary amino acid, and is glucogenic. D-Serine (*symbol*: D-Ser *or* DSer), (*R*)-2-amino-3-hydroxypropanoic acid, in both free and combined forms occurs in silkworms and earthworms; residues of D-serine occur in certain peptide antibiotics, e.g. polymyxins D_1 and D_2. [*Note*: the absolute configuration of D-serine (and hence that at the α-carbon atom of other α-amino acids of the D series) is identical to that of D-glyceraldehyde (and hence to that at the reference carbon atom of other monosaccharides of the D series).]



L-serine

L-serine dehydratase EC 4.2.1.13; *systematic name*: L-serine hydro-lyase (deaminating); *other names*: serine deaminase; L-hydroxyaminoacid dehydratase. An enzyme that catalyses a reaction between L-serine and water to form pyruvate and ammonium ion. It is a pyridoxal-phosphate enzyme. The enzyme for gluconeogenesis from serine in *Escherichia coli* is a 4Fe–4S protein.

serine hydroxymethyl transferase *see* **glycine hydroxymethyltransferase**.

serine-like carboxypeptidase *see* **serine endopeptidase**.

serine *C*-palmitoyltransferase EC 2.3.1.50; an enzyme involved in the biosynthesis of **sphingoid** bases. It catalyses the formation of 3-dehydro-D-sphinganine from palmitoyl-CoA and L-serine, releasing CoA and CO_2. Pyridoxal-phosphate is a coenzyme.

serine peptidase any enzyme that has a residue of serine (and one each of aspartate and histidine) at the active centre and is irreversibly inhibited by organic fluorophosphates (which phosphorylate the serine's hydroxyl group). Serine peptidases are of two types: (1) **serine-type carboxypeptidases**, and (2) **serine endopeptidases**, subsubclass EC 3.4.21. During catalysis by serine peptidases an acylenzyme intermediate is formed by esterification of the hydroxyl group of the reactive serine with the carbonyl group of a sensitive peptide bond of the substrate. The serine endopeptidase group includes **chymotrypsin**, most **elastases**, **kallikrein**, **thrombin**, **trypsin**, and a number of microbial proteinases. *See also* **serine-type carboxypeptidase**.

serine/threonine kinase a **protein kinase** that phosphorylates serines or threonines on its target protein.

serine/threonine-specific protein phosphatase EC 3.1.3.16; *recommended name*: phosphoprotein phosphatase; *other names*: protein phosphatase-1; protein phosphatase-2A; protein phosphatase-2B; protein phosphatase-2C. This name includes enzymes that hydrolyse the serine- or threonine-bound phosphate group from phosphoproteins.

serine transhydroxymethylase *see* **glycine hydroxymethyltransferase**.

serine-type carboxypeptidase EC 3.4.16.1; any enzyme of broad specificity that hydrolyses protein with release of a C-terminal amino acid.

serinium serine cation; the cation, $HO–CH_2–CH(NH_3^+)–COOH$, derived from **serine**.

serino+ *prefix* denoting the group, $HO–CH_2–CH(NH–)–COOH$, derived from **serine** by loss of hydrogen from the amino group.

sero+ *comb. form* denoting a connection within or origin in **serum**.

serological pertaining to, or originating in, serum; connected with the study of serum.

serology the study of **serum**; in particular, the immunological phenomena involving circulating antibody that may be observed *in vitro*.

serosa a **serous membrane**, especially the peritoneal covering. —**serosal** *adj.*

serotonergic 1 describing a nerve that is activated by **serotonin**. **2** describing a nerve that acts by the release of serotonin from the nerve endings. *Compare* **adrenergic**, **aminergic**, **cholinergic**, **peptidergic**, **purinergic**.

serotonin 5-hydroxytryptamine (*abbr.*: 5-HT); a monoamine neurotransmitter occurring in the peripheral and central nervous systems and having hormonal properties; it is also found in mast cells, platelets, brain, and the enterochromaffin cells of the gastrointestinal tract, and causes vasoconstriction, increased vascular permeability, and contraction of smooth muscle. Its reuptake via a 5-HT transporter is sensitive to antidepressants and to cocaine. Serotonin is involved in mood control, fear, and anxiety. It is formed from tryptophan, after hydroxylation to 5-hydroxytryptophan, by tryptophan 5-monooxygenase (EC 1.14.16.4; requires tetrahydrobiopterin), followed by decarboxylation by aromatic-L-amino-acid decarboxylase (EC 4.1.1.28). It is a substrate for **monoamine oxidase**.

serotonin receptor *see* **5-hydroxytryptamine receptor**.

serotransferrin *see* **transferrin**.

serous 1 relating to or resembling **serum** (or similar watery fluid). **2** producing a fluid resembling serum.

serous membrane *or* **serosa** a thin connective-tissue membrane lining certain closed body cavities and reflected over the viscera. The peritoneum of the abdomen, pleura of the chest, and pericardium of the heart are all serous membranes. Each consists of a **parietal layer**, lining the walls of the cavity, and a **visceral layer** covering the organs. The two are continuous, forming a closed sac. *Compare* **mucous membrane**.

serpentine domain any series of transmembrane segments of a single polypeptide chain of a membrane protein that traverses the lipid bilayer several times, as, e.g., in **7TM proteins**.

serpin any of a superfamily of proteins, many of which inhibit serine proteases, and are highly similar to classical serine protease inhibitors, such as **α_1-antitrypsin** or antithrombin. The superfamily is now considered to extend beyond compounds that are known to be protease inhibitors and, based on similarity, includes proteins such as **ovalbumin** and **angiotensinogen**, which have no inhibitory function. [From serine protease inhibitor.]

serpocidins members of the serine protease (with chymotryptic activity) superfamily that are present in neutrophil **azurophil granules**. They include: **cathepsin G**, which is active against proteins of Gram-positive and Gram-negative bacteria; and **azurocidin**, **elastase**, and proteinase 3. The latter three are encoded by a gene cluster at 19pter, and are active against proteins of Gram-negative bacteria.

Sertoli cell *or* **sustentacular cell** a supporting cell of the mammalian testis that surrounds and nourishes developing sperm cells. [After Enrico Sertoli (1842–1910), Italian histologist.]

serum (*pl.* **sera** *or (esp. US)* **serums**) the liquid extruded after blood has clotted and the clot has retracted (**syneresis** (def. 2)). *Compare* **plasma**.

serum albumin *or* **plasma albumin** the smallest and most abundant of the plasma proteins; M_r 65 000–68 000 for the bovine form, 69 000 for the human. It is involved in the regulation of osmotic pressure, and in the transport of sparingly soluble metabolites. The serum albumins belong to a multigene family of proteins that includes **α-fetoprotein** and **vitamin D binding protein.** Human serum albumin has three homologous domains, which assemble to form a heart-shaped molecule. It is an all-α protein, containing 28 helices, ranging from five to 31 amino-acid residues, formed into six subdomains; two each of these subdomains form one of the major domains. Bovine (serum) albumin (*abbr.*: BSA) and human (serum) albumin (*abbr.*: HSA) are widely used as standards in protein estimations; these include fatty acids, amino acids (such as tryptophan), steroids, metals (e.g., calcium, copper, zinc), and hydrophobic drugs. *See also* **albumin**.

serum amyloid A *abbr.*: SAA; any plasma protein whose synthesis in liver is induced by interleukins 1 and 6 and other cytokines. **SAA1** and **SAA2** (each of 104 amino acids) are acute-phase reactants. Their cleavage releases the N-terminal polypeptide (76 residues), which forms fibrils and accumulates in reactive amyloidosis. **SAA4** is not an acute-phase reactant, does not form fibrils, and is a normal constituent of high-density lipoproteins (HDL). Their function is unknown.

serum amyloid P-component *abbr.*: SAP; a precursor of amyloid component P. Amyloid component P is found in basement membranes, and is associated with **amyloid** deposits.

serum converting enzyme *a former name for* **angiotensin converting enzyme**.

serum globulin any **serum protein** that is also a **globulin**. An early classification of globulins was based on their mobility on electrophoresis. **Serum albumin** moves the fastest; behind albumin on paper electrophoresis or cellulose acetate strips are two bands known as the α_1- and α_2-globulin bands, followed by a β-globulin band, with the γ-globulins forming a diffuse band near the origin. The α_1-globulins include thyroxine- binding protein, transcortin, α_1-glycoprotein, α-lipoprotein, and antitrypsin; the α_2-globulins include haptoglobin, α_2-glycoprotein, macroglobulin, and ceruloplasmin; the β-globulins include transferrin, β-lipoprotein, and β-glycoprotein; the γ-globulins comprise the immunoglobulins.

serum protein any protein contained in serum; the term is usually applied to those proteins present in high quantities. The most prominent of these is **albumin**, which is present in the normal serum of human adults in the range 34–48 g L^{-1}. *See also* **serum globulin**.

serum response element *abbr.*: SRE; a stretch of DNA, usually of the sequence CCATATTAGG, that regulates promoters for genes that are activated by addition of serum to cell cultures.

serum spreading factor *see* **vitronectin**.

seryl the acyl group, $HO–CH_2–CH(NH_2)–CO–$, derived from **serine**.

sesqui+ *comb. form* **1** denoting one-and-a-half times; in a ratio of three parts to two. **2** *(in chemistry)* indicating a compound having one-and-a-half molecular proportions of the specified element group, or unit, either in relation to a second component, as in sesquioxide (e.g. chromium sesquioxide, Co_2O_3), or in relation to a reference compound, as in **sesquiterpene**; it also sometimes denotes a compound intermediate in constitution between two others, as in sesquicarbonate (e.g. sodium sesquicarbonate, Na_2CO_3•$NaHCO_3$•$2H_2O$).

sesquiterpene any **terpene** formed from three isoprene units, i.e. having 15 carbon atoms per molecule (a monoterpene has 10 carbon atoms and is formed from two isoprene units).

sesquiterpene lactone any sesquiterpene (15 carbon atoms) containing a lactone structure. Several are derived from *Artemisia* spp., including **artemesinin** (qinghaosu) from *A. annua* (qing hao), which has been used for almost 2000 years as an antimalarial.



artemesinin

sester+ *comb. form* **1** denoting two-and-a-half times; in a ratio of five parts to two or 10 parts to 4. **2** *(in chemistry)* indicating a compound having two-and-a-half molecular proportions of the specified group or unit in relation to a reference compound, as in **sesterterpene**.

sesterterpene any **terpene** formed from five isoprene units, i.e. having 25 carbon atoms per molecule (a monoterpene has 10 carbon atoms and is formed from two isoprene units). An **ophiobolin** is an example.

sev *symbol for sevenless* gene; *see* **Sevenless protein**.

Sevag method a method for removing proteins from nucleic acids. The proteins are precipitated after repeated denaturation by shaking with a solution of octanol in chloroform.

Sevenless protein *abbr*.: Sev; a **tyrosine kinase** receptor, encoded by the *sevenless* (*sev*) gene, that participates in differentiation of R7 photoreceptors in *Drosophila*. Sev has a ligand, **Boss**, the product of the *bride of sevenless* (*boss*) gene; it is expressed by R8 photoreceptor cells and internalized in a Sev-dependent manner.

seven-minute phosphate *see* **labile phosphate**.

seven-transmembrane-domain protein *or* **seven-transmembrane-segment protein** *or* **seven-transmembrane-helix protein** *or* **7TM protein** a protein that contains, in a single polypeptide chain, seven hydrophobic domains that traverse the lipid bilayer. This structural characteristic is typically used to describe the structures of receptors that couple to effector systems through **G proteins**; these are also sometimes referred to as **serpentine receptors**. The structures of bacteriorhodopsin (a 7TM protein but not a G protein-coupled receptor (GPCR)) and of bovine rhodopsin (which is a GPCR) have been determined to high resolution; similar structural characteristics have been attributed to several other proteins, largely on the basis of sequence comparison. Thus, for many proteins, the name '7TM protein' is a tentative one, and the implication that the transmembrane domains are helical is equally so.

seven-up a receptor required for photoreceptor cells during eye development. It is a **zinc-finger** DNA-binding protein with two forms (1 and 2) generated by alternative splicing.

severe combined immunodeficiency *see* **SCID**.

sex chromatin a condensed mass of **chromatin** that represents an inactivated X chromosome. In mammalian nuclei, each X chromosome apart from the activated one forms a sex chromatin body or **Barr body**.

sex chromosome a chromosome involved in sex determination. In many species, these are the **X chromosome** and **Y chromosome**. They are distinguished from the **autosomes** i.e. all the other chromosomes of that species. In some species, however, e.g. fish of the genus ***Xiphophorus***, sex determinants are spread over a number of chromosomes.

sex determination the specification of the sex of an individual organism by genes. In many animal species, these genes are located on the **X chromosome** and the **Y chromosome**. Their effects are manifested as a result of secretion of **androgens** and **estrogens**.

sex-determining region of Y chromosome *see* **SRY**.

sex factor *or* **fertility factor** *or* **F factor** *or* **F agent** an episomal genetic element (*see* **episome**) in bacteria that enables the cell to act as a genetic donor. Cells of such donor strains are able to form stable unions with cells devoid of such factors and to transfer to them extrachromosomal material, including the sex factor, and sometimes segments of bacterial chromosomes (*see* **conjugation** (def. 4)). The **F plasmid** is the prototypical sex factor, responsible for conjugation in certain strains of *Escherichia coli*.

sex hormone any steroid hormone that is responsible for controlling sexual characteristics and reproductive function. **Estrogens** and **progesterone** are the female sex hormones, while **androgens** are the male sex hormones. They are produced mainly by the ovaries or testes, with contributions from the adrenals and placenta.

sex hormone-binding globulin (*abbr*.: SHBG) *or* **testosterone-binding globulin** a plasma glycoprotein of the globulin group, secreted by liver, that transports the sex hormones testosterone, estradiol, or their derivatives. Its level increases rapidly early in pregnancy and following estrogen therapy.

Sex lethal *symbol*: *Sxl*; a *Drosophila* gene whose product regulates sexual differentiation. It is so called because it kills flies if it is inappropriately active in males or inactive in females. The functional gene product is expressed in embryos that have the chromosomal constitution 2X:2A where A represents a single set of autosomes. Flies with an X:A ratio of 1.0 express SXL and develop as females whereas those with a ratio of 0.5 do not produce SXL and develop as males. The presence of SXL in females triggers sex-specific alternative mRNA splicing that leads to the production of sex-specific *doublesex* (*dsx*) and *transformer* (*tra*) products.

sex linkage the linkage of a gene producing a certain phenotype (often unrelated to primary or secondary sexual characters) with a **sex chromosome** (usually an X chromosome). Such a gene, or the character it determines, is said to be **sex linked**. Mutation of genes on the X chromosome is often apparent only in male offspring, which have only one X chromosome. The mutation may be masked in the female unless the mutation also occurs on the other X chromosome.

sex pilus (*pl.* **sex pili**) a long (2–3 μm but can be up to 20 μm) hollow proteinaceous projection from the surface of a bacterium that permits **conjugation** and the transfer of an episome from a donor 'male' cell to a recipient 'female' cell. The **F plasmid** of *E. coli* is an episome that carries genes for the expression of the **F-pilus** and is transferred as single-stranded DNA during conjugation.

sexual conjugation *see* **conjugation** (def. 4).

S-form *abbr. for* smooth form; describing bacterial colonies with a **smooth** appearance. *Compare* **R form** (def. 2).

SGD *abbr. for Saccharomyces* genome database; s*ee* **genome database**.

SGF *abbr. for* skeletal growth factor.

SGOT *abbr. for* serum glutamic–oxaloacetic transaminase (not recommended; *see* **aspartate transaminase**).

SGPT *abbr. for* serum glutamic–pyruvic transaminase (not recommended; *see* **alanine transaminase**).

sh *see* **programming language**.

shadow casting a procedure used in the preparation of specimens for electron microscopic examination. The specimen is exposed in a vacuum to a heavy metal evaporated with an electrically heated tungsten filament. Because the metal atoms travel in straight lines, if evaporation is from an acute angle the metal will condense on only one side of the features of the specimen leading to variations in electron density over the specimen, creating a 'shadow' effect.

SHAGGY a protein serine/threonine kinase of *Drosophila* that is highly homologous with mammalian **GSK-3**.

shaker a superfamily of voltage-gated channels for K^+, Na^+, and Ca^{2+} found in animal cells, named for the *Drosophila* mutant from which the first K^+ channel was cloned. Shaker proteins are homotetramers, each subunit containing six transmembrane segments. Segment 4 has a regular pattern of lysine or arginine residues in the third position. This forms the voltage sensor. Between segments 5 and 6 is a loop (the P domain) that is forced back into the membrane by two proline residues at each end (which act as helix breakers), and also contains a conserved TXGYGD motif. The four P domains form the ion pore . *See* **AKT1.**

sham operated describing a control procedure in which all the operations employed in a surgical technique are imitated with the exception of the experimental lesion that is the subject of study.

SHAR *abbr. for* shell archive; a file format that is similar in some respects to a **TAR** file but does not require a special program to extract the archive because of a facility in the UNIX Bourne shell. The command (UNIX or Linux) to extract files from an archive programs.shar is: sh programs.shar.

Shardinger enzyme *see* **xanthine oxidase**.

shark's tooth comb a plastic device for creating wells in an electrophoretic gel. It is shaped like a comb with the teeth coming to a point.

Sharples super centrifuge a, now superseded, efficient centrifuge with a flow-through rotor in which the sedimentation path was short. It is used for harvesting bacteria, blood cells, etc. The version powered with an electric motor turned at 21 000–23 000 rpm while the air-turbine-driven version turned at 50 000 rpm. The instruments of this type have been superseded by others that can operate continuous flow rotors.

SHBG *abbr. for* sex hormone-binding globulin.

SHC a gene family first identified by screening cDNA libraries for genes encoding SH2-containing proteins (*see* **SH domain**). The mammalian gene encodes two overlapping, widely expressed proteins with a C-terminal SH2 domain that binds phosphotyrosine residues on activated growth factor receptors. Phosphorylated Shc binds **Grb2**, and may form a link between certain tyrosine kinases and the Grb2/Ras signalling pathway.

SH domain *abbr. for* Src homology domain; the **SH2 domain** is a protein module, consisting of ~100 residues, found in many proteins involved in signal transduction. Apart from Src, which contains the prototype SH2 domain (*see* **src**), these include, among many others, phospholipase C, products of proto- oncogenes such as **ABL**, **FYN**, and **FGR**, GTPase-activating protein, and protein tyrosine phosphatases. The SH2 domain has also been found in structural proteins such as **fodrin**. One function of the domain is to bind to the autophosphorylated site of growth factor receptors, e.g. PDGF and EGF receptors. Proteins with SH2 domains are frequently found also to have SH3 domains. The **SH3 domain** is composed of ~50 amino acids, and was originally identified in Src, but has since been found within a number of other proteins. SH3 domains mediate protein–protein interactions through their ability to recognize and bind proteins containing specific amino-acid sequences rich in proline and hydrophobic residues. To date, there are known to be at least two general classes of ligand to which SH3 domains can bind: class I, which comprises proteins containing the consensus sequence PxLPPZP; and class II, with the sequence XPPLPxR (where x is any amino acid, and Z appears to be a residue specific to the type of SH3 domain involved). Given the nature of the proteins possessing SH3 domains and SH3-binding domains, it is clear that the protein interactions mediated by these motifs are important to the operation and maintenance of cytoskeletal architecture and intracellular signalling pathways.

SH2 domain *see* **SH domain**.

SH3 domain *abbr. for* Src homology 3 domain. *See* **SH domain**. *See also* ***src***.

shear 1 to disrupt or fracture (an entity) using forces acting parallel to a plane, rather than perpendicularly, as with tensile or compressive forces. For example, shear forces can be used to disrupt DNA or other macromolecules by enclosing the molecules between two closely applied plane surfaces moving rapidly in opposite directions. Homogenization techniques depend on shear forces. **2** the deformation or fracture produced by such forces.

shear gradient *see* **viscosity**.

shear rate *see* **viscosity**.

shear stress *see* **viscosity**.

Sherman paradox the seemingly paradoxical situation in fragile-X syndrome whereby the risk of mental retardation appears to increase in successive generations and the daughter of an unaffected male carrier is more likely to have affected offspring than the mother of the unaffected male carrier. This phenomenon is now called **anticipation**, and is explained by the expansion of CGG repeats during maternal meiosis. [After Stephanie L. Sherman, US geneticist.]

shibire the protein homologue of **dynamin** in *Drosophila*.

shikalkin the racemic mixture of **alkannin** and its (+)(*R*) enantiomer, shikonin.

shikimate the anion of shikimic acid; [–]3α,4α,5β-trihydroxy-1-cyclohexene-1-carboxylic acid; (3*R*,4*S*,5*R*)-trihydroxy-1-cyclohexene-carboxylic acid; an important intermediate, in microorganisms and plants, in the **shikimate pathway** for the synthesis of phenylalanine, tyrosine, tryptophan, and many other substances (e.g. tocopherol, vitamin K, folic acid, ubiquinone, enterobactin, and some antibiotics). The enzyme **3-phosphoshikimate 1-carboxyvinyltransferase** (EPSP synthase) in higher plants is specifically inhibited by the compound **glyphosate**, which inhibits growth and is an effective and readily degraded broad-spectrum herbicide. Shikimic acid was first isolated from the plant *Illicium religiosum* (star anise) in 1885. The name is derived from the Japanese name for this plant, *shikimi-no-ki*. *See also* **shikimate kinase**.

shikimate 5-dehydrogenase EC 1.1.1.25; *systematic name* shikimate: NADP+ 5-oxidoreductase; an enzyme of the **shikimate pathway** that catalyses the reduction by NADPH of 3-dehydroshikimate to shikimate with formation of NADP$^+$. With the now-accepted chemical numbering for shikimate, it is in fact a 3-dehydrogenase. *See also* **pentafunctional arom polypeptide**.

shikimate kinase EC 2.7.1.71; *systematic name*: ATP:shikimate 3-phosphotransferase; an enzyme of the **shikimate pathway** that catalyses the phosphorylation by ATP of shikimate to shikimate 3-phosphate with formation of ADP. The product is the precursor of 5-*enol*pyruvylshikimate 3-phosphate (5-*O*-(1-carboxyvinyl)-3-phosphoshikimate) from which **chorismate** is formed. *See* **pentafunctional arom polypetide** for another example. *See also* **shikimate**.

shikimate pathway a multi-branched metabolic pathway that leads from carbohydrate precursors via shikimate to: (1) phenylalanine and tyrosine, via chorismate and prephenate(*see* **arogenate**); (2) tryptophan, via chorismate and anthranilate; (3) ubiquinone, plastoquinones, and tocopherols, via chorismate; (4) many naphthoquinones (including the vitamins K), 3-carboxy aromatic amino acids, salicylate, and dihydroxybenzoate (for enterobactin formation) via chorismate and isochorismate; and (5) certain non-aromatic cyclohexane compounds, via shikimate. The carbohydrate precursors are phospho*enol*pyruvate and D-erythrose 4-phosphate; they yield 2-dehydro-3-deoxy-D-*arabino*-heptonate 7-phosphate (I, more commonly termed 3-deoxy-D-*arabino*-heptulosonate 7-phosphate, *abbr.*: DAHP) by action of EC 4.1.2.15, 2-dehydro-3-deoxyphosphoheptonate aldolase (DAHP synthase). I is converted to 3-dehydroquinate (II) by 3-dehydroquinate synthase, EC 4.6.1.3, and II is then converted to 3-dehydroshikimate (III) by 3-dehydroshikimate dehydratase, EC 4.2.1.10. Shikimate is then formed from III by **shikimate 5-dehydrogenase**, EC 1.1.1.25, and converted to shikimate 3-phosphate (IV) by **shikimate kinase**, EC 2.7.1.71. Phospho*enol*pyruvate is used again to convert IV to 5-*enol*pyruvylshikimate 3-phosphate (V, *abbr.*: EPSP) by 3-phosphoshikimate 1-carboxyvinyltransferase, EC 2.5.1.19, and V yields chorismate (VI) by action of **chorismate synthase**, EC 4.6.1.4. Chorismate leads to prephenate by action of **chorismate mutase**, EC 5.4.99.5, and undergoes isomerization by isochorismate synthase, EC 5.4.99.6, to form isochorismate. Organization of the various enzymatic activities varies considerably in plants, bacteria, yeasts, and other fungi. In yeasts and other fungi, and also in *Euglena gracilis*, the conversion of DAHP to EPSP requires a complex pentafunctional polypeptide specified by the *arom* gene cluster (*see* **pentafuctional arom polypeptide**).

shikonin the (+)-(*R*) enantiomer of **alkannin**.

Shine–Dalgarno sequence a ribonucleotide sequence for the formation of the preinitiation complex between a 30S ribosomal subunit and an mRNA molecule. It is a seven-nucleotide, pyrimidine-rich sequence near the 3′ terminus of 16S (prokaryotic) or 18S eukaryote ribosomal RNA, found in many organisms, that forms base pairs with a complementary three- to seven-nucleotide, purine-rich sequence (the Shine–Dalgarno sequence) preceding the initiation codon in many mRNA molecules, thereby allowing the initiating ribosomal subunit to bind the mRNA so as to discriminate between AUG or GUG (i.e. initiation) triplets and to select the one at the beginning of a cistron. [After John Shine (1946–) and Lynn Dalgarno (1935–).]

SHIRPA a protocol for phenotype assessment designed to analyse behavioural changes in mice caused by **ENU mutagenesis**. The first four letters of the acronym are from the names of participating institutions in the UK.

shockate the preparation that is obtained when (bacterial) cells are suspended in an osmotically stabilizing medium and lysed by the sudden addition of water, followed by immediate centrifugation.

short-chain describing an aliphatic compound with a chain length of less than 10 carbons.

short-chain acyl-CoA dehydrogenase an enzyme that catalyses the following reaction in fatty-acid oxidation:

$$RCH_2CH_2COSCoA + FAD + RCH = CHCOSCoA + FADH_2$$

in which the acyl moiety (R) contains 4–6 carbon atoms. It is a homotetrameric flavoprotein of the mitochondrial matrix, with each subunit containing 388 amino acids). Several mutations lead to enzyme deficiency, which manifests in infancy as hypoglycemia, acidosis, hyperammonemia, and short-chain organic aciduria.

short interfering RNA *abbr*.: siRNA; a double-stranded RNA, 21–23 bp long, that can specifically silence gene expression. The most efficient gene silencing effect is given by having a 19 nucleotide region complementary to the mRNA and projections of two nucleotides at the 3′ ends.

short-patch repair **excision repair** of DNA in which the excised DNA is about 20 nt long. It contrasts with **very-short-patch repair**, for mismatches between specific bases, and **long-patch repair**, in which stretches of ≈1500 nt or longer are involved. *See also* **DNA repair enzyme**, ***uvr***.

shotgun cloning a method, first used for cloning an entire genome, in which the DNA is randomly broken into fragments of approximately the average size of genes. The fragments are then cloned into suitable vectors, to give a **genome library**.

shotgun collection *see* **genomic library**.

shotgun sequencing a strategy for sequencing whole genomes. Fragmented genomic DNA is cloned into a plasmid vector and randomly picked clones are sequenced using primers annealing to the plasmid. Sequences are compared and aligned using contig building software. Enormous computational power is required for sequencing large genomes in this way.

showdomycin 2-(*β*-D-ribofuranosyl)-maleimide; an antibiotic produced by *Streptomyces showdoensis* and active against several Gram-positive bacteria. It is used as a thiol-reactive agent. *Compare* ***N*-ethylmaleimide**.



shrimp alkaline phosphatase an enzyme that catalyses hydrolysis of 5′-phosphate from DNA (or RNA) regardless of whether the DNA has the 5′ end protruding or recessed, or is blunt-ended.

shRNA *abbr. for* short-hairpin RNA.

shuttle an intracellular metabolic cycle concerned in the transfer of, e.g., reducing equivalents or carbon chains across membranes. Different carriers operate each way across the membrane. Examples include the **3-hydroxybutyrate cycle**, the **glycerol-3-phosphate cycle**, and the **malate–aspartate cycle**.

shuttle vector a DNA molecule, e.g. a plasmid, that can replicate in two different host organisms and can therefore be used to 'shuttle' or convey genes from one to the other.

shuttle vesicle an endocytotic vesicle that transfers proteins across an epithelial cell from one face to another e.g. from the sinusoidal to the bile-canalicular face of a hepatocyte.

sI *symbol for* a residue of the ribonucleoside thioinosine; mercaptopurine ribonucleoside (alternative to Sno).

Si *symbol for* silicon.

***si*-** *stereochemical descriptor* denoting *sinister* (i.e. counterclockwise, or 'left-handed') configuration of face of a trigonal atom. *See* ***Re/Si* convention**.

SI *abbr. for* Système International (d'Unités); International System (of Units); a rationalized coherent system of metric units, in which the magnitude of any physical quantity may be expressed, that is recommended for use by scientists throughout the world. It is based on seven **SI base units**: **ampere**, **candela**, **kelvin**, **kilogram**, **metre**, **mole**, and **second**. There are also 22 named **SI derived units**, which are expressed in terms of the base units, and two **SI supplementary units**, **radian** and **steradian**, which are regarded as dimensionless derived units. A series of prefixes signify decimal multiples and submultiples of any SI unit.

Sia *symbol for* the sialoyl group.

sial+ *a variant of* **sialo+** (before a vowel).

sialagogue *or* **sialogogue** any agent that stimulates the flow of saliva. **—sialagogic** *or* **sialogogic** *adj.*

sialate the anion of **sialic acid**.

sialic of, or relating to, saliva or a salivary gland.

sialic acid any of the *N*- or *O*-substituted derivatives of **neuraminic acid** found as components of complex carbohydrates, e.g. *N*-acetylneuraminic acid (5-(acetylamino)-3,5-dideoxy-D-*glycero*-D-*galacto*-non-2-ulosonic acid, (*abbr*.: Neu5Ac; *see also* **NeuNAc**). Linkage of sialic acids is through C-2 to monosaccharides at the ends of glycosylation chains of glycolipids and glycoproteins. Neu5Ac can also be linked at its C-8 and C-9 hydroxyl groups to another Neu5Ac residue, often forming multiple repeats as in mammalian **NCAM**. Hydroxyl groups at C-4, -7, -8, and -9 can be *O*-acylated (*see also* **NeuOAc**). Other common derivatives are *N*-glycoloylneuraminic acid (in mammals, but not normally in humans; *abbr*.: NeuGc), and N-**ketodeoxyoctanooylneuraminic acid** (e.g. in bacteria). Sialic acid accumulates in lysosomes in Salla disease and infantile sialic acid storage disease, and in cell cytosol in sialuria.

sialidase EC 3.2.1.18; *recommended name*: exo-*α*-sialidase; *former name*: neuraminidase; a glycosidase enzyme that hydrolyses 2,3-, 2,6-, and 2,8-glucosidic linkages joining terminal nonreducing *N*- or *O*-acylneuraminyl residues to galactose, *N*-acetylhexosamine, or *N*- or *O*-acylated neuraminyl residues in oligosaccharides, glycoproteins, or glycolipids.

sialidosis *another name for* **mucolipidosis** I.

sialin *or* **anion and sugar transporter** (*abbr*.: AST); an integral protein (495 amino acids) of lysosomal membranes, that contains 12 transmembrane segments and permits hydron-driven exit of sialic acid (and glucuronic acid) into the cytosol. It is expressed mostly in cardiac and skeletal muscle, liver, kidney, brain, and placenta. Mutations result in the allelic **Salla disease** and infantile sialic acid storage disease.

sialo- *or (before a vowel)* **sial+** *comb. form* **1** of, or relating to, saliva or a salivary gland; sialic. **2** denoting the presence in a compound of one or more residues of sialic acid. *Compare* **asialo+**.

sialoadhesin a macrophage-restricted sialic-acid-dependent glycoprotein receptor of several forms. It contains 17 immunoglobulin-like domains. It is an adhesion molecule that recognizes oligosaccharides terminating in NeuAc(*α*2-3)Gal in N-linked and O-linked glycans.

sialogogue *a variant spelling of* **sialagogue**.

sialosyl the glycosyl group derived by removal of the exomeric hydroxyl group from sialic acid or sialate.

sialoyl the acyl group derived from sialic acid by removing the hydroxyl group from its carboxyl group.

sialuria a very rare, autosomal dominant disease in which coarse features, hepatosplenomegaly, and developmental delay accompany massive excretion of free sialic acid in urine. Sialic acid accumulates in cell cytosol as a result of impaired regulation of sialic acid synthesis by **UDP-*N*-acetylglucosamine 2-epimerase** by the allosteric inhibitor CMP-sialic acid.

SIC *abbr. for* selenocysteine insertion complex.

sickle cell an abnormal red blood cell that contains mostly HbS or HbS and another hemoglobin variant. Such cells occur chiefly in **sickle-cell anemia** and in the sickle-cell trait. At low oxygen tensions such cells adopt a crescent shape reminiscent of the blade of a sickle. In HbS there is replacement of Glu by Val at position 6 in the hemoglobin β chain. In its deoxygenated state the HbS forms long rodlike helical fibres, which deform the red cells because the β6 Val can pack into a pocket at the EF corner (between helices E and F) of another β chain, a pocket which is lost in conformational changes resulting from oxygenation.

sickle-cell anemia an inherited disease of humans caused by homogyzosity for the gene for HbS (*see* **sickle cell**). It is particularly common in populations indigenous to or orginating from the Mediterranean region, parts of Saudi Arabia and India, and in those of African origin. The resultant abnormal red blood cells, called **sickle cells**, are removed from the circulation at a faster rate than normal, leading to anemia. There is no satisfactory treatment, and early death often results. Heterozygotes have **sickle-cell trait**; these survive longer and benefit from greater resistance against the malaria parasite, which is adversely affected by sickle-cell trait during the red-cell phase of its life cycle. When the heterozygous sickle cells pass through capilliaries, they sickle, causing them to lose K$^+$ and killing the malaria parasite, which needs high levels of K$^+$. *See also* **glucose-6-phosphate dehydrogenase**.

side-by-side model *abbr*.: SBS model *or* SBS; a model of duplex DNA consisting of an alternating arrangement of right-handed and left-handed segments of duplex DNA, or other double-stranded polynucleotide, with five base pairs per segment. This produces a structure similar to the **Watson–Crick model of DNA** except that the two antiparallel strands are side by side rather than intertwined in a double helix.

side chain **1** any part of an organic molecule based on an aliphatic carbon chain that can be regarded as branching from a main chain. **2** the part of an amino acid that extends from the α-carbon atom, and is unique to that amino acid.

sideramine one of the categories of **siderochrome**. *See also* **sideromycin**.

siderochrome *see* **siderophore**.

sideromycin any iron-containing antibiotic compound elaborated by certain actinomycetes. Sideromycins are structurally related to sideramines (*see* **siderochrome**), which can antagonize their antibiotic action.

siderophage *an alternative name for* **siderophore D**.

siderophilin *an alternative name for* serotransferrin, serum **transferrin**.

siderophore *or* **siderochrome** any of various low-molecular-mass Fe(III)-chelating substances elaborated by aerobic or facultatively anaerobic microorganisms, especially when growing in iron-deficient media. Fe^{3+}–siderochrome complexes have very high stability constants (10^{30}–10^{50} dm^{3}mol^{-1}). They are taken up by specific transport proteins in the microorganisms; subsequent intracellular release of iron requires enzymic action. Siderophores are of two main categories, one or both of which may be formed by any particular organism: (1) catechol derivatives, e.g. **enterobactin**; and (2) hydroxamic acid derivatives, e.g. **mycobactin** (*see also* **ferrichrome**). The transport systems for ferrichrome or ferric enterobactin in certain strains of bacteria appear to be identical with the membrane receptors for colicin M or B respectively (*see* **colicin**), and in the former case for the antibiotic albomycin and various phages as well.

siderosome a membrane-bound organelle found in spleen macrophages. Siderosomes contain aggregates of **hemosiderin** and may be derived from **lysosomes**.

siemens *symbol*: S; the SI derived unit of **electric conductance**, defined as the electric conductance between two points on an electric conductor when an electric potential difference of one volt causes an electric current of one ampere to flow; i.e. $1\ \mathrm{S} = 1\ \Omega^{-1}$. It was formerly called the **mho** or the reciprocal ohm. [After (Ernst) Werner von Siemens (1816–92),German electrical engineer, industrialist, inventor, and metrologist.]

sievert *symbol*: Sv; **1** the SI derived unit of (radiation) **dose equivalent**, equal to one joule per kilogram of living tissue; i.e. $1\ \mathrm{Sv} = 1\ \mathrm{J\ kg^{-1}}$. Also, 1 Sv = 100 rem. *Compare* **gray**. **2** *or* **intensity millicurie** an obsolete non-SI unit of intensity of gamma radiation, numerically equal to 8.4 röntgens per hour. [After Rolf Maximillian Sievert (1896–1966), Swedish radiation physicist.]

sieve tube exudate protein *abbr*.: STEP; any of numerous types of proteins present usually at low concentration in phloem exudates. They include enzymes of glycolysis, gluconeogenesis, and other aspects of carbohydrate metabolism, structural proteins (**P-proteins**), transcription factors, and lectins.

sievorptive chromatography a form of **chromatography** in which absorption and molecular-sieve properties are combined.

***Si*-face** (of an atom or molecule) *see* ***Re/Si* convention**.

SIF cell *abbr. for* small intensely fluorescent cell.

sigma *symbol*: σ (lower case) *or* Σ (upper case); the eighteenth letter of the Greek alphabet. For uses *see* **Appendix A**.

sigma bond *see* **orbital**.

sigma factor an **RNA polymerase** initiation factor occurring in bacteria; a protein that promotes attachment of the RNA polymerase, of which it is a subunit, to specific initiation sites, and is then released. The main sigma factor of *Escherichia coli* is σ^{70}. An unrelated family is σ^{54}, with associated regulatory proteins; members of this are specific to certain operons. Other sigma factors are involved in response to heat shock and respiratory stress; examples from *E.coli* include σ^{E} and σ^{32}. Major switches in transcriptional control in bacteria, e.g. sporulation in bacilli, and transcriptional control in certain phages, involve modification to, or replacement of, sigma factors.

sigma orbital *see* **orbital**.

sigma receptor any receptor that is activated by powerful psychotomimetic drugs, e.g. **phencyclidine**. Sigma receptors appear to mediate disorientated and depersonalized feelings.

sigma subunit a component of bacterial RNA polymerase; *see* **sigma factor**.

sigmoid *or* **sigmoidal** S-shaped; especially as in a sigmoid flexure (e.g. of the large intestine); or a sigmoid plot, i.e. one similar to a skewed letter S, that is with slope increasing initially slowly, progressively increasing more rapidly, and then decreasing towards a plateau. —**sigmoidicity** *n.*

sigmoid kinetics *(in enzymology)* a type of kinetics of enzyme-catalysed reactions characterized by a sigmoid plot of rate versus substrate concentration. Such kinetics are characteristic of **allosteric** enzymes, in that progressive activation occurs with increasing substrate concentration due to **cooperativity** in binding of substrate. The presence of allosteric modifiers will alter the inflection of the curve, activators shifting it towards that found in Michaelis–Menten kinetics (*see* **Michaelis kinetics**).

signal **1** any variable property or parameter that serves to convey information. **2** the message potentially to be transmitted by any agonist interacting with a cell membrane receptor. **3** a **signal peptide**.

signalase *see* **signal peptidase**.

signal averaging a method used to improve **signal-to-noise ratios**, particularly in spectroscopy, by summing repeated scans of the information. The signals are thereby reinforced while the background noise tends to average out.

signal hypothesis a model, now largely substantiated, for the synthesis of secretory proteins on ribosomes bound to the rough **endoplasmic reticulum**. It holds that secretory proteins have mostly hydrophobic residues at the N terminus, which act as a signal to mediate binding to the ER membrane. It was proposed in 1971 by the US cytologist Gunter Blobel (1936–) and the US cell biologist David Domingo Sabatini (1931–), and by the Argentinian-born British biochemist César **Milstein** (1927–) and coworkers in 1972. *See* **signal peptidase**, **signal peptide**, **signal recognition particle**.

signalling molecule any molecule, e.g. **hormone**, **cytokine**, or **second messenger**, that cues the response of a cell to the behaviour of other cells or objects in its environment.

signal peptidase any endopeptidase that removes the **signal peptide** after passage of a protein through an endoplasmic reticulum (ER), mitochondrial, or chloroplast membrane. In prokaryotes there are two types: **1** signal peptidase I, EC 3.4.99.36; *recommended name*:

leader peptidase; *other name*: prelipoprotein signal peptidase; an endopeptidase that cleaves N-terminal signal peptides from secreted proteins and periplasmic membrane proteins. It is a single-pass protein of the inner membrane. **2** signal peptidase II, EC 3.4.99.35; *recommended name*: premurein-leader peptidase; an endopeptidase that selectively cleaves the signal peptide from bacterial membrane lipoproteins, hydrolysing the protein on the N-terminal side of a specific Cys residue.

In mammals, signal peptidases of the ER (EC 3.4.–.–) consist of: SPC 18 and SPC 21 (single-pass type I transmembrane proteins, each with a luminal serine endopeptidase domain); SPC 22/23 (a single-pass glycoprotein); and SPC 25 and SPC 12 (which span the membrane twice and have termini in the cytosol). Signal peptidases for processing proteins targeted to mitochondrial and chloroplast membranes are poorly understood.

signal peptidase II *see* **premurein-leader peptidase**.

signal peptide *or* **leader peptide** *or* **pre-part** *or* **prepeptide** *or* **prepiece** *or* **presequence** (def.1) *or* **signal** any sequence of amino-acid residues that, when linked to a newly synthesized protein, directs the protein to a location among the organelles of a eukaryotic cell, or from the cytoplasm to the periplasmic space of prokaryotic cells. The term originally applied to the N-terminal linked peptide of secretory proteins that is bound by the **signal recognition particle**, which transfers the ribosome to the endoplasmic reticulum. Such peptides usually comprise 20–30 amino-acid residues, and are characterized by a central region of hydrophobic amino acids preceded by one or more basic amino-acid residues. An interesting feature is that, at the junction of the signal peptide and the mature protein, there is no consensus sequence of amino-acid residues, so the basis for the specificity of the protease at this position remains unclear (*see* **signal peptidase**). The term signal peptide is now more generally applied to any peptide that is responsible for the location of a newly synthesized protein within the organelles of eukaryotic cells (*see* **protein kinesis**). Thus it applies to the mitochondrial proteins synthesized in the cytoplasm, nuclear proteins, and luminal proteins that are retained within the cisternae of the endoplasmic reticulum. In addition to the signal peptides described, which may be located either at the N terminus or C terminus of the nascent protein, and which are subsequently cleaved, single-spanning membrane proteins also contain a signal sequence within the protein known as a **stop-transfer sequence**. This serves to anchor the protein within the membrane. The orientation of the protein within the membrane may be either type I or type II, depending on whether the N terminus of the resulting protein is extracytoplasmic (type I) or cytoplasmic (type II). *See also* **signal recognition particle**.

signal peptide protease *abbr*.: SPP; a presenilin-type aspartic protease that catalyses intramembrane cleavage of some signal peptides after they have been removed from a preprotein. It is an integral membrane protein of the endoplasmic reticulum and contains seven transmembrane segments. In humans it generates signal sequence-derived lymphocyte antigen-E epitopes, which are recognized by the immune system.

signal recognition particle *abbr*.: SRP; a ribonucleoprotein particle of 325 kDa, composed of a 7S (300 nucleotide) RNA molecule and a complex of six different polypeptides. For proteins destined for the endoplasmic reticulum, as they emerge from the large ribosomal subunit, the SRP binds both to the N-terminal signal peptide and to the ribosome. This binding arrests further translation, preventing the proteins from being released into the cytosol. The SRP–ribosome complex then diffuses to the endoplasmic reticulum, where it is bound to the **signal recognition particle receptor**, which allows resumption of protein synthesis, and facilitates the passage of the growing polypeptide chain through the **translocon**. Through a process involving GTP hydrolysis, the SRP–SRP receptor complex dissociates, and SRP returns to the cytosol. Of the six polypeptides of SRP, the 54 kDa subunit (SRP54) is the central player. It contains an N-terminal GTPase domain and a C-terminal domain that binds directly to the signal peptide and the SRP RNA.

signal recognition particle receptor *abbr*.: SRP receptor; a transmembrane heterodimeric protein (α subunit, 69 kDa; β subunit, 30 kDa), also known as **docking protein**, located in the rough endoplasmic reticulum. Both subunits contain GTPase domains with which **signal recognition particle** interacts. In the presence of GTP and SRP receptor, SRP is released from the ribosome–nascent chain complex. The α subunits have a negatively charged N-terminus and a positively charged but phosphorylated cytoplasmic tail (C terminus). *See also* **signal peptide.**

signal-to-noise ratio the proportional difference between the average values for a specific property under investigation (signal) and the average of nonspecific values (noise) in any record. *See also* **signal averaging**.

signal transduction the process by which an extracellular signal (chemical, electrical, or mechanical) is converted into a cellular response. Typically, interaction of a hormone, growth factor, or other agonist with a specific membrane receptor leads to signal amplification by synthesis within the cell of one or more **second messengers**, or to activation of other downstream cascades, e.g. by phosphorylation of proteins. Chemical agonists that cross the cell membrane (e.g. steroid hormones) produce a cellular response without such amplification of the signal. Electrical signals flowing down axonal membranes lead to release of neurotransmitters at synapses. Their plasma membrane receptors are similar to those for hormones and growth factors, or are ion channels. For phototransduction *see* **photosynthesis**, **visual cascade**.

signature *see* **pattern**.

signature database *an alternative name for* **pattern database**.

significant *(in statistics)* reaching a degree of **probability** that experimental values lie on a distribution different from that of control values, such that the investigator will conclude that experimental and control samples differ, using tests such as Student's *t*-test or the chi-square test. The degree of probability that will be accepted as indicating a significant difference depends on the type of investigation being conducted. If the tests indicate that the probability that the results are due to chance is ≥5% (for biological or medical studies) or ≤1% or, in some cases, ≤0.1% (for biochemical studies), differences are considered significant. —**significance** *n.*

silaffin a peptide that is implicated in the biogenesis of diatom biosilica. Silaffins are rich in serine and lysine residues that are, respectively, phosphorylated and linked to long-chain polyamines. Silaffin-1A from *Cylindrotheca fusiformis* has the sequence (before modification): SSKKSGSYSGSKGSK.

silane **1** monosilane; silicon tetrahydride; SiH_4; the silicon-containing analogue of methane. **2** any of a class of saturated silicon hydrides. Such compounds are silicon-containing analogues of alkanes or cycloalkanes; linear or branched silanes are of general formula $Si_n\ H_{2n+2}$, and cyclic silanes, termed cyclosilanes, are of general formula $[SiH_2]_n$ ($n > 2$). The value of n, when >1, may be indicated by a specific or general numerical prefix; e.g. disilane, cyclohexasilane, oligosilane, polysilane. Silane and disilane are gases with a repulsive odour; higher silanes are liquids or solids. Silanes are spontaneously flammable in oxygen or air. **3** *a term often loosely applied to* any hydrocarbyl or other derivative of a silane.

silanization treatment of a hydrophilic surface with a reactive **silane** (def. 3) such as dimethyldichlorosilane, trimethylchlorosilane, octyltrichlorosilane, or an octadecyltrialkoxysilane in order to render it more hydrophobic. Such a treatment is useful in particular for converting hydrophilic **silanol** (def. 4) groups on the surfaces of glassware or dried silica-gel particles into lipophilic alkylsiloxane moieties. When applied to glass, it reduces adsorption of polar compounds and minimizes the activation of lymphocytes, platelets, or other cells that can occur when untreated glass vessels are used; other benefits include promotion of drainage of aqueous liquids and minimization of electrical leakage (*see also* **siliconize**). Silanization has been applied to particles of dried silica gel for use in reversed-phase adsorption chromatography (*see also* **end capping**) and to diatomaceous earth used as the support for the stationary phase in reversed-phase liquid–liquid partition chromatography or in some variants of gas–liquid (partition) chromatography. *Compare* **silylation**. —**silanize** *vb.*; **silanized** *adj.*

silanol **1** silyl hydroxide; H_3SiOH; the silicon-containing analogue of methanol. **2** any monohydroxy derivative of a **silane** (def. 2); such compounds are silicon-containing analogues of alkanols and are of general formula $Si_n\ H_{2n+1}OH$. **3** *a commonly used term for* any *Si*-hydrocarbyl derivative of silanol, silanediol, or silanetriol; such derivatives are respectively of general formula R_3SiOH, $R_2Si(OH)_2$, or $RSi(OH)_3$. **4** the trivalent group –>Si–OH occurring in hydrated silica (so-called silicic acid). Such groups occur also on the surfaces of dried silica-gel particles and of silica-based glasses under normal conditions (i.e. in equilibrium with undried air).

sildenafil *see* **Viagra**.

silent mutation *or* **synonymous mutation** *or* **same-sense mutation** a nucleotide substitution that does not result in an amino acid substitution in the translation product owing to the redundancy of the genetic code. The term 'silent' is also applied to a protein gene product arising from such a mutation, e.g. **silent hemoglobin**. *Other names*: silent site mutation; silent nucleotide change; silent polymorphism.

silent polymorphism *an alternative name for* **silent mutation**.

silica silicon(IV) oxide; silicon dioxide; SiO_2; a colourless or white solid used in many chromatographic procedures; silicic acid contains **silanol** (def. 4) groups to some of which water is bound. For chromatographic use, it is heated to 100 °C to drive out this water. Heating above 170 °C causes formation of oxide linkages (Si–O–Si), and at very high temperatures (800–1000 °C) it forms glass. Silicic acid is available in a variety of particle sizes. For chromatography, these range from 10 to 500 μm, the larger sizes being used for column chromatography at normal pressures, the smaller sizes for thin layer chromatography and high-pressure liquid chromatography. **Silica gel** is silicic acid precipitated as granules, about 3 mm diameter; it is hygroscopic and used as a drying agent, which can be re-used after heating. A powder of very fine silica particles, 0.007–0.014 μm, known as **fumed silica**, has thixotropic properties and has been used to create a gel in organic solvents, e.g. in scintillation cocktails to maintain hydrophilic materials in suspension during counting (now superseded by cocktails that themselves form a gel with water). Silica is found in certain algae, notably in the hard shell, or test, of diatoms (*see* **silaffin**); it also serves to reinforce the stems of the primitive vascular plants known as horsetails.

siliceous *or* **silicious** of, pertaining to, or containing **silica**.

silicone any oligomeric or polymeric **siloxane** containing the repeating structural unit –O–SiR_2–, where R is a hydrocarbyl (e.g. methyl or phenyl) group. The molecule is usually linear, but can be branched, crosslinked, or cyclic. Silicones are odourless and generally colourless, and are characterized by high hydrophobicity and by remarkably high chemical and thermal stability. Silicones may be oils, greases, gums, elastomers, or resins, and have a wide range of clinical, electrical, engineering, industrial, and laboratory applications. In commercial usage, the term often includes organosilicon compounds used for **silanization** and **silylation**.

siliconize to render (filter-paper, glassware, textiles, etc.) water-repellent by application of a coating of an appropriate silicone. *See also* **silanization**. **—siliconized** *adj.*; **siliconizing** *n.*

siloxane any saturated silicon-oxygen hydride with unbranched or branched chains of alternating silicon and oxygen atoms in the molecule. Unbranched siloxanes are of general formula $H_3Si–[O–SiH_2]_n–SiH_3$; each is named after its parent **silane** (def. 2), e.g. disiloxane (n = 0), tetrasiloxane (n = 2). Hydrocarbyl derivatives are commonly included. *See also* **silicone**.

silver staining a sensitive method for detecting protein in polyacrylamide gels. Silver ions are reduced to metallic silver in the presence of the developing reagent, formaldehyde, in a reaction promoted by the protein. Amounts of less than 1 μg of protein can be detected. A modification of the protocol can be used for the sensitive detection of DNA in polyacrylamide gels.

silyl **1** H_3Si–, the group derived from **silane** (def. 1) by loss of a hydrogen atom. **2** any hydrocarbyl derivative, R_3Si–, of the **silyl** (def. 1) group.

silylation the process of converting an organic compound into its **silyl** (def. 2) derivative by attachment of trimethylsilyl (or similar organosilicon) groups. Reagents frequently used are trimethylchlorosilane and 1-(trimethylsilyl)imidazole, although others have particular applications. Reactive compounds include those possessing amino, carboxyl, hydroxyl, or thiol groups, for which silylation affords selective protection during synthetic work (*see* **protecting group**). Silylation is widely used for conversion of mixtures of related compounds into derivatives capable of separation and analysis by gas chromatography/mass spectrometry. *Compare* **silanization**. **—silylate** *vb.*; **silylator** *n.*; **silylated**, **silylating**, *adj.*

simian characteristic of, resembling, or belonging to the apes.

simian immunodeficiency virus *abbr.*: SIV; a lentivirus, common in the sooty mangabey (a type of monkey) and many African green monkeys. SIV_{sM} is closely related to – and probably gave rise to – HIV-2 (*see* **HIV**). HIV-1 is closely related to SIV from chimpanzees. Infection of sooty mangabeys and African green monkeys does not cause disease, but SIV infection occurs in macaques in captivity and is pathogenic.

simian virus 40 *abbr.*: SV40; an icosahedral virus containing circular duplex DNA of about 5.2kb associated with four histones (H4, H2A, H2B, H3) in a minichromosome. It infects monkeys and apes and induces tumours in other species, its DNA being integrated into the host genome. It has two types of life cycle: in permissive cells (usually monkey permanent cell lines) replication occurs in normal infection; in nonpermissive cells there is no lytic infection, but growth transformation can occur. The virus is useful as an **expression vector** in recombinant DNA technology, having good promoter properties: it can be used either as a virion or as a construct maintained transiently in host cells at high copy number in unintegrated plasmid-like DNA molecules. *See also* **small T-antigen**.

similarity *(in bioinformatics)* the extent to which biopolymeric sequences share identical or related characters (nucleotides or amino acids) at equivalent positions, usually expressed as a percentage. For protein sequences, the degree of relatedness of amino acids is quantified in substitution or mutation matrices – e.g. PAM (point accepted mutation), BLOSUM – allowing similarity scores to be assigned in pairwise comparisons.

similarity matrix *see* **scoring matrix**.

simple diffusion *or* **passive diffusion** a type of **diffusion** (def. 2) across a membrane in the absence of any specific transporting agent or carrier. *Compare* **facilitated diffusion**, **active transport**.

simple radial immunodiffusion *see* **single radial immunodiffusion**.

simple sequence repeat *abbr.*: SSR; a DNA sequence comprising repeats of identical or highly similar short motifs. SSRs are polymorphic and include minisatellites, microsatellites, and nontandem motif arrangements (the latter are called **cryptically simple sequences**). SSRs are ubiquitous in the human genome and account for at least 0.5% of genomic DNA.

SIMS *abbr. for* secondary ion mass spectrometer.

sin *abbr. for* sine.

Sin 3 a mammalian nuclear protein that contains four paired amphipathic helix domains and associates with two histone deacetylases, retinoblastoma protein-binding proteins, p53, BRCA1, c-Ski, and possibly other proteins.

sinalbin a glucoside found in white or yellow mustard. *See also* **sinapine**.



sinapine 2[[3-(4-hydroxy-3,5-dimethoxyphenyl)-1-oxo-2-propenyl]-oxy]-*N*,*N*,*N*-trimethylethanaminium; a component of **sinalbin**; it is also found in black mustard and other seeds.



sinaptobrevin *a variant spelling of* **synaptobrevin**.

sine *abbr*.: sin; a trigonometric function, being the ratio of the side of a right-angled triangle opposite a given angle to the hypotenuse; the sine of an obtuse angle is numerically equal to that of its supplement.

SINE *abbr. for* short interspersed nucleotide element; a highly repeated sequence of DNA occurring interspersed in a mammalian genome; it is similar to a **LINE** but is shorter – typically less than 500 bp long. The major SINE in the human genome is the **Alu sequence**. SINEs appear to be processed **pseudogenes** derived from genes that encode small cytoplasmic RNAs including tRNAs. Thus the sequences of SINES are often homologous to the sequences of such RNAs.

Singer–Nicholson model *an alternative name for* **fluid-mosaic model**.

single-cell protein *abbr*.: SCP; a protein-rich material produced by the culture of bacteria, yeasts, other fungi or algae, and extracted for use as a protein supplement in animal or human foods.

single-copy plasmid a plasmid that replicates at the same pace as the bacterial chromosome, and thus maintains equality in numbers with the chromosome.

single nucleotide polymorphism *abbr*.: SNP; a single nucleotide position in a genome sequence at which alternative alleles are present at an appreciable frequency within a population. SNPs are important in biomedical research because they can be used as markers for disease-associated mutations, and may account for the variations in individual responses to bacteria, viruses, toxins, and drugs.

single-pass *(in protein biochemistry)* describing an integral membrane protein that contains only one transmembrane segment. *Compare* **multipass**.

single radial immunodiffusion *or* **Mancini method** an **immunodiffusion** technique in which holes (wells) are cut in a sheet of antibody-containing agar in a glass dish or on a slide. The wells are filled with antigen solution, which is then left to diffuse radially outwards; in doing so, it reacts with antibody to form a ring of precipitate. The diameter of the circle of precipitate is proportional to the concentration of antigen.

single-spanning describing an integral membrane protein having a single hydrophobic sequence embedded in the membrane lipid bilayer. Such a sequence anchors the protein in the membrane.

single-strand binding protein *abbr*.: SSB protein; any of a group of proteins found in bacteria and mitochondria that have a greater affinity for **single-stranded DNA** than for double-stranded species. They are essential for replication, recombination, and repair. They bind tightly and cooperatively, and do not catalyse associated activities, such as the DNA-dependent ATPase activities of **helicases** and **topoisomerases**. They have been called ‘unwinding’, ‘melting’ and ‘helix-destabilizing’ proteins, but each of these names is rather misleading, as these proteins have multiple functions.

single-strand conformation polymorphism analysis *abbr*.: SSCP analysis; a method for detecting mutations by the rate at which single-stranded DNA migrates on electrophoresis gels, under conditions in which the conformation adopted by the DNA is critical. The technique involves amplification of a DNA sequence of interest using the **polymerase chain reaction** (PCR); the DNA is denatured to form single strands and then applied to the gel under nondenaturing conditions. The three-dimensional conformation adopted by ssDNA is sequence dependent and sensitive to single base changes, and this in turn affects the rate of migration in the gel. Wild-type DNA produces two bands of characteristic mobilities that act as references with which to compare the rate of migration of DNA containing a mutation or polymorphism. Heterozygotes characteristically produce four bands on the gel, two from the wild-type allele and two from the mutant or polymorphic allele.

single-stranded DNA *abbr*.: ssDNA; a form of **DNA** consisting of a single chain of deoxyribonucleotides. ssDNA occurs naturally in certain circumstances: (1) transiently, during replication (*see* **replicate**), when the duplex helical molecule of double-stranded (ds) DNA is unwound in the replication fork, initiated by **helicase**; (2) during replication of circular DNA, when in some circumstances only one strand is replicated, yielding a single-stranded product; as replication proceeds, the synthesized DNA unwinds as a single-stranded ‘tail’. Replication may proceed around the unbroken circular DNA strand for more than one cycle, giving rise to the term **rolling circle**; (3) in certain filamentous **coliphages**, such as M13, f1, and fd, which contain a single-stranded circular DNA molecule.

singleton (*in gene sequencing*) a nucleotide sequence that has no overlaps with other fragments at a given stringency and is not therefore contained in any fragment assembly for a given gene.

singlet oxygen a dioxygen molecule in which two 2p electrons have similar spin. It is more highly reactive than the form in which these electrons are of opposite spin. Singlet oxygen is produced in chloroplasts that, due to mutation, lack carotenoids; excited triplet chlorophyll reacts with oxygen to yield singlet oxygen, which is normally quenched by carotenoids. In the absence of carotenoids, lethal photodynamic damage occurs.

single-turnover kinetics the kinetics of an enzyme-catalysed reaction in conditions under which formation of the enzyme–substrate complex can be measured. Such conditions are required for the detection and analysis of transient enzyme–substrate and enzyme–intermediate forms in the pre-steady state (*see* **pre-steady state kinetics**), and contrast with measurement of the multiple recycling of the enzyme in the steady state. Although the reaction is proceeding normally, only the first part is studied, leading to the expression ‘single-turnover conditions’. In this kind of study, a substrate is chosen for which the enzyme–substrate complex can be distinguished from substrate alone, e.g. by having a different absorption spectrum. The rate of formation of the complex can then be determined, often by stopped-flow methods.

singly labelled describing a **specifically labelled** compound containing only one isotopically modified atom in a uniquely specified position, e.g CH_3–CH[^{2}H]–OH.

Sin 3–HDAC *abbr. for* Sin 3–histone deacetylase; a protein complex that in mammals consists of **Sin 3**, two histone deacetylases (HDAC 1 and 2), two retinoblastoma-associated proteins (RbAp46 and RbAp48), and two Sin 3-associated proteins (SAP18 and SAP30)

sinigrin 1-thio-*β*-D-glucopyranose 1-[*N*-(sulfo-oxy)-3-butenimidate] monopotassium salt; a *β*-D-thioglucoside occurring in mustard seeds and horseradish roots; it is used as a substrate for thioglucosidase.



sinister *Latin* left; used to describe the left, or counterclockwise, configuration of one of the two faces of a compound containing a trigonal carbon atom. It is designated by the prefix *si*-. *Compare* **rectus**. *See also* **Re/Si convention**.

sintered glass *or* **frit** small particles of glass that have been heated so that they just fuse but without extensive melting. The resultant material is porous, and is often used in glass filtration apparatus or as a support to retain packing materials in chromatographic columns.

Sir *abbr. for* silent information regulator; any of a family of highly conserved NAD-dependent histone/protein deacetylases, present in nearly all living cells, that catalyse the reaction:

acetyl-protein + NAD =
O-acetyl-ADP ribose + protein + nicotinamide.

In bacteria, Sir-2 controls acetyl-CoA synthetase by deacetylating a residue in the active site. In yeast it is involved in gene silencing, chromosomal stability, and ageing. Sir-2-like proteins are called *sirtuins*. Seven homologues (SIRT1 to SIRT7) occur in humans.

sirna a bioinformatics computer program used for the design of siRNA duplexes.

siRNA *abbr. for* small interfering RNA; a form of microRNA (miRNA) that associates with RNA helicase and RNase molecules to form a complex called **RISC**. The siRNA then unwinds and directs precise, sequence-specific degradation of mRNA. siRNAs are 21–23 bp long, generated by **Dicer** from a dsRNA precursor, and are highly specific for the nucleotide sequence of their target mRNA. They require **Argonaute** to function.

siroheme *or (esp. Brit.)* **sirohaem** a heme molecule discovered in bacterial sulfite reductase, EC 1.8.99.1. It is a tetrahydroporphyrin, having adjacent, reduced pyrrole rings. It is also a component of nitrite reductase (EC 1.6.6.4) from *Nitrobacter*.



siroheme synthase *or (esp. Brit.)* **sirohaem synthase** a multifunctional bacterial protein that contains **uroporphyrin-III C-methyltransferase**, **ferrochelatase,** and precorrin-2 oxidase activities. The latter activity converts precorrin-2 into **siroheme** by oxidation and Fe^{2+} chelation.

sirtuin *see* **Sir**.

sirup *a variant spelling (esp. US) of* **syrup**.

sis an oncogene (v-*sis*) from simian osteosarcoma virus that is also expressed in human connective tissue tumours. The protooncogene, c-*sis*, encodes the B chain of **platelet-derived growth factor** (PDGF), and v-*sis* encodes an almost identical B chain, differing only in the amino acids at its N and C termini. Cells transformed by v-*sis* produce the B chain, which stimulates the PDGF receptor in an autocrine fashion.

site-directed mutagenesis *or* **site-specific mutagenesis** the use of cDNA technology to generate a **point mutation** at a predetermined position in a gene. It may be achieved in a number of ways but is commonly performed by **oligonucleotide-directed mutagenesis**.

site-1 protease *see* **SP1**.

site-2 protease *see* **SP2**.

site-specific DNA methyltransferase *see* **DNA methylase**.

sitosterol 22,23-dihydrostigmasterol; a widely distributed plant sterol related to **stigmasterol**.



β-sitosterol

SI units *see* **SI**.

SIV *abbr. for* simian immunodeficiency virus.

six-frame translation (*in sequence analysis*) translation of a DNA sequence taking into account the three possible reading frames in each direction of the strand, giving rise to three forward and three reverse translations.

six-loop-six structure the topology of an integral membrane protein in which six N-terminal transmembrane segments are separated from six segments in the C-terminal region by a hydrophilic loop. It is characteristic of many transporters in eukaryotes and prokaryotes.

sizing column a **gel-filtration** column that is used to provide information about the M_r (size) of proteins.

sizing gel a **gel-filtration** medium, especially one used in a sizing column.

sizukacillin *see* **peptaibophol**.

Sjl protein *abbr. for* synaptojanin-like protein; any of three proteins of yeast that have phosphatidylinositol-5-phosphatase activity: Sjl1p (946 amino acids); Sjl2p (1183 amino acids); and Sjl3p (1107 amino acids). The first two seem to function in endocytosis.

Sjögren–Larsson syndrome an autosomal recessive disorder in which congenital ichthyosis is associated with mental retardation, retinopathy, spastic diplegia or tetraplegia, and accumulation of fatty alcohols in tissues. It results from mutations that cause deficiency of the enzyme fatty aldehyde:NAD^+ oxidoreductase. [After Torsten Sjögren (1859–1939), Swedish physician, and Tage Konrad Leopold Larsson (1905–), Swedish scientist.]

Sjögren syndrome an autoimmune disease, usually of middle-aged women, in which lymphocytes infiltrate and destroy salivary and lacrimal glands, and autoantibodies for several ribonucleoproteins appear in serum. It is often associated with other autoimmune diseases. [After Henrik C. Sjögren (1899–1986), Swedish ophthalmologist.]

S2 kallikrein *see* **tonin**.

SKALP *abbr. for* skin-derived antileukoproteinase; *other name* elafin; a serine protease inhibitor; it probably inhibits elastase-mediated tissue proteolysis.

skatole 3-methylindole; a bacterial metabolic product of indoleacetic acid that contributes to the odour of feces.

skeletal growth factor a protein that stimulates bone growth. Skeletal growth factor from human bone (hSGF) stimulates growth in human bone cells and embryonic chick bones in culture. The activity involves **insulin-like growth factors** (IGFs) in association with IGF-binding proteins (IGFBPs).

skeletin *(formerly) an alternative name for* **desmin**.

skeleton 1 *(in zoology)* any structure that provides support and protection for the soft tissues and organs of the body. An **exoskeleton**, such as the cuticle in arthropods, lies external to the body tissues, while an **endoskeleton**, such as the bony or cartilaginous skeleton of vertebrates, lies within the body. **2** *(in chemistry)* the carbon chain of a molecule, including any noncarbon elements that necessarily link carbon moieties of the chain. —**skeletal** *adj.*

skew 1 asymmetric, biased, distorted. **2** oblique, slanting. **3** (of a statistical distribution) not symmetrical about the mean. **4** to become or make skew; to distort. *See also* **skew conformation**. —**skewness** *n.*

skew conformation 1 any conformation of a six-membered ring form of a monosaccharide or monosaccharide derivative when three adjacent ring atoms and the remaining nonadjacent ring atom are coplanar. Such compounds may be designated by the conformational descriptor -*S* added to the name. The reference plane is so chosen that the lowest-numbered carbon atom in the ring, or failing that the atom numbered next above it, is exoplanar. Skew conformation is the median conformation through which one **boat conformation** passes during conversion to another boat conformation in the cycle of flexible forms; it is similar to **twist conformation** (def. 1). *See also* **conformation**. **2** *a less common alternative term for* synclinal conformation; *see* **conformation**.

Ski *abbr. for* super killer; any of a group of yeast cytoplasmic proteins that normally repress translation of an endogenous RNA virus. When Ski protein is mutated, a super killer phenotype results from overexpression of a toxin by the virus. Ski2p, Ski3p, Ski7p, and Ski8p are associated with the exosome core in the cytoplasm.

SKI a gene related to v-*ski*, the oncogene of Sloan-Kettering viruses; it has no marked homology with other oncogenes. It does not bind DNA but interacts with a histone deacetylase complex, Sin3, and Smads 2 and 3.

slab gel a gel, usually polyacrylamide or starch, that is formed as a sheet rather than a rod.

slaty a coat colour mutation in mice allelic for the *tyrp-2* gene that causes dark-grey (slate-coloured) melanin to be formed. The enzyme affected is **dopachrome *Δ*-isomerase**.

SLC *abbr. for* solute carrier; any member of the solute carrier gene series, which currently comprises 43 families and 298 transporter genes. SLC7A7, for example, is a gene for the cationic amino acid carrier light chain belonging to family SLC7.

sleep peptide any peptide that brings about sleep when infused into the cerebrospinal fluid (CSF) of animals. Delta-sleep- inducing peptide, isolated from CSF, has the structure Trp-Ala-Gly-Gly-Asp-Ala-Ser-Gly-Glu. A large number of endogenous substances isolated from the brain can likewise induce sleep, but it is not known if this is their physiological function.

sliding clamp *an alternative name for* proliferating cell nuclear antigen. *See* **PCNA**.

sliding filament model a model of muscle contraction in which contraction results from **thin filaments** sliding past **thick filaments**. The activation involves enhanced binding of Ca^{2+} by troponin C (*see* **troponin**) associated with the thin filament. In the resting state, troponins I and T inhibit the actin–tropomyosin complex of the thin filament from binding to myosin; increase in Ca^{2+} concentration causes troponin C (each molecule of which binds up to four Ca^{2+} ions) to release this inhibition, allowing the myosin headgroups to bind actin. Then, in the presence of ATP, the thin filaments slide over the thick filament myosin molecules to cause contraction. The ATPase of myosin heads hydrolyses the ATP; the latter must be continuously produced for contraction to continue.

sliding 1 the mode of action of ***lac* repressor** in *Escherichia coli*. It first binds at a non-operator site, then slides along the DNA until it finds the target site, i.e. the **operator**. **2** the displacement of a nucleosome along a track of DNA. *See* **sliding clamp**, **sliding filament model**.

slime mould *or (US)* **slime mold** any of a group of organisms that exhibit features of both fungi and protozoa. Characteristically they exist as slimy masses on decaying wood or in damp soil, and have the ability to switch from an amoeboid single-celled phase, called a **myxamoeba**, to an aggregated or multicellular phase from which fruiting bodies may arise. In the so-called **true slime moulds**, the myxamoebae form an acellular mass called a plasmodium, whereas in the **cellular slime moulds** the myxamoebae aggregate to form a multicellular pseudoplasmodium, or 'slug'. A well-known example of a cellular slime mould is *Dictyostelium discoideum*; when the food supply is exhausted, its myxamoebae aggregate to form a small (1–2 mm) slug, containing up to 10^5 cells, which migrates to seek an area of food abundance. When nutritional conditions are favourable the slug undergoes differentiation to form fruiting bodies, from which spores are released. Germination of a spore leads to the formation of a myxamoeba. *D. discoideum* has a relatively small genome (about 10 times larger than that of a bacterium) and is popular with geneticists, providing insights into the nature of the inducible behaviour leading to aggregation, and the rapid cell division and differentiation that precede the formation of a fruiting body.

slip a term used for situations in which the mitochondrial enzyme, **cytochrome *c* oxidase**, may carry out its reaction without pumping protons into the intermembrane space.

slit one of a group of proteins, secreted by cells at the midline in the *Drosophila* embryo, that binds to a **Robo** receptor on growth cones of axons and prevents them from crossing the midline. Slit proteins are also present in non-neuronal tissues.

slope $\delta y/\delta x$, where results are expressed graphically as a continuous line, the ordinate (vertical axis) representing *y*, the abscissa (horizontal axis) representing *x*.

slow-cycling rhodopsin a **retinal**-containing, energy-transducing pigment present in small amounts in some of the strains of *Halobacterium halobium,* in which purple membranes occur. It is distinct from **bacteriorhodopsin** and **halorhodopsin**, and is believed to play a role in the characteristic variation in the phototactic response of such organisms at different wavelengths. Illumination with yellow light, or with blue or near-ultraviolet light, results respectively in accumulation of forms with absorption maxima at 375 nm and 590 nm.

slow reacting substance (of anaphylaxis) *or* **slow reacting substance A** *abbr*.: SRS *or* SRS-A; a substance that mediates anaphylaxis; it was identified as a polar, lipid-like compound synthesized in mammalian tissues as a consequence of the combination of antibody with antigen. It increases vascular permeability and induces contraction of some types of smooth muscle, especially bronchial muscle. It is slow in action relative to histamine – hence its name – and is not antagonized by antihistamines. **Leukotrienes C_4**, **D_4**, and **E_4** are the active components.

SLP-76 *abbr. for* SH2-containing leukocyte protein 76 kDa; an adaptor protein involved in platelet degranulation, secretion of interleukin 2, and formation of lymphatic vessels. It is phosphorylated on tyrosine residues by **Syk**.

slurry a fluid suspension of particles having the consistency of cream.

Sly syndrome *see* **mucopolysaccharidosis VII**.

Sm *symbol for* samarium.

***Sma* I** a type 2 **restriction endonuclease**; recognition sequence CCC↑CGG.

Smac *abbr. for* second mitochondria-derived activator of caspases. *See* **Diablo**.

Smad any of several proteins that act as transcription factors. The name is derived from a fusion of the gene names *sma* (in *Caenorhabditis elegans*) and *Mad* (in *Drosophila*). Smads fall into one of three classes: (1) receptor-regulated (R-Smads: 1, 2, 3, 5, and 8); (2) common-partner (Co-Smads: 4 and 4β); and (3) inhibitory (I-Smads: 6 and 7). R-Smads and Co-Smads share two highly homologous sequences in the N-terminal and C-terminal regions: one is important for complex formation, regulation of transcription, and interaction with receptor serine/threonine protein kinases (e.g. bone morphogenetic protein receptors); the other binds DNA and associates with other transcription factors. R-Smad-Co-Smad dimers enter the nucleus following activation by ligand binding to the receptors.

small cytoplasmic ribonucleoprotein *abbr*.: scRNP; *other name*: 'scyrp'; any particulate complex of proteins with molecules of **small cytoplasmic RNA**, found in the cytoplasm. The function of scRNPs is unknown.

small cytoplasmic RNA *abbr*.: scRNA; any of various low-molecular mass RNA molecules (100–300 nt) found in the cytoplasm as components of **small cytoplasmic ribonucleoprotein**.

small Hsp one of a family of small heat-shock proteins. Like the alpha-crystallin family they consist of 12- to 43-kDa proteins. They tend to form large multimeric complexes. Their chaperone activity is confined to the binding of unfolded intermediates, thereby protecting them from irreversible aggregation. Unlike Hsp70 and Hsp90, the function of small Hsp is not dependent on ATP.

small intensely fluorescent cell *abbr*.: SIF cell; a cell found in autonomic ganglia and containing dopamine. The name derives from the appearance of such cells after formaldehyde condensation in fluorescence microscopy.

small leucine rich proteoglycans a group of small interstitial proteoglycans which have a high degree of homology in their protein core sequence. Each has between 10 and 12 highly conserved leucine rich tandem repeats which makes up the central portion of the core protein. The current members of the group are **fibromodulin** and **lumican**, which are both keratan sulphate substituted, and **decorin** and **biglycan** which are both chondroitin sulphate substituted.

small modulating RNA *abbr*.: smRNA; small (~20 bp) noncoding double-stranded RNAs with possible functions in regulating cell-type-specific gene expression.

small nuclear ribonucleoprotein *abbr*.: snRNP (hence often colloquially termed 'snurp'); any of various particulate complexes of proteins with molecules of **small nuclear RNA** (snRNA), found in the eukaryotic nucleus; the particles are ~250 kDa. They are named according to the snRNAs they contain: the U4/U6 snRNP, e.g., contains U4 and U6 snRNA. They are involved in RNA splicing (*see* **spliceosome**). Patients with systemic lupus erythematosus make antibodies directed against one or more snRNPs.

small nuclear RNA *abbr*.: snRNA; any of the RNA molecules (100–300 nt) that contain a uridine-rich region, are designated U1, U2, ... U12 RNA, and are found in the eukaryotic nucleus as components of **small nuclear ribonucleoprotein**. *See* **Sm protein**, **spliceosome**.

small nucleolar ribonucleoprotein *abbr*.: snoRNP (hence often colloquially termed ‘snorp’); any of various particulate complexes of proteins with molecules of **small nucleolar RNA**, found in the eukaryotic nucleolus. They are possibly the same as **processosomes**.

small nucleolar RNA *abbr*.: snoRNA; any small RNA that is associated with the eukaryotic nucleus as a component of **small nucleolar ribonucleoproteins** and participates in the processing of ribosomal RNA in cell nuclei. snoRNAs have a long stretch of sequence complementarity to conserved sequences in mature mRNA. Six have been identified in metazoan cells (87–280 bases) and 12 in yeast (125–605 bases). They seem to assemble with a large multi-RNA RNP complex.

small serine proteinase inhibitor *see* **smapin**.

small T-antigen *see* **T-antigen** (def. 1).

smapin *abbr. for* small serine proteinase inhibitor; any protein (up to 100 amino acids) of nematodes that contains five disulfide bonds and inhibits serine proteinases.

S_1 mapping *or* S_1 **nuclease mapping** a technique based on the ability of **S_1 nuclease** to remove single-stranded (ss) DNA or ssRNA from DNA/RNA hybrids. It has been used to detect coding regions in DNA that has been hybridized – with cDNA for a particular mRNA or the mRNA itself – since any ssDNA formed by introns is removed by the S_1 nuclease leaving only the coding DNA. The enzyme can be used similarly to identify the 5′ end of a mRNA.

SMART *abbr. for* simple modular architecture research tool; *see* **derived database**.

Smc *abbr. for* structural maintenance of chromosomes; any of a family of proteins involved in binding to and separation of sister chromatids during the cell cycle. Smc1 and Smc3 are components of the **cohesin** complex. Smc2 and Smc4 are components of the **condensin** complex.

SMCC *abbr. for* SRB- and MED-containing cofactor complex; a multiprotein complex (1.5 MDa, ≈25 polypeptides) that contains several homologues of components of the yeast transcriptional coactivator mediator. Its subunit composition is almost identical to that of **TRAP**.

SmcX a protein encoded on the X chromosome that escapes X-chromosome inactivation in mouse and human. It belongs to the ARID family of DNA-binding regulatory proteins (*see* **ARID protein**). A homologue (called **SmcY**) is encoded on the Y chromosome.

SmcY a protein encoded on the Y chromosome that is homologous to **SmcX**. It belongs to the ARID family of DNA-binding regulatory proteins (*see* **ARID protein**). In mouse, it is essential for expression of male-specific minor histocompatibility antigens.

smectic (of a substance) being or having a **mesomorphic** state in which the molecules are arranged in parallel layers. The molecules in any layer can move in the plane of that layer but not into adjacent layers. *Compare* **nematic**. *See also* **liquid crystal**.

smectic mesophase *see* **liposome**, **liquid crystal**.

Smith–Waterman alignment algorithm *(in sequence analysis)* a global dynamic programming algorithm optimized for local alignment. A modification of the **Needleman–Wunsch alignment algorithm**, it aligns similar segments of sequence pairs and exploits a substitution matrix with negative values (otherwise, if non-negative values are used, it behaves as a global alignment algorithm). *See* **alignment algorithm**.

SMN protein *abbr. for* survival motor neuron protein; a protein (294 amino acids) that is widely expressed in cell nuclei, where it interacts with components of the spliceosome. Mutations, including gene deletions, cause autosomal recessive spinal muscular atrophy.

smooth describing a bacterial strain having shiny (smooth) colonies. *See* **smooth–rough variation**.

smooth endoplasmic reticulum *abbr*.: SER; *see* **endoplasmic reticulum**.

smooth muscle *or* **involuntary muscle** muscle that lacks striations, hence giving a ‘smooth’ appearance under the microscope; it produces slower, longer lasting contractions than **striated muscle** and is present in visceral organs such as stomach, bladder, intestine, and uterus, and the walls of arteries. The cells are mononucleate, and contain both **thick filaments** and **thin filaments** but not in the pattern that leads to striations. Contraction is regulated by the sarcoplasmic (cytosolic) free Ca^{2+} concentration, which increases from resting levels of 120–270 nm to 500–700 nm in response to stimuli such as membrane depolarization, or α-adrenergic or muscarinic agonists. Ca^{2+} bound to calmodulin activates **myosin-light-chain kinase**, which phosphorylates myosin at Ser^{19} of each of the two 20 kDa light chains. This causes cycling of myosin cross-bridges along actin filaments and the development of force (*see* **sliding filament model**). **Calponin**, **caldesmon**, and **protein kinase C** may also play a role in fine-tuning the contractile state.

smooth–rough variation *or* **S→R variation** any type of cell-surface variation that occurs in bacteria, usually changing the appearance of colonies from that of the original. In the Enterobacteriaceae the colonies are typically shiny (smooth) and change to matt (rough), an S→R variation that may be accompanied by loss of surface antigens, reduction or loss or virulence, and changes in susceptibility to certain bacteriophages.

Sm protein any of a family of proteins that participate in splicing of pre-mRNA. Seven members assemble into a ring, their inner surface binding the uridine-rich region of small nuclear RNAs that are shared among small ribonucleoproteins.

smRNA *abbr. for* small modulating RNA.

SMRT *abbr. for* silencing modifier of retinoid and thyroid hormone; a protein that binds **NCoR** and unliganded receptors for retinoic acid and thyroid hormone. This complex then binds the histone deacetylase complex **Sin 3-HDAC**, which represses transcription.

***sn*-** *prefix* signifying stereospecifically numbered; it is used in designating the configuration of derivatives of prochiral compounds (especially glycerol and its derivatives) to ensure differentiation from conventional numbering. Thus sn-1 denotes C-1 of the glycerol moiety of a phospholipid under the **stereospecific numbering** system. C-2 and C-3 are similarly denoted *sn*-2 and *sn*-3.

Sn *symbol for* tin.

SNAP *abbr. for* **1** *S*-nitroso-*N*-acetylpenicillamine. **2** synaptosome-associated protein; a number of these exist. The nomenclature has become somewhat confusing, since SNAPs exist with different but closely related roles. Thus SNAP-25 functions as a SNAP receptor, or **SNARE**, while other SNAP proteins such as α-SNAP (*see* def. 3) function to bind NSF proteins (*see* ***N*-ethylmaleimide**) to SNAREs such as SNAP-25. **3** soluble NSF attachment proteins, such as α-SNAP, β-SNAP, etc. These are cytoplasmic proteins that mediate binding of ***N*-ethylmaleimide-sensitive fusion protein** to membranes. *See also* **SNARE**, **SNARE hypothesis**.

SNARE *abbr. for* SNAP receptor; **syntaxin**, **synaptobrevin**, and SNAP-25 (*see* **SNAP** (def. 2)) act as SNAREs; they bind in an ATP-dependent manner to NSF–SNAP complexes (SNAP in this case being the NSF attachment protein (*see* ***N*-ethylmaleimide**)). Syntaxin, synaptobrevin, and SNAP-25 form a complex that is much more effective than the single proteins acting alone, suggesting that a core complex bridges the synaptic vesicle and plasma membranes, and may function in the docking and fusion process. *See also* **SNARE hypothesis**.

SNARE hypothesis a model of vesicular fusion that involves two types of **SNARE;** v-SNAREs on vesicles and t-SNAREs on target membranes. Each transport vesicle has its own v-SNARE, which recognizes a cognate t-SNARE on a target membrane and mediates docking; fusion is then mediated by *N*-ethylmaleimide-sensitive fusion protein and an attachment protein (**SNAP** (def. 3)).

Snell’s law *see* **refraction**.

SNF *abbr. for* sucrose nonfermenting; a defect in *Saccharomyces cerevisiae* that prevents it from metabolizing sucrose because of failure to activate transcription of the sucrase gene. *See* **SWI/SNF**.

Sno *symbol for* a residue of the ribonucleoside thioinosine; mercaptopurine ribonucleoside; alternative to sI.

snoRNA *abbr. for* small nucleolar RNA.

snoRNP *abbr. for* small nucleolar ribonucleoprotein.

snorp *colloquialism* for snoRNP, i.e. **small nucleolar ribonucleoprotein**.

SNP *abbr. for* single nucleotide polymorphism.

snRNA *abbr. for* small nuclear RNA.

snRNP *abbr. for* small nuclear ribonucleoprotein.

S_1 nuclease EC 3.1.30.1; *recommended name*: *Aspergillus* nuclease S_1; an endonuclease from *Aspergillus oryzae* that degrades single-stranded (ss) RNA or ssDNA to 5′ mononucleotides; it has no apparent base specificity. It is useful for the removal of unpaired regions in hybridization technology (*see also* **S_1 mapping**). The enzyme is a monomer, and contains three zinc atoms.

SNuPE *a proprietary name for* single nucleotide primer extension; a method for detecting **single nucleotide polymorphisms** in which a primer is annealed to the target sequence with its 3′ end immediately before the polymorphic site. The identity of the polymorphic nucleotide is revealed by which of the four different fluorescently labelled dideoxynucleoside triphosphates, incorporated by DNA polymerase, it forms a base pair with .

snurp *colloquialism for* snRNP, i.e. **small nuclear ribonucleoprotein**.

snurposome any morphologically and biochemically distinct granule in the amphibian oocyte nucleus that contains one or more types of small nuclear ribonucleoproteins (snRNP).

soap any salt formed between a hydroxide of a metal (usually an alkali or alkaline earth) and a higher fatty acid; such compounds are useful as **detergents** (def. 2). It can also mean the salt of any ionized lipid **amphipath**, e.g. of a long-chain amine or sulfate or of a sterol carboxylate. The common soaps were traditionally the mixed sodium salts (giving **hard soaps**) or the mixed potassium salts (giving **soft soaps**) of oleic, palmitic, and stearic acids, prepared by **saponification** of animal or vegetable fats or oils with sodium or potassium hydroxide respectively. Modern soap compositions are more complex, with solid or liquid soaps containing various additional detergents.

soapstone *see* **talc**.

SOB medium a nutritionally rich growth medium for the culture of recombinant strains of *E. coli*.

SOC medium a nutritionally rich growth medium for the culture of recombinant strains of *E. coli*. It is identical to **SOB medium** except that it contains 20 mM glucose.

SOD *abbr. for* superoxide dismutase.

soda any of various compounds of sodium, especially sodium hydroxide (NaOH; **caustic soda**), sodium hydrogencarbonate (sodium bicarbonate, $NaHCO_3$; **baking soda**), sodium carbonate decahydrate ($Na_2CO_3{\bullet}10H_2O$; **washing soda**), or sodium monoxide (Na_2O).

soda glass common glass, made from a mixture of silica, sodium oxide (soda), and lime, in approximate proportions SiO_2 70%, Na_2O 15%, CaO 10%. Its low melting point led to the production of more heat-resisting glasses, e.g. Pyrex. *See also* **borosilicate (glass)**.

sodium *symbol*: Na; a soft, silvery-white, highly reactive alkali metal of group 1 of the (IUPAC) **periodic table**; atomic number 11; relative atomic mass 22.997. Sodium is widely distributed and is one of the most abundant elements of the Earth's crust, notably as sodium chloride (salt), especially in sea water. Apart from the nonradioactive, and most abundant, isotope, sodium-23, there are two radioactive isotopes, **sodium-22** and **sodium-24**. In biochemistry, sodium (Na^+) is the principal extracellular cation, and the one that largely determines the extracellular fluid volume. In humans the normal range for plasma sodium is 135–145 $mmolL^{-1}$. Sodium ions are actively pumped out of cells by **sodium/potassium ATPase**. Their concentration is regulated by **aldosterone**, which increases sodium reabsorption in the kidney distal tubule. Sodium was formerly known as 'natrium', hence the symbol Na and the term **natriuretic**.

sodium-22 a radioactive nuclide of sodium, $^{22}_{11}Na$. It emits a β^+ particle (1.83 MeV) and gamma radiation (1.275 MeV). Its half-life is 2.605years.

sodium-24 a radioactive nuclide of sodium $^{24}_{11}Na$. It emits an electron (β^- particle, 1.39 MeV) and gamma radiation (2.75 MeV). Its half-life is 15.02h.

sodium–alanine symporter *see* **sodium/neutral amino acid cotransporter**.

sodium–calcium ion exchanger a plasma membrane protein **antiporter** of muscle and nerve cells that promotes the exchange diffusion of sodium and calcium ions. Influx of Na^+ to the cytosol drives the efflux of Ca^{2+} from the cell. The affinity for Ca^{2+} is low, so that it only functions at high intracellular Ca^{2+} concentrations, transporting Ca^{2+}, e.g., during excitation–contraction coupling.

sodium channel any structure that permits controlled (gated) passage of sodium ions through membranes. Voltage-gated channels are involved in conduction and transmission of nerve impulses, whereas transmitter-gated channels respond only to neurotransmitters (*see* **cholinoceptor**). Voltage-gated channels are integral proteins in the plasma membranes of excitable cells. They sense the membrane electric field, opening channels to permit an inward flux of sodium ions, thereby causing the membrane depolarization that is essential for the propagation of the **action potential**. The *Electrophorus* electroplax protein is a single chain of about 2000 amino-acid residues and contains four homologous repeats, each of which has six putative transmembrane segments with extensive nonmembrane cytosolic and extracellular loops. It shares significant homology with other ion channels, particularly the α1 subunit of the Ca^{2+} channel. A cytoplasmic loop has been implicated in the rate of inactivation of the channel. The protein bears about 500 sugar residues (mostly *N*-acetylglucosamine and sialic acid) and 50 fatty-acyl chains (palmitoyl and stearoyl). The mammalian channels are heterooligomeric, consisting of a large α subunit similar to the *Electrophorus* protein, and several other smaller peptides; most of the functional properties reside in the α subunit. The α subunit is the target for polypeptide neurotoxins, e.g. from scorpions; other sodium-channel blockers include **saxitoxin**, **tetrodotoxin**, and **veratridine**.

sodium dodecyl sulfate *or (esp. Brit.)* **sodium dodecyl sulphate** *abbr.*: SDS; sodium lauryl sulfate; $CH_3(CH_2)_{10}CH_2OSO_3{\bullet}Na$; the sodium salt of the 1-dodecanol half-ester of sulfuric acid (1-dodecanol was formerly known as lauryl alcohol). It is an anionic detergent and wetting agent; aggregation number 62 (0–0.1 m Na^+), 101 (>0.1 m Na^+); CMC 7–10 mm (0–0.05 m Na^+), 1–2 mm (0.1–0.2 m Na^+). The amphipathic dodecylsulfate anion is a powerful hydrophobic-bond breaker, hence it is much used in protein chemistry as, e.g., a denaturant, a dissociant of oligomers, and a solubilizer of membrane components. *See also* **SDS–polyacrylamide gel electrophoresis**.

sodium–hydrogen ion exchanger a plasma membrane protein that functions as a Na^+/H^+ **antiporter**. Influx of Na^+ drives the efflux of H^+. It functions to maintain intracellular pH, to which it is sensitive, its activity increasing as pH falls.

sodium-ion channel *see* **sodium channel**.

sodium/neurotransmitter transporter any of a family of integral membrane glycoproteins, having 12 putative transmembrane helices, that are involved in sodium-dependent transport of neurotransmitters: e.g., the sodium- and chloride-dependent GABA transporter 1 from human, which is the target for cocaine and other psychomotor stimulants.

sodium/neutral amino-acid cotransporter an integral membrane protein responsible for the Na^+-dependent uptake of the neutral amino acids alanine, serine, glycine, cysteine, and proline. Transporters with specificities for different types of amino acid are **system A**, **system L**, and **system N**.

sodium/potassium ATPase EC 3.6.1.37; *recommended name*: Na^+/K^+-exchanging ATPase; *systematic name*: ATP phosphohydrolase (Na^+/K^+-transporting); *other names*: sodium pump; Na^+,K^+-ATPase. An integral membrane protein that catalyses the hydrolysis of ATP to ADP and orthophosphate. Na^+,K^+-ATPases pump out approximately 3 Na^+ ions for every 2 K^+ ions that enter, with hydrolysis of 1 ATP. They consist of two large α subunits and two smaller β subunits. The α subunits bear the active site and penetrate the membrane, while the β subunits carry oligosaccharide groups and face the cell exterior only. **Ouabain** is a specific inhibitor.

sodium pump any **transporter** of sodium ions across membranes, especially enzymes of the Na^+,K^+-ATPase type (*see* **sodium/potassium ATPase**). The Na^+/K^+ ratio across the plasma membrane of eukaryotic cells (outside: Na^+ 140 mm, K^+ 10 mm; inside: Na^+ 10 mm, K^+ 100 mm) requires that sodium ions be continually pumped out of the cell in exchange for potassium ions if the gradient is to be maintained; this is an energy-requiring process. *See also* **active transport**.

software archive a site, usually accessed by **anonymous FTP**, from which public-domain software can be downloaded. Some software is in binary, i.e. is designed to be loaded directly into the local computer; some code is written in a high-level language, such as C, C++, or PERL, and needs to be compiled locally. Typically software for Windows PCs and Apple Macintosh computers is of the former type, and more generic code and software for UNIX and

Linux systems is of the latter and requires compiling, typically with a supplied **Makefile** or (in the case of Linux) as an **RPM** file.

sol any fluid colloidal system composed of two or more components. The dispersed phase may be either particles of solid or droplets of liquid, and the continous phase either a liquid or a gas (*see* **aerosol**).

solanesol a 45-carbon polyprenol present in tobacco leaves.



solation the (usually reversible) act or process of forming a **sol** from a **gel**. *Compare* **gelation**. —**solate** *vb.*

solenoid 1 a cylindrical coil of wire that acts as a magnet when carrying an electric current. **2** a tightly coiled higher-order structure of **chromatin** consisting of stacks containing six nucleosomes per turn. **3** the coiled structure of some proteins.

solid a physical state of matter in which the constituent atoms, ions, or molecules have no translatory motion though they vibrate about fixed positions. In **crystalline solids** the constituents are arranged in a definite array, whereas in **amorphous solids** they are not. Solids, especially crystalline solids, commonly have characteristic melting temperatures at which they change to **liquids**.

solid-phase peptide synthesis *see* **peptide synthesis**.

solid-phase technique any technique in which reagents are immobilized on a support or in some other way insolubilized. In **radioimmunoassay** the insolubility or binding properties of an antigen–antibody complex are commonly exploited to remove labelled antigen. Enzymes immobilized on columns (**immobilized enzymes**) have many applications. In **peptide synthesis**, the growing peptide chain may be immobilized on a column. So-called solid-phase extraction systems are in effect extractions using batch column chromatography techniques, in which the material to be extracted is bound to a column, then removed by **batch elution**. In peptide **sequencing** a peptide immobilized on a column may be degraded residue by residue, facilitating recovery of the undegraded remaining peptide at each cycle.

solid scintillation fluorography a technique for visualizing radioactive materials in a specimen (e.g. a chromatogram) by covering the specimen with a solid **fluor** and allowing the ejected photons to darken an applied photographic emulsion. *Compare* **fluorography** (def. 2).

solid-state *(in electronics)* describing any system in which current flow takes place entirely through solid materials, such as semiconductors and transistors, rather than through vacuum devices such as thermionic valves.

solubility 1 the attribute of being soluble, of being able to dissolve. **2** the amount of a substance (**solute**) that can dissolve in a given amount of another substance (**solvent**) at a given temperature and pressure.

solubility product *symbol*: K_{sp}; for a solute $A_x B_y$ that ionizes in a stated solvent according to the equilibrium $A_x B_y \rightleftharpoons xA + yB$, at a given temperature and pressure, $K_{sp} = [a_A]^x [a_B]^y$, where $[a_A]$ and $[a_B]$ are the activities of the two ions when the solution is saturated by the solute. In unsaturated solutions the product $[a_A]^x [a_B]^y$ can have any value less than K_{sp}, but if further amounts of either ion are added from whatever source, such that K_{sp} is exceeded, precipitation from solution will occur to the extent that the relationship $[a_A]^x [a_B]^y = K_{sp}$ is restored. In dilute solutions the concentrations C_A and C_B of A and B may be used as a good approximation.

solubilize *or* **solubilise** to bring into solution any material, especially complexes that normally exist in the cell as part of membrane structures. Such materials usually have hydrophobic domains, and solubilization depends on masking these with detergents or similar substances, to bring the material into micellar suspension.

soluble 1 capable of being dissolved in or as if in a fluid. **2** (of, e.g., a problem or mathematical equation) capable of being solved.

soluble collagen *see* **tropocollagen**.

soluble RNA *abbr*.: S-RNA *or* sRNA; *an old term for* **transfer RNA** (a 'soluble' RNA fraction from disrupted liver cells that did not sediment after centrifuging at 100 000 *g* for several hours led to the discovery of transfer RNA).

solute a dissolved substance, particularly a component of a **solution** that is present in a smaller amount than the **solvent**.

solution 1 a homogeneous molecular mixture of two or more substances, usually of dissimilar molecular structures, i.e. of a solid in a liquid. **2** the action or process of solving a problem. **3** the result of solving a problem, equation, etc.

solvation the (loose) combination of solvent with molecules or ions of the solute.

solvation effect the effect of solvent molecules on the behaviour of (especially) macromolecules in solution, especially during centrifugation.

solvent 1 a substance or mixture, usually a liquid, that is able to dissolve other substances to form a solution. Typically it has the same physical state as the solution itself, and is the component of greatest extent in the solution. **2** *(in chromatography)* the liquid used to pass through a chromatography column, paper, or other support to 'develop' the chromatogram.

solvent-perturbation method a technique in which some physical property of a macromolecule is measured in a polar and in a nonpolar solvent. For example, it can be determined whether an amino-acid residue in a protein is internal or external by measuring the absorption spectra of the protein in the two types of solvents. Difference spectroscopy is conveniently applied in such instances.

soma (*pl.* **somata** *or* **somas**) **1** the whole of any plant or animal organism but excluding the germ cells. **2** the body, as opposed to the mind. *See also* **somatic cell**. —**somatic** *adj.*

somat+ *a variant form of* **somato+** (before a vowel).

somatic cell any cell of an organism other than a germ cell.

somatic cell genetic disorder a genetic disorder in which defects are restricted to specific somatic cells, e.g. cancer cells. This contrasts with germ-line genetic disorders – single gene, multifactorial, and chromosome – in which the abnormality is present in all cells, including the germ cells.

somatic cell hybrid a hybrid cell formed from the fusion of different cells, usually from different species. Somatic cell hybrids obtained by the fusion of human and rodent cells are frequently used for gene mapping. *See* **cell fusion**.

somatic cell hypermutation The process in the lifetime of a **B lymphocyte** whereby **mutations** arise in the **immunoglobulin** polypeptides. The rate of mutation is especially high in the region around the **IgG** genes. The mechanism becomes activated as B cells differentiate and is associated with **class switching** and so IgG molecules usually vary more from **germline** sequences than **IgM**.

somatic crossing over *an alternative name for* **mitotic recombination**.

somato+ *or (before a vowel)* **somat+** *comb. for* denoting the body, or soma.

somatocrinin *another name for* growth hormone releasing hormone (**GHRH**).

somatogenic 1 originating in the **soma** (def. 1), or body tissues. **2** of organic, rather than mental, origin.

somatoliberin *the recommended name for* growth hormone releasing hormone (**GHRH**).

somatomammotropin human chorionic somatomammotropin; *see* **choriomammotropin**.

somatomedin *generic name for* **insulin-like growth factors** (*abbr*.: IGF); in the human they comprise IGF-IA, IGF-IB, and IGF-II. Somatomedins were characterized by: (a) activity on cartilage (incorporation of sulfate and thymidine), (b) insulin-like activity in adipose and muscle, and (c) mitogenic activity in cell culture. Somatomedin A is IGF-II, and somatomedin C is IGF-I (A and B). The term 'somatomedin' should be used only as a generic term, IGF-I (A or B) and IGF-II being used for the specific peptides. Somatomedin B, released from **vitronectin**, is a serum factor of unknown function, is increased in response to **somatotropin**, and is a proteinase inhibitor.

somatostatin *or* **somatotropin-release inhibiting factor** (*abbr*.: SRIF) *or* **growth hormone-release inhibiting hormone** (*abbr*.: GH-RIH); a hypothalamic cyclic 14-residue peptide that inhibits the release of the pituitary growth hormone **somatotropin** and the release of glucagon and insulin from the pancreas of fasted mammals; it also inhibits the release of gastrointestinal hormones and other secretory proteins. **Somatostatin 14** has the sequence Ala-Gly-Cys-Lys-Asn-Phe-Phe-Trp-Lys-Thr-Phe-Thr-Ser-Cys, with a disulfide link between cysteines 3 and 14. In **somatostatin 28** the 14-residue peptide is extended by the N-terminal residues SANSNPALAPRE-RKAG–. Both forms are derived from the 92 amino-acid precursor, **prosomatostatin**, by tissue-specific proteolytic processing. Somatostatin is widely distributed in the central nervous system and in peripheral tissues such as stomach, intestine, and pancreas. It has effects that are tissue specific, and can function as a neurotransmitter. *See also* **somatostatin receptor**.

somatostatin receptor any G-protein-associated membrane protein that binds different forms of **somatostatin** and mediates their effects. Some receptors act through G_i to decrease intracellular Ca^{2+} concentrations and inhibit the voltage-dependent current, I_{Ca}. Somatostatin 14 enhances and somatostatin 28 reduces potassium current, I_K. In *Rattus norvegicus* the type 1 receptor has higher affinity for somatostatin 14 than 28 and is coupled to phosphotyrosine phosphatase and sodium–hydrogen-ion exchanger. Types 2 and 3 are receptors for somatostatins 14 and 28 and inhibit adenylate cyclase. Type 4 is a receptor for somatostatin 14 and inhibits adenylate cyclase. Type 5 is a receptor for somatostatin 28 and inhibits adenylate cyclase. Hybridization studies indicate these are members of a larger family of somatostatin receptors; they are G-protein-coupled adenylate cyclase activators.

somatotrope *or* **somatotroph** a type of cell found in the lateral wings of the anterior pituitary and comprising about 50% of the hormone-producing cells of that part of the gland. Somatotropes are responsible for the production of **somatotropin, and their** adenomas cause **acromegaly**.

somatotroph *see* **somatotrope**.

somatotrophic **1** stimulating and maintaining the growth and development of any cell or tissue. **2** *(sometimes)* of or pertaining to **somatotropin**.

somatotropic **1** of, or relating to, **somatotropin**. **2** stimulating the mechanisms connected with growth or development of a cell or tissue. *Compare* **somatotrophic**.

somatotropic hormone *see* **somatotropin**.

somatotropin *or* **growth hormone** (*abbr*.: GH); *also called* **somatotropic hormone** (*abbr.*: STH); a hormone secreted by the anterior pituitary whose main effect is to stimulate growth. The human hormone (hGH) is mostly synthesized as the precursor of a single-chain, 191-residue protein, M_r 22000, but 5–10% is a form of M_r 20000 resulting from alternative splicing that deletes codons for amino acids 32–46 from the mRNA. Genes encoding hGH, **prolactin**, and **choriomammotropin** form a family with high nucleotide homology with five coding exons. Somatotropin secretion is pulsatile, especially during fasting, when cycles of about four hours' duration occur; it is stimulated by fasting or hypoglycemia, and hormonally by glucagon, GHRH, estrogens, and arginine vasopressin, and during the first phase of sleep; secretion is inhibited by hyperglycemia, somatostatin, the insulin-like growth factor IGF-I, and glucocorticoids. It is secreted from storage granules. *In vivo*, somatotropin tends to promote synthesis of protein, and lipolysis or reduced fat deposition, and growth and mitosis of cartilage. Deficiency leads to pituitary dwarfism types I and IV. Its actions *in vitro* include stimulation of amino-acid uptake in muscle, and lipolysis in adipose tissue, but many of its actions *in vivo* may depend on its action in stimulating synthesis and secretion of **somatomedins**. hGH has 85% homology with human choriomammotropin and 35% homology with human prolactin. *See also* **GHRH**, **GHRH receptor**, **hypopituitarism**.

somatotropin-release inhibiting factor *abbr*.: SRIF; *an alternative name for* **somatostatin**.

somatrem methionyl human **somatotropin** (growth hormone); somatotropin with an additional N-terminal methionine. It results from the production of somatotropin using cDNA technology in bacterial clones; methionine is involved in the initiation of bacterial protein synthesis.

+some *comb. form* denoting body, esp. intracellular particle.

somite any of a series of paired blocks of mesoderm that form during early development in vertebrate embryos and lie on either side of the notochord. —**somital** *or* **somitic** *adj.*

sonicate to expose any material or sample to ultrasonic pressure waves (at or around 20 kHz). The immersion of vessels in a water bath and their exposure to ultrasound is used as a means of cleaning (*see* **sonication bath**). The insertion of a **sonicator** probe into a vessel containing a suspension of membranes or other large assemblies causes their dispersion to smaller aggregates or assemblies.

sonication bath a water bath that is equipped with an oscillator, sited beneath the bowl, to produce ultrasound waves that permeate the water. It may be used for cleaning glass or other vessels or for degassing solvents.

sonicator a device that produces **ultrasonic** pressure waves. It usually consists of a stainless-steel rod, of diameter from 1–2 mm to about 2 cm, that is activated by an oscillator to produce ultrasound waves and is inserted into a vessel to **sonicate** a sample. *See also* **sonication bath**.

sonic hedgehog proteins analogues of **hedgehog protein** found in **zebrafish** and chickens, and involved (in the latter case) in limb-bud pattern formation. The hedgehog proteins thus appear to be vital to pattern formation in several metazoan groups. The name sonic hedgehog is an allusion to a children's animated cartoon character.

sophorose the disaccharide 2-*O*-*β*-D-glucopyranosyl-D-glucose; it occurs in a glycoside of *Sophora japonica*.



sorbin a heat-stable peptide isolated from porcine intestine that increases water and sodium absorption in the intestine and gall-bladder.

sorbitol *a nonsystematic name for* D-glucitol, one of the ten stereoisomeric hexitols. It can be derived from glucose chemically or metabolically (by NADPH-requiring aldehyde reductase; *other name*: aldose reductase, EC 1.1.1.21) by reduction of the aldehyde group, and is converted to D-fructose by L-iditol 2-dehydrogenase (EC 1.1.1.14). It is widely distributed in algae and higher plants, and was first discovered (1872) in the juice of berries from mountain ash (*Sorbus aucuparia*). It about half as sweet as sucrose, and is often used in sweeteners in conjunction with saccharin. Industrially it is of great importance in the food, pharmaceutical, paper, and textile industries. Its formation from excessive glucose concentrations in diabetics may have pathological implications in lens tissue, which cannot convert it to fructose.

sorbose *a trivial name for* the ketohexose *xylo*-2-hexulose; the enantiomer, L-sorbose, is present in fermented juice of mountain-ash berries, being formed by the bacterial oxidation of **sorbitol**. It is produced by fermentation and used in the manufacture of **ascorbic acid**.

sorcin a protein, encoded in multidrug-resistant cells (*see* **MDR**), that binds calcium with high affinity. *See also* **grancalcin**.

Soret band an absorption band at about 400 nm, characteristic of porphyrins. *See also* **cytochrome absorption bands**. [After Louis Soret (1827–90), Swiss physicist.]

sorocarp *see* ***Dictyostelium discoideum***.

sos *symbol for son of sevenless*, a gene for a guanine-nucleotide releasing protein involved in neuronal development in *Drosophila*. When bound to the activated Sev receptor (*see* **Sevenless protein**) the *sos* product, Sos, activates *ras* by stimulating release of GDP, thereby promoting uptake of GTP.

SOS repair *or* **error-prone repair** a metabolic alarm system, occurring in bacteria, that helps the cell to save itself in the presence of potentially lethal stresses such as UV irradiation, thymine starvation, or the inactivation of genes essential for replication. Responses include mutagenesis, filamentation (cell elongation in the absence of division), activated excision repair, and activation of latent phage genomes. Mutagenesis occurs because under SOS conditions the gaps formed opposite **thymine dimers** can be filled by replication rather than by daughter-strand transfer. Replication of the dimer template is extremely inaccurate. The proteins involved include RecA protein (*see* ***recA***) and the products of two other RecA-inducible genes; expression is regulated by the ***lexA*** gene product.

SOURCE *abbr. for* Stanford Online Universal Resource for Clones and Ests; a unified genomic resource for functional annotations, ontologies, and gene expression data.

Southern blotting a procedure for transferring denatured DNA from an agarose gel to a solid support membrane such as nitrocellulose or nylon. It depends on tenacious binding by nitrocellulose of single-stranded (ss) DNA but not of double-stranded (ds) DNA. The gel is soaked in 0.5 m NaOH, which converts the dsDNA to ssDNA. The gel is then overlaid with a sheet of nitrocellulose paper, which in turn is covered by a thick layer of paper towels and the entire assembly is compressed by a heavy weight. The liquid in the gel is forced (blotted) through the nitrocellulose so that the single-stranded DNA binds to it at the same position it had in the gel. The transfer to nitrocellulose can also be accomplished by **electrophoretic transfer**. Nylon is used in preference to nitrocellulose. DNA bands may be located using a radioactive or otherwise labelled probe. The name led to a nomenclature for other types of **blotting** (*see also* **Northern blotting**, **South-western blotting**, **Western blotting**). [After E. M. Southern (1938–), British molecular biologist.]

South-western blotting a technique in recombinant DNA technology for detecting plaques expressing **fusion proteins** where part of the sequence is for a protein that binds to a particular DNA sequence. After treatment of the plaques to ensure release of the protein, **plaque-lift** is carried out onto a nitrocellulose (or other) **transfer membrane**, which is then incubated with a radiolabelled duplex DNA oligonucleotide that binds to the protein, which can then be detected by **autoradiography**. The term was derived by extension through the cardinal points from **Southern blotting**.

Soviet gramicidin *an alternative name for* **gramicidin S**.

SOX *abbr. for* SRYHMG-box gene; any of a family of genes encoding transcription factors that are related to SRY and contain HMG-type DNA-binding domains. SOX1 and SOX2 proteins are crucial for activating crystallin genes in the lens but are expressed in many tissues. SOX9 protein (509 amino acids) is widely expressed in fetal and adult tissues and is essential for formation of cartilage and testes. Many mutations result in campomelic dysplasia. *SOX10* is expressed in melanocytes and neural crest derivatives during development, and mutations result in Waardenburg syndrome type 4.

Soxhlet extractor an apparatus for exhaustive extraction of soluble components from a sample of solid material by recycling a solvent through it, whereby solvent vapour from a boiler is continually condensed and the condensate allowed to percolate through the sample in a solvent-permeable thimble, from which it is returned, usually periodically via a siphon, to the boiler, where the eluted substances accumulate. [After Franz Soxhlet (1848–1926), Belgian chemist, who devised it.]

soybean *or (esp. Brit.)* **soya bean** a leguminous plant, *Glycine max*, originating in China (known from at least 2500 BC) but cultivated widely in Asia, Europe, and America for forage and for its seeds. The bean has an oil content of 18–22%, and is also rich in protein — soybean protein is a human food and is the basis of tofu. *See also* **soybean oil**, **soybean trypsin inhibitor**.

soybean oil an edible oil obtained from the seeds of the soybean plant and valued for its high content of linoleic acid. The composition is typically as follows: 18:2 ω6, 44–62%; 18:3 ω3, 4–11%; 18:1 ω9, 19–30%; 16:0, 7–14%.

soybean trypsin inhibitor *abbr.*: STI; either of two types of trypsin inhibitor, the Bowman–Birk and the Kunitz inhibitors, which have given their names to classes of proteinase inhibitor. The two soybean inhibitors differ from each other in size, structure, and properties. The **Bowman–Birk inhibitor** contains 71 amino acids and seven disulfide bonds. There are two active sites, one specific for trypsin and the other for chymotrypsin. Bowman–Birk inhibitors are found in many cereals and legumes, and may represent storage proteins. **Kunitz inhibitors** comprise three allelic proteins, A, B, and C, and two Kunitz-type inhibitors, named KTI1 and KTI2. The A, B, and C proteins have 181 amino acids and two disulfide bonds. They are heat-stable, resistant to proteases, and form a 1:1 stoichiometric complex with trypsin that is highly stable (K_a 5×10^9). They weakly inhibit chymotrypsin and are inactive against other endopeptidases, but modification of Arg^{63} to Trp converts them to strong chymotrypsin inhibitors with little action on trypsin. The Kunitz family embraces trypsin, chymotrypsin, cathepsin D, and subtilisin inhibitors (*see* **Kunitz inhibitor**).

sp *abbr. for* synperiplanar; *see* **conformation**.

sp. (*pl.* **spp.**) *abbr. for* species (singular).

sp-300 a protein (8204 amino acids) of *Drosophila* that has the same general structure as **ANC-1** of *Caenorhabditis elegans* and the Syne proteins of mammals. It contains multiple spectrin repeats and a nuclear envelope localization domain, and structurally consists mostly of coiled coil.

Sp *abbr. for* isomer of a thionucleotide.

Sp1 *abbr. for* specificity protein 1; a transcriptional activator protein of humans that targets genes by binding to GC-rich sequences in certain promoters. It contains glutamine-rich activation domains that bind components of transcription factor TFIID, including the glutamine-rich component TAFII 130. It interacts with human mutant huntingtin, which carries an expanded glutamine repeat.

SP *abbr. for* **1** secretory piece. **2** substance P. **3** spasmolytic polypeptide.

SP-1 *abbr. for* secretory protein 1.

S1P *abbr. for* site-1 protease; a transmembrane serine protease of the subtilisin family. It occurs in the Golgi apparatus, with its catalytic domain in contact with the lumenal loop of **SREBP**. S1P is inhibited by binding of sterol to **SCAP**, and cleaves SREBP into its transcriptional and regulatory domains. Release of the transcriptional domain for entry into the nucleus needs a cleavage by **S2P**.

S2P *abbr. for* site-2 protease; a highly hydrophobic zinc metalloprotease of the Golgi apparatus that releases the transcriptional domain of **SREBP** after **S1P** has separated it from the regulatory domain.

[S]pA *symbol for* adenosine 5′-thiophosphate (alternative to Ado*P*[S].

space *or* **volume of distribution** (*in tracer kinetics*) an apparent volume obtained as the amount of radioactivity retained divided by the concentration of the tracer in the plasma. *See* **apparent exchangeable mass, compartment**.

spacer 1 *(in molecular biology)* a sequence of bases of unknown function occurring in DNA and lying between sequences of transcribed DNA; spacer DNA is not usually transcribed. The term also refers to some stretches of **primary transcript**, e.g. a region in the mammalian primary transcript for rRNA, lying between 18S RNA and 28S RNA, that is not found in mature rRNA. **2** *(in chromatography) an alternative term for* **spacer arm**.

spacer arm *or* **spacer** the (usually) hydrocarbon chain interposed between the specific ligand and the supporting matrix in **affinity chromatography**.

spacer gel *(in electrophoresis)* a small section of gel, polymerized above a polyacrylamide (or other) resolving gel, that lacks resolving power and serves to concentrate the material being electrophoresed as a tight band at the top of the resolving gel.

Spalt a transcription factor protein (1355 amino acids) that contains nine zinc fingers. In mouse it is expressed in the central nervous system, limb buds, palate, teeth, kidneys, and genitals. In *Drosophila* it is involved in wing imaginal disc formation.

SPARC *abbr. for* secreted protein acidic and rich in cysteine; *also called* **osteonectin**; an abundant non-collagenous protein of bone and cartilage secreted by osteoblasts but widely expressed in cells of tissues undergoing morphogenesis or wound repair and secreted into the basement membrane, where it interacts with other proteins, e.g. collagen and thrombospondin, and appears to have a role in regulating cell growth. It contains an **EF-hand** that binds one calcium ion and an acidic region that binds other calcium ions more loosely.

spare receptor any of the receptors in excess of those required to evoke a given response to a drug, hormone, or other agonist. The size of the population of spare receptors (**receptor reserve**) can vary with the tissue and with the magnitude of the response being measured. For different drugs, the receptor reserve varies with drug efficacy.

sparging the bubbling of gas into a liquid medium. This technique may be applied to fermenters to introduce air directly into a culture, or it may be used to replace one dissolved gas by another, e.g. in displacing oxygen with an inert gas in liquid chromatography solvents.

sparse matrix *(in sequence analysis)* a **scoring matrix** in which most of the elements or cells have zero score. Sparse matrices perform with high selectivity.

sparsomycin an antibiotic inhibitor of peptidyltransferase activity of prokaryotic ribosomes.

spasmolytic polypeptide *abbr.*: SP. *See* **trefoil factor**.

spastic ataxia of Charlevoix-Saguenay *abbr.*: SACS; an autosomal recessive early-onset neurodegenerative disease with a high prevalence in the Charlevoix-Saguenay region of Quebec, Canada. It is caused by mutations in the gene (locus at 13q12) for **sacsin**, which contains a single exon encoding 4265 amino acids.

spatula a small, flattened or curved utensil made of metal (often stainless steel), bone, or wood and used to dispense crystalline or powdered material.

Spd *abbr. for* sphingoid.

specialist database *or* **boutique database** a database that maintains a specialist data set, dedicated, for example, to a specific gene family, molecular or macromolecular property, disease or diseases. For example, GCRDB (G Protein-Coupled Receptor Database) and MEROPS house information relating specifically to the superfamily of G protein-coupled receptors and to peptidases, respectively; BRENDA stores information pertaining to enzymes; DIP houses information on experimentally determined protein–protein interactions; PDBsum (Protein Data Bank summary) summarizes information relating to protein structures in the PDB (Protein Data Bank); OMIM (Online Mendelian Inheritance in Man) contains information on human genes and genetic disorders.

speciation 1 the evolutionary process by which divergent species of animals or plants are formed from a common ancestral stock. **2** the chemical form or compound in which an element occurs in both non-living and living systems. It may also refer to the quantitative distribution of an element.

species (*pl.* **species**) *abbr.*: sp. (*sing.*) *or* spp. (*pl.*); a fundamental taxonomic category ranking below a genus and consisting of a group of closely related individuals that can interbreed freely to produce fertile offspring.

species-specific confined to the one or several species referred to.

specific 1 relating to a particular or specified thing. **2** (as a modifier of certain quantitative terms) indicating a relationship of the quantity to mass and dimension in terms of standard (now normally SI) units; e.g. **specific catalytic activity**, **specific enzyme activity**, **specific optical rotation**. **3** of, or relating to, a **species**. *See also* **specificity**.

specific acid catalysis a **homogeneous catalysis** in which the catalysts are free hydrons, H^+ (or hydronium ions, H_3O^+). The catalysis is not affected by other acidic species present. *Compare* **general acid-catalysis**.

specific activity the **activity** (def. 1, 2) of, e.g., a radionuclide or an enzyme, expressed as a function of mass.

specifically labelled describing an isotopically labelled compound in which both the position of labelling and the number of labelling nuclides at that position are known. Such a molecule is designated by a convention exemplified by $CH[^2H_2]–CH_2–O[^2H]$.

specific base catalysis a **homogeneous catalysis** in which the catalysts are hydroxide ions, $OH^–$. The catalysis is not affected by other basic species present. *Compare* **general base-catalysis**.

specific catalytic activity the **catalytic activity** of an enzyme under specified conditions divided by the mass of an enzyme or enzyme preparation. It is a quantity useful for denoting the extent of purification of an enzyme; it may be expressed in katals per kilogram.

specific dynamic action the increase in heat production that occurs in animals after the ingestion of food, particularly of protein.

specific enzymic activity the phenomenological coefficient that relates **enzymic activity** under specified conditions to the mass of an enzyme or enzyme preparation. It may be expressed in katals per kilogram of protein. Now obsolete, it has been superseded by **specific catalytic activity**. *Compare* **molar enzymic activity**.

specific gravity *a former name for* **relative density**.

specific heat capacity *symbol*: c_p (at constant pressure) *or* c_v (at constant volume); the quantity of **heat** required to raise the **temperature** of unit mass of a substance by one degree. It is expressed (usually) in J K^{-1} kg^{-1}.

specificity the degree to which an association between two molecular units may be considered unique; in many applications it is judged by the magnitude of an effect (enzyme–substrate, ligand–receptor interaction, or drug action). It is measured under defined conditions, in relation to the magnitude of effect of other substances with similar action, and when the substance is in direct competition with other such substances. The competitive success of other substances is normally quantified by kinetic analysis. *See* **competitive inhibition, specificity constant**.

specificity constant the ratio of the catalytic constant, k_{cat}, to the Michaelis constant, K_m. It can aid in comparing the activity of an enzyme in its action on different substrates. From **Michaelis kinetics**, using the Michaelis–Menten equation,

$$v = (k_{cat}/K_m)[E]_o[S]$$

when [S] is very small (since then, little enzyme has bound substrate, so $[E] \approx [E]_o$, and [S] can be neglected in relation to K_m). Thus for substrate A,

$$v_a = (k_{cat}/K_m)_A[E]_o[A],$$

and for substrate B,

$$v_b = (k_{cat}/K_m)_B[E]_o[B].$$

So

$$v_a/v_b = (k_{cat}/K_m)_A{\times}[A] \,/\, (k_{cat}/K_m)_B{\times}[B],$$

and, at the same substrate concentrations, the activity of the enzyme against the different substrates reduces to a comparison of the respective specificity constants (k_{cat}/K_m); K_m is not of itself a sufficient index of specificity.

specific optical rotation *symbol* $[\alpha]^{\theta}_{\lambda}$; the optical rotation of light of a specified wavelength (or frequency) achieved by a solution at a specified temperature. It is given by the relation $[\alpha]^{\theta}{}_{\lambda} = \alpha/l\,\rho$ where α is the observed rotation in degrees, l is the length of the sample tube (in dm), ρ is the density of the liquid (in gml^{-1}), λ is the wavelength of the light (or other electromagnetic radiation) used, and θ is the Celsius temperature. For a solution of concentration c (in g solute per 100 ml solution), $[\alpha]^{\theta}{}_{\lambda} = \alpha/lc$ in degrees dm^2 g^{-1}. *Compare* **molecular optical rotation**.

specific refractivity *see* **refractivity**.

specific viscosity *symbol*: η_{sp}; the fractional change in **viscosity** produced by adding a solute to a solvent. It is given by the equation:

$$\eta_{sp} = (\eta / \eta_0) - 1 = Avc + Bv^2c^2 + Cv^3c^3 + ...$$

where η_0 is the viscosity of the solvent, η is the intrinsic viscosity of the solution, A, B, and C are shape-dependent constants, c is the concentration of the solute, and v is the specific volume of one solute molecule.

specific volume *symbol*: v; for a pure substance, the volume, V, of a sample, divided by the mass, m, of the sample; $v = V/m = 1/\rho$, where ρ is the **mass density** of the substance. The SI unit is m^3 kg^{-1}. *See also* **partial specific volume**.

'specifier' protein a protein that, when it combines with an enzyme or enzyme–substrate, modifies the catalytic specificity of the system. An example is α-lactalbumin, which modifies the substrate (acceptor) specificity of *N*-acetyllactosamine synthase (EC 2.4.1.90; *other name*: UDPgalactose:*N*-acetylglucosamine *β*-D-galactosyltransferase) from *N*-acetylglucosamine to glucose.

spectinomycin an aminocyclitol antibiotic secreted by *Streptomyces spectabilis*. It is widely active against Gram-negative bacteria, including *Neisseria gonorrhoeae*, but less so against Gram-positive bacteria. It inhibits protein synthesis by binding to the 30S ribosomal subunit.



spectra the plural of **spectrum**.

spectrin a protein that is the major constituent of the erythrocyte cytoskeletal network. It associates with band 4.1 (*see* **band protein**) and **actin** to form the cytoskeletal superstructure of the erythrocyte plasma membrane. It is composed of non-homologous chains, α and β, which aggregate side-by-side in an antiparallel fashion to form dimers, tetramers, and higher polymers. Anchorage to the cytoplasmic face of the plasma membrane is mediated by another protein, **ankyrin**, which links β spectrin to transmembrane protein band 3, and by the binding of band 4.1 to **glycophorin**. Interaction between spectrin and other proteins is thought to be responsible for maintenance of the biconcave shape of human erythrocytes, for regulation of plasma membrane components, and for maintenance of the lipid asymmetry of the plasma membrane.

spectrin repeat *see* **spectrin**.

spectrofluorometer an instrument used for measuring the **fluorescence** emitted by compounds excited by incident radiation produced within the instrument. The excitation radiation is produced by a lamp, and filters or diffraction grating monochromators are employed to isolate both the incident and emitted radiation to narrow wavebands. The emitted radiation is detected by photomultipliers.

spectrogram a photographic record of a **spectrum** produced by a **spectrograph**.

spectrograph a **spectrometer** or **spectroscope** with a facility for producing a photographic record of the spectrum under consideration. *Compare* **spectroscope**. —**spectrographic** *adj.*; **spectrographically** *adv.*; **spectrography** *n.*

spectrometer any instrument used to produce and examine a **spectrum**, such as a **spectrophotometer** or a **spectroscope**. —**spectrometric** *adj.*; **spectrometry** *n.*

spectrophotometer an apparatus to measure the proportion of the incident light (or other electromagnetic radiation) absorbed (or transmitted) by a substance or solution at each wavelength of the spectrum. —**spectrophotometric** *adj.*; **spectrophotometry** *n.*

spectroscope an instrument for studying spectra, either qualitatively or quantitatively. —**spectroscopic** *or* **spectroscopical** *adj.*; **spectroscopically** *adv.*

spectroscopy the investigation of the chemical composition, molecular structure, or atomic structure of a substance or solution by observation of its interaction with electromagnetic radiation using a spectroscope.

spectrum (*pl.* **spectra**) *(in physics)* an arrangement of the components of a complex electromagnetic radiation (light, etc.) or sound in order of frequency or energy, thereby showing a distribution of energy among the components. —**spectral** *adj.*

Spemann's organizer an embryonic signalling centre located in the dorsal lip of the blastopore. It plays a crucial role in the organization of the formation of the main body axis of a developing embryo. [After Hans Spemann (1869–1941), German zoologist and embryologist.]

spermaceti *or* **cetaceum** a white, translucent, waxy solid, m.p. 42–50°C, consisting mainly of the ester cetyl palmitate and obtained from oil in the head of the sperm whale (*Physeter catodon*) and related cetaceans. It is used in the manufacture of cosmetics, ointments, soaps, etc.

spermadhesin *or* **AQN1** a secretory protein of male accessory glands that is found on the sperm surface, and mediates sperm binding to the zona pellucida.

spermatogenesis the formation of spermatozoa in the male reproductive system. The sperms are formed from male germ cells, **spermatogonia**, which line the inner wall of the seminiferous tubules in the testis. A single spermatogonium divides by mitosis to form **primary spermatocytes**, each of which undergoes the initial division of meiosis to form two **secondary spermatocytes**. Each of these then undergoes the second meiotic division to form two **spermatids**, which mature into spermatozoa without further cell division by a process called **spermiogenesis**. All these cell types are nourished and supported by neighbouring **Sertoli cells**. Spermatogenesis also requires the presence of testosterone-secreting **Leydig cells**.

spermatogenesis factor *see* **dysferlin**.

spermidine *N*-(3-aminopropyl)-1,4-diaminobutane; $NH_2(CH_2)_3NH(CH_2)_4NH_2$; one of the polyamines.

spermidine synthase EC 2.5.1.16; *other names*: putrescine aminopropyltransferase; aminopropyl-transferase; an enzyme that catalyses the formation of **spermidine** and 5′-methylthioadenosine from *S*-adenosylmethioninamine and putrescine.

spermine *N*,*N*-bis(3-aminopropyl)-1,4-diaminobutane; $NH_2(CH_2)_3NH(CH_2)_4NH(CH_2)_3NH_2$; one of the polyamines.

spermine synthase EC 2.5.1.22; *other name*: spermidine aminopropyltransferase; an enzyme that catalyses the formation of **spermine** and 5′-methylthioadenosine from *S*-adenosylmethioninamine and spermidine.

sperm tail *see* **cilium**.

SPF *abbr. for* specific-pathogen-free.

Sph *symbol for* sphingosine.

S phase the phase of the eukaryotic cell cycle in which DNA is synthesized. *See* **cell-division cycle**.

spherocyte a red blood cell that has lost its normal biconcave shape owing to damage to the surface membrane or to some disorder of metabolism. Spherocytes appear smaller and darker than normal red cells.

spherocytosis the condition of having **spherocytes** in the blood. Hereditary spherocytosis in humans is a chronic hemolytic anemia that results from defects in ankyrin, band 3 protein, α spectrin, β spectrin, or 4.2 protein.

spheroid **1** a solid figure that is similar to but not identical with a sphere. **2** an **ellipsoid of rotation**, especially one in which the major axis of its parent ellipse is only slightly longer than its minor axis. —**spheroidal** *adj.*

spheroplast the globular form of a bacterial cell in which the cell-wall structure has been modified (e.g. by growth in the presence of penicillin) rather than totally removed. The term also denotes a form of yeast cell obtained by partial hydrolysis of the cell wall. A prefix may be used to indicate the method of induction, e.g. penicillin-spheroplast. *Compare* **protoplast**.

spherosome an organelle, generally spherical or oblate and 0.4–3 µm in diameter, that occurs in lipid-storage tissues in plants, e.g. endosperm of castor-bean seeds. Spherosomes are enclosed within a phospholipid monolayer (a half-unit membrane) with embedded oleosins and other proteins, and contain triacylglycerols formed by enzymes in the endoplasmic reticulum (ER) and partitioned into the interior of the ER membrane at sites defined by the presence of oleosins.

sphinganine D-*erythro*-2-amino-1,3-octadecanediol; D-*erythro*-dihydrosphingosine; the metabolic precursor of **sphingosine**. It is formed from palmitoyl-CoA and serine by the action of **serine *C*-palmitoyltransferase**, which forms 3-dehydro-D-sphinganine, which is then reduced to sphinganine by 3-dehydrosphinganine reductase, EC 1.1.1.102. *See also* **sphingolipids**, **sphingoid**.

sphingoid *or* **sphingoid base** *symbol*: Spd; any of a class of compounds comprising **sphinganine**, and its homologues and stereoisomers, and derivatives of these compounds.

sphingolipid any lipid that contains the long-chain amino diol, **sphingosine**, or a closely related base (i.e. a **sphingoid**). A fatty acid is bound in an amide linkage to the amino group and the terminal hydroxyl may be linked to a phosphate ester or a carbohydrate. The predominant base in animals is sphingosine while in plants it is **phytosphingosine**. The main classes are: (1) phosphosphingolipids (also known as sphingophospholipids), of which the main representative is **sphingomyelin**; and (2) **glycosphingolipids**, which contain at least one monosaccharide and a sphingoid, and include the **cerebrosides**

and **gangliosides**. Sphingolipids have a structural role in cell membranes, and may be involved in the regulation of protein kinase C.

sphingolipid activator proteins *see* **saposins**.

sphingolipidosis (*pl.* **sphingolipidoses**) any inherited pathological condition in humans in which one or more sphingolipids accumulate in the tissues because of a deficiency of the corresponding degradative enzyme. They include **ceramidase** deficiency, **Fabry's disease**, **galactosylceramide lipidosis**, G_{M1} and G_{M2} **gangliosidoses, Gaucher's disease**, **metachromatic leukodystrophy**, and **sphingomyelin lipidosis**.

sphingomyelin *N*-acyl-4-sphingenyl-1-*O*-phosphorylcholine; any of a class of phospholipids in which the amino group of **sphingosine** is in amide linkage with one of several fatty acids, mostly C_{20} or higher and either saturated or monounsaturated, while the terminal hydroxyl group of sphingosine is esterified to phosphorylcholine. Sphingomyelins are found in large amounts in brain and other nervous tissue. They do not occur in plants.

sphingomyelinase *see* **sphingomyelin phosphodiesterase**.

sphingomyelin lipidosis *or* **Niemann–Pick disease** a genetic disease of humans in which **sphingomyelin** accumulates in the tissues due to a deficiency of the enzyme **sphingomyelin phosphodiesterase**. It is associated with mental retardation.

sphingomyelin phosphodiesterase EC 3.1.4.12; *other names*: acid sphingomyelinase; neutral sphingomyelinase; a lysosomal enzyme that catalyses the hydrolysis of sphingomyelin to *N*-acylsphingosine and choline phosphate. Deficiency of the enzyme is the cause of Niemann–Pick disease (**sphingomyelin lipidosis**), in which there is an accumulation of sphingomyelin.

sphingophospholipid *see* **sphingolipid**.

sphingosine *symbol*: Sph; *trans*-D-*erythro*-2-amino-4-octadecene-1,3-diol; $CH_3(CH_2)_{12}CH{=}CH{-}CHOH{-}CHNH_2{-}CH_2OH$; a long-chain amino diol sphingoid base that occurs in most **sphingolipids** of animal tissues. *See also* **phytosphingosine**.

sphingosine *N*-acyltransferase EC 2.3.1.24; an enzyme of the pathway for synthesis of sphingolipids that catalyses the acylation of sphingosine by acyl-CoA to form *N*-acylsphingosine (ceramide) and CoA.

spicule a roughly cone-shaped structure or tissue element, such as that projecting from the membrane of a red blood cell. Calcareous or siliceous spicules are found in the skeletons of sponges and corals.

spin *(in physics)* **1** the quantized angular momentum of an elementary particle, in the absence of orbital motion. **2** the quantized angular momentum of an atomic nucleus, including contributions from the orbital motions of nucleons. **3** the quantized angular momentum of an electron that adds to the orbital angular momentum, thus producing fine structure in line spectra.

spinal and bulbar muscular atrophy (*abbr.*: SBMA) *or* **Kennedy's disease** an X-linked progressive neuromuscular disorder that results in proximal muscle weakness, muscle atrophy, and involuntary contractions or fasciculations. It is caused by expansion of a CAG trinucleotide repeat in the androgen receptor gene. [After William Kennedy, US neurologist.]

spinal cord the part of the central nervous system that is enclosed in the vertebral column. It connects the innervation of most parts of the body via the spinal nerves to the brain.

spinal muscular atrophy an autosomal recessive disorder in which degeneration of lower motor neurons leads to progressive atrophy of limb and trunk musculature. It is caused by mutations in a neuronal apoptosis inhibitory protein. *See* **IAP**.

spinal nerves the pairs of nerves that arise from the spinal cord and are distributed to various peripheral parts of the body. In humans there are 31 pairs.

spin column chromatography *or* **spun column chromatography** a small-scale chromatography procedure in which fluid is moved through the column by centrifugal force. It has the advantage that several columns can be run simultaneously in the centrifuge rotor.

spin coupling *or* **spin–spin coupling** (*in magnetic resonance spectroscopy*) the influence of a nuclear or electron spin on another. In NMR the nuclear spin of one nucleus is coupled via the bonding electrons to the coupled nucleus, which experiences two different microenvironments and thus resonates at two slightly different frequencies. This results in the splitting (**spin–spin splitting**) of the resonance line into two lines (a doublet). In EPR spectroscopy the electron-nuclear coupling is known as **hyperfine coupling**. Electron–electron couplings can also occur, and lead to splitting or broadening of the EPR spectrum.

spin density the fraction of unpaired electron spin that is in the vicinity of a given atomic nucleus in a molecule.

spindle the array of microtubules and associated molecules that forms between the opposite poles of a eukaryotic cell during mitosis or meiosis and serves to move the duplicated chromosomes apart. During mitosis the spindle starts to form outside the nucleus while the chromosomes are condensing during prophase. At the start of M phase, the two **centrosomes** that have been formed move to opposite sides of the nucleus, and form the two poles of the mitotic spindle. Microtubules grow away from the centrosomes towards the chromosomes, the minus ends being attached to the centrosome, and the plus ends growing towards the **kinetochore**. These microtubules eventually bind to kinetochores and are thus known as kinetochore microtubules. Other microtubules, known as polar microtubules, grow towards the chromosomal region, but eventually bind directly to other polar microtubules growing from the opposite centrosome. these push the poles of the spindle apart. Each centrosome eventually becomes attached through the kinetochore microtubules to one of the sister chromatids of each chromosome, and pulls these away to effect the chromatid separation that occurs at anaphase. A similar series of events occurs at the corresponding phases of meiosis.

spin hamiltonian a formulation in **quantum mechanics** used in the determination of the energy levels of the spin of an electron or a nucleus in **electron spin resonance spectroscopy** or, less commonly, in **nuclear magnetic resonance spectroscopy**. *See also* **Hamiltonian operator**.

spin immunoassay *or* **free-radical assay technique (of immunoassay)** (*abbr.*: FRAT) a technique in which a **spin label** is attached to a specimen of the substance to be assayed and an antibody is raised against the substance. On mixing the antibody with the labelled substance there is a change in the electron spin resonance (ESR) spectrum because of the inhibition of tumbling caused by the antibody 'immobilizing' the labelled substance. On adding some of the unlabelled substance there is competition for the antibody, and the changes in the ESR spectrum are partially reversed to an extent dependent on the concentration of the added, unlabelled, substance.

spin label **1** a synthetic paramagnetic organic free radical, usually having a molecular structure and/or chemical reactivity that facilitates its attachment or incorporation at some particular target site in a macromolecule, or assemblage of macromolecules. **2 spin-label** to effect labelling of a substance or structure with a spin label (def. 1).

spin-lattice relaxation time *or* **longitudinal relaxation time** *(in magnetic resonance spectroscopy) symbol*: T_1; the time taken for the upper nuclear or electron spin state to dissipate its excess energy. Its reciprocal is the spin-lattice relaxation rate (*see* **correlation time**).

spinner culture a method of culturing cells that uses the rotation of an impeller to maintain cells in suspension.

spinocerebellar ataxia *abbr.*: SCA; any of a heterogeneous group (SCA1 to SCA10) of neurological disorders caused by variable degrees of degeneration of the cerebellum, brainstem neurons, and spinocerebellar tracts. Most subtypes result from expansion of the number of translated or untranslated CAG trinucleotide repeats in a gene for an ataxin, atrophin-1, or the α1A subunit of a neuronal Ca^{2+} channel. *See* **hemiplegic migraine**.

spin polarization *or* **spin polarisation** a phenomenon in which the unpaired electron spin on one atom or part of a molecule is transferred to another atom, brought about by interaction between the unpaired electron on the first atom and the paired electrons on the second atom (which lacks unpaired electrons) causing one of the paired electrons to have a lower energy than the other. *See also* **chemically induced dynamic nuclear polarization**.

spin probe *see* **electron paramagnetic resonance spectroscopy**.

spin–spin broadening an increase in line width in **electron spin resonance spectroscopy**, caused by interactions between neighbouring dipoles.

spin–spin coupling *see* **spin coupling**.

spin–spin coupling constant *(in nuclear magnetic resonance spec-*

troscopy) a measure of the specific interaction of one nucleus with another that gives rise to a splitting of the resonance bands produced by each nucleus.

spin–spin splitting splitting in the lines of a magnetic resonance spectrum brought about by the interaction of the magnetic moment of the nucleus or unpaired electron in a molecule with those of neighbouring nuclei or electrons. It is used in the assignment of particular nuclear resonances and in the determination of molecular conformations. *See also* **hyperfine splitting**.

spin state the orientation, in a strong magnetic field, of an unpaired electron or nuclear spin, e.g. parallel or antiparallel to the field direction.

spin trapping a technique in which a reactive free radical is trapped by an addition reaction to produce a more stable radical, detectable by **electron spin resonance spectroscopy**, whose hyperfine coupling parameters permit identification of the initial radical trapped.

spiro compound any compound containing two rings joined by one common atom, designated the **spiro atom**, as in the case of the γ-lactone ring of **spironolactone**.

spironolactone 7-(acetylthio)-17-hydroxy-3-oxo-pregn-4-ene-21-carboxylic acid γ-lactone; a synthetic steroid lactone that is used as a diuretic. It is structurally similar to **aldosterone**, and competitively inhibits the renal tubular action of this hormone. It is metabolized to canrenone, the active compound, by removal of the acetylthio group and insertion of a 6,7 double bond.



spleen exonuclease *see* **phosphodiesterase II**.

spleen tyrosine kinase *see* **Syk**.

splenin *see* **thymopoietin**.

splenopentin a synthetic peptide that corresponds to residues 32–36 of splenin (*see* **thymopoietin**).

spliceosome a **ribonucleoprotein** complex, containing RNA and **small nuclear ribonucleoproteins** (snRNPs) that is assembled during the **splicing** of the messenger RNA **primary transcript** to excise an **intron**. snRNPs designated U1, U2, U4, U5, and U6 are variously involved; U1 may bind the GU consensus sequence of the 5′ **splice site** and U5 with U4/U6 probably binds to the 3′ splice site consensus sequence, AG. U2 may be part of a component binding the UACUA[A]C consensus sequence ([A] is invariant) at a site slightly upstream from the 3′ splice site, known as the branch site. The mechanism appears to involve cutting at the 5′ side of the GU consensus sequence, which curls back to form a G5′–2′A bond with the invariant A of UACUA[A]C. This linkage generates the loop of the so-called **lariat**. Cutting out the 3′ splice site follows on the 3′ side of AG to release the complete intron (in the form of the lariat), and the cut ends of the exons are then ligated.

splice site the sequence of bases at each end of an **intron** that determines the point of **splicing**. The 5′ splice site (site at the 5′ end of the intron) is termed the donor site, consensus sequence GU, while the 3′ splice site is termed the acceptor, consensus sequence AG.

splice variant *or* **alternatively spliced form** any of various proteins of different length that arise through translation of mRNAs that have not included all available exons in the template DNA.

splicing 1 (*of DNA*) the covalent linkage, by the action of a **DNA ligase** (EC 6.5.1.1, requires ATP, or EC 6.5.1.2, requires NAD$^+$), of two fragments of duplex DNA at complementary single-stranded terminations. **2** (*of RNA*) the enzymic process in eukaryotic cells by which **introns** are excised from heterogeneous nuclear RNA (hnRNA) following its transcription from DNA, and the cut ends are rejoined to form messenger RNA (mRNA), in which the message is continuous, before its translation into polypeptide. In yeast, the splicing of transfer RNA involves cutting at the splicing junctions by an endonuclease, followed by a process involving ATP, whereby the two exon sequences are joined. Group I mitochondrial RNA is spliced by an autocatalytic mechanism, the RNA itself having the ability to catalyse its own splicing; nuclear mRNA precursor – the primary transcript – is spliced by a complex assembly incorporating snRNP and called a **spliceosome**; it involves the formation of a **lariat**. Splicing of group II mitochondrial RNA also involves the formation of a lariat, but without formation of a spliceosome. Splicing in which the cut ends are joined directly within the same RNA molecule is called ***cis*-splicing**; ***trans*-splicing** refers to situations in which the cut end from the splicing site rejoins to a splicing site on another RNA molecule. **3** (*of protein*) a post-translational modification of protein that includes two concerted proteolytic cleavages and one ligation, resulting in excision of an inner sequence of the original polypeptide chain to form one protein, and ligation of the two outer sequences to form a second protein. It is thought to be an autocatalytic process. The excised inner sequence is known as an **intein**, the ligated outer sequences as an **extein**. *See also* **gene splicing**.

splicing factor 2 *abbr*.: SF2; a protein, present in nuclear extracts, that functions in an early step in splicing pre-mRNA. It is resistant to mild heat treatment, but inactivated by *N*-ethylmaleimide. It consists of two peptides, P32 and P33, and is involved in ensuring accuracy of splicing. *See also* **pre-mRNA processing protein**.

splicing regulatory protein *see* **SR protein**.

split gene a gene that consists of coding (exon) and noncoding (intron) sequences.

spoke protein a protein associated with the filamentous structure of kinetochore microtubules in the mitotic spindle. Soluble, and cytoplasmically localized during interphase, it becomes primarily associated with the mitotic spindle in mitosis.

spongiform encephalopathy any disease of humans and other animals characterized by the presence of many vacuoles in brain tissue, giving it a spongy appearance. The group includes **bovine spongiform encephalopathy**, **scrapie** in sheep, and **Creutzfeldt–Jakob disease**, **Gerstmann–Straussler syndrome**, and **kuru** in humans. Some of these are classified as **transmissible spongiform encephalopathies**, being caused by infectious agents and carried from one individual to another and in some cases from one species to another. *See also* **prion**, **prion protein**.

spontaneous generation *see* **abiogenesis**.

spontaneous hypoglycemia *see* **glycemia**.

spore a small, often microscopic, reproductive unit consisting of one or several cells. Spores are produced by fungi, bacteria, certain plants, and protozoa. They may variously serve as a means of rapid vegetative propagation, or as a dormant stage in the organism's life cycle. Spores have very low metabolic activity and give rise to a vegetative cell upon germination; they are usually more heat resistant than vegetative cells and are adapted for dispersal. Spores may be sexual or asexual.

sporulation the formation of **spores**.

spot 1 *(in chemistry) or* **spot test** to test for a substance by applying a small amount of detection reagent to a surface. **2** *(in molecular biology)* to detect, using radioactive oligonucleotide probes, oligonucleotides applied in spots onto hybridization filters (**spot blots**).

spoT a gene in *Escherichia coli* for the enzyme guanosine-3′,5′-bis(diphosphate) 3′-pyrophosphohydrolase; EC 3.1.7.2; *other name*: (ppGpp)ase; it catalyses the hydrolysis of guanosine 3′,5′-bis(diphosphate) to guanosine 5′-diphosphate and pyrophosphate as a part of the **stringent response**. The name is jocular, ppGpp and pppGpp being called 'magic spot nucleotides'. *See also* ***relA***, **stringent factor**.

spp. *abbr. for* species (plural).

SPP-1 *see* **osteopontin**.

SPP *abbr. for* signal peptide protease.

[S]ppA *symbol for* adenosine 5′-β-thiodiphosphate (alternative to Ado*PP*[S]).

SP6 phage promoter a 20 bp sequence from bacteriophage SP6 that is sometimes incorporated into the design of plasmid vectors to permit ***in vitro* transcription** of cloned inserts using SP6 RNA polymerase.

[S]pppA *symbol for* adenosine 5′-γ-thiotriphosphate (alternative to Ado*PPP*[S]).

spreading factor *see* **hyaluronidase**.

SP6 RNA polymerase a single subunit enzyme from bacteriophage SP6 that transcribes genes downstream from the **SP6 phage promoter**.

SQDG *abbr. for* sulfoquinovosyldiacylglycerol (*see* **sulfonolipid**).

SQL *abbr. for* symbolic query language; a **query language** used with relational databases, e.g. **SYBASE**. It is often pronounced 'sequel'.

squalamine an aminosterol from the dogfish shark, *Squalus acanthias*. It has antibiotic properties against Gram-negative and Gram-positive bacteria and protozoa. It is an adduct of **spermidine** and a sulfate bile salt.



squalene 2,6,10,15,19,23-hexamethyl-2,6,10,14,18,22-tetracosahexaene; the linear triterpene precursor of all cyclic triterpenoids and the sterols. Although first isolated from shark-liver oils, it is widely distributed in plant and animal cells as a metabolic intermediate. It is formed from acetyl-CoA, via **mevalonate**, **isopentenyl diphosphate**, **geranyl diphosphate**, and farnesyl diphosphate. The latter is converted to presqualene diphosphate, which is then reduced to squalene by NADPH with loss of pyrophosphate; both steps are catalysed by **farnesyltransferase**. [From Latin *squalus*, marine fish, later specifically used to mean shark.]



squalestatin a fermentation product of *Coelomycete* spp. and a selective inhibitor of squalene synthase. It lowers serum cholesterol.



sr *symbol for* steradian.

Sr *symbol for* strontium.

SR *abbr. for* sarcoplasmic reticulum.

src an oncogene (v-*src*), originally discovered in the Rous sarcoma virus, whose product is pp60$^{\text{v-}src}$, a 60 kDa protein that undergoes phosphorylation/dephosphorylation. The **protooncogene**, c-*src*, codes for a related protein; both proteins are **tyrosine kinases**. The C-terminal 19 residues of pp60$^{\text{c-}src}$ are replaced by 12 other residues in pp60$^{\text{v-}src}$. The Src family is the largest of the nonreceptor tyrosine kinase families. It includes Src, Yes, Fyn (*see* ***FYN***), Lck (*see* ***LCK***), Lyn (*see* ***lyn***), Blk (*see* ***blk***), Hck, Fgr (*see* ***FGR***), and Yrk, which range in size from 53 to 64 kDa. They all have an N-terminal myristoylation site, a unique domain, an SH2 domain and an SH3 domain (*see* **SH domain**), a tyrosine kinase domain, and a C-terminal regulatory domain. In vertebrates, the kinase activity is usually inhibited by the phosphorylation of a tyrosine residue within the kinase domain. In v-*src* the region encoding this tyrosine is deleted leading to v-Src having a higher constitutive tyrosine kinase activity than c-Src. Other mutations associated with oncogenic activation map to the SH2 and SH3 domains, suggesting that Src may be inactivated by the binding of its SH2 domain to the phosphotyrosine residue in its negative regulatory domain. The SH3 domain may also participate in this repression.

Src homology domain *see* **SH domain**.

Srd *symbol for* a residue of the ribonucleoside thiouridine (when the position of the thiol group in its thiouracil moiety is unknown or unspecified; alternative to S or sU).

SRE *abbr. for* serum response element.

SREBP *abbr. for* sterol-response-element binding protein; any of three transcription factors that are membrane proteins of the endoplasmic reticulum and Golgi apparatus. Each is complexed with **SCAP** (SREBP-cleavage activating protein), which serves as a sterol sensor. SREBP is cleaved by two Golgi-specific proteases, **S1P** and **S2P**, which release the transcription domain for entry into the nucleus and transcription of genes that contain a 10 bp sterol-response element in their promoter region. These include genes for LDL receptor and enzymes of cholesterol, fatty acid, and triacylglycerol synthesis. SREBP is a polypeptide of ≈1100 amino acids. Its N-terminal half contains a sequence of acidic residues (for binding of accessory transcriptional activators), a basic helix-loop-helix-leucine zipper sequence (for DNA binding and for homodimer or heterodimer formation), and a transmembrane segment. The C-terminal half contains one transmembrane segment and a regulatory domain that interacts with the cytoplasmic domain of SCAP. Cholesterol and polyunsaturated fatty acids, acting via the sterol-sensing domain of SCAP, block the release of the transcriptional domain of SREBP by S1P and S2P. In animals SREBP-1a and -1b are encoded by the same gene using alternative splicing; SREBP-2 is encoded by a different gene.

SREBP-cleavage activating protein *see* **SCAP**.

SRF *abbr. for* serum response factor; a nuclear, dimeric transcription factor. It binds **Elk-1**, which is constitutively bound to the **serum response element**.

SRIF *abbr. for* somatotropin release-inhibiting factor (i.e. **somatostatin**).

sRNA *or* **S-RNA** *abbr. for* soluble RNA (an early name for **transfer RNA**).

SRP *abbr. for* signal recognition particle.

SR protein *abbr. for* splicing regulatory protein; any protein that contains one or more N-terminal RNA-recognition domains that bind RNA with sequence specificity, and a C-terminal Arg-Ser-rich (or RS) domain for protein binding. They function in pre-mRNA splicing and assemble on exonic splicing enhancer sequences. When they bind the C-terminal domain (CTD) of the largest subunit of RNA polymerase II they are called **SCAF** or CASP.

SR-related protein any protein that is related to, but different structurally and functionally from, proteins of the SR family. They function as splicing factors but are not part of small nuclear ribonucleoproteins. They bind to exonic splicing-enhancer sequences on pre-mRNA. *Compare* **SR protein**.

SRS *or* **SRS-A 1** *abbr. for* slow reacting substance (of anaphylaxis). **2** *abbr. for* Sequence Retrieval System; *see* **information retrieval software**.

S→ R variation *see* **smooth–rough variation**.

SRY *abbr. for* sex-determining region of Y chromosome; *other name*: testis-determining gene; a gene on the Y chromosome in humans that encodes a DNA-binding protein (240 amino acids) that induces differentiation of Sertoli cells in the developing gonad so that they produce and secrete anti-Müllerian hormone, which causes regression of female internal genitalia. It also induces Leydig cells to secrete the androgen necessary for development of male genitalia. The DNA-binding domain (≈80 amino acids) is homologous with that of HMG proteins. Many mutations in the gene cause familial XY gonadal dysgenesis (i.e. a female phenotype in the presence of X and Y chromosomes).

ss *abbr. for* single-stranded.

SSB protein *abbr. for* single-strand binding protein.

SSC a solution used in DNA hybridization procedures. A solution of 20× SSC contains 3.0 M NaCl and 0.3 M sodium citrate.

SSCP analysis *abbr. for* single-strand conformation polymorphism analysis.

ssDNA *see* **DNA**.

SSPE a solution used in DNA hybridization procedures. A solution of 20× SSPE contains 3.0 M NaCl, 0.2 M NaH_2PO_4, and 0.02 M EDTA.

SSR *abbr. for* simple sequence repeat.

St *symbol for* stokes (a cgs unit of kinematic viscosity).

Sta *symbol for* statine.

stability constant *symbol*: K_s; an equilibrium constant for the reversible formation of a complex chemical compound from two or more simpler entities; the reciprocal of the **dissociation constant**. In some cases, an **apparent stability constant** (*symbol*: K'_s), constrained with respect to certain variables (e.g. pH) is determined (for the distinction see **equilibrium constant**). The stability constant is also known as the **association constant** (*symbol*: K_{ass}) in cases where ions associate into a substance, e.g. for the reaction $A^+ + B^- \rightarrow= AB$, the (concentration) stability or association constant is given by:

$$K_s = [AB]/[A^+][B^-] = K_{ass}.$$

stable expression *(in genetics)* the production of a recombinant protein sustained over a period of weeks or months. *Compare* **transient expression**.

stable factor *an alternative name for* factor VII; *see* **blood coagulation**.

stable isotope an **isotope** that is not radioactive.

stachyose *or* **lupeose** the tetrasaccharide, *O*-α-D-galactopyranosyl-(1→6)-*O*-α-D-galactopyranosyl-(1→6)-*O*-α-D-glucopyranosyl-β-D-fructofuranoside, isolated from *Stachys tuberifera* rhizomes. It is widely distributed, usually associated with **raffinose** (*see* that entry for synthesis) and **sucrose.**

stacking gel *an alternative name for* **spacer gel**.

staggered conformation *see* **conformation**.

stainless steel steel that is resistant to corrosion due to its high content of chromium and, often, nickel. It is highly resistant to all organic acids and weak mineral acids but is slowly attacked by concentrated mineral acids. It does not rust.

Stains-all *a proprietary name for* 1-ethyl-2-[3-(3-ethylnaphtho[1,2-*d*]thiazolin-2-ylidene)-2-methylpropenyl]naphtho[1,2-*d*]thiazolium bromide; a cationic carbocyanine metachromatic dye used as a semiselective stain for locating nucleic acids, proteins, and polysaccharides. RNA stains bluish-purple, DNA blue, protein red, and phosphoprotein blue.



stamp collecting according to Lord Rutherford (1871–1937), one of the two branches of science (the other being physics).

standard *(in analytical chemistry)* **1 primary standard** a chemical that can be obtained in an unvarying state (e.g. of purity and/or stability) and used as an approved example against which other examples of the same chemical can be compared. **2 secondary standard** a chemical that can be used for comparative purposes following calibration against a primary standard. Although its properties are less stringent than a primary standard, its ready availability makes for convenience of use. *See also* **standard atmosphere**, **standard state**, **standard temperature and pressure**.

standard atmosphere an internationally established reference for pressure, defined as 101 325 pascals. The **atmosphere** (def. 3) (*symbol*: atm), equal to 101 325 pascals, was formerly used as a unit of pressure; its use is now discouraged. *See also* **standard temperature and pressure**.

standard curve a plot of any appropriate parameter against known amounts (or concentrations) of detectable substance. Such a curve can be used to determine the amount (or concentration) of the same substance in an unknown solution given a reading for the parameter in the unknown solution.

standard deviation *abbr.*: SD; *symbol*: *s* (for a sample) *or* σ (for a distribution); the common measure of dispersion of a series of observations of *x* that is normally distributed. It is the root-mean-square average of the deviations of the observations from their mean and is in the same units as those of the observations. The standard deviation, s_x, is given by:

$$s_x = \sqrt{\left[\frac{1}{n}\sum_{i=0}^{n}(x-\bar{x})^2\right]}$$

Where $\bar{x}$ is the arithmetic average of deviations of *x* and *n* is the number of observations; s_x^2 is called the variance of the sample of observations of *x*. Some authorities prefer the definition:

$$s_x = \sqrt{\left[\frac{1}{n-1}\sum_{i=0}^{n}(x-\bar{x})^2\right]}$$

so that s_x^2 is then the best estimate of the variance, σ^2, of the population from which the sample of observations of $\bar{x}$ was made. *See also* **degrees of freedom**, **standard error of estimate of the mean**.

standard error of estimate of the mean *or* **standard error of the mean** *abbr.*: SEM; a measure of the reliability of an estimate of the **mean** of a population. It is equal to the **standard deviation**, s_x, of the observations divided by the square root of the number of observations, *n*; i.e. SEM = $s_x/\sqrt{n}$.

standard free energy *see* **Gibbs energy**.

standardize *or* **standardise** to relate any instrument, vessel, or reaction to an absolute standard. **—standardization** *or* **standardisation** *n.*

standard pressure *symbol*: *p*; an established reference for pressure. Since 1982 the recommended standard pressure for reporting thermodynamic data has been set at 10^5 pascals (1 bar). Before 1982 it was taken to be 101 325 pascals (1 atmosphere).

standard state a set of conditions, established by convention, under which a standard reference is determined or calculated. *See* **chemical potential**, **enthalpy**, **entropy**, **Gibbs energy**, **hydrogen electrode**, **standard pressure**, **standard temperature and pressure**.

standard temperature and pressure *abbr.*: stp *or* s.t.p. *or* STP; the standard conditions for the comparison of properties of gases. Standard temperature is now 298.15 K (formerly 273.15 K, i.e. 0°C) and **standard pressure** is 10^5 pascals. *Former name*: normal temperature and pressure (*abbr.*: ntp *or* n.t.p. *or* NTP).

stanniocalcin a peptide of bony fishes that counteracts hypercalcemia and stimulates phosphate resorption in kidney.

Staphylococcus a genus of Gram-positive bacteria, commonly associated with wounds and generally causing localized infections. *Staphylococcus aureus* forms yellow or orange pigments and yields plasmids that are useful in recombinant DNA experimentation: *S. aureus* plasmids coding for resistance to various antibiotics can be transfected into *Escherichia coli* or into *Bacillus subtilis* where they are stable, replicate, and express antibiotic resistance. They have provided the basis from which improved vectors have been developed.

staphylokinase a noncatalytic protein (136 amino acids) produced by *Staphylococcus* spp. that binds to and activates plasminogen. It has no sequence similarity to streptokinase, and is used to dissolve blood clots.

StAR *abbr. for* steroidogenic acute regulatory; a protein of the mitochondrial matrix that is phosphorylated in response to cAMP released by corticotropin in the adrenal cortex and gonads. It plays a role in the entry of cholesterol into the matrix. Point mutations in the gene for StAR at 8p11.2 (which encodes 286 amino acids) result in congenital lipoid adrenal hyperplasia.

star activity the relaxation of specificity under nonoptimal conditions exhibited by some restriction endonucleases. They then cleave DNA sequences that are similar to but not identical with their defined recognition sequence.

starch the most important reserve polysaccharide found in plants. It has two components: **amylose**, which is a homopolymer of glucose units linked only by $\alpha(1 \rightarrow 4)$ bonds; and **amylopectin**, also a glucose homopolymer (branched) that contains $\alpha(1 \rightarrow 6)$ bonds as well as $\alpha(1 \rightarrow 4)$ bonds. Starch is synthesized in chloroplasts during active periods of photosynthesis, accumulating as starch grains. It is then converted to sucrose and translocated to storage organs, such as seeds and tubers, where it is re-formed. *Compare* **glycogen**.

starch (bacterial glycogen) synthase EC 2.4.1.21; *recommended name*: starch synthase; *systematic name*: ADPglucose:1,4-α-D-glucan 4-α-D-glucosyltransferase; *other name*: ADPglucose–starch glucosyltransferase. An enzyme that catalyses a reaction between ADPglucose and (1,4-α-D-glucosyl)$_n$ to form (1,4-α-D-glucosyl)$_{n+1}$ and ADP. It uses ADPglucose instead of the UDPglucose of **glycogen synthase**.

starch debranching enzyme *an alternative name for* **R-enzyme.**

starch phosphorylase *see* **α-glucan phosphorylase**.

starch synthase EC 2.4.1.11; *recommended name (example)*: glycogen (starch) synthase (the nature of the synthetic product should be included in the name); *systematic name*: UDPglucose:glycogen 4-α-D-glucosyltransferase; *other name*: UDPglucose–glycogen glucosyltransferase. An enzyme that catalyses a reaction between UDPglucose and (1,4-α-D-glucosyl)$_n$ to form (1,4-α-D-glucosyl)$_{n+1}$ and UDP. *See also* **glycogen synthase**. *Compare* **starch (bacterial glycogen) synthase**.

starch syrup *an alternative name for* **corn syrup**.

Stargardt macular dystrophy *or* **juvenile macular degeneration** an autosomal recessive condition that is the most common form of macular degeneration. It manifests in the pre-teen years and is caused by mutations in an ABC transporter protein, called ABCR (ABC transporter retina, or Rim protein; 2273 amino acids), that is found in rod photoreceptor outer segments. [After Karl Stargardt (1875–1927), German ophthalmologist.]

stargazin a protein (38 kDa) with four transmembrane segments that is essential for bringing AMPA receptor (an ionophoric glutamate receptor) to the postsynaptic membrane. Its intracellular C-terminal region binds to the postsynaptic protein PSD-95. It is homologous with the γ subunit of voltage-gated Ca^{2+} channels of muscle. Defects in the protein are the cause of stargazer mutant mouse.

Start an important checkpoint in the G_1 phase of the eukaryotic **cell-division cycle**. Passage through Start commits the cell to enter S phase.

start codon the trinucleotide **codon** AUG that codes for *N*-formylmethionine, the first amino-acid residue in the synthesis of all prokaryotic and mitochondrial proteins.

start kinase a complex of cdc2 (*see* ***cdc*** **gene**) and a G_1 **cyclin** that is a serine/threonine protein kinase; its activation is necessary for the cell to pass **Start**. The identity of the G_1 cyclin modifies the specificity of the complex.

start point the base pair in DNA at which the first nucleotide is incorporated into an RNA transcript. It is usually a purine, and often is the central base of the sequence CAT. It is sited at the downstream end of the **promoter**. *Compare* **start codon**.

start protein any protein that is involved uniquely at the start of the cell cycle. For example, protein Cdc10 from *Schizosaccharomyces pombe* (which has a close homologue in *Saccharomyces cerevisiae*) is probably a transcriptional regulator for *cdc10* and also for *cdc2*, which encodes a component of **start kinase**.

starve to deprive of nutrients. In animal experiments a minimum of 24 h deprivation is generally understood. Cultures may be starved of specified single nutrients.

stasis arrest or stagnation of flow.

+stasis *comb. form* denoting lack of movement; cessation of flow. —**+static** *adj.*

STAT *abbr. for* signal transducer and activator of transcription; a family of eukaryotic transcription factors that mediate the response to many cytokines and growth factors. Upon receptor activation, STAT proteins dimerize, translocate to the nucleus, and bind to specific promoter sequences on target genes. Seven different genes have been so far identified in mammals. Example: STA1_HUMAN, 750 amino acids (87.33 kDa).

+stat *comb. form* indicating a device for maintaining a particular property at a constant value, e.g. **cryostat**, **thermostat**. —**+static** *adj.*

stathmin *other names*: phosphoprotein p19; oncoprotein p18; prosolin; a ubiquitous, phylogenetically conserved, cytoplasmic protein that serves as a phosphorylated intermediate in diverse second-messenger pathways. Stathmin undergoes phosphorylation; both phosphorylation and expression of the protein are regulated throughout development, in response to extracellular signals that control cell proliferation and differentiation. It is a major phosphorylation substrate in neurons.

+static *see* **+stasis**, **+stat**.

statics *functioning as sing.* the branch of applied mathematics dealing with the interaction of forces in nonmoving systems.

statin **1** a phosphoprotein present specifically in the nuclei of nonproliferating cells. It forms a complex with a 45 kDa serine/threonine protein kinase, and has structural similarity to the elongation factor EF-la. **2** any of a class of drugs used to lower blood cholesterol levels through inhibition of hydroxymethylglutaryl-CoA reductase. Examples are Lipitor (atorvastatin) and Zocor (simvastatin). The effect of these drugs can be enhanced by the simultaneous administration of an agent, such as **cholestyramine**, that prevents the reabsortion of bile acids, thus increasing the conversion of cholesterol to bile acids. **3** a variant spelling of **statine**.

+statin *word ending (in hormone nomenclature)* denoting a hypothalamic release-inhibiting factor (or hormone). *Compare* **+liberin**.

statine *or* **statin** *symbol*: Sta; [3*S*,4*S*]-4-amino-3-hydroxy-6-methylheptanoic acid; a novel amino acid contained in positions 3 and 5 of **pepstatin A**.

stationary phase **1** *(in chromatography)* the immobile phase to which the analyte adsorbs or partitions from the mobile phase. **2** *(in fermentation)* the phase of an *in vitro* culture of microorganisms or eukaryotic cells that follows the exponential growth phase and in which there is little or no growth.

statistically significant *see* **significant**.

statistical mechanics the theoretical analysis of molecular properties based on quantum theory.

statistical sample a finite selection of items from a population of which the measurement of a variable will give a close approximation to the distribution of that variable in the whole population. *See also* **random sample**, **sample**.

statistics **1** *functioning as sing.* the science of collecting, analysing, interpreting, and presenting quantities of numerical data. **2** *functioning as pl.* a collection of quantitative data. —**statistical** *adj.*

stator the part of the **H^+-transporting ATP synthase** that is held fixed relative to the F_0 part during flow of hydrons through the latter. *Compare* **rotor**.

statyl the acyl group derived from **statine**.

Staufen a dsRNA-binding protein of *Drosophila* that is involved in localizing maternal mRNA in oocytes and the embryo. It contains five dsRNA-binding motifs (**dsRBMs**). Mouse and human homologues lack the first dsRBM, bind tubulin, and interact with the rough endoplasmic reticulum and with polysomes.

staurosporine an antibiotic from *Streptomyces* spp., M_r 466.2, best known as a potent inhibitor of protein kinase C.



Ste *symbol for* the stearoyl group, CH_3 –$[CH_2]_{16}$–CO–.

steady state a condition in which the properties of any part of a system are constant during a process or reaction; i.e. where the rate of formation or increase of a particular quantity is balanced by its rate of removal or decrease.

steady-state fluorescence anisotropy a method in which a sample containing a fluorescent compound is irradiated with plane-polarized light, the emitted fluorescence being analysed to determine its degree of polarization both in the plane of the excitation radiation and in a plane at right angles to this. Only molecules of the fluorescent compound that are aligned in the plane of the incident radiation can absorb radiation and be excited to emit fluorescence. If, in the interval between absorption of the radiation and the emission of fluorescence, the molecule moves out of the plane of polarization of the incident radiation, the emitted radiation will lose polarization (be depolarized) to a degree that depends on the extent to which the molecule had moved. The technique is used to measure the degree to which fluorescent probes are tumbling in a sample. If the probes are held in a relatively rigid position, the extent of depolarization will be small, if tumbling freely it will be high.

steady-state kinetics the analysis of an enzyme reaction in the steady state, i.e. after the pre-steady state and when the intermediates have reached a steady concentration. The duration of the steady state is relatively short, and this state is in any case an approximation since the accumulation of products and the depletion of substrate occur continuously from the start of the reaction. *See* **Michaelis kinetics**.

steapsin *an old term for* **pancreatic lipase**.

stearate 1 *a trivial name for* octadecanoate, CH_3– $[CH_2]_{16}$–COO^-, the anion derived from stearic acid, or octadecanoic acid, a saturated straight-chain higher fatty acid. **2** any mixture of free stearic acid and its anion. **3** any salt or ester of stearic acid. *See also* **stearoyl**.

stearin 1 *an old name for* any of the glyceryl esters of stearic acid, especially the triester, **tristearin** (tristearoylglycerol). **2** *a commercial name for* a grade of stearic acid containing other fatty acids, especially palmitic acid.

stearoyl *symbol*: Ste; *numerical symbol* 18:0; *a trivial name for* octadecanoyl, CH_3–$[CH_2]_{16}$–CO–, the acyl group derived from stearic acid (*see* **stearate**). A major fatty-acid component of plant and animal lipids; tallow and other hard animal fats contain up to 35%. Together with palmitate it represents a high proportion of the saturated fatty-acid content of dietary and other lipids. It is synthesized from palmitoyl-CoA by a microsomal chain-elongation enzyme. It is incorrectly referred to as **stearyl**.

stearoyl-CoA desaturase EC 1.14.99.5; *systematic name*: stearoyl-CoA,hydrogen donor:oxygen oxidoreductase; *other names*: acyl-CoA desaturase; fatty-acid desaturase; Δ^9-desaturase. An enzyme that catalyses a reaction between dioxygen, an electron donor and stearoyl-CoA to form oleoyl-CoA. It is an iron protein with a short half-life, and is the only inducible component of the endoplasmic reticulum fatty acyl-CoA desaturase system. It utilizes electrons from reduced cytochrome b_5.

stearyl 1 *a common name for* octadecyl, CH_3–$[CH_2]_{16}$–CH_2–, the alkyl group derived from octadecane; octadecyl is recommended. **2** *an old trivial name for* octadecanoyl; **stearoyl** is now recommended.

steatite *see* **talc**.

steato+ *comb. form* indicating presence or relation to fatty substances.

steatorrhoea the presence of abnormally large amounts of fat in the feces.

steatosis fatty degeneration of tissue.

steel factor *see* **stem cell factor**.

steel factor receptor *see* ***kit***.

stefin *see* **cystatin**.

Stelazine *see* **trifluoperazine**.

stellacyanin a blue, copper-containing mucoprotein of low molecular weight obtained from the Japanese lacquer tree, *Rhus vernicifera*. It functions as an electron-transfer protein, accepting electrons from the cytochrome b_6–f complex, and donating them to **photosystem** I, and has been much studied for the structure of the copper-binding site.

STEM *abbr. for* scanning transmission electron microscope.

stem cell any member of the various groups of reserve cells that replace cells destroyed during the normal life of the animal, e.g. blood cells, epithelial cells, spermatogonia, and skin cells. Stem cells can divide without limit; after division, the stem cell may remain as a stem cell or proceed to terminal differentiation.

stem cell factor (*abbr.*: SCF) *or* **mast cell growth factor** *or* **steel factor** a **cytokine** that stimulates the proliferation of mast cells. It is produced by endothelial cells, fibroblasts, bone marrow cells, and Sertoli cells. A homodimer glycoprotein with type I membrane and soluble forms, it enhances the proliferation of both myeloid and lymphoid hemopoietic progenitors. Its receptor is the membrane receptor-tyrosine kinase encoded by the protooncogene c-*kit* (*see* ***KIT***).

stem cell marker any molecule, especially one expressed at the cell surface, that is used to distinguish stem cells from other cells; e.g. CD34.

stem name any generic name for a category of similar compounds, enzymes, organisms, etc. that is used also as an affix in forming the specific names of individual members of such a category.

steno+ *or (before a vowel)* **sten+** *comb. form* indicating narrowness.

stenohaline describing an organism that is unable to tolerate wide variations in environmental osmotic pressure.

stenothermous describing an organism that is unable to tolerate wide variations in environmental temperature.

STEP *abbr. for* **sieve tube exudate protein**.

step gradient a discontinuous gradient, formed in a tube by layering solutions of different densities carefully one on the other. In column chromatography the same effect is achieved by pumping buffers of different composition sequentially through the column. *See* **gradient**.

steradian *symbol*: sr; the SI supplementary unit of solid angle. It is equal to the angle subtended at the centre of a sphere by an area of surface equal to the square of the sphere's radius. The surface of a sphere subtends an angle of 4π sr at its centre.

stercobilin *or* **stercobilin IXα** a linear red-brown tetrapyrrole formed in heme catabolism. Structurally it is an oxidation product of **stercobilinogen.** Metabolically, it is formed from urobilinogen by intestinal bacteria and is the major pigment of feces.



stercobilinogen *an alternative name for* 10,23-dihydrostercobilin; *former name*, stercobilinogen IXα. A product of heme catabolism; it is a **urobilinogen** molecule in which the double bonds between the methyl and ethyl substituents on the two end rings have been reduced.

sterculic acid *see* **cyclic fatty acid**.

stereo+ *comb. form* denoting solid or three-dimensional.

stereobase unit the smallest set of one, two, or more successive **configurational base units** that prescribes repetition in a polymer molecule.

stereochemistry the branch of chemistry dealing with the three-dimensional properties of molecules; the study of the properties of **stereoisomers**. *See* ***cis–trans*** **isomerism**, ***Re*/*Si*** **convention**, **sequence rule**, **stereospecific numbering**.

stereoheterotopic a term describing chemically-like ligands (or faces of double bonds) whose separate replacement with an achiral ligand (or for faces, addition of an achiral reagent) gives rise to two stereoisomers. If the stereoisomeric products are **enantiomers**, the



stercobilinogen

ligands (faces) are enantiotopic; if they are diastereoisomers, the ligands (faces) are diastereotopic. for more extensive descriptions, see diastereotopic, enantiotopic.

stereoisomer any of two or more **isomers** that have the same molecular constitution and differ only in the three-dimensional arrangement of their atomic groupings in space. Stereoisomers may be **diastereoisomers** or **enantiomers**. *Compare* **constitutional isomer**. —**stereoisomeric** *adj.*; **stereoisomerism** *n.*

stereology the body of mathematical methods dealing with the interpretation of the structure and dimensions of three-dimensional objects from information contained in two-dimensional representations, such as photomicrographs of tissue sections.

stereoregular polymer a regular polymer composed of molecules having a regular repetition of identical **stereobase units** at all stereoisomeric sites of the main chain.

stereoselective polymerization the formation of a polymer from a mixture of stereoisomeric monomer molecules by preferential incorporation of one species into a growing polymer chain.

stereospecific (of an enzymatic or other reaction system) acting on or producing a particular **stereoisomer**; stereochemically specific. —**stereospecificity** *n.*

stereospecific numbering a numbering system applied mostly to prochiral compounds, *Caabc*, with two similar atoms, or groups of atoms, *a*. It numbers the prochiral *a* groups and, by extension, their chiral derivatives. A stereospecifically numbered compound is designated by the prefix *sn*-. The Hirschmann system was devised particularly so that the ^{14}C-labelled glycerol giving rise to [3,4-$^{14}C_2$]glucose (in rats) could be termed [1-^{14}C] glycerol and thus be related, biosynthetically and by nomenclature, to [1-^{14}C]lactate. It uses the basic *R*/*S* system (*see* **sequence rule**) to set up a model, which is viewed away from the group with the lowest sequence priority. If this is *c* in *Caabc*, a counterclockwise ordering is examined for the remaining three groups, *baa*, starting with *b*. The first *a* group to be encountered receives the lower number. The numbering for glycerol is shown in structure 1. By extension, the glycerol phosphate formed by **glycerol kinase** becomes *sn*-glycerol 3-phosphate (structure 2). This structure has also been described as D-glycerol 3-phosphate, L-glycerol 3-phosphate, and L-α-glycerophosphate. The Hirschmann nomenclature has found wide acceptance in the lipid field. The Hanson and Hirschmann system expands the *R*/*S* system in a logical fashion (rather than using the arbitrary counterclockwise ordering described for glycerol). The two similar groups, *a*, of *Caabc* are first given *pro-R* and *pro-S* assignments. Then, following the established '*R* precedes *S* rule', *pro-R* precedes *pro-S*, and the *pro-R* group is assigned the lower number. This system has been applied to citric acid as shown in structure 3. Application of this system to glycerol unfortunately leads to the product of glycerol kinase being *sn*-glycerol 1-phosphate. Although this system has a logical basis in terms of established nomenclature, it seems unlikely that the *sn* system for glycerol and derivatives will be brought into line.



(1) glycerol



(2) *sn*-glycerol-3-phosphate



(3) citric acid

stereospecific polymerization a polymerization in which a **tactic polymer** is formed.

steric relating to effects involving arrangements of atoms in space.

steric hindrance 1 prevention of the free rotation of an atom or group in a molecular entity with respect to a connected one due to the relative sizes and/or spatial disposition of the atoms or groups in question. **2** restriction or prevention of the reaction of a molecular entity with another due to the relative sizes and/or spatial disposition of atoms or groups in either or both of the reactants.

sterilant a substance that destroys or eliminates all forms of microbial life in the inanimate environment, including bacteria, bacterial spores, fungi, fungal spores, and viruses. *Compare* **disinfectant**, **sanitizer**.

sterile 1 (of inanimate objects) free from microbiological or other life forms. **2** (of a living organism) incapable of sexual reproduction.

sterilize *or* **sterilise 1** to treat in such a way as to kill undesired microorganisms without damaging the material under treatment. *Compare* **disinfection**. **2** to render incapable of sexual reproduction. —**sterilization** *or* **sterilisation** *n.*

Stern–Volmer equation an expression relating **fluorescence quenching** to the concentration of the quenching substance, *c*, and the fluorescence lifetime, τ. It is: $F_o/F = 1 + kc\,\tau$, where F_o is the fluorescence intensity when no quencher is present, *F* is the fluorescence intensity in the presence of quencher, and *k* is a constant that depends on the system; the concentration of the absorbing molecule must be the same in both quenched and unquenched systems. The **Stern–Volmer plot** is a plot of F_o/F against concentration of quenching substance, from the slope of which, if the fluorescence lifetime is known, the quenching constant can be obtained. [After Otto Stern (1888–1969) and M. Volmer] .

steroid any of a large group of substances that have a ring system based on 1,2-cyclopentanoperhydrophenanthrene. The group includes such natural products as **bile acids**, **corticosteroids**, **sex hormones**, **sterols**, and various plant steroids. *See also* **vitamin D**.

steroid diabetes the combination of decreased glucose tolerance, fasting hyperglycemia, and glucosuria, found in patients exposed to excessive quantities of **glucocorticoids**. It may thus accompany **Cushing's syndrome**.

steroid-hormone receptor any intracellular receptor that binds steroid hormones and mediates their effects; the family also includes receptors for thyroid hormones, retinoids, and vitamin D. After the steroid enters the cell, the steroid–receptor complex is translocated to the nucleus and binds to a specific DNA sequence, a **response element**. The receptors contain a modulating N-terminal domain, a zinc finger DNA-binding domain, and a C-terminal steroid-binding domain.

steroid *Δ*-isomerase EC 5.3.3.1; *systematic name*: 3-oxosteroid Δ^5–Δ^4-isomerase; *other name*: Δ^5–Δ^4-ketosteroid isomerase. An enzyme involved in microbial transformation of steroids; it catalyses the reaction:

$$\text{3-oxo-}\Delta^5\text{-steroid} = \text{3-oxo-}\Delta^4\text{-steroid.}$$

steroid 21-monooxygenase EC 1.14.99.10; *other names*: steroid 21-hydroxylase; cytochrome P450 21A1; an enzyme that catalyses a 21-hydroxylation of progesterone to 11-deoxycorticosterone and of 17-hydroxyprogesterone to 11-deoxycortisol in the fasciculata/reticularis region of the adrenal cortex. It is a heme–thiolate protein. Mutations that decrease its activity result in congenital adrenal hyperplasia: there is a failure to synthesize cortisol, and this results in overproduction of **corticotropin**, 17-hydroxyprogesterone, and androstenedione.

steroid 11*β*-monooxygenase EC 1.14.15.4; *other names*: steroid 11*β*-hydroxylase; cytochrome P45011B1 (*or* CYP11B1); cytochrome P45011B2 (or CYP11B2). Either of the enzymes found in the mitochondrial matrix of adrenal cortical cells that are involved in production of cortisol and aldosterone. CYP11B1 converts 11-deoxycorticosterone to corticosterone and 11-deoxycortisol to cortisol, in the zona fasciculata and zona reticularis. CYP11B2 also has **aldosterone synthase** activity, converting corticosterone to aldosterone in the zona glomerulosa. Mutations in CYP11B1 lead to congenital adrenal hyperplasia, whereas mutations in CYP11B2 lead to aldosterone deficiency.

steroid 17*β*-monooxygenase EC 1.14.99.9; *other names*: steroid 17*β*-hydroxylase; cytochrome P45017. An enzyme of the endoplasmic reticulum occurring in the zona fasciculata and zona reticularis of adrenal cortex and in the gonads. It catalyses the following conversions:

(1) progesterone → 17*β*-hydroxypregnenolone →
17*β*-dehydroepiandrosterone;
(2) progesterone → 17-hydroxyprogesterone →
androstenedione.

Both reactions involve sequential 17*β*-hydroxylation and 17,20-lyase reactions. Mutations that decrease both activities results in congenital adrenal hyperplasia.

steroidogenesis the biosynthesis of steroids, but often referring to the genesis of other steroids from cholesterol.

steroidogenic factor 1 *abbr*.: SF-1; a protein of the nuclear receptor family of zinc finger transcription factors that regulates tissue-specific expression of P450 steroid hydroxylases, 3*β*-hydroxysteroid dehydrogenase, ACTH receptor, StAR, and anti-Müllerian hormone. It is expressed in gonads and adrenal glands from the earliest stages of development, and in the hypothalamus and anterior pituitary gland of mouse and human. Gene knockout in mice results in lack of adrenal glands and gonads.

steroid 5*α*-reductase *or* **3-oxo-5*α*-Δ^4-dehydrogenase** either of two enzymes that catalyse the reaction: testosterone + NADPH + H^+ → 5*α*-dihydrotestosterone + $NADP^+$. One of the enzymes, 5*α*-reductase 1, has an alkaline pH optimum and is found in liver and skin. The other, 5*α*-reductase 2, has an acid pH optimum and is found in the male urogenital tract. Many mutations resulting in 5*α*-reductase 2 deficiency cause an autosomal recessive form of testicular feminization syndrome.

sterol any **steroid** that contains one or more hydroxyl groups and a hydrocarbon side-chain in the molecule.

sterol *O*-acyltransferase EC 2.3.1.26; *other names*: cholesterol acyltransferase; sterol-ester synthase; an intracellular enzyme that catalyses the formation of cholesterol ester from acyl-CoA and cholesterol. It is involved in the storage of cholesterol esters in phagocytic cells, a process that plays a part in producing lipid-laden cells in arterial walls. There are two isozymes in yeast. The enzyme belongs to the superfamily of membrane-bound *O*-acyltransferases.

sterol carrier protein 2 *abbr*.: SCP2; a protein (123 amino acids) required for intracellular sterol transport. It may be a cofactor for the endoplasmic reticulum enzyme 3*β*-steroid-Δ^7-reductase (EC 1.3.1.21), which converts 7-dehydrodesmosterol to desmosterol in the final stages of cholesterol biosynthesis. SCP2 is produced from a short transcript that forms part of a long transcript encoding SCPx, and also by cleavage of SCPx in the peroxisomal matrix – the C-terminal region of SCPx contains SCP2.

sterol 27-monooxygenase *or* **sterol 27-hydroxylase** *or* **cytochrome P45027** *or* **CYP27**. A mitochondrial cytochrome P450 enzyme (498 amino acoids) that catalyses hydroxylation of the C27 in the side chain of cholesterol or of dihydroxycholestane. This is the first step in the degradation of this side chain in the biosynthesis of bile acids. Many mutations lead to enzyme deficiency and cerebrotendinous xanthomatosis.

sterol-response-element binding protein *see* **SREBP**.

sterol-sensing domain a hydrophobic domain of proteins that binds cholesterol. *See* **SREBP**.

steryl-sulfatase EC 3.1.6.2; *other names*: steroid sulfatase (sulfatase); steryl-sulfate sulfohydrolase; arylsulfatase C; an enzyme that catalyses the hydrolysis of 3-*β*-hydroxyandrost-5-en-17-one 3-sulfate to 3-*β*-hydroxyandrost-5-en-17-one and sulfate.

stevioside 13-[(2-*O*-*β*-D-glucopyranosyl-*α*-D-glucopyranosyl)-oxy]kaur-16-en-18-oic acid *β*-D-glucopyranosyl ester; a glycoside extracted from the leaves of *Stevia rebaudiana* (yerba dulce). It is used as a sweetening agent, being about 300 times as sweet as sucrose.



STH *abbr. for* somatotropic hormone; *see* **somatotropin**.

STI *abbr. for* soybean trypsin inhibitor.

Stickler syndrome *or* **arthro-ophthalmodystrophy** an autosomal dominant chondrodysplasia in which early joint degenerative disease is accompanied by disorders of the eye and deafness. Mutations in genes for collagens XIα-1, XIα-2, and IIα-1 are responsible. [After Gunnar Stickler (1925–), US physician.]

sticky end *see* **cohesive end**.

stiff-man syndrome *or* **stiff-person syndrome** a rare progressive rigidity of the body musculature. In ≈60% of patients autoantibodies to glutamate decarboxylase are present in plasma and cerebrospinal fluid, and in ≈58% of patients diabetes mellitus type 1 is also present. The muscular hyperactivity is suppressed by sleep, anesthesia, GABA agonists, or curare.

stigmasterol 3*β*-hydroxy-24-ethyl-$\Delta^{5,22}$-cholestadiene; a **phytosterol** structurally related to *β*-sitosterol (*see* **sitosterol**) and found in plant oils.



stilbene *or* **1,2-diphenylethene** an unsaturated hydrocarbon, $C_6H_5CH{=}CHC_6H_5$, several derivatives of which occur in plants, where they protect against bacterial and fungal pathogens, discourage herbivory, inhibit seed germination, and function as growth inhibitors and in dormancy. Combrestatin and resveratrol are substituted stilbenes.

stilbestrol *or (esp. Brit.)* **stilboestrol** 4,4′-dihydroxystilbene; a synthetic nonsteroid compound, first prepared in 1938, that became a source of a range of compounds with estrogenic activity, of which α,β-diethylstilbene (*see* **diethylstilbestrol**) is the most active. Stilbestrol has been used as a growth promoter in farm animals but is now banned in most countries. It is still used to treat hormonal disorders in small animals. It was formerly used to treat prostatic cancer but there is some evidence for its carcinogenicity.



trans-stilbestrol

still an apparatus for the distillation of liquids, including the preparation of distilled water. It consists of a heated vessel, a condenser, and a receiver. A continuous apparatus incorporates an automatic feed for the liquid in question, a heating element, and a thermoregulator.

stimulate *(in physiology)* to provide a **stimulus** to any tissue or cell leading to its excitation or to initiation of a sequence of events with some defined endpoint, involving an electrical event, activation of a metabolic pathway, or initiation of cell division or growth. —**stimulation** *n.*; **stimulative** *adj.*

stimulus *(in physiology)* any event or phenomenon, such as radiation, electrical potential, or addition of molecules that leads to excitation of a tissue or cell.

stimulus–response coupling a molecular mechanism, often involving **signal transduction**, that transmits a stimulus from the exterior of a cell's plasma membrane, in many cases through **second messenger** pathways, to effector systems that bring about a response. For example, in **stimulus–secretion coupling** the effector system brings about a secretion event such as degranulation of mast cells or release of hormone (e.g. insulin) from storage granules to the cell exterior.

stimulus–secretion coupling *see* **stimulus–response coupling**.

stochastic arrived at by skilful conjecture; e.g. a stochastic model, a stochastic process.

stock solution a solution of a reagent, at a stable or convenient concentration, from which appropriate dilutions can be made at the time of use.

Stock system *(in inorganic nomenclature)* a system of designating the **oxidation number** of an element by placing a Roman numeral in parentheses immediately following the name of the element or, where symbols are used, in superscript to the right of the symbol; e.g. manganese(IV) oxide, $Mn^{IV}O_2$.

stoichiometry *or (rarely)* **stoicheiometry** the quantitative relationship of the reactants and products of a chemical reaction in the proportions that they appear in the chemical equation describing the reaction. —**stoichiometric** *or* **stoicheiometric** *adj.*

stokes *symbol*: St; the cgs unit of **kinematic viscosity**; its use is now discouraged. In SI units, kinematic viscosity is measured in square metres per second; 1 St = 10^{-4} m^2 s^{-1}. [After (Sir) George Gabriel Stokes (1819–1903), British mathematician.]

Stokes' law of fluorescence a law stating that the wavelength of the emitted fluorescent light, λ_{em}, is greater than that of the light exciting the fluorescence, λ_{ex}. This relationship is true for most fluorescent materials; those for which it does not hold are termed **anti-Stokes**.

Stokes' law of viscosity a law stating that the frictional coefficient, *f*, of a spherical particle of radius *r*, moving through a liquid of viscosity η, is given by $f = 6\pi\eta r$.

Stokes' loss the loss of excitation energy available for fluorescence due to collision of molecules in the first excited state, S_1, with their neighbours, which results in a lower vibration level of S_1.

Stokes' shift the difference in wavelength between the excitation and emission maxima for a particular fluorescent substance. In quantitative form, Stokes' shift is $10^7(1/\lambda_{ex} - 1/\lambda_{em})$, where λ_{ex} and λ_{em} are the corrected maximum wavelengths for excitation and emission expressed in nanometres.

stoma (*pl.* **stomata**) any of the pores in the epidermis of plants, particularly in leaves, through which gaseous exchange takes place.

stomatin *or* **band 7.2b protein** a major membrane protein of human erythrocytes that contains a central domain also found in prohibitins and flotillin. It is lacking in an autosomal dominant form of hemolytic anemia (hereditary stomatocytosis).

stop codon any of the trinucleotide **codons**, UGA, UAG, and UAA, that signal the termination of translation of a messenger RNA molecule and the release of the nascent polypeptide chain. *See also* **termination codon**.

stopped-flow technique a method in which two solutions are caused to flow into a mixing chamber and then into an observation chamber, after which the flow is stopped abruptly and the chemical reaction is followed, usually spectroscopically, as the mixture in the observation chamber ages. Critical features include the quality of mixing, the speed with which the mixed solution fills the observation chamber, and the geometry of the observation chamber in relation to the sensitivity of observation. *See also* **rapid-reaction kinetics**.

STOP protein *abbr. for* stable tubule only polypeptide; a protein that blocks the endwise dissociation of microtubules.

stop-transfer protein *or* **stop-transfer sequence** *see* **signal peptide**.

storage granule any small **organelle**, bounded by a lipid-bilayer membrane, that contains stored material. For example, mast-cell storage granules contain histamine, while those of pancreatic B cells contain insulin; in both cases the stored material is destined for secretion. This involves a stimulus that causes fusion of the granule membrane with the plasma membrane, followed by release of the granule contents by **exocytosis**.

storage polysaccharide any polysaccharide that serves as a form of stored energy in living organisms. Storage polysaccharides include starch, phytoglycogen (e.g. in maize), and fructosans (e.g. inulin) in plants, and glycogen in animals.

stp *or* **s.t.p.** *or* **STP** *abbr. for* standard temperature and pressure.

straight-chain describing any chain of carbon atoms in which none of the carbon atoms is directly bonded to more than two other carbon atoms.

strain **1** a group of related individuals having certain characters that distinguish the members from other such groups within the same species or variety; a race. **2** a line of organisms descended or derived from a particular ancestral individual. **3** *(in physics)* the temporary or permanent deformation of a body resulting from an applied stress.

streptavidin a tetrameric biotin-binding protein (subunit M_r 14 500), produced by *Streptomyces avidinii*, that binds up to four molecules of **biotin** per molecule. It is used in enzyme-linked immunosorbent assay (ELISA), radioimmunoassay, immunocytochemistry, and protein blotting. It is also used to detect DNA probes that contain bound biotin. The streptavidin may be labelled with **FITC**, gold, peroxidase, or another agent. Alternatively, a biotin-labelled detection system (such as alkaline phosphatase) can be bound to streptavidin through another of its biotin-binding sites. Streptavidin has the advantage over **avidin** of having a near-neutral isoelectric point (7.25–7.45), with consequently less nonspecific binding. *See also* **biotinylation**.

streptidine 1,3-diguanido-2,4,5,6-cyclohexanetetrol; the non-carbohydrate component of **streptomycin**.



streptobiosamine 5-deoxy-2-*O*-[2-deoxy-2-(methylamino)-α-L-glucopyranosyl]-3-*C*-formyl-L-lyxose; a disaccharide component of **streptomycin**, containing **streptose** and *N*-methylglucosamine.



Streptococcus a genus of Gram-positive, facultatively or obligately anaerobic cocci or coccoid bacteria that produce **streptokinase**, **streptolysin**, and **streptodornase**.

streptodornase any of at least four deoxyribonucleases produced by streptococci. They have the characteristics of **deoxyribonuclease I** (EC 3.1.21.1), cleaving DNA to 5′-phosphodinucleotide and 5′-phosphooligonucleotide end-products. [From streptococcal deoxyribonuclease.]

streptokinase a noncatalytic protein secreted by certain streptococci that binds to and activates **plasminogen, thus converting it** to plasmin, which in turn lyses fibrin clots. It has been used therapeutically after heart attacks and strokes. It shows no sequence similarity to staphylokinase.

streptolydigin an antibiotic, derived from *Streptomyces lydicus*, that is particularly potent against anaerobes and some Gram-positive aerobes. It inhibits **RNA polymerase, thereby** reducing the rate of transcription, and slowing the rate of phosphodiester bond formation without affecting the fidelity of transcription. This contrasts with **rifampicin**, which inhibits initiation. *Compare* **rifamycin**.



streptolysin either of two **hemolysins** produced by certain streptococci (particularly of group A). **Streptolysin-O** (oxygen-sensitive) is produced in serum-free medium. Its hemolytic activity is destroyed by oxygen (but restored by certain mild reducing agents, e.g. 2-mercaptoethanol) and inhibited by free cholesterol. It is immunogenic, the level of circulating antibody (**antistreptolysin-O**, ASO) being useful in the diagnosis of streptococcal infections. Streptolysin-O can also lyse lysosomes. It resembles O-toxin of *Clostridium perfringens*, and can be used as an agent to permeabilize cells. **Streptolysin-S** (serum-dependent) is oxygen-insensitive and its production is promoted by serum proteins. Its hemolytic activity is inhibited by phosphatidyl ethanolamine at low concentration. It is nonimmunogenic, and is also toxic to leukocytes.

Streptomyces a genus of filamentous, spore-forming, Gram-positive bacteria that are largely responsible for the 'earthy' smell of soil but are chiefly remarkable for the diversity of secondary metabolites that they produce, including clinically useful antibiotics, e.g. **streptomycin**. They are amenable to genetic manipulation with many plasmid and phage vectors; this provides a unique opportunity for overexpression and for the design and synthesis of novel and 'hybrid' antibiotics. *See also* **streptomycete**.

streptomycete strictly, any member of the bacterial genus ***Streptomyces***. However, the term may include certain related types, including *Streptoverticillum* spp.

streptomycin an **aminoglycoside antibiotic** produced by the soil bacterium *Streptomyces griseus*, having a relatively broad spectrum of activity but particularly active against mycobacteria (especially *Mycobacterium tuberculosis*), enterobacteria, and staphylococci. It binds the 30S ribosomal subunit and distorts the A site (**aminoacyl site**), thereby causing miscoding or prevention of binding of aminoacyl-tRNA. The components of streptomycin are **streptidine**, **streptose**, and *N*-methyl-L-glucosamine.



streptose L-streptose; 5-deoxy-3-*C*-formyl-L-lyxose; a component of **streptomycin** and **streptobiosamine**.



streptovaricin any **ansamycin** antibiotic obtained from *Streptomyces spectabilis*. *Compare* **rifamycin**.



Streptovaricin	W	X	Y	Z	R
A	OH	OH	Ac	OH	$COOCH_3$
B	H	OH	Ac	OH	$COOCH_3$
C	H	OH	H	OH	$COOCH_3$
D	H	OH	H	H	$COOCH_3$
E	H	O=	H	OH	$COOCH_3$
G	OH	OH	H	OH	$COOCH_3$
J	H	OAc	H	OH	$COOCH_3$
K	OH	OAc	H	OH	$COOCH_3$

streptozocin 2-deoxy-2-(3-methyl-3-nitrosoureido)-D-glucopyranose; a broad-spectrum antibiotic, antineoplastic, and diabetogenic substance isolated from *Streptomyces achromogenes*. It has a rapid and specific cytotoxic effect on the B cells in pancreatic islets, and is used to induce experimental diabetes in animals and for chemotherapy of insulinoma or other islet-cell neoplasms in humans. It acts as a methylating agent for DNA.



α-D-streptozocin

stress-activated protein kinase (*abbr*.: SAPK) *an alternative name for* **JNK**.

stress-associated protein kinase *abbr*.: SAPK; *an alternative name for* **JNK**.

striated muscle muscle in which the **thick filaments** and **thin filaments** are arranged in microscopically visible bands producing a striped appearance. Such an arrangement is typical of skeletal muscle and cardiac muscle. *Compare* **smooth muscle**. *See also* **sarcomere**.

strict aerobe *see* **aerobe**.

strict anaerobe *see* **anaerobe**.

stringency *(in molecular biology)* the rigour with which the ability of complementary DNA sequences to recognize each other (and thus to hybridize) is tested. It is affected by temperature, ionic strength, and the presence of destabilizing agents such as formamide. As temperature is increased it becomes less likely that more distantly related sequences will hybridize; hence, high stringency is associated with high temperature. Low ionic strength also gives high stringency.

stringent very rigorous. *See also* **stringency**, **stringent control**, **stringent plasmid**, **stringent response**.

stringent control a mechanism of control of plasmid replication whereby the plasmid is replicated only once for each time the chromosome is replicated, thus regulating the plasmid copy number.

stringent factor a protein associated with ribosomes, and encoded by the gene ***relA***, that is associated with the **stringent response**. It is an enzyme that donates a pyrophosphate group to 3′ of either 5′-GTP or GDP to produce pppGpp and ppGpp, which probably act as allosteric modulators mediating the stringent response. *See also* **relaxed mutant**, **spoT**.

stringent plasmid a plasmid that has a limited number of copies per cell.

stringent response a response by bacteria to poor growth conditions (e.g. lack of amino acids) in which the cell shuts down protein synthesis and other metabolic activity. *See also* **relaxed mutant**, **stringent factor**.

strip 1 to remove adherent, admixed, or combined substances or material from a fundamental, underlying, or required substance or structure. **2** *(in molecular biology)* **a** to remove polysomes from rough endoplasmic reticulum *in vitro* to produce **stripped membranes** (*see* **degranulation** (def. 2)). **b** to remove ribosomal proteins from a ribosome to produce a **core particle**. **c** to remove the amino acid from an aminoacyl-transfer RNA molecule to produce **stripped transfer RNA**. **d** to remove hybridized **probe** (def. 3) from a **transfer membrane** prior to reprobing. **3** *(in biochemistry)* to remove endogenous 2,3-bisphosphoglycerate from a hemoglobin solution to produce **stripped hemoglobin**. **4** to remove liquid components from a gaseous mixture.

stripped hemoglobin a hemoglobin solution from which endogenous 2,3-bisphosphoglycerate has been removed, e.g. by gel filtration, or dialysis at high NaCl concentrations.

stripped membrane rough endoplasmic reticulum from which polysomes have been removed *in vitro* by treatment with EDTA.

stripped transfer RNA a molecule of aminoacyl-transfer RNA from which the amino acid has been hydrolytically removed.

stRNA *abbr. for* small temporal RNA; a form of microRNA (*see* **miRNA**) that is ≈22 nt long and derived from dsRNA by the endonuclease activity of **Dicer** and **Argonaute**. It is highly conserved in certain animals and controls developmental events.

stroma (*pl.* **stromata**) **1** fibrous connective tissue or other intercellular material that forms the structural framework of an organ, as opposed to the functional tissue (parenchyma). **2** the spongy framework of protein strands within a red blood cell in which the hemoglobin is packed. **3** *(in botany)* the space enclosed by the double membrane of a **chloroplast** but excluding the thylakoid space. It contains DNA, ribosomes, and some temporary products of photosynthesis. **4** *(in mycology)* a mass of interwoven hyphae in which fruiting bodies (perithecia) develop. —**stromal** *adj.*

stromelysin EC 3.4.24.17; *other names*: matrix metalloproteinase-3 (*abbr*.: MMP-3); transin-1; an enzyme that catalyses the degradation of fibronectin, laminin, and some gelatins and collagens. Zn^{2+} and Ca^{2+} are cofactors. It is a glycoprotein of the extracellular matrix. Stromelysin 1 is secreted by fibroblasts; stromelysin 2 is secreted by keratinocytes.

strong acid an **acid** that remains ionized except at the lowest pH values, i.e. one that has a large **acid dissociation constant**.

strong base a **base** that remains ionized except at the highest pH values, i.e. one that has a large **basic dissociation constant**.

strophanthin a highly toxic glycoside mixture produced by *Strophanthus kombe*, with actions similar to those of **digoxin** and **ouabain**.

structural gene any gene that carries the genetic information for the structure of a protein. One or more structural genes may be contained in an **operon**. *Compare* **regulator gene**.

structural genomics the systematic effort to determine the 3D structures of all proteins encoded in complete genomes.

structural polysaccharide any polysaccharide of plant cell walls that performs a structural function. There are three solubility classes: **pectins**, extractable with dilute acid; **hemicelluloses**, extractable with aqueous alkali; and **microfibrillar polysaccharides**.

structure-based alignment the alignment of protein sequences made on the basis of structure comparison. Structure-based alignments do not always respect patterns of sequence conservation and may consequently differ from sequence alignments. They should not be considered the 'right' answer (or 'gold standard') – they merely reflect a different model of protein comparison, usually used for different purposes from those of sequence-based alignments. *See* **structure comparison**.

structure classification database a database in which protein structures are classified according to their geometrical and evolutionary similarities. Structures tend to be classified at the level of their individual domains, but multidomain structures can also be classified into evolutionary families and superfamilies. Examples of such databases include SCOP (structural classification of proteins) and CATH (class architecture topology homology).

structure comparison the comparison of protein folds by superposition of equivalent alpha or beta carbon atom coordinates. Equivalence of positions is largely determined by comparing the similarities of the properties or relationships of the residues or secondary structures. The quality of the structural superposition is measured in terms of the root mean square deviation (RMSD) (typically 4Å or less for similar folds). Structure comparison is important, e.g., for detecting relationships between proteins that are not evident at the sequence level owing to their extreme divergence.

structure database a database that houses the 3D structural coordinates of biological macromolecules, as determined by X-ray crystallography, nuclear magnetic resonance (NMR), electron microscopy and/or molecular modelling. The PDB (Protein Data Bank) is the global repository for macromolecular structure information of the RCSB (Research Collaboratory for Structural Bioinformatics). The MSD (Macromolecular Structure Database), derived in part from the PDB, is the structure database of the European Bioinformatics Institute (EBI). The MMDB (Molecular Modelling Database) is the NCBI's (National Center for Biotechnology Information) subset of 3D structures obtained from the PDB, excluding theoretical models. The PDBj (Protein Data Bank Japan) is the subset of PDB from the Institute for Protein Research in Osaka University.

structure factor a parameter describing the scattering of electromagnetic radiation (e.g. X-rays) by an electron. It is the ratio of the radiation scattered by any real sample to that scattered by a single electron at the origin.

strychnine a bitter alkaloid obtained from seeds of the Indian tree *Strychnos nux-vomica*. It is highly toxic, and is sometimes used to poison moles, rodents, and other vermin. It causes convulsions by antagonizing the inhibitory transmitter, glycine, in the spinal cord (*see* **glycine receptor**). *See also* **brucine**.



STS *abbr. for* sequence-tagged site.

Stuart factor *or* **Stuart–Prower factor** *an alternative name for* factor X; *see* **blood coagulation**. [After a Mr Stuart, in whom the deficiency was first described.]

Student's *t* test a statistical test, based on a distribution due to William Sealy Gosset (1876–1937) writing in 1908 under the pseudonym 'Student', that can be applied to small samples of data, *x*. In this distribution *t* depends only on the sample size, *N*, and not on the variance of the population; as *N* increases, the distribution curve of *t* approaches a normal distribution curve more closely.

STX *abbr. for* saxitoxin.

sU *symbol for* a residue of the ribonucleoside thiouridine (when the position of the thiol group in its thiouracil moiety is unspecified or unknown; alternative to S or Srd).

s^{2}U *symbol for* a residue of the ribonucleoside 2-thiouridine (alternative to ^{2}S).

s^{4}U *symbol for* a residue of the ribonucleoside 4-thiouridine (alternative to ^{4}S).

sub *jargon term for* **subculture** (def. 1).

sub+ *prefix* **1** beneath, under, at the bottom (of). **2** immediately below in order, rank, or status; secondary. **3** less than, partial(ly), imperfect(ly). **4** in place of. **5** denoting a subordinate part or subdivision of a whole. **6** *(in chemical nomenclature)* designating a compound that contains less than the usual proportion of a specified element; e.g. carbon suboxide, C_2O_3. *Compare* **infra+**, **super+**.

subcellular describing organelles, functional units, or other components that are found within cells or derived from cells.

subcellular organelle a pleonasm that is commonly used to describe **organelles** (which by definition are subcellular).

subclone to clone into a new vector a subfragment of part of a larger cloned DNA, after excising the required fragment using restriction endonucleases.

subculture **1** to prepare a fresh culture from a small sample of an existing culture. **2** a culture prepared in such a way.

subcutaneous *abbr.*: s.c.; below the skin.

suberin the polymeric substance that covers the epidermal cell layer in the underground parts of plants (e.g. roots and tubers), and in stem epidermis, cork cells of the periderm, and surfaces of wounded cells. It is a polyester containing very-long-chain ω-hydroxy fatty acids and dicarboxylic acids, and phenolics such as *p*-coumaric and ferulic acids. The core is lignin-like and has attached long-chain hydrocarbons.

sublime to vaporize from the solid without passing through a liquid phase. —**sublimation** *n.*

submaxillaris protease an endopeptidase isolated from the submaxillary gland of mice. It cleaves Arg-|-Xaa bonds.

submaxillary relating to the region beneath the upper jaw (maxilla).

submaximal below the maximal.

submitochondrial particle any particle derived by disruption of mitochondria. *See* **H^+-transporting ATPase**, **complex I, II, III, IV**.

submolecular describing any chemical or chemical component that exists or functions at a lower level of complexity than that of intact individual molecules. The term may be used in reference to electrons, ions, free radicals, or other molecular fragments. *Compare* **supramolecular**.

subnatant **1** lying under. **2** a liquid lying under a **supernatant** or under solid material. *Compare* **infranatant**.

suboptimal below or failing to reach the optimal condition.

subsite a site, e.g. on a protein, that has a specific function within the overall function of a larger site.

substance K *see* **neurokinin A**.

substance K receptor *or* **neurokinin A receptor** *or* **NK-2 receptor** a G-protein-associated membrane receptor that binds substance K and mediates its intracellular effects by activating the **phosphatidylinositol cycle**.

substance P *abbr.*: SP; an 11-residue amide,

$$\text{H-Arg-Pro-Lys-Pro-Gln-Gln-Phe-Phe-Gly-Leu-Met-NH}_2,$$

found in most tissues of the mammalian body but especially in nervous tissue (both central and peripheral) and in gut tissues. It also occurs in the central nervous system of many other vertebrtates. Derived from **protachykinin β precursor**, it is a **tachykinin**; it causes hypotension and vasodilation, and stimulates contraction of the intestine and secretion of saliva. *See also* **tachykinin receptor**.

substituent group *or* **substituent** *(in organic-chemical nomenclature)* any atom or **group** (def. 1) that has replaced or can be considered to have replaced (i.e. been substituted for) a hydrogen atom in a parent molecule; for bivalent or tervalent groups there are corresponding replacements of two or three hydrogen atoms.

substitute cysteine accessibility method *see* **SCAM**.

substituted mechanism a mechanism of an enzyme reaction in which a substrate reacts with the enzyme to produce a modified enzyme and a product. The modified enzyme then reacts with a second substrate to produce a second product and regenerate the enzyme, e.g.

$$E + S_1 \rightleftharpoons E^* + P_1,$$

then

$$E^* + S_2 \rightleftharpoons E + P_2,$$

where E is the enzyme, E* the modified enzyme, S_1 and S_2 the substrates, and P_1 and P_2 the products.

substitution **1** *(in genetics)* a type of point mutation in which one base pair is replaced by another. In a **transition**, a base is replaced by another of the same chemical class (e.g. a purine by a purine, or pyrimidine by another pyrimidine); in a **transversion**, a base is replaced by one of a different type (e.g. purine by a pyrimidine, or vice versa). **2** *(in sequence analysis)* the replacement of a nucleotide or amino acid residue by another at a given position in an alignment. For protein sequences, if the aligned residues have similar physicochemical properties, the substitution is said to be conservative (e.g. Ile and Leu).

substitution matrix *or* **amino acid exchange matrix** *or* **mutation matrix** a symmetrical 20×20 matrix containing values proportional to the probability that amino acid *i* mutates to amino acid *j* for all pairs of amino acids; the diagonal denotes the odds for self-conservation. The most widely used mutation or substitution matrices are the PAM (point accepted mutation) and BLOSUM (Blocks substitution matrix) series. PAM matrices were calculated from aligned sets of closely related sequences, and larger evolutionary distances were extrapolated from the original 1-PAM matrix. BLOSUM matrices were derived from alignments of larger, more diverse sets of sequences. Where the alignments are large enough to be statistically significant, the resulting matrices should reflect the true probabilities of mutations occurring during a particular evolutionary period.

substitution reaction the replacement of a substituent (normally hydrogen), usually at a carbon atom, by any other group.

substrate **1** a substance that is acted upon, especially by an enzyme; a molecule or structure whose transformation is catalysed by an enzyme. **2** *or* **substratum a** the base upon which an organism grows or lives, e.g. soil or rock. **b** the material upon which a microorganism grows or is placed to grow.

substrate activation the increase of an enzyme's activity by its substrate by an **allosteric** mechanism. *Compare* **substrate inhibition**.

substrate cycle interconversion of reactant and product by two enzymes, one of which (A) catalyses the reaction in one direction while the second enzyme (B) catalyses the reaction in the opposite direction, e.g.

$$\text{fructose 6-phosphate} \ldots \underset{B}{\overset{A}{\rightleftharpoons}} \text{f fructose 1,6-bisphosphate.}$$

As **flux** (def. 3) (i.e. the rate of reaction catalysed by A minus rate of reaction catalysed by B) through a system varies, the rate of each enzyme reaction may vary independently with concomitant changes in cycling rate. The existence of a substrate cycle increases sensitivity of control, since even if rates of forward and reverse reaction are high, changes in one or both may make relatively larger changes to flux; e.g. if rate of A = 9 and rate of B = 8, then flux = 1; if rate of A doubles to 18 and rate of B remains 8, then flux = 10 (i.e. increases tenfold).

substrate dissociation constant *or* **substrate constant** *symbol* K_s; the parameter of an enzymatic reaction that is the equilibrium (dissociation) constant for the reaction ES = E + S; i.e. $K_s = [E][S]/[ES]$.

substrate inhibition the inhibition of an enzyme's activity by its substrate by an **allosteric** mechanism. *Compare* **substrate activation**.

substrate-level phosphorylation the formation of ATP (or GTP) in a coupled reaction that is not linked to an electron transport system, e.g. coupled to the deacylation of succinyl coenzyme A or the conversion of 3-phosphoglyceroyl phosphate to 3-phosphoglycerate.

substrate-site hypothesis a hypothesis for the control of insulin release from pancreatic islet B cells by glucose. It postulates that the glucoreceptor is either a carrier transporting glucose into the cell or an enzyme phosphorylating glucose, and the signal for insulin release is a metabolite in the pathway of metabolism of glucose in the B cell. *Compare* **regulator-site hypothesis**.

substratum (*pl.* **substrata**) **1** any layer (stratum) or structure that lies beneath another, or that forms a base or underlying support for something else. **2** *an alternative term for* **substrate** (def. 2).

subtligase any engineered derivative of **subtilisin** that efficiently ligates peptides. The two mutations converting the peptidase, subtilisin, to a ligase involve Ser^{221} to Cys and Pro^{225} to Ala.

subtilin *or* **subtilin C** an antibiotic produced by *Bacillus subtilis* and active against Gram-positive bacteria, *Neisseria* spp. (*N. catarrhalis*, *N. gonorrhoeae*), and some pathogenic fungi.

subtilisin EC 3.4.21.62; a bacterial **serine endopeptidase** enzyme from *Bacillus subtilis* and other *Bacillus* spp. (e.g. commercially from *B. licheniformis*). It has broad specificity for peptide bonds, with preference for a large uncharged residue at P1 (*see* **peptidase P-sites**) and low activity for glutamyl residues; it hydrolyses peptide amides. The enzyme has similar active-site geometry to the trypsin family but otherwise no homology. *See also* **Nagarse proteinase**.

subtractive cloning a technique for isolating genes expressed in one cell population but not in another. Nucleic acid (typically first-strand cDNA) from which one seeks to isolate differentially expressed genes is hybridized to a large excess of nucleic acid (typically poly(A)$^+$ mRNA) from a source that does not express those genes. Only sequences common to the two sources will hybridize and these are removed (typically by chromatography on hydroxyapatite) leaving a pool of nucleic acid enriched in the sequences of interest. This pool can be used to make a cDNA library from which clones of interest may be isolated.

subtractive hybridization a method to identify DNA or RNA that is present in one sample but not in others, and forming the basis of **subtractive cloning**.

subtrahend *(in mathematics)* the number to be subtracted from another number (the minuend).

subunit any polypeptide component within a protein, or other distinct biochemical entity, whether identical to or different from any other components, that is separable from such other components without rupture of covalent bonds. The term is sometimes used in a more restricted sense as referring to any chemically or physically identifiable submolecular entity within a protein, whether identical to, or different from, other components.

subunit-exchange chromatography a form of chromatography in which protein subunits are immobilized on a solid matrix and allowed to interact with protein subunits in solution. Quantification of subunit exchange between the matrix and solution may be used in analysing the association–dissociation properties of the protein system. The method also provides a powerful, specific purification method.

Suc– *symbol for* **succinyl** (def. 1).

–Suc– *or* **Suc<** *symbol for* **succinyl** (def. 2).

succinamic acid *a trivial name for* 3-carbamoylpropanoic acid, the monoamide of succinic acid.

succinamide *a trivial name for* butanediamide, the diamide of succinic acid.

succinate **1** *a trivial name for* butanedioate; ethanedicarboxylate; the dianion of succinic acid. It is an important intermediate in metabolism and a component of the **tricarboxylic-acid cycle**. **2** any mixture of free succinic acid and its mono- and dianions. **3** any salt or ester of succinic acid.

succinate–CoA ligase (GDP-forming) EC 6.2.1.4; *other name*: succinyl-CoA synthetase (GDP-forming); an enzyme of the tricarboxylic-acid cycle that catalyses the formation of succinyl-CoA from GTP, succinate, and CoA with release of GDP and orthophosphate.

succinate dehydrogenase EC 1.3.99.1; *systematic name*: succinate:(acceptor) oxidoreductase; *other names*: fumarate reductase/dehydrogenase. A bacterial enzyme, or a degraded entity from succinate dehydrogenase (ubiquinone), a major component of mitochondrial complex II (*see* **respiratory complex**). It catalyses the oxidation of succinate by an acceptor to form fumarate and a reduced acceptor; it does not react with ubiquinone or free FAD.

succinate dehydrogenase (ubiquinone) EC 1.3.5.1; *systematic name*: succinate:ubiquinone oxidoreductase; *other name*: succinic dehydrogenase. An enzyme that catalyses the oxidation of succinate by ubiquinone to form fumarate and ubiquinol. It is an iron–sulfur flavoprotein (FAD), containing at least four different subunits: a flavoprotein, an iron–sulfur protein, and two hydrophobic anchor proteins, one of which is cytochrome b_{556}. It is located in the mitochondrial inner membrane, where it is a major component of complex II of the respiratory chain.

succinate-semialdehyde dehydrogenase EC 1.2.1.24; a homotetrameric enzyme of mitochondrial matrix that catalyses the reaction:

$$\text{succinate semialdehyde} + \text{NAD}^+ + \text{H}_2\text{O} = \text{succinate} + \text{NADH}.$$

Succinate semialdehyde can undergo transamination to form γ-aminobutyric acid. However, the transaminase primarily functions to convert γ-aminobutyrate to succinate-semialdehyde, which is then converted to succinate by succinate-semialdehyde dehydrogenase in the catabolism of γ-aminobutyrate. Mutation results in 4-hydroxybutyratic aciduria, which is associated with retarded mental, motor, and language development. *See also* **4-aminobutyrate transaminase**.

succinic dehydrogenase *see* **succinate dehydrogenase (ubiquinone)**.

succinimide *a trivial name for* butanimide; 2,5-pyrrolidinedione; the imide of succinic acid. For structure *see* **+imide**.

succinoglycan *or* **EPS I** an acidic exopolysaccharide produced by *Rhizobium* spp. that is important for invasion of the nodules that the bacteria elicit on their host, *Medicago sativa.* Succinoglycan is a high-molecular-weight polymer composed of repeating octasaccharide subunits. These subunits are synthesized on membrane-bound isoprenoid lipid carriers, beginning with a galactose residue followed by seven glucose residues, and modified by the addition of acetate, succinate, and pyruvate.

succinyl **1** *(in biochemistry) symbol*: Suc–; the univalent acyl group 3-carboxypropanoyl, HOOC–$[CH_2]_2$–CO–, derived from succinic acid by loss of one hydroxyl group. **2** *(in chemistry) symbol*: –Suc– *or* Suc<; the bivalent acyl group butanedioyl, –CO–$[CH_2]_2$–CO–, derived from succinic acid by loss of both hydroxyl groups.

succinylation the introduction of one or more **succinyl** (def. 1) groups into a substance by acylation, either chemically, e.g. with succinic anhydride, or enzymically, e.g. with succinyl-coenzyme A. It is used to acylate a protein's free lysine (and other) amino groups to change their charge at neutral pH from positive to negative and to render adjacent peptide bonds resistant to hydrolysis by trypsin; it can also cause disaggregation of a multimeric protein. The reaction occurs readily at pH 7–10 (at 0–25 °C), but it is irreversible, unlike the otherwise similar processes of **citraconylation** and **maleylation**, and so is of limited usefulness in protein sequence work.

succinylcholine chloride *see* **suxamethonium**.

succinyl-CoA synthetase (GDP-forming) *see* **succinate–CoA ligase (GDP-forming)**.

***O*-succinylhomoserine** an intermediate in methionine biosynthesis in plants and bacteria. It is formed by succinylation (utilizing succinyl-CoA) of homoserine. It reacts with cysteine with loss of succinate to form cystathionine.



sucralose 4,1′,6′-trichloro-4,1′,6′-trideoxy-*galacto*-sucrose; a chlorinated sucrose, tasting sweeter than sucrose itself.



sucrase **1** *recommended name*: sucrose α-glucosidase; EC 3.2.1.48; *systematic name*: sucrose α-D-glucohydrolase; an α-D-glucosidase-type enzyme from intestinal mucosa that hydrolyses sucrose and maltose. It is also known as **sucrase–isomaltase** by virtue of being an oligo-1,6-glucosidase, EC 3.2.1.10, displayed towards isomaltose. **2** any bacterial or plant enzyme of sub-subclass EC 2.4.1 (hexosyltransferases) that synthesizes homopolysaccharides from sucrose by transfer of either its fructose moiety or its glucose moiety respectively to a fructan or to a glucan, with release of the opposing moiety as free D-glucose or D-fructose. The recommended names are formed by adding 'sucrase' to a prefix indicating the polysaccharide product. These enzymes include: (1) **amylosucrase**; EC 2.4.1.4; *other name*: sucrose–glucan glucosyltransferase; *systematic name*: sucrose:1,4-α-D-glucan 4-α-D-glucosyltransferase; it synthesizes amylose; (2) **dextransucrase**; (3) **inulosucrase**; EC 2.4.1.9; *other name*: sucrose 1-fructosyltransferase; *systematic name*: sucrose:2,1-β-D-fructan 1-β-D-fructosyltransferase; it synthesizes inulin; and (4) **levansucrase**; EC 2.4.1.10; *other name*: sucrose 6-fructosyltransferase; *systematic name*: sucrose:2,6-β-D-fructan 6-β-D-fructosyltransferase; it synthesizes levan.

sucrase–isomaltase *see* **oligo-1,6-glucosidase**.

sucrase–isomaltase deficiency *see* **oligo-1,6-glucosidase**.

sucrose *or* **saccharose** *the trivial name for* *O*-β-D-fructofuranosyl-(2→1)-α-D-glucopyranoside; a sweet-tasting, nonreducing disaccharide. It is usually isolated industrially in crystalline form from sugar cane, *Saccharum officinarum,* or from sugar beet, *Beta vulgaris.*



sucrose gradient a density gradient that consists of different concentrations of sucrose layered in a centrifuge tube. It is used to separate molecules or particles on the basis of their sedimentation coefficients. *See also* **isopycnic centrifugation**.

sucrose-phosphate synthase EC 2.4.1.14; *systematic name*: UDPglucose:D-fructose-6-phosphate 2α-D-glucosyltransferase; *other names*: UDPglucose–fructose-phosphate glucosyltransferase; sucrosephosphate–UDP glucosyltransferase. An enzyme that catalyses a reaction between UDPglucose and D-fructose 6-phosphate to form sucrose 6-phosphate and UDP.

sucrose phosphorylase EC 2.4.1.7; *systematic name*: sucrose:orthophosphate α-D-glucosyltransferase; *other name*: sucrose glucosyltransferase. An enzyme that catalyses the phosphorylysis of sucrose to D-fructose and α-D-glucose 1-phosphate.

sucrose synthase EC 2.4.1.13; *systematic name*: UDP glucose:D-fructose 2α-D-glucosyltransferase; *other names*: UDPglucose–fructose glucosyltransferase; sucrose–UDP glucosyltransferase. An enzyme that catalyses a reaction between UDPglucose and D-fructose to form sucrose and UDP.

Sudan a family of dyes that are soluble in organic solvents and are used for staining lipids. **Sudan Red** is the 2,2′-demethyl analogue of **Oil Red O**. **Sudan Black B** is used for staining chromosomes, Golgi apparatus, and leukocyte granules.

suffix tree a data structure that allows rapid solution of problems involving character strings (sequences) and facilitates substring searches. The tree is built by removing the first character of a string, storing the resulting suffix, removing the first character of the result, storing this, and so on, until the result is a single character.

sugar any, usually sweet, soluble disaccharide or small oligosaccharide carbohydrate. More specifically it is applied to **sucrose**, the sugar of commerce. The name is sometimes used as a synonym for **carbohydrate**. *See also* **beet sugar**, **blood sugar**, **cane sugar**, **corn sugar**, **fruit sugar**, **grape sugar**, **malt sugar**, **milk sugar**, **mushroom sugar**, **reducing sugar**.

sugar acid any **aldaric acid**, **aldonic acid**, or **uronic acid**.

sugar alcohol *an old name for* **alditol**.

sugar beet the plant *Beta vulgaris*, which has a large root with a high sugar content, for which it is extensively cultivated.

sugar transporter any of various families of transmembrane proteins responsible for sugar transport into cells. **GTR1** causes facilitated diffusion of glucose, whereas XylE protein in *Escherichia coli* acts as an H^+–xylose symporter (*see* ***xylE***). Both belong to the 12-transmembrane domain superfamily. *See* **glucose transporter, PTS.**

suicide enzyme *see* **suicide repair (of DNA)**.

suicide inhibitor a type of enzyme inhibitor that is relatively unreactive and becomes reactive only after interaction with the enzyme's active site. *See also* **photosuicide inhibitor**.

suicide repair (of DNA) a response in bacterial and mammalian cells to exposure to a nontoxic alkylation dose. Such exposure causes the rapid induction of enzymes that remove the ***O*^{6}-methylguanine** formed by the alkylating agent. In this process the methyl group is transferred to the enzyme, which is thereby inactivated (i.e. it is a **suicide enzyme**).

suicide substrate 1 a substrate that causes an enzyme to be modified in a way that permanently inactivates it. **2** a compound that is converted by a metabolic pathway into an inhibitor of the pathway, as with the conversion of fluoroacetate to fluorocitrate. If the pathway is of sufficient importance, the cell thereby 'commits suicide'. *See also* **lethal synthesis**.

sulfa drug any **sulfonamide** compound that is clinically useful in the treatment of bacterial infections.

sulfamethoxazole 4-amino-*N*-(5-methyl-3-isoxalolyl)benzenesulfonamide; a **sulfonamide** antibacterial agent. As a mixture with **trimethoprim** it has the name **co-trimoxazole** (*proprietary names*: Bactrim; Septrim).

sulfane a chain of divalent sulfur atoms, as in hydrogen per-sulfide (HSSH) or polysulfanes (H_2S_x ; e.g. H_2S_5 is pentasulfane).

sulfanilamide *p*-aminobenzenesulfonamide; *see* **sulfonamide**.

sulfatase *see* **arylsulfatase**.

sulfate *or (esp. Brit.)* **sulphate** the anion SO_4^{2-}.

sulfate adenylyltransferase EC 2.7.7.4; *other names*: sulfate adenylate transferase; ATP-sulfurylase; sulfurylase; an enzyme that catalyses the formation of **adenosine 5′-phosphosulfate** (adenylylsulfate) from ATP and sulfate with release of pyrophosphate.

sulfatide a **galactosyl cerebroside** with a sulfate radical esterified at the 3′ position of the galactose moiety. Sulfatides are formed by **galactosylceramide sulfotransferase**.

sulfatide lipidosis *an alternative name for* **metachromatic leukodystrophy**.

sulfation factor *an alternative name for* **somatomedin**.

sulfenic acid a compound having the structure RSOH (e.g. cysteine sulfenic acid), in which the sulfur is oxidized by addition of one oxygen atom. *Compare* **sulfinic acid**.

sulfhemoglobin any of a group of poorly characterized derivatives of **hemoglobin**, often formed *in vivo* together with ferrihemoglobin. They are incapable of carrying oxygen and cannot be converted back to hemoglobin.

sulfhydryl *or* **thiol** the chemical group –SH; it is found in the amino acid **cysteine** and in other molecules. Two sulfhydryls can be oxidized to a disulfide bond, –S–S–.

sulfinic acid a compound having the structure RS(=O)OH (e.g. cysteine sulfinic acid), in which the sulfur is oxidized by addition of two oxygen atoms. *Compare* **sulfenic acid**.

sulfite *or (esp. Brit.)* **sulphite** the anion SO_3^{2-}.

sulfite oxidase EC 1.8.2.1; the terminal enzyme in the degradation of sulfur-containing amino acids in animals. It catalyses the oxidation of sulfite to sulfate and is present in the mitochondrial intermembrane space in many tissues but not in blood or skeletal muscle. The crystal structure of the chicken-liver enzyme contains a domain for binding heme, another for molybdenum cofactor, and a third for dimerization. *See* **sulfite oxidase deficiency**.

sulfite oxidase deficiency a severe, frequently fatal, autosomal recessive human disease that presents with convulsions early after birth, encephalopathy, and accumulation and increased excretion of sulfite, thiosulfate, and *S*-sulfocysteine. It produces neuronal cell loss and demyelination, and results from various mutations that inactivate **sulfite oxidase**.

sulfite reductase *abbr.* SiR. **1 sulfite reductase (NADPH)** EC 1.8.1.2; *systematic name*: hydrogen sulfide:NADP$^+$ oxidoreductase; the enzyme responsible for interconversion of hydrogen sulfide and sulfite in plants and most bacteria. It catalyses the reduction of sulfite, e.g. released from **3′-phosphoadenosine 5′-phosphosulfate** by thioredoxin. The reaction is:

$$H_2S + 3\ NADP^+ + 3\ H_2O = \text{sulfite} + 3\ NADPH;$$

cofactors are FAD, FMN, and siroheme. In plants and most microorganisms the H_2S reacts with *O*-acetylserine to form cysteine and acetate. The enzyme also oxidizes H_2S to sulfite. **2 sulfite reductase** An enzyme, EC 1.8.7.1; *systematic name*: hydrogen-sulfide:ferredoxin oxidoreductase. In plants it is a siroheme containing iron–sulfur protein that catalyses the reaction:

$$\text{sulfite} + 6\ \text{reduced ferredoxin} = H_2S + 6\ \text{ferredoxin} + 3H_2O.$$

sulfmethemoglobin the complex formed by combination of sulfide with the ferric ion of **ferrihemoglobin** in poisoning by sulfide.

sulf(o)+ *or (esp. Brit.)* **sulph(o)+** of, or pertaining to, or containing a sulfur atom or group.

sulfoindocyanine *or (esp. Brit.)* **sulphoindocyanine** a fluorescent dye, such as **Cy3** and **Cy5**, used in labelling proteins and DNA.

sulfokinase *or* **aryl sulfotransferase or phenol sulfotransferase** EC 2.8.2.1; an enzyme that catalyses transfer of a sulfate radical from 3′-phosphoadenylylsulfate to a phenol to form an aryl sulfate.

sulfolipid any lipid containing sulfur, especially a **sulfatide**. *See also* **sulfonolipid**.

sulfonamide 1 the amide of a sulfonic acid; the sulfonamide group is $–SO_2–NH_2$. **2** *(in biology and medicine) or* **sulfa drug** any of a group of antibacterial substances derived from **sulfanilamide** (*p*-aminobenzenesulfonamide), many of which have a substituent on the amide nitrogen.



sulfanilamide

sulfonate an anion of a sulfonic acid, having the structure RS(=O)(O$^-$)2, in which the sulfur is oxidized by addition of one oxygen atom.

sulfone the oxidation product that results when one oxygen atom is added to sulfur bonded to two alkyl chains.

sulfonolipid *or* **plant sulfolipid** 1,2-diacyl-3-(6-sulfo-α-D-quinovosyl)-*sn*-glycerol; sulfoquinovosyldiacylglycerol (*abbr.*: SQDG); the only sulfolipid present in higher plants and the only known lipid with a sulfonic-acid linkage; the predominant fatty acid is α-linolenic acid. Sulfonolipid is localized in the chloroplasts, mainly in the membrane of the thylakoids.

sulfonylurea any oral hypoglycemic drug that contains a sulfonic acid–urea nucleus modified by chemical substitution. The group includes tolbutamide, chlorpropamide, gliburide, and glipizide. A sulfonylurea receptor is the regulatory subunit for the ATP-dependent K^+ channel (**KATP**) of the pancreatic B-cell plasma membrane. The drugs also bind intracellular proteins on membranes of secretory granules of these cells, which may mediate part of their effect.

sulfonylurea receptor 1 *abbr.*: SUR-1; an integral membrane protein of pancreatic B cells that binds sulfonylurea drugs with high affinity and regulates the function of ATP-sensitive K channel (*also called* K_{ATP}). It binds ATP and ADP, belongs to the ABC transporter family, and in hamster contains 1582 amino acids. Several mutations in SUR-1 have been associated with persistent hyperinsulinemic hypoglycemia of infancy (PHHI).

sulfoxide the oxidation product that results when two oxygen atoms are added to sulfur bonded to two alkyl chains.

sulfur *or (esp. Brit.)* **sulphur** *symbol*: S; a yellow nonmetallic element of group 16 of the IUPAC **periodic table**; atomic number 16; relative atomic mass 32.066. Its main oxidation states are –2, +4, and +6.

Sulfur exists in a number of forms including crystalline (rhombic, monoclinic, rhombohedral) and amorphous forms. The relative abundance of stable isotopes is: sulfur-32 (mass 31.972) 95.02%; sulfur-33 (mass 32.971) 0.75%; sulfur-34 (mass 33.968) 4.21%. There are two radioactive isotopes, **sulfur-35** and **sulfur-38**. Sulfur is important as a constituent of the amino acids methionine and cysteine, and as a constituent of **glutathione**. It also occurs in **sulfolipids**. Sulfate is the terminal electron acceptor for anaerobic respiratory metabolism in certain bacteria e.g. *Desulfovibrio* spp.

sulfur-35 the radioactive nuclide, $^{35}_{15}$S, with a mass of 34.969. It emits an electron (β^- particle, 0.167 MeV), no gamma radiation, and has a half-life of 87.4 days.

sulfur-38 the radioactive nuclide, $^{38}_{16}$S, with a mass of 37.971. It emits an electron (β^- particle, 3.0 MeV) and gamma radiation (1.94 MeV), and has a half-life of 2.87 h.

sulfurylase *see* **sulfate adenylyltransferase**.

sulph(o)+ *a variant spelling (esp. Brit.) of* **sulf(o)+**.

sum **1** the total value of a set of individual values. **2** to determine a sum.

sumatriptan 3-[(2-dimethylamino)ethyl]-*N*-methyl-1*H*-indole-5-methanesulfonamide; an agonist for 5-HT_{1D} receptors (*see* **5-hydroxytryptamine receptor**). It constricts cerebral blood vessels, and is used in the treatment of migraine and cluster headaches. *Proprietary name*: Imigran (succinate).

summation the determination of the **sum** (def. 1) of a series.

SUMO *abbr. for* small ubiquitin-related modifier; *other name*: sentrin; a ubiquitin-like protein that becomes conjugated by an isopeptide bond with several proteins (e.g. RanGAP1, PML, IκB in mammals). Human SUMO (101 amino acids) shares 18% sequence identity with ubiquitin, and a globular fold consisting of beta sheets wrapped around an alpha helix. Conjugation (**sumoylation**) is between Gly-97 (uncovered by removal of the C-terminal tetrapeptide by a SUMO-specific protease) and the side chain of a lysine in the target protein. It occurs predominantly in the nucleus and regulates nuclear transport, signal transduction, the stress response, and cell-cycle progression; it does not involve proteasomes. Deconjugation (**desumoylation**) is catalysed by SUMO-specific proteases.

sumoylation *see* **SUMO**.

SUMT *abbr. for S*-adenosyl-L-methionine:uroporphyrin-III *C*-methyltransferase (*see* **uroporphyrin-III *C*-methyltransferase**).

Sunday driver a mutation in *Drosophila* that mixes up intracellular traffic.

super+ *prefix* **1** above, over, at the top (of). **2** of greater size or extent, or of higher quality. **3** beyond the usual or normal standard; exceeding. **4** *(in chemical nomenclature)* designating a compound that contains more than the usual proportion of a specified element. *Compare* **sub+**, **supra+**.

superantigen an antigen with the ability to activate a large proportion (up to 20%) of T lymphocytes in a given individual through interaction with the variable domain of the β chain of the lymphocyte's antigen receptor. This contrasts with conventional foreign antigens the peptides of which, attached to the major histocompatibility complex (MHC), have to be specifically recognized by the T-cell receptor. With superantigens the specificity resides in the β chain of the receptor not the MHC peptides. This accounts for the fact that many more than usual T lymphocytes are activated. Superantigens are present in a number of bacteria and viruses; the best example is the *Staphylococcus* enterotoxin. Superantigens have been implicated in **autoimmunity**.

supercoil *or* **superhelix** *or* **coiled coil** the form of DNA that can be envisaged as resulting if a **duplex** were turned through a hairpin bend and the two duplex rails twisted one around the other. DNA *in vivo* generally is supercoiled, and as it has a closed structure, a supercoil may be envisaged as a rubber band twisted to a helical shape. In **negative supercoiling** the DNA twists around its axis in the opposite direction from the clockwise turns of the right-handed double helix; this allows relief of torsional pressure, and the DNA is said to be **underwound**. Twisting in the other direction (**positive supercoiling**) increases torsional pressure, winding the double helix more highly; the DNA is said to be **overwound**. **Superhelix density**, σ, is defined as the number of turns of the superhelix, τ, per turn of the duplex, β; i.e. $\sigma = \tau/\beta$ (β represents about 10 base pairs). **Linking number** is the number of times the duplex strands cross over each other (in projection onto a plane surface). The number of superhelical turns is called the **writhing number** (W).

supercritical fluid chromatography a technique that can be regarded as an extension of **gas–liquid (partition) chromatography** in which the mobile phase is a relatively dense gas such as CO_2 (or SF_6, NH_3, or Xe). The gas must be pumped (at pressures up to 6000 psi) through a capillary column that is coated with stationary phases similar to those used in gas chromatography. The system depends on the partition of the compounds being separated between the stationary and mobile phases and has the advantage that compounds with high boiling points partition appreciably into the gas phase at temperatures well below their boiling points so that such compounds can be separated at lower temperatures than with less dense gases.

superfamily any group of genes and their cognate proteins that are related usually by sequence homology.

superfold **1** a common fold found in nonhomologous proteins (e.g. TIM barrels). **2** *(sometimes) an alternative term for* **super-secondary structure**.

superfolding (*of proteins*) the formation of small domains, beyond the level of simple secondary structures, that are energetically stable and contribute as units to the full tertiary structure of a protein. They may consist of **alpha helices** or **beta sheets** or both. They may be formed during the early stages of protein folding, before the protein has fully folded. For example, **beta barrels** are **super-folds**.

superfusion **1** the pouring of a liquid onto or over something. **2** *(in physiology and medicine)* a technique in which blood, plasma, or other fluid is allowed to drip onto, or flow over, the surface of an organ or piece of tissue.

supergene a group of linked genes (*see* **linkage** (def. 1)) that are usually inherited as a unit.

superhelix *an alternative name for* **supercoil**.

superhelix density *see* **supercoil**.

superinfection the proliferation of one or more pathogenic microorganisms arising from the disturbance of a mixed population of microorganisms normally sustained at non-pathogenic levels by secretion of endogenous antibiotics. Such disturbance can be induced by administration of exogenous antibiotic agents.

superinfection inhibition interference with the entry or establishment of an entering plasmid by a resident plasmid.

supernatant **1** floating on the surface of a liquid or lying over something. **2** (*or* **supernate**) **a** liquid lying above another liquid, a sediment, or a settled precipitate. **b** the fluid phase that remains after removal of solid material by centrifugation. A **cell supernatant** is the fluid phase that remains after centrifugation of a cell homogenate at high speed (characteristically at 100 000 *g* for 30 min). *Compare* **infranatant**.

supernate *an alternative name for* **supernatant** (def. 2).

superoxide **1** the anion, O_2^-, formed by addition of one electron to **dioxygen**. **2** any compound containing the superoxide anion.

superoxide dismutase *abbr.*: SOD; EC 1.15.1.1; *systematic name*: superoxide:superoxide oxidoreductase; *other names*: cytocuprein; erythrocuprein; hemocuprein. Any of a group of metal-containing enzymes that bring about the **dismutation** of superoxide radicals to form dioxygen and hydrogen peroxide as follows:

$$O_2^{-}\bullet + O_2^{-}\bullet + 2H^+ = O_2 + H_2O_2.$$

It is important in removing the highly toxic superoxide radical. Some (e.g. those from *Neurospora*, yeast, erythrocytes, heart, peas) contain copper and zinc; others (e.g. those from *Escherichia coli*, *Streptomyces mutans*) contain manganese or iron. Eukaryotic cells have copper–zinc types in cytoplasm and manganese types in mitochondria. The copper–zinc types comprise a well-conserved family with four motifs.

Superscript *proprietary name for* a reverse transcriptase derived from Moloney murine leukemia virus (MMLV) and modified by protein engineering to have reduced RNase H activity.

super-secondary structure *or (sometimes)* **superfold** the arrangement of protein secondary structures into discrete folded units – e.g. beta barrels, β-α-β units, and Greek keys. *Compare* **superfold** (def. 1).

supported reagent any reagent linked to a **support medium**.

support medium any (usually solid or insoluble) medium to which a cell, reagent, or functional group can be attached.

suppression 1 *(in molecular biology)* the cancellation, or reversal of the effects, of one mutation by another mutation, except where the second mutation causes a single base change at the same point as an earlier **point mutation** (in which case the term **reversion** is used). In **intergenic suppression**, the effects of a mutation in one gene are reversed by a mutation in another gene, usually because the second gene codes for a mutant tRNA (*see* **frameshift suppressor**). In **intragenic suppression** a mutation is cancelled by a second mutation close to the first in the same gene, normally within the same triplet, giving rise to a codon that is compatible with translation to a functional protein product. As an example, if the first mutation changed AGT (leading to the RNA codon for Ser) to ATT (giving a nonsense codon), a suppressor mutation might change the triplet to ATA (giving the RNA codon for Tyr); if the change Ser to Tyr led to a functional protein, suppression would be achieved. *See also* **amber suppressor**, **ochre suppressor**, **opal suppressor**. **2** *(in immunology)* any attenuation of an immune response. The existence of a subpopulation of T cells, **suppressor cells**, is held to be responsible for attenuation of the effect of **helper cells**. A different mechanism is probably responsible for the reduction in antibody production arising from injection of antibody prior to administration of antigen. Allotype suppression refers to suppression of the production of one allotype (e.g. expression of the allotype inherited from the mother, and suppression of the allotype of the father).

suppressor cell *or* **suppressor T cell** *or* **T-suppressor cell** any **T lymphocyte** that inhibits (*see* **suppression** (def. 2)) the stimulation of the immune response by **helper cells**. Classically, suppressor cells belong to the **CD8$^+$** subset in the human. Induction of the suppressor function may derive from helper cells.

suppressor gene a gene that can reverse the effect of a specific type of mutation in another gene. *See* **suppression** (def. 1).

suppressor mutation a secondary mutation that totally or partially restores a function lost due to a primary mutation at another locus. *See* **suppression** (def. 1).

suppressor tRNA any species of **transfer RNA** (tRNA) that recognizes a **termination codon** in messenger RNA. It adds an amino-acid residue to what is normally the C terminus of a nascent polypeptide chain; hence termination of synthesis of the peptide is suppressed and a **readthrough** protein is consequently formed. Suppressor tRNA may occur naturally or be produced by mutagenesis.

supra+ *prefix* above, over, greater than. *Compare* **infra+**, **super+**.

supramolecular describing any chemical system or component thereof that exists and functions at a higher level of complexity than intact individual molecules. In biochemistry the term may refer to multienzymes, microtubules, organelles, biological membranes, viral envelopes, cell walls, ribosomes, or other cellular elements; hence, e.g., supramolecular assembly, supramolecular complex, supramolecular structure. *Compare* **submolecular**.

suprarenal gland *an obsolete term for* **adrenal gland**.

suprarenin *a former name for* adrenaline (i.e. **epinephrine**).

Sur *symbol for* a residue of the thiopyrimidine base **thiouracil**.

SURE *abbr. for* Stop Unwanted Rearrangement Events; a proprietary strain of *E. coli* developed to allow cloning of DNA sequences that cannot be cloned in other *E. coli* strains.

SURF1 *abbr. for* surfeit gene 1 product; one of the proteins encoded by a cluster of six housekeeping genes (locus at 9q34). It is targeted to the inner mitochondrial membrane, contains 300 amino acids and two transmembrane segments, and is required for normal activity of complex IV of the respiratory chain in humans. Mutations affect mostly the brain and produce **Leigh syndrome**.

surface-active agent *an alternative term for* **surfactant**.

surface concentration *see* **concentration** (def. 1).

surface plasmon resonance a phenomenon that occurs when light is reflected off thin metal films, which may be used to measure interaction of biomolecules on the surface. An electron charge density wave arises at the surface of the film when light is reflected at the film under specific conditions. A fraction of the light energy incident at a defined angle can interact with the delocalized electrons in the metal film (plasmon) thus reducing the reflected light intensity. The angle of incidence at which this occurs is influenced by the refractive index close to the *backside* of the metal film, to which target molecules are immobilized. If ligands in a mobile phase running along a flow cell bind to the surface molecules, the local refractive index changes, leading to a change in SPR angle which is proportional to the mass being immobilised. This can be monitored in real time by detecting changes in the intensity of the reflected light, producing a *sensorgram.*

surface-stress theory a theory that relates mechanical stress to enlargement of the bacterial cell wall during growth. The cell wall withstands stress from hydrostatic pressure by a stress-bearing, two-dimensionally linked peptidoglycan sacculus that surrounds the cell. During enlargement, enzymes that enlarge the wall must at the same time maintain the hydrostatic integrity of the cell by withstanding stress.

surface tension *symbol*: *Y or σ or γ*; the property that makes a liquid behave as if it had an elastic skin on its surface – at an interface with a gas or an immiscible liquid – as a result of intermolecular forces tending to pull the molecules in the surface into the interior of the liquid. It is defined as the force acting tangential to the surface on one side of a line of unit length in the surface, and is expressed in newtons per metre. It can also be defined as the work required to produce unit increase in surface area, expressed in joules per square metre.

surfactant *or* **surface-active agent** any substance, such as a **detergent** or an **emulsifier**, that can bring about a reduction of the **surface tension** of a liquid, allowing it to foam, to penetrate porous solids more easily, and to wet surfaces of nonporous solids or of immiscible liquids.

surfactant protein *abbr*.: SP; any of four proteins secreted by type II cells of alveoli and bronchial mucosa as constituents of **pulmonary surfactant**. SP-A and SP-D are **collectins**, having similar structures and serving mostly in defence against microorganisms. SP-B and SP-C are structurally unrelated and help stabilize the phospholipids of the secretion. SP-B is an amphipathic 79-residue polypeptide. SP-C is a hydrophobic 33–34-residue polypeptide. All are derived from larger precursors. Many mutations in the gene at 2p12-p11.2 for SP-B, and more rarely in the genes for the other proteins, are associated with respiratory distress syndrome of infants (especially in those born prematurely), and also in adults.

surfactin a surface-active antibiotic and nonimmunogenic hemolysin secreted by *Bacillus subtilis*. It consists of a nonapeptide (containing two residues each of L- and D-leucine) in cyclic depsipeptide linkage with *β*-hydroxy-*ω*-methylmyristic acid. It is classified in the TC system under the number 1.C.12.

surfeit gene *see* **SURF1**.

surrogate genetics a branch of molecular genetics in which DNA is modified *in vitro* and then reintroduced into a genetic system – the 'surrogate' system – e.g. by injection into *Xenopus* oocytes, by transfection of cells, or by the creation of transgenic animals. The effect of the modification on the expression of the gene provides insights into the role in the genetic system of particular base sequences.

surveyor substrate one of a system of fluorescent substrates designed to measure distances within the active centre of an enzyme and also to survey other aspects of the topography of the active centre during the catalytic event.

survivin a member of the Inhibitor of Apoptosis gene family implicated in regulation of cell division and suppression of apoptosis. It is over-expressed in human cancers, being concentrated in mitotic spindle. In normal tissue, survivin is expressed only during the development of the embryo and fetus, where it is believed to play a role in controlling apoptosis.

Sushi domain *or* **complement control protein module** *or* **short consensus repeat** a polypeptide domain of ~60 amino acids that contains disulfide bonds between the first and third, and second and fourth cysteines, as found in β_2 glycoprotein-1 of plasma, in complement proteins, and in **blood coagulation** factor XIII.

suspension culture the culture of cells in medium without adherence to a stationary substrate. Relatively few animal cell types are amenable to suspension culture (classically **HeLa cells** can be so grown). An intermediate situation utilizes beads to which the cells adhere; the beads can be maintained in suspension and collected by sedimentation

Su(var) *abbr. for* suppress variegation; any of a group of genes in *Drosophila* and yeast that suppress euchromatin/heterochromatin variegation in the higher structure of chromatin. Among them are genes for many enzymes that modify residues in the N-terminal regions of core histones of nucleosomes. Their action leads to gene silencing and assembly of heterochromatin. Su(var) genes are opposed by the products of **E(var)** genes. Some human homologues encode histone methyltransferases that selectively methylate histone H3 at lysine residue 9.

suxamethonium succinylcholine chloride, 2,2′-[(1,4-dioxo-1,4-butanediyl)bis(oxy)]bis[*N*,*N*,*N*-trimethylethanaminium] dichloride; a nicotinic receptor ligand that causes sustained activation of the receptors leading to blockade of synaptic transmission (‘depolarizing block’). It is used as a neuromuscular blocking agent in surgery. It acts by mimicking acetylcholine at the neuromuscular junction, but disengagement from the receptor site and subsequent breakdown are slower than for acetylcholine. It is hydrolysed by serum cholinesterase and recovery is spontaneous. **Decamethonium** was the first drug of this type to be developed. Both of these compounds depend for their action on the $N^+–N^+$ distance of 1.1 nm. *Compare* **curare**, **tubocurarine**.

Sv *symbol for* **1** sievert. **2** svedberg (alternative to S).

SV40 *abbr. for* simian virus 40.

svedberg *or* **Svedberg unit** *symbol*: S *or* Sv; a coherent non-SI unit used as a measure of **sedimentation coefficient**; 1 S = $10^{–13}$s.

Svedberg centrifuge a centrifuge, designed and built by Swedish colloid chemist Theodor Svedberg (1884–1971) in 1923, that was the forerunner of the **ultracentrifuge**.

Svedberg equation an equation relating the relative molecular mass, M_r, of a solute to its sedimentation velocity in an applied centrifugal field. If *s* is the sedimentation coefficient, *D* is the diffusion coefficient, $\bar{v}$ is the partial specific volume of the solute, ρ is the density of the solution, *R* is the gas constant, and *T* is the thermodynamic temperature, then

$$M_r = sRT/D(1\ \bar{v}\rho).$$

swainsonine 8*α*,*β*-indolizidine-1*α*,2*α*,8*β*-triol; an inhibitor of a number of *α*-mannosidases, particularly Golgi mannosidase II (*see* **Golgi mannosidase**), an important enzyme in the synthesis of the core oligosaccharide of a number of membrane glycoproteins. It inhibits the growth of tumours and prevents metastases in mice. [After its source, *Swainsona canescens*] .



swaposin a feature of some proteins in which domains, characteristically found in one protein, are found arranged in a different order in other proteins. The phenomenon was first commented on in relation to certain plant aspartic peptidases, which contain saposin-like domains swapped into a different order from that found in **saposins** (hence the name). In another example, some **pleckstrin homology domains** are found to be interrupted by inserts of **SH domains**.

sweetener any compound intended as a substitute for sucrose in sweetening food or drink, and aimed at avoiding the possible harmful effects of sucrose. Such compounds therefore should be nonnutritive and nonharmful but with a taste and aftertaste similar to those of sucrose. They include **aspartame**, **lactitol**, **mannitol**, **monellin**, **saccharin**, **stevioside**, **sucralose**, and **volemitol**. Sodium cyclamate was used as a sweetener until it was banned in the USA in 1970 because of its carcinogenicity.

sweetness one modality of the sense of taste, characterized by the effect of certain sugars such as sucrose and fructose.

SWI *abbr. for* mating-type switching gene; a gene of yeast that is required for transcriptional regulation of an endonuclease involved in mating-type switching. *See* **SWI/SNF**.

swinging-bucket rotor a type of centrifuge head in which the centrifuge tubes are placed in buckets that swivel on trunnions so that at speed the tube is oriented with its axis parallel to the centrifugal force (i.e. horizontal). Such a head is essential for zonal centrifugation through density gradients as angled tubes induce mixing. *Compare* **angle head**.

SWI/SNF *abbr. for* switching/sucrose nonfermenting; a protein complex (≈2.0 MDa) that contains ≈11 polypeptides and is present in all eukaryotic cells. It causes ATP-dependent nucleosome remodelling and stimulates binding of transcription factors to DNA. It was first characterized in yeast as essential for expression of genes for mating type switching and for sucrase. Inositol tetrakisphosphate stimulates its action. *See* **NURF**.

Swiss-Prot *see* **sequence database**.

switch **1** *(of a gene)* to activate (switch on) or inactivate (switch off) transcription. **2** *(of a protein)* to change from an active to an inactive form by changing conformation, e.g. as a result of binding to a specific ligand or of chemical modification. **3** *(in development)* to transfer from synthesis of a protein appropriate for a fetus to that appropriate for postnatal life. **4** *(in immunity)* to change synthesis of one class of immunoglobulins to that of another. *See* **molecular switch**.

switch peptide the flexible covalent connection between the **variable region** and **constant region** of an immunoglobulin molecule.

switch recombinase *see* **homothallic switching endonuclease**.

swivelase *see* **DNA swivelase**.

SWRP *abbr. for* systemic wound response protein; a group of defence proteins in plants whose synthesis is induced by the peptide hormone **systemin** in response to wounds inflicted mechanically or by herbivorous insects. At the target tissue systemin activates a signalling cascade that produces jasmonic acid, which is the inducer of the SWRP genes.

Sxl *symbol for* **sex lethal** gene of *Drosophila*.

SYBR Gold a proprietary cyanine dye used for fluorescent staining of nucleic acids with great sensitivity.

SYBR Green *a proprietary name for* one of two asymmetrical cyanine dyes whose fluorescence is greatly increased by binding to DNA. Sybr Green I is used for the measurement of low concentrations of DNA and in monitoring DNA amplification in real-time polymerase chain reaction.

Syk *abbr. for* spleen tyrosine kinase; a protein tyrosine kinase that phosphorylates the adaptor protein SLP-76. It and SLP-76 are involved in platelet degranulation, secretion of interleukin 2, and generation of lymphatic vessels. Mice with mutations in Syk or SLP-76 develop arteriovenous malformations.

sym+ *a variant form of* **syn+** (before b, m, or p).

sym- *prefix (in chemical nomenclature)* denoting symmetric; e.g. *sym*-trinitrobenzene.

symbiont an organism that lives as a partner in a **symbiosis**.

symbiosis (*pl.* **symbioses**) a long-term association between individuals belonging to two different species. The term is often used in a restricted sense to denote associations that are beneficial to one or both partners, although strictly it refers equally to neutral or harmful associations. —**symbiotic** *adj.*

symbiosome a vacuole within root cells of nitrogen-fixing plants that forms on infection by *Rhizobium* species and engulfs one or more bacteria, which become transformed to bacteroids. The delimiting membrane (peribacteroid membrane) acquires newly synthesized proteins (nodulins), which form membrane channels, transport proteins, enzymes of carbon and nitrogen metabolism, or leghemoglobin.

symmetry precise correspondence between two halves with respect to both size and shape. A molecule has an *n*-fold **axis of symmetry** if rotation around this axis through an angle of 360°/*n* produces an arrangement indistinguishable from the original (*n* being a small integer). For example, water has a twofold (*n*=2) axis of symmetry. A plane of symmetry is a plane drawn through a molecule such that a mirror placed in this plane forms an image of one half of the molecule that is superimposable on the other half. For example, a plane of symmetry is present in *meso*-**tartaric acid**. An alternating axis of symmetry or rotation–reflection axis is an axis such as is present in a molecule when rotation around the axis through an angle of 360°/*n* followed by reflection in a plane perpendicular to the axis produces a molecule superimposable on the original molecule. For example, a compound with such a twofold (n=2) axis is fumaric acid. A centre of symmetry is a position (point) such that if a straight line is drawn from every atom to the point, and is continued beyond the point, an equivalent atom is found at a distance equal to that between the point and the original atom. A molecule with such a centre has a twofold alternating axis of symmetry. An example of a molecule with a centre of symmetry is fumaric acid.

sympathectomy the surgical section of sympathetic nerve fibres.

sympathetic nervous system one of the two divisions of the **autonomic nervous system** the other being the parasympathetic nervous system. Most, but not all, sympathetic nerves release **norepinephrine** as a neurotransmitter.

sympatheticomimetic *an alternative term for* **sympathomimetic**.

sympathomimetic *or* **sympatheticomimetic** **1** describing a substance or action that stimulates the **sympathetic nervous system**; **adrenergic**. **2** a sympathomimetic agent, especially a sympathomimetic amine.

symport *or sometimes* **cotransport** a transport process in which two substances (usually a cation and an uncharged molecule) move across the membrane on a specific transporter, the process representing a downhill movement of one of them (the cation) and an uphill movement of the other (the uncharged molecule). In some cases, a cation and an anion are transported together when no external source of energy is required. The proteins involved may be designated as **symporters**.

syn- *abbr. for* synclinal (def. 1); *see also* **conformation**.

syn+ *comb. form* signifying similarity, association, or concerted action.

Synacthen *see* **tetracosactide**.

synaeresis *a variant spelling of* **syneresis**.

synapse *or (rare)* **synapsis** the junction between a nerve fibre of one neuron and another neuron; the site of interneuronal communication. As the nerve fibre approaches the synapse it enlarges into a specialized structure, the **presynaptic nerve ending**, which contains mitochondria and **synaptic vesicles**. At the tip of the nerve ending is the **presynaptic membrane**; facing it, and separated from it by a minute cleft – the **synaptic cleft** – is the **postsynaptic membrane** of the receiving neuron. On arrival of nerve impulses, the presynaptic nerve ending secretes **neurotransmitters** into the synaptic cleft. These diffuse across the cleft and transmit the signal to the postsynaptic membrane. *See also* **neuromuscular junction**. **—synaptic** *adj.*

synapsin I a major neuron-specific protein present in virtually all synaptic vesicles. Phosphorylated at multiple sites by Ca^{2+}- calmodulin-dependent and cyclic AMP-dependent protein kinases, it coats synaptic vesicles, and binds to the cytoskeleton. Synapsin IB is derived by alternative splicing; synapsins II are related.

synapsis **1** the pairing of chromosomes during **meiosis**. **2** *a less common word for* **synapse**.

synaptic cell adhesion molecule *see* **SynCAM**.

synaptic cleft the extracellular space, typically some 20 nm across, that separates the presynaptic nerve ending from the postsynaptic membrane of the receiving neuron (or other target cell) in a **synapse**. Chemical mediation of nerve transmission occurs across the synaptic cleft.

synaptic vesicle a vesicle, 20–65 nm in diameter, occurring within the cytoplasm of the presynaptic nerve ending and often closely related to the presynaptic membrane (*see* **synapse**). Synaptic vesicles store **neurotransmitters** and release them by fusing with the presynaptic membrane.

synaptic vesicle-associated membrane protein *another name for* **synaptobrevin**.

synaptobrevin *or* **sinaptobrevin** *or* **synaptic vesicle-associated membrane protein** (*abbr.*: VAMP) a SNAP receptor and member of the physin family involved in the docking and fusion complex (*see* **SNARE**) of synaptic vesicles and playing a central role in neural exocytosis. Synaptobrevin isoforms 1 and 2 (VAMP-1 and VAMP-2) are known. Both are expressed in all the main rat tissues, but differential expression is found, e.g. VAMP-1 is restricted to exocrine pancreas and kidney tubular cells, VAMP-2 predominates in islets of Langerhans and kidney glomerular cells.

synaptogyrin any of a family of membrane proteins (29 kDa) of synaptic vesicles of neurons and neuroendocrine cells. It contains four transmembrane segments, localizes (and shares some sequence homology) with synaptophysin, and like it is phosphorylated on tyrosine residues. *See also* **gyrin**.

synaptojanin a protein, found in nerve terminals in brain, that has inositol 5-phosphatase activity, and binds to the SH3 domain of **amphiphysin**, colocalizing with that protein in double immunofluorescence micrographs. It appears to participate with **dynamin** in synaptic vesicle recycling. It shares similarity with the yeast protein Sac1, which is genetically implicated in phospholipid metabolism and the function of the actin cytoskeleton.

synaptonemal complex an elaborate structure that holds paired chromosomes together during synapsis in prophase I of meiosis and promotes genetic recombination. It consists of a ladder-like protein core (comprising central elements joined to lateral elements by transverse filaments) with corresponding regions of the two sister chromatids aligned on opposite sides. FKBP6 is one of the protein components.

synaptophysin an integral membrane glycoprotein of the physin family that occurs in presynaptic vesicles of neurons and in similar vesicles of the adrenal medulla. It is a marker protein for neuroendocrine cells and neoplasms.

synaptosome any of the discrete particles (nerve-ending particles) formed from the clublike presynaptic nerve endings that resist disruption and are snapped or torn off their attachments when brain tissue is homogenized in media isosmotic to plasma. In synaptosomes the main structural features of the nerve endings are preserved.

synaptosome-associated protein *see* **SNAP** (def. 2).

synaptotagmin an abundant integral membrane protein of synaptic vesicles and chromaffin granules, with a proposed role in membrane interactions during trafficking of synaptic vesicles at the active zone of the synapse. The primary structure contains two copies of a repeat that is homologous to the regulatory domain of protein kinase C.

synarchic regulation *see* **synarchy**.

synarchy cooperation between two intracellular messengers (e.g. cyclic AMP and Ca^{2+}) that act in concert to activate intracellular pathways.

SynCAM *abbr. for* synaptic cell adhesion molecule; a brain-specific type I integral membrane protein that mediates homophilic cell adhesion at synapses. The longest transcript encodes 456 amino acids, organized into three extracellular immunoglobulin-like domains, a transmembrane segment, and an intracellular **PDZ domain**.

syncatalytic synchronous with the catalytic process.

synchrotron an apparatus used in nuclear physics that accelerates particles of atomic size through an electric field. The particles are initially charged by an ion source, and their path may be linear (**linear accelerator**) or of spiral form (**cyclotron**). The acceleration imparts a high kinetic energy to the particles, which can lead to structural changes in the particles. One use of a synchrotron, therefore, is the production of radioactive or other nuclides for use in biology or medicine. A synchrotron radiation source is a circular storage ring in which electrons are accelerated in a magnetic field.

synclinal **1** *abbr.*: *syn-*; describing one of the two possible conformations of the base and sugar ring in a nucleotide, the other being the **anticlinal** conformation. *See* **conformation**. **2** *or (sometimes)* **gauche** *or* **skew** *abbr.*: *sc-*; describing a particular staggered conformation of a molecule in which the **torsion angle** is within ±60° of 0°. *See* **conformation**.

syncytium (*pl.* **syncytia**) a mass of cytoplasm containing several nuclei enclosed within a single plasma membrane. Syncytia are normally derived from single cells that fuse or fail to complete cell division. Examples are muscle fibres, formed by fusion of **myoblasts**, and residual bodies formed during **spermatogenesis**.

SYND2 *abbr. for* syndecan-2. *See* **syndecan**.

syndapin 1 a cytosolic protein that contains an SH3 domain, binds dynamin of the cytoskeleton, and is involved in vesicle budding at the plasma membrane. It also binds the brain-specific **synaptojanin** and **synapsin I**.

syndecan a type I integral membrane proteoglycan that links the cytoskeleton to the interstitial matrix. It bears heparin sulfate and chondroitin sulfate, and binds to bFGF (*see* **fibroblast growth factor**) with high affinity, and also to components of the extracellular matrix. Its intracellular domain binds to the actin cytoskeleton.

syndein *an alternative name for* **ankyrin**.

syndesine a di(α-amino acid) isolated from hydrolysates of certain **collagens**, in which it forms covalent cross-links between adjacent polypeptide strands. It is formed by **aldol condensation** between the side chains of a residue of **allysine** and one of **hydroxyallysine**; two isomers are possible.

syndiotactic having or relating to a regular alternation of differences in stereochemical structure in the repeating units of a polymer. *Compare* **isotactic**.

syndrome a set of concurrent symptoms characteristic of a particular pathological state.

syndrome X *see* **hyperinsulinemia syndrome**.

Syne *abbr. for* synaptic nuclei expressed; either of two proteins found enriched at the nuclear envelope of myonuclei clustered at neuromuscular junctions. They are probably involved in anchoring nuclei to the cytoskeleton. Syne-1 (human: 8739 amino acids) and Syne-2 (6855 amino acids) each contain actin-binding domains, large central domains of spectrin repeats, and a C-terminal nuclear envelope transmembrane domain. Mouse homologues have been partially characterized. Syne proteins are homologous with ANC-1 (of *Caenorhabditis elegans*) and Msp-300 (of *Drosophila*).

synemin a protein, M_r 230 000, found in the Z disk of skeletal and cardiac muscle cells, and in **intermediate filaments** of some non-muscle cells. It binds tightly to **desmin**.

synenkephalin *or* **proenkephalin 1–70** a derivative of **proenkephalin** secreted as an intact molecule or as a part of precursors in the adult brain and adrenal medulla. It has the immunoreactivity of proenkephalin, but does not contain the enkephalin sequence.

syneresis *or* **synaeresis** **1** *(in chemistry)* the separation of liquid from a gel caused by contraction of the gel structure. **2** *(in pathology)* the gradual contraction of a blood clot that occurs after its formation, leading to a more solid mass that seals the ruptured blood vessel.

synergism **1** the phenomenon whereby the effect of two or more agonists together is greater than the sum of their effects when used individually. **2** the concerted action of two muscles to enhance their combined effects. *Compare* **antagonism**. —**synergetic** *or* **synergistic** *adj.*

synergist **1** an agent that increases the effectiveness of another agent. **2** a muscle that acts in concert with another muscle to increase its effect. *Compare* **antagonist**.

synexin *or* **annexin VII** a cytosolic Ca^{2+}-dependent, lipid-binding protein belonging to the **annexin** family. Originally isolated from adrenal medullary cells, isoforms have since been found in skeletal muscle, brain, and liver, and also in *Dictyostelium discoideum*. Adrenal medulla and liver have isoforms of 47 kDa and 51 kDa, while skeletal muscle has only the 51 kDa isoform. Synexin promotes membrane fusion, aggregates isolated chromaffin granules, and forms voltage-dependent calcium channels in artificial and natural membranes.

syngamy the union of the nuclei of two gametes to form the single nucleus of the zygote during fertilization; sexual reproduction. —**syngamic** *or* **syngamous** *adj.*

syngeneic of or pertaining to cell types in an experimental mammalian chimera that are antigenetically similar. *Compare* **allogeneic**.

synologue *or (esp. US)* **synolog** a gene transferred to a species from another during or after the fusion of the two species. Examples are genes transferred to the eukaryotic cell from the endosymbionts that have evolved into the mitochondria and chloroplasts. *Compare* **xenologue**.

synology the transfer of genes between organelles and the nucleus. –**synological** *or* **synologic** *adj.*; –**synologically** *adv.*

synonym codon a **synonym triplet** in messenger RNA.

synonymous codon usage *abbr.*: SCU; the frequency with which a codon is used relative to its synonymous alternative(s) in a particular species, gene, or group of genes. Synonymous alternatives are not used with equal frequency; *see* **codon usage bias**.

synonymous mutation *an alternative name for* **silent mutation**.

synonym triplet any of two or more trinucleotides of a nucleic acid that can specify the same amino acid. In messenger RNA the term is synonymous with **synonym codon**.

synovia *or* **synovial fluid** the fluid surrounding a joint or filling a tendon sheath.

synovial membrane *or* **synovium** the membrane of mesothelial cells and connective tissue that surrounds a joint; it secretes the **synovia**.

synovium *an alternative name for* **synovial membrane**.

synperiplanar *see* **conformation**.

syntaxin a SNAP receptor (**SNARE**) involved in docking of synaptic vesicles at the presynaptic zone of a **synapse**.

synteny the state in which genes or other loci reside together in a linkage group, i.e. on the same chromosome. Conserved synteny denotes that homologous genes occur in the same linkage groups across the genomes of different species. –**syntenic** *adj.* –**syntenically** *adv.*

synthase an enzyme that catalyses a condensation reaction in which no nucleoside triphosphate is required as an energy source. *Compare* **synthetase**.

synthase kinase glycogen synthase α kinase. *See* **non-specific serine/threonine protein kinase**.

synthesis *(in chemistry)* the production of a more complex molecule from simpler reagents by one or a series of reactions. —**synthesize** *or* **synthesise** *vb.*

synthesizer *or* **synthesiser** an instrument that automates a chemical synthesis, especially of peptides or oligonucleotides.

synthetase an enzyme that catalyses a condensation reaction in which a nucleoside triphosphate is required as an energy source. *Compare* **synthase**.

synthetic **1** of, or pertaining to, **synthesis**. **2** (of a substance or material) chemically synthesized as opposed to prepared from recognizable natural materials. Such a product is identical chemically to that isolated from the natural source.

synuclein a brain presynaptic protein that is expressed also in other tissues, but at very low levels. It is highly conserved, rodent and zebrafish α synucleins being 95% and 86% identical to human. Some mutations are linked to familial **Parkinson's disease**.

synxenic pertaining to the growth of organisms of a single species in the presence of one or more other species. Cultures in which one, two, three, or more other species are involved are described, respectively, as **monoxenic**, **dixenic**, **trixenic**, or **polyxenic**. *Compare* **axenic**. —**synxenity** *n.*; **synxenize** *or* **synxenise** *vb.*

synxenite the principal organism being studied in a **synxenic** culture.

syringomycin a cyclic lipodepsipeptide-containing nonprotein amino acids and forming cation-permeable pores. It is produced by the Gram-negative bacterium *Pseudomonas syringae* and is classified in the TC system under number 1.D.2.

syringopeptin a channel-forming cyclic lipodepsipeptide similar to **syringomycin**. It is classified in the TC system under number 1.D.3.

syrup *or* **sirup** **1** a thick, sticky, viscous liquid consisting of a concentrated aqueous solution of sucrose. **2** the concentrated juice of a fruit or plant, especially of sugar cane. **3** any solution that is thick, sticky, and viscous.

system A a transport system for the uptake of neutral amino acids by animal cells. It prefers amino acids having short, polar or linear side chains, including the nonmetabolizable 2-aminoisobutyric acid. Transport is sodium ion-dependent and is reduced by lowered extracellular pH. **System ASC**, prominent in erythrocytes, is distinguished from system A on the basis of pH insensitivity and higher stereospecificity. *See also* **sodium/neutral amino acid cotransporter**, **system L**, **system N**.

system ASC *see* **system A**.

systematic evolution of ligands by exponential enrichment *abbr.*: SELEX; an iterative method for selecting high-affinity **aptamers** using directed molecular evolution to enrich oligonucleotide mixtures with respect to their ability to bind a target.

systematic name **1** *(in organic-chemical nomenclature)* a name of a molecule that is composed wholly of specially coined or selected syllables, with or without numerical affixes and locants; e.g. oxazole, pentane, cyclohex-2-en-1-ol. Such a name unequivocally specifies the complete chemical structure of a particular molecular entity. *Compare* **semisystematic name**, **trivial name**. **2** *(in enzyme nomenclature)* a name of an enzyme that describes its catalytic action as exactly as possible, thus identifying the enzyme precisely and permitting a code number to be assigned to it. Thus all proteins having the same catalytic property share the same systematic name and code number. The systematic name consists of the name of the substrate or, in the case of a bimolecular reaction, of the two substrates separated by a colon (with small and equal spaces before and after the colon); and the nature of the catalysed reaction, ending in '+ase'.

systematics *functioning as sing.* **1** the study of systems, especially the principles of classification. **2** *(in biology)* the discipline that deals with classification and nomenclature.

Système International *abbr.*: SI; Système International d'Unités; a system of units based on the metric system. *See* **SI units**.

systemic concerning the whole body of an animal or a whole plant rather than an individual part.

systemic circulation the blood vessels supplying all parts of the body except the lungs.

systemin an 18-residue polypeptide, isolated from tomato leaves, that acts as a potent activator of plant protease inhibitor genes. It induces synthesis of two protease inhibitors in tomato and potato leaves. It is the only plant polypeptide hormone-like signalling molecule presently known. It has the sequence

AVQSKPPSKRDPPKMQTD,

and is proteolytically processed from a 200-residue precursor, **prosystemin**. Plant protease inhibitors are induced by wounding, e.g. by insects or pathogens, and may be part of the plant defence mechanisms.

system L a transport system responsible for the uptake of neutral amino acids by animal cells. It prefers branched-chain and aromatic amino acids such as leucine, isoleucine, valine, phenylalanine, and the nonmetabolizable analogue 2-aminobicyclo-[2,2,1]-heptane-2-carboxylic acid (BCH). The transport mechanism is sodium-ion-independent and may be stimulated by lowered extracellular pH. It is present in a wide variety of animal cell types, including avian and mammalian. *See also* **sodium/neutral amino-acid cotransporter**, **system A**, **system N**.

system N a sodium-ion-dependent transport system responsible for the uptake of asparagine, glutamine, and histidine amino acids by animal cells. *See also* **sodium/neutral amino acid cotransporter**, **system A**, **system L**.

systems biology the study of biology as an interconnected system of dynamic, interdependent genetic, metabolic, cellular, and pathway events (rather than as a set of individual molecular components), in an attempt to understand how emergent properties appear at increasing levels of complexity and hence how biological systems function as an integral whole.

systole a rhythmical repeated contraction, as of the chambers of the heart or of a pulsating vacuole. *Compare* **diastole**. **—systolic** *adj.*

Tt

t 1 *symbol for* **a** tert+ (i.e. **tertiary**) in a chemical name (alternative to *t*). **b triton** (def. 2). **2** *abbr. for* terminator sequence.

t *symbol for* **1** time. **2** Celsius temperature (alternative to θ). **3** transference number.

t- *abbr. for* **1** *tert-*. **2** *trans-*.

$t_{½}$ *symbol for* half-life. *See also* **$T_{½}$**.

T *symbol for* **1** tera+ (SI prefix denoting 10^{12} times). **2** tritium. **3** tesla. **4** a residue of the α-amino acid L-threonine (alternative to Thr). **5** a residue of the base thymine in a nucleic-acid sequence. **6** a residue of the ribonucleoside ribosylthymine (*not* thymidine, i.e. deoxyribosylthymine; alternative to Thd). **7** twist number.

T *symbol for* **1** thermodynamic temperature. **2** transmittance. **3** period. **4** kinetic energy (alternative to E_K or K).

-*T* conformational descriptor designating the **twist conformation** (def. 2) of a five-membered ring form of a monosaccharide or monosaccharide derivative. Locants of ring atoms that lie on the side of the structure's reference plane from which the numbering appears clockwise are indicated by left superscripts and those that lie on the other side of the reference plane are indicated by right subscripts; e.g. 1,2-*O*-isopropylidene-β-L-idofuranose-$^3T_2$. *See also* **conformation**.

$T_{½}$ *symbol for* half-life of a radionuclide (alternative to $t_{½}$).

T_1 *symbol for* spin-lattice relaxation time, longitudinal relaxation time.

T_2 *symbol for* spin-lattice relaxation time, transverse relaxation time.

T_m *or* **t_m** *or* **Θ_m** *symbol for* melting temperature.

T_t *symbol for* transition temperature.

T1 *abbr. for* bacteriophage T1, a **T-odd phage**.

T2 **1** *or* T_2 *symbol for* L-diiodothyronine. **2** *abbr. for* bacteriophage T2, a **T-even phage**.

T3 **1** *or* T_3 *symbol for* L-triiodothyronine. **2** *abbr. for* bacteriophage T3, a **T-odd phage**.

T4 **1** *or* T_4 *symbol for* L-thyroxine. **2** *abbr. for* bacteriophage T4, a **T-even phage**.

T6 *abbr. for* bacteriophage T6, a **T-even phage**.

T7 *abbr. for* bacteriophage T7, a **T-odd phage**.

tA *symbol for* N^6-(threonylcarbamoyl)adenosine; *see* **hypermodified base**.

Ta *symbol for* tantalum.

TACE *see* **ADAM-17**.

tachometer an instrument that measures the speed at which any object is rotating. —**tachometric** *adj.*; **tachometry** *n.*

tachy+ *comb. form* denoting fast or rapid.

tachykinin any of a group of closely related vasoactive peptides characterized by a rapid stimulant effect on vascular (and extravascular) smooth muscle, producing hypotension (*compare* **bradykinin**). They also have a direct effect on nervous tissue, and stimulate salivary and lachrymal secretion. Naturally occurring tachykinins are oligopeptide amides containing 10–12 amino-acid residues, and terminating in the common sequence -Phe-Xaa-Gly-Leu-Met-NH_2 (where Xaa = Phe, Tyr, Ile, or Val). Mammalian tachykinins include neuromedin K, **neurokinin A** (formerly substance K) and **substance P**; others (e.g., **eledoisin**, **physalaemin**) occur in amphibians and octopods. Substance P and neurokinin A are generated from a preprotachykinin protein precursor (*see* **protachykinin β precursor**). The primary mRNA transcript is differentially processed into three mature mRNAs: α, β, and γ; the β and γ preprotachykinin mRNAs are predominant in the rat, each encoding substance P and neurokinin A.

tachykinin receptor any G-protein-associated membrane protein that binds **tachykinins** and mediates their transmembrane action. There are three classes: (1) NK_1 (407 amino acids, human), agonist potency: substance P (SP) > neurokinin A (NKA) > neurokinin B (NKB); (2) NK_2 (398 amino acids, human), agonist potency: NKA > NKB >> SP; and (3) NK_3 (452 amino acids, rat), agonist potency: NKB > NKA > SP. In all, ligand binding activates phospholipase C.

tachyphylaxis a decline in the response to repeated application of an agonist. *See also* **desensitization**, **fade**.

tachyplesin any peptide antibiotic of arthropods, 17 or 18 amino acids long and with a C-terminal arginine α-amide. Tachyplesins are abundant in hemocyte debris of horseshoe crabs (*Tachypleus* spp.), and are active against Gram-positive and Gram-negative bacteria, and fungi such as *Candida albicans*. It is classified in the TC system under number 1.C.34.

***tac* promoter** a constructed hybrid **promoter** that contains the –35 sequence of the *trp* promoter and the –10 sequence of the *lacZ* promoter. *See* **minus 10 region**.

Tacrolimus *see* **FK506**.

-tactic refers to the ability of a motile cell or organism to move along a gradient, e.g. of a chemical (chemotactic) or light (phototactic).

tactic polymer a regular polymer in whose molecules there is an ordered structure with respect to the configurations around at least one main-chain site of stereoisomerism per **constitutional base unit**.

tactile capable of exciting the sense of touch; relating to the sense of touch (as a sense organ).

tactoid a **paracrystal**-like aggregate; the term may be applied to the rodlike filaments of hemoglobin that form in **sickle cells**, or to assemblies of virus particles (e.g. of tobacco mosaic virus).

TAE a buffer for agarose gel electrophoresis comprising 40 mM Tris-acetate and 1 mM EDTA.

tafazzin one of a family of acyl-CoA synthetases that is important in cardiolipin synthesis. Mutations in the gene locus (at Xq28) produce **Barth syndrome**.

tag **1** to identify by a marker; for example, a cell may be tagged by attachment of a (fluorescent or radiolabelled) antibody. **2** an identifier used in tagging.

Tagamet *see* **cimetidine**.

D-tagatose *a nonsystematic name for* D-*lyxo*-2-hexulose, a hydrolysis product of some plant gums.



α-D-pyranose form

Tagit *a proprietary name for* *N*-succinimidyl 3-(4-hydroxyphenyl) propionate; it is used in the preparation of **Bolton and Hunter reagent** for tagging peptides and proteins with radioiodine.



tail **1** an extension growing or appending from a point of origin or attachment. For example, the fatty-acyl groups of a phospholipid and the glycerol to which they are bonded are referred to as the tail. *Compare* **headgroup**. **2** *(in chromatography)* a region of more slowly moving or decomposed material extending back from a band towards the **origin**. *See also* **poly(A) tail**, **tailing**.

tailing **1** the addition of a stretch of identical nucleotides to the ends of a restriction fragment using **terminal deoxynucleotidyl transferase**. **2** the spreading out of a band or spot in a chromatographic process.

TAIL PCR *abbr. for* thermal asymmetric interlaced polymerase chain reaction; a method for finding previously unknown sequences adjacent to known sequences in genomes. It is useful for recovering sequences flanking sites of insertional mutagenesis caused by integration of a plasmid, T-DNA, or transposon.

Takahara disease *an alternative name for* **acatalasemia**.

Takifugu rubripes *see* **fugu**.

Tal *symbol for* a residue, or sometimes a molecule, of **talose**.

talaric acid one of the **hexaric acids**; *see also* **aldaric acid**.

talc a soft mineral composed of hydrated magnesium silicate, $Mg_3Si_4O_{10}(OH)_2$, with small quantities of metal impurities. In its powdered form it is known as talcum powder, or French chalk, and in granular form as soapstone (steatite). Powdered talc is used as a lubricant, as a filler in paper and other products, and in cosmetics, etc.

talcum powder powdered **talc**.

talin a protein involved in connections between the cytoskeleton and the plasma membrane. A phosphoprotein, it binds strongly to **vinculin**, and less strongly to **integrins**. It is a founder member of the **TERM** family.

talo+ *or (before a vowel)* **talos+** *comb. form* of **talose**.

talo- *prefix (in chemical nomenclature)* indicating a particular configuration, a set of (usually four) contiguous CHOH groups as in the acyclic form of D- or L-**talose**. *See also* **monosaccharide**.

talopeptin *N*-(6-deoxy-*α*-L-talopyranosyl-oxyphospho)-L-leucyl-L-tryptophan; an inhibitor of several metallopeptidases, including **thermolysin**. *Compare* **phosphoramidon**.

talosaminouronic acid a component of the **peptidoglycan** of archaea.



talose *symbol*: Tal; *the trivial name for* the aldohexose *talo*-hexose, which differs from glucose in the configuration of the groups at C-2 and C-4; there are two enantiomers.



α-D-talose

Tamm–Horsfall glycoprotein *or* **uromodulin** the principal glycoprotein of human urine. It occurs in other species, e.g. the cow and rat. The molecule is filamentous, with an M_r of several million, and is composed of subunits of M_r ~80 000; it contains about 25% carbohydrate and a small amount of lipid. An abnormally high M_r is observed in cystic fibrosis. *See also* **proteinuria**. [After Igor Tamm (1922–71), US virologist, and Frank Lappin Horsfall (1906–71).]

tamoxifen [*Z*]-2-[4-(1,2-diphenyl-1-butenyl)-phenoxy]-*N*,*N*-dimethylethanolamine; an estrogen antagonist used in the treatment of breast cancer and suggested for prophylaxis in women with a family history of breast cancer. It can behave as a pure estrogen agonist, a partial agonist, or an antagonist, depending on the species of animal, the target organ examined, and the endpoint measured. It is a **genotoxic** carcinogen in the rat.



tan *abbr. for* tangent (def. 1).

tandem affinity purification *abbr.*: TAP; a separation technique designed to isolate protein complexes, whereby an IgG-binding domain sequence tag is added to the gene for a target protein, and the protein is synthesized with the section encoded by the tag. Proteins with the domain are separated from a mixture using an affinity column containing IgG beads, to which they stick. If the target protein is part of a complex, proteins associated with it are also retained on the column.

tandem-crossed immunoelectrophoresis *see* **crossed immunoelectrophoresis**.

tandem mass spectrometry *abbr.*: MS/MS; a separation technique in which samples are first ionized and then subjected to two or more sequential stages of **mass spectrometry** analysis using either laser-based methods – e.g. MALDI (matrix-assisted laser desorption/ionization) and SELDI (surface-enhanced laser desorption and ionization) – or electrospray-based (e.g. ESI) methods.

tandem repeat 1 (of DNA sequences) an arrangement in which two or more copies of a particular base sequence are situated immediately one after the other. Tandem repeats are commonly found in **telomeres**, the repeated sequence being characteristic of species and source of DNA, and of relatively short length (up to about 10 bases). They also occur in **highly repetitive DNA**. **2** (of genes) a cluster of adjacent multiple copies of the same gene. The genes for ribosomal RNA (rRNA) are characteristically contained in tandem clusters, sometimes referred to as **ribosomal DNA** (rDNA). *See also* **concatemer**.

Tanford–Kirkwood theory a theory of protein titration curves based on a model in which the charges are taken to be discrete unit charges located at fixed positions on the protein molecule. [After Charles Tanford (1921–) and John Gamble Kirkwood (1907–59).]

tangent 1 *abbr.*: tan; a function of an angle, being, in a right-angled triangle, the ratio of the side opposite the given angle (if acute) to that of the side opposite the other acute angle. The tangent of an obtuse angle is numerically equal to that of its supplement but of opposite sign. **2** a straight line that touches, but does not cut, a curve or a curved surface.

tangential-flow filtration a convenient and rapid method of concentrating cells, cell organelles, or other particulate material, or for eliminating such material from suspensions. In a special apparatus, the suspension flows over ('tangential flow') a semipermeable membrane; only material smaller than the membrane pores will pass through the membrane, forming the filtrate, leaving larger matter to be collected (retentate).

Tangier disease a rare autosomal recessive condition in humans in which there is a deficiency or complete absence of **high-density lipoprotein**. Homozygotes have very low levels of **apolipoprotein A-I**. There is accumulation of cholesterol esters in cells of the mononuclear phagocyte system. The condition is relatively benign as organ function is not affected. [After Tangier Island, Chesapeake Bay; the disease was first found in inhabitants of this island.]

tankyrase a 142 kDa protein associated with telomeres in human cells, and also present in the Golgi apparatus, the nuclear pore complex, and mitotic centrosomes. It has a catalytic domain homologous to that of **PARP-1**, and 24 tandem repeats of the ankyrin motif.

It does not require DNA for activity and has **TEP-1** as substrate, causing release of the latter from telomeric DNA.

tannic acid *or* **tannin** *or* **gallotannin** *or* **gallotannic acid** *an imprecise term used for* a mixture of hydrolysable **tannins** (def. 1).

tannin 1 any polyphenolic plant product that can be used to tan animal skins to produce leather. Tannins are divided into **hydrolysable tannins** (the larger group) and **condensed tannins**. The former consist of a polyhydric alcohol, usually glucose, esterified with either gallic acid or hexahydroxydiphenic acid. Condensed tannins are polymers of flavans, never contain sugar residues, and are often termed **flavolans**. Tannins form insoluble tannates with proteins, which forms the basis of **tanning** (def. 1). The release of tannins during the extraction of plant enzymes can lead to formation of insoluble enzyme tannates. The addition of polyvinylpyrrolidone may help to avoid this problem. Good tanning agents should have an M_r of between 500 and 3000 and contain sufficient phenolic hydroxyl groups (1–2% of M_r) to form effective cross-links with protein. **2** *a common name for* **tannic acid**.

tanning 1 a technique, known by the Egyptians around 3000 BC, for producing leather from animal skins by the use of **tannin** (def. 1). Modern methods using chrome salts are faster, taking a few hours rather than weeks. **2** the treating of red blood cells with tannic acid. Such cells are used in a test for anti-thyroglobulin antibodies, after they have been treated with thyroglobulin. The tanning enhances sensitivity.

T antigen 1 any early gene product of a genetic locus of certain transforming DNA viruses, including adenovirus, simian virus 40 (SV40), and polyoma virus. The substance originally detected in nuclei of transformed cells by immunofluorescence (hence 'T' for tumour or transformation) led to the identification of several early proteins that are needed for replication. Two products are formed by SV40, known as **large T antigen** (*or* T antigen) and **small t antigen** (*or* t antigen). Polyoma virus produces large T antigen, middle T antigen, and small t antigen. Large T antigen of SV40 alone is sufficient to immortalize primary rodent cells and transform established rodent cell lines. It is a multifunctional protein that is a potent transcriptional activator which activates promoters containing a TATA box or initiator element and at least one upstream transcription-factor-binding site. Middle T antigen of polyoma virus is essential for polyoma-virus-mediated tumorigenesis and cell transformation. It activates cellular tyrosine kinases, including c-Src, c-Yes, and Fyn, and binds phosphatidylinositol 3-kinase and protein phosphatase 2A. Small t antigen of SV40 has a helper effect in SV40 transformation. It binds protein phosphatase 2A and regulates the phosphorylation and transcriptional transactivation of **CREB protein**. It stabilizes p53 in a manner that correlates with enhanced transformation efficiency of SV40. **2** an antigen found on normal human erythrocytes that is unreactive unless the cells are first treated with neuraminidase. **3** one of the principal protein antigens in the cell wall of *Streptococcus* spp. **4** *abbr. for* transplantation antigen (i.e. a class I MHC antigen); see **major histocompatibility complex**.

TAP *abbr. for* tandem affinity purification.

tapeworm any parasitic flatworm (phylum Platyhelminthes) belonging to the class Cestoda.

Taps *or* **TAPS** *abbr. for* *N*-tris(hydroxymethyl)methyl-3-aminopropanesulfonic acid; 3-[2-hydroxy-1,1-bis(hydroxymethyl)ethyl]-amino propanesulfonic acid; a **Good buffer substance**, pK_a (20°C) = 8.4.



***Taq* DNA polymerase** a heat-stable DNA polymerase from the thermophilic bacterium *Thermus aquaticus*. It is widely used in the **polymerase chain reaction** (PCR). The enzyme lacks 3′→5′ exonuclease activity and therefore has no proofreading function. It has a template-independent terminal transferase activity with a preference for the addition of deoxyadenosine to the 3′ ends of PCR products.

Tar a protein that serves as a multifunctional receptor of *E. coli*, used for detection of aspartate and temperature. This capability involves methylation at up to eight sites in the protein's cytoplasmic domain.

TAR *abbr. for* tape archive; a file format (not necessarily on a tape) used on UNIX (or Linux) computers. TAR files usually have the extension .tar; they are not **compressed** but might be compressed in which case the extension would become .tar.Z or .tar.gz. The program tar is needed to extract the files from the archive.

tare 1 to compensate for the weight of a container, etc. when weighing, by adjusting the balance to zero with the empty container in place before adding the material to be weighed. **2** the weight of the tared vessel or material.

target the object at which an action or process is directed. For example, a **target cell** is the cell under attack by a cytolytic or killer cell or other cytolytic agent, and a **target tissue** is the tissue that is acted on by any hormone, growth factor, or other agonist. *See also* **drug target**.

target discovery *or* **target identification** the process of identifying a biological entity (usually a protein or gene) that interacts with, and whose activity is modulated by, a particular compound. Once a suitable target has been identified, it may then go on to **target validation**.

targeting subunits protein subunits that specify the location and catalytic and regulatory properties of protein phosphatases and kinases.

target repeat *see* **transposon**.

target site the site where a **restriction endonuclease** cleaves a DNA molecule; usually the **recognition site** (def. 2).

target theory *(in radiation chemistry)* a theory stating that all single hits on biologically active macromolecules by particles or quanta of ionizing radiation result in damaged and inactive molecules, that no partially active molecules are formed, and that all unhit molecules retain full activity.

target validation the process by which the role of a target (usually a specific gene or protein) is confirmed within a pathogenic process.

tartaric acid 2,3-dihydroxybutanedioic acid; 2,3-dihydroxysuccinic acid; an **aldaric acid** formed by oxidation of a **tetrose** at C-1 and C-4. The L$_g$(+) (*see* **d/l convention**), or 2*R*,3*R*, enantiomer occurs widely in plants, especially grape juice, and in fungi and bacteria; the D$_g$(–) (or 2*S*,3*S*) enantiomer and *meso* form have limited distribution in plants. The racemic mixture, DL-tartaric acid, sometimes occurs during wine manufacture; it was originally known as **paratartaric acid**. The first determination of an absolute configuration by anomalous dispersion of X-rays was made on sodium rubidium L(+)-tartrate in 1951. The property of **optical activity** of some substances was first described by **Pasteur** in experiments with crystals of sodium ammonium tartrate.



L-form



meso-form

Tarui disease *an alternative name for* **glycogen disease** type VII.

tasiRNA *abbr for* trans-acting **siRNA**, siRNAs that direct cleavage of endogenous mRNAs having a region of complementarity to the siRNAs but little overall resemblance to the genes from which the siRNAs were transcribed.

tat a membrane protein complex, found in bacteria and plants, that carries folded proteins (with their cofactors) in their intact state through energy-transducing membranes. The system recognizes the **twin-arginine** motif in the protein to be transported.

TATA-binding protein *abbr.*: TBP; a component of transcription factor IID (*see* **TFII**). *See also* **RNA polymerase**.

TATA box *or* **Hogness box** a base-sequence element common in eukaryotic promoters, characterized by the consensus TATAAAA. It binds a general transcription factor and specifies the position where **transcription** is initiated.

tau **1** *symbol*: τ (lower case) *or* T (upper case); the nineteenth letter of the Greek alphabet. For uses *see* **Appendix A**. **2** *an alternative name for* transcription factor TFIIIC; *see* **TFIII**.

tau protein a microtubule-associated protein that promotes microtubule assembly, and stabilizes microtubules. It constitutes at least a part of the paired helical filament (PHF) core found in **Alzheimer's disease**.

tau-protein kinase EC 2.7.11.26; a protein serine/threonine kinase that phosphorylates **tau protein**.

taurine 2-aminoethanesulfonic acid; it is derived metabolically from cysteine by oxidation of the sulfhydryl group to sulfoxide followed by decarboxylation of the resulting cysteic acid. *N*-conjugated with cholic acid, it forms the bile salts **taurochenodeoxycholate, taurocholate**, and **taurodeoxycholate**.



taurochenodeoxycholate the anionic form of the amido conjugate of **taurine** and **chenodeoxycholate**. It is a major **bile acid**.



taurocholate the anionic form of taurocholic acid, *N*-cholyltaurine, a major **bile salt** of humans and other mammals. It is useful as an anionic bile-salt detergent (aggregation number 4; CMC 3–11 mM). Taurine conjugates of other bile acids are known, e.g. **taurochenodeoxycholate** and **taurodeoxycholate**.



taurocyamine *N*-(aminoiminomethyl) taurine, found in marine polychaete worms. The guanidine group can be phosphorylated to form phosphotaurocyamine, which acts as a **phosphagen**.

taurodeoxycholate the anionic form of taurodeoxycholic acid, *N*-(7-deoxy)cholyltaurine. It is useful as an anionic bile-salt detergent (aggregation number 6; CMC 1–4 mM).

taurolipid any lipid consisting of a non-hydroxy fatty acid esterified with a hydroxy group of tri-, tetra-, or pentahydroxystearic acid in amide linkage with taurine. Taurolipids are characteristic of the protozoan *Tetrahymena*.

tauryl the acyl group, $H_2N–CH_2–CH_2–SO_2–$, derived from taurine.

taut form *abbr.*: T form; *see* **tense form, Monod–Wyman–Changeux model for allosteric interaction**.

tautomer any of the alternative structures that may exist as a result of **tautomerism**.

tautomerism a form of constitutional isomerism in which a structure may exist in two or more constitutional arrangements, particularly with respect to the position of hydrogens bonded to oxygen. The isomers, or tautomers, are readily interconvertible and exist in equilibrium. The best-known example is **keto–enol tautomerism**, in which the structures $X–C(=O)–CH_2–X$ (keto) and $X–C(OH)=CH–X$ (enol) exist, in proportions determined by the equilibrium position for the conditions pertaining (normally strongly favouring the keto form). Other examples include quinone–quinol and **amino–imino tautomerism**. **—tautomeric** *adj.*

-taxis refers to the movement of a motile cell or organism along a gradient, e.g. of a chemical (chemotaxis) or light (phototaxis).

taxol an antitumour and antileukemic agent isolated from the bark of the Pacific yew, *Taxus brevifolia*. It is used clinically to treat refractory ovarian cancer. It inhibits mitosis and blocks the cell cycle at G or M phases through enhancement of the polymerization of **tubulin** and the consequent stabilization of the **microtubules**. Taxol is manufactured semisynthetically from a material present in *T. baccata*. A total chemical synthesis has also been achieved. A compound with similar properties, isolated from the myxobacterium *Sporangium cellulosum*, is **epothilone**; this is more water-soluble than taxol and can be produced in quantity by fermentation. Taxol and its analogues are known as **taxanes**. One proprietary name is Paclitaxel. A proprietary name of a semisynthetic analogue is Docetaxel.



taxon (*pl.* **taxa**) a named taxonomic group of any rank; a particular taxon comprises organisms having certain genetic characters in common. Strictly, the term should be used to denote only named groups, e.g. Chordata, Hominidae, etc., not as a generic term for the ranks themselves, e.g. phylum, family, etc.

Tay–Sachs disease *or* **G_{M2} gangliosidosis** an inherited neurological metabolic disorder resulting from deficiency of the lysosomal enzyme, **hexosaminidase** (form A, deficiency in α chain). This leads to the accumulation of its substrate, ganglioside G_{M2} (*see* **ganglioside**), in the brain. The disease is relatively common (1 in 2500 live births) among Ashkenazy Jews. There is motor and mental deterioration with an exaggerated startle response to sound; by 18 months of age, most patients are blind, deaf, and spastic; they die by the age of 3 years. *See also* **saposin**. [After Warren Tay (1843–1927), British physician, and Bernard Sachs (1858–1944), US neurologist.]

Tb *symbol for* terbium.

TBARS *abbr* for thiobarbituric acid-reactive substances, compounds of low-molecular-mass, particularly malondialdehyde, that are formed during the decomposition of lipid peroxidation products. They are measured in order to estimate the degree of cellular damage caused by oxygen radicals.

TBE a buffer for agarose gel electrophoresis that comprises 90 mM Tris-borate and 1 mM EDTA.

TBP *abbr. for* TATA-binding protein (*see* **TFII**, **RNA polymerase**).

tBu *abbr. for* tertiary butyl (alternative to Bu^t).

TBW *abbr. for* total body water; *see* **body water**.

Tc *symbol for* technetium.

TCA *abbr. for* **1** tricarboxylic acid. **2** trichloroacetic acid.

T-cap a protein of the Z disc of skeletal and cardiac muscle that is associated with the N-terminal portion of **titin**. Defects in T-cap or in titin lead to dilated cardiomyopathy.

Tψ C arm the base-paired segment of the clover-leaf model of **transfer RNA** to which the loop containing the base sequence TψC is attached (ψ = pseudouridine).

T cell *an alternative name for* **T lymphocyte**.

T_H cell *abbr. for* **helper cell**.

T-cell growth factor *abbr.*: TCGF; *an alternative name for* **interleukin 2**.

T-cell receptor a glycoprotein of the **immunoglobulin** superfamily. It is present on T-cell (**T-lymphocyte**) membranes and resembles class II MHC antigens (*see* **major histocompatibility complex**) but its α and β chains are disulfide bonded. T-cell receptors recognize target antigen in combination with MHC, transduce the signal into the T cell, probably through mediation by associated CD3 molecules (see **CD marker**), and bring about T-cell activation. A small number of adult T-cell receptors have γ and δ chains. This class of receptor appears first in ontogeny.

T-cell-replacing factor *abbr.*: TRF; *a former term for* some interleukins. *See* **interleukin 1**, **interleukin 5**.

TCGF *abbr. for* T-cell growth factor (i.e. **interleukin 2**).

T chain *an alternative name for* **secretory piece**.

tcl *see* **programming language**.

T-coffee *see* **multiple alignment program**.

TCP-1 *abbr. for* T-complex protein 1; a **molecular chaperone** that forms two stacked rings, 12–16 nm in diameter and is associated with other proteins in a 850–900 kDa complex. It is similar in function to Hsp60 (a **heat-shock protein**) in mitochondria and the ***groEL*** product in bacteria (*see also* **chaperonin**).

TC system a classification system of membrane transport proteins, using a five-digit designation for each of the defined and sequenced transport proteins. It comprises several classes (1 Pores and channels; 2 Electrochemical-potential-driven transporters; 3 Primary active transporters; 4 Group translocators; 5 Transmembrane electron carriers; 8 Accessory factors involved in transport; 9 Incompletely characterized transport systems), each class containing several subclasses; the subclasses are divided into families, the families into subfamilies and these then contain all the relevant individual proteins. Thus, for example, bacterial Ag^+-exporting ATPase is TC 3.A.3.5.4.

T-DNA *abbr. for* transfer DNA; that part (23 kb) of the *Agrobacterium* **Ti plasmid** that is incorporated into the genome of infected plant cells. It codes for an **opine**, usually **nopaline** or **octopine**, which the transformed cells produce and the bacteria then use. Each end of the T-DNA is flanked by a nearly identical 25 bp sequence; the righthand one is essential for the transfer process.

TDP *abbr. for* **1** ribosylthymine diphosphate *or* ribothymidine diphosphate. **2** thymidine diphosphate (dTDP is recommended).

Tdr *or* **TdR** *or* **TDR** *abbr. for* thymine deoxyriboside (i.e. thymidine). Use deprecated; the symbol dThd is recommended.

TdT *abbr. for* **terminal deoxynucleotidyltransferase**.

Te *symbol for* tellurium.

TE a buffer commonly used for dissolving DNA and comprising 10 mM Tris-chloride and 1 mM EDTA at pH 7.4, 7.6, or 8.0.

TEA *abbr. for* **1** triethanolamine; $N(CH_2CH_2OH)_3$; a base used in the preparation of buffers, pK_a (25°C) 7.90. **2** tetraethylammonium; used (as the chloride) to block sympathetic and parasympathetic ganglionic transmission.

TEAE *abbr. for* the triethylaminoethyl group, $(C_2H_5)_3NCH_2CH_2$–. It is used in hydroxylated chromatographic support matrices, e.g. cellulose, Sephadex, to form anion-exchange columns.

α-tectorin a protein (2155 amino acids) that, like otogelin, is specific to the cochlear tectorial membrane. It contains a C-terminal transmembrane segment, an N-terminal domain similar to one in **entactin**, and four vWF domains. Several mutations are associated with an autosomal recessive form of isolated deafness.

teichoate the anionic form of **teichoic acid**.

teichoic acid any polymer occurring in the cell wall, membrane, or capsule of Gram-positive bacteria and containing chains of glycerol phosphate or ribitol phosphate residues. Additionally, carbohydrates are linked to glycerol or ribitol, and some –OH groups are esterified with D-alanine.

tektins a family of similar proteins that are adapted to the assembly of a variety of eukaryotic cell structures. Tektins have common features that adapt them to sensitive and specific associations with molecules of their own kind; they have similar amino-acid compositions: they include actin, actin-like proteins, some microtubule proteins, mitochondrial structural protein, and erythrocyte membrane proteins.

tele a designator of the position of one of the nitrogens of the histidine imidazole ring, indicating the nitrogen furthest from the side chain. It is often symbolized by τ, as in N^τ. *Compare* **pros**.

teleology the doctrine or study of ends or final causes, especially as related to the evidences of design or purpose in nature; the use of design, purpose, or utility as an explanation of any natural phenomenon. An example of a teleological concept in biology is that organs are made to react for the good of the organism as a whole.

teleonomy the idea that the existence of a structure or a function in an organism must have conferred an evolutionary advantage upon that organism.

teleost any member of the infraclass Teleosti, comprising fishes with rayed fins and a swim bladder; it includes most of the extant bony fishes.

telestability the transmission of three-dimensional stability from a stable part of a macromolecule to an inherently less stable part.

telethonin a protein that colocalizes with actin in the Z disc of skeletal muscle, where it interacts with **FATZ** and, through its N-terminal 140 residues, with the same region of titin. Two nonsense mutations in the gene at 17q12 result in autosomal recessive limb-girdle muscular dystrophy type 2G.

telokin the C-terminal sequence of smooth muscle **myosin-light-chain kinase** expressed as an independent protein. It binds calmodulin.

telolysosome a **lysosome** that has accumulated so much indigestible residue that it is unable to accumulate further material to be digested. The structure still contains enzymes but these are no longer renewed. It is a type of **residual body**.

telomerase EC 2.7.7.–; *other name*: telomerase reverse transcriptase (*abbr.*: TERT); a DNA polymerase enzyme involved in **telomere** formation, and in telomere elongation to maintain the telomere sequences during replication. The catalytic subunit contains several sequence motifs characteristic of reverse transcriptase and at least one telomerase-specific motif. Activity is undetectable in most human somatic cells but is present in germ-line cells, in ≈90% of tumours, and in immortalized cell lines. The enzyme recognizes the G-rich strand of an existing telomere repeat sequence, elongating it in the 5′ to 3′ direction. The yeast *Candida albicans* contains two highly homologous catalytic subunits each of 867 amino acids. In fission yeast, the core enzyme contains Est2p before the S phase, and becomes activated late in S phase when Est1p and Est3p are recruited to the core (*see* ***EST1***). The RNA component includes a template for synthesizing the G-rich repeating sequence, and in humans is bound by dyskerin.

telomerase-associated protein a human protein of 2629 amino acids that interacts with the RNA component of **telomerase**. It contains two sequence repeats in the N-terminal region, a central NTP-binding domain, and WD40 repeats in the C-terminal region.

telomere the DNA–protein structure that seals either end of a chromosome. Telomeric DNA consists of simple tandemly repeated sequences specific for each species. In human germline cells the 3′ end of each chromosome contains 1000–1700 repeats of the hexanucleotide TTAGGG, and the 5′ end contains the complementary repeats. In somatic cells the repeat number decreases with each round of replication. Telomeric sequences are added to the 3′ terminus of chromosomal DNAs by **telomerase**, thereby maintaining telomere length. **TEP-1** binds to telomeric repeats. **—telomeric** *adj.*

telomere-specific protein-1 *see* **TEP-1**.

telomeric repeat-binding factor (*abbr.*: TRF) *an alternative name for* **TEP-1**.

telopeptide any of the peptides that protrude from the triple-helical body of **tropocollagen**, and have a composition different from the triple-helical portions. They are removed by proteases, with concomitant breakage of intramolecular interchain bonds. They are thought to occupy near-terminal positions. The antigenic response to injected heterologous tropocollagen is directed against these telopeptide appendages external to the triple helix.

telophase the final stage of **mitosis** or **meiosis** in which the nuclei form in the daughter cells.

TEM *or* **T.E.M.** *abbr. for* **1** transmission electron microscope; *see* **electron microscope**. **2** Tris–EDTA–mercaptoethanol (buffer).

TEMED *abbr. for* *N,N,N′,N′*-tetramethylethylenediamine; *N,N,N′,N′*-tetramethyl-1,2-diaminoethane; a polymerizing agent used in the preparation of polyacrylamide gels. It stabilizes free radicals produced by ammonium persulfate.



temperate phage a **bacteriophage** that, following infection of its host bacterium, may either enter the lytic cycle, like a **virulent phage**, or establish a symbiotic relationship with the host cell that results in its perpetuation in the descendants of the bacterium. Bacteria carrying temperate phage are said to be **lysogenic**, while the carried phage is called a **prophage**.

temperature *abbr.*: temp.; a fundamental physical quantity of a body, region, or system that determines the direction of net heat flow between it and its surroundings. If two systems have the same temperature they are in thermal equilibrium and there is no net heat flow between them. If they have different temperatures they are not in thermal equilibrium and heat flows from the system of higher temperature to that of lower temperature. Essentially there are two different methods of measuring temperature. One is to use a scale of values set up between arbitrary fixed points based on reproducible temperature-dependent events. For example, the **Celsius temperature** scale uses a freezing point and boiling point of water as fixed points, to which are assigned the values 0 and 100, respectively; the scale between them is divided into 100 degrees. Although widely used for many practical purposes, it lacks a theoretical basis and is unsuitable in many scientific contexts. Instead, the concept of **thermodynamic temperature** is used. This is defined in terms of the second law of thermodynamics (*see* **thermodynamics**) and is independent of any particular substance. However, in practice thermodynamic temperatures cannot be measured directly. Consequently, a practical realization of the thermodynamic temperature scale is used, called the **International Practical Temperature Scale** (IPTS). This is based on a number of fixed points, and is measured in **kelvins**; it defines temperature down to 13.81 kelvins, the triple point of equilibrium hydrogen.

temperature coefficient of a reaction *symbol*: Q_{10}; the factor by which the velocity of a chemical reaction is increased by raising the temperature, t, by 10°C. Usually it is the ratio of the rate of reaction at $(t + 10°)$ to that at t, denoted by $Q_{10} = k_{t+10}/k_t$, where k_{t+10} and k_t are the rate constants at the respective temperatures. The Q_{10} value of homogeneous chemical reactions is generally in the range 2–3; many enzyme-catalysed reactions and physiological processes exhibit, over a limited range of temperatures, a Q_{10} value of ≈2. *See also* **Arrhenius equation**.

temperature jump a technique used in **relaxation kinetics** for the study of enzyme mechanisms in which the temperature is raised rapidly (e.g. over about 1 μs), the reaction being monitored during this and the subsequent (very short) period during which the system relaxes to a new equilibrium.

temperature-sensitive mutation a mutation that is manifest in only a limited range of temperature. The mutant carrying such a mutation behaves normally at the lower, **permissive temperature**, but when grown at the lower or higher, **restrictive temperature**, it shows the mutant phenotype.

template a macromolecule whose structure serves as a pattern for the synthesis of another macromolecule. The term applies particularly to a nucleic acid on which another nucleic acid of complementary base sequence is synthesized, as in genetic **transcription**, or in the case of messenger RNA, on which a polypeptide is synthesized (genetic **translation**).

template RNA *an alternative name for* **messenger RNA**.

template strand *see* **noncoding strand**.

TEMPO *abbr. for* 2,2,6,6-tetramethylpiperidinooxy; 2,2,6,6-tetramethylpiperidine 1-oxyl; a stable free radical used as a spin label in electron spin-resonance spectroscopy.



temporal gene any gene that 'programs' a system in time, determining the activation of genes controlling different developmental stages in various cell types.

tenascin a glycoprotein of the extracellular matrix that is widely distributed and prominent during embryonic development, being produced by mesenchymal and glial cells. In adults it is present in small amounts in the central nervous system, cartilage, soft-tissue stroma, and close to basement membranes, but is prominent in a variety of tumours and in areas of wound healing. It consists of six identical (or similar) polypeptide chains, which radiate from a central knob, like the spokes of a wheel, with a knob at the free end of each. Several isoforms (1573 to 2203 amino acids) result from alternative splicing from one gene, and differ by tissue and time of appearance during development. The central knob contains the hydrophobic N-termini and their eight cysteine residues, which play a part in hexamer formation. Each chain contains ≈15 epidermal growth factor repeats and up to 15 ≈90-residue fibronectin repeats, and a C-terminal 210-residue segment rich in basic amino acids. Tenascin interacts with the cell-surface transmembrane proteoglycan **syndecan** and with fibronectin. It promotes or inhibits cell adhesion depending on cell type. *Other names*: hexabrachion; cytotactin; neuronectin; gmem; ji; myotendinous antigen; glioma-associated extracellular matrix antigen; gp150–225.

teniposide a semisynthetic lignan derivative prepared from **podophyllotoxin**. It acts like **etoposide**, but is a stronger cytotoxin.



ten-minute phosphate *see* **labile phosphate**.

tense form *or* **taut form** *abbr.*: T form; the form of an allosteric protein that has a lower affinity for a ligand than the R form (**relaxed form**). *See* **Monod–Wyman–Changeux model (for allosteric interaction)**.

tenside any of the group of surface-active compounds widely known as **detergents**. The name derives from their effects on surface tension.

tension 1 the concentration of a gas expressed as the partial pressure of the gas. **2** the force exerted by stretching any material. **3** voltage, electromagnetic force, or potential difference, as in high tension, low tension.

tensor 1 *(in mathematics)* a quantity expressing the ratio in which the length of a **vector** is increased. *Compare* **scalar**. **2** *(in anatomy)* a muscle that stretches or tightens some part while not altering the direction of the part.

tentoxin cyclo[L-leucyl-*N*-methyl-(*Z*)-dehydrophenylalanyl-glycyl-*N*-methyl-L-alanyl]; a cyclic tetrapeptide isolated from *Alternaria alternata*. It induces chlorosis in some plant species when applied to the germinating seedling.

TEP-1 *abbr. for* telomere-specific protein-1; *other name*: telomeric repeat binding factor (*abbr*.: TRF); a protein (439 amino acids) associated with telomeres, where it is a substrate for tankyrase, which causes its release from telomeric DNA. It is also a component of the large ribonucleoprotein complexes known as **vaults**, where it is a substrate for V-PARP. It contains an N-terminal aspartate and glutamate-rich region, two nuclear localization signals, and a sequence strongly homologous to the DNA-binding repeats of MYB.

Ter *see* **reactancy of enzymes**.

tera+ *symbol*: T; SI prefix denoting 10^{12} times.

terato+ *or (before a vowel)* **terat+** *comb. form* denoting congenital abnormality.

teratocarcinoma a **teratoma** that includes carcinomatous cells.

teratogen a substance that produces malformations in embryos. —**teratogenic** *adj.*

teratoma a tumour composed of disorganized tissues that are foreign embryologically to the tissue normally found at the site. Teratomas most frequently occur in testis or ovary, and may be derived from remnants of multipotential embryological cells that can differentiate into many cell types.

TERM a family of F-actin binding proteins, named from **talin** and the related proteins **ezrin**, **radixin**, and **moesin**.

terminal amino acid the amino-acid residue at the end of a peptide or polypeptide chain. The **C-terminal amino acid** is the one that has a free α-carboxyl group (*see* **C terminus**); the **N-terminal amino acid** is the one that has a free α-amino group (*see* **N terminus**).

terminal deletion *see* **deletion**.

terminal deoxynucleotidyltransferase *abbr*.: TdT; EC 2.7.7.31; *recommended name*: DNA nucleotidylexotransferase; *systematic name*: nucleoside-triphosphate:DNA deoxynucleotidylexotransferase; *other names*: terminal transferase; terminal deoxyribonucleotidyltransferase. An enzyme, commonly isolated from calf thymus, that catalyses the successive transfer of deoxynucleotide residues from the corresponding nucleoside triphosphates to the 3′ end of an oligo- or polydeoxynucleotide. It is a template-independent, Mg^{2+}-dependent **DNA polymerase**.

terminal oxidase an enzyme in a respiratory chain that transfers electrons from other carriers such as quinol or cytochrome *c* to oxygen, forming water..

terminal tip *an alternative name for* **leaf** (def. 3).

terminal transferase *see* **terminal deoxynucleotidyltransferase**.

terminal web the cortical network of **cytoskeleton** filaments under the plasma membrane. Actin filament bundles may be attached, and it contains a dense network of **spectrin** molecules.

termination codon *or* **terminator codon** any **codon** that signals the termination of a growing polypeptide chain. *See also* **amber codon**, **ochre codon**, **stop codon**.

termination factor any protein that participates in the termination of either transcription (*see* **rho protein**) or translation (*see* **release factor**).

terminator (of transcription) a DNA sequence lying just downstream of the coding segment of a gene that is recognized by RNA polymerase as a signal to stop synthesizing messenger RNA during **transcription**.

termolecular reaction *see* **molecularity**.

ternary consisting of three parts.

ternary complex any complex formed between three chemical entities, e.g. a complex formed between an enzyme and two substrate molecules.

terpene any lipid that consists of multiples of **isoprene** (C_5H_8) units. Terpenes may be acyclic, cyclic, or multicyclic, saturated or unsaturated, and can be substituted by various functional groups, e.g. OH. Terpenes containing 10, 15, 20, 30, 40, or more carbon atoms per molecule are known as **mono-**, **sesqui-**, **di-**, **tri-**, **tetra-**, or **polyterpenes** respectively. The class includes alcohol, aldehyde, and carboxylic acid derivatives of terpene hydrocarbons. Isoprene is the only naturally occurring **hemiterpene**, i.e. having five carbons, but the phosphorylated compounds Δ^2- and Δ^3-isopentenyl diphosphates are key intermediates in terpene biosynthesis. *See also* **polyprenyl**.

terpenoid 1 resembling a **terpene** in chemical structure. **2** any member of a class of compounds characterized by an isoprenoid chemical structure (as in a **terpene**) and often including their oxygenated and hydrogenated derivatives.

Terramycin *a proprietary name for* **oxytetracycline** .

tert- *abbr.: t-; prefix (in chemical nomenclature)* signifying **tertiary** (def. 1).

tertiary *(in chemistry)* **1 a** *prefix*: *tert-* (*abbr*.: *t-*); describing an alkyl compound (e.g. an alkanol) in which the functional group (e.g. a hydroxyl group) is attached to a carbon atom linked to three others. **b** describing the carbon atom bearing the functional group in such a compound. **2** describing an amide or an amine in which three appropriate groups are attached to a nitrogen atom. **3** describing a salt formed by replacing all three of the ionizable hydrogen atoms of a tribasic acid by one, two, or three other cations of appropriate valency. *Compare* **primary**, **secondary**.

tertiary structure the level of protein structure at which an entire polypeptide chain has folded into a 3-D structure. The tertiary structure results from interactions between amino-acid residues that may be widely separated in the primary structure, but may be brought into proximity by the folding of the polypeptide chain. The forces of interaction between residues include hydrogen bonds and electrostatic attraction. The structure is stabilized in some proteins by disulfide bonds. In multichain proteins, the term tertiary structure applies to individual chains. *Compare* **primary structure**, **secondary structure**, **quaternary structure**.

Tes *or* **TES** *abbr. for N*-tris(hydroxymethyl)methyl-2-aminoethanesulfonic acid; 2-{[2-hydroxy-1,1-bis(hydroxymethyl)ethyl]amino}-ethanesulfonic acid; a **Good buffer substance**; pK_a (20°C) = 7.5.

tesla *symbol*: T; the SI derived unit of **magnetic flux density**. It is equal to one weber of magnetic flux per square metre; i.e. $1\ T = 1\ Wb\ m^{-2}$. [After Nikola Tesla (1856–1943), Croatian-born US physicist.]

testes-specific poly(A) polymerase *abbr*.: TPAP; a cytoplasmic poly(A) polymerase (70 kDa) that is specific to testes, and is involved in poly(A) tail extension of mRNAs expressed by haploid-specific genes. Male mice that lack the enzyme are infertile because spermiogenesis is arrested at the rounded spermatid stage.

testican a multidomain glycoprotein of testes.

testicular of, or relating to, the **testis**.

testicular feminization *or* **testicular feminisation** an inherited condition in which genetic males have developmental abnormalities ranging from a complete external female phenotype to partially masculinized ambiguous genitalia. The commonest form is X-linked and results from any of several hundred mutations in the androgen receptor that impair its sensitivity to the hormone. An autosomal recessive form results from many mutations that produce steroid 5α-reductase 2 deficiency and lack of 5α-dihydrotestosterone (*see* **steroid 5α-reductase**).

testis (*pl.* **testes**) the male gonad; in vertebrates there is typically a pair of testes, producing spermatozoa and synthesizing **androgens**.

testosterone 4-androsten-17β-ol-3-one; the principal and most potent androgen. It is formed from androstenedione by 3α(17β)-hydroxysteroid dehydrogenase (NAD^+) (EC 1.1.1.239), in Leydig cells of the testis. Testosterone is responsible during embryonic development for virilization, and promotes and maintains male secondary sex characteristics throughout life. It is also synthesized in the ovary from which some is secreted into the blood, but most is converted to estradiol. Its actions are in large part mediated by **dihydrotestosterone**, to which it is converted in target cells. *See also* **androgen receptor**.



testosterone

TetA a membrane-associated protein of Gram-negative bacteria that exports tetracycline from the bacterial cell thereby conferring antibiotic resistance. It is under the control of the **tetracycline repressor** (TetR). *See* **tetracycline resistant**.

tetanus 1 a disease resulting from infection with the bacterium *Clostridium tetani*. *See also* **tetanus toxin**. **2** *or* **tetany** a sustained contraction of a muscle. **—tetanal** *or* **tetanoid** *adj.*

tetanus toxin the protein toxin of *Clostridium tetani*, the causative agent of tetanus. It is a heterodimer of light and heavy chains. It blocks neural exocytosis and thus norepinephrine release, possibly as a result of a Zn^{2+}-dependent proteolysis of **synaptobrevin** by the light chain, but also by inhibition of a neuronal transglutaminase (protein–glutamine γ-glutamyltransferase, EC 2.3.2.13). The protein is synthesized as a precursor of 1314 amino acids. This is cleaved to yield the light chain (residues 1–456) and heavy chain (residues 457–1314).

tetanus toxoid the **toxoid** prepared from *Clostridium tetani* toxin and included in anti-tetanus immunogens.

tetany *an alternative term for* **tetanus** (def. 2).

tetO 1 a 42 bp operator sequence from the tetracycline resistance operon of *E. coli* (Tn10). **2** a gene in Gram-negative bacteria encoding a tetracycline resistance protein that abolishes the effect of the antibiotic on protein synthesis.

Tet-Off *a proprietary name for* a system for regulating the expression of transgenes *in vivo* by manipulating the concentration of **tetracycline**. The gene of interest is placed downstream from **tetO** tetracycline response elements. The tetracycline *trans*-activator tTA (a fusion protein incorporating the N-terminal 1–203 amino acids of the **tetracycline repressor** protein TetR and the C-terminal 127 amino acids of the HSV VP16 activation domain) binds to tetO response elements and activates transcription. Addition of tetracycline or doxycycline causes dissociation of tTA from the operator thereby turning off transcription of the gene of interest.

Tet-On *a proprietary name for* an adaptation of the **Tet-Off** system in which a modified *trans*-activator, **rtTA**, binds to **tetO** sequences in the presence of doxycycline thereby activating transcription of the gene of interest.

TetR *abbr. for* tetracycline repressor.

tetra+ *or (before a vowel)* **tetr+** *comb. form* **1** denoting four, fourfold, every fourth; *see also* **tetrakis+** (def. 1). **2** *(in chemical nomenclature)* (*distinguish from* **tetrakis+** (def. 2)) **a** indicating the presence in a molecule of four identical specified unsubstituted groups; e.g. tetrachloroethylene, tetramethylammonium chloride. **b** indicating the presence in a molecule of four identical inorganic oxoacid residues in linear anhydride linkage; e.g. sodium tetraborate.

tetracosa+ *or (before a vowel)* **tetracos+** *comb. form* indicating twenty-four.

tetracosactide *or* **tetracosactrin** *or* **cosyntropin** *generic names for* β$^{1-24}$-corticotropin, a synthetic polypeptide identical to the N-terminal 24 residues of **corticotropin**, and having all of its hormonal activity. It is sometimes known as 1–24 ACTH. Proprietary names include Synacthen.

tetracosapeptide a 24-residue peptide.

tetracycline 1 any of a group of broad-spectrum antibiotics that are also effective against rickettsial organisms, mycoplasmas, and certain protozoa. Their bacteriostatic activity depends on the direct inhibition of protein synthesis. They are active against protein synthesis on bacterial 70S or eukaryotic 80S ribosomes although 70S ribosomes are rather more sensitive. The tetracyclines are much more effective in intact bacteria than in eukaryotic cells because of selective absorption by bacterial cells. They inhibit the binding of aminoacyl-tRNA to the acceptor site on the ribosome. **2** any antibiotic based on the tetracycline nucleus (*see* **polyketide**). They include aureomycin (7-chlortetracycline); terramycin (5-oxytetracycline); declomycin (6-demethyl-7-chlorotetracycline); doxycycline (6-deoxy-5-oxytetracycline). *See also* **tetracycline resistant**.



tetracycline repressor *abbr.*: TetR; a homodimer that binds to tandem DNA operators through N-terminal alpha helix-turn-alpha helix domains thereby blocking expression of the associated *tetA* gene and its own gene *tetR*. *See* **TetA**, **tetracycline resistant**.

tetracycline resistant *abbr.*: TC^{r}; resistant to the effects of the antibiotic **tetracycline.** Three different mechanisms of tetracycline resistance are known – tetracycline efflux, ribosome protection, and tetracycline modification – and over 60 tetracycline resistance genes have been sequenced. In enteric bacteria two **transposons**, Tn1721 and Tn10, commonly carry the genes for tetracycline resistance. Tn10 encodes two proteins: a membrane-located protein (TetA, M_r 36 000) that appears to mediate resistance and a repressor protein, TetR (*see* **tetracycline repressor**), associated with the inducibility of tetracycline resistance. The membrane protein pumps the tetracycline out of the cells against a concentration gradient. Foreign DNA may be fused to the tetracycline-resistance gene in a cloning vector thereby enabling bacterial clones containing the foreign DNA to be selected from those lacking resistance to the antibiotic. The plasmid pBR322 confers resistance to both tetracycline and ampicillin. Insertion of a foreign DNA at certain sites inactivates either or both genes.

tetracycline sensitive *abbr.*: TC^{s}; sensitive to the effects of **tetracycline**.

tetradeca+ *or (before a vowel)* **tetradec+** *comb. form* indicating fourteen.

tetradecadienoic acid any 14-carbon straight-chain fatty acid having two double bonds. Tetradeca-3*E*,5*Z*-dienoic acid (**megatomic acid**) and the (3*Z*,5*Z*)-isomer are sex attractants for *Attagenus megatoma* and for *A. elongatulus* respectively.

tetradecapeptide a 14-residue peptide.

tetradecenoic acid any 14-carbon monounsaturated fatty acid. Tetradec-9*Z*-enoic acid (**myristoleic acid**) is the most common naturally occurring form, but the 4*Z*-isomer occurs in tohaku oil and the 5*Z*-isomer (**physeteric acid**) in sperm-whale oil.

tetraenoic describing an acid having four double bonds. In long-chain fatty acids of the *n*-6 or *n*-3 families (*see* **fatty acid**), these will be **methylene-interrupted double bonds**.

tetragonal symmetry an arrangement, e.g. of a crystal or of ligands around a metal ion in solution, having a single fourfold axis of **symmetry**.

tetrahydro+ *comb. form* indicating the presence of four hydrogen atoms at positions of specific interest (in relation to the parent compound, or as specified by a locant).

tetrahydrobiopterin *see* **biopterin**.

tetrahydrofolate *abbr.*: H$_4$folate *or* (not recommended) THF; *N*-[4-{[(2-amino-3,4,5,6,7,8-hexahydro-4-oxo-pteridin-6-yl)methyl]-amino}benzoyl]-L-glutamate; folate bearing additional hydrogens at positions 5, 6, 7, and 8 of the pterin moiety. It is formed by the action of **dihydrofolate reductase** on dihydrofolate with NADPH as co-substrate.



tetrahydrofolate

tetrahydrofuran *abbr.*: THF; tetramethene oxide; an organic solvent that is useful for bringing into aqueous solution compounds that are otherwise sparingly soluble in water. It is a cyclic ether that is moderately soluble in water.



tetrahydromethanopterin *abbr.*: H$_4$MPT; a derivative of 7-methylpterin (2-amino-4-hydroxy-7-methylpteridine) that is involved in methane formation in **methanogenic** bacteria. It undergoes a series of interconversions involving N^5 and N^{10}, analogous to those of the **folate coenzymes**, with formation of formyl-H$_4$MPT, methenyl-H$_4$MPT, methylene-H$_4$MPT, and methyl-H$_4$MPT.



Tetrahymena a genus of ciliated protozoans, members of which are used in studies of ciliary axonemes, self-splicing RNA, and telomere reproduction.

tetrakis+ *prefix* **1** denoting four times, quadrupled; *see also* **tetra+** (def. 1). **2** *(in chemical nomenclature)* (*distinguish from* **tetra+** (def. 2)) **a** indicating the presence in a molecule of four identical specified groups each substituted in the same way; e.g. tetrakis(2-hydroxyethyl)ammonium chloride. **b** indicating the presence at separate positions in a molecule of four identical inorganic oxoacid residues; e.g. inositol 1,3,4,5-tetrakisphosphate.

tetrakisphosphate *see* **multiplying prefix**.

tetraloop a tetranucleotide **hairpin loop**.

tetramer a molecular complex having four components or subunits. If the subunits are identical, the term **homotetramer** is used; if any one is different from any other, the complex is called a **heterotetramer**.

tetraose tetrasaccharide; a stem name for any oligosaccharide consisting of four of the same residues per molecule in one type of linkage, as in cellotetraose. *Distinguish from* **+tetraose** and **tetrose**.

+tetraose *suffix* used to indicate a glycolipid containing an oligosaccharide moiety composed of four (identical or different) sugar residues, as in gangliotetraose. *Distinguish from* **tetraose**.

tetrapeptide a four-residue peptide.

tetraplex DNA *or* **quadruplex DNA** a four-stranded DNA structure adopted by sequences rich in guanine bases. Two major classes are known. The first involves the folding back of a repetitive sequence of guanines resulting in antiparallel strands. The other is characterized by the association of four independent parallel strands. *See also* **triplex DNA**.

tetrapyrrole a structure found in **heme** and other **porphyrins**, **chlorophylls**, **bacteriochlorophylls**, **phytochromes**, **phycobilins**, and **corrinoids** (e.g. vitamin B$_{12}$). It consists of four pyrroles variously substituted and linked to each other through carbons at the α position; in the case of hemes, these links are formed by one-carbon units (methylidene group). Characteristically, a metal is found coordinated to the pyrrole nitrogens, including iron (in hemes), magnesium (in chlorophylls), copper (in **turacin**, the pigment of turaco bird feathers), and nickel (in **factor F$_{430}$**, a prosthetic group in methanogenic bacteria). Synthesis is via aminolevulinic acid, which is synthesized from glycine and succinyl-CoA in animals and nonphotosynthetic organisms by 5-aminolevulinate synthase. For further steps in the pathway, *see* **porphobilinogen synthase**, **hydroxymethylbilane synthase**, **uroporphyrinogen-III synthase**, and **uroporphyrinogen decarboxylase**.

tetraric acid an **aldaric acid** derived by oxidation of a **tetrose** at C-1 and C-4. There are three tetraric acids, D-, L-, and *meso-* **tartaric acids**.

tetrasaccharide an oligosaccharide with four **monosaccharide** units.

tetrasomic describing any polysomic cell, tissue, or individual in which one chromosome is represented four times in an otherwise **diploid** chromosome complement. *Compare* **monosomic**, **nullisomic**, **trisomic**. —**tetrasomy** *n.*

tetraspanin any of a family of integral membrane proteins that contain four transmembrane helices and have intracellular N- and C-termini. They contain <350 amino acid residues and occur mostly in vertebrates.

tetratricosapeptide repeat *abbr.*: TPR; a degenerate consensus sequence of 34 amino acids found in multiple copies in several fungal and other proteins. These sequences participate in RNA synthesis regulation, protein import, and *Drosophila* development. Each sequence has two regions that are stereochemically complementary in α-helical conformation, and form a hole and a knob surrounded by hydrophobic residues.

tetrazolium salt any compound that is readily reduced to highly coloured, sparingly soluble formazan compounds. Tetrazolium salts are employed in the assay of some dehydrogenases, and include Blue Tetrazolium and Nitroblue Tetrazolium. **1*H*-tetrazole** is used in the chemical synthesis of oligonucleotides.

tetritol any alditol having a chain of four carbon atoms in the molecule.

tetrodotoxin *abbr.*: TTX; *also known as* **fugu toxin**; a toxin found in the liver and ovaries of the **fugu**, or puffer fish (order Tetraodontiformes, from which the toxin derives its name). It is a specific, reversible blocker of voltage-gated sodium channels, and can cause death by increasing paralysis. The LD$_{50}$ in mice is 8 μg kg^{-1}. It does not block potassium or chloride channels.



tetrose any aldose having a chain of four carbon atoms in the molecule. *Distinguish from* **tetraose**.

tetrulose any ketose having a chain of four carbon atoms in the molecule.

T-even phage any one of the **bacteriophages** T2, T4, or T6 of *Escherichia coli*. These DNA phages share a number of morphological, biochemical, and other features that distinguish them as a group from **T-odd phages** and are important historically in research on phages.

Texas Red a red-emitting fluorophore and a sulfonyl chloride derivative of sulforhodamine 101. It is used with **FITC** in dual-label flow microfluorimetric and fluorescent microscopic studies because its excitation and emission spectra do not overlap with those of fluorescein.

text mining the automated process by which large volumes of unstructured, natural-language text are analysed in order to pinpoint and extract user-specified information.

TF *abbr. for* **1** tissue factor. **2** transcription factor.

TFII any of a group of **transcription factors** for eukaryotic RNA polymerase II promoters. **TFIIA** is needed for TFIID binding. **TFIIB** binds to RNA polymerase. **TFIID** has two components, a TATA-binding protein that binds to the **TATA box**, and one of a number of accessory factors; it shows weak homology with bacterial **sigma factors**. **TFIIE** binds to RNApolymerase; it also shows weak homology with bacterial sigma factors. It is a tetramer of two α chains and two β chains.

TFIII any of a group of **transcription factors** for eukaryotic RNA polymerase III promoters. **TFIIIA** is a zinc-finger protein (*see* **zinc finger**) that binds both DNA and the 5S RNA transcript. **TFIIIB** is an RNA polymerase-binding protein. **TFIIIC** (*or* **tau**) is a heterotrimer.

TFA *abbr. for* trifluoroacetic acid.

T form *abbr. for* tense form (*or* taut form).

TG1 a derivative of the *E. coli* strain JM101 used for the propagation of bacteriophage M13 vectors.

TGF *abbr. for* transforming growth factor.

Th *symbol for* thorium.

thalassemia *or (esp. Brit)* **thalassaemia** any disease resulting from an inherited defect in the rate of synthesis of one of the types of globin subunits of **hemoglobin**. Such defects lead to ineffective erythropoiesis, hemolysis, and a variable degree of anemia. In **alpha thalassemia** the defect is in the production of α globin and there is concomitant excessive β- and γ-globin production leading to the formation of various abnormal hemoglobins. In **beta thalassaemia** the formation of β globin is defective with an excessive synthesis of α globin and the continued production of fetal hemoglobin ($\alpha_2\gamma_2$).

thalidomide *N*-(2,6-dioxo-3-piperidyl)phthalimide; *α*-phthalimidoglutarimide; a synthetic tranquillizer and sedative. It was first used (in the 1950s) as a racemate, which causes severe fetal abnormalities such as the absence or shortening of one or more limbs. The L(*S*) enantiomer apparently has the teratogenic activity (*see* **teratogen**), while the D(*R*) enantiomer has the desired sedative property. The situation is unclear since thalidomide racemizes rapidly *in vivo*.



(*S*)-form

THAM *abbr. for* tris(hydroxymethyl)aminomethane; *see* **Tris**.

thanatogene a hypothetical gene whose expression is supposed to lead to cell death in terminally differentiated cells. [From Greek *thanatos*, death.]

thanatophoric dysplasia an autosomal dominant form of severe dwarfism that is usually lethal at or soon after infancy. It results from mutations in fibroblast growth factor receptor 3.

thapsigargin a tumour-promoting sesquiterpene lactone. It inhibits the calcium pump **SERCA** and increases cytosolic Ca^{2+}.



thapsigargin

thaumatin a sweet-tasting, basic, 20 kDa protein isolated from the berries of the bushy African plant, *Thaumatococcus danielli*; there are five different forms. Its sweetness in aqueous solution is 2500 times greater than that of sucrose; it has sequence similarities with **monellin**.

Thd *symbol for* a residue of the ribonucleoside ribothymidine; ribosylthymine; thymine riboside (alternative to T). *Compare* **dThd**.

Thd5′*P* *symbol for* ribothymidine 5′-phosphate.

Thd5′*PP* *symbol for* ribothymidine 5′-diphosphate (alternative to ppT).

Thd5′*PPP* *symbol for* ribothymidine 5′-triphosphate (alternative to pppT).

thebaine one of the alkaloids present in opium.

T-helper cell *see* **helper cell**.

theobromine 3,7-dimethylxanthine; the principal alkaloid of the cacao bean. Its actions are similar to those of **theophylline**. *See also* **caffeine**.



theophylline 1,3-dimethylxanthine; a competitive inhibitor of cyclic AMP phosphodiesterase. It has diuretic and cardiac stimulatory action, and relaxes smooth muscle; it is a bronchodilator. *See also* **caffeine**, **theobromine**.



Theorell–Chance mechanism *(in enzyme kinetics)* an enzyme mechanism in which it is obligatory for substrates to bind in a certain order and in which no kinetically significant ternary complex is formed. [After Axel Hugo Theodor Theorell (1903–82), Swedish biochemist, and Britton Chance (1913–), US biochemist.]

theoretical plate a term used in the analysis of chromatography column performance; the higher the number of theoretical plates achieved, the greater the efficiency of the column. The number of theoretical plates is derived by dividing the peak width by the retention time. The term derives from the concept that the column can notionally be divided into a large number of 'slices' or 'plates' at each of which the separation process will progress. *See also* **effective theoretical plate number**.

therapeutic index the ratio of **LD50** (median lethal dose) to **ED50** (median effective dose), used in quantitative comparison of drugs.

therm+ *a variant form of* **thermo+** (before a vowel).

thermal analysis *see* **differential thermal analysis**, **differential scanning calorimetry**.

thermal conductance *symbol*: G; the ability of a material to conduct heat, measured as the ratio of the heat flow rate, Φ, to the temperature difference, i.e. $G = \Phi/\Delta T$. SI units are watts per kelvin.

thermal conductivity *symbol*: λ *or* k; a measure of the ability of a material to transmit heat. It is the heat flux in W m^{-2} divided by the temperature gradient; i.e. $\lambda = J_q /(\mathrm{d}T/\mathrm{d}l)$, where J_q is the heat flux and $\mathrm{d}T$ is the thermodynamic temperature difference over the length, $\mathrm{d}l$. It is measured in watts per metre per kelvin.

thermal denaturation profile a curve relating some physical property of a biopolymer in solution (e.g. viscosity, optical absorbance, or optical rotation) to temperature. The shape of the curve indicates the occurrence of physical changes in the biopolymer, e.g. separation of the two strands of double-stranded nucleic acid or alteration in the tertiary structure of a protein. *See also* **denaturation**, **melting temperature**.

thermal equilibrium the condition of a system when there is no tendency for heat to flow within it, or to or from its surroundings; all parts of the system and its surroundings are at the same temperature.

thermistor a semiconductor whose resistance is sensitive to temperature. [From thermal resistor.]

thermitase EC 3.4.21.66; *other name*: thermophilic *Streptomyces* serine protease; a Ca^{2+}-binding serine proteinase from *Thermoactinomyces vulgaris*, and a homologue of **subtilisin**. It is inhibited by *p*-mercuribenzoate, which reacts with the cysteine residue near the active-site histidine.

thermo+ *or (before a vowel)* **therm+** *comb. form* indicating a relationship to heat or heat transference.

thermobarometer a control manometer and flask used in a **Warburg apparatus**, or other constant-volume-type respirometer, to compensate for changes in temperature and barometric pressure during the course of an experiment.

thermochromism any reversible change of colour of a substance with change of temperature. *Compare* **electrochromism**, **photochromism**. **—thermochromic** *adj.*

thermocouple a device consisting of two pieces of dissimilar metals joined together at a point, their free ends being connected to an instrument to measure electromotive force (emf). The emf produced at the metal–metal junction is a function of the junction temperature, hence a thermocouple may be used to measure temperature. The phenomenon is known as the **Seebeck effect**.

thermodynamicase *(sometimes) an alternative name for* **protein disulfide isomerase**.

thermodynamic equilibrium constant *see* **equilibrium constant**.

thermodynamics the study of the laws that govern the conversion of energy from one form to another, the direction in which heat will flow from one system to another, and the availability of energy to do work. The **zeroth law of thermodynamics** states that if two systems are each in thermal equilibrium with a third system, then they must be in thermal equilibrium with each other. The **first law of thermodynamics** or the **law of conservation of energy** specifies that in an isolated, adiabatic system the sum of the internal energies of all kinds, U, remains constant, whatever may be the changes within the system itself. If a system of constant mass gains heat, q, and has work, w, done on it then a change in its internal energy, ΔU, occurs such that $\Delta U = q + w$. (Where the system loses heat, $q < 0$, and where work is done by it, $w < 0$.) The **second law of thermodynamics** is concerned with the restrictions in the direction of energy flow in natural systems and takes account of the irreversibility of natural processes. It specifies that the entropy of any system, S, unlike energy, is not conserved but increases with time in any spontaneous process in an isolated system. In the limiting case of a reversible process, the increase in entropy of a system, $\mathrm{d}S$, is defined as the heat absorbed by the system, $\mathrm{d}q_{\mathrm{rev}}$, divided by the thermodynamic temperature, T; i.e. $\mathrm{d}S = \mathrm{d}q_{\mathrm{rev}}/T$. The **third law of thermodynamics** is concerned with the fact that the difference between the change in enthalpy, ΔH, and the change in the free energy, ΔG, of a system diminishes as the temperature of the system diminishes, and the value of $(\Delta H - \Delta G)$ tends to zero as the thermodynamic temperature tends to zero. This requires that the change in the heat capacity of the system (at constant pressure), ΔC_{p}, and ΔS must fall to zero at 0 K.

thermodynamic temperature *or (formerly)* **absolute temperature** *symbol*: T; a fundamental physical quantity – one of the seven SI base quantities – defined in terms of the laws of thermodynamics, independently of any particular substance. The SI unit is the **kelvin**. *See also* **temperature**.

thermogenesis the generation of heat by specialized tissues in mammals and in flowers or inflorescences of plants, e.g. arum lilies (*Arum maculatum*). In mammals, this function is performed by **brown adipose tissue**. **—thermogenic** *adj.*

thermogenin *another name for* **brown fat uncoupling protein**.

thermolabile unstable at elevated temperatures. *Compare* **thermostable**. **—thermolability** *n.*

thermolysin EC 3.4.24.27; *other name*: *Bacillus thermoproteolyticus* neutral proteinase; a heat-stable metalloendoproteinase produced by *B. thermoproteolyticus*; it contains four zinc and calcium ions. It catalyses the preferential cleavage: Xaa-|-Leu > Xaa-|-Phe.

thermolysis the cleavage of one or more covalent bonds caused by exposing a chemical compound to a raised temperature. *See also* **pyrolysis**. **—thermolytic** *adj.*

thermometer any instrument for measuring temperature. All thermometers depend on the change with temperature of some easily measured physical property such as the expansion of mercury (or other liquids) or the change in electrical resistance. *See also* **thermocouple**.

thermometry the branch of physics concerned with thermometers and the measurement of temperature.

thermoneutron activation *an alternative name for* **radioactivation**.

thermoosmosis the flow of solvent, especially water, across a membrane as a result of a temperature gradient across the membrane.

thermophile an organism, especially a microorganism, that can tolerate high temperatues and that grows optimally at temperatures above 45°C. *Compare* **mesophile**, **psychrophile**. **—thermophilic** *adj.*

thermoregulator any device or mechanism (including physiological) that controls the temperature of an environment. **—thermoregulatory** *adj.*

ThermoSequenase *proprietary name for* a DNA polymerase modified by protein engineering to have the thermal stability required for **cycle sequencing**.

thermospray *or* **electron spray mass spectrometer** (*abbr.*: ESMS); an instrument that directly applies a proportion of the eluent of a liquid chromatograph to a mass spectrometer for analysis of resolved components.

thermostable maintaining characteristics or function under a change (normally increased) of temperature. *Compare* **thermolabile**. **—thermostability** *adj.*

thermostat 1 an automatic device for regulating temperature, especially maintaining a constant temperature. Such devices often work by cutting off the supply of heat when the required temperature is exceeded and restoring it when the temperature falls below the required value. **2** to provide with or to control using a thermostat. **—thermostatic** *adj.*

thermotitration the determination of the endpoint of a reaction, or the point at which the reaction reaches equilibrium, by measurement of heat of reaction.

THESIT *an alternative name for* $C_{12}E_9$ (*see* **$C_x E_y$**), or Lubrol PX (*see* **Lubrol**).

theta *symbol*: θ (lower case) *or* Θ (upper case); the eighth letter of the Greek alphabet. For uses *see* **Appendix A**.

theta structure *or* **replication eye** *or* **replication bubble** the structure that forms during replication of circular duplex DNA by the opening up of the two strands. Under electron microscopy it looks like a Greek theta.

L-thevetose 6-deoxy-4-*O*-methyl-L-glucose; a component of some cardiac glycosides.

THF *abbr. for* **1** tetrahydrofuran. **2** tetrahydrofolate (H$_4$folate preferred).

thia+ *or (before a vowel)* **thi+** *comb. form* containing sulfur, especially in place of carbon. *See also* **thio+**.

thiamine *or (sometimes)* **thiamin** *or (formerly)* **aneurin(e)** *an alternative name for* **vitamin B_1** .

thiamine diphosphate *or (sometimes)* **thiamin diphosphate** *or (formerly)* **thiamin pyrophosphate** *abbr.*: TPP; *see* **vitamin B_1** .

thick filament a longitudinal assembly of **myosin** molecules occurring in muscle. The thick filaments are the major constituents of the A band of the **sarcomere** in skeletal muscle; they interact with the **thin filaments** to bring about muscle contraction (*see* **sliding filament model**).

thimet oligopeptidase a thiol-activated metallopeptidase (78.5 kDa) that prefers substrates 6–17 residues long, and cleaves them 3–6 residues from the C-terminus. It is present in cytosol or vesicles, has a neutral pH optimum, and is inactivated by oxidation.

thin filament a molecular complex of **actin**, **troponin** (composed of troponins I, T, and C), and **tropomyosin**, found in muscle tissue. In striated muscle the thin filaments span the I band and interdigitate between the ends of the **thick filaments** in the A band. Interaction between the thin and thick filaments brings about muscle contraction (*see* **sliding filament model**).

thin-film dialysis a type of **dialysis** that maintains the **diffusate** and the **retentate** in thin layers in intimate contact with the dialysis membrane in order to lessen the contribution to the overall rate of the process made by diffusion of solutes in free solution. Very rapid removal or exchange of small molecules can occur, especially if the volume ratio of diffusate to retentate is high. With appropriate membranes the technique may also be used for analytical studies of the size and conformation of peptides and proteins in solution.

thin-layer chromatography *abbr.*: TLC; chromatography on a thin layer of any of various powdered materials, including silicic acid, aluminium oxide, or cellulose. The layer, characteristically between 0.05 and 1 mm thick, is made to adhere to a sheet of glass, aluminium, or plastic. Thicker layers accept heavier loading, while thinner layers resolve more efficiently and rapidly. Resolving power is high, runs are rapid, and, because support materials such as silicic acid or aluminium oxide are inert to them, corrosive sprays, such as sulfuric acid, can be used to convert organic materials to carbon (a process known as charring), revealing them as black spots.

thio+ *or (sometimes before a vowel)* **thi+** *comb. form* **1** relating to or containing sulfur. **2** *(in chemical nomenclature)* denoting replacement of oxygen in a compound by (bivalent) sulfur. In trivial names of compounds it is used as a prefix (as in thiouracil; *compare* **uracil**), whereas in the systematic names of individual compounds it is used as an affix and is usually placed before the affix denoting an oxygen atom or an oxygen-containing group (as in ethanethiol; *compare* **ethanol**), although for organic sulfides, if named analogously to ethers by substitutive nomenclature, it replaces oxy+ (as in 3-(methylthio)propionate. *Compare* **thia+**. *See also* **mercapto+**.

thioacetal *see* **acetal**.

thiobarbituric acid 4,6-dihydroxy-2-mercaptopyrimidine. It reacts with aldehydes, particularly malondialdehyde, produced by oxidation of unsaturated fatty acids, to form a fluorescent red adduct.



thioctic acid *a less common name for* **lipoic acid**.

thiocyanate **1** the anion, N≡C–S⁻, derived from thiocyanic acid. **2** any salt of thiocyanic acid. **3** any organic compound containing the monovalent group –S–C≡N. *Compare* **isothiocyanate**.

thioester any organic compound formed, actually or formally, by the elimination of the elements of water either (1) between the carboxyl group of a carboxylic acid and a thiol, or (2) between the thiocarboxyl group of a thiocarboxylic acid and an alcohol or phenol. Thioesters formed by mechanism (1) are of general formula R^1–CO–SR^2, whereas those formed by mechanism (2) may be of general formula either R^1–CO–SR^2 or R^1–CS–OR^2.

thioether *an old name for* any organic sulfur-containing compound of general formula R^1–S–R^2. Sulfide is now the recommended generic name.

thiogalactoside transacetylase *see* **galactoside acetyltransferase**.

thioglucosidase EC 3.2.3.1; *systematic name*: thioglucoside glucohydrolase; *other name*: sinigrase. An enzyme that hydrolyses thioglucosides to the constituent thiol and sugar, e.g. sinigrin to glucose and *N*-(sulfoxy)-3-mercapto-3-butenimidate.

thioglycoside *or* ***S*-glycoside** any glycoside formed from a sugar and a thiol compound, e.g. **sinigrin**.

thiohemiacetal *see* **acetal**.

thiohemiketal *see* **acetal**.

thiohypoxanthine *an alternative name for* **mercaptopurine**.

thioinosine *symbol*: sI *or* Sno; 6-thioinosine; thiohypoxanthine riboside; mercaptopurine ribonucleoside; 9-*β*-D-ribofuranosyl-6-mercaptopurine; a synthetic nucleoside. *See also* **mercaptopurine**.



thioketal *see* **acetal**.

thiokinase any ATP-requiring enzyme of sub-subclass EC 6.2.1 (acid thiol ligases) that synthesizes CoA thioesters of various fatty acids. These enzymes (recommended names given first) are: (1) **acetate–CoA ligase**, which acts on acetate, propanoate, and propenoate; (2) **butyrate– CoA ligase**; EC 6.2.1.2; *other names*: fatty acid thiokinase (medium chain); butyryl-CoA synthetase; butanoate–CoA ligase (AMP forming); this acts on C_4 to C_{11} acids and on corresponding 3-hydroxy- and 2,3- or 3,4-unsaturated acids; (3) **long-chain-fatty-acid–CoA ligase**; EC 6.2.1.3; *other names*: fatty acid thiokinase (long chain); acyl-CoA synthetase; acid:CoA ligase (AMP forming); this acts on a wide range of long-chain saturated fatty acids, depending on the tissue of origin of the enzyme; and (4) **acetate–CoA ligase (ADP-forming)**; also acts on propionate and (very slowly) on butanoate.

thiol **1** *or (formerly)* **mercaptan** any organic compound containing –SH as the principal group directly attached to a carbon atom. **2** *or* **sulfhydryl** the (covalently linked) –SH group in any chemical compound.

+thiol *suffix (in organic chemical nomenclature)* indicating the presence of a **thiol** group attached to a carbon atom. *Compare* **mercapto+**.

thiolactomycin an antibiotic isolated from *Nocardia* spp. It selectively inhibits straight-chain fatty-acid synthases of the multienzyme complex type (as in *E. coli*) but not the multicatalytic protein type (as in *Saccharomyces cerevisiae*).

thiolase a misleading generic name for certain enzymes of differing chain-length specificity within sub-subgroup EC 2.3.1 (acyltransferases) that catalyse the **thiolysis** by coenzyme A of CoA thioesters of *β*-oxo fatty acids according to the general equation:

$$\text{RCO–CH}_2\text{CO–CoA + CoA = RCO–CoA + CH}_3\text{CO–CoA.}$$

Thiolases are thiol enzymes, their *S*-acyl derivatives being formed as intermediates in the reactions catalysed. Although the overall reactions are reversible, the equilibrium positions greatly favour cleavage. These enzymes include: **acetyl-CoA *C*-acetyltransferase** (EC 2.3.1.9) and **acetyl-CoA C-acyltransferase** (EC 2.3.1.16).

thiolate **1** the anion, R–S⁻, derived from a **thiol** (def. 1). **2** any salt of a thiol. **3** to introduce a thiol group into an organic compound. **—thiolation** *n.*

thiol proteinase *an old name for* **cysteine endopeptidase**.

thioltransacetylase A *see* **dihydrolipoamide *S*-acetyltransferase**.

thiolysis lysis of a covalent organic compound by a thiol; a reaction analogous to **alcoholysis** in which bond cleavage is mediated by nucleophilic attack by the –SH group of an alkanethiol. The term is applied to the **thiolase**-catalysed cleavage of a β-oxoacyl-CoA by coenzyme A in each turn of chain-length reduction during fatty-acid catabolism. —**thiolytic** *adj.*

thionein the apoprotein of a **metallothionein**.

thionin any of a group of small proteins, characterized by two conserved motifs, that occur in plants and are toxic to animals. The toxic principle of leaf thionin in barley is formed from residues 29–34 of a 137-amino-acid precursor. Thionins act by forming pores in the membranes of the affected organism. They are classified in the TC system under number 1.A.44.

thionucleoside any *N*-glycoside of any **thiopurine** or **thiopyrimidine**.

thionucleotide any phosphoric ester of any **thionucleoside**.

thiopurine any **purine** in which a thiol group has replaced a hydroxyl group. *Compare* **mercaptopurine**.

thiopyrimidine any **pyrimidine** in which a thiol group has replaced a hydroxyl group.

thioredoxin any of the widely occurring heat-stable hydrogen-carrier proteins of ≈12 kDa that serve as hydrogen donors in various reduction reactions, notably of ribonucleoside diphosphates to the deoxy analogues, and in the light-dependent reductive activation of various chloroplast enzymes (including several in the pentose-phosphate cycle). Chloroplast thioredoxin occurs in *f* and *m* forms, which show specificity in their enzyme-activating properties; a third form (designated *c*), of unknown function, occurs outside chloroplasts. Thioredoxins can exist in disulfide (i.e. oxidized) and dithiol (i.e. reduced) states, interconversion being catalysed by ferredoxin–thioredoxin reductases. *See also* **thioredoxin reductase (NADPH)**.

thioredoxin reductase (NADPH) EC 1.6.4.5; a flavoprotein (FAD) enzyme that catalyses the reaction:

$$\text{NADPH + oxidized thioredoxin =}$$
$$\text{NADP}^+ \text{ + reduced thioredoxin.}$$

thiotemplate mechanism *or* **protein thiotemplate mechanism** the mechanism of biosynthesis of *Bacillus brevis* peptide antibiotics, e.g. **gramicidin S** and **tyrocidin** A, in which the precursor amino acids, after activation, are bound as thioesters to the synthetase enzymes.

thiouracil *symbol*: Sur; 2-thiouracil; 4-hydroxy-2-mercaptopyrimidine; 4-oxy-2-thiopyrimidine; a thiopyrimidine found in seeds of members of the cabbage family (e.g. *Brassica* spp.) and as a minor base in certain types of ribonucleic acid, especially transfer RNA (*see also* **thiouridine**). Thiouracil, 6-methylthiouracil, and 6-propylthiouracil are used to treat hyperthyroidism and thyrotoxicosis. They inhibit biosynthesis of the thyroid hormones at the peroxidase-catalysed iodination and coupling steps.



thiouridine *symbol*: S *or* sU *or* Srd; either of two constitutional isomers occurring as minor nucleosides in certain types of ribonucleic acid, especially transfer RNA (tRNA): **2-thiouridine** (2-thiouracil riboside; 1-β-D-ribofuranosyl-4-oxy-2-thiopyrimidine; *symbol*: ^{2}S *or* s^{2}U), or its 5-methyl, 5-(methylaminomethyl), or 5-(methoxycarbonylmethyl) derivatives, which are found in some tRNA species in the first position of the anticodon; and **4-thiouridine** (4-thiouracil riboside; 1-β-D-ribofuranosyl-2-oxy-4-thiopyrimidine; *symbol*: ^{4}S *or* s^{4}U), which is found in some tRNA species elsewhere than in the anticodon.



2-thiouridine

third law of thermodynamics *see* **thermodynamics**.

thixotrope a gel that exhibits **thixotropy**.

thixotropy the property shown by certain fluids and gels of becoming less viscous when subjected to stress, e.g. by shaking or stirring, and of becoming more viscous again when the stress is relieved. —**thixotropic** *adj.*

Thr *symbol for* a residue of the α-amino acid L-threonine (alternative to T).

THR a gene family encoding thyroid receptors; part of a superfamily including receptors for steroids, retinoic acid, and vitamin D_3; *see* ***erbA***.

threading a fold-recognition method that identifies folds compatible with the sequences of proteins of unknown fold by threading the target sequence through template structures held in a reference library. In this process, the side chains are replaced and the main chain is kept constant, and the compatibility of the target with the template is estimated by means of pair potentials and solvation potentials. The approach is used when the target shows little or no similarity to any other sequence.

threitol active erythritol, *threo*-1,2,3,4-tetrahydroxybutane, *threo*-1,2,3,4-butanetetrol; an enantiomeric pair of polyols, configurationally isomeric with **erythritol**. D-Threitol occurs in certain fungi, e.g. the honey fungus, *Armillaria mellea*.

threo- a configurational prefix to the systematic name of a polyhydric alcohol, especially of a monosaccharide, used to indicate the particular stereochemical configuration of a set of two contiguous >CHOH groups that occurs in D-threose (see ***threose*** for structure) or L-threose, e.g. D-*threo*-2-pentulose for D-xylulose. *Compare* ***erythro-***.

threoninate **1** threonine anion; the anion, $\mathrm{CH_3{-}CH(OH){-}CH(NH_2){-}COO^-}$, derived from **threonine**. **2** any salt containing threonine anion. **3** any ester of threonine.

threonine *the trivial name for* α-amino-β-hydroxybutyric acid; (2*R**,3*S**)-2-amino-3-hydroxybutanoic acid; $\mathrm{CH_3{-}CH(OH){-}CH(NH_2){-}COOH}$; an α-amino acid with two chiral centres. Because molecules of threonine possess a second chiral centre, at C-3, in addition to the chiral centre at C-2 common to all α-amino acids other than glycine, the enantiomers L-threonine, (2*S*,3*R*)-2-amino-3-hydroxybutanoic acid (*symbol*: T *or* Thr), and D-threonine, (2*R*,3*S*)-2-amino-3-hydroxybutanoic acid (*symbol*: D-Thr *or* DThr), are diastereoisomeric with those of **allothreonine**, (2*R**,3*R**)-2-amino-3-hydroxybutanoic acid. [*Note*: the enantiomers of threonine may also be named semi-systematically as derivatives of threose: $\mathrm{L_s}$-threonine in amino-acid nomenclature is synonymous with 2-amino-2,4-dideoxy-$\mathrm{D_g}$-threonic acid in carbohydrate nomenclature, and $\mathrm{D_s}$-threonine with 2-amino-2,4-dideoxy-$\mathrm{L_g}$-threonic acid (the subscript letters s or g being added to the configurational prefixes where there might be uncertainty regarding the reference centre of chirality; *see* **D/L convention**).] L-Threonine is a coded amino acid found in peptide linkage in proteins; codon: ACA, ACC, ACG, or ACU. In mammals, it is an essential dietary amino acid, is glucogenic, and its deficiency causes fatty liver. The fungal toxins phalloidin and phalloin contain one residue of D-threonine per molecule.



L-threonine

threonine aldolase *see* **glycine hydroxymethyltransferase**.

threonine dehydratase EC 4.2.1.16; *systematic name*: L-threonine hydro-lyase (deaminating); *other names*: threonine deaminase; L-serine dehydratase; serine deaminase. A pyridoxal-phosphate enzyme that catalyses a reaction between L-threonine and water to form 2-oxobutanoate, NH_3, and water; it acts also on L-serine. In *Escherichia coli* type 1 is responsible for the first step of isoleucine biosynthesis (serine is an alternative but poorer substrate); type 2 is a catabolic enzyme that acts on both serine and threonine, and is properly considered as a hydroxy-amino-acid deaminase.

threonine synthase EC 4.2.99.2; *systematic name*: *O*-phospho-L-homoserine phospho-lyase (adding water). A pyridoxal-phosphate enzyme that catalyses the formation of L-threonine from *O*-phospho-L-homoserine and water with release of orthophosphate. It shows sequence homology with the serine dehydratase/threonine dehydratase group.

threoninium threonine cation; the cation, CH_3–CH(OH)–CH(NH_3^+)–COOH, derived from **threonine**.

threonino the alkylamino group, CH_3–CH(OH)–CH(COOH)–NH–, derived from **threonine**.

threonin-*O*^{3}-yl the alkyloxy group, HOOC–CH(NH_2)–CH(CH_3)–O–, derived from **threonine**.

threonyl the acyl group, CH_3–CH(OH)–CH(NH_2)–CO–, derived from **threonine**.

threose *the trivial name for* the aldotetrose *threo*-tetrose; it has D and L enantiomers, which are respectively diastereoisomeric with those of erythrose. *See also* **threo-**.



α-D-threose

threshold the value that must be achieved or exceeded for an effect to become discernible. For example, the **kidney threshold of excretion**, for any substance, is the plasma concentration at which not all of the substance that appears in the filtrate can be reabsorbed, so that it appears in the urine.

THRF *abbr. for* thyrotropic hormone releasing factor; i.e. **thyrotropin-releasing hormone**.

THRH *abbr. for* thyrotropic hormone releasing hormone; i.e. **thyrotropin-releasing hormone**.

thrombin EC 3.4.21.5; *other name*: fibrinogenase; a serine proteinase, M_r 33 700–33 900, the natural coagulant of **fibrinogen**. Thrombin appears in the blood following activation of the coagulation system, as a result of proteolysis of **prothrombin**. It catalyses the preferential cleavage of Arg-|-Gly, activating fibrinogen to **fibrin** and releasing fibrinopeptides A and B. Its effects are mediated by the **thrombin receptor**. *See also* **blood coagulation**.

thrombin receptor a protein of platelets and vascular endothelial cells that binds **thrombin** and mediates its intracellular effects. It is a G-protein-coupled receptor. The precursor of human thrombin receptor is a glycoprotein of 425 amino acids. The signal peptide comprises amino acids 1–26, and amino acids 27–41 are removed by thrombin, after which the new N terminus functions as a tethered ligand and the receptor is thereby activated.

thrombocyte *an alternative name for* **platelet**.

thrombogenic 1 tending to promote the formation of a blood clot (i.e. a **thrombus**). **2** having a precursor function for, or tending to promote, the formation of **thrombin**.

β-thromboglobulin a protein (79 amino acids) derived from **platelet basic protein precursor** by removal of the first four N-terminal residues from **LA-PF4**. Released as a homotetramer into plasma by activated platelets, it mediates several actions in the inflammatory response, including chemotaxis of leukocytes. It is the precursor of NAP2 (68 amino acids).

thrombokinase *an alternative name for* factor Xa; *see* **blood coagulation**.

thrombolysis the degradation of a blood clot (i.e. **thrombus**) as a result of physiological or pharmacological action.

thrombolytic 1 tending to promote **thrombolysis**. **2** a drug or other substance promoting thrombolysis.

thrombomodulin *abbr.*: TM; *other name*: fetomodulin; a specific endothelial cell receptor that binds thrombin, the complex converting protein C to activated protein C. It is a type I membrane protein.

thrombophilia any tendency to intravascular thrombosis. The commonest form is resistance to activated **protein C** due to a mutation in blood coagulation factor V.

thromboplastin *an alternative name for* factor III; *see* **blood coagulation**.

thrombospondin *or* **glycoprotein G** a thrombin-sensitive major glycoprotein located in the alpha granules of human platelets. It is secreted on thrombin activation, and binds to the platelet membrane in the presence of Ca^{2+}. It is an adhesion molecule that mediates cell–cell and cell–matrix interactions, and can bind to fibrinogen, fibronectin, laminin, and type V collagen. It is a trimeric, disulfide-linked protein and contains three types of repeating amino-acid sequence: the first is 57 amino acids long and shares similarity with circumsporozoite protein from a malarial parasite; the second is 50–60 amino acids long and shares similarity with **epidermal growth factor**; the third occurs as a continuous eight-fold repeat of a 38-residue sequence; structural similarity with **calmodulin** indicates that these repeats constitute multiple calcium-binding sites.

thromboxane any of a class of **prostanoids** synthesized by **thromboxane-A synthase** (EC 5.3.99.5) from prostaglandin H (the product of prostaglandin-endoperoxide synthase) as thromboxane A (TXA). Depending on whether the substrate of the enzyme is dihomo-(6,9,12)-linolenate, arachidonate, or eicosa-5,8,11,14,17-pentaenoate, the product is TXA$_1$, TXA$_2$, or TXA$_3$ respectively. TXA$_2$ is the major thromboxane *in vivo*. It is synthesized in platelets when these are activated by other aggregatory compounds and strongly reinforces the aggregatory reaction. TXA$_2$ is converted in minutes to the inactive thromboxane B$_2$ (TXB$_2$) by addition of water across the endoperoxide. Oxidation of the 11-hydroxy group of TXB$_2$ to an oxo group yields 11-dehydro-thromboxane A$_2$, a major long-lived metabolite in human plasma, useful for measurement as an index of thromboxane production. Beta-oxidation of TXB$_2$ yields 2,3-dinor-thromboxane B$_2$, the major human urinary metabolite. **Dideoxy-epoxymethanoprostaglandin F$_{2\alpha}$** is a stable analogue that mimics TXA$_2$.



TXA$_2$

thromboxane-A synthase EC 5.3.99.5; *other names*: thromboxane synthase; thromboxane synthetase (*abbr.*: TXS); an enzyme that catalyses the formation from (5*Z*,13*E*)-(15*S*)-9α,11α-epidioxy-15-hydroxyprosta-5,13-dienoate of (5*Z*,13*E*)-(15*S*)-9α,11α-epoxy-15-hydroxythromba-5,13-dienoate (**thromboxane** A$_2$). It is a heme-thiolate protein. 1-(7-carboxyheptyl)imidazole and benzylimidazole inhibit thromboxane-A synthase, as does the drug U-63557A, sodium furegrelate.

thrombus (*pl.* **thrombi**) a blood clot forming within a blood vessel. Thrombus formation may occur as a normal response during physiological blood coagulation. It may also occur pathologically, triggered by **atheroma**, and is the immediate cause of ischemia in a heart attack. Thrombi may also form, especially in veins, at other times, e.g. after surgery, and if they reach the lungs cause pulmonary embolism.

Thunberg method an early method for detecting and estimating **dehydrogenases** from the rate and extent of decolorization of Methylene Blue in solution in the presence of enzyme and substrate. The apparatus, known as a **Thunberg tube**, is a stoppered glass tube (sometimes with a side-arm for addition of reagents) that may be evacuated through the stopper, and then sealed by a twist of the stopper. [After Torsten Ludvig Thunberg (1873–1952), Swedish physiological chemist.]

Thx *symbol for* a residue of the *α*-amino acid and thyroid hormone L-thyroxine (alternative to T_4).

Thy *symbol for* a residue of the pyrimidine base thymine (alternative to T).

Thy-1 an allelic variable molecule, encoded on mouse chromosome 9, that is present on all T lymphocytes and also occurs in brain. It is a GPI-anchored membrane glycoprotein of the immunoglobulin superfamily, with a simple structure homologous to the **variable region** of an immunoglobulin molecule. *See also* **thymopoietin**.

thylakoid a saclike vesicle that bears the photosynthetic pigments in photosynthetic organisms. In prokaryotes the thylakoids are of various shapes and are attached to the plasma membrane. In eukaryotes they are flattened, membrane-bound disclike structures located in the **chloroplasts**; in higher plants they form dense stacks called **grana**. Isolated thylakoid preparations can carry out photosynthetic electron transport and the associated phosphorylation.

thymic hormones *see* **thymopoietin**, **thymosin**.

thymidine *or* **deoxyribosylthymine** *symbol*: dT *or* dThd; thymine 2′-deoxyriboside; 1-(2-deoxy-*β*-D-ribofuranosyl)-5-methyluracil; a deoxynucleoside very widely distributed almost entirely as phosphoric esters in deoxynucleotides and deoxyribonucleic acid, DNA. *Compare* **ribothymidine**. Because thymidine is absent from ribonucleic acid, the incorporation of radioisotope-labelled thymidine into cells is the basis of a procedure for measuring the rates of DNA synthesis and cell growth.



thymidine 5′-diphosphate *symbol*: dThd5′*PP or* ppdT; *the recommended name for* thymidine diphosphate (*abbr.*: dTDP), 5′-diphosphothymidine, 5′-thymidylyl phosphate, thymidine 5′-(trihydrogen diphosphate). It is an intermediate in the formation of thymidine 5′-triphosphate from thymidine 5′-phosphate. Derived compounds are the rare **nucleosidediphosphosugars** thymidinediphosphorhamnose and its biosynthetic precursor thymidinediphosphoglucose.

thymidine kinase EC 2.7.1.21; *systematic name*: ATP:thymidine 5′-phosphotransferase; an enzyme that catalyses the phosphorylation of thymidine to thymidine 5′-phosphate. It acts on thymidine as a first step in its further metabolism. Mitochondrial and cytosolic forms are known, the latter being more active in proliferating than in resting cells.

thymidine monophosphate *abbr.*: dTMP; *an alternative name for* any **thymidine phosphate**, but in particular for thymidine 5′-phosphate, especially when its distinction from thymidine (5′-)diphosphate and thymidine (5′-)triphosphate requires emphasis.

thymidine phosphate *symbol*: dThd*P*; thymidine monophosphate (*abbr.*: dTMP); any phosphoric monoester or diester of thymidine. There are two monoesters – thymidine 3′-phosphate and **thymidine 5′-phosphate** – and one diester – thymidine 3′,5′-phosphate – although thymidine 5′-phosphate is the ester commonly denoted (the locant being omitted if no ambiguity may arise). Thymidine 3′-phosphate (*symbol*: dThd3′*P*) (*or* thymidine 3′-monophosphate (*abbr.*: 3′dTMP) *or* 3′-thymidylic acid) is released from deoxyribonucleic acid by certain endo- or exonucleases, e.g. deoxyribonuclease II (EC 3.1.22.1) or spleen exonuclease (EC 3.1.16.1). The monophosphoric diester thymidine 3′,5′-phosphate (*symbol*: dThd-3′,5′-*P*) (*or* thymidine 3′,5′-(cyclic)phosphate *or* cyclic thymidine 3′,5′-monophosphate (*abbr.*: 3′,5′-cyclic dTMP *or* cyclic dTMP *or* cdTMP)) is an intermediate during the acid hydrolysis of deoxyribonucleic acid.

thymidine 3′-phosphate *see* **thymidine phosphate**.

thymidine 3′,5′-phosphate *see* **thymidine phosphate**.

thymidine 5′-phosphate *or* **5′-thymidylic acid** *or* **5′-phosphothymidine** *or* **5′-*O*-phosphonothymidine** *symbol*: dThd5′P; *recommended names for* thymidine monophosphate (*abbr.*: dTMP), thymidine 5′-(dihydrogen phosphate), thymine (mono)deoxynucleotide. (The locant is commonly omitted if there is no ambiguity as to the position of phosphorylation.) It is synthesized (very indirectly) from **uridine 5′-phosphate**, its immediate precursor being 2′-deoxyuridine 5′-phosphate – *see* **thymidylate synthase**. Resynthesis of dTMP from free thymidine formed by degradation of DNA can also be effected via a **salvage pathway**.

thymidine phosphorylase *see* **pyrimidine-nucleoside phosphorylase**.

thymidine 5′-triphosphate *symbol*: dThd5′*PPP or* pppdT; *the recommended name for* thymidine triphosphate (*abbr.*: dTTP), 5′-triphosphothymidine, 5′-thymidylyl diphosphate, thymidine 5′-(tetrahydrogen triphosphate); a substrate for DNA synthesis. It is formed from thymidine 5′-phosphate by nucleoside-phosphate kinase (EC 2.7.4.4) and nucleoside-diphosphate kinase (EC 2.7.4.6), which transfer in turn the terminal phosphoric residues from two molecules of ATP.



thymidyl either of the chemical groups formed by the loss of a 3′- or a 5′-hydroxyl group from the deoxyribose moiety of thymidine.

thymidylate 1 either the monoanion or the dianion of thymidylic acid. **2** any mixture of thymidylic acid and its anions. **3** any salt or ester of thymidylic acid.

thymidylate synthase EC 2.1.1.45; *systematic name*: 5,10-methylenetetrahydrofolate:dUMP *C*-methyltransferase; an enzyme responsible for the formation of thymidylate, dTMP, by the *de novo* pathway. It catalyses reductive methylation of 2′-deoxy-5′-uridylate, dUMP, by reaction with 5,10-methylenetetrahydrofolate to form dihydrofolate and dTMP. Thymidylate synthase is a target for the antineoplastic agents **fluorouracil** and fluorodeoxyuridine. These drugs are metabolized to fluorodeoxyuridylate, which is a potent irreversible inhibitor of the enzyme. *See also* **thymineless death**.

thymidylic acid any phosphoric monoester of thymidine. The position of the phosphoric residue on the deoxyribose moiety of a given ester may be specified by a prefixed locant – *see* **thymidine phosphate**. However, 5′-thymidylic acid is the ester commonly denoted, its locant usually being omitted if no ambiguity may arise. 5′-Thymidylic acid is a recommended name for **thymidine 5′-phosphate**.

thymidylyl the thymidine[mono]phospho group; the acyl group derived from **thymidylic acid**.

thymin *a former name for* **thymopoietin**.

thymine *symbol*: T *or* Thy; 5-methyluracil; 2,4-dihydroxy-5-methylpyrimidine; one of the two major pyrimidine bases present (as thymidine) in DNA but not in RNA other than (as ribothymidine) in transfer RNA, where it is a minor base.



thymine dimer a **pyrimidine dimer** formed within a DNA strand from two adjacent thymine residues by **photodimerization**. It is most commonly of the cyclobutadipyrimidine type.

thymineless death the death of an animal or bacterial cell following thymine (or thymidylate) deprivation. Such a deprived cell may continue to produce protein and RNA, but can no longer synthesize DNA in the absence of thymidylate. It eventually loses its vitality and dies, perhaps because it is also unable to repair altered or damaged DNA. The phenomenon may be demonstrated with a thymine-requiring auxotrophic bacterial mutant by omitting thymine from the medium, or with any cell by adding **fluorouracil** or its metabolite fluorodeoxyuridine, which inhibit **thymidylate synthase**. A rapidly metabolizing animal cell, such as a tumour cell, is particularly susceptible to thymineless death.

thymine deoxyriboside *an alternative name for* **thymidine**.

thymine riboside *an alternative name for* **ribothymidine**.

thyminose *a former name for* 2-deoxy-D-ribose (*see* **deoxyribose**).

thymo+ *comb. form* of, or pertaining to, the thymus.

thymocyte any **lymphocyte** found in the thymus.

thymocyte mitogenic factor *abbr.*: TMF; *an alternative name for* **interleukin 2**.

thymocyte-stimulating factor *abbr.*: TSF; *an alternative name for* **interleukin 2**.

thymoma a tumour of thymic tissue.

thymonuclease *another name for* **deoxyribonuclease I**.

thymonucleic acid *an alternative term for* **thymus nucleic acid**.

thymopentin a synthetic pentapeptide that corresponds to residues 32–36 of **thymopoietin**.

thymopoietin *abbr.*: TP; *former name*: thymin; any one of three polypeptide hormones that result by alternative splicing of the same gene, and originally isolated from bovine thymus. They have pleiotropic actions on prothymocytes, inducing expression of the differentiation antigens such as **Thy-1**, and are important in T-cell development and function. They impair neuromuscular transmission after injection in mice, due to an effect on the nicotinic acetylcholine receptor. A synthetic pentapeptide corresponding to residues 32–36, named **thymopentin** and with the sequence Arg-Lys-Asp^{34}-Val-Tyr, has full activity. **Splenin**, a corresponding peptide in spleen, contains a similar pentapeptide, called **splenopentin**; bovine splenin has Glu in place of Asp^{34}, and human splenin has Ala in the corresponding position. These replacements affect the biological activity.

thymosin any of the polypeptide hormones of thymic origin that are involved in differentiation of T lymphocytes in the thymus. They include α_1 and β_4 thymosins, which are of known structure. Prothymosin-α is an oncoprotein that inhibits apoptosis by inhibiting formation of the complex (of seven molecules of Apaf-1 with seven of cytochrome *c*) that activates caspase 9. Thymosin β_4 (human, bovine, rat) has the sequence SDKPDMAEIEKFDKSKLKKTETQEKNPLPSKETIEQEKQAGES.

thymulin a zinc-requiring immunomodulatory thymic nonapeptide that induces T-cell differentiation. Its level is decreased in immunodeficiency and in autoimmune disease.

thymus a bilobed glandular organ located in the mediastinum in the anterior thorax. In mammals the thymus is encapsulated and divided into lobules, each consisting of cortex and medulla; the cortex consists mainly of lymphocytes (thymocytes). It is responsible for populating the blood, lymph, and thymus-dependent areas with **T lymphocytes** during the neonatal period. Although large at birth it shrinks thereafter and may be difficult to identify in adults. It is important in **cell-mediated immunity**. —**thymic** *adj.*

thymus nucleic acid *a former name for* **deoxyribonucleic acid,** so called because the thymus was the first particularly rich source of a nucleic acid thought to be characteristic of animal tissues and distinct from that believed to be characteristic of plant tissues (called **yeast nucleic acid**).

thyro+ *comb. form* of, or pertaining to, the **thyroid gland**.

thyrocalcitonin *see* **calcitonin**.

thyroglobulin a protein in the **thyroid gland**, tyrosyl residues of which are modified to form the principal thyroid hormone, **thyroxine**, which is released by proteolysis. Thyroglobulin, a dimer of molecular mass ~660 kDa, is the main constituent of the so-called colloid of the thyroid follicles. Iodination of certain tyrosyl residues results in the formation of 3,5-iodotyrosyl residues; the iodinated phenolic moiety of one of these tyrosyls (in the free form, this would be a 2,6-iodophenyl group) is then transferred to the phenolic oxygen of another iodinated tyrosyl to form a tetraiodo compound; this is released by proteolysis as thyroxine (T_4) (some triiodo forms are also produced). The proteolysis occurs as colloid migrates from the basal to the apical surfaces of the thyroid cell. The colloid containing the modified thyroglobulin is taken into vesicles by phagocytosis to form periodic acid–Schiff positive (PAS) vesicles. Dense granules containing proteolytic enzymes then fuse with the vesicles to digest the thyroglobulin with the loss of PAS-positive material. The vesicles containing triodothyronine and thyroxine are then extruded.

thyroidectomy the surgical removal of the thyroid gland.

thyroid gland a ductless gland of vertebrates, located near the larynx in most species, that secretes the hormones **thyroxine** and **triiodothyronine**. It contains closely packed follicles, or acini, each consisting of a sac that has a layer of cuboidal cells resting on an outer basement membrane. Each follicle is full of thyroglobulin-containing colloid. This is synthesized and secreted into the colloid space by the follicular cells; microvilli extend from the apical surface of the follicular cells into the colloid. In between the follicles are nests of parafollicular cells, or C cells, that synthesize **calcitonin**. Enlargement of the thyroid is called **goitre**. The thyroid concentrates iodide, a property that can be used for thyroid imaging, and for the treatment of cancer of the thyroid.

thyroid hormone either of the compounds secreted by the **thyroid gland**, namely **thyroxine** and **triiodothyronine**.

thyroid hormone receptor a receptor for **triiodothyronine** that belongs to the superfamily of eukaryotic transcription factors and the steroid/thyroid/retinoic acid family of nuclear receptors for hormones. There is a ligand-binding domain in the C-terminal region, a zinc-finger DNA-binding domain in the central region, and a function-modulating domain in the N-terminal region. Binding of hormone induces changes in conformation that control transcriptional activation and repression, and also regulates homo- or heterodimerization. In the absence of ligand, these receptors repress basal gene expression, probably through co-repressor proteins. Numerous mutations in the gene for the receptor result in resistance to thyroid hormone.

thyroid-hormone receptor-associated protein *see* **TRAP**.

thyroid response element *abbr.*: TRE; *see* **response element**.

thyroid-stimulating hormone *abbr.*: TSH; *recommended name*: thyrotropin; *other name*: thyrotropic hormone; a hormone, secreted by the adenohypophysis, that stimulates the activity of the thyroid gland. The bovine hormone is a glycoprotein (M_r 28 300) of α and β chains. The α chain has an amino-acid sequence identical with the α chain of **luteinizing hormone** and follicle-stimulating hormone. TSH increases uptake of iodide by the thyroid, the rate of conversion of diiodotyrosine to thyroxine, and the release of thyroid hormones. The release of TSH is influenced by **thyrotropin-releasing hormone**.

thyroliberin *recommended name for* **thyrotropin-releasing hormone**.

thyronine 4-(4-hydroxyphenoxy)phenylalanine; the notional parent structure of thyroid hormones (*see* **thyroglobulin**).



thyronine

thyroperoxidase a glycosylated integral membrane protein and enzyme of the apical surface of thyroid follicle cells, involved in the formation of thyroxine from thyroglobulin. It contains 933 amino acids and a transmembrane segment near the C-terminus. The N-terminal region contains the catalytic site and a heme moiety, and shares 42% sequence homology with myeloperoxidase. It catalyses the peroxidative iodination of specific tyrosine residues of thyroglobulin to monoiodotyrosine and diiodotyrosine, a process called **organification**. It also catalyses coupling of two of these diiodotyrosine residues to form thyroxine, a process called **coupling**. Both processes require the presence of hydrogen peroxide. Several mutations lead to congenital goitre and hypothyroidism due to the failure in organification.

thyrotoxicosis *see* **hyperthyroidism**.

thyrotroph a thyrotropic cell.

thyrotrophic having the effect of nourishing the thyroid gland, stimulating its growth and maintaining its size.

thyrotropic *or (esp. Brit.)* **thyrotrophic** having a modulating effect on the thyroid gland, especially in stimulating the synthesis of thyroid hormones. *See* **thyrotropin**.

thyrotropic hormone *an alternative name for* **thyroid-stimulating hormone**.

thyrotropic hormone releasing factor (*abbr.*: THRF) *or* **thyrotropic hormone releasing hormone** (*abbr.*: THRH) *an alternative name for* **thyrotropin-releasing hormone**.

thyrotropin *the recommended name for* **thyroid-stimulating hormone**.

thyrotropin receptor a G-protein-associated membrane protein that binds thyrotropin (i.e. **thyroid-stimulating hormone**) and mediates its intracellular effects. Different forms are produced by alternative splicing. Mutations are associated with hyperfunctioning thyroid adenomas. The hyperthyroidism of **Graves' disease** results from autoantibodies that stimulate the thyroid through the thyrotropin receptor.

thyrotropin-releasing factor *abbr.*: TRF; *an alternative name for* **thyrotropin-releasing hormone**.

thyrotropin-releasing hormone *abbr.*: TRH; *recommended name*: thyroliberin; *other name*: thyrotropin-releasing factor (*abbr.*: TRF); a hormone, released by the mammalian hypothalamus, that regulates the secretion of **thyroid-stimulating hormone** (TSH) by the adenohypophysis. It is present not only in primitive vertebrates but also in *Amphioxus* (a provertebrate) and in nerve ganglia of snails. It is the tripeptide pyroGlu–His–Pro–NH_2, the cyclized glutamate and prolylamide being essential for activity. The pyroGlu is derived from a glutamine residue in the precursor, with release of ammonia, and the C-terminal amine from a glycine residue in the precursor (*see* **C-terminal peptide amidation**). It is released from a polyprotein precursor that contains six copies of the tetrapeptide sequence required to generate the hormone. TRH occurs in other parts of the brain, in pancreatic islets, and in the gastrointestinal tract; it probably serves as a neurotransmitter or neuromodulator, being known in mammals to alter sleep patterns, increase motor activity and blood pressure, and affect norepinephrine turnover. *Other names*: thyrotropic hormone releasing factor (*abbr.*: THRF); thyrotropic hormone releasing hormone (*abbr.*: THRH).

thyroxine *abbr.*: Thx *or* T_4; 4-(4-hydroxy-3,5-diiodophenoxy)-3,5-diiodophenylalanine; 3,3′,5,5′-tetraiodothyronine; the main hormone secreted by the thyroid gland, although its activity is lower than that of **triiodothyronine** (T_3). It is synthesized from L-tyrosyl residues of **thyroglobulin.** Thyroxine is essential for normal metabolism and physical development. It stimulates the metabolic rate, causing increased oxygen consumption and heat production in tissues. Although in humans the plasma levels of T_4 are 20-to 50-fold higher than those of T_3, T_4 is converted to T_3 in tissues and the effects are mediated by T_3 binding to receptors in the cell nucleus, leading to mRNA and protein synthesis. The normal range in human blood is 60–150 nmol L^{-1} (total of bound and free), 9–26 pmol L^{-1} (free). The chemical constitution of thyroxine was deduced by the British biochemist Sir Charles R. Harington (1897–1972), and confirmed by synthesis (1927).



thyroxine-binding globulin *abbr.*: TBG; a major thyroid hormone transport protein found in mammalian serum. It is synthesized in liver, and variations in its concentration in serum result in similar variations in the level of circulating thyroid hormones. Alterations in its affinity for thyroid hormone also affect circulating thyroid hormone levels, decreased affinity being accompanied by decreased serum concentration. In the human, this variation may result from non-thyroidal illness, the presence of drugs (salicylates and phenytoin block thyroid- binding sites), or genetic variation, many variants being known.

Ti *symbol for* titanium.

TIC complex *abbr. for* peptide-translocating channel on inner chloroplast membrane; a protein complex of the inner chloroplast membrane that forms a peptide-translocating channel. The major component is TIC 110. *Compare* **TOC complex**.

tight coupling a term applied to mitochondrial function implying a high degree of efficiency in the yield of ATP (or other functional response) in relation to electron flow. The nearer the yield approaches the optimal value, the tighter the coupling is said to be. Tight coupling is obtained in isolated mitochondria only if gentle procedures, preserving membrane integrity, are employed during isolation. *See also* **chemiosmotic coupling hypothesis**, **phosphorus:oxygen ratio**.

tight junction *or* **zona occludens** (in vertebrate tissues) a beltlike region of very close contact between the plasma membranes of adjacent cells, such that the intercellular space is completely occluded. Tight junctions occur in epithelia and brain endothelia, and are effective barriers to the passage of water and solutes. *Compare* **gap junction**.

tight turn *see* **beta turn**.

TIGR *abbr. for* The Institute for Genome Research; *see* **sequencing centre**.

TIM *abbr. for* **1** triose-phosphate isomerase. **2** translocase of inner mitochondrial membrane; a protein complex that forms a channel in the inner mitochondrial membrane for proteins targeted for import into the organelle. It comprises four transmembrane proteins (Tim33, Tim23, Tim17, and Tim14) and a peripheral protein (Tim44). Tim23 and Tim17 contain 3–4 transmembrane segments each. The portion of Tim23 in the intermembrane space contains heptad repeats for coiled-coil formation and is sensitive to the electrochemical gradient across the inner membrane. TIM and **TOM** are believed to be apposed across the intermembrane space. *See also* **DPP**.

TIM barrel a protein structure in which 8 α/β segments form a barrel, as first described for **triose-phosphate isomerase**.

time *symbol*: *t*; one of the seven SI base physical quantities, usually indicating duration or a precise moment. The SI base unit of time is the **second**.

time constant a characteristic time taken by a system or a process to respond to a perturbation.

time course a graph plot of a parameter (that changes with time) scaled on the ordinate and time scaled on the abscissa.

time-of-flight mass spectrometer a type of **mass spectrometer** in which molecular ions from an ion source are ejected by a laser flash or electrical pulse, and are separated by their speed of travel, which is inversely proportional to their **mass-to-charge ratio**.

time-resolved fluorescence a method in which a sample is irradiated using a laser delivering a short pulse of light, after which the exponential decay of fluorescence is measured using a photomultiplier. Lanthanides such as europium emit fluorescence over a period of microseconds and measurements can be made after the relatively short-lived autofluorescence of proteins has decayed. It is used as the basis of DELFIA. *See also* **steady-state fluorescence anisotropy**.

time-resolved fluorescence spectrometry a method in which a sample is irradiated using a laser delivering a short (sub-nanosecond) pulse of light, after which the exponential decay of fluorescence is measured using a photomultiplier. The sensitivity of detection must be at the single photon level ('single photon counting'), and fluorescence lifetimes as short as a few nanoseconds can be determined. However, a disadvantage of the technique is that many measurements over possibly several hours may be needed to obtain reliable and sufficient data. *See also* **steady-state fluorescence anisotropy**.

TIMP *abbr. for* tissue inhibitor of metalloproteases; any protein that inhibits metalloproteinases. TIMP-1, *or* EPA (erythroid potentiating activity), mediates erythropoiesis. It forms complexes with enzymes such as collagenases, bringing about irreversible inactivation. *See also* **matrix metalloproteinase**.

tintometer an apparatus formerly used for determining the colour of a solution by comparison with a graded colour scale.

tiny RNA *see* **miRNA**.

Ti plasmid *abbr. for* tumour-inducing plasmid; any large conjugative plasmid found in the soil bacterium *Agrobacterium tumefaciens* and responsible for **crown-gall disease** of broad-leaved plants – a segment of the Ti plasmid, the **T-DNA**, is found in the genome of the tumour tissue of affected plants. With appropriate modifications the Ti plasmid can carry foreign DNA sequences into the genome of a susceptible plant.

Tiselius apparatus an apparatus for performing **moving boundary electrophoresis** in which there is a U-tube with sliding joints. This enables the protein (or other) solution and the buffer to be placed in separate parts of the U-tube and sharp boundaries made between them when the parts are slid into position to complete the U-tube. [After Arne Wilhelm Kaurin Tiselius (1902–71), Swedish protein chemist.]

tissue any collection of cells that is organized to perform one or more specific function. *Compare* **organ**.

tissue culture 1 the technique or process of growing or maintaining tissue cells (**cell culture**), whole organs (**organ culture**), or parts of an organ, from an animal or plant, in artificial conditions. **2** any living material grown or maintained by such a technique.

tissue extract *an alternative name for* factor III; *see* **blood coagulation**.

tissue factor *abbr.*: TF; *or* factor III; a transmembrane glycoprotein, mainly of subendothelial cells, that initiates **blood coagulation** by forming a complex with factor VII or VIIA. The complex activates factors IX or X. In normal hemostasis tissue factor initiates cell-surface assembly and propagation of the coagulation protease cascade.

tissue grinder any device for disrupting tissue by a crushing or shearing action. The term may embrace devices ranging from a meat grinder (mincer), mechanical pestle and mortar, or mill, to the more precise **Potter–Elvehjem homogenizer** or the **Dounce homogenizer**.

tissue kallikrein *see* **kallikrein**.

titer *the US spelling of* **titre**.

titin *or* **connectin** a giant 521 kDa protein that forms a single molecule elastic filament, extending from the M line to the Z line in the striated muscle sarcomere, and is one of the largest polypeptides yet described. The sequence consists mainly of repeats of two types of ~100-amino-acid motifs (termed class I and class II) that share similarity with the fibronectin type-III domain and **immunoglobulin superfamily** C2 domain, respectively. There is also a domain characteristic of protein kinases near the C terminus. It is thought to play an important role in sarcomere alignment during muscle contraction. *See also* **twitchin**.

titratable acidity 1 a measure of the acidity of a urine sample, expressed as the volume of 0.1-M NaOH required to neutralize, usually to a phenolphthalein endpoint, a 24-hour volume of urine. **2** a measure of the acidity of any solution, etc.

titrate 1 to add acid of known concentration to base of unknown concentration (or vice versa) until the point of equivalence is reached, from which can be determined the concentration of the unknown. **2** more generally, to add any standard solution to an unknown until some detectable equivalence point is reached, enabling the amount of the unknown to be determined. **3** (*esp. in microbiology or immunology*) to determine the maximum dilution at which activity can be detected. *See* **titre** (def. 2). **—titratable** *adj.*; **titration** *n.*

titration curve originally, a curve relating pH to the equivalents of strong base added per equivalent of acid in the solution. Similar curves are obtained when the logarithm of ligand concentration is plotted against the degree of association (or dissociation) of a ligand to its acceptor, or when redox potential is plotted against the degree of oxidation (or reduction) of a redox system.

titration p*K* *symbol*: p*G*; a kind of **p*K*** that characterizes the titration curve of a multibasic acid. If this acid has *n* hydrons that titrate over the pH range of interest, then its titration curve is identical to that of an equimolar mixture of *n* (hypothetical) monobasic acids. The p*K* values of these acids are the titration p*K* values of the multibasic acid. They differ little from the **molecular p*K*** values if the differences between sequential molecular values exceed unity. *See also* **group p*K***.

titre *or (esp. US)* **titer 1** a value found by titration; *see* **titrate** (def. 1, 2). **2** *(in microbiology and immunology)* a measure of the concentration or activity of an active substance, e.g. an antibody, in a solution, usually expressed as the highest dilution of the solution in which the activity can be detected. By convention, if the highest dilution giving activity is 100-fold, the titre is said to be 100.

titrimetry the technique of measurement by titration, particularly using instrumentation and automation.

Tl *symbol for* thallium.

TLC *abbr. for* thin-layer chromatography.

tld a gene in *Drosophila* for **Tolloid** protein, which is required for normal dorsal development. Mutations in *tld* lead to a partial transformation of dorsal ectoderm into ventral ectoderm.

TLR *abbr. for* Toll-like receptor.

T lymphocyte *or* **T cell** any lymphocyte that undergoes maturation and differentiation in thymus. T lymphocytes are responsible for immune reactions involving cell–cell interaction, i.e. **cell-mediated immunity**. Subsets include: (1) cytotoxic T-lymphocytes, directly reponsible *in vivo* for the death of cells identified for elimination; they include nonspecific killer cells (**NK cells**) and specific cytotoxic T-lymphocytes primed by antigen activation; (2) **helper cells**, which collaborate with **antigen-presenting cells** in the initiation of an immune response; and (3) **suppressor cells**, which down-regulate the response of helper cells.

Tm *symbol for* thulium. *Compare* **T_m**.

TMA *abbr. for* transcription-mediated amplification.

TMB-8 *abbr. for* (8-diethylamino)octyl-3,4,5-trimethoxybenzoate; an agonist that blocks intracellular Ca^{2+} channels.



TM domain *abbr. for* transmembrane domain.

TMF *abbr. for* thymocyte mitogenic factor; i.e. **interleukin 2**.

TMM *abbr. for* too many mouths; a protein (496 amino acids) of *Arabidopsis* that is expressed in proliferative postprotodermal cells and is thought to be a receptor. It contains a transmembrane segment at the C-terminus and ten uninterrupted leucine-rich repeats in the central region. Mutations in the gene produce abnormal clusters of stomata on the leaf surface.

TMP *abbr. for* **1** ribosylthymine monophosphate *or* ribothymidine monophosphate, *the common names for* ribosylthymine 5′-phosphate, ribothymidine 5′-phosphate, 5′-ribothymidylyl phosphate, thymine riboside 5′-phosphate. **2** *(sometimes)* thymidine monophosphate. dTMP is recommended.

7TM protein *an alternative name for* **seven-transmembrane-domain protein**.

TM7 receptor *or* **TM7 protein** any plasma membrane receptor or other protein that contains seven transmembrane segments, each of 20–25 amino acids. Included are the family of G-protein associated membrane receptors and the **TRP channels**.

tmRNA *abbr. for* transfer-messenger RNA; *other names*: 10SaRNA; SsrA; a bacterial RNA (260–430 nt long, depending on species) that contains a tRNA domain that can be charged with an alanine residue at the 3′ CCA end, and a short open reading frame (ORF) of nine codons. It binds at the A site of a ribosome that has stalled during translation because of some defect in the mRNA, adds its Ala to the nascent chain, then moves to the P site of the ribosome, the chain being transferred to the tmRNA (a process called **trans-translation**). Translation ends at the stop codon of the ORF, the defective protein being targeted for degradation.

TMR spectroscopy *abbr. for* topical magnetic resonance spectroscopy.

TMS *abbr. for* **1** tetramethylsilane; a water-soluble reference substance used in nuclear magnetic resonance spectroscopy. **2** the trimethylsilyl group; the symbol Me_3Si– is preferred.

TMV *abbr. for* tobacco mosaic virus, an RNA plant virus.

Tn *abbr. for* **1** troponin. **2** transposon.

TNBS *abbr. for* 2,4,6-trinitrobenzenesulfonate; a reagent that combines readily with amino groups. It may be used either to protect these groups or to introduce a chromophore. It is removable using hydrazine.

Tn-C *abbr. for* troponin C.

TNF *abbr. for* tumour necrosis factor.

TNF-α converting enzyme *abbr.* TACE. *other names* TNF-α convertase, ADAM-17; a member of the ADAM family of metalloprokinases that cleaves the TNF-α precursor present in plasma membranes of activated macrophages and T cells to release soluble TNF-α, which is a cachectin.

TNF receptor-1-associated death-domain protein *see* **TRADD**.

TNF receptor-associated protein 2 *abbr.*: TRAF 2; an adaptor protein that is recruited by **TRADD** as part of the signalling complex that forms on the intracellular domain of tumour necrosis factor (TNF) receptor 1 following its binding by TNF. It recruits two inhibitor of apoptosis proteins (IAP1 and IAP2) that have ubiquitin–protein ligase activity. It may activate a protein kinase that activates the transcriptional activator JUN.

Tn-I *abbr. for* troponin I.

TNMR *or* **tnmr** *abbr. for* tritium nuclear magnetic resonance (spectroscopy).

TNS *abbr. for* 2-*p*-toluidylnaphthalene-6-sulfonate; a **fluor** used in **extrinsic fluorescence** studies of proteins.

Tn-T *abbr. for* troponin T.

tobacco acid pyrophosphatase an enzyme used for removing the 5′ cap from mature mRNA by hydrolysis of the diphosphate bond.

TOC complex *abbr. for* peptide-translocating channel on outer chloroplast membrane; a protein complex of the outer chloroplast membrane that forms a peptide-translocating channel. The core component is TOC 75. *Compare* **TIC complex**.

tocopherol *a generic term for* di- and trimethyltocols; α-tocopherol is 5,7,8-trimethyltocol, and is active as **vitamin E**; β-tocopherol is 5,8-dimethyltocol; γ-tocopherol is 7,8-dimethyltocol; and δ-tocopherol is 8-methyltocol.



α-tocopherol

T-odd phage any one of the **bacteriophages** T1, T3, T5, or T7 of *Escherichia coli* that share morphological, biochemical, and other features that distinguish them from **T-even phages**.

togavirus *or (formerly)* **arbovirus** any RNA animal virus consisting of an enveloped, icosahedral, 50–70 nm capsid with single-stranded infectious RNA (plus strand) of 4 MDa. Togaviruses include mosquito- and tick-borne viruses causing encephalitis and yellow fever.

tolaasin a channel-forming cyclic lipodepsipeptide similar to **syringomycin**. It is produced by *Pseudomonas tolaasi* and causes the brown blotch disease of the cultivated mushroom *Agaricus bisporus*. It is classified in the TC system under number 1.D.4.

tolbutamide 1-butyl-3-(*p*-tolylsulfonyl)urea, *N*-[(butylamino) carbonyl]-4-methylbenzenesulfonamide; the prototype of sulfonylurea drugs, which exert a hypoglycemic action by stimulating release of insulin from the pancreas and are used to treat type II **diabetes mellitus**.

TolC a homotumeric protein that forms a 12-stranded beta-barrel that spans the **outer membrane** of *E. coli* and has a long 12-stranded, mostly alpha-helical, barrel that extends far into the periplasm. It permits exit of large secreted proteins and of smaller toxic compounds. Each channel consists of a homotrimer, with each subunit containing 471 amino acids.

TolC channel funnel a structure that functions to export substances out of the Gram negative bacteria by the Type I secretory pathway. It forms a contiguous channel with an inner membrane transporter, providing a direct pathway through the periplasm and outer membrane. TolC channels eliminate a wide variety of toxic compounds and drugs.

tolerance **1** the progressive attenuation of the response to an agent (usually a drug) whereby increasing concentrations of the agent are required to maintain the response. Underlying mechanisms confer either functional (or pharmacodynamic) tolerance, where the loss of response is due to desensitization of effector mechanisms, or metabolic (or pharmacokinetic) tolerance, whereby elimination of the agent is accelerated usually by induction of catabolic enzymes or other inactivating mechanism. **2** the ability of an organism to grow and thrive in an unfavourable environment. **3** an allowable deviation from a standard. **4 immunological tolerance**.

tolerogen an antigen that, in given circumstances, induces **immunological tolerance** when administered to an animal. Tolerogens may, when presented in different circumstances, induce an immune response. **—tolerogenic** *adj.*

Toll a developmental protein in *Drosophila melanogaster*, the product of *toll* gene, that is required for embryonic dorsal–ventral polarity. It is a type I transmembrane signalling receptor protein with a **leucine-rich repeat** segment.

Toll-like receptor *abbr.*: TLR; any of a family of receptors that are homologous to Toll of *Drosophila* and occur on leukocytes and epithelial cell surfaces. They recognize components of pathogenic microorganisms and trigger secretion of cytokines such as tumour necrosis factor and interleukins 6 and 8. About ten have been identified in humans. TLR2 binds bacterial peptidoglycan and lipoprotein; TLR4 binds Gram-negative lipopolysaccharides; TLR5 binds flagellin; and TLR9 binds the CpG motif of bacterial DNA.

tolloid a developmental protein in *Drosophila melanogaster* encoded by the ***tld*** gene; it is a member of the **astatin** subfamily of metalloproteases.

tol plasmid a plasmid that specifies the degradation of aromatic hydrocarbons. *Pseudomonas putida* containing the pWWO plasmid grows on toluene, *m*- and *p*-xylene, *m*-ethyltoluene, and 1,2,4 trimethylbenzene. Enzymes required for the metabolism of these compounds are encoded by the *xyl* operons.

TOM *abbr. for* translocase of outer mitochondrial membrane; a complex of transmembrane proteins in the outer mitochondrial membrane that consists of receptors for proteins targeted for import into the organelle and a general insertion pore (GIP). The receptors are the heterodimers Tom70–Tom37 and Tom22–Tom20. The GIP consists of multiple copies of Tom40, Tom7, Tom6, and Tom5. Tom40 is predicted to form a beta barrel, whereas all the others have one transmembrane segment each. The cytosolic parts of Tom70 and Tom20 contain tetratricosapeptide repeats, which bind and bring their respective heterodimers together. This information is based on studies performed on the yeast complex. It is believed that TOM and **TIM** are apposed across the intermembrane space.

tomography a radiographic technique that can image a thin plane or section of a body. An X-ray beam is focused on an area of a body, the beam is then rotated, and successive images are stored and subsequently analysed by computer (**computer-assisted tomography**, or CAT scanning). **Positron emission tomography** (or PET scanning) involves the detection of X-rays emitted from radionuclides that decay by positron emission and are located within the patient's body, e.g. from ^{15}O (**oxygen-15**) after administration of $H_2{}^{15}O$.

ton 1 *or (esp. US)* **long ton** a unit of mass equal to 2240 **pounds** avoirdupois (1016.05 kg). **2** *or (esp. US)* **short ton** *or* **net ton** a unit of mass equal to 2000 pounds avoirdupois (907.18 kg). **3** metric ton; *see* **tonne**.

TonB-dependent transporter any 22-stranded beta-barrel transporter protein of the outer membrane of Gram-negative bacteria that is dependent for its function on contact with the TonB complex of the inner membrane. Examples are the ferric enterobactin receptor/transporter (FepA) and the ferrichrome receptor/transporter (FhuD), which permit entry of iron chelates and of vitamin B_{12}.

tone 1 *(in physiology) or* **tonus** the state of sustained partial tension adopted by muscles in order to maintain posture, etc. It is brought about by the contraction of only a certain proportion of the muscle fibres at any given time. **2** *(in clinical medicine)* the state or degree of firmness of a muscle on palpation.

tonicity 1 the **osmotic pressure** of a solution; often used in the sense of the ratio of the osmotic pressure of a solution to that of a given reference solution. **2** (of a muscle) the condition of possessing **tone** or tension. *See also* **hypertonic**, **hypotonic**, **isotonic**.

tonin EC 3.4.21.35; *other names*: esterase 1; S2 kallikrein; RGK-2; RSKG-5; a serine protease, present in several rat tissues, that can cleave angiotensinogen and angiotensin-tetradecapeptide renin substrate to produce angiotensin II directly. It also acts on the Phe-|-His bond of angiotensin I to form angiotensin II.

tonne *or* **metric ton** *symbol*: t; a unit of mass equal to 10^3 kg. 1 tonne = 0.984 207 UK ton or 1.102 31 short (US) tons.

tonometer 1 an apparatus, usually a closed glass vessel, used to equilibrate a liquid, especially blood, with a particular gas of known partial pressure. When equilibrium is established the phases are separated and the gas in question determined in both phases. **2** a device for measuring vapour pressure.

tonus *an alternative term for* **tone** (def. 1).

too many mouths *see* **TMM**.

tooth-lid factor *a name originally given to* **epidermal growth factor**.

top+ *a variant form of* **topo+** (before a vowel).

TOPA *abbr. for* 3,4,6-trioxyphenylalanine; 6-hydroxydopa. *See also* **TOPA-quinone**.

TOPA-quinone 3,4,6-trihydroxyphenylalanine quinone; 6-hydroxydopa quinone; the covalently bound redox prosthetic group of bovine plasma amine oxidase and some other copper-containing oxidases. It is formed by a post-translational modification involving hydroxylation of tyrosine contained in an active site with the consensus sequence, Asn-Tyr-Asp/Glu.



TOPA-quinone

topical relating to a particular place or part of the body; local; (of a medicament, nutrient, etc.) applied locally rather than systemically. —**topically** *adv.*

topical magnetic resonance spectroscopy *abbr.*: TMR spectroscopy; a method for obtaining high-resolution **nuclear magnetic resonance** spectra from a selected place in a larger specimen (e.g. a specific organ of a living body). The sensitive volume is generated by superimposing high-order magnetic field gradients onto the main magnetic field of the spectrometer in such a manner as to define a central region of uniform field and adjustable size, surrounded by rapidly changing fields. Signals may be detected from individual nuclei, and the signals can be attributed to specific metabolites, enabling measurement of the level of these metabolites *in situ*.

topo+ *or (before a vowel)* **top+** *comb. form* denoting place or region.

topochemical 1 of, or pertaining to **topochemistry**. **2** of, pertaining to, or constituting a locally confined chemical reaction. **3** describing a combined tactile and chemical sense in some animals that is important in the perception of odours in relation to track or position.

topochemistry the characteristic chemical activity of a **topomer**.

topogenesis *an alternative term for* **morphogenesis**, especially in regard to biomolecular structures. —**topogenic** *adj.*

topogenic sequence any part of the sequence of a nascent polypeptide that is involved in getting the mature protein to its proper position in the cell. *See* **signal peptide**.

topogenic signal any feature of the structure of a macromolecule that directs it to a particular organelle in a cell. The term includes **topogenic sequence**. *See* **mannose 6-phosphate**.

topography 1 the science and practice of describing the arrangement in space of shapes and surfaces, and of components in relation to one another. **2** the detailed description, or representation on a map, diagram, etc., of the surface features of a three-dimensional object, or part of one, with reference to the underlying structure. *Compare* **topology**. —**topographic** *or* **topographical** *adj.*; **topographically** *adv.*

topoinhibition the inhibition of a cellular process by an action at the cell membrane, especially through contact with, or proximity to, other cells.

topoisomer *or* **topological isomer** any of two or more **isomers** of a macrocyclic molecule, or system of two or more macrocyclic molecules or molecular subunits, that differ in the degree of knotting of a loop or the degree of interlocking of rings. Topoisomers of a given molecule, or system of molecules, display the same connectivity, bond orders, and configurations but can be interconverted only by breaking and reforming a covalent bond; they have different **linking numbers**. *Compare* **topomer**. —**topoisomeric** *adj.*; **topoisomerism** *n.*

topoisomerase *see* **DNA topoisomerase**.

topological bond the force equivalent to a chemical bond that may be conceived as holding together any two interlocked rings of a catenated molecular structure or two loops of a knot in a cyclic molecule. Such a bond is the property not of a pair of atoms but of the complete molecule, the strength of the union being that of the weakest chemical bond in the entire structure.

topological isomer *an older name for* **topoisomer**.

topological isomerism *an alternative term for* topoisomerism; *see* **topoisomer**.

topological winding number *see* **supercoil**.

topology 1 *(in molecular biology)* the study of deformability and deformation of structures, including macromolecules. The basic concept is founded on whether a particular figure or surface can be continuously deformed without rupture and remaking of, e.g., a chemical bond. **2** *(in botany)* the study of localities where plants are found. **3** *(in mathematics)* the branch of geometry that deals with general types of shape rather than with particular shapes and sizes; the study of relationships that remain invariant under one-to-one transformation. *Compare* **topography**. **—topological** *or* **topologic** *adj.*; **topologically** *adv.*

topomer any of two or more **conformers** of a macromolecule that have differing **topography** (def. 2). Any topomer (or its exact mirror image) is characterized by a unique set of interactions between any two residues of the complete sequence of the macromolecule. *Compare* **topoisomer**.

topotactic describing a chemical reaction in which the product has an ordered geometric relationship to the reactant.

top yeast *see* **bottom yeast**.

torin *or* **calpromotin** a protein of human erythrocytes that forms a ten-subunit torus that interacts with the plasma membrane, with stomatin and with cyclophilin. Each subunit contains 198 amino acids.

toroid **1** *an alternative term for* **torus**. **2** the solid enclosed by a torus. **—toroidal** *adj.*

torr *symbol*: torr; a non-SI unit of pressure, used especially in connection with low pressures. It is defined as equal to 1/760 of an atmosphere; i.e. 1 torr = 101 325/760 Pa = 133.322 Pa. Its use is now discouraged, in favour of the **pascal**. [After Evangelista Torricelli (1608–47), Italian physicist.]

torsin an **AAA protease** of the endoplasmic reticulum lumen. Mutation leads to autosomal dominant torsion dystonia.

torsion **1** the twisting of something about an axis by the application of equal and opposite rotational forces acting in parallel planes. **2** the twist so produced. **—torsional** *adj.*

torsion angle *symbol*: θ *or* ω; consider an assembly of attached atoms represented by the generalized partial structure X–A–B–Y, where neither X nor Y is collinear with A and B, then the torsion angle is the smaller angle subtended by the bonds X–A and Y–B in a plane projection obtained by viewing the assembly along the axis A–B. Depending on the direction of rotation, right or left, of the bond to the furthermost atom, Y, relative to the bond to the atom nearest the viewer, X, the angle is considered positive or negative, respectively. The multiplicity of the bonding of the various atoms is not relevant. A torsion angle may similarly be defined for a partial structure X–A–Z–B–Y where Z represents one or more additional atoms and A, Z, and B are collinear. The torsion angles for the backbone of a polypeptide chain are symbolized as follows: that for rotation about the N–C^{α} bond is denoted by ϕ; that for rotation about the C^{α}–C' bond is denoted by ψ; that for rotation about the C'–N bond is denoted by ω. The torsion angles for the backbone of a polynucleotide chain are as shown below. *See also* **conformation**, **Ramachandran plot**, **beta turn**.



designation of torsion angles for polynucleotides

torsion balance an instrument, used for the rapid weighing of small amounts of substances, in which the sample is balanced by the torsion of a wire and the amount of torsion that has to be applied to restore balance is indicated as a scale calibrated in units of mass.

torso a gene for a tyrosine kinase (EC 2.7.1.112) receptor in *Drosophila melanogaster*. The receptor is a type I membrane glycoprotein and is involved in the determination of anterior and posterior structures in the embryo.

torulin *an obsolete name for* extracts of yeast that cure polyneuritis in pigeons fed on a diet of polished rice, no doubt due to the vitamin B_1 content of yeast extract.

torus (*pl.* **tori**) a shape generated by rotating a circle or disk about an axis that is displaced outside the diameter of the circle or disk, but in the same plane; i.e. shaped like a ring doughnut (donut). *See also* **toroid**. **—toric** *adj.*

Tos *symbol for* the tosyl group.

tosyl *symbol*: Tos; *a trivial name for* the toluene-4-sulfonyl group, CH_3–C_6H_4–SO_2–, with which amino groups may be modified by allowing them to react with *p*-toluenesulfonyl chloride. *Compare* **pipsyl**.

total body water *abbr.*: TBW; *see* **body water**.

totipotent (of a cell) having the potentiality to develop in any way possible, given its particular genetic constitution, and thus to form a new organism or to regenerate any part of an organism.

touchdown PCR a variant of **polymerase chain reaction** (PCR) in which the annealing temperature is decreased by, say, 1°C every second cycle until a touchdown annealing temperature is reached for completion of the amplification. The advantage is that it enriches for products containing correct matches between primers and template, and minimizes spurious priming during amplification.

Tourette syndrome a relatively common autosomal dominant condition, characterized by chronic motor and vocal tics, that usually begins in childhood. Dopamine drugs enhance the symptoms, whereas certain dopamine receptor antagonists decrease them. The gene product responsible is unknown. [After Georges Gilles de la Tourette (1857–1904), French physician.]

toxic **1** poisonous. **2** of, relating to, or caused by a **toxin** or poison.

toxicity **1** the quality or state of being poisonous or toxic. **2** the relative degree of being poisonous or toxic; the potency of a **toxin**.

toxicogenic *an alternative term for* **toxigenic**.

toxicogenomics the analysis of the toxic effects of potential new drugs on gene expression patterns in target cells or tissues. It aims both to prioritize compound pipelines (to eliminate expensive failures in drug development), and to reveal genetic signatures that may predict toxicity in these compounds.

toxicology the science dealing with the effects of poisons on living organisms. The term is sometimes restricted to the effects of synthetic poisons and the term **toxinology** used when dealing with naturally occurring poisons.

toxic shock syndrome a syndrome of acute high fever, hypotension, diarrhoea, and a skin rash, that occurs in women usually during menstruation and with use of certain highly absorbent types of tampons. It is occasionally fatal, and is caused by infection from contamination by certain strains of *Staphylococcus aureus* that produce **toxic-shock syndrome toxin-1** (TSST-1).

toxic shock syndrome toxin-1 *abbr.*: TSST-1; a protein (193 amino acids) secreted by certain strains of *Staphylococcus aureus*, that is responsible for the **toxic shock syndrome**. It is a potent inducer of interleukins 1 and 2 and tumour necrosis factor.

toxify to poison; to render poisonous. **—toxification** *n.*

toxigenic *or* **toxicogenic** *or* **toxinogenic** (especially of bacteria and fungi) producing toxin.

toxin any of various specific poisonous substances that are formed biologically. Not all such poisons are so termed, their classification as toxins being somewhat arbitrary and tending to vary with the discipline concerned; furthermore, the term is sometimes extended to include synthetic poisonous substances. Various types of toxin may be designated according to the source of the toxin, e.g. **endotoxin**, **exotoxin**, **mycotoxin**, **phycotoxin**, **phytotoxin**, and **zootoxin**, or according to the specific or prime site of action of the toxin, e.g. **hepatotoxin** and **neurotoxin**.

toxinogenic *an alternative term for* **toxigenic**.

toxinology *see* **toxicology**.

toxoid an **exotoxin** that has been modified (e.g. by formalin treatment) so that its toxicity has been lost while its antigenicity (both immunogenicity and reactivity) is retained.

toxophore a term introduced by the German biochemist Paul Ehrlich (1854–1915) to denote the specific chemical group in a toxin molecule that is responsible for its toxic effect. Unlike the **haptophore**, it is destroyed on conversion of the toxin to a **toxoid**.

TP *abbr. for* thymopoietin.

TPA *abbr. for* **1** tissue-type plasminogen activator; *see* **plasminogen activator**. **2** 12-*O*-tetradecanoyl-phorbol-13-acetate (*or* phorbol 12-myristate 13-acetate; *see* **PMA**).

TPAP *abbr. for* testes-specific poly(A) polymerase.

TPCK *abbr. for* L-(1-tosylamido-2-phenyl)ethylchloromethyl ketone; a modifying reagent for histidine residues in peptidases such as trypsin.



T3 phage promoter a short DNA sequence recognized by the RNA polymerase from bacteriophage T3, e.g. –17 AATTAACC-CTCACTAAAGGAAGA +6.

T7 phage promoter a short DNA sequence recognized by the RNA polymerase from bacteriophage T7, e.g. –16 TATACGACT-CACTATAGGGAGA +6.

TPI *(formerly) abbr. for* **1** triphosphoinositide; use PtdInsP_2 (or PIP$_2$) instead. **2** phosphatidylinositol 4,5-bisphosphate; use PtdIns-4,5-P_2 instead. *See* **phosphoinositide**.

TPN *abbr. for* triphosphopyridine nucleotide; obsolete, use **NADP$^+$** .

TPNH *abbr. for* reduced triphosphopyridine nucleotide; obsolete, use **NADPH**.

TPP *abbr. for* thiamine diphosphate (*formerly* thiamin pyrophosphate); *see* **vitamin B$_1$** .

TPQ *abbr. for* topaquinone trioxyphenylalanine quinone; a quinone cofactor produced by post-translational modification of a tyrosyl residue in some quinoproteins.

TPR *abbr. for* tetratricosapeptide repeat.

tpr-met an oncogene formed by the translocation of the *tpr* (translocated promoter) locus of chromosome 1 and *met* (the gene for **hepatocyte growth factor receptor**).

T protein *see* **glycine cleavage enzyme**.

tra *symbol for* ***transformer***, a gene in *Drosophila*.

trace (*in sequencing*) a DNA sequence chromatogram that constitutes the primary data source for large-scale sequencing projects. Within the trace, coloured peaks represent each of the bases; the relative heights of the peaks determine which particular bases are read off to generate the raw nucleotide sequence.

tracee *(in tracer kinetics)* the non-radioactive compound of which the tracer is the radioactive equivalent; coined to represent unambiguously what has been variously called **stable material**, **mother substance**, etc. *Compare* **compartment**.

trace element *or* **microelement** any element that is present in the body of an organism at relatively minute concentrations (often arbitrarily defined as <0.005%), and consequently is required in the organism's diet in extremely small amounts. In higher animals the most important trace elements include: iron, zinc, copper, manganese, iodine, cobalt, molybdenum, selenium, and chromium. The extended list includes lead, arsenic, antimony, nickel, bromine, fluorine, boron, silicon, aluminium, silver, cadmium, bismuth, mercury, vanadium, titanium, indium, barium, strontium, and lithium. The term may be extended to cover elements of primarily toxicological interest.

trace metal any **trace element** that is a metal.

tracer an element or compound containing atoms that can be distinguished from their normal counterparts by physical means, e.g. by virtue of their radioactivity, mass spectrum, colour, etc. Tracers are used in biochemistry for following the metabolic pathways of substances in an organism, cell, or cell-free system.

track an individual lane resolving the components of a single sample on a slab electrophoresis gel.

tracking dye a dye that is added to a sample on an electrophoresis gel to be the fastest component and thus to indicate visually how far the samples have run at any instant in time.

TRADD *abbr. for* TNF receptor-1-associated death-domain protein; a cytosolic protein that interacts with tumour necrosis factor (TNF) receptor 1 after TNF binding and leads to activation of **NF-κB** and apoptosis. *See* **tumour necrosis factor receptor**.

TRAF 2 *abbr. for* TNF receptor-associated protein 2.

tragacanth **1** any thorny leguminous shrub of the genus *Astragalus*. **2** a gum obtained especially from *A. gummifer* and used extensively in commerce. It is a complex mixture of polysaccharides, including D-galacturonic acid, D-xylose, L-fucose, and D-galactose.

trailer sequence a sequence following the termination signal at the 3′ end of **messenger RNA**.

training set a data set that is characteristic of, or encapsulates information on, the problem to be solved, and is used as input for learning algorithms, such as neural nets and hidden Markov models (HMMs).

trait any observable, phenotypic feature of an individual.

TRAM *or* **TRAM protein** *abbr. for* translocating chain associating membrane protein; a transmembrane protein that spans the **rough endoplasmic reticulum** of mammalian cells, and plays a role in the translocation of nascent proteins destined for export from the endoplasmic reticulum.

TRAMP *abbr. for* tyrosine-rich acidic matrix protein; *other names*: 22 kDa extracellular matrix protein; dermatopontin; a protein of the extracellular matrix that may have various binding and adhesion functions.

TRANCE *an alternative term for* **RANKL**.

tranexamic acid *trans*-4-(aminomethyl)cyclohexanecarboxylic acid; it inhibits binding of plasminogen and plasmin to fibrin thereby inhibiting fibrinolysis.



trans+ *or (sometimes before s-)* **tran+** *comb. form* denoting across, beyond, on the other side, transverse; transfer, interchange. *See also* ***trans*-acting**.

trans- *abbr.*: *t*-; *prefix (in chemical nomenclature)* denoting a *trans*-isomer; *see* ***cis–trans* isomerism**.

***trans*-acting** describing a regulatory genetic element whose effects are insensitive to its position. Examples include the genes for bacterial repressors. *Compare* ***cis*-acting**.

***trans*-activation** gene activation by means of a ***trans*-acting** mechanism.

transacylase *an older name for* **acyltransferase**.

transaldolase EC 2.2.1.2; *other names*: dihydroxyacetone transferase, glyceronetransferase; an enzyme of the pentose phosphate pathway that catalyses the transfer of a 3-carbon glycerone moiety from sedoheptulose 7-phosphate to glyceraldehyde 3-phosphate forming erythrose 4-phosphate and fructose 6-phosphate. It has a broad substrate specificity.

transamidation a chemical reaction in which the amino group of an amide is exchanged for another amino group, i.e.:

$$R{-}CO{-}NHA + BNH_2 = R{-}CO{-}NHB + ANH_2.$$

Transamidation is catalysed by such proteolytic enzymes as **trypsin**, **chymotrypsin**, **papain**, and **subtilisin**.

transamidination a chemical reaction, catalysed by a transamidinase (aminotransferase) enzyme of sub-subclass EC 2.1.4, in which the amidino moiety of arginine is reversibly transferred to an amino group to form a different guanidino compound. An example is **glycine amidinotransferase**.

transaminase *an alternative name for* **aminotransferase**. *See also* **alanine transaminase**, **aspartate transaminase**, **transamination**.

transamination a chemical reaction, catalysed by any **aminotransferase** (transaminase) enzyme, in which the α-amino group of one amino acid is transferred to the α-carbon atom of an α-oxo acid. As a result, the α-oxo acid is transformed into an amino acid, and the amino acid that donated the amino group is converted to the corresponding α-oxo acid:

$$\mathrm{R'{-}CH(NH_2){-}CO_2H + R''{-}CO{-}CO_2H =}$$
$$\mathrm{R'{-}CO{-}CO_2H + R''{-}CH(NH_2){-}CO_2H}$$

Transamination is important in the catabolism of amino acids, in which the amino group is eventually or directly transferred to oxaloacetate (to form aspartate) or to α-oxoglutarate (to form glutamate). If transferred to aspartate, the amino group enters the **urea cycle** at the argininosuccinate step; if transferred to glutamate, the amino group is removed by glutamate dehydrogenase, yielding ammonia, which then enters the urea cycle. Transamination is also involved in amino-acid synthesis. Pyridoxal phosphate is the coenzyme of aminotransferases. Transamination was discovered by the Russian biochemists Alexander Evseyevich Braunstein (1902–86) and Maria Grigorievna Kritzmann (1904–71).

transbilayer signifying across or through the membrane **lipid bilayer**, as in **transbilayer distribution**, transbilayer movement.

transbilayer distribution the distribution of components between the two leaflets of a membrane lipid bilayer, but often referring specifically to lipids. In the plasma membrane this distribution is asymmetric: phosphatidylcholine and sphingomyelin are relatively enriched in the outer leaflet, and phosphatidylethanolamine and phosphatidylserine are more predominant in the inner leaflet (i.e. the cytoplasmic face).

transcarboxylase **1** methylmalonyl-CoA carboxyltransferase; EC 2.1.3.1; *systematic name*: (*S*)-2-methyl-3-oxopropanoyl-CoA:pyruvate carboxyltransferase; a biotinyl-protein, containing cobalt and zinc, that is present in prokaryotes and catalyses the transfer of a carboxyl group from methylmalonyl-CoA [(*S*)-2-methyl-3-oxopropanoyl-CoA] to pyruvate forming oxaloacetate and propanoyl-CoA. **2** a component of the prokaryote form of **acetyl-CoA carboxylase** that transfers the carboxyl group from *N*-carboxybiotin to acetyl-CoA.

transcarboxylation the transfer of a carboxyl group from one compound to another, e.g. as catalysed by a **transcarboxylase**.

transcobalamin *abbr*.: TC; any of three plasma glycoproteins (TC I, TC II, and TCIII) that are secreted by the liver and bind cobalamin. TC II binds newly absorbed cobalamin and transports it to the tissues, where the complex binds a specific receptor, is endocytosed, and the cobalamin released in lysosomes. In the postabsorptive state most cobalamin is bound to TC I. Deficiency of TC II results in congenital macrocytic anemia, which progresses to include immunodeficiency and neurological complications.

transconjugant a bacterial cell that has received genetic material from another bacterium by **conjugation**. A transconjugant should be referred to as a **recombinant** only if the transferred genetic material has been inserted into a pre-existing **replicon** in the recipient. If the transferred material is perpetuated *per se* as a plasmid, then the cell is called a **plasmid transconjugant**. If such material is not a plasmid and does not become a resident replicon, it will fail to replicate; the bacterium will be called an **abortive transconjugant**.

transcortin a specific plasma α_1-globulin, M_r 52 000, that binds **cortisol** at one binding site, and serves to transport the hormone. It also binds corticosterone and certain other steroid hormones; aldosterone is bound only weakly. Transcortin is synthesized in the liver. The normal serum concentration of transcortin is 3–4 mg $\mathrm{dL^{-1}}$; saturation occurs at a cortisol serum concentration of about 28 µg $\mathrm{dL^{-1}}$, other cortisol being less tightly bound to albumin or (about 5%) unbound. *Other names*: corticosteroid-binding globulin; corticosteroid-binding protein; cortisol-binding globulin (*abbr*.: CBG); cortisol-binding protein.

transcribe **1** to copy. **2** to use DNA as a template for the synthesis of mRNA, or, in some cases (e.g. as in retrovirus infection), to synthesize DNA from an RNA template. *See* **transcription**.

transcribing strand *an alternative name for* **noncoding strand** (of duplex DNA).

transcript the product of a **transcription** process; the **primary transcript** is the immediate product of an RNA polymerase.

transcriptase *an alternative name for* **DNA-dependent RNA polymerase**.

transcription the synthesis of either RNA on a template of DNA or DNA on a template of RNA. The latter is important in the replication of **retroviruses** by the enzyme **reverse transcriptase.** In the transcription of double-stranded (ds) DNA the RNA is formed on a template comprising only one strand, the transcribed strand. This is also called the antisense strand since the other strand is termed the sense strand. Transcription involves many steps. (1) The region of DNA to be transcribed must be unwound approximately one turn to form an open loop to allow the transcribed strand to form a DNA–RNA hybrid with the 3′ end of the newly synthesized RNA. (2) The mRNA is transcribed by **RNA polymerase** from nucleoside triphosphates. The enzyme binds to the **promoter**, which is a region of DNA on the transcribed strand that has a characteristic base sequence (e.g. **TATA box**), usually located upstream of the start of transcription. However, in the case of eukaryotic RNA polymerase III, the promoter may sometimes be located downstream of the start point. In prokaryotes, for transcription to proceed, a complex must be formed on the dsDNA with the promoter and an accessory factor, **sigma factor**. In eukaryotes, an extensive and complex system of **transcription factors** regulates the process. While prokaryotes appear to utilize only a single RNA polymerase, eukaryotes possess three RNA polymerases; RNA polymerase I is located in the nucleolus and is responsible for the synthesis of ribosomal RNA. This polymerase accounts for the greatest quantity of RNA synthesized. RNA polymerase II is situated in the **nucleoplasm** and is responsible for the synthesis of heterogeneous nuclear RNA, for **primary transcript** from which messenger RNA is formed. This polymerase is thus instrumental in determining the nature of the protein profile of the cell. RNA polymerase III is also in the nucleoplasm and synthesizes transfer RNA. (3) In eukaryotes RNA polymerase II advances along the DNA template. The DNA unwinds ahead of the growing RNA and rewinds behind it thereby stripping the newly synthesized RNA from the transcribed strand of the DNA. The origin of the energy requirements for this movement is unclear. The movement is terminated by specific sequences in the transcribed DNA strand. In some cases **rho protein** plays a part in termination. (4) **Transcription factors**, which may be ***cis*-acting** or ***trans*-acting**, control transcription. In prokaryotes changes are very rapid since transcription and translation are tightly coupled. In eukaryotes such changes are slower. The activity of eukaryotic transcription factors is enhanced by proteins called **enhancers**, which may exert their influence over distances of several thousand base pairs. They may be **upstream**, **downstream**, or even in the midst of a transcribed gene. They may also be tissue specific. In the case of eukaryotes where the gene is split by **introns** the entire gene is transcribed and the introns are subsequently excised from the primary transcript by splicing.

transcriptional repressor any **transcription factor** (usually bacterial) that down-regulates gene expression by binding to an **operator**.

transcriptional silencing the repression of gene expression in a chromosomal region, which can span several or many genes. It can spread along a chromosome until insulator sequences are reached. Silencing can limit the expression of transgenes inserted into genomes randomly.

transcriptional territory any large group of adjacent genes that are expressed together but are not related by structure or function of their products.

transcriptional unit the segment of DNA within which the **transcription** occurs that eventually leads to RNA formation. *Compare* **cistron**, **gene**.

transcription elongation complex the complex of proteins required for elongation of the transcript during transcription in eukaryotes. It includes several transcription factors, RNA polymerase, elongin and other elongation factors, chromatin modelling complexes, and RNA processing proteins.

transcription factor *abbr.*: TF; any protein required to initiate or regulate **transcription**; the term includes **enhancers** as well as the general transcription factors. Transcription factors bind to DNA sequence elements upstream of the **start point** and thus participate in the formation of the complex that includes RNA polymerase and initiates transcription. *See, e.g.* **NF-KB**, **Oct**, **TFII**, **TFIII**.

transcription initiation complex the complex of over 100 proteins (3.5 MDa) required for initiation of transcription in eukaryotes. It includes several transcription factors, RNA polymerase, Mediator, chromatin remodelling complexes, histone acetylases, and transcriptional activator proteins.

transcription *in vitro* *an alternative name for* ***in vitro* transcription**.

transcription-mediated amplification *abbr.*: TMA; a method for RNA amplification that uses RNA transcription by an RNA polymerase (such as T7 RNA polymerase) and DNA synthesis by reverse transcriptase to produce RNA transcripts from either DNA or RNA templates. It takes place under isothermal conditions and amplification of the order of 10^9-fold is possible in less than 30 min. Oligonucleotide primers are specific for the target sequence at the 3′ end and have a promoter for the RNA polymerase at the 5′ end.

transcription start site *abbr.*: TSS; the location at the 5′ end of a gene, adjacent to the **promoter**, at which the RNA polymerase complex binds to the DNA and initiates the process of transcription of that gene into mRNA. The precise context of the TSS depends on the gene, its host organism, the type of polymerase involved, and other factors. *Compare* **start point**.

transcriptome the entire set of mRNAs transcribed from a cell's genome. *Compare* **proteome**. **–transcriptomic** *adj.*

transcriptomics the study of transcriptomes, particularly how transcript patterns are affected by development, disease, or environmental factors such as hormones, drugs, etc. *Compare* **proteomics**.

transcytosis the transport of molecules across a cell, especially across a **polarized cell**, such as an intestinal epithelial cell, which has a basolateral and an apical membrane of different composition, which thus provides a spatially orientated transport system. The molecules undergoing transcytosis are usually contained within vesicles. One example is the absorption of maternal antibodies from the gut in newborn animals. The antibodies are taken into epithelial cells by endocytosis at the apical surface, and are transported through the cell before being released at the basal surface into the blood. Transcytosis also occurs in thyroid cells: following endocytosis from the thyroid follicle, thyroglobulin is transported across the cell in vesicles with concomitant proteolysis, with release of thyroid hormone into a blood capillary at the opposite face of the cell (*see* **thyroid gland**). **—transcytotic** *adj.*; **transcytose** *vb.*

transdeamination *a former term for* the coupling of a transamidation reaction and the dehydrogenation of L-glutamate whereby an amino group of an amino acid is transferred to α-oxoglutarate by a transaminase enzyme and the resulting L-glutamate is dehydrogenated to yield α-oxoglutarate, ammonia, and a reduced coenzyme molecule.

***trans*-dominant mutation** a mutation in a regulatory gene that can control the expression of a structural gene on another chromosome.

transducer any device that converts a quantity of energy from one form into another.

transducin *abbr.*: G_T *or* G_t; a heterotrimeric **G protein** of the retina, and a component in the visual transduction pathway. In the vertebrate light response, inactive heterotrimeric transducin with bound GDP ($G_{t\alpha\beta\gamma}$·GDP) binds the photoactivated rhodopsin, metarhodopsin II, and releases GDP. GTP then binds to the α subunit, which then separates from both the receptor and the βγ heterodimer. $G_{t\alpha}$ then activates cyclic GMP phosphodiesterase, and the resulting fall in cyclic GMP concentration closes cyclic GMP-gated cation channels and hyperpolarizes the retinal rod cell, generating the nerve impulse.

transducon any large protein complex that contains components of a signalling cascade anchored to one or more scaffold proteins.

transduction 1 *(in microbiology)* the transfer of genetic information to a bacterium from a bacteriophage or between bacterial or yeast cells mediated by a phage vector. In **generalized transduction** any of the donor genes may be transduced, whereas in **specialized transduction**, i.e. by a **lysogenic** bacteriophage, only those genes at one of the ends of the prophage can be transduced. **Abortive transduction** occurs when phage DNA is not incorporated into the bacterial genome, but can nevertheless be transmitted in the phage to one of the daughter cells. **2** *(in biochemistry)* the activation of an intracellular effector pathway as a result of receptor activation by an extracellular signal. *See also* **second messenger**, **signal transduction**.

transesterification a chemical reaction in which the alcohol moiety of an ester is exchanged for another alcohol:

$$R–CO–OA + BOH = R–CO–OB + AOH$$

It is catalysed by such proteolytic enzymes as trypsin, chymotrypsin, papain, and subtilisin, and by esterases.

***trans*-fatty acid** any fatty acid that contains ethylenic bonds in the *E* configuration (i.e. *trans*). They can occur as the result of biohydrogenation in ruminant animals (cows, sheep, and goats) or during partial hydrogenation/isomerization of unsaturated fats (both vegetable and animal) to harden fats. Because of the association with risk of heart disease, the levels of *trans* fatty acids in margarines are kept to a minimum (at least in the UK and Denmark). The reasons why trans fatty acids are associated with increased risk of heart disease is uncertain – they lower HDL cholesterol compared with the corresponding *cis*-isomers, but not compared with carbohydrate.

transfection originally the process of infection of competent bacterial cells by free bacteriophage or plasmid nucleic acid that results in the subsequent production of normal bacteriophage or plasmids in the infected bacterial cell. It has come to mean the process of bringing about genetic alteration of any cell or organism using recombinant DNA technology.

transferase an enzyme that catalyses the transfer of a group – e.g. a methyl group, glycosyl group, acyl group, or phosphorus-containing group – from one compound (the donor) to another compound (the acceptor). Transferases, of which there are many, are EC class 2 enzymes.

transference number *or* **transport number** *symbol*: *t*; the fraction of the current being carried by a given type of ion when an electric current is passing through an electrolytic solution.

transfer factor a **lymphokine** extractable from leukocytes and thought to transfer the ability to elicit a **delayed hypersensitivity** reaction from one person or animal to another.

transfer gene any gene carried by a **conjugative plasmid** that is responsible for the donor phenotype.

transfer membrane a membrane used with **blotting** techniques in recombinant DNA technology or protein studies. Materials of interest are transferred from an electrophoretic gel to the transfer membrane either by capillary attraction or by using an electric potential (**electroelution**). Transfer membranes are of three types: (1) nitrocellulose – mixed esters of cellulose acetate and cellulose nitrate; high cellulose nitrate improves binding of biomolecules while a low percentage of cellulose acetate improves handling properties; nucleic acids can be fixed to nitrocellulose membranes by baking; (2) nylon, which is physically more robust and reusable, and to which nucleic acids can be fixed by exposure to ultraviolet light; or (3) polyvinylidene-based membranes.

transfer-messenger RNA *see* **tmRNA**.

transfer potential *another name for* **group transfer potential**.

transfer reaction *another name for* **group transfer reaction**.

transferrin any of a class of monomeric, two-domain (76–81 kDa), metal-binding glycoproteins, widely distributed in physiological fluids and cells of vertebrates, with the characteristic property of a stringent association of their metal-combining properties with an anion-binding requirement; iron-binding transport proteins that bind two Fe^{3+} in association with bicarbonate (or other anion). They are an essential component in cell culture media, transporting iron into cells through the **transferrin receptor**. The transferrin family includes proteins such as **lactoferrin**, **melanotransferrin** (with electrophoretic polymorphisms), ovotransferrin (*see* **conalbumin**) and **serotransferrin** (*other names*: siderophilin; β-1-metal binding globulin).

transferrinjection a method of gene transfer in which DNA complexed to transferrin–polycation conjugates is introduced into cells by receptor-mediated endocytosis.

transferrin receptor a type I transmembrane glycoprotein of the plasma membrane that, on binding transferrin, undergoes endocytosis for transfer of Fe^{3+} ions into the cell. It consists of two identical single-pass subunits joined extracellularly by a disulfide bond. The intracellular domain is phosphorylated and palmitoylated, i.e. acylated with a palmitoyl group by a process analogous to **myristoylation**. Synthesis of the receptor is regulated by binding of aconitase to mRNA when intracellular iron concentrations are low, stimulating receptor synthesis, possibly by stabilizing the mRNA.

transfer RNA *abbr.*: tRNA; *other names*: acceptor RNA; amino-acid-accepting RNA; *(formerly)* soluble RNA (*abbr.*: S-RNA *or* sRNA). Any relatively small **RNA** molecule (73–93 nt) that mediates the insertion of an amino acid at the correct point in the sequence of a nascent polypeptide during protein synthesis. The amino-acid residue is attached by ester link to the adenosine of a CCA sequence at the 3′ terminal of tRNA at either the 2′- or 3′-OH on the ribose. Specific tRNA molecules are present for the various amino acids. The amino acid is attached by a specific amino acid–tRNA ligase, which first forms an aminoacyl-adenylate, and then transfers the aminoacyl group to the tRNA. Each tRNA possesses an **anticodon** of three nucleotides that base pairs in an antiparallel fashion with the codons of mRNA. There are 61 sense codons but only about 41 different tRNAs in the cytoplasm and even fewer in mitochondria due to flexibility in the base pairing between codon and anticodon (*see* **wobble hypothesis**). The sequence of tRNA for phenylalanine – determined by US biochemist Robert Holley (1922–93) – indicated a clover-leaf secondary structure and the anticodon to be on a loop lacking base pairing. The tertiary structures that have been determined for tRNAs have supported the clover-leaf structure. tRNA is characterized by the presence of many unusual **minor bases** whose function has not been completely established. *See also* **initiator transfer RNA**, **suppressor tRNA**.

transform **1** to bring about **transformation**. **2** *(in mathematics)* **a** a process for deriving one mathematical entity from another. **b** the transformed entity itself.

transformant a bacterial cell that has undergone **transformation** (def. 1), i.e. one that contains integrated donor genes that can be detected by plating on media selective for some or all of the donor genes.

transformation **1** *or* **genetic transformation** the intraspecific and interspecific transfer of genetic information by means of 'naked' extracellular DNA in bacteria. In transformation, in contrast to **transduction**, the DNA not integrated into the recipient's genome cannot function and manifest its genetic information phenotypically. **2** characteristic and inherited changes produced in cells in culture when they have been treated with certain viruses (which may be DNA- or RNA-containing), or with chemical carcinogens, or with X-rays, or when they have been subjected to genetic modification by DNA technology. In animal cells, these changes include certain specific alterations in morphology (especially of the nucleus) and stainability, and the cells usually show a loss of **contact inhibition** and can give rise to neoplastic growth on injection into animals. The term also refers to corresponding changes occurring in cells *in vivo*. **3** *or* **blast transformation** *or* **lymphocyte transformation** the morphological and other changes that occur in both B and T lymphocytes when they are cultured in the presence of an antigen to which they are primed, or that occur nonspecifically in B lymphocytes when they are exposed to a mitogen (e.g. certain lectins). The lymphocytes increase in size and develop a basophilic ribosome-rich cytoplasm, a prominent nucleolus, and a paler-staining nucleus. After about three days these cells resemble **blast cells**. **4** the alteration produced in certain specific hormone-receptor proteins, present in the extranuclear region of hormone-responsive cells, when the hormone binds to them. This alteration is accompanied by the migration of the hormone–receptor complexes to the nucleus. **5** *or* **nuclear transformation** (of an atomic nucleus) the change of one **nuclide** to another.

transformer *symbol*: *tra*; a gene in *Drosophila* that is required for all aspects of female somatic sexual differentiation. Binding of the female SXL protein to the transformer pre-mRNA transcript results in splicing to remove exon 2, which contains a stop codon present in the male transcript. In this way females express a functional transformer protein, and males a nonfunctional one.

transforming growth factor *abbr.*: TGF; either of two types of mitogenic **cytokine**, TGFα and TGFβ. **TGFα** was isolated and purified on the basis of its ability to stimulate cell growth in soft agar. It is produced by macrophages, brain cells, and keratinocytes, and is mitogenic for fibroblasts, is angiogenic *in vivo*, and induces epithelial development. It is a glycoprotein and a member of the **epidermal growth factor** (EGF) family, interacting with the EGF receptor. TGFα comprises 50 amino acids with the following sequence (residues invariant in the EGF family are underlined): $\mathrm{VVSFHND\underline{C}PDSHTQF\underline{C}FH\underline{G}T\underline{C}RFLVQEDKPA\underline{C}V\underline{C}HSG\underline{Y}VGA\underline{RC}EHADLLA}$. **TGFβ** is a multifunctional peptide that controls proliferation, differentiation, and other functions in many cell types. It is produced by fibroblasts, platelets, monocytes, chondrocytes, and osteoblasts. A glycoprotein with EGF repeats, at least five types (TGFβ1 to TGFβ5) are known; all have 112 amino acids except TGFβ5, which has 114. They have a great many biological activities and can be mitogenic or antiproliferative depending on cell type. Platelets contain large amounts, but these proteins are also found in a variety of cell types. Alternative splicing results in different forms of TGFβ1 in platelets and fibroblasts.

transforming growth factor receptor any of the membrane proteins that bind transforming growth factor β (TGFβ) and mediate its effects. Three types of receptor for TGFβ have been distinguished: types I and II have high affinity for TGFβ1, with lower affinity for TGFβ2; type III has high affinity for TGFβ1, 2, and 3. Types I and II have a single transmembrane domain with a cytoplasmic protein serine/threonine domain. The human type III receptor has a single transmembrane domain and little cytoplasmic structure. It is derived from an 849-amino-acid precursor, of which residues 1–16 are the signal, 17–781 form the extracellular domain (heavily glycosylated), and 808–849 are intracellular. It may present TGFβ to the signalling receptors.

transforming principle *a historical name for* the purified DNA that, when incorporated into a bacterial cell, brings about the **transformation** (def. 1) of that cell. The term was used, most famously, by Oswald Theodore Avery (1877–1955, US bacteriologist and immunologist) and colleagues in their work establishing that DNA, not protein, was responsible for genetic transformation. They used a wild strain of *Pneumococcus*, known as S (for smooth) strain because of the kind of colony that it forms, which is pathogenic; and a mutant strain, known as R (for rough) strain, which is non-pathogenic. When mice were injected with live R strain or heat-killed S strain, they remained healthy, but when injected with a combination of live R strain and heat-killed S strain they died. These workers concluded that the live R strain could be transformed into a pathogenic strain by material from the heat-killed S strain, and were able to demonstrate that the material was DNA.

transfuse to transfer blood from one animal into the circulation of another animal, or to inject liquid into the circulation of an animal to maintain the circulating fluid volume. **—transfusion** *n.*

transgene a gene that is inserted, using cDNA technology, into the germ line in a manner that ensures its function, replication, and transmission as a normal gene. *See also* **transgenesis**, **transgenic**.

transgenesis the creation in plants or animals of a stably incorporated gene or genes derived from another cell or organism which can be passed on to successive generations.

transgenic describing an organism harbouring in its germ line a gene that has been introduced using cDNA technology (*see* **complementary DNA**). In animals, the transgene is introduced during transient culturing of an egg or early embryo, which is then implanted into a foster mother. Several techniques are available: cells may be transferred from one embryo to another (to produce a **chimera**); **pluripotent** cells can be introduced into an embryo; cells infected with a retrovirus can be introduced; or cDNA can be introduced by microinjection into the pronucleus of a fertilized egg. In plants, plasmids from *Agrobacterium tumefaciens* have been widely used to produce transgenic varieties. The **Ti plasmid** is a natural vector for genetically engineering plant cells, because it can transfer its **T-DNA** to the plant genome. Expression of the introduced genes can be controlled by suitable promoters, such as the cauliflower mosaic virus promoter.

transgenomes large complexes of DNA found inside recipient cells following transfection of the latter with calcium phosphate-precipitated DNA.

transgenosis the transfer of genetic information between unrelated organisms and its expression (including gene maintenance, transcription, translation, and function), especially when donor and recipient cells are widely separated by evolution (e.g. bacterial and eukaryotic cells respectively) and when the mechanisms of gene transfer and maintenance are obscure. *Compare* **transgenesis**.

transglutaminase *an alternative name for* **protein–glutamine γ-glutamyltransferase**.

transglycosylation a chemical reaction in which one glycosyl residue is transferred from a glycoside onto a receptor molecule so as to form a new glycosidic linkage, e.g. in the biosynthesis of polysaccharides. The process involves breaking simple glycosidic linkages and reforming them into different types of glycosidic linkages. **Glycosyltransferases** are in subclass EC 2.4; also included in the term are glycosyl transfers to water and to inorganic phosphate.

transient 1 temporary, transitory, short-lived. **2** a sudden, short-lived disturbance in a system. **3** a short-lived chemical species such as an excited atom or molecule or a free radical.

transient expression the phenomenon whereby following transfection of mammalian cells with recombinant DNA a high level of expression of the protein of interest may be possible for only a few days. *Compare* **stable expression**.

transient-phase kinetics *an alternative name for* **pre-steady-state kinetics**.

transient receptor potential channel *see* **TRP channel**.

***trans* isomer** *see* ***cis–trans* isomer**.

transition *(in molecular biology)* a type of mutation of DNA that occurs by replacement of one purine by another purine, or one pyrimidine by another pyrimidine whether by chemical change or by substitution. *Compare* **transversion**.

transition element *or* **transition metal** any element whose atom has an incomplete d-subshell of extranuclear electrons, or which gives rise to a cation or cations with an incomplete d-subshell. Such elements fall into groups 3 to 11 inclusive of the IUPAC **periodic table**. (Elements of group 12, which formerly were also considered as transition elements, have complete d-subshells and are now excluded.) The first series of transition elements is in period 4 of the periodic table and comprises those of proton numbers 21 to 29 inclusive, i.e. the elements scandium, titanium, vanadium, chromium, manganese, iron, cobalt, nickel, and copper; the second series is in period 5 and comprises those of proton numbers 39 to 47 inclusive, i.e. the elements yttrium, zirconium, nobium, molybdenum, technetium, ruthenium, rhodium, palladium, and silver; the third group is in period 6 and comprises those of proton numbers 57 to 79 inclusive, i.e. the **lanthanoids** together with the elements hafnium through to gold; and the fourth series is in period 7 and contains those of proton numbers 89 to 103 inclusive, i.e. the **actinoids**, and may well be found also to contain a number of elements of proton number 104 or more that yet remain to be characterized or discovered. The lanthanoids and actinoids are designated **inner transition elements** of periods 6 and 7 respectively; their atoms also have incomplete inner f-subshells of electrons. All transition elements are metals, they often have more than one valency state, and they form many coordination complexes, which frequently are coloured.

transition state *or* **activated complex** *(in enzymology)* the state of most positive molar **Gibbs energy** through which an assembly of atoms must pass on going from the reactants of a single-step chemical reaction to the products. This is the state that occurs immediately after binding of the reactants to the enzyme's active site; it is during this time that transient bonds between reactants and enzyme are first formed, and initial electronic interactions occur. It is followed by a state in which more stable intermediates form, prior to the eventual formation of products.

transition-state theory the theory that relates the rate of an enzymic reaction to the difference in **Gibbs energy** between the **transition state** and **ground state** ($\Delta G^{\ddagger}$). If x is the ground state and $x^{\ddagger}$ the transition state, then the rate of decomposition of x is given by:

$$-d[x]/dt = \nu[x^{\ddagger}] = [x](kT/h)\exp(-\Delta G^{\ddagger}/RT),$$

where ν is the vibrational frequency of the bond that is breaking, h is the Planck constant, k the Boltzmann constant, R the gas constant, and T the thermodynamic temperature.

transition temperature *symbol*: T_t; (of a membrane lipid) the surface temperature at which a heated lipid bilayer undergoes transition from one physical state (e.g. liquid crystalline) to another (liquid). *See also* **pretransition temperature**, **phase transition (of lipids)**.

transit peptide any ~4 kDa peptide sequence at the N or C terminus (or both) of cytoplasmically synthesized precursor proteins of certain chloroplast proteins that contains the information to ensure both the specific post-translational transport of the protein into the chloroplast and its localization within the organelle. The transit peptide is removed within the chloroplast.

transit time the time taken by a coenzyme or metabolite in travelling between two enzymes. If the two enzyme reactions were infinitely fast, the overall velocity would be determined by the reciprocal of the transit time.

transketolase EC 2.2.1.1; *systematic name*: sedoheptulose-7-phosphate:D-glyceraldehyde-3-phosphate glycolaldehydetransferase; *other name*: glycolaldehyde transferase. An enzyme that catalyses the transfer of a glycolaldehyde (HOH_2C–CHO–) moiety from xylulose 5-phosphate to ribose 5-phosphate to form glyceraldehyde 3-phosphate and sedoheptulose 7-phosphate, in the pentose phosphate pathway. It requires thiamine diphosphate (TPP) as coenzyme; a glycolaldehyde–TPP intermediate is formed transiently during the reaction. It has broad substrate specificity. Measurement of transketolase activity in a red cell hemolysate, in the presence and absence of thiamin, gives an indication of the thiamin status of the individual (by revealing the degree of activation of the enzyme in the absence of thiamin).

translation 1 *(in molecular biology)* the process by which a particular sequence of bases in messenger RNA (mRNA) determines a sequence of amino acids in a polypeptide chain during **protein and peptide biosynthesis**. One or more specific base triplets (codons) code for each of the 20 amino acids (*see* **genetic code**). Each codon of the mRNA molecule is recognized by the corresponding anticodon on the **transfer RNA** (tRNA) to which the amino acid is attached. The tRNA binds to a site on the large subunit of the **ribosome**, which is associated with the small subunit to which the mRNA is bound. The first codon (the initiation codon) in each mRNA molecule is AUG, which codes for formylmethionine (in prokaryotes and mitochondria) or methionine (in eukaryotes). The methionine or formylmethionine, or just the formyl group, is removed before the chain is completed. Completion of translation is signalled by one of three termination codons. **Release factors** effect the release of the complete polypeptide chain and the dissociation of the ribosomal subunits. **2** movement or displacement laterally in space without rotation or change of orientation.

translational frictional coefficient *see* **frictional coefficient**.

translational fusion *an alternative name for* **gene fusion**.

translation *in vitro* *an alternative name for* ***in vitro* translation**.

translation start site the mRNA codon at which the ribosome initiates the process of translation of the sequence into an amino acid sequence. The start codon is usually AUG (coding for methionine); in prokaryotes it may also be GUG (leucine). In prokaryotes, ribosome binding to the AUG is mediated by the **Shine–Dalgarno sequence**. In eukaryotes, recognition of the AUG is mediated by the **Kozak sequence**, which the 40S ribosomal subunit locates by scanning the message starting from the 5′ end.

translocase a system catalysing translocation of a substrate across an osmotic barrier. *See* **EF-G**, **translocator**.

translocation a vectorial transfer process, e.g. of a solute across a membrane. *See also* **chromosomal translocation**. **—translocational** *adj.*

translocator *or* **porter 1** a system catalysing a secondary translocation reaction, i.e. one not involving primary bond exchanges between different pairs of chemical groups or the donation and acceptance of electrons. **2** any molecular group that is attached to a substrate during transport of the latter across a membrane.

translocon a translocation complex that is the specific site of protein translocation across the endoplasmic reticulum. It involves the **signal recognition particle receptor**. The component proteins, called **translocon-associated proteins** (*abbr*.: TRAP), may be involved in ensuring retention in the endoplasmic reticulum of resident proteins. TRAP proteins form a heterotetramer of α, β, γ, and δ subunits.

translucent transmitting light (or other radiation) with some scattering or diffusion. Consequently, objects cannot be clearly distinguished through translucent materials. *Compare* **transparent**. —**translucence** *or* **translucency** *n.*

transmembrane domain *abbr*.: TM domain; a region of a protein sequence that traverses a membrane. For alpha-helical structures this is normally a span of 20–25 residues; for beta-structures the span is generally shorter, typically ≈12 residues. Alpha-helical TM domains are often predicted by the presence of characteristic peaks and troughs in **hydropathy profiles**.

transmembrane protein any protein that traverses the membrane, especially the plasma membrane. For the different types, *see* **membrane protein**.

transmethylation the transfer of a methyl or methylene group, as frequently occurs in **one-carbon metabolism**. Methyltransferases are in sub-subclass EC 2.1.1, and enzymes concerned with one-carbon metabolism are in sub-subclass EC 2.1.2. *See also* **C_1 compound**, **folate coenzymes**, ***S*-adenosylmethionine**.

transmissible dementia *see* **prion**.

transmissible spongiform encephalopathy *abbr*.: TSE; *see* **spongiform encephalopathy**.

transmission 1 the act, process, or an instance of transmitting. **2** the proportion of radiant energy that is transmitted perpendicularly through a substance or solution; *compare* **transmittance**. **3** the delivery of a nerve stimulus across a **synapse**, e.g. by a neurotransmitter.

transmission coefficient *(in nuclear physics)* the probability that a particle striking a nucleus penetrates it.

transmission electron microscope *abbr*.: TEM; *see* **electron microscope**.

transmission factor *an alternative name for* **transmittance**.

transmittance *or* **transmission factor 1** *(in chemistry) symbol*: T; the ratio I/I_0, where I_0 is the intensity of electromagnetic radiation falling on a body or substance and I the intensity after transmission through it. It is a dimensionless physical quantity. **2** *(in physics) symbol*: τ; the fraction of radiant energy that, having entered an absorbing substance, reaches its far boundary. It is given by

$$\tau = \Phi_{tr}/\Phi_0 = \exp(-\kappa cl),$$

where Φ_{tr} and Φ_0 are the radiant powers of the transmitted and incident radiation, κ is the molar napierian absorption coefficient, c the speed of light in the medium, and l the path length.

transmitter-gated channel *see* **ion channel**.

transparent transmitting light with little scattering or diffusion so that objects beyond the transparent material can be clearly distinguished. The term can be used in appropriate circumstances to indicate materials allowing the passage of other electromagnetic, particulate, or sonic radiation without disturbance. *Compare* **translucent**. —**transparency** *n.*

transpeptidase 1 *an alternative term for* **peptidyltransferase**. **2** the enzymic activity of a number of proteinases that catalyse, apart from hydrolysis of peptide links, the replacement of one terminal amino-acid residue in a peptide by another amino acid or other suitable molecule. **3** certain aminoacyltransferase enzymes, e.g. D-glutamyl transpeptidase, D-glutamyltransferase (EC 2.3.2.1), and glutamyl transpeptidase (i.e. **γ-glutamyltransferase**, EC 2.3.2.2).

transpeptidation a reaction catalysed by a **transpeptidase**.

transphosphoribosidase *see* **adenine phosphoribosyltransferase**.

transplantation antigen *an alternative term for* **histocompatibility antigen**.

transport the movement of a material from one place to another, especially the movement of substances around the body (e.g. in blood) or across a biological membrane, or of electrons along a series of carriers. This term implies a positive agency, compared with **passive diffusion**. *See also* **active transport**, **antiport**, **facilitated diffusion**, **symport**, **transport protein**.

transporter a membrane protein catalysing the passage of molecules across a membrane.

transport method *see* **transport process**.

transport number *an alternative term for* **transference number**.

transport piece *see* **secretory piece**.

transport process any process, such as sedimentation, diffusion, or electrophoresis, that is irreversible in the thermodynamic sense, the system being removed from a state of equilibrium. Such processes are of particular value in providing information about the dimensions, shapes, and masses of macromolecules.

transport protein a protein that is instrumental in transporting material, often in a specific manner, across a biological membrane, or within a biological fluid (e.g., blood). *See* **TC system**.

transposable element *another name for* **transposon**.

transposase an enzyme that is responsible for the transposition of **transposable elements** or **transposons**. Transposases are involved in site-specific DNA recombination required for transposition in bacteria and other organisms.

transpose 1 to alter the position of; to interchange or place in a different order. **2** *(in mathematics)* **a** to interchange the rows and columns of a **matrix** (def. 8). **b** the matrix resulting from interchanging the rows and columns of a given such matrix.

transposition 1 the process of transposing or the state of being transposed. **2** something that has been transposed; especially a segment of a chromosome or a piece of a DNA molecule.

transposition sequence *an alternative name for* **translocation sequence**.

transposon *or* **transposable element** a specific DNA sequence that is transferred from one **replicon** to another. Transposons were first identified as a result of work on **transposable elements** and also as spontaneous insertions in bacterial operons. The simplest are referred to as **insertion sequences**, being designated IS followed by a number related to the sequence in which they were identified, preceded by an indication of the site of insertion followed by a double colon (thus λ::IS1 indicates an IS1 element inserted into phage lambda). Each transposon is flanked by repeated sequences, due to short sequences copied from the original gene called **target repeats** or **direct repeats**, and also due to short inverted repeats that are a property of the insert. More complex transposons, called **composite transposons**, may have a central portion having a variety of markers, and flanked by IS elements that are responsible for identifying the transposon for transposition. These are designated Tn followed by a number. In eukaryotes, transposons constitute much of the **repetitive sequences** in the genome, with up to a few hundred repeat copies. They are flanked by terminal inverted sequences; the terminal sequences in each strand characteristically represent the complementary bases of the inverted sequence, i.e. TCAG......CGTA. Some transposons move physically from one site to another, while others are replicated, with one copy remaining at the original site and a duplicate inserting elsewhere. Both mechanisms involve a **transposase** enzyme; the former also requires a **resolvase** enzyme.

transthyretin a thyroid-binding protein occurring in the bloodstream, and having an unusual structure. The molecule is a homotetramer, each monomer comprising two four-stranded β-sheets, and having the shape of a prolate ellipsoid. Two of the monomers dimerize, and the dimers themselves dimerize to form a structure with an internal channel. Defects in transthyretin cause various forms of amyloidosis and hyperthyroxinemia.

trans-translation the transfer of a nascent polypeptide from a stalled bacterial ribosome onto a **tmRNA** followed by translation of the open reading frame (ORF) of the tmRNA.

transudate any fluid, with its solutes, that has passed through a membrane or through the interstices of a system.

transude to pass or be passed through a membrane or the interstices of a system as a **transudate**. —**transudation** *n.*

transverse relaxation a process in magnetic resonance spectroscopy, such as EPR and NMR, that describes the decay of transverse (x,y) magnetization. The characteristic spin-spin relaxation time is normally given the symbol T_2.

transversion a type of mutation of DNA involving the insertion of a purine in place of a pyrimidine, or vice versa. *Compare* **transition**.

***trans*-zeatin-producing protein** an isopentenyl transferase (dimethylallyl transferase) of sub-subclass EC 2.5.1. It introduces the isopentenyl moiety (2-methylbut-2-en-1-ol group) into zeatin.

TRAP *abbr. for* **1** translocon-associated protein; *see* **translocon**. **2** thyroid-hormone receptor-associated protein; a multiprotein complex of human cells that is associated with ligand-bound thyroid hormone receptor. It has an almost identical subunit composition to that of **SMCC**. It is the equivalent of the yeast transcriptional coactivator mediator.

trap hypothesis **1** a mechanism for the binding of proteinases by **α_2-macroglobulin** (α_2M). It proposes that, when α_2M interacts with a proteinase, hydrolysis of one or more peptide bonds in its **bait region** occurs, whereupon α_2M undergoes a conformational change that entraps the proteinase molecule, thus hindering reaction between the proteinase and other large substrate molecules. **2** *see* **methyltetrahydrofolate trap hypothesis**.

TRASH domain *abbr. for* trafficking, resistance, and sensing heavy metals domain; a well-preserved protein-sequence motif (≈38 residues) that contains three cysteine residues and is predicted to form a treble-clef finger (three or four beta strands with a C-terminal alpha helix) for metal coordination. It is present in many prokaryotic and several vertebrate proteins, alone or with other motifs.

Trasylol *a proprietary name for* **aprotinin**.

TRE *abbr. for* **1** TPA response element, a response element for phorbol esters. **2** **thyroid response element**. *See* **response element**.

Treacher Collins syndrome an autosomal dominant disorder of craniofacial development caused by mutation of the ‘treacle’ gene *TCOF1* (locus 5q32-q33.1). The treacle gene product is a nucleolar phospoprotein that participates in the 2′-O-methylation of pre-rRNA. [After Edward Treacher Collins (1862–1919), British ophthalmologist.]

tree length the total number of steps required to map a data set onto a phylogenetic tree, or the sum of the estimated or actual branch lengths in a tree.

trefoil domain *an alternative name for* **P domain**.

trefoil factor (*abbr*.: TFF) *or* **trefoil peptide** a family of abundant, highly stable and conserved polypeptides (≈60 amino acids long) secreted mainly by the mammalian gastrointestinal mucosa. Each member contains six conserved cysteine residues, predicted to form three intrachain loops (*see* **P domain**). There are three species in human: **p52** (52 amino acids), which is produced by gastric fundus and is highly expressed in cancers and around ulcerative disease of the upper intestinal tract; **SP** (spasmolytic polypeptide); and **ITF** (intestinal trefoil factor), which is secreted by goblet cells of musosa of intestine and colon especially at sites of injury, inflammation, or dysplasia. They are thought to be involved in repair of mucosal damage.

trefoil motif *an alternative name for* **P domain**.

trehalose *α*-D-glucopyranosyl-*α*-D-glucopyranoside; *α*,*α*-trehalose; a nonreducing disaccharide, *also known as* **mushroom sugar** *or* **mycose**, that acts as a reserve carbohydrate in certain fungi (especially yeasts), algae, and lichens. It is cleaved by trehalase but not by most other *α*-glucosidases. It is a component of **cord factors**, which are a mixture of trehalose 6,6′-mycolates (*see* **mycolic acid**). *α*-D-Glucopyranosyl-*β*-D-glucopyranoside (*α*,*β*-trehalose) and *β*-D-glucopyranosyl-*β*-D-glucopyranoside (*β*,*β*-trehalose) occur naturally, but only very rarely. The carbohydrate is a **compatible solute** that acts as a cryoprotectant in many microorganisms, and is used industrially as a preservative in foods and pharmaceuticals.

TrEMBL *abbr. for* translated EMBL; *see* **sequence database**.

tremerogen any of a group of oligopeptides that contain non-amino-acid components and are the sex hormones of the jelly fungi. They induce formation of a conjugation tube in compatible cell types. They may contain a farnesyl group bound to cysteine.

Tresyl *proprietary name* indicating the 2,2,2-trifluoroethane sulfonyl group; Tresyl-activated Sepharose can be used in the preparation of affinity gels, the sulfonyl groups being readily displaceable by amines, thiols, phenolic groups, or imidazole, which remain bound to the gel as the stationary component; e.g.

$$\text{support–O–}SO_2\text{–}CH_2\text{–}CF_3 + RSH =$$
$$\text{support–S–R} + HOSO_2\text{–}CH_2\text{–}CF_3.$$



trehalose

tretinoin *a WHO-approved nonproprietary name for* **retinoic acid**, especially for pharmacological use.

TRF *abbr. for* **1** thyrotropin-releasing factor; i.e. **thyrotropin-releasing hormone**. **2** T-cell-replacing factor; *see* **interleukin 5**. **3** telomeric repeat-binding factor. *See* **TEP-1**.

TRF-III *or* **TRF-m** *see* **interleukin 1**.

TRH *abbr. for* thyrotropin-releasing hormone.

tri+ *comb. form* **1** denoting three, threefold, thrice, every third; *see also* **tris+**. **2** *(in chemical nomenclature)* (*distinguish from* **tris+** (def. 2)) **a** indicating the presence in a molecular entity of three identical specified unsubstituted groups, e.g. trichloroethylene, trimethylamine. **b** indicating the presence in a molecular entity of three identical oxoacid residues in linear anhydride linkage; e.g. adenosine 5′-triphosphate.

triac *(informal) abbr. for* 3,3′,5-triiodothyroacetic acid, a catabolite of **thyroxine**.



triaconta+ *or (before a vowel)* **triacont+** *comb. form* denoting thirty or thirty times.

triacontanoic acid melissic acid; a 30-carbon straight-chain aliphatic acid; m.p. 93.6°C (methyl ester 71.5°C).

triacontapeptide a 30-residue peptide.

triacylglycerol *or (formerly)* **triglyceride** any triester of glycerol; the three fatty acids may all be the same, or differ in any permutation. Triacylglycerols are important components of plant oils, animal fats, and animal plasma lipoproteins. The degree of unsaturation of the component fatty acids determines the melting point: plant oils, which typically contain a high percentage of (poly)unsaturated fatty acids, are liquid, while animal fats, being more highly saturated, are solid or semisolid. *See also* **lipoprotein** and individual plant oils and animal fats.

triacylglycerol lipase EC 3.1.1.3; *systematic name*: triacylglycerol acylhydrolase; *other names*: lipase; triglyceride lipase; tributyrase. An enzyme that catalyses the reaction:

$$\text{triacylglycerol} + H_2O = \text{diacylglycerol} + \text{fatty-acid anion}.$$

There are various types ranging from those found in microorganisms to those such as **pancreatic lipase**, and the hormone-sensitive lipase of mammalian adipose tissue. That from the yeast *Geotrichum candidum* is a 544-amino-acid globulin with mainly alpha helix and turns; it contains one modified glutamine residue (pyrrolidone carboxylic acid).

triad a group of three; e.g. three amino acid residues can constitute a catalytic triad.

triadin a major membrane glycoprotein of the sarcoplasmic reticulum triad junction of skeletal and cardiac muscle. The luminal domain has a highly conserved region, and can bind both the ryanodine receptor and calsequestrin.

+triaose *suffix* used in nomenclature to indicate a molecule containing an oligosaccharide moiety composed of three sugar residues (which may be the same or different), as in gangliotriaose. *Distinguish from* **triose**.

triazine-dye affinity chromatography a type of **dye-ligand chromatography** in which the coupled dye is a triazinyl compound. It is not **affinity chromatography** in the original sense.

Triazol reagent a proprietary reagent used for the extraction of RNA from tissues.

tribbles a protein of *Drosophila* that inhibits mitosis in early development by binding to String (a Cdc25 homologue) and promoting its ubiquitination and degradation by proteasomes. It contains a truncated kinase motif, but lacks an ATP-binding site and *in vitro* kinase activity. The mammalian homologues TRB1, 2, and 3 strongly resemble tribbles. *See* **NIPK**.

tributyltin chlorotributylstannane; tri-N-butyltin chloride, $SnBu_3$; an organometallic compound, used primarily as a biocide in antifouling paints. It is extremely toxic to aquatic life and causes severe reproductive effects in aquatic organisms.

TRiC *see* **TCP-I**.

tricaprin *a trivial name for* **tridecanoin**, the triacylglycerol containing three caproyl (decanoyl) residues. *See also* **tricaproin**, **tricaprylin**.

tricaproin *a trivial name for* **trihexanoin**, the triacylglycerol containing three capric (hexanoic) ester residues. *See also* **tricaprin**, **tricaprylin**.

tricaprylin *a trival name for* **trioctanoin**, the triacylglycerol containing three caprylic (octanoic) ester residues. *See also* **tricaprin**, **tricaproin**.

tricarboxylic acid *abbr.*: TCA; any organic compound having three carboxylic-acid groups. The name often has the connotation of relationship with **citric acid**, as in the **tricarboxylic-acid cycle**.

tricarboxylic-acid cycle (*abbr.*: TCA cycle) *or* **citric-acid cycle** *or* **Krebs cycle** a nearly universal metabolic pathway in which the acetyl group of acetyl coenzyme A is effectively oxidized to two CO_2 and four pairs of electrons are transferred to coenzymes. The acetyl group combines with oxaloacetate to form citrate, which undergoes successive transformations to isocitrate, 2-oxoglutarate, succinyl-CoA, succinate, fumarate, malate, and oxaloacetate again, thus completing the cycle. In eukaryotes the tricarboxylic acid is confined to the mitochondria. *See also* **glyoxylate cycle**.

trichloroacetic acid *abbr.*: TCA; Cl_3CCOOH; an organic acid widely used for the precipitation of protein from tissue and other cell extracts. A final concentration of 3–9% (w/w) is normally used. TCA can be extracted into diethyl ether.

trichloroethyl alcohol 2,2,2-trichloroethanol; an active metabolite of chloral hydrate with CNS depressant actions.

trichohyalin a structural protein produced and retained in cells of the inner root sheath and medulla of the hair follicle. In the sheep, 75% of its amino acids are glutamate or glutamine, arginine or lysine; the gene is also expressed in epithelia, hoof, and rumen. Trichohyalin associates in regular arrays with keratin intermediate filaments.

trichostatin A an antifungal antibiotic from *Streptomyces platensis*. It is a reversible inhibitor of histone deacetylase.

trichothiodystrophy a syndrome of neurological dysfunction, premature ageing, photosensitivity, and brittle hair and nails. It is caused by a defect in **nucleotide excision repair** as a result of mutations in the xeroderma pigmentosum complementation proteins XPB (782 amino acids) and XPD (760 amino acids). These are DNA helicases, the largest subunits of transcription factor TFIIH, and essential for transcription initiation.

tricine *or* **TRICINE** *trivial name for N*-tris[(hydroxymethyl)methyl]-glycine; *N*-[2-hydroxy-1,1-bis(hydroxymethyl)ethyl]glycine; a **Good buffer substance**; p*K* (20°C) = 8.15.



tricorn protease a protease (1071 amino acids) with trypsin-like specificity that is abundant, with proteasomes, in archaebacteria such as *Thermoplasma acidophilum*. It forms a homohexameric toriid that resembles a tricorn hat, and cleaves oligopeptides produced by proteasomes into di-, tri-, and tetrapeptides. Aminopeptidases with different specificities are usually associated with it.

tricosa+ *or (before a vowel)* **tricos+** *comb. form* denoting twenty-three or twenty-three times.

tricosapeptide a 23-residue peptide.

trideca+ *or (before a vowel)* **tridec+** denoting thirteen or thirteen times.

tridentate 1 having three teeth or toothlike projections. **2** (of a **ligand**) chelating a metal ion by means of three donor atoms.

triene any alkatriene or substituted alkatriene.

+triene(+) *or (before a vowel)* **+trien+** *(in chemical nomenclature) infix or suffix* in systematic names denoting the presence in a molecular structure of an unsaturated aliphatic hydrocarbon chain containing three (conjugated or unconjugated) double bonds. The position of each double bond may be indicated by a locant for its lowest numbered carbon atom; e.g. cycloheptatriene, icosa-8,11,14-trienoic acid.

trienoic indicating a compound having a carboxylic-acid group and an aliphatic chain with three double bonds.

trienoyl indicating the acyl group of a trienoic acid.

triflavin a **disintegrin** from the snake *Trimeresurus flavoviridis*, containing an Arg-Gly-Asp (**RGD**) motif, that inhibits fibrinogen interaction with platelet receptors, and thereby inhibits platelet aggregation.

trifluoperazine 10-[3-(4-methyl-1-piperazinyl)propyl]-2-(trifluoromethyl)-10*H*-phenothiazine; an antagonist with high affinity for D_2 **dopamine receptors**. It is used in the treatment of manic and schizophrenic psychoses and as an inhibitor of **calmodulin** action. *One proprietary name*: Stelazine (dihydrochloride).



trifluoroacetic acid *abbr.*: THA; CF_3COOH; a strong organic acid used: (1) as a catalyst in organic synthesis; (2) to cleave Cbz– and tBoc– groups from protected amino acids; and (3) as the anhydride, to prepare trifluoroacetyl derivatives for the protection of alcohols and amines, and as volatile derivatives for gas–liquid chromatography.

trifunctional protein an enzyme protein complex, present on the matrix side of the inner mitochondrial membrane, that has long-chain 2-enoyl-CoA hydratase, long-chain 3-hydroxyacyl-CoA dehydrogenase, and long-chain 3-ketoacyl-CoA thiolase activities. That from rat liver consists of four α subunits (79 kDa), which bear the first two aforementioned activities, and four β subunits (51 kDa), which bear the third activity. Deficiency is associated with massive excretion of long-chain 3-hydroxycarboxylic acids. In **type 1 deficiency**, probably a defect of the α subunits, only the dehydrogenase activity is lacking. In **type 2 deficiency**, probably a defect of β subunits, all three activities are lacking.

trigger **1** to induce (often rapidly) into activity. **2** a mechanism or agent that brings about such an action. The term is commonly used in connection with membrane receptor activation and signal transduction, as in trigger mechanism.

trigger factor a 48 kDa protein of eubacteria that binds ribosomes in 1:1 stoichiometry, and also binds nascent ≈57-residue polypeptides by hydrophobic interaction. It dissociates from the nascent chain after this is released from the ribosome. It has **peptidylprolyl isomerase** activity but binds nascent chains independently of their proline content. *See* **NAC**.

triglyceride *a former name for* **triacylglycerol**; this usage is discouraged because 'triglyceride' is properly a generic term for compounds having three glyceryl residues (e.g. **cardiolipin**).

trigonelline nicotinic acid *N*-methylbetaine; 3-carboxy-1-methylpyridium inner salt; a metabolite of nicotinic acid. It is excreted in the urine after the consumption of relatively large amounts of nicotinic acid. It is also produced in alfalfa root exudates, where it induces *nod* genes in some *Rhizobium* species.

trihydric (of a chemical compound) containing three hydroxyl groups per molecule; trihydroxy; used especially of alcohols.

triiodothyronine *abbr.*: T_3; 3,3,5-triiodo-L-thyronine; one of the hormones secreted by the thyroid gland. Plasma levels of T_3 are much lower than those of **thyroxine** (T_4) (20- to 50-fold), but the physiological activity of T_3 is higher. Much of T_4 is converted to T_3 within cells. T_3 binds to a **thyroid-hormone receptor**, which binds to **thyroid response element**, a transcription-regulatory element. *See also* **thyroglobulin**.



trilaurin a triacylglycerol in which all the fatty-acyl moieties are **lauroyl** (dodecanoyl).

trimer a molecular complex having three components or subunits. If these are identical, it is referred to as a **homotrimer**; if any one is different from any other, it is called a **heterotrimer**. **—trimeric** *adj.*

trimethoprim 2,4-diamino-5-(3,4,5-trimethoxybenzyl)pyrimidine; a specific inhibitor of formylation and a competitive inhibitor of **dihydrofolate reductase**. The trimethoprim resistance gene can be used as a selectable marker for cloning vectors in animals or plants. *See also* **sulfamethoxazole**.



trimethylaminuria *see* **fish-odour syndrome**.

trimyristin a triacylglycerol in which all the fatty-acyl moieties are **myristoyl** (tetradecanoyl).

trinactin a neutral macrotetralide antibiotic with an action similar to that of **nonactin**.

trinitroglycerin glyceryl trinitrate; trinitroglycerol; the nitrate moiety is metabolized to nitrite and, subsequently, to **nitric oxide** and nitrosothiol, which activate guanylate cyclase. The resulting increase in cyclic GMP synthesis may explain the potent vasodilator effects of this and similar organic nitrates.

trinor+ *prefix (in a trivial name of a compound)* indicating replacement of three methyl groups by hydrogen. *See also* **nor+**.

trinucleotide repeat an increase in copy number of a normally polymorphic triplet. Some genetic disorders, e.g. **fragile X syndrome**, result from this.

triol any aliphatic chain having three hydroxyl groups.

triolein a triacylglycerol in which all the fatty-acyl moieties are **oleoyl** (*cis*-9-octadecenoyl). *See also* **triolein breath-test**.

triolein breath-test a test for intestinal malabsorption of fat. When ^{14}C-labelled triacylglycerol (10 μCi) is administered by mouth, a proportion of the ^{14}C will be breathed out as $^{14}CO_2$, which is trapped in a solution of hyamine carbonate for scintillation counting.

triose **1** any monosaccharide having a chain of three carbon atoms in the molecule, i.e. the chiral enantiomers D- and L-**glyceraldehyde**, and their achiral constitutional isomer **glycerone**. **2** trisaccharide; used as a stem name for any oligosaccharide consisting of three residues of the same sugar in a single type of linkage, as in maltotriose. *Distinguish from* **+triaose**.

triose phosphate D-glyceraldehyde 3-phosphate, glycerone phosphate, or a mixture thereof. These two compounds are interconvertible by the enzyme **triose-phosphate isomerase**.

triosephosphate dehydrogenase (NADP$^+$) *see* **glyceraldehyde-3-phosphate dehydrogenase (NADP$^+$) (phosphorylating)**.

triose-phosphate isomerase *abbr.*: TIM; EC 5.3.1.1; *systematic name*: D-glyceraldehyde-3-phosphate ketol-isomerase; *other names*: triosephosphate mutase; phosphotriose isomerase. The sugar **isomerase** enzyme that is important in the glycolytic pathway, and catalyses the aldose–ketose isomerization of the two **triose phosphates**, i.e. the reaction:

D-glyceraldehyde 3-phosphate = glycerone phosphate.

trioxsalen 2,5,9-trimethyl-7*H*-furo[3,2-*g*][*1*]-benzopyran-7-one; 4,5′,8-trimethylpsoralen (*abbr.*: TMP); a pigmentation agent (photosensitizer). *See also* **psoralen**.

tripalmitin a triacylglycerol in which all the fatty-acyl moieties are **palmitoyl** (hexadecanoyl).

tripeptide a three-residue peptide.

triphenylmethyl group *abbr.*: trityl; a group used in chemical syntheses to protect nitrogen, sulfur, and, particularly, oxygen functions as their trityl derivatives. It is stable under many conditions, and readily removed by mild acid. It can be introduced by reagents such as triphenylmethyl chloride.

triphosphate **1** the pentavalent ion, $P_3O_{10}^{5-}$, derived from triphosphoric acid, decaoxotriphosphoric(V) acid, $(HO)_2PO–O–PO(OH)–O–PO(OH)_2$ (an acid not known in the free state). **2** any mixture of the anions of triphosphoric acid. **3** any (partial or full) salt or ester of triphosphoric acid. **4** any organic compound containing three phosphoric residues linked linearly by oxygen atoms. **5** name of the univalent group $–O–PO(OH)–O–PO(OH)–O–PO(OH)_2$ (irrespective of its state of ionization). **6** *(formerly)* any organic compound containing three independent phosphoric residues attached to different parts of the molecule; now incorrect, use **trisphosphate**.

triphospho+ **1** *prefix* to a chemical name indicating the presence in ester linkage of a triphosphoric residue. **2** *(formerly) prefix* to a chemical name indicating the presence of three independent phosphoric residues in ester linkages; now incorrect, use **trisphospho+**.

triphosphoinositide *abbr.*: TPI; *a former name for* **phosphatidylinositol 4,5-bisphosphate** (*symbol*: PtdIns-4,5-P_2). Current nomenclature requires bisphosphate, trisphosphate, etc. for the substituent phosphates on the inositol moiety. Other phosphatidylinositol bisphosphates are known, e.g. PtdIns-phosphatidylinositol 3,4-biphosphate.

triphosphopyridine nucleotide (oxidized) *abbr.*: TPN$^+$; *an obsolete name for* **nicotinamide-adenine dinucleotide phosphate**.

triphosphopyridine nucleotide (reduced) *abbr.*: TPNH; *an obsolete name for* **nicotinamide-adenine dinucleotide phosphate (reduced)**.

triphosphoric *symbol*: *PPP or* (in the one-letter convention for nucleotides) ppp; *general name for* a residue of triphosphoric acid, $(HO)_2PO–O–PO(OH)–O–PO(OH)_2$, whether singly or multiply attached through oxygen to other groups and whether or not any residual hydroxyl groups are dissociated.

triple bolus test *see* **combined test of pituitary function**.

triple helix **1** (*in proteins*) a superhelically coiled arrangement of three polypeptide chains, e.g. as in **tropocollagen**. **2** *or (sometimes)* **triplex** *see* **triplex DNA**.

triple membrane *see* **unit membrane**.

triple point the point on a phase diagram at which three phases may coexist.

triplet 1 *(in molecular biology)* any sequence of three purine and/or pyrimidine bases in nucleic acids that specifies a particular amino acid. It is synonymous with **codon** in mRNA or **anticodon** in DNA or tRNA. *See also* **synonym triplet**. **2** a collection of three of a kind. **3** any one of three offspring born from a single pregnancy.

triplet code the **genetic code**, which is based on **triplets** (def. 1) of purine and pyrimidine bases.

triplet repeat any stretch of DNA that has the same three nucleotides (triplet) repeated in tandem fashion.

triplet repeat disorder a genetic disease resulting from the expansion of triplet repeats, such as Huntington's disease (CAG), fragile X syndrome (CCG), and myotonic dystrophy (CTG).

triplex DNA a three-stranded structure formed by duplex DNA in association with an oligonucleotide, when purine or pyrimidine bases occupy the major groove of the DNA double helix adopting **Hoogsteen base pairing** with the Watson–Crick base pairs. Triplex DNA may be involved as an intermediate in **crossing over**. *See also* **tetraplex DNA**.

triploid 1 describing a cell, tissue, or organism having three times the haploid (monoploid) number of chromosomes. **2** such a cell, tissue, or organism. —**triploidy** *n.*

TRI reagent a proprietary reagent formulated to facilitate the extraction of RNA, DNA, and protein from tissues.

tris+ *prefix* **1** denoting three times, thrice, tripled; *see also* **tri+** (def. 1). **2** *(in chemical nomenclature)* (*distinguish from* **tri+** (def. 2)) **a** indicating the presence in a molecular entity of three identical specified groups each substituted in the same way; e.g. tris(2-hydroxyethyl)amine. **b** indicating the presence at separate positions in a molecular entity of three identical inorganic oxoacid residues; e.g. inositol 1,4,5-trisphosphate.

Tris *or* **TRIS** *or* **THAM** tris(hydroxymethyl)aminomethane; 2-amino-2-hydroxymethyl-1,3-propanediol; a compound widely used as a biological buffer substance in the pH range 7–9; pK_a (20°C) = 8.3; pK_a (37°C) = 7.82.



trisaccharide an **oligosaccharide** with three **monosaccharide** units.

Trisacryl 1 *a proprietary name for* *N*-acryloyl-2-amino-2-hydroxymethyl-1,3-propanediol; $CH_2=CH–CO–NH– C(CH_2OH)_3$; a compound used in the manufacture, by copolymerization with a cross-linking agent such as *N,N′*-diallyl L-tartardiamide (*abbr.*: DATD) or *N,N′*-methylenebisacrylamide, of a range of strongly hydrophilic artificial support materials of controlled porosity that are useful for gel-permeation chromatography. Copolymerization with a cationic or anionic derivative as a third component yields support materials of utility in ion-exchange chromatography. Such materials are thermally, chemically, and biologically stable, and resistant to high pressures. **2** *as modifier* describing a range, or any member of a range, of such chromatographic support materials; e.g. Trisacryl polymers, Trisacryl ion-exchangers, Trisacryl gels, Trisacryl GF05, DEAE–Trisacryl M.



triskelion a hexamer of **clathrin** molecules, composed of three heavy chains and three light chains. In the **electron microscope**, triskelions appear to have three bent arms each linked into a central point. [From triskele, a symbolic figure consisting of three legs radiating from a common centre.]

trisomic 1 describing a cell, tissue, or organism having three copies of one or more chromosome(s) in an otherwise diploid chromosome set. In humans, trisomy 21 (i.e. presence of three copies of chromosome 21) is asssociated with **Down's syndrome**. **2** such a cell, tissue, or organism. —**trisomy** *n.*

trisphosphate any compound containing three independent phosphoric residues in ester linkages, at positions indicated by locants; e.g. inositol 1,4,5-trisphosphate. *Compare* **triphosphate**.

trisphospho+ *prefix* to a chemical name indicating the presence of three independent phosphoric residues in ester linkages, at positions indicated by locants. *Compare* **triphospho+**.

tristearin a triacylglycerol in which all the fatty-acyl moieties are **stearoyl** (octadecanoyl).

trithorax one of a group of proteins in *Drosophila* that regulate the expression patterns of many developmental genes. Trithorax group proteins are involved in countering chromatin-based gene silencing to maintain gene activity, and enable established patterns of gene expression to be transmitted over multiple rounds of cell division. *Compare* **polycomb**.

tritiate to combine or label with **tritium**; to replace one or more atoms of hydrogen with tritium. Tritium may be introduced into specific sites by chemical synthesis but ^{3}H-labelled steroids are prepared by the reduction of unsaturated precursors with $^3H_2$, the number of ^{3}H atoms introduced depending upon the degree of unsaturation of the precursor and the catalyst used. Biosynthesis is rarely used for ^{3}H-labelling since intramolecular migration of ^{3}H atoms is often caused by enzymes.

tritin a type I **ribosome-inactivating protein** from wheat.

tritium the radioactive isotope of hydrogen, $^3_1$H (i.e. the nucleus contains two neutrons and one proton). It decays to produce β^- particles of low energy (0.018 MeV); half-life 12.26 years. *Compare* **deuterium**, **protium**.

tritium nuclear magnetic resonance spectroscopy *abbr.*: tritium NMR spectroscopy *or* TNMR spectroscopy; the application of **nuclear magnetic resonance spectroscopy** to determine the positions and extents of tritium substitution in substances (generally of known structure) that have been labelled with tritium (^{3}H). The technique depends upon an equality of the displacements of the resonance frequencies (chemical shifts) of tritium and protium (^{1}H) nuclei in corresponding environments relative to those occurring with the tritiated and nontritiated forms, respectively, of a reference substance. The method is quick, nondestructive, and applicable to very small amounts of material. It is thus particularly useful for determining the pattern of labelling in substances that are costly, complex in structure, and/or unstable. The technique is also used to follow the chemical and steric course of biochemical reaction sequences.

triton 1 *(in chemistry) symbol*: $^3H^+$; the cation derived from an atom of **tritium**; a **hydron** of nucleon number 3. **2** *(in nuclear physics) symbol*: t; a particle having a charge equal and opposite to that of an electron and having a mass of 3.0155 Da.

Triton *the proprietary name for* any of a series of polyoxyethylene ethers of certain alkylphenols that are surfactants and classed as nonionic detergents. Those used most commonly are based on the formula *tert*-octyl-$C_6H_4–[OCH_2CH_2]_xOH$; e.g. in Triton X-45, $x \approx 5$; in Triton X-100, $x = 9$ or 10 (aggregation number 100–155, CMC 0.2–0.9 mM); in Triton X-405, $x \approx 40$; Triton CF is a benzyl-polyoxyethylene *tert*-octylphenyl ether; Triton N-101 is a polyoxyethylene nonylphenyl ether ($C_9H_{19}–C_6H_4–[OCH_2CH_2]_x$ OH), with $x = 9$ or 10.

tritosome a **lysosome** that is loaded with Triton. Tritosomes have an isopycnic density in sucrose solution of about 1.14, and can thus be separated readily from other cell constituents.

tritriaconta+ *or (before a vowel)* **tritriacont+** *comb. form* denoting thirty-three or thirty-three times.

triturate 1 to rub or grind (solid material) to a very fine powder either dry or in a liquid. **2** a finely ground powder or an even mixture of finely ground powders, especially powdered drugs.

trituration **1** the act of triturating or the condition of being triturated; *see* **triturate** (def. 1). **2** the composing of a dental amalgam.

trityl *trivial name for* the **triphenylmethyl group**.

trivial name *(in chemical nomenclature)* a name of a chemical species that has no part of it used in a systematic sense; e.g. xanthophyll, urea. It generally has historical or colloquial origins, and refers to attributes such as appearance or source. It makes no pretension to describe molecular structure. The adjective 'trivial' has no perjorative meaning, numerous compounds of biochemical interest having approved or recommended trivial names. *Compare* **descriptive name**, **systematic name**.

trixenic *see* **synxenic**.

trk *abbr. for* tropomyosin receptor kinase; a protooncogene encoding a transmembrane tyrosine kinase receptor that is selectively expressed in certain neurons of neural crest origin, or, as its counterpart *trkB*, in cells of the neuroepithelium. It is required for high-affinity binding of nerve growth factor, and neurotrophins 3 and 4. It was discovered as the transforming factor of a colon carcinoma and was originally known as *onc*D. The oncogenic activity results from a genomic rearrangement that produces a hybrid protein consisting of part of a nonmuscle tropomyosin sequence and the transmembrane and cytoplasmic domains of Trk.

tRNA *abbr. for* transfer RNA.

T3 RNA polymerase an enzyme from bacteriophage T3 that will transcribe sequences downstream from the **T3 phage promoter** and is used for ***in vitro* transcription**.

T7 RNA polymerase an enzyme that will transcribe sequences downstream from the **T7 phage promoter** and is used for ***in vitro* transcription**.

Trojan horse inhibitor *see* **affinity label**.

Trojan peptide *an alternative name for* **penetratin**.

tropane 8-methyl-8-azabicyclo[3.2.1]octane; the basic ring system in tropane alkaloids.



+trope *suffix* denoting turning.

+troph *suffix* denoting an organism with a specified mode of nutrition, e.g. **autotroph**, **chemotroph**.

trophic of, or concerning, nourishment, nutrition. *Compare* **tropic** (def. 1).

+trophic *suffix* denoting nourishment, nutrition; e.g. organotrophic, saprotrophic. *See also* **+tropic**.

+trophin *noun suffix* denoting a substance having a **trophic** function. *See also* **+tropin**.

tropho+ *or (before a vowel)* **troph+** *comb. form* denoting food or nourishment.

trophoblast the outer part of the blastocyst stage of a mammalian conceptus. Its outermost layer consists of syncytial cells concerned with penetration and implantation into the uterine endometrium; these cells secrete extracellular hydrolases that facilitate movement of the blastocyst into the previously organized endometrial structure.

+trophy *noun suffix* **1** denoting food or nourishment. **2** denoting growth or size.

tropic **1** *or (sometimes, esp. Brit.)* **trophic** having a stimulating effect (especially of a hormone, etc.). **2** of or relating to a **tropism**.

+tropic *or (sometimes, esp. Brit.)* **+trophic** *suffix* denoting a stimulatory function; e.g. gonadotropic. *See also* **+trophic**, **+tropin**.

tropic acid α-phenyl-β-hydroxypropionic acid; (*S*)3-hydroxy-2-phenylpropanoic acid; a compound that occurs in ester form in **atropine** and other tropane alkaloids.

+tropin *or (sometimes, esp. Brit.)* **+trophin** *noun suffix* denoting a substance having a stimulatory function, especially a hormone produced by the adenohypophysis. *See also* **+trophin**.

tropine tropan-3α-ol; 2-hydroxytropane; *N*-methyl-8-azabicyclo[3.2.1]octan-3-ol; **atropine** is the ester with (±)-tropic acid. Tropine is a *meso* structure. The –OH group is *trans* to the CH_3N– group. In the geometrical isomer, **pseudotropine**, this relationship is *cis*.



tropinone *N*-methyl-8-azabicyclo[3.2.1]octan-3-one; the oxidation product of **tropine**.

tropism movement directed towards some positive stimulus, or away from some negative stimulus.

+tropism *noun suffix* denoting a specific type of **tropism** as indicated by the prefixed word.

tropocollagen *or* **soluble collagen** a rod-shaped molecule, 3000 Å long and 15 Å in diameter, consisting of two α1 and one α2 polypeptide chain, each of about 1000 amino-acid residues, of which about a third are glycine, and 21% are proline plus hydroxyproline; they also contain hydroxylysine. The three polypeptide chains wind around each other to form a superhelical cable, the chains of which are hydrogen-bonded to each other. Tropocollagen fibres spontaneously associate, with their N-terminal sequences overlapping C-terminal sequences of adjacent chains in a staggered array, to form **collagen** molecules. *Compare* **procollagen**. *See also* **registration peptide**.

tropolone 2-hydroxy-2,4,6-cycloheptatrien-1-one; a structure found in some mould metabolites and in **colchicine**.



tropomodulin a cytoskeletal tropomyosin-regulatory protein that binds to the end of erythrocyte tropomyosin and blocks its head-to-tail association along actin filaments; it does not bind to F actin. Its modulation of the spectrin–actin complex affects the viscoelastic properties of erythrocytes.

tropomyosin a protein found in smooth, skeletal and cardiac muscle. It comprises α and β subunits, and is bound to **actin**, forming a component of the **troponin** complex that regulates calcium-dependent binding of actin and myosin and, consequently, muscle contraction. Tropomyosin forms a characteristic coiled coil, with a prominent seven-residue periodicity. Different isoforms are produced by differential splicing: e.g., isoforms of α-tropomyosin differ in striated and smooth muscle.

tropomyosin kinase EC 2.7.1.132; an enzyme that catalyses the phosphorylation of tropomyosin to form *O*-phosphotropomyosin.

tropone 2,4,6-cycloheptatrien-1-one.



tropone

troponin *abbr.*: Tn; a central regulatory protein of striated muscle contraction, comprising three subunits: **troponin T** (Tn-T), which binds to **tropomyosin**; **troponin I** (Tn-I), which regulates actinomyosin ATPase; and **troponin C** (Tn-C), which binds Ca^{2+} and, with Ca^{2+} bound, abolishes the inhibition of the binding of myosin to actin filaments produced by the other two troponins.

+tropy *noun suffix* denoting turning.

TROSY *abbr. for t*ransverse *r*elaxation *o*ptimized *s*pectroscopy: a method in NMR spectroscopy that gives sharper peaks for proteins of high molecular mass.

trp a family of tryptophan biosynthetic genes in bacteria. The following examples of *trp* gene products are from *Escherichia coli.*

(1) TrpA and TrpB are the α and β subunits of tryptophan synthase (EC 4.2.1.20); it catalyses the formation of L-tryptophan from L-serine and 1-(indol-3-yl) glycerol 3-phosphate; glyceraldehyde 3-phosphate is also formed. The enzyme is a tetramer (α_2,β_2); the subunits have half-activities (α for aldol cleavage of indoleglycerol phosphate and β for tryptophan synthesis).

(2) TrpC is a monomeric bifunctional enzyme: the 'TrpF domain' is *N*-(5′-phosphoribosyl)anthranilate isomerase (EC 5.3.1.24); it catalyses the interconversion of *N*-5′-phosphoribosyl-anthranilate and 1-(2-carboxyphenylamino)-1-deoxy-D-ribulose 5-phosphate. The 'TrpC domain' is **indole-3-glycerol-phosphate synthase** (EC 4.1.1.48; *abbr.*: IGPS); it catalyses the decarboxylation of 1-(2-carboxyphenylamino)-1-deoxy-D-ribulose 5-phosphate to form 1-(indol-3-yl) glycerol 3-phosphate, CO$_2$, and H$_2$O.

(3) TrpE/G, **anthranilate synthase** (EC 4.1.3.27); it catalyses a reaction between chorismate and L-glutamine to form anthranilate, pyruvate, and L-glutamate. This enzyme is a tetramer with two molecules of component I (TrpE) and two of component II (TrpG). (4) TrpR, aporepressor (*trp* is co-repressor) for the operators of the *trp* operon, *trpR* itself, and *aroH*; a homodimer of known 3-D structure.

Trp *symbol for* a residue of the *α*-amino acid L-tryptophan (alternative to W).

Trp-2 tyrosinase-related protein 2; this is a product of the *tyrp- 2* gene. *See also* **slaty**.

TRP channel *abbr. for* transient receptor potential channel; any of a family of membrane ion channels, first characterized as *Drosophila* TRP, which is responsible for the depolarization of photoreceptor cells in response to light. Mammalian homologues belong in three classes: short TRP (*or* STRP), long TRP (*or* LTRP), and osm-9-like (*or* OTRP). **TRP channel 2** (*or* LTRPC2) is expressed in many human tissues including immunocytes, where it is heptahelical and has a long cytoplasmic tail. It is activated by adenosine diphosphoribose (ADPR) and by NAD (the precursor of ADPR), and is inhibited by ATP. It is a nonspecific cation channel that permits Ca^{2+} influx into cells and has ADPR pyrophosphatase activity. **LTRPC7** is widely expressed in mouse tissues and is an ion channel and protein kinase. The cold and menthol (CMR1) and the heat and capsaicin (TRPM8) receptors are also members of the TRP family.

true cholinesterase *an alternative name for* **acetylcholinesterase**.

true negative an entity that is not a true member of a data set and is not recognized by a discriminator for that data set. *Compare* **false negative**.

true positive a match that is recognized by a discriminator for a given data set and is a true member of that data set. *Compare* **false positive**.

truncate 1 to shorten by cutting. **2** to terminate prematurely. **—truncation** *n.*

truncated hemoglobin any of a family of small oxygen-binding heme proteins that are widely distributed in eubacteria and protozoa, and nearly ubiquitous in the plant kingdom. They are 20–40 residues shorter than nonvertebrate hemoglobins and are distinct from bacterial flavohemoglobins, plant symbiotic and nonsymbiotic hemoglobins, and animal hemoglobins. They consist of four alpha helices rather than the eight of animal hemoglobins.

Trypan Blue a blue dye that is water-soluble and possesses sulfate and amino groups, whose charge prevents it from penetrating the plasma membrane of healthy cells. Dead cells or cells with damaged membranes take it up, making it a useful stain for determining cell viability (*see* **dye-exclusion test**). It does, however, stain healthy macrophages.



trypanosomatid any protozoan of the order **Kinetoplastida**, which includes **trypanosomes** and other genera.

trypanosome any member of the genus *Trypanosoma* (order **Kinetoplastida**), comprising parasitic flagellate protozoans. Infection causes trypanosomiasis in a range of animals. In humans there are two main forms: African trypanosomiasis (or sleeping sickness), which is caused by *T. brucei* and transmitted by tsetse flies, and South American trypanosomiasis (or Chagas' disease), which is caused by *T. cruzi* and transmitted by insects such as the assassin bug. Invasion of the nervous system is more common with the African form than with the South American form, which mainly affects the heart.

trypanothione the oxidized form of N^1,N^6-bis(glutathionyl)spermidine, derived from the trypanosomatid *Crithidia fasciculata*, a parasite of insects. Members of the **Kinetoplastida** lack **glutathione reductase**, and **glutathione** is converted to the conjugate, trypanothione. *See also* **trypanothione reductase**.



trypanothione reductase EC 1.6.4.8; *systematic name*: NADPH:trypanothione oxidoreductase; an enzyme unique to **trypanosomatids**, and hence a potential chemotherapeutic target. It catalyses the reaction:

NADPH + trypanothione =
NADP$^+$ + reduced trypanothione;

FAD is a cofactor. *See also* **trypanothione**.

trypsin EC 3.4.21.4; a serine endopeptidase occurring in two forms, known as α and β trypsin. These result from proteolytic cleavage, β being formed directly from the precursor, **trypsinogen**, and α and other forms by further cleavage. Trypsin is of major importance in protein digestion in the small intestine, trypsinogen being a constituent of **pancreatic juice**. Trypsin is also widely used as a proteolytic agent experimentally, e.g. in protein sequencing. It preferentially cleaves at Arg-|-Xaa and Lys-|-Xaa. *See also* **trypsin inhibitor**.

trypsin inhibitor any naturally occurring substance that inhibits the activity of **trypsin**. *See* **pancreatic trypsin inhibitor, soybean trypsin inhibitor**.

trypsinize *or* **trypsinise** to treat something, especially intact cells or membrane preparations, with trypsin. Trypsinization is used to release cells from adhesion to tissue-culture plates, and to indicate domains of integral membrane proteins (unattacked bonds might indicate that they are shielded by inclusion within the membrane). **—trypsinization** *or* **trypsinisation** *n.*

trypsinogen the pancreatic **zymogen** precursor of **trypsin**. It is secreted in **pancreatic juice** and in the duodenum is cleaved by **enteropeptidase**, which cleaves the Lys^8-|-Ile^9 bond in trypsinogen, to yield β trypsin.

tryptamine *β*-3-indolylethylamine; 3-(2-aminoethyl)indole; 2- (1*H*-indol-3-yl)ethanamine; (C$_8$H$_6$N)CH$_2$–CH$_2$–NH$_2$; a biogenic amine, formed by enzymic decarboxylation of tryptophan. Of widespread occurrence in mammalian tissues, it is found also in plants, and is a product of microbial degradation of proteinaceous material.

tryptase EC 3.4.21.59; *other names*: mast cell tryptase; mast cell protease II; skin tryptase; lung tryptase; pituitary tryptase. An enzyme that cleaves Arg-|-Xaa, Lys-|-Xaa, but with more restricted specificity than **trypsin**. It is a trypsin-like serine endopeptidase released from the secretory granules upon mast-cell activation. Cytotoxic T-lymphocyte tryptase, or CTL tryptase, is **granzyme A**.

tryptic of, or relating to, trypsin; effected or produced by the action of trypsin; especially **tryptic digestion**, the partial hydrolysis of a protein by trypsin.

tryptophan *or (formerly)* **tryptophane** *the trivial name for* β-3-indolylalanine; α-amino-β-3-indolepropionic acid; 2-amino-3- (1*H*-indol-3-yl)propanoic acid; $(C_8H_6N)CH_2–CH(NH_2)–COOH$; a chiral α-amino acid. L-tryptophan (*symbol*: W *or* Trp), (*S*)-2-amino-3-(1*H*-indol-3-yl)propanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: UGA (only in mitochondria) or UGG. In mammals, it is an essential dietary amino acid, and is glycogenic. The peptide antibiotic, **tyrocidin** C, contains one residue per molecule of D-tryptophan (*symbol*: D-Trp *or* DTrp), (*R*)-2-amino-3-(1*H*-indol-3-yl)propanoic acid.



L-tryptophan

tryptophanal α-amino-β-3-indolepropionaldehyde; 2-amino-3-(1*H*-indol-3-yl)propanal; $(C_8H_6N)CH_2–CH(NH_2)–CHO$; the α-amino-aldehyde analogue of **tryptophan**.

tryptophanase **1** EC 4.1.99.1; *recommended name*: tryptophanase; *systematic name*: L-tryptophan indole-lyase (deaminating). An enzyme that catalyses a reaction between water and L-tryptophan to form indole, pyruvate, and NH_3. It is responsible for indole formation in *Escherichia coli* and other enteric bacteria and bacilli. The reaction is comparable to that of β-tyrosinase (*see* **tyrosinase** (def. 2)). **2** *an alternative name for* **tryptophan 2,3-dioxygenase**.

tryptophanate **1** tryptophan anion; the anion, $(C_8H_6N)CH_2–CH(NH_2)–COO^-$, derived from **tryptophan**. **2** any salt in which tryptophan is anionic. **3** any ester of tryptophan.

tryptophan 2,3-dioxygenase EC 1.13.11.11; *systematic name*: L-tryptophan:oxygen 2,3-oxidoreductase (decyclizing); *other names*: tryptophan pyrrolase; tryptophanase; tryptophan oxygenase; tryptamine 2,3-dioxygenase. An enzyme that catalyses a reaction between dioxygen and L-tryptophan to form L-formylkynurenine. It is a heme protein in mammalian liver, and it shows broad specificity towards tryptamine and other derivatives.

tryptophan 5-hydroxylase EC 1.14.16.4; *recommended name*: tryptophan 5-monooxygenase; *systematic name*: L-tryptophan, tetrahydrobiopterin:oxygen oxidoreductase (5-hydroxylating); *other name*: tryptophan oxygenase. An enzyme that catalyses a reaction between dioxygen, L-tryptophan, and tetrahydrobiopterin to form 5-hydroxy-L-tryptophan, dihydrobiopterin, and water. This is the rate-limiting enzyme in the biosynthesis of the neurotransmitter **serotonin** (**5-hydroxytryptamine**).

tryptophanium tryptophan cation; the cation, $(C_8H_6N)CH_2–CH(NH_3^+)–COOH$, derived from **tryptophan**.

tryptophan 2-monooxygenase EC 1.13.12.3; *systematic name*: L-tryptophan:oxygen 2-oxidoreductase (decarboxylating); *other name*: tryptophan oxygenase. An enzyme that catalyses a reaction between dioxygen and L-tryptophan to form indole-3-acetamide, CO_2, and water. This is the first step in **auxin** biosynthesis.

tryptophan 5-monooxygenase *the recommended name for* **tryptophan 5-hydroxylase**.

tryptophano the alkylamino group, $(C_8H_6N)CH_2–CH(COOH)–NH–$, derived from **tryptophan**.

tryptophanol 3-(2-amino-3-hydroxypropyl)indole; 2-amino-3-(1*H*-indol-3-yl)propanol; $(C_8H_6N)CH_2–CH(NH_2)–CH_2OH$; the α-amino-alcohol analogue of **tryptophan**.

tryptophan oxygenase *an alternative name for* **1** **tryptophan 2,3-dioxygenase**. **2** **tryptophan 2-monooxygenase**. **3** **tryptophan 5-hydroxylase**.

tryptophan pyrrolase *an alternative name for* **tryptophan 2,3-dioxygenase**.

tryptophan repressor *see* ***trp***.

tryptophan synthase *see* ***trp***.

tryptophan tryptophylquinone *abbr*.: TTQ; a quinoprotein cofactor of methylamine dehydrogenase, EC 1.4.99.3, an enzyme of methylotropic bacteria. TTQ consists of a tryptophanyl side-chain cross-linked to the tryptophyl 6,7-dione side-chain of a modified tryptophan residue.

tryptophyl the acyl group, $(C_8H_6N)CH_2–CH(NH_2)–CO–$, derived from **tryptophan**.

TSE *abbr. for* transmissible spongiform encephalopathy.

TSF *abbr. for* thymocyte-stimulating factor, i.e. **interleukin 2**.

TSH *abbr. for* thyroid-stimulating hormone.

TSS *abbr. for* transcription start site.

TSST-1 *abbr. for* toxic shock syndrome toxin-1.

T state *see* **T form**.

tTA *abbr. for* tetracycline regulated *trans*-activator. *See* **Tet-Off**.

TTP *abbr. for* **1** ribosylthymine triphosphate *or* ribothymidine triphosphate, *common names for* ribosylthymine 5′-triphosphate, ribothymidine 5′-triphosphate, 5′-ribothymidylyl triphosphate, thymine riboside 5′-triphosphate. **2** *(sometimes)* thymidine triphosphate. dTTP is recommended.

TTQ *abbr. for* tryptophan tryptophylquinone; a quinone cofactor produced by post-translational modification of two tryptophan residues in some quinoproteins.

TTSP *abbr. for* type II transmembrane serine protease; any of a class of single-pass transmembrane proteins that have an extracellular C-terminal region containing a serine protease domain. Other domains can also be present. Human examples include **corin** and **enteropeptidase**.

T tubule *abbr. for* transverse tubule; a type of tubule in a muscle fibre that arises as an invagination of the plasma membrane and penetrates the fibre, running mostly transversely among the fibrils and surrounding each of them with a ring. Each ring is shared by adjacent fibrils and the whole forms an intercommunicating system of tubules across the fibre. The function of these tubules is to pass the excitation signal from the muscle cell plasma membrane to the sarcomeres, ensuring rapid and synchronous activation. *See also* **sarcoplasmic reticulum**.

TTX *abbr. for* tetrodotoxin.

tuberin a protein that is widely expressed and shares a region of homology with GTPase-activating proteins. It forms a largely cytosolic complex with **hamartin**. It may be a tumour suppressor. Many mutations in the gene at 16p13.3 produce tuberous sclerosis type 2 (TSC2). The equivalent gene is inactive in the Eker rat and in the *gigas* mutant of *Drosophila*.

tuberous sclerosis an autosomal dominant multisystem disorder that frequently manifests as seizures, behavioural abnormalities, various skin lesions, and renal tumours and cysts. It is caused by mutations in **tuberin** and in **hamartin**.

tubocurarine (+)-tubocurarine is the active principle of **curare**; it is a nicotinic cholinergic receptor competitive antagonist, and is used as a muscle relaxant. It contains groups that are arranged in space in a rigid framework like the atoms of acetylcholine and are important in its action. It competes with acetylcholine at the neuromuscular junction and causes the endplate potential to fall dramatically.

tubulin a widely distributed globular protein, profilaments of which form the structural elements of a **microtubule**. It is a heterodimer of two chains, α and β, each ~50 kDa. The stable form of isolated tubulin is a dimer in which α–β pairing is believed to predominate; such a heterodimer is also the basic component of the microtubule. The dimer binds two molecules of GTP, one at an exchangeable site on the β chain and one at a non-exchangeable site on the α chain. The GTP is hydrolysed to GDP at the plus end more slowly than assembly of heterodimers, to give a GTP cap at that end. GDP–tubulin is disassembled more readily than GTP–tubulin, so the rate of GTP hydrolysis could regulate tubulin assembly. At least 6 isoforms are now known, designated α, β, γ, δ, ε, and ζ.

***α*-tubulin acetylase** *see* **tubulin *N*-acetyltransferase**.



(+)-tubocurarine

tubulin *N*-acetyltransferase EC 2.3.1.108; *other name*: α-tubulin acetylase; an enzyme that catalyses the reaction:

acetyl-CoA + α-tubulin L-lysine =

CoA + α-tubulin N^6-acetyl-L-lysine.

tubulinyl-Tyr carboxypeptidase EC 3.4.17.17; *other names*: carboxypeptidase-tubulin; soluble carboxypeptidase; an enzyme that catalyses the cleavage of the Glu-|-Tyr bond to release the C-terminal tyrosine residue from the native tubulin. It is inactive on carbobenzoxy-Glu-Tyr.

tuftelin *or* **enamelin** an acidic enamel protein of teeth, with a composition similar to tuft proteins. It is found in association with the crystal component, and secreted at a very early stage of enamel formation in vertebrate teeth.

tuftsin the tetrapeptide Thr-Lys-Pro-Arg, from **leukokinin** (leukophilic human IgG). It is present in the Fc fragment of IgG, binds to and stimulates the bactericidal, phagocytic, and tumoricidal activities of macrophages and granulocytes, and may also stimulate the migration of polymorphonuclear leukocytes. [After Tufts University, where it was discovered.]

tumble **1** to rotate in a plane vertical to the axis of rotation; 'head over heels'. Proteins and other macromolecules tumble in solution whereas integral membrane proteins rotate on an axis normal to the plane of the membrane but cannot tumble through the membrane surface. **2** in bacterial chemotaxis, to change direction by a rapid reversal of the direction of flagellar rotation, the bacterium then 'tumbling' in response to Brownian motion.

tumor *a variant spelling (esp. US) of* **tumour**.

tumorigenic describing a substance or treatment that has the tendency to cause the formation of a **tumour**.

tumour *or (esp. US)* **tumor** a mass of proliferating cells lacking, to varying degrees, normal growth control. Tumours may be benign, i.e. growing slowly, or malignant, i.e. growing aggressively, invading neighbouring tissues, and spreading to distant parts of the body by releasing cells into the bloodstream or lymph. These cells form secondary tumours (*see* **metastasis**). *See also* **adenoma**, **carcinoma**, **lymphoma**, **sarcoma**. —**tumorous** *or* **tumoral** *adj.*

tumour initiator any compound that causes the formation of a tumour.

tumour necrosis factor *abbr.*: TNF; either of two related proteins: TNF-α (*or* cachectin) is produced mainly by monocytes and macrophages, whereas TNF-β (*or* lymphotoxin) is produced by lymphoid cells. They show ≈30% sequence homology, bind to the same cell-surface receptors, and exist as homotrimers. They have a multiplicity of actions. In binding to their receptors, present on virtually all cells examined, they activate a large array of cellular genes and also multiple signal-transduction pathways, kinases, and transcription factors. Their genes are single-copy genes, closely linked within the MHC cluster. *See* **tumour necrosis factor** α; **tumour necrosis factor** β, **tumour necrosis factor receptor**.

tumour necrosis factor α (*abbr.*: TNF-α) *or (formerly)* **cachectin** a **cytokine** that is produced by macrophages, monocytes, endothelial cells, neutrophils, smooth muscle cells, activated lymphocytes, and astrocytes. It is a transmembrane glycoprotein and cytotoxin with a variety of functions, including the ability to mediate the expression of genes for growth factors, cytokines, transcription factors, and receptors. It can cause cytolysis of certain tumour cell lines, it has been implicated in the induction of cachexia (but *see* **cachectic factor**), it is a potent pyrogen, causing fever by direct action or by stimulation of interleukin 1 secretion, and it can stimulate cell proliferation and induce cell differentiation under certain conditions. The molecule is a homotrimer. *See also* **tumour necrosis factor**.

tumour necrosis factor β (*abbr.*: TNF-β) *or (formerly)* **lymphotoxin** a **cytokine** produced by T lymphocytes that is cytotoxic for a wide range of tumour cells. It binds to the same ligands as **tumour necrosis factor** α. *See also* **tumour necrosis factor**.

tumour necrosis factor receptor *abbr.*: TNF receptor; either of two distinct receptors for **tumour necrosis factor** (TNF), one of M_r 55 000 and the other of 75 000. The two types have related extracellular domains, based on cDNA sequencing, and these are also related to the extracellular domains of nerve growth factor receptor and some other cell-surface molecules. These form a receptor family characterized by four domains with regularly spaced cysteine residues; each has a single transmembrane domain; the intracellular domains show no significant homologies. Either TNF receptor type alone appears sufficient for high-affinity binding and full biological activity, and binds either **tumour necrosis factor** α or **tumour necrosis factor** β with high affinity. The signal transduction mechanism remains speculative, but receptor activation leads to a number of events, including activation of protein kinase C, protein kinase A, phospholipase A_2, and phosphatidylcholine-specific phospholipase C, and accumulation of cyclic AMP and diacylglycerol.

tumour promoter any compound that sensitizes tissues to the action of a **tumour initiator**, or predisposes tissue to become tumorous in any other way.

tumour-suppressor gene a normal gene that suppresses tumorigenesis. Certain cancers are associated with mutant tumour-suppressor genes; *see* (e.g.) **p53**, ***RB***.

TUNEL *abbr* for terminal deoxyribonucleotidyl transferase (TdT)-mediated dUTP nick end labelling. A method of labelling cleaved DNA molecules by enzymically attaching a 2′-deoxyuridyl tag to the 3′ end and detecting it with a fluorescent antibody. Used for recognizing apoptosis *in situ*.

tunnel effect the phenomenon in which an electron or a proton, because of its small mass, does not behave kinetically according to the laws of classical mechanics. These particles can sometimes penetrate an energy barrier that is greater than their kinetic energy.

turacin *see* **tetrapyrrole**.

turanose 3-*O*-*α*-D-glucopyranosyl-D-fructose; an early product of the acid hydrolysis of **melezitose**.



turbid (of a solution) opaque due to the presence of suspended particles. —**turbidity** *n.*

turbidimeter an instrument for measuring the degree to which turbidity hinders the passage of light through a solution.

turbidimetry the quantitative determination of the concentration of substances in suspension by measurement of the decrease in light transmission caused by the suspended particles. *Compare* **nephelometry**.

Turcot syndrome the clinical combination of a primary tumour of the central nervous system and multiple colorectal adenomas or familial predisposition to colorectal cancer. It is associated with germline mutations in *APC*, in *mutL* homologue 1 (h*MLH1*), or in postmeiotic segregation homologue 2 (h*PMS2*). [After Jacques Turcot (1914–), Canadian surgeon.]

turnaround sequence (in DNA) a sequence of nucleotides between two **inverted repeats**. A turnaround sequence will cause a 'bubble' of noncomplementary nucleotides at one end of a **hairpin**.

Turner syndrome a chromosomal abnormality in females characterized by inheritance of only one X chromosome, or one normal X chromosome and one with a structural abnormality. The frequency in liveborn girls is about 1/5000. The syndrome is associated with short stature, webbing of the neck, a failure to menstruate, and infertility. [After Henry H. Turner (1892–1970), US endocrinologist.]

turnover number an obsolete expression of enzymic activity, variously defined on different occasions as the number of substrate molecules converted to product per catalytic site per minute, or as the number of moles of substrate converted per mole of enzyme per minute or second; it has the dimension of reciprocal time. *Compare* **catalytic constant**, **katal**.

turret a multiple cuvette holder that rotates in a spectrophotometer.

T-vector cloning a method for cloning polymerase chain reaction (PCR) products that depends on the addition of deoxyadenosine to the 3′ ends of the products by the terminal transferase activity of ***Taq*** **polymerase**. Vectors with single dideoxythymidine residues at the 3′ ends of the linearized vector form AT base pairs with the PCR products and are ligated efficiently before bacterial transformation and cloning.

Tween *the proprietary name for* a series of surfactants based on polyoxyethylene sorbitan esters. For example, Tween 20 is polyoxyethylene sorbitanmonolaurate (CMC 0.059 mM). Similarly the sorbitan moiety in other Tweens is: Tween 40, sorbitanmonopalmitate; Tween 60, sorbitanmonostearate; Tween 65, sorbitantristearate; Tween 80, sorbitanmonooleate (aggregation number 58, CMC 0.012 mM); Tween 85, sorbitantrioleate.

twilight zone a region of identity (~0–20%) within which sequence alignments appear plausible to the eye but are not statistically significant (i.e. the same alignment could have arisen by chance). *Compare* **midnight zone**.

twin-arginine a motif, consensus sequence SRRXFLK, found in the signal peptides for certain proteins, that is required for transport of the protein in the folded state, complete with cofactors, by the **tat** complex. Transport of the protein is driven by the membrane potential.

Twinkle a mammalian mitochondrial protein, similar to the primase/helicase of bacteriophage T7, that is required for integrity of the mitochondrial genome. Mutations in humans cause autosomal dominant progressive external ophthalmoplegia (*abbr.*: PEO).

twist a *Drosophila* gene for a ***myc*** family homodimeric **helix-turn-helix** transcription factor involved in the establishment of germ layers.

TWIST the human orthologue (202 amino acids) of *twist* protein (490 amino acids) of *Drosophila*. It is a basic helix-loop-helix transcription factor. *twist* protein induces myogenesis during development. Mutations in TWIST cause **Saethre–Chotzen syndrome**.

twist conformation 1 a median conformation of a nonplanar, six-membered, saturated ring compound through which one **boat conformation** passes during conversion into another boat conformation, or through which a boat conformation passes during conversion into a **chair conformation** or vice versa. It is similar to **skew conformation** (def. 1). **2** any conformation of the five-membered ring form of a monosaccharide or monosaccharide derivative when three adjacent ring atoms are coplanar and the other two lie on opposite sides of the plane. The conformational descriptor *-T* may be added to the name of such a compound. *See also* **conformation**.

twist number *or* **twisting number** *symbol*: T; the total number of base pairs in a DNA molecule divided by the number of bases per turn of the double helix. It is one of the properties that identifies **topological isomers** of DNA. *See also* **linking number**, **writhing number**.

twitchin the protein product of *unc-22*, one of about 40 genes important for muscle assembly and function in the nematode, *Caenorhabditis elegans*. Twitchin is a giant myosin-associated protein (*compare* **titin**) that is autophosphorylated on threonine; it contains repeats that are similar to **fibronectin** type III. The protein was named for a mutation that results in twitching. It has a counterpart in *Aplysia californica,* and presumably other invertebrates.

two-carbon fragment 1 any group of atoms containing two carbon atoms. **2** a metabolically active acetyl radical, as in acetyl coenzyme A.

two-component regulatory system one of the signal transduction systems in microorganisms and plants that consists of a membrane **sensor kinase** (SK) and a cognate response regulator (RR). Such systems respond to different types of environmental signal by autophosphorylation of a conserved histidine residue in SK and subsequent transfer to aspartate in RR, which then activates transcription of target genes.

two-component signal transduction a system used by bacteria and lower eukaryotes to adapt to the prevailing environmental and nutrition conditions. A typical system comprises a sensor **histidine kinase** and a cognate **response regulator**. In response to a particular stimulus, the activated sensor kinase phosphorylates its cognate response regulator. This activated response regulator then effects changes in gene expression.

two-dimensional chromatography a chromatographic method in which separation is first effected in one direction and, after rotation of the chromatogram through 90°, then in a second direction, often with a different solvent (or a different pH). **Two-dimensional electrophoresis** works on the same principle.

two-dimensional polymer a macromolecular structure in which approximately parallel chains extending in one direction are cross-linked by another series of approximately parallel chains extending in a second direction. Bacterial cell-wall peptidoglycans are two-dimensional polymers, with glycan chains extending in one direction, cross-linked to peptide chains.

TXA *abbr. for* thromboxane A (*see* **thromboxane**).

TXB *abbr. for* thromboxane B (*see* **thromboxane**).

Tylenol *see* **acetaminophen**.

Tylosin a **macrolide** class antibiotic, similar to **erythromycin**, used in animal feeds and in studies on the structure of **ribosomes**.

tyndallization *or* **tyndallisation** a method of sterilization in which the sample is heated at 80–100°C on successive days so as to kill cells on each occasion, but to allow spores (which are not killed by heating) to produce susceptible cells during the intervening periods of incubation. [After John Tyndall (1820–93), British natural philosopher, alpinist, and popularizer of science.]

type 1,2,3 copper different classes of copper-binding sites in proteins. In type 1, or blue copper centres, the copper is coordinated to at least two imidazole nitrogens from histidine and one sulfur from cysteine. They are characterized by small copper hyperfine couplings and a strong visible absorption in the Cu(II) state. In type 2, or non-blue copper sites, the copper is mainly bound to imidazole nitrogens from histidine. Type 3 copper centres comprise two spin-coupled copper ions, bound to imidazole nitrogens.

type III system a protein secretory system found in Gram-negative bacteria that is responsible for the secretion of **Yop** proteins. The system is known as type III because it was the third type of secretory system found in the membrane of Gram-negative bacteria.

type II transmembrane serine protease *see* **TTSP**.

typing *(in immunology)* the identification of the classes of histocompatibility antigens, blood groups, or other surface markers present in a sample of serum, or on white blood cells or red blood cells.

Tyr *symbol for* a residue of the α-amino acid L-tyrosine (alternative to Y).

tyramine tyrosamine; *p*-(β-aminoethyl)phenol; 2-(4-hydroxyphenyl)ethylamine; a biogenic amine with adrenergic action, formed by enzymic decarboxylation of tyrosine. It is widespread in mammalian tissues, found in several plant species and in **ergot**, and is a product of microbial action in the intestine, in the putrefaction of animal tissue, and in the ripening of cheese.

Tyr(I_2) *or* (if the context does not imply the locants) **Tyr(3,5-I_2)** *symbol for* a residue of the α-amino acid 3,5-diiodo-L-tyrosine (*see* **diiodotyrosine**).

tyrocidine *or* **tyrocidin** any peptide antibiotic produced by *Bacillus brevis* that is a cyclic decapeptide. The structure of tyrocidine A is (amino acids are L unless otherwise stated) cyclic –Leu–D-Phe–Pro–Phe–D-Phe–Asn–Gln–Tyr–Val–Orn–. Tyrocidine B has L-Tyr in place of L-Phe, and in tyrocidine C D-Trp replaces the D-Phe attached to the Asn. They are similar in structure and action to **gramicidin S**, increasing the permeability of bacterial membranes, promoting leakage of cytoplasmic constituents, and permitting entry of ions larger than those normally transported. *Bacillus brevis* is immune from this action. They have little application in medicine. Biosynthesis is independent of ribosomes (*see* **protein and peptide biosynthesis**).

Tyrode's solution *or* **Tyrode solution** *or* **Ringer–Tyrode solution** a balanced salt solution modified from **Locke's solution**, initially for experiments on mammalian intestine. The solution usually contains (in g L^{-1}, approx.): NaCl (8.0); KCl (0.2); $MgCl_2•6H_2O$ (0.1); $CaCl_2$ (anhydrous, 0.2); $NaHCO_3$ (0.1); $NaH_2PO_4•H_2O$ (0.05); and glucose (1.0). [After Maurice Vejux Tyrode (1878–1930), US pharmacologist, who devised this solution in 1910.]

tyrosinase **1** *an alternative name for* **monophenol monooxygenase**. **2** **β-tyrosinase** EC 4.1.99.2; *recommended name*: tyrosine phenol-lyase; an enzyme that catalyses a reaction between L-tyrosine and water to form phenol, pyruvate, and NH_3. Pyridoxal-phosphate is a coenzyme. The protein contains copper and is a homotetramer, similar to **tryptophanase** (def. 1).

tyrosinate **1** tyrosinate(1–); tyrosine monoanion. In theory, the term denotes any ion, or mixture of ions, formed from **tyrosine**, and having a net charge of –1, although the species $HO–C_6H_4–CH_2–CH(NH_2)–COO^–$ predominates in practice. **2** *the systematic name for* tyrosinate(2–); tyrosine dianion; $^–O–C_6H_4–CH_2–CH(NH_2)–COO^–$. **3** any salt containing an anion of tyrosine. **4** any ester of tyrosine.

tyrosine *the trivial name for β*-(*p*-hydroxyphenyl)alanine; *α*-amino-*p*-hydroxyhydrocinnamic acid; *α*-amino-*β*-(*p*-hydroxyphenyl) propionic acid; 3-(4-hydroxyphenyl)alanine; 2-amino- 3-(4-hydroxyphenyl)propanoic acid; $HO–C_6H_4–CH_2–CH(NH_2)–COOH$; a chiral *α*-amino acid. L-Tyrosine (*symbol*: Y *or* Tyr), (*S*)-2-amino-3-(4-hydroxyphenyl)propanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: UAC or UAU. In mammals, it is an essential dietary amino acid, and is both glucogenic and ketogenic. One residue per molecule of D-tyrosine (*symbol*: D-Tyr *or* DTyr), (*R*)-2- amino-3-(4-hydroxyphenyl)propanoic acid, occurs as its *O*-methyl ether in the antibiotic cycloheptamycin.



L-tyrosine

tyrosine decarboxylase EC 4.1.1.25; an enzyme that catalyses the decarboxylation of L-tyrosine to **tyramine**. Pyridoxal-phosphate is a coenzyme.

tyrosine hydroxylase EC 1.14.16.2; *recommended name*: tyrosine 3-monooxygenase; *systematic name*: L-tyrosine, tetrahydrobiopterin:oxygen oxidoreductase. An enzyme that catalyses a reaction between dioxygen, L-tyrosine, and tetrahydrobiopterin to form 3,4-dihydroxy-L-phenylalanine, dihydrobiopterin, and water; it requires ferric ion. It is the rate-limiting enzyme in the synthesis of **catecholamine** neurotransmitters. In humans four types are produced by alternative splicing. *See* **DOPA-responsive dystonia**.

tyrosine kinase EC 2.7.1.112; *recommended name*: protein-tyrosine kinase; *other names*: tyrosylprotein kinase; protein kinase (tyrosine); hydroxyaryl-protein kinase. An enzyme that transfers the terminal phosphate of ATP to a specific tyrosine residue on its target protein; i.e. it catalyses the phosphorylation by ATP of protein-tyrosine to form protein-tyrosine phosphate with release of ADP. The enzyme molecule has five motifs. The tyrosine kinase family is of profound importance due to its involvement in the signalling processes associated with mitogenic stimulation, cell growth, and oncogenesis. The tyrosine kinases fall into two major classes, those that are cell membrane receptors and integral membrane proteins, and those that are intracellular and function downstream of the receptors. The membrane receptors have been grouped into subclasses according to their structure (all individual polypeptides have a single transmembrane domain, with the kinase activity in an intracellular domain); examples include subclass I, proteins having two cysteine-rich repeat sequences in the extracellular domain of a monomeric receptor, a group that includes the **epidermal growth factor receptor**; subclass II, disulfide-linked heterotetrameric $\alpha_2\beta_2$ structures with extracellular cysteine-rich repeat sequences similar to subclass I, an example being the **insulin receptor**; subclass III, proteins with five immunoglobulin-like repeats in the extracellular domain, and with a non-kinase insert in the kinase region, typified by the **platelet-derived growth factor receptor**; and subclass IV, proteins with three immunoglobulin-like repeats in the extracellular domain, with a non-kinase insert in the kinase region. This classification continues to be extended. The intracellular non-receptor tyrosine kinases include, among many, the products of ***FGR***, ***FYN***, and ***src***. *See also* **protein kinase**.

tyrosine 3-monooxygenase *the recommended name for* **tyrosine hydroxylase**.

tyrosine transaminase *or* **tyrosine aminotransferase** (*abbr.*: TAT) EC 2.6.1.5; *systematic name*: L-tyrosine:2-oxoglutarate aminotransferase; an enzyme that catalyses the reaction:

L-tyrosine + 2-oxoglutarate =
4-hydroxyphenylpyruvate + L-glutamate.

It is a pyridoxal-phosphate enzyme and it catalyses the first step in tyrosine catabolism; defects lead to tyrosinemia type II (**Richner–Ranhart syndrome**).

tyrosinium tyrosine cation; the cation, $HO–C_6H_4–CH_2–CH(NH_3^+)–COOH$, derived from **tyrosine**.

tyrosino the alkylamino group, $HO–C_6H_4–CH_2–CH(COOH)–NH–$, derived from **tyrosine**.

tyrosin-*O*⁴-yl the aryloxy group, $HOOC–CH(NH_2)–CH_2–C_6H_4–O–$, derived from **tyrosine**.

tyrosyl the acyl group, $HO–C_6H_4–CH_2–CH(NH_2)–CO–$, derived from **tyrosine**.

tyrphostin any inhibitor of protein-tyrosine kinases derived from the substituted benzylidenemalononitrile, shown as the core structure; A, B, and C can be $–NO_2$, $(CH_3)_3C–$, –OH, or –H. In tyrphostin 25, [(3,4,5-trihydroxyphenyl)-methylene]-propanedinitrile, D is –CN. Some tyrphostins uncouple oxidative phosphorylation and inhibit lipoxygenases.



tyrphostin 25

tyvelose the aldohexose 3,6-dideoxy-D-mannose, 3,6-dideoxy-D-*arabino*-hexose, a monosaccharide of various lipopolysaccharides produced by some Gram-negative bacteria, e.g. certain serotypes of *Salmonella typhi*, where it contributes to the antigenic specificity of the organism's O antigens. The L-enantiomer is called **ascarylose**.

Uu

u 1 *symbol for* unified atomic mass unit. 2 *see* **IU**.

u *symbol for* 1 speed (alternative to *v*, *w*, or *c*). 2 (bold italic) velocity (alternative to *v*, *w*, or *c*).

U *symbol for* 1 a residue of the base uracil in a nucleic-acid sequence. 2 a residue of the ribonucleoside uridine (alternative to Urd). 3 uniformly labelled. 4 enzyme unit (obsolete; superseded by **katal**). 5 uranium.

U *symbol for* 1 electric potential difference (alternative to ΔV or $\Delta\phi$). 2 internal energy.

U46619 a stable thromboxane A_2 analogue and mimetic; *another name for* **9,11-dideoxy-11α,9α-epoxymethanoprostaglandin $F_{2\alpha}$**.

U937 a cell line derived from a patient with histiocytic lymphoma.

UAA a codon in mRNA for chain termination; the **ochre codon**.

UAC a codon in mRNA for L-tyrosine.

UAG a codon in mRNA for chain termination; the **amber codon**.

UAS *abbr. for* upstream activator sequence; the counterpart in yeast of an **enhancer**.

UAU a codon in mRNA for L-tyrosine.

Ubbelohde viscometer *see* **capillary viscometer**.

UBE3A *symbol for* a gene encoding ubiquitin protein ligase E3A, which functions by attaching the small protein ubiquitin to proteins targeted for degradation within proteasomes. Mutations in the gene are responsible for some cases of Angelman syndrome. The paternal allele is imprinted.

UBIP *abbr. for* ubiquitous immunopoietic polypeptide.

ubiquilin a protein that binds to **presenilins**, promotes their accumulation, and appears to increase their synthesis. It is related to ubiquitin in structure, and like ubiquitin is present in the neuropathological lesions characteristic of Alzheimer's disease (neurofibrillary tangles) and Parkinson's disease (Lewy bodies). The responsible gene maps to a region thought to contain a gene for late-onset Alzheimer's disease.

ubiquinol *abbr.*: QH_2; reduced **ubiquinone**.

ubiquinol–cytochrome *c* reductase EC 1.10.2.2; *systematic name*: ubiquinol:ferricytochrome-*c* oxidoreductase; *other name*: complex III. An enzyme complex that catalyses the oxidation of ubiquinol by two molecules of ferricytochrome *c* to form ubiquinone and two molecules of ferrocytochrome *c*. It contains cytochromes b_{562}, b_{566}, and c_1, and a Rieske iron–sulfur protein.

ubiquinone *or (formerly)* **coenzyme Q** *abbr.*: Q; a lipid-soluble electron-transporting coenzyme that is an essential component in the **respiratory chain**. The structure is shown below; *n* has values from 6 to about 12, as indicated by the abbreviation Q_n. Ubiquinone is synthesized in mammals from tyrosine, and in bacteria and other organisms by the **shikimate pathway**. *See also* **protonmotive Q cycle**.



ubiquinone reductase *see* **NADH dehydrogenase (ubiquinone)**.

ubiquitin 1 a small, highly conserved, heat-stable protein of 76 amino-acid residues, first isolated from bovine thymus, but subsequently found in the cells of all tissues studied, in animals, yeast, bacteria, and higher plants. Located in both nuclei and cytoplasm, it derives its name from its widespread distribution. It undergoes an ATP-dependent reaction with proteins that results in condensation of its terminus with lysine amino groups; this process is mediated by a large multiprotein complex, the 26S **proteasome**. For example, cyclin degradation in the control of the cell cycle is triggered by ubiquitination. Thus, the cell has two means of protein degradation: ubiquitination and proteolysis in lysosomes. Such modified proteins are degraded rapidly. Ubiquitin is synthesized as a polyubiquitin precursor, with exact head-to-tail repeats, the number of repeats differing between species. In some species, there is a final amino acid after the last repeat (e.g., Val in human). Some ubiquitin genes encode a single copy of ubiquitin fused to a ribosomal protein. The following sequence is conserved in numerous species:

MQIFVKTLTGKTITLEVEPSDTIENVKAKIQDKEGIP-
PDQQRLIFAGKQLEDGRTLSDYNIQKESTLHLVLRLRGG.

2 *a former name for* **ubiquitous immunopoietic polypeptide**.

ubiquitin-activating enzyme E1 an enzyme that activates ubiquitin by first adenylylating, with ATP as co-substrate, its C-terminal glycine residue and thereafter linking this to itself via the side chain of a cysteine residue, releasing AMP. The protein is a monomer and can accommodate two ubiquitin molecules.

ubiquitination *see* **ubiquitin** (def. 1).

ubiquitin-conjugating enzyme E2 *or* **ubiquitin-carrier protein** an enzyme that accepts the ubiquitin attached to **ubiquitin-activating enzyme E1** and, with **ubiquitin–protein ligase E3**, transfers it to the acceptor protein. Numerous isoforms exist within a species, with specificity for an E3 isozyme and an acceptor protein. Some E2 isoforms transfer the ubiquitin directly to the acceptor protein without the need for E3.

ubiquitin–protein ligase E3 EC 6.3.2.19; *other names*: ubiquitin-conjugating enzyme; ubiquitin-activating enzyme; an enzyme that couples ubiquitin to a protein lysine to form protein N-ubiquitylly-sine with hydrolysis of ATP to ADP and pyrophosphate. Several isozymes with specificity for an E2 and the acceptor protein exist with a species.

ubiquitous immunopoietic polypeptide *abbr.*: UBIP; a polypeptide that has lymphocyte-differentiating properties, and can stimulate adenylate cyclase. It is involved in maintenance of chromatin structure, regulation of gene expression, stress response, and ribosome biogenesis. It was formerly called ubiquitin. *See also* **proteasome**.

Ubl protein *abbr. for* ubiquitin-like protein. *See* **SUMO**

UCA a codon in mRNA for L-serine.

UCC a codon in mRNA for L-serine.

UCG a codon in mRNA for L-serine.

UCP *abbr. for* brown fat uncoupling protein.

UCU a codon in mRNA for L-serine.

Udo *symbol for* the undecanoyl group, $CH_3–[CH_2]_9–CO–$.

UDP *abbr. for* uridine (5′-)diphosphate.

UDP-*N*-acetylglucosamine 6-dehydrogenase EC 1.1.1.136; an enzyme that catalyses the reaction:

UDP-*N*-acetyl-D-glucosamine + 2 NAD^+ + H_2O =
UDP-*N*-acetyl-2-amino-2-deoxy-D-glucuronate + 2 NADH.

UDP-*N*-acetylglucosamine–dolichyl-phosphate-*N*-acetylglucosamine phosphotransferase EC 2.7.8.15; an enzyme that catalyses a reaction between UDP-*N*-acetyl-D-glucosamine and dolichyl phosphate to form *N*-acetyl-D-glucosaminyl-diphosphodolichol and UMP. This is the first reaction in the synthesis of oligosaccharide lipids.

UDP-*N*-acetylglucosamine 2-epimerase EC 5.1.3.14; an enzyme that catalyses the reaction:

UDP-*N*-acetyl-D-glucosamine =
UDP-*N*-acetyl-D-mannosamine.

This is the initial reaction in the synthesis of sialic acid, and the enzyme is allosterically inhibited by CMP-sialic acid. The activity resides in the N-terminal 416 residues of the bifunctional protein (727 amino acids), which has *N*-acetylmannosamine kinase activity in the C-terminal portion. Mutations that impair binding of the inhibitor to the epimerase portion cause the rare disease sialuria.

UDP-*N*-acetylglucosamine 4-epimerase EC 5.1.3.7; an enzyme that catalyses the reaction:

UDP-*N*-acetyl-D-glucosamine =
UDP-*N*-acetyl-D-galactosamine.

UDPG *abbr. for* uridinediphosphoglucose; UDPGlc is preferred (to avoid possible ambiguity in context with galactose).

UDPGal *or* **UDPgalactose** *abbr. for* uridinediphosphogalactose.

UDPgalactose 4-epimerase *abbr.*: GALE; *an alternative name for* **UDPglucose 4-epimerase.**

UDPGlc *(preferred) abbr. for* uridinediphosphoglucose; *see also* **UDPG**.

UDPglucose 6-dehydrogenase EC 1.1.1.22; an enzyme that catalyses the reaction:

UDPglucose + 2 NAD^+ + H_2O =
UDPglucuronate + 2 NADH.

UDPglucose 4-epimerase *the recommended name and systematic name for* the isomerase EC 5.1.3.2; *other names*: UDPgalactose 4-epimerase; (*abbr.*: GALE); *(formerly)* galactowaldenase; an enzyme that interconverts uridinediphosphoglucose and uridinephosphogalactose. The mechanism involves oxidation of the C-4 hydroxyl group of the hexose moiety of either uridinediphosphosugar to an oxo group by a tightly bound molecule of NAD^+; the resultant NADH is then reoxidized by the intermediate oxo derivative with inversion of configuration of the resulting hydrogen and hydroxyl groups at C-4. Mutations that produce enzyme deficiency result in a benign anomaly when it affects only blood cells, or in a severe but rare form of galactosemia when it affects all tissues. The difference may reflect the degree of molecular instability produced by the mutation. The human gene encodes 348 amino acids. *Compare* **UDPglucose–hexose-1-phosphate uridylyltransferase**.

UDPglucose–hexose-1-phosphate uridylyltransferase EC 2.7.7.12; *systematic name*: UDPglucose:α-D-galactose-1-phosphate uridylyltransferase; *other names*: **uridylyltransferase**; galactose-1-phosphate uridylyltransferase. An enzyme that interconverts uridinediphosphoglucose and uridinediphosphogalactose. It is important in the metabolism of galactose by catalysing the exchange reaction:

UDPglucose + α-D-galactose 1-phosphate =
α-D-glucose 1-phosphate + UDPgalactose.

More than 150 mutations cause deficiency of the enzyme, which is associated with a form of **galactosemia**. In *Escherichia coli* the enzyme comprises 890 amino acids (102.31 kDa) and modifies the **nitrogen regulatory protein P_{II}** . *Compare* **UDPglucose 4-epimerase**.

UDPglucose pyrophosphorylase *an alternative name for* **UTP–glucose-1-phosphate uridylyltransferase**.

UDPglucuronate 4-epimerase EC 5.1.3.6; an enzyme that catalyses the reaction:

UDP-D-glucuronate = UDP-D-galacturonate.

UDPglucuronate 5′-epimerase EC 5.1.3.12; an enzyme that catalyses the reaction:

UDP-D-glucuronate = UDP-L-iduronate.

NAD^+ is a cofactor.

UDPglucuronosyltransferase EC 2.4.1.17; *abbr.*: UDPGT *or* UGT; *recommended name*: glucuronosyltransferase; an enzyme involved in the formation of **glucuronosides**. It catalyses a reaction between UDPglucuronate and an acceptor to form UDP and acceptor *β*-D-glucuronoside. The numbering of variants uses several systems; the one followed here has UDPGT followed by a number, letter, and sometimes a number, e.g. UDPGT1F, UDPGT2B1O. Human examples include: UDPGT1a (bilirubin-specific isozyme 1); UDPGT1b; and UDPGT1c (*or* UGT13).

UDPGP *abbr. for* UDPglucose pyrophosphorylase (i.e. **UTP– glucose-1-phosphate uridylyltransferase**).

UGA **1** a codon in nonmitochondrial mRNA for chain termination; the **opal codon**. **2** a codon in mitochondrial mRNA for L-tryptophan.

UGC a codon in mRNA for L-cysteine.

UGG a codon in mitochondrial mRNA, and the only codon in nonmitochondrial mRNA, for L-tryptophan.

UGU a codon in mRNA for L-cysteine.

+ulose *noun suffix* denoting a **ketose**; it may be expanded to **+ulofuranose** or **+ulopyranose** according to whether the cyclic form of the sugar is five-membered or six-membered respectively.

+ulosonic acid *noun suffix* denoting a **ketoaldonic acid**; it may be expanded to **+ulofuranosonic acid** or **+ulopyranosonic acid** according to whether the cyclic form of the sugar acid is five-membered or six-membered respectively.

ultimate carcinogen *or* **ultimate carcinogenic metabolite** any metabolite of a **chemical carcinogen** that reacts with cellular constituents so as to initiate carcinogenesis. *See also* **proximate carcinogen**.

ultimobranchial body one of a pair of glandlike structures derived from the last branchial (gill) pouches. They occur in all vertebrates except cyclostomes. In most mammals they become embedded in the respective lobes of the thyroid gland, forming **C cells**, which secrete the hormone **calcitonin**.

ultra+ *prefix* **1** beyond in space; on the other side (of). *Compare* **infra+**, **trans+**. **2** beyond a specified (esp. in scientific usage, lower) limit, range, value, etc. *Compare* **super+**. **3** beyond the common, ordinary, natural, etc.; extreme(ly). *Compare* **hyper+**.

ultracentrifuge any centrifuge that operates at high rotational velocities generating high gravitational fields. Ultracentrifuges can be operated at known speeds with small variations and without temperature fluctuations. They may be either analytical or preparative.

ultradian (of a biological activity) occurring less often than once per 24-hour period. *Compare* **circadian**, **infradian**.

ultrafilter a filter of small pore size suitable for **ultrafiltration**.

ultrafiltration a separation process whereby a solute of molecular size significantly greater than that of the solvent molecule is removed from the solvent by the application of a hydraulic pressure, which forces only the solvent to flow through a suitable membrane (usually one having a pore size in the range 0.001–0.1 μm), thereby concentrating the solute.

ultramicrotome a device for preparing very thin sections of cells or tissues, after fixing and embedding or freezing, for inspection in the transmission electron microscope.

ultrasonic of, pertaining to, or producing **ultrasound** waves.

ultrasonication the process of exposing material to **ultrasound**. It is used for cell disruption, for denaturation of proteins, and for cleaning solid surfaces. *See also* **sonicate**.

ultrasonic disintegrator an apparatus for disintegrating cells and other material, or for cleaning solid surfaces, by exposing them to **ultrasound**. *See also* **sonicator**.

ultrasound propagated waves, of the same nature as sound but inaudible, with frequencies of >20 kHz. Frequencies of ≈25 kHz can be used for disintegrating cells and subcellular components and also in cleaning baths for the removal of deposits on a wide variety of objects. In physiotherapy the range of 0.5–3 MHz is used for the relief of painful muscles by producing warmth and by changing the permeability of cell membranes, which allows for the removal of fluid. For diagnostic purposes the range of 3–12 MHz is commonly used and is a popular method of non-invasive imaging, e.g. in pregnant women. There is also ultrasonic microscopy, which mimics light microscopy and employs sound in the GHz range. Ultrasound is also being developed for the disintegration of tumours.

Ultraspiracle *abbr.*: USP; a nuclear hormone receptor of *Drosophila* that forms heterodimers with the ecdysteroid receptor and with *Drosophila* hormone receptor 38 (DHR38).

ultrastructure the fine structure of an organ, tissue, cell, or subcellular particle, especially that demonstrable with an electron microscope.

ultraviolet (radiation) *abbr.*: UV *or* uv; electromagnetic radiation of wavelengths in the range 13.6–400 nm (frequencies 750 THz–22.1 PHz). This range overlaps the wavelengths of soft X-radiation and ends just across the short-wavelength limit of visible light. Ultraviolet radiation is often divided into **near ultraviolet** (200–400 nm) and **far ultraviolet** (or **vacuum ultraviolet**) (<200 nm);

radiation in the far ultraviolet is absorbed by O_2 and requires the use of evacuated apparatus or flushing with N_2.

ultraviolet-endonuclease an enzyme involved in the repair of ultraviolet-irradiated DNA in microorganisms. *See also* **deoxyribonuclease (pyrimidine dimer)**, ***uvr***.

ultraviolet reactivation *see* **W reactivation**.

Ultrogel *the proprietary name for* a range of bead-form rigid support materials used in **gel filtration**, **affinity chromatography**, and related procedures. It consists of a lattice of polyacrylamide in a matrix of agarose gel.

umbelliferone 7-hydroxycoumarin; a common component of plant extracts, used as a fluorescent pH indicator and as a fluorescent label.



UML *abbr. for* universal markup language; *see* **markup language**.

UMP *abbr. for* uridine monophosphate; i.e. uridine phosphate.

UMP synthase the combination of enzymes that form uridine 5′-phosphate from orotate: these are **orotate phosphoribosyltransferase** (forming orotidylic acid) and **orotidine 5′-phosphate decarboxylase**. *See also* **uridine-5′-monophosphate synthase**.

umu bacterial genes encoding proteins that are involved in the error-prone **SOS repair** process, probably by allowing bypass synthesis across a damaged template.

un+ *prefix* **1** *(used with adjectives, adverbs, and nouns)* not; opposite of; contrary to. **2** *(used with verbs)* reversal of an action or state; release; removal from.

unary operator an arithmetic or logical operator (e.g. NOT) that operates on only one variable. *Compare* **binary operator**.

unc-86 a gene of *Caenorhabditis elegans* that encodes a transcription factor containing the **POU domain** and contributes to the naming of the domain.

uncharacterized protein family *abbr.*: UPF; a related group of protein sequences whose function has not been experimentally determined and that shows no similarity to other, functionally characterized, sequences.

uncoating enzyme an enzyme that catalyses the removal of the protein coat from a virus.

uncoded amino acid *an alternative term for* **noncoded amino acid**.

uncompensated acidosis an **acidosis** in which there is a fall of the blood pH, due to the inadequacy of the physiological compensating mechanisms.

uncompensated alkalosis an **alkalosis** in which there is a rise of the blood pH, due to the inadequacy of the physiological compensating mechanisms.

uncompetitive inhibition the inhibition of an enzyme system when the inhibitor does not combine with the free enzyme, but only with one of the enzyme–substrate intermediates.

unconventional myosin any of about 14 isoforms of muscle **myosin** (myosin II) that function as motor proteins and are also found in many nonmuscle cell types. Each consists of a globular head (an actin-activated ATPase) and a short tail (which binds membranes including those of organelles and vesicles). Movement of the head over actin microfilaments is responsible for cytokinesis, cytoplasmic streaming, and axonal transport. **Myosin I** is present in most nonmuscle cells. **Myosin Va** is responsible for transport of melanosomes in pigment cells and of vesicles in neurons. Mutations in its gene at 15q21 are associated with Griscelli syndrome (hypopigmentation of skin and hair and immunological deficiency). **Myosin VIIa** is a protein of 2215 amino acids. Some mutations in its gene at 11q13.5 are associated with a form of familial nonsyndromic deafness, whereas others result in Usher syndrome type I (congenital deafness with vestibular dysfunction and retinitis pigmentosa). **Myosin XV** is 3530 amino acids long and present in the sensory cells of the inner ear. Mutations in its gene at 17p11.2 result in a form of familial nonsyndromic deafness.

uncoupled 1 disconnected; unfastened. **2** *(in biochemistry)* describing an organism, tissue, cell, or mitochondrion in which phosphorylation is dissociated from oxidation in the **respiratory chain**. *See also* **uncoupling**.

uncoupler *an alternative name for* uncoupling agent (*see* **uncoupling**).

uncoupling *(in biochemistry)* the dissociation of phosphorylation from oxidation in the **respiratory chain**, so that electron transport proceeds without the esterification of phosphate and without the need for inorganic phosphate. An **uncoupling agent** (*or* uncoupler) is a substance that causes uncoupling of phosphorylation from electron transport at one or more points in the electron-transport chain. A classical example is **dinitrophenol**. Uncoupling agents probably act by causing leakage of protons across the mitochondrial inner membrane thereby destroying the proton gradient that drives oxidative phosphorylation. *See also* **chemiosmotic coupling hypothesis**.

uncoupling protein *see* **brown fat uncoupling protein**.

undec+ *or* **undeca+** *prefix* denoting eleven.

undecaprenol *or* **bactoprenol** a polyunsaturated long-chain (C_{55}) primary alcohol containing 11 **prenyl** units.

undecaprenyl phosphate *or* **undecaprenol phosphate** a very hydrophobic phosphate ester of **undecaprenol**. It acts as a membrane-soluble carrier to which intermediates are combined in the course of the biosynthesis of bacterial cell-envelope components, e.g. peptidoglycan and lipopolysaccharide. *Other names*: bactoprenyl phosphate; carrier lipid; C_{55} carrier lipid; C_{55} lipid carrier.

underivatized *or* **underivatised** (of a substance) in the naturally occurring state.

undulin a non-collagenous glycoprotein of the interstitial extracellular matrix, associated with collagen. Isolated from skin or placenta, it is found mainly between densely packed mature collagen fibrils as bundles of uniform wavy fibres. It is a member of the fibronectin–tenascin family, and is related to collagen type XIV. It is associated with dense collagen matrices in soft tissues, and is likely to be involved in the supramolecular organization of interstitial collagens. Human undulin 2 shares sequence similarity with fibronectin type III.

ung *see* **uracil-DNA *N*-glycosylase**.

Uni *see* **reactancy of enzymes**.

uni+ *comb. form* consisting of, having, or relating to one.

unicode a set of characters that, unlike **ASCII**, occupy 16 bits and can therefore encode many different alphabets.

unidentified reading frame *abbr.*: URF; an open reading frame that encodes a protein of unknown function.

unified atomic mass unit *or (formerly)* **atomic mass unit** (*abbr.*: amu *or* a.m.u.) *symbol*: u; a non-SI unit of mass equal to one-twelfth of the mass of one atom of carbon-12; i.e.

$$1\ \mathrm{u} = m_a(^{12}\mathrm{C})/12 \approx 1.660\,540 \times 10^{-27}\ \mathrm{kg}.$$

It is identical with **dalton**.

uniformly labelled *symbol*: U; describing a **labelled compound** in which the label is distributed in a statistically uniform, or nearly uniform, manner between all the possible positions in the molecule.

UniGene *see* **cluster database**.

unimolecular reaction *see* **molecularity**.

uniparental disomy the inheritance of two copies of a chromosome from one parent.

uniport a membrane transport process in which a single kind of substrate (ion or uncharged molecule) is transported across the membrane, either by the mechanism of mediated diffusion where the substrate equilibrates at the two membrane sides (e.g., monosaccharides in mammalian erythrocytes; TC 2.A.1.1.12), or by active transport where an external source of energy is used to achieve movement against a chemical potential or an electrochemical potential gradient (e.g., plasma membrane H^+-transporting ATPase TC 3.A.3.3.1 or EC 3.6.3.6). Such transport systems may be designated as **uniporters**.

UniProt *abbr. for* universal protein sequence database; *see* **composite database**.

unique (sequence) DNA *or* **single-copy DNA** any unique and specifically ordered nucleotide sequence in DNA that occurs only once in a genome. *Compare* **repetitive sequences**.

unitary matrix *an alternative name for* identity matrix. *See* **scoring matrix**.

unit cell the smallest portion of a crystal that, by translation in three dimensions, is able to account for the structure of the entire crystal. The array of unit cells, arranged along parallel straight lines, makes up the **crystal lattice**.

unit membrane *or* **double membrane** *or* **triple membrane** any membrane, irrespective of cellular location, that on staining with osmium or other heavy metals appears in section in the electron microscope as a pair of parallel dark lines separated by a less dense layer, the whole being 6–10 nm thick. Unit membranes include the plasma membrane and the membranes of organelles such as mitochondria, nuclei, and endoplasmic reticulum.

unit of replication *see* **replicon**.

unit of transcription *see* **transcriptional unit**.

univalent 1 *or* **monovalent** (of a chemical species) having a **valency** of one. **2** an unpaired chromosome seen during meiosis when bivalents are also present. Such a chromosome either lacks a homologue or results from **asynapsis**. **—univalency** *n.*

UniVec *see* **vector database**.

universal buffer mixture any solution containing several buffering systems chosen so as to provide a relatively high buffer capacity over a wide pH range.

universal donor an individual with O-type blood; such blood may be transfused into any recipient. *See* **ABO system**.

universal primers oligonucleotides used as primers in DNA sequencing reactions that are specific for plasmid sequences flanking the cloned DNA insert. Because sequences such as the T3, T7, or SP6 promoters are commonly used in this position, primers annealing to them can be used to obtain sequences of inserts cloned in a variety of vectors.

universal recipient an individual with AB-type blood; such individuals may be transfused with blood from any donor. *See* **ABO system**.

unmediated transport *or* **nonmediated transport** the movement of a solute across a barrier by **diffusion** (def. 1).

unpaired electron an electron in an atom or molecule whose spin is not paired with the oppositely directed spin of another electron in the same atom or molecule. Only systems containing unpaired electrons will give an electron spin resonance signal. *See* **electron spin resonance spectroscopy**.

unrooted tree a **phylogenetic tree** in which the evolutionary ancestor is unknown.

unsaponifiable lipid *or* **unsaponifiable material** part of a lipid sample that is not solubilized by **saponification**. It consists principally of steroids and terpenes.

unsaturated 1 (of a solution) able to dissolve more of the solute in question. **2** (of an organic compound) containing double bonds; *see also* **polyunsaturated**. **3** (of any chemical system, e.g. an enzyme or antibody) not fully saturated with ligand (e.g. substrate or antigen).

unsaturated-fatty-acid oxidation the degradation of unsaturated fatty acids to CO_2 and H_2O; this is achieved largely by enzymes of the **beta-oxidation system**, but enzymes specific for unsaturated fatty acids are also required. Thus, when beta-oxidation reactions have removed carbons to the point at which the resulting acyl-CoA molecule has a Δ^3-*cis* double bond (which is not a substrate for **enoyl-CoA hydratase**), an enoyl-CoA isomerase (*see* **dodecenoyl-CoA Δ-isomerase**) converts this bond to a Δ^2-*trans* double bond. Similarly, when an acyl-CoA with a Δ^4-*cis* double bond is produced, which again is not a substrate for enoyl-CoA hydratase, **2,4-dienoyl-CoA reductase** followed by enoyl-CoA isomerase yield the substrate with a Δ^2-*trans* double bond.

untranscribed spacer a region of genomic DNA, lying between genes or groups of genes, that is not transcribed. *See* **spacer** (def. 1).

untranslated region *abbr.*: UTR; any part of an mRNA molecule not coding for a protein; e.g. in eukaryotes the **poly(A) tail**.

unweighted pair-group method with arithmetic averaging *abbr.*: UPGMA; a distance-based, hierarchical clustering method used to create phylogenetic trees under the molecular clock assumption (i.e. assuming constant rates of evolution over different lineages).

unwinding protein *or* **unwindase** any of the proteins concerned in DNA replication that have a higher affinity for single-stranded DNA than for double-stranded DNA and hold the strands apart during replication.

UPA *abbr. for* urokinase-type plasminogen activator; *see* **plasminogen activator**.

UPF *abbr. for* uncharacterized protein family.

UPGMA *abbr. for* unweighted pair-group method with arithmetic averaging.

U5′pp1Gal *symbol for* uridinediphosphogalactose (alternative to Urd*PP*Gal *or* Urd-5′*PP*-Gal).

U5′pp1Glc *symbol for* uridinediphosphoglucose (alternative to Urd*PP*Glc *or* Urd-5′*PP*-Glc).

up-promoter a mutation that increases **promoter** strength in the expression of a gene.

up-regulation 1 the process of reducing or suppressing the response of a cell to a stimulus. **2** a process in which the expression of a gene is increased.

upsilon *symbol*: υ (lower case) *or* Υ (upper case); the twentieth letter of the Greek alphabet.

upstream in or towards positions in a DNA molecule lying in the 5′ direction relative to the start of transcription of a gene.

upstream activator sequence a sequence in yeast DNA that is located 5′, and a few hundred base pairs from, the transcriptional initiator site of a protein-coding gene. When bound by one or more specific proteins it stimulates transcription of the gene. In higher eukaryotes the same role is played by **enhancers**. *See* **USA**.

Ur *or* **UR** *abbr. for* uridine (the symbol Urd is recommended).

Ura *symbol for* a residue of the pyrimidine base **uracil**.

URA3 *symbol for* the gene in *Saccharomyces cerevisiae* for orotidine-5′-phosphate decarboxylase. Null mutants are uracil auxotrophs. Vectors encoding *URA3* can complement yeast strains carrying the *ura3* mutation.

uracil *symbol*: U *or* Ura ; 2,4-dioxopyrimidine; 2,4-pyrimidinediol; a pyrimidine base occurring in RNA (but not in DNA).



uracil-DNA *N*-glycosylase an enzyme (sub-subclass EC 3.2.2) that removes from DNA any uracil resulting from misincorporation of dUTP that has escaped the action of dUTPase (EC 3.6.1.23, dUTP pyrophosphatase). The enzyme hydrolyses the bond at C-1 of the deoxyribose to yield free uracil and DNA containing an apyrimidinic site; another enzyme, apyrimidine endonuclease, recognizes this site and cleaves the phosphodiester bond on the 5′ side of the deoxyribose moiety. Uracil-DNA *N*-glycosylase may represent the evolutionary basis for the presence of T (not U) in DNA. Cytosine deamination leads to U residues, which would generate transition mutations on replication. The enzyme is a monomer, and is highly conserved in all species. In *Escherichia coli* it is encoded by the *ung* gene, and mutations in this can be used in certain forced site-directed mutagenesis protocols.

urate oxidase EC 1.7.3.3; *systematic name*: urate:oxygen oxidoreductase; *other name*: uricase. An enzyme that catalyses the reaction: urate + $O_2 \rightarrow$ intermediate(s) that lead(s) to **allantoin**. It is a conserved peroxisomal copper-containing enzyme. Some mammals (e.g. humans, gorillas) that lack the enzyme are prone to **gout**.

Urd *symbol for* a residue of the ribonucleoside **uridine** (alternative to U).

Urd*P* *symbol for* any uridine phosphate.

Urd2′*P* *symbol for* uridine 2′-phosphate.

Urd-2′3′-*P* *symbol for* uridine 2′,3′-phosphate.

Urd3′*P* *symbol for* uridine 3′-phosphate.

Urd-3′5′-*P* *symbol for* uridine 3′,5′-phosphate.

Urd5′*P* *symbol for* uridine 5′-phosphate.

Urd5′*PP* *symbol for* uridine 5′-diphosphate (alternative to ppU).

Urd*PP*Gal *or* **Urd-5′*PP*-Gal** *symbol for* uridinediphosphogalactose (alternatives to U5′pp1Gal).

Urd*PP*Glc *or* **Urd-5′*PP*-Glc** *symbol for* uridinediphosphoglucose (alternatives to U5′pp1Glc).

Urd5′*PPP* *symbol for* uridine 5′-triphosphate (alternative to pppU).

urea the water-soluble compound $H_2N–CO–NH_2$, produced in the liver via the **ornithine–urea cycle**. It is the main nitrogen-containing (urinary) excretion product in **ureotelic** animals. It is used as a source of nonprotein nitrogen in ruminant livestock feeds.

urea cycle *see* **ornithine–urea cycle**.

urease EC 3.5.1.5; *systematic name*: urea amidohydrolase; a nickel-protein enzyme that catalyses the hydrolysis of urea to carbon dioxide and ammonia. A carbamoylated lysine provides an oxygen ligand to each nickel, thus explaining a requirement for CO_2 as an activator of urease apoenzyme. In *Proteus vulgaris* urease is a decamer of three subunits, probably in two $\alpha\beta_2\gamma_2$ complexes.

urea transporter *abbr.*: UT; any facilitated urea transporter in kidney. In rat kidney, **UT1** (929 amino acids) consists of homologous halves, each containing ten transmembrane segments, and intracellular N- and C-termini. It is present in the collecting duct and is involved in vasopressin-regulated urea resorption. **UT2** is present in the proximal renal tubules, and **UT3** is present in the descending vasa recta.

ureido the $NH_2–CO–NH–$ group, derived from urea by loss of a hydrogen atom.

ureidosuccinase EC 3.5.1.7; an enzyme that hydrolyses *N*-carbamoyl-L-aspartate (ureidosuccinate) to L-aspartate, CO_2, and NH_3.

ureogenic describing an organism (or species) that possesses the full complement of **ornithine–urea cycle** enzymes, and that potentially, but not necessarily, can biosynthesize significant amounts of urea.

ureosmotic describing an organism (or species) that adjusts urea production or retention so as to maintain osmotic equilibrium, rather than as a means of disposing of surplus nitrogen.

ureotelic describing an organism (or species) in which **urea** is the principal end product of the degradation of nitrogen-containing compounds, e.g. mammals and marine fishes.

URF *abbr. for* unidentified reading frame.

+uria *comb. form* signifying (in relation to a substance specified) presence unusually, or at a supranormal concentration, in urine. Hence also used to denote a morbid condition so marked, e.g. **phenylketonuria**.

uric acid 2,6,8-trioxypurine; purine-2,6,8-triol; the end product of purine metabolism in certain mammals (including humans) and the main nitrogenous excretory product in **uricotelic** animals. It is formed from xanthine by **xanthine oxidase**. Uric acid is very sparingly soluble in water, and deposits as monosodium urate crystals in the tissues in gout.



uricase *an alternative name for* **urate oxidase**.

uricosuric (of a drug) tending to promote urinary excretion of uric acid.

uricotelic describing an organism (or species) in which uric acid is the principal end product of the degradation of nitrogen-containing compounds. Uricotelic animals include birds, terrestrial reptiles, and insects. The low solubility of uric acid in water means that it is present as a solid in the excreta of these animals, enabling excretion with little water loss.

uridine *symbol*: U *or* Urd; uracil riboside; 1-*β*-D-ribofuranosyluracil; a ribonucleoside very widely distributed but occurring almost entirely as phosphoric esters in ribonucleotides and ribonucleic acids. *Compare* **pseudouridine**.



uridine

uridine 2′,3′-(cyclic)phosphate *see* **uridine phosphate**.

uridine 3′,5′-(cyclic)phosphate *or* **uridine 3′,5′-cyclophosphate** *see* **uridine 3′,5′-phosphate**.

uridine 5′-diphosphate *symbol*: Urd5′*PP* *or* ppU; *the recommended name for* uridine diphosphate (*abbr.*: UDP); 5′-diphosphouridine; 5′-diphosphouridine; 5′-uridylyl phosphate; uridine 5′-(trihydrogen diphosphate); a universally distributed nucleotide that occurs both in the free state and as a component of a number of important **uridinediphosphosugars**. It is the intermediate in the formation of uridine 5′-triphosphate, UTP, from uridine 5′-phosphate, UMP.

uridine diphosphate galactose *symbol*: Urd-5′-*PP*-Gal *or* U5′pp1Gal *or* UDPGal; uridine 5′-(*α*-D-galactopyranosyl diphosphate); *recommended name*: uridine(5′)diphospho(1)-*α*-D-galactose; an important intermediate in the metabolism of D-galactose and in the formation of numerous derivatives. It is formed by the reaction of galactose 1-phosphate with UDP-glucose (catalysed by **UDPglucose–hexose-1-phosphate uridylyltransferase**), or with UTP (catalysed by **UTP–hexose-1-phosphate uridylyltransferase**).



uridine diphosphate glucose *symbol*: Urd-5′-*PP*-Glc *or* U5′pp1Glc *or* UDPGlc *or* UDPG; uridine 5′-(*α*-D-glucopyranosyl diphosphate); *recommended name*: uridine(5′)diphospho(1)-*α*-D-glucose; an important intermediate in the formation of other sugars from glucose. It is formed by the reaction of glucose 1-phosphate with UTP, catalysed by **UTP–glucose-1-phosphate uridylyltransferase**.



uridinediphosphosugar *abbr.*: UDPsugar; *the recommended name for* **uridine diphosphate sugar**; any **nucleosidediphosphosugar** in which the distal phosphoric residue of uridine 5′-diphosphate is in glycosidic linkage with a monosaccharide (or a derivative of a monosaccharide). UDPsugars are important as coenzymes for reactions involving the transfer of monosaccharide residues in the biosynthesis of oligosaccharides and polysaccharides (especially in plants) and in the formation of the oligosaccharide moieties of **glycoconjugates**. The main UDPsugars are: UDP-L-arabinose, UDP-D-galactose (*see* **uridine diphosphate galactose**), UDP-D-galacturonate, UDP-D-glucose (*see* **uridine diphosphate glucose**), UDP-D-glucuronate, and UDP-D-xylose, all of which are (directly or indirectly) interconvertible where they occur together; UDP-L-iduronate, which is formed by epimerization of UDP-D-glucuronate; UDP-*N*-acetyl-D-galactosamine and UDP-*N*-acetyl-D-glucosamine, which are interconvertible; and UDP-*N*-acetylmuramate, which is synthesized from UDP-*N*-acetyl-D-glucosamine. Certain UDPsugars, particularly UDP-D-glucose and UDP-D-glucuronate, are coenzymes for the formation in animals or plants of glycosides with aglycons such as bilirubin, phenols, plant pigments and sterols, and steroid hormones.

uridine kinase EC 2.7.1.48; *other name*: uridine monophosphokinase; an enzyme that catalyses the phosphorylation by ATP of uridine to uridine 5′-phosphate with formation of ADP.

uridine monophosphate *abbr.*: UMP; *an alternative name for* any uridine phosphate, particularly for uridine 5′-phosphate when its distinction from uridine (5′-)diphosphate and uridine (5′-)triphosphate requires emphasis.

uridine 5′-monophosphate synthase *abbr.*: UMP synthase; a multifunctional enzyme that in higher eukaryotes carries out the following two reactions: (1) orotate phosphoribosyltransferase, EC 2.4.2.10; *other names*: orotidylic acid phosphorylase, orotidine-5′-phosphate pyrophosphorylase; *systematic name*: orotidine-5′-phosphate:pyrophosphate phospho-α-D-ribosyltransferase; a reaction of the pathway for *de novo* biosynthesis of pyrimidine nucleotides. It catalyses a reaction between orotate and 5-phospho-α-D-ribose 1-diphosphate to form orotidine 5′-phosphate and pyrophosphate. (2) Orotidine-5′-phosphate decarboxylase, EC 4.1.1.23; *systematic name*: orotidine-5′-phosphate carboxy-lyase; a decarboxylation reaction that forms uridine 5′-monophosphate and CO_2 from orotidine 5′-phosphate.

uridine phosphate *symbol*: Urd*P*; uridine monophosphate (*abbr.*: UMP); any phosphoric monoester or diester of uridine. There are three monoesters – uridine 2′-phosphate, uridine 3′-phosphate, and **uridine 5′-phosphate** – and two diesters – uridine 2′,3′-phosphate and **uridine 3′,5′-phosphate** – although uridine 5′-phosphate is the ester commonly denoted (the locant being omitted if no ambiguity may arise). Uridine 2′,3′-phosphate (*symbol*: Urd-2′,3′-*P*), *also named* uridine 2′,3′-(cyclic)phosphate *or* cyclic uridine 2′,3′-monophosphate (*abbr.*: 2′,3′-cyclic UMP), is formed as an intermediate during the alkaline hydrolysis of ribonucleic acid. This diester then readily hydrolyses to a mixture of the two monoesters uridine 2′-phosphate (*symbol*: Urd2′*P*), *also named* uridine 2′-monophosphate (*abbr.*: 2′UMP) *or* 2′-uridylic acid *or* uridylic acid a, and uridine 3′-phosphate (*symbol*: Urd3′*P*), *also named* uridine 3′-monophosphate (*abbr.*: 3′UMP) *or* 3′-uridylic acid *or* uridylic acid b.

uridine 2′-phosphate *see* **uridine phosphate**.

uridine 2′,3′-phosphate *see* **uridine phosphate**.

uridine 3′-phosphate *see* **uridine phosphate**.

uridine 3′,5′-phosphate *symbol*: Urd-3′,5′-*P*; *the recommended name for* cyclic uridine 3′,5′-monophosphate (*abbr.*: 3′,5′-cyclic UMP *or* cyclic UMP *or* cUMP); uridine 3′,5′-cyclophosphate; uridine 3′,5′-(cyclic)phosphate; a monophosphoric diester of uridine found in most mammalian tissues. It is a cyclic nucleotide similar to **adenosine 3′,5′-phosphate**, cyclic AMP. It has been reported to inhibit the growth of certain transplantable tumours.

uridine 5′-phosphate *or* **5′-uridylic acid** *or* **5′-phosphouridine** *or* **5′-*O*-phosphonouridine** *symbol*: Urd5′*P*; *alternative recommended names for* uridine 5′-monophosphate (*abbr.*: 5′UMP); uridine 5′-(dihydrogen phosphate); uridine (mono)ribonucleotide. (The locant is commonly omitted if there is no ambiguity as to the position of phosphorylation.) It is synthesized from aspartate via the decarboxylation of orotidine 5′-phosphate (i.e. orotidylic acid). Resynthesis of UMP from free uridine formed by degradation of ribonucleic acid can be effected via a **salvage pathway**. UMP is a key intermediate in the formation of uridine 5′-triphosphate, UTP, and hence in the biosynthesis of other pyrimidine nucleotides.

uridine phosphorylase *see* **pyrimidine-nucleoside phosphorylase**.

uridine 5′-triphosphate *symbol*: Urd5′*PPP or* pppU; *the recommended name for* uridine triphosphate (*abbr.*: UTP); 5′-triphosphouridine; 5′-uridylyl diphosphate; uridine 5′-(tetrahydrogen triphosphate); a nucleotide present in all cells. It is formed from uridine 5′-phosphate via uridine 5′-diphosphate by the successive action of nucleoside-phosphate kinase (EC 2.7.4.4) and nucleoside-diphosphate kinase (EC 2.7.4.6), which transfer in turn the terminal phosphoric residues from two molecules of ATP. UTP is the starting point for the biosynthesis, first of cytidine triphosphate, next of cytidine diphosphate, and then of various deoxyribonucleotides of cytosine, uracil, and thymine. It is important also for the formation of uridinediphosphogalactose and uridinediphosphoglucose through the action of certain **uridylyltransferases**, and thence of a number of other uridinediphosphosugars.



uridyl 1 any chemical group formed by the loss of a 2′-, a 3′-, or a 5′-hydroxyl group from the ribose moiety of uridine. **2** *a misnomer for* **uridylyl**.

uridylate 1 either the monoanion or the dianion of uridylic acid. **2** any mixture of uridylic acid and its anions. **3** any salt or ester of uridylic acid.

uridylic acid *the trivial name for* any phosphoric monoester of uridine. The position of the phosphoric residue on the ribose moiety of a given ester may be specified by a prefixed locant; *see* **uridine phosphate**. However, 5′-uridylic acid is the ester commonly denoted, its locant usually being omitted if no ambiguity may arise. 5′-Uridylic acid is also an alternative recommended name for **uridine 5′-phosphate**.

uridyl transferase *another name for* **UDPglucose–hexose-1-phosphate uridylyltransferase**. This is a misnomer; *compare* **uridyl** *with* **uridylyl**.

uridylyl the uridine[mono]phospho group; the acyl group derived from uridylic acid. *Distinguish from* **uridyl**.

uridylylate to introduce uridylyl groups into a compound (e.g. a protein, a ribonucleic acid, or a sugar phosphate), generally through the action of a uridylyltransferase. **—uridylylated** *adj.*; **uridylylation** *n.*

uridylyl-removing enzyme a putative enzyme present in *Escherichia coli* that detaches uridylyl groups from uridylylated nitrogen regulatory protein P_{II} by hydrolysis, with formation of uridylate. *See also* **nitrogen regulatory protein**, UDPglucose–hexose-1-phosphate **uridylyltransferase**.

uridylyltransferase *an alternative name for* UDPglucose–hexose-1-phosphate uridylyltransferase.

urinalysis the chemical and physical analysis of urine.

urinary of, or pertaining to, urine.

urinary stone protein *see* **osteopontin**.

urine the aqueous excretion produced by the kidneys in higher animals. It serves as a vehicle for the elimination of certain metabolic waste products, e.g. **urea** and **uric acid**, and for the removal of excess ions and water. In mammals and fishes it is fluid, while in birds and reptiles it is semi-solid.

urinometer a **hydrometer** specifically designed and calibrated for measuring the specific gravity of (mammalian) urine.

URL *abbr. for* uniform resource locator; a method for identifying WWW sites that is 'uniform', i.e. independent of any specific protocol. URLs have a convention of the type <type>// of which <type> would typically be http or ftp. Here is a fairly typical URL:

http://www.oup.co.uk/;

in this case

http://www.oup.co.uk/index.html

is the **home page**.

urobilin *or* **urobilin IXα** a yellow linear tetrapyrrole. It is formed in kidney and is an oxidation product of **urobilinogen**; the central methylene group linking pyrrole units has been converted to –CH=. Urobilin gives urine its yellow colour. *See also* **stercobilin**.

urobilinogen *or* **mesobilirubinogen** *or* **urobilinogen IXα** a colourless linear tetrapyrrole formed in heme catabolism by reduction of free **bilirubin** released from its glucuronide by intestinal bacterial hydrolases. The four pyrrole rings are linked by three methylene groups. *See also* **stercobilinogen**.

urocanase EC 4.2.1.49; a cytosolic enzyme of liver that converts *trans*-urocanic acid to 4-imidazole-5-propionic acid. Enzyme deficiency results in the rare autosomal recessive anomaly **urocanic aciduria**, which may be associated with mental retardation.

urocanic aciduria *see* **urocanase**.

urocanoate 4-imidazoleacrylate; 3-(1*H*-imidazol-4-yl)propenoate: an intermediate in the degradation of L-histidine by **histidine ammonia-lyase** with the elimination of ammonium.



urocanic acid

urocortin a neuropeptide that has 45% sequence identity with corticotropin-releasing hormone (**CRH**). It binds CRH receptors and is more potent than CRH in suppressing appetite.

urodilatin a 32-amino-acid peptide, isolated from human urine, that is identical in sequence to human **natriuretic peptide** (ANP), but with an N-terminal Thr-Ala-Pro-Arg tetrapeptide extension. It has actions similar to ANP.

uroflavin 1 *or* **uroflavine** *a former name for* **riboflavin**. 2 *an alternative name for* **aquaflavin**.

urogastrone a protein present in human urine that potently inhibits gastric secretion. It is **epidermal growth factor**.

urokinase a proteolytic enzyme found in urine, blood, and kidney cells, that converts **plasminogen** to **plasmin**. *See* **plasminogen activator**.

uromodulin *another name for* **Tamm–Horsfall glycoprotein**.

uronate 1 the anion of uronic acid. 2 any mixture of a uronic acid and its anion. 3 any salt or ester of a uronic acid.

uronic acid any monocarboxylic acid formally derived by oxidizing to a carboxyl group the terminal hydroxymethylene group either of an **aldose** having four or more carbon atoms in the molecule, or of any glycoside derived from such an aldose. The carbon atom of the (potential) aldehydic carbonyl group is numbered C-1.

uropontin *see* **osteopontin**.

uroporphyrin-III *C*-methyltransferase EC 2.1.1.107; *systematic name*: *S*-adenosyl-L-methionine:uroporphyrin-III *C*-methyltransferase (*abbr.*: SUMT); *other names*: urogen-III methylase; uroporphyrin-III methylase. An enzyme that catalyses a reaction between two molecules of *S*-adenosyl-L-methionine and uroporphyrin III to form two molecules of *S*-adenosyl-L-homocysteine and sirohydrochlorin. It forms part of **siroheme synthase**, which is involved in the biosynthesis of siroheme and cobalamin.

uroporphyrinogen decarboxylase EC 4.1.1.37; *systematic name*: uroporphyrinogen-III carboxy-lyase. A cytosolic enzyme that catalyses the decarboxylation of uroporphyrinogen-III to coproporphyrinogen with loss of four molecules of CO_2; this converts the four carboxymethyl groups of uroporphyrinogen to methyl groups, and is a step in heme synthesis. The crystal structure of the human enzyme (367 amino acids) is available. Mutations in the gene at 1p34 result in enzyme deficiency and the autosomal dominant diseases porphyria cutanea tarda and hepatoerythropoietic porphyria. *See* **porphyria**.

uroporphyrinogen-III synthase EC 4.2.1.75; *systematic name*: hydroxymethylbilane hydro-lyase (cyclizing); *other names*: uroporphyrinogen-III cosynthetase; uroporphyrinogen-III cosynthase. A cytosolic enzyme that catalyses the conversion of hydroxymethylbilane to uroporphyrinogen-III and H_2O. There are two isoforms of the human enzyme (both contain 265 amino acids), derived from the same gene. Many mutations lead to enzyme deficiency and erythropoietic porphyria.

urothione a thienopterin metabolic degradation product of molybdopterin. It is present in human urine, but is undetectable in molybdenum cofactor deficiency.

URR *abbr. for* **untranslated region**.

ursodeoxycholate *or* **ursodiol** 3*α*,7*β*-dihydroxy-5*β*-cholan-24-oate; an epimer of **chenodeoxycholate** found in the bile of bears (hence the name, from Ursidae), as a conjugate with taurine. It prevents the synthesis and absorption of cholesterol and can lead to the dissolution of gallstones.



ursodiol *an alternative name for* **ursodeoxycholate**.

USA *abbr. for* upstream stimulatory activity; the functional characteristic of a protein that binds an **upstream activator sequence** in a yeast gene and stimulates transcription of the gene by RNA polymerase II.

Usher syndrome an autosomal recessive syndrome of retinitis pigmentosa associated with various hearing disorders, depending on the type of syndrome: **type I** involves vestibular dysfunction and congenital deafness; **type II**, the commonest, involves partial hearing loss; and **type III** is associated with progressive hearing loss. Six genes are associated with subtypes of type I (that for myosin VIIA in type IB, and that for harmonin in type IC); one gene is responsible for type II and encodes an extracellular matrix protein (≈1500 amino acids) of retina and other tissues; and one gene is responsible for type III. [After Charles Howard Usher (1865–1942), British ophthalmologist.]

U-snRNA *abbr. for* uridylate-rich small nuclear RNA; a family of snRNA molecules, often designated U1 to U6 snRNA, that contain 100–215 nucleotides and a 'capped' 5′ end. They usually occur as small nuclear ribonucleoprotein particles. Their function may be related to splicing heterogeneous nuclear RNA (hnRNA) to mature mRNA.

USP *abbr. for* United States Pharmacopeia.

USPHS *abbr. for* United States Public Health Service.

UT *abbr. for* urea transporter.

uterine metalloendopeptidase *see* **matrilysin**.

uteroglobin *or* **blastokinin** a steroid-inducible secreted protein regulator of progesterone concentrations reaching the blastocyst and a potent inhibitor of phospholipase A_2. It is a disulfide-linked homodimer.

uterus (*pl.* **uteri**) a muscular part of the reproductive tract of female mammals (except Monotremata) that contains the developing embryo and fetus during pregnancy. —**uterine** *adj.*

UTP *abbr. for* uridine (5′-)triphosphate.

UTP–glucose-1-phosphate uridylyltransferase EC 2.7.7.9; *sys-*

tematic name: UTP:α-D-glucose-1-phosphate uridylyltransferase; *other names*: UDPglucose pyrophosphorylase; glucose-1-phosphate uridylyltransferase. An enzyme that forms uridinediphosphoglucose; it catalyses a reaction between UTP and α-D-glucose 1-phosphate to form UDPglucose and pyrophosphate.

UTP–hexose-1-phosphate uridylyltransferase EC 2.7.7.10; *systematic name*: UTP:α-D-hexose-1-phosphate uridylyltransferase; an enzyme that can form uridinediphosphogalactose. It catalyses a reaction between UTP and α-D-galactose 1-phosphate to form UDPgalactose and pyrophosphate. The sugar substrate α-D-glucose 1-phosphate can also act (but more slowly) as an acceptor, forming uridinediphosphoglucose. Deficiency of the enzyme in infancy causes a mild form of **galactosemia**.

UTP–xylose-1-phosphate uridylyltransferase EC 2.7.7.11; *other name*: xylose-1-phosphate uridylyltransferase; an enzyme that catalyses a reaction between UTP and α-D-xylose 1-phosphate to form UDPxylose and pyrophosphate.

UTR *abbr. for* untranslated region.

utrophin *or* **dystrophin-related protein** (*abbr*.: DRP) a protein that is highly similar to **dystrophin**, and found in normal adult human muscle, primarily at the neuromuscular junction. In the absence of dystrophin, in Duchenne muscular dystrophy, it is also present in the sarcolemma. It is an actin-binding protein related to α-**actinin**. Both gene and protein sequences resemble those for dystrophin. Over-expression of utrophin in a dystrophin-deficient (*mdx*) mouse demonstrates that it can functionally replace dystrophin; it has been suggested that this could offer a therapeutic strategy for Duchenne muscular dystrophy.

UUA a codon in mRNA for L-leucine.

UUC a codon in mRNA for L-phenylalanine.

UUG a codon in mRNA for L-leucine.

UUU a codon in mRNA for L-phenylalanine.

UV *or* **uv** *abbr. for* ultraviolet (radiation).

UV crosslinking a method whereby short exposure (1 min) to ultraviolet (UV) light (254 nm) causes RNA or DNA immobilized on nitrocellulose or nylon membranes to become covalently attached to the membrane.

uvomorulin *or* **epithelial cadherin** *or* **E-cadherin** a type I membrane protein and **cadherin** of non-neural epithelial tissues.

uvr any of four genes in *Escherichia coli* that are induced by the **SOS repair** system and whose products are involved in the repair of damage to DNA caused by UV light and DNA-reactive chemicals. Three of these genes, *uvrA*, *uvrB*, and *uvrC*, encode the three subunits of the ABC excision nuclease; this recognizes the structural distortion created by a **thymine dimer** and cleaves the damaged strand at two sites, about 12 nt apart, leaving a gap that is subsequently filled by polymerase and ligase action. Because the enzyme cuts at two sites it is not a classical endonuclease, but is referred to as an **excinuclease**. The fourth gene, *uvrD*, encodes a DNA helicase with ATPase activity, similar to the *rep* (*see* **RepA**) gene product; it promotes the ATP-dependent unwinding of the DNA duplex during repair.

UWGCG *abbr. for* University of Wisconsin Genetics Computer Group. *See* **GCG**.

Vv

v *symbol for* **1** specific volume. **2** volume (alternative to V). **3** velocity of reaction (i.e. **rate of reaction**); a subscript (in small capital letters) may be added (e.g. v_A) to denote rate of consumption, or rate of formation, of a specified reactant (e.g. A). **4** initial velocity of an enzymic reaction; *see also* **v_0**. **5** (bold italic) velocity (alternative to u, w, or c).

v_0 *symbol for* initial velocity (i.e. initial rate) of an enzymic reaction. The subscript may be omitted when rates at other times are not in question.

v_i *symbol for* chemical flux through the (enzymic) step with rate constant k_i . Similarly, flux through steps with rate constants k_{-i} or k_{ij} are denoted by $v_{-\mathrm{i}}$ and v_{ij} respectively.

v_{max} *symbol for* the true maximum value of the **rate of reaction**. *Compare* **V_{max}**.

V *symbol for* **1** volt. **2** a residue of the α-amino acid L-valine (alternative to Val). **3** vanadium. **4** *the recommended symbol for* **limiting rate**.

V *symbol for* **1** electric potential. **2** potential energy. **3** volume (alternative to v). **4** *the recommended symbol for* **limiting rate**.

V_m *symbol for* molar volume.

V_M *symbol for* hold-up volume.

V_{max} *symbol for* maximum velocity (i.e. **limiting rate**) of an enzyme reaction (alternative to V).

Vac *symbol for* vaccenic acid.

Vac A a toxin secreted by *Helicobacter pylori* that is the major virulence factor in human gastric ulcer formation.

vaccenate 1 *numerical symbol*: 18:1(11); *the trivial name for* either of the isomers (*cis*-vaccenate and *trans*-vaccenate) of octadec-11-enoate, $CH_3–[CH_2]_5–CH{=}CH–[CH_2]_9–COO^–$, the anions derived from *cis*-vaccenic acid, (*Z*)-octadec-11-enoic acid, and *trans*-vaccenic acid, (*E*)-octadec-11-enoic acid, a stereoisomeric pair of monounsaturated straight-chain higher fatty acids. *See also* **octadecenoic acid**. **2** any mixture of either *cis*- or *trans*-vaccenic acid and its corresponding anion. **3** any salt or ester of either isomer of vaccenic acid.

vaccenoyl *symbol*: Vac; *the trivial name for* either of the isomers (*cis*-vaccenoyl and *trans*-vaccenoyl) of octadec-11-enoyl, $CH_3–[CH_2]_5–CH{=}CH–[CH_2]_9–CO–$, the acyl groups derived from *cis*-vaccenic acid, (*Z*)-octadec-11-enoic acid, and *trans*-vaccenic acid, (*E*)-octadec-11-enoic acid. The *cis*-vaccenoyl group is a major fatty-acyl component of many bacterial lipids and a constituent of the oils of marine organisms. The *trans*-vaccenoyl group is present in a minor proportion of the acylglycerols in the body and milk fats of ruminants.

vaccination the process of administering a **vaccine** to produce immunity.

vaccine any preparation of immunogenic material suitable for the stimulation of active immunity in animals without inducing disease. Vaccines may be based on dead or attenuated microorganisms; altered toxins (toxoids); or viruses.

vaccinia virus a DNA virus and the type species of the genus *Orthopoxvirus* (or 'vaccinia subgroup'), which also includes the viruses responsible for cowpox, buffalopox, catpox, mousepox, and (formerly) smallpox (variola virus). Vaccinia infection usually causes only mild symptoms. Because of its serological similarity to the smallpox virus, vaccinia virus was formerly used as the basis of a live vaccine to protect humans against smallpox. Engineered vaccinias with surface antigens of hepatitis B, influenza virus, and vesicular stomatitis virus (which kills cattle, horses, and pigs) have produced useful vaccines in animal tests. However, adverse reactions with vaccinia-virus vaccines are well documented.

vacuolar apparatus the cellular digestive system, consisting of **lysosomes** and closely related, hydrolase-free, vacuolar structures. It is concerned with the digestion of both endogenous and exogenous materials.

vacuolar ATPase an enzyme of the synaptic vesicle membrane that pumps protons into the vesicle as it loses acetylcholine during nerve transmission; subsequently, the hydrons are released as the vesicle is recharged with acetylcholine. The enzyme (at least 10 subunits) resembles **H^+-transporting ATP synthase**, but functions as a proton pump.

vacuolar sorting protein *or* **vacuolar protein sorting-associated protein** (*abbr.*: vps); any of numerous proteins that are involved in the vesicle-mediated transfer of enzymes to the yeast vacuole. Many share similarity with proteins from higher eukaryotes.

vacuole a closed structure, found only in eukaryotic cells, that is completely surrounded by unit membrane and contains liquid material. Plant cells contain a conspicuous vacuole, which may occupy up to 95% of the cell volume. In these cells it has a role similar to that of lysosomes of animal cells, being rich in hydrolytic enzymes (especially various types of protease). In seed reserve tissues, specialized protein storage vacuoles contain abundant storage protein deposited during seed maturation. Upon germination, a specific protease is imported to supply amino acids to the new seedling. *Compare* **vesicle**.

vacuum (*pl.* **vacuums** *or* **vacua**) a space containing a gas at low pressure; i.e. a space in which there are relatively few atoms or molecules. A **perfect vacuum** would contain no atoms or molecules, but this is unobtainable owing to the vapour pressure of materials containing any vaccum. Vacuums may be classified into **low** (or **soft**) **vacuum**, $>\approx 10^{-2}$ Pa; **high** (or **hard**) **vacuum**, $10^{-2}–10^{-7}$ Pa; and **ultra-high vacuum**, $<10^{-7}$ Pa.

vacuum evaporation a technique for depositing a thin film of some solid material on a surface by evaporating the material at a high temperature in a vacuum. Atoms leaving the hot material travel directly to the cool surface to form a coating without colliding with other molecules in the gas phase; they condense on the cool surface and build up a layer of solid. *See also* **shadow casting**.

vacuum ultraviolet *see* **ultraviolet radiation**.

vagusstoff *the German name for* 'active factor'; a factor first demonstrated in 1903 (by German-born US physiologist Otto **Loewi** (1873–1961)) to be secreted into plasma after stimulation of the vago-sympathetic trunk and to inhibit cardiac function. It was later identified as **acetylcholine** by British physiologist (Sir) Henry Hallett Dale (1875–1968).

Val *symbol for* **1** the α-amino acid L-valine (alternative to V). **2** the (*cis*- or *trans*-) vaccenoyl group.

valency *or (esp. US)* **valence 1** the numerical combining power of an atom (and thus of a chemical element), ion, or chemical group, equal to the number of hydrogen atoms that the atom, ion, or group could combine with or replace. *See also* **covalence**, **electrovalence**. **2** the number of antigenic determinants with which one antibody molecule, or fragment thereof, will combine.

valerate 1 *the trivial and preferred name for* pentanoate; the anion, $CH_3–[CH_2]_3–COO^–$, derived from valeric acid (i.e. pentanoic acid). **2** any mixture of free valeric acid and its anion. **3** any salt or ester of valeric acid.

valeryl *symbol*: Vl; *the trivial name for* pentanoyl; the acyl group, $CH_3–[CH_2]_3–CO–$, derived from valeric acid (i.e. pentanoic acid).

valinate 1 valine anion; the anion, $(CH_3)_2CH–CH(NH_2)–COO^–$, derived from **valine**. **2** any salt containing valine anion. **3** any ester of valine.

valine *the trivial name for* α-aminoisovaleric acid; α-amino-β-methylbutyric acid; 2-amino-3-methylbutanoic acid; $(CH_3)_2CH–CH(NH_2)–COOH$; a chiral α-amino acid. L-valine (*symbol*: V *or* Val), (*S*)-2-amino-3-methylbutanoic acid, is a coded amino acid found in peptide linkage in proteins; codon: GUA, GUC, GUG, or GUU. In mammals, it is an essential dietary amino acid, and is glucogenic. Residues of D-valine (*symbol*: D-Val *or* DVal), (*R*)-2-amino-3-methylbutanoic acid, occur in a number of peptide antibiotics: e.g., in several members of the actinomycin family; gramicidins A, B, C, and D; and valinomycin (the latter also contains residues of L-valine).



L-valine

valine–isoleucine aminotransferase *see* **valine–3-methyl-2-oxovalerate aminotransferase**.

valine–3-methyl-2-oxovalerate aminotransferase EC 2.6.1.32; *recommended name*: valine–3-methyl-2-oxovalerate transaminase; *other names*: valine–isoleucine transaminase; valine– isoleucine aminotransferase; an enzyme that catalyses the reaction:

L-valine + (*S*)-3-methyl-2-oxopentanoate =
3-methyl-2-oxobutanoate + L-isoleucine.

See also **transamination**.

valinium valine cation; the cation $(CH_3)_2CH–CH(NH_3^+)–$ COOH, derived from **valine**.

valino the alkylamino group, $(CH_3)_2CH–CH(COOH)–NH–$, derived from **valine**.

valinomycin a cyclic 12-residue depsipeptide antibiotic that consists of three moieties, each having one molecule each of L-valine, D-α-hydroxyvaleric acid, D-valine, and L-lactic acid. The D-valine carboxyl group is directly linked to the α-carbon of L-lactic acid. Valinomycin is produced by *Streptomyces fulvissimus* and is active especially against *Mycobacterium tuberculosis*. It forms an ionophore by folding to produce a hydrophobic surface with an interior that binds Rb^+, Cs^+, NH_4^+, or, especially, K^+. It interferes with oxidative phosphorylation by rendering the mitochondrial membrane permeable to K^+ ions.

valium *see* **diazepam**.

valproic acid 2-propylpentanoic acid; $(CH_3–CH_2–CH_2)_2CH–COOH$; an antiepileptic, also used as sodium valproate (*one proprietary name*: Epilim).

valyl the acyl group, $(CH_3)_2CH–CH(NH_2)–CO–$, derived from **valine**.

VAMP *abbr. for* vesicle-associated membrane protein (i.e. **synaptobrevin**).

vanadyl ribonucleoside complex an inhibitor of ribonucleases sometimes used in the isolation of RNA from cells and tissues.

vancomycin a complex glycopeptide, $C_{66}H_{75}Cl_2N_9O_{24}$, from *Streptomyces orientalis*. It inhibits a specific step in the synthesis of the peptidoglycan layer in the Gram-positive bacterium *Staphylococcus aureus*. It is synthesized by a multimodular nonribosomal peptide synthetase. *See also* **vancosamine**.

vancosamine the aminodeoxysugar 3-amino-2,3,6-trideoxy-3-*C*-methyl-L-*lyxo*-hexose; the carbohydrate component of **vancomycin**.

van den Bergh reaction a reaction for the determination of **bilirubin** that depends on the formation of a red azo dye by bilirubin and diazotized sulfanilic acid. A **direct reaction** in aqueous solution is given by bilirubin glucuronide, and an **indirect reaction** is given in alcoholic solution by free bilirubin. [After A. A. Hijmans van den Bergh (1869–1943), Dutch physician.]

van der Waals force a long-range force between molecules or submolecular groups, effective from >50 nm to interatomic spacings. Such forces are always present, but weak, and often compete with electrostatic forces. In general they do not follow a simple power law; e.g. the force may be attractive at large separations but repulsive at small ones, or vice versa. The van der Waals free energy between two molecules or submolecular groups usually depends on their mutual orientation, i.e. these forces tend to align two molecules so as to minimize their free energy of interaction. [After Johannes Diderik van der Waals (1837–1923), Dutch physicist.]

van der Waals radius one half of the internuclear distance between atoms at equilibrium when the long-range attractive forces balance the short-range repulsive forces. It is larger than the atom's covalent radius and is about equal to the ionic radius of monovalent ions.

Van Dyke protein *an old name for* **neurophysin**.

vanilloid receptor *see* **capsaicin**.

vanillylmandelate *see* **hydroxy-methoxymandelate**.

Van Slyke apparatus **1** a volumetric apparatus formerly widely used for the determination of oxygen and carbon dioxide contents of blood samples. **2** an apparatus for the gasometric determination of aliphatic amino-nitrogen, e.g. in proteins, by measurement of the nitrogen gas evolved on reaction with nitrous acid. [After Donald Dexter Van Slyke (1883–1971), US biochemist.]

van't Hoff equation *or* **van't Hoff isochore** a relation describing the temperature variation of an equilibrium constant, *K*, of a reaction in terms of the change in heat content, $\Delta H'$, i.e. in terms of the heat of reaction at constant pressure. It is: $d\ln K/dT = \Delta H/RT^2$, where *R* is the gas constant and *T* the thermodynamic temperature. [After Jacobus Henricus van't Hoff (1852–1911), Dutch physical chemist.]

van't Hoff law the principle that the osmotic pressure exerted by a solute is equal to the pressure the solute would exert if it were an ideal gas at the same temperature as the solution and of the same volume. Hence $\Pi V = RT$, where Π is the osmotic pressure, *V* is the volume of solution containing 1 mole of solute, *R* the gas constant, and *T* the thermodynamic temperature.

van't Hoff limiting law a relation giving the limiting value for the osmotic pressure exerted by an ideal solute:

$$\text{limit } (c \rightarrow 0)\ \Pi = RT/M_r,$$

where Π is the osmotic pressure, *c* the solute concentration, M_r the relative molecular mass of the solute, *R* the gas constant, and *T* the thermodynamic temperature.

varanic acid *or* **3α,7α,12α,24β-tetrahydroxycholestanic acid** an intermediate (as the CoA ester) in the beta oxidation of the side chain of trihydroxycholestanoyl-CoA to choloyl-CoA in the synthesis of cholic acid. It accumulates in some peroxisomal defects, e.g. in D-bifunctional enzyme deficiency. *See* **peroxisomal bifunctional enzyme**.

variable **1** liable to change; having a range of possible values; liable to deviate from an established type. **2** something that is subject to variation; a quantity or function that can assume any of a set of specified values; a symbol for any unspecified number or quantity.

variable arm *an alternative name for* **extra arm** of tRNA.

variable number tandem repeats *abbr.*: VNTR; a multiallelic DNA polymorphism that results from insertions or deletions of DNA between two **restriction sites**. The existence of these repeats is exploited in **genetic profiling**.

variable region *symbol*: V; a region within a chain of an **immunoglobulin** molecule having an amino-acid sequence that characteristically varies between molecules of the same immunoglobulin class. There are typically four variable regions: the N-terminal halves of the two **light chains** (V_L) and the N-terminal halves of the **Fd fragments** (V_H) of the two heavy chains. The amino-acid sequences of these variable regions determine the structure of the antibody-combining site. *Compare* **constant region**.

variance a measure of the dispersion of a population, the mean square average of the deviations from the **mean**. It is the square of the **standard deviation**, σ, of that population.

variant **1** something that deviates from the norm; used especially of abnormal proteins (e.g., hemoglobins). **2** different; showing variation; used especially of different amino-acid residues in the corresponding positions of polypeptide chains from different sources.

variant Creutzfeldt–Jakob disease *abbr.*: vCJD; *see* **Creutzfeldt–Jakob disease**.

Vasa a protein of *Drosophila* that is required to activate the mRNA for oskar in oocytes.

vascular of, or relating to vessels that conduct fluid from one part of an organism to another, e.g. the blood vessels in animals, or the xylem and phloem in plants.

vascular cell adhesion molecule *see* **VCAM**.

vascular endothelial growth factor *abbr.*: VEGF; *also known as* **vascular permeability growth factor** *or* **vasculotropin**; a protein secreted by epithelial cells, macrophages, and smooth muscle cells, that is active in angiogenesis and endothelial cell growth; it induces endothelial proliferation and vascular permeability. Related to **platelet-derived growth factor**, it is a disulfide-linked homodimer.

vascular endothelial growth factor receptor *abbr*.: VEGF receptor; a type I membrane protein that contains seven immunoglobulin-fold domains in the extracellular segment. It is related to the platelet-derived growth factor receptor, with an intracellular bipartite tyrosine kinase domain.

vascular permeability growth factor *see* **vascular endothelial growth factor**.

vasculature the **vascular** system in animals.

vasculotropin *see* **vascular endothelial growth factor**.

vaso+ *comb. form* denoting a blood vessel.

vasoactive describing any agent that affects the diameter of blood vessels. *See also* **vasoconstrictor**, **vasodilator**.

vasoactive intestinal contractor *see* **endothelin**.

vasoactive intestinal polypeptide *abbr*.: VIP; a basic 28-residue peptide amide, similar to **gastric inhibitory polypeptide**, **glucagon**, and **secretin**, that is widely distributed in the body, mainly in nervous tissue (especially of the gut) and appears to be a neurotransmitter in **peptidergic** autonomic nerves. It has potent hypotensive and vasodilatory effects. It has the sequence

$$\text{HSDAVFTDNYTRLRKQMAVKKYLNSILN–NH}_2.$$

vasoactive intestinal polypeptide receptor *or* **vasoactive intestinal peptide receptor** any G-protein-associated membrane protein that binds **vasoactive intestinal polypeptide** (VIP) and mediates its intracellular effects. That of humans contains 362 residues. It activates adenylate cyclase; other endogenous ligands include peptide HI (PHI), GHRH, and secretin, the order of potency being VIP > PHI > GHRH > secretin.

vasoconstrictor a vasoactive agonist that causes **vasoconstriction**, i.e. a decrease in the diameter of blood vessels.

vasodilator a vasoactive agonist that causes **vasodilation**, i.e. an increase in the diameter of blood vessels.

vasopressin *or* **antidiuretic hormone** (*abbr*.: ADH); either of two nonapeptide hormones secreted by the neurohypophysis and similar to **vasotocin** and **oxytocin**. **[8-Arginine]vasopressin** (*abbr*.: [Arg^8]vasopressin *or* AVP) has the sequence

Cys-Tyr-Phe-Gln-Asn-Cys-Pro-Arg-Gly-amide,

with a disulfide bridge joining residues at positions 1 and 6. It raises blood pressure by constricting the peripheral arterioles and capillaries. It is also an antidiuretic, accelerating water reabsorption from the proximal region of the distal convoluted tubules of the kidney. AVP is released from a large precursor molecule, **vasopressin–neurophysin 2–copeptin precursor**, which includes its associated carrier protein (**neurophysin**). It is packaged into granules where the hormone is cleaved off and secreted into the blood in free form as required. Deficiency of AVP is the cause of autosomal dominant neurohypophyseal diabetes insipidus (ADNDI). The analogue, [8-lysine]vasopressin (*abbr*.: [Lys^8]-vasopressin), in which lysine is substituted for arginine at position 8, is formed, either singly or together with arginine vasopressin, in the pig family.

vasopressin–neurophysin 2–copeptin precursor the precursor of **vasopressin**, neurophysin 2 (*see* **neurophysin**), and copeptin. Copeptin is a glycopeptide (38 amino acids) that is released during processing of the precursor.

vasopressin receptor any G-protein-associated membrane receptor that binds [8-arginine]vasopressin (AVP; *see* **vasopressin**) and mediates its intracellular effects; peptides related to AVP, including **oxytocin**, are also bound. There are two types: V_1 – subdivided into V_{1a} (vascular/hepatic) and V_{1b} (anterior pituitary) – and V_2 (kidney); these can be distinguished pharmacologically on the basis of selective agonists. V_2 receptors are restricted to the kidney and are encoded at the locus for **nephrogenic diabetes insipidus**. V_1 receptors are coupled to phosphoinositide-specific phospholipase C, and V_2 receptors to adenylate cyclase. AVP is a more potent agonist for both V_1 and V_2 receptors than oxytocin. *See also* **oxytocin receptor**.

vasostatin either of two segments of **chromogranin A**. Vasostatin I comprises residues 1–76, lowers vascular tension, reduces secretion of parathyroid hormone, and is bacteriostatic and antifungal. Vasostatin II comprises residues 1–115 and has the first two properties of vasostatin I.

vasotocin a vasoactive peptide, closely related structurally to arginine **vasopressin** and **oxytocin**, that is secreted by the posterior pituitary gland in birds, reptiles, and some amphibians. It has the sequence

Cys-Tyr-Ile-Gln-Asn-Cys-Pro-Arg-Gly-amide,

with a disulfide bond between the two cysteines.

VASP *abbr. for* vasodilator-stimulated phosphoprotein; a substrate for cyclic AMP- and cyclic GMP-dependent protein kinases in platelets. It is associated with actin filaments and focal adhesions, and contains an EVH1 homology sequence that binds a proline-rich motif.

VAST *abbr. for* vector alignment search tool; *see* **database-search program**.

vault a large ribonucleoprotein complex of unknown function localized primarily in the cytoplasm of eukaryotic cells. Vaults contain **V-PARP**, MVP (major vault protein, which is also a substrate for V-PARP), and **TEP-1** (a protein of the telomerase complex). They increase in amount in multidrug-resistant cancers.

VCAM *abbr. for* vascular cell adhesion molecule; a class of **adhesion molecules** belonging to the immunoglobulin superfamily. The class is exemplified by VCAM-1 (CD106; molecular mass 90–110 kDa). This is expressed on endothelial cells, macrophages, dendritic cells, fibroblasts, and myoblasts, and is inducible within 6–10 h by interleukin 1β, interleukin 4, tumour necrosis factor α, or interferon γ. It binds to VLA-4 (*see* **VLA**) and integrin $\alpha_4\beta_7$ (*see* **integrin**), and mediates adhesion of lymphocytes, monocytes, and eosinophils to activated endothelium.

vCJD *abbr. for* variant **Creutzfeldt–Jakob disease**.

VCP *abbr. for* valosin-containing protein; the human homologue of yeast Cdc48. *See* ***cdc*** **gene**.

V(D)J recombinase *see* *RAG*.

VecScreen *see* **vector-screening program**.

vector 1 *or* **vector quantity** a quantity specified by its direction and sense as well as by its magnitude. **2** *(in pathology)* an organism that carries an organism of a different species from one place to another, especially one that transfers a **pathogen** between hosts, either mechanically (**mechanical vector**) or by playing a specific role in the pathogen's life cycle (**biological vector**). *Compare* **vehicle** (def. 2). **3** *(in genetics) see* **cloning vector**.

vector database a repository of known vector sequences used by vector-screening programs to identify sequence contaminants; an example is UniVec.

vectorette PCR a method based on the **polymerase chain reaction** (PCR) used for amplifying an unknown DNA sequence adjacent to a known DNA sequence. It was previously used in **chromosome walking** but still finds application in recovering sequences adjacent to mutations caused by insertional mutagenesis. The double-stranded vectorette is ligated to the ends of restriction fragments thereby introducing a known sequence that can be used to prime one side of a PCR reaction, the other being primed on the known genomic sequence.

vectorial enzyme any enzyme, such as one fixed in a membrane, that is directional in its action, e.g. **sodium/potassium ATPase**.

vectorial processing processing of a fully formed precursor polypeptide into a mature protein when used to drive the movement of the protein from one aqueous compartment (e.g. the cytoplasm) through a membrane into a second aqueous compartment (e.g. an intramitochondrial or intrachloroplastal space). *Compare* **vectorial translation**.

vectorial translation the stage of **translation** in the biosynthesis of any protein destined for export from a cell, where a nascent polypeptide being produced on a **polysome** bound to the membrane of the rough endoplasmic reticulum in a eukaryote is conducted through the membrane by its N-terminal **signal peptide**. *Compare* **vectorial processing**.

vector-screening program a program that uses a database of known vector sequences to screen sequences for vector contaminants; an example is VecScreen.

vegetal hemisphere glycoprotein 1 *abbr*.: Vg-1; a glycoprotein of the TGF-β family (*see* **transforming growth factor**) that facilitates the differentiation of either mesoderm or endoderm.

vegetal pole the end at which most of the yolk is located e.g. in an amphibian egg; the end opposite the **animal pole**.

vegetative describing cells or tissues that are engaged in nutrition and growth rather than sexual reproduction, and excluding dormant forms.

vegetative bacteriophage the intrabacterial genome of a **bacteriophage** when it is noninfective but controlling the synthesis by the host of components needed to make new infective bacteriophage particles.

vegetative reproduction **1** *(in plants)* a form of **asexual reproduction** in which new individuals develop from specialized multicellular organs (e.g. bulbs, corms, tubers) that break off from the parent plant. **2** *(sometimes)* a term used to describe **budding** (def. 2) and similar forms of asexual reproduction in animals such as coelenterates and sponges.

VEGF *abbr. for* vascular endothelial growth factor.

vehicle **1** any inert medium with which a biologically active substance (e.g. a drug) is mixed or in which it is dissolved, suspended, or emulsified in order to increase its bulk and/or to facilitate its absorption after administration. **2** any agent (animate or inanimate) of transmission, especially of infection; *see also* **vector** (def. 2).

vein **1** *(in animals)* the blood vessels conducting blood from the tissues. **2** *(in plants)* a vascular bundle in a leaf.

velocity of reaction *an alternative name for* **rate of reaction**.

venom any toxic animal secretion that is produced by discrete glands and is delivered by a specific mechanism for defensive or offensive purposes.

venombin either of two serine proteinases found in snake venom. **Venombin AB** EC 3.4.21.55; *other name*: gabonase (from the venom of the gaboon viper, *Bitis gabonica*); it cleaves Arg-|-Xaa bonds in fibrinogen to form fibrin and release fibrinopeptides A and B; it is not inhibited by antithrombin III or hirudin. **Venombin A** EC 3.4.21.74; it cleaves Arg-|-Xaa bonds in fibrinogen to form fibrin and release fibrinopeptide A, but further reaction depends on species; it is a trypsin-like enzyme.

venous of, or relating to, a **vein**, or to the blood in the veins.

ventilation the passage of air into and out of the respiratory tract, or other confined space.

Ventolin *see* **sambutamol**.

Vent polymerase *or* **Deep Vent polymerase** *the proprietary name for* thermostable DNA polymerases used as alternatives to ***Taq* DNA polymerase** in the **polymerase chain reaction**. They have a higher fidelity than the *Taq* DNA polymerase, derived in part from their exonuclease activity. They derive from the archaean *Thermococcus litoralis*, isolated from a submarine thermal vent, hence the enzyme's name.

ventral situated towards the belly surface of an animal.

verapamil α-3- [2-(3,4-dimethoxyphenyl)ethyl]methylamino propyl-3,4-dimethoxy-α-(1-methylethyl)benzeneacetonitrile; iproveratril; D365; a Ca^{2+}-blocking agent used in the treatment of cardiac disorders and to inhibit the movement of calcium ions across biological membranes. It acts like **nifedipine, which** binds to the dihydropyridine binding site of vascular voltage-operated **calcium channels;** verapamil probably acts at another related site. *See also* **D600**.



veratridine a toxic alkaloid, $C_{36}H_{51}NO_{11}$, found in the seeds of *Schoenocaulon officinalis* (of the lily family) and in the rhizome of *Veratrum album*. It blocks the development of the action potential involved in axonal conduction, binding to the Na$^+$ channels and blocking them in the open configuration.



veratidine

veratryl alcohol 3,4-dimethoxyphenol, a compound derived from the breakdown of lignin. Is a substrate for lignin peroxidase, becoming oxidized to a cation radical that attacks the lignin structure.



v-erbA related protein *see* **COUP**.

verbascose the tetrasaccharide, *O*-α-D-galactopyranosyl-(1→6)-*O*-α-D-galactopyranosyl-(1→6)-*O*-α-D-glucopyranosyl-(1→2)-β-D-fructofuranoside. It occurs in roots of the mullein, *Verbascum thapsus*.

verdoperoxidase *see* **myeloperoxidase**.

verification **1** establishment of the correctness of a theory, fact, etc. **2** a term used to describe the deacylation of misacylated tRNA molecules by the specific aminoacyl-tRNA synthase.

Verner–Morrison syndrome *or* **pancreatic cholera** a syndrome of humans characterized by severe watery diarrhoea, achlorhydria or hypochlorhydria, weight loss, and dehydration. It is caused by tumours (**VIPomas**), mostly of pancreatic origin (some are neurogenic), that produce **vasoactive intestinal polypeptide** (VIP), the circulating levels of which are raised. [After John Victor Verner (1927–), US physician and Ashton Byrom Morrison (1922–), US pathologist.]

Veronal *a proprietary name for* **barbital**.

verotoxin a pentameric pore-forming toxin (5 × 89 amino acid residues) belonging to the shiga toxin B family (TC 1.C.54).

Versene *a proprietary name for* the tetrasodium salt of **edetate**.

versican *or* **large fibroblast proteoglycan** *or* **chondroitin sulfate proteoglycan core protein 2** a protein involved in intercellular signalling. The N-terminal part is similar to a glial hyaluronate-binding protein; the middle contains glucosaminoglucan attachment sites; the C-terminal part contains EGF-like repeats (*see* **epidermal growth factor**) and a lectin-like domain.

vertical rotor a rotor for use in an **ultracentrifuge**. The wells holding the tubes are drilled parallel to the axis of rotation and at right angles to the lines of the centrifugal force.

very-long-chain acyl-CoA dehydrogenase an acyl-CoA dehydrogenase that is specific for acyl moieties 14–22 carbons long. The human enzyme contains 615 residues and FAD, and occurs as a homodimer associated with the matrix side of the inner mitochondrial membrane. Many mutations result in deficiency and a clinical presentation that resembles **Reye syndrome**.

very-low-density lipoprotein *abbr.*: VLDL; a class of lipoproteins found in blood plasma in many animals (data normally relate to humans). VLDL is also known as pre-beta lipoprotein because its electrophoretic mobility is slightly greater than that of low-density, or beta-lipoprotein. VLDL particles have diameter 25–70 nm, solvent density for isolation (g mL^{-1}) <1.006, hydrated density (g mL^{-1}) 0.97. Their approximate composition (% by weight) is 5–8% unesterified cholesterol, 11–14% esterified cholesterol, 20–23% phospholipid, 44–60% triacylglycerol, 4–11% protein. Their apolipoprotein composition (% by weight total apolipoprotein) is 36.9% B-100, 49.9% C-I + C-II + C-III, 13% E-II + E-III + E-IV. They are synthesized in liver and are the precursor of low-density lipoprotein.

very-low-density-lipoprotein receptor *abbr.*: VLDL receptor; a membrane protein that binds VLDL, accumulates in clathrin-coated pits, and internalizes VLDL. It has a large extracellular domain, a single transmembrane domain, and a small intracellular domain. In human the precursor protein consists of 873 amino acids; residues 1–27 are the signal, 28–797 constitute the extracellular domain, and 820–873 are the cytoplasmic domain.

vesicle a closed structure, found only in eukaryotic cells, that is completely surrounded by a unit membrane but, unlike a **vacuole**, contains material that is not (or is not known to be) in the liquid state.

Vg-1 *abbr. for* vegetal hemisphere glycoprotein 1.

VHDL *abbr. for* very-high-density lipoprotein.

VHL *abbr. for* von Hippel–Lindau protein; a 213-residue protein encoded at 3p25 by the gene for the **von Hippel–Lindau syndrome** of hereditary renal and other cancers. VHL binds **cullin**-2 and then **elongins** B and C, and the complex translocates to the nucleus. By sequestering elongins B and C it prevents formation of the heterotrimeric transcription factor elongin (which consists of elongins A, B, and C). But its proper function may be to target other nuclear proteins to ubiquitin-mediated degradation. Numerous mutations in the VHL gene are associated with sporadic and hereditary renal carcinoma, indicating that VHL is a tumour suppressor. [After Eugen von Hippel (1867–1939), German ophthalmologist, and Arvid Lindau (1892–1958), Swedish pathologist.]

viability a measure of the capacity of a cell for metabolism and division. It is often estimated experimentally by determining the number of cells that exclude normally membrane-impermeant dyes, e.g. **Trypan Blue**.

Viagra *a proprietary name for* sildenafil; 5-[2-ethoxy-5-(4-methylpiperazin-1-yl)phenyl]-1-methyl-3-propyl-1,6-dihydro-7*H*-pyrazolo[4,3-d]pyrimidin-7-one; used for the oral treatment of male erectile dysfunction. It selectively inhibits a specific phosphodiesterase that hydrolyses cyclic GMP; the latter mediates the action of nitric oxide in normal erectile function, an action which is thus potentiated.

VIC *abbr. for* vasoactive intestinal contractor; *see* **endothelin**.

vic- *prefix (in chemical nomenclature)* denoting the presence of **vicinal** (def. 2) substituents.

vicianose the disaccharide 6-*O*-*α*-L-arabinosyl-D-glucose, obtained from a glycoside in seeds of *Vicia angustifolia*.



β-D-anomer

vicillinpeptidohydrolase *see* **legumain**.

vicinal 1 adjacent, neighbouring. **2** *(in organic chemistry)* describing two (usually identical) atoms or groups attached one to each of two linked carbon atoms in a molecule. The presence of vicinal substituents is denoted by the prefix *vic-* attached to the name of the compound. *Compare* **geminal**.

vicilin a major storage protein in seeds of *Pisum sativum* (pea); it comprises 124 amino acids, M_r 170 000. Legumin-like and vicilin-like globulins are the main storage proteins of most angiosperms and gymnosperms.

vidarabine adenine arabinoside; 9-*β*-D-arabinofuranosyladenine; a purine nucleoside, a metabolite of hypoxanthine arabinoside, produced by *Streptomyces antibioticus*. Its triphosphate derivative inhibits viral DNA polymerase and may be incorporated into viral DNA; it also inhibits DNA synthesis.



Vif *abbr. for* viral infectivity factor; a protein of HIV-1 that is essential for production of infectious viruses by T lymphocytes and macrophages.

vigabatrin *γ*-vinyl-*γ*-aminobutyric acid; *γ*-vinyl GABA; 4-amino-5-hexenoic acid; an irreversible inhibitor of the enzyme GABA transaminase (**4-aminobutyrate transaminase**), which metabolizes the neurotransmitter *γ*-amino-*n*-butyric acid.

vigilin a protein derived from chickens that contains 14 **KH domains**. There is a human homologue.

villin a Ca^{2+}-regulated actin-binding protein occurring in the microvilli of intestinal epithelial cells and kidney proximal tubule cells. Villin consists of a large core fragment, the N-terminal portion, and a small head-piece, the C-terminal portion; the head-piece binds F-actin (*see* **actin**) strongly in both the presence and absence of Ca^{2+}; it is similar to **gelsolin**.

vimentin a protein found in class III **intermediate filaments** in mesenchymal and other non-epithelial cells, and in the Z disk of skeletal and cardiac muscle cells. It is a phosphoprotein, phosphorylation being enhanced during cell division.

vinblastine an alkaloid, $C_{46}H_{58}N_4O_9$, obtained from *Vinca rosea*, that binds to spindle microtubules and arrests metaphase of mitosis. It is used as an antineoplastic agent.



vinblastine

vincristine an alkaloid, $C_{46}H_{56}N_4O_{10}$, obtained from *Vinca rosea* and structurally related to **vinblastine**, that binds to spindle microtubules and arrests metaphase of mitosis. It is used as an antineoplastic agent.



vincristine

vinculin a cytoskeletal protein associated with the cytoplasmic face of the focal adhesion plaques that anchor actin microfilaments to the plasma membrane and that attach a cell to the substratum. It associates with **talin** in binding **integrins** to the cytoskeleton. Vinculin is phosphorylated (on serines, threonines, and tyrosines) and acylated by myristic acid and/or palmitic acid. Vinculin and metavinculin are produced by alternative splicing of the same gene. Metavinculin differs from vinculin in having a 68-residue additional domain near the C terminus.

vindoline the major alkaloid from *Vinca rosea*; $C_{25}H_{32}N_2O_6$. It is without physiological activity but constitutes a pentacyclic moiety of **vinblastine** and **vincristine**.

vinyl ether alk-1-enyl ether; a class of compounds characterized by a bond formed between a long-chain aldehyde and one (in the case of monoalk-1-enyl ethers) or two (for dialk-1-enyl ethers) of the hydroxy groups of the glycerol moiety of a glycerolipid; only the *sn*-1 isomers occur naturally, and chains of 16 or 18 carbons are usual. Such glycerophospholipids are known as **plasmalogens**; ethanolamine glycerophospholipids characteristically contain larger amounts of plasmalogens than other classes, and heart tissue is rich in plasmalogens.

γ-vinyl GABA *see* **vigabatrin**.

viosamine 4-amino-4,6-dideoxy-D-glucose; a component of the lipopolysaccharide of some strains of *Escherichia coli*.

VIP *abbr. for* vasoactive intestinal polypeptide.

VIP36 *abbr. for* vesicular integral membrane protein 36 kDa; a mannose-specific lectin protein that resides in the Golgi apparatus.

VIPoma a tumour producing **vasoactive intestinal polypeptide** (VIP). It is often associated with a watery diarrhoea and other pathological signs known as **Verner–Morrison syndrome**.

viral infectivity factor *see* **Vif**.

viral particle *see* **virion**.

viral RNA RNA that constitutes the genome of certain viruses – the RNA viruses. Examples are poliovirus, which has single-stranded RNA, and cytoplasmic polyhedrosis virus of the tussock moth, which has 10 double-stranded RNA molecules. All **retroviruses** contain RNA as the genome.

virino a former name for a putative type of particulate, noncellular, submicroscopic, transmissible, pathogenic agent, typified by the agent responsible for **scrapie**. The infective particle was believed to consist of a small nucleic-acid molecule covered with host-specified protein. *See* **prion**.

virion *or* **viral particle** a complete virus particle, found extracellularly and capable of surviving in crystalline form and of infecting a living cell. It comprises the nucleic-acid **core** and the protein **capsid**; the latter may be enclosed by an **envelope** in some viral families.

virogene *see* **oncogene hypothesis**.

viroid any of about 30 autonomously replicating plant pathogens that consist of single-stranded (ss) circular RNA (about 350 nt) containing much self-complementarity. They have no genes, so do not express protein. It is assumed that the viroid RNA acts as its own template, subverting host cell enzymes to carry out the replication. The product consists of concatamers of daughter strands that undergo self-cleavage to form new viroid RNA genomes. It is likely that hammerhead structures (*see* **ribozyme**) are involved. An example is potato spindle tuber viroid (PSTV). This is similar to human hepatitis delta, which is part viroid and part virus in that it replicates like a viroid and part of its genome is homologous with PSTV.

virology the scientific study of viruses and the diseases caused by them. **—virological** *adj.*; **virologist** *n.*

viropexis the process by which virus particles are adsorbed onto the surface of a cell and then taken into the cytoplasm.

virtual organization *see* **VO**.

virtual screening *an alternative name for* **combinatorial chemistry**.

virulence the capacity of a microorganism or virus to cause disease in a host under certain conditions. **—virulent** *adj.*

virulent phage a bacteriophage that invariably lyses the bacterium it infects. Virulent phages have no alternative but to follow the **lytic cyle**.

virus a noncellular infective agent that reproduces only in an appropriate host cell. Viruses are typically smaller than bacteria, and can infect animal, plant, or bacterial cells (*see* **bacteriophage**); many are important agents of disease. The infective particle (**virion**) consists of a core of nucleic acid (either DNA or RNA) surrounded by a protein **capsid** and, in some cases, an outer envelope. A virus can interact with its host cell in several different ways. In a lytic interaction the cell's replicative and protein biosynthetic apparatus is directed by the viral genes to produce numerous progeny virions, which are released upon disintegration of the host cell (*see* **lytic cycle**). However, in a persistent infection, low levels of virus production may be sustained without destruction of the host cell. In a **latent infection**, the virus resides in a host cell without replicating, although it may be provoked to enter the lytic phase by some stimulus. Oncogenic viruses, which include both DNA viruses and RNA viruses (**retroviruses**) carry **oncogenes** and are potentially capable of transforming their host cells into tumour cells. Animal viruses are classified according to the nature of their genome and the mechanism of synthesis of messenger RNA (*see* **Baltimore classification**).

virusoids *see* **satellite RNA**.

visceral layer *see* **serous membrane**.

viscometer *or* **viscosimeter** an apparatus for measuring the viscosity or resistance to flow of a liquid.

viscosity *symbol*: η; the resistance to flow of a fluid due to the sum of the effects of adhesion and cohesion. Consider a liquid between two parallel plates, one of which is moving in the x direction with a velocity v. The liquid is thought of as a number of layers, each of which slides along the adjacent layer; the frictional resistance between adjacent layers generates a velocity gradient in the y direction. The deformation of the liquid produced by the velocity gradient is known as **shear** (def. 1). The frictional force, f, between the liquid layers is proportional to the area, A, of the layers and to the velocity gradient between them, such that $f = \eta\ A(\mathrm{d}v/\mathrm{d}y)$, where η is the **coefficient of viscosity** or simply the viscosity; $f/A = F$, the **shear stress**; and $\mathrm{d}v/\mathrm{d}y = G$, the **shear gradient** or **shear rate**. If η is independent of F or G, the fluid is a **Newtonian fluid**; if η is a function of F or G, the fluid is a **non-Newtonian fluid**.

viscotoxin a pore-forming toxin, permitting passage of small molecules across biomembranes. It is produced by various plants. It contains 45–47 amino acid residues organized in two antiparallel α-helices and two antiparallel β-strands. It is classified in the TC system under number 1.C.44.

visinin a calcium-binding protein specific to cone photoreceptors; a chicken isoform homologous to bovine **recoverin** has three Ca^{2+}-binding sites.

Visual Basic *see* **programming language**.

visual cascade the sequence of reactions occurring after the absorption of a photon by visual pigment (e.g. **rhodopsin**). It eventually leads to a rapid fall in cyclic GMP levels, which closes Na^+ channels in the membrane of the visual receptor and activates the nerve impulse in the optic nerve. The activated pigment stimulates the G-protein **transducin,** which initiates the signal-transduction cascade.

visualization software 1 any software that facilitates analysis and interpretation of data using simple visual metaphors (e.g. graphs, trees, 3D images). 2 *(in structure analysis)* software that allows visualization of 3D representations of molecular structures from multiple perspectives, using multiple modes (e.g. backbone trace, space-filled, surface) and multiple colour schemes; examples include MAGE, RasMol, and Cn3D. 3 *(in sequence analysis)* software that allows visualization of sequence properties (such as hydropathy profiles) or visualization and editing of sequence alignments: e.g. CINEMA (colour interactive editor for multiple alignments) and JalView.

visual pigment any of the homologous photosensitive retinal-containing transmembrane proteins of the retina that are responsible for vision. The rods contain **rhodopsin**, while the cones contain **cyanopsin**, **chloropsin**, or **porphyropsin**.

visual purple *see* **rhodopsin**.

vitalism the doctrine that the phenomena of biology are due to a vital principle distinct from physicochemical forces, and cannot be explained by the laws of physics and chemistry alone. The accidental discovery, in 1890, by the brothers Büchner that a cell-free extract of yeast could catalyse alcoholic fermentation did much to convince adherents that such a doctrine was untenable. Also important was Wohler's synthesis of urea from ammonium cyanate in 1828.

vital staining a technique in which living cells or tissues are exposed to a stain that does not kill them. Dyes such as Trypan Blue are excluded from live cells but stain dead cells thereby allowing the proportion of each in a population to be counted using a hemocytometer. Alternatively, the tetrazolium dye MTT stains live cells blue without killing them.

vitamer any of two or more chemically and metabolically related compounds that display qualitatively the same biological activity as a vitamin. For example, retinol, retinal, retinoic acid, 3,4-didehydroretinol, and various carotenes are all vitamers of vitamin A.

vitamin an organic substance that is present in foodstuffs (or in intestinal bacteria) in relatively minute amounts, is distinct from the main organic components of food (i.e. protein, carbohydrate, and fat), and is needed for the normal nutrition of the organism (or species) in question. Deficiency or absence of any vitamin causes a specific deficiency disease. **Vitamins A**, **D**, **E**, and **K** are the fat-soluble vitamins; **vitamins B_1**, **B_2**, **B_6**, **B_{12}**, and **C**, plus **biotin**, **choline**, **folic acid**, **nicotinic acid**, and panthothenic acid (*see* **pantothenate**), are the water-soluble vitamins.

vitamin A 1 *a common name for* **retinol**. 2 *a generic name for* any retinoid exhibiting qualitatively the biological activity of retinol. Included, besides retinol (relative activity 100) are: **retinal** (91); **retinoic acid** (≈65); **3,4-didehydroretinol** (40); **3,4-didehydroretinal**; and **3,4-didehydroretinoic acid** (the activities relative to retinol being measured by the standardized growth test on vitamin A-deficient rats). Vitamin A is fat-soluble, and is present in various lipid-containing animal preparations, especially liver and dairy products. Vitamin A activity is displayed also by various carotenes; these are provitamins, being converted to retinal in the small intestine in most vertebrates. The vitamin A of commerce was originally an extract from fish-liver oils, which contain large amounts of retinol, principally as its palmitate; it is now largely derived chemically. Proper vitamin A nutrition is necessary for: (1) somatic function, including growth and differentiation, e.g. of epithelial structures and bone; (2) reproduction, including spermatogenesis, oogenesis, placental development, and embryonic growth; and (3) visual processes (*see* **retinal**, **3,4-didehydroretinal**). Vitamin A deficiency causes stunted growth, thickening of various membranes by keratinization, and night blindness, xerophthalmia, keratomalacia, and eventually complete blindness. In moderate excess, vitamin A is highly toxic.



vitamin A_1 *an alternative name (not recommended) for* **retinol**.

vitamin A_2 *an alternative name (not recommended) for* **3,4-didehydroretinol**.

vitamin A acid *or* **vitamin A_1 acid** *an alternative name (not recommended) for* **retinoic acid**.

vitamin A_2 acid *an alternative name (not recommended) for* **3,4-didehydroretinoic acid**.

vitamin A alcohol *or* **vitamin A_1 alcohol** *an alternative name (not recommended) for* **retinol**.

vitamin A_2 alcohol *an alternative name (not recommended) for* **3,4-didehydroretinol**.

vitamin A aldehyde *or* **vitamin A_1 aldehyde** *an alternative name for (not recommended)* **retinal**.

vitamin A_2 aldehyde *an alternative name (not recommended) for* **3,4-didehydroretinal**.

vitamin B_1 *or* **thiamine** *or (sometimes)* **thiamin** *or (formerly)* **aneurin(e)** 3-(4-amino-2-methylpyrimidin-5-ylmethyl)-5-(2-hydroxyethyl)-4-methylthiazolium chloride;a water-soluble vitamin, present in fresh vegetables and meats, especially liver. Deficiency in humans causes beriberi, manifest as cardiopathy and neuropathy; in pigeons, a characteristic head-drop is an overt sign of deficiency. **Thiamine diphosphate** (*abbr*.: TPP), formerly known as **cocarboxylase**, is a coenzyme for oxidative decarboxylation and other enzymic reactions, including ones catalysed by pyruvate and oxo-glutarate dehydrogenases, pyruvate decarboxylase, and transketolase.



vitamin B_2 *or* **riboflavin** 6,7-dimethyl-9-ribitylisoalloxazine; *formerly also called* lactoflavin, hepatoflavin, ovoflavin, uroflavin, vitamin G, vitamin H. A water-soluble vitamin, present in most foods but especially in milk and meat products. It is a component of the **flavin nucleotide** coenzymes (e.g. FAD, FMN). Isolated from milk and eggs by Kuhn and co-workers in 1933 and chemically synthesized by them and others in 1935. Significant deficiency seldom



occurs, but causes changes of the tongue and lips and sores in the corners of the mouth.

vitamin B_5 *(rarely) an alternative name for* pantothenic acid; *see* **pantothenate**.

vitamin B_6 *or* **pyridoxine** 2-methyl-3-hydroxy-4,5-bis(hydroxymethyl)pyridine; a water-soluble vitamin; **pyridoxal** and pyridoxamine are vitamers. It is present in many foods, including meats (largely as pyridoxal or pyridoxamine), and plant sources (largely as pyridoxine) such as cereals, lentils, nuts, and vegetables. Pyridoxal phosphate is a coenzyme for enzyme reactions including those for transamination, amino-acid decarboxylation, racemization, and modifications to amino-acid side chains. Deficiency is a minor problem and signs are difficult to produce.



vitamin B_6

vitamin B_{12} *or* **cobalamin** *or* **cobamide** a water-soluble vitamin with several related forms characterized by possession of a **corrin** nucleus containing a cobalt atom. Four of the cobalt coordinate bonds are liganded by nitrogens of the four pyrrole rings found in the corrin nucleus; the fifth position is occupied by the ribonucleotide of 5,6-dimethylbenzimidazole, which is also linked via a 1-amino-2-propanol moiety to one of the pyrrole rings; the sixth position is variously occupied by a cyanide group (cyanocobalamin, the form in which the molecule was first isolated, the cyanide group having been introduced during extraction), or a methyl group (**methylcobalamin**, which is a coenzyme), or a 5′-deoxyadenosyl group (**deoxyadenosylcobalamin**, the other coenzyme form). Vitamin B_{12} is present only in foods of animal origin, especially liver, fish, and eggs. The coenzyme forms are needed for: (1) reactions that require the deoxyadenosyl form, exemplified by **methylmalonyl-CoA mutase**; and (2) reactions that require the methyl form, exemplified by 5-methyltetrahydrofolate-homocysteine *S*-methyltransferase (EC 2.1.1.13) (*see* **5-methyltetrahydrofolate**). In normal individuals, deficiency rarely occurs, but is precipitated by lack of **intrinsic factor**, a protein secreted by gastric mucosa and required for efficient absorption of the vitamin. Lack of intrinsic factor leads to **pernicious anemia**, investigation of which first led to the discovery of cobalamin.



cyanocobalamin

vitamin B_{12r} reductase *see* **cob(II)alamin reductase**.

vitamin C ascorbic acid; a water-soluble vitamin, and the first vitamin to be recognized. Awareness of the ability of fresh vegetables and fruit to prevent **scurvy** is attributed to the British physician James Lind (1716–94), who published *A Treatise on Scurvy* in 1757. The active compound was first isolated in 1928 by Albert Szent-Györgyi (1893–1986; Hungarian-born US biochemist) as 'hexuronic acid', a strong reducing substance from rat adrenals and citrus fruits. This was shown four years later to be identical with the anti-scorbutic substance isolated by Zilva and associates. Vitamin C is widely distributed in vegetables and fruit, but easily destroyed by cooking. *See* **ascorbic acid** for structure. *See also* **l-gulonolactone oxidase**.

vitamin D any steroid that exhibits the biological activity of calciol (= vitamin D_3 – *see below*); the antirachitic vitamin. Such compounds are fat-soluble and structurally related to either the parent hydrocarbon, **cholestane**, or its 24-methyl derivative, ergostane, and all are 9,10-seco-sterols, i.e. 3-hydroxysteroids in which bond breakage has occurred between C-9 and C-10 in ring B of the steroid nucleus. Variants of vitamin D, with their recommended trivial names in parentheses, are: **vitamin D_2** *or* calciferol (**ercalciol** *or* **ergocalciferol**), formed in plants by the action of UV light on the endogenous provitamin **ergosterol** and produced industrially by UV-irradiation of ergosterol isolated from yeast; **vitamin D_3** (**calciol** *or* **cholecaliferol**), occurring naturally in particularly high concentrations in the liver oils of certain fish, especially cod, halibut, or tunny, and produced nonenzymically in the skin of animals by the action of a UV component (230–313 nm) of sunlight on the provitamin 7-dehydrocholesterol; **vitamin D_4** (22,23-dihydroercalciol *or* (24*S*)-methylcalciol or (*formerly*) 22,23-dihydroergocalciferol), produced by irradiation of 22,23-dihydroergosterol; **vitamin D_5** ((24*S*)-ethylcalciol); and **vitamin D_6** ((22*E*)-(24*R*)-ethyl-22,23-didehydrocalciol). Of these variants, calciol (D_3) and ercalciol (D_2) are the most significant. Vitamin D activity is also displayed by several synthetic derivatives or isomers of calciol (or of ercalciol) and by the 25-hydroxylated and 1α,25-dihydroxylated metabolites **calcidiol** and **calcitriol** (or **ercalcidiol** and **ercalcitriol**). Calcidiol (or ercalcidiol) is formed in liver from calciol (or ercalciol) and converted in kidney to calcitriol (or ercalcitriol), the physiologically active form of vitamin D_3 (or D_2). Vitamin D mediates the absorption of calcium and phosphate ions from the intestine and promotes the mineralization of bone. The deficiency conditions of **rickets** (in children) and **osteomalacia** (in adults) may be treated by administration of the vitamin, commonly as D_2. Overdosage results in disturbances of calcium metabolism and ultimately leads to decalcification of bone. *See also* **calcitetrol**. For structures see entries for individual compounds.

vitamin D binding protein *abbr.*: DBP; a multifunctional protein found in plasma and other body fluids, and on the surface of many cell types. In plasma it carries the vitamin D sterols. DBP binds membrane-bound immunoglobulin on the surface of B lymphocytes, and IgG Fc receptor on the membranes of T lymphocytes.

vitamin E α-tocopherol; a fat-soluble vitamin considered to act primarily as an antioxidant. Other tocopherols (*see* **tocopherol** for structure) have vitamin E activity. Vitamin E is thought to prevent the formation of lipid autoxidation products by trapping free radicals and thus preventing the chain reaction that leads to further peroxide formation. It is present in vegetable-seed oils, and also in meat, milk, and eggs. Deficiency occurs only in pathological states in which absorption is affected, and can result in premature red cell death. A relative deficiency may occur when the intake of polyunsaturated fatty acids is high unless the diet is supplemented with α-tocopherol.

vitamin F *(formerly) a collective term for* **essential fatty acids**.

vitamin G *an old name for* riboflavin (i.e. **vitamin B$_2$**).

vitamin H 1 *(sometimes) an alternative name for* **biotin**. 2 *an old name for* riboflavin (i.e. **vitamin B$_2$**).

vitamin H$_1$ *(sometimes) an alternative name for* ***p*-aminobenzoic acid**.

vitamin K 2-methyl-3-phytyl-1,4-naphthoquinone; phylloquinone; 3-phytylmenadione; vitamin K$_1$; a fat-soluble vitamin required for the synthesis of prothrombin and certain other **blood coagulation** factors. The **menaquinones** (vitamins K$_2$) are also active. Vitamin K is found in green leafy vegetables, meat, and milk. Deficiency is uncommon because it is produced by gut bacteria, but gut sterilization may trigger symptoms (decrease in plasma prothrombin) if intake is defective. Vitamin K is a cofactor in the post-translational formation of 4-carboxyglutamyl residues in certain proteins, e.g. **blood coagulation** factors VII. IX. X, and especially prothrombin, during which an epoxidase reaction converts vitamin K$_1$ to its epoxide form, which is converted back by a reductase. This reductase can be inhibited by **warfarin**, which thus reduces vitamin K$_1$ levels, thereby reducing prothrombin formation and so acting as an anticoagulant.



vitamin-K-epoxide reductase (warfarin-sensitive) EC 1.1.4.1; an enzyme that catalyses the formation of 2-methyl-3-phytyl-1,4-naphthoquinone, oxidized dithiothreitol, and H_2O from 3-epoxy-2,3-dihydro-2-methyl-3-phytyl-1,4-naphthoquinone and 1,4-dithiothreitol.

vitamin-like dietary factor any biomolecule that resembles the vitamins in its biological properties and is considered to be produced in inadequate amounts within an organism so that dietary supplementation may be recommended. The term includes: inositol, carnitine, lipoic acid, *p*-aminobenzoic acid, and ubiquinone.

vitellogenin the precursor protein of **lipovitellin** and **phosphitin**, a major egg-yolk protein synthesized in the liver of chickens and *Xenopus*. It has an M_r of 135 000, and is split in the ovary into its constituent proteins. In *Xenopus*, two genes, for vitellogenin I and II, are spread over more than 21 kbp of DNA, their primary transcripts consisting of 6 kbp of **pre-mRNA** with 33 **introns**. A related protein is found in *Drosophila melanogaster*.

vitronectin *or* **serum spreading factor** an adhesion protein, present in plasma and on the external surface of membranes of tissues, that promotes the adhesion of cells in tissue culture. The $\alpha_v\beta_3$ **integrin** binds vitronectin, fibrinogen, laminin, von Willebrand factor, fibronectin, and thrombospondin. The human precursor encodes an N-terminal signal, vitronectin, and somatomedin B (*see* **somatomedin**).

Vl *symbol for* the valeryl group.

VLA a family of **integrins** all having the β_1 subunit. They comprise VLA-1, $\alpha_1\beta_1$ (β subunit also called VLAβ, glycoprotein IIa or gpIIa, CD29; α subunit also called CD49a), which binds laminin (and collagen); VLA-2, $\alpha_2\beta_1$ (α subunit also called gpIa, CD49b), which binds collagen (and laminin); VLA-3, $\alpha_3\beta_1$ (α subunit also called CD49c), which binds fibronectin, laminin, and collagen; VLA-4, $\alpha_4\beta_1$ (α subunit also called CD49d), which binds VCAM-1 and fibronectin; VLA-5 (*or* fibronectin receptor), $\alpha_5\beta_1$ (CD49e), which binds fibronectin; VLA-6 (*or* laminin receptor), $\alpha_6\beta_1$ (CD49f), which binds laminin; $\alpha_7\beta_1$, which binds laminin; $\alpha_8\beta_1$, ligand doubtful; and $\alpha_v\beta_1$ (α subunit also called vitronectin receptor subunit, CD51), which binds fibronectin.

VLDL *abbr. for* very-low-density lipoprotein.

VLGR-1 *abbr. for* very large G-protein-coupled receptor 1; a large cell-surface protein (≈5500 amino acids) that is highly expressed in the developing central nervous system of mouse. The C-terminal region contains seven transmembrane segments and is G-protein-coupled. The extracellular region contains a tandem array of 20 repeats similar to those present in Calx of *Drosophila* (*see* ***Calx***) and in their middle, seven repeats like those present in the C-terminal region of **epitempin**. The human gene is located in a region linked to a form of familial febrile convulsions.

VMA *abbr. for* vanillylmandelic acid; *see* **hydroxymethoxymandelate**.

VO *abbr. for* virtual organization; a concept derived from computer science and comprising people from a variety of actual organizations. One example of a VO would be those involved in different aspects of a large engineering design project. Another would be those involved in, for example, a large genome annotation project.

void volume 1 *(in column chromatography)* the volume of the mobile phase, i.e. total **bed volume** of the column minus the volume occupied by the support particles. 2 *(in gel chromatography) or* **exclusion volume** the volume of the mobile phase passing through the gel required to elute a molecule that never entered the stationary phase.

volemitol D-*glycero*-D-*talo*-heptitol; a polyol widely distributed in plants, fungi, and lichens, and used as a sweetening agent.



volkensin a ricin-like toxic glycoprotein from the roots of *Adenia volkensii*, a Kenyan shrub. It consists of two subunits, A (M_r 29 000) and B (M_r 36 000), linked by disulfide bonds.

volt *symbol*: V; the SI derived unit of electric potential or electromotive force. It is equal to the difference in electric potential between two points on a conductor carrying a constant current of one ampere when the power dissipated between the points is one watt. 1 V = 1 W A^{-1} = 1 J C^{-1}. [After Alessandro Volta (1745–1827), Italian physicist.]

voltage-gated ion channel a cell-membrane channel whose opening is governed by the membrane potential.

voltage-gated K$^+$ channel *or* **KCNQ** any of a family of membrane proteins that form K$^+$ seletive channels that contain six transmembrane segments and intracellular N- and C-termini. The channels open when a change in voltage occurs across the membrane. Mutations in KCNQ1 are common in hereditary **long QT syndrome**. Mutations in KCNQ2 and KCNQ3 cause autosomal dominant familial neonatal convulsions. KCNQ4 mutations cause a form of hereditary deafness.

voltage sensor the fourth transmembrane segment (S4) of shaker-type ion channels. It contains lysine or arginine in every third position and is involved in opening the channel at the permissive voltage. *See* **shaker**.

voltameter *an old term for* **coulometer**.

voltametry *an old term for* **coulometry**.

voltammetry an electroanalytical procedure for identifying and determining the concentrations of various ions in solution by studying the relation between a varied electric potential applied between two electrodes immersed in a test solution and the resultant faradaic current. It includes **anodic stripping voltammetry** and **polarography**. — **voltammetric** *adj.*; **voltammetrically** *adv.*

volume of distribution *symbol*: V_d; the theoretical volume of fluid in which a specified dose of drug is distributed, based on measurement of the concentration of free drug (i.e. that not bound to plasma proteins) in plasma. $V_d = Q/C_p$, where Q is the amount of drug administered and C_p is the concentration in plasma.

volutin granule *or* **metachromatic granule** an electron-dense cytoplasmic inclusion found in various bacteria, yeasts, and other microorganisms. It exhibits **metachromasia** on staining with certain basic dyes, contains polymetaphosphate, and is believed to serve as a phosphate store. *See also* **Babes–Ernst body**.

von Gierke's disease *see* **glycogen disease**.

von Willebrand factor *abbr.*: vWFa; a blood protein involved in clotting. It performs two important hemostatic functions: it links specific platelet membrane receptors to collagen, and possibly other components of subendothelial connective tissue, so mediating platelet adhesion to sites of vascular damage; and it binds to, and stabilizes, factor VIII (*see* **blood coagulation**). Deficiency results in bleeding from skin, owing to failure of platelet adhesion, with a prolonged bleeding time, and also results in spontaneous bleeding into joints and soft tissues as a result of the secondary factor VIII deficiency, caused by the instability of factor VIII. The primary translation product, synthesized by vascular endothelial cells and megakaryocytes, is a protein of 2813 amino acids (309.29 kDa). The human precursor protein encodes a signal peptide, a peptide that is cleaved off and is known as **von Willebrand antigen II**, and the mature protein itself; cysteine is the most abundant amino acid. Before the mature factor is secreted from cells of origin, many intermolecular disulfide bridges between vWF molecules are formed that lead to a complex that may vary in mass from dimers of ~500 kDa to species of more than 20 megadaltons. Inherited defects of vWF affect nearly 1% of the population, but most are not clinically significant. The majority of patients have a quantitative deficiency of vWF, with autosomal dominant inheritance, and are known as type I. Type II variants have an abnormal vWF. In vWF deficiency (*abbr.*: vWD), type IIA intermediate and large complexes are absent. Mutations cluster near Tyr^{842}- |-Met^{843}, a site that is sensitive to proteolysis. vWD type III is rare, and is a severe autosomal recessive disease characterized by virtual absence of vWF, in some cases known to be the result of total or partial deletion of the vWF gene. Unactivated platelets bind vWF through gpIb–IX complex, deficiency of which leads to a bleeding disorder, **Bernard-Soulier syndrome**. After activation, platelets bind vWF through the **integrin** gpIIb–IIIa complex, which is defective in **Glanzmann thrombasthenia**, another bleeding disorder. [After Erik Adolph von Willebrand (1870–1949), Finnish physician.]

V-PARP *abbr. for* vault-poly(ADP-ribose) polymerase; in mammals, a 193 kDa protein that contains a domain homologous to the catalytic domain of **PARP-1**. It binds to, and uses as substrate, MVP of **vaults**, and is also localized to the mitotic spindle. It does not appear to require DNA for activity.

V8 proteinase *see* **glutamyl endopeptidase**.

vps *abbr. for* **vacuolar sorting protein**.

vps34 *or* **vacuolar sorting protein 34** a protein-trafficking protein involved in the sorting and segregation of vacuoles. It is a homologue of **1-phosphatidylinositol 3-kinase**, having that enzymic activity, which may be the mechanism by which it acts. It is, in turn, activated via phosphorylation by a serine/threonine protein kinase, vps15.

VRE *abbr. for* **vancomycin**-resistant *Enterococcus*. It is a drug-resistant pathogen (*compare* **MRSA**) found in hospital populations of bacteria. The resistance arises from modification of the peptidoglycan precursor that is the target for vancomycin.

Vrille a basic leucine zipper transcription factor of *Drosophila* that represses Clock.

v-*yes* *see* ***YES***.

Ww

w *symbol for* **1** mass fraction. **2** work (alternative to *W*). **3** speed (alternative to *u*, *v*, or *c*). **4** (bold italic) velocity (alternative to *v*, *u*, or *c*).

W *symbol for* **1** watt. **2** a residue of the α-amino acid L-tryptophan (alternative to Trp). **3** a residue of an incompletely specified base in a nucleic-acid sequence that may be adenine or may be thymine (in DNA) or uracil (in RNA). **4** a residue of the minor nucleoside **wyosine** (alternative to Y). **5** tungsten.

W *symbol for* **1** weight (alternative to *G* or *P*). **2** work (alternative to *w*). **3** radiant energy (alternative to *Q*). **4** writhing number.

W3 *abbr. for* World Wide Web. *See* **WWW**.

Waardenburg syndrome an autosomal dominant syndrome of developmental defects in and around the eyes, pigmentary defects in eyes and hair, and congenital deafness. Types 1 and 3 are caused by mutations in *PAX-1* and *PAX-3*. Type 3 also shows limb muscle hypoplasia. Type 2 is caused by mutations in **MITF**; type 4 is associated with **Hirschsprung disease**, and is caused by mutations in *SOX10*. [After Petrus Waardenburg (1886–1979), Dutch ophthalmologist.]

WAGR *abbr. for* Wilm's tumour, aniridia, ambiguous genitalia, and mental retardation; a contiguous gene syndrome resulting from a deletion in chromosome 11p13.

WAK1 *abbr. for* wall-associated kinase 1; a single-pass plasma membrane protein of plants, whose N-terminal region interacts with the cell wall while the intracellular region is a protein kinase.

Walden inversion the inversion of the configuration at a chiral centre in a bimolecular nucleophilic substitution reaction. [After its discoverer, Paul Walden (1863–1957), Latvian chemist.]

Waldenström's macroglobulinemia a lymphoid tumour that arises from the most mature B lymphocytes and invariably produces IgM, which appear as a **paraprotein**. [After Jan Goesta Waldenström (1906–1996), Swedish physician.]

Walker motif either of two sequence motifs in proteins that bind and hydrolyse nucleoside triphosphates. Walker-A (or P-loop) consists of the sequence A/GX4GKT/S (in one-letter code), is flanked by a beta strand and an alpha helix, and loops around the triphosphate moiety. Walker-B consists of X4D (where X is almost exclusively a hydrophobic residue), occurs at the end of a beta strand, and interacts with the Mg^{2+} ion of the triphosphate moiety. [After John Walker (1941–), British biochemist who discovered them in H^+-transporting ATPase of mitochondria.]

wall effect **1** *(in centrifugation)* the collision of sedimenting molecules with the wall of the cell. This occurs because the centrifugal field is radial, so can be avoided by using sector-shaped cells. **2** *(in chromatography)* the curving and spreading of a zone as it migrates down a chromatographic column because of inhomogeneities in solvent flow near the wall of the column.

Warburg apparatus a sensitive, constant-volume respirometer for measuring gas exchange of cells, homogenates, or tissue slices. It consists of a small flask, with one or more side arms for the addition of reagents, and a centre well, connected to a U-tube manometer of about 1 mm^2 internal cross-section, fitted with a reservoir for manometer fluid. The vessel is immersed in a constant temperature bath and shaken continually to equilibrate the gas in the liquid phase, where the reaction is taking place, with the gas phase, where the reaction is being measured. It was used extensively for metabolic studies before the wide availabilty of radioactive tracers, but is now virtually obsolete. [After Otto Heinrich Warburg (1883–1970), German physiologist and biochemist.]

Warburg–Dickens–Horecker pathway *or* **Warburg–Dickens pathway** *an alternative name for* **hexose monophosphate pathway**.

Warburg effect **1** the relative overproduction of lactate that occurs in many tumours. **2** the inhibitory effect of high oxygen concentrations on photosynthesis.

Warburg's enzyme *an alternative name for* old yellow enzyme; *see* **yellow enzyme**.

warfarin 3-(α-phenyl-β-acetylethyl)-4-hydroxycoumarin; 1-(4′-hydroxy-3′-coumarin-3′-yl)-1-phenylbutan-3-one; an anticoagulant and rodenticide. It inhibits the reductase that converts the epoxide form of **vitamin K** to its reduced form, which is a cofactor for the production of the 4-carboxyglutamyl residues of, among other proteins, the **blood coagulation** factors II (i.e. prothrombin), VII, IX, and X. [From the name of the patentees, Wisconsin Alumni Research Foundation, + coumarin.] *See also* **vitamin-K-epoxide reductase (warfarin-sensitive)**.



Waring blendor *the proprietary name for* a blender used in the preparation of tissue homogenates. It consists of a hydrodynamically designed vessel (of tetrafoil cross-section) in the bottom of which a specially shaped blade rotates at high speed. [After the manufacturers, Waring Products Corporation.]

washing soda *see* **soda**.

WASP *abbr. for* Wiskott–Aldrich syndrome protein; any of a small family of proteins including WASP1 (whose expression is limited to lymphocytes and platelets) and N-WASP (which is more widely expressed but especially in neurons). They bind small GTPases and phospholipids through their N-terminal regions and are homologous in their C-terminal regions. They activate the **Arp2/3 complex** and help in actin filament nucleation. Over 20 mutations of a locus at Xp11.23-p11.22 for WASP (501 amino acids) are associated with the Wiskott–Aldrich syndrome of severe thrombocytopenia and defective immunity.

Wasserman reaction a **complement-fixation test** for human blood and cerebrospinal fluid, widely used to detect syphilitic infection, although false positive reactions are often given by yaws, leprosy, paroxysmal hemoglobinuria, and malarial infection. The antigen on which the test is based is **cardiolipin**. [After August von Wassermann (1866–1925), German bacteriologist.]

Watanabe rabbit a breed of rabbits suffering from high blood cholesterol levels as a result of mutation of the low-density lipoprotein (LDL) receptor gene. It is used as an animal model for familial hypercholesterolemia.

water balance (of an organism) the **water intake** (as a liquid, the water in food, and water of oxidation) less the **water output** (water in urine, feces, or other excreta, water expended in saturating respired air, water lost through the integument).

waterfall sequence *an alternative name for* **cascade sequence**.

water regain (of an ion-exchange resin) for cationic resins, the weight of water taken up by 1 g dry resin in the hydrogen form; for anionic resins, the weight of water taken up by 1 g dry resin in the chloride form.

water-soluble B *an old name for* a fraction rich in water-soluble vitamins prepared from egg yolk.

Watson–Crick model of DNA a model for one form of **DNA** consisting essentially of two antiparallel helical polynucleotide strands coiled around the same axis to form a double helix. The deoxyribose–phosphate backbones lie on the outside of the helix and the purine and pyrimidine bases lie approximately at right angles to the axis on the inside of the helix. The diameter of the helix is 2.0 nm and there is a residue on each chain every 0.34 nm in the *z* direction. The angle between each residue on the same strand is 36°, so that the structure repeats after 10 residues (3.4 nm) on each strand. The two strands are held together by hydrogen bonds between pairs of bases that are complementary and opposing (i.e. on different strands). Adenine pairs with thymine and guanine with cytosine. The two chains are therefore complementary. Watson and Crick's paper, published in *Nature* in 1953, also contained a prescient statement: 'It has not escaped our notice that the specific pairing we have postulated immediately suggests a possible copying mechanism for the genetic material.' This structure has stood the test of time. It is difficult to exaggerate the importance of the short paper. To quote from L. Stryer's *Biochemistry* (fourth edition), 'This brilliant accomplishment ranks as one of the most significant in the history of biology because it led the way to an understanding of gene function in molecular terms.' *See also* **double helix**. [After James Dewey Watson (1928–), US biologist, and Francis Harry Crick (1916–2004), British molecular biologist.]

Watson strand the upper strand in representations of double-stranded DNA sequences. Open reading frames (ORFs) may occur on either strand of a genomic DNA duplex and it is convenient to distinguish between the strands in order to specify specific ORFs. ORFs in the Watson strand of the yeast genome, for example, are given the suffix W, as in the systematic name YLR451W for the *LEU3* gene on yeast chromosome XII. *Compare* **Crick strand**. [After J.D. **Watson**.]

watt *symbol*: W; the SI derived unit of power or radiant flux; it is the power dissipated when one joule is expended in one second; i.e. 1 W = 1 J s^{-1}. [After James Watt (1736–1819), British engineer.]

wave function *symbol*: ψ *or* w *or* Φ *or* ϕ; the amplitude of the wave associated with a particle, e.g. an electron, as obtained from the Schrödinger wave equation. The square of the value of ψ at any point is proportional to the probability of finding the particle at that point.

wavelength *symbol*: λ; the distance between successive points of equal phase of a wave. Wavelength is equal to the velocity of the wave motion divided by its frequency. For electromagnetic radiation, $\lambda = c_0/\nu$, where c_0 is the velocity of light *in vacuo* and ν the frequency of the radiation.

wavenumber *or* **repetency** for an electromagnetic radiation (e.g. light), the reciprocal of the **wavelength**; i.e. the number of waves in unit distance. *Compare* **kayser**.

wax **1** any lipid fraction from living organisms or from crude petroleum that is a plastic substance, hard when cold, easily moulded when warm, and insoluble in water. **2** any fatty-acid ester of a long-chain monohydroxy alcohol.

wax synthase *see* **long-chain-alcohol *O*-fatty-acyltransferase**.

Wb *symbol for* weber.

WBC *or* **wbc** *or* **w.b.c.** *abbr. for* white blood cell(s); *see* **leukocyte**.

WC *abbr. for* **white collar**.

WD40 *or* **WD repeat** *or* **WD40 repeat** a conserved protein sequence of ≈40 amino acids that typically ends in tryptophan–aspartate (WD in the one-letter code for amino acids). The WD40 protein family comprises many regulatory or adaptor proteins involved in signal transduction, and its members may have one or several WD40 repeats. WD40 mediates protein–protein interaction. Examples are: the β subunits of trimeric G-proteins, the β subunit of protein phosphatase 2A, Apaf-1, and SCAP.

WDHA syndrome *abbr. for* watery diarrhoea, hypokalemia, plus achlorhydria syndrome; i.e. **Verner–Morrison syndrome**.

WD repeat *see* **WD40**.

weak interactions noncovalent interactions between molecules and parts of molecules, including charge–charge interactions, those involving permanent dipoles, van der Waals forces, and hydrogen bonds. They are particularly important in protein and nucleic-acid structure.

weber *symbol*: Wb; the SI derived unit of magnetic flux. It is equal to the flux that, linking a circuit of one turn, produces in it an emf of one volt as it is reduced to zero at a uniform rate in one second; i.e. 1 Wb = 1 V s. [After Wilhelm Eduard Weber (1804–91), German physicist.]

wee1 a gene in *Schizosaccharomyces pombe* encoding a protein kinase (EC 2.7.1.112) that can phosphorylate tyrosine and serine/threonine residues. In yeast it phosphorylates a tyrosine of cdc2; in the human it phosphorylates a tyrosine and a threonine of the equivalent protein. It has conserved catalytic domains of the serine/threonine type of protein kinase, and is a negative regulator for entry to mitosis; it closely resembles the corresponding human homologue. *See also* ***cdc*** **gene**.

weight average molecular mass *old name for* mass average molar mass; *see* **average molar mass**.

weight matrix *an alternative name for* **scoring matrix**.

Weigle reactivation *see* **W reactivation**.

Weiss unit a measure of T4 DNA ligase activity based on ATP–PP_i exchange. One unit is the amount of enzyme required to catalyse the exchange of one nanomole of ^{32}P from $^{32}PP_i$ into ATP as **Norit-adsorbable** material in 20 min at 37°C. ATP and ^{32}P labelled ATP are adsorbed by Norit and recovered by filtration in this bound state for counting of radioactivity.

Werner syndrome a rare autosomal recessive disorder characterized by premature formation of cataracts, scleroderma-like skin, short stature, greying hair and hair loss, a generalized appearance of premature ageing, and a high risk of malignancy. It is caused by mutations in the Werner syndrome gene product (*see* **WRNp**). [After Otto Werner (1879–1936), German physician.]

Wernicke–Korsakoff syndrome a combination of **Wernicke's disease** (gliosis and capillary proliferation leading to ocular manifestations and polyneuropathy) and **Korsakoff's psychosis** (difficulty in recording and retaining new impressions). Wernicke's disease is due to vitamin B_1 deficiency, and manifests particularly in patients with a genetic abnormality in transketolase resulting in its reduced affinity for thiamine diphosphate. In such patients, even mild B_1 deficiency, as often occurs in alcoholics, may produce symptoms. [After Karl Wernicke (1848–1905), German alienist, and Sergei Sergeyevich Korsakoff (1854–1900), Russian neurologist.]

Western blotting a technique for **blotting** proteins onto nitrocellulose, nylon, or other **transfer membrane** after they have been resolved by gel electrophoresis. The proteins can then be detected by autoradiography (if labelled), or through binding to fluorescently labelled, ^{125}I-labelled, or enzyme-linked (*see* **ELISA**) antibody, lectin, or other specific binding agent. The name derives by extension through the cardinal points from **Southern blotting**, the first such blotting technique, with a capital initial by similar extension.

Whitaker plot a plot that, ideally, gives a linear correlation between the logarithm of the relative molecular mass of a macromolecule and the ratio of the **elution volume**, V, to the **void volume**, V_o, when the macromolecules in solution are passed through a suitable **gel filtration** column; i.e. log $M_r = V/V_o$. [After John Robert Whitaker (1929–), US biochemist.]

white adipose tissue *or* **white fat** a tissue developed particularly in mammals and birds to store fat as triacylglycerols to supply energy to the whole animal. The cells contain a single large droplet of fat that, in the nourished state, fills most of the cell. The nucleus lies in the narrow band of cytoplasm around the periphery. Adipose tissue is found in many parts of the body but is concentrated under the skin (subcutaneous) and around internal organs (heart and kidney). *Compare* **brown adipose tissue**.

white blood cell *see* **leukocyte**.

white coat effect the effect of the presence of the investigator on the accurate measurement of the blood pressure of a subject.

white collar *abbr.*: WC; a circadian blue-light photoreceptor that binds to the promotor of the clock component called frequency in the fungus *Neurospora crassa*. It is a light sensor and a DNA-binding transcription factor. WC-1 and WC-2 are zinc-finger proteins that function as a complex.

white fat *see* **white adipose tissue**.

white muscle pale, skeletal, usually involuntary muscle that is relatively deficient in myoglobin and cytochromes. *Compare* **red muscle**.

whole genome PCR a method whereby genomic DNA is converted to a form that can be amplified by the **polymerase chain reaction** (PCR). DNA is reduced to small fragments by restriction enzyme digestion or sonication, and adaptors are ligated to their ends. Oligonucleotides specific for the adaptors can be used for PCR amplification of the fragments. The technique can be used to identify individual fragments capable of binding transcription factors or other DNA-binding proteins using antibodies specific for the protein concerned.

WIBR *abbr. for* Whitehead Institute for Biomedical Research; *see* **sequencing centre**.

widow *(in a sequence alignment)* an amino acid residue or nucleotide base isolated from neighbouring residues or bases by spurious gaps at each side, usually the result of overzealous gap insertion by automatic alignment programs.

WIF-1 *abbr. for* Wnt-inhibitory factor-1. *See* **Wnt**.

WIF domain *see* **Wnt inhibitory factor 1**..

wild-type the **phenotype** that is characteristic of most of the members of a species occurring naturally and contrasting with the phenotype of a **mutant**. *Compare* **auxotroph**.

Williams–Beuren syndrome an autosomal dominant contiguous gene deletion disorder involving over 17 genes on chromosome 7 and characterized by a broad spectrum of abnormalities. The gene at 7q11.23 for FKBP6 (a component of the synaptonemal complex) is frequently part of the deletion. [After J.C.P. Williams (1900–), New Zealand cardiologist and Alois J. Beuren (1919–1984), German cardiologist.]

Wilm's tumour *or* **nephroblastoma** a malignancy in human infants (incidence 1 in 10000) associated with protein **WT33**. [After Marx Wilms (1867–1918), German pathologist.]

Wilson ATPase *see* **Wilson disease**.

Wilson's disease *or* **hepatolenticular degeneration** a rare autosomal recessively inherited disease characterized by degenerative changes in the brain, particularly in the basal ganglia, and cirrhosis of the liver. There are excessive deposits of copper in the liver, brain, cornea, and kidney; the serum copper is usually low and there is a **ceruloplasmin** deficiency. Patients may be effectively treated with British antilewisite (**dimercaprol**) or other chelating agents. [After (Samuel Alexander) Kinnier Wilson (1878–1937), US-born British neurologist.]

Wilzbach method a method for the random labelling of a compound with tritium by exposing it to isotopically pure tritium gas in a sealed container for several weeks. The exchange is promoted by the radiation.

winding angle (of double-stranded DNA) the angle of rotation between successive base pairs.

winding number the number of turns in a closed-circular double-stranded DNA measured relative to a surface on which the DNA lies. *See also* **supercoil**.

windowless counter a counter for radioactive (or X-ray) ionization in which the sample (or source) is not separated from the detector by a membrane or 'window'.

wingless a gene in *Drosophila melanogaster* that encodes a protein in the **WNT family**, probably a growth factor that acts on neighbouring cells to regulate the ***engrailed*** gene. A homologue is present in the brachiopod *Terebratulina retusa*.

Wiskott–Aldrich syndrome a syndrome of thrombocytopenia, eczema, and immunodeficiency, with increased risk of malignancy. It is caused by mutations in a protein (*see* **WASP**) encoded on the X chromosome. [After Alfred Wiskott (1898–1978), German paediatrician, and Robert Anderson Aldrich (1917–), US paediatrician.]

Wiskott–Aldrich syndrome protein *see* **WASP**.

WIT *abbr. for* what is there; *see* **pathway database**.

WNK any of a family of protein serine/threonine kinases, first described in the rat, that have cysteine in place of lysine at a key position in the active site and contain two coiled-coil domains. The human WNK1 (gene on chromosome 12p) shows 86% sequence identity with the rat protein. Large deletions in the first intron increase expression of the protein and cause pseudohypoaldosteronism type II (an autosomal dominant hypertension, hyperkalemia, and metabolic acidosis). hWNK4 (gene on chromosome 17) is highly homologous with hWNK1. Several missense mutations cause pseudohypoaldosteronism type II. Both proteins localize to the distal nephron, hWNK1 being cytoplasmic, while hWNK4 is associated with tight junctions.

Wnt *abbr. for* (*Drosophila*) Wingless/Int-1; any of a family of secreted signalling glycoproteins found throughout the animal kingdom. They are important for patterning and development in the embryo and for regulation of cell proliferation thereafter. Wnt-1 is expressed in the central nervous system. On binding to G-protein-coupled receptors of the **Frizzled** family in the plasma membrane, they cause inactivation of **GSK-3**, which is complexed with APC protein, axin, and β-catenin, and targeted for ubiquitination and proteosomal degradation. In the extracellular space they are inhibited by binding Wnt-inhibitory factor-1 (WIF-1).

WNT family a family of secreted glycoproteins (e.g. WNT-2 from human and mouse) that are signalling molecules in tissue development. They act through G-protein-associated membrane receptors of the frizzled family to inhibit glycogen synthase kinase 3. The *WNT-1* gene is closely homologous to ***wingless***.

Wnt inhibitory factor 1 *abbr.*: WIF-1; a secreted protein that contains an N-terminal WIF domain (≈150 amino acids), which binds and inhibits **Wnt** proteins; five EGF-like repeats; and a short hydrophilic domain in the C-terminal region. Homologues are present in many animals. The WIF domain is related to the extracellular domain of **Ryk** receptor tyrosine kinases. .

wobble base the third base in the anticodon of **transfer RNA** ($5'$ end). It can bind to one of several possible bases at the $3'$ end of the codon in mRNA. *See also* **wobble hypothesis**.

wobble hypothesis the hypothesis that in **translation** (during protein synthesis) a less strict specificity in the base pairing of the $5'$ base of the anticodon of **transfer RNA** (tRNA) allows it to make alternative hydrogen-bonding with the third base of the codon of messenger RNA (mRNA) beyond the usual G–C and A–U pairings. Thus, anticodon U may recognize A or G and anticodon G may recognize C or U. Although the hypothesis has been fully supported by experiment, UGG and AUG are the only examples of the first type of wobble, and no examples of the second type are known. The presence of bases other than U,A,G, or C at the anticodon $5'$ position also contributes to more general pairing at this position. Thus, bases such as **wyosine**, **queuosine**, and **inosine** may be present (I always substitutes for A) with less strict pairing constraints. The degeneracy at the third codon position is consistent with the fact that about 40 different tRNA molecules interact with the 61 possible sense codons.

Wolcott–Rallison syndrome *see* **PERK**.

Wolfgram proteolipid protein one of the three principal classes of central nervous system **myelin protein**, extractable by chloroform: methanol (2:1, v/v), and consisting of three main fractions of 235, 54, and 62 kDa. *Compare* **Folch–Lees protein**. [After F. Wolfgram, who first discovered it.]

Wolf–Hirschhorn syndrome a syndrome of multiple malformations with mental and developmental defects. It is caused by deletion of the gene for **NELF**-A. [After Ulrich Wolf (1933–), German physician and Kurt Kirschhorn (1926–), US physician.]

Wolman disease a rapidly fatal autosomal recessive disease of infancy in which there is massive accumulation of cholesterol esters and triacylglycerols in most tissues. It is associated with mutations that lead to complete elimination in the activity of lysosomal **acid lipase**. [After Moshe Wolman (1914–), Israeli pathologist.]

work *symbol*: *W or w*; the transfer of energy expressed as the product of a force, *F*, and the distance, *s*, through which its point of application moves in the direction of the force; i.e. $W = \int F \, \mathrm{d}s$. The SI unit of work is the joule. The manifestation of work in productive form usually involves transduction by a mechanical device of the action of a force through a distance. A relationship between the work done on (or by) a system of constant mass, the heat it gains (or loses), and the change in the internal energy of the system is provided by the first law of thermodynamics (*see* **thermodynamics**).

World Wide Web *abbr.*: WWW *or* W3; the world-wide network of information (including biochemical and molecular biological data) stored on computers linked to the Internet, and made accessible for visualization and interrogation by browser software.

wortmannin *or* **MS-54** *or* **KY 12420** a potent and specific inhibitor of phosphatidylinositol 3-kinase, derived from the fungus *Penicillium funiculosum*.



W reactivation *or* **Weigle reactivation** *or (formerly)* **UV reactiva-**

tion the phenomenon whereby the survival of UV-irradiated bacteriophage is higher in a UV-irradiated host than in an unirradiated host. [After Jean Jacques Weigle (1901–68), who discovered it and described it in 1953.]

writhing number *symbol*: W; an index of the superhelical coiling of DNA, termed **writhe**. The writhing number and the **twist number** between them determine the **linking number** (L). The writhing number does not have a precise quantitative definition, but represents the degree of supercoiling. A decrease in L involves some decrease in supercoiling, and an increase in L an increase in supercoiling. *See also* **supercoil**.

WRNp *abbr. for* Werner syndrome gene product; *other name*: RECQL3. A RecQ helicase (1432 amino acids) of humans that has 3′→5′ exonuclease activity and binds to the ssDNA-binding protein replication protein A. Over a score of mutations cause **Werner syndrome**.

wt *or* **wt.** *abbr. for* weight.

WT33 a protein that is related to **early growth response proteins**, and is associated with **Wilm's tumour**; it is probably a tumour suppressor. Certain mutations are also associated with Denys–Drash syndrome. Its sequence contains alternative splice sites and a zinc finger.

w/v *or* **wt/vol.** *abbr. for* weight per unit volume (of a solution or mixture).

w/w *or* **wt/wt** *abbr. for* weight per unit weight (of a solution or mixture).

WW domain *or* **WWP domain** a small motif characterized by two conserved tryptophan residues (spaced ~20-23 amino acid residues apart) and a conserved proline, hence its alternative name. It is found in various disparate proteins, including vertebrate YAP protein, mouse NEDD-4, **utrophin** and **dystrophin**, the protein encoded by the gene responsible for **Duchenne muscular dystrophy**. The domain contains ~35-40 residues, which fold as a triple-stranded β-sheet, and may be repeated several (up to 4) times. It binds proteins that contain specific proline motifs ([AP]-P-P-[AP]-Y), and bears some resemblance to **SH3 domains**. It is often associated with other domains characteristic of proteins involved in signal transduction.

WWE motif *see* **deltex**.

wwPDB *abbr. for* Worldwide Protein Data Bank; *see* **composite database**.

WWP domain *another name for* **WW domain**.

WWW *abbr. for* **World Wide Web**.

wyosine *symbol*: W *or* Y; any modified form of guanosine present in the anticodon loop of some species of **transfer RNA**. They are based on the structure N^2-(2-methyletheno)guanosine, and carry varying side chains on the five-carbon imidazo ring. The structure of one such compound is shown. *See also* **minor nucleoside**.



Xx

x *symbol for* **1** amount-of-substance fraction (i.e. mole fraction) or number fraction for condensed phases. *Compare* ***y***. **2** a cartesian space coordinate, complementary to *y* and *z*.

X *symbol for* **a** a residue of an unknown, unspecified, or (specified) unusual α-amino acid (alternative to Xaa). **b** a residue of the ribonucleoside **xanthosine** (alternative to Xao).

X *symbol for* (electric) reactance.

X-537A *an alternative name for* **lasaloacid**.

Xaa *symbol for* a residue of an unknown, unspecified, or (specified) unusual α-amino acid (alternative to X).

Xan *symbol for* a residue of the purine base **xanthine**.

xanthan gum a capsular complex heteropolysaccharide formed by strains of the pseudomonad bacterium *Xanthomonas campestris* and believed to promote adhesion of the organism to its plant host. It is widely used in the cosmetic, food, and other industries as a crystallization inhibitor, emulsifier, gelling agent, etc.

xanthine *symbol*: Xan; 2,6-dihydroxypurine; 2,6-dioxopurine; 3,7-dihydro-1*H*-purine-2,6-dione; a purine formed in the metabolic breakdown of guanine. *Compare* **hypoxenthine**. *See also* **allopurinol**.



xanthine oxidase EC 1.1.3.22; *the recommended name for* hypoxanthine oxidase; *systematic name*: xanthine:oxygen oxidoreductase; *former name*: Schardinger enzyme. A flavoprotein (FAD) enzyme containing two 2Fe–2S clusters and molybdenum cofactor, abundant in milk and liver, that catalyses the oxidation of **xanthine** to urate and superoxide (or hydrogen peroxide) and also the oxidation of hypoxanthine to xanthine. The enzyme has two forms: (1) xanthine dehydrogenase, which has **NAD** as coenzyme, and urate and NADH as products; and (2) xanthine oxidase, which reacts with dioxygen and has urate and H_2O_2 as products. The dehydrogenase is converted reversibly to the oxidase by oxidation of sulfhydryl groups or irreversibly by proteolysis.

xanthinuria the excretion of excessive amounts of xanthine in the urine. It is sometimes due to a hereditary disease in which there is a gross deficiency of **xanthine oxidase** activity in the tissues. *See* **molybdoenzymes**.

xantho+ *or (before a vowel)* **xanth+** *comb. form* denoting yellow.

xanthoma a yellow fatty deposit below the skin or associated with a tendon. Usually multiple, xanthomas are due to extravascular phagocytosis of chylomicrons, LDL-derived cholesterol, or other sterols, by macrophages of skin or subcutaneous tissue. They usually occur in a variety of hyperlipidemias and in cerebrotendinous xanthomatosis but may also occur with a normal plasma lipid profile. **–xanthomatous** *adj.*

xanthophyll any **carotenoid** in which one or more oxygenated functions are present in the molecule.

xanthoproteic test a test for protein in which a yellow colour (or precipitate from solution) forms on addition of conc. nitric acid; the colour turns orange when made alkaline.

xanthopterin a yellow pterin pigment of insect wings, e.g. of the common sulfur butterfly. *Compare* **leukopterin**.



xanthopterin

xanthosine *symbol*: X *or* Xao; xanthine riboside; 9-β-D-ribofuranosylxanthine; a nucleoside formed by the deamination of guanosine.



xanthosine monophosphate *abbr.*: XMP; any xanthosine phosphate, particularly xanthosine 5′-phosphate when its distinction from xanthosine (5′-)diphosphate and xanthosine (5′-)triphosphate requires emphasis.

xanthosine phosphate xanthosine monophosphate (*abbr.*: XMP); any phosphoric monoester or diester of xanthosine. Of the three possible monoesters and the two possible diesters only **xanthosine 5′-phosphate** occurs naturally (the locant being omitted if no ambiguity may arise).

xanthosine 5′-phosphate *or* **5′-xanthylic acid** *or* **5′-phosphoxanthosine** *or* **5′-*O*-phosphonoxanthosine** *symbol*: Xao5′*P*; *alternative recommended names for* xanthosine monophosphate (*abbr.*: XMP); xanthosine 5′-(dihydrogen phosphate); xanthine (mono)ribonucleotide. (The locant is commonly omitted if there is no ambiguity as to the position of phosphorylation.) An intermediate in the biosynthesis of guanosine 5′-phosphate (i.e. 5′-guanylic acid, or GMP), it is formed from inosine 5′-phosphate (i.e. 5′-inosinic acid) by an NAD$^+$-dependent dehydrogenase; a glutamine-requiring amidotransferase reaction (catalysed by **GMP synthase**) then converts XMP to GMP.



xanthylic acid *the trivial name for* any phosphoric monoester of xanthosine. The position of the phosphoric residue on the ribose moiety of a given ester may be specified by a prefixed locant (*see*

xanthosine phosphate). However, 5′-xanthylic acid is the ester commonly denoted, its locant usually being omitted if no ambiguity may arise.

Xao *symbol for* a residue of the ribonucleoside **xanthosine** (alternative to X).

Xao5′*P* *symbol for* xanthosine 5′-phosphate.

Xao5′*PP* *symbol for* xanthosine 5′-diphosphate (alternative to ppX).

Xao5′*PPP* *symbol for* xanthosine 5′-triphosphate (alternative to pppX).

***Xba* I** a type 2 **restriction endonuclease**; recognition sequence: T↑CTAGA.

X box a small nucleotide sequence within the 150 bp response element of the promoter of all MHC class II genes. It binds the **RFX** complex.

X cell *see* **X-Y-Z cell theory**.

X chromosome a **sex chromosome**. It is often found paired in the **homogametic** sex, which in many species is the female, and single in the **heterogametic** sex, in many species the male. The X chromosome carries a large number of genes that control many aspects of development and function. A mutant gene so carried is called X linked. Since males possess only one X chromosome an abnormal gene that it carries cannot be paired with a normal allele; the male is then said to be hemizygous for that gene. The female with two identical members of a pair of X-linked genes is said to be homozygous for that gene; the female with one mutant gene is called a heterozygote or carrier for the abnormal allele. One X chromosome is inactivated during early embryonic development. Since the progeny of each cell have the same inactivated X chromosome, a proportion of cells have the paternal X chromosome in an active state while in the other cells the maternal X chromosome is active. Hence the female who is heterozygous for an abnormal gene will have cells with the normal gene and cells with the mutant gene. She is said to be a mosaic. *Compare* **Y chromosome**. *See also* **sex determination**.

X-chromosome inactivation *or* **X inactivation** the inactivation in female mammals of one of the two **X chromosomes** during early embryonic development. This phenomenon occurs randomly in cells of the female embryo, which is thus a mosaic in respect to whether it the maternal or paternal X chromosome is functional. X inactivation means that the dosage of genes in female cells is comparable with that of males, who inherit only one X chromosome. *See also* **Lyon hypothesis**.

XDP *abbr. for* xanthosine (5′-)diphosphate.

Xe *symbol for* xenon.

Xeloda *another name for* **Capecitabine**.

Xenical (**Orlistat**) A slimming drug that acts by inhibiting lipase in the gut so that fat is not absorbed. As a result about 30% of the fat in a meal is indigested.

xenin a 25-residue peptide isolated from human gastric mucosa. The six C-terminal amino acids are identical to those of the octapeptide, **xenopsin**, present in the skin of amphibians. It stimulates exocrine pancreatic secretion, its concentration rising in plasma after a meal.

xeno+ *or (before a vowel)* **xen+** *comb. form* indicating something strange or foreign.

xenobiochemistry the biochemistry of organic compounds foreign to the organism.

xenobiotic **1** any substance that does not occur naturally but interacts with the metabolism of any organism. **2** of, or relating to, substances that are foreign to living systems.

xenobiotic-response element *abbr*.: XRE; a DNA-regulatory sequence that binds transcription factors that activate gene expression for enzymes that detoxify xenobiotics, including halogenated and other aryl hydrocarbons. *See also* ***Ah***.

xenogeneic *or* **xenogenic** originating in a different species, especially of a tissue transplant. *See also* **xenograft**.

xenograft a tissue graft between individuals of different species.

xenologue *or (esp. US)* **xenolog** a gene acquired by horizontal transfer from another species (but not including gene transfer to eukaryotic cells from their endosymbionts, or hence from organelles to the nucleus). *Compare* **synologue**.

Xenopus laevis the South African clawed toad, the oocytes and embryos of which have been extensively exploited in molecular genetics and vertebrate embryology.

xenotope an antigenic **epitope** that is foreign to an animal.

xenotransplantation the transfer of living cells, tissues, and/or organs from one species to another, especially from nonhuman animals into humans for medical purposes. **–xenotransplant** *n., vb*.

xenotype a class or group of related **xenotopes**; i.e. an antigenic **epitype** that is foreign to a particular animal.

xeroderma pigmentosum an autosomal recessive hereditary skin disease of humans in which homozygotes show a marked tendency to develop skin cancers following exposure to sunlight. It is due to a reduced ability to excise UV-induced cyclobutane **pyrimidine dimers** from DNA.

xerophthalmia progressive drying and wrinkling of the conjunctiva of the eye. One cause is **vitamin A** deficiency.

X-gal *abbr. for* 5-bromo-4-chloro-3-indolyl-β-D-galactoside, a colourless substrate that is hydrolysed by β-galactosidase to galactose and a blue product. It is used with **cloning vectors** containing part of the *lacZ* gene to select recombinants in molecular cloning: the peptide produced by the *lacZ* fragment complements the defective β-galactosidase enzyme in host cells. Insertion of foreign DNA into the vector inactivates the *lacZ* gene, so host cells containing recombinant plasmids will grow as white colonies on medium containing X-gal, whereas host cells containing ‘empty’ vectors will have a functional β-galactosidase and thus produce blue colonies.

***Xho* I** a type 2 **restriction endonuclease**; recognition sequence: C↑TCGAG.

***Xho* II** a type 2 **restriction endonuclease**; recognition sequence: R↑GACTY.

xi *symbol*: ξ (lower case) *or* Ξ (upper case); the fourteenth letter of the Greek alphabet. For uses *see* **Appendix A**.

XIAP *abbr. for* X-linked inhibitor of apoptosis.

XIC *abbr. for* X inactivation centre. *See* **Xist**.

X-inactive-specific transcript *see* **Xist**.

Xiphophorus a genus of fish, that includes the South American minnow, some species of which have been much used for the study of inherited characteristics involved in carcinogenesis. Crossing of certain species, e.g. backcrossing *X. maculatus* (platyfish) with *X. helleri* (swordtail: recurrent parent) leads to spontaneous development of melanoma.

Xis protein *or* **excisionase** the product of the *xis* gene in lambda phage. It is essential in the excision of phage DNA from **prophage**. *See also* **integrase**.

XIST *or (in mouse)* **Xist** *abbr. for* X-inactive-specific transcript; the noncoding RNA(16 500 nt) transcript of the X inactivation centre (XIC) on the X chromosomes of female mammals. It is confined to the nucleus and associated with the heterochromatin (or Barr body) in female interphase nuclei. Xist accumulates before inactivation of the X chromosome.

XL1-Blue a proprietary strain of *E. coli* allowing blue-white colour screening for recombinants and the single-stranded rescue of phagemid DNA.

XL1-Blue MRF′ a proprietary strain of *E. coli* lacking K12 restriction systems and suitable for cloning methylated DNA such as that from eukaryotes.

***Xma* I** a type 2 **restriction endonuclease**; recognition sequence: C↑CCGG.

XML *abbr. for* extensible markup language. *See* **markup language**.

XMP *abbr. for* xanthosine monophosphate; i.e. xanthosine (5′-)phosphate.

XNU *see* **sequence filter**.

xotch a transmembrane protein in *Xenopus* that is similar in sequence, and presumably in role, to the product of **notch**. It is uniformly expressed in early embryos. It contains 36 EGF-like domains and three notch-type repeats.

X-Pro dipeptidase EC 3.4.13.9; *other names*: proline dipeptidase; imidodipeptidase; prolidase; peptidase D; γ-peptidase. A cytosolic homodimeric enzyme that catalyses the hydrolysis of Xaa-|-Pro dipeptides; it also acts on aminoacyl-hydroxyproline analogues, but has no action on Pro-|-Pro. It requires manganese. Enzyme deficiency leads to imidodipeptiduria.

XPS *abbr. for* X-ray photoelectron spectroscopy; *see* **photoelectron spectroscopy**.

XPum a homologue of Pumilio, in *Xenopus laevis*.

X-ray crystallography the study of the geometric forms of crystals by **X-ray diffraction**. Myoglobin was the first protein for which the structure was solved by X-ray crystallography.

X-ray diffraction a method that uses the diffraction pattern obtained by passing X-rays through crystals, or other regular molecular arrays, to measure interatomic distances and to determine the three-dimensional arrangement of atoms (or molecules) in the structure studied. For the pattern to be sharp, the wavelength of the radiation used must be shorter than the regular spacing between the elements of the structure. X-rays typically have wavelengths of only a few tenths of a nanometre, making them suitable for biological samples. X-ray diffraction is used extensively in the determination of structures of proteins, nucleic acids, and other natural products (an early landmark was the determination of the structure of penicillin). In order to resolve the phase differences, much use has been made of **isomorphous replacement** with heavy metal atoms.

X-ray photoelectron spectroscopy *abbr.*: XPS; *see* **photoelectron spectroscopy**.

X-rays *or (sometimes, esp. US)* **x-rays** *or (formerly)* **röntgen rays** electromagnetic radiation emitted by atoms during extranuclear loss of energy of incident radiation (e.g. high-energy electrons, gamma radiation) or by atoms of certain radionuclides during transformation by **electron capture**. X-rays have wavelengths in the range 1 pm–10 nm (frequencies 3 PHz–3 EHz), which lies above that of gamma radiation and overlaps the wavelengths of the far ultraviolet. Characteristic X-rays have specific wavelengths of a particular nuclide or target element. *See also* **bremsstrahlung**, **synchrotron**.

XRE *abbr. for* xenobiotic-response element.

XTP *abbr. for* xanthosine (5′-)triphosphate.

Xul *symbol for* a residue (or a molecule) of the ketopentose xylulose.

xyl+ *a variant (sometimes before a vowel)* of **xylo+**.

Xyl *symbol for* a residue (or a molecule) of the aldopentose xylose.

xylan any homopolysaccharide of **xylose**, consisting mainly of *β*-1,4-linked xylopyranose units with various substituent groups, that occurs in the cell walls of higher plants, and in some marine algae. Xylans form the major glycans of the **hemicellulose** in the fibrous parts of plants.

xylaric acid the **aldaric acid** derived from **xylose**.

xylE a gene in *Escherichia coli* encoding a xylose transport protein that contains 12 transmembrane segments and is an H$^+$–xylose symporter. The gene is induced by xylose. *See also* **sugar transporter**.

xylem the vascular tissue that conducts water and mineral salts from the roots to the aerial parts of a plant and provides it with mechanical support.

xylene cyanol a dye used as a mobility marker in agarose gel electrophoresis.

L-xylitol reductase EC 1.1.1.10; an enzyme of the glucuronate pathway that catalyses the reaction:

$$\text{xylitol} + \text{NADP}^+ = \text{L-xylulose} + \text{NADPH} + \text{H}^+.$$

Deficiency of the enzyme results in essential pentosuria.

xylo+ *or (sometimes before a vowel)* **xyl+** *comb. form indicating the trivial name for* the aldopentose xylose.

xylo- *prefix (in chemical nomenclature)* indicating a particular configuration of a set of three contiguous >CHOH groups, as in the acyclic form of D- or L-xylose. *See* **monosaccharide**.

xylose *symbol*: Xyl; *xylo*-pentose; a constituent of plant polysaccharides (*see* **xylan**); the naturally occurring enantiomer is always D-xylose. In humans most ingested xylose is excreted unchanged in the urine. This is the basis for the **xylose absorption test**, the most widely used test of carbohydrate absorption.



β-D-pyranose form

xylose isomerase EC 5.3.1.5; *systematic name*: D-xylose ketol-isomerase; an enzyme that catalyses the reaction:

$$\text{D-xylose} = \text{D-xylulose};$$

magnesium ions are a cofactor. The 3-D structure is known, and it is a **beta-barrel** protein.

xylose-1-phosphate uridylyltransferase *see* **UTP–xylose-1-phosphate uridylyltransferase**.

xylulose *symbol*: Xul; *the trivial name for* the ketopentose *threo*-2-pentulose; D-xylulose is the naturally occurring enantiomer. Excessive excretion of xylulose in the urine is called essential pentosuria.



α-D-xylulose

D-xylulose 5-phosphate the 5-phosphate ester of D-xylulose and a component of the **pentose phosphate pathway**. It is formed from D-ribulose 5-phosphate by ribulose-phosphate 3-epimerase (EC 5.1.3.1); D-xylulose 5-phosphate then reacts with D-ribose 5-phosphate, catalysed by **transketolase**, to give glyceraldehyde 3-phosphate and sedoheptulose 7-phosphate.

X-Y-Z-cell theory a theory of immunocyte maturation that proposes that the first committed immunocyte, the **X cell**, is transformed by antigen into a memory cell, the **Y cell**, in the primary response, and is further stimulated in the secondary response to become an antibody producer, the **Z cell**.

Yy

y *symbol for* yocto+ (SI prefix denoting 10^{-24} times).

y *symbol for* **1** amount-of-substance fraction (i.e. mole fraction) or number fraction for gases. *Compare* ***x***. **2** a Cartesian space coordinate, complementary to *x* and *z*.

Y *symbol for* **1** yotta+ (SI prefix denoting 10^{24} times). **2** a residue of the α-amino acid L-tyrosine (alternative to Tyr). **3** a residue of an incompletely specified base in a nucleic-acid sequence that may be either cytosine or thymine. **4** a residue of an unspecified pyrimidine nucleoside (alternative to Pyd). **5** a residue of the minor nucleoside **wyosine** (alternative to W). **6** yield. **7** yttrium.

Y *symbol for* admittance (reciprocal of impedance).

YAC *abbr. for* yeast artificial chromosome.

Yang cycle *see* **methionine salvage pathway**.

Yb *symbol for* ytterbium.

Y cell *see* **X-Y-Z-cell**.

Y chromosome a **sex chromosome** found only in the **heterogametic** sex and usually different in size from the **X chromosome**. In many animals it carries the testis-determining factor that triggers male embryonic development.

yeast any of a group of unicellular fungi that reproduce asexually – by budding or fission – and sexually – by the production of ascospores. Yeast cells may occur singly or in short chains, and some species produce a mycelium. The term 'yeast' is often used to mean members of the genus *Saccharomyces*, e.g. *S. cerevisiae*), which is an example of a budding yeast, or *Schizosaccharomyces pombe*, which is an example of a fission yeast.

yeast artificial chromosome *abbr.*: YAC; a specialized cloning vector that contains a **centromere**, an autonomously replicating sequence (ARS), a pair of **telomeres**, selectable marker genes, and the fragment of DNA to be cloned. Usually, genomic DNA is digested to produce fragments containing the genes, which are separated by **pulsed field gel electrophoresis**; the large fragments are then ligated into YACs. They are capable of propagation in yeasts, where they function as 'artificial chromosomes', being efficiently replicated. YACs are essential in large mapping projects, such as the Human Genome Project (*see* **HUGO**), as they are stable and can carry vast DNA inserts of 100 to 1000 kbp.

yeast cloning any method of cloning using yeast as the host. Expression of eukaryote genes by yeasts and other microbial eukaryotes is subject to eukaryotic regulatory systems, and the products undergo post-translational modification in contrast to when they are expressed in prokaryotes. Thus, yeast clones are often used for the expression of glycoproteins.

yeast eluate factor *a former term for* **vitamin B_6**.

yeast filtrate factor *a former term for* pantothenic acid. *See* **pantothenate**.

yeast nucleic acid *a former term for* **ribonucleic acid**.

yeast two-hybrid system a system that exploits two hybrid proteins, X, fused to the GAL4 DNA-binding domain, and Y, fused to the GAL4 activation domain. Plasmids encoding each of the hybrid proteins are introduced together into yeast, which leads to the expression of both hybrids. The system is used to test whether protein Y binds to protein X, for example in investigating the role of newly discovered proteins. If the proteins do bind, the resulting complex will be bound to the upstream activation sequence for the yeast *GAL* genes by the GAL4 DNA-binding domain, and the presence of the GAL4 activation domain will lead to transcriptional activation of the **reporter gene**, i.e. β-galactosidase. The system has the advantage over immunoprecipitation that if Y binds to X, the gene encoding it is already available as a clone. The hybrid containing X is referred to as the **bait**.

yellow enzyme **1 old yellow enzyme**, EC 1.6.99.1; NADPH dehydrogenase; a flavoprotein (FMN in yeast, FAD in plants). **2 new yellow enzyme** *an alternative name for* D-amino-acid oxidase; *see* **amino-acid oxidase**.

yellow fever virus There are two kinds of fever; **jungle** which is a disease of monkeys which is spread by infected mosquitoes; rare in humans; and **urban**, a disease of humans caused by infected mosquitoes *Aedes aegypti*. The virus is a member of the *Flaviviridae* with a sense plus RNA genome translated to a polyprotein of envelope, membrane and capsid proteins. Vaccination is by live-attenuated 17D strain.

yellow marrow *see* **bone marrow**.

***Yersinia* murine toxin** *see* **murine toxin**.

YES **v-***yes* is the oncogene of the Yamaguchi sarcoma virus, and has a cellular counterpart, **c-***yes*, the product of which is a member of the *src* family of non-receptor tyrosine kinases, having a myristoylation site, and SH2, SH3 and tyrosine kinase domains.

yield *symbol*: Y; a ratio expressing the efficiency of a mass conversion process. The yield coefficient is defined as the amount of cell mass or product formed related to the consumed substrate or to the intracellular ATP production.

yin-yang hypothesis a model of biological regulation based on the opposing actions of certain cyclic nucleotides. It arises from the observation that hormones or other biologically active substances that promote the cellular accumulation of cyclic GMP produce cellular responses that are antagonistic to ones occurring when the concentration of cyclic AMP is increased in the same tissues or cells. Hence cyclic GMP and cyclic AMP may have opposing or antagonistic regulatory influences in certain biological systems, by analogy with the oriental concept of yin and yang symbolizing a dualism between opposing natural forces.

+yl *suffix (in chemical nomenclature)* denoting a free valence derived from the loss of a hydrogen atom from a parent hydride, e.g. methyl, pentanyl. It also applies to particular acyl groups, that are exceptions to the rule that acyl groups are named by changing the '-ic acid' or '-oic acid' ending to '-oyl'. These exceptions are acetyl, malonyl, succinyl, propionyl, butyryl, oxalyl, and glutaryl.

yocto+ *symbol*: y; SI prefix denoting 10^{-24} times.

yohimbine an indole alkaloid, $C_{21}H_{26}N_2O_3$, with α_2-adrenoceptor antagonist activity. It is produced by *Corynanthe johimbe* and *Rauwolfia serpentina*.



Yop *abbr. for Yersinia* outer protein; any of a number of proteins, known as virulence proteins, originally found on the surface of Gram-negative bacteria of the genus *Yersinia*; they are now known to be characteristic of plant-pathogenic proteins that are secreted by bacteria of genera as diverse as *Pseudomonas*, *Xanthomonas*, and *Erwinia*. They are also produced by animal pathogens, such as *Shigella flexneri*, *Salmonella typhimurium*, and *Escherichia coli.* They are secreted by the **type III system**. Unlike other secreted proteins, they lack a signal sequence.

yotta+ *symbol*: Y; SI prefix denoting 10^{24} times.

Yphantis method *an alternative name for* **meniscus depletion method** (**sedimentation equilibrium**).

Zz

z *symbol for* zepto+ (SI prefix denoting 10^{-21} times).

z *symbol for* **1** charge number of an ion. **2** a Cartesian space coordinate, complementary to *x* and *y*.

Z *symbol for* **1** zetta+ (SI prefix denoting 10^{21} times). **2** a residue of either of the *α*-amino acids L-glutamic acid or L-glutamine when the state of amidation is uncertain (alternative to Glx). It may also be used to represent a residue of any other substance, such as 4-carboxy-L-glutamic acid (as alternative to Gla) or 5-oxo-L-proline (as alternative to Glp), that yields glutamic acid on acid hydrolysis of peptides. **3** the **benzyloxycarbonyl** group (alternative to Cbz).

Z *symbol for* **1** proton number. **2** impedance.

(*Z*)- *prefix (in chemical nomenclature)* denoting a geometric isomer in which the highest priority substituent groups, determined according to the Cahn–Ingold–Prelog rules (*see* **sequence rule**), are located on the same side of a double bond. *See also* ***E/Z*** **convention**.

zalcitabine *or* **2′,3′-dideoxycytidine** (*abbr.*: ddC); an inhibitor of reverse transcriptase that is used in the treatment of HIV-1 infection.

Zantac *see* **ranitidine**.

ZAP *abbr. for* zinc finger antiviral protein; a protein (776 amino acids) of rat that contains four zinc fingers (of C_4H type). When expressed in fibroblasts in cell culture it confers specific antiviral activity.

ZAP-70 *or* **zeta chain-associated tyrosine kinase** a protein-tyrosine kinase (70 kDa) that associates with the ζ subunit that functions as part of the **T-cell receptor** and **CD3** complex in lymphocytes. It contains two SH2 domains, which interact with immunoglobulin tyrosine-based motifs on ζ or other subunits of these complexes. Rare inactivating mutations in the ζ chain gene cause **severe combined immunodeficiency** (SCID).

zaragozic acid any of a family of fungal metabolites that are potent inhibitors of squalene synthase.



zaragozic acid A

Z-average relative molecular mass *see* **average relative molecular mass**.

Z cell *see* **X-Y-Z cell theory**.

Z disk *or* **Z line** a platelike region of a muscle **sarcomere** to which the plus ends of actin filaments are attached. It is seen as a dark transverse line in micrographs.

Z-DNA *abbr. for* Z form of DNA.

zeatin *trans*-zeatin; (*E*)-2-methyl-4-(1*H*-purin-6-ylamino)-2-buten-1-ol; a plant hormone of the **cytokinin** class. Its derivative, *trans*-zeatin riboside (N^6-(*trans*-4-hydroxy-3-methyl-*cis*-2-buten-1-yl)adenosine) is also a cytokinin. The *cis* form is a rare component in some RNA structures.



zebrafish *Brachydanio rerio*; a small, highly fertile species of characinoid teleost fish with a shiny blue body and four longitudinal yellowish stripes along its sides. It is much used in studies on the molecular biology of differentiation and development in metazoan animals.

Zeeman effect the splitting of a single line in a spectrum, indicative of the degeneration of the excited state of a particular chromophore, into two or more components of slightly different wavelengths brought about by the application of an external magnetic field. [After Pieter Zeeman (1865–1943), Dutch physicist.]

zein the principal storage protein of maize (corn) seeds. It is relatively deficient in the essential amino acids lysine and tryptophan; tryptophan deficiency can occur in human populations dependent on maize as the major protein source. The zein genes are clustered.

Zellweger syndrome *or* **cerebrohepatorenal syndrome** a heterogeneous disorder of peroxisome biogenesis that results from mutations in at least 11 loci for PEX proteins (*see* **peroxin**), most commonly for PEX1. Typically patients have multiple congenital anomalies of the face and head, ongoing metabolic disturbances with accumulation of very-long-chain fatty acids, and usually die in infancy. Infantile **Refsum's disease** is one form of the syndrome. [After Hans Ulrich Zellweger (1909–1990), US paediatrician.]

zeolite any porous alkali metal- or alkaline earth-aluminium silicate that shows ion-exchange properties. Zeolites may be used for water softening or as molecular sieves. —**zeolitic** *adj.*

zepto+ *symbol*: z; SI prefix denoting 10^{-21} times.

zero-order kinetics kinetics shown by a **zero-order reaction**.

zero-order reaction a chemical reaction whose velocity is independent of the concentration of one or more of the reactants. *See* **order of reaction**.

zeroth law of thermodynamics *see* **thermodynamics, laws of**.

zervamicin *see* **peptaibophol**.

zeta *symbol*: ζ (lower case) *or* Z (upper case); the sixth letter of the Greek alphabet. For uses *see* **Appendix A**.

zeta chain **1** a transmembrane protein (16 kDa) of most T cells that contains three intracellular immunoreceptor tyrosine-based activation motifs (ITAMs) to which protein tyrosine kinases (e.g. **ZAP-70**) bind. It forms a dimer of disulfide-linked chains that are tightly associated with components of CD3 and T-cell receptors. **2** the α-globin-like globin that with γ-globin forms Hb Portland I, and with ε-globin forms Hb Gower I, in the first few weeks of human embryonic development. *See* **hemoglobin**.

zeta chain-associated tyrosine kinase *an alternative name for* **ZAP-70**.

zeta potential *symbol*: *ζ*; the potential at the surface of shear of a charged particle; for macromolecular ions it is the potential at the surface of the **hydrodynamic particles** formed by such ions.

zeta protein *an alternative name for* cellular **fibronectin**.

zetta+ *symbol*: Z; SI prefix denoting 10^{21} times.

zeugmatography a technique in which the addition of carefully controlled inhomogeneous magnetic fields enables measurements of **nuclear magnetic resonance** (NMR) to be made at selected regions of heterogeneous samples and hence the formation of two-dimensional maps of the distribution of almost any property measurable by NMR.

Zfn *abbr. for* zinc finger nuclease; a synthetic chimeric protein that contains three C_2H_2 zinc fingers and a nonspecific DNA cleavage domain.

Z form of DNA *abbr.* Z-DNA or DNA-Z; a form of DNA consisting of a left-handed double helix in which the pyrimidine residues are always in the *anti* orientation and the purine residues in the *syn*. So-called because of the zig-zag appearance of its conformation. *See also* **A form** (def. 1), **B form**, **C form**.

Zfp *abbr. for* zinc finger protein.

zidovudine 3′-azido-3′-deoxythymidine (*abbr.*: AZT); an analogue of thymidine, the phosphorylated form of which is an inhibitor of **reverse transcriptase** in **retroviruses**; it also terminates DNA synthesis. Zidovudine undergoes phosphorylation in human T cells to a nucleoside 5′-triphosphate, which competes with thymidine triphosphate (TTP) and serves as a chain-terminating inhibitor of **HIV** reverse transcriptase. It is used clinically to treat patients with HIV infection and AIDS. *Proprietary name*: Retrovir.



Zimm–Crothers viscometer a modified **Couette viscometer** in which the inner cylinder is a self-centring float containing a steel pellet. The inner cylinder is rotated by an external rotating magnetic field, the speed of rotation being dependent, *inter alia*, on the viscosity of the fluid. The instrument only measures the viscosity of a sample relative to a standard.[After Bruno H. Zimm (1920–) US chemist and Donald M. Crothers (1937–) US biophysical chemist.]

Zimmermann reaction the reaction of *m*-nitrobenzene in strongly alkaline solution with the methylene group at position 16 in 17-ketosteroids to give a purple colour with an absorption maximum at 520 nm. It may be used to estimate such steroids.

Zimm plot a graphical double extrapolation used to analyse most macromolecular light-scattering data. Measurements are made of Kc/R_θ at various concentrations as a function of the scattering angle, 2θ, where K is an optical constant, c is the concentration, and R_θ is the Rayleigh ratio. A series of plots of Kc/R_θ against $(\sin^2\theta + K'c)$ are made, where K' is an arbitrary constant chosen to provide a convenient spread. The data are then extrapolated separately to $c = 0$ and $\theta = 0$. The intersection of the two extrapolated curves yields the relative molecular mass.

zinc *symbol* Zn; a metal of group 12 of the IUPAC **periodic table**; relative atomic mass 65.38; atomic number 30. The principal ore is zincblende, ZnS. Its oxidation state is Zn(II). Zinc oxide is used as an antiseptic. Naturally occurring nuclides include (relative abundance follows each) $^{64}_{30}\mathrm{Zn}$ (48%), $^{66}_{30}\mathrm{Zn}$ (28%), $^{68}_{30}\mathrm{Zn}$ (18%). Radionuclides include **zinc-62**, **zinc-65**, and **zinc-72**. Dietary deficiency in the rat is manifested by retarded growth, alopecia, and lesions in the skin, esophagus, and cornea. Deficiency is rare in normal individuals, but can manifest itself in alcoholics and in patients with renal disease or malabsorption. Zn^{2+} is an essential cofactor for many enzymes. Recent work suggests zinc is bactericidal.

zinc-62 the artificial radioactive nuclide $^{62}_{30}\mathrm{Zn}$; it emits a positron (β^+ particle) (0.66 Mev), and γ-radiation of four energies (0.041, 0.25, 0.51, and 0.60 Mev). It has a half-life of 9.26 h.

zinc-65 the artificial radioactive nuclide $^{65}_{30}\mathrm{Zn}$; it emits a positron (β^+ particle) (0.325 Mev) and γ-radiation (1.12 Mev). It has a half-life of 244.1 days.

zinc-72 the artificial radioactive nuclide $^{72}_{30}\mathrm{Zn}$; it emits an electron (β^- particle) (0.3 Mev) and γ-radiation of three energies (0.016, 0.145, and 0.192 Mev). It has a half-life of 1.938 days.

zinc finger a polypeptide motif present in many DNA-binding proteins, and having the consensus sequence

$$\text{-}CX_{2-4}CX_3FX_5LX_2HX_3H\text{-}.$$

The motif takes its name from its zinc-binding site, which forms a finger-like loop in the peptide, also described as the **Cys_2/His_2 finger**, the Cys and His residues coordinating a zinc ion. Zinc fingers are most notably present in **transcription factors** (e.g., TFIIIA and SP1), which have several repeats of the motif; they are required for binding of the transcription factor to DNA.

ZIP 1 *abbr. for* the leucine zipper domain. *See also* **bZIP**. **2** a family of membrane proteins involved in import of zinc into the cytoplasm in eukaryotes. They are predicted to contain eight transmembrane segments, of which S4 and S8 are highly conserved and contain conserved histidine residues, which may be involved in metal binding.

Z line *another name for* **Z disk**.

Zn *symbol for* zinc.

ZNF9 a protein that contains seven zinc finger motifs, binds RNA, and is expressed in skeletal and heart muscle. Expansion of a CCTG tetranucleotide repeat in intron 1 of the gene causes myotonic dystrophy type 2.

Zollinger–Ellison syndrome a disease syndrome caused by excessive secretion of **gastrin**, either from (type 1) **G-cell** hyperplasia in the antrum of the stomach, or from (type 2) a benign or malignant pancreatic islet tumour (**gastrinoma**). The manifestations include multiple peptic ulcers, or peptic ulcers in unusual sites, with a marked tendency to bleeding, often associated with hyperparathyroidism. [After Robert M. Zollinger (1903–) and Edwin H. Ellison (1918–70).]

zona adherens *see* **desmosome**.

zonadhesin a protein of spermatozoa, probably present in the acrosome, that binds to ZP3 of the zona pellucida of mammalian ova.

zona fasciculata *see* **adrenal gland**.

zona glomerulosa *see* **adrenal gland**.

zonal centrifugation *an alternative name for* **density-gradient centrifugation**.

zonal centrifuge a centrifuge designed to allow large-scale and continuous fractionation by **density-gradient centrifugation**.

zonal rotor any centrifuge rotor of high capacity used preparatively in a **zonal centrifuge**.

zona occludens *an alternative name for* **tight junction**.

zona pellucida a layer of glycoproteins that surrounds a mammalian ovum and disappears before implantation. It is secreted by cells of the Graafian follicle. *See also* **ZP**.

zona pellucida sperm-binding protein *abbr.*: ZP; any of the sulfated transmembrane glycoproteins (ZP1, ZP2, ZP3) that together form the zona pellucida of the oocyte. ZP3 is a sperm receptor.

zona reticularis *see* **adrenal gland**.

zone electrophoresis a method of **electrophoresis** in which the protein (or other) solution is placed at the starting position as a thin band or spot in an inert supporting medium (paper, starch gel, polyacrylamide gel, etc.), containing buffer solution. An electric potential is then applied to the supporting medium, causing the proteins (or other substances) to migrate to give distinct bands or zones. These may be located *in situ* by staining, light absorption, etc., or by analysis after elution of discrete pieces of the supporting medium.

zone precipitation a technique in which protein is precipitated as a zone in a gel-filtration column by eluting with a gradient of a protein-precipitating agent. *See* **gel-permeation chromatography**.

zone spreading the broadening of a zone in electrophoresis or chromatography due to eddy currents or other disturbances in the supporting medium.

zoo blot a method for detecting conservation of DNA sequence during evolution. A segment of DNA being investigated is used as a probe to hybridize against a series of DNA samples from various species, and hence establish whether the DNA sequence has been conserved during evolution.

zoonosis (*pl.* **zoonoses**) any disease that can be transmitted to humans from other animals in natural circumstances.

zooplankton *see* **plankton**.

zootoxin any poisonous substance formed by animal cells.

Zovirax *a proproetary name for* **acyclovir**.

ZP *abbr. for* zona pellucida protein; any of three glycoproteins (ZP1, ZP2, and ZP3) present in the zona pellucida of mammalian ova. ZP3 binds the sperm proteins p47, Sp56, and zonadhesin, which may be present in the acrosome.

Zr *symbol for* zirconium.

Z ring a contractile ring of proteins that forms in the mid-region of the inner side of the plasma membrane of bacteria as part of cell division, normally towards the end of replication. Formation is initiated by **FtsZ** and depends on the presence of the **Min** system for correct localization.

Z scheme a term applied to two-system photosynthetic light reactions, utilizing both **photosystems** I and II. It describes the mode of photosynthesis used by higher plants and algae, and by cyanobacteria. As it is normally plotted, with redox potential (on the ordinate) against time, it shows there is a sudden jump on excitation by a photon of a reaction centre, followed by a slow decline through electron transport components, and gives a (horizontal) Z-like appearance, hence the name.

zuotin a nuclear Z-DNA-binding protein of *Saccharomyces cerevisiae*.

zwischenferment *an obsolete term for* the enzyme–coenzyme complex of **glucose-6-phosphate dehydrogenase.**

Zwittergent *the proprietary name for* any of a group of zwitterionic detergents containing a **betaine** and a sulfonate group; such molecules retain their amphoteric (zwitterionic) properties over a very wide range of pH. The formula is *n*-alkyl *N*,*N*-dimethyl-3-ammonio-1-propanesulfonate. In Zwittergent 3-08, alkyl is octyl (CMC 330 mm); 3-10, decyl (aggregation number 41, CMC 25–40 mm); 3-12, dodecyl (aggregation number 55, CMC 2–4 mm); 3-14, tetradecyl (aggregation number 83, CMC 0.1–0.4 mm); 3-16, hexadecyl (aggregation number 155, CMC 0.01–0.06 mm).

zwitterion *an alternative name for* **dipolar ion**.

zwitterionic buffer a **buffer solution** whose acid or base component is a zwitterion (i.e. **dipolar ion**). The term is used especially of solutions of **Good buffer substances** and newer equivalents.

zygote any fertilized ovum before it has undergone cleavage. **—zygotic** *adj.*

zygotene the second phase of prophase I in **meiosis**.

zymase the name originally given to the heat-labile, nondiffusible fraction of a crude extract of brewers' yeast that, with the addition of the heat-stable, diffusible fraction (i.e. **cozymase**), would enable the alcoholic fermentation of glucose to occur in a cell-free system. It was later shown to consist of a mixture of enzymes, including those of the **glycolytic pathway**.

zymogen *or* **proenzyme** *or (formerly)* **proferment** the inactive precursor of an enzyme, often convertible to the enzyme by partial proteolysis. The term is applied especially to catalytically inactive forms of pancreatic enzymes such as trypsinogen, chymotrypsinogen, proelastase, and procarboxypeptidase; these are cleaved to release the active enzyme after their secretion from granules (**zymogen granules**) in the acinar cells of the pancreas.

zymogen granule a membrane-bound, cytoplasmic **secretory granule** visible by light microscopy. Zymogen granules are formed in the Golgi apparatus of enzyme-secreting cells and serve to store a **zymogen**. The term is used especially of a secretory granule containing the proenzyme of a digestive enzyme.

zymogram **1** any record of a **zone electrophoresis** separation in which enzymes in a sample have been separated and their positions, and relative amounts, revealed by an **activity stain**. **2** any table showing the results of carbohydrate-fermentation tests carried out in the process of identifying a microorganism.

zymology the science dealing with fermentations. **—zymological** *adj.*; **zymologist** *n.*

zymosan a crude preparation of yeast cell walls, consisting chiefly of polysaccharide, that activates the alternative pathway of the complement system in the presence of properdin.

zymosterol cholesta-8,24-dien-3*β*-ol; a sterol present in yeasts e.g. *Candida albicans*, *Saccharomyces cerevisiae*.

zymurgy the branch of chemistry dealing with the applications of fermentation processes, especially to brewing and wine-making.

Zyvox *another name for* Linezolid.

zyxin a protein component of cell substratum and cell–cell adherens junctions. It is a component of adhesion plaques and the termini of stress fibres near the point of association with the cytoplasmic face of the adhesive membrane; it interacts with α-actinin.

Appendices

Appendix A

The Greek alphabet

The Greek alphabet

Name	Capital letter	Lower-case letter	English transliteration
alpha	Α	α	a
beta	Β	β	b
gamma	Γ	γ	g
delta	Δ	δ	d
epsilon	Ε	ε	e
zeta	Ζ	ζ	z
eta	Η	η	ē *or* e
theta	Θ	θ	th
iota	Ι	ι	i
kappa	Κ	κ	k
lambda	Λ	λ	l
mu	Μ	μ	m
nu	Ν	ν	n
xi	Ξ	ξ	x
omicron	Ο	ο	o
pi	Π	π	p
rho	Ρ	ρ	r
sigma	Σ	σ or ς (at end of word)	s
tau	Τ	τ	t
upsilon	Υ	υ	u
phi	Φ	φ	ph
chi	Χ	χ	kh
psi	Ψ	ψ	ps
omega	Ω	ω	ō *or* o

Single-character symbols

α	(*or* α) **1** a heavy chain of immunoglobulin A. **2** maximal agonist effect. **3** alpha particle.
α	(*or* α) **1** angle of optical rotation (α_{obs} is used for observed rotation and $[\alpha]$ for specific optical rotation *or* specific optical rotatory power; α_{m} is used for molar optical rotatory power). **2** absorptance. **3** (linear) napierian absorption coefficient. **4** Bunsen coefficient. **5** partition coefficent. **6** plane angle. **7** *(in organic chemical nomenclature)* a locant for a substituent on the first atom from the atom carrying the principal function in an acyclic structure or in a side chain attached to a cyclic structure. **8** an anomeric configuration (of a sugar molecule or residue; *see* **anomer**). **9** winding number (of a helical duplex DNA molecule).
β	(*or* β) beta particle (β^- is used for an electron and β^+ for a positron).
β	(*or* β) **1** buffer value. **2** pressure coefficient. **3** plane angle. **4** *(in organic chemical nomenclature)* a locant for a substituent on the second atom from the atom carrying the principal function in an acyclic structure or in a side chain attached to a cyclic structure. **5** an anomeric configuration (of a sugar molecule or residue; *see* **anomer**). **6** number of secondary turns (in an unconstrained helical duplex DNA molecule).
γ	(*or* γ) a heavy chain of immunoglobulin G. **2** a photon of gamma radiation. **3** *(obsolete)* microgram (μg now used).
γ	(*or* γ) activity coefficient (γ_{c} is used for activity coefficient when expressed on a concentration basis, γ_{m} when expressed on a molality basis, γ_{x} when expressed on a mole fraction basis, and $\gamma_{\pm}$ is used for mean ionic activity coefficient). **2** electrical conductivity (alternative to κ or σ). **3** mass concentration *or* mass density (alternative to ρ). **4** plane angle. **5** surface tension *or* interfacial tension (alternative to σ). **6** gyromagnetic ratio. **7** *(in organic chemical nomenclature)* a locant for a substituent on the third atom from the atom carrying the principal function in an acyclic structure or in a side chain attached to a cyclic structure.
δ	(*or* δ) **1** a heavy chain of immunoglobulin D. **2** (*in mathematics*) an infinitesimal change or difference.
δ	(*or* δ) **1** chemical shift. **2** number fraction. **3** *(in organic chemical nomenclature)* a locant for a substituent on the fourth atom from the atom carrying the principal function in an acyclic structure or in a side chain attached to a cyclic structure.
Δ	(*or* Δ**)** (*in mathematics*) a finite change or difference.
Δ	(*or* Δ) *(in older organic chemical nomenclature)* a locant for a double bond (a right superscript number designates the lower-numbered carbon atom; see **fatty-acid nomenclature**); no longer recommended for denoting unsaturation in names of individual compounds although it may still be used in generic terms (e.g. Δ^5-steroid) and in symbols (e.g. Δ_2Ach).
ε	(*or* ε) a heavy chain of immunoglobulin E.
ε	(*or* ε) **1** molar (decadic) absorption coefficient. **2** permittivity (ε_{r} is used for relative permittivity and ε_0 for permittivity of vacuum). **3** *(in organic chemical nomenclature)* a locant for a substituent on the fifth atom from the atom carrying the principal function in an acyclic structure or in a side chain attached to a cyclic structure. **4** (*in chemical nomenclature*) hapticity of a ligand (less common alternative to η; *see* **hapto**).
ε_{a}	degree of activation (of an enzymic reaction).

$\boldsymbol{\varepsilon_i}$	degree of inhibition (of an enzymic reaction).
$\boldsymbol{\varepsilon^{v}_{s}}$	elasticity coefficient (of a specific enzymic step in a metabolic system).
ζ	(*or* ζ) electrokinetic potential *or* zeta potential.
η	(*or* η) **1** viscosity (alternative to μ). **2** *(in chemical nomenclature)* hapticity (of a ligand; more common alternative to ε; *see* **hapto**).
θ	(*or* θ) **1** Bragg angle (*see* **Bragg's law**). **2** (*in surface chemistry*) contact angle. **3** plane angle. **4** torsion angle (in a linear sequence of four attached atoms; alternative to ω). **5** Celsius temperature (alternative to t).
$\boldsymbol{\Theta_m}$	melting temperature (alternative to T_m *or* t_m).
$\boldsymbol{[\Theta]}$	molar ellipticity.
$\mathrm{\kappa}$	(*or* $\mathrm{\kappa}$) one type of light chain of any class of immunoglobulin (the other being $\mathrm{\lambda}$).
κ	(*or* κ) **1** electrical conductivity (alternative to γ or σ). **2** electrolytic conductivity *or* (*formerly*) specific conductance. **3** molar napierian absorption coefficient. **4** magnetic susceptibility (alternative to χ). **5** (*in inorganic chemical nomenclature*) an affix in the name of a polydentate chelate complex indicating single attachments of a polydentate ligand to a coordination centre. A right superscript numerical index indicates the number of such attachments.
$\mathrm{\lambda}$	(*or* $\mathrm{\lambda}$) **1** one type of light chain of any class of immunoglobulin (the other being $\mathrm{\kappa}$). **2** *(obsolete)* microlitre (µl now used).
λ	(*or* λ) **1** (*in thermodynamics*) absolute activity (*see* **activity**, def. 4). **2** disintegration constant *or* decay constant. **3** wavelength. **4** thermal conductivity (alternative to k).
Λ	(*or* Λ) molar conductivity (of an electrolyte).
$\mathrm{\mu}$	(*or* $\mathrm{\mu}$) a heavy chain of immunoglobulin M. **2** micro+ (SI prefix denoting 10^{-6} times). **3** (*obsolete*) micron (now called micrometre; symbol: µm).
μ	(*or* μ) **1** *(in chemical nomenclature)* a bridging ligand. **2** viscosity (alternative to η). **3** chemical potential (μ° *or* $\mu^{\ominus}$ is used for standard chemical potential and $\mu^{\sim}$ is used for electrochemical potential). **4** electric mobility (alternative to u). **5** *(in magnetism)* permeability (μ_r is used for relative permeability). **6** magnetic dipole moment (bold italic) (alternative to $\boldsymbol{m}$). **7** electric dipole moment (bold italic) (alternative to $\boldsymbol{p}$).
$\boldsymbol{\mu_0}$	permeability of vacuum (a fundamental physical constant).
$\boldsymbol{\mu_B}$	Bohr magneton (a fundamental physical constant).
$\boldsymbol{\mu_e}$	electron magnetic moment (a fundamental physical constant).
$\boldsymbol{\mu_N}$	nuclear magneton (a fundamental physical constant).
$\boldsymbol{\mu_p}$	proton magnetic moment (a fundamental physical constant).
ν	(*or* ν) **1** stoichiometric number (of a chemical reactant). **2** frequency (alternative to f for electromagnetic radiation). **3** kinematic viscosity. **4** endocyclic torsion angle (in a sugar residue).
ξ	**1** (*in organic chemical nomenclature*) unknown configuration at a chiral centre. **2** extent of reaction.
$\dot{\xi}$	rate of conversion.
$\mathrm{\pi}$	(*or* $\mathrm{\pi}$) a transcendental number that is the ratio of the circumference of a circle to its diameter (3.141 592 653 59...).
π	(*or* π) **1 pros**. **2** (*or* π^{s}) surface pressure.
Π	(*or* Π) **1** osmotic pressure (Π_D may be used to represent colloid osmotic pressure). **2** binding potential (of a ligand).
ρ	(*or* ρ) **1** density *or* mass density (ρ_A *or* ρ_S is used for surface density). **2** mass concentration *or* mass density (alternative to γ). **3** radiant energy density (alternative to w). **4** charge density. **5** resistivity.
σ	(*or* σ) **1** surface tension *or* interfacial tension (alternative to γ). **2** electrical conductivity (alternative to γ *or* κ). **3** wavenumber in a medium. **4** surface charge density. **5** *(in surface chemistry)* area per molecule. **6** *(in nuclear magnetic resonance spectroscopy)* shielding constant. **7** superhelix density (of a helical duplex DNA molecule).
Σ	(*or* Σ) *(in mathematics)* a summation sign.
τ	(*or* τ) **1** ***tele***. **2** bond angle. **3** relaxation time *or* time constant (alternative to T). **4** transmittance *or* transmission factor (alternative to T). **5** mean life. **6** number of superhelical turns (in a helical duplex DNA molecule).
φ	(*or* ϕ) **1** osmotic coefficient (ϕ_m is used for osmotic coefficient when expressed on a molality basis and ϕ_x when expressed on a mole fraction basis). **2** electric potential (alternative to V). **3** fluidity. **4** plane angle. **5** phase difference. **6** volume fraction. **7** Dalziel coefficient. **8** torsion angle (from the anomeric carbon atom to the oxygen atom of a glycosidic bond). **9** quantum yield (alternative to Φ). **10** winding angle (of intercalated helical DNA).
Φ	(*or* Φ) **1** heat flow rate. **2** radiant power *or* radiant (energy) flux (alternative to P). **3** magnetic flux. **4** potential energy (alternative to E_p or V). **5** quantum yield (alternative to ϕ).
χ	(*or* χ) **1** electronegativity. **2** magnetic susceptibility (alternative to κ; χ_m is sometimes used, but it should be reserved for molar magnetic susceptibility). **3** surface electric potential. **4** exocyclic torsion angle (in a sugar residue).
ψ	(*or* ψ) **1** replacement of the –CO–NH– group in a peptide by another (indicated) grouping. **2** torsion angle (from the oxygen atom of a glycosidic bond to the glycosylated molecule). **3** wavefunction (alternative to Ψ).
Ψ	(*or* Ψ) **1** a residue of the ribonucleoside pseudouridine (alternative to Ψrd). **2** electric flux. **3** wave function (alternative to ψ).
ω	(*or* ω) **1** angular frequency. **2** angular velocity. **3** solid angle. **4** torsion angle (in a linear assembly of four attached atoms; alternative to θ). **5** (*in organic chemical nomenclature*) a locant for the terminal atom or group in an acyclic organic compound. **6** (*in notation for polyunsaturated fatty acids*) ω-x signifies that a double bond is located on the xth carbon; unlike standard chemical nomenclature it is counted from the distal (methyl carbon) atom.
$\mathrm{\Omega}$	(*or* $\mathrm{\Omega}$) ohm.
$\mathit{\Omega}$	(*or* $\mathit{\Omega}$) solid angle.

Multi-character biochemical symbols commencing with a Greek character

***α*Lnn**	the linolenoyl *or* (9,12,15)-linolenoyl *or* (*formerly*) *α*-linolenoyl (i.e. (*all-Z*)-octadeca-9,12,15-trienoyl) group (alternative to Lnn).
***β*Aad**	a residue of the *β*-amino acid L-*β*-aminoadipic acid (i.e. L-3-aminohexanedioic acid).
***β*Ala**	a residue of the *β*-amino acid *β*-alanine (i.e. 3-aminopropanoic acid).
***γ*Lnn**	the (6,9,12)-linolenoyl *or* (*formerly*) *γ*-linolenoyl (i.e. (*all-Z*)-octadeca-6,9,12-trienoyl) group.
Δ_2Ach	the (*all-Z*)-eicosa-8,11-dienoyl group.
Δ_3Ach	the (*all-Z*)-eicosa-5,8,11-trienoyl group.
Δ_4Ach	the arachidonoyl (i.e. (*all-Z*)-eicosa-5,8,11,14-tetraenoyl) group.
***Δ*Pam**	the palmitoleoyl (i.e. (*Z*)-hexadec-9-enoyl) group.
***ε*Acp**	*see* ***ε*Ahx**.
***ε*Ahx**	*or* (*formerly*) ***ε*Acp** a residue of the *ε*-amino acid 6-aminohexanoic acid (formerly known as *ε*-aminocaproic acid).
***Ψ*rd**	a residue of the ribonucleoside pseudouridine (alternative to *Ψ*).

Appendix B
Sequence-rule priorities

The names of some common ligands are listed alphabetically below, the numbers preceding them indicating the relative priorities assigned to the ligands under the **sequence rule**. A higher number denotes greater preference; for example, a hydroxy group (numbered 57) takes precedence over an amino group (numbered 43). It should be noted that any change to the structure of a listed ligand may alter the order of preference. Where a ligand consists of or contains a heavy or radioactive isotope of hydrogen, the relative priorities are tritium > deuterium > protium. Racemates with a single chiral centre are labelled (*RS*); extensions of the sequence rule are used in the *E*/*Z*, *pro-R*/*pro-S*, *pro-E*/*pro-Z*, and *Re*/*Si* nomenclature systems.

64	acetoxy
36	acetyl
48	acetylamino
21	acetylenyl
10	allyl
43	amino
44	ammonio (^+H_3N–)
37	benzoyl
49	benzoylamino
65	benzoyloxy
13	benzyl
60	benzyloxy
41	benzyloxycarbonyl
50	benzyloxycarbonylamino
75	bromo
42	*tert*-butoxycarbonyl
15	butyl
16	*sec*-butyl
19	*tert*-butyl
38	carboxy
74	chloro
17	cyclohexyl
52	diethylamino
51	dimethylamino
34	2,4-dinitrophenyl
28	3,5-dinitrophenyl
59	ethoxy
40	ethoxycarbonyl
13	ethyl
46	ethylamino
68	fluoro
35	formyl
63	formyloxy
62	glycosyloxy
17	hexyl
11	hydrogen
57	hydroxy
76	iodo
19	isobutyl
18	isopentyl
20	isopropenyl
14	isopropyl
69	mercapto (HS–)
58	methoxy
39	methoxycarbonyl
12	methyl
45	methylamino
71	methylsulfinyl
66	methylsulfinyloxy
72	methylsulfonyl
67	methylsulfonyloxy
70	methylthio (CH_3S–)
11	neopentyl
56	nitro
27	*m*-nitrophenyl
33	*o*-nitrophenyl
24	*p*-nitrophenyl
55	nitroso
16	pentyl
61	phenoxy
22	phenyl
47	phenylamino
54	phenylazo
18	propenyl
14	propyl
29	1-propynyl
12	2-propynyl
73	sulfo (HO_3S–)
25	*m*-tolyl
30	*o*-tolyl
23	*p*-tolyl
53	trimethylammonio
32	trityl
15	vinyl
31	2,6-xylyl
26	3,5-xylyl

The periodic table of the elements

Group

Period

	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18
1	1 H																	2 He
2	3 Li	4 Be											5 B	6 C	7 N	8 O	9 F	10 Ne
3	11 Na	12 Mg											13 Al	14 Si	15 P	16 S	17 Cl	18 Ar
4	19 K	20 Ca	21 Sc	22 Ti	23 V	24 Cr	25 Mn	26 Fe	27 Co	28 Ni	29 Cu	30 Zn	31 Ga	32 Ge	33 As	34 Se	35 Br	36 Kr
5	37 Rb	38 Sr	39 Y	40 Zr	41 Nb	42 Mo	43 Tc	44 Ru	45 Rh	46 Pd	47 Ag	48 Cd	49 In	50 Sn	51 Sb	52 Te	53 I	54 Xe
6	55 Cs	56 Ba	57–71 La–Lu	72 Hf	73 Ta	74 W	75 Re	76 Os	77 Ir	78 Pt	79 Au	80 Hg	81 Tl	82 Pb	83 Bi	84 Po	85 At	86 Rn
7	87 Fr	88 Ra	89–103 Ac–Lr	104 Rf	105 Db	106 Sg	107 Bh	108 Hs	109 Mt	110 Ds	111 Rg	112 Uub	113 Uut	114 Uuq	115 Uup	116 Uuh	117 Uus	118 Uuo

6	**Lanthanoids**	57 La	58 Ce	59 Pr	60 Nd	61 Pm	62 Sm	63 Eu	64 Gd	65 Tb	66 Dy	67 Ho	68 Er	69 Tm	70 Yb	71 Lu
7	**Actinoids**	89 Ac	90 Th	91 Pa	92 U	93 Np	94 Pu	95 Am	96 Cm	97 Bk	98 Cf	99 Es	100 Fm	101 Md	102 No	103 Lr

Correspondence of recommended group designations to other designations in recent use

IUPAC 1990 recommendations	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18
Usual European convention	IA	IIA	IIIA	IVA	VA	VIA	VIIA	VIII (or VIIIA)			IB	IIB	IIIB	IVB	VB	VIB	VIIB	0 (or VIIIB)
Usual N. American convention	IA	IIA	IIIB	IVB	VB	VIB	VIIB	VIII (or VIIIB)			IB	IIB	IIIA	IVA	VA	VIA	VIIA	VIIIA (or 0)

SI base units

Physical quantity	Name of SI unit	Symbol for SI unit
Length	metre	m
Mass	kilogram	kg
Time	second	s
Electric current	ampere	A
Thermodynamic temperature	kelvin	K
Amount of substance	mole	mol
Luminous intensity	candela	cd

SI prefixes

Submultiple	Prefix	Symbol	Multiple	Prefix	Symbol
10^{-1}	deci	d	10	deca	da
10^{-2}	centi	c	10^{2}	hecto	h
10^{-3}	milli	m	10^{3}	kilo	k
10^{-6}	micro	μ	10^{6}	mega	M
10^{-9}	nano	n	10^{9}	giga	G
10^{-12}	pico	p	10^{12}	tera	T
10^{-15}	femto	f	10^{15}	peta	P
10^{-18}	atto	a	10^{18}	exa	E
10^{-21}	zepto	z	10^{21}	zetta	Z
10^{-24}	yocto	y	10^{24}	yotta	Y

Prefix symbols should be printed in roman type with no space between the prefix and the unit symbol. Prefixes should not be combined into compound prefixes.

SI derived units with special names

Physical quantity	Name of SI unit	Symbol for SI unit	Expression in terms of SI base units	
Absorbed dose (of radiation)	gray	Gy	J kg^{-1}	= m^{2} s^{-2}
Activity (radioactive)	becquerel	Bq	s^{-1}	
Catalytic activity	katal	kat	mol s^{-1}	
Celsius temperature	degree Celsius	°C	K	
Dose equivalent (dose equivalent index)	sievert	Sv	J kg^{-1}	= m^{2} s^{-2}
Electric capacitance	farad	F	C V^{-1}	= m^{-2} kg^{-1} s^{4} A^{2}
Electric charge	coulomb	C	A s	
Electric conductance	siemens	S	Ω^{-1}	= m^{-2} kg^{-1} s^{3} A^{2}
Electric potential, electromotive force	volt	V	J C^{-1}	= m^{2} kg s^{-3} A^{-1}
Electric resistance	ohm	Ω	V A^{-1}	= m^{2} kg s^{-3} A^{-2}
Energy, work, heat	joule	J	N m	= m^{2} kg s^{-2}
Force	newton	N	m kg s^{-2}	
Frequency	hertz	Hz	s^{-1}	
Illuminance	lux	lx	cd sr m^{-2}	
Inductance	henry	H	V A^{-1} s	= m^{2} kg s^{-2} A^{-2}
Luminous flux	lumen	lm	cd sr	
Magnetic flux	weber	Wb	V s	= m^{2} kg s^{-2} A^{-1}
Magnetic flux density	tesla	T	V s m^{-2}	= kg s^{-2} A^{-1}
Plane angle*	radian	rad	1	= m m^{-1}
Power, radiant flux	watt	W	J s^{-1}	= m^{2} kg s^{-3}
Pressure, stress	pascal	Pa	N m^{-2}	= m^{-1} kg s^{-2}
Solid angle*	steradian	sr	1	= m^{2} m^{-2}

* The units radian and steradian are also known as 'SI supplementary units'. Names of units, even those derived from proper names, should be printed with lower-case initial letters. Symbols for units should be printed in roman type.

Single-letter and three-letter symbols for amino acids

Amino acid	One letter	Three letter
Alanine	A	Ala
Arginine	R	Arg
Asparagine	N	Asn
Aspartic acid	D	Asp
Cysteine	C	Cys
Glutamine	Q	Gln
Glutamic acid	E	Glu
Glycine	G	Gly
Histidine	H	His
Isoleucine	I	Ile
Leucine	L	Leu
Lysine	K	Lys
Methionine	M	Met
Phenylalanine	F	Phe
Proline	P	Pro
Serine	S	Ser
Threonine	T	Thr
Tryptophan	W	Trp
Tyrosine	Y	Tyr
Valine	V	Val
Unspecified or unknown	X	Xaa

The genetic code

5′ base	Middle base				3′ base
	U	C	A	G	
U	UUU Phe	UCU Ser	UAU Tyr	UGU Cys	U
	UUC Phe	UCC Ser	UAC Tyr	UGC Cys	C
	UUA Leu	UCA Ser	UAA Ter*	UGA Ter*/Sec	A
	UUG Leu	UCG Ser	UAG Ter*	UGG Trp	G
C	CUU Leu	CCU Pro	CAU His	CGU Arg	U
	CUC Leu	CCC Pro	CAC His	CGC Arg	C
	CUA Leu	CCA Pro	CAA Gln	CGA Arg	A
	CUG Leu	CCG Pro	CAG Gln	CGG Arg	G
A	AUU Ile	ACU Thr	AAU Asn	AGU Ser	U
	AUC Ile	ACC Thr	AAC Asn	AGC Ser	C
	AUA Ile	ACA Thr	AAA Lys	AGA Arg	A
	AUG Met†	ACG Thr	AAG Lys	AGG Arg	G
G	GUU Val	GCU Ala	GAU Asp	GGU Gly	U
	GUC Val	GCC Ala	GAC Asp	GGC Gly	C
	GUA Val	GCA Ala	GAA Glu	GGA Gly	A
	GUG Val	GCG Ala	GAG Glu	GGG Gly	G

*Termination codons have no amino acids assigned to them, except that UGA can be the code for Sec; see selenocysteine insertion sequence.

†The AUG codon is the usual initiation codon as well as that for methionine residues elsewhere. The code is almost universal but differences have been found in mitochondrial DNA from some organisms (see the genetic code entry).



The Oxford Dictionary of Biochemistry and Molecular Biology provides a comprehensive survey of current biochemistry and molecular biology. Over the last few years, the language of the discipline has expanded enormously to the extent that few scientists can expect to be familiar with all aspects of it. This is partly due to the Genome and successive '-omics' projects which have provided comprehensive information about genes, the functions of gene products, and cellular processes. At the same time, terms from other subject areas appear increasingly in the biochemical literature. This popular dictionary has been comprehensively reviewed and updated to include many important new concepts and words. The entries are short but informative, providing up-to-date information on a broad range of topics, including definitions for selected terms from the fields of Bioinformatics, Biophysics, Cell Biology, Chemistry, Genetics, Immunology, Mathematics, Microbiology, Pharmacology, Systems Biology, and Toxicology. There are over 21000 main entries, which provide details of biochemical substances and the processes in which they are involved, define methods and concepts in molecular biology, and give definitions of biochemical symbols and abbreviations. They point out pitfalls where terms are often confused, and explain the precise syntax of biochemical terms such as Greek letters and other formatting, which are invariably lost when searching the Internet. In addition, the dictionary is generously illustrated with over 900 chemical structures.

The Oxford Dictionary of Biochemistry and Molecular Biology will serve as an invaluable reference text for student and professional biochemists and molecular biologists seeking information both from within and outside their own fields. It will also be of relevance and use to a broader audience of life scientists seeking an authoritative overview of fundamental principles.

Jacket illustration: © Spectral-Design/iStockphoto

OXFORD
UNIVERSITY PRESS

www.oup.com

ISBN 0-19-852917-1

9 780198 529170

Practical Navigation for the Modern Boat Owner

PAT MANLEY

WILEY NAUTICAL

John Wiley & Sons, Ltd

Practical Navigation for the Modern Boat Owner

Practical Navigation for the Modern Boat Owner

PAT MANLEY

WILEY NAUTICAL

John Wiley & Sons, Ltd

Copyright © 2008

John Wiley & Sons Ltd, The Atrium, Southern Gate, Chichester,
West Sussex PO19 8SQ, England
Telephone (+44) 1243 779777

Email (for orders and customer service enquiries): cs-books@wiley.co.uk
Visit our Home Page on www.wiley.com

All Rights Reserved. No part of this publication may be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, scanning or otherwise, except under the terms of the Copyright, Designs and Patents Act 1988 or under the terms of a licence issued by the Copyright Licensing Agency Ltd, 90 Tottenham Court Road, London W1T 4LP, UK, without the permission in writing of the Publisher. Requests to the Publisher should be addressed to the Permissions Department, John Wiley & Sons Ltd, The Atrium, Southern Gate, Chichester, West Sussex PO19 8SQ, England, or emailed to permreq@wiley.co.uk, or faxed to (+44) 1243 770620.

Designations used by companies to distinguish their products are often claimed as trademarks. All brand names and product names used in this book are trade names, service marks, trademarks or registered trademarks of their respective owners. The Publisher is not associated with any product or vendor mentioned in this book.

This publication is designed to provide accurate and authoritative information in regard to the subject matter covered. It is sold on the understanding that the Publisher is not engaged in rendering professional services. If professional advice or other expert assistance is required, the services of a competent professional should be sought.

Other Wiley Editorial Offices

John Wiley & Sons Inc., 111 River Street, Hoboken, NJ 07030, USA

Jossey-Bass, 989 Market Street, San Francisco, CA 94103-1741, USA

Wiley-VCH Verlag GmbH, Boschstr. 12, D-69469 Weinheim, Germany

John Wiley & Sons Australia Ltd, 42 McDougall Street, Milton, Queensland 4064, Australia

John Wiley & Sons (Asia) Pte Ltd, 2 Clementi Loop #02-01, Jin Xing Distripark, Singapore 129809

John Wily & Sons Canada Ltd, 6045 Freemont Blvd. Mississauga, Ontario, L5R 4J3 Canada

Wiley also publishes its books in a variety of electronic formats. Some content that appears in print may not be available in electronic books.

Library of Congress Cataloging-in-Publication Data

Manley, Pat.
Practical navigation for the modern boat owner / Pat Manley.
p. cm.
Includes index.
ISBN 978-0-470-51613-3 (cloth : alk. paper)
1. Navigation–Handbooks, manuals, etc. 2. Global Positioning System–Handbooks, manuals, etc. I. Title.
VK555.M267 2008
623.89–dc22

2008003730

British Library Cataloguing in Publication Data

A catalogue record for this book is available from the British Library

ISBN-13: 978-0-470-51613-3 (HB)

Typeset in 10/12 Futura by Thomson Digital, Noida, India
Printed and bound in Italy by Printer Trento, Trento

Contents

Cover Points xi

Foreword xiii

Introduction xv

1 The Global Positioning System 1

How Your GPS Receiver Tells You Which Satellites It Can See 2
How GPS Works 3
Accuracy of the Fix 4
GPS Blackout 5
Deliberate Interference 5
GPS Is Line of Sight 5
Selective Availability 6
Differential GPS 6
Wide Area Augmentation Service 6
Switch-On Delays 7
Measurement of Speed 8
Measurement of Course 8
Measurement of Heading 9
Errors in COG and SOG 9

2 Our Address on the Earth's Surface 11

The Equator 12
Latitude 12

Greenwich Meridian 12
Longitude 12
Our Address 13
International Date Line 13
Measurement of Latitude and Longitude 13
Distance and Direction 14
Direction 16
The Flat Earth 19
The Spherical Earth and 'Map Data' 20
Chart Errors 22
Chart Scale 24
Measuring Latitude and Longitude 25
Chart Symbols 26

3 The Magnetic Compass 29
The Earth's Magnetic Field 30
Steering Compasses 30
Compass Deviation 31
Compass Correction 31
DIY Compass 'Swing' 31
Fluxgate Compasses 33

4 Constructing a Route 35
Using Second-Hand Waypoints 36
Loading the Route into the GPS 38
Constructing a Route on an Electronic Chartplotter or PC 38

5 Tides 39
Tidal Heights 39
Tidal Flow 50
Finding the Value of the Tidal Flow 52

6 Boat Speed 57
Speed over the Ground 57
Speed Through the Water 58
Measuring Speed Through the Water 58
Log Errors 58

7 Depth Sounders **61**
How They Work 62
Depth Units 62
Calibration 62
Depth Alarms 63
False Echoes 63
Fishfinders 63

8 Finding Position **65**
GPS 65
Other Methods 66
Position Lines 67
Fixing Your Position Using Position Lines 69
Errors in Position Lines 70
How Far Can You See? 71
When All Else Fails 72
Chartplotters 73

9 Passage Planning **77**
Overview 78
Detailed Plan 79
Just Prior to Departure 80
Passage Planning – Procedure 81
Preplan 81
For the Planned Day of Departure 81
Passage Making 81
Passage Grid 86
Approach 'Spider's Web' 86
Compass Rose as a Waypoint 87
Unmarked Danger as a Waypoint 88
Clearing Bearing 88

10 Pilotage **89**
Who Does the Piloting? 90
Means of Pilotage 90
International System of Buoyage 90

International Buoyage – All Areas 92
Planning 97
The Basics of Preparing a Pilot Plan 97
Making a Pilotage Plan 98
Working as a Team 101

11 Automatic Identification System 103
What is Automatic Identification System? 104
How Does AIS Work? 104
Class A AIS 104
Class B AIS 104
AIS Displays 105
The AIS Display on a Chartplotter 106
AIS Class B Transceiver 107

12 Radar 109
How Radar Works 110
Navigation Using Radar 113
Pilotage Using Radar 114
Radar Overlay on a Chart Plotter 121
Setting up Your Radar 121
Radar Used for Collision Avoidance 122

13 Autopilots 125
Types of Autopilot 125
Using the Autopilot 126

14 Personal Computers 129
What Type of PC 130
What Make of Chart-Plotting Software? 130
What Type of Electronic Charts? 131
Electronic Charts for PC Based Chartplotters 132
Selecting the Software 133
Constructing a Route 134
Sailing Yacht Route Planning 135

Sending the Route to the GPS 137
AIS on a PC 138
Radar on a PC 139
Navtex on a PC 142
Tides on a PC 142
Connecting to the Boat's Systems 143

Appendix A Deduced Reckoning and Estimated Position 145
DR Navigation 146
Estimated Position 146
Leeway 148
Error in EP 148
EP with Multiple Headings 148

Appendix B Course to Steer 149
Where Do You Want to Go? 150
What Time Interval Do You Choose? 150
Draw in the Tide 151
Draw in the Boat Speed 151
Ground Speed 152
Comparison with EP 153

Appendix C Tidal heights and Tidal streams 155
Atmospheric Pressure Corrections 156
Tide Tables 156
UKHO Tidal Predictions 156
SHOM Tidal Predictions 159
Tidal Streams 161

Appendix D Tidal Planning and Plotting 165
A Long Passage Using a Single CTS 165
Where will the Tide Take You? 167

Credits 169

Cover points

- If you wonder why your in-car navigator shows that you are in a field – Read on
- If you wonder why your in-car navigator takes you on farm tracks – Read on
- If you think that the electronic charts on your chartplotter are accurate – Read on
- If you want to know the depth of water over the rocks – Read on
- If you think pressing 'GO TO' will take you safely to your destination – Read on

Foreword

The methods of navigation used by the modern boat owner have changed quite rapidly from the traditional methods still currently taught. This doesn't make the old methods wrong; it just means that the emphasis has changed.

With GPS used in many cars, the level of computer skills of the general public being high, and the so-called paperless office, the modern boat owner desires a different approach to navigation.

'Practical Navigation for the Modern Boat Owner' will lead you through all aspects of navigation of your boat in a logical order. The pencil and paper chart part of the subject is not introduced until it's demonstrated that some knowledge of traditional navigation is necessary. This practical approach to the subject will ensure that although the modern electronic methods of navigation remain at the forefront, the reader will never be lacking in sufficient knowledge to navigate his/her boat safely in any circumstance.

Proper passage planning is not only desirable, but it is also a legal requirement. This topic is thoroughly covered in an entirely practical manner.

The boat owner cannot rely entirely on electronic navigation for pilotage. Pilotage will introduce the well-established and practical aspects of entering and leaving a harbour or anchorage.

Radar is another area where legally the boat owner is required to know how to use this valuable tool. Again, this topic is approached using a practical and easily understood approach.

Introduction

When I gained my Flight Navigator's License in 1973, other than when I was actually on the ground, I never knew where I was, only where I had been! By the time you had worked out and plotted a fix, you were at least 60 miles further on. Even when I flew Boeing 747s, without a Flight Navigator, the inertial navigation system, which used three onboard gyroscopic platforms to measure acceleration in all three planes to determine where you were, could be 10 miles in error by the time you had flown 12 hours. Incidentally, the Apollo spacecraft to the moon used only one of these inertial systems for navigation!

Modern airliners use a combination of inertial navigation systems continually updated by automatically tuning into ground-based aids to remove any inherent errors. This has the huge benefit of using at least three different types of data on three completely separate systems to continuously monitor each other for errors, which if found are reported to the pilots.

The first time that I ever knew where I was all the time was when I started using GPS on board my own yacht, assuming of course that what it was telling me was correct.

Fortunately for me, I had around 10 million miles of 'real' navigation behind me and I knew when I could trust my GPS and when to treat it with a certain amount of suspicion.

My aim in this book is to show you how to use all the navigation tools at your disposal to the best advantage and to be able to weigh up which ones to place more reliance on according to the circumstances.

To me, navigation has always been more than a means to an end, and I hope you will get as much enjoyment out of it as I do.



The Global Positioning System

How Your GPS Receiver Tells You Which Satellites It Can See
How GPS Works
Accuracy of the Fix
GPS Blackout
Deliberate Interference
GPS Is Line of Sight
Selective Availability
Differential GPS
Wide Area Augmentation Service
Switch-On Delays
Measurement of Speed
Measurement of Course
Measurement of Heading
Errors in COG and SOG



Artwork courtesy of US Dept of Defense

Simplified GPS satellite constellation

The original global positioning system (GPS) consists of 24 satellites orbiting the Earth at a distance of around 11 000 miles. Each orbits once every 12 hours in six orbital plains, so there will be between five and eight satellites in view at any time, from any point on the Earth's surface. The drawing here shows only three orbital plains for clarity.

There are a number of spare satellites in orbit in case of failure and each satellite has a life expectancy of about 7 years. New satellites are launched by the US military as required.

Fears about the American monopoly of accurate position fixing amongst non-USA countries have lead to the establishment of GLONASS (a Russian system) and the pending establishment of GALLILEO (a European system). They work in a similar manner and new versions of GPS receiver may be able to operate with any system.

How Your GPS Receiver Tells You Which Satellites It Can See

On startup, a GPS receiver starts looking for satellites and will display a page showing you its sky view all around the horizon. The outer ring is the horizon, the inner ring is at an elevation of 45 degrees and the centre represents the position in the sky vertically overhead (the zenith). The predicted positions of satellites are shown as empty circles which become coloured when a satisfactory satellite signal is received. The serial number of the satellite is shown in the circle. Alongside the diagrams are vertical bars representing the signal strength (in fact the signal-to-noise ratio or quality of the signal) and again each bar is numbered. In this way, you can see the number of satellites and the quality of the signals being received in order to form an idea of how good a fix you are likely to get. There's often a number giving an indication of the fix accuracy, more of which later.





GPS satellite positions

How GPS Works

Timing


Semi-random code of transmitter and receiver signals
From satellite
In receiver
Time delay
Slide signal sideways to obtain match to measure time difference

Measuring the time taken for the GPS signal to reach the GPS receiver

In order to find its position on the Earth's surface, a GPS receiver needs to find its distances from at least four satellites. Theoretically, it needs only three, but the clock on the receiver is not accurate enough to allow this.

Distance is measured by measuring the time taken for the GPS signal to travel from the satellite to the receiver. As the time taken is only 0.06 second for a satellite immediately overhead, an error of one thousandth of a second would give an error of 200 miles! Each satellite has an onboard 'Atomic Clock', which is super accurate, but for each receiver to be similarly equipped, GPS would not be a practical proposition.

Satellites transmit a semi-random signal, which the receiver matches with its own semi-random signal. The distance the receiver has to move its own signal to get a match is a measure of the time difference and a range can then be calculated. It's a bit like matching continually repeated barcodes in reality. This is accurate enough to get a first guess at the distance.

Fixing Position with GPS

If the distance to the satellite is calculated by the receiver, it can be plotted as a *position line*, where any place on the Earth's surface is the same distance from the satellite. The receiver must lie somewhere on that position line.

If the distances from two more satellites are calculated and plotted, the receiver must lie on all three lines. Normally, this can occur at only one point on the Earth's surface and so that must indicate the position of the receiver.





Cocked hat

Because of small inaccuracies in the receiver's clock, there will be an error in its position. The position lines will not intersect at the same point and will form what is known as a *cocked hat.*

Pseudo Range

A clever trick within the receiver converts the ranges into *pseudo* ranges, which allows them to be shuffled around within certain limits.

The range from a fourth or even more satellites is calculated and added to the *fix*.

The extra position line(s) allows the timing error to be determined and this results in a good fix, where all the position lines intersect at only one point.



Pseudo range



Fourth satellite



Good fix

Accuracy of the Fix



Range rings at 25metres spacing

Normal GPS errors

With range being calculated using the time taken for the signal to travel between the satellite and the receiver, any variation in the speed of the signal and the actual path followed will lead to errors.

Errors due to these effects will normally amount to no more than ±15 metres for 95% of the time, being made up from the following:

- ionospheric effects, ±10 metres;
- ephemeris errors, ±2.5 metres;
- satellite clock errors, ±2 metres;
- multipath distortion, ±1 metre;
- tropospheric effects, ±0.5 metre;
- numerical errors, ±1 metre or less.

With my boat moored in the marina, normal GPS errors were plotted as shown over an 8 hour period. Although most were contained within the 25 metre diameter circle, one was almost 100 metres in error. This is perfectly normal GPS performance.

GPS Blackout

Solar flares can cause a complete GPS signal blackout on the sunlit side of the Earth's surface. In 2006 flares on the 5th and 6th of December caused profound and severe effects to GPS receivers causing a large number of them to stop tracking satellites. Professor Dale Gary of the New Jersey Institute of Technology said 'This solar radio burst occurred during a solar minimum, yet produced as much as 10 times more radio noise than the previous record … at its peak, the burst produced 20 000 times more radio emission than the entire rest of the Sun. This was enough to swamp GPS receivers over the entire sunlit side of the Earth'.

The Solar flare cycle covers a period of 11 years.



Solar flares can cause significant GPS errors even disablement of satellites

Deliberate Interference

The strength of the radio signals carrying the GPS data is very low and can easily be interfered with. Enemies can deliberately try to disrupt signals in a relatively small local area and military agencies regularly deliberately interfere with the signals to judge the results. These tests are promulgated in advance.



Range rings at 25 metres spacing

GPS errors with 'selective availability'

GPS Is Line of Sight

A GPS receiver must be able to 'see' a satellite in order to receive its signal. If buildings, cliffs or trees obstruct that line of site, the signal from that satellite will not be received and the accuracy of the fix may be degraded. It's possible that the signal may be received as it bounces off another surface so it will take longer time to arrive and will give an inaccurate range. Again this can degrade the fix accuracy.

The signal can penetrate some solid surfaces, such as glass, GRP and canvas, and it is sometimes possible for a receiver antenna mounted inside the boat to work satisfactorily.

Selective Availability

Originally, civilian users had their signals deliberately degraded by the US military inducing a randomly varying error, known as *selective availability*, ensuring that accuracy was no better than 100 metres for 95% of the time. This selective availability has been switched off, but the US military may reintroduce it, without warning, at any time. This must always be considered a possibility. On the accompanying chart, the error that disappears northward off the chart was over 800 metres.

Errors that occur from a corrupt satellite signal will be incorporated into the fix by a GPS receiver and can lead to very large errors, measured in miles, and will continue until the satellite is switched off by the monitoring team, which could take up to one and a half hours.

Differential GPS

A GPS receiver fixed in one place will know exactly where it is. Any position derived from the received GPS signals can be compared with its known position and any error deduced. If this error was transmitted to the nearby GPS receivers, they could take account of this error in deducing their own position to give a much more accurate result, with a 95% probability error of 3 metres. This is known as *differential GPS* (DGPS).

To take advantage of this, the GPS receiver needs both a separate DGPS receiver and to be within range of a DGPS station, usually about 200 miles. This is commonly used for survey GPS and was beginning to be common for leisure users until selective availability was switched off, when its need for normal leisure use disappeared because of the inherent 15-metre accuracy.



DGPS

Wide Area Augmentation Service

Wide Area Augmentation Service (WAAS) uses a network of ground stations to monitor the GPS position accuracy. The error corrections are sent to two master stations, which in turn send error correction information to the constellation of satellites. The continuously varying error correction information is broadcast by the satellites and is then available to all WAAS compatible GPS receivers. The 95% error is then reduced to 7.5 metres. Manufacturers usually optimistically claim a 3-metre accuracy. Integrity monitoring is part of this system, so anomalous



WAAS

signals from under-performing satellites are automatically discarded.

WAAS is available only in the United States of America, but European Geostationary Navigation Overlay Service (EGNOS) and the Japanese Multi-Functional Satellite Augmentation System (MSAS) provide the same service in areas covered by these. A WAAS compatible receiver will operate with EGNOS and MSAS.

Range rings at 25 metres spacing
WAAS GPS errors

The Modern GPS Receiver

Modern GPS receivers normally have 12 or more channels which can receive data from 12 different satellites simultaneously. Satellites are moving fairly rapidly along their paths and the ability of the receiver to 'lock' onto a large number of satellites means that they are always using the best data available. It also means that their 'startup' times are very quick.

The oldest receivers have very few channels, so they have to divide their time between using data from only one or a few satellites and searching for new ones. They are inherently slow.

GPS 152
3D Navigation
Units
Com
Alrm
Celes
GPS
Accuracy
2.9m
DOP
1.3
WAAS
03 07 08 15 18 21
GARMIN
MENU
PAGE
ENTER MARK
OUT
NAV MOB
QUIT
IN

A modern GPS receiver

Switch-On Delays

Cold Start

When a new GPS receiver is first switched on, it has no idea of the time, date, where it is or where the satellites are. As the information about the whereabouts of the satellites is transmitted only every 12.5 minutes, it will be some time before the GPS can compute its first fix. This is known as a *cold start.*

Hot Start

When the GPS is switched in the same geographical position as when it was switched off, it knows where to expect the satellites to be, the date and the time, so modern 12 channel receivers can compute their first fix very quickly.

Warm Start

If the GPS receiver has been moved since it was last switched off, it will take longer time than a hot start but much less than a cold start.

Measurement of Speed

There is nothing inherent in the GPS signals that measure speed. However, the receiver does have a lot of built-in information that it can use to present useful information. Once the GPS receiver has worked out its position, it can use its knowledge of the shape and size of the Earth to determine the distance between any two points, so that once it is in motion it can work out the distance between two fixes, and taking the time taken to travel this distance it can deduce its speed. This speed is the *speed over the ground* (SOG), not to be confused with the speed through the water.



Distance travelled in 1 minute = 0.2 nautical miles

Speed over ground (SOG) = 12 knots

SOG Is Not Boat Speed

Boat speed is the speed of the boat through the water and is displayed on the water speed display. Wind, waves and tide will cause the speed over the ground to differ from the water speed.



Effect of tide on speed

Measurement of Course

The GPS signal contains no information on the direction in which the boat is moving. Because the GPS receiver knows the shape of the Earth, it can determine the direction that it has travelled from one fix to another. This *course over the ground* (COG) is exactly what it says and may not be the same as the course steered by the boat.



Because the GPS receiver knows the shape of the Earth, it can calculate the bearing of the second fix from the first. It is thus capable of calculating the course over the ground (COG)

COG Is Not Heading

The heading is the direction that the boat is pointing and is displayed on the compass. The wind, waves and tide can push the boat sideways over the ground, and it's this movement over the 'ground' that is displayed as COG. Only in calm conditions with no tide running will the heading and COG be the same.



The effect of tide on heading

Measurement of Heading

GPS can't measure the boat's heading and can measure only the COG. Once the GPS receiver is moving, because it can determine COG, it knows the direction of true north. We will find, later in this book, that some instruments, such as radar and chartplotters, can make use of heading information to allow the display to be aligned with north to give a *north up* display. Although GPS can provide this information, there are two disadvantages: The information is available only once the boat is in motion and the alignment is based on COG rather than which way the boat is pointing.



Once the GPS receiver is moving
it can determine the direction of North

Errors in COG and SOG

Any random errors in the fixes used to calculate COG and SOG will produce errors in speed and course displayed on the GPS.



Errors in SOG and COG

The rate at which the GPS position is updated is very rapid, but to minimise the effect of random errors, COG and SOG are averaged over about 5 seconds, by default, although the user may alter this time. The longer the time interval, the steadier the reading, but the slower the response to a real alteration of heading or speed.

If the error between two fixes were 15 metres, one to port and the next to starboard, the error in COG over a 5-second period at 6-knots speed could be greater than 45 degrees. Similarly, with similar errors, but in the direction of movement, the SOG displayed could be in error by 6 knots! With selective availability switched off, the normal situation, random errors are likely to be very small, and COG and SOG are generally stable and accurate. With the default setting for the ‘averaging time’, watch the COG and SOG at a constant speed and heading to get an idea of how they respond in normal conditions.

If selective availability is switched on by the US military, the accuracy of COG and SOG will deteriorate significantly.



Our Address on the Earth's Surface

The Equator

Latitude

Greenwich Meridian

Longitude

Our Address

International Date Line

Measurement of Latitude and Longitude

Distance and Direction

Direction

The Flat Earth

The Spherical Earth and 'Map Data'

Chart Errors

Chart Scale

Measuring Latitude and Longitude

Chart Symbols

If you need to find someone, you need their address. To do this on planet Earth, an invisible, theoretical grid has been overlaid on the Earth's surface by geographers. This grid of *Latitude and Longitude* allows us to define any point on the Earth's surface with as much accuracy as we wish.


North Pole
Parallels of latitude
Greenwich Meridian
180°E/W
Equator
Meridians of longitude
South Pole

Latitude and Longitude

The Equator

The Earth spins on an axis through the North and the South Poles. Any circle running around the Earth's maximum circumference is known as a *great circle*. The Equator is a great circle at right angles to the spin axis and equidistant between the poles.



The Equator

Latitude

Latitude is defined as the angle in degrees between the Equator, the centre of the Earth and a point on the Earth's surface. If the point is between the Equator and the North Pole, it's called north latitude and if between the Equator and the South Pole, it's called south latitude. A circle can be drawn through all points of the same latitude, this circle being a *small circle* as its circumference is less than the Earth's, and it is parallel to the Equator. There are an infinite number of points on the Earth's surface with the same latitude, so latitude by itself cannot define our address.


North latitude
Axis or rotation
North Pole
Equator
30 degrees North
30°
60°
60 degrees South
South latitude
South Pole

Latitude

Greenwich Meridian

A half great circle joining the North and the South Poles and running through Greenwich Observatory in London, England is called the Greenwich Meridian. This forms the datum from which the other half of our address is obtained.


Greenwich Meridian
South Pole

Greenwich Meridian

Longitude

The angle in degrees between the Greenwich Meridian where it crosses the Equator, the centre of the Earth and another point on the Equator is called the *longitude*. It is


30 degrees East
Greenwich Meridian
30°
120°
Equator
120 degrees West
This is both 180 degrees East and 180 degrees West

Longitude

called west longitude if it's west of the Greenwich Meridian and east longitude if it's east of the Greenwich Meridian. All points on the Earth's surface having the same longitude lie on a great circle running through both poles and is known as a meridian of longitude.



Address is 22 degrees North, 66 degrees West

Our address on the Earth's surface

Our Address

The combination of the latitude and the longitude of the point provides a unique address on the Earth's surface. We can now tell someone else where we are and also find the address of a place we may wish to visit.

International Date Line

With the Earth spinning around its axis once per day, the date clicks up a day at a time at midnight. If you were to travel around the world faster than the Earth's rotation, you would have time travel, so a mechanism needs to be found to stop that happening and the answer is the International Date Line. When you cross the 180-degree meridian, the date changes, either jumping forward a day– if you're travelling west – or dropping back a day – if you're travelling east. For much of its length, the 180-degree meridian is the International Date Line as well. However, in order that the jump doesn't occur over land, the date line has some wiggles, both east and west, so that the whole of any country or territory is on the same date.


International data line
North Pole
Greenwich Meridian
International date line

International date line

Measurement of Latitude and Longitude

One degree is divided into 60 minutes. Normally, 1 minute is divided into 60 seconds; however, this is rather cumbersome when measuring on a chart, so for navigation purposes, 1 minute is divided using the decimal notation; so, we write down (and say) degrees, minutes and tenths (or hundredths or thousandths) of a minute.

So, for instance, 35 degrees, 43 minutes and 456-thousandths of a minute is written as 35° 43.456′.

Thus, we write a position as

Latitude 35 degrees 43.456 minutes North.
Longitude 026 degrees 12.765 minutes East.

We use the format,

Latitude dd° mm.mmm′.
Longitude ddd° mm.mmm′.

The maximum number of degrees latitude is 90 and the maximum number of degrees longitude is 180.

Distance and Direction

In order to navigate anywhere, we need to determine both the distance and the direction to our destination.

Distance

Most of us are used to miles or kilometres, but these are not the measurements used at sea or in the air. The problem is that these measurements are not related to the geometry of the Earth and so the user has to have a scale of distance to use whenever the distance must be measured.

The Nautical Mile

The nautical mile is directly related to the circumference of the Earth. One degree (60 minutes) of latitude is equal to 60 nautical miles. Thus,


NORTH ATLANTIC OCEAN
INDIAN OCEAN
SOUTH ATLANTIC OCEAN
C-MAP

A chart drawn using a 'Mercator' projection


60 degrees latitude equals 60 x 60 = 3600 nautical miles
60°
45°
30°
15°
0°
Mexico
C-MAP



Use latitude scale at same latitude as distance to be measured



'Walking the dividers'

- One nautical mile equals one minute of latitude.

Distance can be measured directly from the latitude graticule of the chart. The distance from the Equator to 60 degrees North is 60 × 60 = 3600 nautical miles.

If you look carefully at a chart, you will see that the latitude graticule doesn't have constant spacing. This is especially true on a Mercator projection, where the distance between each 10 degrees of latitude gets progressively greater. Where a chart covers a large portion of the Earth's surface, this is especially critical when measuring distance.

So, when measuring distance, we should use the region of the latitude graticule at almost the same latitude as the distance to be measured. If the distance between two points is longer than the 'open' distance of the dividers, measure a convenient length on the latitude graticule and then 'walk' the dividers along the line, counting each step. Measure the remaining small distance and add this to the number of steps and you have the total distance.

Under no circumstances should you use the longitude graticule to measure distance. Only at the Equator it does give approximately the distance, and as you move further away the error increases. At 30 degrees North, 1 minute of longitude equals 0.866 nautical mile and at 60 degrees North (or South) it's only half a mile. At the poles, it is of course 0 nautical mile.

When you change chart scales, check the latitude graticule carefully to ensure that you know what each coloured part



Measuring distance



Latitude graticule markings

represents: 1 mile, 5 miles, 10 miles, etc. It is really easy to make a mistake, especially when one chart is lying on top of another and you can see both latitude graticules.



Wrong scale!

Direction

All meridians pass through the North Pole and so all meridians define the direction of *true* north. It is true because it refers to the geographical pole. For this reason, we measure direction relative to a meridian. On a Mercator chart, the meridians are parallel to each other, so direction can be measured relative to any meridian on the chart.

A conical projection implies that none of the meridians are parallel, and so direction must be measured relative to the meridian *nearest* to where you wish to measure the direction.

Never measure direction relative to the chart's border because this may not be aligned with true north.



Line crosses each meridian at a different angle



Measuring direction with a course plotter



Meridians not aligned with chart border

Magnetic North Pole

The true North Pole is on the Earth's spin axis. However, this is not where a magnetic compass points. The compass needle is attracted towards the *magnetic* North Pole, which at the present time is situated in the north of Canada, about 800 miles south of the true North Pole. It moves slowly, but noticeably and the annual value must be used for navigation.



Magnetic North Pole

Variation

The angular difference between the direction of true north and magnetic north is called *variation* and its value is indicated on a chart, together with its annual change. Variation may be east or west of true north and is annotated accordingly.

Deviation

Because of the influence of the boat and its equipment, the compass rarely points at the magnetic pole, this error being called *deviation*. Deviation is specific to your boat, changes according to the heading (and heel) of your boat, and must be reassessed annually as it will change with time and any additional equipment fitted. Compass correction is dealt with in a later chapter.



Variation

Measuring Direction on the Chart

There are a number of different instruments for measuring direction, and users have their favourites. Probably, the two easiest to use on a small chart table are the 'Portland' type course plotter and the parallel rule.

Course Plotter

This plotter needs nothing except a meridian to line up on, although in practice, parallels of longitude may be used as well on the type of chart normally used.

- Place the edge of the plotter on the line joining two places with the main arrow pointing in the direction of travel.
- Rotate the centre knob to align the grid on the central wheel with the latitude/longitude graticule.
- Read off the direction against the '0' on the centreline of the plotter.
- Variation can be applied as you work using the east or west error offset. This allows the direction to be read directly from the plotter.



If variation were 6 degrees East at this point, read off magnetic direction against 6 degrees East error, in this case 044° magnetic

Read direction against '0', in this case 050° true

Align grid with latitude or longitude and with green arrows pointing north

Measuring direction with a course plotter

Parallel Rule

To use a parallel rule easily, there needs to be a *compass rose* on the chart. A compass rose is a 'protractor', aligned with true north, printed on the chart. An 'inner' concentric protractor aligned with magnetic north may also be shown. The amount of variation and the year of its validity at that point are shown together with the annual change and its direction of change.


Inner protractor aligned with magnetic north
Outer protractor aligned with true north
Variation, with its date of validity and the the annual rate of change

Compass rose

There are likely to be several compass roses on each chart. The variation at each rose may be different.

- Place the edge of the parallel rule along the direction to be measured.
- Open up the parallel rule until the other edge passes through the centre of the nearest compass rose.
- If it wouldn't reach far enough, 'walk' the rule across the chart until it reaches the centre of the compass rose, being careful that its direction isn't altered.


C-MAP
Align parallel rule with direction and open it up so that it passes through centre of compass rose, 'walking' it if necessary
Read off direction on compass rose, in this case 069 degrees true or 074 degrees magnetic

Measuring direction with a parallel rule

Magnetic or True Direction?

All paper charts give direction in degrees true. You can convert these directions to magnetic if you wish. All magnetic compasses show direction in degrees magnetic (with an error due to deviation if this is applicable).

When steering the boat using a magnetic compass to determine the direction, we need to know the 'course to steer' in degrees magnetic. It is, therefore, traditional to convert all directions to magnetic.

Global positioning system (GPS) and electronic chartplotters have the Earth's variation chart built in, so that if they know where they are, they will know the local variation. Therefore, if you wish, you can tell the GPS or chartplotter to show all directions as degrees magnetic. I prefer to do this as I can compare all direction information directly with my magnetic compass without having to tax my poor old brain.

If you have an electronic compass, and use your magnetic compass only as a back up, you can use true direction if you prefer. If you do so, ensure that all the 'electronics' use true direction and that your crew understands what you are doing. At the present time, this is a non-standard procedure, but in the future, this may become the norm.

The Flat Earth

Have you ever tried peeling an orange and laying the peel out on a flat surface? Difficult, isn't it?

As soon as you try and make a chart, paper or electronic, you run up against the problem of transforming a spherical surface into a flat sheet. It's fine if the area covered is no bigger than a football ground, but if you want a sizeable portion of land or sea, you just can't do it easily.

Strictly speaking, mariners and aviators use charts, while maps are used on land, though for serious navigation on land, such as in the desert, and then we are back to charts again.

Chart Projections

Ever since man realised that the Earth wasn't flat, many different ways of depicting the Earth's surface have been tried. All have disadvantages. From looking at some maps, many people think that Greenland is a massive island, bigger than South America, Australia or the United States of America. In reality, Greenland is smaller than Algeria and less than a quarter the size of the United States of America and one-third the size of Australia. So why is this confusion?



The shape's right, the size is wrong

There is no projection that shows *both* correct size *and* correct shape of the continents. If we have the correct shape, we have the wrong size and vice versa. So it depends what use is to be made of the chart or map, which of the many projections is chosen. It doesn't matter if we are considering a paper chart or an electronic one; they all suffer from the same problems. There are many projections that are used by cartographers, but as this is a practical book, we'll just look at a couple of basic principles. Should you wish to do any long distance sailing, you'll need to study this topic further.



Mercator projection

Mercator Projection

Let us imagine a translucent Earth with a powerful light source at its centre. If we were to wrap a cylinder of paper around the globe, the outline of the land would be projected onto the inner surface of the cylinder of paper. If we now trace the outline onto the paper and unfurl it, we would have a chart drawn using the Mercator projection.



We can immediately see that instead of the parallels of latitude being equally spaced, they get further apart as we go towards the poles. This is the projection that makes Greenland (2 172 000 square kilometres) look hugely bigger than the slightly larger Algeria (2 382 000 square kilometres). The meridians, which should meet at the poles, are parallel. Mercator charts are useful for some types of navigation, but we need to be aware of the changing scale of the chart as we move north or south of the Equator. The direction of north is always 'vertical', towards the top of the chart. It is impossible to show the polar regions.

Conical Projections

Again we need to imagine a translucent Earth with a light at the centre. This time, we wrap the paper in the shape of a cone which touches the Earth somewhere north (or south) of the Equator. The area that we're mapping influences where we make the tangent to the surface. We can see that the parallels of latitude are parallel, but curved and the meridians are straight, but converge towards the closest pole.

Within a reasonable distance of the tangential parallel, scale is much more consistent. Look at how Greenland and Algeria are much closer to their proper areas. The direction of north (or south) is not constant but towards some invisible 'vanishing' point. Again we cannot represent the polar regions.



Conical projection



Polar Projections

The only way to show the polar regions on a navigation chart is by having a flat sheet of paper sitting directly on the pole. All parallels of latitude are concentric circles about the pole and meridians are straight lines radiating from the pole. Scale is correct only at the pole. When situated at the pole, all directions are south from the North Pole or north from the South Pole.



Polar projection

The Spherical Earth and 'Map Data'

In fact the Earth isn't a sphere, it's an oblate spheroid, flattened at the poles and with bumps on it. These bumps are not the mountains and oceans, but irregularities which depart from the regular shape of the Earth. They occur over areas large enough for the mapmakers to take them into account when producing maps of their country. Because the bumps effecting each country is slightly different, each national map making organisation has used complicated formulae which best represent their part of the world, so that other map makers know what is going on, each formula is designated a code, known as a *map datum*. This is printed on the chart. For example, in the United Kingdom, the map datum is referred to as OSGB36, which stands for Ordnance Survey of Great Britain, 1936, the year in which it was devised. In the United States of America, it's NAD27, but this is then split into versions for different areas and in Australia it's Aus Geo 66.

Having different map data mattered not one jot. Although the same latitude and longitude may have given positions several hundred metres from their proper position, the 'accuracy' of position fixing was such that these errors were undetectable. Not so now, where even amateur yachtsmen can fix their position to within 15 metres most of the time.

This difficulty was realised when GPS was being designed and a new international datum was produced which, although very complex, allowed for the true shape of the Earth everywhere. This datum is known as WGS84 – World Geodetic System 1984.

Paper Charts

Only very recently have paper charts been drawn using WGS84 as the datum. The majority of paper charts use their local datum, so if the GPS receiver is set to give position in WGS84 format, which it will by default, the position when plotted on the paper chart will be in error by as much as a couple of hundred metres (600 feet). This is of significance only if you are trying to use your GPS for 'close quarters' navigation, which you should never do in isolation in any case. Paper charts printed subsequently to the introduction of GPS should be annotated with the datum used and any correction to be applied. This correction will be correct only for this chart; an adjacent chart may have a different correction. Always check both the datum and the correction for *any* chart you use.



Positions are referred to Ordnance Survey of Great Britain (1936) datum.

Satellite-derived positions

Positions obtained from satellite navigation systems are normally referred to WGS 84 Datum; such positions should be moved 0.03 minute *southward* and 0.10 minute *eastward* to agree with this chart.

Map datum

Modern paper charts always state the correction to be applied when plotting using a WGS84 position. An alternative method is to reset the GPS receiver to present the latitude and longitude to the datum used by the chart. If you do this, you need to remember to reset it if you change the chart. If you're plotting on paper, it should make little difference using the incorrect datum unless you are navigating solely by GPS in a close quarter's situation. Remember errors due to using the incorrect datum could exceed 200 metres (600 feet), so that if your approach channel is only 100 metres (300 feet) wide, you could end up on the rocks!



Datum error distances

Electronic Charts

Electronic charts are copies of paper charts. There are two types of electronic charts:

- *Raster charts* which are faithful reproductions of paper charts that have been scanned to produce the electronic copies. These will have the same datum as the paper chart scanned.
- *Vector charts* which are based on paper charts but enhanced to give 'added value' and if necessary have their datum changed so that all vector charts are WGS84 'compatible'.
- *Electronic chart plotters* use vector charts, so no correction is required.
- *Personal computers* may use either raster or vector charts, so the user needs to set or allow for the relevant map datum.

Chart Errors

There's a general feeling that electronic charts, because they are of the computer age, must be correct. *This is a dangerous assumption because it is simply not true.*

Before we explore the reasons for these errors, just study the three accompanying illustrations. All are of the north coast of the island of Ibiza, in the Mediterranean. All are different versions of modern electronic charting. The up-to-date Navionics chart shows an island at the head of the bay. The very old C-Map chart shows no island and the latest C-Map chart shows the reality. Compare all these with the Google Earth photograph.




Nm
North-Up
(Relative Motion)
(Overlay)
System
PUNTA GALERA
ANCHORAGE
Ves Pos
39°06'.621N
001°30'.867E
COG
039
SOG
0.2
Waypoint 250
Cur Pos
39°07'.349N
001°30'.107E
322
0.936
FIND SHIP
GOTO...
RADAR OPTIONS...
NAVIGATION OPTIONS...
PRESENTATION...



So the first 'rule of using electronic charting' is 'caveat emptor'.



Sourced: Google Maps™ mapping service

When was the Survey Carried Out?


SOURCE DATA
Admiralty Surveys
a 1990 1:25 000
b 1960-64 1:5000-1:20 000
c 1859-66 1:12 255-1:18 360 (leadline)
d 1859-69 1:73 000 (leadline)
e 1830-81 1:117 480-1:520 000 (leadline)
f 1936-68 Lines of soundings
French Government Charts
g 1928-90 1:10 000-1:160 000
Compiled mainly from 19th century leadline surveys
Aerial photography
h 1980
Port Moguer
Spire Plouha
3°00'
05'
55'

UK Hydrographic Office source diagram

UK Hydrographic Office charts always have a source diagram on the chart. This shows both how and when the survey was carried out. Unfortunately not all charts have a source diagram and no vector charts I have seen have them either. Raster charts will if the original paper chart has one.

Vector charts will generally show the date of issue of the paper chart on which it was based, but this chart may well use cartography several hundred years old. Some charts are still based on Captain Cook's surveys and some Pacific Islands are reported to be up to 8 miles out of place.

Note how this area around the Channel Islands in the English Channel was surveyed mostly in the nineteenth century!

Surveying is very expensive and will not be carried out just to satisfy the 'leisure market'. Where commercial needs dictate, up-to-date surveys will be carried out, but this may be only in the channels and approaches used by commercial shipping, leaving the shallower areas unsurveyed by modern means.

In the United States of America, 40% of the shoreline has not been mapped since 1960. Around half of the soundings were carried out by lead line survey prior to 1940 (US Federal Advisory Committee Report 2007, which stated 'depending on the boater's location … can render these charts slightly to grossly inaccurate'). Any electronic chart of the US will be based on these charts.

Who Drew the Chart?

You cannot assume that the chart's publisher carried out the original cartography. The source diagram above shows that although it's from a British Admiralty chart, some of the cartography is French. One can probably make an assumption that not all cartography will be as good as that of the major seafaring nations.

Who Copied the Chart?

Vector charts rely on people to not to make errors when compiling the chart, but naturally errors will occur.

Chart Corrections

Chart corrections are published regularly to correct known errors and to introduce new data. The user is responsible for either buying updated charts or incorporating the updates when published.

Common Sense


HOTEL ATLANTICO
PILOT
FORTE DE SANTA CATARINA
MARINA
RECOMMENDED ANCHORAGE
CHANDLER
YACHT CLUB
ESTALEIROS DA FOZNAVE
PRAIA DO CABEDELO
ADVANCE WAYPOINT
STOP FOLLOW
RESTART XTE

This all sounds very alarmist, but common sense and the use of as many navigation tools as possible must be used at all times. It's an old axiom that groundings occur not because the navigator is uncertain of his position, but because he is sure that he knows where he is but is wrong! Navigators uncertain of their position navigate very cautiously.

The accompanying illustration from the chartplotter of a cautious navigator (an ex airline pilot) shows the planned inbound route to Figeuira da Foz, in Spain. The red 'Xs' are his planned *waypoints*. The red *track line* shows where the chartplotter thought they were, but of course, our cautions navigator followed the buoys, leading lines and the 'lie of the land' to complete a successful arrival. But if it were night or foggy, another 'gung ho' navigator would have ended on the rocks.

The longitude was correct, but the latitude had an error of about 0.15 minute – about 300 metres (900 feet). Was this a datum error, a cartographic error, a vectorisation error or a GPS error? Who knows but it could have ended up as a shipwreck whatever the cause.

Chart Scale

Charts vary according to the area that they cover and hence the detail they contain.

The scale of a chart is given as a ratio; one unit of length on the chart represents very many units of length on the Earth's surface. So a chart scale of 1:1 000 000 means that 1 inch or 1 centimetre on the chart represents 1 000 000 inches or centimetres on the Earth's surface.

The scale chosen for use in any particular circumstance depends on the detail required. You could not enter a harbour using a 1:1 000 000 scale chart; you would probably use a chart with a scale of 1:10000 or 1:5000.

- A *small-scale* chart covers a *large area* and has a high-scale number (say 1:1 000 000) (one divided by one million is a small number).
- A *large-scale* chart covers a *small area* and has a low-scale number (say 1:5 000) (one divided by five thousand is a larger number and therefore larger scale).


C-MAP
Small scale
C-MAP
Large scale

Chart scale

Ideally, you would have a small-scale chart of your cruising area and large-scale charts containing more detail for the harbours and anchorages. In fact, you may need charts of an intermediate scale as well. I, personally, don't buy charts by scale. I look at individual charts and their detail and buy what I want to suit my needs.

Measuring Latitude and Longitude

There will be a grid of latitude and longitude superimposed on the chart. This grid will be in degrees and minutes, as appropriate to the scale of the chart. To obtain the latitude and longitude of any point, we need to compare the position of this point with the grid. Several different tools may be used to do this, and navigators have their own preference.

Using dividers is the only correct method where the meridians are not parallel, such as on a conical projection. However, on such charts the errors using a parallel rule or course plotter will be very small unless the chart's scale is small. If the meridians look parallel, then the error will be too small to be significant for normal navigation.

We'll look at how we would measure the latitude and longitude of a special mark (buoy) near Sydney, Australia, whose position is 34° 06.548′S, 151° 24.962′E.

Using a Parallel Rule

Measuring Latitude

The parallel rule is placed on the nearest part of the *longitude* grid and opened out to touch the point of interest. The position of the rule is adjusted so that one edge cuts a *latitude* graticule and the latitude read off.



Measuring latitude with a parallel rule



Measuring longitude with a parallel rule

Measuring Longitude

The parallel rule is placed on the nearest part of the *latitude* grid and opened out to touch the point of interest. The position of the rule is adjusted so that one edge cuts a *longitude* graticule and the longitude read off.

Using a Course Plotter

Measuring Latitude

The edge of the course plotter is placed on the point of interest and aligned so that the opposite edge or the plotter's grid is parallel with the *longitude* grid. The latitude is measured where the plotter's first edge cuts the *latitude* graticule.



Any part of the edge or the grid of the plotter can be aligned with the lines of latitude or longitude - don't use the grid on the 'wheel'

Measuring latitude with a course plotter

Measuring Longitude

The edge of the course plotter is placed on the point of interest and aligned so that the opposite edge or the plotter's grid is parallel with the *latitude* grid. The longitude is measured where the plotter's first edge cuts the *longitude* graticule.



Any part of the edge or the grid of the plotter can be aligned with the lines of latitude or longitude - don't use the grid on the 'wheel'

Measuring longitude with a course plotter

Using Dividers

Measuring Latitude

Place one point of the dividers on the point of interest and open them out so that the other point touches the *latitude* grid at its closest point. Move the dividers so that one point touches the same latitude grid where it has a graticule and read of the point's latitude.



Measuring latitude with dividers

Measuring Longitude

Place one point of the dividers on the point of interest and open them out so that the other point touches the *longitude* grid at its closest point. Move the dividers so that one point touches the same longitude grid where it has a graticule and read of the point's longitude.

Measuring longitude with dividers

Chart Symbols

Each charting organisation has its own standard chart symbols. They are all pretty similar and there's a new international standard set of symbols for electronic charting.



The geographical position is shown by the circle

A lit navigation aid is shown with a magenta flash

Navigation marks



A	10 metres contour
B	3.9 metres sounding
C	0.0 metre sounding,that is, chart datum
D	Rock of unknown depth consider dangerous to surface navigation
E	Rock awash at chart datum
F	Area which covers and uncovers
G	Drying height of 0.2 metres
H	Rocks which cover and uncover
I	Rock which does not cover (height 1.3 metres)
J	Wreck of unknown depth dangerous to surface navigation
K	Foul ground – if you drop your anchor here it may become fouled
L	Recommended anchorage
M	Anchoring prohibited

Some chart symbols

The major hydrographic organisations publish books containing all the symbols that they use and many of the charts produced for leisure boaters have lists of chart symbols printed on their reverse. Most almanacs also contain a list of commonly used symbols.

Some heights and depths are shown inside brackets, such as (1.7). This means that it can't be put on the chart in exactly the correct place, as it would obscure the detail – they put it as close as possible and enclose it in brackets.

Some symbols are much bigger than their physical counterparts – they are out of scale. The geographical location of the symbol, a buoy, say, is shown by a small circle at the base of the symbol.

Lit navigation aids are shown with a magenta flash.



Clearance under a bridge

Clearance under a cable

Safe clearance under a power transmission cable where published otherwise the actual clearance is shown in black

Vertical clearances

Symbols Depicting Dangers to Navigation

Certain symbols should be committed to memory, as you may not have time to look them up before you encounter an unmarked obstruction:

- Shallow water
- Rocks
- Wrecks
- Overhead cables
- Bridges with low clearance

If you are approaching a charted symbol you don't recognise, check what it means before you get too close.


(3.6)
(1.4)
4.2
0
Height
datum
CD

Rock which does not cover, height above chart datum


5
(1.3)
(1.8)
(2.6)
3.6
Height
datum
CD
5m

Rock which covers and uncovers, height above chart datum, where known


5
0
Height
datum
CD
5m

Rock awash at the level of chart datum


5
0
Height
datum
CD
5m

Underwater rock over which the depth is unknown, but which is considered dangerous to surface navigation


Overhead power cable
Charted vertical clearance
Charted vertical clearance (black)
Safe vertical clearance (Magenta)*
Charted elevation
HAT
MHWS
MHWN
MSL
Charted HW (coast) line
Land survey datum
Sea surface at any time
MLWN
MLWS
CD (usually LAT on Admiralty charts)
Height of tide
Observed depth (sounding)
Charted depth
Drying height
Charted LW (drying) line

* The safe vertical clearance to avoid risk of electrical discharge, has been obtained by applying an adjustment to the physical vertical clearance of the cable above HAT. The deduction is variable and depends on the transmission line voltage.

Check on the chart you are using that these definitions apply to that particular chart

Tide levels and height references


30º
3ºW
30º
2ºW
30º
30º
50ºN
50ºN
30º
3ºW
30º
2º
90
120
150
60
30
E
S
N
W
210
240
270
300
330

The Magnetic Compass

The Earth's Magnetic Field

Steering Compasses

Compass Deviation

Compass Correction

DIY Compass 'Swing'

Fluxgate Compasses

The magnetic compass has a magnetised pointer that aligns itself with the Earth's magnetic field. It, therefore, points towards the Earth's north magnetic pole and so allows the user to 'know where North is'.

The Earth's Magnetic Field

There are two aspects of the field which directly concern the compass needle:

- The horizontal component of the field determines the direction the needle points towards the poles. This is the useful part of the field and gives magnetic direction.
- The vertical component of the field forces the needle to tilt in a downward direction towards the nearest pole. This is the detrimental part of the field, which makes the magnetic compass unusable as it nears the magnetic poles. The angle of the field 'downwards' is known as 'dip'.


North magnetic pole
Earth's magnetic field

Compass needle aligns itself with Earth's magnetic field horizontally


North magnetic pole
Earth's magnetic field
South magnetic pole

Compass needle aligns itself with magnetic field vertically

Steering Compasses

A steering compass is designed to be fixed in position on the boat and is used by the helmsman to 'steer' the boat on a compass course. It is mounted in a 'gimbal' so that the compass stays level, regardless of the heeling or pitching motion of the boat.

To best cope with the problems caused by the dip of the Earth's magnetic field, the magnet is suspended under the 'compass card' according to the hemisphere in which it is designed to be used. In fact there are three types of compass: Northern Hemisphere, Equatorial and Southern Hemisphere. In reality, I have a number of friends who have completed full circumnavigations on their yachts using a northern hemisphere compass and they reported experiencing no problems as a result.


Compass card
Compass vertical pivot
Compass magnet
Angle of dip
Horizontal plain of the compass

Northern Hemisphere compass



Equatorial compass



Southern Hemisphere compass

Compass Deviation

A boat is likely to have a magnetic field of its own, due to the magnetic materials such as its engine, incorporated into it. When the boat remains in a fixed position for some time, its own magnetic field becomes aligned with that of the Earth's magnetic field. When the boat is moved onto any other heading, the magnetic field experienced by the steering compass is a combination of the Earth's and the boat's fields and so the compass does not point directly towards magnetic North. This error is called 'deviation' and will vary in value as the boat's heading changes. Not only that, but also the error will vary as the boat heels, although this is difficult to allow for and is normally ignored.

Compass Correction

Compass errors should be measured and corrected. With possible errors as large as 30 degrees, relying on an uncorrected steering compass can result in dangerous navigational errors. Prior to electronic navigation, steering compasses were routinely checked and adjusted, if necessary. These days many boat owners rely on the electronic element of their navigation to take them to their destination and never even consider compass deviation.

Commercial vessels have their compass corrected by professional 'compass adjusters'. Leisure boat owners can check compass deviation themselves and some 'leisure' compasses allow some simple form of correction. Owners of steel vessels need to take special precautions with their compass installations as the steel hull has a significant magnetic influence.

DIY Compass 'Swing'

It is pretty easy to measure compass error and the process is called 'swinging the compass'. Although the process used by the amateur will not be as accurate as when carried out by a professional compass adjuster, it will be entirely adequate for quantifying any major compass errors.

- Align the boat on a northerly heading using the steering compass.
- Using a hand-bearing compass in known position of minimum deviation, note the heading (to the bows of the boat).
- Continue the procedure noting both the steering compass and hand-bearing compass bearings every 30 degrees until you reach north.



Measured deviation

a



Deviation corrected for 'A' error



Magnetic course	Deviation (+ = west)
000	001
030	002
060	005
090	008
120	008
150	007
180	005
210	003
240	001
270	000
300	–001
330	000
360	001

Total	040
Average (A error)	3

Rotate compass 3 degrees eastwards

Measured deviation



Magnetic course	Deviation (+ = west)
000	–002
030	–001
060	002
090	005
120	005
150	004
180	002
210	000
240	–002
270	–003
300	–004
330	–003
360	–002

Deviation corrected for 'A' error

- Draw a deviation curve.
- If the curve sticks out more on one side of zero deviation than the other, the compass can be rotated in its mount to make the average deviation as close to zero as possible. This error is known as 'A' error.


Fixing bolts and slots, allowing limited adjustment of 'A' error

Adjusting compass for 'A' error

Deviation of the Hand-Bearing Compass

Compass deviation occurs due to the boat's magnetic effect where the compass is positioned, not due to any inherent compass problem. When using the hand-bearing compass, you should find a position in the boat where the boat's deviation is zero or a minimum. This is likely to be as far away from any magnetic material as possible. This could be in the bows or the stern depending on the position of the engine.

To check the deviation in any position, sight the hand-bearing compass on a distant but prominent landmark. Let the boat carry out a full 360-degree circle. If there is no deviation, the hand-bearing compass will maintain a constant bearing all the way around the turn. If the bearing changes, the maximum deviation is half the total change of bearing, though you won't know the actual deviation on any particular heading.

Correction for other errors by an amateur on a leisure boat compass is either not possible or not desirable. Knowing and allowing for any error is sufficient.

Very Large Errors Need to be Investigated

One motor cruiser I was checking had compass errors exceeding 30 degrees – entirely unacceptable. Someone had fitted a loudspeaker on the other side of the bulkhead in the cabin and only a few inches from the compass. Removing the speaker removed the deviation!

On another occasion the boat builder had mounted the windscreen wiper motor only 300 mm (one foot) away from the steering compass. As it wasn't practicable to move either, the large deviation had to be accepted and allowed for.

Fluxgate Compasses

Autopilots and radars need a compass input. This comes from a 'fluxgate' compass, which consists of coils that measure the Earth's magnetic field electronically. There's no magnet in this unit, which is mounted remotely in a suitable position, and the output is sent to any unit or display needing magnetic heading information.


'No magnetic material' warning sign
Fluxgate compass detector
COMPASS AREA

Fluxgate compass

Positioning of the Fluxgate Compass

There are two basic requirements:

- a position of minimum motion due to pitch, heave and roll;
- a position on minimum magnetic deviation.

Often these two requirements are in conflict. The first condition is usually achieved by fitting the fluxgate in the after third of the hull's length. The next best is the middle third and the least desirable is the forward third. However, this latter position is often found to be the area of least deviation! Compromise is required.

Note: The detector must be mounted 'athwart ship' and may need to be mounted *either* on the forward *or* aft side of the bulkhead – check the installation instructions.

Magnetic course	Steer binacle	Steer autopliot
000	001(+1)	359(–1)
030	032(+2)	028(–2)
060	065(+5)	059(–1)
090	098(+8)	091(+1)
120	128(+8)	121(+1)
150	157(+7)	148(–2)
180	185(+5)	177(–3)
210	213(+3)	208(–2)
240	241(+1)	239(–1)
270	270(+0)	270(+0)
300	299(–1)	301(+1)
330	330(+0)	331(+1)
360	001(+1)	359(–1)

Combined deviation card

Autopilot Compass Swing

The fluxgate compass is swung in a special calibration procedure, detailed in the operating manual for the autopilot. Although not a perfect procedure, it is likely to result in the removal of most of any deviation but should be followed by a normal compass swing for the autopilot display and a deviation curve or table provided.



Constructing a Route

Using Second-Hand Waypoints

Loading the Route into the GPS

Constructing a Route on an Electronic Chartplotter or PC

These days we probably think of a route defined by a series of *waypoints*, places to which we wish to go in the process of getting from one place to another.

The term waypoint is relatively modern, stemming from the need to find the latitude and longitude of a point so that we could then enter it into a navigation receiver's processor via a keyboard. When navigation was less sophisticated, we would put some lines on the chart and plot our position to endeavour to keep as close to track as possible. There was no need to extract and write down any latitude and longitude at all unless we were using a sextant.

These days we should be able to enter into the 'navigator' the coordinates (latitude and longitude) of any position that is on our 'way'. These are the waypoints.

The process will differ according to the type of 'navigator' we are using; GPS receiver or GPS chartplotter.

Using Second-Hand Waypoints

You can buy books of waypoints. Also pilot books, almanacs and boating magazines list waypoints. I never use waypoints that I have not plotted myself, and I never join waypoints from a list to form a route, unless I have inspected the area on a recognised chart, paper or electronic. What is the point of using waypoints, the author of which states that you use them at your own peril and that they should not be used for navigation?

A Route for Use with a GPS Receiver

Here, our starting point is a paper chart on which we can draw a complete route. It may not have sufficient detail in areas where we are close to danger, but we can see the whole route on one sheet.

Choose your route so that it is as short as possible, *but* avoids passing too close to any possible hazard. It's possible that you may have to adjust the route when you look at smaller scale charts where the route needs to be inspected more closely.

Do not use the actual position of navigational marks as waypoints. GPS can be so accurate that you might collide with the buoy, and if other navigators also use the same mark, you may collide with their boat. Aim 100 metres or so off.

Let us construct a route from Annapolis to St Michaels in the Chesapeake. We'll need a chart with a scale of around 1:125 000 for the overview and charts of a scale of around 1:2 500 for each end where we need more detail.

Starting at Annapolis we can put the first three waypoints on the large-scale chart, before moving to the small-scale chart to add the next seven waypoints.



The small scale chart used for the overall plan



The Annapolis end of the route

Now we'll need to use the large-scale chart for St Michaels to put the rest of the waypoints in place.



The St Michael end of the route



Waypoint symbol



Route from Annapolis to St Michaels – An overview



Route plan
Annapolis - St Michaels

WAY PT.	Latitude north	Longitude west	Distance	Track (T)
1	38 58.61	076 28.78		
			0.95	106
2	38 58.35	076 27.71		
			2.25	150
3	38 57.21	076 27.34		
			1.9	155
4	38 57.20	076 27.34		
			1.5	132
5	38 56.20	076 25.97		
			7	166
6	38 49.92	076 23.65		
			1.5	137
7	38 48.55	076 22.54		
			1.6	072
8	38 48.92	076 20.86		
			2.5	048
9	38 50.68	076 18.28		
			1.6	072
10	38 51.35	076 16.73		
			1.6	025
11	38 52.71	076 15.28		
			0.6	090
12	38 52.71	076 14.82		
			2.4	158
13	38 50.58	076 13.71		
			1	226
14	38 49.94	076 14.36		
			1	102
15	38 49.64	076 13.11		
			1.4	150
16	38 48.67	076 12.44		
			0.35	199
17	38 48.32	076 12.53		
			0.35	184
18	38 48.18	076 12.67		
			0.3	131
19	38 47.71	076 12.35		
			0.6	233
20	38 47.32	076 12.93		
		Total distance	30.4	

Route plan Annapolis – St Michaels

Once you have a safe route, mark the waypoints and determine their coordinates. There's no standard symbol for a waypoint, as there are other navigation details, such as position. Many navigators, however, use a square with a cross in the middle.

Measure the distance and direction of each leg and note these down on a 'plan'. It's a good idea to use a printed 'pro forma' for this, or on the route-planning page of your navigation logbook. You will end up with something like this.

Note that I put the waypoints on every second line, so that the distance and tracks are on the intermediate lines separating each waypoint. This makes it easier to read than some other systems.

Loading the Route into the GPS

The first thing to remember is that 'rubbish in = rubbish out'. We all know how easy it is to miss-key numbers using a keyboard. The only way of checking you have entered the route correctly is to check the route once it has been entered, and this is where the 'tracks and distances' table comes in.

Once the route is loaded, go to the GPS display that shows the distances and tracks between each waypoint. Some early GPS sets didn't allow this and were potentially dangerous. Check that the distances and tracks tally with your 'paper' plan. You may see a constant error in the tracks. This will probably be because you have measured 'true' directions on the chart, but have told the GPS to display bearings in 'magnetic', or *vice versa*. Any discrepancy must be investigated and usually it's because a latitude or longitude has been miss-keyed, or misread from the chart.

This procedure is mandatory if you wish to avoid potential disaster, but *see the next paragraph.*

Problems with Some GPS Receivers

When you try and review the route on *some* GPS receivers, you may find what appears to be a serious discrepancy in the leg distances. This is because the distances shown, on these sets, are not the *leg* distance but the *running totals*! This is unhelpful to the conscientious navigator, who is now required to carry out additional arithmetic to ensure that the route has been correctly entered.

Constructing a Route on an Electronic Chartplotter or PC

This is much simpler than the previous example, but potentially more dangerous because of the small size of the screen. This danger can be avoided by constructing the route on paper charts first and then transferring it to the chartplotter, or by meticulously zooming in and out and panning backwards and forwards on the plotter or PC screen, as you construct the route.

The courses shown are the actual 'leg-to-leg' bearings



These distances shown are in fact the running totals, not the distance of each leg, as one should expect to be displayed on the 'route review page'

Reviewing the route



Tides

Tidal Heights

Tidal Flow

Finding the Value of the Tidal Flow

Tidal Heights

The Earth and its oceans are subject to the tidal 'pull' of the Sun, Moon and planets. As far as navigators are concerned, it is the combined effect on the level of the surface of the seas that is of interest and this is primarily affected by the relative positions of the Sun and the Moon, whose gravity causes a bulge of water in the direction of the gravitational pull. The bulge is stationary, but the rotation of the Earth on its axis makes it appear that the bulge rotates around the Earth once every 24 hours. At this point, most of the books suddenly draw in a second tidal bulge opposite the first to give us our 'two tides a day' without any explanation.

A simple way to view this is that the Earth gets 'pulled' by the gravitational effect as well, but being solid, it gets pulled as one lump, whereas the oceans, being fluid, are distorted. Thus the Earth is moved within the distorted 'oceans' to give two tides a day. The bulge closest to the Sun is of a slightly different shape to that on the opposite side of the Earth so that successive tidal 'curves' are slightly different in shape and height.



The gravitational pull on the fluid oceans – a 'bump' is pulled towards the gravitational source.



The gravitational pull on the solid earth – the whole earth is pulled towards the gravitational source within the 'oceanic bump'

How gravity causes two tides a day

In the open ocean, the tidal effect is very small, with a daily rise and fall of sea level due to gravity of approximately only 0.3 metre or 1 foot. However, where the proximity of land channels the tidal bulge, the rise and fall is increased and values of up to 15 metres (nearly 50 feet) are seen in some parts of the world.

The Mediterranean and other 'inland seas' and Great Lakes are considered to be 'tide free' although there is a small tidal effect. Trieste, in the Mediterranean, for instance, has a spring tidal range of just over a metre, whereas other parts of the 'Med' have ranges of only 0.3 metre (1 foot).

Spring Tides

When the Earth, Sun and Moon are on the same axis, the gravitational effects are at maximum and the tidal bulge is largest. As the Earth spins within the bulge, the sea level rises as the bulge approaches, reaches a maximum and then falls to a minimum about 6 hours later. The difference between the height of the high water and the height of low water, the *range*, is a maximum and this is known as a *spring* tide and occurs twice a month.



Spring tides occur at New and Full moon

Spring tides

Because of inertia effects, spring tides happen a couple of days after the time when the Sun, Moon and Earth are in line. Spring tides occur, then, a couple of days after the New Moon or the Full Moon are seen.

Neap Tides



Neap tides occur at times of 'Half' Moon

Neap tides

When the line joining the Earth and Moon is at right angles to that joining the Earth and Sun, the gravitational force on the Earth and oceans is minimum and so the gravitational bulge is a minimum also. The tidal range at this time is minimum and these 'lower tides' are called *neap* tides. Neap tides are associated with 'Half Moon', but inertia also affects this; so neap tides occur around 2 days after the first and second 'Half Moon'.

Tides change from spring tides to neap tides and back to spring tides over a 14-day period. The heights of a spring and neap tides vary throughout the year, the highest springs being associated approximately with the equinoxes in the spring and autumn; hence the term 'spring' tides. The lowest neaps are associated approximately with the solstices, the origin of the term neap being unclear but probably originating from the old English 'nepflod' used to describe the lowest high waters.

Tidal Range



Variation from spring tide to neap tide

Whether a tide is neap or spring (or an intermediate) is determined not by the height of high water but by the difference between the height of high water and the next (or preceding) low water. This is called the *tidal range*. Spring tides have a large range and neap tides a small one.

The mean sea level remains roughly constant. At springs, the high water is very high and the low water very low, while at neaps, the high water is much lower and the low water much higher.

With the introduction of international standards for electronic charting, there is a trend for all hydrographic authorities to adopt the same terminology for tide levels. Although there are many different tidal height definitions in the United States of America, such as MLW (mean low water), MLLW (mean lower low


MHWS
MHWN
MLWN
MLWS
The various spring tides throughout the year
The various neap tides throughout the year

Mean high and low water levels

water), MHW (mean high water) and MHHW (mean higher high water), which are still used on paper charts, the following are understood and becoming more common:

MHWS – mean high water springs
MLWS – mean low water springs
MHWN – mean high water neaps
MLWN – mean low water neaps.

Approximately, spring tides will be 25% greater than the mean range and neap tides will be 25% less than the mean range.

The Tidal 'Day'



Tidal 'day' is longer than 24 hours

As the Earth spins on its axis once every 24 hours, one might expect that the tidal 'day' would also span 24 hours. In other words, there would be two high waters in 24 hours, each being 12 hours apart. In fact successive high waters are about 12 hours and 25 minutes apart, so why is this?

Each 'second' high water occurs when that meridian faces the Moon (ignoring inertia effects). As the Earth moves along its orbit around the Sun and the Moon moves in its orbit around the Earth, this takes longer than 24 hours. The average 'extra time' between each second high water is around 50 minutes, but varies between 29 minutes and 1 hour and 26 minutes, because the angular rotation of the Earth around the Sun is not constant. Therefore, on an average, each high water is 12 hours and 25 minutes later than the last.

High Water Time

For any given location, the time of day when high water springs occurs is roughly constant. Likewise the time of the local high water neaps is also roughly constant.

Look at your local tide tables to see what these times are for your home port, and you then have a valuable planning tool.

For instance, in the UK's Solent, high water springs occurs at approximately 12 midnight and 12 noon. High water neaps occur at approximately 6 a.m. and 6 p.m. If you look in your diary to check the 'phase' of the Moon, you can get a reasonable idea of the time of high water, which can be useful if you don't have your tide tables to hand.

Chart Datum (Nothing To Do with Map Datum – the Reference for Latitude and Longitude)

For navigation purposes any water depth has to be referenced to a common datum for it to have any meaning. Most authorities use a datum called *chart datum (CD)*, which to all intents and purposes is the lowest astronomical tide (LAT) *for that length of coastline or that particular port.*

In the United States of America, this is LLW (lowest low water). However, MLLW may be used as the tidal datum for tidal curves in the United States of America and is not as low as lowest astronomical tide. In the United Kingdom, it is called CD or LAT, and in France it is 'Niveau zero' the lowest equinoctial tide.

The reason for using LAT is that there will always be at least the depth shown by the soundings, even at low water. Any higher datum will inevitably mean that sometimes there will be less water than the charted depth.

There is a common misunderstanding that chart datum is constant for the whole of a chart, but this is not so. Coastal effects could cause the lowest astronomical tide to be significantly different at two places close together on the same chart.

The table shown indicates the chart datum associated with different places along part of the UK's Kent coast. They are all referred to the UK Ordnance Survey datum situated at Newlyn, Cornwall, in the United Kingdom, this point being the UK's reference for sea level for all UK maps. The table indicates that there is a 2.34 metres difference in LAT along this stretch of coast.



Tidal levels referred to datum of soundings

Place	Latitude (N)	Longitude (E)	Heights in metres above datum				Datum and remarks
			MHWS	MHWN	MLWN	MLWS	
Dover	51° 07'	1° 19'	6.7	5.3	2	0.8	3.67 metres below ordnance datum (Newlyn)
Deal	51° 13'	1° 25'	6.1	5	2	0.8	3.40 metres below ordnance datum (Newlyn)
Richborough	51° 18'	1° 21'	3.3	2.7	0.3	0.1	1.33 metres below ordnance datum (Newlyn)
Ramsgate	51° 20'	1° 25'	4.9	3.8	1.2	0.4	2.58 metres below ordnance datum (Newlyn)
Broadstairs	51° 21'	1° 27'	4.6	3.7	1.3	0.4	2.35 metres below ordnance datum (Newlyn)
Margate	51° 24'	1° 23'	4.8	3.9	1.4	0.5	2.50 metres below ordnance datum (Newlyn)

Chart datum information as found on UKHO charts

It's also worth noting the significant difference in spring and neap tides from place to place along this 35 miles coastline.

Using Chart Datum

Now we have a load of definitions to think about, what use are they? We need to be very careful when checking depths, heights and clearances under obstructions as not all hydrographic authorities use the same standards. Because commercial shipping is changing over to the use of electronic charts, the International Maritime Organisation introduced a new standard in 2006/2007. Beware, then, not only the 'make' of chart, but also when it was issued. You must check the notes on any chart, or the current list of symbols and abbreviations to see what standard applies to the charts you are using.

Charted depths below chart datum (LAT) are added to the tidal height to find the actual depth (the sounding) at any given time.

Drying heights above chart datum (LAT) are subtracted from the tidal height to find the depth at any given time – *by the very nature of the beast, this depth may actually be above the present water level.*


Overhead power cable
Charted vertical clearance
Charted vertical clearance (black)
Safe vertical clearance (Magenta)*
Charted elevation
HAT
MHWS
MHWN
MSL
Charted HW (coast) line
Land survey datum
Sea surface at any time
MLWN
MLWS
CD (usually LAT on Admiralty charts)
Height of tide
Observed depth (sounding)
Charted depth
Drying height
Charted LW (drying) line

* The safe vertical clearance to avoid risk of electrical discharge has been obtained by applying an adjustment to the physical vertical clearance of the cable above HAT. The deduction is variable and depends on the transmission line voltage.

Check on the chart you are using that these definitions apply to that particular chart

Tide levels and height references

The Tidal Curve

All major ports, known as *standard ports or reference ports*, have 'tide tables' prepared for them by various authorities. These are projected for at least 12 months in advance and often considerably longer. They are based on historical records which allow real tides to be matched to astronomical data. Formulae are then deduced that match the data so that projections may be made for future dates. Generally, the 'match' is good, but differences will always occur. Tidal data cannot take account of transient metrological conditions. Atmospheric pressure of 10 millibars (0.03 inch of mercury) above average (1013.2 millibars–29.92 inches of mercury) will force the water level down by 0.1 metre (4 inches) and conversely the water level will rise by the same amount if the pressure is 10 millibars below average. A strong wind blowing from a constant direction for several days can also raise or lower the water level considerably and it is not unknown for meteorological conditions to change the predicted tide level by as much as 0.5 metre and sometimes considerably more.

It could be argued, then, that the pursuit of super-accuracy in tidal calculations is not appropriate for *most* situations. However, in calm conditions, access across a shallow sandbar may be made using carefully calculated 'height of tide' at low speed with little clearance under the keel – preferably on a rising tide in case you get it wrong.

Secondary Ports

It is uneconomical to have tidal curves and full data for all harbours and anchorages. These 'other' harbours are known as *secondary ports* and are listed with tables of differences from a standard port. Using these differences, the times of high and low water and their heights can be calculated from the tide times of the standard port and its tidal curve.



Standard port										
Port dirty			0000 and 1200	0600 and 1800	0100 and 1300	0700 and 1900	5.1	2.6	1.5	0.1
Secondary ports										
				Time differences			Height differences (in metres)			
Place	Latitude	Longitude	High	Water	Low	Water	MHWS	MHWN	MLWN	MLWS
Nice Harbour	43 26	035 45	−0035	−0020	−0010	−0020	+0.4	+0.2	+0.1	+0.0
Hope Cove	43 33	036 21	+1005	+0055	+0020	+0010	−0.2	−0.1	+0.0	+0.0

Secondary port differences

Electronic Tidal Curves

Without any doubt, these are the easiest and quickest ways to obtain tidal height information. Because each provider may use data from different authorities, there may be apparent discrepancies between different products. The differences may seem large at first glance, with times of high water sometimes differing by as much as half an hour, but when you look at the heights involved, these show that they are less than 0.05 metre (less than 2 inches) apart at the same time, so in reality there is a little difference between them.


Time of high water = 11:58
Height of high water = 4.3 metres
Time line
Tidal curve
Tidal Curve
Show as UTC
UTC
Height (m)
Depth (m)
Clearance (m)
Zoom (hrs) 27
4.4 m
0.0 m
Depth 0.0 (m)
Draught 1.5 (m)
Port
SOUTHAMPTON
Close
Height of tide at 15:05 = 2.6 metres
Time line
Time of low water = 17:00
Height of low water = 1.0 metre
Time line

Tidal curve from PC based navigation software (*seaPro*)

All chartplotters have tidal curves these days, as do many of the PC navigation software packages. There are several tidal programmes available for hand-held computers and some ordinary GPS receivers are able to display tidal curves.

In these, having selected the day in question, you only need to scroll the curser along the 'time line' of the curve for the predicted tidal height to be displayed. Many can be programmed with the draft of your boat to give an instant reading of the clearance under your keel. You will need to consult your instruction book to see how to do this with any particular system.

Paper Tidal Curves

Standard Ports

Different authorities present their data in different ways. Although the curves will be similar, the method of extracting the actual heights for times other than high or low water will differ and may not be obvious to someone used to a different method.

The 'Rule of Twelfths'

In the open sea and along coasts which do not alter the natural shape of the tidal curve (a sine wave) very much, a good rule of thumb that needs nothing except the heights of high and low water is the 'rule of twelfths', though you may find a calculator handy.

This assumes that in the first hour after high water the level falls by *one twelfth* of that tide's range from high water; after the second hour it has fallen by *three twelfths*; after the third hour, *by six twelfths*, the fourth hour by *nine twelfths* and the fifth hour by *eleven twelfths*.

This is the principle used by clocks and watches that indicate the state of tide. It follows that these work only if the tidal curve is close to 'normal' in shape.



Multiply the range by the number of twelfths to get the fall from high water

The `rule of twelfths´

UKHO Method

Tidal curves for ports around the United Kingdom are often far from symmetrical and don't lend themselves to 'rule of thumb' methods of calculation. The UKHO has developed an excellent and simple method of obtaining the height of tide at any time. For full details of this method see Appendix 3.



UKHO style tidal curve for port somewhere

The French (SHOM) Method

The French take a very different approach, which works well for 'smooth' curves, but doesn't take account of 'lumpy' curves, as does the UK method. To allow for neaps and springs, each 'tide' is given a factor, with 100 representing the equinoctial tides above and below mean water level, whose factor is zero. This gives an immediate idea of how 'springy' or 'neapy' the tide is. A graphical solution is used to calculate the height of tide at any given time which takes into account any differences in time taken for the tide to rise, compared with how long it takes to fall (the skew of the tidal curve), but doesn't allow for any 'bumps'. This method is easy, but accurate only for smooth curves. (see Appendix 3 for full details).

Secondary Ports

The UKHO tidal curves make it very easy to adapt the curve for the standard port into the curve for the secondary port, using a graphical solution. With practice the procedure is quick and easy, although to be honest, many yachtsmen are put off using it, maybe because they are striving after unnecessary accuracy.

The French (SHOM) method allows calculation of tidal heights for secondary ports.

Most of the others require mental gymnastics if you need to know tidal heights at times other than high or low water.

For detailed instructions, see Appendix 3.

Calculating the Depth of Water

The principal reason for using tidal height data is to check if the water is deep enough for your boat or that there's sufficient clearance to pass under a bridge or cable. You can use 'electronic' tidal curves if you have them – that's the easiest way – or you'll need to do it all on paper.

Depth in Which to Anchor

It's a good idea to consult the chart for the general depths and to see if there are any rocks or shallow bits, but you won't be using chart datum or soundings.

What you need to know is how much the tide will fall from *now* until the *time of low water.*

Add to this the *draft* of your boat and the *safety allowance* you would like under your keel, what the French call the 'navigator's foot' (pied de pilote), and that's it! That's the minimum depth in which to anchor.

If you are staying over more than one tide, remember to check the lowest low water over the period that you expect to anchor. If it's getting more 'springy', your under-keel clearance will get less each tide.


6.7m
DEPTH
Draft
1
Clearance
1.5
Minimum depth required
2.5
Fall from now until low water
Sea bed
Fall from now until low water
4.2
Fall = 4.2
plus
Minimum Depth = 2.5
equals
Depth to anchor = 6.7
2.5m
DEPTH
Draft
Clearance
Minimum depth required
Sea bed

Depth to anchor

Calculating the Depth of Water

For this you will need to consider the chart datum and the charted depth or drying height.

Add the charted depth to the height of tide or subtract the drying height from the height of tide to find the depth of water.


Height of tide = 3.8
plus
Sounding = 2.3
Depth of water = 6.1
Tidal curve
Height of tide
Depth of water
Chart datum (LAT)
Sounding
Sea bed

Calculating the depth of water with a sounding


Height of tide = 3.8
minus
Drying height = −1.8
Depth of water =2.0
Tidal curve
Height of tide
Depth of water
Drying height
Chart datum (LAT)
Sea bed

Calculating the depth of water with a drying height

Is There Enough Depth of Water to Allow My Passage?

Here we use the depth calculated as above and compare it with the draft of the boat plus the safety allowance. If the depth is greater, we're fine, if it's less we can't proceed. Often we need to find the earliest and latest times we can pass over a sandbar into or out of a harbour. For this we need to know between what times the depth of water will be at least our draft plus allowance.


2.0
Draft
Minimum depth required
3.5
Clearance
1.5


Times, between which, boat may pass over shallows
Minimum depth required = 3.5
Depth of water = Height of tide 6.1 minus drying height 2.6 = 3.5
Height of tide 6.1
Depth of water
3.5
Drying height
Chart datum (LAT)
-2.6

When can we enter or leave?

Can We Get Under the Bridge?

In this calculation we use a different *datum*. If we used LAT, there would *always* be less clearance than that shown on the chart, except at lowest astronomical tide, LAT or its equivalent. This would be potentially dangerous. Until 2006, different authorities used some form of 'higher high water' – MHWS in the United Kingdom or MHW in the United States America. In France they used mean sea level. Now all *new* charts should use highest astronomical tide (HAT). Check what standard your chart is using if you don't have much clearance.

The charted clearance under a cable takes into account the electrically safe clearance, that is there's an allowance for how far the spark can jump! A high-voltage cable will have a bigger allowance than if it were low voltage.

This calculation is a little more complicated because the clearance is above HAT but the water level is above LAT. All we have to do is *add* the *difference* between *HAT* and *LAT* to the charted *clearance*, *subtract* the *height of tide* and we have the *clearance above the water* level. Ok, so a picture is worth a thousand words; well, here's the picture. And yes it's safe to go under. We can, if we need to, find the times between which we can pass safely under the obstruction.


Allowance 2.0
Our requirement 17
Height of mast 15
Charted clearance 18.6
Actual clearance 20.5
HAT
6.2
LAT
Height of tide 4.3
HAT – LAT
= 6.2
Height of tide = 4.3
clearance
= 18.6 + 6.2 – 4.3
= 20.5

Clearance under a bridge

Tidal Flow

The Speed of the Bulge

The Earth spins within the tidal bulges, giving the appearance that the bulges rotate around the Earth. At the Equator, the 'ground speed' of the Earth, due to its spin, is approximately 1000 miles per hour and at 45 degrees North and South, this speed is approximately 700 miles per hour. At 45 degrees latitude, high tide rushes towards us from the east at 700 miles per hour. Makes you think, doesn't it?


Apparent rotation of tidal bulge around the Earth
Rotation of earth on its axis

Rotation of the tidal bulge around the earth


Low water
Tidal flow
Tidal flow
High water
High water
Tidal flow
Tidal flow
Low water

Tidal currents flow 'downhill' from high water to low water


Strong tidal current
High water springs
Low water springs
Weak tidal current
High water neaps
Low water neaps

Strength of tidal current

Where there is a constriction to the flow of the tidal bulge, such as in the English Channel, this speed is considerably modified with the bulge taking around 6 hours to travel from Dover to Falmouth, a distance of about 250 miles, a speed of around 40 miles per hour.

What Causes the Tidal Currents?

The prime mover is the difference between the heights of tide at any two places. Water wants to flow downhill, which is exactly what it does. Thus you would expect there to be zero current at high water as the tide changes direction. This is called *slack water*. The same applies at low water.

However, this is not always the case, as there may be another current flowing as well, which will add to, or subtract from, the tidal current. Consider a river estuary: There may be a river current of three knots, flowing towards the sea. The *flood tide* may be flowing at two knots upstream, so although the tide is rising, the current is still flowing out to sea at one knot – opposite to that which you might expect.

The speed of the tidal current will be strongest at spring tides and weakest at neaps because the slope of the water is steeper at springs as the high water is higher and the low water lower.

Currents due to Eddies

Less intuitive is somewhere such as the Channel Islands, situated in the English Channel. Because the Channel Islands are situated in a large bight and the English Channel becomes very much narrower at this point, a large, rotating, tidal eddy is set up which at times runs counter to the current set up directly by the tidal bulge. In parts of this area, slack water occurs at 'half tide up' and 'half tide down'!



Rotary tidal flow



1 hour before half tide falling

1 hour after half tide falling

Slack water at St Peterport (Guernsey) occurs at half tide up and half tide down

Eddies in a channel, close to the shore can cause the tidal current to reverse some time ahead of 'slack water'. Knowledge of these is very useful if you are trying to 'cheat' the tide.

Currents Caused by Wind

Tidal currents can be modified by wind. A strong wind blowing for some time sets up a general movement of the surface water due to friction. This wind driven surface current can counter or add to the tidal current, and needs to be considered when considering the tidal *set and drift* (the tidal effect on the boat) when planning a passage.

Wind Against Tide

Where a wind driven surface current is running counter to the tidal current, a significant change in wave shape will occur. This effect is known as *wind against tide* and can make a relatively calm sea change abruptly as the tide 'turns'. Where the tidal current is large and the wind strong, conditions can change from *uncomfortable* to *dangerous* very rapidly.

Currents in the Open Oceans and Inland Seas

Because the difference in water level due to the tide is usually very small, generally there's no significant tidal flow. However, this doesn't mean that there are no currents. Currents may be seasonal, such as the North Atlantic's Gulf Stream, in which case they can be predicted long term, or wind driven, in which case they change from day to day.



Even though the difference in tidal heights is small, a restriction to the flow by such things as islands can cause acceleration to the small tidal current to a much larger value that needs to be taken into account. Amongst other places, this effect can be seen in parts of the Mediterranean Sea.

Finding the Value of the Tidal Flow

Various hydrographic departments will have built up a database of tidal flow at specific points during the tidal cycle for neap and spring tides.

Tidal Diamonds

These specific points are shown on charts as a diamond with a letter of the alphabet inside the diamond. These are known as tidal diamonds.

A table is included with specific values of tidal set (spring and neap values) and direction for each hour before and after high water at the stated reference port at the position of each diamond.

The lettered diamonds indicate the position for each set of tidal stream data


C-MAP
ATLANTIC OCEAN
Hartland Point
Boscastle
Exeter
Lyme Regis
DARTMOOR
Berry Head
Start Point
Newquay
A
B
C
ENGLISH CHANNEL
Cap de la Hague
1 : 1500000

The table of tidal stream data

Tidal diamonds



Hours	◇ Geographical Position		◇ A 50°13'.00N 2°55'00W			◇ B 49°38'.00N 3°22'00W			◇ C 49°10'.00N 4°37'00W			
	Directions of streams (degrees) / Rates at spring tides (knots) / Rates at neap tides (knots)											
Before high water 6		–6	074	0.9	0.4	064	1.3	0.7	079	0.8	0.4	–6
Before high water 5		–5	082	1.5	0.7	065	2.3	1.2	085	2.7	1.3	–5
Before high water 4		–4	085	2.0	1.0	067	2.7	1.3	083	2.8	1.4	–4
Before high water 3		–3	089	2.1	1.1	070	2.3	1.1	082	1.7	0.8	–3
Before high water 2		–2	090	1.6	0.8	071	1.5	0.8	083	0.6	0.3	–2
Before high water 1		–1	096	0.7	0.3	062	0.4	0.2	084	0.4	0.2	–1
High Water		0	256	0.6	0.3	256	1.2	0.6	258	0.9	0.5	0
After high water 1		+1	266	1.8	0.9	251	2.2	1.1	268	2.3	1.2	+1
After high water 2		+2	265	2.1	1.0	246	2.6	1.3	266	2.7	1.4	+2
After high water 3		+3	264	2.2	1.1	244	2.2	1.1	262	2.8	1.4	+3
After high water 4		+4	267	1.5	0.7	248	1.6	1.8	264	2.0	1.0	+4
After high water 5		+5	271	0.4	0.2	259	0.4	0.2	270	0.8	0.5	+5
After high water 6		+6	062	0.5	0.3	062	0.9	0.4	070	0.4	0.2	+6

Tidal stream data for each hour before and after the time of high water

We can see that there is only one reference port for any tidal flow table. The time of high water is not for the position of the diamond or even for the nearest port. The reference port may not even be on that chart. It is chosen by the hydrographer to give the most helpful and representative reference time of high water for the area under consideration.

Tidal Atlases

Many charts, pilot books and almanacs contain tidal atlases showing the tidal currents. A small chart has tidal flow arrows marked on it, together with the speed of the current. There is 1 chart for every hour, so there will be 12 charts, enabling the user to estimate the tide at any time in the tidal cycle.

The actual values used in tidal atlases are obtained using the tidal diamond data.

High water Dover (0540 after HW Devonport)


05,11
ATLANTIC OCEAN
Hartland Point
Boscastle
Trevose Head
Newquay
DARTMOOR
Exeter
Lyme Regis
Berry Head
Start Point
02,03
03,05
ISLES OF SCILLY
Seven Stones
CHANNEL
0.6,11
Cap de la Hague
Hurd Deep
ENGLISH CHANNEL
Carteret
Lessay
Coutances
Granville
05,13
08,18
Banc des Langoustiers
1 : 1500000
C-MAP

Tidal stream atlas for western English Channel

Tidal Diamonds Versus Tidal Atlases

Which should you use, diamonds or atlases? If you need to know the information for a particular point such as when diving, use the diamond. For planning or general navigation, it's normally easier to use an atlas.

Tidal Speeds and Directions

Generally, there will be two values for the tidal speed, one for spring tides and one for neap tides. Often these are shown without a decimal point, so 23 is not twenty-three knots, but two point three. Where two figures are shown, the greater is for spring tides, the lesser for neaps and a mental interpolation is sufficiently accurate – in other words, a good guess.

The direction of the tidal arrow is the direction of the flow. Tides, unlike winds, flow *to* a compass point, so a north-westerly tide is flowing towards the north-west. On many tidal atlases the boldness of the arrow signifies its speed.

Each chart will be named for a specific hour before or after high water at the reference port. The currents shown are the average for that particular hour, and apply from half an hour before until half an hour after the nominal time.

Tidal Reference Port

The reference port for tidal atlases need not be for any port particularly close or even within the charted area. What matters is that high water times and tidal range are readily available and that ideally it's in the same time zone so that silly errors can be avoided. The reference port is always stated on the tidal atlas.

You could, and mostly would, be approaching a destination, whose *standard* port for tidal *height* calculations is different from the *reference* port used to obtain the tidal *flow*. This is normal, but sometimes confusion arises as to which information should be in use.

The rule is simple: use the reference port shown on the tidal atlas for the tidal flow, and the standard or secondary port shown on the tide tables for the height of tide.

Tidal Flows on Chartplotters

The electronic charts supplied with modern chartplotters usually have a database that allows the tidal flow to be shown in real time on the plotter's screen. The arrows often have different colours to represent different speed bands. Some allow the tidal flow at different times and the flow at a specific point to be displayed.

Tidal Flows on PC Charting Software

Tidal flow arrows can be shown on many brands of chart-plotting software. Often, by placing the curser at a particular point, the actual value can be shown for that point.


SIMULATION
FIX > CURSOR
50°28.491N
000°58.940W
SOG 6.0 Kts
COG 244° M
DST 16.62 Nm
BRG 180° M

Tidal flow arrows on C-Map max electronic chartplotter


SIMULATION
FIX > CURSOR
50°27.339N
000°59.395W
SOG 6.0 Kts
COG 244° M
DST 17.33 Nm
BRG 177° M
INCR. TIME
DECR. TIME
SET TIME
EXIT

Actual value of tidal flow at the curser. Using the keys to increment or decrement time in one-hour steps, the change in flow can be investigated. A specific time can also be set.


New time
SIMULATION
FIX > CURSOR
50°27.339N
000°59.395W
SOG 6.0 Kts
COG 244° M
DST 16.89 Nm
BRG 173° M
INCR. TIME
DECR. TIME
SET TIME
EXIT
Change keys

Investigating the flow C-map max

Toolbar allows time to be changed so that tidal flow can be investigated



Seapro tidal flow



Tidal flow arrows on Seapro PC plotting software


2007/06/05 13:31:17
2007/06/05 13:31:17
SOUTHAMPTON
PORTSMOUTH
Littlehampton
OK

Estimated flow at 50 11.202N 1 3.642W

Rate 0.6 kts. Dr 107°.

Tidal flow at a specific point and time Seapro

It is of help when planning a trip to 'scroll' the displayed chart backwards and forwards in time to see how the tidal flow changes during the day for any date. This is much the same as looking at the various plates on a tidal atlas, but with the computer doing all the high water time calculations for you.


30º
3ºW
30º
2º
30º
30º
50ºN
50ºN
30º
3ºW
30º
2º

Boat Speed

Speed over the Ground

Speed Through the Water

Measuring Speed Through the Water

Log Errors

There are two sorts of boat speed: speed through the water and speed over the ground.

Speed over the Ground

Speed over the ground (SOG) is measured by GPS and is the total sum of boat speed, tidal effect and wind effect. It is covered in Chapter 1.

Speed Through the Water

This is the resulting speed through the water due to the power of the engine or sails overcoming the drag of the boat in the water and in the air. It is a measure of the boat's performance and is used for traditional chart work and navigation.

Measuring Speed Through the Water

A 'transducer' measures the flow of water past the hull and sends the information to the speed instrument.

Modern speed transducers consist of a paddlewheel protruding slightly below the hull into the water. Any flow of water past the paddlewheel causes it to rotate and the electronics counts the number of revolutions in a given time. This allows the electronics to calculate boat speed and distance travelled. The 'log' as the transducer is known, often incorporates a water temperature transducer as well. Some earlier logs had a little propeller-shaped transducer mounted behind a small fin. The traditional 'trailing log' used a propeller on a long length of line, let out behind the boat, and a mechanical counter that displayed distance travelled. The navigator had to calculate his own speed.

Logs with no moving parts, using the 'Doppler shift' in frequency to measure boat speed have been tried but did not find favour.



Paddle wheel log

Log Errors

The log will read the correct speed (and distance) only if the speed of the water flowing past the hull is the same as the boat's speed through the water. Seems pretty obvious, but because of friction, the layer of water close to the hull gets slowed down. In reality of course, it's the boat that's moving through the stationary water, but the effect is the same – The boat drags some of the water close to the hull along with it.

To allow for the friction effect, the log must be calibrated.

Calibrating the Log

Traditionally, the boat would have covered an official 'measured mile' in both directions and the log distance would have been averaged to calibrate the log.

Today, the GPS 'speed over ground' can be observed and the predicted tidal flow used to calibrate the log.

Two Ways to Do It:

Slack Water

- Calculate the time of slack water.
- Proceed to a buoy or post so that you can check that the tide is slack by observing its 'wake'.
- Adjust the log speed readout to agree with the GPS SOG.



Slack water

Any Other Time

- Use the tidal atlas (or chartplotter tidal flow facility) to find the tidal flow at the current time.
- Find a buoy or post and motor into tide to make the boat stationary relative to the post. SOG should be zero and the boat speed should indicate the strength of tide, which should agree with the prediction.
- Motor at your normal cruising speed and adjust the log speed to agree with the GPS SOG, allowing for tide; that is if you are motoring into a tide of 2 knots, the boat speed should read 2 knots more than SOG.

30°
3°W
30°
2°
30°
30°
50°N
50°N
30°
3°W
30°
2°

Depth Sounders

How They Work

Depth Units

Calibration

Depth Alarms

False Echoes

Fishfinders

The depth of water in which the boat is floating is measured by a depth (or echo) sounder.

How They Work

A transponder sends a pulse of energy downwards from the bottom of the boat. This pulse is reflected by the seabed and returned to the transponder, which is now listening for the return. The time taken for the pulse to travel from the boat to the seabed and return can be translated by the depth sounder's electronics into the depth of water below the transponder. This depth is displayed on the screen of the depth instrument.


Sea level
Depth transducer
Reflected pulses
Transmitted pulses
Seabed

Depth sounder operation

Depth Units

Depth sounders can be set to fathoms (one fathom equals 6 feet), feet or metres. Ideally, the units displayed should be the same as those of the navigation chart you're using.

Calibration

By default, the depth displayed will be the depth below the transducer, which is of no use to anyone. Normally, you'll be able to adjust the display to show the depth below the keel or the depth below the waterline. This is known as an offset.

Many users set the depth to 'depth below the keel'. However, if you wish to use the depth sounder as a navigation tool, it's much better to set the offset so that 'depth below the waterline' is displayed. This is the actual depth of water. If you want to know the depth below the keel, all you need to do is to subtract the draft of the boat and this becomes an automatic action.

How to Calibrate Your Depth Sounder

- Moor your boat in fairly shallow water, preferably with a seabed that is firm and of constant depth.
- Lower a weighted line over the side until the weight just touches the bottom (the line just goes slightly slack).


Weighted line
Sea level
Offset +
Depth transducer
Offset -
Depth below waterline
Depth below transducer
Depth below keel
Seabed

Depth sounder calibration

- Note the point on the line where it enters the surface of the water (if you're quick in hauling the line back up, you'll see where the line becomes wet).
- Measure the 'wet' length of the line.
- Adjust the depth sounder offset so that the unit displays the actual depth of water.
- If you prefer to have 'depth below the keel', set the offset so that the unit displays the actual depth minus the draft of the boat.

Depth Alarms

Many depth sounders allow you to set up one or more audio alarms to warn you that the water is getting shallower (or deeper) than you would like so that you can take appropriate action.

False Echoes

Reflections from turbulence may cause a false shallow depth to be indicated or the signal may be lost altogether, causing the display to flash on and off.



False echo

Fishfinders

Fishfinders use these 'false' echoes to indicate the presence of fish and expert fishermen can even identify the type of fish on very sensitive units.

EAGLE
0
20.9
40
CUDA 128

Fishfinder display

30°
3°W
30°
2°
30°
30°
50°N
50°N
30°
3°W
30°
2°
STANDARD HORIZON
SOG 0.0 Kts
COG 172 M
DST ---.- Nm
BRG --- M
TTG --:--
TIME 10:24:59
Plymouth
English Channel
GPS Chart 1000 C

Finding Position

GPS

Other Methods

Position Lines

Fixing Your Position Using Position Lines

Errors in Position Lines

How Far Can You See?

When All Else Fails

Chartplotters

GPS

A GPS receiver will give us our present position in the form of Latitude and Longitude, so that we won't know where we are until we plot this on a chart.

Active Route

If we have constructed and activated a route, or used the 'Go-To' or MOB functions, our GPS set will give us distance and bearing to the next waypoint and also any cross-track error. The cross-track error is how far left or right we are from the direct line between the position that we activated the route (or pressed the GO-To or MOB keys) and the next waypoint (or place we want to go to or MOB).

The distance to go, bearing to waypoint and cross-track error can all be used as position lines to plot on a chart to make fixing our position easier. Remember though these three types of position line are GPS based and if that is in error, our position lines are inaccurate and could be dangerous. As usual, we should always use as many different navigation tools as possible.


Bearing to waypoint
Distance to waypoint
Cross-track error (XTE)
WP 6
WP 7
C-MAP
LONG ISLAND
SMITHTOWN BAY

Bearing and distance to waypoint and cross-track error


WP 6
WP 7
FIX
C-MAP
LONG ISLAND
SMITHTOWN BAY

GPS fix – brg, dist and XTE

Other Methods

In the age of satellite navigation, it might seem illogical to use anything other than GPS as a means of finding ones position. Indeed, one can argue that to proceed to sea without GPS could be construed as negligent.

However, in Chapter 1 (GPS) and Chapter 2 (Charts) we have seen that errors are possible. On top of this the failure of a single GPS receiver or its power supply can deprive us of this vital piece of equipment.

The most obvious alternative to GPS is visual navigation or pilotage. If you are passing a named buoy or obvious landmark, you know where you are. There are other well-tried methods as well.

Position Lines

A position line is a line on the chart or earth's surface on which you must lie. There are a number of means of obtaining position lines and different means may be mixed to 'fix' your position.

Hand-Bearing Compass

A small hand-held compass can be aligned with a geographical feature and the magnetic bearing from the boat to the feature measured.

In order to plot this bearing on a paper chart, it must be converted to a bearing of the boat from the feature by adding or subtracting 180 degrees. This is known as the reciprocal bearing. The magnetic bearing must also be converted to a true bearing by adding the variation if East or subtracting if West. Using a Portland type plotter, all the conversion can be achieved on the plotter, rather than in the head or on paper. It is very difficult to achieve an accuracy of better than 5 degrees due to the motion of the boat. A legs-apart stance to brace your body is advised.



Single Position Line Using a Hand-Bearing Compass

In this case, a bearing from a boat to a lighthouse is measured as 277 degrees magnetic using a hand-bearing compass. The magnetic variation is 8 degrees East, so the true bearing is 285 degrees. Using the plotter as described in Chapter 2, it



Single position line using a hand-bearing compass is aligned with the base of the lighthouse symbol. The boat must lie somewhere on the position line drawn along the plotter's edge (shown in red).

Single Position Line on a Depth Feature

Here, we are crossing the English Channel. If we suddenly find that our depth, corrected for height of tide is between 1.6 and 2.7 metres, we must be somewhere along this very narrow depth feature, so we have an excellent single position line.





A single position line derived from a linear depth feature

Single Position Line from a Transit

A transit is the visual alignment of two geographical features. If these features are aligned, you must be exactly on a position line joining them. It is the most accurate form of position line available. A transit may be the alignment of two natural features or the alignment of two deliberately placed navigation marks provided for safe navigation through a hazard-strewn area. In the latter case, the most seaward of the two marks is lower than the most landward one to ensure that you know which way to turn should you wander off the alignment. Official transits marked on a chart always have their directions given in degrees True.





A position line derived from being on a 'transit'

Single Position Line Derived from Radar

Radar can allow us to measure both distance and bearing from a geographical position. Bearing is the least accurate and should not be relied on unless you have nothing better. Range (distance) is much more accurate. A distance from your boat to a feature as measured by radar will provide a curved position line, so you will need a pair of compasses to draw this on your chart.


6nm
0°T
Range = 3.9 miles
RANGE
Mono LCD radar
real time scale
HDG MODE
TARGETS
SCREEN
MARPA


BOURNEMOUTH
POOLE BAY
3.9 miles radius
C-MAP by JEPPESEN

Radar range position line

Fixing Your Position Using Position Lines

Fixing your position using position lines should normally consist of three lines, with an angle between each line of 60 degrees for best accuracy, though this is often not possible. Features chosen should be unambiguous, easily identified both on the chart and on the skyline. If you are under way, measure the bearing that changes most slowly first (the one nearest ahead or astern) and the bearing that is changing most rapidly (the one nearest abeam) last. The time that you take the last bearing is the time of the 'fix'. Your position (at the time of the fix) is where the position lines intersect. The convention is to


ISLE OF WIGHT
The Needles
12:46
27.6 miles
C-MAP

A three position line fix

draw a circle around this position, enter the time of the fix and the distance log reading at that time. Using the standard convention, anyone looking at your chart will have all the data needed, without having to look at your written logbook.

Errors in Position Lines

A big advantage of visual and radar position lines is that you are not relying on the accuracy of the cartography to avoid hitting the land. The land is where you or your radar sees it, not where the GPS or the mapmaker tells you where they think it is.

The position given by your position lines is correct in relation to the land, though it may not tally with the latitudes and longitudes shown on your chart – This is important if your charts have large errors, as some do. If your chartplotter shows that your boat is travelling merrily over the land, but your eyes show you to be safely floating on the water, which are you going to believe? Just have a look at the trace from this chartplotter.

It is very difficult to achieve an accuracy of better than plus or minus two and a half degrees when using a hand-bearing compass on a boat at sea. This will lead to errors of


HOTEL ATLANTICO
PILOT
FORTE DE
SANTA CATARINA
16MT
MARINA
CHANDLER
YACHT CLUB
SAO MARTINHO
Waypoint



Error due to incorrect variation



Possible error in fix

±800 metres at 10 miles range from the feature, 400 metres at 5 miles and 250 metres at 3 miles, respectively.

Instead of the position lines intersecting at a point, you'll get a 'cocked hat'. The size of the cocked hat will give an idea of the accuracy of the fix.

The green polygon shown on the accuracy diagram is the area in which you might lie with a plus or minus two and a half degree error in all three bearings.

In particular, avoid the application of variation in the wrong direction, otherwise large errors can occur.

Transits

There should be zero error when the position line is based on a transit and hence a perfect fix results from the intersection of two transits.

Radar

The error of a position line based on a radar range should be no more than 1% of the range, though identifying the exact position of the geographical feature may not be so easy. Radar bearings are prone to error due to the alignment of the antenna, the width of the radar beam, the difficulty of identifying the feature and the application of deviation and variation, so should be used with caution.

How Far Can You See?

Because of the curvature of the earth's surface, the distance to the horizon, which is determined by your eye level, is possibly not as far as you might think. From an eye height of 2 metres it's only a little over 3 miles! Therefore, a buoy beyond 3 miles won't be seen, though in fact most buoys



Eye height (metres)	Distance to horizon (*N* miles)	Eye height (feet)	Object height (metres)	Distance to horizon (*N* miles)	Object height (feet)
2	3.11	7	2	3.11	7
4	4.40	13	4	4.40	13
6	5.39	20	6	5.39	20
8	6.22	26	8	6.22	26
10	6.96	33	10	6.96	33
15	8.52	49	15	8.52	49
20	9.84	65	20	9.84	65
50	15.56	163	50	15.56	163
100	22.00	325	100	22.00	325

Add the *distance to horizon* for your eye height to *distance to horizon* for the charted height of the object to obtain the distance it should be visible.

For a light, use this or the charted visibility, which ever is least.

Visible distance

are too small to be recognised from even this short distance. An object beyond your horizon can still be seen if its highest part is high enough to project above the horizon.

The things that determine how far away any object will be visible are:

- The meteorological visibility – Is it foggy?
- How big it is – Is it actually large enough to be discerned by your eye?
- Your eye height – If you are standing on top of a hill, you can see further.
- How high the object is – Is it high enough to project above your horizon?
- At night, how bright the object's light is?

Nautical almanac's provide tables of distance to the horizon for different eye heights and different object heights. Charts detail the heights of terrain, vertical structures such as chimneys and the heights of lights. They also show the visibility of lights in standard atmospheric conditions. Experience tells you how far away you can discern a buoy, typically no more than a couple of miles at most.

When All Else Fails

If you know where you started from, the course you have been steering, the distance you have travelled, you can deduce where you are. This is called 'deduced reckoning' or 'DR', often called 'ded reckoning' or more frequently 'dead reckoning' – Take your pick.

If you're in tidal waters, then by applying how far the tide will have carried you while you've been travelling, you can estimate where you now are. Unsurprisingly this is known as 'estimated position' or 'EP'.

This method has been used since navigators started roaming the seas and is surprisingly accurate. Using this method, it's unlikely that you'll become terribly lost, provided that your compass and log have been properly calibrated. You'll almost certainly be no more than 10% of your logged distance run from your actual position. The chances are that you'll be much closer, so don't deride this method.

EP and DR are covered fully in Appendix A.


ISLE OF WIGHT
Handfast Pt
The Needles
Anvil Pt
Distance travelled in 1hour on a compass heading of 186 degrees true
DR
position
C-MAP by JEPPESEN

Dead reckoning position


ISLE OF WIGHT
Handfast Pt
Anvil Pt
14:22
24.6 miles
Distance travelled in 1 hour on a compass heading of 186 degrees true
EP
15:22
32.4 miles
DR
position
C-MAP by JEPPESEN

Estimated position

Chartplotters

An electronic chartplotter is a navigation instrument that displays the position of the boat superimposed on an electronic chart. You will find an electronic chartplotter simulator on the Wiley Nautical website at www.wileynautical.com

The boat's position is determined by a GPS receiver. The GPS receiver may be part of the chartplotter, with either an internal or external GPS antenna. Alternatively, the chartplotter may be supplied from a separate GPS receiver.

An electronic chartplotter

C-MAP
NT+
16-SEP-2002
M-EW-C203.04
FRANCE ATLANTIC COASTS
B5XX.0043
MW++

Chart data card


10:26:09
0.0
123
E
135
S

Turn boat to follow 'highway'


50 09.951N
001 02.143W
01:46 PM
00:05
355
6.0
065
0.578
N
W
E
S

The yellow arrow shows the direction to follow



The waypoint is 0.356 miles distant and you will arive in 3 minutes

50 10.136N
001 01.872W
01:49 PM
00:03
080
6.0
081
0.356
N
S

The waypoint is now dead ahead
(alligned with the red line, which allows for tide and leeway)

The electronic chart is supplied on a data card that is plugged into a card slot in the chartplotter. The electronic cartography may be provided by the chartplotter's manufacturer or by a third party provider. Ensuring accurate and up-to-date cartography is a large undertaking and some may consider that a large, well-funded specialist provider may be more accurate than a smaller provider's wares. Most chartplotter manufacturers stick with one provider, but some allow the use of several.

What Can a Chartplotter Do?

Tell You Where You Are

The first and most obvious thing is to display the boat's position on the chart so that you know where the boat is at any time. There are caveats here – See GPS errors in Chapter 1 and chart errors in Chapter 2. There are no source diagrams on electronic charts, although they may refer to the cartography on which they are based or at least the date of the source chart. That gives no idea at all of the date of the surveys, which may well have been in the 19th century.

Allow You to Construct a Route

You can construct a route that you would like the boat to follow. Here, there's another warning. Unlike a car's 'satnav', which is supposed to know where the roads are and will confine the route to known roads, there are no roads at sea. Ask the chartplotter to plan a route between two points which have land or rocks in the way, *it will direct you to run aground*! As detailed in Chapter 4, you must inspect the route thoroughly after you have constructed it.

Allow You to Follow a Route

Having constructed your route, you can follow the progress of the boat along the route to get you where you wish to go. This can be done in several ways:

- Steer the boat to keep as close as possible to the route as drawn on the chart.
- Allow the autopilot to follow the route automatically, although I don't approve of this method. Although this is the normal practise on airliners, there are several dangers on small craft. The navigator is never really aware of the compass course followed and so compass errors can pass undetected. The helmsman/navigator is removed from the close control of the boat and becomes less involved in its safe operation.
- Use one of several other displays available on the chartplotter to keep on track such as the highway or compass.

Allow You to Go Direct to Any Geographical Point

Chartplotters normally have a 'GO TO' function. If the cursor is placed over the point that you wish to go to and the you press the 'GO TO' key, a single leg route is set up giving you near instantaneous instructions of how to get there.



Place the cursor on your destination



Select 'CURSOR' in the 'pop-up' window



'Pop-up' window will show distance and bearing to new destination

Select 'HIGHWAY' soft key to display highway



Turn boat to follow 'highway' or 'compass'

Allow You to Estimate the Height of Tide

Many chartplotters allow the tidal curve for a specified point to be displayed. There will be a number of tidal stations within the database, signified by a special logo on the chart. If the cursor is 'hovered' over the logo, the curve can be displayed.



Tidal curve for a designated point

Allow You to View the Tidal Flow

Many chartplotters are able to display the tidal flow in real time. Both the size and colour of the arrows vary according to the strength of the current.

Tidal flow arrows (red = strong)

Man Overboard

Most chartplotters have a 'man overboard', key. This operates much like the 'GO TO' function, except that when you press the 'MOB' key, the geographical point at that instant is the point to which you wish to go. It is very worth while you experimenting with this function – It won't send any alarms to anybody.

Remember! The position shown for the casualty does *not* take into account any tidal drift. You will have to look down tide for the casualty. A 1 knot tide will cause a drift of



Press Man Overboard (MOB) button

Distance and bearing to MOB

This tells you that MOB has been activated


Track of boat
MOB position
ZOOM IN
Boat position
1. Press any key along bottom
2. Press key under NAV




Position of MOB
Red line is your COG (course over ground)
COG
Bearing to MOB
Distance to MOB
Yellow arrow points to MOB

50 09.903N
001 01.795W
01:42 PM
00:04
225
6.0
046
0.419



50 09.806N
001 02.046W
01:44 PM
00:06
325
6.0
050
0.604

Start turning the boat (preferably into tide) to make the yellow arrow point to the top of the screen



50 09.951N
001 02.143W
01:46 PM
00:05
355
6.0
065
0.578

Continue the turn


The MOB is 0.356 miles distant and you will arive in 3 minutes

50 10.136N
001 01.872W
01:49 PM
00:03
080
6.0
081
0.356

The MOB is now dead ahead (alligned with the red line)

150 metres (170 yards) over a 1 minute period. Look at the chart page to find the direction of drift.

Other Functions

There are many other functions available, so do read the user's manual for full details.

30°
3°W
30°
2°
30°
30°
50°N
50°N
Lyme Regis
Poole
Weymouth
Swanage
ISLE OF WIGHT
Bill of Portland
Anvil Pt
The Needles
ENGLISH CHANNEL
Cap de la Hague
Cap Levi
Carteret
Guernsey
CHANNEL ISLANDS

Passage Planning

Overview

Detailed Plan

Just Prior to Departure

Passage Planning – Procedure

Preplan

For the Planned Day of Departure

Passage Making

Passage Grid

Approach 'Spider's Web'

Compass Rose as a Waypoint

Unmarked Danger as a Waypoint

Clearing Bearing

You should have a plan for any passage you intend to make.

This plan can range from a quick look at the weather and tides for a short passage you've made many times before to a detailed written plan for a longer, open water one. The basic plan can be made well in advance, with only a check of the weather being required just before you start the passage.

The planning process has two stages. Firstly, you need to consider the broad picture – an 'overview', then you need to consider the plan in detail.

Overview

Look at the entire passage on a small-scale chart, preferably a chart that covers the complete route and consider the following:

- Are there any tidal constraints at departure, destination or port of refuge?
- Best route to make best use of tidal streams and available navigation aids.
- Large-scale charts for passage and possible alternative ports.
- Shipping lanes and traffic separation schemes.
- Sunrise and sunset times (light identification times).
- Charted depths which might give a progress check.
- Draft outline plan, note distance and likely passage time.


Lyme Regis
Poole
Weymouth
Swanage
ISLE OF WIGHT
Bill of Portland
Anvil Pt
The Needles
Saint Cat
ENGLISH CHANNEL
L.Channel
Hague
Cap Levi
Cherbourg
Pte. de B
Platte
Hanois
Guernsey
Carteret
CHANNEL ISLANDS
Lessay
Pt. Corbière
Coutances
Plateau des Minquiers
C-MAP

Overview

Tides and Tidal Streams

- Note the times and heights of HW and LW at departure and destination.
- Time of HW and range at reference point for tidal atlas and tidal diamonds.
- Identify limiting depths and fast streams causing tidal gates, correcting plan as necessary.



Tidal Gates:

Needles favourable June 30th 23:00 until July 1st 06:00

Alderney Race favourable July 1st 11:00 – 17:00

Guernsey June 1st 12:00 – 17:00

Marina open HW +/–3 hours 18:00 – 23:59

Tidal gates

Navigation Aids

- Visibility of lights. Coverage of local radio stations for forecasts. Area of coastguard coverage. VHF channels. Racons (buoy with a radar beacon).



Yarmouth to Needles	6.0 miles
Needles to Alderney race	61.0 miles
Alderney race to Guernsey	23.0 miles
Total Distance Yarmouth to Guernsey	90.0 miles
Planned cruising speed	6.0 knots
Estimated time en route	15.0 hours
Needles to start of Westbound traffic lane	26.0 miles
Needles to start of Eastbound traffic lane	38.0 miles

Alternative destinations:
Cherbourg, available at all states of tide and in all weather.

Alderney. Ok but must not be swept passed by tide.
Untennable in strong NE wind.

Outline plan


Tidal gate
Routing east of Alderney
Routing west of Alderney
Westbound shipping lane
Eastbound shipping lane
Visibility of lights at night
Tidal gate
Alternative destination
Tidal gate

Key to overview chart

Detailed Plan

At this stage you can investigate the plan in more detail and if there are strong tidal streams and tidal gates you will need to keep refining the plan as you home in on the best departure time – what's known as an iterative process.

I'll Outline My Way of Doing This

- Using the initial approximate time the trip will take, I juggle any tidal gates to come up with a departure time. This may entail compromise.
- Knowing the departure time, I need to see what the actual tides are on the way to get much more accurate route timings. I use the tidal atlas for the trip, having checked the time of high water used by the atlas for the departure date and a strip of paper on which I can mark the length of the route to the same scale as the tidal atlas. I mark along this route hourly marks for my estimated boat speed. This allows me to move from page to page of the atlas to estimate the tide at the point I expect to be at that time. Sounds complicated? It isn't, as a look at the diagrams will reveal.


Page from tidal atlas
0
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
Read closest tidal arrow to hour required
Scale of hours at 6 knots same scale as tidal atlas
seaPro
HW + 4
Depart Yarmouth at HW Dover + 2 hours

Tide at 2 hours from Yarmouth


Page from tidal atlas
0
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
seaPro
HW + 5

Tide at 3 hours from Yarmouth


Page from tidal atlas
0
1
2
3
4
5
6
7
8
9
10
11
12
13
14
15
16
seaPro
HW + 8

Tide at 6 hours from Yarmouth

- I make a table of the actual tides experienced for each hour along the route, as shown. I include more detail than absolutely necessary at this stage, but it saves work further along the process. Knowing the total distance to be covered is 90 miles, looking at the distance run column, I can see that the ETA at Guernsey will be a little after 16:00, say 16:10.

The method of working out course to steer is shown in Appendix B and Appendix D.

- I can now refine my original plan with more accurate timings.

1. Ideal departure time
2. Estimated arrival time
3. Pilotage for departure port, destination and possible ports of refuge.
4. Open sea passages: Tracks, distances and methods of navigation.
5. Dangers: Distance off to pass, clearing lines.
6. Shipping lanes: Cross at right angles?
7. Ports of refuge: Good shelter? Tidal or other restrictions.
8. Fuel: Gals/hour – passage time – reserve (20%)?
9. Watch system
10. Food

Just Prior to Departure

Check the weather.

Don't keep the plan a secret; discuss it fully with your crew so that they understand your intentions and have confidence in their skipper.

Passage Planning – Procedure

If you work your way through the following procedure, you'll have a plan.

Preplan

How far to go?
How fast will you travel?
How long will it take?
Look at tidal streams.
When should you start/finish to make best use of the tides?
Look at tidal heights.
Are there any tidal height/stream restrictions at departure, alternates or destination?
Do these modify start time?
If these times are incompatible, where can you wait?
Read all pilotage notes (almanac/pilot book).
Prepare pilotage plans.
Prepare route plan – plot on chart(s) – check all tracks and distances.
Load route into GPS/plotter – check all tracks and distances.
Plan catering.
Plan watch roster.

For the Planned Day of Departure

Times and heights of relevant high/low waters – springs or neaps?
Label tidal atlas.
Times of sunrise/sunset.

To steer a constant heading for the whole cross-channed leg (the most effiecient way) the course to steer is obtained from considering all the tides (see Appendix D). The course to steer and the planned ground track is shown here.



High Water Dover 00:20 BST

Hour	Tide		Tidal gain	Tidal loss	Ground speed	Running distance	ETA		
0	↖	2.2	1.5		7.5	0	02:00		
1	←	1.6	0.4		6.4	7.5	03:00		
2	←	1.8	0.5		6.5	13.9	04:00		
3	←	1.7	0.4		6.4	20.4	05:00		
4	←	1.8	0.5		6.5	26.8	06:00		
5	←	1.5	0.3		6.3	33.1	07:00		
6	→	0.8		0.2	5.8	39.4	08:00		
7	→	1.5		0.5	5.5	45.2	09:00		
8	→	2.5		1.0	5.0	50.7	10:00		
9	↗	3.1		1.3	4.7	55.7	11:00		
10	↗	2.2		1.5	4.5	60.4	12:00		
11	→	0.8	0		6.0	64.9	13:00		
12	↙	1.5	1.5		7.5	72.4	14:00		
13	↙	2.2	2.2		8.2	80.6	15:00		
14	↙	1.7	1.7		7.7	88.3	16:00		
15	↙	2.0	2.0		8.0	96.3	17:00		

Total Distance Yarmouth - Guernsey 90 miles
ETA Guernsey 16:10 approx.

En route tide - Yarmouth to Guernsey 1st July 2007

Passage Making

The easiest way to illustrate how to go about navigation, when applied to passage making is to have a look at a real trip. This is my method, and others may do things a bit differently, but I'll tell why I do things my way as we proceed from Salcombe in Devon to Poole Harbour in Dorset.



Yarmouth to Needles	6.0 miles
Needles to Alderney race	61.0 miles
Alderney race to Guernsey	23.0 miles
Total Distance Yarmouth to Guernsey	90.0 miles
Planned cruising speed	6.0 knots
Estimated time en route	15.0 hours
Needles to start of Westbound traffic lane	26.0 miles
Needles to start of Eastbound traffic lane	38.0 miles

Alternative destinations:
Cherbourg, available at all states of tide and in all weather.

Alderney, Ok but must not be swept passed by tide.
Untennable in strong NE wind.

Outline plan

Before We Start

This is a trip of over 100 miles, so at a cruising speed of around 6 knots, it'll take around 17 hours, so here, in the English Channel, where tides can be quite strong, we will have to endure going against the tide for some of the time. I use Seapro chart-plotting software which allows me to investigate the best time to leave, taking account of the tidal flow. Doing it manually, you'll need to take a look at the tidal atlas and decide the best time of departure to make best use of the tides. With a forecast wind of northerly force 4, I hope that we should cruise at about 6.2 knots and Seapro tells me a good time to leave Salcombe is 03:00 BST, taking around 16 hours and 40 minutes to Poole entrance.

Salcombe has a shallow sandbar in the entrance with a least depth of 1.1 metres, so it's worth checking what depth will be available at 03:00. Salcombe's tidal curve shows that the tide will be rising and there will be about 3.7 metres over the bar at 03:00.



01/06/2007
UTC 02:02:05
Height (m) 2.6 m
Depth (m) 3.7 m
Clearance (m) 1.7 m
Depth 1.1 (m)
Draft 2.0 (m)
Port SALCOMBE

Tidal curve for Salcombe 1st June 2007

Poole Harbour entrance is narrow and the tide runs very strongly, so I need to ensure that we get there on the flood. We'll be getting there a little before high water, so that's ok. If we're a bit late, there's a high water 'stand' and I'll have a good couple of hour's leeway. If I'm very late, I'll have to anchor outside, which with a forecast wind from the north is fine.

Checking the tidal atlas, I see that the tide outside Salcombe starts to run to the east just after we leave. It starts to run against us halfway across Lyme Bay, where the tides are weak turning favourable again around Portland Bill, giving us a fair tide all the way to Poole. This confirms that Seapro has come up with a good answer.



01/06/2007
UTC 16:36:17
Height (m) 0.9 m
Depth (m) 0.9 m
Clearance (m) -1.1 m
Depth 0.0 (m)
Draft 2.0 (m)
Port POTTERY PIER

Tidal curve for Poole 1st June 2007

Seapro also has given me the course to steer for each leg, their distances and bearings and the times. The method of



Moon rise 22:21 Moon set 05:26 (full moon)
Sunrise 05:05 Sunset 21:07

Depart Yarmouth	02:00
Needles	03:00
Start westbound shipping lane	07:30
Start eastbound shipping lane	08:00
Enter Alderney Race	13:00
Guernsey (St Peter Port)	17:00
Marina open	18:00
Marina closed	01:00

Skipper on watch	01:30 – 04:30
	07:30 – 09:00
	12:00 – 14:00
	15:00 – 18:00
Crew on watch	04:30 – 07:30
	09:00 – 12:00
	14:00 – 18:00

If strong wind against tide in Alderney race (3.0 knots)
Route via west of Alderney or change destination to
Alderney or Cherbourg

Final plan

doing this manually is given Appendix B. I can now draw the tracks on my navigation chart and check the distances and bearings. If I were entering this data manually into a GPS receiver, it's essential that I thoroughly check all the bearings and distances – rubbish in equals rubbish out. My system allows me to send the route directly from my laptop to my GPS, but I still need to check that it has been sent to the correct place.

On the Way

I don't mark the pages of my tidal atlases with the high water times. I have a card on which I can enter the times and heights based on HW time plus and minus half an hour, rather than HW time itself. This means that I can instantly see what page I should be looking at, just by reference to the clock and the card.


seaPro
Tidal atlas Salcombe 03:00 BST
seaPro
Tidal atlas Salcombe 04:00 BST
Tidal atlas Salcombe 05:00 BST
Tidal atlas 16:00 BST
Tidal atlas 17:00 BST
Tidal atlas 18:00 BST

We leave Salcombe using pilotage, rather than navigation (see Chapter 10), so apart from entering our departure in the log, I don't start my chart work until we reach waypoint number two. GPS is to be my main means of fixing our position, so I will be just plotting our GPS position on the chart every hour, with the occasional bearing to check the GPS. This way, should we loose our GPS or it becomes inaccurate, we will never be more than an hour away from the last reliable fix and it's from this position that I would start my 'traditional navigation' (see Appendix A). It often makes sense to base the time of the hourly fix on the changeover time of each page of the tidal atlas, rather than the 'top of the hour'. If I were travelling in a fast motor cruiser, I'd be plotting every half hour, but see below for the method. I check the distance run between each fix and compare this with the distance logged and the tidal flow to make sure it makes sense. If the logged distance is 6.5 miles and the tide is running at one knot with us, I would expect the two fixes to be about 7.5 miles apart.



WP	BRG (T)	DIST	CTS (M)	Leg time	ETA DEST	WP Position
0						
	187	2.8	192	0:29		
1					03:29	50 11.21 N 03 46.24 W
	117	2.1	121	0:19		
2					03:49	50 10.26 N 3 43.38 W
	072	67.7	074	10:26		
3					14:15	50 31.70 N 02 02.75 W
	055	4.8	064	1:10		
4					15:26	50 34.46 N 01 56.52 W
	025	3.9	034	0:48		
5					16:14	50 37.97 N 01 54.00 W
	331	2.6	333	0:25		
6					16:39	50 40.24 N 01 56.02 W

Passage plan



TIDAL ATLAS PORT HW time HW ht Date

-6	-5	-4	-3	-2	-1	HW	+1	+2	+3	+4	+5	+6

Atlas page change over times

LOCAL PORT HW time HW ht LW ht

-6	-5	-4	-3	-2	-1	HW	+1	+2	+3	+4	+5	+6

Atlas page change over times

Sp. Range Today's Range Np. Range

Tidal atlas times

At displacement boat speeds, it pays to plan to steer one continuous heading allowing for the tide along the complete leg, to use the tide to best advantage (see Appendix D). Seapro draws the planned track over the seabed for me so that I can monitor our progress. I show how to do this manually in Appendix D. Provided that we are keeping reasonably close to our planned ground track with no large errors induced by tide and speed different from planned or compass error, I don't alter heading until the halfway point, provided that it's safe to do so. At that stage, I alter heading to get me back on track at the next waypoint. I do this again at



Date 1st June 2007 From SALCOMBE TO POOLE AT POOLE

Time BST	Course Ordered (C)	Log Distance	Estimated Course Steered	Estimated Dist Run	Estimated Leeway	Wind	Sea	Weather	Vis	Baro	Position	Source of fix	Next WP	Remarks
03:00											Salcombe			Slipped mooring – Pilotage to Prawle Point ETA Poole entrance 16:40
03:45	075	4.8				W4	Sl	F	Good	1022	WP 2 2nl S Prawle point	GPS	3	Set course 076 M ETA WP 3 14:15
04:45	075	10.8	075	5.0	0	NW4	Sl	F	Good	1022	50 12.0 N 03 39.16 W	GPS	3	Autopilot holding heading well
05:45	075	17.1	075	6.3	0	NW4	Sl	F	Good	1023	50 14.33 N 03 24.81 W	GPS	3	Start Pt light 268M Good compass check
06:45	075	23.6	075	6.5	0	N4	Sl	F	Mod	1023	50 17.58 N 03 14.24 W	GPS	3	Tide setting us North as expected
07:45	075	30.2	075	6.6	0	N4	Sl	F	Poor	1023	50 20.44 N 03 04.16 W	GPS	3	Fog patches – sea temp 14.3C Radar on
08:45	075	36.7	075	6.5	0	N4	Sl	F	Mod	1023	50 24.32 N 02 54.11 W	GPS	3	About a knot of tide under us, expect to be set south now ETA WP 3 at 14:30
09:45	075	43.3	075	6.6	0	NW4	Sl	F	Good	1024	50 25.44 N 02 43.1 W	GPS	3	Starting to close track, nice and sunny now
10:45	075	49.4	075	6.1	0	NW4	Sl	F	Good	1024	50 26.38 N 02 32.48 W	GPS	3	Portland light 042M
11:45	075	55.9	075	6.5	0	N4	Sl	F	Good	1024	50 27.12 N 02 24.96 W	GPS	3	Portland light 347M ETA WP 3 14:45, Tide running stronger than expected.
12:45	070	64.5	070	6.6	5	NE4	Sl	F	Good	1024	50 28.07 N 02 17.63 W	GPS	3	Portland light 300M
13:45	070	71.2	070	6.7	5	NE4	Sl	F	Good	1025	50 29.55 N 02 10.85 W	GPS	3	ETA WP3 14:45 ETA Poole ent 17:10
14:45	075	77.8	075	6.6	0	NW4	Sl	F	Good	1025	Way point 3	GPS	4	Alter course 060C for WP4
16:00	065	84.0	065	6.2	0	NW4	Sl	F	Good	1024	Way point 4	GPS	5	Alter course 035C for WP 5
16:50	065	90.3	065	6.3	0	NW4	Sl	F	Good	1024	Way point 5	GPS	6	Alter course 335C for WP 6 – Poole ent
17:15	335	96.3	065	6.0		NW3	Sl	F	Good	1024	Poole Entrance	Vis		Sails down and motored in last leg – Super sail
17:45		101.2									Off Pottery Pier			At anchor in 3.4 metres.

Passage log

half the remaining distance, repeating this every time I halve the distance. As you can see, on this passage, I altered heading only when we started to make leeway as the wind headed us. Although we got 3 miles north of the direct track, we stayed pretty well on our planned ground track.

If you are in a sailing boat, tacking against the wind, tack so that you stay either side of the planned ground track. On an open water passage such as this, it saves navigation effort if you tack on each hourly fix until you get closer to your destination, provided that it's safe to do so and the wind doesn't change direction unfavourably. See Appendix A for the procedure.



Planned ground track



Passage plot

Alternative to Plotting Latitude and Longitude

Plotting latitude and longitude on a small boat at sea is not everyone's 'cup of tea'. There are alternative methods that require more chart work before you start, but simplify the navigator's work on passage. These alternative methods are the only way that you can do any form of chart work on a fast moving boat because of its motion. On a fast motorboat, or any boat in rough seas, thorough planning for all eventualities is a must, as you may not be able to do the paper work on the way.

Note

Some of these methods involve entering coordinates into your GPS which don't form part of a route, so you have no method of cross-checking their accuracy. Do double-check their coordinates and try to check their bearing and direction from a known point, before you use them.

Passage Grid

The passage from Salcombe to Poole, outlined above, could have been made using a passage grid. The GPS set will give the distance to the next waypoint and the cross-track error, provided that the route is active. Using the grid, you can plot your fix by eye using the cross-track error and distance to go. This method is very quick and as accurate as you require.



Passage grid

Approach 'Spider's Web'

If you are approaching your destination, you can use an approach spider's web. The closer you get to your destination, the more accurate it is, which is just what you need. This method uses the bearing and distance to your waypoint – just ensure that the GPS bearing and the grid use the same units, either magnetic or true.



Spider's web grid



Tacking towards a waypoint

The spider's web is also very good if you are tacking towards your destination, giving shorter tacks as you get nearer.

Compass Rose as a Waypoint

You can avoid a lot of chart preparation by inserting a compass rose as one of your waypoints. You don't actually intend going to it, so you mustn't attempt to navigate towards it. The GPS gives bearing and distance to an active waypoint, so all you need to do is place a position line through the centre of the waypoint (in this case the compass rose), aligning it with the 'far side' as it's a direction towards, and then mark off the distance along the position line from the centre of the compass rose. You now have your fix – again pretty quick and accurate, as long as you use the correct direction, either true or magnetic for both the GPS and the compass rose.


WP 1
WP 2
WP 3
C-MAP
Direction towards waypoint is on far side of compass rose
Waypoint at centre of compass rose
Fix
WP 2
ENGLISH

Waypoint at centre of Compass Rose

Unmarked Danger as a Waypoint

If you are worried about going too close to an unmarked danger, such as a dangerous rock, you can put a waypoint at the danger itself. Your GPS will then give you the distance and bearing to the danger so that it can be safely avoided.



GPS gives distance and bearing (1.36 miles, 320 degrees) to unmarked dangerous rock. 'Pierre au Vraic' allowing it to be safely avoided.

Waypoint at unmarked danger

Clearing Bearing

Another way of avoiding an unmarked danger is to use a clearing bearing. In this case I have drawn a line from the next waypoint (which is now active) towards the danger but giving a safe distance off. This is known as a clearing bearing and in this instance is 030 degrees. Provided that we don't allow the boat to stray too far to the west so that the bearing to the waypoint doesn't exceed 030 degrees, we will be safe. Again, make sure that both the bearing and the GPS are given in either magnetic or true.



Clearing bearing


30°
3°W
30°
2°
30°
30°
IALA 'A'
Preferred Channel to Port
Isolated danger
Port hand Marks
South Cardinal
Safe Water
Starboard hand Marks
North Cardinal
Preferred Channel to Starboard
Direction of buoyage
IALA 'B'
Preferred Channel to Port
Isolated danger
Port hand Marks
South Cardinal
Safe Water
Starboard hand Marks
North Cardinal
Preferred Channel to Starboard
Direction of buoyage
50°N
50°N
30°
3°W
30°
2°

Pilotage

Who Does the Piloting?

Means of Pilotage

International System of Buoyage

Planning

The Basics of Preparing a Pilot Plan

Making a Pilotage Plan

Working as a Team

Whereas *navigation* implies that you are fixing your position by plotting on a chart, *pilotage* means that you are controlling your boat so that it follows a prescribed safe path by visual means. This doesn't mean that you can't use electronic aids, but as we have seen, these can sometimes be highly inaccurate, and often pilotage requires us to position our boat accurately to within 10 to 20 metres.

Pilotage occurs at each end of a passage, so pilotage plans need to be included in your passage planning.

The basic aids to pilotage are the human eye, the hand-bearing compass and a properly calibrated depth sounder, speed log, steering compass and a plan. Electronic aids can add to your armoury.

Who Does the Piloting?

Ideally, the pilot should not have any other duties. You often see the skipper of a leisure boat helming and piloting as well. This isn't desirable. If you haven't sufficient crew, use the autopilot if you have one when pilotage is demanding.

Means of Pilotage

Day or Night?

It would seem obvious that night is different from day! However, there is a fundamental difference that becomes apparent only when you are looking for a lighthouse or lit navigation aid. A flashing light is visible only when the light is 'on'. As the majority of marine lights have a short flash and a long period of darkness, it's likely the light will be visible for only about 10% of the time – for 90% of the time it will be invisible!

Unlit aids to navigation will not be visible at all, so only lit transits are of any use at night. Whereas busy commercial ports lend themselves to easy pilotage at night, estuaries and havens used mostly by leisure sailors may be difficult or impossible to enter at night.

International System of Buoyage

The International Association of Lighthouse Authorities (IALA) has standardised the system of buoyage used internationally. Owing to a small disagreement, there are two systems as follows:

IALA System A (IALA-A), used throughout most of the world;

IALA System B (IALA-B), used in the United States of America and those countries which have a close association with the United States of America.

The difference is the colour of the lateral buoys – those marking the edges of a channel:


IALA System A
Starboard hand marks
If lit:
Lights any rythm except Fl(2+1)G
Port hand marks
If lit:
Lights any rythm except Fl(2+1)R
IALA System B
Starboard hand marks
If lit:
Lights any rythm except Fl(2+1)R
Port hand marks
If lit:
Lights any rythm except Fl(2+1)G
Timing

Rythm: Fl = Flashing
The number is the number of flashes
So: Fl (2)G 5s = two green flashes every 5 seconds
If no colour is given, colour is white.

IALA lateral buoyage

IALA System A has the *green* buoys on the starboard (right hand) side of the channel when entering a port, whereas IALA System B has the *red* buoys on the starboard side of the channel when entering a port. For those used to IALA System A, remembering the rhyme 'Red Right Returning' when in IALA System B waters is useful.

Where a channel splits into two, both navigable, but where it is preferable to use one, a preferred channel buoy is used. The main body of the buoy is coloured as if it were in the preferred channel, whilst the colour of the band tells you which way to turn.

The chart will show the 'general direction of buoyage' where there is any doubt.


IALA System A
Bifurcation marks
Preferred chanel to Port
If lit:
Fl(2 + 1)G
Preferred chanel to Starboard
If lit:
Fl(2 + 1)R
IALA System B
Bifurcation marks
Preferred chanel to Port
If lit:
Fl(2 + 1)R
Preferred chanel to Starboard
If lit:
Fl(2 + 1)G

IALA lateral buoyage


IALA System A
IALA System B

General direction of buoyage

It's essential for the pilot to understand that when proceeding in the direction of buoyage, the starboard hand buoys are passed on the starboard side of the boat, that is leave the green buoys to starboard for IALA-A and leave the red buoys to starboard for IALA-B. When proceeding in the opposite direction, the red buoys are left to starboard (IALA-A) and the green buoys are left to starboard (IALA-B). This applies to the preferred channel marks as well. This means that when travelling in the opposite direction, the preferred channel to starboard buoy means 'turn left'.

Aground, the wrong side of the marker

Some people find this concept difficult. Having pulled a boat off a mud bank when the skipper had tried to pass a channel buoy on the wrong side, he continued down river still trying to pass the buoys on the incorrect side. He obviously found it difficult to comprehend the reversal of the colours.


N
W
E
S
North Cardinal
safe water to
the NORTH of
the hazard
West Cardinal
safe water to
the WEST of
the hazard
Hazard
East Cardina
safe water to
the EAST of
the hazard
South Cardinal
safe water to
the SOUTH of
the hazard

Cardinal buoyage system IALA "A" & "B"

International Buoyage – All Areas

The rest of the international system of buoyage is the same in all areas.

Cardinal Buoyage System

This consists of four different buoys that may be placed to the North, East, South or West of a danger. They have differing top-marks, colours and light sequences.


Both points UP
If lit:
Contiuous quick flashes
Points 'EGG' shaped
If lit:
Three quick flashes
Both points DOWN
If lit:
Six quick flashes plus one long flash
Points 'WAIST' shaped
If lit:
Nine quick flashes
The BLACK areas are where the points are 'pointing to'
Timing of sequence
Flashes may be 'quick' or 'very quick'
(60 or 90 flashes per second)
Timing may be 5, 10 or 15 seconds
White light

Cardinal buoyage system IALA "A" & "B"

In order to use the cardinal system reference must be made to a compass.

Safe Water Mark

Indicates 'safe water' and often used at the start of a channel as an 'aiming point'.


Top mark, if fitted, RED ball
If lit:
Iso, or
Oc, or
LFl.10s or
Mo(A)
White light
What this means is
much more light than
is usual for a buoy

IALA safe water mark (the fairway buoy)

Isolated Danger Mark

Placed on, or very close to, an isolated danger. Don't get too close to these as the danger may extend well from the mark, so have a look at the chart. This is the only buoy with a light characteristic of 'flashing 2 white'


Top mark – Two BLACK balls
If lit:
White light
This is the *only* Fl(2) anywhere
If you see this - keep clear

IALA isolated danger mark

Special Mark

These are non-navigational in nature and are used as yacht racing marks, to show the boundaries of danger areas and to indicate water skiing areas etc.

If lit, the lights are yellow


Top mark, if fitted, a yellow cross
If lit:
Fl. Y
Yellow light

IALA 'Special' marks

Emergency Wreck Marking Buoy

Introduce in 2007, these buoys can be quickly placed around a new wreck prior to normal buoys being laid if required. Where several buoys are used to mark the same wreck, the flashing lights are synchronised.

These diagrams show how the IALA buoys may be used.



Emergency wreck-marking buoy

Narrow Channel Marked by Buoys or Beacons at Frequent Intervals

This is the easiest form of pilotage; just keep in the channel. At night, it's desirable to have a list of directions and distances between each buoy.


Note!
Many of these markers are dry at low water
If the channel curves, steer the boat round a curve as well, especially on the inside of a bend. If you go in staight lines between the marks you may run aground.

Don't cut corners



Narrow channel, IALA B, with depths in feet and NOAA chart symbols.

Just follow the buoys

In a curved channel, the channel will curve between individual buoys or beacons, so if you follow a straight line between buoys, you may run into shallows, which curve between them. You need to allow for this curvature.

In a very narrow channel, the buoys, or especially any beacons, may be in water too shallow for your boat at low water, so don't get too close to them. You have to balance this with the requirement to keep as far to the starboard of the channel as safely possible (Colregs Rule 9a)

Channel Marked by Buoys or Beacons Some Distance Apart

In this type of channel, you definitely need to have a list of directions and distances between buoys. At night or in poor visibility, you may depart one buoy and may not see the next for some time. You can easily lose your sense of direction, especially if there's a cross-tide, so use the hand-bearing compass when looking for the next buoy.

The reason for the marker is obvious

The channel markers are there for a purpose

Channels Marked by Transits

As outlined in Chapter 8, transits are the most accurate form of position line. Harbour authorities often install transits, lit or unlit, to mark the centreline of their channels. If you



Using a transit



Multiple lit transits in the shallow Chesapeake bay allow accurate alignment in the channels without recourse to too many buoys.

Transits lit by high intensity directional lights

haven't used a particular transit before, check the bearing to make sure it's the correct one and remember that the charted bearing is in degrees true.

Transits designed specifically for ships with high bridges may give false information to leisure craft. At Hamble BP Oil terminal there are transits to guide the tankers onto the berth. Although the back transit is higher than the front, as it should be, from the cockpit of a small boat the front appears higher, so you could easily turn in the wrong direction to keep the lights in line!



Very tall transit towers give impression that the front light is higher than the back light from the cockpit of a small boat

Tall transit towers



A series of seven tightly sectored red, green and white lights guide the pilot into Devonport Harbour, reducing the number of channel markers required in the deep-water channel.

Sectored lights

In place of transits some channels are marked by sectored lights, some to avoid dangers outside the channel and some so narrow and directionally accurate that you can use them to stay in the correct side of the channel!

No Formal Aids to Pilotage

If there's no charted marks, transits, etc., then you have to make up your own. You have basically four choices:

- Try and find charted features that can be aligned to give a safe transit. With natural transits you need to be aware that buildings may have been demolished or had something built in front of them. Even natural transits in pilot books may have been painted in a different colour, trees may have grown or been chopped down. You always need a fallback.
- Mark bearings on your chart from easily visible landmarks, natural or man-made, and use a hand-bearing compass to stay on the bearing.


Bearing on church tower 039 M
Bearing on church tower 013 M
C-MAP


Church tower
seaPro

Initial approach to river Yealm


C-MAP
074M
0.75NM
059M
1.2NM
070M
1.95NM
092M
0.53NM

It will be difficult to find your way along this channel in poor visibility or at night, so note the directions and distances

Channel with few buoys


Headlands in line 069 M
C-MAP

A natural transit of the two headlands in line on 069 degrees magnetic. In case you can't define the actual headlands, you'll need a fallback plan.

A natural transit


Natural transit from Church tower through breakwater lighthouse
seaPro
Off transit – steer to port
On transit
Off transit – steer to starboard

Choosing your own **'natural'** transit

- Mark bearings on your chart that will keep you clear of hazards. These are known as clearing bearings.
- Use your calibrated depth sounder to follow depth contours.


Bearing on church tower 039 M
Bearing on church tower 013 M
C-MAP

If you approach from outside the 20 **metres depth contour** keeping the bearing of the church tower not more than 039 degrees M and not less than 013 degrees M you will have a safe passage, provided you don't go north of the inbound transit into the River Yealm

Clearing bearings


Heading 222M(3 miles)
30 minutes at 6 knots
Heading 298M
(1 mile)
10 minutes
Zig-zag about 180M(0.7 miles)
7 minutes
C-MAP

To find the entrance to Helford river from Falmouth in misty conditions, you could make a course to the north of the entrance turning South when you get to the 5 metres contour as indicated by your calibrated depth sounder.
Zig-zag along the contour until you get to deep channel and then turn onto the inbound heading.

Using a depth contour

Planning

Pilotage requires planning. If you've been there before, the plan may be in your head, but it has been planned. Your old plan will need to be updated for the weather and tide on the day.

Just like passage planning, of which this becomes part, start off with an overview and assemble the tools you will need, such as large- and small-scale charts, almanac and pilotage notes.

The Basics of Preparing a Pilot Plan

- Pilotage is visual navigation
- Pilotage needs to be planned
- Use large-scale charts
- Check dangers
- Check special rules
- Check VHF channels

Aids to Pilotage:

- Pilot book
- Tidal atlas
- A pilotage plan
- Hand-bearing compass
- Binoculars
- Log distance
- Depth
- GPS – course over ground
- Stop watch
- Radar

Methods:

- Clearing bearings
- Charted transits
- Natural transits

- Sailing along contours
- Course to steer
- Distance/time run
- Recognition of buoys/lights
- Pilot 'pilots' – helmsman steers

Making a Pilotage Plan

To make this exercise more realistic, we'll make a pilotage plan from Plymouth breakwater to the river Yealm on 1st August 2007. In making the plan, you will also be 'rehearsing' how you will conduct the passage.



Overview of pilotage plan from Plymouth breakwater to river Yealm



Plymouth breakwater

- Firstly, put the general route onto the chart. Choose a scale so that you can get the complete passage on one chart and then measure distances and bearings. I list the bearings in degrees magnetic as all my direction instruments at the helm also use degrees magnetic.
- Now, if necessary on a smaller scale chart, look at how you can pilot the first leg. At Duke Rock east cardinal buoy you can check your depth sounder, which should read 6 metres plus the rise of tide. The compass can be checked for gross error as you head for the eastern end of the breakwater, as there should be little cross-tide here. If you have GPS, the COG should be monitored at all times to help ensure that you are achieving the desired tracks.



Pilotage for first part of passage

- Continue on this heading until you reach the East Tinker cardinal buoy. Maintain the heading of 185M until you see the East Tinker cardinal behind you aligned with the Breakwater fort. Now turn onto 160 magnetic and adjust heading to keep the East Tinker in transit with the Breakwater fort (back bearing of 340M) until you reach the 20-metre depth contour. Continue for 0.15 mile (1.5 minutes at 6 knots) and then turn onto 095M.

- Continue eastwards to make good a ground track of 095M, allowing for any tide. Your GPS, set to display COG will help to ensure you keep on track. Ensure that the depth remains at 20 metres or more so that you keep well clear of the drying rock to the south of the Great Mew Stone. As you clear the Great Mew Stone, start looking for the church tower. Looking on about 055M with your hand-held compass will help you find it. You can start your approach to the Yealm once the bearing of the church tower is 039M or less. Ensure that the bearing does not reduce below 019M in order to avoid all obstacles.
- Now start looking eastwards watching for Misery Point to become visible beyond Mouthstone Point. You should soon see the transit beacons well up the wooded slope above Cellar Bay. Once these are in transit turn onto 093M and keep them lined up.
- As you approach the two red buoys (April–October) you will have to 'jiggle' south and leave them to port. Start looking for a red and white marker post high on the north bank. If you steer to keep that on a bearing of 050M, you'll keep in the deepest water while crossing the inner bar.


Bearing on church tower 039 M
Bearing on church tower 019 M
YEALM HEAD
C-MAP


Church tower
seaPro

Initial approach to river Yealm


Transit beacons above Cellar Bay
YEALM HEAD
C-MAP

Transit into Yealm entrance


Bearing 050M for deepest water
NEWTON FERRERS
C-MAP

Entering the Yealm, avoiding the bar

- You are now in the river, but your plan doesn't end until you are where you intend to moor. I've had many students, who having entered the harbour have no idea which way to go or even what they are looking for!
- Some harbours (though not the Yealm) have a Port Signal Station that shows a series of 'traffic' lights controlling your progress. Ensure you know what these lights mean.


C-MAP
Bar Pt
Season Pt
Red Cove
RIVER YEALM
Misery Pt
The Sand Bar
Cellar Bay
Small Craft Moorings
Warren Pt
Yealm Pool
Yealm Hotel

The river Yealm

The Paper Plan to Use in the Cockpit

There are a number of methods of writing your notes. What is essential is that pilotage is done from the cockpit. This is not the time when you want to be at the chart table. Your notes need to be simple, concise and clear.

- If you are good at sketching, draw a sketch map with all the details on it.
- The other method is a 'strip' plan.


Fort
Breakwater
Back bearing
340M
185M
0.86 miles
8.6 minutes
E Tinker
160M
1.1 miles
11 minutes
Church tower
Great Mew Stone
050M
0.7 miles
7 minutes
20 metre depth
095M
1.08 miles
10.8 minutes
1.5 minutes after 20 metres
Not less than 013M
Transit beacons
Not more than 039M
transit 093M
Almost slack @16:00
No VHF at Yealm
No anchoring in Yealm
HW Yealm 08:00/5.1m
LW Yealm 14:20/0.7m
<1.0m under keel
12:45 - 16:00
Aug 1st 2007
Crossing bar
050M
Jiggle south of red buoys

Sketch pilot plan


Pilotage Plan
River Yealm
Red can buoy
Red can buoy
Jiggle starboard
Transit 093M
NLT 013M
Church Tower brg
NMT 093M
20 m contour
20 m contour
Back transit
320M on Fort
E Tinker
Breakwater
Duke Rock

Time	Bearing (track) Mag	Dist. (nM)
2 min	050	0.2
1 min		0.1
6 min	093	0.6
7 min	050	0.7
10.8 min	095	1.08
1.5 min	160	0.15
11 min	160	1.1
1 min	185	0.1
8.6 min	185	0.86
4 min	185	0.4

Strip pilotage plan

- The problem with using a 'proper' chart is that there's just too much detail, although you can put one inside a transparent chart folder and use a wax pencil to draw on the plastic. This also keeps the chart dry and prevents it blowing overboard.

Working as a Team

The pilot needs to ensure that the helmsman understands what is intended, so brief him properly. If you are both pilot and helmsman, use the autopilot if you have one. When in pilotage waters in a sailing boat, consider motoring instead of sailing, especially if you are short handed and in unfamiliar waters.



Initial transit alignment



The buoy has moved to starboard - turn to starboard



The buoy has moved to port - turn to port

Keep the buoy aligned with something in the background

- If the next course is towards a buoy or marker, make sure that it's identified properly. Pointing in its general direction won't do, especially as you will be looking at it from a different perspective. Note a feature on the horizon, say a tree, and relate the position of the buoy with the tree – 'It's three hand width's to the left of that tree sticking above all the others'. If there's no feature, stand behind the helmsman and point to it with your outstretched arm over his shoulder, to give the same perspective.
- At night, this is even more important, as most of the time the buoy will be invisible! Firstly, the pilot needs to identify it himself. Before you get to the end of this leg, use the hand-bearing compass on the expected bearing to find the light defining the next leg and then identify its light sequence. Now point over the helmsman's shoulder towards the buoy and as the light flashes 'announce' each flash 'Flash-Flash-Flash' in time with the light. This will ensure that the helmsman is 'seeing' the same light as you are.
- If there's a cross-tide, asking the helmsman to 'steer for that buoy' is a recipe for disaster. Tell the helmsman which way the tide is flowing. If it's from port to starboard, tell him that he needs to aim 'off to port' and 'keep the buoy on the starboard bow'. If there's an object on the horizon above the buoy – that tree again – tell him to keep the tree and the buoy in transit and explain what you mean if necessary. 'If the buoy moves to port, you must steer to port to bring them back into line' and vice-versa. If there's nothing to use as a transit, ahead or astern, give him a course to steer allowing for the tide, or use the GPS COG as an aid.
- At night, if you're on a transit, help the helmsman, as he will be steering a course.

- If you're on a 'back transit', that is the transit is behind you, remember that the course corrections are the same – if the nearer object moves to port, then you steer to port. Don't use the terms left and right as these are reversed when you look behind you.
- If you are keeping on a bearing to an object, or a clearing bearing, the helmsman should be given a course to steer. You should monitor the bearing as often as necessary and give the helmsman course corrections 'come 5 degrees port onto 045'.
- Once you know that the helmsman is established on the current leg of the passage, monitor him loosely, but start looking for the next object. If you're looking for an object – a tower, say– then identify it in good time, using your hand-bearing compass and binoculars if necessary.
- If you can't find the next object, check your time and distance run since the last. Don't run blindly on into dangerous waters in the hope of seeing it. Either the tide is a lot different to what you assumed or you have made an error in measuring the distance or bearing. On many occasions when teaching pilotage, the lost buoy is just off to one side, but the student navigator has been concentrating on just looking ahead. If the helmsman or other crew members are all 'in the picture' they are likely to have spotted it.


Tide
Heading towards the buoy
Still heading towards the buoy
Still heading towards the buoy and now aground

Just keep heading towards the buoy

30°
3°W
30°
2°
30°
30°
50°N
50°N
STANDARD HORIZON
SIMULATION
FIX > CURSOR
50°36.390N
000°48.402W
SOG 6.0 Kts
COG 063° M
DST 2.886 Nm
BRG 053° M
GPS Chart 1000 C

Automatic Identification System

What is Automatic Identification System?

How Does AIS Work?

Class A AIS

Class B AIS

AIS Displays

The AIS Display on a Chartplotter

AIS Class B Transceiver

What is Automatic Identification System?

Automatic identification system (AIS) allows a transmitter on a ship to broadcast information about the course, speed and position, etc. (dynamic data – navigation information) and also destination, type, MMSI and name, etc. (static information) of the vessel. Receivers on other ships and shore stations can display this information as an aid to collision avoidance, traffic control or national security. The system is compulsory for vessels of 300 tonnes or more and the experience gained over the last couple of years has been very positive, although there are problems that are discussed below.

How Does AIS Work?

Each minute of time is divided into 2250 discrete `time stamped' slots in each of two VHF, line of sight `channels'. A set will listen for other transmissions to find a vacant slot and then `reserves' this slot for its own regular transmissions. If all the slots are busy, it looks for a much weaker signal (indicating a greater range) and takes this slot. This is known as `self-organising'. In very busy areas, the range at which contacts can be seen slowly deteriorates.

Class A AIS

This is the compulsory system fitted by commercial shipping worldwide. It transmits a great deal of data, much of which, such as destination etc., is entered manually by the bridge crew and the rest, such as GPS position, is wired directly from the ship's equipment. The heading information from the compass system has often been found unreliable, as has the data that has been manually entered.

The dynamic information is updated every 10 seconds for vessels up to 14 knots and every 2 seconds for vessels travelling at more than 23 knots and the transmitting power is 12.5 watts.

Class B AIS

AI3000 - Automatic Identification System
ON
Channel
1 2
AIS Receiver
EURONAV

This is a simpler and cheaper system designed for `voluntary fit' vessels and transmits at only 1 or 2 watts. It has a built-in GPS and the `dynamic' data consists of only position, COG and SOG, although heading may be added. Data is transmitted at only 30-second intervals and the set cannot reserve slots ahead. Instead, it has to listen for an unused slot, or a slot with a much weaker signal, on 10 randomly selected slots over a 10-second period. If no slot is available, it cannot transmit and must wait a further 30 seconds and try again. A class B set may thus not be able to transmit regularly even when there are many empty slots as the randomly selected slots may be full.

AIS Displays

On the leisure market there are two types of display available. Ideally the AIS receiver is connected to a chartplotter (or pc plotter) and the `target' information is displayed in the form of a `ship icon' together with its course and speed and whether it is a danger. You can see all the other data if required. All targets in range will be displayed on the screen in a dynamic way. The other alternative is to have a dedicated display, such as that from NASA, where up to 30 targets are shown on a circular `plan position indicator' (PPI) although no indication of your own course is shown on the north-up display.


Cursor
Distance and bearing of the cursor from your boat
STANDARD HORIZON
Your boat
AIS targets

AIS display on chartplotter


A.I.S Radar
2nm
North
Range 14nm
MMSI:
232162123
NASA
EXPLORER
Lat: North
51°31.271
Long: East
8°36.237
Under way
SOG: 12kts
COG: 307°
MODE
HOME
PREV.
NEXT

Most merchant ships have a far less sophisticated navigation display than many leisure craft. Only the very newly built ships have large colour radar screens, electronic chart displays and few have the AIS information co-located on the radar or chartplotter. Most show their AIS data on a very simplified display. This is required to display the data of only three vessels at any one time, showing the distance bearing and name of the vessels although many do have the ability to show more or have a simple PPI. Often, because of the limitations of older bridge design, the AIS data is not within easy view of the Officer of the Watch.

All new builds from July 2008 will have to have an integrated AIS display, but this will not be retrospective.

The AIS Display on a Chartplotter

When the chartplotter is supplied with data from an AIS receiver, all AIS equipped ships within range will be displayed on the chartplotter screen. These ships will be shown as a triangle with a line projected in front of it representing the ship's COG. If you `hover' the screen's cursor over the triangle, more information will be displayed, consisting of at least

- the name of the ship,
- the ship's MMSI,
- the ship's international call-sign,
- the ship's COG,
- the ship's SOG,
- the CPA (closest point of approach),
- the TCPA (time to CPA).

When the cursor is 'hovered' over target, a 'pop-up' box will appear. The target is 2.839 miles from us and the CPA is only 0.64 mile, which is uncomfortably close with all the 'sea-room' available.

AIS target information box

The distance and bearing of the cursor from your boat will be given on the screen so if the cursor is on the target ship you will have its range and bearing.

What the Display Tells You

Looking at the basic chartplotter display, it's difficult to know if any target will pass ahead, collide or pass astern of you. You could resolve the situation graphically, but the AIS computer will do the sums for you. If the transmission from the target contains errors, then a false CPA and TCPA may be displayed.

As far as collision avoidance is concerned, the important information is CPA and TCPA, displayed in the AIS information box. From this you can judge what action, if any, you should take. It's worth stating here that your actions are dictated by the International Regulations for Prevention of Collisions at Sea (Colregs).



This in not where you will meet, as this depends on the speed of each boat.

With only this information the target could pass ahead, collide with you or pass astern.

In this instance, the faster ship will pass ahead of you.

Basic AIS display

The action to be taken differs if you can or can't see the target visually, but as the rules were written long before AIS was conceived, it's unclear if rule 19 applies to vessels seen only by `AIS' rather than `only by radar'.

Normally, you can enter a value of CPA at which you would be uncomfortable. If a target is predicted to get this close (or closer) to you, the triangle will blink on and off and you'll get an audible alarm.

A receiver-only AIS on *your* boat will allow you to monitor commercial shipping as an aid to making collision avoidance decisions. Because of some unreliability of data, especially heading, it must not be taken as an absolute indication of the situation, but in conjunction with radar, it is an exceptionally good situational awareness tool.

Advantages of AIS

- It can see around corners, such as headlands or bends, unlike radar, which can't.
- It can give you the name and MMSI of a ship which you may wish to call.
- It can give you the closest point of approach of the target vessel.



NAME	SIMUL8
MMSI	100000028
CALL SIGN	SIMUL8
SOG	1.7 Kts
COG	086° T
CPA	0.04 Nm
TCPA	00:00:00

The AIS information box

Saga Rose is at anchor, but AIS indicates that she is under way using engine



	Vessel Class A
Name:	SAGA ROSE
MMSI:	308264000
IMO:	6416043
Call Sign:	[illegible]
Status:	Under way using engine
ROT:	0 °/min
SOG:	0.10kts
COG:	302.00 °
Position:	50 10.170N 5 2.290W
Pos accu:	>10m
Hdg:	212 T
ETA:	07:00 10/07
Dest:	FALMOUTH
Draught:	8.5 m
Type:	Passenger ship All ships o
Dim (l x w) m:	190 x 10 (50 140 10 0)
EPFD:	GPS
UTC reports:	3 s
RAIM:	Not in use
AIS Ver:	0
Age:	00:04

	Vessel Class A
Name:	WHITSTAR
MMSI:	232003407
IMO:	6828820
Call Sign:	[illegible]
Status:	Moored
ROT:	-12 °/min
SOG:	6.30kts
COG:	190.20 °
Position:	50 10.019N 5 2.311W
Pos accu:	>10m
ETA:	12:00 11/06
Dest:	FALMOUTH
Draught:	4.0 m
Type:	Tanker No additional Info
EPFD:	GPS
UTC reports:	55 s
RAIM:	Not in use
AIS Ver:	0
Age:	00:09

Whitstar, which has just refuelled Saga Rose, is under way using engine, but her AIS indicates that she is still moored.

Erroneous AIS indications

Disadvantages of AIS

- Only commercial vessels bigger than 300 GRT are required to fit it – you can see only vessels which have it fitted.
- It can transmit erroneous information.

AIS Class B Transceiver

If we fit a class B AIS transceiver (transmitter/receiver) we must be aware of its limitations:

- There is absolutely no guarantee that any commercial vessel will see our class B transmissions, either because of lack of output power, because our set cannot find a free slot or because of deficiencies of their AIS display. Even if they can `see’ us, with only 30-second updating at best, our intentions may not be clear.

- A recent paper by Andy Norris in the Journal of Navigation published by the Royal Institute of Navigation summed it up thus: *Any confidence that the potential user of class B equipment has in expecting own-vessel’s presence to be highlighted to all surrounding SOLAS vessels is misplaced.*
- If we wish to maximise the chances of our vessel being seen by commercial vessels, our best chance is to ensure that our boat will appear on their radar screen. The best way of achieving this is probably to fit an `active’ radar reflector, such as See Me, rather than rely on many of the so-called radar reflectors currently on the market. Some, commonly seen, have such poor radar reflectivity as to be almost useless.

30°
3°W
30°
2°
30°
30°
50°N
50°N
30°
3°W
30°
2°
LightMaster Software

Radar

How Radar Works

Navigation Using Radar

Pilotage Using Radar

Radar Overlay on a Chart Plotter

Setting up Your Radar

Radar Used for Collision Avoidance

The majority of boat owners buy radar for collision avoidance, for which proper training is required. However, radar is a very powerful navigation and pilotage tool as well.

How Radar Works

The radar scanner rotates at approximately 24 revolutions per minute, and while it does this, it transmits pulses of microwave energy. The time interval between each pulse is long enough to allow a pulse to travel out to the maximum range of the radar and back to the scanner. This means that the radar is listening for about 99.9% of the time and transmitting for less than 0.1%. Although each pulse may be 2 or 4 kilowatts, the average power is only 2 to 4 watts.

Measuring Range

If one of these pulses strikes a solid object the pulse is reflected back to the scanner and the time taken for the return journey is used to calculate the distance of the target from your boat.


Range is determined by measuring the time take for a single radar pulse to travel from the radar antenna to the target and back

Measuring range

Measuring Bearing

At the time a returning 'echo' is received, the radar measures the angle of the scanner from the bows of the boat. Because the pulse travels at the speed of light, this is effectively the bearing of the target from the bows. The radar knows nothing about compass


Direction is measured from the bows of the boat in a clockwise direction.

Measuring of direction

direction, so unless it is supplied with direction from an external electronic ‘fluxgate’ compass or a GPS, it can give direction only in degrees ‘relative’. If a GPS heading input is used, radar can measure magnetic direction only when the boat is moving.

The Reflectivity of a ‘Target’

The reflectivity of the target depends on its angle to the radar beam, its size, its surface texture and what it’s made of. The diagrams here give some idea of how the angle and the texture affect how much signal is returned to the radar scanner.


Solid surface perpendicular to radar beam
Good echo
Solid surface at small angle to radar beam
Reasonable echo towards boat
Solid surface at 45 degrees to radar beam
All target reflections vertical
No echo toward boat
Solid, rough surface at 45 degrees to radar beam
Small echo towards boat

Radar target visibility

The Size of the Pulse

A long pulse contains more energy than a short one and so can travel farther to a target and return to the scanner before the pulse is too small to be detected by the radar set.

Two targets close enough together so that they are ‘illuminated’ by the pulse at the same time will show



Range setting	Pulse length (micro seconds)	Pulse length (metres)
0.75 mile or less	0.08	24
Above 0.75 mile and less than 6.0 mile	0.25	75
6 miles or greator	0.70	210

Typical radar pulse lengths
(Raytheon SL 70 radar)

up on the radar screen as only one target. Ideally then, the pulse should be as short as possible, exactly the opposite to the requirement for the pulse to travel as far as possible.

Professional sets allow the operator to select the pulse length manually, but on a 'leisure' set, the pulse length is controlled by the range selected. Generally, there are about three different pulse lengths, associated with different range scales. The shortest is about 25 metres in length and the longest about 100 to 125 metres in length. Thus at the lower ranges two buoys 30 metres apart will show as two 'echoes' on the screen, while at the longest range, the targets would need to be 100 metres apart before they showed as two echoes.



Pulse length



Horizontal beam width

Horizontal Beam Width

To distinguish between two targets close together, the beam should be as narrow as possible. Beam width is controlled by the width of the scanner, a smaller scanner having a larger

Entrance to Portsmouth Harbour is invisible at this range



Horizontal beam width of 8 degrees

beam width. Typically, a 12-inch scanner will have a beam 8 degrees wide, while a 24-inch scanner' beam is about 3 degrees wide. The average 18-inch scanner has a horizontal beam width of 5 degrees. Any two targets falling within the width of the beam will show up as only one echo. When navigating, this may mean that a harbour or river entrance may not be visible on the radar screen until you are close enough to allow the beam to pass through the entrance.

Entrance to Portsmouth harbour is visible at this range



Radar horizontal beam width 2.5 degrees

Vertical Beam Width

A typical vertical beam width is between 25 and 30 degrees wide. This allows the boat to roll from side to side without lifting the radar beam off the surface of the water. A boat has only to roll 12 to 15 degrees before the beam is lifted off the surface, so a sailing boat going to windward may have to de-power to reduce the angle of heel to make the radar useable.



Boat is upright in the water


12.5 degree half angle
With more than 12.5 degrees of heel the radar beam is lifted off surface of sea

Effect of heel on the radar beam

Navigation Using Radar

The 'radar horizon' is slightly farther away than the 'visual horizon' because the beam curves slightly around the Earth's surface. Atmospheric conditions can alter the curvature, so that in high-pressure conditions radar can see farther and in low-pressure situations less far.

Radar power output determines the maximum range, so that distant high points can be seen farther away with a more powerful radar. However, the most important advantage of high power is that the radar can see smaller targets more easily.

Target projects upwards into radar beam beyond horizon



The radar horizon



Distance A = 3.8 nautical miles
Distance B = 1.8 nautical miles
Distance C = 3.6 nautical miles
Distance D = 3.25 nautical miles

Navigation by radar ranges



Note: 'B' is parallel to the shore, not a radius.

Navigation fix by radar ranges

When taking a three-position line fix, one normally tends to think of using bearings. When using radar, bearings are not the tool of choice. Firstly, radar bearings are not very accurate for various reasons; they need to be corrected for deviation and variation, and you need to allow for the horizontal width of the radar beam.

Radar ranges are more accurate, need no correction and are easy to plot, so think 'range first and use bearings only if you have nothing else'.

You need to be able to recognise suitable points both on the chart and on the radar screen. Don't be tempted into using the 'wrong bay'. Measure the 'width' of the bay on the screen (using the range rings and your fingers) and compare this with the width of the bay on the chart using the chart scale. I've seen students identifying a 4-mile wide bay on the radar as a 1-mile wide bay on the chart!

Whereas range from a point is marked on the chart as a curved position line using a pair of compasses, a distance off a beach, say, is marked by a line parallel to the beach.

A radar fix obtained this way will give you a position relative to the real land, not in terms of latitude and longitude as when using GPS, which may be in error.

Pilotage Using Radar

If you see your destination on radar, don't just 'point and go'. Underwater obstructions and shallows can't be seen by radar, and doing so a recipe for disaster.

Do use 'north-up' display for pilotage. It gets very messy and complicated if you don't, as you will have to keep resetting the electronic bearing lines (EBLs) every time you change heading!

Radar pilotage needs planning, as before, but you have an additional tool, which is distance from an object. Use is made of the radar's EBL and variable range marker (VRM). Most sets have two of



We can see the entrance to Portsmouth Harbour so we just 'point and go'. If we look at the chart we can see that we stand a very good chance of running aground, using this tactic.



The route we wish to follow into Portsmouth Harbour using the Swashway and the small boat channel that runs just outside and to the south-west of the deep water channel, shown here in red.


0.72nM
0.61nM
0.28nM
225(T)
049(T)
C-MAP

The distances we need to set up the VRMs and the tracks we need to set up the EBLs on the radar display.


355°T
Boat's Heading
Portsmouth Harbour entrance
EBL2
EBL1
VRM2
VRM1
Boat's position
HDG MODE
TARGETS
SCREEN
MARPA

Initial approach. VRM/EBL1 set to 049.4(T) / 0.604nM
VRM/EBL2 set to 325(T) / 0.705nM
Boat's heading 355(T) to close shore to maintain a 'distance off' of 0.6 to 0.71 nautical mile.
The radar is set to display 'north-up' and the range is set at 3 miles and for clarity, the range rings have been switched off.

Initial pilotage approach


3nm
15°T
HDG MODE
TARGETS
SCREEN
MARPA

VRM/EBL 1
BRG 49.4° T
RNG 0.604nm

VRM/EBL 2
BRG 325.3° T
RNG 0.705nm

Closing shore, now on a heading of 015(T), radar range set at 3 miles.


1.5nm
35°T
HDG MODE
TARGET
SCREEN
MARPA

VRM/EBL 1
BRG 49.4° T
RNG 0.604nm

VRM/EBL 2
BRG 325.3° T
RNG 0.705nm

Almost at the correct 'distance off', on a heading of 035(T). Radar range set at 1.5 nautical miles.


45°T
HDG MODE
TARGETS
SCREEN
MARPA

VRM/EBL 1
BRG 49.4° T
RNG 0.604nm

VRM/EBL 2
BRG 325.3° T
RNG 0.705nm

Well established in 'Swashway' at a 'distance off' of about 0.63 nautical miles on a healing of 045 (T) – one VRM 'wheeel' over the shoreline, the other clear.
Radar range still set at 1.5 nautical miles.


45°T
TM TV3 AUTO
N-UP GT
HDG MODE
TARGETS
SCREEN
MARPA

Speed 5.0kn
Heading 45.0°

VRM/EBL 1
BRG 49.4° T
RNG 0.604nm

VRM/EBL 2
BRG 325.3° T
RNG 0.705nm

'Wheeling' nicely along the Swashway and watching the depth sounder carefully.



Still maintaining the correct 'distance off'. Approaching the northeastern shore, so resetting VRM1 to 0.28 nM, the 'distance off' that we being our turn onto a heading of 325(T). Still watching the depth carefully.



Just reaching 0.28 mile off the northeastern shore, so starting the turn onto 325(T). The cross-check here is that the depth is now increasing to greater then 5 metres.



Turned onto a heading of 355(T), EBL2 (325T) is nearly pointing at southern point of entrance, so maintaining heading 355 of 355 for a little longer.



Changed range to 0.75 mile, come port 10 degrees onto a heading 345(T) as EBL2 is now very nearly on the southern point of the entrance. Depth now is between five and ten metres.



EBL2 now on southern point of entrance and heading 325.



Nicely established in small boat channel. Range set to 0.5 mile.



Almost at entrance, range changed to 0.25 mile.



Inside entrance, range set at 0.125 mile and heading 337(T).


0.25nm
290°T
VRM/EBL 1
BRG 59.5° T
RNG 0.083nm
VRM/EBL 2
BRG 325.3° T
RNG 0.083nm
HDG MODE
TARGETS
SCREEN
MARPA
LightMaster

Through entrance, range set at 0.25 mile, heading 290, turning onto a heading of 217(T) to destination.


0.125nm
217°T
VRM/EBL 1
BRG 59.5° T
RNG 0.083nm
VRM/EBL 2
BRG 325.3° T
RNG 0.083nm
HDG MODE
TARGETS
SCREEN
MARPA
LightMaster

Now on a heading of 217(T), range set at 0.125 mile, proceeding down channel to destination.

each of these, which can be used to find the direction and bearing of targets. In the case of pilotage, we can pre-set these to help us follow our plan. Professional sets allow what is called 'parallel indexing', an excellent aid to pilotage, but we are able to use VRMs instead and if your radar is able to 'float' your EBL/VRM pair, you have a direct equivalent of parallel indexing.

In order to describe the method of using the radar for pilotage, I have set up an approach to Portsmouth Harbour using Lightmaster Software's radar simulator. Having made our plan, we start our approach from the Solent and aim for the shallow water 'Swashway'. We then maintain the desired distance off the northwestern coast to remain in the channel, turn for the entrance when the distance off the northeastern shore is correct and follow the bearing into the entrance, remaining in the small boat channel, just outside the main, deepwater, channel. In a real situation you will be monitoring the depth sounder as well. The following sequence of diagrams shows the process.

Floating EBL/VRM

Some radar sets allow the VRM/EBL origin to be offset, or floated. This allows pilotage where there's not a long straight piece of land with a good radar echo. Because the floated EBL and VRM are anchored to a static radar target or indeed a static position anywhere on the radar screen, we can define a route to be followed, just as we would follow a visual



Chart of entrance to Portsmouth


Fort
seaPro

Radar pilotage plan into Portsmouth Harbour entrance using the 'Swashway' and 'small boat channel'.

Pilotage plan details

transit. To do this, the radar must be used in north-up mode.Let us follow the same route into Portsmouth Harbour as before, but this time we'll use the fort and the northeastern shores to guide us in. There are a number of ways that we could set up the radar, but using the radar simulator, we'll follow through a suitable procedure. I've removed all the buoys from the display so that we can just concentrate on the things we are going to use.

- Mark on the approach chart into Portsmouth the centrelines of the Swashway and the small boat channel.
- Measure the direction of the Swashway and the distance off that it passes from the fort. Note also the point before which you want to be established on the centreline.
- Measure the direction of the small boat channel and the distance off the shore that it cuts the Swashway.


1.5nm
180°T
Fort
VRM/EBL 2
VRM/EBL 1
Boat's position
VRM/EBL 1
BRG 229.4° T
RNG 0.313nm
VRM/EBL 2
BRG 49.4° T
RNG 0.313nm
HDG MODE
TARGET
SCREEN
MARPA
RANGE

VRM/EBL 1 is set to a BRG of 229 T and a RNG of 0.31 mile.
VRM/EBL 2 is set to a BRG of 049 T and a RNG of 0.31 mile.

VRM/EBL 1 is 'floated' so that the bearing passes along the NW side of the fort and the and the VRM is centred on the shoreline

VRM/EBL is floated so that its EBL touches he VRM 1 to become the centreline of the Swashway.

Radar preparation 1


1.5nm
180°T
VRM/EBL 1
VRM/EBL 2
VRM/EBL 1
BRG 229.4° T
RNG 0.313nm
VRM/EBL 2
BRG 49.4° T
RNG 0.313nm
HDG MODE
TARGETS
SCREEN
MARPA
RANGE

VRM/EBL 1 is now floated to coincide with EBL 2.

This forms the centreline of the Swashway that you are going to use for radar pilotage.

Radar preparation 2

- Set up a VRM/EBL to the reciprocal direction of the Swashway and the distance off from the fort.
- Float this to the coast and place the EBL just touching the NW edge of the fort.

Set up the second EBL/VRM to the direction of the Swashway and the distance off from the fort.

- Float this to a position where the Swashway starts and so that the VRM touches the first EBL.
- Move the first EBL so that it is superimposed on the second. This is the centreline of the Swashway.
- Reset the second (now redundant) EBL/VRM to the direction of the small boat channel and the distance off the north-east shore where you will start to follow it.


1.5nm
180°T
VRM/EBL 2
VRM/EBL 1
VRM/EBL 1
BRG 229.4° T
RNG 0.313nm
VRM/EBL 2
BRG 334.5° T
RNG 0.288nm
HDG MODE
TARGETS
SCREEN
MARPA

VRM/EBL 2 is set to BRG 334 T/0.29 nm.
It is then floated so that the VRM touches the shoreline and is centred on EBL 1.

This marks the centreline of the small boat channel and the point at which the change of course is made.

Radar preparation 3


1.5nm
0°T
Boat's heading
North-up
Centre line of Swashway
Range rings
Boat's position
VRM/EBL 1
BRG 229.4° T
RNG 0.313nm
VRM/EBL 2
BRG 334.5° T
RNG 0.288nm
HDG MODE
TARGETS
SCREEN
MARPA

Having constructed the plan on the radar, all you need to do is to follow it.

The boat is heading 000T and is about 0.25 mile from the centre line of the Swashway.

Following the plan 1


1.5nm
40°T
Boat's heading
North-up
Centre line of Swashway
VRM/EBL 1
BRG 229.4° T
RNG 0.313nm
VRM/EBL 2
BRG 334.5° T
RNG 0.288nm
HDG MODE
TARGETS
SCREEN
MARPA

The boat is now steered to maintain the centreline of the Swashway – the current heading is 040T.

Following the plan 2


1.5nm
49°T
Boat's heading
North-up
Boat's position
Centre line of Swashway
VRM/EBL 1
BRG 229.4° T
RNG 0.313nm
VRM/EBL 2
BRG 334.5° T
RNG 0.288nm
HDG MODE
TARGETS
SCREEN
MARPA

Heading is now 049T and the boat is now approaching the small boat channel.

Following the plan 3

- Float this EBL/VRM so that the VRM just touches the shore and its centre is on the Swashway centreline.

This probably sounds a bit complicated, but follow the procedure through on the radar simulator screen shots and you will see that it isn't half as complicated as it sounds.


1.5nm
18°T
Centre line of small boat channel
Boat's heading
North-up
Boat's position
Centre line of Swashway
VRM/EBL 1
BRG 229.4° T
RNG 0.313nm
VRM/EBL 2
BRG 334.5° T
RNG 0.288nm
HDG MODE
TARGETS
SCREEN
MARPA

Boat has reached the centreline of the small boat channel and is turning through 018T onto a heading of 334T

Following the plan 4


1.5nm
336°T
Boat's heading
North-up
Centre line of small boat channel
Boat's position
Centre line of Swashway
VRM/EBL 1
BRG 229.4° T
RNG 0.313nm
VRM/EBL 2
BRG 334.5° T
RNG 0.288nm
HDG MODE
TARGETS
SCREEN
MARPA

The boat is now on the Swashway's centreline and heading 336T

Following the plan 5

- Approach the Swashway centreline from a safe distance. Here we are approaching on a northerly heading and have about a quarter of a mile to run.
- Turn onto the inbound heading and settle down on the centreline, adjusting the heading as required to allow for wind and tide.
- Keep monitoring the depth throughout the approach.
- As you approach the junction of the two legs, be ready to initiate a turn onto the heading of the small boat channel.
- Now keep on the centreline of the small boat channel.


0.75nm
334°T
VRM/EBL 1
VRM/EBL 2
HDG MODE
TARGETS
SCREEN
MARPA

The boat is well along the small boat channel, on its centreline and heading 334T.

Following the plan 6

Parallel Indexing

Using one 'floated' VRM/EBL, and one normal EBL, the screen can be set up for the equivalent of the professional set's parallel index.

- Set up one VRM/EBL with the course as the bearing and the required 'distance off' VRM.
- Float it sideways so that the floated EBL sits on the target echo.
- Set up the second VRM/EBL with the VRM at the required distance off the target echo.
- Wheel the normal, unfloated, VRM (which remains attached to the boat) along the floated EBL.
- This will allow you to steer the boat along the parallel course, compensating for the tide and wind, passing the target at the required distance off.


1.5nm
49°T
Boat's heading
Fort
Normal VRM
Floated VRM/EBL
VRM/EBL 1
VRM/EBL 2
HDG MODE
TARGETS
SCREEN
MARPA

The floated VRM/EBL is just touching the fort

The normal VRM is set to the same distance and is 'wheeled' along the parallel index formed by the floated EBL

Parallel indexing

Your radar is set up and you're now ready to follow the plan.

Each piloting situation is different so you'll need to consider how the radar can be used. It will depend on how accurately the shoreline or other targets will show up on the screen, cliffs showing up very well while low-lying 'beachy' shorelines may be very indistinct. In some situations radar will be of little use in avoiding underwater dangers, because there's no suitable radar target to line up on.


Steep coastline
Flat coastline
Good radar echo
Weak radar echo

Effect of different types of coastline

Radar Overlay on a Chart Plotter

The latest trend in full-sized chartplotters is to combine them with the radar display. It is possible to split the screen so that the chartplotter display uses one-half the screen and the radar the other. It's also possible on many to overlay the radar display on the chartplotter display, so that the two are superimposed. To do this requires a high-speed electronic fluxgate compass.

I find that for collision avoidance purposes the overlaid screen is too cluttered and prefer a separate radar display. However, for the purposes of navigation and pilotage, the overlaid radar has considerable merit.

For the overlay, the radar echoes are often coloured magenta, which is mostly not present on the cartography so the radar echoes stand out well. The radar echoes should correspond with the cartography and this makes identifying the shoreline and navigation marks much easier. Any radar echo that doesn't register with a charted feature is likely to be a ship.


105°T
C-MAP
TARGETS
SCREEN
MARPA

Chartplotter with radar overlay


Radar echo of shoreline registers with charted shoreline
Radar echo of buoy registers with buoy
Echo with no charted feature is probably a ship

Do the radar echoes correspond with the chart?


ADVANCE WAYPOINT
STOP FOLLOW
RESTART XTE

Very large chart error


TARGETS
SCREEN
MARPA
RANGE

With radar overlay, the chart error is very obvious.

Any error in the cartography or GPS will become apparent, because the radar will not agree with the chart. The radar is correct!

Setting up Your Radar

Setting up your radar properly is very important. Most sets have some form of automatic adjustment of some important functions, they're getting better, but you can always do better yourself if you know what to do.

A good illustration of this occurred when I was on a long passage in flat calm seas, and with little else to do, I was playing with the radar. Having adjusted everything very carefully, I noticed some fast moving echoes ahead, but saw nothing on the water. I looked up a little and there were some seabirds (Gannets) flying round ahead and it was their echoes that I could see. I then set all the controls to automatic and their echoes disappeared!

B.R.G.T.

This simple mnemonic should help.

- B – adjust the *brightness* to suit the lighting conditions around you. On an LCD display, you'll need to adjust the *Contrast* instead. This is not adjusting the signal, just making the screen readable.
- R – now select an intermediate *range*, about 4 to 6 miles is good, as long as there are targets within range. Some authors suggest setting gain before setting range, but ideally you need to set the gain at an intermediate range, so why not set the range, first?
- G – adjust the *gain* to give good strong returns, but don't overdo it. As a rule of thumb, on a CRT set, adjust until there are speckles (noise) on the screen and then reduce the gain until they are only just visible. On a LCD screen, adjust the gain until you have speckles and then reduce the gain until there are just no speckles visible. If you are not confident about this set the gain to automatic, but you will loose a bit of performance.
- T – now adjust the *tuning*. Ideally the set will have a tuning meter – you adjust the tuning up and down until you have the maximum number of bars visible. Some modern sets don't have this facility, and adjusting tuning manually may be difficult for the inexperienced, in which case you'd better leave it set to automatic. The tuning control adjusts the receiver frequency so that it's the same as the transmitter frequency. The transmitter magnetron changes frequency as it heats up, so it should be adjusted again after about 10 minutes. The magnetron also changes temperature as the range is changed and needs to be checked again. If you find that automatic tuning gives a good display, you may as well use automatic, although again, you may loose a little performance.

Radar Used for Collision Avoidance

This is a book all about practical navigation. You'll find other books telling how to use radar for collision avoidance (Wiley Nautical's Radar Companion' is one).

However, I think it appropriate to remind readers that special rules come into force when vessels are not in sight of one another and conflicting traffic can be seen only on radar.


fernhurst
Pat Manley
RADAR
COMPANION
2 RADAR SIGNALS
4 THE BEAM
6 THE SCREEN
9 STABILISATION
10 MAIN CONTROLS
12 SUBSIDIARY CONTROLS
13 NAVIGATION
15 PILOTAGE
17 COLLISION AVOIDANCE
Raymarine
Lifeboats

'Colregs'

The normal 'rules of the road' governing 'stand on' and 'give-way' vessels apply only to 'vessels in sight of one another' – rule 11.

Conduct of Vessels in Restricted Visibility

Rule 7 b

Proper use shall be made of radar equipment if fitted and operational, including long range scanning to obtain early warning of risk of collision and radar plotting or equivalent systematic observation of detected objects.

Rule 7 c

Assumptions shall not be made on the basis of scanty information, especially scanty radar information.

Rule 19 d

A vessel which detects by radar alone, the presence of another vessel shall determine if a close-quarters situation is developing and/or risk of collision exists. If so, she shall take avoiding action in ample time, provided that when such action consists of an alteration of course, so far as possible the following shall be avoided:

- an alteration of course to port for a vessel forward of the beam, other than for a vessel being overtaken;

- an alteration of course towards a vessel abeam or abaft the beam.

Rule 19 e

...or which cannot avoid a close–quarters situation with another vessel forward of her beam, shall reduce her speed to the minimum at which she can be kept on her course. She shall, if necessary, take all her way off...

'Rule 19'

Rule 19 of the 'Colregs' can be summarised in the following diagram – there is no stand on vessel and *all* vessels are give-way vessels – and if you are going to use your radar in restricted visibility, you *must* be aware of it. Remember that you can slow down or stop as well as turn.



Ahead
Turn to starboard
Turn to starboard
Targets
Ahead of abeam
Ambiguous zone
Abeam to port
Abeam to starboard
Turn to starboard
Turn to port
Astern

If you need to make a turn to avoid a close quarters situation, this diagram tells you which way to turn. Take extra care in the ambiguous zone the area between 'forward of abeam' and 'abeam'.

The 'essence' of rule 19



Autopilots

Types of Autopilot

Using the Autopilot

An autopilot can reduce the workload on the helmsman and navigator. For longer short-handed passages, it can allow proper time for navigation and pilotage.

13.1. Types of Autopilot

There are two basic types of autopilots:

- A simple autopilot, which maintains a set compass heading.
  - This may have no heading display and will 'take up' the heading the boat is on when the autopilot is switched *on*. Heading is altered with 'left and right' keys and the heading will be monitored using the steering compass.

  - Some will have a heading display, will again take up the heading at 'switch on', have left and right keys, but the heading can now be monitored on the autopilot display and checked against the steering compass.
- An autopilot linked to the navigation instruments, which can automatically take you to a waypoint or even follow a complete route.
  - This type will have a remote 'flux gate' compass, a heading display and keys and displays allowing a route to be followed.

Personally, I do not advocate coupling the autopilot to the navigation system to automatically follow a route for the following reasons:

- With the autopilot making constant alterations of heading to maintain the cross track error to a minimum, the navigator has absolutely no idea of the compass course being followed, and cannot revert to 'DR' navigation if needed.
- Steering a compass-linked course allows any compass errors to become obvious. 'Coupling up' to the route or waypoint means that a constant compass course is not being steered and any compass error is difficult to assess.
- A short-lived GPS error can cause the boat to suddenly veer off course – I have witnessed such incidents.
- The helmsman/navigator loses positional awareness of the operation of the boat.
- Steering a compass-linked course allows the navigator to assess the effect of leeway and the accuracy of the tidal current predictions – essential if he needs to revert to DR navigation.

Raymarine
STANDBY
050
DISP
-1
+1
TRACK
STANDBY
-10
+10
AUTO

13.2. Using the Autopilot

- The autopilot when not being used will be in the 'standby' mode.
- When set to 'auto' mode, the heading can be adjusted to that required by the navigator/pilot.
- By monitoring the bearing and distance to waypoint and the cross track error, the heading can be adjusted to either regain track or go directly to the waypoint if that is a safe course of action.



Manually steering 050


AUTO
050
Heading set on autopilot controller
Tide
Course over ground

Autopilot in heading mode


COG 045
BRG 055
L
R
AUTO
050
Active waypoint
Bearing to waypoint
Active track
Cross track error

Cross track error to an active waypoint

- If you want to couple up to an active waypoint, then 'Track' or 'Nav' is selected. If you are already on the correct track to the waypoint, the autopilot will steer such headings as will maintain the cross track error at zero.
- If you are not on the correct track when you select 'Track' or 'Nav', the autopilot will immediately turn the boat to regain the correct track. You need to be aware which way the boat will turn and by how many degrees, in case there's another boat or obstruction in the way. When the cross track error has been reduced to zero, the boat will again be turned (so keep monitoring what is happening) and then steered to maintain zero cross track error.
- If you have 'coupled up' to a route, you need to be aware of what will happen when you get to the next waypoint. The majority of autopilots will give an audio warning that the waypoint has been reached, and if no action is taken, will revert to heading mode and continue on the last heading. They will not make an unsupervised turn to the next waypoint as this could cause a collision with any nearby boats.


AUTO - TRACK
050
Active waypoint
Active track
Boat on track with no cross track error (XTE)

Autopilot coupled to an active waypoint

If you do decide to use navigation mode, you must continue to 'navigate the boat' mentally and not be distracted.

Personal Computers

- What Type of PC
- What Make of Chart-Plotting Software?
- What Type of Electronic Charts?
- Electronic Charts for PC Based Chartplotters
- Selecting the Software
- Constructing a Route
- Sailing Yacht Route Planning
- Sending the Route to the GPS
- AIS on a PC
- Radar on a PC
- Navtex on a PC
- Tides on a PC
- Connecting to the Boat's Systems

I've been using a personal computer (PC) for some navigation activities on my boat since about 1999. It isn't essential by any means, but it's very useful and I enjoy using it.

Only users who have never experienced a computer crash would ever dream of using a PC as their sole means of navigation.

What Type of PC?

With the advent of 'on board entertainment PCs' there's a temptation to use a desktop or miniaturised desktop computer for the job. That's fine when you are running on mains or generator power, but running off an inverter can cause unwanted shutdowns and I wouldn't recommend it when you are using it for navigation. I believe that a laptop PC is a better bet. It can be run from a smaller inverter or a 12 volts adaptor, but should always be able to fall back on its internal battery if the external power fails. The hard drive in a laptop will be more robust that a desktop version and the cost of a 'ruggedised' laptop is prohibitive.

Unless you want to make use of the three-dimensional (3D) capabilities of some chart-plotting software, a powerful PC is not required. My boat PC runs Windows 98 and has a 475 megahertz CPU and only 64 megabytes of random access memory (RAM). It does an excellent job, but wouldn't run the latest version of my software, which does need more computing power, but a P4 processor and 256 megabytes of RAM should be fine. Check with the software vendor. If you really need to use the fantastic 3D capabilities, then a high-spec machine with a separate graphics card is essential.

There's much to be said for a computer that is never connected to the Internet, as it then wouldn't suffer from a virus.

What Make of Chart-Plotting Software?

This depends very much on personal choice, the depth of your pocket and what you intend to use it for. You need to consider what features you require:

- Some software is pretty basic, allowing a route to be constructed but not planned using tidal stream data. Others allow full tidal planning and weather routing, constructing sailing polar diagrams, using lay lines when tacking and more. Most software is somewhere in between.
- There are two types of electronic charts; raster and vector. Their capabilities are very different and some software will not be compatible with vector charts.
- Automatic Identification System (AIS) can be shown on some systems.

- A radar overlay is possible with some systems, though this will normally be restricted to a specific radar.
- Some systems allow waypoint and route data to be uploaded to a global positioning system (GPS) or chartplotter.
- Some systems allow the software to control the boat's autopilot.
- Some systems allow the use of chartplotter memory cards, which can be used in the PC and then transferred to your chartplotter.

What Type of Electronic Charts?

Of considerable importance is what type of electronic charts can be used.

Raster Charts

- Raster charts are electronic clones of a paper chart.
- They look just like its equivalent paper chart.
- They should be viewed at a specific scale.



UKHO raster chart

– scanned from the UKHO paper chart

Maptech raster chart

– scanned from the UKHO paper chart

SeaPro 'livechart' vector chart

– redrawn using data from UKHO paper chart

Raster and vector charts



Viewed at the correct 'zoom' for the scale of the chart – 1:3,500 – obtained by using the 1:1 control icon – the detail on a chart of a given scale is always the same because there is only one layer

Over-zoomed – no extra detail but the chart becomes 'pixelated'

Over-zoomed, even more giving, even greater pixelation

Raster zooming

Vector Charts

- Vector charts are redrawn completely by the electronic chart cartographers.
- There are many layers, each with different types of data, and these layers may be switched on or off either by the user or automatically as you zoom in or out.
- Photographs, pilots, information, etc. can all be embedded.
- Errors may be introduced in the cartography during the copying process.
- Vector charts may not look exactly like their paper counterparts.
- Vector charts bring huge flexibility to the system.



Detail appropriate to the view – chart scale 1:15000

Zoom in and the detail is increased appropriately –chart scale 1:3500

Zoom in some more and even more detail is shown –chart scale still 1:3500

'Over-zoomed' – no extra detail but no 'pixelation' –chart scale 1:3500

Zooming in on a vector chart

Electronic Charts for PC Based Chartplotters

In the past, each software provider has produced their own electronic charts, but this is getting prohibitively expensive. There is now a tendency to use third party electronic charting, especially as there is now an international standard for electronic cartography.

Professional Cartography

Most new commercial vessels use electronic chart displays on the bridge, and where legislation controls the type of equipment used, all electronic charts will be according to the S57 (vector) International Standard.



S 57 chart

Leisure Cartography

Electronic charts used in the leisure sector are much more variable and will depend on the software provider, some using only one sort of chart and others able to use several, including S57. Probably, the ideal is the ability to use multiple types of charts, including those used by dedicated chartplotters, such as C-Map and Navionics. The user then gets



This Navionics vector chart used on many chartplotters, can also be used with seaPro's PC based chart plotting software. It has many enhancements for the leisure boater including photographs of marinas, etc. Full seaPro passage planning can be made using the Navionics charts.

Navionics charts on a PC

the value added facilities including photographs and marina information, valuable to some boat owners.

Selecting the Software

A visit to the chart-plotting software vendor's web site should show you what facilities are available. There are often several versions to choose from, extra facilities costing more money. Upgrades from one version to another are usually possible.

You need to ask yourself; will the computer be

- The only chartplotter on the boat?
- Used only for constructing a route?
- Used for planning a route – including tidal planning with best time of departure and track made good over the ground?
- Used to construct/plan a route and send the route to a GPS or a chartplotter?
- Used to combine with wind forecasts over the period of the route to plan the best route to take account of the varying wind direction and strength.
- Used to display 'lay lines', tacking angles, sailing 'polars', etc. to optimise best navigate the route of a sailing yacht.
- Is it compatible with the chart type of my choice – raster or vector?
- Can it be used with my chartplotter's memory card?

Constructing a Route

Constructing a route on a PC based chartplotter is usually simplicity itself. The cursor is placed over the position that you wish to have a waypoint, you click the mouse, move onto the next position and click again, continuing to the end of the route. The only problem is that the screen size will limit the amount of detail that you can see, though this is much better than the average dedicated chartplotter. For safety, you'll need to zoom in and out and pan along the route to examine it along its length to ensure that it runs into no dangers.



Click the mouse where you wish to insert waypoints to make up a route.

PC route 1



Zoom in and check each portion of the route for safety.

PC route 2



Zoom in and out as necessary and pan along the route.

PC route 3



Continue along the route at an appropriate zoom.

PC route 4



Until you reach the end of the route.

PC route 5



Some chart-potting software, such as seaPro, allows various departure times to be investigated to give the shortest time on route, using the

Planning departure time



The plan overview shows course to steer for end elapsed time for each leg and ETA destination for the selected departure time.

Route plan



Once the route has been calculated, the track over the ground is displayed as a dashed line and the leg details may also be displayed on the chart if desired.

Route plan details



With a long 'cross-tide' passage, the cross track displacement of the ground track will be significant. Chartplotting software that displays the ground track is at a distinct advantage over those that don't.

Display of ground track

The more comprehensive software is then able to calculate the time en route according to the time and date of departure, allowing for the tidal flow. The course to steer and the elapsed time on each leg are also calculated.

Even better, some software allows the track over the ground to be displayed. This is invaluable, especially where the course is predominantly across the tidal flow, as the cross track displacement may be considerable and could run the boat into danger.

Sailing Yacht Route Planning

A sailing boat's speed depends on the wind strength and direction. You can assume a single average speed and calculate the route using this. If the wind is from ahead, then you'll have to tack down this route and the plan will be very inaccurate.

Sailing Polars

Sailing polars are the performance data for various sail plans, in different wind strengths at different angle to the wind. Initially, they are the designer's predictions, but these are then modified in the light of sea trials.

The polar shown in the diagram is a default polar diagram from Euronav's seaPro chart-plotting software. This can be edited manually and on some versions of the software may be automatically updated as you sail. It is the performance data from these polars that is used with the forecast winds to produce the weather routing sail plans.



Sail Plan: Default

Wind Speed: 10.00

Tacking Angle: 41

True Wind Angle	Boat Speed Kt
43.10	6.21
52.00	6.86
60.00	7.19
75.00	7.52
90.00	7.61
110.00	7.68
120.00	7.56
135.00	7.11
150.00	6.28
180.00	4.35

A sailing polar diagram

Allowing for the Forecast Wind

Some chart-plotting software allows you to insert the forecast wind into the plan, which will then calculate the probable boat speeds in the various wind strengths and directions, telling you when you should tack, using the boat's actual performance data (sailing polars). Good software will allow for the changing tidal flows as well.

An alternative to manually inserting the various wind conditions is to download a weather file from the Internet. Most weather routing software uses the standard GRIB



Wind data can be inserted manually, changing at intervals of your choice for the duration of the voyage, allowing the most advantageous route to be chosen according to both wind and tide.

Weather routing 1



The weather route's tacking points and courses to steer can be calculated.

Weather routing 2



The grib file (weather) can be displayed. If the grib file is for a forecast period of 60 hours, the wind direction and other data if available can be shown for various time intervals.

Midnight GRIB

(GRIdded Binary) format and the files cover a specific forecast time period, giving, say, the conditions every 4 hours for the following 72 hours.

GRIB files are available from various sources. Some are free and have minimal, but sufficient data and some are by subscription. Subscription data will be on a much smaller grid basis and contain added data such as wave heights, temperature, cloud cover and more.



The wind pattern for 24 hours later
24 hour GRIB



The wind pattern for 42 hours later
42 hour GRIB



The wind pattern 72 hours after the initial forecast time.
72 hour GRIB



Weather files (grib files) can be down loaded from the internet and the software then allows the winds from these files to be used to calculate the best route to be calculated
The fastest route

If your software supports weather routing, the vendor's web site will have links to various sources of GRIB files.

Sending the Route to the GPS

Although the PC will almost certainly have the boat's position input from a GPS set, which allows the navigation to be carried out using the PC, it's a very good idea to transmit the route data from the PC to the GPS. In this case, should the PC fail, the route will still be available in the GPS to allow continued electronic navigation. If you are using a dedicated electronic chartplotter, then the route, once constructed on the PC, can be transferred to the chartplotter.

Compatibility of Route Transfer

Unfortunately, some GPS and chartplotter manufacturers use their own protocol, rather than the industry standard NMEA. The PC chart-plotting software uses NMEA sentences to receive GPS and other data, and also uses NMEA to transmit information back to the GPS/chartplotter. At the time of writing, Garmin GPS and chartplotters wouldn't accept route transfers in NMEA. It's possible to send individual waypoints, but you will have to string these together yourself in the Garmin GPS/chartplotter. There seems to be no problem in chartplotters which use third party cartography, such as C-Map and Navionics.

GPS 152
Wpt
By Name
Nearest
Proximity
001
001
003
005
GARMIN
MENU
PAGE
ENTER MARK
OUT
NAV MOB
QUIT
IN

Garmin allows only NMEA waypoints to be transferred, not the whole route.

Garmin transfer

AIS on a PC

Some PC chart-plotting software is able to display AIS information. All received AIS targets are displayed in real time on the chart, with their tracks, course over ground, and with some software a vector based on its rate of turn.



With AIS switched on, all received vessels are displayed. Data boxes show vital information.

AIS display 1


228237700
CPA: 0.60nm 07m54s
36.50kts
202.00 °
Vessel UAIS Messages
Vessel List
Vessels
MMSI
Selecting
Select Vessel from Chart
Deselect Vessel
Zoom Chart
Add to filter list
Accept
Yes
Cancel
Total Vessels
Vessels Stored Details
Rx Texts
Tx Texts
Selected Vessels Texts
Date Time
Destination
Res
Text
Close
seaPro

Type Vessel Class A
MMSI 228237700
CPA 0.60nm 07m54s
Status Under way using engine
ROT 0 °/min
Hdg (T) 202 °
Vessel Type n/a
EPFD n/a
UTC Report 3 s
RAIM not used
AIS Version 0
Age 03:46
SOG 36.50 kts
COG 202.00 °
Lat 50 32.749N
Lng 1 4.799W
Lng >10m

All targets can be displayed and then individual targets selected to display all its transmitted data.

AIS display 2

If the closest point of approach (CPA) becomes less than the user defined value, the target blinks, an audio warning sounds and the display includes the value of the CPA and the elapsed time until the CPA.

A list of all the targets can be displayed on the screen, all the data for each target can be viewed or alternatively if a target is clicked, then its data can be displayed.


228237700
CPA: 0.60nm 07m54s
36.50kts
202.00 °
Vessel Information
Prev
Next
Again
Add to filter list
Close
seaPro

Vessel Class A
MMSI: 228237700
CPA: 0.60nm 07m54s
Status: Under way using engine
ROT: 0 °/min
SOG: 36.50kts
COG: 202.00 °
Position: 50 32.749N 1 4.799W
Pos accu: >10m
Hdg: 202 T
No. Persons: n/a
UTC reports: 3 s
RAIM: not used
AIS Ver: 0
Age: 06:50
Dist: 5.48nm
Brg: 36.3 deg

Individual targets can be 'clicked' to display all its data.

AI display 3

Radar on a PC

Several versions of the PC chart-plotting software are able to act as a radar display. These require a special radar scanner, rather than taking signals from the usual scanner provided with a conventional system. The scanner output is sent directly to the PC and all control of the radar is carried out from the PC software.

The radar display can be 'whole screen' radar only, 'split screen' alongside the chartplotter display, or 'superimposed' on the chart.

Stand-Alone Radar

The radar display fills the PC monitor screen and all the radar controls are operated using the computer mouse. Because all the controls are visible and not immersed in various menu levels, operating the radar is very straightforward – much easier than a modern leisure radar.

The radar may be operated in north-up or head-up modes at a click of the mouse button.



Range 2 miles, head-up display, heading 228

Split Screen Radar

When the PC chart-plotting software is in use, the radar may be displayed in its own window on the PC screen alongside the chart-plotting software. Alternatively, it may be displayed in its own window on the top of the chart-plotting software.



Radar and chart-plotting software side-by-side



Radar window on chart window

Superimposed Radar

The radar display may be superimposed onto the chart display. This has two major advantages:

- Certainty of identifying large cartographic or GPS errors. You need to know where you are relative to the land (and its dangers). Only the radar will tell you this. The accompanying diagram shows a deliberately induced GPS error, which would have been invisible had we not used superimposed radar. Another interesting error which showed up when preparing this section of the book was an apparent angular error in the superimposed image. This was probably due to some form of compass or radar alignment error.



A deliberate GPS error of 1000 metres North and 1000 metres West has been introduced. On the chart plotter alone this would not have been seen. With the radar overlaid on the chart, the error is immediately obvious - the radar must be correct and the GPS or cartography must be wrong.

GPS/cartographic error

- Ease of identifying topographical features on the radar. Because the radar can't see around corners, it's often difficult to match the radar image to the chart. Superimposed radar overcomes this difficulty, especially if there are extensive mud flats which show up



With the error removed our position is correct. The saw-tooth red track line shows where deliberate errors of 300, 600 and 1000 metres were introduced.

The correct picture



Superimposed radar with split screen. Heading 170, radar range 2 miles. There is some evidence of a compass error as the return for the NW and NE shores appear to be misaligned by about 6 degrees.

Superimposed radar and split screen



Heading 040, radar range 0.75 mile. The magenta lines show where I have rotated the radar image through 9 degrees to align it with the directions of the shorelines. This error could be due to compass deviation, the radar not being aligned with the boat's centreline or one set of data being based on magnetic and the other true.

Compass error



Radar superimposed on chart, North-up, heading 230, radar range set at 2 miles. Software has matched the radar range to the scale of the chart and converted the radar image to North-up.

Superimposed radar

on the radar at low water. Also, superimposition sometimes makes it clearer which are boats rather than navigation marks.

PC Radar for Pilotage

The usefulness of superimposed radar for pilotage can't be understated, except for one problem; the screen must be in the view of the pilot, who should be in full view of his surroundings, that is able to look outside.



Superimposed radar and split screen radar being used for pilotage. This utilises two completely different tools with different sources of data, one of which is the land itself, giving much greater confidence.

Split screen pilotage



With the radar set to 0.25 mile range, very accurate pilotage is possible.

Accurate pilotage



GPS error of about 30 metres (the lower of the two traces) would have made pilotage in fog dangerous without radar, which would have shown up the error. If you look carefully at the previous diagram, this difference between the GPS position and the superimposed radar position can be seen.

GPS error

Used at a suitable chart scale on the plotter and a very low range on the radar, then any discrepancy between GPS, cartography and radar can be seen. Provided the radar is set up properly, its view of the world is correct.

We can see in the accompanying diagrams that the ideal is to have a superimposed chart/radar in one half of the screen and the stand alone radar in the other. Obviously, the bigger the screen the better.

This technique can also be used with a radar superimposed chartplotter, but often the screen is too small for accurate use.

PC Radar for Collision Avoidance

Personally, I do not like superimposed radar for collision avoidance as I find it too confusing. I would use split screen radar or standalone radar for this purpose.

Navtex on a PC

Dedicated Navtex receivers are left in standby mode for the whole time so that they will receive all the messages, which are displayed on demand by the user. The PC can be linked to a Navtex receiver, but for the best use the PC will need to be left running all the time, which is probably not the way you will use an onboard PC.



Navtex window in view – you can scroll through the messages.

Navtex

Tides on a PC

Various forms of tidal software are available for use on a PC, some of them 'stand alone' and some integrated with the chart-plotting software.

Tidal Flow

Tidal flow data may be integrated with the chart-plotting software and allows both strategic and tactical planning if the software supports planning.

- It is used in the initial route planning to obtain the time of departure that gives the fastest passage.



Tidal flow can be displayed on some chart plotting software
The flow is given in real time and as the passage progresses,
the tide vectors change accordingly. The time can be scrolled
forward or backwards over any time span to investigate
various tactical options

Tidal flow

- It is used for passage planning when wind against tide is of consideration.
- It is used for passage and re-routing planning where an ebb tide would preclude entry or a flood tide would preclude departure.
- It is used en route for tactical considerations, such as avoiding tide races, etc.

Tidal Heights

Tidal height software is available as standalone software or may be integrated with the chart-plotting software.

Standalone Software

Completely independent of any chart-plotting software, tidal height information is available in both numerical and graphical format. The number of tidal stations and geographical area covered will depend on the software used. Some software will also run on hand-held computers (PDAs).

Built-In Software

Some chart-plotting software has built-in tidal height data. As well as having a list of tidal stations, you may also be able to click on tidal station logos which will then display the real time data for that station. Other dates and times can also be chosen for planning purposes.



Tidal height curves are often available within chart-plotting software, sometimes for many secondary ports as well as standard ports.

Tidal height curves

Connecting to the Boat's Systems

The Industry standard communication language is NMEA 0183, with NMEA 2000 becoming common. Different manufacturers use their own languages as well, but any communication with a PC will be in one of the NMEA standards.

Instrument Wiring

Where a number of different instrument systems are mixed, it is notoriously difficult to get them to interface satisfactorily. Using a 'multiplexer' to combine the instrument outputs into one combined NMEA data stream should solve any problems.


Navico 'Corus' connections
Wind
Speed
Depth
Navico Corus NMEA
Raymarine seatalk connections
Raymarine SL 70 radar
Heading
Rudder reference
A/P controller
Raymarine autopilot computer
A/P remote
AIS
Standard horizon
Port 3 out
Port 2 In
Port 1 in
NMEA 1
NMEA 2
(38400baud)
Ch 1
Ch 2
Ch 3
Ch 4
Multiplexer
All required sentences in NMEA out
NMEA OUT
(Route transfer)
Polling
MNEA in
NMEA out
Furuno Navtex
Icom 505 VHF
PC
Running seaPro

Added complexity requires a multiplexer to ensure only one 'talker' per channel.

Wired Connection

The boat's NMEA output is in the form of an RS232 connection, which connects directly to the PCs serial port. Most modern PCs have no serial port connection, so you will need a serial/USB adaptor, some of which seem unreliable. One proven to work with your software may be a better, though more expensive, option. A particular snag with using a serial/USB interface with Windows 2000, Windows XP and Windows Vista is that your computer is likely to think that the NMEA data are mouse inputs, so you will lose control of your cursor and be unable to use your computer! You can modify your registry (Microsoft Knowledge Base Article - Q131976 http://support.microsoft.com/default.aspx?scid=kb;[LN];Q131976), but the safest way is to ensure that you connect your computer to the live NMEA output before you switch your computer on.


Boat's D.C. supply
Inverter
Boat's instrument NMEA output
Computer power supply
Opto isolated serial connector
Serial/USB adaptor
Laptop computer

Wireless Connection

A convenient way to supply your PC with NMEA data is via a Wi-Fi connection. The NMEA data is fed to a Wi-Fi transmitter, which then transmits all the NMEA data to a Wi-Fi enabled PC. The PC can now be used anywhere on the boat, including the cockpit, and there are no problems with losing control of the mouse cursor.


Standard horizon
Port 3 out
Port 2 In
Port 1 in
Ch 1
Ch 2
Ch 3
Ch 4
Multiplexer
All required sentences in NMEA out
NMEA OUT
(Route transfer)
Wi-Fi intrface
PC
Running seaPro

Wi-Fi link between NMEA and computer

30°
3°W
30°
2°
30°
30°
50°N
50°N
C-MAP

Deduced Reckoning and Estimated Position

DR Navigation

Estimated Position

Leeway

Error in EP

EP with Multiple Headings

When aids to navigation are in short supply, due to equipment failure or lack of any aids, the navigator must resort to traditional methods of navigation.

DR Navigation

DR navigation is the method of deducing your position using only heading steered and distance run. This is 'deduced navigation' and is often known, erroneously in my opinion, as 'dead reckoning' rather than 'ded. reckoning', but anyway it's commonly called 'DR'.

If you know where you started from, the direction in which the boat has been travelling and the distance travelled, it's very easy to plot where you are on a chart. This makes no allowance for tide or wind, so is only of use in relatively calm conditions where there is little or no tide.



DR course steered – 165 (T)



DR – One arrow for water track



DR distance run – 6 miles



DR position – Positions labled

The course steered must be converted from a Compass course to a True course by applying deviation and variation. The distance run is taken from the speed log, which should have been calibrated. If it under reads, you would have travelled further than you thought and may be standing into danger.

Estimated Position

The *estimated position* (EP) is determined by applying any tidal and wind effects to the DR position. We'll look first at applying only tide.

We will need to establish in what direction and at what speed the tide has been pushing the boat for the time since we last knew our position. This is obtained from the tidal atlas. If, for instance, the last 'fix' was 1 hour ago, we will need to examine the tidal


07,14
04,08
04,09
05,10
06,13
06,12
06,13
12,24
09,18
09,19
06,13
09,19
HW - 3
C-MAP
05:30
Do not use this diagram for navigation, it's tailored to the exercise
06:30

The tidal atlas diagram from 05:30 until 06:30

mean tidal stream direction

atlas page for that particular hour. As we will be transferring the direction using our plotter, we need only 'line it up', without actually reading the direction. We will, however, need to determine its speed by noting if the day's tidal range is neaps, springs or in between.

Now we will mark the direction of the tidal flow on the chart, using the plotter. Then we can mark the distance the tide will have carried us since the last fix. The symbol for an EP is a triangle, to distinguish it from a fix.

The resulting position is our estimated position. We must mark on the chart the total distance run and the time of the EP, so that anyone looking at the chart will have all the information they need at a glance.


Fix 05:30
log 4.7
DR 06:30
log 10.7

Draw tidal stream direction


Fix 05:30
log 4.7
DR 06:30
log 10.7

Mark the length of the tidal vector


Fix 05:30
log 4.7
EP 06:30
log10.7

EP at 06:30


Fix 05:30
log 4.7
EP 06:30
log10.7

Probable ground track

If we are interested in where the boat had actually travelled over the ground since the last fix, then all we have to do is join the fix position to the EP. This is the average track that we have made good, though because it has used the average tide for the period, it won't represent the true picture exactly.

Leeway



Leeway

Wind can blow the boat sideways through the water. Boats will be affected in different ways according to their shape, both above and below the water, the direction and strength of the wind, the boat's speed and the direction of the wind relative to the boat. It's normal to allow for 0 degrees, 5 degrees or 10 degrees according to conditions. Leeway can be estimated by measuring the direction of the wake of the boat with a hand-bearing compass and comparing it with the boat's heading. The boat will be blown 'down wind' from the boats heading. It's a good idea to always sketch a wind arrow on your chart so that you apply leeway in the correct direction.

Error in EP



Actual position should be inside the circle of error, which has a radius of 10% of the distance run.

Ten percent circle of error

Because an EP relies on information that may not be as accurate as we would like, it's normal to allow for an error of up to 10% of the distance run when working out our next course. Draw a circle of radius 10% of distance run since the last reliable fix centred on the EP. Assume that your position is in a position, within the circle, nearest to danger. In other words 'navigate the circle' rather than the boat.

EP with Multiple Headings



EP with multiple headings

You don't need to work out an EP at each change of heading. Provided that you note the log distance at each change of heading, you can run a series of DR positions and insert the tide or tides at the end when you are ready.

This will not give you an indication of the ensuing ground track but give a good EP.

Standard Symbols

We must use the standard symbols for our chart work so that any other person will understand what we have plotted.

- The course through the water has *one* arrow.
- The course over the ground has *two* arrows.
- The tide has *three* arrows.

30°
3°W
30°
2°
30°
30°
50°N
50°N
Fix 05:30
log 4.7
C-MAP

Course to Steer

Where Do You Want to Go?

What Time Interval Do You Choose?

Draw in the Tide

Draw in the Boat Speed

Ground Speed

Comparison with EP

Unless you are operating in tideless and windless waters, you will need to calculate a course to steer to get from A to B. If you just steer the direct track between the two points, the wind and tide will take you in a different direction.

At the first sight, it may seem a little complicated, but practice a few times and it should become second nature. One essential reminder is that unlike estimated positions (EPs), the tide comes first, not last!

In order to strive for clarity, the first diagram shows the completed vector triangle, while the subsequent diagrams show the step-by-step method.



The vector triangle

Where Do You Want to Go?

- Draw a line from your starting point (A) to and *beyond* your destination (B). This is so that if the trip takes more than the nominal time you have *guessed*, the line will be long enough. Because this is the ground track, it must have two arrows.



Distance from 05:30 fix to destination is 8.3 miles
At 6 knots it will take about 1 hour 24 minutes

The required ground track

- Measure the distance from A to B.
- Using the probable speed through the water, calculate the estimated time taken to cover the distance A – B. Distance divided by speed gives time in hours. Multiply by 60 to get the time in minutes.
- This time is used to form the basis of the calculation of tidal effect.

What Time Interval Do You Choose?

The 'velocity' triangle you are going to construct must have all three sides representing the *same* period of time. Since we are going to start off with a guessed time, it makes sense to use an easily handled time interval, which will normally be 1 hour. However, sometimes we can use half an hour or even one and a half hours, depending on whether the triangle will fit the paper chart or not.


07,14
04,08
04,09
05,10
06,13
06,12
06,13
12,24
09,18
06,13
09,19
09,19
C-MAP
HW - 3
05:30
Do not use this diagram for navigation, it's tailored to the exercise
06:30

The tidal atlas diagram from 05:30 until 06:30

Estimate the tidal stream

Draw in the Tide

- Transfer the tidal direction from the tidal atlas to the chart, with the tidal flow (three arrows) pointing away from your starting point A.
- Estimate the tidal speed with reference to 'neaps or springs'.
- Mark the tidal vector with how far the tide will take the boat in the time interval of the triangle (C). That is for a 1-hour triangle, use 1 hour of tide; for a half-an-hour triangle, use half an hour of tide.


Fix 05:30
log 4.7

Draw direction of tidal stream



Mark length of tidal vector

Draw in the Boat Speed

- Open up your dividers (or compasses) to the distance that the boat will travel through the water in the time of the triangle. That is 1 hour of boat speed for a 1-hour triangle or half an hour of boat speed for a half-an-hour triangle.
- Mark this distance from the end of the tidal vector (C) to a position where it cuts the line joining A to B and beyond (D). Give it one arrow.


Fix 05:30
log 4.7

Mark off the distance travelled through the water in 1 hour from the end of the tidal vector to the ground track line.

The distance travelled in 1 hour

- You now have a vector triangle, one side of which has the tidal effect for a given period (1 hour or half an hour), the boat speed effect for the same time interval and therefore the third side must represent the distance travelled over the ground for that same time interval.
- The direction of the boat speed vector from the end of the tide (C) to where it cuts the ground track at (D) is the course to steer if there is no leeway.



Course to steer vector



Course to steer = 165 (T) 168 (M)

Measure course to Steer



When calculating course to steer, we will have to 'steer into wind' to make good the course we wish to steer through the water.

Leeway (CTS)

- If there is any leeway, you must steer *into* wind by the estimated leeway to ensure that the path through the water is in the direction C to D.

Ground Speed

- Measure the length of the ground speed side of the triangle (A – D). This is the distance travelled over the ground in the time interval of the triangle. If it's a 1-hour triangle, then this *is* the ground speed. If it's a half-an-hour triangle, then this is the distance travelled in half an hour, so double it to get the ground speed.
- Using this ground speed and the distance from your starting point to your destination (A – B) you can work out your estimated time of arrival (ETA). Distance divided by speed gives the elapsed time in hours. Multiply by 60 to get the time in minutes. Add this to the time you started to get your ETA.



Measure ground speed = 6.7 knots
Distance to destination = 8.3 miles
Time to destination = 1 hour 14 minutes
ETA destination = 06:44

Calculate ETA

Comparison with EP

- Have a look at the accompanying diagram 'DR and CTS' and you will see that the two triangles will bring you to the same point on the chart for the same time interval. A reassurance that the initial 'guessing' was just a tool to get the correct answer.



Our EP after 1 hour will be the same position as that found when calculating course to steer for 1 hour. This is logical as all the data are the same.

DR and CTS



Tidal Heights and Tidal Streams

Atmospheric Pressure Corrections

Tide Tables

UKHO Tidal Predictions

SHOM Tidal Predictions

Tidal Streams

It is possible to obtain heights of tide for any day using ‘online’ sources. However, the navigator is often forced into a position where there’s a need to calculate the height of tide at a particular time manually. There are a number of different methods of doing this, some more accurate than others.

Where the tidal curve is of sine waveform, the rule of twelfths, as discussed in Chapter 5, will serve well. If, however, the curve is 'skewed', that is not symmetrical, or even worse and has deformities, then better methods are required, if an accurate prediction is required. It's essential to reiterate, though, that these are only predictions. The atmospheric pressure and wind can make significant differences, and the navigator needs to exercise caution when using calculated height of tide.

Atmospheric Pressure Corrections

- A pressure of 10 millibars (hPa) above 1013 millibars will depress the tide level by 10 centimetres (4 inches).
- A pressure of 10 millibars below 1013 millibars will raise the tide level by 10 centimetres (4 inches).

Tide Tables

Tide tables are published for most major ports. These give the times and heights of high and low water for every day of the year. Where there's no commercial pressure to publish tables, tables of differences may be available so that the results obtained from the major port (standard ports) can be modified to allow calculations to be made for these 'secondary ports'.



TIME ZONE (UT)
For summer Time add ONE Hour in non-shaded areas

ENGLAND - PORTSMOUTH

TIMES AND HEIGHTS OF HIGH AND LOW WATERS

JUNE

JULY



Standard port PORTSMOUTH							
Times				Height (metres)			
High water		Low water		MHWS	MHWN	MLWN	MLWS
0000	0600	0500	1100	4.7	3.8	1.9	0.8
1200	1800	1700	2300				
Differences BEMBRIDGE HARBOUR							
+0020	0000	+0100	+0020	−1.5	−1.4	−1.3	−1.0
FORELAND (LB Slip)							
−0005	0000	+0005	+0010	+0.1	+0.1	0.0	+0.1
VENTNOR							
−0025	−0030	−0025	−0030	−0.8	−0.6	−0.2	+0.2
SANDOWN							
0000	+0005	+0010	+0025	−0.6	−0.5	−0.2	0.0

Tidal differences at Bembridge



Tidal curve for Portsmouth

UKHO Tidal Predictions

In many parts of the United Kingdom, the tidal curve is skewed, and along parts of England's south coast, the curve is far from smooth, especially due to the flow up and down the channel and the influence of the Isle of Wight.

The UKHO has developed a graphical method of finding the height of tide at any time on any day of the year. This allows for the different shapes of the tidal curve which may apply to spring and neap tides.

The easiest way to describe the use of the UKHO method is by following an example, which will entail the use of the curve for a standard port, applying the differences for a secondary port and then using the curve to find the height of tide at a particular time.

Get Today's Information

We will find the height of tide at Portsmouth at 10:53 BST on 4th July.



TIME ZONE (UT)
For summer Time add ONE Hour in non-shaded areas
ENGLAND - PORTSMOUTH
TIMES AND HEIGHTS OF HIGH AND LOW WATERS
JUNE
JULY

HW 1353 UT Ht 4.5 metres
LW 1917 UT Ht 1.1 metres

Tidal data for 4th July – Portsmouth

HW 1353 uT Ht 4.5 metres
LW 0656 uT Ht 0.9 metres
Range = 3.4 metres



Height of tide 3 hours before high water 2.6 metres

Using the tidal curve

- Look up the times and heights of HW and LW for Portsmouth on 4th July.
- Apply any correction for local time (in this case add 1 hour for BST) and write the time of HW in the HW box at the bottom of the curve.
- Fill in the other time boxes along the bottom of the curve.
- Mark the height of HW on the top tidal height scale.
- Mark the height of LW on the bottom tidal height scale.
- Join these two points with a straight line.
- The heights of HW and LW can be compared with the heights of MHWS and MHWN and of MLWS and MLWN to see what part of the curve needs to be used where there are differences between spring and neap tides.
- Draw a vertical line from the time required on the bottom of the curve (10:53, which equals 3 hours before high water) until it touches the tidal curve.
- From this point draw a horizontal line until it reaches the line joining today's HW and LW heights.
- From this point draw a vertical line to the height of tide scales at the top or bottom of the chart.

- This is the height of tide at the required time.
- The process can be reversed to find the time that the tide will be at a particular height – useful for crossing shallow water.



Or look at it this way!

Another Way of Looking at the Process

- It's not always obvious why the height of tide part of the calculation works as it does.
- If we turn the tidal curve on its side, the method becomes much more obvious.
- The chart datum is coloured red on the bottom of the chart.
- The height of today's HW is on the left and the height of LW is on the right.
- The line joining the two heights represents how the height of tide varies from HW to LW.
- Where the 'time line' hits the 'tidal height line' we can read off the height of tide.

Secondary Ports

Data are published for secondary ports to allow calculation of times and heights of HW and LW. There are complicated ways for obtaining differences at times other than those shown in the differences tables. However, I believe that for most purposes, the information may be obtained by 'inspection'.



HW 1353 LW 1917

HW 4.5 LW 1.1

Standard Port PORTSMOUTH

Times	High Water		Low Water		Height (metres) MHWS	MHWN	MLWN	MLWS
	0000	0600	0500	1100	4.7	3.8	1.9	0.8
	1200	1800	1700	2300				
Differences BEMBRIDGE HARBOUR								
	+0020	0000	+0100	+0020	−1.5	−1.4	−1.3	−1.0
FORELAND (LB Slip)								
	−0005	0000	+0005	+0010	+0.1	+0.1	0.0	+0.1
VENTNOR								
	−0025	−0030	−0025	−0030	−0.8	−0.6	−0.2	+0.2
SANDOWN								
	0000	+0005	+0010	+0025	−0.6	−0.5	−0.2	0.0

Differences

HW +0015 LW+0045 HW -1.4 LW -1.2

HW time	LW time	HW ht	LW ht
1353	1917	4.5	1.1
+0015	+0045	-1.4	-1.2
=1408 ut	=2002 ut	=3.1m	=-0.1 (drying)
=1508 bst	=2102 bst		

Tidal differences at Bembridge

- Draw an arrow between the HW times shown at approximately the correct proportion of the distance between them – for instance, if the time of HW at the standard port were 0400, the arrow would be two-thirds the distance between 0000 and 0600, that is closer to 0600 than 0000. At this stage, we must work in the same time zone as the tide table. In this case we have not yet *added* the one hour for BST.

- Note, a time difference of 0020 means 00 hours and 20 minutes, a time difference of 0115 means 01 hours and 15 minutes. There's no full stop or colon between them. 0115 does not mean 115 minutes!
- Use the same procedure for the time of LW.
- Similarly, draw arrows for the heights of HW and LW, according to their closeness to springs or neaps.
- This allows us to read off the values of the differences directly from the table.
- Apply these differences to the times and heights of HW and LW for the standard port to get the data for our secondary port
- We can now adjust for local time, that is add 1 hour for BST in this case.

SHOM Tidal Predictions

The equivalent to the UKHO in France is SHOM. SHOM offers several methods of calculating the height of tide at any particular time. The simplest is the 'rule of twelfths', which is often sufficient for curves close to being in the shape of a sine wave. Also offered is a mathematical solution able to account for any skew in the sine wave.



JUILLET 2002					AOUT 2002				
		h	min	coef			h	min	coef
1	L	9	09	53	1	J	9	47	44
		21	33	49			22	16	41
2	Ma	9	57	45	2	V	10	46	38
		22	44	43			23	21	36
3	Me	10	54	40	3	S	11	59	35
		23	23	39					
4	J	11	58	39	4	D	0	38	37
							14	53	61
5	V	0	28	40	5	L	1	51	44
		13	02	42			14	18	49
6	S	1	30	45	6	Ma	2	52	55
		13	59	49			15	13	62
7	D	2	26	53	7	Me	3	43	68
		14	50	57			16	02	74
8	L	3	15	62	8	J	4	31	80
		15	35	66			16	47	86
9	Ma	4	01	70	9	V	5	16	91
		16	19	74			17	32	96
10	Me	4	45	78	10	S	6	00	99
		17	02	81			18	16	101
11	J	5	29	84	11	D	6	43	102
		17	45	86			18	59	102
12	V	6	13	88	12	L	7	26	100
		18	29	88			19	43	97
13	S	6	58	89	13	Ma	8	11	93
		19	14	88			20	29	88
14	D	7	44	87	14	Me	8	57	82
		20	01	84			21	18	75

Copyright SHOM 2002

Neaps
Springs

An extract from the SHOM table of coefficients


Duration of tide (LW to HW)
or
Duration of tide (HW to LW)
Tidal range
8 hours
7 hours
6 hours
5 hours
4 hours
0
1
2
3
4
5
6
7
8
9
10
11
12
4 hours
3 hours
2 hours
1 hour
0
1 metre
2 metres
3 metres
4 metres
5 metres
6 metres
Time of interest before or after LW
or
Time of interest before or after HW
Height above LW
or
Height below HW

SHOM graphical method of calculating height of tide

The easiest method for boat owners is their graphical solution.

Tidal Height Coefficients

SHOM provides an annual table of tidal coefficients to distinguish how high and how low are the heights of tide relative to mean sea level (niveau moyen), which has a coefficient of 0 (zero). Spring tides have a coefficient of approximately 1.0, whilst neap tides have a coefficient of approximately 0.5. HAT and LAT are equivalent to 1.2 and zero, respectively. The diagram shows the SHOM definitions and their approximate UKHO equivalents.


PLEINE MER
d'equinoxe coef. 120
PLEINE MER
de vive-eau coef. 95
Mean high water springs
PLEINE MER
moyenne coef. 70
PLEINE MER
de mort-eau coef. 45
Mean high water neaps
20
NIVEAU MOYEN
Mean sea level
20
BASSE MER
de mort-eau coef. 45
Mean low water neaps
BASSE MER
moyenne coef. 70
BASSE MER
de vive-eau coef. 95
Mean low water springs
NIEAU ZERO
des cartes coef. 120
Chart Datum
SHOM definitions
Approximate
UKHO equivalents

SHOM definitions

SHOM Graphical Method

The graphical method can be found in 'votre livre de board', published annually by Bloc Marine(www.blocmarine.com).

The graph used for the solution is shown here and here's how to use it to calculate the height of tide on 14th July at 15:06 French Summer Time:


Duration of tide (LW to HW)
or
Duration of tide (HW to LW)
8hours 7hours 6hours 5hours 4hours
Tidal range
0 1metre 2metres 3metres 4metres 5metres 6metres 7metres 8metres 9metres 10metres 11metres 12metres
6hours 43minutes
4.6metres
B
C
A
D
2hours 20minutes
1.15m
4hours 3hours 2hours 1hour 0 1metre 2metres 3metres 4metres 5metres 6metres
Time of interest before or after LW
or
Time of interest before or after HW
Height above LW
or
Height below HW

July 14th HW 1146 (UT + 1)/6.05 meters
LW 1823 (UT + 1)/1.45 meters

MSL	3.81 meters
Spring range	5.3 meters
Neap range	2.5 millimeters

We want the height of tide at 1506 (UT+2)
Duration of tide HW to LW = 6 hours 43 minutes
Time after HW + 1246 – 1506 = 2 hours 20 minutes
Range for day = 6.05 – 1.45 = 4.6 metres
Height below HW = 1.15 metres
Therefore,

Height of tide is HW (6.05) – 1.15 = 4.9 metres at 1506 French Summer Time

SHOM graphical sulution

- Note the times and heights of HW and LW for Cherbourg.
- Calculate the time after HW that you want to know the height of tide (this can also be done relative to LW) (2 hour 20 minutes – Point A).

- Calculate the duration from HW to LW (6 hour 43 minutes – Point B).
- Calculate the range of the tide – HW ht minus LW ht (4.6 m – Point C).
- Point D shows the height of tide at 15:06 *below* the height of HW.
- If you use the time interval *before* LW, the answer will be the height of tide *above* LW.

Differences at Secondary Port

The method is almost identical to that used by UKHO. Remember to correct for local time *after* you've done all the other calculations.



NOM DU PORT	Niveau moyen m	HEURES AU PORT PRINCIPAL DE REFERENCE				HAUTEURS AU PORT PRINCIPAL DE REFERENCE			
		Pleines mers		Basses mers		Pleines mers		Basses mers	
		VE h min	ME h min	VE h min	ME h min	VE m	ME m	VE m	ME m
CHERBOURG	3,81	**9 45** **21 45**	**3 30** **15 30**	**10 00** **22 00**	**4 20** **16 20**	**6,4**	**5,0s**	**2,5**	**1,1**
			Correction aux heures			correction aux hauteurs			
Saint-Vasst-la-Hougue	4.12	+0 50	+1 20	+1 15	+1 20	+0.35	+0.45	0.0	-0.05

VE is equivalent to spring tides; ME is equivalent to neap tides

SHOM differences from standard ports

Tidal Streams

When planning a passage, plotting an estimated position, or calculating a course to steer (CTS), we will need to know the direction and speed of any tidal stream. This information is provided in 'tidal atlases', which can be bought as a separate publication, found in almanacs or on some charts.

- Each diagram of the atlas shows the average direction and speed over a period of 1 hour.
- Each diagram is for a specific '1 hour' relative to the time of high water at a reference port.
- The reference port may be for a port some distance from the area covered by the atlas.
- Do not assume that the reference port is the same port that you will use for your tidal height calculations.
- The atlas will make it clear which port is to be used.

A Tidal Atlas

Shown here is a tidal atlas for an area to the east of the Isle of Wight. The diagrams are labelled from HW −6 (hours) to HW +6 (hours). Each diagram is valid from half an hour before the stated time until half an hour after the stated time and is the averages for the whole hour. There are two values for the speed, the higher being for spring tides and the lower for neap tides. It's quite valid for the practical navigator to estimate the values in between.


Hw + 1
09:30
10:30
HW + 2
10:30
11:30
HW + 3
11:30
12:30
HW + 4
12:30
13:30
HW + 5
13:30
14:30
HW + 6
14:30
15:30

Tidal atlas – page 2


HW - 5
03:30
04:30
HW - 4
04:30
05:30
HW - 3
05:30
06:30
HW - 2
06:30
07:30
HW - 1
07:30
08:30
HW
08:30
09:00
09:30

HW is at 08:00 UTC - 09:00 BST

Label the bottom corners of each chartlet with the start and finish times for that tidal diagram, that is half an hour before until half an hour after the 'central' time of that particular tidal 'time'. This shows the time that each diagram applies to. This makes life much easier when you use the tidal atlas.

Tidal atlas – page 1

- Label the HW diagram with the time of HW.
- Label the left hand bottom corner with half an hour before HW and the right hand bottom corner with half an hour after HW.
- This gives the times between which this diagram can be used.
- All the other diagrams need to be labelled only with their 'start and finish' times.
- The diagram for HW −3 is shown.


07,14
04,08
04,09
05,10
06,13
06,12
06,13
12,24
09,18
06,13
09,19
09,19
HW - 3
C-MAP
05:30
Do not use this diagram for navigation, it's tailored to the exercise.
06:30

The tidal atlas diagram from 05:30 until 06:30

Tidal Diamonds

Many charts have 'tidal diamonds' marked on them and a table showing the value of the direction and speeds of the tides at these discrete points. They are fine for estimating the tide at a particular point for such operations as diving and fishing, but are cumbersome to use for planning and plotting purposes.



Hours		◇A 50°13'.00N 2°55'00W			◇B 49°38'.00N 3°22'00W			◇C 49°10'.00N 4°37'00W			
◇ Geographical position		Directions of streams (degrees)	Rates at spring tides (knots)	Rates at neap tides (knots)							
Before high water 6	−6	074	0.9	0.4	064	1.3	0.7	079	0.8	0.4	−6
5	−5	082	1.5	0.7	065	2.3	1.2	085	2.7	1.3	−5
4	−4	085	2.0	1.0	067	2.7	1.3	083	2.8	1.4	−4
3	−3	089	2.1	1.1	070	2.3	1.1	082	1.7	0.8	−3
2	−2	090	1.6	0.8	071	1.5	0.8	083	0.6	0.3	−2
1	−1	096	0.7	0.3	062	0.4	0.2	084	0.4	0.2	−1
High water	0	256	0.6	0.3	256	1.2	0.6	258	0.9	0.5	0
After high water 1	+1	266	1.8	0.9	251	2.2	1.1	268	2.3	1.2	+1
2	+2	265	2.1	1.0	246	2.6	1.3	266	2.7	1.4	+2
3	+3	264	2.2	1.1	244	2.2	1.1	262	2.8	1.4	+3
4	+4	267	1.5	0.7	248	1.6	1.8	264	2.0	1.0	+4
5	+5	271	0.4	0.2	259	0.4	0.2	270	0.8	0.5	+5
6	+6	062	0.5	0.3	062	0.9	0.4	070	0.4	0.2	+6

Tidal stream data for each hour before and after the time of high water

The lettered diamonds indicate the position for each set of tidal stream data.



The table of tidal stream data

Tidal diamonds



Date

Tidal port

HW time

Height

HW

LW

Range

Mean Sp range

Mean Np range

Tidal diamond ◇

		Set (T)	Drift kts Sp	Np	Use	(½ hr)
	−6					
	−5					
	−4					
	−3					
	−2					
− ½ hour	−1					
+ ½ hour	HW					
	+1					
	+2					
	+3					
	+4					
	+5					
	+6					

Tidal diamond pro-forma

Just as when using a tidal atlas, each tabulated value for a diamond is the average for the 1-hour period. However, there's insufficient room on the tables to label the values with a time. I've found that many people make mistakes when working out which 'hour' to use, so you may find it helpful to use a pro forma to do this. You can print off a proforma from Wiley Nautical's website www.wileynautical.co.uk.

You don't need to fill in all the blanks, just those that you need, as shown. As before, the actual speeds, if not neaps or springs can be estimated.



Hours		◇A 50°13'.00N 2°55'00W			◇B 49°38'.00N 3°22'00W			◇C 49°10'.00N 4°37'00W			
◇ Geographical Position		Directions of streams (degrees)	Rates at spring tides (knots)	Rates at neap tides (knots)							
Before high water 6	−6	074	0.9	0.4	064	1.3	0.7	079	0.8	0.4	−6
5	−5	082	1.5	0.7	065	2.3	1.2	085	2.7	1.3	−5
4	−4	085	2.0	1.0	067	2.7	1.3	083	2.8	1.4	−4
3	−3	089	2.1	1.1	070	2.3	1.1	082	1.7	0.8	−3
2	−2	090	1.6	0.8	071	1.5	0.8	083	0.6	0.3	−2
1	−1	096	0.7	0.3	062	0.4	0.2	084	0.4	0.2	−1
High water	0	256	0.6	0.3	256	1.2	0.6	258	0.9	0.5	0
After high water 1	+1	266	1.8	0.9	251	2.2	1.1	268	2.3	1.2	+1
2	+2	265	2.1	1.0	246	2.6	1.3	266	2.7	1.4	+2
3	+3	264	2.2	1.1	244	2.2	1.1	262	2.8	1.4	+3
4	+4	267	1.5	0.7	248	1.6	1.8	264	2.0	1.0	+4
5	+5	271	0.4	0.2	259	0.4	0.2	270	0.8	0.5	+5
6	+6	062	0.5	0.3	062	0.9	0.4	070	0.4	0.2	+6



Date: *4th July*

Tidal port: *DOVER*

HW time: *14:28 bs*

Height

HW *6.5*

LW *1.1*

Range *5.4*

6.0 Mean Sp range

3.2 Mean Np range

Tidal diamond ◇A

			Set (T)	Drift (kts) Sp	Np	Use	(½ hr)
	08:00						
	09:00	−6					
	10:00	−5					
	11:00	−4	085	2.0	1.0	1.8	0.9
	12:00	−3	089	2.1	1.1	1.9	0.9
	13:00	−2					
− ½ hour	14:00	−1					
14:28	15:00	HW					
+ ½ hour	16:00	+1					
	17:00	+2					
	18:00	+3					
	19:00	+4					
	20:00	+5					
	21:00	+6					

Tidal diamond calculations



Tidal Planning and Plotting

A Long Passage Using a Single CTS

Where will the Tide Take You?

An open water passage will require the use of a number of tidal diagrams. You could, of course, calculate a new course to steer every hour, but if the passage is to be 'across tide' this is a very inefficient way to work. You will always be pointing into tide and a 12 hour passage could easily take an hour or more to complete using this strategy.



Passage chart

A Long Passage Using a Single CTS

On a long passage leg, a single course to steer can be calculated using many tidal vectors all in one operation and this is much more efficient.

- Draw ground track to destination.
- Measure ground distance.
- Estimate passage time.
- Label tidal stream atlas with times from the tide table.


HW - 5
HW - 4
HW + 1
HW + 2
HW - 3
HW - 2
HW + 3
HW + 4
HW - 1
HW
HW + 5
HW + 6
Standard Port Dover
High water Dover 13:28
Channel tides page 1
Channel tides page 2

- Draw ground track on tidal atlas diagram.
- Mark a strip of paper with hourly progress marks and label the ETA at each point.


START
08:30
09:30
10:30
11:30
12:30
13:30
14:30
15:30
16:30
17:30
END

- Moving from one tidal atlas diagram to the next, estimate the tidal current at each point.


HW - 4
09:00
10:00
082/1.5
Tide at 09:30
HW - 3
11:00
087/2.5
Tide at 10:30
HW - 2
12:00
087/2.5
Tide at 11:30
HW - 1
13:00
093/1.6
Tide at 12:30


HW
13:00
13:28
14:00
192/0.8
Tide at 13:30
HW + 1
15:00
277/1.1
Tide at 14:30
HW + 2
16:00
266/2.5
Tide at 15:30
HW + 3
17:00
269/2.8
Tide at 16:30
HW + 4
18:00
269/2.2
Tide at 17:30



These tidal vectors should have three arrows each, but for the sake of clarity, I've used only one

Ten tidal vectors

- Mark in the tidal vectors at the start point on the passage chart.
- Measure the estimated passage time from the last tidal vector to where it cuts the ground track.


Ten hours of boat speed

Mark off water distance covered in ten hours


CTS =184 (T)

Course to steer

- This is the single course to steer.

Where will the Tide Take You?

It seems common sense to enquire where the boat will travel on its way to its destination. Indeed, how can you monitor the boat's progress if you don't know where it's supposed to be?

This is easily accomplished by plotting *estimated positions* along the way before you even start. This has the added advantage that should you have to resort to plotting EPs, it's already been done at your leisure. So how do you accomplish that?


Passage chart

- Draw your direct track on your passage chart.
- Mark hourly progress points on the chart.



- Draw lines perpendicular to the direct track long enough to accommodate the maximum tidal effect.
- Draw a track grid parallel to direct track with lines at 1 nautical mile spacing. Theoretically, this grid should be parallel to the


Draw lines for the expected progress each hour

CTS, but in reality it's easier to use the direct track, which also makes the grid useful for plotting GPS positions on passage.



Draw parallel 'cross-track error' lines

- Make a table of running tidal offsets for each hour.



Direction	Speed	Offset
076	1.0	1.0
082	1.5	2.5
087	2.5	5.0
087	2.5	7.5
093	1.6	9.1
192	0.8	9.1
277	1.1	8.0
266	2.5	5.5
269	2.8	2.7
269	2.2	0.5

Tidal offsets



Mark in tidal offsets along route

- Mark the offsets on the grid.



Draw ground track though tidal offsets

- Joint the offsets with a continuous line.
- This line is the planned ground track.



Planned ground track using single CTS

- When you steer the single CTS, you should follow this planned ground track. Any error is the error compared with the planned ground track, not compared with the direct track.
- If you are monitoring GPS cross-track error, the error should mirror the running tidal offsets, not remain at zero.

Credits

It would not have been possible to illustrate this book in the way that I had envisaged without the charts and simulations made possible by the cooperation of C-Map, Euronav, Lightmaster Software and Standard Horizon.

Charts Have Been Drawn Using Software Supplied by

C-Map with the kind cooperation of Mr Paul Sumpner, MD of C-Map, UK.

Euronav (seaPro) with the kind cooperation of Dr Brian Morris, MD.

Radar Simulations

Lightmaster Software with the kind cooperation of Mr Martin Quaintance FRIN.

Chartplotter Simulations

C-Map with the kind cooperation of Mr Paul Sumpner, MD of C-Map, UK.

Standard Horizon with the kind cooperation of Yeasu, UK.

'Space' Pictures

Some of the diagrams use images of the earth courtesy of NASA and this imagery may be viewed online at Visible Earth. (http://visibleearth.nasa.gov/)

World Currents Chart

US Naval Laboratory

Ocean currents – 🅮 *This image is a copy of* ***ocean_currents_1943.jpg****, a map from the map collection of the* Perry-Castañeda Library (PCL) of the University of Texas at Austin. *According to the FAQs it is in the* ***public domain***.

Tidal Height and Tidal Currents

Diagrams and data for UK – UKHO and Nautical Data Ltd.
Diagrams and data for France – SHOM and Bloc Marine.
Diagrams and data for USA – NOAA.



Standard Port PORTSMOUTH

Times					**Height (metres)**		
High	Water	Low	Water	MHWS	MHWN	MLWN	MLWS
0000	0600	0500	1100	4.7	3.8	1.9	0.8
1200	1800	1700	2300				
Differences BEMBRIDGE HARBOUR							
+0020	0000	+0100	+0020	-1.5	-1.4	-1.3	-1.0
FORELAND (LB Slip)							
-0005	0000	+0005	+0010	+0.1	+0.1	0.0	+0.1
VENTNOR							
-0025	-0030	-0025	-0030	-0.8	-0.6	-0.2	+0.2
SANDOWN							
0000	+0005	+0010	+0025	-0.6	-0.5	-0.2	0.0

Tidal differences at Bembridge


Overhead power cable
Charted vertical clearance
Charted vertical clearance (black)
Safe vertical clearance (Magenta)*
Charted elevation
HAT
MHWS
MHWN
Charted HW (coast) line
MSL
Land survey datum
Sea surface at any time
MLWN
MLWS
Height of tide
Observed depth (sounding)
Drying height
CD (usually LAT on Admiralty charts)
Charted depth
Charted LW (drying) line

* The safe vertical clearance to avoid risk of electrical discharge, has been obtained by applying an adjustment to the physical vertical clearance of the cable above HAT. The deduction is variable and depends on the transmission line voltage.

Check on the chart you are using that these definitions apply to that particular chart

Tide levels and height references

Tides are UT + 1
(French standard time)



JUILLET 2002

	Heures h	min	Haut m
13 S	5	21	**1,05**
	11	00	**6,1**
	17	37	**1,3**
	23	11	**6,3**
14 D	6	06	**1,05**
	11	46	**6,05**
	18	23	**1,45**
	23	58	**6,2**
15 L	6	53	**1,15**
	12	33	**5,9**
	19	12	**1,6**

For French Summer Time
add 1 hour

Extract from Cherbourg
tide tables


5
0
Height
datum
CD
5m

Rock awash at the level of Chart Datum


5
(1.3)
(1.8)
(2.6)
3.6
Height
datum
CD
5m

Rock which covers and uncovers, height above Chart Datum, where known


(3.6)
4.2
(1.4)
0
Height datum
CD

Rock which does not cover, height above chart datum



Clearance under a bridge



Clearance under a cable



Safe clearance under a power transmission cable where published otherwise the actual clearance is shown in black

Vertical clearances



July 14th HW 1146 (UT + 1)/6.05 meters
LW 1823 (UT + 1)/1.45 meters

MSL	3.81 meters
Spring range	5.3 meters
Neap range	2.5 millimeters

We want the height of tide at 1506 (UT+2)
Duration of tide HW to LW = 6 hours 43 minutes
Time after HW + 1246 – 1506 = 2 hours 20 minutes
Range for day = 6.05 – 1.45 = 4.6 metres
Height below HW = 1.15 metres
Therefore,

Height of tide is HW (6.05) – 1.15 = 4.9 metres at 1506 French Summer Time

SHOM graphical sulution



SHOM graphical method of calculating height of tide



NOM DU PORT	Niveau moyen m	HEURES AU PORT PRINCIPAL DE REFERENCE				HAUTEURS AU PORT PRINCIPAL DE REFERENCE			
		Pleines mers		Basses mers		Pleines mers		Basses mers	
		VE	ME	VE	ME	VE	ME	VE	ME
		h min	h min	h min	h min	m	m	m	m
CHERBOURG	3,81	**9 45** **21 45**	**3 30** **15 30**	**10 00** **22 00**	**4 20** **16 20**	**6,4**	**5,05**	**2,5**	**1,1**
			Correction aux heures			correction aux hauteurs			
Saint-Vasst-la-Hougue	4.12	+0 50	+1 20	+1 15	+1 20	+0.35	+0.45	0.0	-0.05

VE is equivalent to Spring tides; ME is equivalent to Neap tides

SHOM differences from standard ports


Neaps
Springs

JUILLET 2002					AOUT 2002				
		h	min	coef			h	min	coef
1	L	9	09	**53**	**1**	J	9	47	**44**
		21	33	**49**			22	16	**41**
2	Ma	9	57	**45**	**2**	V	10	46	**38**
		22	44	**43**			23	21	**36**
3	Me	10	54	**40**	**3**	S	11	59	**35**
		23	23	**39**					
4	J	11	58	**39**	**4**	D	0	38	**37**
							14	53	**61**
5	V	0	28	**40**	**5**	L	1	51	**44**
		13	02	**42**			14	18	**49**
6	S	1	30	**45**	**6**	Ma	2	52	**55**
		13	59	**49**			15	13	**62**
7	D	2	26	**53**	**7**	Me	3	43	**68**
		14	50	**57**			16	02	**74**
8	L	3	15	**62**	**8**	J	4	31	**80**
		15	35	**66**			16	47	**86**
9	Ma	4	01	**70**	**9**	V	5	16	**91**
		16	19	**74**			17	32	**96**
10	Me	4	45	**78**	**10**	S	6	00	**99**
		17	02	**81**			18	16	**101**
11	J	5	29	**84**	**11**	D	6	43	**102**
		17	45	**86**			18	59	**102**
12	V	6	13	**88**	**12**	L	7	26	**100**
		18	29	**88**			19	43	**97**
13	S	6	58	**89**	**13**	Ma	8	11	**93**
		19	14	**88**			20	29	**88**
14	D	7	44	**87**	**14**	Me	8	57	**82**
		20	01	**84**			21	18	**75**

Copyright SHOM 2002

An extract from the SHOM table of coefficients


SOURCE DATA
Admiralty Surveys
a 1990 1:25 000
b 1960-84 1:5000-1:20 000
c 1859-66 1:12 255-1:18 360 (leadline)
d 1859-69 1:73 000 (leadline)
e 1830-81 1:117 480-1:520 000 (leadline)
f 1936-68 Lines of soundings
French Government Charts
g 1928-90 1:10 000-1:150 000
Compiled mainly from 19th
century leadline surveys
Aerial photography
h 1980
65
Pors Moguer
Spire
Plouha
.106
3°00'
50'
40'
30'
20'
10'
2°00'
49° 00'
h & g
48°32'·77N
40'
35'
05'
3°00'
55'

UK Hydrographic Office source diagram


PLEINE MER
d'equinoxe coef. 120
PLEINE MER
de vive-eau coef. 95
Mean high water springs
PLEINE MER
moyenne coef. 70
PLEINE MER
de mort-eau coef. 45
Mean high water neaps
20
NIVEAU MOYEN
Mean sea level
20
BASSE MER
de mort-eau coef. 45
Mean low water neaps
BASSE MER
moyenne coef. 70
BASSE MER
de vive-eau coef. 95
Mean low water springs
NIEAU ZERO
des cartes coef. 120
Chart Datum
SHOM definitions
Approximate
UKHO equivalents

SHOM definitions



TIME ZONE (UT)

For summer Time add ONE Hour in **non-shaded areas**

ENGLAND - PORTSMOUTH

Times and heights of high and low waters

JUNE	Time	m		Time	m	JULY	Time	m		Time	m
16	0510	0.8	**1**	0456	1.1	**16**	0005	4.6	**1**	0019	4.6
	1202	4.7		1147	4.4		0546	0.8		0601	0.7
SA	1729	0.9	SU	1714	1.2	M	1241	4.6	W	1254	4.7
○				2355	4.4		1802	1.0		1820	0.8
17	0016	4.7	**2**	0535	1.0	**17**	0048	4.5	**2**	0101	4.6
	0557	0.8		1228	4.5		0626	0.8		0641	0.6
SU	1252	4.7	M	1154	1.1	TU	1322	4.6	TH	1335	4.7
	1815	1.0					1843	1.0		1901	0.8
18	0102	4.6	**3**	0034	4.5	**18**	0127	4.4	**3**	0143	4.6
	0642	0.8		0615	0.9		0704	0.9		0722	0.6
M	1339	4.6	TU	1310	4.5	W	1401	4.5	F	1416	4.7
	1900	1.1		1835	1.1		1920	1.1		1943	0.8
19	0147	4.4	**4**	0115	4.4	**19**	0204	4.3	**4**	0226	4.5
	0725	1.0		0656	0.9		0739	1.0		0803	0.8
TU	1426	4.5	W	1353	4.5	TH	1437	4.5	SA	1458	4.6
	1945	1.3		1917	1.1		1956	1.2		2027	1.0
20	0231	4.3	**5**	0158	4.4	**20**	0240	4.2	**5**	0311	4.4
	0807	1.1		0739	0.9		0812	1.2		0848	1.0
W	1511	4.4	TH	1437	4.5	F	1511	4.3	SU	1543	4.5
	2029	1.4		2002	1.1		0232	1.4	◑	2116	1.2



Tidal curve for Portsmouth

Portinatx, Sant Joan de Labritja, Spain
Google

Sourced: Google Maps^{TM} mapping service


OCEAN CURRENTS AND SEA ICE
3
Permanent polar pack ice
CURRENTS
SEA ICE


5
0
Height datum
CD
5m

Underwater rock over which the depth is unknown, but which is considered dangerous to surface navigation

Lifeboats

'Flat calm or force 10. I always wear one.'

Whether they're training or out on a shout, RNLI crew members always wear lifejackets. It's a rule informed by years of experience. They know that, whatever the weather, the sea's extremely unpredictable – and can turn at a moment's notice. They see people caught out all the time. People who've risked, or even lost their lives as a result. The fact is, a lifejacket will buy you vital time in the water – and could even save your life. But only if you're wearing it.

For advice on choosing a lifejacket and how to wear it correctly, call us on 0800 328 0600 (UK) or 1800 789 589 (RoI) or visit our website rnli.org.uk/seasafety/lifejackets

LIFEJACKETS

Useless unless worn

A charity registered in England, Scotland and the Republic of Ireland.

Plants that Contain DMT

*The percentages of alkaloid content in plants vary greatly from one plant to another depending upon growing conditions, time of harvest, location, etc. *

	Arundo donax	Entire Plant contains 5-MeO-DMT (Shulgin, TIHKAL) Flowers contain DMT, 5-MeO-DMT, and 5-MeO-NMT (Shulgin, TIHKAL) Roots contain DMT, 5-MeO-DMT, 5-MeO-NMT, Bufotenine, bufotenidine, dehydrobufotenidine (Shulgin, TIHKAL)
	Desmanthus Illinoensis	Root contains DMT - 0.200% (Ott) Root Bark contains DMT - 0.340% (Ott)

	Phalaris arundinacea	Leaves of contain DMT, 5-MeO-DMT, and related compounds (Smith 1977)
	Phalaris aquatica syn. Phalaris tuberosa	Leaves and seedlings contain DMT, 5-MeO-DMT, and related compounds (Smith 1977) DMT - 0.100% (erowid) 5-MeO-DMT - 0.022% (erowid) 5-OH-DMT - 0.005% (erowid)

	Phragmites australis	DMT in roots (Ott)

	Delosperma acuminatum	DMT, 5-MEO-DMT (Trout's Notes)

	Delosperma cooperi	DMT, 5-MEO-DMT (Trout's Notes)
	Delosperma ecklonis	DMT (Trout's Notes)
	Delosperma esterhuyseniae	DMT (Trout's Notes)
	Delosperma hallii	5-MEO-DMT (Trout's Notes)
	Delosperma harazianum	DMT, 5-MEO-DMT (Trout's Notes)
	Delosperma harazianum Shibam	DMT (Trout's Notes)
	Delosperma hirtum	DMT (Trout's Notes)
	Delosperma lydenbergense	DMT, 5-MEO-DMT (Trout's Notes)
	Delosperma nubigenum	5-MEO-DMT

		(Trout's Notes)
	Delosperma pageanum	DMT, 5-MEO-DMT (Trout's Notes)
	Delosperma pergamentaceum	Traces of DMT (Trout's Notes)
	Delosperma tradescantioides	DMT (Trout's Notes)
	Petalostylis cassioides	0.4-0.5% tryptamine, DMT, etc. in leaves and stems (Johns et al 1966)

	Acacia acuminata	Up to 1.5% alkaloids, mainly consisting of tryptamine in leaf (Lycaeum)

	Acacia alpina	Active principles in leaf (M.Bock)
	Acacia angustifolia	Psychoactive Tryptamines (Rätsch 2004)
	Acacia angustissima	β-methyl-phenethylamine (Glasby 1991) NMT and DMT in leaf, 1.1-10.2 ppm (McSweeney et al. 2005)
	Acacia auriculiformis	5-MeO-DMT in stem bark (Lycaeum)
	Acacia baileyana	0.02% tryptamine and β-carbolines, in the leaf, Tetrahydroharman (Ott)
	Acacia berlandieri	Amphetamine, Methamphetamine, N,N-Dimethylamphetamine, 4-Methoxyamphetamine, 4-Hydroxyamphetamine (Shulgin 2001) DMT and others (Phytochem. 1998)
	Acacia catechu	DMT and other tryptamines in leaf, bark (Trout's Notes)
	Acacia colei	DMT (Dr. Karl and abc.net.au 2005)
	Acacia complanata	0.3% alkaloids in leaf and stem, N-methyl-tetrahydroharman with traces of tetrahydroharman (Johns et al. 1966)
	Acacia confusa	N-chloromethyl-N,N-dimethyltryptamine, N-methyltryptamine, N,N-dimethyltryptamine, and

		N,N-dimethyltryptamine-N-oxide (Quinn et al. 2006)
	Acacia cultriformis	Tryptamine in the leaf and stem (Trout's Notes)
	Acacia farnesiana	Tryptamines and phenethylamines (Lyceaum) N-Methyl-Beta-Phenethylamine (Duke 1992)
	Acacia laeta	DMT in the leaf (Trout's Notes)
	Acacia longifolia	0.2% tryptamine in bark, leaves, some in flowers, phenylethylamine in flowers (Hegnauer 1994) DMT in plant (Lyceaum)
	Acacia maidenii	Bark of A. maidenii contains 0.6% of N-methyltryptamine and DMT in the proportions approx. 2:3 (Fitzgerald & Sioumis 1965)
	Acacia melanoxylon	DMT in the bark and leaf, less than 0.02% total alkaloids (Hegnauer 1994)

	Acacia mellifera	DMT in the leaf (Trout's Notes)
	Acacia nilotica	DMT in the leaf (Trout's Notes)
	Acacia obtusifolia	0.4 to 0.5 % DMT in the dried bark (Csiro 1990)
	Acacia oerfota	Less than 0.1% DMT in leaf (Ott)
	Acacia phlebophylla	0.3% DMT in leaf, NMT (Trout's Notes)
	Acacia podalyriaefolia	Tryptamine in the leaf (Trout's Notes) 0.5% to 2% DMT in fresh bark, phenethylamine trace amounts (Hegnauer 1994)
	Acacia polyacantha	DMT in leaf (Trout's Notes)
	Acacia retinodes	DMT and MMT (www.factorey.ch/Eins.htm) less than 0.02% total alkaloids found (Hegnauer 1994)
	Acacia rigidula	DMT, NMT, tryptamine, amphetamines, mescaline, nicotine and others (Phytochem. 1998)
	Acacia sieberiana	DMT in the leaf (Trout's Notes)
	Acacia verek	Psychoactive (Rätsch 2004)
	Acacia vestita	Tryptamine, in the leaf and stem (Trout's Notes)

		less than 0.02% total alkaloids (Hegnauer 1994)

	Anadenanthera colubrina	seed pods contain dimethyltryptamine and the seeds bufotenin, bufotenin oxide, and oxide of dimethyltryptamine (GRANIER-DOYEUX 1965) Leaves, Bark, and Seeds contain DMT, 5-MeO-DMT and related compounds (Schultes 1977)
	Anadenanthera peregrina	seed pods contain dimethyltryptamine and the seeds bufotenin, bufotenin oxide, and oxide of dimethyltryptamine (GRANIER-DOYEUX 1965) Leaves, Bark, and Seeds contain DMT, 5-MeO-DMT and related compounds (Schultes 1977)
	Anadenanthera macrocarpa	seed pods contain dimethyltryptamine and the seeds bufotenin, bufotenin oxide, and oxide of dimethyltryptamine

		(GRANIER-DOYEUX 1965)
	Desmodium caudatum	Roots: 0.087% DMT, Bufotenine-N-oxide 0.03% (Trout's Notes)
	Desmodium gangeticum	DMT, 5-MEO-DMT, whole plant, roots, stems, leaves (Ott)
	Desmodium gyrans	DMT, 5-MEO-DMT, leaves, roots (Ott)
	Desmodium pulchellum	DMT, 5-MEO-DMT, whole plant, roots, stems, leaves, flowers (Ott)
	Desmodium racemosum	5-MEO-DMT (Ott)
	Desmodium triflorum	DMT-N-oxide, roots (Ott)
	Lespedeza bicolor var. japonica	DMT, 5-MEO-DMT in leaves and root bark (Ott)

	Mimosa Hostilis	Root Bark contains DMT - 0.31% to 0.57% (Schultes 1977)
	Mimosa scabrella	DMT in bark (Ott)
	Mimosa verrucosa	DMT (Schultes 1969)
	Mucuna pruriens	leaves, seeds, stems and roots contain L-Dopa, Serotonin, 5-HTP, and Nicotine, as well as N,N-DMT, Bufotenine, and 5-MeO-DMT (Erowid)
	Petalostylis labicheoides var. casseoides	DMT in leaves and stems (Ott)
	Diplopterys cabrerana	1.3% DMT (Shulgin, TIHKAL) Contains DMT (Ott)

	Horsfieldia superba	5-MeO-DMT and beta-carbolines (Jossang et al. 1991)
	Iryanthera ulei	5-MEO-DMT in bark (Ott)
	Osteophloem platyspermum	DMT, 5-MEO-DMT in bark (Ott)

	Virola calophylla	Leaves 0.149% DMT (Ott)
	Virola carinata	DMT in leaves (Ott)
	Virola divergens	DMT in leaves (Ott)
	Virola elongata	DMT, 5-MEO-DMT in bark and leaves (Ott)
	Virola melinonii	DMT in bark (Ott)
	Virola multinervia	DMT, 5-MEO-DMT in bark and leaves (Ott)

flowering branch
Virola calophylloidea
flower cluster, enlarged
flowering branch
young fruit
Virola calophylla
flower buds, enlarged
Virola theiodora
flowering branch
flower cluster, enlarged

	Virola pavonis	DMT in leaves (Ott)
	Virola peruviana	DMT, 5-MEO-DMT in bark (Ott)
	Virola rufuta	Alkaloids in bark and root, 95% of which is 5-MeO-DMT (Shulgin, TIHKAL)
	Virola sebifera	DMT in bark (Ott)
	Virola theiodora	DMT, 5-MEO-DMT in bark, roots, leaves and flowers (Ott)
	Virola venosa	DMT, 5-MEO-DMT in roots and leaves (Ott)

	Psychotria carthaginensis	0.2% average DMT in dried leaves (Ott)
	Psychotria viridis	Leaves contain DMT - 0.10% to 0.66% (McKenna, 1984)

Arundo donax

Entire Plant contains 5-MeO-DMT (Shulgin, TIHKAL)

Flowers contain DMT, 5-MeO-DMT, and 5-MeO-NMT (Shulgin, TIHKAL)

Roots contain DMT, 5-MeO-DMT, 5-MeO-NMT, Bufotenine, bufotenidine, dehydrobufotenidine (Shulgin, TIHKAL)

Desmanthus Illinoensis

Root contains DMT - 0.200% (Ott)

Root Bark contains DMT - 0.340% (Ott)

Phalaris arundinacea

Leaves of contain DMT, 5-MeO-DMT, and related compounds (Smith 1977)

Phalaris aquatica

syn.

Phalaris tuberosa

Leaves and seedlings contain DMT, 5-MeO-DMT, and related compounds (Smith 1977)

DMT - 0.100% (erowid)

5-MeO-DMT - 0.022% (erowid)

5-OH-DMT - 0.005% (erowid)

Phragmites australis

DMT in roots (Ott)

Delosperma acuminatum

DMT, 5-MEO-DMT (Trout's Notes)

Delosperma cooperi

DMT, 5-MEO-DMT (Trout's Notes)

Delosperma ecklonis



DMT (Trout's Notes)

Delosperma esterhuyseniae



Delosperma esterhuyseniae

DMT (Trout's Notes)

Delosperma hallii 5-MEO-DMT (Trout's Notes)

Delosperma harazianum DMT, 5-MEO-DMT (Trout's Notes)

Delosperma harazianum
Shibam DMT (Trout's Notes)

Delosperma hirtum DMT (Trout's Notes)

Delosperma lydenbergense

DMT, 5-MEO-DMT (Trout's Notes)

Delosperma nubigenum 5-MEO-DMT (Trout's Notes)

Delosperma pageanum DMT, 5-MEO-DMT (Trout's Notes)

Delosperma pergamentaceum Traces of DMT (Trout's Notes)

Delosperma tradescantioides

DMT (Trout's Notes)

Petalostylis cassioides

0.4-0.5% tryptamine, DMT, etc. in leaves and stems (Johns et al 1966)

Acacia acuminata Up to 1.5% alkaloids, mainly consisting of tryptamine in leaf (Lycaeum)

Acacia alpina Active principles in leaf (M.Bock)

Acacia angustifolia Psychoactive Tryptamines (Rätsch 2004)

Acacia angustissima

β-methyl-phenethylamine (Glasby 1991)

NMT and DMT in leaf, 1.1-10.2 ppm (McSweeney et al. 2005)

Acacia auriculiformis

5-MeO-DMT in stem bark (Lycaeum)

Acacia baileyana

0.02% tryptamine and β-carbolines, in the leaf, Tetrahydroharman (Ott)

Acacia berlandieri

Amphetamine, Methamphetamine, N,N-Dimethylamphetamine, 4-Methoxyamphetamine, 4-Hydroxyamphetamine (Shulgin 2001)

DMT and others (Phytochem. 199😎

Acacia catechu

DMT and other tryptamines in leaf, bark (Trout's Notes)

Acacia caven

Psychoactive

Acacia colei DMT (Dr. Karl and abc.net.au 2005)

Acacia constricta

β-methyl-phenethylamine[12]

Acacia complanata 0.3% alkaloids in leaf and stem, N-methyl-tetrahydroharman with traces of tetrahydroharman (Johns et al. 1966)

Acacia confusa

N-chloromethyl-N,N-dimethyltryptamine, N-methyltryptamine, N,N-dimethyltryptamine, and N,N-dimethyltryptamine-N-oxide (Quinn et al. 2006)

Acacia cornigera

Psychoactive,[8] Tryptamines[27]

Acacia cultriformis

Tryptamine in the leaf and stem (Trout's Notes)

Acacia farnesiana

Tryptamines and phenethylamines (Lyceaum)

N-Methyl-Beta-Phenethylamine (Duke 1992)

Acacia filiciana Psychoactive

Acacia floribunda Tryptamine, phenethylamine,[33] in flowers[15] other tryptamines,[34] phenethylamines

Acacia georginae Psychoactive,[8] plus deadly toxins

Acacia greggii

N-methyl-β-phenethylamine,[12] phenethylamine[36]

Acacia harpophylla Phenethylamine, hordenine at a ratio of 2:3 in dried leaves, 0.6% total[6]

Acacia holoserica Hordenine, 1.2% in bark[6]

Acacia horrida

Psychoactive

Acacia implexa

Psychoactive

Acacia karroo
Psychoactive

Acacia kempeana
Psychoactive

Acacia kettlewelliae
1.5[6]-1.88%[38] alkaloids, 92% consisting of phenylethylamine.[6] 0.9% N-methyl-2-phenylethylamine found a different time

Acacia laeta DMT in the leaf (Trout's Notes)

Acacia lingulata
Psychoactive

Acacia longifolia

0.2% tryptamine in bark, leaves, some in flowers, phenylethylamine in flowers (Hegnauer 1994)

DMT in plant (Lyceaum)

Acacia macradenia
Tryptamine

Acacia maidenii

Bark of A. maidenii contains 0.6% of N-methyltryptamine and DMT in the proportions approx. 2:3 (Fitzgerald & Sioumis 1965)

Acacia mangium

Psychoactive

Acacia melanoxylon

DMT in the bark and leaf, less than 0.02% total alkaloids (Hegnauer 1994)

Acacia mellifera

DMT in the leaf (Trout's Notes)

Acacia nilotica


Tab. 393.
c
a
b
Mimosa nilotica. L.

DMT in the leaf (Trout's Notes)

Acacia obtusifolia 0.4 to 0.5 % DMT in the dried bark (Csiro 1990)

Acacia oerfota Less than 0.1% DMT in leaf (Ott)

Acacia penninervis
Psychoactive

Acacia phlebophylla

0.3% DMT in leaf, NMT (Trout's Notes)

Acacia platensis
Psychoactive

Acacia podalyriaefolia

Tryptamine in the leaf (Trout's Notes)

0.5% to 2% DMT in fresh bark, phenethylamine trace amounts (Hegnauer 1994)

Acacia polyacantha



DMT in leaf (Trout's Notes)

Acacia pycantha

Psychoactive,[8] but less than 0.02% total alkaloids

Acacia retinodes

DMT and MMT (www.factorey.ch/Eins.htm)

less than 0.02% total alkaloids found (Hegnauer 1994)

Acacia roemeriana
β-methyl-phenethylamine

Acacia rigidula DMT, NMT, tryptamine, amphetamines, mescaline, nicotine and others (Phytochem. 199😎

Acacia salicina

Psychoactive[8][9] Ash used in Pituri.

Acacia sassa
Psychoactive

Acacia schaffneri

β-methyl-phenethylamine, Phenethylamine[36] Amphetamines and mescaline also found

Acacia schottii
β-methyl-phenethylamine

Acacia senegal
DMT, in the leaf

Acacia simplex

DMT and NMT, in the leaf, stem and trunk bark, 0.81% DMT in bark, MMT

Acacia taxensis
β-methyl-phenethylamine

Acacia tenuifolia
Psychoactive

Acacia tortilis

DMT, NMT, and other tryptamines

Acacia sieberiana DMT in the leaf (Trout's Notes)

Acacia verek Psychoactive (Rätsch 2004)

Acacia vestita Tryptamine, in the leaf and stem (Trout's Notes)

less than 0.02% total alkaloids (Hegnauer 1994)

Anadenanthera colubrina

seed pods contain dimethyltryptamine and the seeds bufotenin, bufotenin oxide, and oxide of dimethyltryptamine (GRANIER-DOYEUX 1965)

Leaves, Bark, and Seeds contain DMT, 5-MeO-DMT and related compounds (Schultes 1977)

Anadenanthera peregrina seed pods contain dimethyltryptamine and the seeds bufotenin, bufotenin oxide, and oxide of dimethyltryptamine (GRANIER-DOYEUX 1965)

Leaves, Bark, and Seeds contain DMT, 5-MeO-DMT and related compounds (Schultes 1977)

Anadenanthera macrocarpa seed pods contain dimethyltryptamine and the seeds bufotenin, bufotenin oxide, and oxide of dimethyltryptamine (GRANIER-DOYEUX 1965)

Desmodium caudatum Roots: 0.087% DMT, Bufotenine-N-oxide 0.03% (Trout's Notes)

Desmodium gangeticum DMT, 5-MEO-DMT, whole plant, roots, stems, leaves (Ott)

Desmodium gyrans DMT, 5-MEO-DMT, leaves, roots (Ott)

Desmodium pulchellum DMT, 5-MEO-DMT, whole plant, roots, stems, leaves, flowers (Ott)

Desmodium racemosum 5-MEO-DMT (Ott)

Desmodium triflorum

DMT-N-oxide, roots (Ott)

Lespedeza bicolor var. japonica DMT, 5-MEO-DMT in leaves and root bark (Ott)

mimosahostilis

Root Bark contains DMT - 0.31% to 0.57% (Schultes 1977)

Mimosa scabrella DMT in bark (Ott)

Mimosa verrucosa DMT (Schultes 1969)

Mucuna pruriens leaves, seeds, stems and roots contain L-Dopa, Serotonin, 5-HTP, and Nicotine, as well as N,N-DMT, Bufotenine, and 5-MeO-DMT (Erowid)

Petalostylis labicheoides var. casseoides DMT in leaves and stems (Ott)

Diplopterys cabrerana

1.3% DMT (Shulgin, TIHKAL)

Contains DMT (Ott)

Horsfieldia superba 5-MeO-DMT and beta-carbolines (Jossang et al. 1991)

Iryanthera ulei

5-MEO-DMT in bark (Ott)

Osteophloem platyspermum DMT, 5-MEO-DMT in bark (Ott)

Virola calophylla


flowering branch
flower cluster, enlarged
Virola calophylloidea
flowering branch
Virola calophylla
flower buds, enlarged
young fruit
Virola theiodora
flowering branch
flower cluster, enlarged

Leaves 0.149% DMT (Ott)

Virola carinata DMT in leaves (Ott)

Virola divergens DMT in leaves (Ott)

Virola elongata DMT, 5-MEO-DMT in bark and leaves (Ott)

Virola melinonii DMT in bark (Ott)

Virola multinervia DMT, 5-MEO-DMT in bark and leaves (Ott)

Virola pavonis DMT in leaves (Ott)

Virola peruviana DMT, 5-MEO-DMT in bark (Ott)

Virola rufuta Alkaloids in bark and root, 95% of which is 5-MeO-DMT (Shulgin, TIHKAL)

Virola sebifera DMT in bark (Ott)

Virola theiodora DMT, 5-MEO-DMT in bark, roots, leaves and flowers (Ott)

Virola venosa DMT, 5-MEO-DMT in roots and leaves (Ott)

Psychotria carthaginensis

0.2% average DMT in dried leaves (Ott)

Psychotria viridis

Leaves contain DMT - 0.10% to 0.66% (McKenna)

Edited:02-04-2008

Uncover the truth,"It's really stranger then fiction".

Acacias

Acacia

Among the most valuable ornamental trees in the drier parts of the world. This massive genus of plants within the larger Legume family, contains over 1200 species of plants, 900 which are native to Australia, the remainder being native to the Americas, Africa and milder parts of Asia. Many provide shelter, shade and timber in dry regions where few other sizeable trees will grown.
Most prefer full sun and well drained soil. Most are propagated from seed, many also propagated from semi-ripe cuttings over heat. Typically germination is greatly improved by pouring boiling water over them and letting them to cool by soaking in cold water over 24 hours. Rubbing sandpaper over the seedcoats can also be done. Germination is rapid.

** photos taken on Jan 3 2011 @ Deerfield Beach Arboretum, Florida.*

** photos of unknown internet source*

Many Acacias are psychoactive (marked ^ at end of text description) and contain the same chemical that makes people and animals dream.
http://en.wikipedia.org/wiki/List_of_psychedelic_plants (video posted beneath)

http://www.erowid.org/plants/acacia/acacia.shtml

Acacia acinacea (Gold-Dust Wattle)
A decorative spreading shrub with long arching branches, native to semi-arid parts of southeastern Australia. Some records include: 3 years - 10 feet; largest on record - 10 x 13 feet.
The oblong, obovate or rounded phyllode leaves, up to 1 x 0.5 inches, are deep blue-green.
Profuse, golden-yellow flowerballs, up to 0.2 inches across, are borne singly or paired from the leaf axils during late spring and spring.
They are followed by curved, twisted pods.
The twigs are angled.
The smooth bark is gray to dark brown.
Hardy zones 8 to 10 in full sun to partial shade. It is drought and heavy clay tolerant. Prune lightly after flowering to encourage new growth.

'Ruby Tips'
Bright red new foliage

Acacia abyssinica
A medium-sized tree, reaching a maximum height of 66 (rarely over 53) feet, that is native to Africa. Some records include: fastest recorded growth rate - 3 feet; largest on record - trunk diameter of 2 feet.
The bipinnate leaves are up to 11 inches in length.
The puffy flowerballs are white.
Hardy zones 9 to 11 (tolerating as low as 15 F).

Acacia acradenia

A large shrub or small tree, reaching a maximum height of 25 (rarely over 13) feet in height, that is a widespread native to arid northern Australia. Some records include: 3 years - 5 feet.
The elliptical leaves are up to 6 x 1.2 inches.
The golden-yellow to orange flower spikes are up to 2.5 inches in length.
The twigs are orange-brown.
The red-gray to brown bark is smooth when young, later turning fibrous.

Acacia acuminata (Raspberry Acacia)
A fast growing, dense, rounded tree reaching a maximum size of 47 x 33 feet, that is native to southwestern Australia. Some records include: 10 months - 4.5 feet; 3 years - 10 feet; largest on record - trunk diameter of 1.5 feet. It is known to resprout after fire but rarely suckers otherwise. It is moderately long-lived, exceeding 50 years.
The linear to narrow-elliptic leaves, up to 10 x 0.4 (rarely over 7) inches, are mid-green.
The golden-yellow flower spikes are up to 1.3 inches in length.
Hardy zones 8 to 10, requiring mediterranean climates. It tolerates drought but not waterlogged soils.

Acacia adsurgens
A spreading shrub or small tree, reaching a maximum size of 23 (rarely over 13) feet in height, that is a widespread but rare native to the arid parts of northern Australia.
Some records include: 6 years - 8 feet with a trunk diameter of 1 inch.
The linear leaves, up to 8 x 0.2 inches, are glossy mid-green.
The cylindrical, golden-yellow flower spikes are up to 0.8 inches in length.
The twigs are reddish or light brown.
The fibrous bark is gray-brown peeling to reveal reddish-brown bark beneath.
Hardy zones 9 to 11 (partial dieback recorded at 16 F).

Acacia adunca (Wallangarra Wattle)
Also called Cascade Wattle. A rapid growing, large bushy shrub or small tree reaching a maximum size of 47 x 20 (rarely over 33) feet that is native to dry forests in far northeast New South Wales in Australia.
The narrow linear, phyllode leaves, up to 6 x 0.1 inches in length, are bright green to blue-green.
The profuse, showy, sweetly fragrant, golden-yellow flower balls, up to 0.3 inches across, are borne in long sprays during late winter and spring.
The slender twigs are red-brown.
Hardy zones 9 to 11 in full sun on well drained soil.

Acacia albida
A beautiful large tree similar in appearance to a mature Gleditsia-Honeylocust.
Some records include: 3 years - 23 feet; largest on record - 110 x 100 feet with a trunk diameter of 6 feet.
Hardy north to zone 9a, tolerating as low as 18 F. Roots have been found as deep as 270 feet.

Acacia alpina (Alpine Wattle)
A dense, low spreading shrub, rarely much taller to 8 feet and spreading as much as 33 feet, that is

native to far southeastern Australia.
The broad obovate phyllode leaves, up to 1.8 x 1.1 inches, are gray-green.
The cylindrical bright yellow flowers, up to 0.6 inches in length, are paired or borne singly along the stems during spring.
Hardy zones 8 to 10 tolerating as low as 8 F. It is also tolerant of snow.

Acacia amblygona (Fan Wattle)
A low spreading shrub native to eastern Australia.
Some records include: 3 years - 5 (rarely over 3) feet; largest on record - 8 x 10 (rarely over 3) feet.
The lower growing forms can valuable for use as groundcover.
The sharply pointed, triangular, phyllode leaves, up to 0.8 x 0.2 inches, are mid- green.
The singular, golden-yellow flower balls, up to 0.3 inches across, are borne winter into early spring.
Hardy zones 9 to 11

Acacia amoena (Boomerang Wattle)
A dense, rounded, large shrub reaching up to 13 feet that is native to highlands in southeastern Australia.
The thick, leathery, oblanceolate phyllode leaves, up to 3.4 x 0.7 inches, are gray-green.
The showy, intense, bright golden-yellow flower balls, up to 0.2 inches across, are borne in short sprays, up to 2.6 inches in length, during late winter and early spring. They are followed by dark brown pods, up to 3.5 x 0.2 inches.
The twigs are reddish-brown.
Hardy zones 8 to 10

Acacia ampliceps (Salt Wattle)
A fast growing, suckering, bushy, semi-pendulous, spreading, large shrub or small tree, reaching a maximum height of 30 feet, that is a widespread native to northwestern Australia. Some records include: 2 years - 9 feet; 3 years - 15 feet.
It makes a great windbreak and is highly valuable for reclaiming salty soil.
The linear to narrow lance-shaped leaves, up to 10 x 1.2 inches, are bright green.
The creamy-white flower balls are borne on racemes up to 4 inches in length.
The twigs are yellowish.
Hardy zones 9 to 10, thriving in hot arid climates. Freezes to ground at 18 F

Acacia amythethophylla
A bushy shrub or small tree, reaching a maximum height of 17 feet, with a tiny natural range of sand dunes around Shark Bay on the central part of Australia's west coast. Some records include: 7 years - 17 feet.
The oblanceolate leaves, up to 4.8 x 0.6 inches, are blue-green.
The pale yellow flower balls are borne on racemes up to 1.4 inches in length.

Acacia aneura (Mulga)
A long lived, moderate growing, evergreen shrubby tree up to 25 feet that is native to much of the dry interior of Australia.
Some records include: fastest recorded growth rate - 4 feet; 4 years - 12 feet; 10 years - 33 feet with

a trunk diameter of 4 inches; largest on record - 60 x 23 feet with a trunk diameter of 1 foot. Mulga is long lived, exceeding 240 years.
Very deep rooted enabling it to survive in arid climates, a 4 foot tall tree was recorded to have a 10 foot taproot.
The flat, narrow, linear phyllode leaves, up to 5 x 0.4 (rarely over 3) inches in length, are gray-green to blue-green above, silvery beneath.
The profuse, golden-yellow flowers are borne on dense spikes, up to 1.2 inches in length, during spring and summer, irregularly the rest of the year.
The fissured bark is dark gray.
Hardy zones 9 to 10 tolerating as low as 15 F, it thrives in climates with 8 to 20 inches of rainfall per year.

Acacia angustissima (Fern Acacia)
A thornless, fast growng large shrub native from Missouri south to Costa Rica, reaching around 8 x 6 feet though may be a small tree more than double that.
Some records include: 2 years - 6 feet; 2.5 years - 17 feet with a trunk diameter of 2.3 inches; largest on record - 23 feet. In cold climates where it grows as a perennial, it can be used for groundcover.
The attractive, finely-textured, fern-like foliage is mid-green.
The white, ball-shaped flowers are borne during summer and fall.
The flowers attract butterflies
Hardy zones 9 to 10 as a shrub, zone 6 to 8 as a perennial, tolerating as low as -10 F. It thrives in full sun to partial shade on just about any fertile, well drained soil. Drought tolerant.

Acacia aphylla (Leafless Rock Wattle)
A leafless but attractive shrub reaching up to 10 x 10 feet that is native to a tiny area just a little bit east of Perth in Australia where it is endangered. It looks like a succulent rather than an Acacia. This Acacia bears no leaves.
The spiny, silvery to gray-green branches are profusely covered by showy, bright yellow flower balls borne singly during spring.
They are followed by linear pods, up to 3.5 inches in length.
Hardy zones 9 to 10 in sun to partial shade on very well drained soil.

Acacia arabica (Egyptian Acacia)
A medium size tree native to a vast area from Africa to southern Asia.
Some records include: 30 years - 60 feet with a trunk diameter of 2.6 feet; largest on record - 82 feet with a trunk diameter of 5.2 feet.
Hardy north to zone 9b

Acacia aroma
A thorny, spreading, small tree, reaching a maximum height of 20 feet, that is native to Bolivia, Peru, Paraguay and Argentina. It is closely related to Acacia macrantha.
Some records include: 2 years - 3 x 6 feet; 9 years - 13 feet.
The pinnate leaves, up to 5.5 inches in length, are composed of 48 to 100 linear leaflets, up to 0.2 x 0.03 inches in size.
The pale yellow flower balls, up to 0.4 inches across, are borne from the leaf axils.

The twigs are dark purplish-brown.
The dark gray to dark brown bark is smooth at first, later becoming shallowly furrowed.
Hardy zones 9 to 11 (slight damage at 16 F).

Acacia ashbeyae
A very attractive, rounded, dense, spreading shrub, reaching a maximum height of 6.5 feet, that is native to southwestern Australia. Some records include: 2 years - 5 x 8 feet; 3 years - 6 x 10 feet.
The very narrow leaves, up to 3.5 inches in length, are gray-green.
The flowers are bright yellow.
Hardy zone 9 to 10 (tolerating 19 F or slightly colder) in mediterranean climates, preferring sandy soil.

Acacia atramentaria
A flat-topped tree, reaching a maximum height of 40 feet, that is native to northern Argentina. Some records include: 3 years - 6 feet; 8 years - 15 feet.
The bark is furrowed and dark gray.
Hardy zones 9a to 10 (fully hardy to 16 F).

Acacia aulacocarpa (Golden Flowered Salwood)
A spreading tree, reaching a maximum height of 50 feet, that is native to the central and northern parts of Australia's east coast.
Some records include: 3 years - 10 feet; largest on record - 16 inch trunk diameter.
The leaves, up to 8 x 1.5 (rarely over 5) inches, are blue-green.
The bright golden-yellow flower spikes are up to 2.4 inches in length.
The bark is smooth.
Hardy zones 9b to 10 (est) in subtropical to tropical climates.

Acacia auriculiformis
A moderately long lived, dense, rounded, large tree native to northern Australia, New Guinea and nearby parts of Indonesia. It is among the worlds fastest growing trees. Some records include: fastest recorded growth rate - 25 feet; 2 years - 20 feet; 3 years - 41 feet with a trunk diameter of 5 inches; 5 years - 50 feet; 8 years - 60 feet; largest on record - 133 x 100 feet with a trunk diameter of 4 feet.
It is an excellent shade tree for subtropic and tropical areas worldwide.
The phyllode leaves, up to 12 x 2 inches, are glossy olive green.
The golden flowers are borne in profuse spikes as the tropical dry season begins.
They are profusely followed by contorted, leathery seed pods.
Hardy zones 10 to 12 in climates with average yearly rainfall of 30 inches or more.
Very soil tolerant, tolerating PH from 3 to 9^

** photo of unknown internet source*

Acacia baeuerlenii
An evergreeen shrub, reaching a maximum height of 13 feet, that is native to the central part of Australia's east coast. Some records include: 3 years - 11 feet.
The linear leaves are up to 6 x 0.5 inches.
The creamy-white flower balls, up to 0.4 inches across, are borne in clusters of 1 to 3 from the lead axils.
Hardy zones 9 to 10 (est) in warm temperate to subtropical climates.

Acacia baileyana (Cootamundra Wattle)
An elegant evergreen tree native to a small area around Cootamundra in the southern part of New South Wales in Australia. The outer branches gracefully droop.
Some records include: fastest recorded growth rate - 7 feet; 5 years - 17 feet; 20 years - 40 x 40 feet; largest on record - 50 x 70 feet with a trunk diameter of 3 feet. Short lived, it usually only lives 20 years.
It has been planted as a street tree in parts of California.
The feathery bipinnate leaves, up to 2 inches in length, are silvery-gray.
The profuse, bright yellow, ball-shaped flowers are borne in dense, axilliary racemes, up to 4 inches in length, during winter and early spring.
The bark is smooth and silvery-gray.
Hardy zones 8 to 10 tolerating as low as 15 F, can recover from 12 F.
It prefers full sun on humus-rich, well drained soil. Drought tolerant. Deer resistant. Pruning after flowering encourages new growth and extends the life of the plant.

'Purpurea'

Attractive purplish foliage.

Acacia bakeri (Baker's Wattle)
Among the largest of all Acacias, it can reach up to 170 x 82 feet with a trunk diameter of 5 feet with a dense rounded canopy. Due to habitat destruction within its natural range, trees exceeding even half that size are now extremely rare. It is slow growing, so the sizes of trees that greeted the settlers won't be around again for a long time. It originally grew in subtropical rainforests along a stretch of coastline on the center part of Australia's east coast.
The elliptical leaves, up to 5 x 1.3 inches, are deep green.
The creamy-yellow flowers are borne on racemes up to 4 inches in length.
They are followed by pods up to 8 x o.5 inches in size.
The close-grained hard, yellowish wood was once used for flooring and cabinetry. This tree is now in danger of extinction.
Hardy zones 9 to 10 in moist, humid subtropical climates.
Seed should be soaked in warm water for 4 hours or until they swell before sowing.

Acacia bancroftii (Bancroft's Wattle)
A very attractive deciduous tree reaching up to 20 feet, that is native to inland areas in central Queensland Australia.
The very large, sickle-shaped phyllode leaves, up to 9 x 5.5 inches, are blue-green.
The bright yellow, ball-shaped flowers are borne in very long racemes during late autumn and winter.
Hardy zones 9 to 11, thriving in warm dry climates.

Acacia berlandieri (Berlandier Acacia)
Also called Guajillo. A very attractive small semi-evergreen to evergreen tree that is native to hills of western Texas, south into Mexico. Some records include: fastest recorded growth rate - 3 feet; 3 years - 5 feet; largest on record - 25 x 25 feet with a trunk diameter of 6 inches.
The fernlike bipinnate, Silktree-like leaves up to 6 inches in length are deep green.
The ferny foliage lends a tropical appearance to the desert landscape.
The fragrant, creamy-white flowerballs are borne during spring.
The stems are armed in curved short thorns.
Berlandier Acacia is toxic to livestock, it is also psychoactive.
It is one of the most cold hardy Acacias, tolerating as cold as 0 F in dry climates.
Extremely drought tolerant, thriving in areas with rainfall as low as 6 inches in a year.

** photo of unknown internet source*

Acacia binervia (Coast Myall)
Also called Acacia glaucescens. A very attractive, long lived, fast growing, dense tree native to eastern Australia. Some records include: 3 years - 13 feet; largest on record - 66 x 35 feet. Also makes an excellent windbreak.
The curved, elliptic phyllode leaves are up to 7 x 2 (rarely over 5.5) inches in size.
The bright yellow flowers are borne in masses of narrow cylindrical, axilliary spikes, up to 2.3 inches in length, during early spring.
The deeply fissured and flaky bark is gray-brown to dark brown.
This plant is toxic to livestock.
Hardy zones 9 to 11 tolerating as low as 19 F in full sun and partial shade.

Acacia bivenosa (Two-Nerved Wattle)
A bushy, dense, rounded shrub, reaching a maximum height of 17 (rarely over 12) feet, that is native to northwest and north central Australia. Some records include: 2 years - 8 feet with a trunk diameter of 3 inches.
The oval to oblong leaves, up to 2 x 1 inches, are blue-green.
The showy, bright yellow flower balls are borne from the leaf axils.
Hardy zones 9b to 11 (plants freeze back to ground level at 19 F, resprouting vigorously).

Acacia bonariensis
An evergreen shrub that is native to Paraguay and northern Argentina.
Some records include: 2 years - 4.5 feet.
Hardy zones 9 to 10

Acacia boormannii
A showy, fast growing, bushy, slender large shrub to small tree, reaching a maximum size of 20 x 17 (rarely over 15) feet, that is native to subalpine zones in far southeastern Australia. It makes a great screen and windbreak.
The linear leaves, up to 3.5 inches in length, are gray-green.
The golden-yellow flower balls, up to 0.2 inches across, are borne on racemes, up to 1.6 inches in length. This plant is spectacular in bloom.
The branches are silvery. The bark is smooth and gray.
Hardy north to zone 8 and is snow and clay tolerant, moderately salt tolerant. Requires average yearly rainfall of 20 inches or more.

Acacia borleae
A shrub that is native to South Africa.
Some records include: 3 years - 6.5 feet.
Hardy zones 9 to 10 (tolerates 16 F with slight damage).

Acacia brachybotrya (Gray Mulga)
A moderate growing large shrub reaching a maximum size of 15 x 15 feet, that is native to semi-arid southeastern Australia. Some records include: 3 years - 12 feet.
The obovate leaves, up to 1.3 x 0.5 inches, are grayish-green to blue-green.
The red Manzanita-like bark looks amazing when exposed through pruning.
Hardy to 18 F

Acacia brachystacha (Turpentine Mulga)
An evergreen shrub to small tree, reaching a maximum size of 20 x 17 feet, that is native to central Australia. Some records include: 9 years - 14 feet.
The very linear leaves are up to 7 x 0.1 inches, are blue-gray to blue-green.
The bright yellow, narrow cylindrical flower spikes, up to 0.8 inches in length, are borne 1 or 2 from the leaf axils.
The gray bark is smooth becoming fissured with age.
Hardy zones 9 to 10 (tolerating 15 F) in semi-arid to desert climates.

Acacia brandeegeana
A small, thicket-forming tree, reaching a maximum height of 23 feet, that is native to Baja California.
Some records include: 9 years - 6 feet.
The pinnate leaves contain 4 to 14 tiny leaflets, up to 0.35 x 0.1 inches.
Hardy zones 9 to 10 (fully hardy to 16 F).

Acacia brunioides
A shrub reaching a maximum size of 6.5 x 5 feet, that is native to Australia's central east coast.
The densely crowded, narrow, needle-like phyllode leaves are up to 0.5 inches in length.
The showy large, globular, light yellow flowerheads are borne singly along the stems late winter into early spring.
Hardy zones 9 to 11. Prune to shape after blooming.

Acacia burkitttii (Pinbush Wattle)
An attractive, fast growing, dense, compact, large spreading shrub to small tree, reaching up to 33 x 15 (rarely over 15) feet, that is native to semi-arid parts of southern Australia.
Hardy zones 8 to 10 in full sun to partial shade preferring sandy soil. Very drought tolerant.
The long, linear, phyllode leaves, up to 8 inches in length, are green.
The oblong spikes of small yellow flowers are borne late winter and spring.
Hardy zones 8 to 10. An excellent landscape plant for dry climates.

Acacia buxifolia (Box-leaf Wattle)
An upright to spreading shrub reaching a maximum size of 13 x 9 feet that is native to the eastern Australian coast.
The leathery, narrow-elliptic, phyllode leaves, up to 1.5 x 0.3 inches, are gray-green.
The very showy, profuse, globular, golden-yellow flowers are borne in dense axilliary panicles, up to 1.8 inches in length, during winter and spring.
Hardy zones 8 to 10, it is very adaptable and tolerates both flood and drought. Pune regularly after flowering to encourage new growth and density.

Acacia caerulescens (Buchan Blue Wattle)
A very attractive, very fast growing, dense, oval to rounded small tree, that is native to extreme southeastern Australia not including Tasmania. Some records include: first year - 10 feet; largest on record - 55 x 40 feet with a trunk diameter of 1.5 feet. It is endangered in the wild with just around 1700 plants left in existence. It makes an excellent landscape tree and should be widely planted where it is adapted in order to preserve it.
The obovate leaves, up to 3.2 x 1.3 inches, are blue-green.
The pale yellow flowerballs are borne on clusters, up to 3.5 inches in length.
Hardy zones 9 (estimate...it may actually be hardier). It is both lime and clay soil tolerant.

Acacia caffra
A medium size tree native to tropical and southern Africa.
Some records include: 4 years - 16 feet; 5 years - 18 feet; 9 years - 17 feet; largest on record - 66 feet.
The bipinnate leaves are up to 9 inches in length.
The flowers are cream colored.
Hardy north to zone 9b tolerating as low as 23 F

Acacia calamifolia
A shrub, reaching a maximum height of 13 feet, that is native to southeastern Australia.
The narrow-linear, phyllode leaves, up to 4.3 inches in length, are gray-green to green.
The flowers are borne on very showy, golden-yellow puffballs.
Hardy zones 9?

Acacia cana
A dense, spreading, small tree, reaching a maximum size of 20 x 20 feet, that is native to eastern Australia. Some records include: 2 years - 4 feet.
The linear leaves are up to 5 x o.1 inches in size. The very attractive foliage is bright gray-green.

The golden-yellow puffball flowers are very showy.
The bark is gray.
Hardy zones 9 to 10 (fully hardy to 16 F).

Acacia cardiophylla (Wyalong Wattle)
A showy spreading, arching shrub or more rarely small tree that is native to New South Wales in Australia. Some records include: 3 years - 3 feet; largest on record - 17 x 13 (rarely over 11) feet.
The bipinnate leaves, up to 2.5 inches, are composed of tiny, heart shaped leaflets.
The profuse, sweetly fragrant, globular, bright yellow flowers are borne in long panicles that cover the stems during late winter and spring.
The bark is smooth and gray.
Hardy zones 8 to 10

Acacia catechu (Black Catechu)
A medium size tree native to Pakistan, India and Burma.
Some records include: fastest recorded growth rate - diameter growth of 0.5 inches; 2 years - 10 feet; largest on record - 80 x 50 feet with a trunk diameter of 3.2 feet.
The fine bipinnate leaves are up to 6 inches in length.
The yellow flowers are borne in long spikes during spring.
The twigs are armed with hooked spines.
Hardy zones 9 to 12^

Acacia cavenia (Cavan)
Also called Espanillo. An attractive twisted trunked, fast growing small tree.
Some records include: fastest recorded growth rate - 5 feet; 2 years - 6 feet; 3 years - 9 feet; 4 years - 12 feet; largest on record - 30 x 30 feet with a trunk diameter of 20 inches. Often used as a hedge in its native Chile.
The bipinnate leaves are composed of tiny leaflets. The foliage is downy at first.
The yellow, ball-shaped flowers are borne from the leaf axils during spring.
The valuable timber is durable and very hard.
The flexible branches are spiny.
Hardy zones 8 to 11. Leaves undamaged at 19 F
Pharmacology: known to contain Tryptamine

** photo of unknown internet source*



Acacia chinchillensis (Chinchilla Wattle)
An attractive, fast growing, small spreading shrub is native to a small area in southern Queensland, Australia. Some records include: 3 years - 4;5 feet; largest on record - 6.6 x 6 feet.
The bipinnate foliage is gray-green. The leaflets are up to 0.3 inches in length.
The showy globular, golden-yellow flowers are borne in panicles during late winter and spring.
The bark is smooth and gray-brown.
Hardy zones 9 to 11. Trim regularly for increased density.

Acacia choriophylla
A thornless small tree reaching a maximum size of 20 x 24 feet, that is native to Florida.
Extremely drought tolerant.

Acacia citrinoviridis
An attractive weeping tree, reaching a maximum height of 50 feet, that is native to western Australia. Some records include: 6 years - 13 feet.
The linear to narrow-elliptic leaves are up to 6.5 x 0.5 inches in size.
The bark is fissured and gray.
Fully hardy to 17 F.

Acacia cognata (River Wattle)
A rapid growing, gracefully weeping, small tree reaching up to 40 x 40 feet, that is native to coastal southeast Australia.
The narrow phyllode leaves, up to 4 inches in length, are bright green.
The globular, golden-yellow flowers are borne on short stalks during late winter and spring.
Hardy zones 9 to 11 (tolerates 20 F) on moist soil in sun to partial shade.

Acacia concurrens
A fast growing tree, reaching a maximum size of 33 feet, that is native to the eastern Australia's

center coast. Some records include: 3 years - 13 feet.
The obovate phyllode leaves, up to 7 x 2.3 inches, are blue-green.
The bright yellow flower spikes are up to 4.3 inches in length.
The fibrous fissured bark is grayish-black.
Hardy zones 9 to 10

Acacia conferta (Crowded-Leaf Wattle)
An attractive fine shrub reaching a maximum size of 15 x 13 feet, that is native to dry areas of southeastern Queensland and nearby parts of New South Wales.
The very dense, nearly needle-like, narrow-oblong, deep gray-green phyllode leaves, are up to 0.5 inches in length.
The small, bright yellow, ball-shaped flowers are borne singly along the stems.
Hardy zones 9 to 11

Acacia confusa (Formosan Acacia)
A medium-sized tree that is native to Taiwan and the Phillipines but has also become an exotic invasive weed in Hawaii. Some records include: largest on record - 66 x 90 feet with a trunk diameter of 3.5 feet.
The narrow, lance-shaped, phyllode leaves are up to 4 x 0.4 inches, are dull green.
The golden-yellow flowerballs are up to 0.4 inches across.
The seeds are highly poisonous.
The slender twigs are smooth and brown.
The bark is smooth and gray.
Hardy zones 10 to 12, preferring a subtropical to tropical climate.
Pharmacology: at a concentration of 1.4%, the roots contain among the worlds highest known concentrations of DMT.

** photo of unknown internet source*

Acacia constricta (Whitethorn Acacia)

A moderate growing, long-lived, large shrub to small tree reaching up to 10 x 15 feet, that is native to Nevado, Arizona to Texas. Some records include: 2 years - 8 feet; 7 years - 14 feet; 11 years - 16 feet. Generally evergreen, it becomes deciduous during extreme drought or cold. It makes an excellent barrier plant.
The soft yellow, puffy, ball-shaped flowers are borne during mid spring to early summer. They are nearly pollen free.
The flowers are followed by attractive deep reddish-brown seed pods, up to 5 inches in length.
The thorns are sharp and white.
Hardy zones 5a to 11, it is among the hardiest of all Acacias, though it is far less hardy in moister climates. Whitethorn Acacia prefers full sun and infrequent deep watering. Very drought and heat tolerant. Deer resistant.
Pharmacology: contains β-methyl-phenethylamine

** photo of unknown internet source*



Acacia continua (Thorn Wattle)
A dense, wiry-stemmed, rigid branched, shrub reaching a maximum height of 6.5 feet that is native to semi-arid parts of southcentral Australia.
The leathery, sharp-tipped, linear leaves, up to 1.6 (rarely over 1) inches in length, are pressed so closely to the stems, that this plant appears leafless.
The foliage is green.
Small, showy, deep golden-yellow, ball-shaped flowers are borne from the leaf axils during early spring.
Hardy zones 9 to 11

Acacia coriacea (Wiry Wattle)
A slightly pendulous, small tree reaching up to 33 x 15 feet, that is a widespread native to northern Australia.
The narrow, linear phyllode leaves, up to 13 x 0.4 inches, are silvery-blue.
The the globular golden-yellow flowers, up to 0.3 inches across, are followed by curled pods, up to 8 inches in length.
The bark is fibrous.
Hardy north to zone 9b (tolerating as low as 20 F). At colder temperatures it will dieback to the base, resprouting rapidly to up to 7 feet during the following summer.
Pharmacology: unknown

Acacia cornigera (Bullhorn Acacia)
A small tree, reaching up to 33 feet, that is native to Mexico and central America.
Some records include: 1 year - 6 feet; 2 years - 7.5 feet; 4 years - 8 feet.
The foliage is bipinnate.
Hardy zones 9 to 11
Pharmacology: contains Tryptamine

Acacia coulteri
Some records include: 2 years - 6 feet; eventual size of 7.5 feet

Acacia covenyi (Bluebush)
A rare fast growing tree, reaching a maximum size of 28 x 30 feet, that is native to far southeastern Australia.
The narrow oblong leaves, up to 2.3 x 0.4 inches, are silvery-blue.
The bright yellow flower puffballs, up to 0.2 inches across, are borne 5 to 8 on a clusters, up to 2.2 inches in length.
Hardy north to zone 8b tolerating 14 F. It thrives in climates with 20 + inches of yearly rainfall.
Drought tolerant.

Acacia cowleana
A small tree, reaching a maximum height of 27 feet, that is native to central Australia. Some records include: 2 years - 9 feet with a trunk diameter of 2 inches.
The oblanceolate leaves, up to 9 x 1.5 inches, are gray-green.
The flower spikes, up to 2 inches in length, are golden-yellow.
The bark is fibrous.
Hardy zones 9 to 11 (tolerating 20 F). Only marginally hardy in Tucson

Acacia craspedocarpa (Leatherleaf Acacia)
Also called Hop Mulga. An evergreen large shrub to small tree reaching a maximum size of 27 x 20 (rarely over 20) feet, that is native to southwestern Australia. Some records include: fastest recorded growth rate - 3 feet; 4 years - 6 feet; 10 years - 9 feet.
The rounded leaves, up to 1 x 0.5 inches, are blue-gray.
The bright yellow flower spikes are up to 0.8 inches in length.
Hardy zones 8 to 10, thriving in semi-arid climates. Very drought tolerant.

Acacia crassicarpa (Thick-Podded Salwood)
A long lived, tall spreading tree that is a widespread native to moist areas of eastern Australia often forming dense pure stands. One of the worlds fastest growing trees reaching up to 100 feet.
The long, curved phyllode leaves, up to 12 x 2 inches in size, are pale green to gray-green.
The golden-yellow flowers are borne in paired spikes during late winter and early spring.
The bark is dark gray-brown.
Hardy zones 9 to 11 (slight damage at 16 F).

Acacia cultriformis (Knife-Leaf Wattle)
A tall, very dense, evergreen shrub with drooping branches that is native to Eucalyptus forests of New South Wales in eastern Australia. Some records include: fastest growth rate - 3 feet; 3 years - 10 feet; largest on record - 26 x 18 feet.
It makes an excellent hedge and screen.
The attractive, pointed-tipped, triangular, phyllode leaves, up to 1.5 x 0.6 inches, are blue-gray.
The lightly fragrant. bright yellow, ball-shaped flowers are borne in sprays up to 3 inches in length.
Hardy zones 8 to 11 tolerating as low as 10 F, does not like climates with high humidity. Prefers full sun (tolerates partial shade) on humus-rich, sandy, well drained soil. Tolerates heat, drought and seaside salt winds.
Pharmacology: contains Tryptamine

** photo of unknown internet source*



'Austraflora Cascade'
A low groundcover form, reaching up to 1 x 13 feet.

Acacia cyclops (Western Coastal Wattle)
A very attractive, dense, bushy, small tree, reaching a maximum size of 28 x 28 feet, that is native to

the western and central part of the southern Australia coast.
Some records include: 10 months - 4.5 feet; 2 years - 8 x 5 feet.
The leathery, oblanceolate, willowy leaves, up to 4 x 0.6 inches, are green.
The pale yellow flowerballs, up to 0.3 inches across, are borne on 2 flowered racemes originating from the leaf axils.
Hardy zones 9 to 11(tolerates 10 F). Drought tolerant and even thrives on pure sand & salt breezes, making it a great choice for stabilizing sand dunes.

Acacia davyi (Corky Thorn)
An attractive, fast growing, evergreen tree, reaching up to 17 x 17 feet.
Some records include: 3 years - 6 feet.
The attractive, ferny bipinnate leaves, up to 6 inches in length, are bright green.
The bright yellow flowerballs, up to 0.3 inches across, are borne during summer.
The attractive, corky to flaking bark ranges from creamy-yellow to light brown.
Hardy zones 9 to 10 (partial damage at 16 F) in full sun to partial shade on well drained soil. Drought tolerant.

Acacia dealbata (Silver Wattle)
A very fast growing, single trunked, broadly-conical large tree to around 70 feet that is native to mountain forests of southeastern Australia and Tasmania.
Some records include: fastest recorded growth rate - 6 feet; 3 years - 20 feet; 5 years - 33 feet; 20 years - 50 x 27 feet (average); 22 years - 70 feet; 28 years - 82 feet with a trunk diameter of 3 feet; largest on record - 150 x 82 feet with a trunk diameter of 5 feet.
The ferny, bipinnate, blue-green leaves, up to 7 inches in length, are composed of many linear leaflets up to 0.3 inches. The finely-textured foliage is very attractive.
The abundant, very showy, very fragrant, bright yellow, ball-shaped flowers are borne in racemes up to 8 inches in length during late winter into spring.
The flowers are followed by seed pods up to 3 inches in length, that constrict between the seeds.
The branchlets are silvery. The bark is smooth and green, eventually becoming gray, developing cracks on older trees.
Hardy zones 8 to 10 tolerating as low as 8 F and it often resprouts from the ground if it did actually get colder. It thrives in milder parts of the British Isles. Prefers full sun and acidic, warm, well drained soil. Preferring consistent moisture, it can tolerate the occasional drought.

** photo of unknown internet source*

subsp 'subalpina'
Originating from high mountains in Australia, it is more consistantly cold hardy but still unlikely to thrive north of zone 8.
It is vigorous, grows large and has very attractive silvery foliage.

Acacia deanii (Deane's Wattle)
A small tree reaching a maximum height of 40 (rarely over 23) feet, that is native to southeastern Australia. Some records include: 3 years - 5 feet; 10 years - 15 feet.
Makes an excellent screen plant.
The ferny bipinnate leaves are dull deep green.
The creamy-white flowerballs are up to 0.2 inches across.
The smooth bark is brownish-purple.
Hardy zones 9 to 10 (fully hardy to 16 F). Very drought tolerant.

Acacia debilis
A large shrub to small tree, reaching a maximum height of 20 feet, that is native to eastern Australia.
Some records include: 3 years - 12 feet; largest on record - 20 feet.
The bipinnate leaves are composed of very narrow leaflets, up to 0.7 inches in length. The foliage is gray-green.
The tiny flower puffballs are golden-yellow.
The branches are reddish and the smooth bark is grayish-green.
Hardy zones 9b to 10 (est)

Acacia decora (Showy Wattle)
A dense, spreading shrub native to dry areas of eastern Australia.
Also called Western Golden Wattle. Some records include: 3 years - 5 feet; largest on record - 17 x 17 feet. Somewhat short-lived, trees exceeding 50 years in age are rare.
The slightly curved, narrow-elliptic leaves, up to 2.5 x 0.5 inches, are bright blue-green.
The very showy, globular, bright yellow flowers are borne in racemes during winter and spring.

The branches are reddish-brown.
Hardy zones 8 to 11 in sun to partial shade. Easy to grow.

Acacia decurrens (Black Wattle)
A highly ornamental, very fast growing, large, erect tree native to New South Wales in Australia. Some records include: fastest recorded growth rate - 17 feet with a trunk diameter increase of 1 inch; 6 years - trunk diameter of 5 inches; 25 years - 60 feet; largest on record - 80 x 66 feet with a trunk diameter of 3 feet. Trees as large as 55 feet are known to grow in Ireland.
The bipinnate leaves, up to 6 inches in length, are deep green.
The linear leaflets are up to 0.6 inches in length.
The fragrant, globular, bright yellow flowers are borne in axilliary racemes, up to 6 inches in length, during late winter and early spring.
The dark gray bark is furrowed.
Hardy zones 8 to 10 (unconfirmed reports of 7) thriving in areas with yearly rainfall exceeeding 18 inches. Very tolerant and easy to grow however may be prone to borers.

'mollis'
2 years - 9 feet.
Only marginally hardy in Tucson.

'subalpina'
11 years - 17 feet with a trunk diameter of 8 inches.
Has very silvery, tiny leaves.

Acacia difformis (Wyalong Wattle)
A small tree, reaching a maximum height of 23 feet, that is native to southeastern Australia.
Some records include: 4 years - 7.5 feet.
The pendulous, narrow-oblanceolate leaves, up to 6.5 x 0.6 inches, are green.
The bright yellow flowers are borne on clusters, up to 2.5 inches in length.
Likely hardy north to zone 8b (fully hardy to 15 F), surviving in Tucson, AZ.

Acacia dunnii (Dunn's Wattle)
A fast growing small tree native to far northwestern Australia. Some records include: 2 years - 21 feet; largest on record - 23 x 20 feet.
The large, falcate, glaucous-blue leaves are up to 18 x 12 (rarely over 15 x 7) inches.
The very spectacular 0.8 inch golden-yellow flower balls are borne on panicles up to 20 inches in length, during most of the year.
Hardy in zone 11, tropics only.

Acacia elata (Cedar Wattle)
A tree native to southeastern Australia. Some records include: fastest recorded growth rate - ; 3 years - 25 feet; largest on record - 133 x 60 feet with a trunk diameter of 2 feet.
The pinnate leaves are composed of lance-shaped leaflets, up to 2.5 x 0.5 inches.
The flowers are creamy-yellow.
The bark is blackish-gray.

Hardiness in North America is unknown, likely north to zone 8b.

Acacia enterocarpa (Jumping Jack Wattle)
A dense, low spreading shrub reaching a maximum height of 5 feet that is native to border areas between South Australia and Victoria in Australia.
The linear leaves are up to 1.8 inches in length.
The bright yellow flowers are borne on globular heads.
Hardy zone 9 to 11 preferring sandy soil.

Acacia eremophila
A dense, rounded shrub, reaching a maximum height of 6.5 feet, that is native to southwestern Australia.
Some records include: 3 years - 4 feet.
The very linear leaves, up to 4.5 inches in length, are mid-green.
The golden-yellow flowerheads are borne from the leaf axils.
Hardy zones 9a to 10, preferring mediterranean or dry climates.

Acacia erioloba (Camel Thorn)
Also called Acacia giraffae. It is a slow growing, shapely spreading evergreen tree that is a widespread native in southern Africa. Some records include: largest on record - 60 x 60 feet with a trunk diameter of 3 feet; longest lived - 300 years.
Hardy zones 9 to 11 tolerating as low as 18 F. It is a valuable shade tree in hot desert climates.
The leaves are bipinnate.
The sweetly fragrant, globular, golden-yellow flowers are borne singly during late winter and early spring.
They are followed by velvety gray coated, wide, sickle-shaped seed pods.
The stems are armed with white thorns.
The bark is rough and deeply fissured.
Hardy zones 9 to 11 tolerating as low as 18 F. Extremely drought tolerant due to its roots reaching as deep as 150 feet in search of water.

** photo of unknown internet source*







Acacia erubescens

Attractive, thorny, medium-sized tree that is native to central and southern Africa.

Some records include: 1 year - 6 feet; 4 years - 10 feet; 10 years - 20 feet.

The leaves are bipinnate.

The bottlebrush flowers are white.

The showy bark is papery.

Acacia estrophiolata
A gracefully weeping Willow-like tree reaching a maximum size of 70 x 35 feet, that is native to inland areas of Australia.
The linear phyllode-leaves are up to 4.3 x 0.2 inches in size.
The pale yellow flowers are borne on globular heads, up to 0.2 inches across.
The bark is smooth and silver.
Hardy zones 9 to 10 (tolerating 20 F).

Acacia falcata (Hickory Wattle)
A small tree reaching a maximum height of 40 (rarely over 15) feet, that is native to southeastern Australia. Some records include: 1st year - 3 feet; 3 years - 15 feet.
The narrow-elliptical, falcate leaves, up to 7.5 x 1.6 inches, are blue-green.
The creamy-white flowers are borne on clusters, up to 2.5 inches in length.
Hardy zones 9 to 10

Acacia falciformis (Pale Hickory Wattle)
A small tree reaching around 33 feet that is native to coastal southeast Australia.
Some records include: 5 years - 30 feet; largest on record - 82 x 40 feet with a trunk diameter of 3 feet.
The pendulous phyllode leaves are up to 9 x 2.5 inches, are blue-green.
Small, very fragrant, yellow, ball-shaped flowers are borne in large clusters, up to 4 inches in length, during spring.
Hardy zone 9 to 10

Acacia farnesiana (Sweet Acacia)
Also called Huisache. A fast growing, wiry, rounded to wide-spreading, small semi-evergreen to evergreen tree native to tropical America ranging north into Baja Peninsula, southern Texas and south Florida. This is a most attractive tree when in full bloom. The outer twigs are pendulous adding to the beauty of this tree.
Some records include: fastest recorded growth rate - 4 feet; 2 years - 7 feet; 3 years - 14 x 12 feet; 10 years - 20 feet; largest on record - 40 x 50 feet with a trunk diameter of 4.5 feet. Long lived, the Sweet Acacia can persist over 100 years. It has spread into the wild outside its native range in parts of southern California, southern Arizona and central Texas to Louisiana and central Florida where it may become invasive on open to semi-open sites on sandy soils.
It makes a great hedge or screen in the desert southwest.
The feathery bipinnate leaves, up to 4 inches in length, are composed of 3 to 8 pairs of pinnae, each having 10 to 25 pairs of pointed, narrow oval leaflets, each up to 0.3 (very rarely 0.5 inches) inches in length. The foliage is bright-green.
The very attractive foliage is finely-textured.
The large, sweetly very fragrant, bright golden-yellow, globular flowers, up to an inch wide, are borne in small clusters in late winter and spring.
Oils obtained from the flowers can be used in the making of perfume.
They are followed by thick, shiny, reddish-purple to very dark brown, oblong pods, up to 3 x 2 inches.

The zig-zagged orange-brown twigs are armed with strong stiff, straight, whitish spines, up to 2 inches in length, that are borne in the leaf axils.
The bark is reddish-brown with abundant pale lenticels on young trees. Gray with long thin vertical strips on older trees.
Hardy zones 8 to 12 tolerating as low as 10 F (however clones from the Caribbean and Florida are killed at or below 20 F), thriving in climates with 12 + inches of yearly rainfall. Very salt, heat and drought tolerant. It is sold in pots in many Florida nurseries. It is easy to grow in just about any soil.
Pharmacology: Contains DMT & Tryptamine

** photo of unknown internet source*



Acacia filicifolia (Fern-Leaf Acacia)
A tree, reaching a maximum size of 60 (rarely over 40) feet, that is native to southeastern Australia.
Some records include: 11 years - 53 x 40 feet with a trunk diameter of 13 inches.
The deep green, fernlike leaves are composed of linear leaflets, up to 0.3 inches in length.
The smooth bark is dark brown.
Hardy zones 8b to 10, thrives and grows very rapidly in milder parts of England.

Acacia fimbriata (Fringed Wattle)
Also called Brisbane Golden Wattle. A fast growing, bushy small tree that is native to eucalyptus forests of coastal areas in eastern Australia.
Some records include: fastest recorded growth rate - 5 feet; 3 years - 10 feet; largest on record - 25 x 20 feet. Fringed Wattle makes an excellent screen.
The linear phyllode leaves, up to 3 x 0.2 (rarely over 2) inches, are deep green.
The profuse, sweetly fragrant, globular, bright yellow flowers are borne in dense clusters, up to 3 inches in length, during late winter and spring.
The slender branches are drooping.
Hardy zones 9 to 11 tolerating as low as 14 F in sun to partial shade.

Acacia fleckii
A multi-stemmed small tree, native to southern Africa that sometimes suckers to form inpenetrable thickets. Some records include: 11 years - 25 feet; largest on record - 33 feet with a trunk diameter of 1 foot.
The foliage is gray-green.
The bottlebrush flower spikes, up to 2.6 inches in length, are creamy-white.
The creamy-white to pale gray bark is smooth or flaking on very old trees.
Hardy zones 9 to 11 (tolerating 20 F). Thrives in Yuma (with irrigation) but not Tucson. Thrives best in tropical climates but will tolerate occasional drought.

Acacia flexifolia (Bent-Leaf Wattle)
A bushy, rounded to spreading shrub reaching up to 7 x 7 feet, that is native to inland parts of southeastern Australia.
Some records include: 3 years - 7 feet; largest on record -
The narrow phyllode leaves are up to 2 (rarely over 0.8) inches in length.
The pale yellow, ball-shaped flowers are borne along the branches during winter and spring.
Hardy zones 9 to 11 tolerating as low as 19 F. Thrives in sun to partial shade. Prune lightly after flowering.

Acacia floribunda (Sally Wattle)
A fast growing, dense small tree with pendulous branches, that is native to coastal parts of eastern Australia. Some records include: 1 day - 1 inch; 5 years - 17 feet; largest on record - 47 x 50 feet. It is generally short lived, only living around 20 years.
The densely crowded, linear, phyllode leaves, up to 7 x 0.5 inches, are deep green.
The profuse, sweetly fragrant, pale yellow flowers are borne in loose spikes up to 3 inches in length during winter and early spring.
They are followed by seedpods up to 4 x 0.3 inches.
The smooth bark is gray with horizontal streaks and lighter mottles.
Hardy zones 9 to 11 tolerating as low as 19 F, in sun to partial shade. Very adaptable and easy to grow.
Pharmacology: contains Tryptamine, phenethylamine

Acacia furcatispina
Some records include: 3 years - 8 feet; 5 years - 12 feet; 12 years - 18 feet.
Hardy zones 9 to 11 (fully hardy to 18 F). Thrives in Tucson

Acacia galpinii
A fast growing, massive, deciduous tree native to southern Africa similar in appearance to a mature Gleditsia - Honeylocust.
Some records include: fastest recorded growth rate - ; 2 years - 18 feet; 3 years - 20 feet; 4 years - 25 feet; 9 years - 35 feet; 12 years - 40 feet; largest on record - 100 x 82 feet with a trunk diameter of 5 feet.
The bipinnate leaves, up to 7 inches in length, are luxuriant bright green.
The long bottlebrush flowers are creamy-white.
Hardy zones 9a to 11 (fully hardy to 16 F), it thrives even in Yuma, AZ extreme heat.

The root system is extensive.

Acacia genistifolia (Early Wattle)
An open shrub, reaching a maximum height of 10 feet, that is native to southeastern Australia.
The linear phyllode leaves are up to 1.6 inches in length.
The flower heads are creamy-yellow.
Hardy zones 9 to 10

Acacia gerrardii subsp 'negerensis'
Some records include: 3 years - 7 feet; 4 years - 10 feet; 8 years - 18 feet; 15 years - 22 feet; largest on record - 45 x 40 feet.
Hardy zones 9 to 11 (fully hardy to 16 F).

Acacia glaucoptera (Clay Wattle)
A rapid growing, dome shaped shrub reaching a maximum size of 8 x 10 feet, that is native to southwestern Australia. Often reaching only 3 feet in height, it can be used for groundcover.
The overlapping, flat leaves, up to 3 x 1 wide, are deep purple at first turning to blue-green. In cool climates, the foliage turns purplish during winter.
The deep yellow flower-balls are borne on very short stalks along the stems during winter and spring.
Hardy zones 9 to 11 tolerating as low as 19 F, thriving in full sun and partial shade. Heat and drought tolerant. It grows well as an understory plant under high canopy trees.
Pruning after flowering and pruning out dead wood encourages new growth.

Acacia gnidium
A dense, spreading shrub, reaching a maximum height of 13 feet, that is native to northeastern Australia.
Some records include: 2 years - 4 feet; 3 years - 6 feet.
The linear leaves are up to 2 inches in length.
Likely hardy north to zone 9, thriving in climates such as southern Arizona with occasional deep watering.

Acacia greggii (Catclaw Acacia)
A small to medium size tree reaching up to 20 x 20 feet, that is a widespread native to the western U.S. from southern California & Nevada to Austin & Corpus Christi, Texas; south into the Baja Peninsula to eastern Mexico. It is deciduous and during dry years may remain dormant or leafless for most of the year.
Some records include: 2 years - 7 feet; 3 years - 10 x 3 feet; 8 years - 15 feet; 12 years - 17 feet; largest on record - 50 x 70 feet with a trunk diameter of 50 inches. Though the maximum longeavity is not known, this tree can certaily exceed 130 years of age on ideal sites. This tree is an excellent choice for a spiny inpenetrable hedge and land reclaimation.
The bipinnate leaves, up to 3 inches in length, are composed of 1 to 3 pairs of pinnae, each having 8, 10 or 12 oval leaflets, each up to 0.3 inches in length.
The entire leaf may have up to 40 leaflets. The foliage is gray-green.
The small, fragrant, bright creamy-yellow flowers are borne in dense oblong cylindrical spikes up to

2.5 inches in length.
They are followed by often curved, flattened pods, up to 5 x 0.8 inches. The pods usually constrict between the seeds. The pods often persist from midsumer through winter into the following spring. The pods are edible and can be eaten raw, however are better boiled with a change of water to reduce their bitterness.
The branches are armed with thick, sharply curved spines up to 0.3 inches in length.
The bark is brown and scaly. The heavy wood is hard and typically not used commercially. It is sometimes used for fence posts. The wood also makes good firewood as it burns hot.
Hardy zones 7 to 9 tolerating as low as -13 F in dry climates. This tree is not known to grow in the humid eastern U.S. Catclaw Acacia prefers a soil PH of 7 to 8.5 and is extremely drought tolerant though much faster growing with occasional deep irrigation.
The seeds may take years to germinate in the wild due to their hard shell.
The seeds will germinate much faster if soaked in water for 24 hours or soaked in acid before sowing. The Catclaw Acacia is also easy to reproduce from semi-ripe cuttings.

** photo of unknown internet source*



Acacia gummifera (Morocco Acacia)
A small tree reaching a maximum height of 33 feet, that is native to north and central Africa.
Hardy north to zone 9, extremely drought tolerant.

Acacia haematoxylon
Some records include: 3 years - 3 feet; 7 years - 5 feet.
Hardy zones 9 to 11 (fully hardy to 16 F).

Acacia hakeoides (Western Black Wattle)
A multi-branched, bushy, small tree native to drier regions of Australia. Some records include: 3 years - 6 feet; largest on record - 33 x 17 feet.
The thick, oblanceolate phyllode leavss, up to 6 x 0.5 inches, are green.
The showy, dense, bright yellow ball-shaped flowers are borne in axilliary racemes during winter and spring.
Hardy zone 8 to 10. Drought tolerant.

Acacia harpophylla (Brigalow)
A fast growing, dense, erect, long lived small tree native to semi-arid parts of eastern Australia. Some records include: 5 years - 8 feet; largest on record - 82 x 60 feet with a trunk diameter of 2 feet. It often suckers to form thickets in the wild. An excellent shade and shelter tree in dry climates.
The curved, leathery, phyllode leaves, up to 8 x 1 inches, are silvery-gray.
The yellow ball-shaped flowers are borne in short racemes during late winter and spring.
The bark is dark and furrowed.
Hardy zones 9 to 10 (fully hardy to 16 F), it thrives in Tucson
The seeds are soft coated and do not need treatment to germinate readily.

Acacia harveyi
A dense, large shrub to small tree, reaching a maximum size of 20 feet, that is native to far southwestern Australia.
Some records include: 3 years - 5 feet; 6 years - 8 feet.
The linear leaves are up to 5 inches in length.
The lemon-yellow flowers are borne on globular heads.
Hardy zones 9 to 11 (fully hardy to 16 F with foliage damage only), preferring mediterranean type climates.

Acacia havilandii (Needle Wattle)
A very attractive, bushy, broad vase-shaped shrub native to southeast Australia.
Some records include: 3 years - 6 x 10 feet; 5 years - 8 feet; largest on record - 13 x 17 feet. The bark is gray-brown.
The sharp pointed, slightly curved, fine, needle-like phyllode leaves are up to 3.2 (rarely over 2) inches in length. The foliage is gray-green.
Masses of bright yellow ball-shaped flowers are borne in late winter and spring.
Hardy zone 9 to 11. Hardy in Tucson

Acacia hebeclada
Some records include: 1 year - 3 x 5 feet; 2 years - 4 x 8 feet; 3 years - 7 feet. Eventual height of 8 feet.
Hardy zones 9 to 10 (tolerates 16 F with slight damage).

Acacia hemsleyi
A small tree, reaching a maximum height of 23 feet, that is native to far northern Australia. Some records include: 2 years - 14 feet with a trunk diameter of 6 inches.
The narrow, oblanceolate leaves are up to 5 x 0.5 inches in size.

The rod-shaped flower spikes are up to 1.3 inches in length..
Only marginally hardy in Tucson.

Acacia heroensis
Some records include: 3 years - 6 feet.
Hardy zones 9 to 11 (tolerating 16 F with slight damage). Hardy in Tucson

Acacia holosericea
A rapid growing, thornless, spreading, small tree that typically only lives around 12 years.
Some records include: 1.5 years - 13 feet with a trunk diameter of 4 inches; 3.5 years - 16 feet; largest on record - 27 feet.
The narrow elliptical leaves are up to 10 x 4 (rarely over 8 x 2) inches.
The foliage is luxuriant blue-green.
The rod-shaped flower spikes are golden-yellow.
Hardy zone 10 though may extend somewhat into zone 9, it is only marginally hardy in Tucson.
Saline soil and flood tolerant.

Acacia howittii (Howitt's Wattle)
A very fast growing, dense, rounded, gracefully weeping tree native to a resticted range in southeast Australia. Some records include: fastest recorded growth rate - 6.6 feet; largest on record - 30 x 10 feet. It makes an excellent tall hedge plant.
The spicy fragrant, narrow elliptical phyllode leaves, up to 1 x 0.3 inches, are deep green.
The fragrant, lemon-yellow flower-balls are borne in masses during spring.
Hardy zone 9 to 10 tolerating as low as 19 F, thriving in full sun or partial shade.
It can tolerate heavy pruning.

Acacia implexa (Hickory Acacia)
A fairly open, erect, long lived shade tree that is native to near coastal and coastal areas of eastern Australia.
Some records include: 3 years - 4.5 feet; largest on record - 53 x 50 feet with a trunk diameter of 1 foot.
The curved phyllode leaves, up to 8 x 1 inches, are green.
The creamy-yellow flower-balls are borne in long racemes during summer and early autumn.
The bark is rough and grayish.
Hardy zones 8 to 11 in sun to partial shade.
Pharmacology: considered Psychoactive

** photo of unknown internet source*

Acacia iteaphylla
A fast growing, bushy, spreading, large weeping shrub reaching a maximum size of 18 x 18 feet that is native to southern Australia.
The broad linear leaves, up to 5.5 x 0.3 (rarely over 4) inches in length, are gray-green.
The fragrant, pale yellow flowers are borne in autumn and winter.
The bark is green on young plants.
Hardy zones 8 to 10. Drought tolerant.

Acacia jennerae
A moderate growing evergreen large shrub or small tree that is native to New South Wales in Australia.
Some records include: 2 years - 11 feet; 3 years - 14 feet; 5 years - 16 feet; largest on record - 20 x 12 feet.
The narrow-elliptical leaves, up to 4.5 x 1 inches, are silvery-blue.
The puffball flowers are golden-yellow.
The bark is reddish-brown.
Hardy zones 9 to 11 (fully hardy to 15 F) and thrives in Tucson.

Acacia karroo (Karroo Thorn)
Also called Acacia horrida. A fast growing, rounded, spreading, medium-sized, deciduous tree that is a widespread native in southern Africa. Some records include: fastest recorded growth rate - 3.5 feet; 2 years - 8 feet; 3 years - 13 feet; 6 years - 16 feet; 7 years - 20 feet; 11 years - 25 feet; largest on record - 70 x 60 feet with a trunk diameter of 1.5 feet. The Karroo Thorn can live up to 300 years. It is naturalized in southern Europe where it is grown as a screen.

The bipinnate leaves, up to 5 x 2 inches, are deep green.
The profuse, sweetly fragrant, deep yellow, ball-shaped flowers are borne at the branch tips during summer though sometimes into autumn.
The orange-red twigs are armed with paired white thorns, up to 2 inches in length.
The smooth bark is brownish-gray.
Hardy zones 8 to 11. Flood tolerant. Invasive roots may be a problem on restricted sites.
Pharmacology: Psychoactive

Acacia kempeana
A spreading large shrub to small tree, reaching a maximum height of 17 feet, that is native to central Australia. Some records include: 6 years - 10 feet.
The narrow elliptical leaves, up to 3.5 x 1 inches, are gray to blue-green.
The dense, golden-yellow flower spikes are up to an inch in length.
The bark is furrowed and brown.
Hardy zones 9 to 10 (fully hardy to 16 F), thriving in warmer parts of the U.S. desert southwest.

Acacia kettlewelliae
A bushy, small tree, reaching a maximum height of 33 feet, that is native to far southeast Australia.
The narrow, elliptical leaves, up to 4 x 0.3 inches, are blue-green to green.
The golden-yellow, puffball flowerheads are borne on clusters, up to 2.5 inches in length.
Hardy zones 8b to 10, is known to exceed 15 feet in the British Isles.

Acacia koa (Koa)
A large, massive trunked, dense, bushy tree native to mountains of Hawaii that can reach over 100 feet and is a close relative of Acacia melanoxylon and Acacia confusa.
Some records include: fastest recorded growth rate - 7 feet; 2 years - 17 feet; 5 years - 33 feet with a trunk diameter of 1 foot; 20 years - 100 feet; largest on record - 140 x 150 feet with a trunk diameter of 11 feet.
The lance-shaped, phyllode leaves, up to 10 inches in length, are gray-green.
The pale yellow ball-shaped flowers are borne in axilliary clusters during spring.
Hardy zone 9 to 11. It's tough timber is valuable for the use in carving and the making of canoes.

** photo of unknown internet source*

Acacia lanigera (Woolly Wattle)
A rigid, rounded to spreading shrub native to far southeast Australia, reaching a maximum size of 10 x 10 feet.
The rigid, narrow-elliptic, phyllode leaves, up to 2.3 x 0.4 inches, are bright green.
The bright yellow flowers are borne in globular flowerheads borne from the leaf axils during late winter and early spring. They are followed by densely hairy, curled, brown pods.
The branches are covered in dense woolly hairs.
The bark is gray.
Hardy zones 8 to 11 and somewhat flood tolerant. Prune after flowering to encourage new growth and dense habit.

Acacia leiocalyx (Curracabah)
An attractive small tree, reaching a maximum height of 33 feet, that is native to the central part of Australia's east coast. Some records include: 2 years - 9 feet with a trunk diameter of 2 inches; 3 years - 12 feet; 4 years - 18 feet.
The narrow-elliptical phyllode leaves, up to 7 x 1.4 inches, are blue-gray.
The very profuse, showy, pale-yellow flowers are borne on rod-shaped clusters.
The branches are reddish.
The flaky, fissured bark is gray-brown.
Hardy zones 9b to 10 (tolerates 21 F with slight damage)

Acacia leucophloea
A large tree with attractive white-gray bark. Some records include: 5 years - 35 feet; largest on record - 120 x 100 feet with a trunk diameter of 5 feet.

It can live up to 100 years.
Tolerates temperatures anywhere from 30 to 122 F and is very drought tolerant.

Acacia leurderitzii
Some records include: 2 years - 14 feet; 5 years - 22 feet. Eventual size of 25 feet.
Hardy in Yuma.

Acacia ligulata (Dune Wattle)
A dense, spreading shrub, reaching a maximum size of 13 x 13 feet, that is native to central and southern Australia.
The narrow-elliptical leaves, up to 3 x 0.5 inches, are deep green.
The deep golden-yellow, ball-shaped flowerheads, up to 0.3 inches across, are borne on short racemes that are borne from the leaf axils.
The branchlets are light brown.
Hardy zones 9 (tolerating 15 F)

Acacia linifolia (Flax Wattle)
A fast growing, graceful, open, airy, erect to pendulous slender shrub reaching up to 20 x 12 feet, that is native to woodland understories around Sydney, Australia.
The branching is slender and arching.
The crowded, linear phyllode leaves are up to 2 inches in length.
The yellow ball shaped flowers are borne 6 to 12 on slender axilliary racemes, up to 2 inches in length, during summer and fall though sometimes persisting into late winter.
Hardy zones 9 to 11 tolerating as low as 20 F

Acacia longifolia (Sydney Golden Wattle)
A fast growing, short trunked, bushy, spreading small tree native to southeastern Australia.
Some records include: fastest recorded growth rate - 7 feet; 6 years - 27 feet; 20 years - 37 x 37 feet; largest on record - 37 x 82 feet; largest in Seattle - 26 feet.
It makes an excellent windbreak and screen.
The thick, straight, narrrow-elliptic, willow-like, leathery, phyllode leaves, up to 10 x 1.5 inches, are heavily longitudinally veined. The foliage is deep green.
The abundant bright yellow flower spikes are borne in erect racemes up to 3 inches in length all along the branches during winter and spring.
Hardy zones 9 to 11 tolerating as low as 19 F; it grows in milder parts of Cornwall, England and there are unconfirmed reports of zone 8 hardiness. Tolerant of limey soils.
Pharmacology: plant contains 0.2% DMT

Acacia macradenia (Zigzag Wattle)
A pendulous shrub, reaching a maximum size of 17 x 13 feet, that is native to northeastern Australia.
Some records include: 3 years - 8.5 feet.
The long, narrow-oblong phyllode leaves are up to 10 x 1 inches in size.
The flower clusters, up to 2 inches in length, contain 8 to 15 flowers.
Hardy zones 9 to 11 (estimate)
Pharmacology: Tryptamine

Acacia macrantha (Steel Acacia)
A small tree to 25 feet that is very similar to the Twisted Acacia that is native to southern Florida and the Caribbean. Some records include: largest on record - 50 x 45 feet with a trunk diameter of 1 foot.
The flowers are followed with pods up to 5.5 inches in length.
Hardy north to zone 9.

Acacia maidenii (Maiden's Acacia)
A medium size tree reaching a maximum size of 66 x 18 (rarely over 50) feet that is native to southeastern Australia. Long-lived, this tree can persist over 100 years.
Not a real massive tree, trunk diameters over 1 foot are extremely rare.
The narrow-elliptic phyllode leaves are up to 8 inches in length.
The creamy-yellow to bright yellow flowers are borne on rod-like spikes, up to 2.3 inches in length.
The flower spikes are borne from the leaf axils.
The branches are light brown. The deep gray-brown bark is smooth on young trees, becoming deeply fissured on older plants.
Hardy north to zone 9 tolerating as low as 19 F. Flood tolerant.
Pharmacology; stem bark contains 0.6% NMT and DMT in 2:3 ratio. The foliage contains both.

Acacia mangium (Black Wattle)
A large spreading tree, up to 120 feet; that native to coastal areas in far northern Queensland, Australia as well as southern New Guinea and the southern Molucca Islands. The Black Wattle makes an excellent shade tree. Some records include: 1st year - 10 feet; 3 years - 50 feet; 5 years - 80 feet with a trunk diameter of 10 inches; 14 years - 100 feet with a trunk diameter of 16 inches; largest on record - 170 x 40 feet with a trunk diameter of 3 feet.
The conspicuous veined, large, lance-shaped to elliptical leaves, up to 12 x 4 inches, are deep green.
The rod-like, creamy-white flowers, up to 5 inches in length, are borne in summer and fall. Twisted, woody pods in clusters follow.
The branches are stout.
The coarsely ridged and cracked bark is gray to dark brown.
Hardy zones 9 to 12 thriving where annual rainfall exceeds 40 inches.
Pharmacology: Psychoactive

** photo of unknown internet source*

Acacia meansii (Late Black Myrtle)

A large, upright, spreading tree native to forests of southeast Australia. Some records include: fastest recorded growth rate - 17 feet; 1 year - 17 feet with a trunk diameter of 1 inch; 2 years - 27 feet; 3 years - 35 feet; largest on record - 100 x 33 feet with a trunk diameter of 2 feet.

It makes for an excellent shade and shelter tree.

The ferny bipinnate leaves, up to 6 inches in length, are glossy deep green.

The profuse, light yellow, globular flowers are borne in loose clusters up to 6 inches in length during late spring to early summer.

The smooth gray to blackish bark becomes corrugated at the base on very old trees.

Hardy zones 7 to 11 thriving in climates with 18 inches of more of rainfall per year.

Drought tolerant.

Acacia melanoxylon (Blackwood Acacia)

A, fast growing, tall, dense broad crowned evergreen tree, up to 150 feet, that is native to coastal eastern Australia and Tasmania. Some records include: 6 years - 33 feet with a trunk diameter of 8 inches; 20 years - 50 x 23 feet; 30 years - 66 feet (average); 40 years - 108 feet; largest on record - 200 x 70 feet with a trunk diameter of 10 feet; largest in England - 90 feet with a trunk diameter of 3 feet. With ideal conditions, it is a long lived tree, persisting well over 150 years.

Used as a street tree in California.

The heavily longitudinally-veined, long, curved, narrow, phyllode leaves, up to 7 x 1 inches, are deep green.

The profuse, light yellow, puffball flowers, up to 0.4 inches across, are borne in masses during late winter and early spring.

The strong, close-grained, dark timber is valuable for making cabinets.

Hardy zones 8 to 10 (tolerating as low as 8 F) in sun to partial shade on a sheltered site on fertile, moist soil. Thrives in parts of England. The Blackwood requires a yearly rainfall between 30 and 72 inches per year.
Tolerant of flooding, salt, wind, smog, heat and shade.
it hates drought and is very prone to borer attack in warm areas.
In South Africa it has escaped into the wild and become a weed.
Pharmacology: bark and leaf contains <0.02% DMT Acacia mellifera A rounded, small tree reaching up to 30 feet that is native to dry regions of Africa, Saudi Arabia & India. It often forms dense inpenetrable thickets in the wild. Some records include: 2 years - 6 feet; 4 years - 10 feet; 11 years - 15 feet. The leaves and stems are rich in protein and are great for feeding livestock in dry regions. The fragrant, creamy-white flowers are borne on short, dense, hanging spikes. The stems are armed with very sharp, recurved thorns. The bark is smooth and gray. Hardy zones 9 to 11 (fully hardy to 16 F). Hardy in Tucson. Thrives where rainfall averages 16 to 32 inches and is clay tolerant. Pharmacology; leaf contains DMT. Acacia milleifolia (Santa Rita Acacia) A very attractive, medium-sized shrub. Some records include: 2 years - 5 feet; eventually up to 8 feet. The pinnate leaves are composed of linear leaflets. The foliage is luxuriant mid-green. The white flowers are borne on showy, rod-like clusters. Hardy zones 9 to 11 (tolerating 16 F with slight damage). Hardy in Tucson. Acacia melvillei (Yarran) A very rare Acacia that is native to southeastern Australia. It is a large shrub to small tree, reaching a maximum size of 50 x 38 feet with a trunk diameter of 20 inches. It is long-lived and trees can persist as long as 150 years. Acacia omalophylla is nearly identical but occurs at higher elevations in the same region of Australia. The narrow willow-like leaves, up to 4.3 x 1 inches, are mid-green. The showy flowers are yellow. Hardy zones 9 to 10 in full sun. Drought and lime tolerant. Acacia modesta A fast growing, medium-sized, deciduous tree, that is native to western Pakistan, Afghanistan and India. Some records include: 2 years - 9 feet; 3 years - 15 feet; 10 years - 22 feet. The double pinnate leaves are up to 2 inches in length. The stems are armed with deep brown thorns, up to 0.25 inches in length. The bark is greenish-gray on young trees, later turning rough and brownish. The wood is hard and durable. Hardy zones 9 to 10. Thrives in Tucson Acacia mollifera (Velvet Acacia) A multi-stemmed, pendulous, small to medium size, evergreen tree native to Australia. Some records include: fastest recorded growth rate - 2 feet; largest on record - 40 feet. The double-pinnate leaves, up to 2.5 inches in length, are silvery-gray. Up to 42 golden-yellow puffball flowers may be borne in a cluster. The stems are densely tomentose. The brown to grayish-black bark is smooth except for becoming fissured near the base on older trees. Acacia montana (Mallee Wattle) A multi-stemmed, large shrub, reaching a maximum size of 13 x 20 feet, that is native to southeastern Australia. Some records include: 6 years - 5.5 feet. The narrow oblong leaves are up to 1.6 x 0.3 inches in size. The golden-yellow puffball flowers, up to 0.3 inches across, are borne from the leaf axils. The stems are either sparsely thorned or have no thorns at all. Hardy zones 9 to 10 (fully hardy to 16 F). Hardy in Tucson Acacia montigena A vining rainforest Acacia, reaching a maximum height of 100 feet, that is a widespread native to Africa. The double-pinnate leaflets are composed of linear leaflets. The young branched are dark brown to black. Hardy zones 10 to 12 Acacia mosambique Some records include: largest on record - 100 x 85 feet with a trunk diameter of 5 feet. Acacia mucronata Similar to Acacia longifolia but is slightly hardier and with very narrow phyllode leaves up to 8 x 0.3 inches. It is taller growing but more narrow in habit, reaching a maximum height of 50 feet. It is native to southeastern Australia including Tasmania. Acacia muelleriana (Mueller's Wattle) An attractive,bushy, multi-stemmed, spreading small tree native to eucalyptus forests in Queensland & New South Wales in Australia. Some records include: 3 years - 13

feet; largest on record - 27 x 20 feet. The double-pinnate leaves are deep green. The leaflets are linear, up to 1.5 inches in length. The creamy-yellow flowers are borne in heads during spring and summer. They are followed by narrow seed pods up to 6 inches in length. The smooth bark is yellow-brown to gray. Hardy zones 9 to 11 Acacia murrayana (Murray's Wattle) A fast growing, small tree, reaching a maximum size of 27 x 27 feet with a trunk diameter up to 8 inches. It is native to central Australia where it often forms suckering colonies in the wild. Some records include: 3 years - 5 feet. The oblanceolate leaves, up to 7 x 0.5 inches, are bright green to blue-green. The showy, golden-yellow flowerballs are borne on clusters up to 2.5 inches in length. Hardy zones 9b to 11 in dry climates. Acacia myrtifolia (Myrtle Wattle) A fast growing, bushy, low to medium size shrub reaching a maximum size of 10 x 10 feet that is native to southern Australia. The erect, lance-shaped to narrow-elliptic, phyllode leaves, up to 6 x 1.3 inches, are reddish at first, turning to deep green. The fluffy, creamy-yellow flowerballs, up to 0.5 inches across, are borne in short racemes, up to 4.5 inches, over a long season during winter and spring. The stems are red. The bark is smooth and gray. Hardy zones 8 to 11 in full sun to partial shade. Prune lightly after flowering to promote new growth.
** photo of unknown internet source*





Acacia nebrownii (Water Acacia)
A moderate growing, dense, semi-evergreen large shrub to small tree reaching a maximum size of 23 x 20 (rarely over 17) feet, that is native to dry parts of southern Africa.
Some records include: 2 years - 8 feet; 3 years - 12 feet; 5 years - 14 feet.
The double-pinnate leaves, up to 1.3 x 0.8 inches, are green.
The showy flowers are golden-yellow.
The yellow to orangish stems are armed with white thorns, up to 2.3 inches in length.
The bark is smooth and reddish.
Hardy zones 9 to 10 (tolerating as low as 18 F) in full sun. It will freeze to the base at 16 F but will regrow rapidly the following spring.
It is tolerant of both flooding and temporary drought.

Acacia neovernicosa (Varnish Acacia)
Also called Chihuahuan Whitethorn. An upright shrub, reaching a maximum size of 13 x 8 feet, that is native from Arizona and southern New Mexico into Mexico. Some records include: 2 years - 7 feet; 4 years - 10 feet; 7 years - 13 feet.
The leaves are double-pinnate.
The puffball flowers are bright yellow.
Hardy zones 7a to 11 in full sun. Tolerant of severe drought and alkaline soil.

Acacia neriifolia (Oleander Wattle)
A fast growing, open, erect, small tree, reaching a maximum size of 50 x 30 (rarely over 30) feet, that is native to eastern Australia. Some records include: 3 years - 7 feet.
The linear to narrow-elliptic, willowy, phyllode leaves, up to 8.5 (rarely over 6) inches in length, are downy white at first turning to blue-green.
The abundant, showy, golden-yellow flower puffballs, up to 0.3 inches, are borne on long narrow axilliary racemes up to 4 inches in length during late spring into early summer.
The gray bark becomes fissured on older trunks.
Hardy zones 9 to 11 in full sun on well drained soil. It prefers a climate with 20 to 28 inches of average yearly rainfall. The seeds require 1 minute immersion in boiling water to break dormancy.

Acacia nigrescens
A shapely, rounded, large tree, that is native to Africa. Some records include: fastest recorded growth rate - 2 feet with a trunk diameter increase of 1.3 inches; largest on record - 80 x 70 feet with a trunk diameter of 3 feet.
Long lived, this tree can exceed 300 years in age.
It makes an excellent shade tree where it is adapted.
The bipinnate leaves are composed of leaflets up to an inch in length.
The very showy, creamy-white flower spikes are borne before the new foliage emerges.
The bark is dark brown to black. The trunk is characteristically covered in thorn tipped knobs.
Hardy zones 9a to 11 in full sun on well drained soil It can thrives where average rainfall is anywhere between 15 and 90 inches in a year though preferring a dry season. Drought tolerant.

Acacia nilotica (Egyptian Acacia)

A rapid growing, dense, rounded, large tree native to drier parts of tropical Africa as well as from Saudi Arabia to India. Some records include: 1 year - 6 feet; 2 years - 12 feet; 3 years - 18 feet; 4 years - 23 feet; 6 years - 25 feet; 10 years - 30 feet; largest on record - 82 x 40 feet with a trunk diameter of 4 feet. It should not be planted in Australia where it can spread into the wild and become an invasive weed. A very attractive landscape tree resembling the Honey Locust in appearance.

The bipinnate leaves, up to 6 (rarely over 3) inches in length, are composed of 0.3 inch leaflets. The deep green foliage can either be deciduous or evergreen depending upon moisture conditions.

The flower puffballs are golden-yellow.

The stems are armed with paired, straight spines up to 3 inches in length.

The deeply fissured bark is dark brown.

Hardy north to zone 9b tolerating as low as 26 F and as well as hot as 120 F. It is both tolerant of flooding, saline soil and also drought, surviving in climates with as low as 14 inches of rainfall per year. It is recommended to direct seed it into its permanent position since transplanting is difficult due to its deep taproot.

Pharmacology: leaf contains DMT

** photo of unknown internet source*


Mimoſa nilotica. L.

Acacia notabilis (Notable Wattle)

Also called Flinder's Wattle. A moderate growing, bushy, spreeading shrub, reaching a maximum height of 17 feet, that is native to southeastern Australia. Some records include: 2 years - 5 feet.

The oblanceolate leaves, up to 5 x 1 inches, are blue-green.

The bright yellow flower puffballs, up to 0.3 inches across, are borne on clusters up to 2.5 inches in length.

The twigs are deep reddish-brown. The bark is smooth and red to gray-brown.
Hardy zones 9 to 10 (fully hardy to 17 F)

Acacia obtecta
A very attractive, slow growing, bushy, rounded shrub,, reaching a maximum size of 13 x 13 feet, that is native to southwestern Australia. Some records include: 8 years - 6 feet; 11 years - 7.5 feet. It is great for soil stabilization where it is adapted.
The linear to oblanceolate leaves, up to 4.5 x 0.3 inches, are dull green.
The showy, bright yellow, flower puffballs, up to 0.4 inches, are borne 2 to 4 on axilliary clusters.
The bark is smooth and pale gray.
Hardy zones 9 to 11 (foliage damage only at 16 F) on sand or clay, preferring a Mediterranean climate.
To propagate, boil the seed for 5 minutes to break dormancy.

Acacia occidentalis (Sonoran Catclaw)
A thorny deciduous tree native to the Sonoran Desert in Mexico that is basically a larger version of Acacia greggii reaching a maximum size of 40 x 40 feet.
Some records include: 2 years - 6 feet; 5 years - 10 feet; 10 years - 20 feet.
The deciduous, compound foliage is gray-green. It casts dense shade.
The creamy ball shaped flowers are borne during spring.
The twisted branches are covered in sharp spines.
Hardy zones 9 to 11 (fully hardy to 15 F). Extremely heat and drought tolerant.
Very hardy in Tucson

Acacia odoratissima (Black Siris)
Correctly called Albizzia odoratissima. Some records include: 2 years - 10 feet; 5 years - 17 feet with a trunk diameter of 6 inches; largest on record - 133 feet with a trunk diameter of 5 feet.
The bipinnate leaves, up to 8 inches in length, are composed of leaflets up to 1.5 x 0.5 inches in size.
The foliage is deep green.
The fragrant, creamy-white flowers are borne 10 to 12 on terminal panicles up to 8 inches in length.

Acacia oxycedrus (Spike Wattle)
A stiff prickly large shrub or small tree reaching a maximum size of 33 x 7 feet, that is native to far southeastern Australia.
The sharp pointed, flat, rigid, lance-shaped phyllode leaves, up to 1.6 x 0.2 inches , are whorled around the stens.
The very showy, dense, light yellow flower spikes, up to 2 inches in length, appear during winter and spring.
The stems are prickly making this an excellent barrier hedge.
The gray-brown bark is smooth, becoming lightly fissured on older plants.
Hardy zones 8 to 10

Acacia pachyacra (Casuarina Acacia)
A bushy shrub, reaching a maximum size of 17 feet, that is native to desert areas of west central Australia. Some records include: 2 years - 6.5 feet; 3 years - 9 feet; 4 years - 12 feet. It resembled the

Casuarina in appearance.
The very linear leaves, up to 8 x 0.04 inches, are bright green to gray-green.
The tiny, golden-yellow flowerballs are borne on clusters, up to 1.3 inches in length.
The branches are reddish-brown.
Hardy zones 10 to 11 (est)

Acacia papyrocarpa (Western Myall)
A slow growing, very dense, rounded to spreading, small tree, reaching a maximum size of 33 feet, that is native to southwestern and south central Australia.
Some records include: 3 years - 7 feet; longest lived - 1000 years.
The very linear leaves, up to 5 x 0.1 inches, are silvery.
The golden-yellow flowerballs are borne on clusters up to 2.5 inches in length.
The bark is gray and fissured.
Hardy zones 9 to 10, (fully hardy to 16 F). Very drought tolerant.

Acacia paradoxa (Kangaroo Thorn)
Also called Acacia armata. A very ornamental, dense, , twiggy, spiny, large shrub to small tree reaching a maximum size of 25 x 25 (rarely over 17 x 13) feet that is a widespread native to southeastern Australia as well as Australia's extreme southwest. It makes an excellent barrier hedge.
It should not be planted in California where it may become an invasive noxious weed.
The wavy edged, narrow-oblong phyllode leaves, up to 1.6 x 0.3 inches, are deep green.
The profuse large, golden-yellow flowerballs, up to 0.5 inches, are borne singly or paired along the stems during late winter and spring.
The stems are armed with needle-like spines.
The finely fissured bark is gray-brown.
Hardy zones 8 to 11, tolerant of extended drought.
It can be pruned lightly one a year to shape.

** photo of unknown internet source*



Acacia pataczekii (Pataczek's Acacia)
A vigorous, handsome, suckering, small tree, that is native to Tasmania. Some records include: 30 years - 20 feet with a trunk diameter of 7 inches.
The narrow-oblong leaves, up to 2.4 x 0.8 inches, are blue-green.
The bright yellow flowerballs are borne on clusters up to 4 inches in length.
The branchlets are dark reddish.
Thrives in milder parts of England.

Acacia patagiata
A rounded to spreading shrub, reaching a maximum size of 8 feet, that is native to far southestern Australia. Some records include: 2 years - 3 x 6 feet; 6 years - 6 feet.
The erect, narrow-oblong phyllode leaves, up to 2.2 x 0.3 inches, are luxuriant blue-green.
The showy, bright yellow flowerballs, up to 0.2 inches across, are borne from the leaf axils.
Hardy zones 9 to 10 (hardy with foliage damage only 16 F) in full sun thriving on well drained sand or clay. Prefers a mediterranean climate.

Acacia pendula (Weeping Myall)
A stunning, slow growing, dense, gracefully weeping tree that is a widespread native to dry regions of eastern Australia.
Some records include: 3 years - 6 feet; largest on record - 48 x 44 feet with a trunk diameter of 25 inches. Long lived, it makes an excellent street tree or windbreak.
The narrow-elliptic phyllode leaves, up to 5.5 x 0.5 inches, are silvery or bluish.
The small, light yellow flowerballs, up to 0.2 inches, are borne 2 to 7 on axilliary racemes, up to 0.6 inches in length. The flowers are borne randomly throughout the year and are not very showy.

The fissured bark is gray or dark brown.
The close grained timber is hard and aromatic.
Hardy zones 9 to 11 tolerating as low as 15 F, thriving in climates with 18 + inches of rainfall per year.
Thrives on well drained soil with infrequent deep watering.
Tolerant of salty soil, drought, temporary flooding and clay. Deer resistant.

Acacia pennatula
A fast growing, dense, very tropical looking tree reaching a maximum size of 50 x 50 feet, that is native to Mexico. Some records include: 2 years - 7 feet; 4 years - 12 feet with a trunk diameter of 3 inches; 5 years - 14 feet; 7 years - 20 feet.
The bipinnate leaves, up to 7 x 1.5 inches, have large feathery pinnae.
The foliage is mid-green.
The bright yellow flower puffballs are borne during spring.
The stems are armed with small paired thorns from the leaf axils.
The fissured bark is brownish-gray.
Hardy zones 10 to 11 in full sun on well drained soil.
Tolerates extreme and reflected heat, even in Yuma, Arizona.
Pharmacology: may contain anticancerous properties.

Acacia penninervis
An erect to spreading, small tree, reaching a maximum height of 27 feet, that is native to the central part of Australia's east coast.
The narrow-elliptic leaves, up to 6.5 x 1.6 inches, are green to blue-green.
The creamy-white flowerballs, up to 0.4 inches across, are borne 15 to 30 on clusters up to 5 inches in length.
The finely to deeply fissured bark is dark gray.
Hardy zones 10 (est)

Acacia permixta (Hairy Acacia)
A shrub that is native to southern Africa. Some records include: 3 years - 7 feet.
The bipinnate leaves are similar to that of the Honeylocust in appearance.
The flower puffballs are bright yellow.
The stems are armed with sharp white thorns.
Hardy zones 9 to 11 (slight damage only at 16 F)

Acacia peuce
A pendulous, medium size tree, reaching a maximum size of 50 x 40 feet, that is native to the Simpson Desert in central Australia.
The extremely narrow leaves are up to 16 x 0.04 (rarely over 6) inches. The foliage is similar in appearance to that of the Casuarina.
The wood is extremely hard.
Hardy zones 8a to 10. Has extreme tolerance of both heat and drought and can survive in climates with as little as 5 to 8 inches of yearly rainfall.

Acacia podalyriifolia (Pearl Acacia)
A very fast growing, highly ornamental, evergreen, slender to spreading, small tree reaching a maximum size of 27 x 27 feet that is native to coastal regions of southern Queensland Australia.
it is typically short lived due to disease and borers.
It is popular as a landscape/street tree for its attractive, silvery, oblong or elliptic, phyllode leaves, up to 2 x 1 inches.
The abundant, very fragrant, golden-yellow flowerballs, up to 0.3 inches, are borne 15 to 30 on dense clusters up to 6 inches in length from early winter into spring.
The stems are downy at first, later turning silvery-gray and smooth. Older trees develop a very attractive blue-green trunk that is finely fissured.
Hardy zones 9 to 11 tolerating as low as 19 F and average yearly rainfall as low as 18 inches. Very clay tolerant. Can be pruned hard after flowering.
Pharmacology: fresh bark contains 0.5% to 2% DMT.

Acacia polyacantha (White Thorn)
A fast growing, layered and flat crowned, semi-deciduous, large tree native to central Africa. Some records include: 1 year - 10 feet; 2 years - 16 feet; 3 years - 20 feet; 5 years - 28 feet; 10 years - 30 feet; largest on record - 82 x 60 feet.
The ferny bipinnate leaves are composed of 11 to 27 pairs of pinnae. The foliage
is luxuriant mid-green.
The narrow, long flower-spikes are creamy-white.
The stems are armed with hooked thorns that often persist on older stems.
The bark is yellow-brown.
Hardy north to zone 9a
Pharmacology: leaf contains DMT

Acacia pravissima (Ovens Wattle)
An extremely fast growing, pendulous, spreading, small evergreen tree native to hill country of southeast Australia.
Some records include: 2 years - 4 feet; 4 years - 6 feet; 20 years - 30 feet; largest on record - 42 x 30 feet with a trunk diameter of 1 foot.
The spine-tipped, triangular, phyllode leaves, up to 0.8 x 0.6 inches, are gray to olive green.
The profuse, golden-yellow, ball-shaped flowers are borne in long racemes up to 4 inches in length during late winter to early spring.
The gray bark is smooth becoming finely-fissured on older trees.
Hardy zone 8 to 10 (tolerating as low as 8 F) in full sun (tolerates partial shade) on humus-rich, well drained soil on a site protected from excessive wind. Thrives on the west coast north to Seattle as well as in England as long as it is planted on a warm sheltered site.
Ovens Wattle prefers consistent moisture but can tolerate the occasional drought. Deer resistant.
Prune after flowering.

'Golden Carpet'
A groundcover form that is low growing, reaching a maximum size of 16 inches x 20 feet.
The tringular leaves are up to 0.4 x 0.3 inches. The profuse yellow flowerballs are up to 0.2 inches across.

Acacia prominens (Gossford Wattle)
An attractive, dense, long lived tree reaching a maximum size of 82 x 45 feet, that is native to a very tiny area near Gossford in southeastern Australia.
It makes a spectacular lawn tree.
The narrow-oblong, blue-green, phyllode leaves are up to 2.5 x 0.5 inches, are blue-green.
The profuse, showy, sweetly fragrant, light yellow flowerballs, up to 0.2 inches, are borne in dense clusters, up to 2.3 inches in length, during late winter and early spring.
The bark is smooth and gray.
Hardy zones 9 to 11 tolerating as low as 19 F. Prefers a shaded sheltered position and moist soil.

Acacia pruinocarpa (Black Gidge)
A fast growing, thornless, small evergreen tree reaching a maximum size of 40 x 30 feet that is native to central and western (not southwestern) Australia.
The linear to narrow-elliptic, thick, leathery leaves, up to 7 x 1.3 inches, are gray-green.
The bright yellow flowerballs, up to 0.3 inches, are borne on racemes up to 6 inches in length, during spring.
Hardy zones 9 to 11 (tolerating 18 F but defoliates at 22 f).

Acacia pruinosa (Frosty Acacia)
A medium size tree native to southeast Australia. Some records include: fastest recorded growth rate - 3 feet; 25 years - 50 feet; largest on record - 60 x 40 feet.
The bipinnate leaves, up to 4 inches in length, have pinnae in 5 pairs. The narrow oblong leaflets are up to 0.7 x 0.25 inches. The foliage is bronze at first, turning to blue-green.
The golden-yellow flowerballs, up to 0.4 inches across, are borne on racemes up to 6 inches in length.
The branches are glossy and reddish. The bark is smooth and reddish-purple.
Hardy north to zone 9

Acacia pubescens (Downy Wattle)
A showy, fast growing, pendulous branched, spreading shrub native to coastal South Wales, Australia where it is endangered due to habitat destruction in its tiny natural range around Sydney.
Some records include: 3 years - 8 feet; largest on record - 20 x 10 feet.
The deciduous, bipinnate leaves, up to 3 x 2 inches, are composed of leaflets, up to 0.2 inches in length. The foliage is silvery at first, turning to bright green.
The profuse bright yellow flowerballs, up to 0.25 inches, are borne 8 to 16 on dense drooping sprays, up to 4.3 inches in length, during late winter and spring.
The branches are soft, downy and dark reddish-brown. The bark is smooth and brownish-gray.
Hardy zone 9 to 11

Acacia pulchella (Prickly Moses)
A spiny, broad spreading, semi-evergreen shrub, reaching a maximum size of 10 x 5 (rarely over 4) feet, that is native to southwestern Australia.
The bipinnate leaves are divided into up to 11 pairs of tiny, narrow oblong leaflets, up to 0.25 inches.
The foliage is luxuriant mid-green.

The tiny, deep yellow flowers are borne in dense, rounded heads during spring.
The stems are armed with 1 to 2 axilliary spines, up to 0.8 inches in length, per node.
Hardy zones 9 to 10 in full sun on fertile, sandy soil. It prefers a mediterranean climate.

Acacia pustula
A small tree closely related to Acacia nerifolia that is native to semi-dry regions of southern Queensland in Australia. Some records include: largest on record - 50 feet.
The drooping, linear phyllode leaves are up to 6 x 0.5 inches.
The main ornamental feature is the masses of late winter light golden-yellow flowers.
The stems are dark reddish.
Hardy zones 9 to 11

Acacia pycnantha (Golden Wattle)
A fast growing, open branched, pendulous tree native to Eucalyptus forest on sandy soils in southern temperate regions of Australia. Some records include: 3 years - 13 feet with a trunk diameter of 3 inches; 4 years - 15 x 7 feet; 25 years - 35 feet; largest on record - 76 x 60 feet with a trunk diameter of 3 feet. It can sucker freely from the base. Golden Wattle is the floral emblem of Australia. It has also escaped into the wild and become a weed in South Africa. It is not a long lived tree, lasting an average of 30 years.
The pendulous, thick, leathery, oblanceolate phyllode leaves, up to 8 x 1.5 inches, are glossy rich green.
The profuse, sweetly fragrant, large, golden-yellow, ball-shaped flowers, up to 0.4 inches, are borne in long racemes up to 12 inches in length during late winter and spring.
They are followed by seed pods up to 4.7 inches in length.
The brown bark is smooth becoming finely fissured on older trees.
Hardy zones 8 to 10 thriving in climates with 14 to 40 inches of rainfall per year.
It prefers hot summers with low humidity. Young trees are not as frost hardy as older more established trees.

Acacia pyrifolia (Kanji Bush)
A shrub, reaching a maximum size of 15 (rarely over 10) feet, that is native to northwestern Australia.
The round leaves, up to 2.3 x 1.6 inches, are blue-gray.
The yellow flowerballs are borne on clusters up to 7 inches in length.
The bark is smooth and gray.
Hardy zones 10 to 11 (severe dieback at 21 F but resprouts vigorously) in semi-arid climates.

Acacia redolens (Prostrate Acacia)
An attractive, very fast growing, wide spreading, evergreen shrub that can be used for groundcover. It is native to far southwestern Australia. Some records include: 3 years - 2.5 x 8 feet; 7 years - 4 x 10 feet; largest on record - 6 x 28 (rarely over 5 x 12) feet.
The lance-shape to spathulate, gray to mid-green leaves are up to 3 x 0.5 inches.
The bright yellow flowerballs are up to 0.2 inches across.
Hardy zones 8a+ in full sun preferring a mediterranean climate. Tolerates drought and ocean salt winds.

'Desert Carpet'
A low groundcover form, reaching up to 2 x 15 feet.

Acacia rehmanniana (Silky Acacia)
A low, dome shaped to flat crowned tree native to southeastern Africa that can reach a maximum height of 30 feet.
The downy bipinnate leaves are bright golden-green at first, later turning to deep green. The foliage is deciduous during drought.
The sweetly fragrant, white, ball shaped flowers are borne in small clusters during summer.
The orangish-brown stems are armed with straight paired thorns.
Hardy zones 9 to 11 (diesback to base at 20 F but resprouts vigorously). Very drought tolerant.

Acacia retinodes (Swamp Wattle)
A semi-pendulous, rounded small tree, that is native to southeastern Australia.
Some records include: fastest recorded growth rate - 5 feet; first year - 5 feet; largest on record - 36 x 36 feet with a trunk diameter of 2 feet.
It is generally short-lived, lasting around 40 years.
The narrow, oblanceolate leaves, up to 8 x 0.6 inches, are blue-green to green.
The creamy-yellow flowerballs are borne on clusters up to 1.6 inches in length.
The bark is smooth and gray on young trees, on older trees becoming rough and blackish-brown.
Hardy north to zone 8b tolerating as low as 15 F. Thrives in England.^

Acacia rhetinocarpa
A spreading, dome-shaped, resinous, attractive shrub reaching a maximum height of 6.6 feet that is native to south central Australia where it is endangered.
The thick, curved, resinous, obovate phyllode leaves, up to 0.2 x 0.14 inches, are blue-green.
The profuse, bright-yellow, ball-shape flowers are borne singly in the leaf axils during late winter and spring.
Hardy zone 8 to 10. Tolerant of alkaline soil.

Acacia riceana (Rice's Wattle)
A pendulous small tree that is native to Tasmania. Some records include: 20 years - 27 x 20 feet; 23 years - 37 feet with a trunk diameter of 1 foot; largest on record - 37 x 30 feet
The rigid, pointed, linear to narrow-oblanceolate phyllode leaves, up to 2.2 x 0.1 inches, are deep green.
The creamy-white, ball-shaped flowers are borne in drooping spikes up to 1.5 inches in length.
Hardy north to zone 8 tolerating as low as 5 F. Heavy shade tolerant.

Acacia rigens (Needle Wattle)
Also called Acacia chordophylla & Acacia loderi. A fast growing, dense, rounded shrub to small tree, rarely exceeding 20 feet, that is widely native to dry regions of southern Australia. Some records include: largest on record - 32 x 23 feet with a trunk diameter of 1 foot. It is long lived and can survive as long as 100 years.
The sharp pointed, stiff, narrow phyllode leaves are up to 5.5 x 0.1 inches, is similar to that of the

Casuarina in appearance. The foliage is gray-green.
The profuse, golden flowerballs, up to 0.3 inches, are borne in small clusters during winter and spring.
The dark gray bark is finely fissured.
Hardy zones 8 to 10 in sun to partial shade. An excellent ornamental plant for arid and semi-arid climates.

Acacia rigidula (Blackbrush Acacia)
An extremely thorny, moderate growing, small tree native to south Texan and northern Mexican Chihuahuan desert. Some records include: fastest recorded growth rate - 2 feet; 4 years - 6 feet; 7 years - 9 feet; largest on record - 27 x 31 feet with a trunk diameter of 1 foot. An excellent lawn tree.
The foliage is deep green.
The stems are extremely thorny.
The attractive bark is pale gray.
Hardy north to zone 8 tolerating as low as 15 F. Requires full sun and is heat and very drought tolerant.
Pharmacology: contains Mescaline & DMT

** photo of unknown internet source*

Acacia rivularis
A bushy rounded shrub, reaching a maximum height of 17 feet, that is native to south central Australia. Some records include: 2 years - 8 feet; 4 years - 13 feet; 8 years - 16 feet. It is generally short-lived, lasting around 20 years.
The linear leaves, up to 5.5 x 0.2 inches, are mid-green.
The bright yellow flowerballs, up to 0.2 inches, are borne on clusters up to 1.6 inches in length.
The bark is gray and finely fissured.
Hardy zones 9b to 11 (est) in semi-arid climates.

Acacia robusta 'Ussumb'
A large tree with a massive deeply ridged trunk. Some records include: largest on record - 75 x 70 feet with a trunk diameter of 4 feet.
The leaves are up to 5 inches in length.
The spines are up to 4 inches or more in length.
Hardy north to zone 9b

Acacia roemeriana
A small evergreen tree native to Texas.
Some records include: 2 years - 6 feet; 7 years - 13 feet; largest on record - 25 x 25 feet with a trunk diameter of 1.6 feet.
The very fragrant flowers are white.
Hardy north to zone 7, it is fully hardy at Tucson.
Requires a deep well drained soil and is very heat tolerant as well as drought tolerant. It is not known to grow in the humid eastern U.S.

Acacia rostellifera
A fast growing, dense, spreading tree reaching a maximum size of 40 x 33 feet with a trunk diameter of 2 feet, that is native to southwestern Australia.
The narrow, oblanceolate leaves, up to 4.5 x 0.7 inches, are green to blue-green.
The golden-yellow flowerballs, up to 0.3 inches across, are borne on clusters, up to 1.3 inches in length.
The bark is fissured and dark gray.
Tolerates as low as 20 F, prererring a mediterranean climate. Thrives in Phoenix, Arizona.

Acacia rubida (Red-Stemmed Wattle)
A fast growing, small bushy tree native to much of southeastern Australia. Some records include: 5 years - 20 feet; largest on record - 45 x 20 feet.
The leathery, narrow, oblanceolate to narrow-elliptic phyllode leaves, up to 8 x 1 inches, are medium green during summer turning reddish during winter.
The profuse, bright yellow flowerballs, up to 0.3 inches across, are borne 10 to 20 on clusters up to 4 inches in length. The flowers are borne during late winter and spring.
The angular stems are deep red. The finely fissured bark is brown.
Hardy zones 8 to 10 tolerating as low as 8 F. Prefers full sun to partial shade and is flood tolerant as well as tolerant of drought.

Acacia salicina (Broughton Willow)
A medium size, evergreen tree native to tropical central and eastern Australia that is similar in habit to the Weeping Willow.
Some records include: 2 years - 10 feet; 4 years - 16 feet; 5 years - 20 feet; 10 years - 20 feet; largest on record - 90 x 70 feet with a trunk diameter of 2 feet.
It is long-lived, lasting for over 50 years in age.
It is a handsome foliage plant with narrow elliptical, blue-green leaves up to 8 x 1.3 inches.
The pale-yellow flowerballs, up to 0.3 inches across, are borne in clusters up to 2.5 inches in length.
The branchlets are dark gray-brown.

The bark is fissured and gray-brown.
Hardy zones 9 to 11 (fully hardy to 16 F though foliage is damaged at 18 F) on deep well drained soil in climates with 15+ inches of yearly rainfall. It is tolerant of flooding, saline soils and pure sand making it an excellent choice for rehabilitating sand dunes but is also good on clay. On dry, sandy soils, the roots can reach up to 50 feet or more in depth, on wet poorly drained soils this tree will be much more shallow roots and also much more prone to uprooting in high winds.

Acacia saligna (Blueleaf Acacia)
Also called Acacia cyanophylla or Orange Wattle. It is a fast growing, dense, bushy, pendulous small tree native to far southwestern Australia. Some records include: fastest recorded growth rate - 2 feet; 1 year - 7 feet; 2 years - 14 x 7 feet; 3.5 years - 21 feet; 4 years - 27 x 27 feet; largest on record - 33 x 33 feet. It has invasive potential in some climates and has become a weed in South Africa.
It typically only lives about 20 years.
The drooping, gray-green, lance-shaped phyllode leaves are up to 12 x 3 inches.
The profuse, large, fluffy, yellow flowerballs, up to 0.5 inches, are borne in racemes up to 3 inches in length during late winter and early spring.
The brownish-gray bark is smooth becoming finely fissured on older trees.
Hardy zones 9 to 11. Minor leaf burn at 19 F, stem damaged at 15 F. Drought tolerant, growing in regions with 8 to 40 inches of rainfall per year, making a great windbreak for northern Africa and the Middle East.
Prefers mediterranean winter rainfall climates.

Acacia schaffneri (Twisted Acacia)
An attractive, moderate growing, twisted, deciduous to evergreen, small tree, reaching a maximum size of 25 x 30 feet, that is native to the southwest U.S. (southeastern New Mexico & Texas), south to Oaxaca Mexico.
Some records include: 2 years - 8 feet; 4 years - 11 feet; 7 years - 14 feet; largest trunk diameter - 8 inches.
The finely-divided, ferny, bipinnate leaves, up to 6 inches in length, are gray-green.
The very fragrant, bright yellow flowerballs are up to 0.4 inches across.
The stems are viciously armed with long, 1 inch, paired, white thorns that originate from the leaf axils.
The bark is grayish-brown.
Hardy zones 8b to 10 (fully hardy at 15 F) in full sun on well drained soil.
It makes a great landscape tree in Arizona as well as in its native range.
Pharmacology: Contains mescaline & Amphetamine

Acacia schottii
A deciduous small shrub, reaching a maximum size of 6 x 5 (rarely over 4) feet, that is native to Texas and Chihuahua Mexico. Some records include: 3 years - 4 feet; 7 years - 6 feet.
The lacy bipinnate leaves are composed of linear leaflets. The foliage is bright green.
The showy, golden-yellow flowerballs are borne spring through summer.
The stems are armed with white spines up to 0.7 inches in length.
Hardy zones 8 to 10 (tolerating 10 F) in full sun on well drained soil.
Very tolerant of heat, drought, clay soil and lime.

Acacia sclerosperma (Limestone Wattle)
A dense, rounded, shrub or small tree, reaching a maximum size of 20 x 13 feet, that is native to western Australia. Some records include: 4 years - 9 feet.
The thick, linear to narrow-elliptic leaves, up to 5.5 x 0.7 inches, are blue-green.
The flowers are yellow.
The bark on the stems and branches is smooth and light gray.
Hardy zones 9b to 11 (est)

Acacia senegal (Senegal Gum Arabic)
A flat-topped, medium-sized, deciduous tree that is a widespread native to the plains of subsaharan Africa as well as Oman, Pakistan and northwest India. Some records include: largest on record - 66 x 66 feet with a trunk diameter of 4.3 feet.
The bipinnate leaves, up to 4 inches in length, are gray-green.
The fragrant white to pale yellow flowers borne in long spikes, up to 4 inches in length, appear autumn and winter.
At the base of each leaf are 3 fierce small pricles, one curves downward, the other 2 curve upward.
The attractive, gray-brown bark is pale and flaky.
Hardy zones 8 to 10 in full sun, thriving in climates with 10 to 15 inches of rainfall in an average year. It can survive droughts lasting up to 11 months and prefers a climate with a dry season lasting at least 5 months.

'leiorachis'
Some records include: 2 years - 6.5 feet; 4 years - 10 feet; 5 years - 16 feet; 9 years - 19 feet.

'rostrata'
Some records include: 2 years - 7 feet; 4 years - 10 feet; eventually up to 16 feet.

Acacia siculiformis (Dagger Myrtle)
A shrub, reaching up to 10 x 6 feet, that is native to far southeastern Australia including Tasmania.
The narrow lance-shaped to narrow-elliptic leaves, up to 1.5 x 0.2 inches, are green.
Thr bright yellow flowerballs, up to 0.3 inches across, are borne from the leaf axils.
The bark is smooth and gray.
Hardy zones 8 to 9, thriving on well drained soil.

Acacia sieberiana (Paperbark Thorn)
A very fast growing, flat-crownded, medium to large, deciduous tree native to southern Africa. Some records include: fastest recorded growth rate - 7 feet; 2 years - 14 feet; 3 years - 20 feet; 6 years - 28 feet; 7 years - 30 feet; 10 years - 40 feet; largest on record - 82 x 51 feet with a trunk diameter of 6 feet.
It makes an excellent street tree for dry climates such as in southern Arizona.
The feathery, bipinnate leaves, up to 6 inches in length, are deep green, turning to yellow in fall. The leaves are composed of leaflets, up to 0.12 inches in length.
The profuse fragrant flowerballs are creamy-white.
The stems are armed with paired white thorns, up to 3 inches in length.

The yellowish-brown, flaky, papery bark peels off in flat strips.
Hardy zones 9 to 11. Very drought tolerant, it also tolerates flooding, sand and clay.
A healthy attractive shade tree even in the extreme heat of Yuma.
Pharmacology: leaf contains DMT

'woodii'
A perennial in Tucson, dying back to the ground at 15 F

Acacia simplex
A climbing tree reaching up to 40 feet that is native to both Argentina and islands in the western Pacific Ocean.
The cupped, rounded leaves are bright green.
Pharmacology: bark, stem bark and leafy stems contain high levels of DMT.
This plant has been used in fishing. Products of this plant are harmless to humans but stun fish.

Acacia smallii (Small's Acacia)
May be the same as Acacia farnesiana and is in fact nearly biologically similar. This tree represents trees of southwestern U.S. origion and are much hardier (to 15 F).
Whether or not it is a separate species or just a regional variant of Acacia farnesiana is a subject of botanical debate.
The bipinnate leaves are composed of tiny leaflets, up to 0.1 inches in length.
Hardy zones 8b to 10

Acacia sophorae (Coastal Wattle)
A dense spreading shrub that is a widespread native of eastern Australia and Tasmania, reaching a maximum size of 20 x 33 feet.
An excellent choice for use in preventing beach erosion. On exposed coastal sites, it is often prostrate in habit.
The broad, oblong phyllode leaves are up to 5 x 1.5 inches.
The golden-yellow bottlebrush-like flower spikes, up to 2 inches in length, are borne during spring.
Hardy zones 8 to 11 in full sun to partial shade, very tolerant of salt laden winds.
Pharmacology: contains Tryptamine

Acacia spectabilis (Mudgee Wattle)
Also called Pilliga Wattle. An open, pendulous, tall slender shrub native to the inland slopes of eastern Australia that reaches a maximum size of 20 x 15 feet. Some records include: 3 years - 7 feet; 5 years - 17 + feet. It can also be used as a screen.
The soft, blue-green, bipinnate leaves, up to 4 inches in length are composed of leaflets up to 0.7 x 0.25 inches.
The spectacular, golden-yellow flowerballs, up to 0.4 inches, are borne on long, dense sprays, up to 8.5 inches, during late winter and spring.
The smooth bark is whitish to blue-gray.
Hardy zones 9 to 11 tolerating as low as 19 F. Drought tolerant.
Prune lightly after flowering to maintain shape.

Acacia stenophylla (Shoestring Acacia)
A beautiful fast growing, pendulous tree, that is native to central and eastern Australia. Some records include: 16 months - 13 feet; largest on record - 66 x 30 feet. It is similar to Acacia salicina and makes an excellent landscape tree in the southwestern U.S.
The very long narrow leaves are up to 20 x 1 inches.
The pale yellow flowerballs, up to 0.5 inches across, are borne from the leaf axils.
The fibrous to fissured bark is dark gray-brown.
Hardy zones 8b to 11 (tolerating as low as 15 F) in full sun on well drained soil.
Tolerates clay, alkaline soil, drought and flooding. Very tolerant of saline soils.
Seed should be soaked in boiling water for 1 minute before sowing.

** photo of unknown internet source*



Acacia suaveolens (Sweet Wattle)
A shrub, reaching a maximum height of 10 feet, that is native to coastal eastern Australia and Tasmania.
The linear to oblanceolate, phyllode leaves, up to 6 x 0.4 inches, are green.
The pale yellow flowerballs, up to 0.3 inches across, are borne on axilliary racemes up to 1.3 inches in length.
The bark is smooth and purplish.
Hardy zones 9 to 10 (est). Tolerates pure sand.

Acacia subporosa (Narrow-Leaf Bower Wattle)
A semi-pendulous, small tree, reaching a maximum height of 40 feet, that is native to far southeastern Australia. Some records include: 5 years - 20 feet.

The narrow-elliptical phyllode leaves are up to 5 x 0.4 inches.
The pale yellow flowerballs are up to 0.4 inches across.
The smooth bark is gray or brown.
Hardy zones 9 to 10 (est)

Acacia terminalis (Cedar Wattle)
Also called Sunshine Wattle. A medium size tree reaching a maximum size of 66 (rarely over 20) feet, native to southeastern Australia.
The bipinnate leaves, up to 4.5 inches in length, are composed of oblong leaflets, up to 0.8 x 0.2 inches. The foliage is reddish at first, turning to glossy deep green.
The golden-yellow flowerballs, up to 0.5 inches, are borne on panicles.
The gray or brown bark is smooth, becoming finely fissured on older trees.
Hardy zones 9 to 10

Acacia tetragonophylla (Kurara)
An attractive, dense, semi-pendulous, rounded, shrub or small tree, reaching a maximum size of 20 x 20 (rarely over 10) feet, that is a widespread native to western and central Australia. Some records include: 2 years - 6 feet.
The prickly, needle-like, linear leaves, up to 2 x 0.12 inches, are bright green.
The bright yellow flowerballs, up to 0.4 inches, are borne from the leaf axils.
The gray bark is finely fissured.
Hardy zones 9 to 10 (fully hardy to 16 F with foliage damage only). Extremely drought tolerant.

Acacia tindaleae (Golden-Top Wattle)
A dense small shrub reaching a maximum height of 6.5 feet that is native to eastern Australia.
The very hairy, small, linear phyllode leaves are densely crowded along the stems.
The profuse, golden-yellow flower balls are borne winter and spring.
Hardy zones 9 to 11 thriving in both subtropical and dry climates.
Prune to shape after flowering.

Acacia tortilis (Umbrella Thorn)
A medium size, attractive, umbrella crowned tree native to most of Africa and the Arabian Peninsula
Some records include: 2 years - 8 x 10 feet; 2.5 years - 16 feet; 11 years - 22 feet with a trunk diameter of 6 inches; largest on record - 70 x 60 feet.
There is a combination of short, recurved and long, narrow spines with all being very sharp.
The very small, bipinnate leaves have very small leaflets.
The foliage is typically evergreen.
The fragrant, white to light yellow, rounded flowers are borne in small clusters in mid summer with the foliage.
They are followed by spirally twisted, light brown pods borne in clusters.
Hardy zones 9 to 11 tolerating as low as 18 F. It is extremely drought tolerant due to its roots which can extend as deep as 170 feet. It is also very heat tolerant, to as high as 122 F.^

'heteracentha'
A subspecies that ranges widely in southern Africa.

Some records include: 1.5 years - 5 feet with a trunk diameter of 2 inches

Acacia tortuosa (Twisted Acacia)
A rounded to wide spreading, semi-evergeen to evergreen small tree native from central Texas, south into Mexico.
Some records include: fastest recorded growth rate - 2 feet; largest on record - 31 x 30 feet with a trunk diameter of 1.5 feet.
The bipinnate leaves, are composed of 3 to 4 pairs of pinnae, each having 10 to 15 pairs of very narrow, pointed leaflets.
The foliage is light-green.
The fragrant, bright-yellow ball-shaped flowers, up to an inch wide are borne in pairs of 3s from the leaf axils.
They are followed by long narrow, slightly compressed pods, up to 5 x 0.3 inches. that constrict between the seeds.
The branches are armed with slender spines up to an inch in length.
The bark is dark brown and furrowed.
Hardy zones 8 to 10, very tolerant of drought as well as being heat and alkaline soil tolerant.

Acacia trachycarpa (Minniritchi)
A moderately fast growing, thornless tree reaching a maximum size of 20 x 25 feet, that is native to northwestern Australia.
Some records include: 1.5 years - 9 feet.
The linear leaves are up to 4 x 0.1 inches in size.
The golden-yellow flower spikes are up to 0.8 inches in length.
The bark is reddish-brown.
Hardy zones 9b to 10 (tolerating 25 F).

Acacia trineura (Three Nerved Wattle)
A rounded, evergreen large shrub, reaching a maximum height of 17 feet, that is native to southeastern Australia.
Some records include: 2 years - 9 feet; 3 years - 11 feet
The narrow, oblong leaves, up to 3.2 x 0.5 inches, are deep green.
The golden-yellow flowerballs, up to 0.2 inches across, are golden-yellow.
3 to 8 flowerballs may be contained in a raceme.
The bark is smooth and gray.
Hardy zones 9 to 11 (fully hardy to 15 F).

Acacia triptera (Spurwing Wattle)
A very dense, spreading, large shrub native to semi-arid regions of eastern Australia. Some records include: 3 years - 28 inches; largest on record - 15 x 23 feet with a trunk diameter of 9 inches. It makes an excellent barrier hedge.
The stiff, curved, pointed, narrow-triangular phyllode leaves, up to 2.2 x 0.3 inches, are purplish at first, turning to mid-green.
The profuse, very showy, bright yellow, bottlebrush-like flower spikes, up to 1.3 inches in length, are borne late winter and spring.

Hardy zones 9 to 11 (tolerating as low as 19 F) in full sun on well drained soil. Extremely drought tolerant.

Acacia truncata
A dense, domed large shrub, reaching a maximum size of 10 x 5 feet, is native to far southwestern Australia.
The tiny leaves (shaped like upside-down triangles) are only up to 1 x 0.5 inches.
The creamy, ball-shaped flowers are up to 0.5 inches.
Hardy north to zone 9, tolerating as low as 19 F
Requires full sun. Salt tolerant.

Acacia uncinata (Wavy-Leaf Wattle)
A spreading to erect shrub with long pendulous branches that is native to New South Wales in eastern Australia.
Some records include: 5 years - 6 feet; largest on record - 10 feet.
The stem clasping, rounded, wavy, hook-pointed phylloides, up to 1.8 x 0.8 inches, are gray-green.
The large bright yellow flowerballs, up to 0.35 inches across, are borne single or in pairs during spring and summer and also on and off at other times of the year.
Hardy zones 9 to 11 tolerating as low as 19 F. Drought tolerant.

Acacia verticillata (Star Acacia)
Also called Prickly Moses. A attractive, prickly, fast growing, arching shrub to small tree (if trained) that is native to Tasmania and southeast Australia. Some records include: fastest recorded growth rate - 2 + feet; 10 years - 20 x 20 feet; largest on record - 33 x 33 feet; largest in England - 30 feet. Excellent for use in hedging.
The whorled, rigid, very sharp, linear, needle-like leaves, up to 1 x 0.3 inches, are arranged in whorls.
The bright yellow flowers spikes, up to 1.8 inches in length, are borne either single or in small groups during late winter and spring.
Hardy zones 8b to 11 tolerating as low as 19 F.
It thrives in milder parts of the British Isles.

Acacia vestitia (Hairy Wattle)
Also called Weeping Boree. A bushy, small weeping tree reaching a maximum size of 27 x 20 (rarely over 13) feet, that is native to far southeastern Australia.
The triangular leaves, up to 0.8 x 0.3 inches, are gray-green.
The showy, golden-yellow flowerballs are borne on long racemes, up to 2.3 inches in length.
The bark is smooth and gray.
Hardy north to zone 9, tolerating as low as 19 F. It can be sheared.

Acacia victoriae (Bramble Wattle)
A moderate growing, spreading, small tree native to inland parts of Australia.
Some records include: 1 year - 5 feet; 3 years - 9 feet; 5 years - 14 feet; 8 years - 18 feet; largest on record - 40 x 33 feet with a trunk diameter of 8 inches.
It can be used for hedging and windbreaks as well. Short lived in many regions, lasting around 15 years. It may sucker readily.

The lance-shaped, gray-green leaves, up to 3.5 x 1 inches in size, have a strong, paired spines at the base.
The fragrant, creamy-yellow flowerballs, up to 0.3 inches across, are borne on racemes up to 4 inches in length, during late winter into early summer.
The bark is smooth and dark gray.
Hardy zones 8 to 11. Fully hardy at 15 F at Tucson. Very drought tolerant due to its deep root system which may penetrate as much as 66 feet or more into the earth.
Moderately salt tolerant.

Acacia villosa
A small thornless tree, reaching a maximum size of 23 feet, that is native to Jamaica where it is threatened. Some records include: 2 years - 8 feet; 4 years - 12 feet.
Hardy zones 10 to 12 (freezes to base at 25 F but may reach as much as 9 feet during the following summer).

Acacia viscidula (Sticky Wattle)
A small tree, reaching a maximum height of 20 feet, that is native to the central part of Australia's east coast. Some records include: 4 years - 7.5 feet; 6 years - 10 feet.
The linear leaves, up to 4.3 x 0.1 inches, are glossy mid-green.
The pale yellow flowerballs are up to 0.3 inches across.
The smooth bark is gray-brown.
Hardy zones 9 to 10 (fully hardy to 16 F)

Acacia visco
An attractive, moderate growing, rounded, medium-sized, deciduous to semi-evergreen tree, reaching a maximum size of 40 x 40 feet, that is native to Argentina.
Some records include: 2 years - 5 feet; 3 years - 9 feet; 8 years - 16 feet; 15 years - 22 feet.
The bipinnate leaves, up to 7 x 3.5 inches, are composed of linear leaflets.
The foliage is bright green at first, turning to deep green.
The showy, creamy-white flowerballs, up to 0.5 inches across, are borne during spring through summer.
Hardy zones 8b or 9 to 11. Fully hardy at 15 F at Tucson but defoliates at temperatures in the mid 20s.

Acacia wilhelmiana (Wilhelm's Wattle)
A compact, dense, spreading, medium sized, evergreen shrub, reaching a maximum size of 10 x 10 feet, that is native to semi-arid regions in southeast Australia.
The narrow, linear leaves, up to 1.3 x 0.16 inches, are green.
The masses of single or paired, golden-yellow flowerballs, up to 0.25 inches, are borne late winter and spring.
Hardy zone 8 to 10. Drought tolerant.

Acacia willardiana (Palo Blanco)
A very attractive, evergreen, weeping tree, reaching a maximum size of 33 x 20 feet, that is native to the Sonoran Desert of Mexico. Some records include: 1 year - 5 feet; 2 years - 13 feet; 3 years - 17

feet; 7 years - 20 feet; 10 years - 25 feet. An excellent landscape tree in hot desert climates, it looks like a cross between a Casuarina and a Weeping Willow from a distance.
The bipinnate leaves, up to 4 inches in length, are composed of linear leaflets, up to 0.2 inches in length.
The creamy-yellow flowers are borne on bottlebrush-like spikes, up to 2.5 inches in length.
The attractive bark is white and peeling.
Hardy zones 9b to 11 tolerating as low as 25 F. Very heat tolerant, preferring a hot south facing wall north of zone 10. During extended droughts, a deep watering once a month is recommended.
Pest and disease resistant.

Acacia wrightii (Wright Acacia)
A densely crowned, small evergreen tree reaching up to 20 x 20 feet, that is native to most of central and western Texas, south into eastern Mexico.
Some records include: fastest recorded growth rate - 3 feet; 3 years - 7 feet; 4 years - 11 x 4+ feet; 10 years - 15 feet; 13 years - 17 feet; largest on record - 40 x 40 feet with a trunk diameter of 2 feet.
The bipinnate leaves, up to 3 inches in length, are composed of 1 to 3 pairs of pinnae, each having 3 to 5 pairs of oval leaflets, each up to 0.8 inches in length.
The somewhat hairy foliage is bright-green.
The small, fragrant, light-yellow flowers are borne in cylindrical spikes up to 1.5 inches in length. They are followed by often curved, flattened pods, up to 6 x 1.5 inches. The pods contain narrowly oval seeds up to 0.3 inches in length. The ripened seed pods are not persistant, falling early in autumn.
The branches are sparsely armed with thick, curved brown spines.
The bark is dark brown, scaly and furrowed.
Hardy zones 7 to 10. Fully hardy at 15 F at Tucson. Very tolerant of both heat and drought. It is not known to grow in the humid eastern U.S.
Seeds germinate much better if soaked in sulfuric acid for 20 minutes before sowing to loosen the seed shells.

Acacia xanthophloea (Fever Tree)
A handsome, widespreading, fast growing, large deciduous tree native to southeastern Africa.
Some records include: 2 years - 14 feet; 3 years - 22 feet; 4 years - 25 feet; 5 years - 30 feet; 30 years - 50 x 40 feet; largest on record - 100 x 80 feet with a trunk diameter of 4 feet.
The bipinnate leaves are up to 4 inches in length. The foliage is yellow-green.
The fragrant, rounded, golden-yellow flowers are borne in small clusters with the leaves during spring.
The paired, white thorns, up to 3 inches, are straight and sharp.
The bark is mature trees is smooth, powdery and yellow-green. This is among the few trees in the world that can produce photosynthesis from the bark.
Hardy zones 9 to 11. Flood tolerant. It even thrives in the extreme summer heat of Yuma, Arizona, it also thrives in Phoenix and warmer parts of Tucson.

** photo of unknown internet source*

Posted by Randy Stewart Landscape at 1:01 PM 0 comments

The official manual used by the AMGA to teach single pitch rock climbing

“I’ve been waiting for this book for a long time. Professionalism, programming, pedagogy, anchors . . . this is a comprehensive resource for understanding the complexities of teaching in the single pitch environment. Highly recommended!”
—Arno Ilgner, AMGA Single Pitch Instructor and author of *The Rock Warrior’s Way: Mental Training for Climbers*

“If you want a thorough treatise on what to expect in the [AMGA SPI] course, as well as a ton of information on climbing gear and its evolution, this book will fill your needs. Even if you don’t intend to take the course and just want to know what are considered best practices by the AMGA, the answers are here.”
—Russ Clune, AMGA Single Pitch Instructor and standard-setting Gunks first ascentionist

Rock Climbing: The AMGA Single Pitch Manual is intended to serve as a textbook for past and future participants of the American Mountain Guide Association’s Single Pitch Instructor program. The book builds upon Bob Gaines’ book *Toproping* to more specifically address the needs of the professional climbing instructor and advanced recreational climbers. It presents the most current, internationally recognized standards for technical climbing systems used in single pitch rock terrain. Included are chapters on effective teaching in the outdoor environment, risk management, professionalism, and rescue.

Bob Gaines has been a professional rock climbing guide since 1983. He is the owner of Vertical Adventures Rock Climbing School, voted the top rock climbing school in America by *Outside* magazine. An AMGA Certified Rock Instructor and AMGA Single Pitch Instructor Program Provider, he is the author of *Best Climbs Joshua Tree National Park, Best Climbs Tahquitz and Suicide Rocks, Rappelling,* and *Toproping*, and the coauthor of *Climbing Anchors* (all FalconGuides). Visit him at verticaladventures.com.

Jason D. Martin is a professional guide, writer, and the director of operations at the American Alpine Institute. He has guided in Red Rock Canyon, Joshua Tree National Park, the Cascades, the Sierra, the Alaska Range, Canada’s Coast Range, and the Andes of Ecuador, Bolivia, and Peru. An AMGA Certified Rock Guide and an AMGA Single Pitch Instructor Program Provider, he is also a playwright, film critic, and outdoor adventure writer. He coauthored *Washington Ice: A Climbing Guide* and authored *Fun Climbs Red Rocks: Topropes and Moderates*. Visit him at alpineinstitute.com.

Front cover photo by Bob Gaines

facebook.com/AMGAUSA

@amgausa

made in the USA

Join our community

$21.95 / Canadian $23.95
ISBN 978-0-7627-9004-3
52195
9 780762 790043

Essential gear for every adventure: **Outfit Your Mind**®

FALCONGUIDES®

Rock Climbing

FALCON GUIDES®
falcon.com

FalconGuides®
is an imprint of
Globe Pequot Press

A FALCON GUIDE®

HOW TO CLIMB® SERIES

Rock Climbing

The AMGA Single Pitch Manual

BOB GAINES AND
JASON D. MARTIN

FALCON GUIDES

GUILFORD, CONNECTICUT
HELENA, MONTANA

AN IMPRINT OF GLOBE PEQUOT PRESS

HOW TO CLIMB™ SERIES

Rock Climbing

The AMGA Single Pitch Manual

Bob Gaines and Jason D. Martin

FALCON GUIDES

GUILFORD, CONNECTICUT
HELENA, MONTANA

AN IMPRINT OF GLOBE PEQUOT PRESS

To buy books in quantity for corporate use
or incentives, call **(800) 962–0973**
or e-mail **premiums@GlobePequot.com.**

FALCONGUIDES®

Copyright © 2014 by Bob Gaines and Jason D. Martin

ALL RIGHTS RESERVED. No part of this book may be reproduced or transmitted in any form by any means, electronic or mechanical, including photocopying and recording, or by any information storage and retrieval system, except as may be expressly permitted in writing by the publisher. Requests for permission should be made in writing to Globe Pequot Press, Attn: Rights and Permissions Department, PO Box 480, Guilford, CT 06437.

FalconGuides is an imprint of Globe Pequot Press.
Falcon, FalconGuides, and Outfit Your Mind are registered trademarks of Morris Book Publishing, LLC.

Photos: Bob Gaines unless credited otherwise.
Illustrations: Mike Clelland
Text and layout designer: Casey Shain
Project editor: Julie Marsh

Library of Congress Cataloging-in-Publication data is on file.

ISBN 978-0-7627-9004-3

Printed in the United States of America
10 9 8 7 6 5 4 3 2 1

***Warning:* Climbing is a dangerous sport. You can be seriously injured or die. Read the following before you use this book.**

This is an instruction book about rock climbing, a sport that is inherently dangerous. Do not depend solely on information from this book for your personal safety. Your climbing safety depends on your own judgment based on competent instruction, experience, and a realistic assessment of your climbing ability.

The training advice given in this book is based on the authors' opinions. Consult your physician before engaging in any part of the training program described by the authors.

There are no warranties, either expressed or implied, that this instruction book contains accurate and reliable information. There are no warranties as to fitness for a particular purpose or that this book is merchantable. Your use of this book indicates your assumption of the risk of death or serious injury as a result of climbing's risks and is an acknowledgment of your own sole responsibility for your safety in climbing or in training for climbing.

Globe Pequot Press, the authors, and the American Mountain Guides Association (AMGA) assume no liability for accidents happening to, or injuries sustained by, readers who engage in the activities described in this book.

Contents

Acknowledgments vii
Introduction viii
About the American Mountain Guides Association (AMGA) viii
AMGA Certification x
Concept Driven Techniques and the AMGA xii
How to Use This Book xiii

Chapter 1: The Role of a Climbing Instructor 1

Chapter 2: Professionalism

Pre-Program Preparations 3
At the Instructional Site 4

Chapter 3: Programming

Permitting 7
Risk Management and Liability 9
Risk Management in the Field 12
Stewardship 14
Instructor Meetings 16

Chapter 4: Pedagogy: The Art of Teaching

Learning Styles 17
Lesson Planning 20
Learning from Mistakes 22
Teachable Moments 23
Taking Kids Climbing 24
Teaching Climbing Movement 26

Chapter 5: Baseline Equipment

Harness 28
Helmets 31
Ropes 32
Knife 44
Slings and Webbing 44
Cords and Cordelettes 50
Carabiners 52
The Instructor's Pack 61

Chapter 6: Knots and Hitches

Loop Knots 62
Double Loop Knots 72
Knots for Webbing 78
Bends 80
Knots for Joining Two Ropes 83
Hitches 85
Stopper Knot 101

Chapter 7: Protection and Anchoring

Rock Assessment 102
Natural Anchors 108
Passive Protection 112
Active Protection 123
Fixed Anchors 135

Chapter 8: Anchor Systems

Fundamental Anchor Anatomy and Principles 145
Notes on Redundancy 146
Notes on Load Distribution 148
Vectors 162

Chapter 9: Advanced Anchor Rigging Systems and Institutional Anchors

Using a Setup Rope: Components Far Apart 164
Instructor Tether: Managing Risk at the Cliff's Edge 165
Extensions: Creating a Master Point Over the Cliff's Edge 167
Systems Using a Setup Rope 167
The Joshua Tree System—V Rigging with Extension Rope 168
The Lifeline System—V Rigging with Instructor Tether 173
The Backside System—Pre-Equalized Extensions 175
The Three-in-One System 179

Chapter 10: Risk Management at the Crag

Rockfall 183
Terrain Hazards 184
Closing the System 184
Systems Checks 184
Falling 185
Other Considerations 186

Chapter 11: Top- or Base-Site Management for a Single Pitch

Top-Managed Sites 187
Base-Managed Sites 190
Belaying 192
Belaying in a Base-Managed Site 196
Backup Belayers 199
Belaying from the Top 201
Lowering from a Top-Managed Site 204
Lowering with a Munter Hitch 204
Lowering with an Assisted Braking Device 204
Using a Backup When Lowering 205

Chapter 12: Rappelling

Teaching Rappelling 208
Student Rappel Belays 208
The Instructor Rappel Backup 210
Managing the Risks—
Avoiding Rappelling Accidents 216

Chapter 13: Basic Assistance and Rescue Skills

Assistance from the Base 221
Assistance from the Top 227

Chapter 14: Fixed Lines 231

Chapter 15: Leading

Student Lead Belay Training 234
Ground Anchors, Student Belay
Backups, and Knots 236
Descent Options 237
Teaching a Student to Lead 237

Appendix A:
Leave No Trace Ethics 240

Appendix B:
How to Determine a Fall Factor 242

Appendix C:
Autoblocking Devices 244

Appendix D:
Wilderness Medical Certifications 247

Appendix E:
Recommended Reading 248

Appendix F:
Climbing Instructor
Employment Resources 249

Index 252

About the Authors 257

Acknowledgments

The creation of a book like this is a grand effort with many parties involved. First, we would like to thank those who assisted the most in this process: Ron Funderburke and Ed Crothers of the AMGA, and John Burbidge and Julie Marsh from Globe Pequot Press. Ed and Ron provided most of the technical support for this text from the AMGA, and John and Julie patiently worked to put it all together. Special thanks to Casey Shain for the excellent job on the layout and design.

Thanks to the instructors, guides, and volunteers who took time out of their busy schedules to pose for, shoot, and donate photos for this project. In particular, Bob would like to thank Patty Kline, Mark O'Brien, Erik Kramer-Webb, Tony Grice, Dave Mayville, Ryan Murphy, Reggie Bulman, Kevin Jackson, Bryan Baez, Robin Depke, Ryan Bennet, William Jaques, Adam Radford, Wills Young, Nicholas Giblin, Chris Idiart, Dan Richter, Frank Bentwood, Terri Condon, David Berlin, Ben Shackelford, Andrew Jones, Eric Ludwig, Adam Hufford, Kris Jackson, Todd Gordon, and Chris Ramirez. Jason would like to thank Tim Page, James Pierson, Richard Riquleme, Jeremy Wilson, and Betsy Winter. We would also like to thank those who gave us feedback throughout this process. These include John Belanger, Tom Kirby, Casey O'Brien, and Dunham Gooding.

Thanks to our fellow guides and mentors who have taught us so much over the years. Jason would like to specifically thank Michael Powers, Art Mooney, Tom Hargis, Marcus Jollif, and Adam Fox. Bob would like to thank Jon Tierney, Alan Jolley, Peter Croft, Scott Cosgrove, Marcus Jollif, Dylan Taylor, Josh Jackson, Chris Baumann, Todd Vogel, Erik Kramer-Webb, Tony Grice, Tony Sartin, Pat Dennis, and Dave Mayville. Bob would like to give a sincere thanks to John Long for the many insightful conversations while working together on the Climbing Anchors books.

And finally, we would like to thank our families. Jason would like to thank Krista, Holly, and Caden for supporting all of his endeavors. And Bob would like to thank his wife, Yvonne, for her help with the photography.

Introduction

Rock climbing is a sport unlike any other. Hanging on by your fingertips, high above the ground, gives us a sense of focus and freedom that few other activities provide. We love the feeling of the warm sun on our backs while we stick the perfect jam or pull the crux move. We relish in our movement over the stone and the beauty of our surroundings. We love the element of exploration that comes with the sport and the anticipation of a trip to a new crag or the ascent of a new route. And we adore both the acquaintances that are made on the rock as well as the enduring friendships that are built within a climbing partnership.

We love it all so much that we have a desire to share it with others.

And while we wish to share this with others, we have to understand that the role of the climbing instructor comes with a great deal of responsibility. People can get hurt or even killed in this sport. With that in mind, it's important that those who wish to teach have the proper training before instructing any level of climber.

This text was designed to be a supplement to the American Mountain Guides Association Single Pitch Instructor (SPI) Course. The SPI course was designed to help capable recreational climbers transition into capable and effective climbing instructors. The course—and this text—focuses on the technical skills required of an instructor as they are applied in all forms of single pitch climbing instruction. In addition to this, the course addresses the essential educational and environmental tenets required to teach climbing. AMGA Single Pitch Instructors are expected to demonstrate the technical and educational proficiencies necessary to instruct a variety of single pitch rock climbing skills in a secure and effective manner to both groups and individuals.

The SPI course is intended for recreational climbers who are already proficient in both toprope and lead climbing. It was designed to benefit those who wish to facilitate outdoor climbing programs for groups such as those offered by guide services, camps, schools, universities, climbing clubs, therapeutic groups, churches, and climbing gyms.

Those who wish to teach climbing in the outdoors tend to have a higher success rate obtaining employment as climbing instructors with this training and certification. Additionally, the AMGA recommends this program as a precursor to upper-level AMGA climbing instruction and guide programs.

About the American Mountain Guides Association (AMGA)

The American Mountain Guides Association is the organization that oversees guide and instructor training in the United States, while also supporting and advocating for climbing instructors, guides, and accredited guide services. The organization is dedicated to supporting these groups through excellence in instructor and guide education, through the development of standards to ensure the quality of services provided to the public, and by serving as a resource for access to and the protection of the natural environment. As a group, the AMGA

AMGA presidents at the 2010 AMGA annual meeting. Back row, from left to right: Alan Pietrasanta, Ian Wade, John Cleary, Mark Houston, Dunham Gooding, Phil Powers, Dick Jackson, and John Bicknell. Front row, kneeling: Margaret Wheeler and Doug Robinson.

BETSY WINTER

presents a strong and unified voice for high standards of professionalism in guiding and climbing instruction.

The AMGA is grounded in a powerful tradition that continues to evolve with the ever-changing arena of mountain guiding and climbing instruction. The organization offers a series of training courses and exams designed to certify guides and climbing instructors to highly respected and internationally recognized standards.

A Brief History of the AMGA

The profession of instructing and guiding in the mountains spans back to the start of the United States as a nation. However, it wasn't until 1979 that a group of twelve guides got together in Jackson, Wyoming, and decided that it was time to formalize an organization to represent the greater guiding community. The goals these guides developed were written in a bar on the back of a napkin and became known as the Moose Bar Charter. As a result, the American Professional Mountain Guides Association was born. Over the next few years, the "P" was dropped, and the AMGA developed and grew throughout the United States.

In the AMGA's formative years, there was a great deal of wrangling. Instructors and guides are independent minded, and an organization overseeing standards wasn't always popular. Early presidents such as Doug Robinson, Alan Pietrasanta, Ian Wade, and Dunham Gooding spent much of their time trying to expand the ranks of the guides involved, while also overseeing the development of certification courses for guides and accreditation programs for guide services.

Unity among guides and guide services became especially important in the mid-1980s. At that time a worldwide liability insurance crisis shook the guiding industry to its core. After steps were taken to secure affordable insurance appropriate for climbing schools and guide services, independent-minded guides began to see that there was great value in working together as an association.

The next major goal of the AMGA was to gain acceptance into the International Federation of Mountain Guides Associations (IFMGA). Admission into this organization would allow American guides access to the European Alps while recognizing that AMGA programs met an international standard. Between 1990 and 1997, AMGA presidents Steve Young, Dunham Gooding, Matt Culbertson, and John Cleary worked tirelessly to achieve this goal. On November 22, 1997, delegates admitted the AMGA into the IFMGA after a unanimous vote from the existing member countries. Today the AMGA is the sole representative of the United States to the twenty-six-member IFMGA, the international governing body responsible for guiding standards and education around the world.

In the late 1990s, under the supervision of Mark Houston, both as technical director and then as president, and with help from Jon Tierney and others, the AMGA developed the Toprope Site Manager program. Unfortunately, the TRSM program was limited in its scope and didn't adequately meet the needs of instructors looking to advance to higher-level AMGA courses. It wasn't until 2008, under the supervision of Adam Fox, that the Single Pitch Instructor program became the nation's premier entry-level program for those who sought to be climbing instructors. In 2009, after a third party review, the AMGA SPI received the endorsement of the UIAA (Union Internationale des Associations d'Alpinisme) as meeting the international standards for the training of climbing instructors.

Today the AMGA continues to develop its programs to meet changing standards and to support the growing community of guides and climbing instructors in the United States. In addition, the organization has become a resource for land managers and outdoor industry leaders by promoting land stewardship, world-class training, and sustainable practices to protect our natural resources.

The AMGA is the post-graduate school of guiding, and it is where professional climbing instructors and guides go to develop their skills in order to attain the highest level of training and certification.

AMGA Certification

There are three disciplines of certification in the AMGA: Rock, Alpine, and Ski. Some of the disciplines have multiple levels of certification. For example, in the Rock discipline one can be certified at the Single Pitch Instructor level, the Rock Instructor level, or the Rock Guide level. In each of the disciplines, the guide level is the highest level of certification. If an individual obtains AMGA certification at the guide level in Rock, Alpine, and Ski, then that person will be granted the International Federation of Mountain Guides Associations (IFMGA) certification, which is the highest level of certification available for a guide.

The Single Pitch Instructor certification was designed for those who wish to work in a single pitch setting and as an entry-level program for those who wish to continue on to gain a higher level of training and certification.

If you are interested in working solely in a single pitch setting, then there is no reason to continue on to a higher level of training. However, if you do wish to work on multi-pitch rock terrain, in the alpine, or on skis, then additional courses will be required in order for you to be adequately trained.

Following is a breakdown of the different types of certification available from the AMGA and the terrain guidelines for the certifications:

AMGA Single Pitch Instructor

AMGA Single Pitch Instructors are trained and assessed to operate on all routes that:

- The anchors are accessed by either nontechnical terrain or by leading technical 5th-class terrain.
- Are climbed without intermediate belays.
- Present no difficulties on approach or retreat from the area, such as routefinding, scrambling, or navigating.

AMGA Climbing Wall Instructor—Toprope

AMGA Climbing Wall Instructors (Toprope) are trained and assessed to operate on indoor climbing and bouldering walls and climbing structures that:

- Do not involve lead climbing.
- Do not include the instruction of lead climbing.

AMGA Climbing Wall Instructor—Lead

AMGA Climbing Wall Instructors (Lead) are trained and assessed to operate on indoor climbing and bouldering walls and climbing structures that:

- Involve lead climbing.
- Include the instruction of lead climbing.

AMGA Rock Instructor

Rock Instructor certification is designed to apply to most "cragging" rock climbing areas in the United States. AMGA Rock Instructors are trained and assessed to operate on all rock routes that:

- Are Yosemite Decimal System Grade III or shorter in length.
- Do not have approaches or descents where extensive use of short-rope techniques is appropriate for security.
- Are not remote in nature.
- Do not involve technical snow, glacier travel, the use of skis, or exposure to avalanche risk.

AMGA Rock Guide

Rock Guide certification is designed to apply to all Rock Instructor terrain, but it also includes climbs of much greater length, including big wall and aid climbs, and climbs where significant short-roping is appropriate for the safeguarding of clients on either approaches or descents. AMGA Rock Guide certification is not, however, applicable to terrain that is alpine in nature (i.e., remote or involves technical snow or technical glaciated or icy terrain). AMGA Rock Guides are trained and assessed to operate on all rock routes that:

- Are Yosemite Decimal System Grade IV or Grade V in length.
- Include approaches and descents that may require extensive use of short-roping technique for security.
- May be remote in nature.
- Do not involve glacier travel, the use of skis, or exposure to avalanche risk.

AMGA Alpine Guide

AMGA Alpine Guide certification is designed for guiding glaciated and non-glaciated peaks, approaches, and climbs, with no limitation with respect to season or elevation. It includes rock climbs, peak ascents, waterfall ice climbs, and expeditionary climbing. AMGA Alpine Guides are trained and assessed to operate in all alpine and rock terrains that:

- Are Yosemite Decimal System Grade V or shorter (for rock routes).
- Are not conducted on skis where the main objective of the outing is either a ski tour or the enjoyment of downhill skiing.
- AMGA Alpine Guides who hold both Alpine and Rock Guide certifications are allowed to guide alpine rock routes that are YDS Grade V or longer.

AMGA Ski Guide

AMGA Ski Guide certification is designed for guiding either ski tours or ski ascents/descents on alpine touring or free-heel equipment. AMGA Certified Ski Guides are trained and assessed to operate in all terrains that:

- Include as the main objective either ski touring, off-piste, and/or mechanized skiing.
- Are on slopes up to 50 degrees.
- May employ the use of rope including short-roping techniques with the use of ice axe and crampons.
- Require travel on crevassed glaciers.
- Have significant avalanche hazard.
- Involve multi-pitch ice or rock.

IFMGA American Mountain Guide

IFMGA American Mountain Guide certification is designed for individuals certified as AMGA Rock, Alpine, and Ski Guides. IFMGA/American Mountain Guides are trained and assessed to operate in all alpine, rock, and ski terrain.

Concept Driven Techniques and the AMGA

"I want to learn the AMGA way."

The preceding comment is incredibly common. But it is a misperception of what the AMGA is and what it does. There is no "AMGA way."

The American Mountain Guides Association teaches students a series of different techniques in each of the disciplines. Association guidelines seldom dictate which technique an individual is required to use. Instead, AMGA program instructors evaluate their students on the application of the techniques that they have learned. In other words, one student might accomplish the exact same goal using a completely different technique than another student, but both might still be acceptable.

There are a lot of right ways to do things. Some ways may be more efficient and some ways may be more effective. The goal of an AMGA instructor is to find the best and most efficient way based on the circumstance.

In the Single Pitch Instructor curriculum, there are a handful of prescribed techniques that are taught. However, the bulk of the material is driven by concept. A concept is a general idea of how something should work. For example, you may wish to set up a toprope with an anchor that self-adjusts to a variable direction of load. There are a number of ways to do this. You could use a quad or a magic-x with load limiting knots, or an equalette. What you use doesn't matter. Instead, what matters is that you achieved a self-adjusting system, which is conceptual in nature.

In the SPI curriculum there are a number of concepts. An SPI provider's goal is not necessarily to have a student ape exactly what is in this text, or exactly what an individual instructor has taught, but instead to demonstrate an understanding of each concept and how to apply it.

How to Use This Book

This book is broken into two major sections. The first part (chapters 1 through 4) covers instructor knowledge. The information here, concerning everything from professionalism to pedagogy, combines to provide a foundation of base-level knowledge that every climbing instructor should have. The second part (chapters 5 through 15) delves into the specific technical skills that are needed to effectively run programs in a single pitch setting. Like the first part, this second part also provides a foundation, though this foundation is built of technical skills.

To fully understand and appreciate the material presented in this text, readers should have a solid understanding of toproped climbing and have experience with traditional climbing. This is not a "how-to-toprope" book or a "how-to-lead-climb" book, but a book that assumes you already have those skills and wish to take them to the next level.

This text was specifically designed as a supplement to the AMGA SPI program. It was not designed to be used by independent practitioners without the oversight of a qualified instructor. Readers of this book are strongly advised to work through the material herein with an AMGA Single Pitch Instructor Program Provider.

AMGA Single Pitch Instructors Tom Kirby and Erin Smart toprope at Mount Erie in Washington State.

JASON D. MARTIN

CHAPTER 1

The Role of a Climbing Instructor

Working as a climbing instructor is a very special job. The dream is alluring: work at the crag every day under cloudless skies, become a master climber, explore new places, meet fascinating people, and teach them the art of rock craft. And while the dream is alluring, it doesn't reflect the complete picture. The reality is that when you become a climbing instructor you are no longer able to follow your climbing whims or operate the way you may have in the past as a recreational climber.

Working as a climbing instructor and climbing recreationally are two very different things. Recreational climbers assume a limited amount of responsibility for one another. There is an implied assumption between partners that each person will be the primary manager of his or her own safety.

Professional climbing instructors are not climbing recreationally and are not climbing for themselves. The job requires managing risk first, followed closely by the quality of the student experience.

The most critical role that a climbing instructor provides is that of a risk manager. First, we have to manage our own exposure to the inherent risks of working in a vertical environment. There is no student security without instructor security. And second, we must manage the risk to our students.

While risk management is the most important aspect of the climbing instructor's job, the quality of the student experience comes in a close second. When working in a climbing program, personal goals and ambitions are put aside. It is not about you "living the dream," but instead is about the students, their goals, and their ambitions.

At the outset one of the best ways to achieve the dual objectives of managing risk and student experience is to choose an appropriate crag. If the crag is appropriate to the student(s), then both the objective and subjective dangers will be manageable. Additionally, the student climber will feel comfortable in the setting and will be more emotionally open to learning the art of climbing.

The other major difference between recreational climbing and climbing instruction is the obvious fact that a climbing program is an instructional setting where students look for advice and training. This means, for example, that once an appropriate crag has been chosen, then the next step is to choose an appropriate curriculum. Think about where a student is at the beginning of the day, and what the desired goal is at the end. Don't skip or rush through instruction to accommodate instructor desires. Focus on where the student is and where he or she needs to be.

The most effective instructors are those who recognize these distinctions early in their instructional career. The most ineffective are those who attempt to teach while still acting as a recreational climber.

Terri Condon leads a trad climb during her AMGA Single Pitch Instructor Assessment at Joshua Tree National Park, California.

CHAPTER 2

Professionalism

Doctors, lawyers, and teachers don't have too many conversations about professionalism. They don't have to. They act the part without anybody telling them to. They dress appropriately for their workday, they use the language of their respective professions, they make concrete plans about how they are going to handle the challenges of their day, and they are respectful of those they're working with. Additionally, professionals are up to date with the best and most current practices in their field, they undergo formal training, they demonstrate a level of mastery through peer assessment and certification, they pursue continuing education, and they adhere to a code of ethics.

When climbing instructors act professionally, they represent three different interests. First, they represent themselves. If an instructor would like to be thought of as a respected professional, then she has to act as one. Second, they represent the companies, schools, or programs that they work for. In this day and age, a lack of professionalism can lead to negative press online, which can have a serious and long-term impact. And third, instructors represent all climbing instructors. If a recreational climber has a negative experience with one climbing instructor, that often creates an impression of climbing instructors in general.

Clearly, if an instructor develops a reputation for a lack of professionalism, it will affect his or her bottom line. Program directors don't want to hear anything negative about their instructors. What they want to hear is that everybody had a successful and enjoyable day.

Presenting oneself as a professional engenders trust and confidence from one's students. But there's a great deal more to professionalism than just attitude. Professionalism is something that should permeate every instructional day from the moment a student has contact with an organization to the moment he or she leaves.

Pre-Program Preparations

Professionalism starts in the office. The best way to present a professional program is to be prepared. Following is a short list of questions to consider before meeting students at the crag:

- Are there land-use permits in place or has permission to operate at the location been granted? If charging for a program on public lands, a land-use permit will be required. If operating on private lands, you may need to obtain permission.
- What are the rules and regulations regarding the area?
- Do you have liability insurance, or do you have coverage from the organization that you're working for?
- Do the marketing materials accurately reflect the experience that you will provide your students?
- If working a course for an organization, do you know what the marketing materials say about the course or program that you intend to run?
- Do the students have any medical conditions?

- Do you have student emergency contact information?
- Did you collect climbing biographies from your students?
- Have you or a representative from your organization been made available to the students to answer any questions that they might have?
- Have you researched the area where you plan to operate? Do you have a Plan B, in case your initial plan for the day falls through due to crowding or some other unforeseen circumstance?
- If it's going to be an instructional day, do you have lessons prepared?
- Do you have a release or acknowledgement of risk form for your students?
- Have you developed an emergency plan?
- Do you have appropriate first-aid training for the location that you intend to work?
- Do you have other required credentials? Some areas require instructors to obtain a state guide's license, and others require individuals to hold a Leave No Trace Trainer or Master Educator certification. If you're providing meals, some areas may require that you hold a food handler's license.

Obviously, some of these issues will be the responsibility of the organization an instructor works for. However, if the organization doesn't provide information on the questions that seem to be its responsibility, then it's the instructor's responsibility to make sure that each of these questions has been answered.

At the Instructional Site

Professionalism continues from the office and into the field. Once in the field, an instructor is a role model not only for the students, but also for other recreational climbers in the area. With that in mind, instructors should model the way that they believe people should act at the crag by being considerate and having a low impact.

Managing both the students and the scene is an important part of the day. This management doesn't necessarily relate only to the technical and pedagogical aspects, but it also pertains to how the instructor relates to the group, how the group acts, and how the instructor interacts with recreational climbers.

The crag needs to be a place for people to experience climbing without feeling put down or threatened. Threatening language in particular is sometimes not obvious and can come from inappropriate comments or jokes that might seem minor to an instructor, but can have an impact on one or more of the students. It is important to continually monitor the language, jokes, and conversations taking place so that all members feel respected.

When in contact with recreational climbers or other instructors, be professional, courteous, and friendly. Try not to tie up routes when other parties are waiting and make sure that students park themselves and their gear in unobtrusive places.

The ropes, harnesses, and equipment used on a program should be in good repair. The instructor's rack and rope should be organized in the instructor's pack before arriving at the crag. When unpacked, everything should remain organized. Avoid creating a "yard sale" at the base of the crag with equipment and packs scattered all over the place.

Most instructors choose to carry a notebook with student information, lesson plans, and time management strategies. This helps an instructor stay on track and organized. An organically run day without set lessons, strategies, and notes is feasible for advanced-level instructors, but should be avoided by those new to the profession.

The way that each individual instructs is different, and it's often difficult to determine how long it will take to teach certain lessons or to cycle through students at a toprope or rappel site. For new instructors it's important to keep track of how long each activity takes in the instructor's notebook. This will help with time management strategies on future programs.

Managing student time is only one aspect of time management. Often the most time-consuming element of the day is setting up and taking down systems. It is imperative that instructors have mastery of these foundational skills. Additionally, when planning for the day, instructors need to remember to account for this time.

AMGA Single Pitch Instructors are required to be able to lead 5.6 traditional routes and to toprope 5.8, both in good style. These are minimum standards, and most instructors climb harder than the standard. Though an ability to "climb hard" is not a prerequisite for an instructor, an ability to model good technique is. Professional instructors should constantly work on their climbing skills in order to demonstrate the best technique possible.

Professionalism at the crag is essential. A climbing instructor's professional demeanor should be a model for students, for recreational climbers, and for other instructors from before the trip starts to the moment that the last student leaves.


UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
SPECIAL RECREATION PERMIT APPLICATION
FORM APPROVED
OMB NO. 1004-0119
Expires: December 31, 2013
Type or Print Plainly in Ink
Red Rock Canyon NCA - 2012-2017
Southeast Utah - Moab BLM - 201
Squamish
National Park Service
U.S. Department of the Interior
NATIONAL PARK SERVICE
Application for
Guided Rock Climbing and Climbing Instruction
Commercial Use Authorizations

A stack of permits and permit applications at the American Alpine Institute.

JASON D. MARTIN

CHAPTER 3

Programming

Most climbing schools offer a variety of courses. Within the simple beginner to advanced-level framework, there might be any number of courses that focus on a specific skill or a specific series of skills. These could include anything from beginner courses for people who have never put on a harness before, to advanced courses in high-end movement or traditional lead climbing.

Regardless of the course, the one thing that instructors must keep in mind is that students signed up for a specific curriculum, and aside from managing risk, the most important instructor goal of the day should be to honor that curriculum.

To provide the curriculum that has been sold, instructors will need to find an appropriate crag for the program. To operate at the crag, they will need a land-use permit and an understanding of liability. They will need to be aware of risk management issues and develop an emergency response plan. They should be conscious of crag etiquette and advocacy. And they will need to have functional equipment for their programs and foster good communication with other staff members. In other words, to provide the curriculum that has been sold, the instructor will have to do a lot of prep work.

Permitting

In the United States, climbing destinations are managed by a patchwork of different agencies that operate independently of one another. On the federal level the primary land managers include the National Park Service, the USDA Forest Service, and the Bureau of Land Management. Regional land managers include state, county, and city parks and private lands. This variety and the many different and sometimes contradictory rules and regulations pose serious administrative challenges. In addition to all this, the resource is not growing, but the demands on the resource are.

The popularity of recreation on public lands has exploded over the last decade. This has resulted in more and more commercial operators vying for a limited number of permits. The combination of this and the mandate that land managers preserve and protect wild places has created an often-frustrating challenge for independent instructors and organizations that seek land-use permits.

Legal access to public lands in particular is important because most climbing instruction takes place on such lands. If the students pay a fee of any sort to participate—whether for a commercial operation, a nonprofit, an individual instructor, a school, or a university—then a permit is required to operate legally on public lands.

Operating on public lands without a permit is breaking the law and could result in a wide array of consequences. These range from a minor citation to a significant fine or even an arrest. In some cases it is possible to be permanently banned from public lands for willfully disregarding land-use regulations. Indeed, there are some insurance providers that will deny coverage if they discover that an operator was working without a permit at the time of an incident that resulted in a lawsuit. Working on public lands without a permit is serious and should never be taken lightly.

There are two main questions that an individual or an organization should ask to determine whether or not a land-use permit is required:

(1) Did the participants pay to engage in the activity?

Did they pay any fee at all? Were they asked to pay tuition for the course or guided days? Were they asked to submit a donation to the program? Are they required to rent equipment from the operation in order to participate?

If the answer to any of these questions is yes, then the land manager should be contacted to determine if a commercial-use permit is required. Even if you are a volunteer instructor for a club, but the club is taking in funds, the land manager should be contacted to determine if a permit is required.

(2) Are the instructors getting paid to run the program or to provide the instruction?

If the instructors receive any kind of compensation, then they or the organization will need to obtain a permit. Compensation could mean an hourly or daily wage, a stipend, meals, or even "free" equipment. Nearly any type of compensation outside of a thank-you constitutes commercial use.

There is a bit of a gray area when it comes to salaried teachers or professors who work with students from their school at a crag. Some land managers will require such a group to obtain a permit, whereas others will allow it to operate without one. Teachers and professors should contact the land manager at the desired location for more information.

Some public lands have special permits for educational institutions and not-for-profits. Educators are encouraged to contact land managers to see if they have programs like this available. If an area does not offer "educational permits," it is encouraged to suggest such a program to the manager.

The first step to obtaining use authorization is to contact the land management agency and get in touch with the person who handles recreational commercial or nonprofit use.

If the land manager is accepting new permit holders, he or she will provide an application. It is not uncommon for the application process to take a significant amount of time, so plan adequately.

Nearly all permit applications will require some kind of application fee. It is not uncommon for land managers to also ask for additional monies prior to the issuance of a permit. These include, but are not limited to, monitoring fees, reservation fees, or administrative fees. The costs for all of these vary based on the land management agency and the type of permit.

Nearly every land manager will require commercial users to hold general liability insurance before issuing a permit. The land manager is usually included in the policy as an "additional insured." This liability policy—often between $500,000 and $1,000,000—provides them some cover if an accident takes place during a program.

At the end of the year, the permit holder will be required to submit reports that include revenues and user days. Many contracts include a clause that states that the land manager has the right to audit a permit holder at any time. Therefore it is important for organizations to keep excellent financial and user day records, as failure to do so could lead to the loss of the permit. It should be noted that many land managers compare your reports to any other reports that they have on hand. For example, if an instructor has to sign in at a ranger station before operating each day, the land manager will compare the final report to the information gathered at the station.

Fees are calculated in different ways. Some land managers charge a flat fee for operations, whereas others charge anywhere from 2 percent to 4.5 percent of gross income. Most charge 3 percent of gross.

Guides, instructors, and guide services spend a great deal of time trying to obtain and then maintain their permits. For many, this is a major administrative duty. As a result, the way that the majority of new guides and instructors choose to access public or private lands is through guide services or other organizations that have laid the groundwork and developed relationships with local land managers. In many cases it is much easier to get hired by a guide service than it is to obtain an individual permit.

Risk Management and Liability

In the context of climbing instruction, risk management is broadly defined as the identification of the risks that pose a threat to students, instructors, or a program, and to find ways to avoid or mitigate those risks.

A recommended practice for avoiding and mitigating risk is to systematically assess potential sources of harm, outline ways to avoid or reduce exposure to harm, and determine how to respond in the event of an incident or accident. When compiled into a document, a risk management plan is created. No matter the size of the program, from the very smallest to the very largest, the development of a written plan is essential. Additionally, everyone involved with the program should have a copy of the plan and be familiar with the contents.

An intelligent and well thought out risk management plan accomplishes the following:

- It can greatly reduce the number and severity of incidents or injuries.
- It protects the instructor and the program from potential negligence lawsuits.
- In the event of a negligence lawsuit, it can provide a layer of protection to the instructor and program during the defense against the suit.

An emergency response plan is typically a part of the overall risk management plan.

There are a number of considerations that should be addressed in the plan.

First-Aid Requirements

Climbing instructors must have appropriate first-aid training. The AMGA terrain standards state that Single Pitch Instructors are required to hold and maintain a Wilderness First Aid (WFA) certificate if they intend to work in the frontcountry, or a Wilderness First Responder (WFR) certificate if they intend to work in the backcountry. If it will take less than 2 hours to evacuate a student to definitive medical care, then an instructor is working in the frontcountry. However, if it will take more than 2 hours, then an instructor is working in the backcountry and will need to hold a WFR certification. Additionally, instructors must hold a CPR certification. Most American guide services require their instructors to maintain WFR and CPR certifications.

Participant Screening

Collect both physical and medical information on the trip's participants. Be sure to be aware of any conditions that might need to be considered before the trip, such as allergies, injuries, or medical conditions that could hinder a student's ability to participate. It is important to have this information in the field in case something happens, but it is equally important to protect each student's privacy in these matters.

Communications

If an incident occurs, it is imperative to have a communications plan. If the plan is to use a cell phone for this, be sure to know where there is reception and to have all appropriate phone numbers. If using a radio, a sat phone, or a personal locator beacon, understand how each of the devices work. Additionally, if there is a possibility that students will be required to operate one of these devices, they will need to be briefed on their use.

Evacuation

Instructors need to have a plan for an injured climber. Obviously there are levels of injury—some will only require an easy hike out, whereas others may involve a carryout or even an air evacuation. If evacuating the climber, an instructor should know where the nearest hospital is located. If calling for a rescue, have an understanding of what will happen and who will show up.

Minors

In the United States, by law, a minor child cannot enter into a contractual agreement. A release of liability is a contract. Additionally, some states allow legal guardians of minor children to sign away their right to sue; most do not. There are strategies for dealing with this dilemma, but they are beyond the scope of this book. The bottom line for the Single Pitch Instructor is to be aware of the protocols put in place by the organization one works for and to follow those protocols.

Student Safety Briefing

Before the trip starts, explain safety procedures to your students. Brief them on the communications plan and where the nearest hospital is located. If carpooling to the crag, it will be important for everyone to note where the keys are stored, whether in a pack, a pocket, or hidden near the vehicle. And lastly, the instructor should show the students where he or she keeps the first-aid kit and check to see who else in the group has first-aid training.

Post-Trip Contact

Establish somebody to check in with at the end of each program. If the instructor does not check in on time, that person needs to have instructions on what he or she should do to facilitate a rescue.

Incident Debrief

If something happens and a student or an instructor is hurt, or if there is a "close call," it's important to debrief the incident with the organization's management and with other instructors. Climbing instructors can learn a great deal from discussions following an incident.

Assumption of Risk and Liability Release Forms

Another important risk management tool is the use of release of liability or assumption of risk forms. When well crafted, these documents serve two purposes. First, they inform participants of the "inherent risks" that are or could be involved in rock climbing. Even the best risk management planning cannot eliminate all risk. Inherent risks are risks that are an integral part of an activity, which, if removed, completely alter the nature of the activity. By signing one of these documents, a participant is acknowledging that they have been made aware of the risks and that they are choosing to participate despite the risks.

Second, in the event of a participant's injury or death, these documents protect the instructor and program from charges of negligence. Simply put, negligence means that the instructor and the program have a "duty" to manage the "foreseeable" risk of harm to participants. A claim of negligence means that they failed in that duty, an incident occurred, and the participant suffered a loss. With a properly executed release of liability form, a participant is agreeing to give up the right to sue for negligence.

It is essential that all participants sign a release of liability or an assumption of risk form. Making sure that happens is often the responsibility of the climbing instructor. A recommended procedure for executing this process properly is to:

- Inform participants to read and, if they agree to the terms, sign and date the document.
- Allow the participants time to read the document. This process should not be rushed.

- Collect the documents, making sure they have not been altered and are signed and dated. If the form uses boxes or lines after paragraphs, be sure they are checked or initialed.
- Store in a secure location.

If a participant will not sign the document as it is written, they cannot be allowed to participate in the activity. Also, it is not the responsibility of the instructor to interpret language in the document for participants. A well-written release should use language that a "reasonable" person can understand. If the same questions come up time and again, it is time to have the document reviewed by an attorney familiar with recreation law.

Liability

A question often asked by climbing instructors is "Can I be held personally liable and sued in the event of an accident?"

The bad news is that the answer is yes. If an accident involving serious injury or the death of a participant occurs, a lawsuit may follow. Along with the program, it is common that the instructor involved will be named as a defendant. The good news is that having general liability insurance will assist in the defense of the suit, and if a settlement is either reached between the parties or is handed down by the court, it will cover all or most of the settlement costs and, in some cases, but not all, attorney fees. That said, it is important to understand that not all liability insurance policies are created equally. These types of policies tend to be written in technical language that is difficult for the layperson to understand, consist of many pages, include exclusions, and don't make for the most exciting reading. Regardless, there are several questions a climbing instructor should ask:

- Are all employees covered? This may depend on whether the instructor is an employee or an independent contractor.
- Does it cover all activities? For example, some policies will cover rock climbing, but not ice climbing.
- Is it in effect for all areas of operation? The policy may not be in effect if the instructor or program is guiding without a permit.

For the climbing instructor, the name of the game is to reduce exposure to liability. Basically, this means conducting business at the "standard of a reasonable professional." This includes, but is not limited to, following a program's policies and procedures, being in step with current industry standards, using appropriate and well-maintained equipment, being respectful and building a good rapport with students, adhering to the rules and regulations of land management agencies, and getting training and, ideally, certification for the terrain worked on.

Even when following the best practices, there are a couple of subtle ways that climbing instructors can inadvertently increase their exposure to liability. The first is misrepresentation. An example of this would be an instructor who markets services as an "AMGA Guide," "trained and certified by the AMGA," or any of a number of other examples, but in reality is an AMGA Single Pitch Instructor. The problem here is that it would be pretty easy for a participant to make the case that when he purchased the services of an "AMGA Guide," he thought was hiring a fully certified IFMGA/AMGA Guide; in other words, he paid for one thing and got something else. In legal terms, this is referred to as "fraudulent inducement." If a court were to uphold the accusation, one likely outcome would be that all contracts between the instructor and the participant would be nullified; this includes the release of liability. Should that occur in a negligence suit, one of the most important tools for the defense is gone. The solution to this problem is easy: Instructors need to be specific about who they are and what they do when promoting their services.

The other subtle way to increase exposure to liability is to tell participants they will be kept safe. A legal definition of the word *safe* is "free from harm." As mentioned earlier, a "reasonable person" understands or has been informed that there are inherent risks in rock climbing. However, if marketing materials, operations manuals, a website, or the instructor tell participants that they will be kept safe and someone is injured or killed, any defense that might have been provided by the common law doctrine of inherent risk will have been severely compromised, if not lost. Again, the solution is fairly simple: Climbing is not safe, don't say that it is.

Risk Management in the Field

For AMGA Single Pitch Instructors, there are four types of risk that students might encounter on a program. They are psychological, sociological, financial, and physical. It's important to recognize each of these risks to students and to understand how to mitigate them.

Psychological

The fear of falling and the fear of heights are simultaneously attractive and repellent to students. Many new climbers are fascinated by the idea that they can climb to a point where a fall would result in their death, whereas others seek out climbing to combat a fear of heights.

There are two common ways to alleviate a student's fear of heights. The first is to spend a significant amount of time early in the day discussing "the system." In other words, explain the strengths of the ropes, the slings, and the other equipment. The idea is to assure students intellectually that the system will not fail. The problem is that an intellectual discussion is often not enough to alleviate the emotional nature of their fears.

The second way is through exposure therapy. The more often a climber is lowered on a climbing rope and caught by a belay, the more secure he will feel. Additionally, the more that a climber actually climbs, the more secure he will feel. For this reason, it's always a good idea to have a beginner climb a route more than once.

In extreme situations where a climber has a severe fear of heights, instructors might consider using incremental exposure therapy. In other words, have the student climb up 5 feet and then lower him. Then have the student climb up 8 feet and lower again. Every time the climber goes up, there will be an incremental decrease in fear. This is because the climber is becoming familiar with both the moves on the route and the security offered by the system.

Sociological

A second risk is fear of failure in front of other students, or in front of the instructor. Some may even be afraid of ridicule for their failure. It's not uncommon for students to apologize for their inability to complete a route. Some are embarrassed, and others believe that the fact they didn't get up somehow damaged the day for other students or the instructor. This, of course, couldn't be further from the truth.

Students need to be comfortable with you and with the others in your program. Instructors should strive to create a place where it is acceptable for their students to fail. At times this may mean moderating student comments to ensure that negativity is kept to a minimum.

Another excellent tool is for the students to see the instructor challenged on a route. Once a student has displayed competency with belaying, climb a route that is hard for you and let the students watch as you try to work out the moves. This will help them to understand that working a route, taking falls, and failing is part of the game.

Financial

Anytime a person spends money on a program, there is financial risk. A lot can go wrong that could make an individual feel like she wasted her money. These include the following:

A professional search and rescue deputy is short-hauled to an accident victim in Red Rock Canyon, Nevada.

JASON D. MARTIN

- Program goals were not met.
- Course was poorly or unprofessionally run.
- Student was placed in a course that didn't match her skill level.
- Personal equipment is lost or broken.

These four financial risks are easily averted. First and foremost, it's important to run a professional program. Instructors should meet and attempt to exceed all program goals.

Second, when screening someone for a program, ask probing questions to make sure that the student is placed in the proper course. Occasionally an instructor is placed in the awkward position of working with a student who has been assigned to the wrong program. A skilled instructor does her best to accommodate the person, and then makes sure that program administrators are made aware of the mistake.

And finally, be careful with student gear. Make sure that everyone leaves with the same equipment they arrived with.

Physical

The most obvious risk in rock climbing is that of an injury or a fatality. This is likely the number one risk that students think about when they sign up for a course.

The best instructors are those that are a little bit paranoid. Managing risk is paramount in climbing instruction, and an instructor who can imagine a wide array of dangers is an instructor who is likely to keep her students from injury.

There are a handful of things a climbing instructor can do to mitigate physical risk:

- Orient students to safety procedures around the crag. These include everything from checking knots to belay backups to climbing commands, etc.
- Create boundaries at the climbing site. Some crags are exposed, and there are places where students shouldn't be without a rope. Other crags may have excellent resting spots where students can relax away from the base without their helmets on. Make it clear to students what is appropriate at the crag.
- If working with other instructors, meet regularly to discuss risks and other programming issues. If working alone, set aside time to speak to other instructors and program administrators about their experiences.

Risk management and liability in adventure sports and adventure tourism is a massive subject. Seminars are held every year on this topic at the Association for Outdoor Recreation and Education (AORE) Conference, at the Wilderness Risk Management Conference, and at the Association for Experiential Education (AEE) Conference. Additionally, dozens of books, blogs, and websites are devoted to the subject.

Understanding liability is something that instructors—especially independent instructors—need to invest themselves in just as deeply as the rest of their training. Knowledge of liability issues is not the sexiest part of the climbing world, but can go a long way toward keeping an instructor in the field and out of the courtroom.

Stewardship

Because climbing instructors visit the same crags over and over again, they are in the unique position to see problems as they arise. Whether there are issues with graffiti, trail-braiding, litter, or something else, they are often the first to notice. Noticing is not enough. Climbing instructors should be advocates for the places where they work.

It is not uncommon for instructors to go to work and then go home, leaving the issues surrounding the crag at the crag. Perhaps they clean up some trash while they're in the field, but they don't make much of an effort beyond that. It is essential that instructors work to be more involved in stewardship, local climbing politics, and climbing advocacy.

AMGA Access director Scott Massey removes and replaces an old bolt on Rebel Without a Pause (5.11a) in Red Rock Canyon, Nevada. Prior to working for the AMGA, Scott guided in Red Rock, where he oversaw numerous crag-related stewardship projects.

JASON D. MARTIN

Many climbing areas have a local climbing stewardship organization. Sometimes these are connected to the Access Fund, and sometimes they're stand-alone organizations. Many advocacy groups focus on a very specific area, like the Friends of Indian Creek, the Las Vegas Climbers Liaison Council, or the Friends of Joshua Tree; whereas others have a much broader scope, like the Washington Climbers Coalition, the Northern Colorado Climbers Coalition, or the Southeastern Climbers Coalition. Regardless of an organization's purview, all of these organizations have one thing in common: They need volunteers.

If you don't have the time to volunteer for an advocacy group, make sure to participate in "Adopt-a-Crag"–style activity days. These usually involve litter cleanup and trail-building activities. They may also include re-bolting projects or the removal of invasive plant species. These events are excellent places to meet other local climbers and to give back to the place that provides you an opportunity to work.

Crag stewardship is not just good for the climber's soul; it's just the right thing to do.

Instructor Meetings

If working with another instructor, plan for informal meetings throughout the instructional day. This allows everyone to stay on the same page. Issues that come up during the day can include anything from safety concerns to instructional problems, from inclement weather strategies to dealing with a difficult student. In other words, these meetings cover the gamut.

If working for an organization or guide service, administrators may have formal meetings or debriefs after each course. If they don't actively provide a debrief session, then take the initiative and offer to meet with them. Most administrators appreciate it when new instructors come to them to talk about their programs.

Finally, if you have the opportunity to meet with the instructional staff on a weekly or monthly basis, take advantage of that. Instructors often work alone or with one or two other people. The more exposure you have to other instructors, their hardships and victories in the field, the better an instructor you will become.

CHAPTER 4

Pedagogy: The Art of Teaching

As climbing instructors, it's easy to get focused on the technical aspects of the job: A cam goes here, a rope goes there, a belay works like this, a lower works like that, etc. When we're with other instructors, we tend to talk about how to run a program at a given crag or how to deal with a certain technical situation. Indeed, our students come to us in part because we're experts in the technical aspects of climbing, but that's not the main reason why they climb with us.

They climb with us because they want to learn.

Musicians, actors, writers, painters, and photographers are artists. They spend years refining every aspect of their craft, becoming better as each day marches by. After decades of criticism and self-assessment, these people become masters.

Pedagogy is the art of teaching. And like the musician or the painter, one must dedicate time and energy to the art in order to become a master.

This chapter provides an introduction to the art of teaching as it pertains to climbing. But this is only an introduction, and it is recommended that aspiring instructors seek out other resources—both master-level instructor mentors as well as written materials on educational theory and technique—to continue moving personal development toward mastery.

Learning Styles

Effective instructors not only demonstrate a wealth of knowledge and expertise, but are also able to convey information about what they know in a way that others can readily comprehend, understand, remember, and then go out and use themselves.

When teaching a figure eight follow-through knot to a group of six novices, something like this typically happens: About half the group gets it right the first time, two people get it right after a few tries, and one person just can't get it right even after multiple tries. Why is this? People have differing learning styles, and it is usually not a question of intelligence, but rather a problem with the way the information is being presented that does not suit their particular learning style. Often, taking a different approach with the presentation of the information will help in comprehension and retention.

The theory of learning styles presented here is based on New Zealand educator Neil Fleming's VAK model. There are a number of different theories out there, but this one is a good introduction to the concept of how people learn.

The three main learning styles are visual, auditory (verbal), and kinesthetic (VAK). And although most people embody some combination of different learning styles, one is usually predominant.

Learning knots at Joshua Tree National Park, California.

Visual learners pick up information most effectively by reading the written word and viewing photos or illustrations. They need to see it to learn it. This group represents the highest percentage of the population (roughly 65 percent), and they learn most effectively from written communication. Visual learners think in pictures and words. They prefer their information presented in a written format as opposed to the spoken word, and usually prefer to take detailed notes when presented with verbal information. They can have difficulty with spoken directions. For example, a verbal description of how to get to some place is likely ineffective to them, but a written description along with

a map would prove useful. For this group charts, diagrams, graphs, and visual schematics are highly effective. When teaching a knot to this group, a verbal description is of little help, but presenting the sequence of tying the knot like a schematic diagram, with step 1, step 2, and so forth, may prove more successful.

Auditory, or verbal, learners represent another large segment of the population (around 30 percent) and learn most effectively from the spoken word. They need to hear it to learn it. This group is composed of the most sophisticated speakers, and they relate most effectively to spoken words. They are good listeners and will listen attentively to a verbal presentation and take notes afterward. They benefit from hearing lectures and participating in group discussions. They prefer their information presented in a verbal format, and for them information is not tangible unless it is spoken. They can have difficulty with written directions.

Another, much smaller, percentage of people are kinesthetic learners, who learn by doing, by getting the feel and tactile sensation of performing the steps required to learn a task. They are usually gifted athletes and can learn a knot just by seeing it tied, then tying it once or twice. Kinesthetic learners prefer hands-on learning and can appear slow if information is not presented to them in a style that suits their learning method.

Most people learn most effectively by watching, doing, and reflecting on a particular technique. Around 450 BC the great Chinese philosopher Confucius said: "Tell me and I will forget; show me and I may remember; involve me and I will understand." Various research studies point to the fact that people remember best by watching a demonstration, having a discussion, practicing the skill, then teaching it to others. Military trainers use the EDIP principle (explain, demonstrate, imitate, practice).

When teaching climbing techniques, the climbing instructor should present the topic in a way that most broadly targets all the differing learning styles. The approach can be simple:

1. Tell (auditory or verbal)
2. Show (visual)
3. Do (kinesthetic)

Using this approach, here is an example of how to teach an abstract concept, such as a complicated knot:

1. Tell. Verbally describe the steps to tie the knot.
2. Show. Demonstrate the knot. Facing in the same direction as the person being taught is helpful.
3. Do. Have the student practice tying the knot.

This is the basic approach, although there are additional teaching methods that will help in memory retention and learning, namely imagery and mnemonic devices. An example of using imagery when teaching the bowline knot: "The snake comes up through the hole, around the tree, and back down through the hole." Attaching a verbal image of an animal or thing is one of the most effective ways to remember an abstract concept.

Mnemonic devices are another form of memory aid. The most common one is the acronym. The military is big on acronyms, like IED (improvised explosive device), SOTG (Special Operations Training Group), etc. In teaching climbing, some common acronyms are ABC (anchor, belayer, climber) or BARCK (buckle, anchor, rope, carabiner, knot).

To most effectively teach climbing techniques, it's best to start with an approach that presents the information for a broad range of learning styles, then try to identify each person's particular learning style in order to aim directly at his or her individual style. If someone is not getting the information, change the approach and present it another way. Use imagery and mnemonics to help students remember key principles (like safety checks or anchoring fundamentals), and chances are they will retain these key concepts throughout their climbing lifetime.

AMGA_i-258_3pp_CS55.indd 19 2/27/14 11:48 AM

Lesson Planning

Many climbing instructors are natural born teachers. But even the best teachers do a better job when they have a structure to work within. Creating concrete unit and lesson plans provides that structure.

Remember when you were in high school and there was a unit on the Civil War or a unit on *Romeo and Juliet*? And remember when during that unit, you studied the battle of Gettysburg or Shakespearean language? These were individual lessons inside of a larger learning arc, an arc that is referred to as a unit.

In rock climbing instruction a unit could cover something as vast as anchor building, while an individual lesson within that unit might cover something like placing a cam. In other words, a lesson is a bite-size piece of a unit, and a series of lessons together combine to provide the knowledge required to complete a unit.

Student-Learning Objective—This is the overriding goal of the lesson or unit, what students should be able to show after they have received instruction.

Examples of student-learning objectives for units and individual lessons include the following:

Unit Objectives

- Students will demonstrate an ability to pass a climbing gym test.
- Students will demonstrate an ability to build an anchor.
- Students will demonstrate an ability to set up a toprope.

Lesson Objectives

- Students will demonstrate an ability to tie a figure eight follow-through.
- Students will demonstrate an ability to belay effectively.
- Students will demonstrate an ability to use appropriate climbing commands.

Please note that each of the preceding sentences starts with "students will demonstrate an ability to . . ." It's incredibly important for every learning objective to start with this, because it provides a concrete goal that can be measured.

In a lesson plan, start with the student-learning objective, work into the specifics, and then culminate in an evaluation. There are many examples of lesson plans out there, but they all start with a learning objective and finish with an evaluation. Following is a simple outline of a lesson plan and how each part of the lesson functions:

Student-Learning Objective—"Students will demonstrate an ability to . . ."

1. **Set**—Preparation for what the students are about to learn. It could be a complex and creative opening, or a very simple, "this is what you're going to learn today."
2. **Input**—The actual teaching of the lesson.
3. **Guided Practice**—Working with the students until they achieve mastery.
4. **Evaluation**—Evaluating whether the student has learned the requisite material.

Many instructors do a very good job of identifying a learning objective, setting up a lesson, teaching it, and practicing a skill, but often don't evaluate students when they're done. Evaluation is just as important as any other part of the lesson.

Following is a sample plan for a knot-tying lesson:

Student-Learning Objective—Students will demonstrate an ability to tie a figure eight follow-through.

1. **Set**—Explain to students that this is one of the most important knots they will learn. They will need this knot to tie into the rope, and if they want to join a climbing gym, they will be tested on it.

2. **Input**—Demonstrate how to tie the knot. With certain populations you might choose to use a mnemonic (a memory trick) to help the students remember.

AMGA_i-258_3pp_CS55.indd 20 2/27/14 11:48 AM

Single Pitch Instructor Sample Lesson Plan

Lesson Title: **Timeframe:** Overall timeframe for the lesson:

Student-Learning Objective: Students will demonstrate an ability to . . .

Audience: Brief description of the audience including age, skill level, limitation, etc.

Prerequisites: List any prerequisite training or skills.

Lesson Location and Special Notes: Identify where the lesson will take place. Have a back-up plan in place if the location is being used. Add reminders such as equipment needs, classroom prep, and "don't forget" notes.

Time	**Materials**
____min	**Set:** Prep the students for what they are going to learn.
____min	**Input:** Provide the content of the lesson.
____min	**Guided Practice:** Work with the students to achieve mastery.
____min	**Evaluation:** Test the students on their mastery of the subject.

Does the lesson reach multiple learning styles? **Yes** **No**

Instructors new to lesson plans should photocopy this sample plan and fill it out for each lesson they intend to teach.

3. **Guided Practice**—Practice the knot with the students.
4. **Evaluation**—Have all the students show that they know how to tie the knot.

Many less effective climbing instructors don't take the time to build lesson plans. The result is that they learn how to teach through an organic process of trial and error, which is terrible for the students who are forced to work with an instructor on an error day.

A review of the day with input from the students provides valuable feedback from their perspective of how they perceived an instructor's presentation of the topics. This allows the instructor to improve and modify the approach for the next time. Getting feedback from students is key to becoming a better instructor.

The best teachers prepare lesson plans on paper ahead of time and then continue to tweak them over a period of months and years. They use a structured approach through student feedback and self-assessment and keep track of what works and what doesn't work. They make note of all student-learning objectives and do their best to make sure that their students achieve those objectives.

Master teachers don't just appear out of the woodwork. They work hard every day to be the best.

Harsh Lessons

In my (BG) career as a rock climbing instructor, I've received training and undergone testing and evaluation of my guiding skills. The toughest lessons, but the most memorable ones, came from the mistakes I made that were critiqued by my mentors and peers. I've also found, in my role as an examiner for the AMGA Single Pitch Instructor exam, that candidates learn more and remember best from their mistakes when it really counts, when they're being scored in a pass or fail test situation. The harshest lessons in life are the ones we don't soon forget.

Learning from Mistakes

Asking a student with some experience to perform a task can tell an instructor a great deal about the student and where to begin. For example, one quick test that can be given to new students is to simply hand them the end of the rope with the instructions: "Go ahead and tie into the rope." The way that they accomplish this easy task tells more about where they're at than even a brief interview.

Another example: When teaching anchoring fundamentals to a group class in a ground-school setting, present a concept with a verbal presentation, a demonstration, and then a hands-on practice (tell-show-do). Give each of the students a scenario (e.g., this is the edge, here are the crack systems you can work with, build your anchor system so that your master point is here, etc.), then let the students build an anchor system to their satisfaction, without constant coaching by the instructor along every step in the process. By letting them finish without instructor input, they are likely to make some mistakes. Then, as a group, go around and critique each anchor system setup. In this way everyone learns from everyone's mistakes. The big plus is that it gives the instructor valuable and instant feedback on whether or not the students have grasped the concepts just presented and shows what they (or we) need to work on to achieve our objective.

This can be a very effective strategy when teaching a lesson to one or two students who have some modicum of anchoring experience but have asked for a refresher course. Start by giving them

Anchor rigging session during AMGA Single Pitch Instructor course at Joshua Tree National Park, California.

a specific scenario, like rigging a toprope anchor, and then let them rig it without any coaching. What is seen in the final product of their anchor system helps the instructor decide if he or she needs to start with more basic concepts, or can simply move on and build from a solid foundation to more advanced topics. At this point the instructor can prepare a lesson plan specifically targeted at the students' skill level and build upon their current foundation to reach the objective for the day.

Teachable Moments

A less formal way to present information is to explain and describe the technique as it comes up during the course of the outing or class. These are often referred to as teachable moments. For example, when setting up a climbing situation for students, explain to them as they are tying in to the rope the importance of closing the system by tying a stopper knot in the other end of the rope. If they are on a slab climb and their heels come up, tightening their leg muscles, explaining the correct technique of relaxing the calf muscles and dropping the heels down is a teachable moment. Try to keep it positive. Many teachable moments occur when a simple mistake has been made, and addressing it at that very moment is a great way to teach someone the correct way to do something. The trick is to do it in a positive way that encourages the student to try something new and instantly improve or react positively to a potentially negative situation. Often, the ideal time to address a question is at the moment a particular event that illustrates a key point is occurring. This adds valuable context to the concept.

Taking Kids Climbing

Many kids are natural climbers with an instinctive curiosity and tendency to want to climb things. If you take kids to a rock climbing environment, they'll spontaneously want to explore, climb boulders, and scramble around on the rocks. The obvious danger, however, is that in a fall or slip they can get seriously scraped up, or worse.

Climbing develops muscular strength, balance, and kinesthetic awareness and introduces kids to valuable concepts like problem solving, teamwork, and the success that comes from perseverance and determination.

Toproping is the best method to use to take kids climbing. By the time they are in elementary school, most kids will have reached the level of physical and emotional development to allow them to enjoyably experience climbing in a toprope setting. Nevertheless, there are definitely challenges among this population. It can be difficult to sustain the attention of small children for any sort of sustained lesson. Try to reserve lengthy lessons for those children who seem to show an active interest in acquiring new skills.

It can be very difficult to initiate a lower on a small child. Many of them are so small, the friction of the toprope system is almost as great as the child is heavy. Low-friction belay devices, skinny ropes, and smooth, round-stocked carabiners at the master point can help, but in some cases, the other end of the climbing rope can be used to help retrieve these small climbers.

Selecting climbing equipment for small children can also be challenging. Many small children do not have well-defined hips, so a standard sit harness would be inappropriate for them. There are a number of full body harnesses designed for children, and these should be seriously considered if programming for children becomes frequent. Similarly, small climbing shoes are not always the first thing an instructor considers when selecting shoes for a fleet, but climbing shoes are just as helpful for a 6-year-old as they are for a 60-year-old. Climbing helmets are also just as important for children as for adults, so having those sizes available will be essential.

Route selection is also a challenge when designing programming for children. Because they are so much shorter than even the shortest adults, they will often use drastically different movement strategies than adults. Smaller holds are more realistic options for smaller hands. Be careful, therefore, of feature-oriented climbs, like face climbs. Sometimes the distances between holds are just unrealistic. Instead, try to find climbs that have a homogenous character for the entire pitch, like crack climbs, chimneys, or slabs. A climb with a uniform character can be climbed by people of all sizes. Set up a short, easy climb on either a low-angle slab or a short wall with abundant hand- and footholds. Teach them the basic climbing signals. For their first time, have them climb up a short distance (say 10 feet above the ground), then go through the signals and have them lean back and weight the rope, get into the lowering position, and get lowered back down to the ground. If a child does not possess the requisite balance to successfully be lowered down the climb, or if they are so small they will require some sort of retrieval system, it is better to know that *before* they reach the top of a climb. Take on a climb in small increments, and don't allow them

How Young Is Too Young?

I (BG) have seen, over the years, cases of precocious children with great balance (as young as age 3) who were physically talented enough to climb and be lowered on a toprope.

AMGA Single Pitch Instructor Tim Page assists as a child lowers. If a child is too light to lower, you may be able to attach the other end of the rope to his harness and pull down to provide more weight.

JEREMY WILSON

What Makes a Good Teacher?

Just because you can run 100 meters in 9.7 seconds doesn't necessarily mean you'll be a great track-and-field coach, but it helps. If you have great talent and are able to effectively communicate, you have a winning combination. But I (BG) have seen many world-class climbers who were poor teachers, and many competent but not exceptional climbers who were excellent teachers. What I always look for in my climbing school are instructors who have both traits: talented climbers and patient teachers. Climbers who have mastered all the various climbing techniques at a high level can ultimately be the best teachers, as their mechanics and fundamentals are so sound that they have the innate ability to easily demonstrate key concepts. But they also must be effective communicators and have enthusiasm, patience, empathy, and a desire to share their knowledge in a way that truly benefits their students.

to climb too high above the ground if they're not ready for it. You want the experience to be fun, not terrifying. If they're not yet able to be lowered down, they can swing around on the rope and play on the rock a little bit. There will be a next time. Just familiarizing them with the rope, harness, and equipment can be a good start.

Teaching Climbing Movement

Perhaps the greatest teaching challenge instructors will face involves actually showing people how to use their bodies on the rock, how to actually climb things. The magnitude of the subject is unfathomable. If an instructor looks at a single climb, for example, how many different moves are on that climb? Are there patterns? Are there consistent strategies? The variability of the moves on a single climb is of course compounded by the variety of bodies that will attempt to climb it. This person is tall, this person is short, this person has great upper body strength, this person has none. Even if the bodies were identical, this person is aggressive, that person is contemplative, this person is fearful, that person climbs with reckless abandon, and so on. Of course, instructors don't get to teach one climb; they are trying to teach dozens of climbs, on dozens of crags, with dozens of rock types, in dozens of climates. It is an immensely dense subject.

This text cannot reasonably cover a topic that large, and it is probably folly for an instructor to attempt to do so as well. Instead, try to focus on what is absolutely essential for a successful experience. When teaching beginners, instructors should first focus on the fundamental difficulties all beginners have: It is difficult to make a bipedal creature move in a quadrupedal manner. Second, teach the specific moves that your students will need to climb in a given area.

Bipeds Becoming Quadrupeds

Most mammals move through terrain on all four limbs, and the coordination of those four limbs does not change when they begin to climb trees, mountainsides, or even rock cliffs. Humans have evolved to move through the world on their hind legs, leaving the forelimbs free to use tools, care for children, etc. It is a strange and counterintuitive proposition to tell a bipedal brain that it must forget its evolutionary programming and move like a quadruped. That is the fundamental difficulty that all beginners have. Even though bipedal locomotion has conditioned them to shift their center of gravity from one foot to the next as they move through terrain, the presence of handholds—the proposition of quadrupedal locomotion—short-circuits their brains. They consistently fail to transfer their center of gravity from one foot to the next when they are holding something in their hands. That is why beginners get pumped when they climb 5.5. They are not necessarily weak, but their upper bodies must exert enormous energy to execute a skill that is normally reserved for their legs.

Unfortunately, knowing and understanding this predicament, even carefully explaining it to a student, doesn't make the learning any less difficult. But, if the predicament is carefully explained to the student, the subsequent coaching will be more precise, more focused on the real problem. Instead of shouting useless and ambiguous feedback to a student, "Trust your feet! Trust your feet! Just stand up!" an instructor can be more precise, "Shift your center of gravity from your low step to your high step!"

Often experienced climbers do not understand how perfectly unconscious their understanding of this fundamental problem is. Their bipedal brains have fully adjusted to quadrupedal locomotion. Climbing instructors need to help their students catch up.

Terrain-Specific Movement

Most likely there will be moves that are specific to the terrain, and instructors should concentrate their coaching on those specific skills. It will be useless to tell students about nuanced and esoteric concepts like flagging or heel hooking if the terrain they are climbing is low angled. There is no need to teach crack climbing if there are no cracks, and so on. Try to find the three or four techniques that are consistent in the course area and teach those skills. On a low-angled climb, for example, students will need to know how to smear. But backstepping and edging are probably extraneous pieces of information. Students will need to focus attention on dynamic weight transfers from a low step to a high step, but they will not need to toe hook or do foot switches. Students will need to mantle, but they will never need to dyno. Be specific; find the movement patterns at the crag and teach those skills.

CHAPTER 5

Baseline Equipment

An office worker can't do anything without a functional computer. A carpenter can't build a house without a hammer. A taxi driver is useless without a working taxi. And a climbing instructor is not a climbing instructor without certain essential tools. An instructor's baseline equipment is composed of the instruments crucial to a successful day of climbing instruction.

Following is a breakdown of the essential baseline equipment required by a professional climbing instructor.

Harness

The modern climbing harness is not only more comfortable than the swami belts of climbing's golden era, but they also are manufactured and sold with incredible variety. A climbing instructor selects two types of harnesses—the instructor harness and the participant harness—from a wide array of options for two essential purposes. In the course of a climbing outing, an instructor will need to use the harness to rack lead protection, carry an array of assistance and anchoring tools, tie into a rope (or two ropes) while also using the belay loop, haul a rope, rappel on one device and transfer to another, and so on. A participant, on the other hand, may never need to carry an extraordinary amount of equipment, may never do any sort of technical multitasking, and may only actually sit in the harness while being lowered. As a result of these two fundamentally different harness applications, a climbing instructor should deploy two different sets of criteria when selecting the best harness for the job. In both cases a harness with a waist belt, leg loops, and a belay loop will be the most comfortable and useful.

When selecting an instructor harness, look for a model that has

- a separate space for belaying/clipping to the harness (belay loop) and tying-in (the hard points of the harness)

Swami Days

I (BG) began climbing before the advent of the modern climbing harness. Instead of a harness, I used a swami belt. I took a 20-foot length of 2-inch-wide nylon webbing (rated at 8,000 lbs.), wrapped it a bunch of times around my waist, and tied it with a water knot. Then I tied my climbing rope around the swami belt with a figure eight follow-through. This setup discouraged **hangdogging** and was rib jarring in a leader fall! Soon we figured out how to add leg loops, which made the rig more comfortable, to say the least!

- gear loops to hold all tools and a rack
- adjustable leg loops (if you'll be climbing in different seasons, with different amounts of clothing)
- comfortable for all-day use

For a participant harness, look for a model that has

- durability to sustain repeated novice use
- simple functionality to expedite instruction and supervision
- adjustability to fit a large of number of body types and sizes

Modern, lightweight climbing harness.



Modern speed buckle.

Top brands include Arc'teryx, Black Diamond, Petzl, Metolius, Trango, Mammut, Misty Mountain, and Camp USA.

Some newer models have webbing with "speed buckles" that are pre-threaded and already doubled back. Other harnesses have the old-school "double pass" buckle, where the webbing belt must be doubled back through the buckle. The instructor should be able to demonstrate how to properly buckle and use each student's harness.

For students, fully adjustable models are convenient and efficient, especially for outfitting groups. Black Diamond, for example, offers a fully adjustable model with speed buckles for sizes extra small through medium, and another model for large to extra large.

Harnesses should be retired when the belay loop becomes frayed or shows signs of wear. For recreational climbers, Petzl recommends using nylon products no longer than seven years, even with minimal use. In an institutional setting, harnesses are retired sooner than that.



Traditional, doubled-back buckle.



Harness with adjustable leg loops.

Helmets

Back in the 1960s and 1970s, very few climbers (probably less than 10 percent) wore helmets. Today it's the opposite. Most climbers wear helmets, particularly in trad climbing areas. The professional standard is for all guides and instructors to wear a helmet and to enforce a helmet policy for their students.

Even in the seemingly benign single pitch environment, rockfall can be a real hazard, especially if there is loose rock at the top of the cliff. Rockfall can occur naturally (from wind or melting snow or ice) but more commonly is caused by other climbers. The most common scenarios are a climber pulling off a handhold or breaking off a foothold while climbing, inadvertently kicking off a rock from the top of the cliff, or causing a rockfall by manipulation of the rope. Be especially aware when other climbers are at the top, rigging anchors and setting ropes, as rocks are easily dislodged by ropes being pulled around. When teaching groups, establish a mandatory helmet zone at the base of the cliff, and then watch for students who are lounging at the base without a helmet.

Students should be taught that while on the cliff or at the top of the cliff, if a rock (or any object) is dislodged, the universal signal is "ROCK!" How loud the signal is yelled can signify the size of the rock. If the warning comes from 100 feet or more away, students can be taught to look up, judge

Helmets help manage risk in the single pitch environment.

the trajectory, and move aside accordingly. If the signal comes from just above, students should be instructed to hunker down and not look up, so as not to get hit in the face. Obviously, wearing a helmet is most important when climbing, belaying from the base of the climb, and hanging out at the bottom of the cliff.

Be particularly alert for rockfall when rappelling, as it can be caused by the rope coming into contact with the cliff, particularly if the climber swings from side to side and especially if there is loose rock on the cliff.

Top brands of climbing helmets include Petzl, Black Diamond, Mammut, and Camp USA.

Ropes

History

Mountaineering's first golden age ended abruptly on July 14, 1865. For Edward Whymper, who led a team of seven climbers up the first ascent of Switzerland's Matterhorn—at the time the last great unclimbed peak in the Alps—both triumph and tragedy were his fate on that great and dreadful summer's day. After reaching the summit the climbers, all tied together with manila ropes, began a tedious descent. One of the party suddenly slipped, pulling several of the others off. While Whymper held fast, clinging to a rock outcrop to avoid being yanked into the abyss, the rope broke, sending four climbers to their death. Later buried in the Zermatt cemetery, the Matterhorn soars above them as their tombstone for all time. Some speculated that the rope had been cut with a knife, but a formal investigation and inspection of the rope revealed the cord had simply parted—broken under the strain.

Through the late nineteenth and early twentieth century, climbing and rappelling ropes were made from natural fibers like hemp, manila, and sisal. While strong enough for many applications, these ropes were ill-suited to the rigors of climbing and rappelling, and subject to mildew and rot.

Nylon, also known by the generic name polyamide, was developed by the Dupont company in 1935. Modern nylon climbing and rappelling ropes that could actually hold up to the forces generated from leader falls were first manufactured in the 1940s, coinciding with the availability of high-quality "nylon 6," allowing the construction of lighter weight ropes that could stretch to absorb great forces and hold more than 2 tons. Nylon is still by far the best material for rock climbing and mountaineering ropes, due to its ability to stretch and absorb the forces created in a fall, making it superior to any other yarns currently available for this application.

Polyester, patented in 1941, has less stretch than nylon and is today widely used in the manufacture of low-stretch ropes used in rescue, fixed lines, rope systems, and rappelling, where dynamic properties are not required.

Early nylon climbing ropes were a three-strand, woven rope with the brand name Goldline. The three-strand twisted construction (called laid construction) consisted of three strands of twisted filaments spiraled into one singular rope. These ropes stretched considerably under body weight, and if you were rappelling or prusiking without contact to the rock, the spiral construction would result in a dizzying spin on your way down.

Kernmantle Ropes

The big step up in rope technology came in 1953 with the advent of the first kernmantle rope, made in Europe. The kernmantle design consists of an outer, tightly woven sheath (mantle) over a core of twisted, parallel fibers (kern). The core of the rope provides most of the rope's strength, and the sheath protects the core from abrasion and damage and reduces friction as the rope runs through carabiners and rappel devices. The kernmantle rope handles better and is more durable than a rope with laid construction.

During the 1950s and into the golden age of big wall climbing in Yosemite during the 1960s,



Deconstructed kernmantle rope showing the braided white interior core under the more tightly woven sheath.

MAXIM
MAXIM
10.1

Selection of dynamic ropes from Nomad Ventures climbing shop, Idyllwild, California.

Dynamic Rope Types

Dynamic ropes are sold in single, double, and twin configurations.

A **single rope** (marked on the label with a 1 inside a circle) is the most commonly used rope for rock climbing and rappelling and is used as a single strand.

A **half rope** (marked on the label with a ½ inside a circle) is used primarily for alpine rock climbing and mountaineering and consists of a pair of ropes both tied in to the leader, who alternates clipping one strand at a time into protection. This configuration reduces rope drag through protection and provides two full-length ropes to facilitate a rappel descent.

A **twin rope** (marked with two overlapping circles) is used primarily in alpine climbing and should only be used with the two strands together; each climber ties into both strands and both strands are clipped into points of protection. The big advantage is that it allows for retrievable rappels the length of the rope, and it is lighter than a half rope. A single strand of a twin should never be used alone for any purpose.

Goldline ropes were still the standard, as they were about a third of the price of kernmantle ropes. Once they became more widely manufactured and distributed, with a correspondingly better price, kernmantle ropes became the standard climbing rope worldwide by the late 1960s and early 1970s.

Today the kernmantle rope is the standard design used in climbing, rappelling, caving, canyoneering, vertical rope access, fixed lines, rescue, and life safety ropes. These ropes are made from nylon, polyester, or a combination of these and other synthetic yarns. There are three basic types of kernmantle ropes: dynamic, low-stretch, and static. A dynamic rope is required for situations where a high-impact force can be generated—such as in a leader fall—and therefore is the standard rope for rock climbing, ice climbing, and mountaineering, where the rope will be used for belayed climbing and rappelling. A dynamic rope will typically stretch about 26 to 36 percent during a leader fall (dynamic elongation) and around 7 to 11 percent under body weight (static elongation).

UIAA and CE Certification for Dynamic Ropes

Dynamic ropes sold for rappelling, climbing, and mountaineering are tested and certified to UIAA (Union Internationale des Associations d'Alpinisme) and CE (Conformité Européenne) standards and should bear the UIAA or CE certification on the label. This means that the rope has been tested and certified by a "third party" at one of three UIAA-approved testing facilities to meet the European Norm (EN) 892 and UIAA-101 standard for dynamic rope. To receive this certification, the rope sample must survive at least five UIAA drop tests. This test is done by taking an 80 kg (176 lb.) weight, attaching it to one end of a 9-foot length of rope, then raising it 8½ feet above the anchor and dropping it 15 feet over a 10mm diameter bar (similar to a carabiner) that is anchored approximately 1 foot above where the rope end is anchored. This simulates a fall factor of 1.7 (total distance of the fall divided by the length of rope in the system), which is a very severe fall in climbing situations.

For a single rope, during the first drop, the peak impact force on the rope is measured and must be less than or equal to 12 kN (8 kN for a half rope with a weight of 55 kg) with a corresponding stretch of less than or equal to 40 percent. Twin ropes have the same requirements as a single rope but must survive at least twelve drops without breakage. In addition to the stringent drop test requirements, sheath slippage can be no more than 1 percent, and static elongation under an 80 kg (176 lb.) load can be no more than 10 percent for a single rope and no more than 12 percent for a half or twin rope.

To the best of our knowledge, the only documented rope failures among UIAA-certified ropes were ropes that were cut over sharp edges and one rope with known pre-exposure to sulfuric acid.

Static and Low-Stretch Ropes

For many years the term *static rope* was used to define any low-stretch rope typically used as a rescue rope or as a fixed line for rope access, rappelling, and life safety. As rope manufacturers developed new techniques and technologies to create better low-stretch ropes, the terms *static rope, low-stretch rope, low-elongation rope,* and *semi-static*

STERLING
ROPE

Climbing shops sell static and low-stretch ropes from spools, cut to the length you desire.

rope, often used interchangeably, became somewhat ambiguous, especially since all ropes have some stretch, so a more precise definition was needed.

The Cordage Institute, an international rope industry association that disseminates industry standards, defines two categories of non-dynamic ropes: static and low-stretch.

STATIC ROPES

Static is defined as rope with a maximum elongation of less than 6 percent at 10 percent of the rope's minimum breaking strength (MBS). New technology allows manufacturers to create static ropes with virtually no stretch—think of them almost like a wire cable. For example, the Sterling Rope company's ½-inch diameter HTP Static rope stretches only 0.8 percent with a 300-pound load and has a safe working load (SWL) of 908 pounds, which is ⅒ of its MBS of 9,081 pounds.

These ropes should not be used for toprope belaying, but can be used for anchor rigging and fixed lines, although low-stretch is also preferable for those applications since even a slight amount of stretch means a lower impact force on the anchors.

Static ropes generally have poor handling characteristics due to their stiffness and are typically used only for haul lines, high lines, zip lines, and rappelling, where dynamic properties are not required. A static rope should never be used for lead climbing or for belaying, where it may be subject to a high-impact force.

LOW-STRETCH ROPES

The Cordage Institute defines low-stretch as a rope with an elongation between 6 and 10 percent at 10 percent of the rope's MBS. Since a low-stretch rope has relatively little stretch (usually 3 to 4 percent under body weight) compared to a dynamic rope, it is a great choice if you're using it just for toproping and rappelling, but it should not be used for leading. Low-stretch ropes may also be a good choice for rigging anchor extensions and fixed lines because they are easy to tie knots with, and they reduce potential impact forces when used as a tether or belay.

Dynamic versus Low-Stretch

When buying ropes, the following criteria will help the instructor assess which rope is best for a particular application.

A dynamic rope is required for situations where you'll be using the rope for leading or belaying, where any impact force is anticipated. A low-stretch rope should not be used for lead climbing, because rope stretch is the key to absorbing the energy generated in a leader fall.

For a program involving just toproping, using a low-stretch rope makes a lot of sense, since dynamic rope stretch is often a hazard, or at least a nuisance, in a toprope situation. Picture a 100-foot-high cliff set up as a toprope. At the start of the climb, you'll have 200 feet of rope in the system. Let's say you're belaying a climber using a dynamic rope, with a bit of slack, and the climber falls 15 feet up the route. Let's assume the rope has a static elongation of 9 percent. Do the math: 185 feet times 9 percent equals 16.7 feet. Chances are your climber will find herself on a 16.7-foot bungee cord that eventually returns her to the ground (the thing she is most worried about impacting).

Diameter and Sheath Percentage

Ropes sold for climbing and rappelling commonly range from 9 to 11mm; 10mm is a very popular diameter among climbing instructors, as it's durable yet light and supple. Recently there has been a trend toward ever-thinner ropes. Ropes as thin as 9.4mm in diameter are UIAA rated for lead climbing. But these thinner ropes are generally stretchier and will wear out far more quickly. For toproping, selecting a rope that is thinner than 10mm in diameter often results in having to purchase new ropes more frequently.

Low-Stretch Ropes

In my (BG) climbing school program, we've used low-stretch ropes for our toproping classes for more than twenty-five years. These low-stretch ropes stretch about 3 to 4 percent under body weight, slightly more in a toprope fall with a bit of slack. From a risk management standpoint, it just makes sense to use a low-stretch rope for toprope situations, especially if you're setting up relatively long routes (up to 100 feet high). I look for a rope with either a CE EN 1891 Type A certification or a National Fire Protection Agency (NFPA) light use certification, with a diameter of between 10 and 10.5mm, to be compatible with various belaying and rappelling devices. I also check the rope's suppleness to ensure the rope will hold knots firmly and handle well. Sterling makes an excellent low-stretch polyamide (nylon) rope called the Safety Pro. I prefer the 10.5mm diameter for good handling and durability for toproping and rappelling.

If using a dynamic rope for toprope belaying, beware of the dangers of rope stretch, and keep the rope taut in situations where the climber is just off the ground or just above a ledge.

Thinner ropes generally stretch more and cut more easily over sharp edges. A thicker diameter rope also affords more friction when used with rappelling devices.

Many manufacturers now provide information on the sheath's percentage of the total weight. A rope with a higher percentage of sheath (40 percent or more) will generally be more durable for rappelling use than one with a lower sheath percentage.

Sharp Edge Resistance

The UIAA has developed a new, optional test for manufacturers to receive a "sharp edge resistant" certification. The test is very similar to the UIAA drop test, although instead of dropping the rope over a rounded bar simulating a carabiner, a sharp edge is used. This is a pass or fail test, and although not a true indicator of durability, it's a good measure of the rope's ability to resist slicing over sharp rock edges. As mentioned earlier, some of the only documented cases of modern climbing ropes breaking in the field have been when the rope was cut over a sharp edge.

Static Elongation

This is a measure of how much the rope stretches under a weight of 80 kg (176 lbs.), telling you how much your rope will stretch during a normal rappel or when someone hangs on the rope. For toproping, rappelling, and fixed rope applications, some instructors prefer a low-stretch rope with a static elongation of around 3 to 4 percent. Most dynamic climbing ropes have a static elongation of about 8 or 9 percent.

Dry or Non-Dry

Nylon, when it gets wet, absorbs water, which weakens the fibers. Nylon ropes can lose much of their strength when wet (at least 30 percent; some studies show over 50 percent loss of strength), so manufacturers sell ropes with a "dry coating" to keep the rope from absorbing water and make it more abrasion resistant. If using a dynamic nylon rope in snow, ice, or wet conditions, a rope with a dry coating is recommended.

Marking the Middle of Your Rope

Many climbers use a black felt tip marking pen to mark the midpoint of their rope. In 2002 the UIAA Safety Commission issued a warning based on testing done by the UIAA and by some rope manufacturers that showed the ink from some marking pens decreased the strength (more specifically, the rope's ability to hold repeated falls in accordance with the EN 892 testing standard) by as much as 50 percent. While this may seem to be a shocking figure, the UIAA president pointed out that "such a marked rope can only break in practice when the 2 or 3 centimeters, which are marked, are placed over a sharp rock edge when the rope is loaded by a fall." While this is a very remote possibility, an instructor should consider other alternatives to identify the midpoint on a rope, or at least use only marking pens sold or recommended by the manufacturer of your rope. Tape is not a good option, as it can slide on the rope or, more likely, become gummy and stick in rappel and belay devices. A good option is to use a "bipattern" rope, which is a rope that changes pattern at the middle without a change in yarns or color. Another option is a "bicolor" rope, which has a color change at the midpoint of the rope. The rope manufacturer changes yarns and joins the yarns together with what is known as an "air splice" (forcing the ends to entwine around each other using extremely high air pressure). The process creates a cosmetic blemish at the yarn change, which the manufacturers say is actually stronger than continuous fibers because of the extra fibers at the splice. Without a middle mark on your rope, to find the middle simply start with both ends and flake the rope out until you reach the middle.

For pure rock climbing in dry conditions, it might not be worth the added cost, as dry ropes are generally more expensive and the coating wears off with repeated toproping.

Rope Length

In the 1970s the standard length for a dynamic climbing rope was 50 meters (165 feet). Today the standard is 60 meters (200 feet), and many climbers use 70-meter ropes (230 feet). These are the standard pre-cut lengths you can buy from a climbing shop. Static and low-stretch ropes are commonly sold in pre-cut lengths and are also sold directly from spools, cut to your desired length. Climbing instructors should select a length that is appropriate for the climbs they intend to instruct, choosing a length that will allow them to work at both the bottom (where the rope will need to be twice as long as the climb is tall) and the top of a given climb. It seems particularly wasteful to carry 70 meters of rope if the average climb in a given area is only 50 feet tall.

Rope Care and Use

Many instructors have access to climbing equipment, including ropes, through pro-purchase programs. Top brands include Sterling, Maxim, Bluewater, Mammut, Edelrid, Edelweiss, Petzl, Millet, and Metolius.

Avoid setting up a climb or rappel where a rope might abrade or cut over an edge. This can severely weaken or ruin your sheath in just one outing! Avoid standing or stepping on the rope, as this can grind sharp pebbles and grit through the sheath and into the core. Minimize the rope's exposure to UV light, as this will weaken the fibers over time. Store ropes in a shaded, dry place.

A dirty rope can be washed in a tub by hand or in a washing machine (preferably a front-loading washing machine, because a top-loading machine's agitator will abrade the rope) with hot water and a soap suitable for nylon. It's not a bad idea to run the machine once with nothing in it before washing the rope to make sure that there is no residual bleach inside. If washing a rope in a bathtub, make sure the tub is free from any chemicals that may damage the rope. It's best to daisy chain the full length of the rope before washing it in a machine to keep it from getting tangled. Let the rope dry by hanging it in a shaded area.

Be vigilant and protect all rope from coming into contact with any chemicals that contain acids, bleaching or oxidizing agents, and alkalines. Acid is the arch enemy of nylon and can severely weaken nylon and polyester fibers. Be extremely cautious to avoid exposing your rope to battery acid or any type of acid that may be encountered in your garage or the trunk of your car. It is wise to store your rope in a rope bag.

It is not a good idea to use a rope without knowing its history. Keep track of its history and age. Most manufacturers recommend keeping a rope for no longer than five to seven years even with minimal use, and no longer than ten years even if the rope has been stored and never used. In an institutional setting, ropes are usually retired well before the manufacturer's recommendation.

Inspect a rope by running your hand over the entire length of the sheath when coiling and uncoiling the rope. Visually inspect for excessively worn areas on the sheath, and feel for irregularities (voids, flat spots, etc.) in the core. The rope should be retired (or cut to a shorter length) if the sheath is excessively worn or frayed, exposing the core, or if there are any anomalies in the core. Multiple fast rappels can burn the sheath of a rope, a result of heat generated by the friction between the rope and rappel device. If the sheath feels glazed or melted, the rope should be retired.

Coiling and Uncoiling Your Rope

With a new rope, take extra care the first time it is uncoiled to prevent kinking. The best method is to simply unroll the rope from the coil, as if pulling it off a spool, holding the rope and rotating the coil until the entire rope is stacked on the ground, keeping the rope free from any twists. Once the rope is in a loose pile, inspect the rope by running it foot by foot through your hands from one end to the other, then coil it with the butterfly coil method.

BACKPACKER OR BUTTERFLY COIL

The backpacker, or butterfly, coiling method puts fewer kinks in your rope. It is also the fastest way to coil a rope, since you start with both ends or from the middle and coil a doubled rope. When coiling from the ends, a good idea is measuring two and a half arm lengths (both arms extended), then begin the butterfly.

MOUNTAINEER'S COIL

Another standard coiling method is called the mountaineer's coil. This is a traditional method that makes for a classic, round coil that can be easily carried over the shoulder or strapped onto the top of a pack.

Backpacker or Butterfly Coil


1


2


5


6


7

3



4



8



9



10



The Mountaineer's Coil











Knife

Many instructors carry a knife, but it's important to be very careful with when and how it is used. A rope under tension cuts more easily than one not under tension.

Slings and Webbing

In the 1960s and 1970s, 1-inch-wide tubular nylon webbing was the standard sling material, tied into a loop with a water knot or double fisherman's knot. Eventually, sewn slings with bartacked stitching came onto the market and were actually stronger than the same material tied with a knot. Sewn slings are not only stronger but also more secure in that there is no need to worry about the knot loosening and coming untied.

Flat Webbing

Flat webbing is woven solid, as opposed to tubular webbing, which is woven into a hose-like shape. It is stiffer and more abrasion resistant than softer tubular webbing, with a higher tensile breaking strength (Sterling 1-inch flat webbing is rated at 43.5 kN or 9,800 lbs.), which makes it useful for high-strength applications. Its stiffness, however, makes it more difficult to knot and gives it poor handling characteristics, making it unpopular with climbers.

Tubular Webbing

There are two types of tubular nylon webbing: mil-spec and climb-spec.

Since webbing was originally manufactured for military applications, mil-spec means that the webbing meets the standards demanded by the military. Mil-spec has a coarser, rougher-textured weave, with a more pronounced ribbing across the width of the webbing. Climb-spec is a finer, more high-quality weave, without the noticeable ribbing and with a more tightly woven edge. Climb-spec usually tests slightly stronger than mil-spec webbing and is generally more abrasion resistant and more impervious to tearing or slicing over a sharp edge, but both are suitable for climbing applications and both are roughly the same price.

The Bluewater company, known for manufacturing high-quality webbing, says its climb-spec tubular nylon webbing "outperforms normal Mil-spec webbing in strength, flexibility, knotability, and durability. There is minimum exposure to individual fibers as a result of high thread count and fine weave pattern." Bluewater's 1-inch climb-spec

What Kind of Knife Is Best?

In thirty years of climbing, I (BG) have never had to cut anything out of a rappel device. I have used a knife to cut off old nylon webbing and cord from rappel anchors, to replace it with new material. In fact, if I'm doing a climb that requires a rappel using a natural anchor such as a tree or block of rock, I'll make sure I have a small knife and extra webbing. I prefer a stainless steel knife with a serrated blade that easily cuts both rope and webbing. Petzl makes several models specifically for climbing, with a folding design that has a round hole on one end to clip into a carabiner. The small and lightweight Trango Pirana has a unique design that can't open up on you when it's folded closed and clipped into a regular-size carabiner.



Top: Bluewater 1-inch climb-spec nylon webbing, rated at 18 kN tensile strength (4,047 lbs.).
Bottom: REI 1-inch mil-spec nylon webbing, rated at 17.8 kN tensile strength (4,002 lbs.).

webbing has been tested to over 6,000 pounds loop strength when tied with a water knot.

The Sterling Rope Company's version of climb-spec webbing is called Tech Tape, with a "smoother, denser weave and higher tensile strength" than their mil-spec webbing and a 4,300-pound tensile strength. Sterling's mil-spec webbing is rated to a minimum breaking strength of 4,000 pounds tensile strength and 6,129 pounds in a bartacked sewn loop.

Pre-sewn nylon slings are typically sold in $^{11}\!/_{16}$-inch (18mm) width, bartacked into 24-inch or 48-inch loops with a rating of 22 kN (4,946 lbs.) loop strength.

Climbing shops sell both mil-spec and climb-spec 1-inch tubular nylon webbing from spools, cut to any length desired. Be aware that these spools of webbing contain taped splices where the webbing ends have been joined together with masking tape.



Nylon Webbing Comparison. Top to bottom: 1-inch tubular nylon webbing tied with water knot (Sterling Tech Tape, rated at 4,300 lbs. tensile strength); 18mm Metolius Nylon Sling, rated at 22 kN loop strength (4,946 lbs.); 18mm Black Diamond Runner, rated at 22 kN loop strength; 11⁄16-inch Sterling tubular webbing tied with a water knot (rated at 3,000 lbs. tensile strength).

Tape Won't Hold Body Weight

It seems impossible for it to happen, but I (BG) know of two cases where spliced webbing was sold to customers who then used it with only the masking tape joining the webbing together, in one case with devastating results.

One advantage of cut to length nylon webbing is that it can be untied and re-tied around a tree, through a tunnel, or threaded through bolt hangers for a rappel anchor.

The Bluewater company recommends the maximum lifespan of its nylon webbing to be no more than five years, and also recommends retiring a nylon sling if it has been subjected to temperatures above 176 degrees Fahrenheit, is scorched or glazed from a rope being pulled across it, shows signs of UV degradation from being left out in the elements (faded color and/or stiffness), or if it has been exposed to acid or bleach. Like a nylon rope, nylon webbing can lose an appreciable amount of strength when wet or frozen.

Spectra and Dyneema Slings

Spectra slings, introduced in the late 1980s, were lighter, less bulky, and stronger than nylon. Dyneema is a more recent innovation, typically sold in various-length loops sewn with bartacked stitching in 10mm width. Dyneema and Spectra both have almost the identical chemical makeup of high-molecular-weight polyethylene, which, pound for pound, is stronger than wire cable. Most experts say that the manufacturer of Dyneema consistently produces more high-quality fibers than the manufacturer of Spectra material, and most of the climbing and rappelling slings on the market today are made from Dyneema.

Both Spectra and Dyneema slings are constructed from parallel fibers—very strong but with

Tensile Strength vs. Loop Strength

Strength ratings are often given as *tensile strength* and *loop strength*. Tensile strength is tested by a straight pull on a single strand of the material with no knots, done by wrapping the material around a smooth bar (4-inch diameter gives the most accurate test) on both ends and pulling until it breaks. Loop strength is the material tested in a loop configuration, either tied with a knot (in the case of webbing, usually the water knot) or sewn with bartacked stitching. In general, webbing loop strength when tied with a water knot is about 80 percent of twice the tensile breaking strength, and bartacked sewn webbing loop strength is generally about 15 percent stronger than the same material tied with a water knot, depending upon the quality and number of bartacks.



Dyneema Sling Comparison. Top to bottom: 1-inch tubular nylon webbing (for comparison); Wild Country 10mm Dyneema sling (22 kN or 4,946 lbs.); Black Diamond 10mm Dynex Runner (22 kN); Mammut 8mm Dyneema Contact Sling (22 kN).

high lubricity, which means the material itself is inherently slick. That is the reason it can only be purchased in sewn loops—it does not hold knots well. *Do not cut a Spectra or Dyneema sling and re-tie it with a water knot!*

Both Spectra and Dyneema have a lower melting point than nylon (around 300 degrees Fahrenheit for Dyneema/Spectra compared to nylon's melting point of around 480 degrees). The lower melting point, along with the inherent slipperiness, make Spectra and Dyneema slings a poor choice for tying friction hitches like the prusik, klemheist, or autoblock, compared to 5mm or 6mm diameter nylon cord.

In a pinch, if required to use a sling to tie a

Girth-hitching two Dyneema slings together can decrease their strength by 50 percent, but for most climbing situations, this is not a concern since the loop strength is 5,000 pounds to begin with.

friction hitch, use a nylon one over a Dyneema or Spectra sling, as nylon will grip better. The newer, thinner (10mm width) Dyneema slings will work for friction hitches, and they do possess some nylon in their construction, but if they start to slide on a rope when under load, the friction will generate heat, which could potentially weaken the sling.

Both Spectra and Dyneema fibers do not retain dye and cannot be colored, so the fiber is distinctive in that it is always white. Manufacturers add a blend of nylon to Spectra and Dyneema, usually in a distinctive border pattern, and it is likely that in the future there will be more nylon in the mix. The Metolius company recently came out with 13mm width slings that are a blend of 36 percent Dyneema and 64 percent nylon.

When using Spectra or Dyneema slings, think of them like a wire cable—they have no stretch, even with nylon blended into the weave. Avoid tying knots with them—it can be almost impossible to untie a simple overhand knot in the newer, thinner Dyneema after it has been seriously weighted. Wild Country warns that the material loses a hefty percentage of its strength (around 50 percent) when tied in a simple overhand knot or girth-hitch—a property that nylon does not possess. The best way to use a Spectra or Dyneema sling is clipped to carabiners. If using them in a sling-to-sling configuration, either basket one sling over another, or use a properly tied girth-hitch.

When buying slings for rappelling, 1-inch or $^{11}/_{16}$-inch width tubular nylon webbing will be the most versatile material for rigging rappel anchors, as it can be cut to a desired length and tied with a water knot. Double-length (48-inch) sewn nylon slings are also handy for tethering into anchors and extending a rappel device away from the harness. The UIAA states that sewn slings should have a minimum load-bearing capacity of 18kN.

Recent studies show that dirty slings are weaker than clean ones. The Mammut company suggests that "to maintain the quality and safety of your slings, you need to clean them regularly." Mammut recommends to "clean soiled slings in hand-hot water with a small amount of mild detergent or in a delicates machine cycle up to 30 degrees centigrade (86 degrees Fahrenheit). Rinse in clear water. Leave to dry in shade."

Cords and Cordelettes

A good all-purpose cordelette is 7mm diameter nylon cord, about an 18- to 20-foot length tied into a giant loop with a double fisherman's knot or a double overhand flat bend.

Cordelettes made with a Spectra or Dyneema core and nylon sheath have incredibly high strength and low stretch. Pound for pound, Spectra and Dyneema are stronger than steel (and is the material used in body armor for the military), but both Spectra and Dyneema lose an appreciable amount of strength when tied with knots. Because these cords are so light and strong, with less bulk to carry, they have become popular, especially for rock climbing. The Bluewater company markets the 5.5mm diameter Titan Cord, with a Dyneema core and nylon sheath, rated at 13.7 kN (3,080 lbs.). They say its "combination of high strength, low elongation and light weight provides superior characteristics over other combinations. Dyneema does not lose significant strength with repetitive flexing and offers a huge increase in abrasion and cut resistance over other materials. Bluewater Titan Cord can be cut and sealed with a hot knife. We recommend a triple fisherman's knot for tying 5.5 Titan into loops."

Ideal Cordelette

I (BG) prefer a length that allows me to double the cordelette within the span of my outstretched arms. My favorite brand is Sterling, whose 7mm diameter nylon cord is rated at 12.4 kN (2,788 lbs.) and tests over 5,000 pounds when tied into a loop with a double fisherman's knot.

In recent years high-tech cords utilizing aramid fibers (namely Technora) for the core, with a nylon sheath, have become popular. Aramid fiber has extraordinary tensile strength (stronger than Spectra or Dyneema) with low stretch and an extremely high melting point (900 degrees Fahrenheit), making it difficult to cut and melt. The best way to cut it is with wire cable cutters. Then milk the nylon sheath over the end and seal it by melting the nylon with a lighter. The Sterling 6mm Powercord has a Technora core and nylon sheath, with a single strand breaking strength of around 19 kN (4,271 lbs.); and the 5mm Tech Cord, sold by Maxim/New England Ropes, with a 100 percent Technora core and polyester sheath, rates at a whopping 5,000 pounds tensile strength.

However, at the 2000 International Technical Rescue Symposium, Tom Moyer presented a paper titled "Comparative Testing of High Strength Cord" that revealed some startling deficiencies in Technora and other high-tech cords. Testing showed that with repeated flexing, aramid fibers break down much more quickly (losing strength) than good old-fashioned nylon. In his study a flex cycle test was performed on various cordelettes. The cord sample was passed through a hole in a steel fixture, flexed 90 degrees over an edge, and loaded with a 40-pound weight. The steel fixture was rotated back and forth 180 degrees for 1,000 bending cycles, then the cord's tensile strength was tested (single strand pull test) at the section that had been flexed. The Technora sample showed a remarkable loss of nearly 60 percent of its strength, while Sterling 7mm nylon cord and 1-inch tubular nylon webbing showed no strength loss at all. Bluewater Titan Cord (Spectra core/nylon sheath) showed a few hundred pounds of strength loss, but was nowhere near the drastic loss of Technora. Further research is warranted. The big advantage of these high-tech cords is their low weight, high strength, and low bulk, which is advantageous for situations like multi-pitch rock climbing and canyoneering.



Cord Comparison. Top to bottom: Bluewater 5mm Titan Cord tied with triple fisherman's knot (Dyneema core/nylon sheath, tensile strength 13.7 kN or 3,080 lbs.); Sterling 6mm Powercord tied with triple fisherman's knot (Technora core/nylon sheath, tensile strength 19 kN or 4,271 lbs.); Sterling 7mm Nylon Cordelette tied with double fisherman's knot (nylon core/nylon sheath, tensile strength 12.4 kN or 2,788 lbs.).

If using these high-tech cords, be sure to tie the cordelette with a triple fisherman's knot, and consider replacing them more often with high use. Keep in mind that the price tag on the high-tech cords is roughly twice as much as nylon. The bottom line is this: For an all-purpose cordelette, it is hard to beat old-school nylon—a 7mm diameter nylon cord is a good choice because it is thick enough to be used in a single loop application, like a personal tether. Narrower 5mm and 6mm cord are great to tie friction hitches like the prusik, klemheist, and autoblock, but these smaller-diameter nylon cords don't provide enough tensile strength to be used as a critical link. When buying this accessory cord to be used primarily for friction hitches, buy the softest, most pliable cord that you can find; a stiff cord won't grip as well. Also, be aware of the difference between 5mm nylon accessory cord (typically rated at 5.2 kN or 1,169 lbs.) and 5mm high-tenacity cord (like Bluewater Titan Cord rated at 13.7 kN (3,080 lbs.) As mentioned, 5mm nylon is less useful as a cordelette, while a 5mm high-tenacity cord offers a much greater tensile strength for anchor building and critical link applications.

Carabiners

Carabiners are used primarily to attach various links (like slings and rope) together in the anchor or belay chain. Locking carabiners are used in critical applications and in conjunction with belay and rappel devices. Carabiners come in a variety of shapes: oval, D-shaped, and pear-shaped.

The basic design is of aluminum alloy, with a spring-loaded gate on one side. The spine of the carabiner is the solid bar stock opposite the gate. The small protrusion on one end of the gate is called the nose, and this will tell you which way



Carabiners come in a dazzling array of designs for various applications. Top row (left to right): asymmetrical D, regular D, oval, wiregate D, bentgate D. Bottom: pear-shaped locking. The most useful carabiners for toproping are ovals, Ds, and pear-shaped locking. Bentgate carabiners are used primarily for sport climbing (on the rope-clipping end of a quickdraw).

the gate opens by visual observation. The basic design has a small pin on the gate that latches into a groove on the nose end. The preferable "keylock" design eliminates the pin, and the gate and bar come together in a machined notch. A wiregate carabiner has a wire under tension serving as the gate, providing a wide opening because of its slim mass and eliminating "gate flutter," which is a vibration of a normal solid gate during a fall or peak loading of the carabiner.

Oval carabiners are useful for racking gear, and for use in sets of two or three for connecting the climbing rope to the toprope anchor master point. Because of their symmetry, the gates can be opposed and reversed, and the carabiner configuration retains its oval shape. Two opposed and reversed ovals can also be used in lieu of one locking carabiner at any critical junction in the anchor system, in situations where there are no additional locking carabiners and extra security at a key point is needed. Three opposite and reversed ovals are the equivalent of two opposite and reversed locking carabiners.

Locking carabiners are used for critical links and applications where it is absolutely imperative that



Wiregate carabiner. Every carabiner you buy should have the UIAA breaking strength rating stamped on the spine.



Two oval carabiners with the gates properly opposed and reversed.



Three ovals opposed and reversed at a toprope anchor master point.

the carabiner gate stays closed, like on a rappel or belay device, at a critical link in the anchor system, or when attaching the belayer's climbing rope to the anchor.

D-shaped carabiners have the strongest configuration, since when the carabiner is loaded on the major (long) axis the weight naturally is loaded closest to the spine. For this reason a locking D is a good choice for a belay/rappel carabiner. A locking pear-shaped carabiner is useful for many applications because of its wide aperture on one side. It's a good carabiner to use with a Munter hitch, and a great carabiner to pair up for use at the toprope anchor master point. When using two opposed and reversed pear-shaped locking carabiners, the symmetry is maintained (unlike an asymmetrical D shape), and the climbing rope runs smoothly through the carabiners.

The most common locking carabiner is the screwgate. The screwgate locking carabiner is just that, a mechanism with a collar that screws shut over the nose of the carabiner. Obviously, with a screwgate locking carabiner, it is important to remember to lock it, and it's an essential habit to always check locking carabiners to make sure they are locked. Check them with a close visual



Two pear-shaped locking carabiners with the gates opposed and reversed on a toprope anchor master point.



Locking carabiners (left to right): Petzl William Triac, Petzl William Ball Lock, Black Diamond Twistlock, Black Diamond Screwgate.

inspection, and also by pressing on the gate (squeeze test) for an additional precaution.

If you're absentminded, or occasionally find yourself not locking a screwgate carabiner, consider buying an autolock or twistlock carabiner. The twistlock design has a spring-loaded gate that locks automatically, and there are several autolocking designs on the market that have a tri-action mechanism that must be manipulated (like pushing the gate upward, then twisting the gate to lock it; or pressing a button, then twisting open the gate), but some climbers find these difficult to use. Interestingly, for industrial workers in the Industrial Rope Access environment (rappelling and rope ascending on the faces of dams, buildings, and bridges), OSHA standards require autolocking carabiners, as does the tree-trimming industry.

The UIAA has determined the following strength ratings for a carabiner to be CE certified.

For oval carabiners:

- Closed gate strength, major (long) axis: 18kN (4,047 lbs.)
- Minor axis (cross-loading) strength, closed gate: 7kN (1,574 lbs.)
- Major axis strength, gate open: 5kN (1,124 lbs.)

For regular D-shaped carabiners:

- Closed gate strength, major (long) axis: 20 kN (4,496 lbs.)
- Minor axis (cross-loading) strength, closed gate: 7kN (1,574 lbs.)
- Major axis strength, gate open: 7kN (1,574 lbs.)

For locking carabiners:

- Closed gate strength, major (long) axis: 20 kN (4,496 lbs.)
- Minor axis (cross-loading) strength, closed gate: 7kN (1,574 lbs.)
- Major axis strength, gate open: 6kN (1,349 lbs.)

An important thing to remember with carabiners is that a carabiner is only about one-third as strong if it's loaded with the gate open. For this reason, keep a few things in mind when using a carabiner:



Carabiners should always be loaded on the major axis.



Bad. Never load a carabiner in three directions as shown here.



Very bad. Never load a carabiner on the minor axis or with a force outward on the gate.

- Always load the carabiner in the proper direction—on the major, or long, axis.
- Do not cross-load a carabiner (on the minor axis) or load it in three directions (called triaxial loading).
- Do not load a carabiner over an edge of rock—this can open the gate when the carabiner is loaded, and two-thirds of the carabiner's strength will be lost.

Ovals

I (BG) have used three ovals for thousands of client days without incident. Simply oppose and reverse the outside carabiners to the middle one. The wide radius created by the three carabiners provides a stable platform for the rope and tends not to flip sideways as often as two locking, which can pin the rope against the rock while lowering if the climber's (weighted) strand is on the outside, away from the rock.



Three steel ovals with the gates opposed and reversed at a toprope anchor.

What's in the Pack?

I (BG) prefer a pack that has accessory straps and buckles so I can strap a rope on the outside of the pack. In addition to my rack, slings, cordelettes, belay devices, helmet, shoes, harness, food, water, headlamp, knife, and extra clothing, I carry two first-aid kits. One is a small ''patch kit'' with small bandages, tape, and a blister kit for minor cuts, scrapes, and blisters. Inside this one I'll also have NSAIDs (aspirin and ibuprofen), acetaminophen, and Benadryl. I also carry a roll of athletic tape. For client care I carry extra sunscreen, lip balm, a trash bag, and a squirrel-proof container for food storage.

My larger first-aid kit is a trauma kit complete with trauma shears, heavy absorbent pads, tape, large bandages, roller gauze, a pocket mask, a couple of Sam splints, and two epi pens.

An instructor's kit should include a communication device (e.g., cell phone, satellite phone, or walkie-talkie), pen and paper (SOAP notes if you're a WFR), and a written emergency response plan with standard operating procedures and appropriate actions for specific scenarios.

Retire a carabiner if it shows a groove from excessive rope wear, or if the gate is no longer in alignment with the body of the carabiner after it has been dropped a considerable distance. If the gate is sticky, washing it with soap and water and using some graphite lubricant will usually take care of the problem.

In the professional realm, the industry standard for attaching the climbing rope to the toprope anchor master point is either two locking carabiners or three oval carabiners with the gates opposed and reversed.

When doing a lot of toproping, aluminum carabiners actually wear rather quickly, developing noticeable grooves. When this happens, they should be retired. Petzl recommends retiring a carabiner with 1mm of wear, about the thickness of a dime. Also, worn-off aluminum particles get on the rope and on the belayer's hands. Using steel ovals solves this problem, as steel is far more durable and wears much more slowly than aluminum.

The Instructor's Pack

A climbing instructor is constantly striving to select the perfect tool for a given task. The instructor's pack is no exception. It should be large enough to hold everything an instructor will need to run an outing and be prepared for emergencies. For most, the best pack is large, about 4,000 to 5,000 cubic inches, and any items that do not fit inside the pack (like a rope or a helmet) are strapped down firmly. A climbing instructor should be able to move through terrain with grace and balance, without swinging or dangling encumbrances, prepared to deal with all contingencies.

CHAPTER 6

Knots and Hitches

What knot should I use here? What hitch should I use there? The answer isn't always obvious. Many knots and hitches accomplish the same thing and work equally well in similar applications. Others do not.

An instructor's job is first to determine which knot or hitch is appropriate for the technical task at hand and, second, to develop strategies for teaching knots and hitches appropriate to a given lesson.

The following pages discuss a wide array of baseline knots and hitches used regularly by Single Pitch Instructors. Certainly there are many more that could be acceptably used in a single pitch setting or taught to students with specific learning objectives, but these represent a fundamental standard of knowledge that every instructor should hold.

Loop Knots

Loop knots are tied by taking two strands of rope (called a bight) and wrapping them back over themselves so that the knot does not slide, or by taking the end of the rope and tying it back over the standing part so the knot does not slide. Loop knots are used to clip the rope into a carabiner, or to tie around an object.

Overhand Loop

This is the simplest knot used to form a loop. It requires less rope to tie than the figure eight. For most applications, however, the figure eight loop is preferable because it tests slightly stronger than the overhand loop and is easier to untie in small-diameter cord.

Knot Terminology

Bend: Two ropes tied together by their ends.

Bight: Two strands of rope where the rope is doubled back on itself.

Load strand: The strand of the rope that bears all the weight.

Hitch: A knot that is tied around another object (such as a carabiner or rope).

Standing end: The part of the rope that the end of the rope crosses to form a knot.

Tag end: The very end of a rope, or the tail end that protrudes from a knot.



Overhand loop.



Finished overhand loop.

Figure Eight Follow-Through

This is the standard knot that climbers use for tying the rope to their harness. It can also be used to tie a rope around an object like a tree or through a tunnel. Climbers have gravitated toward this knot over the years because it is strong, secure, and easy to recognize when tied correctly. Instructors like it because it is easy to teach, and the uniform nature of the knot enables quick inspection and supervision. When tied correctly, the knot is tight, with a 5- to 8-inch tail, and it has bilateral symmetry because the initial figure eight and its follow-through strand are always parallel.



A well-dressed figure eight follow-through has bilateral symmetry. The original strand of rope from the initial figure eight and the follow-through strand are parallel through each curve of the knot. As a result, if a viewer were to draw an imaginary line through the middle of the knot, vertically or horizontally, the halves of the knot would reflect each other in shape, size, and general appearance. This bilateral symmetry gives the knot its signature uniformity, making it easy to recognize from a distance.

Tying In with a Figure Eight Follow-Through



Check the harness manufacturer's guidelines for information on how to properly tie the rope to the harness. For harnesses with belay loops, generally follow the same path as the belay loop, which goes through two tie-in points on the harness. Tie the figure eight so that its loop is about the same diameter as your belay loop. The figure eight knot does not require a backup knot.

Figure Eight Loop

Another standard climbing knot, the figure eight loop is used for tying off the end of a rope, or for tying a loop in the middle, or "bight," of a rope. It is also commonly referred to as a "figure eight on a bight."



How to tie a figure eight loop.



Finished figure eight loop clipped to an anchor.

Tying the In-line Figure Eight (aka Directional Figure Eight)

In-line Figure Eight

Also known as a directional figure eight, this knot, like the clove hitch, can be used to tie off a series of anchors in a line. It takes some practice to master this knot, but some find it easier to use than a clove hitch.



Cross the strands to form a simple loop.



Cross a bight over the single strand.



Cross the bight under the strand.



Thread the bight back through the loop you've just formed.



Finished in-line figure eight.

Bowline

Boy Scouts were taught this knot with the saying "the rabbit comes up through the hole, around the tree, and back down through the hole." The bowline is very useful to tie the rope around something, like a tree, block of rock, or tunnel in the rock. It is important to note that a bowline knot requires a backup, as weighting and unweighting the knot easily loosens it. Always tie half of a double fisherman's knot to back it up. One advantage of the bowline is this same feature—it is very easy to untie after it has been weighted, so it is used regularly by professional riggers.

Tying the Bowline



Tying the bowline. The bowline should always be tied with a backup, shown here with half a double fisherman's for the backup knot (final photo).





Double Loop Knots

BHK

The BHK, an acronym for “big honking knot,” is technically a double overhand on a bight, used to create a redundant master point. It is commonly used for toprope anchor extensions and master points using rope.

Tying the BHK (“Big Honking Knot”)







1 Start by taking a doubled bight about 4 feet long.

2 & 3 Then tie an overhand loop on all four strands.



Master point toprope extension using a BHK and three steel oval carabiners with the gates opposed and reversed.



4 & 5 For greater security, take the single loop and hitch it all the way back around the body of the two-loop knot or clip it into the carabiners on the master point.

Double Loop Figure Eight

This knot is used primarily to clip in to or equalize two anchor points. If the two loops are used together at a master point, however, they are not redundant, due to the configuration of the knot.

Tying the Double Loop Figure Eight



Take a bight of rope and cross it back over itself, forming a loop.



Take two strands of the bight and wrap them around the standing part, then poke them through the loop.



To finish, take the loop at the very end of the bight and fold it down and around the entire knot you've just formed.



The double loop figure eight is a great knot to use to equalize two gear placements. You can manipulate the knot by loosening one strand and feeding it through the body of the knot, shortening one loop, which makes the other loop larger.

Double Loop Bowline

This knot is handy for equalizing two anchor points or clipping in to a two-point anchor. It can shift when weighted, so always back it up with a half a double fisherman's if the tail end is near the body of the knot.

Tying the Double Loop Bowline



Take a bight of rope and cross it over the standing part.



Thread the bight through the loop you've just formed.



Configure the end of the bight in a loop above the rest of the knot.



Flip the loop down like a hinge behind the rest of the knot.



Pull on the two loops until the end of the bight tightens at the base of the knot.



The two loops can be adjusted by feeding one strand into the body of the knot, which alternately shortens one loop and lengthens the other.

Knots for Webbing

Nylon webbing is a slick material that should be tied with caution: There have been many accidents where poorly tied knots in nylon webbing have failed. The two recommended knots for tying nylon webbing into a loop are the water knot (also known as the ring bend) and the double fisherman's knot (also known as the grapevine knot). When tying the water knot, your finished tails should be a minimum of 3 inches in length. It is important you tighten the water knot properly, as it has a tendency to loosen if tied slackly in a sling that is being used over time.



Tying the water knot (ring bend).



Tying nylon webbing with a double fisherman's (grapevine) knot.



The water knot.

Why would you ever use nylon webbing tied with a knot as opposed to a sewn runner? A sewn nylon runner is stronger than the same material tied with a knot. The answer is for rappel anchors when the slings are tied around a tree or through bolt hangers. It is also sometimes useful to untie the knot, thread it through something (like a tunnel), and re-tie it.

The double fisherman's knot is also a good knot to use to tie nylon webbing into a loop, although it does require more length of material to tie and is very difficult to untie after it has been seriously weighted.

Bends

A bend is a knot that joins two ropes or lengths of cord together. These knots are used to tie your cordelette into a loop, and also to tie two ropes together for rappelling.

Figure Eight Bend (aka Flemish Bend)

A variation of the figure eight follow-through, this knot can be used to tie two ropes together. It has superior strength and is easy to untie after it has been weighted. It is simply a retraced figure eight. On 9mm to 11mm diameter rope, tie it with the tails a minimum of 5 inches long.



The figure eight bend.





Tying the double fisherman's knot (aka grapevine knot). When tying 7mm nylon cord, leave the tails about 3 inches long.

Double Fisherman's Knot

This is the preferred knot to use for joining nylon cord into a loop to make a cordelette or prusik loop. It is also a very secure knot to tie two ropes together for a double-rope rappel, but can be difficult to untie.

Triple Fisherman's Knot

For 5mm and 6mm diameter high-tech cord (i.e., Spectra, Dyneema, Technora), a triple fisherman's knot tests slightly stronger than the double fisherman's. (Moyer, Tom, Paul Tusting, and Chris Harmston [2000]. http://user:xmission.com/~tmoyer/testing/High_Strength_Cord.pdf. 2000 International Technical Rescue Symposium.)



To tie a triple fisherman's, make three wraps before feeding the cord back through.



The triple fisherman's knot.

Knots for Joining Two Ropes

Standard knots for joining two ropes include the double fisherman's knot and the figure eight bend. The double fisherman's is more difficult to untie than the figure eight bend once weighted; the figure eight bend, while relatively easy to untie, is bulky. Tie these knots with a minimum of 3 inches of tail, and carefully tighten the knots before using them. A stiff rope makes it harder to cinch the knots tight, so be especially careful with a stiffer rope.

Which knot to use should be based on several variables. If the ropes differ drastically in diameter, or are very stiff, the most foolproof knot is the figure eight bend, backed up with half a double fisherman's on each side. This is a bulky knot, but it provides a real sense of security.



Double fisherman's knot.



Figure eight bend.



Figure eight bend with fisherman's backups.

Flat Overhand (aka Euro Death Knot)

How this knot received the "Euro Death Knot" moniker is unclear. Most likely the knot was initially adopted by Europeans and deemed unsafe when first seen by American climbers unfamiliar with its use. In reality, it is rarely responsible for incident or injury. In one such rappelling accident in recent times (in the Tetons, September 1997), the flat overhand failed when it was sloppily tied with too short of a tail. Ironically, former *Rock and Ice Magazine* editor George Bracksieck wrote in July of that year that "the one-sided overhand knot (tails parallel and together) remains the best knot for rappelling. . . . Be sure to leave plenty of tail and to set it snugly." After analyzing the accident, Grand Teton ranger Mark Magnusun wrote: "I intend to do some additional research in an effort to gain information on the overhand knot used for joining ropes, the origin of the 'Euro-death' nickname, and incidents of other failures."



Flat overhand knot.



Flat overhand with overhand backup.

From 1999 to 2009 various tests revealed the flat overhand to be roughly 30 percent weaker than the double fisherman's for tying two ropes together, but still plenty strong for rappelling situations. Testing also revealed that it was virtually impossible to get the knot to fail, as long as it was tied with a suitable-length tail and properly tightened.

Petzl, a leading manufacturer of rappelling devices, recommends the flat overhand as the knot to use for joining two rappel ropes together, as long as the ropes are of similar diameter and the tail is a minimum of 20 centimeters (8 inches).

The flat overhand has become widely adopted as the knot for joining two rappel ropes of similar diameters because it is easy to tie and easy to untie after it has been weighted, and it presents a clean profile when pulled down the cliff as the ropes are retrieved, thus less likely to jam in a crack. For added security it can be easily backed up simply by tying another flat overhand above the first one, although this adds bulk.

That being said, there are a few cautions: It is not recommended for tying together two ropes of drastically differing diameters (e.g., 7mm to 11mm), or for use on very stiff ropes. The bottom line is that the knot should be used with discretion, well tightened (pull hard on all four strands), and tied with a long tail (minimum of 8 inches).

The flat overhand is a poor choice for use with nylon webbing, and it has been responsible for rappel anchor failures where it was tied in webbing with a very short tail. The flat eight is even more dangerous if tied with short tails, especially in nylon webbing, and has been responsible for numerous accidents, as it inverts at shockingly low loads when the knot rolls inward and collapses.

Hitches

A hitch is a knot that is tied around something. A friction hitch is a knot tied with a cord or sling around another rope, utilizing friction to make the knot hold when it is weighted, but releasable and moveable without untying when it is unweighted.

Clove Hitch

The clove hitch is used to fasten a rope to a carabiner, tied around the wide base of a carabiner. The beauty of the clove hitch is easy rope-length adjustment without unclipping from the carabiner, making it a truly versatile knot for anchoring purposes: for anchoring a belayer, tying off an anchoring extension rope, or tying off the arms of a cordelette.

Get in the habit of tying the load-bearing strand on the spine side of the carabiner. Doing so loads the carabiner in the strongest configuration. Be sure to tighten the clove hitch properly by cranking down on both strands.

Slip Hitch

This is a simple knot used to tie off a knob or spike of rock.

Munter Hitch

The Munter hitch can be used for belaying, lowering, and rappelling. The mule knot, backed up with an overhand, is used to tie off a Munter hitch. The great advantage of the Munter/mule combination is that it can be tied off and released when the rope is weighted and under tension, making it one of the key knot combinations for many systems used in single pitch terrain.

The Clove Hitch



Tying the clove hitch.

The Slip Hitch



How to tie a slip hitch. The slip hitch can be tightened by pulling on one strand, making it more secure than a girth-hitch for tying off knobs of rock.



Tying the Munter Hitch on a Carabiner


1


2


3


4


5

Tying the Munter Hitch



Hold a single strand of rope with both hands, thumbs pointing toward each other.



Cross the right-hand strand in front of the left-hand strand and hold the two strands where they cross with the left thumb and forefinger, then slide the right hand down about 6 inches.



Bring the right strand up and behind the loop.



Clip a locking carabiner where the forefinger is shown here, below the two top strands.

Tying a Mule Knot



When tying a mule, be aware that when the rope is under tension (holding a climber's weight), it is necessary to maintain control of the brake strand.



Keeping the load and brake strands parallel, form a loop on the brake strand by crossing it behind while still maintaining your grip with your brake hand.



With the non-brake hand, take a bight of rope and pass it through the loop you've created, with the load strand in between the loop and the bight. Snug the mule knot up tight against the Munter hitch.



Pull some slack and finish with an overhand loop backup.

Tying Off a Tube Device with a Mule Knot in Front of the Device



First pass the bight of rope (on the brake hand side) through the belay carabiner.



Then tie the mule knot above your device on the load strand of rope going to the climber.


Black Diamond
ATC-XP

Finish with an overhand backup.

Tying Off a Tube Device on the Carabiner Spine



First pass a bight of rope through the carabiner and form a loop. If the device is under tension, pinching the rope against the device with the opposite hand will help lock it off.



Then pass a bight of rope through the loop you've created, with the spine between the loop and the bight.



Finish by tying an overhand backup on the load strand.

Prusik Knot

A prusik knot is used for rope ascending and as a component in many load transfer systems. It can be loaded in either direction. To tie a prusik, first make a "prusik cord" out of a 5-foot length of 6mm diameter nylon cord tied into a loop with a double fisherman's knot. Buy the softest, most pliable nylon cord available, because a softer cord will grip best. To tie the prusik, simply make a girth-hitch around the rope with the cord, then pass the loop of cord back through the original girth-hitch two or three more times. Dress the knot to make sure all the strands are even and not twisted—a sloppy friction hitch will not grip as well. Test the knot before using it. A thinner cord will grip better, but below 6mm in diameter, the cord will be too weak for many rescue applications. To slide the prusik after it has been weighted, loosen the "tongue," which is the one strand opposite all the wraps.

Tests on various friction hitches reveal that the prusik consistently has the most holding power in a wide array of cord and rope combinations, so use the prusik in scenarios (like 3:1 raising systems) where it will be loaded with more than body weight.



Tying a prusik knot.



A four-wrap prusik.

Klemheist Knot

This is another useful friction hitch that is quick and easy to tie, and is a good choice as a rope-ascending knot or if you're forced to use a sling rather than a piece of cord to tie a friction hitch. If using a sling, pick a nylon one over a Spectra or Dyneema sling, because it grips better and is less susceptible to weakening if it gets hot (nylon has a higher melting point). Four wraps of 6mm cord tied on a single 10mm diameter rope usually work well. After the hitch has been weighted, loosen the tongue (the one strand opposite all the wraps) to slide it more easily. The klemheist also can be loaded in either direction. If tied the opposite way, with the tongue at the base of the wraps, it is commonly referred to as the hedden knot. The hedden knot can be unreliable if it is formed by simply reversing the direction of a klemheist.

Tying the klemheist knot


1


2


3


4

Autoblock

Sometimes called the "third hand," the autoblock is used to back up your brake hand when lowering someone, or to back up the brake hand when rappelling. Tie your autoblock loop from a 4-foot 9-inch length of 5mm- or 6mm-diameter nylon cord tied into a loop with a double fisherman's knot. On a doubled rope, three wraps usually works best, and on a single strand of rope, four wraps.



The autoblock with nylon cord.



The Sterling Hollow Block, shown here wrapped in an autoblock configuration, is a 100 percent Technora sling designed specifically for use with friction hitches.

Stopper Knot

This knot is used as a safety knot in the end of a rope to "close the system." It is essentially half of a triple fisherman's knot tied on one strand of rope. A stopper knot prevents lowering accidents when the rope length is too short and the end of the rope travels through a belay device. A stopper knot also prevents rappelling off the end of the rope if rappelling with a plate, tube, or assisted braking (e.g., Grigri) device. When using two ropes, tie a separate knot at the end of each rope, as tying both ropes together can cause the ropes to twist around each other.



Tying a stopper knot.



Always close the system by either tying into the end of the rope or tying a stopper knot.

CHAPTER 7

Protection and Anchoring

Nearly every system that a climber can build starts either with good protection placed in solid rock or with strong independent natural features. Many recreational climbers make placements that are "good enough" but could be better. It's an instructor's job to not only make excellent placements, but also to evaluate student placements.

"Good enough" isn't good enough. An instructor should strive to make the best placements possible given the circumstances, while developing strategies to help students understand the dual arts of protecting a climb and building anchors.

Rock Assessment

The first thing to think about when assessing an anchor is the integrity and structure of the rock itself. Catastrophic anchor failures have occurred not because the gear placements were bad, or the rigging was flawed, but because the rock itself was unsound. Determining good rock structure and knowing what to watch out for are fundamental requirements to build solid anchors.

When placing gear, the ideal crack is what instructors call "a crack in the planet," a deep fissure that runs perpendicular (i.e., at a right angle) to the plane of the rock face, cleaving a massive, solid face of granite.

In general, there are two things to avoid: detached blocks and flakes. A detached block is just that—a chunk of rock that is not attached to the main rock structure, but is either sitting on top of the cliff like a boulder, or is part of the main rock face but completely fractured with cracks on all sides.

To assess a block, start by looking at its size. How big is it? Is it the size of a refrigerator, a car, or a house? Putting a piece of gear in the crack beneath a smaller block is a very bad idea. When the piece is weighted, it has a prying effect outward on the block. Even large blocks can shift easily. Look at how the block is situated. Is it perched down low, where it cannot slide out? Does it rest on a flat surface, or is it resting on an inclined slab? When tying off blocks, watch for sharp edges that may fray or cut the rigging rope, and use padding or an edge protector when needed. Generally, be very skeptical of using detached blocks as part of an anchor system, especially smaller blocks.

Flakes should also be avoided. A flake is formed by a crack in the rock that runs parallel to the main rock face. It can be wafer thin, or several feet thick. A flake is inherently weak, since any gear placement, when loaded, will exert a prying effect outward on the structure of the flake, which can fracture the flake if it's not strong enough to bear the force. In a naturally weak rock, like sandstone, a thin flake of rock can be extremely weak.

Exfoliation is a natural process of granite formations and is the key in the formation of domes. Flakes of granite are layered, like layers of an onion, and the outer layer peels off from time to time due to the effects of weathering and gravity, exposing a new layer beneath.



Use good judgment if anchoring to detached blocks. Avoid small ones and those situated on an inclined slab or those precariously perched. A good rule of thumb when using detached blocks is this: for a sole monolithic anchor, the block should be at least as big as a full-sized refrigerator, resting on a flat surface.

Rockslide!

One of the largest examples of exfoliation occurred in Yosemite Valley on a hot July day in 1996 at the Glacier Point Apron. An enormous flake, roughly the size of a football field and about 4 feet thick, detached from a point high on the cliff, shearing off in one gigantic piece. After a 2,000-foot free fall, the impact resulted in a massive explosion, creating a 300 mile per hour shock wave of wind that felled a thousand pine trees in a wide swath. A tourist, in line at the Happy Isles snack bar over a quarter mile away, was killed when hit by a piece of the shrapnel from the blast.



This camming device has been placed behind a flake of rock (left). If the cam is loaded, it will pry outward, potentially breaking the flake. This can cause the anchor to fail and also send the chunk of rock tumbling down onto people below.



This fabricated anchor is set up only to illustrate a point. Leaning back on this rappel anchor would most likely pull this detached flake right off the cliff.

When building anchors, look with skepticism at any flake. How thick is it, and how well attached to the main rock structure or cliff face? Test its soundness by thumping on it with the palm of the hand. Does it vibrate? Is there a hollow sound? When analyzing rock structure, act like a geologist and scrutinize the rock and its various formations very carefully.



Another dangerous anchor rig using a very questionable block. The block sits on a severely inclined slab, and a pull on this toprope anchor setup may be just enough to send it sliding down the slab and over the brink.

Macro to Micro Rock Assessment

When assessing rock structure, evaluate from macro to micro. Macro is the big picture. Look at the main rock face. Is there a massive, solid rock structure? Is there a crack in the planet? Or are the cracks an intricate matrix where no real massive piece of completely solid rock exists. Are there block or flakes? Is it possible to avoid using them? These are questions



This detached flake is a great example of bad rock structure.

that need to be asked. Never blindly place gear in cracks without first scrutinizing the big picture: the overall structure and integrity of the rock itself.

Microstructure is what's inside the crack. Is the surface of the rock rotten, grainy, dirty, or flaky? Are there hollow spots or hollow flakes inside the crack itself? Microstructure can affect the integrity of gear placements as much as the overall macrostructure.



Bad microstructure: The right side of this nut rests on a fragile flake.



You don't have to be a geologist to figure out that this flake is ready to exfoliate. Many catastrophic anchor failures are due to poor rock structure.

Natural Anchors

Natural anchors utilize the natural features found at the crag environment, such as trees, and the configuration of the rock itself. Trees are plentiful in some areas, rare in others, like in a desert environment. When assessing the reliability of a tree, there are several considerations. Is the tree alive or dead? What is the environment (dry or wet)? What is the diameter of the tree's trunk? How deeply rooted is the tree? When using a tree as part of an anchor system, a good rule of thumb is to choose a live, healthy tree with a minimum trunk diameter of approximately 12 inches. Generally speaking, trees rooted in a thin carpet of topsoil tend to be less reliable as anchor points than those deeply rooted in a thicker layer of topsoil. Climate should also be taken into account when considering the use of trees as anchor points. Trees in areas where the climate is wet and humid and the topsoil is thin can be less desirable as anchors than those in an area of thin topsoil but a dry climate.

The rock itself can be used for anchoring. Look for large spikes or horns of rock attached to the main rock structure to tie off as part of the anchor. A tunnel in a solid rock structure is called a thread and is utilized by threading a sling or cord, or tying a rope, through the tunnel. Limestone is a rock type with many threads, whereas threads in granite are a rarity.



OK. A properly girth-hitched nylon sling.



Good. A double-length (48-inch) nylon sling tied with an overhand knot makes the sling itself redundant.



Good. A figure eight follow-through knot used to tie the anchor rope directly to the tree.



I (BG) came across this natural anchor several hundred feet up a route on Tahquitz Rock, near Idyllwild, California. Someone had obviously rappelled from it, probably to escape an afternoon thunderstorm. Although the anchor has two basic components, each trunk is less than 3 inches in diameter, and the master point where you'd thread your rappel rope is a nonredundant, single aluminum rappel ring (albeit rated at 3,000 lbs.). The real problem I have with this rappel anchor is simply the size of the "tree" itself. I'm glad I didn't have to rappel from it!



A solid block tied off with a doubled cordelette using a figure eight knot, making the cordelette itself redundant.



A sling threaded through a tunnel with a girth-hitch. This is called a "thread."



The same thread with a doubled cordelette tied with a figure eight. This adds redundancy—if one loop is cut, three loops back it up.



A slip hitch used to tie off a knob of rock.

Monolithic Anchors

Instructors will often encounter natural anchors that are so large and reliable, they may be trusted as the sole component in an anchoring system. Titanic boulders and large trees are often unquestionably reliable, and that level of absolute certainty is how the merit of a monolith should be evaluated. If, after careful examination and consideration, there is any doubt of the integrity, security, and strength of a monolithic component, it is not monolithic and should not be used, or should be backed up appropriately. Common examples include living, deeply rooted trees that are larger in diameter than the entire climbing team; or a boulder the size of a small vehicle, firmly attached and embedded in the landscape.



A single pine tree used for a toprope anchor. Both the cord and the carabiners are doubled for redundancy in the rigging.

Just make sure the sling or rope around the anchor is redundant. For example, when rigging a rappel anchor around a tree, use two separate slings with two rappel rings to gain redundancy in the anchor system, at least in the rigging. When rigging a belay or toprope anchor, loop two strands of the cordelette around the tree, then tie a figure eight knot for a two-loop master point. Clip in with two locking carabiners, opposed and reversed, to achieve redundancy in the anchor rigging (although technically, one single tree is nonredundant). Use caution and sound judgment when using a nonredundant natural anchor.

Passive Protection

The Evolution of Chockcraft

A chockstone is simply a rock wedged in a crack. Naturally occurring chockstones can be as small as a pebble or as big as a house. The notion of using a chockstone for an anchor dates back to the origins of the sport. In the late 1800s, in the British Isles, rock climbers began using natural chockstones for anchors by slinging a cord around them and attaching their rope to the sling with a carabiner. The use of artificial chockstones—called chocks, or more commonly, nuts—began in the early 1960s, at a cliff in North Wales of all places, at a crag named Clogwyn du'r Arddu. The hike up to the crag followed a railroad track, and some ambling climber picked up a nut along the way and pocketed it. Up on the cliff he threaded a small cord through the nut before wedging it in a constriction in a thin crack. Thus the subtle art of chockcraft was born.

In American rock climbing, pitons were used almost exclusively for protection and anchors until the 1970s. In Europe, pitons were made of soft iron and once hammered into a crack were nearly impossible to remove and reuse. Legendary



A selection of chocks from the 1970s. Nuts have evolved over the years but are still based on the same original basic designs.

Now You See It, Now You Don't

A friend of mine (BG) put up a new route at Joshua Tree—a 40-foot-high sport climb with five bolts—up the face of a massive block that was a facet of a larger cliff. One day I got a phone call: "Tony's route fell down!" I didn't believe it until I walked out there and saw it with my own eyes. The gigantic block was top heavy and had simply toppled over, with the side where Tony's route was now straight down in the dirt, leaving behind a void in the cliff the size of a small house. I got down on my hands and knees and peered underneath. I could see one of the bolt hangers! Bouldering legend Chris Sharma visited the site shortly thereafter, climbing what is now one of Joshua Tree's most difficult boulder problems, up the newly exposed overhanging face of one side of the block.

NEUTRINO
NEUTRINO BD

A selection of modern-day nuts.

American climber John Salathe, a wrought-iron worker by trade, developed the first hard steel pitons, forged from an old Ford Model A axle, which he used for his famous ascents in Yosemite Valley during the 1940s. These high carbon steel pitons could be driven and then removed, over and over again.

Yvon Chouinard refined and innovated the design of chrome molly steel pitons from 1957 to 1965, improving on Salathe's designs with the introduction of knifeblade, horizontal (called the Lost Arrow), and angle pitons. These pitons revolutionized big wall climbing in Yosemite during the "Golden Age" of the 1960s, where hundreds of placements were required for the ultimate big wall climbs in Yosemite, like El Capitan. Once placed, they could be removed by the second, leaving the climbing route in the same condition for the next climbing team. Climbing standards in Yosemite led the world at the time.

But it came with a price. On popular climbs in Yosemite, the repeated pounding and removal of hard steel pitons began to permanently damage the cracks, leaving ugly "pin scars" every few feet up



Piton scars on a Yosemite crack.

crack systems. Cracks were getting "beat out," and something had to be done. In Yosemite the National Park Service actually closed down a few climbs because of piton damage.

When the great American climber Royal Robbins made a trip to England in the 1960s, he saw how effective nuts could be, and he imported the idea back to Yosemite. His 1967 ascent of The Nutcracker, one of Yosemite's most popular climbs, was done entirely with nuts, Royal's way of showing that nuts were a viable alternative to the destructive pitons. Today there still are piton scars on the route, a testament to how slow American climbers were to embrace the new and more gentle technology of chockcraft—a big change from bashing hard steel pitons into cracks with heavy blows from a hammer.

The change was finally precipitated by the fact that many cracks were simply being destroyed. Even granite is relatively soft when compared to cold hard steel. But it wasn't until Yvon Chouinard introduced chocks to American rock climbers in his 1972 equipment catalog, and Doug Robinson espoused the virtues of nuts in his seminal treatise, *The Whole Natural Art of Protection,* that the American climbing community firmly embraced the idea of "clean climbing," a new ethic where climbing anchors were placed and removed without scarring or damaging the rock.

Today there are thin crack climbs in Yosemite where for hundreds of feet every finger jam is in an ancient piton scar, although now instead of using pitons, nuts can be slotted into the V-shaped bottom of the old pin scars.

Artificial chocks now come in a dazzling array of shapes and sizes, the largest ones capable of holding over 3,000 pounds, and the tiniest micro-nuts designed to hold body weight only. The Hexentric, commonly called a Hex, is a unique, six-sided nut with four distinct orientations of placement, first introduced by Chouinard Equipment in 1971. It was followed by the Stopper in 1972, with its simple, but effective, tapered trapezoidal shape. Although there have been many new designs



The classic designs of the Hex (left) and the Stopper (right) have changed little since their inception in the early 1970s.

introduced since then, they are basically variations on a theme to these classic and timeless designs, which are still as viable today as they were more than forty years ago.

Another ingenious design, called the Tricam, invented by Greg Lowe in 1973 and available to the public in 1981, is essentially a single cam that can be used either passively or actively. Since it has a tapered design, with a point on one end, it can be wedged like a nut (called a passive placement) or used like a cam (called an active placement), where a mechanical action (i.e., camming) takes place. The camming action occurs when the sling is loaded on the back, or spine, of the cam, between two rails that contact the rock on one side of the crack, creating a force that pivots like a fulcrum onto the



The Lowe Tricam.



Tricam in camming mode.



Tricam in passive mode.

Assessing Nut Placement

To assess a nut placement, remember these three key elements:

1. Rock structure
2. Direction of pull
3. Surface contact

A good acronym is SOS:

S Structural integrity of the rock
O Orientation (direction of pull)
S Surface contact

pointed end on the other side of the crack. The design is useful for many horizontal crack situations, but can be somewhat difficult to remove with one hand or once it is weighted.

Be aware that in the smaller-size Tricams, when set in the passive mode, a Stopper of similar size is considerably stronger. The reason is because on the Tricam, the load is being placed directly on the scroll pin that connects the webbing to the body of the Tricam. (A pink Tricam in passive mode is rated at 6 kN; a similarly sized Stopper, 10 kN. In camming mode the pink Tricam is rated at 9 kN.)

When placing a nut, or any other piece of gear for that matter, again the first thing to consider is the overall integrity of the rock itself. The importance of rock assessment cannot be overemphasized. Nuts have very low holding power in soft sandstone, rotten, or flaky rock. Avoid placing nuts in cracks under or around detached blocks, or in cracks behind loose flakes. Look for "straight-in" cracks in massive rock structure, where the crack runs perpendicular to the plane of the rock face.

Once a good crack system is found, look for obvious constrictions in the crack itself. A "bottleneck" placement is found where the crack tapers drastically, and the proper size nut is fitted in the narrowing constriction.

With a basic tapered nut, like the Stopper, the preferred placement is in the narrow configuration, since this setting has the most surface contact and stability. The wider endwise configuration is an option for narrow slots and shallow cracks, but ultimately has less surface contact and generally less stability.

The typical nut placement is in a vertical crack, but horizontal cracks will work if there is a narrowing at the lip of the crack and you can slide a nut in



Stopper in a bottleneck placement. There is simply no way that in a downward pull the nut could be pulled through the bottleneck—something would have to give, either the rock itself or the nut or wire cable breaking.

from the side, then pull it into the constriction.

The real art of chockcraft comes into play with the more subtle placements. Look for any slight variations in the walls of the crack. When placing a nut, aim for maximum surface contact between the metal faces of the chock and the walls of the crack.

When the walls of the crack are virtually parallel sided, using the camming action of a Tricam or Hex is the best option for a nut placement, although this is territory that specific camming devices were designed for.

After rock quality has been assessed, the next concern when placing a nut is the direction of pull. In what direction will the chock be loaded? Most placements can withstand a pull in only *one* direction. While the nut may be able to withstand a load of 2,000 pounds in that one direction, the slightest tug in the opposite direction might jerk the nut right out of its placement. When incorporating a nut placement into an overall anchor system, look at the ultimate direction the anchor system will be loaded and orient placements in a line toward this focal point (called the master point).

Setting a nut properly is also important. Many novice climbers make a great nut placement but fail to set it properly, which makes the nut susceptible



Excellent. This Stopper placement is in good, solid rock and has flush surface contact on both sides of the nut.



Good. This endwise Stopper placement has good surface contact on both sides.



Bad. The left side of this nut lacks surface contact with the rock.



Marginal. This Stopper is in a good bottleneck, but since it lacks flush contact on the right side, a slightly outward pull will pluck it from its placement.



Good. The left side of this nut is nearly 100 percent flush, and the curve of the nut on its right side fits the curve of the crack.



Excellent. This nut has good surface contact on both sides, plus the lip on the right side of the crack protects against any outward force.



Excellent. This Hex placement has near complete contact on both faces of the nut in a solid straight-in crack. Loading the nut's cable will kick in the camming action of the Hex.

to levering out of its placement if pulled from a different angle than intended. Setting the piece is accomplished by simply applying several stout tugs in the direction the piece will be loaded, most easily accomplished by attaching a sling to the nut with a carabiner and yanking on the sling, firmly wedging the nut in its intended placement. While this definitely makes the nut more difficult to remove, it is an important concept that many novices miss.

Carrying a nut tool, which is a metal pick designed for nut removal, facilitates "cleaning" nuts. To clean a nut can be as easy as yanking it in the opposite direction from the intended direction of pull, but be careful with recalcitrant nuts that can suddenly pop out and hit your face or teeth. Yanking a piece out can also send a hand bashing into the rock, scraping knuckles. A better approach to removing a nut is to use the nut tool, giving the nut a tap opposite from the direction of loading. For larger nuts an easy way to loosen them is to tap the nut with a carabiner, metal to metal.

To become skilled at chockcraft takes practice. Look for good rock structure, preferably a straight-in crack. Then look for any obvious V-shaped constrictions in the crack. If there is nothing obvious, look for any subtle narrowing of the width of the crack. Practice nut placements, aiming for maximum surface contact between metal and rock, keeping in



Good. This Hex is in a narrowing pocket, and both sides of the nut have good surface contact.



Bad. No surface contact on the left side makes this Hex placement likely to fail with the slightest outward force.



Excellent. This endwise placement has great surface contact on both sides.



A nut tool is indispensable for removing chocks. Here are two models: Black Diamond (top) and Metolius (bottom).

To remove a nut with a nut tool, inspect the placement and determine the intended direction of pull, then tap in the opposite direction.

mind the paramount importance of direction of pull. Set the nut with a sharp tug. Once set, it should not move, pivot, or wiggle in its placement when you test it with a slight tug in the opposite direction of the intended direction of loading. Practice will help to develop the knack for seeing what size nut is needed for a particular placement, then selecting the proper nut and fitting it into the crack on the first try. Every nut placement is different, some less than perfect, some great, some worthless. It is important to have enough knowledge to know what's good and what's not, and what constitutes a placement that can be trusted.

Active Protection

In the mid-1970s a stout, muscular fellow by the name of Ray Jardine could often be seen peering through binoculars, gazing upward at the various nooks and crannies on the walls of Yosemite Valley. With his thick beard and glasses, he looked like a bird watcher, but Ray wasn't looking for birds. The bulging forearms gave it away—Ray was a climber, and he was looking for the ultimate crack: one of those perfectly straight cracks that split Yosemite's steep walls like a surgeon's incision, shooting upward for a hundred feet, uninterrupted.

Ray had invented a new technology—the spring-loaded camming device, or SLCD—that allowed him to place reliable protection in even perfectly parallel-sided cracks. When he found his ultimate crack climb, he swore his partners to secrecy and set out on a mission: to climb the most difficult crack ever climbed in Yosemite. He named it the *Phoenix*—a fingertip to hand-size crack on a gently overhanging wall high above Cascade Falls in the lower valley. After dozens of attempts using his newfangled technology, he finally succeeded in climbing Yosemite's first 5.13. Ray called his miracle invention the "Friend," and soon the word was out. Some climbers called it "cheating," while others claimed it was "the greatest invention since the nylon rope."

Marketed by Wild Country, the Friend soon became an integral part of every rock climber's rack. Ray soon retired from climbing and, financed by his proceeds from the licensing of the Friend, went on to sail around the world, hike the Pacific Crest Trail, row across the Atlantic, and ski to the South Pole.

The idea of the SLCD, or "camming device" for short, is simple in concept yet complex in design. Jardine's original design consisted of a unit with a rigid aluminum shaft connected by an axle to four independent, spring-loaded aluminum cams (called "lobes"). The cams retracted via a trigger bar that slid up and down a slot in the shaft. The unit was fitted into a parallel-sided crack with the cams retracted; when weight was applied to a sling tied



The original Wild Country Friend was one of the greatest innovations in rock climbing.

Spring-loaded camming devices have become an integral part of every climber's rack.

into a hole in the bottom of the shaft, the cams were activated in response to the load. To keep the unit from being pulled out of the crack, a corresponding force held it in place. The downward force in the direction of the shaft was transferred outward at the cams, which generated an outward force against the walls of the crack.

The disadvantage of Ray's design was that a rigid shaft could not flex or bend in the direction of pull, an especially troubling problem for placements in horizontal cracks.

Today there is a huge array of SLCDs on the market, and the majority of these designs have flexible wire cable shafts instead of rigid ones. One of the biggest improvements since the invention of the Friend was the first double-axle design, called the Camalot, introduced by Black Diamond Equipment, which allows for a much greater range of placement of the cams. Now, in addition to units with four cam lobes, there are TCUs (three-cam units) and offset cams (for flared cracks).



The Black Diamond Camalot was the first double-axle design.

The Metolius Power Cam has color-coded dots that help you assess your placement.



The Metolius offset TCU (three-cam unit) works well in slightly flaring cracks.

Placing an SLCD

When placing an SLCD, the first thing to consider is rock quality. SLCDs can fail if the rock is soft, brittle, or loose. They can easily pull out if placed behind a small, loose block or thin flake of rock. In solid granite, in an ideal placement, a Black Diamond Camalot can hold as much as 14 kN (3,147 lbs.) Do not rely on a camming device to hold in very soft sandstone, or in rotten or flaky rock. Cam manufacturer Metolius advises: "Rock fails in two basic ways: either a relatively large piece breaks off or the surface layer is crushed under the pressure of the cam lobe, allowing the cam to 'track out.' Instructors must assess the integrity of the rock and choose the soundest possible location for your placements. Look for fractures in and around the walls of a potential placement that could denote weakness, as well as pebbles, crystals, or micro-flakes that could snap off. Be extremely suspicious of placements behind flakes or blocks."



Bad. Any force applied to this Black Diamond Camalot will be converted to an outward force that can pry out and potentially break the flake of rock it's placed behind.

Since they rely on friction to a certain extent, camming devices are not as strong in exceptionally slick or polished rock, or rock that is wet or icy. Again, avoid placements behind detached blocks and loose flakes—the outward expansion of the cams can generate a tremendous force that can pry the rock loose. Look for straight-in cracks in solid rock. A straight-in crack is one that runs perpendicular to the face of the rock, bisecting the rock at a right angle.

When placing a camming device, look for a section of the crack where the walls are uniformly parallel, or where they form a subtle pocket. Avoid widening cracks, where the crack is wider above the cams, as the camming device, due to its spring-loaded design, will naturally have a tendency to wiggle upward as the cam is activated. This phenomenon is known as "walking." This walking movement is most exaggerated when the cam's sling and cable are manipulated from side to side, but it can also happen when the piece is repeatedly weighted and unweighted, as in toproping. In a crack where the walls are uniformly parallel, or where the crack narrows slightly above the cams, if there is any walking, the cams will not open any wider and will stay within acceptable retraction range. As a test, pull the device from side to side to see what walking, if any, occurs. There is only one definitive solution to walking: Cams must be placed in a slot or crack that dead-ends or closes off. Otherwise, walking can be somewhat mitigated by slinging, supervising the placement, and creating anchor systems that self-adjust as direction of load



Bad. Even though the cams on this Black Diamond Camalot are within the acceptable range (right around 50 percent retracted), the widening crack above will allow the cams to easily "walk" into the wider section, even with minimal loading and unloading of the device. Avoid this situation, since the cams can potentially walk to an open and unstable position.



Very good placement. All the cams have good surface contact in a solid, straight-in crack, and the cams are in the recommended range for a Camalot (50 to 90 percent retraction).

varies. The key point here is that walking is something to be aware of and watch for.

Another key to a good placement is the range of retraction on the cams. Black Diamond recommends that the Camalot be placed in the lower to mid-expansion range (50 to 90 percent retraction), while Wild Country advises the following for its single-axle designs: "It is vitally important that all the cams make contact with the sides of the rock, preferably in the middle half of their expansion range (i.e., the cams should be one-quarter to three-quarters open)." Metolius recommends to "select the largest size cam that will fit without getting stuck. Cams should not be placed near the wide end of their expansion range. When a unit is loaded, it expands as the slack is removed from the system and the cams and rock compress. A nearly tipped-out cam won't have enough expansion left to accommodate this process. A loose cam is also more prone to walking and has little range left to adjust."



Bad. The two outside cams are not in the acceptable range for a Camalot (too wide), and they don't have flush contact with the walls of the crack.



Good. This Metolius Power Cam displays optimal green "range finder" dots in a solid, parallel-sided crack.



Poor. Although the range of retraction is acceptable, this Metolius Power Cam could easily walk up into the wider pod in the crack above the cams, rendering the placement unstable. Also, the outside right cam has poor surface contact and is too close to the edge of the crack.



Placing a camming device with a rigid shaft in a horizontal crack with the shaft protruding can be dangerous because the shaft can break if loaded at a 90-degree angle during a leader fall.



Camming units with flexible shafts are the best option for horizontal placement. Metolious recommends that in a horizontal crack, the outside cams should be placed on the bottom of the crack for maximum stability.



Good. This Camalot, placed in a solid horizontal slot, has all four cams tighter than 50 percent retraction with flush surface contact.



Borderline too tight. This Camalot is around 90 percent retracted. Any tighter and it may be very difficult to remove. There is also some loss of holding power in the last 10 percent (90 to 100 percent retracted) on a Camalot.



Very poor. The cams are barely retracted and nowhere near the recommended range. The piece can easily walk and might fail completely.



Borderline marginal. While this Metolius Power Cam is in a pocket that lends some stability to the placement, the range of retraction is between the yellow and red "range finder" dots; the red dots signify a marginal placement. The next larger unit would fit nicely.



Fair. This Camalot is in a slightly flaring crack, with the inside cams retracted tighter than the outside ones, although each set of cams (inside and outside) are within a suitable range and all the cams have flush contact with the rock.



Bad. The crack is way too flared for this Metolius Power Cam, and the cam on the right side has very poor surface contact with the rock.



Good. This Metolius cam is in the tighter aspect of its range. Green means good to go.



Bad. The cams are too open, rendering the placement unstable. Shoot for at least halfway tight on the cams.



The same crack with two different placements. In the left-hand photo, the left outside cam has poor contact and is too close to the edge of the crack. By flipping the cam around (right photo), the gold cam now has flush surface contact with the rock. Since the inside and outside sets of cams are offset, flipping the cam one way or the other can often afford a better placement, particularly in shallow cracks in corners.

To illustrate what constitutes an acceptable range of retraction for the cams of a camming device, let's look at the Black Diamond Camalot in greater detail.

What is 50 to 90 percent retracted for a double-axle camming device like the Camalot? When you're looking at the Camalot without pulling on the trigger, it's at 0 percent retraction. Squeezing the trigger mechanism so that the cams are as tight as possible is 100 percent retracted. At 100 percent retracted, in a very tight placement, the Camalot will likely be very difficult to remove. In the last 10 percent of the tightest aspect of the range (90 to 100 percent retracted), the Camalot also loses some of its holding power, another reason not to go too tight on a placement. The starting point for a good placement is at 50 percent retraction, which is when the cams are pulled at least halfway tight. Looking at the base of the cams, 50 percent retraction is when the base of each cam is at a 45-degree angle relative to the vertical axis of the Camalot. If the cams are symmetrically retracted, they will be at a 90-degree angle relative to each other. A common mistake is to place a Camalot near the outer limit

The innovative Link Cam, by Omega Pacific, covers the range of four standard camming devices in a single unit.

of its range (0 to 50 percent retraction). This can prove to be a very unstable placement if the unit moves at all in the crack, which can easily happen if the Camalot is placed in a crack that widens above the cams and the piece is repeatedly weighted and unweighted. Again, the optimal Camalot placement is when the cams are at least halfway tight (50 percent retracted). From the beginning position, pull the trigger mechanism until the range on the cams is half the starting size, then go only smaller and tighter from there. Scrutinize your placement after the camming device has been placed in a crack to make sure the cams are in the acceptable range.

Metolius cams have a unique color coding that assists in their assessment. The company gives this advice: "Verify that you have chosen the best size by making sure that the green Range Finder dots are lined up where the cam lobes touch the walls of the placement. Yellow dot alignment is okay too, but you must exercise more caution with the placement, because the cam will be less stable, hence more prone to walking, and it will have less expansion range left to accommodate walking to a wider position. If the cam you choose aligns in the yellow zone, the next larger size will align perfectly in the green zone. Use that cam instead, if it's still on your rack. Never use a placement in the red zone unless it's the only placement available."

Study the literature that comes with any camming device and learn what the manufacturer recommends for the acceptable range of retraction and the various placement criteria. Most manufacturers also have informative PDF files on camming device guidelines that can be downloaded from the company's website.

To become proficient in the use of camming devices takes thought and practice. To develop confidence quickly, hire an AMGA certified guide or climbing instructor to critique placements. Metolius suggests to "practice placing cams in a safe venue,

Ground Practice

When I (BG) teach camming device placements, I first demonstrate the fundamentals, then let students make a variety of placements with a critique on each one. Working with an instructor allows them to learn from their mistakes before venturing out on their own. Better to learn in a "ground-school" setting than on their first toprope anchor that their "Friend" was no friend at all.

at ground level, before you trust your life to a cam placement. This process can teach you a lot, but written guidelines and practice are no substitute for qualified instruction. We strongly recommend that you learn to place cams under the supervision of a certified guide."

Fixed Anchors

Pitons

A piton is a metal spike that is hammered into a crack for an anchor. The blade of the piton is the part hammered into the crack, leaving the protruding eye into which a carabiner can be clipped. Piton anchors are something of a rarity these days, but occasionally fixed pitons (also called pins) can be found at the top of a crag. Follow these steps before using any fixed pin. First, assess the rock structure and look at the crack where the piton resides. Is it behind a block or flake, or is it in a straight-in crack with good structure? A good piton should be driven in all the way to the eye, and should not wiggle when clipping into it with a sling and pulling on it to test it. The piton itself should not be excessively corroded or cracked. (Look closely at the eye of the piton, as this is usually where the piton will be cracked.) To effectively



Pitons (left to right): Angle, horizontal, Leeper Z, knifeblade.

An angle piton, driven all the way to the eye—a good placement.

test a fixed pin, a hammer is needed. Give the piton a light tap—it should have a high-pitched ring to it, and the hammer should spring off the piton. Without a hammer, tap it with a carabiner or small rock. The best test is to clip a sling into it and give it a vigorous yank in the direction it will be loaded. Over time, pitons suffer from the vagaries of thermal expansion and contraction, particularly in winter, as water expands when it freezes, prying and loosening the piton. Often a piton can be easily plucked out by hand after only a few seasons. If utilizing fixed pitons as part of a toprope anchor system, always back them up, and use them with skepticism.

Bolts

The most common fixed anchor is a two-bolt anchor. Some knowledge of the history, characteristics, and specifications of bolts used for rock climbing will improve one's ability to assess the reliability of bolt anchors.

In the 1960s and 1970s, bolts were placed by hand drilling—an arduous process where a drill bit was inserted into a drill holder, then a hammer was used to pound on the holder to painstakingly drill into the rock. Once the hole was deep enough, a bolt, with a hanger attached, was hammered into the hole. The most common bolt during that era was the ubiquitous ¼-inch contraction bolt, called the Rawl Drive, manufactured by the Rawl Company and designed for the construction industry for anchoring in masonry or concrete. A contraction bolt has a split shaft that is wider than the diameter of the hole. When pounded into the hole, the two bowed shaft pieces are forced to straighten slightly, contracting under tension in the hole. This works fine for hard granite, but in soft rock, like sandstone, the split shaft doesn't really contract all that much, and there is little tension to keep it in the hole, resulting in very weak pullout strength (i.e., pulling straight out on the bolt).

Another problem with ¼-inch bolts is that they came in various lengths, some as short as ¾ inch long, and once placed in the rock, there was no way for future climbers to determine the length of the bolt merely by inspection.

There are two basic styles of ¼-inch Rawl Drive bolts. The buttonhead design has a mushroom-like head and is pounded into the hole with the hanger preattached. The threaded Rawl Drive has threads with a nut on the end to hold the hanger in place, a weaker configuration since the threads can weaken the shear strength of the shaft if the hanger is at the level of the threads. But more significantly, the threaded design has a serious flaw: Pulling straight out on the bolt hanger will only be as strong as the holding power of the nut on the threads, a dangerous problem if the nut is at the very end of the threads.

The shear strength on a brand-new ¼-inch Rawl Drive bolt is roughly 2,000 pounds, but the problem with contraction bolts is not shear strength but pullout strength, which varies drastically depending on the quality and hardness of the rock. In very soft sandstone the pullout strength of a ¼-inch contraction bolt is extremely low, rendering the bolt unsafe.



The infamous ¼-inch threaded Rawl Drive contraction bolt, complete with the SMC "death hanger." This ticking time bomb was removed and replaced from a route on Suicide Rock, California.

The buttonhead Rawl Drive bolts were also sold in ⁵⁄₁₆-inch diameters, these being far more reliable as long as they were placed in good, hard, fine-grained granite. The ⁵⁄₁₆-inch buttonhead, for example, has a shear and pullout strength in excess of 4,000 pounds, and for many years was the bolt of choice for first ascensionists who were hand drilling bolts. The ⁵⁄₁₆-inch buttonhead Rawl Drive was discontinued, but the ⅜-inch buttonhead is still on the market today, with a shear strength of 7,000 pounds and a pullout strength of over 4,000 pounds in the best granite.

Probably the most disconcerting problem associated with bolts from the ¼-inch era is not the bolts themselves but the hangers. During that time, hangers made for rock climbing were manufactured primarily by the SMC company. Thankfully, the hangers are easily identified, as the "SMC" brand is stamped on them. There were two series of hangers: one good, and one very bad. The "bad" hangers



Buttonhead Rawl Drive contraction bolts (left to right): ⅜-, ⁵⁄₁₆-, and ¼-inch sizes.



¼-inch threaded Rawl Drive bolts with "good" (left) versus "bad" (right) SMC hangers.



$\frac{5}{16}$-inch buttonhead Rawl contraction bolt with "good" SMC hanger. In a good placement in solid granite, these bolts are rated at over 4,000 pounds shear strength.

were nicknamed the SMC "death hangers," since some of them failed under body weight after only a few seasons of exposure to the elements. These hangers are identifiable by a distinctive corrosive discoloration—a yellowish or bronze tint, whereas the "good" SMC hangers, made from stainless steel, show no signs of corrosion or rust and still appear silvery bright, even after twenty-five years. Another noticeable difference is in the thickness of the hangers—the "bad" hangers roughly the thickness of a dime, and the "good" ones the thickness of a quarter.

Another dangerous relic from the 1970s is the Leeper hanger. Over 9,000 of these hangers were manufactured by Ed Leeper of Colorado, and subsequently recalled because of stress corrosion



The recalled Leeper hanger can easily be identified by its unique shape and rusty condition.



Bad corrosion on a $\frac{3}{8}$-inch diameter threaded Rawl Drive bolt with a badly corroded Leeper hanger to match.



The ⅜-inch diameter Powers Power Bolt expansion bolt with a stainless steel hanger has become the minimum standard for climbing anchor bolts.

problems with the metal, which rusted badly since it was not made of stainless steel. These hangers are easily identifiable due to their strange geometric shape and their rusty condition.

In the 1980s sport climbing was ushered into the United States, and climbers began to place bolts on rappel using cordless rotary hammer power drills. Since these bolts would now have to absorb numerous falls, climbers began to look for the strongest bolts available, and the standard became ⅜-inch diameter for good, solid rock (like granite) and ½-inch diameter for softer rock (like sandstone)—standards that are still prevalent today.

Although there are numerous types of bolts used in rock climbing today, the gold standard has long been the "5-piece Rawl" expansion bolt (now sold as the Powers Power Bolt). This expansion bolt has a shaft with a hex head on one end and threads on the other end (the end that goes in the hole), with a cone-shaped piece screwed onto the threads. The shaft has a two-part split sleeve, and as the hex head is tightened, the cone climbs up the threads and under the sleeves, which presses the sleeves outward, "expanding" the bolt in the hole. The more you tighten it, the wider the sleeve gets. The performance and strength of the bolt relies, to a great extent, on two things: the tolerance (diameter) of the hole, and the strength of the rock itself. In good rock the ⅜-inch Power Bolt is rated at over 7,000 pounds shear strength, with a pullout strength of roughly 5,000 pounds.

Since these bolts are really designed for the construction business, the Powers Fastener company lists strength ratings based on the density of the concrete they are placed in. Concrete is given a psi (pounds per square inch) rating. For example, "2,000 psi concrete" means that it would take a weight of 2,000 pounds to crush a square inch of concrete. Hard, dense granite is analogous to 6,000 psi concrete, and soft sandstone is more like 1,000 psi concrete.

Once a bolt has been installed, it's impossible to see what's going on beneath the surface (like with the length of the bolt), and all that can be seen is the head of the bolt, again making identification of the type of bolt more difficult.

For more in-depth information, peruse "mechanical anchors" on the Powers company



⅜-inch threaded expansion bolt.

website (www.powers.com); there is an excellent tutorial on the various types of bolts and how strong they are in differing rock types.

Even if lacking expertise in mechanical engineering or in identifying bolt design and type, it is important to know what to watch for when inspecting a bolt anchor. An obvious red flag is rust. SMC "death hangers," Leeper hangers, homemade aluminum hangers, and any bolt or hanger with obvious signs of corrosion should not be trusted. Look closely and identify the diameter of the bolt. A ⅜-inch diameter bolt has become the minimum



⅜-inch Powers expansion bolt with stainless steel Mad Rock hanger.



⅜-inch stainless steel Powers bolt with stainless steel Petzl hanger, painted to match the rock color.

Beware the ¼-inch Bolts

As someone who has replaced many bolts over the years, I (BG) can tell you that any ¼-inch bolt should be considered suspect, particularly in less than perfect rock. I've plucked out many ¼-inch contraction bolts that came out with about the same resistance as a nail being pulled out of plywood. To replace a ¼-inch bolt, the best method is to pry it out of its hole, then re-drill the same hole to a ½-inch diameter and install a ½-inch diameter stainless steel Powers Power Bolt (10,000 lbs. shear strength) with a stainless steel hanger. I like to paint the hanger (before I install it) the same color as the rock so that the bolt is visually unobtrusive. It's a good feeling to replace a ticking time bomb with a solid anchor that will last a lifetime.



A well-engineered rappel anchor. Both bolts are ⅜-inch stainless Powers bolts with stainless steel Petzl hangers, along with a stainless steel chain, quick link, and ring. Everything was painted before installation to match the color of the rock.



All these old bolts at Joshua Tree were replaced with brand-new stainless steel hardware, courtesy of the American Safe Climbing Association (ASCA).

standard, along with a stainless steel hanger. A bolt with threads and a nut holding the hanger in place is generally not as strong as the hex head types.

The rock should not show cracks emanating from the bolt placement—a more common problem with contraction bolts than expansion bolts.

In a good placement, the hanger should be flush against the rock and should not budge or be deformed in any way. A "spinner" is a bolt that protrudes enough so that the hanger can be easily spun around 360 degrees. This generally means that when the bolt was installed, the hole was not drilled deeply enough, and the bolt contacted the bottom of the hole before the hanger could be drawn flush against the rock.

If the bolt wiggles slightly when pulled or the hanger is loose, and the bolt has a hex head or a nut on threads, tightening the bolt with a wrench may help, but most likely the bolt has a problem that can't be fixed. If, while trying to tighten it, no increasing resistance is felt, and it won't tighten any further, then the bolt has serious problems—usually this means the tolerance (diameter) of the hole is too big for the bolt, or the rock is too soft.



This rack has a good assortment of both nuts and camming devices.

The American Safe Climbing Association (ASCA) has been very active in donating the necessary (and expensive) hardware to climbers who take on the task of upgrading unsafe bolt anchors with modern, stainless steel bolts and hangers. To support their efforts and donate to the ASCA, visit www.safeclimbing.org.

CHAPTER 8

Anchor Systems

If the hundreds of pages of how-to literature, magazine articles, blogs, lengthy message board posts, and hours of instruction from professionals and climbing partners teach us nothing else, it's that anchors are something climbers pay attention to. And yet, much of what is said and has been said is facile. Most climbing anchors involve the simple combination of obvious components, using strong materials to make an unquestionably effective master point. As climbing instructors, and as climbers too, there is a tendency to obsess over the outliers, conflate simple problems and complex solutions, and worry ourselves. This section will attempt to differentiate between the simple tools used to solve simple problems that instructors are likely to encounter, and the more complex tools used to solve complicated problems that instructors will rarely encounter.



A simple three-point cordelette anchor.

For every anchor, simple or complex, the need for an unquestionably reliable, strong, and secure attachment point is the goal. The responsibility for managing risk of harm to others should inspire an anchor builder to create an anchor that can do the work of the climbing system, can easily sustain any potential loads that emergency scenarios may create, and can still give the entire climbing team a margin of error. So how strong is that? How strong would something have to be to eliminate all doubt?

Let us begin by considering the base-managed toprope, the system where the toprope has been redirected through the anchor and the climber and the belayer are on the ground. If the climber weighs 100 pounds, the belayer must match that weight in order to arrest the climber; therefore, we'll call the belayer a counterweight. At any point in a taut climbing system, the anchor must be able to hold the climber (100 lbs.) and the counterweight (100 lbs.); that's 200 pounds. But the climbing system is not always perfectly taut. The latent elongation of the climbing rope means that the climber is always a mass in motion, a mass on a sort of bungee cord when he or she falls. With a perfect belay, let's say that the climber's dynamic weight is more like 200 pounds. Now the counterweight is 200 pounds too, and the anchor must hold 400 pounds. Now let's say that the climber moves faster than the belayer can belay, or the belayer is a bit inattentive, and the falling climber now generates an even bigger dynamic load. Four hundred pounds is not inconceivable, and matched by a 400-pound counterweight, the anchor needs to hold 800 pounds. Now, if we could conceivably create an 800-pound load, how strong would the anchor need to be to create an unquestionably reliable, strong, secure attachment point? Now consider that climbing instructors are often taking all kinds of people climbing, people who weigh more than 100 pounds, for example. How strong would the anchor need to be? More than 800 pounds, surely. More than 2,000 pounds? More than 3,000? There is no definite answer. "Unquestionably reliable, strong, and secure" might mean different things to all of us. That is both the challenge and the beauty of anchor building.

The goal of this chapter is to demonstrate skills that will allow an instructor to build an anchor that not only solves this problem effectively, but provides a reasonable margin of safety. Since all climbing gear, attachment tools, carabiners, protection, and ropes are overly strong, we should be able to build anchors that solve the problem unquestionably well.

Fundamental Anchor Anatomy and Principles

All anchors have the same fundamental anatomy. They have components, attachments, and a master point. Most anchors also have a shelf. Together these create the acronym, CAMS.

C = Components are the features or tools that ground an anchor to the landscape. They are often organized into natural (trees, boulders, terrain features) and artificial (bolts, pitons, removable protection) categories.

A = Attachments are the materials that combine the relative strength of each component and consolidate their strength in a focal point.

M = Master point is the point of the anchor where all critical attachments occur.

S = Shelf. Some anchors also have a shelf, an auxiliary attachment point with all the same load-bearing and security qualities as the master point. It should only be used in an auxiliary fashion.

All anchors should strive to adhere to the following fundamental principles:

1. Eliminate or limit extension: Given the failure of any individual part of the anchor, the attachment systems will not extend enough to severely shock load the remaining components.
2. Redundancy: Given the failure of any feature of the anchor system (with the exception of

a monolithic component), there will be other features to reinforce or back up that initial failure.

3. Intelligent load distribution: Given any load the anchor may sustain during its use, the attachment system should distribute load to the components in a manner that optimizes the relative strength and security of each component.
4. Strength: All attachments, components, knots, rock, or natural features must have more than adequate strength to sustain any load that could be applied to it during a climbing activity.
5. Simplicity: Given the anchoring tools available, the available components, and the prevailing conditions, an anchor should be efficiently constructed and deconstructed; while accomplishing all the other principles of anchoring, it should make efficient use of time and equipment.

Notes on Redundancy

By itself, redundancy does not guarantee safety—rappelling off a bunch of old weathered slings or a couple of old rusty chain links, for example—but redundancy in anchor systems is something to always strive for as a baseline and a starting point for evaluation. In rock climbing, a nonredundant anchor is considered marginal by professional standards. Many canyoneering enthusiasts argue that redundancy at the anchor system is superfluous, as there will be a point in the system where redundancy can no longer be maintained—rappelling on only one rope, with one rappel device, on one locking carabiner. This is absolutely true, so it's important to remember why redundancy is important to climbers. Unlike the canyoneering participant on rappel, or the military unit launching out of a helicopter, climbers are intentionally challenging themselves by climbing unknown difficulties. There is nothing unpredictable about a rappel; the line will be loaded consistently and in the same direction. But a rock climber's movements are erratic and unpredictable, with wide variation from one climber to the next, especially on a challenging climb. Systemic redundancy is a way to create a satisfactory margin of error to account for that unpredictability. Sometimes instructors might intentionally modify the concept of redundancy if they can substitute supervision to provide the security that redundancy might otherwise offer. The rope direct belay is a good example. A thoughtful instructor knows that the principle of redundancy is not simply being ignored, but that redundancy is not necessarily the goal. Security is the goal; redundancy is just one of the most common ways to create that security.

The Rope Direct Belay

If the belay anchor is initially built well back from the edge, and you want to belay from the edge to maintain a visual on the climber who's climbing up from below, you can use the climbing rope and a rope direct belay technique, which is essentially belaying off an extended master point. Attach your climbing rope to the master point on the anchor with a clove hitch on a locking carabiner, so you can adjust the length and position yourself just where you'd like at a stance near the edge where you can see the climber. Off the back side of the clove hitch, leave a little slack, then tie a figure eight loop and clip it into a separate locking carabiner to the master point. On this strand of rope, tie a figure eight loop and clip in your assisted braking device (ABD), at an ergonomic position slightly above you (toward the anchor) but not so far away that you can't reach the device and manipulate the handle if need be. This method is referred to as "rope direct" because you are essentially belaying directly off the anchor, albeit extended whatever distance is required to position you at the edge. Using a device like a Grigri, you'll have the benefit of a quick and



The rope direct belay rigging. This rigging technique allows you to position yourself away from the anchor and still use the direct belay technique, albeit on an extended master point. The belayer is attached to the master point with a clove hitch to a locking carabiner. Off the back side of the clove hitch, the rope is clipped back to a separate carabiner with a figure eight loop. Off this strand, the Grigri is clipped to another figure eight loop. Here the distance is fairly close to the anchor, but this rigging technique is most useful for greater distances between the anchor and your desired belay stance, limited only by the length of available rope. The big advantage is visual contact with your climber in situations where the anchor is some distance back from the edge.



Students practice rigging a uniform load anchor system using double loop figure eights. The master point is tied with a BHK.

easy conversion to a raising system if required, and it's easy to lower someone on this setup by redirecting the brake strand on the Grigri.

Notes on Load Distribution

Most toproping situations involve an anchor that is uniformly loaded in a single direction. This is true of top-managed and base-managed climbs. Most anchor systems involve components that have comparable strength: a pair of bolts, a trio of cams in a similar size range, a combination of strong natural and removable components. In these cases, load distribution is fairly simple. A cordelette and 48-inch slings allow an anchor builder to pull tension on the components and tie a strong overhand or figure eight knot to ensure that the load is theoretically distributed to all the components. But in this configuration these anchors have been proven to have misleading load distributions. They do not in fact equalize the total load between the components. John Long argued this point compellingly in *Climbing Anchors.* John maintained that even if one could achieve equalization, the slightest shift in the direction of load would

Four-piece uniform load anchor pre-equalized with a cordelette in the anticipated direction of load. If the load shifts even slightly, all of the load will come to bear on a single piece. If that piece were to fail, the vector would shift to the next piece to load, albeit with minimal extension from the cordelette. The cordelette system is essentially a series of backups rigged with minimal extension.





This toprope anchor, rigged using the Joshua Tree System, is an example of a variable load (aka self-equalizing) anchor system.



Each leg of the V is connected to two camming devices rigged with magic Xs and load-limiting knots on 48-inch nylon slings. If the direction of load shifts slightly, the magic Xs will adjust accordingly to distribute the load on each leg of the V.

distort that equalization. He further noted that even if the load was 100 percent uniform and equalization was 100 percent perfect, he would still suggest to the anchor builder that not all the components are of equal merit, deserving an equal share of the load. When necessary, a more effective anchor builder ignores the idea of equalization and intentionally manipulates the distribution of the total load. In the following examples we will describe simple, timely systems that are most appropriate when complex load distributions are not necessary, as well as more complex systems used to intelligently distribute load to components when the load varies in direction and the components are not equally strong.

The Cordelette: A simple solution to a common anchoring problem

The cordelette system is an attachment system where the anchor builder ties off the cordelette in the anticipated direction of load. If the direction of load shifts slightly in any direction, all the load goes onto one placement (albeit with minimal extension). For toprope anchor systems, in most cases it is simple to determine the direction the anchor system will be loaded in, so a simple solution like the cordelette makes sense most of the time. Using the cordelette in this manner, the anchor builder essentially creates a system of backups. If one piece fails, the load transfers instantly to the remaining pieces with minimal shock loading, since the rigging limits extension.

The cordelette can be used to attach two, three, four, or even five placements to a master point, so it is versatile as well as simple. For two placements, like a two-bolt anchor, start by doubling the cordelette, then clip the doubled strand into both bolts with a pair of carabiners. Pull down between the bolts in a manner that targets the anticipated load, gather all the strands together, and tie an overhand or figure eight on a bight. There should be four strands of cord at the master point.

To rig three or four placements, clip the cordelette into all the placements, pull down between the



Simple two-bolt anchor rigged with a Tech cord (5,000 pounds tensile strength) cordelette. The cordelette is doubled to start with, producing four strands at the master point loop, and the climbing rope is clipped into three oval carabiners opposed and reversed.

pieces in a manner that targets the anticipated load, gather all the loops together, and tie an overhand or figure eight on a bight. Many instructors like to clip a carabiner into all the gathered loops and pull in the anticipated loading direction, then tie a figure eight knot with the carabiner attached to help even out all the strands.



Demonstration of pre-equalized cordelette with three anchor placements, tied with a 7mm nylon cordelette. A clove hitch has been tied to the top left piece to keep the double fisherman's knot away from the end loops. This is a simple and effective rig as long as the direction of load is predetermined, which is most often the case when toproping.



This four-piece anchor is pre-equalized with a 7mm nylon cordelette. The overhand knot creates a four-loop master point to which the two opposed and reversed locking carabiners are clipped.

Rigging a Cordelette



An 18- to 20-foot-long cordelette is usually long enough to equalize three or four anchor points, as long as they are not spaced too far apart. Use a sling or two if necessary to get all the carabiners you'll be clipping into within a workable range. Clip a single strand of the cordelette into each carabiner, then pull down between the pieces and gather the loops (with three pieces you'll have three loops). Clipping a carabiner into the loops before tying the knot will make it easier to equalize all the strands. Tie a figure eight knot to create your master point, which should be roughly 3 to 4 inches in diameter. If you don't have enough cord to tie a figure eight, an overhand knot takes up less cord.



The drawback of the cordelette system (left) is that if the direction of the anticipated load changes, one piece in the anchor takes all the load (right). Think of the cordelette system as a system of backups: If the one piece that is loaded fails, the load goes onto the next piece with relatively minimal extension in the system. For toproping anchors, since the load on the anchor system is relatively low, the cordelette system has the advantage of being easy to use and simple to rig, negating any potential for shock loading.

The Sliding X

The sliding X (aka magic X) is a simple way to distribute load to two anchor points with a sling, creating an anchor system that adjusts as the load shifts in one direction or another. If using the sliding X with a long sling (like a sewn, 48-inch double-length sling), it is possible to minimize extension by tying overhand knots just above the clip-in point. This allows the system to adjust, but limits any extension if one piece fails. Or two single-length slings can be used together with a sliding X, creating a redundant rig with minimal extension.

Rigging a Sliding X



Use a single sling to create a self-equalizing system that adjusts with changes in the direction of load.



As an anchor system, this rigging is not redundant. For the sling itself to be redundant, there must be an overhand knot tied on both sides of the sliding X.



A simple two-bolt anchor can be rigged with a sliding X using two slings and two locking carabiners at the master point for a redundant, self-equalizing system. With a two-bolt anchor, many instructors use locking carabiners on the bolt hangers too. The drawback of this rig is that if one bolt were to fail, the system would extend to the length of the slings. As a general rule of thumb, limit the maximum extension in your anchor system to half the length of a single (24-inch) sling.

The Quad

The quad is a slightly more complicated system for a variable load direction using a cordelette. It's a great system to use for toprope anchors. It gives near perfect equalization with minimal extension and great strength. To rig the quad, start by doubling a cordelette, then grab the middle with the fist. Tie an overhand knot on each side of the fist, and it is ready to rig. Clip the double-strand loops into the bolts with locking carabiners, then clip only three of the four strands at the master point, leaving one loop outside the master point carabiners. This ensures that if one bolt fails, carabiners remain clipped into a pocket on the master point.



A two-bolt anchor rigged with a 7mm cordelette and the quad system.



The cordelette is clipped directly to the bolt hangers with locking carabiners, bypassing the cheap hardware store lap links (which are only rated at around 1,000 lbs.).



Detail of quad rig master point with three ovals opposed and reversed.



Detail of quad rig with two locking carabiners opposed and reversed.

Stacked Sliding Xs

This gives you a complex rig for a variable load with slings. Occasionally an anchor builder encounters anchor configurations that have components with very different strengths. Imagine a narrow 4-inch crack that immediately closes to a ½-inch crack running along the top of the crag. An effective anchor builder understands that a 4-inch SLCD is much stronger and has a much higher margin of error in its placement (due to its large camming range). By comparison, ½-inch SLCDs are weaker and have a minuscule camming range. These components are not equally strong, and therefore distributing load to them in an equal manner would not take advantage of their relative strengths and weaknesses. In other words, equalizing the pieces would not be an intelligent distribution of the load. An effective alternative would be to build a sliding



Here the green sling equalizes two components of lesser strength than the top right piece. Although this anchor system achieves good equalization and logical load distribution, it is not redundant because the red sling is not redundant at the master point.



The rigging is now made redundant by tying an extension-limiting overhand knot on each side of the sliding X, although the green sling will not minimize extension.



Here the rigging is redundant with minimal extension. The two pieces on the left have been equalized with the red 48-inch nylon sling, using a sliding X and extension-limiting overhand knots. The yellow 48-inch nylon sling equalizes this point to the single, strongest piece in the anchor, again with a sliding X and extension-limiting overhand knots.

X with load-limiting knots between the two ½-inch SLCDs, creating a mini–master point. Then a second sliding X with load-limiting knots would connect the 4-inch SLCD to the first sliding X, to that mini–master point.

The Equalette

The equalette is a complex rig for a variable load direction using a cordelette. It gives the anchor builder four strands, or "legs," running from the master point to the various pieces in the anchor



The equalette rigged with a 7mm nylon cordelette. This is a versatile system to use for equalizing three or four placements, giving you redundancy, equalization, and no extension. The only drawback is in its complexity and the fact that it does not have one singular master point to clip into. Here the equalette is rigged to four placements, using the various "arms" of the cordelette attached with clove hitches for easy adjustment.



Detail of the equalette master point using two locking carabiners opposed and reversed.



Detail of equalette master point rigged with a Dyneema sling. Tying an overhand knot in a Dyneema sling reduces its strength by 50 percent; it's better to use a 7mm nylon cordelette when rigging the equalette, as you'll be tying lots of knots.



Detail of an equalette toproping rig tied with a doubled cordelette for a two-bolt anchor.

matrix. These four legs can be tied to the pieces with figure eights, clove hitches, or double loop knots like the double loop eight or double loop bowline.

To tie an equalette rig, form a U shape with the cordelette and grab the bottom of the U, positioning the fisherman's knot on the cordelette about 18 inches away from the bottom of the U. Tie an overhand knot on both sides of your fist, about 10 inches apart.

At the master point there will be two separate loops. Clip into each loop with a separate locking carabiner.

Vectors

A vector is a quantity that incorporates both direction and magnitude. Picture a tightrope walker balancing out on the middle of a wire. If he weighs 200 pounds, the load at each end where the wire is attached will be roughly 1,000 pounds. Why is this? When two anchor points are equalized, as the angle of the wire, sling, cord, or rope approaches 180 degrees, the forces at the anchor points increase drastically. When the angle is narrow, the load is distributed at around 50 percent to each anchor.

Keep this in mind when building toprope anchor systems. If the angle between two anchor points reaches 120 degrees, the load at each anchor is 100 percent. Strive to keep all the angles under 60 degrees to split the load roughly 50/50. A good way to help guarantee an intelligent load distribution is to keep the angles in an attachment system under 90 degrees. Also, avoid rigging a sling between two anchors in a triangular configuration (called the American Triangle), which, even at 90 degrees, places 1.3 times the force at each anchor point. An American Triangle rigged at 120 degrees would almost double the load at each anchor point!


ANCHOR POINT
ANCHOR POINT
120°
100 lb to each anchor
80°
70 lb to each anchor
40°
54 lb to each anchor
20°
50 lb to each anchor
100 lb LOAD

This diagram illustrates how a 100-pound load is distributed between two anchor points at various angles. Keep the angle between two anchors as narrow as possible, striving to keep it under 60 degrees. At 120 degrees the load is 100 percent at each anchor! Think of 0 to 60 degrees as ideal, 60 to 90 degrees a caution zone, and over 90 degrees a danger zone.

American Triangle

Load per anchor with 100 lbs. of force

Bottom Angle	**V Rigging**	**Triangle Rigging**
30 degrees	52 lbs.	82 lbs.
60 degrees	58 lbs.	100 lbs.
90 degrees	71 lbs.	131 lbs.
120 degrees	100 lbs.	193 lbs.
150 degrees	193 lbs.	380 lbs.



The American Triangle rigged at a rappel anchor. Avoid rigging with a triangle configuration—it adds unnecessary forces to your anchor points. Stick to a V configuration for lower loads.

CHAPTER 9

Advanced Anchor Rigging Systems and Institutional Anchors

In the previous chapter, fundamental anchoring principles were discussed with strategies to create an unquestionably effective attachment point. Those principles will carry an anchor builder through all disciplines in climbing. The Single Pitch Instructor, however, will also require further skills for establishing an anchor and setting a toprope, because there are a few challenges that are unique to a Single Pitch Instructor's terrain:

1. Sometimes the components in an anchor, natural or otherwise, are far apart from each other, too far for a cordelette or a 48-inch sling.
2. The cliff's edge is an especially dangerous place for an instructor who is trying to keep safe and supervise participants.
3. When working at the base of a climb, a master point of the anchor has to be positioned in a place that is hazardous, such as over the cliff's edge.

Using a Setup Rope: Components Far Apart

Thankfully, a Single Pitch Instructor can bring along extra tools for anchor building. Unlike a multi-pitch or alpine climbing team, a single pitch team can afford to carry a little bit of extra weight. A length of static or low-stretch rope is worth every ounce of extra weight. To use it effectively and efficiently, an instructor should be able to stand at the site of the intended master point, look back into the terrain, select potential components, then use the setup rope to connect those components to the master point. A common sequence might proceed as follows:

1. Determine the climb and a distance from the cliff's edge directly above the climb where there is little risk of falling over the edge.
2. Face the terrain and use raised arms to target potential components (trees, boulders, removable and permanent protection). Let the arms forecast the vectors the setup rope will eventually create to make sure component selections are not too far apart.
3. Flake out the rope and take the end of the rope out to the most distant component. Attach the rope to that component in whatever manner is most efficient and effective.
4. Leave enough slack at the site of the intended master point to tie a BHK, then take the remaining bight of rope back to the other component.
5. Once both components are connected, a closed U shape awaits the anchor builder at the site of the intended master point. Use this bight of rope to tie a BHK that distributes load to the components along the anticipated direction of pull (toward the climb).

This sequence of connecting a setup rope to components and tying a BHK has limitless variations. Becoming efficient takes practice.

Instructor Tether: Managing Risk at the Cliff's Edge

Most climbers and climbing instructors alike have become familiar enough with the danger of the cliff's edge that their balance, their attentiveness, and their caution allow them to monitor and regulate proximity to a drop-off. Climbing instructors, however, cannot rely entirely on these skills because they are also supervising their students, observing the environment, and trying to complete setups efficiently. In other words, they are more distracted,



A simple tether using a cordelette. The instructor has girth-hitched the 7mm nylon cordelette through both tie-in points on the harness (then clipped to an anchor with a locking carabiner.



Here the cordelette has been threaded through both tie-in attachment points and tied with an overhand knot for redundancy to create a simple tether.



A simple tether using the rope tied with a clove hitch at the anchor.

and distraction is very dangerous indeed. Fortunately, climbing instructors have many options to secure themselves when in proximity to a cliff's edge; they can construct some form of instructor tether.

- Fixing a section of rope to an anchor allows an instructor many tethering options—using a Grigri, an ATC with friction hitch backup, a clove hitch, a full-strength sling with a klemheist, or even tying in to the rope.
- Any number of slings and cordelettes might work nicely to create a long leash. Instructors can girth-hitch one end of a closed loop to the harness and attach the opposite end of the loop to the master point.
- The climbing rope itself is always an obvious tethering tool. Instructors can easily tie in with a figure eight follow-through and then attach the climbing rope to the anchor with a clove hitch.

When using a Grigri on an instructor tether, tie an overhand knot backup whenever you take your brake hand off the rope. Always tie a stopper knot in the end of a rope tether to close the system.



Extensions: Creating a Master Point Over the Cliff's Edge

Once an instructor has a master point and a tethering method, it may be necessary to create an extension for a secondary master point, which will allow a base-managed toprope to run through a pair of carabiners free and clear of the cliff's edge. Many instructors refer to this secondary master point as the action point, or hot point. Either way, since it is a part of the anchor, the same fundamental principles that govern the master point should also govern the extension. For a typical extension, the instructor might attach a section of static or low-stretch rope to the initial master point with an overhand or figure eight loop then feed out a loop of slack that hangs over the cliff's edge, closing the long loop with another overhand or figure eight loop. Now, using the tether, an instructor can comfortably and securely set up a position at or just over the edge to tie a BHK. This is the point where the climbing rope will finally be placed.

Systems Using a Setup Rope

Aside from being the best tool for the individual tasks mentioned so far, a setup rope further proves itself as an elegant and efficient anchoring tool because it can be used to accomplish all three tasks—combine components, build tethers, and create extensions. When the full range of possibilities are understood by a climbing instructor, certain patterns emerge in the use of the tool; we call those patterns "systems." It should be understood, however, that the most elegant and efficient use of the tool often involves a combination of the techniques demonstrated. An instructor will want to explore the most applicable terrain, the programmatic options, and the economy of materials used for each technique when deciding how to use the setup rope to build a given anchor.

The Joshua Tree System—V Rigging with Extension Rope

Most anchors in Joshua Tree National Park in California require gear placements set well back from the cliff's edge, and bolted anchors are a rarity. Out of necessity, instructors at Joshua Tree developed a system to rig toprope anchors that is both efficient and redundant, using a length of low-stretch rope.

To rig the Joshua Tree System, visualize a V configuration, with two separate sets of anchors on the top of the V, and the point, or bottom, of the V being the toprope master point over the edge of the cliff. Ideally, the angle of the V should be as narrow as possible—at least less than 90 degrees. Once you have determined where the climb is and where you want your master point, picture the V in your mind and begin to set your anchors. If using natural anchors, it could be as simple as two trees. For simplicity let's say we have two anchors: anchor A and anchor B. Start by attaching one end of your static rigging rope to anchor A. This can be done either by using a sling or cordelette and a locking carabiner to a figure eight loop, or by tying the rope directly around the tree. (The re-threaded bowline works well for tying a rope to a tree.)

Now, to increase security as you approach the cliff's edge, protect yourself by taking a 48-inch nylon sling and attaching it to your rigging rope with a klemheist knot. The 48-inch sling with klemheist is an excellent full-strength tether option in this system; be sure to attach the sling to the belay loop with a locking carabiner. A nylon sling is better for this application because nylon has some stretch, whereas Spectra or Dyneema are static (like a wire cable) and have no stretch. Now you can slide the klemheist knot up and down the rigging rope to safeguard yourself as you work near the edge. Tie a BHK so that your master point dangles just over the lip of the cliff's edge, positioned directly above your chosen climb. Attach your climbing rope with carabiners (either two opposed and reversed locking, or three opposed and reversed ovals) and run the rope back to anchor B, attaching it with a clove hitch to a locking carabiner. This will allow you to adjust the tension and fine-tune the load distribution.

The Joshua Tree System allows the anchor builder to tether to a leg of the anchoring system. That's why the klemheist and 48-inch nylon sling is an important selection for tethering—any other method would not allow the anchor builder to precisely position the master point. But it is almost exclusively a system used for base-site climbing anchors, since neither of the component anchors are positioned directly above the climb and the master point itself is positioned so far below the edge of the climb that top-site management would be impractical. The Joshua Tree System also boasts excellent material economy. It only requires enough material to extend out to the cliff's edge; that is, two times the distance between the component anchors and the edge (with a little extra for knot tying).

Personal Preference

I (BG) prefer to tie both legs of the V into anchor points using figure eight loops. I know from experience that the BHK takes about 4 feet of rope to tie. So I'll tie both ends of the V first, with about 4 feet of the extension rope dangling over the edge, weighted down by a few carabiners to find my equalization point. Then I'll pull the point of the V back up and tie my BHK last.



Proper use of a friction hitch for security while rigging a toprope. Here the instructor is tethered with a 48-inch nylon sling, attached to one leg of the setup rope with a klemheist knot and clipped into the harness belay loop with a locking carabiner.



Overview of the Joshua Tree System. The right "leg" of the extension rope is attached with a figure eight loop to a locking carabiner clipped to a master point on a three-piece anchor pre-equalized with a cordelette. The left leg of the extension rope goes to a two-piece anchor pre-equalized with another cordelette, attached with a clove hitch on a locking carabiner for adjustment of the extension rope. A BHK is tied for the master point, with two opposed and reversed locking carabiners ready for the climbing rope.



Close-up of the master point on the Joshua Tree System using a BHK and three steel oval carabiners with the gates opposed and reversed.



Toprope all day long with your extension rope rubbing on a sharp edge . . .



. . . and you'll end up with a seriously abraded rope like this one.



A commercially made edge protector, like this one sold by Petzl, is a wise investment. Attach it to the rigging rope with a friction hitch.



This finished rig illustrates the simplicity of the Joshua Tree System, with the lower leg connected to two anchors using a double loop figure eight. The upper leg was connected last, using a clove hitch to a locking carabiner for equalization, attached to two pieces and a doubled sling. Note the edge protector guarding both legs of the extension rope from abrasion.

Take care to make sure the extension rope is not resting over sharp edges at the lip of the cliff. This setup is an "unmonitored" anchor system, which means that once rigged, the climbing instructor will be at the base and not able to watch what is happening at the anchor—like the extension rope abrading over an edge, so take special care to prevent this by padding the edge; a pack or rope bag will work or, better yet, use commercially made edge protectors.

If you learn to tie double loop knots like the double loop figure eight and double loop bowline, along with the in-line figure eight, you'll be able to eliminate many slings and cordelettes from your anchor system and become more efficient in your rigging.

The Lifeline System—V Rigging with Instructor Tether

This is a variation of the Joshua Tree rigging method. Instead of tethering with a klemheist and a 48-inch sling, an instructor may find it advantageous to tether with a fixed section of rope. While the Joshua Tree System attaches the end of the rope to one of the component anchors, the Lifeline System attaches a figure eight with a bight so that two load-bearing strands are available for use. The one strand is only long enough



Example of V rigging with a tether. Each leg of the V consists of two bomber pieces. The bottom leg is equalized to the two placements with a double loop bowline, and the top leg (with tether) is equalized with a double loop figure eight.

to access the cliff's edge and serves as an instructor tether, while the second becomes the same leg of the anchor system that the Joshua Tree System utilizes. The important concept to remember here is that the tether should be clipped into a bona fide, redundant anchor—not just a single piece of gear.

An astute instructor should immediately conclude that this variation of the Joshua Tree System does not have the same material economy as its forbearer. While the Joshua Tree System only requires two lengths of material to connect the component anchors to the master point, the Lifeline will



Here the instructor has rappelled using an instructor tether to approach the edge in low-angle but exposed terrain to make some adjustments on his BHK master point toprope rig. Whenever you take your brake hand off the Grigri in low-angle terrain, tie a backup knot (overhand loop) as shown here, because if you unweight the Grigri, the rope can slide through. Always tie a stopper knot on the end of your tether before you begin using it.

require three, with a little extra for knot tying, of course.

Instructors may find the Lifeline to be an effective system if the other half of the anchor, the second component anchor, is in a precarious or inaccessible place. The Lifeline would provide access to those components so that the anchor can be completed. The Lifeline is also an excellent tool for probing an ambiguous cliff's edge to pinpoint the location of the climb. Lastly, the Lifeline might be an excellent tool to access anchoring hardware normally intended for sport climbing use. Such anchors are typically installed over the cliff's edge, where access from above may not only be atypical, but dangerous without the Lifeline System.

The Backside System—Pre-Equalized Extensions

Unlike the Joshua Tree or Lifeline Systems, the Backside System preestablishes a space for both a top-managed system and a bottom-managed system at the same time. In the simplest terms, this is done by setting up a V configuration and tying two BHKs into it. The top BHK becomes the master point for top management. The backside of that top BHK should be long enough to droop over the edge of the cliff, where a second BHK is tied. The bottom BHK then becomes the master point for bottom-managed operations.

Similar to the Joshua Tree System, an instructor will be tethered to a leg of the anchor system. A 48-inch nylon sling tied as a klemheist is a logical choice for tethering.

The Backside System can boast certain material economies that the Joshua Tree and Lifeline Systems cannot because it does require entire component anchor points. It presumes that the initial master point will be positioned above the climb. But its greatest strength is its programmatic versatility. As mentioned, it can easily be used for top-managed sites as well as base-managed sites. Furthermore, when built in anticipation of both kinds of activities, it allows the instructor to quickly transition from one to the other.

Rigging the Backside System

1. Configure a Joshua Tree V with a loop of rope hanging over the edge of the cliff. Make sure to estimate for the amount of rope that will be eaten up by the dual BHKs.
2. Determine where you would like your top-managed high master point to be and tie a BHK there. The backside of the BHK should be long enough to hang over the edge of the cliff.
3. Tie a second BHK in the loop that hangs over the edge. There are two options to secure the toprope BHK: Pass the BHK through the backside of the knot or clip all three loops of the BHK into the toprope carabiners.
4. Use a klemheist with a 48-inch nylon sling to tether to one of the ropes directly below the high master point. Do not clip into this friction hitch until you are ready to make a transition to the bottom.
5. If operating from the high master point, pull the backside of the high master point up and stack it out of the way.

Making the Transition from Rigging to Rappelling

When using any of the aforementioned systems, if you decide to rappel to the base, you will need to transition from some tethering tool to rappelling. In all three systems, it is reasonable to tether over the cliff's edge to access the climbing rope. Fixed sections of rope with ABDs make this transition quite easy, because the instructor can rappel over the edge instead of downclimbing while adjusting a klemheist. Once in position over the cliff's edge, pull up your doubled rappel rope, rig your rappel device, and back it up with an autoblock. Once the rappel is correctly rigged and double-checked, the original tethering system may be deconstructed.


LARGE LIVE TREE
LOCKING CARABINER
FIGURE EIGHT on a bight
REMAINING length of rope
HIGH MASTER POINT
KLEMHEIST used for transition from HIGH to LOW point
48-inch sling
BHK KNOT
2 LOCKING CARABINERS reversed and opposed
LOW MASTER POINT
TOPROPE

The Backside System.

MIKE CLELLAND



AMGA Single Pitch Instructor Richard Riquelme managing a climber on a Backside System. Note that the pre-equalized strands are uphill and out of the way.

JASON D. MARTIN

Loading the Backside of a BHK

It may strike an instructor as unusual to load the backside of a BHK in this manner. Although this application does not conform to the way instructors have typically seen a BHK in use, it is an acceptable way to load a BHK. It is essentially a double flat overhand. As long as the resultant BHK loop is either in use or adequately long enough, it is highly unlikely that a climbing team could create a load large enough to compromise the backside use of the BHK.



Making the transition on an instructor tether with an ABD. The instructor pre-rigged his rappel device—extended on a doubled nylon sling and backed up with an autoblock knot attached with a locking carabiner to his belay loop. Once he descends on the tether below the master point and weights his pre-rigged system, he can double-check everything before unclipping the Grigri.



Making a transition with a 48-inch sling attached to one strand of the rigging rope with a klemheist knot. The rappel device is backed up with an autoblock. This technique could be used to transition to a rappel using the Backside or Joshua Tree Systems.

The Three-in-One System

Popularized by Adam Fox during his tenure as the AMGA's SPI Discipline Coordinator, the Three-in-One System was conceived as an efficient rigging system for professional instructors that addresses the needs for instructor security, top-managed scenarios, and easy conversion to a bottom-managed site. Instructors around the country have learned to appreciate its signature elegance, since it manages to anchor, create an instructor tether, and create an extension with the same rope. Three tasks with one rope: Three-in-One.

Even in its simplest configuration, the Three-in-One System will require enough rope to accomplish all these tasks. An instructor can anticipate the amount of rope needed by multiplying the distance between the components and the cliff's edge by three. If the components are farther from the cliff's edge than a third of the setup rope length, the Three-in-One System may not be effective.

Start by building a high master point in much the same sequence as previously discussed:

1. Locate the climb and a distance from the cliff's edge directly above the climb that reduces the risk of falling over the edge.
2. Face the terrain and use raised arms to target potential components (trees, boulders, removable and permanent protection). Let the


LESS THAN 90°
HIGH MASTER POINT
BHK KNOT
LOCKING CARABINERS
LOOP KNOT
RIGGED with ONE ROPE
THE THREE-IN-ONE SYSTEM
INSTRUCTOR TETHER
BHK KNOT
3 OVALS
STOPPER KNOT
TOPROPE

The Three-in-One System.

MIKE CLELLAND

arms forecast the vectors the setup rope will eventually create to make sure the component selections are not too far apart. Keep in mind that a narrow-angle V configuration (or at least less than 90 degrees) is the goal.

3. Flake out the rope and take the end of the rope out to the most distant component. Strive to use the setup rope alone to attach the component. Bowlines can be very helpful.
4. Leave enough slack at the site of the intended master point to tie a BHK, then take the remaining bight of rope back to the other component. Again, try to attach the bight directly to the component to avoid using some other tool; a bowline with a bight works well for this application.
5. Once both components are connected, a closed U shape awaits the anchor builder at the site of the intended master point. Use this bight of rope to tie a BHK that distributes the load to the components along the anticipated direction of pull (toward the climb).

Anchor Redundancy

In both of the illustrations included in this chapter, the rigging rope is tied off to two different bombproof anchor points. This is not a requirement. The rigging rope could go to two different anchor points, or it could go to a single solid anchor. For example, if you have a giant tree or a solid multi-piece traditional anchor, there is no need to build a second anchor. Both strands of the rigging rope could be attached to the same master point.

Now that the master point is built, use what is left of the setup rope to construct the rest of the system. Start with the instructor tether:

1. Since one end of the setup rope is tied to the most distant component, take the other end and tie a stopper knot.
2. Toss the stopper-knotted tail of rope so it hangs down about 10 feet below the cliff's edge.
3. With this distance measured, affix the rope to the master point using a figure eight loop and a locking carabiner.
4. With the attachment of a Grigri or assisted braking device, this fixed length of rope will be the instructor tether.

Next, an extension can easily be created using the rope that remains.

1. From the backside of the instructor tether, feed out a loop of slack that hangs over the cliff's edge.
2. Close the long loop with another overhand or figure eight loop.
3. Now, using the tether, an instructor can comfortably and securely position themselves at or just over the edge to tie a BHK.

Stepping back, an instructor should see that the entire system—anchor, tether, and extension—has been tied with the same setup rope.

Making the Transition from Rigging to Rappelling

To rappel back to the base, use the instructor tether to facilitate a secure, easy transition to a pre-rigged rappel. Simply pull up the doubled rappel rope, rig a rappel device, back it up with an autoblock, then rappel on the instructor tether with a Grigri until the rappel is tight to the pre-rigged rappel setup. Double-check the rappel device and make sure the autoblock is grabbing, then finally unclip from the Grigri and proceed with the rappel.

CHAPTER 10

Risk Management at the Crag

Every year the American Alpine Club publishes *Accidents in North American Mountaineering,* detailing significant climbing accidents for the year in a comprehensive analysis. Studying what happened to other climbers can heighten an instructor's awareness of what to watch out for to avoid a mishap. John Dill, head of Yosemite's Search and Rescue (SAR) team, studied the most serious climbing accidents that happened in Yosemite Valley from 1970 to 1990. During that time fifty-one climbers died in accidents, 80 percent of them, Dill estimates, "easily preventable." In his article "Staying Alive," Dill points out that state of mind is the key to effective risk management: "It's impossible to know how many climbers were killed by haste or overconfidence, but many survivors will tell you that they somehow lost their good judgment long enough to get hurt. It's a complex subject and

INSTRUCTOR
AREA

Sign at Mountain Warfare Training Center, Leavitt Meadows, California.

Inattentional Blindness

Inattentional blindness is a term psychologists use to describe the neurological phenomenon that occurs when the brain fails to see something obvious, when attention is distracted or focused on something else. Psychologists who study multitasking have found that most of us aren't the multitaskers we think we are: Our brain is simply switching back and forth from one activity to another, deactivating one area of focus to process the other task. In my (BG) role as an examiner for guides' certification exams, I've seen examples of inattentional blindness many times during complicated technical scenarios, where the instructor has moved his focus without seeing an obvious error, like a carabiner unlocked at a key belay or rappel device. It's as if the mind skipped a step, or the brain said that everything was correct and complete, when in fact it wasn't—a cognitive blind spot.

Psychologists theorize that once the brain determines what is important, it fills in the picture with whatever your expectations believe should be there. These failures of awareness happen to all of us, at one time or another, but we're not aware of them, so we don't realize what we've missed! A systematic and routine checklist is helpful, but what we really need to learn to look for is what might be wrong, not what looks right.

Pat Ament, the great Colorado climber of the 1960s and 1970s, writes in his book *Rock Wise:* "As with all of climbing, it is attitude that saves or kills. There is no better beginning than within the mind, in the form of complete concentration. There is no room for oversight or for dismissing what is logically understood. Keen intuition must evaluate all which strikes both mind and eye. Preparing . . . is a process of reasoning and advancing through a regular chain of tests until a synthesis reads go."

sometimes a touchy one. Nevertheless . . . at least three states of mind frequently contribute to accidents: ignorance, casualness, and distraction."

Proper risk management in the single pitch environment involves identifying and assessing hazards, making the right decisions to avoid these hazards, then implementing controls and supervision to minimize the risks.

Rockfall

One environmental hazard is rockfall, which can be naturally occurring (caused by melting ice, wind, etc.) or more likely man-made, caused either by someone pulling off or stepping on a loose hold, or in most cases by a rope being pulled or dragged across the top edge or the face of the cliff. Dropped equipment is also a hazard. Setting up a helmet perimeter zone at the base of the cliff minimizes the danger, as does requiring students to not hang out at the very base of the cliff in the rockfall zone unless they are belaying or climbing. An explanation of the risk is appropriate (i.e., why you need to wear your helmet at the base and while belaying and climbing), as is an explanation of the universal verbal signal for a falling rock or dropped piece of equipment: "ROCK!" Being vigilant is the best strategy, especially when other climbers are directly above or at the top of the cliff.

Terrain Hazards

Another environmental hazard is the terrain itself. If working at the top of the cliff, falling off the edge is a real hazard, as is any steep and exposed terrain involved in scrambling up to the top. In very exposed situations a fixed line can be rigged. See chapter 14, Fixed Lines, for more information.

The base of the cliff also has terrain hazards. The ideal base for group classes would be perfectly flat, but this is often not the case or even possible. Showing students the proper approaches to the climb and belay spots and supervising them is important. Often the most dangerous aspect of taking a large group climbing in a toprope crag setting is their scrambling around on uneven terrain at the base of the cliff, unroped, where they aren't protected by a toprope. The use of ground anchors is important for the belayers in situations where there are chasms and drop-offs adjacent to the belay stances.

Closing the System

In the single pitch environment, the rope system should always be closed. This simple protocol will prevent many accidents during lowering and rappelling. A closed system means that both ends of the rope have a knot in them—either the end is tied into someone's harness, or a stopper knot is tied on a free end. This simple habit prevents the end of the rope from ever going through a belay or rappel device. Always close the system.

Systems Checks

The instructor is responsible for risk management for the entire group. A protocol for systematically checking every climber and belayer before every climb should be standard procedure. A commonly used system is to start with ABC: Check the ground anchor (if used), check the belayer, then check the climber. A proper systems check should be both visual and verbal. The instructor should be close enough to clearly see the harness buckle and rope tie-in. A verbal check is important because it lets the student recognize and learn what to check for. The best method is to have the students themselves go through the checks, with instructor supervision, to get into the habit of a mandatory systems check before every climb.

Anchor

Check the ground anchor to make sure the belayer is in a line between the direction she will be pulled in the event of a fall and the anchor itself. A good way to attach the belayer to the ground anchor is with a clove hitch to a locking carabiner (the end is tied to the front of the belayer's harness with the standard figure eight follow-through knot).

Belayer

Check the belayer's harness, to make sure it is buckled properly. Check the figure eight follow-through knot, to make sure that it is (1) tied properly and (2) threaded through the correct tie-in points at the front of the harness. Check the belayer's belay device, to make sure the rope is properly threaded through the device, and lastly, check the belayer's locking carabiner on the belay device, to make sure that it is locked. Check that the belayer is wearing her helmet.

Climber

Check the climber's harness, to make sure it is buckled properly. Check the climber's figure eight follow-through knot, to make sure that it is (1) tied properly and (2) threaded through the correct tie-in points at the front of the harness. Check to ensure the climber is wearing his helmet.

These checks are simple, but it is surprising how many times students are caught making a mistake somewhere along these lines. The instructor needs to do these checks before every climb. It's that simple. Go through the checks with the students until they learn what to look for, and have the belayer/

climber pair go through the checks themselves with instructor supervision.

New instructors might want to come up with an acronym to help remember what to look for, such as CRASH:

C = carabiner (squeeze check the locking carabiners)

R = rope (check to make sure the rope is not twisted at the top anchor, and check the knots)

A = attitude (check to make sure the climber is ready or has any questions)

S = stuff (check for any extraneous stuff on the climber that should be removed)

H = helmet and harness

Another common one is BARCK:

B = buckles on the harness

A = anchor (check the ground anchor)

R = rope

C = carabiners locked

K = knots

Whatever system is used, know what to check for, and be methodical.

Falling

With a sound toprope anchor, a good belayer, a proper tie-in, and good systems check, the biggest risks the climber faces during the climb are from falling. If the belayer is attentive and there is minimal slack in the system, the fall will be short and uneventful. For novices a demo on how to fall is important, showing them the proper position if a fall does occur: a wide stance with the legs, leaning back to weight the harness, not grabbing onto the rope, extending both arms outward against the rock, not clutching the rock or grabbing handholds.

The falls to guard against and watch out for are falls when the climber is too far to the right or left in relationship to the toprope anchor, which result in a swing or pendulum across the rock face; and falls when there is too much slack in the rope. Remember, if using a dynamic rope with a lot of rope in the system, rope stretch can be substantial (dynamic ropes stretch approximately 10 percent even in a toprope fall). When a climber is directly above the ground or a ledge, take particular care to

A discussion and demonstration on proper falling technique is appropriate for novices—feet wide, hanging in the harness, arms outstretched to brace against the rock, not grabbing the rope.



The right side of this toprope setup is clipped into a bolt that will act as a directional to prevent a falling climber from swinging.

ensure the rope is slightly under tension (especially if you are using a dynamic rope), to guard against rope stretch in the event of a fall.

A directional can be used to prevent a swing in the event of a fall. A directional is a separate piece of gear placed below and to the right or left of the main anchor. For example, if the start of the route is 20 feet to the right of the toprope anchor, and the climber falls near the bottom, he will swing 20 feet to the left during the fall (or even hit the ground). A solid piece placed directly in line above the start would be a directional, preventing the swing. When the climber reaches the piece, he simply unclips and continues to the top. As the climber is being lowered, he re-clips into the directional so that the climb is ready for the next climber.

Other Considerations

Climbing sites can be the habitat for things that sting and bite, both flora and fauna. Students should be informed of the hazard and given strategies to avoid an unpleasant encounter.

Weather is another hazard that must be considered. Instructors should check the forecast prior to the work day to ensure they and their students are adequately prepared for whatever weather conditions the day may bring. An excellent resource for regional and spot forecasts anywhere in the United States is the National Weather Service website: www.weather.gov.

CHAPTER 11

Top- or Base-Site Management for a Single Pitch

If an observer took a snapshot of recreational climbing teams around the country, he might begin to think that single pitch climbing has a default pattern. First, most climbers establish the climb; it is either led or the anchor is assembled and the toprope is tossed down from the top. The climber and the belayer are on the ground at the beginning and the end of the climb. Belaying seems to universally happen with the rope having been redirected through the anchor, and the belayer uses his or her own body as a counterweight, belaying directly off the belay loop. After the climb is over, someone has to clean the anchor.

It is inarguable that this single pitch paradigm predominates the climbing community, but instructors should appreciate that just because this arrangement is typical, it is not the only way to work a climb. In fact, many veteran instructors find the opposite arrangement, where the belayer lowers the climber down from the top of the climb, to be the most common arrangement in single pitch outings. For a professional instructor, neither arrangement should become the default setting. Every single outing, every crag, and every student requires a thorough instructor to make a choice: "Shall I work at the top of this climb, or shall I work at the bottom?" The goal of this chapter is to inventory all the options an instructor has when working in a single pitch setting, divulge the tools that are necessary to enable those options, and explore the criteria that an instructor would use to make an appropriate choice for his or her students.

Top-Managed Sites

Working at the top of a climb has many obvious advantages. For one thing, it may be the only way to work the crag. Many climbs are located along sea cliffs and riverbanks, on the rims of a canyon or cave, or at the top of a multi-pitch climbing area. For these kinds of climbing areas, the base of the climb is either inaccessible (hundreds of feet away), or there is water lapping against the bottom of the cliff. In each case, the climbing team will have to approach the top of the climb, build an anchor, lower a climber down, and have the climber climb back to the top.

When the instructor does have a choice, however, between the top and the bottom of a climb, there are still clear advantages to the top.

- The entire climbing team is rarely in danger of rockfall in an area accessed from the top.
- There is 50 percent less rope in the system, compared to a base site, minimizing rope elongation.
- Some climbers like climbing to the instructor.
- Belaying from the top allows an instructor to use an entire rope length when leading, opening longer pitches and huge stretches of terrain.
- The instructor can usually see the anchor system the entire time, monitoring components, sharp edges, and other users.
- An instructor already at the top of the climb can immediately clean the anchor, making the top site a more efficient way to work.
- The top site opens up programming options like rappelling.



A top-managed site at Joshua Tree National Park, California.

AMGA Single Pitch Instructor James Pierson top-manages a climber from a cliff in Washington's Larrabee State Park. Instructors working on a sea cliff have no choice but to work from the top.

TIM PAGE

There are clearly disadvantages to the top site as well. It is difficult or impossible to see climbers from above on many crags, and coaching individual moves is difficult. The climber's rope always goes over the edge when belaying from above, so sharp edges are particularly troublesome. Many cliff-top ecosystems are fragile and should not be unnecessarily impacted. Lastly, the cliff's edge is always close by, so instructors have to build technical systems to protect themselves and closely supervise participants who may try to venture too close to a precipice.

Because of these advantages and disadvantages in top-site work, instructors may find themselves preferring the top site for low-ratio work, especially in areas where lead climbing is the most common way to access the anchor. If there are only one or two students to manage, it is an efficient way to work.

When establishing a top site, instructors need to select an anchor and a stance that allows them to mitigate risks when approaching the cliff's edge (with a tether of some sort), recognizing that the space between the anchor and the cliff's edge is about to become a busy place. Instructors will be moving back and forth, students will be entering the system, rappels will be rigged, ropes will be stacked, etc. Instructors come to think of this area in front of the anchor as the "workspace," and that is an appropriate way to think of it. As a workspace, it should be clear of all superfluous equipment and personal items. As a workspace, tools should be logically arranged for easy access, or intentionally stowed. As a workspace, the things that happen there should have the tone of work: intentional, careful, and diligent. Students will need to be carefully instructed about where to stand and when and how it's okay to approach the cliff's edge.

Base-Managed Sites

Working from the base of the cliff has distinct advantages: There is no danger of anyone falling off the edge of the cliff, belayers are easily supervised, and climbers can be seen and coached on their way up the route. Recreational climbers will be most familiar with this arrangement, and it is most likely the system that they will default to using on their own, with friends, or in climbing gyms.

But hazards do exist for base-managed sites, such as rockfall and dropped gear. If the climbs are long, there is more rope in the system, so rope stretch can be a big hazard, particularly if a dynamic rope is being used for toproping.

Because of these advantages and disadvantages in base-site work, instructors may find themselves preferring the base site for high-ratio instruction. Groups can cheer on their friends, the outing has a social atmosphere, and multiple climbing teams can be supervised simultaneously. Furthermore, each climbing team can employ up to four student roles, so no one needs to sit idly by, waiting for their turn to do something. For any given climbing rope, one student will climb, one will belay, one can be a backup belayer, and one can serve as a ground anchor.

When should a ground anchor be used? If both the climber and belayer are roughly the same body weight and the terrain at the base of the cliff is flat, a ground anchor is unnecessary. But if the climber outweighs the belayer by more than 40 percent, a ground anchor should always be considered. A severe weight discrepancy will be even more obvious in low-friction setups, like overhangs. But friction, from a climber's body on a low-angled slab, or directional pieces that redirect the toprope, or the rope running over the rock itself, will help mitigate

The Ground Anchor

The worst accident I (BG) have had in thirty-five years of rock climbing happened when I was belaying in a toprope situation without a ground anchor. I was belaying from the base of the climb in a relaxed position about 15 feet out from the base of the cliff. Between the ledge I was belaying from and the cliff itself was a deep chimney. My partner was climbing on a toprope and suddenly fell while attempting an overhang about 50 feet above me. He swung wildly in the air. I easily caught the fall and locked off my belay device in the brake position, but I was pulled off my stance, swinging 15 feet straight into the wall like a pendulum. I braced for the impact with an outstretched leg and sustained a severely sprained ankle. A simple ground anchor would have prevented this accident. Belaying accidents are common, and in almost every case, they have the same element: no ground anchor.



This belayer is using a large block of rock for a ground anchor, ensuring she won't budge if the climber falls.

a severe difference in weight. Ground anchors rarely hurt anything. It is especially important to establish a ground anchor for the belayer in uneven terrain, particularly if the belay stance is perched high on top of boulders, or is some distance away from the base of the cliff.

A good system to rig a ground anchor is to start with the belayer tying in to the end of the rope. Not only does this "close" the rope system, but it allows the belayer to use the climbing rope to connect to a ground anchor with a clove hitch, which can be easily adjusted to suit the stance.

Natural anchors are obvious choices for ground anchors, like a sling or cordelette around a tree or a large block of rock. A single bomber cam or nut in a crack will also suffice. A seated student is an excellent choice for a ground anchor, especially if vegetation has been heavily impacted or other options are not available. The ground anchor student should be given a comfortable seat, like on top of a backpack.

The belayer in a toprope scenario will be pulled in a line directly to the toprope anchor master point, so he or she should be anchored and braced

AMGA_i-258_3pp_CS55.indd 191 2/27/14 11:58 AM

accordingly. Ideally the ground anchor will be low and directly behind or beneath the belayer or just slightly to the side. Remembering the ABCs may be helpful: anchor, belayer, climber. There should be a straight line between the anchor, the belayer, and the direction of pull created by the climber.

Belaying

Whether at the top-managed site or the base-managed site, belaying is a skill performed by students and instructors alike. It doesn't matter who is belaying or what they are belaying with, belaying is a very serious responsibility. It is a skill that instructors must understand, teach, and supervise.

All belaying has three irreducible principles that comprise the grounding theory of belaying; all the techniques discussed in this text will invoke these three key principles.

- The brake hand never leaves the rope.
- The hand transition should be made in a position of strength.
- The body should be positioned comfortably and sustainably.

Even before the popularization of manufactured belay devices, these principles were apparent. From device to device, the fundamental principles never changed. The hip belay was one of the original forms of the belay, and the principles used to make it work also apply to modern belay devices.

BELAY DEVICES

Today there is a wide variety of belay devices available. The most commonly used belay device is a tube or slot device (with two slots so it can be used for both belaying and rappelling on a doubled rope). A bight of rope is threaded through one of the slots in the belay device and clipped into a locking carabiner attached to the belay loop on the front of the belayer's harness. When the two strands of rope (one going to the climber, one to



Black Diamond ATC belay device.



Black Diamond ATC XP in high-friction mode with the teeth on the braking side.

The "Dreaded" Hip Belay

I (BG) began climbing before the advent of the belay device. Back in the 1970s we used the "hip belay" technique to catch a fall, which was simply wrapping the rope around your waist to generate enough friction to stop a fall. Catching a climber on a big "whipper" was painful indeed, and I often ended a hard day of climbing with a black streak singed across the back of my waistline.



To take in rope, start with the brake hand at your hip and the guide, or "feel," hand extended.



To take up slack, the brake hand goes out as the guide hand comes in.



The guide hand reaches above the brake hand and pinches the rope . . .



. . . so that the brake hand can slide back.



In the event of a fall, the brake hand brings the rope in front of the waist for maximum friction.

Standard Climbing Signals

A methodical systems check along with proper use of the universal climbing signals are integral parts of climbing. Ambiguity in the use of climbing signals has led to many tragic accidents, simply because of lack of communication between the climber and belayer. One infamous tragedy occurred at a popular ice climbing area, in a toprope setup, when the climber reached the top of the climb (at the top of the cliff) and the anchor. The climber yelled, "I'm OK!" but the belayer thought he heard, "Off belay." The belayer unclipped the rope from the belay device and took the climber off belay, thinking he was going to walk off the top. The climber leaned back to be lowered and fell to his death.

On a base-managed toprope climb, it's important to be vigilant at the transition from the climb up to the lower down. This is where most accidents due to improper communication and climbing signals occur. There should be no ambiguity. Many instructors hold onto the strand of rope that goes back down to the belayer until sure that the belayer has heard the command and is in the brake position and ready to hold weight. In most cases the instructor will be within visual contact, so in addition to hearing the verbal commands, the instructor should also look down and visually verify that the belayer is being attentive, with the brake hand in the proper position, alert and ready to lower in a controlled manner. In situations where climbing with other parties around, it's best to include the belayer's name in the signal (e.g., "Off belay, Bob.") to prevent confusion.

Here are the standardized climbing signals used in many climbing schools:

On belay?: Climber to belayer, "Am I on belay?"

Belay on: Belayer to climber, "The belay is on."

Climbing: Climber to belayer, "I'm beginning the climb."

Climb on: Belayer to climber, "Go ahead and start climbing; I have you on belay."

Up rope: Climber to belayer, "There is too much slack in my rope. Take up some of the slack." (Too much slack in the belay rope will mean a longer fall. Remember that rope stretch also contributes to the total distance of a fall, especially when there is a lot of rope out in a toprope scenario.)

Slack: Climber to belayer, "Give me some slack, the rope is too tight."

Tension (or Take): Climber to belayer, "Take all the slack out of the rope and pull it tight; I am going to hang all my body weight on the rope." (This could be a situation where the climber simply wants to rest by hanging in the harness while weighting the rope, or a toprope situation where the climber is getting ready to be lowered back down a climb.) Be careful with the word "take" as it can be misheard as "slack" or "safe."

Tension on (or I've got you): Belayer to climber, "I've taken the rope tight, and my brake hand is now locked off in the brake position, ready to hold all your weight."

Lower me (or Ready to lower): Climber to belayer, "I'm in the lowering position [feet wide, good stance, sitting in the harness, weighting the rope, and leaning back], and I'm ready to be lowered."

Lowering: Belayer to climber, "I'm proceeding to lower you."

Off belay: Climber to belayer, "I'm safe. You can unclip the rope from your belay device and take me off belay." (Never take someone off belay unless this signal has been heard. The universal contract between belayer and climber is that the belayer must never take the climber off belay unless the climber gives the belayer the "off belay" command.)

Belay off: Belayer to climber, "I've unclipped the rope from my belay device and have taken you off belay."

That's me!: Climber to belayer, "You've taken up all the slack in the rope and the rope is now tight to my harness."

Watch me!: Climber to belayer, "Heads up! Be attentive with the belay—there is a good chance I'm going to fall right here!"

Falling!: Climber to belayer, "I'm actually falling, go to your brake position and lock off the rope to catch my fall!" (A fall can happen so fast that the climber might not be able to shout this signal during a short fall, but it helps the belayer react more quickly, especially in situations where the belayer can't see the climber.)

ROCK!: Climber to belayer and others below, "I've dislodged a rock and it's now freefalling below me—watch out below!" (The equivalent signal to "fore!" in golf, "ROCK!" should also be yelled when the climber drops a piece of equipment.)

the belayer's brake hand) are held parallel, in front of the belay device, there is little friction, but when the brake strand is held at a 180-degree angle relative to the strand going to the climber, the device affords maximum friction, making it relatively easy to hold the force of a falling climber.

So long as a belay method adheres to the three fundamental principles of belay, there are many techniques acceptable for a sound belay. Along with loyalty to the fundamental principles, good belaying technique effectively manages rope slack, requires maintaining a brake hand on the brake strand side of the rope, and generates enough friction to stop a fall and properly lower a climber.

Over the last decade advances in technology have allowed manufacturers to produce thinner ropes, and belay devices have evolved along with the ropes. When buying a belay device, check the manufacturer's specifications and make sure it's appropriate for the diameter of the climbing ropes being used. The most popular tube device is the Black Diamond ATC (tongue in cheek for Air Traffic Controller), which also comes in a more versatile version with teeth on one side (the ATC XP) that gives the belayer two options: a regular friction mode when the brake strand is on the non-teeth side, or roughly twice the amount of friction when the brake strand is on the teeth side.

Assisted braking devices (ABDs) have become popular for toprope belaying. The most popular models include the Petzl Grigri and the Trango Cinch. These devices have a mechanical lever that



Petzl Grigri in lowering mode.



Trango Cinch in lowering mode.

should engage during a fall. Once weighted, the braking lever pinches the brake strand quite hard, so the device has a handle that must be opened to release the tension. When lowering a climber, the belayer must simultaneously manipulate the mechanical lever with the handle with one hand, while maintaining friction and controlling the speed of the lower with the brake hand. These coordinated movements mean that ABDs are far from foolproof, and many accidents have occurred with ABDs, typically when someone is being lowered. The cardinal rule to teach with any belay device is this: Never take your brake hand off the rope! After all, it's the first fundamental principle of belay.

With any belay device, read the manufacturer's guidelines carefully, and seek proper instruction from an AMGA certified instructor if you have any doubts about how to use the device or the proper technique to use when belaying with the device.

Belaying in a Base-Managed Site

Whether using an ATC or an ABD, the following sequence best adheres to the fundamental principles of belay in a base-managed site.

The PBUS (pull, brake, under, slide) method of belaying on a toprope. Start by clipping the rope into the slot in the belay device closest to the spine side of the carabiner and orient the rope so that the brake side is down.





To take up rope, pull the rope up with your brake hand (palm down) as you simultaneously pull the rope down with the other hand . . .



. . . then brake the rope down under your belay device.



Take your non-brake hand and firmly grasp the rope directly under the belay device . . .



. . . then slide your brake hand up against that hand and repeat the process. This technique is easy to learn and maintains a firm brake position on the rope at all times. In a fall, remember that the brake position is down.


1


2

After you've mastered the PBUS method, a more advanced technique is to brake under and switch the brake hand, alternating back and forth with either hand.


3

Two-Rope Toprope Setups

When rigging long topropes of more than half a single rope length, two ropes can be tied together using knots like the double fisherman's knot or figure eight bend knot. With such a huge amount of rope out between the climber and the belayer, rope stretch is a major concern, especially when using dynamic ropes. Remember that even a short fall in a toprope situation will stretch a dynamic rope about 10 percent, so tighten up the rope when belaying someone just off the ground, or just above a ledge.

Here are two methods that can be used to deal with the knot joining the two ropes. The simple solution, and also the best if there will not be a stance for the climber to stop at, avoids the knot pass altogether. With the knot joining the two ropes at the anchor, tie a figure eight loop and attach it to the climber's belay loop with two locking carabiners (gates opposed and reversed). When the climber reaches the anchor, the knot will be just above the belayer's device, so no knot pass is required.

Another solution is to use two belay devices. The climber ties in to the end of the rope as usual. The belayer anticipates the knot pass and has a second belay device clipped to his belay loop, at the ready. When the knot reaches the belayer, the belayer alerts the climber to find a good stance, then ties a backup knot (overhand loop) on the brake hand side of the belay device. The belayer steps forward to create a bit of slack, then clips the rope into the second belay device on the climber's side of the knot, leaving the first belay device clipped in. If another person is available, that person can assist the belayer simply by holding the rope with both hands under a little tension above the belay device as the belayer accomplishes this. When the climber reaches the anchor, the belayer lowers the climber until the knot is almost to the belay device, and the process is reversed: The climber takes a stance, the belayer unclips the second belay device (first double-checking that the first belay device is still clipped in and has the backup knot), then unties the backup knot and lowers the climber as normal. Knot-passing techniques are something that should be practiced with a qualified instructor.

Backup Belayers

The purpose of the backup belayer is simple: In case the primary belayer loses control of the brake, the backup belayer, holding the brake strand side of the rope, holds the rope to prevent a fall, essentially backing up the belayer's brake hand. For first-time belayers it is appropriate for the instructor to be the backup belayer. For intermediate-level students who have demonstrated proficiency in belaying techniques, other students are commonly used for backup belayers. As an instructor, when you demonstrate a climb with a student belayer, adding another student as a backup belayer gives you an added layer of protection.

To properly back up a belay, the backup belayer should be positioned behind and, if possible, below the belayer's brake hand, so that the backup belayer's hands can activate the brake position of the belayer's device if needed. The backup belayer takes in or feeds out rope as needed, leaving enough slack so that the rope is not being tugged from the belayer's brake hand, or in any way impeding the belayer's ability to manage the belay. If the belayer



Backup belayer in action. Note that the backup belayer is providing a hip belay for extra security. This may be required in places where an in-line belay backup is difficult to achieve.

JASON D. MARTIN



Here a climber provides a "meat anchor" for the belayer. The backup belayer provides an in-line backup belay.

RON FUNDERBURKE

loses control of the brake hand, the backup belayer essentially takes over the braking role. The critical juncture for the backup belayer is when the climber reaches the anchor and transitions into being lowered. The backup belayer can also help the belayer by managing the free end of the rope, preventing any tangles from reaching the belayer.

Some instructors run the rope from the belayer's brake strand through a carabiner on a ground anchor behind the belayer, redirecting the rope back up to a backup belayer. When done properly, this keeps the rope low and in the braking plane, which allows the backup belayer to stand or change locations without compromising the effectiveness of the backup. This redirect technique is also helpful if the instructor is the backup belayer. The instructor can stand in front of the belayer to visually monitor the belayer and climber at the same time while keeping the brake strand in the braking plane.

Another backup technique is the use of a "catastrophe knot." This is simply an overhand knot tied on the rope on the brake strand side of the belayer's belay device. The catastrophe knot can be used if, for some reason, the instructor needs to walk away from the backup belayer role momentarily. If the climber falls and the belayer loses control, the overhand knot will jam in the belay device, preventing a catastrophic fall.

Belaying from the Top

The method preferred by most professional instructors when belaying from the top of the cliff is the direct belay. In a direct belay the belay device is



A direct belay with a Munter hitch. In this sequence the belayer's right hand is the brake hand. The starting position (position 1) is with the brake hand at the top and the guide (or feel) hand lower (left photo). Pull the rope down with the brake hand as the guide hand goes up (center). Feeding the rope up toward the carabiner with the guide hand, rather than pulling the rope down tightly with just the brake hand, lessens kinking of the rope. Now take the non-brake hand and grasp the rope below the brake hand (right). This is both the brake position and lowering position. Unlike a tube device, the maximum friction with a Munter hitch is when the two rope strands are parallel to each other. To continue the hand sequence, return to position 1.



The direct belay. A Grigri is clipped directly to the master point.



Detail of a direct belay setup. The belayer is anchored with a clove hitch, and the Grigri is clipped directly to the anchor master point.

clipped directly to the anchor, and in the event of a fall, the anchor, not the belayer, bears the brunt of the fall and holds the climber's weight.

Using a standard belaying device, like an ATC, is not recommended for use in a direct belay, because unless the device is positioned below waist level, the braking position will be very awkward, and the instructor will be in a weak and dangerous position to hold a fall. If the master point is above waist level, the Munter hitch works well, since the braking position for maximum friction is when the two strands of rope are parallel to each other, with the brake position down below the carabiner, not above it. Belaying with a Munter also allows instructors the option of positioning themselves some distance away from the Munter belay carabiner due to the maximum braking power achieved with both rope strands parallel to each other.

A commonly used method for a direct belay is to use an assisted braking device (e.g., Petzl Grigri

Not for Instructors

Recreational climbers tend to use two systems that have limited applications for professional instructors. The first is the indirect belay, which is a fancy way of saying a belay directly off the harness. The second is the redirected belay, a technique where the rope runs from the belayer at the top through carabiners at the anchor and then back down to the climber.

The indirect belay is considered to be indirect because the force of a fall is not directly placed on the anchor. Instead, the belayer's body takes a portion of the force, which depending on the position and stance could be a large portion or a small portion.

An indirect belay is a poor choice for an instructor because you are "in the system," frozen in the position that you set up. This makes it difficult to see and coach your climber. Additionally, if something goes wrong, it is difficult, technical, and time consuming to escape the belay.

A redirected belay is a similar technique, but instead of running directly to the climber's belay loop, the rope is first redirected through carabiners in the anchor. The problems with the redirected belay are similar to those with the indirect belay. The instructor can become stuck in the system, unable to coach a climber below, and this belay also is difficult to escape in the event of an emergency.

In addition to the preceding, there are two other problems implicit in a redirected belay. First, when a heavy climber lowers, the belayer can be pulled up into the system. And second, this system puts more force on the anchor.

A redirected belay puts more force on the anchor by creating a 2:1 pulley system at the master point. Such a system requires an equal amount of weight on both strands of rope to remain static. In other words, if a 200-pound person falls on a redirected belay, you will have to counteract that weight with an additional 200 pounds, placing 400 pounds directly onto the anchor.

While some might argue that there are legitimate reasons to use an indirect or a redirect belay, there are few legitimate reasons to use these techniques in a single pitch instructional scenario.

or Trango Cinch) or autoblocking device (e.g., ATC Guide or Petzl Reverso) clipped directly to the master point of the anchor.

The advantage of a Grigri or similar device is that in the event of a fall, the Grigri simply locks off, and the anchor holds the climber's weight. When using a Grigri in the direct belay mode, take care when the device is close to the rock, as anything that presses against the handle (i.e., the rock) will release the braking mechanism. Be sure to position the handle away from the rock.

Remember, a regular ATC or similar non–autoblocking device is not recommended for use in a direct belay if the master point is at or above the belayer's waist level, as the braking position would be very awkward.

Lowering from a Top-Managed Site

There are several lowering methods that are quick and easy to rig. Before lowering someone, make sure the system is closed and the rope is properly flaked at the instructor's feet. Climbing instructors should choose an ergonomic stance that will not put them in an awkward position, and will allow visual contact with students all the way to the ground. If the anchor is not close enough to the edge to allow this, a tether or anchor extension should be incorporated into the system.

Lowering with a Munter Hitch

The rope is flaked at the instructor's feet, so if there are any tangles, they can be handily dealt with. Note that the tail of the rope sitting on top of the rope stack will soon be tied to a student. Therefore, wherever that rope goes, the student will have to follow that same path while approaching the cliff's edge to be lowered. Make sure the student has a clear avenue to the cliff's edge once on belay. Toss the rope to the student and instruct them to tie in. Next, use a locking carabiner designed for use with a Munter hitch on the anchor. Back it up with an autoblock clipped to a locking carabiner at the instructor's belay loop, and begin formal belay commands with the student. One advantage of the Munter hitch for lowering is that an instructor does not have to be at the Munter carabiner to effectively manage the braking position, since the optimal friction is when both rope strands are parallel to each other. This allows an instructor some flexibility; he or she can tether as far away from the Munter as desired while maintaining an effective belay.

Lowering with an Assisted Braking Device

When given the option, many Single Pitch Instructors will lower a student using a Grigri. Since it has a built-in braking system, there is no need to back it up with an autoblock. Petzl actually sells a carabiner, called the Freino, that has a special gate on the side of the carabiner for the brake strand to be clipped into, to facilitate lowering. Without the special carabiner, an instructor can redirect the brake strand back up through a separate carabiner clipped to the master point (or, on a cordelette anchor, up to the shelf). The big advantage of the Grigri is that once the rope is clipped in, it can be used for lowering (just remember to redirect the brake strand!) or belaying (as the climber climbs back up), and it's all set to rig a 3:1 hauling system if a climber needs some assistance on the way back up.



A Grigri in lowering mode with the brake strand redirected using the Petzl Freino carabiner, which is specifically designed for this application.



A Grigri rigged for lowering with the brake strand redirected through a carabiner clipped to the master point.

Using an Autoblock Knot as a Backup When Lowering

Whenever lowering a student with a belay device other than an assisted braking device, it's best to back up the brake hand with an autoblock knot clipped to a locking carabiner attached to the instructor's belay loop.

Some instructors call the autoblock the "third hand," because if the brake hand releases when lowering or rappelling, the autoblock grabs the brake strand of the rope. The autoblock adds an extra level of security, especially when there are tangles in the rope that require untangling.

If the stance at the anchor does not allow a clear field of vision down the cliff, to watch climbers while lowering, then instructors can rig the rope direct belay system to position themselves at the edge to maintain visual contact. Instructors should always strive for visual contact with their students whenever belaying or lowering.

The belayer is ready to lower the climber with a Munter hitch on a locking carabiner clipped to the master point, backed up with an autoblock clipped to a locking carabiner attached to the belayer's belay loop.





Lowering with a Munter hitch and an autoblock. The belayer is holding an autoblock backup that's clipped with a locking carabiner to his belay loop.



Here the instructor is positioned at the cliff's edge to maintain visual contact with the climber being lowered using a munter hitch at the anchor's BHK master point. The instructor is using a Grigri on the white fixed line (instructor tether) to allow for adjustable positioning. Note the backup knot tied on the fixed rope on the brake strand side of the Grigri. The instructor's brake hand on the lowering rope is backed up with an autoblock knot attached to his belay loop.

CHAPTER 12

Rappelling

The first question the instructor needs to answer is "why rappel?" Is there an easier way to descend from the top of the cliff? Would lowering be more efficient? Can the risks be properly managed? The most common reasons for rappelling are to teach novices the fundamental skills of rappelling or to provide students with an experience. Every recreational climber needs to know the fundamentals of rappelling; it is one of the cornerstone skills of technical rock climbing. Additionally, rappelling can be an impactful activity. It is an activity where students take complete responsibility for managing their own risk. Properly facilitated, it can be a great tool for building self-confidence and generating a sense of accomplishment. The instructor should have clear goals for conducting the activity and should avoid treating rappelling like an amusement ride.

Teaching Rappelling

Site Selection

Site selection is important to teach a novice rappelling technique. Select a site that has a comfortable, flat area on top without a drastic transition from the horizontal to the vertical. The ideal site should have a high master point for the rappel and belay anchor and a flat "desktop" area that extends at least 10 feet back from the edge of the cliff, be free of loose rocks, and have a rounded, gradual edge for a comfortable transition to a wall that is angled slightly less than vertical. The site should also provide a good stance for the instructor, where he or she can coach and model while maintaining visual and verbal contact with the student during the entire rappel. The cliff face should be free of loose rock and uniformly flat, not riddled with cracks, and without corners or overhangs. The base should have a nice flat landing area without boulders, bushes, or trees.

Rigging for Contingencies

In the institutional setting all students are belayed when they are learning to rappel. A good instructional system anticipates any potential problems that may occur during a rappel and uses a rigging system that is ready to remedy any problem.

Student Rappel Belays

Belaying students while rappelling can be done from the base or from the top of the cliff. The technique used at the base is called the fireman's belay. This technique requires the instructor to be at the bottom of the rappel. Holding the rappel rope, the instructor can stop the rappeller's progress by forcefully pulling down on the rope. When the instructor pulls down on the rope and applies tension, the rappeller will stop—it's not possible to move down the rope when it is under tension. This technique requires the instructor to be on high alert, prepared to arrest a fall the moment it happens. Failure to react quickly can lead to loss of control of the belay, with catastrophic consequences. The fireman's belay should be limited to situations where there are two instructors present: one to perform the belay and one to monitor and coach the students on top. It is



Instructor-belayed rappel rigged from a high master point.

Elevators

Care needs to be taken to avoid having the master point pinned to the ground once the student has weighted the system and gone over the edge. A low master point has two disadvantages. It makes the system difficult to manage for the instructor, and it makes the transition over the edge far more demanding for the novice rappeller. The SAR community uses a ''high redirect'' (aka an elevator) to deal with this; it's also an elegant solution to the problem for the climbing instructor. A simple way to create an elevator is to use a pack to prop up the master point; however, the use of trees or terrain features are a much more effective way. With a little creativity there is no reason to grovel in the dirt while managing a belayed rappel.

not a recommended belay technique when dealing with novices or when facilitating an experience. Assisting or rescuing a student in mid-rappel is highly problematic with this technique.

The preferred method for students who will be rappelling for the first time is to provide a belay from above. The system can be rigged using one or two ropes. One line is the rappel line; the other is the belay line. If the length of the rappel is less than half the rope length, the system can be rigged with a single rope. One end is tied to the belayer, and the other end goes to the ground and includes a stopper knot. If the rappel is more than half a rope length, two ropes are required. The rappel rope is attached to the anchor with a Munter/mule combination, which is releasable under tension. The rappeller is tied into the belay rope and belayed on a direct belay with a Munter hitch off the anchor. The belay rope is neatly stacked at the instructor's feet.

It is recommended that an assisted braking device *not* be used in this situation, for a couple of reasons. First, it is difficult to manage the ABD and maintain visual contact with the rappeller. Second, and more importantly, it is nearly impossible to provide slack to the belay line smoothly as the rappeller progresses. Under this circumstance, the student isn't actually rappelling; it becomes more of a lower.

Sometimes the rappeller encounters a problem (like long hair or clothing stuck in the rappel device, or a knot in the rappel rope) and can't continue. As always, seek the nontechnical solution first. If one cannot be found, fix the problem by doing the following:

1. Tie off the Munter on the belay line with a mule knot and overhand backup.
2. Release the mule knot on the rappel line and give the rappeller some slack.
3. Have the rappeller fix the problem (e.g., take the hair out of the device).
4. Re-tie the mule knot with an overhand backup.
5. Release the mule knot on the belay line and continue belaying the rappel.

The Instructor Rappel Backup

Instructors should manage personal risk by using a backup when rappelling. In the old days the most common method for a rappel backup was using a prusik knot on the ropes above the rappel device, connected to the harness with a sling. The nonbrake hand would cup the prusik knot and hold it in a loosened position during the rappel, allowing it to slide down the rope. Letting go of the knot allowed it to slide up and grab onto the ropes,

Extended Master Point for Belay Strand

The belay line on a releasable rappel should always be extended so that the carabiners don't pinch the rope between one another. One way to do this is to use a runner basketed through the master point. By tying an overhand knot in the basketed sling, two additional redundant master points are created. Another way is to mule off the rappel line on one locking carabiner, while belaying the student off two enchained locking carabiners. And yet another way is to use a double loop figure eight knot, making each loop a different length, provided an appropriate diameter anchor rope is used and that it is not placed on an abrasive surface.



Detail of belayed rappel setup, rigged for contingencies. The rappeller is rappelling on the rope in the foreground, tied to the master point with a Munter/mule combination, which is releasable under tension. The belayer is belaying with the direct belay technique using a Munter hitch from an extended master point, created by basketing a double-length (48-inch) nylon runner through the anchor's two-loop master point, then tying it with an overhand knot for redundancy. The Munter/mule/overhand combo is one ugly knot, but it's easily releasable under tension, and that's the beauty of it.



At this site the distance of the rappel is over 100 feet, so the system is rigged with two ropes. The yellow rope is the rappel rope, attached to the anchor with a Munter/mule/overhand combination. The blue rope is the belay line. Note how the instructor has created multiple master points with the doubled yellow nylon sling.



Here one bi-pattern rope is used for a releasable belayed rappel scenario. A BHK master point is rigged with a low-stretch (red) rope. The instructor is attached to a tether (red rope) with a Grigri. The striped orange dynamic rope held by the instructor is the belay line, and the rope at the bottom is the other half of the bi-pattern dynamic rope, serving as the rappel rope, attached to the anchor with a Munter/mule/overhand combination. By basketing the yellow nylon sling through the two-loop BHK master point and tying an overhand knot, the instructor has created two additional master points.



Without staggered master points, things can get clustered in a releasable rappel scenario.

stopping the rappel. There are two drawbacks with this method. One is that for the prusik to lock off, it must hold all the rappeller's weight. The second is that once it is weighted, the rappeller must remove all body weight from the prusik knot in order for it to be released, not an easy task on a free-hanging rappel.

The modern rappel backup utilizes the autoblock knot, rigged below the rappel device. There are two distinct advantages with this method. One is that for the autoblock knot to grab, it only needs to hold a very small percentage of the rappeller's weight, since it is on the braking side of the device, and the device itself is holding most of the weight and providing most of the friction. It is essentially like a brake hand squeezing and gripping the rope, and for that reason some instructors refer to it as the "third hand." The second big advantage of the autoblock method is that it is releasable under tension (i.e., when weighted and grabbing onto the rope). While rappelling down, simply form a circle with the thumb and forefinger (like the OK sign) and push the autoblock down while descending, allowing the rope to freely slide through the knot. When released, the autoblock knot rides up and grabs onto the rope, like the brake hand squeezing the rope. Releasing the autoblock, even when weighted, is as simple as sliding it back down and holding it in the "open" position. It's a beautiful thing, and easy to rig.



Left: Black Diamond ATC XP rigged for rappelling with a three-wrap autoblock backup clipped to the leg loop with a locking carabiner.

Bottom: another view of how to rig an autoblock backup, here using a Black Diamond ATC rappel device and a three-wrap autoblock tied with 6mm nylon cord attached to the leg loop with a locking carabiner.



Not Foolproof

I (BG) conducted several tests over the last year with my autoblock rigged at my leg loop and my rappel device (ATC) at my belay loop. With someone giving me a fireman's belay to back me up, I flipped upside down to see if the autoblock would grab and hold. In three out of four tests, it failed to grip since it had ridden up against my ATC, and the rope kept sliding right through. It's not a foolproof backup.

When the technique was first introduced, the autoblock was attached to the rappeller's leg loop with a carabiner. The disadvantage of clipping the autoblock to a leg loop is that if for some reason the rappeller were to go unconscious and flip upside down, the autoblock would ride up and come in contact with the rappel device, which would prevent it from grabbing.

Also, recent harness leg loop buckle designs (particularly the Black Diamond trakFIT and Petzl "doubleback" buckle systems) can loosen when a carabiner is clipped into them and pulled outward. If using an autoblock on a leg loop, make sure the harness buckle cannot be defeated by an outward pull, or better yet, use a harness with a fixed (no buckle) leg loop design. If you have a harness with one of these buckles and need to rappel off the belay loop, consider clipping your autoblock to the inside of the leg loop, opposite the buckle.

In recent years a more secure method has been developed: extending the rappel device with a sling attached to the harness, and rigging the autoblock clipped into the belay loop. One configuration is to rig a double-length sewn nylon sling threaded



Note where the carabiner sits on the harness. Rigging an autoblock backup from this position has the potential to unbuckle the leg loop.

JASON D. MARTIN



If you have a harness with suspect buckles, rig the autoblock backup from the inside of the leg loop.

JASON D. MARTIN



Adam Fox demonstrates the proper use of an extended rappel device with autoblock backup. A double-length nylon runner is threaded through the harness tie-in points and tied with an overhand knot for redundancy. The rappel device is the Black Diamond ATC Guide in rappel mode. The autoblock knot is clipped to a locking carabiner attached to the belay loop.

through both tie-in points at the front of the harness and tied with an overhand knot, to gain redundancy at the sling. The preferred cordage is a nylon sling (18mm or 11⁄16-inch width) over a thin (10mm) Dyneema sling for this application because nylon has a higher melting point. If the rappel rope is running across the sling, it could potentially create some heat due to the friction, which could damage the sling and reduce its breaking strength in later applications.

Managing the Risks—Avoiding Rappelling Accidents

When teaching rappelling to novice climbers, it is important to stress risk management. Although rappelling is a simple technique, statistically a high percentage of rappelling accidents end in a fatality. Analyzing rappelling accidents helps to understand what can go wrong and what to do to keep it from happening. Here is a look at the most common rappelling accident scenarios.

Scenario 1: Rappelling Off One or Both Ends of the Rope

This happens with some regularity, and almost every year there are several fatal rappelling accidents in America where someone simply rappelled off the end (or ends) of a rope. In the single pitch environment, it can happen when the ends are uneven on a double-rope rappel, especially if there is no middle mark. When the short end passes through the rappelling device, only one strand of the doubled rope remains in the device, and the climber's body weight rapidly pulls the rope through the rappel anchor, quickly dispatching the climber to the ground. To prevent this, *close the system* by tying stopper knots separately in both ends of the rope. Make sure that the stopper knot will jam in the rappel device that is being used.

Scenario 2: Not Clipping Both Strands of the Rope into the Carabiner on a Double-Rope Rappel

This is an easy mistake to make when not alert and double-checking the system. When visually inspecting the top of a tube-style device, it will appear as if both strands are properly threaded because the device holds the bight of rope inside itself, even if the rope hasn't been clipped into the carabiner behind it. If only one strand makes it into the locking carabiner, when leaning back and weighting the rope, the climber will descend as rapidly as in the first scenario—and with equally injurious or fatal results. A good habit is to first tether in with a sling to the rappel anchor, rig the rappel device, then weight the rappel system and double-check everything before unclipping the tether. Rigging an autoblock backup is also a good idea.

Check and Check Again

I (BG) have done thousands of rappels in my climbing career, and one time I caught myself not clipping both strands on a double-rope rappel. Luckily for me I'd rigged an autoblock backup, and as I weighted the system, I noticed my error. If not for that autoblock backup, I probably wouldn't be writing this today.

Rappelling Systems Check

It is important to teach students how to go through a systematic mental checklist before rappelling. An acronym that facilitates the process is ABCDE. A is the rappel anchor. Take a look at the anchor, slings, chains, etc., and make sure the rappel rope is threaded properly through the anchor. The anchor should be redundant all the way to the point where the rope is threaded through the anchor. Do not rely on a single piece of gear in the anchor system, whether it is a single cord, sling, or rappel ring. B is for buckles on your harness—double-check to make sure they are buckled properly and doubled back appropriately. C is for carabiner. Make sure the locking carabiner that attaches the rappel device to the harness is being loaded properly on the long axis—and squeeze check to make sure that it is locked! D is for look down and see where the rope goes. Does it reach the ground? Or the next ledge? E is for the rope ends. Do they have stopper knots? Is the system closed?

Scenario 3: Not Tethering to the Anchor

A sewn sling clipped to the anchor with a locking carabiner for a tether is all it takes to prevent this scenario. Using a daisy chain as a personal tether is not recommended, because if a carabiner is clipped into two adjacent loops, a weak and dangerous connection has been created. Better than a standard daisy chain with sewn pockets is the newer, modern version that consists of full runner-strength sewn loops, like the Metolius PAS (personal anchor system) or the Sterling Chain Reactor. These more versatile tethers also allow the rappel device to be extended away from the harness as described in the Instructor Rappel Backup. Again, a good habit is to weight the rappel device and check to make sure it's rigged properly and supports body weight before unclipping the tether from the anchor.



Tether comparison. Left to right: Sterling Chain Reactor, Metolius PAS, Black Diamond Daisy Chain.



A traditional daisy chain with bartacked pockets is not recommended for rappel extensions or as a personal tether, because if a carabiner is clipped into two loops, an extremely weak connection is created (3 kN or 674 lbs.).



To rig a tether/rappel extension with a sling, start with a double-length (48-inch/120cm) sling and girth-hitch it through both tiein points on the harness. Tie an overhand knot about halfway down the length of the sling, adjusting the knot so that when it is clipped back into the harness belay loop with a locking carabiner, the length to the overhand knot is equalized. Clip the locking carabiner of the rappel device into both loops in the sling to make the sling itself redundant when it's clipped back into the harness belay loop.





Here my double-length (48-inch) Black Diamond 18mm nylon sling is rigged as a tether/extension. I (BG) girth-hitched the yellow sling through both harness tie-in points. I'd previously tied an overhand knot in the sling, and I then clipped the locking carabiner of my rappel device (a Petzl Reverso) into both loops in the sling. I rigged an autoblock backup with a Sterling Hollowblock and clipped it to my harness belay loop with a locking carabiner. After I double-check everything, I'll unclip the locking carabiner from the anchor and clip it back to my harness belay loop, adding redundancy to the sling.

CHAPTER 13

Basic Assistance and Rescue Skills

One of the many reasons that a student elects to take a course from a certified climbing instructor is that there is an unwritten agreement between the instructor and the student. The agreement is that if the student gets into trouble on the course, the instructor will be there to help the student get back out of trouble.

Certainly the word "trouble" could mean many different things. Examples include anything from forgetting one's water bottle in the car to suffering an injury. From a technical perspective in a single pitch environment, trouble commonly means that an individual is stuck somehow on a route. Following are several ways to get people unstuck and out of trouble.

Assistance from the Base

The first step in any assist scenario is to seek out the nontechnical solution. Coaching, encouraging, directing, or allowing gravity to take over are more efficient and expose both the instructor and student to fewer risks. When it becomes apparent that a nontechnical solution will not resolve the problem, it is time to incorporate more advanced techniques.

The basic assist skills presented below are most easily accomplished with an ABD, like a Grigri, and it is recommended that an ABD be used for belaying from both the base and top of the cliff, as it streamlines and facilitates these assist techniques. It is the right tool for the job and worth every extra ounce that it weighs over a traditional belay device. It is recommended that instructors learn the climber pickoff and the 3:1 raising system with a Grigri before trying it without one.

The Climber Pickoff

The "climber pickoff" is essentially the same technique used by the belayer to rescue a fallen lead climber who is injured and can't be lowered. The difference in a toprope situation is that there is a solid anchor system, not just the one piece of gear that held the leader's fall.

The climber pickoff utilizes a counterbalance ascension and rappel technique and requires minimal equipment. Basically the instructor ascends the rope to the climber, then rappels down with them.

All that is needed is the following equipment:

- 1 double-length (48-inch) sling
- 1 locking carabiner
- 1 prusik cord (6mm or 7mm soft nylon cord, 5 feet long, tied into a sling with a double fisherman's knot)

When belaying with a Grigri, follow these steps:

1. Start by tying a backup knot (overhand loop) on the brake strand side of the Grigri.
2. Tie a friction hitch (klemheist or prusik) with the prusik cord on the load strand going up to the climber, and attach the double-length sling to it with a locking carabiner.
3. Ascend the rope by sliding the friction hitch up, so that when the foot is placed in the sling the knee is bent at a 90-degree angle. A knot can be tied in the sling to shorten it as needed. Stand up in the sling, and as you straighten the leg, simultaneously pull the slack through the Grigri (pulling straight up on the brake strand) and hang in the harness off the Grigri. Alternate

standing up in the sling, then hanging in the harness, tight to the Grigri. About every 10 feet or so, tie a backup knot (overhand loop) on the brake strand side of the Grigri.

4. Upon reaching the climber, transfer the friction hitch from the instructor side of the rope onto the rope above the climber. The instructor then takes the double-length sling and threads it (basket style) through his or her belay loop and clips both ends of the sling to the locking carabiner attached to the friction hitch. Where the friction hitch is positioned will affect where



Counterbalance rappel using a Grigri after "picking off" a climber from the cliff.

the assisted climber will be positioned. If the friction hitch is high, the climber will remain at that position while rappelling. If the position of the friction hitch (klemheist or prusik) is just above the climber tie-in knot, the climber will move up and slightly above the instructor while descending.

5. Rappel with the Grigri, untying the backup knots as you descend.

Basic assistance skills will allow an instructor to assist a student if needed.

Rare Rescues

In over thirty years of professionally guiding thousands of clients in toprope situations, I (BG) have only had a few instances where I actually had to go up on the rock and bring a climber down—all of them being young kids who were overcome by fear and mentally lost control, afraid to lean back and weight the rope so they could be lowered back down. Having the knowledge and skills to go up the rope and bring a student down is important in case the instructor ever has to assist an injured student, even in a toprope situation.

If taking over someone else's belay and the belay strand is weighted, the sequence would be as follows:

1. Tie a backup knot (overhand loop) on the brake strand side of the belayer's belay device.
2. Clip a Grigri onto the rope between the backup knot and the belayer's belay device.



3. Tie a friction hitch (prusik or klemheist) on the load strand (going up to the climber) of the belayer's rope.



4. Thread (basket style) the double-length sling through the belayer's belay loop and attach it to the friction hitch with a locking carabiner.



5. Have the belayer give slack at the belay device—the tension will now be transferred to the friction hitch, with the belayer essentially becoming a ground anchor; the belayer then can unclip and remove the belay device.



6. Transfer the weight of the hanging climber from the belayer to the instructor's Grigri, by taking up all the slack in the rope and pulling upward on the brake strand side of the Grigri, using body weight as the anchor.
7. Unclip one end of the sling from the locking carabiner at the friction hitch.
8. Ascend the rope by sliding the friction hitch up, so that when the foot is placed in the sling the knee is bent at a 90-degree angle. A knot can be tied in the sling to shorten it as needed. Stand up in the sling, and as you straighten the leg, simultaneously pull the slack through the Grigri (pulling straight up on the brake strand) and hang in the harness off the Grigri. Alternate standing up in the sling, then hanging in the harness, tight to the Grigri. About every 10 feet







or so, tie a backup knot (overhand loop) on the brake strand side of the Grigri.

9. Upon reaching the climber, transfer the friction hitch from the instructor side of the rope onto the rope above the climber. The instructor then takes the double-length sling and threads it (basket style) through his or her belay loop, and clips both ends of the sling to the locking carabiner attached to the friction hitch. Where the friction hitch is positioned will affect where the assisted climber will be positioned. If the friction hitch is high, the climber will remain at that position while rappelling. If the position of the friction hitch (klemheist or prusik) is just above the climber tie-in knot, the climber will move up and slightly above the instructor while descending.



10. Rappel with the Grigri, untying the backup knots as you descend.

Assistance from the Top

Coaching

The best and easiest way to assist a climber who's climbing up to you from below is simply to position your belay stance where you'll be able to watch them. By having visual contact you'll be able to manage the belay more effectively, taking in slack in sync with the movement of the climber. Giving advice to a climber who encounters a challenging section may prove ineffective if the instructor can't actually see them.

Vector Pull

If someone just physically can't do a move or is too tired to climb up a tough crux section, some assistance from the belayer may be enough to get them over the impasse. A simple method is the vector pull.

Imagine a rope strung tight across a chasm, anchored on both ends, rigged for a climber to clip in with a pulley to slide across. This is known as a Tyrolean traverse. If the climber weighs 200 pounds and is hanging from the middle of the rope, with an angle slightly less than 180 degrees, the force at each anchor is roughly 1,000 pounds. As the angle approaches 180 degrees, the force on the anchor points increases even more. Less angle, less force. For example, when the angle is relatively narrow (22 degrees or less), the 200-pound climber weights each anchor with only 100 pounds. Let's say the instructor is belaying from the top of the cliff, and the climber is unable to move up past a tough section of the climb. With a tight rope (180-degree angle), by reaching down and pulling perpendicular to the line of the rope, a surprising amount of force can be generated just by creating an angle slightly less than 180 degrees. By pulling on the rope at a right angle, it is like the climber hanging in the middle of the Tyrolean traverse who is generating ten times his bodyweight at the anchor points. This is often enough to boost someone past a move, especially if he is able to assist by climbing.

3:1 Raising System

One reason to use the direct belay technique with an ABD when belaying from the top of the cliff is that it is easily converted to a 3:1 raising system (aka the Z system) in a matter of seconds. For most climbing instructors, the direct belay is always the first choice, providing the anchor is solid, because it allows the instructor to anticipate and prepare for any eventuality, like a quick lowering or raising of the climber. Most instructors use a Grigri, clipped directly to the master point or extended master point (using the climbing rope). To set up a 3:1 raise, follow these steps:

1. Tie a backup knot (overhand loop) on the brake strand side of the Grigri. This allows the



Also known as the Z pulley system, the 3:1 raising system is easy to rig if a Grigri is being used for a direct belay. The Grigri is the ratchet (which locks off when needed to reset), and the friction hitch is the tractor (which moves up and down the field). The distance the rope travels between resets is called the throw.

instructor to go “hands free” and release the brake strand.

2. Tie a friction hitch (prusik or klemheist) on the load strand going down to the climber.
3. Clip the brake strand side of the rope (from the Grigri) to a locking carabiner clipped to the friction hitch and push the friction hitch as far as possible toward the climber.
4. Next, untie the backup knot and pull up on the brake strand side of the rope. For every 3 feet pulled through the GriGri, the load is raised 1 foot. Friction is the enemy in any raising system. If the rope going to the climber is in contact with a large surface area of rock, the raise will be correspondingly more difficult. A pulley at the friction hitch carabiner reduces friction and makes it easier to pull. Remember, this technique is for assisting a climber, helping them get past a tough spot, not to haul up a severely injured or unconscious climber.
5. When the friction hitch is all the way to the Grigri, reset the friction hitch by sliding it back down toward the climber. The Grigri’s built-in ratchet will lock off and hold the load as this is done. Then continue the raise.



A 3:1 assisted raise. With the climber also pulling, there is a tremendous mechanical advantage, making it far easier to raise someone than with a 3:1 raise.

3:1 Assisted Raise

For this method the climber must be close enough that it is possible to throw him a bight of rope. The climber clips the rope into his harness to assist in the raise. Using this system allows both the climber and instructor to work together, and makes it much easier for the instructor to raise the climber.

The steps are as follows:

1. Tie a backup knot (overhand loop) on the brake strand side of the belay device.
2. Toss a bight of rope down to the climber and have him clip it into his belay loop with a locking carabiner. If he already has a locking carabiner on his harness, have him clip that to his belay loop and to the bight of rope. If not, carefully lower the carabiner down. Don't throw it.
3. Identify which strand the climber should pull on by shaking it.
4. Untie the backup knot.
5. The climber pulls down as the instructor pulls up on the brake strand side of the rope. Warn the climber to watch his hands so they are not pinched in the carabiner when pulling.

CHAPTER 14

Fixed Lines

A fixed line is a rope that is literally fixed in one location to provide additional security to climbers, by providing a line that they can be attached to while moving. In an instructional setting, fixed lines provide a means to protect an individual in a group who is required to move over small sections of exposed 2nd, 3rd, or even 4th-class terrain.

Fixed lines should not be employed to protect long sections of exposed or 5th-class terrain. They should only be installed in areas where the likelihood of a fall is relatively low, but where the consequences of a fall are high enough to warrant additional protection. The first line of defense in these areas is that the terrain is easy enough that the student is unlikely to fall. The fixed line is a backup to the student's ability to effectively scramble. If the consequences of a fall are high, a belay is necessary.

Fixed lines usually take time to rig. If possible, place them before the students arrive. If the local ethic doesn't allow for this, then scout the area thoroughly and make a fixed line plan before the instructional day starts.

Following are the steps for fixed line installation:

1. Scout the crag or the approach to the instructional area for exposure and determine where a fixed line is needed.
2. Build an anchor at the top of the crag and clip the end of the rope into the master point with a locking carabiner.
3. Work down through the exposed area, pulling the rope down and placing gear along the way.

   At each piece of gear, the fixed line should be clipped in with a loop knot. The rope should *not* run through the carabiners freely. Each section of the rope should be isolated.

Depending on the fixed line's orientation and the terrain, the means by which the line is secured at the beginning varies. A catastrophe knot or a single anchor point may be sufficient. For traverses or anywhere else that an unfixed end could lead to catastrophe, such as an injury or fatality, an anchor system should be used.

There are three ways commonly used to travel on a fixed line. The method chosen is determined by the terrain, the orientation of the rope, and the amount of security desired. The first, and simplest, method is a hand line. As the name implies, the students simply hold the line. In this case the likelihood of a fall is low, and the individual or group simply needs a little bit of additional security.

Second is to use lobster claws. This technique involves girth-hitching two slings to the tie-in point on the climber's harness with a locking carabiner clipped to the end of each sling. The climber clips and locks both carabiners on the fixed line, then moves along the line. The climber bypasses anchor points by clipping past each point with one lobster claw and then the other. This allows the climber to stay attached to the rope at all times

The lobster claw technique is good for exposed traverses, but is not acceptable when the fixed line is in a vertical orientation where a student could fall back to the previous anchor point. Doing so could generate forces exceeding a factor 2 fall.

The third technique, which offers the greatest security, is to use a friction hitch on the fixed line,



A climber using the lobster claw technique to pass an anchor point.

JASON D. MARTIN

which the climber clips into with a lobster claw. A friction hitch offers the most security because it won't allow the climber to fall anywhere if he or she slips (unless the hitch itself slips). If a section requires such tactics, it's a good idea to prerig the friction hitches, to allow the climber to smoothly clip in and continue moving. When the climber arrives at a friction hitch, one lobster claw is clipped to the friction hitch and the other to the rope.

The friction hitch fixed line technique should be used sparingly. If you believe that you need to resort to this technique, first ask yourself if it would be possible to belay the section. If you cannot belay the section, then consider the consequences of a friction hitch slipping. If the consequences are high, you may need to choose a different crag. No matter which technique you choose to employ, only one climber should ever be attached to a given part of the line. You should never have two climbers in the same section of the system.

Fixed lines are a useful tool, but they should not take the place of a real belay. Before exposing students to a fixed line, make sure to weigh all the options. Make sure that it is the best solution to the problem. And make sure that everybody knows exactly what they're supposed to do as they move up or down the line.



A climber is using a friction hitch (prusik) on the rope for more security. Note the bight of rope coming down from above. When a piece is not available, it is often possible to use a long bight of rope to extend a less convenient placement in order to continue the logical route of the fixed line.

JASON D. MARTIN

CHAPTER 15

Leading

Leading is dangerous, whether the instructor is on the sharp end with an inexperienced belayer, or watching a student lead for the first time. The risk management mantra of "What is the likelihood of a fall and what are the consequences?" should be in the forefront of the instructor's mind when lead climbing with students.



AMGA Single Pitch Instructor Richard Riquelme belays a leader using the principal belay position for a Grigri.

JASON D. MARTIN

Student Lead Belay Training

When an instructor works at a venue that requires a lead to access the anchors, it is important to add a lead belay contingent to the belay lesson. Once the PBUS (pull, brake, under, slide) technique has been taught and the student demonstrates proficiency, then it is appropriate for an instructor to move into a lead belay lesson.

The orientation of the student's hands while belaying a leader should reflect the posture taken in the braking position of the PBUS. The student pays out rope with the guide hand above the device, while the brake hand remains in the same position below the device. If the student needs to bring rope back in, he or she simply reverts back to the PBUS toproping technique.

There are instructors who prefer to have students belay them with an assisted braking device. The advantage to these devices is that they reduce the likelihood of catastrophic failure of the system. The problem with them is they are far from foolproof and require specialized instruction and technique.

There are a number of devices on the market, and they all have their own idiosyncrasies. It's important to read all associated instructions before

Leading with a Student Belayer

"When you're leading, you should just assume that you're soloing."

It was my (JDM) first year working as a climbing instructor, and this was one of the first things another young instructor shared with me. At the time it made sense. Indeed, in my first two years of instructing, I led literally hundreds of pitches with terrible student belays.

But then it came to me.

The student belays weren't terrible because the students were inexperienced belayers. The student belays were terrible because I didn't invest the time and energy in the students to ensure that their lead belay technique was flawless. From that time forward, I invested myself in ensuring that my lead belays were solid.

Approximately a year after I started spending more time with students on belay technique, I was teaching an aid-climbing clinic in Red Rock Canyon. I placed a piece behind a massive flake and bounce tested it.

It held.

As I worked my way up to the top of my aiders, the flake shifted and the piece popped. I dropped about 6 feet before the rope arrested my fall. The energy that I put into the belay lesson was not wasted. My student easily caught me.

using a new device, follow the manufacturer's recommendations, heed the manufacturer's warnings, and practice with the device prior to using in an institutional setting.

The Petzl Grigri is one of the more common devices on the market. As a result, lead belay technique with the Grigri is described here.

The primary belaying position for the Grigri is the PBUS position, with a guide hand above the device on the rope and a brake hand below. As a leader moves up the rock, the belayer slowly feeds rope through the device, gently pulling with the guide hand, while pushing rope through with the brake hand. If the rope is fed at an appropriate speed, the cam in the Grigri will not engage.

In this principal belay position, the belayer's brake hand never leaves the rope. If there is a need to bring in slack, the belayer reverts to the PBUS toproping technique.

Because the cam automatically engages with a sudden acceleration of the rope, it can be difficult to pay out slack quickly. The simplest solution to this problem is to never allow the rope to suddenly accelerate. This may be accomplished by the leader placing gear at chest level or lower and extending the protection with runners. Doing so allows the leader to clip into the protection without having to give a quick tug on the rope.

If the curricular goal is to teach a student the finer points of lead belaying, then there are two ways to give slack to a climber who needs it quickly. The first and easiest way is to simply step in toward the wall. This will immediately put slack into the system and works well. However, this technique is not recommended for novice belayers as they are often tied down to ground anchors and cannot easily move.

The second way is to shift the brake hand, sliding it up the rope to the device, and brace the index



The proper way to give slack quickly with a Petzl Grigri.

finger against the lip of the moving sideplate. Press the thumb of the brake hand down on the cam where the handle is attached while continuing to hold the brake strand of the rope. Pull slack with the guide hand. Once finished, immediately return to the principal belay position.

Petzl recommends that you:

1. Always keep the brake strand in the brake hand. There is never a valid reason to let go of the brake strand.
2. Never grip the device with the entire hand.
3. Anticipate the lead climber's movement, including when additional rope is needed to make a clip.

In a toprope setting, a rope is generally set up early in the day and may be used to practice belaying. In a lead setting, practicing this skill requires some creativity. One method is to clip the first bolt of a sport route, or place a piece of gear about 10 feet up. Clip the rope and then have the student practice belaying a leader on this short mock setup.

Ground Anchors, Student Belay Backups, and Knots

In addition to using a Grigri and placing a lot of protection, here are three other ways to increase instructor security during a lead. First, use a ground anchor. Second, employ a backup belayer. And third, tie knots in the rope behind the belayer and the backup belayer.

A ground anchor keeps the belayer under control. The belayer is fixed to a given spot. If the belayer is anchored, the opportunity to trip, fall over, and pull the instructor off is greatly reduced. The belayer will remain in the designated stance.

With two or more students, a backup belayer will increase security. It is far less likely that both students will drop the leader. To add even greater security, put a friction hitch on the rope behind the belayer and attach it to the backup belayer's belay loop. Rather than being dependent on a hand belay, the backup belayer manages the rope with the assistance of a "third hand."

Some instructors tie knots in the rope behind the belayer and the backup belayer. As the instructor leads and the knots approach the belay team, either the backup belayer or, ideally, a third student unties them. Even if there are a series of mistakes, the leader will still have a reasonable margin of error.

No matter what steps are taken to increase instructor security, it remains important to regularly look down and check on the belayer. Make sure that the belay system is employed appropriately and communicate error corrections as needed.

AMGA_i-258_3pp_CS55.indd 236 2/27/14 12:00 PM

Descent Options

If walking off or downclimbing is not possible for the climbing instructor, the other descent options from the top of a route are either to rappel or be lowered.

The most secure method is to rappel. When being lowered, the instructor is completely reliant on the belay system and at the greatest exposure to risk of system failure. If there are any doubts about the security of the system (i.e., the belayer), the instructor should rappel.

However, if the curricular goal of the program is to teach the student how to operate as an independent climber, then the student will have to learn how to lower. When faced with that situation, the instructor can mitigate the risk by placing a friction hitch on the belay strand of the rope as a backup, clipping the friction hitch to a sling that is then clipped into the instructor's belay loop with a locking carabiner. While being lowered, the instructor manages the friction hitch, releasing it if the belayer loses control of the brake strand.

Teaching a Student to Lead

When teaching lead climbing skills, it is important to know whether or not the organization offering the course permits students to lead. It is also important to find out if the insurance policy permits student leads.

Regardless of whether the organization or insurance policy allows leading, prospective leaders should spend a great deal of time mock leading. A mock leader is a climber who is on toprope while simultaneously dragging a lead line. The toprope protects the student from a real fall, while the lead line provides the illusion of leading. The student can place gear or clip bolts just as if leading for real, but without the consequences.

After a student has completed a mock trad lead, the instructor can climb the route and inspect the pieces. Ideally, the instructor will provide the student with feedback on the quality of each placement while removing the gear.

An instructor may also choose to have a student belay the mock leader while the instructor ascends a fixed line beside the leader, which will allow the instructor to give feedback in the moment. The instructor may use the same rope climbing technique as described for a climber pickoff (chapter 13, Basic Assistance and Rescue Skills).

If only one rope is available, it is still possible to set up a mock lead. Simply tie both ends of the rope into the climber. One end will come from the climber's harness, run up through the toprope anchor, and drop back down to the belayer. The rest of the rope will lay in a pile between the climber and belayer.

The advantage of the single line mock lead system is that only one rope has to be carried. However, there are two disadvantages with a single line. First, students will have to unclip each piece as they are lowered. There won't be enough rope to leave it running through the pieces. And second, with a single line system, the student may have a harder time distinguishing between the belay line and the lead line. When climbers have two ropes in a mock lead scenario, they're usually different colors. This makes it easier for students to distinguish between the lead line and the belay line.

Most instructors will spend a great deal of time in ground school, teaching students how to place gear or clip bolts before moving into a mock lead sequence. Sport leaders should understand how to clip correctly before getting on the rock, while trad leaders should have a solid understanding of gear placement. Both sport climbers and trad climbers need to be educated in placement or clipping strategies before working their skills on a mock lead.

If teaching a clinic on sport leading, be sure to spend significant time in ground school practicing the transition from a toprope to a rappel. This can be done using traditional pieces close to the ground. Clip locking carabiners to two solid pieces and treat them like bolts. The student will then be



A climber mock leads on a single rope. Note the rope running up to the anchor above the climber, back down to the belayer, into the pile on the ground, and then back to the climber.

JASON D. MARTIN

able to practice the transition from start to finish.

If the instructor is in a position to allow students to lead for real, be extremely conservative. Beginning leaders should not fall. By choosing an appropriate crag—a crag where the student feels confident, or a very easy route, or even a 4th-class route—the exposure to potential student injury decreases dramatically.

Occasionally, an instructor may have a student who is an experienced climber and would like to lead. If organization policy and insurance allow this, then the instructor has to be the one to decide whether or not it's appropriate for the student to lead. This generally requires some assessment of both the student's movement skills and ability to clip or place gear appropriately. If an instructor doesn't like what he or she sees in a student assessment, then the instructor should not be afraid to say no. It's better to have an upset student than a seriously injured student.

Appendix A: Leave No Trace Ethics

Climbers should practice Leave No Trace principles from the moment they step out of the car. The following simple steps will help keep the climbing sites we all share as clean as possible, with minimal degradation to the climbing area and the surrounding environment:

- At popular climbing areas, use the outhouses located at most parking areas before you embark on your approach to that day's chosen cliff.
- Always use marked climber's access trails where they are available. If there is no marked trail to the cliff, minimize your impact by walking on durable surfaces (e.g., a sandy wash, rock slab, or barren ground).
- At popular, easy-access crags, avoid making a beeline from the parking lot straight to the crag without first looking for an established path or trail. Walking off-trail can significantly impact vegetation and cause soil erosion if enough people do it over a period of time.
- If traveling in a group in more remote, pristine areas where no trail exists, fan out instead of walking in single file and try to walk on the most durable surfaces, avoiding fragile vegetation. Don't leave rock cairns to mark the path, as this takes away the challenge of routefinding from those who prefer to experience it on their own terms.
- If nature calls and you're far from any outhouse, deposit solid human waste well away from the base of any climbing site, water source, or wash by digging a cathole 4 to 6 inches deep. Cover and disguise the cathole when you're done. Pack out all toilet paper and tampons in a ziplock bag. Better yet, use "blue bags" and pack out all human waste. Urinate on bare ground or rock, not plants. Urine contains salt, and animals will dig into plants to get at it.
- Leave no trace means just that—pack out everything you bring in, including all trash and food waste (that means apple cores and orange peels, too). Set an example for your group by picking up any trash you find; plan ahead and always carry a trash bag with you when you go out to the crag.

Principles of Leave No Trace

1. Plan ahead and prepare
2. Travel and camp on durable surfaces
3. Dispose of waste properly
4. Leave what you find
5. Minimize campfire impacts
6. Respect wildlife
7. Be considerate of other visitors

- Don't monopolize popular routes by setting up a toprope and then leaving your rope hanging on the climb, unused. If your climb begins from a campsite, ask permission to climb from the campers if the site is occupied. Minimize your use of chalk, and if you're working a route, clean off any tic marks with a soft brush after you're done. Protect everyone's access to a climbing area by being courteous, beginning with parking only in designated areas and carpooling whenever possible. Noise pollution can be a problem, from blasting tunes on a boom box to yelling and screaming while attempting a hard climb. Be considerate and aware of those around you, and limit your noise production to a reasonable level.
- Pick up all food crumbs and don't feed any wild critters—this habituates them to human food and encourages them to beg and scavenge, sometimes even chewing holes in backpacks to get at food.
- Leave all natural and cultural objects so that they can be experienced by everyone in their natural setting. If you are climbing in a national forest or national park, obey all regulations concerning the gathering of firewood and other objects.

For more information on Leave No Trace ethics, visit www.LNT.org.

Appendix B: How to Determine a Fall Factor

Fall factors are determined by a simple formula. Divide the length of the fall by the length of rope out between the belayer and climber.

The greater the fall factor, the greater the force on the rope, on the belayer, and on the anchor. A factor 2 fall is the maximum that may be attained in a standard climbing fall, since the length of a fall can't exceed twice the length of the rope.

In a multi-pitch setting, a factor 2 fall only takes place when a leader who has not placed any protection takes an unobstructed fall, drops past the belayer, and then falls directly onto the belayer's system. If the climber places protection above the belayer, it is no longer possible to generate a factor 2 fall, as the length of the fall can no longer be twice the length of the rope out.

Many other factors play into the calculation of a true fall factor. For example, if an individual tumbles down a slab, the impact will be quite different than if he fell unobstructed. If the belayer is pulled off the ground or a piece fails, all of these things change the true math.

A factor 2 fall is extremely serious. The forces generated can exceed the strength rating of gear, potentially resulting in anchor failure. Also, the impact force on the belayer is tremendous. Loss of control of the belay or injury to the belayer are both possible outcomes. As such, it is imperative

Fall Factors

Following are some simple word problems that you can use to determine if you understand how to calculate fall factors:

1. A lead climber places a piece 15 feet off a belay. As he reaches 20 feet, he falls, dropping 10 feet. What type of fall factor did he generate?
2. A lead climber on a multi-pitch climb leads 50 feet up above his belayer without placing any gear. He slips and drops 50 feet back to his belayer and then continues to fall another 50 feet, for a grand total of 100 feet. What type of fall factor did he generate?
3. A lead climber is 50 feet up. His last piece is 10 feet below him. He falls. What kind of fall factor did he generate?

Answers: (1) Factor 0.5, (2) Factor 2, (3) Factor 0.4

that multi-pitch climbers use the anchor as the first piece of protection or place gear immediately after leaving the belay station. This will limit the possibility of a high-impact fall.

Single Pitch Instructors are not as concerned about fall factors as much as multi-pitch guides, but there is still cause for concern.

A common practice among climbers is to clip into the anchor with a personal tether. Personal tethers include slings, a PAS, or a daisy chain. If the climber is positioned above the anchor, clipped in with a personal tether, and falls, a high-impact fall—potentially as high as a factor 2 fall—will occur. Due to the static nature of tether material, there is a possibility that the personal tether will break. Some tether materials, like nylon, do better in testing than others, but a fall onto a tether is still a concern that has to be kept in mind. Additionally, the impact force generated to the climber's body can easily result in an injury. The takeaway point here is that a climber does not need to be tied into a rope to suffer a factor 2 fall.


PEEL!
GOTCHA!
FALL FACTOR = length of fall / length of rope between belayer and climber

Calculating the fall factor.

MIKE CLELLAND

Appendix C: Autoblocking Devices

Autoblocking devices like the Petzl Reverso, the Black Diamond ATC Guide, the Mammut Bionic Alpine, the CAMP PIU 2, and the myriad of others on the market are not covered in the Single Pitch Instructor curriculum. These devices are excellent multi-pitch devices and work well in a single pitch environment. However, many new instructors come into the AMGA Single Pitch Instructor Course with limited experience working with assisted braking devices and the Munter hitch. It is extremely important for instructors to understand how to use these tools, since they are the best tools for Single Pitch Instructor terrain. Students who move into the upper-level AMGA courses spend a great deal of time working with autoblocking devices, but at the beginner level, instructors must first have a baseline understanding of essential tools.

Though autoblocking devices are not part of the curriculum and candidates will not be tested on them, it was felt that they should be covered in this text. This is primarily because autoblocking devices are increasingly common at both single and multi-pitch crags throughout the country, and most students have been exposed to them.

Autoblocking devices are a hybrid between standard tube-style devices and plaquette-style devices. They can be used to belay a leader or to toprope, just like any other tube-style device. However, they have one additional feature. When belaying from above, they can be hung directly from the anchor by an additional carabiner hole and rigged to securely belay one or two climbers.

As with all climbing equipment, it's important to read the manufacturer's instructions. These devices vary and there are small differences between them. But the concept is the same. A bight of rope runs through the vertical slot on the front of the device, with the strand on top going to the climber



An autoblocking device set up in "guide mode," loaded with the climber strand on the top and the belay strand on the bottom.

and the belay strand on the bottom. This bight is secured to the back of the device with a locking carabiner. When weighted, the strand going to the climber squeezes the belay line, holding it in position and locking it off.

If these devices are loaded improperly, the autoblocking function will not engage. Always pull down on the climber's line after loading the device to ensure that it locks. If the climber's line moves easily, the device is not loaded properly.

Another reason this device is not taught in the SPI curriculum is that, when set up in autoblocking mode, it requires specialized techniques to unlock the device when it is loaded. It is important to understand that these devices, when in autoblock mode, were not designed for long lowers and are a poor choice for lowering a climber in single pitch terrain. Situations may arise that require unlocking an autoblocking device to lower a climber a short distance, and users should understand how that can be accomplished. Following are three methods.

Simple Lower by Ratcheting Carabiner

The first type of lower requires that a belayer crank the locking carabiner that secures the bight of rope back and forth. This allows the load to lower incrementally. This method is used for very short lowers. It is important for the belayer to keep the brake hand on the brake strand of the rope during this process.

Simple Lower with a Nut Tool or Carabiner

In the second lower, a nut tool or small carabiner is used to leverage the device. This method works well for lowers of one or two body lengths. Following is a breakdown of the lower:



A belayer ratchets the carabiner up and down to complete a short lower.

JASON D. MARTIN

1. Attach a friction hitch to the brake strand and clip it to the belayer's belay loop.
2. Put a nut tool or carabiner in the small hole in the bottom of the autoblocking device.
3. Crank the device up and back, "breaking" the autoblock's hold on the rope.
4. Maintain control of the brake strand while allowing the rope to pass slowly through the device.
5. Once the lower is complete, return the device to its original position.



Using a carabiner to open up the device in order to make a short lower.

JASON D. MARTIN

Complex Lower with a Redirect

This method can be used for moderate-length lowers. Again, if a longer lower is required, the system should be transferred to a more secure system. Following is a breakdown of the lower.

1. Tie off the backside of the rope with a catastrophe knot.
2. Attach a friction hitch to the brake strand and clip it to the belayer's belay loop.
3. Place a carabiner somewhere high in the anchor system, above the autoblocking device.
4. Redirect the brake strand through the carabiner high in the system.
5. Run a cord or a sling through the small hole in the bottom of the autoblocking device.
6. Thread the cord or sling through a second carabiner high in the system and attach it to the belayer's belay loop.
7. Untie the catastrophe knot.
8. Lean back on the redirected cord, "breaking" the system.
9. Maintain control of the brake strand while allowing the rope to pass slowly through the device.
10. Once the lower is complete, return the device to its original position.

Appendix D: Wilderness Medical Certifications

AMGA Single Pitch Instructors are required to hold and maintain a Wilderness First Aid (WFA) certificate if they intend to work in the frontcountry, or a Wilderness First Responder (WFR) certificate if they intend to work in the backcountry. If it will take you less than 2 hours to evacuate a student to definitive medical care, then you are working in the frontcountry. However, if it will take more than 2 hours, then you are working in the backcountry and you will need to hold a WFR certification.

A number of organizations throughout the United States offer WFA and WFR certifications, though not all certifications are the same. Some require recertification every two years, while others require it every three. Some companies have reciprocity with one another, while others do not. Be sure to do your research before committing to a certification course. You should know what you're getting into ahead of time and should be aware of how easy—or how hard—it will be to find recertification courses when your certification expires.

In addition to a WFA or WFR certification, instructors are required to hold and maintain a CPR certification.

Following is a breakdown of common wilderness first-aid medical certifications.

Wilderness First Aid (WFA)

This 16- to 30-hour program provides a baseline introduction to wilderness medicine. This course is recognized by the AMGA as a minimum requirement for individuals working in a frontcountry environment.

Wilderness First Responder (WFR)

This 70- to 90-hour certification course is considered a baseline requirement for most backcountry professionals in the United States. The AMGA recognizes this as a minimum level of training for those working in a backcountry wilderness environment.

Outdoor Emergency Care (OEC)

The National Ski Patrol developed the OEC as a first-aid program for members of the ski patrol who work at resorts. This program requires students to devote 80 to 100 hours to the course of study. The AMGA recognizes this as an equivalency to the Wilderness First Responder, as do many land managers.

Wilderness Emergency Medical Technician (WEMT)

The WEMT course meets all the requirements of an EMT course as well as the requirements of a WFR course. Most programs require four weeks of full-time intensive study. The AMGA recognizes this as a higher level of training than the WFR program.

Appendix E: Recommended Reading

Climbing instructors should have a strong understanding of the contents of a wide array of instructional climbing texts. The following are excellent resources for the Single Pitch Instructor candidate. The seasoned certified instructor may find these texts useful to supplement lessons.

Baseline Climbing Skills

Climbing Anchors. John Long and Bob Gaines. Globe Pequot Press/FalconGuides. Guilford, CT. 2013.

Rock Climbing Anchors: A Comprehensive Guide. Craig Luebben. The Mountaineers Books. Seattle, WA. 2007.

Rock Climbing: Mastering the Basic Skills. Craig Luebben. The Mountaineers Books. Seattle, WA. 2004.

Toproping. Bob Gaines. Globe Pequot Press/FalconGuides. Guilford, CT. 2012.

Rappelling. Bob Gaines. Globe Pequot Press/FalconGuides. Guilford, CT. 2013.

Advanced Climbing and Instructional Skills

Coaching Climbing. Michelle Hurni. Globe Pequot Press. Guilford, CT. 2002.

The Rock Warrior's Way: Mental Training for Climbers. Arno Ilgner. Desiderata Institute. La Vergne, TN. 2006.

Self Rescue, 2nd ed. David Fasulo. Globe Pequot Press/FalconGuides. Guilford, CT. 2011.

Technical Handbook for Professional Mountain Guides. American Mountain Guides Association. Boulder, CO. 1998.

Adventure Activities / Outdoor Leadership / Education

The Backcountry Classroom: Lessons, Tools and Activities for Teaching Outdoor Leaders. Jack Drury, Bruce Bonney, Dene Berman, and Mark Wagstaff. ICS Books. Merrillville, IN. 1992.

Best New Games. Dale N. LeFevre. Human Kinetics. Champagne, IL. 2002.

Cowstails and Cobras II: A Guide to Games, Initiatives, Ropes Courses & Adventure Curriculum. Karl Rohnke. Project Adventure, Inc. Hamilton, MA. 1998.

Islands of Healing: A Guide to Adventure Based Counseling. Jim Schoel, Dick Prouty, and Paul Radcliffe. Project Adventure. Beverly, MA. 1989.

Outdoor Leadership: Techniques, Common Sense and Self-Confidence. John Graham. The Mountaineers Books. Seattle, WA. 1997.

Soft Paths. David Cole, Bruce Hampton, and Dana Watts. Stackpole Books. Harrisburg, PA. 1998.

Appendix F: Climbing Instructor Employment Resources

The following resources may be helpful when searching for a job in the outdoor industry. Many of these provide a variety of job opportunities for outdoor educators, instructors, and guides, so pay close attention to find the job that is the right fit.

AMGA Newsletter

www.amga.com

After completing the AMGA Single Pitch Instructor Course, members will be placed on the American Mountain Guides Association mailing and e-mail lists. The AMGA's monthly newsletter includes listings for mountain guide and climbing instructor jobs.

The AMGA job board tends to lean heavily toward for-profit guide services.

AORE Listserv

www.aore.org

The Association of Outdoor Recreation and Education was designed to bring together outdoor professionals in college recreation and outdoor pursuits programs and community and military recreation programs for an annual conference. The yearly conference was designed for academic outdoor professionals to network and trade ideas.

AORE members have access to a listserv that has an academic focus, and many of the jobs are at universities or community colleges.

There is an annual fee to become a member of the AORE community.

Association for Experiential Education

www.aee.org

This is another association that has an academic focus. Like the AORE job announcements, this organization posts a wide array of jobs, from those at schools, to challenge courses, to climbing walls.

Backdoor Jobs

www.backdoorjobs.com/adventure.html

The Backdoor Jobs website is devoted to adventure tourism jobs including climbing and mountaineering, but also covers rafting, backpacking, and mountain biking guides.

Certified Guides Co-op

www.certifiedguidescooperative.com

The Certified Guides Co-op provides Single Pitch Instructors with significant professional work history an opportunity to gain access and insurance. The Co-op is designed for instructors with an established client base who wish to work independently of a guide service, school, or other organization. Instructors must have at least 200 days of single pitch instruction after they become certified instructors to apply.

Chronicle of Higher Education

www.chronicle.com

This is a university job board that focuses heavily on academic jobs.

Military Recreation Jobs

www.armymwr.com;
www.navymwr.org;
www.nafjobs.org;
www.usajobs.gov

As the military is extremely broad, so are the job resources. These are a select few websites where you may find outdoor recreation job opportunities on and around military bases.

Mountain Guide Jobs

www.mountainguidejobs.com

This is a site that provides a very short list of organizations and companies that are looking for climbing and mountaineering guides.

NOLS Jobs Announcements

www.nols.edu/alumni/contact/listservices.php

The NOLS Jobs Announcements is a listserv designed for outdoor professionals. It provides information on some NOLS-related jobs, but the majority of the listings are for adventure education jobs throughout the United States and Canada.

This listserv was designed with NOLS and Wilderness Medicine Institute alumni in mind. However, it does not discriminate against those who have not taken a NOLS course.

This is an extremely active job board, with dozens of new postings coming through every week.

Outdoor Adventure Professional Network

http://adventurejobs.co/

This particular site posts jobs in all the outdoor disciplines.

Outdoor Ed

www.outdoored.com

The Outdoor Ed website is a job-listing website that provides information on both seasonal and year-round adventure tourism jobs. Mountaineering and rock instruction jobs are regularly highlighted on the site.

Outdoor Industry Jobs

www.outdoorindustryjobs.com

This website is a dumping ground of outdoor industry–related jobs. There are some adventure educator and guide jobs on the site, but many of the jobs are retail and gear representation.

Rock Climbing Jobs

www.rockclimbingjobs.com

This site focuses on rock climbing jobs at adventure summer camps.

Northwest Information Exchange

http://groups.google.com/group/nw-information-exchange?pli=1

The Northwest Information Exchange is a place where instructors and guides in the Pacific Northwest trade information about current conditions in the mountains. However, guide service owners and staffing managers regularly post open positions on the listserv.

You will need to be actively working as a guide or instructor for a guide service to get access to the listserv.

San Juan Information Exchange

https://groups.google.com/forum/?hl=en-US#!forum/San-Juan-information-exchange

This is a guide conditions listserv like the Northwest Information Exchange. However, the focus of this exchange is the Ouray/Telluride/Silverton/Durango area of Colorado. Occasionally employment requests are sent out through the listserv.

Like the Northwest Exchange, you must be actively working in the field for a guide service to obtain access to the site.

Index

American Triangle, 162–63
anchoring
  to detached blocks, 102–3, 118, 126
  rock assessment and, 102–7
anchoring systems, 144–63
  about: overview of, 144–45
  anchor anatomy/principles (CAMS), 145–46
  Backside System, 175–79
  BARCK check, 185
  checking, 184–85
  CRASH check, 185
  creating master point over cliff edge, 167
  extensions with tether, 167
  instructor tether, 165–67
  Joshua Tree System, 168–72
  Lifeline System, 173–75
  redundancy and, 146–48, 181
  Three-in-One System, 179–81
  using setup rope, 164, 167
  V rigging with extension rope, 168–72
  V rigging with instructor tether, 173–75
  vectors and, 162–63
  See also load distribution
anchors
  anatomy and principles (CAMS), 145–46
  bolts, 136–43
  checking, 184
  fixed, 135–43
  monolithic, 112
  natural, 108–12
  pitons, 135–36
  tethering to, 218–20
assessing rocks, 102–7
assistance and rescue skills
  assistance from base, 221–27
  assistance from top, 227–30
  climber pickoff, 221–27
  coaching, 227
  3:1 assisted raise, 230
  3:1 raising system, 227–29
  vector pull, 227
assisted braking devices (ABDs), 195–96, 202–3, 204–5, 210
auditory (verbal) learners, 19
autoblock (“third hand”)
  as backup when lowering, 205–7
  function and tying, 100
  as rappel backup, 213–16
  rigged into belay loop, 215–16

backpacker (butterfly) coil, 39, 40–41
Backside System, 175–79
backup belayers, 199–201
BARCK check, 185
base-managed sites, 190–92
  advantages and disadvantages of, 190
  assistance from. *See* assistance and rescue skills
  backup belayers, 199–201
  belaying in, 196–98
  ground anchors and, 190–92, 236
  for high-ratio instruction, 190
  perspective on top-managed and, 187
“Belay off” signal, 195
“Belay on” signal, 194
belaying
  autoblock as backup when lowering, 205–7
  backup belayers, 199–201
  in base-managed sites, 196–98. *See also* base-managed sites
  devices for, 192–96
  fundamental principles of, 192
  hip belay, 193
  indirect belay, 203
  leading guidelines. *See* leading
  lowering from top-managed site, 204
  lowering with assisted braking device, 204–5
  lowering with Munter hitch, 204, 205–7
  with Munter hitch, 201, 202–3
  PBUS method, 234–35
  redirected belay, 203
  standard signals for, 194–95
  systems checks, 184–85
  in top-managed sites, 201–4. *See also* top-managed sites
  two-rope toprope setups, 199
  See also rappelling
bends, 80–82
  about: purpose of, 80
  double fisherman’s knot, 81
  figure eight bend (Flemish bend), 80, 83
  triple fisherman’s knot, 82
BHK (“Big Honking Knot”)
  Backside System and, 175–77
  function and tying, 72–73
  loading backside of, 177
bolts, 136–43

bowline, 70–71
bowline, double loop, 76–77
butterfly (backpacker) coil, 39, 40–41

camming devices (SLCDs), 123–35
CAMS, 145–46
carabiners, 52–61
  array of designs/applications, 52
  autolock or twistlock, 56–57
  basic design, 52–53
  D-shaped, 54, 57
  loading guidelines, 57–60
  locking, 52, 53–57
  oval, 52, 53, 57, 59
  pear-shaped, 52, 54, 55
  screwgate, 54–56
  strength ratings, 57
  tying Munter hitch on, 88–89
  when to retire, 61
  wiregate, 52, 53
catastrophe knot, 201, 246
children
  liability and minors, 10
  minimum age for, 24
  taking kids climbing, 24–26
chockcraft evolution, 112–23
"Climb on" signal, 194
climber pickoff, 221–27
climbing instructor
  instructor meetings, 16
  professionalism, 3–5
  risk management. *See risk management references*
  role of, 1
  stewardship, 14–16
  teaching skills. *See* teaching, art of
climbing movement
  bipeds becoming quadrupeds, 26–27
  teaching, 26–27. *See also* teaching, art of
  terrain-specific movement, 27
"Climbing" signal, 194
climbing signals, standard, 194–95
closing the system, 184
clove hitch, 85, 86
coaching, 227
coiling and uncoiling ropes, 39–43
communications plan, 9
contacts, post-trip, 10
cordelettes and cords
  anchoring solution, 151–54
  instructor tether, 165–67
  the quad, 157–58
  rigging, 153
  types and characteristics, 50–52
  See also ropes
CRASH check, 185

debrief, incident, 10
descent options, 237
directional (in-line) figure eight, 68–69
double fisherman's knot, 78–79, 81, 83
double loop knots, 72–78
  BHK ("Big Honking Knot"), 72–73
  double loop bowline, 76–77
  double loop figure eight, 74–75
dry coating ropes, 37–38
dynamic ropes, 34–35, 36
Dyneema and Spectra slings, 47–49

elevators, 209
equalette, 160–62
equipment basics, 28–61
  autoblocking devices, 244–46
  belay devices, 192–96
  harnesses, 28–30
  helmets, 31–32
  knives, 44
  pack and its contents, 61
  slings and webbing, 44–49
  See also carabiners; ropes
ethics, leave no trace, 240–41
Euro Death Knot (flat overhand), 84–85
evacuation plan, 9
extensions
  creating master point over cliff edge, 167
  pre-equalized (Backside System), 175–79
  V rigging with, 168–72

failure, fear of, 12
fall factor, determining, 242–43
falling hazards, 185–86
"Falling!" signal, 195
fear, of heights/of failure, 12
figure eight bend (Flemish bend), 80, 83
figure eight follow-through, 64–65
figure eight loop, 66–67. *See also* double loop knots; in-line (directional) figure eight
financial risk, 12–14
fireman's belay, 208
first-aid requirements, 9
fisherman's knots
  double, 78–79, 81, 83
  triple, 82
fixed lines, 231–33
flakes, avoiding, 102–7, 118, 126
flat overhand (Euro Death Knot), 84–85
Flemish bend (figure eight bend), 80, 83

grapevine knot. *See* double fisherman's knot
ground anchors
  base-managed sites and, 190–92
  checking, 184
  student belay backups, knots and, 236

harnesses
  about, 28–30

- checking, 184–85
heights, fear of, 12
helmets, 31–32
Hexcentric (Hex), 116, 119, 121, 122
hip belay, 193
hitches. *See knots and hitches references*

inattentional blindness, 183
incident debrief, 10
indirect belay, 203
in-line (directional) figure eight, 68–69
instructional site
- base-managed. *See* base-managed sites
- professionalism at, 4–5
- for rappelling, selecting, 208
- top-managed. *See* top-managed sites

instructor meetings, 16
instructor tether, 165–67

Joshua Tree System, 168–72

kernmantle ropes, 32–34
kinesthetic learners, 19
klemheist knot, 98–99
knives, 44
knots and hitches, categories
- about: knot terminology definitions, 62
- bends, 80–82
- double loop knots, 72–78
- hitches, 85–100
- for joining two ropes, 83–85
- loop knots, 62–71
- stopper knot, 101
- for webbing (water knot and double fisherman's knot), 78–79

knots and hitches, specific
- BHK ("Big Honking Knot"), 72–73
- bowline, 70–71
- catastrophe knot, 201, 246
- clove hitch, 85, 86
- double fisherman's knot, 78–79, 81, 83
- double loop bowline, 76–77
- double loop figure eight, 74–75
- figure eight bend (Flemish bend), 80, 83
- figure eight follow-through, 64–65
- figure eight loop, 66–67
- flat overhand (Euro Death Knot), 84–85
- in-line (directional) figure eight, 68–69
- klemheist knot, 98–99
- mule knot, 92–97
- overhand loop, 62–63
- prusik knot, 97–98
- slip hitch, 85, 87
- stopper knot, 101
- triple fisherman's knot, 82
- tying off tube device on carabiner spine, 96
- tying off tube device with mule knot in front of device, 94–95
- water knot, 78, 79
- *See also* autoblock ("third hand"); Munter hitch

leading, 234–39
- decent options, 236
- ground anchors, student belay backups, and knots, 236
- student-lead belay training, 234–36
- teaching student to lead, 237–39

learning from mistakes, 22–23
learning styles, 17–19
leave no trace ethics, 240–41
lesson planning, 20–22
lessons, harsh, 22
liability
- guidelines/exposure to, 11–12
- minors and, 3
- release forms, 10–11

Lifeline System, 173–75
load distribution, 148–62
- about: overview of, 148–51
- cordelette solution, 151–54
- equalette for, 160–62
- the quad for, 157–58
- sliding X for, 154–56
- stacked sliding Xs for, 159–60

loop knots, 62–71
- bowline, 70–71
- figure eight follow-through, 64–65
- figure eight loop, 66–67
- in-line (directional) figure eight, 68–69
- overhand loop, 62–63

loop strength, 47
"Lower me (or Ready to lower)" signal, 194–95
lowering
- with assisted braking device, 204–5
- autoblock as backup when, 205–7
- with Munter hitch, 204
- from top-managed sites, 204

"Lowering" signal, 195
low-stretch ropes, 36, 37

magic X. *See* sliding X
medical certifications, wilderness, 247
minors. *See* children
mistakes
- avoiding. *See risk management references*
- learning from, 22–23

mountaineer's coil, 39, 42–43
movement. *See* climbing movement
mule knot, 92–97

Munter hitch
  belaying with, 201, 202–3
  lowering with, 204, 205–7
  Munter/mule/overhand combination, 211, 212
  tying, 85, 88–91

natural anchors, 108–12
nut placement, assessing, 118

objectives (unit and student-learning), 20, 21
“Off belay” signal, 195
“On belay?” signal, 194
Outdoor Emergency Care (OEC) program, 247
overhand loop, 62–63

pack, of instructor, 61
PBUS method, 197, 234–35
pedagogy. *See* teaching, art of
permitting, 7–9
physical risk, 14. *See also risk management references*
pitons, 135–36
post-trip contact, 10
professionalism, 3–5
  at instructional site, 4–5
  pre-program preparations, 3–4
programming, 7–16
  about: overview of, 7
  instructor meetings, 16
  permitting, 7–9
  stewardship, 14–16
  See also risk management references
protection
  active, 123–35
  avoiding flakes, 102–7, 118, 126
  camming devices (SLCDs) for, 123–35
  chockcraft evolution, 112–23
  passive, 112–23
  rock assessment, 102–7
  See also anchoring/anchors references
prusik knot, 97–98
psychological risk, 12

quad, the, 157–58

rappelling, 208–20
  avoiding accidents (3 scenarios), 216–20
  extended master point for belay strand, 210
  fireman’s belay and, 208
  instructor backup, 210–16
  not clipping both strands on double-rope rappel, 217
  not tethering to anchor, 218–20
  off one/both ends of rope, 217
  rigging for contingencies, 208
  site selection, 208
  student rappel belays, 208–10
  systems check, 217
  teaching, 208
  transitioning from rigging to, 175–79, 181
  troubleshooting device/rope problems, 210
reading materials, additional, 248
redirected belay, 203
redundancy, 146–48, 181
release forms, 10–11
rescue skills. *See* assistance and rescue skills
resources, other
  instructor employment resources, 249–51
  reading materials, 248
risk management
  communications plan, 9
  evacuation plan, 9
  first-aid requirements, 9
  incident debrief, 10
  minors precaution, 10
  post-trip contact, 10
  risk/liability release forms, 10–11
  screening participants, 9
  at site. *See* risk management, in field
  student safety briefing, 10
risk management, in field, 182–86
  avoiding repelling accidents, 216–20
  closing the system, 184
  falling hazards, 185–86
  fear of failure, 12
  fear of heights, 12
  financial risk, 12–14
  importance of, 182–83
  inattentional blindness and, 183
  other considerations, 186
  physical risk, 14
  psychological risk, 12
  rockfall hazards, 183
  sociological risk, 12
  standard climbing signals, 194–95
  systems checks, 184–85, 194, 217
  terrain hazards, 184
rock assessment, 102–7
“ROCK!” signal, 195
rockfall hazards, 183
rockslide, 103
role of climbing instructor, 1
rope direct belay, 146–47
ropes, 32–43
  care and use, 38–39
  coiling and uncoiling, 39–43
  diameter and sheath percentage, 36–37
  dry coating, 37–38
  dynamic, 34–35
  dynamic vs. low-stretch, 36
  fixed lines, 231–33
  history of, 32

  kernmantle, 32–34
  knots for joining, 83–85
  length of, 38
  low-stretch, 36, 37
  sharp edge resistance, 37
  static, 35–36
  static elongation, 37
  See also cordelettes and cords

safety. *See* risk management
screening participants, 9
setup rope
  with components far apart, 164
  systems using, 167
  two-rope toprope setups, 199
signals, standard, 194–95
site. *See* instructional site
"Slack" signal, 194
SLCDs (camming devices), 123–35
sliding X, 154–56
sliding Xs, stacked, 159–60
slings and webbing, 44–49
  flat webbing, 44
  girth-hitching slings together, 49
  knots for webbing (water knot and double fisherman's knot), 78–79
  masking tape splice precaution, 47
  Spectra and Dyneema slings, 47–49
  strength ratings (tensile vs. loop strength), 47
  tubular webbing, 44–47
slip hitch, 85, 87
sociological risk, 12
Spectra and Dyneema slings, 47–49
stacked sliding Xs, 159–60
static elongation, of ropes, 37
static ropes, 36
stewardship, 14–16
stopper knot, 101
strength ratings
  carabiners, 57
  ropes (tensile vs. loop strength), 47
student lead belay training, 234–36
student rappel belays, 208–10
student safety briefing, 10
swami belt, 28
systems checks, 184–85, 194, 217

"Take (or tension)" signals, 194
teachable moments, 23
teaching, art of, 17–27
  about: overview of, 17
  climbing movement, 26–27
  learning from mistakes, 22–23
  learning styles and, 17–19
  lesson planning, 20–22
  objectives (unit and student-learning), 20, 21
  qualities of good teachers, 26
  taking kids climbing, 24–26
  teachable moments and, 23
tensile strength, 47
"Tension (or take)" signals, 194
"Tension on (or I've got you)" signal, 194
terrain hazards, 184
tether, instructor, 165–67
tethering to anchor, 218–20
"That's me!" signal, 195
"third hand." *See* autoblock ("third hand")
3:1 assisted raise, 230
3:1 raising system, 227–29
Three-in-One System, 179–81
top-managed sites, 187–90
  advantages of, 187
  assistance from. *See* assistance and rescue skills
  belaying in, 201–4
  disadvantages of, 189
  establishing site, 189–90
  lowering from, 204
  for low-ratio instruction, 189
  mitigating risks, 189–90
  perspective on base-managed and, 187
toprope setups, two-rope, 199
Tricam, 117–18, 119
triple fisherman's knot, 82

"Up rope" signal, 194

V rigging with extension rope, 168–72
V rigging with instructor tether, 173–75
vector pull, 227
vectors, 162–63
verbal (auditory) learners, 19
visual learners, 18–19

"Watch me!" signal, 195
water knot, 78, 79
webbing. *See* slings and webbing
Wilderness Emergency Medical Technician (WEMT), 247
Wilderness First Aid (WFA) certificate, 9, 247
Wilderness First Responder (WFR) certificate, 247

Z system (3:1 raising system), 227–29

About the Authors

Bob Gaines began rock climbing at Joshua Tree in the 1970s. Since then he has pioneered over 400 first ascents in the park. Bob began his career as a professional rock climbing guide in 1983 and is the owner of Vertical Adventures Rock Climbing School, which offers classes and guided climbs at Joshua Tree. In 2008 Vertical Adventures was voted the number 1 rock climbing school in America by *Outside* magazine.

Bob has worked extensively in the film business as a climbing stunt coordinator. He has coordinated over forty television commercials, and he was Sylvester Stallone's climbing instructor for the movie *Cliffhanger.* Bob is an AMGA Certified Rock Climbing Instructor and currently teaches the AMGA Single Pitch Instructor Course at Joshua Tree. He has worked extensively training US military special forces, including US Navy Seal Team 6, and is known for his technical expertise in anchoring and rescue techniques.

Bob is also the author of *Best Climbs Joshua Tree, Best Climbs Tahquitz and Suicide Rocks, Toproping, Rappelling,* and the co-author of *Climbing Anchors* (with John Long).

Jason D. Martin is an AMGA Certified Rock Guide, the operations director at the American Alpine Institute, and a freelance writer. He has been teaching the AMGA Single Pitch Instructor Course since the program's inception in 2008. Much of Jason's adventure writing revolves around the work he does in the mountains. Jason has professionally guided in the Cascades, the Sierra, Red Rock Canyon, Joshua Tree National Park, the Alaska Range, the Coast Mountains of Canada, and in the Andes of Bolivia, Ecuador, and Peru. He wrote the guidebook *Fun Climbs Red Rocks: Topropes and Moderates* and co-authored *Washington Ice: A Climbing Guide.* His writing has appeared in the *Seattle Post Intelligencer, San Antonio Current, Mt. Baker Experience, Northwest Mountaineering Journal, Climbing* magazine, and in numerous other publications. He currently manages the American Alpine Institute blog (blog.alpineinstitute.com), generating numerous climbing and outdoor articles every week. In addition to his work as an outdoor writer and guide, Jason is also a playwright and film critic.

FIND A GUIDE » BECOME ONE
AMERICAN MOUNTAIN GUIDES ASSOCIATION
1979
AMGA.COM

The official manual used by the AMGA to teach single pitch rock climbing

"I've been waiting for this book for a long time. Professionalism, programming, pedagogy, anchors . . . this is a comprehensive resource for understanding the complexities of teaching in the single pitch environment. Highly recommended!"
—Arno Ilgner, AMGA Single Pitch Instructor and author of *The Rock Warrior's Way: Mental Training for Climbers*

"If you want a thorough treatise on what to expect in the [AMGA SPI] course, as well as a ton of information on climbing gear and its evolution, this book will fill your needs. Even if you don't intend to take the course and just want to know what are considered best practices by the AMGA, the answers are here."
—Russ Clune, AMGA Single Pitch Instructor and standard-setting Gunks first ascentionist

Rock Climbing: The AMGA Single Pitch Manual is intended to serve as a textbook for past and future participants of the American Mountain Guide Association's Single Pitch Instructor program. The book builds upon Bob Gaines' book *Toproping* to more specifically address the needs of the professional climbing instructor and advanced recreational climbers. It presents the most current, internationally recognized standards for technical climbing systems used in single pitch rock terrain. Included are chapters on effective teaching in the outdoor environment, risk management, professionalism, and rescue.

Bob Gaines has been a professional rock climbing guide since 1983. He is the owner of Vertical Adventures Rock Climbing School, voted the top rock climbing school in America by *Outside* magazine. An AMGA Certified Rock Instructor and AMGA Single Pitch Instructor Program Provider, he is the author of *Best Climbs Joshua Tree National Park, Best Climbs Tahquitz and Suicide Rocks, Rappelling,* and *Toproping*, and the coauthor of *Climbing Anchors* (all FalconGuides). Visit him at verticaladventures.com.

Jason D. Martin is a professional guide, writer, and the director of operations at the American Alpine Institute. He has guided in Red Rock Canyon, Joshua Tree National Park, the Cascades, the Sierra, the Alaska Range, Canada's Coast Range, and the Andes of Ecuador, Bolivia, and Peru. An AMGA Certified Rock Guide and an AMGA Single Pitch Instructor Program Provider, he is also a playwright, film critic, and outdoor adventure writer. He coauthored *Washington Ice: A Climbing Guide* and authored *Fun Climbs Red Rocks: Topropes and Moderates.* Visit him at alpineinstitute.com.

Front cover photo by Bob Gaines

facebook.com/AMGAUSA

@amgausa

made in the USA

Join our community

$21.95 / Canadian $23.95
ISBN 978-0-7627-9004-3
52195
9 780762 790043

Essential gear for every adventure: **Outfit Your Mind**®

FALCONGUIDES®

Rock Climbing

FALCON GUIDES®
falcon.com

FalconGuides®
is an imprint of
Globe Pequot Press

A FALCON GUIDE®

HOW TO CLIMB® SERIES

Rock Climbing
The AMGA Single Pitch Manual

BOB GAINES AND
JASON D. MARTIN

The official manual used by the AMGA to teach single pitch rock climbing

“I’ve been waiting for this book for a long time. Professionalism, programming, pedagogy, anchors . . . this is a comprehensive resource for understanding the complexities of teaching in the single pitch environment. Highly recommended!”
—Arno Ilgner, AMGA Single Pitch Instructor and author of *The Rock Warrior’s Way: Mental Training for Climbers*

“If you want a thorough treatise on what to expect in the [AMGA SPI] course, as well as a ton of information on climbing gear and its evolution, this book will fill your needs. Even if you don’t intend to take the course and just want to know what are considered best practices by the AMGA, the answers are here.”
—Russ Clune, AMGA Single Pitch Instructor and standard-setting Gunks first ascentionist

Essential gear for every adventure: **Outfit Your Mind**®

Rock Climbing: The AMGA Single Pitch Manual is intended to serve as a textbook for past and future participants of the American Mountain Guide Association’s Single Pitch Instructor program. The book builds upon Bob Gaines’ book *Toproping* to more specifically address the needs of the professional climbing instructor and advanced recreational climbers. It presents the most current, internationally recognized standards for technical climbing systems used in single pitch rock terrain. Included are chapters on effective teaching in the outdoor environment, risk management, professionalism, and rescue.

Bob Gaines has been a professional rock climbing guide since 1983. He is the owner of Vertical Adventures Rock Climbing School, voted the top rock climbing school in America by *Outside* magazine. An AMGA Certified Rock Instructor and AMGA Single Pitch Instructor Program Provider, he is the author of *Best Climbs Joshua Tree National Park*, *Best Climbs Tahquitz and Suicide Rocks*, *Rappelling*, and *Toproping*, and the coauthor of *Climbing Anchors* (all FalconGuides). Visit him at verticaladventures.com.

Jason D. Martin is a professional guide, writer, and the director of operations at the American Alpine Institute. He has guided in Red Rock Canyon, Joshua Tree National Park, the Cascades, the Sierra, the Alaska Range, Canada’s Coast Range, and the Andes of Ecuador, Bolivia, and Peru. An AMGA Certified Rock Guide and an AMGA Single Pitch Instructor Program Provider, he is also a playwright, film critic, and outdoor adventure writer. He coauthored *Washington Ice: A Climbing Guide* and authored *Fun Climbs Red Rocks: Topropes and Moderates*. Visit him at alpineinstitute.com.

Front cover photo by Bob Gaines

facebook.com/AMGAUSA

@amgausa

made in the USA

Join our community

$21.95 / Canadian $23.95
ISBN 978-0-7627-9004-3
52195
9 780762 790043

FALCONGUIDES®

Rock Climbing

FALCON GUIDES®
falcon.com

FalconGuides®
is an imprint of
Globe Pequot Press

A
FALCON
GUIDE®

HOW TO CLIMB® SERIES

Rock Climbing

The AMGA Single Pitch Manual

BOB GAINES AND
JASON D. MARTIN



RSMeans

ILLUSTRATED CONSTRUCTION DICTIONARY

STUDENT EDITION


31'-4"
30'-9"
10"
8'-0"
1'-1"
31'-9"
10"
19'-10"
FLOOR S.J. COVER
SEE DTL. 8/A8.01
GLUED
SURFACE MOUNTED
WALK-OFF MAT
VEST.
19' T.B.
DATUM
LINE
FACE OF
EX. FOUNDATION
SEE STRUCT. DWGS.
INT. S.J.
COVER
SEE DET.
4/A8.01
18'-5"
CLASSROOM
CLASSROOM
O.H.

RS**Means**
ILLUSTRATED
CONSTRUCTION
DICTIONARY

RSMeans
Illustrated Construction Dictionary

Student Edition

WILEY
John Wiley & Sons, Inc.
RSMeans

Cover image: Courtesy of RSMeans
Cover design: Michael Rutkowski
This book is printed on acid-free paper. ♾
Copyright © 2012 by R.S. Means Company LLC. All rights reserved.
Published by John Wiley & Sons, Inc., Hoboken, New Jersey.
Published simultaneously in Canada.

No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording, scanning, or otherwise, except as permitted under Section 107 or 108 of the 1976 United States Copyright Act, without either the prior written permission of the Publisher, or authorization through payment of the appropriate per-copy fee to the Copyright Clearance Center, Inc., 222 Rosewood Drive, Danvers, MA 01923, 978-750-8400, fax 978-646-8600, or on the web at www.copyright.com. Requests to the Publisher for permission should be addressed to the Permissions Department, John Wiley & Sons, Inc., 111 River Street, Hoboken, NJ 07030, 201-748-6011, fax 201-748-6008, or online at http://www.wiley.com/go/permissions.

Limit of Liability/Disclaimer of Warranty: While the publisher and author have used their best efforts in preparing this book, they make no representations or warranties with the respect to the accuracy or completeness of the contents of this book and specifically disclaim any implied warranties of merchantability or fitness for a particular purpose. No warranty may be created or extended by sales representatives or written sales materials.The advice and strategies contained herein may not be suitable for your situation. You should consult with a professional where appropriate. Neither the publisher nor the author shall be liable for damages arising herefrom.

For general information on our other products and services, or technical support, please contact our Customer Care Department within the United States at 800-762-2974, outside the United States at 317-572-3993 or fax 317-572-4002.

Wiley publishes in a variety of print and electronic formats and by print-on-demand. Some material included with standard print versions of this book may not be included in e-books or in print-on-demand. If this book refers to media such as a CD or DVD that is not included in the version you purchased, you may download this material at http://booksupport.wiley.com.

For more information about Wiley products, visit our Web site at www.wiley.com.

Library of Congress Cataloging-in-Publication Data:

RSMeans illustrated construction dictionary. — Student ed.

p. cm.

ISBN 978-1-118-13352-1 (pbk.); 978-1-118-35170-3 (ebk.); 978-1-118-35171-0 (ebk.); 978-1-118-35315-8 (ebk.); 978-1-118-35316-5 (ebk.); 978-1-118-35318-9 (ebk.)
1. Rev. ed. of Means illustrated construction dictionary. 2003. 2. Building—Dictionaries. 3. Construction industry—Dictionaries. I. R.S. Means Company. II. Means illustrated construction dictionary. III. Title: Illustrated construction dictionary.

TH9.M42 2013
624.03—dc23

2012009782

Printed in the United States of America
10 9 8 7 6 5 4 3 2 1

Contents

Preface vii

Acknowledgments ix

Terms and Definitions 1

Appendix 355

Preface

RSMeans Illustrated Construction Dictionary, Student Edition is a must-have companion to any construction-related curriculum. The engineering staff at RSMeans has edited the original *RSMeans Illustrated Construction Dictionary* to apply specifically for the student. Terms are defined in easy-to-understand language, and supplemented by over 1,400 illustrations. In addition to a higher percentage of illustrations, many illustrations new to this Student Edition have been added to make learning easier.Whenever possible, words or phrases are explained in non-technical language. When technical terms are used, they are also defined as separate entries. Very old architectural terms are purposely omitted, as this is intended to be a current construction dictionary with up-to-date terminology. A useful appendix illustrates and identifies the symbols that a building professional is likely to encounter.

Terms for new construction trends, such as BIM, building automation, energy and environmental conservation, "green" construction practice, engineered lumber products, the newest seismic technologies, and historic preservation are also covered. The editors obtained the assistance of industry groups, associations, societies, and manufacturers, as well as published authors who are nationally recognized authorities, to achieve this comprehensive construction trades, practices, and equipment dictionary.

Acknowledgments

This edition would not have been possible without the work of the RSMeans engineering staff. The editors also thank John Schaufelberger at the University of Washington and Clark Cory of Purdue University for their review of the material and recommended revisions for this student edition. Finally, a special thanks to the American Association of Cost Estimators (AACE) for allowing us to reprint some of their invaluable cost engineering terminology.

A

Abbreviations

a acre, ampere
A area, area square feet, ampere

A&E architect-engineer

AAMA Architectural Aluminum Manufacturers Association

AASHTO American Association of State Highway and Transportation Officials

ABC aggregate base course, Associated Builders and Contractors

ABS acrylonitrile butadiene styrene, asbestos-bonded steel

ABT air blast transformer, about

ac, a-c, a.c. alternating current

a.c. asphaltic concrete (a.c. paving)

AC air conditioning, alternating current (on drawings), armored cable (on drawings), asbestos cement

ACB asbestos-cement board, air circuit breaker

ACC accumulator

Access. accessory

ACD automatic closing device

ACEC American Consulting Engineers Council

ACGIH American Conference of Governmental Industrial Hygienists

ACI American Concrete Institute, Association of Construction Inspectors

ACM asbestos-containing material, asbestos-covered metal

ACS American Ceramic Society

ACSR aluminum cable steel reinforced, aluminum conductor steel reinforced

Acst acoustic

Actl actual

a.d. air-dried

AD access door, air-dried, area drain, as drawn

ADA Americans with Disabilities Act

ADAAG Americans with Disabilities Act Accessibility Guidelines

ADD addendum (on drawings), addition (on drawings)

Addit additional

ADF after deducting freight (used in lumber industry)

ADH adhesive

ADI after date of invoice

adj adjacent, adjoining, adjust, adjustable

ADS automatic door seal

af audio frequency

AFE Association for Facilities Engineering (formerly the American Institute of Plant Engineers)

AFL-CIO American Federation of Labor and the Committee for Industrial Organization

AFUE Annual fuel utilization efficiency

AG above grade

AGA American Gas Association

AGC Associated General Contractors

Agg, Aggr aggregate

AGL above ground level

AH, A HR, amp hr ampere-hour

AHERA Asbestos Hazard Emergency Response Act

AHU air-handling unit

AI Asphalt Institute

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

AIA American Institute of Architects, Asbestos Information Association

AIC ampere interrupting capacity

AIEE American Institute of Electrical Engineers

AIMA Acoustical and Insulating Materials Association

AISC American Institute of Steel Construction

AISE Association of Iron and Steel Engineers

AISI American Iron and Steel Institute

AITC American Institute of Timber Construction

AL, alum aluminum

Allow, ALLOW allowance

ALM alarm

ALS American Lumber Standards

alt altitude

ALT alternate

ALTN alteration

ALY alloy

AM ante meridiem

AMB asbestos millboard

AMD air-moving device

amp, Amp ampere

ANFO ammonium nitrate fuel oil mix

ANL anneal

Anod anodized

ANSI American National Standards Institute

AP access panel

APA The Engineered Wood Association (formerly the American Plywood Association)

APC acoustical plaster ceiling, American Plastics Council

APF acid-proof floor

API American Petroleum Institute

APPA The Association of Higher Education Facilities Officers (formerly the Association of Physical Plant Administrators)

Appd approved

Approx approximate

APR air-purifying respirator

Apt apartment

APW Architectural Projected Window

AR as required, as rolled

ARC W, ARC/W arc weld

ARS asbestos roof shingles

ART artificial

AS automatic sprinkler

ASA American Standards Association

asb asbestos

ASBC American Standard Building Code

asbe asbestos worker

ASC asphalt surface course

ASCE American Society of Civil Engineers

ASCII American Standard Code for Information Interchange

ASEC American Standard Elevator Codes

ASES American Solar Energy Society

ASHRAE American Society of Heating, Refrigeration, and Air-Conditioning Engineers

ASIS American Society for Industrial Security

ASME American Society of Mechanical Engineers

asph asphalt

ASR automatic sprinkler riser

ASSE American Society of Sanitary Engineering

ASTM American Society for Testing and Materials

AT asphalt tile, airtight

ATB asphalt-tile base

ATC acoustical tile ceiling; architectural terra-cotta, automatic temperature control

ATF asphalt-tile floor

atm atmosphere, atmospheric

aux auxiliary

av, ave, avg average

A/W all-weather

AW actual weight

AWEA American Wind Energy Association

AW&L all widths and lengths

AWG American wire gauge

AWI Architectural Woodwork Institute

AWPI American Wood Preservers Institute

AWS American Welding Society

AWWI American Wood Window Institute

Definitions

abaciscus, abaculus **1.** A tessara or small square stone used in mosaic tile. **2.** A small abacus.

abamurus A masonry buttress for the support of a wall.

abandonment **1.** To surrender the right or claim of interest without specifically transferring it. **2.** The act of deserting one's obligations under a contract frequently manifested by removing personnel, materials, and equipment from the job site.

abate **1.** To cut away in stone or to beat down on metal in order to create figures or a pattern in relief. **2.** To reduce or decrease concentrations of pollutants.

abatement **1.** The encapsulation or removal of building materials containing pollutants (such as lead or asbestos) to prevent the release of or exposure to fibers. **2.** In lumber industry, the amount of wood lost as waste during the process of sawing or planning.

abatvent A wall louver that restricts wind from entering a building, but admits light and air.

abatvoix An acoustical reflector for a single voice, such as behind and over a church pulpit.

ABC extinguisher A fire extinguisher suitable for use on type A, B, and C fires.



ABC extinguisher

A-block A hollow masonry unit with one closed end commonly used at wall openings.



A-block

Abney level A handheld level used for measuring elevations and vertical angles.



Abney level

above finished floor Datum or benchmark for measuring the height above a floor, abbreviated as AFF.

above-grade subfloors A floor above ground level, but with no headroom below.

abrade To scrape or wear away a surface by friction or striking.

Abrams' law The rule stating that with given materials, curing, and testing conditions, concrete strength is inversely related to the ratio of water to cement. Low water-to-cement ratios produce high strengths.

abrasion resistance index A comparison of the abrasion resistance of a given material to that of rubber. The index is applied principally to aggregate handling equipment.

abrasive **1.** A hard material used for wearing away or polishing a surface by friction. **2.** The material that is adhered to or embedded in a surface such as sandpaper or a whetstone.

abrasive blasting A method of cleaning surfaces with a high-pressure stream of air and an abrasive material such as sand or steel grit.

abrasive floor A floor with an abrasive adhered to or embedded in the surface to provide traction and prevent slipping.

abrasive floor tile Floor tile with an abrasive adhered to the surface.

abrasive nosing A strip of anti-skid abrasive adhered to or attached to the nosing of a stair tread.

abrasive stair tread A stair tread with an abrasive surface.

abrasive terrazzo A terrazzo floor with an abrasive surface rather than a high polish.

abreuvoir The mortar joint between masonry units.

absorbed moisture Moisture that has been absorbed by a solid such as masonry.

absorbent **1.** A material that has an affinity for certain substances and attracts these substances from a liquid or gas with which it is in contact, thus changing the physical and/or chemical properties of the material. **2.** A substance that attracts and holds large quantities of liquid.

absorber **1.** A device containing liquid for the absorption of vapors. **2.** In a refrigeration system, the component on the low-pressure side used for absorbing refrigerant vapors.

absorber plate That part of a solar energy system that collects the solar energy.



absorber plate

absorption **1.** The process by which a liquid is drawn into and fills permeable pores in a solid body, increasing its weight. **2.** The process by which solar energy is collected on a surface. **3.** The increase in weight of a porous object resulting from immersion in water for a given time, expressed as a percent of the dry weight.

absorption air conditioning An air cooling and dehumidifying system powered by solar or other energy collected on absorbing plates.

absorption bed or field (disposal field, drain field) A network of trenches that may contain coarse aggregate and distribution pipe and is used to distribute septic tank effluent into the surrounding soil.

absorption chiller Heat-operated refrigeration unit that uses an absorbent (lithium bromide) as a secondary fluid to absorb the primary fluid (water), which is a gaseous refrigerant in the evaporator. The evaporative process absorbs heat, thereby cooling the refrigerant (water), which in turn cools the chilled water circulating through the heat exchanger.

absorption loss **1.** Water losses that occur until soil particles are sufficiently saturated, such as in filling a reservoir for the first time. **2.** Water losses that occur until the aggregate in a concrete mix is saturated.

absorption rate (initial rate of absorption) **1.** The weight of water absorbed by a brick or concrete masonry unit that is partially immersed in water for one minute, expressed in grams or ounces per minute. **2.** The annual rate at which new housing or leasable space is being sold or leased. The absorption rate of a prior year often is used to predict the needs for next year. (A gross absorption rate measures the consumption of new housing/space only.)

absorption-type liquid chiller A system using an absorber, condenser, and associated accessories to cool a secondary liquid.

ABS plastic pipe Acrylonitrile-butadiene-styrene plastic pipe, which is resistant to heat, impact, and chemicals.

abstract of bids A list of the bidders for a sealed bid procurement indicating the significant portions of their bids.

abstract of title A deed for a parcel of land showing encumbrances and a history of ownership.

abut To join or touch at one edge or end without overlapping.

abutment (butment) **1.** The structure that supports the end of a bridge or arch or that anchors the cables of a suspension bridge. **2.** The surface at which one member meets another.

abutment piece In structural framing, the horizontal member that distributes the load of vertical members and is thus the sole plate of a partition.



abutment piece

abuttals The properties adjacent to a parcel of land or body of water and which mark the boundaries of that land or water body.

abutter A property owner contiguous or within a specified distance from a parcel of land.

Accelerated Cost Recovery System (ACRS) A method of calculating depreciation of assets placed in service from 1980 to 1986 for federal income tax purposes. Replaced by the Modified Accelerated Cost Recovery System (MACRS) by the Tax Reform Act of 1986.

accelerated depreciation Asset depreciation at a faster rate than the straight-line method. Examples include the 200% or 150% declining balance methods.

accelerating admixture An admixture for hydraulic concrete that shortens setting time and inhibits early strength development.

accelerator An additive that, when added to paint, concrete, mortar, or grout mix, speeds the rate of hydration and thereby causes it to set or harden sooner.

accelograph An instrument used to measure displacement during an earthquake. Often installed in buildings to measure movement.

accent lighting Fixtures or directional beams of light arranged so as to bring attention to an object or area.

acceptance Compliance by an offeree with the terms and conditions of an offer.

acceptance, final (partial) The formal action by the owner accepting the work (or a specified part thereof), following written notice from the engineer that the work (or specified part thereof) has been completed and is acceptable subject to the provisions of the contract regarding acceptance.*

acceptance certificate A dated and signed document issued to a contractor by an owner certifying that all the work of a construction project is complete and in accordance with all provisions of the contract.*

accepted bid The proposal or bid a contractor and an owner or owner's representative use as the basis for entering into a construction contract.

access **1.** The means of entry into a building, area, or room. **2.** A port or opening through which equipment may be inspected or repaired.

access connection A ramp or roadway for entering or exiting an arterial highway.

access control system Computerized building security equipment, such as badge readers, designed to protect against unauthorized entry into buildings or building zones.

access door or panel A means of access for the inspection, repair, or service of concealed systems, such as air-conditioning equipment.

access flooring A raised flooring system with removable panels to allow access to the area below. This type of flooring is frequently used in computer rooms because it provides easy access to cables.



access door or panel

accessible That which is easily removed, repaired, or serviced without damaging the finish of a building.

accessible route A continuously unobstructed path connecting all accessible elements and spaces of a building or facility.



accessible route

accessories In the placing of concrete, the items used to assemble scaffolding, shoring, and forms, other than the wales, frames, and the forms themselves.

accessory building A secondary building on the same lot adjacent to the main building.

access to the work The right of the contractor to ingress and egress, and to occupy the work site as required to reasonably perform the work described in the contract documents. An example of denial of access to the work would be on the segment of a sewer installation project where no easements or work limits are indicated, but the contractor is ordered, after contract award, to conduct operations within a narrow work corridor necessitating different or unanticipated construction methods (e.g., use of sheeting).*

accolade Ornamental treatment over an arch, doorway, or window formed by two ogee curves meeting in the middle.

accordion door A retractable door, usually fabric-faced, hung from an overhead track and folding like the bellows of an accordion.

accordion partition A retractable partition having the same features as an accordion door.



accordion partition

accouplement **1.** In architecture, the pairing of pilasters or columns, as in a colonnade or buttress. **2.** In carpentry, a tie or brace between timbers.

accumulator (surge drum, surge header) **1.** A pressure vessel whose volume is used to maintain a constant pressure. **2.** In refrigeration, a storage chamber for low-side refrigerant.

acetone A highly flammable organic solvent used with lacquers, paint thinners, paint removers, and resins.

acetylene A carbon gas which, when combined with pure oxygen and ignited, produces an extremely hot flame used in gas welding and metal cutting.

acetylene torch The torch used for welding and cutting. Contains compressed acetylene and oxygen.



acetylene torch

AC generator A generator that produces alternating current.



AC generator

achromatic color White, colorless light.

acid- and alkali-resistant grout or mortar A grout or mortar that is highly resistant to prolonged exposure to alkaline compounds, acid liquids, or gases.

acid etch (aciding) A method of cleaning the latence from concrete by washing it with an acid solution and rinsing with water.

acid-proof floor A floor that resists deterioration when exposed to acid.

acid resistance A measurement of a surface's ability to resist the corrosive effect of acids.

acid-resistant brick Brick that resists deterioration caused by exposure to acid. This type of brick should be laid with acid-resistant mortar.

acid soil Soil with a pH value of less than 6.6.

acid steel Steel made with a silica flux or in a silica-lined furnace.

acorn nut Nut with hexagonal base and rounded top that encases the end of the screw.

acoustical A term used to define systems incorporating sound control.

acoustical barrier A building system that restricts sound transmission.

acoustical block (acoustic block) A masonry block with sound-absorbing qualities, usually defined in terms of its NRC (noise reduction coefficient) rating.

acoustical board A construction material in board form that restricts or controls the transmission of sound.

acoustical ceiling A ceiling system constructed of sound-control materials. The system may include lighting fixtures and air diffusers.

acoustical door A door constructed of sound-absorbing materials and installed with gaskets around the edges.

acoustical enclosure (acoustical booth, acoustical room) An enclosure constructed of acoustical materials for privacy in speaking, listening, and recording, as in a recording studio or a telephone booth.

acoustical lining Insulating material secured to the inside of ducts to limit sound and provide thermal insulation.

acoustical materials Materials that absorb and isolate sound and reduce reverberation, including felts, tiles, boards, and plasters.

acoustical metal deck A metal decking that includes a sound-absorbing material installed at a small additional cost per square foot.



acoustical metal deck

acoustical panel Modular units composed of a variety of sound-absorbing materials for ceiling or wall mounting.

acoustical reduction factor A value, expressed in decibels, that defines the reduction in sound intensity that occurs when sound passes through a material.

acoustical sprayed-on material A fibrous material with acoustical properties applied to a surface by spraying through a nozzle.



acoustical tile

acoustical tile A term applied to modular ceiling panels in board form with sound-absorbing properties. This type of tile is sometimes adapted for use on walls.

acoustical transmission factor The reciprocal of the sound reduction factor. A measure of sound intensity as it passes through a material, expressed in decibels.



acoustical wallboard

acoustical wallboard Wallboard with sound-absorbing properties.

acoustical window wall Double-glazed window walls with acoustical framing. This type of wall system is used particularly at airports.

acoustic lining Insulating material secured to the inside of ducts to attenuate sound and provide thermal insulation.

acoustics **1.** The science of sound transmission, absorption, generation, and reflection. **2.** In construction, the effects of these properties on the acoustical characteristics of an enclosure.

acquiescence A term frequently used when owners of adjacent properties agree on a boundary between their properties, if the original boundary is difficult or impossible to establish.

acre A common unit of land-area measurement equal to 160 square rods, or 43,560 square feet.

acre foot A unit of volume measurement equal to one acre times one foot thick. The acre foot is used to measure the volume of water or ore deposits.

acrylic *See* **acrylic resin.**

acrylic fiber Fiber produced from polymerized acrylonitrile, a liquid derivative of natural gas. A tough economical fiber commonly used in commercial and residential carpets and draperies.

acrylic plastic glaze A clear plastic sheet that is bonded to glass and that increases the ability of the glass to resist breaking and shattering.

acrylic resin (acrylate resin) In construction, clear, tough, thermoplastic resin manufactured in sheet and corrugated form, used as an adhesive, and as the main ingredient in some caulking and sealing compounds.

action item An element of work, design, research, or other task to be competed before a specific date or time, such as the before a subsequent meeting of involved parties.

action level The point when a concentration of hazardous materials reaches a level where OSHA regulations dictate protective steps be taken.

activated sludge Sludge that has settled out of oxygenated sewage.

active earth pressure The horizontal component of pressure exerted on a wall by earth.

active leaf In a double-leaf door, the leaf to which the latching or locking mechanism is attached.

active solar energy system A system that primarily collects and transfers solar energy using mechanical means that are not powered by solar energy.

active walls Building walls that act as a generator or collector of energy. An example is a double glass wall that collects solar energy and reflects excess heat when the desired interior envelope temperature has been reached. This combination reduces a facility's net heating and cooling load.

activity In critical path method (CPM) scheduling, a task or item of work required to complete a project. Also called *task*.



activity

activity arrow In arrow diagrams in critical path method scheduling, a graphic representation of an activity.



activity arrow

activity duration In critical path method scheduling, the estimated time required to complete an activity in time units (weeks, days, hours, etc.). There are three types of duration: original (or planned) duration, actual duration, and remaining duration. For in-progress activities, the completion duration is calculated by combining actual duration (so far) and remaining duration.

act of God An unforeseeable, inevitable event caused by natural forces over which an insurance policyholder has little or no control.

actual costs The actual expenditures incurred by a program or project.*

actual cost records Contemporaneous construction and accounting records detailing actual costs from a constructed project, including invoices, contracts, subcontracts, change orders, and applications for payment.*

actual damages Damages that can be assessed against an owner or contractor if either or both fail to perform their respective responsibilities and obligations as contained in the construction contract. Actual damages are considered economic (monetary) damages that can be clearly determined and proven, typically awarded by a court as the result of a lawsuit brought by one of the parties to the construction contract.*

actual dimension The real dimensional measurement of a piece of lumber, masonry unit, or other construction material.

actual finish date Date when work on an activity is substantially complete. Activity substantial completion is when only minor or remedial work remains and successor activities may proceed without hindrance from the predecessor's remaining work. It is not necessarily the last day work will be performed on that activity. The remaining duration of this activity is zero.*

actual start date Date when work on an activity actually started with intention of completing activity within the planned duration. The actual start date is not necessarily the first date work was performed on that activity. Interim starts and stops for an activity may show the need for splitting the activity into component parts.*

actuator In hydraulics, a motor or cylinder designed to convert hydraulic energy into mechanical energy.

acute angle An angle less than 90°.

adapt To modify a building or space to make it suitable for new requirements or purposes.

adaptable building A building that can be easily updated or modified to meet changing needs or requirements.



acute angle

adapter Any device designed to match the size or characteristics of one item to those of another, particularly in the plumbing, air-conditioning, and electrical trades.



adapter

ADA Standards for Accessible Design As an adjunct to the Americans with Disabilities Act, a set of standards that establish minimum technical requirements for the design and construction of buildings and facilities. Their intent is to increase the level of accessibility in the built environment, in existing facilities as well as new construction and alterations.



ADA Standards for Accessible Design

addendum A document describing an addition, change, correction, or modification to contract documents. An addendum is issued by the design professional during the bidding period or prior to the award of contract, and is the primary method of informing bidders of modifications to the work during the bidding process. Addenda become part of the contract documents.

addition **1.** An expansion to an existing structure, generally in the form of a room, floor, or wing. An increase in the floor area or volume of a structure. **2.** A chemical added to cement at the time of its manufacture to help the process or to alter the cement's characteristics.



addition

additive A substance that is added to a material to enhance or modify its characteristics, such as curing time, plasticity, color, or volatility.

additive alternate A specific alternate option for construction specifications or plans that results in a net increase in the base bid.

address system An electronic audio system with a microphone and speakers installed for either fixed (permanent) or mobile use. Wiring for a permanent system should be done prior to any finish work.

addressable system An advanced fire alarm or security system that provides for easy monitoring, remote testing, and quick location of an alarm condition.

adhesion The binding together of two surfaces by an adhesive.

adhesion-type ceramic veneer Ceramic tile or veneer attached to a backing by mortar, grout, or adhesive only. No anchors are used.

adhesive Generally, any substance that binds two surfaces together. In construction, the term is used principally in the wallboard and roofing trades.

adiabatic process A thermodynamic process occurring in the absence of heat gain or heat loss.

adit **1.** The entrance or approach to a building. **2.** The entrance to a mine.

adjustable base anchor An attachment to the base of a door frame above a finished floor.

adjustable clamp A temporary clamping device that can be adjusted for position or size.

adjustable square (double square) A carpenter's tool used for marking and scribing lumber. An adjustable square usually incorporates a level bubble.



adjustable square (double square)

adjustable wrench A wrench with a jaw that can be adjusted to fit different size nuts or bolt heads.



adjustable wrench

adjusted base cost The total estimated cost of a project after adding or deducting addenda or alternatives.

adjuster A representative of the insurance company who negotiates with all parties involved in a loss in order to settle the claim equitably. An adjuster deals with the policyholder, repair contractor(s), witnesses, and police (if necessary), and acts as a middleman between these parties and the insurance company.

adjusting nut A threaded nut used for alignment of an object. Often coupled with a locking nut to secure it in position.



adjusting nut

adjusting screw A screw used for alignment of an object. Often coupled with a locking nut to secure it in position.

adjustment The determination of: (a) the cause of a loss, (b) whether it is covered by the policy, (c) the dollar value of the loss, and (d) the amount of money to which the claimant is entitled after all allowances and deductions have been made.

admixture An ingredient other than cement, aggregate, or water that is added to a concrete or mortar mix to affect the physical or chemical characteristics of the concrete or mortar. The most common admixtures affect plasticity, air entrainment, and curing time.

adobe Earthen, sun-cured brick. A relatively labor-intensive, but low-embodied energy material, adobe absorbs excess heat during hot days and releases it during cool nights, thereby moderating a building's internal temperature.

adobe brick A large, roughly formed, unfired brick made from adobe and straw.

adsorbed water Water that is held on the surface of materials by electrochemical forces. This water, such as that on the surfaces of aggregate in a concrete mix, has a higher density and thus different physical properties from those of the free water in the mix.

adsorbent A material that has the ability to extract certain substances from gases, liquids, or solids by causing them to adhere to its surface without changing the physical properties of the adsorbent. Activated carbon, silica gel, and activated alumina are materials frequently used for this application.

adsorption The process of extracting specific substances from the atmosphere or from gases, liquids, or solids by causing them to adhere to the surface of an adsorbent without changing the physical properties of the adsorbent.

ad valorem Latin for based on value. Real property taxes, as they are based on the value of real property, are an ad valorem tax. An ad valorem tax is levied in proportion to value.

advance payment A partial payment to a contractor made shortly after the contract is signed. Similar to a down payment.

advance payment bond The generic term for the assurance of performance provided by a contractor to an owner that any money advanced to the contractor will be properly used to pay for project costs.

advance slope method A method of placing concrete in which the sloped face of the fresh concrete moves forward as the concrete is placed.

advance waiver of liens A waiver of all the contractor's rights to file mechanic's or materialmen's liens against the owner for nonpayment for work performed. Such advance waiver may be a condition of the owner's contract.

advertisement for bids Published notice of an owner's intention to award a contract for construction to a constructor who submits a proposal according to instructions to bidders.

adz A long-handled tool with a curved blade set perpendicular to the handle. Used for dressing lumber.



adz

adz-eye hammer A claw hammer with a long eye for receiving the handle.

aerate To introduce air into soil or water, for example, by natural or mechanical means.

aeration The process of introducing air into a substance or area by natural or mechanical means.

aeration plant A sewage treatment plant in which air is introduced into the sewage to accelerate the decomposition process.

aerator A mechanical device that introduces air into a material such as soil, water, or sewage.

aerator fitting A pipe fitting used to introduce air into a flow of water.

aerial Pertaining to, caused by, or present in the air.

aerial ladder An extension ladder capable of reaching high places and often mounted on a vehicle such as a fire truck.

aerial lift A term commonly applied to mobile working platforms that are elevated hydraulically or mechanically.



aerial lift

aerial survey A survey of the earth's surface based on aerial photographs and ground control points.

aerodynamic instability A harmonic motion occurring in a structure during high winds and endangering structural integrity. The term was used to define the failure of the Tacoma Narrows Bridge.



aerofilter

aerofilter A bed of coarse aggregate used for filtering sewage.

affidavit of noncollusion A sworn statement by the bidders on a project that the prices on their proposals were arrived at independently without consultation between or among them.

affinity A tendency for two substances to unite chemically or physically.



A-frame

A-frame **1.** A structural system or hoisting system with three members erected in the shape of an upright capital letter "A." **2.** A building with a steep gable roof that extends to the ground.

afterfilter (final filter) In air conditioning, a filter located at the outlet end of the system.

age hardening A term used to describe a hardening process of metals at room temperature.

agent Under agency law, an agent is authorized by the principal to act on the principal's behalf. Generally, an agent's acts bind the principal as though the principal had acted directly.



aggregate

aggregate Granular material such as sand, gravel, crushed gravel, crushed stone, slag, and cinders. Aggregate is used in construction for the manufacturing of concrete, mortar, grout, asphaltic concrete, and roofing shingles. It is also used in leaching fields, drainage systems, roof ballast, landscaping, and as a base course for pavement and grade slabs. Aggregate is classified by size and gradation.

aggregate, abrasive An antiskid aggregate worked into the surface of a concrete floor.

aggregate bonding capacity The maximum total contract value that a bonding company will cover (in performance bonds) for all of a construction company's current contracts.

aggregate, coarse Aggregate that is larger than ⅛″ and is retained on the No. 8 sieve.

aggregate, coarse-graded Aggregate with a continuous grading from coarse to fine, with a predominance of coarse particles.

aggregrate, concrete The fine and course aggregate used in manufacturing concrete. Both are usually washed and graded.

aggregrate, exposed A concrete surface with the aggregate exposed, formed by applying a retarder to the surface before the concrete has set, and subsequently removing the cement paste to the desired depth.

aggregrate, fine Aggregate smaller than ⅛″. Fine aggregate passes through the No. 8 sieve.

aggregrate, heavyweight The aggregate produced from materials with high specific gravity, such as limonite, iron ore tailings, and magnetite.

aggregate interlock The term applied to a situation in which the aggregate from one side of a concrete joint projects between the aggregate of the other side of the joint, thus resisting shear.

aggregate, lightweight One of several materials used to decrease the unit weight of concrete, thereby reducing the structural load and the cost of the building. The materials most commonly used are perlite and vermiculite. The use of lightweight aggregate is costly, but sometimes necessary in construction.

aggregate limit The maximum amount an insurance policy will pay for the sum of all personal injury and property damage claims that may arise during the term of the policy as the result of multiple occurrences. Legal defense costs may be excluded from this limit.

aggregate, masonry Washed sand used in a mortar mix.



aggregate panel

aggregate, open-graded An aggregate in which a skip between the sieve gradations has been deliberately achieved so that the voids are not filled with intermediate-size particles.

aggregate panel A precast concrete panel with exposed aggregate.

aggregate, plaster Natural or manufactured washed sand used in a plaster mixture.

aggregate, roof **1.** The aggregate used for a tar-and-gravel application. **2.** The ballast used for membrane-type roofing.

aggregate spreader A piece of equipment used for placing aggregate to a desired depth on a roadway or parking lot.

aggregate testing Any of a number of tests performed to determine the physical and chemical characteristics of an aggregate. Common tests are for abrasion, absorption, specific gravity, and soundness.


aggregate, roof

aggregate, well-graded An aggregate that incorporates sizes from the maximum to the minimum specified so as to fill most of the voids. This type of aggregate is used for asphaltic concrete mixes and for base courses.

aggressive sampling During removal of hazardous materials, the agitation of air to test success of remediation effort.

aging **1.** A method of classifying individual receivables by age groups, according to the time elapsed from the date due. **2.** A process used to make building materials appear old or ancient. **3.** The chemical and physical changes in a material incurred by the passage of time.

agitation The rotation of, or moving of blades through, a drum containing concrete or mortar to prevent segregation or setting of mixture.

agitator A mechanical device used to maintain plasticity and to prevent segregation, particularly in concrete and mortar.


agitator

A-grade wood **1.** A plywood surface that is smooth and paintable, and considered the best standard veneer. May be composed of more than one piece well jointed together. **2.** Plywood designation A-face, best veneer grade.

agreement **1.** A promise to perform, made between signatories to a document. **2.** In construction, the specific documents setting forth the terms of the contracts among architect, owner, engineer, construction manager, contractor, and others.

agreement form A standard printed form used by the signatories to an agreement, with blank spaces to fill in information pertinent to a particular contract.

agricultural lime A granular hydrated lime used for soil conditioning.

air admittance valve A one-way valve that allows air to enter into a plumbing drainage system if negative pressure in the piping occurs.

air balancing The process of adjusting a heating or air-conditioning duct system to provide equal distribution to all areas.

air barrier A component of the building envelope system that prohibits air leakage into a building and reduces the risk of condensation buildup. House wrap and fluid-applied air barriers are examples.

airborne transmission A term that refers to sound traveling through air in a structure.

air break A piping arrangement in which a drain from a fixture appliance or device discharges through an open connection into a receptacle or interceptor. Used to prevent backflow or back siphonage.

airbrush A device with a nozzle for applying paint with compressed air.


airbrush

air chamber In water piping, a vertical pipe containing entrapped air to absorb the pressure shock when a valve is closed suddenly.

air change The volume of air in an enclosure that is being replaced by new air. The number of air changes per hour is a measure of ventilation.

air circuit breaker A breaker that discontinues current flow in air.

air cleaner A device, often hung from the ceiling, for removing impurities from the air. The device may have a mechanical or electrostatic filter.


air chamber

air compressor A machine that extracts air from the atmosphere and compresses it into a holding chamber. The most common use of compressed air is for the operation of pneumatic tools. Air compressors are classified by the number of CFM (cubic feet per minute) of compressed air they can produce.

air-conditioner A mechanism that controls temperature, humidity, and/or the cleanliness of air within an enclosure.


air compressor

air-conditioning system An air treatment system designed to control the temperature, humidity, and cleanliness of air and to provide for its distribution throughout the structure.

air content The volume of air present in a concrete or mortar mix, expressed as a percentage of the total volume. A controlled air content prevents concrete from cracking during the freeze/thaw cycle.

air curtain (air wall) A narrow stream of air directed across an opening to deter the transfer of hot or cold air, contaminants, and insects from one side to the other.

air density The weight per unit volume of air, expressed in pounds per cubic foot.

air diffuser An outlet in an air-supply duct for distributing and blending air in an enclosure. Usually, a round, square, or rectangular unit mounted in a suspended ceiling.


air diffuser

air-distributing ceiling A suspended ceiling system with small perforations in the tiles for controlled distribution of the air from a pressurized plenum above.

air door An invisible barrier of high-velocity air that separates different environments. Sometimes called *air walls*, air doors are typically used for garage-type or larger doors to reduce infiltration and ex-filtration.

air drain An empty space left between a foundation wall and a parallel wall to prevent the fill from lying directly against the foundation wall.

air-entraining agent An admixture for concrete or mortar mixes that causes minute air bubbles to form within the mix. Air entrainment is desirable for workability of the mix and prevention of cracking in the freeze/thaw cycle.

air-entraining hydraulic cement Hydraulic cement containing an air-entraining addition in such amount to cause the product to entrain air in mortar within specified limits.

air escape In plumbing, a valve for automatically discharging excess air from a water line.

air exchange rate Refers to the rate at which outside air replaces indoor air in a building, expressed in either air changes per hour (ACH) cubic feet per minute (CFM).

air gap In plumbing, the distance between the outlet of a faucet and the overflow level of the fixture.

air grating A fixed metal grating, particularly in masonry foundation walls, for ventilation.



air grating

air hammer A portable, pneumatic percussion tool used for breaking and hammering.

air-handling troffer A ceiling lighting unit that incorporates an air diffuser.

air-handling unit (AHU) The traditional method of heating, cooling, and ventilating a building by which single- or variable-speed fans push air over hot or cold coils, then through dampers and ducts and into one or more rooms.



air hammer


EXHAUST FAN
AUTOMATICALLY CONTROLLED DAMPER, TYP.
RETURN AIR
RETURN AIR FROM AIR-CONDITIONED SPACES
PREHEAT COIL
CHILLED WATER COIL
HUMIDIFIER
RETURN AIR DAMPER
FAN
FLEXIBLE CONNECTORS
AIR FILTER
PREHEAT COIL
BELT GUARD
MINIMUM OUTSIDE AIR
℄ OF FAN INLET
MOTOR
VARIABLE OUTSIDE AIR
SUPPLY AIR FAN
AIR-HANDLING UNIT CASING
TYPICAL 30" x 60" MIN. ACCESS DOOR
AIR DUCT TO AIR-CONDITIONED SPACES
HEATING SOURCE
4" HIGH HOUSEKEEPING PAD
COOLING SOURCE
VIBRATION ISOLATORS

air-handling unit (AHU)

air leakage The air that escapes from a system or enclosure through cracks, joints, and couplings.

air lift A device that uses compressed air to lift slurry or dry powder through piping.

airlock **1.** An airtight chamber such as that used in tunnel and caisson excavation. **2.** A system of double doorways permitting entry and exit while preventing airflow from one area to another, as from a contaminated area to an uncontaminated area. **3.** An entrance room between areas of different pressures, such as the entrance to an air-supported structure. **4.** In plumbing, air trapped in a system and preventing flow.

air makeup unit A system for introducing fresh, conditioned air into an enclosure from which air is being exhausted.

air-mixing plenum In an air-conditioning system, a chamber in which fresh air is mixed with recirculated air.

air monitoring In asbestos abatement, a procedure used to determine the fiber content in a volume of air over a measurable period of time.

air permeability test A procedure for determining the fineness of powdered material such as cement.

air pocket A void filled with air, such as in a water piping system or in a concrete form when placing concrete.

air purge valve A device for eliminating trapped air from a piping system.

air-purifying respirator A device that removes pollutants from a contaminated atmosphere as a person breathes.



air-purifying respirator

air receiver The air storage tank on a compressor.

air regulator An instrument for regulating the flow or pressure of air in a system.

air release valve A valve that releases air from a water pipe or fitting.

air rights The exclusive right of real property owners to possess the airspace above their land, as long as they comply with building and zoning laws.

air separator A pneumatic device that uses air to sort materials by size.

air shaft (air well) A roofless enclosed area within a building, admitting light and ventilation.

air splitter Device inside an air duct that divides a single air stream into several streams.

air-supported structure A nonrigid structure supported by atmospheric pressure that is slightly higher inside the tank than outside. The difference in pressure is created by fans.


FABRIC ENVELOPE
STRESS RELIEF
NONSTRESS RELIEF
HEAT-SEALED SEAM, TYP.
HEATER
INFLATION BLOWER
VEHICLE AIR LOCK DOOR
CONTINUOUS OR NONCONTINUOUS ANCHORAGE SYSTEM
STRESS RELIEF SYSTEM (ONE-WAY CATENARY CABLE OR WEBBING REINFORCEMENT)
EXIT OR REVOLVING DOOR
STANDBY GENERATOR FOR BACKUP POWER

air-supported structure

air terminal The top of a lightning protection system on a building.

air test A test for leaks in ductwork and in drainage and pipe systems where compressed air is forced into a sealed system and leaks are detected with a pressure gauge.

airtight Refers to the inability to permit air passage.

air tube system A tubular conveying system that uses air pressure to move capsules containing paperwork from one station to another.

air washer A water spraying mechanism for cleaning and humidifying air in a ventilation system.

airway The air space between the thermal insulation and sheathing on a roof.



airway

aisleway Any open passageway permitting access and traffic flow between sections within a building.

alarm system An installed electrical system devised to protect against unauthorized entry or fire by giving off an audible and/or visual signal.

alclad A product having an aluminum or aluminum alloy coating metallurgically bonded to the surface. The coating is anodic to the core, thus protecting it physically and electrolytically against corrosion.

alcove A recess or partly enclosed extension opening into a larger room.

algorithm A set of mathematical instructions, or a computer program, used to produce a control output.

alidade A sighting apparatus often used with a plane table for determining and plotting horizontal and/or vertical angles.

aligning punch A tool used for aligning holes in structural steel. Often referred to as a spud wrench.

alignment **1.** The adjustment of elements in a plane such as structural steel. **2.** The plane or horizontal orientation of a structure or roadway.

aliphatic resin glue Thermoplastic adhesive used to bond wood and other porous materials.

alite The primary constituent of Portland cement clinker. Alite is composed of tricalcium silicate and small amounts of magnesium oxide, aluminum oxide, ferric oxide, and other materials.

alkali **1.** A liquid that has a pH greater than 7.0. **2.** Water-soluble salts of alkali metals, such as sodium and potassium, which occur in concrete and mortar mixes. The presence of alkaline substances may cause expansion and subsequent cracking.

alkali resistance The ability, particularly of paint, to resist attack by alkaline materials.

alkali soil Soil that has a pH value of 8.5 or higher and is thus harmful to some plant life.

alkyd paint A paint, with an alkyd resin base, that produces a quick-drying, hard surface.

alkyd plastics Thermoset plastics with good heat and electrical insulation properties. Commonly used in paints, lacquers, and molded electrical parts where temperatures will not exceed 400°F.

alkyd resin A synthetic resin used as a binder in lacquers, adhesives, paints, and varnishes.

Allen wrench A section of hexagonal stock used to turn an Allen head screw or bolt.

alligatoring Rough cracking of a painted surface, often caused by applying another coat before the first is dry or by exposing a painted surface to extreme heat.



Allen wrench

alligator shears (lever shears) A shop tool used for shearing sheet metal.

allocable cost A cost that is assignable to a particular contract or other cost objective.

allocated cost The total cost of an asset's individual components, summarized, including incorrect costs, and classified into one of four categories.

allowable bearing value (allowable soil pressure) The bearing capacity of a soil, in pounds per square foot (psf), determined by its characteristics, such as shear, compressibility, water content, and cohesion. The higher the allowable bearing value of a soil, the smaller the footing required to support a structural member.

allowable cost Any reasonable cost that may be recovered under the contract to which it is allocable.

allowable load The ultimate load divided by a safety factor.

allowable pile-bearing load The allowable load used to design a pile cluster to support a structure.

allowable stress The maximum stress allowed by code for members of a structure, depending upon the material and the anticipated use of the structure.

allowance **1.** A stated requirement of the contract documents whereby a specified sum of money is incorporated, or allowed, into the contract sum in order to sustain the cost of a stipulated material, assembly, piece of equipment, or other part of a construction contract. This device is convenient in cases where the particular item cannot be fully described in the contract documents. **2.** In bidding, an amount budgeted for an item for which no exact dollar amount is available. **3.** A contingency for unforeseen costs. **4.** The classification of connected parts or members according to their tightness or looseness.

alloy A homogeneous mixture of two or more metals developed and used because of its lower cost and/or the certain desirable properties it exhibits.

alpha gypsum A specially processed calcined gypsum with an extremely high compressive strength.

ALTA survey Short for American Land Title Association, a land survey that identifies the title commitments of the parcel in addition to the normal as-built conditions.

alteration Construction within a structure or to its exterior closure that does not change the overall dimensions of the structure. Alteration includes remodeling and retrofitting.

alternate A specified item of construction that is set apart by a separate sum. An alternate may or may not be incorporated into the contract sum at the discretion and approval of the owner at the time of contract award.

alternate bid An amount stated in a bid that can be added or deducted by an owner if the defined changes are made to the plans or specifications of the base bid.

alternating current An electric current that reverses direction at regular intervals. In the United States, most current for domestic use reverses direction at 60 cycles per second.

alternative dispute resolution (ADR) A confidential method of settling a dispute without going to court, typically negotiation, mediation, or arbitration.

alternator A machine that develops alternating current by mechanical rotation of its rotor.

altitude In surveying or astronomy, the angular distance of a celestial body above the horizon.

alum A double sulfate added to plaster as a hardener and accelerator.

alumina Aluminum oxide found in the clay used to make brick and clay tile.

aluminum A silver-colored, nonmagnetic, lightweight metal used extensively in the construction industry. It is used in sheets, extrusions, foils, and castings. Sheets are often anodized for greater corrosion resistance and surface hardness. Because of its light weight and good electrical conductivity, aluminum is used extensively for electrical cables. Aluminum is usually used in alloy form for greater strength.

aluminum-clad window A factory-finished and sealed window whose wooden construction is enclosed with aluminum sheeting.

aluminum-coated steel Steel coated with aluminum to inhibit corrosion.

aluminum door A glazed door with aluminum stiles and rails.



aluminum door

aluminum foil A very thin aluminum sheet used extensively for thermal reflection and moisture protection.

aluminum nitrate fuel oil mix (ANFO) An inexpensive explosive used in blasting and mining operations.

aluminum paint A paint containing aluminum paste, which gives the paint good heat-, light-, and corrosion-resistant properties.

aluminum window A glazed window with an aluminum sash and muntins.



aluminum window

ambient lighting The general background lighting, whether natural or artificial, of an area.

ambient noise The total noise level from all sources in a given area, either within a building or in an outside environment.

ambient temperature The temperature of the environment surrounding an object.

amendment A modification of the contract by a subsequent agreement. This does not change the entire existing contract but does alter the terms of the affected provisions or requirements.*

American Arbitration Association (AAA) A private nonprofit organization that provides education, training, and administrative assistance to parties who use nonjudicial methods, such as alternative dispute resolution (ADR) for resolving disputes. The AAA is involved primarily with binding arbitration and mediation.

American basement (walk-out basement) The floor of a building partly above and partly below grade.

American Conference of Governmental Industrial Hygienists (ACGIH) An organization of professionals skilled in the science of industrial hygiene.

American Federation of Labor (AFL) A labor organization or union formed in the United States under the leadership of Samuel Gompers in 18 86. The American Federation of Labor provided an "umbrella" organization, the purpose of which was to represent to management the interests of workers in various trades, crafts, and other skilled disciplines related to manufacturing and construction.

American Federation of Labor and the Committee for Industrial Organizations (AFL-CIO) A major union formed by the merger of the two organizations listed above under the leadership of John L. Lewis in 1955. The AFL-CIO represents the interests of various types of member workers in industry and other endeavors (including construction) for the purpose of negotiating with management for acceptable wages, benefits, and other material interests of worker-employees.

American Lumber Standards Committee (ALSC) The committee that maintains standards for hardwood and softwood grading, including those for size and nomenclature. Rules for grading are established by the U.S. Department of Commerce and enforced by regional organizations.

American National Standards Institute (ANSI) Publisher of the American National Standards, a reference book outlining the approved standards and specifications for all facets of building construction.

American standard beam A hot-rolled steel I-beam designated by the prefix S before the size and weight.



American standard beam

American standard channel A hot-rolled steel channel designated by the prefix C before the size and weight.



American standard channel

American Standard Code for Information Interchange (ASCII) An accepted standard for computerized data transmission.

American standard pipe threads (Briggs standard) The thread size and pitch commonly used in the United States for connecting pipe and fittings.

American wire gauge (American standard wire gauge, Brown and Sharpe gauge) The standard in the United States for specifying and manufacturing wire and sheet metal sizes, particularly electrical wire and metal flashing.

Americans with Disabilities Act (ADA) A federal civil rights act prohibiting discrimination against people with disabilities. There are five sections that cover different aspects of discrimination: employment, state and local government, public accommodations and commercial facilities, telecommunications, and miscellaneous provisions.

Americans with Disabilities Act Accessibility Guidelines (ADAAG) The minimum guidelines that must be followed to meet ADA Standards for Accessible Design. *See also* **ADA Standards for Accessible Design**.

ammeter An instrument for measuring the rate of ampere flow through an electric circuit.

amorphous A type of rock that has no crystalline structure.

amortization The process of paying off stock, bonds, a mortgage, or other indebtedness through installments or by a sinking fund.

amount of mixing The mixing action employed to combine the ingredients of concrete or mortar, measured in time or number of revolutions.

ampacity A designation of the current-carrying capacity of an electrical wire, expressed in amperes.

ampere The electromotive force required to move one volt of electricity across one ohm of resistance. A measure of electrical current.

amplitude In sound or vibration, the maximum variation from the mean position.

analog point In Building Automation Systems, a sensor, such as a damper or temperature sensor, that has a continuous range of settings that can be monitored or controlled by the system.

analog signal A signal in the form of a fluctuating quantity (such as voltage or current strength) that reflects variations, such as loudness. It is not limited to discrete units.



anchor (anchorage)

anchor (anchorage) **1.** A device to prevent movement when in tension, such as a tie-back for sheet piling. **2.** In masonry composite wall construction, the tension connection between components. **3.** In prestressed or posttensioned concrete, the end connection for the tendons. **4.** A timber connector. **5.** The metal devices that secure metal door and window frames to masonry. **6.** In piping systems, a device that secures piping to a structure.

anchorage bond stress (development bond stress) The forces on a deformed reinforcing steel bar divided by the product of the perimeter times the embedded length.

anchorage deformation (anchorage loss, anchorage slip) In prestressing concrete members, the deformation of an anchor or slippage of tendons when the prestressing device is released.

anchorage zone **1.** In pretensioning, the area of the member in which the stresses in the tendon anchor are developed. **2.** In posttensioning, the area adjacent to the anchorage that develops secondary stresses.

anchor block A block of wood in a masonry wall that provides a means of attaching other wood members.

anchor bolt (foundation bolt, hold-down bolt) A threaded bolt, usually embedded in a foundation, for securing a sill, framework, or machinery.



anchor bolt (foundation bolt, hold-down bolt)

anchor bolt plan A plan view showing size and location of all anchor bolts for a building's systems components. May be included in structural steel and shop drawings.

anchor plate A plate attached to an object to which accessories or structural members may be attached by welding, screwing, nailing, or bolting.

anchor rod A threaded metal rod attached to hangers and used to support pipe and ductwork.

anchor strip A wooden, plastic, or metal board surrounding a window and nailed to the building's framing to serve as a windbreak.

anemometer An instrument that measures the velocity of airflow.



anemometer

angle **1.** The figure or measurement of a figure formed when two planes diverge from a common line. **2.** In construction, a common name for an L-shaped metal member.

angle bead (angle staff, staff angle) A metal or wood strip set at the corner of a wallboard or plaster wall to serve as a guide and to provide protection. Angle beads are most commonly made of nonferrous or galvanized perforated sheet metal.

angle block (glue block) A small block of wood used to fasten or stiffen the joint of two adjacent wood members, usually at right angles.

angle bond A metal tie that projects into each wall at a corner and is used to bond masonry.

angle brace (angle tie) A piece of material temporarily or permanently secured across an angle to make it rigid, such as a strip of wood nailed across the corners of a window frame to keep it square during installation.

angle brick A brick cast with an oblique angle on one of its corners.

angle cleat (angle clip) A short section of angle iron used to attach structural members, such as precast panels, to structural steel.


angle cleat (angle clip)

angle closer A special brick or a portion of a brick used to close the bond on the outside corner of a brick wall.

angle collar (bevel collar) A cast-iron pipe angle fitting with a bell-type connection at each end.

angle float (angle trowel) A trowel with two surfaces meeting at right angles. An angle float is used for finishing plaster or concrete in an inside corner.


angle float (angle trowel)

angle framing Light-gauge framing with an angle iron.


angle framing

angle gauge A template used to set or maintain an angle during construction.

angle iron (angle bar, angle section) An L-shaped steel structural member classified by the thickness of the stock and the length of the legs.


angle iron (angle bar, angle section)

angle lacing A system of connecting two structural components with angle irons.

angle plane A hand tool used to remove projections and smooth inside corners on a plaster brown coat covering once it has set.

angle strut An angle iron erected to carry a compression load.

anglet A groove in a material or structure, most often containing a right angle.

angle valve A valve with the inlet at right angles to the outlet for controlling flow in a pipe.


angle valve

angular aggregate An aggregate made of crushed material with sharp edges, as opposed to screened gravel with rounded edges.

angular measure The deviation between two lines that meet at a point, measured in degrees, minutes, and seconds.

anhydrite An additive used in the manufacture of Portland cement to control the set.

anhydrous calcium sulfate (dead-burnt gypsum) Gypsum from which all the water of crystallization has been removed.

anhydrous gypsum plaster A high-grade finish plaster with most of the water of crystallization removed.

animal glue A strong adhesive with poor water resistance made from bones and hides of animals. Often used in furniture manufacture.

anionic surfactant A negatively charged adjuvant with limited compatibility used in asbestos abatement.

annealed wire A pliable wire used in construction primarily for reinforcing steel tie wires.

annealing The process of subjecting a material, particularly glass or metal, to heat and then slow cooling to relieve internal stress. This process reduces brittleness and increases toughness.

annex A secondary structure either near or adjoining a primary structure.

annual fuel utilization efficiency (AFUE) A seasonal efficiency rating that is an accurate estimation of fuel used for furnaces and direct-fired forced hot air systems. It measures the system efficiency and accounts for start-up, cool-down, and other operating losses.

annular ring nail A nail with a series of threadlike rings on its shank to give it good holding power. This type of nail is used for attaching gypsum board to wood studs.


annular ring nail

annunciator An electrical signaling device that identifies when a circuit is engaged.

anode The conductor rod used in an electrical system to protect underground tanks and pipes from electrochemical action.

anodize The process of creating electrolytically a hard, noncorrosive film of aluminum oxide on the surface of a metal. This film can be either clear or colored.

antechamber An entrance, vestibule, or foyer.

anticorrosive paint A paint containing corrosive-resistant pigments such as zinc chromate, lead chromate, or red lead. This type of paint is used as a primer on iron and steel products.

antiflotation pads Concrete pads secured to underground tanks to add sufficient weight to the tank to overcome buoyancy when empty.

antimicrobial A compound commonly added to other products to prevent bacterial growth on the surface of a finished product.

antioxidant Any substance that inhibits oxidation, which deteriorates plastics and other materials.

antisiphon trap (deep-seal trap) In a drainage system, a plumbing trap that provides a water seat to prevent siphonage.

antislip paint A paint with coarse particles mixed in to roughen the surface to which it is applied. This type of paint is used on steps, ramps, walkways, and porches.

antistatic agent An additive that reduces the development of static electricity on the surface of plastics or on carpeting.

anvil The part of a pile hammer that transmits the driving force to a pile.

aperture In construction, any opening left in a wall for a door, window, or for ventilation.

apex The peak, or highest point, of any structure.

apex stone (keystone, saddle stone) The highest stone or block in an arch, gable, dome, or vault. Apex stones are often decorative.



apex stone (keystone, saddle stone)

apparent density The mass per unit volume (or the weight per unit volume) of a material, taking into consideration any voids.

appliance An electric or gas device used to provide occupant comfort or convenience such as by producing light, heat, air conditioning, refrigeration, and so forth.

appliance panel An electrical service panel with circuit breakers or fuses specifically designed for service to appliances.

application bond The measurement of the strength of adhesion between two adhered surfaces.

application butyl An adhesive with a butyl base used in caulking and sealants.

application cement A common term for mastics used in flooring and roofing applications.

application failure The separation by chemical or physical means of two adhered surfaces.

application for payment A formal written request for payment by a contractor for work completed on a contract and, if allowed for in the contract, materials stored on the job site or in a warehouse.

application mortar A mixture with an adhesive additive used for affixing ceramic wall or ceiling tile.

application neoprene A liquid neoprene compound applied to concrete foundation walls for waterproofing.

application spreader A trowel with notched edges used for applying adhesive.

applied trim Strips or moldings applied to, as opposed to manufactured with, door and window frames and wood paneling.



applied trim

appraisal A dollar estimate of the value of a certain item of property, or the assessment of the value of a loss. The estimate is developed from market value, replacement cost, income produced, or a combination of these factors. Appraisals are usually made by qualified professional appraisers.

apprentice A person who works with a skilled craftsman for a number of years in order to learn the trade. An apprentice is generally rated by the number of years served.

approach ramp **1.** An access for vehicles to a highway. **2.** A sloped access for the handicapped to a building, in lieu of stairs.

approved In construction, materials, equipment, and workmanship in a system, or a measurable portion thereof, which have been accepted by an authority having jurisdiction. Usually, the term refers to approval for payment, approval for continuation of work, or approval for occupancy.

approved equal Material, equipment, or method of construction that has been approved by the owner or the owner's representative as an acceptable alternative to that specified in the contract documents.

appurtenance **1.** Something added on to a main structure or system. **2.** A condition added to a property deed, such as a right-of-way.

apron **1.** A piece of finished trim placed under a window stool. **2.** A slab of concrete extending beyond the entrance to a building, particularly at an entrance for vehicular traffic. **3.** The piece of flat wood under the base of a cabinet. **4.** Weather protection paneling on the exterior of a building. **5.** A splashboard at the back of a sink. **6.** Bowl-front closing device for a scraper bowl. **7.** At an airport, the pavement adjacent to hangars and appurtenant buildings.



apron

apron flashing **1.** The flashing that diverts water from a vertical surface on a building to a sloped roof, such as that around a chimney. **2.** Flashing that leads water from a roof into a gutter.



apron flashing

apron molding The piece of flat wood under the base of a cabinet.

apron piece (pitching piece) A piece of lumber protruding from a wall to support the rough stringers at the top or at a landing of a wooden staircase.

apron wall A distinct exterior wall panel extending from a windowsill to the window below.

aquastat An electrical control activated by changes in water temperature.

arbitration The process by which parties agree to submit their disputes to the determination of a third, impartial party (referred to as the arbitrator), rather than pursuing their claims before a judge and jury in a court of law.

arbor **1.** An enclosure of closely planted trees, vines, or shrubs that are either self-supporting or supported on a framework. **2.** The rotating shaft of a circular saw or shaper.

arc **1.** The electrical discharge between two electrodes. When the electrodes are surrounded by gas in a lamp, they become a bright, economical light source. **2.** Any portion of a circle or the angle that it makes.

arcade A covered passageway between buildings, often with shops and offices on one or both sides.

arc cutting A method of cutting metal with an electric welding machine. The metal melts from the heat produced by the arc between the electrode and the metal.

arch A curved or flat structure spanning an opening. The shape and size of arches are limited by the materials used and the support provided.

archaic materials Historical components and assemblies that are essential to the integrity of a historic structure, but that are not in common use for new construction. Examples include traditional solid masonry construction, historic reinforced concrete assemblies, terra cotta masonry, lead-coated copper sheet metal assemblies, and hollow clay tile interior partition walls.


arch

arch brick (compass brick, feather edge brick, radial brick, radiating brick, radius brick, voussoir brick) **1.** One of a number of types of brick manufactured to construct curved surfaces such as arches and round manholes. **2.** Extremely hard-burned brick from an arch of a scove kiln.

arching The bridging of shear stresses in a soil mass across an area of low shear strength to adjacent areas of higher shear strength.

architect A professionally qualified and licensed person who prepares plans and specifications for a building or structure. Architectural services include such duties as project analysis, development of the project design, and the preparation of construction documents (including drawings, specifications, bidding requirements, and general administration of the construction contract).

architect-engineer A person or company providing services as both architect and engineer.

architect's approval Permission granted by the architect, acting as the owner's representative, for actions and decisions involving materials, equipment, installation, change orders, substitution of materials, or payment for completed work.

architect's scale A draftsman's tool with proportionate, graduated spaces. May be flat, like a ruler, or three sided. The three-sided scale has 10 separate scales: 1⁄8″ and 1⁄4″, 1″ and 1⁄2″, and 3⁄8″. 3⁄16″, and 3⁄32″, and 1½″ and 3″.

architectural Pertaining to a class of construction, particularly in home building, of higher-than-average quality. The term often pertains to the ornamental features of a structure.

architectural area of buildings The total of all stories of a building, after adjustments, computed according to AIA standards, measured from the exterior faces of exterior walls and from the center line of walls between buildings.

architectural barrier An architectural feature that is not compliant with accessibility for disabled users or prohibits usage or access to a building.

architectural concrete Structural or nonstructural concrete that will be permanently exposed to view and therefore requires special attention to uniformity of materials, forming, placing, and finishing. This type of concrete is frequently cast in a mold and has a pattern on the surface.


architectural concrete

architectural door A grade classification of door that designates higher-than-standard specifications for material and appearance.

architectural drawings Also called core drawings, these show the layout of the building and its use of space. Architectural drawings convey the structure's aesthetic value and show the dimensions and placement of all key features.

architectural fee The cost of architectural services to an owner. The fee varies according to the services provided and the complexity of the project.

architectural glass Glass with a configurated surface to obscure vision or diffuse light.

architectural floor plan The most common plan view that shows doors, windows, walls, and partitions.

architectural millwork (custom millwork) Millwork manufactured to meet the specifications of a particular job, as distinguished from stock millwork.


architectural millwork (custom millwork)

architectural precast concrete Precast concrete that, through application, finish, shape, color, or texture, contributes to a building's architectural form and finished effect.

architectural programming A process that identifies a structure's proposed use, code, agency review, and approval requirements and identifies the necessary rehabilitation and restoration of existing components, and any other needed improvements.

architecture The art and science of designing and building structures.

architrave In classical architecture, **1.** the bottom-most beam that spans from column to column resting directly upon the capitals; **2.** ornamental moldings around door or window openings.

arch stone The wedge-shaped masonry units used in building an arch.

arch truss A roof truss having a curved upper chord and a straight lower chord.



arch truss

arc voltage The reaction of a circuit's inductance to the rate of current change in the circuit.

arc welding The joining of metal parts by fusion. Heat is produced by the electricity passing between an electrode and the metal, and is usually accompanied by a filler metal and/or pressure.

area **1.** A measurement of a given planar region or of the surface of a solid. **2.** A particular part of a building that has been set aside for a specific purpose.

area drain A catch basin or other device designed to collect surface water.

area light A light source used to illuminate a significant area, either indoors or outdoors.

area method A construction cost estimating system employing unit square foot costs multiplied by the adjusted gross floor area of a building.

area wall A masonry wall surrounding or partly surrounding an open area, particularly one below grade, such as an areaway at the entrance to a basement.

areaway An open area located below grade and adjacent to a building to provide light, air, or access to a basement or crawl space.



areaway

areaway grating A steel or cast-iron grating placed over an areaway, usually at grade level.

armature The rotating part of a motor or generator consisting of copper wire wound around an iron core.



armature

arm conveyor A belt with protruding arms or angles to carry materials into a building.

armor coat Durable pavement comprised of two or more thin layers of aggregate and asphalt.

armored cable (metal-clad cable) An electrical conduit of flexible steel cable wrapped around insulated wires.



armored cable (metal-clad cable)

armored concrete Concrete with a surface treatment containing steel or iron and used in areas with heavy, steel-wheeled traffic.

armored faceplate A metal faceplate mortised into the edge of a door to protect the lock mechanism.

armored front A tamperproof metal plate that covers the set screws of a mortise lock.



armored faceplate

armored plywood Plywood that is faced on one or both sides with metal cladding.

armor plate (kick plate) A metal plate that is installed on the lower part of a door to protect it from kicks and scratches.

arrester **1.** A wire screen at the top of a chimney or incinerator to prevent burning material from flying out. **2.** In electrical equipment, a protective device that limits surge voltages by diverting current.

arrow diagram A CPM (critical path method) diagram in which arrows represent activities in a project.

articles Also referred to as *clauses*, these separate and numbered paragraphs within a construction contract state the rights, duties, responsibilities, and obligations of the parties (e.g., the owner and the contractor) to the contract.

artificial intelligence Computer systems that solve problems symbolically rather than algorithmically. Similar to the warning, decision-making, and problem-solving process in the human brain.

artificial stone A material containing stone chips and cement, mortar, or plaster that is seasoned for several months, then polished for a finish that simulates stone.

artificial turf A synthetic material designed to simulate a natural surface, and used to form playing surfaces for indoor or outdoor sports arenas, such as football fields.

asbestos (asbestos fiber) A flexible, noncombustible, inorganic fiber used primarily in construction as a fireproofing and insulating material.

asbestos encapsulation An airtight enclosure of asbestos fibers with sealant or film that prevent fibers from becoming airborne and creating a potential health hazard.

asbestos removal A special trade that has developed since the health hazards of airborne asbestos have been revealed. Applies principally to ceiling tile, fireproofing, and pipe insulation.

asbestos work A classification system designed by OSHA that rates the level of training needed to perform asbestos-related tasks. Class I involves the removal or abatement of thermal insulation or surfacing asbestos-containing materials (ACM); Class II involves removing asbestos floor or ceiling tiles, siding, roofing, or piping; Class III involves repair and maintenance operations where employees may disturb ACM; and Class IV involves custodial activities during which employees contact ACM.

as-built drawings Record drawings made during construction. As-built drawings record the locations, sizes, and nature of concealed items such as structural elements, accessories, equipment, devices, plumbing lines, valves, mechanical equipment, and the like. These records (with dimensions) form a permanent record for future reference.

as-built schedule A time-scaled graphic depiction of the historical record of events, activities, and progress of a given project.

ash A sturdy, long-grained hardwood with excellent bending qualities. This wood is used in veneers, trim, and flooring.

ash dump An opening in the bottom of a firebox or fireplace into which ashes are swept, falling into an ashpit below.



ash dump

ashlar **1.** Any squared building stone. The term usually refers to thin stone used as facing. If the horizontal courses are level, it is called coursed ashlar, if they are broken, it is called random ashlar. **2.** Short vertical studs between the ceiling joists and the rafters.

ashlar brick (rock-faced brick) A brick with a broken face resembling stone.

ashlar line A horizontal line on the exterior face of a masonry wall.

ashlar masonry A stone masonry wall or veneer composed of rectangular units bonded with mortar.



ashlar masonry

ashlar veneer A nonstructural wall facing composed of ashlar masonry.

ashpit A cleanout under a fireplace, usually at the base of a chimney, where ashes are removed.

as-late-as-possible (ALAP) An activity for which the scheduling application sets the early dates as late as possible without delaying the early dates of any successor.*

aspect The orientation of a building with respect to the points of a compass.

aspect ratio **1.** In any configuration, the ratio of the long dimension to the short dimension. **2.** The ratio of the width of a duct to its height.

aspen A smooth-grained, white hardwood used for trim and veneer.

asphalt A dark brown to black bitumen pitch that melts readily. It appears in nature in asphalt beds and is also produced as a by-product of the petroleum industry.

asphalt, blown Asphalt that has had air blown through it at high temperatures to give it workability for roofing, pipe coating, foundation waterproofing, and other purposes.

asphalt base course A bottom paving course consisting of coarse aggregate and asphalt.



asphalt base course

asphalt block A manufactured paving block made from asphaltic concrete and aggregate. The block is typically manufactured in squares, rectangles, and hexagons, and comes in dark gray or black colors.

asphalt cement Asphalt that has been refined to meet the specifications for use in paving and other special uses.

asphalt coating (asphalt-lined pipe) The asphaltic coating of corrugated metal pipe. Coatings can be inside, outside, or just on the invert.

asphalt color coat An asphalt surface treatment that has been impregnated with aggregate of a specified color.

asphalt curb An extruded or hand-formed berm made from asphaltic concrete.



asphalt curb

asphalt cutback An asphalt that has been liquefied by an additive for a specific use.

asphalt cutter Any of a variety of machines designed to cut asphalt pavement.

asphalt dampproofing The application of asphalt to the surface of a concrete or masonry wall to prevent passage of absorption of water or moisture.

asphalt emulsion Liquid asphalt in which water has been suspended. When the water evaporates, the asphalt hardens.

asphalt expansion joint Premolded felt or fiberboard impregnated with asphalt and used extensively as an expansion joint for cast-in-place concrete.



asphalt expansion joint

asphalt felt Felt impregnated with asphalt and used in roofing and sheathing systems.

asphalt filler (asphalt joint filler) A liquid asphalt used for filling joints and cracks in pavement and floors.

asphalt flashing cement A semisolid asphaltic material used to apply flashing.

asphaltic A term used to describe materials containing asphalt. While sometimes used interchangeably with asphalt in the construction industry, it is usually more correct to use asphaltic.

asphaltic concrete (asphalt paving, bituminous concrete, blacktop) A mixture of liquid asphalt and graded aggregate used as a paving material for roadways and parking lots. It is usually spread and compacted in layers over a prepared base while still hot.

asphaltic macadam A term generally referring to a penetration method of paving whereby the aggregate is placed first, then liquid asphalt is sprayed into the voids, followed by the addition of a finer-graded aggregate. Penetration macadam usually needs a seal coat to prevent damage caused by water infiltration.

asphaltic mastic (mastic asphalt) A viscous asphaltic material used as an adhesive, a waterproofing material, and a joint sealant.

asphalt leveling course A course of asphaltic concrete pavement of varying thickness spread on an existing pavement to compensate for irregularities prior to placing the next course.

asphalt, liquid An asphaltic material having a fluid consistency at normal temperatures. The common types specified for pavements are cutback, rapid curing (RC), medium curing (MC), and slow curing (SC), which are blended with petroleum solvents and emulsion, which is blended with water.

asphalt overlay One or more courses of asphaltic concrete placed over existing pavement. The process of overlaying usually includes cleaning, and application of a tack coat, followed by a leveling course.

asphalt paint An economical, liquid-asphaltic product used principally for weatherproofing.

asphalt paper A paper that has been coated or saturated with asphalt for use as a moisture barrier.

asphalt pavement Any pavement made from one or more layers of asphaltic concrete.

asphalt pavement sealer A material applied to asphalt pavement after compaction to protect it from deterioration caused by exposure to weather or petroleum products.

asphalt penetration A measure of the hardness or consistency of asphalt, expressed as the distance a needle of standard diameter will penetrate a sample under given time, load, and temperature conditions.

asphalt-prepared roofing (asphaltic felt, bituminous felt, cold-process roofing, prepared roofing, rolled roofing, rolled strip roofing, roofing felt, sanded bituminous felt, saturated felt, self-finished roofing felt) A roof covering manufactured in rolls and made from asphalt-impregnated felt with a harder layer of asphalt applied to the surface of the felt. All or part of the "weather" side may be covered with aggregate of various sizes and colors.

asphalt prime coat A tack coat, usually an emulsion, to increase the adhesion of one course to another in pavement construction.

asphalt primer A liquid asphalt of low viscosity that is applied to a nonbituminous surface such as concrete to prepare the surface for an asphalt course.

asphalt seal coat A thin asphalt surface treatment used to waterproof and improve the wearing surface texture of pavement, particularly that of an asphaltic macadam. Depending on the intended purpose for the pavement, a seal coat may or may not include aggregate.

asphalt shingles (composition shingles, strip slates) Roofing felt saturated with asphalt, coated on the weather side with a harder asphalt and aggregate particles, and cut into shingles for application to a sloped roof.

asphalt shingles (composition shingles, strip slates)

asphalt surface course The top or wearing course of asphaltic concrete pavement.

asphalt surface treatment The application of liquid asphalt to any asphaltic pavement, with or without adding aggregate.

asphalt tack coat A light coat of asphalt, usually an emulsion, added to an existing pavement to create a bond between the pavement and another course.



asphalt surface course

aspirator A device that draws a stream of gas or liquid into it by means of the suction created by liquid or gas passing through an orifice. An aspirator is used for mixing air with a stream of water or for mixing a controlled amount of a chemical with water.

as-planned schedule A project schedule prepared by the contractor to indicate the intended progress and method of performance. Frequently used as the baseline schedule for calculating delay.

assembled occupancy For design purposes, the maximum number of people who will occupy a room or hall at one time.

assessed valuation The value of a property assigned by a municipality for real estate tax purposes. The valuation may be higher or lower than the market value of the property.

assessment **1.** A tax on property. **2.** A charge for specific services, such as sewer or water, by a government agency.

assessment ratio The ratio between the market value and assessed valuation of a property, expressed as a percent.

asset An item of monetary value, which can include real, personal, or financial property, that is expected to have some value in a future period.

assignment **1.** A transfer of rights, frequently involving rights arising under a contract. **2.** With respect to a contract, a document stating that payment for work completed or materials delivered must be made to someone other than the company or person specified in the contract.

associate dimensioning A feature of a computer-aided design and drafting system that dynamically recalculates all dimensions affected by a change the operator has made.

astragal **1.** A molding attached to one of a pair of doors or casement windows to cover up the joint between two stiles. **2.** A bead molding, most often half-round and ornate, with a narrow flat band, or fillet, on at least one side.



astragal (a)



astragal (b)



astragal (c)



astragal (d)

atmospheric pressure The pressure (14.7 psi) exerted by the earth's atmosphere at sea level under standard conditions.

attenuation The sound reduction process utilizing a sound-absorbing system.

Atterberg limits Terms defining the properties of soils at different water contents.

Atterberg test Laboratory tests to determine the Atterberg limits.

attic Unfinished space between ceiling joists of the top story of a building and the roof rafters.

attic tank A domestic water storage tank installed above the highest plumbing fixture in a building to provide water pressure by gravity.

attic ventilator An electric fan, frequently thermostatically controlled, to push hot air out of an attic.



attic ventilator

attorney-in-fact One who holds a power of attorney from another to execute documents on behalf of the grantor of the power.

attribute In the context of asset or project planning, a characteristic or property that is appraised in terms of whether it does or does not exist (e.g., go or not-go) with respect to a given requirement.*

audio frequencies Frequencies between 15 and 20,000 cycles per second (Hz), which is within hearing range of the human ear.

audio masking system Reducing distracting sounds and increasing speech privacy through the use of sound-masking equipment or software. Some systems provide protection from laser beams and other high-tech sound detection devices.

audit The examination of records, documents, and other evidence for the purpose of determining the propriety of transactions and assessing fiscal compliance with relevant cost and accounting requirements.

auger **1.** A carpenter's hand tool used for boring holes in wood. **2.** A handheld or rotary-powered tool with a helical cutting edge used for drilling holes in soil. Augers are used for taking soil samples, drilling for caissons, or drilling for cast-in-place piles.

auger

authority having jurisdiction (AHJ) A person who has the delegated authority to determine, mandate, and enforce code requirements established by jurisdictional governing bodies.

authorized work An effort that has been approved by higher authority and may or may not be definitive.*

autoclave A chamber in which steam at high pressure is used to cure precast concrete members.

automatic door A power-operated door that opens at the approach of a person or vehicle and closes when the person or vehicle has passed.

automatic fire pump A pump in a standpipe or sprinkler system that turns on when the water pressure drops below a predetermined level.

automatic fire vent (automatic smoke vent) A device in the roof of a building that operates automatically to control fire or smoke.



automatic fire vent (automatic smoke vent)

automatic iris An optical device, much like the iris in the eye, containing a diaphragm that expands and contracts to control the amount of light that passes through the lens.

automatic operator A remote-control operating device. The term usually refers to the opening and closing of doors by electronically actuated switches.

automatic sprinkler system A fire safety system designed to provide instant and continuous spraying of water over large areas in the case of fire.



automatic sprinkler system

automatic transfer switch In an electrical system, a switch that automatically transfers the load to another circuit when the voltage drops below a predetermined level.

auxiliary contact An additional contact not normally associated with operation of a switching device such as a contact or circuit breaker.

auxiliary rafter (cushion rafter) A rafter used to strengthen the main rafter, usually at the area of greatest load.

auxiliary reinforcement In a prestressed concrete member, refers to all reinforcing steel other than the prestressing steel.

average annual cost The conversion, by an interest rate and present worth technique, of all capital and operating costs to a series of equivalent equal annual costs. As a system for comparing proposal investments, it requires assumption of a specific minimum acceptable interest rate.*

average bond stress The force exerted on a steel reinforcing bar divided by the product of the perimeter multiplied by the embedded length.

average grade The average of ground surface elevations within a building site.

average haul The average distance material is transported from where it originates to where it is deposited, such as from cut to fill in roadway construction.

awl A hand tool used for piercing holes, particularly in leather. Often fitted with a needle for sewing heavy materials.

awning A projection over a door or window, often retractable, for protection against rain and sun.



awning

awning window A window that is hinged at the top.



awning window

ax (axe) A sharp-edged hand tool for splitting wood and hewing timber.

axed brick (rough axed brick) Brick shaped by an ax so as to create rough surfaces.

ax hammer A hand tool for dressing stone.



ax hammer

axial fan A fan that produces pressure from the velocity of gas passing through the impeller, with no pressure being produced by centrifugal force.



axial fan

axial force diagram In statics, a graphic representation of the axial loads acting at each section of a structural member.

axial load (axial force) The longitudinal force acting on a structural member.

axis A straight line representing the center of symmetry of a plane or solid object.

azimuth The horizontal angle measured clockwise from north to an object.

B

Abbreviations

B1S banded one side, bead one side

B2E banded two ends

B2S banded two sides, bead two sides, bright two sides

B2S1E banded two sides and one end

B3E beveled on three edges

B4E beveled on four edges

B beam, boron, brightness

BA bright annealed

BAS building automation system

bat. batten

B&B in the lumber industry, grade B and better; balled and burlapped

bbl, Bbl., brl barrel

BC building code

b&cb beaded on the edge and center

bcc body-centered cubic

BCM broken cubic meter

BCY broken cubic yard

bd in the lumber industry, board

bdl bundle

BE in the piping industry, beveled end

BET between

Beth B Bethlehem beam

bev beveled

bev sid beveled siding

BF, bd ft board foot

BFP backflow preventer

bg bag

BG below ground or below grade

Bg cem bag of cement

Bh Brinell hardness

Bhn Brinell hardness number

BHP brake horsepower, boiler horsepower

BI black iron

BICSI Building Industry Consulting Service International

BIM Building Information Modeling

Bit, Bitum. bituminous

Bk backed

Bkrs breakers

B/L bill of lading

BL building line

bldg, Bldg building

blk block, black

BLKG blocking

BLO blower

BLR boiler

blt built, borrowed light

bm board measure

BM beam, bench mark

B/M, BOM bill of materials

BMEP brake mean effective measure

B&O back-out punch

BOCA Building Officials and Code Administrators International

b of b back of board

boil boilermaker

BP blueprint, baseplate, bearing pile, building paper

bpd barrels per day

BPG beveled plate glass

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

BPM blows per minute

BR bedroom

brc brace

brcg bracing

BRG bearing

BRI building-related illness

BRK brick

BRKT, bkt bracket

BRS brass

Br Std, BS British Standard

BRZ bronze

BRZG brazing

B&S beams and stringers; bell and spigot; Brown and Sharpe gauge

BSMT basement

BSR building space requirements

BTB bituminous treated base

btr, Btr better

Btu British thermal unit

BTUH Btu per hour

but buttress

BW butt weld

B&W black and white

BX interlocked armored cable

Definitions

babbitt An antifriction alloy composed of tin and lesser amounts of copper and antimony. Babbitt is used in bushings and bearings.

back **1.** That part, area, or surface that is farthest from the front. **2.** The portion behind or opposite that is intended for use or view. **3.** The reverse (scale). **4.** That portion that offers strength or support from the rear. **5.** The extrados of an arch or vault sometimes concealed in the surrounding masonry. **6.** In slate or tile, the side opposite the bed. **7.** The surface of wallboard that receives the plaster. **8.** The side of a piece of lumber or plywood opposite the face. The back is the side with the lower overall quality or appearance.

back arch A concealed arch that supports the inner part (or backing) of a wall where a lintel carries the exterior facing.

backband A rabbeted molding used to surround the outside edge of a casing in an opening such as a door or window.

backbone subsystem In a premises distribution system, the cable that runs from the equipment room to the various floors in a building. In a single-floor building, the subsystem is the main trunk of the communications system.

back boxing Thin boards used in construction of double-hung windows to enclose the channel in which the sash weights hang, and to keep the channel free of mortar

back-brush To paint over a freshly painted surface with a finishing return stroke.

backcharge A charge against a contract in the form of a credit change order to a contractor for the cost of having others perform portions of their contract.

back check The mechanism in a hydraulic door closer or door check that reduces the speed with which the door can be opened.

back clip A special clip used on the hydraulic door closer or door check that reduces the speed with which the door can be opened.

back coating Asphalt coating applied to the back of shingles or rolled roofing.



back check

back-draft damper A damper, the blades of which are gravity-controlled and allow the passage of air in one direction only.

back edging A process by which glazed ceramic pipe is cut by first chipping away the glaze and then chipping the underlying pipe until it is cut through.

backer rod foam Foam rope used to seal wide gaps and joints before caulk is applied, reducing unwanted air leakage.

backfill Earth, soil, or other material used to replace previously excavated material, as around a newly constructed foundation wall.



backfill

backfilling **1.** The process of placing backfill. **2.** Rough masonry laid behind a facing or between two faces. **3.** Brickwork laid in spaces between structural timbers



backfilling

backflow **1.** The unintentional reversal of the normal and intended direction of flow. Backflow is sometimes caused by back siphonage. **2.** The flow of water or other liquids, mixtures, or substances into the distributing pipes of a potable water supply system from a source other than the intended source.

backflow preventer A device or means to prevent backflow into the potable water system.



backflow preventer

backhoe A powered excavating machine used to cut trenches by drawing a boom-mounted bucket through the ground toward the machine. The bucket is raised and swung to either side to deposit the excavated material.



backhoe

backing **1.** The bevel applied to the upper edge of a hip rafter. **2.** Positioning furring onto joists to create a level surface on which to lay floorboards. **3.** Furring applied to the inside angles of walls or partitions to provide solid corners for securing wallboard. **4.** The first coat of plaster on lath. **5.** The unseen or unfinished inner face of a wall. **6.** Coursed masonry applied over an extrados of an arch. **7.** Interior wall bricks concealed by the facing bricks. **8.** The wainscoting between a floor and a window. **9.** The material under the pile or facing of a carpet. **10.** The stone used for random rubble walls.

backing board **1.** In a suspended acoustical ceiling, gypsum board to which acoustical tiles are secured. **2.** Gypsum wallboard or other material secured to wall studs prior to paneling to provide rigidity, sound insulation, and fire resistance.

backing brick A lower quality of brick used in places where it will be concealed by face brick or other masonry.

back iron Reinforcing steel plate on a wood plane.

backjoint A rabbet in masonry such as that over a fireplace to receive a wood nailer.

backlight To illuminate from behind (and often above) an object.

back lining (back jamb) **1.** In a weighted sash window, the thin wood strip that closes the jamb of a cased frame to provide a smooth surface for the operation of the sash and, where applicable, prevents abrasion of brickwork by the sash weights. **2.** The framing piece that constitutes the back recess for box shutters.

back lintel A lintel used to support the backing of a masonry wall, and therefore, not visible on the face.

back-mop To apply hot bituminous material, either by mop or mechanical applicator, to the underside of roofing felt during the construction of a built-up roof.



back-mop

back-nailing Nailing the layers, or plies, of a built-up roof to the substrate to help prevent slippage. Performed in addition to hot mopping.

back nut **1.** A threaded nut that helps to create a watertight joint, as on the long thread of a pipe connector, and whose one dished side accepts a grommet. **2.** A locknut.

back-paint To apply paint to the reverse or unseen side of an object, not for appearance but for protection against weather.

backplastering Plaster applied to one face of a lath system following the application and subsequent hardening of plaster that has been applied to the opposite face.

backplate A wood or metal plate that functions as backing for a structural member.

back pressure Hydraulic or pneumatic pressure in a direction opposite the normal and intended direction of flow through a pipe, conduit, or duct. Usually caused by a restriction to the flow.

back primed Back-painted woodwork. Used primarily for exterior shingles, siding, or trim.

backsaw A handsaw used in finish carpentry work. The back (noncutting) edge of the saw is stiffened with a steel or brass strip. A backsaw is used for cutting mitered joints and other joinery work.



backsaw

backset The offset or horizontal distance between the face or front of a door back to the center of the keyhole or central axis of the knob.

backshoring Reinsertion of shores beneath a stripped concrete slab after the original formwork and shoring has been removed from a small section. Unlike reshoring, backshoring keeps the slab from supporting its own weight or the weight of existing loads above it until the slab attains full strength.



backset

back sight In surveying, a sight on an established survey point or line.

backsplash A protective panel, apron, or sheet of waterproof material positioned on a wall behind a sink, counter, or lavatory.

backsplash

backup **1.** That part of a masonry wall behind the exterior facing. **2.** Any substance placed into a joint to seal the joint and reduce its depth, and/or to inhibit sagging of the sealant. **3.** Overflow due to blockage in a piping system. **4.** Supporting documents for an estimate or schedule including detailed calculations, descriptions of data sources, and comments on the quality of the data.*



backup

backup figures The detailed calculations that produce unit prices.

backup strip (lathing board) A narrow strip of wood secured to the corner of a wall or partition to provide a base on which to nail the ends of the lathing.

back veneer The ply on veneer plywood opposite the face veneer and usually of lesser quality.

back vent In plumbing, a venting device installed on the downstream side of a trap to protect it from siphonage.

backwater valve (backflow valve) A check valve in a drainage pipe that prevents reversal of flow.

badger plane A large, wooden hand plane for rabbeting, whose mouth is fashioned obliquely from side to side to allow its use close to corners.

baffle **1.** A tray or partition employed on conveying equipment to direct or change the direction of flow. **2.** An opaque or translucent plate-like protective shield used against direct observation of a light source; a light baffle. **3.** A plate-like device for reducing sound transmission. **4.** Any construction intended to change the direction of flow of a liquid.

bag (sack) A quantity of Portland cement; 94 pounds in the United States, 87.5 pounds in Canada, 112 pounds in the United Kingdom, and 50 kilograms in most other countries. Different weights per bag are commonly used for other types of cement.

bag plug An inflatable drain stopper usually placed at the lowest point in a piping system; used during testing of the system's integrity.

bag trap A plumbing trap, shaped like an S, whose inlet and outlet are in alignment.

bakelite A plastic developed for use in electrical fittings, door handles, pulls, etc. Bakelite has high chemical and electrical resistance.

balance arm A supporting arm at the side of a projected window that allows the sash to be opened without an appreciable change in its center of gravity.

balance beam (balance bar) A counterbalance consisting of a long beam attached to a movable structure, such as a drawbridge or gate, whose weight it offsets during opening and closing.

balanced circuit A three-wire electric power circuit whose main conductors all carry substantially equal currents, either alternating or direct, and in which there exists substantially equal voltages between each main conductor and neutral.

balanced door A door that is installed using double-pivoted hardware, which allows it to swing open in a semi-counterbalanced manner.

balanced earthwork Cutting and filling in which the amount of one is equal to the amount of the other after swelling and compaction factors are applied.



balanced earthwork

balanced load **1.** In an electric circuit, such as a three-wire system, a load connected such that the currents on each side are equal. **2.** In reinforced concrete beam design, a load that would cause crushing of concrete and yielding of tensile steel simultaneously.

balanced sash A sash in a double-hung window that requires very little effort to raise or lower because its weight is counterbalanced with weights or pretensioned springs.

balance spring A window mechanism for counterbalancing a sliding sash to keep it open as needed.



balanced sash

balanced step (dancing step, dancing winder) One of a series of winders that are balanced (as opposed to radiating from a common center). Their narrow ends are nearly equal in width to that of the straight portion of the adjacent stair flight to provide the line of traffic with a relatively even tread width.

balance point The temperature outside at which the heat lost from a building equals the heat gained from the occupants and equipment inside.

balancing **1.** Adjusting the mass distribution of a rotor to diminish journal vibrations and control the forces on the bearings from eccentric loading. **2.** In an HVAC system, adjusting the system to produce the desired level of heating and cooling in each area of a building.

balancing damper A plate or adjustable vane installed in a duct branch to regulate the flow of air in the duct.

balancing valve (balancing plug cock) A pipe valve used to control the flow rather than to shut it off.



balancing valve (balancing plug cock)

balcony **1.** A platform that protrudes from a building. It can be cantilevered or supported from below, and is usually protected by a railing or balustrade. **2.** A gallery protruding over the main floor of an auditorium; usually provides additional seating. **3.** In a theater, an elevated platform used as part of a permanent stage setting.



balcony

ballast **1.** A layer of coarse stone, gravel, slag, etc., over which concrete is placed. **2.** The crushed rock or gravel of a railroad bed on which ties are set. **3.** The transformer-like device that limits the electric current flowing through the gas within a fluorescent lamp. **4.** A high-intensity discharge that provides a lamp with the proper starting voltage. **5.** Material placed in a vessel to provide temporary stability.

ballast factor The ratio of the luminous output of a lamp when functioning on a ballast to its luminous output when functioning under standardized rating conditions.

ballast noise rating The degree of noise created by a fluorescent lamp ballast, represented by the letters A (the quietest) to F (the loudest).

ball-bearing hinge A butt hinge having ball bearings positioned between the knuckles to reduce friction.

ball catch A door fastener in which a spring-tensioned metal ball engages the striking plate to keep the door closed until force is applied.

ball-check valve A device used to stop the flow of liquid in one direction while allowing flow in an opposite direction. The pressure against a spring-loaded ball opens the valve in one direction of flow. Pressure from the other direction forces the ball against a seat, closing the valve and preventing flow.



ball-check valve

ball cock A float valve incorporating a spherical float; used to control the height of water, as in a toilet tank. *See also* **float valve**.

ball float The somewhat spherical floating device by which a ball valve is controlled.

ball joint A flexible mechanical joint that allows the axis of one part to be set at an angle to the other by virtue of the design of the two components. One possesses a fixed spherical shell to accommodate the ball-shaped end of the other.

balloon framing (balloon frame) A style of wood framing in which the vertical structural members (the posts and studs) are single, continuous pieces from sill to roof plate. The intermediate floor joists are supported by ledger boards spiked to or let into the studs. The elimination of cross grains in the studding reduces differential shrinkage.

ballpark figure A rough estimate.

ball peen hammer A hammer having a hemispherical peen on one end and used by metal workers, stonemasons, and mechanics.



ball peen hammer

ball valve A spherically shaped gate valve that provides a very tight shut-off for fluids in a high-pressure piping system.

baluster (banister) **1.** One of a series of short, vertical supporting elements for a handrail or a coping. **2.** Any vase-shaped supporting member or column. **3.** The roll on the side of an Ionic capital.

balustrade A complete railing system, including a top rail, balusters, and sometimes a bottom rail.



balustrade

band **1.** A group of small bars or the wire encircling the main reinforcement in a concrete structural member to form a peripheral tie. A band is also a group of bars distributed in a slab, wall, or footing. **2.** A horizontal ornamental feature of a wall, such as a flat frieze or fascia, usually having some kind of projecting molding at its upper and lower edges. **3.** Frequencies that occur in a range between two set limits.

band clamp A metal clamp consisting of two pieces that are bolted at their ends to hold riser pipes.

banding Wood strips or veneer attached to the exposed edges of plywood or particleboard in the construction of furniture or shelves.



band clamp

band joist A vertical member that forms the perimeter of a floor system.

band saw A power saw consisting of a continuous piece of flexible steel that runs around two pulleys and has teeth on one or both sides. A band saw is used to cut logs into cants, to rip lumber, and to cut curved shapes.

bandwidth A range of frequencies expressed in cycles per second (Hertz). The greater the bandwidth, the more information that can be transmitted.



band saw

bank A mass of soil rising above a digging or trucking level. Excavation and loading are done at the face of a bank.

bank cubic yard A unit designating one cubic yard of earth or rock, measured or calculated before removal from the bank.

banker A table or bench on which stonemasons or bricklayers shape their materials before setting them.

bank material Soil or rock in its natural state before excavation or blasting.

bank measure A determination of the volume of a mass of soil or rock in its natural state before excavation or blasting.

bank-run gravel (bank gravel, run-of-bank gravel, all-in aggregate) Granular material excavated without screening, scalping, or crushing. This type of gravel is a naturally occurring aggregate comprised of cobbles, gravel, sand, and fines.

bank sand Sand that is unlike lake sand in that it has sharp edges that provide a better bond and more strength when used in plastering.

bar **1.** A deformed steel member used to reinforce concrete. **2.** A solid piece of metal whose length is substantially greater than its width.

barbed wire (barbwire) Two or more wires twisted together with intermittent barbs incorporated during manufacture. Used for security and livestock fencing.

bar bending The process of bending reinforcing steel into shapes required for reinforced concrete construction.



barbed wire (barbwire)

bar chart (Gantt chart) A chart that graphically describes activities on a work-versus-time scale, illustrating planned start and completion dates for the various project activities.

bar clamp A carpenter's clamping device consisting of a long bar with adjustable clamping jaws. A bar clamp is used to hold joinery components during gluing.

bare cost The estimated cost of an item of work or a project before the bidder's markup for overhead and profit.

barefaced tenon (bareface tenon) A tenon that has a "shoulder" on one side only, and is used in the construction of wood doors.

bargain and sale deed A deed in which the grantor admits that he has some interest in, though not necessarily a clear and unencumbered title to, the property being conveyed. This kind of deed often contains a warranty that the grantor did not encumber the property or convey away any part of the title during his period of ownership.

bargeboard A board that hangs from the projecting end of a gable roof, often ornamental.

barge spike (boat spike) A long, square spike with a chisel point, used primarily in heavy timber construction.

bar graph A graphical representation of simultaneous events charted with reference to time. A bar graph is a simplified method of charting events, such as the processes of building construction. The horizontal axis of the chart is scaled to increments of time; the various events are charted vertically. The duration of the event is charted by a horizontal line or bar beginning at the time the event is scheduled to begin and ending at the time the event is scheduled to be completed. At any point in time, the reader can observe the number of events that are occurring simultaneously.



bar graph

bar joist A light steel joist of open-web construction with a single zigzag bar welded to upper and lower chords at the points of contact. Used as floor and roof supports.



bar joist

bar mat An assembly of steel reinforcement composed of two or more layers of bars placed at right angles to each other and tied together by welding or wire ties.

barometer A device that measures atmospheric pressure.

barrel 1. A unit of weight measure for Portland cement, equivalent to four bags or 376 pounds. **2.** A standard cylindrical vessel with a liquid capacity of 31½ gallons. **3.** That part of a pipe where the bore and wall thickness remain uniform.

barrel bolt (tower bolt) A cylindrical bolt mounted on a plate that has a case projecting from its surface to contain and guide the bolt.



barrel bolt (tower bolt)

barricade An obstruction used to deter the passage of persons or vehicles. Any of several devices used to detour or restrict passage.

barrier-free environment A building or area that is fully accessible and usable by disabled people.

barrow 1. A wheelbarrow. **2.** A large mound of earth or pile of rocks intentionally placed on top of an ancient burial site for protection.

bar sash lift A handle on the bottom rail of a sash for raising and lowering the sash.



bar sash lift

bar spacing The distance between parallel reinforcing bars, measured center to center.

bar strainer 1. A screening device, fabricated from parallel bars or rods, used over a drain to prevent the entrance of foreign objects. **2.** A bar screen.

bar support (bar chair) A rigid device of formed wire, plastic, or concrete, used to support or hold reinforcing bars in proper position during concrete operations.



bar support (bar chair)

bar-type grating An open grate with parallel bearing bars evenly spaced and attached to a frame. The grating may be cast or welded and may have crossbars.



bar-type grating

barway A gate with one or more sliding bars that act as large latch bolts.

BAS *See* **Building Automation System**.

bascule A structure that rotates like a saw around a horizontal axis, and that has a counterbalance at one end. The most common use is for a bascule bridge.

base 1. The lowest part of anything upon which the whole rests. **2.** A subfloor slab or "working mat," either previously placed and hardened or freshly placed, on which floor topping is placed. **3.** The underlying stratum on which a concrete slab, such as pavement, is placed. **4.** A board or molding used against the bottom of walls to cover their joint with the floor and to protect them from kicks and scuffs. **5.** The protection covering the unfinished edge of plaster or gypsum board.

base anchor A fixed or adjustable metal device attached to the base of a door frame to secure it to the floor.

base angle Angle iron stock attached to the perimeter of a foundation for supporting and aligning tilt-up wall panels.



base angle

base bid The amount of money stated in the bid as the sum for which the bidder offers to perform the work described in the bidding documents, prior to the adjustments for alternate bids that have been submitted.

base bid specifications The specifications that list or describe those specific materials, equipment, and construction methods that comprise the base bid exclusive of any alternate bids.

base block A usually unadorned, squared block that terminates a molded baseboard at an opening or serves as a base when attached to the foot of a door or the bottom of window trim.

baseboard heater A heating system in which the heating elements are housed in special panels placed horizontally along the baseboard of a wall. The heat source is commonly from hot water, steam, or electricity.



baseboard heater

base coat **1.** The plaster beneath the finish coat. **2.** The initial coat of paint or stain applied to a surface.

base course **1.** A layer of material of specified thickness constructed on the subgrade or subbase of a pavement to serve one or more functions, such as distributing loads, providing drainage, or minimizing frost action. **2.** The lowest course of masonry in a wall, pier, foundation, or footing course.

base flashing **1.** In roofing, the flashing supplied by the upturned edges of a watertight membrane. **2.** The metal or composition flashing used with any roofing material at the joint between the roofing surface and a vertical surface, such as a parapet or wall.



base flashing

base line **1.** The meticulously established reference line used in surveying or timber cruising. **2.** In construction, the center or reference line of location of a highway, railway, building, or bridge.

baseline schedule **1.** A fixed project schedule that is the standard by which project performance is measured. The current schedule is copied into the baseline schedule that remains frozen until it is reset. Resetting the baseline is done when the scope of the project has been changed significantly, for example after a negotiated change. At that point, the original or current baseline becomes invalid and should not be compared with the current schedule. **2.** Version of schedule that reflects all formally authorized scope and schedule changes.*

basement The bottom full story of a building below the first floor. A basement may be partially or completely below grade.

base metal In joining two metal pieces, the parent metal that is actually welded, brazed, or soldered, and remains unmelted after the joining process, as opposed to the filler metal deposited during the joining operation.

base molding Trim molding applied to the upper edge of interior baseboard.

baseplate A plate used to distribute vertical loads from structural columns or machinery.

base screed A galvanized metal screed with perforated or expanded flanges to provide ground for plaster and to separate areas of dissimilar materials.

base sheet The saturated and/or coated felt sheeting laid as the first ply in a built-up roof system.



baseplate

base shoe (base shoe molding, carpet strip, carpet stripmolding, floor molding, shoe molding) The molding or carpet strip covering the joint between a floor and a baseboard, often a quarter-round bead.

base shoe corner A block or a piece of molding installed in the corner of a room so as to eliminate the need to miter the base shoe.

base tee A pipe tee that has an attached supporting baseplate.

base tile The bottom course of tile in a tiled wall.

base trim Any decorative molding at the base of a wall, column, or pedestal.

basin **1.** A somewhat circular natural or excavated hollow or depression having sloping sides and usually used for holding water. **2.** A similarly shaped plumbing fixture, such as a sink.

basin wrench A wrench with a long shank and ratcheted jaws used in plumbing for difficult-to-reach areas, as when installing a faucet behind a sink.



basin wrench

basket crib A construction of interlocking timbers that can be arranged to function as a shaft liner, a protective device around a concrete pier in water, or a temporary floating foundation.

basket weave A pattern of bricks placed flat or on edge and arranged in a checkerboard layout.

bas-relief (basso-riviero, basso rilievo) Sculpture, carving, or embossing that protrudes slightly from its background.

basswood (American linden) A fine-textured softwood used for carving, cabinet work, and paneling. Basswood is also the primary source of excelsior.



basket weave

bastard Any nonstandard item deviating from normal size, slope, fabrication, or quality.

bastard file A flat file whose grain is somewhat less than coarse and that is primarily used to smooth metal surfaces.

bastard hip Hip roof design in which the angles of the hip rafter are not equal (or 45 degrees).

bastard granite A gneissic rock whose formation resembles that of true granite. Bastard granite is used mostly in wall construction but is not a true granite.

bastard masonry **1.** Thin blocks of facing stones used to face brick or rubble walls. Bastard masonry is dressed and built to resemble ashlar. **2.** Rough, quarry-dressed ashlar stones.

bastard pointing In masonry, a type of pointing that emphasizes the joint by forming a small ridge projecting along its center.

bastard-sawn **1.** Lumber that has been sawn so that the annual rings make angles of 30°–60° to the surface of the piece. **2.** Any lumber that has been flat-sawn, plain-sawn, or slash-sawn.

bat **1.** A burned brick or shape that, because it is broken, has only one good end. **2.** A piece of brick. **3.** A single unit of batt insulation. **4.** A piece of wood that serves as a brace.

bat bolt A bolt whose butt or tang has been provided with barbs or similar protrusions to increase its grip.

batch The quantity produced as the result of one mixing operation, as in a batch of concrete.

batch box A container of known volume used to measure the constituents of concrete or mortar in proper proportions.

batch mixer A machine that mixes concrete, grout, or mortar in batches in accordance to a design mix. Each batch is used completely before a second batch is started.



batch mixer

batch plant An installation of equipment including batchers and mixers as required for batching and mixing concrete materials. Called a *mixing plant* when mixing equipment is included.

bathroom A room usually equipped with a water closet, a lavatory, a bathtub and/or a shower.

batted work (broad tooled) Stone whose surface has been scored downward from the top by administering 8 to 10 narrow, parallel strikes per inch with a batting tool.

batten **1.** A narrow strip of wood used as siding to cover the joints of parallel boards or plywood. The resultant pattern is referred to as *board and batten*. **2.** A strip of wood placed perpendicular to several parallel pieces of wood to hold them together. **3.** A furring strip fastened to a wall to provide a base for lathing or plastering. **4.** In roofing, a strip of wood placed over boards or roof structural members to provide a base for the application of wood or slate shingles, or clay tiles. **5.** The steel strip that fastens the metal flooring on a fire escape.



batten

batten door (ledged door, unframed door) A door in which stiles are absent and that consists of vertical boards or sheathing secured on the back side by horizontal battens.

batten roll (conical roll) In metal roofing, a roll joint fabricated over a triangular wood piece.

batten seam In metal roofing, a seam fabricated around a wood strip.

batter **1.** To incline from the vertical. **2.** A slope, such as that of the outer side of a wall, that is wider at the bottom than at the top.



batten seam

batter boards Pairs of horizontal boards nailed to wood stakes adjoining an excavation. Used with strings as a guide to elevation and to outline a proposed building. The strings strung between boards can be left in place during excavation.

batter brace (batter post) **1.** A bracing member positioned diagonally so as to reinforce an end of a truss. **2.** An inclined timber that forms a side support to a tunnel roof.



batter boards

battered wall A wall that slopes backward, as by recessing or sloping masonry in successive courses.

batter level An instrument used to measure the inclination of a slope.



battered wall

batter pile (brace pile, raking pile, spur pile) **1.** A pile driven somewhat diagonally so as to resist horizontal forces. **2.** Any pile installed at an angle to the vertical.

batter rule An instrument used to adjust the inclination of a battered wall during its construction. A batter rule incorporates a rule or frame and a plumb line and bob.

batter stick A tapered board hung vertically by its wide end or used in conjunction with a level to check the batter of a wall surface.

batting tool A mason's dressing chisel used to apply a striated surface to stone.

batt insulation Thermal or sound-insulating material, such as fiberglass or expanded shale, that has been fashioned into a flexible, blanket-like form, often with a vapor barrier on one side. Batt insulation is manufactured in dimensions that facilitate its installation between the studs or joists of a frame construction.

bay **1.** In construction, the space between two main trusses or beams. **2.** The space between two adjacent piers or mullions, or between two adjacent lines of columns. **3.** A small, well-defined area of concrete laid in the course of placing larger areas, such as floors, pavements, or runways. **4.** The projecting structure of a bay window.

bay window A usually large window or group of windows that projects from a wall of a building forming a recess within the building.



bay window

beacon **1.** A light that indicates a location by directing its powerful beam slightly above the horizontal and rotating it so that to a stationary observer, it appears to be flashing. A beacon is used at airports, on lighthouses, etc. **2.** A transmitter that broadcasts warning or guiding signals.

bead **1.** Any molding, stop, or caulking used around a glass panel to hold it in position. **2.** A stop or strip of wood against which a door or window sash closes. **3.** A strip of sheet metal that has been fabricated so as to have a projecting nosing and two perforated or expanded flanges. A bead is used as a stop at the perimeter of a plastered surface or as reinforcement at the corners. **4.** A narrow, half-round molding, either attached to or milled on a larger piece. **5.** A square or rectangular trim less than 1″ in width and thickness. **6.** A choker ferrule; the knob on the end of a choker.

bead-and-real Half-round molding into which are incorporated alternating patterns of discs and elongated beads.

bead board A decorative form of wainscoting that consists of a quarter-round molding.

bead butt (bead and butt) Thick, framed panelwork, as on a door, having one face flush with the frame and decorated with moldings (beads) on the adjoining edges, running with the grain and butting against the rail. The other side is recessed and without moldings.

bead molding Small, half-round, convex molding, either continuous or divided, that resembles a succession of beads.

beam **1.** A horizontal structural member, such as a girder, rafter, or purlin, that transversely supports a load and transfers the load to vertical members, such as columns and walls. **2.** The graduated horizontal bar of a weighing scale.



beam

beam anchor (joist anchor, wall anchor) A metal tie used to secure a beam, joist, or floor firmly to a wall.

beam-and-girder construction A type of floor construction in which slabs are used to distribute the load to evenly spaced beams and girders.



beam-and-girder construction

beam bearing plate A metal plate positioned under the end of a beam to distribute the reaction load over a larger area. When used under a column, it is called a *loose plate*.

beam blocking Covering or enclosing a beam, joist, or girder to make it appear larger than it really is.



beam bolster

beam bolster A rod or heavy wire device used to support steel reinforcement in the formwork for a reinforced concrete beam.

beam brick A lintel made of brick courses, often held together by metal straps.

beam ceiling A type of construction in which the structural and/or ornamental overhead beams are left exposed to view from the room below.

beam column A structural member that transmits an axial load as well as a transverse load.

beam compass An instrument comprising a small horizontal bar with two vertical components that can slide along it. One carries a sharp-pointed tip and is held by the user in a stationary position. The other carries a pencil tip and is moved around the first to draw circles or arcs of circles for full-size working drawings.

beam fill (beam filling) Masonry, brickwork, or concrete placed between floor or ceiling joists to stiffen the joists and provide fire resistance.

beam form A retainer or mold constructed to give the necessary shape, support, and finish to a concrete beam.



beam form

beam hanger (beam saddle) **1.** A wire, strap, or other hardware device used to hang beam forms from another structural member. **2.** In timber construction, a strap, wire, or stirrup used to support a beam.

beam haunch A poured concrete section that continues beyond a beam to support the sill.



beam pocket

beam pocket **1.** A space left open in a vertical structural member to receive a beam. **2.** An opening in the column or girder form where forms for an intersecting beam will be framed.

bearing **1.** That section of a structural member, such as a column, beam, or truss, that rests on the supports. **2.** A device used to support or steady a shaft, axle, or trunnion. **3.** In surveying, the horizontal angle between a reference direction, such as true north, and a given line. **4.** Descriptive of any wall that provides support to the floor and/or roof of a building.



bearing

bearing bar **1.** A wrought-iron bar used on masonry to offer a level support for floor joists. **2.** A supporting bar for a grating.

bearing pile A pile that supports a vertical load.



bearing pile

bearing plate A steel plate positioned under a beam, column, girder, or truss to distribute a load to a support member.



bearing plate

bearing stratum The soil or rock stratum on which a footing or mat bears or carries the load transferred to it by a pile, caisson, or similar deep foundation unit.

bearing wall Any wall that supports a vertical load as well as its own weight.

bed **1.** The mortar into which masonry units are set. **2.** Sand or other aggregate on which pipe or conduit is laid in a trench. **3.** To set in place with putty or similar compound, as might be performed in glazing. **4.** A supporting base for engines or machinery. **5.** To level or smooth a path onto which a tree will be felled. **6.** To set glass in place using putty.

bedding **1.** A prepared base for masonry or concrete. **2.** The lath or other support(s) on which pipe is laid.

bedding coat (bed coat) Ordinarily, the initial coat of joint compound on gypsum board applied over tape, bead, and other fastener heads.

bedding dot A small area of plaster built out of the face of a finished wall or ceiling that acts as a screed for leveling and plumbing in a plastering operation.

bedding stone A flat slab of marble with which bricklayers and masons check the flatness of rubbed bricks.

bed dowel A dowel placed in the mortar bed for a stone to prevent settlement before the mortar has set.

bed joint **1.** The horizontal layer of mortar on which a masonry unit is laid. **2.** In an arch, a horizontal joint or one that radiates between adjacent voussoirs. **3.** A horizontal fault in a rock formation.

bed molding **1.** A molding placed at the angle between a vertical surface and an overhanging horizontal surface, such as between a side wall and the eaves of a building. **2.** The lowest molding in a band of moldings. **3.** In classical architecture, a molding of a cornice of an entablature, located between the corona and the frieze.

bedplate A baseplate, frame, or platform that supports a structural element, furnace, or heavy machine.

bedrock Solid rock that underlies the earth's surface soil and that can provide, by its very existence, the foundation on which a heavy structure may be erected.

bed timber A large wood member set perpendicular to trusses that serves as a foundation or support element.

BEES (Building for Environmental and Economic Sustainability) A methodology that considers multiple environmental and economic impacts over the building product's entire life cycle to develop a rational decision-making scoring system.

Belgian block A paving stone shaped like a truncated pyramid and laid with the largest face down.

bell (hub) A portion of a pipe that, for a short distance, is sufficiently enlarged to receive the end of another pipe of the same diameter for the purpose of making a joint.



bell (hub)

bell-and-spigot joint (bell joint, spigot-and-socket joint) The most commonly used joint in cast-iron pipe. Each length is made with an enlarged diameter or bell at one end into which the plain or spigot end of another piece is inserted. The joint is sealed by cement, oakum, lead, or rubber caulked into the bell around the spigot.



bell-and-spigot joint (bell joint, spigot-and-socket joint)

belled caisson A caisson with an enlarged, bell-shaped base.

belled excavation The bell-shaped lower portion of a shaft or footing excavation frequently used in caisson construction.

belling In pier, caisson, or pile construction, the process of enlarging the base of a foundation element at the bearing stratum to provide more bearing area.



belling

bellows expansion joint In a run of piping, a joint accomplished with flexible metal bellows that can expand and/or contract linearly to allow for thermally induced linear fluctuations of the run itself.

bell transformer A very small transformer that supplies low voltage power on demand to doorbells or similar devices.

belt **1.** A flexible continuous loop that conveys power (or materials) between the pulleys or rollers around which it passes. **2.** A course of brick or stone that protrudes from a wall of similar material and is usually positioned in line with the windowsills.

belt course **1.** In masonry, a continuous layer of stone or brick that protrudes from the face of a stone or brick wall. **2.** In carpentry, a horizontal band around a building, usually made of a flat board member and molding.

belt loader An excavating machine comprising an auger or other cutting edge that digs away the earth, and a conveyer belt that elevates the excavated material for loading onto a truck or depositing elsewhere.

belt sander An electrically powered, portable sanding tool with a continuous abrasive belt driven in one direction only. A belt sander is used to smooth surfaces, usually wood.



belt sander

belvedere A rooftop pavillion or a small structure, like a gazebo, for enjoying a vista.

bench brake A large, heavy, bench-mounted device for bending sheet metal.

bench dog A peg or pin partially inserted into a hole at an edge or end of a workbench to help secure a piece of work or prevent it from sliding off the bench.

benched foundation (stepped foundation) A foundation cut as a series of horizontal steps in an inclined bearing stratum to prevent sliding when loaded.

bench hook (side hook) In carpentry, any device used to protect the top surface of a workbench from being scarred or damaged by any slipping or sliding of the work. It usually keeps the work positioned toward the front of the bench.



benched foundation (stepped foundation)

benching **1.** A half-round channel cast in the concrete in the bottom of a manhole to direct discharge when the flow is low. **2.** Concrete placed in horizontal steps on steeply sloping fill to prevent sliding. **3.** Concrete laid on the side slopes of drainage channels where the slopes are interrupted by manholes, etc. **4.** Concrete laid in a pipeline trench to provide firmer support.

bench mark **1.** A marked reference point on a permanent object, such as a metal disc set in concrete, whose elevation as referenced to a datum is known. **2.** A mark made by a surveyor or general contractor to be used as a reference point when measuring the elevation or location of other points.

bench stop A usually notched, adjustable metal apparatus fastened close to an end of a workbench to hold a piece of wood securely during planing.

bench table A course of masonry, wide enough to form a seat, that protrudes from the foot of an interior wall or column.

bench vise An ordinary vise attached to a workbench to hold a material or component in place while it is being worked on.



bench vise

bend **1.** An elbow fitting or other short length of bent conduit used to join two lengths of straight adjacent conduit. **2.** A pipe fitting used to achieve a change in direction.

bending extra A charge (an extra) by the fabricator for bending reinforcing bars. Extras are charged by the ton according to bar sizes.

bending iron A tool used to shape or expand pipe.

bending moment The bending effect at any section of a beam. The bending moment is equal to the algebraic sum of moments taken about the center of gravity of that section.

bending moment diagram A graphic representation of the variation of bending moment along the length of the member for a given stationary system of loads.

bending schedule A list of reinforcement prepared by the designer or detailer of a reinforced concrete structure that shows the shapes, dimensions, and location of every bar, and the number of bars required.

bend test Subjecting a flat bar to a 180° cold bend in order to test its weld or steel and to check its ductility, which is verified if no cracking occurs during the test.

benefit cost analysis A method of evaluating projects or investments by comparing the present value or annual value of expected benefits to the present value or annual value of expected costs.*

benefit-to-cost ratio (BTC) Benefits divided by costs, where both are discounted to a present value or equivalent uniform annual value.*

bent **1.** A structural framework, transverse to the length of a structure, designed to carry lateral as well as vertical loads. **2.** Any of several grasses of the genus *agrostis* that are used where a resilient, velvety texture is required.



bent

bent bar A reinforcing bar bent to a prescribed shape, such as a truss, straight bar with hook, stirrup, or column tie. A bent bar is bent to pass from one face of a member to the other.

bentonite A clay composed principally of minerals in the montmorillonite group and characterized by high absorption and very large volume change with wetting or drying.



bent bar

berm **1.** An artificially placed continuous ridge or bank of earth, usually along a roadside. Also called a *shoulder*. **2.** A ridge or bank of earth placed against a masonry wall. **3.** A ledge or strip of earth placed so as to support pipes or beams. **4.** Earthen dikes or embankments constructed to retain water on land that will be flood-irrigated. **5.** Earthen or paved dike-like embankments for diverting runoff water. **6.** A raised wall enclosing a liquid waste storage or spill area. **7.** An asphaltic concrete or concrete curb.

best practices Practical techniques gained from experience that have been shown to produce best results.*

bevel **1.** Any angle (except a right angle) or inclination of any line or surface that joins another. **2.** An adjustable instrument used for determining, measuring, or reproducing angles. **3.** In welding, preparation on the edges to be welded.

bevel angle In welding, the angle created by the prepared edge of a member and a plane perpendicular to the surface of the member.

bevel board (pitch board) A board that has been cut to a predetermined desired, or required, angle and employed in any angular wood construction, including roof and stair framing.

bevel chisel A wood-cutting chisel whose cutting edge is angled between its sides.



bevel chisel

bevel cut Any cut made at an angle other than a right angle.

beveled edge **1.** A vertical front edge on a door, cut so as to have a slope of $^{1}/_{8}$″ in 2″ from a plane perpendicular to the face of the door. **2.** The factory-applied angle on the edge of gypsum board that creates a “vee” grooved joint when two pieces are installed together. **3.** A chamfer strip incorporated into concrete forms for columns or beams so as to eliminate sharp corners on the finished product.

beveled end The end of a pipe or fitting that has been prepared for welding.



beveled end

beveled washer A washer with a bevel on one side, and used mostly in structural steel work to provide a flat surface for the nut wherever a threaded rod or bolt passes through a beam at an angle.



beveled washer

bevel joint A carpentry joint in which two wood pieces meet at any angle except a right angle.

B-grade wood The classification of a somewhat inferior grade of solid surface veneer that contains visible repair plugs and tight knots.

bias The fixed voltage applied to an electrode.

bibcock (bib, bibb, bib tap) **1.** Any faucet or stopcock that has its nozzle directed downward. **2.** Any tap supplied by a horizontal pipe.



bibcock (bib, bibb, bib tap)

bib valve Any standard bibcock or faucet equipped with a handle that is turned in one direction to initiate the flow of water, and turned in the opposite direction (screwed down) to shut off the flow by closing a washer disk onto a seating within the valve.

bid A complete signed proposal to perform work (or a designated portion) for a stipulated sum. A bid is submitted in accordance with the bidding documents.

bid abstract (summary) On a given project, a compilation of bidders and their respective bids, usually separated into individual items.

bid bond A form of security executed by the bidder or principal in conjunction with a surety to guarantee that the bidder will enter into a contract within a specified period of time and will furnish the required bonds for performance and labor and materials payment.

bid call A published announcement that bids for a specific construction project will be accepted at a designated time and place.

bid date A predetermined date for the receipt of bids, usually set by the architect and owner.

bidder An entity or person who submits a bid for a prime contract with the owner. A bidder is not a contractor on a specific project until a contract is signed between the bidder and the owner.

bidding documents Documents usually including advertisement or invitation to bidders, instructions to bidders, bid form, form of contract, forms of bonds, conditions of contract, specifications, drawings, addenda, and any other information needed to completely describe the work so that constructors can adequately prepare proposals or bids for the owner's consideration.

bidet A low, basin-like bathroom fixture used for washing the lower part of the body.

bid form A form, furnished to the bidder, on which to submit his bid.

bid opening (bid letting) A formal meeting held at a specified time and place at which sealed bids are opened, tabulated, and read aloud.

bid package All drawings, specifications, documents, estimates, paperwork, bid forms, and bid bonds relevant to a construction project. A contract is based on the bid package.



bidet

bid protest A challenge by a disappointed bidder. On a government contract, this is submitted to the contracting officer or the GAO.

bid results The display of all the bids on a project.

bid security (bid guarantee) A bid bond or deposit submitted with a bid to guarantee to the owner that the bidder, if awarded the contract, will execute the contract within a specified period of time and will furnish any bonds or other requirements of the bid documents.

bifolding door A door that has two leaves, each consisting of two panels hinged together so that they fold on each other when the door is opened. One free edge of each leaf, or pair of panels, is hinged at a doorjamb; the other edge is supported from and guided by an overhead track.



bifolding door

bilateral contract A contract in which both contracting parties are bound to fulfill obligations toward each other.

bill of materials (BOM) **1.** Set of physical elements required to build a project. **2.** Hierarchical view of the physical assemblies, subassemblies, and components needed to fabricate a manufacturing product. **3.** Descriptive and quantitative list of materials, supplies, parts, and components required to produce a designated complete end item of materials, assembly, or subassembly.*

BIM application A very broad category of any software that can be used with a BIM platform or BIM environment to support Building Information Modeling. Thus, traditional applications such as drafting, rendering, specification writing, and engineering analysis tools are all potentially BIM applications, if workflows and/or data exchange integrates them in Building Information Modeling.

The term can be further qualified to denote specific application areas. For example, "BIM Architectural Design Application" is often used to refer to applications used primarily for architectural design, such as Revit®Architecture, Bentley Architecture, DigitalProject® and ArchiCAD®, or "BIM 4D application," that supports animation of a BIM model according to an associated construction schedule.

BIM environment A BIM environment is the functional capability embedded in a BIM server. It encompasses the data management information, and software for enforcing policies and practices that integrate the applications (tools or platforms) within an organization. Often the BIM environment is not conceptualized explicitly, but grows in ad hoc manner, driven by needs within the firm. Integration and support across multiple BIM platforms is its critical raison d'être, as well as managing communication with external systems. A BIM environment is supported by a set of policies and practices that facilitates management of BIM project data.

BIM platform A BIM design application that generates data for multiple uses and incorporates multiple tools directly or through interfaces with varying levels of integration. Most BIM design applications serve not only a tool function, such as 3D parametric object modeling, but also other functions, such as drawing production and application interface, making them also platforms.

BIM process A process that relies on the information generated by a BIM design tool for analysis, fabrication detailing, cost estimation, scheduling or other use.

BIM server A BIM server is a database system whose schema is based on an object-based format. It is different from existing project data management (PDM) systems and web-based project management systems in that PDM systems are file-based systems, and carry CAD and analysis package project files. BIM servers are object-based, allowing query, transfer, updating and management of individual project objects from a potentially heterogeneous set of applications. BIM servers are targeted to support BIM environments.

BIM system A software system that incorporates a BIM design application and other applications that utilize the BIM data. The system may be connected through a local area network or the Internet.

BIM tool A task-specific software application that manipulates a building model for some defined purpose and produces a specific outcome. Examples of tools include those used for drawing production, specification writing, cost estimation, clash and error detection, energy analysis, rendering and visualization.

bin A storage container, usually for loose materials such as sand, stone, or crushed rock.

binary code In computer technology, a system of representing numbers or letters using the base-2 (binary) number system.

binder **1.** Almost any cementing material, either hydrated cement or a product of cement or lime and reactive siliceous materials. The kinds of cement and the curing conditions determine the general type of binder formed. **2.** Any material, such as asphalt or resin, that forms the matrix of concretes, mortars, and sanded grouts. **3.** That ingredient of an adhesive composition that is principally responsible for the adhesive properties that actually hold the two bodies together. **4.** In paint, that nonvolatile ingredient, such as oil, varnish, protein, or size, that serves to hold the pigment particles together in a coherent film. **5.** A stirrup or other similar contrivance, usually of small-diameter rod, that functions to hold together the main steel in a reinforced concrete beam or column.

binder course (binding course) **1.** A succession of masonry units between an inner and outer wall that serve to bind them. **2.** In asphaltic concrete paving, an intermediate course between the base and the surfacing material composed of bituminously bound aggregate of intermediate size.



binder course (binding course)

binding post **1.** A set screw that holds a conductor against the terminal of a device or on equipment. **2.** A post attached to an electric wire, cable, or apparatus to facilitate a connection to it.



binding post

binding yarn (binder warp, crimp warp) In carpeting, the natural or synthetic yarn incorporated lengthwise into the woven fabric to "bind" the tufts of pile securely.

bin-wall A retaining, supporting, or protective structure made from a group of connected bins filled with gravel or sand. May serve as an abutment, a pier, a retaining wall, or as a shield against gunfire or explosion.



bin-wall

biological remediation The process of degrading a contaminant through a bioremediation process.

biological wastewater management Using natural or simulated wetlands to purify wastewater through biological processes.

biomass All of the living material in a given area; most often refers to vegetation.

biometrics Electronic methods of identifying and authenticating a person's identity through the confirmation of his/her physiological or sometimes behavioral characteristics. Techniques include fingerprint matching, iris and retinal scanning, facial recognition, hand geometry matching, voice recognition, and vein matching.

biparting door A sliding door with two leaves that slide in the same plane and meet at the door opening.



biparting door

birch A strong, fine-grained hardwood commonly used in veneer, furniture, flooring, and turned wood products.

bird screen Wire mesh used to cover chimneys, ventilators, and louvers to prevent birds from entering buildings through these accesses.

bird's mouth An L-shaped cut made in a diagonal timber, such as a rafter, so that it snugly fits against another timber, such as a wall plate.



bird's mouth

bit **1.** The tool that fits into a brace or drill and is rotated to bore a hole. **2.** On a soldering iron, the (usually copper) tip that heats the joint and melts the solder. **3.** That part of a key that is inserted into a lock and engages the tumblers or bolt. **4.** A binary digit; the smallest unit of computerized data.

bite In glazing, the overlap between the innermost edge of the stop or frame and the outer edge of the light or panel.

bit extension A length of rod held at one end by the chuck of a brace and equipped at the other end for holding a bit. A bit extension permits the drilling of holes whose required depth is greater than the length of an ordinary bit.

bit key (wing key) Any key that has a bit.

bitumen Any of several mixtures of naturally occurring or synthetically rendered hydrocarbons and other substances obtained from coal or petroleum by distillation. Bitumen is incorporated in asphalt and tar and is used in road surfacing and waterproofing operations.

bituminous Composed of, similar to, derived from, relating to, or containing bitumen. The term bituminous is descriptive of asphalt and tar products.

bituminous base course (black base) Bituminously bound aggregate serving as a foundation for binder courses and surface courses in asphalt paving operations.

bituminous cement A class of dark substances composed of intermediate hydrocarbons. Bituminous cement is available in solid, semisolid, or liquid states at normal temperatures.

bituminous coating Any waterproof or protective coating whose base is a compound of asphalt or tar.



bituminous coating

bituminous distributor A tank truck equipped with a perforated spray bar through which heated bituminous material, such as tar or road oil, is pumped onto the surface of a road.

bituminous emulsion **1.** A suspension of any globules of a bituminous substance in water or an aqueous solution. **2.** An invert emulsion of the above, i.e., a suspension of tiny globules of water or an aqueous solution in a liquid bituminous substance. This type of bituminous emulsion is applied to surfaces to provide a weatherproof coating.



bituminous distributor

bituminous grout A mixture of bituminous material and fine sand or other aggregate that, when heated, becomes liquid enough to flow into place without mechanical assistance. Bituminous grout will air-cure after being poured into cracks or joints as a filler and/or sealer.

bituminous leveling course In paving operations, a course consisting of a mixture of asphalt and sand and used to level or crown a base course or existing deteriorating pavement prior to the application of a surface.

bituminous macadam A paving material comprising bituminously coated coarse aggregate.

bituminous paint A thick black waterproofing paint containing substantial amounts of coal tar or asphalt.

B-labeled door A door carrying a certification from Underwriters' Laboratories that it is of a construction that will pass the standard fire door test required for a Class B opening, and that it has been prepared (with cuts and reinforcement) to receive the hardware required for a Class B opening.



B-labeled door

black japan A black, high-quality bituminous paint or varnish.

black plate Uncoated cold-rolled steel in 12″ to 32″ wide sheets.

black steel pipe Steel pipe that has not been galvanized.

black water Wastewater from toilets and other plumbing fixtures that may be contaminated with bacteria or other harmful organisms.

Blaine apparatus Air-permeability apparatus for measuring the surface area of a finely ground cement.

Blaine test A method for determining the fineness of cement or other material based on the permeability to air of a sample prepared under specified conditions.

blank door **1.** A recess in a wall fitted with a fixed door, and used for architectural effect. **2.** A door that has been fixed in position to seal an opening.

blanket **1.** Soil or pieces of rock remaining or intentionally placed over a blast area to contain or direct the throw of fragments. **2.** Insulation sandwiched between sheets of fabric, plaster, or paper facing, used for protecting fresh concrete during curing.

blanket insulation Faced or unfaced thermal or sound insulation, usually made of fiberglass, available in densities and thicknesses that allow it to conform to the various-shaped spaces it encounters in its many applications. Blanket insulation is the same as batt insulation, except that it is supplied in continuous rolls instead of sheets. *See also* **insulation blanket**.



blanket insulation

blank flange (blind flange) **1.** A flange in which the bolt holes are not drilled. **2.** A solid plate fitting used to seal off flow in a pipe.



blank flange (blind flange)

blank jamb A vertical component of a door frame as installed without any preparation for hardware installation.

blank-off A blank plate sealing off a sector of a diffuser to prevent airflow in the direction of the blank-off plate.

blast To loosen, crack, or move rock or hard-packed soil by the detonation of explosives.

blast cleaning Any cleaning method in which air, liquid, abrasive, or some combination of these is applied under pressure.

blast-furnace slag The nonmetallic waste that develops simultaneously with iron in a blast furnace. Consists essentially of silicates and aluminosilicates of calcium and other bases.



blank jamb

blast hole A vertical hole with a diameter of at least 4″ and drilled to accept a charge of blasting explosives.

blasting The process of loosening rock or hard-packed material with explosives.

blasting cap A metallic tube closed at one end, containing a charge of one or more detonating compounds, designed for and capable of detonation from the sparks or flame of a safety fuse inserted and crimped into the open end.

blasting mat A blanket of interwoven steel cable or interlocking steel rings placed over a blast to contain the resultant fragments.

BLCC A National Institute of Standards and Technology (NIST) software program that performs life-cycle analysis of buildings and components, useful for comparing alternate designs that have higher initial costs, but lower operating costs over the life of the building.

bleaching Lightening, whitening, or removing color, either by chemical means, such as chlorine or oxalic acid, or by exposure to certain kinds of light.

bleeder A small valve used to drain fluid from a pipe, radiator, or small tank.

bleeding **1.** The autogenous flow of mixing water within, or its emergence from, freshly placed concrete or mortar. Bleeding is caused by the settlement of the solid materials within the mass. Also called *water grain*. **2.** In painting, seepage of resin or an undercoating of paint through the finish coat. **3.** In lumber, the exuding of sap or resin.

bleed-through (strike-through) Discoloration in the face plies of wood veneer caused by seepage of cement through the veneer.

blended cement A hydraulic cement consisting of an intimate and uniform blend of (a) granulated blast-furnace slag and hydrated lime, (b) Portland cement and granulated blast-furnace slag, (c) Portland cement and pozzolan, or (d) Portland-blast-furnace slag, cement, and pozzolan. Blended cement is produced by intergrinding Portland cement clinker with the other materials or by a combination of intergrinding and blending.

blending valve A three-way valve that permits the mixing required to obtain a desired liquid temperature.

blind **1.** Any panel, shade, screen, or similar contrivance used to block light or inhibit viewing. **2.** An assembly of wood stiles, rail and wood slats, or louvers used in conjunction with doors and windows.



blind

blind casing The rough window frame or subcasing to which the trim is added.

blind door A door with a louver instead of glass.



blind door

blind drain **1.** A trench filled with pervious materials such as crushed stone through which water flows toward an outlet. **2.** A drain that is not connected to a sewage system.

blind header **1.** A brick or other masonry unit that, when laid, gives the appearance of a header while in reality is somewhat less than a whole unit. A blind header can also be a half-brick laid where only one end is visible. **2.** A header brick concealed within a wall and functioning to bond adjacent tiers of bricks.

blinding **1.** Applying a layer of weak concrete or other suitable material to reduce surface voids or to provide a clean, dry working surface. **2.** The clogging of the openings in a screen or sieve by the material being separated. **3.** Applying small chips of stone to a freshly tarred surface.

blind joint (bastard joint) **1.** A masonry joint, such as that of a *blind header*, that is entirely concealed. **2.** In a double Flemish masonry bond, a thin joint between the adjacent ends of two stretchers. This joint bisects a header in the course directly below it.

blind mortise (stopped mortise) A mortise in, but not through, a member.

blind mortise and tenon joint A joint between a blind mortise and a stub tenon.



blind mortise and tenon joint

blind nailing (concealed nailing, secret nailing) Nailing performed so that the nailhead cannot be seen on the face of the work.



blind nailing (concealed nailing, secret nailing)

blind pocket A pocket in the ceiling at a window head. A blind pocket is used to conceal an object when not in use, such as a venetian blind in the raised position.

blind rivet A small-headed pin with an expandable shank used for joining light gauge metal.



blind rivet

blind stop A rectangular molding nailed between the outside trim and the outside sash of a window frame, which serves as a stop for storm sashes or screens.

blister Usually an undesirable moisture and/or air-induced bubble or bulge that often indicates that some kind of delamination has taken place. Blisters can occur between finish plaster and the base coat, between paint or varnish and the surface to which it has been applied, between roofing membranes or between membrane and substrate, between reinforcing tape and the gypsum board to which it has been adhered, etc.



block

block **1.** A usually hollow concrete masonry unit or other building unit, such as *glass block*. **2.** A solid, often squared, piece of wood or other material. **3.** A piece of wood nailed between joists to stiffen a floor. **4.** Any small piece of wood secured to the interior angle joint to strengthen and stiffen it. **5.** A pulley and its enclosure. **6.** A solid piece of wood or other material used to fill spaces between formwork members.

block and tackle A mechanical device comprised of pulley blocks and ropes or cables, and used to hoist or move heavy objects or loads.



block and tackle

block beam In structural design, a flexural member composed of individual blocks joined together by prestressing.

block bridging (solid bridging, solid strutting) Short boards fixed between floor joists to stiffen the joists and distribute the load.

block-in-course A kind of masonry employed in heavy construction that consists of squared, hammer-dressed stones laid so that the joints are close and the course is not higher than 12″.

blocking **1.** Small pieces of wood used to secure, join, or reinforce members, or to fill spaces between members. **2.** Small wood blocks used for shimming. **3.** A method of bonding two parallel or intersecting walls built at different times by means of offsets whose vertical dimensions are not less than 8″ (20 centimeters). **4.** The sticking together of two painted surfaces when pressed together. **5.** An undesired adhesion between touching layers of material, such as occurs during storage.



blocking

blocking course In masonry, a finishing course, usually of stones, placed on top of a cornice.

blockwork Masonry of concrete block and mortar.



blockwork

bloom **1.** A thin, hazy film on old paint, usually caused by weathering. **2.** A similar film on glass, resulting from general atmospheric deposition of impurities, or caused more by smoke, vapor, etc. **3.** Efflorescence on brickwork. **4.** A hazy or other kind of discoloration that sometimes occurs on the surface of rubber products. **5.** The term given to steel that has been reduced from an ingot by being rolled in a blooming mill to a dimension of at least 6″ square; if further reduced, it becomes a *billet*.

blowback The difference between the pressure at which a safety valve opens and the pressure at which it closes automatically after the release of excess pressure has occurred.

blow count **1.** The number of times that an object must be struck to be driven into the soil to a desired or specified depth. **2.** In soil borings, the number of times a sample spoon must be struck to be driven 6″ or 12″. **3.** In pile driving operations, the number of times a pile must be struck to be driven 12″. **4.** The number of blows per unit distance of advance.


Ground Surface Elev. 94.6'
Blows per Foot
Datum = 0-0"
Loose Sand Some Gravel Some Bricks Little Wood Stones & Loam & Fill
3
5
20'-0"
Firm Fine Sand & Gravel
20
24
22
18
43'-0"
Firm Fine & Medium Sand & Gravel
16
20
45'-5"
Refusal (120 Blows, No Penetration) Water Level 43'-6"

blow count

blower A fan, especially one for heavy-duty use such as forcing air through ducts to an underground excavation.

blowhole (gas pocket) In concrete, a bug hole or small regular or irregular cavity, not exceeding 15 mm in diameter, resulting from entrapment of air bubbles in the surface of formed concrete during placement and compaction.

blown-in insulation Insulation that is pumped or injected into walls, roofs, and other areas.

blown joint (blow joint) A plumbing joint sealed with the use of a blowtorch.

blow-off **1.** A discharge outlet on a boiler to allow for expulsion of undesirable accumulations of sediment and/or for drainage. **2.** In a sewer system, an outlet pipe for expelling sediment or water or for draining a low sewer.

blows (boils) In dewatering, small springs that bubble up on the floor of an excavated pit caused by unrelieved aquifers. Blows can cause large soil movement if not attended to properly.

blowtorch A small, portable, gas-fired burner that generates a flame hot enough to melt soft metals. A blowtorch is used to melt lead in plumbing operations, heat soldering irons, and burn off paint.

blowtorch

blow up (blowout) Localized buckling or breaking up of rigid pavement as a result of excessive longitudinal pressure.

blueboard A type of wallboard used as a base for and finished with veneer plaster.

blueprint A negative image reproduction having white lines on a blue background and made either from an original or from a positive intermediate print. Today, the term almost always refers to *photocopied* prints, which are architectural or working drawings having blue or black lines on a white background.

bluestone A hard, fine-grained sandstone or siltstone of dark green to bluish-gray color that splits readily to form thin slabs. A type of flagstone, bluestone is commonly used for paving walkways.

blue top A grade stake driven into the ground that indicates the finished grade level.

board Lumber ranging from 4″ to 12″ (10 × 30 cm) wide and less than 2″ (5 cm) thick.

board and batten A type of siding in which the joints between vertically placed boards or plywood are covered by narrow strips of wood.



board and batten

board and brace A type of carpentry work consisting of boards grooved on both edges with thinner boards inserted between them and fitted into the grooves.

board foot The basic unit of measurement for lumber. One board foot is equal to a 1″ thick board, 12″ in width and 1′ in length. Thus, a 10″ long, 12″ wide, 1″ thick piece contains 10 board feet. When calculating board feet, nominal sizes are assumed.

board insulation (insulating board, insulation board) Lightweight thermal insulation, such as polystyrene, manufactured in rigid or semi-rigid form, whose thickness is very small relative to its other dimensions. Board insulation offers little structural strength and is usually applied under a finish material, although some types are surface-finished on one side.



board insulation (insulating board, insulation board)

board measure A system of measuring quantities of lumber, using one board foot as the basic unit of measurement.

board sheathing A sheathing made of boards, usually tightly spaced, although open spacing may be used in some roofs.

boardwalk A walkway made of boards or planks, often used as a promenade along a beach or shore.

boasted work A dressed stone surface with roughly parallel narrow chisel grooves of varying widths that do not extend across the entire face of the stone.

boatswain's chair A seat supported by slings and attached to a suspended rope. Designed to accommodate one worker in a sitting position.



boatswain's chair

bodily injury Any form of physical injury, sickness, or disease that is experienced by a person.

body **1.** The principal volume of a building, such as the nave of a church. **2.** The load-carrying part of a truck.

body coat In painting, an intermediate coat of paint applied after the priming coat but before the finishing coat.

boil **1.** A wet run of material at the bottom of an excavation. **2.** A swelling in the bottom of an excavation due to seepage.

boiled linseed oil Linseed oil to which manganese, lead, or cobalt salts have been added so that it will harden rapidly when applied in thin layers.

boiler A closed vessel in which a liquid is heated or vaporized, either by application of heat to the outside of the vessel, by circulation of heat through tubes within the vessel, or by circulating heat around liquid-filled tubes in the vessel.



boiler

boiler economizer The last pass of boiler tubes or a heat exchanger located in the flue pipe that extracts some of the heat from the flue gases before they are vented to the atmosphere.

boiler horsepower **1.** Boiler horsepower is equal to the evaporation of 34.5 lbs of water per hour from and at 212° F, 33, 475 Btu/hour. **2.** The largest rating obtained by dividing the square feet of a boiler's surface by 10.

boiler jacket The thermal insulation surrounding a boiler. A more aesthetically acceptable enclosure, often made of metal, usually covers the jacket.

boiler plate **1.** Medium-hard steel from which boilers are fabricated. The steel is rolled into plates whose thicknesses may vary from 0.25″ to 1.5″. **2.** Standard text used in documents such as contract agreements.

boiler rating The heating capacity of a boiler, expressed in Btus per hour. The boiler rating should not be confused with the horsepower rating.

boiler scale Disintegrated bits of steel plate from a boiler's interior lining, which flake and fall to the boiler floor and should be removed periodically.

boiler steel A medium-hard steel that is rolled to become boiler plate.

bollard **1.** A series of short posts set to prevent vehicular access or to protect property from damage by vehicular encroachment. A bollard is sometimes used to direct traffic. **2.** A post on a slip or wharf for securing mooring or docking lines.



bollard

bolster **1.** In concrete, an individual or continuous support used to hold reinforcing bars in position. Usually used in slab work. **2.** A short wood or steel member positioned horizontally on top of a column to support beams or girders. **3.** A mason's blocking chisel. **4.** A piece of wood, generally a nominal 4″ in cross section, placed between stickered packages of lumber or other wood products to provide space for the entry and exit of the forks of a lift truck.



bolster

bolt **1.** An externally threaded, cylindrical fastening device fabricated from a rod, pin, or wire, with a round, square, or hexagonal head that projects beyond the circumference of the shank to facilitate gripping and turning. A threaded nut fits onto the end of a bolt and is tightened by the application of torque. **2.** The protruding part of a lock that prevents a door from opening. **3.** Raw material used in the manufacture of shingles and shakes. A wedge-shaped split from a short length of log that is taken to a mill for manufacturing. **4.** Short logs to be sawn for lumber or peeled for veneer. **5.** Wood sections from which barrel staves are made. **6.** A large roll of cloth or textile. **7.** A single package containing two or more rolls of wallpaper.



bolt

bolted pressure switch A switch that uses movable blades and stationary contacts with arcing contacts to make and break switching action.

bolt sleeve A tube surrounding a bolt in a concrete wall to prevent the concrete from sticking to the bolt and acting as a spreader for the formwork.



bolt sleeve

bona fide bid A good faith bid that is essentially complete and complies with the bidding documents. Must be signed by a properly empowered party.

bond **1.** The adhesion and grip of concrete or mortar to reinforcement or to other surfaces against which it is placed, including friction due to shrinkage and longitudinal shear in the concrete engaged by the bar deformations. **2.** The adhesion of cement paste to aggregate. **3.** Adherence between plaster coat or between plaster and a substratum produced by adhesive or cohesive properties of plaster or supplemental materials. **4.** In masonry, the connection between stones, bricks, or other materials formed by laying them in an overlapping arrangement, one on top of another, to form a single wall mass. **5.** The arrangement of, or pattern formed by, the exposed faces of laid masonry units. **6.** The layer of glue in a plywood joint. **7.** A written document, given by a surety in the name of a principal to an obligee to guarantee a specific obligation.

bond beam A horizontally reinforced concrete or concrete masonry beam built to strengthen and tie a masonry wall together. A bond beam is often placed at the top of a masonry wall with continuous reinforcing around the entire perimeter.



bond beam

bond blister A blister that sometimes forms between the base material and the coating, particularly on metal-clad products.

bond breaker A material used to prevent adhesion between freshly placed concrete and the substrate.

bond coat **1.** That coat of plaster that is applied over masonry and is bonded to it. **2.** A primer coat of paint or sealer.

bond course In masonry, the course consisting of units that overlap more than one wythe of masonry.



bond course

bonded member A prestressed concrete member in which the tendons are bonded to the concrete either directly (pretensioned) or by grouting (posttensioned).

bonded posttensioning A process in posttensioned construction whereby the annular spaces around the tendons are grouted after stressing in such a way that the tendons become bonded to the concrete section.



bonded posttensioning

bonded roof A type of roofing guarantee offered by the manufacturer that may or may not be purchased by the owner, and that covers materials and/or workmanship for a stated length of time.

bonded tendon A prestressing tendon that is bonded to the concrete either directly or through grouting.



bonded tendon

bonder (header) A masonry unit that ties two or more wythes of a wall together by overlapping.

bond face That face of a joint to which a field-molded sealant is bonded.

bonding In electrical circuitry, the connecting or joining of metal parts to form an electrical conductive path. Prevents the accumulation of static electricity and assures the safe conduction of electrical current.

bonding agent **1.** A substance applied to a suitable substrate to create a bond between it and a succeeding layer, as between a subsurface and a terrazzo topping or subsequent application of plaster. **2.** A licensed professional who identifies the most appropriate bonding company from which a contractor should purchase construction bonds.

bonding capacity The maximum total contract value a bonding company will extend to a contractor in performance bonds. The total bonding capacity is the sum of all contracts being bonded.

bonding company A firm providing a surety bond for work to be performed by a contractor, payable to the owner in case of default of the contractor. The bond can be for work performance or for payment for materials and labor.

bonding jumper (bonding conductor) In a circuit, the connection between parts of a conductor to maintain the ampacity requirements of the circuit.

bond length (development length) The length of embedment of reinforcing steel in concrete required to develop the design strength.

bondstone In stone facing, a stone that extends into the backing to tie the facing wall with the backing wall. *See also* **bonder**.

bond strength **1.** Resistance to separation of mortar and concrete reinforcing steel and other materials with which it comes in contact. **2.** Collective expression of all forces, such as adhesion, friction due to shrinkage, and longitudinal shear in the concrete engaged by the bar deformations that resist separation.

bond stress **1.** The force of adhesion per unit area of contact between two bonded surfaces. **2.** Shear stress at the surface of a reinforcing bar, preventing relative movement between the bar and the surrounding concrete.

bonnet A wire mesh cover over the top of a chimney or vent.



bonnet

bonus provisions Provisions in the contract between the owner and the contractor for granting monetary rewards to the contractor for achieving some savings that benefit the owner. For example, a stipulated bonus may be offered for early completion of the work, or the achievement of some savings in construction cost.

book matching (herringbone matching) Consecutive flitches of veneer from the same log, laid side by side so that the pattern formed is almost symmetrical from the common center line. Book matching is used in decorative paneling and cabinetry.

book value The net amount at which an asset is carried on the books and reported in the financial statements: the asset's cost at acquisition, reduced by the amount of accumulated depreciation on the asset.

boom A long, straight member, hinged at one end, and used for lifting heavy objects by means of cables and/or hydraulics. Booms can be of lattice construction or heavy tubular material.



boom

boom crane A crane with a long slender boom, usually of lattice construction.

boom crane

boom hoist A lifting device with a vertical mast and an inclined boom commonly used to hoist materials in multistory building construction.

boom jack A short member on which sheaves are mounted to guide cables to a working boom on a crane or derrick.

boost-buck transformer A device that raises or lowers the voltage of a supply line.

booster Any device that increases the power, force, or pressure produced by a system.

booster fan An auxiliary fan that increases the air pressure in a system, such as an HVAC system, during certain peak requirement times.

boot **1.** A term used to describe sleeves or coverings in many construction trades, such as a boot for pile driving, a boot for passing a pipe through a roof, and a boot for cold-air return to a furnace casing. **2.** The money that compensates for differences in value in a 1031-exchange. Boot is taxable even though the exchange may be tax-free.



boot

bore **1.** The inside diameter of a pipe, valve, fitting, or other hollow tubular object. **2.** The circular hole left by boring.

bored latch A door latch manufactured to fit into a circular hole in a door.

bored lock A lock manufactured to fit into a circular hole in a door.

bored well A water well constructed by drilling a hole with an auger and then inserting a casing.

borescope A fiber-optic device that allows for nondestructive investigation of an area with restricted access, such as a housed mechanical assembly or a cavity inside a wall. Often used with a still or video camera.

boring (borehole) A hole drilled in the ground to obtain samples for subsoil investigation. Borings are important in determining the load-bearing capacity of the soil and the depth of the water table.

borrow (borrow fill material) In earth moving, fill acquired from an excavation source outside the required cut area.

borrowed light A glazed unit in an interior partition to allow light to enter from an adjoining room or passageway.

borrow pit An excavation site, other than a designated cut area, from which material is taken for use nearby.

boss **1.** A projecting block, usually ornamental, placed at the exposed intersection or termination of ribs or beams of a structure. **2.** The enlarged portion of a shaft. **3.** In masonry, a stone that is left protruding from the surface for carving in place at a later time. **4.** A projection left on a cast pipe fitting for alignment or for gripping with tools.

Boston hip (Boston ridge, shingle ridge finish) **1.** A method of finishing a ridge or hip on a flexible shingled roof in which a final row of shingles is bent over the ridge or hip with a lateral overlap. **2.** A method of finishing a ridge or hip on a rigid-shingled slate or a tile roof in which the last rows on either side overlap at the hip or ridge. Alternate courses overlap in opposite directions.

bottle brick A hollow brick shaped so that it can be mechanically connected to adjoining bricks. In each brick there is also a void available for inserting reinforcing steel, if required.



bottle brick

bottom arm A long strap secured to the bottom rail of a door to attach it to a floor closer or pivot hinge.

bottom bolt A vertically mounted bolt on the bottom of a door that slides into a socket in the floor.

bottom chord The lowest longitudinal member of a truss. It is usually horizontal, but may be at an incline depending on truss design.

bottom rail The lowest bottom member of a door. The bottom rail connects the stiles.

boundary survey A closed diagram (mathematically) depicting the complete outer boundary of a site. Shows dimensions, compass bearings, and angles. A licensed land surveyor's signed certification is required, and a *metes and bounds* or other written description may be included.

bow The longitudinal deflection of a piece of lumber, pipe, rod, or the like, usually measured at its center.



bottom rail

bow saw A hand tool with a thin saw blade held in place between the two ends of a bow-shaped piece of metal.

bowstring roof A roof supported by bowstring trusses and fabricated in the shape of a bow.

bowstring truss (bowstring beam, bowstring girder) A structural roof truss having a bow-shaped top cord and a straight or cambered bottom cord.



bowstring truss (bowstring beam, bowstring girder)

bow window **1.** A window that projects from a wall in the shape of an arc. **2.** A rounded bay window.

box casing In finished carpentry, the inner lining, as in a cabinet.

box column A built-up, hollow column, usually square in shape, used in porch construction.

box culvert A rectangular-shaped, reinforced concrete drainage structure either cast in place or precast in sections.

box drain A small rectangular-shaped drainage structure usually constructed of brick or concrete. It may be covered or have an open grate on top.



box culvert

boxed mullion A hollow mullion in a window frame built up from boards so as to appear solid; houses sash weights.

box frame A window frame containing hollow sections on either side in which the sash weights are suspended.

box gutter A rectangular-shaped wooden roof gutter recessed in the eaves to conceal them and to protect them from falling foliage.

boxing **1.** Enclosing or casing, as in window frame construction. **2.** In welding, continuing a principle fillet weld around a corner of the member. **3.** Pouring paint back and forth from one pail to another to ensure a uniform consistency.

box out To make a form that will create a void in a concrete wall or slab when the concrete is placed.

box scarf A joint in a rectangular-shaped roof gutter formed by beveling the ends of the two pieces to be joined.

box sill A common method of frame construction using a header nailed across the ends of floor joists where they rest on the sill.

box stair An interior staircase in which the edges of the treads and risers are not revealed but closed in with a closed stringer. A box stair typically has a partition on both sides.

box stoop An elevated platform at the entrance to a building with stairs running parallel to the building. The underside of the platform and stairs is enclosed.

box strike A fastening on a door frame (a strike) with an enclosed recess to receive a lock bolt.

box wrench A mechanic's hand tool with a closed socket, usually at each end, that fits over the head of a bolt or a nut.



box wrench

brace (bracing) **1.** A diagonal tie that interconnects scaffold members. **2.** A temporary support for aligning vertical concrete formwork. **3.** A horizontal or inclined member used to hold sheeting in place. **4.** A hand tool with a handle, crank, and chuck used for turning a bit or auger.



brace (bracing)

braced excavation Excavation in which the perimeter is supported by sheeting.

brace rod A round steel member used as a tension brace, especially to transfer wind or seismic loads.

brace table (brace scale) **1.** The markings on a carpenter's square indicating the length of the hypotenuse for right triangles with various length legs. **2.** A brace table used by carpenters to determine the length to cut braces.

bracket An attachment projecting from a wall or column used to support a weight or a structural member. Brackets are frequently used under a cornice, a bay window, or a canopy.

bracket pile A steel H pile driven next to an existing foundation. A steel bracket is welded to the pile and extends under and supports the foundation.

bracket saw A handsaw with a narrow blade attached to the open ends of a three-sided rectangular holder. Used for cutting curved shapes.

bracket scaffold (bracket staging) Scaffolding supported by brackets that are temporarily attached to the side of a building or column. Bolts or inserts are usually left in the previous construction to attach the brackets. This method saves the expense of shoring from the ground up.

brad A slender, smooth, wire nail with a small deep head. Used for finish carpentry work.

brad awl A carpenter's tool that looks like an ice pick and is used to make holes for brads and wood screws.



brad awl

brake **1.** A device for slowing, stopping, and holding an object. **2.** A machine used to bend sheet metal.

brake drum A rotating cylinder with a machined surface (either internal or external) on which a brake band or shoe presses in order to slow, stop, or hold an object.

brake horsepower The horsepower output of an engine or other mechanical device, as measured at the flywheel or belt by applying a mechanical brake and measuring the work per unit time.

branch In plumbing, an inlet or outlet from the main pipeline, usually at an angle to the main pipeline. The pipe may be a water supply, drain, vent stack, or any other pipe used in a mechanical piping system.

branch circuit A portion of the electric system that extends wiring beyond the fuse or other device that is protecting that circuit.

branch duct In HVAC, a smaller duct that branches from the main duct. At each branch duct, the cross-sectional area of the main duct is reduced.



branch duct

branch sewer A sewer that receives sewage from a relatively small area and is connected to a main sewer or manhole.

branch vent **1.** A vent connecting one or more individual vents to a vent stack or stack vent. **2.** A vent pipe to which are connected two or more pipes that vent plumbing fixtures.

brand name or equal A product description that identifies one or more commercial products by brand name and sets forth those characteristics of the named product that are essential to the owner's needs.

brander To nail furring strips to girders, joists, or walls in preparation for installing plaster or another finish material.

brass **1.** A copper alloy with zinc as the principal alloying element. **2.** Slang for plumbing fittings and faucets, regardless of their actual material of composition.

braze To join two pieces of metal by soldering them together with a nonferrous metal such as brass.

breach of contract The failure, without legal cause, to perform some contractually described obligation in accordance with the terms of the contract.

breakdown A term used to define the separation of a project or an estimate into parts.

breakdown structure A hierarchical structure by which project elements are broken down, or decomposed.*

breakdown voltage Voltage that causes the failure of existing insulation, permitting the flow of electric current.

breaker panel Refers to the main electrical box and its circuit breakers, which distribute electricity to each branch circuit.

breakeven chart A graphic representation of the relation between total income and total costs for various levels of production and sales indicating areas of profit and loss.*

breakeven point **1.** In business operations, the rate of operations output, or sales at which income is sufficient to equal operating costs or operating cost plus additional obligations that may be specified. **2.** The operating condition, such as output, at which two alternatives are equal in economy. **3.** The percentage of capacity operation of a manufacturing plant at which income will just cover expenses.*

breaking load The smallest load, determined by test, that would cause the failure of a structural system.

break joints (staggered joints) The arrangement of modular structural units, such as masonry or plywood sheathing, so that the vertical joints of adjacent units do not line up.



break joints (staggered joints)

break lines Lines used in drafting to omit part of an object so that the representation will fit on a drawing.

breast **1.** The part of a wall that extends from the window stool to the floor level. **2.** A projecting part of a wall, such as at a chimney.

breast board A system of movable sheeting used to retain the face of an excavation, especially in tunnel work.

breastsummer **1.** A large supporting horizontal timber that spans a wide opening in an external wall, usually the breast of the wall.

breather A mechanism that allows air to move in and out of a container to maintain even atmospheric pressure.

breech fitting A Y-shaped fitting in ductwork or pipework.

breeching The exhaust duct or pipe that leads from a furnace or boiler to the stack or chimney.



breeching

breeze brick A brick made from pan breeze and Portland cement, often laid into a brick wall because of its good nail-holding properties.

breezeway A covered passageway open at both ends, which connects two buildings or two portions of a building.



breezeway

brick A solid masonry unit of clay or shale, formed into a rectangular prism while plastic, and then burned or fired in a kiln.

brick anchor Corrugated fasteners designed to secure a brick veneer to a structural concrete wall.



brick anchor

brick and brick A method of laying brick so that units touch each other with only enough mortar to fill surface irregularities.

brick-and-half wall A brick wall that has the thickness of one header plus one stretcher.

brick cement A waterproofed compound used in masonry and stucco work.

brick closure Short pieces of brick used in corners or jambs to maintain the pattern.

brick gauge A standard height for brick courses when laid, such as four courses in a height of 12″.

brick grade A durability rating given to brick. SW, MW, and NW ratings refer to a brick's ability to withstand severe weathering, moderate weathering, and negligible weathering, respectively.

brick hammer A hand tool used by masons for breaking and dressing brick. One end of the head is square and flat and the other end is shaped like a chisel.



brick hammer

bricklayer's square scaffold A scaffold composed of framed wood squares that support a platform. A bricklayer's square scaffold is limited to light- and medium-duty.

brick molding The wood molding covering between the brick masonry and a door or window frame.

brick set A chisel-like tool used with a brick hammer to make exact cuts in brick.

brick trimmer A brick arch supporting a fireplace hearth or shielding a wood trimming joist from flames in front of a fireplace.

brick trowel A hand trowel with a pointed handle used to pick up mortar from a mortar tub and place and spread it in the joints.

brick type A rating given to facing brick based on its tolerance, chippage, and distortion. FBS, FBX, and FBA are designations for solid brick; HBS, HBX, and HBB are for hollow brick.

brick veneer A facing of brick laid against a structural wall but not bonded to the wall, and which bears no load other than its own weight.

brick whistle **1.** A weep hole in a brick wall. **2.** A small hole in a mortar joint at the base of a wall for draining any moisture that penetrates the wall.



brick veneer

bridge **1.** A structure built to span an obstruction or depression and capable of carrying pedestrians and/or vehicles. **2.** In an electric blasting cap, the wire that heats with current and ignites the charge. **3.** The temporary structure built over a sidewalk or roadway adjacent to a building to protect pedestrians and vehicles from falling objects.

bridge crane A crane often used in manufacturing or assembling heavy objects. A bridge crane requires a bridge spanning two overhead rails. A hoisting device moves laterally along the bridge while the bridge moves longitudinally along the rails.

bridge deck The load-carrying floor of a bridge that transmits the load to the beams.

bridge financing The short-term financing needed to bridge a shortfall between a loan presently committed or in place and the total financing required to complete a project.

bridged floor A floor supported by common joists.

bridge thrust The horizontal thrust from vertical loads on an arched bridge.



bridged floor

bridging **1.** A method of lateral bracing between joists for stiffness, stability, and load distribution. **2.** A delivery method in which an owner selects a designer to develop partial design documents and then selects a design-builder to complete the design and construct the project.



bridging

brine In a refrigeration system, a liquid used as a heat transfer agent that remains a liquid and has a flashpoint above 150°. The liquid is usually a salt solution.

Brinell hardness A measure of the hardness of a metal determined in the laboratory by measuring the indentation made by a steel ball in the surface of the metal.

British thermal unit (Btu) A standard measurement of the heat energy required to raise the temperature of one pound of water one degree Fahrenheit.

brittle A characteristic of a material that makes it fracture easily without bending or deforming.

broach **1.** To free stone block from a quarry ledge by cutting out the webbing between holes drilled close together in a row. **2.** To cut wide parallel grooves in a diagonal pattern across a stone surface using the point of a chisel, finishing it for architectural use. **3.** Any pointed structure, such as a steeple or spire, that is built for ornamental purposes. **4.** A spire that rises directly from a tower, often without an intervening parapet. **5.** A half pyramid constructed above the corners of a square tower, serving as an architectural transition from the slat of the tower to an octagonal spire.

broaching **1.** A method of quarrying stone in which close holes are drilled around the breakline. A chisel, called a *broach*, is used to break the remaining material. The stone is then removed with wedges. **2.** A method of making shaped holes in metal by removing small pieces in succession with a reaming tool.

broadloom A seamless carpet woven on a wide loom, usually 6′ to 18′ (1.8 to 5.5 meters) wide.

broadscope A term describing the content of a section of the specifications, as established by the Construction Specifications Institute. A broadscope section covers a wide variety of related materials and workmanship requirements. (*Narrowscope* specifications denote a section describing a single material; *mediumscope* denotes a section dealing with a family of materials.)

broad tool A wide steel chisel used in the finish dressing of stone.

broken joints Vertical joints of masonry arranged in a staggered structure with no unit placed directly on top of another. Provides a more solid bond and increases structural strength.



broken joints

broken joint tile A roofing tile that overlaps only the tile directly below it.



broken joint tile

bronze **1.** An alloy composed of copper and tin. **2.** A bronze-colored alloy that uses a sizable measure of copper to alter the properties of its chief elements, as in aluminum bronze or magnesium bronze.

bronzing **1.** The application of metal bronze provider to an object or substance. **2.** The powdery decomposition of a paint film caused by exposure to the elements and natural wear.



broom-finish concrete

broom-finish concrete Concrete that has been brushed with a broom when fresh in order to improve its traction or to create a distinctive texture.

brown coat (floating coat) **1.** In two-coat wet-wall construction, the first rough coat of plaster applied as a base coat over lath or masonry. **2.** In three-coat work, the second coat of plaster applied over a scratch coat to serve as a base for the finish coat.



brown coat (floating coat)

brownfield sites Abandoned or underused industrial sites that often require remediation of hazardous waste or other pollutant contamination prior to reuse.

brown millerite An oxide of calcium, aluminum, and iron commonly formed in Portland cement and high alumina cement mixtures.

brown-out **1.** To apply a base coat of plaster. **2.** The setting process of base-coat plaster, which darkens to a brown hue as it dries. **3.** A partial loss of electrical power that dims lights. A brownout is less severe than a blackout.

brown rot A fungus that attacks the cellulose of wood, so called for the residual brown powder it leaves behind on the destroyed matter.

brush (brushed) finish A finish created by applying a rotating wire brush to a surface.

brush rake A large apparatus that is attached to the front of a tractor to clear land of brush and debris.



brush rake

Brussels carpet **1.** A carpet of worsted yarn in multiple colors, attached to a backing of tough linen thread in a pattern of uncut loops. **2.** A less costly substitute for actual Brussels carpet, made in a single color of yarn.

bubble **1.** Either the air bubble in a leveling tube or the tube itself. **2.** A large void in gypsum board caused by air entrapment during manufacturing.

bubble diagram A diagram that shows the functional relationships in a building or firm.

bubble tube A tube containing an air bubble, used to level a tool or an instrument.

bubbling Trapped bubbles of air or vapors that erupt on a painted surface during application or drying.

buck **1.** The wood or metal subframe of a door, installed in a wall to accommodate the finished frame. **2.** One of a pair of four-legged supporting devices used to hold wood as it is being sawed.



buck

bucket A scoop-shaped attachment for an excavating machine that digs and transports loose earthen materials. Often outfitted with opening and closing mechanisms to facilitate unloading.

bucket trap A mechanical steam trap that operates on buoyancy and is designed with an inverted or upright cup that prevents the passage of steam through the system it protects.

buck frame (core frame, subframe) A wood frame built into the wall studs of a partition to accommodate a door lining.

buckle **1.** The distortion of a structural member such as a beam or girder under load. This condition is brought on by lack of uniform texture or by irregular distribution of weight, moisture, or temperature. **2.** A flaw or distortion on the surface of a sheet of material, particularly asphalt roofing. **3.** A thin tree branch bent in the shape of a "U" to fasten thatch onto roofs.

buckling load In a compression member or compression portion of a member, the load at which bending progresses without an increase in the load.

buck opening A rough door opening.

budget A rough estimate of the value of a portion of, or total cost of, a construction project.

budgeted cost of work performed (BCWP) Measure of the amount of money budgeted to complete the actual work performed as of the data date. Represents the value of work performed, rather than the cost of the actual work performed. In current earned value management system usage, it is referred to as "earned value" or EV.*

budgeted cost of work scheduled (BCWS) Measure of the amount of money budgeted to complete the scheduled work as of the data date. In current earned value management system usage, it is referred to as "planned value" or PV.*

buff **1.** To clean and polish a surface to a high luster. **2.** To grind and polish a floor of terrazzo or other exposed aggregate concrete.

buffer **1.** Blasted rock left at a face to improve fragmentation and reduce scatter during a subsequent blast. **2.** A loose metal mat used to control scattering of blast rock. *See also* **spring buffer**

buff standard brick A buff-colored brick that may be either 2¼″ × 3¾″ × 7¾″ or 2″ × 4″ × 8″, nominal.

buggy (concrete cart) A two- or four-wheeled cart, with or without a motor, used to transport small amounts of concrete from hoppers or mixers to forms.

bug holes Small cavities, usually not exceeding ~5$^{1}/_{8}$″ (15 mm) in diameter, at the surface of formed concrete. Bug holes are caused by air bubbles trapped during placing and compacting of wet concrete.



buggy (concrete cart)

builder's jack A temporary bracket, attached to a windowsill, that projects outward and supports scaffolding.

builder's risk insurance A special form of property insurance to cover work under construction.

builder's staging A heavy scaffold made from square timbers, usually used where heavy materials are handled.

building area The sum of the horizontal projected area of all buildings on a site. Terraces and uncovered porches are excluded, unless the stipulations of a mortgage lender or governmental program require their inclusion.

Building Automation System A network of integrated computer components that automatically control a wide range of building operations such as HVAC, security/access control, lighting, energy management, maintenance management, and fire safety control.



building block

building block Any rectangular masonry unit (except brick) used in building construction. Typical materials are burnt clay, concrete, glass, gypsum, etc.



building brick (common brick)

building board Any board of building material, usually with a facing, which can be used as a finished surface on walls or ceilings.

building brick (common brick) Brick that has not been treated for color or texture. Used as an all-purpose building material.

building codes The minimum legal requirements established or adopted by a government such as a municipality. Building codes are established by ordinance, and govern the design and construction of buildings.

building drain That part of the lowest piping of a drainage system that receives the discharge from soil, waste, and other drainage pipes inside the walls of the building and conveys it to the building sewer.

building ecology The environment inside a building, such as air quality, lighting, and acoustics, and its effect on a building's occupants and the overall environment.

building envelope The elements of a building that enclose conditioned areas and through which thermal energy may be transferred to or from the outside environment.

Building Information Modeling (BIM) We use BIM as a verb or an adjective phrase to describe tools, processes and technologies that are facilitated by digital, machine—readable documentation about a building, its performance, its planning, its construction and later its operation. Therefore, BIM describes an activity, not an object. To describe the result of the modeling activity, we use the term *building information model*, or more simply *building model* in full.

Building Model (or Building Object Model) This consists of a digital database of a particular building that contains information about its objects. This may include its geometry (generally defined by parametric rules), its performance, its planning, its construction and later its operation. A Revit® model and a Digital Project® model of a building are examples of building models. *Building model* can be considered the next-generation replacement for *construction drawings* or *architectural drawings*. Downstream in the process, the term *fabrication model* is already in common use as a replacement for *shop drawings*.

Building model repository A building model repository is a database system whose schema is based on a building object based format. It is different from existing project data management (PDM) systems and web-based project management systems in that the PDM systems are file-based, and carry CAD and analysis package project files. Building model repositories are object-based, allowing query, transfer, updating and management of individual project objects from a potentially heterogeneous set of applications. *See also* **BIM Server**.

building inspector An official employed by a municipal building department to review plans and inspect construction to determine if they conform to the requirements of applicable codes and ordinances, and to inspect occupied buildings for violations of the same codes and ordinances.

building integrated photovoltaics (BIPV) Substituting a conventional part of building construction with photovoltaic material. Shingles, standing seam metal roofing, spandrel glass, and overhead skylight glass are some examples.

building line **1.** The line, established by law, beyond which a building shall not extend, except as specifically provided by law. Exceptions may be made for terraces or uncovered porches. **2.** The outermost dimension of a building, generally used for building placement in relation to zoning or plot restrictions.

building main The water supply pipe (including fittings) that extends from the water main or other source of supply to the first distribution branch of a building.

building material Any material used in construction, such as sand, brick, lumber, or steel.

building occupancy A classification of the use or intended use of a structure, such as business or residential, for determining hazards, requirements, and restrictions.

building official (building inspector) An appointed government official who is responsible for enforcing building codes. The building official may approve the issuance of a building permit, review the contract documents, inspect the construction, and approve issuance of a certificate of occupancy.

building paper A heavy, asphalt-impregnated paper used as a lining and/or vapor barrier between sheathing and an outside wall covering, or as a lining between rough and finish flooring.



building paper

building permit A written authorization required by ordinance before construction on a specific project can begin. A building permit allows construction to proceed in accordance with construction documents approved by the building official.

building services The utilities, including electricity, gas, steam, telephone, and water, supplied to and used within a building.

building thermal envelope Parts of a building that enclose conditioned spaces, including exterior walls, roof, and floors.

building trades The skilled and semiskilled crafts employed in building construction, such as carpentry, masonry, or plumbing.

built-up **1.** Fabricated of two or more pieces or sheets that are laminated. **2.** Assembled by fastening a number of pieces or parts to each other.

built-up air casing A field-fabricated enclosure for an air-handling system, with base, curbs, and drains.

built-up beam **1.** A metal beam made of beam shapes, plates, and/or angles that are welded or bolted together. **2.** A concrete beam made of precast units connected through shear connectors. **3.** A timber beam made of smaller pieces that are fastened together.

built-up rib A rib made of laminations of various size timbers.

built-up roofing (composition roofing, felt-and-gravel roofing, gravel roofing) A continuous roof covering made up of various plies or sheets of saturated or coated felts cemented together with asphalt. The felt sheets are topped with a cap sheet or a flood coat of asphalt or pitch, which may have a surfacing of applied gravel or slag.



built-up roofing (composition roofing, felt-and-gravel roofing, gravel roofing)

built-up section In metal building systems, a structural member made from individual plates welded together.

bulb angle A hot-rolled angle with a formed bulb on the end of one leg.

bulb bar A rolled steel bar with a formed bulb on one edge.

bulb tee A rolled steel tee with a formed bulb on the edge of the web.



bulb tee

bulkhead **1.** A horizontal or inclined door providing outside access to a cellar or shaft. **2.** A partition in concrete forms to separate placings. **3.** A structure on the roof of a building to provide headroom over a stairwell or other opening. **4.** A low structure on a roof covering a shaft or protruding service equipment. **5.** A retaining structure that protects a dredged area from earth movement.



bulkhead

bulking (moisture expansion) An increase in the volume of a quantity of granular material when moist, over the volume of the same quantity when dry.

bulk liquid A pumpable material that has a moisture content greater than 70%.

bulk material Material bought in lots. These items can be purchased from a standard catalog description and are bought in quantity for distribution as required. Examples are pipe (nonspooled), conduit, fittings, and wire.*

bulk solid A material with a moisture content less than 30%.

bulldog grip A U-bolt threaded at each end.

bulldozer **1.** A tractor with a large, blunt blade attached to its front end by hydraulic-controlled arms. A bulldozer is used to push, shape, or move earth or rock short distances. **2.** A machine used to bend reinforcing bars into U shapes.



bulldozer

bullet catch A type of door latch consisting of a spring-loaded steel ball. The loaded ball holds the door closed but rolls free when the door is pulled.

bullet-resisting glass (bulletproof glass) A laminated assembly of glass, usually at least four sheets, alternated with transparent resin sheets, all bonded under heat and pressure. Bullet-resisting glass is also made of laminations of special plastics.

bull float A board of wood, aluminum, or magnesium mounted on a pole and used to spread and smooth freshly placed, horizontal concrete surfaces.



bull float

bull header (bull head) A brick with one rounded corner used to form a corner at a doorjamb or laid on edge to form a windowsill.

bullnose (bull's nose) **1.** A rounded outside corner or edge. **2.** A metal bead used in forming a rounded corner on plaster walls.

bullnose plane A small, handheld carpenter's plane with the blade set forward.

bullnose step (bull stretcher) A step, usually the bottom one in a flight, with a semicircular end that projects beyond the railing.

bullnose stretcher **1.** A masonry stretcher with one of the corners rounded. **2.** Any stretcher that is laid on edge, as at a windowsill.



bullnose stretcher

bullnose trim A structural member or piece of trim that has a rounded edge, such as a stair tread, windowsill, or door sill.

bull pin A tapered steel pin used to align holes in steel members so bolts can be inserted.

bull-point A pointed steel hand drill that is struck with a hammer to chip off small pieces of rock or other masonry.

bulwark A low wall used as a defensive shield.

bundle Refers to a package of shingles. Typically, 3 bundles make up a square, and there are 27 shingles per bundle.

bundle of lath A quantity of lath for plastering, usually 50 pieces of wood lath, 5/16″ × 1½″ × 48″ (0.79 × 3.8 × 122 cm) or 6 sheets of gypsum lath, 16″ × 48″ (41 by 122 cm).

bundler bars An assembly of up to four parallel reinforcing bars connected to one another and enclosed in stirrups or ties. Used as a unit in reinforced concrete, particularly in columns.

bunker **1.** A compartmentalized storage container for aggregate or ore. **2.** Space in a refrigerator for ice storage and for the cooling element. **3.** A protective shelter usually constructed of reinforced concrete and located partially or fully below ground. **4.** A metal shield in a crushing or screening operation used to direct raw material to the feed belt.

buoyant foundation A reinforced concrete foundation designed and located such that its weight and superimposed permanent load is approximately equal to the weight of displaced soil and/or ground water.

burden **1.** The loose material that overlays bedrock. **2.** The depth of material to be moved or loosened in a blast. **3.** The distance from a blast face to a line of blast holes. **4.** The cost of maintaining an office with staff other than operating personnel. Includes also federal, state, and local taxes; fringe benefits; and other union contract obligations. In manufacturing, burden sometimes denotes overhead.*



burner

burner That part of a boiler or furnace in which combustion takes place.

burning **1.** Flame-cutting metal plates to a desired shape. **2.** A method of repairing lead roofs by replacing damaged sections.

burning-brand test A standard test to determine the resistance of a roof covering to exposure from flying brands.

burnt sienna Sienna that has been calcined to obtain a rich brown pigment. Used for coloring paint and stain.

burnt umber Umber that has been calcined to obtain a red to reddish-brown pigment. Used for coloring paint and stain.

burr **1.** An uneven or jagged edge left on metal by certain cutting tools. **2.** Partially fused brick. **3.** A batch of bricks that were accidentally fused together. **4.** A curly figure in lumber that was cut from an enlarged trunk of certain trees, such as walnut.

bus (bus bar) An electric conductor, often a metal bar, that serves as a common connection for two or more circuits. A bus usually carries a large current.

bus duct (busway) A prefabricated unit containing one or more protected busses.



bus duct (busway)

bush hammer A hand or power hammer that has a serrated face with many pyramidal points. A bush hammer is used to dress concrete or stone.



bush hammer

bush-hammered concrete Concrete with an exposed aggregate finish that has been obtained by removing the surface cement using a percussive hammer with a serrated face.

bush-hammer finish A stone or concrete finish obtained through use of a percussive hammer with a serrated face. Used for decorative purposes or to provide a rough surface for better traction or adhesion.

bushing **1.** A threaded or smooth (for soldered tubing) pipe or tube fitting used to connect pipes or tubes of different diameters. **2.** A metal sleeve screwed or fitted into an opening to protect and/or support a shaft, rod, or cable passing through the opening. Usually the inside surface of the bushing is machined to close tolerance to reduce friction and abrasion. **3.** An insulating structure for a conductor, with provision for an insulated mounting.

business agent An official of a trade union who represents the union in negotiations and disputes and checks jobs for compliance with union regulations and union contracts.

butt **1.** A short length of roofing material. **2.** The thick end of a shingle.



butt

butt casement hinge A type of toe-plate hinge intended for use on casement sashes.

butted frame A door frame with a depth equal to or less than the thickness of the wall in which the frame is mounted.

butt end The thicker end of a handle, tapered pole, pile, or other rod-shaped object.

butt-end treatment The process of protecting that part of a timber or post that will be exposed to soil and/or water by treating it with a preservative chemical.

butter (buttering) **1.** To apply mortar to a masonry unit with a trowel. **2.** To spread roofing cement smoothly with a trowel. **3.** To apply putty or compound sealant to a flat surface of a member before setting the member, such as buttering a stop before installing it.

butterfly hinge A decorative hinge.

butterfly spring A formed piece of spring metal set over the pin of a hinge to serve as a door closer.

butterfly valve A valve that contains a disk that rotates 90° within the valve body. Has excellent throttling characteristics.



butterfly valve

butterfly wall tie A masonry wall tie made from heavy wire in the shape of a figure eight.

buttering trowel A small trowel used to apply mortar to a brick before laying the brick.

butt fusion A method of joining thermoplastic resin pipe or sheets in which the ends to be joined are heated to the molten state, pressed together, and held until the material sets.

butt hinge The common form of hinge consisting of two plates, each with one meshing knuckle edge, connected by means of a removable or fixed pin through the knuckles.



butt hinge

butt joint **1.** A square joint between two members at right angles to each other. The contact surface of the outstanding member is cut square and fits flush to the surface of the other member. **2.** A joint in which the ends of two members butt each other so that only tensile or compressive loads are transferred.

buttonhead The head of a bolt, rivet, or screw that is shaped like a segment of a sphere and has a flat bearing surface.



buttonhead

button punching Crimping the interlocking lap of metal ducting panels with a dull punching tool. Button punching has been largely replaced by spot welding overlapping edges.

buttress **1.** An exterior pier of masonry construction, often sloped, which is used to strengthen or support a wall or absorb lateral thrusts from roof vaults. **2.** An A-shaped formwork of timber or steel used to strengthen or support a wall.

butt splice A butt joint secured by fastening a short piece of wood or steel to each side of the butted members.

butt weld joint **1.** A joint made by welding two butted pieces or sheets together. **2.** A welded pipe joint made with the ends of the two pipes butting each other.



butt weld joint

butyl rubber (synthetic rubber) sealant A type of one-component sealant that may also contain fillers, such as calcium carbonate and talc powder, as well as polybutene and other additives that promote adhesion.

butyl stearate A colorless, oily liquid used for dampproofing concrete.

buy-in A bidder's attempt to win a contract by submitting a price that will result in a loss, with the hope of making the contract profitable through change orders or follow-on contracts.

BX Flexible metal conduit armored with spirals of galvanized steel and containing multiple insulated electric wires.

bypass **1.** A pipe or duct used to divert flow around an element. **2.** A pipe used to divert flow around another pipe or piping system.

C

Abbreviations

c candle, cathode, channel, conductivity, cycle
C carbon, Celsius, centigrade, hundred
CAA Clean Air Act
Cab cabinet
CAB cabinet, cement-asbestos board
CAD computer-aided design
CADD computer-aided design and drafting
CAFM computer-aided facility management
Cair air tool laborer
cal calorie
calc calculated
cap capacity
carp carpenter
CAT catalog (catalogue)
CATV community antenna television
CATW catwalk
CB catch basin, center beaded, circuit breaker
CB1S center beam one side
CB2S center beam two sides
CBMA Certified Ballast Manufacturers Association
CBR California bearing ratio
C&Btr grade C and better (used in lumber industry)
cc cubic centimeter
C/C center to center
CCA chromate copper arsenate
CCF hundred cubic feet
CCTV closed-circuit television
CCW counterclockwise
cd candela
CD grade of plywood face and back
cd/sf candela per square foot
CDX plywood, grade C and D, exterior glue
Cefi cement finisher
ceil ceiling
Cem cement
cem fin cement finish
cem m cement mortar
cent central
cer ceramic
CERCLA Comprehensive Environmental Response, Compensation, and Liability Act
CF cubic feet, centrifugal force, cooling fan, cost and freight, hundred feet
CFCs chlorofluorocarbons
CFL compact fluorescent lamp
cfm, CFM cubic feet per minute
CFR Code of Federal Regulations
CFS cubic feet per second
cg center of gravity
CG ceiling grille, center of gravity, coarse gram, corner guard
CG2E center groove two edges
chfr chamfer
chkd checked
CHIM chimney

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

CHRIS Chemical Hazard Response Information System
CHU centigrade heat unit
CHW chilled water
CI cast iron, certificate of insurance
CIF cost, insurance, and freight
CIFE cost, insurance, freight, and exchange
CII Construction Industry Institute
cin bl cinder block
CIP cast-iron pipe, cast in place
CIR circle, circuit, circular
Circ circuit
CIRC circumference
cl closet
CL center line, carload lot
Clab common laborer
CLF hundred linear feet, current-limiting fuse
clg ceiling
clk caulk
CLP cross-linked polyethylene
clr clear
cm centimeter
CM center matched, construction management
CMMS computerized maintenance management software
CMP corrugated metal pipe
CMPA corrupted metal pipe arch
CMU concrete masonry unit
CND conduit
c-o cleanout
Co company
CO certificate of occupancy, change order, cleanout, cutout
CO_2 carbon dioxide
coef coefficient
col column
com common
COMB, Comb combination
comp compartment, compensate, component, composition
COMPF composition floor
COMPR, compr composition roof, compress, compressor
conc, Conc concrete
conc b concrete block
conc clg concrete ceiling
conc fl concrete floor
cond conductivity
const constant, construction
constr construction
Cont continuous, continued
CONTR contractor
conv convector
cop coping, copper
corb corbeled
corn cornice
corr corrugated
Cos cosine
cot cotangent
Cov cover
CP candlepower, cesspool
CPA control point adjustment
CPFF cost plus fixed fee
cplg coupling
CPM critical path method, cycles per minute
CPr hundred pair
CPU central processing unit
CPVC chlorinated polyvinyl chloride
CRC cold-rolled channel
Creos creosote
CRI color rendering index
crib cribbing
CRN cost of reproduction/replacement new
CRP controlled rate of penetration
cr pl chromium plate
Crpt carpet and linoleum layer
CRSI Concrete Reinforcing Steel Institute
CRT cathode ray tube
c/s cycles per second
CS cast stone, carbon steel, commercial standard, caulking seam
CSA Canadian Standards Association (CSA International)
CSC cosecant
CSF hundred square feet
csg casing
CSI Construction Specifications Institute
CSK countersink
ct coat (coats)
CT current transformer
CTB cement-treated base
c to c center to center
ctr center, counter
CTS copper tube size
cu cubic
cu ft cubic feet
cu in cubic inch

cur current

cu yd cubic yard (27 cubic feet)

CV center vee

CV1S center vee one side

CV2S center vee two sides

cw clockwise, continuous wave

CW cool white, cold water

CW pt cold water point

cwt hundred weight

CWX cool white deluxe

CY cycle, cubic yard (27 cubic feet)

CY/Hr cubic yards per hour

cyl, cyl cylinder

CYL L cylinder lock

cyp cypress

1/C single conductor

2/C two conductors

Definitions

cabana A small shelter of open, tent, or wood-frame construction placed near swimming pools or the shoreline.



cabin

cabin **1.** A small, simple hut or house. **2.** A rustic shelter often made of logs.

cabinet **1.** A small room or private apartment, especially for study or consultations. **2.** A suite of rooms for exhibiting articles and curiosities. **3.** A case, box, or piece of furniture with sets of drawers or shelves and doors, used primarily for storage. **4.** An enclosure with doors for housing electrical devices and wiring connections.



cabinet

cabinet filler The wood piece that closes the space between cabinets and adjacent walls or the ceiling.

cabinet finish A varnished, oiled, or polished wood surface finish, as distinguished from a painted surface finish.

cabinet head A decorative molding along the top of a door frame.

cabinet heater A metal housing enclosing a heating element, with openings to facilitate air flow. The heater frequently contains a fan for controlling the air flow.

cabinet lock A spring bolt or magnetic latch.

cabinet scraper A flat steel blade used for smoothing wood or removing a finish, such as paint or varnish, from a surface.

cabinet work Wood joinery used in the construction of built-in cabinets and shelves.

cable **1.** A rope or wire comprised of many smaller fibers or strands wound or twisted together. **2.** A group of electric conductors insulated from each other but contained in a common protective cover.



cable

cable assembly A cable and its accompanying connectors to be used for a specific purpose.

cable ceiling heat A radiant heating system, installed in a ceiling, that sends current through encased conductors to produce heat.

cable duct (cable conduit) A rigid, metal, protective enclosure through which electrical conductors are run. For underground installations, concrete or plastic pipes are usually used.

cable length A standard surveying measurement equal to 720′.

cable pulling compound A lubricant used to facilitate the pulling of wires through a cable duct or conduit.

cable roof A system comprised of a roof deck and covering that are supported by cables.

cable sheath The protective cover that surrounds a cable.

cable support box An electrical box that is mounted on a wall and provides support for the weight of cables within a vertically installed conduit.

cable-supported construction A structure that is supported by a system of cables. This system is used for long-span roofs and for suspension bridges.

cable tray An open, metal framework used to support electrical conductors. Similar to cable duct except that the cable tray has a lattice-type construction and an open top.



cable tray

cable vault An underground structure utilized in the pulling and joining of underground electric cables.

cadmium plating A coating of cadmium metal applied over a base metal, usually for corrosion protection.

cage **1.** The box or enclosed platform of an elevator or lift. **2.** An enclosure for electrical lights or signals. **3.** Any rigid open box or enclosure.

caisson **1.** A drilled, cylindrical foundation shaft used to transfer a load through soft strata to firm strata or bedrock. The shaft is filled with either reinforced or unreinforced concrete. **2.** A watertight box or chamber used for construction work below water level.



caisson

caisson drill A piece of boring equipment used to excavate a shaft (usually vertical) in the earth for construction of a building footing.

caisson pile A cast-in-place pile formed by driving a hollow tube into the ground and filling it with concrete.



caisson pile

calcimine (kalsomine) A low-cost wash, white or colored, used on ceilings, interior plaster, or other masonry-type surfaces.

calcine The process of heating a substance to a point just below its melting temperature in order to remove chemically combined water.

calcined gypsum Gypsum that has been partially dehydrated. In this form it is used as a base material to which mineral aggregate, fiber, or other material may be added to produce the desired plaster.

calcite The main raw material used in the manufacture of Portland cement. Calcite is a crystallized form of calcium carbonate and is the principal component in limestone, chalk, and marble.

calcium chloride A saltwater solution added to concrete and mortar during mixing. Acts as a drying agent and decreases setting time.

calcium silicate brick A concrete product made primarily from sand and lime that is hardened by autoclave curing.

calcium silicate insulation Hydrated calcium silicate that has been molded into rigid shapes and forms. The material is commonly used for pipe insulation where service temperatures reach 1,200°F. Particularly well suited for pipe insulation because it is not appreciably affected by moisture.

calculate To do mathematical work; to seek a numerical value.

calculated live load The useful load-supporting capability above the weight of the structural members, usually specified in the applicable building code.

calculate schedule A modeling process that defines all critical activities and individual activity scheduling data. The process applied in most scheduling software calculates the start and finish dates of activities in two passes. The first pass calculates early start and finish dates from the earliest start date forward. The second pass calculates the late start and finish activities from the latest finish date backwards. The difference between the pairs of start and finish dates for each task is the float or slack time for the task.*

calculation The product or result of mathematical work.

calendar Defined work periods and holidays that determine when project activities may be scheduled. Multiple calendars may be used for different activities, which allows for more accurate modeling of the project work plat (e.g., 5-day workweek calendar vs. 7-day workweek.*

calendar start date The date assigned to the first unit of the defined calendar; the first day of the schedule.*

calf's-tongue molding (calves-tongue molding) A molding with repeating semi-oval shapes, half pointing in the same direction or, when surrounding an arch, pointing to a common center.

caliber The internal diameter of a pipe. In construction, most pipe is specified by outside diameter, with a further designation for wall thickness.

caliche A term used to describe gravel or sand loosely cemented together by calcium carbonate or other salts.

California bearing ratio A ratio used to determine the bearing capacity of a foundation. It is a ratio of the force per unit area per minute required to penetrate a soil mass, to the force required for a similar penetration of a standard crushed rock material.

California brass ring A sampler used to collect soil samples during well installation. Samples are tested for volatile organic compounds.

caliper (calliper) An instrument with two hinged legs used to determine the thickness or diameter of objects.



caliper (calliper)

calked rivet A rivet that has not been properly driven, but has been tightened to fit its hole by having the edge of its head driven under with a cold chisel.

calorie The amount of heat required, at a pressure of one atmosphere, to raise the temperature of one gram of water 1°C.

calorific value The amount of heat liberated by the oxidation or combustion of the unit weight of a solid material, or the unit volume of a gas or liquid.

cam **1.** An eccentric wheel mounted on a rotating shaft and used to produce reciprocal or variable motion in an engaged or contacted part. **2.** In a lock, the rotating piece attached to the cylinder that actuates the locking mechanism.

camber A slightly convex curvature built into a beam or truss to compensate for deflection under a load. Camber is also built into structural components, roadways, or bridges to facilitate run off of water.

camber arch A flat arch with a very small upward curve of the undersurface. The upper surface may or may not be curved.

camber beam A beam constructed with a slight upward curve in the center.

camber diagram A construction drawing that shows the desired design camber along the beam, truss, or structural component.

camber piece The temporary wood support or template used to lay a slightly curved brick arch.

cambium The thin layer of tissue that lies between a tree's bark and its wood.

came A flexible, cast-lead rod used in stained glass windows to hold together panes or pieces of glass.

camelback truss A truss whose upper chord is comprised of a series of straight segments so that the assembly looks like the hump of a camel's back.

camelhair mop A high-quality, soft-haired brush used for varnishing, gilding, or painting.

cameo window A fixed oval window, often highly decorative.

cam handle (locking handle) On a hinged window, the handle that rotates against its keeper plate, thus pulling the window tight and locking it.

campaniform A term used to describe a structure in the shape of a bell.

Canadian Standards Association A nongovernmental body established in Canada for the purpose of developing uniform standards on products, processes, and procedures.

canal (canalis) **1.** Any watercourse or channel. **2.** A channel or groove fluting in carved ornamentation.

candela A unit of luminous intensity; formerly called *candle*.

candlepower The luminous intensity of a light source expressed in *candelas*.

canopy **1.** An overhanging shelter or shade covering. **2.** An ornamental rooflike structure over a pulpit.


canopy

cant **1.** To slope, tilt, or angle from the vertical or horizontal. **2.** A log that has been slabbed on one or more sides.

cantilever **1.** A structural member supported at one end only. **2.** A beam, girder, or supporting member that projects beyond its support at one end.

cantilever footing **1.** A footing with a tie beam connected to another footing to counterbalance an asymmetrical load. **2.** In retaining wall construction, a wide, reinforced footing with reinforcing steel extending into the retaining wall to resist the overturning moment.


cantilever retaining wall

cantilever retaining wall A retaining wall that has a wide footing to resist its overturning moment.

cantilever truss A truss that is anchored at one end and overhangs a support at the other end.

cantilever wall A wall that resists its overturning moment with a cantilever footing.

canting strip A horizontal ledge near the bottom of an exterior wall sloped to conduct water away from the face of a building or its foundation.


canting strip

cant strip (chamfer strip) A three-sided piece of wood, one angle of which is square, used under the roofing on a flat roof where the horizontal surface abuts a vertical wall or parapet. The sloped transition facilitates roofing and waterproofing. *See also* **chamfer**.

canvas A closely woven cloth, usually made of cotton, used for tarpaulins, awnings, sun covers, and temporary canopies.

canvassing A process used to repair uneven plaster. Performed by adhering canvas strips or other fabric-like material to the surface. Also provides a stable base for paint or wallpaper.

canvas wall A plaster wall with a canvas covering, that may be painted or wallpapered.

cap **1.** The top piece, often overhanging, of any vertical architectural feature or wall. A cap may be external, as on an outside wall or doorway; or it may be internal, as on the top of a column, pilaster, molding, or trim. **2.** A layered system of cover—whether natural soils, rock, synthetics, pavement, and/or polymeric liners—that controls hydrogeologic processes. **3.** Decorative molded cornice or projection covering the lintel of a window.

capacitor A device used to introduce capacitance into an electric circuit. The device consists of conducting plates insulated from each other by a layer of dielectric material.

Cape Cod house (cape) A simple frame house with a shingled, steeply pitched roof, central chimney, and one or one-and-a-half floors. The style originated in colonial Cape Cod, Massachusetts, and has evolved over hundreds of years into several popular variations.


Cape Cod house (cape)

cap flashing A section of flashing attached to a vertical surface in order to prevent water from entering behind the base flashing.

capillary action In subsurface soil conditions, the rising of water above the horizontal plane of the water table.

capillary flow The flow of moisture through any form, shape, or porous solid by means of capillary action.

capillary tube **1.** A small-diameter tube used in refrigeration to restrict the flow of refrigerant from the condenser to the evaporator. **2.** The small-diameter tubing used to connect temperature- and pressure-sensing bulbs to a control mechanism.

capillary water Water that, by virtue of capillary action, is either above the surrounding water level or has penetrated where a body of water would not normally go.


capital

capital The top member of a column, pier, pillar, post, or pilaster; usually decorative.

capital, fixed The total original value of physical facilities which are not carried as a current expenses on the books of account and for which depreciation is allowed by the federal government. It includes plant equipment, building, furniture and fixtures, and transportation equipment used directly in the production of a product or service. It includes all costs incident to getting the property in place and in operating condition, including legal costs, purchased patents, and paid-up licenses. Land, which is not depreciable, is often included. Characteristically, it cannot be converted readily into cash.*

capitalization The total value of a corporation's equity.

capitalize To increase the total value of a corporation's equity through expenditures that increase the evaluation of property, plant, and equipment.

capital project A project in which the cost of the end result or product is capitalized (i.e., cost will be depreciated). The product is usually a physical asset such as property, real estate or infrastructure, but may include other assets that are depreciable.*

capital, working The funds in addition to fixed capital and land investment that a company must contribute the project (excluding start-up expense) to get the project started and meet subsequent obligations as they come due. Working capital includes inventories, cash, and accounts receivable minus accounts payable. Characteristically, these funds can be converted readily into cash. Working capital is normally assumed recovered at the end of the project.*

cap molding (cap trim) The molding or trim above a door or window casing.

capping brick Brick that is used to cap off the top of a wall.

capping piece (cap piece, cap plate) The timber used to cover the top of a series of uprights or other vertical members.

cap plate The plate on top of a column or post that supports the load. *See also* **capping piece**.



cap plate

cap sheet The top ply of mineral-coated felt sheet used on a built-up roof.

capstone A stone segment in a coping.

carbon absorption A water treatment system most often used for residential applications that removes the odor and unpleasant taste sometimes found in municipal water supplies. Carbon filters are not certified for removing VOCs, lead, coliform, or asbestos.

carbon-arc cutting A metal cutting process in which arc heat melts a path through metal. The arc is established between an electrode, which forms one terminal of an electric circuit, and the workpiece, which forms the other terminal.

carbon-arc welding An arc-welding process in which the heat for fusion is generated by an electric arc between a carbon electrode and the workpiece.

carbonation The process of burning or converting a substance through chemical reaction into a carbonate. For example, the reaction between carbon dioxide and the calcium compounds in cement paste or mortar to produce calcium carbonate.

carbon steel Steel that owes its distinctive properties (primarily its strength) to the carbon it contains, as opposed to the characteristics imparted by other alloying elements.

carcass roofing The roofing framework before the decking, membrane, shingles, etc., have been applied.



carcass roofing

carcinogen A cancer-causing substance.

cardinal change A series of changes in the work that are so extensive and significant as to change the entire character of the work required by the contract, thereby constituting a breach of contract.

care, custody, and control A feature of construction liability insurance policies that excludes damage to property in the care, custody, or control of the insured.

carillon A set of fixed bells sounded by striking with hammers operated either mechanically or from a keyboard. By extension, a bell tower or campanile.



carillon

carpenter Gothic Gothic-style architecture and ornamentation constructed of wood.

carpenter's brace (bit brace) A crank-shaped tool with a chuck on one end to hold a drill bit or auger. A hole is bored by rotating the crank.

carpenter's bracket scaffold A scaffold that supports a platform using wood or metal brackets.

carpenter's level A hand tool used by carpenters to determine a horizontal or vertical plane or line. The level is a wood or metal bar about 2′ long with four spirit levels set into it.

carpenter's square (framing square) A flat, metal, L-shaped tool that constitutes an accurate right angle and is engraved with divisions and markings useful to a carpenter laying out and erecting framing.



carpenter's square (framing square)

carpet backing The base material on the back of a carpet. The backing is usually made of jute, cotton, or carpet rayon, and may have a coating of latex.

carpet bedding Beds of low-growing plants, which may be used in ornamental design or as an erosion-preventing ground cover.

carpet cushion (carpet underlayment) A padding made of hair, felt, jute, foam, or sponge rubber that is placed on the floor before a carpet is laid. The cushion helps to provide resilience and extends the life of a carpet.

carpet density The number of pile rows per inch, for the length of the carpet.

carpet float A tool used by plasterers to give texture to a sand finish. The tool consists of a wood float covered with a piece of carpeting. The density of the carpet determines the type of finish.

carpet strip **1.** A flat strip of molding used to fasten the edge of carpeting. **2.** A piece of wood or metal, approximately the same thickness as the carpet, installed at the edge of a carpet, as at a threshold.



car platform

car platform The structural floor of an elevator car that supports the load.

carport

carport A roofed shelter for automobiles, usually attached along the side of a dwelling, with one or more sides open.

carriage The sloping beam that is installed between the stringers to support the steps of a wooden staircase.



carriage bolt

carriage bolt A threaded bolt with a round, smooth head. The bolt is prevented from rotating in its hole by a square neck directly under the head.

carriage clamp A clamp used in carpentry and cabinetry.

carrier angle A metal angle attached to stair carriers or stringers to support the tread or riser.

carrier bar A flat metal bar used to support stair treads or risers in a manner similar to carrier angles.



cartridge fuse

carrying channel A three-sided metal molding used in the construction of a suspended ceiling.

cartridge fuse A low-voltage fuse consisting of a current-responsive element inside a cylindrical tube with a terminal on each end.

cartridge heater An electric heater in the shape of a cylindrical cartridge, with the heating coils at one end and a fan at the other.

carvel joint A flush, longitudinal joint between boards or planks with no tongues, grooves, or laps.

cascade refrigerating system Two or more refrigerating systems connected in series. The cooling coil of one system is used to cool the condenser of the next system. This type of system is an efficient way to produce and maintain ultra-low temperatures.

case **1.** A box, sheath, or covering. **2.** The process of covering one material with another; to encase. **3.** A product or food display counter, such as a refrigerated case for displaying ice cream or frozen produce. **4.** A lock housing.



cased opening (trimmed opening)

case bay The area of a building floor or roof between two beams or girders.

cased beam An exposed interior beam encased in finished millwork.

cased opening (trimmed opening) An interior doorway or opening with all the trim and molding installed, but without a door or closure.

cased post An exposed interior post or column encased in finished millwork.

case-hardened **1.** Term used to describe a steel or iron alloy with a hard surface developed by a special heat-treatment process. **2.** Timber whose outer fibers have dried too rapidly, thus causing checking and cracking.

case-hardened glass Glass that has been heated and quenched, thus giving it a hardness and strength several times greater than it originally possessed.

casein paint A paint using the white amorphous phosphoprotein emulsion from milk as a base adhesive and binder.



casement window

casement **1.** A window sash that opens on hinges that are fixed on either side. **2.** A ventilation panel that opens on vertical hinges like a door. **3.** A casing.

casement door **1.** A door consisting of a wooden frame around glass panels, which make up a major portion of the area of the door. **2.** A French door.

casement stay The brace or bar used to hold a casement window open in any of several positions.

casement window A window assembly that has at least one casement or vertically hinged sash.



casework

case mold A frame support, usually made of plaster, that holds smaller plaster pieces in position in a mold.

casework A term for assembled cabinetry or millwork.

cash allowance A sum included in the contract for construction that covers required items not specifically described. Any differences in cost between the total charges for these items and the cash allowance amount are handled through change orders.

cash flow The amount of cash a company or construction project generates, or fails to generate, over a specific period of time.

cash flow management The planning of project expenditures relative to income or authorized funding in such as way as to minimize the carrying cost of the financing of the project to keep within the constraints of a time-phased budget. This may be achieved by accelerating or delaying some activities, but at the risk of ineffective performance, late completion and consequent increased cost.*

casing **1.** The exposed millwork enclosure of cased beams, posts, pipes, etc. **2.** The exposed trim molding or lining around doors and windows. **3.** The pipe liner of a hole in the ground, such as that used for a well, caisson, or pile.

casing bead A metal molding or wood strip that acts as a stop, an edge, or a separation between different materials.

casing-bead door frame A metal door frame used in plaster walls that includes a strip or molding along its outer edges as a ground or guide for the plaster.

casing knife A knife used to trim wallpaper around casing, molding, or other edges.



casing nail

casing nail **1.** A nail with a very small head. **2.** A finishing nail.

casting Any object that has been cast in a mold. The object may be made of iron, steel, plaster, concrete, plastic, or any other castable material.

casting plaster A plaster mixture with additives to provide properties desirable for casting work.

cast-in-place concrete (in situ concrete) Concrete poured into forms at its final location.

cast iron An iron alloy cast in sand molds and machined to make many building products such as ornamentation, pipe and pipe fittings, and fencing.

cast molding A molding or molding component that has been cast, removed from the mold, and then fastened in place. The molding may be made of plaster, concrete, plastic, or some similar material.

catalyst **1.** A substance that accelerates or retards chemical reactions. **2.** The hardener that accelerates the curing of adhesives, such as synthetic resins.

catch The fitting that mates with a latch or cam to lock a door, gate, or window.

catch basin (catch pit) A receptacle or reservoir that receives surface water runoff or drainage. Typically made of precast concrete, brick, or concrete masonry units, with a cast-iron frame and grate on top.

catch drain A long drain installed across or along a slope to collect and convey surface water.



catch basin (catch pit)

category One of the divisions of the breakdown in construction specifications, smaller than a trade.

catenary arch An arch constructed on the curve of an inverted catenary.

cathead The top piece of a hoist tower to which pulleys or sheaves are attached.

Catherine-wheel window **1.** A round window with mullions like wheel spokes. **2.** A rose window.



Catherine-wheel window

cathodic protection A form of protection against electrolytic corrosion of fuel tanks and water pipes submerged in water or embedded in earth. Protection is obtained by providing a sacrificial anode that will corrode in lieu of the structural component, or by introducing a counteracting current into the water or soil. This type of protection is also used for aluminum swimming pools, cast-iron water mains, and metal storage tanks.

catslide **1.** The term used in the southern United States for a *saltbox* home. **2.** The long pitched roof at the rear of a saltbox, which often sweeps down to the ground.

catwalk A small, permanent walkway, usually elevated, to provide access to a work area or service/maintenance access to lighting units, stage draperies, etc.

caulk (calk) **1.** To fill a joint, crack, or opening with a sealer material. **2.** The filling of joints in bell-and-spigot pipe with lead and oakum.

caulking gun A hand or power tool that extrudes caulking material through a nozzle.



caulking gun

caustic An alkaline material that has a corrosive or irritating effect on living tissue.

caustic lime A material, white when pure, that is obtained by calcining limestone, shells, or other forms of calcium carbonate. Caustic lime is also called *quicklime* or *burnt lime* and is used in mortars and cements.

cavity The empty space between studs and joists.

cavity fill Material placed in the hollow of a wall, ceiling, or floor to provide insulation or sound deadening.

cavity flashing The continuous waterproof barrier that covers the longitudinal opening in a cavity wall.



cavity fill

cavity wall (hollow masonry wall, hollow wall) An exterior masonry wall in which the inner and outer wythes are separated by an air space, but tied together with wires or metal stays.

C/B ratio saturation coefficient The ratio of the weight of water absorbed by a masonry brick or block immersed in cold water to the weight absorbed when immersed in boiling water. This is a measure of the resistance of the masonry to spalling due to freezing and thawing.



cavity wall (hollow masonry wall, hollow wall)

C-clamp A C-shaped clamp frequently used in carpentry and joinery. Force is applied by rotating a threaded shaft through one jaw of the C to force the work against the other jaw.

cedar A softwood with reddish heartwood and white sapwood noted for decay resistance and used for shingles, shakes, posts, and gutters.



C-clamp

ceiling **1.** The overhead inside lining or finish of a room or area. **2.** Any overhanging surface viewed from below.

ceiling cornice The molding installed at the intersection of the wall and ceiling planes.

ceiling diffuser Any air diffuser, located in a ceiling, through which warm or cold air is blown into an enclosure. The diffuser is designed to distribute the conditioned air over a given area.

ceiling height The distance between a room's finished ceiling and floor.

ceiling outlet In a ceiling, a metal or plastic junction box that supports a light fixture and encloses the connecting fixture wires.

ceiling plenum In air-conditioning systems, the air space between a hung ceiling and the underside of the floor or roof above. Acts as a return to the air-handling unit.

ceiling sound transmission The transmission of sound between adjacent rooms through the ceiling plenum above.

ceiling strap Wood strips nailed to the bottom of roof rafters or floor joists for the support or suspension of a ceiling.



ceiling strap

ceiling strut A temporary brace suspended from an overhead structure or framing and used to hold door frames in place while the adjacent walls are being constructed.

ceiling suspension system A gridwork of metal rails and hangers erected for the support of a suspended ceiling and ceiling-mounted items, e.g., air diffusers, lights, fire detectors, etc.


ceiling suspension system

cellar A room or set of rooms below or predominantly below grade, usually under a building.

cellular concrete (aerated concrete) Concrete that has had gas-forming chemicals mixed with the basic ingredients, so that the final set material is lighter than ordinary concrete, due to its porosity. This type of concrete is often used as insulation when it is placed over a roof slab.


cellar

cellular-core door A hollow-core door filled with a lightweight, honeycomb-shaped, expanded material to provide rigidity and support.

cellular floor A flooring system that incorporates prefabricated raceways for telecommunications and electrical wiring.

cellular framing A method of framing in which the walls are composed of cells, with the cross walls transmitting the bearing loads to the foundation.

cellular plastic Plastic molding or extrusion with a pattern of cells that give it rigidity and reduce its weight.

cellular raceway A channel in a modular floor or wall that may be used as a raceway for electrical conductors.

celluloid A thermoplastic material often used in thin sheets because of its good molding properties.

cellulose A naturally occurring substance made up of glucose units. Constitutes the main ingredient in wood, hemp, and cotton, and is used in many construction products.

cellulose fiber tile A sound-absorbing acoustical tile made from cellulose fiber.

Celsius scale A thermometer in which the interval between the freezing point and boiling point of water is divided into one hundred parts or degrees. Named after Aners Celsius, a Swedish astronomer. Also called a *centigrade thermometer*.

Celtic cross A cross formed from a long vertical column, a shorter horizontal bar, and a circle about their intersection.

cement Any chemical binder that makes bodies adhere to it or to each other, such as glue, paste, or Portland cement.


Celtic cross

cement-aggregate ratio The ratio of cement to aggregate in a mixture, as determined by weight or volume.

cementation The firming and hardening of a cementitious material.

cement board (cement backer board) A water-resistant wallboard made of concrete faced with fiberglass on both sides. Commonly used as an underlayment in wet areas like bathtub surrounds and as a backer for ceramic tile. Brand names include Durock® and Wonder Board®.

cement block An inaccurate term, usually in reference to concrete block or to a hollow or solid-cast masonry unit.

cement-coated nail A nail coated with cement to increase its friction and holding power.

cement content (cement factor) The quantity of cement per unit volume of concrete or mortar, expressed in pounds or bags per cubic yard.

cement gravel Gravel bound together in nature by clay or some other natural binding agent.

cement grout **1.** A thin, watery mortar or plaster that is pumped or forced into joints, cracks, and spaces as an adhesive sealer. **2.** A mixture that is pumped into the soil around a foundation to firm it up and provide better load-bearing characteristics.

cement gun A tool used for spraying or injecting cement grout or mortar material.


cement gun

cementitious Capable of setting like a cement.

cement mixer **1.** A concrete mixer. **2.** A container used to mix concrete ingredients by means of paddles or a rotary motion. The container may be manually or power operated.

cement mortar A plastic building material made by mixing lime, cement, sand, and water. Cement mortar is used to bind masonry blocks together or to plaster over masonry.


cement mixer

cement paint (concrete paint) Paint containing white Portland cement and usually applied over masonry surfaces as a waterproofing.

cement paste A mixture of cement and water.

cement plaster Plaster containing Portland cement as the binder and commonly used on exterior surfaces or in damp areas.

cement, Portland A fine gray powder made from three main ingredients: silica, alumina and lime. May also include slag or flue dust. Used as a base material for mortar and concrete.

cement rock (cement stone) A natural, impure limestone that contains the ingredients for the manufacture of Portland cement.

cement stucco **1.** A mixture of Portland cement, sand, and a small percentage of lime. Used to form a hard covering for textured exterior walls. **2.** A fine plaster used for interior decorations and moldings.


cement stucco

cement temper The addition of Portland cement to lime plaster to improve its strength and durability.

center **1.** A point that is exactly halfway between two other points or surfaces. **2.** A point equidistant from all points on the circumference of a circle. **3.** The internal core of a built-up construction.

center bit A cutter used for boring holes in wood. The cutting end consists of a sharp, threaded screw for guidance and for pulling the tool deeper into the work piece. The bit also has a scorer for marking the outline of the hole and a lip for cutting away the wood inside the hole. The other end of the bit is usually a tapered rectangular block that is clamped in the chuck of a brace.

center-hung door (center-pivoted door) A door that is supported by, and swings about, pivot pins. The pins are inserted into or attached to the door on the center line of its thickness.

center-hung sash A window sash hung so that it rotates horizontally about hinge pins at its center. To open, the top part of the window swings into the room and the bottom part projects outside the building.

centering **1.** The temporary support for a masonry arch while the arch is being built. **2.** The temporary forms for all supported concrete work.

center line A line of alternating long and short segments that indicates the center of a particular object. Frequently labeled with the letter C superimposed over the letter L.

center of gravity (center of mass) The location of a point in a body or shape about which all the parts of the body balance each other.

center pivot **1.** The pins of a window sash that are centrally located in the frame so that the window rotates horizontally about its center line. **2.** The pivot pins of a door that support the door on the center line of its thickness.

center punch A tool for making starter indentations in metal where a hole is to be drilled. The punch has a sharp conical point on one end and is hit by a hammer on the other end.

center rail The horizontal portion or member that separates the upper and lower sections of a recessed panel door.

center stringer The structural member of a stair system that supports the treads and risers at the midpoint of the treads. center-to-center (on center) The distance from the center line of one beam, part, or component of a structure to the corresponding center line of the next similar unit (for example, center-to-center of rafters or joists).

centimeter A metric unit of length equal to one one-hundredth of a meter. One inch equals 2.54 cm.

central-mixed concrete Concrete that is mixed in a stationary mixer and then transported to the site, as opposed to *transit-mixed concrete*.

central system A system that utilizes a single source and distribution system for an area. Examples are central heating and/or air-conditioning systems, central power systems, and central water systems.

centrifugal chiller A gas compressor used for chilling in which the compression is obtained by centrifugal force.

centrifugal compressor An air or gas compressor in which the compression is obtained by centrifugal force.

centrifugal force The force away from the center of a rapidly spinning impeller.



centrifugal pump

centrifugal pump A pump that draws fluid into the center of a rapidly spinning impeller and uses the force of the spin (centrifugal force) to impart pressure and velocity to the fluid as it leaves the periphery.

ceramic Items made of clay or similar materials that are baked in a kiln to a permanent hardness. Ceramic products include pottery, tile, and stoneware.

ceramic glaze A material that is applied over a clay product and then baked to produce a hard, vitreous, glassy surface. The glaze may be transparent or colored.

certificate A written document appropriately signed by responsible parties testifying to a matter of fact in accordance with a requirement of the contract documents.

certificate of insurance A document prepared by an insurance company or its agent that states the period of time for which the policy is in effect, along with the types and amounts of coverage for the insured.

certificate of occupancy A written document issued by the governing authority in accordance with the provisions of the building permit. The certificate of occupancy indicates that, in the opinion of the building official, the project has been completed in accordance with the building code. This document gives the owner permission from the authorities to occupy and use the premises for the intended purpose.

certificate of payment A statement issued by a design professional notifying the owner of the amount due to a contractor for work completed and/or the delivery or storage of building materials.

certified construction specifier A construction professional who, by experience and examination by the Construction Specifications Institute, has been certified as proficient in the knowledge and art of preparing technical specifications for the construction process.

certified forest product A product created from materials obtained from forests that have met specific environmental guidelines, and that are certified for use in green construction.

certified wood Wood from well-managed forests that replenish, rather than deplete, old growth timber.

chain **1.** A unit of length used by land surveyors (*Gunter's Chain*): 7.92″ = 1 link; 100 links = 66′ = 4 rods = 1 chain; 80 chains = 1 mile. **2.** An engineer's chain is equal to 100′. **3.** A series of rings or links of metal connected to each other to form useful lengths.

chain

chain door fastener A chain that can be secured by a slide bolt between a door stile and a doorjamb to allow the door to be opened slightly while remaining securely fastened.

chain fall An assembly of chain with blocks or pulleys for hoisting or pulling a heavy load.

chaining pin A metal pin used for marking measurements on the ground.

chain intermittent fillet weld An interrupted fillet weld on both sides of a joint. The weld segments are opposite one another.

chain link fence

chain link fence A fence made of steel wire fabric supported by metal posts.

chain molding A molding carved to simulate the appearance of a chain.

chain-pipe wrench (chain tongs) A wrench for turning or restraining pipe. The wrench consists of a lever handle with a serrated jaw. The jaw is held in contact with the pipe by a roller chain that wraps around the pipe.

chain riveting A type of riveting in which the rivets are placed in parallel adjacent rows. Chain riveting is not as strong as the staggered riveting pattern, which has more tear material between rivets.

chain saw A gas- or electric-powered saw having cutting teeth running around a bar of flat steel. Used for cross-cutting logs, etc.

chain timber Large beams built horizontally into a masonry wall to provide support and a tie-in during construction.

chain trencher A machine that uses a chain belt to excavate a trench.

chair **1.** A frame built into a wall to provide support for a sink, lavatory, urinal, or toilet. Also called a *carrier*. **2.** In concrete construction, a small metal or plastic support for reinforcing steel. The support is used to maintain proper positioning during concrete placement.

chair rail A horizontal piece of wood attached to walls to prevent damage to plaster or paneling from the backs of chairs.

chalk A soft limestone, white, gray, or buff-colored, composed of the remains of small marine organisms. In construction, chalk is commonly dyed blue and used with a chalk line or snap line for marking lines.

chalk line **1.** A light cord that has been surface-coated with chalk (usually blue) and is used for marking. **2.** The line left by a chalked string.

chamfer The beveled edge formed at the right-angle corner of a construction member.


chamfer

chamfer bit A tool bit for beveling the upper edge of a hole in wood so that a flat-head wood screw can be driven flush with the wood surface.

chamfer plane A carpenter's plane designed for cutting chamfers.

chancel arch An arch employed in some church designs to indicate the separation of the church body (*nave*) from the chancel or sanctuary.

chandelier A branched light fixture that is often ornate, and usually suspended from a ceiling.

change In construction, a deviation in the design or scope of the work as defined in the plans and specifications that are the basis for the original contract.

change, constructive An act or failure to act by the owner or the engineer that is not a directed change, but which has the effect of requiring the contractor to accomplish work different from that required by the existing contract documents.*

change documentation/log Records of changes proposed, accepted, and rejected.*

change in scope A change in the defined deliverables or resources used to provide them.*

change in sequence A change in the order of work initially specified or planned by the contractor. If this change is ordered by the owner and results in additional cost to the contractor, the contractor may be entitled to recovery under the changes clause.*

change management The formal process through which changes to the project plan are identified, assessed, reviewed, approved, and introduced.*

change order Written authorization provided to a contractor approving a change from the original plans, specifications, or other contract documents, as well as a change in the cost. With the proper signatures, a change order is considered a legal document.

changes in the work Changes to the original design, specifications, or scope of work as requested by the owner. All changes in the work should be documented on change orders.

channel **1.** A structural steel member shaped like a "U." **2.** In glazing, a U-shaped member used to hold a pane or panel. **3.** A watercourse, usually manmade. **4.** The suspension system for a suspended ceiling. **5.** A path for the transmission and reception of electromagnetic signals between two or more points.


channel

channel block A hollow concrete masonry block with a groove or furrow in it to provide a continuous recess for reinforcing steel and grout.


channel block

channel cutter A hand tool used to cut light-gauge metal framing.

channel glazing A window glazing system in which glass panels are set in a U-shaped channel using removable beads or glazing stops.

channeling Decorative fluting or grooving, as in the grooves in a vertical column.

channel iron (channel bar) A U-shaped, rolled, structural steel member, the web of which is always deeper than the width of the flanges. The web depth is the size of the channel.

channel runner A primary horizontal support in a suspended ceiling system.

charcoal filter **1.** A filter containing pulverized charcoal for removing odors, smoke, and vapors from the air. **2.** A filter for purifying and cleaning water.

charette **1.** The push or effort to complete an architectural problem within a specified time. **2.** A meeting held early in the design phase of a project during which the design team, contractors, end users, community stakeholders, and technical experts are brought together to develop goals, strategies, and ideas for maximizing the environmental performance of the project.

charge **1.** A quantity of explosives set in place. **2.** A load of refrigerant in a refrigeration or air-conditioning system.

charging door The door of a furnace or incinerator through which loads or charges are inserted.



charging door

chase A continuous enclosure in a structure that acts as a housing for pipe, wiring conduits, ducts, etc. A chase is usually located in or adjacent to a column, which provides some physical protection.

chattel Any item of property, movable or immovable, except real estate or a freehold.

chattel mortgage A mortgage or security interest in personal property as collateral for a loan.

cheapener An additive in paint that is used to impart desirable characteristics to or extend coverage of the paint. Cheapener does not necessarily make the paint cheaper in cost.

check **1.** A flapper or valve that permits fluid to flow in one direction only. **2.** An attachment that regulates movement, such as a door check. **3.** A small split in wood that runs parallel to the grain. Caused by shrinking during drying.



check

check lock A small, supplementary lock designed to control the bolt or action of a larger lock.

check rail The horizontal meeting rail of a double-hung window.

check stop A molding strip or bead used to restrain a sliding unit such as a window sash.

check strip A bead or molding used for parting.

check throat The groove cut longitudinally along the underside of window and door sills to prevent rainwater from running back to the building wall.

check valve (back-pressure valve, clack valve, reflux valve) A valve designed to limit the flow of fluid to one direction only.

checkered plate A metal plate with a waffle-like pattern of squared projections cast or rolled into its surface.



checkered plate

cheek In general, the side of any feature, such as the side of a dormer.

cheek boards **1.** The vertical stops or bulkheads placed at the ends of a concrete wall form. **2.** Trim applied to the side of a dormer.



cheek

cheek cut (side cut) The oblique cut made in a rafter or jack rafter to permit a tight fit against a hip or valley rafter or to square the lower end of a jack rafter.



cheek cut (side cut)

chemical bond A bond between similar materials caused by the interlocking of their crystalline structures. Once formed, there is no defined parting line in the bond that would permit a clean separation.

chemical closet (chemical toilet) A toilet that contains or recirculates a chemical that breaks wastes down while serving as a disinfectant and deodorant. It does not use water to flush and carry away sanitary waste to a public septic system.

chemical flux cutting The use of a chemical compound or flux to expedite oxygen torch cutting.

Chemical Hazard Response Information System (CHRIS) A series of monographs prepared for the U.S. Coast Guard, each of which provides detailed information on the hazards of a particular chemical.

chemically foamed plastic Spongy or cellular plastic material formed by the gas-producing action of its component chemical compounds.

cherry picker A powered lift for raising workers or materials. Consists of a basket or a lift attached to the end of a telescoping boom, and may be either self-propelled or mounted on a truck.

chiding A method of gilding.

chilled-water refrigeration system A cooling system in which cold water is circulated to remote cooling coils/blower units.

chiller A piece of equipment that utilizes a refrigeration cycle to produce cold (chilled) water for circulation to the desired location or use.

chilling The process of applying refrigeration in moderation so as to achieve cooling without freezing.

chimney A vertical, noncombustible structure with one or more flues to carry smoke and other gases of combustion into the atmosphere.



chimney

chimney apron The metal flashing built into the chimney and roof at the point of penetration. Serves as a moisture barrier.

chimney arch The upper structure over a fireplace.

chimney back The inside back wall of a fireplace, which may be made of firebrick masonry or ornamental metal, and is intended to reflect heat out into the room.



chimney arch



chimney back

chimney block Solid concrete blocks cast as segments of a circle for laying up or building round flues.

chimney bond A pattern of stretcher bond used in laying up the internal brickwork in masonry chimneys.

chimney breast (chimney piece) That part of the front of a fireplace that projects out into the room.

chimney can (chimney pot) A cylindrical extension placed on top of a chimney to improve the draft. It can be masonry or metal.

chimney cap (bonnet, chimney head) **1.** The slab or masonry top piece on a chimney. **2.** A metal top piece designed to minimize rainfall down the flue while improving the draft.



chimney cap (bonnet, chimney head)

chimney connector The smokepipe or metal breeching that connects the top of a stove, furnace, water heater, or boiler to a chimney flue.

chimney crane A swinging iron arm attached to the inside of a fireplace to support cooking pots over the fire.

chimney cricket (saddle) A small false roof built behind a chimney on the main roof to divert rainwater away from the chimney.

chimney effect (flue effect, stack effect) The process by which air, when heated, becomes less dense and rises. The rising gases in a chimney create a draft that draws in cooler gases or air from below. Stairwells, elevator shafts, and chases in a building often draw in cold air from lower floors or outside through this same process.

chimney flue The vertical passageway in a chimney through which the hot gases flow. A chimney may contain one or several flues. Flues are typically lined with fired clay pipes to resist corrosion and facilitate cleaning.

chimney gutter The flashing placed around a chimney for waterproofing the roof penetration.

chimney hood A covering top or cap that blocks rain from entering the flue.

chimney jamb The vertical sides of a fireplace opening.



chimney jamb

chimney lining The noncombustible, heat-resisting material that lines the flue inside the chimney. Typically, the lining consists of round or rectangular fired clay material.

chimney throat (chimney waist) **1.** The narrowest part of a flue. **2.** The area above a fireplace and below the smoke shelf, where the damper is usually located.



chimney throat (chimney waist)

chimney wing The sides of a fireplace chimney above the opening that close into the throat of the damper opening.

Chinese lacquer (Japanese lacquer, lacquer) A natural varnish, originating in China or Japan, and extracted from the sap of a sumac tree. This lacquer forms a high-quality surface.

chink **1.** A small, elongated cleft, rent, or fissure, such as the openings between logs in a log cabin wall. **2.** To install insulation around gaps in exterior walls and door and window frames.

chinking Any material used to fill in voids, such as those in stone walls or between the timbers of a log cabin.

chip **1.** A small piece of semiconducting substrate material, such as silicon, on which miniaturized electronic circuitry (LSI or VLSI circuits) is fabricated. **2.** A small fragment of metal, wood, stone, or marble that has been chopped, cut, or broken from its parent piece.

chipboard A flat panel manufactured to various thicknesses by bonding flakes of wood with a binder. Chipboard is an economical, strong material used for sheathing, subflooring, and cabinetry.

chip cracks (eggshelling) Similar to alligatoring or checking except that the edges of the cracks are raised up from the base surface.

chipper **1.** A small pneumatic or electric reciprocating tool for cutting or breaking concrete. **2.** Gasoline- or diesel-powered machine featuring a system of blades used to shred or chip logs or brush.

chisel A metal tool with a cutting edge at one end, used in dressing, shaping, or working wood, stone, or metal. A chisel is usually tapped with a hammer or mallet.



chisel

chisel bar A heavy metal bar with a sharp edge at one end.

chisel knife A sharp, narrow, square-edged knife used to remove paint or wallpaper.

chlorinated rubber A rubber-based product used in paints, plastics, and adhesives.

chlorinated solvent A material that dissolves greases and oils. Contains one or more chlorine atoms in its chemical structure.

chlorine A highly corrosive elemental gas.

chlorofluorocarbons (CFCs) Compounds consisting of chlorine, fluorine, and carbon atoms that are degraded only by the sun's radiation in the stratosphere, where released chlorine may contribute to ozone depletion. They can persist in the troposphere for 100 years or longer.

chord **1.** The top or bottom members of a truss (typically horizontal), as distinguished from the web members. **2.** A straight line between two points on a curve.



chord

chromate A greenish-yellow primer applied to steel members to inhibit corrosion. Chromate is a salt of chromic acid, frequently referred to as lead or zinc chromate.

chrome steel Carbon steel to which chromium has been added (in proportions of 0.5% to 2.0%) to increase the steel's hardness and yield strength.

chromium A grayish-white metallic element added to steel to enhance its strength and hardness. It is also used as a plating medium because of the rust-resisting surface that results. Chromium plating produces a highly polished finish.

chromium plating The application, by electroplating, of a thin coat of chromium to provide a hard, protective wearing surface or a surface that can take a decorative high polish.

chronic toxic chemical A substance that causes adverse health effects that may be delayed in their appearance, but usually cause permanent damage.

chuck An adjustable device with teeth that holds a cutting or drill bit in place.



chuck

churn molding A molding with a repeating wavy or chevron pattern.

chute An inclined plane or trough for sliding various items or bulk materials to a lower level, with the help of gravity.

cinder concrete A lightweight concrete that uses cinders for coarse aggregate.

circline lamp A fluorescent lamp with a circular tube.

circuit **1.** A closed path followed by an electric current. **2.** A piping loop for a liquid or gas. *See also* **channel**.

circuit breaker (automatic circuit breaker) An electrical device for discontinuing current flow during an abnormal condition. Unlike a fuse, a circuit breaker becomes reusable by resetting a switch.



circuit breaker (automatic circuit breaker)

circular arch An arch whose inner surface, and occasionally a portion of its outer surface, describe a circle.

circular cutting and waste The cutting of material such as flooring, roofing, or decking to create a curved surface or to go around a curved intersection. Also, a measure of the resulting waste material.

circular mil An electrical term for the cross-sectional area of a wire. A conductor with a diameter of one mil (0.001″) has a cross-sectional area of one circular mil.

circular mil-foot A unit of measure for an electrical conductor that is one circular mil in diameter and 1′ long.

circular saw A circular steel blade fitted with cutting teeth and mounted on an arbor.

circular spike A metal timber connector with teeth set in a ring. The teeth grip the wood as a central axial bolt is tightened.

circular stair (spiral stair) A cylindrical stairway in which the staircase is built in the shape of a corkscrew.



circular stair (spiral stair)

circulating head (circulating pressure) The pump-induced pressure in a piping system, such as one for hydronic heat, chilled water, or domestic hot water.

circulation **1.** The flow of a liquid or a gas within a closed series of pipes. **2.** The flow of air (fresh, heated, or cooled) in a building. **3.** The flow of people through a building. **4.** Any pipe forming a part of a liquid or gas circuit.

cistern A catch basin on a roof or an enlargement at the end of a gutter for catching and storing rainwater.

city planning (town planning, community planning) The conscious control of growth or change in a city, town, or community, taking into account aesthetics, industry, utilities, transportation, and many other factors that affect the quality of life.

civil drawings Site drawings, such as utility, grading and drainage, site improvements, and landscaping plans. Civil drawings encompass all work other than the structure itself.

civil engineer An engineer specializing in the design of public works, such as roads, buildings, dams, bridges, and other structures, as well as water distribution, drainage, and sanitary sewer systems.

C-label A door certified by Underwriters' Laboratories as meeting their class C level requirements.

cladding A covering or sheathing applied to provide desirable surface properties, such as durability, weathering, and corrosion or impact resistance.



cladding

claim **1.** A contractor's request for additional compensation or an extension of time pursuant to the contract terms. **2.** A request to be paid for the cost of damages when an insured loss occurs.

claims examiner Relative to insurance claims, the supervisor who oversees the paperwork submitted by the field adjuster.

clamp A mechanical device used to hold items together or firmly in place while other operations are being performed. The clamping force may be applied by screws, wedges, cams, or a pneumatic/hydraulic piston.

clamping screw A screw used with wood or metal jaws to provide a clamping force for temporary or permanent fastening.



clamping screw

clamping time The amount of time a bonded joint must remain immobile in a clamp in order for the glue to set.

clamshell **1.** A bucket used on a derrick or crane for handling loose granular material. The bucket's two halves are hinged at the top, thus resembling a clamshell. **2.** A wood molding with a cross section that resembles a clamshell.

clapboard (bevel siding, lap siding) A wood siding used as exterior covering in frame construction. It is applied horizontally, overlapped with the grain running lengthwise. The thickest section of the board is on the bottom.



clapboard (bevel siding, lap siding)

clapper valve A swing check valve that permits fluid flow in one direction only.

clarification drawing An illustration provided by an architect or engineer to explain in more detail some area or item on the contract documents, or as a part of a job change order or modification.



clapper valve

Clarke beam A composite beam consisting of planks bolted with their flat sides together and then strengthened with a board nailed across the joint.

class **1.** A group of items ranked together on the basis of common characteristics or requirements. **2.** A division grouping or distinction based on grade or quality. **3.** The opening into which a door or window will be fitted.

Class Ia flammable liquid A liquid having a flash point below 73°F (22.8°C) and a boiling point below 100°F (37.8°C).

Class Ib flammable liquid A liquid having a flash point below 73°F (22.8°C) and a boiling point at or above 100°F (37.8°C).

Class Ic flammable liquid A liquid having a flash point at or above 73°F (22.8°C) and below 100°F (37.8°C).

Class II combustible liquid A liquid having a flash point at or above 100°F (37.8°C).

Class IIIa combustible liquid A liquid having a flash point at or above 140°F (60°C) and below 200°F (93.4°C).

Class IIIb combustible liquid A liquid having a flash point at or above 200°F (93.4°C).

Class A, B, C, D, E Fire-resistance ratings applied to building components such as doors or windows. Class A is an Underwriters' Laboratories classification for a component having a 3-hour fire endurance rating; Class B, a 1 or 1½-hour rating; Class C, a ¾-hour rating; Class D, a 1½-hour rating; and Class E, a ¾-hour rating.

Class A fire A fire involving ordinary combustibles, such as wood, paper, some plastics and textiles.

Class B fire A fire involving oil, gas, paint, or other flammable liquids.

Class C fire A fire involving live electrical equipment that requires the use of electrically nonconductive extinguishing agents.

Class D fire A fire involving combustible metals such as magnesium, titanium, and sodium that require an extinguishing medium that does not react with the burning metal.

classical architecture Characteristic of or pertaining to the styles, types, and modes of structural construction and decoration practiced by the Greeks and Romans.

classicism An architectural style derived from the basic principles and design of Greco-Roman or Italian Renaissance buildings.

clause A subdivision of a paragraph or subparagraph within a legal document such as a contract. A clause is usually numbered or lettered for easy reference.


classical architecture

claw bar A steel bar that is straight at one end and bent at the other. The straight end has a chisel point, while the bent end has a notch for pulling out nails. A claw bar is used for general demolition work.

claw plate A round timber connector that has raised prongs to bite into the wood.

clay A fine-grained material, consisting mainly of hydrated silicates of aluminum, that is soft and cohesive when moist, but becomes hard when baked or fired. Clay is used to make bricks, tiles, pipe, earthenware, etc.

clay content In any mixture of soil or earth, the percentage of clay by weight.

clay-mortar mix A mixture consisting of pulverized clay that is added to masonry mortar to act as a plasticizer.

clay pipe Pipe made of earthenware and glazed to eliminate porosity. Clay pipe is used for drainage systems and sanitary sewers.


clay pipe

clay spade A wide, flat, chisel-like cutting tool used in a pneumatic hammer to cut into tightly compacted materials like clays.


clay spade

clay tile A fired earthenware tile used on roofs. Called *quarry tile* when used for flooring.

Clayton Act Legislation enacted by Congress in 1914 to lessen the negative effects of the Sherman Anti-Trust Act by allowing labor to organize for purposes of negotiating with a single employer.


clay tile

clean aggregate Sand or gravel aggregate that is free of clay, dirt, or organic material.

clean energy Energy obtained from a renewable source that produces zero or low emissions and has minimal environmental impact.

cleanout **1.** A pipe fitting with a removable threaded plug that permits access for inspection and cleaning of the run. **2.** A door in the base of a chimney that permits access for cleaning. **3.** A small door in a ventilation duct to permit access for removal of grease, dust, and dirt blockages.

cleanout door The door in a cleanout frame. *See also* **cleanout**.


cleanout


cleanout door

clean power Power that is relatively free of electrical noise and harmonic distortion.

clean room A special-purpose room that meets requirements for the absence of lint, dust, or other particulate matter. In a clean room, the filter systems are high efficiency and the air exchange is one-directional laminar flow.

clearance (clearage) **1.** The distance by which one item is separated, or clear, from another; the empty space between them. **2.** An intentional gap left to allow for minor dimensional variations of a component or a part.

clear glaze A transparent glaze for ceramic applications.

clearing The removal of trees, vegetation, or other obstructions from an area of land. Also referred to as clearing and grubbing.

clearing arm A branch on a pipe to provide access for cleaning.

clearstory (clerestory) That part of a church or building that rises above the roofs of the other parts of the building, with windows for admitting light to the central interior area.

cleat A small block of wood nailed to the surface of a wood member to stop or support another member.

cleat wiring Electrical wiring that is exposed and supported on standoff insulators.

cleavage A natural parting or splitting plane found in slate, mica, and some types of wood.

cleavage plane In crystalline material, the plane along which splitting can easily be performed.

cleft timber A wooden beam that has been split to the desired size or shape.

clench bolt (clinch bolt) A bolt designed to have one end bent over to retain it in place.

clench nail (clinch nail) A nail made to have the protruding point bent over after being driven.

clerk of the works A representative of the architect or owner who oversees construction, handles administrative matters, and ensures that construction is in accordance with the contract documents.

clevis A U-shaped bar of metal with holes drilled through the ends to receive a pin or bolt. A type of shackle.



clevis

client **1.** Party to a contract who commissions the work. On capital projects, may also be referred to as the “owner.” **2.** Customer, principal, owner, promoter, buyer, or end user of the product or service created by the project.*

climbing crane A hoisting device with a vertical portion that is attached to the structure of a building so that as the construction is built higher and higher, the crane rises along with it.



climbing crane

climbing form Vertical concrete formwork that is successively raised after each pour has hardened. The formwork is anchored to the concrete below. *See also* **slip form**.



climbing form

clink **1.** The sealed edge between sheets of metal roofing. **2.** A pointed steel bar used to break up concrete.

clinker brick A hard brick that is frequently formed with a distorted shape and is used for paving.

clinometer An instrument for measuring angles of elevation or inclination.

clip **1.** To cut off, as with shears. **2.** A short piece of brick that has been cut. **3.** A small metal fastening device.

clip joint A thicker-than-usual mortar joint used to raise the height of a masonry course.

clipped gable A gable roof with a shortened ridge pole creating a short hip roof at the gable.

clipped header (false header) In masonry, a half-brick placed in a wall to look like a header.

clipped lintel A lintel connected to another structural member to help carry the load.

cloister **1.** A monastic establishment such as a monastery or convent. **2.** A covered passageway on the side of an open courtyard, usually having one side walled and the other an open arcade or colonnade.

cloistered arch (cloistered vault) A structure whose sides have the appearance of four quarter rounds fitted together so that the corner joints appear as an “X” when viewed from above.

cloister garth An open courtyard surrounded by a cloister.

close **1.** An enclosed place, such as the area around a cathedral. **2.** A passage from a street to a court and the houses facing it. **3.** The common stairway of an apartment building.

close-boarded (close-sheeted) **1.** Sheathing with boards fitted tight against one another. **2.** Privacy fencing in which adjacent boards are fitted tight against one another.

close-coupled tank and bowl A toilet in which the bowl and water tank are manufactured separately and then bolted tightly together with only a gasket at the joint.



close-coupled tank and bowl

close-cut The trimming of a roof covering (shingle, tile, or slate) where adjacent surfaces of a hip or valley meet.

closed-cell A type of foamed material in which each cell is totally enclosed and separate so that the bulk of the material will not soak up liquid like a sponge. Closed-cell material is characteristic of certain types or insulation board and flexible glazing gaskets.

closed-circuit grouting A system of injection that fills all voids to be grouted at each hole and returns excess grout to the grouting apparatus.

closed-circuit television A television circuit with no broadcasting facilities and a limited number of reception stations. Transmission is typically between two points. Can be integrated into a Building Automation System and used for building security purposes.

closed competitive selection (closed bidding) A process of competitive bidding whereby the private owner limits the list of bidders to persons he has selected and invited to bid. *See also* **closed list of bidders**.

closed list of bidders A list of those contractors who have been approved by the architect and owner as the only ones from whom bid prices will be accepted. *See also* **closed competitive selection**.

closed loop control An instrument that measures the changes in a controlled variable (temperature, pressure) and actuates the control device (valve, damper) to bring about a change.

closed loop system In Building Automation Systems, the arrangement of heating, ventilating, and air-conditioning components so that each component affects and can respond to the other, allowing system feedback.

closed shaft A vertical opening in a building that is covered over or roofed at the top.

closed sheathing (closed sheeting) A continuous framework with boards or planks placed side by side to support or retain the sides of an excavation.



closed sheathing (closed sheeting)

closed shop A term applied to a trade or skill that requires membership in a particular union to the exclusion of nonunion members.

closed specifications Specifications that require certain trade name products or proprietary processes. Provisions for alternatives are not included.

closed stair (closed stair string, closed string) A stairway with covered strings on both sides so that the ends of the treads and risers are not visible.

closed system Any heating or cooling system in which the circulating medium is not expended, but is recirculated through the system.



closed valley

closed valley A roof covering in a roof valley laid so that the flashing is not visible.

close-grained Wood in which the annual growth rings are close together, thus indicating slow growth.



close nipple

close nipple A short piece of pipe that is threaded from both ends, leaving no smooth outside surface.

closeout The completion of project work. The phase at the end of a project life cycle just before the operation begins.*

closer **1.** A mechanism for automatically closing a door. **2.** The final masonry unit (brick, stone, or block) that completes a horizontal course. The unit may be whole or trimmed to size.

closer

closer reinforcement A metal plate attached to a door and/or a frame to reinforce the area where a door closer is installed.

closer reinforcing sleeve A plate used to reinforce the corner joints of a metal door frame.

close studding A method of construction in which studs are spaced close together and the intervening spaces are filled with plaster.

closet **1.** A small room or recess for storing utensils or clothing. **2.** A water closet.

closet bend The 90° soil pipe fitting installed beneath a toilet.

closet bolt A special bolt for securing a floor-mounted toilet to the floor and soil pipe flange.

close tolerance A term describing smaller allowable dimension deviation than would normally be allowed.

closet pole (closet rod) A strong rod mounted horizontally in a closet to support coat hangers.

closet stop valve The valve underneath a tank-type water closet. The valve is used to shut the water off so that repairs can be made to the flushing mechanism inside the tank.

closing costs The costs associated with the sale/purchase of real estate property, such as legal fees, recording fees, and title search and insurance, but not including the cost of the property itself.

closing device (automatic closing device, self-closing device) **1.** A mechanism that closes a door automatically and slowly after it has been opened. **2.** A mechanism, usually fused, that releases and closes a fire door, damper, or shutter in the event of a fire.



closing device (automatic closing device, self-closing device)

closing stile The vertical side of a door or casement sash that seats against the jamb or frame when the door or window is closed.



closing stile

closure bar A flat metal bar that is attached to a stair string next to a wall. The bar bridges or covers the opening between the string and the wall.

clout **1.** A metal sheathing or protection plate on a moving wood member to protect it from wear. **2.** A type of nail.

clustered column Two or more columns, joined together at the top and/or bottom, which share the structural load equally.

clustered pier A pier consisting of several shafts grouped together as a single unit, frequently surrounding a heavier central member.

cluster housing A planned residential development with dwelling units built close to one another and common open space for use by all residents.

clutch A friction or hydraulic coupling between a power source and a drive train.

coach bolt A bolt with a smooth, circular head. Rotation of the bolt in its hole during tightening is prevented by the square shoulder or neck under the head.



coach bolt

coal-tar pitch (tar) A black bituminous material made from the distillation of coal and used as a waterproofing material on built-up roofing and around elements that protrude through a roof.

coarse aggregate Aggregate that will not pass through a ~$^{1}/_{4}''$ sieve screen.

coarse filter A prefilter used in air-conditioning systems to remove large particles such as dust and lint. This type of filter is usually reusable after being vacuumed or washed.

coarse-grained **1.** A term used to describe wood in which the annual growth rings are widely separated, thus indicating fast growth. *See also* **coarse-textured**. **2.** The "pebbly" effect that sometimes occurs on a photographic enlargement.

coarse-textured (coarse-grained) A term referring to a porous, open-grained wood that usually requires priming and filling to produce a smooth surface.

coat A single covering layer of any type of material, such as paint, plaster, stain, or surface sealant.

coated base sheet (coated base felt) The underlying sheet of asphalt-impregnated felt used in built-up roofing.



coated base sheet (coated base felt)

coated glass Insulating glass that has been treated to help retain building heat. Coated glass also blocks ultraviolet and infrared light.

coated nail A nail with a coating on it. The coating may be cement, copper, zinc, or enamel.

coat rack A piece of furniture that supports several coats (with or without hangers) and that may include a stand for umbrellas and a tray for galoshes.



coat rack

coaxial cable A cable consisting of a tube of conducting material surrounding a central conductor. The tube is separated from contact with the cable by insulation. Coaxial cable is used to transmit telephone, telegraph, television, and computer signals.

cock **1.** A valve having a hole in a tapered plug. The plug is rotated to provide a passageway for fluid. **2.** Any device that controls the flow of liquid or gas through a pipe. *See also* **sill cock** *and* **bibcock**.

cock bead A bead that projects higher than the adjacent surface.

cocking (cogging) The fitting together of notched timbers, beams, or pieces of wood to form a joint.

code The legal requirements of local and other governing bodies concerning construction and occupancy. The enactment and enforcement of codes is intended to safeguard the public's health, safety, and welfare.

Code of Federal Regulations A uniform system of listing all the regulations promulgated by any federal agency.

code review drawings Drawings that portray compliance to applicable codes and standards that can be developed by or through the contractor and are supplementary to a written scope of work (also called *incidental drawings*).

coefficient of conductivity The measure of the rate at which a material will conduct thermal energy, or heat.

coefficient of expansion For building materials, the increase in dimension per unit of length caused by a rise in temperature of one degree Fahrenheit, expressed in decimal form.

coefficient of friction A ratio of the force causing an object to slide to the total force perpendicular to the sliding plane. The ratio is a measure of the resistance to sliding.

coefficient of performance **1.** In a heat pump, the ratio of heat produced to energy expended. **2.** In a refrigeration system, the ratio of heat removed to energy expended.

coefficient of static friction The coefficient of friction required to make an object start sliding.

coefficient of subgrade reaction The ratio of load per unit area on soil to the corresponding deformation.

coffer (lacunar) **1.** An ornamental recessed panel in the ceiling of a vault or dome. **2.** A cofferdam; a caisson.

cofferdam A watertight enclosure used for foundation construction in waterfront areas. Water is pumped out of the cofferdam allowing free access to the work area.



cofferdam

coffering A ceiling with ornamental recessed panels.

cog **1.** In a cogged joint, the portion of wood left where a beam has been notched. **2.** A nib on roofing tiles.

cogeneration The simultaneous production of power and another form of useful thermal energy in a single process. A common example is the use of combustion or co-combustion processes to produce both electricity and steam or hot water.

cohesion **1.** In soils, the sticking together of particles. **2.** In adhesives or sealants, the ability to stick together without cracking.

cohesionless soil A sod, such as clean sand, with no cohesive properties. cohesive failure The internal shearing of a joint sealant that is weaker cohesively than the adhesion bond to the adjacent joint surfaces. The possible causes for failure include insufficient curing, excessive joint movement, improper joint dimensions, or improper selection of the sealant itself.


coil

cohesive soil Soil that tends to hold together in a comparatively stable clump or mass, such as clay.

coil A term applied to a heat exchanger that uses connected pipes or tubing in rows, layers, or windings, as in steam heating, water heating, and refrigeration condensers and evaporators.

coiled expansion loop A gradual bend, loop, or coil of pipe or tube intended to absorb expansion and contraction caused by temperature changes. By flexing like a spring, undesirable stresses on the piping system are relieved or minimized.

coinsurance penalty The penalty against a policyholder for not carrying enough insurance on his or her property. In these cases, the full cost of the claim will not be paid by the insurance company. Repair contractors should be aware that the policyholder will have to pay a substantial part of the repair bill.

cold-air return In a heating system, the return air duct that transports cool air back into the system to be heated.

cold-cathode lamp An electric-discharge lamp that operates with low current, high voltage, and low temperature. The color of the light depends on the vapor used in the lamp.

cold cellar An underground storage area where fruit and vegetables are stored during the winter. The constant ground temperature keeps the contents from freezing and retards rotting.

cold check Fine cracks that appear in some wood finishes, such as paint and varnish, after being subjected to alternating warm and cold temperatures.

cold chisel A steel chisel with a tempered edge for cutting cold steel.

cold deck (cold duct) In an HVAC system, the source of cold air for cooling interior zones.

cold-drawn A process in which metal is formed in shape and size by being pulled through dies while cold. This type of metal forming has an effect on final surface finish and hardness and is often used in the manufacture of wire, tubing, and rods.

cold-finished bar A metal bar that has been drawn or rolled to its final dimensions while cold. The process of cold finishing produces a hard, smooth, surface finish.

cold flow The continuing permanent change in slope of a structural system under constant load.

cold joint The joint between two consecutive pours of concrete if the time elapsed between the first and second pours is such that the first pour has started to set.

cold-laid mixture Any mixture that may spread at ambient temperatures without being preheated.

cold mix (cold patch) An asphaltic concrete made with slow-curing asphalts and used primarily as a temporary patching material when hot mix plants are closed. Cold mix is used to repair potholes, but is less durable than hot mix.

cold molding **1.** Material that is shaped at ambient temperature and hardened by baking. **2.** The material that is used in the cold-molding process.

cold-process roofing Built-up roofing consisting of layers of asphalt-impregnated felts that are bonded and sealed with a cold application of asphalt-based roof cement.

cold-rolled Descriptive of a metal shape that has been formed by rolling at room temperature, thus giving a dense, smooth, surface finish and high tensile strength.

cold room A walk-in refrigerator for storage of perishable materials.

cold saw A saw for cutting metal at room temperature. A cold saw may be either circular or reciprocating.

cold set A hardened hand tool used to flatten sheet metal seams.

cold-setting adhesive A glue that sets at ambient room temperature.

cold solder A soft-metal, air-hardening material used for bonding two metals at ambient temperatures. Cold solder, unlike a true solder, does not require a hot bond.


collar

collar **1.** A flashing for a metal vent or chimney where it passes through a roof. **2.** A trim piece to cover the hole where a vent goes through a wall or ceiling. **3.** A metal band that encircles a metal or wooden shaft.

collar beam The horizontal board that joins the approximate midpoints of two opposite rafters in order to increase rigidity.

collar beam roof (collar roof) A roof with rafters connected by collar beams.

collaring The pointing of masonry or tile joints under overhangs.


collar tie

collar joint The joint between the collar beam and roof rafters.

collar tie A horizontal tie connecting pairs of opposite rafters near the ridge of the roof.

collusion A secret agreement or action of a fraudulent, illegal, or deceitful nature.

colonial architecture **1.** An architectural style from a mother country that has been incorporated into the buildings of settlements or colonies in distant locations. **2.** Eighteenth-century English Georgian architecture as reproduced in the original colonies of the United States.


colonial casing

colonial casing A style of door and window trim molding.

color chart A standardized card or folder showing a display of colors or finishes.

colored aggregate Aggregate material that has been selected for use because of its natural color.

colored concrete Concrete mixed with colored cement or to which pigment has been added during mixing.

color rendering index (CRI) A measure of the quality of a light, where the ability of the light to render an object's true color(s) is compared to that of a reference light. Under a lamp with a low CRI rating, colors will appear unnatural.

color temperature The actual degree measurement, in Kelvin, of the color of a light source.

column A long, relatively slender, supporting pillar. A column is usually loaded axially in compression.



column

column baseplate A bearing plate beneath a column that distributes the load coming down through the column over a wider area.



column baseplate

column clamp A latching device for holding the sections of a concrete column form together while the concrete is being placed.



column clamp

column footing The foundation under a column that spreads the load out to an area large enough so that the bearing capacity of the soil is not exceeded and differential settling does not occur.

column schedule A production plan outlining the construction of columns in a structure. Provides column sizes, elevations (top and bottom), and type and size of reinforcement required.

column ties Steel reinforcement surrounding the vertical reinforcement in a concrete column to align the bars and provide additional strength. May be rectangular or ring-shaped.

comb **1.** A tool used to produce a rough surface or pattern in plaster or concrete. **2.** A comb board.

comb board A board with notches on its upper edge, used to cover the joint at the ridge of a pitched roof.

combed Descriptive of a surface that has been raked with a comb to produce a rough or patterned finish.

combination door An exterior door that has interchangeable panels of glazing and screening—one for summer and the other for winter use.



combination door

combination faucet A faucet that is connected to both hot- and cold-water supply pipes so that the water it dispenses can be of the desired temperature.



combination faucet

combination fixture **1.** A combination kitchen and laundry sink in a single unit, with both deep and shallow bowls side by side. **2.** An institutional or prison fixture that combines the functions of a sink and toilet into a single fixture.

combination plane A carpenter's or joiner's hand tool that has interchangeable blades or guides so that it can be used for various shaping operations.

combination waste and vent system A plumbing system with an oversized waste pipe that also serves as a vent pipe.

combination window A window with replaceable screen and glass inserts for summer and winter use.

combined aggregate A mixture of both fine and coarse aggregate used in concrete.

combined footing A footing that receives loading from more than one column or load-supporting element.



combined footing

combined frame A doorway with a fixed panel of glass on either or both sides of the door.

combined load The total of all the loads (live, dead, wind, snow, etc.) on a structure.

combined sewer A sewer that receives both storm water and sewage.

combing **1.** The act of dressing a stone surface. **2.** The use of a serrated comb or brush to create a surface pattern or roughness in paint, plaster, or concrete. **3.** Those shingles on a roof that project above the ridge line. **4.** The top ridge on a roof.

combplate The fixed floor plate at either end of an escalator or moving walkway that has fingers that project into the serrations of the moving segments to prevent an object from wedging into the seam.

combustible Descriptive of a substance that will burn in the air, pressure, and temperature conditions of a burning building.

combustion A rapid chemical process, such as oxidation, that produces significant thermal energy (heat), and usually light as well.

combustion air Fresh, outside air brought in via ductwork to the furnace and/or hot water heater.

combustion chamber The section within a woodstove, boiler, or furnace where the burn takes place, typically lined with firebrick or insulation.

comfort chart A chart showing the limits of human comfort for various combinations of temperature, relative humidity, and circulating air velocity.

commercial projected window A type of steel window used in commercial and industrial applications where decorative trims and moldings are not used. A projected window has one or more panels that rotate either inward or outward on a horizontal axis.

commercial tolerances Allowable variations in the dimensions of items mass-produced for the commercial market.

comminution To reduce to minute particles, as in the grinding of coal or the screening of sewage.

commissioning The process of ensuring that the complex array of equipment that provides lighting, heating, cooling, ventilation and other amenities in facilities works together effectively and efficiently. Commissioning typically begins during the facility's conceptual design phase and ideally continues throughout the life of the facility.

commissioning agent A member of the project team who ensures the proper installation and operation of technical building systems. Normally, the commissioning agent is hired directly by the owner and works independently of both the designer and contractor.

committed cost A cost which has not yet been paid, but an agreement, such as a purchase order or contract, has been made that the cost will be incurred.*

Committee for Industrial Organizations (CIO) A labor union organized in 1935 for the purpose of representing industrial workers. The CIO was created as a result of a dispute with the American Federation of Labor (AFL). John L. Lewis, president of United Mine Workers and a member of the CIO, was instrumental in merging the AFL and CIO in 1955.

common area maintenance (CAM) charge A provision in a commercial lease that requires the tenant to pay a proportionate share of the common area operation costs.

common bond (American bond) A brick masonry wall pattern in which a header course of brick is laid after every five or six stretcher courses.



common bond (American bond)

common brick Brick not selected for color or texture, but instead used as filler or backing. Though usually not less durable or of lower quality than face brick, common brick typically costs less. Greater dimensional variations are also permitted.

common ground A strip of wood recessed in a masonry or concrete wall to provide a surface to which something else can be nailed.

common joist (bridging joist) One of a series of parallel beams laid on edge to support a floor or ceiling.



common joist (bridging joist)

common lime Hydrated lime or quick lime used in plaster or mortar.

common nail A general-purpose, headed nail with a diamond-shaped point used where appearance is not important, as in framing.



common nail

common rafter (intermediate rafter, spar) A wood framing member that reaches from the rafter plate at the eaves to the ridge board.

common wall **1.** A wall built on the boundary between separate lots of land so that it does not belong completely to either owner. **2.** A party wall between dwellings in a condominium or row house.

community antenna television (CATV) A single source of television signals transmitted to multiple receivers. Used in buildings that have television cables. Can be integrated in the building's communications system.

compacted volume The volume of any mass of material after it has been compressed, particularly soil in an embankment or fill area.

compact fluorescent lamp (CFL) Efficient lightbulbs that use far less energy than standard, incandescent bulbs. CFLs typically provide 8,000 hours of usage, compared to less than 2,000 for incandescent bulbs.

compact fluorescent lamp (CFL)

compaction **1.** The compression of any material into a smaller volume; for example, waste compaction. In specifying compaction of embankment or fill, a percent compaction at optimum moisture content is often used. Another method is to specify the equipment, height of lift, and number of passes. **2.** The elimination of voids in construction materials, as in concrete, plaster, or soil, by vibration, tamping, rolling, or some other method or combination of methods.

compaction pile A pile driven into the ground to compact soil and increase its bearing capacity.

compactor A machine that compresses or compacts materials by using hydraulic force, weight, or vibration.



compactor

company Term used primarily to refer to a business first party, the purpose of which is to supply a product or service. In a capital project, typically refers to the contractor who is performing services for an owner or client.*

compartmentation The containment of smoke within a building by using a system of barriers and compartments.

compass **1.** An instrument for locating the magnetic north pole of the earth. **2.** A mechanical drawing device used to draw circles.



compass

compass brick A curved brick used in circular patterns or to form an arch.

compass plane A carpenter's plane with a curved baseplate and/or blade for finishing curved wood pieces.

compass rafter A rafter with one or both sides curved.

compass roof A roof built out of curved rafters.

compass saw (keyhole saw) A small tapering handsaw used to cut rounded shapes or circles.

compass survey A surveyor's traverse using bearings determined by a compass, as opposed to bearings determined by recording the angles turned by the instrument.

compass work (circular work) Carpentry or joinery based on a circular or curved motif.

compatibility agent A substance that, when added to another substance, improves the stability and even distribution of that substance. For example, compatibility agents allow the simultaneous application of a pesticide and fertilizer, or two or more pesticides.

compensation **1.** The amount paid for goods, labor, or services provided. **2.** An amount paid to settle a claim for damages.

compensatory damages An award for damages intended to compensate the plaintiff by granting a monetary amount equal to the loss or injury suffered.

completed operations An insurance term referring to coverage for personal injuries or damage to property that occurs after construction has been completed. At least one of the following conditions must be met: all activities governed by the contract are finished; all activities at one project site are finished; or that part of the project that precipitated the claim is in use by the owner. This insurance does not cover the actual finished project itself.

complete fusion In welding, a total merging of the welded surfaces, including all of the weld filler material.

completion bond (construction bond, contract bond) The guarantee by a bonding company that a contract will be completed and will be clear of all liens and encumbrances.

completion date The date certified by the architect when the work in a building, or a designated portion thereof, is sufficiently complete, in accordance with the contract documents, so that the owner can occupy the work or a designated portion thereof for the use for which it is intended.

composite arch An arch formed from three or four centers of curvature.

composite beam A beam combining different materials to work as a single unit, such as structural steel and concrete or cast-in-place and precast concrete.



composite beam

composite column A column designed to combine two different materials or two different grades of material to form a structural member. A structural steel shape may be filled with concrete, or a structural steel member for reinforcing may be encased in concrete.

composite construction A building constructed of various building materials, or by using more than one construction method, such as a structural steel frame with a precast roof, or a masonry structure with a laminated wood beam roof.



composite construction

composite door A door with a wooden or metal shell over a lightweight core. The core is usually made of foam or a material that is shaped like a honeycomb cell.

composite fire door A door made of metal or chemically treated wood surrounding a core material. The door is rated as resistant to fire for some specified period of time.

composite girder A girder assembled from component parts of similar or different materials; for example, a plate girder or a bar joist with wooden flanges.

composite joint 1. A joint that is secured by using more than one method, such as riveting and welding. **2.** In plumbing, a general reference to joining bell-and-spigot pipe with packing materials such as rope and rosin, or cement and hemp.



composite door

composite pile A pile consisting of more than one member or material, but designed to act as one unit.

composite truss A load-supporting framework of several members. Those members in compression are made of wood; the tension members are usually made of steel.

composition board (composite board) A manufactured board consisting of any of several materials, usually pressed together with a binder. Composition board is frequently used as sheathing, wall board, or as an insulation or acoustical barrier.

composition roofing (built-up roofing) A roof consisting of several layers, thicknesses, or pieces.



composition roofing (built-up roofing)

composition shingles (asphalt shingles) Shingles made from felt impregnated and covered with asphalt, and then coated on the exposed side with colored granules.



composition shingles (asphalt shingles)

compound beam (built-up beam) A beam consisting of smaller components that have been assembled and fastened together to function as a single unit.

compound pier (compound pillar) A column usually consisting of one central shaft surrounded by secondary shafts, or by two or more equal shafts working in conjunction with one another.

compound wall A wall constructed of more than one material.

Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) A federal law defining the government actions in the event of an uncontrolled release of hazardous materials into the environment.



compound wall

comprehensive general liability insurance A type of insurance that provides blanket coverage for all types of liability with the exception of those specifically excluded. It covers contractual liability as well as unforeseen future hazards, and may also include automobile coverage. Completed operations liability, more extensive contractual coverage, and product liability insurance can be added to this type of policy.

compressed fiberboard Wood fiber that has been compressed into sheets and is commonly used as a paneling material.

compressed straw slab A board manufactured from straw compressed with a binder and cured.

compressibility The ease with which a fluid is reduced in volume by the application of pressure.

compression Structurally, it is the force that pushes together or crushes, as opposed to tension, which is the force that pulls apart.

compression bearing joint A joint consisting of a structural member in compression, pressing or bearing against another member also in compression.

compression chiller A system in which water is cooled by liquid refrigerant that vaporizes at a low pressure and proceeds into a compressor. The compressor increases the gas pressure so that it may be condensed in the condenser.



compression bearing joint

compression joint 1. A bell-and-spigot joint that becomes watertight when the spigot is pressed into a compression gasket in the bell. **2.** Any joint that is engineered to employ pressure as a seal.

compression, schedule When an excessive amount of noncritical tasks are delayed until they become critical tasks and create chaos near the end of a schedule or phase.

compression tank In a hot water heating system, a tank that absorbs the water pressure exerted.

compression test 1. A test of any material by compression to determine its useful strength characteristics. The test is most often performed in accordance with standards published by the American Society for Testing and Materials or some other professional or industrial organization. **2.** A determination of the compression developed in each cylinder of an internal combustion engine.

compressive stress The resistance of a material to an external pushing or shortening force.

compressor **1.** A machine that compresses air or gases. **2.** In refrigeration/air-conditioning, a machine that compresses a refrigerant gas, which then goes to an evaporator. **3.** A truck- or trailer-mounted apparatus, usually diesel-driven, that generates compressed air for demolition hammers, sandblasting, and similar needs on a construction site.



compressor

computer-aided design (computer-aided design and drafting) The use of computer technology to analyze, design, or model a building or system. Allows for greater efficiency and consistency, faster reproduction, and easier alteration than traditional methods.

computerized maintenance management software (CMMS) The use of computer technology to schedule plant and equipment maintenance, track assets, and efficiently carry out overall facility management. The purpose of CMMS is to simplify the planning and administrative functions of maintenance, purchasing, and inventory management.

concave joint A masonry joint formed by a curved pointing tool and used particularly on exterior masonry walls.



concave joint

concealed hinge A hinge mortised into both the jamb and edge of a door so that it is hidden when the door is closed.

concealed location As defined for the purpose of building codes, any area of a building that cannot be reached without doing permanent damage to other building components.

concept documents A series of drawings and other definitive documents that illustrate a design professional's concept for a project.

concourse An open area for the circulation of large crowds within a building, as in an airport terminal or shopping mall.

concrete A composite material consisting of sand, coarse aggregate (gravel, stone, or slag), cement, and water. When mixed and allowed to harden, it forms a stonelike material.

concrete

concrete admixture A special substance or chemical added to a concrete mix. Typically, an admixture is used to control setting, entrain air, impart color, control workability, or to waterproof.

concrete aggregate Granular mineral material that is mixed with cement and water to form concrete.

concrete block A masonry building unit of concrete that has been cast into a standard shape, size, and style.



concrete block

concrete board A concrete and fiberglass panel typically used as a tile backing material.

concrete bond (bond plaster) A thin gypsum plaster coat applied to a concrete face as a base for subsequent coats of plaster.

concrete contraction The shrinkage of concrete that occurs as it cures and dries.

concrete curing compound A chemical applied to the surface of fresh concrete to minimize the loss of moisture during the first stages of setting and hardening.

concrete cylinder test A compression test for concrete strength. Wet samples of concrete are carefully placed in specially made containers 6″ in diameter and 12″ high. The cylinders are sent to a laboratory where a compression test is performed. This is done by putting the concrete in a hydraulic machine that measures the pressure(s) needed to crush it. Cylinder tests are usually performed for each pour on a project that requires concrete strength control.

concrete finish The smoothness, texture, or hardness of a concrete surface. Floors are trowelled with steel blades to compress the surface into a dense protective coat. Walls that are exposed to the weather are often ground with a carborundum stone or wheel, with cement then added to fill the small voids. A smooth surface is desired so that water cannot enter the small holes, freeze, and deteriorate the surface.

concrete finishing machine **1.** A portable machine with large paddles like fan blades used to float and finish concrete floors and slabs. **2.** A large power-driven machine mounted on wheels that ride on steel pavement forms. Used to finish concrete pavements.



concrete finishing machine

concrete floor hardener An additive used to impart extra wear and chip resistance to concrete floors. The additive may be placed in the mix before the floor is cast, or it may be applied to the surface in liquid or granular form.

concrete, foamed Concrete to which a chemical foaming agent has been added. The result is a light, porous material, full of air holes, with low strength and good thermal properties.

concrete insert A device, such as a pipe sleeve, a threaded bolt, or a nailing block, that is attached to a concrete form before placing concrete. When the concrete forms are removed, the insert remains embedded in the concrete.



concrete insert

concrete masonry **1.** Concrete blocks laid with mortar or grout in a manner similar to bricks. **2.** Concrete that may be poured in place or as special tilt-up building walls.

concrete nail A steel nail that has been hardened and fitted with a diamond point so that it can be driven into concrete without bending.

concrete, normal weight Concrete made with the standard mix of component materials and weighing approximately 148 lbs. per cu. ft.

concrete paver **1.** A machine used to pave roads with concrete. A paver is equipped with a loading skip, a rotating drum, and a discharge boom. **2.** A precast paving block used in landscaping for walks and patios.

concrete pile A slender, precast concrete-reinforced member that is embedded in the soil by driving, jetting, or insertion into a predrilled hole. May or may not be prestressed.


concrete pile

concrete planer A machine with cutters or grinders used to level and refinish old concrete pavement.

concrete plank A hollow-core or solid, flat beam used for floor or roof decking. Concrete planks are usually precast and prestressed.


concrete plank

concrete, prestressed Concrete members with internal tendons that have been tensioned to put a compressive load on the members. When a load is applied to a prestressed member, compression is decreased where tension would normally occur.

concrete pump A pump that forces premixed concrete through a hose to a desired location.


concrete pump

concrete, ready-mixed (transit-mixed) Concrete delivered to a site, mixed and ready for placement.

concrete reinforcement Metal bars, rods, or wires placed within formwork before concrete is added. The concrete and the reinforcement are designed to act as a single unit in resisting forces.

concrete saw A power saw used, for example, to cut concrete in order to remove damaged sections of pavement or to groove the surface to create a control joint.


concrete saw

concrete slump test A test to determine the plasticity of concrete. A sample of wet concrete is placed in a cone-shaped container 12″ high. The cone is removed by slowly pulling it upward. If the concrete flattens out into a pile only 4″ high, it is said to have an 8″ slump. This test is done on the job site. If more water is added to the concrete mix, the strength of the concrete decreases and the slump increases.

concurrent insurance Insurance under two or more policies that are exactly alike in their terms and conditions, even though they might be different in the dollar amounts of coverage or the dates the policies begin. (Nonconcurrent insurance differs in the terms and conditions as well.) This condition can complicate the collection process for contractors.

condenser The heat exchanger in a refrigeration system that removes heat from the high pressure refrigerant gas and transforms it into a cool liquid.

condensing unit In a refrigeration system, the mechanism that pumps vaporized refrigerant from the evaporator, compresses and liquefies it, and returns it to the refrigerant control. Includes the compressor, condenser, condenser fan motor, and controls.

conditioned air Building air whose temperature and relative humidity is controlled.

conditions of the contract A document detailing the rights, responsibilities, and relationships of the parties to the contract for construction.

condominium A legal system by which individual units of real property, such as apartments, stores, or offices, may be owned separately. Each unit owner obtains all the rights incidental to ownership of real property, and shares with the other owners rights to the common areas in the building, facilities, or land of the condominium.

conductive flooring Flooring designed to prevent electrostatic buildup and sparking. Typical uses include floors in computer areas and hospital operating rooms.

conductivity The rate at which heat is transmitted through a material.

conductor **1.** Any substance that can serve as a medium for transmitting light, heat, or sound. **2.** In electricity, a wire or cable that can carry an electric current. **3.** A pipe that leads rainwater to a drain.


conductor

conduit (cable conduit) **1.** A pipe, tube, or channel used to direct the flow of a fluid. **2.** A pipe or tube used to enclose electric wires to protect them from damage.

conduit (cable conduit)

conduit body The portion of a conduit or tubing system that makes the interior of the system accessible at a junction or terminal point.

confidence level The probability **1.** that results will be equal to or more favorable than the amount estimated or quoted; **2.** that the decision made will achieve the desired results; or **3.** that the stated conclusion is true. *Note:* Confidence level may also be expressed as “equal to or less favorable.” If that is the case, it should be so noted. Without such as note, the definition shown is assumed.*

confidentiality agreement A legal document that allows the release of trade secret information to physicians and others who may need this information to protect workers from danger or to treat an exposed worker.

conglomerate A rock deposit consisting of stones of varying sizes naturally cemented together as a natural concretion.

connected load The total load, as measured in watts, that is connected to an electric supply system if all lights and equipment are turned on.

consequential damages Losses that do not flow directly from the actions of the defendant, but rather are the result of special or remote circumstances relating to those actions.

conservation In the context of historic buildings, efforts to bring old building finishes and features to a condition as close as possible to their original state when new. Conservation also involves planning and carrying out maintenance practices that will ensure the best appearance and condition of the building and its features for as long as possible.

conservation easement An easement restricting a land owner to land uses that are compatible with long-term conservation and environmental values.

consistency A reference to the relative mobility or plasticity of freshly mixed concrete or mortar, as measured by a slump test for concrete, and by a flow test for mortar and grout.

consistometer A device for measuring the firmness or consistency of concrete, mortar, grout, plaster, etc.

console **1.** A control station with switches and gauges to govern the operation of mechanical, electrical, or electromechanical equipment. **2.** An ornamental bracket-like member used to support a cornice.

consolidated formation Soil strata that may have been subjected to glacial or other consolidating loads in the geological past.

consolidation **1.** Compaction of freshly poured concrete by tamping, rodding, or vibrating to eliminate voids and to ensure total envelopment of aggregate and reinforcement. **2.** Compaction of soil in an embankment to achieve a higher bearing strength.

constant-voltage transformer A transformer designed to minimize or eliminate the variations in standard line voltage and to produce an unchanging voltage, as required by computers and some instrumentation.

constant-wattage ballast An efficient lamp ballast that provides high power factor by minimizing the effects of voltage variations.

constructability The input of construction knowledge and expertise throughout the planning, design, procurement, and field operations to improve the means and methods of improving the design intent.

constructability review The practice of peer reviewing the plans and specifications prior to issuing for bid with the intent of correcting errors, omissions, inconsistencies, or discrepancies.

construction administrator One who oversees the fulfillment of the responsibilities of all parties to the contract for construction, for the primary benefit of the owner. In the typical project, construction administration is usually provided by the design professional. However, the owner may employ a separate professional entity for this purpose.

construction change A change allowed to the contractor for the consequences of an owner failing to perform certain obligations in a contract, where such failure causes extra cost and schedule for the contractor. Examples include overinspection by the owner, the owner's failure to grant legitimate schedule extensions, or the owner's failure to coordinate other contractors and subcontractors on the job site.

construction change directive (CCD) An alternate mechanism for directing the contractor to perform additional work to the contract when time and/or cost of the work is not in agreement between the owner and contractor performing the work.

construction cost The sum of all costs, direct and indirect, inherent in converting a design plan for material and equipment into a project ready for start-up, but not necessarily in production operation; the sum of field labor, supervision, administration, tools, field office expense, materials, equipment, and subcontracts.*

construction documents The written specifications and drawings that provide the requirements of a construction project.

construction drawings The portion of the contract documents that gives a graphic representation of the work to be done in the construction of a project.

construction-grade lumber Good quality lumber that is generally free of defects.



construction joint

construction joint The interface or meeting surface between two successive pours of concrete.

construction management **1.** Project management as applied to construction. **2.** A professional service that applies to effective management techniques to the planning, design, and construction of a project from inception to completion for the purpose of controlling time, cost, and quality, as defined by the Construction Management Association of America (CMAA).*

construction manager One who directs the process of construction, either as the agent of the owner, as the agent of the contractor, or as one who, for a fee, directs and coordinates construction activity carried out under separate or multiple prime contracts.

construction manager-at-risk (CMAR) A project-specific delivery method that is suited for medium to large capital or renovation projects. CMAR provides technical assistance to the designer during the design phase, has a cost-capping feature, and allows construction to start before design documents are 100% complete. The CMAR contracts directly with subcontractors, fabricators, and material suppliers.

construction progress Construction progress is monitored and reported as percent complete. Actual work units completed are measured against the planned work units for each applicable account in the bill of materials or quantities. Usually reported against individual accounts by area and total project.*



construction wrench

construction wrench A wrench with a handle and jaw at one end for holding or turning fasteners, pipes and fittings. The other end is pointed and is used to align mating holes in steel construction.

constructive change A change to a contract resulting from conduct by the owner that has the effect of requiring the contractor to perform work different from that presented in the contract.

constructor One who is in the business of managing the construction process. A contractor is a constructor who is acting under the terms of a contract for construction.

consultant A person (or organization) with an area of expertise or professional training who contracts to perform a service.

consulting engineer A licensed engineer, employed to perform specific engineering tasks.

consumables Supplies and materials used up during construction. Includes utilities, fuels and lubricants, welding supplies, worker's supplies, medical supplies, etc.*

contact adhesive (dry-bond adhesive) A bonding agent that is applied to two surfaces and allowed to dry before being pressed together.

contact pressure The pressure or force that a footing and the structure it supports exerts on the soil below.

containment berm A physical barrier used to keep liquids from running outside of a protected area.

containment box A temporary container for hazardous liquid spills.

contemporaneous documentation Actual project invoices, plans, and specifications, used to document the outlay of capital by a particular taxpayer for a particular construction project. Generally considered the best supporting documentation for a quality cost segregation study.

contiguous Adjacent and touching properties.

contingency An amount included in the construction budget to cover the cost of unforeseen factors related to construction.

contingency allowance A specified sum included in the contract sum to be used at the owner's discretion, and with his approval, to pay for any element or service that was unforeseen or that is desirable but not specifically required of the contractor by the construction documents.

continuous beam A beam supported at three or more points, and thus having two or more spans.



continuous beam

continuous footing A concrete footing supporting a wall or two or more columns. The footing may vary in depth and width.



continuous footing

continuous girder A girder supported at three or more points.

continuous header Wood frame construction in which the top plate is replaced by a double member, such as a 2″ × 8″ on edge, that acts as a lintel over all wall openings.

continuous rating The constant load that a device can carry at rated primary voltage and frequency without damaging or adversely affecting it.

continuously reinforced pavement A longitudinally reinforced concrete pavement with no intermediate transverse expansion or contraction joints.

continuous span A rigid span extending over three or more supports so that bending movements are transmitted from one segment to the next.

continuous waste and vent A single pipe, the upper portion of which is a vent, while the lower portion functions as a waste drain.

contour line A line on a map or drawing indicating a horizontal plane of constant elevation. All points on a contour line are at the same elevation.

contract An agreement between two parties to perform work or provide goods, including an agreement or order for the procurement of supplies or services.

contract change An authorized modification to terms of a contract. May involve, but is not limited to **1.** a change in the volume or conditions of the work involved; **2.** the number of units to be produced; **3.** the quality of the work or units; **4.** the time for delivery; and/or **5.** the consequent cost involved.*

contract completion date The date established in the contract for completion of all or specified portions of the work. This date may be expressed as a calendar date or as a number of days after the date for commencement of the contract time is issued.*

contract dates The start, intermediate, or final dates specified in the contract that impact the project schedule.*

contract documents All the written and graphic documents concerning execution of a particular construction contract. These include the agreement between the owner and contractor, all conditions of the contract including general and supplementary conditions, the specifications and drawings, any changes to the specifications and drawings, any changes to the original contract, and any other items specifically itemized as being part of the contract documents.

contract for construction An agreement between owner and contractor whereby the contractor agrees to construct the owner's project in accordance with the contract documents, within a specified amount of time, and for consideration to be paid by the owner as mutually agreed.

contracting officer The representative of a government agency with authority to bind the government in contract matters.

contracting officer's decision The contracting officer's final ruling regarding a properly submitted claim.

contraction joint (control joint) A formed, sawed, or tooled groove in a concrete structure. The purpose of the joint is to create a weakened plane and to regulate the location of cracking resulting from the dimensional change of different parts of the structure.



contraction joint (control joint)

contract modification Any unilateral or bilateral written alteration of the contract in accordance with the governing regulations and contract clauses.

contractor A constructor who is a party to the contract for construction, pledged to the owner to perform the work of construction in accordance with the contract documents.

contractor's option As laid out in the contract documents, the ability of the contractor to select predetermined materials, methods, or systems, at his or her option, with no change in the contract sum.

contractor's qualification statement A statement of the contractor's qualifications, experience, financial condition, business history, and staff composition. This statement, together with listed business and professional references, provides evidence of the contractor's competence to perform the work and assume the responsibilities required by the contract documents.

contract price The monies payable by the owner to the contractor under the contract documents as stated in the agreement.*

contract sum An amount representing the total consideration in money to be paid the contractor for services performed under the contract for construction.

contributory negligence A term used to describe legal responsibility for an error or fault by one or more parties who have allegedly contributed in whole or in part to a loss or damage suffered by another party as a result of a specific occurrence.

control joint Grooves manually made on concrete flooring to help control where the concrete should crack.

controlled fill A backfilling or embankment operation in which the moisture content, depth of lift, and compaction equipment are closely regulated by specification and inspection.

controller An electrical, electronic, pneumatic, or mechanical device designed to regulate an operation or function.

convection The movement of a gas or liquid upward as it is heated and downward as it is cooled. The movement is caused by a change in density.

conversion **1.** The change in use of a building, as from a warehouse to residential units, that may require changes in the mechanical, electrical, and structural systems. **2.** The sawing or milling of lumber into smaller units.

conveyance An instrument or deed by which a title of property is transferred.

conveyors Frame-mounted continuous belts that move aggregate, earth, or concrete.

coolant A fluid used to transfer heat from a heat source to a heat exchanger, where the heat is removed and the coolant is usually recycled.

cooling load The amount of air conditioning that would be required to keep a building at a specified temperature during summer months (usually 78°F), regardless of variations in outside temperature.

cooling tower An outdoor structure, frequently placed on a roof, over which warm water is circulated for cooling by evaporation and exposure to the air. A *natural draft cooling tower* is one in which the airflow through the tower is due to its natural chimney effect. A *mechanical draft tower* employs fans to force or induce a draft.



cooling tower

cool roof A roof made of materials (typically light in color) that have a high thermal emittance and solar reflectance. Cool roofs can substantially reduce a building's cooling load.

coordinator The device on a pair of double doors that permits the doors to close in the correct sequence. If the door with the overlapping astragal closed first, the other door would strike the astragal and not close properly.

cope **1.** To cut the end of a molding to match the contour of the adjacent piece. **2.** To cut structural steel beams so that they fit tightly together.

coping The protective top member of any vertical construction such as a wall or chimney. A coping may be masonry, metal, or wood, and is usually sloped or beveled to shed water in such a way that it does not run down the vertical face of the wall. Copings often project out from a wall with a drip groove on the underside.



coping

copper A pure metal that is ductile, malleable, nonmagnetic, and high in electrical and thermal conductivity. Used for roofing in many historic buildings, copper is also a primary material in piping and electrical wiring.

copper fitting In piping, an elbow, tee, reducer, or other fitting made of wrought copper, cast brass, or bronze.

copper roofing A roof covering made of copper sheets joined by weatherproof seams.

copper roofing

corbel A course or unit of masonry that projects beyond the course below. A corbel may be used entirely for decoration or for a ledge to support a load from above.



corbel

core **1.** The interior structure of a hollow-core door. **2.** A cylindrical sample of concrete or rock extracted by a core drill. **3.** The void in a concrete masonry unit. **4.** The center layer of a sheet of plywood. **5.** The vertical stack of service areas in a multistory building. **6.** The central part of an electrical winding. **7.** Metal support for a handrail. **8.** The rubble filling in a thick masonry wall. **9.** The center material between facing papers in gypsum wallboard.

coreboard (battenboard) A manufactured board with a wood fiber or wood chip center and bonded veneer faces on both sides.

cored beam **1.** A precast concrete beam with longitudinal holes through it. **2.** A beam that has had core samples removed for testing.

core drill **1.** A drill used to remove a core of rock or earth material for analysis. **2.** The drilling of a hole through a concrete floor, wall, or ceiling for running pipe or conduit.

core gap An open joint extending through, or partly through, a plywood panel, that occurs when core veneers are not tightly butted. When center veneers are involved, the condition is referred to as a *center gap*.

coring The core drilling of a sample of rock, soil, or concrete to obtain a test sample.

corkboard Compressed and baked granulated cork used in flooring and sound conditioning and as a vibration absorber.



corner bead

cork tile Tile made from cork particles bound and pressed into sheets and covered with a protective wearing finish.

corner bead An L-shaped, light-gauge metal strip used to finish drywall and plaster wall angles and corners.

corner brace The diagonal braces let into the studs of wood frame structures for reinforcement.



corner brace

corner reinforcement **1.** The reinforcement in the upper corners of a metal door frame. **2.** The metal angle strip used at the corners of plaster or gypsum board construction. **3.** The bent reinforcing rods embedded at the corners of a cast-in-place concrete wall.

corner return block A concrete masonry block with solid faces on its sides and on one end. Used at the end of a run of blocks.

cornice **1.** An ornamental molding of wood or plaster that encircles a room just below the ceiling. **2.** An ornamental topping that crowns a structure. **3.** An exterior ornamental trim at the meeting of the roof and wall. This type of cornice usually includes a bed molding, a soffit, a fascia, and a crown molding.



cornice

corporation An association of individuals established under certain legal requirements. A corporation exists independently of its members, and has powers and liabilities distinct and apart from its members.

corridor A long, interior passageway, usually with doors opening to rooms, apartments, or offices and leading to an exit.

corrosion The oxidation or eating away of a metal or other material by exposure to chemical or electrochemical action such as rust.

corrugated aluminum Sheet aluminum that has been rolled into a parallel wave pattern to impart stiffness.

corrugated fastener A small, wavy, steel fastener with one edge sharpened. The fastener is driven into two pieces of wood, bridging the joint in order to hold them together.

corrugated metal Sheet metal that has been rolled into a parallel wave pattern for stiffness and rigidity.



corrugated metal

corrugated roofing Corrugated metal or fiberglass mounted on rafters as sheet roofing.



corrugated roofing

corrugated siding Siding made of sheet metal or asbestos-cement composition board and used for siding on factories and other nondecorative buildings. By corrugating the material, the structural strength is increased.



corrugated siding

cost The total expenditure in dollars approved after the completion of a project.

cost analysis A historical and/or predictive method of ascertaining for what purpose expenditures on a project were made and utilizing this information to project the cost of a project as well as costs of future projects. The analysis may also include application of escalation, cost differentials between various localities, types of buildings, types of projects, and time of year.*

cost engineer An engineer whose judgment and experience are utilized in the application of scientific principles and techniques to problems of estimation; cost control; business planning and management science; profitability analysis; project management; and planning and scheduling.*

cost estimate A prediction of quantities, cost, and/or price of resources required by the scope of an asset investment option, activity, or project. As a prediction, an estimate must address risks and uncertainties. Estimates are used primarily as inputs for budgeting, cost or value analysis decision making in business, asset and project planning, or for project cost and schedule control processes. Cost estimates are determined using experience and calculating and forecasting the future cost of resources, methods, and management within a scheduled timeframe.*

cost-plus-fee agreement An agreement between an owner and the contractor or a design professional that provides for payment of all costs associated with completion of their duties. This includes direct and indirect costs as well as a fee for services, which may be a fixed amount or a percentage of costs.

cost plus fee with guaranteed maximum price (CPF-GMP) A delivery method similar to CPF, except that it has a cost-capping feature that reduces the owner's risk. CPF-GMP is more popular than CPF for projects of higher value.

cost-reimbursement contract A type of contract in which the pricing arrangement involves the payment of allowable costs incurred by the contractor during performance.

cost segregation A process of identifying assets within a larger construction project and using cost estimating techniques that allocate costs to individual items of property, which can then be classified for depreciation purposes (e.g., land improvements, buildings, equipment, furniture and fixtures, etc.). The underlying incentive for building owners is the significant acceleration of tax benefits (depreciation deductions) resulting in improved current after-tax cash flow.

cotter pin A split metal pin that, when pushed through a hole in a shaft or a bolt (and having the ends bent), prevents parts or nuts from vibrating loose.



cotter pin

counter **1.** A person or device that keeps a tally of the occurrences of some event, such as the number of loads of fill. **2.** A long, flat surface over which sales are transacted at a store or business. **3.** A flat work surface in a kitchen.

counterbrace A diagonal brace that balances the force from another brace as part of a web network in a truss.

counterflashing A thin strip of metal frequently inserted into masonry construction and bent down over other flashing to prevent water from running down the masonry and behind the upturned edge of the base flashing.

countersink **1.** A conical depression cut to receive the head of a flat-head bolt or screw for driving it flush with the surrounding surface. **2.** A bit used to cut a conical depression.

countersunk rivet A rivet used in countersunk holes.

countertop The level surface material covering cabinetry, such as in a kitchen or bath.

counterweight A weight that balances another weight, for example, a sash weight that balances a window sash, or a large weight that balances a lift bridge.

couple Two equal, opposite, and parallel forces that tend to produce rotation. The movement equals the product of one force times the perpendicular distance between the two.

coupler A metal clamplike device used to join and extend tubular frames and braces in barricades or scaffolding.

coupling A fitting for joining two pieces of pipe.

course **1.** A horizontal layer of bricks or blocks in a masonry wall. **2.** A row or layer of any type of building material, such as siding, shingles, etc.



course

coursed masonry Any masonry units laid in regular courses, as opposed to rough or random rubble.



coursed masonry

coursed rubble Masonry construction consisting of roughly dressed stones of mixed sizes and shapes, with small stones used to fill irregular voids.



coursed rubble

coursing joint **1.** The horizontal mortar joint between two courses of masonry. **2.** In an arch, the arched joint between two curving courses.

court An open, unobstructed space surrounded on at least three sides by walls or buildings.

court deed A deed executed by a court official conveying title to a property purchaser following judicial foreclosure, often called a *sheriff's deed.*

cove A concave-shaped surface where a ceiling and wall meet.

cove lighting Indirect lighting in which the fixtures are behind a molding or valance, and thus out of sight.

covenant A term used to describe one or more specific points of agreement that may be set forth in a contract.

cover **1.** That which envelops or hides, such as a protecting cover of paint. **2.** That part of a tile or shingle that is overlapped by the next course. **3.** The minimum thickness of concrete between the reinforcing steel and the outer surface of the concrete.

coverage **1.** The nominal square feet of area that a can of stain or paint can be expected to cover. **2.** The amount of surface that may be covered by a unit, such as a bundle, square, or ton of building material. **3.** An insurance policy, or the dollar protection that policy provides. The amount of protection depends on many factors, including the type of insurance, amount of insurance purchased, policy limits, and exclusions. **4.** Dependable estimates or firm bids for portions of a construction project.

coving **1.** Concave molding such as that used at the intersection of a wall and the ceiling. **2.** The outward curve of an exterior wall to meet the eaves. **3.** The curving sides of a fireplace that narrows at the back.

cradle **1.** A scaffold that is suspended outside the roof or top of a structure. **2.** A U-shaped support for pipe or conduit.

cradle-to-grave analysis A methodology used to determine the energy, environmental, and waste implications of a product, material, or system. Analysis begins at the point of raw material extraction and includes refinement or fabrication, transportation, use, and eventual reuse or disposal.

cramp **1.** A device for supporting a frame in place during construction. **2.** A U-shaped metal bar used to lock adjacent blocks of masonry together, as in a parapet wall.

crane A machine for raising, shifting, or lowering heavy weights, commonly by means of a projecting swinging arm.

craneway Steel or concrete column and beam supports and rails on which a crane travels.

crank A twist or bend in a reinforcing bar.

crawler tractor A powered earth-moving vehicle that moves on continuous, segmented, cleated treads or tracks. The tracks provide low ground-bearing pressure and a high level of mobility and power.



crawler tractor

crawling A defect in the application of paint whereby the paint film raises, separates, or breaks apart. Usually caused by painting over a slippery or glassy surface, or from applying heavy or elastic coatings over a hard or brittle surface.

crawl space **1.** In a building or portion of a building without a basement, the accessible space between the surface of the ground and the bottom of the first floor joists, with less-than-normal headroom. **2.** Any interior space of limited height designed to permit access to components such as ductwork, wiring, and pipe fittings.

crawl space vents A system of openings in a crawl space to allow for an air exchange that will reduce moisture and harmful gas buildup.

creep **1.** The slow but continual permanent deformation of a material under sustained stress. **2.** The very slow movement of rock or soil under pressure. **3.** Gradual deformation of a roofing membrane due to thermal stress.

crescent truss A truss in which the upper and lower chords are curved in the same direction, but with different radii of curvature, so that they meet at the ends, thus giving the assembly a crescent-shaped appearance.

crew tasks Tasks done by the crew that combine the performance of different individuals, versus a single individual. Each crew member performs a specific function to complete the overall task.

crib **1.** A boxed-in area, the sides of which may be an open lattice, often filled with stone, and used as a retaining wall or support for construction above. **2.** A retaining framework lining in a shaft or tunnel.



crib

cribbing A system of open boxes built with heavy timbers and filled with rocks or pervious fill. Used as a retaining wall.

cribwork An open construction of beams, at the face of an embankment, the alternate layers of which project to provide lateral stability, prevent erosion, and resist thrust or overturning.



cricket

cricket A secondary roof built on top of an existing roof designed to divert water drainage away from vertical protrusions.

crimp A sharp bend in a metal sheet, as in the joint in metal roofing.

crimped wire Wire that has been deformed or bent to improve its bonding effectiveness when used to reinforce concrete.

cripple **1.** In construction framing, members that are less than full length, for example, studs above a door or below a window. **2.** In roofing, a bracket secured at the ridge of a pitched roof to carry the scaffold for roofers.

cripple jack rafter A short supporting beam that extends from a valley rafter to a hip rafter.

critical angle The maximum angle or rise of a stair or ramp before it becomes unsafe for public use. For stairs the angle is 50°; for ramps, it is 20°.

critical delay An event that results in the overall project completion occurring later than originally planned.

critical path A term used to describe the order of events (each of a particular duration) that results in the least amount of time required to complete a project.

critical path method (CPM) A system of construction management that involves the complete planning and scheduling of a project, and the development of an arrow diagram showing each activity, its appropriate place in the timetable, and its importance relative to other tasks, and the complete project.

critical task A task or activity that lies on the critical path of the schedule, which if delayed will delay the completion of the project.

cross-bar In a grating or grill, one of the bars perpendicular to the primary bar.

cross-beam (brow post) **1.** A large beam that spans two walls or sides of a structure, frequently holding them together. **2.** A brace between opposite whalings or sheeting in an excavation. **3.** In bridge construction, a beam that spans the trusses and supports the stringers or deck.

cross-bracing (cross-bridging) Diagonal braces placed in pairs that cross each other.



cross-bracing (cross-bridging)

cross-connection **1.** A piping connection between two otherwise separate piping systems, one of which contains potable water, and the other water of unknown or questionable safety. **2.** In a fire protection system, a connection from a Siamese fitting to a standpipe or sprinkler system.

crosscut Cutting wood at a right angle to the grain.

crosscut saw A saw with its teeth filed and set to cut across the grain of a piece of wood.

cross-furring (brandering, counterlathing) Strips or slats attached to the lower edge of joists to which plastering lathing is nailed.



cross-furring (brandering, counterlathing)

cross-garnet hinge (T-hinge) A hinge that is shaped like the letter T, with the head attached to the door frame and the long part fastened to the door.

cross-laminated Laminated wood members in which the grain of some layers is at a right angle to the grain of other layers.

crosslap joint A wood joint in which two pieces are each cut to half their thickness at the overlap, so that the total thickness of the system does not change.

crossover **1.** In an auditorium, a walkway that is parallel to the stage and connects with the aisles. **2.** A pipe fitting used to bypass a section of pipe. **3.** A connection between two piping systems.

cross peen hammer A hammer with one face flat and the other a wedge. Used to break or work hard surfaces.

cross-runner In a suspended or T-bar ceiling, one of a series of short pieces that span between the long runners.



cross-runner

cross-section A diagram or illustration showing the internal construction of a part or assembly if the front portion were removed.

crown **1.** An ornamental architectural topping. **2.** The central top section of an arch or vault. **3.** The high point in the center of a road that causes water to flow to the edges. **4.** The top of a tree or flowering plant. **5.** In plumbing, the section of a trap that changes direction from vertical to horizontal. **6.** The convex curvature or camber in a beam.

crown

crown course **1.** The top row of a roofing material. **2.** The row that actually covers the ridge.

crown rafter The central common rafter in a hip roof.

crushed gravel Gravel that has been crushed and screened so that substantially one face of each particle is a fractured face.

crushed stone Stone crushed and screened so that substantially all faces result from fracturing.

crystallization As applied to absorption chillers, the precipitation of salt crystals from the absorbent. This causes a slushlike mixture that plugs fluid passages within the chiller and renders it inoperable.

cube strength An analytical strength test of Portland cement in which a standard-size concrete cube is loaded to failure.

cul-de-sac A dead-end street that ends in an enlarged turn-around area.

culvert A transverse drain under a roadway, canal, or embankment other than a bridge. Most culverts are fabricated with materials such as corrugated metal and precast concrete pipe.



culvert

cumulative batching The weighing of a batch of material by adding the components successively to the same container and balancing the scale at each new total weight.

curb cock (curb stop) A control valve that is placed in the water supply pipe that runs from a water main in a street to a building.

curb form **1.** A form used with a curb machine for extruding concrete curbs to produce a desired shape and finish on the curb. **2.** A reusable metal form for cast-in-place concrete curbs.

curb level The elevation of the curb grade in front of a building, as measured at the center of its street frontage.

curb machine A self-propelled, hand-operated machine for extruding bituminous or concrete curbs.

curb plate **1.** The wall plate at the top of a circular or elliptical structure. **2.** The plate on which the upper rafters of a curb roof rest.

curb roof (gambrel roof, mansard roof) A roof with the slope divided into two pitches on each side.

cure **1.** A change in the physical and/or chemical properties of an adhesive or sealant when mixed with a catalyst or subjected to heat or pressure. **2.** To maintain the proper moisture and temperature after placing or finishing concrete to assure proper hydration and hardening.

curing blanket A layer of straw, burlap, sawdust, or other suitable material placed over fresh concrete and moistened to help maintain humidity and temperature for proper hydration.

curing membrane Any of several kinds of sheet material or spray-on coatings used to temporarily retard the evaporation of water from the exposed surface of fresh concrete, thus ensuring a proper cure.

curling A change in the shape of wood, such as straightness or flatness, due to drying or temperature differences.

current The movement of electrons through a conductor. Measured in amperes.

current assets Cash and other assets that will be consumed or converted into cash within one year.

current-carrying capacity (ampacity) The maximum rated current, measured in amperes, that an electrical device is allowed to carry. Exceeding this limit could lead to early failure of the device or create a fire hazard.

current density The current flowing to or from a unit area of an electrode surface.

current liabilities Liabilities to be paid within one year.

current-limiting fuse A fuse that acts as a protective device by interrupting currents in its current-limiting range and guarding against overcurrents in an electrical system.

current transformer A transformer generally used to convert a current supplied at one current rate to another current rate.

curtained doorway A doorway consisting of two overlapping sheets of plastic over a door frame, each attached to the frame at the top and down one side. Allows worker entry into and from an area while minimizing the air movement between rooms.

curtain wall The exterior closure or skin of a building. A curtain wall is nonbearing and is not supported by beams or girders.



curtain wall

cushion **1.** Wood placed so as to absorb a force by acting as a buffer or by transmitting it over a larger area. **2.** A stone placed to accept and spread out a vertical load. **3.** An isolating pad against shock and vibration for glass, machinery, equipment, etc.

cut **1.** Material excavated from a construction site. **2.** A term for the area after the excavated material has been removed. **3.** The depth of material to be removed, as in a 5′ cut. **4.** To reduce a cost item.

cut and fill An operation commonly used in road building and other rock and earthmoving operations in which the material excavated and removed from one location is used as fill material at another location.



cut and fill

cutaway drawing A drawing of an area or object that shows what would be seen if a slice could be made into the area or object and a piece removed. *See also* **cross-section**.

cutback asphalt A bituminous roof coating or cement that has been thinned with a solvent so that it may be applied without heat to roofs or other areas that need sealing or cementing. Also used for dampproofing concrete and masonry.

cut nail (clasp nail) A hard, wedge-shaped nail used for nailing hardwoods such as oak flooring.



cut nail (clasp nail)

cutoff **1.** A wall or barrier placed to minimize underground water percolation or flow. A cutoff is often used at the inlet and outlet of culverts. **2.** The design elevation at which the tops of driven piles are cut.

cutout **1.** A mechanical or electrical device used to stop a machine when its safe limits have been exceeded. **2.** An opening in a wall or surface for access or other purposes. **3.** A piece stamped out of sheet metal or other sheet material.

cutout box A metal box used in electrical wiring to house circuit breakers, fuses, or a disconnect switch.

cutting in A painting technique used to paint around the edges of an object or area, such as trim or a light fixture.

cybertecture A term coined as the result of development of the "smart" house, which is wired to integrate power and telecommunications into one computer-directed system.

cycle The flow of alternating current as it travels in one direction, then reverses itself and travels in the opposite direction. A 60-cycle circuit completes 60 cycles per second.

cycle time The time required to complete a repetitive operation such as a batch mix or the refill of a toilet tank after flushing.

cylinder lock A lock in which the keyhole and tumbler mechanism are contained in a cylinder or escutcheon separate from the lock case.

cylinder unloaders Automatic devices used to hold open the reciprocating compressor valves of a number of cylinders in order to reduce compressor pumping capacity when not being used to full capacity.

cypress A wood of average strength and very good decay resistance and durability.

D

Abbreviations

d degree; density; penny (nail size)

D deep; depth; diameter; dimensional; discharge

DA discharge air

D/A digital-to-analog

DACS digital alarm communicator system

DBOM design, build, operate, maintain

DCC Digital Command Control

D&CM dressed and center matched

DCV demand-controlled ventilation

D&M dressed and matched

D&MB dressed and matched beaded

D&SM dressed and standard matched

D1S dressed one side

D2S dressed two sides

D2S&CM dressed two sides and center matched

D2S&SM dressed two sides and standard matched

D4S dressed four sides

DAD double acting door

db decibel

DBA a unit of sound level (as from the A-scale of a sound-level meter), doing business as

DB Clg double-headed ceiling

DBG distance between guides

Dbl double

DBT dry-bulb temperature

DC direct current, distribution center

DD design development, device description

DDC direct digital controller

DE digitally enhanced

DEC decimal

DEG degree, degrees

DEL delineation

Demo demolition

Demob demobilization

DEPT department

DER distributed energy resources

DET detached, detail, double end trimmed

DF damage free, direction finder, drainage free, drinking fountain, Douglas fir

dfl Douglas fir-larch

dflct deflection

dfu drainage fixture unit

DGI daylight, disability, or discomfort glare index

DH double-hung

DHW domestic hot water, double-hung window

DIA diameter

Diag diagonal

DIM dimension

DIN Dutch industry normal (German industry standard)

Dis, Disch discharge

Distrib distribution

DIV division

Dk deck

dkg decking

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

DL dead load, deadlight, diesel

DM demand management, document management

DN down

Do ditto

DOC delivery order contract

DOE U.S. Department of Energy

DOE-2 software used to predict the use and cost of energy for different types of buildings

DOT Department of Transportation

DOZ dozen

Dp depth

DP degree of polymerization, dew point, double-pitched, differential pressure

DPC dampproof course

DPST double pole, single throw

Dr, DR dining room, drain, dressing room, driver

DRG drawing

drink drinking

drn drain, drainage

drwl drywall

DS double strength, downspout, drop siding

DSA double strength A grade

DSB double strength B grade

DSGN design

DSIRE Database of State Incentives for Renewables and Efficiency

DT drum trap

DT&G double tongue and groove

DTS digital theater system

Dty duty

DU disposal unit

DUP duplicate

DV displacement ventilation

DVTL dovetail

dwg, DWG drawing

DWV drain waste vent

DX deluxe white, direct expansion

DXF AutoCAD Drawing Interchange Format or Drawing Exchange Format

dyn dyne

Definitions

dabber A soft, round-tipped brush for applying varnish or for polishing and finishing gilding.

dado **1.** The flat-bottomed groove cut into one board (usually across the grain) to receive the end of another. If the groove is cut at the edge of a board, it is called a *rabbet*. **2.** An ornamental paneling above the baseboard of a room finish. **3.** Part of a column between the base and the cap or cornice.

daily allocable overhead The amount of main office overhead per day that is allocated to a delay as calculated using the Eichleay formula.

daily report log A daily report or historical record of the day-to-day events on a construction site, recording weather, temperature, personnel, subcontractors, accidents, visitors, and specific progress. Many states consider this a legal record.

dam The barrier built into the trapway of a toilet that controls the water level in the toilet bowl.

damages A measure of monetary compensation that a court or arbitrator awards to a plaintiff for loss or injury suffered by the plaintiff's person, property, or other legally recognizable rights. *See also* **liquidated damages**.

damp course (damp check, dampproof course) In masonry construction, an impervious course or any material that prevents moisture from passing through to the next course (usually a horizontal layer of material such as metal, tile, or dense limestone).

damper **1.** A blade or louver within an air duct, inlet, or outlet that can be adjusted to regulate the flow of air. **2.** A pivotal cast-iron plate positioned just below the smoke chamber of a fireplace to regulate drafts.



damper

damping **1.** The force that acts to reduce vibrations in the same way that friction acts to reduce ordinary motion. **2.** The gradual dissipation of energy over a period of time.

dampproofing An application of a water-resisting treatment or material to the surface of a concrete or masonry wall to prevent passage or absorption of water or moisture. Can also be accomplished by using an admixture in the concrete mix.



dampproofing

dap A notch made in one timber to fit the end of another.

darby (derby, derby float, derby slicker) A hand float or trowel, about 4′ long, used by concrete finishers and plasterers in preliminary floating and leveling operations. The float is usually made of wood or aluminum and has either one or two handles.



darby (derby, derby float, derby slicker)

dash-bond coat A thick slurry of Portland cement, sand, and water applied to a concrete wall with a brush or whiskbroom to act as a bond for a subsequent plaster coat.

database Part of a computer's software program that contains files and lists of related information organized for quick access. In Building Automation Systems, the database consists of digital and analog point names; descriptions such as temperature set points; and operating information such as programs and passwords.

data center A space that houses a facility's critical computer systems and has specialized protective features, such as backup power, fire suppression, HVAC, and communications.

date of acceptance Date on which the client agrees to final acceptance of the project. Commitments against the authorized funds usually cease at this time.*

date of agreement The date shown on the face of an agreement, or the date the agreement is signed (usually the date of the award).

date of commencement of the work The date established in the *notice to proceed* or, in the absence of such notice, the date of the agreement established by the parties for the work to begin.

date of substantial completion The date when work (or a portion of the work) is certified by the architect to be sufficiently complete as specified in the contract documents. The owner should be able to occupy the work fully or partially.

datum A base elevation to which other elevations are referred.

daub **1.** To rough-coat with plaster. **2.** To rough-coat a stone surface by striking it with a special hammer.

Davis-Bacon Act A federal labor law enacted in 1931 that requires laborers and mechanics (those who do physical work) on federally funded construction projects be paid no less than the local prevailing wages. The Davis-Bacon Act applies to all federally funded contracts over a specified value.

daylight compensation An energy-saving lighting system controlled by a photocell that decreases lamp intensity as daylight increases.

daylight factor A component in calculating the amount of natural outdoor light entering a building.

daylight harvesting Maximizing use of sunlight to illuminate interior building space. Photo sensors are used to measure natural light levels; artificial lighting can be adjusted accordingly.

daylighting Admitting natural light into a space, including distributing light at uniform levels, avoiding glare and reflections, and controlling artificial light to achieve energy and cost savings.

daylight lamp A lamp manufactured with daylight glass. The output is generally 35% less than that from an incandescent lamp.

daylight sensor A device that measures ambient light levels, used to help control lighting levels and conserve energy.

D-cracking The progressive formation of fine hairline cracks in concrete surfaces. In highway pavement these cracks run parallel to joints and edges and cut diagonally across corners. *See also* **D-line crack**.

deactivator A tank containing iron filings, through which hot water is passed to be purged of its active oxygen and other corrosive elements.

dead Refers to a conductor that is not connected to an electrical source.

dead air space Unventilated air space between structural elements. The space is used for thermal and sound insulation.

deadband In HVAC, a temperature range in which neither the heating nor cooling systems are activated.



dead air space

dead band widening system A control system for boilers and furnaces that allows for a wide system dead band, or time delay, from set point. Burners can be shut off and stay on for longer periods of time, with fewer cycles. Avoiding short boiler cycling increases the net system efficiency.

dead bolt The bolt on a type of door lock that must be operated positively in both directions by turning a key or a thumb bolt.

dead end **1.** In stressing a tendon, the end opposite the one to which stress is applied. **2.** In plumbing, a drain line or vent that has been purposely terminated by a cap, plug, or other fitting.

deadening The use of insulating and dampening materials to restrict the passage of sound.



dead end

dead-front Refers to an electrical device in which the front part is insulated from voltage and can be touched without receiving an electric shock.

dead level **1.** The state of being absolutely level, with no pitch or slope. **2.** A grade of asphalt used on a level or nearly level roof.

deadlight A fixed window sash.

dead load A calculation of the weight of a building's structural components, fixtures, and permanently attached equipment (used in designing a building and its foundations).

deadlock A type of door lock employing a dead bolt.

deadman A heavy anchor, such as a concrete block or a log, usually buried underground and used for securing the end of a tie or guy. This device is frequently used with sheeting and retaining walls.

deal In the lumber industry, boards or planks usually more than 9″ wide and 3″ to 5″ thick.



deadman

debarment The formal sanction by the government prohibiting a contractor from receiving contracts as a result of certain proscribed actions including crimes, fraud, etc.

debt service The periodic repayment of loans including interest and a portion of the principal.

decal A design that can be transferred from a special paper onto any of a number of different surfaces.

deceleration The opposite of acceleration. A direction, either expressed or implied, to slow down job progress.*

decenter To lower or remove shoring or centering.

decibel **1.** The standard unit of measurement for the loudness of sound. **2.** In closed-circuit television, a numerical unit used to express the difference in power levels, usually between acoustic or electric signals.

deciduous A term used to describe those trees that shed their leaves annually. Includes most hardwoods and some softwoods.

deck **1.** An uncovered wood platform usually attached to or on the roof of a structure. **2.** The flooring of a building. **3.** The structural system to which a roof covering is applied.



deck

deck curb A curb around the edge of a roof deck or around roof-mounted equipment.



deck curb

decking **1.** Light-gauge, corrugated metal sheets used in constructing roofs or floors. **2.** Heavy planking used on roofs or floors. **3.** Another name for slab forms that are left in place to save stripping costs. **4.** The use of inert material to separate explosive charges.



decking

deck paint A special hard-surface paint that is resistant to abrasive wear and used particularly on decks and porches.

declining balance depreciation A method of computing depreciation in which the annual charge is a fixed percentage of the depreciated book value at the beginning of the year to which the depreciation applies.

decomposition Separation of the scope of work and requirements into smaller, component packages, so that work effort can be more effectively monitored and controlled.*

deconstruction A green building strategy that involves reuse of construction materials salvaged from buildings that are being demolished or remodeled. New building designs may include plans for deconstruction and later reuse of materials.

decontamination chamber A series of rooms separated from one another and from work areas by airlocks. Prevents contamination of sensitive work areas and/or the spread of dangerous substances used in the work area. Commonly used in asbestos abatement.

decorative block A concrete masonry unit manufactured or treated to have a desired architectural effect. The particular effect may be in color, texture, or both.

decoupling Separation of building elements to reduce or eliminate the transfer of sound, heat, or physical loads from one element to the other.



decorative block

deductible The dollar amount that the policyholder agrees to pay in the event of a loss. The insurance company pays the amount over the deductible, up to the limit of the policy.

deduction The amount of money deducted from the contract sum by a change order.

deductive alternate An alternative bid that is lower than that bidder's base bid.

deductive change A change resulting in a reduction in the contract price.

deed **1.** A legal document giving an individual rights or ownership to a property. **2.** A document that forms part of a contract and which, when signed by both parties, legally commits the contractor to perform the work according to the contract documents, and commits the client to pay for the work.

deed in lieu of foreclosure Refers to a deed given by a defaulting property owner to a creditor so that the lender does not have to proceed with foreclosure. Following a deed in lieu, the creditor may not be able to sue for a deficiency judgment, and the debtor may preserve credit reputation.

deed restriction A restriction on the use of a property as set forth in the deed.

deep-seal trap (antisiphon trap) A U-shaped plumbing trap having a seal of 4″ or more.



deep-seal trap (antisiphon trap)

default An omission of, or failure to perform, a contractual duty.

defect Any condition or characteristic that detracts from the appearance, strength, or durability of an object.

defective Work that is unsatisfactory, faulty or deficient, or does not conform to the contract documents, or does not meet the requirements of any inspection, reference standard, tests or approval referred to in the contract documents.*

defective specifications Specifications and/or drawings that contain errors, omissions, and/or conflicts that affect or prevent the contractor's performance of the work.*

defective work (deficiencies) Work that does not comply with the requirements of a contract.

defendant An individual against whom a claim or action is brought.

defense An explanation or reason why a person or entity should not be held legally responsible (liable) as a result of claims made against them by another party.

deflected tendons (draped tenon) Tendons in a concrete member that have a curved trajectory with respect to the gravity axis of the member.

deflection **1.** The bending of a structural member as a result of its own weight or an applied load. **2.** The amount of displacement resulting from this bending.

deflection angle In surveying, a horizontal angle as measured from the prolongation of the preceding transit line to the next line.

deflection limitation Maximum allowable deflection—dictated by the bending limit of the material under the required design load.

deflectometer An instrument for measuring the degree to which a transverse load causes a beam or other structure to bend.

deformation A change in the shape or form of a structural member that does not cause its failure or rupture.



deformed bar (deformed reinforcing bar)

deformed bar (deformed reinforcing bar) A reinforcing bar manufactured with surface deformations to provide bonding strength when embedded in concrete.

deformed reinforcement In reinforced concrete, reinforcement comprising bars, rods, deformed wire, welded wire fabric, and welded deformed wire fabric.

degradation Deterioration of a painted surface by heat, light, moisture, or other elements.

degree 1/360th of the circumference of a circle or a round angle.

degree-day A unit of measure for heating-fuel consumption. The unit is used to specify the nominal heating load of a building in winter. One degree-day is equal to the number of degrees, during a 24-hour day, that the mean temperature is below 65° F, which is the *base temperature* in the United States.

dehumidifier A device for removing water vapor from the air.

delamination Separation of plies of materials, usually due to failure of the adhesive. May occur, for example, in veneers, roofing, and laminated wood beams.

delay An event or condition that results in work activity starting, or the project being completed, later than originally planned.

deliquescence The absorption of moisture from the air by certain salts in plaster or brick, resulting in damp spots that appear darker than the surrounding material.

deliverable **1.** A report or product of one or more tasks that satisfy one or more objectives and must be delivered to satisfy contractual requirements. **2.** Another name for products, services, processes, or plans created as a result of doing a project. A project typically has interim as well as final deliverables.*

delivery Transfer or handover of a product from one party to another.*

delivery hose The hose through which concrete, mortar, grout, or shotcrete is pumped.



delivery hose

delivery order contract (DOC) A comprehensive procurement system for organizations to obtain construction services that is designed to lessen construction response time, reduce in-house workload and enhance quality control.

deluge sprinkler system A dry-pipe sprinkler system particularly well suited for areas that may experience temperatures below freezing. The system is actuated by a heat- or smoke-detection device, which then turns a valve to admit the water.



deluge sprinkler system

demand The electric load integrated over a specific interval of time, usually expressed in watts or kilowatts.

demand-controlled ventilation The adjustment of ventilation in response to actual occupancy and CO_2 readings.

demand factor In an electrical system, the ratio of the maximum demand to the connected load.

demand load The actual amount of electrical load on a circuit on any given time.

demand management Control of the load, or demand for electrical power, generally in keeping with utility rate fluctuations.

demand response Power management equipment that reduces a facility's power consumption during peak demand periods.

demolition The intentional destruction of all or part of a structure.

demountable partition (relocatable partition) A non-load-bearing wall made of prefabricated sections that can be readily disassembled and relocated. These partitions may be full height or partial height.



demountable partition (relocatable partition)

dense-graded aggregate Aggregate sized so as to contain a minimum of voids, and therefore to have the maximum weight when compacted.

densified impregnated wood (compregnated wood, compressed wood, resin-treated wood) Laminated wood that has been impregnated with resins and compressed to greatly increase its density and strength.

density **1.** In urban planning, the number of people living within an acre (or sometimes a square mile) of land. **2.** The ratio of the mass of a specimen of a substance to the volume of the specimen; the mass per unit volume of a substance. **3.** The closeness of pile yarn; the amount of pile packed into a given area of carpet, usually measured in ounces per square yard. **4.** The number of lots or building units per acre of land as determined by the zoning bylaw having jurisdiction.

density control The testing of concrete used in a structure to maintain the specified density.

dentil band A wood molding installed to create the effect of a series of dentils.

dentils Square, toothlike blocks used as ornaments under a cornice.



dentils

Department of Health and Human Services The federal agency responsible for establishing health and safety standards for the protection of persons.

Department of Labor The federal agency that oversees all laws associated with hiring, employing, and protecting workers.

Department of Transportation (DOT) The federal agency responsible for regulating the safe transportation of goods and materials within the United States.

deposited metal The filler metal placed during welding.



deposited metal

deposit for bidding documents A deposit required from the bidder for each set of the plans, specifications, and other bidding documents for a contract. Normally the deposit is returned to the bidder upon return of the documents in good condition and within a specified time.

deposition A formal method of obtaining information relevant to a lawsuit by verbally asking an individual questions under oath prior to trial.

depository A location where bids are received by an awarding authority.

depot **1.** A storehouse, warehouse, or transfer station. **2.** A railroad or bus station for ticketing, sheltering, transferring, and shipping passengers and freight.

depreciation The allocation of a part of the cost of a property, plant, or equipment item (that has a limited useful life) over its estimated useful life.

depreciation factor The ratio of initial illumination on an area to the present illumination of the same area, used in lighting calculations to account for depreciation of lamp intensity and reflective surfaces.

derrick A device consisting of a vertical mast and a horizontal or sloping boom operated by cables attached to a separate engine or motor. The device is used for hoisting and moving heavy loads or objects.



derrick

descriptive specification A type of specification that provides a detailed description of the required properties of a product, material, or piece of equipment, and the workmanship required for its proper installation.

desiccate To dry thoroughly or to make dry by removing the moisture content, as in the seasoning of timber by exposing it in an oven to a current of hot air.

desiccator An apparatus in which a substance is dried.

design **1.** To create a graphic representation of a structure. **2.** The graphic architectural concept of a structure. **3.** To make a preliminary sketch, drawing, or outline.

design-bid-build (DBB) A traditional method of construction project delivery involving the selection and award of professional design services followed by a separate process for construction services once the design documents are complete.*

design/build (design-construct) A method of construction in which the contractor provides both design and construction services to an owner.

design contingency An amount included in a construction budget to cover additional costs for possible design changes. The amount of contingency varies with the stages of design. As the design is finalized, the contingency should be reduced to near zero for most school projects.*

design development The process of reviewing and modifying construction drawings as a result of owner input, coordinating with other design disciplines, building code compliance and general fine-tuning.*

design development phase The second phase of a designer's basic services, which includes developing structural, mechanical, and electrical drawings, specifying materials, and estimating the probable cost of construction.

design load **1.** In structural analysis, the total load on a structural system under the worst possible loading conditions. **2.** In air-conditioning, the maximum heat load a system is designed to withstand.

design pressure The highest pressure expected during operation of a system, device, or piece of equipment.

design professional A term used generally to refer to architects; civil, structural, mechanical, electrical, plumbing, and heating, ventilating, and air-conditioning engineers; interior designers; landscape architects; and others whose services have either traditionally been considered "professional" activities, require state licensing or registration, or otherwise require the knowledge and application of design principles appropriate to the problem at hand.

design review A formal, documented, comprehensive and systematic examination of a design to evaluate design requirements and capability of the design to meet these requirements and to identify problems and propose solutions.*

design specification A type of specification that prescribes the materials and methods to be used for contract performance.

design strength **1.** The assumed value for the strength of concrete and yield stress of steel, used to develop the ultimate strength of a section. **2.** The load-bearing capacity of a structural member, determined by the allowable stresses assumed in the design.

design to budget A requirement in the contract between an owner and a design professional that requires the design professional to redesign the project at no additional cost to the owner if the contract price exceeds the owner's budget.

destination elevators A system that groups passengers in order to reduce individual elevators' travel time.

detached dwelling A structure intended for habitation that is surrounded by open space.

detached garage A parking structure whose exterior walls are surrounded by open space.



detached garage

detail A large-scale architectural or engineering drawing indicating specific configurations and dimensions of construction elements. If the large-scale drawing differs from the general drawing, it is the architect's or engineer's intention that the large-scale drawing be used to clarify the general drawing.

detailed engineering The detailed design, drafting, engineering, and other related services necessary to purchase equipment and materials and construct a facility.*

detailed estimate of construction cost A forecast of the cost to construct a project, based on unit prices of materials, labor, and equipment, in contrast to a parameter estimate or square-foot estimate.

detail(ed) schedule A schedule used to communicate the day-to-day activities to working levels on the project. The intent of this schedule is to finalize remaining requirements for the total project.*

detailer A draftsman who prepares shop drawings and lists of materials.

detention door A special steel door with fixed lights and steel bars, used to restrict passage in prisons and mental institutions.

detention window A narrow, metal awning window manufactured especially for the security of prisons and mental institutions.

detritus tank A settling tank in a sewage-treatment system for collecting sediment without interrupting the flow of sewage.

developed area An area or site on which improvements have been made.

developed length The length of a pipeline, including fittings, measured along its center line.

developed surface A curved or angular surface graphically represented as flattened out on a plane.

development A tract of land that has been subdivided for housing and/or commercial usage and includes streets and all necessary utilities.

deviation costs The sum of those costs, including consequential costs such as schedule impact associated with the rejection or rework of a product, process, or service due to a departure from established requirements. Also may include the cost associated with the provision of deliverables that are more than required.*

device In an electrical system, a component that carries but does not consume electricity, such as a switch or a receptacle.

deviling The act of scratching a plaster coat prior to applying another coat.



device

dewater To remove water from a job site by pumps, wellpoints, or drainage systems.

dewpoint **1.** The temperature at which air of a given moisture content becomes saturated with water vapor. **2.** The temperature at which the relative humidity of the air is 100%.

D-grade wood Used only for interior wood applications, such as for inner plies and backs, where specified.



dewater

diagonal A straight structural member forming the hypotenuse of a right triangle, as in the diagonal bracing of a stud wall.

diagonal bond A pattern of bricklaying in which every sixth course is a header course, with the bricks placed diagonally to the face of the wall to form a decorative herringbone pattern.

diagonal brace A member installed at an angle to make a rectangular frame more rigid.



diagonal brace

diagonal bridging Crossing pairs of diagonal bracing that extend between the top of one floor joist and the bottom of the adjacent joist. The bracing is used to distribute the load and to decrease deflection.

diagonal buttress A support structure constructed at a 45° angle to the right-angle corner extension of two exterior walls.

diagonal crack A crack forming at about a 45° angle to the longitudinal dimension of a concrete member, beginning at the tension surface of the member.

diagonal pitch The distance between one rivet or bolt in one row to the nearest rivet or bolt in the next row of a structural member with two or more rows of bolts.

diagonal rib A structural member that crosses the bay of a vault in a diagonal direction.

diagonal sheathing A covering of wooden boards placed diagonally over an exterior stud wall. Although slightly more expensive to install, this method provides a more rigid frame than horizontally installed boards, and may be more architecturally pleasing.

diagonal tension In concrete structural members, the tensile stress resulting from shearing stresses within the member.

diameter The line in a circle passing through its center. Also refers to the nominal diameter designated by an approved material standard.

diamond blade A high-strength circular saw blade used to cut brick, concrete, tile, and other hard surfaces.

diamond drill A high-strength rotary rock drill that cuts a core in rock to create blasting holes.

diamond lath (diamond mesh) A type of expanded metal strip used as a base for plaster. Manufactured by slitting and expanding metal sheets.

diamondwork Masonry laid up so as to incorporate diamond shapes, usually every sixth course.



diamond lath (diamond mesh)

diaphragm **1.** A stiffening member between two structural steel members, used to increase rigidity. **2.** The web across a hollow masonry unit. **3.** An instrument to measure the flow of water in pipes.

diaphragm pump (mud sucker) A reciprocating water pump with a flexible diaphragm used for continuous dewatering of excavations containing mud and small stones.



diaphragm

diaphragm valve A valve that is actuated by fluid pressure on a diaphragm.

die A tool for cutting threads on pipe and bolts.

die-cast A method of casting by forcing molten metal into a mold.

differential settlement Uneven, downward movement of the foundation of a structure, usually caused by varying soil or loading conditions and resulting in cracks and distortions in the foundation.

differing site conditions Unanticipated physical conditions at the site that differ materially from those set forth in the contract or ordinarily encountered in work of the same nature.

diffused light Light reflecting from a surface rather than radiating directly from a light source.



diffuser

diffuser **1.** Any device or surface that scatters light or sound from a source. **2.** A circular, square, or rectangular air distribution outlet, generally located in the ceiling, and composed of deflecting members to discharge supply air in various directions.

digital Refers to communications equipment and procedures in which information is represented in binary form (1 or 0), as opposed to analog form (variable, continuous wave forms).

digital theater system A surround-sound system used in homes and commercial applications.

digital video recording (DVR) A video recording system used as a surveillance device that is capable of retaining voluminous records for long periods of time, limited only by the digital storage device.

dike (dyke) **1.** An earth embankment for retaining water. **2.** A large ditch.

dilation The expansion of concrete during cooling or freezing.

dimension A distance between two points, lines, or planes.

dimension line A light, fine line with arrowheads or tick marks at each end, used to show the measurements of the main object lines.

dimension lumber (dimension stuff) Lumber that is cut from 2″ to less than 5″ thick, and 2″ or more wide.

dimension shingles Shingles cut to a uniform size, usually 5″ or 6″ wide, and used for special architectural effects.

diminished stile (diminishing stile, gunstock stile) A door stile that has a narrower dimension at a panel, particularly at a glazed panel.

diminishing pipe (taper pipe) A pipe reducer.



dimmer

dimmer An electrical device that varies the amount of light given off by an electrical lamp by varying the current.

dip **1.** In geology, the slope of a fault or vein. **2.** In plumbing, the lowest point of the inside top of a trap.

dipcoat A covering of paint or other coating applied by immersing an object in a liquid. Usually applied as an anticorrosive.

dipper The digging bucket attached to the arm of a power shovel or backhoe.



dipper stick

dipper dredge A bucket used as part of a dredging operation for excavating under water.

dipper stick The straight arm that connects the dipper with the boom of a power shovel.

dipper trip The mechanism that releases the latch to the bucket door of a power shovel to discharge the load.

direct component The portion of light from a lamp or luminaire that arrives at the workplane without being reflected.

direct costs The labor, material, subcontractor, and heavy equipment costs directly incorporated into the construction of physical improvements.

direct current A term applied to an electrical circuit in which the current flows in one direction only.

direct damages Damages that can be expected to arise as a matter of course from a breach.

direct digital control (DDC) A system that receives electronic signals from sensors, converts those signals to numbers, and performs mathematical operations on the numbers inside a computer. The computer output (in the form of a number) is converted to a voltage or pneumatic signal to operate an actuator.

direct drive A system in which the driver and the driven element (motor and fan) are positively connected in line to operate at the same speed.

direct dumping The placing of concrete using a chute or bucket directly into open forms at or near its final position.

direct expansion (DX) Refrigeration systems that employ expansion valves or capillary tubes to meter liquid refrigerant into the evaporator.

direct expense All cost items that are directly incurred by or chargeable to a project, assignment, or task.

direct-indirect lighting A lighting system employing diffused light luminaires that emit little or no light horizontal to the lighting unit.

directional drill rig A drill rig that can drill holes in directions other than vertical.

directional lighting The lighting of an object or workplace from a desirable source location.

direct lighting A lighting system, usually emitting light in a downward direction, that distributes 90% to 100% of its light in the direction of the surface to be lit.

direct luminaire A luminaire that directs 90% to 100% of its light downward.

directory board An informational panel with changeable letters, such as those located in an office building lobby.

direct overhead costs Project overhead costs that are directly related to one individual project. These may include temporary facilities, trailer rental, superintendence, telephone usage, staging or lifts, and electrical power.*

direct personnel expense Salaries and wages, including fringe benefits, of all principals and employees attributable to a particular project or task.

direct solar gain Solar heating achieved when sunlight enters a room directly and heats the room or is stored in walls or floors.

direct system A heating, air conditioning, or refrigerating system that employs no intermediate heat exchanger to heat or cool a space.

dirt-depreciation factor A measurement of the reduction of light emitted by a luminaire as a result of accumulated dirt.

disappearing stair A hinged stair, usually folding, that is attached to a trap door in the ceiling and can be raised out of sight when not in use.

discharge head The pressure (in pounds per square inch or psi) measured at the center line of the discharge side of a pump and very close to the discharge flange converted into feet.

disconnecting means A device or group of devices that can disconnect the conductors of a circuit from their supply source.



disappearing stair

discontinuous construction A method of construction whereby structural members are staggered to reduce sound transmission through a wall or floor.

discounting Adjusting cash flow to a common point in time (often the present) when an analysis is performed. The conversion of all costs and savings to time-equivalent "present values" allows them to be added and compared in a meaningful way.

discount rate A percentage rate used to compute the present value of future cash flow.

discovery A pretrial procedure providing for the full disclosure of all facts and documents related to a contract dispute. The methods used include production of documents, depositions, interrogations, and requests for admission.

disintegration Deterioration or crumbling caused by oxidation, freezing, or exposure to other elements. The term is often applied to the deleterious effects suffered by exposed concrete.

disk sander A hand-held power tool that has a rotating, circular abrasive disk used for smoothing or polishing a surface.

dismantling The process of taking apart a structure or building in sections in order to reassemble them elsewhere.



disk sander

dispatching The selecting and sequence of jobs to be run at individual work stations and the assignment of these jobs to workers. In many companies, dispatching is done by the actual shop line supervisor, setup worker, or lead worker. A dispatcher is usually a representative of the production control department, which handles this job assignment task.*

dispersing agent An additive that increases the workability or fluidity of a paste, mortar, or concrete.

displacement **1.** The volume displaced by a piston or ram moving to the top or bottom of its stroke. **2.** In hydraulics, the volume of water displaced by a floating vessel.

displacement pile A pile that displaces soil as it is driven by either shifting or compacting it.

displacement ventilation Ventilation that uses natural convection processes to move warm air up and out of a building. Displacement ventilation tends to use less energy than conventional forced air ventilation, as it works with natural convection processes.

disposal unit An electric motor-driven unit installed in a sink to grind food waste for disposal through the sanitary sewer system.

dispute A disagreement between the owner and the contractor as to a question of fact or contract interpretation which cannot be resolved to the mutual satisfaction of the parties.*

dispute procedure The administrative procedure for processing a contract dispute with the United States government. This procedure is provided for in the Contract Disputes Act.

disruption The result of actions or inactions that interfere with performance efficiency, thereby requiring additional effort in performance of the contract work.

distance separation The distance, as specified in fire-protection codes, from an exterior wall to an adjacent building, property line, or the centerline of an adjacent street.

distributed antenna system Antennas and active repeater amplifiers used to enhance wireless communications within a building.

distributed generation A facility's generation and supply of electricity or heat for its own use. Surplus electrical power can be delivered to the utility's grid.

distributed load A load distributed evenly over the entire length of a structural member or the surface of a floor or roof, expressed in weight per length or weight per area.

distribution **1.** The movement of heated or conditioned air to desired locations. **2.** The delivery of electricity over a system from transmission points. **3.** The placement of concrete from where it is discharged to its final location.

distribution board (distribution panel, distribution switchboard) An electric switchboard or panel used to distribute electricity within a building. The switchboard is enclosed in a box and contains circuit breakers, fuses, and switches.

distribution box A container located at the outlet of a septic tank to distribute the effluent evenly to the drain tiles in the absorption field.

distribution line The main electrical feed line to which other circuits are connected.



distribution board (distribution panel, distribution switchboard)

distribution reinforcement The placement of small-diameter reinforcing steel at right angles to the main reinforcing steel in a slab. This method of reinforcement is used to distribute the load and prevent cracking.

distribution steel The small-diameter reinforcing steel used in distribution reinforcement.

distribution transformer A device that transforms primary voltage into a lower secondary voltage for use within a building.

district heating or cooling Distribution of heat or cooling from a large district plant, at greater efficiency than would be the case with numerous, smaller plants.

ditch A long, open trench used for drainage, irrigation, or for burying underground utilities.



ditch

diversion A pipe, trench, or channel, usually temporary, used to divert the flow of water from its usual course.

diversity factor In electrical systems, the sum of the individual demands of the subsystems divided by the maximum demand of the whole system.

dividers A compass with both legs terminating in points. Used for transferring measurements from a plan or map to a scale, or vice versa.

divider strips The nonferrous metal or plastic strips used as screeds in terrazzo work. Also used to divide the panels.



divider strips

division One of the standard major construction index classifications used in specifying, pricing, and filing construction data.

division wall (fire wall) A regulation fire-resistant wall extending from the lowest floor of a building through the roof to prevent the spread of fire.

D-line crack (D-crack) **1.** One of several fine, closely spaced, randomly patterned cracks in concrete surfaces. **2.** Similar cracks parallel to the edges or joints in a slab. **3.** Larger cracks in a highway slab that run diagonally across its corners.

dobying Blasting a boulder by mud-capping rather than drilling.

dock A raised platform for the loading and unloading of trucks. Often, the elevation of a portion of the dock is adjustable to accommodate the differing heights of truck beds.

dock bumper A recoiling or resilient device attached to a dock to absorb the impact of a truck.

dog **1.** In concrete forming, the hardware that holds the end of a snap tie. **2.** Any device used for holding, gripping, or fastening an object.



dog

dog anchor (dog iron) A short piece of iron with its two pointed ends bent at right angles, driven into two adjoining pieces of timber to hold them together.

dog bars Intermediate vertical members in the lower part of a gate, used to prevent animals from passing through.

dog-ear In roofing or flashing, an external corner formed by folding rather than cutting the metal.

dolly **1.** One of a variety of small, wheeled devices used to move heavy loads. **2.** A block of wood placed on the upper end of a pile to cushion the blow of a hammer. **3.** A steel bar with a shaped head to back up a rivet while the rivet is being driven.



dolly

Dolly Varden siding Beveled wood siding that is rabbeted along the bottom edge, such as on novelty siding.



Dolly Varden siding

dome **1.** A hemispherical roof such as that commonly seen on government structures. **2.** A rectangular pan form used in two-way joist or waffle concrete floor construction.



dome

dome light A dome-shaped skylight made of glass or plastic.



dome light

domestic hot-water heater A packaged unit that heats water for household purposes.

domestic sewage Household waste, including that originating from single- or multi-family housing.

door A movable member used to close the opening in a wall.

door area The total area of outside doors and facings. Used in computing heating and cooling requirements of a building.

door casing The finished visible frame into which a door fits.

door check An automatic door closer.

door class A fire-rating classification for doors.

door clearance The distance or space between the bottom of a door and a finished floor, or between two double doors.

door closer A device that controls the speed and force of closure of a door.



door closer

door contact (door switch) A switch in an electrical circuit that is opened or closed by opening or closing a door.

door frame The surrounding assembly into which a door fits. Consists of two uprights, jambs, and a head over the top.

door hand (door swing) The direction of the swing of a door, expressed as either left-hand or right-hand.

door head **1.** The horizontal upper member of a door frame. **2.** A lintel.

door holder A device for holding a door open.

door jack A device for holding a wooden door in place while the hinges are being set or while the door is being planed to fit.



door frame

door latch A device for holding a door closed. Usually a beveled bolt self-activated by a spring or by gravity when hitting the strike.

door mullion The vertical member in the middle of a double door frame that contains the strike of the two leaves.

door opening The size of a door frame opening measured between jambs and from the finished floor (or threshold) to the head.

door operator A power-operated mechanism for opening and closing an elevator door.

door pivot The pin on which a swinging door rotates.

door pocket The opening in a wall or partition that receives a sliding door. The door is installed on tracks during the rough framing stage of construction.

door rail Any of the horizontal members that connect the stiles of a door. In a flush door, the members are hidden. In a panel door, the members are exposed.


door pocket

door schedule A table in the contract documents listing all the doors by size, specifications, and location.

door sill *See* **threshold**.

door stile The outside, upright members of a door.

door strip A weatherproofing material used around a door.

door trim The casing or molding around a door frame that covers the joint between the frame and the wall.

doorjamb The vertical member on each side of a door frame.

doorstop The strip on the door frame against which the door closes.

dope **1.** In plumbing, a material placed on pipe threads to make them waterproof. **2.** An additive in mortar or plaster to accelerate or retard the set.


doorstop

dormant beam Any large beam that supports smaller ones.

dormer A projection through the slope of a roof for a vertical window.

dormer cheek The side wall of a dormer.

dormer window A window on the front vertical face of a dormer.

dormitory A residential building that includes sleeping facilities. Most commonly found at an educational institution.


dormer

dot A small amount of plaster placed on a surface between grounds to aid the plasterer in maintaining a constant thickness.

D.O.T. shipping name A material classification name assigned by the Department of Transportation to all transportable materials.

double-acting door (swinging door) A door with double-acting hinges so that it can swing both ways.

double-acting frame A door frame without stops, which allows a double-acting door to swing both ways.

double-acting hinge A door hinge that allows the door to swing both ways.

double back (double up) A method of applying two coats of plaster where the second coat is applied before the first coat has set.

double-break switch An electrical switch that opens and closes a conductor in two places.

double breasted A firm that operates or has ownership in both open shop and union companies.

double brick A masonry unit that measures 4″ × 5~THQ″ by 8″. The nominal measurement of standard bricks is 4″ × 2-2/4″ × 8″.

double bridging Bridging that breaks the span of joists into three sections.


double-acting hinge

double cheek cut A two-sided cut that forms a “V” at the end of a rafter, especially in hip and gambrel roofs.

double corner block A concrete masonry unit that has flat, rectangular faces.

double course (doubling course) Two thicknesses of roofing or siding shingles laid one over the other so that there is complete coverage of at least two layers overall.

double-cut saw A saw with teeth that cut both on the push and the pull stroke.

double door Two single doors or leaves hung in the same door frame.

double egress frame A door frame designed for two doors, both of the same hand, swinging in opposite directions. The door that swings toward the viewer is called a *reverse-hand door*.

double-end-trimmed Refers to wood that has been passed through saws and trimmed smoothly at both ends, commonly in length increments of 2′.

double-extra-strong pipe A specification for steel pipe that indicates the wall thickness has been increased to give the pipe double strength.


double egress frame

double-faced hammer A hammer whose head has two striking faces.

double-faced stock AA and AB grades of sanded plywood, both interior and exterior, having a good appearance on both sides.

double Flemish bond Brickwork laid up so that it has a pattern of headers and stretchers laid alternately on both faces.

double floor A floor constructed with a subfloor under a finished wood floor.

double-framed floor A floor system constructed with both binding joists and common joists. The ceiling is attached to the binding joists and the floor is laid on the common joists. The binding joists are framed by girders.

double-framed roof A roof framing system in which both longitudinal and lateral members are used, such as one that employs purlins.

double-gable roof An M-shaped roof with a valley between two gables.

double glazing Window with two panes of glass with an air space between for increased thermal and sound insulation.

doublehanded saw A crosscut saw with a handle on each end, designed to be used by two people.

double header A header joist for an opening made stronger by using two pieces of lumber.

double-gable roof

double-hung window A window that has two vertical sliding sashes, one above the other, mounted on separate guides so that either or both can be opened at one time. This is the type of window most commonly used on wood-frame houses.


double-hung window

double layer Two layers of gypsum board installed over each other to improve fire resistance or sound-suppression characteristics.

double-lock seam In metal roofing and ductwork, a seam formed by double-folding the edges of adjacent sheets and laying them down.

double L stair A stair with two landings turning 90° each, one near the top and one near the bottom.

double-margin door An extra-wide door constructed to look like two doors.



double L stair

double partition A partition constructed with two rows of studs to form a pocket door or a cavity for soundproofing.

double-pitched A roof with a second pitch or slope, such as a gambrel roof.

double-pole switch An electrical switch that has two blades and contacts that open or close both sides of a circuit simultaneously.


double partition

double pour In built-up roofing, a second, final application of bitumen without adding another layer of felt.

double rafter A pair of roof rafters installed alongside each other.

double return stair A stair with one flight to a landing, separating into two flights to the next floor.

double roof A roof-framing system in which the rafters rest on purlins.

double step In timber framing, a double notch cut into a tie beam supporting the rafters to reduce horizontal shear.

double-strength glass Plate or float glass that is ⅛″ thick.

double-suction riser method The use of two pipes for the upward flow of refrigerant suction gas. During periods of low refrigeration load, the refrigerant flow of one of the risers is blocked by the accumulation of oil in the base of the riser, diverting refrigerant flow at a higher velocity to transport oil up the other riser.

double swing frame A frame for two matching doors, each of which swing in the same direction.

double T-beam A precast concrete member composed of two beams with a flat slab cast monolithically across and projecting beyond the top of the two beams.


double T-beam

double-throw switch An electrical switch that can make connections in either of two circuits by changing its position.

double-tier partition A partition that is continuous through two stories of a building.

double-wall cofferdam A cofferdam constructed from two rows of sheet piling with fill between them. Used principally for high cofferdams that require greater stability.

double-walled heat exchanger A heat exchanger with two walls between the collector fluid and the potable water.

double-welded joint A joint welded on both sides.

doubling piece A cant strip or fillet.

doubly prestressed concrete A concrete member prestressed in two directions perpendicular to each other.

doubly reinforced concrete A concrete member cast with compression reinforcing steel as well as tension reinforcing steel.

Douglas fir *Pseudotsuga taxifolia*. A coniferous softwood found throughout the western United States and Canada and grown abundantly on the western slopes of the Cascade Mountains in Oregon. This tree produces a strong, durable timber that is widely used in general construction as well as in finish applications.

dovetail (dovetail joint) In finish carpentry, an interlocking joint that is wider at its end than at its base.

dovetail cramp A dovetail-shaped metal fastener used for lifting masonry units.

dovetail cutter A rotary power tool used to shape dovetail joints and mortises.


dovetail (dovetail joint)

dovetail half-lap joint A dovetail joint and mortise cut halfway through adjoining pieces to give the appearance of a butt or miter joint on the opposite side.

dovetail hinge A strap hinge with both leaves shaped like a dove's tail (wider at the end than at the base).

dovetail miter A joint having a concealed dovetail so that it appears to be a miter joint.

dovetail plane A wood-finishing tool used for preparing dovetail joints.

dovetail saw A small tenon saw or back saw with a stiffening strip along its back and fine teeth for preparing dovetails.

dowel A cylindrical piece of stock inserted into holes in adjacent pieces of material to align and/or attach the two pieces.

dowel-bar reinforcement Short sections of reinforcing steel that extend from one concrete pour into the next. Used to increase strength in the joint.



dowel-bar reinforcement

dowel lubricant A lubricant applied to dowels placed in adjoining concrete slabs to allow longitudinal movement in expansion joints.

dowel plate A steel plate with holes through which dowels are driven to trim them to size.

dowel screw A threaded dowel.

downlight A small direct-lighting unit, usually recessed in the ceiling and directing light downward only.

downpayment A partial payment of the construction project's contract price made by an owner to a contractor immediately at the beginning of the contract.*

downspout (drainpipe, conductor, leader) A vertical pipe used to carry rainwater from the roof to either the ground or a drainage system.



downspout (drainpipe, conductor, leader)

down-the-hole drill A percussion drill used for excavation powered from the surface that goes down the hole without the use of steels.*

downtime The amount of time a piece of equipment cannot be used due to failure, repair, or maintenance.

dozer shovel A tractor-mounted unit that can be used for pushing, digging, or loading earth.

draft **1.** The drawing power of air and gases through a chimney flue. **2.** A note similar to a check except that banks will not cash it without certain preliminary processing. A draft takes 10 to 14 days to "clear," or be guaranteed by the bank. (During this period, the bank sends the draft back to the insurance company for validation.) **3.** A smooth strip worked on a stone surface to be used as a guide for finishing the surface.

draft curtain (curtain board) A noncombustible curtain surrounding a high-hazard area to contain and direct flame, smoke, and fumes.

draft gauge An instrument used to measure differences in air pressure.

draft hood A cap that fits over a chimney flue to prevent downdrafts.



draft hood

drafting chisel A tool used most commonly to cut a narrow border or line at the end of a stone.

draft regulator A controlling device that maintains a desired draft level in an appliance.

drag **1.** A long, serrated plate used to level and score plaster in preparation for the next coat. **2.** Any combination of logs, chains, or other materials dragged behind a tractor to fine-grade earth.

dragging A textured finish similar to graining in which a wet, stippled paint surface is brushed with a clean, natural brush to produce subtle stripes.

dragline A bucket attachment for a crane that digs by drawing the bucket towards itself using a cable. The attachment is most commonly used in soft, wet materials that must be excavated at some distance from the crane. This device is used extensively in marsh or marine work.

dragon beam A short, horizontal membrane that bisects the angle of the wall plate at the corner of a wood-frame building, and bisects the angle brace at its other end. The member supports a hip rafter at one end and is supported by the angle brace at the other end.

drag saw A powered reciprocating saw used to cross-cut logs.

drag strut A structural member that transfers lateral force from one vertical member to another.

drain A pipe, ditch, or trench designed to carry away wastewater.



drain

drainage **1.** Wastewater. **2.** The process by which wastewater is carried away.

drainage fill **1.** Granular material placed beneath a concrete floor slab to inhibit the capillary rise of moisture. **2.** Lightweight concrete that is placed on a floor or roof to promote drainage.

drainage piping The piping comprising the plumbing of a drainage system.

drainage system All the components that convey the sewage and other wastewater to a point of disposal.

drain cock A cock or spigot at the lowest point of a water system where the system can be drained.

drain tile Short-length sections of tile laid with open joints, usually surrounded with aggregate and covered with asphaltic paper or straw. Used to drain the water from an area.

drapery track A system of tracks or bars that support draperies and allow them to be drawn.



drapery track

drawbar The bar attached to the back of a tractor for pulling equipment.

drawdown The distance by which the groundwater level is lowered by excavation, dewatering, or pumping.

drawer dovetail A dovetail joint in which the tenons of one member do not pass completely through the other member, such as the joint used on the front of a drawer.

drawer kicker A block that prevents a drawer from tilting downward when open.

drawer roller Prefabricated sliding drawer hardware employing rollers to facilitate the opening of a drawer.

drawer runner (drawer slip) The strips on which a drawer slides.

drawer slide The hardware on which a drawer slides.

drawer stop A device that prevents a drawer from sliding all the way out.

drawings **1.** Graphic illustrations depicting the dimensions, design, and location of a project. Generally including plans, elevations, details, diagrams, schedules, and sections. **2.** The term, when capitalized, refers to the graphic portions of a project's contract documents.

drawknife (drawshave) A two-handled, curved, woodworking knife used by pulling it toward the user.



drawknife (drawshave)

drawn finish A smooth, bright finish on longitudinal stock obtained by drawing the stock through a die.

draw tongue The bar attached to a machine so that it can be pulled by another machine.

dredge **1.** To excavate under water. **2.** The equipment used for excavating under water, such as a clamshell, dragline, or suction line.

drencher system A fire-protection sprinkler system that protects the outside of a building.

dressed Building material that has been prepared, shaped, or finished on at least one side or edge.

dressed and matched (tongued and grooved) Refers to boards or planks that have been machined so that each piece has a tongue on one edge and a groove on the other.



dressed and matched (tongued and grooved)

dressed lumber (dressed stuff) Lumber that has been processed through a planing machine in order to attain a smooth surface and uniformity of size on at least one side or edge.

dressed size The true dimensions of lumber after sawing and planing, as opposed to the nominal size.

dresser A plumber's tool for flattening sheet lead and straightening lead pipe.

dresser coupling A device for connecting unthreaded pipe.

dressing compound Liquid bituminous material used to cover and protect the exposed surfaces of roofing felt.

dress up To fasten and fabricate structural members on the ground before erection.

drier **1.** A unit containing a desiccant that is installed in a refrigeration circuit to collect excess water in the system. **2.** An additive to paints and varnishes that speeds the drying process.

drift **1.** In a water-spraying system, the entrained, unevaporated water picked up by the air movement through it. **2.** In aerial surveying, the angle at which a plane must crab, or turn its nose into the wind, in order to fly a predetermined line. **3.** A natural deposit of loose material such as rock or sand. **4.** The lateral movement or deflection of a structure.

drift control agent An additive used in spray mixtures to ensure a cohesive spray solution and reduce spray drift.

drifter A pneumatic drill used for drilling horizontal or sloped blastholes.

driftpin (drift punch) A tapered pin used in steel erection to align holes for bolting or riveting.

drift plug A hardwood plug that is driven into a lead pipe to straighten it or to flare the end.

drill **1.** A handheld, manually operated or power-driven rotary tool for boring holes in construction materials. **2.** A large machine capable of drilling 4″ diameter blast holes 100′ deep in rock cuts or quarries. **3.** A machine capable of taking core samples in rock or earth.



drill

drill bit The part of a drill that does the cutting.

drilled-in caisson A caisson that is socketed into rock. *See also* **caisson**.

drill press A rotary drill, mounted on a permanent stand, that operates along a vertical shaft.

drill steel Hollow steel sections that connect the percussion drill with the bit. Air is blown through the steel to clean out the drill hole.



drilled-in caisson

drip **1.** A groove in the underside of a projection, such as a windowsill, that prevents water from running back into the building wall. **2.** A condensation drain in a steam heating system. **3.** An interruption or offset in an exterior horizontal surface, such as a soffit, immediately adjacent to the fascia, designed to prevent the migration of water back along the surface.

drip cap (drip mold, drip molding) A horizontal molding placed over exterior door or window frames to divert rainwater.

drip edge **1.** The edge of a roof from which rainwater drips into a gutter



drill press

or away from the structure. **2.** The metal or wood strip that stiffens and protects this edge.

drip irrigation A landscape watering system using low water pressure and flexible tubing placed on the ground. These systems conserve water by targeting the roots of plants, rather than letting water evaporate as sprinklers would do.

drip pan A device for catching and containing drips and leaks from liquid storage drums.

dripstone A drip cap made of stone.

dripstone course A course of stone projecting out beyond the face of a wall to shed water away from the wall.

drive band (driving band) A steel band placed around the top of a wooden pile to protect it during driving.

driven pile A pile that is driven into place by striking it with a pile-driving hammer.

drivescrew (screw nail) A screw that is driven with a hammer and removed with a screwdriver.

drive shoe A cap placed over the bottom of a pile to protect the pile during driving.

driving cap A steel cap placed over the top of a pile to protect the pile during driving.

driving resistance The number of blows required to drive a pile a given distance.

drop In air conditioning, the vertical distance that a horizontally projected air stream has fallen when it reaches the end of its throw.

drop apron A metal strip that is bent downward at the edge of a metal roof to act as a drip.

drop-bottom bucket A concrete bucket whose bottom opens when it touches the surface where the concrete is to be deposited.

drop box An electrical outlet box hung from above, as from a ceiling.

drop ceiling (dropped ceiling, suspended ceiling) A nonstructural ceiling suspended below the structural system, usually in a modular grid pattern. A drop ceiling usually contains a lighting system and can also conceal wiring, piping, and ductwork in the space above (the plenum).



drop ceiling (dropped ceiling, suspended ceiling)

drop elbow A pipe fitting, at a 90° angle, with one or more flanges for attachment to a wall or stud.

dropout An event where voltage decreases to zero for at least five milliseconds.

dropout ceiling A suspended ceiling with heat-sensitive tiles that are designed to drop out in the event of a fire and sprinkler discharge. A dropout ceiling is aesthetically pleasing, as it does not require that sprinklers be extended below the ceiling.

drop panel The part of a cast-in-place flat slab that has been thickened on the underside at the location of the columns.



dropped girder (dropped girt)

dropped girder (dropped girt) A girder that runs below the floor joists and supports them.

drop siding A type of siding that is tongued and grooved or ship-lapped so that the edge of each board fits into the edge of the adjoining board.



drop siding

drop vent In plumbing, a vent that is connected at a point below the fixture.

drop wire An electrical conductor dropped from a pole to a building to supply electric power to the building.

drought tolerance The capacity of a landscape plant to function well in drought conditions.

drove A mason's broad, blunt chisel used for facing stone.

drum **1.** One of the stone cylinders forming a column. **2.** The wall supporting a dome. **3.** The rotating cylinder used to wind up cable on a hoist. **4.** The cylinder in which transit-mixed concrete is transported, mixed, and agitated.

drum rasp A cylindrical abrasive device used with a power drill to smooth or contour wood, plastic, and soft metals.

drum sander A power tool with a cylindrical abrasive sleeve used to smooth or contour wood, plastic, and soft metals. Usually mounted on a stand.

drum trap A cylindrical plumbing trap usually set flush with a floor so that easy access can be gained by unscrewing the top.

drunken saw (wobble saw) A type of circular saw designed to operate with a built-in wobble so that the kerf it makes is greater than the thickness of the saw. This type of saw is used for grooving and for other special purposes in carpentry.

dry basin systems Condenser water systems in which the cooling tower basin is located indoors, and away from the cooling tower.

dry batch weight The weight of the materials, excluding water, used to make a batch of concrete.

dry-bond adhesive (contact adhesive) An adhesive that seems dry but that adheres on contact.

dry-bulb temperature The ambient temperature indicated by an ordinary thermometer with an unmoistened bulb.

dry clamping The practice of piecing together all parts of an assembly, such as a table, before fastening to confirm that all joints fit.

dry concrete Concrete that has a low water content, making it relatively stiff. The effects are a lower water-cement ratio, less pressure on forms, lower heat of hydration, and a consistency that allows for placement on a sloping surface.

dry course The first course of a built-up roof, which lies directly on the insulation without bitumen.

dry density The weight of a soil sample that has been heated to 105° centigrade (Celsius) to remove the moisture.

dry filter A device for removing pollutants from the air in a system by passing the air through various screens and dry, porous materials. Most dry filters in HVAC systems today are made of spun fiberglass.

dry glazing The installation of glass using dry, preformed gaskets in place of glazing compound.


dry glazing

dry ice A substance made of solid carbon dioxide that is used in refrigeration applications. Dry ice sublimates, or changes directly from a solid to a gas.

drying shrinkage Contraction caused by the loss of moisture, particularly in concrete, mortar, and plaster.

dry joint A masonry joint without mortar.

dry masonry Masonry laid without mortar.

dry mix A concrete or mortar mixture that contains little water in proportion to its other ingredients.

dry mortar Mortar mixed to a very dry consistency, but still wet enough for hydration. This type of mortar is used to prevent compaction in the joints of high, narrow lifts.

dry-packing (dry-tamp process) The forceful injection of a damp concrete mixture into a confined space where high strength and little shrinkage is desired, such as under a bearing plate.

dry-pipe sprinkler system (dry sprinkler) A sprinkler system whose pipes remain empty of water until the system is activated. This type of system is particularly useful where there is danger of freezing.


dry-pipe sprinkler system (dry sprinkler)

dry-pipe valve The valve that activates a dry-pipe sprinkler system.

dry-powder fire extinguisher A handheld fire extinguisher that discharges a dry powder by means of a compressed gas. This type of extinguisher is effective for Class B and Class C fires.

dry return In a steam heating system, a return pipe above the water level.

dry-rodded volume A standard method of compacting aggregate when designing a concrete mix.

dry-rodded weight The unit weight of aggregate compacted under standard conditions and used when designing a concrete mix.

dry rodding Compaction of aggregate in a container under standard conditions for determining the unit weight in a concrete mix design.


dry-pipe valve

dry rubble construction A method of construction using stone rubble but no mortar.


dry rubble construction

dry sampling In soil testing, the practice of obtaining an undisturbed sample of earth with a boring tool.

dry shake (dry topping) A concrete surface treatment, such as color, hardening, or antiskid, which is applied to a concrete slab by shaking on a dry, granular material before the concrete has set and then troweling it in.

dry strength The strength of an adhesive joint determined under standard laboratory testing conditions.

dry tape The application of joint tape to gypsum board using an adhesive other than the standard joint compound.

dry-type transformer A transformer whose core and coils are not immersed in an oil bath.

dry-volume measurement Measurement of the ingredients of a concrete or mortar mix by using their bulk volume. This method is used principally in mix design.

drywall

drywall Interior finish construction materials that are manufactured and installed in preformed sheets, such as gypsum wallboard. Drywall is an alternative to plaster.

drywall construction Interior construction using drywall rather than plaster.


drywall construction

drywall frame A door frame specifically designed to be used with drywall construction.

dry well A pit or well that is filled or lined with coarse aggregate or rocks and designed to contain drainage water until it can be absorbed into the surrounding ground.

dual bed system A gas-phase or liquid adsorption treatment system with two carbon absorbers, a pump, and associated piping, that can be configured in series or in parallel, depending on facility requirements.


drywall frame

dual duct In electrical wiring, a duct that has two individual raceways.

dual-duct system An HVAC system using two ducts, one for hot air and one for cold air. The air from these ducts is blended in mixing boxes before distribution to each location.

dual-flush toilets Toilets that conserve water by allowing different settings for liquid versus solid waste.

dual-fuel system A heating unit that can use either of two types of fuel.

dual project gates Providing one gate for employees of union firms working on the project and a separate gate for employees of nonunion firms working on the project. In the event of a labor dispute, only the union gate can be picketed.

dual vent (common vent) A single plumbing vent that serves two fixtures.

dubbing (dubbing out) **1.** Filling in irregularities in a plaster wall before applying the final coat. **2.** Roughing in a plaster cornice before forming it with the final coat.

duckboard A wooden walkway across a wet area.

duct **1.** In electrical systems, an enclosure for wires or cables, often embedded in concrete floors or encased in concrete underground. **2.** In HVAC systems, the conduit used to distribute the air. **3.** In post-tensioning, the hole through which the cable is pulled.



duct

duct liner Fiberglass sound and thermal insulation material used inside the sheet metal ducts of air conditioning systems.

duct static pressure **1.** The pressure acting on the walls of a duct. **2.** The total pressure less the velocity pressure. **3.** The pressure existing by virtue of the air density and its degree of compression.

duct system The connected elements of an air-distribution system through ductwork.



duct system

ductwork The ducts of an HVAC system.

due care A legal term defining the standards of performance that can be expected, either by contract or by implication, in the execution of a particular task.

dumbwaiter A small hoisting mechanism or elevator in a building used for hoisting materials only. The dumbwaiter was originally developed by Thomas Jefferson for use in his home at Monticello.

dummy In CPM (critical path method) scheduling, a restraint with no activity and no time.

dumped fill Soil that has been deposited, usually by truck, but has not yet been spread or compacted.



dumbwaiter

dumpster Portable container box normally placed on a construction site for the disposal of job-generated refuse.

dumpy level A surveying instrument consisting of a telescope rigidly attached to a vertical spindle. Used to determine relative elevation.

dunnage **1.** Waste lumber. **2.** Temporary timber decking. **3.** Structural support for a system within a building that is independent of the building's structural frame. An example would be the supports for an air-conditioning cooling tower. **4.** Strips of wood used in stowing cargo to provide air space between pieces or packages.

duplex (duplex house, two-family house) A house with two separate dwelling units often sharing the same parcel of land.

duplex apartment An apartment with rooms on two floors connected by a private staircase.

duplex burner A gas heating system with two burners that can burn either simultaneously for rapid heating or separately during lower heating demand.



duplex (duplex house, two-family house)

duplex cable Two conductors, separately insulated, encased in a common insulated cover.

duplex receptacle (duplex outlet) Two electrical receptacles housed in the same outlet box.

duramen The hard inner portion, or heartwood, of a tree.



duplex receptacle (duplex outlet)

duration The amount of time estimated to complete an activity in the time scale used in the schedule (hours, days, weeks, etc.). Planned production rates and available resources will define the duration used in a given schedule.*



duration

Durham fitting A cast-iron, threaded, pitched fitting used on drainage pipes.

Durham system A wastewater system using all threaded pipes and pitched fittings.

durometer An instrument for determining the relative hardness of a material.

dust collector Any device used to collect the dust produced by a machine or tool, such as those required at all rock-drilling operations and those used with bench saws.

dust-free time The time required for a paint or varnish application to become dust-free under given environmental conditions.

dustproof strike A strike plate for a lock with a spring plunger that completely fills the bolt hole when the bolt is not in it.

Dutch door A door with two leaves, one above the other.

Dutch hip roof A style of roof framing similar to that in a hip roof, but with a small gable at the top.


Dutch door


Dutch hip roof

Dutch lap A method of applying shingles with a head lap and a side lap.

dutchman In carpentry and joinery, a small piece inserted to cover a joint or a defect.


Dutch lap

dwarf partition A partition that does not extend to the full ceiling height.

dwarf wall Any wall less than one story in height, such as a subwall for a crawl space or a wall that supports sleepers for the floor above.

dwelling unit A room or rooms designed for permanent living accommodations for one or more persons.

dynamic Refers to information that will be updated and displayed automatically on a building automation system CRT or display panel when the status of the building equipment changes.

dynamic analysis The analysis of stresses in a framing system under dynamic loading conditions.

dynamic load A load on a structural system that is not constant, such as a moving live load or wind load.

dynamic loading Loading imposed by a piece of machinery through vibration, in addition to its dead load.

dynamic penetration test A test to determine the bearing capacity of soil where a testing device is delivered a series of blows to penetrate the soil.

dynamic resistance The resistance of a pile to blows from a pile hammer, expressed in blows per unit of penetration.

E

Abbreviations

e eccentricity, erg

E east, engineer, equipment only, modulus of elasticity, 90° elbow

ea each

EA exhaust air

EAM enterprise asset management

E and OE errors and omissions excepted

eastern S-P-F eastern spruce, pine, or fir

EB1S edge bead one side

E&CB2S edge and center bead two sides

EC electrical contractor

ECI energy conservation initiative

ecol ecology

Econ economy

ECM energy conservation measure

ECN engineering change notice

EDA emergency declaration area, equipment distribution area

EDP electronic data processing

EDR equivalent direct radiation

EE eased edges, electrical engineer, energy efficiency, errors excepted

EEM energy efficiency measure

EEO equal opportunity employer

EF entrance facilities

eff efficiency

EG edge (vertical) grain

ehf extremely high frequency

EHP effective horsepower, electric horsepower

EHS environmental health and safety

EIA Electronic Industries Alliance

EIS energy information system

EL elevation, elevator, electroluminescence

elec electric, electrical, electrician

elev elevation, elevator

Elev elevating, elevator

EM end matched

EMCS energy management and control system, energy monitoring and control system

EMF electromotive force

EMI electromagnetic interference

EMPP equal marginal performance principle

EMS energy (or emergency) management system

EMT electrical metallic conduit, thin wall conduit

emu electromagnetic unit

enam enameled

encl enclosure

eng engine

Eng engine

engr engineer

EOC energy operations center

EOL end of line termination

EPA Environmental Protection Agency

EPC Electronic product code; engineering, procurement, and construction

EPDM ethylene propylene diene monomer

EPO emergency power off

EPS expanded polystyrene

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

eq equal

Eq equation

Eqhv equipment operator, heavy

Eqlt equipment operator, light

Eqmd equipment operator, medium

Eqmm equipment operator, master mechanic

Eqol equipment operator, oilers

equip equipment

equiv equivalent

erec erection

ER equipment room

ERW electric resistance welding

ESCO energy service company

ESD emergency shutdown, electrostatic discharge

est estimate

EST estimated

esu electrostatic unit

ET ethyl

EV electron volt

evap evaporate

EV1S edge vee one side

EW each way

EWSD early warning smoke detector

EWT entering water temperature

ex example, extra

exc excavation, except

excav excavation

exh exhaust

exp expansion

Exp expansion

exp bt expansion bolt

ext exterior

extg extracting

extru extrusion

exx examples

E The rating of elasticity or stiffness of a material.

Definitions



ear (shoulder)

ear (shoulder) **1.** A small decorative or structural projecting member or part of a structure or piece. **2.** A small metal projection on a pipe by which it can be nailed to a wall.

earliest event occurrence time In CPM (critical path method) scheduling, the earliest completion of all the activities that precede the event.

earliest expected completion date The earliest calendar date on which the completion of an activity work package or summary item occurs.*

early finish In CPM (critical path method) scheduling, the first day on which no work is to be done for an activity, assuming work began on its early start time.

early start In CPM (critical path method) scheduling, the first day of a project on which work on an activity can begin if all preceding activities are completed as early as possible.



earth auger (earth borer, earth drill)

early strength The strength that has developed in concrete or mortar, usually within 72 hours after placement.

early warning smoke detector A device designed to alert building occupants before they become endangered by a fire.

earnest money The deposit that is made by the purchaser when a purchase contract is made to show the purchasers serious intent.

earth auger (earth borer, earth drill) A screw-like drill (usually powered) for boring cylindrical holes in earth or rock.

earth berm A small, earthen, dike-like embankment, usually used for diverting runoff water.

earth coupling The practice of building into the ground to take advantage of the vast thermal mass of the earth, which typically remains a constant temperature at a certain depth below grade (depending on the climate).

earth electrode A metal plate, water pipe, or other conductor of electricity partially buried in the earth so as to constitute and provide a reliable conductive path to the ground.

earthing lead The conductor that makes the final connection to an earth electrode.

earth pigment Pigment derived from the processing of materials or substances mined directly from the earth.

earth plate A buried metal plate that serves as an earth electrode.

earth pressure The horizontal pressure exerted by retained earth.

earthquake load The total force that an earthquake exerts on a given structure.

earth station (ground station) The equipment set up on earth to communicate with satellites.

earthwork A general term encompassing all operations relative to the movement, shaping, or compacting of earth.

eased edge Any slightly rounded edge.

easement **1.** The legal right afforded a party to cross or to make limited use of land owned by another. **2.** A curve formed at the juncture of two members that otherwise would intersect on an angle.

easing Excavation that allows an allotted space to accommodate a foreign piece or part.

eastern red cedar A distinctively red, fine-textured, aromatic wood often used for shingles and closet linings.

eastern S-P-F Eastern spruce, pine, or fir—softwoods whose primary uses include structural lumber as in posts, beams, framing, and sheathing.

eaves **1.** Those portions of a roof that project beyond the outside walls of a building. **2.** The bottom edges of a sloping roof.

eaves board A thick, feather board nailed across rafters at the eaves of a building to slightly raise the first course of shingles.



eaves

eaves course The first course of shingles or tiles at the eaves of a roof.

eaves fascia (fascia board) A board secured horizontally to, and covering the vertical ends of, roof rafters. The board may support a gutter.



eaves fascia (fascia board)

eaves flashing A thin metal strip dressed into an eaves gutter from a roof in order to prevent overflowing water from running down the exterior siding.

eaves gutter (eaves trough) A long, shallow wood or metal trough fitting installed under and parallel to the eaves in order to catch and direct water dripping from a roof.

eaves plate A wood beam installed horizontally at the eaves and used in the absence of a rafter-supporting wall to support the feet of roof rafters between existing posts or piers.

eaves strut A structural piece spanning columns at the edge of a roof. The term is usually associated with preengineered steel buildings.

eaves vent Vent openings under the eaves of a house to allow the exchange of air in the attic.

eccentric Not having the same center or center line.

eccentric fitting A fitting whose opening or centerline is offset from the run of pipe.

eccentric load A load or force upon a portion of a column or pile not symmetric with its central axis, thus producing bending.



eccentric load

eccentric tendon In prestressed concrete, a steel element or tendon that does not follow a trajectory coincidental with the gravity axis of the member.

ecology The study of the relationship between living things and their environment.

economic life The term during which a structure is expected to be profitable. Generally shorter than the physical life of the structure.

economizer cycle A system of dampers, temperature and humidity sensors, and actuators, which maximizes the use of outdoor air for cooling.

economy brick A cored, modular brick with nominal dimensions of 4″ × 4″ × 8″ and intrinsic dimensions of about 3½″ × 3½″ × 7½″.



economy brick

economy wall A 4″-thick, back-mortared brick wall strengthened at intervals with vertical pilasters. Designed to support roof framing or walls.

edge beam A stiffening beam at the edge of a slab.

edge form Formwork used to limit the horizontal spread of fresh concrete on flat surfaces such as pavements or floors.

edge grain Lumber sawn so as to reveal the annual rings intersecting the wide face or surface at an angle of at least 45°.

edge guide An attachment to a router that ensures straight cuts by keeping the bit parallel to the work surface edge.

edge joint **1.** A joint between two veneers or laminations, formed in the direction of the grain. **2.** A joint created by the edges of two boards or surfaces united so as to form an angle or corner.

edge nailing Nailing through the edges of successive boards, such as floorboards, so that each board conceals the nails in the board adjacent to it.

edger (edging trowel) A tool used to fashion finishing edges or round corners on fresh concrete or plaster.



edger (edging trowel)

edge spacer A spacer that positions and holds a pane of glass in place within a window frame.

edgestone A stone used for curbing.

edge strip A plain or molded strip of wood or metal used to protect the edges of panels.



edge strip

edge treatment The finish used to conceal the plies of a plywood edge. Finish may involve molding, wood strips, or wood putty.

edge vent An opening at the perimeter of a roof for the relief of water vapor pressure within the roof system.

edging **1.** An edge molding. **2.** An edging strip. **3.** The process of rounding to reduce the possibility of chipping or spalling exposed edges of concrete slabs. **4.** The process of grinding the edge of flat glass to fit an application.

effective area **1.** The net area of an air inlet or outlet system through which air can pass. The effective area equals the free area of the device multiplied by the coefficient of discharge. **2.** The cross-sectional area of a structural member, calculated to resist applied stress.

effective area of reinforcement In reinforced concrete, the product derived by multiplying the cross-sectional area of the steel reinforcement by the cosine of the angle between its direction and the direction for which its effectiveness is considered.

effective date of the agreement The date indicated in the agreement on which it becomes effective, but if no such date is indicated, the date on which the agreement is signed and delivered by the last of the two parties to sign and deliver.*

effective depth The depth of a beam or slab section as measured from the top of the member to the centroid of the tensile reinforcement.

effective height of a column In calculating the slenderness ratio, multiply a valve by the actual column length. The valve varies depending on whether the column is fully or partly restrained at both ends.

effective length The distance between inflection points in a column when it bends.

effective modulus of elasticity The combination of elastic and plastic effects in an overall stress-strain relationship in a service structure.

effective opening The minimal cross-sectional area of the opening at the point of water supply discharge, expressed in terms of the diameter of a circle. The diameter of a circle of equivalent cross-sectional area is given in instances where the opening is not circular.

effective prestress The stress remaining in concrete resulting from prestressing after *loss of prestress*. Effective prestress includes the effect of the weight of the member, but not the effects from any superimposed loads.

effective reinforcement The reinforcement assumed to be active in resisting applied stress.

effective span The center-to-center distance between the supports of a beam, girder, or other structural member.

effective stress In prestressed concrete, the remaining stress in the tendons after the loss of prestress.

effective temperature A single-figure index reflecting the combined effects of temperature, humidity, and air movement on the sensation of warmth and/or cold felt by the human body. Numerically equivalent to the temperature of still, saturated air, which produces an identical sensation.

effective thickness of a wall The thickness of a wall, used in calculating the slenderness ratio.

efficacy The ratio of light output to energy consumption, measured in lumens per watt.

efficiency The ratio of actual performance to theoretical maximum performance.

effort The number of labor units necessary to complete work. Effort is usually expressed in staff hours, staff days, or staff weeks and should not be confused with duration.*



effluent

effluent **1.** In sanitary engineering, the liquid sewage discharged as waste, as in the discharge from a septic tank. **2.** Generally, the discharged gas, liquid, or dust byproduct of a process.

egress An exit or means of exiting.

ejector **1.** A pump for ejecting liquid. **2.** In plumbing, a device used to pump sewage from a lower to a higher elevation. **3.** In excavation, a dirt-pushing mechanism in a scraper bowl.



ejector

ejector grille A ventilating grille with slots shaped so as to force out air in divergent streams.

elastic Refers to any material that can return to its initial state after having been deformed by an outside force.

elastic curve In structural analysis, the curve showing the deflected shape of a beam with an applied load.

elastic design An analytical design method in which the design of a structural member is based on a linear stress-strain relationship that assumes that the active stresses are equal to only a fraction of the given material's limit of elasticity.

elasticity The ability of a material to return to its initial state after having been deformed by some outside force.

elastic limit The maximum amount of deforming stress a material can sustain and still return to its initial shape without having incurred any permanent deformation.

elastic loss In pretensioned concrete, the condition resulting in the reduction of prestressing load due to the elastic shortening of a member.

elastic shortening **1.** A linearly proportional decrease in the length of a structural member under an imposed load. **2.** In prestressed concrete, the shortening of a member caused by, and occurring immediately upon, application of force induced by prestressing.

elastomer A term descriptive of various polymers that, after being temporarily but substantially deformed by stress, will return to their initial size and shape immediately upon the release of the stress.

elastomeric waterproofing A method of foundation moisture protection using impervious flexible sheet metal.

elbow A sharply bent or fabricated angle fitting, usually of pipe, conduit, or sheet metal. *See also* **knee**.



elbow

elbow catch A spring-loaded locking device having on one end a hook that engages a strike, and on the other end a right angle bend that provides a means for releasing the catch. Commonly used to lock the inactive leaf of a pair of cabinet doors.

electrical conductivity The ability to transmit an electrical current.

electrical drawings Graphic representations of the electrical requirements of a project, including power distribution, lighting, and low-voltage specialty wiring, such as for fire alarms, telephone/data, and technology wiring.

electrically supervised Refers to a closed-circuit wiring system that utilizes a current-responsive device to indicate a failure within the circuit or an accidental grounding.

electrical metallic conduit Heavy-walled conduit that encloses and protects wiring.

electrical resistance The opposition to the flow of an electric current as manifested by a device, conductor, substance, or circuit element. Electrical resistance is measured in *ohms*.

electric arc welding (electric welding) The joining of metal pieces by fusion, the heat for which is provided by an electric arc or the flow of electric current between the electrode and the base metal. The electrode is either a consumable, melting and bead-depositing, or nonconsumable metal rod. The base is the parent metal.

electric baseboard heater A heating system with electric heating elements installed in longitudinal panels, usually along the baseboards of exterior walls.



electric baseboard heater

electric cable **1.** An electric conductor comprising several smaller-diameter strands that are twisted together. **2.** A group of electric conductors that are insulated from one another.

electric-discharge lamp A lamp that emits light through a process where electric current flows through a vapor or gas.

electric drill A portable, handheld, motor-driven tool used for boring holes in a material. Powered either by direct or alternating current.



electric drill

electric eye A photoelectric cell whose resistance varies in response to the amount of light that falls on the cell. An electric eye is often incorporated into electric circuits where it is used in measuring or control devices that depend on illumination levels or on the interruption of a light beam.

electric feeder In power distribution, a set of electric conductors that originate at a primary distribution center and supply power to one or more secondary distribution centers, branch-circuit distribution centers, or a combination of these.

electric field A particular region or space characterized by the existence of a detectable electric intensity at every point within its perimeter.

electric fixture An electrical device that is fastened to a ceiling or wall and used to hold lamps.



electric fixture

electric generator A mechanism that transforms mechanical power into electrical power.

electric lock A locking mechanism in which the motion of a latch or bolt is controlled by applying voltage to the terminals of the mechanism.

electric meter A device that measures the amount of electricity consumed over a certain period of time.

KILOWATTHOURS

electric meter

electric outlet A point in an electric wiring system at which current is delivered through receptacles equipped with sockets for plugs, making it available to supply lights, appliances, power tools, and other electrically powered devices.

electric panelboard A panel or group of individual panel units capable of being assembled as a single panel and designed to include fuses, switches, and circuit breakers. The units are housed in a cabinet or cutout box positioned in or against a wall or partition and accessible only from the front.



electric panelboard

electric receptacle A contact device, usually installed in an outlet box, which provides the socket for the attachment of a plug to supply electric current to portable power equipment, appliances, and other electrically operated devices.



electric receptacle

electric space heater A portable, self-contained heating device in which electricity supplies the heat energy. The heat is blown into a given space or room by a powerful electric fan also contained within the unit.

electric space heater

electric strike An electrical mechanism that allows the release of a door at a remote location.

electric switch A device used for opening or closing electric circuits or for changing the connection of a circuit.

electrode **1.** A solid electric conductor through which an electric current enters or leaves an electrolyte, vacuum, gas, or other medium. **2.** That component in an arc welding circuit through which electric current is conducted between the electrode holder and the arc itself. **3.** In resistance welding, that component through which the electric current in the welding machine passes directly to the work and that is usually accompanied by pressure, such as from a clamp.

electrolysis The process of producing chemical changes or the breakdown of chemical compounds into their constituent parts by passing a current between electrodes and through an electrolyte.

electrolyte **1.** A substance that separates into ions when in a solution or when fused, thereby becoming electrically conducting. **2.** A conducting medium in which the flow of electric current occurs by the migration of ions.

electrolytic copper Copper refined through electrolytic deposition and used in the manufacturing of tough pitch copper and copper alloys.

electrolytic corrosion The deterioration of metal or concrete by the chemical or electrochemical reaction resulting from electrolysis.

electromagnetic interference (EMI) Radiation emission from a transmission medium caused by using high-frequency signal modulation. Can be reduced by shielding.

electromotive force (EMF) The force that moves electricity in a conductor. EMF, usually measured in volts, is the difference in electric potential, or voltage, between the terminals of a source of electricity.

electronic ballast A ballast that uses semiconductor components to increase the efficiency of a fluorescent system by increasing the frequency (in kilohertz) of its lamp operation.

electronic controls In an HVAC system, the electronically operated sensors and controls.

electronic distance meter (EDM) A surveying device used to measure distance. Distance is determined from the time it takes transmitted electromagnetic waves to reach a target.

electrostatic precipitator (electrostatic air cleaner) A type of filtering device that prevents smoke and dust from escaping into the atmosphere by charging the particles electrically as they pass through a screen. The particles are attracted to one of two electrically charged plates and subsequently removed.

elevated conduit An electrical conduit hung from structural floor members.

elevated floor Any floor system not supported by the subgrade.



elevated floor

elevated slab A floor or roof slab supported by structural members.

elevated water tank A domestic water tank supported on an elevated structural framework to obtain the required head of pressure.

elevation **1.** A vertical distance relative to a reference point. **2.** A view or drawing of the interior or exterior of a structure as if projected onto a vertical plane.

elevator A "car" or platform that moves within a shaft or guides and is used for the vertical hoisting and/or lowering of people or material between two or more floors of a structure. An elevator is usually electrically powered, although some short-distance elevators (serving fewer than six or seven floors) are powered hydraulically.



elevator

elevator car That part of an elevator that includes the platform, enclosure, car frame, and gate or door.

elevator interlock A device on the door of each elevator landing that prevents movement of the elevator until the door is closed and locked.

elevator machine beam A steel beam that is usually positioned directly over the elevator in the elevator machinery room and is used to support elevator equipment.

elevator pit That part of an elevator shaft that extends from the threshold level of the lowest landing door down to the floor at the very bottom of the shaft.



elevator pit

elevator recall The override of elevator operation by a building's fire safety system upon activation of a fire alarm. In a fire emergency, elevator cars automatically return to the ground floor and can be operated only by a fire department.

elevator shaft A hoistway through which one or more elevator cars may travel.



elevator shaft

ell (el) **1.** An extension, addition, or secondary wing that joins the principal dimension of a building at a right angle. **2.** Same as *elbow*.

elliptical arch An arch in the shape of a semiellipse and whose intrados is in the form of an ellipse.

embankment A ridge constructed of earth, fill rocks, or gravel and used most commonly to retain water or to carry a roadway. The length of an embankment exceeds both its width and its height.



ell (el)

embedded length That length of embedded steel reinforcement that extends beyond a critical section.

embedded reinforcement In reinforced concrete, any slender steel members, such as rods, bars, or wires, that are embedded in concrete in such a way as to function together with the concrete in resisting forces.

embodied energy The energy needed to produce a building product, not accounting for transportation, durability, reuse, and recycling.

embossed Describes a material whose surface is raised or indented.



embedded reinforcement

emergency ballast A lighting system that uses a battery to function in the event of a power loss. When AC power fails, the emergency ballast senses the failure and immediately switches to the emergency mode to illuminate lamps at a reduced lumen output.

emergency declaration area (EDA) An area officially declared in need of hazardous waste or material cleanup.

emergency exit A door, hatch, or other device leading to the outside of the structure and usually kept closed and locked. The exit is used chiefly for the emergency evacuation of a building, airplane, or other occupied space when conventional exits fail, are insufficient, or are rendered inaccessible.

emergency lighting Temporary illumination provided by battery or generator and essential to safety during the failure or interruption of the conventional electric power supply.

emergency power Electricity temporarily produced and supplied by a standby power generator when the conventional electric power supply fails or is interrupted. Emergency power is essential in facilities such as hospitals, where even relatively short power outages could be life threatening to certain individuals.

emergency stop switch A safety switch in the car of an elevator that can be manually operated to cut off electric power from the driving machine motor and brake of an electric elevator, or from

c05.indd 106 06/09/12 8:49 AM

the electrically operated valves and/or pump motor of a hydraulic elevation.

emery wheel An abrasive wheel similar to a grinding wheel but composed primarily of emery (or aluminum oxide) and rotated at high speeds for fine grinding or polishing.

eminent domain The legal right or power of a government to take for public use privately owned property, usually with some degree of compensation to its owner.

emissivity The relative ability of a surface to emit radiant heat.

emittance A percentage of the energy absorbed by a solar energy collector.

empty-cell process A procedure in which wood is impregnated with liquid preservatives under pressure.

emulsion **1.** A mixture of two liquids that are insoluble in one another and in which globules of one are suspended in the other (such as oil globules in water). **2.** The mixture of solid particles and the liquid in which they are suspended but insoluble, as in a mixture of uniformly dispersed bitumen particles in water, in which the cementing action required in roofing and waterproofing would occur as the water evaporates.

emulsion glue A usually cold-setting glue manufactured from emulsified synthetic polymers.

emulsion paint A paint comprising tiny beads of resin binder that, along with pigments, are dispersed in water. Evaporation of the water affects the coalescence of the resin particles, thus forming a film that adheres to the surface and binds the pigment particles. Vinyl, latex, or plastic paints are examples based on polyvinyl acetate emulsion.

emulsion sprayer An apparatus used in highway resurfacing to spray an emulsified asphalt tack coat on the existing surface.

enamel A type of paint composed of particles of finely ground pigments and a resin binder that dries to form a hard, glossy film with very little surface texture.

enameled brick In masonry, a brick or tile with a glazed ceramic finish.



enameled brick

encapsulant (sealant) A liquid applied to asbestos-containing material that prevents the release of fibers into the air either by forming a membrane over the material or by penetrating the material and binding the fibers together.

encapsulate To encase a material or substance; to hide data (such as computer processing logic).

encapsulation A technique for trapping asbestos fibers in a dense chemical substance.

encase To cover with or enclose in a case or lining.



encase

encased beam A metal beam usually enclosed in concrete or some other similar material.



encased beam

encaustic **1.** Descriptive of a process in which a material is covered with a mixture of paint solution and wax, then set by heat after application. **2.** Relating to paint or pigment that has been applied to glass, tile, brick, or porcelain and then set or fixed by the application of heat.

encaustic tile A decorative or pavement tile whose pattern is created by inlaying clay of one color in a background of a different-colored clay.

enclosed knot A wood knot that is invisible from the surface of a wood member because it is completely covered by surrounding wood.

enclosed stair An interior staircase that has a closed string on each side, often encased in walls or partitions. There are also door openings at various floor levels, thus making it accessible to hallways of living units.

enclosure The containment behind airtight, impenetrable, permanent barriers of sprayed-on or troweled-on asbestos-based materials.

enclosure system A contamination-control system consisting of a work area, a holding area, a washroom, and an uncontaminated area.

enclosure wall An interior or exterior non-load-bearing wall of skeleton construction, usually anchored to columns, piers, or floors.

encroachment The unauthorized intrusion or extension of a building or structure onto the property of another.

end anchorage A mechanism designed to transmit prestressing force to the reinforced concrete of a post-tensioned member.



end anchorage

end bearing pile A pile supported mainly by point resistance. The pile's point (toe) rests on or is embedded in a posttensioned member.

end butt joint (end joint) **1.** A joint formed when boards are connected square end to square end. **2.** A joint between two veneers, formed perpendicular to the grain. **3.** In masonry, a joint in which mortar connects the butt ends of two bricks.

end channel A metal stiffener welded horizontally into the tops and bottoms of hollow metal doors to supply strength and rigidity.

end checks Small cracks that develop in the end grain of drying lumber.

end distance The distance from an end of a member to the center of its nearest bolt hole, nail, or screw.

end grain The grain that is exposed when a piece of wood is cut perpendicular to the grain.

end grain

end-grain core Plywood or panel core made from wood blocks that are sawn and glued so that the grain is at right angles to the forces of the panels.

end lap The overlap in a lap joint, such as at the end of a ply of roofing felt.

end lap joint An angle joint involving two members, each having been cut to half its thickness and lapped over the other in such a way as to result in a change of direction.

endless saw A band saw.



endless saw

end matched Descriptive of boards or strips that are tongued along one end and grooved along the other.

end post A post or other structural member in compression at the end of a truss.

end rafter A common rafter positioned in line with the ridge of the roof.

end scarf A scarf joint between two timbers made by notching and lapping the ends and then inserting the end of one into an end of the other.

end section In a drainage system, the prefabricated, flared metal end attached at the inlet and outlet to prevent erosion.

end span In a continuous-span floor design, the exterior span, which is often more heavily reinforced.

end stiffener One of the vertical angles connected to the web of a beam or girder at its ends, to stiffen the beam and transfer the end shear to the shoe, baseplate, or supporting member.

end-use/least cost A major green consideration when designing a building and selecting products. This factor involves an evaluation of the end users' needs and explores different ways of achieving them at the lowest cost with the greatest efficiency over time.

energized Electrically connected to a source of voltage.

Energy and Atmosphere (EA) A term used by LEED in reference to energy consumption and efficiency and greenhouse gas emissions.

energy audit A survey of heat loss through the components of a structure.

energy efficiency measure (EEM) A design, operation, or technology change for the purpose of reducing energy consumption.

energy efficiency ratio (EER) A measure of energy efficiency in the cooling mode that represents the ratio of total cooling capacity to electrical energy input.

energy-efficient design Design that emphasizes highly effective space conditioning equipment and controls, a tight building envelope, and an efficient ventilation system.*

energy-efficient lighting Light fixtures and lamps, such as CFL and LED, that consume substantially less energy than conventional incandescents.

energy harvesting Capture of renewable energy, such as solar, and conversion of that energy into usable electricity.

Energy Information Administration A division of the U.S. Department of Energy.

energy management system (EMS) A system that monitors and controls energy-consuming systems, in the most energy-efficient manner, through software programs.

energy modeling Using computer modeling software to analyze alternative energy systems to help determine the most efficient design. It typically involves not only mechanical and electrical systems, but building orientation, materials, lighting, and landscaping.

energy recovery A process whereby energy from one source is used to provide energy for another process.

energy recovery ventilator (ERV) Mechanical equipment that is added to the ventilation system, featuring a heat exchanger to provide controlled ventilation into a building, while increasing energy efficiency.

energy savings performance contract (ESPC) A contracting partnership between an agency/consumer and an energy services company (ESCO) in which the ESCO evaluates the facility's energy needs and consumption and identifies strategies for improvement. The ESCO often helps pay for the initial cost of implementation in exchange for a share of the energy savings.

energy service company (ESCO) A firm that provides energy management services in exchange for a set fee or an amount tied to a facility's energy cost savings.

energy service provider (ESP) A company that provides energy or energy management services.

Energy Star A volunteer rating and labeling program sponsored by the Department of Energy and the Environmental Protection Agency (EPA) to encourage the use of energy-efficient products.

Energy Star buildings A voluntary partnership between U.S. organizations and the U.S. Environmental Protection Agency (EPA) to promote energy efficiency in buildings.

Energy Usage Intensity (EUI) A measurement used for the purpose of rating a facility's energy consumption per square foot; used by the U.S. Department of Energy.

engineer A design professional who, by education, experience, and examination, is duly licensed by one or more state governments for practice in the profession of engineering. This practice may be limited to one or more specific disciplines of engineering. Construction-related engineering disciplines include civil, structural, mechanical, or electrical systems design.

engineer brick Brick whose nominal dimensions are 3⅕″ × 4″ × 8″.



engineer brick

engineered items Items that are purchased to be used for a particular purpose and are engineered to unique specifications, as opposed to commodity materials. This typically includes tagged items and materials that require detailed engineering data sheets.*

engineering survey A survey undertaken for the purpose of obtaining information essential to the planning of an engineering project.



engineer's scale

engineer-in-training A person who is qualified to become a registered professional engineer in all respects but the necessary professional experience.

engineer's scale A straightedge on which each inch is divided into uniform multiples of ten, thus enabling drawings to be made with distances, loads, forces, and other calculations expressed in decimal values.

engineer's transit **1.** An instrument used in surveying to measure and to lay out vertical and horizontal angles, distance, directions, and differences in elevation. **2.** A theodolite, the directions of whose alidade and telescope are reversible.



English garden wall bond (American bond, common bond)

English bond **1.** Brickwork consisting of alternate courses of headers and stretchers. **2.** A strong, easily laid bond.

English garden wall bond (American bond, common bond) Widely used brickwork that can be laid quickly because headers constitute only every fifth or sixth course, with all the other courses being stretchers.

English tile A smooth, flat, single-lap clay roofing tile with interlocking sides.

entablature In classical architecture, the total beam member spanning from column to column, including the architrave (bottom), frieze (middle), and cornice (top).

enterprise asset management Any software system designed to assist with facility management, including the maintenance of physical assets, proper and safe plant operation, and warranty and leasing information.

enthalpy The total amount of heat in a material or system, measured in Btus per pound.

enthalpy wheels Also referred to as heat wheels, a heat recovery system that removes moisture from the ambient air while also cooling the ventilated air by passing all incoming air over a desiccant-coated wheel. This process removes up to 85% of heat/moisture.

entitlement A claimant's right or grounds for recovering losses (as opposed to determining the amount of the losses).

entrained air Nearly spherical microscopic air bubbles that are purposely incorporated into mortar or concrete during mixing. Entrained air is added in order to lessen the effects of the freeze/thaw cycle on concrete that will be exposed to the weather.

entrance An exterior door, lobby, passage, or other designed point of entry into a building.

entrance facilities (EF) Equipment, such as hardware and cables, used to connect utilities to a facility.

entrapped air Voids in concrete that are of at least one millimeter in diameter, and which are the result of air other than entrained air.

envelope **1.** A term used to denote the extreme outside surface and dimensions of a building. **2.** An assembly of planes representing the limits of an area that may house a structure, i.e., a zoning envelope.

environmental audit An assessment of a facility's compliance with local and national environmental requirements.

environmental building consultant A specialist in sustainable building design who makes recommendations regarding the impact of building materials as they are produced, including waste generated in the construction process and over the product life cycle.

Environmental Protection Agency (EPA) An independent federal agency, formed in 1970, that establishes and controls rules for protecting the environment.

environmental remediation The process of treatment, containment, or removal of hazardous or toxic wastes to protect human health and the environment.

EOS Economy of scale.

EPAct The U.S. Energy Policy Act of 2005. Among its many components, it allows for tax incentives and loan guarantees for various energy-related projects and conservation.

EPA Identification Number A number assigned to each generator of hazardous waste that notifies the EPA of its activity.

EPDM roofing A single-ply roofing material manufactured of an elastomeric polymer synthesized from ethylene, propylene and a small amount of diene monomer. Because of its versatility in application methods, EPDM roofing may be used for any roof shape, slope, height, and climatic exposure.

epoxy Any of several synthetic, usually thermosetting, resins that provide superior adhesive power and hard, tough, chemical- and corrosion-resistant coatings.

epoxy joint In masonry, an unsealed joint in which epoxy resin is used in place of mortar.

epoxy resin A material containing an average of more than one epoxy group per molecule used in the preparation of special coatings or adhesives for concrete and as binders in epoxy resin mortars and concrete.



equalizing bed

equalizing bed A layer of sand, stone, or concrete laid in the bottom of a trench as a resting place for buried pipes.

equipment All the machinery, tools, and apparatus necessary for the proper construction and acceptable completion of a project.

equipment distribution area (EDA) A space housing equipment cabinets in a data center.



equipment ground

equipment ground **1.** A connection that provides a path to ground a conductor within the equipment. **2.** A ground connection to any metal part of a wiring system or equipment that does not carry current.

equity The residual value of a business or property, often calculated by subtracting the amount of outstanding liens or mortgages from the total value of the business or property.

equivalent direct radiation (EDR) A unit of heat delivery equal to 240 Btu per hour.

equivalent embedment length That longitudinal part of an embedded reinforcement that is capable of developing stress equivalent to that developed by a hook or mechanical anchorage.

equivalent length The resistance of a duct or pipe elbow, valve, damper, orifice, bend, fitting, or other obstruction to flow, expressed in the number of feet of straight duct or pipe of the same diameter that would have the same resistance.

equivalent round A term used to define the size of an oblong-shaped pipe. The equivalent round of the oblong pipe is equal to the diameter of a pipe with the same circumference.

equivalent thickness The solid thickness to which a hollow unit would be reduced if there were no voids and it had the same face dimensions.

erection The positioning and/or installation of structural components or preassembled structural members of a building, often with the assistance of powered equipment such as a hoist or crane.

erection bracing Temporary bracing used to hold framework in a safe condition during construction until enough permanent construction has been put in place to provide complete stability.

ergonomics The interaction between people and work, particularly the design of machines, chairs, tables, etc., to suit the body and to permit work with minimum fatigue.

erosion The gradual deterioration of metal or other material by the abrasive action of liquids, gases, and/or solids.

erratum An error in printing, writing, or editing, especially one included in a list of corrections appended to a book or publication in which the error appeared.

escalation An increase in the cost of performing construction work, resulting from performing the work in a later period of time and at a cost higher than originally anticipated in the bid.

escalator A continuously moving, power-driven, inclined stairway used to transport passengers between different floor levels of a building or into and out of underground stations.



escalator

escutcheon **1.** The protective plate, usually metal or plastic, that surrounds a door keyhole or a light switch. **2.** A pipe flange covering a floor hole through which the pipe passes. *See also* **faceplate**.



escutcheon

Essex board measure A chart appearing on a certain type of carpenter's steel square, listing the number of board feet contained in a board 1″ thick and of several standard sizes.

estimate The anticipated cost of materials, labor, equipment, or any combination of these for a proposed construction project.

estimated design load The sum of (a) the useful heat transfer, (b) the heat transfer to or from the connected piping, and (c) the heat transfer that occurs in any auxiliary apparatus connected to a heating or air-conditioning system.

estimated maximum load The calculated maximum heat transfer that a heating or air-conditioning system might have to provide.

estimating The process of determining the anticipated cost of materials, labor, and equipment of a proposed project.

estimator One who is capable of predicting the probable cost of a building project.

etching The process of using abrasion or corrosion (acid) to wear away the surface of glass or metal, often in a decorative pattern.

EtherCAT Ethernet for Control Automation Technology.

Ethernet Computer networking technology used for local area networks and wireless and metropolitan area networks. The Institute of Electrical and Electronics Engineers (IEEE) provides Ethernet standards.

ethylene glycol **1.** Antifreeze. **2.** A water-miscible alcohol used to transfer heat in heating and cooling provide stability in latex- and water-based paints during freezing conditions.

ettringite A naturally occurring mineral containing a large amount of sulfate calcium sulfoaluminate. Ettringite is also produced synthetically by sulfate attack on mortar and concrete.

eurythmy In architecture, orderliness or harmony of proportion.

evaporable water Water held by the surface forces or in the capillaries of set cement paste, measured as the water that can be removed by drying under specific conditions.

evaporative cooling Cooling achieved by the evaporation of water in air, thus increasing humidity and decreasing dry-bulb temperature.

evaporator The part of a refrigeration system in which vaporization of the refrigerant occurs, absorbing heat from the surrounding fluid and producing cooling.

event In a CPM (critical path method) arrow diagram, the starting point for an activity that cannot occur until all work preceding it has been performed. Indicated on the arrow diagram by a number enclosed in a circle.



event

e-waste Electronic equipment that contains lead, mercury, or other hazardous material, and is subject to federal and state disposal requirements.

excavation **1.** The removal of earth, usually to allow the construction of a foundation or basement. **2.** The hole resulting from such removal.



excavation

excavator **1.** A company or individual who contracts to perform excavation. **2.** Any of several types of power-driven machines used in excavation.

exception report A report sent to the EPA by a generator of hazardous waste. The exception report is released when the generator does not receive copies of hazardous waste manifest forms from transporters or disposers of wastes that the generator has shipped off-site for disposal.

excess reprocurement costs Additional costs that the government incurs following a default termination to reprocure the defaulted quantity of supplies, services, or unfinished work.

exchange The centrally located arrangement of communications equipment governing the connection of incoming and outgoing lines, including signaling and supervisory tasks.

exchange, private branch (PBX) A telephone exchange system that provides manually operated private telephone service within an organization (a company, for example) as well as access to the public telephone network.

excusable delay A delay to contract performance that is beyond the control, fault, or negligence of the contractor. If a delay is determined to be excusable, the government cannot initiate a termination for default.

executed **1.** Under contract law, a contract that has been signed by both parties. **2.** Work that has been completed.

exempt employees Employees exempt from overtime compensation by federal wage and hours guidelines.*

exfiltration The flow of air outward through walls, joints, or other apertures.

exfoliation **1.** The flaking, scaling, or peeling of stone or other mineral surfaces usually caused by physical weathering, but sometimes by heating or chemical weathering. **2.** The heat treatment of minerals for the purpose of expanding their original volume many times over.


exhaust fan

exhaust fan A device used to draw unwanted, contaminated air away from a particular room or area of a building to the outside.

exhaust fume hood A prefabricated hood unit that serves to confine noxious or toxic fumes for subsequent exhausting or filtration.

exhaust grille A grate or louvers through which contaminated air exits to the atmosphere.

exhaust shaft A duct through which exhaust air is carried to the outside atmosphere.

existing building In codes and regulations, an already completed building or one that prior laws or regulations allowed to be built.

existing conditions survey Inspection and documentation of a building's composition, configurations, and as-built conditions. Includes visual inspection, laboratory analysis, and often more invasive, destructive investigational procedures.

exit That part of an exit system that, because of its separation from the rest of the building by devices such as walls, doors, and floors, provides a reasonably safe and protected emergency escape route from a building.

exit access The corridor or door leading to an exterior exit.

exit control alarm An electronic device that activates an alarm when a fire exit door is opened.

exit corridor An enclosed passageway or corridor that connects a required exit with direct or easy access to a street or alley.


exit device (panic exit device)

exit device (panic exit device) An exit door locking device, consisting of a bar across the inside of a door that, when pushed, releases the door latch.

exit discharge That part of an exit system beginning at the termination of the exit at the exterior of a building and ending at ground level.

exit light An illuminating sign above an exit that identifies it as an exit.

exothermic Descriptive of a reaction during which heat is released.

expanded aluminum grating An aluminum grating manufactured by cutting and mechanically stretching a single piece of sheet aluminum.

expanded blast-furnace slag A cellular material, used as lightweight aggregate, derived from treating molten blast-furnace slag with water, steam, and/or other agents.

expanded clay Clay expanded to several times its original volume by the formation of internal gas caused by heating it to a semiplastic state.

expanded glass (foam glass) A thermal insulation with a closed-cell structure, manufactured by foaming softened glass so as to produce a myriad of sealed bubbles, and then molding the glass into boards and blocks.


expanded metal

expanded metal A type of open-mesh metal lath made by slitting and stretching sheet metal. Comes in different patterns and thicknesses.

expanded metal partition A partition constructed from thin framing or support members covered with heavy expanded metal lath and plastered on both sides to produce a solid finished product 1½″ to 2½″ thick.

expanded polystyrene (EPS) A type of foamed styrene plastic that has a high resistance to heat flow and a high strength-to-weight ratio. EPS is used as insulation, as an inexpensive glazing, and in formwork for concrete, among many other applications.

expanded rubber Closed-cell rubber manufactured from a solid rubber compound.

expanding bit (expansion bit) A drilling bit whose blade can be adjusted to bore holes of different diameters.

expanding plug A drain stopper usually located at the lowest point of a piping system. When inflated, the plug seals the pipe.

expansion bead In plastering, a metal strip placed between materials to allow for movement.

expansion bearing An end support of a span, which allows for the expansion or contraction of a structure.

expansion bend (expansion loop) In a pipe run, a usually horseshoe-shaped bend inserted to allow thermal expansion of the pipe.

expansion bolt (expansion anchor, expansion fastener, expansion shield) An anchoring or fastening device used in masonry, which expands within a predrilled hole as a bolt is tightened.


expansion joint

expansion coil An evaporator fabricated from tubing or pipe.

expansion joint In a building structure or concrete work, a joint or gap between adjacent parts, which allows for safe and inconsequential relative movement of the parts, caused by thermal variations or other conditions.

expansion joint cover The prefabricated protective cover of an expansion joint, which also remains unaffected by the relative movement of the two joined surfaces.

expansion joint filler Material used to fill an expansion joint to keep it clean and dry. Materials commonly used are felt, rubber, and neoprene.

expansion loop (expansion bend) A large radius loop in a pipeline that absorbs the longitudinal expansion and contraction in the line due to temperature changes.



expansion loop (expansion bend)

expansion sleeve A short length of metal or plastic pipe built into a wall or floor to allow for the inconsequential expansion and/or contraction of the element (usually another, smaller pipe) that passes through it.

expansion strip **1.** The material used in an expansion joint. **2.** Resilient insulating material used as a joint filler between a partition and a structural member.

expansion tank **1.** In a hot-water system, the tank that provides for the increased volume of the water heated in the heating tank below it. **2.** A device to control pressure in a fluid system by storing excess liquid.



expansion tank

expansion valve The valve that controls the flow of refrigerant to the cooling element in a refrigeration system.

expansive cement (expanded cement, expanding cement, sulfoaluminate cement) A type of cement whose set paste increases in volume substantially more than the set paste of Portland cement. Used in applications where the desired results include the compensation for volume decrease due to shrinkage, or the induction of tensile stress in reinforcement.

expediter One who monitors and facilitates the arrival of building materials or equipment to meet a progress schedule.

expert witness In a court case or other legal or arbitration proceeding, an individual who, because of his/her exceptional knowledge, experience, or skill in a particular field or subject is accepted by the court (or by those presiding over other legal or arbitration proceedings) as being qualified to render an authoritative opinion in matters relating to his/her field of expertise.

exploded view An illustration depicting the disassembled individual components in proper relationship to their assembled positions therein.

explosion-proof box Electrical equipment housing designed in compliance with hazardous location requirements to withstand an explosion that could occur within it and to prevent ignition by the explosion of flammable material, liquid, or gas that might externally surround it.



explosion-proof box

explosion-proof fixture Electric lighting fixture that will not explode or ignite when in contact with a flammable gas or liquid.

explosion welding The use of a controlled explosion to weld members together.

explosive rivet A rivet whose explosive-filled shank is exploded by striking it with a hammer after the rivet has been inserted.

exposed Refers to an unprotected or uninsulated “live” component of an electrical system whose location makes it susceptible to being inadvertently touched or approached by someone at an unsafe distance.

exposed aggregate The coarse aggregate in concrete work revealed when the surface layer of concrete paste is removed, usually before the full hardening of the concrete.



exposed aggregate

exposed area In roofing, the part of a shingle that is not covered by another shingle.

exposed masonry Any masonry construction whose only surface finish is a coat of paint applied to the face of the wall.

exposed nailing A method of nailing that leaves the nails exposed to the weather.

exposed suspension system A method of installing a suspended acoustical ceiling in which the panel-supporting grid is left exposed in a room.

exposure hazard The probability of a building’s exposure to fire from an adjoining or nearby property.

extended overhead Overhead costs accumulated during compensable delay periods when full production was not achievable.

extended surface A fitting, usually composed of metal fins or ribs, that provides additional surface area on a pipe or tube through which heat is transferred.



extended surface

extended use An increase in the function of a building, achieved by interventions such as rehabilitation or adaptive use.

extender **1.** An opaque, white, inert mineral pigment, such as calcium carbonate, silica, diatomaceous earth, talc, or clay, that is added to paint to provide texture, lower gloss, or reduce paint cost by providing bulk. **2.** A volume-increasing, cost-reducing additive in synthetic resin adhesives.

extensibility The capability of a sealant to be stretched in tension.

extension **1.** A wing, ell, or other addition to an existing building. **2.** The product of a quantity multiplied by a unit price. **3.** The completion of a mathematical equation. **4.** An agreement between parties extending to term of a contract.

extension casement hinge An exterior hinge on a casement window whose sash swings outward. The hinge is located so as to provide enough clearance to allow the cleaning of the hinged side from the inside when the window is open.


extension ladder

extension device Any device, other than an adjustment screw, used for accomplishing vertical adjustment.

extension flush bolt (extension bolt) A type of flush bolt whose head connects to the operating mechanism via a rod, which is inserted through a hole bored in the door.

extension ladder A ladder comprising more than one section, each of which slides within and locks on the other, thus allowing lengthening.

extension rule A rule containing an extendable, calibrated, sliding insert.

exterior-glazed Descriptive of glazing that has been set from the outside of a building.


exterior insulation and finish systems (EIFS)

exterior insulation and finish systems (EIFS) Exterior cladding assembly consisting of a polymer finish over a reinforcement adhered to foam plastic insulation that is fastened to masonry, concrete, building sheathing or directly to the structural framing. The sheathing may be cement board, gypsum sheathing or another acceptable substrate.

exterior paint Paint formulated with durable binder and pigment, making it suitable for exposure to weather.

exterior panel In a concrete slab, a panel with at least one of its edges not adjacent to another panel.

exterior plywood Plywood whose layers of veneer are bonded with a waterproof glue.

exterior stair An often legally required exit consisting of a series of flights of steps affixed to the structure but not enclosed.


exterior stair


exterior trim

exterior trim Any visible or exposed finish material on the outside of a building.

exterior wall An outer wall or vertical enclosure of a structure.

external vibration Brisk agitation of freshly mixed concrete by a vibrating device strategically positioned on concrete forms.

extra A work item performed in addition to the scope specified in the contract. Often involves an additional cost.

extraction The process of mechanically removing layers of old paint or other material and retaining a portion of the substrate for laboratory analysis.

extraction procedure toxicity The propensity of a substance to emit toxins under a specific test procedure, defined by the EPA, which uses an acid to extract the toxins from the substance in question.

extranet A shared communications network that uses Internet technology to allow collaborating parties to share information. Especially useful with large, fast-track projects that require extensive documents.

extra-strong pipe The common designation for steel or wrought iron pipe having wall thickness greater than that of standard-weight pipe.

extra work Any work, desired or performed, but not included in the original contract.

extruded section Structural sections formed by extrusion and used in light construction.

extruded tile A tile formed by pushing clay through a die and cutting it into specified lengths.


extruded section

extrusion coating A thin film of extruded molten resin, which is pressed onto a substrate to produce a coating with an adhesive.

eye **1.** In architecture, the opening in the uppermost portion of a cupola. **2.** The nearly circular center of the roll or volute of an Ionic capital. **3.** The middle roundel of a pattern or ornament. **4.** A hole through a member to provide access, such as for the passage of a pin. **5.** In tools, the receiving orifice in the head of the implement.

eye bolt An anchoring device comprising a threaded shank with a lopped head, designed to accept a hook, cable, or rope.

eyebrow A window or ventilation opening through the surface of a roof. Unlike a dormer, it forms no sharp angles with the roof, but rather is incorporated into the general horizontal line of the continuous roof, which is carried over it in a wave line.


eye bolt

eye of a dome The opening at the very top of a dome.

F

Abbreviations

f fine, focal length, force, frequency, fiber stress
F Fahrenheit, female, fill, fluorine
FA fresh air, fire alarm
fab fabricate, fabricated
fac facsimile
FAI fresh air intake
FAIA Fellow of the American Institute of Architects
FAO finish all over
FAR floor-area ratio
FAS free alongside ship, firsts and seconds
FBGS fiberglass
FBM foot board measure
fc, FC footcandle, compressive stress in concrete, extreme compressive stress
FCC Federal Communications Commission
fcc face-centered cubic
FDB forced draft blower
FDC fire department connection
fdn, fdtn, fds, FDN foundation, foundations
fdry foundry
Fe ferrum (iron)
FE fire escape
F.E. front end
FEA Federal Energy Administration
FEMA Federal Emergency Management Agency
FEP fluorinated ethylene propylene (Teflon)
FFA full freight allowance
FG fine grain, flat grain, finished grain
FHA Federal Housing Administration
FHC fire hose cabinet
FHWA Federal Highway Administration
FID flame ionization detector
Fig figure
fill filling
Fin finish
Fixt fixture
fl floor, fluid
Fl floorline, floor, flashing
flash flashing
FLG flooring
fl oz fluid ounce
Flr floor
FLUOR fluorescent
fm fathom
FM frequency modulation, Factory Mutual
Fmg framing
FML flexible membrane liner
FMT flush metal threshold
FMV fair market value
fndtn foundation
FOB free on board
FOC free of charge
FOHC free of heart centers
FOK free of knots

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

fount fountain

fp fireplace, freezing point

fpfg fireproofing

fpm feet per minute

FPRF fireproof

fps feet per second

fr frame

FR, Fr fire rating

frmg framing, forming

FRP fiber-reinforced plastic

frt freight

frwy freeway

FS federal specifications

FSES fire safety evaluation system

FST flat-seam tin

ft foot, feet

ftc footcandle

ftg footing

fth fathom

ft lb foot pound

ft sm feet surface measure

Furn furnish, furnished

fus fusible

fv face velocity

FW flash welding

fwd forward, four wheel drive

Definitions

fabricate **1.** To build, to construct, to manufacture. **2.** To make by fitting together standardized parts. **3.** To assemble in the shop, as to assemble a reinforced steel part.

Façade The exterior face of a building, sometimes decorated with elaborate detail.

face **1.** The surface of a wall, masonry unit, or sheet of material that is exposed to view or designed to be exposed in finish work. **2.** To cover the surface layer of one material with another, as to *face* a wall with brick or fieldstone. **3.** The surface area to be excavated during a construction project. **4.** The side of a hammerhead used to strike.

face block (faced block) A unit of concrete masonry with a plastic or ceramic face surface, often glazed or polished for special architectural uses.



face block (faced block)

face brick (facing brick) **1.** Brick manufactured to present an attractive appearance. **2.** Any brick that is exposed, such as on a fireplace.



face brick (facing brick)

faced insulation Any batt insulation with a moisture barrier on one or both sides. The barrier may be paper, plastic, or foil.

faced plywood Plywood that is faced with plastic, metal, or any material other than wood.

face frame cabinets Cabinets with a hardwood frame on the face of the cabinet that masks the raw edges of the sides, adds rigidity to the cabinet, and provides a strong base for attaching hinges.



face frame cabinets

face glazing The compound applied with a glazing knife after a light has been bedded, set, and fastened in a rabbeted sash.

face grain The grain on the face of a plywood panel. The face grain should always be placed at right angles to the supports when applying it to a roof or subfloor.

face mark A mark made on the face of a piece of lumber, usually in pencil or crayon, near the edge or end of the piece that identifies the work face of a planed timber.

face measure The measurement of the area of a board or panel. Face measure is not the same as board measure, except when the piece being measured is 1″ thick.

face mix A concrete mix bonded to the exposed surface of a cast stone building unit.

face mold **1.** A template used in ornamental woodworking to mark the boards from which pieces will be cut. **2.** A device used to examine the shape of wood and stone faces and surfaces.

face nailing Nailing perpendicular to the face of wood and through the face of the material.

face oiling A light coating of oil on the face of concrete panels to aid in removing the forms after the concrete sets.

faceplate Any protective and/or decorative plate such as an *escutcheon*.

face side The better, wide side of a rectangular piece of lumber.

face string (finish string) An exterior string, usually of better material or finish, placed over the rough string in the construction of a staircase.

face veneer Those veneers of higher grade and quality that are used for the faces of plywood panels, especially in the sanded grades. Face veneer is selected for decorative qualities rather than for strength.

face width The width of the face of a piece of dressed lumber. In tongued or lapped lumber, the face width does not include the width of the tongue or lap.



face width

facility In project work, this term usually refers to the constructed environment, e.g., buildings, structures, infrastructure, plant, and equipment.*

facility audit **1.** An assessment of the physical condition and functional performance of an organization's facilities. **2.** A review of activities at a facility or location, the purpose of which is to identify the improper storage, handling, or disposal of hazardous materials or waste.

facility engineer An engineer who provides technical expertise to ensure the optimal operation of a facility's plants, grounds and offices. Responsibilities include maintaining and improving the efficiency of existing equipment and systems while overseeing the installation of new equipment and systems.

facility management system (FMS) An electronic control system that helps facility managers maximize a facility's performance.

facility manager A professional who coordinates the planning, design, and management of a facility, including its systems, equipment, and furniture. A facility manager helps an organization meet its long-term strategic and operational objectives while daily maintaining a safe, efficient working environment.

facing block A concrete masonry unit having a decorative exterior finish.

factor of safety **1.** Stress factor of safety: the ratio of the ultimate strength, or yield point, of a material to the design working stress. **2.** Load factor of safety: the ratio of ultimate load, moment, or shear of a structural member to the working load, moment, or shear, respectively, assumed in design.



facing block

factory-built A reference to a construction, usually a dwelling, that is built, or at least partially preassembled, in a factory rather than *on site*. Most factory-built units are constructed in two or more modules, often complete with plumbing, wiring, etc. The modules are delivered to a building site and assembled there. Finish work is then performed. Factory-built houses are generally less expensive to build and quicker to erect because of savings gained through mass production and factory efficiencies.

factory finished A product that has been coated or stained as part of the manufacturing process.

factory primed A product to which an initial undercoat of paint has been applied.

factory select A grade of shop lumber containing 70% or more of No. 1 door stock, but having other defects, such as pitch or bark pockets, beyond the restrictions allowed in the No. 1 grade of lumber.

Fahrenheit (F) Temperature scale on which the freezing and boiling points of water are 32° and 212°, respectively.

failing wedge A V-shaped piece of steel, aluminum, or plastic that is driven it into the back cut when felling a tree. The purpose is to keep the saw from binding, and to help control the direction of the fall.

failure A deficiency of a structural element that makes it unable to continue the load-bearing function for which it was originally designed.

failure to perform When an owner or contractor, or both, does not perform each and all of his respective obligations in the construction contract.*

Fair Labor Standards Act (FLSA) An act of the Congress of the United States enacted in 1936, and the subject of numerous amendments to the present day. Commonly referred to as the Minimum Wage Law, it establishes a minimum wage for all workers with the exception of agricultural workers, and additionally provides a maximum of a 40-hour workweek for straight time pay for employees earning hourly wages.

fairlead A device such as a ring or a block of wood with a hole in it, through which cable or rope is led for alignment.



fairlead

fair market value A price that is fair and reasonable in light of current conditions in the marketplace.

fall The slope in a channel, conduit, or pipe, stated either as a percentage or in inches per feet.

falldown Those lumber or plywood items of a lesser grade or quality that are produced as an adjunct to the processing of a higher quality stock.

false attic An architectural addition, built above the main cornice of a structure, that conceals the roof rafters but has no rooms or windows.

false door A nonoperable door placed in a wall for architectural appearance.

false front A front wall that extends beyond the sidewalls and/or above the roof of a building to create a more imposing façade.

false heartwood Dark innerwood that has been colored by disease or fungi so that it resembles heartwood in color.

false joint A groove in a solid masonry block or stone that simulates the appearance of a joint.



false joint

false rafter A short extension added to a main rafter over a cornice.

falsework The temporary structure erected to support work in the process of construction. Falsework consists of shoring or vertical posting formwork or beams and slabs, and lateral bracing. *See also* **centering**.



falsework

fan brake horsepower (Bhp) The horsepower output of a fan as measured at the pulley or belt. Bhp includes losses due to turbulence and other inefficiencies.

fan-coil unit An air-conditioning unit that houses an air filter, heating or cooling coil, and a centrifugal fan, and operates by moving air through an opening in the unit and across the coils.


fan-coil unit

fancy butt A shingle with the butt end machined in a pattern. Fancy butt shingles are usually used on sidewalls to form geometric designs in the shingle pattern.

fanlight A semicircular or semielliptical window built above the opening of a door. A fanlight often has triangular panes of glass, in between radiating bars or leads, and resembles the form of an open fan.


fanlight

fan pressure curve The curve that represents the pressure developed by a fan operating at a fixed rpm at various air volumes.

fan suction box A specially designed 90° fitting installed at the fan inlet that reduces the inlet pressure loss created by system effect.

fan surge Turbulent flow caused when insufficient air enters the fan wheel to completely fill the space between the blades. Some of the air reverses its direction over a portion of the fan blade.

fan truss A truss with struts that radiate like the ribs of a fan, supported at their base by a common suspension member.

fascia (facia) **1.** A board used on the outside vertical face of a cornice. **2.** The board connecting the top of the siding with the bottom of a soffit. **3.** A board nailed across the ends of the rafters at the eaves. **4.** The edge beam of a bridge. **5.** A flat member or band at the surface of a building.


fascia (facia)

fastener Any mechanical device used to hold together two or more pieces, parts, members, etc.

fast-track construction A building method in which construction is begun on a portion of the work for which the design is complete, while design on other portions of the work is under way.

fat edge A ridge of paint at the bottom edge of a surface when too much paint has been applied or because the paint runs too freely.

fatigue The weakening of a material caused by repeated or alternating loads. Fatigue may result in cracks or complete failure.

fatigue failure The phenomenon of rupture that occurs when a material is subjected to repeated loadings at a stress substantially less than the ultimate tensile strength.

fatigue life **1.** The number of cycles of a specified loading that a given specimen can be subjected to before failure occurs. **2.** A measure of the useful life of similar specimens.

fatigue strength The maximum stress that can be sustained for a number of stress cycles without failure.

fat mix (rich mix) A mortar or concrete mix with a relatively high cement content. Fat mix is more easily spread and worked than a mix with the minimum amount of cement required for strength.

fat mortar (rich mortar) Mortar with a high percentage of cement. Fat mortar is sticky and adheres to a trowel.

fault **1.** A defect in an electrical system caused by poor insulation, imperfect connections, grounding, or shorting. **2.** A shifting along a plane in a rock formation that causes differential displacement.

faulting Differential vertical displacement of a slab or other member adjacent to a joint or crack.

faux bois French term for "false wood," referring to simulated wood grain. Also called *graining*.

feasibility study A thorough study of a proposed construction project to evaluate its economic, financial, technical, functional, environmental, and cultural advisability.

feather To blend the edge or finish of new material smoothly into an existing surface.

featherboard A safety device used to prevent table saw kickback.


featherboard

feather edge (featheredge) The beveling or tapering of the edge of one surface or surface coating where it meets another.


feather edge (featheredge)

feather joint A joint between two squared, closely butted boards made by plowing a groove along the length of each and fitting them with a common tongue.

Federal Communications Commission (FCC) A regulatory agency based in Washington, D.C., that was established by the Communications Act of 1934 to regulate broadcast communications (wire, radio, and television) in the United States.

Federal employer identification number A number assigned by the Internal Revenue Service to identify a business for tax purposes.

Federal Hazardous Substances Act The federal law that controls the use of hazardous constituents in consumer products.

Federal Home Loan Mortgage Corporation A government sponsored organization, nicknamed "Freddie Mac," that provides a secondary market for mortgages.

Federal Housing Administration (FHA) A division of the Department of Housing and Urban Development. The FHA works through lending agencies to provide mortgage insurance on private residences that meet the agency's minimum property standards. The FHA has also been charged with administering a number of special housing programs.

Federal Mediation and Conciliation Service An agency of the U.S. Department of Labor that acts as a mediator in the settlement of disputes as provided in the National Labor Relations Act of 1935 and the Labor Management Relations Act of 1947.

Federal National Mortgage Association A corporation that provides a secondary mortgage market for FHA-insured and VA-guaranteed home loans; commonly known as Fannie Mae.

fee Remuneration for professional services.

feeder **1.** An electrical cable or group of electrical conductors that runs power from a larger central source to one or more secondary or branch-circuit distribution centers. **2.** A tributary to a reservoir or canal. **3.** A bolt or device that pushes material onto a crusher or conveyor.

feeler gauge A gauge used to measure the thickness of a gap, consisting of a series of blades of graduated thicknesses.



feeder

fee simple An enduring, inheritable interest in land that may be legally honored until the death of all potential heirs of the original owner, and that the owner is free to convey at any time.

fell To cut down a tree. A faller fells a tree with a falling saw.

felt A fabric of matted compressed fibers, usually manufactured from cellulose fibers from wood, paper, or rags, or from glass fibers.

felt paper Paper sheathing used to insulate walls and to prevent infiltration of moisture.

femerell A ventilator, often louvered, used to draw smoke through a roof when a chimney is not provided.

fence A straight-edge guide mounted parallel to a saw blade to guide a cant as it passes through the saw.



felt

fence pliers Heavy-duty pliers used to cut thick wire. May also include a claw to remove pins and fasteners.

fender A protective bumper, sometimes of wood or old tires.

fenestration The layout and design of windows in a building.

feng shui An approach to interior design, based on Chinese ideals, that seeks to create harmonious surroundings, as in selecting light fixtures, arranging furniture, or determining the siting of a house.

ferrous metal Metal in which the principal element is iron.



fence pliers

ferrule **1.** A tube or metallic sleeve, fitted with a screwed cap to the side of a pipe to provide access for maintenance. **2.** A metal sleeve or collar attached to the end of a short cable in making a choker. The ferrule fits into the bell of the choker. Also called a *nubbin*. **3.** Spacer tube used in hanging metal gutter to prevent deforming of the gutter when attached.



ferrule

fiberboard A general term referring to any of various panel products, such as particleboard, hardboard, chipboard, or other types formed by bonding wood fillers using heat and pressure.

fibered plaster Gypsum plaster reinforced with fibers of hair, glass, nylon, or sisal.

fiberglass (fibrous glass, glass fiber) Filaments of glass formed by pulling molten glass into random lengths that are either gathered in a wool-like mass or formed as continuous threads. The wool-like form is used as thermal and acoustical insulation. The threadlike form is used as reinforcing material and in textiles, glass fabrics, and electrical insulation.

fiberglass reinforced plastic (FRP) A coating of glass fibers and resins applied as a protective layer to plywood. The resulting composite is tough and scuff resistant. It is used to manufacture containers, cooling towers, concrete forms, and shower stalls.

fiber optics The transmission of light pulses through bundles of fine, transparent fibers.

fiber-optic waveguides Fine, transparent fibers, usually thin filaments of glass or plastic, through which a light beam can be transmitted.

fiber saturation point The point of wood moisture content when the cell walls are completely saturated with water, but there is no water in the cell lumens and intercellular spaces.

fiber stress The longitudinal compressive or tensile stress in a structural member.

fibrous Resembling or composed of fibers.

fibrous concrete Concrete with glass or other fibers added to increase tensile strength.

fibrous plaster Cast plaster reinforced canvas, excelsior, or other fibrous material.

FICA A federal law that imposes a Social Security tax on employees, employers, and the self-employed.

fiddleback grain A rippling or undulating grain common to certain hardwoods, such as maple and sycamore.



fiddleback grain

fiducial mark A standard reference point or line used as a base in surveying.

field **1.** In masonry, an expanse of brickwork between two openings or corners. **2.** A term used to designate a construction project site. **3.** Occupation such as a trade, profession, or specialty. **4.** An area of floor, wall, or ceiling that is covered with tile or other preformed shapes that did not require cutting, as opposed to those areas along a border or edge.

field applied **1.** The application of a material, such as paint, at a job site, as opposed to being applied at a factory. **2.** The construction or assembly of components in the field.

field cost Engineering and construction costs associated with the construction site rather than with the home office.*

field engineer A representative of certain government agencies who oversees projects at the site. Also called a *project representative* or *field representative*.

field gluing A method of gluing plywood floors in which specially developed glues are applied to the top edges of floor joists. Plywood is then laid on the joists and nailed in place. The combination of gluing and nailing results in a stiffer floor construction and tends to minimize squeaks and nail popping.



field gluing

field inspection The reinspection of lumber or plywood in the field, usually at the buyer's location. A field inspection is requested by a buyer when he believes a delivered product to be inferior to that specified.

field-molded sealant A joint sealant in liquid or semisolid form that can be molded to the desired shape as it is installed in the joint.

field order In construction, a written order passed to the contractor from the architect to effect a minor change in work, requiring no further adjustment to the contract sum or expected date of completion.

field painting The painting of structural steel or other metals after they have been erected and fastened.

field rivet A rivet driven in a field connection of structural steel.

field sound transmission class (FSTC) An onsite measurement of the ability of a specific construction element, such as a wall partition, to block sound.

fieldstone **1.** Loose stone removed from the soil. **2.** Flat slabs of stone suitable for use in dry wall masonry.



fieldstone

field supervision The site supervisory work performed by a designated individual.

field work Any work performed at a job site.

figure The natural wood pattern that is created by growth rings, knots, and other deviations from regular grain.

figured glass Translucent sheet glass rolled with a bas-relief pattern on one face, providing high but obscure light transmission, with the degree of obscurity depending on the pattern.

filament A fine wire used in an incandescent lamp. The form is designated by a letter: S, straight wire; E, coil; CC, coiled coil.

file A handheld steel tool with teeth or raised oblique ridges, used for scraping, redressing, or smoothing metal or wood.

fill **1.** The soil or other material used to raise the grade of a site area. **2.** A subfloor leveling material.



fill

filled particleboard Particleboard to which plastic material has been applied to fill gaps between particles on the edges or faces.

filler **1.** Finely divided inert material, such as pulverized limestone, silica, or colloidal substances sometimes added to Portland cement, paint, or other materials to reduce shrinkage, improve workability, or act as an extender. **2.** Material used to fill an opening in a form.

filler block Concrete masonry units placed between joists or beams under a cast-in-place floor.

filler coat A coat of paint or varnish used as a primer.

filler metal Metal, added by a welding process, that has a melting point either approximately the same as or below the base metal.

fillet **1.** A narrow band of wood between two flutes in a wood member. **2.** A flat, square molding separating other moldings. **3.** A concave junction formed where two surfaces meet.

fill insulation **1.** Thermal insulation placed in prepared or natural cavities of a building. **2.** Any variety of loose insulation that is poured into place.

fill insulation

film-surfaced hardboard siding Hardboard to which a thin, dry sheet of paper, coated on both sides with a phenol-formaldehyde resin adhesive, has been applied. Such coatings are often printed with grain patterns in imitation of actual veneers, and are used as an inexpensive substitute for the higher priced veneer panels.

filter **1.** A device to separate solids from air or liquids, such as a filter that removes dust from the air or impurities from water. **2.** Granular matter placed on an area to provide drainage while preventing the entry and flow of sediment and silt.

filter bed A bed of granular material used to filter water or sewage.



filter bed

filter block A hollow, vitrified clay masonry unit used for trickling filter floors in sewage treatment plants.



filter block

filter fabric Tough fabric used in excavation that screens out soil while allowing the passage of water. Also called *engineering fabric.*

filtering faucet A faucet that filters out particles to improve the taste, appearance, and safety of water.

filtering faucet

fin A narrow, linear projection on a formed concrete surface, resulting from mortar flowing out between spaces in the formwork.

final acceptance The formal acceptance of a contractor's completed construction project by the owner, upon notification from an architect that the job fulfills the contract requirements. Final acceptance is often accompanied by a final payment agreed upon in the contract.

final completion A term applied for a project that has been completed according to the terms and conditions set forth in the contract documents.

final inspection An architect's last review of a completed project before issuance of the final certificate for payment.

final payment The payment an owner awards to the contractor upon receipt of the final certificate for payment from the architect. Final payment usually covers the whole unpaid balance agreed to in the contract, plus or minus any amounts altered by change orders.

final stress **1.** In prestressed concrete, the stress that remains in a member after substantially all losses in stress have occurred. **2.** The stress in a member after all loads are applied.

final waiver of liens A document prepared and executed by the contractor at the conclusion of the project stating that all subcontractors and material suppliers have been paid in full and that no mechanic's or materialmen's liens will be filed against the owner. Typically required to be filed with the owner as a condition of receiving the contractor's final payment or release of retention for the work he performed.*

fine aggregate **1.** Aggregate passing the ⅜″ (9.5-mm) sieve and almost entirely passing the No. 4 (4.75-mm) sieve and predominantly retained on the No. 200 (75-micrometer) sieve. **2.** That portion of an aggregate passing the No. 4 (4.75-mm) sieve and predominantly retained on the No. 200 (75-micrometer) sieve.

fine grading The final grading of ground to prepare for seeding, planting, or paving.



fine grading

fine-grained soil Soil in which the smaller grain sizes predominate, such as fine sand, silt, and clay.

fineness modulus A factor obtained by adding the total percentages by weight of an aggregate sample retained on each of a specified series of sieves, and dividing the sum by 100. In the United States the standard sieve sizes are No. 100 (150 micrometer), No. 50 (300 micrometer), No. 30 (600 micrometer), No. 16 (1. 18 mm), No. 8 (2.36 mm) and No. 4 (4.75 mm), and ⅜″ (9.5 mm), ¾″ (19 mm), 1½″ (38.1 mm), 3″ (75 mm), and 6″ (150 mm).

fines **1.** Soil that passes through a No. 200 sieve. **2.** Fine-milled chips used in the production of particleboard. Fines are larger than sander dust or wood flour and are used on the faces of particleboard panels, with coarser chips used as the core of the board. **3.** An undesirable by product of cutting wafers and strands for waferboard and oriented strand board.

finger joint A method of joining two pieces of lumber end to end by sawing into the end of each piece a set of projecting "fingers" that interlock. When the pieces are pushed together, these form a strong glue joint.



finger joint

finial A decoration on the point of a spire, pinnacle, or conical roof.



finial

finish **1.** The texture of a surface after compacting and finishing operations have been performed. **2.** A high-quality piece of lumber graded for appearance and often used for interior trim or cabinet work.

finish carpentry Carpentry that involves the installation of finish woods (and trim made of plastic or molded polyurethane materials) to provide a finished appearance to installed doors, windows, stairs, and other features of a building's interior. Elements include casing, baseboard, railings, mantels, louvers, paneling, and shelving.

finish carpentry

finished grade The top surface of an area after construction is completed, such as the top of a road, lawn, or walk.

finished size The final size of any completed object including trim.

finisher A tradesman who applies the final treatment to a concrete surface, including patching voids and smoothing.

finish floor The wearing surface of a floor.

finish flooring The material used to make the wearing surface of a floor, such as hardwood, tile, or terrazzo.

finish grinding **1.** The final grinding of clinker into cement, with calcium sulfate in the form of gypsum or anhydrite generally being added. **2.** The final grinding operation required for a finished concrete surface, such as bump cutting of pavement, fin removal from structural concrete, or terrazzo floor grinding.

finishing Leveling, smoothing, compacting, and otherwise treating surfaces of fresh or recently placed concrete or mortar to produce the desired appearance and service.

finishing machine A power-operated machine used to give the desired surface texture to a concrete slab.



finishing machine

finishing nail A slender nail, with a narrow head, that may be driven entirely into a wood surface, leaving a small hole that can be filled with putty or a similar compound.

finishing nail

Fink truss (Belgian truss, French truss) A symmetrical truss, formed by three triangles, commonly used in supporting large, sloping roofs.



Fink truss (Belgian truss, French truss)

fir **1.** A form of softwood indigenous to temperate zones, used principally for interior trim and framing. Varieties include Douglas fir, silver fir, balsam fir, and white fir. **2.** Although used most often to refer to Douglas fir, which is also a pseudo-fir, a general term for any of a number of species of conifers, including the true firs.

fire alarm system An electrical system, installed within a home, industrial plant, or office building that sounds a loud blast or bell when smoke and flames are detected. Certain alarms are engineered to trigger sprinkler systems for added protection.

fire area An area in a building enclosed by fire-resistant walls, fire-resistant floor/ceiling assemblies, and/or exterior walls with all penetrations properly protected.

fireback (chimney back) **1.** The heat-resistant back wall of a fireplace, built of masonry, cast metal or wrought metal, that withstands flames and radiates heat into the area served. **2.** A fire-resistant attachment to the back wall of a fireplace that keeps the masonry from absorbing too much heat.

fireblocking Installed building materials designed to resist spread of fire in concealed spaces to other areas of a building.*

fire box In a chimney, the metal box that contains the fire.

firebreak **1.** A strategic space between buildings, clusters of buildings, or sections of a city that helps to keep fires from leaping or spreading to surrounding areas before they can be contained. **2.** Any doors, walls, floors, or other interior structures engineered to go inside a building.

fire brick A flame-resistant, refractory ceramic brick used in fireplaces, chimneys, and incinerators.



fire brick

fire clay An earthy or stony mineral aggregate having as the essential constituent hydrous silicates of aluminum with or without free silica. Fire clay is plastic when sufficiently pulverized and wetted, rigid when subsequently dried, and of suitable refractoriness for use in commercial refractory products.

fire control damper An automatic damper used to close a duct if a fire is detected.

fire cut A sloping cut on the end of a wood beam or joist supported on a masonry wall. If somewhere along its length the joist or beam burns through, injury to the wall is minimized.

fire detection system A series of sensors and interconnected monitoring equipment that detect the effects of a fire and activate an alarm system.

fire division wall A wall that subdivides one or more floors of a building to discourage the spread of fire.

fire door **1.** A highly fire-resistant door system, usually equipped with an automatic closing mechanism, that provides a certain designated degree of fire protection when it is closed. **2.** The opening in a furnace or a boiler through which fuel is added.

fire-door rating A system of evaluating the endurance and fire resistance of door, window, or shutter assemblies, according to standards set by Underwriters Laboratories Inc., or other recognized safety authorities. Ratings of A through F are assigned in descending order of their effectiveness against fire.

fire endurance **1.** The length of time a wall, floor/ceiling assembly, or roof/ceiling assembly will resist a standard fire without exceeding specified heat transmission, fire penetration, or limitations on structural components. **2.** The length of time a structural member, such as a column or beam, will resist a standard fire without exceeding specified temperature limits or collapse. **3.** The length of time a door, window, or shutter assembly will resist a standard fire without exceeding specified deformation limits.

fire escape A continuous, unobstructed route of escape from a building in case of fire, sometimes located on the outside of an exterior wall.

fire extinguisher A portable device for immediate use in suppressing a fire. There are four classes of fires: A, B, C, or D. A single device is designed for use on one or more classes.



fire extinguisher

fire-extinguishing system An installation of automatic sprinklers, foam distribution system, fire hoses, and/or portable fire extinguishers designed for extinguishing a fire in an area.



fire-extinguishing system

fire hazard The relative danger that a fire will start and spread, that smoke or toxic gases will be generated, or that an explosion will occur, endangering the occupants of a building or area.

fire-hazard classification A designation of high, ordinary, or low assigned to a building, based on its potential susceptibility to fire, judged by its contents, functions, and the flame-spread rating of its inner furnishings and finishes.

fire hydrant A supply outlet from a water main, for use in firefighting.



fire hydrant

fire load (fire loading) The amount of flammable contents or finishes within a building per unit of floor area, stated either in pounds per square foot or Btus per square foot.

fire management panel A fire alarm control unit consisting of multiple single-zone fire alarm control modules, a telephone module, an HVAC module, and an audio communications module.

fire partition An interior partition that does not fully qualify as a fire wall, but has a fire endurance rating of not less than two hours.

fireproof **1.** Descriptive of materials, devices, or structures with such high resistance to flame that they are practically unburnable. **2.** To treat a material with chemicals in order to make it fire resistant.

fireproofing The use of fire-resistant materials for the protection of structural members to insure structural integrity in the event of fire.



fireproofing

fireproof wood Chemically treated wood that is fire resistive. No wood can be completely fireproof, but wood can be treated so that it is highly resistant to heat and flame and very difficult to ignite under ordinary circumstances.

fire protection The practice of minimizing the probable loss of life or property resulting from fire, by fire-safe design and construction, the use of detection and suppression systems, establishment of adequate firefighting services, and training building occupants in fire safety and emergency evacuation.

fire-protection sprinkler system An automatic fire-suppression system, commonly heat activated, that sounds an alarm and deluges an area with water from overhead sprinklers when the heat of a fire melts a fusible link.

fire-protection sprinkler valve A valve, normally open, that is used to control the flow of water in a sprinkler system.

fire-rated system Wall, floor, or roof construction using specific materials and designs that have been tested and rated for conformance to fire safety criteria, such as the flame spread rate.

fire resistance **1.** The property of a material or assembly to withstand fire, characterized by the ability to confine a fire and/or to continue to perform a given structural function. **2.** The property of a material or assembly that makes it so resistant to fire that, for a specified time and under conditions of a standard heat intensity, it will not fail structurally and will not permit the side away from the fire to become hotter than a specified temperature.

fire-resistant door A door designed to confine fire to one part of a structure, keeping it from spreading through an entire building. It may be a solid-core wooden door, or one sheathed in metal, depending on the intended location. Doors are rated for the projected time they could be expected to perform their function during a fire. Most building codes require that the door between living quarters and a garage be fire resistant.

fire-resistive construction Construction in which the floors, walls, roof, and other components are built exclusively of noncombustible materials, with fire-endurance ratings equal to or greater than those mandated by law.

fire-retardant finish Paint composed in part of noncombustible substances such as silicones, chlorinated waxes and resins, and antimony oxide, used to protect combustible surfaces, inhibiting the rapid spread of flames.

fire-retardant wood Wood chemically impregnated or otherwise treated so that the fire hazard has been reduced.

fire separation A floor or wall, with any penetrations properly protected, having the fire endurance required by authorities and acting to retard fire spread in a building.

fire shutter A complete metal shutter assembly with the fire endurance required by code. The rating depends on the location and nature of the opening.

firestat A fixed thermostat in an air-conditioning system, preset at a temperature required by code or other authorities, usually 125°F (52 °C).

firestop **1.** A short piece of wood, usually a 2″ × 4″ or 2″ × 6″, placed horizontally between the studs of a wall. Firestops are equal in width to the studs. They are usually placed halfway up the height of the wall to slow the spread of fire by limiting drafts in space between the sheathing on the two sides of the wall. Building codes usually do not require firestops in walls that are less than 8' high. **2.** Masonry units placed in wood framed walls.



firestop

fire tower A vertical enclosure, with a stairway, having the fire endurance rating required by code and used for egress and as a base for fire fighting.

fire wall An interior or exterior wall that runs from the foundation of a building to the roof or above, constructed to stop the spread of fire.

fir & larch A mixture of Douglas fir and western larch, sold as either individual species or as one species grouping. The two species are intermixed because they have similar characteristics and are used in similar ways.

firing The controlled-heat treatment of ceramic or brick ware in a kiln or furnace.

first coat The initial application of mortar, known as *base coat* in two-coat work, and *scratch coat* in three-coat work.

first in, first out (FIFO) A type of accounting for inventory in which items purchased first are assumed to be the first to be sold. An accountant will compute the cost and profit on the oldest or first in the inventory.

first mortgage The mortgage or security in a property that takes precedence over all other mortgages on the property.

fished joint A butted timber joint made using fishplates.



fished joint

fish scale A fancy butt shingle pattern with the exposed portion of the shingle rounded. When used as siding, the overall effect is the pattern of fish scales.

fitch A thin, long-handled paintbrush used especially for touching up recessed areas.

fitting **1.** A standardized part of a piping system used for attaching sections of pipe together, such as a coupling, elbow, bend, cross, or tee. **2.** The process of installing floor coverings around walks, doors, and other obstacles or projections. **3.** In electrical wiring, a component, such as a bushing or locknut, that serves a mechanical purpose rather than an electrical function.



fitting

fit-up The construction necessary within the demising walls of a leased space, including partitions, finishes, fixtures, lighting, power, equipment, etc., allowing the space to be used for its leased purpose.

fixed assets Assets, such as real property, that are not readily converted to cash.

fixed beam A structural beam with fixed, as opposed to hinged, connections.

fixed costs These costs can be defined in two different ways. In total, fixed costs remain the same as volume changes. On a per-unit basis, fixed costs decline as volume increases. Examples include office rent, administrative salaries, insurance, and office supplies.

fixed fee A fixed amount specified in a contract to compensate a contractor for all materials and services required to complete the project.

fixed light A window or portion of a window that does not open. Also referred to as *fixed sash*.



fixed light

fixed limit of construction cost A maximum amount to be paid for a construction job as specified in the agreement between owner and architect.

fixed plate heat exchanger A static device that transfers sensible heat through plates separating a warm air stream from a cold air stream.

fixed-price contract A type of contract in which the contractor agrees to construct a project for an established price, agreed in advance.

fixed-rate mortgage A mortgage on which the interest rate remains the same through the period of the loan.

fixed retaining wall A retaining wall supported both at its top and bottom.

fixing The installation of glass panels in a ceiling, wall, or partition. Fixing is distinct from glazing, which covers most other uses, such as the installation of glass in windows, doors, and showcases.

fixture **1.** An electrical device, such as a luminaire, attached to a wall or ceiling. **2.** An article that becomes part of real property by virtue of being merged or affixed to it, although it was originally a distinct item of personal property.



fixture

fixture drain A drain that leads from the trap of a fixture to another drainpipe.

fixtures Tangible goods that are permanently attached to, or embedded in, real property so that they are considered to be part of the real property.

fixture supply The pipe connecting a plumbing fixture to a supply line.



fixture supply

fixture unit A measure of the rate at which various plumbing fixtures discharge into a drainage system, stated in units of cubic volume per minute.

fixture whip A flexible wiring system used between the junction box and lighting fixture.

flagging **1.** A walk or patio paved with flagstones. **2.** The process of setting flagstones. *See also* **flagstone**.



flagging

flagstone A flat, irregular-shaped stone, usually 1″ to 4″ thick, used as pedestrian paving or flooring. Flagstones are set in mortar or aggregate outdoors and in mortar indoors.

flame cleaning A method of cleaning mill scale, moisture, paint, and dirt from steel by applying a hot flame.

flame cutting Cutting metal with an oxyacetylene torch.

flame ionization detector An ionization detector that uses hydrogen flame to generate ions.

flameproof Able to resist the spread of flame and not easily ignited, but having less fire resistance than fire-retardant substances.

flame-retardant Treated to resist flame spread and ignition.

flame-spread rating A numerical value given to a material designating its resistance to flaming combustion. Materials can have a rating of 100, as in untreated lumber, to 0, as in asbestos sheets.

flame treating A process by which inert thermoplastic materials and objects are prepared to receive paints, adhesives, lacquers, and inks by immersion in open flame, causing surface oxidation.

flammability A material's capacity to burn.

flammable Capable of being ignited easily, burning intensely, or having a rapid rate of flame spread.

flange **1.** A projecting ring, ridge, or collar placed on a pipe or shaft to strengthen, prevent sliding, or accommodate attachments. **2.** The longitudinal part of a beam, or other structural member, that resists tension and compression.

flange angle An angle shape used as one of the parts making up the flange of a built-up girder.

flange union A method of connecting threaded pipe using a pair of flanges screwed onto the ends of the pipe and bolted together.



flange

flapper The moving part of the flush valve in a toilet that allows water to leave the tank during the flush cycle.

flap trap (flap valve) A hinged flap within a plumbing system that restricts water flow to one direction, preventing backflow.

flaring tool A tool used to flare the end of a pipe for a fitting.

flash **1.** To make a joint weathertight using flashing. **2.** An intentional or accidental color variation on the surface of a brick. **3.** A variation in paint color resulting from variable wall absorption. **4.** The conversion of condensate into steam.



flaring tool

flash chamber A tank placed between the expansion valve and evaporator in a refrigeration system to separate and bypass any flash gas formed in the valve.

flashing A thin, impervious sheet of material placed in construction to prevent water penetration or direct the flow of water. Flashing is used especially at roof hips and valleys, roof penetrations, joints between a roof and a vertical wall, and in masonry walls to direct the flow of water and moisture.



flashing

flashing block A concrete masonry unit with a slot cast in one face to receive and hold one edge of a flashing.

flashing cement A mixture of solvent and bitumen, reinforced with inorganic glass or other fibers, and applied with a trowel.

flash point **1.** The minimum temperature at which a combustible liquid will give off sufficient vapor to produce a combustible mixture when mixed with air and ignited. Defined flash points are for specific enclosure conditions and ignition energy. **2.** The temperature at which a substance will spontaneously ignite.

flash welding A welding process that joins metals with the heat produced by the resistance to an electric current between the surfaces of the metals, followed by application of pressure.

flat **1.** Descriptive of a structural element having no slope, such as a flat roof. **2.** One floor of a multilevel building, or full-floor apartment. **3.** Descriptive of low-gloss paint, used either as an undercoat or as a final coat. **4.** A thin iron or steel bar with a rectangular cross section.

flat arch An arch with slight curvature.

flat-chord truss A truss with the top and bottom chords nearly flat and parallel.

flat coat An intermediate coat of paint applied between the primer and finish coat.

flat enamel brush A brush used to apply smooth films of enamel on woodwork, about 2″ to 3″ (5 to 7.5 cm) wide with flagged and tapered bristles.



flat-chord truss

flat face Pipe flanges with the entire face of the flange faced straight across. These flanges use a full face gasket. Commonly employed for pressures of less than 125 lbs.

flathead **1.** A screw or bolt with a flat top surface and a conical bearing surface. **2.** A rivet with a flattened head.

flat jack A hydraulic jack made of light-gauge metal welded into a flat rectangular shape that expands under hydraulic pressure.

flat molding A thin, flat molding used only for interior and exterior finish work.

flat paint A paint that dries to a low gloss or flat finish.

flat plate A flat slab without column capitals or drop panels.



flat plate

flat plate collector A panel of metal or other suitable material used to convert sunlight into heat. Flat plate collectors are usually a flat black color and transfer the collected heat to circulating air or water.



flat plate collector

flat rolled Steel plates, sheets, or strips manufactured by rolling the steel through flat rollers.

flat roof A roof with only enough pitch to allow drainage.

flat sawing Sawing logs with parallel cuts, a conversion method that wastes less timber than others.

flat seam A seam between two joined sheets of metal, formed by turning up, folding, flattening, and finally soldering the edges.

flat skylight A skylight installed in a horizontal position, slanted only enough to permit rainwater runoff.

flat slab A concrete slab reinforced in two or more directions, generally with drop panels at supports, but without beams or girders.

flat spot A spot on a glossy painted surface that fails to absorb the paint properly, usually because of a porous place on the undercoat, resulting in a flat finish that flaws the appearance of the surface.

flatwork A general term that refers to any concrete slab that requires finishing, such as a walkway or floor.

Flemish bond A brick wall laid up with alternate headers and stretchers in each course. Headers in the next course are centered over the stretchers in the course below.



Flemish bond

flexible connector **1.** In ductwork, an airtight connection of nonmetallic materials installed between ducts or between a duct and fan to isolate vibration and noise. **2.** A connector in a piping system that reduces vibration along the pipes and compensates for misalignment. **3.** An electrical connection that permits movement from expansion, contraction, vibration, and/or rotation.



flexible connector

flexible coupling A mechanical connection between rotating parts that adapts to misalignment, such as a universal joint.

flexible membrane liner (FML) A liner used to contain liquids or runoff in soil or on the soil surface.

flexible metal conduit A flexible raceway of circular cross-section for pulling electric cables through.

flexible-metal roofing Roof coverings of flat sheet metal, such as copper, galvanized iron, or aluminum.

flexible mounting A flexible support for machinery to reduce vibration between the machinery and its foundation or slab. Flexible mountings are usually made of rubber, neoprene, steel springs, or a combination of these.

flexible pavement A pavement structure that maintains intimate contact with and distributes loads to the subgrade and depends on aggregate interlock, particle friction, and cohesion for stability. Cementing agents, where used, are generally bituminous materials, as contrasted to Portland cement in the case of rigid pavement. *See also* **rigid pavement**.

flexible seamless tubing A seamless, welded, or soldered metal tube widely used for volatile gases and gases under pressure.

flexural bond In prestressed concrete, the stress between the concrete and the tendon that results from external loads.

flexural rigidity A measure of stiffness of a member, indicated by the product of the modulus of elasticity and moment of inertia divided by the length of the member.

flight A run of steps without intermediate landings.

flight header A horizontal structural member used to support stair strings at a floor or platform.

flight rise The vertical distance between two levels connected by a flight of stairs.

flight run The horizontal distance between top and bottom risers in a flight of stairs.

flitch **1.** A log, sawn on two or more sides, from which veneer is sliced. **2.** Thin layers of veneer sliced from a cross section of a log, as opposed to turning the log on a lathe and peeling from the outer edge in a continuous ribbon. Flitch veneers are often kept in order as they are sliced from a log. This provides a pattern to the veneer after it is laid up in panels. Panels that are laid up with matching flitches are said to have a flitch pattern. **3.** A product cut from a log by sawing on two sides and leaving two rounded sides, often used for joinery.

flitch beam (flitch girder, sandwich beam) A beam built up by two or more pieces bolted together, sometimes with a steel plate in the middle. The pieces, or flitches, are cut from a squared log sawn up the middle. The outer faces of the log are placed together, with their ends reversed to equalize their strength.

flitch plate The steel plate pressed between components of a flitch beam.

float **1.** A tool, usually of wood, aluminum, magnesium, rubber, or sponge, used in concrete or tile finishing operations to impart a relatively even but still open texture to an unformed fresh concrete surface. **2.** To rest by a dozer blade's own weight or to be held from digging by upward pressure of a load of dirt against its mold board. **3.** A body floating on water, which opens a valve in a water tank when the water level falls. **4.** A tool used to polish marble. **5.** In manufacturing, the amount of material in a system or process, at a given point in time, that is not being directly employed or worked upon. **6.** In projects, the amount of time that an activity may slip in its start and completion before becoming critical.*



float

float coat A finish coat of cement paste applied with a float.

floated coat (topping coat) A layer of plaster applied to a surface with a float, usually the intermediate coat between the scratch coat and the finish coat.

float finish A rather rough concrete surface texture obtained by finishing with a float.



floated coat (topping coat)

float glass A high-quality, flat glass sheet with smooth surfaces, manufactured by floating molten glass on a bed of molten metal at a temperature high enough for the glass to flow smoothly.

floating The operation of finishing a fresh concrete or mortar surface by use of a float, preceding troweling when that is the final finish.

floating floor A floor used in sound-insulating construction. The finish floor assembly is isolated from the structural floor by a resilient underlayment or by resilient mounting devices for machinery. The construction isolates machinery from the building frame.

floating foundation A reinforced concrete slab designed to move with the surface of the ground without structural damage.

floating wood floor A floating wood floor constructed on a layer of resilient material that isolates it from the building structure.

float scaffold A large platform supported by ropes from overhead.

float trap A steam trap regulated by a float in the condensate chamber.

float valve (float-controlled valve) A valve controlled by a float in a chamber, such as the float valve in a tank for a water closet.


float valve (float-controlled valve)

flood coat The top layer of bitumen poured over a built-up roof, which may have gravel or slag added as a protective layer.

flooding The stratification of different colored pigments in a film of paint.

floodlight **1.** A projector type of luminaire designed to light an area or object to a level of illumination higher than the surrounding illumination. **2.** A metal housing containing one or more lamps used to illuminate a stage uniformly.

floodplain A land area that may be subject to flooding. Used in plot plans and to determine suitability for construction and insurability.

floor **1.** The surface within a room upon which one walks. **2.** The horizontal division between two stories of a building, formed by assembled structural components or a continuous mass, such as a flat concrete slab.

floor/area ratio The ratio of the total floor area of a building to the area of the building lot.

floor beam Any beam that supports the floor of a building or the deck of a bridge.


floor beam

floor box A metal electrical outlet box providing outlets from conduits in or under the floor.

floor cavity In the science of lighting, the area formed by the workplane, the floor, and the walls between the two.

floor clearance The distance between the bottom of a door and the finished floor or threshold.

floor closer A device installed in a recess in the floor below a door used to regulate the opening and closing swing of the door.

floor drain A fixture set into a floor, used to drain water into a plumbing drainage system.


floor drain

floor framing Structural supports for floor systems, including joists, bridging, and subflooring.


floor framing

floor furring Wood furring used to raise a finished floor above the subfloor and provide a space for piping or conduit.

floor hatch A unit with a hinged panel, providing access through a floor.

floor hole An opening in a floor, roof, or platform measuring less than 12″ in its least dimension, so that a person cannot fall through.

flooring **1.** A tongued and grooved piece of lumber used in constructing a floor. Flooring is sold mostly in superior and prime grades, and is produced either as vertical grain or flat grain. **2.** Any finished floor material.

flooring saw A handsaw with teeth on both edges and a blade that tapers to a narrow point, used to cut holes in wood floors.

floor joist Any light beam that supports a floor.

floor load The live load for which a floor has been designed, selected from a building code, or developed from an estimate of expected storage, equipment weights, and/or activity.

floor panel A prefabricated section of floor, consisting of finish floor, subfloor, and joists.

floor pit Any deep recess in a floor used to provide access to machinery, such as an elevator pit.


floor pit

floor plan A drawing showing the outline of a floor, or part of a floor, interior and exterior walls, doors, windows, and details such as floor openings and curbs. Each floor of a building has its own floor plan.

floor receptacle An electric outlet set flush with the floor or mounted in a short pedestal at floor level.


floor receptacle

floor sealer A liquid sealer applied with a brush, sprayer, or squeegee to seal floor surfaces, such as concrete or wood.

floor slab A structural slab, usually concrete, used as a floor or a subfloor.


floor slab

floor span **1.** The distance, in inches, between the centers of floor joists in a floor system. **2.** The span covered by floor joists between supports.

floor stop A door stop mounted on the floor.

floor system The entire system of components that makes up a floor, including joists, subfloor, finish floor, etc.

floor tile **1.** Modular units used as finish flooring. Floor tile may be comprised of resilient (vinyl, rubber, or cork), ceramic, or masonry materials. **2.** Structural units used for floor or roof slab construction.

floor truss A manufactured truss used as a floor joist.

floor-type heater (floor furnace) An air-heating unit mounted below a floor grille or grate. Warm air rises from the center of the grille and cold air returns at the perimeter of the grille.

floor underlayment Particleboard, plywood, waferboard, or similar products used on a subfloor to provide a smooth surface on which to lay the finish floor.

floor varnish A tough, durable varnish used on floors.



floor underlayment

flow control valve A cylindrical pressure-compensating valve that regulates the flow of water. Rated in gpm or gpd.

flow-downs Clauses from a prime contractor's contract with the government that are incorporated into the prime's subcontracts.

flow pressure The pressure at or near an orifice during full fluid flow.

flow reducer A water-conserving mechanism attached downstream from a building's water shutoff valve that reduces the amount of water flow received from the street.

flow trough A sloping trough used to convey concrete by gravity flow from a transit mix truck, or a receiving hopper to the point of placement. *See also* **chute**.

flow welding A welding technique that brings metal to welding temperature by pouring a molten filler metal over it.



flow trough

flue **1.** A noncombustible and heat-resistant passage in a chimney used to convey products of combustion from a furnace fireplace or boiler to the atmosphere. **2.** The chimney itself, if there is a single passage.

flue damper An automatic door in a furnace or boiler's flue that closes when the burner is off, reducing heat loss.

flue grouping The consolidation of multiple flues in one chimney or stack to limit the number of vertical shafts through a structure.

flue lining (chimney lining) The lining of a chimney flue composed of heat-resistant firebrick or other fireclay materials, which prevents fire, smoke, and gases from escaping the flue to contaminate surroundings.



flue lining (chimney lining)

flue pipe A tight duct that conveys products of combustion to a chimney or flue.

fluidifier An admixture employed in grout to decrease the flow factor without changing water content.

flume A channel made of wood, metal, or concrete and used for drainage purposes on a grade, trestle, or bridge.



flue pipe

fluorescence Visible light generated and emitted from a substance such as a phosphor by absorbing radiation of shorter wavelengths.

fluorescent lamp A low-pressure mercury electric-discharge lamp in which a phosphor coating on the inside of the tube transforms some of the ultraviolet energy generated by the discharge into visible light.

fluorescent lighting fixture A luminaire designed for fluorescent lamps.

fluorescent pigments Pigments that absorb ultraviolet radiant energy and convert it to brilliant, visible light.

fluorescent reflector lamp A fluorescent lamp with the coating on only a part of its cross-section so that the light produced will be directed.

fluorescent strip A luminaire in which fluorescent lamps are mounted on a wiring channel containing the ballast and lamp sockets. Usually reflectors or lenses are not used.



fluorescent strip

fluorescent U-lamp The tubular fluorescent lamp bent at 180° through its center, forming a U-shape.

fluorinated ethylene propylene (FEP) A soft plastic copolymer with relatively low tensile strength, high chemical resistance, and low coefficient of friction. Applications include coatings and protective linings, chemical and medical equipment, extruded insulation and glazing film for solar panels. A common brand name is Teflon®.

fluosilicate Magnesium or zinc silica-fluoride used to prepare aqueous solutions sometimes applied to concrete as surface-hardening agents.

flush **1.** Having a surface or face even with the adjacent surface. **2.** To send a quantity of water down a pipe to clean, fill, or empty it.

flush bushing In plumbing, a bushing without a shoulder and engineered to fit flush into the fitting with which it connects.

flush-cup pull A door pull for a sliding door. The pull is mortised flush into the door and has a curved recess serving as a finger grip.

flush door A door with flush surfaces and concealed structural parts.

flush glazing Glazing in which glass is set in a channel, which may be formed by a rabbet



flush-cup pull

and stops, in a frame. The glazing, formed or a compound, is flush with the frame at the top of the channel.

flush-head rivet A rivet with a countersunk head.

flush joint Any joint with its surface flush with the adjacent surfaces.

flushometer (flushometer valve) A flushing valve, designed for use without a flush tank or cistern, that is activated by direct water pressure to deliver a certain quantity of water for flushing needs.



flush joint

flushometer (flushometer valve)

flush panel A panel in which the exposed surface is in the same plane as the exposed surfaces of the surrounding frame.

flush paneled door A door with one or both surfaces in the same planes as the surfaces of the rails and stiles.

flush plate In electricity, the metal or plastic cover that shields the flush wiring device in a wiring box and provides covering for an outlet or switch, with holes cut into its face to accommodate switch handles and plugs.

flush switch An electrical switch installed in a flush wall box in such a way that only its front face is exposed to view.



flush tank

flush tank A tank that holds water for flushing one or more plumbing fixtures.

flush valve A valve installed in the bottom of a toilet tank to discharge the water needed to flush the fixture.

flush wall box A wall box that houses an electric device and is embedded in a wall, floor, or ceiling with its exposed face in the same plane as the surrounding surface.



flush wall box

flute In architecture, one of multiple grooves or channels of semicircular to semielliptical sections, used to decorate and to embellish members, such as the shafts of columns.

flying bond A masonry bond formed by laying occasional headers at random intervals.

flying scaffold Staging suspended by ropes or cables from outrigger beams attached at the top of a structure.

flying shore A horizontal member that provides temporary support between two walls.

fly rafter A gable-end rafter on a roof overhang that runs parallel to the common rafters and is supported by the lookout rafter.



flying scaffold

flywheel effect The tendency of a building to retain heat due to its mass-thermal-inertia.

foam concrete A lightweight, cellular concrete made by infusing an unhardened concrete mixture with prepared foam or by generating gases within the mixture.

foam core The center of a plywood *sandwich panel*, consisting of plastic foam between wood veneers. The foam may be introduced in a liquid form that is forced under pressure into a space between the wood veneer skins, or the skins may be applied to a rigid plastic foam board.

foam glass (cellular glass, expanded glass) A thermal insulation made by foaming glass with hydrogen sulfide. Foam glass has a closed cell structure and is a low fire hazard material. It is manufactured in the form of block or board with a density of 9 to 10 lb. per cu. ft. (14 to 16 kg per cu m).

foaming agent A substance incorporated into plastic mixtures of concrete, rubber, gypsum, or other materials that helps to produce a light foamy consistency by releasing gases into the mixture.

foam-in-place insulation A plastic foam employed for thermal insulation, prepared by mixing an insulation substance with a foaming agent just before it is poured or sprayed with a gun into the enclosed receptacle cavities.

fog The visibility and path of the effluent air stream exiting a cooling tower and remaining close to the ground.

fog curing **1.** The storage of concrete in a moist room in which the desired high humidity is achieved by the atomization of fresh water. **2.** The application of atomized fresh water to concrete, stucco, mortar, or plaster.

fog sealed Descriptive of surfaces lightly treated with asphalt without a mineral cover.

foil **1.** In masonry, one of multiple circular or nearly circular holes, set tangent to the inside of a larger arc, that meet each other in pointed cusps around the arc's inner perimeter. **2.** A metal formed into thin sheets by rolling.

foil-backed gypsum board A gypsum board with aluminum foil on one face. The foil acts as a vapor barrier.

folded-plate construction A type of construction used with span roofs. Thin, flat elements of concrete, steel, or timber are connected rigidly at angles to each other, similar to accordion folds, to form members with deep cross-sections.

folding door

folding door An assembly of two or more vertical panels hinged together so they can open or close in a confined space. A floor- or ceiling-mounted track is usually provided as a guide.

folding partition **1.** Large panels hung from a ceiling track, sometimes supported also by a floor track, which form a solid partition when closed, but stack together when the partition is maneuvered into an open position. **2.** A partition, faced with fabric and hung from a ceiling track, that folds up flexibly when opened like the pleated balloons of an accordion.



folding partition

folding rule A rule made of lengths that are joined by pivots so it can be folded when not in use.

foliated joint A joint made between two boards by fitting their rabbeted edges together, forming a continuous surface on either face.

foot **1.** The bottom or base of an object. **2.** A unit of measurement of length in the English system. **3.** A projection on a cylindrical roller used to compact a layer of earth fill.

foot block A mat of concrete, steel, or timber used to distribute a vertical load from a post or column over an area of supporting soil.

footcandle The common U.S. unit of measurement of the illuminance on a surface. One footcandle is equal to one lumen per sq. ft. The international unit of measurement is the lux. One footcandle is equal to 10.76 lux.



footing

footing That portion of the foundation of a structure that spreads and transmits the load directly to the soil.

footing beam **1.** A reinforced concrete beam connecting pile caps or spread footings to distribute horizontal loads caused by eccentric loading. **2.** The tie beam in a roof system.



footing beam

footing course A broad course of masonry at the foot of a wall, which helps prevent the wall from settling.

footing step A change in elevation of a strip footing.



footing step

footing stop In concrete work, a temporary board used to close up concrete until work can resume.

footpiece An item of ductwork in a heating, air-conditioning, or ventilating system that serves to change the direction of the airflow.

footplate A timber used in wood frame construction to disperse heavily concentrated structural loads among a number of supporting members, as a plate installed below a row of wall studs.

foot-pound A unit measure of work or energy in the English System equal to the force in pounds multiplied by the distance in feet through which it acts.

footprint The area that falls directly beneath and shares the same perimeter as a structure.

force, compression A force acting on a body, tending to compress the body (pushing action).

forced-air furnace A warm-air furnace, outfitted with a blower, that heats an area by transmitting air through the furnace and connecting ducts.



forced-air furnace

forced draft A draft of air that is mixed with fuel before the mixture is fed into the combustion chamber of a furnace or boiler.

force majeure An unexpected or unanticipated event that, if it occurs, can provide the owner or contractor, or both, a legitimate reason to delay the project, cease work, or cancel the contract without penalty. A force majeure clause in a construction contract attempts to define those events. Such events may be, for example, natural disasters deemed "acts of God," unanticipated government mandates, civil disturbances, and so forth.

force, shear A force acting on a body which tends to slide one portion of the body against the other side of the body (sliding action).

force, tension A force acting on a body tending to elongate the body (pulling action).

force, torsion A force acting on a body that tends to twist the body (twisting action).

forecast **1.** An estimate and prediction of future conditions and events based on information and knowledge available at the time of the forecast. **2.** When in respect to resource requirements, considering future conditions and events, it is a synonym for an estimate.*

foreclosure The legal transfer of a property deed or title to a bank or other creditor because of the owner's failure to pay the mortgage, whereupon the owner loses the right to the property.

Forest Stewardship Council (FSC) An international organization formed in 1993 that is concerned with ecological, social, and economic aspects of the forest management practices used to produce wood products. In order to earn Forest Stewardship Council certification, a wood product must meet certain criteria as it moves from the logging site through to the end user.

forging A piece of metal worked into a desired shape by one or more processes, including pressing, rolling, hammering, and upsetting.

forklift truck A self-powered vehicle equipped with strong prongs, or forks, that can be raised or lowered. A forklift truck is used to move objects, especially material on pallets, from one location and/or level to another.

form A temporary structure or mold for the support of concrete while it is setting and gaining sufficient strength to be self-supporting.



form

form anchor A device used to secure formwork to previously placed concrete of adequate strength. The device is normally embedded in the concrete during placement.

form board A board or sheet of wood used in formwork.

form coating A liquid applied to interior formwork surfaces for a specific purpose, usually to promote easy release from the concrete, to preserve the form material, or to retard the set of the near-surface matrix for preparation of exposed-aggregate finishes.

form hanger A device used to support formwork from a structural framework. The dead load of forms, weight of concrete, and construction and impact must be supported.



form hanger

form insulation Thermal insulation, equipped with an airtight seal, that is applied to the exterior of concrete forms. Used to preserve the heat of hydration at required levels so that concrete can set properly in cold weather.

form lining Selected materials used to line the face of formwork in order to impart a smooth or patterned finish to the concrete surface, to absorb moisture from the concrete, or to apply a set-retarding chemical to the formed surface.

form ply Plywood commonly used for constructing forms.

form pressure Lateral pressure acting on vertical or inclined formed surfaces, resulting from the fluid-like behavior of the unhardened concrete.

form scabbing The inadvertent removal of the surface of concrete as a result of adhesion to the form.

form tie A tensile unit adapted to prevent concrete forms from spreading due to the fluid pressure of freshly placed, unhardened concrete.



form tie

formwork The total system of support for freshly placed concrete, including the mold or sheathing that contacts the concrete, as well as all supporting members, hardware, and necessary bracing.



formwork

foundation The entire masonry substructure below the first floor or frame of a building, including the footing upon which the building rests.

foundation drainage tile Tile or piping, either porous or set with open joints, used to collect subsurface water or for the dispersion of effluent.

foundation engineering The category of engineering concerned with evaluating the ability of a locus to support a given structural load, and with designing the substructure or transition member needed to support the construction.



foundation drainage tile

foundation vent Vent openings in a foundation wall that allow for exchange of air and reduce moisture.

foundation wall That part of the foundation of a building forming a retaining wall for the portion of the building that is below grade.

four-way switch A switch used in a wiring layout to allow a circuit to be turned on or off from more than two places. Two three-way switches are used, and the remainder are four-way.

foxtail wedge A small wedge used to spread the split end of a bolt in a hole or the split end of a tenon in a mortise to secure the bolt or tenon.

foyer A subordinate space between an entrance and the main interior of a theater, hotel, house or apartment.

frame An assembly of vertical and horizontal structural members.

frame clearance The clearance between a door and the door frame.

frame construction A construction system in which the structural parts are wood or dependent on a wood framework for support. *See also* **framing**.

framed building A type of building construction in which vertical loads are carried to the ground on a frame.


frame construction

framed ground One of the vertical wood members fastened around an opening to which a door casing is attached, usually built with a tenon joint between the head and doorjambs.

framed joist A joist that is specially cut or notched in order to be joined securely with other joists or timbers.

frame gasket A strip of flexible material applied to the stop of a door frame to ensure tight closure.

frame house A house of frame construction, usually with exterior walls sheathed and covered with wood siding.

framer A carpenter who erects the wood frame of a home, including walls, trusses, rafters, decking, and floor systems.

frame wall A wall of frame construction.


frame wall

framework A network of structural members or components joined to form a structure, such as a truss or multilevel building.

framing **1.** Structural timbers assembled into a given construction system. **2.** Any construction work involving and incorporating a frame, as around a window or door opening. **3.** The unfinished structure, or underlying rough timbers of a building, including walls, roofs, and floors.


framing

framing anchor A sheet metal device used to join light wood members such as studs, joists, and rafters.


framing anchor

framing, balloon A system of framing a building in which all vertical structural elements of the bearing walls and partitions consist of single pieces extending from the top of the soleplate to the roofplate and to which all floor joists are fastened.

framing plan A drawing of each floor of a building showing exact locations of framing members and their connections. May include wall elevations and details.

framing, platform A system of framing a building in which floor joists of each story rest on the top plates of the story below or on the foundation sill for the first story, and the bearing walls and partitions rest on the subfloor of each story. *See also* **framing**.

f rating The measurement of stress (symbolized by the letter *f*) in a piece of lumber. Generally, the higher the *f* rating, the stronger the piece of lumber.

free fall **1.** Descent of freshly mixed concrete into forms without drop chutes or other means of confinement. **2.** The distance the concrete falls.

free float A term used in project management, planning, and scheduling methods such as PERT and CPM. The free float of an activity is the amount by which the completion of that activity can be deferred without delaying the start of the following activities or affecting any other activity in the network.

free moisture Moisture having essentially the properties of pure water not absorbed by aggregate in a test sample or a stockpile.

free on board (FOB) Refers to the point to which the seller will deliver goods without charge to the buyer. Additional freight or other charges connected with transporting or handling the product become the responsibility of the buyer.


freestanding

freestanding Said of a structural element that is fixed at its base and not braced at any upper level.

freezer A room or cabinet mechanically refrigerated to maintain a temperature of about 10°F (–12°C) used for food storage.

freezeback A roofing condition that occurs when water is forced back under the shingles by ice that has thawed and then refrozen.

freeze-thaw The cycle from freezing to thawing often detrimental to construction materials such as concrete. Air entrainment of concrete to be exposed to the elements is helpful in preventing damage from freeze-thaw cycles.


French door (casement door, door window)

French door (casement door, door window) A door, or pair of doors, with glass panes constituting all or nearly all of its surface area.

French drain A drainage ditch containing loose stone covered with earth.

French roof A mansard roof with nearly perpendicular sides.


French roof

frequency A measure of oscillations per second, applied to the current or voltage of AC electrical circuits, sound waves or vibrating solid objects, and stated in hertz (HZ) or cycles per second (CPS).

frequency modulation A method of modifying a sound-wave signal to relay information.

fresh-air inlet 1. A connection to a building drain, located above the drain trap and leading to the atmosphere. 2. An outside air vent for an HVAC system.

friction The resistance to relative motion, sliding or rolling, between two surfaces in contact. May produce heat.

friction catch Any catch held in position by friction when engaged with its strike.



friction catch

friction head In hydraulics, the energy lost by friction in a pipe. This may include losses at elbows and bends.

friction loss The stress loss in a prestressing tendon resulting from friction between the tendon and duct or other device during stressing.

friction pile (floating pile foundation) A load-bearing pile that receives its principal vertical support from skin friction between the surface of the buried pile and the surrounding soil.



friction pile (floating pile foundation)

friction tape An insulating tape used by electricians, made of a fibrous base impregnated with a moisture-resisting compound that will stick to itself but not to most other materials.

friction welding A process by which thermoplastic materials are softened and welded together with heat produced by friction.

frieze A horizontal exterior trim member positioned between the siding of a structure and its soffit.

fringe benefits Compensation paid to a worker in addition to his or her wages. Usually consists of paid vacation and sick time, pension, health insurance, and so forth.

front-end loader A machine with a bucket fixed to its front end, having a lift-arm assembly that raises and lowers the bucket. A front-end loader is used in earth moving and loading operations and in rehandling stockpiled materials.



front-end loader

front hearth (outer hearth) The part of a hearth that occupies the room served by a fireplace, skirting the front of the fireplace opening.

frost boil 1. An imperfection on a concrete surface caused by the freezing of trapped moisture that swells and crumbles the affected concrete. 2. The softening of soil caused by melting and release of subsurface water during a thaw.

frost line The depth to which frost penetrates the ground. This depth varies from one part of the country to another. Footings should be placed below the frost line to prevent shifting.

frostproof closet A water-closet bowl that retains no standing water. The trap and the valve for its water supply are located below the frost line.

fuel cell Cell that uses hydrogen as a fuel source through a catalytic process, producing electricity and giving off heat and small amounts of hot water as by products. The heat can be captured for space-heating needs, and the electricity generated can provide for power.

fuel-fired boiler An automatic, self-contained mechanical unit or system that produces heat by burning solid, liquid, or gaseous fuels.



fuel-fired boiler

full A reference to lumber that is slightly oversize.

full bond A masonry bond in which all bricks are laid as headers.

full-face respirator A respirator that covers the whole face with a protective shield.

full-flush door A door made of two sheets of steel assembled in hollow-metal construction with a top and bottom either flush or closed off with end panels, and seams that are visible only on the edge of the door.



full-louvered door

full glass door A door with glass in the area between rails and stiles except for dividing mullions. The glass is usually heat-treated or tempered.

full-louvered door A door with louvers filling the entire area between rails and stiles.

full-penetration butt weld A butt weld with a depth equal to the thickness of the smaller of the two members between which it lies.



full-penetration butt weld

full-surface hinge A hinge that may be installed on the surface of a door and jamb without need of mortising.



full-surface hinge

furlong A unit of measure equal to 220 yards or ⅛ of a mile.

furnace 1. That part of a boiler or warm-air heating plant in which combustion takes place. 2. A complete heating unit that transfers heat from burning fuel to a heating system.

furnish The raw material used to make reconstituted wood-based nonveneer panel products.

furred Provided with furring to leave an air space, as between a structural wall and plaster or between a subfloor and wood flooring.

furring 1. Strips of wood or metal fastened to a wall or other surface to even it, to form an air space, to give the appearance of greater thickness, or for the application of an interior finish such as plaster. **2.** Lumber 1″ in thickness (nominal) and less than 4″ in width, frequently the product of resawing a wider piece. The most common sizes of furring are 1″ × 2″ and 1″ × 3″.



furring strip

furring strip Wood or metal channels used for attaching gypsum or metal lath to masonry walls as a finish or for leveling purposes.

furring tile Tile designed for lining the inside of exterior masonry walls. It is not intended to support superimposed loads and has a scored face for the application of plaster.

furrowing The process of making furrows in the mortar bed with the tip of a trowel to speed up bricklaying by better distributing mortar.



fuse

fuse A protective device, made of a metal strip, wire, or ribbon that guards against overcurrent in an electrical system. The device melts if too much current is generated and breaks the circuit.



fuse box

fuse box A metal box with a hinged cover that houses fuses for electric circuits.

fusetron A special fuse that will carry an overload of current for a short time without "blowing" or opening the circuit. A fusetron is used where a heavy load, such as the starting of a motor, may overload a circuit momentarily.

fusible link A metal link made of two parts held together by a low-melting-point alloy. When exposed to fire-condition temperatures, the link separates, allowing a door, damper, or device to be closed.

fusible metal An alloy with a low melting point used in high temperature detecting devices.

fusion In welding, the melting and coalescence of a filler metal and base metal or two base metals.

FUTA The Federal Unemployment Tax Act, a federal law that imposes an unemployment tax on employers.

G

Abbreviations

g	gram, gravity, gauge, girth
G	gas
ga	gauge
gal	gallon
galv	galvanized
GAO	The U.S. General Accounting Office
GATT	General Agreement on Tariffs and Trade
GB	glass block
GC	general contractor
GCF	greatest common factor
gen	general
GFCI	ground-fault circuit-interrupter
GI	galvanized iron
gl	glass, glazing
GM	grade marked
GMV	gram molecular volume
GOB	general obligation bonds
Goth	Gothic
gov/govt	government
gpd	gallons per day
gpf	gallons per flush
gph	gallons per hour
gpm	gallons per minute
GPS	global positioning system
gr	grade, gravity, gross, grains
G/R	grooved roofing
gran	granular
gr fl	ground floor
gr fl ar	ground floor area
grnd	ground
gr wt	gross weight
G/S	grade-stamped
GT	gross ton
gtd	guaranteed
gup	grading under pavement
GYP	gypsum

Definitions

gabion A large compartmentalized container, usually cylindrical or rectangular, often fabricated from galvanized steel hexagonal wire mesh. When filled with stone it is used in the construction of foundations, dams, erosion breaks, etc.



gabion

gable The portion of the end of a building that extends from the eaves to the peak or ridge of the roof. The gable's shape is determined by the type of building on which it is used: triangular in a building with a simple ridged roof, or semioctagonal in a building with a gambrel roof.



gable

gableboard A board covering the timbers that extend over the gable end of a gable roof.

gable dormer A dormer that protrudes horizontally outward from a sloping roof and has its own gabled ends, whose base meets that of the sloping roof.



gable dormer

gable roof A ridged roof having one or two gabled ends.

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

c07.indd 134 06/09/12 8:51 AM

gable vents Vent openings mounted in the top of a gable of a house to allow the exchange of air in the attic.

gable wall A wall whose upper portion is a gable.

gable window A window built into or shaped like a gable.

gain **1.** The mortise or notch in a piece of wood into which a piece of wood, hinge, or other hardware fits. **2.** An increase in transmission signal power from one point to another, expressed in decibels. **3.** An increase in the volume of sound of a radio.

gallery **1.** A long enclosure that functions as a corridor inside or outside a building or between different buildings. **2.** The elevated (usually the highest) designated seating section in an auditorium, theater, church, etc. **3.** A room or building in which artistic works are exhibited.

gallery apartment house An apartment house whose individual units can be entered from an exterior corridor on each floor.

galleting (gaffering) The use of chips of rock, stone, or masonry to fill the joints of rough masonry, either for appearance or to minimize the required amount of mortar.

gallon A standard liquid measure: The British imperial gallon contains 10 lbs. of water; the American gallon contains 8.33 lbs. of water.

gallon per minute (gpm) A unit measure of flow. Equals a flow rate of one gallon in one minute.

gallows bracket A triangular wall bracket often used for the support of shelving.

galvanic corrosion The electrochemical action that occurs as a result of the contact of dissimilar metals in the presence of an electrolyte.

galvanize The process of protectively coating iron or steel with zinc, either by immersion or electroplating (electrogalvanizing).

galvanized iron Zinc-coated iron sheet metal.

galvanized pipe Zinc-coated steel or wrought-iron pipe.

gambrel roof A roof whose slope on each side is interrupted by an obtuse angle that forms two pitches on each side, the lower slope being steeper than the upper.



gambrel roof

gang A working technique in which several machines and/or apparatuses are controlled by a single force and combined in such a way as to function as a single unit.

gang form Prefabricated form panels connected together to produce large reusable units. Gang forms are usually lifted by crane or rolled to the next location.



gang form

gang sawing A method of stone-cutting that made possible the use of stone as a veneer on buildings.

gantry crane A revolving crane situated atop a heavy framework that moves along the ground on tracks.

Gantt chart A time-scaled bar chart named after Henry L. Gantt.*

GAO The U.S. General Accounting Office that, under the direction of the Comptroller General of the United States, has jurisdiction over bid protests. The GAO is an arm of the Congress.

gap grading A particle-size distribution of aggregate that is practically or completely void of certain intermediate sizes.

garbage disposal unit An electrically motorized device that grinds waste food and mixes it with water before disposing of it through standard plumbing drainage pipes.

garden house In a garden, a small gazebo or other shelter.

garden tile Molded structural ceramic units used in a garden or on a patio as stepping stones.

garden wall bond Usually, ornamental brickwork that is only a single brick thick and is composed mostly of stretchers showing a fair face on each side.

gargoyle A waterspout, often with carvings of grotesque human or animal features, that projects from a roof gutter so as to drop rainwater clear of a wall, often through its open mouth.

garnet A silicate mineral with an isometric crystal structure. Garnet occurs in a variety of colors and is used as gemstones, abrasives, or gallers.

garnet paper A finishing and polishing paper covered with powdered garnet abrasive.

garrison house A style of house whose second story overhangs the face of the first story on one or more walls.



garrison house

gas A fluid (in the form of air) with neither independent shapes nor volume, that can expand indefinitely.

gas engine An internal-combustion engine that uses a gas rather than gasoline as fuel.



gas engine

gas-filled lamp A type of incandescent lamp with a bulb atmosphere consisting of an inert gas within which the filament operates.

gas furnace A furnace that burns gas to produce heat.

gasket Any of a variety of seals made from resilient materials and placed between two joining parts (as between a door and its frame, an oil filter and its seat, pipe threads and their fitting, etc.) to prevent the leakage of air, water, gas, or fluid.

gas main The public's gas supply as piped from the providing utility company into a community.

gas metal-arc welding A method of welding that achieves coalescence by arc-heating between the work and a consumable electrode.

gas meter A mechanical device that measures and records in cubic feet the volume of gas passing a given point.

gas pocket In a casting, a hole or void caused by the entrapment of air or gas that is produced during the solidification of the metal.

gas refrigeration A refrigeration system in which a gas flame is used to heat the refrigerant.

gas vent An exhaust pipe through which undesirable gaseous by-products of combustion are vented to the outside.



gas vent

gas welding Any of several welding methods in which a gas flame provides the heat necessary for coalescence and in which pressure and/or a filler metal may or may not be employed.

gate A usually hinged device of solid or open construction that is installed as part of a fence, wall, or similar barrier and that, when opened (either by swinging, sliding, or lifting), provides access through that barrier.

gate operator An electronically operated mechanism that, when activated, serves to open or close a gate.

gate valve A valve utilizing a gate, usually wedge-shaped, that allows fluid flow when the gate is lifted from the seat. Gate valves have less resistance to flow than globe valves, and should always be used fully open or fully closed.



gate valve

gauge (gage) **1.** The numerically designated thickness of sheet metal. **2.** The designated diameter of a screw or wire, or the thickness of the wall of tubing. **3.** A measuring device for pressure or liquid level. **4.** The distance between rows of bolt or rivet holes in the same member. **5.** A wood or metal strip used as a thickness-control guide in bituminous or concrete paving operations. **6.** In plastering, a screed. **7.** The act of adding or the amount of gauging plaster needed to hasten the setting of common plaster. **8.** In laid roofing, the exposed length of a shingle, slate, or tile.



gauge (gage)

gauge box (gauging box) A container in which a batch of concrete, mortar, or plaster is measured and mixed.

gauged A term that refers to a material that has been ground so as to produce particles of uniform shape and/or thickness.

gauged brick Brick that has been sawn, ground, or otherwise shaped to accurate dimensions for special applications.

gauged mortar **1.** Mortar made of cement, sand, and lime in specific proportions. **2.** Any plastering mortar that is mixed with plaster of paris to hasten setting.

gauged skim coat A mixture of gauging plaster and lime putty applied very thinly as a final coat in plastering. The mixture is troweled to produce a smooth, hard finish.



gauged skim coat

gauge glass A glass tubular device or vertical cylindrical device, often graduated, that indicates the level or amount of liquid in a tank or vessel.

gauge rod A stick used for measuring the gauge in brickwork. If used to mark floor and sill levels, the rod is termed a *story rod*, or *story pole*.

gauging plaster Plaster of paris (gypsum plaster) that is usually mixed with lime putty to produce a quick-drying finish coat.

gazebo A small, round, octagonal, or similarly shaped structure, usually roofed but open-sided, built in parks or large gardens to provide shelter or a place to view the surrounding area.



gazebo

gear A toothed wheel, cone, cylinder, or other machined element that is designed to mesh with another similarly toothed element for purposes that include the transmission of power and the change of speed or direction.



gear

General Agreement on Tariffs and Trade (GATT) A specialized agency of the United Nations that seeks to ease the barriers of international trade.

general & administrative costs (G&A) The fixed cost incurred in the operation of a business. G&A costs are also associated with office, plant, equipment, staffing, and expenses thereof, maintained by a contractor for general business operations. G&A costs are not specifically applicable to any given job or project.*

general conditions The portion of the contract document in which the rights, responsibilities, and relationships of the involved parties are itemized.

general contract In a single contract system, the documented agreement between the owner and the general contractor for all the construction for the entire job.

general contractor For an inclusive construction project, the primary contractor who oversees and is responsible for all the work performed on the site, and to whom any subcontractors on the same job are responsible.

general diffuse lighting Lighting from units that direct 40% to 60% of their emitted light upward and the remainder downward.

general foreman The general contractor's on-site representative, often referred to as the *superintendent* on large construction projects. It is the responsibility of the general foreman to coordinate the work of various trades and to oversee all labor performed at the site.

general industrial occupancy The designation of a conventionally designed building that can be used for all but high-hazard types of manufacturing or production operations.

general liability insurance Insurance that protects a project and any adjacent properties from damage or loss as a result of an accident during the construction process.*

general obligation bonds Instruments of obligation that, by permission of the public through referendum, are issued to investors by a subdivision of government. These bonds promise incremental payment of principal and interest from revenues collected annually by the government. In return, funds are supplied by investors and are used to pay for the construction of publicly owned buildings or other public works projects.

general partnership An association of two or more people to conduct business for profit as co-owners. The participants in a general partnership, called *general partners*, share all aspects of the business including assets, profits/losses, liability, and management responsibility.

general-purpose branch circuit An electrical circuit that supplies a number of outlets.

general requirements The designation or title of Division 1 (the first of 16) in the Construction Specifications Institute's Uniform System. General requirements usually include overhead items and equipment rentals.

general terms and conditions **1.** That part of a contract, purchase order, or specification that is not specific to the particular transaction but applies to all transactions. **2.** General definition of the legal relationships and responsibilities of the parties to the contract and how the contract is to be administered. They are usually standard for a corporation and/or project.*

generator **1.** A mechanical or electromechanical device that converts mechanical energy into electrical power, as an alternator producing alternating current or a dynamo producing direct current. **2.** A person, firm, or entity whose activities create a hazardous waste.

geodesic dome A stable, dome-shaped structure fabricated from similar lightweight members connected to form a grid of interlocking polygons.


geodesic dome

Georgian architecture Neoclassical style of architecture that prevailed in 18th-century Great Britain. Characterized by orderly design, rectangular shapes, and symmetrical window placement.

geotechnical engineering A specialty in the field of civil engineering that focuses on geology and soil mechanics leading to the design of foundation structures.

geotextiles Synthetic fabrics that can be used to separate back filling materials to promote proper drainage. Commonly used in conjunction with high retaining walls and landscape design.

geothermal heat An energy-efficient heating system that uses subsurface ground temperatures to keep the system's water at a moderate temperature. Less energy is then required to heat the water enough warm the building.

gesso A plaster base coat, for gilding or decorative painting, consisting of gypsum plaster, calcium carbonate, and glue.

gilding **1.** The application of gilt (as gold leaf or flakes) to a surface. **2.** A surface ornamented with gilt.

gimlet A small hand tool, of ancient origin, whose handle is perpendicular to a screw point, and that is used for boring small holes (less than 1/4″) in wood.

gin A simple lifting device consisting of a vertical pole, tripod, or other frame.

gin block A simple tackle block, with a single pulley in a frame, having a hook on top for hanging.


gin block

gingerbread An ornate style of architecture, usually employed in exterior house trim, and common in the United States during the 19th century.

gin pole A cable-supported vertical pole used in conjunction with blocks and tackle for hoisting.

girandole A branched fixture or bracket for holding lamps or candles, either freestanding or protruding from a wall, often having a mirror behind it.

girder A large principal beam of steel, reinforced concrete, wood, or a combination of these, used to support other structural members at isolated points along its length.

girder casing Material that encloses and protects (as from fire) the part of a girder extending below ceiling level.


girder casing

girder post Any support member, such as a post or column, for a girder.

girdle A horizontal band around the shaft of a column.

girt (girth) **1.** A horizontal member used as a stiffener between studs, columns, or posts at intermediate level. **2.** A rail or intermediate beam that receives the ends of floor joists on an outside wall.


girt (girth)

girth **1.** The circumference of any circular object. **2.** The distance around a column.

give-and-take lines Straight equalizing lines used in calculating band areas and their boundaries.

glare Any unwanted brightness that brings discomfort or reduced visibility.

glass A hard, brittle, inorganic product, ordinarily transparent or translucent, made by the fusion of silica, flux, and a stabilizer, and cooled without crystallizing. Glass can be rolled, blown, cast, or pressed for a variety of uses.

glass block A hollow, translucent block of glass, often with molded patterns on either or both faces, that affords pleasantly diffused light when used in non-load-bearing walls or partitions.


glass block

glass cement Any glue or other adhesive material that serves to bind glass to glass, or glass to another material.

glass cloth A wall covering made from woven vegetable fibers, especially arrowroot bark, that are laminated onto a paper backing.

glass cutter A small hand tool having a pointed diamond tip or a sharp, small, hardened steel wheel that scores glass.

glass door A door fabricated without stiles or rails and consisting entirely of thick, heat-strengthened, or tempered glass.

glass, obscure Sheet glass that has been made translucent instead of transparent. It is sandblasted or molded to make the surfaces irregular.

glasspaper A fine sandpaper or polishing paper whose abrasive is powdered glass.

glass size The size to which a piece of glass is cut so as to glaze a given opening. Its length and width should be ⅛″ less than the distance between the outside edges of the rebates.

glass stop **1.** A glazing bead. **2.** A fitting at the lower end of a patent glazing bar to prevent the pane from sliding down.

glass, structural Cast glass in squares or rectangles, 1″ to 2″ thick, sometimes laid up between concrete ribs, frequently as tile. Larger units are made in hollow or vacuum blocks. The wide use of the product is in colored and polished sheets for interior wall surfacing.

glass tile Transparent or translucent units installed in a roof surface that allow light to enter the room below.

glass wool Spun fiberglass used mostly for thermal and acoustical insulation and as a filtering medium in air and water filters.

glaze **1.** To install glass panes in a window, door, or another part of a structure by applying putty or other material to hold the glass in place. **2.** A hard, thin, glossy ceramic coating on the surface of pottery, earthenware, ceramics, and similar goods. Usually called *enamel*, a transparent solution that, when dry, provides tiles with a hard, shiny finish. Can be applied by either painting or dipping.



glaze

glaze coat **1.** The smooth top layer of asphalt in built-up roofing. **2.** A temporary, protective coat of bitumen applied to built-up roofing that is awaiting top-pouring and surfacing. **3.** In painting, the application of a nearly transparent coat that enhances and protects the coat below it.

glazed brick Brick or tile with a surface produced by fusing it with a glazing material.

glazed door Any door with glass panes or panels and top and bottom rails.

glazed tile Ceramic or masonry tile with an impervious, glossy finish.



glazed door

glazement A waterproof surfacing used on masonry that creates a smooth, durable finish.

glazier A person whose trade is to install glass in structures. The glazier removes old putty, cuts glass to fit the openings requiring it, and secures it there by whatever means are necessary or appropriate.

glazier's putty A glazing compound often made from a mixture of linseed oil and plaster of paris, and sometimes including white lead.

glazing **1.** Fixing glass in an opening. **2.** The glass surface of an opening that has been glazed.

glazing bead (glass stop) **1.** A narrow strip of wood, plastic, or metal fastened around a rebate and used to hold glass in a sash. **2.** At a glazed opening, removable trim that holds the glass in place.

glazing compound Any putty or caulking compound used in glazing to seal the joint at the edges of the glass.

glazing fillet A narrow wood or plastic strip fastened to the rebate of a glazing bar and used instead of face putty to hold glass in place.



glazing bead (glass stop)

glazing gasket A narrow, sometimes grooved, prefabricated strip of material such as neoprene, that offers a dry alternative to glazing compound in glazing operations. The gasket is impervious to moisture and temperature and is often used with large panes or sheets of glass.

glazing sprig A small headless nail that holds a pane of glass in its wooden frame while putty hardens.

glazing tape A resilient tape used to seal glass into a frame, sash, or opening.

global positioning system (GPS) A global system of U.S. navigational satellites that locates precise points and coordinates on earth.

global warming An increase in the average temperature of the Earth's atmosphere, often used to refer to climatic changes due to increased emissions of greenhouse gases.

globe (light globe) **1.** A protective enclosure or covering over a light source. The globe is usually made of glass and can also serve to diffuse, redirect, or change the color of the light. **2.** An incandescent lamp.

globe valve A valve with a rounded body utilizing a manually raised or lowered disc that, when closed, seats so as to prevent fluid flow. Globe valves are ideal for throttling in a semi-closed position.



globe valve

gloss Surface luster, usually expressed in terms ranging from matte to high gloss.

glow lamp A type of low-consumption electric discharge lamp whose light is produced close to the electrodes within an ionized gas. A glow lamp is often used as an indicating light.

glue A general term for any natural or synthetic viscous or gelatinous substance used as an adhesive to bind or join materials.

glue bond A measure of how well articles are fastened together after being glued.

glued floor system A method of floor construction in which a plywood underlayment or other structural panel is both glued and nailed to the floor joists. This creates a stronger, stiffer floor less prone to squeaking than floors fastened only with nails.

glue-laminated timber Timber composed of wood layers, or laminations, glued together with the grains longitudinally parallel.

Commonly used for columns, headers, posts, beams, and truss components.

glue nailed A term applying to plywood joints and connections that have been both glued and nailed to produce the stiffest possible construction.

glue-up The process of spreading glue on the surfaces of veneers of similar sizes and pressing them together to form a sheet of plywood.

glycol Liquid with a very low freezing point that is miscible with water.

gob bucket (concrete bucket) On a crane, the bucket that is used to carry concrete.



gob bucket (concrete bucket)

going The horizontal distance between two consecutive risers or stairs. The horizontal distance between the first and last riser of an entire flight is called the *going of the flight* or the run.

going rod A rod used in planning the going of a flight of steps.

gold bronze Powdered copper or copper alloy used for bronzing, or in the manufacture of gold or bronze paint.

good one side (G1S) A grade of sanded plywood with a higher grade of veneer on the face than on the back. G1S is used in applications where the appearance of only one side is important.

good two sides (G2S) The highest grade of sanded plywood. G2S is allowed to have inlays or neat wood patches and is used in applications where the appearance of both sides is important.

gooseneck **1.** In plumbing, a curved, sometimes flexible fitting connection or section of pipe. **2.** In HVAC, a screened, U-shaped intake or exhaust duct. **3.** The curved end of a handrail at the top of a stair. **4.** The curved connector from a tractor to a trailer.

gothic arch A typically high, narrow arch with a pointed top and a jointed apex (as opposed to keystone).

gouge A cutting chisel having a long, curved blade and used for hollowing out wood, or for making holes, channels, or grooves in wood or stone.

government anchor A V-shaped anchoring device usually fabricated from ½″ round bar, and used in steelwork to secure a wall-bearing (or other) beam to masonry.



government anchor

gouache A type of thick, water-based, decorative paint.

Gow caisson (Boston caisson, caisson pile) A series of steel cylinders from 8′ to 16′ high used to protect workers and equipment during deep excavation in soft earth. Each successive cylinder is 2′ in diameter smaller than its predecessor, through which it is dropped or driven deeper into the surrounding soft clay or silt to prevent excessive loss of ground and to facilitate deep excavation. When excavation and construction are complete, the cylinders are withdrawn.

grab bar A short length of metal, glass, or plastic bar attached to a wall in a bathroom, near a toilet, in a shower, or above a bathtub.

grab bar

grab bucket A bucket-like device with hinged lower halves or "jaws" hydraulically or cable operated from a crane or used for rehandling granular materials.

grab crane A crane outfitted with a grab bucket.

Gradall A trade name for a wheel-mounted, articulated, hydraulic backhoe often used with a wide bucket for dressing earth slopes.



Gradall

gradation An assessment, as determined through sieve analysis, of the amounts of particles of different sizes in a given sample of soil or aggregate.

grade **1.** The surface or level of the ground. **2.** A classification of quality as, for instance, in lumber. **3.** The existing or proposed ground level or elevation on a building site or around a building. **4.** The slope or rate of incline or decline of a road, expressed as a percent. **5.** A designation of a subfloor, either above grade, on grade, or below grade. **6.** In plumbing, the slope of installed pipe, expressed in the fall in inches per foot length of pipe. **7.** The classification of the durability of brick. **8.** Any surface prepared to accept paving, conduit, or rails.

grade beam A horizontal end-supported (as opposed to ground-supported) load-bearing foundation member that supports an exterior wall of a superstructure.



grade beam

grade course The first course of brick, block, or stone, at grade level, usually waterproofed.



grade course

graded aggregate **1.** Aggregate having size ranging from coarse to graded sand. **2.** A fine aggregate (under ¼″) having a uniformly graded particle size.

grade line **1.** A line of stakes with markings, each at an elevation relative to a common datum and from whose elevations a grade between their terminal points can be established. **2.** A strong string used to establish the top of a concrete pour or masonry course.



grader

grader A multipurpose earthworking machine used mostly for leveling and crowning. A grader has a single blade, centrally located, that can be lifted from either end and angled so as to cast to either side.

grade stamp (grade mark) A stamp on a manufactured piece of wood that designates it meets certain standards of quality as set forth by one of several standards organizations. Stamps for structural lumber, for instance, include information on species, moisture content, and lumber grade.

grade stake In earthwork, a stake that designates the specified level.

gradient **1.** The change in elevation of a surface, road, or pipe, usually expressed in a percentage or in degrees. **2.** The rate of change of a variable such as temperature, flow, or pressure.



grading

grading **1.** The act of altering the ground surface to a desired grade or contour by cutting, filling, leveling, and/or smoothing. **2.** Sorting aggregate by particle size. **3.** Classifying items by size, quality, or resistance.

grading curve A line on a graph illustrating the percentages of a given sample of material that pass through each of a specific series of sieves.

grading instrument A surveyor's level having a telescope that can be adjusted upward or downward to lay out a required gradient.

grading plan A plan showing contours and grade elevations for existing and proposed ground surface elevations at a given site.

grading rules Quality criteria that determine the classification of lumber, plywood, or other wood products.

gradual load The gradual application of a load to the supporting members of a structure.

grain **1.** The directional arrangement of fibers in a piece of wood or woven fabric, or of the particulate constituents in stone or slate. **2.** The texture of a substance or pattern as determined by the size of the constituent particles. **3.** Any small, hard particle (like sand). **4.** A metric unit of weight; 7,000 grains equal one pound.

grain size **1.** A size classification of mineral particles in soil or rock. **2.** One of the physical characteristics of a particle of soil, which relates to its mechanical properties.

grandfather clause A clause that allows activities that were legal under an old law to continue under a superseding law.

grandmaster key **1.** A key that not only operates all the locks within a given group having its own master key, but several such groups. **2.** A master key of master keys.

granolithic concrete A type of concrete made from a hard aggregate whose particle shape and surface texture render it conducive for wearing-surface finishes on floors.

granolithic finish A concrete wearing surface, placed over a concrete slab, containing aggregate chips to improve its longevity.

granular **1.** A technical term relating to the uniform size of grains or crystals in rock. **2.** Composed of grains.



granular fill insulation

granular fill insulation An insulation material such as perlite or vermiculite that can be easily placed or poured because it comes in the form of chunks, pellets, or modules.

granular material A sandy type of soil whose particles are coarser than cohesive material and do not stick together.



grass cloth

graphite paint A type of paint made from boiled linseed oil, powdered graphite, and a drier. Graphite paint is used to inhibit corrosion on metal surfaces.

grass cloth A wall covering made from woven vegetable fibers, especially arrowroot bark. The cloth is laminated onto a paper backing.



grate

grate **1.** A type of screen made from sets of parallel bars placed across each other at right angles in approximately the same plane. A grate allows water to flow to drainage, while covering the area for pedestrian or vehicular traffic. **2.** A surface with openings to allow air to flow through while supporting a fuel bed, as in a coal furnace.

gravel Coarse particles of rock that result from naturally occurring disintegration or that are produced by crushing weakly bound conglomerate. Gravel is retained on a No. 4 sieve.

gravel, bank run Naturally occurring gravel deposits that are often located along rivers or lakes.



gravel roofing

gravel roofing Roofing composed of several (built-up) layers of saturated or coated roofing felt, sealed and bonded with asphalt or coal-tar pitch that, for solar protection and insulation purposes, is then covered with a layer of gravel or slag. Usually used on flat or nearly flat roofs.

gravel stop A metal strip or flange around the edge of a built-up roof. The stop prevents loose gravel or other surfacing material from falling off or being blown off a roof.



gravel stop

gravity dam A pyramid-shaped dam whose own weight resists the force of the water behind it.

gravity separator A chamber in which oil rises and remains on the surface of wastewater until it is removed.

gravity wall A massive concrete retaining wall whose own weight prevents it from overturning.

gravity water supply (gravity water, gravity system) A water distribution system in which the supply source is located at an elevation higher than the use.

gray paper The rough textured, unsized paper that covers the back of regular gypsum board, or both face and back on backing board products.

gray water Wastewater recycled from appropriate sinks, showers, baths, and laundry, which can be used for watering plants, cooling HVAC equipment, and other purposes.

grease extractor A device installed in conjunction with a cooking exhaust system and employing grease-collecting baffles positioned so as to create a path of sharp turns through which the cooking exhaust is passed at high velocity. The grease, which is particulate and heavier than air, is collected on the baffles by centrifugal force, while the carrying air continues around the sharp turns on its way to being exhausted, thus becoming cleaner at each baffle.

grease interceptor (grease trap) A device installed between the kitchen drain and the building sewer to trap and retain fats and grease from kitchen waste lines.



grease interceptor (grease trap)

green A term referring to unseasoned timber or to fresh, unhardened concrete, plaster, or paint.

green board (moisture-resistant) Gypsum board distinguishable by the green color of its face paper. Green board is designed to be used in areas that are often damp, such as in bathrooms for tile backing.

green building Design, construction and product selection that minimizes a structure's impact on the natural environment.



greenfield

greenfield Flexible metal conduit for electrical wiring.

greenhouse A glass-enclosed space with a controlled environment for growing plants, vegetables, and fruits out of season.



greenhouse

greenhouse effect 1. The conversion of the sun's rays into heat that is retained by the glass roof of a greenhouse. **2.** The steady, gradual rise in temperature of the earth's atmosphere due to heat that is retained by layers of ozone, carbon dioxide, and water vapor.

Green Lights Program A government program sponsored by the Environmental Protection Agency that is aimed at promoting energy efficiency through investment in energy-saving lighting.

green power Refers to the production of electricity from environmentally friendly sources, including wind and solar power, photovoltaics, geothermal, biomass, hydrogen fuel cells, and so forth with the goal of reducing the use of fossil fuel and carbon dioxide generation.

green process Manufacturing products with consideration for the source of materials, energy-efficient manufacturing methods, use of recycled materials in packaging, and reclaiming manufacturing waste.

green products Sustainable products that minimize the impact on the natural environment.

green roof Also called a *living roof*, a roof with a layer of soil and plantings that dissipates solar heat, provides good insulation, absorbs rainwater runoff, generates oxygen, and protects and therefore extends the life of the roofing material below. It can also give the roof space a garden-like appearance. The roofing becomes its own ecosystem with soil and plantings.

greenwash Term referring to companies that overstate their environmental practices in order to conceal unsound procedures and appear environmentally responsible to the public.

grid 1. In surveying, a system of evenly spaced perpendicular reference lines with its intersections used to measure elevations. **2.** The structural layout of a given building. **3.** A system of crossed reinforcing bars used in concrete footings.



grid

grid ceiling 1. A ceiling with apertures into which are built luminaries for lighting purposes. **2.** Any ceiling hung on a grid framework.

grid line Any line that is part of a reference pattern for surveying or a layout.

grillage Steel or wooden beams used horizontally under a structure to distribute its load over its footing or underpinning.

grille 1. Any grating or openwork barrier used to cover an opening in a wall, floor, paving, etc., for decoration, protection, or concealment. **2.** A louvered or perforated panel used to cover an air duct opening in a wall, ceiling, or floor. **3.** Any screen or grating that allows air into a ventilating duct.



grille

grillwork In construction, any heavy framework of timbers or beams used to support a load on soil instead of on a concrete foundation.

grinder 1. A device that sharpens or removes particles of material by abrasion. **2.** A machine or tool for finishing concrete surfaces by abrasion.

grinder pump A sewage pump that reduces solids and grinds and pumps material.

grit **1.** A granular abrasive used in making sandpaper or on grinding wheels to give a surface a nonslip finish. **2.** Particles of sand or gravel contained in sewage.

grizzly **1.** A screen or grate used to remove oversize particles during aggregate processing or loading. **2.** A gate or similar device on a chute.

groin **1.** In architecture, a ridge or curved line formed at the junction of two intersecting vaults. **2.** A structure built outward from a shore into water to direct erosion or to protect against it.

groin centering **1.** A method of supporting ribless groining during vaulting. **2.** In ribbed vaulting, the support of the stone ribs by timbers until construction is complete.

grommet A metal or plastic eyelet that provides a reinforced hole in a material, such as cloth or leather, that might otherwise tear from the stress on the hole when a fastener or other device is passed through it or attached to it.

grommet

groove In carpentry, a narrow, longitudinal-channel cut in the edge or face of a wood member. The groove is called a *dado* when cut across the grain, and a *plow* when cut parallel to it.

groove joint A joint formed by the intentional creation of a groove in the surface of a wall, pavement, or floor slab for the purpose of controlling the direction of random cracking.



groove joint

groover A tool for creating grooved joints in unhardened concrete slabs.



groover

groove weld A weld between the existing preformed grooves in members being joined.

gross area **1.** The total area without deducting for holes or cutouts. **2.** The whole or entire area of a roof. **3.** In shingles, the entire area of a shingle, including any parts that might have had to be cut out. **4.** The total enclosed floor area of a building.

gross cross-sectional area The total area of that portion of a concrete masonry unit that is perpendicular to the load, inclusive of any areas within its cells and reentrant spaces.

gross floor area The total area of all the floors of a building, including intermediately floored tiers, mezzanine, basements, etc., as measured from the exterior surfaces of the outside walls of the building.

gross output The number of Btus available at the outlet nozzle of a heating unit for continuously satisfying the gross load requirements of a boiler operating within code limitations.

gross volume **1.** The total volume within the revolving part of a drum concrete mixer. **2.** The total volume of the trough on an open-top concrete mixer.

ground **1.** The conducting connection between electrical equipment or an electrical circuit and the earth. **2.** A strip of wood that is fixed in a wall of concrete or masonry to provide a place for attaching wood trim or burring strips. **3.** A screed, strip of wood, or bead of metal fastened around an opening in a wall and acting as a thickness guide for plastering or as a fastener for trim. **4.** Any surface that is or will be plastered or painted. **5.** Any electrical reference point.

ground area The area computed by the exterior dimensions of the structure.

ground beam **1.** A reinforced concrete beam or heavy timber positioned horizontally at ground level to support a superstructure. **2.** A ground sill.

ground bus An electrical bus to which individual equipment grounds are connected and which itself is grounded at one or more points.

ground coat The base or undercoat of paint or enamel, often designed to be seen through the topcoat or glaze coat.

ground course A first horizontal course of masonry at ground level.

ground cover A planting of low plants that in time will spread to form a dense, often decorative mass. Ground cover is also used to prevent erosion.

grounded Descriptive of an object that is electrically connected to the earth or to another conducting body that is connected to the earth.

grounded system A system of electric conductors, at least one of which is intentionally grounded, either solidly or by means of a device that limits current.



ground-fault circuit interrupter

ground-fault circuit interrupter An electrical outlet fitted with code-required safety protection.

ground floor In a building, that floor closest to the level of the surrounding ground.

grounding electrode A conductor that is firmly embedded in the earth, and can thus function to maintain ground potential on the conductors connected to it.

grounding outlet An electrical outlet whose polarity-type receptacle includes both the current-carrying contacts and a grounded contact that accepts an equipment-grounding conductor.

ground plan The plan of a structure at ground level.

grounding plug A receptacle plug comprising a male member that, when plugged into a live grounding outlet, provides a ground connection for an electric device.



grounding outlet

grounding rod The rod that grounds an electrical panel.

ground iron Plumbing drain and waste lines installed under the floor of a basement.

ground joist Floor joists laid on sleepers, dwarf sills, or stones.

ground line The natural grade line or ground level from which excavation measurements are taken to determine excavation quantities.

ground pressure **1.** The weight of a machine or a piece of equipment divided by the area, in square inches, of the ground that supports it. **2.** Pressure exerted on a structural member by the adjacent soil or fill.

ground-source heat pump A geothermal heating and cooling system that uses the moderating temperatures of the Earth to heat or cool a home.

groundwater **1.** Naturally occurring water that moves through the Earth's crust, usually at a depth of several feet to several hundred feet below the Earth's surface. **2.** Water contained in the soil below the level of standing water.

groundwater recharge The reintroduction of water into the ground, as from trenches beyond the construction area or through injection.

groundwater table The top elevation of groundwater at a given location and at a given time.

ground wire **1.** An electrical conductor leading directly or indirectly to the earth. **2.** Strong, small-gauge wire used in establishing line and grade, as in shotcrete work.

groundwork Batters used in roofing and siding as a base over which slate, tiles, and shingles are applied.

grout **1.** A hydrous mortar whose consistency allows it to be placed or pumped into small joints or cavities, as between pieces of ceramic clay, slate, and floor tile. **2.** Various mortar mixes used in foundation work to fill voids in soils, usually through successive injections through drilled holes.

grouted-aggregate concrete Concrete that is produced by injecting grout into prepositioned coarse aggregate.

grouted masonry **1.** Hollow masonry units with some or all of the cells filled with grout. **2.** Masonry comprising two or more wythes, the spaces between which are filled solidly with grout.



grouted masonry

grouting **1.** The placing of grout so as to fill voids, as between tiles and under structural columns and machine bases. **2.** The injection of grout to stabilize dams or mass fills, or to reinforce and strengthen decaying walls and foundations. **3.** The injection of grout to fill faults and crevices in rock formations.



grouting

grout lift The height of grout placed in masonry wall voids during a single placement.

growth ring A ring that designates the amount of a tree's growth in a single year.



growth ring

grub In site work, the clearing of stumps, roots, trees, bushes, and undergrowth.

guarantee (guaranty, warranty) A legally enforceable assurance of quality or performance of a product or work, or of the duration of satisfactory performance.

guaranteed maximum cost The maximum amount above which an owner and contractor agree that cost for work performed (as calculated on the basis of labor, materials, overhead, and profit) will not escalate.

guaranteed maximum cost contract A contract for construction wherein the contractor's compensation is stated as a combination of accountable cost plus a fee, with guarantee by the contractor that the total compensation will be limited to a specific amount. This type of contract may also have possible optional provisions for additional financial reward to the contractor for performance that causes total compensation to be less than the guaranteed maximum amount.

guaranty bond A type of bond that is given to secure payment and performance. Each of the following four bonds are types of guaranty bonds: **1.** bid bond, **2.** labor and material payment bond, **3.** performance bond, and **4.** surety bond.

guard **1.** Any bars, railing, fence, or enclosure that serves as protection around moving parts of machinery or around an excavation, equipment, or materials. **2.** A security guard hired to maintain safety and security at a construction site.



guard board

guard board A raised board around the edge of a scaffold or gantry crane to keep men and tools from falling off.

guard rail **1.** A horizontal rail of metal, wood, or cable fastened to intermittent uprights of metal, wood, or concrete around the edges of platforms or along the lane of a highway. **2.** The rail that separates traffic entering or exiting through side-by-side automatic doors.



guard rail

guesstimate An educated guess or approximation of the cost of a project made by the cost estimator, without having performed a detailed quantity takeoff.

guide wire **1.** A steel wire or cable used to guide the vertical movement of a stage curtain in a theater. **2.** A line or wire that guides the movement of a counterweight arbor. **3.** A wire placed along the edge of a roadway to be paved. A sensor on the pavement spreader adjusts the elevation of the pavement from the wire.

gumbo Soil composed of fine-grained clays. When wet, the soil is highly plastic, very sticky, and has a soapy appearance. When dried, it develops large shrinkage cracks.

gumwood Wood from a gum tree, especially eucalyptus, used mostly for interior trim.

gun **1.** Equipment designed to deliver shotcrete. **2.** A pressure cylinder for pneumatic delivery of freshly mixed concrete. **3.** A spray gun. **4.** A slang expression for a transit, as it is used to *shoot* grades.

gun consistency The degree of viscosity of caulking or glazing compound that renders it suitable for application by a caulking gun.

gun finish The finish on a layer of shotcrete left undisturbed after application.

gunite Concrete mixed with water at the nozzle end of a hose through which it has been pumped under pressure. Gunite is applied or placed pneumatically, as shot, onto a backing surface.

gusset A metal or wood brace attached to structural members at their joints to add strength and stability.

gusset plate A plate fastened across a joint, as in wood or steel framework members. *See also* **chain**.



gusset plate

gutter **1.** A shallow channel of wood, metal, or PVC positioned just below and following along the eaves of a building for the purpose of collecting and diverting water from a roof. **2.** In electrical wiring, the rectangular space allowed around the interior of an electrical panel for the installation of feeder and branch wiring conductors.



gutter

gutter bed A strip of flexible metal over the wall side of a gutter that prohibits any gutter overflow from penetrating the wall.

gutter hook A bent metal strip used for securing or supporting a metal gutter.

gutter plate **1.** A single side of a box or valley gutter, lined with flexible metal and carrying the feet of the rafters. **2.** A beam that supports a lead gutter.

gutter spikes Long (6″ to 12″) aluminum or galvanized steel nails used to hang gutters.

gutter straps Metal bands used to support gutters.

guy A cable or rope anchored in the ground at one end and supporting or stabilizing an object at the other end.

gypsum A naturally occurring, soft, whitish mineral (hydrous calcium sulfate) that, after processing, is used as a retarding agent in Portland cement and as the primary ingredient in plaster, gypsum board, and related products.

gypsum backerboard A type of gypsum board, not as smooth as wall-board, surfaced with gray paper, and manufactured specifically as a base onto which tile or gypsum wallboard is adhered.

gypsum board A panel whose gypsum core is paperfaced on each side, and that is used to cover walls and ceilings while providing a smooth surface that is easy to finish. Used as a substitute for plaster.



gypsum board

gypsum concrete A mixture of calcined gypsum binder, wood chips or other aggregate, and water. The mixture is poured to form gypsum roof decks.



gypsum concrete

gypsum fiber concrete A gypsum concrete whose aggregate is composed of wood shavings, fiber, or chips.

gypsum fiber panels Gypsum panels with fiber reinforcement concentrated on each face of the panel.

gypsum lath A gypsum board used as the base for application of gypsum plaster.

gypsum-lath nail A low-carbon steel nail with a large flat head and long point. The characteristics make it especially suitable for fixing gypsum lath and plasterboard.



gypsum-lath nail

gypsum perlite plaster A base-coat plaster manufactured from gypsum and an aggregate of perlite.

gypsum plaster A plaster made from ground calcined gypsum. The set and workability of gypsum plaster are controlled by various additives. When mixed with aggregate and water, the resulting mixture is used for base-coat plaster.

gypsum sheathing A type of wallboard whose core is made from gypsum with which additives have been mixed to make it water-resistant. The sheathing is surfaced with a water-repellent paper to make it appropriate for exterior wall coverings.

gyratory crusher A rock-crushing mechanism whose central conical member moves eccentrically within a circular chamber.

H

Abbreviations

h harbor, hard, height, hours, house, hundred

H "head" on drawings, high, high strength bar joist, Henry, hydrogen

HA hour angle

handhld handheld

H&M hit and miss

HASP health and safety plan

haz hazardous

HAZMAT hazardous materials

HB hollow bark

HC high capacity

HCFCs hydrochlorofluorocarbons

HCl hydrochloric acid

HD heavy duty, high density

hd head(s)

hdbrd hardboard

hdcp handicap

hdlg handling

HDO high-density overlaid

HDPE high-density polyethylene

Hdr header

hdw, hdwe, hdwr hardware

hdwd hardwood

He. helium

HE high explosive

Help helper average

hem hemlock

HEPA high-efficiency particulate air (filter)

HEW Department of Health, Education, and Welfare

hex hexagon

hf half, high-frequency

HF hot finished

HFCs hydrofluorocarbons

hg hectogram

Hg mercury

hgr hanger(s)

hgt height

hi high

HI height of instrument

HIC high interrupting capacity

HID high intensity discharge

hint high intensity

hip hipped (roof)

HIPS high-impact polystyrene

hl hectoliter

hm hectometer

HM hollow metal

hndrl handrail

HO high output

H-O-A hand-off-auto

hol hollow

hor, horiz horizontal

H or M hit or miss

hosp hospital

HOW homeowner's warranty

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

hp, HP horsepower

HP high pressure, steel pile section, handicapped person

HPF high power factor

HPLC high-performance liquid chromatography

hr hour

HRS hazard ranking system, hot rolled steel

Hrs/Day hours per day

HS high strength, hollow stem

HSC high short circuit

hsg housing

hst hoist

ht, Ht height, heat

HT high-tension

htd heated

htg, Htg heating

htr heater(s)

Htrs heaters

HTRW hazardous toxic radiological waste

HUD Department of Housing and Urban Development

hv, HV high voltage

HVAC heating, ventilating, and air conditioning

hvy, Hvy heavy

HW high-water, hot water, hazardous waste, heavy weight

HWM high-water mark

hwy highway

Hyd, Hydr hydraulic

hyd, hydraul hydraulic, hydrostatics

hyd exc hydraulic excavator

hydrocar hydrocarbons

hydrst hydrostatic

hyp, hypoth hypothesis; hypothetical

hz hertz (cycles)

Definitions

habitable space General living areas in a building, excluding bathrooms, storage, and utility spaces.

hachure One of the short parallel lines used on an architectural drawing for shading or for indicating a section of a drawn object, or on a topographic map for indicating the degree and direction of slopes and depressions.

hack **1.** To cut or strike at something irregularly or carelessly, or to deal heavy blows. **2.** A person who lacks, or does not apply, knowledge or skill in performing his job.

hacking **1.** Striking a surface with a special tool so as to roughen it. **2.** A style of bricklaying in which the bottom edge is set in from the plane surface of the wall. **3.** In a stone wall, the breaking of a single course into two or more courses, sometimes for effect but usually because of the scarcity of larger stones.

hacksaw A lightweight, metal-cutting handsaw having a narrow, fine-toothed blade retained in an adjustable metal frame.



hacksaw

hair interceptor In plumbing, a traplike device installed in the waste drain side of a fixture's plumbing system to capture and collect hair on screens or in perforated steel baskets that are removable from the bottom of the device.

hairline cracks Very fine, barely visible random cracks appearing on, but not penetrating, the finish surface of materials such as paint and concrete.

hairpin **1.** A type of wedge used in tightening some kinds of form ties. **2.** Hairpin-shaped rebar sometimes used in beams, columns, and prefabricated column shear heads.

half-bat (half-brick) A half-brick produced by cutting a brick in two, across its length.

half-brick wall A brick wall having the thickness of a brick laid as a stretcher.



half-brick wall

half header Half of a brick or concrete block made by cutting the unit longitudinally through its faces. Half headers are used to close the work at the end of a course.

half-landing (halfpace landing, halfspace landing) A platform in a stairway, where the stairs change direction halfway between the floors of a building.



half-landing (halfpace landing, halfspace landing)

half-mortise hinge A door hinge with one plate surface-mounted on the jamb and the other plate mortised into the door stile.



half-mortise hinge

half-pitch roof A roof with a pitch whose rise is equal to one-half the width of the span.

half-principal A roof rafter or similar member with the upper end not extending all the way to the ridgeboard, but instead supported by a purlin.

half-rabbeted lock A type of mortise lock having a front turned into two perpendicular planes, used on a door with a rabbeted edge.

half-span roof (lean-to roof) A roof that slopes in only one plane and abuts a higher exterior wall.



half-span roof (lean-to roof)

half-story An attic or story immediately below a sloping roof and usually having some partitions and a finished ceiling and floor.



half-story

half-timbered Descriptive of a building style common in the 16th and 17th centuries, with foundations, supports, knees, and studs all made of timbers. The wall spaces between the timbers are filled with masonry, brick, or lathed plaster.

half-truss One side of a jack truss spanning from a main roof truss to a wall, usually at an angle to the main truss.

halide torch A device used to detect leaks of halocarbon refrigerant. The color of the sampling torch's normal, alcohol-produced, blue flame becomes a bright green when the refrigerant is detected.

hall **1.** A large room in which people assemble for entertainment or meetings. **2.** A small entrance room or corridor. **3.** A term often used in the proper names of public or university buildings.

hammer A hand tool with a handle perpendicular to its head, for driving nails or other applications involving pounding or striking.

hammer beam (hammer-beam trusses) Either one of a pair of short horizontal members used in place of a tie beam in roof framing. A hammer beam is attached to the foot of a principal rafter and supported from below by a brace to the supporting column.

hammer brace The brace, often curved, between a hammer beam and pendant post.

hammer dressed Descriptive of stonemasonry having a finish created only by a hammer, sometimes at the quarry.

hammer drill A pneumatically powered mechanism using percussion to penetrate rock.

hammerhead crane A heavy-duty crane with a swinging boom and counterbalance, giving it a "T" shape.

hammer man The workman on a pile hammer who operates the hoist or controls the steam jet that, in turn, powers the hammer.

hammermill crusher An impact type crusher that breaks up and grinds materials to a finished size.

hance **1.** A small arch or half arch connecting a larger arch or lintel to its jamb. **2.** Light-concealing trim member at the top of a window.

hand **1.** Prefaced by "left" or "right" to designate how a door is hinged and the direction it opens. **2.** Preceded by "left" or "right" to designate the direction of turn one encounters when descending a spiral stair, with "right-hand" being clockwise.

hand brace A wood-boring hand tool made of a single frame of small diameter bar or rod bent to form a stationary bracing handle at one end and a bit-holding chuck at the other. A short distance from, but parallel to, the central axis, a handle repeatedly turns in wide circles, causing the bit to turn.

hand drill A hand-operated boring device made up of a central steel tube containing a shaft. At one end is a handle and at the other a bit-holding chuck.

hand float A wooden tool used to lay on and to smooth or texture a finish coat of plaster or concrete.

handicap door opening system A door equipped with a knob or latch and handle located approximately 36″ from the floor, and an auxiliary handle on the other side at the hinge edge, for convenience to persons in wheelchairs.



hand float

handicapped fixtures Refers to plumbing fixture connections complying with ADA requirements that are exposed and located in facilities for handicapped individuals.

handicap water cooler A water cooler set low and operated by push-bars or levers for convenience to persons in wheelchairs.

hand line **1.** A line attached to a structural member or piece of building equipment being hoisted. Used to control the position of the item during erection or setting. **2.** A line manipulated to control stage rigging in a theater.

hand punch A struck tool designed for punching or marking metal, driving and removing pins, and aligning holes. Range in size from 1/4″ to 1″ in diameter, and 4½″ to 20″ long.

handrail A bar of wood, metal, or PVC, or a length of wire, rope, or cable, supported at intervals by upright posts, balusters, or similar members or, as on a stairway, by brackets from a wall or partition, so as to provide persons with a handhold.



handrail

handsaw Any manual woodcutting saw having a handle at one end by which it is gripped and manipulated.

handsplit and resawn (HS and RS) A type of cedar shake. Handsplits are split from cedar bolts by a mallet and froe (a type of steel blade). The pieces are then ripped on a resaw to produce two shakes, each with a rough, split face and a smooth, sawn back.

hand tight Descriptive of couplings tightened by hand by the application of force roughly equal to the force an average man can exert.

hang To install a door or window within its respective frame and/or by its respective hardware.

hanger **1.** A strip, strap, rod, or similar hardware for connecting pipe, metal gutter, or framework, such as for a hung ceiling, to its overhead support. **2.** Any of a class of hardware used in supporting or connecting members of similar or different material as, for instance, a stirrup strap or beam hanger for supporting the end of a beam or joist at a masonry wall. **3.** A person whose trade it is to install gypsum board products.



hanger

hanging gutter A metal gutter attached to the roof eaves with metal straps and sometimes further supported by the fascia.

hanging rail The horizontal section at the top and bottom of a door, to which the hinges are secured.



hanging gutter

hanging steps Cantilevered steps.

hanging stile **1.** The vertical structural member on the side opposite the handle, to which the hinges are fastened. **2.** That vertical section of a window frame to which the casements are hinged.



hanging stile

hardback Molding and BTR lumber which is D-select graded from the good face only, which must be clear. The back may contain knots that do not extend through the piece.

hardboard Dense sheets of building material made from heated and compressed wood fibers.

hard-burnt **1.** Descriptive of clay products, such as bricks or tiles, having been burnt or fired at high temperatures, resulting in their durability, high compressive strength, and low absorption. **2.** A hard plaster, such as Keene's.

hard conversion The conversion from one system of measurement to another, with an inherent consequence being the necessity of changing the physical sizes of the products involved.

hard edge A special preparation used in the core of gypsum board under the papered edges to provide extra resistance.

hardener **1.** Any of several chemicals serving to reduce wear and dusting when applied to concrete sustaining heavy traffic, such as a floor. **2.** The curing agent of a two-part synthetic resin, adhesive, or similar coating. **3.** A substance used to harden plaster casts or gelatin molds.

hard finish A mixture of gypsum, plaster, and lime applied as a finish coat, usually over rough plastering, then troweled to provide a dense, hard, smooth finish.

hardness **1.** The resistance of a substance, material, or surface, to cutting, scratching, denting, pressure, wear, or other deformation. **2.** The degree, expressed as parts per million or grains per gallon of calcium carbonate in water, to which calcium and magnesium salts are dissolved in water.

hardpan Highly compacted soil, boulder clay, or other usually glacially deposited mixture, sometimes including sand, gravel, or boulders. The extreme density of hardpan makes its excavation difficult.

hard plaster Quick-setting calcined gypsum, usually used in finishing, often requiring a retarding agent to be incorporated in the mix to help control the set.

hardscape Nonplant material landscape work, such as paving and building structures, that occurs as part of a construction project.

hard solder Solder containing silver, copper, or aluminum, and thus requiring more intense heat for melting than does soft solder. Hard solder is usually applied with a brazing torch.

hard stopping A stiff paste having a calcined gypsum content, causing it to harden quickly. Hard stopping is used in painting operations to fill deep holes and wide cracks.

hardware **1.** A general term encompassing a vast array of metal and plastic fasteners and connectors used in or on a building and its inherent or extraneous parts. The term includes rough hardware, such as nuts, bolts, and nails, and finish hardware, such as latches and hinges. **2.** The mechanical equipment associated with data processing. In building automation systems, computer hardware includes the central processing unit (CPU), hard disk drive, monitor (CRT), keyboard, controllers, and analog or digital point modules. Digital equipment such as controls, sensors, and actuators are considered field hardware.



hardware

hardware cloth Usually galvanized, thin screen made from wire welded or woven to produce a mesh size of ⅛″ to ¾″.

hard water Water containing a concentration higher than 85.5 ppm of dissolved calcium carbonate and other mineral salts.

hard wired A communications link permanently joining two devices, nodes, or stations.

hardwood A general term referring to any of a variety of broad-leaved, deciduous trees, and the wood from those trees. The term does not designate the physical hardness of wood, as some hardwoods are actually softer than some softwood (coniferous) species.

harmonic The sinusoidal component of an arc voltage that is a multiple of the fundamental wave frequency.

harsh mortar A mortar that is difficult to spread due to an improper measure of materials.

Hartford loop The configuration of a steam boiler's return piping connections serving to equalize the pressure between the supply and return sides of the system, thus preventing water from backing out of the boiler and into the return line.

harvested rainwater Rainwater collected in a storage unit that can be treated or untreated and used for a variety of applications, such as flushing toilets, serving HVAC units, washing clothes, and irrigation.

hasp A metal fastening device made up of a staple secured to and protruding from one member, and a hinge with a slotted plate fastened to another member. The slotted plate can be slipped over the staple and then locked with a tapered pin or a padlock.



hasp

hatch An opening in a floor or roof of a building, as in a deck of a vessel, having a hinged or completely removable cover. When open, a hatch permits ventilation or the passage of persons or products.



hatch

hat channel furring A light gauge metal furring strip used on vertical concrete surfaces to provide for fastening of finish materials.

hatchet A wood-handled tool having a steel head flattened at one end and suitable for striking or driving, and formed at the other end into a wide, sharp blade suitable for chopping. The underpart of the blade may or may not be notched for pulling.

hatchet iron The hatchet-shaped tip of a type of plumber's soldering iron.

haul distance The distance measured along the centerline or most direct practical route between the center of mass of excavation and the center of mass finally placed. It is the average distance material is moved by a vehicle. *

haunch **1.** A bracket built into a wall or column to support a load falling outside the wall or column, such as a hammer brace in a hammer-beam roof. **2.** Either side of an arch between the crown, or centerstone, and the springing, or impost. **3.** A thickening of a concrete slab to support an additional load, as under a wall.



haunch

haunched beam A beam or similar member broadened or thickened near the supports.

haunched floor A floor slab thickened around its perimeter.



haunched floor

hawk A flat, thin piece of wood or metal approximately 1 foot square and having a short, perpendicular handle centered on its underside. A hawk is used by plasterers for holding plaster from the time it is taken from the mixer to the time it is troweled.

haydite Heated shale having an expanded cellular structure, making it a suitable lightweight aggregate for concrete.

hazard classes Nine classes established by the United Nations to categorize hazardous materials: flammable liquids, flammable solids, explosives, gases, oxidizers, radioactive materials, corrosives, poisonous infectious substances, and dangerous substances.

hazard insurance Insurance that protects against property damage from certain hazards such as storms and fire.

hazardous area **1.** The part of a building where highly toxic chemicals, poisons, explosives, or highly flammable substances are housed. **2.** Any area containing fine dust particles subject to explosion or spontaneous combustion.

hazardous ranking system (HRS) A scoring system used by the U.S. Environmental Protection Agency to assess various environmental aspects of sites, such as ranking disposal sites in need of cleanup.

hazardous substance Any substance that, by virtue of its composition or capabilities, is likely to be harmful, injurious, or lethal.

hazardous waste A material defined by any of several statutes and regulations, usually characterized by a propensity to cause an adverse health effect to humans.

H-bar A steel or aluminum bar used in structural systems, such as suspended ceilings, that has a cross-section in the shape of an "H."

H-beam A misused designation for an HP pile section.



H-beam

H clip A small metal clip that resembles an "H" shape that is used to strengthen the joint of plywood roof sheeting or wafer board.

head **1.** The top of almost anything, such as the head of a nail or a window head. **2.** In roofing, a tile of normal width but only half the normal length, and used in constructing the eaves course. **3.** The horizontal member across the top of a window or door between the jambs, sometimes offering structural support for construction above it. **4.** The measure of the pressure of water, expressed in feet of water. One psi equals 2.31 feet of water.

headache ball (breaker ball) The rounded, heavy, metal or concrete demolition device swung on a cable from the boom of a crane to break through concrete or masonry construction.

head casing The horizontally placed board at the head or top of a door or window opening between the two vertical casings.

header **1.** A rectangular masonry unit laid across the thickness of a wall, so as to expose its end(s). **2.** A lintel. **3.** A member extending horizontally between two joists to support tailpieces. **4.** In piping, a chamber, pipe, or conduit having several openings through which it collects or distributes material from other pipes or conduits.



header

header block A concrete masonry unit from which part of one face shell has been removed to facilitate bonding with adjacent masonry, such as brick facing.

header course In masonry, a course comprising only headers.



header course

header tile In a masonry-faced wall, a tile having recesses to accept headers.

head flashing In a masonry wall, the flashing over a projection, protrusion, or window opening.

heading **1.** In mining, the digging face and its immediate work area in a tunnel, drift, or gallery. **2.** The increase of expansion of a localized cross-sectional area of metal bar due to hot-forging. **3.** A general classification of a category of data, under which follow more specific classifications. **4.** Pieces of lumber from which a keg, or barrel head, is cut. **5.** Stock after it has been cut and assembled to form a barrel head.

heading joint **1.** The joint formed between two pieces of timber connected end-to-end, in a straight line. **2.** The joint between two adjacent masonry units in the same course.

head jamb The horizontal member that constitutes the doorhead or top of a door opening.

headlap That portion of a shingle not exposed to the weather, because it is covered by the shingle(s) in the course above it.



headlap

head mold The molding over an opening such as a door or window.

head pressure The operating pressure in the discharge line of a refrigeration system.

head room **1.** The vertical distance, or space, allowable for passage, as in a room or under a doorway. **2.** The space between the top of one's head and the nearest obstacle above it, as inside a vehicle. **3.** The unobstructed vertical space between a stair tread and the ceiling or stairs above.



headstone

headstone Any principal stone in masonry construction, such as the keystone in an arch or the cornerstone of a building.

headwall The wall, usually of concrete or masonry, at the outlet side of a drain or culvert, serving as a retaining wall, as protection against the scouring or undermining of fill, or as a flow-diverting device.



headwall

heart The center portion of the cross-section of a log. The term usually refers to heartwood.

heart bond A masonry bond, used in walls too thick for through stones, in which a third header covers the joint of two headers meeting within a wall.

hearth The floor of a fireplace and the adjacent area of fireproof material.

hearthstone **1.** A large stone used as the floor of a fireplace. **2.** Other naturally occurring or synthetic materials used to construct a hearth.

heartwood (heart wood) The core of a tree, which is no longer vital to the life growth of the tree and which is often darker and of a different consistency than the growing sapwood.

heat The form of energy inherent in the motion of atoms or molecules, measured in British thermal units, and transferred automatically (wherever temperature differences exist) from warmer to cooler bodies, areas, or elements by conduction, convection, or radiation.

heat-absorbing glass Slightly blue-green-tinted plate glass or float glass designed with the capacity to absorb 40% of the infrared solar rays and about 25% of the visible rays that pass through it. Cracking from uneven heating can occur if the glass is not exposed uniformly to sunlight.

heat-affected zone In welding or soldering, an area of metal that has been altered but has not yet melted.

heat balancing **1.** An efficient procedure for determining a numerical degree of combustion by totaling all the heat losses, in percentages, and subtracting the result from 100%. **2.** A condition of thermal equilibrium where heat gains equal heat losses.

heat capacity The amount of heat required to increase the temperature of a given mass by one degree. The capacity is arrived at numerically by multiplying the mass by the specific heat.

heated space An area of a building that is directly supplied with heat.

heater **1.** A general term including stoves, appliances, and other heat-producing units. **2.** A person who heats something, such as a steelworker who heats rivets on a small forge before passing them to the sticker.

heat exchanger A device designed to transfer heat between two physically separated fluids. The fluids are usually separated by the thin walls of tubing.



heat exchanger

heat gain The net increase in Btus, caused by heat transmission, within a given space.

heating degree days (HDD) A quantitative comparison of the average daily outdoor air temperature to the standard of 65°F used to analyze energy needed to heat or cool a space. One degree day equals one day with an average temperature one degree above 65°F.

heating load The number of Btus per hour required to maintain a specified temperature within a given enclosed space.

heating plant The entire heating system of a building or complex, including either a boiler, piping, and radiators, or a furnace, ducts, and air outlets.



heating plant

heat island effect A pattern of elevated temperatures in urban areas caused by structural and pavement heat fluxes and pollutant emissions. In some cases, urban temperatures can be as much as 10°F warmer than nearby rural areas, which can result in increased energy demands and heat-related illnesses.

heat loss **1.** The net decrease in Btus within a given space, by heat transmission through spaces around windows, doors, etc. **2.** The loss by conduction, convection, or radiation from a solar collector after its initial absorption.

heat of fusion The amount of heat needed to melt a unit mass of a solid at a specified temperature.

heat of hydration **1.** Heat resulting from chemical reactions with water, as in the curing of Portland cement. **2.** The thermal difference between dry cement and partially hydrated cement.

heat pump A refrigeration system designed to utilize alternately or simultaneously the heat extracted at a low temperature and the heat rejected at a higher temperature.

heat recovery The extraction of heat from any source not primarily designed to produce heat, such as a chimney or light bulb.

heat-reflective glass Window glass in which the exterior surface has been treated with a transparent metallic coating to reflect substantial portions of the light and radiant heat striking it.

heat sealing The use of heat and pressure to bond plastic sheets or films.

heat seaming In roofing, joining thermoplastic films or sheets together by heating contact areas so that they fuse together.

heat sink **1.** The substance or environment into which heat is discharged after its removal from a heat source, as by a heat pump. **2.** Any medium capable of accepting discharged heat.

heat source **1.** Any area, environment, or device that supplies heat. **2.** The area from which a refrigeration system removes heat.

heat tracing system A heating system with an externally applied heat source, usually a heating cable, that traces the object to be heated.

heat transfer fluid The liquid substance used to carry heat away from its source to be cooled, usually by another fluid, as in a heat exchanger.

heat transmission The rate at which heat passes through a material by the combination of conduction, convection, and radiation.

heat transmission coefficient Any of several coefficients used to calculate heat transmission by conduction, convection, and radiation through a variety of materials and structures.

heave The localized upward bulging of the ground due to expansion or displacement caused by phenomena such as frost or moisture absorption.

heavy concrete Concrete having a high unit weight up to 300 pounds per cubic foot, primarily due to the types of aggregate employed and the density of their ultimate incorporation. Such diverse materials as trap rock, barite, magnetite, steel nuts, and bolts can be used as aggregate. The density makes heavy concrete especially suitable for protection from radiation.

heavy construction Construction requiring the use of large machinery, such as cranes or excavators.

heavy-duty scaffold A scaffold constructed to carry a working load not to exceed 75 pounds per square foot.



heavy-duty scaffold

heavy-edge reinforcement In highway pavement slabs, reinforcement made of wire fabric with up to four edge wires that are heavier than any of the other longitudinal wires.

heavy joist A timber at least 4″ thick and 8″ wide.

heavy metal A naturally occurring elemental metal with a high molecular weight.

heavy timber **1.** A type of construction requiring noncombustible exterior walls with a minimal fire-resistance rating of two hours, solid or laminated interior members, and heavy plank or laminated wood floors and roofs. Also called *mill construction*. **2.** Rough or surface pieces with a least dimension of 5″.

heavyweight aggregate Aggregate possessing a high specific gravity, such as barite, magnetite, limonite, ilmenite, iron, and steel, making it suitable for use in heavy concrete.

hectare A measurement of land area equal to 2.471 acres or about 107,637 square feet.

hedge In master production scheduling, a quantity of stock used to protect against uncertainty in demand. The hedge is similar to safety stock, except that a hedge has the dimension of timing as well as amount.*

heel **1.** The lower end of a door's hanging stile or of a vertically placed timber, especially if it rests on a support. **2.** A socket, floor brace, or similar device for wall-bracing timbers. **3.** The bottom inside edge of a footing or a retaining wall. **4.** The back end of a carpenter's plane.

heel strap A steel fastening device for connecting a rafter to its tie beam.

height **1.** The distance between two points in vertical alignment or from the top to the bottom of any object, space, or enclosure. **2.** The vertical distance between the average grade around a building, or the average street curb elevation, and the average level of its roof. **3.** The rise of an arch.

height board A measuring device for setting the heights of stair risers.

height of instrument The height of a leveling instrument above the datum being used in the survey.



helical reinforcement

helical reinforcement Column reinforcement bent in the form of a helix. More commonly called *spiral reinforcement*.

helical rotary compressor (screw-type compressor) A device that compresses gas by trapping it in the space formed by the flutes of meshing screws, thus reducing the gas volume.

helical staircase (spiral staircase) A staircase built in the form of a helix.

heliostat An instrument having an automatically adjusting mirror that follows the apparent movement of the sun and continuously reflects its rays onto a collector.



helical staircase (spiral staircase)

helix **1.** A reinforcing rod bent to form a spiral used for reinforcing the circumference of concrete columns. **2.** A volute found on a Corinthian or Ionic capital. **3.** Any spiral structure, ornament, or form.



helix

helve **1.** A tool handle, such as that of an ax, hatchet, or hammer. **2.** The handle of a wagon.

hem-fir A species combination used by grading agencies to designate any of various species, such as white fir and western hemlock, having common characteristics. The designation is used for identification and standardization of recommended design values and because some species, in lumber form, cannot be visually distinguished.

hemihydrate Any hydrate having only half a molecule of water for every molecule of compound. The most common hemihydrate is partially hydrated gypsum, or plaster of paris.

hemlock A coniferous North American tree, the wood of which is used in general construction and for pulp.

hemp A natural fiber once widely used in cordage, but now almost totally replaced by synthetic fibers, such as nylon and dacron. Hemp is still laminated to a paper backing to produce a type of wallcovering.

HEPA-filtered vacuum A vacuum device fitted with a high efficiency particulate removal system.

hepatoxin A substance that causes liver damage.

herbicide A substance that kills plants on contact.

hermaphrodite caliper A tool with two hinged legs used to lay out lines that are parallel with the edges of the workpiece. It can also be used to locate the center of cylindrical shaped workplaces.

herringbone bond In masonry, a type of raking bond in which a zigzag effect is created by laying rows of headers perpendicular to each other.



herringbone bond

herringbone drain (chevron drain) A V-shaped drain.

herringbone work In masonry, the zigzag pattern created by laying consecutive courses of masonry units at alternating 45° angles to the general run of the course.

hertz A unit of measurement of frequency equal to one cycle per second.

hewn Roughly cut, fabricated, shaped, or dressed.

hex roofing Hexagonally shaped asphalt roofing shingles.

hickey (hicky) **1.** A threaded electrical fitting for connecting a light fixture to an outlet box. **2.** An apparatus used to bend small pipe, conduit, or reinforcing bar.

hick joint In masonry, a mortar joint cut in any direction to be flush with the face of the wall, resulting in a hairline crack that render the joint no longer watertight.

high-bay lighting Usually an industrial lighting system having direct or semidirect luminaires located high above floor or work level.



high-bay lighting

high-build coating A coating composed of a series of films that are thicker than those normally associated with paints (minimum 5 mils) and thinner than troweled material.

high-carbon steel Steel having a carbon content between 0.6% and 1.5%.

high chair Slang for a heavy, wire, vaguely chair-shaped device used to hold steel reinforcement off the bottom of the slab during the placement of concrete.



high chair

high-density overlay A cellulose fiber sheet impregnated with a thermosetting resin and bonded to plywood, rendering a hard, smooth, waterproof, wear-resistant surface for use in concrete formwork and decking.

high-density plywood Plywood manufactured from resin-impregnated veneer and formed with heat at high pressures to render a product having at least twice the density of conventional plywood.

high-density polyethylene (HDPE) An extensively polymerized plastic used for pipe. Polyethylene material is highly abrasion and corrosion resistant, and thereby able to handle a wide variety of slurries and abrasive materials as well as nearly all acids, caustics, salt solutions and other corrosive liquids and gases.

high-early-strength concrete Concrete containing high-early-strength cement or admixtures causing it to attain a specified strength earlier than regular concrete.

high-efficiency particulate air filter (HEPA filter) A high-efficiency (99.9%) dry filter made in an extended surface configuration of deep space folds on submicron glass fiber paper.

high gloss Descriptive of a substantial degree of luster or of a paint that dries with a lustrous, enamel-like finish.



high hat

high hat A recessed lighting fixture that sheds its light vertically downward.

high-hazard contents Those building contents that, in a fire, might explode, burn with such vigor as to approximate explosion, produce toxic fumes, or produce other dangerous effects.



high-intensity discharge lamp

high-impact polystyrene A plastic with good toughness, moderately high heat resistance, and good resistance to stress cracking.

high-intensity discharge lamp A mercury, high-pressure sodium, or other electric discharge lamp requiring a ballast for starting and for controlling the arc, and in which light is produced by passing an electric current through a contained gas or vapor.

high-mass construction A building construction approach using masonry, adobe, or other building materials that can lessen the extremes of diurnal flux, especially in arid climates.

high-output fluorescent lamp A rapid-start fluorescent lamp with greater flux as a result of its operation on higher current.

high-performance building A building that is energy-efficient, healthy, and comfortable for its occupants.

high-pressure laminate Laminate manufactured at pressures between 1,200 and 2,000 pounds per square inch during its molding and curing processes. Used in furniture, paneling, and cabinet manufacturing, high-pressure laminate is also an ideal material for access flooring around sensitive equipment because of its excellent ability to dissipate static electricity.

high-pressure mercury lamp A mercury vapor lamp designed to function at a partial mercury vapor pressure of about 1 atmosphere or more (usually 2 to 4).

high-pressure overlay A plastic laminate consisting of layers of melamine sheet or phenolic-impregnated kraft paper onto which a melamine-impregnated printed pattern sheet and/or a translucent melamine overlay may have been impressed. The laminate is produced at a temperature above 300°F and a pressure of about 400 psi, resulting in a hard, smooth, wear-resistant surface that is often bonded to wood and used in doors and on tabletops.

high-pressure sodium lamp A sodium vapor lamp, operating at a partial vapor pressure of 0.1 atmosphere, that produces a wide-spectrum yellow light.

high-pressure steam curing (autoclave curing) The steam curing of products made from cement, sand-lime, concrete, or hydrous calcium silicate in an autoclave at temperatures of 340° to 420°F.

high-pressure steam heating system A steam heating system in which heat is transported from a boiler to a radiator by steam at pressures above 100 psi.

high rib lath An expanded metal lath used as a backup for wet wall plaster and as formwork for thin concrete slabs.



high rib lath

high-rise **1.** A building having many stories and serviced by elevators. **2.** A building with upper floors higher than fire department aerial ladders, usually ten or more stories.

high side (high pressure side) Those parts in a refrigeration system that are exposed to pressure at least as great as condenser pressure.

high-strength bolts Bolts made from high-strength carbon steel or from alloy steel that has been quenched and tempered.

high-rise

high-strength steel Steel with an inherent high yield point.

high-tensile bolt (high-tension bolt) A bolt made from high-strength steel and tightened to a specified high tension. High-tensile bolts have replaced the use of steel rivets in steel-frame construction.

high transmission glass Glass that transmits an exceptionally high percentage of visible light.

high-velocity duct system A duct system carrying air at more than 2,400′ per minute.

hinge A flexible piece or a pair of plates or leaves joined by a pin so as to allow swinging motion in a single plane of one of the members to which it is attached, such as a door or gate.

hinge backset The horizontal distance from the edge of a hinge to the face of the door that closes against a rabbet or stop.

hinge, electric A hinge designed to pass electric wires from the frame to the door for use in an electric-controlled lock.



hinge, electric

hinge jamb The doorjamb to which the hinges are fastened.

hinge joint Any joint allowing action similar to that permitted by a hinge and only a very slight separation between the adjacent members.

hinge, security **1.** A hinge with a pin that cannot be removed. **2.** A hinge with a stud in one leaf projecting into the other leaf when the door is closed so the door cannot be moved with the pin removed. **3.** *See* **hinge, electric**.

hip **1.** The exterior inclining angle created by the junction of the sides of adjacent sloping roofs, excluding the ridge angle. **2.** The rafter at this angle. **3.** In a truss, the joint at which the upper chord meets an inclined end post.

hip-and-valley roof A roof incorporating both hips and valleys.

hip bevel **1.** The angle between two adjacent sloping roofs separated only by a hip. **2.** The angle at the end of a rafter that allows its conformation to the oblique construction at a hip.

hip capping The top layer of a hip's protective covering.

hip hook *See* **hip iron**.

hip iron (hip hook) A galvanized steel or wrought iron bar or strip secured to the foot of a hip rafter to hold the hip tiles in place.

hip jack In a hip roof, a rafter shorter in length than most of the other rafters used in the same construction, whose upper end is secured to a hip rafter.

hip molding The molding on a hip rafter.

hipped end Either of the triangular ends of a hipped roof.

hipped gable (jerkin head) A modified gabled end that is gabled only about halfway to the ridge and then inclines backward and forms hips where it meets the two principal slopes.



hip rafter

hip rafter The rafter that, in essence, is the hip of a roof, by virtue of its location at the junction of adjacent inclined planes of a roof.

hip roof A roof formed by several adjacent inclining planes, each rising from a different wall of building, and forming hips at their adjacent sloping sides.


hip roof

hip vertical The upright tension member in a truss, the lower end of which carries a floor beam, and the upper end of which joins an inclined end post and an upper cord at a hip.

historical database Records accumulating past project experience stored as data for use in planning, estimating, forecasting and predicting future events. Often includes data that has been processed so as to facilitate planning and other purposes such as validation and benchmarking (e.g., metrics, etc).*

historic records Documentation from past projects that can be used to predict trends, analyze feasibility and highlight problem areas/pitfalls on future similar projects.*

hit-and-miss window A two-part window with the lower sash containing movable ventilation panels. One panel slides in front of the other to permit air flow.

H-molding An H-shaped trim piece used in a butt joint assembly. The two channels of the "H" hold the members in place.

hod In masonry construction, a V-shaped, trough-like container with a pole handle projecting vertically downward from the bottom to allow steadying with one hand while being carried on the shoulder of a laborer (hod carrier) at a construction site. A hod is used to transport bricks or mortar.


hoe

hoe **1.** An implement similar to a garden hoe but having a larger blade to facilitate the mixing of cement, lime, and sand in a mortar tub at a construction site. **2.** A backhoe.

hog **1.** In masonry, a course that is not level, usually because the mason's line was incorrectly set and/or pulled. **2.** A closer in the middle of a course. **3.** A machine to grind waste wood into chips for fuel or other purposes.

hog-backed Cambered. The term is often used in reference to a sagging roof.

hogging The sagging of the end extremities of a beam or timber supported only in the middle.


hoist

hoist **1.** Any mechanical device for lifting loads. **2.** An elevator. **3.** The apparatus providing the power drive to a drum, around which cable or rope is wound in lifting or pulling a load. Also called a *winch.*

holdback **1.** A safety device on a conveyor to prevent reverse motion of the belt automatically. **2.** Funds retained until specific events occur or work is completed.

hold down A connector device used to resist overturning caused by uplift on the chords of shear walls.

hold-down clip A fastener used in an exposed suspension acoustical ceiling system or in roofing to join and anchor adjacent sections of capping.

holding tank A tank used for temporary storage of chemicals or materials being processed.

holiday A small area inadvertently missed during painting or other surfacing applications.*

holistic design An approach that emphasizes the functional relationship between the various building parts and the facility as a whole. May include protection of Earth's resources, as well as an element of spirituality, aiming to create spaces that enrich the quality of the environment *and* the lives of those who use the building.

hollow-backed Descriptive of the unexposed surface of a piece of wood, stone, or other material, intentionally hollowed to render a snug fit against an irregular surface.

hollow bed In masonry, a bed joint in which mortar is placed so as to provide contact only along the edges.

hollow brick A hollow clay masonry unit in which the net cross-sectional area is at least 60%.

hollow chamfer Any concave chamfer.

hollow-core door A flush door with plywood or hardwood faces secured over a skeletal framework, the interior remaining void or honeycombed.

hollow masonry unit (hollow block) A masonry unit in which the net cross-sectional area is less than 75% of the gross cross-sectional area when compared in any given plane parallel to the bearing surface.


hollow masonry unit (hollow block)

hollow metal **1.** Light-gauge metal fabricated into a door, window frame, or similar assembly. **2.** Descriptive of an assembly thus produced.

hollow metal door A hollow-core door constructed of channel-reinforced sheet metal. The core may be filled with some type of lightweight material.

hollow metal frame A door frame constructed of sheet metal with reinforcing at hinges and strikes.

hollow plane A woodworking plane with a convex blade for fashioning hollow or concave molding.

hollow roll A process of joining two flexible metal roofing sheets in the direction of the roof's maximum slope by lifting them at the joint and bending them there to create a cylindrical roll. The fastening of the roll sometimes requires a fastener or metal clip.

Home Energy Rating System (HERS) A scoring system established by the Residential Energy Services Network (RESNET) in which a home built to the specifications of the HERS Reference Home (based on the 2006 International Energy Conservation Code) scores a HERS Index of 100, while a net zero energy home scores a HERS Index of 0. The lower a home's HERS Index, the more energy-efficient it is.

home office Office of a company in the country of origin or centralized location. Usually synonymous with head office.*

home office cost Those necessary costs, typically not incurred at the project site, involved in the conduct of everyday business, which can be directly assigned to specific projects, processes, or end products, such as engineering, procurement, expediting, legal fees, auditor fees inspection, estimating, cost control, taxes, travel, reproduction, communications, etc.*

homogeneous Similar in structure, composition, appearance, or texture.

hone A smooth, fine-grained stone against which a tool's cutting edge is worked to achieve a finish edge much sharper than that yielded by the coarser stone used in preliminary sharpening procedures. Usually, an oil is used in the process to carry off minute particles of loose stone and metal to prevent them from clogging the pores on the stone's surface.

honed finish The very smooth surface of stone effected by manual or mechanical rubbing.

honeycomb **1.** In concrete, a rough, pitted surface resulting from incomplete filling of the concrete against the formwork, often caused by using concrete that is too stiff or by not vibrating it sufficiently after it has been poured. **2.** Voids in concrete resulting from the incomplete filling of the voids among the particles of coarse aggregate, often caused by using concrete that is too stiff. **3.** In sandwich panel construction or in some hollow-cored doors, resin-impregnated paper is fabricated into a network of small, interconnected, open-ended, tubular hexagons laminated between two face panels to provide internal support.

hood **1.** A protective cover over an object or opening. **2.** A cover, sometimes including a fan, a light fixture, fire extinguishing system, and/or grease filtration/extraction system, and supported, hung, or secured to a wall such as above a cooking stove chimney, or to draw smoke, fumes, and odors away from the area and into a flue.


hood

hook **1.** Any bent or curved device for holding, pulling, catching, or attaching. **2.** A terminal bend in a reinforcing bar.

hook-and-butt joint A scarf joint between timbers with their ends fashioned to lock together positively and resist tension.

hook bolt A bolt with an unthreaded end bent into an "L" shape.


hook bolt

hooked bar In reinforced concrete, a reinforcing bar which has a hooked end to facilitate its anchorage.


hooked bar

hook knife (hook bill knife, linoleum knife) A knife with a blade in which the cutting edge is bent back toward itself in the same plane, forming a hook shape.

hoop reinforcement Closely spaced steel rings providing circumferential or lateral reinforcement to prevent buckling of vertical reinforcing bars in concrete columns.

hopper **1.** A top-loading, bottom-discharging funnel or storage bin, as for crushed stone or sand. **2.** One of a pair of draft barriers at the sides of a hopper light. **3.** A toilet bowl, usually funnel-shaped.

hopper lite (hopper light) **1.** A bottom-hinged, inward-opening window sash which allows air to pass above it when open. **2.** A side-hinged, inward opening window sash which, when open, allows most of the passing air over its top, but also allows the passage of some air through a narrow opening along its bottom.

horizon **1.** The apparent intersection of the earth and sky, as perceived from any given position. **2.** The same illusion as it might be portrayed in a perspective drawing.

horizontal Parallel to the plane of the horizon and perpendicular to the direction of gravity.

horizontal application A method of installing gypsum board with its length perpendicular to the framing members.

horizontal auger A drilling machine with a horizontally mounted auger, used to drill blast holes in strip mining.

horizontal boring Soil-boring on the horizontal as opposed to the vertical.

horizontal bracing Any bracing lying in a horizontal plane.

horizontal branch A branch drain accepting waste products delivered to it vertically, by gravity, from one or more similar but usually smaller fixtures, and conducting them horizontally to the primary disposal drain.

horizontal bridging Perpendicular braces between joists or beams placed horizontally to stiffen the system and distribute the load.


horizontal bridging

horizontal control In surveying, a control system in which the relative positions of points has been established by traverse, triangulation, or another system.

horizontal distance The distance between points anywhere on a horizontal plane.

horizontal panel A wall panel in which the major dimension is horizontal.

horizontal pipe Any pipe placed or laid horizontally or at an angle to the horizontal of less than 45°.

horizontal sheeting In excavation, any type of earth-restraining sheeting placed horizontally between and supported by soldier piles.


horizontal sheeting



horizontal shoring

horizontal shoring **1.** Extendible beams or trusses capable of providing concrete form support over fairly long spans, thus reducing the number of vertical supports required. **2.** The collective support provided by several horizontal shores in an application.



horn

horn The extension beyond a right-angled joint that is part of a stile, jamb, or sill.

horse **1.** Framework functioning as a temporary support, such as a sawhorse. **2.** In a stair, one of the slanting supports or strings carrying the treads and risers.

horsehead **1.** A frame-like device for supporting a pulley back over a pit so that people and materials may be lowered into it and raised out from it. **2.** Forepole support when tunneling through soft material.

horsepower A unit measurement of power or energy in the United States Customary System. Mechanically, a single horsepower represents 550 foot-pounds per second. Electrically, a single horsepower represents 746 watts.

horsepower hour A unit representing the amount of work performed by one horsepower in one hour.



hose bib (hose cock)

hose bib (hose cock) An outdoor water faucet protruding from a building at about sill height, which is usually threaded to accept a hose connection.

hose cabinet Identifiable cabinet to house folded hose and valve, partially recessed and wall-mounted.

hose coupling A connection between hoses or between a hose and a pipe.

hose station In a fire safety system, a storage rack that includes a valve, hose, and nozzle.

hose stream test A test that measures an assembly's ability to withstand lateral impact from falling debris during a fire endurance period and before active fire suppression efforts begin.

hospital arm pull A door handle having an extension to allow opening by hooking one's arm around it, thus leaving the hands free.

hospital door A flush door through an opening large enough to allow passage of beds and/or other large equipment.

hospital door hardware The special hardware with which hospital doors are often equipped, such as arm pulls, hinges, terminated stops, latches, and strategically placed protective metal strips or plates.

hospital hinge A fast pin hinge furnished with a special tip to eliminate the possibility of injuries caused by the projection of conventional hinge tips.

hot Slang for a *live* or electrically charged wire or other electrical component.

hot-air furnace A heating unit in which air is warmed and from which the warmed air is drawn into ducts to be carried throughout a building or selected portion thereof.

hot-cathode lamp A type of fluorescent, electric discharge lamp in which the electrodes operate at incandescent temperatures and in which the arc and/or circuit elements provide the energy required to maintain the cathodes at incandescence.

hot chisel A type of chisel used to cut red-hot steel. Has a sharp edge usually 2″ to 2¼″ wide.

hot-dip galvanized Descriptive of iron or steel immersed in molten zinc to provide it with a protective coating.

hot driven rivet Any rivet heated just prior to placement.

hot glue A glue requiring heating before being used.

hotmelt A thermoplastic substance almost always heated before being applied as a coating, sealer, or adhesive.

hot mix Paving made of a combination of aggregate uniformly mixed and coated with asphalt cement. To dry the aggregate and obtain sufficient fluidity of asphalt cement for proper mixing and workability, both the aggregate and asphalt must be heated prior to mixing.

hot press The method of producing plywood, laminates, particleboard, or fiberboard, in which adhesion of layers in the panel is accomplished by the use of thermosetting resins and a heat process, under pressure, to cure the guidelines.

hot rolled Descriptive of structural steel members or sections shaped from steel fillets or plates, heated to a plastic state, by passing them through successive pairs of massive steel rollers, each of which serves to bring the product closer to its final, intended shape, such as an angle, channel, or plate.

hot-setting adhesive An adhesive whose proper setting necessitates a minimum temperature of 212°F.

hot spraying The spraying of paints or lacquers in which the viscosity has been reduced by heat rather than by thinners, allowing formation of a thicker coat, requiring less spraying pressure, hence less overspray.

hot surface **1.** A highly alkaline or highly absorbent surface. **2.** A surface having a high temperature.

hot water As defined for the purpose of building codes, water temperature that is 110°F or greater.

hot water boiler Any heating unit in a hot water heating system in which or by which water is heated before being circulated through pipes to radiators or baseboards throughout a building or portion thereof.

hot water heating system One in which hot water is the heating medium. Flow is either gravity or forced circulation.

hot-water supply The combination of equipment and its related plumbing supplying domestic hot water.

hot wires An electrically charged or power-carrying wire.

hot work Any construction operation involving flames or hot air, or use of heat-producing equipment, such as arc welders and cutting equipment, brazing and soldering equipment, blow lamps, or bitumen boilers.



hot-water supply

housed joint A usually perpendicular joint formed where the full thickness of one member's edge or end is accepted into a corresponding housing, groove, or dado in another member.



housed joint

house drain In any given plumbing system, as of a house or building, the major lowest horizontal pipe(s) connecting directly to the building sewer just outside the building wall.

house pump In a gravity supply system, the pump that is used to fill the gravity tank that supplies water to the building.

house sewer The exterior horizontal extension of a house drain outside the building wall leading to the main sewer, either public or private, and connecting directly to the sewer pipe.

housing Casings that enclose heating, ventilation, and air conditioning equipment, such as coils, filers, or fans. Made most often of sheet metal. May also be used to enclose other types of equipment.

Howe truss A truss with vertical and diagonal webs. The members of the vertical web absorb tension while those of the diagonal web absorb compression.

H-pile A type of steel beam driven into the earth by a pile driver.

H-runner A lightweight, H-shaped, metal member used on its side in a suspended ceiling system, so that its flat top fastens to a channel and the flat bottom fits into the kerfs in the ceiling tiles.

hub **1.** The central core of a building, usually the area into which stairs and/or elevators are incorporated, and from which hallways or corridors emanate. **2.** The usually strengthened central part of a wheel, gear, propeller, etc. **3.** The end of a pipe enlarged into a bill or socket. **4.** A rotating piece within a lock, through whose central aperture the knob spindle passes to actuate the mechanism. **5.** In surveying, a stake designating a theodolite position. **6.** Caulking or cement connections between pipe joints.

hue **1.** The designation of color. **2.** Characteristic by which one color differs from another.

humidifier A mechanical apparatus to add moisture to the air or other material.

humidistat (hygrostat) The automatic regulating device of a humidifier or dehumidifier that is sensitive to and actuated by changes in humidity.



hung ceiling

humidity The water vapor contained in a given space, area, or environment.

hung ceiling A nonstructural ceiling having no bearing on walls, being entirely supported from above by the overhead structural element(s) from which it is suspended.

hung sash A sash hung from its sides by cords or chains, whose other ends are secured to counterweights to allow movement in the vertical plane.



hung window

hung window A window containing one or more hung sashes.

hurricane clips Metal anchor used in pole construction to fasten floor joists to a supporting beam or other structural member.

hurricane-prone regions As defined for the purpose of building codes, coastal regions of the United States susceptible to hurricanes with wind speed greater than 90 mph, including the coasts of the Gulf of Mexico and Atlantic Ocean, as well as Hawaii, Puerto Rico, American Samoa, Guam, and the Virgin Islands.

hurricane protection shield A durable guard that folds out accordion-style to protect windows and sliding glass doors from the high winds of hurricanes.

hybrid beam A fabricated beam having flanges made from steel with a specified minimum yield strength different from that of the steel used in the web plate.

hybrid photovoltaic generator system A power system that combines solar photovoltaics with a conventional generator system to minimize life cycle costs. It takes advantage of the low operating cost of a photovoltaic array and the on-demand capability of a generator. To optimize cost, a PV system can incorporate a generator to run infrequently during cloudy periods. The PV array typically provides 70% to 90% of the annual energy, and the generator provides the remainder.

hydrant A discharge connection to a water main, usually consisting of an upright pipe having one or more nozzles and controlled by a gate valve.

hydrated lime A dry, relatively stable product derived from slaking quicklime.



hydrant

hydration **1.** Any chemical action occurring as the result of combining a material with water. **2.** The chemical reaction that occurs when cement is mixed with water.

hydraulic Characterized or operated by fluid, especially under pressure.

hydraulic cement Cement whose constituents react with water in ways that allow it to set and harden under water.

hydraulic dredge A floating dredge or pump by which water and soil, sediment, or seabed are pumped, either on board for sifting, as for clams or oysters before they are discharged overboard, or through a series of floating pipes for discharge on shore.

hydraulic ejector A pipe through which the working chamber of a pneumatic caisson is cleansed of sand, mud, or small gravel.

hydraulic excavator A powered piece of excavating equipment having a hydraulically operated bucket.

hydraulic fill Fill composed of solids and liquid, usually water, and usually delivered by a dredge. After placement, the water eventually drains to leave only the solid fill.

hydraulic friction Resistance to flow, effected by roughness or obstructions in the pipe, channel, or similar conveying device.

hydraulic glue Glue unaffected by water.

hydraulic hydrated lime The dry, hydrated, cementitious product resulting from the process of calcining a limestone containing silica and alumina to a temperature just below incipient fusion. The resultant lime will harden under water.



hydraulic jack

hydraulic jack A mechanical lifting device incorporating an external lever to which force is applied to cause a small internal piston to pressurize the fluid, usually oil, in a chamber. The pressure exerts force on a larger piston, causing it to move vertically upward and raise the bearing plate above it.

hydraulic lift An elevator car or platform moved by a piston, or plunger, powered by a pressurized fluid, usually oil, in a cylinder.

hydraulic lime Lime composed of at least ten silicates and which will set and harden under water.

hydraulic mortar A mortar capable of hardening under water, hence used for foundations or underwater masonry construction.



hydraulic lift

hydraulic pump The device causing the fluid to be forced through a hydraulic system.

hydraulic splitter A concrete- or rock-cracking mechanism incorporating a wedge inserted into a predrilled hole and then expanded by hydraulic power to cause the cracking.

hydraulic test Employing pressurized water to test a plumbing line for pressure integrity.

hydrocarbons Class of chemical compounds consisting of hydrogen and carbon.

hydrochlorofluorocarbons (HCFCs) Compounds composed of hydrogen, chlorine, fluorine, and carbon atoms. They do not persist to the same extent as chloroflourocarbons, and so do not pose as great a threat to the ozone layer.

hydrofluorocarbons (HFCs) Compounds composed of hydrogen, fluorine, and carbon atoms. Because they do not contain chlorine, they are not involved in ozone depletion.

hydrogeologic testing A means of determining the structure and characteristics of subsurface soils and rocks, and the way water flows through them.

hydronic A term pertaining to water used for heating or cooling systems.

hydrophobic cement A treated cement with a reduced tendency to absorb moisture.

hydro-seeding The liquid application of a combined mixture of grass seed, fertilizer, pesticide, and a moisture-retaining binder sprayed under pressure over an area requiring lawn or grass cover.

hydrostatic head The pressure in a fluid, expressed as the height of a column of fluid, which will provide an equal pressure at the base of the column.

hydrostatic pressure Pressure exerted by water, or equivalent to that exerted on a surface by water in a column of specific height.

hydrostatic strength The capability of a pipe to resist internal pressure buildup, measured under specific conditions.

hygrometer An instrument used for measuring the moisture content of air.

hygrometric expansion The expansion of a material as it takes on moisture.

hygroscopic Having the tendency to absorb and retain moisture from the air.

Hypalon® roofing An elastomeric roof covering available commercially in liquid, sheet, or putty-like (caulking) consistency in several different colors. Hypalon® roofing is more resistant to thermal movement and weathering than neoprene.

hypotenuse The side of a right triangle that faces the right angle.



hypotenuse

I

Abbreviations

I moment of inertia

IARC International Agency for Research on Cancer

IBI Intelligent Buildings Institute

IC interrupting capacity, ironclad, incense cedar

ICBO International Conference of Building Officials

ICC Interstate Commerce Commission, International Code Council

ID inside dimension, inside diameter, identification

IDHA International District Heating Association

IDLH immediately dangerous to life and health

IEEE Institute of Electrical and Electronics Engineers, Inc.

IESNA Illuminating Engineering Society of North America

IF inside frosted

IFB invitation for bids

Ihp indicated horsepower

IMC intermediate metal conduit

imp imperfect

in inch

inc included, including, incorporated, increase, incoming

incan incandescent

incl included, including

Ins insulate, insurance

inst installation

insul insulation, insulate

int intake, interior, internal

IP iron pipe

IPS iron pipe size

IPT iron pipe threaded

IR inside radius at the start, or initiation, of an activity

IRS Internal Revenue Service

ISO Insurance Services Office, International Organization for Standardization

IWP Idaho white pine

Definitions

i In the critical path method (CPM) of scheduling, the symbol that represents the event at the start, or initiation, of an activity.

I-beam A structural member of rolled steel whose cross section resembles the capital letter "I."

ice dam An accumulation of ice and snow at the eaves of a sloping roof.



I-beam

idle equipment cost The cost of equipment that remains on site ready for use but is placed in a standby basis. Ownership or rental costs are still incurred while the equipment is idle.*

idler A gear or wheel used to impart a reversal of direction or rotation of a shaft.

idle time A time interval during which either the worker, the equipment or both do not perform useful work.*

igneous rock A rock formed by the solidification of molten materials.

illuminated sign A sign that is illuminated by an internal or external source, often used to mark a path of emergency exit.

illumination The intensity of light on a surface exposed to incident light.



illuminated sign

I-joist An engineered wood product created with two flanges joined by a web that develops certain structural capabilities. I-joists are also used for rafters.

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

impact cost Added expenses due to the indirect results of a changed condition, delay, or changes that are a consequence of the initial event. Examples of these costs are premium time, lost efficiency, and extended field and home office overhead.*

impact crusher A crushing machine that utilizes a series of hammers to break up materials.



impact crusher

impact damages Losses that affect the overall performance and cost of contract work, such as delay to the project, lost labor productivity, and acceleration. Distinguished from direct damages.

impact factor A number by which a static load is multiplied to approximate that load applied dynamically.

impact isolation **1.** The use of insulating material and structures that reduce the transmission of impact noise. **2.** The degree of effective reduction of impact noise transmission accomplished by the structures and materials designed and used specifically for that purpose.

impact load The dynamic effect on a stationary or mobile body as imparted by the short, forcible contact of another moving body.

impact noise The sound created when a building surface is struck by an object.

impact noise rating The single-number rating used to evaluate and compare the effectiveness of assemblies and floor/ceiling constructions in isolating impact noise. The higher the number, the greater the effectiveness in suppressing noise.

impact resistance The resistance of a member or assembly to dynamic loading. Also refers specifically to an insulations ability to withstand damage or abuse.

impact sound transmission Sound that originates by contact with the structure and travels through the structure.

impact test Any of a number of dynamic tests (usually a load striking a specimen in a specified manner) used to estimate the resistance of a material to shock.

impact wrench An electric or pneumatic wrench with adjustable torque that is supplied to a nut or bolt in short, rapid impulses.

impedance Measured in ohms, the total opposition or resistance to the flow of current when voltage is applied to an alternating-current electric circuit.



impact wrench

impeller **1.** The vaned member of a rotary pump that employs centrifugal force to convey fluids from intake to discharge. **2.** A related device used to force pressurized gas in a given direction. **3.** In ventilation, a device that rotates to move air.

impermeable Descriptive of a material that does not allow the passage of liquid.

impervious Highly resistant to penetration by water.

impervious soil A very fine-grained soil, such as clay or compacted loam, that is so resistant to water penetration that slow capillary creep is the only means by which water can enter.

imposed load Any load that a structure must bear, exclusive of dead load.

impost The often distinctively decorated uppermost member of a column, pillar, etc., that supports an end of an arch.

impoundment A water storage area or tank.

impracticability Inability to perform work because of extreme and unreasonable difficulty, expense, injury, or loss involved. This is sometimes considered practical impossibility.*



impost

impregnation **1.** The penetration of a (timber) product under pressure with an oil, mineral, or chemical solution, usually for preservation. **2.** Treating soil with a liquid waterproofing agent to reduce leakage.

improvement A physical change or addition made on a property so as to increase its value or enhance its appearance.

impulse radar The process of using a generator to produce an electromagnetic pulse that travels through a structure to record and measure the changes in wave velocity without causing damage to the structure. Used to investigate the stability of structures such as bridges, castles, roads, and modern concrete structures.

inactive leaf (inactive door) In a pair of doors, the stationary leaf to which the strike plate is secured. It is usually bolted at the head and sill.

inbark (bark pocket) Ingrown bark enclosed in the wood of a tree by growth and subsequently exposed by manufacture.

inbond A masonry bond across the entire thickness of a wall, and usually consisting of headers or bondstones.

incandescence The emission of visible light as a consequence of being heated.

incandescent lamp A lamp in which electricity heats a (tungsten) filament to incandescence, producing light.

inch A measure of length equal to 1⁄12 of a foot (2.54 cm).

inch of water A unit of pressure that is equal to the pressure exerted by a 1″-high column of liquid water at a temperature of 39.2°F (4°C).

inch-pounds **1.** A unit of work derived by multiplying the force in pounds by the distance in inches through which it acts. **2.** A unit of energy that will perform an equivalent amount of work.

incident radiation Solar energy, both direct and diffuse, upon its arrival at the surface of a solar collector or other surface.

incident sound Noise that is directly received from the source, as distinguished from sound that is reflected from a surface.

incinerator A type of furnace in which combustible solid, semisolid, or gaseous wastes are burned.

incipient decay The early stage of decay in timber in which the disintegration has not proceeded far enough to affect the strength or hardness.

incising **1.** Cutting in, carving, or engraving, usually for decorative purposes. **2.** Cutting slits into the surface of a piece of wood prior to preservative treatment to improve absorption.

inclination **1.** The deviation of a surface or line from the vertical or horizontal. **2.** The angle produced by the deviation of a surface or line from the vertical or horizontal.



inclination

incline A slope, slant, or gradient.

inclined-axis mixer A truck-mounted concrete mixer. A revolving drum rotates around an axis that is inclined from the horizontal axis of the truck's chassis.

increaser In plumbing, a coupling with one end larger than the other. Generally, the small end has outside threads and the large end has inside threads.



increaser

incremental cost (benefit) The additional cost (benefit) resulting from an increase in the investment in a project.*

incrustation Mineral, chemical, or other deposits left in a pipe, vessel, or other equipment by the liquids that they convey.

indent In masonry, a gap left in a course by the omission of a masonry unit. An indent is used for bonding future masonry.

indented bolt A type of anchor bolt comprising a plain bar into which indentations have been forged to increase its grip in concrete or grout.



indented bolt

indented wire Wire whose surface has been provided with indentations to increase its bond when used as concrete reinforcement or for pretensioning tendons.

indenture **1.** An official agreement between a bond issuer and his bondholders. **2.** Any deed or contract between two or more parties.

independent contractor A contractor who, under written contract, provides services to an owner but is not considered an employee of the owner for tax or other legal reasons. The independent contractor controls the means, method, and manner of producing the result to be accomplished.*

independent cost estimate (ICE) A cost estimate made in order to validate other prior estimates for a project.

index mark In surveying, a mark used as a sighting reference to take measurements.

index of plasticity The numerically expressed difference between the liquid and plastic limits (of a cohesive material).

Indiana limestone A durable, easily sawn, planed, carved, and lathed limestone quarried in, and exported from, the state of Indiana.

indicated horsepower The horsepower, determined by an indicator gauge, that is developed in the cylinders exclusive of losses sustained due to engine friction.

indicator pile A pile driven to evaluate future pile.

indicator valve A valve that includes some device indicating its open or closed condition.

indigenous Descriptive of any product, substance, growth, outcropping, characteristic, etc., that is geographically native to the area where it occurs, as opposed to having been introduced there.

indirect costs In construction, all costs that do not become a final part of the installation, but are required for the orderly completion of the installation and may include, but are not limited to, field administration, direct supervision, capital tools, startup costs, contractor's fees, insurance, taxes, etc.*

indirect expense Overhead or other indirect costs incurred in achieving project completion, but not applicable to any specific task.

indirect gain/loss In passive solar design, heat gain or loss that occurs at the surface of a thermal storage wall. Typical materials include brick, concrete, and water.

indirect lighting Lighting achieved by directing the light emitted from a luminaire toward a ceiling, wall, or other reflecting surface, rather than directly at the area to be illuminated.

indirect luminaire A luminaire that distributes 90% to 100% of its emitted light upward.

indirect waste pipe A waste pipe that discharges through an air break or air gap into a trapped receptacle or fixture, rather than directly into the building drainage system.

indirect water heater A water heater system that increases the temperature of the water via a remote heat exchanger.

individual vent A pipe that vents a fixture drain and that is connected to the main vent system at some point higher than the fixture.

indoor air quality (IAQ) The quality and general healthfulness of air within a building, as affected by temperature, humidity, and airborne contaminants.

indoor environmental quality (IEQ) An important criterion for green, or sustainable, building design, this refers to general overall building occupant comfort. Includes humidity, ventilation, and air circulation, acoustics, and lighting.

induced draft A process in which air is drawn through the cooling tower into the fan.

induced draft boiler A boiler that uses a fan at its discharge end to pull air through the burner and oiler, and transfer the exhaust products into the atmosphere through a chimney.



induced draft boiler

induced draft water-cooling tower A water-cooling tower incorporating one or more fans in the path of the saturated air stream leaving the tower.

inductance The process that occurs when one conductor is placed next to another carrying AC current. The ever-changing magnetic field that results will induce a current in the first conductor.

induction The entrainment of air in a room by the strong flow of primary air from an air outlet.

induction air terminal units A factory assembly consisting of a cooling coil and/or heating coil that receives preconditioned air under pressure that is mixed with recirculated air by the induction process.

induction motor A motor that operates on alternating current. Its primary winding is usually on the starter, which is connected to the electric power source. Its secondary winding, usually on the rotor, conveys the induced current.

induction welding A type of welding in which coalescence is achieved by heat derived from the work's resistance to an induced electric current, either with or without applied pressure.

inductive loads Loads whose voltage and current are out-of-phase. Most loads in modern electrical distribution systems are inductive.

industrial hygienist In asbestos abatement, a professional hired by the building owner to sample and monitor the air, and for other safety-related tasks.

industrial waste Liquid waste from manufacturing, processing, or other industrial operations, which might include chemicals but not rainwater or human waste.

industry standard Readily available information in the form of published specifications, technical reports and disclosures, test procedures and results, codes and other technical information and data. Such data should be verifiable and professionally endorsed, with general acceptance and proven use by the construction industry.

inelastic behavior Deformation of a material that remains even after the force that caused it has been relieved or removed.

inert **1.** Chemically inactive. **2.** Resistant to motion or action.

inertia The tendency of a body at rest to remain at rest, or of a body in motion to remain in motion in a straight line unless directly influenced by an external force.

inertia block Usually a concrete block supported on some sort of resilient material and used as a base for heavy, vibrating mechanical equipment, such as pumps and forms, to reduce the transmission of vibration to the building structure.

inert pigment A pigment or extender that does not react chemically with the materials with which it is being mixed.

inexcusable delays Project delays that are attributable to negligence on the part of the contractor, which lead, in many cases, to penalty payments.*

infilling Fill material providing insulation, stiffness, and/or fire resistance. It is used in buildings to fill the void areas, within a frame, between structural members.



infilling

infiltration The leakage of air into a building through the small spaces around windows, doors, etc., caused by pressure differences between indoor and outdoor air.

inflammable Easily ignitable and highly combustible. The preferred term is *flammable*. *See also* **combustible**.

inflatable gasket A type of gasket whose effective seal results from inflation by compressed air.

inflatable structure An airtight structure of impervious fabric, supported from within by slightly greater than atmospheric pressure generated by fans.

inflation A persistent increase in the level of consumer prices, or a persistent decline in the purchasing power of money, caused by an increase in available currency and credit beyond the proportion of available goods and services.*

inflection The bending of a straight line from concave to convex, or the converse.

inflecture point That point in a flexural structural member where reversal of curvature occurs and the bending moment is zero.



inflecture point

information stake A stake used on-site to convey surveying measurements to an excavation crew.

infrared camera A device used to detect uninsulated or underinsulated areas and gaps in the building envelope where heat is escaping in the winter and entering in the summer.

infrared heater A source of heat-producing wavelengths, longer than visible light, which do not heat the air through which they pass, but only those objects in the line of sight.

infrared lamp A type of incandescent lamp that often has a red glass bulb to reduce its radiated visible light. Such a lamp emits more radiant power in the infrared region than does a standard incandescent lamp, and it has a lower filament temperature, which contributes to its longer life.

infrastructure Improvements supporting an area, including transportation, roadways, communication, and utility systems.

ingle **1.** A fireplace. **2.** A hearth.



ingle

ingot A large mass of molten metal cast in a vertical mold but requiring further processing before becoming a finished product.

inhibitor Oxidants added to coatings to retard drying, skinning, and other undesirable effects or conditions.

initial drying shrinkage The difference between the length of a concrete specimen when first poured and the final, permanent length of the same specimen after it has dried, usually expressed as a percentage of the initial moist length.

initial prestress The stress or force applied to prestressed concrete at the time of its stressing.

initial set That point in the setting of a concrete and water mixture when it has attained a certain degree of stiffness, but is not yet finally set. Initial set is usually expressed in terms of the time required for a cement paste to stiffen enough to resist a pre-established degree of penetration by a weighted test needle.

initial stress The stress existing in a prestressed concrete member prior to the occurrence of any loss of stress.

initiating circuit A circuit in a fire safety system that contains sensors to detect a fire condition.

injection burner A gas burner in which gas and air for combustion are forced into the burner by a gas jet.

inlay **1.** To decorate with inlaid work. **2.** An ornamental design cut into the surface of linoleum, wood, or metal, and filled with a material of different color, often by gluing.

inlet **1.** The surface connection to a closed drain or pipe. **2.** The upstream end of any structure through which there is a flow.

inorganic material Substances of mineral composition, not carbon compounds of animals or vegetables.

input system A ventilating system utilizing a fan to draw air from a roof into rooms through ducts. An air cleaner or filter and an automatic air heater are usually included.

insert **1.** A patch, plug, or shim used to replace a defect in a plywood veneer. **2.** A unit of hardware embedded in concrete or masonry to provide a means for attaching something. **3.** A nonstructural patch in laminated timber, made for the sake of appearance.


insert

inside-angle tool In masonry and plastering, a float designed especially for shaping inside (internal) angles.

inside caliper A caliper with pointed legs turned outward that is used for measuring inside diameters.

inside casing The interior trim around the frame of a door or window, which might consist of dressed boards, molding, and trim.


inside casing

inside corner molding Concave or canted molding used to cover the joint at the internal angle of two intersecting surfaces.

inside lining Any part of a cased frame that has its face toward the building or structure.

inside stop Usually, a beaded or molded strip of wood secured to the casing along the inside edge of the inner sash to hold it in place and restrict its movement to the vertical plane.

inside thread The threaded inner surface of a pipe or fitting that accepts the outside threads of another pipe or fitting.


inside thread

inside trim Any trim used inside a building.

in situ **1.** In place, as natural, undisturbed soil. **2.** Descriptive of work accomplished on the site rather than in prefabrication elsewhere, as in cast-in-place concrete.

in situ concrete Concrete placed where it will harden to become an integral part of the structure, as opposed to precast concrete.

in situ soil test Soil testing performed in a borehole, tunnel, or trial pit, as opposed to being performed elsewhere on a sample that has been removed.

inspection **1.** A visual survey of construction work—either completed or in progress—to ensure that it complies with the contract documents. **2.** Examination of the work by a public official, owner's representative, or others.

inspection eye A pipe fitting equipped with a plug that can be removed to allow examination or cleaning of the pipe run.


inspection eye

inspection manhole A covered shaft leading from the outside down to a sewer or duct, so constructed as to allow a person to enter it from the surface.


inspection manhole

inspector A person authorized and/or assigned to perform a detailed examination of any or all portions of the work and/or materials.

instant lock (instant locker) **1.** An automatic lock that is actuated by the closing of the door. **2.** A time lock or chromatic lock working on the same principle.

instructions to bidders A document included as part of the bidding requirements that sets forth specific instructions to candidate constructors on procedures, expectations, and disclaimers of the owner, and other necessary information for the preparation of proposals for consideration by the owner for a competitive bid.

insulate To provide with special features and/or materials that afford protection against sound, moisture, heat, or heat loss.

insulated cavity wall A hollow masonry wall with a cavity containing some type of insulation.

insulated concrete forms (ICF) Highly insulated, pre-engineered forms for reinforced concrete walls with R-values as high as R-40. Most often made of polyvinyl chloride (PVC) or expanded polystyrene foam (EPS).

insulated conductor An electrical conductor that is contained within an NEC-approved, nonconductive material.

insulated flange A coupling that interrupts the electrical transmission between two metal pipes.

insulated metal roofing A type of roofing panel made from mineral fiber, insular glass, foamed plastic, etc., and faced with light-gauge flexible metal.

insulated roof membrane assembly (IRMA) A roofing system where the roof membrane is laid directly on the roof deck and then covered with extruded foam insulation and ballasted with stone.

insulating board A thin, lightweight, rigid or semirigid board, usually of processed plant fibers, that offers little structural strength but does provide thermal insulation. It is usually applied under a finish material.



insulating board

insulating concrete Concrete possessing low thermal conductivity and used as thermal insulation.

insulating fiberboard Building board manufactured from processed plant fiber in a variety of sizes, thicknesses, densities, and strengths.

insulating formboard Insulation board that serves as a permanent form for poured-in-place gypsum or lightweight concrete roof decks.

insulating glass Glazing comprising two or more panes of glass, between which there exist(s) a hermetically sealed airspace(s), joined around the edges.


DEPENDING ON DEGREE OF SECURITY PROTECTION REQUIRED, THICKNESS CAN RANGE FROM 1" (25 MM) TO APPROXIMATELY 4-3/4" (121 MM)
MULTIPLE LAYERS OF GLASS AND/OR POLYCARBONATE PLASTIC
EDGE SPACER AND AIRSPACE
03568

insulating glass

insulating resistance The measure of a material's ability to inhibit electric current flow.

insulating sheathing Insulating board with a minimum thermal resistance of R-2 of the core material.

insulation **1.** Material used to reduce the effects of heat, cold, or sound. **2.** Any material, device, or technique that provides protection against fire or the transfer of electricity, heat, cold, moisture, or sound. **3.** Thermal insulation is a material used for covering pipes, ducts, vessels, etc., to effect a reduction of heat loss or gain.

insulation batt Flexible insulation of loosely matted plant or glass fibers faced on one or both sides with kraft paper or aluminum foil and usually available in specifically sized sections.



insulation batt

insulation blanket Usually composed of the same materials and the same widths and thicknesses as batts, but is available in rolls.

insulation lath Gypsum lath with an aluminum foil backing that provides resistance to heat flow and moisture.

insulation resistance The resistance of an insulator to a directly applied current.

insulator An insulating device designed and used to physically support a conductor and electrically separate it from other conductors or objects.

insurance A contract, typically referred to as an insurance policy, in which the insurer, in return for the premium stated in the policy, agrees to pay the insured up to the limits specified in the policy for losses or damages incurred by the insured.

insurance, builder's risk A specialized form of property insurance that provides coverage for loss or damage to the work during the course of construction.

insurance, certificate of A document, issued by an authorized representative of an insurance company, stating the types, amounts, and effective dates of insurance in force for a designated insured.

insurance, completed operations Liability insurance coverage for injuries to persons or damage to property occurring **1.** when all operations under the contract have been completed or abandoned; **2.** when all operations at one project site are completed; or **3.** when the portion of the work out of which the injury or damage arises has been put to its intended use by the person or organization for whom that portion of the work was done. Completed operations insurance does not apply to damage to the completed work itself.

insurance, comprehensive general liability A broad form of liability insurance covering claims for bodily injury and property damage that combines, under one policy, coverage for all liability exposures (except as specifically excluded) on a blanket basis and automatically covers new and unknown hazards that may develop.

insurance, contractor's liability Insurance purchased and maintained by the contractor to protect from specified claims that may arise out of, or result from, the contractor's operations under the contract, whether such operations are by the contractor or by any subcontractor, or by anyone directly or indirectly employed by any of them, or by anyone for whose acts any of them may be liable.

insurance, employer's liability Insurance protection for the employer against claims by employees or employees' dependents for damages that arise out of injuries or diseases sustained in the course of their work, and that are based on common law negligence rather than on liability under workers' compensation acts.

insurance, extended coverage An endorsement to a property insurance policy that extends the perils covered to include windstorm, hail, riot, civil commotion, explosion (except steam boiler), aircraft, vehicles, and smoke.

insurance, liability Insurance that protects the insured against liability on account of injury to the person or property of another.

insurance, loss of use Insurance protecting against financial loss during the time required to repair or replace property damaged or destroyed by an insured peril.

insurance, owner's liability Insurance to protect the owner against claims arising out of the operations performed for the owner by the contractor and arising out of the owner's general supervision.

insurance, personal injury Bodily injury, and also injury or damage to the character or reputation of a person. Personal injury insurance includes coverage for injuries or damage to others caused by specified actions of the insured, such as false arrest, malicious prosecution, willful detention or imprisonment, libel, slander, defamation of character, wrongful eviction, invasion of privacy, or wrongful entry.

insurance policy A contract that provides insurance against specific loss. *See also* **insurance**.

insurance, professional liability Insurance coverage for the insured professional's legal liability for claims for damages sustained by others allegedly as a result of negligent acts, errors, or omissions in the performance of professional services.

insurance, property Coverage for loss or damage to the work at the site caused by the perils of fire, lightning, extended coverage perils, vandalism and malicious mischief, and additional perils (as otherwise provided or requested).

insurance, property damage Insurance covering liability of the insured for claims for injury to or destruction of tangible property, including loss of use resulting therefrom, but usually not including coverage for injury to, or destruction of, property that is in the care, custody, and control of the insured.

insurance, public liability Insurance covering liability of the insured for negligent acts resulting in bodily injury, disease, or death of persons other than employees of the insured, and/or property damage.

insurance, special hazards Insurance coverage for damage caused by additional perils or risks to be included in the property insurance (at the request of the contractor, or at the option of the owner). Examples often included are sprinkler leakage, collapse, water damage, and coverage for materials in transit to the site or stored off the site.

insurance, workers' compensation (workmen's compensation insurance) Insurance covering the liability of an employer to employees for compensation and other benefits required by workers' compensation laws with respect to injury, sickness, disease, or death arising from their employment.



integral frame

intake The opening or device through which a gas or fluid enters a system.

integral frame A metal door frame whose trim, backhands, rabbets, and stops are all fabricated from one piece of metal for each jamb and for each head.

integral lock A type of mortise lock in which the cylinder is contained in the knob.

integral waterproofing The waterproofing of concrete achieved by the addition of a suitable admixture.



integral lock

integrated building system A building designed to efficiently use climatic resources for heating, cooling, lighting, and electric power generation.

integrated ceiling A suspended ceiling system in which the grid and individual acoustical, illumination, and air-handling elements are combined to form a single, integrated system.

integrated design Also referred to as holistic or whole building design. A design method that integrates, early in the process, the whole building team, including all disciplines. For a sustainable building, resource efficiencies, indoor air quality and other goals can be achieved most effectively with this approach.

integrated project delivery A project delivery method in which the three parties, owner, designer, and contractor, execute a single relational contract to work together collaboratively and share in the risks associated with the project.

integration An essential concept in sustainable building that views the building as a system and allows the discovery of synergies and potential tradeoffs or pitfalls with design choices. An integrated design approach helps maximize synergies and minimize unintended consequences.

intelligent building (smart building) A building that contains some degree of automation, such as centralized control over HVAC systems, fire safety and security access systems, and telecommunication systems.

intercept In surveying, the length of the staff visible between the two stadia hairs of a transit's telescope.

interceptor An apparatus that functions to trap, remove, and/or separate harmful, hazardous, or otherwise undesirable material from the normal waste that passes through it, allowing acceptable waste and sewage to discharge by gravity to the disposal terminal.



interceptor

intercom A general term for an internal communication system, such as one employing telephones, or microphones and loudspeakers that function without a central switchboard.

interconnection Any arrangement of pipes whereby water may flow from one system to another as determined by the pressure differential between the two systems.

interest expense A contractor's cost of borrowing funds or use of equity capital.

interface A common boundary shared by two adjacent parts of a system.

interference **1.** Any obstruction that prevents planned or normal usage or operations. **2.** Cooling tower effluent that enters the intake of an adjacent tower.

interior door A door installed inside a building, as in a partition or wall, having two interior sides.

interior finish The interior exposed surfaces of a building, such as wood, plaster, and brick, or applied materials such as paint and wallpaper.

interior plywood Plywood in which the laminating glue is adversely affected by moisture; hence, it should be restricted to indoor or interior applications.

interior span An uninterrupted beam or slab that is continuous with neighboring spans.

interior stop In glazing, a removable bead or molding strip that serves to hold a light or panel in position when the stop is on the interior of the building, as opposed to an exterior stop.



interior span

interior wall A wall having two interior faces and existing entirely within the exterior walls.

interlocked **1.** Firmly joined. **2.** Closely united. **3.** Placed in close relative proximity, or in a specific relationship with another or others.

interlocking joint **1.** In ashlar or other stonework, a joint accomplished by joggles in the joining units. **2.** In sheet metal, a joint between two parts whose preformed edges engage to form a continuous locked splice.

intermediate floor beam In floor framing, any other floor beams that are positioned between the end floor beams.

intermediate rail In a door, any rail, one of which might be a lock rail, between the top and bottom rails.

intermediate stiffener On a beam or girder, any stiffener between the end stiffeners.

intermittent-flame-exposure test An ASTM test of roof covering that involves exposing a sample of the roof material to a gas flame for a specified interval.

intermittent weld A weld whose continuity is interrupted by recurrent unwelded spaces.



intermediate rail

internal glazing Glazing placed in interior partitions or.

internal partition trap A plumbing trap that relies on an internal partition of some form, rather than the water used in a standard trap, for a seal.

internal pressure The pressure within a building. Dependent on outside conditions, such as wind velocity, and the number and location of openings in the building.

internal treatment The treatment of water by feeding chemicals into the boiler rather than into the preheated water itself.

internal vibration Rapid agitation of freshly mixed or placed concrete performed by mechanical vibrators inserted at strategic locations.

intern architect An apprentice architect who works under the direction of registered architects.

International Building Code (IBC) The building code established in 2000 by the International Code Council (ICC) that, when adopted by a jurisdiction, covers all buildings other than one- and two-family dwellings and multiple single-family dwellings not more than three stories in height.

International Residential Code (IRC) The International Code Council's (ICC) building code that, when adopted by a jurisdiction, covers all one- and two-family dwellings not more than three stories in height.

interoperability The ability of BIM tools from multiple vendors to exchange building model data and operate on that data. Interoperability is a significant requirement for team collaboration and data movement between different BIM platforms.

interpolate To estimate untested values that fall between tested values.

interrogatories A formal method of obtaining information relevant to a lawsuit from a party by submitting written questions that must be answered under oath within a certain time period.

interruption A stopping or hindering of the normal process or flow of an activity.*

interstate commerce The buying, selling, or exchange of goods or property across state lines.

interstitial condensation Condensation that forms within an element of a building, such as within a wall.

intrados The undersurface or interior curve of an arch or vault.

intrusion alarms Sensors that detect break-ins or forced entries into a facility.

intumescent Descriptive of a material, like a paint or caulk, that forms a passive fire protection system when applied to another material, like steel or pipe. The intumescent material remains inactive until subjected to heat, when it swells and chars and creates a fire barrier.



intrados

inventory control **1.** A management plan designed to minimize the number and quantity of hazardous substances on a construction project. **2.** A managerial process to control the quantity of items in storage.

invert The lowest inside surface or floor of a pipe, drain, sewer, culvert, or manhole.

invert block A wedge-shaped, hollow, masonry tile incorporated into the invert of a masonry sewer.



invert

inverted ballast A lamp ballast that operates on direct current.

inverted crown The fall or pitch from the sides to the center of a road, driveway, etc.

invert elevation The elevation of an invert (lowest inside point) of pipe or sewer at a given location in reference to a benchmark.

inverter Power conditioning equipment for photovoltaic systems used to convert DC power from photovoltaic arrays, wind turbines, water turbines, fuel cells, or batteries to AC power. A rotary inverter is a DC motor driving an AC generator. More common are static inverters, which use power transistors to achieve the conversion electronically.

invitation to bid A written notice of an owner's intention to receive competitive bids for a construction project wherein a select group of candidate constructors are invited to submit proposals.

invited bidders (preferred bid list) A group of bidders chosen by the owner to submit bids for a project.

invoice An itemized bill listing the items and charges of merchandise and/or work.

ion An atom with one or more electrons missing.

ion exchange The process of either gaining or losing electrons from compounds in a chemical exchange.

Ionic order An order of architecture characterized by a column that has spiral volutes at its capital.

ionization detector A device that indicates the presence of specific gaseous compounds in air by subjecting the compound to ultraviolet light or hydrogen flame, and recording the number of ions created.

iron A lustrous, malleable, magnetic, magnetizable, metallic element mined from the earth's crust as ore in hematite, magnetite, and lemonite. These minerals are heated together to 3,000°F in a blast furnace to produce pig iron, which emerges from the furnace as 95% iron, 4% carbon, and 1% other elements.

iron, cast An iron alloy usually containing 2½% to 4% carbon and silicon, possessing high compressive but low tensile strength, and that, in its molten state, is poured into sand molds to produce castings.

iron, malleable Cast iron that has undergone an annealing process to reduce its brittleness.

iron oxide A primary ingredient in a whole range of inorganic pigments.

ironwork A comprehensive term for iron fashioned to be used decoratively or ornamentally, as opposed to structurally.

iron, wrought The purest form of iron metal, which is fibrous, corrosion-resistant, easily forged or welded, and used in a wide variety of applications, including water pipes, rivets, stay bolts, and water tank plates.



ironwork

irrigation **1.** The process or system, and its related equipment, by which water is transported and supplied to otherwise dry land. **2.** The use of water thus supplied for its intended purpose.

irritant A substance that causes discomfort, such as tearing, choking, vomiting, rashes, reddening of the skin, itching, or other topical responses.

isobar A line drawn on a map to indicate the limits of equal contaminant or pressure concentrations.

Isocyanate A glue used in making some building materials, such as bamboo flooring. Once dry, it does not produce toxic pollutants.

isolated heat gain Solar heating achieved using an attached sunspace, such as a greenhouse.

isolated solar gain Passive solar heating in which heat to be used on one area is collected in another area.

isolated spread footing A footing that transmits a load from columns to the supporting soil. If the soil is weak or the column loads heavy, isolated spread footings must be larger.

isolating switch A switch that isolates a circuit from its power source.

isolation joint A joint positioned so as to separate concrete from adjacent surfaces or into individual structural elements that are not in direct physical contact, such as an expansion joint.



isolation joint

isolator The device on a circuit that can be removed to break the circuit in the absence of flowing current.

isometric drawing A type of projection drawing showing three dimensions. The horizontal planes generally appear at 30° from the standard horizontal axis, while the vertical lines are drawn parallel to the actual vertical axis.



isometric drawing

isotherm A line on a graph or map joining points of equal temperature.

isotropic Exhibiting the same properties in all directions.

item A subdivision of the breakdown, smaller than a category, but larger than an element.

itemize To list or state each item separately, as in an itemized bid.

J

Abbreviations

J&P	joists and planks
jct	junction
JIC	Joint Industrial Council
jour	journeyman
JP	jet propulsion
jt, jnt	joint
jtd	jointed
jsts	joists
junc	junction

Definitions

j A symbol used to describe the event at the head of an activity arrow in a critical path method (CPM) schedule.



jack

jack **1.** A portable mechanism for moving loads short distances by means of force applied with a lever, screw, hydraulic press, or air pressure, as in applying the prestressing force to the tendons, or making small adjustments in the elevations of forms or form support, as in lift slab or slipform operations. **2.** In electricity, a female connecting device or socket to which circuit wires are attached and into which a plug may be inserted (as on a telephone switchboard).

jacked pile A pile that is forced into the ground by jacking against the building above it.



jacket

jacket **1.** A covering, either of cloth or metal, applied to exposed heating pipes or ducts, to exposed or unexposed casing pipes, or over the insulation of such pipes. **2.** A watertight outer housing around a pipe or vessel, the space between being occupied by a fluid for heating, cooling, or maintaining a specific temperature. **3.** In wire and cable, the outer sheath or casing that protects the individual wires within from the elements and provides additional insulation properties.

jackhammer A handheld, pneumatically powered device that hammers and rotates a bit or chisel. A jackhammer is used for drilling rock or breaking up concrete, asphalt paving, etc.



jackhammer

jacking device A mechanism used to stress the tendons for prestressed concrete, or to raise a vertical slipform. *See also* **jack**.

jacking force The temporary force applied to tendons by a jacking device to produce the tension in prestressing tendons.

jacking plate A steel-bearing plate used during jacking operations to transmit the load of the jack to the pile.

jacking stress The maximum stress that occurs during the stressing of a precast concrete tendon.

jack lagging The timber-bearing members employed in building the forms for arches or for other unusual shapes.

jackleg An outrigger post.

jack plane A medium-sized carpenter's plane used to do the coarse work on a piece of timber, such as truing up the edges in preparation for finish planing.

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

jack post An adjustable metal structural support most often used to replace inadequate supporting members.

jack rafter Shortened rafter generally found in hip roofs. A hip jack rafter spans from the plate to the hip rafter. A hip-valley cripple jack spans between a hip rafter and a valley rafter. A valley jack spans from a valley rafter to the ridgeboard.

jack screw A screw-operated mechanical device equipped with a load-bearing plate and used for lifting or leveling heavy loads.

jack shaft A short drive shaft, as between a clutch and a transmission.

jack shore An adjustable, usually telescopic, single-post metal shore.



jack shore

jack timber In framework, a timber that is shorter than the rest because it has been intercepted by another member.

jack truss A roof truss that is smaller than the main trusses, such as a truss in the end slopes of a hip roof.

jamb An exposed upright member on each side of a window frame, door frame, or door lining. In a window, these jambs outside the frame are called *reveals*.

jamb anchor A metal anchoring device that secures the frame to the wall when inserted in the rear of the jamb of a door frame or window frame.



jamb anchor

jamb block A concrete masonry unit that is slotted at one end and used as an opening to receive a window or door frame.

jamb depth The face-to-face depth of a door frame.

jamb horn In a window frame, that portion of the jamb that extends beyond the sill or head jamb.

jamb post The vertical timber that serves as a jamb at the side of an opening.

jamb stud A wood or metal stud adjacent to the doorjamb.

japan **1.** A dark-colored, short-oil varnish used to provide a hard, glossy surface. **2.** A type of resin varnish often used in paints as a drying agent.

japanned Painted with black japan and then baked.

jaw One of a pair of opposing members of a device used for holding, crushing, or squeezing an object, as the jaws of a vise or a pair of pliers.

jaw crusher A rock-crushing device comprising one fixed inclined jaw and one movable inclined jaw. It is used to reduce rock to specific sizes.

J channel A plastic or metal channel, shaped like a J, that is used to support building trim material.

jedding ax A stonemason’s hand tool with two faces, one flat and the other pointed.

jemmy (jimmy) A short (less than 18″) pinch bar or crowbar, both ends of which are curved.

jerrybuilt Constructed in a shoddy or flimsy manner.

jet **1.** A high-velocity, pressurized stream of fluid or mixture of fluid and air, as emitted from a nozzle or other small orifice. **2.** The nozzle or orifice that shapes the stream. **3.** An orifice or other feature of a toilet that starts the siphon action by directing water into the trapway.

jetting The process by which piles or well points are sunk with the aid of high-pressure water or air. Jetting is the option usually employed in locations where nearby buildings might be adversely affected during pile-driving operations.

jetty **1.** Any portion of a building that protrudes beyond the part immediately below it, such as a bay window or the second story of a garrison house. **2.** A dike-like structure, usually of rock, that extends from a shore into water, usually to provide some kind of protection, but sometimes to induce scouring or bank-building. **3.** A deck on pilings constructed for landing at the edge of a body of water.

jib The hoisting arm of a crane or derrick, whose outer end is equipped with a pulley, over which the hoisting cable passes.

jib boom The hinged extension attached to the upper end of a cranes boom. Its purpose is to extend the reach of the crane or the height of the boom.



jib boom

jib crane **1.** A crane having a swinging jib, as opposed to an overhead traveling crane, which does not. **2.** A cantilevered boom or horizontal beam with hoist and trolley capable of picking up loads in all or part of a radius around the column to which it is attached.

jib door A door constructed and installed so as to be flush with its surrounding wall and whose unobtrusiveness is furthered by the lack of hardware on its interior face.

jig A device that facilitates the fabrication or final assembly of parts by holding or guiding them in such a way as to ensure their proper mechanical and relative alignment. A jig is especially useful in ensuring that duplicate pieces are identical.

jigsaw An electrically powered, table-mounted saw with a small, narrow, vertically reciprocating blade that is capable of cutting a tighter radius than a band saw.



jigsaw

jimmer A hinge comprising two leaves that are permanently joined with a fixed pin.

jitterbug A grate tamper used to cause sand and cement grout to rise to the surface of wet concrete during placement of slabs. May be motorized or hand operated.

job (job site) **1.** Term commonly used to indicate the location of a construction project. **2.** An entire construction project or any component of a construction project.

jobber **1.** A person reasonably knowledgeable and somewhat skilled in most of the more common construction operations, such as carpentry, masonry, or plumbing. **2.** In construction, a jack-of-all-trades.

job condition Those portions of the contract documents that define the rights and responsibilities of the contracting parties and of others involved in the work. The conditions of the contract include general conditions, supplementary conditions, and other conditions.

job-made Made or constructed on the construction site, as a job-made ladder.

job order authorization Written authorization by the owner to accomplish the described work.

job order contracting (JOC) An indefinite delivery/indefinite quantity project delivery method used for construction, remodeling, repair, and landscaping projects. It can also be used for maintenance services. Pricing structures are based on competitively bid coefficients applied to preestablished unit prices. JOC contracts usually have options for annual renewal.

job order proposal The design, along with a detailed scope of work including a project's performance times and price proposal, submitted in accordance with contract requirements. The scope of work and performance times are mutually agreed on before the job order contractor submits a lump-sum, fixed-price, detailed price proposal.

job overhead The expense of such items as trailer, toilets, telephone, superintendent, transportation, temporary heat, testing, power, water, cleanup, and similar items, possibly including bond and insurance associated with the particular project.*

job site The area within the defined boundaries of a project.

joggle **1.** A notch or protrusion in one piece or member that is fitted to a protrusion or notch in another piece to prevent slipping between the members. **2.** A protrusion or shoulder that receives the thrust of a brace. **3.** A horn or stub tenon at the end of a mortised piece to strengthen it and prevent its lateral movement. **4.** The enlarged portion of a post by which a strut is supported. *See also* **key**.

joggle joint In masonry or stonework, a joint that employs joggles in the adjacent members so as to prevent their lateral movement.



joggle joint

See also **joggle**.

joggle truss A roof truss comprising a single, centrally positioned post whose upper end is joggled to connect with the overhead chord, and whose lower end is supported by two braces that angle upward to join the ends of the chord.

joiner's chisel (paring chisel) A long-handled woodworking chisel whose cutting is accomplished without the aid of a striking tool, but by hand force only.



joiner's chisel (paring chisel)

joiner's hammer A hammer whose head has a flat end for striking and a clawed end for pulling nails.



joiner's hammer

joinery **1.** Woodworking that deals more with joining and finishing, such as that required by doors, cabinets, or trim. **2.** A European designation for quality grades of lumber suitable for cabinetry, millwork, or interior trim.

joint **1.** The point, area, position, or condition at which two or more things are jointed. **2.** The space, however small, where two surfaces meet. **3.** The mortar-filled space between adjacent masonry units. **4.** The place where separate but adjacent timbers are connected, as by nails or screws, or by mortises and tenons, glue, etc.



joint

joint banding The visible striping of each panel joint—usually a result of oversanding or uneven absorption of the primer due to differences in surface texture. More noticeable under critical lighting.

joint bolt (handrail bolt) A threaded metal rod or bolt having a nut at each end, used to bring two ends of a handrail together, as well as in joinery to bolt two mating surfaces together, as in a butt joint.

joint box A cast-iron box constructed around a joint between the ends of two electric cables. The cables' protective lead (or other) sheathing is secured by bolted clamps on the exterior of the box, which may be filled with insulation.

joint compound (joint cement) A premixed finishing material for embedding joint tape and filling and finishing gypsum panel joints, corner bead, trim, and fasteners. Sanded to a smooth finish.

jointer (jointer plane) **1.** A power-driven woodworking tool or long, hand-operated, bench plane used to square the edges of lumber or panels. **2.** An offset metal tool used to smooth or indent mortar joints in masonry. **3.** A metal tool about 6″ long and 2″ to 4″ wide, having interchangeable depth-regulating bits and used for cutting joints in fresh concrete. **4.** In masonry, a bent strip of iron used in a wall to strengthen a joint.

joint filler **1.** A powder that is mixed with water and used to treat joints, as in plasterboard construction. **2.** Any putty-like material similarly used. **3.** A compressible strip of resilient material used between precast concrete units to provide for expansion and/or contraction.

jointing **1.** Finishing the surface of mortar joints, as between units or courses, by tooling before the mortar has hardened. **2.** The finishing, as by machining, of a squared, flat surface on one face or edge of a piece of wood. **3.** The initial operation in sharpening a cutting tool, consisting of filing or grinding the teeth or knives to the desired cutting circle.

jointing compound In plumbing, any material, such as paste, paint, or iron cement, used to ensure a tight seal at the joints of iron or steel pipes.

joint knife A hand tool with a wide flexible blade used to apply and smooth joint compound to drywall.


joint reinforcement

joint reinforcement Any steel reinforcement used in or on mortar joints, such as reinforcing bars or steel wire.

joint rule A metal rule having one end formed at a 45° angle. It is used in plastering to form and shape miters at the joints of cornice moldings.

joint sealant An impervious substance used to fill joints or cracks in concrete or mortar, or to exclude water and solid matter from any joints.

joint tape Paper, paper-faced cotton tape, or plastic mesh fabric, used with mastic or plaster to cover the joints between adjacent sheets of wallboard.


joist

joist **1.** A piece of lumber 2″ or 4″ thick and 6″ or more wide, used horizontally as a support for a ceiling or floor. Also, such a support made from steel, aluminum, or other material. **2.** Parallel beams of lumber, concrete, or steel used to support floor and ceiling systems.


joist anchor

joist anchor A beam, wall anchor, or metal tie used to anchor beams or joists to a wall. An example is a metal strip with one end embedded in a concrete or masonry wall and the other end secured to a joist or rafter, so as to provide a lateral tie between the wall and a floor or roof. This type of anchor acts in shear and in tension.

joist bridging Lateral braces inserted between joists to evenly distribute loads.


joist hanger

joist hanger A metal angle or strap used to support and fix the ends of wood joists or rafters to beams or girders. This type of anchor acts in shear and in tension.

joule The metric unit used to measure heat, work, and energy. One joule is the amount of work done or energy expended by a force of 1 newton acting through a distance of 1 meter.

journal **1.** That section of a shaft or axle that rotates within a load-supporting bearing. **2.** The project superintendent's daily report of activities on a project.

journeyman The second or intermediate level of development of proficiency in a particular trade or skill. As related to building construction, a journeyman's license, earned by a combination of education, supervised experience, and examination, is required in many areas for those employed as intermediate level mechanics in certain trades (e.g., plumbing, mechanical, and electrical work).


jumbo brick

jumbo brick **1.** A brick manufactured larger than standard size, measuring 8″ × 4″ × 4″, including mortar joints.

jumper **1.** The short length of wire or cable used to make a usually temporary electrical connection within, between, or around circuits and/or their related equipment. **2.** A steel bar used manually as a drilling or boring tool. **3.** A stretcher covering two or more vertical joints in square rubble. **4.** The inverted mushroom-shaped component of a domestic water tap, on which the washer fits.




junction box

junction box A metal box in which splices in conductors or joints in runs of raceways or cable are protectively enclosed, and which is equipped with an easy access cover.

junction chamber That section in a sewer system where the flow from one or more sewers joins or converges into a main sewer.

jurisdictional dispute An argument between or among labor unions over which entity should perform certain work.

just-in-time A "pull" logistical system driven by actual demand. The goal is to produce, provide, or deliver parts or supplies just in time for the next operation. The approach reduces stock inventories or storage costs, but leaves no room for error.*

jut Any protruding part of a building or structure, such as a jut window.

jute A plant fiber, from which a strong, durable yarn is made and used mostly for carpet backing, burlap, and rope.

K

Abbreviations

k kilo, knot

K Kalium

Ka cathode

kc kilocycle

kcal kilocalorie

kc/s kilocycles per second

KD kiln-dried

KDN knocked down

kg keg, kilogram

kHz kilohertz

KIT. kitchen

kl kiloliter

KLF kips per lineal foot

km kilometer

kmps kilometers per second

kn knot

Kr krypton

kv kilovolt

KVA kilo volt ampere

kvar kilovar

kw kilowatt

kwhr/kwh kilowatt-hour

Definitions

kalamein door A fire door whose solid wood core is usually covered with galvanized sheet metal.


kalamein door

kaolin A usually white mineral found in rock formations, composed primarily of low-iron hydrous aluminum silicate, and used as a basic ingredient in the manufacture of white cement and as a filler or coating for paper and textiles.

keel molding A molding having two ogee curves that meet at a point or fillet, forming a shape that resembles that of a ship's keel.


keel molding

Keene's cement **1.** A white cementitious material manufactured from gypsum that has been burned at a high temperature and ground to a fine powder. Alum is added to accelerate the set. The resulting plaster is hard and strong and accepts and maintains a high polish, hence it is used as finishing plaster. **2.** Anhydrous calcined gypsum.

keeping the gauge In masonry, maintaining the proper spacing of courses of brick.

keeping the perpends In masonry, the accurate laying of the units so that the perpends (end joints) in alternating courses line up vertically.

kelly ball A round-bottomed metal plunger that is dropped into fresh concrete, the degree of penetration indicating the consistency of the concrete.


kelly ball

Kelvin scale A temperature scale on which absolute zero is measured (0°K, equivalent to 273°C). It uses Celsius degrees.

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.



kerf

kerf **1.** A saw-cut in wood, stone, etc., that is usually performed crosswise and usually not completely through the member. Cuts are usually made to allow for bending. **2.** A groove cut into the edges of acoustical tiles to accommodate the splines or supporting elements in a suspended acoustical ceiling system.

kerfed beam A beam in which several kerfs have been cut so as to permit bending.

kettle **1.** The storage container for asphalt to be used for "hot mopped" roof construction. **2.** Any open vessel used to contain paint or in which glue is melted.

key **1.** The removable actuating device of a lock. **2.** A wedge of wood or metal inserted in a joint to limit movement. **3.** A wedge or pin through the protruding part of a projecting tenon to secure its hold. **4.** The tapered last board in a sequence of floorboards, which, when driven into place, serves to hold the others in place. **5.** The roughened underside of veneer or other similar material intended to aid in bonding. **6.** In plastering, that portion of cementitious material that is forced into the openings of the backing lath. **7.** A small, usually squared piece that simultaneously fits into the keyways or grooves of a rotating shaft and the pulley.

key brick A brick whose proper fit in an arch is attained by tapering it toward one end.

keyed Fastened or fixed in position in a notch or other recess, as forms become keyed into the concrete they support.

keyed beam **1.** A lap-jointed beam with joggles or slots cut into both components. Keys are driven into the joggles or slots to increase the bending strength of the joint. **2.** A compound beam whose adjacent layers possess mating grooves to help resist horizontal shearing stress at the interfaces.

keyed brick A brick, one of whose faces has been supplied with a usually dovetail-shaped recess, that serves as a mechanical key for plastering or rendering.



keystone

keyed joint **1.** A joint between two timbers that employs a key to ensure its security. **2.** The concave pointing of a mortar joint.

keyhole saw (hole saw) A thin, narrow-bladed saw used to cut holes in panels or other surfaces.

key plan A small plan that depicts the units in a layout.

key plate An escutcheon.

keystone The usually wedge-shaped uppermost, hence last, set stone or similar member of an arch, whose placement not only completes the arch but also binds or locks its other members together.



keyway

key switch An on-off switch in an electric circuit, which is actuated by a removable key rather than a toggle or button.

key valve A valve operated by a key rather than a handle or lever.

keyway **1.** A recess or groove in one lift or placement of concrete that is filled with concrete of the next lift, giving shear strength to the joint. Also called a *key*. **2.** In a cylindrical lock, the aperture that receives and closely engages the key for its entire length, unlike a keyhole of a common lock. **3.** A key-accepting groove in a shaft, pulley, sprocket, wheel, etc.

keyway forms Metal forms for pouring connected concrete slabs. Holes allow a keyway to be bolted on, then removed.

K factor The measure of a transformer's ability to withstand the heating effects of nonsinusoidal harmonic currents.

kibble A bucket-like device in which material, water, tools, and/or men are raised from a shaft.

kick **1.** In brick, a shallow depression, fray, or panel. **2.** The raised fillet of a brick mold that forms the frog. **3.** The pitch variation between patent glazing and the surrounding roof.

kickback **1.** When a rotating sawblade is pinched by the material it is cutting, momentarily stopping the blade and causing it to pull away from the material. **2.** The illegal return of part of the purchase price by the seller to induce purchase or to improperly influence future purchase of goods or services.

kicker **1.** A wood block or board attached to a formwork member in a building frame or formwork to make the structure more stable. In formwork, a kicker acts as a haunch to take the thrust of another member. Sometimes called a *cleat*. **2.** A catalyst. **3.** An activator, as the hardener for a polyester resin. **4.** A luminaire used to accent or highlight a subject.



kicker

kick lift A jacking wedge that raises or adjusts a piece of gypsum board into position for nailing.

kick-off meeting A meeting that takes place at the beginning of a project. Its purpose is to introduce the project team members, review the overall project, and to discuss items such as construction site logistics, the phasing plan, and the schedule.*

kickpipe A short length of pipe that provides protection for an electric cable where it protrudes from a floor or deck.

kickplate **1.** A metal strip or plate attached to the bottom rail of a door for protection against marring, as by shoes. **2.** A plate, of any metal, used to create a ridge or lip at the open edge of a stair platform or floor, or at the back edge or open ends of a stair tread.

kill **1.** To terminate electrical current from a circuit. **2.** To shut off an engine. **3.** To prevent resin from bleeding through paint on wood by the preliminary application to knots of a shellac or other resin-resistant coating.

kickplate

kiln A furnace, oven, or heated enclosure for drying (wood), charring, hardening, baking, calcining, sintering, or burning various materials.

kiln-dried **1.** Control-dried or seasoned artificially in a kiln. **2.** Lumber that has been seasoned in a kiln to a predetermined moisture content.

kiloampere A unit of electric current equal to 1,000 amperes.

kilocalorie The amount of heat needed to raise the temperature of one kilogram of water 1° Celsius.

kilovolt A unit of electric potential difference equal to 1,000 volts.

kilovolt-ampere A unit of apparent power equal to 1,000 volts or amperes.

kilowatt A measurement or unit of power equal to 1,000 watts or approximately 1.34 horsepower.

kilowatt consumption The amount of electrical power used over a specified time.

kilowatt demand The maximum electrical power usage required to operate a facility over a specified time.

kilowatt-hour A unit of measurement equal to the amount of energy expended in one hour by one kilowatt of power.

king closer A rectangular brick, one corner of which has been removed diagonally to leave a 2″ end, and that functions as a closer in brickwork.


king closer

king pile In strutted sheet pile excavation, a long guide pile driven at the strut spacing in the center of the trench before it is excavated.

kingpin A vertically mounted swivel, pivot, or hinge pin usually supported both above and below.

king post In a roof truss, a member placed vertically between the center of the horizontal tie beam at the lower end of the rafters and the ridge, or apex of the inclined rafters.

king stud In framing, a vertical support member that extends from the bottom to top plate alongside an opening for a door or window.

kip A unit of weight equal to 1,000 pounds.

kiss mark Marks on the faces of bricks where they were in contact with one another during their firing in a kiln.

kitchen As defined for the purpose of building codes, a space whose designated purpose is food preparation.

kite A sheet of kraft paper applied to a sheet of coated roofing during manufacturing to measure the weight of the granules applied to the surface of the roofing.

knapping hammer A steel hammer whose head design may vary, but which is used for breaking and shaping stone, splitting cobbles, etc.

knee **1.** A naturally or artificially bent piece of wood, as used for a brace or haunch. **2.** A sharp, right-angled bend in a pipe. Also called an *elbow*. **3.** A convex handrail.

knee brace A brace between vertical and horizontal members in a building frame or formwork to make the structure more stable. In formwork, it acts as a haunch.


knee brace

knee bracket A brace used to provide extra support under bow and angle bay projecting windows.

kneeler **1.** The pattern-breaking stone or brick at the point where a normal masonry wall changes and begins to form the curve or angle of an arch or vault. **2.** In a gable, the sloped-top, level-bedded stone that supports the inclined coping. **3.** Ecclesiastical furnishing that may be provided for kneeling in a pew. May be attached to the frontal or to the back of the pew.

knee rafter A rafter whose lower end is bent downward to rest more firmly against a wall. Sometimes called a *knee piece*.

knee wall **1.** A wall that shortens the span of the roof rafters by acting as a knee brace, in that it supports the rafters at some intermediate point along their length. **2.** A short wall constructed to extend the height of an existing foundation or other wall system.

knife-blade fuse A type of cartridge fuse in which the metal blades at each end of the cylinder make contact with the fuse within.

knife switch A type of electric switch designed with a hinged or removable blade that enters or embraces the contact clips.


knife-blade fuse

knife-type trencher A vibratory plow attachment used on a trenching machine to install telephone and power cable, television cable, irrigation systems or other light weight cable-type products in the ground without digging a trench.

knob lock A door lock whose spring bolt is operated by one or more knobs, but whose dead bolt is actuated by a key.

knob rose The usually raised round plate that is attached to a door face so as to surround a hole in the door and form a knob socket.



knob rose

knob shank The stem of a doorknob, into whose hole or socket the spindle is received and fastened.

knocked down Descriptive of precut, prefitted, and premeasured, but unassembled construction components, such as might be delivered to a job for on-site assembly.

knocked-down frame A door frame that comes from the manufacturer in three or more parts.



knockout

knockout A prestamped, usually circular section in an electrical junction box, panel box, etc., which can be easily removed to provide access for a fitting or raceway cable.

knot The hard, cross-grained portion of a tree where a branch meets the trunk.

knot cluster A compact grouping of two or more knots surrounded by deflected wood fibers or contorted grain.

knot sealer Any sealer, such as shellac, used to cover knots in new wood to prevent sap or resin bleed-through.

knotty pine Pine wood sawn so as to expose firm knots as an appearance feature. Knotty pine is used for interior paneling and cabinets.

knuckle One of the enlarged, protruding, cylindrical parts of a hinge through which the pin is inserted.

knuckle joint A hinged joint by which two rods are connected.

knurling Very small ridges or beads as machined on a surface to facilitate gripping.

kraft paper A strong brown wrapping paper made from sulfate wood pulp that is sometimes impregnated with asphalt or resin for better moisture resistance when used in construction.

K series A standard Steel Joist Institute designation for long-span steel joists.

K truss A truss in which the arrangement of panels, chords, and web members resembles the letter K.



K truss

k value The thermal conductivity of a substance or material.

L

Abbreviations

L lambert, large, medium wall copper tubing
l labor only, left, length, liter, long, lumen
L & E labor and equipment
L & H light and heat
Lab. labor, laboratory
Lad ladder
LAG lagging
LAM laminated, laminate
LAN local area network
LAS laboratory analytical service
LAT latitude, lattice
Lath lather
LAV lavatory
lb, lbs pound, pounds
lbf/sq in pound-force per square inch
lb/hr pounds per hour
lb/LF pounds per linear foot
lbl label
LBL conduit body, load bearing
Lbr lumber
lc load center
lcd liquid crystal display
LCL less-than-carload lot
LCM least common multiple, loose cubic meter
L&CM lime and cement mortar
LCY loose cubic yard
ld load
lbbrk loadbreak
ldg loading
LDG landing
LDPE low-density polyethylene
Ldr loader
LE leading edge, lead equivalent
LEED Leadership in Energy amd Environmental Design
LECA light expanded clay aggregate
LED light-emitting diode
LEMA Lighting Equipment Manufacturers' Association
Len lens
lf lightface, light framing, lineal foot, linear foot, low frequency
lg large, length, long
Lg. large, length, long
LG liquid gas
Lge large
LGLCS landfill gas and leachate control system
lgp low ground pressure
lgr longer
lgs lengths
lgt lighting
lgth length
L&H light and heat
LH left hand, long-span, high strength bar joist, labor hours
LIC license
LIFO last in, first out
lin lineal, linear
lin ft linear foot, lineal feet

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

lino linoleum

liq liquid

LJ obsolete designation for long- span, standard-strength bar joist

lknt locknut

LL live load

L&L latch and lock

LL&B latch, lock, and bolt

LLD lamp lumen depreciation

LLRW low-level radioactive waste

lm lumen

LM lime mortar

lm/sf lumens per square foot

lm/W lumens per watt

Lm^3 loose cubic meter

lnd lined

lng, Lng lining

LNG liquefied natural gas

lnr liner

L&O lead and oil (paint)

LOA length overall

log logarithm

L-O-L lateralolet

log logarithm

lox liquid oxygen

LP liquid petroleum, low pressure

L&P lath and plaster

LPF low power factor

LPG liquid petroleum gas

l-pull line pull

LR living room, law reports, long radius

LS left side, loudspeaker, lump sum

LSA low specific activity

L/s liters per second

LT long ton, light

ltd limited

ltg lighting

Lt Ga light gauge

LTL less than truckload lot

Lt Wt lightweight

LUST leaking underground storage tank

LV low voltage

lvl level

LVL laminated veneer lumber

lvr louver

LW low water

LWC lightweight concrete

LWM low water mark

Definitions

label **1.** A projecting molding along the sides or top of a window. **2.** Manufacturer identification located on a product that contains the manufacturer's name, the product's performance characteristics, and any testing information by inspection agencies.

labeled door A door that carries a certified fire-rating issued by Underwriters' Laboratories, Inc. 3-hour fire doors (A) are used in walls separating buildings or dividing a single building into fire areas. 1½-hour (B and D) fire doors are used in openings in 2-hour rated vertical enclosures such as stairs, elevators, etc., or in exterior walls subject to severe fire exposure from outside the building. 1-hour fire doors are for use in openings in 1-hour rated vertical enclosures. ¾-hour fire doors (C and E) are for use in openings in corridor and room partitions or in exterior walls which are subject to moderate fire exposure from outside the building. ½-hour fire doors and ⅓-hour fire doors are used where smoke control is a primary consideration, and for the protection of openings between a habitable room and a corridor when the wall has a fire-resistance rating of not more than one hour.

labeled frame A door frame that conforms to standards and tests required by Underwriters' Laboratories, Inc., and has received its label of certification.

labeled window A fire-resistant window that conforms to the testing standards of Underwriters' Laboratories, Inc., and bears a label designating its fire rating.

labor Effort expended by people for wages or salary. Generally classified as either direct or indirect. Direct labor is applied to meeting project objectives and is a principal element used in costing, pricing, and profit determination; indirect labor is a component of indirect cost, such as overhead or general and administrative costs.*

labor and material payment bond (payment bond) A bond procured by a contractor from a surety as a guarantee to the owner that the labor and materials applied to the project will be paid for by the contractor. Those who have direct contacts with the contractor may be considered claimants.

labor burden Taxes and insurances the employer is required to pay by law based on labor payroll on behalf of or for the benefit of labor. (In the United States, these are federal old-age benefits, federal unemployment insurance tax, state unemployment tax, and workers' compensation.)*

labor cost Gross direct wages paid to the worker (bare labor).*

laborer Ordinarily denotes a construction worker who has no specific trade and whose function is to support the activity of the licensed trades.

labor hour A worker hour of effort, synonymous with work hour.*

labor productivity A measure of production output relative to labor input. In cost estimating, inverse measures such as work hours/quantity or unit hours are common (where lower values reflect higher productivity or efficiency). Labor productivity (or efficiency) is improved by increasing production for a given work hour or decreasing work hours for a given production.*

labor rate Labor cost expressed on a per unit of labor effort basis (e.g., labor costs/labor hour).*

labor union An organization or confederation of workers with the same or similar skills who are joined in a common cause (such as collective bargaining) with management or other employers for work place conditions, wage rates, and/or employee benefits.

laced corner A method of laying shingles at interior and exterior corners on sidewalls. The corner shingles of each course are laid alternately on the faces of the two walls in order to overlap each other and eliminate the need for corner boards.

laced valley On a roof, the interweaving of shingles or tiles where two planes meet at a downward angle.


laced valley

lacing A system of members used to connect the different elements of a composite column or girder in such a way that they structurally act in unison. Also refers to securing insulation materials via hooks or wire, etc.

ladder core A hollow structure of wood or insulation board used as the core of interior doors and built with strips running vertically or horizontally through the core area.

ladder jack scaffold A simple scaffolding system that uses ladders for support. The ladder jack is attached to the ladders to provide support for the staging plank.

ladder ties Long parallel reinforcing rods studded with cross rods so as to resemble a ladder. Used in masonry installations.

lag Time that an activity follows, or is delayed from the start or finish of its predecessor(s). Sometimes called an offset.*

lag bolt (coach screw, lag screw) A threaded screw or bolt with a square head.


lag bolt (coach screw, lag screw)

lagging **1.** Heavy wood boards used to line the sides of excavations and prevent cave-ins. **2.** Preformed insulation for pipes and tanks.

laitance In concrete, a weak, crumbly, and dusty surface layer caused by excessive water that has bled to the surface and subsequently weakened it. Overworking the surface during finishing can aggravate the problem. If laitance forms between pours, it must be brushed and washed away.

lally column A trade name for a pipe column from 3″ to 6″ in diameter, sometimes filled with concrete.

laminate **1.** To form a product or material by bonding together several layers or sheets with adhesive under pressure and sometimes with nails or bolts. **2.** Any material formed by such a method.


lally column

laminated beam (laminated veneer lumber) A straight or arched beam formed by built-up layers of wood. The method of lamination may be gluing under pressure, mechanical nailing or bolting, or a combination.


laminated beam (laminated veneer lumber)

laminated glass (safety glass, shatterproof glass) A shatter-resistant safety glass made up of two or more layers of sheet glass, plate glass, or float glass bonded to a transparent plastic sheet.


DEPENDING ON PVB AND GLASS LIGHT THICKNESS, LAMINATED GLASS CAN VARY FROM 1/4" TO 3/4" IN THICKNESS
POLYVINYL BUTYRAL (PVB) THICKNESS RANGES FROM 0.03" TO 0.09"
GLASS THICKNESS RANGES FROM 1/8" TO 3/8"
laminated glass (safety glass, shatterproof glass)

laminated wood (laminated veneer lumber) Any of several products formed by built-up layers (plies) of wood. Thin wood veneers may be laminated to a wood subsurface, several plies may be laminated together to form plywood, or thicker pieces may be used to form structural members such as beams or arches.

laminate floor A composite flooring product notable for its durability that is made of plastic resin and cellulose paper with a decorative finish layer. Its core material is a high-density fiberboard.

laminboard A compound board consisting of a core of small strips of wood glued together and covered by veneer faces.

lamp Any device that converts electric energy into light.

lamp depreciation The loss of luminous output in a lamp over time due to the accumulation of dirt on lamps, reflectors, and room walls and ceilings.

lamp life A rating that provides the life expectancy of a lamp. Obtained by testing a sample of lights and noting when 50% are no longer operating.

land-clearing rake A device outfitted with blades and attached to the front of a tractor to cut, collect, and remove brush from the site of proposed construction.

landfill An engineered disposal system characterized by the burial of waste material in alternating layers with an approved fill material.

landing An intermediate platform between flights of stairs, or the platform at the top or bottom of a staircase.

landing tread That board or portion of a stair landing that is closest to the next step down. The tread has an appearance and dimensions similar to the other treads, but it is actually part of the landing, and not a true tread.

land reclamation Gaining land from a submerged or partially submerged area by draining, filling, or a combination of these procedures.

Landrum-Griffin Act Enacted by Congress in 1959, this act requires labor union management to be subject to audit for the funds of union members for which they are responsible.


landing tread

landscape architect A person whose professional specialty is designing and developing gardens and landscapes, especially one who is duly licensed and qualified to perform in the landscape architectural trade.

landscaping The combined grounds work tasks that improve the appearance of a plot of land, including adding plantings and lawn, constructing walkways and patios, and regrading as necessary.

land survey *See* **boundary survey** *and* **survey**.

land surveyor A person (usually registered in the state where survey is being done) whose occupation is to establish the lengths and directions of existing boundary lines on landed property, or to establish any new boundaries resulting from division of a land parcel.

land treatment area A defined parcel of land on which wastes are deposited for the purpose of allowing natural cleansing actions to occur.

land-use analysis A systematic study of an area or region that documents existing conditions and patterns of use, identifies problem areas, and discusses future options and choices. A part of the general planning process, such an analysis might cover topics such as traffic flow, residential and commercial zoning, sewer services, water supply, solid-waste management, air and water pollution, or conservation areas. In short, any factors that could affect how particular areas of land should or should not be used.

lane striping The application of lines on pavement to define parking spaces, traffic lanes, etc.

lanyard A safety line tying a worker to a stable element of a structure to prevent a long fall in the event of an accident above ground level.

lap cement Asphalt used in roll roofing as an adhesive between the laps.

lap joint In construction, a type of joint in which two building elements are not butted up against each other, but are overlapped, with part of one covering part of the other. Typical examples include roof and wall shingles, clapboard siding, welded metal sheets or plates, and concrete reinforcing bars lapped together at their ends.


lap joint

lapped joint A lapped joint, like a van stone joint, is a type of pipe joint made using loose flanges on lengths of pipe. The ends of this pipe are lapped over to give a bearing surface for a gasket or metal-to-metal joint.

lapping **1.** The overlapping of reinforcing bars or welded wire fabric for continuity of stress in the reinforcing when a load is applied. **2.** The smoothing of a metal surface using a fine abrasive.



lapping

lap-riveted The riveting together of two metal members or plates where they have been deliberately overlapped, thus forming a lap joint.

lap seam The same as a lap joint, but typically used to refer to sheet metal, and sometimes plates, that are welded, soldered, or riveted at the overlapping joint.

lap siding Horizontal siding with each row covering part of the next, rather than butted up against each other.

lap splice In concrete construction, the simplest method for providing continuity of steel reinforcement. Ends of reinforcing bars are overlapped a specified number of diameters, usually no fewer than 30, and tied with wire.

lap weld pipe Pipe made by welding along a scarfed longitudinal seam in which one part is overlapped by another.

large quantity generator A classification of the Resource Conservation and Recovery Act (RCRA). One is considered a large quantity generator (LQG) for a particular month if 2,200 pounds or more of hazardous waste is generated, or more than 2.2 pounds of acute hazardous waste per calendar month.

larmier (corona, lorymer) A specific drip strip or molding that is part of a cornice. By projecting from the surrounding cornice, it catches rain and forces it to drip off away from the wall.

laser An acronym for light amplification by stimulated emission of radiation, a device that amplifies radiation in the visible or infrared parts of the spectrum.

laser level Surveying tool that employs a laser as a reference for measurements or verifying alignment.

laser level

last in, first out (LIFO) A method of accounting for inventory in which it is assumed that goods bought last are sold first. This allows automatic updating of inventory values.

late dates Calculated in the backward pass of time analysis, late dates are the latest dates on which an activity can start and finish without delaying a successor activity.*

latent defect A defect in materials or equipment that would not be revealed under reasonably careful observation. A patent defect, on the other hand, is one that may be discovered by reasonable observation.

lateral buckling The failure of any structural column, wall, or beam that has undergone excessive side-to-side (lateral) deflection, movement, or twist.

lateral sewer A sewer that discharges into another sewer or branch, but is engineered without any other common tributary to it.

lateral support Any bracing, temporary or permanent, that provides greater support in resisting side-to-side (lateral) forces and deflections. Floor and roof members typically provide lateral support for walls, columns, and beams. Vertical pilasters or secondary walls may also provide support.

lateral thrust Any force applied at a right angle to a member.

latest event occurrence time In the CPM (critical path method) of construction scheduling, the final deadline by which a particular item of work must be completed in order to avoid delaying the entire project.

latest finish date In the critical path method of scheduling, a completion deadline for a particular activity. Work performed after this deadline will result in project delay.



latest start date

latest start date In the critical path method of scheduling, the deadline for starting a particular activity. A late start will throw off the schedule and delay the project.

latex caulk A semisolid caulk containing water, ground calcium carbonate, plasticizers, mineral spirits, ethylene, glycol, surfactants, and pigments. Used to close joints or cracks between material.

latex paint A paint with a latex binder, usually a polymeric compound, characterized by its ability to be thinned or washed from applicators with water.

latex patching compound A compound used to fill voids, large gaps or penetrations in a floor, especially a subfloor before application of a floor covering.

lath Strips of wood or metal used as a base for plaster.

lathe A machine used to shape circular pieces of wood, metal, or other material. The stock is rotated on a horizontal axis while a stationary tool cuts away the unwanted material or creates ornamental turned work.

lath hammer A hammer used chiefly for cutting and nailing wood lath, designed with a nail-driving hammerhead, as well as a hatchet blade with a lateral nick that is used for pulling out nails.



lattice

lattice Typically, a diagonal network or grid of strips of material. Lattice is often used as ornamental screening, or to provide privacy.

lattice truss (lattice beam, lattice girder) A structural truss in which the web is a latticework of diagonal members.

lavas Natural stone used in building as a facing, veneer, and decoration. Pink, purple, and black are typical shades.



lavatory

lavatory **1.** A basin, with running water and drainage facilities, used for washing the face and hands. **2.** A room with a washbasin and a toilet, but no bathtub. **3.** A room containing a toilet.

lay A term used to define the direction of twist of the strands or wires in wire rope. The strands or wires have either a right-hand or left-hand lay.

lay-in Describes tile or panels that are installed into metal channels in suspended ceiling systems.

laying line (laying guide) Lines printed on felt or roll roofing as a guide for the amount of lap required.

laying out **1.** Marking of materials in preparation for work, showing where they are to be cut. **2.** Marking the location for the placement of building members.

layout A design scheme or plan showing the proposed arrangement of objects and spaces within and outside a structure.

lay-up **1.** The reinforcing material that is placed into position in the mold during the manufacturing of reinforced plastics. Also, the resin-impregnated reinforcement. **2.** The method or process of assembling veneers to manufacture plywood.

L-beam A beam whose section has the form of an inverted L, usually occurring in the edge of a floor, of which a part forms the top flange of the beam.

L-column The portion of a precast concrete frame composed of the column, the haunch, and part of the girder.

L/D ratio The relationship of the span (L) of a beam, column, slab, or truss to its depth (D).

leachate Liquid from rainfall, groundwater, or other sources that has percolated through a landfill mass and that contains biological and/or chemical wastes and dissolved or suspended materials. This waste is often hazardous and may need to be collected and treated to avoid groundwater contamination.

leaching The process of separating liquids from solid materials by allowing them to percolate into surrounding soil.

leaching well (leaching pit) A pit with porous walls that retain solids but permit liquids to pass through. It is not used to treat raw sewage but may be used to allow septic tank effluent to be absorbed into the surrounding soil.

lead **1.** (Pb) A soft, dense heavy metal easily formed and cut. Historically, lead was used for flashing and for the joints in stained glass windows. **2.** End sections of a masonry wall, usually at the corners, which are built up, in steps, before the main part of the wall is begun. Also, a string stretched between these end sections that serves as a guide for the rest of the wall. **3.** In electricity, conduction of electric current from the electric source to point of contact such as a welding lead. **4.** Time that an activity precedes the start of its successor(s). Lead is the opposite of lag.*

lead-based paint (LBPs) Toxic oil-based paint containing lead-based pigments often found on old buildings. Prohibited in residential construction by the federal government starting in 1978, as exposure poses a health hazard.

lead chromate One of a number of opaque pigments that range from orange to yellow in color and have strong tinting properties.

lead-covered cable (lead-sheathed cable) An electric cable protected from damage and excess moisture by a lead covering.

leaded light A window whose diamond-shaped or rectangular glass panes are set in lead frames called cames.

leader **1.** In a hot-air heating system, a duct that conveys hot air to an outlet. **2.** A downspout.

leader head That part of a drainpipe assembly that is placed at the top of a leader and serves as a catch basin to receive water from the gutter.

lead foil tape An acrylic, weather-resistant, highly malleable tape with good tack, bond and resistance to solvents and heat. Used as a moisture barrier, a maskant in electroplating and chemical milling, and in thermopane window sealing. Also used in alarm systems, with conductive tape attached to a window to detect breakage.

leading edge The vertical edge of a hinged swinging door or window that is opposite the hinged edge and in proximity to the knob or latch.



leading edge

lead joint A joint in a water pipe, such as a bell-and-spigot joint, into which molten lead is poured.

lead-lag ballast A ballast that serves to cut down on the stroboscopic effect of two fluorescent lamps, one of which is on a leading current and the other on a lagging current.

lead-lined door A door with lead sheets lining its internal core to prevent the penetration of x-ray radiation.

lead-lined frame A frame that is used with lead-lined doors and is itself lined internally with lead sheets to prevent penetration of x-ray radiation.

lead-lined sheetrock Sheetrock internally lined with sheet lead to provide protection from x-ray radiation.



lead-lined door

lead plug **1.** A cylinder of lead placed inside a hole in a masonry, plaster, or concrete wall. A screw or nail driven into it will then be firmly held in place. **2.** In stonemasonry, a piece of lead that holds adjacent stones together. Grooves are cut in both rock surfaces to be joined, and molten lead is poured into it.

lead roof A flat roof with a surface of sheet lead.

leads A collective term for short sections of electric conductors, generally insulated.

lead shield A lead sleeve used to provide anchorage for expansion bolts or screws. Similar to a *lead plug*.



lead shield

lead slate (copper slate, lead sleeve) A cylinder of sheet lead or sheet copper that surrounds a pipe at the point where it passes through a roof, ensuring a watertight intersection.

lead soaker A piece of lead sheeting that forms a weathertight joint at the intersection of a roof and of any vertical wall that passes through the roof at a hip or valley.

lead spitter The tapered part of a drainpipe assembly that connects a lead gutter with a downpipe.

lead tack **1.** A lead strip used to attach a lead pipe to some means of support. **2.** A lead strip placed along the edge of metal flashing. One side of the strip is attached to the structure, while the other side is folded over the free edge of the flashing.

leakage current Unwanted electric current that remains in a circuit or device. Can occur with improperly grounded electrical equipment. Leakage current can be observed by wire or semiconductor detectors.

lean construction Eliminating the waste associated with the delivery of construction projects.

lean mix (lean mixture) **1.** A mixture of concrete or mortar with a relatively low cement content. **2.** A plaster with too much aggregate and not enough cement, which thus renders it unworkable. **3.** A mixture of gasoline and oil in which the gasoline portion is on the high side in relation to the oil.

lean mortar A mortar with a low cement content, which makes it sticky, overly adherent to the trowel, and difficult to apply.

lean-to roof A roof with one pitch, supported at one end by a wall extending higher than the roof.

learning curve A term applied to the time required for a new craftsman or crew to attain the productivity level of an experienced craftsman or crew.

ledge **1.** A molding that projects from the exterior wall of a building. **2.** A piece of wood nailed across a number of boards to fasten them together. **3.** An unframed structural member used to stiffen a board or a number of boards or battens. **4.** Bedrock.

ledger **1.** A horizontal framework member that carries joists and is supported by upright posts or by hangers. **2.** A slab of stone laid flat, such as that over a grave. **3.** A horizontal scaffold member, positioned between upright posts, on which the scaffold planks rest.



ledger

ledger board **1.** One of multiple boards attached horizontally across a series of vertical supports, as in the construction of a fence. **2.** A ribbon strip.

ledger strip On a beam that carries joists flush with its upper edge, the strip of wood attached along the bottom edge of the beam that serves to seat the joists and to support them.

leech field A designated area of a lot where sewage is permitted to be filtered and discharged into. Leech fields are most commonly found in areas not accessible to a municipal sewer system.

LEED® Leadership in Energy and Environmental Design (LEED), a U.S. Green Building Council rating system for single-family, commercial, institutional, and high-rise residential buildings. Used to evaluate environmental performance from a "whole building" perspective over a building's life cycle.

left-hand stairway A stairway on which the handrail is positioned on the left-hand side in the direction of ascent.

left on the table The dollar difference between the low bid and the next bid above.

legal notice A covenant, often incorporated in the language of an agreement between two or more parties, that requires communication in writing, serving notice from one party to the other in accordance with terms of the agreement.

length The longest dimension of an object.

lessons learned A project team's learning, usually defined during close out. Should be limited to capturing/identifying work process improvements.*

let in In joinery, to fasten a timber securely in place by inserting or embedding it in another.

let-in brace A diagonal brace inserted or let in to a stud.



let-in brace

letter form of agreement (letter agreement) An agreement, in letter format, written by the sender, to be signed by the addressee, intended to be legally binding.

letter of credit Letter from a lender that promises to pay a beneficiary a specified sum of money for performance of a specific set of conditions, occasionally used in lieu of a payment bond.

letter of intent A letter that states the intent to enter into a formal agreement. Terms of the anticipated agreement may be stated in a general way.

level **1.** A term used to describe any horizontal surface that has all points at the same elevation and thus does not tilt or slope. **2.** In surveying, an instrument that measures heights from an established reference. **3.** A spirit level, consisting of small tubes of liquid with bubbles in each. The small tubes are positioned in a length of wood or metal that is handheld and, by observing the position of the bubbles, used to find and check level surfaces.

level A–D clothing The EPA's classification of personal protective equipment. Level A clothing offers the greatest amount of protection and should be worn whenever there is a risk to skin, eyes and the respiratory system. It utilizes an encapsulated chemical protective suit. Level D offers little protection and should only be worn on a site with no hazards.

level control Benchmarks or other devices used to identify points of known elevation on a project site.

leveling The procedure used in surveying to determine differences in elevation.



leveling plate

leveling plate A bearing plate set to an elevation used for setting structural steel.

leveling rod (leveling staff) A graduated straight rod used in construction with a leveling instrument to determine differences in elevation. The rod is marked in feet and fractions of feet, and may be fitted with a movable target or sighting disc.

leveling rule A long level used by plasterers to detect irregularities in the height of horizontal surfaces measured at various points.

level spreaders A stormwater management device installed parallel to a slope that changes concentrated flow to sheet flow.

leveraged buyout Any acquisition of a company where the buyer uses the company's internal assets and cash flows to provide the collateral for the loans required to make the acquisition.

lever arm In a structural member, the distance from the center of the tensile reinforcement to the center of action of the compression.

lever tumbler In a lock, a type of pivoted tumbler.

lewis (lifting pin) A metal device used to hoist heavy units of masonry. A lewis is equipped with a dovetailed tenon that is made in sections and fitted into a corresponding recess cut into the piece of masonry to be moved.

lewis bolt (lewis pin) **1.** A bolt shaped into a wedge at its end, which is inserted into a prepared hole in a heavy unit or stone and secured in place with poured concrete or melted lead. **2.** An eyebolt inserted into heavy stones and used in the manner of a lewis to lift and move the stones.



lewis bolt (lewis pin)

L-head The top of a shore formed with a braced horizontal member projecting from one side and forming an inverted L-shaped assembly.

liability A situation in which one party is legally obligated to assume responsibility for another party's loss or burden. Liability is created when the law recognizes two elements: the existence of an enforceable legal duty to be performed by one party for the benefit of another, and the failure to perform the duty in accordance with applicable legal standards.

liability insurance Insurance designed to safeguard the insured from liability resulting from injury to another person or another person's property.

license The permission by competent authority to do an act that, without such permission, would be illegal.

licensed contractor An individual or a firm that has, where required by law, obtained certification from a government office, to practice construction contracting.

lien A legal means of establishing or giving notice of a claim or an unsatisfied charge in the form of a debt, obligation, or duty. A lien is filed with government authorities against title to real property. Liens must be adjudicated or satisfied before title can be transferred.

life **1.** That period of time after which a machine or facility can no longer be repaired in order to perform its design function properly. **2.** The period of time that a machine or facility will satisfactorily perform its function without a major overhaul.*

life cycle A term often used to describe the period of time that a building can be expected to actively and adequately serve its intended function.

life-cycle assessment The determination of the environmental burdens associated with a product or process, including materials used and wastes released. The assessment considers the extraction and manufacturing of the materials, transportation and distribution, use and maintenance, and final disposal or reuse.

life-cycle costing The determination of the value of a system, such as roof covering, amortized over the projected life of the system, as opposed to the value determined by the initial cost only. Life-cycle costs include such costs as service and maintenance.

life safety code Developed by the NFPA Committee on Safety to Life, an international organization dedicated to saving lives from fire.

lift **1.** The concrete placed between two consecutive horizontal construction joints, usually consisting of several layers or courses, such as in slip forming. **2.** The amount of grout, mortar, or concrete placed in a single pour. **3.** A British term for elevator.

lifting block A combination of pulleys or sheaves that provide a mechanical advantage for lifting a heavy object.

lift joint A surface at which two successive concrete lifts meet.

lifts (tiers) The number of frames of scaffolding erected one above each other in a vertical direction.

lift slab A method of concrete construction in which floor and roof slabs are cast at ground level and hoisted into position by jacking. Also, a slab that is a component of such construction.



lift slab

light **1.** A man-made source of illumination, such as an electric light. **2.** A pane of glass.

light-framed construction Building construction that features vertical and horizontal structural components made up of wood or light-gauge steel framing.

lighting cost The total of the cost of a system's lamps, operating energy, and lamp replacement.



light

lighting outlet An electrical outlet that serves to accommodate the direct connection of a lighting fixture or of a lamp holder and its pendant cord.

lighting panel An electric panel housing fuses and circuit breakers, which serves to protect the branch circuits of lighting fixtures.

light loss factor In illumination calculations, an adjustment factor that estimates losses in light levels over time due to aging of the lamp, dirt on the room surfaces, and other causes. Losses corrected by lamp replacement or cleaning are termed recoverable. Nonrecoverable losses would be due to deterioration of the fixture or voltage drops.

lightning arrester A device that connects to and protects an electrical system from lightning and other voltage surges.

lightning conductor (lightning rod) A cable or rod built of metal that protects a building from lightning by providing a direct link to ground.

light pollution The glare from inefficient outdoor lights, especially around highly populated areas, making it difficult to discern the features of the night sky.

light shelves A daylighting system based on sun path geometry, used to bounce light off a ceiling, project light deeper into a space, distribute light from above, and diffuse it to produce a uniform light level below.

light to solar gain ratio (LSG) The ratio of visible light transmittance to the solar heat gain coefficient (SHGC). LSG measures the ability of glazing to provide light without excess solar heat gain.



light shelves

lightweight block A cement masonry unit manufactured using lightweight aggregate and often used to reduce the weight of partitions.

lightweight concrete Concrete of substantially lower unit weight than that made using gravel or crushed-stone aggregate.

light well An inside shaft with an open top through which light and air are conveyed from the outdoors to windows opening on the shaft.

lignin **1.** A substance that occurs naturally in wood and joins with cellulose to make up the chief constituents of wood tissue. **2.** A crystalline byproduct of paper pulp, used in manufacturing plastics, wood chipboard, and protective chemical coatings that prevent corrosion.

like-kind property In a 1031 exchange, property that is of the same nature.

lime Specifically, calcium oxide (CaO). Also, a general term for the various chemical and physical forms of quicklime, hydrated lime, and hydraulic hydrated lime.

lime-and-cement mortar A lime, cement, and sand mortar used in masonry and cement plaster. In addition to imparting a favorable consistency to the mix, the lime also increases the flexibility of the dried mix, thus limiting cracks and minimizing water penetration.

lime concrete A lime, sand, gravel, and concrete mix made without Portland cement. Lime concrete is found in older structures, but is no longer in general use.

lime putty A thick lime paste used in plastering, particularly for filling voids and repairing defects.

limestone A sedimentary rock composed mostly of calcium carbonate, calcium, or dolomite. Limestone can be used as a building stone, with its commercial grades being A. Statuary, B. Select, C. Standard, D. Rustic, E. Variegated, and F. Old Gothic. It is also crushed into aggregate, crushed for agricultural lime, or burned to produce lime.

limit control A safety device for a variety of mechanical systems that detects unsafe conditions, sounds an alarm, and shuts off the system.

limit design Any of a number of structural design methods based on limits related to stability, elasticity, fatigue, deformation, and other structural criteria.

limited combustible material A material that is noncombustible, as defined by the National Fire Protection Agency, yet fails to meet the NFPA's definition of combustible material. Must not exceed a potential heat value of 3500 Btu per pound.

limit of liability The greatest amount of money that an insurance company will pay in the event of damage, injury, or loss.

limit switch **1.** An electrical switch that controls a particular function in a machine, often independently of other machine functions. **2.** A safety device, such as a switch that automatically slows down and stops an elevator at or near the top or bottom terminal landing.

line A marked or defined limit or border.

lineal foot A straight-line measurement of one foot, as distinguished from a cubic foot volume or a square foot area.

linear diffuser An elongated diffuser with parallel slots with deflectors to divert airflow in various directions.

linear heat detector A cable-like component of a fire detection system that detects heat anywhere along its length.

linear measurement (long measure) A unit or system of units for measuring length: 12″ = 1′, 3′ = 1 yard, 1 yard = 0.9144 meters, 1 mile = 5,280′.

linear prestressing Prestressing as applied to linear structural members, such as beams, columns, etc.

line drilling In the blasting of rock, the boring of a series of holes along the desired line of breakage. Holes are spaced several inches apart to create a plane of weakness.

line drop A decrease in voltage caused by the resistance of conductors in an electric circuit.

line item Any item specifically called for on a plan or specification price-out sheet and listed with all of the quantities, unit prices, and extensions.

line level A spirit level used in excavation and pipe laying. Each end of the level has a hook used to hang it from a horizontal line.


line level

line of credit A fixed amount of credit granted to cover a series of transactions.

line of levels A series of differences in elevation as measured and recorded by surveyors.

line of sight (sight line) The line extending from a telescope or other long-distance sighting device, along which distant objects can be viewed.

line pipe A welded or seamless pipe typically used to convey gas, oil, or water.

lining Any sheet, plate, or layer of material attached directly to the inside face of formwork to improve or alter the surface texture and quality of the finished concrete.

lining panel A strip that secures the lower edges of sheet metal roofing sheets along the eaves of a roof.

lining paper A waterproof or water-resistant building paper placed under siding and roofing shingles.

link The circuit that connects two points.

linked switch A series of mechanically connected electrical switches designed to act simultaneously or sequentially.

link fuse A type of exposed fuse attached to electrically insulated supports.

linoleum A form of resilient floor covering that is manufactured of ground cork and oxidized linseed oil. Linoleum is applied to a coarse fabric backing and possesses a low resistance to staining, dents, and abrasion.

linseed oil A drying oil processed from flaxseed and used in many paints and varnishes.

lintel A horizontal supporting member, installed above an opening such as a window or a door, that serves to carry the weight of the wall above it.


lintel

lintel block (U-block) A special U-shaped concrete block used with other blocks to form a continuous-bond beam or lintel. Reinforcing steel is placed in the void followed by mortar or grout.


lintel block (U-block)

lintel course A course of stonemasonry set level to a lintel, but different from the rest of the wall by virtue of size or finish.

lip A rounded, overhanging edge or member.

liquefaction The sudden failure of a loose soil mass due to total loss of shearing resistance. Typical causes are shocks or strains that abruptly increase the water pressure between soil particles, causing the entire mass to behave similarly to a liquid.

liquid adsorption A natural process in which molecules of a liquid are physically attracted to and held at the surface of a solid.

liquid asphaltic material An asphaltic product too soft to be measured by a penetration test at normal temperatures. The material is principally used for cement surface treatments.

liquidated damages An amount, specified in a contract for construction, to cover damages incurred by the owner as a result of the contractor's failure to complete the work within the time frame set forth in the contract.

liquid indicator A device located in the liquid line of a refrigerating system and having a sight port through which flow may be observed for the presence of bubbles.

liquid limit The water content at which soil passes from the plastic to the liquid state under standard test conditions. The limit is expressed as a percentage of the dry weight of the soil.

liquid line In a refrigeration system, the pipe transporting refrigerant away from the condenser.

liquid membrane forming compound A material sprayed or rolled on a fresh concrete surface to restrict the loss of moisture from the concrete.

liquid petroleum gas (LPG) A general term referring to propane, butane, and other similar hydrocarbons stored as liquids and used as fuel.

liquid roofing Any of a number of different liquid or semiliquid roofing materials used to create a seamless waterproof membrane.

liquid volume measurement A measurement of grout on the basis of the total volume of solid and liquid constituents.

listed Refers to approved equipment or material that has been evaluated to meet appropriate testing and standards.

liter A metric measure of capacity equal to 61.022 cubic inches, or 2.113 American pints.

litigation The process by which parties submit their disputes to the jurisdiction and procedures of federal or state courts for resolution.

litmus A piece of test paper containing a chemical indicator that changes color when exposed to liquids. Litmus paper is used to determine acidity or alkalinity values expressed as pH variations.

live **1.** Descriptive of a wire or cable connected to a voltage source. **2.** A descriptive term for a room with a very low level of sound absorption.

live load The load superimposed on structural components by the use and occupancy of the building, not including the wind load, earthquake load, or dead load.

live part Any part or component of an electrical device or system that is engineered to function at a voltage level different from that of the earth.

live steam Steam that has not condensed and still retains its energy, such as steam issuing from a boiler or radiator.

load **1.** The force, or combination of forces, that act upon a structural system or individual member. **2.** The electrical power delivered to any device or piece of electrical equipment. **3.** The placing of explosives in a hole.

load-bearing tile A form of tile used in masonry walls that is capable of supporting loads superimposed on the wall structure.

load-bearing wall A wall specifically designed and built to support an imposed load in addition to its own weight.



load-bearing wall

load binder A device used to tighten chains that are holding loads in place on a truck bed.

loader A construction machine used to push or transport earth, crushed stone, or other construction materials. The bucket, or scoop, is located on the front of the vehicle and can be raised, lowered, or tilted.



loader

load factor **1.** In structural design, the factor applied to the working load to determine the design's ultimate load. **2.** In a drainage system, the percentage of the total flow that occurs at a particular location in the system. **3.** A ratio of the average air-conditioning load on a system to the maximum capacity.

loading dock leveler Typically, an adjustable mechanized platform built into the edge of a loading dock. The platform can be raised, lowered, or tilted to accommodate the handling of goods or material to or from trucks.

loading dock seal A flexible pad installed around the door of a loading dock to form a tight seal between the receiving doors and the opening of a truck that is backed into the dock.

loading platform (loading dock) A platform adjoining the shipping and receiving door of a building, usually built to the same height as the floor of the trucks or railway cars on which shipments are delivered to and from the dock.

loading ramp A fixed or adjustable inclined surface that adjoins a loading platform and is installed to ease the conveyance of goods between the platform and the trucks or railway cars that transport goods.

loam Soil consisting primarily of sand, clay, silt, and organic matter.

local area network (LAN) A type of distance-limited communications network used for data transfer, text, facsimile, and video applications.

local buckling In structures, the failure of a single compression member. The local failure may cause the failure of the whole structural member.

location factor An instantaneous overall total project factor for translating the summation of all project cost elements of a defined construction project scope of work, from one geographical location to another. Location factors include given costs, freights, duties, taxes, field indirects, project administration, and engineering and design. Location factors do not include the cost of land, scope/design differences for local codes and conditions, and the cost for various operating philosophies.*

location survey The establishment of the position of points and lines on an area of ground, based on information taken from deeds, maps, and documents of record, as well as from computation and graphic processes.



location survey

lock corner A corner held together by interlocking construction of adjacent members, such as the dovetail joint on the front panel of a drawer.

lock face The surface of a mortise lock, which remains visible in the edge of a door when the lock is installed.

locking device In scaffolding, a device used to secure a cross brace to the frame or panel.

locking pliers Pliers with clamping jaws that can be tightened with a screw attachment on one handle.

lock keeper The box on a doorjamb that accommodates the extending bolt on a lock.

locknut **1.** A special nut that locks when tightened so that it will not come loose. **2.** A second nut used to prevent a primary nut from loosening.

lock rail On a door, the horizontal structural member situated between the vertical stiles at the same height as the lock.



lock rail

lock reinforcement A metal plate installed inside the lock stile or lock edge of a door and designed to receive a lock.

locksaw A saw used for cutting the seats for locks in doors. The saw is designed with a tapering blade that can be flexibly maneuvered.

lock seam (lock joint) In sheet metal roofing, a joint or seam formed by bending the two adjoining edges over in the form of hooks, which are interlocked. The hooks are then pressed down tightly to form a seam.

lockset A complete system including all the mechanical parts and accessories of a lock, such as knobs, reinforcing plates, and protective escutcheons.

lock stile (closing stile, locking stile, striking stile) On a door or a casement sash, the vertical member that closes against the jamb of the frame that surrounds it. The stile is located on the side away from the hinges.

lock-strip gasket (structural gasket) Typically, a thick and stiff black neoprene glazing gasket that holds and attaches panes of glass to each other or to the surrounding structure. During installation the gasket is tightened by the insertion of a wedge-like strip (the lock-strip) along the entire length of the gasket.



lock-strip gasket (structural gasket)

lock washer A circular washer with a break that helps it keep a nut tightly in position.

lock washer

locus A small map included on a site plan that shows the general location of a project with respect to local highways, roads, and recognized landmarks.

loess Silty material that is deposited by the wind, but maintains significant cohesion due to the presence of clay or other cementitious materials.

loft **1.** Space beneath a roof of a building, most commonly used for storage of goods. **2.** In a barn, the upper space at or near the ceiling with an elevated platform on which hay and grains are stored. **3.** The upper space in a church or auditorium, sometimes enclosed and cantilevered, which accommodates a pipe organ or area for a choir. **4.** The space between the grid and the upper part of the proscenium in a theater stagehouse. **5.** Within a loft building, the unpartitioned upper spaces visible from the floor immediately below.

logic panel Any electronic control panel that is designed to perform a specific control sequence.

log mean Refers to the value of insulation thickness for curved piping in order to produce the same resistance to heat flow as a straight, flat area.

long column In structural design, a column of sufficient slenderness to necessitate a reduction of its load-bearing capacity.

long float A concrete finishing float designed to be handled by two men.

long header A header that runs a wall's full depth.

longitudinal bond In masonry, a bond in which a number of courses are laid only with stretchers and used principally for thick walls.

longitudinal bracing Bracing that extends lengthwise or runs parallel to the center line of a structure.

longitudinal joint Any joint parallel to the long dimension of a structure or pavement.

longitudinal reinforcement Steel reinforcement placed parallel to the long axis of a concrete member.


longitudinal reinforcement

long lead items Those components of a system or piece of equipment for which the times to design and fabricate are the longest and for which an early commitment of funds may be desirable or necessary in order to meet the earliest possible date of system completion.*

long-life lamp An incandescent lamp that has a lower luminous output than standard lamps of equal wattage, but a longer design life than the value set for lamps of its general class.

long-radius elbow In plumbing, a pipe elbow with a larger radius than is standard. The elbow is designed to mitigate losses from friction and to facilitate the flow of liquids through the pipe.


long-radius elbow

long screw A nipple, usually measuring 6″ long, with one thread that is longer than average.

long span The distance between supports in a structure, usually spanned by a truss or heavy timber.


long span

long span lintel A lintel used in light-gauge metal stud framing that has a steel channel for extra support over an opening.

long span steel joist A structural framing joist that provides large open areas within a building. It is usually a very deep beam due to the nature of the building system.

long span structure A building that uses long span roof joist systems in its design to create large unobstructed areas within the structure, e.g., a domed stadium.

long ton A unit of weight equal to 2,240 pounds (1,016 kilograms).

lookout A short wooden brace or block that supports an overhanging portion of a roof.

loop Sometimes called a local line or subscriber loop, the local circuit between a subscriber station and the exchange.

looping in In interior electrical wiring, the connection of an outlet by two conductor cables, one to and one from the outlet. Splices (junction boxes) are thus avoided, but more wire is used.

loop vent In plumbing, a venting configuration for multiple fixtures, as in a public restroom. The vent pipe is connected to the waste branch in only two places, before the first and last fixtures. The fixtures are not individually vented. The two vents are connected together in a loop, and the loop is then connected to the vent stack.

loose cubic yard (meter) A unit of measure with which to express the volume of loose soil, rock, or blasted earth material.

loose-fill insulation Any of several thermal insulation materials in the form of granules, fibers, or other types of pieces that can be poured, pumped, or placed by hand.

loose knot A knot on a piece of lumber that is not fixed firmly and is likely to fall out.

loose lintel A lintel that is placed across a wall opening during construction to support the weight of the wall above, but which is not attached to another structural member.

loose material Soil, rock, or earth materials in loose form, whether blasted or broken by artificial or natural means.


loose-pin hinge

loose-pin hinge A hinge, usually for a door, that can be separated by the removal of a vertical pin.

loose yards A term defining the cubic measurement of earth or blasted rock after excavation, as when loaded on a truck. Equal to a volume of 27 cubic feet.

Los Angeles Abrasion Test A test for abrasion resistance on concrete aggregates.

loss of prestress In prestressed concrete, the reduction in prestressing force that results from the combined effects of strain in the concrete and steel, including slip at anchorage, relaxation of steel stress, frictional loss due to curvature in the tendons, and the effects of elastic shortening, creep, and shrinkage of the concrete.

loss on ignition The percentage loss in weight of an ignited sample to constant weight at a specified temperature, usually 900°C to 1,000°C.

lot A parcel of land that is established by a survey or delineated on a recorded plot.

lot line The limit or boundary of a land parcel.

louver A framed opening in a wall, fitted with fixed or movable slanted slats. Though commonly used in doors and windows, louvers are especially useful in ventilating systems at air intake and exhaust locations.


louver

louver board (luffer board) One of multiple narrow boards or slats on a louver door, window, or ventilator. The boards are installed at an angle.



louver door

louver door A door or louver, usually assembled with its blades in a horizontal position, which allows air to pass through the door when it is closed.

low-alkali cement A cement containing smaller-than-usual amounts of sodium and/or potassium. Its use is necessary with certain types of aggregate that would otherwise react with high levels of alkali.

low-alloy steel Steel composed of less than 8% alloy.



low bed (low boy)

low bed (low boy) A flatbed trailer used to carry heavy equipment.

low bid In bidding for construction work, the lowest price submitted for performance of the work in accordance with the plans and specifications.

low-carbon steel (mild steel) Steel with less than 0.20% carbon. This type of steel is not used for structural members, due to its ductility. It is good for boilers, tanks, and objects that must be formed.

low-density concrete Any concrete with a unit weight lower than 50 pounds per cubic foot.

low-density polyethylene (LDPE) A widely used thermoplastic that is inexpensive and easy to process. Low-density polyethylene is the softest and most flexible version of this material, and is commonly used in packaging and injection molding.

low emissivity glass (low e glass) Insulating glass with a coating or special component that keeps heat in during winter and out during summer. Low e glass reflects internal long-wave radiation, as that from a heat source, back into a home while keeping the short-wave radiation of the sun out.

lowest responsible bidder (lowest qualified bidder) The bidder who has submitted the lowest legitimate bid. The owner and architect must agree that this person (or firm) is capable of performing the work covered by the bid proposal.

lowest responsive bid The lowest bid that meets the requirements set forth in the bid proposal.

low-flow toilet An economically and environmentally efficient toilet that uses less water per flush than a conventional model.

low-hazard contents Building contents with such an exceptionally low level of combustibility that they are unable to propagate or sustain a fire in and of themselves.

low-heat cement (type IV cement) A special cement that minimizes the amount and rate of heat generation during hydration (setting). Strength is also achieved at a slower rate. Use is limited to structures involving large masses of concrete, such as dams, where the heat generated would be excessive if normal cement were used.

low-iron glass Glass with a low iron content that has a higher visible transmittance and thus a greater ability to collect solar energy.

low-lift grouting The common and simple method of unifying concrete masonry, in which the wall sections are built to a height of not more than 4′ (1.2 meters) before the cells of the masonry units are filled with grout.

low-pressure mercury lamp A mercury-vapor lamp, including germicidal and fluorescent lamps, whose partial pressure during operation is no more than 0.001 atmosphere.

low-pressure sodium lamp A lamp that produces light via radiation from sodium vapor. Because it renders most colors gray, it is considered a monochromatic light source.

low steel A characteristically soft steel that contains less than 0.25% carbon.

low-temperature supply air Supply air below 50°F.

low VOC Building materials and finishes that exhibit low levels of off-gassing, the process by which volatile organic compounds (VOCs) are released from the material, impacting health and comfort indoors and producing smog outdoors. Low (or zero) VOC is an attribute to look for in an environmentally preferable building material or finish.

low-voltage lamp A lamp, typically compact halogen, that operates at 12V and requires a transformer. Popular lamps include MR11, MR16, and PAR36.

low-voltage lighting control A remote-control system that controls a number of lighting circuits. Lights are turned on or off automatically by electronic controls located within the low-voltage lighting control panel.

L runner The fastener used at the base of solid gypsum lath.

lubricant A substance used to minimize friction between two areas.

luffing boom (live boom) A crane boom with the ability to move vertically while slewing 360 degrees.

lug **1.** Any of several types of projections on a piece of material or equipment. Such projections are used during handling and installation. **2.** A connector for fastening the end of a wire to a terminal.

lug bolt A bolt with a flat iron bar welded to it.

lumber Timbers that have been split or processed into boards, beams, planks, or other stock that is to be used in construction and is generally smaller than heavy timber.



lumber core (stave core)

lumber core (stave core) Wood door core made up of narrow strips of lumber glued together at the edges and commonly held together by a veneer, which is glued to both faces with its grain at 90° to that of the core wood.

lumber, matched Lumber whose side or end edges are cut to form tongue-and-groove joints that fit together when laid side by side or end to end.

lumen A unit of luminous flux that defines the quantity of light.

lumen-hour A measurement of light equal to one lumen for one hour.

lumen method A simple way to calculate the luminaires required to achieve a desired lighting intensity for an area.

luminaire A lighting fixture, with or without the lamps in it.

luminaire efficiency In lighting calculations, a special ratio of the light emitted by a light fixture to the light emitted by the lamps inside the fixture.

luminaire shielding Any device such as a louver, lens, or baffle that controls or directs light from a lamp.

luminous ceiling An area lighting system, mounted on a ceiling, that has a surface of light-transmitting materials with light sources installed above it.

luminous paint A phosphorescent or fluorescent paint that glows in the dark after exposure to direct light. Has many safety applications, including use on light switch plates, exit signs, stair edges, and fuse boxes.

lump sum An item or category priced as a whole rather than broken down into its elements.

lute **1.** A long-handled scraper used to level asphalt or wet concrete. **2.** A straightedge used to strike off clay from a brick mold.



lute

lux A measure of illumination striking a surface. One lux is equal to one lumen per square meter.

M

Abbreviations

m meter

M thousand, bending moment (on drawings)

M&V measurement (or monitoring) and verification

ma milliampere

MA mechanical advantage, mixed air

MAC media access control; message authentication code; moves, adds and changes

mach machine, machinist

mag magazine, magneto

MAN manual, metropolitan area network

manuf manufacture

mas masonry

MAT mixed air temperature

mat, matl material

max maximum

mb millibar

MBF 1,000 board feet

MBH 1,000 Btus per hour

MBM, mbm thousand feet board measure

MBMA Metal Building Manufacturer's Association

MC moisture content, metal-clad, mail chute

MDF medium-density fiberboard

MDO medium-density overlay

me marbled edges

ME mechanical engineer

meas measure

mech mechanic, mechanical

med medium

memb member

MEMS micro-electro-mechanical systems

mep mean effective pressure

MEP mechanical, electrical, plumbing

MER mechanical equipment room

MERV minimum efficiency reporting value

met metallurgy

mezz mezzanine

mf mill finish

MF04 MasterFormat 2004

mfg manufactured

Mg magnesium

MG motor generator, mixed grain

mgt management

MH manhole

MHW mean high water

mi mile

mid middle

min minimum, minor, minute

MIS Management Information System

misc miscellaneous

mix, mixt mixture

mks meter-kilogram-second

ml, ML material list

mldg, MLDG molding

MLS multiple listing service

MLW mean low water

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

MMF magnetomotive force

Mn manganese

MN magnetic North, main

Mo molybdenum

MO month

mod, modif modification

MOD model

MOE modulus of elasticity

MOL maximum overall length

MOT motor

MOU memorandum of understanding

mp melting point

mpg miles per gallon

mph miles per hour

MPOE minimum point of entry

MPS master production schedule, materials and resources

mr moisture-resistant

MRL machine room-less (elevator systems)

MRO maintenance, repair and operations

MRP manufacturing resource planning, materials resource planning

MRT mean radiant temperature

MSDS Material Safety Data Sheet

MSF per 1,000 square feet

MSG Model Support Group of the International Alliance for Interoperability

msl mean sea level

MSR machine stress rated

MTBF mean time between (system or device) failures

mtg, mtge mortgage

MTTR mean time to restore or repair (a system or device)

mult multiple, multiplier

mun, munic municipal

MUTOA multiuser telecommunications outlet assembly

mxd mixed (lumber industry)

Definitions

macadam A method of paving in which layers of uniformly graded, coarse aggregate are spread and compacted to a desired grade. Next, the voids are completely filled by a finer aggregate, sometimes assisted by water (water-bound), and sometimes assisted by liquid asphalt (asphalt-bound). The top layers are usually bound and sealed by some specified asphaltic treatment.

machine bolt A threaded straight bolt usually specified by gauge, thread, and head type.



machine bolt

machine burn Any darkening or burning of a material during milling or other machining.

machined A term used to describe a smooth finish on a metal surface.

machine excavation Digging or scooping performed by a machine, as opposed to that performed by hand.



machine excavation

machine finish A finish on a stone surface produced by a smooth-edged planer.

machine rating A standard describing the power that an electric motor is designed to produce.

machine room-less elevator systems Elevators that do not require an area to house equipment.

machine stress-rated lumber Lumber that is rated mechanically by a machine that evaluates its structural properties.

made ground Land or ground created by filling in a low area with rubbish or other fill material. Often, such created land is not suitable for building without the use of a pile foundation.

magnesia Finely processed magnesium oxide.

magnesite flooring A finished surface material consisting of magnesium oxide, sawdust, and sand combined in various proportions, and subsequently applied to integral concrete floors.

magnesium A lightweight silver-colored metal that is highly flammable and immune to alkalies and is usually used in an alloy. A scale-forming element found in some boiler feed water.

magnesium float A hand tool with a flat magnesium base used to finish concrete flatwork.



magnesium float

magnetic bearing The horizontal angle from magnetic north for a given survey line.

magnetic catch A door catch that uses a magnet to hold it in the closed position.

magnetic overload relay An overcurrent protection switch or fuse.

magnetic switch An electric switch using an electromagnet for operation.

magnetite A naturally occurring, black iron oxide used as an iron ore and as a high-density aggregate in concrete.

mahogany A straight-grained, medium-density wood originating in the West Indies, Central America, and South America, and used principally in interior plywoods and cabinetry.

mail slot A slot in a wall or door for receiving incoming mail. The slot usually has a cover to prevent draft.

main **1.** In electricity, the circuit that feeds all subcircuits. **2.** In plumbing, the principal supply pipe that feeds all branches. **3.** In HVAC, the main duct that feeds or collects air from the branches.

main bar (main reinforcement) A reinforcing bar in a concrete member designed to resist stresses from loads and moments, as opposed to those designed to resist secondary stresses.

main beam A structural beam that transmits its load directly to columns, rather than to another beam.



main beam

main cross-connect The connecting point (in a structured cabling system) between entrance cables, equipment cables, and inter-building backbone cables.

main couple The main truss in a timber roof.

main office expense A contractor's main office expense consists of the expense of doing business that is not charged directly to the job. Depending on the accounting system used, and the total volume, this can vary from 2% to 20%, with the median about 7.2 percent of the total volume.

main rafter A structural roofing member that extends from the plate to the ridge pole at right angles.

main runner In a suspended ceiling system, one of the main supporting members.



main runner

main sewer In a public sanitary sewer system, the trunk sewer into which branch sewers are connected.

main stack In plumbing, a vent that runs from the building drains up through the roof.

maintenance The process of implementing measures to conserve a site, building, structure, or object over an extended period of time to prevent deterioration.

maintenance bond A contractor's bond in which a surety guarantees to the owner that defects of workmanship and materials will be rectified for a given period of time. A one-year bond is commonly included in the performance bond.

maintenance curve For a light source, a plot of lumens vs. time.

maintenance factor In lighting calculations, the ratio of illumination of a light source or lighted surface at a given time to that of the initial illumination. This factor is used to determine the depreciation of a lamp or a reflective surface over a period of time.

main tie In a roof truss, the bottom straight member that connects the two feet.



main tie

makeup air unit A unit to supply conditioned air to a building to replace air that has been removed by an exhaust system or by combustion.

makeup water Water that is added to a system to replace water that has been lost through evaporation or leaking.

male connector An electrical connector with contacts that fit into a female connector.

male nipple A short length of pipe with threads on the outside of both ends.

male plug An electrical plug that inserts into a receptacle.

male thread A thread on the outside of a pipe or fitting.



male thread

malleability The property of a metal that enables it to be hammered, bent, and extruded without cracking.

malleable iron Cast iron that has been heat-treated to reduce its brittleness.

mallet A small wooden hammer used to drive another tool, such as a chisel or a gouge.

management host computer A computer that serves as a management-machine interface in a building automation system.

mandrel A retractable insert for driving a steel pile.

manganese An alloy that is added to most steels as a hardener and deoxidizer.

manhole A vertical access shaft from the ground surface to a sewer or underground utilities, usually at a junction, to allow cleaning, inspection, connections, and repairs.

manhole cover A removable cast iron cover for a manhole. As many manholes are in paved areas, the cover must be strong enough to bear the weight of traffic.


STANDARD MANHOLE FRAME AND COVER
2'-0" - 4'-0" DIAMETER, MIN.
FINISH GRADE
GASKETED JOINTS REQUIRED IN SANITARY MANHOLES
FLEXIBLE JOINT FOR SANITARY PIPE CONNECTIONS
SLOPE DOWN
VARIES
4"
2'-8"
8"
4'-0" - 6'-0" DIAMETER, MIN.
PRECAST CONCRETE 5" MIN. THICKNESS
METAL MANHOLE STEPS
CONCRETE FOOTING ON COMPACTED SUBGRADE
CONCRETE BENCH, SHAPED TO PROVIDE POSITIVE DRAINAGE
00975

manhole

manhole frame The cast iron frame into which a manhole cover fits.

manhole invert In a sewer manhole, the elevation or grade of the inlet or outlet pipes.

manhole step A preformed metal or fiberglass step that is permanently fixed to the inside of a manhole or catch basin.

manifest 1. A list of the contents or the cargo of any shipment. **2.** A specific form used by a generator of hazardous waste to track the waste from the site of generation to the site of final treatment or disposal.

manifold A distribution or collection pipe or chamber having one inlet and several outlets, or one outlet and several inlets.



manifold

man lift A motorized scaffold characterized by a bucket or platform. Motorized buckets, also known as "cherry pickers," can hold up to three people. Motorized platform capacity is limited only by weight.

man lock A chamber in which personnel pass from one environmental pressure to another, such as when entering or leaving a caisson.

manometer A U-shaped tube filled with a liquid used to measure the differential pressure of gasses.



mansard roof

mansard roof A roof with a double pitch on all four sides, the lower level having the steeper pitch. *See also* **curb roof.**

mantel (mantelpiece) The shelf above and the finished trim or facing around a fireplace.



mantel (mantelpiece)

manual A system of controls that can be operated by hand.

manual batcher A batcher with gates and scales that can be operated by hand.

manual fire alarm box A device that initiates an alarm signal when activated by hand.

manual fire pump A pump for water supply to a sprinkler or standpipe system that must be activated by hand.

manufactured homes (mobile homes) Manufactured homes are factory-finished inside and out, and usually have wheeled chassis.

manufactured sand A fine aggregate that is produced by crushing stone, gravel, or slag.

manufactured wood A joist, truss, beam, or other product made from smaller pieces of wood, usually glued together. Manufactured wood can provide greater strength and has the environmental benefit of using waste material rather than virgin lumber.

manufacturer's specifications Documented installation or maintenance instructions produced by a product manufacturer. Often these instructions must be carefully followed in order to maintain a product warranty.

maple A hardwood that grows in North America and Europe and has a dense uniform texture. Maple is used primarily in flooring and furniture.

marble A metamorphic rock, chiefly calcium carbonate, with various impurities that give it distinctive colors. Marble is used in the architectural facing of both interior and exterior walls.

margin **1.** The amount added to the cost of materials as a markup. **2.** An edge projecting over the gable of a roof. **3.** The space between a door and the jambs. **4.** The measurement of the exposure of overlapped shingles.

marginal bar A glazing bar that separates a large glazed area in the middle of a window from smaller panes around the outside.

margin draft In stonemasonry, a dressed border on the edge of the face of a hewn stone.

margin strip In wood flooring, a narrow strip that forms a border.

margin trowel A plasterer's hand trowel on which the edges are turned up to finish plaster in corners.

marine glue A waterproof glue used on exterior plywoods and other wood-gluing applications where water may be encountered.

marine paint A paint containing elements to withstand exposure to sunlight, salt, and fresh water.

marine plywood A high-grade plywood especially adaptable to boat hull construction. All inner plies must be B grade or better.

marked face The front or veneer side of a wood building product.

market value The monetary price upon which a willing buyer and a willing seller in a free market will agree to exchange ownership, both parties knowing all the material facts but neither being compelled to act. The market value fluctuates with the degree of willingness of the buyer and seller and with the conditions of the sale.*

marking gauge A carpenter's hand tool for scribing a line parallel to an edge. The gauge has a scribe on a rod whose distance is adjustable at the head, and rides along the edge of the material.

mark out To lay out the locations where cuts are to be made on lumber.

markup A percentage of other sums that may be added to the total of all direct costs to determine a final price or contract sum. In construction practice, the markup usually represents two factors important to the contractor. The first factor may be the estimated cost of indirect expense often referred to as *general overhead.* The second factor is an amount for the anticipated profit for the contractor.

marl A silty clay, found in the bottom of lake beds or swamps, with a high percentage of calcium carbonate.

marquee A canopy extending out from an entrance for protection from the weather.

marquetry Mosaics of inlaid wood and sometimes ivory and mother of pearl.

Martin's cement Similar to Keene's cement and used in plaster. This type of cement contains potassium carbonate as an additive in place of the alum used in Keene's cement.

mash hammer A heavy, short-handled mason's hammer with two striking faces. Used with a chisel to remove old mortar between bricks in preparation for repointing. This term is also used regionally as another name for a sledgehammer.

masking The temporary covering of areas adjacent to those to which paint is to be applied. Masking is applied either by sticking something on, as with masking tape, or by covering with a firm mask.

masking tape An adhesive-backed tape used for masking that comes in rolls and various widths. The tape is applied to the surface that is to be left unpainted and removed after the painting has been done, leaving a clean, straight line.

mason A workman skilled in the trade of masonry and/or the finishing of concrete floors.

masonry Construction composed of shaped or molded units, usually small enough to be handled by one man and composed of stone, ceramic brick, or tile, concrete, glass, adobe, or the like. The term *masonry* is sometimes used to designate *cast-in-place concrete*.


masonry

masonry anchor A metal device attached to a door or window frame that is used to secure it to masonry construction.

masonry bonded hollow wall A hollow masonry wall in which the inner and outer wythes (thicknesses) are tied together with masonry units rather than metal ties.

masonry cement A mill-mixed mortar to which sand and water must be added.

masonry fill Insulation material used to fill the voids in masonry units.

masonry filler unit Masonry units that are placed between joists or beams prior to placing the concrete for a concrete slab. The filler unit is used to reduce the amount of concrete required and the weight of the slab.

masonry insulation Sound and thermal insulation used in masonry walls. The material can be either rigid insulation, or an expanded aggregate such as perlite.

masonry nail A hard steel nail with a fluted shank that can be driven into masonry or concrete.

masonry panel A prefabricated masonry wall section that is constructed on the ground or in a shop and erected by crane.

masonry pointing Troweling mortar into a masonry joint after the masonry units have been laid.

masonry reinforcing Refers to both the lateral steel rods or mesh laid between the courses of masonry units and the vertical rods that are grouted into the voids.


masonry reinforcing

masonry toothing Cutting or leaving out of alternate masonry units in a wall to provide a bond for new work.

masonry unit Natural or manufactured building units of burned clay, stone, glass, gypsum, concrete, etc.


masonry unit

masonry veneer A single wythe of masonry for facing purposes.

mason's hammer A steel hammer having one square face for striking and one curved chisel face for trimming masonry units.

mason's level Three separate levels set in a straight bar of wood or metal for determining level or plumb lines. The level is usually about 4′ long.

mason's lime Lime used in preparing plaster or mortar.

mason's line A heavy string or cord used by masons to align courses of masonry.

mason's measure A method of making a quantity survey of masonry units required for a job that counts corners twice and does not deduct for small openings.

mason's miter A corner formed out of a solid masonry unit, the inside of which looks like a miter joint. The joints are actually butt joints away from the corner.

mason's putty A lime-based putty mixed with Portland cement and stone dust, and used in ashlar masonry construction.

mason's scaffold A self-supporting scaffold for the erection of a masonry wall. The scaffold must be strong enough to support the weight of the masons, the masonry units, and the mortar tubs during construction.


mason's scaffold

mass Property of a body that resists acceleration and produces the effect of inertia. The weight of a body is the result of the pull of gravity on its mass.

mass diagram A plotted diagram of the cumulative cuts and fills at any station in a highway job. The diagram is used in highway design and to determine haul distances and quantities.

mass haul curve A curve developed from the mass diagram to display haul distances and quantities in a highway job.

mass profile A road profile graphically showing volumes of cut and fill between stations.

mass shooting The simultaneous detonation of explosives in blast holes, as opposed to detonation in sequence with delay caps.

mast The vertical member of a tower crane that carries the load lines.

mast arm The bracket attached to an exterior lamppost that supports a light.


mast arm

master A term applied to the third and highest level of achievement for a tradesman or mechanic, who by supervision, experience, and examination has earned a master's license attesting that he is a master of the trade and no longer requires supervision of his work, as is the case with the journeyman and apprentice levels.

Master Builder A term applied to one who performs the functions of both design and construction. The Master Builder approach to building construction has been a practice commonplace in much of the world for many centuries. In the United States, design and construction are traditionally seen as two separate and distinct functions.

master clock system An electrical system that synchronizes all the clocks in a building.

MasterFormat The name owned and created by the Construction Specifications Institute (CSI) of the United States and

c13.indd 194 06/09/12 9:01 AM

Construction Specifications Canada (CSC) denoting a numerical system of organization for construction-related information and data, based on a 16-division format.

master key A key that operates all the locks in a master-keyed series.

master-keyed lock A locking system intended for use in a series, each lock of which may be actuated by two different keys, one capable of operating every lock of the series, and the other capable of operating only one or a few of the locks.

master plan A zoning plan of a community classifying areas by use, or zoning code used as a guide for future development.

master plumber A plumber licensed to install and assume responsibility for contractual agreements pertaining to plumbing, and to secure needed permits. A journeyman plumber is licensed to install plumbing only under the supervision of a master plumber.

master schedule The most complete schedule for a project, it covers not only the construction portions, but also items that are not strictly construction-related, such as financing deadlines and community board reviews. The master schedule includes all of the details of the project, but can be presented in a summary or executive-level format, with the ability to "drill down" into specific parts to get more detailed information, as needed.

MASTERSPEC® A widely used master specification system, developed by the American Institute of Architects, for design professionals and members of the construction and building industries.

master switch An electrical switch that controls two or more circuits.

mastic **1.** A thick bituminous-based adhesive used for applying floor and wall tiles. **2.** A waterproof caulking compound used in roofing that retains some elasticity after setting.

mat **1.** A heavy, flexible cover for retaining blasted rock fragments that is usually made of wire, chain, or cordage. **2.** A grid of reinforcing bars.

matched boards Boards having been worked with a tongue on one edge and/or end, and a groove at the opposite edge and/or end to provide a tight joint when two pieces are fitted together.



matched boards

material cost The cost of everything of a substantial nature that is essential to the construction or operation of a facility, both of a direct or indirect nature. Generally includes all manufactured equipment as a basic part.*

material safety data sheet (MSDS) A form published by manufacturers of hazardous materials to describe the hazards thereof.

materials cage The platform on a hoist used for transporting materials to upper floors.

materials lock The chamber through which materials are passed from one environmental pressure to another.

mat foundation A continuous thick-slab foundation supporting an entire structure. This type of foundation may be thickened or have holes in some areas and is typically used to distribute a building's weight over as wide an area as possible, especially if soil conditions are poor.

matrix In concrete, the mortar in which the coarse aggregate is embedded. In mortar, the cement paste in which the fine aggregate is embedded.

matte A dull surface finish with low reflectance.

matte-surfaced glass Glass that has been etched, sandblasted, or ground to create a surface that will diffuse light.

mattock A heavy digging tool with a hoe blade on one side of the head and a pick or ax on the other.

mattress A grade-level concrete slab used to support equipment, such as transformers and air conditioning units, outside a building.

maturing The curing and hardening of construction materials such as concrete, plaster, and mortar.

maul A long-handled heavy wooden mallet.

maximum demand **1.** The greatest anticipated load on an electrical system during a given period of time. **2.** The greatest anticipated load on a sanitary waste system during a given period of time.

maximum density The largest unit weight to which a material may be compressed.

maximum power point (MPP) In photovoltaic systems, the point at which the most possible current is drawn from a cell, and the voltage subsequently drops off. The MPP changes slightly with temperature and intensity of sunlight. Most photovoltaic (PV) systems have power conditioning electronics, called maximum power point trackers (MPPT), that constantly adjust the voltage in order to maximize power output. Simpler systems operate at a fixed voltage close to the optimal voltage.

maximum rated load The greatest live load, plus dead load, which a scaffold is designed to carry, including a safety factor.

meager lime A low-purity lime commonly used in plaster. Contains at least 15% impurities.

mean roof height The distance from average grade to average roof elevation.

means of egress Any continuous exit path from a building to the outside.

measurement standard Any standard set to ensure that measurements are recorded in a reliable, uniform manner.

mechanic **1.** A person skilled in the repair and maintenance of equipment. **2.** Any person skilled in a particular trade or craft.

mechanical advantage The ratio of the weight lifted by a machine divided by the force applied.

mechanical application The placing of plaster or mortar by pumping or spraying, as opposed to placement by hand with a trowel.

mechanical bond (mechanical connection) A bond formed by keying or interlocking as opposed to a chemical bond by adhesion, as plaster bonding to lath or concrete bonding to deformed reinforcing rods.

mechanical completion Unit is essentially complete for start-up operation and test run. All major work is completed. Minor work not interfering with operation may not be completed, such as punch list and minor touchup work.*

mechanical drawing **1.** A graphic representation made with drafting instruments. **2.** Plans showing the HVAC and plumbing layout of a building.



mechanical drawing

mechanical equivalent of heat A measure of mechanical energy that equates work (measured in Joules) and thermal energy (measured in calories). Equal to one Btu of heat and 778 foot-pounds.

mechanical joint A plumbing joint that uses a positive clamping device to secure the sections, such as a flanged joint using nuts and bolts.



mechanical joint

mechanical plan In construction documents, the print that shows piping, ductwork, HVAC equipment, and fire safety systems.

mechanical properties The properties of a material defining its elasticity and its stress-strain relationships.

mechanical room A room or space that houses HVAC, plumbing, and electrical equipment, as well as controllers for a building automation system.

mechanical trowel A machine with interchangeable metal or rubber blades used to compact and smooth plaster.

media filtration A physical process that removes suspended solids from an aqueous waste stream by forcing the fluid through a porous medium.

medium **1.** Any material used for the transmission of signals (radio, light, and sound waves). A medium could be cable or wire (radio); optical fiber (light); or water, air, or free space (sound). **2.** In paint, the liquid in which the other ingredients are suspended or dissolved.

medium carbon steel Steel with a carbon content from 0.3 to 0.6 percent.

medium curing asphalt Liquid asphalt composed of asphalt cement and a kerosene-type dilutent (thinner) of medium volatility.

medium-density fiberboard (MDF) A fiberboard made of compressed wood fibers glued together. The smooth and stable surfaces of MDF provide an excellent substrate for painting or the application of decorative lamination or wood veneers. Commonly used to manufacture furniture, cabinets and flooring systems.

medium-density overlay (MDO) An exterior-grade plywood or fiberboard with a fiber resin veneer on both sides. An ideal base for paint, MDO is commonly used for signs.

medium-density polyethylene (MDPE) A widely used, inexpensive thermoplastic that is easy to process and has good to excellent chemical resistance. It is also soft and cannot be used in temperatures much above 150°F. MDPE combines the characteristics of low- and high-density polyethylene. It is less translucent than LDPE but more flexible than HDPE.

medium-temperature water-heating system A water-heating system with a boiler that heats water to between 250°F and 350°F before it is supplied to heating devices.

meeting posts With a double gate, the stiles that meet in the middle.

meeting rail With a double-hung window, the horizontal rails that meet in the middle.

megabit Approximately one million bits.

megahertz One million hertz (Hz).

melamine A plastic laminate made by fusing a resin-impregnated surface material, under heat and pressure, into a dense, ~5EF″ board. Has superior scratch and water resistance and is not prone to delamination.

member A general term for a structural component of a building, such as a beam or column.

membrane curing A process of controlling the curing of concrete by sealing in the moisture that would be lost to evaporation. The process is accomplished either by spraying a sealer on the surface or by covering the surface with a sheet film.

membrane fireproofing A lath and plaster layer applied as a fireproofing barrier.

membrane roofing A term that most commonly refers to a roof covering employing flexible elastomeric plastic materials from 35 to 60 mils thick, that is applied from rolls and has vulcanized joints. The initial cost of an elastomeric-membrane roof covering system is higher than a built-up roof, but the life-cycle cost is lower.



membrane roofing

membrane theory In thin-shell design, the assumption that a shell has no strength in bending because of deflection, and, that the only stresses in any section are in tension, compression, and shear.

membrane waterproofing The application of a layer of impervious material, such as felt and asphaltic cement, to a foundation wall.



membrane waterproofing

mending plate A steel strap with predrilled screw holes used to span and strengthen wood joints.

mensuration The determination of length, area, and volume.

merchant pipe A lightweight pipe that is up to 8% lighter than standard pipe.

mercury switch An electrical switch that contains mercury in a vial to make a silent contact.

mesh **1.** A network of wire screening or welded wire fabric used in construction. **2.** The number of openings per lineal inch in wire cloth.

mesothelioma A rare form of cancer linked in almost all cases to asbestos exposure.

metal-clad fire door A flush door with a wood core or stiles and rails and heat-insulating material covered with sheet metal.

metal crating Open metal flooring for pedestrian or vehicular traffic used to span openings in floors, walkways, and roadways.

metal curtain wall A metal exterior building wall that is attached to the structural frame but does not support any roof or floor loads.

metal deck Formed sheet-metal sections used in flat-roof systems.

metal framing Metal framed partitions commonly used for fire-rated construction

metal gutter Typically, a preformed aluminum or galvanized steel trough attached at the eaves of a sloped roof.

metal halide lamp A high-intensity discharge (HID) lamp that produces light from a metal vapor such as mercury or sodium.

metal lath Any of a variety of metal screening or deformed and expanded plate used as a base for plaster. The metal lath is attached to wall studs or ceiling joists.

metallic insulation A heat shield of thin metal applied over insulating board or sheathing.

metallic paint A paint containing metal flakes that reflect light.

metal nosings Metal enclosures over the cut ends of acoustic lining sections in ductwork.

metal pan A form used for placing concrete in floors and roofs. A metal pan may also be made of molded fiberglass.

metal primer The first coat of paint on a metal surface. Primer usually contains rust inhibitors and/or agents to improve bonding.



metal deck

metal framing



metal lath

metal roof panel A metal roof sheet that interlocks and has a weather exposure after installation less than 3 SF per sheet.

metal roof panel

metal sash block A concrete masonry unit with a groove in the end into which a metal sash can fit.

metal track In metal-stud construction, a U-shaped channel member used along floors, ceilings and walls as a brace for metal studs.

metal trim Grounds, angle beads, picture rails, and other metal accessories that are attached prior to plastering.

metal valley A roof valley gutter lined with sheet metal flashing.

metal wall ties The prefabricated metal strips that secure a masonry veneer to a structural wall.

metal window A solid metal-framed window such as those used in factories.



metal wall ties

metamorphic rock A rock mass whose crystalline structure, composition, or texture has been altered by great heat or pressure during its formation.

meter **1.** The base unit of length in the metric system of measurement. A meter is equivalent to 39.37″. **2.** A device for measuring the flow of liquid, gas, or electrical current.

meter stop A valve in a water service line that cuts off the flow of water before it reaches the meter.

metes and bounds The limits or boundaries of property, as identified by measured distances and compass bearings.

methyl methacrylate (MMA) A rigid, transparent material widely used in the manufacture of acrylic resins and plastics, as well as in surface-coating resins, emulsion polymers, and impact modifiers.

metric ton A weight equal to 1,000 kilograms or 2,205 pounds.

mezzanine A suspended floor, usually between the first floor and the ceiling, that covers less area than the floor below.

mica A naturally occurring, clear silicate used in thermal and electrical insulation, paint suspensions, and composite roofing materials.

microcell A cell within a cellular phone network—with a low-power base station that covers a facility such as a hotel, transportation hub, or mall.

microlam Refers to high-strength, construction-grade engineered wood beams constructed of wooden strands bonded with adhesive under pressure. Also known as laminated veneer lumber (LVL).

micrometer **1.** Instrument used for accurately measuring extremely small distances. **2.** Unit of linear distance equal to one-millionth of a meter.

micron A metric unit of measure equal to one-millionth of a meter, commonly used in particle measurement. One micron is approximately 1/25,400 (0.00004) of an inch.

microwave A very short electromagnetic wave with a wavelength range from one millimeter to one meter.

microwave motion detector A device that detects motion by sending out a microwave signal and looking for a return. A moving object will reflect back some microwave energy, triggering a response. Applications include security, lighting and automatic door systems.

middle lap joint A T-shaped joint formed when the end of one member and the middle of another are joined. Each member is halved along the area of the joint to form a flush connection.

middle strip In flat-slab framing, the slab portion that occupies the middle half of the span between columns.

mil A measure of thickness typically used to describe materials such as plastic sheeting, trash bags, or vinyl, equal to 0.001″. Used to measure coating, wire, and material thickness.

mildew A fungus that grows on damp fabric and other materials, particularly when there is a lack of air circulation.

mildewcide A product used to retard or prevent the growth of mildew.

mild steel A steel having a low carbon content, and therefore being relatively soft and ductile. This type of steel is sometimes used for the manufacture of boilers and tanks, but not for structural beams, columns, or lintels. Mild steel is not as resistant to corrosion as wrought or cast iron and corrodes faster if not regularly maintained.

mile A distance measure equal to 5,280 feet, 1,760 yards, or 8 furlongs.

mileage tax A license tax levied on intrastate transportation business to compensate for use of the state's public roads.

milestone A specific, predetermined measurement of the completion of a project typically used for progress payment purposes.

milkiness A whitish haze caused by moisture and often occurring in a varnish finish.

milk of lime A hydrated lime slaked in water to form a lime putty.

mill To shape metal or wood to a desired dimension by a machine that removes excess material.

mill construction Historically, a type of construction used for factories and mills, and consisting of masonry walls, heavy timbers, and plank floors.

Miller Act A federal labor law that requires general contractors working on federally funded construction projects to obtain performance bonds and labor and material payment bonds to protect the interests of subcontractors and suppliers. The Miller Act applies to all U.S. government construction contracts valued at more than $25,000.

mill finish The type of finish produced on metal by the extrusion or cold rolling of sections.

milling **1.** In metal, the process of shaping an item by rotary cutting machines. **2.** In stonework, the shaping of a stone to the desired dimensions.

mill length (random length) Refers to length of pipe, usually for power plant or oil field use, often made in double random lengths of 30′ to 35′. (The usual run-of-the-mill pipe is 16′ to 20′ in length.)

mill run Products from a mill, such as a sawmill, that have not been graded or sized.

mill scale A thin, loose coat of iron oxide that forms on iron or steel when heated.

millwork All the building products made of wood that are produced in a planing mill, such as moldings, door and window frames, doors, windows, blinds, and stairs. Millwork does not include flooring, ceilings, and siding.



millwork

millwright A carpenter skilled in the layout, installation, and alignment of heavy equipment such as that used in manufacturing.

mineral admixture A substance added to concrete as both a filler, improving the physical structure by occupying the spaces between the cement particles, and as a "pozzolan," reacting chemically to impart far greater strength and durability.

mineral dust Aggregate passing the No. 200 screen, usually a by-product of crushed limestone or traprock.

mineral fiber insulation Insulation primarily composed of rock, slag, or glass fibers.

mineral fiber tile A preformed ceiling tile composed of mineral fiber and a binder with good acoustical and thermal properties.



mineral fiber tile

mineral-filled asphalt Asphalt with mineral dust in suspension to improve its body and plasticity.

mineral-insulated cable Seamless copper tubing carrying one or more conductors that is embedded in refractory minerals and used in areas that may be subjected to high heat.

mineral spirits A liquid paint thinner and solvent obtained from a petroleum distillation process.

mineral-surfaced felt A roofing felt used on flat or sloped roofs that has a mineral-aggregate surface that improves its wearing and heat-reflecting properties.

mineral wool Fibers formed from mineral slag, the most common being glass wool, which is used in loose or batt form for thermal and sound insulation and for fireproofing.

minimum acceptable pressure The lowest pressure in an air and water distribution system that still allows for safe and efficient operation.

Minimum Efficiency Reporting Value (MERV) A classification used for air filters, determined by a standard ASHRAE test. A higher number MERV indicates a filter that traps more contaminants.

minimum point of entry (MPOE) The point at which carrier lines terminate, usually 12" inside of a building's foundation wall.

minimum wage law Common term used to describe the Fair Labor Standards Act enacted by Congress in 1938. This act established a minimum wage for workers and the 40-hour workweek.

minor change A job change requiring field approval only. No change order is necessary.

minor diameter The smallest diameter of a screw thread.

minority business enterprise (MBE) A business that is at least 51% owned and operated by African Americans, Asian Americans, Hispanic Americans and/or Native Americans.

minute An angle measurement equal to 1/60 of a degree.

mission tile A clay roofing tile shaped like a longitudinal segment of a cylinder. The tile is used on sloped roofs with the concave side alternately up, then down.



mission tile

miter box A device used by a carpenter or cabinetmaker to cut the bevels for a mitered joint.

miter clamp A clamping device that holds a mitered joint during fastening and gluing.

miter cut The beveled cut, usually 45°, made at the end of a piece of molding or board that is used to form a mitered joint.

miter dovetail A dovetail joint in which the pins do not project all the way through, so that it looks like a mitered joint.

mitered hip A roofing hip that has been close cut.

mitered valley A roofing valley that has been close cut.

miter gauge A gauge that measures the angle of a miter.

miter joint A joint, usually 90°, formed by joining two surfaces beveled at angles, usually 45° each.

miter knee The miter joint formed when the horizontal handrail at a landing is joined to the sloping handrail of the stairs.

miter plane A carpenter's planing tool used for preparing the surfaces for miter or butt joints.

miter rod A flat metal plate with one end cut at a 45° angle that plasterers use to finish inside corners.

miter square A carpenter's square with one edge having an angle of 45° for laying out miter joints.

miter valve A valve with a disk that sits at a 45° angle to the valve axis.

mitigation of damages A duty that the law imposes on an injured party to make a reasonable effort to minimize his or her damages after an injury.

mix design The selection of specific materials and their proportions for a concrete or mortar batch, with the goal of achieving the required properties with the most economical use of materials.

mixed in place An asphalt course of mineral aggregate and emulsified asphalt mixed at the site by special road-mixing equipment.

mixer A machine for blending the ingredients of concrete, mortar, or grout. Mixers are divided into two categories: batch mixers and continuous mixers. Batch mixers blend and discharge one or more batches at a time, whereas continuous mixers are fed the ingredients and discharge the mix continuously.



mixer

mixer truck *See* **transit mix**.

mixing box In HVAC systems, a chamber, usually located upstream of the filters, that collects outside air and return air.

mixing cycle The elapsed time between discharges of a batch mixer.

mixing speed In mixing a batch of concrete, the rate of rotation of a mixer drum or of the mixing paddles expressed in revolutions per minute (RPM). The rate can also be expressed as the distance traveled, in feet per minute (FPM), of a point on the circumference of a mixer drum at its maximum diameter.

mixing valve A valve that mixes two liquids or a liquid and a gas, such as steam with water or hot water with cold water.

mixing water The water used in mixing a batch of concrete, mortar, or grout, exclusive of water previously absorbed by the aggregates. As a general rule, the water should be clean enough to drink.

mix proportions The quantities of cement, coarse aggregate, fine aggregate, water, and other additives in a batch of concrete by weight or volume.

mobile crane Any crane mounted on wheels or tracks. They are classified by lifting capacity.

mobile gantry A movable framework housing a work platform or means to support equipment.

mobile hoist A personnel or material platform hoist that can be towed to and around the site on its own wheels.

mobile scaffold A scaffold that can be moved on wheels or casters.

model **1.** A scale representation of an object, system, or building used for structural, mechanical, or aesthetic analysis. **2.** A compilation of parameters used in developing a system.

model codes Professionally prepared building regulations and codes, regularly attended and revised, designed to be adopted by municipalities and appropriate political subdivisions by ordinance. Model codes are used to regulate building construction for the welfare and safety of the general public.

model server *See* **BIM server**.

modem Short for *modulator/demodulator*. An electronic device that transmits data to or from a computer via telephone lines. A modem translates between digital signals (used by data processing equipment) and analog signals (used in voice switching equipment). Once the data is sent through the telephone lines, it is retranslated back into digital form in the computer at the receiving end.

modification (to construction contract documents) **1.** A change to a contract that is made after the contract has been signed by both parties. **2.** A change order.

modified accelerated cost recovery system (MACRS) The method currently required for determining the calculation of asset depreciation for tax purposes. MACRS comprises two subsystems: the General Depreciation System (GDS) and the Alternative Depreciation System (ADS).

modified asphalt Asphalt whose binder has been modified by additives such as rubber or polymers for specific applications.

modified bitumen A heavy roofing material employing multiple layers of asphalt and reinforcers around a core of plastic or rubber modifiers. Installed with a special torching apparatus, a cold adhesive, or hot-mopped into place using methods of asphalt application.

modular masonry unit A brick or block manufactured to a modular dimension of 4″.

modular ratio The ratio of the modulus of elasticity of steel to that of elasticity of concrete, denoted by n in the formula: $n = Es/Ec$.

modulation The tendency of a control to adjust by increments and decrements, rather than in an "on/off" fashion.

modulus of compression The measure of a material's resistance to inward pressure.

modulus of elasticity The unit stress divided by the unit strain of a material that has been subjected to a strain below its elastic limit.

modulus of resilience The measure of the elastic energy absorbed by a unit volume of a material when it has reached its elastic limit in tension.

modulus of rigidity The measure of a material's resistance to shear. The ratio of unit shearing stress to unit shearing strain.

modulus of rupture The measure of a beam's maximum load-carrying capacity. The ratio of the rupture's bending moment to the beam's section modulus.

modulus of toughness The measure of energy per unit volume that is absorbed by a material when subject to impact, up to the point of fracture.

mogul base A screw-in type base for a large incandescent lamp usually of 300 watts or more.

Mohs scale An arbitrary scale devised to determine the relative hardness of a mineral by its resistance to scratching by another mineral. Talc is rated No. 1, and diamond is rated No. 10.

moist room An enclosure maintained at a given temperature and relative humidity and used for curing test cylinders of concrete or mortar.

moisture barrier A dampproof course or vapor barrier, but not necessarily waterproof. *See also* **vapor barrier**.

moisture content The weight of water in materials such as wood, soil, masonry units, or roofing materials, expressed as a percentage of the total dry weight.

moisture gradient The difference in moisture content between the inside and the outside of an object, such as a wall or masonry unit.

moisture migration The movement of moisture through the components of a building system such as a floor or wall. The direction or the movement is always from high-humidity areas to low-humidity areas.

moistureproofing The application of a vapor barrier.

moldboard The curved shape or blade of a plow, bulldozer, grader, or other earth-moving equipment.



moistureproofing

molded brick Brick that has been cast rather than pressed or cut, often with a distinct design or shape.

molded-case circuit breaker An electrical circuit breaker manufactured in a molded insulated housing.

molded insulation Thermal insulation premolded to fit plumbing pipes and fittings. Common materials are fiberglass, calcium silicate, and urethane foams, with or without protective coverings.

molded plywood Plywood that has been permanently shaped to a desired curve during curing.

molding An ornamental strip of material used at joints, cornices, bases, door and window trim, and the like, and most commonly made of wood, plaster, plastic, or metal.



molding

mole An excavation machine used to bore tunnels.

molecular sieve A device for selective collection, by adsorption, of a substance in a gas or a liquid.

moler brick Brick, made from moler earth or diatomite, that has better insulation properties than common brick.

moment An applied load or force that creates bending in a structural member. It is numerically expressed as the product of the force times the length of the lever arm, and given in units such as foot-pounds.

moment connection A rigid connection between structural members that transfers moment from one member to the other, and thus resists the moment force. A pinned connection cannot resist moment forces, only shear forces.



moment connection

moment of inertia In a structural member, the product of each element of mass times the square of the distance from an axis.

momentum The mass times the velocity of a moving object.

money damages A monetary award that a party who has breached a contract is ordered by a court to pay as compensation to the nonbreaching party.

monitor **1.** A raised section of a roof, often along the ridge of a gable roof, with louvers or windows in the side for ventilation or light. **2.** In closed-circuit television, a video display device used to check the quality of a picture or image transmitted by a camera.

monkey wrench A wrench with a fixed jaw and an adjustable jaw.

monolithic In glazing, a window containing only one light or pane.

monolithic concrete Concrete that has been cast continuously with no joints other than construction joints.

monolithic construction The pouring of concrete grade beam and floor slab together to form a building foundation.

monolithic surface treatment A concrete finish obtained by shaking a dry mixture of cement and sand on a concrete slab after strike-off, then troweling it into the surface.

monolithic terrazzo Terrazzo applied directly over a concrete surface instead of over a mortar underbed.

monopost An adjustable metal column that supports a bearing point or beam.

Monotube® pile A cold-processed steel pile with a fluted cross section for use in deep foundations.

mop plate A protective plate at the bottom of a door, such as a kickplate.

mop sink A low, deep sink used by janitors.



mop sink

moratorium A temporary denial of permission to develop, used by local government to create an opportunity to formulate permanent growth policies and plans for an area.

mortar **1.** A plastic mixture used in masonry construction that can be troweled and hardens in place. The most common materials that mortar may contain are Portland, hydraulic, or mortar cement, lime, fine aggregate, and water. **2.** The mixture of cement paste and fine aggregate that fills the voids between the coarse aggregate in fresh concrete.



mortar

mortar aggregate (mortar sand) Natural or manufactured fine aggregate, usually washed screened sand.

mortar bed A layer of fresh mortar into which a structural member or flooring is set.

mortarboard A board about 3 feet square on which mortar is placed for use by a mason on a scaffold.

mortar box A shallow box in which mortar or plaster is mixed by hand.

mortar mill (mortar mixer) A machine with paddles in a rotating drum for mixing and stirring mortar.



mortar box

mortise **1.** A recess cut in one member, usually wood, to receive a tenon from another member. **2.** A recess such as one cut into a door stile to receive a lock or hinge.

mortise and tenon joint A joint between two members, usually wood, which incorporates one or more tenons on one member fitting into mortises in the other member. Used on joints such as door stiles, door rails, window sashes, and cabinetry.



mortise and tenon joint

mortise chisel A carpenter's tool for cutting mortises.

mortise gauge A carpenter's tool for scribing the location on mortises. It is similar to a marking gauge, but scribes two parallel lines.

mortise machine A power-driven machine for cutting rectangular or round mortises in a wood member.

mortise pin A pin that secures a mortise and tenon joint by being driven through either the extension of the tenon or through the whole joint.

mosaic **1.** An aerial photographic map pasted up using the center portion of overlapping vertical photographs. **2.** A design created by inlaying pieces of stone, glass, or tile in a mortar bed. **3.** A design of inlaid pieces of wood.

motion-detection equipment A device that detects motion by sending out a fixed electromagnetic or ultrasonic signal. A moving object will disrupt the frequency of the signal, triggering a response. Applications include security, lighting and automatic door systems.

motor controller A device that controls the power delivered to a motor or motors.



motor controller

mouse **1.** A device with a piece of curved lead and string for pulling a sash cord over a pulley. **2.** A handheld device that is moved around on a desk or surface to control the cursor in a computer and select functions.

movable form A large prefabricated concrete form of a standard size that can be moved and reused on the same project. The form is moved either by crane or on rollers to the next location.



movable form

movable partition A non-load-bearing demountable partition that can be relocated and can be either ceiling height or partial height.

moving ramp A continuously moving belt or other system designed for carrying passengers on a horizontal plane or up an incline.

M-roof Any roof that incorporates two adjacent pitched roofs in resemblance to the letter "M."

muck **1.** A soil high in organic material, often very moist. **2.** Any soil to be excavated.

mucking Rearward removal of heading excavation.

mud **1.** Soil containing enough water to make it soft and plastic. **2.** A slang expression for joint compound.

mudjacking A method of raising a depressed concrete highway slab or slab-on-grade by boring holes at selected locations and pumping in grout or liquid asphalt.

mud pan Rectangular, angle-sided pan, shaped like a bread pan, used by joint finishers to handle portions of joint compound. The straight-cut lip of the pan ensures that the taping knife can be cleaned regularly.

mud rotary drilling method A drilling method that uses mud as the lubricant for the drill.

mudsill A plank or beam laid directly on the ground, especially for posts or shores for formwork or scaffolding.

mud slab A base slab of low-strength concrete from 2″ to 6″ thick placed over a wet subbase before placing a concrete footing or grade slab.

muffle A layer of grout over a plaster mold used to rough in the plaster. The muffle is chipped off when the final coat of plaster is applied.

mulch Organic material such as straw, leaves, or wood chips spread on the ground to prevent erosion, to control weeds, to minimize evaporation as well as temperature extremes, and to improve the soil.

mullion The vertical member separating the panels or glass lights of a window or door system.

multiconductor An electrical cable containing multiple wires inside a single outer jacket.

multimedia filter A water-supply system filter that incorporates several different filtering elements or materials.

multiple glazing Any glazing that incorporates two or more sheets of glass, as in a thermal- or sound-insulating application.

multiple-layer adhesive An adhesive film used as a bond between dissimilar materials.

multiple of direct salary expense An accounting method used to pay for professional services. It is based on direct salary expenses multiplied by a factor that accounts for the cost of benefits that are linked to direct salary as well as indirect expenses, other direct expenses, and profit.

multiple prime contract A contract used when one or more constructors are employed under separate contracts to perform work on the same project, either in a sequence or coincidentally.

multiple surface treatments A term applied to successive pavement surface treatments of asphaltic materials and aggregate.

multiplex To send signals from more than one source simultaneously over a single channel.

multiplier A factor used to adjust costs for modifications, such as for location, time, or size of project.

multistage stressing The prestressing of concrete members in stages as the construction progresses.

multiunit wall A masonry wall with two or more wythes.

multiuser telecommunications outlet assembly A connecting point within a structured cabling system; for multiple users for a work area.

multizone system **1.** An air-conditioning system that is capable of handling several individual zones simultaneously. **2.** A heating or HVAC system having individual controls in two or more zones in a building.



multizone system

multizone units Air-handling units with parallel heating and cooling air paths providing individual mixing of air-distribution circuits into a single duct for each zone.

municipal lien A claim or lien filed by a municipality against a property owner for collection of the property owner's proportionate share of a public improvement made by the municipality that also improves the property owner's land.

muntin A short vertical or horizontal bar used to separate panes of glass in a window or panels in a door. The muntin extends from a stile, rail, or bar to another bar. *See also* **vertical bar**.



muntin

muriatic acid An acid mixed with water to clean masonry. Muriatic acid is also commonly used to etch smooth concrete surfaces for painting.

mushroom The spreading out of concrete at the top of a caisson pier, causing it to be wider than the thickness of the foundation wall.

mushroom construction A system of flat-slab concrete construction, with no beams, in which columns are flared at the top to resist shear stresses near the column head.



mushroom construction

mylar A thin, tough, smooth polyester film used as a drafting medium.

N

Abbreviations

n, N noon, number, North, nail, nitrogen, normal

Na sodium

NAAMM National Association of Architectural Metal Manufacturers

NAIOP National Association of Industrial Office Properties

NAT natural

NBC National Building Code

NBFU National Board of Fire Underwriters (now merged into the American Insurance Association)

NBIMS National Building Information Model Standard

nbm net board measure

NBS National Bureau of Standards

NC noise criterion

NCM noncorrosive metal

NCX fire-retardant treated wood

NDT nondestructive testing

NEC National Electrical Code

NECA National Electrical Contractors Association

NELMA Northeastern Lumber Manufacturers Association

NEMA National Electrical Manufacturers Association

NESC National Electrical Safety Commission

NESHAPS National Emission Standards for Hazardous Air Pollutants

NFC National Fire Code

NFIP National Flood Insurance Program

NFoPA National Forest Products Association

NFPA National Fire Protection Agency

NFRC National Fenestration Rating Council

NHLA National Hardwoods Lumber Association

NHPMA Northern Hardwood and Pine Manufacturers Association

Ni nickel

NIBS National Institute of Building Sciences

NIC not in contract

NIOSH National Institute of Occupational Safety and Health

NLRA National Labor Relations Act

NLRB National Labor Relations Board

NM nonmetallic sheathed

NOC network operations center

NOM nominal

NOP not otherwise provided for

norm normal

NPS nominal pipe size

NPV net present value

nr near, noise reduction

NRC noise reduction coefficient

NS not specified

ntp normal temperature and pressure

NTS not to scale

nt. wt., n.wt. net weight

num numeral

NwFA National Wood Flooring Association

NWWDA National Wood Window and Door Association

N1E nosed one edge (lumber industry)

N2E nosed two edges (lumber industry)

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

Definitions

nail A slender piece of metal with a point on one end that is driven into construction materials by impact. Nails are classified by size, shape, and usage.


nail

nailable concrete Concrete, usually made with a suitable lightweight aggregate, with or without the addition of sawdust, into which nails can be driven.

nailer A strip of wood or other fitting attached to or set in concrete, or attached to steel to facilitate making nailed connections.

nailing block (nog) A wood block set into masonry or steel and used to facilitate fastening other structural members by nailing.

nailing ground A nailing strip to which trim is attached.

nailing schedule A specific pattern or configuration of nails, most often used for fastening components of a structural assembly.

nail pop The protrusion of a nail from a wall or ceiling, usually attributed to the shrinkage of or use of improperly cured wood framing.

nail puller One of a variety of hand tools for pulling nails. The shape and size depends on the nails to be pulled.


nail puller

nail set A handheld, tapered steel rod specifically designed to drive nail heads below the surface of wood. The rod is used specifically in finish carpentry work.

naphtha-based oil Petroleum oil used as an additive in herbicides. Naphtha oil alone has herbicidal properties on some weeds and grasses.

narrow light door A door with a narrow vertical light near the lock stile.

narrow-ringed timber Lumber with fine-grained, closely spaced growth rings.

National Building Information Model Standard A standard developed by a National Institute of Building Sciences Facility Information Council committee. It integrates life-cycle information for use by facility management and AEC professionals.


narrow light door

National Electric Code® (NEC) A nationally recognized code that addresses proper installation of electrical systems and equipment. Published by the National Fire Protection Association, the code is revised and reissued every three years.

National Emission Standards for Hazardous Air Pollutants (NESHAPS) Federal air pollution regulations instituted by the Clean Air Act and enforced by the Environmental Protection Agency (EPA).

National Fenestration Rating Council (NFRC) An organization that provides ratings for energy performance for windows and skylights, doors, and accessories.

National Fire Protection Association (NFPA) A nonprofit organization that publishes the National Electrical Code®, the Life Safety Code®, the Fire Prevention Code™, the National Fuel Gas Code®, and the National Fire Alarm Code®.

National Institute of Building Sciences A nonprofit organization that works with the government and private sector on "solutions for the built environment," including standards, new technologies, and dissemination of information.

National Labor Relations Act An act of Congress sometimes known as the Wagner Act, enacted in 1935. This act mandated a framework of procedure and regulation by which management-labor relations are to be conducted.

National Lumber Grades Authority One of seven regional grading agencies in North America that are authorized to write and publish grading rules for lumber.

native landscape Plantings that are selected because they have adapted to thrive in the local environment without irrigation, fertilizer, or pesticides, and that provide storm-water management.

natural asphalt Asphalt occurring in nature through natural evaporation of petroleum. This type of asphalt can be refined and used in paving materials.

natural cement A hydraulic cement produced by heating a naturally occurring limestone at a temperature below the melting point, and then grinding the material into a fine powder.

natural convection The movement of air resulting from differences in density usually caused by differences in temperature.

natural draft Refers to the movement of air through a cooling tower by the force of air density differential.

natural gas A naturally occurring combustible gas used for industrial and domestic heating and power.

natural grade The undisturbed elevation of a property before any excavation operations.

naturally durable wood As defined for the purpose of building codes, the heartwood of certain species of decay-resistant wood, including black walnut, cedar, redwood, and black locust.

natural resin Any naturally occurring thermoplastic substance. Used in paints and varnishes, among other applications.

natural seasoning In the lumber industry, a curing process using natural air convection.

natural stone Stone shaped and sized by nature as opposed to stone that has been quarried and cut.


natural stone

NCX fire-retardant treated wood Treated wood generally used on exterior balconies, steps, and roof systems. Carries the Underwriters' Laboratories rating of FRS.

neat **1.** Idiom for exact dimensions, e.g., excavation to the designed width of the footing. **2.** A term referring to a process by which a material is prepared for use without addition of any other materials except water. Examples include neat cement or neat plaster.

neat cement A cement mortar or grout made without addition of sand or lime.

neat line The line or plane defining the limits of work, particularly in excavation of earth or rock. Excavation beyond the neat line is usually not a pay item in a unit price contract.

neat plaster Plaster mixed with no aggregate.

needle **1.** In underpinning, the horizontal beam that temporarily holds up the wall or column while a new foundation is being placed. **2.** In forming or shoring, a short beam passing through a wall to support shores or forms during construction. **3.** In repair or alteration work, a beam that temporarily supports the structure above the area being worked on.

needle nose pliers

needle nose pliers Pliers that are outfitted with long thin jaws for use in narrow spaces.



needle valve

needle valve A type of globe valve in which a long pin or needle, tapered at the end, moves in and out of a conical seat to regulate the flow of liquid.

negative cash flow On a construction project, when the periodic payments a contractor receives from an owner for the performance of the contract's construction work amount to less than what he will pay out during the same period for expenses associated with the work. (The amount of money coming in is less than the amount going out.)

negative float The amount of delay that a task on the critical path of the schedule has incurred, expressed in days.

negative friction The additional load placed on a pile by the settling of fill placed around it. The effect of negative friction is to pull the pile down.

negative pressure ventilation system A method of providing low-velocity airflow from uncontaminated areas into contaminated areas by means of a portable exhaust system equipped with HEPA filters.

negligence The failure of a party to conform its conduct to the standard of care required by law. The law requires that a person exercise that degree of care which a reasonable person would exercise under the same or similar circumstances.

negotiated procurement A procedure used by the U.S. government for contracting whereby the government and potential contractor negotiate on both price and technical requirements after submission of proposals. Award is made to the contractor whose final proposal is most advantageous to the government.

negotiation A process used to determine a mutually satisfactory contract sum, and terms to be included in the contract for construction. In negotiations, the owner directly selects the constructor and the two, often with assistance of the design professional, derive by compromise and a meeting of the minds the scope of the project and its cost.

neon lamp A lamp that gains its illumination by electric current passing through neon gas.



neoprene roof

neoprene A synthetic rubber with high resistance to petroleum products and sunlight. Neoprene is used in many construction applications, such as roofing and flashing, vibration absorption, and sound absorption.

neoprene roof A roof covering made of neoprene sheet material with heat-welded joints, which can be either ballasted or nonballasted. This type of roof covering has good elastic and durability properties over a long time span.



neoprene vibration pad

neoprene vibration pad A vibration-absorbing device placed under permanently installed machinery.

neoprene waterproofing Sheet waterproofing material placed on the outside of a foundation wall with a mastic.

nestable joist Standard shape for a light-gauge framing joist.

nested nails Nails having a crescent-shaped piece missing in the head to allow them to be fitted tightly together.

nested studs Two studs placed together for additional support in framing an opening.

net cross-sectional area In defining a masonry unit, the gross cross-sectional area minus the area of the ungrouted cores or cellular voids.

net cut In excavation, the total cut, minus the compacted fill required, between particular stations.

net fill In excavation, the compacted fill required, minus the cut material available, between particular stations.

net floor area The occupied area of a building not including hallways, elevator shafts, stairways, toilets, and wall thicknesses. The net floor area is used for determining rental space and fire code requirements.

net load In heating calculations, the heating requirement, not considering heat losses, between the source and the terminal unit.

net metering Allowing electric meters of power-generating facilities, such as solar or wind power, to turn backward when more energy is produced than customers consume. Net metering allows customers to use the excess energy their own system generates to offset their consumption over an entire billing period, not just at the time the electricity is produced.

net savings (NS) A measure of long-run profitability of an alternative relative to a base case. It can be calculated as an extension of the life-cycle costing (LCC) method as the difference between the LCC of a base case and the LCC of an alternative.

net site area The area of a building site less streets and roadways.

net weight The weight of an article, cargo, or other load minus the transporting vehicle.

network In CPM (critical path method) terminology, a graphic representation of activities showing their interrelationships.

network schedule A method of scheduling the construction process where various related events are programmed into a sequential network on the basis of starting and finishing dates.

neutral **1.** An electrical conductor used as the primary return path for current during normal operation of an electrical device. **2.** The center tap of a three- or four-wire transformer. Neutral cable will carry current when there is an unbalanced load between wires.

neutral axis In structural design, an imaginary line in a structural member where no tension, compression, or deformation exist. If holes are to be drilled through a structural member for conduits or pipes, they should be drilled at the neutral axis.

neutral cash flow On a construction project, when the periodic payments a contractor receives from an owner for the performance of the contract's construction work equal what will be paid out during the same period for expenses associated with the work. (The amount of money coming in equals the amount going out.) This is virtually impossible to achieve.

neutralize To reduce the pH of an alkali, or to raise the pH of an acid, to approximately 7.0.

neutralizing The treatment of concrete, plaster, or masonry surfaces with an acid solution in order to neutralize the lime before application of paint.

neutralizing basin In a building drainage system, a device that neutralizes acid-bearing wastes before their entry into the system.

newel The post supporting a handrail at the top and bottom of a flight of stairs. Also, the center post of a spiral staircase.



newel

N-grade wood **1.** In molding, stock intended for natural or clear finishes. The exposed face must be of one single piece. **2.** In plywood, cabinet quality panels for natural finishes.

nibbed tile A small lug at the upper end of a roofing tile that hooks over a batten.



nibbed tile

nib grade (nib guide, nib rule) A wooden straight edge nailed on the ceiling's base plaster coat as a guide for a cornice molding.

nickel A silver-colored, hard ductile metal used in alloys, batteries, and electroplating. Nickel is used extensively on plumbing fixtures, where its anticorrosive properties are important.

nickel silver A silver-colored class of nickel alloys containing copper and zinc but not silver.

nickel steel A steel alloy with 3% to 5% nickel content, that gives it greater strength, ductility, and anticorrosive properties.

nidge (nig) To dress or shape the edge of a masonry stone with the sharp point of a hammer, as opposed to doing so with a chisel and mallet.

night cycle program In a building automation system, an energy-saving computer program that maintains a reduced temperature in the heating season and an elevated temperature during the cooling season during unoccupied periods.

night purge program In a building automation system, a computer program that replaces building air with cooler outdoor air during the early morning hours of the cooling season.

nighttime ventilation Cooling buildings with outside air at night to minimize the cooling load during the day. Ventilation can be achieved naturally via temperature drops, wind, cross-ventilation, and stack effect, or through use of wind towers and mechanical ventilation.

nippers A hand tool for cutting wire and small rods.

nipple A piece of pipe less than 12″ long and threaded on both ends. Pipe over 12″ long is regarded as a cut measure.

nipple

nobble The process of shaping building stones to the roughly desired dimensions while the stone is still at the quarry.

noble A technical term describing a metal's degree of resistance to corrosion.

no damages for delay clause A contract provision that states that a contractor's sole remedy for delay is an extension of time without any monetary compensation even if the delay is caused by the owner or its agents.

node **1.** In critical path method scheduling, a junction of arrows containing the i-j number, early start, and late finish. **2.** In electrical wiring, a junction of several conductors.

no-fines concrete A concrete mixture with little or no fine aggregate.

no-hub pipe Cast iron pipe that is fabricated without hubs for coupling.

noise In closed-circuit television, interference detected on a cable circuit that reduces or destroys the clarity of the signal. Sometimes called snow.

noise absorption The reduction of noise in an enclosure by introducing sound-absorbing materials or methods of construction that restrict the transmission of sound.

noise criterion curve Defines the limits that the octave band spectrum of a noise source must not exceed if a certain level of occupant acceptance is to be achieved.

noise insulation Sound-absorbing materials installed in partitions, doors, windows, ceilings, and floors.

noise reduction **1.** The difference, expressed in decibels, between the noise energy in two rooms when a noise is produced in one of the rooms. **2.** The difference in noise energy from one side of a partition to another when a noise is produced on one side.



noise insulation

noise reduction coefficient The average sound absorption coefficient of a material to the nearest 0.05 at four frequencies: 250, 500, 1,000, and 2,000 cycles.

nominal Term indicating that the full measurement is not used. Usually slightly less than the full net measurement, as with 2″ × 4″ studs that have an actual size when dry of 1½″ × 3½″. Pipe size designations are also described as nominal. For example, 2″ nominal is 2~3⅛″ O.D.

nominal dimension **1.** The size designation for most lumber, plywood, and other panel products. In lumber, the nominal size is usually greater than the actual dimension, thus, a kiln-dried 2″ × 4″ ordinarily is surfaced to 1½″ × 3½″. In panel products, the size is generally stated in feet for surface dimensions and increments of 1⁄16″ for thickness. Product standards permit various tolerances for the latter, varying according to the type and nominal thickness of the panel. **2.** In masonry, a dimension larger than the one specified for the masonry unit by the thickness of a joint.



nominal dimension

nominal mix The proportions of the constituents of a proposed concrete mix.

nonagitating unit A truck-mounted container for transporting central-mixed concrete, not equipped to provide agitation (slow mixing) during delivery.

non-air-entrained concrete Concrete in which neither an air-entraining admixture nor air-entraining cement has been used.

nonbearing partition A partition that is not designed to support the weight of a floor, wall, or roof.

nonbearing wall A wall designed to carry no load other than its own weight.

noncohesive soil A soil in which the particles do not stick together, such as sand or gravel.

noncollusion affidavit A notarized statement by a bidder that the bid was prepared without any kind of secret agreement intended for a deceitful or fraudulent purpose.



nonbearing wall

noncombustible Any material that will neither ignite nor actively support combustion in air at a temperature of 1,200°F when exposed to fire.

noncompensable delay A delay for which the contractor receives a time extension only and may not recover its delay-related costs from the owner.

nonconcordant tendons In a statically indeterminate structure, tendons that are not coincident with the pressure line caused by the tendons.

nonconductor A material that does not easily conduct electric current. Such materials are used as insulators.

nonconforming work Work that does not fulfill the contractually agreed upon requirements.

noncorrosive flux A flux used in soldering operations that does not chemically attack the base metal.

nondestructive testing The examination of an object with technology that does not affect the object's future usefulness. Applications include the evaluation of the strength of concrete or a weld using ultrasonic measures.

nondrying A term applied to a material containing oils that do not oxidize or evaporate, and therefore do not form a surface skin. The term is often applied to glazing compounds.

nonelectric delay blasting cap A detonating cap with a delay device built in so that it detonates at a designated time after receiving an impulse or signal from a detonating cord.

nonevaporable water The water that is chemically combined during cement hydration and that is not removable by specified drying.

nonexcusable delay A delay that is the fault of the contractor for which the contractor will receive neither a time extension nor compensation.

nonferrous A term referring to any metal or alloy that does not contain iron, such as brass or copper.

nonflammable A material that will not burn with a flame.

nonfreeze sprinkler system A fire protection sprinkler system that is designed to operate in freezing temperatures.

nonionic surfactant An adjuvant with no electrical charge. Nonionic surfactants are compatible with all types of pesticides.

nonmetallic sheathed cable Two or more electrical conductors enclosed in a nonmetallic, moisture-resistant, flame-retardant sheath.



nonmetallic seathed cable

nonnailable decks In built-up roofing, a deck or substrate requiring the base sheet to be adhered rather than mechanically fastened.

non-point-source pollution Runoff contamination from an overall site or land use and not discharged from a single pipe, such as sediment from construction sites, oils from parking lots, or fertilizers and pesticides washed from farm fields.

nonpotable substitution system A system that uses byproduct water to replace potable water for systems that do not require fresh water.

nonpressure pipe A pipe with no pressure rating, and therefore only suitable for conveying liquid by gravity.



nonprestressed reinforcement

nonprestressed reinforcement Reinforcing steel in a prestressed, concrete structural member that is not subjected to prestressing or posttensioning.

nonproduction costs Overhead costs, or the cost of supporting actual production activities.

nonrestrictive specification A type of specification that is written so as not to restrict the product to a particular manufacturer or material supplier.

nonreturn valve A check valve that allows flow in only one direction.

nonsimultaneous prestressing The posttensioning of tendons individually rather than simultaneously.

nonsiphon trap A plumbing fixture that creates a water seal that cannot be siphoned, but still allows the free flow of liquids.

nonskid floor A concrete floor surface treated with carborundum powder, iron filings, or other material to improve its traction qualities, especially when wet. The surface may also be brushed before the concrete sets to create a rough finish.

nonstaining mortar A mortar, with low free-alkali content, that avoids efflorescence or staining of adjacent masonry units by migration of soluble materials.

nontilting mixer A rotating drum concrete mixer on a horizontal axis. Concrete is discharged by inserting a chute that catches the concrete from the rotating fins.

normal consistency **1.** The degree of wetness exhibited by a freshly mixed concrete, mortar, or neat cement grout when the workability of the mixture is considered acceptable for the purpose at hand. **2.** The physical condition of neat cement paste determined with the Vicat apparatus in accordance with a standard method of testing.

normalizing The heating of steel or other ferrous alloys to a specified temperature above the transformation range, followed by cooling in ambient air. The process reduces the brittleness and strength of the metal, but increases its ductility.

normally closed valves Valve ports are closed to flow when external power or pressure is not being applied.

normally open valves Valve ports are open to flow when external power or pressure is not being applied.

normal power factor ballast A ballast whose power factor is between 0.4 and 0.6.



Norman brick

Norman brick A brick with nominal dimensions of 2¾″ × 4″ × 12″. Three courses of Norman brick lay up to 8″.

nosing The horizontal projection of an edge from a vertical surface, such as the nosing on a stair tread.



nosing

no-slump concrete Fresh concrete with a slump of 1″ or less.

notching A timber joint in which one or both of the members have a section or notch cut out.

notch joist A joist with a section cut out to fit a ledger or girder.

notice to bidders A notice included in the bidding documents that informs prospective bidders of the bidding procedures and the opportunity to submit a bid.

notice to creditors During bankruptcy proceedings, the formal notification to creditors of a meeting or the granting of an order for relief.

notice to proceed A written notice from the project owner to the contractor in which the contractor is authorized to proceed with the work on a specified date.

novation One party's agreement to release another party from a contract in exchange for a new party as substitute.

nozzle An attachment to the outlet of a pipe or hose that controls or regulates the flow.

N-truss A Pratt truss.

nuisance alarm An alarm triggered by a malfunction or incorrect information.

nurses call system An electrically operated system for use by patients or personnel for summoning a nurse.

nut A short metal block with a threaded hole in the center for receiving a bolt or threaded rod.



nut

nylon fiber A synthetic fiber used extensively in floor coverings, wall coverings, drapery, and other furnishings.

O

Abbreviations

O	oxygen
OA	overall; outside air
O/A	on approval
OAI	outside air intake
OA&M	operation, administration, and maintenance
OAS	outside air supply
OASIS	Organization for the Advancement of Structured Information Standards
OAT	outdoor air temperature
oBix	open Building Information Xchange
OBM	ordinance benchmark
OBS	obsolete; open back strike
OC, oc	on center
OCT	octagon
OD	outside diameter
ODS	ozone-depleting substance
OEM	original equipment manufacturer
OFCI	owner-furnished and contractor-installed
OFE	owner-furnished equipment
OFF	office
OFOI	owner furnished and owner installed
OG, og	ogee
O/H, OVHD, OH	overhead
OHS	oval-headed screw
OJT	on-the-job training
OLED	organic light-emitting diode
O&M	operations and maintenance
OO	object-oriented; owners and operators
Opex	operating expense
opp	opposite
opt	optional
OR	outside radius, owner's risk
ord	order, ordinance
ORIG	original
OS	operating system
OS&Y	outside screw and yoke
OSCR	Open Standards Consortium for Real Estate
OSHA	Occupational Safety and Health Administration; Occupational Safety and Health Act
OSS	operations support systems
OZ, oz	ounce

Definitions

oak A hard, dense wood used for heavy framing, flooring, interior trim, plywood, and furniture. The two types available from mills are white oak and red oak.

oakum A caulking material made from hemp fibers that are sometimes saturated with tar. Oakum is commonly used with a bell-and-spigot joint in cast iron pipe. Oakum is packed into the joint with a hammer and chisel before molten lead is poured into the joint to seal it.

obligation A result of custom, law, or agreement by which an individual is duty bound to fulfill an act or other responsibility.

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

oblique drawings One face of an object drawn directly on the picture plane. Projected lines are drawn at a 30° or 60° angle.



oblique drawings

oblique photograph An aerial photograph taken with the camera axis inclined away from the vertical. A high oblique photograph is one that shows the horizon; a low oblique does not include the horizon.

obscure glass Glass that transmits light but does not allow a view of objects on the other side, such as ground glass or frosted glass; translucent glass.

observation of the work The architect, during construction-phase visits to a project, observes the progress and quality of the work. The purpose of the visits is to verify that work is proceeding as specified in the contract documents.



obscure glass

obsolescence **1.** The condition of being out of date. A loss of value occasioned by new developments that place the older property at a competitive disadvantage. A factor in depreciation. **2.** A decrease in the value of an asset brought about by the development of new and more economical methods, processes, and/or machinery.

O

occupancy The designed or intended use of a building. Also, the ratio of present space being used or rented to the designed full use, expressed as a percent.

occupancy management Identifying the presence of building users in different parts of a facility, for example by using occupancy sensors, in order to save energy by automatically turning off lights in unoccupied spaces.

occupancy rate The number of persons per building, unit, room, or floor.

occupancy sensor A heat-sensitive electronic sensor that reacts to moving heat sources within its monitored field. Used as a component of security and lighting systems.

occupant load The maximum number of persons in an area at a given peak period.

occupant unit cost estimate An early-stage planning estimate based on the projected number of facility users. Costs are expressed per common unit, which may be desks for schools, seats for auditoriums, beds for hospitals, or rental rooms for hotels. Also referred to as *end product unit, end unit*, or *capacity* estimates.

Occupational Safety and Health Act The federal law governing the safety of workers in the workplace.

odorless mineral spirit A thinner used in interior paints because of its odorless qualities.

odorless paint A water-based paint, or a base using odorless mineral spirit, that produces very little odor.

off-center (out-of-center) A load that is applied off the geometric center of a structural member, or a structural member that is placed off the geometric center of an applied load.

offer A proposal, as in a wage and benefits package, to be accepted, negotiated, or rejected.

off-gassing The release of airborne particulates, often from installed construction materials such as carpeting, cabinetry, or paint, that can cause allergic reactions and other health problems in building occupants.

Office of Federal Contract Compliance (OFCC) An agency of the U.S. Department of Labor that requires contractors for federal projects to maintain affirmative action in providing equal rights for employees under the provisions of Title IV of the Civil Rights Act of 1964, which forbids discrimination by an employer on the basis of race, color, religion, sex, or national origin.

off-road hauler A heavy-duty rear dump truck or bottom dump wagon capable of routinely hauling over rough haul roads.

offset **1.** In surveying, a line or point placed at a given distance from a control line or point used to reestablish the original location. **2.** In plumbing, an assembly of fittings on a pipeline that takes one section of pipe out of line but parallel to a second section. **3.** Any bend in a pipe.

offset bend An intentional distortion from the normal straightness of a steel reinforcing bar in order to move the center line of a segment of the bar to a position parallel to the original position of the centerline. The offset bend is commonly applied to vertical bars that are used to reinforce concrete columns.

offset screwdriver A screwdriver whose head is set at 90° to its shaft.

offset stakes Stakes placed by the excavator to mark the corners of a building after the surveyor's stakes have been removed.



offset stakes

ogee **1.** A double curve much like the letter S. **2.** The union of concave and convex lines.

ogee molding Cornice molding (may be multiple moldings) utilizing ogee and/or reverse ogee curves to provide definition.



ogee molding

ohm A unit of electrical resistance in a conductor that produces a decrease in voltage of 1 volt with a constant current of 1 ampere.

ohmmeter An instrument for measuring the electrical resistance in a conductor or appliance in ohms.

Ohm's law A scientific law stating that the current in an electrical circuit is directly proportional to the voltage and inversely proportional to the resistance. Stated as an equation:
I (current) = E (voltage) / R (resistance).

oil-based paint Commonly known as oil paint, any paint that has an oil base or binder along with coloring pigments. Becomes brittle and yellow with age.

oilborne preservative One of two general classifications for wood preservatives, the other being waterborne salts. Examples of oilborne preservatives include creosote and various chlorinated phenols, such as pentachlorophenol.

oil burner A fuel-oil-burning unit installed in a furnace or boiler.



oil burner

oiled and edge sealed A process used to resist moisture and preserve plywood concrete form panels. Oiling and sealing increases the number of times a panel can be used and makes the panel easier to release from the concrete.

oiler The second person assigned to a piece of equipment such as a crane. An oiler's principal job is to lubricate the equipment.

oil-filled transformer A transformer having its core and coils immersed in an insulating oil such as mineral oil.



oil-filled transformer

oil paint A paint with drying oil as a base, as opposed to a water base or other base.

oil separator In a refrigeration system, a device for purging the refrigerant of oil and oil vapor.

oil stain A stain, with an oil base containing dye or pigment, used to penetrate and permanently color wood or other porous materials.

oilstone A stone with a fine-grained, oil-lubricated surface used to sharpen the cutting edge of tools.

oil switch (oil-immersed switch) A switch immersed in oil or in another insulating fluid.

oil varnish A high-gloss varnish that contains a blend of drying oil and gum or resin, principally used for interior finishes.

oil/water separator A device that allows oils mixed with water to become trapped in a holding section for removal, while the water is allowed to pass through for disposal.

old wood Reused wood that has previously been worked.

olive knuckle hinge (olive butt, olive hinge) A single-pivot paumelle hinge with knuckles that join to form an oval shape.



olive knuckle hinge (olive butt, olive hinge)

OmniClass A construction classification system that includes prior systems (MasterFormat, UniFormat, and EPIC).

on center **1.** A measurement of the distance between the centers of two repeating members in a structure. **2.** A term used for defining the spacing of studs, joists, and rafters.

on-demand bond A monetary form of contractor performance assurance, typically provided by a bank, where the bond is payable to the owner simply on his demand, and usually without the owner having to provide the bank any evidence or details of the contractor's failure to perform.

one by A slang term for lumber with a nominal thickness of 1″, as in a 1″ × 3″ board.

one-hour rating A measure of fire resistance, indicating that an object can be exposed to flame for an hour without losing structural integrity or transmitting excessive heat.

one-line system A graphic representation of a power distribution system using lines and symbols to indicate its major components.

one-on-two (one-to-two) A slope in which the elevation rises one foot in two horizontal feet.

one-piece toilet A toilet whose tank and bowl were manufactured as a single fixture.

one-pipe system **1.** In drainage systems, two vertical pipes with waste and soil water flowing down the same pipe and all branches connected to the same antisiphon pipe. **2.** A heating circuit in which all the flow and return connections to the radiators come from the same pipe. The radiator at the far end is therefore much cooler than the radiator that is nearest the heat source.

one-way joist construction A concrete floor or a roof framing system with monolithic parallel joists cast with the slab. The joists are supported on girders, which in turn are supported by columns.



one-way joist construction

one-way slab A slab panel, bound on its two long sides by beams and on its two short sides by girders. The dead and live loads acting on the slab area may be considered to be entirely supported in the short or transverse direction by the beams; hence, the term *one-way*.



one-way slab

one-way system The arrangement of steel reinforcement within a slab that is designed to bend in only one direction.

on grade A concrete floor slab resting directly on the ground.

on-off sprinkler A fire safety system sprinkler that activates like a traditional sprinkler but ceases operation when room temperature reaches a safe level. On-off sprinklers can reduce the amount of water discharged during a fire, thus reducing cleanup and water damage.

opacity In painting, the ability of a paint to cover or hide the original background.

opalescent glaze A smooth surface with a milky appearance.

open assembly time The time required between the application of glue to veneer or to joints and the assembly of the pieces.

open bid An offer to perform a contract in which the bidder reserves the right to reduce his bid to compete with a lower bid.

open bidding A bidding procedure wherein bids or tenders are submitted by and received from all interested contractors, rather than from a select list of bidders privately invited to compete.

open Building Information Xchange (oBix) A standard for Web communications between building electrical and mechanical systems and applications.

open cell A cell that interconnects with other cells in foam rubber, cellular plastics, and similar materials.

open-cell foam Cellular plastic with a great many open and interconnected cells.

open-cell process A process for fixing preservative in wood under pressure. The chemical used as a preservative is retained in the cell walls only, with the cells left empty.

open circuit The absence of a direct connection between two points in an electrical network.

open construction A description of any building element that is temporarily left unfinished or exposed to allow for easy inspection.

open cut An excavation in the ground that is open to the sky at its surface, as opposed to a tunnel or horizontal mine shaft.



open cut

open defect Any hole or gap in lumber, veneer, or plywood that has not been filled and repaired.

open-end block **1.** An A-block or H-block of concrete masonry. **2.** A block of standard material and size built with recessed end webs.

open excavation Excavation in which no shores, piles, or sheeting are used to hold back the soil at the edge of the excavation.



open-end block

open-frame girder An open-web girder or truss built with verticals connected rigidly to top and bottom chords, but with no diagonals.

open-graded aggregate **1.** An aggregate that contains almost no mineral filler. **2.** A compacted aggregate with relatively large void spaces.

open grain **1.** Lumber that is not restricted by the number of rings per inch or rate of growth. **2.** Timber with a coarse texture and open pores.

open-hole inspection Inspection by a building inspector or engineer of an open excavation, to identify, based on soil type and conditions, the type of foundation that should be installed.

opening light An operable pane or sash in a window that may be open or shut, as opposed to a fixed light.

opening protective A device installed over an opening to guard it against the passage of smoke, flame, and heated gases.

opening size The size of a door opening as measured from jamb to jamb and from the threshold or floorline to the head of the frame, allowing for the size of the door and for the necessary clearance to open and close it freely.

open joint **1.** A joint in which two pieces of material that are joined together are not entirely flush. **2.** A joint that is not tight.

open loop control A hydraulic control system that does not have a direct link between the valve of the controlled variable (temperature, pressure) and the controller.

open mortise A mortise or notch that is open on three sides of the piece of timber into which it is cut.

open plan A building plan that has relatively few interior walls or partitions to subdivide areas for different uses.

open plumbing Plumbing that is exposed to view beneath its fixtures, with ventilated drains and traps readily accessible for inspection and repairs.

open riser The space between two successive treads of a staircase built without solid risers.

open-riser stair A stair built without solid risers.

open roof (open-timbered roof) A style of roof with exposed rafters, sheathing, and supporting timbers visible from beneath, and no ceiling.



open-riser stair

open shaft A vertical duct or passage in a building that is used to ventilate interior spaces, drawing in outside air from its open top.

open sheeting (open sheathing, open timbering) Vertical or horizontal supporting planks and timbers that are set along an excavated surface at intervals. Open sheeting is used whenever the ground is firm and dry enough to be effectively shored up without closed sheeting.

open shelving Shelving that is exposed to view, not concealed by doors or cabinets.

open shop (merit shop, nonunion shop) A term describing a firm whose employees are not covered by collective bargaining agreements.



open shelving

open space A term used in urban planning for parks, woods, lawns, recreation spaces, and other areas on which no building stands.

open stairway A stairway with one side or both sides open to the room in which it is located.

open string (open stringer, cut string) A stairway string with its upper edge cut or notched to conform with the treads and risers of the stairs.

open system A piping system for water or fuels in which the conduits that



open stairway

circulate the liquid are attached to an elevated tank or tower, with open vents to facilitate storage, access, and inspection.

open-timbered floor A style of floor construction in which the joists and other supporting timbers are exposed and visible from the underside.

open-timbering Description of structures built with their timberwork or wooden framework exposed to view, or without plaster or another covering; exposed timberwork.

open time The time that is required for the completion of the bond after an adhesive has been spread.

open-top mixer A mixer consisting of a trough or a segment of a cylindrical mixing compartment within which paddles or blades rotate about the horizontal axis of the trough.

open valley A type of roof valley on which shingles and slates are not applied to the intersection of two roof surfaces, leaving the underlying metal or mineral-surfaced roofing material exposed along the length of the valley.

open web A form of construction on a truss or girder in which multiple members, arranged in zigzag or crisscross patterns, are used in place of solid plates to connect the chords or flanges.

open-web steel joist A steel truss with an open web, constructed of hot-rolled structural shapes or shapes of cold-formed, light-gauge steel.



open-web steel joist

open-web studs Light-gauge steel framing construction of wire rods welded to flanges for use as backing lath.

open wiring A network of electrical wiring that is not concealed by the structure of a building, but is protected by cleats, flexible tubing, knots, and tubes, which also support its insulated conductors.

operable partition A partition made of two or more large panels suspended on a ceiling track, and sometimes also supported on a floor track, which may be opened by sliding the panels so that they overlap. The panels form a solid partition when closed.



operable partition

operable window A window that may be opened and shut to accommodate ventilation needs, as opposed to a fixed light or fixed sash.



operable window

operating engineer The worker or technician who operates heavy machinery and construction equipment.

operating expense (opex) Expenses attributed to operations, generally with a useful life of one accounting period or less. These costs are not subject to amortization or depreciation.

operating pressure The pressure registered on a gauge when a system is in normal operation.

operations control center May refer to a building area where building systems operations are managed and tracked—or to those functions themselves. Also called a *network operations center*.

opposed-blade damper A damper installed over an air passage to regulate the volume of air entering an enclosure. The damper is operated by means of two sets of blades linked so that adjacent blades can open and turn in opposite directions.

optical access control A security device, often featuring turnstiles, that allows only properly identified people to pass through an access port.

optical coatings Very thin coatings applied to glass or other transparent materials to increase the transmission of or reduce the reflection of sunlight.

optical fiber cable A medium through which light pulses are transmitted, consisting of a glass core surrounded by a protective sheath. Light pulses are introduced into the optical fiber by a laser or light-emitting diode.

optics **1.** The study of light and vision. **2.** A system of lenses, filters, prisms, or mirrors used in electronics to direct, disperse, reflect, or otherwise control light rays.

optimum moisture content The percentage or degree of moisture in soil at which the soil can be compacted to its greatest density. Optimum moisture content is used in specifications for compacting embankments.

optimum start program A building automation system that delays the startup of a heating or cooling system until the last possible moment while still maintaining building comfort levels during occupancy.

orangeburg **1.** A standard paneling pattern used in decorative plywood. Orangeburg panels have random-width grooving, with the width between each panel following a pattern of 4–8–4–7–9–6–4–6 inches. **2.** A common term for bituminous fiber drainage pipe.

orange peel (orange peeling) **1.** A surface flaw on paint, resulting from poor flow or application, that leaves the finish pocked with tiny holes like citrus skins. **2.** A wavy surface defect on porcelain enamel. **3.** A segmented hemispherical bucket that resembles a peel of half an orange, equipped with self-opening and closing capabilities and used to excavate earth. **4.** A distinctive texture applied to drywall.

orbital sander A handheld electrical sander whose base, covered with sandpaper or abrasive material, moves rapidly in an elliptical pattern and is used chiefly for coarse work.



orbital sander

order-of-magnitude estimate An estimate made without detailed engineering data based on a unit such as bells in a hospital or classrooms in a school.

ordinary-hazard contents Building contents that burn at moderate speed and give off smoke, but release no poisonous fumes or gases that would cause an explosion under fire conditions.

or-equal clause A clause within the technical specification section of the project manual that allows a contractor to propose a product or method that is equal to that which has been specified by the design professional.

organic Descriptive of materials or compounds produced from vegetable or animal sources.

organic clay Clay containing a high volume of composted animal or vegetable materials.

organic light-emitting diode (LED) An LED with an emissive layer made of organic compounds.

organic silt Silt composed in large part of organic substances.

organic soil A highly compressible soil with heavy organic content, considered generally undesirable for construction because of its inability to bear sizable loads.

oriel In architecture, a projecting bay, frequently outfitted with one or more windows, that is corbeled out from the wall of a structure or supported by brackets and that serves both to expand interior space and to enhance the appearance of the building.

oriel window A window housed in an oriel. An oriel window's projection does not extend to the ground, differentiating it from a bay window.



oriel window

orientation The siting of a building relative to compass direction and, therefore, to the sun, which can impact heating, lighting, and cooling costs.

oriented-core barrel A surveying instrument that takes and marks a core to show its orientation, and at the same time records the bearing and slope of the test hole.

oriented strand board (OSB) Panels made of narrow strands of wood fiber oriented lengthwise and crosswise in layers, with a resin binder. Depending on the resin used, OSB can be suitable for interior or exterior applications.

orifice meter A device used to measure the amount of liquid or gas flowing through a pipe.

original equipment manufacturer (OEM) A company that uses components from one or more other companies to build a product that it sells under its own company name.

O ring A round gasket used as a sealant in pipe joints and valves.

orthographic projection A method of representing the exact shape of an object by dropping perpendiculars from two or more sides of the object to planes, generally at right angles to each other. Collectively, the views on these planes describe the object completely. The term *orthogonal* is sometimes used for this system of drawing.

orthotropic A contraction of the terms *orthogonal* and *anistropic* as in the phrase "orthogonal anistropic plate"; a hypothetical plate consisting of beams and a slab acting together with different flexural rigidities in the longitudinal and transverse directions, as in a composite beam bridge.

oscillating saw A power saw with a straight blade that oscillates in short strokes.

oscillator Any electronic component that generates alternating voltage.

oscilloscope An electronic device that uses a cathode ray tube or a fluorescent-coated tube to produce visual displays corresponding to changes in electrical signals.

Ottawa sand Silica sand produced by processing material obtained by hydraulic mining of massive orthoquartzite situated in deposits near Ottawa, Illinois. The sand is composed almost entirely of naturally rounded grains of nearly pure quartz and is used in mortars for testing of hydraulic cement.



oscillating saw

outband A masonry jamb stone that serves as a stretcher and is cut to accommodate a frame.

outcrop A segment of an underground rock stratum or a formation that breaks through the surface of the earth and forms a visible protuberance.

outer string On a stairway, the string that stands away from the wall on the exposed outer edge of the stair.

outfall The final receptacle or depositing area for sewage and drainage water.

outfall sewer A sewer that receives the sewage from the collecting system and conducts it to a point of final discharge or to a disposal plant.

outgassing The driving out or freeing of gases from fabrics and building materials.

outlet **1.** The point in an electrical wiring circuit at which the current is supplied to an appliance or device. **2.** A vent or opening, principally in a parapet wall, through which rainwater is released. **3.** In a piping system, the point at which a circulated liquid is discharged.

outlet box The metal box, located at the outlet of an electrical wiring system, that serves to house one or more receptacles.

outlet ventilator An opening covered with a louvered frame, serving as an outlet from an enclosed attic space to the outside.

outline specifications A listing of shortened specification requirements (normally part of schematic or design development documents).

outlooker In roof construction, a projecting member that supports the portion of the roof beyond the face of a gable.



outlet box

out-of-plumb Deviating from a true vertical line of descent, as determined by a plumb line.

out-of-true Descriptive of a structural member that is twisted or otherwise out of alignment.

output **1.** The net volume of work produced by a system. **2.** The maximum capacity or performance that a system is capable of under normal conditions of operation.

outrigger **1.** A beam that projects beyond a wall in order to support an overhanging roof or extended floor, built in a direction perpendicular to the joists of the structural member it serves. **2.** An extended beam that supports scaffolds or hoisting tackle as work is being performed on or near a building's wall. **3.** A beam that gives stability to a crane by widening its base.

outrigger scaffold A scaffold suspended from outrigger beams or brackets fixed to the outer wall of a building.

outrigger shore (horsing) A bracket installed temporarily to support an outrigger beam or another projecting member.

outside air Fresh, unconditioned air from outside of a building.

outside-air intake (fresh-air intake) An opening or inlet to the outside of a building, through which fresh air is introduced to the boiler room or to an air-conditioning system.



outside-air intake (fresh-air intake)

outside caliper A measuring instrument set on adjustable legs and used especially to measure the outside circumference and diameter of round or cylindrical objects and structures.

outside casing (outside architrave, outside facing, outside lining, outside trim) The supporting members of the jamb or head on a cased window that face the outside and have the appearance of trim.



outside casing (outside architrave, outside facing, outside lining outside trim)

outside corner The outward-projecting corner where two walls meet.

outside corner molding A molding that covers and protects the projecting outside angle of two intersecting surfaces, as in wood veneer. *See also* **corner bead**.

outside foundation line A line that indicates where the outer side of a foundation wall is located.

outside glazing External windows or glass doors installed in a building from the outside.

outside screw and yoke A valve configuration where the valve stem, with exposed external threads supported by a yoke, indicates the open or closed position of the valve.

outside studding plate The soleplate or double top plate in the construction of a wood-frame wall or partition, usually built with stock of a size equal to the studding.

outstanding leg A leg of a structural angle member, generally unconnected to any other member.



outside studding plate

outsulation **1.** The placing of insulation to the exterior of a wall. **2.** The elimination of all thermal bridges between the inner and outer surfaces of a wall.

out-to-out In measurements, a term meaning that the dimensions are overall.



out-to-out

oven dry The condition resulting from having been dried to essentially constant weight in an oven at a temperature that has been fixed, usually 221°F and 230°F (105°C and 115°C).

oven dry wood (bone dry wood) Wood that gives off no moisture when subjected to a temperature of 212°F (100°C).

overall (overall dimension) The total external dimension of any building material, including all projections.

overbreak Excavation performed beyond the work limits established by the neat line.

overburden **1.** A mantle of soil, rock, gravel, or other earth material covering a given rock layer or bearing stratum. **2.** An unwanted top layer of soil that must be stripped away to open access to useful construction materials buried beneath it.

overcloak The portion of a metal roofing sheet that overlaps the edge of an adjacent sheet set underneath it.

overcurrent protection Safety provisions within an electrical system, such as would be furnished by ground fault circuit interrupters, that guard against damage and injury resulting from excessive current by shutting off the flow of current when it reaches a certain level.

overdesign A term used to describe adherence to structural design requirements beyond service demands, as a means of compensating for statistical variation, anticipated deficiencies, or both.

overdig The amount of clean soil that is removed below or beyond the extent of contamination at a site to make sure all waste has been taken away.

overflow (overflow pipe) **1.** A pipe installed to prevent flooding in storage tanks, fixtures, and plumbing fittings, or to remove excess water from buildings and systems. **2.** An outlet fitted to a storage tank to set the proper level of liquid and to prevent flooding.

overhand work The process by which bricklayers install brick in an external wall while standing on a scaffold or on the floor inside a building or structure.

overhang The extension of a roof or an upper story of a building beyond the wall/story situated directly beneath.

over-haul The distance excavated material is transported beyond that given as the stated hauling distance.

overhead (indirect expense, overhead expense) The costs to conduct business other than direct job costs; included in bidder's markup.

overhead balance A tense steel coil or spring installed in the head jamb of a window frame to serve as a balance for the sash.

overhead concealed closer A door closer, installed out of view in the head of the door frame, designed with a hinged arm that connects the door with the top rail of the frame.

overhead door (overhead-type garage door) A door, constructed of a single leaf or of multiple leaves, that is swung up or rolled open from the ground level and assumes a horizontal position above the entranceway it serves when opened. Commonly used as a garage door.



overhead door (overhead-type garage door)

overhead service Electric service that is delivered to a structure by lines that are above the ground.

overhead shovel A tractor loader that digs at one end, swings the bucket overhead, and dumps at the other end.

overhead traveling crane A lifting machine generally power-operated at least in its hoisting operation. The crane is carried on a horizontal girder, reaching between rails above window level at each side of a shop, and consists of a hoisting cab that can travel from end to end on the girder. The whole area between the rails can thus be traversed by the cab.

overlaid plywood (overlay) Plywood with a surfacing material added to one or both sides. The material usually provides a protective or decorative characteristic to the side, or a base for finishing. Materials used for overlays include resin-treated fiber, resin film, impregnated paper, plastics, and metal.

overlapping astragal (wraparound astragal) A molding that is attached lengthwise along the masting edge on one of a pair of doors to close the gap between them, providing a weather-resistant seal and stopping the transmission of light or smoke from one side of the doors to the other.



overlapping astragal (wraparound astragal)

overlay **1.** A layer of concrete or mortar, seldom thinner than 1″ (25 mm), placed on and usually bonded to the worn or cracked surface of a concrete slab either to restore or to improve the function of the original surface. **2.** The surfacing of a plywood face with a solid material other than wood. *See also* **overlaid plywood**.

overlay flooring Finish flooring of maple, mahogany, oak, or other hardwood cut into narrow tongue-and-groove strips.



overlay flooring

overload **1.** A load exceeding that for which the bearing structure was designed. **2.** Excess power, current, or voltage in an electrical device or circuit that is not designed to accommodate it.

overload capacity The limit of excess power, current, or voltage that an electrical device or circuit can accommodate before it is damaged.

overload relay A relay in a motor circuit that disconnects the motor from its power source if the current that feeds the motor surpasses a certain predetermined level.

overrun brake (overriding brake) A brake fitted to a towed vehicle, such as a concrete mixer to a trailer. It operates as soon as the towing truck slows down and the towed vehicle tends to push into it. Movement of the towed vehicle applies the overrun brake, making safe high-speed towing possible.

oversailing course **1.** A course of masonry that extends beyond the face of the wall in which it is set. **2.** A string course.

oversize brick A brick measuring greater than 2½″ × 3½″ × 7½″.

overstretching Stressing of tendons to a value higher than designed for the initial stress to: (a) overcome friction losses, (b) overstress the steel temporarily to reduce creep that occurs after anchorage, and (c) counteract loss of prestressing force that is caused by subsequent prestressing of other tendons.



oversailing course

overtime **1.** A term applied to the number of hours worked in excess of the normal contract for one day or one week. **2.** A term applied to the payment for this time, frequently 1½ or double the normal rate of pay.

overturning The failure of a retaining wall as the result of hydraulic or earth pressure on one side. Overturning occurs when walls are built on a narrow base or with materials too light to withstand surrounding pressure.

ovolo A convex molding approximately the shape of a quarter circle.



ovolo

owner The owner of a project, that is also party to the owner-contractor and owner-designer agreements.

owner–architect agreement Contract between owner and architect for professional design services.

owner–contractor agreement The contract formed between owner and contractor describing performance of the construction work for a project (or a portion thereof).

owner's inspector A party hired by an owner to inspect the work.

owner's representative The designated official representative of the owner (may be an architect, engineer, or contractor) to oversee a project.

oxidation **1.** The reaction of a chemical compound mixed or exposed to oxygen. **2.** Part of the asphalt-refining process, wherein oxygen is incorporated in hot, bituminous liquids by blowing it through the melted substance. **3.** The hardening of asphalt coating on a roof under exposure to sun and air.

oxidized asphalt Asphalt that has been specially treated by having air blown through it at high temperatures, making it suitable for use in roofing, hydraulics, pipe coating, membrane envelopes, and undersealing.

oxidizer An agent that, when acting on another substance, causes the attachment of an oxygen atom thereto.

oxyacetylene The mixture of oxygen and acetylene, forming a highly combustible gas used for cutting and welding metal.

oxychloride cement (sorel cement) A hard, durable cement made up of calcined magnesia and magnesium chloride, occasionally blended with fillers.

oxygen cutting A process of metal cutting in which the separation of the metal is effected by its chemical reaction with oxygen at high temperatures.

ozone Triatomic oxygen (O_3), an unstable form of oxygen that is produced by ultraviolet activity and electrical discharges and is used as an oxidizing agent, a deodorizer in air-conditioning and cold storage systems, and as an agent for stemming the growth of bacteria, fungus, and mildew. Excessive concentrations of ozone are poisonous to humans.

P

Abbreviations

p part, per, pint, pipe, pitch, pole, post, port, power

P phosphorus, pressure, pole, page, projection

P & T pressure and temperature

P & I purchase and install

P & SDS piping and surface decontamination solvents

P1E planed one edge

P1S planed one side

P1S2E planed one side and two edges

P4S planed four sides

P & T posts and timbers, pressure and temperature

PA particular average, power amplifier, preliminary assessment, professional association, purchasing agent, public address system

PAH polycyclic aromatic hydrocarbons

pan panel

Pape paperhanger

PAPI precision approach path indicator

PAPR powered air purifying respirator

PAR. paragraph, part, partition, parabolic reflector

par. parapet

par planed all round

PARP full-facepiece air purifying respirator

part, partn partition, partial

partbd particleboard

PASS passenger, passage

Patt pattern

pat. patent

PAX private automatic (telephone) exchange

Pb lead

Pb pushbutton

PC Portland cement, power connector, personal computer

pc piece

PCB polychlorinated biphenyl

PCCP prestressed concrete cylinder pipe

PCE pyrometric cone equivalent

pcf pounds per cubic foot

pckg packaged

PCM phase contract microscopy

pc/pct percent

pcs pieces

PD per diem, potential difference

pd paid

Pd palladium

PE professional engineer, probable error, plain end, polyethylene, porcelain enamel

pe plain-edged

pecky cyp pecky cypress

ped pedestal, pedestrian

pegbrd pegboard

pelec photoelectric

pend pendant

PEP Public Employment Program

per perimeter, by the, period

PERF perforate, perforated

PERM permanent

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

c16.indd 218 06/09/12 4:58 PM

PERP perpendicular

Pers personal

PESB preengineered steel building(s)

PERT project evaluation and review technique

PET precision end trimmed

PF power factor, profile

PFA pulverized fuel ash

PFD preferred

P&G post and girder

ph phase, phot

PH phase, Phillips head

pH hydrogen-ion concentration

ph phase

phos phosphate

photo photograph

Ph phenyl

PI pressure injected

PIB polyisobutylene

PID photoionization detector

pil pilaster

pile pile driver

PITI principal, interest, taxes, and insurance

piv pivoted

PIV post indicator valve

Pjtn projection

Pjtr projector

pk park, peak, plank

pkd packed

pkfr plank frame

pkg package

pkgng packaging

pkng packing

pkt pocket

pkwy parkway

pl plain, plate

plah plasterer helper

plas plaster

P/L plastic laminate

PL pile, plate, plug, power line, pipe line, private line

pl place, plate

platf platform

PLC programmable logic controller

Plf pounds per linear foot

PLG piling

plh production labor-hour

Pll pallet

PLM polarized light microscopy

plmb, plb, PLMB plumbing

plstc plastic

pluh plumber's helper

plum plumber

ply plywood

PLYWD plywood

PM post meridiem

pmh production man-hour

pmp pump(s)

PNEU pneumatic

PNL panel

Pntd painted

Pntg painting

PO purchase order

POL polish, petroleum, oil and lubricants, polished

polarogr polarographic

polthn polyethylene

polyest polyester

polyiso polyisocyanurate

polyprop polypropylene (also PP and PL)

PORC porcelain

Pord painter, ordinary

Port portable

PORT CEM portland cement

pos, POS positive

posn position

pot. potential

POTW publicly owned treatment works

pp ponderosa pine, pages, piping

PP-AC air-conditioning power panel

Ppd prepaid

PPE personal protective equipment

PPGL polished plate glass

PPH parts, per hour

ppm parts per million

PPSD package, power supply

ppt, pptn precipitate, precipitation, parts per thousand

PR payroll, pair

Prcs process(es)

Prscg processing

prcst precast

pre-assm preassembled

preb prebend

prec preceding

precp precipitation

pre-eng preengineered

prefab prefabricated

prefin prefinished

prelim preliminary

prem premium

prep preparation, prepared

press pressure

pretreat pretreated, pretreatment

prfcn purification

prgm program

pri primary

prin principal

pris prismatic

prl parallel

prod. production, product

prog progressive

proj project, projection, projecting

prom programmable read-only memory

prop property, propelled, propeller, proportional

prot protection, protective

prov provisional

prox proximity

PRP potentially responsible party, purpose

prs pairs

prt particle

PRV pressure-regulating valve, pressure relief valve

ps pieces, power shift

PS polystyrene

p.s.e. planed and square-edged

psf pounds per square foot

psi pounds per square inch

psig pounds per square inch

psj planed and square-jointed

PSP plastic sewer pipe

Pspr painter, spray

Psst painter, structural steel

PT pipe thread, potential transformer, part, point, packed tower

pt paint, pint, payment, port, point

ptfe polytetrafluoroethylene

ptg planed, tongued, and grooved

PTN partition

PTTU packed tower treatment unit

PU pickup, plutonium, ultimate load

PUD pickup and delivery

pur purlins

PUR polyurethane

PVA polyvinyl acetate

PVC polyvinyl chloride

pvmt pavement

pvntr preventer

PW paper wrapped

PWA Public Works Administration

pwr power

pwred powered

PWR pressurized water reaction

pwt pennyweight

1PH single phase

Definitions

3PH three phase

pace A landing in a staircase.

pache Color coding used on drawings to aid in quantity takeoffs for estimating.

Pacific silver fir *Ables ammilis*. This species is found in British Columbia, Washington, and Oregon. The name comes from the silvery appearance of the underside of the tree's needles. Its wood is classed in the hem-fir group.

Pacific yew *Taxus brevifolia*. This species, generally small in size, is not a commercially important tree. Its wood is heavy and strong and is used for such purposes as archery bows. Yews are usually found growing in the shade of larger trees.

pack The bundling in which shakes and shingles are shipped. In shakes, the most prevalent pack is a 9/9. This describes a bundle packed on an 18″ wide frame with nine courses, or layers, at each end. The most common pack for shingles is 20/20. Because of their smoother edges, shingles can be packed tighter than shakes, a bundle of shakes usually contains a net of about 16″ of wood across the 18″ width of the frame.



packaged air conditioner

packaged air conditioner A factory-assembled air-conditioning unit ready for installation. The unit may be mounted in a window, an opening through a wall, or on the building roof. These units may serve an individual room, a zone, or multiple zones.

packaged boiler A factory-assembled water or steam heating unit ready for installation. All components, including the boiler, burner, controls, and auxiliary equipment, are shipped as a unit.



packaged boiler

packer A device inserted into a hole in which grout is to be injected, which acts to prevent return of the grout around the injection pipe. A packer is usually an expandable device actuated mechanically, hydraulically, or pneumatically.

packer-head process A method of casting concrete pipe in a vertical position in which concrete of low water content is compacted with a revolving compaction tool.

packing **1.** Stuffing of shaped elastic material to prevent fluid leakage at a shaft, valve stem, or joint. **2.** Small stones, usually embedded in mortar, used to fill cracks between larger stones.

packing gland A protective sleeve used over cable or piping in applications where pressure or other factors pose a threat.

pack set The condition where stored cement will not flow from a container such as a rail car or silo. It is caused by interlaced particles or electrostatic charges on particles.

pad **1.** A plate or block used to spread a concentrated load over an area, such as a concrete block placed between a girder and a load-bearing wall. **2.** A shoe of a crawler-type track.

paddle wheel scraper A heavy-duty excavation machine with a wheel that scrapes soil into a large bowl section.

pad foundation A thick slab-type foundation used to support a structure or a piece of equipment.


pad foundation

padlock A unit lock with a U-shaped bar that is passed through a staple of a hasp or link in a chain, and the bar pressed into the body to lock.

pad out To add shims to framing so that a finished wall or ceiling will be correctly aligned.

pailing Sheathing constructed of vertical boards that is used in concrete formwork.

paint **1.** A mixture of a solid pigment in a liquid vehicle that dries to a protective and decorative coating. **2.** The resultant dry coating.

paint base The liquid vehicle into which a pigment is mixed to produce a paint.

paint grade A description of a wood product that is more suitable for painting than for a clear finish.

paint remover A liquid solvent applied to dry paint to soften it for removal by scraping or brushing.

paint roller A tube with a fiber surface that is mounted on a roller and handle, and used to apply paint.

paint system A specific combination of paints applied in sequence. A paint system consists of a combination of some of the following coats: sealer or primer, stain, filler, undercoat, and one or more topcoats.

paint thinner A liquid compatible with the vehicle of a paint, used to make a paint flow easier. Paint thinner lowers the viscosity of paints, adhesives, etc.

pale (paling) **1.** One of the stakes in a palisade. **2.** A picket in a fence.


pale (paling)

palisade A fence of poles driven into the ground and pointed at the top.

palladian window A tripartite or three-light window that features a central arched window with balanced rectangular lights on each side.


palladian window

pallet **1.** A platform used for stacking material and arranged to be handled by a forklift truck. **2.** A wood insert in a brick wall used for support of a surface system.

palletized A term used frequently in the shingle and shake industry. Both items are often shipped on pallets from the mill for ease in handling while in transit. These shipments are referred to as palletized loads.

palm sander A handheld electrical sander with a vibrating or orbital base to which sandpaper is attached for finer sanding.

pan **1.** A prefabricated form unit used in concrete joist floor construction. **2.** A container that receives particles passing the finest sieve during mechanical analysis of granular materials. **3.** A structural panel.


pan

pan and roll roofing tile A roofing tile system consisting of two types of tile: A flat or slightly curved tile with a flange on each side, and curved tile that fits the flanges and closes the joints.

pan construction A type of concrete floor or roof in which pan forms are used to create intersecting ribs, resulting in a waffle-like undersurface.

pane A flat sheet of glass installed in a window or door. The installed sheet is also referred to as a light.

panel **1.** A section of form sheathing, constructed from boards, plywood, metal sheets, etc., that can be erected and stripped as a unit. **2.** A concrete member, usually precast, rectangular in shape, and relatively thin with respect to other dimensions. **3.** A sheet of plywood, particleboard, or other similar product, usually of a standard size, such as 4′ × 8′.

panelboard A board on which electric components and/or controls are mounted.


panelboard

panel box A box in which electric switches and fuses are mounted.

panel clip A specially shaped metal device used in joining panels in roof construction. The clip substitutes for lumber blocking and helps to spread the load from one panel to the next one.

panel construction A general term used to describe construction where building components are assembled elsewhere before being brought to a site for placement.

panel door A door constructed with panels, usually shaped to pattern, installed between the stiles and rails, which form the outside frame of the door.



panel door

paneling The material used to cover an interior wall. Paneling may be made from a 4′ × 4′ *select* milled to a pattern and may be either hardwood or softwood plywood, often prefinished or overlaid with a decorative finish, or hardboard, and usually prefinished.

panel insert A metal unit used instead of glass in a panel door.

panel molding A decorative molding, originally used to trim raised panel wall construction.



paneling

panel point Point of intersection of the members of a truss.

panel product Any of a variety of wood products such as plywood, particleboard, hardboard, and waferboard, sold in sheets or panels. Although sizes vary, the board size for most panel products is 4′ × 8′.

panel strip **1.** A strip extending across the length or width of a flat slab for design purposes. **2.** A narrow piece of wood or metal used to hide a joint between two sheathing boards forming a panel.

pan form stair A metal stair assembly with metal sheet pans at the treads to hold precast or cast-in-place masonry or stone treads.

pan fraction **1.** The reported results of mechanical analysis of granular materials. **2.** The weight of the material retained on any one sieve divided by the initial weight of the sample.

pan head A head of a screw or rivet shaped like a truncated cone.

panic bolt The bolt in panic hardware that is released by pressure on a horizontal bar.

panic exit hardware, mortise type Panic exit hardware in which the lock mechanism is concealed within the door or set into a rectangular cavity (called a *mortise*) that has been cut in the edge of the door.

panic exit hardware, rim type Panic exit hardware in which the lock mechanism is located on the inside face of the door.

panic exit hardware, vertical rod type Panic exit hardware with latches at the top and/or bottom of the door. The latches are connected to a vertical rod that, in turn, is connected to a crossbar. In an emergency, the latches are released simply by pressing the crossbar.

panic hardware A door-locking assembly that can be released quickly by pressure on a horizontal bar. Panic hardware is required by building codes on certain exits.



panic hardware

pants Steel plates attached to the hammer of a pile driver to aid in driving sheet piling.

pan-type humidifier A pan with water placed in a flow of air to increase humidity. A heating element may be placed in the pan for greater evaporation.

paper-backed lath Any lath with building paper attached. A paper-backed lath serves as formwork and reinforcing for a concrete floor over open web joists.

paperboard (pasteboard, cardboard) A stiff cardboard composed of layers of paper, or paper pulp, compressed into a sheet.

paper form A heavy paper mold used for casting concrete columns and other structural shapes.



paper form

paperhanger A tradesperson experienced and trained in preparing surfaces for and hanging wall coverings.

paper overlay Paper prepared for application to the face of a panel after first being printed in four colors with the grain and color of a more valuable wood, or in a decorative design.

paper sheathing Felt or heavy paper sheets used as an air and/or vapor barrier in walls.



paper sheathing

papreg A paper product produced by impregnating sheets of high-strength paper with synthetic resin and then laminating the sheets to form a dense, moisture-resistant product.

parabolic aluminized reflector (PAR) lamp A lamp that utilizes a light reflector shaped so as to project light from a small source in an approximately parallel beam, as in a spotlight.

parabolic luminaire A fluorescent fixture with a louver of parabolic-shaped baffles that provide excellent light control and reduce glare.

paraform Paraformaldehyde, an additive used with wood flour as a hardener in adhesives. *See also* **resorcinal resin adhesive**.

parallel **1.** The condition in which two lines or planes are an equal distance apart at all points. **2.** Electric blasting caps arranged so that the firing current passes through all of them at the same time.

parallel activities Two or more activities than can be done at the same time. Allows a project to be completed faster than if activities were arranged sequentially.*

parallel chord truss An engineered structural component, composed of a combination of members, with its top and bottom members positioned flat and parallel to each other.

parallel circuit An electrical circuit that has at least two paths for electricity to flow, with loads parallel to each other as a result.

parallel connection A connection at which a flow is diverted to two or more parallel conduits.

parallel flow An arrangement of a heat exchanger where the hot and cold materials enter at the same end and flow to the exit.

parallel-laminated veneer A product in which the veneers have been laminated with their grains parallel to one another. Parallel laminated veneer is used in furniture and cabinetry to provide flexibility over curved surfaces, and in the production of laminated veneer structural products.

parallel siding (square-edged siding) **1.** Siding that is not beveled. **2.** Siding having edges of the same thickness.

parallel welding The joining of metal parts by fusion, with the electric current that produces the weld divided and routed through the electrode and metal along similar paths.

parallel-wire unit A posttensioning tendon composed of a number of wires or strands that are approximately parallel.

parameter A variable in a mathematical expression.

parametric estimate Estimating algorithms or cost estimating relationships that are highly probabilistic in nature (i.e., the parameters or quantification inputs to the algorithm tend to be abstractions of the scope). Typical parametric algorithms include, but are not limited to, factoring techniques, gross unit costs, and cost models (i.e., algorithms intended to replicate the cost performance of a process of system).*

parapet **1.** That part of a wall that extends above the roof level. **2.** A low wall along the top of a dam.



parapet

parapet gutter A gutter built or placed behind a parapet.

paretta Cast masonry with a surface of protruding pebbles.

parge coat A coat of masonry cement applied to masonry for resistance to penetration of moisture.

pargetting **1.** Lining of a flue to aid in smooth flow and increase fire resistance. **2.** Application of a dampproofing masonry cement. **3.** Ornamental, often elaborate, facing for plaster walls.



pargetting

paring chisel A long-handled chisel used to shape wood by hand without the use of a mallet.

paring gouge A long, thin woodworking gouge, the cutting edge of which is beveled on the concave side.

parliament hinge An H-shaped hinge.

parquet flooring A floor covering composed of small pieces of wood, usually forming a geometric design.



parquet flooring

parsing A thin coat of plaster or masonry cement.

partial cover plate A cover plate attached to the flange of a girder but not extending the full length of the girder.

partially air-dried (PAD) Wood seasoned to some extent by exposure to the atmosphere without artificial heat, but still considered green or unseasoned.

partial occupancy An owner's occupation and use of a project before final completion.

partial prestressing Prestressing to a stress level such that, under design loads, tensile stresses exist in the precompressed tensile zone of the prestressed member.

partial release Release in a prestressed concrete member of a portion of the total prestress initially held wholly in the prestressed reinforcement.

particle size **1.** Minimum particle diameter that will be removed by an air filter. **2.** Diameter of a pigment particle in paint. **3.** Diameter of a grain of sand in a mechanical analysis test.

particle size distribution A tabulation of the result of mechanical analysis expressed as the percentage by weight passing through each of a series of sieves.

particleboard A generic term used to describe panel products made from discrete particles of wood or other ligno-cellulosic material rather than from fibers. The wood particles are mixed with resins and formed into a solid board under heat and pressure.

parting bead A narrow strip between the upper and lower sashes in a double-hung window frame.

parting slip A thin piece of wood in the cased frame of a sash window separating the sash weights. Also called a *parting stop*.

parting tool A turning tool with a narrow blade and V-shaped gouge used for cutting recesses or grooves in wood.

partition A dividing wall within a building, usually non-load-bearing.



partition

partition block Light concrete masonry unit with a nominal thickness of 4″ to 6″.



partition block

partition plate The top horizontal member of a partition, which may support joists or rafters.

partition stud A steel or wood upright in a partition.

partition tile A hollow, clay unit for use in interior partitions. The surface of a partition tile is often grooved for plastering.

partnering A set of collaborative processes (as opposed to a relationship only); a commitment to achieve mutually identified objectives between two (or more) organizations, based on cooperation, open communication, and heightened effectiveness through continuous improvement.

partnership The joining of two or more individuals for a business purpose whereby profits and liabilities are shared.

party wall A common wall between two living units.

Pascal's law A principle that states that pressure applied to a confined fluid at any point is transmitted equally in all directions.

pass **1.** One-direction application of a substance, such as paint or a layer of shotcrete, placed in one movement over the field of operation. **2.** A single progression of a welding operation along a joint, resulting in a weld bead.

passage (passageway) A horizontal space for moving from one area of a building to another.

passenger elevator An elevator mainly used for people.

passive solar energy system A solar energy system that collects and distributes thermal energy through a structure via natural means, without using pumps or fans.

pass-through An opening in a partition for passing objects between adjacent areas.

pass-through clause Contract language that allows a general contractor to pass risk and responsibilities to subcontractors by reference.

paste content (of concrete) Proportional volume of cement paste in concrete, mortar, or the like, expressed as volume percent of the entire mixture.

paste paint A pastelike mixture of pigment and solvent, usually requiring additional solvent for use.

pat A specimen of neat cement paste about 3″ (76 mm) in diameter and ½″ (13 mm) in thickness at the center, and tapering into a thin edge on a flat glass plate for indicating setting time.

patch **1.** A piece of wood or synthetic material used to fill defects in the plies of plywood. Also called a *plug*. **2.** A compound used in stonemasonry to replace chips and broken corners or edges in fabricated pieces of cut stone or to fill natural voids. The patch is applied in plastic form.

patch board (patch panel) A board with jacks and plugs for terminals of electric circuits. The circuits may be temporarily interconnected by patch cords.

patch gun **1.** A hand tool that "shoots" a premixed material for patching and repairing exterior finishes like stucco. **2.** A hand tool used to apply joint compound to drywall.

patent defect A defect present in materials, equipment, or completed work detectable by reasonably careful observation. A patent defect is distinguished from a latent defect, which could not be discovered by reasonable observation.

patent glazing Any of a number of devices, usually preformed neoprene gaskets, for securing glass in frames without putty.

patent-hammered Stonework finish applied to the face of building stone.

patent knotting A solution of shellac and benzine or similar solvent used to seal knots in wood.

patent stone (artificial soil) Stone chips embedded in a binder of mortar, cement, or plaster. The surface may be ground and/or polished.

patina Color and texture added to a surface as a result of oxidation or use, such as the green coating on copper or its alloys.

patten The base of a column.

pattern **1.** A plan or model to be a guide in making objects. **2.** A form used to shape the interior of a mold.

pattern cracking Fine openings on concrete surfaces in the form of a pattern, resulting from a decrease in volume of the material near the surface and/or an increase in volume of the material below the surface.

patternmaker's saw A small hand saw with fine teeth used to make intricate cuts.

pattern staining Dark areas on finished plaster, particularly on the interior of external walls, which are caused by different thermal conductance of backings.

paumelle A door hinge with a single joint, usually of modern design.



paumelle

paved invert In piping, the lower portion of a corrugated metal pipe whose corrugations have been filled with smooth bituminous material to resist scour and erosion and improve flow.

pavement base The layer of a pavement immediately below the surfacing material and above the subbase.

pavement, concrete A layer of concrete over roads, sidewalks, canals, playgrounds, and those areas used for storage or parking.



pavement, concrete

pavement saw A self-propelled machine with a circular saw blade for cutting control joints.

pavement sealer A bituminous coating used to seal and renew the surface of asphalt paving.

paver **1.** A block or tile used as a wearing surface. **2.** A machine that places concrete pavements.



pavement saw

pavilion roof **1.** A roof composed of equally hipped areas. **2.** A pyramid-shaped roof.

paving The hard surface covering of areas such as walks, roadways, ramps, waterways, parking areas, and airport runways.

paving aggregate The various solid materials, such as sand, gravel, or slag, used in construction of a pavement.

paving asphalt A sticky residue from the refining of crude oil. Paving asphalt is used in built-up roofing systems, as the binder in asphaltic concrete, or as a waterproofing agent.

paving breaker (chipper) A handheld, pneumatic tool for cutting pavements.

paving brick A vitrified clay brick with good resistance to abrasion.

paving unit A fabricated or shaped unit used in a pavement surface.

payback method A technique of economic evaluation that determines the time required for the cumulative benefits from an investment to recover the investment cost and other accrued costs.*

payback period (PB) Measures the length of time until accumulated savings are sufficient to pay back the initial cost. Discounted payback (DPB) takes into account the time value of money by using time-adjusted cash flows. If the discount rate is assumed to be zero, the method is called simple payback (SPB).

payment bond A form of security purchased by the contractor from a surety, which is provided to guarantee that the contractor will pay all costs of labor, materials, and other services related to the project for which he is responsible under the contract for construction.

payment schedule An arrangement for payments to the contractor, typically based on amounts of work completed.

payments withheld A provision of AIA General Conditions of the Contract for Construction, which provides that the owner may withhold payments to the contractor if, in the opinion of the design professional, the work falls behind the schedule of construction, or in the event that the work deviates from the provisions of the contract documents.

payout time The time required to recover the original fixed investment from profit and depreciation. Most recent practice is to base payout time on an actual sales projection.*

p bar A heavy steel bar, shaped like a chisel at one end, used for prying.

pea gravel Screened gravel, most of the particles of which will pass a ⅜″ (9.5 mm) sieve and be retained on a No. 4 (4.75 mm) sieve.

peak joint The joint of a roof truss that is at the ridge.



peak joint

peak levels In measuring ambient air contamination, above average levels of ambient contamination due to the sudden release of a contaminant into the air. Usually occurs for a short period of time immediately following the release.

peak load The maximum demand or design load of a device, system, or structure over a designated time period.

peak-load controller An electrical controller used to limit the maximum power demands to a device or system.

peat Fibrous organic matter in various stages of decomposition, found in swamps and bogs, and used to enrich soil for plantings.

peavey A long-shafted tool with a hook that is used by loggers to roll logs, break jams, pry rocks, tighten chains, and push over trees.

pebble dash (rock dash) An exterior finish in which crushed rock or pebbles are embedded in mortar, plaster or stucco.

pecan *Carya illinoensis*. One of the largest native hickories, its wood is used in furniture and flooring.

peck **1.** Channeled or pitted areas or pockets sometimes found in cedar or cypress, the decay resulting from fungus in isolated spots. **2.** A dry measure equal to 2 gallons.

pedestal **1.** An upright compression member whose height does not exceed three times its average least lateral dimension, such as a short pier or plinth used as the base for a column.**2.** Utility boxes that house connections and/or switches for telephone, electrical, or cable television service.



pedestal

pedestal floor A flooring system that is elevated from the subfloor to accommodate cabling, piping, ductwork, or other building systems.

P

pedestal lavatory Lavatory supported by a pedestal rather than wall hung. Supply and waste lines are enclosed by the pedestal.

pedestal pile A cast-in-place concrete pile constructed so that concrete is forced out into a widened bulb or pedestal shape at the foot of the pipe, which forms the pile.

pedestrian control device Any device, especially turnstiles, but including gates, railings, or posts, used to control the movement of pedestrians.

pediment A decorative unit, often triangular in shape, above a doorway.



pedestal pile



pediment

peel To produce veneer from a log through rotary cutting.

peeler A log from which veneer is peeled on a lathe, for the production of plywood. A peeler-grade log most frequently is from an old-growth tree, with a high proportion of clear wood.

peeling **1.** A process in which thin flakes of mortar are broken away from a concrete surface, such as by deterioration or by adherence of surface mortar to forms as they are removed. **2.** Separation of paint or other coating from the surface to which it was applied, often caused by poor adhesion due to inadequate pre-painting preparation, or effects of moisture.

peen The end of a hammer, other than a claw hammer, opposite the hammering face. A peen may be pointed or ball- or cone-shaped. A peen is used for chipping, indenting, and metalworking.

peen-coated nail A mechanically galvanized nail coated by tumbling in a container with zinc dust and glass balls.

peg **1.** A pointed pin of wood used to fasten wood members together. **2.** A short, pointed wooden stick used as a marker by surveyors.

peg-and-plank A rustic wood floor of planks and exposed pegs.

pegboard A hard fiberboard sheet, usually ¼″ thick with regular rows of holes for attaching pegs or hooks.

pelmet A valance or cornice, sometimes decorative, at the head of a window to conceal a drapery track or other fittings.

pelmet board A board at the head of a window, acting as a pelmet.

pelmet lighting Lighting furnished by sources that are concealed by a pelmet.

penalty clause A clause in a contract specifying a charge against the contractor for failure to complete the work by a prearranged date.

penciling Painting mortar joints, usually white.

pencil rod Plain metal rod of about ¼″ (6 mm) diameter.

pendant **1.** An electric device suspended from overhead. **2.** A suspended ornament in Gothic architecture, used in vaults and timber roofs.

pendant luminaire A suspended lighting unit.



pendant luminaire

pendent sprinkler A fire safety system sprinkler with a head that features a deflector plate that directs discharged water downward.

penetrant An additive that increases a liquid's ability to penetrate a surface or enter the pores of a substrate. Penetrants are typically used as wetting agents.

penetrating finish A low-viscosity oil or varnish that penetrates into wood with only a film of material at the surface.

penetration **1.** A test of the hardness of an asphalt utilizing a weighted needle at standard conditions. **2.** The cut-off depth of piles or sheet piling. **3.** The depth of a caisson below ground level. **4.** The intersection of two surfaces of vaulting.

penetration macadam Pavement made from layers of coarse, open-graded aggregate (crushed stone, slag, or gravel) followed by the spray application and penetration of emulsified asphalt.

penetration test A test to estimate the bearing capacity of soil by recording the number of blows required to drive a standard tool into soil.

penitent post A short post placed against the wall and supporting an arch or tie beam.

penny A measure of the length of a nail. The larger the number is, the longer the nail.

pentachlorophenol A chemical used in wood preserving, usually applied under pressure so that it will penetrate the wood.

percentage fee A fee paid to the contractor or the architect that is a percentage of the total construction cost.

percentage humidity The ratio, expressed as a percentage, of the weight of water vapor in a pound of dry air to the weight of water vapor if the same weight of air were saturated.

percentage void The ratio, expressed as a percentage, of the volume of voids to the gross volume of material.

percent complete An estimate of the percentage complete for an activity as of a particular data date. Percent complete may be based on time expended, cost or resources employed, or measurement of work in place.*

percent fines **1.** Amount, expressed as a percentage, of material in aggregate finer than a given sieve, usually the No. 200 sieve. **2.** The amount of fine aggregate in a concrete mixture expressed as a percent by absolute volume of the total amount of aggregate.

c16.indd 226 06/09/12 4:58 PM

percent saturation The ratio, expressed as a percentage, of the volume of water in a soil sample to the volume of voids.

percolation The movement of a fluid through a soil.

percolation test A test to estimate the rate at which a soil will absorb waste fluids, performed by measuring the rate (percolation rate) at which the water level drops in a hole full of water.

percussion drill A pneumatic or electric tool that drills holes by applying a rapid series of blows.



percussion drill

perfections Shingles 18″ long and 0.45″ thick at the butt.

perforated drain A subsurface draining system that uses pipes with holes in the bottom to allow water or other liquid to percolate into the soil.

perforated facing A perforated sheet or board used as a finished surface and allowing a fraction of sound to penetrate the surface to an absorbent layer.

perforated metal pan A unit that forms the exposed surface of a type of acoustical ceiling. The perforated pan contains a sound-absorbent material, usually in pad form.

perforated tape A special paper tape used to reinforce the material covering joints between gypsum boards.

performance **1.** A term meaning fulfillment of a promise made by one party to a contract or agreement in return for compensation. **2.** The manner in which or the efficiency with which something acts or reacts in the manner in which it is intended.

performance-based fee A fee structure that rewards a consultant's effort to meet or exceed the clients goals, such as minimizing a project's life-cycle cost. The designer's fee is based on a measurement, such as energy use or operating cost of the completed facility.

performance bond **1.** A guarantee that a contractor will perform a job according to the terms of the contract, or the bond will be forfeited. **2.** A bond procured by the contractor which shows that a surety guarantees (to the owner) that the work will be performed in accordance with the contract documents. Unless prohibited by statute, the performance bond can be combined with the labor and material payment bond. *See also* **surety bond**.

performance measurement baseline The time-phased budget plan against which contract performance is measured. It is formed by the budgets assigned to scheduled work elements and the applicable indirect budgets.*

performance measurement system **1.** An organization's defined processes for monitoring and updating project and/or organization progress at a detailed level over time. **2.** A quantitative tool (for example, rate, ratio, index, percentage) that provides an indication of an organization's performance in relation to a specified process or outcome.*

performance specification A description of the desired results or performance of a product, material, assembly, or piece of equipment with criteria for verifying compliance.

perimeter drain A drainage system around a house usually comprised of perforated plastic pipe.

perimeter grouting Injection of grout, usually at relatively low pressure, around the periphery of an area that is subsequently to be grouted at greater pressure. Perimeter grouting is intended to confine subsequent grout injection within the perimeter.

perimeter heating system A system of warm-air heating in which outlets for air ducts are located near the outside walls of rooms and are close to the floor. The returns are near the ceiling.

perimeter installation A method of floor installation where adhesive is only used along the outside edges and seams of the flooring material, allowing for faster installations and easier repairs

perimeter isolation A method of installing a building material, such as concrete or wallboard, so that it is separated from structural elements. This isolation helps reduce the cracking that can result when structural members shift. Perimeter isolation is also used as a sound control measure.

perlite A volcanic glass having a perlitic structure, usually having a higher water content than obsidian when expanded by heating. Perlite is used as a lightweight aggregate in concretes, mortars, and plasters.

perlite composite board A rigid insulation board formed of expanded perlite, fibers, and a sizing material. Often recommended as a product for sustainable design because it is commonly manufactured with postconsumer paper.

perm A unit of water vapor transmission through a material, expressed in grains of vapor per hour per inch of mercury pressure difference.

permanent bracing Bracing that forms part of a structure's resistance to horizontal loads. Permanent bracing may also function as erection bracing.

permanent form Any form that remains in place after the concrete has developed its design strength. A permanent form may or may not become an integral part of the structure.

permanent load The load, including a dead load or any fixed load, that is constant through the life of a structure.

permanent shore An upright used to support dead loads during alterations to a structure and left in place.

permeable paving Paving materials that allow rainwater to pass through into the ground to replenish the water table.

permeability **1.** The property of a material that permits passage of water vapor. **2.** The property of soil that permits the flow of water.

permeance The resistance, measured in perms, to the flow of water vapor through a given thickness of material.

permit A document issued by a governing authority such as a building inspector approving specific construction. Among the types of permits are the building permit, demolition, zoning, grading, septic, plumbing and electrical permits.

perpend **1.** A stone that extends completely through a wall and is exposed on each side of the wall. **2.** A joint between masonry units.

personal protective equipment (PPE) Special clothing, devices and equipment worn by workers for protection against documented or potential site hazards. Examples include respirators and eye, ear and skin protection. *See also* **level A–D clothing**.

PERT (project evaluation and review technique) Along with CPM, PERT is a probabilistic technique for planning and evaluating progress of complex programs. Attempts to determine the time required to complete each element in terms of pessimistic, optimistic, and best-guess estimates.*

pervious soil A soil that allows relatively free passage of water.

pessimistic time estimate The maximum time required for an activity under adverse conditions. It is generally held that an activity would have no more than one chance in a hundred of exceeding this amount of time.*

petcock A small valve installed on equipment or piping for drainage of liquids or air.



petcock

petroleum asphalt Asphalt refined directly from petroleum, as opposed to asphalt from natural deposits.

petroleum hydrocarbon Petroleum products are complex mixtures of hydrocarbon compounds, ranging from light, volatile, compounds to heavy, long-chained, branched compounds. The composition of petroleum hydrocarbons varies depending upon the source of the crude oil and the refining practices used. A number of solvents are refined from cured petroleum and used to lower the viscosity of oils and resins.

petroleum spirit A thinner, for paints and varnishes, having a low-aromatic hydrocarbon content, obtained in petroleum distillation.

petrology The science of rocks, dealing with their origin, structure, composition, etc., from all aspects and in all relations.

pew A benchlike seat used in a church.

pH A measure of hydrogen ion concentration expressed as an exponential number used to determine the relative acidity or alkalinity of a liquid.

phase A major period in the life of an asset or project. A phase may encompass several stages.

phase converter An electrical device that converts single-phase power to the smooth, continuous and universally adaptable three-phase power.

phasing Working on a construction project in parts and at specified intervals. Usually phasing is required when construction activity is not permitted at certain locations or on particular dates during the project.

phenol A product of the petroleum industry used in the production of phenolic resin, epoxy resins, plasters, and exterior plywood glue. Phenol is made from benzene. It exists naturally in coal tar and wood tar. However, phenol from these sources is rarely used in the production of glue.

phenolic insulation A rigid, closed cell foam insulation product made with phenolic plastics. No longer used in the roofing industry because when wet it will chemically attack steel decks. However, it has not posed problems when used over concrete or wood decks, or gypsum boards sealed with a vapor retarder.

phenolic resin glue An adhesive used for bonding exterior plywood. Phenolic resin is produced in a reaction between phenol and formaldehyde. An extender is usually added to the phenolic resin prior to use in the plywood-manufacturing process.

Philadelphia leveling rod A leveling rod in two sliding parts with color-coded graduations. The rod can be used as a self-reading leveling rod.

Philippine mahogany The wood of several types of trees found in the Philippines. The wood resembles mahogany in grain. Density varies from very light to quite heavy. The heavier, darker woods are durable and strong and used like mahogany. The lighter-weight colored woods are used for interior plywood.

Phillips head screw A screw with a recessed head and an X-shaped driving indentation.

phosphatizing A chemical treatment process used on steel to prevent corrosion.

phosphor mercury-vapor lamp A high-pressure mercury-vapor lamp with a phosphor-coated glass cover over the lamp proper. The phosphor in the cover adds colors not generated by the lamp.

photoelectric cell An electronic device for measuring illumination level or detecting interruption of a light beam. The electric output or resistance of the device varies according to the illumination.

photoelectric control An electric control that responds to a change in incident light.

photometer A device that measures luminous intensity, light distribution, color, and other qualities of a luminaire.

photo-oxidation Oxidation resulting from exposure to sunlight.

photovoltaics (PV) Devices that convert sunlight directly into electricity. PVs generate power without noise, pollution, or fuel consumption, and are useful where utility power is not available, reliable, or convenient.

physical percentage complete Percentage of work content of an activity or project achieved as of a particular date. Physical completion of any activity represents the most accurate, unbiased measure or appraisal in accordance with the accept method of measurement, tempered with judgment and experience. Physical completion is not linked to work hours budgeted or expended.*

physical progress The status of a task, activity, or discipline based on preestablished guidelines related to the amount or extent of work completed.*

physical restraint A situation in which a physical activity or work item must be completed before the next activity or work items in the sequence can begin (e.g., concrete must harden before removing formwork).*

phytoremediation A low-cost option for site cleanup when the site has low levels of contamination that are widely dispersed. Phytoremediation (a subset of bioremediation) uses plants to break down or uptake contaminants.

piano hinge A continuous strip hinge used in falling doors, etc.

pick A hand tool, consisting of a steel head pointed at one or both ends and mounted on a wooden handle, for loosening and breaking up compacted soil or rock.

picked finish A surface finish for stonemasonry in which the surface is covered with small pits made by striking it perpendicularly with a pick or chisel.

picket A sharpened or pointed stake, post, or pale, usually used as fencing.

picket fence A fence consisting of vertical piles, often sharpened at the upper end, supported by horizontal rails.

pickled A metal surface that has been treated with strong oxidizing agents to remove scale and provide a tough oxide film.

pickup **1.** The amount by which an estimate for an item is higher than the actual cost; savings; underrun. **2.** Unwanted adherence of solids to the open surface of a sealant. **3.** Common term for a small open-body truck with a half-ton to one-ton capacity.

pickup load The heat consumption required to bring piping and radiators to their operating temperature when a heating system is first turned on.

picture window A large window, usually a fixed sheet of plate or insulating glass.


picture window

pieced timber **1.** A timber made from two or more pieces of timber fitted together. **2.** A damaged timber patched with a fitted piece of wood.

pien check In a stair constructed of stone, a rabbet cut in the front edge of a tread that fits over the riser below it.

pier **1.** A short column to support a concentrated load. **2.** Isolated foundation member of plain or reinforced concrete. **3.** Means of support for bridge spans or the ends of a lintel or arch. **4.** A marine dock or breakwater structure.

pierced louver A louver set in the face sheets or panels of a door.


pierced louver

pigment A coloring matter, usually in the form of an insoluble fine powder, dispersed in a liquid vehicle to make paint.

pigment/binder ratio Amount of pigment in paint relative to the amount of binding agent.

pig spout A sheet metal flashing system that directs water out through the face of a gutter instead of through a downspout.

pigtail **1.** An antisiphon piping device used to protect a pressure gauge. **2.** A flexible conductor attached to an electric component or appliance to connect it to a circuit.

pigtail splice A connection of two electric conductors, made by placing the ends of the conductors side by side and twisting the ends about each other.

pike pole A long pole, with a spear-type point and a hook on one end, used to move logs around in a mill pond.

pilaster A column built within a wall, usually projecting beyond the wall.


pilaster

pilaster block Concrete masonry units designed to form plain or reinforced concrete masonry pilasters of the projecting type.

pile A slender timber, concrete, or steel structural element, driven, jetted, or otherwise embedded on end in the ground for the purpose of supporting a load.

pile-bearing capacity The load on a pile or group of piles that will theoretically produce failure if exceeded.


pile

pile bent Two or more piles driven in a row transverse to the long dimension of the structure and fastened together by capping and (sometimes) bracing.

pile cap **1.** A structural member placed on, and usually fastened to, the top of a pile or a group of piles and used to transmit loads into the pile or group of piles and, in the case of a group, to connect them into a bent. Also known as a *rider cap* or *girder*. **2.** A masonry, timber, or concrete footing resting on a group of piles.



pile cap

pile core The mandrel used to drive the shell of a cast-in-place concrete pile.

pile driver A machine for driving piles, usually by repeated blows, from a free-falling or driven hammer. A pile driver consists of a framework for holding and guiding the pile, a hammer, and a mobile plant to provide power.

pile extractor A machine for loosening piles in the ground by exerting upward striking blows. The actual removal is by a crane.

pile friction The friction forces on an embedded pile limited by the adhesion between soil and pile and/or the shear strength of the adjacent soil.

pile hammer A weight that strikes a pile to drive it into the ground. The weight may fall freely or be assisted by steam or air pressure.

pile height The height of piles in a carpet measured from the top surface of the backing to the top of the pile.



pile load test A static load test of a pile or group of piles used to establish an allowable load. The applied load is usually 150% to 200% of the allowable load.

pile point Hardened steel tip affixed to the end of a pile to reduce damage.

pile shoe A pointed or rounded device on the foot of a pile to protect the pile while driving.


pile shoe

pile tolerance The permitted deviation of a pile in the horizontal and vertical planes.

pillar **1.** A post or column that supports part of a structure. **2.** A column of ore left in a mine to support the ground overhead.

pilot boring A preliminary boring or series of borings to determine the nature of the soil in which a foundation will be dug or a tunnel driven.

pilot hole A guiding hole for a nail or screws, or for drilling a larger hole.

pilot light **1.** A small, constantly burning flame used as an ignition source in a gas burner. **2.** A low-wattage light used to indicate that an electric circuit, control, or device is active.

pilot nail A temporary nail used to align boards until permanent nails are driven.

pin A peg or bolt of some rigid material used to connect or fasten members.

pincers A joined tool with a pair of jaws and handles used to grip an object.

pinch bar A steel bar with a chisel point at one end used as a lever for lifting or moving heavy objects.

pin connection In structural analysis, any member connection designed to transfer axial and shear forces, but not moments.

pine oil A high-boiling-point essential oil obtained from the steam distillation of pine needles, twigs, etc. Used industrially as a solvent. Used in paint to provide good flow properties and as an antiskinning agent.

pine shingles Shingles made from pine wood.

pine tar A blackish-brown liquid distilled from pine wood. Pine tar is used as an antiseptic externally and an expectorant internally and also to make the grips of tools sticky.

pin hinge A butt hinge with a pin for the pivot.



pin hinge

pinhole (pin hole) **1.** In wood, a small, round hole made by a beetle or worm in the standing timber. **2.** In plaster, a surface defect caused by trapped air. **3.** In painted surfaces, a defect usually caused by impurities or dirt. **4.** In glazed ceramic surfaces, a small round hole.

pin knot A knot with a diameter no larger than ½″.

pinnacle **1.** The highest point. **2.** A turret or elevated portion of a building. **3.** A small ornamental body or shaft terminated by a cone or pyramid.

pintle A vertical pin fastened at the bottom and serving as a center of rotation.

pin tumbler A lock mechanism having a series of small pins that must be properly aligned by a key to open.

pipe **1.** A hollow cylinder or tube for conveyance of a fluid. **2.** From ASTM B 251–557: Seamless tube conforming to the particular dimensions commonly know as “standard pipe size.”



pipe

pipe bend (pipe elbow) A pipe fitting used to change direction.



pipe bend (pipe elbow)

pipe chase A vertical space in a building reserved for vertical runs of pipe.

pipe column A column made of steel pipe and often filled with concrete.

pipe coupling A fitting used to connect two lengths of pipe in a direct line.

pipe covering Any wrapping on a pipe that acts as thermal insulation and/or a vapor barrier.

pipe cross A fitting used to connect four lengths of pipe in the same plane with all lengths at right angles to each other.

pipe cutter A hand tool for cutting pipe or tubing, consisting of a frame with a cutting wheel and drive wheels. Cutting is accomplished by forcing the cutting wheel into the pipe material and rotating the tool around the pipe a number of times.



pipe cutter

pipe die An adjustable tool for cutting threads on or in a pipe.

pipe fitting Bends, tees, and other connectors used in assembling pipe.

pipe gasket A fabricated packing to seal joints in pipe.

pipe hanger A device or an assembly to support pipes from a slab, beam, or other structural element that is above the pipe.

pipe laser **1.** A self-leveling instrument used in surveying that employs a laser as a reference for measurements or verifying alignment. **2.** A plumber’s tool used to simplify pipe alignment and installation. Once a hole is drilled in a stud or beam for pipe placement, the laser is directed through the hole to indicate where the hole in the next stud or beam should go.

pipelayer **1.** A tradesperson skilled and trained in laying and joining pipes of glazed clay, concrete, iron, or steel in a trench. **2.** An attachment for a tractor or other machine consisting of a winch and side boom for placing lengths of pipe in a trench.

pipeline heater A heater, usually a wrapping, with an electric element used to prevent the liquid in the pipe from freezing or to maintain the viscosity of the liquid.

pipe pile A cylinder, usually 10″ to 24″ in diameter, generally driven with open ends to form a friction pile. This pile may consist of several sections from 5′ to 40′ long joined by special fittings, such as cast-steel sleeves. A pipe pile is sometimes used with its lower end closed by a conical steel shoe.

pipe plug A pipe fitting with outside threads and a projecting head used to close the opening in another fitting.

pipe reducer A pipe fitting used to connect two lengths of pipe of different diameters.

pipe ring A circular-shaped metal part used to support a pipe from a suspended rod.

pipe run Any path taken by pipe in a distribution or collection system.

pipe saddle An assembly to support a pipe from the underside.



pipe scaffolding

pipe scaffolding A flexible scaffold anchored against a building. This prevalent type of scaffold is also referred to as "metal tube" or "coupler scaffold."

pipe sleeve A cylindrical insert cast in a concrete wall or floor for later passage of a pipe. Also a larger pipe usually used in embankments that allows a smaller pipe to be installed later or to protect it from heavy loads.

pipe stop A stopcock in a pipe.

pipe strap A thin metal strip used as a pipe hanger.



pipe tee

pipe tee A T-shaped fitting to connect three lengths of pipe in the same plane with one length at right angles to the other two.

pipe thread A V-cut screw thread cut on the inside or outside of a pipe or fitting. The diameter of the thread tapers.



pipe wrench (alligator wrench)

pipe wrench (alligator wrench) A heavy hand tool with adjustable serrated jaws for gripping, screwing, or unscrewing metal pipe.

piping **1.** An assembly of lengths of pipe and fittings, i.e., a run of pipe. **2.** Movement of soil particles by percolating water that produces erosion channels.

piping loss The heat lost from piping between the heat source and the radiators.

piston A solid cylinder that fits inside a larger cylinder and moves as a result of the power it receives. It can be used to transmit power to or from a connecting rod. Found in reciprocating engines, pumps, and compressors.

pit **1.** An excavation, quarry, or mine made or worked by the open cut method. A pit seldom goes below the ground water level. **2.** The area between the stage and the first row of seats in a theater. **3.** A small hole or cavity on a surface.

pitch **1.** An accumulation of resin in the wood cells in a more or less irregular patch. Pitch is classified for grading purposes as light, medium, heavy, or massed. **2.** The angle or inclination of a plane such as a roof, which varies according to climate, design, and materials used, and is expressed as a ratio of rise per run. **3.** The set, or projection, of teeth on alternate sides of a saw to provide clearance for its body. **4.** The ratio of rise to run of stairs. **5.** The reciprocal of the number of threads per inch.



pitched roof

pitched roof A roof having one or more surfaces with a slope greater than 10° from the horizontal.

pitch pocket **1.** A flanged metal device used to provide a watertight seal around columns or other roof penetrations. **2.** An opening between growth rings which usually contains or has contained resin, or bark, or both. A pitch pocket is classified for grading purposes as very small, small, medium, large, closed, open, or through.

pitch select D select or better, except that the grade admits any amount of medium to heavy pitch. Massed pitch is admissible but limited to half the area of an otherwise high line piece. Dimensions are 4″ and wider, 6′ and longer in multiples of one foot.

pith knot A minor defect in lumber, a pith knot is a knot whose only blemish is a small pith hole in the center.

pitot tube A device, used with a manometer or other pressure-reading device, to measure the velocity head of a flowing fluid.

pit-run gravel Ungraded gravel used as taken from a pit.

pitting Development of relatively small cavities in a surface due to phenomena such as corrosion, cavitation, or, in concrete, localized disintegration.

pivot A short shaft or pin about which a part rotates or swings.

pivoted door A door that swings on pivots, rather than a door hung on hinges.

pivoted window A window with a sash that rotates about fixed horizontal or vertical pivots.



pivot hinge

pivot hinge A hinge with a short fixed shaft or pin upon which a part rotates or swings. Commonly used for cabinet doors.

placement **1.** The process of placing and consolidating concrete. **2.** A quantity of concrete placed and finished during a continuous operation.

placing The deposition, distribution, and consolidation of freshly mixed concrete in the place where it is to harden. Also, inappropriately referred to as *pouring*.

placing drawings Detailed drawings used to position steel reinforcement in concrete construction.

plain bar A reinforcing bar without surface deformations, or one having deformations that do not conform to the applicable requirements.

plain concrete **1.** Concrete without reinforcement. **2.** Reinforced concrete that does not conform to the definition of reinforced concrete. **3.** Used loosely to designate concrete containing no admixture and prepared without special treatment.

plain end (P.E.) Used to describe the ends of pipe that are shipped from the mill with unfinished ends. These ends may eventually be threaded, beveled, or grooved in the field.

plain rail A meeting rail in a double-hung window that is the same thickness as the other members of the frame.

plain-sawn Wood sawn from logs so that the annual rings intersect the wide faces at an angle less than 45°.

plan **1.** A two-dimensional overview of the design, location, and dimensions of a project (or a portion of a project). **2.** Formalized, written method of accomplishing a project task. **3.** An intended future course of action. **4.** The basis for project controls. **5.** A generic term used for a statement of intentions whether they relate to time, cost, or quality in their many forms. **6.** A predetermined course of action over a specified period of time which represents a projected response to an anticipated environment in order to accomplish a specific set of adaptive objectives.*

planar frame A structural frame with all members in the same plane.

plane **1.** A flat surface. **2.** A tool used to smooth or shape wood. **3.** To run sawn wood through a planer to smooth its surface.

planed all round A piece that has been surfaced on all four sides.

planed lumber Lumber that has been run through a planer to finish one or several sides.

plane of weakness The plane along which a body under stress will tend to fracture. The plane of weakness may exist by design, by accident, or because of the nature of the structure and its loading.

planer A machine used to surface rough lumber.

planer heads Sets of cutting knives mounted on cylindrical heads that revolve at high speed to dress lumber fed through them. Top and bottom heads surface or pattern the two faces, while side heads dress or pattern the two edges or sides.

plane surveying Surveying that neglects the curvature of the earth.

planimeter A mechanical device that measures plane areas on a map or drawing.

planing The process of smoothing a surface by shaving off small chips.

plank A piece of lumber 2″ or more thick and 6″ or more wide, designed to be laid flat as part of a load-bearing surface, such as a bridge deck.

planking Material used for flooring, decking, or scaffolding.



planking

planking and strutting The temporary timbers supporting the soil at the side of an excavation.

planned cost The approved estimated cost for a work package or summary item. This cost when totaled with the estimated costs for all other work packages results in the total cost estimate committed under the contract for the program or project.*

planned value Measure of the value of work planned to have been performed so far.*

planner In project control, a team member with the responsibility for planning, scheduling and tracking of projects. They are often primarily concerned with schedule, progress, and manpower resources.*

planning The process of developing a scheme of a building or group of buildings by studying the layout of spaces within each building, and of building and other installations in an open space.

plan room A service provided by construction industry organizations or service companies, sometimes available to interested constructors, materialmen, vendors, and manufacturers. Plan rooms provide access to contract documents for projects currently in the process of receiving competitive or negotiated bids.

planting In masonry, laying the first courses of a foundation on a prepared bed.

plant mix **1.** A mixture of aggregate and asphalt cement or liquid asphalt, prepared in a central or traveling mechanical mixer. **2.** Any mixture produced at a mixing plant.

plant overhead Those costs in a plant that are not directly attributable to any one production or processing unit and are allocated on some arbitrary basis believed to be equitable. Includes plant management salaries, payroll department, local purchasing and accounting, etc.*



plaster

plan view A drawing that depicts an object, assembly, or floor plan from above.

plaster **1.** A cementitious material or combination of cementitious material and aggregate that, when mixed with a suitable amount of water, forms a plastic mass or paste. When applied to a surface, the paste adheres to it and subsequently hardens, preserving in a rigid state the form or texture imposed during the period of elasticity. **2.** The placed and hardened mixture created as in definition 1 above.

plaster aggregate Graded mineral particles and mineral, vegetable, or animal fibers to be used with gypsum or cement-base plasters to produce a plaster mix.

plaster base Any working ground to receive plaster, including wood, metal, or gypsum lath, insulating board, or masonry.



plaster base

plaster bead An edging, usually metal, to strengthen applied plaster at corners.

plasterboard (sheetrock, drywall) Any prefabricated board of plaster with paper facings. Plasterboard may be painted or used as a base for a finish coat of applied plaster.

plasterboard nail A nail for fastening plasterboard to a supporting system. The nails are galvanized with a flat head and a deformed shank.

plaster bond The mechanical or chemical adhesion of plaster to a surface.

plasterer's putty A hydrated lime with just enough water added to make a thick paste for use as a hole or crack filler.

plaster ground A wood strip or metal bead used as a guide for application of a desired thickness of plaster or for attaching trim.

plaster lath A supporting structure for plaster, such as a wood lath, metal lath, or lath board.

plaster of paris Gypsum, from which three-quarters of the chemically bound water has been driven off by heating. When wetted, it recombines with water and hardens quickly. *See also* **hemihydrate**.

plaster ring A metal collar attached to a base and used as a guide for thickness of applied plaster and a fastener for trim.

plaster set The initial stiffening of a plaster mix that may be reworked without the addition of water.

plastic bond fire clay **1.** A fire clay of sufficient natural plasticity to bond nonplastic material. **2.** A fire clay used as a plasticizing agent in mortar.

plastic cement A synthetic cement used in the application of flashing.

plastic consistency **1.** Condition of freshly mixed cement paste, mortar, or concrete that allows that deformation to be sustained continuously in any direction without rupture. **2.** In common usage, concrete with slump of 3″ to 4″ (80 to 100 mm).

plastic cracking Cracking that occurs in the surface of fresh concrete soon after it is placed and while it is still plastic.

plastic curtains Curtains or strip doors that reduce infiltration and exfiltration within a building. These barriers typically consist of several strips of heavy plastic (often transparent or translucent) that form a fairly tight seal, yet allow easy passage.

plastic deformation Deformation that does not disappear when the force causing the deformation is removed.

plastic glue Resin bonding materials used in joining wood pieces. These materials include: **1.** Thermosetting resins such as phenol-formaldehyde, urea-formaldehyde, and melamine resin. **2.** Thermoplastics such as acryl polymers and vinyl polymers. **3.** Casein plastics. **4.** Natural resin glues.

plasticity **1.** The capability of being molded, or being made to assume a desired form. **2.** A property of a material that allows it to retain its form when bent. **3.** A complex property of a material involving a combination of qualities of mobility and magnitude of yield value. **4.** That property of freshly mixed cement paste, concrete, or mortar that determines its resistance to deformation and ease of molding.

plasticizer **1.** A material that increases plasticity of a cement paste, mortar, or concrete mixture. **2.** Various substances added to organic compounds to create a more flexible finished product. These additives are frequently used in roofing materials and concrete.

plasticizing **1.** Producing plasticity or becoming plastic. **2.** Softening wood by hot water, steam, or chemicals to increase its moldability.

plastic laminate A thin board used as a finished surfacing, made from layers of resin-impregnated paper fused together under heat and pressure.

plastic limit The water content at which a soil will just begin to crumble when rolled into a thread approximately ⅛″ (3 mm) in diameter. *See also* **Atterberg limits**.

plastic lumber An alternative building material that is usually manufactured with recycled plastics. In contrast to wood, it will not splinter, rot, or warp. Used in decking and pilings, among other applications.

plastic skylight A molded unit of transparent or translucent plastic that is set in a frame for use as a skylight.

plastic soil Any soil that can be molded or deformed by moderate pressure without crumbling.


plastic skylight

plastic wood A quick-drying putty of nitrocellulose, wood flour, resins, and solvents used as a filler for holes and cracks.

plate **1.** In formwork for concrete, a flat, horizontal member at the top and/or bottom of studs or posts. If on the ground, a plate is called a mudsill. **2.** In structural design, a member, the depth of which is substantially smaller than its length and width. **3.** In framing, the top plate (horizontal) connects with the top of wall studs. The floor joists, rafters, or trusses rest on it. The sole plate is at the bottom of wall studs. The still plate (horizontal) rests on and is anchored to the foundation. **4.** A flat rolled iron or steel product.

plate anchor An anchor bolt used to fasten a plate or sill to a foundation.

plate girder A girder fabricated from plates, angles, or other structural shapes, welded or riveted together.


plate girder

plate glass High-quality glass of the same composition as window glass but thicker, up to 1¼″, with ground and polished faces, usually used for large areas in a single sheet.

plate stock Component that makes up the bottom and top of a typical wood framed wall. Usually the same dimension as the wall framing stock but may be a lesser grade.

plate-type tread A stair tread fabricated from metal plate and/or floor plate. The riser may be integral.

plate vibrator A self-propelled, mechanical vibrator used to compact fill.

platform **1.** A floor or surface raised above the adjacent level. **2.** A landing in a stairway. **3.** A working space for persons, elevated above the surrounding floor or ground level such as a balcony or platform for the operation of machinery or equipment.


platform

platform framing A framing system in which the vertical members are only a single story high, with each finished floor acting as a platform upon which the succeeding floor is constructed. Platform framing is the common method of house construction in North America.

plenishing nail A large nail used to fasten planks to joists.

plenum **1.** A closed chamber used to distribute or collect warmed or cooled air in a forced air heating/cooling system. **2.** The space between the suspended ceiling and the floor above. **3.** The space between a raised floor and the floor below. **4.** A closed chamber used to collect or distribute fluids in a distribution or collection system.



plenum

plenum barrier A barrier, erected in a plenum ceiling, used to reduce sound transmission between rooms or over a large area.

plenum chamber *See* **plenum**.

plenum fans (plug fans) Single-inlet, single-width centrifugal fans without the scroll, permitting 360° air delivery from the fan wheel.

pliers A pincer-like hand tool with opposing jaws for gripping, cutting, and bending.

plinth **1.** A block or slab supporting a column or pedestal. **2.** The base course of an external masonry wall when of different shape from the masonry in the wall proper. **3.** The base of a monument or statue, often with inscription.

plinth course **1.** The masonry course that forms the plinth of a stone wall. **2.** The final course of a brick plinth in a brick wall.

plot **1.** A measured and defined area of land. **2.** A ground plan of a building and adjacent land.



plot

plot plan A diagram showing the proposed or existing use of a specified parcel of land.

plow **1.** In molding, a rectangular slot of three surfaces cut with the grain of the wood. **2.** In carpentry, a tool that cuts grooves. **3.** A drywall tool with a bent trowel used to finish corners.

plug **1.** A wood peg driven into a wall for support of a fastener. **2.** A stopper for a drain opening. **3.** A male-threaded fitting used to seal the end of a pipe or fitting. **4.** A fixture for connection of electric wires to an outlet socket. **5.** A fibrous or resinous material used to fill a hole and close a surface. **6.** Material that stops or seals the discharge line of a channel or pipe.

plug center bit A plug-shaped bit used to enlarge a hole or counterbore around the hole.

plug cock A valve where full flow is through a hole in a tapered plug. Rotating the plug 90° completely stops the flow.



plug cock

plug fuse A fuse contained in an insulated container with a metal screwbase. There is a small window on the face of the container for checking the condition of the fuse element.

plugged lumber Lumber in which a defect has been filled by material to provide a smooth paint surface.

plugging chisel A steel rod, with a star-shaped point, used for drilling holes in masonry by striking with a hammer.

plug tenon A short tenon that projects from the material into which it is fitted, the free end fitting into a mortise. A plug tenon is used to provide lateral stability for a wood column.

plug weld A weld made through a circular hole in one of the members to be connected.

plumb Vertical, or to make vertical.

plumb bob A cone-shaped metal weight, hung from a string, used to establish a vertical line or as a sighting reference to a surveyor's transit.



plumb bob

plumb bond Any bond in masonry in which the vertical joints are in line.

plumb cut A vertical cut, as in the cuts in a rafter at the top ridge where it meets the ridge plate.

plumber's rasp A coarse rasp used to file lead.

plumber's round iron A specially shaped soldering iron used to solder seams in tanks.

plumber's solder An alloy with a low melting point used for joining metal pieces such as copper pipes.

plumbing **1.** The work or practice of installing in buildings the pipes, fixtures, and other apparatuses required to bring in the water supplies and to remove water-borne wastes. **2.** The process of setting a structure or object truly vertical.

plumbing boot Metal support installed to reinforce wall studs in cases where a cut has been made for a plumbing drain line.

plumbing fixture A receptacle in a plumbing system, other than a trap, in which water or wastes are collected or retained for use and ultimately discharged to drainage.



(a) plumbing fixture



(b) plumbing fixture

plumbing ground Drain and waste lines underneath a basement floor.

plumbing jack A sleeve surrounding a drain or vent pipe on a roof.

plumbing, rough Advance work done by a plumbing contractor. Includes installation of waste and supply piping, shower pans and tubs, and gas piping.

plumbing stack A vent pipe installed through the roof materials.

plumbing system Arrangements of pipes, fixtures, fittings, valves, and traps in a building that supply water and remove liquid-borne wastes.

plumbing trim Last stage of the plumbing contractor's work prior to final inspection. It includes pipe connections to fixtures and appliances.

plumbing waste line Plastic piping for removal of sewage.

plumb joint A sheet metal joint made by lapping the edges and soldering them together flat.

plumb level A level that is set in a horizontal position by placing it at a right angle to a plumb line.

plumb rule A board or metal rule, fitted with one or more leveling bubbles, used to establish horizontal and vertical lines.

plume **1.** The effluent mixture of heated air and water vapor discharged from a cooling tower. **2.** An identifiable and definable stream of pollutants in an otherwise clean volume of air or water.

plunger (plumber's friend) A tool, consisting of a large rubber suction cup on a wood handle, for clearing plumbing traps of minor obstructions.

ply **1.** A single layer or sheet of veneer. **2.** One complete layer of veneer in a sheet of plywood.

plymetal Plywood covered on one or both sides with sheet metal.

plywood A flat panel made up of a number of thin sheets (veneers), of wood. The grain direction of each ply, or layer, is at right angles to the one adjacent to it. The veneer sheets are united under pressure by a bonding agent. Interior-grade plywood is suitable for indoor use or for outside use when subject only to occasional, temporary moisture, while exterior-grade plywood uses a weather-resistant adhesive.

plywood grade The widely recognized grading system administered by the American Plywood Association that rates plywood on the quality of its veneer (from A to D) and on its exposure durability.

pneumatic control system A system in which control is effected by pressurized air.

pneumatic drill A reciprocating drill actuated by compressed air.

pneumatic feed Delivery equipment in which material is conveyed by a pressurized air stream.

pneumatic hammer An air-powered tool with a linear driven shaft fitted with a chisel or hammer.

pneumatic structure A fabric envelope supported by an internal air pressure slightly above atmospheric pressure. The pressure is provided by a series of fans.

pneumatic water supply A water supply system for a building in which water is distributed from a tank containing water and compressed air.

pocket **1.** A recess in a wall to receive an end of a beam. **2.** A recess in a wall to receive part or all of an architectural item, such as a curtain or folding door. **3.** The slot on the pulley stile of a double-hung window through which the sash weight is placed in the sash weight channel.

pocket channel A U-shaped opening in a window frame or sash where the glazing is inserted.

pocket chisel A chisel with a wide blade that is sharpened on both sides.

pocket door A door that opens by sliding into and "hiding" in a wall recess.

pocket piece A small piece of wood that closes the *pocket* in the pulley stile of a double-hung window.

podium **1.** A stand for a speaker. **2.** An elevated platform for a conductor. **3.** The masonry platform on which a classical temple was built.

point **1.** A fee equal to 1% of the principal amount of a loan. Charged by the lender when the loan is made. **2.** A tooth for a saw. **3.** A mason's tool. **4.** A thin, triangular or diamond-shaped piece of metal used in glazing to hold glass in a wooden frame. **5.** A piece of equipment that is monitored or controlled by a building automation system.

pointed work The rough finish on the face of a stone that is made by a pointed tool.

pointing **1.** The finishing of joints in a masonry wall. **2.** The material with which joints in masonry are finished.

pointing trowel A diamond-shaped trowel used in pointing or repointing masonry joints.

point load A term used in structural analysis to define a concentrated load on a structural member.

point of inflection (point of contraflexure) **1.** The point on the length of a structural member subjected to flexure where the curvature changes from concave to convex or conversely, and at which the bending moment is zero. **2.** Location of an abrupt bend in a plotted locus of points in a graph.

point of support A point on a member where part of its load is transferred to a support.



point of support

point source **1.** A light source, the dimensions of which are insignificant at viewing distance. A fluorescent lamp is a point source at a large distance. **2.** A pollution source that is discharged at an identifiable point such as a single pipe or smoke stack.

Poisson's ratio The ratio of transverse (lateral) strain to the corresponding axial (longitudinal) strain resulting from uniformly distributed axial stress below the proportional limit of the material.

polarity The direction of electric current flow in a DC circuit.

polarized receptacle An electric receptacle with contacts arranged so a mating plug must be inserted in only one orientation.



polarized receptacle

pole **1.** A long, usually round piece of wood, often a small diameter log with the bark removed, used to carry utility wires or for other purposes. A pole is often treated with preservative. **2.** Either of two oppositely charged terminals, as in an electric cell or battery. **3.** Either extremity of an axis of a sphere.

pole-frame construction A construction system using vertical poles or timbers.

pole plate A horizontal board or timber that rests on the tie beams of a roof and supports the lower ends of the common rafters at the wall, and also raises the rafters above the top plate of the wall.

pole sander A sanding block on the end of a long pole that makes the sanding of drywall ceiling joints easier.



pole sander

polish **1.** To give a sheen or gloss to a finish coat of plaster. **2.** The operation in which fine abrasives are used to hone a finished surface to a desired smoothness.

polished finish A finish so smooth that it forms a reflective surface, usually produced by mechanical buffing and chemical treatment of a surface with no voids.

polishing varnish A hard varnish that can be polished by rubbing with abrasive and mineral oil without dissolving the resin.

polycarbonate A transparent thermoplastic with a high impact strength and a high modulus of elasticity. Its excellent insulating qualities make it ideal for many electrical applications.

polychlorinated biphenyls (PCBs) A group of hydrocarbon-containing chlorine compounds that, before being banned as pollutants, were used in hundreds of industrial and commercial applications, including electrical and hydraulic equipment, sealants, rubber, paints, and plastics. PCBs are not readily biodegradable, and the United States stopped producing them in 1977.

polychloroprene (neoprene) An oil-resistant, synthetic rubber. In roofing, used for membranes and flashing. The common name for polychloroprene is neoprene.

polyester resin A synthetic resin that polymerizes during curing and has excellent adhesive properties, high strength, and good chemical resistance.

polyethylene A thermoplastic high-molecular-weight organic compound. In sheet form, polyethylene is used as a protective cover for concrete surfaces during the curing period, a temporary enclosure for construction operations, and as a vapor barrier. It is also commonly used for culvert pipes and in other piping systems.



polyethylene

polyethylene vapor barrier A plastic film used to prevent the passage of vapor or moisture into areas where it could collect and do damage.

polyisobutylene (PIB) A synthetic rubber derived from the polymerization of isobutylene. In roofing, used for membranes and flashing.

polyisocyanurate (polyiso) A polymer with a high R-value commonly used as insulation. It is available as a liquid, sprayed foam or rigid foam boards, usually faced with a foil paper. Increasingly, polyiso board products are also being used for sheathing. Often specified for applications where increased fire resistance is desired.

polymer **1.** The product of polymerization. Some polymers are elastomers, while others are plastics. **2.** A rubber or resin consisting of large molecules formed by polymerization.

polymer-cement concrete A mixture of water, hydraulic cement, aggregate, and a monomer or polymer. The cement is polymerized in place when a monomer is used.

polymethyl-methacrylate (PMMA) A transparent thermoplastic that offers good weather resistance and a high strength-to-weight ratio.

polypropylene A tough plastic with good resistance to heat and chemicals. Polypropylene is a polymer of propylene, and is found in everything from packaging to molded automobile parts.

polystyrene foam A low-cost, foamed plastic weighing about 1 lb. per cu. ft., with good insulating properties and resistance to grease.

polystyrene resin Synthetic resins, varying in color from water-white to yellow, formed by the polymerization of styrene on heating, with or without catalysts. These resins may be used in paints for concrete, for making sculptured molds, or as insulation.

polysulfide coating A protective coating system prepared by polymerizing a chlorinated alkyl polyether with an inorganic polysulfide. This coating exhibits outstanding resistance to ozone, sunlight, oxidation, and weathering.

polytetrafluoroethylene (PTFE) A fluorocarbon-based polymer with high chemical and weather resistance, low friction, and electrical and thermal insulation. The most common brand name is Teflon®. PTFE's many construction applications include usage in hydraulic machinery and in plumber's joint tape.

polyurethane Reaction product of an isocyanate with any of a wide variety of other compounds containing an active hydrogen group. Polyurethane is used to formulate tough, abrasion-resistant coatings, and is also used for foam insualtion products.

polyurethane insulation (PUR insulation) Any of a number of insulation products made of polyurethane. Forms include rigid boards, spray foams, and pourable mixes.

polyvinyl acetate (PVA) Colorless, permanently thermoplastic resin, usually supplied as an emulsion or water-dispersible powder, which may be used in paints for concrete. Polyvinyl acetate is characterized by flexibility, stability towards light, transparency to ultraviolet rays, high electric strength, toughness, and hardness. The higher the degree of polymerization, the higher the softening temperature.

polyvinyl chloride (PVC) A thermoplastic resin derived from the polymerization of vinyl chloride. Plasticizers have been added to give it flexibility. Widely used in piping products, it is also used for siding, floor covering, window housing, and fencing. In roofing, it is used for membranes and flashing. Also used in the manufacture of nonmetallic waterstops for concrete. PVC materials are to be avoided in green construction because it has been linked to cancer, birth defects, and groundwater contamination.

pommel **1.** A knob at the top of a conical or domelike roof. **2.** A rounded metal block on an end of a handle, raised and dropped by hand to compact soil.

ponderosa pine (western white pine, western yellow pine) *Pinus ponderosa*. A pine species found in a wide range that reaches from British Columbia to Mexico, and from the Pacific coast to the Dakotas. The wood is widely used in general construction, most often as boards, but is more valued for its uses in millwork and in cuttings for remanufacture.

ponding **1.** The process of flooding the surface of a concrete slab by using temporary dams around the perimeter in order to satisfactorily cure the concrete. **2.** The accumulation of water at low points in a roof. The low points may be produced or increased by structural deflections.

pop (blow, blister) A delaminated area in a plywood panel.

popcorn concrete No-fines concrete containing insufficient cement paste to fill voids among the coarse aggregate so that the particles are bound only at points of contact.

poplar A member of the willow family. Its wood is used in furniture core stock, crates, and plywood. In North America: *Populus tretnula*, aspen; *P. balsamifera*, cottonwood; and *P. tacamahaca*, *balsam poplar*.

popout The breaking away of small portions of a concrete surface due to internal pressure, leaving a shallow, typically conical, depression.

popping Shallow depressions ranging in size from pinheads to ¼″ in diameter, immediately below the surface of a lime-putty finish coat. Popping is caused by expansion of coarse particles of unhydrated lime or of foreign substances.

pop rivet A fastener installed with a rivet gun to connect metal pieces.

pop valve A safety valve made to open immediately when the fluid pressure is greater than the design force of a spring.

porcelain A hard glazed or unglazed ceramic used for electrical, chemical, mechanical, or thermal components.

porcelain enamel A silicate glass bonded to metal by fusion at a temperature above 800°F (427 °C). Porcelain enamel is not a true porcelain.

porcelain tile A dense, usually impervious, fine-grained, smooth-surfaced, ceramic mosaic tile or paver.

porch A structure attached to a building, usually roofed and open-sided, and often at the entrance. Sometimes screened or glass-enclosed.



porch

porcupine boiler A vertical, cylindrical boiler with many projecting, closed stubs to provide an additional thermal surface.

porosity The ratio, usually expressed as a percentage, of the volume of voids in a material to the total volume of the material, including the voids.

porous paving Paving surfaces designed to allow storm water infiltration and reduce runoff.

portico **1.** A covered walk consisting of a roof supported on columns. **2.** A colonnaded (continuous row of columns) porch.

portico

portlandite A mineral, calcium hydroxide, that occurs naturally in Ireland. Portlandite is a common product of hydration of Portland cement.

Portland stone A limestone, from the island of Portland off the coast of England, used as a building stone.

position **1.** A trader's open contracts in the futures market. **2.** A reference to a shipping period, as in "Feb/March position."

positioned weld A weld on a joint that has been oriented to facilitate the welding.

position indicator A device that shows the position of an elevator in its hoistway. Also called a *hall position indicator* if at a landing, or a *cab position indicator* if in the cab.

positive cutoff A below-ground wall that extends to an impervious lower stratum to block subsurface seepage.

positive displacement Moving a fluid by capturing and then discharging a fixed amount of fluid. A piston pump is one example of a positive displacement pump.

positive moment A condition of flexure in which, for a horizontal simply supported member, the deflected shape is normally considered to be concave downward and the top fibers subjected to compression stresses. For other members and other conditions, consider positive and negative as relative terms.

positive float Amount of time available to complete noncritical activities or work items without affecting the total project duration.*

positive pressure Pressure that is greater than atmospheric pressure.

positive reinforcement Reinforcement for positive moment.

post **1.** A member used in a vertical position to support a beam or other structural member in a building, or as part of a fence. In lumber, 4 × 4s are often referred to as posts. Most grading rules define a post as having dimensions of 5″ × 5″ or more in width, with the width not more than 2″ greater than the thickness. **2.** Vertical formwork member used as a brace. Also called a shore, prop, and jack. **3.** A secondary column located at the end of a building to support its girts.

post and beam framing A structural framing system in which beams rest on posts rather than bearing walls.

post and pane A type of construction in which timber framings are filled in with brick or plaster panels, leaving the timbers exposed.

postbuckling strength The load that can be carried by a structural member after it has been subjected to buckling.

postconstruction services **1.** Services rendered after the release of the final invoice for payment or over 60 days from the date of substantial completion of the project. **2.** Any services necessary to allow the owner to use and/or occupy the facility.

postconsumer recycled content Material that has been used by consumers, such as used newspaper, and has been diverted or separated from waste management systems for recycling.

post shore, adjustable timber single-post Individual timber used with a fabricated clamp to obtain adjustment and not normally manufactured as a complete unit.



post shore, adjustable timber single-post

post shore, fabricated single-post Type 1: Single all-metal post, with a fine-adjustment screw or device in combination with pin-and-hole adjustment or clamp. Type 2: Single or double wooden post members adjustable by a metal clamp or screw and usually manufactured as a complete unit.

post-tensioned concrete Concrete that has the reinforcing tendons tensioned after the concrete has set.

potable water Water that satisfies the standards of the responsible health authorities as drinking water.

potato masher A simple hand tool used to mix joint compound. The tool has a wire mixer similar to that of the kitchen implement of the same name.

potentiometer An instrument for controlling electrical potential. Measures an unknown voltage by comparing it to a standard voltage.

pot life Time interval, after preparation, during which a liquid or plastic mixture is usable.

pound-calorie The amount of heat required to raise one pound of water 1°C.

pour coat (top mop) The top coating of asphalt on a built-up roof, sometimes including embedded gravel or slag.

pour point The lowest temperature at which a lubricant flows under specified conditions.

pour strip In concrete formwork, a narrow guide placed inside the form to direct the concrete.

powder post A condition in which wood has decayed to powder or been eaten by borers that leave holes full of powder.

power The rate of performing work or the rate of transforming, transferring, or consuming energy. Power is usually measured in watts, Btu/hour, or horsepower.

power buggy A wheelbarrow-sized machine powered by a gasoline engine or an electric motor.

power cable A usually heavy cable, consisting of one or more conductors with insulation and jackets, for conducting electric power.



power cable

power consumption The rate at which power is consumed by a device or unit (such as a building), usually expressed in kilowatt-hours, Btu/hour, or horsepower-hours.

power drops Electrical power outlets to serve specific pieces of equipment.

power factor A calculation, expressed as a percentage, that relates the volt amperes of an AC circuit, or the apparent power, to the wattage, or the true power. In essence, it provides a measurement of how effectively electrical power is being used. A higher power factor means a more effective use of electrical power.

power panelboard A panelboard used for circuits supplying motors and other heavy power-consuming devices, as opposed to a panelboard used for lighting circuits.



power panelboard

power sander An electric-powered hand tool used for smoothing and/or polishing.

power shovel A self-propelled, power-operated machine used to excavate and/or load soils or debris.

power take-off On construction equipment, an attachment enabling the power from the prime mover to be used to drive an auxiliary machine or tool.

power transformer A device in an alternating-current electrical system that transfers electric energy between circuits, usually changing the voltage in the process.



power transformer

power vent A vent with a fan that boosts the flow of air.

pozzolan A siliceous, or siliceous and aluminous, material which, in itself, possesses little or no cementitious value but will, in finely divided form and in the presence of moisture, chemically react with calcium hydroxide at ordinary temperatures to form compounds possessing cementitious properties.

pozzolan cement A natural cement, used in ancient times, made by grinding pozzolan with lime.

Pratt truss A type of truss with parallel chords, all vertical members in compression, and all diagonal members in tension. The diagonals slant toward the center.



Pratt truss

practical coverage The actual coverage of a paint or other coating based on the intended dry film thickness and with an allocation (usually 15%) for material loss.

preaction sprinkler system A dry pipe sprinkler system in which water is supplied to the piping when a smoke or heat detector is activated.



preaction sprinkler system

precast concrete Concrete structural components, such as piles, wall panels, beams, etc., fabricated at a location other than in place.

precise level An instrument similar to an ordinary surveyor's level but capable of finer readings and including a prism arrangement that permits simultaneous observation of the rod and the leveling bubble.

precompressed zone The area of a flexural member that is compressed by the prestressing tendons.

preconsolidation pressure The greatest effective pressure a soil has experienced.

pre-construction services Services provided by the construction contractor during the development of the design, which may include preliminary cost estimating, preparing a preliminary construction schedule, and constructability review.

precooling coil In an HVAC system, a cooling coil located at the air-entering side of the primary cooling coil.

precuring In plywood manufacturing, the premature curing of an adhesive due to press temperatures being too high, a too rapid resin-curing speed, or a malfunctioning press. Precuring can result in plywood delamination or a poor quality surface in particleboard.

precut A lumber item, usually a stud, that is cut to a precise length at the time of manufacture, so that it may be used in construction without further trimming at the job site.

precycling Proactive approach of selecting products and materials according to their potential for lessening the amount of material that goes into the waste stream and for future recycling. Precycling includes buying in bulk, avoiding one-time use products, and choosing products that are biodegradable and have the least amount of throwaway packaging, for example.

predesign services Services provided by the design professional that precede customary services. Predesign services include assistance of the owner in establishing the program, schedule, budget, and project limitations.

predrilled Materials, such as roof decking, that have been drilled at the mill to accommodate bolts or other hardware.

prefabricate To fabricate units or components at a mill or plant for assembly at another location.

prefabricated construction A construction method that uses standard prefabricated units that are assembled at a site along with site fabrication of some minor parts.

prefabricated flue A vent for fuel-fired equipment that is assembled from factory-made parts.

prefabricated joint filler A compressible material used to fill control, expansion, and contraction joints and may also be used alone, or as a backing for a joint sealant.

prefabricated masonry panel A wall panel of masonry units constructed at an assembly site and moved to a job site for erection.



prefabricated flue

prefabricated modular units Units of construction that are preassembled at the factory and shipped as a complete unit to the job site. They usually can be installed with a minimum of adjustments.

prefabricated tie A manufactured assembly consisting of two heavy parallel wires tied together by welded wires. The tie is laid in masonry joints to tie two wythes together.



prefabricated tie

prefilled A particleboard panel whose surface has been made smooth by the application of a solvent-based filler before being shipped. Such panels have decorative overlays or laminates applied to them.

prefilter A filter placed before the main filter(s). A prefilter is coarser and is used to remove larger particles.

prefinished Products with a finish coating of paint, stain, vinyl, or other material applied before they are taken to the job site.

prefiring Raising the temperature of refractory concrete under controlled conditions prior to placing it in service.

preformed asphalt joint filler Premolded strips of asphalt, vegetable or mineral filler, and fibers for use as a joint filler.



preformed asphalt joint filler

preformed foam Foam produced before it is mixed with other ingredients to make cellular foam.

preformed sealant A factory-shaped sealant that requires little field fabrication prior to installation.

preheat coil A coil, in an air-conditioning system, used to preheat air that is below 32°F (0°C).

preheater **1.** A heat exchanger used to heat air that is to be used in the combustion chamber of a large boiler or furnace. **2.** A heat exchanger used to heat a fluid flowing into a process or location.

An example would be to preheat outdoor air entering a heated space using the exhaust air.

preheat fluorescent lamp A fluorescent lamp, the electrodes of which must be preheated before the arc can be started. The preheating can be manual or automatic.

prehung door A packaged unit consisting of a finished door on a frame with all necessary hardware and trim.

preliminary site assessment The first phase in an environmental remediation operation, in which it is determined whether there is a reasonable probability that a hazardous waste exists at a site.

preliminary drawings Drawings prepared in the early phase of building design.

preliminary estimate A rough estimate made in an early stage of the design work, prior to receipt of firm bids.

premises wiring Strictly speaking, the external and internal wiring that runs from the service point of utility conductors into a structure and to its outlets. Also includes all associated hardware and fittings.

premium grade A general term describing the quality of one item as superior to another.

premolded asphalt panel A panel with a core of asphalt, minerals, and fibers, covered on each side with asphalt-impregnated felt or fabric and pressure-bonded. The outside is then coated with hot asphalt.

preposttensioning A method of fabricating prestressed concrete in which some of the tendons are pretensioned and a portion of the tendons are posttensioned.

prepreg In reinforced plastic, the reinforcing with applied resin before molding.

prequalification of bidders The investigation and subsequent approval of prospective bidders' qualifications, experience, availability, and capability regarding a project.

present value The value of a benefit or cost found by discounting future cash flows to the base time. Also, the system of comparing proposed investments, which involves discounting at a known interest rate (representing a cost of capital or a minimum acceptable rate of return) in order to choose the alternative having the highest present value per unit of investment.*

present value method A means of evaluating capital expenditures by converting projections of cash inflows and outflows over time to their present value, using an estimated discounting rate.

preservationist A term applied to one who objects to the use of natural resources because of a belief that such use will destroy basic values of the resource. The term is often used to refer to a member of various groups opposed to the expansion of industrial/commercial uses of public lands.

preservative Any substance applied to wood that helps it resist decay, rotting, or harmful insects.

preshrimmed tape sealant A preformed sealant that resists deformation when compressed.

preshrunk concrete **1.** Concrete that has been mixed for a short period in a stationary mixer before being transferred to a transit mixer. **2.** Grout, mortar, or concrete that has been mixed one to three hours before placing to reduce shrinkage during hardening.

press brake A machine used to bend and shape cold-form metal sheets and strips.

pressed brick Brick that is molded under mechanical pressure. The resulting product is sharp-edged and smooth, and is used for exposed surfaces.

pressed earthen block Blocks of earthen material made by compressing a mixture of soil and aggregate without the use of chemical additives. Application and usage is similar to that of adobe.

pressed wood A panel wood product manufactured by compressing wood fibers and adhesive under heat. Common examples include particleboard, hardwood plywood paneling, and medium-density fiberboard.

pressure **1.** The force per unit area exerted by a liquid or gas on the walls of a container. **2.** The force per unit area transferred between surfaces.

pressure bulb The zone in a loaded soil mass that is bounded by a selected stress isobar.

pressure cell An instrument used to measure the pressure within a soil mass or the pressure of the soil against a rigid wall.

pressure connector A mechanical device that forms a conductive connection between two or more electric conductors, or between one or more conductors and a terminal, without the use of solder.



pressure connector

pressure differential valve A valve controlled by the pressure difference in the supply and return main to divert flow from the supply main to the return main.

pressure drop **1.** The drop in pressure between two ends of a pipe or duct, between two points in a system, or across valves, fittings, etc., caused by friction losses. **2.** In a water system, the drop caused by a difference in elevation.

pressure forming A thermoforming process for plastics in which pressure forces a sheet against a mold, as opposed to vacuum forming.

pressure gauge An instrument for measuring fluid pressure.



pressure gauge

pressure gluing A method used to glue wood that places the members under high pressure until the glue sets.

pressure-injected footing A cast-in-situ concrete pile that features a steel cylindrical shaft with an enlarged base that is driven into the ground. It can be used in nearly all soil conditions and can safely withstand very high compressive and tensile forces and substantial horizontal loads.

pressure-reducing valve A valve that maintains a uniform fluid pressure on its outlet side as long as pressure on the inlet side is at or above a design pressure.



pressure-reducing valve

pressure-regulating valve A valve that automatically reduces water pressure to maintain a predetermined design pressure.

pressure-relief damper A damper that will open when pressure on the inside exceeds a design pressure.

pressure-relief device A device or valve that is designed to open or rupture when pressure on a designated side exceeds a design value.

pressure-relief hatch A roof hatch designed to open or blow off under pressure from an explosion in a building. Some smoke and heat vents are also designed as pressure-relief hatches.

pressure-relieving joint A horizontal expansion joint in panel wall masonry, usually below supporting hangers at each floor. These joints prevent the weight of higher panels from being transmitted to the masonry below.

pressure reset system A control system for boilers and furnaces that allows wide fluctuations in pressure. As a result, the burners can be shut off for longer periods and stay on for longer amounts of time, with fewer cycles. Avoiding short cycles increases the net system efficiency.

pressure-sensitive adhesive An adhesive material that remains tacky after the solvents evaporate and will adhere to most solid surfaces with the application of light pressure.

pressure treating A process of treating lumber or other products with various chemicals, such as preservatives and fire retardants, by forcing the chemicals into the structure of the wood using high pressure.

pressure wire connector Any device that maintains a mechanical connection between electrical conductors through the use of pressure.

prestressed concrete wire Steel wire with a very high tensile strength, used in prestressed concrete. The wire is initially stressed close to its tensile strength. Then some of this load is transferred to the concrete, by chemical bond or mechanical anchors, to compress the concrete.

prestressing Applying a load to a structural element to increase its effectiveness in resisting working loads. Prestressed concrete is a common example.

prestressing cable A cable or tendon made of prestressing wires.

prestressing steel High-strength steel used to prestress concrete, commonly seven-wire strands, single wires, bars, rods, or groups of wires or strands.

pretensioned concrete Concrete that has its reinforcing tendons stressed before the concrete is placed. Tension on the tendons is then released to provide load transfer where concrete has achieved strength.



pretensioned concrete

pretensioning A method of prestressing reinforced concrete in which the tendons are tensioned before the concrete has hardened.

prevailing wage Wage set by federal and state governments for construction work based on wages paid for similar work in the same local area.

preventive maintenance (PM) Periodic, scheduled work on selected equipment and building components, usually consisting of required inspection, cleaning, lubrication, and minor adjustment to help prevent systems failure.

price index A number which relates the price of an item at a specific time to the corresponding price at some specified time in the past.*

price out **1.** The activity of applying dollar values to the items in a takeoff. **2.** The final estimate sheet showing all dollar values.

pricing In estimating practice, after costing an item, activity, or project, the determination of the amount of money asked in exchange for the item, activity, or project. Pricing determination considers business and other interests (e.g., profit, marketing, etc.) in addition to inherent costs. The price may be greater or less than the cost depending on the business or other objectives. In the cost estimating process, pricing follows costing and precedes budgeting.*

prick punch A pointed steel hand punch used to mark metal.



prick punch

prills Bulk, porable dry explosive consisting of pea-sized granules.

primacord A detonating fuse for high explosives, consisting of an explosive core in a strong, waterproof covering. Also called detonating cord.

primary air Air that is fed to a burner to be mixed with gas.

primary battery A battery of two or more primary cells.

primary blasting The blasting operation in which a natural rock formation is dislodged from its original location.

primary branch **1.** A drain between the base of a soil or waste stack and a building drain. **2.** The largest single branch of a water supply line or an air supply duct in a building.

primary cell A cell that generates electric current by electrochemical action. In the process, one of the electrodes is consumed and the process cannot be effectively reversed. The cell cannot be recharged from an external source of electric power.

primary consolidation Soil compaction in saturated fine grain soils caused by the application of sustained loads, principally due to the squeezing out of water in the voids of the affected soil.

primary distribution feeder A feeder that operates at primary voltage supplying a distribution circuit.

primary excavation Excavating undisturbed soil.

primary light source **1.** A source of light in which the light is produced by a transformation of energy. **2.** The most obvious source of light when several sources are present.

primary member One of the main load-carrying members of a structural system, generally columns or posts.



primary member

prime **1.** A grade of finish lumber ranking below superior, the highest grade, and above E, the lowest grade of finish. Finish graded prime must present a fine appearance and is designed for application where finishing requirements are less exacting. **2.** To supply water to a pump to enable it to start pumping. **3.** In blasting, to place the detonator in a cartridge or charge of explosive. **4.** The primary architect or contractor on a job that features several. **5.** To seal a porous surface to prevent or reduce staining, shrinkage, and drying out.

prime bid A bid presented directly to the owner or his agent, rather than a subcontractor's bid to a general contractor.

prime coat **1.** An application of low-viscosity liquid asphalt to an absorbent surface. **2.** The first or preparatory coat in a paint system.

prime contract An agreement formed between the owner and the contractor for a major portion of the work on a construction contract.

prime contractor Any contractor on a project having a contract directly with the owner.

primer A base, preparatory paint that is applied to an uncoated surface to improve the adhesion and durability of the finish coat. Primer can be latex or alkyd (oil-based) paint.

primer/sealer A paint product manufactured to both prime a material for future paint application while sealing it from moisture.

priming **1.** The application of a prime coat. **2.** Filling a pump or siphon with fluid to enable flow. **3.** The first or annual filling of a canal or reservoir with water.

princess post Subsidiary verticals, between queen posts or the king post, and walls, used to stiffen a roof truss.

principal **1.** The principal authority or person responsible for a business such as architecture, engineering, or construction. **2.** The capital amount of a loan or other obligation as distinguished from the interest. **3.** In professional practice, any person legally responsible for the activities of that practice. **4.** The person or entity under whose debt or obligation is the subject or a performance or payment bond issued by a surety.

principal beam The main beam in a structural frame.

principal-in-charge The professional individual within a design firm ultimately responsible for monitoring services in connection with a given project.

principal post A corner post in a framed building or a door post in a framed partition.



principal post

principal rafter One of the diagonals in a roof truss that support the purlins on which rafters are laid.

principal stress Maximum and minimum normal stresses at a point in a stressed body.

prism A surveying device used as a reference target when using electronic equipment to measure distance.

prismatic beam A beam with a uniform cross section. Both of its flanges run parallel along its longitudinal axis.

prismatic glass Glass with parallel prisms rolled into one face. The prisms refract light rays and change their direction.

private branch exchange (PBX) A telephone system, located on a customer's premises, that is owned and operated by the customer rather than a telephone company. A PBX system switches internal calls between the customer's users on local lines while also making external lines available. Using a PBX can save a customer money because it eliminates the need for direct lines from each user to the telephone company.

privy An outhouse serving as a toilet.

probabilistic design Method of design of structures using the principles of statistics (probability) as a basis for evaluation of structural safety.

processed shake A sawn cedar shingle that is textured on one surface to resemble a split shingle.



processed shake

Proctor compaction test A test to determine the moisture content of a soil at which maximum compaction can be obtained. The test establishes the density-moisture relationship in a soil.

Proctor curve Plot of the dry density of soil resulting from standard lab compactive effort versus moisture content.

product data Information furnished by the manufacturer to illustrate a material, product, or system for some portion of the work which includes illustrations, standard schedules, performance charts, instructions, brochures, diagrams, warranties.

production costs Parts of the actual, physical project, including materials, labor, tools, equipment, and subcontractor costs for each task or activity incorporated in the final structure.

production schedule A short-interval schedule used to plan and coordinate a group of activities.*

productivity Work performed per unit of time, or time to perform unit of work, such as square feet per hour.

products liability insurance Insurance for liability imposed for damages caused by an occurrence arising out of goods or products manufactured, sold, handled, or distributed by the insured or others trading under the insured's name. Occurrence must occur after product has been relinquished to others and away from premises of the insured.

product standard A published standard that establishes: **1.** dimensional requirements for standard sizes and types of various products; **2.** technical requirements for the product; and **3.** methods of testing, grading, and marking the product. The objective of product standards is to define requirements for specific products in accordance with the principal demands of the trade.

professional corporation A corporation created expressly for the purpose of providing professional practice and related services, which may have special requirements under the law, as opposed to requirements for corporations in general.

professional engineer A professionally qualified and duly licensed individual that performs engineering services such as structural, mechanical, electrical, sanitary, and civil engineering.

professional liability insurance Insurance coverage protecting against legal liability for damage claims sustained by others. Damage claims allege negligent acts, errors, or omissions in the performance of professional services.

professional practice The conduct and work of a design professional in which services are rendered within the framework of recognized professional ethics, standards, and applicable legal requirements.

profile A drawing showing a vertical section of ground, usually taken along the center line of a highway or other construction project.

profit Earnings from an ongoing business after direct and project indirect costs of goods sold have been deducted from sales revenue for a given period (gross profit).

profit margin Ratio of profit to either total cost or total revenue. Usage often varies depending on the type of company. Retail companies generally use the profit-to-revenue ratio. Wholesale companies and contractors generally use the profit-to-cost ratio.*

profit sharing Provisions in special agreements or contracts for construction where the contractor, as an incentive to save money for the owner, is paid, in addition to the final contract sum, some percentage of any net savings he may achieve if he is able to deliver the finished project to the owner's satisfaction at a total cost below a specified limiting amount.

proforma A project specific projection of future income and expenses used to evaluate the project's investment worthiness.

pro forma invoice An invoice sent before the order has been shipped in order to obtain payment before shipment.

program A written statement presenting design objectives, constraints, and project criteria, including space requirements and relationships, flexibility and expandability, special equipment, and systems and site requirements.

program manager An official in the program division who has been assigned responsibility for accomplishing a specific set of program objectives. This involves planning, directing and controlling one or more projects of a new or continuing nature, initiation of any acquisition processes necessary to get project work under way, monitoring of contractor performance and the like.

programming phase The design stage in which the owner develops and provides full information regarding requirements for the project, including a program.

progress chart A chart that shows various operations in a construction project, such as excavating and foundations, along with planned start and finish dates in the form of horizontal bars. Progress is indicated by filling in the bars.

progressive kiln A dry kiln in which green lumber enters one end and is dried progressively as it moves to the other end where it is removed.

progress payment A scheduled partial payment made during the work process to cover costs of work completed or materials delivered to date.

progress schedule A pictorial or written schedule (including a graph or diagram) that shows proposed and actual start and completion dates of the various work elements.

project The total construction activities, usually on one site. The work performed under the contract documents may be the whole or a part of the project.

project architect The party designated by the principal-in- charge to manage a given project for a firm.

project certificate for payment A statement to the owner confirming the amounts due individual contractors. Issued by the design professional where multiple contractors have separate necessary agreements with the owner.

project cost The total project cost, which includes the cost of construction, professional compensation, land, furnishings and equipment, financing, and other charges.

project designer (designer's office) The person assigned by the principal-in-charge to be responsible for guiding the overall direction of a project's design.

projected window A window with one or more sashes that swing either inward or outward.


projected window

project engineer An assistant to the contractor's project manager who is responsible for the documentation required for the management of the project. Often refers to an individual who uses engineering and management skills though is not necessarily a registered professional."

project evaluation and review technique (PERT) schedule A schedule that charts the activities and events anticipated in a work process.

project float The time that exists between the early finish of the last activity of a CPM network and the contractual completion date of the project. Project float can be internalized into the network and become network float.*

projecting belt course A course of masonry that projects beyond the face of the wall to form a decorative shelf.

projecting brick One of a number of bricks that project from a wall to form a pattern.

projection Any component member or part that extends out from a building for a relatively short distance.


projection

project management **1.** The utilization of skills and knowledge in coordinating the organizing, planning, scheduling, directing, controlling, monitoring and evaluating of prescribed activities to ensure that the stated objectives of a project, manufactured product, or service, are achieved. **2.** The art and science of managing a project from inception to closure as evidenced by successful product delivery and transfer.*

project manager The individual designated by the principal-in-charge to manage a given project. Normally includes administrative and technical responsibilities.

project manual A bound booklet that contains the contract documents, with the exception of the drawings, specifically organized into bid requirements, contract information, general conditions for constructions and technical specifications.

project record documents The documents, certificates, and other information relating to the work, materials, products, assemblies, and equipment that the contractor is required to accumulate during construction and convey to the owner for use prior to final payment and project closeout.

project representative The architect's representative at the project site, who assists in the administration of the construction contract.

project team A collection of professional entities directed and otherwise coordinated to perform work or services for a project.

project web site An Internet site created for those involved in a specific construction project with the goal of increasing efficiency by improving access to information. Such sites can make a variety of information available—from a file of project team members and their e-mail addresses, to the project manual, field reports, meeting notes, and the shop drawing log.

promissory estoppel An equitable doctrine that prevents subcontractors from withdrawing their bids prior to acceptance by the prime contractor, making a subcontractor's quote binding if it meets specific criteria.

promissory note A legal instrument, agreement, or contract made between a lender and a borrower by which the lender conveys to the borrower a sum or other consideration known as principal for which the borrower promises repayment of the principal plus interest under conditions set forth in the agreement.

proof stress **1.** Stress applied to materials sufficient to produce a specified permanent strain. **2.** A specific stress to which some types of tendons are subjected in the manufacturing process as a means of reducing the deformation of anchorage, reducing the creep of steel, or ensuring that the tendon is sufficiently strong.

property damage insurance Insurance covering legal liability for claims for injury to or destruction of tangible property (including loss of use). *See also* **care, custody, and control**.

property insurance Insurance that compensates the insured for loss of property (real or personal) resulting from direct physical damage. Damages include fire, lightning, extended coverage perils, vandalism, and malicious mischief, among other damages.

property line A recorded boundary of a plot.

property survey A professional examination of documents and land to determine specific boundaries.

proportional control In an HVAC system, the controlled device (valve or damper) is positioned proportionally in response to slight changes in the controlled variable (temperature, pressure).

proportional limit The greatest stress that a material is capable of developing without any deviation from proportionality of stress to strain (Hooke's Law).

proprietary specification A specification that describes a product, material, assembly, or piece of equipment by trade name and/or by naming the manufacturer or manufacturers who may produce products acceptable to the owner or design professional.

protected corner Corner of a slab with adequate provision for load transfer, so that at least 20% of the load from one slab corner to the corner of an adjacent slab is transferred by mechanical means or aggregate interlock.

protected noncombustible construction Noncombustible construction in which bearing walls (or bearing portions of walls), whether interior or exterior, have a minimum fire resistance rating of two hours and are stable under fire conditions. Roofs and floors, and their supports, have minimum fire resistance ratings of one hour. Stairways and other openings through floors are enclosed with partitions having minimum fire resistance ratings of one hour.

protected opening An opening, in a rated wall or partition that is fitted with a door, window, or shutter having a fire resistance rating appropriate to the use of the wall.

protected ordinary construction Construction in which roofs and floors and their supports have a minimum fire resistance rating of one hour, and stairways and other openings through floors are enclosed with partitions that have minimum fire resistance ratings of one hour. Such construction must also meet all the requirements of ordinary construction.

protected wood-frame construction Construction in which roofs and floors and their supports have minimum fire resistance ratings of one hour, and stairways and other openings through floors are enclosed with partitions with minimum fire resistance ratings of one hour. Such construction must also meet all the requirements of wood frame construction.

protection board Asphalt-impregnated boards used in roofing installations to protect bituminous coatings from damage.

protocol A procedure or practice established by long or traditional usage and currently accepted by a majority of practitioners in similar professions or trades. Protocol represents the generally accepted method of action or reaction that may be expected to be followed in a transaction.

proving ring A device for calibrating load indicators of testing machines, consisting of a calibrated elastic ring and a mechanism or device for indicating the magnitude of deformation under load.

proximate cause The cause of an injury or of damages which, in natural and continuous sequence, unbroken by any legally recognized intervening cause, produces the injury, and without which the result would not have occurred. Existence of proximate cause involves both **1.** causation in fact, i.e., that the wrongdoer actually produced an injury or damages, and **2.** a public policy determination that the wrongdoer should be held responsible.

proximity switch A sensor that is activated by the intrusion of objects into an area.

psychrometer An instrument for measuring water vapor in the atmosphere, utilizing both wet- and dry-bulb thermometers.

psychrometric chart A chart that graphically represents the interrelation of air temperature and moisture content. Commonly used by building engineers and designers.


p-trap

p-trap P-shaped trap that provides a water seal in a waste or soil pipe, used mostly at sinks and lavatories.

public liability insurance Insurance covering liability for negligent acts causing bodily injury, disease, or death of persons other than employees of the insured. Also covers liability for property damage.

public sewer A common sewer controlled completely by a public authority.

public space **1.** An area within a building to which the public has free access, such as a foyer or lobby. **2.** An area or piece of land legally designated for public use.

public utility A service for the public such as water, sewers, telephone, electricity, or gas.

public water main A water supply pipe controlled by public authority.

public way A street, alley, or other parcel of land open to the outside air and leading to a public street. A public way is deeded or otherwise permanently appropriated for public use. A minimum width is usually specified by code.

puddle **1.** To settle loose soil by flooding and turning it over. **2.** To vibrate and/or work concrete to eliminate honeycomb. **3.** Clay that has been worked with some water to make it homogeneous and increase its plasticity so it can be used to seal against the passage of water.

puddle weld A weld used to join two sheets of light-gauge metal. A hole is burned in the upper sheet and filled with weld metal to fasten the two together.

puff pipe A short vent pipe on the outlet side of a trap; used to prevent siphoning.

pug box **1.** A box, with a removable cover, placed in an electric raceway to facilitate the pulling of conductors through the raceway. **2.** A manual activator for a fire alarm system.

pugging A layer of clay, mortar, sawdust, or felt used for soundproofing purposes.

pug mill **1.** A machine for mixing and tempering clay. **2.** The part of an asphaltic concrete plant where the heated batch materials are mixed.

pull **1.** A handle used for opening a door, drawer, etc. **2.** To loosen rock at the bottom of a hole by blasting.

pull-chain operator A chain or control used to open or close a device such as a damper.

pulldown handle A handle fixed to the bottom rail of the upper sash of some double-hung windows.

pulley (pulley sheave) A wheel, with a grooved rim, that carries a rope or chain, and turns on a frame.


pulley (pulley sheave)

pulley block A frame that contains one or more pulleys.


pulley block

pulley stile The upright in a window frame on which the sash pulleys are supported and along which the sash slides.

pulling **1.** The drag on a paintbrush caused by high paint viscosity. **2.** Installing and connecting wires in an electric system.

pull scraper A hand scraper, consisting of a steel blade at approximately right angles to the handle, that is used to remove old finishes or for smoothing wood.

pulpboard A solid board composed of wood pulp.

pulsed arc transfer An arc welding method that involves operating a power source between low and high current levels. The high current level, called a "pulse," forces an electrode drop to the workpiece, while the low current level, or "background," maintains the arc between pulses. Major benefits of the process include better arc characteristics and greatly reduced spatter and fume generation.

pulse tube boiler A boiler using a sealed combustion system in which residual heat from the initial cycle ignites all subsequent air-gas mixtures, and flue gas condensation takes place in the heat exchanger.

pumice A highly porous lava, usually of relatively high silica content, composed largely of glass drawn into approximately parallel or loosely entwined fibers.

pumice concrete A lightweight concrete in which pumice is used as the coarse aggregate and which has good thermal insulation value.

pumice stone A solid block of pumice used to rub or polish surfaces.

pump A machine, operated by hand or a prime mover, used to compress and/or move a fluid.

pumped concrete Concrete that is transported through a hose or pipe by means of a pump.

pump head The pressure differential produced by an operating pump.

pumping (of pavements) The ejection of water, or water and solid materials, such as clay or silt, along transverse or longitudinal joints and cracks, and along pavement edges. Pumping is caused by downward slab movement activated by the passage of loads over the pavement after the accumulation of free water on or in the base course, subgrade, or subbase.

pump jack An adjustable support used to raise and lower scaffolding.

pump mix Concrete formulated for placement using a pump.

puncheon **1.** Roughly dressed, heavy timber used as flooring, or as a footing for a foundation. **2.** Short timbers supporting horizontal members in a cofferdam.

punching shear **1.** Shear stress calculated by dividing the load on a column by the product of its perimeter and the thickness of the base or cap, or by the product of the perimeter taken at one half the slab thickness away from the column and the thickness of the base or cap. **2.** Failure of a base when a heavily loaded column punches a hole through it.

punch list A list of items within a project, prepared by the owner or his representative, and confirmed by the contractor, which remain to be replaced or completed in accordance with the requirements of the contract for construction at the time of substantial completion.

punitive damages (exemplary damages) Damages are awarded by a judge to a plaintiff not merely to compensate the plaintiff for losses incurred, but to punish the defendant for wrongful conduct and to use the plight of the defendant as an example to potential wrongdoers.

purchase order A formal written authorization to a vendor to provide certain goods or services and to bill the buyer for them at the specified price. The purchase order becomes a contract when it is accepted by the vendor.

purge To remove unwanted liquid, sediment, air or gas from a ductline, pipeline, container, space, or furnace.

purge pump A compressor that removes noncondensibles from a refrigeration system.

purlin One of several horizontal structural members that support roof loads and transfer them to roof beams.



purlin

purlin cleat A shaped metal fastener used to secure a purlin to its support.



purlin cleat

purlin plate A purlin, in a curb roof, located at the curb and supporting the ends of the upper rafters.

purlin post A strut that supports a purlin to reduce sag.

purlin roof A roof in which purlins are supported directly on walls rather than rafters.

push bar A heavy bar across a glazed door, screen door, or horizontally pivoted window sash, used to open or close the door or window.

push drill A hand drill that is operated by pushing on its handle. A spiral ratchet rotates the bit.

push hardware A fixed bar or plate operated by pushing.

push plate A metal plate used to protect a door while it is pushed open.

push point A thin piece of metal used in glazing to hold glass in a wooden frame. A bent section of the point makes it easy to push the point into the wood.

push stick A tool or piece of wood used with a table saw to guide the wood being cut.

putlog Short pieces of timber that support the planks of a scaffold. One end of the timber is supported by the scaffold, the other is inserted in a temporary hole left in the masonry.

putlog hole The temporary hole in masonry that supports one end of a putlog.

putty A doughlike mixture of pigment and vehicle, used to set glass in window frames and fill nail holes and cracks.

putty coat Final smooth coat of plaster.

putty knife A knife, with a broad flexible blade with a flat end, used to apply putty.

pycnometer A vessel for determining the specific gravity of liquids or solids.

pylon **1.** A steel tower used to support electrical high-tension lines. **2.** A movable tower for carrying lights.

pyramidal light A skylight shaped like a pyramid.

pyramidal light

pyrolyze To bring about a chemical change through the action of heat.

pyrometer An apparatus for measuring high temperatures.

pyrometric cone A small, slender, three-sided oblique pyramid made of ceramic or refractory material for use in determining the time-temperature effect of heating and in obtaining the pyrometric cone equivalent of refractory material.

Q

Abbreviations

q quart

Q quantity heat flow

qa quality assurance

qc quality control

QC quick coupling

QA/QC quality assurance/quality control

qda quantity discount agreement

QF quick firing

qr quarter

QR quarter-round

Qrtz quartz

qs quarter-sawn

qt quart

qty quantity

QTR quarry-tile roof; on drawings, quarter

quad quadrant

QUAD quadrangle

QUAL quality

QUAN quantity

quar quarterly

Definitions

quadrangle (quad) An open rectangular courtyard surrounded on all sides by buildings.

quadrant **1.** One quarter of the circumference of a circle; an arc of 90°. **2.** An angle-measuring instrument.

quad-tube lamp A compact fluorescent lamp with a double twin tube configuration.

qualifications and assumptions Items that are not completely defined in the project documents for which the estimator is required to use judgment in developing the estimate.*

qualification submittals Data pertaining to a bidder's qualifications that must be submitted as set forth in the instructions to bidders.*

qualitative analysis The analysis of a sample (solid, liquid, or gas) to identify its components.

quality Characteristics of a product, material, or installation/workmanship that may determine its durability, longevity, appearance, safety, efficiency, and/or other attributes. A grade of Idaho white pine equivalent to D *select* in other species.

quality acceptance criteria Specified limits placed on characteristics of a product, process, or service defined by codes, standards, or other requirement documents.*

quality appraisal Quality activities employed to determine whether a product, process, or service conforms to established requirements, including: design review, specification review, other documentation review, constructability review, materials inspection/tests, personnel testing, quality status documentation, and post project reviews.*

quality assurance A system of procedures for selecting the levels of quality required for a project or portion thereof in order to perform the functions intended, and for assuring that these levels are obtained.

quality audit A formal, independent examination with intent to verify conformance with the acceptance criteria. An audit does

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

not include surveillance or inspection for the purpose of process control or product acceptance.*

quality conformance Quality management activities associated with appraisal, training, and prevention adapted to achieve zero deviations from the established requirements.*

quality control A system of procedures and standards by which a constructor, product manufacturer, materials processor, or the like, monitor the properties of the finished work.

quality corrective action Measures taken to rectify conditions adverse to quality and, where necessary, to preclude repetition. Corrective action includes rework and remedial action for nonconformance deviations.*

quality management Concerns the optimization of the quality activities involved in producing a quality product, process or service. As such, it includes appraisal, training, and prevention activities. *

quality performance tracking system A management tool providing data for the quantitative analysis of certain quality-related aspects of projects by systematically collecting and classifying costs of quality.*

quantification In estimating practice, an activity to translate project scope information into resource quantities suitable for costing. In the engineering and construction industry, a take-off is a specific type of quantification that is a measurement and listing of quantities of materials from drawings.*

quantitative analysis The analysis of a sample (solid, liquid or gas) to determine the proportions of its various components.

quantity overrun/underrun The difference between estimated quantities and the actual quantities in the completed work.

quantity survey A detailed analysis of material and equipment required to construct a project.

quarry An open excavation in the surface of the earth for mining stone.

quarry run Indiscriminate building stone as it comes from the pit without regard to color or structure.

quarrystone bond In masonry, a term applied to the manner in which stone is arranged in rubblework.

quarry (promenade) tile Machine-made, unglazed tile.

quarry tile Clay tile used for flooring or walls.

quarter bend A 90° bend, as in piping.



quarter bend

quarter closer (quarter closure) A brick cut to one-fourth of its normal length; used either as a spacer, or to complete a course.

quartered lumber Lumber that has been quarter-sawn approximately radially from the log.

quartered veneer Veneer that has been sliced in a radial direction, that is, at right angles to the growth rings. The term *quartered* comes from the use of blocks that have been cut into quarters before slicing. Quarter slicing brings out the presence of medullary rays; quarter-sliced veneer appears striped.

quarter hollow A concave molding formed by a 90° arc; the opposite of a quarter round.

quarter round A type of molding used as a base shoe; presenting the profile of a quarter circle.

quarter round

quartersawn (rift-sawn) Lumber sawn so that the annual rings form angles from 45° to 90° with the surface of the piece.

quarter-turn Descriptive of a stair that turns 90° as it progresses from top to bottom.

quartz glass (silica glass) Glass consisting of pure, or nearly pure, amorphous silica. Of all glass, qua6eriors often incorporated turrets, dormers, hip and gable roofs, bay windows, and extensive decorative moldings or carvings. Wood, stone, or stucco was used in addition to brick.



quarter-turn

queen closer A half-brick of normal thickness, but half-normal width. Used in a course of brick masonry to prevent vertical joints from falling above one another.



queen closer

queen-post truss (queen truss) A pitched roof support using two vertical tie posts connected between the tie beam and the rafters.

quenching Immersing hot, solid items in a cool liquid. Used as a means of tempering metals.

quick condition Soil that is weakened by the upward flow of water. Minute channels are created that significantly reduce the bearing capacity of the soil.

quick-load test Compression testing of piles that applies loads of increasing weight for brief time periods.

quick response sprinkler A sprinkler very sensitive to high temperatures, that reacts quickly to a fire, helping to limit smoke damage by arresting the fire at an earlier stage.

quick test A test performed on a cohesive soil to measure shear, before the sample has drained.

quirk **1.** A narrow groove or bead located at or near the intersection of two surfaces or next to a molding, so as to reduce the possibility of uncontrolled cracking. **2.** Acute angle between adjoining pieces of molding. **3.** Thin groove on the bottom of a drip cap to keep water away from the joint.

quirk molding **1.** Trim piece with a narrow groove. **2.** Trim with both inward and outward curves.

quoin (coign, coin) **1.** A right-angle stone in the corner of a masonry wall to strengthen and tie the corner together. **2.** Keystone in an arch.



quoin

quotation A price for materials or services provided by a contractor, subcontractor, supplier, or vendor.

quote To make an offer at a guaranteed price.

Q

R

Abbreviations

r	rain, range, rare, red, river, roentgen, run
R	radius, right, symbol for capacity of a pile
Ra	radium
RA	remedial action, return air, registered architect
R&A	(facility) repair and alteration
rab	rabbeted
RAB	rabbet
rad	radiator
raft	rafter
RAG	return air grate
RAM	rapid access memory, risk assessment methodology
RAMCAP	Risk Analysis and Management for Critical Assets Protection
RAT	return air temperature
RBM	reinforced brick masonry
RC, R/C	reinforced concrete, red cedar
RC asphalt	rapid-curing asphalt
RCM	reliability-centered maintenance
RCP	reinforced concrete pipe
RCR	room cavity ratio
RCRA	Resource Conservation and Recovery Act
RCx	retro-commissioning (of existing buildings)
1/4 RD	quarter-round
1/2 RD	half-round
rd	road, rod, round
RD	roof drain, round, remedial design
rdm	random
rebar	reinforcing bar
recap	recapitulation
recd	received
recip	reciprocal
RECP	receptacle
rec room	recreation room
rect	rectangle, rectified
red	reduce, reduction
ref	reference, refining
REF	refer, reference
REFR	refractory, refrigerate
refrig	refrigeration
reg	registered
Reg	regular
REG	register, regulator
rein, reinf	reinforced
REINF	reinforce, reinforcing
REIT	real estate investment trust
REM	removable
remod	remodel
rent	rental
rep, REP	repair
repl, REPL	replace, replacement
REPRO	reproduce
reqd, REQD	required
res	resawn
ret	retain, retainage

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

c18.indd 250 06/09/12 9:04 AM

RET return

RETS real estate transaction standard

rev revenue, reverse, revised

REV revise

rf roof

RF roof, radio frequency, return fan

RFA RCRA Facility Assessment

RFC request for comment

RFD reduced function device

Rfg roofing

RFI radio frequency interference, request for information

RFI/CMS RCRA Facility Investigation/Corrective Measures Study. *See also* **RCRA**.

RFP request for proposal

RFQ request for quotation, request for qualifications

rgh, Rgh rough

RG 6 type of coaxial cable

Rh rhodium, Rockwell hardness

RH relative humidity

RHN Rockwell hardness number

RI refractive index, remedial investigation

RIBA Royal Institute of British Architects

rib gl ribbed glass

RI/FS Remedial Investigation/Feasibility Study

RIS Redwood Inspection Service

riv river

Rj road junction

RKI rotary kiln incineration

R/L, RL random lengths

rm ream, room

RM room

r mld raised mold

rms root mean square

ROD record of decision

ROP record of production

ROPS rollover protection system

rot rotating, rotation

rpm revolutions per minute

RPP remote power panel

RRGCP reinforced rubber gasket concrete pipe

RRM rapidly renewable materials

RRS railroad siding

R/S resawn

RSF rentable square feet

RSJ rolled steel joist

RSPA Research and Special Program Administration

rt right

RT raintight, real temperature, real time

RTD resistance temperature detector

RTN return to normal

Rub, rub Ruberoid, rubble

rw redwood, roadway, right-of-way

RW, R/W random widths, right-of-way

R/W&L, RW/L random widths and lengths

rwy, ry railway

rab A rod or stick used to mix concrete or mortar.

Definitions

rabbet A cut or groove along or near the edge of a piece of wood that allows another piece to fit into it to form a joint.

rabbet depth The depth of a glazing rabbet.

rabbeted lock (rebated lock) A lock that is fitted into and flush with the rabbet on a rabbeted doorjamb.

rabbet joint A longitudinal edge joint formed by fitting together rabbeted boards.

rabbet plane A plane for cutting a rabbet or fillister in wood, open on one side, with the blade extending to the open side.



rabbet joint

rabbet size The actual size of a rabbeted glass opening, equal to the glass size plus two edged clearances.

race **1.** A channel intended to contain rapidly moving water. **2.** A groove in a machine part in which an object moves.

raceway **1.** Any furrow or channel constructed to loosely house electrical conductors. These conduits may be flexible or rigid, metallic or nonmetallic, and are designed to protect the cables they enclose. **2.** A man-made channel for directing water flow as in a hydroelectric plant.



raceway

rack A framework of metal bars used to prevent waterborne trash from entering a waterway.

rack-and-pinion elevator A platform or enclosure in which linear motion is created by the use of a rotating gear pinion mated to, and revolving on, a vertical stationary rack.

racked A temporary support used to brace and prevent deformation.

racking (racking back) **1.** A method entailing stepping back successive courses of masonry in an unfinished wall. **2.** The movement of structural elements out of level or plumb by forces such as stress, wind, or material shrinkage or expansion. **3.** The installation of roof shingles in a straight line across the roof instead of on the diagonal. This method is quick, but is not often used because it can produce shingles incorrectly nailed and color variations.

rack saw A saw with wide teeth.

radial Radiating from, or converging to, a common center.

radial arch roof A roof supported by arches that radiate out from a central point.

radial-arm saw (radial saw) A circular saw suspended above the saw table on a cantilevered arm. The material remains stationary while the saw is free to move along its projecting beam.

radial-curved fans Backward-curved centrifugal fans with flat blades.

radial grating Grating in which the *bearing bars* extend radially from a common center, and the *cross bars* form concentric circles.



radial grating

radially cut grating Rectangular grating cut into panels shaped as segments of a circle to fit annular or circular openings.

radial shrinkage The shrinkage of wood across its diameter or growth rings as it dries.

radian The standard metric unit for a plane angle, as compared to customary units of degree (°), minute (′), and second (″).

radiance Light emitted or reflected from a designated area.

radiant barrier A reflective sheet or spray-on material applied to attic floors, rafters, or roof decking to reduce the flow of heat in and out of a building.

radiant cooling An efficient cooling system that typically involves running cool water through a building's floors, walls, or ceilings.



radiant cooling

radiant energy Energy traveling in electromagnetic waves.

radiant heating system A system with heating terminals that deliver heat by radiation from a hot surface, such as those heated by the flow of hot water or electric current.

radiation The transmission of energy by means of electromagnetic waves of very long wavelength. The energy travels in a straight line at the speed of light and is not affected by the temperature or currents of the air through which it passes.

radiator A visually exposed heat exchanger consisting of a series of pipes that allows the circulation of steam or hot water. The heat from the steam or hot water is given up to the air surrounding the pipes.



radiator

radio frequency interference (RFI) Disturbance of radio frequency bands by other high-frequency equipment nearby. Fluorescent lighting creates RFI.

radiological screening A soil test than can determine approximate areas of local contamination.

radius gauge (fillet gauge) A gauge that measures the radius of curvature of small concave and convex surfaces.

radius of curvature A measure of the dimensions of a curve, as in the radius of curvature of a directional wall.

radius of gyration An imaginary distance from an axis to a point such that, if an object's mass were concentrated at the point, the moment of inertia would not change.

radon An odorless, colorless radioactive gas given off by some soils and rock with a short half-life (less than four days). If found in homes in sufficient concentrations, radon exposure can cause health problems.

rafter One of a series of sloping parallel beams used to support a roof covering.



rafter

rafter plate A plate used to support the lower end of rafters and to which they are fastened.

rafter table A carpenter's square with a table of values for determining the lengths and angles of cut for roof rafters.

rafter tail That part of a rafter overhanging the wall.

raft foundation A continuous slab of concrete, usually reinforced. Employed as a foundation laid over soft ground, or where heavy loads must be supported.

rag felt An asphaltic felt consisting of rags saturated with asphalt, creating a waterproof composition for use on roofs, i.e., roofing paper and asphalt shingles.

ragwork Courses of irregular stone masonry laid in a random pattern without parallel surfaces. The stones are roughly shaped with nonuniform joints.

rail **1.** A horizontal member supported by vertical posts, e.g., a handrail along a stairway. **2.** A horizontal piece of wood, framed into vertical stiles, such as in a paneled door. **3.** Track used to direct or control the path of a vehicle or device.



rail

rail fence A barrier or boundary constructed of rails and their supporting posts.

railing **1.** A solid wood band around one or more edges of a plywood panel. **2.** A *balustrade.*

rails **1.** The horizontal members that form the outside frame of a door, including pieces used as a cross bracing between the top and bottom rails. **2.** The horizontal members of a fence between posts. **3.** The side pieces of a ladder to which rungs or steps are attached.

rail steel reinforcement Reinforcing bars hot-rolled from standard T-section rails.

Raimann patch (football patch) A patch, elliptical in shape, used to fill voids caused by defects in the veneers of plywood panels.

The Raimann patch is one of the two patch designs allowed in A-grade faces.

rain cap A protective cover installed at the top of a roof vent to prevent rain from entering. Sometimes screened to keep out birds as well.

rain catchment system Connected gutters, downspouts, and barrels or cisterns that capture and store rainwater for irrigation and indoor use.

rainscreen A method of constructing walls in which the cladding is separated from a membrane by an airspace that allows pressure equalization to prevent rain from being forced in. Often used for high-rise buildings or for buildings in windy locations.

rain sensor An electronic device that shuts off an automatic sprinkler system when it rains, conserving water when irrigation is not needed.

rainwater harvesting On-site rainwater collection and storage systems used to offset potable water needs for a building and/or landscape. Systems can take a variety of forms, but usually consist of a surface for collecting precipitation (roof or other impervious surface) and a storage system.

rainwet **1.** Lumber that has excess moisture content because of exposure to rain after it was dried. **2.** Surface lumber that has been stained or weathered by exposure to rain.

raised flooring system A floor constructed of removable panels supported by stringers allowing easy access to the space below.

raised girt (flush girt, raised girth) A stiffening member, parallel to and level with the floor joists, used to strengthen and protect.

raised molding A molding not on the same level or plane as the wood member or assembly to which it is applied.

raising hammer A hammer with a long head and a rounded face that is used in sheet metal work.

rake **1.** To slant or incline from the vertical or horizontal. **2.** A board or molding that is placed along the sloping edge of a frame *gable* to cover the edges of the siding. **3.** A tool used to remove mortar from the face of a wall.



rake

raked joint A joint in a masonry wall that has the mortar raked out to a specified depth while it is still soft.



raked joint

raker **1.** A sloping brace for a *shore head.* **2.** A tool for raking out decayed mortar from the joints of brickwork.

rake trim Flashing used to close gap between the roof and the end walls.

raking course A course of bricks laid diagonally across faces of a brick wall for added strength.

raking flashing A parallel flashing used at the intersection of a chimney or other projection, with a sloping roof.

raking riser A riser that is not vertical, but slopes away from the *nosing* for added foot room on the lower riser.

raking stretcher bond A bond in brickwork in which the vertical joint of each brick is displaced a small, fixed distance from the vertical joint of the brick below.

ram **1.** A cylinder that contains a plunger instead of a piston and rod. **2.** The plunger in a hydraulic press.

rammed earth Earth formed into thick, durable monolithic building walls that are energy efficient and fire resistant. Typically used in hot, dry climates, rammed earth walls are composed of screened engineered soil and cement, formed to be 18″ or 24″ thick. If used in cooler climates, rammed earth may require supplemental insulation or additional heating or cooling.



rammed earth

ramming A form of heavy tamping of concrete, grout, or the like by means of a blunt tool forcibly applied.

ramp A sloping surface to provide an easy connection between floors.

rampant vault A type of barrel vault exhibiting two quarters of different radii. The quarters have a common crown but the abutments are at different levels.

random ashlar (random bond) Constitutes ashlar masonry in which stones are set without continuous joints, and appear to follow a random pattern, although a large pattern may be repeated.



random ashlar (random bond)

random lengths (RL) Lumber of various lengths. A random length loading is presumed to contain a fair representation of the lengths being produced by a specific manufacturer.

random paneling Board paneling of varying widths of the same grade and pattern. The term refers to plywood paneling grooved to represent random width paneling.

random shingle One of a number of shingles of the same length, but varying widths.



random shingle

random widths Boards, lumber, and shingles of varying widths.

range **1.** A row or course of masonry. **2.** A straight line of objects such as columns. **3.** The difference between prices, costs, estimates, and bids.

range-in (wiggling-in) The term used by a surveyor for the trial-and-error procedure of finding a previously established line.

range lines North-south lines used as reference points in the rectangular survey system, originally created to survey land in the U.S. public domain.

range rod (range pole) A device that consists of a pole 7′ to 8′ long, equipped with a metal point. It is painted alternately red and white in bands 1′ wide. The pole is used by surveyors for locating points of reference.

rapid-curing asphalt A liquid composed of asphalt, cement, and a highly volatile diluent such as naphtha or gasoline.

rapid-hardening cement A high-early-strength cement.

rapidly renewable materials (RRM) Raw materials such as cork, bamboo, and straw that can be regrown quickly and are therefore considered sustainable.

rapid-start fluorescent lamp A fluorescent lamp designed for operation with a ballast that provides a low-voltage winding to preheat the electrodes and initiate the arc without a starting switch or the application of high voltage.

ratchet A mechanism with a hinged catch, or pawl, that slides over and locks behind sloped teeth on a gear or rod, allowing motion in one direction only.



ratchet

ratchet brace A carpenter's clamp used in confined spaces where a full turn of the brace cannot be achieved. It is fitted with a pawl mechanism allowing the bit to be rotated while in the hole.

ratchet drill A hand-operated drill that works with a hinged catch engaging on a wheel or chuck.



ratchet brace

rated lamp life The average life of a particular lamp fixture.

rated load The overall weight that a piece of machinery is designed to carry.

rated speed The speed at which a piece of machinery is designed to operate with an appropriate load.

ratio The relative size of two quantities expressed as one divided by the other.

rat-tail file A file with a circular cross-section that tapers to a small diameter at the end opposite the handle.

raveling A term used for the progressive deterioration of asphalt pavement. The aggregate dislodges and becomes fragmented.

raw linseed oil Linseed oil that has been refined, but has not received further processing such as boiling, blowing, or bodying.

rawl plug A short fiber cylinder with a lead lining, driven into a hole in wood, masonry, glass, plaster, tile, concrete, or other materials to receive and hold a screw.



rawl plug

raw material A material used for the construction or manufacture of goods or products.

raw water Water that requires treatment before it can be used, such as water for steam generation.

raze To tear down, demolish, or level to ground.

RCRA Facility Assessment (RFA) A site investigation, regulated under RCRA, that is used to determine the nature and extent of contamination at a particular location.

RDX (cyclotrimethylenetrinitramine) An explosive commonly encountered in unexploded ordnance sites.

reactance Opposition to alternating current (AC) by capacitance or inductance or both. It is expressed in ohms, and symbolized by X.

reaction Resistive forces acting on a structural member that serve to hold it stable.

reactivated carbon Carbon that has been used for volatile organic compound adsorption, which is then treated for reuse.

reactive aggregate Aggregate containing substances capable of reacting chemically with the products of solution or hydration of the Portland cement in concrete or mortar, under ordinary conditions of exposure, resulting in harmful expansion, cracking, or staining.

reactive silica material Several types of materials that react at high temperatures with Portland cement or lime during autoclaving, including pulverized silica, natural pozzolan, and fly ash.

ready-mixed concrete Concrete manufactured for delivery to a purchaser in a plastic and unhardened state.

ready-mixed plaster A calcined gypsum plaster with aggregate added during manufacture. A powder product that requires the addition of water.

reagent A substance used in analysis and synthesis of chemical reactions.

realignment A change in the horizontal layout of a highway, may also affect vertical alignment.

real property (real estate) Land and anything growing on the land, or constructed on it, such as buildings, stone walls, fences, driveways, garages, underground swimming pools, trees, shrubs, and gardens. Real property also includes *fixtures*, or items that are permanently affixed to real property, such as light fixtures, oil burners, fuse boxes, and plumbing. Real property does not include things that are grown on the land for the purpose of being sold, such as crops, or trees from a tree farm. Such products that are to be severed from real property and sold are treated as *goods*.

reamer A bit with sharp, spiral, fluted, cutting edges along the shaft that may be slightly tapered. Used to enlarge drilled holes or remove burrs from the inside of pipe.



reamer

reasonable cost A cost that would be incurred by an ordinarily prudent person in the conduct of competitive business.

rebar Short for reinforcing bar.

rebound Aggregate and cement or wet shotcrete that bounces away from a surface against which it is being projected.

rebound hammer An apparatus providing a rapid indication of the strength of concrete based on the distance of rebound of a spring-driven missile.

rebutted and rejointed (R&R) Shingles with edges machine-trimmed to be exactly parallel and butts retrimmed at precisely right angles for use primarily in sidewall applications.

receipt of bids The official action of an owner in receiving sealed bids that have been invited or advertised in accordance with the owner's intention to award a contract for construction.

receiver A tank to hold fluids or gases, as on an air compressor.

receptacle A contact device installed in an electric outlet box for the connection of portable equipment or appliances.



receptacle

receptor The shallow basin in the floor of a shower.

recessed fixture A lighting fixture the bottom edge of which is flush with the finish surface.



recessed fixture

recessed pointing A type of joint where the mortar is kept back approximately ¼″ from the face of the wall. This particular joint protects the mortar from peeling.

recharging **1.** The replenishment of ground water through direct injection or infiltration from trenches outside the area. **2.** The replenishment of electric energy in a storage battery.



recessed pointing

reciprocal leveling A surveying technique used in leveling across streams, gullies, and other obstructions. To eliminate instrumental errors, levels are taken from two setups, one near each point.

reciprocating chiller (reciprocating compressor) Single-acting compressor using pistons that are driven by a connecting rod from a crankshaft.

reciprocating compressor An air compressor using a piston to compress the air, and employing valves for intake and discharge.

reciprocating engine A steam or internal-combustion engine with cylinders and pistons as opposed to a turbine.

reciprocating pump A water pump using a piston(s) for intake and discharge. Depending upon valve arrangement, the pump can be either single- or double-acting.

reciprocating saw A saw operated in a back and forth or up and down motion extending from an engine or other power source, e.g., a saber saw.



reciprocating saw

recirculated air Return air that is reconditioned and distributed once again, as opposed to makeup air.

reclaimed lumber Wood building materials removed from a deconstructed building in such a way that they can be reused for nonstructural purposes.

recloser Device that protects a power system from service interruption by automatically opening and closing as overcurrents (short circuits) are detected. They detect the fault, close and reset to open the line, often more than once. It clears the fault and reenergizes the distribution line.

reconstruction The process of depicting (by means of new construction) the form, features and detailing of a nonsurviving site, landscape, structure or object for the purpose of replicating its appearance at a specific period of time, and in its historic location.

record of decision (ROD) An agreement between the site owner(s) and other responsible parties and the regulators that stipulates the remedial action requirements, schedule, and cost sharing for cleanup.

recovery peg A temporary surveying marker of known location and elevation, used to reestablish a permanent marker that is to be replaced.

rectangular survey system A land survey system using longitude and latitude geographical coordinates. Established by the U.S. government, it is also called *government survey system*.

rectangular tie A piece of bent heavy wire in the shape of a rectangle used as a wall tie.

rectifier An electrical device that converts alternating current (AC) to direct current (DC).

recycle Revisiting partially or fully completed activities to perform additional work due to a change.*

recycled concrete Hardened concrete that is crushed to be used as aggregate.

recycled content Products such as steel, plastic lumber, and carpet cushion, fabricated with postconsumer materials or postindustrial byproducts.

recycling Reusing, reprocessing, or refabricating products after their initial use. Examples of recycled products include some types of tile, glass, asphalt paving, masonry, metal framing, insulation, toilet compartments, and carpet.

redesign Creating a plan to change an existing building to a new appearance or configuration.

red herring A proposed contract term that is not critical, but is offered for the purpose of distracting the other party.

red label A grade of shingle between blue label #1 and black label #5, graded by the Red Cedar Shingle and Handsplit Shake Bureau.

red lead A compound of lead used in paints to improve the anticorrosive properties of the paint used on steel and iron.

red oxide A pigment used in paints to prevent rusting and corrosion.

redress **1.** Financial compensation for a loss caused by the actions of another. **2.** To set right, remedy, or rectify.

red rot An early stage of decay.

redry To turn material to a dry kiln or veneer dryer for additional drying when the material is found to have a higher moisture content level than desired.

reduced function device (RFD) In building automation systems, a device that serves just one function, such as temperature monitoring. In contrast, a full-function device might control variable air volume.

reducer **1.** A solvent used in paints to reduce the viscosity of the paint. **2.** A pipe fitting, larger at one end than at the other. A reducing coupling. **3.** A substance that chemically reacts with another by removing an oxygen atom from the chemical structure of the second substance.



reducer

reducing joint The connecting joint of unequally sized electrical conductors.

reduct A small piece of material cut from a larger piece to make the larger piece uniform or symmetrical.



reducing joint

reduction of area The difference between the original cross-sectional area of a tensile specimen and the smallest area after rupture, expressed as a percentage of the original area.

redundant power An extra power source. It may be a complete second power system or a just an additional generator. Duplicate power service allows users to switch large amounts of a building's power load to another system.

Redwood Inspection Service One of seven regional grading agencies in North America that are authorized to write and publish grading rules for lumber.

reed switch Two or more highly conductive reeds inside a glass container. The reeds open or close together in response to a magnetic field.

reeding A decorative molding with several parallel half-round moldings.

reentrant angle An internal angle of usually less than 90°.



reeding

reeving **1.** Threading a rope through the blocks to assemble a block and tackle. **2.** Threading or placing a pulling or control line.

reference line A series of two or more points in line to serve as a reference for measurements.

reference mark A supplementary mark close to a survey station. One or more such marks are located and recorded with sufficient accuracy so that the original station can be reestablished from the references.

reference standards Professionally prepared generic specifications and technical data compiled and published by competent organizations generally recognized and accepted by the construction industry. These standards are sometimes used as criteria by which the acceptability and/or performance of a product, material, assembly, or piece of equipment can be judged.

reference standard specification A type of nonproprietary specification that relies on accepted reference standards to describe a product, material, assembly, or piece of equipment to be incorporated into a project.

refill tube A tube in toilets that sends water from the ballcock into an overflow tube to refill the bowl after a siphon break.

reflectance The ratio of light reflected from a surface to the light incident on the surface. Reflectances are often used for lighting calculations. The reflectance of a dark carpet is around 20%, and a clean white wall is roughly 50% to 60%.



refill tube

reflected plan A plan of an upper surface, such as a ceiling projected downward.

reflected sound Sound that has struck a surface and "bounced off."

reflection The return from a material's surfaces of light or sound waves.

reflection cracking The occurrence of cracks in overlays and toppings that coincide with the location of cracks in the base slab.

reflective insulation A thermal material having one or both faces metallically coated to reflect the radiant energy that strikes its surface.

reflective roof Roofing treated with a special coating that reflects the sun's heat away from the building, reducing the building's heat gain and prolonging the life of the roof.

reflector A device used to redirect light or sound energy by the process of reflection.

refraction The change in path of a light ray or energy wave as it passes obliquely from one medium to another.

refractories Materials, usually nonmetallic, used to withstand high temperatures.

refractory Resistant to high temperatures.

refractory brick A brick manufactured for high temperature use.

refractory concrete Concrete having refractory properties and suitable for use at high temperatures, generally about 315°C to 1,315°C, in which the binding agent is a hydraulic cement.

refrigerant The medium used to absorb heat in a cooling cycle.

refrigerant charge The quantity of refrigerant in a refrigeration system.

refrigerant compressor unit A unit consisting of a pump with various controls for regulating refrigerant flow.

refrigeration cycle A thermodynamic process whereby a refrigerant accepts and rejects heat in a repetitive sequence.

refrigeration system A system in which a refrigerant is compressed, condensed, and expanded as a means of removing heat from a cold reservoir. The heat is rejected elsewhere at a higher temperature.

refusal The depth at which a pile cannot be driven any deeper.

regenerative heating The use of heat rejected from one part of the heating cycle and transferred to another part.

register An opening to a room or space for the passage of conditioned air. The register has a grille and a damper for flow regulation.


register

reglaze To replace the glass in a window.

reglet A groove in a wall to receive flashing.

regulated-set cement A Portland cement with admixtures for the purpose of controlling its set and early strength.

regulation The ability of a ballast to hold constant (or nearly constant) the output watts (light output) during fluctuations in the voltage feeding of the ballast. Normally specified as +/– percent change in output compared to +/– percent change in input.

regulator **1.** A device that maintains an appropriate rate of release of pressurized substances. **2.** An electronically controlled device that regulates system voltage.


reglet

rehabilitation (rehab) The process of making possible a compatible use for a property through repair, alternations and additions, while preserving those portions or features that convey what have been determined to be important cultural or architectural values.

reheat coil A coil in an air supply duct, used to control the temperature of air being supplied to individual spaces or a group of spaces.

reheating The heating of return air in an air-conditioning system for reuse.

reinforced bitumen felt A light roofing felt saturated with bitumen and reinforced with jute cloth.

reinforced blockwork Masonry blockwork with reinforcing steel and grout placed in the voids to resist tensile, compressive, or shear stresses.

reinforced cames Lead bars with a steel core for reinforcing, used in leaded lights.


reinforced blockwork

reinforced concrete Concrete containing adequate reinforcement, prestressed or not prestressed, and designed on the assumption that the two materials (steel and concrete) act together in resisting forces.

reinforced masonry Unit masonry construction in which steel reinforcement is so embedded that the materials act together in resisting tensile, compressive, and/or shear stresses.

reinforced plastic Plastic that has components added to it, such as glass fiber, to increase its strength and stiffness.

reinforced T-beam A concrete T-beam strengthened internally with steel rods to resist tensile and/or shear stresses.

reinforcement Bars, wires, strands, and other slender members embedded in concrete in such a manner that the reinforcement and the concrete act together in resisting forces.


reinforcement

reinforcement, cold-drawn wire Steel wire made from rods that have been hot-rolled from billets and cold-drawn through a die used for concrete reinforcement of small diameter such as in gauges not less than 2 mm nor greater than 16 mm.

reinforcement, cold-worked steel Steel bars or wires that have been rolled, twisted, or drawn at normal ambient temperatures.

reinforcement displacement Movement of reinforcing steel from its specified position in the forms.

reinforcement, distribution bar Small-diameter bars, usually at right angles to the main reinforcement, intended to spread a concentrated load on a slab and to prevent cracking.

reinforcement, four-way A system of reinforcement in flat slab construction comprising bands of bars parallel to two adjacent edges and also to both diagonals of a rectangular slab.

reinforcement, helical Steel reinforcement of hot-rolled bar or cold-drawn wire fabricated into a helix, more commonly known as spiral reinforcement. Used in round columns.


reinforcement, helical

reinforcement, high-strength Concrete reinforcing bars having a minimum yield of 60,000 psi or 414 MPa.

reinforcement, hoop A one-piece closed tie or continuously wound tie not less than #3 in size, the ends of which have a standard 135° bend with a 10-bar-diameter extension, that encloses the longitudinal reinforcement in a column.

reinforcement, lateral Usually applied to ties, hoops, and spirals in columns or column-like members.


reinforcement, hoop

reinforcement, principal Elements or configurations of reinforcement that provide the main resistance of reinforced concrete to tensile loads borne by structural components.

reinforcement ratio Ratio of the effective area of the reinforcement to the effective area of the concrete at any section of a structural member.

reinforcement, secondary Reinforcement other than main reinforcement.

reinforcement, transverse Reinforcement at right angles to the longitudinal reinforcement. Transverse may be main or secondary reinforcement.

reinforcement, two-way Reinforcement arranged in bands of bars at right angles to each other.



reinforcement, two-way

reinforcement, welded Reinforcement joined together by welding.

reinforcing bar A steel bar, usually with manufactured deformations, used in concrete and masonry construction to provide additional strength.



reinforcing bar

reinforcing plate An added plate used to strengthen a member or part of a member.

reinforcing tape A tape that is used to hide and strengthen joints between drywall sheets.

rejection of work The act of rejecting work that is defective, or that which does not conform to contractually agreed upon requirements.

relamping The replacement of lamps (bulbs) in light fixtures. May be done as each fails, or may be done on a schedule.

related trades The different building trades required to complete a project.

relative compaction The dry density of soil expressed as a percentage of the density of the soil after a standard compaction test.

relative humidity The ratio of the quantity of water vapor actually present to the amount present in a saturated atmosphere at a given temperature, expressed as a percentage.

relaxation of steel Decrease in stress in steel as a result of creep within the steel under prolonged strain, or as a result of decreased strain of the steel, such as results from shrinkage and creep of the concrete in a prestressed concrete unit.

relay An electromagnetic or electromechanical device using small currents and voltages to activate switches or other secondary devices.

release agent Material used to prevent bonding of concrete to a surface, such as to forms.

release paper A protective film, coated lightly on one side with adhesive, used to protect a surface during shipment and installation.

relief Carved or embossed decoration raised above a background plane.

relief angle Structural angle introduced to help support masonry over an opening or at specified elevations or multistory construction.

relief cut An initial cut made to keep the saw from binding when a curved section is about to be cut.

relief damper A damper in an air-conditioning system that opens automatically at a set pressure differential to balance pressures in a building.

relief valve A pressure-activated valve held closed by string tension and designed to automatically relieve pressure in excess of its setting.



relief valve

relief vent An auxiliary vent that is supplementary to regular vent pipes. The primary purpose is to provide supplementary circulation of air between drainage and vent pipes.

relish In carpentry, the shoulder around or at the side of a tenon.

reluctance The opposition a material offers to magnetic force.

rem (rad equivalent man) These are units used to measure radiation as it affects humans.

remedial action A permanent remedy taken instead of, or in addition to, a removal action that is in response to a release or threatened release of hazardous substances.

remedial design The phase of the site remediation process in which remedial technologies and processes are designed prior to installation.

Remedial Investigation/Feasibility Study (RI/FS) The phase of the site remediation process in which the nature of contaminants is determined and a remedial remedy is selected. It is a site investigation and cleanup selection process that includes activities such as project scoping, data collection, risk assesment, treatability studies, analysis of alternatives, and remedy selection.

remediation The process of correcting a problem such as mold infestation.

remodeling Making alterations to an existing structure such that it will be better suited to current needs.

remoldability The readiness with which freshly mixed concrete responds to a remolding effort such as jigging or vibration, causing it to reshape its mass around reinforcement and to conform to the shape of the form.

remolding test A test to measure remoldability.

remote-control circuit An electrical circuit that controls another circuit by means of a relay device.

removable mullion A door mullion that can be removed from a door frame to allow passage of oversized objects.

removable stop A removable molding or trim used to stop motion and permit the installation of windowpanes or doors.

rendering **1.** The application, by means of a trowel or float, of a coat of mortar. **2.** A drawing of a project or a portion of a project that delineates materials, shades, and shadows.



rendering

renewable energy Energy from natural resources that replenish themselves, such as the sun, wind, rain, tides, and geothermal sources.

renewable energy

renewable energy certificates (RECs) Also referred to as "green tags," RECs each represent one megawatt hour of renewable energy. RECs may be sold by those who produced the energy to offset the cost of generating it.

renovation Modernizing the elements within a structure to meet current functional and aesthetic requirements.

repeater A device that can receive a weak one-way or two-way communications signal, amplify or reshape it, and retransmit it. In digital transmission, a weak pulse train of discrete signals is received, amplified, retimed, and reconstructed for delivery back to the source. In fiber optics, a low-power light signal is converted electronically and retransmitted via a light-emitting diode or laser light source.

repeating theodolite A theodolite designed so that an angle can be turned several times; and successive angle measurement accumulated, with the final reading representative of the accumulations.


repetitive member

repetitive member One of a series of framing or supporting members such as joists, studs, planks, or decking that are continuous, or spaced not more than 24 inches apart; and are joined by floor, roof, or other load-distributing elements. In repetitive-member framing, each member is connected to, and receives some shared support from, the others.

replacement value The estimated cost to replace an existing building based on current construction costs.

reproductive toxin A substance that chemically or biologically interferes with the reproductive process.

request for information (RFI) A formal request for preliminary information for the purpose of evaluating potential bids for design services, construction services, or both. This request does not usually signify a firm commitment by an owner, but it provides information on potential bidders and their capabilities. The information gathered by RFIs is sometimes used to develop a list of architects, engineers, or contractors who will eventually receive a request for proposal (RFP).

request for job order (JO) proposal The owner's notification to the contractor of an upcoming project (JO). This document identifies and briefly describes the project, the desired or required dates and times for performing the work, and contact information of the owner's designated project representative. The request may include other project-specific information. Response times to the request are in accordance with contract requirements.

request for proposal (RFP) Material provided to potential contractors to communicate government requirements and solicit proposals.

requisition To apply for progress payments based on work completed at the end of the pay period (usually one month). Abbreviated term for application for payment.

reroofing Replacing or covering an existing roof.

resaw **1.** To saw a piece of lumber along its horizontal axis. **2.** A band saw that performs such an operation.

resawn board A piece of lumber, most commonly $\frac{11}{16}''$ thick, obtained by resawing a piece of 6/4 common. Used mostly for sheathing and industrial applications. Produced most often from ponderosa pine and white fir.

resealing trap A trap connected to a plumbing fixture drainpipe so constructed as to allow the rate of flow to seal the trap without causing self-siphonage.

reservoir A tank or receptacle used for the accumulation and retention of a fluid.

reset controls Controls for hot water systems that inversely monitor the hot-water loop set point as compared to the outdoor temperature. For example, the system may be set for 180°F when the outdoor temperature is 0°F, and, inversely, the loop temperature could be 120°F when the outdoor air temperature is 45°F.

resetting (of forms) Setting of forms separately for each successive lift of a wall to avoid offsets at construction joints.

reshoring The construction operation whereby the original shoring or posting is removed and replaced in such a manner as to avoid deflection of the shored element or damage to partially cured concrete.

resident engineer An engineer retained by the owner as a representative on the construction site. Frequently used on governmental projects.

residential occupancy Occupancy of a building in which sleeping accommodations are provided for normal residential purposes.

residual approach A methodology for determining the cost of an asset within a construction project.

residual deflection The amount of deviation that remains after an applied load has been removed.

residual stress The stress remaining in a member after an applied force has been removed.

resilience The work done per unit volume of a material in producing strain.


resilient channel

resilient channel A mounting device with flexible connectors used for fastening gypsum board to studs or joists. Helps reduce the transmission of vibrations.


resilient clip

resilient clip A flexible metal device for mounting gypsum board to studs or joists; used to reduce noise and vibrations.

resilient flooring A manufactured interior floor covering material, in either sheet or tile form, that is resilient.

resin **1.** A natural or synthetic solid, or semisolid organic material of indefinite and often high molecular weight having a tendency to flow under stress. It usually has a softening or melting range and fractures conchoidally. **2.** A natural vegetable substance occurring in various plants and trees, especially the coniferous species, used in varnishes, inks, medicines, plastic products, and adhesives.

resin chipboard A particleboard that uses a resin to ensure a uniform consistency.

resistance brazing A process in which coalescence is produced by the heat obtained from the resistance of the work to the flow of an electrical current.

resistance welding A process creating a metallurgical bond between metal by producing heat obtained from the resistance offered by the work to the flow of electric current, and by the application of an external pressure.

resistor A device included in an electric circuit to introduce a desired resistance.

resonance A condition reached in an electrical or mechanical system when the applied load frequency coincides and is equal to the natural undamped frequency of the system.

resonator **1.** A device that intensifies vibration and volume, usually of sound waves. **2.** A hollow metal container that is utilized to create microwaves.

resorcinol resin adhesive A synthetic resin adhesive made with resorcinol-formaldehyde resin using a hardener, usually composed of wood flour and paraform. The adhesive provides an exterior quality glueline and will cure at room temperature. It is used in the manufacture of laminated beams or scarf joints.

Resource Conservation and Recovery Act (RCRA) The primary federal law that governs hazardous and toxic materials at operating facilities. It defines solid and hazardous waste, authorizes the EPA to set standards for facilities that generate or manage hazardous waste, and establishes a permit program for hazardous treatment, storage, and facilities.

respirator A device used to facilitate breathing in a hazardous atmosphere.

respond A support, usually a pilaster or corbel, attached to a wall and supporting one end of an arch, groin, or vault rib.

respondent The party defending a construction claim.

responsiveness The bid's conformance with the solicitation's salient requirements (price, quantity, quality, performance time).

restitution A court-ordered money award that is intended to restore the parties to their financial position as it existed before the contract was formed.

restoration Returning an existing property to a condition that depicts its form, features, and character as they appeared at a particular period of time. Restoration may involve removal of features from other periods in the property's history and reconstruction of missing features from the targeted period.

restraint (of concrete) Restriction of free movement of fresh or hardened concrete following completion of placing in formwork or molds, or within an otherwise confined space. This restraint can be internal or external and may act in one or more directions.

restricted Relative to electrical systems, it refers to areas classified hazardous; or a confined area.

retainage A specific portion of the contract sum that is withheld from progress payments as specified in the owner-contractor agreement.

retaining wall **1.** A structure used to sustain the pressure of the earth behind it. **2.** Any wall subjected to lateral pressure other than wind pressure.

retardation Reduction in the rate of hardening or setting, i.e., an increase in the time required to reach initial and final set or to develop early strength of fresh concrete, mortar, or grout.

retarder An admixture that delays the setting of cement paste, and hence of mixtures such as mortar- or concrete-containing cement.

retempering Addition of water and remixing of concrete or mortar that has lost its workability and become too stiff. This is not usually recommended, as some of the strength is lost.



retaining wall

retention **1.** A percentage, usually 10%, withheld from a periodic payment to a contractor, in accordance with the owner-contractor agreement, for work completed. The retention is held until all terms of the contract have been fulfilled. **2.** The amount of preservative, fire-retardant treatment, or resin retained by treated or impregnated wood.

retentivity The capacity of a material to hold magnetism.

reticulated Covered with crossing lines, netted.

reticuline bar Sinuously bent bars that interconnect adjacent bearing bars in a grating.

retract The mechanism on a dipper shovel bucket excavator that moves the bucket.

retro-commissioning (RCx) Commissioning of existing buildings.

retrofit To modify an existing structure or system within the structure to accommodate upgrading.

return The continuation, in a different direction, of a molding or projection, usually at right angles.

return-air Air returned from a conditioned room or space for processing and recirculation.

return-air intake An opening, usually with a control damper, through which return air reenters an air-conditioning system.

return bend A 180° bend in a pipe.



return bend

return corner block A concrete masonry unit with a plane surface at one end as well as the front face; used at outside corners.

return grille The grille on a return air intake, usually employing a damper.

return mains Pipes or ducts that reroute fluid or air back to the supply source.

return on investment (ROI) A calculation in investment analysis that expresses income as a percentage of capital. There are several specific varieties in general use, such as the internal rate of return (IRR), and the rate of return on equity capital (ROE).


return corner block

return pipe The drain line that returns the water from condensed heating steam to the boiler for reuse.

return system A series of ducts, pipes, or passages that returns a substance, whether it be air or water, to the source for reuse.

reveal **1.** The side of an opening in a wall for a window or door. **2.** Reveal is the depth of exposure of aggregate in an exposed aggregate finish.

reveal pin (reveal tie) A screw or clamp located inside a window opening used to secure scaffolding to the opening.

revent pipe An individual vent that connects directly to a waste fixture and the main or branch vent pipe.

reverberation The perpetuation of sound within a space after the source has ceased, such as an echo.

reverse-acting controllers Devices that decrease control pressure as the control variable (temperature, pressure) increases.

reverse-acting diaphragm valve A valve that opens on application of pressure on a diaphragm and closes when the pressure is released.

reverse board & batten A siding pattern in which the wider boards are nailed over the battens, producing a narrow inset.

reverse-trap water closet Toilet that has a siphonic trapway at the rear of the bowl and integral flushing action.

reversible lock A lock that can be adapted to fit a door of either hand.

reversible siding Resawn board siding that may be installed with either the surfaced or sawn side exposed.

reversion **1.** The tendency of a processed material to return to its original state. **2.** Chemical reaction leading to deterioration of a sealant due to moisture trapped behind the sealant.

revertible flue A flue or chimney that momentarily redirects the gas flow path downward during its normal upward ascent.

revet To face a foundation or embankment with a layer of stone, concrete, or other suitable material.

revetment Facing, such as masonry, used to support an embankment.

revolving door An exterior door consisting of four leaves set at right angles to each other and revolving on a central pivot. Used to limit the passage of air through the opening and eliminate drafts.

R factor The measurement of a material's (such as insulation, windows, and roofing) resistance to the passage of heat. Also known as *R-value*.

rheology The science dealing with flow of materials, including studies of deformation of hardened concrete, the handling and placing of freshly mixed concrete, and the behavior of slurries, pastes, and the like.

rheostat An electric resistor, so constructed that its resistance may be varied without opening the circuit in which it is installed. Used to control the flow of electric current as in a light dimmer.


rheostat

rib **1.** One of a number of parallel structural members backing sheathing. **2.** The portion of a T-beam that projects below the slab. **3.** In deformed reinforcing bars, the deformations or the longitudinal parting ridge.


rib

ribbed panel A panel composed of a thin slab reinforced by a system of ribs in one or two directions, usually orthogonal.

ribbed vault A vault with ribs that support, or appear to support, the web of the vault.

ribbing (crimping, washboarding) A more or less regular corrugation of the surface of wood, caused by differential shrinkage.

ribbing up Circular joinery made by gluing several layers of veneer with a parallel grain structure.


ribbed panel

ribbon A narrow strip of wood or other material used in formwork.

ribbon board **1.** A horizontal brace used in balloon framing where the board is applied to notches in the studs. **2.** A *let-in brace*.

ribbon loading Method of batching concrete whereby the solid ingredients, and sometimes the water, enter the mixer simultaneously.

ribbon strip A horizontal board set into the studs to help support the ends of rafters or joists.

riblath (rib lath) Stiffened expanded metal lath with ribs that provide greater strength and allow for increased spacing between members. It is not used for curved surfaces.

rice hull ash A byproduct from burning agricultural rice waste that can be used in applications similar to cement.

rich concrete Concrete of high cement content.

rich lime A pure lime that, when mixed with mortar, improves the plasticity or workability of the mortar.

riddle A coarse sieve for separating and grading granular material.

ridge The horizontal line formed by the upper edges of two sloping roof surfaces.

ridge beam A horizontal timber to which the tops of rafters are fastened.

ridgeboard (ridgepole, roof tree) The longitudinal board set on edge used to support the upper ends of the rafters.


ridgeboard (ridgepole, roof tree)



ridgecap (ridge cap)

ridgecap (ridge cap) A layer of wood or metal topping the ridge of a roof.

ridge rib A projecting structural element following the ridge of a vault.

ridge shingles Shingles that cover a house's ridgeboard.

ridge stop The flashing that forms a watertight barrier between the edge of the roofing membrane and the vertical wall or chimney rising above it.

ridge strap A metal connector that fastens opposing rafters together to resist suction forces caused by uplift at the ridge line.

ridge vent A vent installed along the top ridge of a roof to permit air to pass through to the attic or the peak of a cathedral ceiling.



ridging

ridging **1.** An upward dislodgement of the roof membrane. **2.** Long narrow blisters in the surface of built-up roofing.

rift A narrow fissure in rock.

rig **1.** To provide with equipment or gear for a special purpose. **2.** To assemble in a makeshift manner. **3.** An assembled piece of equipment, such as an oil-drilling rig.

rigger A worker who prepares heavy equipment or loads of materials for lifting.

rigging Lines or cables used to lift heavy loads.

riggot A trough or gutter for draining off rainwater.

right-hand rule **1.** A rule for determining polarity produced by flowing electric current. **2.** Rule-of-thumb to envision the orientation of nut movement on a bolt to loosen/tighten it. Right thumb points along threaded shaft; direction of fist opening shows direction of nut loosening.

right-of-way A strip of land, including the surface and overhead or underground space, that is granted by deed or easement for the construction and maintenance of specific linear elements such as power and telephone lines, roadways and driveways, and gas or water lines.

right-to-know A right granted to workers by the Occupational Safety and Health Act (OSHA), by which they must be informed of the risks and hazards associated with the chemicals and substances that they are required to use in the workplace.

Right to Work Law State law providing, in general, that employees are not required to join a union as a condition of retaining or receiving a job.

rigid connection A connection between two structural members that prevents end rotation of one relative to the other.

rigid foam insulation Panels of polyurethane foam that are used in commercial and residential construction as roof or outside wall insulation. The panels or boards include barrier board, and structural insulation panels (SIPs). The facings on the boards include metals, foil, glass fiber, kraft paper, or oriented strand board (OSB).



rigid connection



rigid frame

rigid frame A structural framing system in which all columns and beams are rigidly connected; there are no hinged joints.

rigid metal conduit A raceway constructed for the pulling in or withdrawing of wires or cables after the conduit is in place and made of standard weight metal pipe permitting the cutting of standard threads.

rigid pavement Pavement that will provide high bending resistance and distribute loads to the foundation over a comparatively large area.

rim joist Perimeter joist for wood floor framing system. Usually referred to in conjunction with composite wood floor joists.

rim latch A surface-mounted latch.

rim lock A face-mounted door lock.

rime The rung of a ladder.

rimpull The capability of wheeled construction equipment to move a load.

ring-shank nail A nail with ring-like grooves around the shank to improve its grip.

rip To saw lumber parallel to the grain.

ripper A device with protruding claws that is pulled by a tractor. Used to penetrate and disrupt the earth's surface up to 3′ in depth.

ripping Fragmenting a rock formation by a tractor pulling a heavy tooth.

riprap Irregularly broken, large pieces of rock, used along stream banks and oceanfront property as protection against erosion.

ripsaw A coarse-toothed saw used for cutting wood in the direction of the grain.

rise **1.** The vertical distance from the top of a tread to the top of the next higher tread. **2.** The height of an arch from springing to the crown. **3.** The vertical height from the supports to the ridge of a roof. **4.** Height difference between the crown of a road and its lowest point.



riser

rise and run The angle of inclination or slope of a member or structure, expressed as the ratio of the vertical rise to the horizontal run.

riser **1.** A vertical member between two stair treads. **2.** A vertical pipe extending one or more floors.

riser height The vertical distance between the tops of two successive treads.

rising hinge (rising butt hinge) A door hinge fabricated with a slope on the knuckle, which causes the door to rise when opened. A rising hinge is used when there are obstructions along the door's bottom edge, e.g., carpeting.

risk management An approach to management and procedure designed to prevent occurrence of culpability, potential liability, contravention of law, or other potential risk that could bring about loss in the process of building construction.

risk probability A concept applied to assess a facility's security needs based on consideration of factors such as incidence history, trends in the surrounding environment, warnings or threats, and similar events occurring at other comparable schools.

rive Splitting wood along the grain. Shingles are cut in this fashion.

rivet A metal cylinder or rod with a head at one end that is inserted through holes in the materials to be fastened. The protruding end is flattened to tie the two pieces together.



rivet



riveting

riveting The act of fastening or securing two or more parts with rivets.

R-number A number used by ASHRAE to indicate the molecular structure of chemical refrigerants.

road base A mixture, typically stone and sand, used as the base for road paving.

road forms Wood or steel forms set on edge to form the side of a concrete road slab, also used as screeds.

road heater A traveling machine that prepares a road surface for treatment by blowing a flame or hot air on it.

road oil A heavy petroleum oil, usually a slow-curing asphalt.

roadway The area of a highway including the surface over which vehicles travel as well as the land along the edges, such as slopes, ditches, channels, or other gradations necessary to ensure proper drainage and safe use.

rock anchor Steel rod anchored in rock by grouting used to hold temporary shoring or retaining walls around an excavation.

rock drill A high-powered pneumatic or electrically driven device for boring holes into rock.

rocker shovel Mechanical tunneling shovel.

rockers Slang term for drywall installers.

rock-faced A type of rough finish on stone. Essentially the same face that resulted when the stone was first struck from the quarry.

rock pocket A porous, mortar-deficient portion of hardened concrete, consisting primarily of coarse aggregate and open voids, caused by leakage of mortar from form, separation or segregation during placement, or insufficient consolidation.



rock rake

rock rake Tractor attachment with multiple teeth that is used to clear trees and rocks.

rock saw A circular saw that removes a wide kerf on the upper surface of a log. A rock saw is used to remove stones or debris before a log enters the head rig.

Rockwell hardness A measure of the resistance of a material to indentation, expressed as an index number obtained by pressing a standard steel ball or diamond into the material under controlled conditions. A high index number indicates a hard material.

rock wool A type of mineral wool made by forming fibers from molten rock and slag. Used as insulation in walls and ceilings.

rod Sharp-edged cutting screed used to trim shotcrete to forms or ground wires.

rod bender A power-assisted device with adjustable rollers and supports that is used for bending steel reinforcing rods into usable shapes.

rod cutter Trench-type, hydraulically operated, wedgelike shear, used to cut steel reinforcing rods.

roddability The susceptibility of fresh concrete or mortar to compaction by means of a tamping rod.

rodding Compaction of concrete or the like by means of a tamping rod.

rod level A device used to ensure a leveling rod or stadia rod is in the vertical position before taking any instrument readings.

rod target (target rod) A metal disc that slides upon a track on a leveling rod, used for taking sights in surveying.

roll (noun) **1.** A quantity of sheet material wound in cylindrical form. **2.** A rounded strip of roofing fastened to and running along the ridge of a roof. **3.** Any type of rounded molding. **4.** Any heavy, metal cylinder used to flatten, smooth, or form material.

roll (verb) A slang term referring to the installation of floor joists or trusses.



rolled beam (rolled steel beam)

rolled beam (rolled steel beam) A beam that is fabricated of steel and passed through a hot-rolling mill.

rolled glass Glass that is manufactured with a patterned surface that partially obscures vision and light.



roller

roller 1. A heavy, self-propelled or towed device used to compact granular fill. **2.** A small hand tool used to smooth wall covering and flooring.

roller shade An automated window shade with a motor that adjusts the shade to control light, privacy, and solar heat gain.

rolling grille door A device similar to a rollup door, but with an open grille rather than slats; used as security protection.



rolling grille door

rolling resistance The resistance of a substrate to turning wheels on top.

rolling scaffolding A reliable, inexpensive scaffold used on interiors up to 20′ in height. Suitable for close inspection and construction work on walls and ceilings.


rolling scaffolding

roll joint A point of connection formed by rolling two edges of sheet metal together and then compressing the roll.

rollup door (rolling shutters) A device consisting of horizontal interlocking metal slats that ride along wall guides. When the door is opened the slats coil around a barrel assembly located above the door.

Roman brick Brick that measures 4″ × 2″ × 12″.

Romanesque architecture Style of building with massive walls, vaults, and rounded arches.

Romex The most familiar trade name for nonmetallic sheathed cable.

roof covering The covering material installed in a building over the roof deck. The type of covering used depends on the roofing system specified to weatherproof the structure properly.

roof deck The foundation or base upon which the entire roofing system is dependent. Types of decks include steel, concrete, cement, and wood.


roof deck

roof drain A drain designed to accept rainwater on a roof and discharge it into a leader.

roof flange A collar that fits around a pipe penetrating through the roof, making the opening watertight.

roof framing A group of members fitted or joined together to provide support for the roof covering.

roof hatch (roof scuttle) A weathertight assembly with a hinged cover, used to provide access to a roof.


roof hatch (roof scuttle)

roofing bond A guarantee by a surety company that a roof installed by a roofer in accordance with specifications will be repaired if it fails within a certain period of time. Failure must be due to normal weathering.

roofing bracket A bracket used in slope roof construction, having provisions for being fastened to the roof, or supported by ropes fastened over the ridge and secured to some suitable object.

roofing nail A special-purpose, short-threaded nail with a large head, usually galvanized or aluminum with a neoprene or plastic washer to aid in fastening roof coverings.

roofing square **1.** A steel square used by carpenters. **2.** A measure of roofing material.

roofing tile A preformed slab of baked clay, concrete, cement, or plastic laid in rows as a roofing cover. Tiles have a variety of patterns, but fall into two classifications: roll and flat.


roofing tile

roof jack A sleeve installed around plumbing waste vent pipes.

roof joist A rafter on a flat roof that supports the roof loads; usually 2 × 10s or 2 × 12s.

roof live load Any external loads that may be applied to a roof deck, such as rain, snow, construction equipment, and personnel.

roof overhang The part of a roof that extends over the side wall or end wall of a building.

roof pitch The slope of a roof expressed as the ratio of the rise of the roof to the horizontal span.

roof plate A wall plate that supports the lower end of rafters.

roof principal A roof truss.

roof sheathing Any sheet or board material, such as plywood or particleboard, connected to the roof rafters to act as a base for shingles or other roof coverings.

roof slope The angle of a roof compared to a horizontal plane.

roof space The space between the roof and the ceiling of the highest room.

roof span The shortest distance between the seats of opposite common rafters.

roof structure Any structure on or above the roof of a building.

roof terminal The top point of the plumbing vent pipe as it exits through the roof, often 12″.

roof truss A truss used in the structural system of a roof.

roof vent A device used to ventilate an attic or roof cavity.

room cavity ratio (RCR) A ratio of room dimensions used to quantify how light will interact with room surfaces. A factor used in illuminance calculations.

room finish schedule Information provided on design drawings specifying types of finishes to be applied to floors, walls, and ceilings for each location.

root **1.** The part of a tenon that widens at the shoulders. **2.** The point where the back or bottom of the weld meets the base metal.

root diameter A measurement of the major diameter on nuts and the minor diameter on screws.

rope **1.** Twisted strands of fiber made into strong, flexible cord. **2.** Strands of wire braided or twisted together that are used for heavy hoisting or hauling.

rope caulk A preformed, ropelike bead of caulking compound that may contain twine reinforcement to facilitate handling.

rope diameter The largest diameter of the cross section of a wire rope. Fiber ropes are usually measured by circumference (3.14 × diameter).

rope lay The direction in which the wires or strands are twisted during manufacture.

c18.indd 264 06/09/12 9:05 AM

rose The metal plate or escutcheon between a doorknob and the door.

rose bit A bit for countersinking holes in wood.

rose nail A wrought nail with a cone-shaped head.

rosette **1.** A round pattern with a floral motif. **2.** A circular or oval, ornamental, wood plaque that is used to terminate a wood piece such as a stair rail at a wall. **3.** A decorative nailhead or screwhead.

rose window (wheel window) Circular window with a radial pattern resembling a wheel with spokes and a hub.

rosin paper A paper coated with resin. Rosin paper is laid between lead sheets and sheathing to allow for thermal movement in lead roofing.

rotary compressor An air compressor using a rotary impeller driving air through a curved chamber to compress the air.

rotary cutting A method of obtaining wood veneers by rotating logs against a flat knife and peeling the veneer off in a long continuous sheet. Peeling provides a greater volume and a more rapid production than does sawing or slicing.

rotary drill A machine for making holes in rock or earth by a cutting bit at the end of a metal rod, usually turned by a hydraulically—or pneumatically driven motor.



rotary float (power float)

rotary float (power float) Motor-driven revolving blades that smooth, flatten, and compact the surface of concrete slabs or floor toppings.

rotary hammer Electric boring tool that rotates with percussive action and cuts very hard materials.



rotary hammer

rotary pump Any pump using gears, vaned wheels, or a screw mechanism to displace liquid, usually delivering large volumes at low pressure.



rotary pump

rotating laser A leveling and surveying instrument with a revolving head that emits a laser beam horizontally. A sensor then picks up the beam to determine an elevation.

rotor The rotating armature or member within an electrical device or motor.

rotunda A circular building or hall that is round inside and out and usually domed.

rough-cut joint (flat joint, flush joint, hick joint) A mortar joint that is flush with the face of the brickwork.

rough estimate An estimate made without detailed investigation.

rough floor A base or subfloor, consisting of a layer of boards or plywood nailed to the floor joists.



rough floor

rough grading Cutting and filling the earth for preparation of finish grading.



rough grind The initial operation in which coarse abrasives are used to cut the projecting chips in hardened terrazzo down to a level surface.

rough hardware Any fittings, such as screws, bolts, or nails that should be concealed for a finished product.

rough-in dimensions In plumbing installations, the distance from the center of a water supply, waste opening or mounting holes to the finished wall or floor.



rough hardware

roughing-in **1.** The base coat in three-coat plasterwork. **2.** Any unfinished work in a construction job. **3.** Installing the concealed portion of electrical or plumbing systems to the point of connection for electrical outlets or appliances, or plumbing fixtures.

roughing-out A preliminary shaping operation in carpentry.

rough lumber Wood that has been sawn at the mill, but not trimmed.

rough opening An opening in a wall or framework into which a door frame, window frame, subframe, or rough buck is fitted.

rough rendering Applying a coat of plaster without removing the irregularities.

rough sill A horizontal member laid across the bottom of an unfinished opening to act as a base during construction of a window frame.

rough work The framing, boxing, and sheeting for a wood-framed building.

round **1.** A molding that may be semicircular to full round, as in a closet rod. **2.** A turn of wire rope around a drum.

rout **1.** To deepen and widen a crack, preparing it for patching or sealing. **2.** To cut out by gouging.

router An electrically driven device with various bits for cutting grooves or channels in wood.

router gauge A carpenter's tool consisting of a guide, a bar with a scale, and a narrow chisel as a cutter; used in inlaid work to cut out narrow channels in which colored strips are laid.



router

router patch (Davis patch) A wood patch in plywood with straight sides and rounded ends, similar to a tongue depressor; used to fill voids caused by defects. The router patch is one of two patch designs allowed in A-grade faces.

router plane (router plough, router plow) A woodworker's plane for cutting grooves or channels in wood.

rowlock course (bull header) Brick pattern in which bricks are set on their face edges with the ends visible in the wall face.



rowlock course (bull header)

royals Shingles with 24″ edges and a thickness of ½″ at the butt.

rubbed brick Brick that has one or more smooth faces.

rubbed finish **1.** On woodwork, a dull finish obtained from hand rubbing with a rag or pad saturated with water or oil and pumice. **2.** A finish obtained by using an abrasive, often a carborundum stone, to remove surface irregularities from concrete.

rubbed joint A process for joining two narrow boards. Both boards are planed smooth, and then coated with glue and rubbed together until all air pockets and excess glue are expelled from the joint. No clamping is necessary, and the joint is extremely strong.

rubber **1.** A highly resilient natural material manufactured from the juice of rubber trees and other plants. **2.** Any of various synthetically manufactured materials with properties similar to natural rubber. **3.** A cushioned backing for a carpet.

rubber silencer (bumper) A small round rubber device that attaches to a rabbeted doorjamb, which silences the noise caused by a slamming door.

rubber tile A soft and yielding floor covering that reduces the transmission of impact noises produced by walking or from other causes.

rubber-tired roller A machine for compacting and kneading soil using pneumatic-tired rollers.

rubbing brick A silicon-carbide brick used to smooth and remove irregularities from surfaces of hardened concrete.

rubble Rough stones of irregular shape and size, broken from larger masses by geological processes or by quarrying.

ruff-sawn A designation for plywood paneling or siding that has been saw-textured to provide a decorative, rough-sawn appearance.

rule **1.** A straightedge with graduations used for measuring, laying out lengths, or drawing straight lines. **2.** A straightedge for working plaster to a plane surface.

rule of thumb A statement or formula that is not exact but is close enough for practical work.

run **1.** In plumbing, a pipe or fitting that continues in the same straight line as the direction of flow. **2.** In roofing, the horizontal distance between the outer face of the wall and the roof ridge. **3.** In stairs, the horizontal distance from the face of the first riser to the face of the last riser.

runaround system A heat recovery system in which coils in an exhaust duct transfer a portion of the exhaust air heat to a fluid. The fluid is then circulated to coils that give up a portion of the fluid's heat to the air in a cold air duct.

rung A bar, usually of circular cross section, used as a step in a ladder.

run-in-place A method of producing ornamental plaster on-site, typically on a workbench. The plaster is attached to the wall after setting.



rung

run molding A formed molding of plaster or similar material formed by passing a template over the plastic material.

runner **1.** The lengthwise horizontal bracing or bearing members. **2.** A cold-rolled channel used to support steel studs in a partition or ceiling tile.

running **1.** Descriptive of a repeating design in a band having a smooth progression. **2.** Forming a cornice of plaster or similar material in place with a running mold. **3.** Operating a powered hand tool, particularly a drill.

running foot A linear foot. The term is a measurement of the actual length of a piece of lumber, without regard to the thickness or width of the piece.

running ground Earth in a semiplastic state that will not stand without support.

running inch A linear inch. The term is a measurement of the actual length of a piece of lumber. *See also* running foot.

running mold A template shaped to a desired cornice and mounted on a wood frame; used by plasterers to form a molding or cornice in place by applying plaster as the mold is moved along the ceiling line.

running screed A narrow strip of plaster used in place of a rule to guide a running mold.

running shoe A metal guide on a running mold to prevent wear and allow it to slide freely on a rule.

running trap A U-shaped pipe fitting installed in a drain line to prevent the backflow of sewer gases.

runway Decking over an area of concrete placement, usually of movable panels and supports, on which buggies of concrete travel to points of placement.



running trap

rust Any of various powdery or scaly reddish-brown or reddish-yellow, hydrated, ferric oxides formed on the surface of iron or steel that is exposed to moisture and air. Rust eventually will weaken or destroy the material if allowed to progress.

rustication Providing a continuous groove in vertical concrete at a preferred location by applying a form strip prior to placing concrete, and removing it after concrete has set.

rustic brick A brick that has a rough-textured finish produced by covering it with sand, wire brushing, or impressing it with a pattern.



rustication

rustic finish (washed finish) A type of terrazzo topping in which the matrix is recessed by washing prior to setting so as to expose the chips without destroying the bond between chip and matrix. A retarder is sometimes applied to the surface to facilitate this operation.

rustic joint A deeply sunk mortar joint that is accented by beveling the edges of the adjacent stone.

c18.indd 266 06/09/12 9:05 AM

rustic stone Any rough, broken stone suitable for masonry with an uneven appearance, most commonly limestone or sandstone, usually set with the longest dimension horizontal.

rust joint A watertight pipe connection that uses iron filings as a catalyst to induce rusting in iron pipe joints.

rust pocket An area in the bottom of a ventilating pipe for the collection and removal of rust and debris.

R value A measure of a material's resistance to heat flow at a given thickness of material. The term is the reciprocal of the U value. The higher the R value, the more effective the particular insulation.

S

Abbreviations

S side, south, southern, seamless, subject, sulphur

S1E surfaced one edge

S1S surfaced one side

S1S1E surfaced one side and one edge

S1S2E surfaced one side and two edges

S2E surfaced two edges

S2S surfaced two sides

S2S1E surfaced two sides and one edge

S2S&CM surfaced two sides and center matched

S2S&SL surfaced two sides and shiplapped

S4S surfaced four sides

S4S&CS surfaced four sides and caulking seam

SA smart actuator, system air

S/A shipped assembled

SAB sound attenuation batt, blanket, or board

SAC security and access control

SAE Society of Automotive Engineers

SAF safety

SAFB sound attenuation fire batt

SAN sanitary

S&E surfaced one side and edge

S&G studs and girts

S&H staple and hasp

S&M surfaced and matched

sanit sanitation

SAP sampling and analysis plan, security access and parking

sar supplied air respirator

SAT supply air temperature

sat saturate, saturation

SB1S single bead one side

SBA Small Business Association

SBC Standard Building Code

SBS sick building syndrome

SC site closeout, substantial completion

scba self-contained breathing apparatus

sch school

SCH schedule

scp spherical candlepower

SCS structured cabling system

SD sea-damaged, standard deviation

S/D shop drawings

SDA specific dynamic action

Sdg siding

SDV switched digital video

Se selenium

S/E square-edged

sec second

SECT section

sed sediment, sedimentation

SEER Seasonal Energy Efficiency Ratio

sel select, selected

Sel select

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

sep, SEP	separate
SERI	Solar Energy Research Institute
SERV	service
SE&S	square edge and sound
SE Sdg	square-edge siding
SEW	sewer
sf, SF	square foot, surface foot, specialty fabricator, supply fan
SFPE	Society of Fire Protection Engineers
SFRC	steel-fiber-reinforced concrete
Sftwd	softwood
sfu	supply fixture unit
SG	slash grain
SGD	sliding glass door
SH	sheet, shower, single-hung
sh	shingles
shf	superhigh frequency
SHGC	solar heat gain coefficient
shp	shaft horsepower
SHSS	site health and safety supervisor
sht	sheet, sheath
SI	system integrator
Si	silicon
SIA	Security Industry Association
SIC	Standard Industrial Classification
sid	siding
SIM	similar
SJI	Steel Joist Institute
SK	sketch
Sk	sack
SKU	stock keeping unit
sky	skylights
SL&C	shipper's load and count
slid.	sliding
S/L, S/LAP	shiplap
SM	standard matched, surface measure
SMACNA	Sheet Metal and Air Conditioning Contractor's National Association
s mld	stuck mold
SMS	sheet-metal screw
so	south
SO	seller's option
SOC	security operations center
SOHO	small office/home office
soln	solution
SOO	sequence of operations
SOP	standard operating (or operations) procedure
SOV	shutoff valve
SOW	statement of work
sp	specific, specimen, spirit, single pitch (roof)
SP	soil pipe, standpipe, self-propelled, single pole, static pressure
SPEC	specification
sp gr, SP GR	specific gravity
sp ht	specific heat
SPKR	loudspeaker
spl	spline
SPL	special
spr	spruce
SPT	standard penetration test
sp vol	specific volume
sq	square
sq e	square edge
sq E&S	square edge and sound
sq ft	square foot
sq in	square inch
sq yd	square yard
SR	sedimentation rate, service request
ss	single strength (glass)
SS, S/S	stainless steel, smart sensor, sustainable site
sst	standing seam tin (roof)
SST	stainless steel
st	stairs, stone, street
ST	steam, street
STC	sound transmission class
std, STD	standard
Std M	standard matched
ST	supply temperature
STG	storage
STK	stock, select tight knot
STL	steel
STP	standard temperature and pressure, shielded twisted pair
Stpg	stepping
str	stringers
Str	structural
STR	strike
STR1E	straight line rip one edge
Struc	structural
STS	shared tenant services, static transfer switch
st sash	steel sash
ST W	storm water
sty	story

sty hgt story height

SUB substitute

sub fl subfloor

subpar subparagraph

subsec subsection

sup supplementary, supplement

SUP supply

supp supplement

SUPSD supersede

supt, SUPT, SUPER superintendent

SUPV supervise

supvr supervisor

sur, SUR surface

surv survey, surveying, surveyor

svc service

SVE soil vapor extraction

sw switch

SW switch, seawater, southwest

SWBD switchboard

SWG, S.W.G. standard wire gauge

SY square yard

sy jet syphon jet (water closet)

SYM symmetrical

SYN synthetic

SYS system

syst system

Definitions

saber saw A handheld power saw with a reciprocating blade extending through the base of the saw.



saber saw

sabin A unit of measure used to rate the sound absorption qualities of a material or assembly. Equal to one foot of a perfectly absorptive surface.

sack A certain quantity of cement, typically 94 pounds (United States) and 87.5 pounds (Canada), for Portland or air-entraining Portland cement and as indicated for other cement types. See also **bag**.

sacking Correcting concrete surface defects by applying a mixture of cement and sand and rubbing with burlap or another coarse material.

sack joint A flush masonry joint that has been wiped or rubbed with a rag or an object such as a rubber heel or a burlap sack.

sack rub (sack finish) A finish for formed concrete surfaces, designed to produce even texture and fill all pits and air holes After dampening the surface, and before it dries, a mixture of dry cement and sand is rubbed over it with a wad of burlap or a sponge-rubber float to remove surplus mortar and fill the voids.

sacrificial protection The use of a metallic coating, such as zinc-rich paint, to protect steel. In the presence of an electrolyte, such as salt water, the metallic coating dissolves instead of the steel.



saddle

saddle **1.** A fitted device used with hangers to support a pipe. **2.** A series of bends in a pipe over an obstruction. **3.** A short horizontal member set on top of a post as a seat for a girder. **4.** Any hollow-backed structure with a shape suggesting a saddle, as a ridge connected to two higher elevations or a saddle roof.

saddle bar One of the horizontal iron bars across a window opening to secure leaded lights.

saddle bead A glazing bead or channel for securing two panes of glass together.

saddle bend A bend made in a conduit to provide clearance where it crosses another conduit.

saddle block The boom swivel block through which the stick of a dipper shovel slides.

saddle board A board used to cover the joint at the ridge of a pitched roof.

saddle fitting A type of gasketed fitting clamped around the exterior of a pipe; used when a connection to a previously installed pipe is required.

saddle flange A flange that is curved to conform to the surface of the boiler or tank to which it is welded, riveted, or otherwise attached, and designed to accept a threaded pipe.

saddle flashing Flashing installed over a cricket.



saddle joint

saddle joint **1.** A joint in sheet-metal roofing, in which one end of one sheet is folded downward over the turned-up edge of the adjacent sheet. **2.** A stepped joint in a projecting masonry course to prevent the penetration of water.

saddle scaffold A scaffold erected so as to bridge the ridge of a roof, usually used during chimney repair.

safe **1.** A built-in or portable chamber used to protect materials or documents from fire and/or theft. **2.** A pan or other collector placed beneath a pipe or fixture to collect leakage or overflow.

safe load The maximum load on a structure that does not produce stresses greater than those allowable.

safe room or shelter-in-place room A building space designed and constructed to provide protection in a natural or other disaster. The space may be structurally reinforced and may have limited air exchange.

safety belt A belt-like device worn around the waist and attached to a life-line or structure to stop a worker during a fall.

safety curtain A heavy iron or fiberglass curtain used in auditoriums to prevent fire spread. Also referred to as a fire curtain.

safety fuse A cord containing black powder or other burning medium encased in flexible wrapping and used to convey fire at a predetermined and uniform rate for firing blasting caps.

safety lintel A load-carrying lintel positioned behind a more decorative but somewhat less functional lintel, as in the aperture of a window or door.

safety nosing An abrasive, nonslip stair nosing whose surface is flush with the tread against which it is placed.


safety nosing

safety shutoff device A device in a gas burner that will shut off the supply of gas if the flame is extinguished.

safety stock The average amount of stock on hand when a replenishment quantity is received. Its purpose is to protect against the uncertainty in demand and in the length of the replenishment lead time. Safety stock and cycle stock are the two main components of any inventory.*

safety switch In an interior electric wiring system, a switch enclosed within a metal box that has a handle protruding from the box to allow switching to be accomplished from outside the box.

safety time In a time series planning system, material is frequently ordered to arrive ahead of the forecast requirement date to protect against forecast error. The difference between the forecast requirement date and the planned in-stock date is safety time.*


safety switch

safety tread A tread on a stair that has a roughened surface or roughened inserts to improve traction.

safe working pressure The maximum working pressure at which a vessel, boiler, flask, or cylinder is allowed to operate, as determined by the American Society of Mechanical Engineers Boiler Code; usually so identified on each individual unit.

safing **1.** Noncombustible material used as a fire barrier around the perimeter of a floor or around protrusions or penetrations. **2.** In ductwork, a type of barrier or similar device installed around a component to ensure that air flows through that component and not around it.

safing off Installation of fire safety insulation around floor perimeters, between floor slab and spandrel panels. Insulation helps retain integrity of fire-resistance ratings.

sagging **1.** Subsidence of shotcrete material from a sloping, vertical, or overhead placement. **2.** The condition of a horizontal structural member bending downward under load. **3.** A paint defect where paint runs after it has been applied.

sag rod A tension member used to limit the deflection of a girt or purlin in the direction of its weak axis or to limit the sag in angle bracing.

sailor A rectangular masonry unit, such as a brick, that is set upright with its largest side facing out.


sag rod

salamander A portable source of heat, customarily oil-burning, used to heat an enclosure around or over newly placed concrete to prevent the concrete from freezing.

sal ammoniac (ammonium chloride) A material used in soldering flux and iron cement.

salient Descriptive of a projecting part of an object or member, as a salient corner.

sally A projection, such as the end of a rafter beyond the notch, which has been cut to fit a plate or beam.

salmon brick (chuff brick, place brick) Comparatively soft and underburnt brick, usually because of its high placement in the kiln, and so named because of its color.

salt-glazed brick (brown-glazed brick) Brick whose surface faces have a lustrous glazed finish resulting from the thermochemical reaction between silicates of clay and vapors of salt or other chemicals during firing.

salt-glazed tile Facing tile with a lustrous glazed finish, obtained by thermochemical reaction between silicates of clay and vapors of salt or other chemicals during firing.

salvage value The value assigned to the piece of equipment at the end of the depreciation period.

samples Examples of workmanship establishing the standards against which the rest of the work will be measured.

sampling approach A methodology for determining the cost of an asset within a construction project. Uses a model to analyze identical types of construction and is most popular for redundant types of projects such as retail chain stores.

sand **1.** Granular material passing the 3/8″sieve, almost entirely passing the No. 4 (4.75-millimeter) sieve, and predominantly retained on the No. 200 (75-micrometer) sieve, and resulting from natural disintegration and abrasion of rock or processing of completely friable sandstone. **2.** That portion of an aggregate passing the No. 4 (4.75-millimeter) sieve, and resulting from natural disintegration and abrasion of rock or processing of completely friable sandstone. *Note*: The definitions are alternatives to be applied under differing circumstances. Definition 1 is applied to an entire aggregate either in a natural condition or after processing. Definition 2 is applied to a portion of an aggregate. Requirements for properties and grading should be stated in the specifications. Fine aggregate produced by crushing rock, gravel, or slag commonly is known as manufactured sand.

sand asphalt A mixture of ungraded sand and liquid asphalt used for an economical base or wearing surface for pavements.

sandbag A canvas bag that is filled with sand and used as a counterweight or for emergency damming of water flow.

sandblast A system of cutting or abrading a surface, such as concrete, by a stream of sand ejected from a nozzle at high speed by compressed air. Sandblasting is often used for cleanup of horizontal construction joints or for exposure of aggregate in architectural concrete.

sand box (sand jack) A tight box filled with clean, dry sand, on which rests a tight-fitting timber plunger that supports the bottom of posts used in centering. A plug from a hole near the bottom of the box permits the sand to run out when it is necessary.

sand clay A naturally occurring sand that contains about 10% clay, or just enough to make the material bind tightly when compacted.

sand-coarse aggregate ratio Ratio of fine to coarse aggregate in a batch of concrete, by weight or volume.

sand-dry Descriptive of a stage in the drying process of paint where sand will not adhere to the surface.

sanded-face shingle A shingle with retrimmed edges and butts that has been sanded to remove saw marks, etc., and is to be applied to a wall as part of a decorative effect.

sander A machine designed to smooth wood and remove saw or lathe marks and other imperfections. Sanders range in size from hand-held to large drums or belts capable of surfacing a full-size panel.

sand-faced brick A brick formed in a mold that has been sprinkled with sand to facilitate removal.



sander

sand filter A bed of sand laid over graded gravel, used as a filter for a water supply.

sand filter trenches A network of sewage-effluent-filtering trenches incorporating perforated pipe or drain tiles surrounded by fine sand sandwiched between coarse aggregate, and equipped with an underdrain to remove whatever material has passed through. The trenches are used to remove solid or colloidal material that cannot be removed by sedimentation.



sand filter trenches

sand finish **1.** In plastering, a textured final coat, usually containing sand, lime putty, and Keene's cement. **2.** A smooth finish derived from rubbing and sanding the final coat.

sand grout (sanded grout) Any grout in which fine aggregate is incorporated into the mixture.

sanding machine A stationary machine having a moving belt, disk, or spindle with an abrasive surface, usually a sandpaper; used for smoothing surfaces.

sand interceptor (sand trap) A watertight device that can be directly or indirectly connected to a drainage system to intercept and prevent sand or other solids from passing into the system.

sandpaper Strong, tough paper coated on one side with glue or other adhesive material, into which an abrasive such as flint, silica, or aluminum oxide has been embedded. The resulting product is used primarily for resurfacing or cutting wood, metal, plastic, or glass and is available in an extensive range of coarseness or grit.

sandpile A foundation formed by ramming sand into a hole left by a pile that was driven and removed.

sand pine *Pinus clausa*. A type of pine found almost exclusively in north central Florida, where it grows in very sandy soil. The wood is used mostly for pulp.

sand plate A flat steel plate or strip welded to the legs of bar supports for use on compacted soil.

sand pocket A zone in concrete or mortar containing sand without cement.

sand seal Emulsified asphalt covered with fine aggregate applied to pavement to improve skid resistance and to prevent air and water penetration.

sandstone A cemented or otherwise compacted sedimentary rock composed predominantly of sand grains. It has been used as cut stone for carved ornament.

sand streak A streak of exposed fine aggregate in the surface of formed concrete caused by bleeding.

sand trap *See* **sand interceptor**.

sandwich beam *See* **flitch beam**.

sandwich construction Composite construction usually incorporating thin layers of a strong material bonded to a thicker, weaker, and lighter core material, such as rigid foam or paper honeycomb, to create a product that has high strength-to-weight and stiffness-to-weight ratios.

sandwich panel A panel formed by bonding two thin facings to a thick, and usually lightweight, core. Typical facing materials include plywood, single veneers, hardboard, plastics, laminates, and various metals, such as aluminum or stainless steel. Typical core materials include plastic foam sheets, rubber, and formed honeycombs of paper, metal, or cloth. **2.** A prefabricated panel that is a layered composite formed by attaching two thin facings to a thicker core. An example is precast concrete panels, which consist of two layers of concrete separated by a nonstructural insulating core.



sandwich panel

sanitary code Municipal regulations established to control sanitary conditions of establishments that produce and/or distribute food, serve food, or provide medical services.

sanitary cove A piece of metal used in a stair between the surface of the tread and the face of the riser to facilitate cleaning.

sanitary cross In a soil pipe system, a cross pipe, whose 90° transitions are curved to direct the flow from the branches toward the direction of the main flow.

sanitary engineering That part of civil engineering related to public health and the environment, such as water supply, sewage, and industrial waste.

sanitary sewage (domestic sewage) Sewage containing human excrement and/or household wastes that originate from sanitary conveniences of a dwelling, business, building, factory, or institution. Does not include storm water.

sanitary sewer **1.** A sewer line designed to carry only liquid or waterborne waste from the structure to a central treatment plant. **2.** The conduit or pipe that carries sanitary sewage.

sanitary tee A T-fitting for pipe, having a slight curve in the 90° transition so as to channel flow from a branch line toward the main flow.



sanitary tee

sanitary ware Devices of porcelain enamel, stainless steel, or other material, such as bathtubs, sewer pipes, toilet bowls, and washbasins.

Santorin earth A volcanic tuff originating on the Grecian island of Santorini and used as a pozzolan.

sap grade **1.** A grade of southern yellow pine export lumber. **2.** KD saps.

saponification Gray residue that has collected on the inside surface of a concrete sub-grade wall or floor. It is the result of moisture leaching chemicals from the concrete.

sapwood The wood just beneath the bark of a tree, normally lighter in color than the rest of the wood, but usually not as strong as the rest of the wood.

sarking (sarking board) A thin board employed in sheathing applications, as under the tiles or slates of a roof.

c19.indd 272 06/09/12 9:05 AM

Sarnafill A roofing manufacturer known for a product used as a substitute for copper roofing because of its lower cost and green color.

sash (window sash) The framework of a window that holds the glass.

sash adjuster *See* **casement stay**.



sash (window sash)

sash and frame A preassembled unit consisting of a cased frame and a double-hung window.

sash balance A spring-loaded device, usually a spring balance or tape balance, used as a counterbalance for a sash in a double-hung window. A sash balance replaces sash weights, cords, and pulleys.

sash block *See* **jamb block**.



sash and frame

sash center (sash plate) The support for a horizontally pivoting sash or transom, consisting of a socket that is secured to the jamb or frame, and a pin on which the sash or transom actually pivots.

sash chain A metal chain used in place of a sash cord to connect a vertically hung sash with its counterweight.

sash chisel A chisel having a wide blade honed on both sides, used for deep cutting, such as cutting the mortises in pulley stiles.

sash cord A rope connecting a sash with its counterweight in a double-hung window.

sash-cord iron A metal holder used to connect a sash cord or chain to the window.

sash counterweight *See* **sash weight**.

sash door *See* **glazed door**.

sash fast (sash fastener, sash holder) Any fastening device that holds two window sashes together to prevent their opening or rattling. A sash fast is usually attached to the meeting rails of a double-hung window.

sash fillister **1.** A rabbet cut in a glazing bar to receive the glass and glazing compound. **2.** A special plane for cutting such rabbets.

sash hardware All accessories used to balance a vertically hung sash, including chains or cords, weights, and pulleys.

sash holder *See* **sash fast**.

sash lift *See* **window lift**.

sash lift and hook A sash lift having a locking lever that holds the window fixed by contact with a strike in the frame. Raising the sash automatically releases the strike.

sash line *See* **sash cord**.

sash lock A sash fast that is controlled by a key. *See also* sash fast.

sash plane A carpenter's plane having a notched cutting blade for trimming the inside of a door frame or window frame.

sash plate (sash center) One of the pair of plates constituting the pivoting mechanism for a horizontally pivoting sash or transom.

sash pocket *See* **pocket**.

sash pull A plate, with a recess for fingers, set in a sash rail, or a handle attached to a rail to use in raising or lowering a window.

sash pulley A pulley mortised into the side of the frame of a double-hung window. The sash chord or chain passes over the pulley to the sash weight.

sash ribbon A metal tape used in place of a sash chord or chain.

sash saw **1.** A small miter saw used to cut the tenons of sashes. **2.** A saw fitted in a frame that moves vertically.



sash pull

sash schedule Information provided on design drawings regarding the selection and installation of window sashes.

sash spring bolt *See* **window spring bolt**.

sash stop (window stop) A small strip fastened to a cased frame to hold a sash of a double-hung window in place.

sash stuff Wood cut to standard sizes and shapes for use in making window frames.

sash tool A round brush used in painting items such as window frames and glazing bars.

sash weight A weight, usually cast iron, used to balance a vertically hung window.

sash window Any window, but usually a double-hung window, having a vertically or horizontally sliding sash.

saturant **1.** A substance, usually a diluted encapsulant, added to water to increase the amount of solute that can be dissolved at a certain temperature. A wetting agent used to improve penetration. **2.** A bituminous material with a low softening point, used for impregnating felt in asphalt-prepared roofing.

saturated air Air that contains the maximum amount of water vapor it can hold at its temperature and pressure.

saturated surface dry Condition of an aggregate particle or other solid when the voids between the particles are filled with water and no water is on the exposed surfaces.

saturated vapor pressure The pressure at a given temperature in a closed container that contains a liquid and the vapor from that liquid, once equilibrium conditions have been reached.

saturation temperature The temperature at which vapor and liquid coexist in stable equilibrium.



saucer dome

saucer dome A dome that has a rise less than its radius.

sauna A room in which a person bathes in steam produced when water is sprayed or poured over heated rocks or another heated surface.

savings-to-investment ratio (SIR) A dimensionless measure of performance that expresses the ratio of savings to costs, recommended for establishing priorities among projects.



sauna

The numerator of the ratio contains the operation-related savings; the denominator contains the increase in investment-related costs.

saw **1.** To cut by means of a hand or powered tool having a thin, flat metal blade, band, or stiff plate with cutting teeth along the edge. **2.** A toothed steel device used to cut construction materials.

saw bench A bench on which a circular saw is mounted.

saw cut (control joint) A cut made in hardened concrete by diamond or silicone-carbide blades or discs.

sawdust concrete Concrete in which the aggregate consists mainly of sawdust from wood.

sawed finish Descriptive of the surface of any stone that has been sawn.

sawed joint A joint cut in hardened concrete by special equipment to less than the full depth of the member.

sawhorse (sawbuck) A four-legged bench, usually used in pairs, made primarily to hold wood while being sawed.

saw kerf A slot or kerf that is cut into wood with a saw.

sawn veneer Veneer that has been cut from a block with a saw, rather than peeled on a lathe or sliced off by a blade. Sawn veneer is sometimes said to be more solid than sliced or peeled veneer. Because of saw kerf waste, it is more costly to produce.

saw set **1.** The angle at which the teeth of a saw are set. **2.** A tool used to set the teeth of a saw at a desired angle.

saw table The table or platform of a power saw.

saw texture A texture put on a piece of siding or paneling by a saw or knurled drum to give it a textured, rough, and/or resawn appearance.

saw-tooth roof (sawtooth roof) A roof with a profile similar to the teeth in a saw, composed of a series of single-pitch roofs, whose shorter or vertical side has windows for light and air. This roof shape is found primarily on industrial buildings.

sawyer In a sawmill, a worker who operates the head rig, or main saw, to make the initial cuts on a log. Also refers to a concrete saw operator.

scab A short piece of wood fastened to two formwork members to secure a butt joint.

scabble To dress stone with a pick, scabbling hammer, or broad chisel, leaving prominent tool marks so that a rough surface is left. Finer dressing usually follows.

scabbling hammer (scabbing hammer) A hammer, used for rough dressing stone, with one end pointed for picking.



scabbling hammer

scaffold **1.** Any temporary, elevated platform and its supporting structure used for supporting workmen and/or materials. **2.** Any raised platform.

scaffold board A board used in forming a work platform on a scaffold.

scaffold height That height of a wall under construction that necessitates the addition of another section of scaffold so that construction of the wall can continue.



scaffold

scagliola Plasterwork in imitation of ornamental marble, consisting of ground gypsum and glue colored with marble or granite dust.

scalability The issue of how well a system behaves as the data it uses grows in size. Some applications operate well only with small datasets. File-based systems tend to have file size limitations while systems that use a database tend to be much less dependent on file size.

scale **1.** A draftsman's tool with proportioned, graduated spaces. **2.** A system of proportioned drawing in which lengths on a drawing represent larger or smaller lengths on a real object or surface. **3.** The flaky material resulting from corrosion of metals, especially iron or steel. **4.** A heavy oxide coating on copper or copper alloys resulting from exposure to high temperatures and an oxidizer. **5.** Any device for measuring weight.

scale drawing A drawing in which all dimensions are reduced proportionately according to a predetermined scale.

scaling Local flaking or peeling away of the near-surface portion of hardened concrete or mortar, or of a layer from metal

scaling hammer A hand or power hammer used in a chiseling fashion in masonry work.

scaling, light Does not expose coarse aggregate.

scaling, medium Involves loss of surface mortar to 5 to 10 mm in depth and exposure of coarse aggregate.

scaling, severe Involves loss of surface mortar to 5 to 10 mm in depth with some loss of mortar surrounding aggregate particles 10 to 20 mm in depth.

scaling, very severe Involves loss of coarse aggregate particles, as well as mortar, generally to a depth greater than 20 mm.

scalper A sieve for removing oversized particles.

scalping The removal of particles larger than a specified size by sieving.

scant Less than standard or required size.

scantling **1.** A small piece of lumber, ordinarily yard lumber, 2″ thick and less than 8″ wide, or lumber not more than 5″ square. **2.** The dimensions, especially width and thickness, of construction materials such as stone or timber. **3.** A stud or similar upright framing timber. **4.** Any hardwood that has been squared, but is not of standard dimensions.

scarf joint A joint made by chamfering, or beveling, the ends of two pieces of lumber or plywood to be joined. The angled cut on each is made to correspond to the other so that the surfaces of the two pieces being joined are flush.

scarify **1.** To break up or scratch a surface such as earth or pavement. **2.** To roughen a surface by sanding or other means to improve adhesion of paint.

scarp A steep slope, natural or man-made.

schedule A chronological itemization, often in chart form, of the sequence of project tasks.

schedule contingency Duration added to a schedule activity to allow for the probability of possible or unforeseen events. Use in this manner is not recommended as the contingency is hidden and may be misused.

schedule number Schedule numbers are American Standards Association designations for classifying the strength of pipe.

Schedule 40 is the most common form of steel pipe used in the mechanical trades.

schedule of values (cost breakdown) A listing of elements, systems, items, or other subdivisions of the work, establishing a value for each, the total of which equals the contract sum. The schedule of values is used for establishing the cash flow of a project.

schema As applied to databases, the abstract representation or model of data for some use. SQL is a popular database language for creating and operating on database schemas.

schematic design phase (schematic drawing) The phase of design services in which the design professional consults with an owner to clarify the project requirements. The design professional prepares schematic design studies with drawings and other documents illustrating the scale and relationship of the project's components to the owner. A statement of estimated construction cost is often submitted at this phase.

schist A metamorphic rock, the constituent minerals of which have assumed roughly parallel beds, used principally for flagging.

Schmidt hammer An instrument used to measure the compressive strength of concrete. Testing involves gauging the distance of the hammer's rebound after it strikes the material.

scissor lift An electric or gas-powered platform mounted on folding arms and used to provide elevated work areas or to raise or lower unit loads.

scissors truss A roof truss with tension members extending from the foot of each principal rafter to the upper half of its opposite member.



scissors truss

scope creep Gradual progressive change (usually additions to) of the project's scope such that it is not noticed by project management team or customer. Typically occurs when the customer identifies additional, sometimes minor, requirements that, when added together, may collectively result in a significant scope change, resulting in cost and schedule overruns.*

scope of work An accurate, detailed, and concise description of the work to be performed by the contractor, the owner, and third parties in a construction contract.

scoping A primary component process in response to a request for a JO proposal, which includes a site visit by the contractor's representative(s) and the owner's representative(s) to identify and document various site characteristics and job conditions that will be impacted by the project's design and/or owner's intent.

score **1.** In concrete work, to modify the top surface of one pour, as by roughening, so as to improve the mechanical bond with the succeeding pour. **2.** To tool grooves in a freshly placed concrete surface to reduce cracking from shrinkage. **3.** To scratch or otherwise roughen a surface to enhance the bond of plaster, mortar, or stucco that will be applied to it. **4.** To groove, notch, or mark a surface for practical or decorative purposes.

S corporation A corporation that has elected to be taxed like a partnership, in accordance with the provisions of subchapter S of the Internal Revenue Code.

scotia A deep, concave molding more than ¼ round in section, especially as found in classical architecture at the base of a column.

scour **1.** Erosion of a concrete surface by water movement exposing the aggregate. **2.** Erosion of a river bottom by water movement.

scouring Smoothing freshly applied mortar or plaster by working it in circular motions with a cross-grained wooden float.

scraper **1.** A digging, hauling, and grading machine having a cutting edge, carrying bowl, a movable front wall or apron, and a dumping or ejecting mechanism. **2.** A machine that is towed behind a vehicle to level the ground surface.

scraping Removal of a top layer of paint with a sharp instrument, such as a scalpel.

scratch To score or groove a coat of plaster to provide a better bonding surface for a successive coat.

scratch-brushed finish (satin finish) A surface finish rendered by mechanical wire brushing or abrasive buffing.

scratch coat The first coat of plaster or stucco applied to a surface in three-coat work and usually cross-raked or scratched to form a mechanical key with the brown coat.

SCR brick A patented brick with nominal dimensions of 22/3″ × 6″ × 12″, as designated or classified by the Structural Clay Research (trademark of the Structural Clay Products Institute). It will render three courses in 8" and will render a wall whose nominal thickness is 8″.



SCR brick

screed **1.** To strike off concrete lying above the desired plane or shape. **2.** A tool for striking off the concrete surface, sometimes referred to as a *strikeoff*.



screed

screed coat The plaster coat made flush with the screeds.

screed guide Firmly established grade strips or side forms for unformed concrete that will guide the strikeoff in producing the desired plane or shape.

screeding The operation of forming a surface by the use of screed guides and a strikeoff. *See also* **strike off**.

screed strip One of a series of long narrow strips of plaster, carefully leveled to serve as guides for the application of plaster to a specified thickness.

screen façade An architectural facing used to disguise the shape or size of a building.

screenings That portion of granular material that is retained on a sieve.

screen mold A molding, originally used in the construction of screens and now used extensively in cabinetry and finished carpentry, where a clear strip is required, as on the edge of a shelf made of plywood or particle board.

screw A fastener with an external thread.

screw anchor A type of molly whose metal, plastic, or fiber shell is inserted into a hole in masonry, plaster, or concrete, and expanded when the screw is driven in.

screw clamp A woodworking tool consisting of a pair of opposing jaws that can hold pieces of wood and are adjusted by two screws.

screw conveyor A helical screw shaft turning on the concentric axis of a pipe. Conveys fine-grained or liquid material.

screwdriver A hand tool with the shanks tip shaped to fit the recess in the head of a screw; used to drive or remove the screw.

screwdriver

screwed joint A pipe joint consisting of threaded male and female parts joined together.

screwnail *See* **drivescrew**.

scribe To mark and cut the edge of a member for an irregular cut that will allow it to fit a similarly irregular space.

scriber A pointed tool used to mark guidelines on wood, metal, and plastic.

scrim A coarse, meshed material, such as wire, cloth, or fiberglass, that spans and reinforces a joint over which plaster will be applied.

scroll compressor A rotary positive displacement compressor with a fixed and a rotating scroll, in which compression takes place by confining gas volume by the meshing of the scrolls.

scroll molding An ornamental molding, semicircle in cross section, with a slight overhang on the rounded surface that faces outward.

scroll saw A handsaw consisting of a thin blade in a deep U-shaped frame and a handle. A scroll saw is used for cutting thin boards, veneers or plates, and is especially good for cutting curves.

scrub plane A wood plane having a blade with a convex cutting edge, used in rough carpentry work.

scrub sink A plumbing fixture equipped to enable medical personnel to scrub their hands prior to a surgical procedure. The hot and cold water supply is activated by a knee-action mixing valve or by wrist or foot control.



scrub sink

scum **1.** A deposit, sometimes formed on the surface of clay bricks, caused by soluble salts in the clay that accumulate on the surface during drying, or by the formation of deposits during kiln firing. (2) A mass of organic matter that floats on the surface of sewage. **3.** A film of impure matter that forms on the surface of a body of water.

scupper Any opening in a wall, parapet, bridge curb, or slab that provides an outlet through which excess water can drain.

S curve A rudimentary method of illustrating the progress of billings as a function of time as measured against the schedule.



scupper

scutching Dressing stone with a special hammer whose head contains several steel points.

s-dry A description of lumber seasoned to a moisture content of 19% or less prior to surfacing.

seal A legal term used to describe the signature or other representation of an individual agreeing to the terms and conditions of an agreement or contract.

sealed bearing A conventional bearing that has been provided with seals on its sides so that the bearing can be used for longer periods without greasing.

sealed bid A bid, based on contract documents, that is submitted sealed for opening at a designated time and place.

sealed bidding A basic method of procurement that involves the solicitation of bids and the award of a contract to the responsible bidder submitting the lowest responsive bid. This type of bidding is commonly used on public works projects.

sealer **1.** Any liquid applied to the surface of wood, paper, or plaster to prevent it from absorbing moisture, paint, or varnish. **2.** A liquid coating applied over bitumen or creosote to restrict it from bleeding through other paints. **3.** A final application of asphalt or concrete to protect against moisture. **4.** Any liquid coating used to seal the pores of the surface to which it is applied.

sealing joints Filling pavement joints with a flexible material.

seal slab A concrete slab placed along the bottom of a trench to stabilize bedding material.

seal weld A weld used primarily to seal a joint against leakage.

seam A joint between two sheets of material, such as metal.

seaming The process of joining metal sheets by bending over or doubling the edges and pinching them together.



seam

seamless flooring Fluid- or trowel-applied floor surfaces that do not contain aggregates.

seamless pipe An extruded seamless tube having certain standardized sizes of outside diameter and wall thickness, commonly designated by nominal pipe sizes and American National Standards Institute's schedule numbers.

seam weld A resistance weld made in overlapping parts.

seasonal commodities Commodities that are normally available in the marketplace only in a given season of the year.*

seasonal energy efficiency ratio (SEER) A measure of cooling efficiency for air conditioning products. The higher the SEER rating, the more energy efficient the unit. The government's established minimum rating for air conditioning is 10.

seasoned **1.** Timber that is not green, having a moisture content of 19% or less, and is air- or kiln-dried. **2.** Cured or hardened concrete.

seasoning check A small split that occurs in the grain of wood when moisture is extracted too rapidly.

seat The cut made at the lower end of a rafter that enables it to fit securely over the top wall plate

seat angle A short leg on a steel angle fastened to a column or girder to support the end of a beam.



seat angle

seating pressure The pressure generated by the action of a spring and control air to close the automatic control valve plug against its seat.

second **1.** A piece of secondary quality or one not meeting specified dimensions. **2.** A unit measure of time.

secondary air **1.** Air that is introduced into a burner above or around the flames to promote combustion, in addition to the primary air that is premixed with the fuel or forced as a blast under a stoker. **2.** Air already in an air-conditioned space, in contrast to primary air that is supplied to the space.

secondary beam A flexural member that is not a portion of the principal structural frame of a building.

secondary branch In the plumbing of a building drain or water-supply main, any branch that is not the primary branch.

secondary combustion The burning of combustible gases and smoke that are not burned during primary combustion. Such combustion can be either by design to create added energy or an unintentional, undesirable event.

secondary consolidation (secondary compression, secondary time effect) The reduction in volume of a soil mass caused by the application of a sustained load to the mass and due principally to the adjustment of the internal structure of the soil mass after most of the load has been transferred from the soil water to the soil solids.

secondary containment A chamber for the collection of oil that has leaked from a fuel oil tank.

secondary feeder Any electrical conductor that runs from a building's service entrance to one of its distribution centers.

secondary light source A light source that is not itself a luminaire or otherwise intrinsically light-producing or light-emitting, but that instead receives light from another source and simply serves to redirect it, as by reflection or transmission.

secondary member A structural member that carries a load to a primary member. Examples include purlins, headers, and jambs.

secondary moment In statically indeterminate structures, the additional moments caused by deformation of the structure due to the applied forces. In statically indeterminate prestressed concrete structures, the additional moments caused by the use of a nonconcordant prestressing tendon.

secondary reinforcement Reinforcing steel in reinforced concrete, such as stirrups, ties, or temperature steel. Secondary steel is any steel reinforcement other than main reinforcement.



secondary reinforcement

secondary sheave A supplementary sheave or block used to enable double wrapping of hoisting ropes and increase traction and/or lifting power.

secondary subcontractor A subcontractor employed by the contractor to complete minor portions of the work, or a subcontractor other than those identified as primary subcontractors.

secondary winding The winding on the output side of a transformer.

second coat The second coat of plaster, which is the brown coat in three-coat work or the finish coat in two-coat work.

second-growth timber Wood from trees grown after a virgin forest has been cut down.

seconds A grade of lumber used in the hardwood industry and sometimes in the overseas trade, as in firsts and seconds.

secret dovetail (miter dovetail) A joint whose external appearance implies a simple miter joint, but having dovetailing concealed within it.

section **1.** A topographical measure of land area, equal to one mile square or 640 acres. One of the 36 divisions in a township. **2.** The most desired pieces of veneer, clipped to standard widths of 54″ and 27″, because of the ease of using them in assembling a panel. The actual width may vary from 48″ to 54″, or 24″ to 27″. **3.** A drawing of an object or construction member cut through to show the interior makeup. **4.** A segment of the project specifications that cover a work item.

sectional insulation Insulation that is manufactured to be assembled in the field, such as pipe insulation molded in two parts to fit around a pipe in the field.

sectional overhead doors Doors made of horizontally hinged panels that roll into an overhead position on tracks, usually spring-assisted.



sectional overhead doors

sectional valve In a piping system, a control valve that is used to isolate a section for repair or other reason.

section modulus A term pertaining to the cross section of a flexural member. The section modulus with respect to either principal axis is the moment of inertia with respect to that axis divided by the distance from that axis to the most remote point of the tension or compression area of the section, as required. The section modulus is used to determine the flexural stress in a beam.

security screen A heavy screen in a special frame used as a barrier against escapes or break-ins.



security screen

security screw A screw with a tamper-proof head design.

security system A system that monitors and may also document aspects of access control, various types of alarms, perimeter security, and closed circuit TV and video surveillance.

security window A steel window used in stores, warehouses, and similar commercial buildings to provide protection against burglary.

sediment (silt) Material that settles to the bottom of a liquid.

sedimentary rock Rock such as limestone or sandstone that is formed from deposits of sediment consolidated by cementitious material and/or the weight of overlying layers of sediment.

sediment basin A dug-out or depressed area used for retention of debris or sediment on a construction site.

seepage **1.** The slow percolation of water through a soil. **2.** The quantity of water that has moved slowly through a porous material.

seepage bed A trench at least a yard wide into which coarse aggregate and a system of distribution pipes are placed so as to allow the treated sewage that passes through them to seep into the surrounding soil.

segmental arch An arch where the curve through the length of the arch is less than a semicircle.

segmental member A structural member made up of individual elements prestressed together to act as a monolithic unit under service loads.

segment saw A large-diameter circular saw consisting of pie-shaped sections and whose narrow kerf makes it especially suitable for cutting veneer.

segregation The differential concentration of the components of mixed concrete, aggregate, or the like, resulting in nonuniform proportions in the mass.



segregation

seismic bracing Structural reinforcement that is designed to protect against wind and earthquake.

seismic code A building code pertaining to earthquakes and other seismic activity that governs structural design and defines the requirements of preventive measures.

seismic load (earthquake load) The assumed lateral load an earthquake might cause to act upon a structural system in any horizontal direction.

seizing **1.** Friction damage to a metal surface by another metal surface. **2.** Restriction or prevention of motion of a metal component caused by fusion or coherence with another component.

select A high-quality piece of lumber graded for appearance. Select lumber is used in interior and exterior trim, and cabinetry.

selected bidder The bidder selected by the owner to consider the award of a construction contract.

selective bidding A process of competitive bidding for award of the contract for construction whereby the owner selects the constructors who are invited to bid to the exclusion of others, as in the process of open bidding.

selective digging Separating two or more types of soil while excavating, such as loam from sandy soil.

selective glazing Window material, such as glass, that screens out the infrared and ultraviolet portions of the solar spectrum, but allows visible light to pass. Selective glazing is recommended if a clear appearance is desired, or if a high visible transmittance is required to meet daylighting goals.

select material Excavated pervious soil suitable for use as a foundation for a granular base course of a road, or for bedding around pipes.

select merchantable **1.** A grade of boards intended for use where knotty-type lumber of fine appearance is required. **2.** An export grade of sound wood with tight knots and close grain, suitable for high-quality construction and remanufacture.

select structural The highest grade of structural joists and planks. This grade is applied to lumber of high quality in terms of appearance, strength, and stiffness.

select tight knot (STK) A grade term frequently used for cedar lumber. Lumber designated STK is selected from mill run for the tight knots in each piece, as differentiated from lumber that may contain loose knots or knotholes.

selenitic cement (selenitic lime) A type of lime cement that has had its hardening properties improved by the addition of 5% to 10% plaster of paris.

self-ballasted lamp An arc-discharge lamp with a special built-in filament coil that controls both starting and operating currents.

self-closing fire door A fire door equipped with a closing device.

self-desiccation The removal of free water by chemical reaction so as to leave insufficient water to cover the solid surfaces and to cause a decrease in the relative humidity of the system. The term is applied to an effect occurring in sealed concretes, mortars, and pastes.

self-drilling screw A fastener that does not require a predrilled hole.

self-faced stone An undressed stone such as a flagstone.

self-furring Metal lath or welded-wire fabric formed in the manufacturing process to include means by which the material is held away from the supporting surface, thus creating a space for *keying* of the insulating concrete, plaster, or stucco.

self-furring nail A nail with a flat head and a washer or spacer in the shank, used for fastening reinforcing wire mesh and spacing it from the nailing member.



self-furring nail

self-healing A redundancy in a system or a network (such as a backup power supply) that allows operations to continue in the event of failures in certain components.

self-leveling sealant A sealant, such as one used on concrete joints or cracks, with properties such that the simple force of gravity will level it.

self-sealing paint A type of paint that can be applied over a surface of inconsistent porosity to seal it and still dry to a uniform color and sheen.

self-spacing tile Ceramic tile with protuberances on the sides that space the tiles for grout joints.

self-stressing concrete (chemically prestressed concrete) Expansive-cement concrete (mortar or grout) in which expansion, if restrained, induces persistent compressive stresses in the concrete.

self-tapping screw A screw designed to cut its own threads in a predrilled hole.

self-test An automatic diagnostic procedure.

selvage (selvedge) **1.** An edge or edging that differs from the main part of a fabric or granule-surfaced roll roofing. **2.** The finished lengthwise edge of woven carpet that will not unravel or require binding.

selvage joint In roofing, a lapped joint mortised with mineral-surfaced cap sheets. A small part of the longitudinal edge of the sheet below contains no mineral surfacing so as to improve the bond between the lapped top sheet surface and the bituminous adhesive.

semicircular arch A round arch whose intrados is a complete semicircle.

semicircular dome A dome constructed in the shape of a half-sphere.



semicircular arch

semiconductor **1.** An electric conducting material, with resistivity in the range between metals and insulators, such as germanium or silicon. **2.** Miniature electric devices manufactured from semiconductor materials.

semidetached dwelling One of a pair of dwellings with a party wall between them.

semidetached house One of a pair of houses with a party wall between them.



semidetached house

semidirect lighting Lighting from luminaires that direct 60° to 90° of the emitted light downward and the balance upward.

semidome A half-dome equal to one-fourth of a hollow sphere, as might be found above a semicircular niche or apse.

semiflexible joint In reinforced concrete construction, a connection in which the reinforcement is arranged to permit some rotation of the joint.

semigloss **1.** The degree of surface reflectance midway between glass and eggshell. **2.** Paints and coatings displaying these properties.

semi-indirect lighting Lighting from luminaires that direct 60° to 90° of their emitted light upward and the balance downward.

semirigid frame A type of structural framework construction in which some flexibility is allowed at the joints of columns and beams.

sensible heat Heat that alters the temperature of a material without causing a change in state in that material.

sensor A device designed to detect an abnormal ambient condition, such as smoke or high temperature, and to sound an alarm or operate a device.

separate-application adhesive An adhesive consisting of two parts, each part being applied to a different surface. The surfaces are brought together to form a joint.

separation **1.** The tendency of coarse aggregate to separate from the concrete and accumulate at one side as concrete passes from the unconfined ends of chutes, conveyor belts, or similar arrangements. **2.** The tendency of the solids to separate from the water by gravitational settlement.

septic system A wastewater treatment system installed at the site of a home. Systems typically include a septic tank in which waste is biologically processed and a drain field that allows remaining liquids to be absorbed by the soil.

septic tank A watertight receptacle that receives the discharge from a sewage system, or part thereof. They are constructed to separate solids from the liquid, digesting organic matter during a period of detention, and discharging the clarified liquids.



septic tank

sequence of operations An accounting of a system's procedures for start-up and shut-down, response to varying conditions, and certain scheduled operations.

sequence-stressing loss In posttensioning, the elastic loss in a stressed tendon resulting from the shortening of the member when additional tendons are stressed.

serial digital alarm communicator transmitter A transmitter that accepts output from devices such as a fire alarm control.

serial distribution A group of absorption trenches, seepage pits, or seepage beds arranged in a series so total effective absorption area of one is used before flow enters the next.

sericite A white clay material used in masonry as a filler in grouting cement. Also used as a paint extender.

series circuit A circuit supplying electrical energy to a number of devices connected so that the same current passes through each device.

series wiring A wiring configuration in which electrical current travels along one conductor or wire. Unlike parallel wiring, series wiring is seldom used.

serpentine wall Garden wall that follows a curved ogee path resembling a serpent.

server room A space (often designed with additional/backup power and cooling supply and protective systems) that houses computer servers and communications equipment.

service box Within a building, a metal box located at the point where the electric service conductors enter the building.

service conductors Those conductors (wires) that carry electrical current from the street mains, or transformers, to the service equipment of the building being supplied.

service dead load The dead weight supported by a structural member.

service drop The overhead conductors that connect the electrical supply or communication line to the building being served.



service conductors

service ell (street ell) A fitting for threaded pipe with a 45° or 90° bend, a male thread on one end, and a female thread on the other.

service entrance The location where an electrical supply line enters a building.

service entrance switch The circuit breaker or switch, with fuses and accessories, located near the point of entrance of supply conductors to a building and intended to be the main control and cut-off for the electrical supply to that building.

service lateral Those underground electrical service conductors (wires) between the street main, including any risers at a pole or other structure or from transformers, and the point of initial connection with the service entrance conductors in a terminal box or other enclosure either inside or outside a wall of the building being served. In the absence of such a box or enclosure, the service lateral connects the street main and the point at which the service conductors enter into the building.

service live load The live load specified by the general building code or bridge specification, or the actual nonpermanent load applied to a structural system.

service panel The main circuit breaker panel or fuse box where the electric service lead ties into the building's circuits.

service period In lighting, the number of hours per day that natural daylight provides a specified amount of illumination, often expressed as a monthly average.

service pipe **1.** The water or gas pipe that leads from a supply source, usually public distribution mains in the street, to the particular building(s) being served. **2.** The pipe or conduit through which underground service conductors are run from the outside supply wires to the customer's property.



service pipe

service road A road or drive in a complex that is intended for vehicles making deliveries or collecting waste.

service systems The heating, ventilating, air-conditioning, water, and electric distribution systems in a building.

service tee A tee fitting used for threaded pipe and having one end threaded on the outside, and the other end and the branch threaded on the inside.

service temperature The highest temperature at which a material can be used without compromising its strength or other properties.

service valve In a piping system, any valve that isolates a device or apparatus from the rest of the system.

set **1.** The condition reached by a cement paste, mortar, or concrete when it has lost plasticity to an arbitrary degree usually measured in terms of resistance to penetration or deformation. Initial set refers to first stiffening; final set refers to attainment of significant rigidity. **2.** To transform a resin or adhesive from its initial liquid or plastic state to a hardened state by physical or chemical action, such as condensation, polymerization, oxidation, vulcanization, gelation, hydration, or the evaporation of volatile ingredients. **3.** To drive a nail so far that its head is below the surface into which it has been driven. **4.** The overhang given to the points of sawteeth resulting in a kerf slightly wider than the saw to facilitate sawing motion.

setback The minimum distance required by code or ordinance between a building and a property line or other reference.

setback thermostat Programmable thermostat that can be set to different temperatures at different times of the day or week.

set point The desired value of the controlled variable (i.e., temperature, pressure).

setting bed The mortar subsurface to which terrazzo is applied.

setting block In glazing, a small block of wood, lead, neoprene, or other suitable material placed under the bottom edge of a light or panel to support it within the frame and prevent it from settling down onto the lower rabbet or channel.

setting shrinkage A reduction in volume of concrete prior to the final set of cement, caused by settling of the solids and by the decrease in volume due to the chemical combination of water with cement.

setting temperature The temperature to which an adhesive or resin must be subjected in order for setting to occur.

setting up That point in the initial drying of a paint or other liquid coating at which it is no longer able to flow.

settlement Sinking of solid particles in grout, mortar, or fresh concrete, after placement and before initial set.

settling The lowering in elevation of sections of pavement or structures due to their mass, the loads imposed on them, or shrinkage or displacement of the support.

settling basin An enlargement or basin within a water conduit that provides for the settling of suspended matter, such as sand; and is usually equipped with some means of removing the accumulated material.

set up **1.** The stationing of a surveying instrument, such as a transit.

sewage Any liquid home waste containing animal or vegetable matter in suspension or solution. Sewage may include chemicals in solution; ground, surface, or storm water may be added as it is admitted to or passes through the sewers.

sewage ejector A plumbing device used to raise sewage to a higher elevation.

sewage gas The mixture of gases, odors, and vapors, sometimes including poisonous and combustible gases, found in a sewer.



sewage ejector

sewage treatment plant Structures and appurtenances that receive raw sewage and bring about a reduction in organic and bacterial content of the waste so as to render it less dangerous and less odorous.

sewer Generally, an underground conduit in which waste matter is carried in a liquid medium.

sewerage The entire works required to collect, treat, and dispose of sewage, including the sewer system, pumping stations, and treatment plant.

sewer appurtenances Manholes, sewer inlets, and other devices, constructions, or accessories related to a sewer system but exclusive of the actual pipe or conduit.

sewer brick Low-absorption, abrasive-resistant brick intended for use in drainage structures.

sewer lateral or side sewer Part of a sanitary sewer system that delivers the wastewater from a home to the main sewer lines.

sewer stub or sewer tap The point at which a home's sewer line joins the municipal sewer system.

s-green A description of lumber surfaced while at a moisture content of more than 19%.

shading coefficient The measure of the solar heat coming through the glass of a window. A low shading coefficient means reduced air conditioning expense.

shaft 1.That portion of a column between the base and the capital. **2.** An elevator well. **3.** A pit dug from the ground surface to a tunnel to furnish access and ventilation. **4.** Any enclosed vertical space in a building used for utilities or ventilation. **5.** Any cylindrical rod connecting moving parts in a machine.



shaft

shaft wall Fire-resistant wall that isolates elevators, stairwells and vertical mechanical chases in high-rise construction. This wall must withstand the fluctuating (positive and negative) air-pressure loads created by elevators or air distribution systems.

shake 1. Roofing or sidewall material produced from wood, usually cedar, with at least one surface having a grain split face. **2.** A crack in lumber due to natural causes.



shake

shallow trench system A drainage system that can be used for dispersal of gray water for irrigation.

shank 1. The main body of a nail, screw, bolt, or similar fastener extending between the head and the point. **2.** The usually metal part of a drill or other tool that connects the working head to the handle.

shank hanger Device used to attach metal gutters to a structure by fastening to sheathing or rafters.

shape 1. A solid section, other than flat product, rod, or wire sections, furnished in straight lengths and usually made by extrusion; but sometimes fabricated by drawing. **2.** A wrought product that is long in relation to the dimensions of its cross section, which is of a form other than that of sheet, plate, rod, bar, tube, or wire. **3.** To work on a piece of wood or other material to make it conform to a predetermined desired or required pattern, or to render from its surface a specific texture or degree of smoothness.



shape

shaper 1. A woodworking machine with a vertically revolving cutter for cutting irregular outlines, moldings, etc., in wood placed on a table below the cutter. **2.** A metalworking machine similar to a planer, except that the cutting tool is moved back and forth across the surface.

sharp sand Coarse sand made up of particles of angular shape.

shaving A very thin slice of wood removed in dressing, and used in some types of panels.

shear 1. An internal force tangential to the plane on which it acts. **2.** The relative displacement of adjacent planes in a single member. **3.** To cut metal with two opposing passing blades or with one blade passing a fixed edge.

shear block Face nailing of plywood to wall studs to prevent the wall from sliding and falling.

shear braces A bracing system, usually using metal brackets or straps, that eliminates most structural wall sheathing.

shear connector 1. A welded stud, spiral bar, short length of channel, or any other similar connector that resists horizontal shear between components of a composite beam. **2.** A timber connector.



shear connector

shear diaphragms Members in a structure utilized to resist shear forces, such as those caused by wind load. *See also* **shear wall**.

shear failure (failure by rupture) Failure in which movement caused by shearing stresses in a soil or rock mass is of sufficient magnitude to destroy or seriously endanger a structure.

shearhead Assembled unit in the top of the columns of flat slab or flat plate construction to transmit loads from slab to column.

shearing force The algebraic sum of all the tangential forces acting on either side of the section at a particular location in a flexural member.

shearing machine An apparatus having a movable blade that passes a fixed cutting edge to cut metal.

shear legs A hoisting device from two or more poles fastened together near their apex, from which a pulley is hung to lift heavy loads.

shear plate 1. A shear-resisting plate used to reinforce the web of a steel beam. **2.** In heavy timber construction, a round steel plate usually inserted in the face of a timber to provide shear resistance in joints between wood and nonwood.



shear plate

shear-plate connector A type of timber connector employed in wood-to-wood or wood-to-steel applications.

shear reinforcement Reinforcement designed to resist shear or diagonal tension stresses.

shear slide A type of landslide where a section of earth slides away from the material beneath it in a single consolidated mass.

shear splice A type of splice designed to distribute the shear between the two members that it joins.

shear strain (shearing strain) The angular displacement or deformation of a member caused by a force perpendicular to its length.

shear strength The maximum shearing stress that a material or structural member is capable of developing, based on the original area of cross section.

shear stress The shear-producing force per unit area of cross section, usually expressed in pounds per square inch.

shear stud A short unthreaded bolt welded to the top flange of a steel beam. The shear studs are embedded in a concrete slab to form a composite beam and stud.



shear stud

shear wall (shearwall) A wall portion of a structural frame intended to resist lateral forces, such as earthquake, wind, and blast, acting in the plane or parallel to the plane of the wall.

sheath An enclosure in which posttensioning tendons are encased to prevent bonding during concrete placement.

sheathed cable Electric cable protected by nonconductive covering, such as vinyl.

sheathing **1.** The material forming the contact face of forms. Also called *lagging* or *sheeting*. **2.** Plywood, waferboard, oriented strand board, or lumber used to close up side walls, floors, or roofs preparatory to the installation of finish materials on the surface. **3.** The first covering of exterior studs or rafters by boards, plywood, or particleboard.



sheathing

sheathing felt Roofing felt that has been saturated or impregnated, usually with some type of bitumen of low softening point (100° to 160°F).

sheathing paper *See* **building paper**.

sheave **1.** The grooved wheel of a pulley or block. **2.** The entire assembly over which a rope or cable is passed, including not only the pulley wheel but also its shaft bearings and side plates.

sheave block A pulley with a housing and bail.

she bolt A type of form tie and spreader bolt in which the end fastenings are threaded into the end of the bolt, eliminating cones and reducing the size of holes left in the concrete surface.



she bolt

shed dormer A dormer window having vertical framing projecting from a sloping roof, and an eave line parallel to the eave line of the principal roof. A shed dormer is designed to provide more space under a roof than a gabled dormer would provide.



shed dormer

sheepsfoot roller A powered or towed earth-tamping or compacting machine consisting of a large drum with projecting studs or feet with enlarged outer ends.

sheet A thin piece of material, such as glass, veneer, plywood, or rolled metal.

sheet asphalt A plant-mixed asphalt paving material containing sand that has passed through a 10-mesh sieve, and some type of mineral filler.

sheet glass (common window glass) Flat glass made by continuous drawing.

sheeting **1.** Structural wood panel, usually OSB or plywood, installed over studs, floor joists, or rafters/trusses. **2.** Planks used to line the sides of an excavation, such as for shoring and bracing. **3.** Sheet piling. **4.** A form of plastic in which the thickness is very small in proportion to length or width, and in which the plastic is present as a continuous phase throughout, with or without filler.



sheeting

sheeting driver An air hammer attachment that fits onto the ends of planks to allow their being driven without splintering.

sheeting jacks Push-type turnbuckles used to support sheeting in a trench.

sheet lath Heavier and stiffer than expanded-metal lath, it is fabricated by punching geometrical perforations in copper alloy steel sheet.

sheet lead Lead that has been cold-rolled into a sheet and whose designation is determined by the weight of one square foot of the finished product.

sheet metal Metal, usually galvanized steel but also aluminum, copper, and stainless steel, that has been rolled to any given thickness between 0.06″ and 0.249″ and cut into rectangular (usually 4′ × 8′) sections, which are then used in the fabrication of such items as ductwork, pipe, and gutters.

sheet-metal screw Usually a self-tapping screw, either round, flat, or pan-headed, threaded from tip to head, and used without a nut for fastening lapped sheet metal and some other materials. When equipped with a pointed tip, no tap hole is required.



sheet-metal screw

sheet-metal work The fabrication, installation, and/or final product, such as the ductwork of a heating or cooling system, as performed or produced by a worker skilled in that trade.

sheetpiling A barrier or diaphragm formed of sheet piles that is used to prevent the movement of soil or keep out water during excavation and construction. Sheet piles are constructed of timber, sheet steel, or concrete.

Shelby tube A sampling device used to collect soil samples during a drilling operation.

shelf **1.** Any horizontally mounted board, slab, or other flat-surfaced device upon which objects can be stored, supported, or displayed. **2.** A ledge, as of rock, of a setback.

shelf angles Structural angles with holes or slots in one leg for bolting to the structure to support brickwork, stone, or terra cotta.

shelf cleat A wood (or other) strip that supports a shelf along one edge.

shelf life Maximum duration that a material can be stored and still remain in a usable condition.



shelf angles

shelf rest (shelf pin, shelf support) A type of angle bracket through whose vertical portion a pin is passed and inserted into one of several position-adjusting holes such as in a wall, or cabinet.

shelf standard A metal or wood shelf support with slots that allow adjustable placement of brackets to support shelving.

shell **1.** Structural framework. **2.** In stressed-skin construction, the outer skin applied over the frame members. **3.** Any hollow construction when accomplished with a very thin curved plate or slab.

shellac A transparent coating produced by dissolving lac, a resinous secretion of the lac bug, in denatured alcohol.

shell aggregate A type of aggregate made up of fine sands and the shells of mollusks, such as clams, oysters, and scallops.

shell construction **1.** A type of reinforced concrete construction in which thin curved slabs are primary elements. **2.** Construction in which a curved exterior surface has been obtained by using shaped steel and hardboard or curved plywood panels.

shell pile A load-supporting structural element that consists of a steel shell embedded in the ground and filled with concrete.

sherardizing A type of galvanizing process that is mainly used for small items such as fittings and fasteners. Sherardizing is the diffusion coating of zinc on steel, and is accomplished by submerging items in hot zinc dust.

shield In excavation, a short, hollow section mounted at the heading end of a jacked pipe or tunnel with a front-leaning plane to deter soil inflow.

shielded conductor An insulated electric conductor enclosed in a metal sheath or envelope.



shielded conductor

shielded metal-arc welding An arc welding process wherein coalescence is produced by heating with an arc between a covered metal electrode and the work. Shielding is obtained from decomposition of the electrode covering. Pressure is not used, and filler metal is obtained from the electrode.

shielded pair Two insulated wires in a cable wrapped with metallic braid or foil to prevent interference caused by external electric and magnetic fields and facilitate a clean transmission.

shielding (screening) **1.** The erection of an interfering barrier (usually made of metal) to prevent electric, magnetic, or electromagnetic fields from escaping or entering an enclosed area. **2.** Any device that blocks, diffuses, or redirects light, such as a baffle or lens.

shim A strip of metal, wood, or other material used to set base plates or structural members at the proper level for placement of grout, or to maintain the elongation in some types of posttensioning anchorages.

shingle **1.** A roof-covering unit made of asphalt, wood, slate, asbestos, cement, or other material cut into stock sizes and applied on sloping roofs in an overlapping pattern. **2.** A thin piece of material, such as wood, cement, asbestos, or plastic, used as an exterior wall finish over sheathing.



shingle

shingle lap A type of lap joint whereby the thinner of two tapered surfaces is lapped over the thicker.

shingle molding An exterior molding used at the joint of roof shingles and the fascia.

shingle nail A galvanized steel, aluminum alloy, or coated steel nail, often having a threaded shank. There are two types of shingle nails: one for wood shingles and one for asphalt shingles, the latter having a larger head.

shingle tile A flat clay tile used primarily for roofing and laid so as to overlap.

shinglewood Another name for western red cedar.

shingling hatchet (claw hatchet) Similar to a lath hammer, this tool consists of a hammer head, a hatchet, and a notch or nail claw.

shiplap Lumber that has been worked to make a rabbeted joint on each edge so that pieces may be fitted together snugly for increased strength and stability

shivering (peeling) The splintering that critical compressive stresses can precipitate in fired glazes or other ceramic coatings.



shiplap

shock load The impact load of material such as aggregate or concrete as it is released or dumped during placement.

shoe **1.** Any piece of timber, metal, or stone receiving the lower end of virtually any member. Also called a *soleplate*. **2.** A metal device protecting the foot, or point, of a pile. **3.** A metal plate used at the base of an arch or truss to resist horizontal thrust **4.** A support for a bulldozer blade or other digging edge to prevent cutting down. **5.** A cleanup device following the buckets of a ditching machine. **6.** A short section used at the base of a downspout to direct the flow of water away from a wall.



shoe

shoe molding A base shoe used at the bottom of a baseboard to cover the space between the finished flooring and the baseboard.

shooting board A jig to hold a board while its edge is being squared or beveled.

shooting plane A light plane used to square or bevel the edge of a board with a shooting board.

shop coat A surface coating applied in a fabricating shop.

shop drawings Drawings created by a contractor, subcontractor, vendor, manufacturer, or other entity that illustrate construction, materials, dimensions, installation, and other pertinent information for the incorporation of an element or item into the construction.

shop lumber (factory lumber) Lumber graded, in a shop or factory, according to the number of pieces, of designed size and quality, into which it may be cut.

shop painting The application of paint, usually one coat, to metals in the shop before shipment to a job site.

shop rivet A rivet driven in the shop.

shop steward A union official elected to represent members of a particular trade or department. Position responsibilities include soliciting new members, collecting dues, and initial negotiations for grievances.

shore (post, prop, strut, tom) A temporary support for formwork and fresh concrete or for recently built structures that have not developed full design strength.

shore hardness number A number representing the relative hardness of materials. It is the height of rebound observed when a standard hammer strikes the material being tested.

shore head A wood or metal horizontal member placed on and fastened to a vertical shoring member.



shore (post, prop, strut, tom)

shoring **1.** Props or posts of timber or other material in compression; used for the temporary support of excavations, formwork, or unsafe structures. **2.** The process of erecting shores.

shoring, horizontal A metal or wood load-carrying strut, beam, or trussed section used to carry a shoring load from one bearing point, column, frame, post, or wall to another. Horizontal shoring may be adjustable.



shoring



shoring, horizontal

shoring layout A drawing prepared prior to erection showing the arrangement of equipment for shoring.

short circuit An accidental electric connection of relatively low resistance between two points of different potential in an electric circuit, causing a high current flow between the two points.

short-cycling The turning off, followed by immediate restarting of a compressor or furnace.

short grain Wood in which part of the grain runs diagonally to the length of the piece and that is subject to failure under load.

short-length **1.** A piece of stock lumber usually less than 8′ (2.44 m) long. **2.** A piece of sawn hardwood usually less than 6′ (1.83 m) long (Brit).

short nipple A pipe nipple with a short unthreaded length between the threaded ends.

short-oil varnish A varnish having a low vehicle content, containing less than 15 gallons of oil per 100 pounds of resin.

short ton A unit of measurement of weight in the English system equal to 2,000 pounds.



short nipple

shotblasting A process similar to sandblasting, except that metal shot is used. Often used to remove oil and grime from old pavement surface.

shotcrete **1.** Mortar or concrete pneumatically projected at high velocity onto a surface. Also known as *air-blown mortar*. **2.** Pneumatically applied mortar or concrete, sprayed mortar, and gunned concrete.

shotcrete gun A pneumatic device used to deliver shotcrete or to move concrete.

shot saw A power tool that shoots steel pellets to cut and finish building stone.

shoulder **1.** An unintentional offset in a formed concrete surface usually caused by bulging or movement of formwork. **2.** The enlarged section of a bolt or screw shank just below the head.

shoulder bolt In construction, a fastener that attaches wall and roof paneling to framing members.

shoved joint A vertical joint in brickwork made by laying the brick in a bed of mortar and shoving the brick toward the last brick laid.

shower bath (shower, shower stall) The compartment and plumbing provided for bathing by overhead spray.

shower-bath drain A floor drain in a shower bath.

shower head A nozzle used to spray water in a shower bath.

shower mixer A valve in a shower bath used to mix hot and cold water supplies to obtain a desired water temperature.



shower bath (shower, shower stall)

shower pan A pan of concrete, terrazzo, concrete and tile, or metal used as a floor in a shower bath.

shower room Part of the worker decontamination enclosure system. Usually located between the equipment room and the clean room, acts as an airlock between contaminated and noncontaminated areas. Contains hot and cold tap water suitable for showering during decontamination.

shower stall door A door in a shower partition.

show rafter A rafter, often ornamental, that is visible below a cornice.

shrinkage Volume decrease caused by drying and/or chemical changes, such as of concrete or wood.



shower stall door

shrinkage-compensating A characteristic of grout, mortar, or concrete made using an expansive cement in which volume increase, if restrained, induces compressive stresses intended to approximately offset the tendency of drying shrinkage to induce tensile stresses.

shrinkage cracking The cracking of a structure or member due to failure in tension caused by external or internal restraints from carbonation and/or reduction in moisture content.

shrinkage factor The percentage of reduction in volume of a given soil from bank to compacted state.

shrinkage limit The water content at which a reduction in water content will not cause a decrease in volume of the soil mass but an increase in water will increase the volume.

shrinkage loss Reduction of stress in prestressing steel resulting from shrinkage of concrete.

shrinkage reinforcement Reinforcement designed to resist shrinkage stresses in concrete.

shrink-mixed concrete Ready-mixed concrete mixed partially in a stationary mixer and then mixed in a truck mixer.

shrunk joint A joint made by placing a piece of heated pipe over the ends of two cool pipes and allowing it to contract.

shunt An electrical device with a low resistance or impedance connected in parallel across another electrical device to divert current from the second device.

shutter A movable cover or screen used to cover an opening, especially a window opening.

shutter butt A narrow hinge used on shutters and small doors.



shutter

shutting shoe A receptacle of metal or stone set in the paving or ground beneath a gate with two leaves to receive the vertical bolt.

SIA format A standard format developed for alarm system communications interfaces.

siamese connection A wye connection on the outside of a building with two inlet connections, used by the fire department to supply water to a sprinkler and/or standpipe system.

sick building syndrome (SBS) A condition where a significant proportion of the occupants of a building experience symptoms that are not related to a specific disease and that usually disappear when they leave the building. These symptoms are usually caused by indoor pollutants such as volatile organic compounds.



siamese connection

sidecasting Piling soil beside the excavation.

side-dump loader An earth loader with its bucket mounted on a pivot so it can be dumped to either side as well as in front.

side-entrance manhole A deep manhole with the access shaft built into the side of the inspection chamber.

sidehill A slope crossing the line of work.

sidehill cut An excavation for a highway through a sidehill, leaving a bank on one side only.

side lap The distance that a piece of material, such as steel roof deck, overlaps an adjacent piece.

side light A fixed frame of glass beside a window or door.

sidelighting A form of daylighting that provides natural, directional light.

side mounting Typical mounting detail for posts and rails to a fascia when floor mounting is not an option.

side post One of a pair of posts in a roof truss, each set at an equal distance from the center of the truss.

side vent A vent connected to the drain pipe at an angle of 45° or less from vertical.

sidewalk door A cellar door opening directly onto a sidewalk. The door is flush with the sidewalk when closed.



sidewalk door

sidewalk elevator **1.** An elevator opening onto a sidewalk. **2.** An elevator platform without a cab that rises to a level flush with a sidewalk.

sidewall The exterior wall of a building.

side yard The open space between a side of a dwelling and the property line.

siding (weatherboarding) Lumber or panel products intended for use as the exterior wall covering on a house or other building.



siding (weatherboarding)

sieve A metallic plate or sheet, a woven wire cloth, or other similar device, with regularly spaced apertures of uniform size, mounted in a suitable frame or holder, for use in separating material according to size. In mechanical analysis, an apparatus with square openings is a sieve; one with circular apertures is a screen.

sieve analysis The determination of the proportions of particles within certain size ranges in a granular material by separation on sieves of different size openings.

sieve number A number used to designate the size of a sieve, usually the approximate number of openings per inch. The number is applied to sieves with openings smaller than ¼″ (6.3 mm).

sight glass A glass tube used to indicate the liquid level in boilers, tanks, etc.

sight rail A series of rails set with a surveying instrument, and used to check the vertical alignment of a pipe in a trench.

signal Aggregate waves that are transmitted or received.

signal sash fastener A sash fastener beyond reach of a person. The fastener consists of a catch operated by a ring moved by a fitting on a long pole.

silica Silicon dioxide (SiO_2).

silica brick A refractory brick made from quartzite containing approximately 96% silica with alumina and lime.

silica flour (silica powder) Very finely divided silica; a siliceous binder cement that reacts with lime under autoclave curing conditions. The flour is prepared by grinding silica, such as quartz, to a fine powder.

silica gel (synthetic silica) A drying agent made from a form of silica.

silicate paint A paint utilizing sodium silicate as the binding agent.

silicon A metallic element used mainly as an alloying agent but used in pure form in electrical rectifiers.

silicon bronze A copper alloy used in hardware and other applications where a high resistance to oxidation is desirable.

silicon carbide An artificial product (SiC), granules of which may be embedded in concrete surfaces to increase resistance to wear or as a means of reducing skidding or slipping on stair treads or pavement. Silicon carbide is also used as an abrasive in saws and drills for cutting concrete and masonry.

silicone A resin, characterized by water-repellent properties, in which the main polymer chain consists of alternating silicon and oxygen atoms, with carbon-containing side groups (free radicals). Silicones may be used in caulking or coating compounds or admixtures for concrete.

silicone-carbide paper A tough, black, water-resistant sandpaper used in wet sanding and finishing.

silicone paint A heat- and chemical-resistant paint used on chimneys, stoves, and heaters, that requires heat to cure.

sill **1.** The horizontal member of the bottom of a window or exterior door frame. **2.** As applied to general construction, the lowest member of the frame of the structure, resting on the foundation and supporting the frame.



sill

sill anchor An anchor bolt used to fasten a sill to its foundation.

sill cock A water faucet located on the exterior of a building roughly at the top of the sill. A sill cock is usually threaded to provide a connection for a hose.



sill anchor



sill course

sill course A course of brickwork at a windowsill, usually projected to shed water.

sill plate or mudsill **1.** A horizontal framing member installed on a structure's foundation. **2.** The bottom framing member of an interior wall frame.

sill seal Insulation (fiberglass or foam) installed between the foundation wall and wood sill plate to fill gaps.

silo **1.** A tower-like structure, usually cylindrical, used to store items such as grain, coal, or minerals. **2.** A structure built in the ground to house a military missile.

silt (inorganic silt, rock flour) **1.** A granular material resulting from the disintegration of rock, with grains largely passing a No. 200 (75-micrometer) sieve. **2.** Such particles in the range from 2 to 50 micrometers in diameter.

siltation test A test to measure the impurities present in a sand sample.

silt box A steel box in a catch basin that can be removed to clean out the silt.

silt trap A trap that catches waterborne soil before it can enter a drainage system and obstruct flow.

silver solder A solder containing silver and having a high melting point, used for high-strength solder joints.

simple beam A beam without restraint or continuity at its supports.

simple span The support-to-support distance of a simple beam.



simple span

simulated masonry Products manufactured from a variety of materials including cement, minerals, epoxy, and fiberglass and used to simulate natural stone.

single-acting door Any door mounted so that it swings in only one direction.

single-acting hammer A pile-driving hammer using compressed air or steam to raise the ram to the height from which it is dropped.

single-cleat ladder A ladder made of two side rails with single treads between them.

single-cut file A file having serrations cut in one direction only.



single-hubpipe

single-duct system An air-conditioning system using one duct to serve a number of different areas.

single-hubpipe A pipe with a hub at one end only.

single-hung window A window with a movable and a fixed sash that is vertically hung.

single-package refrigeration system A factory-assembled and tested refrigeration system shipped in one section. No refrigerant-containing parts are connected in the field.



single-ply roofing

single-ply roofing A membrane roofing system that uses polymer-based synthetic material in flexible sheet or liquid form as an alternative to traditional built-up roofing. Made from a variety of bitumens, polymers, fillers, plasticizers, stabilizers and other additives, single-ply roofing products are commonly applied over an insulating material and secured with ballast, mechanical fasteners or an adhesive.

single-point adjustable suspension scaffold A manually or power-operated platform supported by a single wire attached to its frame; used for light work only.

single-pole scaffold A platform resting on putlogs or crossbeams supported on ledger beams and posts on the outer side and by the wall on the inner side.

single-pole switch An electric switch with one movable and one fixed contact.

single prime contractor A constructor acting alone to fulfill the contractor's responsibility under the contract for construction.

single-roller catch A catch consisting of a spring-loaded roller on the door and a strike plate on the jamb. The door catches automatically and is opened by pushing or pulling.

single span Any structure without intermediate support.

single-stage absorption In an HVAC system, absorption chillers with one generator to evaporate refrigerant (water) from the solution.

single-stage curing An autoclave curing process in which precast concrete products are put on metal pallets for autoclaving and remain there until stacked for delivery or yard storage.



single-wythe wall

single-throw switch An electric switch opened or closed by the operation of a single pair of contacts.

single-wythe wall A stone, brick, or concrete wall that is one masonry unit thick.



sink

sink A plumbing fixture consisting of a water supply, a basin, and a drain connection.

sinker nail A wire nail with a small, slightly depressed head, driven below the surface of a wood member as a hidden fastener.

sinter The process of forming a material by heating powder to a temperature just below its melting point so that it fuses together.

sintering grate A grate on which material is sintered.

siphonage The removal of fluid from a device, such as a trap, caused by suction produced by fluid flow.

siphon break **1.** During a toilet flush, the point when air is reintroduced into the trapway, ending the siphoning or pulling action that empties the bowl. **2.** A small groove in a surface that breaks capillary action and diverts water.



siphon trap

siphon trap An S-shaped plumbing trap containing water as a gas seal.

S-iron A retaining plate at each end of a tie rod used with a turnbuckle to tie two masonry walls together.

sisal A fiber from the leaves of the sisal plant; used in making rope and cord, and as reinforcing in plaster.

sistering The reinforcement of a structural member by nailing or attaching a stronger piece to a weaker one.

site The location of the project geographically, usually defined by legal boundaries.

site analysis services Services, as described in a schedule of designated services, that are necessary to determine limitations of the site and the corresponding project requirements.

site audit A review of activities at a construction site to identify inappropriate material and wasteful management practices.

site built The construction of a structure at the site where it is to remain.

site characterization In an environmental remediation operation, the process of defining and analyzing the contaminants and media of a site to determine the nature and extent of contaminants present.

site closeout The final phase in an environmental remediation effort that occurs after it is determined that site poses no future significant health risk.

site conditions clause A contract clause that typically requires the contractor to, at a minimum, inspect and understand the grade level and above-ground job site conditions prior to the start of any construction activities. The clause may also obligate the contractor to take full responsibility for the site's subsurface conditions.

site drainage **1.** An underground system of piping carrying rainwater or other wastes to a public sewer. **2.** The water so drained.

site drawings Also called *civil drawings*, these illustrate a structure's relationship to the property, including various engineering improvements to the site, such as the sanitary system, utilities, paving walks, curbing, and so forth.

site investigation A complete examination, investigation, and testing of surface and subsurface soil and conditions. The report resulting from the investigation is used in design of the structure.

site plan A plan of the area of a proposed construction operation, including the building outline, parking, work areas, and/or property lines.

site preservation Minimizing the effect of a new building on the building site (environment).

site safety officer The person responsible for establishing the appropriate health and safety equipment to be used by workers at a hazardous waste site.

sitzbath A bathtub, designed to support a person in the sitting position, used for therapeutic treatment.

size To bring a piece to specified dimensions.

sized lumber Lumber uniformly manufactured to net surfaced sizes. Sized lumber may be rough, surfaced, or partly surfaced on one or more faces.

sizing (size) The application of diluted glue or adhesive to hardwood veneer to prepare the wood for application of a standard concentration of glue. Sizing reduces the amount of standard glue that will be absorbed. Sizing is often used when woods of different densities are glued together.

skeleton construction A type of construction in which loads are carried on frames made of beams and columns. Walls of upper floors are supported on the frames.

skeleton steps A simple stairway consisting of treads and a support carriage, but no risers.

skew back (skewback) A sloping surface against which the end of an arch rests, such as a concrete thrust block supporting the thrust of an arch bridge.

skew chisel A woodworking chisel with a sharp cutting edge of oblique angle and beveled sides.

skew corbel A specially shaped stone at the bottom of a stone gable forming an abutment for the coping, eave gutters, or wall cornices.

skewed Forming an oblique angle with a main center line.

skid resistance A measure of the frictional characteristics of a surface.

skim coat A thin coat of plaster, usually either the finish coat or the leveling coat.



skewed

skin **1.** The materials, such as steel, aluminum and/or glass that make up a curtain wall. **2.** The outer veneer or ply of a lamination or built-up piece. **3.** The thin face of a hollow-core door. **4.** A tough layer formed on the surface of paint in a container.

skin friction The friction between soil and a structure, such as a retaining wall, or between soil and a pile.

skirt (apron) The border or section of molding under a window stool.

skirting block **1.** A corner block where a base and vertical framing meet. **2.** A concealed block to which a baseboard is attached.

skylight A glazed opening in a roof to admit light.



skylight

slab A flat, horizontal (or nearly horizontal) molded layer of plain or reinforced concrete, usually of uniform but sometimes of variable thickness, positioned either on the ground or supported by beams, columns, walls, or other framework.

slab bar bolster A wire form used to support reinforcing while placing concrete.

slab form The formwork used in placing a concrete slab.

slabjacking A process used to correct concrete slabs that have sunk. Holes are drilled through the slab and materials are forced through the holes to raise the slab.

slab on grade A concrete slab placed on grade, sometimes having insulation board or an impervious membrane beneath it.



slab on grade

slab-on-grade construction A type of construction in which the floor is a concrete slab poured after plumbing and other equipment is installed.

slack The amount allowed for contingency in an estimate.

slack-rope switch A safety device that shuts off electric power to the drive of an elevator if the supporting cables become slack.

slag block A concrete masonry unit with blast furnace slag as the coarse aggregate.

slag concrete Portland cement concrete with blast furnace slag as the coarse aggregate.

slag sand A sandlike material made by crushing and grading blast furnace slag.

slake **1.** To add water to quicklime to make putty. **2.** To crumble or disintegrate on exposure to moist air.

slamming strip An inlay along the edge of the lockstile of a flush wood door.

slant A sewer pipe connecting a house sewer to a common sewer.

slasher saw A set of circular saws operated in combination for quick cross-cutting of lengths of wood before chipping or grinding into pulp fibers, or as fuel.

slat A thin, narrow strip of wood, metal, or plastic.

slate A fine-grained metamorphic rock possessing a well-developed fissility (slaty cleavage) usually not parallel to the bedding planes of the rock.

slate batten A batten fastened across rafters in order to support slates on a roof.

slate boarding Close boarding used to support slates or tiles.

slate roll (slate ridge) A cylindrical rod formed from slate, having a V-shaped notch cut on its underside, and used to form the ridge on a roof.

slating **1.** The installation of slates on a roof or wall. **2.** The slate shingles on a roof or wall, taken collectively.



slating

slave A mechanism under the control of a similar mechanism. A point that responds to a trigger. In fire safety systems, for example, if a fire alarm causes a siren to go off, the siren is the slave.

sled runner A hand tool with a curved or right-angled blade that is used to create uniform masonry joints.

sleeper One of many strips of wood fastened to the top of a concrete slab to support a wood floor

sleeper clip A metal clip used to fasten sleepers to a concrete subfloor.

sleeper joist A joist supported on sleepers.

sleeper wall Any short wall that supports floor joists.

sleeve *See* **pipe sleeve**.

slender beam A beam that if loaded to failure without lateral bracing of the compression flange would fail by buckling rather than in flexure.

slenderness ratio The ratio of effective length or height of a wall, column, or pier to the radius of gyration. The ratio is used as a means of assessing the stability of the element.

slewing Rotating the jib of a crane so the load moves through a horizontal arc.

sliced veneer Veneer sliced from a face of a squared-off log.

sliding fire door A fire door hung from an overhead track. The track may be sloped for direct gravity operation or horizontal with operation by weights, cables, and pulleys.

sliding sash Any window that moves horizontally in grooves.

slimline lamp A type of instant-starting fluorescent lamp with a single pin base.



sliding sash

slip Movement occurring between steel reinforcement and concrete in stressed, reinforced concrete indicating anchorage breakdown.

slip form (slipform, sliding form) A form that is pulled or raised as concrete is placed. The form may move in a generally horizontal direction to lay concrete evenly for highway paving or on slopes and inverts of canals, tunnels, and siphons; or vertically to form walls, bins, or silos.

slip joint **1.** A vertical joint between an old and a new brick wall, made by cutting a slot in the old wall and filling it with brick projecting from the new wall. **2.** A joint in plumbing in which one pipe slips within another and the seal is made by a pressure device fitting over the joint, often threaded to the larger pipe.

slip-joint conduit Electric conduit connected by short couplings that slip over the ends of the conduit.



slip-joint conduit

slip-joint pliers Pliers having jaws connected by a rivet through a slot in one part, allowing two settings for the jaws.

slip match A veneer pattern that creates a repeat effect by laying similarly grained wood sheets alongside each other.

slip-resistant tile Ceramic tiles with abrasive particles or grooves in the surface.

slip stone A handheld, coarse sharpening stone used to hone cutting and woodworking tools.

slope **1.** The angle of repose at which a soil material will stand without moving. **2.** The slope of a roof, ramp or paving expressed as one unit of rise to one unit of run.

slope map A map displaying the topography of an area, along with a discussion of topographic features.

slope ratio Relation of the horizontal projection of a surface to its rise. For example, 2′ horizontal to 1′ rise is shown as 2:1 or 2 to 1.

slop sink A deep sink set low on a wall, used to clean mops and to empty and clean pails.

slot outlet An air-supply outlet with a length-to-width ratio greater than 10:1.



slop sink

slot weld A weld between two members made by welding within a slot in one of the members.

sloughing Subsidence of shotcrete, due generally to excessive water in mixture.

slow-burning A misleading term implying a material is fire-safe. The term must be related to a particular test for interpretation.

slow-burning construction Heavy timber construction with large flat surfaces, as opposed to joisted construction.

slow-curing asphalt Liquid asphalt made of asphalt cement and oils of low volatility.

slow-evaporating solvent A solvent with a high boiling point, used to lengthen, and thus improve, the drying time of paint.

sludge **1.** The semi-liquid, settled solids from treated sewage. **2.** Waste material composed of wet fines produced from grinding a terrazzo floor. **3.** Accumulated solids in the wash water reservoir of paint spray booths.

slugging The pulsating and intermittent flow of shotcrete material due to improper use of delivery equipment and materials.

sluice A steep, narrow passage for water. *See also* **sluicing**.

sluicing Moving soil by use of rapidly flowing water, for excavation or particle grading.

slump A measure of consistency of freshly mixed concrete, mortar, or stucco equal to the subsidence measured to the nearest ¼″ (6 mm) of the molded specimen immediately after removal of the slump cone.

slump block A concrete masonry unit intentionally removed early from a mold so that it slumps slightly.


slump block

slump cone A mold in the form of the lateral surface of the *frustum* of a cone with a base diameter of 8″ (203 mm), top diameter 4″ (102 mm), and height 12″ (305 mm), used to fabricate a specimen of freshly mixed concrete for the slump test. A cone 6″ (152 mm) high is used for tests of freshly mixed mortar and stucco.



slump cone

slump test The procedure for measuring slump.

slurry A mixture of water and any finely divided insoluble material, such as Portland cement, slag, or clay in suspension.

slurry seal machine A self-propelled machine used for delivering a mixture such as an asphalt emulsion slurry seal.

slurry wall A vertical trench used to contain, capture, or redirect groundwater flow in the vicinity of a environmental remediation site.

smart actuator A device that combines control and sensor capabilities.

smart building *See* **intelligent building**.

smart escalator An escalator that has controls, such as automatic slowing or stopping of the system when it is not being used.

smart glass Glazing that can adjust for opacity and light and heat transmission.

smart lighting Lighting designed for energy efficiency. May include high efficiency fixtures, daylighting and automatic controls that make adjustments based on conditions such as occupancy.

smart time scheduling A control system for lighting and HVAC based on time settings rather than occupancy sensors.

smart window Any window that uses removable coatings or a light-sensitive suspended particle device to allow for greater control of solar gain.

smelting The process of melting a metal, typically in a blast furnace, or fusing it to separate it from impurities.

smoke **1.** A suspension in air of particles that are usually solid. **2.** Carbon or soot particles less than 0.1 micron in size, resulting from incomplete combustion, such as of oil, wood, or coal.

smoke and fire vent A vent cover, installed on a roof, that opens automatically when activated by a heat-sensitive device, such as a fusible link.

smoke chamber The transition portion of a chimney between the fireplace and the flue.

smoke damper A damper arranged to close and stop flow automatically when smoke is detected.

smoke-developed rating A relative number indicating the smoke produced when the surface of a material burns, as measured during an ASTM E-119 flame spread test.


smoke chamber

smoke shelf A concave shelf at the back of a smoke chamber to redirect downdrafts up the chimney.

smoke test A test using a nontoxic, visible smoke to determine the routes taken by air currents and/or to detect leaks.

smoke zone or smoke control zone **1.** A building space with compartmentalization and pressurization that can control smoke. **2.** An HVAC zone where smoke is detected.

smoother bar A heavy, rod-like attachment to excavation equipment that breaks up clumps of soil disturbed during excavation operations.

smoothing iron A handheld, hot iron with a long handle, used for smoothing asphaltic pavement joints.

smoothing plane A small, fine carpenter's plane used for finishing.

smooth-surfaced roofing A built-up roofing membrane, the top surface of which is either hot-mopped asphalt, an asphalt emulsion of a cutback coating, or an inorganic top felt.


smooth-surfaced roofing

snake **1.** A long, resilient wire used by electricians in running wires through conduit. The snake is pushed through and then used to pull the wires. **2.** A flexible metal wire used to clear clogged plumbing fixtures.

snap cutter One of a variety of hand tools used to cut tile, cast iron pipe, and fittings.


snap cutter

snapping line A layout line made by stretching a chalked line across a surface and snapping the line.

snap switch A manually operated switch used to control low-power indoor circuits.

snap tie A proprietary concrete wall-form tie, the end of which can be twisted or snapped off after the forms have been removed.

snifter valve A valve that allows air into a tank or piping system automatically through the use of a mechanical device or by other external means.

snips *See* **tin snips**.

snow load The live load allowed by local code, used to design roofs in areas subject to snowfall.

soakaway An excavated pit designed to receive excess surface water for gradual draining.

soaking period In high-pressure and low-pressure steam curing, the time during which the live steam supply to the kiln or autoclave is shut off and the concrete products are exposed to the residual heat and moisture.

soap A brick or tile of normal face dimensions but with a nominal thickness of 2″.

soapstone A soft rock containing a high proportion of talc; used for such items as sinks, bench tops, and carved ornaments.

socket **1.** British term for the enlarged end of bell-and-spigot pipe. **2.** A mechanical device for supporting a lamp or plug fuse and completing the electric circuit.

socket plug A plug for the end of an interior-threaded pipe fitting consisting of a threaded piece with a recess into which a tool is placed to turn it.

socket weld A pipe joint made by use of a socket weld fitting that has a female end or socket for insertion of the pipe to be welded.

socket wrench A box wrench with a recessed socket at the end of a shank that fits over the head of a nut or bolt for tightening or removing the nut or bolt.



socket wrench

sod **1.** The upper layer of soil containing grass roots. **2.** High quality grass grown commercially for use in landscaping. Laid as a finished lawn.

soda-acid fire extinguisher A fire extinguisher that discharges water under pressure. The pressure is produced by mixing soda and acid to generate carbon dioxide.

sodium silicate A material that is used to waterproof concrete and mortar, to encapsulate asbestos, and to insulate.

sodium silicate adhesive A noncombustible, inorganic, high-strength adhesive with unsatisfactory weather resistance.

sodium vapor lamp An electric discharge lamp that produces light when sodium vapor is activated by current passing between two electrodes. Commonly used in street lights, they can take three to four minutes to warm up to full light output.



soffit

soffit The underside of a part or member of a structure, such as a beam, stairway, or arch.

soffit board A board that forms the soffit of a cornice.

soffit bracket A bracket used to mount an exposed exterior door closer to a door frame head or transom bar.



soffit bracket

softening point The temperature at which bitumen softens or melts; used as an index of fluidity.

soft solder A solder used to join metals in welding and brazing applications. It is typically a mixture of tin and lead, although soft solder of pure lead is used in some industries to join copper.

soft water Water with a low mineral content.

softwood **1.** A general term referring to any of a variety of trees having narrow, needle-like or scale-like leaves, usually coniferous. **2.** The wood from such trees. The term has nothing to do with the actual softness of the wood; some softwoods are harder than certain of the hardwood species.

soft glass Glass susceptible to thermal shock because it has a high coefficient of thermal expansion and a low softening point.

soft-mud brick Brick produced by molding, often by hand, relatively wet clay (20% to 30% moisture). When the inside of the mold is sanded to prevent sticking of the clay, the product is sand-struck brick. When the molds are wetted to prevent sticking, the product is water-struck brick.

soft rot Decay in wood, where the residue is chiefly cellulose.

soil A generic term for unconsolidated natural surface material above bedrock.

soil absorption system A disposal system, such as an absorption trench, seepage bog, or seepage pit, that utilizes the soil for subsequent absorption of treated sewage.

soil-cement Soil, Portland cement, and water mixed and compacted in place to make a hard surface for sidewalks, pool linings, and reservoirs, or for a base course for roads.

soil class A classification of soil by particle size, used by the U.S. Department of Agriculture: (a) gravel, (b) sand, (c) clay, (d) loam, (e) loam with some sand, (f) silt-loam, and (g) clay-loam.

soil classification test A series of tests combined with sensory observations used to classify a soil. The tests may include such aspects as grain size, distribution, plasticity index, liquid limit, and density.

soil creep The slow movement of a mass of soil down a slope, caused by gravity and aggravated by pore water.

soil drain A horizontal soil pipe.

soil hydraulic conductivity A measure of the rate at which water will flow through a soil matrix.

soil mechanics The application of the laws and principles of mechanics and hydraulics to engineering problems dealing with soil as a building material.

soil pipe A pipe that conveys the discharge from water closets or similar fixtures to the sanitary sewer system.

soil profile A vertical section through a site showing the nature and sequence of layers of soil.

soil sample A representative sample of soil from a specific location or elevation of a construction site, usually extracted to determine bearing capacity.

soil stabilizer **1.** A machine that mixes in-place soil and an added stabilizer, such as cement or lime, in order to stiffen the soil. **2.** A chemical added to soil to stiffen it and increase the stability of a soil mass.

soil stack A vertical soil pipe that carries the discharge from water closet fixtures.

soil vapor extraction A process that removes volatile organic compounds from a soil matrix through vacuum extraction of the air in the soil.

solar altitude A vertical measurement, between 0 and 90 degrees, used in solar analysis and design.

solar azimuth A horizontal measurement used for solar analysis and design.

solar cells Components in solar energy collection systems, they come in four basic types: (a) single-crystalline, (b) multicrystalline, (c) amorphous thin film, and (d) hybrid.

solar collector Any device intended to collect solar radiation and convert it to energy.

solar constant The average rate at which radiation energy from the sun is received at the surface of the earth, equal to 430 Btus per hour per square foot (1.94 cal. per min. per sq. cm.).

solar energy The radiant energy from the sun.

solar flat plate collector A solar collector in the shape of a flat plate, consisting either of a series of photovoltaic cells or a sandwich panel made up of a black surface, a film of circulating water or air, and a transparent cover.


solar flat plate collector

solar gain Heat that enters a building through windows as solar energy. Considered a "passive" heat source, as opposed to those sources that artificially generate heat.

solar heat exchanger A means of transferring the heat in storage in a solar heating system to the area to be heated.

solar heat gain coefficient (SHGC) The measure of the solar radiation admitted through a window, including radiation directly transmitted and that absorbed and subsequently released inward.

solar heating system An assembly of components, including collectors, heat exchangers, piping, storage system, controls, and supplemental heat source, used to provide heat and/or hot water to a building, with the sun as the main source of energy.


solar heating system

solar hot-water system A system that uses a collector, typically mounted on a roof, to absorb heat from sunlight.

solar insolation The amount of solar energy available at a given time in a given area.

solarium A room or porch with a great deal of glass and located for maximum exposure to the sun.


solarium

solar orientation The alignment of a building relative to the sun, initially set either for maximum or minimum heat gain, depending on the local climate.

solar pin That part of a building's heat load produced by solar radiation striking the building or passing through windows.

solar radiation Energy from the sun, which can be absorbed and converted into heat energy, reflected or transmitted.

solar screen **1.** An openwork or louvered panel of a building positioned to act as a sun shade. **2.** A perforated wall used as a sun shade.

solar storage Fluid and/or rocks used to hold some of the heat energy collected by a solar heat collector.

solder **1.** An alloy, usually lead-tin, with a melting point below 800°F (427°C), used to join metals or seal joints. **2.** The process of joining metals or sealing joints using solder and heat.

soldered joint A gas-tight pipe joint made by applying solder to a heated joint.

soldering gun A tool with a pistol grip and a small electrically heated bit that reaches operating temperatures rapidly, used to solder electrical components.

soldering nipple A nipple with one end threaded and the other plain. The plain end is used for a soldered joint and the threaded end for a mechanical joint.

soldier **1.** A vertical wale used to strengthen or align formwork or excavations. **2.** A masonry unit set on end so its long, narrow face is vertical on the face of the wall.

soldier beam A rolled-steel section driven into the ground to support a horizontally sheeted earth bank.

soldier course A course of brick units set on end with the long, narrow face vertical on the wall face.


soldier course

soldier pile **1.** In an excavation, a vertical member that supports horizontal sheeting and is supported by struts across the excavation and by embedment below the excavation. **2.** A vertical member used to support formwork and held in place by struts, bolts, or wires.

solenoid An electromagnetic coil used to activate a mechanical device or switch.

solenoid valve A valve opened by a plunger in which movement is controlled by an electromagnet.

soleplate **1.** A solepiece or shoe that serves as a base for studs in a core of solid wood or mineral composition, as opposed to a partition. **2.** A plate welded or bolted to the underside of a plate girder that bears on a pad.

solid core **1.** The inner layers of a plywood panel that contain no open irregularities, such as gaps or open knotholes, and in which the grain runs perpendicular to the outer plies. Solid core is primarily used as underlayment for resilient floor covering. **2.** A flush door, used in entries and as fire-resistant doors in which particleboard or wood blocks completely fill the area between the door skins.

solid-core door A door having a core of solid wood or mineral composition.

solid frame The frame of a door or window having jambs, head, and sill made of solid pieces of timber rather than parts.

solid glass door A door in which the glass essentially provides all the structural strength.

solid loading Filling a drill hole with explosive, except for a stemming space at the top.

solid masonry unit **1.** A masonry unit whose minimum net cross-sectional area parallel to its bearing surface is 75% or more of its gross cross-sectional area. **2.** A masonry unit having holes less than 3/4″ (2 cm) wide or less than 0.75 sq. in. (5 sq cm) passing through, or having frogs that do not exceed 20% of its volume. In either type, up to three handling holes, not exceeding 5 sq. in. (32.5 sq cm) each, are allowed. The total area of all through holes may not exceed 25% of the gross area.


solid masonry unit

solid masonry wall A wall built of solid masonry units with all joints filled with mortar and no hollow wythes.


solid masonry wall

solid modeling The general type of geometric modeling where the elements being modeled and operated on are closed and bounded, enclosing a volume. Solid modeling can represent solid shapes but also is misnamed because it can also represent the shapes of voids, such as a room.

solid mopping The application of hot asphalt over an entire roof surface.

solid punch A steel rod used to drive bolts out of holes.

solid rock Rock that cannot be moved or processed without being blasted.

solids content **1.** The portion of a protective coating material that remains on the surface after drying. Sometimes referred to as nonvolatiles. **2.** In an adhesive, the percentage of weight of the nonvolatile matter.

solid-state welding A welding process in which coalescence takes place at temperatures below the melting point of the metals being joined and without use of a brazing filler metal. Sometimes this is accomplished through the use of pressure.

solid-web steel joist A steel truss or light beam having a solid web; usually cold-formed from sheet steel and having a channel shape.



solid-web steel joist

solvent A liquid in which another substance may be dissolved.

solvent adhesive An adhesive having a volatile organic liquid as a vehicle.

solvent extraction An ex situ remediation process in which contaminated sediment, soil or sludge is mixed with a solvent to separate the contaminant from its existing matrix.

solvent welding A process where a chemical liquid solvent is used to soften and join together two or more thermoplastic materials.

sonic pile driver **1.** A vibrating pile-driving hammer. Puts a pile into its resonant vibration range, causing it to slide down into the soil. **2.** A machine used to drive piles or sheet piling into soil using a head vibrated at a high frequency, usually less than 6,000 times per minute.

Sonotube® A product consisting of a preformed casing made of laminated, waxed paper; used to form cylindrical piers or columns.

sound A vibratory disturbance, with the frequency in the approximate range between 20 to 20,000 cycles per second, capable of being detected by a human ear



Sonotube®

sound absorption The process of dissipating sound energy.

sound attenuation Measures taken to soundproof a wall or subfloor.

sound attenuation batt Insulation designed to reduce noise transmission.

sound attenuation fire batt (SAFB) Insulation that provides acoustical and thermal control, as well as fire resistance.

sound damping The use of fibrous sound-absorbing material in a partition to reduce sound transmission. Damping in floor/ceiling construction has a wider application for impact sound than for airborne sound.

sound deadening board A board with good sound absorption qualities; used in sound-control.

sound insulation (acoustic insulation) The use of materials and assemblies to reduce sound transmission from one area to another or within an area



sound insulation (acoustic insulation)

sound isolation Attenuating sound transmission between adjacent spaces.

sound knot A dead knot in wood that is undecayed, at least as hard as the surrounding wood, and held firmly in place.

sound leak Opening in a partition that allows air (and sound) to pass through. Examples include small holes in a wall, openings for electrical boxes and plumbing, and cracks around doors.

sound masking Provision of white noise to provide privacy or reduce distractions.

soundness The freedom of a solid from cracks, flaws, fissures, or variations from an accepted standard.

sound pressure The change in pressure resulting from vibration in the audible frequency range. Conversational speech at close range produces a sound pressure of about one dyne per sq. cm.

sound pressure level (SPL) Expressed in decibels, the SPL is 20 times the logarithm to the base 10 of the ratio of the sound pressure to a reference pressure of 20 micropascals.

soundproofing **1.** The design and construction of a building or unit to reduce sound transmission. **2.** The materials and assemblies used in a building or unit to reduce sound transmission.

sound-rated door A door constructed to provide greater sound attenuation than that provided by a normal door; usually carrying a rating in terms of its sound transmission class (STC).



sound-rated door

sound reduction factor The effectiveness, measured in decibels, that a building assembly exhibits at lessening the intensity of sound.

sound transmission The passage of sound from one point to another, as from one room to another, or from a street to a room within a building.

sound transmission class (STC) A single number indicating the sound insulation value of a partition, floor-ceiling assembly, door, or window, as derived from a curve of insulation value as a function of frequency. The higher the number is, the greater the insulation value.

sound transmission loss The reduction in sound when it passes through a partition, wall, or ceiling.

southern yellow pine A species group composed primarily of loblolly, longleaf, shortleaf, and slash pines. Various subspecies also are included in the group.

space frame Any three-dimensional structural frame capable of transmitting loads in the three dimensions to supports. A space frame is usually an interconnected system of trusses or rigid frames.

space heater A small heating unit, usually equipped with a fan, intended to supply heat to a room or portion of a room. The source of heat energy may be electricity or a fluid fuel.



space heater

space planning The process and act of laying out and designing space for a tenant's needs.

spacer **1.** A device that maintains reinforcement in proper position, or keeps wall forms a given distance apart before and during concreting. **2.** A small block of wood or other material placed during installation on the edges of a pane of glass to center it in the channel and maintain uniform width of sealant beads to prevent excessive sealant distortion.

spacing criterion The maximum distance between interior light fixtures that will ensure a uniform illumination on a work plane.

spacing factor (power spacing factor) An index related to the maximum distance of any point in a cement paste or in the cement paste fraction of mortar or concrete from the periphery of an air void.

spackle (speckling, sparkling) A paste, or a dry mixture blended with water to form a paste; used to fill holes and cracks in plaster, wallboard, or wood.

spade A sturdy digging tool having a thick handle and a flat blade that can be pressed into the ground with a foot.

spading Consolidating mortar or concrete by repeatedly inserting and withdrawing a flat, spadelike tool.

spall A fragment usually in the shape of a flake, detached from a larger mass by a blow through the action of weather, by pressure, or by expansion within the larger mass. A small spall involves a roughly circular depression not greater than 20 mm in depth nor 150 mm in any dimension; a large spall may be roughly circular or oval or, in some cases, elongated.

span The horizontal distance between supports.

spandrel (spandril) That part of a wall between the head of a window and the sill of the window above it.

spandrel beam A beam in the perimeter of a building spanning columns, and usually supporting floor or roof loads.

spandrel glass Opaque glass used in curtain wall construction to conceal structural elements.



spandrel glass

spanner **1.** A horizontal cross brace. **2.** A collar beam.

spar **1.** A common rafter. **2.** A heavy, round timber. **3.** A bar used as a gate latch.

sparge pipe A perforated pipe used to distribute flushing water for a urinal.

spark arrester (bonnet) A device at the top of a chimney or stack to catch sparks, embers, or other ignited material over a given size.

spar varnish A varnish with superior weather-resisting qualities; used on exterior wood.

spat A protective sheet, usually stainless steel, installed at the bottom of a door frame.

spatter dash (spatterdash) A rich mixture of Portland cement and coarse sand, thrown onto a background by a trowel, scoop, or other appliance so as to form a thin, coarse-textured, continuous coating. As a preliminary treatment, before rendering, it assists bonding of the undercoat to the background, improves resistance to rain penetration, and evens out the suction of variable backgrounds.

spec Abbreviation for "on speculation," used when a building is constructed before a buyer or tenant is obtained.

special assessment A charge imposed by a government on a particular class of properties to defray the cost of a specific improvement or service; presumably of benefit to the public but of special benefit to the owners of the charged properties.

special hazards insurance Insurance coverage for damage such as sprinkler leakage, water damage, collapse, and coverage for materials in transit (or off-site). The damage must be caused by additional perils and risks not covered in standard property insurance.

special matrix terrazzo A finish flooring consisting of colored aggregate and organic matrix.

special-quality brick A brick that is durable when used under conditions of exposure.

specialty drawings Graphic representations of the unique requirements of various spaces' special uses (such as kitchens, libraries, retail spaces, and home theater systems). Specialty drawings outline the coordination among other building systems, most commonly the mechanical and electrical systems.

special use permit Permission granted to a landowner to use property in a way that would not normally be allowed in a zoning district.

species A category of biological classification. A species is a class of individuals having common attributes and designated by a common name.

specific adhesion A bond created by chemical means, rather than mechanical.

specification A detailed and exact statement of particulars, especially a statement prescribing materials, dimensions, and workmanship for something to be built or installed.

specifications or specs Documents that define the qualitative requirements for products, materials, and workmanship upon which the contract for construction is based.

specific gravity **1.** The ratio of the mass of a unit volume of a material at a stated temperature to the mass of the same volume of gas-free distilled water at a stated temperature. **2.** The ratio of the density of one substance to another when used as the standard. Water is the standard for determining specific gravity of solids and liquids; hydrogen is used for gases.

specific gravity, bulk The ratio of the mass in air of a unit volume of a permeable material, including both permeable and impermeable voids normal to the material, at a stated temperature to the mass in air of equal density of an equal volume of gas-free distilled water at a stated temperature.

specific gravity factor The ratio of the weight of aggregates, including all moisture, as introduced into the mixer to the effective volume displaced by the aggregates.

specific heat A quantity that describes the ability of a body to absorb heat and increase its temperature. The specific heat of a substance is the ratio of the amount of heat that must be added to a unit mass to raise its temperature through one degree to the amount of heat that is required to raise the temperature of an equal mass of water one degree.

specific volume The volume of a given weight of a material, typically a gas, expressed as cubic feet per pound at specific conditions. Simply put, the reciprocal of density.

specifier One who writes or prepares specifications.

spectral power distribution The distribution of radiant power, usually expressed in watts per nanometer, with respect to wavelength.

spectrophotometer An instrument for measuring the intensity of radiant energy of desired frequencies absorbed by atoms of molecules. Substances are analyzed by converting the absorbed energy to electrical signals, proportional to the intensity of radiation.

speculative builder A contractor who develops, constructs, and then sells (or leases) a property.

speed square A triangular-shaped tool used to mark perpendicular and angled lines.

spigot **1.** The end of a pipe that fits into the bell, or upset, end of another pipe to form a joint after caulking. **2.** A faucet.

spike A heavy nail, sometimes having a square cross section, and 3″ to 12″ (7.6 to 30.5 cm) long.

spike-and-ferrule installation A type of gutter installation in which the gutter is secured by long nails in metal sleeves.

spiked grill fastener A multi-tooth connector made of steel that is used to fasten heavy timbers. Commonly used in roof truss and flooring construction.

spile **1.** A peg or plug of wood. **2.** A spout for directing the flow of sap from sugar maples. **3.** A heavy wooden stake.

spillway A passage to convey overflow water from a dam or similar structure.

spindle **1.** A small axle on which an object turns. **2.** The bar in a lock that connects the knob(s) or handle(s) with the latching mechanism. **3.** A short, turned-wood part, such as a baluster.



spiral reinforcement

spiral A continuously wound length of reinforcing steel in the form of a cylindrical helix.

spirally reinforced column A column in which the vertical bars are enveloped by spiral reinforcement, (i.e., closely spaced, continuous hooping).

spiral reinforcement Continuously wound reinforcement in the form of a cylindrical helix.

spiral spacer Reinforcement that keeps spirals a uniform distance apart.



spiral stair

spiral stair A flight of stairs whose treads wind around a central newel in a spiral or helix shape. *See also* **circular stair**.

spire Any long, slender, pointed construction on top of a building. A spire is often a narrow, octagonal pyramid set on a short, square tower.

spirit level A device used to set an instrument to true horizontal or true vertical, consisting of a glass tube nearly filled with liquid so a traveling air bubble is formed. Cheap levels are bent concave; better levels are ground internally to an overall concave shape.

spit The depth of one hand-shovel blade.

splash block A small masonry block set in the ground beneath a rain gutter to receive roof drainage and prevent puddling or soil erosion.



splashboard

splashboard **1.** A board placed on a wall at a sink to protect the wall. **2.** A weather molding placed on the bottom of an outside door. **3.** A board set against a wall at a scaffold to protect the wall.

splash brush A brush used to apply water to a finish coat of plaster while it is being troweled smooth.

splash lap That part of the overlap of a seam in sheet-metal roofing that extends onto the flat surface of the next sheet.

splay **1.** To form with an oblique angle, or to bevel. **2.** To spread out or extend.

splay brick (cant brick) A brick with one side beveled at about 45°.

splayed edge A bevel across the full thickness of a piece of wood.

splayed hangers Hangers installed at an angle rather than perpendicular to a support grid or channel.

splayed joint A joint between the ends of two adjacent members in which the ends of each are beveled to form an overlap.



splice

splice Connection of two similar materials to another by lapping, welding, gluing, mechanical couplers, or other means.

splice plate A plate laid over a joint and fastened to the pieces being joined to provide stiffness.

spline (false tongue, feather, slip feather, slip tongue) A piece of metal or wood used to join two pieces of wood, such as decking, together.

spline joint A joint formed by inserting a spline into slots formed in the two pieces to be joined.

splinter **1.** A small, thin, sharp piece of wood broken from a larger piece. **2.** To split or break something into splinters.

split **1.** A crack extending completely through a piece of wood or veneer. **2.** A tear in a built-up membrane resulting from tensile stresses. **3.** A masonry unit one-half the height of a standard unit.



split astragal

split astragal Two pieces of molding attached to the meeting edges of two leaves of a pair of swinging doors, allowing both leaves to be active.

split-batch charging A method of charging a mixer in which the solid ingredients do not all enter the mixer together. Cement or different sizes of aggregate may be added separately.

split-bolt connector A device that holds electrical wires in close contact with a simple assembly. Wires are fed through the device and held in place by a nut tightened on a threaded shaft.

split-conductor cable A cable in which each conductor consists of two or more insulated wires normally in parallel.



split face

split face An exposed, rough face of a masonry unit or stone created by splitting rather than forming or sawing the face.

split-face block Concrete masonry units with one or more faces produced by purposeful fracturing of the unit to provide architectural effects in masonry wall construction.

split fitting A section of electric conduit that is split longitudinally. After conductors have been placed in one half, the unit is assembled and secured with screws.

split frame (split jamb) A door frame with the jambs split in two or more pieces to allow the use of a pocket-type sliding door.

split hanger A two-piece pipe hanger that is tightened around a pipe.

split jamb A two-piece doorjamb that can be adjusted to accommodate varying wall thicknesses.

split level A type of house in which the floor levels on one side of the house are one-half story above or below those on the other side.



split level

split-phase motor An induction motor that typically has two windings, a main and an auxiliary. While noisier, more expensive, and harder to start than three-phase motors, single-phase motors are excellent for medium duty applications and where stops and starts are somewhat frequent.

split pin A pin or spike that spreads during insertion, or that can be split after insertion.

split ribbed block Concrete masonry units featuring a ribbed face with ribs that have been slit off, providing a rough texture.

split-ring connector A timber connector consisting of a metal ring set in circular grooves in two pieces; the assembly being held by bolts.



split-ring connector

split-spoon sampler A sampling device used to collect soil samples during well drilling.

splitter damper A single blade damper hinged at one end, installed to divert air from a main duct into a branch duct.

splitting tensile test (diametral compression test) A test for tensile strength in which a cylindrical specimen is loaded to failure in diametral compression applied along the entire length.

spoil Dirt or rock excavated and removed from its original location but not used for embankment or fill.

spokeshave A carpenter's tool for shaping curved edges, consisting of two handles and used as a drawing knife or planing tool.

spokeshave

sponge rubber Expanded rubber having interconnected cells, used as a resilient padding and as thermal insulation.

spoon **1.** A small, steel plasterer's tool used in finishing moldings. **2.** A recovery tool used in soil sampling.

spot In gypsum construction, to treat fastener heads with joint compound material. As the fastener sets below the surface of the board, an indentation is formed, allowing a recess, which is filled by spotting.

spot elevation A point on a map or plan with its existing or proposed elevation noted.

spot ground A piece of wood attached to a plaster base and used as a gauge for thickness of applied plaster.

spotter **1.** The person who directs a truck driver into a loading or unloading position. **2.** The horizontal framework between the machinery deck of a pile driver and the leads.

spotting **1.** Directing trucks for loading or unloading. **2.** Spots of adhesive material used to fasten a veneer to its backing. **3.** A defect in a painted surface consisting of spots of a different color, shade, or gloss than the rest.

spot-weld A small circular weld between two metal pieces made by applying heat and pressure.

spray bar A pipe with ports used to apply liquid asphalt to a road surface.

spray booth An enclosed or partly enclosed area used for the spray-painting of objects, usually equipped with a waterfall system to catch overspray and/or a filtered air supply and exhaust system.



spray bar

spray drying A method of evaporating the liquid from a solution by spraying it into a heated gas.

sprayed acoustical plaster An acoustical plaster applied with a special spray gun. The plaster usually has a rough surface and may be perforated with hand tools before hardening.

sprayed fireproofing An insulating material sprayed directly onto structural members with or without wire mesh reinforcing to provide a fire endurance rating.



sprayed fireproofing

spray-in-place insulation An insulation material applied with a gun or sprayer to surfaces or cavities. Examples include loose cellulose fiberfill and polyurethane foam.

spray painting Applying paint, lacquer, or a similar material with a special tool activated by air pressure.

spray pond A component of a cooling system that cools water for use by forcing it upward through spray nozzles and collecting it in a pool.

spreader **1.** A piece of wood or metal used to hold the sides of a form apart until the concrete is placed. **2.** A brace between two wales. **3.** A device for spreading gravel or crushed stone for a pavement base course. **4.** A stiffening member used to keep door or window frames in proper alignment during shipment and installation. **5.** An additive that increases the surface area over which a given volume of liquid will spread when poured on a solid or other liquid.



spreader

spreader box A piece of heavy construction equipment that connects to the back of a vehicle and spreads rock, asphalt, concrete, or other materials.

spread footing A generally rectangular prism of concrete, larger in lateral dimensions than the column or wall it supports; used to distribute the load of a column or wall to the subgrade.



spread footing

spreading rate **1.** The number of square yards of surface covered by a gallon of paint. **2.** The rate at which bitumen or other material is applied to the surface of a roof.

spread-of-flame test A fire test for roof coverings in which a specified flame source is applied to a sample while a specified air stream is directed at the sample. The sample may be mounted horizontally or at an angle, depending on the intended end use of the product.

spreadsheet Large, wide sheet with many columns that is used to tabulate all estimates and sub-bids when putting a bid together.

spring **1.** An elastic body or shape, such as a spirally wound metal coil, that stores energy by distorting and imparts that energy when it returns to its original shape. **2.** The line or surface from which an arch rises.

spring-bolt (cabinet lock) A spring-loaded, beveled bolt that self-latches when a door or drawer is closed.

spring brace Temporary brace used to adjust wood frame walls for straightness and plumb.

spring buffer An assembly containing a spring that is designed to absorb and dissipate kinetic energy, such as that from a descending elevator car or counterweight.

spring clamp Any clamp with pressure exerted by a spring. One variety is used to hold parts during gluing; another is used as a temporary electric connection.


spring hinge

springer (skewback, summer) **1.** The stone from which an arch springs. **2.** The bottom stone of the coping of a gable. **3.** The rib of a groined vault.

spring hinge A hinge with one or more springs mounted in its barrel to return a door to the closed position. The hinge may be single-acting or double-acting for a swing door.


sprinklered

springing line The horizontal line connecting the points from which an arch or arches rise.

sprinklered Said of an area of a building that is protected from fire by an automatic sprinkler system.

sprinkler flow switch A fire sprinkler line sensor that detects water flow and notifies the fire alarm control panel.

sprinkler head

sprinkler head A distribution nozzle used in a fire-protection sprinkler system. The head may be closed by a plug held in place by a heat-sensitive device.

sprocket (cocking piece, sprocket) A wedge-shaped piece of wood attached to the upper side of a rafter at the eave to form a break in the roof line.

spruce-pine-fir (SPF) Canadian woods of similar characteristics that have been grouped for production and marketing. The SPF species have moderate strength, are worked easily, take paint readily, and hold nails well. They are white to pale yellow.

sprung molding A molding that has its interior corner beveled off to better fit a right-angle joint.

spud **1.** A hand tool used to strip bark from logs. **2.** A sharp, narrow bar or spade used for removing gravel and roofing from a built-up roof.


spud vibrator

spud vibrator A vibrator used for consolidating concrete, having a vibrating casing or head that is inserted into freshly placed concrete.

spun concrete Concrete compacted by centrifugal action, such as in the manufacture of pipes and utility poles.

spun lining The smooth bituminous lining in a corrugated metal pipe formed by spinning the pipe around its axis.

spur **1.** An appendage to a supporting member such as a buttress, shore, or prop. **2.** A decorative stone base that makes the transition from a round column to a square or polygonal plinth. **3.** A carpenter's tool with a sharp point used for cutting veneer. **4.** A rock ridge left projecting from a side wall after a blast. **5.** A short length of railroad track; usually parallel to a main track and used for loading, unloading, or storage.

square **1.** A quantity of shingles, shakes, or other roofing or siding materials sufficient to cover 100 square feet when applied in a standard manner; the basic sales units of shingles and shakes.

square edge In context of acoustical tile, a square-edge is not beveled and creates a hairline joint when installed.

square-framed Joinery framing with all angles of stiles, rails, and mountings cut square.

square roof A roof with two sloping surfaces, each at an angle of 45° from the horizontal.

square up To trim a timber or piece of wood, using a plane, so that its cross section is rectangular.

squaring Aligning or constructing an item or assembly so that all angles are 90°.


squeezed joint

squeegee **1.** Window cleaning tool. **2.** Fine gravel installed for grading a floor prior to placement of concrete).

squeezed joint A joint formed by coating surfaces of two pieces with cement and squeezing them together.

squinch A small arch built across an interior corner of a room to support a superimposed load, such as a dome or the spire of a tower.

squint A small oblique opening in an interior wall of a medieval church to allow a view of the high altar from the aisles.

stab To roughen bricks in preparation for a plaster coat.

stability A measure of the ability of a structure to withstand overturning, sliding, buckling, or collapsing.

stabilization Temporary structural and weather protection used to maintain the essential form and structural integrity of the existing property before restoration begins.

stabilizer A substance that makes a solution or suspension more stable, usually keeping particles from precipitating.

stack **1.** A chimney. **2.** A vertical structure containing one or more flues for the discharge of hot gas. **3.** A vertical supply duct in a warm, air-heating system. **4.** Any vertical plumbing pipe, such as soil pipe, waste pipe, vent, or leader pipe. **5.** A collection of vertical plumbing pipes. **6.** A tier of shelves for books. **7.** To place trusses on framed walls where they will be installed.

stack bond (stacked bond) A masonry pattern bond in which all vertical and horizontal joints are continuous and aligned.


stack bond (stacked bond)

stackhead A vertical duct that discharges exhaust air into the atmosphere at high velocity.

stack vent **1.** The extension of a soil or waste stack above the highest horizontal drain or fixture connected to the stack. **2.** A device installed through a built-up roof covering to allow entrapped water vapor to escape from the insulation.

stadia rod (stadia) A graduated surveyor's rod used with a transit or similar instrument to determine distances. An observed intercept on the rod, as defined by two lines in the reticle of a telescope, is converted into the distance between the instrument and the rod by use of similar triangles.

staff bead A thick exterior molding placed between a door or window and a masonry wall.

staff man (rodman) A person who sets the leveling rod for a surveyor in leveling or stadia work.

stage grouting Sequential grouting of a hole in separate steps or stages, in lieu of grouting the entire length at once.

staggered Descriptive of fasteners, joints, or members arranged in two or more rows so that the beginning of each row is offset from the adjacent one.

staggered course A course, of shingles or tiles for instance, where the butts do not form a continuous horizontal line.

staggered riveting Rows of rivets installed in a staggered pattern.

staggered-stud partition A partition made of two rows of studs with alternating studs supporting opposite faces of the partition and each stud making contact with only one wall. Staggered-stud partitions often have an interwoven fiberglass blanket to improve the sound-insulation value of a partition.

staging (scaffolding) **1.** A temporary working platform against or within a building for construction, repairs, or demolition. **2.** A temporary working platform supported by the temporary timbers in a trench.


staging (scaffolding)

stain **1.** Color in a dissolving vehicle. When spread on wood or similar material, the stain penetrates and gives color to the material. **2.** A discoloration in the surface of a material, such as wood or plastic.

stainless steel Any of a number of steels alloyed with chromium and nickel. Depending on the alloy, the metal may possess good corrosion resistance, high heat tolerance, or high strength.

stair **1.** A single step. **2.** A series of steps or flights of steps connected by landings, used for passage from one level to another.

stair carriage or stringer Support framing members for stair treads, usually a 2″ × 12″ notched plank. Also known as a "rough horse."

staircase **1.** A single flight or multiple flights of stairs including supports, frameworks, and handrails. **2.** The structure containing one or more flights of stairs.


staircase

stair headroom The least clear vertical distance measured from a nosing of a tread to an overhead obstruction.

stair landing A level platform installed at the point where stairs change direction, at the top of a flight of stairs, or between flights.

stair rise The height of a stair (vertical distance between treads).

stairwell A vertical shaft enclosing a stair.


stairwell

stake A short, pointed piece of wood or metal driven into the ground as a marker or an anchor.

staking out The process of driving stakes for batter boards to locate the limits of an excavation, or to identify the boundaries of a parcel of land.

stalactite A downward-pointing deposit formed as an accretion of mineral matter produced by evaporation of dripping water from the surface of rock or of concrete; commonly shaped like an icicle.

stalagmite An upward-pointing deposit formed as an accretion of mineral matter produced by evaporation of dripping water, projecting from the surface of rock or concrete, commonly conical in shape.

stamp A seal required on drawings for commercial projects that contains the architect's or engineer's name and registration number. The individual's signature is usually required over the stamp.

stanchion **1.** A vertical post or prop supporting a roof, window, etc. **2.** An upright bar or post, as in a window, screen, or railing.


stanchion

standard **1.** A grade of lumber suitable for general construction and characterized by generally good strength and serviceability. In light framing rules, the standard grade applies to lumber that is 2″ to 4″ thick and 2″ to 4″ wide. It falls between the construction and utility grades. **2.** General recognition and conformity to established practice.

standard absorption trench An absorption trench 12″ to 36″ (30 to 90 cm) wide, containing 12″ (30 cm) of clean, coarse aggregate and a distribution pipe covered with a minimum of 12″ (30 cm) of earth.

standard air Air with a density of 0.075 lb per cu. ft. (0.0012 gm per cc) that is close to air at 68°F (20°C) dry bulb and 50% relative humidity at a barometric pressure of 29.9″ (76 cm) of mercury.

standard and better A mix of lumber grades suitable for general construction. The *and better* signifies that a portion of the lumber is actually of a higher grade than standard (but not necessarily of the highest grade). The proportion of higher grades included is a factor in determining market value.

standard atmosphere A pressure equal to 14.7 lb per sq. in. (1.01 × 10 dynes per sq. cm).

standard brick Brick with the dimensions 2¼″ × 3¾″ × 8″. Standard modular brick measures 2⅔″ × 4″ × 8″.

standard deviation A statistic, used as a measure of dispersion in a distribution, that is equal to the square root of the arithmetic average of the squares of the deviations from the mean.

standard hook A hook at the end of a reinforcing bar made in accordance with a standard.

standard knot Any knot in wood 1½″ (3.8 cm) or less in diameter.

standard matched Tongue-and-groove lumber with the tongue and groove offset, rather than centered as in center-matched lumber.

standard net assignable area The area of a project that can be rented to an occupant.

standard penetration resistance (Proctor penetration resistance) The load required to produce a standard penetration of a standard needle into a soil sample at a standard rate.

standard penetration test A test to estimate the degree of compactness of soil in place by counting the number of blows required to drive a standard sampling spoon 1′ (0.3 m) using a 140-pound (64-kg) weight falling 30″ (0.8 m).

standard sand Ottawa sand accurately graded to pass a U.S. Standard No. 20 (850-micrometer) sieve and be retained on a U.S. Standard No. 30 (600-micrometer) sieve, for use in the testing of cements.

standard temperature and pressure (STP) The standard conditions used to measure properties of matter. Standard temperature is 32°F, 0°C or 273° Kelvin—the freezing point of water. Standard pressure is the pressure exerted by a column of mercury 760 mm high, referred to as 1% atmosphere.

standard tolerance A generally accepted tolerance for a specific product.

standard wire gauge The legal standard wire gauge in Great Britain and Canada.

standby lighting Lighting provided to supply illumination in the event of failure of the lighting system so that normal activities can continue.

standing finish Those items of interior finish that are permanent and fixed, as distinguished from such items as doors and movable windows.

standing leaf An inactive leaf of a double-door bolted in the closed position.

standing seam A seam, in sheet metal and roofing, made by turning up two adjacent edges and folding the upstanding parts over on themselves.



standing seam

standing waste A vertical overflow pipe connected to piping at the bottom of a water tank to control the height of storage.

standpipe **1.** A pipe or tank connected to a water system and used to absorb surges that can occur. **2.** A pipe or tank used to store water for emergency use, such as for fire fighting.

standpipe system A system of tanks, pumps, fire department connections, piping, hose connections, connections to an automatic sprinkler system, and an adequate supply of water used in fire protection.



standpipe system

staple A double-pointed, U-shaped piece of metal used to attach wire mesh, insulation batts, building paper, etc.; usually driven with a staple gun.

staple gun (stapler) A spring-driven gun used to drive staples used for fastening materials such as building paper and batt insulation.

staple hammer A hand tool that holds a magazine of staples and drives a staple when the face strikes a surface.

stapling flange A flange on the edges of a faced insulation batt or blanket that is used to staple the insulation to studwork.

starter **1.** A device used with a ballast to start an electric-discharge lamp. **2.** An electric controller used to accelerate a motor from rest to running speed and to stop the motor.

starter board A 6″ or 8″ board used at the eave of a roof to provide a solid nailing surface for the first courses. A starter board is also used in reroofing to replace the old shingles at the eaves.

starter piece The piece of pipe that starts the branch line. It extends from the cross main or riser nipple to the first head for a fire protection system.

starter strip (starting strip) A strip of composition roofing material applied along the eaves before the first row of shingles is laid.

starting newel The first support post for a handrail at the bottom of a stairway.

starved box A variable air volume box that has a less-than-desired flow despite a fully open damper.

starved joint A poorly bonded glue joint resulting from the use of too little glue.

statement of probable construction cost A cost estimate prepared by the design professional during each of the design phases for the owner's use.

statement of work A written statement describing the procurement of architectural and engineering services, including preliminary or schematic design, design development, and construction document preparation.

static head The static pressure of a fluid expressed as the height of a column of the fluid that the pressure could support.

static pressure **1.** The pressure exerted by a fluid on a surface at rest with respect to the fluid. **2.** The pressure a fan must supply to overcome resistance to airflow in an air distribution system.

statics That branch of mechanics dealing with forces acting on bodies at rest. Statics is the basis of structural engineering.

static test **1.** A test that subjects a curtain wall to a pressure differential equal to a specified wind pressure. **2.** A test that simulates the flow of water over a curtain wall during a hurricane. **3.** A test to determine the pressure exerted by a fluid while the system is at rest.

static transfer switch A device that transfers an electrical load from one AC power source to another without interruption.

static vent A vent that does not have a fan.

station **1.** A point on the Earth's surface that can be determined by surveying. **2.** On a survey traverse, particularly a roadway, every 100′ interval is called a station.

station roof **1.** A roof shaped like an umbrella and supported by a single column. **2.** A long roof supported on a row of columns and cantilevering off one or both sides of the column line.

station yards of haul The product of the number of cubic yards in a haul and the number of 100′ (30.48-m) stations through which it is hauled.

statute A law or enactment of the various federal, state, and local rule-making bodies such as Congress, state legislatures, and local planning and zoning boards.

statute of frauds A statute specifying that certain kinds of contracts, such as for the sale or lease of real property, are unenforceable unless signed and in writing, or unless there is a written memorandum of terms signed by the party to be charged. Statute varies by state.

statute of limitations Provision of law establishing a certain time limit from an occurrence during which a judgment may be sought from a court of law.

statutory bond A bond of which the content and form are established by statute.

statutory requirements Requirements that are embodied in the law.

staunching piece A gap left between adjacent concrete bays until the concrete has cured and shrunk, when it is then filled with more concrete.

stave **1.** A narrow strip of curved wood used in the construction of barrels, buckets, or tanks. **2.** A ladder rung.

stay Anything that stiffens a frame or stabilizes some structural component.



stay

stay bolt A long, metal rod with a threaded end and used as a stay.

stay rod Any rod-shaped tie used temporarily or permanently to prevent spreading of the parts it connects.

steam box An enclosure for steam-curing concrete products.

steam chest A container in which wood is steamed for bending or forming.

steam cleaner A machine that provides pressurized steam to a nozzle for the purpose of cleaning grease or dirt from a surface. Detergents or chemicals are sometimes added.

steam curing Curing of concrete or mortar in water vapor at atmospheric or higher pressures and at temperatures between about 100°F and 420°F (40°C and 215°C).

steam-curing cycle **1.** The time interval between the start of the temperature-rise period and the end of the soaking period or the cooling-off period. **2.** A schedule of the time and temperature of periods that make up the cycle.

steam grid humidifier An air duct humidifier that introduces steam into the air through perforated pipes.

steam hammer A pile hammer activated by steam pressure.

steam heating system A heating system in which heat is transferred from a boiler or other source, through pipes, to a heat exchanger. The steam can be above, at, or below atmospheric pressure.

steaming A process in which logs are heated with steam or hot water in special vats prior to peeling them into veneer. Steaming results in smoother veneer and improved recovery from the log. A similar process is used to prepare wood for bending or shaping.

steam injection In an environmental remediation operation, the process of injecting steam into soil to aid in the extraction of soil vapor or groundwater.

steam pipe Any pipe for the conveyance of steam.

steam stripping **1.** A process of removing volatile contaminants from soil or water by passing steam through the soil or water. **2.** A method of removing wallpaper.

steam traps A device that discharges condensate air and prevents the passage of steam.

steam vat (steam chest) A container used in steaming to soften logs or flitches before peeling or slicing veneers.

steel Any of a number of alloys of iron and carbon, with small amounts of other metals added to achieve special properties. The alloys are generally hard, strong, durable, and malleable.

steel domes 19″ × 19″ or 30″ × 30″ metal forms used in two-way joist construction of cast-in-place concrete slabs.

steel erector A contractor who undertakes to place, plumb, and secure a steel structure.

steel-frame construction Construction in which steel columns, girders, and beams comprise the structural supporting elements.



steel-frame construction

steel inspection An inspection prior to concrete placement to ensure that steel rebar, window bucks, and other components are properly installed in compliance with the approved foundation plan.

steel sheet Cold-formed sheet or strip steel shaped as a structural member for the purpose of carrying the live and dead loads in lightweight concrete roof construction.

steel sheet piling Interlocking rolled-steel sections driven vertically into the ground to serve as sheeting in an excavation or to cut off the flow of groundwater.



steel sheet piling

steel stair fill Concrete that is poured into metal pans to form stair treads and landings.

steel stud anchor A steel clip fastened to a door frame and used to secure the frame to a steel stud.

steel trowel A smooth concrete finish obtained with a steel trowel.



steel trowel

steening Brickwork laid without mortar.

steering brake A brake to slow or stop one side of a tractor.

steering clutch A clutch that can disconnect power from one side of a tractor.

stem bars Bars used in the wall section of a cantilevered retaining wall or in the webs of a box. When a cantilevered retaining wall and its footing are considered as an integral unit, the wall is often referred to as the stem of the unit.


stem bars

stemming A suitable inert, incombustible material, such as rock bits or other packing, or device used to confine or separate explosives in a drill hole, or to cover explosives in mudcapping.

stenciling A decorative painting technique using hand-cut or pre-manufactured cut-out shapes.

step brazing A method of brazing in which filler metals of successively lower brazing temperatures are used to prevent softening of previously brazed joints.

step down transformer An electric transformer with a lower voltage at the secondary winding terminals than at the primary winding terminals.

step joint **1.** A notched joint used to connect two wood members meeting at an angle, such as a tie beam and a rafter. **2.** A joint between two rails with different heights and/or cross sections.

stepped flashing Flashing at the intersection of a sloped roof and a wall or chimney. The upper edge of each sheet is stepped with relation to adjacent sheets to maintain a safe distance from the sloped roof surface.

stepped footing **1.** A wall footing with horizontal steps to accommodate a sloping grade or bearing stratum. **2.** A column or wall footing composed of two or more steps on top of one another to distribute the load.

stepped foundation A foundation constructed in a series of steps that approximate the slope of the bearing stratum. The purpose is to avoid horizontal force vectors that might cause sliding.


stepped foundation

stepping Lumber designed to be used for stair treads. Stepping is vertical-grained and is customarily shipped kiln-dried, surfaced three sides, and bull-nosed on one edge. Besides the "C & Better" and "D" grades of solid wood, stepping is also made from particleboard for use where it will be covered.

stepping off Laying off the required length of a rafter by use of a carpenter's square.

step-plank Any hardwood lumber used to make steps, usually 1¼″ to 2″ (3.2 to 5.1 cm) thick.

step soldering A method of soldering in which solders with successively lower application temperatures are used to prevent the disturbing of previously soldered joints.

step-taper pile A pile formed of straight-sided, thin-walled segments of spirally corrugated steel that, once driven into the ground, are filled with concrete.

step-up transformer An electric device that used to convert a power supply to a higher voltage circuit.

stereobate The foundation, substructure, or platform upon which a building is constructed.

stereo photogrammetry The science of measuring from two photographs taken from known positions in relation to the building or structure. Using known dimensions of parts of the structure, other dimensions can then be determined by scaling.

stereotomy The practice of cutting stone to specified forms and then placing it.

sterling A grade of Idaho white pine boards, equivalent to #2 common in other species.

stick **1.** Any long, slender piece of wood. **2.** A waxed paper cartridge containing an explosive, usually 1$^{1}/_{8}$″ × 8″ (3 × 20 cm). **3.** A rigid bar fastened to the bucket and hinged at the boom of a power shovel or a backhoe.

stick built A term describing frame houses assembled piece-by-piece from lumber delivered to the site with little or no previous assembly into components. The more typical type of residential construction is stick built.


stick built

sticker An additive that increases the strength with which water-soluble materials attach to solid surfaces.

sticky cement Finished cement that develops low or zero flowability during or after storage in silos, or after transportation in bulk containers, hopper-bottom cars, etc. Sticky cement may be caused by: (a) interlocking of particles, (b) mechanical compaction, (c) electrostatic attraction between particles, or (d) moisture.

stiffened compression element A compression element that has been stiffened on its weak axis in order to resist buckling on that axis.

stiffener **1.** A bar, angle, channel, or other shape attached to a metal plate or sheet to increase its resistance to buckling. **2.** Internal reinforcement, usually light-gauge channels, for a hollow metal door.

stiff leg derrick An erection derrick with a vertical mast shorter than its boom. The mast is tied from its peak to a triangular structural frame at its base by rigid steel members.

stiffness Resistance to deformation.

stiffness factor A measure of the stiffness of a structural member. For a prismatic member, the stiffness factor is equal to the ratio of the product of the moment of inertia of the cross section and the modulus of elasticity for the material to the length of the member.

stile **1.** The vertical members forming the outside framework of a door or window. **2.** A roofing tile with an S-shaped cross section.


stile

stilt **1.** A post used to raise a structure above ground or water level. **2.** A compression member placed above or below a similar member to gain additional height.

stinger A slang term for a welding rod.

stipple To make dots or short dashes on a surface as a decorative effect.

stippled finish A dotted or pebbly textured finish on the surface coat of paint, plaster, or porcelain enamel, induced by punching the unset surface with a stiff brush.


stipple

stipulated sum agreement A contractual agreement in which a fixed amount is established for performance of the work.

stirrup **1.** A reinforcement used to resist shear and diagonal tension stresses in a concrete structural member. **2.** A steel bar bent into a U or box shape and installed perpendicular to, or at an angle to the longitudinal reinforcement, and properly anchored. **3.** Lateral reinforcement formed of individual units, open or closed, or of continuously wound reinforcement. The term *stirrups* is usually applied to lateral reinforcement in flexural members and the term *ties* to lateral reinforcement in vertical compression members.

stitched veneer Veneer sheets composed of random width pieces of veneer sewn together with heavy thread. Several stitch lines run across the width of each piece of stitched veneer. In veneer production, the random width pieces are run through a large sewing machine and reclipped in desired (usually standard 48″ to 54″) sizes. Stitched veneer is usually used in the core plies of plywood.

stitch rivet One of a number of rivets installed at regular intervals and in a straight line to connect two parts and provide lateral stiffness.

stitch welding The union of two or more parts with a line of short, equally spaced welds.

stock **1.** Material or devices readily available from suppliers. **2.** The body or handle of a tool. **3.** A frame to hold a die when cutting external threads on a pipe. **4.** The total value of the equity in a corporation.

stock brush A brush used to apply water to base coat or finish coat plaster to improve workability.

stock lumber Lumber cut to standard sizes and readily available from suppliers.

stock millwork Millwork manufactured in standard shapes and sizes and readily available from suppliers.

stockpile Material stored for later use, such as topsoil.

stock size A standard size of an item that is readily available from suppliers.

stoichiometric combustion A controlled combustion where fuel is reacted with the exact amount of oxygen required to oxidize all carbon, hydrogen, and sulfur in the fuel to carbon dioxide, water, and sulfur dioxide.

stone **1.** Individual blocks of rock processed by shaping, cutting, or sizing. For use in masonry work. **2.** Fragments of rock excavated, usually by blasting, from natural deposits and further processed by recrushing and sizing. For use as aggregate. **3.** A carborundum or other natural or artificial hone used to sharpen cutting edges of tools.



stone

stone dust Pulverized stone used in the construction of walkways or other stable surfaces. The dust is mixed with soil and compacted or used with gravel to fill spaces between irregular stones. Stone dust is a byproduct of stone-crushing operations.

stonemason A craftsman skilled in constructing stonemasonry, including any preparation at the site.

stone sand Fine aggregate resulting from the mechanical crushing and processing of rock.

stone seal An asphaltic wearing surface made by rolling aggregate into a heavy application of bituminous material. Application is usually repeated several times.

stone veneer, thin Stone cut 2″ thick or less and applied to an interior or exterior building surface in a non-load-bearing manner. Granite, marble, limestone, slate and travertine are most commonly used.

stonework **1.** Masonry construction using stone. **2.** The preparation or setting of stone for building or paving.



stonework

stool **1.** A narrow interior shelf, across the lower part of a window opening, that butts against the sill. **2.** A framed support. **3.** A toilet.



stool

stool cap The molding that sits on the windowsill and extends into a room to form a kind of shelf.

stop **1.** On doors, the molding on the inside of the doorjamb that causes the door to stop in its closed position, preventing it from swinging through. On windows, the molding that covers the inside face of the jamb. **2.** A type of molding nailed to the face of a door frame to prevent the door from swinging through. A stop is also used to hold the bottom sash of a double-hung window in place. **3.** A valve used to shut off water supply to a fixture.

stop-and-waste cock A stopcock with a drain plug in the valve. When the valve is closed, water in the downstream piping can be drained through the plug. A stop-and-waste cock is often used at connections to outdoor faucets so the exterior piping can be drained for the winter.

stop box A cast-iron pipe installed vertically underground and covered with a lid. It provides access (with a tool on a pole) to a water cut-off valve for the home.

stopcock A valve to shut off the flow of fluid in a branch of a distribution system in a building.

stop glazing Either the lip at the back of a rabbet or the molding applied at the front. These serve to hold a light in a sash or frame with the help of spacers.

stopped miter A miter joint used with members of different thickness.

stop valve Any valve in a piping distribution system that is used to stop flow.

stop work order or stop order An order issued by the owner's representative to stop work on a project. Reasons for the order include failure to conform to specifications, unsatisfied liens, labor disputes, and inclement weather.

storage life (shelf life) The length of time that a product, such as a package adhesive or sealant, can be stored at a specified temperature range and remain usable.

storefront sash An assembly of light metal members that form a frame for a fixed-glass storefront.

storm clip A clip on the exterior of a glazing bar that holds the pane in place.



storefront sash

storm drain A drain used to convey rain water, subsurface water, condensate, or similar discharge, but not sewage or industrial waste.

storm sewer A sewer used for conveying rainwater and/or similar discharges, but not sewage or industrial waste, to a point of disposal.



storm drain

story That part of a building between the upper surface of a floor and the upper surface of the floor above. Building codes differ in designations applied when a part of a story is below grade

story-and-a-half The designation of a building in which the second story rooms have low headroom at the eaves.

story pole A pole used to gauge height (in stories) during masonry construction.



story-and-a-half

story post An upright post that helps support a beam on which a floor rests.

story rod A wooden rod of a length equal to one story height, sometimes divided in parts each equal to one riser in a stair, for use in stair construction.

straightedge (rod) A rigid, straight piece of wood or metal used to strike off or screed a concrete surface to proper grade, or to check the flatness of a finished grade.

straight grain A piece of wood in which the principal grains run parallel to its length.

straight joint **1.** A continuous joint in a wood floor formed by the butt ends of parallel boards. **2.** An edge joint between two parallel timbers. **3.** Vertical joints in masonry that form a continuous straight line.

straight-joint tile A term describing single-lap tiles designed to be laid so that the edges of each course run in a straight line from eave to ridge.

straight-line theory An assumption in reinforced-concrete analysis according to which the strains and stresses in a member under flexure vary in proportion to the distance from the neutral axis.

S

strain Deformation of a material resulting from external loading. The measurement for strain is the change in length per unit of length.

strain gauge A sensitive electrical or mechanical instrument used to measure strain in loaded members or objects, usually for research or development.

straining beam (straining piece, strutting piece) **1.** A horizontal strut in a truss, placed above the tie beam or the bottom of the rafters, usually mid-height. **2.** The chord between the upper ends of the posts in a queen post truss.

strake A single row of clapboard siding.

strand A prestressing tendon composed of a number of wires twisted about a center wire or core.

stranded wire A group of fine wires used as a single electric conductor.



stranded wire

S-trap An S-shaped trap that provides a water seal in a waste or soil pipe. Used most commonly at sinks and lavatories.

strap A metal plate fastened across the intersection of two or more timbers.

strap bolt A bolt in which the middle portion of its shank is flattened, so the unit can be bent in a U-shape.

straphanger A hanger made from a thin, narrow strip of material.



S-trap

strap wrench A hand tool with a flexible, adjustable strap that is used to tighten or remove irregularly shaped connectors, pipes, or fittings.

stratification **1.** The separation of overwet or overvibrated concrete into horizontal layers with increasingly lighter material toward the top. Water, laitance, mortar, and coarse aggregate will tend to occupy successively lower positions in that order. **2.** A layered structure in concrete resulting from placing of successive batches that differ in appearance. **3.** The occurrence in aggregate stockpiles of layers of differing grading or composition.

stratified rock Rock that has been formed by compaction, cementation, or crystallization of successive beds of deposited material.

stratum A bed or layer of rock or soil.

straw bale A low-embodied-energy farming by-product that can be used to build highly insulated (R-50), fire- and termite-resistant walls. Paired with stucco exterior and drywall interior, straw bale is a plentiful green construction alternative to lumber.

streamline flow Fluid flow in which the velocity at every point is equal in magnitude and direction.

street elbow (service ell, street ell) A pipe elbow with male threads on one end and female threads on the other.

street floor That floor of a building nearest to street level. According to some building codes, the street floor is a floor level not more than 21″ above or 12″ below grade level at the main entrance.

street lighting luminaire A complete lighting unit intended to be set on a pole or post with a bracket.

strength design method (ultimate strength method) A design method in which service loads are increased sufficiently by factors, often referred to as load factors, to obtain the ultimate design load. The structure or structural element is then proportioned to provide the desired ultimate strength.



street lighting luminaire

stress Intensity of internal force (i.e., force per unit area) exerted by either of two adjacent parts of a body on the other across an imagined plane of separation. When the forces are parallel to the plane, the stress is called *shear stress;* when the forces are normal to the plane, the stress is called *normal stress;* when the normal stress is directed toward the part on which it acts it is called *compressive stress;* when it is directed away from the part on which it acts it is called *tensile stress.*

stress corrosion cracking Cracking of metal that occurs under the combined influence of certain corrosive environments and applied or residual stresses.

stress crack An external or internal crack in a plastic as a result of applied tensile stresses.

stressed-skin construction Construction in which a thin material on the surface of a building is used to carry loads.

stressed-skin panel A panel assembled by fastening plywood or similar sheets over a frame or core, on both sides. The result is a composite structural member.

stress-graded lumber Lumber graded for strength according to the rate of growth, slope of grain, and the number of knots, shakes, and other defects.

stressing end In prestressed concrete, the end of the tendon from which the load is applied when tendons are stressed from one end only.

stress relaxation Stress loss developed from strain when a constant length is maintained under stress.


stressing end

stress-relief heat treatment A process used to relieve residual stresses that involves the uniform heating of a material or structure to a high temperature.

stress-strain diagram A diagram for a particular material with values of stress plotted against corresponding values of strain, usually with stress plotted as the ordinate.

stretcher A masonry unit laid with its length parallel with the face of the wall.

stretcher bond (running bond, stretching bond) A masonry bond with all courses laid as stretchers and with the vertical joint of one course falling midway between the joints of the courses above and below.

striated Having parallel grooves in the face, as in a fluted column.


stretcher bond (running bond, stretching bond)

striated face The face of a plywood panel that has been given closely spaced, shallow grooves to provide a vertical pattern.


striated face

strike **1.** In masonry, to cut off the excess mortar at the face of a joint with a trowel stroke. **2.** To remove formwork. **3.** A work stoppage by a body of workers. **4.** A metal plate installed on a door frame where a latch or dead bolt engages.

strike breaker One who takes the place of a worker who has gone on strike.

strike off (strikeoff) To remove concrete in excess of that which is required to fill the form evenly or bring the surface to grade, performed with a straightedged piece of wood or metal by means of a forward sawing movement or by a power-operated tool appropriate for this purpose.

strike plate (strike, striking plate) A plate or box, mounted in a jamb, with a hole or recess shaped to receive and hold a bolt or latch from a lock on the door.

striker A slightly beveled metal plate attached to a strike plate to guide a door latch to its socket.

strike reinforcement A metal piece welded inside a hollow metal frame to which the strike plate is attached and which also serves to strengthen the frame.

striking The removal of temporary supports from a structure.


strike plate (strike, striking plate)

stringcourse (belt course) A horizontal band of masonry, usually narrower than the other courses, which may be flush or projecting, and plain or ornamented.

stringer or string **1.** A secondary flexural member parallel to the longitudinal axis of a bridge or other structure. **2.** A horizontal timber used to support joists or other cross members in floors or ceilings. **3.** In stairs, the framing member that supports the treads.

stringer bead A continuous bead of weld metal made by moving the electrode in a direction parallel to the bead without much transverse oscillation.

strip **1.** Board lumber 1″ in nominal thickness and less than 4″ in width, frequently the product of ripping a wider piece of lumber. The most common sizes are 1″ × 2″ and 1″ × 3″. **2.** To remove formwork or molds. **3.** To remove an old finish with paint removers. **4.** To damage the threads on a nut or bolt.

strip core (blackboard) A composite board whose core is made of strips of wood, laid loose or glued together. Veneer is glued to both sides of the core with its grain at right angles to the grain of the core pieces.

strip flooring Flooring made of wood strips that are pieced together in a tongue-and-groove assembly.

strip mopping A method of applying hot bitumen to a roof deck in parallel strips.

stripper **1.** A liquid compound formulated to remove coatings by chemical and/or solvent action. **2.** A drywall tool with a serrated wheel for cutting wallboard.

stripping felt A narrow strip of roofing felt used to cover a flange of metal flashing.

stripping shovel A mobile power shovel with a long boom for ditching and removal of bulk material.

strip pouring A quick and economical way to place concrete slabs, allowing for a continuous pour with control points cut after the concrete has set.

stroke **1.** A run of clapboard on the side of a house. **2.** A row of steel plates in a steel chimney.

strongback A frame attached to the back of a form to stiffen or reinforce it during concrete placing or handling operations.

struck joint A masonry joint in which excess mortar is removed by a stroke of a trowel.


strongback

struck tools Tools that perform work by placing the sharp end (called the *working* end) of the tool on a surface and striking the other end (the *struck* end) with a hammer. The working end of a struck tool must be kept sharp. The face on the struck end must be kept smooth and even to prevent off-center blows. Examples of struck tools include chisels, punches, and wedges.

structural A term applied to those members in a structure that carry an imposed load in addition to their own weight.

structural analysis The determination of stresses in members in a structure due to imposed loads from gravity, wind, earthquake, thermal effects, etc.

structural clay facing tile A structural clay tile with a finished ceramic face.

structural clay tile A hollow masonry unit molded from clay, shale, fireclay, or a mixture of such materials.

structural drawings Graphic representations of the members, assemblies, and systems that will transmit live and dead loads of the structure to the earth.


structural clay tile

structural engineering That branch of engineering concerned with the design of the load-supporting members of a structure.

structural failure **1.** The inability of a structure or structural member to perform its intended function, perhaps caused by collapse or excessive deformation. **2.** A marked increase in strain without an increase in load.

structural frame All the members of a building or other structure used to transfer imposed loads to the ground.

structural glued-laminated timber A wooden structural member made from selected boards strongly glued together.


structural glued-laminated timber

structural insulated panel (SIP) A rigid panel, often constructed of polyurethane foam insulation between a facing material such as foil or oriented strand board, that exhibits both strength and thermal insulating properties.

structural joists and planks Lumber 2″, 3″, or 4″ thick and 6″ or wider, graded for its strength properties. Such planks are used primarily for joists in residential construction and graded, in descending order, select structural, #1, #2, and #3. The #1 and #2 grades are usually marketed in combination as #2 & Better.

structural light framing A category of dimension lumber up to 4″ in width that provides higher bending strength ratios for use in engineered applications, such as roof trusses. The lumber is often referred to by its fiber strength class, such as 175f for #1 & Better Douglas Fir, or as stress-rated stock.

structural lumber Any lumber with nominal dimensions of 2″ or more in thickness and 4″ or more in width and that is intended for use where working stresses are required. The working stress is based on the strength of the piece and the use for which it is intended, such as beams, stringers, joists, planks, posts, and girders.

structural plate With reference to drainage structures, heavily corrugated steel plate, usually curved, that are bolted together to form large pipes, arches, and other drainage structures.

structural shape A hot-rolled or cold-formed steel member of standardized cross section and strength, generally used in a structural frame. Common structural shapes are angle irons, channels, tees, H-sections, and wide flange beams.

structural steel Steel rolled in a variety of shapes and manufactured for use as load-bearing structural members.

structural steel fastener Any fastener used to connect structural steel members to each other, or to supporting elements, or with concrete to make a composite section.

structural tee **1.** A structural shape made by cutting a wide-flange beam or I-beam in half. **2.** A hot-rolled steel member shaped like the letter T.

structural timber Structural lumber with a nominal dimension of 5″ or more on each side, used mainly as posts or columns.

structural veneer Veneers used in the construction of structural plywood panels, as opposed to decorative veneers.


stuctural steel

structure A combination of units fabricated and interconnected in accordance with a design and intended to support vertical and horizontal loads.

structure-borne sound Sound energy imparted directly to and transmitted by the elements of a structure. Plumbing noises traveling through pipes are a good example.

structured cabling system (SCS) A cabling system that supports several applications, such as video, voice, data, and building automation systems functions, reducing the overall cost and space required for cabling.

structure height The vertical distance from grade to the top of the structure.

stub A short projecting element.

stub mortise A mortise that does not project entirely through the piece in which it is cut.

stub tenon A short tenon cut to fit a stub mortise.

stub wall A low wall, usually 4″ to 8″ (100 mm to 200 mm) high, placed monolithically with a concrete floor or other members to provide for control and attachment of wall forms.

stucco A cement plaster used to cover exterior wall surfaces; usually applied over a wood or metal lath base.


stucco

stud **1.** A vertical member of appropriate size (2″ × 4″ to 4″ × 10″) (or 50 mm × 100 mm to 100 mm × 250 mm) and spacing (16″ to 30″) (or 400 mm to 750 mm) to support sheathing or concrete forms. **2.** A framing member, usually cut to a precise length at the mill, designed to be used in framing building walls with little or no trimming before it is set in place. Studs are most often 2″ × 4″, but 2″ × 3″, 2″ × 6″ and other sizes are also included in the stud category. Studs may be of wood, steel, or composite material. **3.** A bolt having one end firmly anchored.

stud anchor A floor anchor for studs in a wall.

stud bolt A bolt firmly anchored in, and projecting from, a structure, such as a concrete pad; used to secure another member, as in bolting a sill plate to concrete.



stud bolt

stud crimper A hand tool used to speed metal stud construction. The crimper joins vertical studs to horizontal runners with a piercing action.

stud driver A device for driving a hardened steel fastener into concrete or other hard material, consisting of a hand-held driver that positions the fastener. A blow on the head of the driver forces the fastener into the material.

stud grade A grade of framing lumber under the National Grading Rule established by the American Lumber Standards Committee. Lumber of this grade has strength and stiffness values that make it suitable for use as a vertical member of a wall, including use in load-bearing walls.

stud gun A powered stud driver.

stud opening A rough opening in wood framing.

stud partition A partition in which studs are used as the structural base. Wallboard is usually applied over the studs.



stud partition

stud shoe A metal bracket used as reinforcing for a vertical stud.

stud welding Attaching a special metal shear stud into a steel member by resistance welding. A special gun is used to hold the stud and provide electric current for the welding process. Shear studs are used for composite construction in which steel and concrete form a composite beam.

study **1.** A preliminary sketch. **2.** The programming phase of facility planning that precedes building design.

stuff Sawn timber.

styrene butadiene rubber (SBR) or SB latex A synthetic rubber material widely used for applications including wiring insulation and for conventional carpet backing. SBR contains potentially toxic chemicals.

Styrofoam® The brand name of a lightweight extruded polystyrene product noted for its excellent thermal insulation performance.

sub Contraction of subcontractor.

subbase **1.** A layer in a pavement system between the subgrade and base course or between the subgrade and the concrete pavement. **2.** The bottom front strip or molding of a baseboard.



subbase

subbasement **1.** A level, or levels, of a building below the basement. **2.** A story immediately below a basement.

subbid A bid offered by a subcontractor.

subbidder (subbidder) A person or entity who has a direct contract with the contractor for a portion of the work at the site.

subcontract An agreement between a prime contractor and a contractor (specializing in a particular trade) for the completion of a portion of the work for which the prime contractor is responsible.

subcontractor One under contract to a prime contractor by subcontract for completion of a portion of the work for which the prime contractor is responsible.

subcooling Cooling a refrigerant below its saturated condensing temperature.

subdrain A pipe with perforations or open joints that has been buried in a trench backfilled with pervious soil for the purpose of intercepting groundwater or seepage.

subfeeder An electric feeder that originates at a distribution center other than the main distribution centers and supplies one or more branch-circuit distribution centers.

subfloor (blind floor, counterfloor) A rough floor laid on floor joists and serving as a base for the finish floor. A subfloor may also be used as a structural diaphragm to resist lateral loads.



subfloor (blind floor, counterfloor)

subflooring Plywood sheets or construction grade lumber used to construct a subfloor.

subflorescence Salt crystallization inside masonry units, which can cause damage to the units' internal structure. It may occur when the mortar surrounding the masonry units has a lower rate of permeability than the units themselves.

subframe (rough buck, subbuck) **1.** A structural frame of wood members or channel-shaped metal members that support the finish frame of a door or window. **2.** A framework supporting wall siding or panels.

subgrade **1.** The soil prepared and compacted to support a structure or a pavement system. **2.** The elevation of the bottom of a trench in which a sewer or pipeline is laid.

submetering Measuring utilities used by individual tenants in a building.

submittal A sample, manufacturer's data, shop drawing, or other such item submitted to the owner or the design professional by the contractor for the purpose of approval or other action, usually a requirement of the contract documents.

submit the bid Deliver a bid to a sponsor.

sub-purlin (subpurlin) A light structural section used as a secondary structural member, and used in lightweight concrete roof construction to support the formboards over which the lightweight concrete is placed.



sub-purlin

subrail A component of a stair rail system that runs down the stairs from the top of the string and upon which the balusters are mounted.

subsealing The placing of a waterproofing material under an existing pavement to waterproof the pavement and to fill voids in the subsoil.

subsidence Settlement over a large area as opposed to settlement of a single structure.

subsill **1.** An additional sill fitted to the outside of a window as a stop for screens and to increase the shedding distance. **2.** A rough doorsill fixed to the groundsill.

subsoil The bed or stratum of soil lying immediately below the surface soil and which is usually devoid of humus or organic matter.

subsoil drain A drain installed to collect subsurface or seepage water and convey it to a point of disposal.

substantial completion The condition of the work when the project is substantially complete, and ready for owner acceptance and occupancy. Any items remaining to be completed should, at this point, be duly noted or stipulated in writing.

substantial performance A party's performance of most of its contractual obligations, which entitles it to payment of at least a portion of the contract price and precludes a termination for default.

substation An assembly of equipment, including switches, circuit breakers, buses, and transformers, for switching power from one voltage or system to another.

substitution A product, material, or piece of equipment offered in place of that specified.

S



substructure

substrate An underlying material that supports or is bonded to another material on its surface.

substrate failure A surface failure in a concrete wall at a joint, caused by a sealant of high tensile strength that tears weak concrete or mortar from the face of the joint.

substructure The foundation of a building that supports the superstructure.

subsurface contamination The presence of hazardous materials in the soil or groundwater under a site.

subsurface investigation (geotechnical investigation) The sampling and laboratory testing process (including soil borings) to establish subsurface profiles, relative strengths, compressibility, and other characteristics of strata deep enough to affect project design.

subsurface sand filter A sewage filtering system consisting of a number of lines of perforated pipe or drain tile surrounded by coarse aggregate, an intermediate layer of sand as filtering material, and a system of underdrains to carry off the filtered liquid.

subsurface sewage disposal system A system for treating and disposing of domestic sewage, usually from a single residence, by means of a septic tank and a soil absorption system.

successful bid A bid that is accepted by a sponsor for award of contract; a low bid (assuming that there will be an award of contract).

suction **1.** The absorption of water from a plaster finish coat by the base coat, gypsum block, or gypsum lath, functioning to increase bond and promote better adhesion to the base. **2.** The adhesion of mortar to brick. **3.** A vacuum effect created when wind load on a building creates a load in an outward direction.

suction pump A pump that draws water from a reservoir at a level lower than the pump, or from a pipe operating at a lower hydraulic gradient than the pump.

sulfate attack A chemical and/or physical reaction between sulfates usually in soil or groundwater and concrete or mortar, primarily with calcium aluminate hydrates in the cement-paste matrix, often causing deterioration.

sulfate resistance The ability of concrete or mortar to withstand sulfate attack.

sulfur cement A cement of clay or a similar substance, usually with additives such as sulfur, metallic oxides, silica, or carbon used for sealing joints and coatings in high-temperature areas such as furnace fire boxes.

summer **1.** A horizontal beam supporting floor joists or a wall of a superstructure. **2.** Any heavy timber that serves as a bearing surface. **3.** A lintel of a door or window. **4.** A stone set on a column as a support for construction above, such as a base for a column-supported arch.

sump **1.** A pit, tank, or basin that receives sewage, liquid waste, seepage, or overflow water and is located below the normal grade of the disposal system. A sump must be emptied by mechanical means. **2.** A depression in a roof deck at a drain.

sump pump A small pump used to remove accumulated waste or liquid from a sump.

sun-bearing angle, or relative solar azimuth Used in solar analysis and design, the solar azimuth angle relative to the direction a building surface faces.

sunken joint A small, narrow depression on the face of a piece of plywood. Sunken joints occur over joint gaps in the core plies of plywood.

sunk fillet A fillet formed by a groove in a flat surface.

sun shade Feature on the exterior of a building that provides shade.

sunspace Interior building space where temperatures are permitted to vary beyond a limited range of "comfort" conditions. When the mass overheats with warmth from the sun, the additional stored energy is retrained to help warm the building when outdoor temperatures cool off.

sun-tempered buildings Buildings designed using standard construction methods, but oriented optimally on the site and featuring carefully designed windows to reduce heating load.

super Contraction of superintendent.

superabsorbent materials Materials, often granular, that absorb liquid several times their own weight. An example is humus, which maintains moisture in soil.

superheated steam Steam at a temperature higher than the saturation temperature corresponding to the pressure.

superheaters Devices that add heat to saturated fluids.

superimposed drainage **1.** A natural drainage system developed by erosion and having little relation to the area's geological structure. **2.** A man-made drainage system developed against the existing geological structure.

superintendent The contractor's representative who is responsible for field supervision, coordination, completion of the work, and the prevention of accidents.

superplasticizer Concrete admixture that adds to the concrete's workability despite low water-cement ratio.

superstructure **1.** The part of a building or other structure above the foundation. **2.** The part of a bridge above the beam seats or the spring line of an arch.

supervision Direction of work performed by the contractor's (or others) workers on site, as specifically defined by the contract.

supervisory control and data acquisition (SCADA system) A computer system used in industry to monitor and control facility operations and status. The automation capabilities of a SCADA system provide early detection of developing problems and improve efficiency in acquiring data and generating reports.

supplemental agreement A change to an existing contract accomplished by the mutual action of the parties.

supplemental authorization A written agreement that authorizes a modification to a service contract.

supplemental general conditions Written modifications to the general conditions that become part of the contract documents.

supplemental instructions to bidders Written modifications to the instructions to bidders that become part of the bidding requirements.

supplemental services Services described in the schedule of designated services that are outside the normal range of services, including renderings, energy studies, value analyses, project promotion, and expert testimony.

supplied air respirator (SAR) A breathing apparatus, connected by a long air hose either to a source of compressed air or to an air pump.

supplier A person or entity who supplies materials or equipment from off the site for the work, including specially fabricated work.

supply air The conditioned air delivered to a space or spaces.

supply air outlets Air terminals (such as grilles and diffusers) for the discharge of supply air.

supply fixture unit A measure of the probable demand on a water supply by a particular type of plumbing fixture. The value depends on the volume of water supplied, the average duration of a single use, and the number of uses per unit time.

supply grille A grille through which conditioned air is delivered to a space.



supply grille

supply line In a hot water heating system, the pipe that carries water from the water heater to individual heating units.

supply mains **1.** The pipes that bring water, gas, or other elements into a building. **2.** The pipes through which the heating or cooling fluid flows from the source of heating or cooling to the laterals or risers leading to heating or cooling units.

supply system The connected ducts, plenums, and fittings through which conditioned air is transferred from a heat exchanger to the space or spaces to be conditioned.

supreme A grade in Idaho white pine equivalent to B & Better 1&2 clear, the highest grade of select lumber.

surcharge load A force or combination of charges acting on the upper level of a retaining wall.



supply system

surety An individual or company that provides a bond or pledge to guarantee that another individual or company will perform in accordance with the terms of an agreement or contract.

surety bond A bond or pledge made by an individual or company that guarantees another individual's or company's performance according to a contract's terms.

surface-active agent An additive to a concrete mix to reduce the surface tension of the mixing water and facilitate wetting, penetrating, emulsifying, dispersing, solubilizing, foaming, and frothing of other additives.

surface bonding A method of bonding masonry that involves first laying masonry units with no mortar or cement between the blocks, and then coating the surface with a fiber-reinforced mortar.

surface burning characteristic A rating of interior and surface finish material providing indexes for flame spread and smoke developed.

surface course The top course of asphalt pavement; the wearing course.

surface drain A drain that eliminates water that pools around the foundation of a home. Also referred to as a superficial peripheral drain, it consists of a trench sloped away from the foundation, lined with plastic and filled with crushed rock.

surfaced sizes Sized lumber may be rough, surfaced, or partly surfaced on one or more faces.

surface hinge A hinge, often ornamental, mounted on a face of a door rather than the edge.

surface impoundment A lagoon or pond designed to hold waste materials and prevent their escape to the environment.



surface hinge

surface metal raceway Any surface-mounted furrow or channel constructed of metal to house and protect electrical conductors.

surface moisture (free water, surface water) Free water retained on surfaces of aggregate particles and considered to be part of the mixing water in concrete, as distinguished from absorbed moisture.



surface metal raceway

surface planer A machine used to plane and smooth the surface of materials such as wood, stone, or metal.

surface retarder A retarder applied to a form, or to the surface of freshly mixed concrete to delay setting of the cement in order to facilitate construction joint cleanup or to facilitate production of exposed aggregate finish.

surface tension That property, due to molecular forces, in the surface film of all liquids that tends to prevent the liquid from spreading.

surface vibrator A vibrator used for consolidating concrete by application to the top surface of a mass of freshly mixed concrete.

surface voids Cavities visible on the surface of a solid.

surface wiring switch An electric switch intended for mounting on a surface, such as a wall post, with most of the body of the switch exposed.

surfacing weld A deposit of weld metal on the surface of a material to provide desired dimensions or properties.

surfactant Chemicals that change the properties of surfaces with which they come in contact. In construction, surfactants are used as wetting or spreading agents and to facilitate the mixture of normally incompatible substances. They also affect the emulsification characteristics and alter the behavior (the dispersion, suspension, or precipitation) of pesticides in water. In environmental remediation, a surfactant is used to solubilize contaminants and mobilize the highly contaminated fines material.

surge A transient voltage effect that causes a sudden, undesirable rise or fall in current.

surge arrester A protective electrical device used to absorb overvoltage surges so that circuitry and equipment are not damaged.

surge pile or bin Stored aggregate or asphaltic concrete awaiting later use.

surge tank A tank in a water supply system used to absorb water during a sharp pressure rise or to supply water in a sudden pressure drop.

survey **1.** A topographic or boundary mapping of a job site. **2.** Taking measurements of an existing building. **3.** The examination of the physical or chemical characteristics of the site.

surveying The measurement of distances, elevations, or angles of the earth's surface, including natural and man-made features; usually for the preparation of a plan or map.

surveyor An engineer or technician skilled in surveying.

survey stakes Small pieces of wood, usually 1″ × 2″ or 2″ × 2″ that have been cut and pointed for driving into the ground to mark a survey line or some boundary of construction.

survey traverse A sequence of lengths and angles between points on the earth established and measured by a surveyor. A survey traverse is used as a reference in making a detailed survey.

suspended acoustical ceiling A ceiling designed to be sound absorbent and to be hung from the structural slab or beams in an area.



suspended acoustical ceiling

suspended ceiling (dropped ceiling) A finished ceiling suspended from a framework below the structural framework.



suspended ceiling (dropped ceiling)

suspended metal lath A system in which metal lath is attached to a light framing system that, in turn, is hung from a structural slab or beam.

suspended span A span supported by two cantilevers or a cantilever and a column or pier, used mainly in bridges and some roofs.

suspended-type furnace A unit furnace designed to be suspended from a floor or roof and to supply heated air through ducts to areas other than that in which the furnace is located.

suspension bridge A bridge with a deck suspended from cables that are typically raised on towers.



suspension bridge

suspension of work A situation in which the contractor must stop performance of the contract work.

suspension roof A roof system supported by cables attached to a frame.

sustainable design Selecting technologies and materials and using them in a manner that avoids depleting natural resources. Considers material durability and sustainability, which involves not only the energy and environmental costs to replace the materials, but availability and rate of regeneration.

swage **1.** A tool or die used to bend or form cold metal. **2.** A tool used to set the teeth of a saw by bending each one to the proper transverse angle.



swage

swale **1.** A shallow depression, in a flat area of land, that may be artificial and used in a storm water drainage system. **2.** A low tract of land, usually marshy.

swan-neck **1.** The connector between a gutter outlet and the downspout. **2.** The curved portion of the handrail of a stair connecting the rail to a newel post.

swaybrace A diagonal brace used to resist wind or other lateral forces.

sweating **1.** A soldering technique for joining metal parts. **2.** A gloss that develops on a dull, or matte, paint or varnish film and is caused by rubbing the dry film. **3.** A collection of condensation moisture on a surface that is below the dew point of the air.

sweat joints In plumbing, the union of two copper pipes made by coating the pipes with a tin-based solder, fitting them together, and applying heat to the joint, fusing the pipes together.

swedge bolt An anchor bolt used in concrete or mortar.

sweep **1.** The curvature or bend in a log, pole, or piling; classified as a defect. **2.** A bend in an electrical conduit.

sweep fitting Any plumbing fitting with a large radius curve.



sweep fitting

sweep strip A flexible weather-stripping used on the top and bottom edges of a revolving door.

swell factor The ratio of the volume of loose excavation material to the volume of the same material in place.

swelling A volume increase caused by wetting and/or chemical changes.

swift A reel or turntable on which prestressing tendons are placed to facilitate handling and placing.

swing **1.** The movement of a door on hinges on a pivot. **2.** The rotation of a power shovel on its base.

swing check valve A check valve with a hinged gate to permit fluid to flow in one direction only; used mostly where fluid velocities are low.



swing check valve

swinging latch bolt A latch bolt hinged to a lock or door and operated by swinging rather than sliding.

swinging scaffold A scaffold suspended from a roof by hooks, and a block and tackle.

swing leaf **1.** The active leaf in a double door. **2.** A hinged sash in a casement window.



swinging scaffold

swing saw (pendulum saw) A power saw for ripping, deep cutting, or cross cutting that is mounted on a frame and pushed down into the material to be cut.

swing-up garage door A rigid overhead door that opens as one unit.

swirl finish (sweat finish) A nonskid texture imparted to a concrete surface during final troweling by keeping the trowel flat and using a rotary motion.

switch A device used to open, close, or change the connection of an electric circuit.

switch-and-receptacle An electrical outlet controlled by its own on-off switch. When the switch is turned off, the flow of electricity to the plug is terminated.

switchboard A large panel, frame, or assembly with switches, overcurrent and other protective devices, fuses, and instruments mounted on the face and/or back. Switchboards are usually accessible from front or rear and are not intended to be mounted in cabinets.



switchboard

switchgear Any switching and interrupting devices combined with associated control, regulating, metering, and protective devices, used primarily in connection with the generation, transmission, distribution, and conversion of electric power.



switchgear

switch plate A flush plate used to cover an electric switch.

swivel joint A special pipe fitting designed to be pressure-tight under continuous or intermittent movement of the equipment to which it is connected.

swivel spindle A spindle in a door latch unit with a joint in the middle of its length to allow one knob to be fixed by a stop; works while the other knob operates the latch.

synchronous motor A constant-speed electric motor, usually direct current. The operational speed is equal to the frequency of supply voltage divided by one-half the number of cycles or windings on the machine.

syneresis The contraction of a gel, usually evidenced by the separation from the gel of small amounts of liquid; a process possibly significant in the bleeding and cracking of fresh Portland cement mixtures.

synergy Interaction of substances, materials or systems that produces effects or results not caused by any of the individual substances or entities on its own.

synthetic gypsum A chemical product consisting primarily of calcium sulfate dehydrate derived primarily from an industrial process.

synthetic resin Any of a large number of products similar to natural resins and made either by polymerization or condensation or modifying a natural material.

synthetic rubber A chemically manufactured elastomer, rubber-like in its degree of elasticity.

system effect factor A pressure loss factor that recognizes the effect of fan inlet and outlet restrictions that influence fan performance.

Système International D'unités or International System of Units The contemporary metric system of international standard measures.

systems A process of combining prefabricated assemblies, components, and parts into single assembled units utilizing industrialized production, assembly, and other methods.

T

Abbreviations

t temperature, time, ton

T tee, township, true, thermostat

Ta tantalum

TAD thoroughly air dried

TAT turnaround time

tb turnbuckle

TB through bolt

TBE threaded both ends

TBR timber

T&C threaded and coupled

TC terra-cotta

TCE trichloroethylene

TCLP Toxicity Characteristic Leaching Procedure

TDD (TTY) Telecommunications Devices for the Deaf (teletypewriter)

Te tellurium

TE table of equipment, trailing edge

tech technical

TEL telephone

TEM Total Energy Management

temp temperature, temporary

TEMP temperature

TER terrazzo

TEU technical escort unit

tf tar felt

T&G, T and G tongue-and-groove

TG&B tongued, grooved, and beaded

tg&d tongued, grooved, and dressed

TH true heading

THK thick

therm thermometer

THERMO thermostat

thou thousand

thp thrust horsepower

THRU through

Ti titanium

TL transmission loss

tlr trailer

TM technical manual

tn ton, town, train

TN true north

tnpk, tpk turnpike

TNT trinitrotoluene

to take-off (estimate)

TOC total organic carbon

TOE thread one end

TOL tolerance

T-O-L Thread-O-Let

tonn tonnage

topog, topo topography

TOT total

tp tar paper

TPH total petroleum hydrocarbon

tps townships

tr tread

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

trans transom

TRANS transformer

transp transportation

trf tuned radio frequency

trib tributary

trib ar tributary area

ts tensile strength

TSCA Toxic Substance Control Act

TSD treatment, storage, and disposal

TSDF treatment, storage, and disposal facility

TSS total suspended solids

T&T truck and trailer

TTY text telephone (teletypewriter)

TU trade union, transmission unit

TUB tubing

TV terminal velocity

twp township

TYP typical

Definitions

tabby A type of concrete consisting of a mixture of lime and water, with shells, gravel, or stones used to make blocks for masonry.

tabia Compacted soil mixed together with lime and small stones.

tabled joint A joint in stonemasonry in which a projection cut into a stone fits into a channel cut into the stone below.

table joint Any of various joints in which the fitted surfaces are parallel to the edges of the pieces being joined, with a vertical break in the middle. This break is termed the table. Such joints are used in lengthening structural members.

tachometer A device for measuring rotation speed. Usually refers to revolutions per minute (RPM) of a revolving shaft.

tachymeter An instrument used by surveyors that determines distance, direction and elevation variation with one observation.

tack **1.** A short, sharp-pointed nail with a large head used in laying linoleum and carpets. **2.** A strip of metal, usually lead or copper, used to secure edges of sheet metal in roofing. **3.** The property of an adhesive that allows it to form a strong bond as soon as the parts and adhesive are placed in contact. **4.** To glue, weld, or otherwise fasten in spots.

tack coat A coat of emulsion that enhances the bonding of two layers of asphalt.

tack dry The state of an adhesive at which it will adhere to itself although it seems dry to the touch.

tack-free dry The point where paint or varnish is no longer sticky.

tackle A mechanism for moving materials, including raising or lowering them on a rope and pulley block.

tackless strip A metal or wood strip, with many small upstanding hooks, fastened to a floor or stair. A carpet is stretched beyond the strip. Hooks engage the backing and hold the carpet in place.

tack rag A rag treated with slow-drying or nondrying varnish or resin, and used to clean dirt and foreign matter from the surfaces of articles before they are painted.

tack rivet A rivet used to hold work steady during riveting.

tack weld **1.** A temporary weld to position parts. **2.** One of a series of short welds used where a continuous weld is unnecessary.

tag A strip of sheet metal folded on itself and used as a wedge to hold metal flashing in a masonry joint.

tagline **1.** A line that runs from a crane boom to a clamshell bucket and keeps the bucket firmly in position during operations. **2.** A safety line used by workers performing a job at high elevations or in other dangerous locations where a fall could be injurious. **3.** Rope attached to a heavy member, such as a truss or beam, or a piece of equipment being lifted. The rope is used by a worker on the ground to control the item as it swings up.

tail **1.** The bottom part of a slate shingle. **2.** The part of the roof rafter that extends beyond the wall line. **3.** The section of a stone step that extends into a wall.**tail**

tail bay **1.** The area between a wall and the nearest column line. **2.** In a framed floor or roof, the area between an end wall and the nearest girder.

tail beam A short beam or joist with one end set in a wall and the other supported by a header.



tail

tail cut **1.** A cut in the lower end of a rafter where it overhands the wall; sometimes ornamental. **2.** The seat cut at the lower end of a rafter.

tail in **1.** To secure or fasten one end of a timber, such as a floor joist, at a wall. **2.** To secure one end or edge of a projecting unit of masonry, such as a cornice.

tailing iron A steel member, built into a wall, to take the upward thrust of a cantilevered member that projects from the wall.

tailings **1.** Stones left on a screen used to grade material, as in a crushing operation. **2.** The waste material or residue of a product.

tailpiece **1.** A subordinate joist, rafter, or the like supported by a header joist at one end and a wall or sill at the other. **2.** A handle on the bar end of a two-man power saw.

take-off (takeoff, quantity takeoff) **1.** The process in which detailed lists are compiled, based on drawings and specifications, of all the material and equipment necessary to construct a project. The cost estimator uses this list to calculate how much it will cost to build the project. **2.** The activity of determining quantities from drawings and specifications. **3.** The actual quantity lists.

take-up The process of plaster substrate absorbing water from plaster during installation.

take-up block A pulley block rigged so that its weight or a spring will prevent slack in the lines passing through it.

talc A mineral with a greasy or soapy feel. It is very soft, having the composition $Mg_3Si_4O_{10}(OH)_2$.

talus **1.** A slope formed of rock debris at the bottom of a steep slope. **2.** The slope of a wall.

tambour door A sliding door made of thin folding panels on a flexible backing.

tamp To press a loose material such as soil or fresh concrete into a firm, compact mass by pounding repeatedly on it.

tamper **1.** An implement used to consolidate concrete or mortar in molds or forms. **2.** A hand-operated device for compacting flooring topping or other unformed concrete by impact from the dropped device in preparation for strikeoff and finishing. Contact surface often consists of a screen or a grid of bars to force coarse aggregates below the surface that prevents interference with floating or trowelling.

tandem **1.** A pair of moving parts in which one part follows the action of the other, such as tandem rollers. **2.** A vehicle made up of two units attached to one another, as the cab and trailer of a truck.



tandem

tandem wiring (master-slave wiring) A method of wiring two or more luminaires with one ballast. It saves on installation costs, and electricity.

tang The narrow extending tongue or prong on an object by which it is affixed to another piece, such as the tongue that secures a chisel to a handle.

tangent A straight line or curve that touches another curve at a single point without crossing the curve.

tangential In reference to lumber, it refers to sawing the truck or branch in a longitudinal fashion, perpendicular to the growth rings. Flat-grained lumber is produced by this method.

tank farm One contiguous site that may contain multiple tank fields, typically used for defining and classifying underground storage tanks and aboveground storage tanks.

tank field One continuous cluster of tanks.

tankless water heater (instantaneous heater) A water heater system that relys on instantaneous increases of power to heat water as it is demanded. It has only a mini-assembly of heater coils 36" high or less, and provides an endless amount of hot water. It stores only the water within the coils, and is consequently energy efficient.

tannin A soluble compound found in all woods that can cause staining.

tap **1.** A connection to a water supply. **2.** A faucet. **3.** A tool used to cut internal threads. **4.** To cut internal threads in a nut or hole.



tap

tap bolt A machine bolt that screws into a hole in material without requiring a nut or internal threads. A fully threaded bolt.

tap borer A hand tool used to bore tapered holes, as in a lead pipe for a connection.

tape **1.** A flexible measuring strip of fabric or steel marked off with lines similar to the scale of a carpenter's rule, usually contained in a case to allow rewinding or retracting after use. **2.** One of a number of adhesive-backed fabric or paper strips of assorted width used for various purposes within construction systems.



tape

tape balance A balancing device on a sash that counterbalances the weight of the sash by force of a metal tape coiled around a spring-loaded reel.

tape correction A correction that is figured into a distance measured by a tape in order to compensate for errors resulting from the condition of the tape or the manner in which it was handled.

tape joint A flat joint that is reinforced with tape and sealed with joint compound to provide additional strength.

tape measure (tapeline) A steel strip used by builders and surveyors to measure distances, usually graded in feet, tenths, and hundredths of a foot for use in surveying and engineering. Or, graded in feet, inches, and fractions of an inch for use in the building trades.

taper A gradual diminution of thickness, diameter, or width in an object.

tapered edge strip A tapered insulation strip used to elevate roofing components at the roof's perimeter and penetrations.

tapered insulation Preformed rigid insulation used on roofs at drains or roof intersections requiring a slight change in elevations at the surface.



tapered insulation

tapered tenon A tenon decreasing in width from the root to the projecting end.

tapershank The tapered end of a tool that fits into a socket.

tapersplit Shakes produced by using a mallet and froe, a sharp steel blade, to obtain split faces on both sides. The taper of the shake is a result of reversing the block and splitting the shake from a different end after each split.

taper thread A screw thread developed on a frustum of a cone, used in piping systems to ensure a tight joint, also used on some fasteners such as a screw or plug for a hole with worn threads.

taper tie A tapered steel rod used to hold concrete forms in place. When the forms are being stripped, the tie is removed by hitting the small diameter end and forcing it out through the hole created by the larger end.

tapia An adobe-like building material primarily made from earth or clay.

taping compound (embedding compound) A compound specifically formulated and manufactured for use in embedding of joint reinforcing tape at gypsum board joints.

taping knives Drywall finishing knives that range in width from 4″ to 24″. The smaller knives (4″ to 6″) are utilized for taping, spotting fasteners, taping angles and finishing. The wider blade knives are used in finishing. All have square corners.

taping strip **1.** A strip of roofing felt laid over the joint between adjacent precast concrete units before roofing operations. **2.** A strip of tape used to cover the joint between adjacent roof insulation boards.

tapped fitting Any fitting that has one or more tapped internal threads to receive threaded pipe.



tapped fitting

tapped tee A cast-iron soil pipe tee with a tapped outlet.

tar A dark, glutinous oil distilled from coal, peat, shale, and resinous woods, used as surface binder in road construction and as a coating in roof installation.



tar-and-gravel roofing

tar-and-gravel roofing Built-up roofing made up of gravel or sand, poured over a heavy coating of coal-tar pitch applied to an underlayer of felt.

tar cement Heavier grades of tar for use in construction and maintenance of bituminous concrete pavements.

tare The weight of a rail car, truck, or other conveyance when empty. The tare is deducted from the gross weight of the vehicle and its contents to determine the weight of the freight in figuring freight rates.

target date Date imposed on an activity or project by the user or client that constrains or otherwise modifies the network analysis. There are two types: target start dates, and target finish dates.*

target hardening Prohibiting entry or access to a facility by installing security hardware such as keyed or tamper-proof window locks, deadbolts for doors, interior door hinges, and rock-guard shields for windows.

target leveling rod A leveling rod fitted with a target to facilitate setting or reading.

target schedule A schedule devised or selected as an objective measure against which actual performance can be gauged.*

tarpaulin A waterproof cloth, generally used in large sheets to cover and protect construction materials or other goods stored outdoors.

task **1.** A cohesive, individual unit of work that is part of the total work needed to accomplish a project. **2.** Well-defined component of project work; a discrete work item. There are usually multiple tasks for one activity.*



T-bar

task lighting Lighting directed to a specific work surface or area.

T-bar A light-gauge, T-shaped member used to support panels in a suspended acoustical ceiling.

TBE Threaded both ends. Term used when specifying or ordering cut measures of pipe.



T-beam

T-beam A beam composed of a stem and a flange in the form of a T; usually of reinforced concrete or rolled metal.

T&C Threaded and coupled; an ordering designation for threaded pipe.

tearoff (ripoff) The stripping off of all roof coverings down to the wood.

teazel An angle post used in the construction of a timber-frame building.

teco A metal strap used to secure roof rafters and trusses to the top horizontal wall plate. Sometimes referred to as a hurricane clip.

tee **1.** An elaborately turned finial in the shape of an umbrella; used as finishing ornamental on pagodas, stupas, and topes. **2.** A metal structural member with a T-shaped cross-section. **3.** A pipe fitting that has a side port at right angles to the run.

tee handle A T-shaped handle used in place of a doorknob to operate the bolt on a door lock.

tee iron **1.** A piece of flat, heavy sheet metal, shaped into a T and equipped with drilled, countersunk holes; used to reinforce joints in wood construction. **2.** A steel T-beam section.

tee joint A joint between two members that intersect at right angles to form a T-shaped joint.

tee nut A fastening device that consists of an internally threaded cylinder and a disk with prongs around the perimeter of the bottom. The prongs are driven into wood to hold the nut steady while a bolt is inserted.

telegraphing Grain or other defects showing through on a smooth plywood panel.

telephone exchange The switching center for interconnecting telephone lines that terminate at the central station switch.

telescope To insert or slide one piece inside another.



telescope

telescoping boom A boom that can be extended as a telescope from within itself, eliminating the need to manually add sections to lengthen its reach.

telltale Any device designed to indicate movement of formwork or a point along the length of a pile under load.

tellurometer An electronic instrument that measures distance by transmitting microwaves to an object and determining how fast they bounce back. The time measurement is then converted to feet and inches.

temper **1.** To bring clay mortar or plaster to the proper consistency by moistening and mixing. **2.** To make stronger through processes of heating and cooling. In metals, stress is relieved without affecting hardness by heating to a temperature of 500°F. Other processes use 1,000°F to heat materials that are then allowed to cool naturally in order to soften them and reduce brittleness. **3.** The process of treating a wood surface with liquid resins or oils to increase resistance to water damage.

temperature, curing The temperature to which an assembly with adhesives is subjected in order to cure the adhesive.



temperature reinforcement

temperature differential The difference in temperature between two spaces within a building, or between the indoor and outdoor temperature. Temperature differential causes natural convection currents and air to migrate through cracks and open doors, windows, or other means of egress.

temperature reinforcement Reinforcement designed to carry stresses resulting from temperature changes.

temperature rise The increase of temperature caused by absorption of heat or internal generation of heat, as by hydration of cement in concrete.

temperature rise period The time interval during which the temperature of a concrete product rises at a controlled rate to the desired maximum in autoclave or atmospheric-pressure steam curing.

temperature stress Stress in a structure or a member due to changes or differentials in temperature in the structure or member.

tempered air Air that is warmed before being distributed.

tempered glass Glass that is prestressed by heating and then rapidly cooled, a process that makes it two to four times stronger than ordinary glass. It shatters into pebbles instead of slivers.

tempered water Warm water between 85°F and 110°F.

tempering The addition of water and mixing of concrete or mortar as necessary to bring it to the desired consistency during the prescribed mixing period. For mixed concrete, this will include any addition of water as may be necessary to bring the load to the correct slump on arrival at the work site, but not after a period of waiting to discharge the concrete.

template (templet) **1.** A thin plate or board frame used as a guide in positioning or spacing form parts, reinforcement, or anchors. **2.** A full-size mold, pattern, or frame shaped to serve as a guide in forming or testing contour or shape. **3.** A member of stone, metal or wood that is embedded in a wall in order to support a horizontal member or beam to distribute the load.

temporary construction cost Includes costs of erecting, operating, and dismantling nonpermanent facilities, such as offices, workshops, etc., and providing associated services such as utilities.*



template (templet)

temporary shoring Shoring installed to support a structure while it is being built, and removed when construction is finished.

temporary stress A stress that may be produced in a precast concrete member or a precast concrete component during fabrication or erection, or in cast-in-place concrete structures due to construction or test loadings.

tenant's improvements Improvements made to a house or parcel of land by a tenant at his own expense that commonly become a part of the property and cannot be removed by a departing tenant unless the owner gives his consent.



temporary shoring

tender **1.** An offer showing a willingness to buy or sell at a specific price and under specific conditions. **2.** In futures, the act on the part of a seller of a contract of giving notice to the clearinghouse that he intends to deliver the physical commodity in satisfaction of a futures contract. **3.** A hooktender. **4.** A railroad car attached to a steam locomotive for carrying fuel and water, or a ship providing similar services in a fleet. **5.** A formal offer of a bid.

tendon A steel element such as a wire, cable, bar, rod, or strand used to impart prestress to concrete when the element is tensioned.

tendon profile The path or trajectory of the prestressing tendon.



tendon

tenon A projecting, tongue-like part of a wood member designed to be inserted into a slot or mortise of another member to form a mortise and tenon joint.

tenon-and-slot mortise A glued wood joint formed by a tenon and mortise. Usually the two pieces join at a right angle to each other.

tenoner A machine used to form tenons.

tenon saw (mitre saw) A small backsaw used for cutting tenons.

tenpenny A particular size of nail, generally 3″ long with 69 of them to a pound. The term is believed to have originated in England, where nails of the same size once sold for ten pence per hundred.

tensile strain Elongation of a material that has been subjected to tension by pulling or stretching.

tensile strength Maximum unit stress that a material is capable of resisting under axial tensile loading, based on the cross-sectional area of the specimen before loading. Tensile strength is often used as a measure of fastener strength; it is the load required to pull open the fastener.

tensile stress Stress resulting from tension.

tensile test A test in which a sample is subjected to increasing longitudinal pulling stress until the material fractures.

tension The state or condition imposed on a material or structural member by pulling or stretching.

tension member A tie or other structural member subjected to tension.

tension reinforcement Reinforcement designed to carry tensile stresses such as those in the bottom of a simple beam.

tension rod A rod in a truss or structure that connects opposing components and prevents them from spreading.

tension wood Defective wood usually cut from the upper side of hardwood branches or leaning trunks. The processed lumber exhibits high longitudinal shrinkage, causing warping and splitting.

teratogen A term used in labeling hazardous construction or other materials that adversely affect the human reproductive system.

teredo A marine worm that damages untreated wood by boring holes in it.

terminal **1.** An element attached to the end of a conductor or to a piece of electric equipment to serve as a connection for an external conductor. **2.** A decorative element forming the end of an item of construction. **3.** A point of departure or arrival such as a railway or airport terminal.

terminal box A box, on a piece of electrical equipment, that contains leads from the equipment, ready for connection to a power source. The box is usually provided with a removable cover.



terminal

terminal landing The top and bottom elevator landing. (Courtesy of National Elevator Industry, Inc.)

terminal unit **1.** A unit, at the end of a duct in an air-conditioning system, through which air is delivered to the conditioned space. **2.** Devices located near the conditioned space that regulate the temperature and/or volume of supply air to the space.

terminal velocity The average speed of an airstream in an air-conditioning system as it reaches the end of its throw, used as an indicator of comfort level and degree of draftiness.

termites Insects that destroy wood by eating the wood fiber. Termites are social insects that exist in most parts of the United States, but they are most destructive in the coastal states and in the Southwest. Termites can enter wood through the ground or above the ground, although the subterranean type is most common in the United States. They eat the softer springwood first and prefer sapwood over heartwood.

termite shield A sheet of metal used on a foundation wall or pier as a projecting shield to prevent the passage of termites from the ground to a structure.

terms of payment Defines a specific time schedule for payment of goods and services and usually forms the basis for any contract price adjustments on those contracts that are subject to escalation.*

terne metal An alloy of lead, composed of up to 20% tin.

terneplate Sheet steel coated with an alloy of lead and tin, used chiefly in roofing.

terrace **1.** An embankment with a level top surface and stabilized side slopes. It may be used for agriculture or paved and/or planted for recreational use. **2.** A platform or paved embankment adjoining a building and used for recreational purposes.


terrace

terra-cotta Units of hard, unglazed fired clay, used for ornamental masonry.

terrazzo A type of flooring material made from marble or other stone chips set in Portland cement and polished when dry.


terrazzo

tertiary beam A beam that transfers its load to a secondary beam.

tertiary treatment An advanced stage of the wastewater treatment process, employing methods such as ion exchange, carbon absorption, reverse osmosis, and demineralization of residual solids.

tessera A small square of glass, stone, tile, or marble used in geometric and figurative mosaic work in pavements or floors.

test A trial, examination, observation, or evaluation used as a means of measuring a physical or chemical characteristic of a material, or a physical characteristic of a structural element or a structure.

test cylinder A sample of a concrete mix, cast in a standard cylindrical shape, cured under controlled or job conditions and used to determine the compressive strength of the mix after a specified time interval.

test method The testing procedures used to determine whether a specific product conforms with a particular standard.

test piling A foundation piling that is installed on the site of a proposed construction project and used to conduct load tests to determine the size and quantity of pilings needed for the actual structures.

test pit An excavation made to examine the subsurface conditions on a potential construction site. Samples are taken at specified elevations for lab analysis.

test plug A device that contains water test pressure in drainage pipes as part of a process to check plumbing systems for leakage.

test pressure Air pressure or water pressure used in plumbing to test pipes and fittings for strength and water-tightness.

test tee A pipe tee that is inserted into a drainage system to test it for leaks by subjecting it to water pressure.

texture **1.** The pattern or configuration apparent in an exposed surface, as of concrete or mortar, including roughness, streaking, striation, or departure from flatness. **2.** In referring to lumber, it is the grain of the wood.


texture

texture brick A rough, fired clay brick, often multicolored, commonly used for facing work.

texture cracking Cracking tensile failure, caused by temperature drop in members subjected to external restraints, or temperature differential in members subjected to internal restraints.

texturing The process of producing a special texture on unhardened or hardened concrete.

T&G joint *See* **tongue-and-groove joint**.

thatch A roof covering made of straw, red palm leaves, or similar material fastened together to shed water and provide thermal insulation.

T-head **1.** In precast framing, a segment of girder crossing the top of an interior column. **2.** The top of a shore formed with a braced horizontal member projecting on two sides and forming a T-shaped assembly.

theodolite An instrument used in precise surveying consisting of an alidade that is equipped with a telescope, a leveling device, and an accurately graduated horizontal circle. A theodolite may also have an accurately graduated vertical circle.


theodolite

therm A quantity of heat equal to 100,000 Btus.

thermal break (thermal barrier) An element of low conductivity placed between two conductive materials to limit heat flow; for use in metal windows or curtain walls that are to be used in cold climates.


thermal break (thermal barrier)

thermal bridge The interruption of a layer of thermal insulation by another material with high thermal conductivity (such as metal).

thermal coefficient of expansion A measure of the expected amount of expansion of a material when heated.

thermal conductance The rate at which heat flows from one surface of a material to the other, usually measured or specified at the rate over a unit area and under a unit temperature differential.

thermal conduction The process of heat transfer through a material by internal molecular action.

thermal conductivity A property of a homogeneous body measured by the ratio of the steady state heat flux, time rate of heat flow per unit area, to the temperature gradient, temperature difference per unit length of heat flow path, in the direction perpendicular to the area.

thermal cutout An overcurrent protective device containing a heater element and a renewable fusible member that opens the circuit. The thermal cutout is not designed to interrupt short-circuit currents.

thermal desorption A process that removes organic contaminants (as vapors or condensed liquids) from soils, sludges, and other solid media, which may then be destroyed in a permitted incinerator or used as supplemental fuel.

thermal diffusivity Thermal conductivity divided by the product of specific heat and unit weight. The term is an index of the facility with which a material undergoes temperature change.

thermal expansion The change in length or volume experienced by a material or mass when subjected to a change in temperature.

thermal factor A factor applied in doing lighting calculations that compensates for changes in the light given off by a fluorescent lamp when the ballast/lamp configuration varies from that used in photometric tests.

thermal insulating cement A dry mixture of cement and granular, flaky, fibrous, or powdery materials of low conductivity; when mixed with water and applied to a surface, it dries to provide an insulating covering.

thermal insulation (heat insulation) A material that provides a high resistance to heat flow. Examples are foamed plastics, mineral or glass fibers, cork, and foamed glass. The material is used in the form of blankets, boards, blocks, and poured or granular fill.

thermal lag The time required to add or remove heat from a mass before it reaches the design set point temperature.

thermal limit switch Automatically disconnects the electric supply if air flow through a heater is reduced below a safe level.

thermal mass cooling A method suited to climates with wide diurnal temperature swings. It involves running cool nighttime air across a large indoor building mass, such as a slab. The cool thermal mass then absorbs heat during the day.

thermal movement Changes in dimension of masonry or concrete resulting from fluctuations of temperature over time.

thermal oxidation A process that heats a gas stream to a sufficiently high temperature with adequate residence time to oxidize the hydrocarbons to carbon dioxide and water.

thermally protected A label appearing on the nameplate of a motor or motor-compressor that identifies it as being provided with a thermal protector. *See also* **thermal protector**.

thermal protector A protective device consisting of one or more sensing elements and an external control device to guard against overheating that can result from overload or failure to start.

thermal radiation The transmission of heat through electromagnetic waves from a warm surface to a cooler one.

thermal regenerator A device within a heating duct that is used to recover excess heat and send it to other areas.

thermal resistance (R value) The resistance of a material to the transmission of heat.

thermal shock The subjection of a material or body, such as partially hardened concrete, to a rapid change in temperature that may be expected to have a potentially deleterious effect.

thermal storage capacity A material's capacity to store the sun's heat for later use.

thermal stress (temperature stress) Stress induced in an object or structural member by restraint against movement required to accommodate temperature changes.

thermal transmittance (U-value) The measure of the rate of heat flow per unit area under steady conditions from the fluid on the warm side of a barrier to the fluid on the cold side, per unit temperature difference between the fluids.

thermal unit A unit of heat energy, usually the British thermal unit (Btu) in the English system or the calorie in the metric system.

thermal valve A valve with an activating element that responds to temperature or rate of temperature change.

thermite welding A welding process that uses heated liquid metal and slag resulting from the ignition of a mixture of ferric oxide and aluminum particles.

thermocouple A device for measuring temperature that has two junctions of two dissimilar metals. When the two junctions are at different temperatures, the junction connected to an instrument, such as a voltmeter, generates voltage.

thermoelectric Conversion of electricity to heat or heat to electricity.

thermography Process used to photograph heat being emitted from a structure. The photographs are in color, and the rate of heat loss related to particular colors.

thermomechanical pulping (TMP) A process in which wood chips are heated and softened by steam before being ground into fibers.

thermometer well A specially designed enclosure connected into the piping system and into which a thermometer can be placed to measure the temperature of a fluid in the piping.

thermopiles A support system used in permafrost that relies on temperature differences and natural convection for removing heat from the ground to keep it frozen or refrozen.

thermoplastic Becoming soft when heated and hard when cooled.

thermosetting Becoming rigid by chemical reaction and not remeltable.

thermostat An electric switch controlled by an element that responds to temperature; used in heating and/or cooling systems.

thermostatic expansion valve A valve regulating the flow of volatile



thermostat

refrigerant to a cooling unit, activated by changes in cooling unit pressure and superheat of the refrigerant leaving the cooling unit.

thermostatic trap A steam trap using a thermally actuated element to expand and close a discharge port when a designed amount of steam flows through it, and to contract and allow condensate to flow through as the temperature drops; usually used on steam radiators.

thermosyphon system A solar-powered water heating system that requires no pump or electricity to run.

thick-lift asphalt pavement A paving process in which the asphalt course is placed in one or more lifts of 4″ or more compacted thickness.

thimble **1.** A protective sleeve in a part intended to hold an item supported by, or passing through, the part. **2.** A protective sleeve of metal in the wall of a chimney used to hold the end of a stovepipe or smoke pipe.

thin butt A defect in western red cedar shakes in which the butt end of the shake fails to meet minimum thickness requirements.

thin edge A defect in shakes in which the thickness of 24″ shakes, within 10″ of the butt, is less than half the minimum specified thickness.

T-hinge (tee-hinge) A T-shaped, surface-mounted hinge. The crossarm of the T is fixed to a door frame or post while the length of the T supports a door or gate.



T-hinge (tee-hinge)

thinner Any volatile liquid used to lower the viscosity of a paint, adhesive, or other like material.

thin-set Descriptive of bonding materials for tile that are applied in a layer approximately $\frac{1}{8}''$ (3mm) thick.

thin-shell concrete Reinforced or prestressed concrete used to form a large shell. The thickness of the concrete is small relative to the span of the shell.

thin-wall conduit Electric conduit with a wall thickness that will not support threads. Sections are joined by couplings held in place by setscrews.

third clear (Factory Select, #3 clear) The highest grade of shop lumber. This grade will yield a high percentage of cuttings, but represents a small portion of a mill's total shop production.

third-party commissioning Independent assessment of systems to ensure that their installation and operation meets design specifications and that they are as efficient as possible.

thixotropy The property of a material that enables it to stiffen quickly while standing, but acquire lower viscosity with mechanical agitation, such as certain gels. Material having this property is called thixotropic.

thoroughly air-dried (TAD) Lumber that is air-dried sufficiently to meet the grading rule requirements for dry lumber.

thread A ridge, of uniform cross section, following a helix on the external or internal surface of a cylinder.

thread-cutting screw Screw that cuts threads in metal and joins metal sections.

threaded anchorage An anchoring device that is provided with threads to facilitate attaching the jacking device and to effect the anchorage.

threaded insert A device forced into a predrilled hole to form screw threads.

threaded joint A mechanical joint between threaded pipes.

threaded stud A fastening device with one pointed end driven into a material, such as concrete, and the other end is threaded and extends above the surface for the attachment of structural members.

threads, classes Loose tolerance threads are Class 1. Threads with Class 2 listing are usually stainless steel with normal commercial tolerances. Class 3 are made to stricter tolerances and fit much more tightly. When letter "A" is added to a class, it indicates external threads, or screws. Letter "B" means internal threads or nuts.

three-coat work The application of three coats of plaster: scratch coat, brown coat, and finish coat.

three-hinged arch An arch designed in two parts that are pin-connected, or hinged, to each other and to their supports. Such arches are designed for convenience of transportation and erection.

three-phase line A conductor installation that is able to carry heavy loads of electricity.

three-phase motor Induction motor in which the voltage varies from phase to phase by 120°.

three-point lock An assembly that latches the active leaf or a pair of doors at three points.

three-quarter brick A brick that has a length equal to approximately three-quarters that of a normal brick.



three-quarter brick

three-quarter turn Descriptive of a stair that turns through 270° in its progress from top to bottom.

three-way strap A metal strap used to tie three members of a wood truss together at a joint.

three-way switch An electric switch used to control lights from two different points, as from two different ends of a hallway.

three-way valve A valve with two outlets and one inlet or two inlets and one outlet.

three-wire system A system of electric power supply consisting of three conductors, one of which, the neutral wire, is maintained at a potential midway between the other two.



three-wire system

threshold **1.** A shaped strip on the floor between the jambs of a door; used to separate different types of flooring, or to provide weather protection at an exterior door. **2.** The level of lighting or volume of illumination that permits an object to be seen a specified percentage of the time with specified accuracy.

threshold limit value (TLV) The concentration of a hazardous substance to which a person may be exposed continuously without adverse health effects.



threshold

thriebeam Often used as bridge railing, it is steel plate (usually galvanized) with lengthwise raised areas or corrugations.

throat **1.** A groove cut in the underside of an exterior projecting piece, such as a sill or coping, to prevent water running back across the underside to a wall. **2.** The thinnest part supporting a stair stringer. **3.** The thinnest area of concrete stairs—between the intersection of the back of the tread and bottom of the riser and the underside of the soffit. **4.** The thinnest part of a weld. **5.** The opening in a wood plane hand tool where the shavings pass through.

through bolt A bolt that passes completely through the members it connects.

through bond The transverse bond formed by masonry units extending through a wall.

through lintel A lintel having thickness equal to that of the wall in which it is placed.

through-penetration An opening through a fire-resistive partition or floor/ceiling assembly to provide for an item (such as piping) to pass through it. Through-penetrations usually require the use of a firestop system to protect against the spread of fire through the opening.



through lintel

T

through-penetration firestop A system for sealing through-penetrations in fire-resistant floors, walls, and ceilings.

through tenon A tenon extending completely through the part in which the mortise is cut.

through-wall flashing A flashing that extends completely through a wall, as at a parapet.

throw **1.** The distance a latch bolt extends. **2.** The horizontal or vertical distance an airstream travels after leaving an outlet until its velocity is reduced to a specific value. **3.** The effective distance between a fixture and the area being illuminated.

throwout bearing A bearing that rides on the clutch jackshaft, that carries the engage-and-disengage mechanism.

thrust **1.** The amount of force or push exerted by or on a structure. Sometimes the horizontal component of that force. **2.** In an arch, the resultant force normal to any cross-section of the arch.

thrust bearing A support for a shaft that is designed to resist its end thrust.

thrust block Additional support introduced at the point of intersection between a brace and its support.

thrust washer A washer that holds a rotating part in place and keeps it from moving sideways relative to its bearings.

thumb nail bead Refers to quarter-round molding commonly found on the inside edge of rails and stiles on glazed or raised panel doors.

thumbscrew A screw that has a head that is either curled or flattened so it can be turned with a thumb and fingers.

thumbturn A small lever attached to a bolt lock that operates the lock much like a key by turning it.

tie **1.** A member or device that keeps two separate parts together, i.e., tie beam. **2.** Loop of reinforcing bars encircling the longitudinal steel in columns. **3.** A tensile unit adapted to holding concrete forms secure against the lateral pressure of unhardened concrete, with or without provision for spacing the forms a definite distance apart, and with or without provision for removal of metal to a specified distance from the finished concrete surface.



tie

tieback A rod fastened to a deadman, a rigid foundation, or a rock or soil anchor to prevent lateral movement of formwork, sheet pile walls, retaining walls, or bulkheads.

tie bar **1.** Bar at right angles to, and tied to, minimum reinforcement to keep it in place. **2.** Bar extending across a construction joint.



tieback

tie beam **1.** A concrete beam that connects individual pile caps or spread footings. **2.** A horizontal timber that connects the lower end of two opposite rafters to prevent spreading.

tie plate A plate used to join two components or parallel parts of a built-up structural-steel member.

tie wall A wall built perpendicular to a spandrel wall for lateral stability.

tie wire **1.** A wire used to hold forms together so they will not spread when filled with concrete. **2.** A single-strand wire used to tie reinforcing in place or metal lath to a column.

tige The shaft of a column, from the base moldings to the capital.

tight buildings Buildings that are designed to minimize infiltration air in order to reduce heating and cooling costs.

tight knot A knot in a piece of lumber that is sound and poses no detriment to the proper use of the wood member.

tight sheathing **1.** Tongue-and-groove or matched boards nailed to rafters or studs that may run at an angle to provide stiffness to the roof or wall. **2.** Excavation sheathing with the vertical planks interlocked for use in saturated soils.

tile A thin rectangular unit used as a finish for walls, floors or roofs, such as ceramic tile, structural clay tile, asphalt tile, cork tile, resilient tile, and roofing tile.

tile-and-a-half tile A roof tile that is the same length as the other tiles on a roof, but 1½ times as wide.

tileboard **1.** A wallboard with a factory-applied facing that is hard, glossy, and decorated to simulate tile. **2.** A square or rectangular board of compressed wood or vegetable fibers, used for ceiling or wall facings.

tile creasing A water-shedding barrier at the top of a brick wall consisting of two courses of tile that project beyond both faces of the wall.

tile field A system of distribution tile normally associated with a septic tank and leaching field system.


tile field

tile pin A pin that is passed through a roofing tile into the sheathing underneath to hold tile in place.

tile tie A section of heavy wire used to help secure roof tile.

till (glacial till, boulder clay) An unstratified glacial deposit consisting of compacted pockets of clay, silt, sand, gravel, and boulders, usually having good bearing capacity.

tilting fillet (cant strip, doubling piece) A thin wedge placed under the eave course of shingles or tiles to shed water more effectively.

tilting level A surveyor's level with a bubble mounted on the telescope and a provision for slight tilting of the telescope and level. The upright axis of the unit does not need to be vertical, but the level and telescope must be precisely aligned.

tilting mixer A small mixer for concrete or mortar that is emptied by tilting the mixer about a horizontal pivot.


tilting mixer

tilt-up (tilt-up construction) A method of concrete construction in which members are cast horizontally at a location adjacent to their eventual position and tilted into place after removal of forms.


tilt-up

timber **1.** Square-sawn lumber having a minimum nominal dimension of 5″ in the United States, or approximately equal cross-dimension greater than 4″ × 4½″ or 10 cm × 11 cm in Britain. **2.** Any heavy wood beam used for shoring or bracing.

timber connector One of a variety of metal connectors used in conjunction with bolts to form connections of timbers. Usually the bolt holds the timbers together while the connector prevents slippage.


timber connector

timber-framed building A building that has timbers for above-ground structural elements (except foundations).

timber pile A large, debarked, pressure-treated straight log that is driven into the ground as foundation support.


timber pile

time-delay fuse A fuse in an electric circuit that takes more than 12 seconds to open at 200% load.

time-dependent deformation Combined effects of autogenous volume change, contraction, creep, expansion, shrinkage, and swelling occurring during an appreciable period of time, not synonymous with inelastic behavior or volume change.

timekeeper A representative of the contractor who keeps records of hours worked by employees of the contractor and allocates the hours to various parts of the work.

time line Schedule line showing key dates and planned events.*

timely completion Completion of the specified work, or an agreed upon portion of the work, within the required time limits.

time of completion A specific date stated in the construction contract for substantial completion of the work.

time of haul In production of ready-mixed concrete, the period from first contact between mixing water and cement until completion of discharge of the freshly mixed concrete.

time sensitive costs Costs defined by the duration for which they are needed. The longer the particular item (such as a dumpster) is on the job site, the higher the cost.

time system A system of clocks and control devices, with or without a master timepiece, that will display current time at various locations and may include devices to program other systems, such as bells.

time-temperature curve Rate at which the temperature increases in a fire-testing furnace. Developed by ASTM, NFPA and UL, this curve is adhered to in all fire-resistive testing.

time value of money **1.** The time-dependent value of money stemming both from changes in the purchasing power of money (i.e., inflation or deflation), and from the real earning potential of alternative investments over time. **2.** The cumulative effect of elapsed time on the money value of an event, based on the earning power of equivalent invested funds. **3.** The expected interest rate that capital should or will earn.*

time weighted average (TWA) The average exposure of a person during eight hours to an airborne chemical hazard.

tin A lustrous, white, malleable metal with a low melting point, highly resistant to corrosion; used to make alloys and solder, and to coat sheet metal. When it is added to brass alloys, it provides greater strength and hardness, and also provides corrosion resistance from salt water.

tin-cap A small, flat metal washer used under roofing nails.

tin-clad fire door A door of two or three plywood planks, core covered with metal sheets and constructed in accordance with specifications of labeling authorities.



tin-clad fire door

tingle A flexible metal clip designed to hold a sheet of metal or glass.

tinker's dam Small dam of sand or other noncombustible material that contains the spread of molten solder.

tinning Coating metal with a tin alloy for corrosion protection or as a presoldering procedure.

tinplate Sheet steel or iron that has been coated with tin as protection against corrosion.

tin roofing A roof covering of tinplate or terneplate.

tin roofing

tin saw A saw used for cutting brick kerfs.

tin snips Strong shears with a blunt nose, used to cut sheet metal.

tint A light color made by diluting a color with white.

tip up A downspout extension that directs water away from the building.

titanium A lightweight, silver-gray metal that is strong and quite expensive. It is often added to other metals. Its properties include corrosion resistance against chlorides, acids and salt water.

title sheet The first page of a set of blueprints that usually includes location, name, a plot or sketch of the project, designer's name, and a list of the prints.

T

tobacco juicing Term given to the brown residue that comes out of asphalt products during weathering. Typically, it is seen on asphalt roofing shingles after periods of sun and rain in the first year exposed to the weather. It often disappears after that time.

tobermorite **1.** A mineral found in northern Ireland and elsewhere, having the formula $5CaO \bullet 6SiO_2 \bullet 5H_2O$. **2.** Ca:4H O, the artificial product tobermorite, G, of Brunauer, a hydrated calcium silicate having CaO/SiO ratio in the range 1.39 to 1.75. It forms minute layered crystals that constitute the principal cementing medium in Portland cement concrete, a mineral with 5 mols of lime to 6 mols of silica, usually occurring in plate-like crystals that are easily synthesized at steam pressures of about 100 psi and higher. Tobermorite is the binder in several properly autoclaved products.

tobermorite gel The binder of concrete cured moist or in atmospheric-pressure steam. A lime-rich gel-like solid containing 1.5 to 2.0 mols of lime per mol of silica.

toe **1.** Any projection from the base of a construction or object to give it increased bearing and stability. **2.** That part of the base of a retaining wall that projects beyond the face away from the retained material. **3.** The lower portion of the lock stile. **4.** The junction between the base metal and the face of a filled weld. **5.** To drive a nail at an oblique angle. **6.** That portion of sheeting below the excavated material. **7.** The part of a blasting hole furthest from the face.



toe

toeboard A vertical barrier at floor level erected along exposed edges of a floor opening, wall opening, platform, runway, or ramp to prevent falls of materials.

toehold A batten or board temporarily nailed to a sloping roof as a footing for workers.

toe joint A joint between a horizontal timber and another angle from the horizontal, as between a rafter and a plate.

toenail **1.** To drive a nail at an angle. **2.** A nail driven diagonally from a stud into another framing member.

toenailing Fastening a piece of lumber by driving nails obliquely to the surface. Alternate nails may be opposing to increase holding power.

toeplate A metal bar fastened to an outer edge of grating or the rear of a tread, and projecting above the surface to form a lip. *See also* **kickplate**.

toe wall A low wall built at the bottom of an embankment for greater stability.

toggle bolt A bolt and nut assembly used to fasten objects to a hollow wall or a wall accessible from only one side. The nut has pivoted wings that close against a spring when the nut end of the assembly is pushed through a hole and is open on the other side.



toggle bolt

toggle switch A lever-actuated snap switch.

toilet enclosure A compartment placed around a water closet for privacy.

toilet partition One of the panels forming a toilet enclosure.



toilet enclosure

tolerance **1.** The permitted variation from a given dimension or quantity. **2.** The range of variation permitted in maintaining a specified dimension. **3.** A permitted variation from location or alignment.

tom *See* **shore**.

ton **1.** A measure of weight equal to 2,000 lbs. or 907.2 kg. **2.** In cooling systems, a measurement of chiller size equal to 12,000 Btus of heat removal per hour.

tongue One edge of a piece of lumber that has been rabbeted from opposite faces, leaving a projection intended to fit into a groove cut into another board.

tongue and groove **1.** Lumber machined to have a groove on one side and a protruding tongue on the other, so that pieces will fit snugly together, with the tongue of one fitting into the groove of the other. **2.** A type of lumber or precast concrete pile having mated projecting and grooved edges to provide a tight fit, abbreviated "T&G."



tongue and groove

tongue-and-groove joint (T&G joint) A joint made by fitting a structural, cast-in-place surface for metal. The joint may also be welded. For plastic or wood pieces, the joint may be glued.

tongue-and-lip joint (tongue joint) A type of tongue-and-groove joint, except the tongue is wedge-shaped and the groove is tapered to receive it.

tongued miter A miter joint incorporating a tongue.

ton of refrigeration A measure of refrigerating effect equal to 12,000 Btu per hour.

tooled finish (tooled surface) A stone finish with the surface having 2 to 12 concave grooves per inch.

tooled joint A masonry joint in which the mortar has been shaped or worked before it sets.

tooling time The period of time after applying sealant in a joint during which it is possible to tool.

tooth A fine texture in a paint film provided by pigments or by abrasives used in sanding, providing a base for adhesion of a second coat.

toothed plate (bulldog plate, toothed gusset) A punched metal plate in which the punched metal protrudes from one side, forming teeth. Toothed plates are used for timber connections.

toothed ring A toothed ring that serves as a timber connector, generally used in the manufacture of large member wood trusses.

toothing Cutting or chipping out courses in old work as a bond for new work.

toothing plane A plane with a serrated blade mounted nearly vertically, used to roughen a surface prior to application of a veneer.

top beam A collar beam.

top car clearance The clearance between the top of an elevator car, or crosshead if provided, and the lowest overhead obstruction when the car is level with the top terminal landing.



top car clearance

top chord The upper section of a truss.

top coat The final coat in a paint system.

top cut The vertical cut at the top of a rafter.

top form Form required on the upper or outer surface of a sloping slab or thin shell.

top hung-in window An awning window that pivots at the top, and the bottom swings in.

top lap The shortest distance between the lower edge of an overlapping roof shingle and the uppermost edge of the one in the course directly below.

topographic survey A review process and record of information regarding the surface conditions of a proposed construction site. The resulting drawing normally uses contour lines to convey the surface height or depth relative to a given level.

topping **1.** A layer of concrete or mortar placed to form a floor surface on a concrete base. **2.** A structural, cast-in-place surface for precast floor and roof systems. **3.** The mixture of marble chips and matrix that, when properly processed, produces a terrazzo surface.



topping

topping compound A compound specifically formulated and manufactured for use over taping or all-purpose compounds to provide a smooth, level surface for applying decoration.

top plate A member on top of a stud wall on which joists rest to support an additional floor or to form a ceiling.



top plate

topsoil The surface layer of soil, usually containing organic matter, a mixture of particle sizes, and some animal life.

torch brazing A brazing process in which the heat is supplied by a torch.

torching The application of a lime mortar under the up-slope edges of roof tiles or slates. In full torching, the exposed underside of slates between battens is mortared.

torch soldering Soldering, with a gas flame supplying the required heat.

torpedo level Hand level, which may have a laser, that is used to level and plumb short members.

torque **1.** The force used to rotate something. **2.** Turning or twisting energy measured as the product of a force and a lever arm. **3.** That which tends to produce rotation.

torque converter A hydraulic coupling that introduces slippage to increase torque.

torque viscometer An apparatus used for measuring the consistency of slurries in which the energy required to rotate a device suspended in a rotating cup is proportional to viscosity.

torque wrench A tool used to turn nuts, bolts, and other similarly threaded fasteners. Unlike other types of wrenches, torque wrenches have a built-in device that measures the amount of torque (the turning or twisting force) applied to a nut or bolt. The device may be an audible signal, a scale built into the handle, or a dial, calibrated scale, or light. Torque wrenches limit the maximum amount of force that can be used, thereby preventing damage to the fastener and the material to which it is fastened.

torsel A piece of timber, steel, or stone placed under one end of a beam or joist to distribute its load.

torsion The twisting of a structural member by two equal and opposite torques.

torsion strength The measure of resistance of a material to twisting about an axis. For example, the amount of force needed to twist a fastener apart.

torus roll A joint in sheet metal or lead roofing at the intersection of two surfaces with different slopes. The joint is formed to allow for differential movement.

total float In CPM terminology, the difference between the time available to accomplish an activity and the estimated time required.



total float

total harmonic distortion (THD) A measure of the distortion of sinusoidal waves by harmonics. Fluorescent fixtures reflect harmonics back into the electrical supply system.

total heat The sum of both latent and sensible heat.

total pressure (impact pressure) The sum of velocity pressure and static pressure in a moving liquid. Measurement is expressed in inches of water.

total rise of a roof The vertical distance between the plate and the ridge of a roof.

total run The distance covered by a rafter including any overhang.

total suspended solids (TTS) A measure of the solid or particulate content of a liquid.

touch sanding A light surface sanding.

tower crane A crane with a fixed vertical mast that is topped by a rotating boom and equipped with a winch for hoisting and lowering loads. The winch can be moved along the boom so that any location within the diameter of the boom can be reached.



tower crane

tower equalizing lines Pipes installed to directly connect adjacent cooling tower basins to maintain a common basin water level.

toxic Causing an adverse health effect.

toxic agent A substance that causes an adverse health effect in humans.

TPH test A test used to determine the total quantity of petroleum hydrocarbons in a sample of soil or water.

T-plate A flat metal plate in the shape of a T, used to join or strengthen a right angle joint made between two timbers.

trabeated system A system of building construction using beams or lintels supported by columns.

trabeation (entablature) A type of construction utilizing horizontal members supported by columns. Trabeation is a common method of construction in Japan.

track **1.** A light gauge U-shaped metal member attached to a floor and used to anchor studs for a partition. **2.** A U-shaped member attached to a floor, ceiling, door or window header; used as a guide for a sliding or folding partition, door, or curtain. **3.** A pair of special structural shapes with fastenings or ties for a craneway, movable wall, or railroad. **4.** An electrical raceway that allows the placement and use of a variety of types of luminaires along it.



track

tracking solar collection systems Solar collection systems that are typically pole-mounted to the ground and that track the east-west movement of the sun for maximum energy collection.

track lighting A series of movable lights arranged in a line and located on a strip on the ceiling or mounted flush. Typically used for accent or spot lighting.

track roller In a crawler machine, the small wheels that are under the track frame and that rest on the track.



track roller

traction The friction developed between a body and a surface on which it moves relative to the total amount of driving force exerted.

traction elevator A car and counterweight attached to opposite ends of a hoist rope, which is moved by a traction machine. Used in buildings with more than five floors. (Courtesy of National Elevator Industry, Inc.)

traction machine An electric machine in which the friction between the hoist ropes and the machine sheave is used to move the elevator car. (Courtesy of National Elevator Industry, Inc.)

traction steel Steel with strength of 180,000 to 190,000 pounds per square inch that is used to manufacture wire rope.

tractor A vehicle on tracks or wheels used for towing or operating equipment.

trade (craft) **1.** The business or work in which one engages regularly and which may require manual skill. **2.** A group representing a particular occupation or craft.

trade discount A dealer discount offered to the contractor by the supplier representing the difference between list price and the actual charge for goods or services.

trade stacking Having more subcontractor or prime contractor work crews performing different types of construction work in the same area than is efficient for the flow of the work.

traffic **1.** The total number of messages handled by a communications channel in a given period, expressed in hundred call seconds (CCS) or other units. **2.** Number of vehicles within a specific space and time.

traffic cone A pliable and highly visible cone used as a temporary marker to direct traffic away from a work area.

traffic paint Paint formulated to withstand vehicular traffic, and to be highly visible at night; used to mark traffic lanes and pedestrian crossings.

train A string of connected or unconnected vehicles or mobile equipment, such as a paving train, which consists of mobile machines to lay the various courses of a pavement.

trajectory of prestressing force The path along which the prestress is effective in a structure or member. It is coincident with the center of gravity of the tendons for simple flexural members and statically indeterminate members that are prestressed with concordant tendons; but, it is not coincident with the center of gravity of the tendons of a statically indeterminate structure that is prestressed with nonconcordant tendons.

transducer A substance or device that converts input energy into output energy of a different form, such as a photoelectric cell.

transfer bond In pretensioning, the bond stress resulting from the transfer of stress from the tendon to the concrete.

transfer column A column in a multistory framed building that is not continuous to the building foundation. At some floors the column is supported by a girder or girders, and its load transferred to adjacent columns.

transfer girder A girder that supports a transfer column.

transfer grille A grille or pair of grilles that allow air to move from one space to another, installed in locations such as a wall or door.

transfer medium The material that carries heat from a solar collector to a living area or storage medium.

transfer strength In prestressed concrete, the concrete strength required before stress is transferred from the stressing mechanism to the concrete.

transfer switch A mechanism designed to switch an electrical conductor from one circuit to another without interrupting the current flow.

transformed section A hypothetical section of one material arranged so as to have the same elastic properties as a section of two materials.

transformer An electric device with two or more coupled windings, with and without a magnetic core, for introducing mutual coupling between circuits; generally used to convert a power supply at one voltage to another voltage.


transformer

transformer bank Two or more transformers that are situated in the same enclosure, such as in a transformer vault.

transistor A semiconductor device with three terminals that amplifies electrical power.

transit A surveyor's instrument used to measure or lay out horizontal or vertical angles, or measure distance or difference in elevation.

transit-and-stadia survey A type of survey in which angles are measured with a transit and distances are measured with a transit and a stadia rod.

Transite® A well-known brand name of high-strength cement made from Portland cement and non-asbestos fibers. It is sold in panels and as preformed items and pipe. Formerly made of asbestos-reinforced cement.


transit

transition strip A strip of wood, metal, or vinyl that covers adjacent areas of flooring to ensure a smooth transition.

transit line Any line of a survey traverse projected by use of a transit or similar instrument.

transit mix (transit-mixed concrete) Concrete that is wholly or mainly mixed in a truck mixer, usually while in transit to the job site.

translucent Descriptive of a material that transmits light, but diffuses it sufficiently that an object cannot be seen clearly through the material.

transmission **1.** A gear set or similar device that permits changes in the speed/power ratio and/or direction of rotation. **2.** The process by which incident light leaves an object or surface from a side other than that which receives the light. **3.** The transportation of bulk electricty from the generator to the substation.

transmission length (transfer length) The distance at the end of a pretensioned tendon necessary for the bond stress to develop the maximum tendon stress.

transmission line Any electric line operating at 69,000 or more volts.

transmission loss (TL) The decrease in energy during transmission from one surface of a medium to another, such as, through a panel or wall.

transmittance The capacity of glass to transmit solar energy—in visible light, as well as ultraviolet and infrared ranges. Transmittance is measured in percentages of each type of light.

transom A glazed or solid panel over a door or window, usually hinged and used for ventilation. The transom and bar may be removable for passage of large objects.


transom

transom bar **1.** A horizontal member separating a transom from the door or window. **2.** Any intermediate horizontal member of the frame of a door or window.

transverse cracks Cracks that develop at right angles to the long direction of the member.

transverse joint A joint parallel to the intermediate dimension of a structure.

transverse load A load applied at right angles to the longitudinal axis of a structural member, such as a wind load.

transverse prestress Prestress that is applied at right angles to the principal axis of a member.

transverse reinforcement Reinforcement at right angles to the principal axis of a member.

transverse rib A rib in vaulting that spans the nave, cross aisle, or aisle, at right angles to the longitudinal axis of the area spanned.

transverse section A section of a building taken at right angles to its longest dimension.

transverse shear A shearing action or force perpendicular to the main axis of a member.

trap **1.** A plumbing fixture so constructed that, when installed in a system, a water seal will form and prevent backflow of air or gas, but permit free flow of liquids. **2.** A removable section of stage floor.


trap

trap coil A coil used in the electromagnet that activates a trip.

trapdoor A door set in a floor, ceiling, or roof.

trapeze hanger A horizontal rigid member used to suspend pipes from two rods in instances where longitudinal movement is anticipated.

traprock (trap) Any of various fine-grained, dense, dark-colored igneous rocks, typically basalt or diabase.

trap seal (deep seal) The head (vertical distance between the crown weir and the dip of a trap fixture), expressed linearly resisting back pressure. The height of the water in a toilet bowl, it prevents sewer gases from entering the building.



trapdoor

trapway (passageway) The channel in a toilet that connects the bowl to the waste outlet. The trapway is where siphonic action occurs, and its size is measured in terms of the largest ball that can pass through it.

trash rack A grid of metal bars placed in front of a water inlet to collect larger solids transported by the water.

trave **1.** A beam or timber crossing a building. **2.** A panel in a ceiling delineated by beams or timbers.

travel (rise) The vertical distance between the bottom landing of an elevator or escalator and the top landing.

traveler An inverted, U-shaped structure usually mounted on tracks that permit it to move from one location to another to facilitate the construction of an arch, bridge, or building.

travelers Electrical wires between three-way and/or four-way switches.

traveling cable A cable made of electric conductors, that connects an elevator or dumbwaiter car with a fixed electric outlet in the hoistway.



travel (rise)

traveling crane A tower crane mounted on tires, crawlers, or rails.

traverse **1.** To plane across the grain of wood. **2.** A structural crosspiece, such as a transom bar. **3.** A gallery or loft crossing a building. **4.** A barrier to allow passage by an official or dignitary, but discouraging unauthorized passage.

traverse closure The calculated line that closes a traverse; the resultant error of measurements, sometimes referred to as "linear error of closure."

travertine A variety of limestone deposited by running water, usually stratified; used for interior walls and for floors.

tray ceiling A horizontal ceiling constructed part way up the slope of a gabled roof.

tray ceiling

tread **1.** The horizontal part of a stair. Historically, treads have been made from 5/4″ × 12″ vertical-grain lumber called stepping. In recent years, however, most stepping has been made from particleboard that is given a bullnosed edge. **2.** High-friction coating on a pulley for the purpose of reducing slippage of the belt.

tread length The length of a tread measured perpendicular to the travel line of the stair.

tread plate A fabricated metal tread with a slip-resistant surface.

tread return The projection of a tread beyond the stringer of an open stair.

tread run The horizontal distance between nosings of stair treads.

tread width The horizontal distance from the nosing of a stair tread to the riser above the tread. The tread run plus nosing.



tread width

treated wood Wood that has been treated with a wood preservative.

tree-dozer An attachment for a tractor or bulldozer consisting of metal bars and a cutting blade, used to clear bushes and small trees.

tree grate A metal grating set around a tree and flush with a pavement.



tree grate

trellis A latticework of wood or metal, usually used to support vines.

tremie A pipe or tube through which concrete is deposited under water, having at its upper end a hopper for filling and a bail for moving the assemblage.

tremie concrete Subaqueous concrete placed by means of a tremie.

tremie seal The depth to which the discharge end of the pipe is kept embedded in the fresh concrete that is being placed. The seal is a layer of concrete placed in a cofferdam for the purpose of preventing the intrusion of water when the cofferdam is dewatered.

trench box (trench shield) Box-shaped sheathing made of wood or steel, permanently braced across a trench for excavation and pipe laying. The trench-box unit is pulled along the trench as excavation and pipe laying proceed. It prevents sidewall cave-in during trenching.



trench brace

trench brace A normally adjustable device, used as crossbracing to support sheeting in a trench.

trench drain A cast-in-place or preformed concrete trench usually covered with a grate that serves as both a drain and a collection point for runoff water or other liquid.

trench duct A trough with removable covers through which electric power and control cables are run. It can be a metal unit that is set in concrete or formed in a concrete slab. The top of the covers are level with the floor.



trench duct

trenched footing (neat excavation) A type of footing in which a trench has been excavated to the exact dimensions of the desired footing, and the concrete poured directly into the trench. This type of footing requires no formwork.



trench excavator

trench excavator A self-propelled machine with a side-mounted shovel or chain of buckets, used to excavate trenches.

trench header duct A preformed duct laid in concrete slabs to provide raceways for wiring and communication lines.

trench jack A hydraulic or screw jack used as a cross brace in a trench bracing system.

trestle ladder A self-supporting, portable ladder that is often paired with another to form a portable scaffold system.

trial batch A batch of concrete prepared to establish or check proportions of the constituents.

trial pit A small pit dug to investigate the soil, sometimes dug to bedrock or other dense material.

triangular truss A light wood roof truss used for short spans.

triangulation A method of surveying over long distances by establishing a network of triangles. Most sides in the network are computed from a known side that may be calculated, and two measured angles. Lengths are measured periodically as a check.

triaxial compression test A test whereby a specimen is subjected to a confining hydrostatic pressure, and then loaded axially to failure.

triaxial test A test whereby a specimen is subjected simultaneously to lateral and axial loads.

tricalcium aluminate A compound having the composition $3CaO \bullet Al_2O_3$, abbreviated C_3A. Its mineral phase name is *celite*.

tricalcium silicate A compound having the composition $3CaO \bullet SiO_2$ abbreviated C3S. An impure form of it (alite or celite) is a main constituent of Portland cement. *See also* **alite**.

trig **1.** Bricks laid in the center of a wall to prevent sagging and keep it plumb. **2.** Metal clip used to hold a mason's line.

trigger The condition or event that initiates or causes an interlocking process to occur.

trilateration A method of surveying similar to triangulation, except that distances are measured by electronic instruments, and the two angles are calculated. Quadrilaterals are used in addition to triangles.

trim Millwork, primarily moldings and/or trim to finish off and cover joints around window and door openings.

trim hardware Decorative finish hardware that is functional or used to operate functional hardware.

trimmer (header) **1.** A short beam that supports one or more joists or beams at an opening in the floor. **2.** A beam or joist inserted in a floor on the long side of a stair opening and supporting a header.



trimmer (header)

trimming joist A joist parallel to the common joists, but of larger cross-section, possibly two pieces nailed together, that support a trimmer.

trimming rafter A rafter supporting the end of a header. *See also* **trimming joist**.

trimstone (trim) Decorative masonry members on a structure built or faced largely with other masonry; includes sills, jambs, lintels, coping, cornices, and quoins.

trip (release catch) A device that releases a mechanism, such as a pawl.

trip coil A control device that utilizes a solenoid to open a circuit breaker.

triple glazing Energy-saving windows composed of three panes of glass sandwiched together with air in between. Gases such as argon or others may be used to increase efficiency. *See* **three-phase motor**.

triplex cable Electrical cable composed of three conductor cables twisted together.

tripod A three-legged, adjustable stand for an instrument.

trivet A low support for a surveying instrument used where a tripod cannot be accommodated.

troffer A long recessed lighting unit that is usually installed flush with the ceiling.

trolley beam An exposed steel beam on the underside of a structure, used to support a trolley crane.

trolley hoist Lifting apparatus that features a hoist that moves along an I-beam that is supported above the work area.

Trombe wall A sun-facing wall made of stone, concrete, or other thermal mass material that collects heat during daylight hours and releases it to the space behind the wall over a 24-hour period.



Trombe wall

trough A channel used to contain electric power or control cables.

trowel **1.** A flat, broad-blade, steel hand tool used in the final stages of finishing operations to impart a relatively smooth surface to concrete floors and other unformed concrete surfaces. **2.** Also a flat, triangular-blade tool used for applying mortar to masonry.



trowel

trowel finish The smooth finish surface produced by troweling.

troweling machine A motor-driven device used to trowel concrete. It functions via orbiting steel trowels on radial arms that rotate on a vertical shaft.



truck crane

truck crane A crane mounted on a wheeled vehicle.

truck mixer A concrete mixer suitable for mounting on a truck chassis and capable of mixing concrete in transit.

truck zoning device A freight elevator mechanism that allows the car to be maneuvered within a limited distance above a landing while the door and hoistway door are open.

true wood Heartwood.

trunk **1.** The main wood shaft of a tree. **2.** The shaft portion of a column. **3.** Descriptive of the main body of a system, as a sewer trunk line. **4.** Transmission channel that runs between two central office or switching devices, connecting exchanges to the main telephone network.

trunk sewer A main sewer that receives flow from many tributaries, covering a large area.

trunnion A pivot consisting of two cylinders or pins projecting from the body of the pivoted object.

truscan order One of the five classical orders featuring columns in which the bottom one-third is straight and the top two-thirds are tapered.



truss

truss **1.** A structural component composed of a combination of members, usually in a triangular arrangement, to form a rigid framework; often used to support a roof. **2.** An escalator frame.



trussed joist (open-web joist)

trussed beam A beam, usually composed of timber that is reinforced by a center post beneath the beam and two rods running from the bottom of the post to the ends of the beam.

trussed joist (open-web joist) A joist in the form of a truss.



trussed purlin

trussed purlin A lightweight trussed beam used as a purlin.

trussed rafter roof A roof system in which the cross-framing members are some form of light wood truss.

trussed ridge roof A pitched roof in which the upper support for the rafters is a truss.

trussed-wall opening Any opening in a framed structure with a truss system used to span the opening.

truss rod **1.** A metal rod used as a tension member in a truss. **2.** A metal rod used as a diagonal tie.

try cock Valve used as a backup system of determining water level in a boiler.

try square A normally graduated square, the legs of which are at 90°.

T-shore A shore with a T-head.

tube-and-coupler scaffold A scaffold system using tubes for posts, bearers, braces, and ties. Special couplers connect the parts.

tube axial fans Single-width airfoil wheel fans arranged in a cylinder to discharge air radially against the inside of the cylinder.



tubular-welded-frame scaffold

tub trap The U-shaped section of a bathtub drainpipe designed to hold a water seal to prevent sewer gasses from entering.

tubular fiber form Long tubes of compressed paper used as concrete forms. Often used to pour footings.

tubular lock A type of bored lock that encloses the bolt within a tube.

tubular scaffolding Scaffolding manufactured from galvanized steel or aluminum tube and connected by clamps.

tubular-welded-frame scaffold A scaffold system using prefabricated welded sections that serve as posts and horizontal bearers. The prefabricated sections are braced laterally with tubes and bars.

tuck A recess in a horizontal masonry joint formed by raking out mortar in preparation for tuck pointing.

tuck pointing A method of refinishing old mortar joints. The loose mortar is dug out and the tuck is filled with fine mortar that is left projecting slightly or with a fillet of putty or lime.

tuff, volcanic tuff A highly porous, low-density rock comprising volcanic particles sometimes in stone applications or as a thermal insulation material.

tufted carpet Carpet manufactured by pile yarn punched through carpet backing material that has been previously woven. The pile is cut after.

tumbler The mechanism in a lock holding the bolt until operated by a key.

tumbler switch A lever-operated electric snap switch.

tung oil An oil that dries to a clear finish and resists water, it is often used as a wood finish.

tungsten-halogen lamp (quartz lamp) An incandescent lamp that consists of a tungsten filament, a gas containing halogens, and an envelope of a high-temperature resistant material, such as quartz. The lamp is small compared with lamps of similar wattage.

tungsten steel A very hard, heat-resistant carbon steel containing tungsten.

tunneling Excavating a horizontal hole greater than six feet in diameter.

tunnel test Refers to an ASTM standard test of a material's surface-burning characteristics.

turbidimeter A device for measuring the particle-size distribution of a finely divided material by taking successive measurements of a suspension in a fluid.

turbidimeter fineness The fineness of a material such as soil or Portland cement, usually expressed as total surface area in square centimeters per gram, as determined with a turbidimeter. *See also* **Wagner fineness**.

turbidity The clarity of water, measured by light transmission through a water sample.

turbine Any of various machines that convert the kinetic energy of a moving fluid to mechanical energy. The turbine is often used for driving an electric generator.

turnbuckle A device for adjusting the length of a rod or cable, consisting of a right screw and a left screw coupled by a link.



turnbuckle

turned bolt A machine bolt, usually with a hexagonal head, the shank of which is finished to a close tolerance.

turned work Pieces of stone or woodwork having a circular cross-section, such as posts and balusters. Turned work is usually cut on a lathe.



turned bolt

turning Shaping objects by use of cutting tools while the piece to be shaped is rotated on a lathe.

turning gouge Hand tool used to rough cut wood on a lathe.

turning piece A wood template used by a mason to form a small arch that does not require centering.

turning vane One of several curved fins that are placed inside ductwork at a change in direction in order to promote better airflow.

turn-of-the-nut method A method used to pretension high-strength bolts. The nut is turned from the snug-tight position by either a man using his full strength on a wrench, or a few hits with an impact wrench.

turn piece A small knob used to control a deadbolt from the inside of a door, usually crescent- or oval-shaped for gripping with thumb or fingers.

turnstile A barrier rotating on a vertical axis, usually allowing movement in one direction only and admitting one person at a time. A turnstile is sometimes coin- or token-operated.

turpentine A thin, volatile oil obtained by steam distillation from the wood or exuded resin of certain pine trees. Turpentine was once widely used as a paint thinner and solvent, but now is replaced by solvents derived from petroleum.

tusk tenon A tenon with stepped reinforcing at the lower side.

twin cable A cable consisting of two parallel, insulated conductors fastened side-by-side through the insulation, or by common wrapping.

twin-filament lamp An incandescent lamp with two filaments that are wired independently, used as double-function lamps as in automobile stop lights or as three-level wattage lamps.

twin pug (pugmill) A mill with two blade-supporting shafts running in opposite directions.

twist The distortion from a flat plane caused by the turning or winding of the edges of a board.

twist drill A drill with one or more helical cutting grooves, used to drill holes in metal, wood, and plastic.

twisted pair Two single, insulated wires that have been twisted together to reduce the likelihood of interference to and from other wire pairs.



twisted pair

two-by-four A commonly used piece of timber with nominal dimensions 2″ thick by 4″ wide, i.e., 5 cm thick by 4 cm wide.

two-coat work The application of two coats of plaster: a base coat followed by a finish coat.

two-core block A concrete masonry unit with two hollow cells.



two-core block

two-four-one (2–4–1) Structural wood panels, at least 1⅛″ thick, designed for single-floor applications over joists spaced 48″ apart and also used as roof sheathing in heavy timber construction. The term is synonymous with APA-Rated Sturd-I-Floor and is a registered trade name of the American Plywood Association.

two-handed saw A large saw with two handles intended to be worked by two people; used for felling trees or cross cutting logs, largely replaced by chain saws.

two-part line A single strand, rope, or cable that is doubled back around a sheave to double the capacity.

two-stage absorption A refrigeration system in which the hot refrigerant (water) vapor travels to a second generator. There, upon condensing, it supplies heat for further refrigerant vaporization from the absorbant of intermediate concentration that flows from the first generator.

two-stage curing A process whereby concrete products are cured in low-pressure steam, stacked, and then autoclaved.

two-way joist construction Floor or roof construction in which the floor or roof is supported on two mutually perpendicular systems of parallel joists.



two-way joist construction

two-way reinforcement (two-way system) A system of reinforcement. Bars, rods, or wires are placed at right angles to each other in a slab, and are intended to resist stresses due to bending of the slab in two directions.

two-way slab A reinforced concrete slab in which the main reinforcing runs in two directions, parallel to the length and width of the panel.

Type I & IA Duty Rating Safety ratings for ladders based on load limits. Type I is rated for 250 lbs. Type IA is rated for 300 lbs.

type S fuse A mechanism designed to fit into a screw shell socket to determine whether the fuse is blown. Available in 15, 20, and 30 amperes.

Type X A fire-resistant type of gypsum wallboard.

Tyvek® house wrap Brand name for a weather protector building wrap. In addition to adding insulation, it works to keep moisture from penetrating walls while also allowing the building to "breathe."

U

Abbreviations

u unit

U uranium

UBC Uniform Building Code

UCI uniform construction index

UCS unconfined compressive strength

UDC universal decimal classification

U/E unedged

UF, UGND underground feeder

Ug micrograms

ugnd underground

UHF ultra-high frequency

UL Underwriters' Laboratories, Inc.

Uld unloading

ult ultimate

unassm unassembled

unfin unfinished

unglz unglazed

unhtd unheated

unidir unidirectional

unins. uninsurable

unmtd unmounted

uns unsymmetrical

up upper

UPS uninterruptible power supply, United Parcel Service

ur, UR urinal

URD underground residential distribution

USBM U.S. Bureau of Mines

USBR U.S. Bureau of Reclamation

USG United States gauge

USP United States Primed

UST underground storage tank

Util utility

UTMCD Uniform Traffic Manual for Control Devices

UTP unshielded twisted pair

UV Ultraviolet

USGBC U.S. Green Building Council

Definitions

U-bolt A bolt formed in the shape of the letter U, with threads on the ends to accommodate nuts.



U-bolt

U factor A measure of thermal transmission.

UL label A seal of certification attached by Underwriters' Laboratories, Inc. to building materials, electrical wiring and components, storage vessels, and other devices, attesting that the item has been rated according to performance tests on such products, is from a production lot that made use of materials and processes identical to those of comparable items that have passed fire, electrical hazard, and other safety tests, and is subject to the UL reexamination service.



UL label

ultimate design resisting moment The theoretical, applied bending moment that will cause failure in a reinforced concrete member through yield in the tensile reinforcing steel or crushing of concrete.

ultimate load **1.** The maximum load a structure can bear before its failure due to buckling of column members or failure of a component. **2.** The load at which a unit or structure fails.

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

ultimate set The final degree of firmness obtained by a plastic compound after curing.

ultimate shear stress The stress at a section loaded to its maximum in shear.

ultimate strength The maximum resistance to load that a member or structure is capable of developing before failure occurs. With reference to cross sections of members, the largest moment, axial force, torsion, or shear a material can sustain without failure.

ultimate wiring capacity The average load per unit of area required to cause the rupture and subsequent failure of a supporting mass.

ultrasonic soldering A soldering process, usually performed without a flux, wherein unwanted surface films are removed from the base metal by transmitting high frequency sounds through molten solder, resulting in a more effective welding of the base metal with the solder.

ultrasonic testing A nondestructive method used to test the structural integrity of a pile or a metal element.

ultrasonic welding A process in solid-state welding wherein the metal parts are held together under pressure and joined by applying high frequency sound waves to their surface.

ultraviolet Literally, beyond violet in the color spectrum. A minor component of the sun's radiation, it is also produced artificially in arc lamps.

unbalanced partition A wall built with two layers of drywall on one side and a single layer on the other. Such an imbalance occurs when fire or sound insulation is just needed on one side.

unbalancing A technique used in the pricing process to allocate estimated costs to accounts whose definitions do not fully reflect the nature of the cost being allocated. The purpose of unbalancing is to achieve a desired business result such as improved cash flow. For example, a disproportionate amount of overhead costs may be allocated in a contract bid to early project activities so that early income is maximized.*

unbonded member A posttensioned, prestressed concrete element in which tensioning force is applied against end anchorages only, with tendons free to move within the elements.

unbonded posttensioning Posttensioning in which the tendons are not grouted after stressing.

unbonded tendon A tendon not bonded to the concrete section.

unbound base Material without a binder added.

unbraced frame A structural frame, resistant to the lateral load carried, due to the ability of its members and connections to withstand bending and shear stresses without additional diagonal bracing, K-bracing, or other extra supporting devices.



unbraced frame

unbraced length The greatest length between points on a compression member not restrained against lateral movement by beams, slabs, or bracing.

unbraced length of column Distance between adequate lateral supports.

uncased pile An unlined concrete pile, often reinforced, that has been poured directly into a bored hole in the ground.

uncertainty **1.** The total range of events that may happen and produce risks (including both threats and opportunities) affecting a project. (Uncertainty = Threats + Opportunities.) **2.** All events, both positive and negative whose probabilities of occurrence are neither 0% nor 100%. Uncertainty is a distinct characteristic of the project environment.*

unclassified excavation An excavation priced with a single unit cost, regardless of whether the excavator finds loose fill or embedded rock. Bidders on an unclassified excavation assume the risk for whatever appears.

unconsolidated Not compacted.

uncoursed Descriptive of irregularly placed masonry, which is not laid in courses with continuous horizontal joints, but in a seemingly random pattern.



uncoursed

underbed In terrazzo floor construction, the base mortar, usually horizontal, into which strips are embedded and on which terrazzo topping is applied.

undercloak **1.** The part of a lower sheet in sheet metal roofing that serves as a seam. **2.** A course of tiles or slate used in roofing to provide an underlayer for the first course installed at the eaves.

undercoat **1.** A coat of paint that improves the seal of wood or of a previous coat of paint, and provides a superior adhesive base for the top coat. **2.** A paint used as a base for enamel. **3.** A colored primer paint.

unconfined compressive strength (UCS) A measure of soil bearing capacity, determined by a variety of tests.

undercured Descriptive of concrete, paint, sealant, or other substances applied in wet or elastic form, which have not had time to harden properly because of unsuitable environmental conditions.

undercut To cut away a lower portion of architectural stonework, creating a projection above it that functions as a drip.

undercut door A door with greater than normal clearance at the floor to give more ventilation to an area.

underdrain A drain installed in porous fill under a slab to drain off ground water.

underfloor heating A heating system that uses embedded pipes or electric heating cables beneath a finished floor so that heat radiates steadily from floor level.

underfloor raceway A raceway installed beneath a finished floor to distribute electric conductors and communications wiring. Suitable for use in a concrete floor.



underfloor raceway

underground facilities All pipelines, conduits, ducts, cables, wires, utility access-ways, vaults, tanks, tunnels or other such facilities or attachments, and any encasements containing such facilities that have been installed underground to furnish any of the following services or materials: electricity, gases, steam, liquid petroleum products, telephone or other communications, cable television, sewage and drainage removal, traffic or other control systems or water.*

underground feeder (UF) cable Cable rated for external, underground use.

underground piping Piping that has been or will be laid beneath the surface of the ground.

underground storage tank (UST) A tank system that has at least 10% of its volume underground.

underlay A material, such as asphaltic felt, which isolates a roof covering from the deck.

underlayment Structural wood panels designed to be used under finished flooring to provide a smooth surface for the finish material.

underlining felt The material, usually a No. 15 felt, applied to a wood roof deck before shingles are laid.

underpinning The construction of new substructure support beneath a column or a wall, without removing the superstructure, in order to increase the load capacity or return it to its former design limits.



underpinning

underrun **1.** Opposite of overrun; same as pickup; the (lesser) difference between the actual cost and the estimate. **2.** Decrease in estimated quantity.

undersanded With respect to concrete, containing an insufficient proportion of fine aggregate to produce optimum properties in the fresh mixture, especially workability and finishing characteristics.

underslung car frame The car frame of an elevator with fastening sheaves for hoisting cables attached at or below its platform.

Underwriters' Laboratories, Inc. (UL) A private, nonprofit organization that tests, inspects, classifies, and rates devices and components to ensure that manufacturers comply with various UL standards.

undisturbed sample A sample taken from soil in such a manner that the soil structure is deformed as little as possible.

undressed Descriptive of lumber products that have not been surfaced.

uneven grain Wood grain showing a distinct difference in appearance between springwood and summerwood. Examples are ring-porous hardwoods such as oak, and softwoods such as yellowpine that have soft springwood and hard, dense summerwood.

uneven grain

unfaced insulation Board, batt, or blanket insulation without a vapor barrier.

unglazed tile A hard ceramic tile of homogeneous composition throughout, deriving its color or texture from the materials used and the method of manufacture. The unglazed tile is used for floors or walls.

uniformat A registered trademark system for organizing a cost estimate that is based on building systems.

uniform angle sander A drywall finishing tool with a right-angled sanding device that can be adjusted to fit corner angles. The tool enables a worker to sand both sides of a corner simultaneously.

Uniform Building Code (UBC) One of several national building codes used to promote building safety, health and public welfare. Published by the International Conference of Building Officials (ICBO), it is used throughout the western U.S. states.

Uniform Construction Index The forerunner of the MasterFormat adopted by the Construction Specifications Institute in 1978. This system divides technical data and all related accounting, specifying, and tracking functions into 16 divisions.

Uniform Fire Code A model law devoted to ensuring practices consistent with protecting life and property from fire, explosion, and hazardous materials and conditions.

uniform grading A particle-size distribution of aggregate in which pan fractions are approximately uniform with no one size or group of sizes dominating.

uniformity coefficient A coefficient related to the size distribution of a granular material, obtained by dividing the size of the sieve of which 60% of the sample weight passes by the size of the sieve of which 10% of the sample weight passes.

uniform load A load distributed uniformly over a structure or a portion of a structure.

uninterruptible power supply An electrical supply system that will continue to provide current during a power outage.

union **1.** A confederation of individuals who share the same trade or similar trades and who have joined together for a common purpose. **2.** A pipe fitting used to join two pipes without turning either pipe, consisting of a collar piece that is slipped on one pipe, and a shoulder that is threaded or soldered on that pipe and against which the collar piece bears. Unions allow dismantling a fitting without disturbing the pipe.



union

union elbow A pipe elbow outfitted with a union coupling at one end that makes it possible for the coupling end to connect with the end of a pipe without turning or disturbing the pipe.



union elbow

union tee A pipe tee with a union-type joint on one end.

unitary air-conditioner A fabricated assembly of equipment to move, clean, cool, dehumidify, and sometimes heat the air, consisting of a fan, cooling coil, compressor, and condenser.

unit cost The cost per unit of measurement.

unit hours Work hours per unit of production.*

united inches The sum of the length and width of a piece of rectangular glass, each in inches.

unit heater A factory-assembled heating unit consisting of a housing, a heating element, a fan and motor, and a directional outlet.

unitized Wood products securely gathered into large standard packages or units, usually fastened with steel straps and often covered by tough paper or plastic.



unit heater

unit lock A preassembled lock.

unit price **1.** Current and accurate cost of materials, equipment, and labor used to develop a unit price estimate. **2.** The sum stated in a project bid representing the price per unit for materials and/or services.

unit price contract A construction contract in which payment is based on the work done and an agreed on unit price. The unit price contract is usually used only where quantities can be accurately measured.

unit-type vent One of several relatively small openings on the roof of a structure, equipped with a metal frame and housing as well as manual or automatic hinged dampers that are opened in case of fire.

unit ventilator A unit with operable air inlets, and often with heating and/or cooling coils, that conveys outdoor air into an interior room.



unit-type vent

unit water content **1.** The quantity of water per unit volume of freshly mixed concrete, often expressed as pounds or gallons per cubic yard. **2.** The quantity of water on which the water-cement ratio is based, not including water absorbed by the aggregate.

universal Descriptive of a door lock, door closer, or similar piece of hardware that can be used on either a left-hand or right-hand swing door.

universal joint A coupling between two shafts set at an angle that allows them to rotate and swivel.



universal joint

universal motor A motor that can operate on either alternating or direct current and is usually less than one horsepower.

unkeyed Loose plaster that has become detached from the lath, requiring additional repair other than canvassing.

unloader A control for an electric-motor-driven compressor. The unloader controls the pressure head of the compressor and allows the motor to be started at low torque by disconnecting one or more cylinders during the initial period of operation.

UN number A classification code assigned to a particular material by the Department of Transportation.

unprotected corner Corner of a slab with no adequate provision for load transfer, so that the corner must carry over 80% of the load.

unrestrained member A structural member that is allowed to rotate freely about its supports.



UN number

unseasoned Lumber that has not been dried to a specified moisture content before surfacing. The American Softwood Lumber Standard defines unseasoned lumber as having a moisture content above 19%.

unsound Not firmly made, placed, or fixed, and thus subject to deterioration or disintegration during service exposure.

unsound plaster Hydrated lime, plaster, or mortar that contains particles that are unhydrated and may expand later, causing popping or pitting.

unstable soil Earth material, other than running, that because of its nature or the influence of related conditions, cannot be depended upon to remain in place without extra support, such as would be furnished by a system of shoring.

unstiffened member A structural member or portion thereof that must withstand compressive force, but is not reinforced in the direction perpendicular to that in which it bends most readily.

unsupported wall height Masonry wall construction limit for wall height set by local codes determined by ratio of wall thickness to height of wall.

updating The regular review, analysis, evaluation, and reporting of progress of the project, including recomputation of an estimate or schedule.*

uplift The upward load that wind or water pressure can create on a building.

upright A vertical length of stone or timber. Also any vertical structural member, such as a stanchion.

upset **1.** To make an object or part of an object shorter and thicker by hammering on its end. **2.** A flaw in timber caused by a heavy blow or impact that splits fibers across the grain. **3.** In welding, an increase in volume at the point of the weld caused by applied pressure.



upright

upset welding A process of resistance-welding making use of both the pressure and heat generated by the flow of current as it passes through the resistance provided at the contact point of the surfaces being welded.

upstand (upturn) That portion of a flashing or roof covering that is run up a wall without being tucked in, and which is usually covered with stepped flashing.

upstanding beam A beam projecting above a concrete floor rather than concealed beneath it.



upstand (upturn)

upturned beam A concrete beam that extends above the slab it is designed to support.

urea-formaldehyde foam insulation (UFFI) Insulation used in wall cavities as an energy conservation measure during the 1970s that has relatively high indoor concentrations of formaldehyde.

urea resin adhesive A powder which is mixed with water before use and has high early strength and good heat resistance. Urea resin adhesive is not recommended for exposure to moisture or use in poorly fitted joints.

urea resin glue Urea-formaldehyde resin, an adhesive used in the manufacture of hardwood plywood and interior particleboard panel products. Urea is a soluble, crystalline material found in the urine of mammals, but it is also produced synthetically for the manufacture of plastics and adhesives.

urinal A plumbing fixture designed for the collection of urine and equipped with a water supply for flushing.



urinal

U-stirrup A rod shaped like a U used in reinforced concrete construction.

U-strap Column anchorage to a concrete base using a steel U-shaped anchor bolt embedded in concrete. A wall form tie made of heavy wire bent into a U-shape.

utility **1.** A grade of softwood lumber used when a combination of strength and economy is desired. Utility grade is suitable for many uses in construction, but lacks the strength of Standard, the next highest grade in light framing, and is not allowed in some applications. **2.** A grade of Idaho white pine boards, equivalent to #4 Common in other species. **3.** A grade of fir veneer that allows white speck and more defects than are allowed in D grade. Utility grade veneer is not permitted in panels manufactured under Product Standard PS-1–83. **4.** Gas, water, electrical, and sewer beyond 5′ from a building.

utility easement areas Areas utility company personnel are legally authorized to access in order to service the lines.

utility and better (Util&Btr) A mixture of light framing lumber grades, the lowest being utility. The "*and better*" signifies that some percentage of the mixture is of a higher grade than utility, but not necessarily of the highest grade. In joist and plank grades, the corresponding term is "*#3&Btr.*"

utility pole An outdoor pole installed by a utility company for the support of telephone, electric, and other cables.

utility sheet Metal sheeting that is mill-finished and cut into numerous widths and lengths for general use within the building construction industry.

utility transformer A transformer of primary and secondary wire coils that reduces voltage supplied by a utility to a facility.

utility vent A pipe that helps provide an air supply within a drainage system or fixture to prevent siphonage. The vent rises above the highest water level of the fixture, and turns downward before connecting to the main vent.

utility window A hot-rolled steel window, generally inexpensive, equipped with a hopper light and a fixed light and used principally in garages, shops, and basements.

U-trap A running trap, built in the shape of a U, that forms a seal against the passage of gasses in a pipe, while allowing liquid to flow freely.



U-trap

U-tube (manometer) A U-shaped glass tube filled with water or mercury and used to measure pressure by liquid displacement.

U-value (thermal transmittance) The time rate of heat flow per unit area between fluids on the warm side and cold side of a barrier, calculated in accordance with the difference in unit temperature between the two test fluids.



U-tube (manometer)

V

Abbreviations

V volt, valve, V-groove, vertical shear
V1S vee one side
VA volt amperes
VAC volts alternating current
vac vacuum
val value, valuation
van vanity
VAP vapor
VAR visual-aural range, volt-ampere reactive
var variation, varnished
VAT vinyl-asbestos tile
VAV variable air volume
VC veneer core
VCP visual comfort probability
VCT vinyl composition tile
VD vapor density
VDC volts direct current
vel velocity
ven veneer
vent, VENT ventilator, ventilate
ver version
verm vermiculite
vert, VERT vertical
VF video frequency, vinyl-faced
VG vertical grain
vhf very high frequency
VHO very high output
Vib vibrating, vibrator
vic vicinity
VIF verify in field
vil village
vis visibility, visual
VIT vitreous, vitrified
Vitr vitrification
vit ch vitreous china
vj V-joint
VLDPE very low density polyethylene
vlf very low frequency
VLF vertical linear foot
VLR very long range
voc volatile organic compound
vol, VOL volume
vou voussoirs
VP vent pipe
VRP vinyl reinforced polyester
VS versus, vent stack, vapor seal
VT vacuum tube, variable time
VTR vent through roof
VU volume unit

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

Definitions



vacuum breaker

vacuum **1.** A space that contains no matter. **2.** A space with reduced air or water pressure.

vacuum breaker A pipe or fixture element in a water supply system that prevents siphon or suction action and the backflow that can result.

vacuum circuit breaker An electrical circuit breaker with its surge protection components housed in a vacuum.

vacuum concrete Concrete from which water and entrapped air are extracted by a vacuum process before hardening occurs.

vacuum saturation A process for increasing the amount of filling of the pores in a porous material, such as lightweight aggregate, with a fluid, such as water, by subjecting the porous material to reduced pressure in the presence of the fluid.



valance lighting

vacuum tank In a hot water heating system, a container that holds condensate drawn into the boiler by a vacuum pump.

vadose zone The layer of unsaturated soil above the groundwater level.

valance lighting Lighting from sources that are concealed and shielded by a board or panel at the wall-ceiling intersection. This lighting may be directed either upward or downward.

valley The place where two planes of a roof meet at a downward, or V, angle.

valley board A board nailed to a valley rafter of a roof to accommodate the metal gutter.

valley flashing Sheet metal with which the valley of a roof is lined.

valley gutter The exposed open gutter in the valley of a roof, constructed with sloping sides.



valley

valley jack A rafter in a roof system that is cut shorter than a common rafter and connects the ridge and a valley rafter.

valley rafter In a roof frame, the rafter that follows the line of the valley and connects the ridge to the wall plate along the line where the two inclined, perpendicular sides of the roof meet.

valley roof A pitched roof having one or more valleys.

valley shingle A specially cut shingle designated for placement next to a valley with grains that run parallel to the valley.

valley tile A trough-shaped roofing tile used at a roof valley to create a channel for water runoff.

value **1.** The utility of an object or service or its worth consisting of the power of purchasing other objects or services. **2.** The relative lightness or darkness of a color.

value engineering (VE) An analysis and comparison of cost versus value of building materials, equipment, and systems. VE considers the initial cost of construction, coupled with the estimated cost of maintenance, energy use, life expectancy, and replacement cost.

valve Device that regulates a liquid or gas flowing through piping.

valve flutter Any undesirable movement of a valve during operation.

valve motor An electric or pneumatic motor that operates a valve within an air-conditioning system, regulating it at a location remote from the unit.

valve plug A valve component that moves against a stationary seat to control pressure or flow of a fluid.

valve seat The stationary portion of the valve which, when in contact with the movable portion, stops the flow.

valve stem A threaded, spindle-like valve component that connects the valve plug to an external handle, gearset, or actuator.



valve seat

vaneaxial fan A fan with a disk-type wheel within a cylinder and a set of air-guided vanes on the wheel. The fan is either belt-driven or connected directly to a motor.

vane test, vane shear test A test used to evaluate soil strength and consistency. After a hole is drilled into the earth, a spinning four-bladed shaft is inserted and the soil's resistance to the shaft's vanes is measured.



vaneaxial fan

vanity A cabinet and lavatory combination for a bathroom.

van stone A type of joint made by using loose flanges on lengths of pipe whose ends are lapped over to give a bearing surface for the flange.

vapor barrier Material used to prevent the passage of vapor or moisture into a structure or another material, thus preventing condensation within them.



vapor barrier

vapor heating system A system of steam heating functioning at or near atmospheric pressure, wherein the condensed liquid is returned to the boiler by gravity.

vapor lock The formation of vapor in a pipe carrying liquids, thereby preventing normal flow.

vapor migration Penetration of vapor through walls or roofs, caused by the vapor pressure differential between the inside and the outside of a structure.

vapor pressure A component of atmospheric pressure caused by the presence of vapor. Vapor pressure is expressed in inches, centimeters, or millimeters of height of a column of mercury or water.

vapor retarder A layer of material used to protect roof insulation and moisture-sensitive roofing membranes from the damaging effects of internal humidity.

vapor retarder felt A felt material containing asphalt and used for sealing.

variable air volume (VAV) An air distribution system capable of automatically delivering a reduced volume of constant temperature cool air to satisfy the reduced cooling load of individual zones.



variable air volume (VAV)

variable costs Those costs that are a function of production, e.g., raw materials costs, byproduct credits, and those processing costs that vary with plant output such as utilities, catalysts and chemical, packaging, and labor for batch operations.*

variable inlet vanes VIV Vaned dampers installed at the inlet to a fan to produce a spin to the air entering the fan, which reduces the fan performance.*

variable-volume air system An air-conditioning system that automatically regulates the quantity of air supplied to each controlled area according to the needs of the different zones, with preset minimum and maximum values based on the load in each area.

variegated Descriptive of a material or surface having streak-marks, or patches of a different color or colors.

varnish A clear, colorless substance used chiefly on wood to provide a hard, glossy, protective film. Varnish is manufactured from resinous products dissolved in oil, alcohol, or a number of volatile liquids.

varnish stain A colored transparent varnish with a lesser power of penetration than a true stain.

varved clay Sedimentary soil with alternating layers of clay and silt or fine sand that display contrasting colors as they dry, formed during the differing sedimentation conditions in various seasons of the year.

vault **1.** An enclosure built above or below ground large enough to accommodate human entry. Vaults are used to install, operate, and maintain electrical cables and equipment. **2.** A masonry structure with an arched ceiling. **3.** A room used for storage of valuable records and/or computer tapes that is of fire-resistant construction, has safe electric components, and has a controlled atmosphere.

V-bank filter box An air-handling unit section in which the filters are arranged in a V configuration in order to provide a greater filter surface.

V-beam sheeting Corrugated sheeting formed with flat, V-angled surfaces instead of a rippled or curved surface.

V-brick Brick that is vertically perforated.

V-cut **1.** Descriptive of a style of lettering carved into stone in acute, triangular cuts. **2.** A V-shaped saw cut or incision in wood.

vehicle **1.** In painting, a substance, such as oil, in which pigments are mixed for application. **2.** Any device for conveyance.

vein A thin layer or deposit of one material in another, usually in an approximate plane.

veining The lines that appear in soft bitumens as the material ages.

velocity head A measurement of the velocity of fluid through a pipe or watercourse. The velocity head is equal to the height that the fluid must fall to achieve that same velocity.

velocity riser A vertical pipe with a smaller diameter than adjacent piping that is used to increase the flow velocity of the material conveyed in the pipeline.

veneer **1.** A masonry facing attached to the backup, but not so bonded as to act with it under load. **2.** Wood peeled, sawn, or sliced into sheets of a given constant thickness and combined with glue to produce plywood. Veneers laid up with the grain direction of adjoining sheets at right angles produce plywood of great stiffness and strength, while those laid up with grains running parallel produce flexible plywood most often used in furniture and cabinetry construction.



veneer

veneer adhesives Any of several basic substances used in the gluing of veneers to produce plywood. These include blood glue, soybean glue, and phenolic resins. Other adhesives made from urea, resorcinol, polyvinyl, and melamine are sometimes used in edge gluing, patching, and scarfing.

veneer base Gypsum lath sheeting, ordinarily cut in widths of four feet and in varying lengths and thicknesses, with a core of gypsum and a special paper facing that is receptive to veneer plaster.

veneered construction Construction of wood, reinforced concrete, or steel, faced with a thin layer of another material such as structural glass or marble.

veneered door A hollow or solid core door with veneer faces.

veneered plywood Plywood faced with a decorative veneer, usually wood or plastic.

veneer plaster A mill-mixed gypsum plaster made up of one or two components and desired for its bond, strength, and ease of installation.

veneer saw A hand or power saw with a fine-toothed blade used to cut wood veneers.

veneer tie A wall tie designed to hold a veneer to a wall.

veneer wall A wall with a facing that is attached to, but not bonded to, the wall.



veneer wall

venetian blind **1.** A blind made of thin slats mounted so as to overlap when closed and provide spaces for admitting light and/or air when open. The mounting usually consists of strips of webbing. The unit is operated by cords. **2.** Adjustable exterior slatted shutters.

venetian blind

venetian mosaic A type of terrazzo topping in which large chips of stone are incorporated.

Venetian plaster A wall plaster applied with a trowel in several layers and often coated with a polished waxed finish.

venetian window *See* **palladian window.**


venetian window

vent **1.** A pipe built into a drainage system to provide air circulation, thus preventing siphonage and back pressure from affecting the function of the trap seals. **2.** A stack through which smoke, ashes, vapors, and other airborne impurities are discharged from an enclosed space to the outside atmosphere. **3.** Any opening serving as an outlet or inlet for air.

vent cap Piece at the top of a ventilation pipe.

vent connector A metal pipe connecting the exhaust of a burner to a chimney.

vented form A concrete form that retains the solid constituents of concrete and permits the escape of water and air.

ventilating brick A brick with holes in it for the passage of air.

ventilating jack A sheet metal hood over the inlet to a vent pipe to direct flow into the pipe.

ventilation A natural or mechanical process by which air is introduced to or removed from a space, with or without heating, cooling, or purification treatment.


ventilator

ventilator **1.** A device or opening in a room or building through which fresh air enters the enclosure and stale air is expelled. **2.** A pivoted sash or framework, outfitted with hinged panes of glass that may be opened without opening the sash.

ventilator frame An assembly designed to accommodate a pivoted sash, with two rails and two stiles into which the operable panes are set.

vent sash

vent pipe A small-diameter pipe used in concrete construction to permit the escape of air in a structure being concreted or grouted.

vent sash A small, operable light usually hinged on its upper edge in a window, which may be swung open to allow some ventilation without opening the entire sash.

vent screed A plaster screed with a vented portion, used in roof overhang soffits.

vent stack main vent A vertical vent pipe whose functions are to provide air circulation to or from any part of a building drainage system and to protect its trap seals from siphonage.

vent system **1.** Piping that provides a flow of air to or from a drainage system to protect trap seals from siphonage or back pressure. **2.** A chimney or vent combined with a vent connector to form a clear passageway for expulsion of vent gases from gas-burning equipment to the outside air.

venturi 1 A short tube with a constriction used to measure liquid or gas velocity by the differential pressure as the liquid or gas flows. **2.** A constricted throat in an air passage of a carburetor used to mix fuel and air.

veranda A covered porch or balcony along the outside of a building, intended for leisure.

verbal quotation A contractor's record of a subcontractor's cost proposal for designated work. Quotes given by phone should be followed by a written proposal.

verdigris A bluish green patina that naturally forms on copper, bronze, or brass over time as it is exposed to atmospheric conditions.

verge **1.** The edge that projects over the gable of a roof. **2.** A small shaft of a column employed for ornamental effect. **3.** The unpaved section of a road right-of-way.

verge fillet A strip of wood that is fastened to the roof battens of a gable to cover the upper edges of the gable wall.

vermiculite A group name for certain clay minerals, hydrous silicates or aluminum, magnesium, and iron that have been expanded by heat. Vermiculite is used for lightweight aggregate in concrete and as a loose fill for thermal insulating applications.

vermiculite concrete Concrete in which the aggregate consists of exfoliated vermiculite.

vermiculite plaster A fire-retardant plaster covering for steel beams, concrete slabs, and other heavy construction materials, constituted with an aggregate of very fine exfoliated vermiculite.

Vermont slate A type of slate from Vermont used in paving and roofing.

vertical bar An upright muntin.

vertical bond Masonry bond with one brick or block placed directly on top of the next.

vertical broken joint A tiling pattern that offsets each vertical row by half its length.

vertical exit A stairway, ramp, fire escape, escalator, or any other route of movement that serves as an exit from the floors of a building above or below street level.

vertical-fiber brick A paving brick cut with wire during the manufacturing process, and laid on pavement with the wire-cut side exposed to view.

vertical firing Mechanical arrangement of gas, oil, or coal burners in a furnace so that fuel is vertically discharged up from burners below or down from burners on top.

vertical force The load on a structure from a force acting vertically.

vertically pivoted window A window having a sash that pivots on a vertical axis near its center so the outside of the glass can be conveniently cleaned.


vertical siding

vertical pipe Any pipe or fitting that makes an angle of 45° or less with the vertical.

vertical sand drain A boring through clay or silt filled with sand or gravel to allow soil to drain. Most effective when bored to permeable soil below.

vertical siding A type of exterior wall cladding consisting of wide matched boards.

vertical sliding window A window with one or more sashes that move only in a vertical direction and make use of friction or a ratchet device to remain in an open position.



vertical sliding window

vertical slip form A form that is jacked vertically during construction of a concrete structure. Movement may be continuous with placing or intermittent with horizontal joints.

vertical spring-pivot hinge A spring hinge that is mortised into the heel of a door, which in turn is fastened with pivots to its door head and the floor.

vertical transportation An elevator, escalator, or lift.

vertical tray conveyors A vertical conveying system designed to carry trays or boxes.

very high output fluorescent lamp (VHO lamp) A rapid-start fluorescent lamp designed to operate on a very high current, providing a light flux per unit length of lamp higher than that obtained from a high output fluorescent lamp.

vestibule An anteroom or foyer leading to a larger space.

V-groove Any of several longitudinal cuts made on the faces of pieces of lumber or plywood. Edges are sometimes chamfered to create a V where pieces are placed edge to edge. A V may also be machined the length of the piece to provide decoration. A V pattern also may be used to form tongue-and-groove connections on hardwood or plywood.

vibrated concrete Concrete compacted by vibration during and after placing.

vibrating roller A towed or self-propelled roller with a motor-driven vibrating mechanism.

vibrating screed A machine designed to act as a vibrator while leveling freshly placed concrete.

vibration Energetic agitation of freshly mixed concrete during placement by mechanical devices, either pneumatic or electric, that create vibratory impulses of moderately high frequency that assist in evenly distributing and consolidating the concrete in the formwork.

vibration, external The process of attaching vibrating devices at strategic positions to concrete forms. Particularly applicable to the manufacture of precast items and for vibration of tunnel-lining forms. In the manufacture of concrete products, external vibration or impact may be applied to a casting table.

vibration, internal The process of inserting one or more vibrating elements into concrete at selected locations. Generally applicable to cast-in-place construction.

vibration isolator A flexible support for any form of vibrating or reverberating machinery, piping, or ductwork, serving to reduce the vibrations that are carried to the remainder of the building structure.



vibration isolator

vibration limit That time at which fresh concrete has hardened sufficiently to prevent its becoming mobile when subjected to vibration.

vibrator An oscillating machine used to agitate fresh concrete so as to eliminate gross voids, including entrapped air, but not entrained air, and to produce intimate contact with form surfaces and between embedded materials.



vibrator

vibratory hammer A pile-driving hammer normally weighing from three to five tons that with rapid vibrations causes the soil around the pile to change to a liquid state. The weight of the hammer then slips the pile down through the soil.

vibratory plate A piece of construction machinery that is used to compact soil, pavement underlayment materials, or pavement.

vibroflotation A process used to stabilize and otherwise improve soil for building by compacting loose granular soils.

victaulic pipe Pipe with fittings that allow for movement along joints while remaining watertight.

view sash A picture window with panes of glass divided by muntins.

vinyl A thermoplastic compound made from polymerized vinyl chloride, vinylide chloride, or vinyl acetate. Vinyl is typically tough, flexible, and shiny.

vinyl-clad Doors and windows that have a vinyl covering applied over all exposed surfaces that make up the frame and jamb.

vinyl composition tile A floor tile similar to vinyl-asbestos floor tile except the asbestos has been replaced by glass fiber reinforcing.



vinyl composition tile

vinyl overlay An overlay applied to panel products and moldings and usually printed with a color and grain, needing no further finishing.

vinyl siding Building siding most often consisting of rigid polyvinyl chloride (PVC) used to cover exterior walls.

vinyl tile A vinyl floor tile similar to vinyl-asbestos floor tile, but that does not contain mineral or other fibers.

virgin-growth lumber Wood products harvested from mature trees, with attributes such as a tighter grain, superior hardness, dimensional stability, and durability.

vis, vice, vise **1.** A spiral staircase, generally of stone, with steps winding around a central shaft. **2.** A screw stair.

viscometer Instrument for determining viscosity of slurries, mortars, or concretes.

viscosity The degree to which a fluid resists flow under an applied force.

viscous filter An air-cleaning filter that employs a surface covered with viscous oil or fluid, to which dirt particles and other airborne impurities cling as the air passes through.



vise

vise A gripping tool with adjustable jaws controlled by a lever or screw, used to clamp an object firmly in place while work is being done on it.

visible light transmission or transmittance The percentage of total visible light that passes through a window or similar glazed opening.

visible transmittance VT A window rating that includes the amount of visible light that is transmitted. VT ranges between 0 and 1, and the higher rating indicates more light transmitted.



vision panel

vision panel Glazed opening installed in a door as specified by plans and specifications.

visqueen Plastic sheeting, typically 4 mil or 6 mil in thickness.

visual comfort probability VCP A system that evaluates the visual comfort of a lighting system by rating its direct discomfort glare.

vitreous In describing glazed products, a degree of impermeability in a material characterized by low water absorption. Vitreous is less than 3% absorption in floor and wall tile and low voltage electrical porcelain, and less than 0.3% absorption in other materials.

vitreous china Material with a glass-like finish used for plumbing fixtures.

vitrification **1.** A process of melting soil or wastes to a liquid form, and then cooling the liquid to a hard, glass-like material. **2.** The fusion of grains in clay products under high kiln temperatures, resulting in closure of pores and an impervious material. **3.** A process that transforms the chemical and physical characteristics of hazardous waste so that the treated residues contain hazardous material immobilized in a vitreous mass.

vitrified brick Glazed brick that is impervious to moisture and highly resistant to chemical corrosion.



vitrified-clay pipe

vitrified-clay pipe Glazed earthenware pipe favored for use in sewage and drainage systems because it is impervious to water and resistant to chemical corrosion.

V-joint *See* **V-shaped joint.**

void-cement ratio Volumetric ratio of air plus net mixing water to cement in a concrete or mortar mixture.

void ratio In a mass of granular material, the ratio of the volume of voids to the volume of solid particles.

voids The air spaces between particles in granular material such as sand, or a paste such as mortar.

void-solid ratio The ratio of the sum of the areas of window and door openings to the gross area of an exterior wall of a building.

volatile organic compounds Regulated compounds that lead to the formation of ozone and smog and may be hazardous to humans. VOCs contain carbon molecules and are volatile enough to evaporate from material surfaces into indoor air at normal temperatures.

volatility The tendency of a substance to vaporize, or "escape," from the liquid phase or from the surface of a solid to the vapor phase.

volt The unit of voltage or potential difference equal to the voltage between two points of a conducting wire carrying a constant current of one ampere, when the power dissipated between the points is one watt.

voltage A measurement of electrical potential for a building's circuits.

voltage control Device that maintains a constant, uniform voltage in electrical circuits.

voltage drop The difference in voltage between any two points in an electric circuit.

voltage, nominal A value assigned to a circuit or system for classification purposes. Operation may actually be possible within a range, and the nominal voltage is often the midpoint of that range.

voltage regulator A control device within an electrical system that automatically keeps the voltage supply constant despite variable line voltage at the point of input.

voltage relay A voltage monitoring device that detects changes in levels of current and controls the flow of electricity accordingly.

voltage-to-ground **1.** The voltage between a conductor in a grounded electric circuit and the point of the circuit that is grounded. **2.** The maximum voltage between a conductor in an ungrounded electric circuit and another conductor.

volt-ampere The product obtained by multiplying one volt times one ampere, equivalent to one watt in direct-current circuits and to one unit of apparent power in alternating current circuits.

voltmeter

voltmeter An instrument used to measure the voltage drop between any two points in an electric circuit.

volume batching The measuring of the constituent materials for mortar or concrete by volume.

volume damper Device installed in a duct system circuit to add resistance to the circuit for air volume balancing.

volume method of estimating cost A cost estimating method determined by multiplying an estimated cost per unit of volume by the volume of the building.

volumetric test **1.** A test to determine the integrity of an underground storage tank through review and comparison of tank volume. **2.** A test to determine the air content of fresh concrete.

volute **1.** The spiral-turned handrail detail at the first tread on some stairs. **2.** The spiral treatment that appears at the top of a column, usually Ionic.

vomitory An opening dividing a bank of seats to provide access to and egress from an aisle.

voussoir A wedge-shaped masonry unit in an arch or vault, the converging sides of which are cut along radii of the vault or arch.



voussoir

V-shaped joint (V-joint, V-tooled joint) **1.** A V-shaped horizontal joint in mortar, formed with a steel jointing tool, that serves to resist rainwater penetration. **2.** Two adjacent wood boards, with beveled or chamfered edges, that form a joint in the same plane.



V-shaped joint (V-joint, V-tooled joint)

V-tool A gauge with a V-shaped cutting edge.

vulcanization A chemical process in which a rubber compound becomes less plastic, more resistant to swelling by organic liquids, and more elastic, and its elastic properties are extended over a greater temperature range.

W

Abbreviations

w water, watt, weight, wicket, wide, width, work, with

W watt, west, western, width

w/ with

WA with average

WAF wiring around frame

WB welded base, water ballast, waybill

WBT wet-bulb temperature

WC water closet

WCLIB West Coast Lumber Inspection Bureau

wd wood, window

Wdr wider

WF wide flange, white fir

wfl waffle

wg wing, wire gauge

wh watt-hour

WH water heater

WHP water horsepower

whr watt-hour

whse, WHSE warehouse

WI wrought iron

WK week, work

wm wattmeter

W/M weight or measurement

WM wire mesh

w/o water-in-oil, without

WP waterproof, weatherproof, white phosphorus

wpc watts per candle

w proof waterproofing

wrc western red cedar

wrt wrought

WS weather strip

wsct/wains wainscoting

wt, Wt weight

WT water table, watertight

ww white wash, white woods

WWM welded wire mesh

WWPA Western Wood Products Association

Definitions

waferboard A panel product made of discrete wafers of wood bound together by resin, heat, and pressure. Waferboard can be made of timber species, such as aspen, that are not suitable for lumber or plywood manufacture.

waffle slab A reinforced concrete slab with equally spaced ribs parallel to the sides, having a waffle appearance from below.



waffle slab

wage rate Hourly rate of pay on which the employee's paycheck is calculated, agreed upon between the employer and employee.

Wagner fineness The fineness of Portland cement, expressed as total surface area in square centimeters per gram, determined by the Wagner turbidimeter apparatus and procedure.

wagon drill A movable rig for positioning and holding a pneumatic drill, consisting of a mast with a carrier for the drill and a supporting wheeled carriage.

wagon-head dormer A dormer with a semicircular roof.

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

wainscot The lower portion of an interior wall whose surface differs from that of the upper wall.

wainscot cap The finish molding at the top of wainscot.

waist The narrowest section of a column or similar building element.

wale (waler, whaler) **1.** Timber placed horizontally across a structure to strengthen it. **2.** Horizontal bracing used to stiffen concrete form construction and to hold studs in place.



wale (waler, whaler)

walk-in box A refrigerator or freezer large enough for one or more persons to enter to depositor retrieve food.

walking edger A concrete finishing tool mounted on a long handle and used to produce a radius at the edge of a concrete slab.

wall A vertical element used primarily to enclose or separate spaces.

wall anchor A steel strap used to attach a back-up surface to the masonry fascia.



wall anchor

wall beam **1.** A special form of reinforced concrete framing, used for some apartment buildings, in which walls between apartments are used as deep, transverse beams supporting one edge of a floor slab below and one above. The deep beams alternate between floors and between columns. **2.** A header bolted to a wall and used to support joists or beams.

wall-bearing construction A structural system where the weight of the floors and roof are carried directly by the masonry walls rather than the structural framing system.

wallboard A manufactured sheet material used to cover large areas. Wallboards are made from many items, including wood fibers and gypsum. In North America, the most common is gypsum board, a gypsum-based panel bound by sheets of heavy paper. It is used to cover interior walls and ceilings in place of wet plaster.

wall box (beam box, wall frame) **1.** A bracket fixed to a wall to support a structural member. **2.** A metal box set in a wall to house an electric switch or receptacle.

wall bracket A bracket fastened to a wall and used to support a structural member, pipe, an electric insulator, an electric fixture, or a section of scaffolding.



wall bracket

wall clamp A brace or tie used to connect two parallel walls to each other.

wall column A steel or concrete column fully or partly embedded in a wall.

wall covering Any material or assembly used as a wall finish and not an integral part of the wall.

wall crane A crane with a horizontal arm supported from a wall or columns of a building. The arm may support a trolley.

wall expansion A break designed into a wall to allow room for building materials to expand and contract with thermal conditions.

wall footing A strip of reinforced concrete that is wider than the wall it supports and thus distributes the wall load over a wider area.

wall form A retainer or mold erected to give the necessary shape, support, and finish to a concrete wall.

wall furring Strips of wood or shaped sheet metal attached to a rough wall to provide a plane on which lath and plaster, paneling, or wainscoting may be installed.



wall form

wall grille A perforated plate, casting, punched sheet, or frame used to conceal an opening, radiator, or the like, while allowing a passage for air.

wall guard A protective, resilient strip attached to a wall to protect the surface from carts, transporters, or other movable conveyors.

wall hanger A stirrup or bracket fixed to a wall and used to support one end of a horizontal member.

wall height The vertical distance from the top of a wall to its support, such as a foundation or support beam.

wall hook **1.** A special large nail or hook used as a beam anchor or used on a beam plate. **2.** A hook or bracket fixed in a masonry wall to hold downspouts, lightning rods, etc.

wall outlet An electric outlet mounted in a wall with a decorative cover.

wall plate The top plate in construction, placed on top of studs and bearing the joists of the next floor above.

wall puller A simple hand tool used to help position a stud wall or similar construction.

wall rib A longitudinal rib against an exterior wall of a vaulting compartment.

wall shaft A small column, supported on a corbel or bracket that appears to support a rib of a vault.

wall sign **1.** A sign mounted on, or fastened to, a wall. **2.** A sign attached to the exterior wall of a building and projecting not more than a code-defined distance.

wall spacer A metal tie used to hold forms in position until concrete has set.



wall spacer

wall tie A metal strip or wire used to tie masonry wythes together, or tie a masonry veneer to a wood or concrete frame or wall.

wall tile A glazed tile used in a wall facing.

wall-wash luminaire A luminaire located adjacent to or on a wall with most of its light directed onto the wall.

wane A defective edge of a board due to remaining bark or a beveled end. A wane is usually caused by sawing too near the surface of the log.

ward **1.** A baffle in a lock to prevent use of an unauthorized key. **2.** A division of a hospital or jail.

warehouse set The partial hydration of cement stored for a time and exposed to atmospheric moisture, or mechanical compaction occurring during storage. A partially hardened, unopened bag of cement.

warm-air heating system A heating system in which warm air is distributed through a single register or series of ducts. Circulation may be by convection (gravity system) or by a fan in the ductwork (forced system).



warm-air heating system

warning pipe An overflow pipe with an outlet located so that discharge can be readily observed.

warping A deviation of a slab or wall surface from its original shape, caused by temperature and/or moisture differentials within the slab or wall.

warping joint A longitudinal or transverse joint, with bonded steel or tie bars passing through it, with the sole function of permitting warping of pavement slabs when moisture and temperature differentials occur in the pavement.

warranty A premise made by a seller or contractor responsible for work performed under a contract that the work performed is fit for the purpose intended and is free from structural, electrical, mechanical and other defects.

warren truss (warren girder) A truss consisting of horizontal top and bottom chords, separated by sloping members, and without vertical pieces.



warren truss (warren girder)

wash The top surface of a building element, such as a coping or sill, intended to shed water.

washable Descriptive of a material that may be washed repeatedly without a noticeable deterioration in appearance or function.

wash boring A boring made in the earth by a rotary drill that uses water to stabilize the sides of the hole.

wash coat A thin, almost transparent coat of paint applied to a surface as a sealer or stain.

wash cut A beveled cut in a stone windowsill that diverts water away from the window and the structure.

washer **1.** A flat ring of rubber, plastic, or fibrous material, used as a seal in a faucet or valve or to minimize leakage, as in a threaded connection. **2.** A flat ring of steel that may be split, toothed, or embossed; used in threaded connections to distribute loads, span large openings, relieve friction, or prevent loosening.



washer

wash primer Any thin paint that promotes adhesion of the subsequent coat.

waste The difference between the quantity that must be included in an estimate and the quantity that is actually to be installed, added to the quantity as a percentage. Applicable to materials, waste should not be applied to labor or confused with productivity.

waste and overflow fitting A common bathtub fixture that provides one outlet for a tub drain and another in case water rises above a safe level.



waste and overflow fitting

waste-disposal unit An electrically operated device for grinding waste food and disposing of it through the plumbing drainage pipes.

waste heat recovery An economical measure that involves capturing the heat produced by a process in a cyclic process to serve another need, such as preheating combustion air.

waste management Activities undertaken to minimize, contain, control, store, transport, treat, or dispose of waste material.

waste pipe A pipe to convey discharge from plumbing pipes.

waste-to-energy Conversion of waste products to energy (steam, heat, or electricity) by incineration.

wastewater Water that has been used in a process and contains contaminants.

wasting (dabbing) Splitting of excess stone with a hand tool so that the resulting surfaces of block are nearly flat.

water-absorption The amount of water absorbed by a material under specified test conditions. Commonly expressed as a weight percent of the test specimen.

waterborne preservative Preservative salts dissolved in water and transferred to the wood during the treating process.

water-cement ratio The ratio of the amount of water, exclusive only of that absorbed by the aggregates, to the amount of cement in a concrete or mortar mixture. The ratio is preferably stated as a decimal by weight.

water closet (WC, flushable closet, toilet) A plumbing fixture used to receive human wastes and flush them to a waste pipe.



water closet (WC, flushable closet, toilet)

water crack A fine crack in a coat of plaster, caused by applying a coat over a previous coat that had not dried sufficiently or by using plaster with a water content that is too high.

water gauge A manometer filled with water.

water-gel explosive A wide variety of explosives, all containing water and ammonium nitrate, used for blasting. The explosives are sensitized with an explosive, such as TNT or smokeless powder, with metals such as aluminum, or with other fuels. They may be premixed at a plant or site-mixed immediately prior to loading in a blast hole.

water hammer A loud thumping noise in a water service line due to the surge of suddenly checked water.

water level A simple device used to see that surfaces are level. Most often a long (up to 50′), thin plastic tube filled with water.

water-level control A control on a boiler used to maintain the water at a safe level.

water lime A hydraulic lime or cement that will set under water.

waterline The highest water level in a cistern or flush tank to which the shutoff should be adjusted.

water main A main supply pipe in a water system providing water for public or community use.



water main

water outlet **1.** Any opening or end of pipe used to discharge water to a plumbing fixture, boiler, or other device. **2.** An opening through which water is discharged to the atmosphere.

waterproof adhesive An adhesive that, when properly cured, is not affected by water.

"waterproofed" cement Cement interground with a water-repellent material such as calcium stearate.

waterproofing Any of a number of materials applied to various surfaces, e.g., a building foundation, to prevent the infiltration of water.



waterproofing

water reactive A substance that generates heat or gas in the presence of water.

water-reducing agent A material that either increases workability of freshly mixed mortar or concrete without increasing water content, or maintains workability with a reduced amount of water; the effect being due to factors other than air entrainment.

water-repellent cement A hydraulic cement having a water-repellent agent added during the process of manufacture, with the intention of resisting the absorption of water by the concrete or mortar.

water-repellent paper Gypsum board paper surfacing that has been formulated or treated to resist water penetration.

water retentivity The property of mortar that prevents rapid loss of mix water by absorption.

water ring A perforated manifold in the nozzle of dry-mix shotcrete equipment through which water is added to the materials.

water-saving toilet A toilet that uses between 1.6 and 3.5 gallons per flush.

water seal The water in a trap acting as a seal against the passage of gases.

water-service pipe The part of a water-service main owned by the water department.

watershed The area of land that drains naturally into a stream or complex of streams.

water softener A device to remove calcium and magnesium salts from a water supply, usually by ion exchange.

waterstop A thin sheet of metal, rubber, plastic, or other material inserted across a joint to obstruct the seeping of water through the joint.



waterstop

water-supply stub A vertical supply pipe that supplies fixtures and that reaches less than one story in height.

water-supply system **1.** The system that supplies water throughout a building, including the service pipe(s), distribution and connecting pipes, fittings, and control valves. **2.** The system that supplies water to units in a community, including reservoirs, tunnels, and pipelines.



water-supply system

water table **1.** The top surface of groundwater. **2.** A horizontal, sloped ledge on an exterior wall with a drip molding to prevent water from running down the outside of the wall below.

water tap (faucet) An outlet valve for water.



water tap (faucet)

watertight A joint, enclosure, or assembly that is designed to prohibit the entry of water.

water tube boiler A boiler in which water circulates through the tubes, while combustion gases surround the tubes.

water vapor diffusion The movement of water vapor through permeable materials to areas of different water vapor pressure.

water vapor transmission The rate of water vapor flow, under steady specified conditions, through a unit area of a material, between its two parallel surfaces. Metric unit of measurement is 1 g/24 h. × m^2 × mm Hg.

watt A unit of power equal to the power dissipated in an electric circuit in which a potential difference of 1 volt causes a current flow of 1 ampere. The power required to do work at the rate of 1 joule per second.

watt-hour A unit of work equivalent to the power of 1 watt operating for 1 hour, which is equal to 3,600 joules.

wattmeter A calibrated instrument that measures electric power in watts.

wave front The surface of the wave sphere created when sound waves radiate from the source in all directions, forming a spherical shape.

wavelength The distance between two successive points in a sound or light wave that are characterized by the same phase of oscillation.

wax A material obtained from vegetable, mineral, and animal matter that is soluble in organic solvents, and solid at room temperature. Wax is applied in a liquid or paste form on wood and metal surfaces to provide gloss, and to protect the surface.

wearing course A topping or surface treatment to increase the resistance of a concrete pavement or slab to abrasion.

weather **1.** The length of shingle or tile that is exposed, as measured along the slope of a roof. **2.** To deteriorate or discolor when exposed to the weather. **3.** To slope a surface for the purpose of shedding rainwater.

weatherboard **1.** Boards or siding lapped to shed water. **2.** A projecting member attached to the bottom rail of an external door to divert water from the sill or threshold.



weatherboard

weathered **1.** Descriptive of a surface exposed long enough that distinct weathering has taken place. **2.** Having an upper surface that is sloped to shed water.

weathering **1.** Changes in color, texture, strength, chemical composition, or other properties of a natural or artificial material due to the action of the weather. **2.** The mechanical or chemical disintegration and discoloration of the surface of wood, caused by exposure to light, the action of dust and sand carried by the wind, and the alternate shrinking and swelling of the surface fibers due to continual variation in temperature and moisture content brought on by changes in the weather.

weather resistance The ability of a material or coating to resist weathering.

weatherseal channel A channel installed, flanges downward, on the top of an exterior door.

weatherstrip A strip of wood, metal, felt, plastic, or other material applied at an exterior door or window to seal or cover the joint made by the door or window with the sill, casings, or threshold.

weather-struck joint (weathered joint) A horizontal masonry joint sloped from a point inside the face of the wall to the face of the wall so the joint will shed water.



weather-struck joint (weathered joint)

weaving The alternate lapping of shingles on opposite surfaces when two adjacent roofs intersect.

web **1.** That part of a beam or truss between the flanges or chords, used mainly in resisting shear stresses. **2.** The walls connecting the face shells of a hollow concrete masonry unit.

web crippling Local failure of the web of a structural member caused by a concentrated load.



web

web member In a truss, a secondary structural member that joins the top and bottom chords.

web plate A steel plate forming the web of a built-up girder truss, or beam.

web reinforcement Reinforcement placed in a concrete member to resist shear and diagonal tension.

web splice A splice joining two web plates.



web reinforcement

web stiffener **1.** A vertical steel shape attached to the web of a structural member and used to prevent web buckling. **2.** Blocking added to the web of a composite wood structural member to prevent web buckling.

wedge A piece of wood or metal tapering to a thin edge, used to adjust elevation or tighten formwork.



web stiffener

wedge anchor A wedging device used in the anchorage of a tendon in posttensioned, prestressed concrete.

weep cut A groove cut in the underside of a horizontal board or masonry unit that extends from an exterior wall to keep water from moving back toward the wall.

weep hole (weeps) **1.** A small hole in a wall or window member to allow accumulated water to drain. The water may be from condensation and/or surface penetration. **2.** A small hole in a retaining wall located near the lower ground surface. The hole drains the soil behind the wall and prevents build-up of water pressure on the wall.

weighted average An average in which certain entries, usually at the extremes of the range of values, are manipulated so a number is obtained that is believed to be more representative of the true mean than that obtained by straight averaging.

weir A structure across a ditch or stream used for measuring, or for diverting the flow of water.

weir head The depth of water above the top of a flat weir, or above the bottom of a notch in a notched weir.

weld **1.** To build up or fasten together, as with cements or solvents. **2.** To fasten two pieces of metal together by heating them until there is a fusing of material, either with or without a filler metal.

welded butt splice A reinforcing bar splice made by welding the butted ends.

welded cover plate A cover plate welded to the flange of a structural member, usually to increase strength in the middle length of a span.

welded reinforcement Concrete-reinforcing steel joined by welding, and most often used in columns to extend vertical bars.

welded-wire fabric (welded-wire mesh) A series of longitudinal and transverse



welded-wire fabric (welded-wire mesh)

W

wires of various gauges, arranged at right angles to each other and welded at all points of intersection; used for concrete slab reinforcement.

welding cables The pair of cables supplying electric energy for use in welding. One lead connects a welding machine with an electrode; the other lead connects the machine with the work.

welding fittings Wrought steel elbows, tees, reducers, saddles, and the like, beveled for butt welding to pipe. Forged fittings with hubs or with ends counter-bored for fillet welding to pipe; they are used for small pipe sizes and high pressures.


welding fitting

welding neck flange A flange with a long neck that is beveled for butt-welding to pipe.

welding nozzle A stub-pipe that is shop-welded to a vessel to facilitate welding a connecting pipe in the field.

welding rectifier Equipment used in arc welding to convert AC power to DC power.

welding rod Filler metal in the form of wire or rod used in gas welding and brazing and in some arc welding processes.

welding screw A screw with lugs or weld projections on the top or underside of the head to facilitate attaching the screw to a metal part by resistance welding.

weldment Any assembly made by welding parts together.

weld metal That part of a weld that was melted while welding.

weld nut A nut designed to be attached to a part by resistance welding.

well (wellhole) **1.** Any enclosed space of considerable height, such as an air shaft or the space around which a stair winds. **2.** A correction device for ground water. **3.** A wall around a tree trunk to hold back soil. **4.** A slot in a machine or device into which a part fits.

well drill A rotary drill mounted on a truck and used to drill for water.

well-graded aggregate Aggregate with a particle-size distribution producing maximum density, or minimum void space.

well point A perforated pipe surrounded by pervious soil to permit the pumping of groundwater.

well-point system A series of well points connected to a header and used to drain an area or to control groundwater seepage into an excavation.


well-point system

W

welt **1.** A seam in sheet metal, formed by folding over the edges of two sheets, interlocking the folded portions, and flattening the formed seam. **2.** A strip of wood fastened over a seam, joint, or shaped piece fastened over an angle for reinforcing.


welt

welting strip A strip of sheet metal at the intersection of the roof and a vertical surface. One edge of the strip is fastened to the roof, and the other edge is bent to lock with the lower edge of a vertical sheet.

West Coast Lumber Inspection Bureau (WCLIB) One of seven regional grading agencies in North America that are authorized to write and publish grading rules for lumber.

Western Wood Products Association One of seven regional grading agencies in North America that are authorized to write and publish grading rules for lumber.

wet-bulb depression The difference between the dry-bulb and the wet-bulb temperatures.

wet-bulb temperature **1.** The reading on a thermometer whose bulb is enclosed in a layer of wet fabric. **2.** The ambient temperature of an object cooled by evaporation.

wet-bulb thermometer A thermometer in which the bulb is enclosed in a layer of wet fabric.

wet construction Any construction using materials that are placed or applied in other than a dry condition, as in concreting or plastering.

wet mix Concrete containing too much water, immediately evidenced by a runny consistency.

wet-mix shotcrete Shotcrete in which all ingredients, including mixing water, are mixed before introduction into the delivery hose. The shotcrete may be pneumatically conveyed or moved by displacement.

wet process In the manufacture of cement, the process in which the raw materials are ground, blended, mixed, and pumped while mixed with water. The wet process is chosen where raw materials are extremely wet and sticky, making drying before crushing and grinding difficult.

wet process hardboard Hardboard manufactured by a process in which a wood slurry is combined with a resin binder; and is then dried, first on a screen and later under pressure. The pressure imparts high density to the board and also sets the binder.

wet rot Decay of wood, in the presence of moisture and warmth, as a result of attack by fungi.

wet sanding Applying an abrasive to a surface while one or both are wet. Wet finishing reduces dust and keeps sanding machinery cleaner.

wet screeds Concrete strips placed beforehand at the proper elevation to act as height guides when pouring a concrete slab.

wet screening Screening to remove from fresh concrete any aggregate particles larger than a certain size.

wet sieving Use of water during sieving of a material on a No. 200 or (even finer) No. 325 sieve.

wet standpipe system A standpipe system filled with water at design pressure, ready for immediate use.


wet standpipe system

wet strength The measured strength of an adhesive joint after it has been submerged in a liquid.

wettability The degree to which a surface will absorb a liquid poured upon it.

wettest stable consistency The condition of maximum water content at which cement grout or mortar will adhere to a vertical surface without sloughing.

wetting 1. The soaking of asbestos materials to diminish the level of air contamination they give off when disturbed. The water is mixed with saturants and surfactants before it is applied to the asbestos. **2.** Coating a base metal with filler metal prior to soldering or brazing.

wetting agent A substance capable of lowering the surface tension of liquids, facilitating the wetting of solid surfaces and permitting the penetration of liquids into the capillaries.

wet-use adhesive Adhesives used in glue-laminated timber that will perform satisfactorily under a wide variety of uses, as well as exposure to weather and dry atmosphere.

wheelabration The application of steel abrasives in the form of grit or shot to clean a surface.

wheelbarrow A hand cart with one wheel in front plus two legs and two handles in back; used to move materials short distances.

wheel ditcher A trench digger consisting of a vehicle equipped with a large wheel on which buckets are mounted.

wheel excavator (continuous excavator) 1. A self-propelled unit for excavating a bank with buckets mounted on wheels. The earth is deposited on a conveyor belt for loading up hauling units. **2.** Any power-driven machine used in excavation that moves on wheels, rather than crawlers.



wheel excavator (continuous excavator)

wheel trencher A trencher using a rotating wheel made of two ring plates with buckets every 20° to 30° around the circumference.



wheel trencher

whetstone A piece of natural or manufactured abrasive stone used to sharpen cutting tools.

whip A slang term that describes the vertical movement of improperly secured underlayment.

white coat (finish coat) A lime-putty plaster coat with a troweled finish.

white lead Basic lead carbonate, white in color; used as a pigment in exterior paints, ceramics, and putty.

white Portland cement Portland cement made from materials with low iron content, used to produce concrete or mortar that is white in color.

white roof systems Roofing systems that reflect heat and have proven to reduce the net cooling requirements of a facility by as much as 20%.

white rot A type of decay in wood caused by a fungus that leaves a white deposit.

whitewash Water added to quicklime or slaked lime, whiting, and glue and applied like paint, leaving a white coating.

whiting Calcium carbonate pigment, used as an extender in paint, putty, and whitewash.

Whitney strain diagram The assumed strain distribution of a reinforced concrete member in the yield state that is used in ultimate strength design.

whole-brick wall A brick wall having a thickness equal to the length of one brick.



whole-brick wall

whole-building Integration of a building's systems to maximize sustainable and/or economic functioning by considering many factors including use of energy and other resources, building materials, site preservation, and indoor air quality so that a structure can run at its maximum efficiency; enhance user health, comfort, and productivity; and have the least impact on the environment.

whole design solution A design approach that considers and integrates all building systems, starting with the early design stages—for optimum efficiency and sustainability in the structure. Also holistic, integrated or whole building design.



whole-house fan

whole-house fan A fan (typically centrally located in the uppermost ceiling of a house) that draws fresh outside air into the living space, flushes hot air up to the attic, and exhausts it to the outside.

wicking The tendency of water or any liquid to rise above an established level to saturate a porous solid.



wide-flange beam

wide-flange beam A hot-rolled steel beam having a cross section resembling an H and having wider flanges than an I-beam.

wide-throw hinge A rectangular hinge having extra-wide leaves.



wide-throw hinge

Williot diagram A graphical method used to determine deflections of trusses.



winch

winch A stationary hoisting machine having a rotating drum around which a cable, rope, or chain is wrapped.

windage loss Water removed by circulating air, as in a cooling tower.

wind brace A brace provided in a frame to support the frame against wind loads.

wind column A vertical support to a wall system that is designed to help the system withstand wind loads.

wind drift The horizontal deflection of a structure as a result of wind.

wind electric system A single turbine, smaller than the utility-scale models, but much more efficient than the old-fashioned windmill, producing clean, affordable electricity for a rural home, farm, or business.

winder A tread that is used where a stair turns a horizontal angle, or in a spiral stair; shaped like a wedge or truncated wedge.

windlass A device for lifting heavy objects, usually consisting of a horizontal drum turned by a lever or crank. A cable runs from the object over a pulley to the drum where a cable is wound or unwound to move the object.

wind load The horizontal load used in the design of a structure to account for the effects of wind.



window

window **1.** A normally glazed opening in an external wall to admit light and, in buildings without central air-conditioning, air. **2.** An assembly consisting of a window frame, glazing, and necessary appurtenances. **3.** A small opening in a wall, partition, or enclosure for transactions, such as a ticket window or information window.

window cleaner's anchor An anchor, fastened near a window on an outside wall of a multistory building, to which a person washing the window from the outside can attach a safety belt.

window cleaner's platform A platform suspended from a trolley on the roof of a multistory building used for outside window-washing and maintenance.

window frame The fixed part of a window assembly attached to the wall and receiving the sash or casement and necessary hardware.



window frame

window glass (sheet glass) A soda-lime-silica glass made in continuous sheets of varying thickness and cut to size as required.

window hardware All the devices, fittings, or assemblies necessary to operate a window as intended. Window hardware may include catches, cords, fasteners, hinges, handles, locks, pivots, pulls, pulleys, and sash weights.

window lift (sash lift) A handle fastened to the lower sash of a sliding window for use in moving the sash up or down.

window of time analysis A method of measuring labor productivity losses on a specific project by comparing labor productivity achieved during a period of time when work activities are subject to disruptive events and conditions, versus productivity during a period of time without disruption.

window schedule A tabulation, usually on a drawing, listing all windows on a project; and indicating sizes, number of lights, type of sash and frame, and hardware required.

window spring bolt A spring bolt, used on a sash that is not counter-balanced, that holds the sash in a desired position.



window wall

window tinting Film applied to windows to reduce the amount of solar heat transmission through the glass by increasing the solar reflection (not necessarily visible reflection) and solar absorption of the glass.

window trim The finished casing around a window.

window wall An exterior curtain wall using a frame containing windows that may be fixed or operable. The glazing may be clear, tinted, and/or opaque.

window well A well dug outside of a below-grade window, commonly a basement window, to allow it to operate.

wind power Energy from wind, usually collected by wind turbines.

wind pressure The pressure produced when wind blows against a surface.

windrow **1.** A ridge of loose soil, such as that produced by the spill off of a grader blade. **2.** A row of leaves or snow heaped up by the wind.

wind stop **1.** A weatherstrip used around a door or window. **2.** A strip of wood or metal that covers the joint where a sash or casement meets a stile. **3.** Any wood or metal strip used to cover a crack in an exterior wall of a building.

wind tunnel A structure through which a controlled stream of wind is directed at a model in order to study the probable effects of wind on a structure.



wing

wind uplift The upward component of the force produced as wind blows around or across a structure or an object.

wing **1.** A section or addition extending out from the main part of a building. **2.** The offstage space at a side of a stage. **3.** One of the four leaves of a revolving door.

wing nut A nut provided with wing-like projections to facilitate turning by fingers and thumb.

wing pile A bearing pile (post), usually of concrete, widened at the upper portion to form part of a sheet pile wall.

wing screw A screw provided with wing-like projections to facilitate turning by fingers and thumb. A wing screw is often used to secure windows against unauthorized entry.

wing wall **1.** A short section of wall at an angle to a bridge abutment, used as a retaining wall and to stabilize the abutment. **2.** A short section of wall used to guide a stream into an opening, such as at a culvert or bridge.


wing wall

wiped joint A wiped lead joint connecting two lead pipes.

wire A drawn metal strand or filament.

wire cloth A stiff fabric of woven wire, usually having a larger mesh than insect screen material, and used as reinforcing in plaster, in sieves, and as a leaf catcher in gutters. The number of openings per square inch designates the fineness of the mesh.

wire, cold-drawn Wire made from the rods hot-rolled from billets and then cold-drawn through dies.

wire comb A tool with long wire teeth, used to scratch a coat of wet plaster to increase the bond of a subsequent coat.

wire-cut brick Brick that has been extruded to shape and then cut to length with wire before firing.

wire gauge **1.** The diameter of a wire as defined by several different systems. Ordinarily, the thicker the wire is, the smaller the gauge number is. **2.** A device for measuring the thickness of a wire; usually consists of a metal sheet with standard-sized notches on one or more edges.

wire glass Sheet glass with wire mesh embedded in the glass to prevent shattering.

wire holder An electrical insulator having a screw or bolt for fastening the insulator to a support.

wire lath A welded-wire mesh used as a base for plaster.


wire lath

wire nail A very thin nail with a small head, often used as a finishing nail.

wire nut A connector for two or more electric conductors, made in the form of a plastic cap with an internal spring-thread. It is turned over the parallel or twisted ends of the conductor wires.


wire nut

wire rope A rope made of twisted steel strands laid around a central core.

wire saw A machine for sawing stone using a rapidly moving continuous wire carrying a slurry of sand or other abrasive material.

wireway A raceway with a removable cover for access to wires inside.

wire winding Application of high tensile wire, wound under tension by machines, around concrete circular or dome structures to provide tension reinforcing.

wiring Installing or connecting electrical components. Also refers to systems of wires for electrical work, such as lighting, switchboards, and so forth.

wiring box A box used in interior electric wiring at each junction point, outlet, or switch, that serves as protection for electric connections and as a mounting for fixtures or switches.


wiring box

witness corner A marker set on a property line near to, but not at, a corner. Its relation to the corner is recorded.

wobble-wheel roller A pneumatic compactor consisting of a weighted bed mounted on a series of wheels that are loosely assembled, and allowed to work the surface of a soil.

wood block floor A finished floor consisting of rectangular blocks of a tough wood such as oak, set in mastic with the end grain exposed, usually over concrete slab. A wood block floor is used where very heavy traffic and heavy loads are expected.

wood-cement concrete A Portland cement concrete using sawdust and wood chips as aggregate.


wood-cement concrete

wood-cement particle (WCP) board A high-density board manufactured in Europe for use on exteriors, or where fire resistance is needed. Wood particles are combined with Portland cement, or another mineral, as a binder.

wood-fibered plaster A calcined gypsum plaster containing shredded or ground wood fiber added during manufacture.

wood filler A liquid or paste compound used to fill pores or checks in wood before finishing.

wood fire-retardant treatment The impregnation of wood or wood products with special solutions to reduce the flame spread of the finished product.

wood firestop Wood pieces that are placed between framing members in a wall to slow the spread of fire.

wood flooring Flooring consisting of dressed and matched boards.

wood flour A finely ground, dried, wood powder that is used in plastic wood as an extender. It is also employed in some glues, and in the molding of plastics.

wood-frame construction A type of construction where floors and roofs, as well as exterior and other bearing walls are of wood, rather than masonry.

wood gutter A gutter, under the eaves of a roof, made from a solid piece of wood or built-up boards.


wood gutter

wood lath Narrow strips of wood used as a base for plaster.

wood molding Wood strips that are factory-shaped to commercially available patterns.

wood oil **1.** Tung oil used in the manufacture of varnish, putty, etc. **2.** An oleoresin used for caulking and waterproofing.


wood molding

wood preservative Any chemical preservative for wood, applied by washing-on or pressure impregnating. Products used include creosote, sodium fluoride, copper sulfate, and tar or pitch.

wood screw A threaded fastener that cuts its way into wood when turned under axial pressure.



wood screw

wood slip A wooden nailing strip fixed in a masonry or concrete wall as a means of attaching wood trim or furring strips.

wood stud anchor (nailing anchor) A metal clip attached to the inside of a door frame and used to secure the frame to a wood stud partition.

wood treatment Treatment of wood with a preservative to prevent or retard its decay.

woodwork Work produced by carpenters and woodworkers, especially the finished work.



woodwork

work **1.** All labor and materials required to complete a project in accordance with the contract documents. **2.** The product of a force times the distance traveled.

workability That property of freshly mixed concrete or mortar that determines the ease and homogeneity with which it can be mixed, placed, compacted, and finished.

work breakdown structure (WBS) A hierarchical breakdown of a project that contains successive levels of detail. Provides a way to incorporate project details as they become available without having to prepare an entirely new estimate or budget at each new level.

work capacity The greatest volume in number and/or size of construction projects that a contractor can manage efficiently without increasing the overhead costs.

workflow The sequences of task-related communication among people (normally the project team) to accomplish sequences of tasks and the needed data flows to support those sequences.

working (movement) The alternate swelling and shrinking of wood caused by changes in its moisture content induced by variations in the humidity of its environment.

working life The length of time a liquid resin or adhesive remains useful after the ingredients have been mixed.

working load Forces normally imposed on a member in service.

working stage A section of an assembly room or auditorium partially cut off from the audience section by a proscenium wall. It is equipped with some or all of the following: scenery loft, gridiron, fly gallery, and lighting equipment.

working stress Maximum permissible design stress using working stress design methods.

working stress design A method of proportioning structures or members for prescribed working loads at stresses well below the ultimate, and assuming linear distribution of flexural stresses.

work light **1.** A light in a theater used to provide illumination for rehearsing, scene shifting, or other work onstage or backstage. **2.** A lamp in a protective cage, and having a long, heavy, flexible cord; used to provide temporary illumination in work areas.



work light

workmanship The quality of work performed.

work package The grouping of tasks or scopes of work during the procurement phase that can be contracted together for coordination and economy of scale.

work plane In lighting, the plane at which work is usually done and at which the level of illumination is specified and measured.

worksheet The paper on which the calculations supporting the final estimate are recorded.

worm-drive saw A circular power saw turned by a worm-gear drive. It is heavier and produces more torque on the blasé than a standard circular saw.

worm-drive saw

woven valley A roof valley where shingles or other roofing materials from both sides of the valley are woven together as they are applied by overlapping alternate courses.



woven valley

woven-wire fabric A prefabricated steel reinforcement for concrete composed of cold-drawn steel wires mechanically twisted together to form hexagonally shaped openings.

wrap-around hinge An offset hinge attached to the rabbeted rail of a door or window, providing increased surface area for mounting.



wrap-around hinge

wrapping A method of applying narrow strips of veneer around a curved surface, such as a piece of furniture.

wreath A short, curved portion of a stair handrail that joins the newel post to the rail.

wrecking ball A heavy steel ball or concrete mass on a heavy chain or cable swung by a crane to demolish parts of a structure.

wrecking strip A small piece or panel fitted into a formwork assembly in such a way that it can be easily removed ahead of main panels or forms, making it easier to strip those major form components.

wrench A hand tool consisting of a handle and a jaw at one end; used to turn or hold a bolt, nut, pipe, or fitting. The jaw may be shaped for a specific-sized object or may be adjustable.


wrench

wrinkling (crinkling, reveling) **1.** The distortion in a paint film that appears as ripples and may be deliberately induced as a decorative effect or accidentally caused by drying conditions or paint applied too thickly. **2.** The rippling or crinkling of the surface of an adhesive, usually not affecting performance. **3.** The rippling of an area of veneer, caused by lack of contact with the adhesive.

wrought Descriptive of metals or metalwork shaped by hammering with tools.

wrought iron **1.** Nearly pure ductile iron with a very small percentage of silica throughout. Once the surface iron decomposes, the silica surfacing prevents further oxidation. Wrought iron is no longer commercially available. **2.** A number of easily welded or wrought irons with low impurity content used for water pipes, tank plates, or forged work.


W-truss

wrought nail A nail wrought by hand, often having a head with a decorative pattern.

wrought timber Wood that has been planed on one or more surfaces.


wye

W-truss A wood roof truss with the web members in the shape of a "W."

wye A pipe fitting with a side outlet that is any angle other than 90° to the main run or axis.

wythe (leaf) Each continuous vertical section of a wall one masonry unit in thickness.


wythe

X

Abbreviations

X experimental

XBAR crossbar

XEPS extruded expanded polystyrene

XH, X HVY extra heavy

XL extra large

xr without rights

X STR extra strong

xw without warrants

XXH double extra heavy

Definitions

X-brace (cross brace) A paired set of sway braces.



X-brace (cross brace)

xeriscaping Landscaping featuring native, drought-tolerant, well-adapted plant species, especially in dry climates, to avoid the need for irrigation. Xeriscaping typically calls for less fertilizer and fewer pest control measures than traditional landscapes.

xonolite Calcium silicate monohydrate (C_3S_5H), a natural mineral that is readily synthesized at 150°C to 350°C under saturated steam pressure. Xonolite is a constituent of sand-lime masonry units.

x-ray diffraction **1.** The diffraction of x-rays by substances having a regular arrangement of atoms. **2.** A phenomenon used to identify substances having such structure.

x-ray fluorescence Characteristic secondary radiation emitted by an element as a result of excitation by x-rays, used to yield a chemical analysis of a sample.

x-ray protection Lead encased in sheetrock or plaster to prevent the escape of radiation from the encased room.

xylol An aromatic hydrocarbon distilled from coal tar, used as a solvent for paints and varnishes.

X

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

Y

Abbreviations

y yard

Y yttrium, wye, Y-branch

yd yard

yp yellow pine

YP yield point

YR year

YS yield strength

Definitions

yakima pine *See* **ponderosa pine**.

yard **1.** A unit of length in the English system equal to $3'$. **2.** A measure of concrete. One cubic yard = $3' \times 3' \times 3'$ in volume, or 27 cubic feet. **3.** A term applied to that part of a plot not occupied by the building or driveway.

yardage **1.** An amount of excavated material equal to the volume in cubic yards. **2.** An area of surface (two dimensions) measured in square yards.

yard drain A drain in a pavement or earth surface, used to drain surface water.

yard lumber (general building construction lumber) Lumber graded according to its size, length, and intended use, stockpiled in a lumber yard.

Y-branch (wye branch) A plumbing system branch, in the shape of a Y.

yelm A bundle of reeds or straw used as thatching material for a roof.

Y-fitting (wye fitting) A pipe fitting in the shape of a Y. One arm is usually at 45° to the main fitting and may be of reduced size.



Y-fitting

yield **1.** The volume of freshly mixed concrete produced from a known quantity of ingredients. **2.** The total weight of ingredients divided by the unit weight of the freshly mixed concrete. **3.** The number of product units, such as block, produced per bag of cement or per batch of concrete. **4.** A rate of return as calculated by the profit earned on an investment over a specified period of time.

yield point **1.** The point at which a stressed material begins to exhibit plastic properties. **2.** The point beyond which the material will not return to its original length.

yield strength The stress, less than the maximum attainable, at which the ratio of stress to strain has dropped well below its value at low stresses, or at which a material exhibits a specified limiting deviation from the usual proportionality of stress to strain.

Y-level A surveyor's level with the telescope and level supported by Y-shaped fittings. The telescope can be removed and reversed in order to average out internal sources of error.



yoke

yoke **1.** A tie or clamping device around column forms or over wall or footing forms to keep them from spreading as a result of lateral pressure of fresh concrete. **2.** Part of a structural assembly for slipforming that keeps the forms from spreading and transfers form loads to the jacks. **3.** A collar for supporting pipe. **4.** A soil pipe fitting in the shape of a Y. **5.** Pipe assembly used to install a water meter.

yoke vent **1.** A pipe connecting upward from a soil or waste stack to a vent stack for venting. **2.** A vertical or 45° relief vent of the continuous waste and vent type formed by the extension of an upright wye-branch inlet of the horizontal branch to the stack. Referred to as a *dual yoke vent* when two horizontal branches are thus vented by the same relief vent.

Young's modulus *See* **modulus of elasticity**.

Y-shaped fitting Plumbing fitting in the shape of a Y. Also called a wye.

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

c25.indd 353 06/09/12 9:11 AM

Z

Abbreviations

z zero, zone

Z modulus of section

ZI zone of interior

Zn azimuth, zinc

Definitions

Z-bar A Z-shaped member that is used as a main runner in some types of acoustical ceiling.



Z-bar

Z-bar flashing Z-shaped flashing installed above horizontal door or window trim to keep rainwater from seeping into a structure.

zee A light-gauge member with a Z-like cross section. The flanges of the Z are approximately at right angles to the web.



zee

zeolite A group of hydrous aluminum silicate minerals or similar synthetic compounds used in water-softening equipment.

zero lot line A form of cluster housing development in which individual dwelling units are placed on separately platted lots with very small yards and in some there is no side yard. They may be attached to one another, but not necessarily.

zero-slump concrete Concrete of stiff or extremely dry consistency showing no measurable slump after removal of the slump cone.

zero-water urinal An energy-efficient, wall-mounted urinal that uses no running water, other than for occasional servicing to clean the unit.

z flashing Z-shaped metal flashing applied between panels of plywood siding to shed water.

z-furring channel A z-shaped, galvanized steel track used to mechanically attach blanket or rigid plastic foam insulation to interiors of exterior walls. Also used to attach drywall to concrete, brick, concrete block, and tile.

zigzag rule A folding ruler made of pieces connected by a pivot.

zinc A metallic element used for galvanizing steel sheet and steel or iron castings, as an alloy in various metals, as an oxide for white paint pigment, and as a sacrificial element in a cathodic protection system. Characterized by its brittleness in ordinary temperatures.



z flashing

zinc dust Zinc ground to a fine powder and used as a pigment in priming paints, especially those for use on galvanized surfaces.

zinc oxide (zinc white) A pigment used in paints to provide durability, color retention, and hardness, and to improve sag resistance.

zigzag rule

zone **1.** A space or group of spaces in a building with common control of heating and cooling. **2.** A form of public control over land use. **3.** An area covered by a sprinkler system.

zoned building design Separating areas of a facility by establishing a series of clearly discernible zones to control access.

zone valve A control device for the flow of water or steam to areas, or zones, of a building.

Entries marked with an asterisk (*) are reprinted with the permission of AACE International. Copyright © by AACE International; all rights reserved.

Appendix: Symbols

Lighting Outlets

	Ceiling surface incandescent fixture
	Wall surface incandescent fixture
	Ceiling recess incandescent fixture
	Recess incandescent fixture
	Standard designation for all lighting fixtures; A= fixture type, 3 = circuit number, b = switch control
	Ceiling blanked outlet
	Wall blanked outlet
	Ceiling electrical outlet
	Wall electrical outlet
	Ceiling junction box
	Wall junction box
	Ceiling lamp holder with pull switch
	Wall lamp holder with pull switch
	Ceiling outlet controlled by low voltage switching when relay is installed in outlet box
	Wall outlet—same as above
	Outlet box with extension ring
	Exit sign with arrow as indicated
	Surface fluorescent fixture
	Pendant fluorescent fixture
	Recessed fluorescent fixture
	Wall surface fluorescent fixture
	Channel mounted fluorescent fixture
	Surface or pendant continuous row fluorescent fixtures
	Recessed continuous row fluorescent fixtures
	Incandescent fixture on emergency circuit
	Fluorescent fixture on emergency circuit

Receptacle Outlets

	Single receptacle outlet
	Duplex receptacle outlet
	Duplex receptacle outlet × indicates above counter max height = 42″ or above counter
	Weather proof receptacle outlet
	Triplex receptacle outlet
	Quadruplex receptacle outlet
	Duplex receptacle outlet—split wired
	Triplex receptacle outlet—split wired
	Single special purpose receptacle outlet
	Duplex special purpose receptacle outlet
	Range outlet
	Special purpose connection—dishwasher
	Explosion-proof receptacle outlet. max. height = 36″ to [cl]
	Multi-outlet assembly
	Clock hanger receptacle
	Fan hanger receptacle
	Floor single receptacle outlet

	Floor duplex receptacle outlet
	Floor special purpose outlet
	Floor telephone outlet—public
	Floor telephone outlet—private
	Underfloor duct and junction box for triple, double, or single duct system as indicated by number of parallel lines
	Cellular floor header duct

Switch Outlets

S	Single pole switch, max. height = 42″ to [CL]
S_2	Double pole switch
S_3	Three-way switch
S_4	Four-way switch
S_D	Automatic door switch
S_K	Key operated switch
S_P	Switch and pilot lamp
S_{CB}	Circuit breaker
S_{WCB}	Weatherproof circuit breaker
S_{MC}	Momentary contact switch
S_{RC}	Remote control switch (receiver)
S_{WP}	Weatherproof switch
S_F	Fused switch
S_L	Switch for low voltage switching system
S_{LM}	Master switch for low voltage switching system
S_T	Time switch
S_{TH}	Thermal rated motor switch

S_{DM}	Incandescent dimmer switch
S_{FDM}	Fluorescent dimmer switch
	Switch and single rceptable
	Switch and double recpetacle
 S_A	Special outlet circuits

Institutional, Commercial, and Industrial System Outlets

	Nurses' call system devices—any type
	Paging system devices—any type
	Fire alarm system devices—any type
	Fire alarm manual station—max. Height = 48″ to [CL]
	Fire alarm horn with integral warning light
	Fire alarm thermodetector, fixed temperature
	Smoke detector
	Fire alarm thermodetector, rate of rise
	Fire alarm master box—max. Height per fire department
	Magnetic door holder
	Fire alarm annunciator
	Staff register system—any type
	Electrical clock system devices—any type
	Public telephone system devices
	Private telephone system devices

	Watchman system devices
	Sound system, L = speaker, V = volume control
	Other signal system devices: CTV = television antenna; DP = data processing
	Signal central station
	Telephone interconnection box
	Pneumatic/electric switch
	Electric/pneumatic switch
	Operating room grounding plate
	Patient ground point; 6 = number of jacks

Panelboards

	Flush mounted panelboard and cabinet
	Surface mounted panelboard and cabinet
	Lighting panel
	Power panel
	Heating panel
	Controller (starter)
	Externally operated disconnect switch

Bus Ducts and Wireways

	Trolley duct
	Busway (service, feeder, or plug-in)
	Cable through ladder or channel
	Wireway
	Bus duct junction box

Electrical Distribution or Lighting System, Aerial, Lightning Protection

	Pole
	Street light and bracket
	Transformer
	Primary circuit
	Secondary circuit
	Auxiliary system circuits
	Down guy
	Head guy
	Sidewalk guy
	Service weather head
	Lightning rod
	Lightning protection system conductor

Residential Signaling System Outlets

	Push button
	Buzzer
	Bell
	Bell and buzzer combination
	Annunciator
	Outside telephone
	Interconnecting telephone
	Telephone switchboard
	Bell ringing transformer

O	Electric door opener
M	Maid's signal plug
R	Radio antennal outlet
CH	Chime
TV	Television antenna outlet
Ⓣ	Thermostat

Underground Electrical Distribution or Lighting System

M	Manhole
H	Handhole
TM	Transformer—manhole or vault
TP	Transformer pad
— - - -	Underground direct burial cable
	Underground duct line
	Street light standard fed from underground circuit

Panel Circuits and Miscellaneous

— — — —	Conduit concealed in floor or walls
- - - - - -	Wiring exposed
—➤——➤—	Home run to panelboard—number of arrows indiates number of circuits
———	Home run to panelboard—two-wire circuit
—///—	Home run to panelboard— number of slashes indicates number of wires (when more than two)
——➤ LS–L1,3,5	Home run to panelboard—"LS" indicates panel designation; L1, 3, 5, indicates circuit breaker no.
— C —	Clock circuit, conduit and wire

— E —	Emergency conduit and wiring
— T —	Telephone conduit and wiring
———	Feeders
——C	Conduit turned up
——●	Conduit turned down
Ⓖ	Generator
Ⓜ	Motor
⑤	Motor—numeral indicates horsepowper
Ⓘ	Instrument (specify)
T	Transformer
	Remote start/stop push button station
HTR	Remote start/stop push button station
	Electric heater wall unit

Common Abbreviations on Drawings

EWC	Electric water cooler
EDH	Electric duct heater
AFF	Above finished floor
UH	Unit heater
GFI	Ground fault interrupter
GFP	Ground fault protector
GFCB	Ground fault circuit breaker
EC	Empty conduit
WP	Weatherproof
VP	Vaporproof

HVAC

Ductwork Symbols


Supply duct


Return/exhaust duct



Duct—first number is side shown


Direction of flow


Lined ductwork



Inclined drop in direction of air flow



Inclined rise in direction of air flow


Canvas connection


Access door


Intake louver and screen


20 × 10-L
650 CPM
Exhaust louver


Splitter damper


Round elbow turning vanes



Automatic damper



Fire damper



Volume damper



Smoke damper


24″ Dia. CD
1250 CFM
Supply outlet ceiling diffuser


20 × 10 CD
500 CFM
Supply outlet ceiling diffuser


84 × 6-LD
375 CFM
Linear diffuser


Round elbow


Square elbow


Square elbow turning vanes

Double duct air system


RA
OA
F
P H
C C
FAN
HP
R H
HOT
MP
C C
COLD
HP
MP
LP
Mixing Boxes (VV or CV)
or Induction Units

OA = Outside Air
RA = Return Air
F = Filter
PH = Preheat Coil

CC = Cooling Coil
RH = Reheat Coil
HP = High Pressure Duct
MP = Medium Pressure Duct

LP = Low Pressure Duct
VV = Variable Volume
CV = Constant Volume

Appendix: Symbols

Valves, Fittings, and Specialties

	Gate
	Globe
	Check
	Butterfly
	Solenoid
	Lock shield
	2-way automatic control
	3-way automatic control
	Gas cock
	Plug cock
	Flanged joint
	Union
	Cap
	Strainer
	Concentric reducer
	Eccentric reducer
	Pipe guide
	Pipe anchor
	Elbow looking up
	Elbow looking down
	Flow direction
	Pipe pitch up or down
	Expansion joint
	Expansion loop
	Flexible connnection
	Thermostat
	Thermostatic trap
	Float and thermostatic trap
	Thermometer
	Pressure gauge
	Flow switch
	Pressure switch
	Pressure Reducing valve
	Humidistat
	Aquastat
	Air vent
	Meter
	Elbow
	Tee

Equipment

---- HWS ----	Hot water heating supply
---- HWR ----	Hot water heating return
---- CHWS ----	Chilled water supply
---- CHWR ----	Chilled water return
---- D ----	Drain line
---- CW ----	City water
---- FOS ----	Fuel oil supply
---- FOR ----	Fuel oil return
---- FOV ----	Fuel oil vent
---- FOG ----	Fuel oil gauge line
—o— PD —o—	Pump discharge
— — — — — —	Low pressure condensate return
---- LPS ----	Low pressure steam
---- HPS ----	Medium pressure steam
---- MPS ----	High pressure steam
---- BD ----	Boiler blow-down

Piping Symbols

Valves, Fittings, and Specialties

	Gate
	Globe
	Check
	Butterfly
	Solenoid
	Lock shield
	2-way automatic control
	3-way automatic control
	Gas cock
	Plug cock
	Flanged joint
	Union
	Cap
	Strainer
	Concentric reducer
	Eccentric reducer
	Pipe guide
	Pipe anchor
	Flow direction
	Elbow looking up
	Elbow looking down
	Pipe pitch up or down
	Expansion joint
	Expansion loop
	Flexible connection
	Thermostat
	Thermostatic trap
	Float and thermostatic trap
	Thermometer
	Presssure gauge
	Flow switch
	Pressure switch
	Pressure reducing valve
	Temperature and pressure relief valve
	Humidistat

	Aquastat
	Air vent
	Meter
	Hose bibb
	Elbow
	Tee
	"Y"
	OS and Y gate
	Shock absorber
	House trap
	"P" trap
	Floor drain
	Indirect waste
	Sanitary below grade
	Sanitary above grade
	Storm below grade
	Storm above grade
	Vent
	Combination waste and vent
	Acid waste below grade
	Acid waste above grade
	Acid vent
	Cold water
	Hot water
	Hot water circulation
	Drinking water supply
	Drinking water return

	Gas—low pressure
	Gas—medium pressure
	Gas—high pressure
	Compressed air
	Vacuum
	Vacuum cleaning
	Nitrogen
	Nitrous oxide
	Oxygen
	Liquid oxygen
	Liquid petroleum gas

Fire Protection Piping Symbols

	Fire protection water supply
	Wet standpipe
	Dry standpipe
	Combination standpipe
	Automatic fire sprinkler
	Upright fire sprinkler heads
	Pendant fire sprinkler heads
	Fire hydrant
	Wall fire dept. connection
	Sidewalk fire dept. connection
	Fire hose rack
	Surface mounted fire hose cabinet
	Recessed fire hose cabinet

Plumbing Fixture Symbols

Baths

	Corner
	Recessed
	Angle
	Whirlpool
	Institutional or island

Showers

	Stall
	Corner stall
	Wall gang

Water Closets

	Tank
	Flush valve

Bidet

	Bidet

Urinals

	Wall
	Stall
	Trough

Lavatories

	Vanity
	Wall
	Counter
	Pedestal

Kitchen Sinks

	Single basin
	Twin basin
	Single drainboard
	Double drainboard

Dishwasher

	Dishwasher

Drinking Fountains or Electric Water Coolers

	Floor or wall
	Recesssed
	Semirecessed

Laundry Trays

	Single
	Double

Service Sinks

	Wall
	Floor

Wash Fountains

	Circular
	Semicircular

Hot Water

	Heater
	Tank

Separators

	Gas
	Oil

Material Indication Symbols

Table A-1 Material Indication Symbols

Material	Plan	Elevation	Section
Earth	None	None	
Porous fill	None	None	
Concrete			Same as plan
Brick			Same as plan
Concrete block			Same as plan
Stone	 Cut stone Rubble	 Cut stone Rubble	Same as plan
Steel		None	
Framing wood	 Wall or partition	 Siding Finish wood	 Blocking Framing
Plywood	Indicated by note	Indicated by note	
Sheet metal flashing	Indicated by note		 Shaped Heavy Line
Batt insulation		None	Same as plan

(*Continued*)

Table A-1 Material Indication Symbols (Continued)

Material	Plan	Elevation	Section
Rigid insulation		None	Same as plan
Glass			 **Small scale**  **Large scale**
Gypsum wallboard			Same as plan
Acoustical tile		None	
Ceramic wall tile			Same as plan
Floor tile		None	

Table A-2 Window and Door Symbols

Type	Plan	Elevation
Double-hung windows		
Casement window		
Slider		
Exterior door		
Interior door		
Bifold door		



Fifth Edition

SCUBA DIVING

The authoritative guide to safe, enjoyable diving

Over 130,000 copies sold!

DENNIS GRAVER

HUMAN KINETICS

Scuba Diving

FIFTH EDITION

Dennis K. Graver, EMT, SEI

HUMAN KINETICS

Library of Congress Cataloging-in-Publication Data

Names: Graver, Dennis, author.
Title: Scuba diving / Dennis K. Graver, EMT, SEI.
Description: Fifth Edition. | Champaign, IL : Human Kinetics, [2016] |
Includes bibliographical references and index.
Identifiers: LCCN 2016018110 (print) | LCCN 2016031644 (ebook) | ISBN 9781492525769 (print) | ISBN 9781492542032 (ebook)
Subjects: LCSH: Scuba diving.
Classification: LCC GV838.672 .G74 2016 (print) | LCC GV838.672 (ebook) | DDC 797.2/34--dc23
LC record available at https://lccn.loc.gov/2016018110

ISBN: 978-1-4925-2576-9 (print)

Copyright © 2017, 2010, 2003, 1999, 1993 by Dennis K. Graver

All rights reserved. Except for use in a review, the reproduction or utilization of this work in any form or by any electronic, mechanical, or other means, now known or hereafter invented, including xerography, photocopying, and recording, and in any information storage and retrieval system, is forbidden without the written permission of the publisher.

This publication is written and published to provide accurate and authoritative information relevant to the subject matter presented. It is published and sold with the understanding that the author and publisher are not engaged in rendering legal, medical, or other professional services by reason of their authorship or publication of this work. If medical or other expert assistance is required, the services of a competent professional person should be sought.

The web addresses cited in this text were current as of June 2016, unless otherwise noted.

Acquisitions Editor: Tom Heine; **Developmental Editor:** Anne Hall; **Managing Editor:** Nicole Moore; **Copyeditor:** Jan Feeney; **Permissions Manager:** Martha Gullo; **Senior Graphic Designer:** Nancy Rasmus; **Cover Designer:** Keith Blomberg; **Photograph (cover):** Dirscherl Reinhard/Prisma/age fotostock; **Photographs (interior):** Dennis Graver, unless otherwise noted; **Photo Asset Manager:** Laura Fitch; **Visual Production Assistant:** Joyce Brumfield; **Photo Production Manager:** Jason Allen; **Art Manager:** Kelly Hendren; **Associate Art Manager:** Heidi Richter; **Illustrations:** © Human Kinetics; **Printer:** Walsworth

Human Kinetics books are available at special discounts for bulk purchase. Special editions or book excerpts can also be created to specification. For details, contact the Special Sales Manager at Human Kinetics.

Printed in the United States of America 10 9 8 7 6 5 4 3 2 1

The paper in this book is certified under a sustainable forestry program.

Human Kinetics
Website: www.HumanKinetics.com

United States: Human Kinetics
P.O. Box 5076
Champaign, IL 61825-5076
800-747-4457
e-mail: info@hkusa.com

Canada: Human Kinetics
475 Devonshire Road Unit 100
Windsor, ON N8Y 2L5
800-465-7301 (in Canada only)
e-mail: info@hkcanada.com

Europe: Human Kinetics
107 Bradford Road
Stanningley
Leeds LS28 6AT, United Kingdom
+44 (0) 113 255 5665
e-mail: hk@hkeurope.com

Australia: Human Kinetics
57A Price Avenue
Lower Mitcham, South Australia 5062
08 8372 0999
e-mail: info@hkaustralia.com

New Zealand: Human Kinetics
P.O. Box 80
Mitcham Shopping Centre, South Australia 5062
0800 222 062
e-mail: info@hknewzealand.com

E6733

Scuba Diving

FIFTH EDITION

Contents

Foreword vii
Acknowledgments ix

1 **Diving Into Scuba** 1
- The Joys of Diving 2
- How Diving Evolved 3
- The Diving Community 3
- Diver Training 5
- Proficiency Testing 5
- Diving Prerequisites 5
- Diving Risks 6
- Selecting a Dive Course 8
- Diving Responsibilities 9

2 **Diving Science** 11
- Anatomy for the Diver 12
- Respiration and Circulation 15
- Contrasts in Air and Water Environments 19
- Gas Laws 23
- Air Consumption 28
- Heat, Humidity, Light, and Sound 28

3 **Diving Adjustments** 37
- Thermal Adjustments 38
- Buoyancy Adjustments 41
- Pressure Equalization 43
- Breathing Adjustments 46
- Heart and Lungs 50
- Equilibrium Adjustments and Seasickness 52
- Visual Adjustments 53
- Ingassing and Outgassing 53
- Dehydration Prevention 58
- Mobility Adjustments 59

4 **Diving Equipment** 63
- Basic Equipment for All Divers 65
- Exposure Suits 71
- Weighting Systems 78
- Buoyancy Compensators 80
- Scuba Cylinders 83
- Cylinder Valves 87
- Scuba Regulators 89
- Alternate Air Sources 94
- Instrumentation 96
- Dive Knives and Accessories 100
- Specialized Equipment 104

5 **Diving Environment** 109

Aquatic Biology 110
Potentially Dangerous Aquatic Animals 114
Conservation and Preservation 117
Aquatic Conditions 121
Boat Diving 132

6 **Diving Skills** 137

Preparing to Skin Dive 138
Skin Diving Skills 141
Preparing to Scuba Dive 148
Scuba Diving Skills 152
Managing Physiological Problems 169
Managing Physical Problems 173
Managing Emergencies 178

7 **Dive Planning** 183

Dive-Planning Factors 184
Advance Planning and Preparation 185
Short-Term Planning and Preparation 187
On-Site Planning and Preparation 187
Area Orientations 189
Dive Profile Planning 190
Dive Tables 191
Dive Calculators and Dive Computers 204
Postdive Review 206

8 **Diving Opportunities** 209

Continuing Education 210
Local Opportunities 212
Dive Travel 213
Dive Destinations 216
Career Opportunities 218
Leadership Opportunities 219

Appendix A: Associations and Periodicals 221
Appendix B: AOK Answers 223
Glossary of Scuba Diving Terms 231
Bibliography 239
Index 241
About the Author 245

This page intentionally left blank.

Foreword

Recreational scuba diving has progressed from its beginnings in the 1950s. Dennis Graver's fifth edition of *Scuba Diving* is uniquely designed toward a level of education that provides new divers with an exceptional level of knowledge while promoting safety and enjoyment. With our training agencies, Scuba Educators International (the former YMCA scuba program) and PDIC International, our goal is to provide a full education for new divers. This text accomplishes that goal and perhaps can also be used for advanced programs as well.

At a time when instant gratification leads many to seek recreational activities that can be accomplished with little effort in a brief time, scuba takes new divers into an environment that remains challenging. Therefore, the need for a full education has not changed. Perhaps the delivery of information will change in the future; however, the need to understand the complexities of the undersea world will not.

In addition to bringing this fifth edition up to current levels of information, Dennis has provided end-of-chapter questions that result in additional learning. This edition is among the best of texts in the scuba industry for new divers.

Dave Barry wrote, "There is nothing wrong with looking at the surface of the ocean itself, except that when you finally see what goes on underwater, you realize that you've been missing the whole point." I couldn't agree more.

Tom Leaird, CEO
Scuba Educators International
PDIC International

This page intentionally left blank.

Acknowledgments

My appreciation includes the review of the Application of Knowledge (AOK) questions by Dr. Terry Beattie, former diving medical services officer for the Washington, DC diving unit. His physiology expertise was also helpful.

Wall diving in Haiti



1

Diving Into Scuba

Dive In and Discover

By the end of this chapter, you will be able to do the following:

- Describe the joys of diving.
- Define the terms *closed circuit*, *open circuit*, *scuba*, *semi-closed circuit*, and *C-card*.
- Explain the training requirements for participation in scuba diving activities.
- List two medical conditions that disqualify an individual from scuba diving.
- Describe three risks associated with scuba diving.
- List several questions to ask when selecting an entry-level scuba diver training course.
- Explain several responsibilities that you assume when you become a certified scuba diver.

The Joys of Diving

As a diver, you are weightless and can move in all directions. Your freedom approaches that of a bird as you move in three dimensions in a fluid environment. Diving weightless in clear water in a forest of underwater plants with sunlight streaming down is only one of many unforgettable experiences awaiting you.

Just as there are mountains, plains, and various environments above water, there are various environments for you to experience underwater. Coral reefs, kelp forests, incredible rock formations, and other natural wonders await divers in various geographical regions. In addition, divers can explore piers, jetties, quarries, mysterious shipwrecks, and other artificial structures. The variety of underwater sights is limitless. There is more to view underwater than anyone could possibly see in an entire lifetime. A range of activities—such as photography, hunting, and collecting—make diving challenging and rewarding. Scuba diving includes an activity to interest everyone.

Divers are friendly and easy to get to know; their camaraderie is well known. Diving is a sharing activity, and there is much to share. If you enjoy traveling, you will probably love diving. Dive travel is the number one business of recreational diving. Reasonably priced dive vacations to exotic islands abound. Most divers plan one or more diving vacations each year.

The sensations of diving are fantastic but are difficult to explain. Words cannot describe the peaceful solitude of inner space. Diving contributes to good health, can help reduce work-related stress, can increase self-esteem, and can make you feel great. You need to experience the emotions and sensations for yourself. You will then begin to know the joys of diving.

A giant grouper

When you descend beneath the surface of the water, you enter an entirely new and beautiful world. You have opportunities to see incredible life-forms that only a few people ever see. Imagine swimming in a giant aquarium, and you'll get a glimpse of what you can expect to experience in the underwater world.

How Diving Evolved

Interest in the underwater world has always existed. Driven by curiosity and the need for food, people have ventured beneath the surface of Earth's seas for thousands of years. Records exist of sponge divers, oyster pearl divers, military divers, and even salvage regulations dating back to 3000 BC. In ancient times, the two methods employed for diving were breath holding and the use of an inverted, air-filled bell (which was large and heavy). John Lethbridge, an Englishman, developed an oak cylinder diving engine in 1715 to pump air into a bell. The hand-operated air compressor, invented in 1770, allowed fresh air to be pumped into a submerged diving bell. In 1772, Sieur Freminet of France invented a helmet-hose system that permitted divers to work without a bell. The greatest early advancement in underwater equipment occurred in 1837, when Augustus Siebe (a German living in England) invented the first closed-dress diving suit, which became known as the hard-hat system. Siebe's system was so effective that it dominated underwater work for 100 years, and it is still in use today.

The origin of recreational diving can be traced to 1825. That year, William H. James, an Englishman, invented the first **open-circuit** self-contained underwater breathing apparatus **(scuba)** system. Although this system was not very practical, it did solve the problems of the air hose tether and the depth restrictions related to oxygen poisoning. Benoit Rouquayrol (a French mining engineer) and Auguste Denayrouze (a French naval officer) invented the aerophore in 1865. Their creation is considered the source of modern scuba equipment.

Later, two Englishmen, Henry Fleuss and Robert Davis, developed a **closed-circuit** oxygen rebreather system in 1878. This system eliminated the air hose that had previously tethered divers and restricted their movement. The system had great military application because bubbles were not exhausted into the water. Oxygen rebreathers were used extensively by Italian and British frogmen during World War II. However, the use of oxygen rebreather systems is limited to a depth of 20 feet (about 7.6 m) because breathing pure oxygen at greater pressures causes convulsions, which can be fatal during submersion.

Yves Le Prieur of France developed a manually controlled open-circuit scuba system in the early 1920's (year disputed); however, modern scuba diving was launched with the development of a "demand" scuba system that was perfected by Frenchmen Emile Gagnan and Jacques Cousteau in 1943. With this system, a diver could demand compressed air from a steel cylinder by simply inhaling from a pressure regulator held in the mouth. Scuba was introduced in the United States in 1950 and has been popular ever since.

The military has continued to improve underwater breathing systems that have found their way into use by recreational divers. The latest scuba systems are **semi-closed-circuit** rebreathers. These systems use sophisticated electronics to control the oxygen mixture that a diver breathes, periodically releasing only a small amount of bubbles. High levels of training, frequent use, and dedicated maintenance are required for the safe use of these expensive rebreathers. Table 1.1 outlines the basic features of each type of breathing system in more detail.

The Diving Community

The recreational diving community consists of equipment manufacturers, diving retailers, diving educators, diver training organizations, dive resorts, diving

Table 1.1 Scuba System Comparisons

Open-circuit scuba	Semi-closed-circuit scuba	Closed-circuit scuba
User inhales compressed air	User inhales oxygen and inert gas	User inhales pure oxygen
Exhaled air exhausted into water	Exhaled gases enter closed system	Exhaled gases enter closed system
Air supply duration varies with depth	Carbon dioxide absorbed within system	Carbon dioxide absorbed within system
Components simple	Oxygen added as needed	Oxygen added as needed
Unit easily maintained	Air supply duration unaffected by depth	Depth limit of 25 feet
Affordable	Components sophisticated and complex	Convulsions and death possible
Basic training required for use	Unit requires high maintenance	Components simple
	Expensive	High maintenance
	Highly technical specialty training required	Not available for recreational use
		A predecessor to semi-closed-circuit scuba

supervisors, dive guides, dive clubs and associations, publishing companies, and certified divers. Commercial, scientific, and professional diving are not considered recreational pursuits; separate communities are involved in these types of diving. This book addresses only recreational skin diving and scuba diving. A scuba diver breathes compressed air underwater, while a skin diver holds his or her breath while submerged.

Few laws pertain to recreational scuba diving. The laws that exist do not govern who may dive. The diving industry is self-regulating. The diving community realizes that it is dangerous when people who have not completed a sanctioned course of instruction attempt scuba diving. Dive businesses require proof of completion of training before they will allow you to have your scuba tanks filled or allow you to participate in diving activities. Many dive operations also require proof of recent experience documented in a diving logbook. If you have not been diving for a year or more, you may be required to complete at least one dive under the supervision of a diving professional. The supervised dive requirement helps increase the safety of divers whose skills may need to be refreshed.

When you complete your training requirements as a scuba diver, you receive a certification card called a **C-card**. Most C-cards do not require renewal, but the recreational diving community universally recommends the completion of refresher training after periods of inactivity in excess of six months.

Certified divers may dive without supervision or may employ the services of a diving guide. Just because a divemaster or diving supervisor is aboard a dive boat, you should not assume that this person is a guide who will dive with you. Guide services are not necessarily included with diving trips. If you want a guide to lead you about underwater and show you the sights, you should arrange for guide services in advance.

You will learn more about the community as your diving experience increases. Many opportunities for adventure and enjoyment can be found within this community. Get actively involved in the community when you complete your training and officially qualify as a scuba diver.

Diver Training

A national diver training organization must sanction your training. The training organization establishes standards of training that you must meet before the organization will issue a certification card. The Appendix A includes a list of national diver training organizations. Your instructor should have credentials that identify her as a qualified instructor. The instructor's membership in the training organization must be current in order for the person to be qualified to teach and certify divers. Be sure to confirm your instructor's qualifications.

An entry-level training course usually consists of a series of academic sessions, pool or confined-water (pool-like conditions in open water) sessions, and open-water training (in actual diving locations). You will learn theory in the classroom, learn skills in controlled conditions, and then apply your skills in an actual diving environment. This logical progression is common for all approved diver training courses.

The minimum requirements for your training are as follows: You should have four or more academic sessions, four or more pool sessions, and at least four scuba dives in open water. A skin dive in open water may also be part of your training.

Your initial training should involve a total of 30 to 40 hours of instruction. The instruction should occur over a period of several weeks instead of a few days. The time between class sessions allows you to reflect on your training and helps you absorb and retain the knowledge and skills better than a concentrated training schedule would.

Proficiency Testing

After you have learned and practiced the skills of skin and scuba diving, you must demonstrate your competence at a level established by the agency sponsoring your training. Proficiency testing may include diving exercises that are challenging and fun. Examples include mask recovery and clearing for skin diving, simulated boat exit for scuba diving, alternate air source breathing, buddy breathing, equipment handling, and a sequence of surface entry and equipment donning known as a bailout.

Diving Prerequisites

Scuba diving can be undertaken by anyone over 12 years of age who is in normal health and has a reasonable degree of physical fitness. People younger than this should not participate in scuba diving (even when supervised by adults) because they do not have the mental and emotional maturity to deal with the problems that might arise. Skin diving is a good activity for youngsters if they are well supervised.

For scuba diving, you need to have swimming ability, but you do not need to be a competitive swimmer. At the beginning of your training, you should be able to swim 200 yards (183 m) nonstop at the surface using any combination of strokes. There is no time requirement for the swim. Being comfortable in the water is more important than being able to swim fast. You also need to be able to swim 25 feet (7.6 m) underwater with no push-off. By the end of the course, you should be able to swim 300 yards (274 m) nonstop at the surface using any combination of strokes; you should also be able to swim 50 feet (15.2 m) underwater with no push-off. The goal is to increase your aquatic proficiency during the course.

Good health means your heart, lungs, and circulation are functional and that you do not have any serious diseases. Any medical conditions—even if controllable under normal conditions—that might incapacitate you in the water could cause you to drown while scuba diving. Some individuals with asthma or diabetes may be able to dive if they have obtained special medical approval. People with physical disabilities may also dive if they have medical approval from a physician. The air spaces in your body—sinuses, ears, and lungs—must be normal because changes in pressure affect them. Other medical conditions, such as seizure disorders, absolutely preclude a person's involvement in diving; a seizure while diving can be fatal. Women who are pregnant should not scuba dive. Increased pressure can adversely affect an unborn child. Pregnant women may choose to participate in snorkeling as an alternative to scuba diving. Many women ask whether they may dive during menstruation. Menstruation does not preclude a woman from diving if her health permits participation in other sports during that time.

You need to be emotionally fit as well as physically fit for diving. If you are terrified of water or of feeling confined, diving is probably an activity you should avoid. Normal concerns are to be expected, but stark terror is unacceptable.

You should have a physical examination before you begin your training, especially if it has been more than a year since your last exam. Ask your instructor to recommend a diving physician. Physicians who do not understand the physiology of scuba diving sometimes inappropriately grant approval to people who have medical conditions that place them at great risk in and under the water. Your instructor can likely recommend a physician who understands medical issues related to scuba.

Diving Risks

All activities present some risk. There is risk involved in walking across the street or driving a car. To avoid injury while participating in an activity, people take precautions for their safety. Precautions must be taken for scuba diving just as for any other pursuit. The level of risk in diving is similar to that of flying in an

SCUBA WISE

I nearly drowned when I was 4 years old, and I became terrified of water. When I was 8, I spent a summer with my uncle in Ohio. He would take me to Lake Erie and give me pennies if I would wade into water deep enough to cover my navel. I learned to swim as a Boy Scout at age 11. Although I completed a lifesaving class at age 16, I was still apprehensive about water. When I learned skin and scuba diving and discovered that I could actually relax in water, the water became my ally. For the first time in my life, I enjoyed water and was able to rid myself of my childhood fears. Just because someone feels anxiety about water does not mean that the person can't enjoy scuba diving. If you can swim 200 yards, you can learn to dive and to love being in and under the water.

airplane. Both are low-risk activities when done with well-maintained equipment according to established rules and in good environmental conditions. Unfortunately, both activities are unforgiving if you ignore the rules and recommendations designed to minimize the risks.

The following information (and the information throughout this book) will make you aware of injuries that scuba divers can incur. This information alerts you to potential hazards and, more important, helps you learn to avoid injury. If you do what you are taught to do as a diver, your risk will be minimal, and all of your diving experiences will likely be pleasant ones.

Pressure changes with depth. Changes in pressure can severely injure bodily air spaces if you are not in good health or if you fail to equalize the pressure in the bodily air spaces with the surrounding pressure. You will learn equalizing techniques as part of your training. Gases are normally dissolved in the fluids and tissues of your body. Increased pressure increases the amount of gas dissolved in your body. If you ascend too rapidly from a dive, the gases in your system can form bubbles and produce a serious illness known as **decompression illness**. By regulating your depth, the duration of your dive, and your rate of ascent, you can avoid decompression illness. Failure to heed depth and time schedules and ascent rates can result in serious, permanent injuries.

Diving can be strenuous at times. You need sufficient physical fitness and stamina to handle long swims, currents, and other situations that may arise. If you become winded from climbing a flight of stairs, you may need to improve your level of fitness before learning to scuba dive. Exhaustion in and under the water is hazardous. A good exercise to improve fitness for diving is swimming with fins while breathing through a snorkel.

Diving takes place in water, an alien environment. You use life-support equipment to dive, but you cannot depend entirely on the equipment for your well-being. Aquatic skills are essential in and around water. People with very weak aquatic ability can drown when minor equipment problems occur—problems that could be handled easily by a person with good water skills. To be a scuba diver, you must be comfortable in the water.

You should not be overly concerned with the potential risks of diving because the possible

Red Sea coral cave

injuries are preventable. Learning how to dive as safely as possible is the purpose of your training. You will learn to minimize the risk of injury and maximize your enjoyment of the underwater world.

Selecting a Dive Course

There are many diver training organizations and thousands of professional diving educators. Your phone book might list diving businesses that offer sanctioned courses. Many universities, community colleges, and recreational departments also offer scuba courses. (See Appendix A for a list of diver training organizations.) Ask about the qualifications, experience, and reputation of several diving instructors in your area to select the course that can provide you with the best possible training. Here are some questions you should ask:

- Is this training sanctioned by a diver training agency?
- How long has the instructor been teaching scuba diving?
- Which levels of training is the instructor qualified to teach?
- May I speak with the graduates of a recent class?
- Why is this course better than others in the area?
- Are assisting and rescue techniques taught in the course?
- How many instructor-supervised open-water dives are included?

The tuition for diving instruction is usually between $200 and $300. The lowest-priced course may not necessarily be a bargain. Find out what is included with the course fee and, more important, what the total cost will be for you to become certified as a scuba diver. You do not have to purchase all the equipment needed to scuba dive, but you need to have a mask, snorkel, fins, and usually boots and gloves for your training (see figure 1.1). Use of the additional required equipment is typically part of the course tuition.

You should find out whether the price of the course includes the costs of educational materials and certification. There may be additional costs for travel, lodging, parking, boat fees, and equipment rental for open-water training. Determine the complete cost before enrolling in a course.

When you have selected the best program for you and have enrolled in a course, you should receive a reading assignment for your first session. If you are not given an assignment, speak with the instructor; your learning will be enhanced if you read in advance about the topics to be presented in class. Good diving instructors provide a handout with reading assignments.



Figure 1.1 Required scuba diving training equipment.

Diving Responsibilities

When you qualify as a scuba diver, you assume many responsibilities. You are responsible for your safety, for the safety of those you dive with, for the image of scuba divers, and for the preservation of the diving environment. The diving community encourages divers to accept responsibility for their actions. To be part of the diving community, you need to be a responsible diver. Learn what you should do, then do what you learn.

Summary

Diving can be a source of great joy. Many exciting experiences await the trained diver. You need dive credentials to participate in diving activities. You must complete diver training to obtain your C-card and logbook. But diving is not for everyone. You must have normal health, good swimming skills, and reasonable physical fitness. Diving poses risks that a well-trained, wise, and fit diver can minimize. Compare training programs and choose the best education, which may not be the quickest or the least expensive. Remember that you accept a great deal of responsibility when you become a diver. Do not assume that you can transfer the responsibility for a dive accident to someone else. Ultimately, you control your actions underwater. Become a competent, self-reliant diver who adheres to recommended safety practices, and you will discover the joy of diving.

Application-of-Knowledge (AOK) Questions

The following questions will enhance your understanding of what you have learned in this and every chapter. Take time to consider each question before you look at the answer, which is at the back of the book in Appendix B. When you apply the basic knowledge you have learned and correctly respond to the following questions, you demonstrate understanding, which is a higher level of learning than mere knowledge. Do not be concerned if you do not have a correct response. Your analysis of the question and the revelation of the answer will increase your understanding.

1. What is your primary reason for learning to scuba dive? What do you think you will do while scuba diving after completion of your initial training?
2. Why do beginning recreational divers use open-circuit breathing systems instead of closed-circuit systems?
3. Why should you document your dives in a logbook?
4. What are the advantages of completing a 40-hour scuba diving course rather than a course that is much shorter in duration?
5. Why is a medical examination recommended for those who want to learn scuba diving? What type of doctor is the best choice for a scuba diving medical exam?
6. List three actions you can take to minimize your risk of injury when scuba diving.
7. What are some of the factors that you should consider when selecting a scuba diving course?
8. List three actions you can take to demonstrate that you are a responsible diver.



A sea fan



2

Diving Science

Dive In and Discover

By the end of this chapter, you will be able to do the following:

- List three body air spaces of concern to divers.
- Describe the process of hearing in air.
- Describe the cardiorespiratory process.
- Explain the effect of carbon dioxide on breathing.
- Define the terms *eardrum*, *middle ear*, *eustachian tube*, *nitrogen narcosis*, *hyperventilation*, *hypoventilation*, *density*, *buoyancy*, *pressure*, *gauge pressure*, *absolute pressure*, *Boyle's law*, *Gay-Lussac's law*, *Dalton's law*, *squeeze*, *reverse block*, *ingassing*, *outgassing*, and *partial pressure*.
- Explain the principle of buoyancy and the key to controlling buoyancy.
- Explain the effects of pressure and temperature on a volume of air in a flexible container.
- Explain why it is important to vent your lungs when you ascend in water.
- Convert any temperature to absolute temperature.
- Explain the process of ingassing and outgassing.
- State the two primary factors that affect the air consumption of a scuba diver.
- List four methods of heat loss.
- Describe three potential problems for scuba divers that may be caused by humidity.
- Describe the effects of water on vision and hearing.

Anatomy for the Diver

Inside your body are air-filled spaces that are affected by changes in pressure. The three body air spaces of primary concern to you as a diver are the lungs, the ears, and the sinuses. Understanding the structure and function of your throat will also help you as a diver. Figure 2.1 illustrates the structure and functions of the sinuses, throat, and lungs.

Sinuses

The sinuses warm and humidify inspired air. They secrete mucus to help protect the body by trapping airborne germs. The small airways that connect the sinuses to the nasal passages are normally open. Congested sinuses pose problems for divers. In the next chapter, you will learn more about sinus problems and how to prevent them.

Throat

In addition to being the organ of voice, the throat and larynx help prevent foreign matter from entering the lungs. If something foreign, such as food or water, comes into contact with the larynx, a reflex action causes a spasm of the larynx. Coughing expels the foreign substance. You have experienced this sensation when something has "gone down the wrong pipe." Review the throat section of figure 2.1. During your scuba diving training, you will learn how to keep water out of your larynx to avoid coughing and choking in and under the water.

Lungs

Healthy lungs are essential for scuba diving. The lungs are large organs that contain millions of microscopic air sacs. Your lungs have a maximum capacity and a minimum capacity. When you exhale completely, your lungs are not empty. They contain about 2 pints (1L) of air. The air remaining in your lungs after you have exhaled completely is your residual volume. The amount of air you move in and out of your lungs is your tidal volume. When you are at rest, your tidal volume is small. When you exert yourself, your tidal volume increases until you reach both your maximum lung volume and your residual volume with each breath. Your vital capacity is the difference between the volume of air for a maximum inhalation and the volume of air for a maximum exhalation—typically about 6 to 8 pints (2.8 to 3.8L). In the next chapter, you will learn several reasons why your lungs are the most critical air spaces when diving.

The epiglottis and the soft palate in the back of your pharynx seal the airways to your nasal passages and to your lungs when you swallow.

Sinuses form air spaces that reduce the weight of the head. The sinuses are connected to the nasal passages by small airways.



Sphenoid sinus
Hard palate
Soft palate
Food
To stomach
To lungs
Frontal sinus
Maxillary sinus
Pharynx
Epiglottis
Larynx
Trachea (windpipe)
Lung
Bronchi
Bronchioles
Alveoli
Pleural lining
CO_2
O_2
Maximum inhalation
Maximum exhalation
IRV
TV
ERV
RV
VC
TLC
6
5
4
3
2
1
0
Liters of air (average person)

	Lung volume (liters)	Small	Average	Large
TLC	Total lung capacity	4.0	6.0	8.0
VC	Vital capacity	3.0	4.5	6.0
RV	Residual volume	1.0	1.5	2.0
ERV	Expiratory reserve volume		varies	
TV	Tidal volume		varies	
IRV	Inspiratory reserve volume		varies	

The pleural lining is a slippery layer of tissue that helps maintain lung inflation and keeps the constant motion of the chest from irritating the chest walls.

The lungs are more like sponges than balloons. Air traveling down the trachea passes into the bronchi, which rebranch over 20 times into airways called bronchioles. The bronchioles end in microscopic respiratory air sacs called alveoli.

The alveolar walls are very thin to allow gas to diffuse from the lungs into the blood and from the blood into the lungs.

Figure 2.1 Functions of the sinuses, throat, and lungs.

Colorful fish in a Florida coral cave

Your body is a marvelous machine. It performs many complex functions automatically. Your body is well adapted to an air environment, but it can also adjust in many ways to the aquatic environment. In this chapter, you will become familiar with some of the structures and functions of your body that are important for scuba diving. You will learn the differences between the air and water environments and how changes in pressure affect your body. As a diver, you face many challenges in the underwater environment, but these challenges can be managed.

Ears

Behind your **eardrum** is an air space called the **middle ear**, which is illustrated in figure 2.2. The pressure in the middle ear must equal the pressure in the outer ear; otherwise, the eardrum cannot move freely. The next chapter explains how to keep pressure inside your ears equal to external pressure. Your **eustachian tube** allows the equalization of pressure in the middle ear. The liquid-filled cochlea contains hairlike projections called cilia, which convert mechanical movement to electrical signals for the brain. The movement of the oval window by the tiny bones of the middle ear causes the liquid and the cilia in the cochlea to move back and forth. The oval window movement could not take place without a second window in the hearing organ—the round window. When the oval window moves inward, the round window moves outward, and vice versa.

If the motion sensed by your semicircular canals and the visual cues received by your eyes are not in harmony, motion sickness can result. Sudden changes in temperature or pressure in the middle ear can affect your semicircular canals

Abbreviations

✓ **ATA**	atmospheres absolute
✓ **atm**	atmospheres
✓ **CO**	carbon monoxide
✓ **CO_2**	carbon dioxide
✓ **°C**	degrees Celsius
✓ **°F**	degrees Fahrenheit
✓ **FFW**	feet of freshwater
✓ **FSW**	feet of seawater
✓ **ft**	feet
✓ **m**	meters
✓ **O_2**	oxygen
✓ **psia**	pounds per square inch absolute
✓ **psig**	pounds per square inch gauge



The semicircular canals sense motions and help the brain maintain body balance.

Three tiny bones couple vibrations from the eardrum to the inner ear.

To couple sound to the cochlea, the round and oval windows move in opposite directions.

The eardrum (a flexible, airtight barrier) separates the outer ear from the middle ear.

The eustachian tube is an airway between the middle ear and the throat.

Figure 2.2 Process of hearing in air.

and cause temporary disorientation. (The next chapter presents potential ear problems for divers, how to avoid them, and how to handle them if they happen.)

Teeth

You may be surprised to learn that there are dental concerns for divers. Pressure can affect air pockets in improperly filled teeth and can cause tooth pain. If a tooth hurts only under pressure or only after a dive, see your dentist and tell him what you suspect. The roots of some upper molars extend into the sinus cavities. You should postpone diving for several weeks after you have had a tooth extracted.

Your mouth and jaws are designed for an even bite. If you bite hard on a mouthpiece with only your front teeth for prolonged periods, your jaws will become sore. Special mouthpieces designed for a proper bite can help reduce the problem. You should not have to bite hard on a mouthpiece to hold it in place. If you find biting necessary, get lighter equipment. Prolonged, improper biting that irritates your jaws can lead to serious inflammation of your jaws and ears.

Respiration and Circulation

One of the fascinating processes within the human body is your ability to breathe in air and circulate oxygen to the tissues with no conscious effort. As your level of exertion increases, your heart and lungs automatically adjust to meet the increased demands for oxygen and nourishment. An understanding of the gases involved in respiration and the basics of respiration and circulation can help you understand the effects and the demands of diving on your lungs and heart.

Gases We Breathe

Several gases affect recreational divers. You need to know about their effects on your body. About 80 percent of air is nitrogen (N^2). At sea-level pressures, nitrogen has no effect on your body. At a depth of about 100 feet (30 m), the increased pressure of the gas has a detrimental effect, which is called **nitrogen narcosis**. Excessive nitrogen in your body at the end of a dive can produce a serious illness known as decompression sickness. You will learn more about nitrogen narcosis and decompression sickness in the next chapter.

Oxygen (O_2) is the gas that supports human life. Any other gas mixed with oxygen serves only as a vehicle for oxygen to be inspired. Approximately 21 percent of air is oxygen (see figure 2.3). You need to breathe at least 10 percent oxygen to remain conscious. However, oxygen breathed under high pressure is poisonous and causes convulsions because oxygen at increased pressure affects your nervous system. You usually have compressed air—not pure oxygen—in your scuba tanks. A specialty form of diving uses a nitrogen and oxygen mixture with a higher percentage of oxygen than is found in air. The mixture, which reduces the effects of nitrogen at depth, is called **nitrox**. The use of special mixed gases, including nitrox, requires special training, equipment, and procedures.



Figure 2.3 Composition of air.

As your tissues use oxygen, they produce carbon dioxide (CO_2). Carbon dioxide is the primary stimulus for respiration. The greater the level of carbon dioxide in your body, the greater your urge to breathe will become. If the level of carbon dioxide in your body becomes too great, unconsciousness will result.

Carbon monoxide (CO) is a poisonous gas produced by the incomplete combustion of gas or oil. The exhaust from an internal combustion engine contains carbon monoxide. An oil-lubricated air compressor that overheats can produce carbon monoxide. Even a minute amount of carbon monoxide in your scuba tank can poison you and lead to unconsciousness or death. Air filling stations must take care to avoid contamination of air with carbon monoxide.

Breathing and Circulation Mechanics

When you need to breathe, sensors at the base of your brain send a signal that stimulates your diaphragm to contract and your chest to expand. This draws air into your lungs in the same way that an old-fashioned bellows draws in air when you expand it. Your diaphragm contracts and increases the volume of the chest cavity, while the muscles of your chest expand your chest cavity to inspire air. Figure 2.4 illustrates how the heart, lungs, and circulatory system work in the process of respiration.



The function of capillaries is to exchange materials between the bloodstream and the interstitial fluid surrounding body cells. In some organs, specialized capillary structures help do this job. The structure of the alveolus, villus, and glomerulus all serve to maximize capillary surface area.

A capillary is so small that its wall is only one cell thick, making it easy for many materials to move through the wall and into the interstitial fluid bathing the body's cells.

On the arteriole end of the capillary, blood pressure in the vessel is greater than the osmotic pressure of the blood in the vessel. The result is that fluid moves out of the vessel to body tissue, carrying hormones, small proteins, oxygen, and nutrients to cells.

On the venule end of the capillary bed, blood pressure in the vessel is less than the osmotic pressure of the blood in the vessel. The net result is that fluid, carbon dioxide, and wastes are drawn from the body tissue into the capillary vessel.

CO_2
O_2
O_2
CO_2
Lungs: Alveolus
Intestine: Villus
Kidney: Glomerulus
Inferior vena cava 16 mm
Abdominal aorta 20 mm
Average diameter of blood vessels (actual size)
Large: Left common iliac vein
8 mm
Large: Common iliac artery
10 mm
Small: Lesser saphenous vein
3 mm
Small: Dorsalis pedis artery
3.3 mm
Venule: .035 mm
Capillary (not visible) 8 µm
Arteriole: .035 mm
High pressure
Pressure decreasing
Low pressure

Figure 2.4 The cardiorespiratory system.

Blood consists of plasma (which is a colorless liquid) and a variety of cells. Hemoglobin, a blood component, is the primary oxygen-carrying mechanism in the blood. Approximately 45 percent of the blood is hemoglobin. Hemoglobin releases oxygen when it reaches tissues that need oxygen.

When the tissues use oxygen, they produce carbon dioxide. The carbon dioxide diffuses into the venous system and into the lungs in exchange for oxygen. This completes a circulatory cycle, which takes about 30 seconds.

Carotid sinuses on each side of the neck sense blood pressure within the circulatory system. Excessive pressure on the carotid sinuses during exercise causes the heart to slow when it should be working hard to meet the oxygen demands of the body. Decreased output from the heart can lead to insufficient oxygen for the brain, which can cause unconsciousness. A blackout caused by pressure on the carotid sinuses (see figure 2.5) is a carotid sinus reflex. Therefore, beware of diving equipment that is tight around your neck.



Figure 2.5 Excessive pressure on the carotid sinuses can lead to unconsciousness.

Exhalation is usually a passive process. To exhale carbon-dioxide-laden air from the lungs, the diaphragm relaxes, and the elasticity of the chest cavity forces air from the lungs. You ventilate your lungs approximately 12 to 20 times per minute when at rest. Respiration functions automatically. The key to respiration is the level of carbon dioxide in your circulatory system. When the carbon dioxide in your body reaches a certain level, your brain stimulates respiration. When you voluntarily hold your breath, the buildup of carbon dioxide within your body urges you to breathe. Many people believe that the amount of oxygen in the body controls respiration, but it is primarily the level of carbon dioxide that regulates breathing.

Hyperventilation is rapid, deep breathing in excess of the body's needs. Limited hyperventilation—three or four breaths—enhances breath holding (see figure 2.6*a*). But if you hold your breath after excessive hyperventilation, you may lose consciousness without warning before being stimulated to breathe (see figure 2.6*b*). A breath-holding diver who loses consciousness from lack of oxygen usually blacks out near the surface during ascent. The sudden loss of consciousness near the surface is called **shallow-water blackout**. Loss of consciousness while in the water can cause drowning. You should avoid excessive hyperventilation.

If you breathe rapidly and shallowly, carbon dioxide continues to build in your system, but you do not expel it from your lungs. Inadequate breathing is **hypoventilation**. Shallow breathing is dangerous, especially when you exert yourself, because you can lose consciousness from lack of oxygen. You need to breathe sufficiently to exchange the air in your lungs.



Figure 2.6 Charts showing (*a*) limited hyperventilation and (*b*) excessive hyperventilation.

Contrasts in Air and Water Environments

We live immersed in air, which is a fluid. Air has weight and takes up space. We don't pay much attention to our immersion in air because we are adapted to this environment. We have lived in it all of our lives, and we cannot see the air. The weight of the atmosphere does affect us, however.

Air weighs about 0.08 pound per cubic foot (1.28 mg per cubic cm) at sea level. As altitude increases, air becomes thinner, so its weight per volume is less in the mountains than it is at the seashore (see figure 2.7). The change in the


Air pressure
Increases
Air is less dense at altitude, so pressure decreases as altitude increases
Air pressure
Decreases

Figure 2.7 Air density and pressure are affected by altitude.

weight of air affects the air spaces in our ears when we fly or when we drive in the mountains.

Density

Density is weight per unit volume (for example, pounds per cubic foot). Water is a fluid, but it is much heavier than air. Seawater weighs about 64 pounds per cubic foot (1.025 g per cubic cm), which makes it about 800 times denser than air. Freshwater, because it does not contain salt, weighs a little less than seawater: 62.4 pounds per cubic foot (1 g per cubic cm). Temperature affects the density of water, air, and all fluids; cold water is slightly denser than warm water.

Air can be compressed, but water is essentially incompressible. Air becomes thinner as altitude increases, whereas water density remains constant throughout the water column.

Drag

Drag is a force that slows movement. Resistance to movement is much greater in water than in air. Factors affecting drag include the viscosity of the fluid, the speed of motion, and the size and shape of the object moving through the fluid. Drag is greater when the fluid is denser, the motion is faster, the object is larger, or the surface of the object is more irregular (see figure 3.9 in chapter 3).

Because of water's higher density, the molecules of water are much closer together than those of air. The tightly packed molecules affect the transmission of light, sound, and heat (see table 2.1). Light travels about 27 percent slower in water than in air. Sound travels about 4 times faster in water than in air. Still water conducts heat nearly 25 times faster than air does and moving water can

Table 2.1 Water Compared With Air

Property	Air	Water	Comparison	Effects
Density	0.08 lb/ft^3 (1.3 kg/m^3)	62.4 to 64 lb/ft^3 (1,000 kg/m^3)	Water is 800 times denser than air.	Resistance to movement
Compressibility	Yes	No	Air density varies; water density is constant (at dive pressures).	Affects body & attached air spaces
Speed of light	186,000 mi/s (300,000 km/s)	140,000 mi/s (225,400 km/s)	Light travels 27% more slowly in water.	Affects vision
Light absorption	Low	High	Water absorbs color quickly.	Light & color loss
Speed of sound	1,125 ft/s (340 m/s)	4,900 ft/s (1,400 m/s)	Sound travels 4 times faster in water.	Unable to determine source
Conductivity	0.17	3.86 to 4.12	Heat loss is 22 to 24 times faster in water than in air.	Rapid loss of body heat
Heat capacity	0.24	0.94 to 1.0	The heat capacity of water is 4 times greater than air.	Absorbs heat quickly

conduct heat hundreds of times faster than air. Water has an enormous capacity for absorbing heat with little change in its temperature. The higher density of water affects you in many ways when you dive. The next chapter explains how to deal with the effects of water density.

Buoyancy

An object's ability to float in a liquid depends on the density of the object compared with the density of the fluid in which the object is immersed. Water exerts pressure equally in all directions, even upward. You can feel the upward force (**buoyancy**) of water when you try to push something under the water. Buoyancy results from the difference in pressures on the upper and lower surfaces of an object. The weight of an object plus the weight of the fluid (air, water, or both) above the object exert a downward force. Fluid pressure pushes upward from below. The difference between these two forces is the buoyancy of the object.

Archimedes, an ancient Greek scientist, discovered that the force of buoyancy acting on a submerged object equals the weight of the water displaced (this is known as **Archimedes' principle**). A hot-air balloon floats in air because the hot air inside the balloon weighs less than the volume of cooler air the balloon occupies. A diver is buoyed upward with a force equal to the weight of the water that the diver displaces (see figure 2.8). If you and your equipment weigh less than the weight of the water you displace, you will float, or have positive buoyancy. If you and your equipment weigh more than the water being displaced, you will sink. An object that sinks has negative buoyancy. If you and your equipment weigh exactly the same as the water displaced, you neither float nor sink. Instead, you remain at the depth where you are; you have **neutral buoyancy**.


An object immersed in a fluid is buoyed up by a force equal to the weight of the fluid displaced.
Volume of water displaced
192
Buoyancy 192 lb (87 kg)
Diver + equipment 192 lb (87 kg)
Positive +
Neutral
Negative –
Three states of buoyancy

Figure 2.8 Principles of buoyancy.

As a diver, you can float at the surface, sink to the bottom, or hang suspended between the bottom and the surface. If the volume of an object increases with very little change in its weight, buoyancy increases. This happens when you add air to an inflatable jacket or vest. The next chapter addresses the factors affecting buoyancy and the principles of buoyancy control.

Pressure Measurement

Force (often weight) per unit area—such as pounds per square inch or grams per square centimeter—is **pressure**. The envelope of air surrounding the earth is the atmosphere. The weight of one square inch of the atmosphere at sea level is 14.7 pounds (1.03 kg per square cm), or 1 atmosphere (atm) of pressure. As you descend in water, the weight of the fluid—the pressure—exerted on each square inch of your body increases. One square inch of saltwater that is 33 feet (10.1 m) in height weighs 14.7 pounds, 1 atm, or 1.01 bar. One square inch of freshwater 34 feet (10.36 m) in height also exerts a pressure equivalent to 1 atm. Because 1 bar is almost equal to 1 atm, we'll consider them identical in this book. Because water does not compress (at the pressures involved with recreational diving), it follows that water pressure increases by 1 atm for every 33 feet of saltwater (33 FSW) and for every 34 feet of freshwater (34 FFW). Figure 2.9 shows how **atmospheric pressure** and water pressure are measured.


Pressure measurement
1 in.^{2}
1 atm gauge pressure
2 atm absolute pressure
3 atm absolute pressure
4 atm absolute pressure
Each 33 ft of water equals 1 atm of pressure
33 ft
66 ft
99 ft
2 atm gauge pressure
Absolute pressure equals gauge pressure **plus** atmospheric pressure
3 atm gauge pressure
Pressure
1 atm of air pressure (14.7 psi)
Air
1 in. × 1 in. × 100 miles
=
1 atm of water pressure (14.7 psi)
Salt water
1 in. × 1 in. × 33 ft

Depth		Gauge pressure			Absolute pressure		
FSW	FFW	In atm		In psig	In ATA		In psia
0	0	0	=	0.0	1 ATA	=	14.7
33	34	1	=	14.7	2 ATA	=	29.4
66	68	2	=	29.4	3 ATA	=	44.1
99	102	3	=	44.1	4 ATA	=	58.8
132	136	4	=	58.8	5 ATA	=	73.5

Gauge pressure compared to absolute pressure in fresh and salt water.

Figure 2.9 Principles of pressure measurement.

The reference for pressure is either the atmospheric pressure at sea level or zero pressure (outer space). A pressure gauge that reads zero at sea level displays only the pressure in excess of one atmosphere. Tire gauges and depth gauges are good examples of instruments that indicate **gauge pressure**, which may be measured in pounds per square inch gauge (psig), feet or meters of seawater, or bars of pressure.

The total pressure exerted is what matters to divers. The pressures of both the atmosphere and the water apply to diving. The reference for the total pressure is zero, as in a vacuum. The total pressure is called **absolute pressure**, which is measured in pounds per square inch absolute (psia). When people express absolute pressure increments in atmospheres, they use atmospheres absolute (ATA).

You obtain absolute pressure by adding atmospheric pressure to gauge pressure. Be sure you understand the concept because we'll use absolute pressure when dealing with the effects of pressure in this and later chapters.

Gas Laws

When you compress a quantity of gas, you reduce its volume and increase its density and temperature. Allowing a quantity of gas to expand increases its volume, decreases its density, and decreases its temperature. Because divers use gases, you need to understand the relationships between these properties (pressure, volume, density, and temperature) of gases.

Boyle's Law

Boyle's law states that for any gas at a constant temperature, the volume varies inversely with the absolute pressure, while the density varies directly with the absolute pressure. If you compress a closed, flexible air space (such as a balloon), you reduce its volume in proportion to the increase in pressure. When you double the pressure, a closed, flexible air space occupies only half the volume that it did originally. No air is lost. The molecules compress into a smaller area. The density of the air is twice as great as it was originally. When you return the compressed air space to its original pressure, the air inside expands until the object reaches its original volume. You compress your lungs during a breath-hold descent, and they return to normal volume when you return to the surface, provided that you do not expel air underwater.

Scuba equipment provides air to you at the exact pressure of the surrounding water. This allows you to expand your lungs to their normal volume regardless of the depth. The density of the air inside the lungs increases in proportion to the water pressure. If the water pressure doubles, the density of the air in your lungs also doubles. Figure 2.10 shows the relationships between pressure, volume, and density for a gas-filled, flexible-walled container.

Boyle's law also applies when you reduce the surrounding pressure. As outside pressure decreases, compressed air in a closed, gas-filled, flexible container expands in proportion to the reduction in pressure; for instance, if the pressure halves, the volume doubles. If a container filled with compressed air at depth is vented correctly during ascent, expanding air escapes through the vent, and the container remains full throughout the ascent. If the container is not vented, pressure inside increases when the container reaches its maximum volume. If the container is weak, the increase in pressure will rupture the container. This concept is important to scuba divers, who have many air spaces filled with



Figure 2.10 Pressure, volume, and density relationships.

compressed air. Vented air spaces do not pose a hazard. But if your lungs are not vented during ascent, life-threatening injuries will result. If you do not vent air from a flotation jacket during ascent, control of buoyancy will be lost as air expands and the jacket volume increases.

Figure 2.10 shows an interesting point about the rate of change of pressure (and volume) in water. The pressure doubles from 1 atm to 2 atm in 33 feet (10 m) of seawater. Doubling the pressure again requires a depth of 99 FSW (30 m). Note that you must ascend from 99 feet to a depth of 33 feet—a distance of 66 feet (20 m)—to experience the same rate of change of pressure that you experience when you ascend from 33 feet to the surface. In other words, the closer you get to the surface, the greater the rate of change of pressure (and of the volume of an air space). You must be more attentive to compressed air in air spaces the nearer you are to the surface.

The change in pressure that you experience during descents and ascents in water is perhaps the most significant challenge of diving. Changes in pressure have direct, mechanical effects on your body. Pressure imbalance in your body air spaces can cause discomfort. In the air environment, you feel pressure changes as a result of changes in altitude, but pressure changes in water occur at a much greater rate than in air. You can sustain serious injury unless you keep the pressure in air spaces inside and attached to you equalized with the surrounding water pressure. Boyle's law causes **squeezes** and **reverse blocks**, which figure 2.11 illustrates. Knowledgeable and experienced divers routinely equalize pressures to avoid squeezes and blocks. Keeping pressure in air spaces equalized with the surrounding pressure is one of the main subjects of the next chapter.

Gay-Lussac's Law

Boyle's law addresses gas at a constant temperature because the temperature affects the pressure and volume of a gas. Jacques Charles, a French chemist, discovered that the volume of gas at a constant pressure changes with temperature. Joseph-Louis Gay-Lussac, a French scientist, defined the effect of



If the pressure inside an air space is less than the surrounding water pressure, the outside pressure attempts to compress the air space. This condition is a “squeeze.”

During descent, squeezes may occur in ears, sinuses, the mask, and other air spaces in or attached to the body.

During ascent, the pressure surrounding an air space decreases. If the air inside the space, which was equalized to a higher pressure during descent, cannot escape, a situation that is the reverse of a squeeze occurs. When the pressure inside an air space is greater than the surrounding pressure, the condition is a “reverse block.”

A “block” describes a situation where some form of blockage prevents compressed air from entering.

Prevention of both squeezes and blocks involves keeping the pressure within an air space equalized with the surrounding pressure.

Figure 2.11 An explanation of squeezes and reverse blocks when equalizing pressure.

temperature: For any gas at a constant volume, the pressure of the gas varies directly with the absolute temperature. Just as absolute pressure must be used for pressure calculations, absolute temperature must be used for temperature computations. The absolute temperature scale for Fahrenheit temperatures is Rankine. To convert a Fahrenheit temperature to Rankine, add 460 degrees. The absolute temperature scale for a Celsius temperature is Kelvin. To convert a Celsius temperature to Kelvin, add 273 degrees.

You can observe the effect of **Gay-Lussac’s law** with a scuba tank, which has a constant volume. Decreasing the temperature of the air in a tank causes the pressure to decrease. Increasing the temperature of the air in a tank causes the pressure to increase. A scuba tank taken from the trunk of a hot car and cooled in water experiences a drop in pressure, although no air leaves the cylinder. Pressure increases or decreases in a standard 80-cubic-foot (2,265 L) aluminum scuba cylinder at a rate of about 6 psig per degree Fahrenheit temperature change. Pressure increases or decreases in a standard 71.2-cubic-foot (2,016 L) steel scuba cylinder at a rate of about 5 psig per degree Fahrenheit temperature change.

Dalton’s and Henry’s Laws

A gas can diffuse into or out of a substance. When a gas comes into contact with a liquid, the gas dissolves into the liquid. The amount of gas that diffuses into the liquid depends on the density and temperature of the liquid, the pressure of the gas in contact with the liquid, and the length of time that the gas is in contact with the liquid. Another term for the process of gas diffusion into a liquid is **ingassing**. Because the human body is primarily liquid, the gases you breathe diffuse into your body tissues.

In a mixture of gases, such as air, the percentage of the total pressure exerted by each gas is the **partial pressure** of that gas. **Dalton's law** states that the total pressure exerted by a mixture of gases is the sum of the pressures that would be exerted by each gas if it alone were present and occupied the total volume. The partial pressure of a gas determines the amount of that gas that dissolves into a liquid. **Henry's law** expresses gas absorption: The amount of a gas that dissolves in a liquid at a given temperature is directly proportional to the partial pressure of that gas. Table 2.2 shows the partial pressures of gases in the air at 1 ATA.

The partial pressure of a gas is the percentage of the gas in the mixture times the absolute pressure of the mixture. The partial pressure of a gas at depth has the same effect as a higher percentage of that gas at the surface. If a mixture of gas contains 2 percent carbon dioxide (CO_2) at sea level (14.7 psia, or 1.03 kg per square cm), the partial pressure of the CO_2 is 0.294 psia (0.021 kg per square cm). If the absolute pressure of the same mixture of gases increases to the pressure found at a depth of 99 feet (30 m) in the ocean (58.8 psia, or 4.12 kg per square cm), the partial pressure of the CO_2 is 1.176 psia (0.082 kg per square cm). The amount of CO_2 sensed by the body at 99 feet is four times greater than the amount that is sensed at the surface. Breathing 2 percent CO_2 at a depth of 99 feet is the same as breathing 8 percent CO_2 at the surface! A high level of CO_2 has a profound effect on respiration. The surface-equivalent effect of partial pressures makes minute amounts of contaminants in breathing gases unsafe at depth. Table 2.3 shows the surface-equivalent effect of partial pressures at various depths.

Table 2.2 Partial Pressures of Gases in Air at 1 ATA

	Percentage	Partial pressure at 1 ATA	Partial pressure of gas at 1 ATA (metric)
Nitrogen	78%	11.466 psia	0.803 kg/cm^2
Oxygen	21%	3.087 psia	0.2163 kg/cm^2
Argon	0.93%	0.137 psia	0.0095 kg/cm^2
Trace gases	0.04%	0.006 psia	0.0004 kg/cm^2
Carbon dioxide	0.03%	0.004 psia	0.0003 kg/cm^2
Totals	100%	14.7 psia	1.03 kg/cm^2

Table 2.3 Surface-Equivalent Effect of Partial Pressures

Depth	Pressure	O_2*a	CO*b	CO_2*c
0 ft (0 m)	1 ATA	20%	20 ppm	2%
33 ft (10 m)	2 ATA	40%	40 ppm	4%
66 ft (20 m)	3 ATA	60%	60 ppm	6%
99 ft (30 m)	4 ATA	80%	80 ppm	8%
132 ft (40 m)	5 ATA	100%	100 ppm	10%

*Breathing 20% oxygen at 132 ft (40 m) has the same effect as breathing 100% oxygen at the surface.

*Breathing a mixture containing 40 ppm CO at 66 ft (20 m) is the same as breathing 120 ppm CO at the surface!

*Breathing a mixture containing 2% CO_2 at 99 ft (30 m) is the same as breathing 8% CO_2 at the surface and causes shortness of breath, rapid breathing, and headache.

Additional Information About Gas Laws

The following gas formulas can be used to make precise mathematical calculations of pressure, volume, and temperature.

Boyle's law: $P_1V_1 = P_2V_2$

P_1 = Initial pressure (psia or ATA)
P_2 = Final pressure (psia or ATA)
V_1 = Initial volume
V_2 = Final volume

Example: A balloon with 2 pints of air floats from 2 ATA to the surface (1 ATA). What is the volume of the balloon at the surface?

P_1 = 2 ATA
P_2 = 1 ATA
V_1 = 2 pints
V_2 = Unknown

Rearranging the formula to solve for V_2, we find that:

$$V_2 = \frac{P_1V_1}{P_2} = \frac{(2 \times 2)}{1} = 4 \text{ pints}$$

Partial pressure = absolute pressure 3 percentage of gas

Example: What is the partial pressure of oxygen if the gas constitutes 20 percent of a gas mixture that has an absolute pressure of 58.8 psi?

$$PP = 58.8 \times 0.2 = 11.76 \text{ psia}$$

Gay-Lussac's law: $\frac{P_1}{T_1} = \frac{P_2}{T_2}$

P_1 = Initial pressure (psia or ATA)
P_2 = Final pressure (psia or ATA)
T_1 = Initial temperature (°R or °K)
T_2 = Final temperature (°R or °K)

Example: A scuba tank with a pressure of 2,250 psig and a temperature of 70 °F is heated to a temperature of 150 °F. What is the pressure of the scuba tank at the higher temperature? First, convert readings for pressure and temperature to absolute measures.

P_1 = 2,250 psig + 14.7 psia = 2,265 psia
P_2 = Unknown
T_1 = 70 °F + 460 = 530 °R
T_2 = 150 °F + 460 = 610 °R

Rearranging the formula to solve for P_2, we find that

$$P_2 = \frac{P_1T_2}{T_1} = \frac{2,265 \times 610}{530} = 2,607 \text{ psia}$$

$$2,607 \text{ psia} - 14.7 \text{ psia} = 2,592 \text{ psig}$$

When a liquid has absorbed all of a gas that it can hold, the liquid is saturated. When you reduce the partial pressure of the gas in contact with the liquid, gas diffuses out of the liquid. This process is **outgassing**. Ingassing and outgassing provide a foundation for the dive computers and tables used to prevent decompression sickness; these tables are presented in chapter 7.

Air Consumption

The volume of air you breathe per minute during exertion is much more than the volume you breathe at rest—up to 17 times more on land and about 14 times more in the water. In the water, pressure on the torso allows only 85 percent of normal inhalation.

Because the density of the air breathed increases with depth, depth significantly affects the rate at which you consume air. For a given level of exertion, a supply of air lasts only half as long at a pressure of 2 ATA as it does at a pressure of 1 ATA. With heavy exertion at a pressure of 4 ATA (at a depth of 99 feet, or 30 m), you exhaust an air supply over 40 times faster than you would when at rest at the surface! The rapid depletion of your air supply is one reason that you must avoid heavy exertion while diving.

The rate of air consumption is expressed in cubic feet per minute (or liters per minute) or psig (or atmospheres or bars) per minute. By knowing your consumption rate for various levels of activity, you can plan your dives. When you know your consumption rate and the amount of air available, you can calculate air supply duration for future dives.

Heat, Humidity, Light, and Sound

You experience many changes when you enter water. You lose body heat faster, and you lose body moisture when you use scuba equipment. In addition, what you see is deceiving, and what you hear can cause confusion. When you understand what happens to you in water (and why it happens), you can better manage the differences between the water and air environments.

Heat Transfer

The net effect of the various forms of heat transfer is that you can chill quickly while diving. Radiation, convection, and conduction transfer heat from one medium to another (see figure 2.12). Heat waves radiate from exposed surfaces, heat travels upward through fluids by convection, and heat is transferred directly via conduction between substances in contact with each other. Metals are good conductors. Water is a poor conductor compared with metal, but water conducts heat about 25 times faster than air (depending on density). Conduction and convection are the primary means by which heat is transferred from a diver to the surrounding water. Heat rises from the skin, and water carries the heat away. You also lose body heat through the process of evaporation. Moisture evaporates from your lungs when you are breathing underwater and from the surface of your skin when you perspire above water. Scuba equipment expands high-pressure air and cools it. Your body heat warms the air you breathe, and you lose the heat with each exhalation.


Losing or retaining excessive heat is dangerous!
Radiation
Heat waves radiate to surrounding objects without physical contact.
Convection
Heat warms surrounding fluid, which rises and is replaced by cooler fluid.
Conduction
Heat lost through direct physical contact. Water conducts 25 times faster than air!
Evaporation (in air)
Perspiration cools when it changes from a liquid to a vapor.
Respiration
Heat added to air in the lungs is lost with exhalation.

Figure 2.12 Heat transfer and loss.

You can slow the transfer of heat by insulating yourself with a material that is a poor conductor of heat. Exposure suits help insulate you from the environment, but insulation does not help reduce heat lost through respiration. The next chapter presents ways to manage the problems of heat loss.

Humidity

Scuba divers must be aware of the effects of humidity, or the amount of water vapor present in a gas. The temperature of the gas determines the amount of water vapor a gas can absorb and retain. The warmer the gas, the more humidity the gas can contain.

You humidify inspired air. The process of compressing the air that is put into scuba tanks dehumidifies the air in the cylinder. You lose moisture from body tissues when you breathe dry scuba air. The resulting fluid loss can cause partial dehydration, an undesirable condition, especially for a scuba diver. In the next chapter, you will learn how to avoid the problems of dehydration.

Diving poses other humidity challenges that you must manage. Moisture in the air inside your mask condenses on the faceplate as the air cools. Unless you thoroughly clean your mask lens in advance so that the condensation runs off in a thin sheet, foggy beads of condensation will form and blur your vision. Chapter 6 presents the process for cleaning, or defogging, your mask.

Additional Information About Air Consumption

The following air consumption formulas can be used to calculate consumption rates and air supply duration. To calculate the rate of air consumption, you need three items of information: the depth at which you have remained for a period of time, the length of time you have remained at that depth, and the amount of air you have used during that time.

1. Determine your depth air consumption rate (DACR). This is simply the amount of air used divided by the time at depth. For example, the DACR for a diver who uses 1,000 psi (68 atm) in 10 minutes is 100 psi (6.8 atm) per minute.

$$\text{DACR} = \frac{\text{Air used}}{\text{Time at depth}}$$

2. Convert the DACR to the surface air consumption rate (SACR). You need to express the rate in terms of volume rather than pressure. After you do this, you can apply the air consumption rate to any depth and to a cylinder of a different size from the one used initially to calculate the air consumption rate. Obtain the surface consumption rate by multiplying the DACR by the ratio of the pressure at the surface to the pressure at depth. Because you can express pressure in terms of depth, you can use the following formula:

$$\text{SACR} = \text{DACR} \times \frac{33\text{ ft (or 10 m)}}{\text{Diving depth} + 33\text{ ft (or 10 m)}}$$

   If, for example, your depth consumption rate for a depth of 33 feet (10 m) is 30 psi (2 atm) per minute, your SACR is 30 (33/66) = 15 psi per minute, or 2 (10/20) = 1.0 atm per minute.

3. Convert the rate to volume, establish a ratio of the tank volume and pressure (when the tank is full) to the breathing rate volume and pressure, then solve for the breathing rate volume (BRV) as follows:

$$\frac{V_1}{P_1} = \frac{V_2}{P_2}$$

   where

V_1 = Full tank volume

V_2 = Breathing rate volume (BRV)

P_1 = Full tank pressure

P_2 = Breathing rate pressure

   so

$$\text{BRV} = \frac{V_1 \times P_2}{P_1}$$

   For example, the breathing rate volume (BRV) for a diver with an 80-cubic-foot (2,265 L), 3,000 psi (204 atm) tank and an SACR of 30 psig (2.04 atm) per minute is

BRV = 80 ft^3 3 30 psi/min/3,000 psi = 0.8 ft^3/min

Metric BRV = 2,265 L 3 2.04 atm/min/204 atm = 22.65 L/min

4. For the same level of activity, you can calculate the approximate duration (in minutes) of any amount of air from a tank of any size used at any depth. Here is an example: How long will 1,750 psi (119 atm) of air from a 71.2-cubic-foot (2,016 L), 2,475 psi (168 atm) tank last at a depth of 70 feet (21.3 m) for a diver with a breathing rate volume (BRV) of 0.8 cubic feet (22.7 L) per minute?

First, determine the volume of air in the tank at a pressure of 1,750 psi (119 atm). The formula for determining the volume of air in the tank is

$$V_2 = \frac{V_1 \times P_2}{P_1}$$

where

V_1 = Full tank volume

V_2 = Partially filled tank volume

P_1 = Full tank pressure

P_2 = Partially filled tank pressure

The air supply volume for the partially filled tank is therefore

$$V_2 = \frac{71.2 \times 1,750 \text{ psi}}{2,475 \text{ psi}} = 50.3 \text{ ft}^3\text{, or}$$

$$V_2 = \frac{2,016 \text{ L} \times 119 \text{ atm}}{168 \text{ atm}} = 1,428 \text{ L}$$

The formula for air supply duration (ASD) is

$$\text{ASD} = \frac{\text{Air supply volume}}{\text{BRV}} \div \frac{\text{Diving depth} + 33 \text{ ft (or 10 m)}}{33 \text{ ft (or 10 m)}}$$

The air supply duration (ASD) for the question posed earlier is

$$\text{ASD} = \frac{50.3 \text{ ft}^3}{0.8 \text{ ft}^3 / \text{min}} \div \frac{70 \text{ ft} + 33 \text{ ft}}{33 \text{ ft}} = 20 \text{ min}$$

$$\text{Metric ASD} = \frac{1,428 \text{ L}}{22.7 \text{ L} / \text{min}} \div \frac{21.3 \text{ m} + 10 \text{ m}}{10 \text{ m}} = 20 \text{ min}$$

These calculations may seem complicated at first, but the ideas are simple. The calculations become easy with practice. Let’s review the four steps of air consumption calculations: (1) Determine your depth air consumption rate (DACR); (2) determine your surface air consumption rate (SACR); (3) determine your breathing rate volume (BRV); and (4) determine the air supply duration (ASD) for a quantity of air. The abbreviated formulas for the calculations are as follows:

$$\text{DACR} = \frac{\text{Air used}}{\text{Time at depth}}$$

$$\text{SACR} = \text{DACR} = \frac{33 \text{ ft (or 10 m)}}{\text{Diving depth} + 33 \text{ ft (or 10 m)}}$$

$$\text{BRV} = \frac{V_1 \times P_2}{P_1}$$

$$\text{ASD} = \frac{\text{Air supply volume}}{\text{BRV}} \div \frac{\text{Diving depth} + 33 \text{ ft (or 10 m)}}{33 \text{ ft (or 10 m)}}$$

In freezing temperatures, moisture from your exhaled breath can cause a scuba regulator to freeze. Water in other items of diving equipment can also freeze. If you intend to dive in a cold environment, you should complete special training and should know how to prepare and use your equipment in those conditions.

Light and Vision

The density of water makes it challenging for divers to interpret what they see and hear. Light travels faster in air than in water. When rays of light traveling in water pass through the lens of your mask, they accelerate and bend (refract). The effect is that what you see underwater is magnified. Objects appear to be at three-fourths of their actual distance (25 percent closer) and four-thirds of their actual size (33 percent larger). The visual distortion requires adjustments, and you will learn to make these with experience. An object that is 12 feet (3.7 m) away appears to be only 9 feet (2.7 m) away. A fish that appears to be about 2 feet (0.6 m) long is actually only 1.5 feet (0.5 m) in length. Many new divers discover that items they bring back from diving are much smaller than they perceived them to be underwater. Figure 2.13 illustrates how light is perceived differently in water.

One difficulty caused by the refraction of light is that distant objects appear closer than they are. This can create a hazard in clear water when you look downward from a drop-off. You may be tempted to go to a point that appears to be at a safe distance but might actually take you beyond your planned maximum


External reflection
All light reflected from the surface of smooth water
Angle 48.5° or less
Angle 48.5° or less
Internal reflection
All light reflected from the underside of the surface
Light rays
Reflection
Refraction
Diffusion
Color absorption
0 ft
15 ft
30 ft
45 ft
60 ft
75 ft
100 ft
Reds
Oranges
Yellows
Greens
Blues
Greys
Reflection, refraction, diffusion, and absorption are factors affecting light in water. Refraction has the most effect on underwater vision.
Refraction
Air
Fish looks closer and larger
Actual fish

Figure 2.13 Visual perception is distorted underwater.

SCUBA WISE

There is an old joke about a young woman who returned home from her first session of scuba diving training and was unenthusiastic when asked whether she enjoyed the class. Her reply was "First the instructor told us all the ways that we could die, then he worked us in the water until I thought that I was going to die." Fortunately, instructors do not teach classes that way today. The reason for learning about potential injuries is to understand how to prevent them. Armed with knowledge that you can convert to wisdom through proper application, you can avoid all of the potential problems identified in this chapter. The use of scuba diving instruction for fitness training is also outdated. Reasonable physical fitness is a prerequisite for scuba diving. Any healthy person who can swim 200 yards (61 m) continuously is fit enough to dive. The objective of modern scuba training is to help you learn to relax in and under the water, not to whip you into shape.

depth. You must realize that distance perception is inaccurate, and you must rely on your depth gauge instead of your vision.

You have two types of vision: day vision and night vision. You use different parts of your eyes for each type. When you move from a brightly lit area into a dimly lit area, your vision needs 15 to 30 minutes to adapt to the lower level of light. Even after the adaptation, your ability to see fine details is much less than your ability with day vision. In addition, particles in water diffuse, scatter, and attenuate light. The deeper you go, the less light there is. In **turbid** water, the amount of light decreases very quickly with depth. A dive in turbid water involves a change from day vision to night vision.

Water affects light in many ways. The surface of water reflects light. When light strikes the surface of calm water at an angle less than 48 degrees, the water reflects all the light. Early morning and late afternoon sunlight do not penetrate calm water. Light rays going toward the surface from underwater also reflect from the interface, making the underside of the surface appear like a mirror when viewed at the proper angle.

Objects you view underwater often lack their natural colors. White light, such as sunlight, comprises all the colors of the spectrum. Increasing depth absorbs various colors. The water absorbs warm colors, such as red and orange, with only 30 feet (9 m) of depth. Cooler colors, such as blue, penetrate deepest. This is why deep, clear water is blue. The underwater scene appears drab at depths below 100 feet (30 m). Fortunately, you can restore all the colors of the spectrum underwater by using an artificial light at close range.

Another visual challenge is disorientation. When you are weightless in water and do not have a visual reference, **vertigo** can result. Vertigo is the feeling of movement perceived as a spinning sensation. This problem can occur when the water is turbid and visibility is poor, when the water is crystal clear but there are no visual clues for orientation, and when waters of different densities mix together. You will learn how to manage the challenges of disorientation in the next chapter.

A final visual problem is poor visibility in water compared to air. In air environments, visibility is measured in miles, but in water it is measured only in feet. Particles suspended in water cause turbidity, which hampers vision. Reduced visibility makes it difficult to locate objects underwater, to maintain contact with your buddy, and to find your way. You must develop skills to cope with these challenges, including search techniques, buddy system techniques, and underwater navigation skills.

Sound and Hearing

Sound travels well in water. You can hear many sounds while diving. On land you can determine the direction of a sound by the difference in the time it takes the sound to reach one ear and then the other. This interval is brief but sufficient for your brain to discern it. Underwater, you hear sound conducted through water and the bones of your head to your inner ears. Sound travels about four times faster in water than in air. The time delay between a sound reaching one ear and then the other is so small that directional discernment is difficult underwater.

Sound does not transfer well from air to water. Only 0.01 percent of sound can travel directly between air and water. You must use special devices to make voice communications effective underwater.

Summary

The aquatic environment affects your body in several ways. Pressure affects your air spaces: your ears, sinuses, and lungs. The rate of change of pressure in water is many times greater than in air and increases as you approach the surface during ascent. Changing pressures also affect the diffusion of gas into and out of liquids. The level of carbon dioxide in your body controls your respiration, and the partial pressure of the carbon dioxide is affected by depth. Temperature also affects the pressure of a constant volume of gas. Depth and activity have the greatest effect on air consumption. Water absorbs heat from the body, so divers need insulation to help prevent excessive heat loss. Humidity can cause several problems for scuba divers. The difference in density between air and water affects your buoyancy, mobility, heat loss, vision, and hearing. Now that you are aware of the effects of the aquatic environment on your body, you are prepared to learn to adjust to the underwater environment.

Application-of-Knowledge (AOK) Questions

1. If you are exerting underwater and find yourself breathing rapidly and deeply and suddenly feel that you are not receiving enough air, what should you do?
2. A sudden change of conditions while you are diving increases your anxiety, and you notice that your breathing is rapid and shallow. Your anxiety level increases because you feel unable to manage the situation in which you find yourself. What action will help alleviate your anxiety and abnormal breathing?
3. While diving with an experienced diver, you compare tank pressures and discover that you are using twice as much air as your buddy, who is the same size as you. You are using equipment that is identical to your buddy's. What could be causing you to have the high rate of air consumption?
4. Maintained scuba equipment is extremely reliable, but if your regulator started leaking water when you inhaled and you were at a depth of 60 feet (18.3 m), what should you do?
5. While swimming in a pool, you notice a swimmer breathing rapidly and deeply before swimming underwater. You keep an eye on the swimmer because he may lose consciousness without warning while submerged. What is the cause of this problem, and what could you tell the swimmer to help him understand how to prevent an accident?
6. You are diving in water that has a temperature of 60 °F. (15.6 °C) and begin shivering. You decide to increase your activity level to produce more body heat. Is this a good course of action?

Cup corals in the Red Sea

3

Diving Adjustments

Dive In and Discover

By the end of this chapter, you will be able to do the following:

- Define the terms *hypothermia*, *hyperthermia*, *vasoconstriction*, *heat exhaustion*, *heatstroke*, *equalization*, *Toynbee maneuver*, *Valsalva maneuver*, *trapdoor effect*, *skip breathing*, *barotrauma*, *pulmonary barotrauma*, *arterial gas embolism*, *mediastinal emphysema*, *subcutaneous emphysema*, *pneumothorax*, *vertigo*, *perfusion*, *ambient pressure*, *half-time*, *compartment*, *controlling compartment*, *decompression illness*, *dehydration*, and *nitrogen narcosis*.
- State the cause, effect, signs and symptoms, first aid treatment, and prevention of hyperthermia, hypothermia, squeezes, reverse blocks, respiratory distress, pulmonary barotrauma, vertigo, seasickness, decompression illness, and nitrogen narcosis.
- Explain three ways to control buoyancy while scuba diving.
- Explain when to equalize pressure in your ears during descent and what to do if the pressure does not equalize.
- Explain how to minimize resistance to movement for underwater swimming.

To function effectively underwater, you need specific attitudes, equipment, knowledge, and skills. This chapter provides the fundamental knowledge and begins shaping the attitudes required to minimize the risk of injury. You will apply the basic aspects of anatomy, physiology, and physics you have learned to a typical person descending into the depths and ascending back to the surface.

Thermal Adjustments

Maintaining your body's core temperature within a few degrees of normal is challenging in water. When you are immersed in water, you lose body heat rapidly. A water temperature of 50 °F (10 °C) can incapacitate an unprotected diver within 15 minutes. Even water at a temperature of 80 °F (27 °C), which feels relatively warm, can chill a diver within an hour. Wearing only a bathing suit in 80 °F (27 °C) water is the same as being without any clothing in air that is 42 °F (6 °C).

Your brain regulates your body functions to maintain your body temperature. If your core temperature is less than 95 °F (35 °C), you will suffer from **hypothermia**. You need to guard against mild and severe hypothermia, both of which can be dangerous. If your core temperature is higher than normal, you experience the effects of **hyperthermia**. You need to understand the effects of two types of hyperthermia—heat exhaustion and heatstroke—and you must try to prevent them. They both can be dangerous.


Anemone in Bonaire

In chapter 2, you learned about the effects of water on your body. In this chapter, you will learn how to deal with those effects. Most people with average intelligence and normal health can make adjustments to the aquatic environment, such as buoyancy control and the equalization of pressure. You make many adjustments automatically, but some you must make consciously. Learning to make the transition from an air environment to an underwater environment requires professional instruction and guidance. You need to learn what to do, then do what you have learned.

Heat Loss

Your body has a variety of physiological responses to the loss of heat. Respiration increases automatically when you get chilled. This is undesirable because you heat and moisturize inspired air, and you lose the heat and moisture with each exhalation. The more you breathe, the more heat and moisture you lose to the environment (and the shorter your dive time). Water depth compounds the problem because the greater the surrounding pressure, the greater the density of the air that you breathe. Denser air absorbs more heat than air that is less dense. The deeper you dive, the quicker you get cold.

Anything that affects the function of your body—excitement, fear, seasickness, and other forms of illness—can increase heat loss. This is why good health and a confident state of mind are safety recommendations.



Figure 3.1 Areas prone to high heat loss.

One way your body responds to cold is to shunt blood from the extremities through **vasoconstriction**. The circulatory shunting reduces heat loss because it keeps warm blood from passing through areas of your body that have little insulation. Your head, neck, underarms and sides, groin, hands, and feet are the areas of your body most prone to heat loss underwater (see figure 3.1). Fortunately, you can insulate these areas easily. In cold water, you can lose considerable heat from your head and neck because the head receives a large supply of blood and lacks natural insulation. Your body does not shunt blood from your head as it does from other body extremities. In water at a temperature of 70 °F (21 °C) or less, you must be sure to insulate your head and neck.

Hands have large surface areas relative to their volume. To prevent excessive heat loss from your hands when you get cold, your body shunts blood from them until they reach a temperature of 50 °F (10 °C). At this temperature, your body restores circulation to your hands to partially rewarm them. Hands quickly lose their warmth to the water. If you dive without hand protection in cold water, you lose body heat through your hands. Because your hands may become numb and lack strength when they get cold, you should insulate them to keep them functioning and to conserve body heat.

Small people chill more quickly in water than large people do. Small people have less muscle mass to generate and store heat. Insulation is important for all divers, but protection against heat loss is more critical for those of smaller stature.

Failure to wear adequate insulation leads to hypothermia. Hypothermia also results from repeated or prolonged exposure. Slow chilling of your body is undesirable. You lose muscle strength and feeling, and your muscles may cramp. Severe heat loss also affects your ability to reason. Another body response to heat loss is shivering, which restores heat through muscular activity. Shivering, which generates about five times as much heat as your body produces at rest, is helpful on land, but is not beneficial in water. Water conducts away the heat you produce by shivering, and you get colder. Uncontrollable shivering indicates that you have lost too much heat from the core of your body and that you cannot rewarm yourself without getting out of the water. When you are shivering, you should terminate the dive. Rewarm yourself thoroughly before diving again. To help your body temperature return to normal, you should put on clothes that are warm and dry, stay in warm surroundings, and consume warm nonalcoholic drinks. You can become so cold that shivering ceases. This occurs because severe hypothermia has incapacitated the body's ability to produce heat. A cold person who is not shivering requires medical care.

You must understand that warming the surface of your body is different from warming the core of your body. You may feel warm, but your deep core temperature may remain below normal. If you return to the water in this condition, you will quickly become chilled. The only way to be sure that you are thoroughly warmed is to keep warming yourself until you begin to perspire. Perspiration occurs when the core temperature begins to rise above normal. To warm yourself, get dry, wrap everything except your face in blankets, and stay that way until you perspire. Most people will shed the blanket when their skin is warm, not being aware that the core of their body is still below normal temperature.

Overheating

You can prevent excessive loss of body heat by insulating your body with an exposure suit, but insulation can cause another problem. When you insulate your body to reduce heat loss in water, you reduce your body's ability to rid itself of excess heat above water. The evaporation of perspiration helps cool your body, but if you cover your body, perspiration cannot evaporate. You may become overheated in warm climates when you are preparing to dive. Maintaining your body temperature within acceptable limits before, during, and after dives can be a challenge. Figure 3.2 describes some of the causes and effects of overheating.

When a person is unable to stop the rise of core temperature, **heat exhaustion** occurs. This condition is serious. A person affected by heat exhaustion becomes weak and may collapse. The victim looks pale and feels sweaty. Place a person with this condition in a cool place, remove the exposure suit, and take steps to lower the person's body temperature. If the victim is alert and not nauseous, have him or her drink a diluted electrolyte fluid or water to replace lost body fluids.

A more serious form of hyperthermia is **heatstroke**, which occurs when the body temperature becomes so high that the body's temperature-regulating ability shuts down. A victim of heatstroke looks flushed and has hot, dry skin. The mental status of a heat stroke victim is not normal. The victim may be delirious, or unresponsive, or have seizures. Heat stroke is extremely serious. Cool the patient's body immediately and summon medical assistance.


Minimize exertion and exposure to direct sunlight.
Insulation reduces your ability to get rid of excess body heat.
Unfit and overweight people are more susceptible to overheating.
Heat exhaustion
• Collapse
• Pale appearance
• Skin cool and clammy
Heatstroke (a medical emergency)
• Collapse
• Flushed appearance
• Skin hot and dry

Figure 3.2 Take precautions against overheating by learning the symptoms of heat stroke and exhaustion.

Preventing hyperthermia is much better than treating it after it occurs. You should avoid prolonged exposure to warm temperatures when wearing insulation. If the air temperature is warm, douse yourself with water after donning your exposure suit and before donning the remainder of your diving equipment. Stay out of direct sunlight if possible. All thermal considerations for diving are especially important for divers whose physical fitness is marginal.

Buoyancy Adjustments

Exposure suits and other equipment affect your buoyancy. You must adjust the amount of weight you wear to control your depth in the aquatic environment. When you are too buoyant, you must fight to remain submerged; when you carry excess weight, you must work hard to keep from sinking or to stay off the bottom. You need to maintain neutral buoyancy underwater and positive buoyancy at the surface. In chapter 2, you learned the principle of buoyancy and the three states of buoyancy: positive, negative, and neutral. Now you will learn some practical applications of buoyancy.

Your body—which is composed of solids, liquids, and air spaces—has an average density nearly the same as water. A typical human body immersed and relaxed in water has a positive buoyancy of a few pounds when the lungs are filled with air; it has a negative buoyancy of a couple of pounds when the lungs contain the minimum amount of air. Fortunately, the density of water and resistance to movement prevent you from moving up and down rapidly when you breathe.

Factors Affecting Buoyancy

People usually wear some type of exposure suit when diving. Most exposure suits increase buoyancy, so divers wear weights to offset the buoyancy of the suit and achieve neutral buoyancy. These weights are made of lead, which is about 12 times denser than water.

Your initial state of buoyancy in water will depend on the volume of water you and your equipment displace. You can vary your volume—with a negligible increase or decrease in your weight—by adding air to or venting air from your buoyancy compensator (BC). Increasing BC volume increases buoyancy, while decreasing BC volume decreases buoyancy.

Your buoyancy is affected by your physical size and weight, your lung capacity, the equipment you wear, and the items you carry (see table 3.1). Exposure suits use air or small bubbles of gas for insulation. When you descend while wearing an exposure suit, pressure compresses your suit and reduces its volume, so you become less buoyant. You must add air to your BC to compensate for buoyancy lost from suit compression. On the other hand, buoyancy increases as you consume air from your scuba cylinder. Air weighs 0.08 pounds per cubic foot (1.3 g per L). A typical scuba tank contains 80 cubic feet (2,265 L) of air. A full tank weighs 6 pounds (2.7 kg) more than an empty tank. As you consume air from your scuba tank, you must vent some of the air that you added to your BC to compensate for suit compression. The trade-off helps you keep buoyancy constant during a dive.

Inflating your lungs increases your buoyancy, while deflating them reduces buoyancy. A high average lung volume makes you float; a low average volume makes you sink. When you become excited or begin moving quickly, your respiration increases, which affects your buoyancy. For optimal control of buoyancy, you should maintain a calm, relaxed state.

The density of water also affects buoyancy. Saltwater is denser than freshwater, so you are more buoyant in the ocean than in a lake. This means that if you

Table 3.1 Factors Affecting Buoyancy

Factor	Effect
Size and weight of diver	Obese divers are more buoyant.
Type and amount of equipment	Larger equipment is more buoyant (because of increased volume).
Amount of weight worn	Weights decrease buoyancy.
Amount of air in BC	Increasing volume increases buoyancy.
Amount of air in tank	Buoyancy increases as air decreases.
Amount of air in lungs	Exertion or excitement increases volume and buoyancy.
Suit compression	Pressure decreases volume and buoyancy.
Items carried	Added weight decreases buoyancy.
Type of water (salt or fresh)	Denser water increases buoyancy.

SCUBA WISE

At some point, many divers discover a special feeling of becoming part of the underwater world. I remember vividly an overwhelming feeling—a strange combination of peace and exhilaration—that I experienced during a dive in the Red Sea. The goal of training is to help you adjust to a new environment. When you adjust, you can relax, and when you can relax, you can focus more on your exciting new surroundings than on yourself. Meeting the demands of diving is challenging, but when you succeed, the exuberance is worth every adjustment you have to make. People can adjust well to new situations. Training helps people adjust more quickly, easily, and safely than they can by trial and error. Study the remaining chapters carefully to learn how to adjust to the subaquatic environment. I want you to feel what I felt in the Red Sea and have felt many times since while diving. The feeling of being one with the sea is powerful, moving, and unforgettable.

are weighted for neutral buoyancy in the ocean, you must remove some weight to achieve neutral buoyancy for freshwater diving. The amount of weight you remove is about 3 percent of the combined dry weight of you and your equipment. For example, if a neutrally weighted 160-pound (73 kg) diver with 60 pounds (27 kg) of equipment, including 16 pounds (7 kg) of weights, wants to dive in freshwater instead of seawater, the diver must remove about 7 pounds (3 kg) of weight in order to be weighted correctly.

Ways to Control Buoyancy

As a diver, you can control buoyancy in three ways: by the amount of weight you wear and carry, by the amount of air in your BC, and by the amount of air in your lungs. These means of control are coarse, medium, and fine adjustments, respectively. The skills you need to learn in order to adjust to the aquatic environment include determining the correct amount of weight to be worn, regulating the amount of air in your BC, and varying your breathing for minor buoyancy adjustments. Chapter 6 describes these skills.

Pressure Equalization

One of the most important adjustments you must learn is how to handle the effects of pressure changes in water. Pressure changes rapidly as you descend and ascend. To avoid discomfort and injury, you must keep the pressure in the air spaces inside and on your body equalized with the outside pressure. This section identifies the procedures for pressure equalization.

Equalizing Pressure in the Sinuses

Your sinuses equalize pressure automatically as long as they are healthy. But when you have a cold or respiratory illness, the membranes lining your sinuses become swollen. The swelling can close the narrow air passages leading to the sinuses. If you descend with swollen sinus membranes, a sinus squeeze will result. Because the sinuses are formed in bone, they do not compress as a flexible container does. When the pressure inside the sinuses is less than the surrounding pressure, the outside pressure causes the linings of the sinuses to swell and ooze fluids into the cavities. The swelling and fluid reduce the volume and compress the air that is there. Do not attempt this painful method of equalization because your problems are not over after you descend. When you ascend in this condition, the compressed air in the sinuses expands to its original volume. The expansion can force the fluid in your sinuses out through the openings, which are swollen shut. Avoid this painful process; don't dive unless your sinuses are clear and normal. Figure 3.3 shows what happens to both healthy and congested sinuses under pressure.



Air can move freely in and out of a healthy sinus (A), so equalization is automatic during descent (B) and ascent (C).



Air cannot get into or out of a congested sinus (A). The body forces fluids into the sinus at depth to equalize the pressure (B). The air in the sinus tries to expand to its original volume during ascent (C).

Figure 3.3 The mechanisms of equalizing pressure in the sinuses.

Do not use medications to relieve stuffiness and congestion caused by an illness before you go diving. Increased pressure can reduce the medication's effects and the duration of its effectiveness. Decongestants do not cure an illness; they simply mask its symptoms. When medication taken to open swollen airways wears off, a rebound effect occurs. The airways become more swollen than they were before you took the medication. If the rebound occurs while you are diving, you can trap high-pressure air in your sinuses. If you are not well enough to dive without medications, you should not dive.

Equalizing Pressure in the Ears

You must equalize the pressure in your ears more often than any other air space. Whereas the air passages to your sinuses are normally open, the **eustachian tubes** from your throat to your ears are normally closed. You must learn how to open the tubes at will to allow air to pass through them and equalize pressure in the air spaces of your middle ears.

You can make several movements to open the ends of the eustachian tubes where they connect with the throat. Swallowing, yawning, lifting the base of your tongue, and jutting the jaw forward (either individually or in combination) should produce a cracking sound in your ears. The opening of the tubes causes the sound. Some divers are fortunate because they can use simple movements to equalize pressure in their ears during descent. Most people require a more forceful means of equalization. Many divers use a technique known as the **Toynbee maneuver**, which you do by blocking your nostrils, closing your mouth, and swallowing. The **Valsalva maneuver** is even more forceful and is done by blocking your nostrils, closing your mouth, and gently attempting to exhale.

You must avoid excessive force when you use the Valsalva method because you could damage your ears permanently by rupturing the round window. When pressure in the outer ear increases, the eardrum bulges inward. The bones of hearing in the middle ear transmit the movement to the oval window in the inner ear. When you attempt to exhale against closed airways, you create an internal pressure on your inner ears. The attempted exhalation pressure in conjunction with the external pressure exerted on the oval window can cause the round window to rupture; this is a serious injury that can result in a permanent high-frequency hearing loss and constant ringing in the ear. Because you control how hard you attempt to exhale in a Valsalva maneuver, you can prevent this injury. Be careful!

You must equalize pressure in the air spaces of your middle ear early (before descent) and frequently. If you delay equalization during descent, increasing pressure will hold your eustachian tubes closed—and if you attempt to force air through them, this will only close them tighter. This is the **trapdoor effect**, a difficulty you can avoid by keeping the pressure in your middle ears and your throat equal. You can then open your eustachian tubes and allow air to pass through them. Figure 3.4 shows the trapdoor effect.

You should equalize pressure in your ears before descending and about every 2 feet (0.6 m) for the first 15 feet (4.6 m) of descent, about every 3 feet (0.9 m) from 15 to 30 feet (4.6 to 9.1 m), and as needed thereafter. You can feel and hear air enter your ears when you eliminate any difference in pressure. If you attempt to equalize pressure but cannot get air into your ears, you should ascend several feet to reduce the pressure on your eustachian tubes and try again. If that works, continue your descent. If that does not work, ascend a few more feet and try again. Your initial descents may be somewhat jerky until you become accustomed to equalization techniques.

Failure to equalize pressure in your middle ears is as bad as trying to equalize forcefully. In an unequalized middle ear, pressure bows the eardrum inward. If the squeeze continues, pressure forces blood and fluid into the middle ear. This

Methods to equalize pressure:
- Blowing gently with mouth closed and nostrils blocked.
- Swallowing with mouth closed and nostrils blocked.
- Jutting the jaw forward while yawning with mouth closed.



When pressure is not equalized often during descent, the pressure difference holds the end of the eustachian tube closed and prevents any further equalization until the diver ascends enough to relieve the pressure.

Figure 3.4 Helpful techniques for pressure equalization.

process takes time, but it is usually painful. It also damages the ear. If you feel discomfort or pressure in your ears during descent, you should ascend until the pain is gone, and then ascend another couple of feet before trying to equalize.

If you ignore an ear squeeze and continue your descent, the pressure differential can rupture your eardrum. The rupture instantly equalizes the pressure in your middle ear but damages your ear in the process. A rupture of your eardrum causes a temporary loss of hearing and a feeling of fullness in your ear. Cold water rushing into the middle ear can also cause temporary disorientation (see the section on Equilibrium Adjustments and Seasickness later in this chapter). If you suspect an ear injury, see a physician; prompt treatment can minimize the risk of permanent injury.

You can cause an outward rupture of an eardrum if you block the ear canal with a plug or if you cover your ears with a watertight covering. When you obstruct an ear canal, the air in your outer ear remains at surface pressure while the pressure in your middle ear increases with equalization during descent. The difference in pressure between the middle and outer ear pushes the eardrum outward until it breaks. You can prevent such an injury. Do not wear earplugs while diving, and avoid waterproof seals over your ears.

Equalizing is easier when you descend in an upright position as opposed to a head-down position. Membranes line the airways in your head, and gravity affects blood in the vessels within the membranes. When you are upside down in water, the membranes of your air passages swell and narrow.

Difficulties with ear equalization during ascent are uncommon. Air expanding inside the middle ear escapes through the eustachian tube. Air passes out through the tube much more easily than it goes in; you do not have to do maneuvers to open your tubes so the air can escape. But if a plug of mucus happens to block a tube, pressure can build up in the middle ear and cause an uncomfortable reverse block. If you feel pain or pressure in an ear during ascent, stop the ascent. Excess pressure inside the ear usually works its way out if given time. If you are forced to surface, the pain will increase, and an injury can result. Have the ear examined by a physician, especially if you have recurring reverse blocks.

Equalizing Pressure in the Mask

The air space inside the dive mask is affected by changes in pressure. If you descend without increasing the amount of air inside your mask, pressure pulls your face and eyes into the mask slightly. The pulling sensation, if ignored, ruptures capillaries in your eyes and on your face and causes a mask squeeze. After a mask squeeze, the whites of your eyes will be red, and your face will be red and puffy. There is no excuse for a mask squeeze. You can prevent the problem by exhaling through your nose as needed during descent to keep the pressure inside your mask equal to the surrounding pressure.

Breathing Adjustments

Breathing while in water differs from breathing while on land in several ways. You cannot breathe as freely in water as you can on land. Pressure on the lungs from immersion in water prevents you from breathing as fully as you can in air. Also, it is not as easy to get large quantities of air from a scuba system as it is to breathe deeply above water.

When you ascend, compressed air in your lungs expands, which can cause your lungs to rupture unless you allow the excess air to escape. A normal breathing pattern allows expanding air to escape; breath holding does not. A primary rule of scuba diving is to always breathe continuously.

There is a chance that you will inhale some water. This may cause you to choke and gasp when the water strikes your vocal cords. You need to learn the correct methods of breathing while in and under the water.

Lung Overexpansion

The most important aquatic breathing adjustment is overcoming the instinct to hold your breath underwater. When you breathe compressed air at depth, the density of the air in your lungs is greater than it is at the surface. When you ascend, the air in your lungs expands as the surrounding pressure decreases. If you hold your breath, your lungs expand until they reach their maximum volume, then rupture with an ascent of as little as 4 feet (1.2 m). You must avoid breath holding when breathing compressed air underwater. You should breathe continuously or exhale a small amount of air continuously, and you should never hold your breath during ascent after breathing compressed air. Figure 3.5 illustrates why you must breathe continuously, and the section following the figure describes the possible consequences of breath holding while ascending with compressed air in your lungs.

Skip Breathing

Some divers attempt to extend their air supplies by holding each breath for several seconds. This dangerous practice is called **skip breathing**. When you hold your breath, you increase the amount of carbon dioxide in your circulatory system, which increases your urge to breathe and reduces your breath-holding ability. A high level of carbon dioxide in your body will reduce your ability to cope with difficulties that may arise. And if you skip breathe, you may forget to exhale while ascending, or you may have a headache after the dive. You must be sure to breathe continuously when breathing compressed air.

Breathing Problems

Divers can encounter respiratory difficulties if they overexert themselves, breathe contaminated air, inhale water, or run out of air. Fortunately, you can prevent all of these problems.

Overexertion

Scuba equipment allows you to breathe comfortably while underwater. A regulator delivers air with little respiratory effort, but breathing underwater requires more effort than breathing above water. If you do not maintain your scuba equipment properly, the effort required to inhale and exhale can be excessive and can cause respiratory distress.

Scuba regulators have a limited capacity to supply air. Regulators are not designed for activities involving heavy exertion. Commercial divers use helmets with air hoses to supply large amounts of air to meet their requirements while working underwater. You must avoid strenuous activities underwater because


Exhaling ascent
Non-exhaling ascent
V = Volume
D = Density
P = Pressure
V = 1
D = 1
P = 1
V = 1
D = 2
P = 2
33 ft
Lungs over-pressured
V = 1
D = 3
P = 3
66 ft
V = 1
D = 4
P = 5 ⅓
V = 1
D = 4
P = 4
99 ft
V = 1
D = 4
P = 4

Figure 3.5 **A breath-holding ascent after breathing compressed air can cause lung rupture. Breathe continuously while ascending.**

you can overbreathe your equipment and experience air starvation, a suffocating feeling of not being able to get enough air.

While diving, you should make your breaths longer and slower than your breaths on land. Pace your activity to keep respiration at a slow, controlled rate. If breathing becomes rapid or labored, cease all activity immediately and focus on exhaling deeply until your respiration returns to a controlled rate.

Contaminated Air

If the compressed air in your tank comes from an air compressor that is not operated or maintained properly, your tank can contain contaminated air. The contamination is likely to be carbon monoxide (CO), a gas produced by incomplete combustion. CO in the body impedes the blood's ability to transport oxygen. Blood hemoglobin's affinity for CO is 210 times greater than its affinity for oxygen. Hemoglobin normally exchanges oxygen for CO_2 about every half minute, but when CO attaches to hemoglobin, the contaminant remains bonded to the hemoglobin for hours. Breathing contaminated air under pressure can make you ill and render you unconscious. Avoid contaminated air by having your tank filled only with pure air. CO is an odorless, tasteless gas, but it is usually accompanied by other gases that have a foul taste and odor. If the air from a scuba tank smells or tastes foul, do not use it. Report the situation immediately to the facility that filled the cylinder. Good air stations have their air tested regularly to ensure purity.

Water Inspiration

If you inhale water, your larynx spasms as a reflex action to keep the liquid out of your lungs. Avoid coughing and choking in water; not only are these reflexes unpleasant, but they can cause you to inspire more water and lose buoyancy. You need to breathe differently underwater than you do on land. Avoid quick inhalations. Begin a breath with a light, slow inhalation to ensure that you are inhaling air and not water. Once air begins flowing, the remainder of your inhalation can be normal.

You can also prevent droplets of water from going down your throat by placing the tip of your tongue on the roof of your mouth behind your upper teeth to act as a splashboard. If, in spite of all you do to avoid it, you inhale some water and start coughing, try swallowing hard three times in rapid succession. The swallowing helps you overcome your coughing reflex.

If water does enter your lungs, it interferes with respiration. If an extensive area of the lungs is irritated by water, you can drown. This is a risk you face in any aquatic pastime. The purpose of your training is to allow you to enjoy the aquatic environment with the minimum risk of injury, especially of drowning. When you follow the rules and practices that you are taught, the risk of injury while diving is negligible.

An automatic response to the inhalation of water is to swallow it in an effort to keep your airways dry. When you swallow saltwater, you can experience illness, nausea, or diarrhea. If you swallow several mouthfuls of saltwater while diving, you should terminate the dive.

Running Out of Air

Some divers do not monitor their air supplies and run out of air at depth. Running out of air underwater is no more excusable than running out of gas on the freeway when you have a working gauge. There are ways to manage an out-of-air situation (which you will learn in chapter 6), but it is much better to avoid the problem by monitoring your instruments and keeping them in working order.

Potential Lung Injuries

Pulmonary Barotrauma

Barotrauma is trauma or injury caused by pressure. **Pulmonary barotrauma** is any lung injury caused by pressure. Failure to allow expanding air to escape from the lungs during ascent can cause several forms of pulmonary barotrauma, either singularly or in combination.

Arterial Gas Embolism


Air embolism

An **embolism** is a blockage of circulation. An embolism resulting from an air bubble blocking the arterial circulation is an **arterial gas embolism** (AGE). This occurs when air expanding in the lungs forces bubbles of air into the circulation. Air bubbles enter the capillary beds of the lungs and pass through the heart, which pumps the bubbles into arteries supplying blood to the body. The diameter of an artery decreases as the distance from the heart increases. At some point, a bubble lodges in an artery and becomes an embolus (plug). It is common for an arterial gas embolism to occur in an artery leading to the brain. The embolus has the effect of a stroke, causes unconsciousness, and is an extremely serious injury. Anytime a diver loses consciousness after a dive, you should suspect AGE. The temporary obstruction of an airway, such as that caused by a cold, increases the risk of AGE. Healthy lungs are a prerequisite for diving.

Mediastinal Emphysema


Mediastinal emphysema

If a rupture of the lung does not force air into the circulation, the air may travel along the bronchi and enter the middle area of the chest (called the mediastinum). This results in a **mediastinal emphysema**, which means that air is in the tissues in the middle of the chest. The injury causes a dull ache or tightness that worsens with coughing, swallowing, or taking a deep breath. Expanding air can interfere with the circulation of the heart and cause loss of consciousness.

Heart and Lungs

Immersion changes your cardiac workload. When you are upright in water, there is greater pressure on your lower limbs than on the upper part of your body. The pressure differential shifts more blood than normal into the upper part of your body. Your heart pumps a greater volume with each beat and works from 1.3 to over 1.5 times harder in this situation than it does on land.

Water temperature alters your heart's rate and rhythm. In addition, physical and emotional stress make your heart work harder. The combined effects of water pressure, exercise, cold, and stress can cause serious problems if your heart is not healthy. If you have heart problems and wish to dive, you should first obtain medical approval from a diving physician. Even minor heart problems can cause you to suddenly lose consciousness in the water, and you could drown. Fitness for diving is an important safety issue.

Subcutaneous Emphysema

Expanding air in the mediastinum can migrate upward along the breastbone. The air then swells the tissues around the neck, producing an injury known as **subcutaneous emphysema**, which means that air is in the tissues under the skin. The injury can cause changes in the voice, crackling of the skin, and a feeling of fullness in the neck.



Subcutaneous emphysema

Pneumothorax

If a lung rupture forces air into the space between the lungs and the lining of the chest wall, a condition known as **pneumothorax** occurs. This means that air is trapped in the chest cavity. As the air trapped in the pleural space expands during ascent, it collapses the lung and can affect the action of the heart. Symptoms include severe pain and breathing difficulty.



Pneumothorax

Lung injuries are serious and can be life threatening. Life support may be required. This is one reason that you should complete a course in cardiopulmonary (heart and lung) resuscitation (CPR). You may have to administer first aid until professional medical treatment (which all lung injuries require) is available.

Failing to allow excess air to escape causes nearly all lung overexpansion injuries. You can prevent injuries by breathing continuously. If you remove the scuba regulator from your mouth for any reason, exhale lightly and continuously to avoid breath holding.

Cold water increases the effort required by your heart because cold causes the body to reduce circulation to the extremities in order to conserve heat. With more blood in the core of the body and an increased workload from pressure, your heart may not be able to pump the increased blood volume. The result can be excess blood in the small blood vessels of the lungs. These small blood vessels will transfer fluid to the air spaces of the lungs to reduce pressure. The accumulation of fluid in the lungs—known as pulmonary edema—causes severe breathing distress and can lead to panic or even loss of consciousness. You should test your circulatory ability gradually. Avoid strenuous dives in cold water until you have gradually adjusted to being underwater.

Your ability to exert effort in water is not as good as it is on land. When under pressure, your heart and lungs do not function as well as they normally do. A situation in which you are trying to work hard underwater can quickly result in a frightening sensation of suffocation when your equipment is unable to deliver the amount of air that your body requires. To stay within your cardiopulmonary limitations, you must learn to limit your activities and to pace yourself.

Equilibrium Adjustments and Seasickness

If you rupture an eardrum, water that is colder than body temperature can come into contact with the semicircular canals of your inner ear. The canals provide information for your brain to maintain equilibrium and are sensitive to temperature and pressure changes. Cold water cooling the semicircular canals can cause vertigo, a subjective feeling of movement perceived as a spinning sensation. This disorientation will pass when the water in the middle ear warms to body temperature. Obviously, it is better to prevent vertigo than to deal with it.

When a sudden change in pressure occurs in the air space of the middle ear of one ear (a change that affects the semicircular canals), this can also produce a disorienting sensation called alternobaric vertigo. The disorientation from alternobaric vertigo passes quickly when the brain recovers from the sudden pressure change.

Vertigo has many causes. Fortunately, instances of severe disorientation are rare in diving. If you experience disorientation while underwater, try to grasp a solid object for a point of reference until the feeling passes. If suspended in the water, close your eyes and hug yourself to reduce the effects of the vertigo. Avoid panic by telling yourself that the sensation will not last long.

Motions detected in your inner ears, visual references, and pressures on the joints of your limbs all affect your equilibrium. When your brain receives mixed signals from your inner ears, eyes, and body, you can experience motion sickness. You must avoid seasickness—motion sickness experienced aboard a vessel—because vomiting in or under the water is hazardous.

Medications can help reduce the tendency to be seasick. The medicine dulls the senses of the organs of balance in your ears. Unfortunately, the medications can have other undesirable effects. If you are prone to seasickness, consult a diving physician about the type of medication you should try. Take some of the medicine several days before you plan to dive, and note the effects, if any. If the medication produces drowsiness or blurred vision, do not use it while diving. Seek an alternative that does not produce side effects. Medications that cause dizziness, drowsiness, changes in heart rhythm, or blurred vision can cause you to lose consciousness under pressure. Many divers do successfully use medications to prevent seasickness; you need to find a type that works for you. Take medication for motion sickness at least 30 minutes before you are exposed to motion.

If you do not want to use medication, you may use other techniques to reduce the likelihood of seasickness. Eat a good, non-spicy meal before diving. An empty, acid-filled stomach becomes upset more easily than a full one. People whose breakfast before diving consists of coffee and orange juice are good candidates for motion sickness. When aboard a vessel, you should position yourself as near the center of the boat as possible. Avoid the front end of the boat. You should also avoid breathing engine fumes and avoid reading. You can reduce your reaction to the boat's motion by lying down for a while with your eyes closed. Being still allows your inner ears to adjust to the motion without visual signals confusing your brain.

You can become disoriented when you are weightless in a dimly lit environment. Under some conditions, it can be difficult to tell which way is up if you rely only on your sense of balance. To prevent disorientation, you must learn to recognize clues about your orientation in the water. Water in your mask settles to the lowest point, bubbles ascend, and heavy objects you hold (such as your weight belt) orient themselves up and down.

Visual Adjustments

Experience will help you adjust to magnified vision underwater. You can adjust so quickly to distance corrections in water that you have to readjust when you surface from a dive. At the end of a dive, the distance to a boat or to the shore can look much greater than it is. You may be surprised to find that you require less time than you think to swim to a destination.

Your vision also compensates for color differences. If you know an object's true color, the object will look more like that color. The use of artificial light at close range makes it easier to view the rich and magnificent colors in the underwater world.

Your vision adjusts to low light levels, but the process takes time. Short, deep dives in turbid water do not allow complete visual adjustment, and details will not be clear. You cannot see well without artificial light. You can improve your ability to see while diving by avoiding bright light and glare before a dive. Wear good, dark sunglasses above water during the day. When you complete training for night diving, you will learn other techniques to help your eyes adjust for diving at night.

Humidity can cause condensation to form on the lens of your mask and obscure your vision. A clean glass surface will not fog, so make sure you clean the lens or lenses of your mask thoroughly before diving.

Ingassing and Outgassing

Your body absorbs nitrogen underwater, and there are limits to the amount of nitrogen that you can safely eliminate at the end of a dive. If you exceed these limits, you can be injured. In this section, you will learn the theory of decompression, which will help you understand how dive tables and dive computers function to help you avoid injuries.

Decompression Theory

Gases diffuse by moving from areas of greater concentration to areas of lesser concentration. When external pressure increases, gases diffuse from your lungs into your blood, and then from your blood into your tissues. When the **ambient (surrounding) pressure** decreases, diffusion occurs in the reverse sequence.

Two factors that affect diffusion of gases in your body are time and **perfusion** (the circulation in a tissue). The greater the circulation in a tissue, the sooner the pressures of the gases in that tissue come into balance with the pressures of the gases you breathe. Reaching this state of equilibrium takes time. The amount of time it takes a tissue to accumulate half of the gas it can hold at a given pressure is a **half-time**. A tissue is saturated (holds all the gas it can at a given pressure) after six half-times. If perfusion permits 50 percent of a gas to diffuse into a tissue in 5 minutes, the tissue saturates in 30 minutes. Outgassing also occurs in six half-times.

Air is primarily nitrogen and oxygen. The oxygen in the air you breathe is of no concern during decompression within the limits of recreational diving (130 feet or 39.6 m maximum) because you use the oxygen. Nitrogen, the primary component of air, is inert. Your body cannot use the nitrogen, so when you ascend, you must eliminate the excess nitrogen that you absorbed at depth. Because nitrogen diffuses from your body, there is no problem unless the reduction in pressure is so great that you cannot eliminate the nitrogen fast enough. When you reduce the pressure on a liquid rapidly and there is sufficient gas dissolved in the liquid, the gas forms bubbles. An excellent example of this is CO2 dissolved in carbonated beverages (see figure 3.6). The gas remains dissolved in a sealed, pressurized container. When you reduce the pressure suddenly by opening the container, the gas forms bubbles because it cannot diffuse out of solution slowly. If a beverage container has a tiny leak, however, the carbon dioxide comes out of solution slowly without bubbling. There is no bubbling when you open a container that has a slow leak because the gas has already diffused out of solution.



Figure 3.6 Rapid pressure reduction causes dissolved gases to form bubbles within the decompressed liquid.

You must be concerned about the amount of nitrogen in solution in your body and the rate at which you eliminate it. If you absorb too much nitrogen while diving and do not ascend in a manner that allows the excess nitrogen to be eliminated without forming bubbles, the bubbles are likely to cause decompression sickness, a serious diving illness.

Mathematical models provide estimates of the amount of nitrogen in different parts of your body. Because circulation varies in different parts of your body, tissues absorb nitrogen at differing rates. Decompression experts use mathematical models, called **compartments**, to estimate gas absorption and elimination by various areas of the body. A compartment is identified by its half-time. A 5-minute compartment has a half-time of 5 minutes. Experts use compartments ranging from 5 minutes to as long as 960 minutes when calculating gas absorption and elimination.

A compartment that has absorbed gas can withstand some lowering of pressure before bubbling occurs. Originally, scientists believed that a reduction in pressure by a ratio greater than two to one would cause bubbling to occur in divers whose tissues were saturated at a particular depth. This ratio was considered a surfacing limit that could not be exceeded. Then scientists discovered that the surfacing ratios are different for various compartments because of differences in perfusion. For example, brain tissue absorbs and eliminates inert gas faster than bone tissue. Body areas that eliminate gas quickly have a higher surfacing ratio than compartments that eliminate gas slowly. The difference in ratios poses an interesting and complex problem for divers because one tissue controls how long a diver can remain at one depth, while another tissue controls how long the diver can remain at another depth. The **controlling compartment** was used to establish our modern time limits for diving. Do not remain at any depth longer than the time it takes the controlling compartment to exceed its surfacing ratio. If you do, you must prevent bubble formation by stopping during the ascent to allow time to eliminate the excess gas. The time limits for various depths have been conveniently arranged into tables and included in dive computer software. These tools help divers keep the amount of nitrogen in solution in the various tissues of the body within the surfacing ratio of each compartment.

It takes time to eliminate excess gas from tissues. The rate at which you reduce pressure (ascend) is important. The dive tables presented in chapter 7 use an ascent rate, or pressure reduction rate, no greater than 30 feet (9 m) per minute. The mathematical models for some dive computers use rates two or three times slower than the dive tables. You must ascend slowly to prevent the formation of bubbles in your body tissues.

Partial ascents with stops before continuing the ascent can help with outgassing and the prevention of bubble formation. These delays are called safety stops or rest stops, and they are recommended when ascending from any depth in excess of 30 feet. The deeper you dive, the more safety stops you should take when ascending. The recommended practice is to stop for five minutes at half of the deepest depth to which you have been diving and to stop again at a depth of 15 to 20 feet (4.5 to 6.1 m) for five minutes before surfacing.

Decompression Illness

Commonly known as the bends, decompression illness (DCI) is the result of a reduction in pressure (decompression) that is too rapid for the amount of gas in solution in body tissues. The gas forms bubbles in the tissues or in the blood before it can diffuse into the lungs and be eliminated. Scientists do not fully understand what occurs when DCI strikes. The symptoms may appear immediately after surfacing from a dive or days after diving. About half of all DCI cases occur within one hour after diving. The symptoms vary depending on the amount and location of the bubbles. Severe cases of decompression illness can have severe neurological effects and produce permanent paralysis. Common symptoms include the following:

- A mottled skin rash
- Joint pain
- Numbness
- Tingling
- Weakness
- Paralysis

The following factors can increase the chances of DCI:

- Lack of sleep
- Tight-fitting apparel

- Alcohol and its aftereffects
- Exercise during and after diving
- Dehydration
- Cramped position
- Illness
- Altitude after diving
- Age
- Scar tissue or injuries
- Cold water
- Medical conditions

Some experts believe that you should avoid postdive activities that stimulate circulation because increased perfusion may contribute to DCI. Specific activities to avoid include physical exercise, drinking alcoholic beverages, and taking hot showers or baths. Reduced pressure at altitude, such as flying in a plane or driving into the mountains too soon after diving, also poses an additional risk factor that can cause DCI. Avoid all activities that increase the likelihood of decompression illness.

A person suffering from DCI requires prompt first aid and medical treatment because it is an extremely serious condition. The illness worsens with time. The best first aid measure is to administer oxygen in the highest concentration possible. Breathing oxygen eliminates nitrogen in inspired air and enhances the diffusion of nitrogen from the body. The patient should remain still and should sip water. Make arrangements to have the patient transported to the nearest medical facility. After initial medical treatment, the medical staff will arrange to transfer the patient to a facility that has a hyperbaric (high-pressure) chamber. The patient is placed inside a large vessel called a recompression chamber (see figure 3.7). Hyperbaric treatment consists of increasing the pressure in the chamber to reduce or eliminate the symptoms, administering medications, and then slowly decompressing the patient. Recompression must be done in a chamber.



Figure 3.7 Recompression chambers are the only safe method to restore pressure after becoming sick.

Decompression illness is extremely serious because it can cause permanent injury. DCI can cause joint pain and neurological deficits that cannot be cured. To reduce the likelihood of DCI, you should remain well within the established time and depth limits for diving. Surface at a rate no faster than that specified by the dive computer you use. Stop at least twice during ascent (as previously recommended) and eliminate excess nitrogen before surfacing (see figure 3.8). Ascending at the proper rate and stopping are forms of decompression that reduce the likelihood of DCI. (The details about planning your ascent and time delays are provided in chapter 7.) An additional precaution that can help you avoid DCI is to delay excursions to altitude after diving.

Another point to keep in mind is that it is often difficult to distinguish between the symptoms of an arterial gas embolism and DCI. Any diver who has neurological symptoms after a dive should seek medical attention immediately.



Figure 3.8 Divers completing a decompression stop on their ascent to the surface.

Nitrogen Narcosis

The increased partial pressure of nitrogen can cause a condition known as nitrogen narcosis, or rapture of the deep, at depths of about 100 feet (30 m) and deeper. Scientists do not know the exact mechanism of nitrogen narcosis, but its effects are similar to those of anesthetic gases. The feelings associated with narcosis range from euphoria to overconfidence to terror, although some divers do not experience any unusual feelings. Narcosis affects you whether or not you experience abnormal feelings. And it impairs thinking, judgment, reasoning, memory, and the ability to do physical tasks. Narcosis is hazardous; it reduces your awareness and your ability to respond to an emergency. Susceptibility to narcosis varies from person to person and within an individual from day to day.

Narcosis begins suddenly at depth—usually around 100 feet (30m). You can relieve its symptoms rapidly by ascending to a shallower depth to reduce the narcotic effect.

The following factors predispose a person to narcosis:

- A high level of systemic CO2 caused by exertion
- Alcohol or its aftereffects
- Anxiety
- Cold
- Medications
- Social drugs

Experience, frequent diving, and concentration will reduce susceptibility to narcosis. Preventing narcosis is always better than attempting to cope with it.

Specialty training can qualify you to dive with special gas mixtures that reduce the effects of nitrogen. Diving with mixed gases without completing the required training is dangerous and should never be attempted.

Dehydration Prevention

You need to preserve body fluids to prevent **dehydration**. Getting cold makes you produce more urine than normal. Each breath you take from your scuba cylinder must be humidified as explained in the previous chapter. Breathing dehumidified air causes dehydration. You receive air underwater by creating an inhalation pressure that opens valves in your air delivery system. The inhalation pressure is slight, but it is greater than normal. Inhaling harder than normal is negative-pressure breathing, which also has the physiological effect of increasing urine production. Breathing underwater compounds the problem of dehydration.

Diuretic beverages (such as coffee and alcohol) and some types of medications cause increased urine production. Avoid ingesting anything that makes you urinate more than normal. You must prevent excessive dehydration because the condition predisposes you to diving injuries. To prevent dehydration, you should do the following:

- Insulate yourself to stay as warm as possible.
- Keep your regulator well maintained so you can breathe as easily as possible.
- Avoid diuretic drinks and medications.

- Replenish body fluids frequently; drink fluids before and between dives.

  Note: If you wait until you are thirsty to drink when diving, you are already dehydrated. Be proactive and drink at least 1 pint (500 ml) of appropriate fluid after every dive. A good after-dive beverage is a sports drink diluted with an equal amount of water. Avoid alcoholic beverages because they increase dehydration.

Mobility Adjustments

The equipment that you wear for diving limits your mobility. It reduces your range of motion and makes it difficult to walk. The colder the water, the thicker your exposure suit, so the less your range of movement.

Diving equipment is fairly heavy, and it is challenging to lift and move. Improper lifting techniques can cause back injuries. Squat down and lift with your legs to pick up a tank or weight belt instead of bending over. The weight of the equipment changes your center of gravity and affects your balance. Keeping your balance during entries and exits can be challenging on a rocking boat or an uneven surface for your feet. Move carefully and hold on to something or someone for support when you move around out of the water.

You wear fins so that you can use the large muscles of your legs for propulsion. When diving, you need to learn to use your legs for swimming and your body angle to control direction. These techniques free your hands for other uses underwater. Minimize the use of your hands for propulsion. Fins make it difficult for you to walk when you're out of the water. Shuffle your feet while moving backward or sideways, keep your knees bent, and be careful not to fall.

Drag slows your movement in the water. One factor affecting drag is the speed of motion. The greater the speed, the greater the resistance to movement. The average diver can sustain a speed of a little more than 1 mile an hour (0.9 knot, or 1.6 km per hour). A knot equals 1.15 miles per hour (1.85 km per hour) and is the method of measuring speed in water. Doubling the speed increases the energy requirement fourfold. Trying to move in water as if it were air causes exhaustion quickly. Use a slow, steady pace and slow, deliberate motions to reduce the effects of drag.

Another factor affecting drag is the size of the object in motion. The larger the surface area exposed, the greater the resistance. A swimming diver is under the influence of four forces: Weight (negative buoyancy) pulls the diver downward, lift (positive buoyancy) pulls the diver upward, thrust moves the diver forward, and drag slows forward progress (see figure 3.9). Divers usually wear weight around the waist, which pulls the lower half of the body downward. Buoyancy from the BC lifts the upper half of the body. The effect of these forces increases the surface area of the diver and therefore the drag. You should adjust the amount of weight you wear so that your body is as horizontal as possible in the water. Correct weighting minimizes drag and the effort required to swim. Also consider placing a small amount of weight near the top of your body to adjust your trim—that is, your position in the water.

Water flows smoothly across a smooth and rounded surface but flows turbulently across an irregular surface. When the surface is irregular, the turbulent flow increases drag. Just as vehicles designed to travel through fluids are streamlined to reduce the drag caused by turbulent flow, you can choose and configure your equipment so that it presents the smoothest surface possible to the flow of water.



L
D
Direction line
T
W
L
D
Direction line
T
W
Improper trim and streamlining
Proper trim
T
L
D
Direction line
W

The forces affecting a swimming diver include weight (W), drag (D), thrust (T), and lift (L) or buoyancy.

If lift and weight forces are not aligned, the diver will not be level. Part of the thrust must be used to overcome the head-up or the head-down position.

If the diver is weighted and trimmed correctly, as shown in the center illustration, all of the thrust is along the direction line.

Correct trim and streamlining of equipment reduce frontal area and the energy requirements of swimming.

When the bottom is silty, a head-down position is desirable to keep the fins from stirring up silt.

Figure 3.9 Weight, drag, thrust, and lift (buoyancy) affect divers as they move through the water.

Summary

You have to make many changes in your normal behavior to adjust to the underwater environment. The way you breathe is the most important adaptation. You must breathe continuously and avoid breath holding when you use scuba equipment. You must also limit your activity and pace yourself to avoid overexertion. Managing the mechanical and physiological effects of pressure requires major adjustments. You must keep pressure equalized in your air spaces to avoid pressure injuries, and you must limit your depth and time at depth to avoid nitrogen narcosis and decompression illness. Being in the underwater environment seems strange at first, but you can conform to weightlessness and other strange feelings. The sensations of diving become exhilarating as you gain experience in the new world beneath the surface.

Application-of-Knowledge (AOK) Questions

Remember that this is an exercise in thinking, not a quiz. If you carefully consider each situation and how you would respond to it, your time will be well invested even if your thoughts are different from the solution provided. Imagine each situation as vividly as possible.

1. You are wearing a wetsuit and swimming against a current (which is a good idea under most circumstances) in cold water. You are becoming colder with each passing minute. What action, other than ending the dive, can you take to reduce your heat loss?
2. After a dive during which you shivered, you exit the water on a cool, cloudy, windy day. What actions can you take to get warm that are not likely to cause physiological problems? Hint: Rapid rewarming can affect your heart rhythm and may also cause decompression illness.
3. You are wearing 17 pounds of lead weights while diving at a depth of 40 feet (12 m) when your weight belt suddenly slips off. How rapidly do you think you will float upward, and what actions can you take to recover from this situation?
4. You are wearing a wetsuit, a BC, and a weight belt while scuba diving at a depth of 33 feet (10 m). Your buoyancy is adjusted to be perfectly neutral at this depth. You have to ascend 10 feet (3.3 m) to clear a reef. What actions will you need to take to control your buoyancy as you swim over the reef?
5. You are pulling yourself hand over hand down an anchor line to descend to a dive site and are having difficulty equalizing the pressure in your ears. Your normal equalization methods are not working. What should you do to equalize the pressure in your ears?
6. Why do you need to equalize the pressure in your body air spaces and your mask more frequently at the beginning of the descent than when you are approaching your diving depth?
7. You are having trouble keeping up with your buddy, who is swimming ahead. You are breathing heavily and beginning to feel starved for air. What actions should you take?
8. When you switched tanks between dives, you accidently selected one that is almost empty. You were also distracted and failed to check the pressure before you started the dive. You are at a depth of 50 feet (15 m) when it becomes hard to breathe. You look at your pressure gauge and find a reading of zero. Based on what you know at this point in your training, what action do you think is appropriate?

Large, beautiful angelfish at a coral reef in Cozumel, Mexico



4

Diving Equipment

Dive In and Discover

By the end of this chapter, you will be able to do the following:

- Describe the purpose, types, features, selection criteria, and care and maintenance of skin and scuba diving equipment.
- Contrast steel and aluminum scuba cylinders, wet and dry suits, integrated and nonintegrated weighting systems, and reserve and nonreserve valves.
- Define the terms *buoyancy*, *compensator*, *defogging*, *shorty*, *jumpsuit*, *Farmer Johns*, *K-valve*, *J-valve*, *DIN valve*, *valve seat*, *burst disk*, *O-ring*, *port*, *stage*, *octopus*, *capillary gauge*, *Bourdon tube*, *Boyle's law*, *outgassing*, *bezel*, *submersible pressure gauge (SPG)*, *blowout plug*, *alternate air source (AAS)*, *pony tank*, *Spare Air unit*, *lubber line*, *console*, and *ceiling*.

You will become familiar with the following items in this chapter:

- Masks
- Snorkels
- Fins
- Skin diving vests
- Exposure suits
- Weighting systems
- Buoyancy compensators
- Scuba cylinders
- Cylinder valves
- Scuba regulators
- Alternate air sources
- Instrumentation
- Dive knives and other accessories
- Specialized equipment

You need to be equipped properly to dive in open water. A snorkeler (a diver who remains at the surface) should wear a mask, a snorkel, fins, and a skin diving vest. A skin diver (a breath-holding diver who dives beneath the surface) uses snorkeling equipment and may wear an exposure suit and a weight belt (if the suit requires weights). Scuba equipment includes, at a minimum, a mask, a snorkel, fins, an exposure suit, a weighting system (if needed), a **buoyancy compensator** (BC), a scuba unit (cylinder, valve, regulator, **alternate air source**), instrumentation, and a dive knife. For cold water, a diver also needs a hood, boots, and gloves. Figure 4.1 shows fully equipped divers.


Schooling hatchetfish in the Red Sea

Equipment helps people adapt to the underwater environment. It allows them to see, breathe, move, monitor their position, remain comfortable, have fun, and rest. Diving is an equipment-intensive activity. In this chapter, you will learn what equipment you need, how to select the best equipment for your needs, and how to care for your equipment.



ZavgSG/iStock/Getty Images

4x6/Getty Images

Figure 4.1 Fully equipped cold-water (left) and warm-water (right) divers.

Basic Equipment for All Divers

The mask, snorkel, fins, and some flotation device are basic equipment for all types of recreational diving (snorkeling, skin diving, and scuba diving).

Masks

The eyes require an air space in front of them to focus sharply. Your mask provides an air space and a window to another world. Many styles of masks are available, but only two basic types are used for recreational diving: purge and nonpurge. A purge is a one-way valve through which you can expel water that enters the mask. As you will learn in chapter 6, you can remove water from a mask without a valve, so many masks do not feature a purge valve. A third type of mask, a full-face mask, is for commercial and specialty applications only. Figure 4.2 shows the most common types of masks.



Figure 4.2 Test dive masks before you buy to ensure a snug and comfortable fit.

The type of mask you choose is not nearly as important as the fit of the mask on your face. The mask must fit your facial contours perfectly so it will remain comfortable and watertight throughout a dive. Fit and comfort are the most important features to consider when you select a mask. To test the fit of a mask, remove the strap or position it on the front of the mask. Tilt your head back and lay the mask (do not push it) on your face. Make sure your hair is not under the sealing edge of the mask; then inhale gently. If the mask pulls onto your face snugly from the partial vacuum created by your inhalation, the mask fits. If you have to push the mask to get it to seal on your face, the mask will probably leak when you use it underwater.

Factors that affect the fit and comfort of a mask include the style, the type of material, and the type of sealing edge of the mask. The best masks are made from silicone, which is soft, pliable, and nonallergenic and resists deterioration better than rubber compounds (see figure 4.3). The buoyancy of smaller masks poses no problems, but the tug of buoyancy of a larger-volume mask can affect the seal. Low-volume masks are easier to clear of water and provide excellent visibility. A wide, double-edged seal does a better job of keeping out water than a single-edge seal.

A film of oil from production is on the surface of the glass lenses of new masks. You must remove the film completely—a process called **defogging**—or the mask will fog continuously underwater. Clean your mask thoroughly with scouring powder. The glass (which is tempered) is too hard to be scratched by the abrasive, so do not be timid when cleaning your mask. Commercial defogging solutions help keep your mask clear while you dive. If a clean mask fogs slightly during use, you can allow a small amount of water into the mask and wash it across the fogged area to resolve the problem.


Soft, wide sealing edge
Nondeteriorating material
Low volume
Corrective lenses
Nose pocket for equalization access
Purge valve (optional)
Easily adjustable, securely locking strap buckles

Figure 4.3 Mask features.

Several options are available for visual correction if you need it. Hard contact lenses cannot be used, because gases that are released from the body during ascent can be trapped between the lens and the surface of the eye. This can injure the eye. If you wear soft contact lenses, you can use them for diving after you complete your training; however, you should not use them during training because you may lose them when you are learning how to clear water from your mask. Some contact lens wearers prefer a mask with a small purge valve because they can expel water from the mask with little risk of losing a contact lens. Several companies prepare and bond corrective lenses into any diving mask. Interchangeable corrective lenses are available for some masks. If you require only a simple correction, you may be able to obtain corrective lenses for your mask when you purchase it.

Store your mask in a mask box when you are not using it. The box helps keep the mask from getting damaged and helps prevent discoloration of the silicone mask skirt.

Snorkels

A human head weighs about as much as a bowling ball. If you had to swim while holding a bowling ball out of water, you would become exhausted quickly. If you swim while holding your head above water, you will tire rapidly. But if you allow buoyancy to support your head in the water, you can relax and swim for hours. A snorkel allows you to breathe while water supports your head—allowing you to conserve energy and enjoy continuous underwater viewing.

In its simplest form, a snorkel is nothing more than a breathing tube that extends from a diver's mouth to a point above the waterline. A basic diving snorkel is a J-shaped tube with a mouthpiece on one end. Just as with masks, there are two types of snorkels: purge and nonpurge (see figure 4.4). A purge snorkel has a one-way valve through which you can expel water that enters the tube. As you will learn in chapter 6, you can clear water from a snorkel that lacks a purge valve, so some snorkels do not have a valve. Some types of purge snorkels are self-draining; gravity drains water from the tube automatically when you are at the surface of the water.

Additional snorkel options include a swivel mouthpiece and a flexible hose for the lower half of the tube. With the flexible hose, the lower part of the tube—which is usually curved—hangs straight down when you are not using your snorkel (see figure 4.5). The flex-hose snorkel reduces interference between the snorkel and your scuba regulator. Special mouthpieces can be used to maximize comfort, and devices are available to prevent water from entering the top end of the snorkel, although water exclusion devices are not essential.



Figure 4.4 Three common types of snorkel are purge (two at left and far right) and nonpurge (center right).


Colorful,
reflective
band
Flex hose
Custom
mouthpiece
Water
exclusion device
(optional)
Self-draining
Swivel
mouthpiece
Purge valve

Figure 4.5 Features of a flex hose and self-draining snorkel.

The fit of your snorkel is the most important consideration, much more important than the type. The mouthpiece must not irritate your mouth, gums, or jaw when in place for extended periods of time. The angle of the mouthpiece in your mouth should not require you to bite hard to hold the mouthpiece in place. A snorkel that fits poorly may cause sore gums or jaws. A snorkel tube should have an inside diameter of approximately 3/4 inch (1.9 cm) so that resistance to airflow through the tube does not make breathing difficult.

Attach the snorkel to your mask strap on the left side using a snorkel keeper because your regulator hose goes over your right shoulder. Several types of snorkel keepers are available. Popular keepers are the simple ones depicted in figure 4.6. The adjustment is correct if the snorkel mouthpiece remains in your mouth when you open your mouth wide.



Figure 4.6 Two types of snorkel keepers.

Fins

Diving would be much less enjoyable without fins. Fins increase your ability to move in the water and free your hands for other activities. You move in water by pushing against the water. Fins increase your ability to move by presenting a larger surface area than your hands or feet alone. The muscles of your legs are much larger and stronger than your arm muscles. Your arms would tire quickly if fins were attached to your hands, but your legs are strong enough to handle the load. Fins also help stabilize you in water by providing a large surface to resist movement. The resistance provides leverage for countermovement and directional control.

The two basic types of fins are shoe (full-foot) fins and open-heel fins. Shoe fins slip on to bare feet, so they are good snorkeling fins for tropical climates. You wear open-heel fins with foot coverings called boots. Open-heel fins, generally used for scuba diving, are usually larger and stiffer than shoe fins (see figure 4.7). Small, flexible snorkeling fins may be inadequate for the harder work of scuba diving.

Special materials and designs abound. The fundamental features of a fin are the size and stiffness of the blade (see figure 4.8). The larger and stiffer the blade, the greater the propulsion but also the greater the physical demand when you move the fin through the water. A blade that is too stiff can cause you to cramp and become fatigued. You should begin with fins of a moderate size and stiffness. When you can use those fins for extended periods without difficulty, you may consider fins that can provide greater propulsion.

The most important criteria for the selection of any item of diving equipment are fit and comfort, and this is especially true of fins. To help ensure proper fit, sit down and try on a fin. Wear a boot if you are trying on an open-heel fin. Hold your foot in the air and wiggle it up and down and from side to side. The fin and your foot should move as a single unit. If your foot moves inside the foot pocket, the fin is too large. Diving equipment should fit snugly but not tightly.



Figure 4.7 Three styles of open-heel fins.


Elongated foot pocket
High-tech material
Blade size and stiffness
Easily adjustable, securely locking straps

Figure 4.8 Features of dive fins.

A fin that is too tight can cause your foot to cramp. The foot pocket of the fin should fit snugly but should not exert pressure on your foot. Select your fins using fit, comfort, and blade size and stiffness as your primary criteria. Features, fashion, and cost should be secondary considerations.

Skin Diving Vests

When you blow air into a skin diving vest (which is smaller and less complex than a buoyancy compensator), you can achieve positive buoyancy (floating). Positive buoyancy is invaluable when you want to rest at the surface or carry items you have collected while diving. Wear a buoyancy device whenever you dive. You can achieve negative buoyancy (sinking) by venting air from the skin diving vest.

Divers use one basic type of skin diving vest; this vest fits around the neck and secures at the waist (see figure 4.9). A standard feature of a skin diving vest is an oral inflation tube, which comes in various sizes. It is easier to use larger tubes with mouthpieces than smaller tubes without mouthpieces.



Figure 4.9 Skin diving vest.

Care and Maintenance of Skin Diving Equipment

Your skin diving equipment will provide years of service if you take care of it properly. Rinse the equipment with clean, freshwater after use; dry it in the shade; and store it in a cool, dark, smog-free location. Prolonged sunlight, smog, salt crystals, and swimming pool chlorine will harm your equipment. Fill a skin diving vest partially with freshwater after use, and swish the water inside. Drain the vest completely, and then inflate it for drying and for storage. Periodically inspect the straps on your mask and fins for drying and cracking, and replace straps when they begin to deteriorate. After your mask has dried, rub a drop of defogging solution on the lens to help keep the lens clean during storage.

Exposure Suits

You should wear some type of exposure protection when diving regardless of the water temperature. An exposure suit provides protection against scrapes and stings in addition to providing insulation.

The two basic types of exposure suits are wet suits and dry suits. Generally speaking, the colder the water, the thicker your suit should be and the more of your body should be covered by the suit. Suits come in many configurations, but most are one piece or a combination of a jacket and pants. Vests are accessories that help conserve heat in vital organs. Hoods, boots, and gloves help reduce heat loss from the head, feet, and hands, respectively.

Wet Suits

A wet suit is a good exposure suit for water temperatures ranging from 60 to 85 °F (15.6 to 29.4 °C). A wet suit allows water inside, but any water that enters can also exit and carry heat with it. The better the fit of the suit, the less water inside and the warmer the suit. Table 4.1 provides a comparison of the various types of wet suits. The following descriptions provide some additional information.

Table 4.1 Wet Suits

Type	Warmth	Features	Temperature range
Spandex	45% more than bare skin	Light, compact; useful as undergarments for thicker suits	78 °F (25.6 °C) +
Thermoplastic	30% warmer than spandex	Neutrally buoyant; no weights required; wicks perspiration; windproof	75 °F (23.9 °C) +
Plush-lined thermoplastic	10% warmer than unlined	Same as thermoplastic	72 °F (22.2 °C) +
Foam neoprene 1⁄8 in. (2–3 mm) 3⁄16 in. (4 mm) 1⁄4 in. (5–6.5 mm)	20-100% warmer than plush-lined thermoplastic	Buoyant; weights required; long drying time; evaporation chills wearer; minor repairs easy to do	Down to 60 °F (15.6 °C)
Hoods, vests, boots, and gloves or mitts	16-66% more warmth	Reduces water circulation; layering allows flexibility for various temperatures	Down to 60 °F (15.6 °C)

Spandex suits are thin, stretchy, attractive, full-body garments that are popular for diving in tropical waters. Spandex garments provide 45 percent more insulation than bare skin and provide protection against stings, scrapes, and sunshine. Spandex suits are light and compact for travel. They are also useful as undergarments for thicker neoprene wet suits, adding an extra layer of insulation and allowing you to slip into the heavier suit more easily. If you live in a temperate climate, you can use a spandex body suit beneath a neoprene wet suit for local diving and use the spandex suit by itself for vacation diving in the tropics (see figure 4.10).

Thermoplastic—sandwiched between two layers of spandex—is another type of wet suit material. A suit made from this three-ply material is about 30 percent warmer than a spandex suit. Thermoplastic suits are thin (1.2 to 1.4 mm) and designed for use in tropical waters (75 to 85 °F [24 to 29 °C]). Some suits feature soft, plush lining for extra warmth. The plush lining increases the warmth of the suit by about 10 percent. You can wear a thermoplastic suit beneath a neoprene wet suit for extra warmth in colder water.

Thermoplastic material offers several advantages: The balance between the weight and volume of this unique material makes it neutrally buoyant, so you may not need a weight belt. The stretchy fabric allows you to move freely. The material draws perspiration away from your body but is windproof.

A third type of wet suit material is foam neoprene, as in the suits shown in figure 4.11. The foam contains tiny bubbles of inert gas, which provide insulation. The thicker the wet suit material, the greater the insulation quality of the suit. A 1/8-inch (about 3 mm) neoprene wet suit is about 20 percent warmer than a plush thermoplastic suit.

The thickness of foam neoprene in wet suits ranges from 1/8 inch for warm-water diving to 3/8 inch (about 9 mm) for extreme cold-water diving. The most common wet suit thicknesses are 1/8 inch, 3/16 inch (about 4 mm), and 1/4 inch (about 6 mm). You can layer wet suit material on critical areas of your body to



Figure 4.10 Common styles of warm-water wet suits: foam neoprene jumpsuit (left), shorty (center), and nylon (right).



Figure 4.11 Common styles of cold-water wet suits: Jackets at left and center (worn with or without an attached hood) are worn over Farmer Johns at right to form layers.

reduce heat loss, but the thicker the insulation you wear, the more difficult it is for you to control buoyancy. Choose the thickness of wet suit material used by experienced divers in the area where you plan to dive.

Nylon usually covers both sides of the neoprene used for wet suits. The nylon increases the strength and durability of the suit, which is glued and sewed together. You can make minor repairs with wet suit cement, but you should have a wet suit manufacturer do extensive repairs.

Neoprene wet suits require weights to achieve neutral buoyancy. The suit provides immediate buoyancy when you release the weights, but the buoyancy of the suit can be either a benefit or a hazard. Neoprene is not windproof, and the evaporation of water from the suit between dives can chill you. You can wear a wet suit overgarment to retain warmth between dives in colder climates. Neoprene suits take longer to dry than other types of exposure suits. Mobility is good with thin neoprene wet suits but decreases as the thickness of the material increases.

Numerous wet suit designs are available, including the **shorty**, the one-piece **jumpsuit**, and **Farmer Johns** (see figures 4.10 and 4.11). You must consider several features when selecting a wet suit design. The more zippers a suit has, the more water circulates inside the suit and the greater the loss of heat. You can get zipperless suits for cold-water diving. Good wet suits feature a spine pad to minimize water circulation along the channel formed by your spine, and some suits for cold-water diving have attached hoods to minimize water circulation at the neck. You may spend time kneeling around and in the water, so knee pads are a desirable feature.

Heat packs are available for wet suits. These packs contain a nontoxic, reusable chemical that heats to about 130 °F (54 °C) for half an hour or more, depending on conditions. The packs fit into special pockets that are an optional suit feature.

You can buy wet suits in standard sizes, or you can have a suit tailored for a custom fit. The fit of a wet suit is its most important feature. The suit must fit snugly all over, but it must not fit so tightly that it hampers your breathing and circulation. A suit that fits well may feel slightly restrictive out of the water. The true test of the fit of a suit is to dive with it. You may be able to rent a wet suit identical to one you would like to purchase.

Wet Suit Accessories

Scuba divers wear footwear for warmth and foot protection. Several types of footwear—called boots or booties—are available for various needs. Boots, usually made from neoprene, may cover only the foot or both the foot and the ankle (see figure 4.12). Boots range from inexpensive neoprene socks to sturdy footwear with durable, molded soles. They may or may not have zippers. Zippered boots are easier to don and remove, but boots without zippers are warmer.



Figure 4.12 Boots are available with or without zippers.

You should wear hand coverings when the water temperature is less than 70 °F (21 °C). Some divers wear gloves for protection, such as when catching lobsters. Types of hand coverings include gloves, mitts, and gauntlets (see figure

4.13). Wear mitts in cold water because they are thicker and have less surface area for heat dissipation than gloves have. Wear gauntlets (neoprene mitts with long cuffs) when the water is extremely cold. Thin neoprene gloves provide sufficient insulation in temperate water. Do not wear gloves in tropical areas. You are more likely to touch things when wearing gloves, and grabbing delicate coral reefs and marine animals while wearing gloves may harm the animals.

A hood is an important warmth accessory that can reduce your heat loss from 20 to 50 percent, depending on the temperature of the water. Two basic types of hoods—attached hoods and separate hoods—are available for wet suits (see figure 4.14). Cold-water divers like attached hoods because they restrict water circulation in a suit more than separate hoods do. Some separate hoods have skirts that end at the base of the neck; other cold-water hoods have large bibs that cover the neck and shoulder area. Thin hoods are used for protection in warm water, and thicker hoods are used for insulation and protection in cold water.



Figure 4.13 Gloves and mitts protect divers' hands from cold temperatures and injuries.



Figure 4.14 Hoods conserve warmth in cold waters.

Figure 4.15 The addition of a vest can increase the warmth of your wet suit by as much as 16 percent.

You can increase the warmth of your wet suit by as much as 16 percent by wearing a vest. Wet-suit vests come in all types of material and provide an additional layer of insulation (see figure 4.15). Layering is an effective technique that reduces water circulation while increasing insulation. Some vests have attached hoods.

Wet Suit Care and Maintenance

With proper care, wet suits can provide years of service. Soak your wet suit in clean, warm freshwater after each use. If you can't soak your suit, rinse it. Hang your suit on a wet suit hanger, which is wider than a typical clothes hanger; dry the suit in the shade; and store it on the hanger in a cool, dark, smog-free location. A garage is a poor environment for storing equipment because of emissions from automobile exhaust. Do not fold your wet suit for storage because folds can form permanent creases, which insulate poorly. Inspect your suit regularly for seam integrity and tears. Make repairs or have them made as needed.

Dry Suits

When the water temperature is less than 60 °F (15.6 °C), consider using a dry suit, which is an exposure suit that keeps out water. Dry suits are much warmer than wet suits for three reasons:

1. Air is in contact with your skin instead of water. Because air conducts less heat than water, you lose less heat via conduction.
2. You wear undergarments beneath a dry suit. The undergarments trap a layer of air, which is a good insulator.
3. Suit compression affects two of the three types of dry suits only slightly, so the insulating ability of those types of dry suits remains nearly constant regardless of depth. Constant volume in a dry suit provides an advantage over a wet suit, which compresses with depth and expands during ascent.

Dry suits are identified by the material from which they are made. Table 4.2 compares the three most common types of dry suits. The foam neoprene dry suit is made of the same material as a wet suit, but the dry suit has seals at the wrists and neck, attached dry boots, and a waterproof zipper (see figure 4.16).

A dry suit can cost two to five times as much as a wet suit, but with proper care and maintenance, a good dry suit will last many times longer than a wet suit. If you dive primarily in cold water, a dry suit is a good investment.

A dry suit creates a closed air space that is subject to squeezing. A low-pressure inflator valve, which is a standard feature, allows you to add air to the suit during descent to prevent suit squeeze. Because air expands during ascent, an exhaust valve is another standard feature. Get a dry suit that has a constant-volume exhaust valve that automatically maintains a constant state of buoyancy during ascent.

Diving is a diuretic activity—that is, it increases the amount of urine you produce. Urination in a wet suit is a regular practice by divers in open water, but the problem is more complex when you wear a dry suit. An optional feature for a dry suit is a relief zipper, which is useful only when you are out of the water.

Table 4.2 Dry Suits

Type	Advantages	Disadvantages
Foam neoprene	Form fitting and streamlined	Long drying time; hard to locate and repair leaks; buoyancy control difficult
Crushed neoprene	Durable; easy to repair; long lasting; less buoyant than foam neoprene	Less insulation than foam neoprene; expensive; somewhat bulky
Shell (two kinds) • Coated nylon • Rubberized fabric	Fast drying; easy to repair; nylon suits inexpensive; rubberized suits long lasting	Easily punctured; bulky; nylon suits do not last long; rubberized suits expensive

Divers wearing a dry suit have to exit the water to urinate, and those without a relief zipper must disrobe.

Several types of undergarments for dry suits are available. Some are inexpensive but compress with depth and lose insulating ability when wet. More expensive undergarments are highly resistant to compression and retain most of their insulating quality even if wet. Many divers who wear dry suits prefer to wear two layers of undergarments: a thin garment against the skin to carry perspiration away from the body and a thicker overgarment to provide the bulk of the insulation. Moisture conducts heat, so you are warmer when perspiration is wicked away from your body.

Dry suits have several drawbacks. Controlling buoyancy is more difficult with a dry suit than with a wet suit. Rapid, uncontrolled ascents can occur unless you control the suit. Training is essential before attempting to dive in a dry suit. Dry suits are bulkier than wet suits. It is easier to don and remove a dry suit than a wet suit, but the bulkiness of a dry suit makes surface swimming difficult. A dry suit also restricts your mobility more than a wet suit does. The inconveniences of a dry suit are of little consequence, however, when warmth is your primary concern.



Figure 4.16 **Dry suits can be made from foam neoprene, crushed neoprene, or nylon.**

Berenika Lychak/iStock/Getty Images

Dry Suit Accessories

Most dry suits have attached boots, a desirable feature. Thin latex booties are found on less expensive suits; more expensive suits have hard-soled boots. You should wear heavy socks for insulation with latex booties, and you must wear wet suit boots over the latex booties to protect them. The end result is that divers who wear dry suits usually need fins with large foot pockets.

You can wear neoprene gloves or mitts with a dry suit. If the water is extremely cold, you can get dry gloves with insulating liners that attach to some dry suits. An attached latex dry hood is an option for some models, but most divers use a separate neoprene dry suit hood. Figure 4.17 shows examples of dry suit accessories.

Dry Suit Care and Maintenance

Dry suits require more care than wet suits. The zipper and the control valves are expensive to replace, so do not allow salt crystals to form in the zipper or in the valves. Soak and rinse the zipper and valves in clean freshwater as soon as possible after a saltwater dive. Wash the neck and wrist seals with soapy water, and then rinse them. Coat latex seals with pure talc after they dry. The talc helps protect the rubber from the elements. Fold dry suits in half over a wide hanger for drying. Lubricate the suit zipper according to the manufacturer's instructions, then store the suit with the zipper open. If the suit needs to be repaired, have an authorized dealer make the repairs. As with wet suits, store your dry



Figure 4.17 Dry-suit boots and gloves help keep divers warm.

suit inside your home. The rubber seals on dry suits are adversely affected by exhaust emissions.

Exposure Suit Selection

You should consider many factors when selecting an exposure suit and accessories: your physical characteristics, where you intend to dive, how you intend to dive, how much diving you intend to do, and what you intend to do while diving. The amount of money you want to invest is also a factor, but keep in mind that buying an inexpensive suit may be false economy. If the suit does not meet your needs, you will have to spend more money for another suit.

The amount of diving you intend to do is an important factor. If you plan to make only one dive per day, your insulation requirements are not as great as they are if you plan to dive several times per day. The more time you plan to spend in the water, the warmer your suit needs to be.

If you are a thin person who gets chilled easily, you need more insulation than the average person for a given water temperature. People with more-than-average body fat may not require as much insulation as those with average body fat; fat is a good, natural insulator. Thermal comfort is essential for diving safety and enjoyment.

If you intend to do most of your diving in one area, the most popular type of suit in the area is probably the best type for you. If the local waters are cold, you have to choose between a wet suit and a dry suit. If you choose to get a wet suit as your first exposure suit for cold-water diving, a layered design with Farmer John pants, a vest, and a step-in jacket with an attached hood retains more warmth than high-waisted pants, a regular jacket, and a separate hood. A custom fit retains more warmth than a suit of a standard size.

Dry suits are not desirable for long surface swims because you can overheat, and the drag caused by the bulkiness of some dry suits may cause you to tire or cramp. On the other hand, dry suits retain much more warmth at depth than wet suits. If most of your diving will be deeper than 40 feet (12 m), if the water is 60 °F (15.6 °C) or colder, and if you can avoid long surface swims, a dry suit is a good choice—as long as you obtain training before using the suit.

If you plan to dive in a variety of climates, a spandex or thermoplastic suit combined with a neoprene wet suit may be a good option. You can wear different parts of the suits to meet different warmth requirements. Your diving activity affects your needs. An underwater hunter looking for game generates more body heat than an underwater photographer whose movements are minimal. The less active you are while diving, the more insulation you need. Your desires, needs, and budget determine the features you select for your exposure suit. When choosing features for your suit, you should consider the features that are popular with local experienced divers and diving leaders.

The accessories you select for your suit depend on the type of suit you choose, the temperature of the water, the activity you intend to pursue, and your budget. A hood may be thin and short for warmer water, thick with a long skirt for colder water, or a dry suit type. Foot coverings may be low cut, ankle high, or attached to the suit. The soles may be soft or hard. Hand coverings range from nothing to thick mitts, gauntlets, or dry gloves.

Local diving professionals can help with your selection of an exposure suit and accessories. No matter what type of exposure suit you choose, keep in mind that it is an investment in your enjoyment of diving. Diving is not fun if you get cold.

Weighting Systems

Exposure suits increase your buoyancy. You need weights for ballast in order to achieve neutral buoyancy. One type of weighting system is a weight belt (see figure 4.18); another type integrates the weights into the scuba unit.

Weights can be attached to or inserted into a belt that you wear around your waist. The belt is heavy nylon webbing two inches (five cm) wide. You can thread the belt through lead weights, wrap pouches of lead shot around the belt, or put weights or pouches of lead shot into pockets on pocket-type belts. A hollow fabric belt that you can fill with lead shot is more comfortable on your hips than hard weights. Lead shot, which comes in different sizes, causes less damage than hard lead weights if you drop the belt accidentally. Smaller-diameter shot weighs more per volume than larger shot, so the more weight you need, the smaller the shot you should use.

Because exposure suits compress with depth, a weight belt around your waist loosens unless it has a means of compensating for the suit compression. An



Figure 4.18 Weight belt with various sizes of weights.

elastic compensator is a desirable feature for a weight belt; you can select from a variety of designs.

Secure the weights on your weight belt so that they will not shift position. Pocket-type belts are good in this respect. When you thread separate weights onto a belt, you should secure the first and last weights with retainers, which are available as accessories.

The most important feature of any weighting system is the quick release. In the event of an emergency, you must discard weights quickly to establish positive buoyancy. No matter what type of system you choose, a reliable, easily located, and easily operated quick release is essential.

Several types of weights are available. Large, curved hip weights help offset the buoyancy of cold-water exposure suits. Smaller, rectangular weights find widespread use because they are economical. Coated weights are attractive and practical. Manufacturers mold weights into various shapes and offer a heavy vinyl coating as an option. The coating reduces pollution from lead, improves appearance, makes the weights easier to see in the water, and reduces suit abrasion. Fabric mesh packets filled with lead shot are popular. You can get bulk lead shot for hollow fabric belts. Coated lead shot, although slightly more expensive, is better than uncoated shot. Shot-filled tubular ankle weights are also available, although some diving experts believe ankle weights are unnecessary.

An integrated weighting system eliminates the need for a weight belt by holding lead weight in the **backpack** that holds the scuba cylinder or in the buoyancy compensator. An integrated weighting system makes the scuba unit heavier, but it also allows better distribution of weight than a separate system can provide. Some divers consider an integrated weighting system advantageous because weights are less likely to shift, a suit compression compensator is not needed, and having the weight above the waist improves the diver's trim in the water and reduces strain on the lower back. However, when you raise your center of gravity, you are more likely to lose your balance and fall when you are out of the water. You need strength, good balance, and caution to use an integrated weighting system. Integrated systems usually use lead shot, either in bulk or in pouches.

Weighting System Care and Maintenance

Weighting systems do not require as much care and maintenance as other items of diving equipment. Do not soak or rinse raw lead after use because lead in the runoff pollutes the environment. If gray water seeps from your weight system, replace the lead with new, coated lead. (You can recycle old lead, so do not throw it away.) Pocket-type weighting systems allow you to remove the weights and rinse the remainder of the system.

Regularly inspect the functional aspects, such as the quick release and the compensator. If you use a belt, inspect the weight retainers to make sure they are not broken, and make sure the end of the belt is clean and neat for easy insertion into the buckle. If the end of your belt is frayed, trim and singe it. When you fix a frayed end, be careful that you do not cut or burn yourself.

Weighting System Selection

When selecting a weighting system, you should consider your physical characteristics, the amount of weight you need, and how frequently you will need to change the amount of weight you use.

If you have a large build, your waist is larger than your hips, and your exposure suit is thick, a weight belt may not work well—especially if you need more than 30 pounds (13.6 kg) of weight. In chapter 6, you will learn how to test your buoyancy to determine the amount of weight that you need. Consult with divers whose physical characteristics are similar to yours for advice about weighting systems. If you require more than 30 pounds of weight, you may need weights on a weight belt plus an integrated system. If you require only a small amount of weight, nearly any type of weight system is acceptable.

If the type of diving you do varies, the amount of weight you need also varies. If you dive in freshwater and in saltwater, you need to adjust your weights. When you vary your exposure suit configuration, you also need to vary the amount of weight you wear. The more you need to change weights, the more you need a weighting system that allows changes to be made easily.

Buoyancy Compensators

A buoyancy compensator (BC) helps you control buoyancy. You can inflate your BC at the surface to increase buoyancy, deflate it to reduce buoyancy for descent, and add air to it to achieve neutral buoyancy underwater. Most BCs also contain a backpack to hold your scuba cylinder.

The three types of BCs are jacket style, back mounted, and front mounted (see table 4.3 for style comparison). Most BCs used in diving today have a wraparound jacket design, which provides front and rear buoyancy. There are two basic jacket designs: One style has inflation tubes over the shoulders; a newer style has straps over the shoulders. The straps have convenient, adjustable releases (see figure 4.19).



Figure 4.19 Jacket-style buoyancy compensator with shoulder straps and quick-release clasps.

Table 4.3 Buoyancy Compensators

Type	Location of buoyancy chamber	Advantages	Disadvantages
Jacket style	Front and rear	Even lift; diver can remain upright	Not suitable for skin diving
Back mounted	Rear	Does not interfere with valve operation for dry suits	Pushes diver forward; difficult for diver to remain upright
Front mounted	Front	Suitable for skin diving; allows diver to remain upright	Need separate backpack for cylinders; requires disconnection of inflator hose before removal; does not provide as much lift as jacket

Back-mounted BCs place buoyancy chambers behind you. These systems are useful for underwater modeling and for specialty diving activities. Models look better without bulky BCs covering them, and back-mounted units do not interfere with valve operation on dry suits as much as other types of BCs do.

Front-mounted BCs fit around your neck and cover your chest area. This was the first type of BC, but few divers use front-mounted BCs today. Most divers today believe that BC jackets are superior to front-mounted ones. You can use a front-mounted BC for both skin diving and scuba diving. Jacket-style and back-mounted BCs are not suitable for skin diving.

In its simplest form, a BC is a bladder with attachments (see figure 4.20). The bladder may be coated material that constitutes the BC itself, or a separate bladder may be inside a fabric shell. The seams of a BC bladder are glued or electronically welded, depending on the type of material.

Buoyancy Compensator Selection

When selecting a BC, you should consider your physical characteristics, where you plan to dive, and the type of diving you plan to do. Some BCs provide more buoyancy than others. A cold-water diver wearing a wet suit needs more lift than a warm-water diver wearing a thin exposure suit, although a large amount of lift is not necessarily desirable.

If you are a large, strong individual, the size and bulk of a BC may not be of much concern. But if you are small, you may be wise to choose a small, compact BC. The length of the BC is important. If the BC extends downward too far, this makes donning and removing your weight belt difficult. If you are shortwaisted, consider an integrated weighting system. The fit is important because a BC needs


Pressure relief valve
Single-bladder construction
Pull-dump valve (cable inside hose)
Shoulder adjustment and release
Accessory rings
Cylinder retaining band on back
Low-pressure inflator valve
Pockets
Cummerbund waistband
Deflation/oral inflation valve

Figure 4.20 Desirable BC features.

to support you in the water. The BC should fit snugly and not ride up on your body. Models that allow adjustment for a custom fit are desirable.

Another desirable feature is a single-bladder construction, which is less expensive and requires less maintenance than a separate bladder. Renting and using different types of BCs will aid you in making a selection. Talk to experienced divers and diving professionals, and observe BC preferences in the area where you dive.

Buoyancy Compensator Care and Maintenance

Your investment in a BC is large. But, like most diving equipment, your BC will provide years of service if you take care of it. You need to rinse your BC inside and out after use, especially after use in a swimming pool or in the ocean. Chlorine in pool water and salt crystals from seawater are harmful to your BC. Drain the water from your BC after use, fill it about a third full with freshwater, swish the water around, and then drain the bladder. Rinse the inflator assembly thoroughly, and leave the BC fully inflated until it dries. Inflation will test the airtight integrity of the bladder and valves. If the BC does not remain firm for

Diving Equipment Checklist

✓ Mask, snorkel, and snorkel keeper
✓ Fins and boots
✓ Scuba tank (filled)
✓ Buoyancy compensator
✓ Exposure suit, hood, and gloves
✓ Weight system
✓ Regulator with pressure gauge
✓ Alternate air source
✓ Instruments to monitor depth, time, and direction (separate or integrated)
✓ Signaling devices (whistle, mirror, safety tube)
✓ Dive knife
✓ Float, dive flag, and anchor
✓ Dive tables
✓ Dive light
✓ Slate and pencil
✓ Marker buoy
✓ Collecting bag
✓ Gear bag

Spare equipment

✓ Scuba tank(s)
✓ Weights
✓ Straps
✓ O-rings
✓ Snorkel keeper

Secondary equipment

✓ First aid kit
✓ Emergency phone numbers and radio frequencies
✓ Logbook
✓ Swimsuit
✓ Towel
✓ Jacket
✓ Hat or visor
✓ Sunglasses
✓ Dive kit
✓ Save-a-dive kit
✓ Drinking water

at least an hour, take it to a professional repair facility. Anytime your BC fails to function properly, have it professionally repaired. It is hazardous to attempt BC repairs without special training, tools, and parts.

Scuba Cylinders

A scuba cylinder stores compressed air at high pressure. The container must be strong and free of corrosion. Scuba cylinders (also called tanks) are made of either aluminum or steel. Each type has advantages and disadvantages. Figure 4.21 shows examples of various steel and aluminum tanks.



Figure 4.21 Scuba cylinders come in many sizes and are made of steel or aluminum.

Steel Cylinders

Steel scuba cylinders come in various sizes with various pressure ratings. Common sizes are 63, 71.2, 80, and 100 cubic feet (1,784, 2,016, 2,265, and 2,832 L). The pressure to which the cylinders can be filled, called the working pressure, ranges from 1,800 to more than 4,000 pounds per square inch (psi), or 122 to 272 standard atmospheres (atm).

Some compressors pump air only to 2,500 psi (170 atm). When you cannot get air at a pressure higher than 2,500 psi, a steel tank may be more desirable than an aluminum tank. A steel 71.2-cubic-foot scuba tank filled to 2,250 psi (153 atm) contains about 5 cubic feet (142 L) more air than an 80-cubic-foot aluminum tank filled to the same pressure. The aluminum tank must be filled to 3,000 psi (204 atm) to obtain 80 cubic feet.

The main disadvantage of a steel cylinder is that it can rust, which can render a tank unsafe and unusable. Do not allow water inside a scuba cylinder. The high-pressure atmosphere has a large amount of oxygen to fuel corrosion. You can keep the inside of a steel scuba tank dry, but the outside is exposed to moisture. Galvanizing inhibits rust on the outside of steel tanks, but the inside may not be galvanized because galvanization affects air purity. Painting a galvanized surface may improve the appearance of a cylinder, but paint alone is an inadequate finish because cracks or chips in the paint allow moisture to reach the steel. The tank will begin to rust unless there is a galvanized coating beneath the paint.

Another disadvantage of a steel scuba tank is that it has a rounded bottom because of the manufacturing process. The tank cannot stand by itself unless you place a rubber or plastic boot, called a tank boot, on the end of the cylinder. The boot makes the base of the tank flat so it will stand. Some boots have flat sides to help keep a tank from rolling when you lay the cylinder on its side. Moisture and salt trapped between the tank boot and the cylinder can cause corrosion. Boots with internal ridges—the preferred type of boot—are self-draining.

Aluminum Cylinders

Aluminum alloy cylinders also come in various sizes with various pressure ratings. Common sizes are 63, 80, and 100 cubic feet (1,784, 2,265, and 2,832 L). The working pressure for aluminum cylinders is 3,300 psi (224 atm).

Aluminum corrodes, but the oxide that forms arrests the corrosive process—this is a significant advantage over the corrosive process of rust in steel tanks. Rust is an accelerating process, but corrosion in an aluminum cylinder is a self-arresting process.

The bottom of an aluminum cylinder is flat. You do not need a tank boot on the cylinder to allow it to stand by itself, but many divers put boots on aluminum tanks to protect the tank and any objects struck by the bottoms of the cylinders.

Aluminum cylinders also have drawbacks. Aluminum is softer than steel, so aluminum tanks can be dented and gouged more easily than steel tanks. On aluminum tanks, brass cylinder valves control the flow of air. Electrolytic action between the dissimilar metals of the cylinder and the valve can cause the valve to seize in the aluminum cylinder threads unless the valve is removed periodically and coated with a special compound. Valve seizing seldom is a problem with steel cylinders.

Aluminum cylinders do not need to be galvanized. You can paint them to improve appearance, but do not bake the paint finish. Temperatures hotter than 180 °F (82.2 °C) reduce the strength of an aluminum cylinder and can cause it to explode when filled. If you would like your cylinder painted, have it done by a professional tank-painting service.

Cylinder Markings

Several rows of markings on the neck of a scuba cylinder provide useful information about the cylinder. You should be able to determine the meaning of several of the marks. Figure 4.22 shows an example of cylinder neck markings.


DOT - 3AA2250
123456 / PST /1 - 02 / Æ
6 - 95
Department of Transportation
Materials used for steel tank
Service pressure in psi
Serial number
Inspector's official mark
DOT - 3AA 2250
123456 / PST / 1 - 16 / Æ
6 - 95
Manufacturer
Month and year of original hydrostatic test
Month and year of current hydrostatic test

Figure 4.22 Cylinder neck markings.

The first row of marks on tanks manufactured in the United States discloses the government agency that sanctioned the manufacture of the tank, the type of metal from which the tank was made, from, and the working pressure. The first letters in the row identify the government agency, such as DOT (U.S. Department of Transportation), CTC/DOT (Canadian Transportation Commission and the U.S. Department of Transportation), or ICC (the former U.S. Interstate Commerce Commission). The next characters in the first row identify the type of metal that the tank was made from. The marks 3A and 3AA are designations for steel cylinders. The marks 3AL, E 6498, and SP6498 are designations for aluminum cylinders. The final figures in the first row—the important ones for you to remember—are numbers indicating the working pressure of the cylinder in pounds per square inch.

The second row of markings includes the serial number of the tank (which you should record for identification purposes) and letters or numbers identifying the manufacturer of the cylinder. The month and year of the tank's first pressure test are located somewhere below the second row. U.S. regulations require compressed gas cylinders to be pressure-tested before being put into service and every five years thereafter. Subsequent test dates can be stamped anywhere on the neck of the tank. A registered symbol between the month and year of a pressure test identifies the facility that did the testing.

Tanks are filled at an air (or "fill") station (see figure 4.23).When you take your cylinder to an air station for filling, the facility personnel will examine the tank markings to determine whether the cylinder test date is current and to identify the pressure to which the tank can be filled.

Cylinder Selection

The main criteria for the selection of diving equipment—fit and comfort—apply to scuba tanks as well. A small person should use a small tank. Larger divers may require larger tanks because they have larger lungs and use more air.

The material from which a tank is made affects its capacity, size, and working pressure. Although steel is heavier than aluminum, aluminum tanks are larger and heavier than steel tanks with similar capacities. Because aluminum is not as strong as steel, the walls of an aluminum tank are thicker than the walls of a steel tank of approximately the same capacity. The higher the pressure rating, the greater the capacity of a tank of a given size. Modern high-pressure steel scuba tanks are high-capacity cylinders, but they are quite heavy. Good sizes for small divers to consider for an initial scuba tank are 50 and 63 cubic feet (1,416 and 1,784 L). Popular sizes for divers of average size are 71.2 and 80 cubic feet (2,016 and 2,265 L).

Another important factor to consider when selecting a scuba tank is the buoyancy of the cylinder, which is determined by the volume and weight of the tank. Aluminum tanks are more buoyant than steel tanks. High-capacity tanks have a greater change in buoyancy than smaller cylinders as you use air from them. The change in buoyancy between a full and an empty tank can vary by more than 8 pounds (3.6 kg; see table 4.4). Some tanks are negatively buoyant



Figure 4.23 Scuba cylinder filling station.

Table 4.4 Cylinder Size, Working Pressure, and Buoyancy

Capacity (ft³/L)	Working pressure (psi)	Buoyancy (lb) from full to empty
Aluminum 50/1,416	3,000	–2.7 to +1.3
Aluminum 63/1,784	3,000	–2.3 to +2.7
Steel 71.2/2,016	2,250	–2.0 to +3.6
Aluminum 80/2,265	3,000	–2.0 to +4.4
Steel 76/2,152	2,400	–6.5 to –0.1
Steel 80/2,265	3,500	–7.4 to –1.0
Steel 102/2,888	3,500	–7.6 to +0.5

whether full or empty, but most tanks sink when full and float when empty. Buoyancy for tanks varies so much that you should select the tank most often used for diving in your area or try diving with several different tanks to determine which is easiest to manage.

You need to decide whether you are going to dive using compressed air, enriched-air nitrox, or mixed gases. If your breathing gas is anything other than compressed air, your cylinder, cylinder valve, and regulator must be dedicated to the specialized gas. It is unsafe to use a compressed air cylinder and regulator with mixed gases. Regulators, valves, and cylinders must be "oxygen clean" and "oxygen safe" when used with mixed gases.

Multiple-tank scuba units are used for specialty applications. As a beginning diver, you do not need double or triple scuba tanks. A single tank is adequate for most diving activities.

Cylinder Accessories

Fabric or plastic sleeves can help protect the exterior of your scuba cylinder. Some sleeves have places to attach items within easy reach. Tank bands, which secure a cylinder to a buoyancy compensator, vary. Some allow you to attach a small, backup scuba cylinder to your main cylinder. Additional accessories are available to help you carry or transport your scuba cylinders. Tank boots are a desirable cylinder accessory.

Cylinder Care and Maintenance

Scuba tanks are high-pressure vessels. They are strong, but you should handle them with care. Exterior damage can render your scuba tank useless. Avoid throwing scuba tanks or allowing them to roll about on the deck of a boat or in the trunk of your car. Secure cylinders for transportation or storage. Unless you are holding a scuba cylinder, do not leave it standing in an upright position, especially at a dive site. If the cylinder falls, it can injure someone or damage the tank valve or regulator. However, you should store your scuba tanks in an upright position so that any moisture inside will settle to the bottom where inspectors can detect it with relative ease. Rinse the outside of your cylinder with clean, fresh water after use, and pay special attention to the boot area of steel tanks.

Corrosion can ruin a cylinder rapidly, and pieces of corrosion can damage a tank valve or scuba regulator. One way to prevent moisture from entering a tank is to keep air in the tank. Water can get into an empty scuba cylinder while you are diving, so avoid using all the air in your tank. Moisture can enter an empty tank if you store it with the valve open. Store your scuba cylinder with a few hundred pounds (about 20 atm) of pressure inside. A low pressure keeps moisture out but provides little oxygen to aid corrosion if there is moisture in the tank.

The filling process can force water into the tank. A water trap in an air compressor is supposed to remove moisture from air, but if the moisture-removal system does not function properly, water can be pumped into your tank along with air. The filling hose attachments for scuba tanks can get wet, and water inside the filling attachments can be forced into your cylinder. Using a high-quality air station is important.

The diving industry requires an annual visual inspection of scuba cylinders. The examination consists of an external inspection, the removal of the valve from a cylinder, an internal inspection using a special light, special electrical testing for aluminum cylinders, the replacement of the valve, and the attachment of a decal indicating the inspection date. Most air stations require a current inspection sticker on a tank before they will fill it. When you handle your scuba tank, listen for sounds of anything moving inside the cylinder. If you hear anything, have the tank visually inspected.

U.S. government regulations specify that compressed gas cylinders must be pressure-tested every five years. Some countries require pressure testing every year or two. The test is hydrostatic because it takes place in water. An inspector fills a scuba tank with water and submerges it in a closed container that is completely filled with water. The inspector applies pressure to the scuba tank hydraulically, and the tank expands slightly from the pressure. The expansion displaces water from the container holding the scuba tank. The inspector measures the expansion and then releases the pressure. The tank must return to within 10 percent of its original volume within a specified period of time. If the tank is too brittle to expand and contract correctly, the inspector condemns it.

You may transport a scuba tank on an airplane only if the tank is completely empty and the valve is open—a situation that is not good for scuba tanks. Do not transport your cylinder by air. Diving destinations have tanks readily available, so there is no need to take a tank on a dive trip.

Cylinder Valves

Cylinder valves control the flow of a liquid or gas. Four types of valves are available for scuba tanks: the simple valve, the reserve valve, the high-pressure valve, and the multiple-cylinder valve. Because multiple tanks are for advanced specialty diving activities, this section addresses only the simple and high-pressure valves.

Simple Valve

A simple valve is an on-off valve that operates like a faucet. You turn the valve handle counterclockwise to open it and clockwise to close it. The first catalog of diving equipment listed this type of valve as item K, and the valve has been identified as a **K-valve** ever since (see figure 4.24).

The **valve seat** is a soft-sealing surface. It is the portion of the valve that closes and stops the flow of air. You can damage the seat with excessive closing pressure.

Valves for scuba tanks have several features, one of which is a snorkel tube that extends from the bottom of the valve into the scuba cylinder. The valve snorkel prevents moisture or particles from entering the valve when you invert the tank. Another standard feature of tank valves is a thin, metal disk called a **burst disk**. If a tank is overfilled or the heat from a fire causes the tank pressure to increase to a hazardous level, the disk will burst and vent the tank to prevent an explosion. The disks corrode over time, and occasionally a burst disk ruptures. The failure makes a loud noise, and the tank hisses loudly, but the situation is not dangerous (even if it occurs while you are diving, which is unlikely). If the burst disk in your tank valve ruptures, you need to have the valve serviced professionally. Manufacturers rate burst disks for various pressures, and the correct disk must be used. Keep the pressure rating of the burst disk in mind if you want to change a valve from one scuba tank to another. A valve with a low-pressure burst disk will rupture if you use it on a tank with a higher pressure rating.



Figure 4.24 K-valve.

There are two types of outlets for scuba tank valves. The traditional outlet is nearly flush with the surface of the valve and surrounded by a soft, circular ring called an **O-ring**. The ring forms the high-pressure seal between the valve and the scuba regulator, so the ring must be clean and free of nicks or cuts. A newer type of threaded outlet with a recessed O-ring seal is a **DIN valve**, which withstands higher pressures than a traditional O-ring valve (see figure 4.25). Tank pressures in excess of 3,000 psi (204 atm) require a DIN fitting.



Figure 4.25 Close-up of a DIN valve.

Reserve Valve

A **J-valve** (the valve was listed as item J in the first equipment catalog) was designed to maintain a reserve of air to permit a normal ascent. The introduction of **submersible pressure gauges** (SPGs) for scuba tanks has rendered the J-valve obsolete.

The reserve lever on a J-valve created problems. If the lever was in the incorrect position (down), the valve would not maintain a reserve. If the diver failed to put the reserve lever in the up position before a dive or if the lever was bumped during a dive, the diver relied on a reserve of air that was not available. Safety concerns also contributed to the demise of the J-valve.

Valve Care and Maintenance

Cylinder valves are made of soft metal and have thin areas, so physical abuse can ruin them. A protective cap is a good accessory for a tank valve. The cap helps prevent loss of the O-ring, helps keep dirt out of the valve, and helps prevent physical damage to the high-pressure sealing surface around the valve opening. Protection of the valve is one reason that you should secure scuba tanks when you store them and should not leave them standing unattended. If a tank rolls about or falls over, this can damage the valve and render it inoperable.

When you open a tank valve, you should turn it slowly, open it all the way, and then close it one half turn. If something strikes the handle, a valve seat that is fully open will be damaged more than if it were closed slightly. When you close the valve, avoid excessive force, which shortens the life of the valve seat.

Rinsing your tank valve after use is a good idea, but soaking the valve by inverting your scuba tank in a container of warm water is better than rinsing. Water remains in the valve opening after rinsing or soaking. Open the valve momentarily to blow the water from the opening. If you leave the water in the opening and have the tank filled before the water evaporates, moisture will be forced into the tank.

Have your tank valve serviced annually by a professional. Also have your valve professionally serviced anytime it fails to operate easily or when the burst disk needs to be replaced. Valves receive partial servicing (lubrication) during the annual visual inspection of your scuba tank. The large O-ring that seals the valve to the scuba tank can be replaced at the time of the visual inspection. But partial servicing of your valve during a tank inspection is not the annual servicing of the valve. In a complete valve servicing, a qualified repair technician completely disassembles the valve, cleans the parts, replaces various parts, reassembles the valve, and then tests the unit.

Scuba Regulators

The function of a regulator is to reduce high-pressure air to a breathable level. Most scuba regulators use two **stages** of pressure reduction. The first stage of a regulator attaches to the valve of a scuba cylinder and reduces the high pressure to an intermediate pressure of about 140 psi (9.5 atm). The first stage of the regulator connects via a hose to the second stage, which contains the mouthpiece. The second stage reduces the pressure from the intermediate level to the surrounding pressure. A scuba regulator is a demand system; it delivers air only when you demand it by inhaling, unlike a constant-delivery, free-flow system, which commercial divers use. Scuba regulators are highly reliable and have a fail-safe design that turns the demand system into a free-flow system in the event of a component failure. Figure 4.26 provides more information about scuba regulator terms.



Figure 4.26 Scuba regulator nomenclature: (1) first stage, (2) dust cover, (3) low-pressure hose, (4) low-pressure inflator hose, (5) console, (6) high-pressure hose, (7) primary second stage, (8) extra second stage.

First Stages

The first stages on scuba regulators are either balanced or unbalanced. Changes in tank pressure affect the performance of a balanced first stage only slightly. With an unbalanced first stage, the performance of the regulator changes as tank pressure changes, so a balanced first stage is desirable.

The two main types of valves for the first stages of regulators are diaphragm and piston (see figure 4.27). A diaphragm first stage has a diaphragm that keeps water and dirt from the working parts inside. A bias spring combined with water pressure pushes the valve open. Tank pressure closes the valve when the first-stage pressure equals intermediate pressure plus water pressure. A diaphragm valve has more parts than a piston first stage, so it is more expensive to manufacture and service. The diaphragm valve's exclusion of water and dirt from the mechanics allows high performance for longer periods of time than a piston valve.

Piston first stages have an open, simple design with few moving parts. Water pressure in direct contact with the piston combines with the force of a bias spring to open the piston valve. Tank pressure causes the piston to move and the valve to close when the first-stage pressure equals intermediate pressure plus water pressure. Piston first stages are easier and less expensive to service than diaphragm first stages. But dirt, salt crystals, and mineral deposits that accumulate inside a piston regulator can affect its performance. Each type of first stage has advantages and disadvantages, so either type is acceptable. A diaphragm-piston regulator combines the diaphragm and piston concepts. The diaphragm excludes water and dirt and transfers pressure to a piston.



Figure 4.27 Typical regulator first stages. Red arrows represent spring pressure. Black dots represent O-rings.

A first stage must have a means of attachment to the tank valve. A typical regulator has a yoke that surrounds the valve and mates the regulator to the tank valve. The regulator inlet, which has an inlet filter, secures to a tank with a yoke screw. Scuba regulators that operate at above-average pressures use a DIN fitting instead of a yoke screw. A DIN fitting screws directly into a DIN valve and does not have a yoke.

First stages include multiple openings called **ports**. One of the ports is for high-pressure air measurement with an SPG. The remaining ports are for low-pressure air. A regulator should have several low-pressure ports to supply air to the primary second stage, an alternate second stage, a BC inflator, and possibly a dry suit inflator. The sizes of ports vary. The high-pressure port is usually larger than the low-pressure openings. This helps prevent connection errors; a low-pressure hose inadvertently connected to the high-pressure port would rupture.

Some regulators feature environmental shielding by sealing special fluid inside a flexible chamber attached to the first stage. The sealed, flexible chamber transmits water pressure to the regulator, but no water, salt, or dirt can enter the first stage. Extremely cold water can cause an unshielded regulator to freeze, but the fluid in an environmental chamber does not freeze.

Second Stages

The most common second stage is shaped like a cup lying on one side (see figure 4.28). Imagine a pliable diaphragm across the top of the cup, a mouthpiece attached to the bottom of the cup, and an exhaust valve attached to the lower side. A lever that activates a valve inside the container is in contact with a static diaphragm. An inhalation through the mouthpiece creates a partial vacuum inside the second stage. The pressure reduction pulls in the diaphragm, which moves the lever and opens the valve, allowing air to flow from the first stage


Air from tank
Inlet valve
Purge button
Mouthpiece
Movable lever
Flexible diaphragm
Exhaust valve
Static
Inlet valve opens
Inhalation
Exhaust valve closed
Diver inhales
Inlet valve closes
Exhalation
Exhaust valve open
Diver exhales

Do not depress purge button when rinsing a regulator.

Have regulator serviced professionally every year.

Figure 4.28 Regulator operation.

of the regulator into the second stage. When you stop inhaling, the buildup of pressure returns the diaphragm and lever to their normal positions, closing the valve and stopping the flow of air. When you begin to exhale, increased pressure inside the second stage opens the exhaust valve, allowing air to escape.

The two types of second-stage valves for scuba regulators are the downstream valve and the pilot valve. In a downstream-valve regulator, a small bias spring holds a valve closed. Inhalation moves the diaphragm, which moves a lever. The lever movement overcomes the resistance of the bias spring and opens a valve, allowing intermediate-pressure air to enter the second stage. After inhalation, air flows until the diaphragm moves outward, allowing the bias spring to close the valve. Downstream second-stage valves are simple and inexpensive, and they tolerate more sand and dirt than pilot valves do.

In a pilot-valve regulator, the movement of the diaphragm in the second stage opens a small valve that in turn opens a larger valve. When you stop inhaling from the regulator, the diaphragm returns to its normal position, and the valves close. A pilot valve delivers air up to four times more easily than a downstream valve. But pilot valves are more expensive to manufacture and service than downstream valves, and in shallow water, you may experience the effect of shuddering air movement with a pilot-valve regulator.

All regulators have a purge button or area on the regulator that you depress to manually open the second-stage valve. Use the purge to test the regulator, to expel water and debris from inside the second stage, and to relieve the pressure in the regulator after you close the tank valve.

The location of the exhaust valve varies. The exhaust valve may be at the bottom, the side, or the front of the second stage. The position of the exhaust affects the bubble pattern and the clearing of the regulator when it has water inside and the mouthpiece is in your mouth. Some regulators direct exhaust bubbles by means of an exhaust tee. You will learn more about regulator positioning for clearing in chapter 6.

A regulator is either right-handed, left-handed, or bidirectional, referring to the direction from which the regulator hose must come when the regulator is in your mouth. For example, the hose must come from the right side when you are using a right-handed regulator. The hose may come from either side when you are using a bidirectional regulator. The directional configuration is important only for knowing how to orient the regulator when you place it in your mouth. Figure 4.29 shows the possible directional configurations.

Some second-stage casings feature strong, light, durable materials that do not bend or corrode as metal does. Several types and styles of mouthpieces are available. Use a soft, comfortable mouthpiece that does not cause jaw fatigue. A repair technician can replace mouthpieces quickly and easily.



Figure 4.29 Scuba regulators have different configurations.

Regulator Accessories

A regulator hose is flexible but has rigid metal connectors crimped onto the ends. The points where the hose and the metal meet are stress points because the hose fibers strain against an unyielding surface. To prevent the breakdown of the hose fibers at the stress points, you should use hose protector sleeves. At a minimum, equip all regulator hoses with hose protectors at the first-stage end of each hose.

Padded regulator bags help protect your regulator during transportation or storage. The bag should be large enough to accommodate the regulator and all hoses without bending the hoses sharply.

Adapters allow you to use DIN-fitting regulators on standard cylinder valves. Use protective covers for the threads on DIN fittings.

Purge depressors are a built-in feature on some regulators and an accessory for regulators that do not have them. A purge depressor partially depresses the purge button to remove bias spring pressure from the second-stage valve when you are not using the regulator, thus extending the life of the valve seat.

Colored second-stage covers allow you to color-coordinate your regulator with your other equipment. Other accessories include various mouthpieces and hose adapters (as previously mentioned).

Regulator Selection

It takes effort to inhale and exhale through a scuba regulator. Effort is needed to overcome resistance; good regulators have minimal breathing resistance. Compare the performance data for various regulators, and select one that lets you breathe easily over a wide range of tank pressures, which implies a balanced first stage.

Choose a widely used and easily serviced regulator. You should get a regulator that can be serviced by facilities anywhere you happen to be and that uses readily available parts.

The type of diving you do should affect your selection. If you plan to do most of your diving from shore, you should avoid a pilot-valve second stage, which is adversely affected by sand and dirt. Diaphragm first stages are a better choice if most of your diving is from shore.

If you do not have a scuba tank, consider purchasing the tank and regulator at the same time so that you can match the fittings of the regulator and the cylinder valve. If you will be diving in water that is near freezing, you should select an environmentally shielded regulator. Remember that enriched-air nitrox and mixed gases require specially cleaned and dedicated regulators.

Regulator Care and Maintenance

Your regulator is a precision instrument; it requires care and maintenance to ensure the best possible performance. Keep sand and dirt out of your regulator. Do not allow salt crystals to form inside. Soak your regulator in clean, fresh, warm freshwater as soon as possible after diving in the ocean. You need to remove salt before it dries. If you cannot soak your regulator, you should at least rinse it. A combination of soaking and rinsing is best. Follow these rules when rinsing or soaking a regulator:

- *Keep the inside of the first stage dry.* The purpose of the dust cover on the first stage is to keep out water and dust. Develop the habit of replacing the dust cover and securing it in place with the yoke screw anytime you do not have the regulator attached to a tank. Make certain the dust cover is in place before you rinse or soak a regulator.

- *Allow low-pressure water to flow gently through the second stage and also into the openings on the first stage.* High-pressure water can force dirt or grit into crevices, where it causes damage. Gentle pressure washes the dirt away.
- *Do not press the purge button when you rinse the second stage unless the regulator is pressurized.* If you do not pressurize the regulator and you press the purge button while water is inside the second stage, you open the second-stage valve and allow water to flow through the hose into the first stage.

When the regulator has dried thoroughly, lay it flat for storage. For prolonged storage, place the regulator in a plastic bag to help protect it against the harmful effects of smog. Do not bend the hoses sharply because bending damages hose fibers. Replace hoses that are cut, bulging, or leaking.

You can avoid most problems with your regulator by having it serviced annually. Have your regulator serviced even if it seems to be functioning properly. Failure to invest in regular service can affect your safety and shorten the life of your regulator.

Alternate Air Sources

Several equipment options can help if you run out of air underwater (although running out of air is due only to sheer negligence). Your best option is an alternate air source (AAS), which is a source of compressed air other than your primary scuba regulator. An AAS is valuable if your primary source of air begins free-flowing or leaking during a dive; you can switch to the AAS and make a normal ascent. The two primary types of alternate air sources are extra second stages and backup scuba units. An extra second stage allows two divers to share air without passing a single mouthpiece back and forth. Backup scuba units are fully redundant scuba systems that provide an independent source of air in an emergency. You are not dependent on a buddy to provide air when you are equipped with a backup system. Extra second stages are less expensive than backup scuba units but do not provide the benefits of an independent scuba system.

Extra Second Stages

Two types of extra second stages are available. The first is an extra second stage for your regulator; the second is a BC low-pressure inflator that has an integrated regulator second stage (see figure 4.30). An extra second stage, or **octopus**, should meet the following criteria:

- The first stage of the regulator should be capable of meeting the airflow demands of two second stages.



Figure 4.30 Extra second stages.

- The hose on the extra second stage should be several inches longer than the hose on the primary second stage.
- The extra second stage should attach to your chest area in such a way that your buddy can remove it quickly and easily. Do not allow the extra second stage to dangle.
- The attachment device should cover the mouthpiece opening of the extra second stage to prevent the regulator from free-flowing and to keep dirt and debris from getting inside.
- The extra second stage should be brightly colored for easy identification.

A regulator second stage may be integrated into a BC low-pressure inflator in one of two ways. The BC inflator can have a built-in regulator second stage, or quick-release hose fittings on the regulator second stage can allow it to be connected in series in the low-pressure hose leading to the inflator assembly. Both types of extra second stages have advantages and disadvantages. An integrated second stage requires one less hose on your regulator because a single hose provides air for both the extra second stage and the BC inflator. When you must share air and you have an integrated second stage, you must breathe from the integrated second stage because the hose is too short for your buddy to use. With an extra second stage, you or your buddy can use either air source. Extra second stages integrated into the BC inflator may leak air. To stop a leak, you must disconnect the low-pressure air, thereby losing the functions of the low-pressure inflator and the extra second stage.

Backup Scuba Units

Two types of backup scuba units are available. A **pony tank** is a small (about 13- to 20-cubic-foot, or 368 to 566 L) scuba cylinder with a separate, standard regulator. You clamp a pony tank to the side of your main scuba cylinder. A **Spare Air unit** is a smaller (2 to 4 cubic foot, or 57 to 113 L) scuba cylinder with a special regulator integrated directly into the valve. A pony tank provides an adequate supply of air for many situations, but a Spare Air unit provides only enough air to permit an ascent from shallow depths. On the other hand, a Spare Air unit is small and light, whereas a pony tank is bulky and heavy (see figure 4.31).



Figure 4.31 A pony tank and a Spare Air unit.

Alternate Air Source Care and Maintenance

AAS equipment should receive the same care and maintenance as your primary scuba equipment. Some divers attempt to save money by having only their primary scuba equipment serviced annually. This is false economy. AAS equipment needs servicing just as much as primary scuba equipment does.

Instrumentation

You move in three dimensions in water the way a pilot does in air. Instruments are important safety requirements for flying. A pilot needs information about altitude, direction, time, and amount of fuel remaining. Similarly, you need information about depth, direction, time, and amount of air remaining. The minimum instrumentation you need is a depth gauge, an underwater timer, a submersible pressure gauge (SPG), and a compass. A dive computer is highly recommended. All required instrumentation can be provided by a single integrated device.

Depth Gauges

To tell how deep you have descended, you can use one of four types of depth gauges: a **capillary gauge**, a **Bourdon tube**, a diaphragm gauge, or an electronic gauge. Manufacturers calibrate depth gauges in seawater. Most mechanical gauges do not indicate the correct depth in freshwater, but they indicate the equivalent seawater depth if you use them starting at sea level in freshwater or if they adjust for altitude pressure changes. The reading of gauges in freshwater is acceptable because tables for time limits at various depths are based on sea-level depths. Table 4.5 compares the four types of depth gauges.

A capillary depth gauge is a simple instrument. It is a hollow, air-filled, transparent plastic tube sealed at one end and placed around a circular dial. The open end of the tube aligns with zero on the gauge dial. A capillary gauge uses the principle of **Boyle's law**. Water pressure compresses the air inside the tube during descent. The position of the air–water interface inside the tube relative

Table 4.5 Depth Gauges

Type	Accuracy	Advantages	Disadvantages
Capillary	Accurate only to depth of about 40 ft (12 m)	Rugged, inexpensive	Can clog with debris or air bubbles
Bourdon tube	Reading accurate within 1% to 2%	Accurate	Can be damaged by reduced pressure at altitude
Diaphragm	Very accurate	Can adjust zero setting for pressure changes at altitude	Expensive
Electronic	Reading accurate within 6 in. (15 cm)	Gauge may zero itself to compensate for changes in atmospheric pressure	Must have sufficient battery power; expensive

to markings on the dial indicates the depth. At two atmospheres of pressure, the air column in the tube compresses to one half its original length.

A Bourdon tube is a thin metal tube formed into a spiral. The tube may be open to the water, or it may be closed and placed inside a housing filled with oil. Oil-filled Bourdon gauges are more popular than open-tube gauges. Pressure on an open-tube gauge begins to straighten the tube and increases the coil diameter. The straightening produces a spiral movement of the tube, which is linked mechanically to a needle to indicate the depth. Water pressure causes the coil of a closed-tube gauge to decrease in diameter. The movement of the coil, linked mechanically to a needle, indicates the amount of pressure exerted on the gauge.

The accurate but expensive diaphragm gauge uses elaborate mechanics to connect a thin, movable diaphragm to an indicating needle. Electronic depth gauges, also accurate and expensive, use a pressure sensor (transducer), electrical circuitry, a display, and a battery to indicate depth.

A maximum-depth indicator is a desirable feature for depth gauges. As you will learn in chapter 7, you must know the depth of a dive for planning purposes. A digital depth gauge retains the maximum depth you attain. The instrument displays the information until the next dive or for 12 or more hours after a dive; it then resets automatically. Many modern depth gauges with needle displays have a thin indicating wire that the gauge needle pushes along the dial face. When the needle retreats, the wire remains at the highest point reached on the dial. You can reset the indicating wire by turning a screw on the dial face. When you use this type of gauge, you must remember to reset the maximum-depth indicator before each dive.

Underwater Timers

You can use either an automatic or a manual underwater timer to keep track of time during a dive. Either type may indicate time with hands on a dial or with a digital display. Pressure activates automatic timers, which start timing at a depth of about 3 to 5 feet (1 to 1.5 m) and stop timing when the depth is less than that. Automatic timers are better than watches because you do not have to remember to start or stop the timing of your dive, although you have to reset some watch-type automatic timers before a dive. Waterproof watches that you can use as underwater timers usually feature a rotating **bezel**, a movable ring that you can set to indicate elapsed time. Digital watches are accurate, but their small buttons can make them difficult to operate. The best timers are electronic automatic timers, which can keep track of how long you dive, how long you are at the surface between dives, and how many dives you make. You do not have to remember to reset or activate anything when you use an automatic electronic timer. Dive computers track underwater time precisely. Some computers can display a timed profile of the dives that you make.

Dive Compasses

Rarely can you see more than 100 feet (30 m) underwater, so a navigational aid can be valuable. If you dive without a directional reference, you can end a dive a long distance from your planned exit point. A dive compass can help you avoid long surface swims or swims through thick surface canopies of water plants. You can use a compass to navigate beneath the canopies, where there are passages through the plants. A compass is also useful for relocating a precise area underwater and as a surface navigation device if fog arises.

Three types of compasses are card types, needle types, and electronic. Card and needle compasses are mechanical. Magnetic deposits in the earth near the North Pole attract either a magnetized disk or a magnetized needle to provide a directional reference. The compass card or needle can deviate from its correct alignment if it is in close proximity to ferrous metal or a source of magnetic forces such as a magnet or electrical motor.

The earth's magnetic field varies in different locations, and the variations affect the balance of the compass card or needle. Some manufacturers offer compasses balanced for different zones of the earth. A good compass has a good tilt potential of plus or minus 30 degrees. Be sure to ask about balancing when selecting a compass.

Diving compasses have liquid inside to dampen the swinging of the needle or disk. To be useful for diving, a compass needs a reference line, called a **lubber line**, to indicate the direction of travel relative to the needle reference. Another desirable feature is a rotating bezel with bracketing index marks that allows you to mark the needle position for a specific direction.

You view some compasses from the top and some from the side. Side-reading compasses display the course in a window on the side of the instrument. You look across a top-reading compass. You will learn how to read and use a compass in chapter 6.

Digital compasses are usually an integrated component of a dive computer (see figure 4.32). The direction of travel is displayed both graphically and numerically. A heading (desired direction) can be set and the device will indicate any correction needed to remain on course. Bearings can be stored in a memory device.



Figure 4.32 Console with computer and SPG (left) and electronic dive compass (right).

Submersible Pressure Gauges

An SPG is analogous to the gas gauge of a car and is just as essential. The SPG measures scuba cylinder pressure. You can use either a mechanical or an electronic SPG. A mechanical SPG is a high-pressure Bourdon tube. High-pressure air from the cylinder passes through the regulator first stage, through a high-pressure hose, and into a Bourdon tube inside a housing at the end of the high-pressure hose. The pressure tries to straighten the spiral tube, which moves a needle on a dial to indicate the tank pressure. Physical shock can damage a mechanical SPG.

An electronic SPG has a pressure sensor (transducer), circuitry, a battery, and a display. It is a form of a high-pressure depth gauge. The display may be digital or graphic. Either a symbol or numbers (in pounds per square inch, atmospheres, or bars) indicate the amount of air in your tank. If the electronics get wet or if the battery dies, an electronic SPG will not function. Some electronic SPGs are hoseless—they do not require an air hose between the cylinder and the gauge, which usually serves multiple functions (dive computer, compass, and SPG). You should retain at least 300 to 500 psi (20 to 34 atm) in your tank at the end of a dive. Mechanical SPGs typically have a red area on the dial for the last 500 psi. When you dive, you should monitor your air supply and make sure that you surface before the needle gets into the red area. Electronic depth gauges usually warn of a low supply of air by blinking the display.

An SPG has a **blowout plug** to relieve pressure in the housing in the event of a high-pressure leak. Identify the blowout plug on your SPG, and do not place anything over the plug that will prevent it from functioning. If the plug cannot come out to release high pressure inside the SPG housing, the face of the instrument can explode.

Instrument Consoles

You can purchase diving instruments individually or in combination. It is convenient to combine several gauges into a display unit called a **console**. An instrument console attaches to the high-pressure hose coming from your regulator first stage. When your instruments are in a console, your arms are free of gauges, and dive preparations are quicker.

The two types of instrument consoles are mechanical and electronic. A mechanical console contains an SPG and a depth gauge. Some also contain an underwater timer, a compass, and a thermometer. The instruments usually feature luminous displays, which are easy to read in low light.

With an electronic console, all instrument information is in a single display (see figure 4.32). If one gauge fails in a mechanical console, the remainder can still function; but when an electronic console fails, all the information provided by the unit is lost. Electronic displays are difficult to read in the dark unless they feature some type of illumination.

Dive Computers

A dive computer is an electronic instrument with a pressure sensor, electronic circuitry, a battery, and a display. A programmed computer inside the instrument uses pressure and time information to continuously calculate the uptake of nitrogen by various compartments that have different half-times. A half-time is the length of time required for a mathematical model (compartment) to increase or decrease its gas absorption or elimination by one-half. A compartment—which resembles, but does not duplicate body tissues—is completely saturated or desaturated in six half-times. When the absorption by any one of a computer's compartments reaches a predetermined level, the device indicates that you are approaching the time limit after which a direct ascent to the surface will no longer be possible. On reaching that time limit, the computer indicates a minimum depth—a **ceiling**—that you cannot exceed during ascent. You risk decompression sickness unless you wait until the computer indicates that sufficient outgassing has occurred to allow you to continue your ascent. A dive computer provides extremely accurate time and depth information. Other common features are a low-battery warning, a rapid-ascent warning, a dive log mode, a dive-planning mode, and information about flying after diving. Additional information about dive computers is provided in chapter 7.

Instrument Care and Maintenance

Physical abuse can damage instruments, so protect your instruments from shock. Secure your console instead of allowing it to swing freely.

Heat or prolonged exposure to hot sunlight can cause oil in a liquid-filled gauge to expand and break the seal on the housing encasing the instrument. If you break the seal, you must have the gauge repaired. Hot water in a whirlpool or a shower can cause an underwater timer to expand, break a seal, and allow water inside. Do not subject diving instruments to high temperatures.

Have air leaks in SPGs repaired at the first opportunity. Have your depth gauge tested for accuracy from time to time by a professional repair facility, or compare your gauge with an extremely accurate instrument, such as a digital depth gauge. Follow all the manufacturer's recommendations. Reduced pressure at elevations above sea level can damage some instruments. Unless an instrument is designed for use at altitude, pack it in an airtight container for flying. Soak and rinse instruments with clean, fresh water after use. Give special attention to pressure-sensing areas to prevent them from becoming clogged with dirt or salt crystals.

Electronic gauges require batteries. Some gauges must be returned to the manufacturer for battery replacement. Gauges that permit the consumer to replace batteries will flood if the batteries are not replaced properly.

Dive Knives and Accessories

This section addresses some additional required and optional equipment. Figure 4.33 shows examples of a dive knife and other dive accessories.

Dive Knives

A dive knife is a required equipment item. Lines and cords in water can cause entanglements, so you must have a knife to cut yourself or your buddy free if necessary.


Figure 4.33 Dive knives and accessories.

The many designs of dive knives include large knives and small knives. A small knife positioned where you can reach it easily is better than a large knife that you cannot reach. The most important feature of a dive knife is an effective cutting edge. Good blades are corrosion resistant and hold a sharp edge; serrated blades cut lines more effectively than straight blades.

Some knives are multipurpose tools designed for prying, digging, pounding, and measuring in addition to cutting. If you have a multipurpose knife as a diving tool, you should also have a small, separate dive knife.

A dive knife comes with a sheath, which has some means to lock the knife in place. Make sure the sheath lock is reliable to prevent losing a knife. You can attach a small knife to your leg, your arm, your console, or your BC. Wear a large knife on the inside of your leg and secure it with straps that stretch to compensate for exposure suit compression.

To prevent corrosion, rinse your dive knife after diving. Inspect the edge for sharpness, remove any rust, and coat the blade with grease.

Accessories

You are likely to need several small, but important, accessory items. These items include a gear bag, a dive flag and float, dive lights, dive kits, signaling devices, dive slates, and a diver's first aid kit.

Gear Bags

You need so much equipment for diving that you also need a means to carry it. Gear bags can be simple or complex. They can feature multiple compartments, padding, novel ways for carrying or moving, sealed fabric edges, and various fabrics. The best type for you depends on your needs and how much you want to invest. Be sure to get a bag with webbing handles that completely surround the bag to provide full, durable support. No matter what your budget, you need a gear bag for your equipment.

Dive Flags and Floats

In many areas, local law requires the use of a dive flag while diving. In the United States, the traditional dive flag is a red flag with a white diagonal stripe (see figure 4.34). The flag is usually vinyl, mounted on a fiberglass staff, and stiffened with



Figure 4.34 Dive flags.

a wire so that it stands out from the staff at all times. In addition to the red and white flag, you should use the international Alpha flag—a swallow-tailed blue and white flag—when diving from a vessel. The Alpha flag is a general dive flag in countries other than the United States.

Unless you are diving from a boat, you need a float to support your dive flag. Some flagstaffs have a float attached. You can also get attachments to secure a dive flag to an inner tube. Another option is a flag-holding canvas covering for an inner tube.

Dive Lights

A dive light can increase your diving enjoyment. Light levels are low underwater, and a light restores color to objects at depth and allows you to peer under ledges and into holes. You can see and enjoy much more when you use a dive light.

The many types of dive lights available include large, powerful, rechargeable lights and small lights that use disposable batteries. Consider a small dive light initially. A large light is for night diving, which is an advanced activity. A small light is easy to carry and is useful both for day dives and as a backup light for night diving. Many of today's small dive lights are bright and compact (see figure 4.35). Maintain your dive light according to the manufacturer's instructions.



Figure 4.35 Dive lights are useful during the day or night to restore color visibility and illuminate dark places.

Kits

Two equipment kits are recommended: a dive kit and a save-a-dive kit. The dive kit contains items you use frequently for diving. The save-a-dive kit contains items you may need to salvage a dive. See the Equipment Kits sidebar for items that you might include in each kit. Because the items in your dive kit are small and get wet, you may want to keep them in a container by themselves so you can find them easily.

Once you get yourself and your equipment to a dive site, you don't want a minor equipment problem to keep you from diving. A broken strap, a missing O-ring, and a torn mouthpiece are examples of problems that can stop you from diving unless you have spare parts. Keep save-a-dive items in a waterproof box. Do not mix wet items from your dive kit with dry items in your save-a-dive kit.

Dive Slates

You need to record and refer to information around and in the water when you dive. Plastic slates are better than paper because water does not affect the slates. You can write on dive slates with a standard lead pencil or a grease pen.

Equipment Kits

Dive Kit

- Defogging solution for your mask
- Lip balm
- Wet suit shampoo
- Seasickness medication
- Sunscreen

Save-a-Dive Kit

- Mask strap
- Regulator mouthpiece
- Fin strap
- Crescent wrench
- Snorkel keeper
- Screwdrivers
- Tank valve O-rings
- Cable ties
- Quick-release buckle
- Twine
- Weight keepers
- Duct tape
- Superglue
- Extra batteries
- Heavy nylon thread and heavy-duty needles
- Neoprene cement
- Fiberglass cast tape for temporary repairs

Dive slates include checklist slates, reference slates, logbook information transfer slates, and writing slates. All types have value. You will probably have several slates when you become an experienced diver. Initially, you should have an equipment checklist, a dive-planning slate, and an underwater writing slate.

Signaling Devices

Long-range signaling devices are invaluable if you become adrift, especially in areas where currents are strong. You should have a whistle readily available. A whistle is more effective than shouting to gain attention. The sound from a whistle does not require much energy to produce, and it travels well over water.

A diver's air horn, powered by low-pressure air, works with as little as 50 psi (3.4 atm) of tank pressure and produces a sound that can be heard up to a mile away. Although this device is small, it is so loud that you must point the horn away from yourself to avoid hearing damage.

You can get long, bright, thin, inflatable safety tubes that fit easily into your BC pocket. Inflate a safety tube at the surface to make yourself easier to spot in the water.

You can use a signal mirror to flash sunlight long distances over water. Other forms of signaling devices for divers are flashlights, strobe lights, and waterproof flares. The greater the chance of being caught in a current, the greater your need for signaling devices.

Diver's First Aid Kit

Diving takes place in remote areas, and because it is a physical activity, someone may be injured. You need to be prepared for an emergency. You should have a first aid kit at the dive site. See the First Aid Kit sidebar for items that should be included in a standard first aid kit. Pack the items in a waterproof container. Chapter 6 addresses the use of the first aid items.

First Aid Kit

- Rescue breathing mask
- Tweezers
- Seasickness medication
- Bandage scissors
- Isopropyl alcohol
- Penlight
- Hydrogen peroxide
- Coins for emergency phone calls
- White vinegar
- Emergency contact information for diving accidents
- Baking soda
- Diving first aid book
- Analgesic and antiseptic ointment
- Space blanket
- Hot packs
- Pen and small notebook
- Eyewash
- Rubber band tourniquet
- Triangular bandages

Specialized Equipment

Other specialized equipment for scuba diving includes nitrox (oxygen-enriched air) equipment, mixed-gas equipment, and rebreathers. This equipment permits divers with specialty training to obtain longer dive times. The risks associated with the use of specialized equipment make training and adherence to the rules pertaining to its use absolutely essential.

Enriched-Air Nitrox (EANx)

Breathing gas that contains levels of oxygen greater than the 21 percent found in air provides benefits for divers. Higher oxygen levels reduce the amount of nitrogen absorbed, thereby reducing the problems posed by decompression illness. However, divers must know the technical requirements and dangers associated with the use of EANx. Dedicated equipment and specialty training are essential.

Filling standard cylinders with EANx is not permitted. Nitrox equipment is clearly marked to differentiate it from standard scuba equipment (see figure 4.36). Nitrox blending stations are available at many modern dive facilities. Standard blends of nitrox are EAN32 and EAN36, which contain 32 and 36 percent oxygen respectively (also called Nitrox32 and Nitrox36). Nitrogen and oxygen are blended together during the filling process, but the final mixture may not be exact. Divers need to test the oxygen percentage of the gas in their cylinder before diving. The divers use a handheld oxygen analyzer to ensure that the oxygen level is acceptable.

If you breathe oxygen at a partial pressure that is too high,



Figure 4.36 Nitrox tanks have explicit markings to differentiate them from standard cylinders.

convulsions can occur. Partial pressures of oxygen must be kept within safe limits (1.4 to 1.6 atm or bars). For this reason, there are maximum operating depths (MODs) for nitrox diving. The MODs for EAN32 and EAN36 are 110 feet (33.5 m) and 95 feet (29 m) respectively. These are absolute depths and must not be exceeded. Additionally, divers must determine equivalent air depths (EADs) for decompression. Modern dive computers allow divers to select the type of breathing gas being used. The computers automatically calculate EADs and are recommended for mixed-gas diving.

Dive operators and gas blending facilities require proof of specialty training for the use of EANx. Training is widely available.

Technical Diving

This form of diving is even more specialized than the use of enriched-air nitrox because it involves the use of mixed gases and highly technical equipment. Breathing gases include helium, neon, nitrogen, and oxygen; these gases are mixed in various quantities depending on the depth. Obviously, divers need substantial training before they attempt this method of diving. Some gas mixtures will not sustain life until the partial pressure of the oxygen in the mix increases with depth. In this instance, technical divers must use travel tanks to reach a safe depth before switching to the low-oxygen mixture in the primary unit. The principal goal of technical diving is to allow divers to exceed recreational depth and time limits. Technical diving has greater risks than recreational diving, but many consider the rewards worth the risk.

Some technical divers use multiple large-capacity cylinders for open-circuit scuba diving. Others use complex and expensive closed-circuit rebreathers (CCRs) to obtain greatly extended dive times. Rebreathers, which use a mixture of oxygen and inert gas, allow exhaled oxygen to be breathed repeatedly until it is metabolized. Additional oxygen is added as needed to the inert gas in the system to maintain required levels. Exhaled carbon dioxide is absorbed by a canister called a scrubber. Oxygen replacement may be controlled automatically by a central processing unit or may be controlled manually by a valve. The result, which is not affected by depth, allows a diver to remain submerged for hours at a time or to make multiple dives with a single fill of breathing gas. Figure 4.37 illustrates a modern CCR.

Dive preparation and predive procedures vary greatly from open-circuit scuba diving. For example, a diver needs to prebreathe a CCR to activate the absorption process of the carbon dioxide scrubber. This procedure can take several minutes and is affected by the temperature of the absorbent. The diver also needs to check the unit's calibration at a depth of 20 feet (6 m) during descent. Changes in the gas mixture that are made during ascent must be managed by a central processing unit or managed manually by the diver. This truly is technical diving.



Figure 4.37 CCR 2000 rebreather.

Courtesy of Dan Wible.

SCUBA WISE

If you want to avoid diving accidents, you should use familiar, correctly fitting, well-maintained dive equipment the way that it is intended. As I look back over several decades of dive experience, I can recall many instances when divers got into trouble because they did not follow the essential equipment safety procedures summarized in the previous sentence. Diving allows us to explore an alien environment using life-support equipment. Modern scuba equipment is manufactured well, but you must take care of it and have it serviced periodically to keep it functioning properly. Would you even consider going into outer space with life-support equipment that was not carefully maintained and serviced? We go into inner space when we dive. Our life-support equipment is just as vital to us as an astronaut's.

Equipment problems while diving do arise, but equipment failure is rarely the cause of an accident. Problems cause anxiety and stress. A diver experiencing stress from environmental factors and fear may panic from the added stress that a minor equipment problem might pose. Learning to manage yourself and your equipment helps you reduce stress, avoid panic, and prevent an accident. One of the most important rules of accident-free diving is to have good, familiar equipment that is in good condition and to use it properly.

Oxygen levels are managed by employing multiple sensors, which are accurate devices when maintained and calibrated. Current CCRs lack reliable carbon dioxide sensing devices. Carbon dioxide toxicity can be fatal, and a diver's symptoms are not a reliable indicator. This problem requires the usage time of the carbon dioxide absorbent to be monitored and the absorbent must be discarded when time limits (based on statistical tests) have been attained.

Because CCRs are expensive, must be used frequently, and require extensive maintenance, they are used by relatively few divers. But the advantage of greatly extended dive times appeals to many divers, so the popularity of rebreathers is increasing.

Summary

Diving involves a great deal of equipment. You are beginning to understand the equipment you need to have, how to select it, and how to care for it. You will learn more about equipment from your instructor, from retailers, from magazines, and from other divers. Get good equipment, and give it the best care possible. Diving is not enjoyable if you have constant equipment problems.

Application-of-Knowledge (AOK) Questions

1. Diving equipment is expensive. What are the best procedures to follow that will increase the life of your equipment?
2. What two concerns are most important when selecting diving equipment?
3. You were unaware that your regulator was free-flowing behind you at the surface at the end of a dive, and your tank lost all of its air. When you move your tank after the dive, you feel water sloshing inside. How was the water able to get into your cylinder?
4. You have weighted yourself to be weightless in water and are able to sink with your BC deflated just by exhaling. At the end of the dive you are unable to stop your ascent as you near the surface, even when you exhale completely. What is causing this undesirable change in buoyancy?
5. You are diving in a dry suit. You have added air to the suit to maintain a constant volume as you descend. You find a small anchor on the bottom and decide to salvage it. You pick up the anchor and carry it with you. To offset the weight of the anchor, you add more air to your dry suit. Why is this action a dangerous practice?
6. You and your buddy are practicing compass navigation by swimming a compass course. You place your compass next to your buddy's to compare headings and proceed along your planned course, but you missed your mark and had to surface. You find that you swam in the wrong direction. What caused this error?
7. What is the best way to remove salt, debris, or chlorine from you diving equipment?
8. A scuba regulator can have four or five hoses attached to the first stage. Can you think of the purposes of these hoses?
9. What are the best reasons for having good dive equipment and maintaining it properly?

School of barracuda in the Florida Keys

5

Diving Environment



Dive In and Discover

By the end of this chapter, you will be able to do the following:

- Describe the aquatic food cycle and explain how the process contributes to red tide.
- List five types of aquatic life injuries and three ways to avoid such injuries.
- List four types of pollutants and describe the effects they have on the underwater environment.
- List three actions that divers can take to help preserve aquatic life.
- List five ways to keep from damaging the environment while you are underwater.
- Contrast the general diving conditions for freshwater diving and saltwater diving.
- Describe the hazards of cavern diving, cave diving, and ice diving.
- Explain the cause of tides and their effects on diving activities.
- Explain the cause of waves and surf and their effects on diving activities.
- Explain the causes of currents and their effects on diving activities.
- Describe a rip current and explain how to escape from one.
- Define the terms *plankton*, *bloom*, *red tide*, *kelp*, *stipes*, *fronds*, *ciguatera*, *scombroid*, *tetrodotoxin*, *thermocline*, *overturn*, *reverse thermocline*, *upwelling*, *eddies*, *cavern*, *cave*, *sink*, *siphon*, *turbid*, *continental shelf*, *tsunami*, *stand*, *spring tide*, *neap tide*, *flood*, *ebb*, *slack water*, *fetch*, *swell*, *crest*, *trough*, *wave height*, *wavelength*, *wave period*, *wave train*, *surge*, *surf*, *gyres*, *downwelling*, *rip current*, *drift*, *set*, *drift dive*, and *trail line*.

Aquatic Biology

The plants and animals of the underwater world are wondrous and diverse. The millions of animals in the aquatic realm range from those that are microscopic to those weighing tons. To appreciate, respect, and enjoy aquatic life, you need to learn a bit about biology. This section familiarizes you with the flora and fauna of the aquatic realm. Aquatic life fits into three categories: lifeforms that drift with the currents, those that swim freely and are able to move against the currents, and those that dwell on the bottom.

Drifters

The drifters are called **plankton**. Animals that drift are called zooplankton. Drifting plants are called phytoplankton. Plankton begins the food cycle in the waters (see figure 5.1). Small animals eat plankton, and larger animals eat the smaller animals. When the large animals die, their remains sink to the bottom and decompose. The decomposed material rises to the surface, where it becomes food for the plankton. Warm water and nutrients cause some plankton to multiply. Overpopulations of plankton, called **blooms**, can color the water, destroy underwater visibility, and form toxins in animals that feed by filtering water. Toxin from blooms makes clams and mussels unsafe for consumption during summer months in some areas. One type of red phytoplankton often creates blooms, known as **red tide**, in the seas. Diving conditions are poor in areas affected by plankton blooms.

Another type of aquatic plant, called algae, is an important part of the aquatic world. Plants use light to produce their own food and become food for animals. They convert water and carbon dioxide to oxygen and carbohydrates through the process of photosynthesis. Various types of algae are found in underwater areas where light is available. Most algae grow in shallow water where light is most abundant. Thick moss drapes objects in some freshwater areas. Turtle grass is a grasslike, green, tropical saltwater plant that provides a habitat for many forms of life. Some types of long, flowing algae in cold and shallow water, such as surf grass or eel grass, can cause you to trip if you try to walk in them. Slippery plants cover rocks and can cause you to slip and fall unless you move cautiously.

Giant algae, called **kelp**, produce long strands, called **stipes**, in which you can become entangled. You can learn how to avoid and how to deal with this problem. A rootlike structure, called a holdfast, anchors kelp to the bottom; numerous gas bladders, called floats, lift

Learning to dive gives you an opportunity to become more familiar with the aquatic environment, which covers over 70 percent of the surface of the earth. The underwater world is fascinating. This chapter introduces you to biological and physical conditions of the diving environment. You will learn the effect of people on the environment and the effect of the environment on people. You affect the underwater world more than you might imagine.

A juvenile octopus in California

the top parts toward the surface. What appear to be the leaves of kelp are **fronds**. Large areas of kelp are known as kelp beds, which have thick canopies that blanket the surface of the water (see figure 5.2). It is difficult to swim through a kelp canopy at the surface, but it is easy to swim between the clumps of stipes beneath the surface. Underwater navigational skills are important when diving in areas where kelp is dense. Kelp forests are popular diving areas because they contain great quantities of life.



Figure 5.1 The underwater food cycle.



Figure 5.2 A typical kelp bed.

Swimmers

One of the rewards of diving is seeing fish. Fish can be found in nearly all the waters of the world. You cannot outswim even the slowest fish, so do not chase them. If you want to observe fish closely, you must blend into the environment. Fish will get closer to you than you could ever get to them.

Collecting for aquariums requires specialized knowledge and procedures. Most fish have an internal air bladder for buoyancy control. If a fish is taken to the surface too quickly, the air bladder expands and kills the animal. Avoid handling fish because the experience can be traumatic as well as physically damaging to the animal. And the fish's spine could injure you.

Eating some types of fish can harm you, as some fish are poisonous. Types of fish poisoning include **ciguatera**, **scombroid**, and **tetrodotoxin**. Ciguatera results from eating fish that consume a certain species of algae. Ciguatera poisoning causes gastrointestinal problems within 6 to 12 hours. Scombroid poisoning, which produces nausea and vomiting within an hour, can result if you eat fish that have not been kept chilled. Tetrodotoxin, the most serious fish poisoning, results from eating exotic fish such as blowfish or puffer fish (figure 5.3). Tetrodotoxin poisoning can cause death within minutes. Avoid eating large and unusual-looking fish. Check with local fishermen to determine which fish are safe for consumption.

Many large mammals—sea lions, seals, dolphins, whales, and manatees—inhabit the water. They are graceful, beautiful, and sometimes awesome in

Figure 5.3 Eating improperly prepared puffer fish can result in potentially fatal poisoning.

appearance. Viewing them is an exciting experience. Some are curious and may approach you. Aquatic mammals will usually not harm you in the water if you leave them alone. But sea lions and seals are defensive on land and might bite if you get too close.

Bottom Dwellers

Bottom dwellers include animals that are stationary, such as coral and sea fans, as well as animals that move about, such as crabs and lobsters. Living, stationary bottom dwellers are usually not included in fish and game regulations, and you should not take them. Do not take coral, sea fans, and animals that appear stationary, such as starfish. If you hunt crabs and lobsters for food, you should know how to determine the gender of the animals, how to catch them without harming them, and how to measure them for minimum size. Do not take females, particularly those bearing eggs. Some divers take only one claw from a crab to conserve the species. A crab can feed and defend itself with one claw and can regenerate a new claw to replace the one taken.

Hydroids

If you dive in saltwater, you should know about hydroids, a category of animal that includes bottom dwellers, such as coral, and swimmers, such as jellyfish (see figure 5.4). Some hydroids, such as the beautiful sea anemone, have a round, columnlike body with a mouth surrounded by tentacles. This is a polyp form of hydroid. Another type, called the colonial form, can assume many different


Portuguese man-of-war
Left: Undischarged stinging cell, or nematocyst, of a coelenterate. Right: Discharged stinging cell. (Microscopic views)
Jellyfish
Sea wasp
Some hydroids, such as jellyfish and fire coral, have stinging cells that can inflict painful injuries.
The hairlike projections from fire coral cause painful stings.
Anemones and coral have stinging cells, but the cells are not harmful to people.

Figure 5.4 Several types of hydroids have stinging cells.

shapes. Colonies of hydroids can encrust a surface, and groups of colonies form jellyfish. Learn to recognize and avoid hydroids that can injure you.

Potentially Dangerous Aquatic Animals

Aquatic animals use a variety of mechanisms to obtain food and to defend themselves from attack. You can minimize your chances of injury by being familiar with the ways in which animals can inflict injury. Aquatic animals are rarely aggressive toward humans; they flee, hide, or stand still as you approach. If you do not touch, threaten, or provoke an animal, the animal is unlikely to injure you intentionally. But remember, aquatic animals are wild animals (figure 5.5). If you feed them, and they bite you in the process, you should not blame the animals. Table 5.1 lists types of injuries that you could sustain from aquatic animals and recommended first aid.

Animals That Cause Abrasions or Cuts

Many animals, such as some types of coral and barnacles, have sharp, hard structures that easily cut flesh. Such cuts can be painful, are slow to heal, and can get infected. Avoid contact with reefs and rocks covered with sharp animals. Some fish have knifelike protrusions on their gill plates or at the base of their tails. They defend themselves by flailing rapidly back and forth and slashing anything near them.

Animals That Puncture or Lacerate

Sea urchins are the porcupines of the seas. Cold-water urchins have short, thick spines, while warm-water urchins have spines that are long and thin. The spines of all urchins can penetrate an exposure suit if you bump into them. The spines break off in your flesh and produce a painful, red, swollen wound. The spines can be difficult to remove, so if you are unable to avoid a sea urchin injury, see a physician to have the spines removed.

Some fish have a row of long, sharp spines along their back. The scorpionfish has hollow dorsal spines that have venom-filled sacs at the base. If you are punctured by the spines and compress the venom sacs, you inject yourself with a toxin. The toxin of some species, such as the stonefish, can cause serious symp-

Figure 5.5 Potentially dangerous aquatic animals: (*a*) White tip shark; (*b*) cone snail; (*c*) sea snake; and (*d*) jellyfish with jacks.

Scott Frier: www.wildlifephotoworkshops.com



toms. Some fish, such as the lionfish (also called the turkey fish or zebra fish), have spines in other fins. The toxin of a lionfish produces serious symptoms in humans. Freshwater catfish also have venomous spines.

A shellfish called the cone shell uses venom to kill animals for food. The venom is highly toxic, and these animals can inject their venom into humans. Do not handle conical shells in tropical waters.

Rays are bottom dwellers that are round and flat. Some rays have a sharp, serrated barb at the base of the tail. The rays blend into the bottom. When someone disturbs a ray, it defends itself by arching its back and thrusting its barb into the attacker. A sheath, which often remains in the laceration wound, covers the barb and contains a toxin. Stingray wounds in the ankles of divers, waders, and swimmers are common in some areas. Avoid stingray wounds by shuffling your feet along the bottom as you walk. The torpedo ray, an animal found on the West Coast of the United States, can generate electricity. This ray can stun a diver, so you need to be able to recognize it. Avoid contact if you encounter one.

Animals That Bite

Use discretion to avoid being bitten by aquatic animals. One large freshwater fish that can bite is the gar. Turtles can inflict serious wounds. Muskrats may attack in defense, and moray eels in the ocean can deliver a serious bite. Alligators also have the potential to inflict an injury but have not been known to hurt divers.

Sharks can bite, but attacks on scuba divers are nearly nonexistent. Hollywood has exaggerated the danger of sharks; only a few species of sharks are aggressive, and it is rare to encounter these types in the waters visited by divers. Most divers would be delighted to see a shark because these animals usually retreat from an area frequented by scuba divers.

Retreat from snakes if you encounter them. Do not handle snakes; they can be extremely venomous. A sea snake's bite can produce a life-threatening emergency. Some freshwater snakes, such as the cottonmouth, are also venomous. The blue-ringed octopus, while only the size of a golf ball, is one of the most toxic creatures on earth. Don't allow curiosity to endanger your life.

Animals That Sting

Many aquatic animals can sting. Learn to identify and avoid contact with jellyfish, featherlike or whiplike hydroids, certain worms, and even some sponges.



Table 5.1 Potentially Dangerous Aquatic Animals

Injury	First aid
Abrasions or cuts	
Barnacle	Scrub and disinfect the wound.
Coral	
Punctures or Lacerations	
Cone shell	Soak the injured area in hot water. For a cone shell sting, apply a venous tourniquet and immobilize the injured area. It is advisable to seek medical attention for injuries caused by the spines of the scorpionfish family.
Sea urchin	
Venomous fish (e.g., scorpionfish, lionfish)	
Stingray	
Bites	
Barracuda	Stop the bleeding; clean and disinfect the wound. For a blue-ringed octopus bite, apply pressure to the wound and seek immediate medical attention—it may be necessary to administer rescue breathing. For a sea snake bite, apply pressure, immobilize the area, and get prompt medical attention.
Blue-ringed octopus	
Moray eel	
Sea snake	
Shark	
Turtle, muskrat, alligator	
Stings	
Bristle worm	Soak the injured area in vinegar.
Fire coral	
Fire sponge	
Jellyfish	

Seek medical attention as needed for any injury.

Hydroids have tiny stinging cells, called nematocysts, that they use to kill food. The sting of some animals, such as encrusting fire coral, is merely annoying; but the sting of others, such as the Portuguese man-of-war or the box jellyfish, can cause a medical emergency. A tropical marine worm, called a bristle worm, has tufted, silky bristles along the sides of its body. The bristles, which are fine and brittle, penetrate the skin easily, are difficult to remove, and cause a burning sensation. Do not touch or handle these worms. You should wear an exposure suit at all times while diving in the ocean. The suit provides protection from stings, but be careful when you remove it. The stinging cells of marine animals remain active even if they are not on the animal. Parts of jellyfish and other animals that are on your equipment can sting if they come into contact with your skin when you remove the equipment. Avoid contact with any unusual debris clinging to your equipment after diving in salt water because it could be part of a jellyfish. Some jellyfish come to the surface at night in tropical waters. Dangerous stinging animals are seasonal in some regions. Check with local divers to find out what to avoid and when to be on the alert.

Avoiding Danger

Many aquatic animals are potentially dangerous. Tropical waters have the most dangerous animals. Serious injuries to divers are not common because divers avoid animals that can hurt them. You should respect animals, but do not be overly concerned about them. Do not panic or flee just because you see a potentially dangerous animal; simply avoid contact with it. Learn to recognize the dangerous animals in an area, know where to look for them, be alert for them, and keep clear of them. Move slowly and look carefully. Shuffle your feet when wading. Don't touch anything unless you know it is safe to touch it. Neutral buoyancy—the ability to hover—is an excellent defense against aquatic injuries.

The biology of the underwater world is so interesting that many divers study it as a hobby. It is fun to learn about animals and plants and then observe them in their natural habitats. Some divers, fascinated with aquatic life, pursue biology as a career.

Conservation and Preservation

Life in the waters is beautiful and precious, but pollution from people jeopardizes life in the lakes and seas. Divers are physically ruining beautiful reefs. Unless we take action immediately, there is a real danger that many areas of the underwater world will become barren and lifeless. We must preserve and conserve the resources of our waters.

Because the waters are so vast, people often take them for granted. Lakes and seas seem too big to be harmed, but that is not the case. The underwater environment is fragile; the balance of nature can be upset more easily than many people realize. We think of the seas as being great and powerful because we see big waves and pounding surf. People who do not see beneath the surface may not realize the delicate nature of the animals that inhabit the waters. Some living things in the seas grow slowly, only a fraction of an inch (or centimeter) per year.

As a diver, you can help reduce damage to the underwater world. Every diver should take two actions: (1) Do everything possible personally to preserve the diving environment, and (2) do everything possible to educate others and help them learn to preserve the aquatic environment. You will get closer to the aquatic environment than most of your friends. You will see firsthand the effects of pollution, litter, and exploitation. You will also see the beauty and abundance that are possible when the environment is clean and unmolested. Your influence in society can make a difference. If you do not become part of the solution to problems in the aquatic environment, you are part of the problem.

Pollution

Stemming pollution is one of the greatest challenges facing the world. Humans are incredible polluters of the environment; we have polluted the air, the land, and the waters. People dump billions of gallons and pounds of waste into water every day. People seem to think that when something is out of sight, it is no longer a problem. This is not true of pollutants. Sewage, industrial waste, garbage, and sediment have killed and are continuing to kill many underwater environments.

If we stopped all pollution today, the aquatic environment would continue to suffer for decades from the waste materials that are already in the water.

Runoff from land that enters rivers and streams and flows into the ocean also causes pollution. Chemicals used in agriculture, on lawns, and in gardens cause death and destruction in the aquatic environment. Sediment from construction and drilling finds its way into water. The sediment blocks out life-giving sunlight and smothers bottom-dwelling creatures.

Lakes and oceans have been viewed as bottomless toilets for waste disposal. There are two problems with this narrow view: (1) Animals and plants live in the water and are killed by the pollution; (2) the water cannot be replaced because large bodies of water cannot be flushed.

Diver Impact

As a diver, you can harm the environment in several ways. You can remove living things from the environment, you can smash and kill living things while moving about underwater, and you can stir up clouds of silt on the bottom. The silt can choke and kill some organisms. Good intentions can also cause problems; handling and feeding animals can kill them.

You can be an effective predator underwater. Many animals are available for you to hunt and take. A few callous individuals kill things for sport, but responsible people take only what they will eat. Although the impact of divers is of little significance compared with commercial fishing, you should keep in mind that you do have an effect. If you spearfish on a reef, the fish in the area will soon be unapproachable by divers. If you want to be a predator, you must do so in a responsible manner. Conservation and preservation of aquatic resources are important topics that are discussed later in this section.

It is difficult to resist touching animals underwater, but you should refrain until you know what animals may be touched and how to touch them without harming them. Many animals are delicate; rough handling will kill them. Predators will eat animals that a diver removes from a protected area for viewing. Some animals, including fish, have a protective coating of mucus. If the coating is removed by handling, the animal can develop an infection and die. The stress of being handled by a gigantic, bubble-blowing monster may be more than some aquatic animals can take. Sea turtles may abort their eggs after being harassed by a playful diver. Do not be guilty of killing things for your amusement. After

SCUBA WISE

There are similarities between the environments above and below water. Temperature, weather, plants, and animals change when you travel from region to region on land. We enjoy the variety of mountain, plain, forest, and desert regions. Similarly, the world beneath the water varies from region to region. The enjoyment that the various underwater environments provide is a major reason why dive travel is so popular.

When you go to places on land that are rugged, remote, and hazardous, you need special training and equipment. There are dangers everywhere you go. Careful planning and preparation help minimize risks and are essential. A guide makes exploration safer and more enjoyable. When you go diving in places that are rugged, remote, and hazardous, the same requirements apply. Enjoy the wonderful differences beneath the waters—coral reefs, vertical walls, wrecks, and so forth—but always be properly prepared and equipped and always obtain an orientation to a new area.

you learn how, you can get extremely close to animals underwater. You can interact with them and enjoy them without handling them.

Feeding animals underwater was a popular activity until environmentalists showed that this is harmful (not to mention dangerous). Several potential problems are associated with feeding aquatic animals. Unnatural food given to animals can interfere with their digestion. The animals may become dependent on the food fed to them by divers and may not be able to forage if the food supply is discontinued. Food can make animals overcome their natural fear of divers. When an animal that would normally take cover at the sight of a diver becomes accustomed to divers providing food, the animal will readily approach a diver who is a hunter.

A diver underwater has the potential to be a bull in a china shop. Overweighted divers plow along the bottom with their fins pointed downward, stirring up great clouds of silt. Buoyancy difficulties cause divers to hold on to and crash into reefs and other living things. Divers who rest on the bottom crush plants and animals without realizing the damage. Divers who swim too close to a reef often kick animals to death.

Prevention of Diver Impact

One of the most important reasons for developing good buoyancy control skills is to prevent damage to the underwater environment. An environmentally responsible diver is properly weighted and in control of buoyancy at all times. Make your diving no-contact diving. You should be able to hover above a reef, move your mask within inches of an animal, and view it without touching anything but water and without stirring up silt. Learn to use your hands to scull into position while your fins remain still. Sculling is positioning achieved with short movements of the hands (not the arms). Buoyancy control and sculling are excellent skills for reducing diver impact. Figure 5.6 shows a diver sculling.

Another way to protect the environment is to keep your equipment secured close to you so that it does not dangle and drag. Equipment that drags along the bottom for an entire dive can do a lot of damage. Streamline your equipment. Moving slowly underwater conserves energy and air and makes you less likely to come into contact with animals. This helps you avoid injuring both yourself and animals.

If you must hold on to something underwater or push yourself away from something, you should look before you touch, and you should avoid touching anything that is living. If you must settle onto the bottom for some reason, select an area where there is no visible life. If you are weightless, keep in mind that one finger may be all you need to provide the leverage to move. Leave no evidence that you ever visited an underwater area.



Figure 5.6 Sculling helps minimize the diver's impact on the aquatic environment.

Conservation

Many animals that were once plentiful are nearly extinct because of a lack of conservation. Buffalo and passenger pigeons are good examples of this happening on land. In some areas, this is happening to aquatic animals. Bait fish that once swarmed in enormous schools in some areas no longer exist. With no food to eat, larger predatory fish no longer frequent the areas.

Fish and game regulations are designed to conserve natural resources. Rules regarding sizes, seasons, limits, and the means by which game may be taken have been established to help ensure an ongoing supply of a resource. Obey fish and game regulations, and encourage others to abide by them as well. In most areas you need a license to harvest fish and seafood. There are written regulations you need to be familiar with. Size, sex, limit, and season laws can impose a stiff fine if you fail to adhere to the regulations. Check with your local Department of Fish and Game. The rules can benefit everyone in the long run.

If you take living things from the water, do it in a responsible manner. Avoid taking animals from areas that are popular dive sites. Limit hunting and collecting to remote areas where the impact of divers is much less. Take only what you need, not what you can get or what you are allowed. The two types of hunters most harmful to the environment are the quantity hunter and the trophy hunter. The quantity hunter seeks to take as much and as many of everything as possible to build an image as a mighty hunter. The trophy hunter seeks the largest animals, which destroys the fittest of the breeding stock. If you kill an animal, you have a duty to know how large one must be to breed and what the maximum size of the animal is. You should take animals that have had the opportunity to reproduce, but do not take the largest ones. It is difficult at times to be selective, but you should attempt to conserve life.

Nature left undisturbed maintains a balance of life. Animals are both predator and prey. An animal eats another animal and is in turn eaten by others. If there are too many predators, their population diminishes because of an inadequate food supply. If there is a temporary overpopulation of prey, the number of predators increases. People upset nature's balance. We are the most reckless predators of all. We disturb the food cycle with pollution, hunting, fishing, boating, and every other way that we affect the aquatic environment. It takes nature longer to recover from our impact than from any natural disaster. People must lessen their effect on the environment to reduce interference with the natural management of the life within the waters.

Preservation

Preservation is everyone's business, but it is more your business now than it was before you became a diver. You probably know more than your friends and neighbors about the aquatic environment. You must be an ambassador for preservation. You must educate and motivate people to help preserve the diving environment.

What people do above water affects life beneath the surface. What people put down their drains and toilets winds up in the aquatic environment, as do the chemicals they use on their lawns and gardens. Litter in and around the water kills animals, birds, fish, and shellfish Think twice about the products you buy, how you use what you purchase, and how you dispose of your wastes. Where will the toxic chemicals and waste you use end up? Be environmentally conscientious; then teach others to be so, too. A simple act, such as the use of detergents without phosphates, can make a difference. Phosphates are powerful nutrients that upset the balance of nature when dumped into the aquatic environment.

Be involved in your community. Be concerned about issues such as sewage treatment, toxic wastes, and construction, which can be extremely harmful. Waste products from manufacturing are also harmful. Help others understand the seriousness of pollution.

Become more informed and keep informed. Join groups that are working to preserve the environment. Organizations such as the Ocean Conservancy, the Reef Environmental Education Foundation (REEF), and the Oceanic Society merit your membership. These groups provide up-to-date information and details on how you can help. Various organizations sponsor underwater cleanups from time to time; these are enjoyable and worthwhile. (For a list of environmental organizations you can join, see Appendix A.)

There are actions you can and should take when you go diving. Dispose of trash properly, and encourage others to do the same. If you have a boat for diving, anchor it away from reefs to avoid reef damage caused by the anchor and chain. Retrieve trash you find in the environment, especially plastic. Collect plastic, monofilament, lead, and stainless steel leaders. Not all trash is bad. Bottles and cans provide homes for animals. Report unlawful dumping and lost or discarded fishing nets and traps, which continue to catch and kill after abandonment.

Aquatic Conditions

The particular state of the environment and the physical situations in which divers find themselves are referred to as the aquatic conditions. The conditions of concern include the temperature, visibility, and the degree of movement of the water. You need to be familiar with aquatic conditions in general and local aquatic conditions specifically.

The Big Picture

Many factors affect the seas. The sun bears down on the earth at the equator more directly than on other parts of the earth. The climate and waters near the equator are warm; the greater the distance from the equator, the colder the water. The difference in water temperatures in different parts of the world causes the movement of air and water by convection currents. Winds move from areas of high pressure to areas of low pressure. Winds and the turning of the earth move water. On a global scale, water currents move in a clockwise direction in the northern hemisphere of the earth and in a counterclockwise direction in the southern hemisphere. Weather generally moves from west to east. The gravitational attraction between the earth and other planetary bodies produces changes in the water level called tides. Storms at sea produce energy in the form of waves that travel thousands of miles before giving up their energy in the form of surf.

Seasonal changes, winds, and storms affect inland bodies of water. Water from snow and rain in the mountains and hills flows into streams, rivers, and lakes. Water seeping into the ground resurfaces in quarries and springs.

Weather, seasons, geography, and other factors affect both surface and underwater diving conditions. The water can be rough at the surface but calm at depth. There may be a current at the surface but none on the bottom. The visibility may be good at the surface but poor on the bottom, or vice-versa. The temperature is usually warmer at the surface than it is at depth. You should become familiar with both surface and underwater conditions and their effect on your diving.

Perhaps the most important fact to remember about diving conditions is that they vary. Thus, an environmental orientation is important when you dive in a new region. The diving conditions usually dictate the way you dive. What works well in one area may be totally ineffective for another. An understanding of the effects of diving conditions in an area is important. You should know what conditions to expect, how the conditions affect your approach to diving, and how to manage the effects of the conditions. For example, in one area, it may be safe to wade into the water and put on your fins; however, in another area, you may need to put your fins on before you wade in.

General Freshwater Diving Conditions

Freshwater is 2.5 percent less dense than saltwater, so you are less buoyant in freshwater than in saltwater. The density of water varies with temperature. Freshwater is most dense at a temperature of 39.2 °F (4 °C)—the usual temperature and density of the water at depths greater than 60 feet (18 m) in freshwater lakes and quarries. The water becomes lighter when it is either warmer or cooler than this. Freshwater often forms layers: a layer of warmer, lighter water on top of a layer of colder, denser water. The change from the warm water to the colder water, called a **thermocline**, is abrupt. When the water is calm, the thermocline appears to have wisps of smoke on top of it when viewed from above. The refraction of light is different when the density of the water is different, so there is a slight visual blurring at the interface of a thermocline. When you dive in freshwater, you must insulate yourself for the water temperature below the thermocline. Although the surface of a lake may be warm and sunny, the water at the bottom may be close to freezing.

The best season for diving in a freshwater lake or quarry depends on the body of water. Spring and fall are often good times because the water temperature is the same from surface to bottom, there is oxygen for fish at all depths, populations of plankton are low, and visibility is usually good.

In later spring, the sun warms the surface water, and the lack of wind keeps the surface water from mixing with the colder water at depth. The water stratifies, and a thermocline forms that remains until fall. The layer of water below the thermocline stagnates in most lakes during the summer. Decaying matter depletes oxygen and creates toxins. Fish seek refuge above the thermocline. Sunlight and warm water often lead to plankton blooms, which are aggravated by pollution.

In the fall, the surface water in lakes and quarries cools until it equals the temperature of the water at depth. Colder water and reduced sunlight stifle plankton growth, and visibility improves. Winds cause water circulation. The movement of water from the top to a depth of about 60 feet, called an **overturn**, carries oxygenated water to the bottom and leads to what is called spring diving conditions. Visibility tends to be poor during an overturn.

In the winter, the surface water in a lake or quarry is colder than the water at the bottom. A **reverse thermocline** exists and remains until the temperature of the surface water warms to that of the water at the bottom. This allows the spring overturn to begin. Water becomes 10 percent lighter when it freezes. If ice sank when it froze, bodies of water could become solid ice from top to bottom.

Ice that forms over water insulates the water beneath it. Figure 5.7 shows the annual cycle of freshwater lakes and the concept of thermoclines.

When a strong wind blows along a shore for a sustained period over a body of water, the surface water is pushed away from shore. This water is replaced by colder water flowing up from the depths. This is called an **upwelling**, which can also occur in the ocean. If the wind conditions persist, the water temperature can become constant throughout the water column, even in the summer. An upwelling carries nutrients from the depths into shallow water and brings animals into the area. After an upwelling, a bloom can occur because of the increase in nutrients in warm, shallow water.

Specific Freshwater Diving Conditions

People can have good diving experiences in many kinds of freshwater environments. Springs, low-altitude lakes, and quarries are good sites for divers who do


Wind
Depth
Spring overturn
0
50
100
150
Depth in feet
Thermocline
30
40
50
60
70
Temperature °F
Wind
Depth
Stratified water: summer period
Wind
Depth
Fall overturn
0
50
100
150
Depth in feet
Reverse thermocline
30
40
50
60
70
Temperature °F
Ice
Wind
Ice
Depth
Stratified water: winter period

Figure 5.7 Thermocline, reverse thermocline, and the annual cycle of overturn in lakes.

not live near a coast. Other freshwater environments—such as rivers, caverns and caves, high-altitude and frozen lakes, and areas with submerged wreckage—can be dangerous. You should complete specialty training courses before diving in any hazardous area.

You may encounter strong currents in rivers (see figure 5.8). The currents are strongest at the surface and on the outside of bends. Countercurrents and swirling currents, called **eddies**, are common, and entanglements are likely in many rivers. Water flowing through a porous obstruction, such as a pile of logs, can pin a diver against the debris. Currents can undercut the bank of a river, so direct access to the surface can be impossible at times. Rivers are especially prone to seasonal changes and are often unpredictable.

Freshwater springs can provide beautiful diving environments. The flow of clean, calm water, which is usually at a moderate temperature (65 to 78 °F, or 18 to 26 °C), provides excellent visibility. The water often flows through underground limestone cave systems that extend for thousands of feet. Diving in open-water basins in a spring is appropriate for certified divers, but a diver should not enter any overhead area where a direct, vertical ascent to the surface is not possible. A large, roomlike opening where light from the surface can be seen is called a **cavern**. Areas that extend farther than a cavern where no surface light can be seen are called **caves** (see figure 5.9). Divers must complete specialty courses and must meet several requirements to dive in caverns and caves. Entering such an environment—even for a short distance—without the required training and equipment can be fatal. No amount of diving experience without cave diving training qualifies a diver to enter a cave. It is easy to



Figure 5.8 Because many rivers have strong currents and pose other unique diving challenges, specialty training is advised.

Berenika/iStock/Getty Images



Depth, distance, light, and tunnel-size restrictions for cavern diving

Figure 5.9 Dark blue areas are caves; light blue areas are caverns.

become disoriented, to stir up thick clouds of silt that instantly reduce visibility to nothing, and to panic and drown. You may dive in spring basins, but stay out of caverns and caves unless you meet the requirements to dive in them. Appendix A contains contact information for organizations that offer training in cavern and cave diving.

Sometimes the earth collapses into an underground cave system and forms a **sink**. The water flowing into the sink forms a basin. An opening called a **siphon** channels water from a sink back into the system. Diving in siphons can be dangerous. The amount of water moving through a system depends on the amount of rainfall in the area. Under extreme conditions, the normal flow of water can reverse.

People dig pits to excavate sand, gravel, and stone. At some depth, they encounter the water table, and the pit floods, forming a quarry or sand pit. At some of these sites, you can see submerged construction equipment that was abandoned when the pit flooded. Sand pits and quarries tend to have fair to good visibility, although the disturbance of silt that has settled to the bottom can ruin the visibility quickly. Gravel quarries usually have more silt than other types of quarries, so the water may be turbid.

Lakes can be excellent dive sites. There are freshwater lakes at altitudes above 10,000 feet (3,048 m). Diving at altitudes above 1,000 feet (305 m) is a specialty called altitude diving. This type of diving presents many hazards because the rate of pressure change is greater when you descend into water at an atmospheric pressure that is less than the pressure at sea level. You must follow special procedures to avoid decompression sickness. Problems can also result from the thinner air, which provides less oxygen with each breath taken above water.

When ice forms over water in the winter, diving becomes hazardous. Perils of ice diving include hypothermia, the freezing of regulator and buoyancy control valves, and getting lost beneath the ice. Ice diving can be beautiful and adventurous, but it is dangerous when attempted without the proper training, equipment, and procedures.

Potential hazards when diving in freshwater include body heat loss, submerged trees, wire, fishing line, hooks and lures, log jams, debris, currents, rapids, whirlpools, poor visibility, silt, and overhead restrictions. You can minimize these hazards with training, experience, equipment, correct diving techniques, area orientations, and good judgment.

General Saltwater Diving Conditions

The earth contains five oceans. Seas, gulfs, and bays are smaller sections of the oceans. The land beneath the oceans is not flat. The **continental shelf** is an underwater area that extends from land and slopes gradually to a depth of about 600 feet (183 m). Beyond the continental shelf are great underwater canyons and mountains, as well as hills, valleys, and great plains. In some areas, the tips of mountains and volcanoes extend above the surface of the ocean from great depths, forming islands. In other areas, deep canyons sever the continental slope, creating deep-water conditions close to shore.

The saltwater environment varies greatly from one part of the earth to another. The clear waters of the Caribbean, with temperatures that can exceed 85 °F (29 °C), feature coral reefs covered with beautiful, lush animals that look like plants. Schools of colorful tropical fish abound. Temperate waters, with temperatures ranging from 55 to 70 °F (13 to 21 °C), may have great forests of kelp, which contain more life per volume than a tropical rain forest. Cold ocean waters in northern latitudes are nutrient rich and teeming with life. Beautiful sights and wonders can be experienced in all the oceans of our planet.

Oceans are always in motion. Tides, winds, and currents cause water movement. An underwater earthquake can move water by creating gigantic seismic waves known as a **tsunami**. Although these giant waves are also called tidal waves, the tide has nothing to do with them. Tsunamis can cause great destruction, but they are rare and can be forecasted.

The energy source for movement of ocean water may be local or may originate thousands of miles away. You need to understand what causes water to move, how it moves, and how to dive in ocean water that is in motion.

Tides

The gravitational attraction between the sun, the moon and the earth pulls water toward these heavenly bodies. The resulting increase in water depth is a high tide. Water pulled away from the sides of the earth in the process produces a decrease in water depth called low tide. A high tide forms on the side of the earth opposite the moon because the attraction of the moon is least at that point and because of the centrifugal effect created by the rotation of the earth. At any given time, two areas on the earth are experiencing high tides and two areas are experiencing low tides. During a brief period of time called a **stand**, the tide neither rises nor falls; four tidal stands can occur per day—two high and two low. Geographical formations interfere with or enhance the rising and falling of the water in some areas.

The sun also affects the tides, but only about half as much as the moon because the moon is much closer to the earth. When the moon and the sun are aligned with the earth, which occurs twice monthly (during the new and full moons), tides are highest and are called **spring tides** (see figure 5.10). When the moon and sun are at right angles to each other in relation to the earth, tides are lowest and are called **neap tides**.



Figure 5.10 The effect of the sun and moon on tidal patterns.

The moon rotates around the earth in the same direction that the earth spins; therefore, the duration of a lunar day (moonrise to moonrise) is nearly 25 hours. This causes tides to occur at different times each day and explains why the heights of subsequent tides vary.

During a tidal change, water flows from one area to another. The water movements caused by the tides are called tidal currents, and they vary in velocity between tides. The flow of water into an area because of high tide is called a **flood**. The flow of water away from an area because of low tide is called an **ebb**. Between flood and ebb, a period of time occurs when the water has minimal movement. The term for this period is **slack water**. Because of geographical features of the earth, water cannot move instantly in many areas. There is usually a delay between the predicted time of a tide and the time when the water is slack.

Tidal changes affect diving activities and operations. Large differences in the water level between tides affect visibility and other conditions. Water height also affects entries and exits, shoal areas when boating, the mooring of boats, and the loading and unloading of vessels. Divers should know how high the tide will be. Tidal changes are small (less than 2 feet, or 0.6 m) in some areas or on some days, but they are large (more than 6 feet, or 1.8 m) in other areas or on other days. The greater the difference between high and low tide, the greater the effect of the tides.

Because the earth, moon, and sun follow set courses, the tides are predictable. Tides vary because the distance between planetary bodies and their positions relative to one another change constantly. Despite all the variables, scientists can predict with accuracy when the tides will occur and the heights of the tides. The U.S. government publishes tide tables, and national weather channels broadcast tidal information continuously. Local correction tables and current tables can provide more precise information. Tide tables refer to the height of the tide in relation to an average of the low tides in an area (see figure 5.11). Wind and barometric pressure affect the height of tides, aiding or opposing the movement of tidal waters.



November 2015

	Low tide				High tide			
	a.m.	ht.	p.m.	ht.	a.m.	ht.	p.m.	ht.
	Sunrise 6:19			-PST-	Sunset 5:08			
1 Su	1:35	1.0	2:35	0.5	7:49	6.4	8:46	4.7
2 M	2:06	1.3	3:17	0.9	8:21	6.7	9:36	4.4
3 Tu	2:38	1.7	4:06	1.0	8:56	8.8	10:35	4.0
4 W	3:14	2.1	5:02	0.9	9:33	6.7	11:44	3.7
5 Th	3:50	2.6	6:03	0.7	10:19	6.5	—	—
	Sunrise 6:24			-PST-	Sunset 5:03			
6 F	4:42	3.0	7:17	0.4	1:14	3.5	(11:15	6.0)
7 Sa	6:00	3.3	8:36	0.2	2:57	3.8	12:28	5.4
8 Su	8:23	3.3	9:43	0.1	4:15	4.0	2:03	
9 M	10:12	2.8	10:42	0.1	5:01	4.4	3:39	
10 Tu	11:22	2.1	11:27	0.3	5:37	4.9	4:55	
	Sunrise 6:28			-PST-	Sunset 5:00			
11 W	—	—	12:14	1.4	6:09	5.3	5:	
12 Th	12:06	0.6	12:59	0.8	6:34	5.6	6	
13 F	12:38	0.9	1:38	0.3	6:59	5.9		
14 Sa	1:07	1.3	2:13	0.1	7:24	8.1		
15 Su	1:31	1.6	2:45	0.3	7:47	6.2		
	Sunrise 6:33			-PST-	Sunset			
16 M	1:56	2.0	3:21	0.4	8:1			
17 Tu	2:21	2.2	3:53	0.3				
18 W	2:40	2.5	4:33	0.				
19 Th	3:03	2.7	5:1					
20 F	3:21	3.						

Figure 5.11 Tide table.

Generally, it is best to dive at high tide, but you may need to time your diving to coincide with slack water in areas with strong tidal currents. The timing may not be important in areas where tidal changes are small. Consider local knowledge about the effects of tides when planning your dives.

Waves and Surf

Ripples form when wind blows across water. You can see this in a puddle on a windy day. When ripples form on a large body of water and the wind continues to blow, the sides of the ripples form a surface against which the wind can push to set the water in motion. The longer and harder the wind blows in a constant direction, the larger the waves that form. As waves move away from the area in which they were created—an area called the **fetch**—the tops of the waves become rounded, undulating forms called **swells**. The water within a swell moves in a circular motion but has little forward motion. The effect is similar to the transmission of a waveform along a rope that is tossed up and down at one end. Waves of energy travel along the rope, but the rope itself does not move forward.

Swells are energy forms that can travel thousands of miles through water and still contain a great deal of energy. The top of a wave is called the **crest**. The bottom is called the **trough**. The distance from the crest to the trough is the **wave height**. The distance between waves is a **wavelength**. The time it takes two waves to pass a given point is a **wave period**. A long series of waves is a **wave train**. The greater the height of a wave and the greater the wavelength of a train of waves, the greater the energy contained in the waves. Two trains of waves can have phases during which the waves of each train reinforce one another and produce larger waves, called wave sets. The formation of larger and smaller waves can occur in phases. By timing the rhythm of the surf, you can make entries and exits easier by moving through the surf zone when the wave sets are small. Figure 5.12 illustrates fundamental concepts of waves and surf.

The water within a passing wave moves in a circular motion (this motion is called an orb). The diameter of the motion equals the height of the wave at the surface and diminishes with depth. Motion from a passing wave can be felt to a depth equal to half the wavelength for a series of waves. If there is 100 feet (30 m) between waves, you can feel the effect of a passing wave to a depth of 50 feet (15 m).

When waves enter shallow water, contact with the bottom interrupts the circular motion of the water within the waves. The circular movements flatten and eventually become a back-and-forth subsurface motion called **surge**. Wave contact with the bottom causes waves to slow and to become steeper. The wave height increases as the depth of the water decreases. When the depth of the water is about the same as the wave height, the wave becomes unstable and tumbles forward. At this point, the water within the wave moves forward and gives up its energy in breaking waves known as **surf**. In areas with offshore reefs, sand bars, and underwater obstructions, waves can break in shallow water, pass over the obstruction, reform, and break again in shallow water near the shore. Waves that break offshore indicate the presence of shallow water in the area where the waves are breaking.

Waves can break and release their energy all at once, or they can spill forward and expend their energy over a wide area. Waves that build quickly and break suddenly form plunging breakers. Waves that spill forward over some distance to shore are spilling breakers. Plunging breakers occur on steeply sloping shores,


Fetch
Wind
Ripple
Chop
Wind waves
Sea
Swell

Wind over water causes waves—undulating forms of energy that can travel thousands of miles.


Energy traveling in waves

Wave movement is a flow of energy similar to that caused by vertically shaking one end of a rope.


Wave terms
Wavelength
Crest
Wave height
Still water level
Trough
Orb
Depth
Surge limit
Wavelength



As a wave passes, water particles (represented by the circles) do not move with the wave; rather, they complete their orbit by returning to their starting point.



Wave sets resulting from two wave trains


Types of breakers
Spilling
Plunging


1
2
3
4
5
1. Surf zone
2. Breaker
3. Uprush
4. Backrush
5. Surge
Waves in shallow water

Figure 5.12 Wind speed, the absence or presence of obstacles, and the shape and depth of the ocean floor influence the formation of waves and surf.

while spilling breakers occur on bottoms with shallow slopes. Spilling breakers tend to reduce visibility more than plunging breakers.

The crashing water of surf contains air. The white water and foam in the surf zone do not provide as much buoyancy as water that does not contain air. It can be difficult to remain above water in the foam of surf, but you should not attempt to rise above the breakers because you can be picked up and tossed forward by the moving water. You should remain low in the wave and breathe from your scuba regulator.

Surf rushes up the face of a beach and then flows back again to the still water level. The return flow of water is called the backrush. This countercurrent, sometimes called an undertow, does not extend beyond a depth of three feet (about a meter). Although backrush can be strong when surf is large on a steep beach, the belief that an undertow can carry a swimmer out to sea is a misconception.

The surf's crashing onto the shore moves sand. Gentle summer waves carry sand onto the beach. Large, rough winter waves carry the sand offshore, where it forms sand bars. This action explains why some beaches are rocky in the winter and smooth in the summer.

Currents

Currents are to water what wind is to air—fluid in motion. Because water is 800 times denser than air, water poses much more resistance to movement than air. You need to know how and why water moves and how to move with it. The force of water in motion is too great to resist. You must learn to use the flow of water to your advantage.

Wind, gravity, tides, and convection cause currents; the most common currents are wind-generated surface currents. Because of the rotation of the earth, currents flow at an angle to the wind that generates them. When the wind pushes water away from an area, a compensating current replaces the water displaced. Overall, the effect on the earth is to produce large circulating currents, called **gyres**, that move clockwise in the northern hemisphere and counterclockwise in the southern hemisphere.

When wind blows along a coast, a vertical compensating current—an upwelling—occurs. Another vertical current, the opposite of an upwelling, is a **downwelling**. A strong downwelling current is rare, but it can occur under the right conditions where there is a steep drop-off near shore. It is frightening to be pulled downward in water. You should find out if and where a downwelling occurs in an area, and you should avoid that location. If you get caught in a downwelling, swim horizontally until you are clear of the current. Trying to swim up against the current can lead to exhaustion and panic.

Water flows in layers (see figure 5.13). The water at the surface moves quickly with the wind, whereas the water a few feet beneath the surface moves slower. The greater the depth, the less the effect of a surface current. After 12 hours of a sustained wind in a given direction, the speed of a surface current is approximately 2 percent of the wind that drives it. Because water flows in layers, it is possible for a surface current to flow in one direction and for a subsurface current to flow in the opposite direction only a few feet beneath the surface.



Figure 5.13 The laminar flow of water is similar to a stack of boards with rollers between them. When the stack is tipped, the top board moves much farther than the bottom board. Surface water moves more than water at depth.

Surface water at the equator expands as it is warmed and flows slowly toward the poles of the earth. At the same time, water cooled near the poles increases in density and sinks. Slow-moving convection currents result. These currents do not affect diving procedures, but they greatly affect the oceans by moving nutrients and pollution.

Water can move swiftly, and water movement intensifies whenever an amount of water passes through a restriction. When water moves past irregular formations, turbulence produces dangerous eddies and whirlpools. Swift-water diving is a specialty that is considered hazardous even with experience and training.

Incoming waves can pass over an underwater obstruction, such as a sand bar, and trap water on a shore. If the backrush of water flows back to sea through a narrow opening in the obstruction, a **rip current** exists. The current is narrow and strong and moves away from shore. The current dissipates shortly after passing through the restricted area. You can identify rips by a fan-shaped area of water on the shore, by muddy and foamy water in the rip area, and by a section of waves that breaks before the other waves (see figure 5.14). Rip currents can be stationary or moving. You must learn to recognize and avoid rip currents. If you are unable to swim toward shore, you are probably in a rip current. Swim parallel to the shore for about 60 feet (18 m) to get clear of the rip; then turn and proceed toward shore.

Waves breaking on a shore at a slight angle move water along the shore. The current is called a longshore current, and it affects diving. On steep beaches, the current can cut a shallow trough in the bottom close to shore. The trough, called a longshore trench, is a sudden drop-off and can cause an unsuspecting wading diver to fall. Items dropped into the surf zone move along the shoreline in the direction of the longshore current. The movement of sand on beaches occurs because of wave action combined with longshore currents.

Two types of currents result from all the forces of nature: standing currents, which are constant, and transitory currents, which occur briefly. The Gulf Stream that flows around Florida and up the eastern coast of the United States and the Antilles Current that flows through the Caribbean are examples of standing


Trapped water accumulates on shore and funnels offshore through narrow opening
Shore
Wave breaks over obstruction
Reef or sand bar
Wave
Dispersal area

Figure 5.14 A classic rip current.

currents. A longshore current is a transitory current. A rip current can be either type. You should be familiar with the currents you will encounter or may encounter in an area.

Currents can flow at a rate of hundreds of feet per minute. The speed of a current is its **drift**, and the direction assumed by a current is its **set**. A fully equipped diver can swim at a rate of 60 to 100 feet (18 to 30 m) per minute (0.6 to 1.0 knots). Attempting to fight even a mild current is a futile waste of energy. Strong water movement can dislodge equipment, cause regulators to free-flow, and cause rapid heat loss. You must learn to recognize and estimate currents. If the currents are strong, you must avoid them. Even if they are mild, you should avoid struggling against them. The primary rule for diving in currents—when you begin and end your dive at the same point—is to dive in a direction opposite the flow at the surface; then use the surface current to aid you when you return at the end of the dive. (See chapter 7 for techniques to estimate currents.)

You also need to know some other general rules for diving in currents. Water movement is minimal at the bottom. Whenever possible, descend along a line from the surface to the bottom. If the current is still strong when you reach the bottom, ascend on the line and abort the dive. When you are unsure of your location during a dive, it may help to surface, determine the direction to the exit point, redescend, and move along the bottom toward your destination.

When there is a surface current, you should minimize the time spent at the surface. Whenever possible, hold on to a fixed object at the surface to keep from drifting downcurrent at a dive site. When a surface current is mild, swim against it to maintain your position at the surface. Develop the habit of noting your surface position in relation to a fixed reference. If you are caught in a sudden, strong current, swim across it to escape from it.

A dive in which the diver moves with the flow of a current is a **drift dive**. Simple drift dives along a coast are acceptable when planned. You enter the water at one point, move along the shore with the current, and exit at another point downstream. Another type of drift diving, which is a specialty activity, involves diving in currents from a boat. This type of diving is hazardous because the boat must be operated while divers are in the water. Do not attempt drift diving from boats unless you have completed specialty training and have a trained, experienced captain for the vessel.

Potential saltwater diving hazards include body heat loss, currents, surf, marine life, poor visibility, and fishing nets and equipment. You can minimize the hazards of ocean diving by following the recommendations that were described in this section.

Boat Diving

All divers eventually dive from boats, either small private boats or large charter vessels. Space is limited aboard boats, so you should organize your equipment compactly and pack it in the order in which you will need it. You may need to carry equipment for some distance to a boat, so plan to wear your scuba tank and weight belt and carry a bag in each hand. One bag should contain your dive gear, and the other bag should hold your lunch, camera, and any items that you want to keep dry.

Charter Boat Diving

You need to be well rested, so you should avoid partying the night before boat diving. Eat a meal that is free of acid and fat before you depart. Arrive at least 30 minutes before the scheduled departure time. Check in with a crew member. Usually, you must sign a roster and complete some forms. Ask where to stow your gear, and pick out a suitable space to store your dry items. If you are prone to seasickness, take preventive medication before the boat gets underway.

Tour the vessel. Locate the head (bathroom) and the emergency equipment. Stay out of the engine room and the wheelhouse (see example in figure 5.15). If you did not come with a buddy, you should find one before reaching the dive site. Listen carefully to the orientation provided by the captain or crewmember.

If you begin to feel queasy after the boat gets underway, you should go outside to the center of the boat and concentrate on the horizon. Sleep may help you acclimate to the boat's motion. If you are nauseated or vomiting when it is time to dive, avoid scuba diving. Vomiting underwater is hazardous. Mildly seasick divers may recover by snorkeling or by swimming to a nearby shore and waiting until they feel better.

Diving operations begin only when indicated by the captain. When you are ready to enter the water, check out with the divemaster. Typically, you will enter the water by stepping off the side of the boat, and you will exit the water by boarding a swim step at the stern (rear) of the vessel. Using the anchor line for your descent is a good practice.

Begin your dive against any current so that the water movement can assist you back to the boat at the end of the dive. Crew members often deploy a **trail line**—a long line with a float attached—to the stern for you to use in pulling yourself to the boat against the current (see figure 5.16). You should dive upcurrent; however, if you end up downcurrent from the boat and are unable to reach the trail line, you should make yourself buoyant, signal the boat, remain calm, and wait to be picked up after all the other divers have boarded the vessel.

If you hear a yelping, sirenlike sound while underwater, you should surface. The sound is from an electronic diver recall system. Remain where you are, and



Figure 5.15 Typical charter boat configuration.



Figure 5.16 Divers can use a trail line to pull themselves to the boat if they surface downcurrent.

look to the boat for instructions. Learn the vessel's recall procedures in advance.

At the end of the dive, return to the boat by swimming along the bottom or at the surface. You should avoid skimming (swimming just beneath the surface), because you cannot be seen and you could be struck by a passing boat. Also avoid crowding the exit area. Divers should exit one or two at a time and remain clear of divers climbing the boarding ladder. Retain your equipment until immediately before exiting the water. If you do not know what equipment to remove, ask for instructions. Immediately after exiting, pick up any equipment that you handed to someone during your exit, and clear the exit area to make room for others.

After your last dive, pack your equipment before the boat gets underway. Be available for a visual roll call, which is required. Watch and learn from experienced divers.

Charter boat dives provide memorable diving experiences. Learn the proper techniques for diving from charter boats and then do what you have learned.

Small-Boat Diving

When you plan to dive from a small boat, make sure the boat is equipped for safety and has all the equipment required by the Coast Guard. The boat should also have a first aid kit. Leave a float plan—information about where you are going and when you plan to return—with someone who can summon assistance if you are delayed. Have a radio or cell phone aboard for emergency communications. Check the weather and water conditions in advance, and reschedule the dive if conditions will be unfavorable or are marginal on the planned dive day. Diving is not good when the weather is bad.

Small boats pitch, roll, and pound, so stow your equipment securely and expect it to get wet. If the trip to the dive site is short, you should suit up on shore. Doing so is easier and safer. If you must suit up in a small boat, remain seated and help one another. Before you enter the water, make sure that there is a means to get back into the boat. More than one diver has been stranded alongside a boat, unable to exit the water. Display the dive flag, but only while diving. Deploy a trail line and float.

The usual entry from a small boat is a seated back roll made by two divers at the same time. This method enables the divers to avoid rocking the boat and causing one diver to lose balance and fall in when unprepared. The descent should be down the anchor line to ensure that the anchor is set and clear. If possible, you should leave an operator in the boat. A sudden weather change, a slipping anchor, or a change of water movement could pose serious problems at the end of a dive if the boat is unattended.

At the end of the dive, remove your weights and scuba unit before exiting. If you cannot hand them to someone in the boat, clip them to gear lines that have been hung over the side. Exit the water and pull in your equipment.

Boat diving is good diving. Be prepared, conserve space, plan ahead, learn the rules, and follow those rules. Learn more about boating to make boat diving more enjoyable. Complete a course in seamanship and small-boat handling.

Summary

The aquatic environment is vast and wonderful. We depend on it for our existence. We need to learn about it, care for it, and respect it. We must protect the environment and encourage everyone we know to assist in that effort. Because the environment varies greatly from place to place, you need an area orientation before diving. There are hazards in the underwater world, just as there are hazards on land. You can minimize aquatic hazards with training, experience, planning, proper procedures, and common sense.

Application-of-Knowledge (AOK) Questions

This chapter provides knowledge but does not explain how to apply it. In the remaining chapters you will learn the skills for diving in various environments. Right now you need to digest what you know about the diving environment and consider how it might affect your diving.

1. In what ways will the temperature of the water affect your diving?
2. In what ways will the visibility under water be affected by the environment and by you?
3. What ways can you recall that can help you manage currents while diving?
4. When you encounter strange animals while diving, how should you respond?
5. How much training and experience are required until you are able to dive anywhere at any time?
6. When you are an experienced scuba diver, where is the safest and most comfortable place to be when diving?
7. If you were equipped for diving in the ocean and wanted to dive in fresh water, what equipment changes would you need to make?
8. What do you think you need to know about diving conditions when you intend to go diving?

Beautiful coral reefs in the Red Sea



6

Diving Skills

Dive In and Discover

By the end of this chapter, you will be able to do the following:

- Prepare, assemble, don, adjust, inspect, and disassemble your equipment for skin and scuba diving.
- Demonstrate 16 skin and scuba diving hand signals.
- Explain how to test and control buoyancy.
- Explain how to clear water from a mask, a snorkel, and a scuba regulator.
- Explain how to descend, swim with fins, and ascend when skin and scuba diving.
- Explain how to handle, remove, and replace skin and scuba diving equipment.
- Describe various entry and exit techniques for skin and scuba diving.
- Explain how to use dive flags.
- Explain the buddy system and lost buddy procedures.
- Explain how to use a compass for underwater navigation.
- Explain how to prevent and manage seasickness, dizziness, stress and panic, overexertion, coughing, cramps, entanglement, loss of buoyancy control, loss of air supply, and dive emergencies.
- Explain how to rescue a diver who is not breathing and the first aid procedures for an injured scuba diver.
- Define the terms *buddy system*, *flutter kick*, *scissors kick*, *modified frog kick*, *dolphin kick*, *surf*, *neutral buoyancy*, *diver's push-ups*, *open-valve ascent*, *reference descent*, *nonreference descent*, *buddy line*, *compass heading*, *compass course*, *reciprocal compass course*, *flaring*, and *buddy breathing*.

You will learn most of the diving skills in controlled conditions; when you have developed the basic skills, you will apply them in open water. (Open water is any body of water representative of dive sites in the local area.) When you can demonstrate the skills of diving in open water, you are ready to receive your diving certification.

Preparing to Skin Dive

This section covers the skills of skin diving, many of which apply to scuba diving. When you swim at the surface and breathe through a snorkel, you are snorkeling. Scuba divers snorkel to conserve the air in their cylinder for underwater activities. When you breathe through a snorkel at the surface, hold your breath, and dive beneath the surface, you are skin diving. As a diver, you need to master the skills of snorkeling, skin diving, and scuba diving in order to enjoy all that the underwater world has to offer.

Preparing Equipment

Be ready to start your lesson when you come to your first water session. Prepare your mask, snorkel, and fins in advance. Clean your mask lens thoroughly so it will not fog (a description of the cleaning procedure is provided in chapter 4). Adjust the mask strap so it is snug but not tight. Attach the snorkel to the mask strap on the left side, and adjust the snorkel so it is comfortable in your mouth. If your fins have heel straps, adjust them so they are snug but not tight. Complete all adjustments before your first water session.

Inspect your skin diving vest or buoyancy compensator by inflating it, making sure it does not leak, and then deflating it. Put it on, reinflate it, and adjust the strap or straps so it will stay in position in the water. You may need to use a strap that runs between your legs and attaches to the front and back of the flotation device to keep it from riding up when you are in the water.

If you wear an exposure suit, your instructor will suggest an initial amount of weight for your weight belt. Adjust the length of the belt at the buckle end so the excess strap at the opposite end does not exceed 6 inches (15 cm). Allow 2 inches (5 cm) for each two-slot weight that you thread onto the belt. Distribute the weight on both sides of the belt so that you will be balanced in the water. Lock the weights in place with weight retainers.

Mark your personal equipment with your initials so that you can identify it. You can use special paint or markers (available at dive stores) or colored tape. Pack

Diving requires many skills, and you must repeat these skills correctly until you can execute them automatically. When you have mastered the skills of diving, your enjoyment can begin because you will be able to devote more attention to things of interest. The basic skills of skin diving and scuba diving are introduced in this chapter.

Anemones and clownfish in the Red Sea

your equipment—with the exception of your weight belt—in a gear bag. Place the items you will don last, such as your fins, on the bottom. Place the items you will don first, such as your exposure suit, on the top.

Donning and Inspecting Skin Diving Equipment

Don the pants or legs of your exposure suit first, then your boots, and then the top part of your suit. Donning a snug-fitting wet suit is easier if you wet the inside of your suit with water (to which you have added some mild shampoo) or if you wear a spandex suit as an undergarment. Place the ends of the legs of your wet suit over the tops of your boots so that water can drain from your suit when you exit from a dive. If the boots are outside the legs of your wet suit, water from the suit will balloon your boots when you get out of the water. If you become warm while donning the exposure suit, cool yourself before proceeding with your preparations. For open-water diving, don a cold-water hood before donning your wet suit jacket so that the skirt of the hood is underneath your jacket.

After you put on your exposure suit, you should clean and defog your dive mask and then set it aside until you are ready to don it (see the description of the cleaning procedure in chapter 4). Leave about 1/2 inch (1.27 cm) of water inside the mask so it will not dry before you put it on, and place the mask where it will not get damaged.

Don your skin diving vest or BC next. Place the skin diving vest over your head, and then secure the straps. Inflate the vest fully to make sure it will not be too tight. The straps should be as snug as possible without being uncomfortable or interfering with breathing.

Don your weight belt after the skin diving vest so the belt will be clear of the vest straps. Grasp the free end of the weight belt (the end without the buckle) in your right hand, and grasp the buckle end in your left hand. Pick up the belt, step through it, pull it into position across your back, and bend forward so that gravity supports the weight of the belt. Then tighten the belt and secure the quick release. Always wear the weight belt with a right-hand release, even if you are left-handed, so that a rescuer will know how to release your belt in an emergency. If you always hold the free end of the belt in your right hand when donning it, you will always have a right-hand quick release.

Don the remainder of your skin diving equipment—mask, snorkel, and fins—at the water's edge or, if it is calm, in the water. Place the mask on your forehead and pull the mask strap over the back of your head using both hands to position the strap. Position the mask on your face, clearing any hair from beneath the sealing edge of the mask. Reposition the mask strap so it lies flat. If the mask has a split strap, position the split above and below the crown of your head. Don your snorkel when you don your mask. Check the adjustment of the snorkel when your mask is in place.

Stabilize yourself when putting on fins so that you don't lose your balance and fall. Hold on to your buddy (see "The Buddy Diving" section later in this chapter) or an object for support, or sit at the water's edge. Hold one side of a fin, bend one leg into a figure-four position, push the fin onto your foot, and pull the strap or heel pocket into place (see figure 6.1). Repeat the process for the other fin. Avoid walking with fins. If you must walk a few steps while wearing fins, shuffle your feet and walk backward. If you try to walk forward, you can lose your balance or damage your fins.

After you have donned your equipment, you should inspect it for completeness, correct positioning, and adjustment. When you are satisfied with your



Figure 6.1 Donning fins.

equipment, inspect your buddy's equipment while he inspects yours. Inspect from head to toe. You may be able to see something that your buddy could not see, or vice versa. Develop the habit of inspecting each other's equipment before every dive.

Skin Diving Skills

Diving skills can be divided into three categories: skin diving skills, scuba diving skills, and problem management skills. This section introduces skin diving skills.

Using Skin Diving Hand Signals

You cannot talk with a snorkel in your mouth and your face in the water, so you must use hand signals as a primary means of communication. You need to learn and use the standard hand signals shown in figure 6.2. You will learn additional hand signals for scuba diving. Display hand signals clearly and deliberately when you send them, and acknowledge all hand signals you receive.

Figure 6.2 Skin diving hand signals.



1. Descend 2. Ascend 3. Stop



4*a*. OK 4*b*. OK 4*c*. OK



5. Something's not right 6. Emergency

Using a Skin Diving Vest

You inflated and deflated your skin diving vest as part of your diving preparations. You also need to learn how to deflate and inflate the vest in the water. To deflate the vest, position your body so the vest's exhaust port is the highest point. Hold the deflation valve open while you sink lower in the water. The water pressure helps force the air from the vest. You may have to hold the collar of the vest down with one hand to remove the air from that area. When you have vented all of the air from the vest, close the valve to prevent water from entering. Get your buddy to confirm that all the air is out of your vest.

Inflating the vest in the water is easier with your head underwater instead of above water. Take a breath of air, duck your face beneath the surface, insert the oral inflator into your mouth, open the valve, exhale into the vest, and close the valve. Repeat this process until you have the desired buoyancy.

Testing Buoyancy

Your buoyancy should be neutral at the surface. If you are too buoyant, you will have to struggle to descend and remain underwater. If you are not buoyant enough, you will tire quickly at the surface and sink while swimming underwater. You must be able to adjust your buoyancy correctly.

If you are wearing an exposure suit, you need weights to offset the buoyancy of the suit. With all equipment in place, position yourself in chest-deep water. Exhaust all air from your skin diving vest. Take a full breath, hold it, lift your feet from the bottom, and remain motionless while you slowly count to 10. If you sink, remove some weight and try again. If you exhale half of the air in your fully inflated lungs and still can't submerge, you need to add weight until you can. When your weighting is correct, you remain at the surface while holding a full breath and sink when exhaling. Adjust your weighting until you achieve neutral buoyancy, which means that you neither sink nor float when holding an average breath. Have your buddy watch while you make the final test. With your lungs about half full of air, the top of your head should remain even with the surface of the water when you are motionless in a vertical position.

Clearing the Mask

When your head is above the surface, water inside a mask will run out if you pull the bottom of the mask away from your face. Water inside a mask underwater also flows out the bottom of the mask if you displace the water with air. Putting air inside the mask is easy: Just exhale lightly through your nose. A long, light exhalation is better than a short, forceful one because a strong exhalation blows air past the seal of the mask and does not displace water effectively.

To clear a mask that has a purge valve, seal the mask against your face, tilt your head downward to make the purge the lowest point in the mask, and exhale through your nose until the mask is clear of water. To clear a mask without a purge, hold the top of the mask against your forehead, take a breath, and start exhaling slowly (see figure 6.3). When the level of the water is below your eyes, tilt your head back while continuing to exhale, and the remainder of the water will flow out the bottom of the mask. You must be exhaling when you tilt your head back or water will run up your nose. Bubbles from the bottom of the mask indicate when you have cleared all the water from your mask. It may



Figure 6.3 Clearing a mask.

sound as though it takes a long time and a lot of air to clear a mask, but with practice you will be able to flood and clear your mask several times after a single inhalation. Clearing requires only a few seconds.

Using the Snorkel

Stand in the water and lean forward with the snorkel in your mouth. Place your face in the water and inhale gently. If you inhale forcefully at first, you might inhale water. When you are sure the tube is clear, you may breathe more forcefully through your snorkel. When you descend beneath the surface, the snorkel tube can fill with water. Self-draining snorkels drain nearly all the water from the tube when you surface.

If your snorkel is not the self-draining or water exclusion type, you have to blast the water from the tube with a strong, sharp exhalation. To do this, blow hard into the snorkel to force the water out. Inhale cautiously after exhaling. If a little water remains in the tube, you can breathe past it if you inhale gently. After you fill your lungs again, expel the remaining water with another forceful exhalation.

If you have a simple snorkel without valves, you can clear the tube while ascending by using the displacement method. Begin by looking up to invert the snorkel; then exhale a small amount of air into the tube. As you ascend, the air expands according to Boyle's law and displaces the water in the tube, which will be clear of water when you reach the surface. The tube is inverted at this point, however, so when you turn it to the upright position, water will flow into the tube unless you exhale while rolling your head forward at the surface. Continuous exhalation prevents water from entering the tube. When you use the displacement method, which is easier than the blast method, you can take a breath the moment you reach the surface. Figure 6.4 shows the displacement method.



Figure 6.4 Displacement method of clearing a snorkel.

Learn to keep the snorkel in your mouth when you are in the water. Avoid the temptation to remove the mouthpiece and shake the water from your snorkel. You do not have to remove the mouthpiece when you can clear your snorkel proficiently. When your hands are occupied, you will not be able to remove and replace the snorkel to clear it.

Using Fins

Fins provide large surfaces that you can push—using the strong muscles of your legs—against the water for propulsion. The blades of the fins need to push the water the way a broom sweeps a floor. A broom cannot sweep if you move it up and down, and your fins will not provide propulsion if you move them lengthwise in the water. You must kick them back and forth in wide, sweeping kicks. Small fins allow short, quick kicks, but larger fins require wider, slower kicks. Moving efficiently, not speedily, is your objective when wearing fins.

The most common fin kick is the **flutter kick**, which is an up-and-down kick that you can do facing down, up, or to the side. Your fins need to be underwater to provide propulsion. It is easier to keep your fins submerged at the surface when you are on your back or on your side instead of your belly. Move your legs up and down from the hip while bending your knees only slightly. Extend your legs almost fully throughout each stroke, and use wide, slow kicks. Keep your hands at your sides or extend them in front. Do not use your hands and arms to swim. Figure 6.5 shows the flutter kick.

The **scissors kick**, shown in figure 6.6, is a resting kick. The scissors kick is similar to a flutter kick, but it requires less energy. While lying on your side, slowly extend one leg backward while you extend the other leg forward, and then pull your legs together quickly. Hold a streamlined position with your toes pointed while you glide through the water. When you come to a stop, repeat the stroke. Extend your legs almost fully throughout the stroke.

A **modified frog kick** is useful because it uses different muscles than the flutter and scissors kicks. Changing kicks is helpful if you become tired or develop leg cramps. The modified frog kick is different from a swimmer's frog kick. Assume a facedown position with your fins perpendicular to the bottom. Rotate your ankles so that the tips of the fins point outward, slide the fins tip first in an outward direction, then pull the bottoms of the fins together quickly in a wide, sweeping arc. Extend your legs almost fully throughout the stroke, and then hold the final position with your feet together and your toes pointed while you glide (see figure 6.7). When you come to a stop, repeat the stroke.



Figure 6.5 Flutter kick.



Figure 6.6 Scissors kick.

The **dolphin kick** is also useful for a change of pace or if you lose a fin. Hold both feet together continuously. Exert force against the water with a wavelike up-and-down motion of your body. To begin, straighten your body, extend your feet together, bend your shoulders forward, and pull your feet slightly backward. Next, lift your shoulders, thrust forward forcefully with your hips, and then pull down with your fins. When you see this kick demonstrated, you will be able to learn it by imitation. If you lose a fin, you can use the dolphin kick to propel yourself. Cross your legs and put the leg without a fin behind the one that has a fin. Figure 6.8 shows the dolphin kick.

Performing Surface Dives

You need to be able to dive down to see the beautiful world beneath the surface. The initial dive beneath the surface of the water is a surface dive. The principle of a surface dive is simple: You raise part of your body above the water and point yourself straight down; the part of your weight above the water drives you downward. Once you are submerged, you start swimming to continue your descent.

You should learn three types of surface dives: the pike, the tuck, and the feet-first dive (see figure 6.9). You do the pike dive while moving forward at the surface. Bend forward at the waist to make your trunk vertical in the water. Next, quickly lift your legs out of the water to a vertical position. The more of your legs you can lift out of the water, the farther your surface dive will push you under the water. For shallow dives, you can do the pike dive by lifting only one leg.

When you have learned the pike dive, you are ready for the tuck dive, which is similar. Do the tuck dive from a stationary position. Begin in an upright position in the water, pull your knees to your chest, and sweep backward with your arms to roll yourself forward in the water. When you are inverted, extend yourself fully into a vertical position. The procedure is a coordinated movement that you must do quickly to get your legs above water. After you extend your legs, the remainder of the dive is the same as the pike dive.

Use a feet-first dive in areas where surface plant growth is dense because you are less likely to get entangled. Begin in a stationary, upright position, and use a strong scissors kick to propel yourself up and out of the water as far as possible. Pull your arms downward to your sides for added lift. When you reach the highest point, point your toes downward, and hold your arms to your sides. The weight of your body will push you below the surface. Raise your arms upward when you are below the surface to push yourself even lower. When your downward momentum ends, do a tuck dive to invert yourself, then continue your descent.



Figure 6.7 Modified frog kick.



Figure 6.8 Dolphin kick.



Figure 6.9 Surface dives.

Performing Descents, Underwater Swimming, and Ascents

To prepare to descend, vent all air from your flotation device. Use an ear-clearing maneuver (described in chapter 3) at the surface so that it will be easy to equalize pressure in your ears while you descend. Hyperventilate three times, inhale as fully as possible, and don't exhale until you return to the surface.

Initiate your descent with a good surface dive. Equalize the pressure in your ears and mask every couple of feet during your descent. Use wide, slow, powerful kicks to propel yourself to your desired depth, and then relax as much as possible.

Swimming underwater sounds simple, but some people have trouble controlling direction. Your head is your rudder. Pull your head backward while swimming facedown to go up. Bend your head forward to go down. Bend your trunk to the left or right to turn. With practice, you can go in any direction you choose without using your hands.

Follow these four rules for ascents:

1. Reach up; extend one arm over your head for protection (see figure 6.10).
2. Look up to avoid obstructions and to determine when the surface is near.
3. Come up slowly. A slow ascent is better than a rapid ascent because swimming rapidly uses more oxygen.
4. Revolve once or twice during your ascent to check your surroundings.

Alternate breath-hold dives with your buddy. One diver should remain at the surface, watching, while the other diver is underwater. Make sure your buddy knows where you are at all times.



Figure 6.10 Extend your arm for protection during a skin diving ascent.

Handling Equipment

Occasionally you may need to remove, adjust, and replace skin diving equipment while you are in the water. You should be able to handle your equipment easily with training and practice.

To remove, adjust, and replace your mask, begin by inflating your skin diving vest. Because you will make the adjustment above water, you should use buoyancy to reduce the effort. After you make the adjustment, replace your mask using the procedure for donning the mask described earlier in this chapter.

You may need to adjust a fin strap or remove sand or gravel from your fins while diving. The fins are easier to remove, adjust, and replace than the mask is. You do not need as much buoyancy to work with your fins because you can look into the water and make the adjustment underwater. In fact, too much air in your skin diving vest can be a nuisance. Keep your face in the water, breathe through your snorkel, and work with one fin at a time.

You may need to tighten, adjust, or replace your weight belt. The weights may slip, or the belt may fall off. To tighten or replace your weight belt, you need to get the belt across the small of your back while you are in a facedown position breathing through your snorkel. If you try to replace or tighten the belt in an upright position, you will have a constant fight with gravity. When you are in the correct, facedown position, gravity becomes your ally while you secure the buckle. To get the belt into position across your back, begin in an upright position, holding the free end of the weight belt against the outside of your right thigh. Lean back into a horizontal, faceup position momentarily, and then roll to your left to a facedown position while continuing to hold the free end of the belt against your right thigh. At this point, the belt will be draped across the backs of your thighs. Clear your snorkel so that you can breathe. While holding the free end of the belt in your right hand, reach down with your left hand, grab the buckle end, pull the belt into position across your back, and secure the buckle.

Removing Equipment

Your equipment helps you adapt to the underwater environment. Develop the habit of keeping your equipment in place while you are in the water. You may need to defog your mask or make an adjustment, but other than that you should wear your equipment continuously. Avoid the tendency to prop your mask on your forehead when you are at the surface. Mask propping is a sign of distress and a good way to lose your mask and snorkel. If you must remove your mask while in the water, pull it down around your neck where it will be secure.

Bottom conditions at the dive site determine whether you should remove your fins when leaving the water. In some areas, you can remove your fins in waist-deep water and wade out of the water. In other areas, you need to wear your fins until you are clear of the water. Fins can be removed in several ways. When you prepare to climb a boat ladder, hold the ladder continuously while crossing your legs in a figure-four position to remove each fin. If the boat has a platform at the rear, swim onto the swim step and remove your fins in a kneeling position. When you remove fins in waist-deep water or on land, you should use your buddy for support. On steep beaches, you may choose to crawl from the water. Your buddy can remove your fins while you are on your hands and knees. Your buddy then crawls ahead of you, and you remove your buddy's fins. When you stand up, you exchange fins.

Weight belt removal also varies. When you can walk or climb out of the water, keep your belt on while doing so. When you remove a weight belt, lower it gently instead of dropping it. You can cause damage or injury if you develop the habit of dropping your weight belt. If you must pull yourself onto a dock or into a small boat, remove your belt first and hand it up.

Keep your skin diving vest in place until you are clear of the water. Remove your skin diving vest, and then your wet suit. Remove your wet suit by turning it inside out. Be sure to remove your boots before your wet suit pants. You will need assistance from your buddy to remove a pullover jacket or a jumpsuit.

Preparing to Scuba Dive

Nearly all of the skills of skin diving are used in scuba diving, but you need to learn many additional skills for scuba diving. This section introduces the preparatory skills of scuba diving; the next section covers basic and postdive skills. The more familiar you become with the skills by studying them, the better you will be able to perform them. You must learn the skills correctly from the outset in order to develop good habits for diving safety.

Packing Equipment

Nothing is more inconvenient than getting ready to dive and discovering that something is missing or not right. You should take steps to prevent equipment inconveniences. Begin by using a checklist when you pack your diving equipment to ensure that you have everything you need (see the diving equipment checklist). After taking inventory, inspect your equipment as you pack it. If you have not used your equipment for a while, assemble it and test it first. Make sure everything works properly.

Pack your equipment in your gear bag—except for your weight belt, tank, and BC. When you have to carry your equipment, put your BC on your tank, and carry the tank on your back. Carry your gear bag in one hand, and carry your weight belt in the other hand. Equipment-carrying devices with roller wheels can reduce the work of moving your diving equipment (see figure 6.11).

Figure 6.11 A gear bag with wheels can make transporting equipment easier.

Assembling Equipment

Today's backpacks are part of the BC and have one or more bands to secure the scuba cylinder. Many of the bands are made of webbing, which stretches when wet. Soak a fabric tank band in water for a couple of minutes before securing it around a scuba tank. The soaking softens the webbing and allows it to stretch when you tighten the band. A dry fabric belt may allow the tank to slip when the band gets wet and stretches. A tank that slips from a pack can be a hazard.

Orient your backpack with the opening of the tank valve facing the backpack. Stand the tank up with the valve handle facing to your right. Slide the tank band over the tank with the tank between you and the pack. Tighten the band so the valve opening points directly toward the pack (see figure 6.12).



Figure 6.12 Strapping the backpack to the tank.

The height of the tank band on the tank varies with the type of backpack. Generally, the top of the pack is even with the base of the tank valve. After you attach the pack and before you attach the regulator, don the scuba tank and check the height adjustment by slowly tilting your head backward. If your head hits the tank valve, the tank is too high in the pack. Reach over your shoulder for the tank valve. If you cannot touch it, the tank is too low in the pack. Adjust the height as needed. When you become familiar with the correct height adjustment, you will not need to test it before completing the assembly of the scuba unit, but you should check it before entering the water.

Tighten the band as much as possible before securing it, and test the tightness by grasping the tank valve with one hand and the top of the pack with the other hand. Try to move the pack up and down on the tank. If there is movement, the band needs to be tighter.

Attach the regulator assembly to the scuba tank. The tank valve should have a valve protector or a piece of tape over the valve opening. Remove the cover or tape (but do not litter—put the tape in a trash container or in your gear bag). Make sure that the O-ring remains in place and is free of debris. Loosen the regulator yoke screw, and remove the dust cover. If your regulator second stages have purge depressors, release the purges. Expel any water or dirt from the valve by opening the tank valve slightly and momentarily before you attach the regulator to the tank.

Your regulator has several hoses. Orient the hose to your primary second stage toward the same side of the tank as the handle of the tank valve so that the hose will come over your right shoulder. When you orient the hose this way, the other hoses are properly oriented automatically as long as they are untangled and can hang freely.

Carefully seat the inlet opening of the regulator on the tank valve outlet, and then turn the yoke screw or DIN fitting until it is snug but not tight. Tighten the fittings using only your fingers and thumb. See figure 6.13 for an example of a regulator attachment.

Attach the various regulator hoses to the scuba unit. It is easier to attach the low-pressure hose to the BC before you pressurize the hose. Attach your instrument console to the BC, but do not attach your extra second stage yet.

Turn on the air. Hold the SPG with the front facing away from you and others so it will not cause an injury if it fails when pressurized. The SPG blowout plug should prevent an explosion from occurring, but holding the gauge is a good precaution. Open the tank valve slowly in a counterclockwise direction. Open the valve all the way; then close it one-quarter turn. You should feel the hoses stiffen under pressure. Listen for leaks in the system. If the regulator free-flows, cover the mouthpiece opening with your thumb to stop the flow. If air leaks



Figure 6.13 Your regulator and hoses should look like this if attached correctly to the cylinder.

from the tank valve seal, turn the air off, remove the regulator, and inspect the seal. You may have to replace the O-ring. Solve all air leakage problems before you use the scuba unit.

Testing the unit is the final step. Use your SPG to make sure the tank is full. Reset instruments in your console as needed. While looking at the SPG, depress the regulator purges momentarily to test the second stages and clear them of any debris; then breathe deeply through each second stage several times. The tank pressure reading should remain constant while you breathe from the regulator. If the pressure reading drops when you inhale, you have not opened the tank valve sufficiently. Do not open the valve partially to check the pressure of the tank. When you have finished testing the regulators, attach the extra second stage to the BC. Depress the low-pressure inflation valve on the BC for one or two seconds to make sure the valve functions correctly. When you have completed the assembly and testing of the unit, lay it on its side with the regulator and instruments on top.

Equipment assembly procedures are the same for both new and experienced divers. Always assemble and test your scuba equipment before you suit up. Practice will help you recall the assembly procedures.

Donning and Inspecting Scuba Equipment

With skin diving equipment, you don the weight belt after the skin diving vest, but with a jacket-type BC, you should don the weight belt before the scuba unit.

A good way to don a scuba unit out of the water is for your buddy to hold the system and help you into it. Once your arms are through the shoulder straps, you should bend forward and balance the unit on your back while you secure the waistband. Place the regulator hoses over your shoulders while you fasten the waistband so the hoses are not trapped beneath the waistband. Some dive boats have vertical tank racks on seats to allow you to sit while donning the system. Do not sit on the deck or ground to don a scuba tank, however, because the tanks of other scuba divers can strike you in the head.

Some divers prefer to don the scuba unit in the water—this is a good practice if you dive from a small boat or have a minor back problem. Put the scuba unit into the water first. Make sure that it does not float away! To don a jacket BC unit in the water the way you would don a coat, inflate it fully, sit on it, put your arms through the arm holes, and slide off and into the unit. Or you may put your scuba unit on over your head. Maneuver the tank in front of you with the valve facing you and the backpack facing up. Place the regulator in your mouth and keep the hose of the primary second stage between your arms. (If you place your right arm inside the loop of the hose, the hose will wrap around your arm when you try to lift the tank over your head.) Place your forearms completely through the arm holes just past your elbows, and begin to lift the scuba unit over your head. Rather than lift the unit, you should push yourself down in the water and duck beneath the scuba unit. Lower the tank into position on your back. Use your left hand to pull your snorkel clear of your BC as the tank lowers into position. When the tank is in place, lean forward and secure the waistband.

When you have donned your scuba equipment and the remainder of your diving equipment, inspect all your equipment to make sure it is positioned, adjusted, and functioning correctly. Your buddy should do likewise. Then inspect each other's equipment.

Do a head-to-toe buddy check. Specific checks for each item of equipment are listed in the Head-to-Toe Buddy Check sidebar.

Equipment inspections are important. Solving problems is easier before you enter the water than afterward. It does not take much time to inspect each other's equipment, but the practice can save a lot of time later. Make predive inspections a habit.

Scuba Diving Skills

To be a scuba diver and enjoy diving with minimum risk of injury, you need to learn the proper procedures for entering and exiting the water, controlling your buoyancy, descending and ascending, monitoring your instruments, and coordinating with a buddy. This section provides a helpful introduction to these skills, but you must learn them by doing. You will learn the skills in pool-like conditions and then apply them in open water.

Using Entry Techniques

The four basic types of water entries for divers are wading, seated, feetfirst, and back roll. You need to learn when to use each type and the procedures for each. The objective of any entry is to get into the water as easily as possible without injuring yourself or losing any equipment. After you enter the water and are under control, switch from your regulator to your snorkel if you are going to swim or remain at the surface.

You can make open-water entries from the shore or from a boat. You can wade in from the shore, or you can enter from an artificial structure such as a dock, pier, or jetty. The conditions vary greatly, and so do the entry techniques. Surf may be a factor at some locations. Bottom conditions can range from smooth and soft to rough and firm. The bottom may slope gradually or steeply, and there

Head-to-Toe Buddy Check

Mask	In place, flush on face, no hair under skirt, not fogged
Snorkel	Attached to left side of mask
Scuba cylinder	Valve open all but a quarter turn, valve facing user's right side, height OK, snug in pack
SPG	Full pressure, not damaged or leaking
Scuba regulator	Primary and alternate air sources function OK, both buddies know the placement of the alternate air systems, regulator hoses oriented properly and free for use
Buoyancy compensator	Inflates and deflates properly
Weighting system	In place, proper amount of weight, right-hand quick release accessible, weights clear to drop, both buddies familiar with weight release system
Exposure suit	Properly positioned and zipped
Dive knife	Attached properly, easy to access, secured
Fins	Securely strapped or worn
Instruments	Watch, dive timer, or dive computer ready for use

may be holes and drop-offs. Plants, animals, and rocks may be present in the entry area. A good entry technique for one location may be inappropriate for another. It takes experience and knowledge of the area to determine an effective entry procedure.

You need to know some general techniques when making wading entries at an open-water site. A wading entry sounds simple, but keep in mind that diving equipment affects your center of gravity, your mobility, and your peripheral vision. You must walk backward or sideways when wearing fins.

If there is little or no surf, you can wade in, don your fins, and begin your dive. Breathe through your regulator and have your BC inflated partially. Shuffle your feet to detect holes and rocks and to chase away bottom-dwelling creatures (see figure 6.14). When the water reaches your thighs, lie down in the water and start swimming. In some areas with muddy bottoms, you should not wade because you can sink deeply into the mud and lose a fin when you try to extract your foot. When the bottom is firm and the water is calm, you can wade into the water without your fins and don them in the water. It is helpful to have information about the bottom conditions of a dive site.

In most areas where there is surf, you should don your fins before you enter the water, and you should not remove them until you are clear of the water after the dive. Time your entry to coincide with small waves (see the discussion of waves and surf in chapter 5). Keep all equipment in place, and breathe through your regulator. Deflate your BC because you need to duck beneath breaking waves when they are higher than your waist. If you inflate your BC, you will be unable to duck beneath the waves, and a large wave could lift and toss you. Hold your mask with one hand at all times; spread your fingers and curl them over the top of the mask so you can see. Keep your knees bent and shuffle sideways into the waves to minimize your profile to the moving water. Stop moving just before a wave hits you, allow the wave to pass, and then resume your shuffling until the water is deep enough for you to swim. Allow incoming waves to pass over you, and move through the surf zone quickly.

From a commercial dive boat, you can enter the water from the side or from a water-level platform at the back of the boat. Have all equipment in place, breathe



Figure 6.14 When entering surf, shuffle sideways (keeping knees bent), hold your mask, and lean into waves.

Courtesy of Fred Humphrey.

from your regulator, and hold your mask securely. Have any specialty items, such as a camera, handed to you after you are in the water; another option is to retrieve these items from an equipment line. When entering from the side of a boat, note the direction of boat movement. Wind will cause an anchored boat to swing from side to side. If you enter the water on the side of the boat when the boat is moving in that direction, the boat may pass over you after you enter.

You can do a controlled, seated entry from a dock, from a swimming platform on a boat, or from any surface where you can sit close to the water, whether the water is only a few feet deep or too deep for standing. With all equipment in place, turn and place both hands on one side of your body on the surface that you are seated on. Then lift yourself slightly, move your body out over the water, and lower yourself into the water. A controlled, seated entry is a simple and easy entry (see figure 6.15).

Use feet-first entries when the distance to the water is too high for a seated entry, such as when entering from a commercial charter boat. Two types of feet-first entries can be used: giant stride and feet together.

Use the giant-stride entry, shown in figure 6.16, when the distance to the water is about 3 to 5 feet (1 to 1.5 m) and you want to remain at the surface during the entry. Stand at the entry point with your equipment in place and your BC partially inflated. Observe the point of entry and make sure the area is clear. Hold your mask firmly with one hand, spreading your fingers so you can see. Look straight ahead while stepping out with one leg. The entry is a step, not a hop or a jump. If you step out as far as you can, your trailing leg follows automatically. Keep one leg extended forward and the other leg extended backward until you hit the water; then pull your legs together quickly to stop your downward momentum. As soon as you stabilize at the surface, turn and signal that you are OK, and then move away from the entry point so that the next diver can enter.



Figure 6.15 Entering the water from a seated position.



Figure 6.16 Giant-stride entry.

Use the feet-together entry to avoid discomfort from the impact when the distance to the water is too high for a giant-stride entry. The procedures are the same as for the giant-stride entry, except that after you step out from the entry point, you bring your legs together before you hit the water. A feet-together entry submerges you. After you bob back to the surface and stabilize, signal the next diver and clear the entry area.

A back-roll entry can be done from either a seated or squatting position. Use the seated back-roll entry from a low, unstable platform, such as a small boat. You can also use a back-roll entry when the distance to the water is too high for a regular seated entry and the platform is too unstable for you to stand. To do a seated back roll, sit with all equipment in place and your back to the water. Move your bottom to the very edge of the surface on which you are sitting. Have someone make sure the entry area is clear. Hold your mask with one hand and your mask strap with the other hand. If you do not hold the mask strap, the force of the water may wash it up over your head, and your mask may fall off. Lean backward to begin the entry. Hold your knees to your chest as you roll backward; if you don't, you may clip your heels on the edge of the surface you were seated on (see figure 6.17). You are likely to do a backward, disorienting somersault in the water with this entry. You can reorient yourself when you bob back to the surface.



Figure 6.17 Entering with legs extended risks clipping the heels on the boat. Tuck the legs into the chest instead.

Christian Wheatley/Getty Images

A squatting back roll is used when there is no suitable surface on which to sit. The thin side of a small, rocking boat is a good example of an unsuitable seat. For a squatting back-roll entry, prepare yourself while sitting on an adequate seat immediately adjacent to the entry area. Make sure the entry area is clear, then stand partially, turn your back to the entry area, and literally sit down into the water (see figure 6.18). Pull your knees to your chest as you enter so that you do not catch your heels.



Figure 6.18 Squatting back-roll entry.

Surface Snorkeling With Scuba Equipment

You may use your snorkel for surface swimming in order to conserve the air in your scuba tank. This procedure is used in areas where divers need to swim from shore to reach the dive area. If you use air from your cylinder for surface swimming, you will reduce the amount of time you can remain underwater. When snorkeling while wearing scuba equipment, you should inflate your BC partially. Excessive air in your BC combined with the weight of your scuba tank

Three Important Scuba Diving Rules

1. Equalize pressure in your ears early and often.
2. Always breathe; avoid breath holding.
3. If the scuba regulator is out of your mouth, exhale continuously.

can cause you to roll sideways when swimming facedown. It is better to swim on your back or side; these positions allow wider kicks than when swimming facedown, and the tank weight is not a factor. If you swim on your back, you can breathe without the snorkel. Swim beside—not behind or in front of—your buddy. Move slowly and steadily, pacing yourself. If you feel short of breath after snorkeling, rest before beginning your descent.

Recovering and Clearing the Regulator

When you are in the water wearing scuba equipment and have removed your regulator second stage from your mouth—such as when snorkeling or talking at the surface—you need to recover it from behind your right shoulder (where it falls naturally). The second stage will have water inside, and you must clear the water before you breathe. If you start with the regulator in your mouth, you need to place the regulator in the water. The task is more difficult than it sounds because if you place the second stage in the water with the mouthpiece facing up, the regulator free-flows. Place the second stage in the water with the mouthpiece facing downward to prevent free-flow.

Two methods can be used to recover the regulator second stage from behind your shoulder. The most popular technique is the sweep method. Lean to the right side so gravity swings the second stage away from you. Reach back with your right hand until you touch the bottom of your scuba tank, and then extend your arm and sweep it forward in a large arc. The hose will lie across your arm, where you can retrieve the second stage easily.

The second method of recovering the second stage is the over-the-shoulder reach. Reach back toward your regulator first stage with your right hand while lifting the bottom of your scuba tank with your left hand. Grasp the second-stage hose where it attaches to the first stage and follow it down to the second-stage end. Some divers find this recovery method difficult or impossible.

Clearing the regulator can be as simple as exhaling into it. As long as the exhaust valve is at the lowest point, the water inside the second stage will be displaced. If the exhaust valve is not at the lowest point when you exhale, only part of the water may be exhausted, and you may inspire some water when you inhale. To avoid choking on inhaled water, find out where the exhaust valve is on your regulator, be sure to make it the lowest point when you clear your regulator, and inhale cautiously after clearing the regulator.

Another way to clear a regulator second stage—the purge method—involves using low-pressure air to clear the water from the chamber. If you insert the mouthpiece into your mouth and depress the purge, you may blow water down your throat. You can prevent this in two ways. One way is to depress the purge lightly as you place the bubbling regulator in your mouth, and to use back pressure from your lungs to keep water out of your mouth and throat. The other method is to place the regulator into your mouth, block the opening with your tongue, and depress the purge momentarily to clear the chamber. Either method is acceptable. If you are purging the regulator while placing it in your mouth, release the purge the moment the regulator is in place to avoid overinflating your lungs. Develop the habit of blowing a continuous stream of tiny bubbles any time the regulator is out of your mouth to avoid holding your breath while breathing compressed air.

Performing Snorkel–Regulator Exchanges

You must be able to switch from breathing from your snorkel to breathing from your regulator and vice versa. When you prepare to descend for diving, you exchange your snorkel for your regulator; when you surface after a dive, you exchange your regulator for your snorkel. Do both exchanges with your face in the water. Take a breath, exchange one mouthpiece for the other, and clear the new breathing device.

Inflating and Deflating the BC

You should be familiar with two ways to inflate a BC and two ways to deflate it. The easiest and most commonly used means of inflation is the low-pressure inflator, which is used to add air to the BC in short bursts. Inflating the BC for several seconds can cause serious buoyancy control problems if the inflator valve sticks. By adding air a little at a time, you have better control of your buoyancy.

If your low-pressure inflator or your integrated second stage develops a problem while you are diving, you may need to disconnect the low-pressure hose. When you disconnect the hose, the low-pressure inflator no longer functions, so you have to control buoyancy by orally inflating the BC. The mouthpiece of a BC is usually more elaborate than the mouthpiece of a skin diving vest. To help keep water out of a BC, the mouthpiece has a purge so that the water inside can be cleared before you open the valve to the BC. To clear the BC mouthpiece and orally inflate the BC, follow this procedure:

1. Insert the mouthpiece into your mouth.
2. Exhale a small amount of air into the mouthpiece to clear it.
3. Keep the mouthpiece in your mouth.
4. Depress the manual inflator-deflator valve.
5. Exhale into the BC.
6. Release the manual inflator-deflator valve.
7. Repeat the procedure until you achieve the desired amount of buoyancy.

You can use the same bobbing technique at the surface that you learned for the skin diving vest (see the previous explanation in this chapter), but oral inflation procedures are different underwater. To inflate a BC orally underwater, follow these steps:

1. Grasp the inflation valve with your left hand, and grasp your regulator second stage with your right hand.
2. Take a breath.
3. Insert the BC mouthpiece into your mouth.
4. Clear the mouthpiece.
5. Exhale most of the air in your lungs into the BC.

6. Save enough air to clear the regulator, which fills with water when you remove it from your mouth.
7. Repeat the procedure until you achieve the desired amount of buoyancy.

You can deflate your BC with the manual inflator-deflator valve or with a dump valve. If you do not use a dump valve, you must open the deflator valve at the lower end of the BC hose and hold it higher than the highest point of the BC. Using a dump valve is more convenient than using the deflator valve. Note that you can deflate your BC only when the exhaust port is the highest point. Air cannot escape if you try to deflate a BC in a horizontal or inverted position, so you need to be in an upright position to deflate your BC.

Testing Buoyancy

Similarities exist between buoyancy testing for skin diving and buoyancy testing for scuba diving, but there are also some important differences. Buoyancy varies more when you scuba dive than when you skin dive. The volume of air in your lungs varies more in scuba diving. You dive deeper, so suit compression affects your buoyancy more. As you use air from your scuba tank, your buoyancy changes. You need to sense buoyancy changes quickly to maintain control of your buoyancy.

Your initial buoyancy test for scuba diving can be the same as your buoyancy test for skin diving. Begin by testing your BC at the surface. Inflate it fully and then deflate it. Make sure the low-pressure inflator and all deflation valves function correctly. With your regulator in your mouth and your BC completely deflated, relax and breathe slowly. When your lung volume is high, you should remain at the surface with your eyes just below the surface–water interface. If you sink with your lungs full of air, you need to remove some weight. When you exhale completely, you should sink. If you cannot sink after a complete exhalation, you need additional weight. Test your buoyancy while you are close to your point of entry, and correct any buoyancy problems before you attempt to dive.

As you descend in open water, you may need to add air to your BC in order to maintain neutral buoyancy. Strive to maintain neutral buoyancy continuously. Add air to your BC in small amounts, and test your buoyancy by stopping all motion and observing what happens. If you are sinking, inhale and add air to your BC. If you are rising in the water, exhale and release air from your BC. With experience you will know when to add air to your BC, when to vent air from your BC, and how much air to add or release.

You can learn buoyancy control in a swimming pool by assuming a rigid, face-down position with your arms at your sides. If your buoyancy is correct, a slow, full inhalation raises your shoulders while your fin tips remain on the bottom; a slow, complete exhalation causes your shoulders to sink. Some people call this buoyancy evaluation **diver's push-ups** (although you do not use your hands). If you do not rise with a full inhalation, you should add a small amount of air to your BC and try again. Figure 6.19 illustrates a diver doing diver's push-ups.

As a scuba diver, you need enough weight to get down at the beginning of a dive and enough weight to allow you to remain in control when you ascend at the end of the dive. The precise weight for scuba diving is the amount you need to hover at a depth of 15 feet (4.6 m) with 300 psi (20 atm) of air in your tank and no air in your BC. This amount may overweight you slightly at the beginning of a dive. Test your buoyancy at a depth of 15 feet at the end of a dive to see if you need to make an adjustment for your next dive.



Figure 6.19 Executing proper diver's push-ups ensures good buoyancy control.

Controlling Buoyancy

No skill identifies a scuba diver's ability as much as buoyancy control. The ability to finely control buoyancy is important for safety, for enjoyment, and for the welfare of the environment. When your buoyancy is out of control, a hazard exists for both you and the environment around you.

With your buoyancy adjusted to the point where you can pivot slightly up and down on your fins on the bottom (in a pool) while inhaling and exhaling, push yourself about 2 feet (0.6 m) off the bottom and remain motionless. You may or may not remain in a horizontal position, but that is not important. Maintain your depth by controlling your average lung volume, but remember to breathe continuously. If you are sinking, keep more air in your lungs. If you begin rising, reduce the amount of air in your lungs. With practice, you will be able to hover motionless just off the bottom.

To demonstrate mastery of hovering, assume a vertical position in the water. Cross your legs at the ankles, grasp one wrist with the opposite hand, and remain motionless. Find an eye-level reference and develop the ability to hover motionless while upright in the water. Pay attention to the buoyancy effects of breathing. Once you master hovering both horizontally and vertically, you will realize several benefits. Your air will last longer, swimming will not tire you as much, you will need fewer buoyancy adjustments, and you will do less damage to the diving environment. Your buoyancy control continues to improve with practice until you become a highly experienced diver.

A useful skill for maintaining neutral buoyancy during ascent is a BC venting technique called an **open-valve ascent**. When you ascend, air in your BC expands and affects your buoyancy. You must release the expanding air to control buoyancy. If you vent the air from time to time, your buoyancy is in a constant state of change: You may not release enough air, or you may release too much. The open-valve ascent is a better alternative. Hold the BC inflator-deflator valve just below the level of your shoulder, point the mouthpiece of the inflator-deflator valve downward, and open the deflator valve. Air cannot escape because the opening is lower than the exhaust port on the BC. While you hold the mouthpiece downward and the deflation valve open, raise the inflator-deflator slowly until air just begins to bubble from the mouthpiece. Bubbling occurs when the mouthpiece and the exhaust port on the BC are at the same level. If you hold the inflator-deflator valve at the bubbling level while ascending, the expanding air inside the BC bubbles out through the open valve, and your buoyancy remains constant. If you need to release additional air to control buoyancy, raise the inflator-deflator slightly; if you need to decrease the amount of air you release, lower the assembly slightly.

Using the Dive Flag

You should display the appropriate dive flag or flags when diving. Authorities in some areas require you to use a flag, and flag use is encouraged in all areas. Follow these conventions when you use a dive flag: Display the flag only when divers are in the water, and surface within 100 feet (30 m) of your flag—the closer the better. The flag does not guarantee your safety from boaters, who are supposed to give the flag a berth of at least 100 feet; however, the flag does serve as a signal to many boaters who recognize that the flag means there are divers in the vicinity. Figure 6.20 shows a boat anchored with a dive flag indicating there are divers in the area.

If you support your flag with a surface float, you need to tow your float to the area where you wish to dive. In areas lacking underwater plants, you can tow the float while you dive. In areas with plants, you need to anchor the float to keep it from drifting away, and you must navigate back to the flag at the end of your dive. When entering through surf, you should tow the surface float behind you. Push the float ahead of you when exiting through surf.

Figure 6.20 Surface as close as possible to the dive flag to keep you safe from other boaters.



Descending

Scuba descents are different from skin diving descents. You usually descend headfirst as a skin diver, but scuba divers descend feet-first. A feet-first descent allows better control of buoyancy, provides better orientation, allows buddies to maintain contact during descent, helps prevent the swallowing of air, and allows easier pressure equalization of air spaces.

Descending involves several procedures, which seem complex at first but become routine with practice. The process of descending includes preparing to descend, initiating the descent, and completing the descent.

1. Preparing to descend
   - Check your instruments. Orient yourself at the surface and set a reference on your compass. Be sure your underwater timer and depth gauge are zeroed.
   - Confirm that your buddy is ready to begin.
   - Exchange your snorkel for your regulator.
   - Pressurize your ears slightly to begin the equalization process (see chapter 3).
   - Hold your BC deflator valve in your left hand.
   - Give or acknowledge the signal to descend.
2. Initiating the descent
   - Begin the descent by venting your BC. It is better to do this with the dump valve than by holding the deflator valve above your head. Hold the inflator-deflator valve in your left hand throughout the descent so you can add or release air from your BC at any time. Exhale fully to help get started downward.
   - Breathe shallowly for the first 10 feet (3 m).
   - Equalize pressure in your ears about every 2 feet (0.6 m) for the first 15 feet (4.6 m). If you experience equalizing problems, ascend a few feet to reduce the pressure, equalize again, and descend again. Exhale some air into your mask to prevent a mask squeeze. (See chapter 3 for a description of pressure equalization.)
   - Keep your fins still while you descend so that you do not stir up silt on the bottom.
   - Control your rate of descent by the average amount of air you keep in your lungs. When you begin sinking while your lungs are full, add a short burst of air to your BC to regain neutral buoyancy.
3. Completing the descent
   - Remain with your buddy throughout the descent.
   - Avoid contact with the bottom.
   - Hover above the bottom, level off to a swimming position, agree on a direction with your buddy, and begin your exploration.

Two types of descents are performed in open water: **reference descents** and **nonreference descents**. A reference descent is one that you control by following a line or the slope of the bottom. You should do a reference descent whenever possible. A descent made vertically in water without any external reference is a nonreference descent, which is more difficult to control than a reference descent.

Clearing the Mask

To clear a mask while scuba diving, you need to develop the skill of breathing through your mouth with your nose exposed to water. With concentration and practice, you can master this skill quickly. First, try inhaling through your mouth and exhaling through your nose. Next, try inhaling and exhaling through your mouth. If you feel any water going up your nose, exhale immediately to keep the water out.

To practice clearing a mask, you need to flood it with water. This is not difficult, but a few tips make it easier. If you exhale lightly while tilting the mask forward on your face to break the seal at the top, the mask releases from your face easily, and the air escapes at the highest point. When you reseat your mask to begin clearing it, be sure to hold back any strands of hair with one hand while you reseat the mask with the other. Hair under the mask causes leakage. If you are wearing a hood, make sure that the hood is clear of the mask before you attempt to clear water from the mask.

Buddy Diving

You should always dive with a companion, using the **buddy system**. A buddy provides reminders and assistance and sees things that you might not see. Buddies inspect each other's equipment, provide feedback based on observations, and work as a team. Dive buddies should remain close enough to each other that one can immediately assist the other in the event of an emergency. The more turbid the water and the greater the depth, the closer buddies should remain to each other. During your training, you should strive to remain within touching distance of your buddy at all times; learn to keep track of your buddy. Maintaining contact with a dive buddy in open water is not difficult when you follow a few standard procedures.

Agree on a position relative to one another and maintain that position as much as possible. That way, your buddy will know where to look for you, and you will know where to look for your buddy. The best dive team configuration is side by side; the least desirable is for one diver to be above and behind the other. Looking up and back is difficult when you are hampered by your equipment.

Agree on a direction of movement. Both parties should maintain that direction until both agree to proceed in a different direction. When you follow this practice, there are fewer directions to consider if you and your buddy become separated.

Confirm your buddy's position every few seconds. If you scan the areas ahead from side to side while swimming, you should get a glimpse of your buddy each time you turn your head in your buddy's direction.

When visibility is poor, physical contact can keep you and your buddy together. Holding hands is appropriate. Or you can use a short line—a **buddy line**—to keep in contact with each other. If you become separated from your buddy underwater, look for your buddy for up to one minute. If you are unable to locate your buddy, ascend slightly and turn in a circle while looking for bubbles. The visibility is often better a few feet above the bottom than it is at the bottom. If you do not see your buddy's bubbles, ascend to the surface and wait for your buddy, who should also duplicate this procedure. When you have reunited at the surface, you can descend again and continue your dive. Obviously, it is better to remain together underwater than to surface to reunite.

The Buddy System

Teaming up with a qualified partner is appropriate for activities that involve risk, such as swimming, rock climbing, and skin and scuba diving. Safety is the primary purpose of the buddy system, but having a dive buddy also makes diving more enjoyable. The following list describes the duties and responsibilities of a good dive buddy:

- Helps to plan the dive in advance and after arrival at the dive site
- Reviews signals and emergency procedures
- Assists with the donning of the scuba unit
- Inspects equipment
- Maintains contact while diving and follows procedures for reuniting if separation occurs
- Provides reminders concerning depth, direction, time, air pressure, and ascent rate
- Points out items of interest
- Identifies problems that you are unaware of, such as an air leak
- Provides reassurance and assistance as needed
- Summons additional assistance as needed
- Provides first aid as needed
- Assists with exits and the removal of the scuba unit

If you are unable to relocate your buddy underwater and your buddy does not surface promptly, look at your surroundings to mark your position so that you will know the approximate location where your buddy was last seen. If someone is overseeing the diving operations, notify this person that your buddy is missing so that a search can be initiated. If you are alone, try to locate bubbles that could indicate your buddy's position.

Underwater Swimming

When you swim along the bottom, your fins can raise a cloud of silt that harms the environment and reduces visibility. Silting is more of a problem when you are overweighted because the excess weight angles your fins toward the bottom when you swim (see figure 6.21). The first step in reducing silt is to weight yourself properly. In areas where the bottom silt is thick, add air to your BC to make yourself slightly buoyant underwater. The buoyancy forces you to swim at a slight downward angle and keeps the thrust of your fins directed upward. Another way to reduce silt is to remain far enough from the bottom to keep from disturbing it.



Figure 6.21 Overweighting can cause divers to stir up a cloud of silt.

Finally, consider changing your kick if you boil up silt with your kick strokes. You should also consider redistributing your weight by placing a small portion of it higher on your body to achieve level trim as described in the “Mobility Adjustments” section of chapter 3.

When you kick something while swimming, you must overcome the tendency to want to get away from whatever you kick. Your kicks are strong and can damage the environment or another diver. As soon as you feel something with a fin, stop kicking, look back to see what you have hit, and maneuver yourself clear before proceeding.

Navigating

To find your way underwater, you can use natural navigation and compass navigation. You can best determine your relative position with a combination of both types of navigation.

With natural navigation, you use your natural surroundings to determine where you are. Light, shadows, plants, formations, water movement, depth, and other indicators can help you navigate. As you move, note your surroundings. Observe which way you are going relative to the movement of the water, the sand ripples on the bottom, the depth contour, and the angle of the sun. By noting natural aids to navigation, you can find your way underwater.

A dive compass increases the accuracy of navigation. Figure 6.22 shows two types of dive compass. You need to be able to set a direction (called a **compass heading**) and to determine which way you are going relative to the directional reference you have set. Your compass should have a reference line, called a lubber line, that you point in the direction of travel. The north-seeking needle or card of the compass establishes a position relative to the lubber line as long as you hold the compass in a level position. Many dive compasses have index marks on a movable bezel. You set the index marks to indicate the heading. Electronic compasses allow you to set a heading and use arrows to indicate the direction that you need to turn to remain on course.



Figure 6.22 Traditional dive compass (left) and electronic dive compass (right).

To go in the direction set on the compass, you must hold the compass so the lubber line is directly in line with the centerline of your body. If the lubber line points to one side, you will not be on course even though the north reference is at the correct point on the dial. Figure 6.23 shows a compass lock position.

A **compass course** is a series of headings that leads to a destination. Many types of compass courses may be used. One frequently used course is the **square compass course**. To navigate a square course, set your initial heading and proceed in that direction for a given distance, which can be measured by time, tank pressure, or fin kicks. Stop and turn 90 degrees to the right while continuing to keep the lubber line aligned with the centerline of your body. Note the relative position of north on the compass, and proceed in the new direction for the same distance as you covered on the first leg of the course. Stop again, and turn another 90 degrees to the right. Note the position of north on the compass, which should be opposite your initial heading. Proceed along the third leg of the course for the same distance as before. Stop once more, turn again 90 degrees to the right, note the relative position of north, and follow the new heading back to your starting point.


Figure 6.23 The compass-lock position.

Divers also frequently follow a **reciprocal compass course**—an out-and-back course. Set the initial heading on the compass. At the midpoint of the dive, turn 180 degrees until north on the compass is directly opposite the original heading. Then follow the reciprocal heading back to your starting point. Advanced scuba diving courses provide additional compass navigation training.

If you do not know precisely where you are when the end of a dive approaches, you may need to surface, find a reference for your exit, and set a compass heading that leads directly to the end-of-dive location. Be especially careful if you surface more than 100 feet (30 m) from your dive flag.

A compass provides correct directional reference information when it is not affected by nearby objects. Metal objects, other compasses, and electrical fields within a couple of feet of a compass can cause it to deviate from its correct reading. Keep metal, magnets, dive lights, and other compasses away from your compass to help ensure accuracy.

Monitoring Instruments

Most diving instruments are passive; that is, they do not provide information unless you look at them. Some instruments emit an audible beep, but most require observation to provide information. Develop the habit of checking your instrumentation frequently while diving so that you can control your depth, dive time, and direction. This will also help you avoid running out of air. You should be able to accurately estimate your tank pressure at any time during training. If you cannot estimate the pressure within 300 psi (20 atm) at any time, you need to monitor your SPG more frequently.

When you are planning to dive in open water, you should look at your instruments when you assemble your equipment. Look at your instruments again when you inspect your equipment. Look at your instruments again before you descend and again while you are descending. Refer to your compass for directional reference before you begin moving underwater. Monitor your gauges every few minutes while diving, and compare your air pressure with your buddy's several times during a dive. At any given time during a dive, you should be able to accurately estimate your depth, your dive time, your direction, your tank pressure, and your buddy's tank pressure. If you cannot do this, you need to improve your instrument-monitoring skills.

Using Scuba Diving Hand Signals

Scuba divers use several hand signals that are not used for skin diving. The signals specific to scuba diving relate to air supply. Learn and use the standard hand signals shown in figure 6.24. Remember to display hand signals clearly and deliberately and also to acknowledge the hand signals you receive.

Ascending

Scuba ascents are different from skin diving ascents, although there are a few similarities. The procedures you need to learn become automatic with practice and experience.

To initiate an ascent, one member of a buddy team gives the ascent signal, which the other acknowledges. Always obey the ascent signal. Prepare to ascend by noting your time, depth, and remaining air. Locate your BC inflator-deflator assembly, and hold it in your left hand. Begin the procedures for the open-valve ascent previously described (see "Controlling Buoyancy").

Begin ascending slowly with your buddy while breathing continuously. Monitor your depth gauge and keep tabs on your buddy. The maximum rate of ascent is 0.5 feet (0.15 m) per second, which is quite slow. Some instruments warn you when your rate of ascent is too rapid. You need training, practice, and awareness to avoid exceeding the maximum rate of ascent.

Stop and decompress (outgas) when indicated by your dive computer. Whether or not you make a "deep stop," you should stop for one to three minutes at a depth of 15 feet (4.6 m) to help prevent decompression sickness (DCS). The procedures for decompression are described in chapter 7. As you ascend, look up and around. Extend one hand above your head for protection against overhead obstacles. Make one full rotation to view the surrounding area as you near the surface. When you reach the surface, make another rotation to view the area, and then inflate your BC to establish buoyancy. Exchange your regulator mouthpiece for your snorkel.

Handling Equipment

Sometimes you will need to remove, adjust, and replace scuba equipment while you are in the water. You may need to remove equipment to exit the water onto a boat, to make an adjustment, or to free the equipment from an entanglement. With training and practice, you should be able to handle your equipment easily.

Removal of the scuba unit is easy because it is similar to removing a coat. Open the releases, slip your left arm free, swing the scuba tank forward under your right arm, hold the scuba unit with your left hand, and pull your right arm free. Freeing your left arm is easier if you insert your hand and wrist through the armhole of the BC first and remove it hand first (instead of pulling your arm through first). If you are at the surface in water too deep for you to stand when you want to remove your scuba unit, you should remove your weight belt first and place it on a surface float or support station. Don the scuba unit in the water according to the in-water donning procedures previously presented in this chapter.



1. Descend

2. Ascend

3. Stop

4*a*. OK

4*b*. OK

4*c*. OK

5. Something's not right

6. Emergency

7. Low on air

8. Out of air

9. Give me air

10. Look

11. Danger

12. Watch me
(finger pointing to chest)

13. You lead, I follow

14. Get with your buddy

Figure 6.24 Scuba diving hand signals.

Using Exit Techniques

The technique you use to exit the water depends on the situation. To exit from shallow water in a swimming pool, begin by removing your weight belt, tank, and fins, in that order. Carefully place the equipment on the side of the pool; then climb out by using the ladder or lifting yourself up onto the edge of the pool.

To exit from the deep end of a swimming pool (as shown in figure 6.25), begin with your BC inflated partially. If you exit on a ladder, grasp the ladder with one hand and remove your fins with the other; maintain contact with the ladder at all times. Place your fins on the edge of the pool, or slide the heel straps over your wrists; then climb the ladder to exit the water. Clear the exit area at once, and take your fins with you. Remove your scuba system and weight belt when you are well clear of the exit area.

To exit from deep water without a ladder, begin by removing your weight belt and carefully placing it out of the water. Remove the scuba unit and use one hand to trap the regulator hose against the surface onto which you will exit. Use your other hand to remove your fins, and place them out of the water. Place both hands on the exit edge. With the regulator hose trapped under one hand, lower yourself to about chin level in the water while you extend one leg forward and one leg backward. Pull yourself upward with your arms, and pull your legs together forcefully in a strong scissors kick to provide upward momentum. Pull with your arms until you are far enough out of the water to push downward and lift yourself from the water (see figure 6.26). Immediately after your exit, turn around and pull your scuba unit from the water carefully.

If you are boarding a boat that has a ladder, you should keep your tank and mask on and keep your regulator in your mouth in case you fall back into the water (see figure 6.27). Use the ladder exit technique described for exiting the deep end of the pool. Maintain contact with the ladder at all times when you



Figure 6.25 Exiting from the deep end using a ladder.



Figure 6.26 Exiting from the deep end without a ladder.

are in the water. If the boat has a platform at the rear, you usually swim onto the platform, remove your fins, and then stand on the platform and board the vessel.

Techniques for wading exits in open water vary with the environment. You should usually wear all your equipment until you are clear of the water. Shuffle your feet along the bottom while moving backward. Surf exits require training and practice. Stop outside the breaking waves and evaluate the surf. Approach the surf zone with your regulator in your mouth and your BC deflated. Hold your mask continually in the surf zone. Follow a breaking wave, and allow additional waves to pass over you until the water is only a couple of feet deep. If the surf is mild, you can stand at that point and back out of the water. If the surf is strong, swim until you can crawl; then crawl clear of the water (see figure 6.28).

When you are clear of the water, work with your buddy to remove your fins. The buddy system is in effect even when you are out of the water.



Figure 6.27 Boarding a boat with a ladder.



Figure 6.28 Using a crawling exit in strong surf.

Courtesy of Fred Humphrey.

Disassembling Equipment

The first step in disassembling your scuba equipment is to turn off the air by turning the valve in a clockwise direction. Release the pressure in the hoses by depressing the purge on the regulator second stage. Keep the purge depressed until you bleed all the air from the system. Next, disconnect all hoses that are connected to the scuba unit: the low-pressure inflator, the extra second stage, and the SPG. Loosen the yoke screw and remove the regulator from the tank. Dry the first-stage dust cover thoroughly and replace it. Loosen the tank band and remove the BC from the scuba tank. Be sure to rinse and care for your equipment as soon as possible (following the procedures described in chapter 4).

Managing Physiological Problems

If you do everything you are trained to do as a scuba diver, you can avoid problems. But it is not a perfect world. If you fail to pay attention or forget to do something, a problem can occur. Good divers can deal with nearly any problem. This section introduces you to proven ways of dealing with potential diving difficulties. Do not be overly concerned about the problems presented. You can prevent them, but knowing how to deal with them helps reduce your apprehension.

Difficulties affecting your physiology include seasickness, dizziness, stress and panic, overexertion, coughing, and cramping. When you have one of these problems, your body sends messages that something is wrong. You need to know the messages and the actions you can take to overcome physiological difficulties.

Seasickness

The best strategy is to try to prevent seasickness (see “Equilibrium Adjustments and Seasickness” in chapter 3) because taking medication after you are seasick is usually ineffective. If you do get seasick, you are likely to vomit. Vomiting underwater can be dangerous because of involuntary gasping that can cause you to choke. Only you can determine your degree of nausea. If you throw up or feel as if you are on the verge of doing so, do not dive. If you feel queasy, getting into the water may help you overcome the feeling. Some divers who feel slightly nauseated find that they feel better if they get into the water quickly and dive. After that first dive, they are fine for the remainder of the day.

You should surface if you feel nauseated while diving. If you must vomit underwater, do not vomit through your regulator. Hold the second stage against one corner of your mouth, and depress the purge fully while you vomit. You should get air instead of water if you gasp. When you have finished throwing up, place the second stage in your mouth, clear it, and resume breathing. The purge method should be a last resort. Vomiting through the regulator is not recommended because this method sometimes results in clogging.

If you are seasick and have to throw up while aboard a boat, do it over the rail on the side of the vessel opposite the wind. Do not use the restroom (or head, as it is called on a boat). The best remedy is to get to land, rest until you feel better, and take seasickness medication before returning to the vessel. If you are ill from motion sickness—and if the dive boat has a dinghy and there is land nearby—you should request to be taken to shore for a while.

Dizziness

The absence of visual clues in a weightless environment can cause temporary dizziness. Visual references can help you prevent disorientation (see chapter 3). Injury, temperature changes, and pressure changes affecting the inner ear can also cause a whirling feeling called vertigo, which may be more difficult to overcome than dizziness caused by disorientation.

To cope with either dizziness or vertigo, you should first seek a fixed visual reference. If possible, make physical contact with something solid for a point of reference. If there is nothing to see or to grasp, close your eyes and hug yourself. In most cases, dizziness passes in a minute or two. If you then move slowly and keep your head still, you should be able to surface. A good buddy can recognize your difficulty and assist you.

Stress and Panic

Stress is the perception of a substantial imbalance between environmental demand and a person’s response capability, and it occurs under conditions where failure to meet demand is perceived as having serious consequences. Stressors are conditions or attitudes that cause stress. Dive stressors, which can be internal or external, include cold, illness, exhaustion, injury, fear, equipment problems, loss of air supply, buddy separation, depth, darkness, currents, and disorientation. Stress is not always bad. Moderate stress can cause a feeling of exhilaration, improve performance, and lead to a positive condition called eustress. Excessive stress causes anxiety, decreases performance, and leads to a negative condition called distress.

Knowledge and appraisal of a situation affect your reaction to stress. Training, experience, and your predisposition toward a situation affect your knowledge and appraisal. Thus, your perception of the circumstances is determined by what you know and are able to do, by what you have done, and by any inherent fears about the circumstances that you might have.

The problem with stress in diving is that it can lead to panic—a sudden, uncontrolled, irrational reaction to a perceived danger. Divers who panic often perish. You must manage stress in order to prevent panic. Dr. Tom Griffiths, who has researched stress, said the following: "The most critical factor in the progression of panic after stress increases is whether or not a problem arises." Divers who can recognize and manage stress can overcome problems and are far safer than those who cannot cope with the effects of stress.

Stress has both physiological and psychological components. Anxiety causes involuntary physiological changes. When stress leads to anxiety, your breathing rate and heart rate increase, your nervous system becomes more active, and your awareness decreases. These factors decrease your performance and increase your anxiety. Then heightened anxiety begins the cycle again. Unless you interrupt the cycle, anxiety escalates into panic. Psychological difficulty is every bit as critical as the physical problems. Frank Pia, a chief lifeguard, says, "Much of the distress that a person experiences when difficulty arises stems from what the person tells himself about the situation." You can be exhilarated by a situation or allow it to cause anxiety and distress. Pia continues, "The difference between panic and a heightened physiological state is the thought process."

Michael J. Asken, who has written books about stress, encourages the use of task-relevant instructional self-talk (TRIST). You determine your emotional state when in distress by what you tell yourself. Asken says that in a stressful situation, "Success is not achieved by focusing on the outcome, hoping for a good outcome, or even telling yourself that the outcome will be OK. The most effective self-talk involves imagining that your instructor is sitting on your shoulder guiding you through your response."

With the previous concepts in mind, you can recognize and manage stress. The first steps are to sense your breathing rate and identify your self-talk when a problem occurs. If your breathing rate is fast and you are having negative thoughts about the situation, it is time to break the stress cycle. Stop all physical activity, establish buoyancy, and breathe deeply. Divers in distress usually have an adequate supply of air! As you gain control of respiration, you can think more clearly. Take control of your thoughts before they take control of you. Imagine that you are telling someone else how to deal with this situation. Assess your options, determine the best course of action, and then take deliberate action. As you begin to overcome the difficulty, your confidence increases and your physiological condition begins to return to normal. Figure 6.29 shows how to break the stress cycle that leads to panic.

Now you can understand why some divers are thrilled by the same situation that causes another diver to panic. Remember that stress is simply a matter of perception and that you can change your perception with training and experience.

You can also learn to manage difficult situations by imagining them vividly in your mind. Your body cannot distinguish the difference between an actual event and one that you imagine. As you learn to solve problems in your mind, you can learn to recognize and manage stress.

Overexertion

If you work too hard while scuba diving, the equipment may not be able to supply enough air to meet your respiratory needs. You experience a sudden feeling of suffocation, and you may suspect that your equipment has malfunctioned. It is unlikely that scuba equipment will cease to function suddenly in a way that restricts airflow. More likely than not, overexertion is causing the feeling that you cannot get enough air. You can manage overexertion similarly to the way you manage stress. Stop all physical activity and breathe deeply; you should overcome your respiratory problem within a minute or two.



Figure 6.29 The panic cycle and how to break it.

Coughing

When water strikes your larynx, a reflex coughing action tries to clear the foreign matter from your airway. When you cough while in water, you may inhale additional water, which can complicate the situation. You need to overcome the reflex as quickly as possible. The best way is to swallow hard three times in rapid succession. If you must cough, try to do so through a regulator so that you inhale air rather than water if you gasp. You can lose buoyancy as you expel air when coughing, so you may need to establish positive buoyancy if you cough excessively.

Cramps

When your muscles get cold or when circulation to your muscles is inadequate, cramping can occur. A cramp is a sudden, strong, involuntary, persistent, painful muscle contraction. Divers tend to get cramps in the lower legs and the feet. To alleviate a cramp, stretch the affected muscle and rub it to increase circulation. Pounding a cramped muscle is ineffective and causes tissue damage. If you experience a cramp in your leg or foot in the water, you may be able to get rid of it by grasping the tip of your fin and pulling it toward you. Another technique to help release a leg cramp is to contract the muscles of the opposite leg. This action can inhibit nerve impulses to the cramped muscles. Buddies should assist one another with getting rid of cramps. Figure 6.30 shows a diver relieving a cramp.



Figure 6.30 Your diving buddy can help you relieve a cramp by rubbing and stretching the cramped muscle.

Managing Physical Problems

Potential physical difficulties in diving include entanglement; loss of buoyancy control; loss of air supply; and a distressed, injured, or incapacitated buddy. As with physiological problems, you can overcome these problems, but it is better to avoid them.

Entanglement

You will probably encounter fishing line, nets, wire, string, and rope in the water—and these items can entangle you. Underwater plants can also entangle divers in some areas. Streamlining your equipment to minimize places where things can get caught helps reduce the chance of entanglement. Being aware also helps. When you encounter something that can entangle you, swim around it or push it beneath you and swim over it. Avoid swimming beneath things that can cause entanglement. The area of your tank valve and regulator first stage is one of the easiest places to become entangled and also one of the most difficult areas to free from entanglement.

If you become entangled underwater, you should stop. Then try to examine the problem without turning because turning often compounds the problem. If you can reach the entanglement, you should free yourself. If not, signal your buddy to help you get free. If you can see what you are doing, you can use your dive knife to cut yourself free. Trying to cut yourself free from something in the area of your tank valve is an obvious mistake. If your tank is entangled and you can't reach the entanglement—and your buddy is not nearby to lend assistance—you should remove your scuba unit, free it from the entanglement, and put it back on.

Loss of Buoyancy Control

You can lose control of buoyancy underwater if you lose weights or if a low-pressure inflator on your BC or dry suit sticks. You can take steps to prevent loss of buoyancy control. Check your weight system from time to time while you are diving to make sure it is secure. Inspect your low-pressure inflators before each use, and have them serviced at the first sign of unusual operation.

If your weights fall off while you are underwater, immediately maneuver yourself into an inverted position, swim down forcefully, and retrieve the weights. If you are successful, you can avoid an uncontrolled ascent; if you are unsuccessful, you will float to the surface. Your rate of ascent depends on how buoyant you are without your weights, the type of exposure suit you are wearing, the amount of air in your BC at the time, your depth, and the amount of surface area you can expose to the direction of motion. You learned in chapters 2 and 3 that the greater the cross-sectional area of an object moving in a given direction, the greater the resistance to movement in that direction. If you lose control of buoyancy and your ascent is uncontrolled, you can slow your rate of ascent by **flaring**—arching your back, extending your arms and legs, and positioning your fins parallel to the surface. Flaring (shown in figure 6.31) is the method recommended to slow a buoyant ascent.

Unless you care for your BC inflator carefully and have it serviced annually, the inflator valve will eventually stick. If your low-pressure inflator sticks in the open position, you should first hold your BC deflator valve in the open position. Modern BCs vent air faster than the low-pressure inflator admits air. If the inflator valve remains stuck, disconnect the low-pressure hose. If an uncontrolled ascent results, flare to slow your rate of ascent.

Loss of Air Supply

You are unlikely to have air supply difficulties if you have your regulator serviced annually, if you maintain your regulator properly, and if you monitor your SPG. Potential problems include a regulator that free-flows, low air pressure, and no air to breathe. Divers have ways to deal with each of these difficulties.



Figure 6.31 Flaring is an excellent way to slow a rapid ascent.

Sand, dirt, vomit, and freezing can cause regulator free-flow. If free-flow occurs, your best course of action is to switch to your extra second stage. You could also use your buddy's extra second stage. If there is no source of air except the regulator that is free-flowing, you can breathe from it by pressing your lips lightly against the mouthpiece, taking the air you need, and allowing the excess air to escape. Look down while you breathe from the regulator to keep the escaping air from causing your mask to leak.

You are supposed to end a dive with at least 500 psi (34 atm) of air in your tank. If you are inattentive and breathe nearly all the air from your cylinder while diving, it will become difficult to get air from your regulator. Divers often refer to this situation as being "out of air," but, in reality, they are out of air only at the depth at which breathing is difficult. As you ascend, the lower ambient pressure allows you to obtain additional air from your tank. When breathing becomes difficult and your tank is nearly empty, you should use your buddy's alternate air source (AAS) or ascend while continuing to breathe shallowly through your regulator.

In the rare event that you should completely lose your primary source of air while underwater, you have five ascent options. Figure 6.32 shows the order of preference of these options.


Emergency ascent option hierarchy
5 Make a buoyant emergency ascent (BEA) if the depth is 50 ft (15 m) or greater.
4 Make an emergency swimming ascent (ESA) if depth is less than 50 ft (15 m).
3 Buddy-breathe (only if both divers are trained).
2 Breathe from buddy's alternate air source (AAS).
1 Breathe from a backup scuba unit.

Figure 6.32 Loss-of-air options.

An extra-second-stage-assisted ascent closely approximates a normal ascent. You ascend while breathing from your buddy's extra second stage. When you require air underwater, get your buddy's attention and give the signals for "out of air" and "give me air," if possible. If your buddy's extra second stage and primary second stage are similar, your buddy will hand you the extra second stage, or you may take it. If your buddy's extra second stage is integrated into the BC low-pressure inflator, your buddy will hand you the primary second stage and breathe from the integrated second stage. If you cannot get your buddy's attention, take the extra second stage, begin breathing, and then signal your buddy that you have no air. After you establish a breathing rhythm, grasp each other's right forearm or BC and ascend normally (see figure 6.33).

An emergency swimming ascent (ESA) is a scuba ascent you do using only the air in your lungs. The ascent rate of an ESA is faster than a normal ascent, but it is not rapid. Retain your regulator in your mouth, and try to breathe from it from time to time. Do not hold your breath or you risk a lung overexpansion injury. If you exhale too much air, you will have a strong urge to inhale. The key to a successful ESA is to exhale enough air that your lungs remain at a comfortable volume. When you do an ESA correctly, you can ascend 50 feet (15 m) easily without an overwhelming desire for air. If the depth is over 50 feet, discard your weights to initiate a buoyant emergency ascent (BEA). Swim



Figure 6.33 Air sharing involves cooperation and coordination with your buddy.

for the first portion of the ascent, but allow yourself to drift up when buoyancy can replace swimming. Flare during the last 15 feet (4.6 m) of a BEA, and keep your lungs at a comfortable—but not maximum—volume.

Buddy breathing—the sharing of a single regulator second stage by two divers—is not a desirable loss-of-air option because it jeopardizes the safety of two people. You and your buddy should practice buddy breathing at the surface before beginning a dive if buddy breathing is a loss-of-air option for the dive. Not all divers are trained to buddy-breathe, and buddy breathing attempted by two divers who are not proficient with the skill can result in disaster. However, those who are proficient buddy breathers can make a loss-of-air situation a mere nuisance.

Initiate buddy breathing with the “out-of-air” signal followed by the signal for “give me air.” Your buddy holds the regulator second stage in the right hand and grasps your shoulder strap with the left hand. Your buddy extends the second stage toward you and holds it in such a way that you have access to the purge. You grasp your buddy’s wrist (not the regulator) with your left hand and grasp your buddy’s shoulder strap with your right hand. Guide the second stage to your mouth and push your lips against the mouthpiece to make a seal instead of inserting the mouthpiece into your mouth. By not putting the mouthpiece into your mouth to breathe, you can exchange the regulator quickly and reduce mask leakage caused by facial movements. Take several quick breaths initially; then pass the regulator back to your buddy. Exhale a small amount of air continuously when you are not breathing from the regulator. The exhalation helps prevent a lung overexpansion injury during ascent. After the initial contact, you and your buddy each take two breaths before passing the regulator. Do not inhale fully when buddy breathing because full breaths can cause buoyancy problems or lung injuries. A medium inhalation is adequate because you receive air every few seconds. You should exhale fully after each first breath that you take. The complete exhalation helps expel carbon dioxide and reduces your urge to breathe.

As soon as you and your buddy establish a breathing rhythm, you should swim to the surface, holding on to each other throughout the ascent. Blow bubbles continuously when the regulator is not in your mouth. Remember to control your buoyancy.

Skills for loss-of-air situations require proficiency, so they must be learned well and renewed periodically. Discuss the procedures for a loss-of-air situation with your buddy, and agree on the options you will use. You should both be familiar with the signals, positions, and techniques.

Assisting Your Buddy

You have read about many ways to assist your buddy and how your buddy can assist you, so you should realize the importance of the buddy system while diving.

In addition to helping your buddy handle entanglements, cramps, equipment problems, and loss-of-air situations, you may need to provide assistance if your buddy is incapacitated from exhaustion, illness, or injury.

A buddy who becomes agitated at the surface needs assistance in regaining control. Help such a buddy establish buoyancy, calm down, and breathe slowly and deeply. When the situation is under control, you may be able to help your buddy resolve the difficulty that caused the agitation.

If your buddy becomes exhausted, provide assistance at the surface with a biceps push, a fin push, or a do-si-do (arm-under-arm) push. The three types of pushes are illustrated in figure 6.34. Use the biceps push when your buddy can help, and use the fin push when your buddy is too exhausted to help at all. Monitor your buddy and offer encouragement while you provide assistance. (Note: Scuba rescues require techniques different from surface assistance.)



Figure 6.34 Providing assistance to an exhausted buddy using the (*a*) biceps push, (*b*) fin push, and (*c*) do-si-do push.

Managing Emergencies

Diving accidents occur when divers do not exercise good judgment or when they fail to follow recommended practices. If you do what you are supposed to do, the chances of a diving accident are extremely small. But you may have to render aid to someone else who violates safety rules. This section identifies the aid you should be capable of providing.

Training and Preparation

Three types of emergency preparedness training are recommended for all divers: first aid, cardiopulmonary resuscitation (CPR), and diving rescue techniques. You can get first aid and CPR training from various public service organizations. You'll learn some diving rescue techniques in your entry-level course, but you should also complete a rescue specialty course.

Emergency preparedness includes having emergency equipment and information available. The emergency equipment available at a dive site should include these items:

- Diving first aid kit (see the checklist of kit items in chapter 4)
- Oxygen delivery system
- Blanket (if appropriate)
- Drinking water

You may not have all of the emergency equipment yourself, but you can determine whether it is available aboard a boat or as part of an organized dive.

Have a means of communication—a telephone, cellular phone, CB radio, or marine radio—to summon assistance. Have contact information for local emergency medical assistance and for the emergency treatment of divers at the dive site. Have phone numbers and radio frequencies for local emergency support services. Examples of numbers to have include the Coast Guard, paramedics, hospital, ambulance, police or sheriff's office, recompression facility, and the Divers Alert Network (DAN). The Divers Alert Network has a 24-hour emergency number 919-684-8111 to assist with the coordination of responses to diving accidents.

Scuba Lifesaving

The principal elements of scuba lifesaving are cognizance, assessment, rescue, and evacuation (CARE). Cognizance is the ability to detect signs that identify or predict an accident. Trained and experienced divers can recognize situations that can lead to accidents before divers enter the water, when they enter the water, at the surface, during descents, underwater, during ascents, and during exits. As your experience increases, you will become more cognizant of potential difficulties.

Assessment is an ongoing evaluation of various factors that can affect a lifesaving situation. Rescuers need to consider their own ability to rescue the victim, the victim's condition, the environmental conditions, the equipment available, and additional resources.

Rescue techniques include approaches, extensions, throws, assists, establishing buoyancy, defenses, towing, deep-water rescue breathing, equipment removal, and removing the victim from the water. The ability to rescue both conscious and unconscious divers at the surface and underwater is an important skill to develop; you should take a scuba lifesaving or rescue specialty course as soon as possible after completing basic scuba training.

An unconscious diver underwater can drown unless rescued immediately. Illness, drugs, and blows to the head can cause loss of consciousness. If a diver loses consciousness underwater, make the diver buoyant and get her to the surface immediately. You do not need to concern yourself about expanding air if the diver is not breathing because an unconscious person exhales automatically regardless of head position. Do not concern yourself about the diver's decompression status; she can be treated for DCS but will die after about four minutes without air. Do not jeopardize your own safety when attempting to rescue another diver.

A diver who is not breathing needs air quickly and must get it at the surface. This is where your CPR skills and diving rescue techniques are invaluable. Open the victim's airway. Often this is all an unconscious person needs to be able to breathe. To open the airway, tilt the head and lift the chin. Turn the person's head to the side to drain water from the mouth and throat. Vomiting is common, so be prepared for it. Clear vomit from the victim's mouth and throat at once or the person may inhale it and choke.

A person who is not breathing after you have opened the airway requires rescue breathing and medical assistance. Shout for help. If you can remove the victim from the water quickly, you should do so. If removal will be delayed by even a couple of minutes, begin rescue breathing while you remain in the water. Keep the victim's airway open and lightly pinch the victim's nostrils to seal them. Seal your mouth over the other person's mouth and fill the person's lungs with air until the chest rises gently. Give the victim one breath every 5 seconds or two breaths every 10 seconds while swimming to safety. A gurgling sound from the victim indicates water or vomit in the airway. Roll the person to the side and drain the fluid before continuing rescue breathing. The preferred method of in-water artificial respiration involves using a rescue-breathing mask, which you can carry in the pocket of your BC. Figure 6.35 shows a person doing rescue breathing using such a mask.

You will probably not be able to detect a pulse in the water, so don't bother trying. You cannot administer CPR in the water; you must remove the victim from the water and position her on a firm surface.

Evacuation is the final element of scuba lifesaving. Evacuation procedures include accident preparedness, communications, and transportation options. Advance planning is essential to evacuate an injured diver to a medical facility.

First Aid

Some aspects of diving first aid are not taught in standard first



Figure 6.35 Rescue breathing with a breathing mask.

aid courses. This section touches on those aspects, but you need the additional study and training that you can get in rescue specialty and oxygen administration courses.

Nothing is more important than attending to basic life support: airway, breathing, and circulation. The next priority for any serious diving injury is treatment for shock. Lay an injured diver who is breathing on his side, keep the person warm (but avoid overheating), and administer sips of water if he is conscious. If you suspect an air embolism, DCS, or near drowning, have the person breathe oxygen in the highest possible concentration. Keep any diver who has lost consciousness or who has symptoms of DCS lying down until he can be evaluated at a medical facility. Monitor the victim continuously.

You should be able to recognize signs and symptoms that indicate a serious diving illness. The following signs and symptoms indicate an injury that requires the prompt administration of oxygen and medical treatment:

- Confusion
- Seizure
- Loss of consciousness
- Nausea or vomiting
- Shortness of breath
- Sudden, extreme weakness
- Numbness or a pins-and-needles sensation
- Inability to do simple motor skills
- Paralysis
- Unequal pupils

Venomous marine animals may be encountered in some parts of the world. A few venomous animals can inflict life-threatening wounds (see chapter 5). The wounds can cause pain, weakness, nausea, shock, mental confusion, paralysis, convulsions, depression, arrest of breathing, and even cardiac arrest. Fortunately, such wounds are rare.

Venomous injuries are either punctures or stings. First aid for venomous puncture wounds involves removing all foreign matter from the wound, applying hot packs to the injured area for half an hour, and keeping the injured area below the level of the heart. The injured person should obtain medical attention.

First aid for a venomous sting includes killing any stinging cells that are in contact with the skin, removing any residue, cleansing the area, applying an analgesic ointment for pain relief, and seeking medical attention. Vinegar is a good solution to apply to all stings to neutralize stinging cells initially.

You may not recall the appropriate first aid procedures in the event of an accident; therefore, you should bring along a diving first aid book to help you identify an injury and administer the appropriate first aid. A wilderness first aid book is also strongly recommended because diving often occurs in remote areas.

Managing Accidents

If a serious diving accident occurs, and no supervisory personnel are available to take charge, you have to manage the situation to the best of your ability. Summon help, but do not leave a seriously injured diver unattended. Enlist the aid of others. Try to locate the injured diver’s identification and medical information. Write down what happened, as well as the person’s dive profile,

SCUBA WISE

People are creatures of habit, and habits are the result of repetition. If you repeat an action correctly enough times, you form a good habit. On the other hand, if you repeat an action incorrectly enough times, you create a bad habit. Divers need good habits to avoid accidents, but sometimes they fail to take the time to develop them. I often watch divers on charter boats and at dive sites as they prepare to dive. I notice that some fail to inspect their equipment adequately, some fail to plan their dive properly, and some fail to follow the practices outlined in this chapter. They usually know what to do, but because they have bypassed many steps every time they go diving, they have a habit of skipping important items. How safe is a pilot if he ignores the preflight checklist? Taking the correct action requires concentration initially, but when repeated until the action becomes a habit, the process becomes automatic. People can make complex processes simple by repeating them. When a skill is executed properly every time, it not only becomes habit but also is easier to recall when you really need it, such as in an emergency. I strongly encourage you to take the time to form good diving habits. If you do, I assure you that the odds of being injured are extremely small.

symptoms, dive times, and so forth. Pin the information in a conspicuous place, and send it with the injured diver to the medical facility. Accompany the diver to the medical facility, if possible.

Summary

The skills of diving range from simple skin diving procedures to complex scuba skills to problem management. You need to learn the skills correctly the first time, practice them until you can do them easily, and renew them frequently to stay proficient. You also need to be trained and prepared to handle a diving emergency. As mentioned previously, visualization of skills can help you develop skills. This is especially important for problem-management skills. Some problems are not common, and you may never encounter them; but you need to be prepared to manage them. If you visualize a problem vividly in your mind, you will be able to remain relatively calm when that problem occurs because you will know what actions to take. Knowing what to do helps you remain relatively calm, which allows you to think and to better manage your situation.

Application-of-Knowledge (AOK) Questions

1. What are ways in which you can control buoyancy?
2. What do you need to remember to do while ascending from a scuba dive?
3. What can you do to minimize the chances of becoming separated from your buddy while scuba diving?
4. The inflator valve on your BC sticks when you open it to add air. What actions can you take to prevent a rapid ascent?
5. What should you do if your regulator begins free flowing while you are underwater and cannot be stopped?
6. When preparing to exit the water into a small boat, what is the correct order for the removal of your equipment?
7. While swimming against a current at the bottom in 40 feet (12.2 m) of water, you begin to experience air starvation. What is the proper way to manage this problem?
8. If you become entangled underwater, what can you do to get free of the entanglement?

Sunset at Grand Cayman

7

Dive Planning

Dive In and Discover

By the end of this chapter, you will be able to do the following:

- List at least nine factors to consider in dive planning.
- Explain the why, who, where, when, how, and what of advance planning.
- Explain the on-site planning procedures for a dive.
- List at least five methods of obtaining area orientations for scuba diving.
- Use dive tables to plan repetitive dives that do not require decompression.
- Explain the planning procedures for cold or strenuous dives, variations in ascent rate, multilevel dives, omitted decompression, diving after required decompression, going to altitude after diving, exceeding maximum time when doing precautionary decompression, and a repetitive-dive residual nitrogen time that exceeds the absolute bottom time of the previous dive.
- Define the terms *residual nitrogen*, *repetitive dive*, *surface interval time*, *maximum bottom time*, *decompression stop*, *repetitive group*, *safety stop*, *residual nitrogen time*, *actual bottom time*, *total bottom time*, *emergency decompression*, *no-decompression-stop limit*, *dive profile*, *step dive*, *spike dive*, *multilevel dive profile*, *sawtooth dive profile*, *scrolling*, and *contingency plan*.
- Explain contingency planning for scuba diving.
- Compare the advantages and disadvantages of dive computers.

In this chapter, you will learn about all phases of dive planning: advance planning, short-term planning, on-site planning, and postdive planning. You will also learn about area orientations and how to do dive profile planning. An essential part of dive planning is scheduling your time and depth to avoid DCS (decompression sickness).

A well-planned dive increases enjoyment and satisfaction and decreases the risk of injury. A poorly planned dive can result in disappointment, embarrassment, and discomfort. By the end of this chapter, you will understand the significance of the expression "Plan your dive, and then dive your plan."

Dive-Planning Factors

Many factors affect your plans for a dive or a diving trip. Keep the following considerations in mind when you are looking ahead to a dive outing:

- Health and fitness are important. Illnesses, required medications, and recent operations probably disqualify you for diving. If your health is not normal, consult a diving physician. If there is any doubt about your physical condition, refrain from diving until you are in good health. If you are prone to motion sickness, take steps to try to prevent it.
- Climate is a big factor affecting dive planning. If you dive close to where you live, dive planning is easier than if you intend to dive thousands of miles away. A difference in climate usually means a big difference in diving conditions, which means a difference in your equipment requirements.
- The distance you travel to a diving destination affects your planning. If you travel far to reach the destination, allow a day to rest and recover from travel before you dive. After even one day of repetitive diving, wait one full day before flying home.
- Weather affects diving conditions significantly. Storms and sudden changes in the weather can make diving dangerous. Know the weather forecast, and reschedule your dive if poor weather is predicted. Know the expected wind speed, air temperature, and water conditions.
- Seasonal changes affect water movement, water visibility, air and water temperatures, entry and exit areas, and the presence of certain types of animals. You

First you learn the theory of diving, then the skills of diving, and then you apply what you have learned. Your training objective is to qualify to dive without supervision, which involves planning your underwater excursions.

Fish in a Red Sea coral cave

should know what to expect at a dive site at different times of the year. It helps to know the visibility, water temperatures, tides, surf, surge, currents, bottom composition, silt conditions, plants, and animals.

You need to be physically and mentally fit for diving. Fitness for diving implies that you are well rested, are well nourished, have the physical strength and stamina to meet the requirements of the environment and the activity, are qualified for the activity, are not apprehensive about your plans, are not goaded into doing something you are not prepared to do, and do not allow pride to affect good judgment.

Your objective for the dive affects your planning. Different diving activities require different plans and different equipment. The planning of an underwater photography dive is not the same as the planning of a dive where you intend to hunt for game.

You must know and observe laws, regulations, and customs. Some areas have laws that require the use of a dive flag. Obey fish and game regulations. Some diving professionals discourage the taking of any living thing in an area. You need to know the behavior expected of you. Knowing the expectations in advance can help you avoid being embarrassed at the dive site.

Etiquette is important. Will early-morning diving activities be offensive to residents near the dive site? Will the parking of vehicles at a site irritate people? Be considerate of others who may be in the area where you intend to dive, including those who are fishing nearby. Consider the impact of noise, changing clothes, and dive site access. Then make your plans using good etiquette.

Advance Planning and Preparation

The first phase of dive planning is the determination of why, who, where, when, how, and what.

Why?	Determine the objective of the dive. What do you want to do? Take photos? Explore? Look for artifacts?
Who?	Determine with whom you want to dive. Select a buddy who is interested in your dive objective.
Where?	Determine a primary and an alternative site. If conditions at the primary site are unfavorable, go to the alternate site.
When?	Determine the best time to dive. The water at most areas is usually calmer in the morning than it is in the afternoon. Tidal currents and height may affect the best time to dive.
How?	Decide how to reach the dive site. Who will drive? What are the directions?
What?	Determine what equipment is needed for the dive. Who will bring the float and flag? How many tanks do you need? Are there any special needs for the intended activity?

Advance preparation can include

- making reservations,
- paying deposits,
- buying or renting equipment,
- having equipment serviced or repaired,
- getting tanks filled,
- obtaining a fishing license or permit,
- preparing equipment for photography, and
- obtaining emergency contact information.

Fresh water diving at Lake Mead, Nevada

Your preparations will usually include a trip to your local dive facility. Inspect your equipment before you go. You may discover a needed repair that requires some time to complete. Identify your equipment needs early.

Short-Term Planning and Preparation

The day and evening before you intend to go diving, you need to take three actions. First, you should find out the weather forecast and current water conditions so you can determine if conditions will be acceptable for your diving activities. Call your dive buddy to discuss and confirm your plans. Last-minute revisions, such as going to the alternative site, may be necessary. If you anticipate poor diving or weather conditions, reschedule the dive.

The second step of short-term preparation is packing your diving equipment and your personal items. (See chapter 4 for an equipment checklist.)

The third step of short-term planning is to write down your dive plans and schedule. Leave this information with a friend. Instruct your friend to notify the authorities if you fail to return by a certain time.

On-Site Planning and Preparation

When you and your buddy arrive at the dive site, you must determine whether the conditions are acceptable for diving. If not, go to an alternative site. If the conditions at the alternative site are also unacceptable, abort the dive.

An important step in the assessment of a dive site is the estimation of the current. Look for telltale signs such as kelp bent over from water movement, a wake around the anchor line or behind an anchored boat, or objects drifting on the surface. Determine the velocity of moving water by measuring how long it takes a floating object to move a known distance, such as the length of your boat. When an object moves 100 feet (30 m) in one minute, the speed of the object is approximately 1 knot (1.15 miles or 1.85 km per hour). When a current exceeds about 1/3 knot (0.4 miles or 0.6 km per hour), you must heed it because you can swim at a speed of only about 3/4 knot (0.86 miles or 1.4 km per hour). Plan the dive so that the current assists you in swimming to your exit point at the end of the dive. Figure 7.1 includes a table that can help you estimate current velocity.

If the diving conditions are favorable, you should then determine the diving area. Select the entry and exit areas for the dive, and discuss the entry and exit procedures. Agree on the course to be followed during the dive. Agree on time, minimum air pressure, and landmarks for changes in direction. You and your buddy should know in advance approximately where you will be at any time during the dive.

An important part of your planning is discussing and agreeing on the procedures for the buddy system. Decide who is in charge of the team, where you will position yourselves relative to each other, how you will move (steadily or start and stop), and what reunion procedures you will follow in the event of separation. Remember that communication is much easier on land than it is underwater, so take advantage of the opportunity you have to communicate and coordinate while preparing for a dive.



Measure how long it takes a floating object to travel 100 feet (30 meters). If an object travels 20 feet (6 meters) in 12 seconds, it travels 100 feet (30 meters) in 1 minute.

Current velocity table
(time to travel 100 feet or 30 meters)

Time (seconds)	Speed (knots)	Time (seconds)	Speed (knots)
5	12.0	95	0.62
10	6.0	100	0.59
20	3.0	110	0.54
30	2.0	120	0.49
40	1.5	130	0.46
50	1.2	140	0.42
60	1.0	150	0.39
70	0.84	160	0.37
80	0.74	170	0.35
90	0.66	180	0.33

Figure 7.1 **You can estimate the velocity of a current if you time how long it takes a floating object to move the length of your boat.**

Always review your plans for emergencies. Agree on air-sharing procedures. Discuss what to do in the event of a serious diving emergency. Know where, how, and whom to call for help. Make sure you both have access to a first aid kit and other emergency equipment. A few minutes spent coordinating procedures before an emergency can save precious seconds if an accident occurs.

Scuba diving requires dive profile planning. You and your buddy need to agree on the maximum time and depth for your dive. You must limit time and depth to avoid decompression illness. Dive profile planning is discussed later in this chapter.

Area Orientations

You should recognize the importance of learning about a dive site before diving there. Because orientation is vital and because you want to be a responsible diver, you need to learn how to obtain orientations. Area orientations can be formal or informal. A formal orientation is provided as a service by a diving professional. The professional will tell you what to look for and what to look out for in the area and will lead you on a dive. A professional dive guide provides suggestions and points out items of interest and potential hazards. When you have completed a formal orientation, ask the professional to sign and stamp your logbook. A continuing education dive course is another excellent form of formal orientation to a new area.

Formal orientations are ideal, but if you cannot arrange to have a professional introduce you to a new region, consider some or all of the following options for an informal orientation:

- Read books, articles, and brochures about diving in the area. Learn as much about an area as you can before you go there.
- Write to dive stores in the region where you intend to dive. Ask if you can participate in a dive class session for your orientation to the area.
- Write to dive clubs in a region where you intend to dive. Ask if you can participate in a club-sponsored dive when you are in the area. Ask for contact information for several club members who dive regularly and may be willing to allow you to go diving with them.
- When you arrive in a new area, find local dive sites and visit them when divers are likely to be there. Ask the divers about the sites while they are preparing to dive or after they exit from a dive. If you have your equipment ready, you may be able to accompany them on a dive. Make sure they have experience in diving at the site.

SCUBA WISE

Having reviewed dive accident reports for many years, I have found that failure to adequately plan or to carry out the plan for a dive is a common cause of accidents and injuries. I have been able to avoid serious injury during decades of diving. However, I have had some bad experiences. These experiences occurred when I failed to plan adequately, when I attempted activities without first completing training for the activity, or when I did not have adequate knowledge of a new dive site.

I dived from shore in California on a beach with a steep incline without taking the time to research the dive. I was used to donning my fins, wading into the water, and swimming beneath the oncoming waves. When I attempted this procedure on this type of beach, I found that there was a trough created by plunging waves, and that the trough was a dropoff. The trough is also where the waves break suddenly and violently. As I waded into the water, I lost my footing at the trough at the same time that a large breaker suddenly formed and pounded me into the trough. I managed to kick past the trough before the next wave hit, but I was humbled by the experience. A key part of dive planning is to understand the terrain and learn the local procedures. After the dive, I watched a local diver literally run into the water after a wave broke, jump over the trough, turn onto his back, pull on one fin, and kick beyond the area where the waves broke. I have used that technique on steep beaches ever since that day when the plunging surf taught me a lesson. Avoid surprises that could be dangerous by learning about any new location before diving there.

- Purchase a space on a diving charter boat. When you board the vessel, tell the crew you are new to the area. Ask for advice about diving procedures, and ask to be introduced to an experienced diver who can provide additional information.

When you dive with local divers, allow them to go first. Do as they say and do as they do. Procedures vary from region to region. A procedure you use in your area may be inappropriate in a different area. For example, in your normal diving environment, you may be able to enter the water from a boat in a current without holding on to a line. But if you tried to do so in a different area, you might be swept away at once. Be humble, listen to others, and follow their example to avoid embarrassment.

Dive Profile Planning

There are limits on how long you may remain at various depths. The amount of nitrogen absorbed by your body determines the limits. You need to be aware of the effects of **residual nitrogen**, which is nitrogen remaining in your system from a dive made within the past 12 hours. Whether you do one dive or a series of dives, it takes time to eliminate nitrogen from your body. If you dive again before the excess nitrogen has had time to outgas, you add to the nitrogen already in your body, and you reach critical nitrogen levels faster than if you had not already absorbed excess nitrogen. A **repetitive dive** is any dive made within 6 to 24 hours (depending on the dive-planning device) of a previous dive. Figure 7.2 shows how the amount of residual nitrogen in the body builds from repetitive dives. A **rest stop**—a precautionary decompression stop during ascent—reduces the risk of decompression illness.



A—Normal amount of nitrogen in body
B—Amount of nitrogen in body after first dive
C—Amount of nitrogen in body after first surface interval
D—Amount of nitrogen in body after second dive
E—Amount of nitrogen in body after second surface interval
F—Amount of nitrogen after third dive

Figure 7.2 If you make a repetitive dive before allowing the residual nitrogen to leave your body, the nitrogen continues to accumulate.

Decompression experts use complex mathematical calculations and field testing to establish time limits for various depths for single and repetitive dives. The time limits are published in tables and programmed into calculators and dive computers. You need to know how to use these dive-planning devices to plan your dive profile so that you can minimize the risk of decompression illness.

No dive-planning device can guarantee that you will not develop decompression illness. Dive tables, calculators, and computers provide information based on statistics acquired through testing. If a diver adheres to the profile limits of a device, the statistical probability that the diver will develop decompression illness is small. The devices assume that you are in good health, that you do not get cold during the dive, that you do not exert strenuously, and that you ascend at the correct rate.

If you dive to the maximum time limits indicated by any dive-planning device, you increase the likelihood of decompression illness. Reducing your exposure to pressure reduces the likelihood of decompression illness.

Dive Tables

The U.S. Navy (USN) developed tables for dive planning. The recreational diving community adopted the military tables in 1980 and has used modified versions successfully. Although the tables were designed for military diving rather than recreational diving, many decompression experts still consider the USN dive tables—with reduced maximum dive times—appropriate tables for recreational use. New Doppler-tested dive tables developed by the USN are the basis for the dive tables presented in this chapter.

The USN tables use compartments with half-times of 5 minutes, 10 minutes, 20 minutes, 40 minutes, 80 minutes, and 120 minutes. The amount of nitrogen remaining in the 120-minute (2-hour) compartment determines the **repetitive group designations** of the tables, which are represented by letters. Because outgassing of a compartment takes six half-times, you can see why the USN tables define a repetitive dive as any dive within 12 hours (6 × 2 hours) of a previous dive.

The tables include four sets of dive tables:

A. Total bottom timetable
B. Surface interval timetable
C. Residual nitrogen timetable
D. Decompression timetable

Dive Table Modifications

Diving organizations and manufacturers have modified the dive tables to make them more appropriate for recreational diving. Here are some typical differences between standard dive tables and the modified dive tables presented in this chapter:

- Reduced time limits—Dive-planning devices today include maximum time limits that are less than the no-decompression-stop limits of the USN dive tables.
- Reduced depth limits—The USN dive tables provide dive-planning information for depths to 190 feet (58 m). The recommended maximum depth limit for recreational diving is 100 feet (30.5 m). New divers should limit diving to

SCUBA EDUCATORS INTERNATIONAL®

PDIC INTERNATIONAL®

READ BEFORE PLANNING A DIVE

SEI & PDIC International Air Diving Tables are designed to enhance diver safety and assist in dive planning. The Air Diving Tables should be used only by persons properly trained in their use. SEI & PDIC International Air Diving Tables provide a conservative safety margin to help avoid decompression sickness. Use of these Air Diving Tables is not guaranteed to eliminate the possibility of decompression sickness. To gain the greatest conservative margin from these tables, divers must carefully plan their dives in accordance with the No-Decompression Stop Limits and ascend no faster than 30 feet per minute with appropriate safety stops. Do not exceed the No-Decompression Stop Limits. Do not dive deeper than 100 feet. Do not use these tables for high altitude diving without calculating an adjustment for high altitude. Susceptibility to decompression sickness varies in accordance with a diver's physical wellness and readiness, environmental conditions, ascent rates, and many other situations and conditions.

© 2009 Scuba Educators International Revised 10-2013

AIR DIVING TABLES

Table A

TOTAL BOTTOM TIME (TBT) IN MINUTES

START HERE

DEPTH Meters	DEPTH Feet	No-Decompression Stop Limit	A	B	C	D	E	F	G	H	I	J	K	L	M
3	**10**		57	101	158	245	426								
4.6	**15**		36	60	88	121	163	217	297	449					
6.1	**20**		26	43	61	82	106	133	165	205	256	330	461		
7.6	**25**	**354**	20	33	47	62	78	97	117	140	166	198	236	285	354
9.1	**30**	**223**	17	27	38	50	62	76	91	107	125	145	167	193	223
10.7	**35**	**168**	14	23	32	42	52	63	74	87	100	115	131	148	168
12.2	**40**	**135**	12	20	27	36	44	53	63	73	84	95	108	121	135
13.7	**45**	**102**	11	17	24	31	39	46	55	63	72	82	92	102	
15.2	**50**	**80**	9	15	21	28	34	41	48	56	63	71	80		
16.7	**55**	**63**	8	14	19	25	31	37	43	50	56	63			
18.3	**60**	**51**	7	12	17	22	28	33	39	45	51				
21.3	**70**	**42**	6	10	14	19	23	28	32	37	42				
24.4	**80**	**32**	5	9	12	16	20	24	28	32					
27.4	**90**	**24**	4	7	11	14	17	21	24						
30.5	**100**	**18**	4	6	9	12	15	18							
33.5	**110**	**16**	3	6	8	11	14	16							
36.6	**120**	**10**	3	5	7	10									
39.6	**130**	**6**	2	4	6										

Repetitive Group Designation

Table C

RESIDUAL NITROGEN TIME (RNT) IN MINUTES

Repetitive Dive Depth in Feet/Meters

	35 11	**40** 12	**45** 14	**50** 15	**55** 17	**60** 18	**70** 21	**80** 24	**90** 27	**100** 30	**110** 33	**120** 36	**130** 39
A	**15** 153	**13** 122	**12** 90	**11** 69	**10** 53	**9** 42	**8** 34	**7** 25	**6** 18	**5** 13	**5** 11	**5** 5	**4** 2
B	**24** 144	**21** 114	**18** 84	**17** 63	**15** 48	**14** 37	**12** 30	**10** 22	**9** 15	**8** 10	**8** 8	**7** 3	6
C	**33** 135	**29** 106	**25** 77	**23** 57	**20** 43	**19** 32	**16** 26	**14** 18	**12** 12	**11** 7	**10** 6	**9** 1	9
D	**43** 125	**37** 98	**32** 70	**29** 51	**26** 37	**24** 27	**20** 22	**18** 14	**16** 8	**14** 4	**13** 3	12	11
E	**53** 115	**45** 90	**40** 62	**35** 45	**32** 31	**29** 22	**25** 17	**22** 10	**19** 5	**17** 1	16	14	13
F	**64** 104	**55** 80	**48** 54	**42** 38	**38** 25	**35** 16	**29** 13	**25** 7	**22** 2	20	18	17	15
G	**75** 93	**64** 71	**56** 46	**49** 31	**44** 19	**40** 11	**34** 8	**29** 3	26	23	21	19	18
H	**88** 80	**74** 61	**64** 38	**57** 23	**51** 12	**46** 5	**39** 3	33	29	26	24	22	20
I	**101** 67	**85** 50	**73** 29	**65** 15	**58** 5	52	44	38	33	30	27	24	22
J	**116** 52	**97** 38	**83** 19	**73** 7	65	58	49	42	37	33	30	27	25
K	**132** 36	**109** 26	**93** 9	81	72	65	54	46	41	36	33	30	27
L	**149** 19	**122** 13	104	90	80	72	59	51	44	40	36	32	30
M	169	136	115	99	88	79	65	55	48	43	39	35	32

Note: For repetitive dives less than 35 feet use the RNT values for 35 feet

Table B

SURFACE INTERVAL TIME (SIT) IN HOURS AND MINUTES

New Repetitive Group	A	B	C	D	E	F	G	H	I	J	K	L	M
A	2:20 0:10	3:36 1:17	4:31 2:12	5:23 3:04	6:15 3:56	7:08 4:49	8:00 5:41	8:52 6:33	9:44 7:25	10:36 8:17	11:29 9:10	12:21 10:02	13:13 10:54
B		1:16 0:10	2:11 0:56	3:03 1:48	3:55 2:40	4:48 3:32	5:40 4:24	6:32 5:17	7:24 6:09	8:16 7:01	9:09 7:53	10:01 8:45	10:53 9:38
C			0:55 0:10	1:47 0:53	2:39 1:45	3:31 2:38	4:23 3:30	5:16 4:22	6:08 5:14	7:00 6:07	7:52 6:59	8:44 7:51	9:37 8:43
D				0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30	5:13 4:22	6:06 5:14	6:58 6:07	7:50 6:59	8:42 7:51
E					0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30	5:13 4:22	6:06 5:14	6:58 6:07	7:50 6:59
F						0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30	5:13 4:22	6:06 5:14	6:58 6:07
G							0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30	5:13 4:22	6:06 5:14
H								0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30	5:13 4:22
I									0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30
J										0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38
K											0:52 0:10	1:44 0:53	2:37 1:45
L												0:52 0:10	1:44 0:53
M													0:52 0:10

37 — Minutes of Residual Nitrogen (RNT) Added to Actual Bottom Time to Compute TOTAL BOTTOM Time

98 — Calculated Maximum ACTUAL BOTTOM TIME (ABT) in minutes. If This Number is Exceeded, a Decompression Stop is Required

SEI & PDIC INTERNATIONAL ACCEPTS NO RESPONSIBILITY FOR ACCIDENTS ARISING FROM THE USE OF THESE TABLES

0:52 — Maximum Time For This Interval

0:10 — Minimum Time For This Interval

Courtesy of Scuba Educators International.

REPETITIVE DIVE PROFILES



DEFINITIONS

BOTTOM TIME (BT). The elapsed time in minutes, starts when the diver leaves the surface in descent and stops when the diver begins safety stop or surfaces (round up to next whole minute). On repetitive dives this is Actual Bottom Time (ABT).

DEPTH. The depth of a dive; use the maximum depth attained during the dive in feet or meters of seawater. When depth is not indicated on the table use the next greater depth available.

NO-DECOMPRESSION STOP LIMIT. The longest amount of time a diver can spend at depth without requiring a decompression stop. Table A lists these for all depths. For repetitive dives the Residual Nitrogen Time (RNT) must be added to the Bottom Time (BT) and the Total Bottom Time (TBT) must not exceed the No-Decompression Stop Limit.

REPETITIVE DIVE. Any dive conducted within the time period specified by the surface interval table (Table B) of a previous dive with a minimum surface interval of 10 minutes. For repetitive dives of less than 35 feet, use the RNT (Table C) values for 35 feet to calculate Total Bottom Time (TBT).

REPETITIVE GROUP DESIGNATION (RG). Letters that relate to the amount of residual nitrogen in a diver's tissues for the time specified in the Suface Interval Table.

RESIDUAL NITROGEN TIME (RNT). Located in Table C, an amount of time, in minutes, which must be added to the Bottom Time (BT) of a repetitive dive to calculate Total Bottom Time (TBT). Represents residual nitrogen still in a diver's tissues from previous dives.

SAFETY STOP. A 3 minute minimum safety stop at 15-25 feet is recommended at the end of all dives.

SURFACE INTERVAL TIME (SIT). Located in Table B, the elapsed time from when a diver surfaces following a dive to the time (next whole minute) that diver starts the descent of the next dive. SIT must be a minimum of 10 minutes.

TOTAL BOTTOM TIME (TBT). Calculated by adding the Bottom Time (BT) and the Residual Nitrogen Time (RNT). For times not indicated at a particular depth, use the next longer time available for that depth.

RULES

ASCENT RATE. Divers should ascend at 30 feet per minute or slower.

DIVES LESS THAN 25 FEET. Dives less than 25 feet do not have a specific No-Decompression Stop Limit. However, if conducted as repetitive dives, they must be calculated as a 35 foot dive for Residual Nitrogen Times (RNT), Table C.

EXCEEDING THE NO-DECOMPRESSION STOP LIMITS. If divers err and stay longer than the times allowed on the No-Decompression Stop Limit, Table A, the divers have exposed themselves to an increased decompression requirement and must refer to the Decompression Stops Table, Table D, for required decompression stops to complete the dive. Once on the surface these divers should not dive again for at least 12 hours or fly for at least 24 hours.

FLYING AFTER DIVING. The longer the surface interval before flying the less likely a diver will experience decompression sickness. A minimum surface interval of 12 hours is required before ascent to altitude in a pressurized aircraft (or a ground altitude of 1000 feet above sea level). Divers who plan to make multiple dives for several days or computer assisted dives should take extra precaution and wait an extended surface interval of greater than 12 hours before flying or ascending to altitude. Divers who have made dives requiring decompression stops should wait a minimum of 24 hours before flying or ascending to altitude.

HIGH ALTITUDE DIVING. These Air Diving Tables are not to be used for diving at altitudes greater than 1000 feet above sea level without calculating altitude adjustments.

ORDER OF DIVES. All repetitive dives should be conducted with each successive dive equal in depth or shallower than the previous dive.

SPORT DIVING MAXIMUM DEPTH. Sport divers should not exceed 100 feet of depth.

SPORT DIVING TIME LIMIT. On any dive the Total Bottom Time (TBT) should not exceed the No-Decompression Stop Limit. Dives requiring mandatory decompression stops should not be planned.

Table D

DECOMPRESSION STOPS TABLE

Depth Feet Meters	Bottom Time (min.)	Time to First Stop (min:sec)	Decompression Stops (min) @ 20ft.	Total Assent (min:sec)	Repetitive Group
40 12.2	135		0		M
	150	0.40	6	7:20	O
	160	0.40	14	15:20	Z
	170	0.40	21	22:20	Z
	180	0.40	27	28:20	Z
50 15.2	80		0		K
	90	1:00	2	3:40	M
	95	1:00	4	5:40	N
	100	1:00	8	9:40	O
	110	1:00	21	22:40	O
60 18.3	51		0		I
	60	1:20	2	4:00	L
	65	1:20	7	9:00	L
	70	1:20	14	16:00	N
	80	1:20	23	25:00	O
70 21.3	42		0		I
	50	1:40	9	11:20	L
	55	1:40	14	16:20	M
	60	1:40	24	26:20	N
	70	1:40	44	46:20	O
80 24.4	32		0		H
	35	2:00	1	3:40	J
	40	2:00	10	12:40	K
	45	2:00	17	19:40	M
	50	2:00	24	26:40	M
90 27.4	24		0		G
	30	2:20	4	7:00	J
	35	2:20	14	17:00	L
	40	2:20	23	26:00	M
	45	2:20	31	34:00	N
100 30.5	18		0		F
	25	2:40	3	6:20	J
	30	2:40	15	18:20	L
	35	2:40	26	29:20	M
	40	2:40	36	39:20	N
110 33.5	16		0		F
	20	3:00	3	6:40	I
	25	3:00	14	17:40	K
	30	3:00	27	30:40	M
	35	3:00	39	42:40	N
120 36.6	10		0		D
	15	3:20	2	6:00	H
	20	3:20	8	12:00	J
	25	3:20	24	28:00	L
	30	3:20	38	42:00	N
130 39.6	6		0		C
	10	3:40	1	5:20	G
	15	3:40	4	8:20	I
	20	3:40	17	21:20	K
	25	3:40	34	38:20	M

Courtesy of Scuba Educators International.

Dive Table Terms

Actual Bottom Time (ABT)—The elapsed time in minutes (rounded up to the next whole minute) from when a diver leaves the surface in descent until the diver begins a rest stop or surfaces.

No Decompression Stop Limit (NDSL)—The maximum time that a diver may stay at a specified depth (indicated in table A). For repetitive dives, the residual nitrogen time (RNT) from table C must be added to the actual bottom time (ABT) to obtain the total bottom time (TBT), which must not exceed the NDSL specified in table A. Table C also indicates the maximum ABT for various depth and repetitive group combinations that will prevent the TBT from exceeding the NDSL.

Repetitive Dive—Any dive conducted within 12 hours of a previous dive with a minimum 10-minute surface interval. For repetitive dives of less than 40 feet, use the 40-foot (12 m) values in table C (RNT table) to determine the TBT.

Repetitive Group Designation (RGD or RG)—A letter that indicates the amount of residual nitrogen in a diver's tissues for 12 hours after diving.

Residual Nitrogen Time (RNT)—An amount of time (in minutes) that must be added to the actual bottom time (ABT) of a repetitive dive to determine the total bottom time (TBT). RNT compensates for residual nitrogen remaining in a diver's tissues from previous dives.

Surface Interval Time (SIT)—The elapsed time (rounded up to the next whole minute) from when a diver surfaces after a dive to the time the diver begins the descent of a repetitive dive. The minimum SIT is 10 minutes.

Total Bottom Time (TBT)—The sum of ABT and RNT. For times not indicated at a particular depth, use the next longest time available for that depth.

depths of about 60 feet (18 m). Advanced divers qualify to dive to approximately 100 feet. Divers who complete a deep-diving specialty course qualify to dive to 130 feet (39 m). Technical divers qualify to dive at even greater depths. Depth in water is similar to speed on land. When you qualify for a driver's license, you may drive at speeds up to the legal limit. Driving at much higher speeds is hazardous and requires specialized training, special equipment, and controlled situations to minimize the risk of serious injury or death. Deep diving (beyond 100 feet) is similar to race car driving in many respects. Deep diving is a professional endeavor that unqualified recreational divers should not attempt.

- Revised **surface interval times**—In 1983, a USN study reported a number of errors in the surface interval timetable. The errors usually do not affect the type of diving that recreational divers do, but some modified versions of the tables include the corrections.

- Combined tables—Modified versions of the USN dive tables often combine information to make the tables easier to use. Tables may include the **total bottom time** (TBT) for repetitive dives along with the **residual nitrogen time** (RNT). Tables may include required decompression information to eliminate a separate decompression timetable.

Dive Table Use

In this section we'll take a closer look at some of the individual elements comprising the combined dive tables.

Table A provides the NDSL, without required decompression stops for various depths. This table also provides a letter designation for various dive profiles. The letter designation indicates the amount of excess nitrogen remaining in your body after a dive.

Table A

TOTAL BOTTOM TIME (TBT) IN MINUTES

START HERE

DEPTH Meters	DEPTH Feet	No-Decompression Stop Limit	A	B	C	D	E	F	G	H	I	J	K	L	M
3	**10**		57	101	158	245	426								
4.6	**15**		36	60	88	121	163	217	297	449					
6.1	**20**		26	43	61	82	106	133	165	205	256	330	461		
7.6	**25**	**354**	20	33	47	62	78	97	117	140	166	198	236	285	354
9.1	**30**	**223**	17	27	38	50	62	76	91	107	125	145	167	193	223
10.7	**35**	**168**	14	23	32	42	52	63	74	87	100	115	131	148	168
12.2	**40**	**135**	12	20	27	36	44	53	63	73	84	95	108	121	135
13.7	**45**	**102**	11	17	24	31	39	46	55	63	72	82	92	102	
15.2	**50**	**80**	9	15	21	28	34	41	48	56	63	71	80		
16.7	**55**	**63**	8	14	19	25	31	37	43	50	56	63			
18.3	**60**	**51**	7	12	17	22	28	33	39	45	51				
21.3	**70**	**42**	6	10	14	19	23	28	32	37	42				
24.4	**80**	**32**	5	9	12	16	20	24	28	32					
27.4	**90**	**24**	4	7	11	14	17	21	24						
30.5	**100**	**18**	4	6	9	12	15	18							
33.5	**110**	**16**	3	6	8	11	14	16							
36.6	**120**	**10**	3	5	7	10									
39.6	**130**	**6**	2	4	6										

Repetitive Group Designation

A B C D E F G H I J K L M

Dive table courtesy of Scuba Educators International.

Table B, the surface interval timetable, provides letter group information based on your surface interval time (SIT). You begin a surface interval with one letter group designation; as you outgas nitrogen, you acquire lower letter group designations.

Repetitive Group Designation

A B C D E F G H I J K L M

Repetitive Dive Depth in Feet/Meters: **130** 39	New Repetitive Group	A	B	C	D	E	F	G	H	I	J	K	L	M
4 2	**A**	2:20 0:10	3:36 1:17	4:31 2:12	5:23 3:04	6:15 3:56	7:08 4:49	8:00 5:41	8:52 6:33	9:44 7:25	10:36 8:17	11:29 9:10	12:21 10:02	13:13 10:54
6	**B**		1:16 0:10	2:11 0:56	3:03 1:48	3:55 2:40	4:48 3:32	5:40 4:24	6:32 5:17	7:24 6:09	8:16 7:01	9:09 7:53	10:01 8:45	10:53 9:38
9	**C**			0:55 0:10	1:47 0:53	2:39 1:45	3:31 2:38	4:23 3:30	5:16 4:22	6:08 5:14	7:00 6:07	7:52 6:59	8:44 7:51	9:37 8:43
11	**D**				0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30	5:13 4:22	6:06 5:14	6:58 6:07	7:50 6:59	8:42 7:51
13	**E**					0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30	5:13 4:22	6:06 5:14	6:58 6:07	7:50 6:59
15	**F**						0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30	5:13 4:22	6:06 5:14	6:58 6:07
18	**G**							0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30	5:13 4:22	6:06 5:14
20	**H**								0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30	5:13 4:22
22	**I**									0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38	4:21 3:30
25	**J**										0:52 0:10	1:44 0:53	2:37 1:45	3:29 2:38
27	**K**											0:52 0:10	1:44 0:53	2:37 1:45
30	**L**												0:52 0:10	1:44 0:53
32	**M**													0:52 0:10

Table B

SURFACE INTERVAL TIME (SIT) IN HOURS AND MINUTES

Dive table courtesy of Scuba Educators International.

Table C, the residual nitrogen timetable, provides adjusted (reduced) no-stop time limits based on the amount of nitrogen in your body from a previous dive or dives. The table also converts your residual nitrogen to an amount of time for each depth. This residual nitrogen time (RNT) must be added to your actual dive time to obtain the total bottom time (TBT) for the repetitive dive.

Table C

RESIDUAL NITROGEN TIME (RNT) IN MINUTES

35 11	**40** 12	**45** 14	**50** 15	**55** 17	**60** 18	**70** 21	**80** 24	**90** 27	**100** 30	**110** 33	**120** 36	**130** 39	Repetitive Dive Depth in Feet/Meters
15 153	**13** 122	**12** 90	**11** 69	**10** 53	**9** 42	**8** 34	**7** 25	**6** 18	**5** 13	**5** 11	**5** 5	**4** 2	**A**
24 144	**21** 114	**18** 84	**17** 63	**15** 48	**14** 37	**12** 30	**10** 22	**9** 15	**8** 10	**8** 8	**7** 3	6	**B**
33 135	**29** 106	**25** 77	**23** 57	**20** 43	**19** 32	**16** 26	**14** 18	**12** 12	**11** 7	**10** 6	**9** 1	9	**C**
43 125	**37** 98	**32** 70	**29** 51	**26** 37	**24** 27	**20** 22	**18** 14	**16** 8	**14** 4	**13** 3	12	11	**D**
53 115	**45** 90	**40** 62	**35** 45	**32** 31	**29** 22	**25** 17	**22** 10	**19** 5	**17** 1	16	14	13	**E**
64 104	**55** 80	**48** 54	**42** 38	**38** 25	**35** 16	**29** 13	**25** 7	**22** 2	20	18	17	15	**F**
75 93	**64** 71	**56** 46	**49** 31	**44** 19	**40** 11	**34** 8	**29** 3	26	23	21	19	18	**G**
88 80	**74** 61	**64** 38	**57** 23	**51** 12	**46** 5	**39** 3	33	29	26	24	22	20	**H**
101 67	**85** 50	**73** 29	**65** 15	**58** 5	52	44	38	33	30	27	24	22	**I**
116 52	**97** 38	**83** 19	**73** 7	65	58	49	42	37	33	30	27	25	**J**
132 36	**109** 26	**93** 9	81	72	65	54	46	41	36	33	30	27	**K**
149 19	**122** 13	104	90	80	72	59	51	44	40	36	32	30	**L**
169	136	115	99	88	79	65	55	48	43	39	35	32	**M**

Note: For repetitive dives less than 35 feet use the RNT values for 35 feet

New Repetitive Group

Dive table courtesy of Scuba Educators International.

Table D, the decompression stops table, provides the amount of time that you must decompress if your total bottom time (actual dive time plus residual nitrogen time) exceeds the maximum no-stop time (NDSL) limit.

Table D

DECOMPRESSION STOPS TABLE

Depth Feet Meters	Bottom Time (min.)	Time to First Stop (min:sec)	Decompression Stops (min) @ 20ft.	Total Assent (min:sec)	Repetitive Group
40 12.2	135		0		M
	150	0.40	6	7:20	O
	160	0.40	14	15:20	Z
	170	0.40	21	22:20	Z
	180	0.40	27	28:20	Z
50 15.2	80		0		K
	90	1:00	2	3:40	M
	95	1:00	4	5:40	N
	100	1:00	8	9:40	O
	110	1:00	21	22:40	O
60 18.3	51		0		I
	60	1:20	2	4:00	L
	65	1:20	7	9:00	L
	70	1:20	14	16:00	N
	80	1:20	23	25:00	O
70 21.3	42		0		I
	50	1:40	9	11:20	L
	55	1:40	14	16:20	M
	60	1:40	24	26:20	N
	70	1:40	44	46:20	O
80 24.4	32		0		H
	35	2:00	1	3:40	J
	40	2:00	10	12:40	K
	45	2:00	17	19:40	M
	50	2:00	24	26:40	M
90 27.4	24		0		G
	30	2:20	4	7:00	J
	35	2:20	14	17:00	L
	40	2:20	23	26:00	M
	45	2:20	31	34:00	N
100 30.5	18		0		F
	25	2:40	3	6:20	J
	30	2:40	15	18:20	L
	35	2:40	26	29:20	M
	40	2:40	36	39:20	N
110 33.5	16		0		F
	20	3:00	3	6:40	I
	25	3:00	14	17:40	K
	30	3:00	27	30:40	M
	35	3:00	39	42:40	N
120 36.6	10		0		D
	15	3:20	2	6:00	H
	20	3:20	8	12:00	J
	25	3:20	24	28:00	L
	30	3:20	38	42:00	N
130 39.6	6		0		C
	10	3:40	1	5:20	G
	15	3:40	4	8:20	I
	20	3:40	17	21:20	K
	25	3:40	34	38:20	M

Dive table courtesy of Scuba Educators International.

Now you are ready to learn how to plan dives using the air diving tables. Use table A to determine the maximum no-stop time (NDSL) for a dive. This is the maximum time you can spend underwater for the deepest depth you reach during a dive. If your total bottom time exceeds the NDSL time, you must complete mandatory decompression using table D (this will be discussed later). Your goal is to avoid exceeding the NDSL.

Rows are horizontal, and columns are vertical. Enter table A on the row corresponding to the deepest depth you plan to reach during a dive, and then move across to the end of the row to find your maximum NDSL. After your dive, reenter the row and find the first number (in minutes) that does not exceed your actual dive time. Proceed downward on the column containing your dive time and locate the repetitive group designation letter (from A to M) for your dive. For example, a dive of 50 feet (15 m) for 30 minutes assigns you to group E. Remember that whenever the depth or duration of your dive exceeds a listed number in the table, you must use the next larger number.

Next, you use table B, the surface interval table, to determine your letter group for a repetitive dive. Your group designation depends on the amount of time that you remain at the surface until you dive again. The longer your surface interval, the closer to the beginning of the alphabet your letter group will be.

Enter table B using the group designation you obtained from table A. Move downward along the column until you find the time range (expressed as hours: minutes; for example, 1:26 is 1 hour and 26 minutes) that your surface interval time (SIT) falls into. Remember that when you exceed a number on the dive tables, you must use the next larger number. Follow the row to the left to find your ending letter group designation. For example, if your letter group was E at the beginning of a 2:00 surface interval, you would be in group C at the end of the surface interval. You would be in group C after a surface interval ranging from 1:45 to 2:39.

Use table C, the residual nitrogen time (RNT) table, to determine both your adjusted maximum no-stop time for a repetitive dive and your residual nitrogen time (which must be added to your actual dive time) for your planned depth. For example, if your repetitive group letter from a previous dive is C and your planned depth for your next dive is 50 feet, your actual bottom time (the smaller, lower number for the depth column coordinate) must not exceed 57 minutes. Additionally, the residual nitrogen time (RNT) for the depth (the larger, upper number for the depth column coordinate) must be added to your actual bottom time. If you dived to 50 feet for 40 minutes as a group C diver, you would add 23 minutes of RNT to your actual bottom time to obtain a total bottom time (TBT) of 63 minutes.

After a repetitive dive, you return to table A and use your total bottom time (TBT) to obtain a new repetitive group designation. For example, your dive to 50 feet for 40 minutes as a group C diver yielded a TBT of 63 minutes. According to table A, 63 minutes of TBT at a maximum depth of 50 feet would assign you to repetitive group I at the beginning of your next surface interval.

Table D is for emergency use only when you exceed the maximum no-stop time (NDSL) for a depth. Avoid dives that require planned decompression. If you unintentionally allowed your total bottom time (TBT) to exceed the NDSL, you would refer to table D to determine the required decompression. For example, if your TBT for a depth of 60 feet (18 m) was more than 51 minutes (the NDSL), but less than 61 minutes, you would need to decompress at a depth of 20 feet (6 m) for 2 minutes. Your total ascent time, including the decompression, would require 4 minutes. Your repetitive group after the decompression dive would be L. This example is for emergency purposes only. You should never plan a decompression dive unless you complete specialty training and meet every requirement for safety.

Special-Equipment Dive Planning

You must use special dive tables if you dive using oxygen-enriched air (nitrox); you learn how to use these tables when you take a nitrox specialty course. Do not attempt specialized diving without proper training. Exceeding the 130-foot (39 m) depth limit by a few feet when breathing compressed air is not particularly dangerous, but exceeding the maximum depth limit (which varies with the gas mixture) when breathing mixed gases can cause seizures and drowning. Gas mixtures other than compressed air are only for divers who have the prerequisite training and equipment.

Dive Profile Terms and Rules

Divers use several types of **dive profiles**, which are created by plotting the time and depth of a dive. Figure 7.3 shows a diagram of a standard profile. A dive to a constant depth for a given period of time is typically depicted as a profile with square corners. A **multilevel dive profile** is a dive that progresses from deep to shallow during a given period of time. When you make a dive in a series of steps, you can refer to it as a **step dive**. A **sawtooth dive profile** is a dive that progresses from deep to shallow and back to deep. Avoid this type of dive. Another profile is the bounce profile. This represents a dive with a short ABT,


Depth
Safety stop
Time

Figure 7.3 Standard dive profile.

such as a dive to free a fouled anchor. You should also avoid this profile, which is depicted graphically as a spike. Bounce profiles are also called **spike dives**. Figure 7.4 graphically depicts these four profiles.

Dive Profile Diagramming

Diagram your dive profiles when planning and recording your dives. Include planned and actual depths, rest decompression stops, bottom times, repetitive group letter designations, and surface interval times. For repetitive dives, include RNTs and TBTs. A simple method for diagramming dive tables is to use a worksheet like the one shown in figure 7.5. Some dive computers automatically record a profile of your dive that may be displayed for review.

Try the following exercise, which combines diagramming with the dive table procedures you have learned. Use the blank diagramming worksheet in figure 7.5 as a template. If you have any difficulties, refer to the preceding section about the use of the dive tables. Assume that all dive times include three-minute rest


70 ft
(21 m)
30 minutes
Square profile
70 ft
(21 m)
30 minutes
40 ft
(12 m)
15 minutes
20 ft
(6 m)
15 minutes
Multilevel or step profile
70 ft
(21 m)
50 ft
(15 m)
40 minutes
Sawtooth profile
70 ft
(21 m)
2 minutes
Bounce or spike profile

Figure 7.4 Types of dive profiles.


:
:
PD
AD
NDSL
NDSL
ABT
PD
AD
NDSL
NDSL
ABT
+ RNT
= BNT
PD
AD
NDSL
NDSL
ABT
+ RNT
= BNT
PD = Planned depth
AD = Actual depth

Figure 7.5 Use a worksheet like this to plan your dives.

stops. Calculate and diagram the following series of dives (the answers to the diagramming problem are in the next paragraph and in figure 7.6):

- The first dive is to 78 feet (24 m) with an ABT of 20 minutes, followed by a surface interval of 1.5 hours.
- The second dive is to 55 feet (16.8 m) with an ABT of 25 minutes, followed by a surface interval of 2 hours.
- The third dive is to 40 feet (12 m) with an ABT of 25 minutes.

Solution: The repetitive group after the first dive is E. After the surface interval, the repetitive group changes to D. The RNT for a D diver at 55 feet (16.8 m) is 26 minutes. The TBT (ABT + RNT) for the second dive is 51 minutes (25 + 26). The repetitive group after the second dive is I. After the second surface interval, the group changes to G. The RNT for a group G diver at 40 feet is 64 minutes. The TBT for the third dive is 89 minutes (25 + 64). The repetitive group after the third dive is J.

The following tips help make dive profile diagramming easier:

- Enter the repetitive group letter at every upper corner of a profile except the first corner.
- Add ABT and RNT to obtain TBT for every repetitive dive. Use the recall word ART to help remember that you add ABT and RNT to obtain TBT.

Now combine the dive table procedures to plan a series of dives. Use the blank diagram shown in figure 7.5. Assume that the depth of the first dive—the deepest dive—is 60 feet. The NDSL, according to table A, is 51 minutes. Plan an ABT


E
1:30
D
3
I
2:00
G
3
J
3
PD 80'
AD 78'
NDSL 32
NDSL 32
ABT 20
PD 60'
AD 55'
NDSL 27
NDSL 37
ABT 25
+ RNT 26
= BNT 51
PD 40'
AD 40'
NDSL 71
NDSL 71
ABT 25
+ RNT 64
= BNT 89
PD = Planned depth
AD = Actual depth

Figure 7.6 Completed diagramming worksheet.

Rules

Ascent Rate. Divers should ascend at 30 feet per minute or slower.

Dives Less Than 25 Feet. Dives less than 25 feet do not have a specific No Decompression Stop Limit. However, if conducted as repetitive dives, they must be calculated as a 35 foot dive for Residual Nitrogen Times (RNT), Table C.

Exceeding the No Decompression Stop Limits. If divers err and stay longer than the times allowed on the No Decompression Stop Limit, Table A, the divers have exposed themselves to an increased decompression requirement and must refer to the Decompression Stops Table, Table D, for required decompression stops to complete the dive. Once on the surface, these divers should not dive again for at least 12 hours or fly for at least 24 hours.

Flying After Diving. The longer the surface interval before flying, the less likely a diver will experience decompression sickness. A minimum surface interval of 12 hours is required before ascent to altitude in a pressurized aircraft (or a ground altitude of 1000 feet above sea level). Divers who plan to make multiple dives for several days or computer-assisted dives should take extra precaution and wait an extended surface interval of greater than 12 hours before flying or ascending to altitude. Divers who have made dives requiring decompression stops should wait a minimum of 24 hours before flying or ascending to altitude.

High Altitude Diving. These Air Diving Tables are not to be used for diving at altitudes greater than 1000 feet above sea level without calculating altitude adjustments.

Order of Dives. All repetitive dives should be conducted with each successive dive equal in depth or shallower than the previous dive.

Sport Diving Maximum Depth. Sport divers should not exceed 100 feet of depth.

Sport Diving Time Limit. On any dive, the Total Bottom Time (TBT) should not exceed the **No Decompression Stop Limit.** Dives requiring mandatory decompression stops should not be planned.

Definitions

Bottom Time (BT). The elapsed time in minutes starts when the diver leaves the surface in descent and stops when the diver begins safety stop or surfaces (round up to next whole minute). On repetitive dives, this is Actual Bottom Time (ABT).

Depth. The depth of a dive; use the maximum depth attained during the dive in feet or meters of seawater. When depth is not indicated on the table, use the next greater depth available.

No Decompression Stop Limit. The longest amount of time a diver can spend at depth without requiring a decompression stop. Table A lists these for all depths. For repetitive dives, the Residual Nitrogen Time (RNT) must be added to the Bottom Time (BT) and the total bottom time (TBT) must not exceed the No Decompression Stop Limit.

Repetitive Dive. Any dive conducted within the time period specified by the surface interval table (Table B) of a previous dive with a minimum surface interval of 10 minutes. For repetitive dives of less than 35 feet, use the RNT (Table C) values for 35 feet to calculate Total Bottom Time (TBT).

Repetitive Group Designation (RG). Letters that relate to the amount of residual nitrogen in a diver's tissues for the time specified in the Surface Interval Table.

Residual Nitrogen Time (RNT). Located in Table C, an amount of time, in minutes, which must be added to the Bottom Time (BT) of a repetitive dive to calculate Total Bottom Time (TBT). Represents residual nitrogen still in a diver's tissues from previous dives.

Safety Stop. A 3-minute minimum safety stop at 15-25 feet is recommended at the end of all dives.

Surface Interval Time (SIT). Located in Table B, the elapsed time from when a diver surfaces following a dive to the time (next whole minute) that diver starts the descent of the next dive. SIT must be a minimum of 10 minutes.

Total Bottom Time (TBT). Calculated by adding the Bottom Time (BT) and the Residual Nitrogen Time (RNT). For times not indicated at a particular depth, use the next longer time available for that depth.

of 28 minutes (including rest stop) for the dive. Your repetitive group designation after the first dive is E. Now plan a repetitive dive to the same depth. Refer to table C to plan the dive because table C provides the maximum allowable times for various letter group designations. If your surface interval is less than 52 minutes, you remain in the E group, your RNT is 29 minutes, and your ABT must not exceed 22 minutes. Your surface interval should be at least 1 hour, as recommended. If you wait an hour between the first and second dive, your repetitive group changes to D, your RNT is 24 minutes, and your ABT cannot exceed 27 minutes. If you want to dive for 28 minutes, you need to extend your surface interval to at least 1 hour and 45 minutes to obtain repetitive group C.

Assume that you repeat the first dive as a group C diver. Your RNT is 19 minutes and your ABT is 28 minutes, so your TBT is 47 minutes. Your repetitive group after the second dive is I.

Assume that the dive site is so good that you want to make a third dive to 60 feet. No ABT minutes are allowed for a diver with a group I designation. Proceed up the column of the table. If you want to dive to 60 feet again for 28 minutes, you need to attain repetitive group C, which allows 32 minutes of diving without required decompression. When you know the group that you need to attain as well as your starting group, you can plan your surface interval. Table B tells you that you must wait at least 5 hours and 14 minutes to move from group I to group C. It would be wise to consider a shallower dive at this point.

Use the tables to plan dives that enable you to avoid emergency decompression. You have three options for planning repetitive dives that do not require mandatory decompression. If your RNT prevents you from making a desired dive, you can (1) reduce the duration of the dive, (2) reduce the depth of the dive, or (3) increase the surface interval preceding the dive.

Special Procedures

Unusual circumstances may arise that require special procedures. You should know the procedures for dive profile planning for each of the following situations:

- A cold or strenuous dive—When a dive is particularly cold or strenuous, use the next greater time for the dive. If the dive is both cold and strenuous, use the next greater time and depth.
- Variations in the rate of ascent—If you ascend faster than 30 feet (9 m) per minute, extend your rest stop by at least two minutes. The faster you ascend, the more you should increase the stop time.
- Multilevel dives—Treat dives to multiple levels as square-profile dives, as if all the time of the dive was at the deepest depth of the dive. Do not attempt to extrapolate the dive tables.
- Omitted decompression—If you need to decompress but fail to do so, use the following procedure for omitted decompression. If you have no symptoms of decompression illness after the dive, remain out of the water, breathe oxygen in the highest concentration possible, rest, drink water, and be alert for symptoms of decompression illness. Wait 24 hours before diving again. If you suspect decompression illness, proceed at once to a hyperbaric facility for a medical examination. The USN has a procedure for in-water decompression, but diving medical experts agree that this procedure is inappropriate unless there is no alternative.

- A rest stop that causes your ABT or TBT to exceed NDSL—If a rest stop causes ABT or TBT to exceed the maximum time limits, determine your repetitive group letter designation using the NDSL for the profile.
- Diving after mandatory decompression—After a dive that requires decompression, wait at least 24 hours before diving again.
- A repetitive dive with an RNT that exceeds the ABT of the previous dive—If the RNT for a repetitive dive exceeds the ABT of the previous dive, use the RNT for planning the repetitive dive.
- Altitude after diving—Ascending to altitude after diving increases the likelihood of decompression illness because of further reduction in pressure. Driving in the mountains or flying after diving can cause decompression illness that would not occur if you remained at sea level until you eliminated the excess nitrogen.

The Divers Alert Network (DAN) recommends that divers wait a minimum of 12 hours before ascent to altitude in a commercial jet airliner (higher than 8,000 feet, or 2,438 m) after a single no-decompression dive. If you make multiple dives for several days, wait at least 18 hours before flight. If your dive requires decompression, a preflight interval substantially longer than 18 hours is required. Lengthening your preflight time interval reduces the chance that you will experience decompression illness.

DAN does not have a recommendation for flying or driving at lower altitudes. The most extensively tested tables for altitudes are the Swiss dive tables. The Swiss tables use a compartment with a much longer half-time than the USN tables. A reasonable approach to altitude delays after diving makes the surface intervals of the USN dive tables equivalent to those of the Swiss tables. Converted USN minimum surface intervals in table 7.1 specify the minimum time required to attain permissible nitrogen levels for various altitudes.

Altitude is any elevation above 1,000 feet (305 m). The altitude delay timetable provides recommended time delays for altitudes up to 10,000 feet (3,048 m). To use the altitude delay timetable, enter the table horizontally on the top line and

Table 7.1 Altitude Delay Timetable

Starting repetitive group

Altitude (ft/m)	ABC	D	E	F	G	H	I	J	K	L	Group*
2,000/610	0:00	0:00	0:00	0:00	0:00	0:00	0:00	0:00	0:00	2:26	K
3,000/914	0:00	0:00	0:00	0:00	0:00	0:00	0:00	0:00	2:37	4:08	J
4,000/1,219	0:00	0:00	0:00	0:00	0:00	0:00	0:00	2:53	4:30	5:51	I
5,000/1,524	0:00	0:00	0:00	0:00	0:00	0:00	3:04	4:57	6:29	7:44	H
6,000/1,829	0:00	0:00	0:00	0:00	0:00	3:20	5:24	7:12	8:38	9:54	G
7,000/2,134	0:00	0:00	0:00	0:00	3:41	6:02	8:06	9:43	11:10	12:36	F
8,000/2,438	0:00	0:00	0:00	4:08	6:50	9:11	11:04	12:41	14:19	15:40	E
9,000/2,743	0:00	0:00	4:57	8:06	10:48	12:58	14:51	16:39	18:11	23:09	D
10,000/3,048	0:00	6:18	10:37	13:25	15:56	18:05	20:10	21:18	23:24	24:50	C

Note: Times represent the minimum recommended time delay before ascending to the listed altitude and are USN surface interval times with a delay factor of 5.4. Times are in hours:minutes (for example, 5:24 is 5 hours 24 minutes).

*Recommended minimum repetitive groups for indicated elevations.

find your starting repetitive group. Next, find the altitude to which you wish to ascend. If you exceed a number, use the next greater one. The time at the coordinates of the desired altitude and your starting repetitive group indicates the minimum time delay recommended before ascending to the altitude selected.

Profile Contingency Planning

When you plan a dive profile, you should also plan for contingencies. You should know what to do in case you unintentionally exceed your planned depth or time or both. A simple matrix, such as that depicted in figure 7.7, is helpful. When diving using dive tables, you should prepare a contingency matrix in advance of your dives and carry it with you while diving. Dive computers automatically provide contingency information.

Not all dive-planning information displayed by a computer can be accepted at face value. You must learn to apply the dive computer guidelines included in this section.

After you complete your plans, you need to implement them. The first rule of dive planning is to plan your dive, and then dive your plan. You and your buddy should make every effort to do as you agreed to do before the dive. When circumstances force changes in your plans, it helps to have **contingency plans**.



Times in boxes are emergency decompression times.

Sample	Planned time 30 minutes	Next greater time 40 minutes	Next greater time 50 minutes
Planned depth 60 ft	0	0	0
Next greater depth 70 ft	0	0	5
Next greater depth 80 ft	0	5	10

	Planned time ____	Next greater time ____	Next greater time ____
Planned depth ____			
Next greater depth ____			
Next greater depth ____			

Figure 7.7 A contingency matrix helps you plan ahead for unexpected events.

These plans need to address many possible contingencies for a dive. For example, you should know what to do if you

- surface downcurrent from a boat when you had planned to surface in front of it,
- are unable to reach or use the exit point you had selected on shore,
- end the dive a long distance from your exit location,
- exceed the maximum allowable bottom time (ABT or TBT) for a dive,
- experience a failure of your dive computer while diving, or
- ascend directly to the surface without precautionary decompression.

Dive Calculators and Dive Computers

The benefits of a dive computer outweigh the potential problems associated with the use of these devices. Because dive computers simplify dive planning, you should obtain a dive computer as soon as you can. However, make sure you learn how to use dive tables and dive calculators so that you will know how to plan a dive if you do not have a dive computer. Although dive computers have minimized the use of dive tables, divers must be able to use dive tables as a backup in case the dive computer fails to work.

Dive calculators are circular planning devices that eliminate the mathematics required with the dive tables. Dive calculators provide precalculated numbers, and they eliminate the need to add and subtract times. Guides on the calculators help eliminate line-jumping errors frequently made when using dive tables.

Dive tables have 5- or 10-foot (1.5 or 3 m) increments and require all the time of a dive to be counted at maximum depth of the dive. If the first part of your dive is deeper than the remainder of the dive, you suffer a penalty because the tables treat the entire dive as if it took place at the deepest depth (see figure 7.8). At the end of the dive, you receive a repetitive group designation that is higher than you deserve. Dive tables are advance-planning devices, while dive computers provide constant information on decompression status.

Dive computers use 1-foot (0.3 m) increments for profile planning, and they calculate nitrogen absorption continuously. As you vary depth during a multilevel dive, you are charged only for the nitrogen you absorb. You do not incur the maximum-depth penalty (see figure 7.8) of the dive tables, so your residual nitrogen time after a multilevel dive is less than when calculated using dive tables. The penalty avoidance is the primary advantage of a dive computer as a planning device. Dive computers also provide advance-planning information by **scrolling** a sequential display of time limits for various depths. You



Figure 7.8 The striped area represents penalty time imposed by dive table procedures.

must carry your dive computer with you when you dive because it provides information about your decompression status continuously and keeps track of your residual nitrogen.

Regardless of the type of dive computer you choose, you need to understand some basic principles. First, be sure to read the instruction manual that comes with your computer. Wait 24 hours after diving with dive tables before using a dive computer to ensure that you eliminate all residual nitrogen from your body. Do not exceed the ascent rate specified by the manufacturer, and do a five-minute rest stop at a depth of 15 to 20 feet (4.6 to 6.1 m) at the end of every dive. If you exceed the rate of ascent specified for your computer, extend the duration of your precautionary stop by at least the amount of time it should have taken you to ascend to the stop depth. Do not make repetitive dives deeper than 80 feet (24 m). Keep your dive computer activated until its outgassing is complete. If your computer fails at any time while you are diving at a depth in excess of 30 feet (9 m), terminate the dive immediately with a rest stop. If your computer fails or if you switch it off accidentally, discontinue diving for 24 hours.

If you exceed the maximum time limit for a dive, decompression is mandatory. The computer displays a ceiling—the minimum depth to which you may ascend. As you decompress, the ceiling becomes shallower until the computer indicates that you may surface. After a minimum interval at the surface, the computer begins scrolling—displaying the time limits for various depths sequentially. Wait 24 hours before diving again after any dive for which a ceiling was displayed.

The concept of backup planning with dive tables is good for square profiles; however, for multilevel dives planned with a computer, the use of the dive tables for backup planning is not feasible.

Modern dive computers offer many features. Here are some examples of the features that a computer may include:

- Operating modes for various breathing gases
- Decompression stop data
- A wireless transmitter that provides both cylinder pressure and remaining air data
- Dive profile lifetime history memories

Dive Computers

Advantages

- The maximum-depth penalty of the dive tables is avoided.
- Dive profile information is accurate.
- Dive computers store a record of the dive profile.
- You can eliminate common errors made when using manual dive planners.
- Dive computers offer additional features, such as an ascent rate indicator.

Disadvantages

- Dive computers are electronic instruments that can fail.
- Dive computers are expensive to purchase and service.
- Each diver must have a separate computer.
- The mathematical model varies from one type of computer to another, so some confusion results when each diver of a buddy team uses a different type of computer.

- A multiple-step ascent rate indicator
- Altitude adjustment
- A dive-planning mode
- Backlighted displays
- Audible alarms

An integrated, wireless-transmitting, digital-compass dive computer provides dive-planning information before, during, and after your dives. This type of computer is a highly desirable device. Central processing units (CPUs) in closed-circuit rebreathers (CCRs) are also sophisticated dive computers that provide highly technical dive-planning information.

The advantages of dive computers greatly outweigh the disadvantages, and computers have become an almost essential item for scuba divers.

Postdive Review

After a dive, you and your buddy should reflect on your experience. How closely did the actual dive match the dive that you planned? If there were deviations from the plan, what caused them? Could you have prevented the deviations with a different plan or approach? What changes can you make to improve the next dive? Some problems require research, or you may need to ask the advice of a diving professional. The experience of each dive should affect your plans for future dives. Your dives with your buddy should progress more smoothly each time you dive together. Each time you visit a dive site, your dive procedures should improve. A review of each dive with your buddy and a discussion about future diving are valuable parts of dive planning. Even if you have a new dive buddy for a dive, you should plan your dives together and discuss the experience afterward. It is a good idea to keep notes about your dives on a waterproof slate and transfer unusual experiences to your dive log along with the usual data. Reflecting on past experiences from time to time will help you become a better diver.

Summary

The saying “If you fail to plan, you plan to fail” is true for scuba divers. All phases of dive planning are important and help ensure enjoyable and successful underwater experiences. Follow the recommended steps for planning, get area orientations when appropriate, have contingency plans, and discuss your dives with your buddy.

Dive profiles are a large portion of dive planning. Plan to dive conservatively. No dive-planning device can guarantee that you will not develop decompression illness after diving. The deeper, longer, and more frequently you dive, the greater your risk of decompression illness. Limit multiple-day and multilevel dives because repetitive multiple-depth profiles make you more susceptible to decompression illness. Make a rest stop at the end of every dive, avoid improper profiles, and have surface intervals of an hour or more. After three consecutive days of repetitive diving, wait a full day before diving again. Exercise good judgment and common sense.

Application-of-Knowledge (AOK) Questions

1. What is the most difficult task of dive planning?
2. How can you make dive planning easier and be more likely to accomplish it?
3. You have a dive planned, the weather and water conditions are good, and you catch a cold virus the day before your dive. Cold medicine minimizes your congestion. What should you do?
4. A friend who has more diving experience than you invites you to dive on a shipwreck that is located at a depth of 120 feet (36.6 m). How should you respond to his invitation?
5. Would you rather plan a dive by using a dive computer or by using dive tables? What is the advantage of each approach?
6. You have been diving at a resort for a week. None of your dives have required decompression other than safety stops. Your plane leaves the day after tomorrow at 10 a.m. When should you stop diving?
7. If you have to go over a mountain pass with an altitude of 5,000 feet (1,525 m) to return home after diving, what action do you need to take?

Sergeant major fish in Cozumel

8

Diving Opportunities



Dive In and Discover

By the end of this chapter, you will be able to do the following:

- List 11 special-interest areas for novice divers and 6 special-interest areas for advanced divers.
- List at least five ways to continue your scuba diving education.
- List at least three ways to get involved with the local diving community.
- List several actions to take when preparing for a dive travel trip.

Continuing Education

A good diver never stops learning. You cannot learn everything you need to know about diving during a single course of instruction. After you complete your entry-level course, you can enroll in an intermediate or advanced scuba course immediately. These courses allow you to gain additional experience under supervision, help you develop important skills (such as navigation), and introduce you to special interest areas of diving. When you have identified a diving specialty you would like to pursue, you should complete a specialty course for that topic. A specialty course helps you begin enjoying the special area from the outset and helps you avoid mistakes and injury. Specialty areas that are of interest to new divers include the following:

- Underwater photography
- Underwater hunting and collecting
- Underwater environment
- Scuba lifesaving and rescue
- Night diving
- Boat diving
- Dry suit diving
- Drift diving
- Cavern diving
- Altitude diving
- Nitrox diving (enriched air)

Chestnut cowry by a starfish in California

As a qualified scuba diver, you can do many things. You can learn more, dive in different areas, be recognized for expertise, help others, or earn money, just to name a few. Opportunities abound.



Wreck diving at Grand Cayman.

The following specialty courses may be of interest to experienced scuba divers with advanced training:

- Wreck diving (penetration)
- Ice diving
- Cave diving
- Deep and wall diving
- Light salvage
- River diving
- Search and recovery
- Rebreather diving
- Mixed-gas diving

Courses are only one way to learn about diving. Many diving seminars, workshops, and conferences are also available. Check the calendar section of diving publications to learn of events scheduled in your area. Diving changes constantly, so you need to keep updating your knowledge of diving medicine, diving equipment, and diving procedures. Continuing education programs give you the opportunity to learn from professionals who are continually involved in diving.

You can learn more about scuba diving by reading books, magazines, and newspapers. Subscribe to a scuba periodical and read all you can about diving. The appendix contains a list of scuba periodicals. You can also visit websites by and for scuba divers.

Another good way to continue your diving education is to join a dive club. Dive clubs offer many benefits to divers, including education. A talk on an interesting subject by a good speaker is usually part of the monthly meeting of a local club.

Continuing your education is important for your safety and enjoyment. When you have increased your knowledge about diving, you may become interested in helping others to learn.

Local Opportunities

You do not need to live in a coastal area to dive regularly or to get involved in diving. You can dive nearly anywhere you can find water, and there are dive stores, dive clubs, and diving events in noncoastal areas. Get involved in diving in your area right away. Find all the diving-related businesses and groups in your area: dive clubs, dive stores, dive boats, diving events, and diving publications. Join a dive club, attend the meetings, and participate in club dives. Find a local diving website to make contact with other divers in the area. Complete continuing education courses. Attend local diving seminars, workshops, con-

Underwater photography at Cozumel.

ferences, and shows. Talk to other divers when you attend diving events. Seize every opportunity to learn and every opportunity to dive with those who are more experienced than you.

Dive Travel

Many divers enjoy taking dive trips to exotic destinations, and there are thousands of beautiful and exciting diving locations to choose from around the world. If you plan to travel somewhere to dive, you need to know how to arrange dive travel, how to prepare to travel, and how to enjoy your trip.

Travel agencies that specialize in dive trips provide valuable information, so it is a good idea to book your trip through one of them. You might want to consider a dive package that includes accommodations and diving. Dive resorts advertise these packages in diving publications and often offer packages for bargain prices at dive shows. Many resorts have toll-free numbers you can call to obtain information about dive packages. To ensure the best value for your money, compare several packages before you book a trip. If a brochure from a dive resort is out of date, check with the resort for current offers.

When planning a dive travel trip, you need to decide whether you want to dive from a live-aboard dive boat or from a shore-based dive resort. A live-aboard trip allows you to dive in a variety of locations. The vessel moves from place to place throughout the day. You dive in remote areas that only a few divers visit. You may find a live-aboard dive trip to be a wonderful experience if diving is the only objective of your trip and you are not affected by motion sickness.

Consider a shore-based dive trip if you do not care for confinement and if you want to participate in activities other than diving. Many beautiful islands and resorts offer a variety of things to do in addition to diving. Nondiving members of your travel party can usually find many sources of enjoyment at a land-based diving destination.

Many diving publications and diving websites are available to help you decide where to dive, although making a choice from all the fantastic destinations available can be difficult. Recommendations from other divers, trips sponsored by your dive club or dive store, and travel presentations can help you decide.

When you have decided on the region for your dive trip, get as much information as possible about diving in the area. Obtain and review brochures, books, articles, videos, and any other materials about the region. The Internet is another excellent resource for information on dive locations. Talk to divers who have been to the location where you plan to go. The more you know in advance, the more enjoyable you can make your experience.

After you select your diving destination, you should make your reservations well in advance, confirm all arrangements in writing, and get clarification concerning cancellations, refunds, and so forth.

Research and plan your dive trip by learning about the water temperature for the time of year when you will be diving. Then obtain the appropriate exposure protection. Remember that too much insulation is better than too little. Also make sure that all your equipment is in good working order.

Plan to avoid sunburn. Sunlight in tropical areas is more intense than in other climates. Use a sunscreen, and unless you are well tanned, keep yourself covered at all times, even while in the water. Use lip balm with a sunscreen ingredient.

Underwater salvage operations.

You cannot develop a tan in a few days, so it is silly to try if you do not already have one. Sunburn can ruin an expensive vacation, and donning an exposure suit is painful when you are burned. It takes only a few minutes for an untanned person to get burned in the tropics, so be careful!

Obtain all required documentation well in advance. Obtaining passports and visas can take months. Be sure to find out whether the country to which you are traveling requires immunizations.

Learn what to expect when you arrive at your destination. Know the frequency and voltage of the electricity; take converters if you are bringing electrical devices that operate on a different voltage. Know the monetary exchange rate. Consider taking a small pocket calculator to help compute the conversion of money.

If you have an expensive camera, video equipment, or jewelry, take your property to a customs office before you leave the country and have it documented to avoid being charged duty on the items when you return home.

Do not procrastinate in making your preparations. Procrastination can cause a cancellation of your trip, a forfeiture of your deposit, and a great deal of frustration. Consider travel insurance.

Limit what you pack for your trip. You do not need much clothing for a dive trip unless you plan to attend formal events. A few pairs of shorts and T-shirts, some swimsuits, and a couple of sets of nice clothes for dinner should suffice. Experienced dive travelers travel light when it comes to clothing and personal effects.

Diving destinations provide tanks and weights, so you do not need to take those items with you. When you pack for your trip, keep in mind that there may be weight limitations for your baggage. Excess baggage costs can be very high. To guard against theft, avoid flaunting expensive diving, photography, and video equipment. Use inconspicuous containers to ship your equipment, and it will be less likely to disappear. Insure luggage that contains expensive equipment. Items I always take with me are mask, snorkel, fins, exposure suit, boots, gloves, regulator, buoyancy compensator, and dive computer. I rent tanks and weights. My gear can be packed in a dive bag, but I prefer to use a suitcase for better protection of the equipment. I pack a dive gear bag in the suitcase because I don't want to use a suitcase at the dive site. There are also dive gear bags that have wheels, which are useful when you can roll the bag.

Be prepared for travel illnesses. Obtaining medications for nausea, diarrhea, and colds is easier before a trip than it is if you become ill in a foreign land.

Flying is the most common method of transportation for dive travel. Air travel usually produces jet lag and dehydration. A viral illness a couple of days after reaching your destination is common because many virus germs are concentrated inside the cabins of airliners. Here are some tips and suggestions concerning air travel:

Schedule your flight to arrive the day before you start diving. It is unwise to plan to dive the same day you arrive.

Drink a full glass of water or fruit juice every hour during your flight to avoid dehydration. Avoid alcohol, milk, and drinks containing sugar. The humidity in an aircraft is about 8 percent, so you will become dehydrated unless you drink plenty of fluids.

Avoid eating heavy meals and salty foods when flying. Light foods cause less dehydration than fatty foods. Consider ordering a special meal of salad and fruit, or bring your own food if meals aren't served on the flight.

Wash your hands frequently when traveling. Germs from your hands can get into your eyes and nose and lead to viral infections.

Remember that baggage compartments on airliners are unpressurized and that the reduced atmospheric pressure can damage your gauges. Therefore, you should either bring your gauges inside the cabin in your carry-on luggage or store them in airtight containers.

As soon as possible after reaching your destination, get some exercise and drink plenty of liquids. Limit your consumption of alcohol, which causes dehydration. Getting intoxicated at the outset of a diving vacation is one of the worst things you can do because you increase your chances of getting DCS.

Confirm your return air reservations as soon as you arrive, especially if you travel to another country. If you fail to do this, you are likely to lose the reservations. You could end up arriving at the airport to go home and discovering that your tickets are not valid.

Your first dive at your destination should be an orientation dive. In addition to learning about diving in the area, you should use the dive to check your buoyancy and make any needed adjustments. Work out any equipment problems during a dive in shallow, still, calm water. Avoid deep dives or moving water until you have acclimated to the area.

After three days of repetitive diving, refrain from diving for a day so that your body can outgas. Go shopping or take a land tour for a refreshing change of pace. Allow one day between your final scuba dive and your scheduled flight home.

SCUBA WISE

Scuba equipment is a means to an end—a mechanism that enables you to go to areas that are otherwise unreachable by the average person. I think of scuba diving as a means of transporting myself to a destination where I can explore or participate in a special activity. Scuba diving without an objective loses its thrill after only a few dives. You need to develop an interest area, which can be anything from bottle collecting to wreck diving. When you have an objective for your dives, diving can be extremely rewarding. Over the years, I have participated in many different diving activities. My favorite underwater pursuit is photography. I can collect priceless memories without removing anything from the environment. In my opinion, underwater photography is the most challenging and the most satisfying dive activity. Select a diving activity that appeals to you, complete training for the activity, and then pursue it. You may choose several different activities. No matter what you choose to do while diving, I hope that your experiences will be as wonderful as mine have been.

The nondiving day before flying helps prevent DCS caused by altitude, and it gives you the opportunity to rinse, dry, and pack your diving equipment. Snorkeling is a good last-day activity, and your mask, snorkel, and fins dry quickly for last-minute packing.

Dive travel can be fun, exciting, and memorable when you plan it well. You can avoid unpleasant, frustrating, and disappointing experiences by researching your destination and preparing properly. Good diving to you!

Dive Destinations

One of the great pleasures of scuba diving is visiting different regions of the country and the world. Fantastic dive sites can be found nationally and internationally. The following areas are popular dive destinations that you might want to visit. The pictures throughout this book were taken at these destinations.

California

Dense kelp beds that form surface canopies make diving in California an unforgettable experience. The kelp provides shelter for many forms of life. Rock formations provide anchorage for the buoyant kelp and support additional life-forms, such as abalone, lobster, and moray eels. An expedition on a live-aboard dive boat to one or more of California's offshore islands during the summer months is an extremely worthwhile scuba experience. Shore diving in California can be difficult because of surf and low visibility. An area orientation is essential before attempting to dive through surf.

Washington

Puget Sound, which was carved into the landscape by glaciers, forms a gigantic body of ocean water that is much more protected than the coastal waters. The Sound contains many shipwrecks and artificial reefs, which are havens for many life-forms. Puget Sound is the home of the world's largest octopus as well as giant lingcod, monkey-faced eels, and beautiful orange and white anemones called metridians. The water is cold, but the visibility is 15 to 20 feet (4.5 to 6.1 m) most of the time. Dry suits are recommended.

Florida

Florida features some of the best and most diverse diving in the United States. From crystal clear springs and rivers to the Keys, there are many spectacular dive sites. Cavern and cave diving are popular, but training for these specialties is mandatory. The Florida coast has abundant shipwrecks. The Keys boast coral reefs and colorful fish. All scuba divers should definitely have a dive excursion to Florida included in their dive log.

New England

The cold waters of the New England area offer a great variety of diving opportunities. Wrecks, reefs, kelp, and creatures captivate your attention. Lobsters with claws and other interesting life-forms are great attractions. If you are able to schedule some time to dive when you travel to this part of the country, you should try to include the adventure in your itinerary.

Great Lakes

These great bodies of freshwater boast the most well-preserved shipwrecks in the United States. Many of these wrecks are in deep water, so you must have specialty training to explore them. Divers who are unfamiliar with the Great Lakes should use the services of a divemaster. If you like wreck diving, this is one of the places to include on your must-see list.

Hawaii

Hawaii offers exciting diving that includes good visibility, spectacular underwater formations, beautiful reef fish, large turtles, and giant marine mammals. Hawaii is a popular diving destination that you should visit if you get the chance. Aloha!

Caribbean

The Caribbean is one of the world's most popular places to dive, and for good reason. The area includes reefs, wrecks, drop-offs, and life-forms that are unique and breathtaking. Visibility is usually excellent. Many dive resorts in the area offer trips to phenomenal locations. Nearly every experienced diver talks about Caribbean diving experiences.

South Pacific

The islands in the South Pacific offer some of the most beautiful diving to be found anywhere on Earth. Divers can see fantastic soft corals, sea fans, and incredible fish. Visibility is outstanding. Many of the island waters feature wrecks and war artifacts. The beauty found above and beneath the water in this part of the world makes trips to the South Pacific highly desirable for scuba divers.

Underwater photography in Southern California

Middle East

The diving destination in this region is the Red Sea, which is unparalleled for scuba diving. The shear walls, the abundant and colorful life-forms, and the crystal clear waters make this one of the most desirable of all diving destinations. If you can afford a trip on a live-aboard charter boat to offshore islands, you will be treated to unforgettable sights.

To learn details of the world's most popular diving destinations, you can do a search of the topic on the Internet. Many websites provide excellent information. Traveling to exotic dive destinations is one of the most enjoyable aspects of scuba diving.

Career Opportunities

Some people love diving so much that they want it to be their vocation. Career opportunities exist for those who are willing to put forth the effort to achieve their desires. Jobs within the recreational dive industry include resort dive guide, instructor, journalist, dive travel coordinator, retail salesperson, and sales representative for equipment manufacturers. People can also work in nonrecreational scuba jobs, such as scientific research, archaeology, engineering studies, hull cleaning, salvage, and underwater repairs. Two of the same rules that apply to recreational pleasure diving also apply to underwater work: (1) Complete training for an activity before you attempt it, and (2) use complete, proper equipment for the activity. Career training opportunities abound. If you are interested in diving as a vocation, you can find information about training in dive periodicals.

Night diving preparations at Catalina Island, California.

Leadership Opportunities

After you have become an experienced diver, you may want to help others learn and enjoy scuba diving. You can take courses to become qualified as a divemaster, assistant instructor, and instructor. Many people who love diving work part-time in the industry in leadership positions. When you are ready for leadership training, contact your scuba training agency for information.

Summary

Always remember that a good diver never stops learning. You should complete additional training, make sure you are trained for any special activity before you attempt the specialty, read as much as possible, join a dive club, and attend educational events. Take advantage of every opportunity to learn more about diving.

Increase your diving abilities and experience by applying what you learn. Participate in dive trips and charters. Research and plan your excursions thoroughly to maximize your enjoyment and minimize your disappointment. Many opportunities are available for diving adventures throughout the world.

Another opportunity for you as a diver is to make a positive contribution to the diving community. You can do this by conducting yourself in a responsible manner at all times and encouraging other divers to act responsibly. Help establish a good image of diving, get involved in issues that pertain to the diving environment, and help educate people who do not dive. Whether your contribution is small and personal or vast and international, you can make a difference. Decide now that your involvement in the wonderful pursuit of scuba diving will be a positive one.

Application-of-Knowledge (AOK) Questions

1. Why are you learning to dive? Do you just want to investigate a new activity, or are you interested in an activity that requires scuba diving?
2. What do you visualize as your progression of training as a scuba diver?
3. How often do you think you will dive? Will most of your diving be local or related to dive travel?
4. If a nondiving friend asked you what can be done to reduce the risk of injury while scuba diving, what advice would you provide?
5. What causes you the greatest concern about scuba diving? What can you do to minimize your concerns?
6. How do you see yourself as a scuba diver in 5 years? In 10 years?

This page intentionally left blank.

Appendix A

Associations and Periodicals

Diver Training Organizations

International Diving Educators Association (IDEA): www.ideascubausa.com/home_15.html

Multinational Diving Educators Association (MDEA): http://neptuneshop.wix.com/mdea#!

National Association of Scuba Educators (NASE): http://naseworldwide.org

National Association of Underwater Instructors (NAUI): www.naui.org

Professional Association of Diving Instructors (PADI): www.padi.com/Scuba-Diving

Scuba Diving International: www.tdisdi.com

Scuba Educators International (SEI): www.seidiving.org

Scuba Schools International (SSI): www.divessi.com

Environmental Organizations

Blue Frontier Campaign: http://bluefront.org

Cousteau Society: www.cousteau.org

Earthecho International: http://earthecho.org

Living Oceans Society: www.livingoceans.org

Marine Conservation Society: www.mcsuk.org

Oceana: http://oceana.org

Ocean Defense International: www.oceandefense.org

Oceanic Preservation Society: www.opsociety.org

Reef Check: www.reefcheck.org

Reef Relief: www.reefrelief.org/mission

Save Our Seas: http://saveourseas.com

Sea Shepherd Conservation Society: www.seashepherd.org

Coral Reef Alliance: http://coral.org

Ocean Conservancy: www.oceanconservancy.org

The Ocean Project: http://theoceanproject.org

NOAA National Marine Sanctuary Project: http://sanctuaries.noaa.gov

Scuba Diving Magazines

Advanced Diver: www.advanceddivermagazine.com
Alert Diver: www.alertdiver.com
Dive Training: https://dtmag.com
Diver: http://divermag.com
Scuba Diving: www.scubadiving.com
Undercurrent: www.undercurrent.org

Appendix B

AOK Answers

Chapter 1

1. Some people learn to scuba dive because they seek a new experience or adventure. Scuba diving training opens the gate to a beautiful underwater world, which can provide many pursuits. Scuba diving should be considered a mode of transportation that takes you to places where you can pursue underwater interests such as exploring, photography, and wreck diving. After completion of your basic scuba diver training, continue your education and obtain an advanced scuba diver rating. With the additional skills acquired with advanced training, you will be ready to learn specialty activities and seek the rewards of your chosen endeavors.
2. An open-circuit scuba system allows a diver to breathe compressed air from a pressurized cylinder and exhaust the used gases into the water. It is a simple, reliable, easily maintained air delivery system, which makes it the safest and most popular scuba system. A closed-circuit scuba system allows a diver to rebreathe exhaled air by removing carbon dioxide and adding the correct amount of oxygen without allowing gases to escape from the system. It is a complex air delivery system that requires specialty training and extremely careful maintenance. Closed-circuit scuba systems are very expensive compared to open-circuit systems.
3. A scuba certification card (C-card) indicates that you have completed initial training, but it does not reflect how recently you have been diving. Certification agencies recommend that you complete simple refresher training if you have not dived for a year or longer. This training is a review of your basic skills under the supervision of an instructor during an open-water dive. The confidence you gain from knowing that your skills are refreshed will make your diving safer. A good reason to log your dives is to document your diving activity. Some dive resorts and charter boats will want to review your log book to determine your diving experience, especially your most recent dives. Logged dives also can help you recall many facts that you would otherwise forget.
4. It is logical that the more time you can use your knowledge and skills of scuba diving under the supervision of a certified diving instructor, the better your knowledge and skills will become. Extended training also allows you to ponder your learning between training sessions. You have time to think of questions that will clarify concepts and increase your understanding of principles. Short scuba training courses do not provide these benefits. The goal of learning is to transfer knowledge and skills acquired in a controlled environment to the actual environment in which they will be used. Longer scuba courses develop a greater ability to transfer your

knowledge and skills, which increases your safety for your independent diving after training.

5. A medical exam for scuba diving should be performed by a scuba diving physician who understands medical issues that could be problematic for those considering scuba training. Knowledge of how pressure affects medical conditions can help prevent pain, suffering, and even death.
6. Actions you can take to minimize your risk of injury while scuba diving are to dive only when you are in good health, use well-maintained equipment, dive in good environmental conditions, and adhere to the safety rules of scuba diving.
7. When you are in the process of selecting an instructional course for scuba diving, you need to know the sanctioning national agency, the instructor's experience, the total cost of the course, the course curriculum and duration, and how much open-water (real environment) training is included.
8. You can show that you are a responsible diver if you do only what you are qualified to do, dive within your personal limitations, adhere to safety rules, and remain aware of how your conduct will be viewed by others—divers and nondivers—when you go diving.

Chapter 2

1. Your exertion has used much oxygen, which has produced much carbon dioxide (CO_2), which stimulates you to breathe more to expel the CO_2. The feeling of a lack of air is caused by the need to reduce the amount of CO_2 dissolved in your blood. You need to minimize your activity immediately and breathe deeply until your breathing returns to normal.
2. Rapid, shallow breathing (hypoventilation) moves only a small amount of air in and out of your body. The structures from your mouth to your lungs do not allow gas exchange, so your body is not getting oxygen or ridding itself of CO_2. Gaining control of your breathing by stopping or reducing activity and breathing deeply until you feel better is the correct course of action and can help prevent panic. When your breathing is under control, you can think clearly and manage the difficulty that caused your anxiety.
3. Many factors affect air consumption, but the primary cause of high air consumption is exertion. Relax and move slowly. If you are too buoyant and have to exert to maintain your position in the water, your air supply will be depleted rapidly. If you are wearing too much weight, your attitude in the water will increase your frontal surface area and drag will increase air consumption. Adjust your weight and trim so you can hang suspended in a level position, and then relax and enjoy diving.
4. The first step is to tell yourself that you have time to manage this problem. The next step is to think of the options available to you. The quickest and easiest solution is to switch to your extra second stage or alternate air source. Your buddy's extra second stage is another good choice. The worst way to manage this problem is to spit out your regulator and swim to the surface.
5. Rapid and deep breathing before holding your breath is hyperventilation, which flushes carbon dioxide from your body. The buildup of carbon

dioxide when you hold your breath is what stimulates you to breathe. If you eliminate too much carbon dioxide from your body, you may lose consciousness while breath holding before you are stimulated to breathe. Loss of consciousness underwater can cause drowning. Hyperventilation should be limited to a few breaths before underwater breath holding to avoid what is called shallow-water blackout.

6. Your body loses heat rapidly in water. When you increase your heat production by exercising in cold water, you lose more heat than you would if you had not increased exertion. If you are wearing a wet suit, ascending to shallower water will increase your insulation as the water pressure decreases. Avoid moving directly into a current, which will push cold water through your suit. Your best action is to obtain better insulation for your entire body for future dives.

Chapter 3

1. The current is pushing cold water into and through your wet suit. If you swim at an angle to the current, you will reduce the flow of cold water through your suit and not get as cold. You can also look for places where you can be shielded from the current. You do not need to swim constantly when diving. Most of the life in the ocean is less than 1 inch (2.45 cm), so it is a good idea to stop and look closely at any underwater formations.
2. Some of the best and safest ways to warm yourself after diving are to remove your wet suit, get dry, get out of the wind and into a warmer environment, wrap yourself in a blanket or sleeping bag, eat high-energy food, drink warm drinks, and avoid stimulants. The principle is to warm yourself from the inside out instead of using external heat, which is dangerous. Remember that your core temperature will not be normal until you begin to perspire.
3. Did you think about the density of water and how much resistance to movement it causes? People usually think they will ascend rapidly if they lose their weights, but if you respond quickly, this situation is not difficult to manage. Quickly deflate any air from your BC. Then invert yourself to get your fins above your head, swim downward forcefully for a few kicks, grasp your weight belt, and replace it. (You will learn how to do this skill in chapter 6.)
4. When you ascend 10 feet (3.3 m) to swim over the reef, your buoyancy will increase because your wet suit and the air in your BC will expand. If the upward excursion is brief, you may be able to control your buoyancy just by keeping the amount of air in your lungs minimal. If the excursion is long or you are unable to control your buoyancy by breathing, vent some air from your BC to maintain neutral buoyancy until you descend again.
5. Remember that it is easier to equalize pressure in your ears if you descend feet first. It is good to use an anchor line for reference and control during a descent, but remain upright as you make your way down the line.
6. You should recall that the rate of change of pressure is greatest near the surface. Therefore, you need to equalize pressure in your ears and mask more frequently near the surface than will be required as the depth of

descent increases. If you can keep your air spaces equalized for the first 33 feet (10 m), you are not likely to have problems beyond that depth.

7. If you don't stop swimming, you will experience air starvation. And if you do stop swimming, your buddy will disappear and you may become separated. Prevention is best. Get your buddy to agree that you will swim side by side at all times and that when one of you stops, you both stop. If your buddy is ahead of you and you want or need to stop, use a rock or the butt of your dive knife to bang on your tank to get your buddy's attention. If your efforts fail, stop and get your breathing under control and then surface to reunite with your buddy if he does not return to you.
8. You are out of air, but only at a depth of 50 feet (15 m). As amazing as it sounds, if you start swimming slowly to the surface, there will be additional air to breathe from your tank as the surrounding pressure decreases with ascent. This is not the best option, however. In chapter 6 you will learn other ways to deal with situations involving loss of air supply.

Chapter 4

1. Minimize sun exposure, soak and rinse after use, store in a dark and dry location that is free of smog, inspect your gear regularly, and have your equipment serviced regularly or as needed.
2. The most important concerns for most diving equipment are fit and comfort. Features, colors, and price do not matter if the equipment does not fit well or is uncomfortable to use. If possible, rent equipment before you make a purchase so you will know if an item is right for you.
3. If all of the air escapes from your tank and the valve in your second stage is open (or if you happen to depress the purge button and open the valve), water can enter your tank. You will learn how to minimize the chances that your regulator will free-flow. If you detect water inside you scuba cylinder, take it to a facility for maintenance as soon as possible.
4. Air has weight. The air in a typical scuba tank weighs five to six pounds (~2.25-2.7 kg) when the tank is full. As you deplete the air, your buoyancy increases. The loss of weight may not be apparent at depth if you wear an exposure suit because pressure compresses the suit. You simply add less air to your BC than you would if you were not wearing an exposure suit. Problems arise as you near the surface with a scuba tank that is nearly empty because your suit expands and you are unable to overcome the positive buoyancy caused by the loss of weight from your cylinder. To avoid this problem, you need to adjust your weight to be neutrally buoyant just below the surface while using a tank with approximately 500 psi of air remaining in the tank.
5. You need just enough air in a dry suit to keep it from squeezing you. Any excess air forms a bubble inside the suit, and the bubble rises to the highest point. If you tip upside down to do something, the bubble can rise to your feet, may loosen your fins, and can cause you to float upward in an inverted position. This problem is just one example of why you need special training in the use of a dry suit.

6. A compass is a magnet, and magnets attract one another. Placing your compass near your buddy's compass causes the needles to shift position and the readings to be inaccurate. You need to keep your compass away from any items that can cause the needle to deviate from its natural direction.
7. The best way to clean your diving equipment is to soak it in warm water, rinse it gently with flowing water, and dry it thoroughly before storing it. Some equipment parts, such as dry suit zippers, require scrubbing. Follow the manufacturer's instructions.
8. The attachments to a scuba regulator first stage may include a cylinder pressure gauge, a primary second stage regulator, an alternate air source second stage, a BC inflator hose, and possibly a dry suit inflator hose.
9. The best reasons for having good dive equipment and maintaining it properly are safety and comfort. You will know when your equipment is right when you are not concerned about it while you are diving.

Chapter 5

1. The water temperature affects the equipment you use, your body temperature, your diving procedures, the visibility underwater, and the underwater life, among other things. Water temperature has a profound impact on your diving adventures. Knowing what to expect and how to be prepared for the temperature of the water is essential.
2. Water visibility is affected by depth, pollution, water movement, weather conditions, algae, temperature, your movements, and other factors. Check present diving conditions with your local dive facility and postpone diving when visibility is poor.
3. A good way to manage currents is to know in advance what to expect. Obtaining training for diving in various currents is important. Being aware that the current is weaker at the bottom than at the surface is helpful. Swimming at right angles to a current may help you get out of some currents. Diving against the current is a common practice, but in some situations it is best to drift with the flow of the current.
4. When you encounter a strange animal underwater, respond by stopping movements, respecting the animal, observing it from a distance, and refraining from provoking or feeding the animal. Nearly all marine animals are defensive, not aggressive. Think and respond. The worst action to take when you see a strange or large animal is to panic and ascend rapidly to the surface.
5. No matter how much training or experience you obtain, you will always need to acquire local knowledge about diving in a new area. Watching and mimicking experienced local divers are a good way to avoid embarrassment, but learning in advance about why the divers use the techniques they use is even better.
6. While it may be difficult to accept until you gain experience, the safest and most comfortable place to be while diving is near the bottom. It is much more uncomfortable and dangerous at the surface of the water.

7. The transition from saltwater diving to freshwater diving requires changes that include the amount of weight you wear and perhaps the type and thickness of your exposure suit.
8. When you plan to dive in a new area, you need information about the area. Weather conditions, seasons, forecasts of diving conditions, area hazards, equipment requirements, and local diving procedures are important to know in advance. Chapter 8 provides resources to help you obtain the information that you need.

Chapter 6

1. Buoyancy can be controlled by the amount of weight worn, the amount of air in your BC, and the amount of air in your lungs. Think of these methods as large, medium, and small ways of control, respectively.
2. To ascend properly from a scuba dive, alert your buddy, hold your BC inflator-deflator with the mouthpiece facing down and the valve open, reach up, swim up, ascend slowly, monitor your rate of ascent and your buddy, turn slowly, stop at a depth of 10 feet (3.05 m) for precautionary decompression, ascend to the surface, and make a complete turn to assess your surroundings. Ascending is a complex skill. Learn it well.
3. Successful buddy contact requires predive planning and communications, agreeing on a direction and maintaining that direction until you both agree on a new direction, maintaining the same position (side by side) relative to one another, holding hands or using a buddy line when visibility is poor, and committing to reunite using standard procedures if you become separated.
4. This situation can be frightening unless you respond quickly. All you have to do is raise and open the deflator valve with one hand and disconnect the low-pressure hose with the other hand. You do not need to terminate your dive because you should have the skills needed for manual inflation of your BC.
5. When a regulator free-flows and will not stop, simply switch to your extra second stage and ascend. Remove your tank at the surface and turn off the air supply. If you allow the tank to empty and the second-stage valve is stuck in the open position, water can get inside your cylinder.
6. To exit the water into a small boat, remove your weight belt and place it in the boat, inflate your BC about half full, and remove your scuba unit. Next, grab the rail of the boat and, while holding the regulator hose from your tank under one hand, kick yourself up and into the boat. Remove remaining equipment after you are in the boat.
7. Swimming against a current can be tiring. If there is a nearby obstruction, such as a rock formation, that you can get behind to minimize the current and rest, seek shelter. If there is an outcropping you can grasp that will allow you to rest and catch your breath, use it. If the bottom is sandy, plunge your knife into the bottom to maintain your position while you recover. The most important action is to reduce your exertion and get your breathing under control. If the situation is unmanageable, surface and drift back to your exit point.

8. The assistance of your buddy is the best way to get free of an entanglement, but you can also remove your scuba unit, clear the entanglement, and replace your equipment. Be sure you learn the skills of equipment removal and replacement well so you can manage minor problems that may occur while scuba diving.

Chapter 7

1. The most difficult task of dive planning is getting started! Most people agree that planning is a good idea, but they procrastinate. You can be successful with almost any task if you push yourself to get started. If you keep a list of things to do, consider adding dive planning to that list.
2. To make dive planning easier, find a buddy who would like to dive with you and agree on which items each of you will plan. Set a date to talk again about your plan. By taking responsibility and setting a date, you will have less work to do and will be more likely to meet your goal of developing a good dive plan.
3. If your health is not normal, do not dive. Congestion from a cold can make it difficult to equalize pressure in your ears and sinuses. Pressure can cause the medicine to terminate sooner than it normally would. When decongestants stop working, air passages can swell and close rapidly and trap air. Notify your dive buddy that you need to postpone your dive trip until you are well again.
4. Assuming you are a novice scuba diver, it would be unwise to attempt a dive on a wreck in deep water. Shipwrecks often occur where conditions, such as currents, can be treacherous. Tell your friend that you are extremely interested but that you need to complete advanced and specialty training so you will be adequately prepared for the dive.
5. When you dive using a dive computer, you avoid the dive table penalty rule of having to assume that all of your dive time was spent at the maximum depth. The computer also stores valuable information about your dive, helps you control your rate of ascent, and indicates when you need to stop for decompression. The disadvantage of a dive computer is that it is an electronic instrument that can fail. Dive tables do not need batteries. The best approach to planning time and depth limits is to develop a contingency plan using dive tables, write the plan on an underwater slate, and take it with you when you dive with your computer. If your computer stops working or you inadvertently turn it off, your contingency plan can help keep you safe.
6. You need to plan. After multiple dives, you should wait 18 hours before flying, so your diving needs to end today.
7. When driving decreases pressure with altitude after you have been diving, you need to consult the altitude delay timetable. If your driving altitude reaches 5,000 feet and your starting repetitive-dive group is 1, you need to wait 3 hours 4 minutes before driving over that pass. This requires planning. If your altitude delay timetable is at home in your book, you won't know how long you need to delay your journey.

Chapter 8

1. Some people learn to dive just to experience the activity. They complete training, purchase equipment, make a few dives, and stop diving. Other people continue training, get involved in the diving community, pursue an underwater hobby, and dive for many years. If you think of scuba diving as a means to an end, it can provide wonderful experiences that will keep you involved for many years.
2. You might see yourself completing an advanced diver course and several specialty courses. It helps to gain some dive experience in addition to your training dives. Just be sure that your excursions are limited to the conditions and depths to which you are qualified.
3. If you are not certain that you will dive regularly or that you will dive only locally, consider renting the major equipment (cylinder, regulator, exposure suit, buoyancy compensator, and weight belt). If you find yourself diving frequently, buy your gear. Renting equipment will help you make a good selection. If you plan to dive primarily at dive destinations, rent the major equipment at the destination. When you become an avid scuba diver, you are likely to have full sets of equipment for both cold- and warm-water diving.
4. The best ways to reduce the risk of injury from scuba diving are to be trained for what you do while diving, have the proper equipment for your dive, and gain experience gradually. Making a dive that greatly exceeds your training and limitations without first gaining several experiences that gradually increase your training and limitations is unwise.
5. Phobias are natural, but if something terrifies you and it is related to diving, learn how to deal with the fear before you are exposed to it. For example, many people fear sharks because of what they have seen in media. What you should know is that dangerous shark encounters are rare and most likely occur at the surface of the water. If you see a shark, remain calm, stay on the bottom, and enjoy the exciting experience.
6. When you look to the future, do you envision yourself diving regularly? Are you just going to wait and see what happens, or do you intend to continue your training, get involved, and become a frequent diver with many friends who also enjoy diving? You can dive for a lifetime and not even begin to see everything the underwater world has to offer. May all your diving experiences be enjoyable and memorable!

Glossary of Scuba Diving Terms

absolute pressure—The total pressure exerted on a diver, which is measured by adding atmospheric pressure to gauge pressure.

actual bottom time—The elapsed time in minutes from when a diver leaves the surface in descent until the diver begins a rest stop or surfaces.

alternate air source—A source of compressed air other than the diver's primary scuba regulator. The two primary types of alternate air sources are extra second stages and backup scuba units.

ambient pressure—The surrounding pressure.

Archimedes' principle—This principle states that the force of buoyancy acting on a submerged object equals the weight of the water displaced.

arterial gas embolism (AGE)—An embolism resulting from an air bubble blocking the arterial circulation.

atmospheric pressure—The pressure exerted by the atmosphere.

backpack—The equipment that holds the diver's scuba cylinder.

barotrauma—Trauma or injury caused by pressure.

bends—See decompression illness.

bezel—A movable ring on a waterproof watch (being used as an underwater timer) or compass that you can set to indicate elapsed time or direction.

blooms—Overpopulations of plankton that can color the water, destroy underwater visibility, and form toxins in animals that feed by filtering water.

blowout plug—A plug included in a submersible pressure gauge to relieve pressure in the housing in the event of a high-pressure leak.

Bourdon tube—A type of depth gauge that uses a thin metal tube formed into a spiral. The movement of the coil, linked mechanically to a needle, indicates the amount of pressure exerted on the gauge.

Boyle's law—This law states that for any gas at a constant temperature, the volume varies inversely with the absolute pressure, while the density varies directly with the absolute pressure.

buddy breathing—The sharing of a single regulator second stage by two divers.

buddy line—A short line used by two divers to keep in contact with each other when visibility is poor.

buddy system—The practice of teaming up with a qualified partner for activities that involve risk, such as skin and scuba diving. A buddy provides reminders and assistance and sees things that you might not see.

buoyancy—The upward force of water.

buoyancy compensator—An item of equipment that helps a diver control buoyancy. You can inflate your buoyancy compensator at the surface to increase buoyancy, deflate it to reduce buoyancy for descent, and add air to it to achieve neutral buoyancy underwater.

burst disk—A thin metal disk that is a standard feature of the valves for scuba tanks. If a tank is overfilled or the heat from a fire causes the tank pressure to increase to a hazardous level, the disk will burst and vent the tank to prevent an explosion.

capillary gauge—A type of depth gauge that is made up of a hollow, air-filled, transparent plastic tube sealed at one end and placed around a circular dial. Water pressure compresses the air inside the tube during descent (based on Boyle's law), and the position of the air–water interface inside the tube relative to markings on the dial indicates the depth.

cavern—A large, roomlike opening in a natural formation where light from the surface can be seen.

caves—Openings in a natural formation that extend farther than a cavern where no surface light can be seen.

C-card—The certification card you receive when you complete your training requirements as a scuba diver.

ceiling—The minimum depth that a diver cannot rise above without the risk of DCS.

ciguatera—Fish poisoning that results from eating fish that consume a certain species of algae.

closed-circuit—Refers to a scuba system that eliminates carbon dioxide from exhaled breath and resupplies oxygen without allowing gases to escape from the system.

compartments—Mathematical models used to estimate gas absorption and elimination by various areas of the body.

compass course—A series of headings on a compass that leads to a destination.

compass heading—A direction that is set on a compass.

console—A display unit into which several instruments can be combined. An instrument console attaches to the high-pressure hose coming from the regulator first stage.

continental shelf—An underwater area that extends from land and slopes gradually to a depth of about 600 feet (183 meters).

contingency plans—Plans that address possible circumstances that could force changes in the original plans for a dive.

controlling compartment—The area of the body that determines how long a diver can remain at a given depth. The determination is made by how quickly a gas diffuses from that compartment.

crest—The top of a wave.

Dalton's law—A law stating that the total pressure exerted by a mixture of gases is the sum of the pressures that would be exerted by each gas if it alone were present and occupied the total volume.

decompression illness (DCI)—A serious medical condition in which a diver has neurological symptoms on surfacing. Also known as the bends.

decompression stops—Precautionary stops made during ascent in order to reduce the risk of decompression illness.

defogging—The process of removing the film of oil from the surface of the glass lenses on a scuba mask in order to prevent the mask from fogging underwater. Commercial defogging solutions can help keep your mask clear while you dive.

dehydration—A physical condition resulting from the excess loss of body fluids.

density—Weight per unit volume.

DIN valve—A newer type of threaded outlet for a scuba tank valve that has a recessed O-ring seal and withstands higher pressures than a traditional O-ring valve. Tank pressures in excess of 3,000 psi (204 atmospheres) require a DIN fitting.

dive profiles—Diagrams used to plan a dive by plotting the time and depth of the dive.

diver's push-ups—A buoyancy evaluation used to learn buoyancy control. When the diver is weighted properly, a full inhalation will raise the shoulders while the fin tips remain on the bottom, and an exhalation will cause the shoulders to sink.

dolphin kick—A type of fin kick in which a diver holds both feet together continuously and exerts force against the water using a wavelike up-and-down motion of the body.

downwelling—A compensating downward current that occurs when wind blows along a coast where there is a steep drop-off near shore.

drag—A force that slows movement.

drift—The speed of a current.

drift dive—A dive in which the divers move with the flow of the current.

eardrum—A thin membrane that separates the ear canal from the middle ear and transmits vibrations to the inner ear via a series of small bones that are attached to the membrane.

ebb—The flow of water away from an area because of low tide.

eddies—Swirling currents that result from non-linear water flow

embolism—A blockage of circulation.

emergency decompression—A required delay in ascent that a diver must take if the actual or total bottom time (ABT or TBT) exceeds the no-decompression-stop limit for a dive.

equalization—The process of keeping the pressure inside an air space in or attached to the body equal to the ambient pressure.

eustachian tube—The part of the ear that allows the equalization of pressure in the middle ear.

Farmer Johns—A type of wet suit design where the leg material extends upward to cover the chest and is held in place with shoulder straps

fetch—The area in which waves were created.

fetch length—The distance wind travels unobstructed. The length of water over which a given wind has blown.

flaring—A method of slowing an uncontrolled ascent by arching the back, extending the arms and legs, and positioning the fins so they are parallel to the surface.

flood—The flow of water into an area because of high tide.

flutter kick—The most common type of fin kick. The flutter kick is an up-and-down kick that you can do facing down, up, or to the side.

fronds—The portions of kelp that appear to be the leaves.

gauge pressure—The pressure indicated by a pressure gauge that reads zero at sea level (this type of gauge displays only the pressure in excess of one atmosphere).

Gay-Lussac's law—This law states that for any gas at a constant volume, the pressure of the gas varies directly with the absolute temperature.

gyres—Large circulating currents that move clockwise in the northern hemisphere and counterclockwise in the southern hemisphere.

half-time—The amount of time it takes a tissue to accumulate half of the gas it can hold at a given pressure.

heat exhaustion—A medical condition that occurs when the core temperature of the body is above normal and the victim has become dehydrated.

heatstroke—An emergency medical condition that occurs when the body temperature becomes so high that the body's temperature-regulating ability shuts down.

Henry's law—This law states that the amount of a gas that dissolves in a liquid at a given temperature is directly proportional to the partial pressure of that gas.

hyperthermia—Higher-than-normal body core temperature.

hyperventilation—Rapid, deep breathing in excess of the body's needs.

hypothermia—Excessive loss of heat from the core of the body.

hypoventilation—Rapid and shallow breathing that does not allow you to expel carbon dioxide from your lungs.

ingassing—The process of gas diffusion into a liquid.

jumpsuit—A one-piece dive suit.

J-valve—A cylinder valve that was designed to maintain a reserve of air to permit a normal ascent. The introduction of submersible pressure gauges for scuba tanks has rendered the J-valve obsolete.

kelp—Giant algae that produce long strands that a diver can become entangled in.

Kelvin—The absolute temperature scale for Celsius temperatures. To convert a Celsius temperature to Kelvin, add 273 degrees.

K-valve—A cylinder valve that is a simple on-off valve that operates like a faucet. You turn the valve handle counterclockwise to open it and clockwise to close it.

lubber line—A reference line on a compass that indicates the direction of travel.

mediastinal emphysema—A lung injury in which air is present in the tissues in the middle of the chest.

middle ear—The air space behind the eardrum.

modified frog kick—A fin kick in which the diver rotates the ankles so that the tips of the fins point outward, slides the fins tip first in an outward direction, then pulls the bottoms of the fins together quickly in a wide, sweeping arc.

multilevel dive profile—A dive that progresses from deep to shallow during a given period of time.

neap tide—The twice-monthly period of lowest tides, which occurs when the moon and sun are at right angles to each other in relation to the earth.

neutral buoyancy—A state of buoyancy that a diver achieves when the diver neither sinks nor floats when holding an average breath.

nitrogen narcosis—A detrimental effect caused by the increased pressure of nitrogen that occurs at a depth of about 100 feet (30 meters).

nitrox—A nitrogen and oxygen mixture with a higher percentage of oxygen than is found in air. The mixture reduces the effects of nitrogen at depth.

no decompression stop limits—The maximum time that a diver may stay at a specified depth.

nonreference descent—A descent made vertically in water without any external reference.

octopus—A term used to describe an extra second stage.

open-circuit—Refers to a scuba system that permits a diver to breathe compressed air from a pressurized cylinder and exhausts the used gases into the water. Open-circuit systems are the safest and most popular form of scuba system.

open-valve ascent—A method for maintaining neutral buoyancy during an ascent by keeping the BC inflator-deflator valve open while holding the valve in a special way.

O-ring—A soft, circular ring that surrounds the outlet for scuba tank valves.

outgassing—The process of gas diffusing out of a liquid. For diving, it pertains to the diffusing of nitrogen absorbed under pressure.

overturn—The movement of water from the top of a lake to a depth of about 60 feet as a result of water circulation caused by winds. This water movement carries oxygenated water to the bottom and leads to what is called spring diving conditions.

partial pressure—The percentage of the total pressure exerted by each gas in a mixture of gases.

perfusion—The circulation in a tissue.

plankton—Aquatic life-forms that drift with the currents.

pneumothorax—A lung injury in which air is trapped in the chest cavity.

pony tank—A backup scuba unit consisting of a small scuba cylinder with a separate, standard regulator.

ports—The openings in the first stage of a regulator. One of the ports is for high-pressure air measurement with an SPG. The remaining ports are for low-pressure air.

pressure—Force (often weight) per unit area.

pulmonary barotrauma—Any lung injury caused by pressure.

Rankine—The absolute temperature scale for Fahrenheit temperatures. To convert a Fahrenheit temperature to Rankine, add 460 degrees.

reciprocal compass course—A course where the diver moves in a given heading for a given distance and returns to the origination point by reversing the direction of travel.

red tide—Blooms created by a type of red phytoplankton.

reference descent—A descent that the diver controls by following a line or the slope of the bottom.

repetitive dive—Any dive made within 6 to 24 hours (depending on the dive-planning device) of a previous dive.

repetitive group or repetitive group designation—The letter on a dive table that indicates the amount of nitrogen in a diver's body.

residual nitrogen—Nitrogen remaining in your system from a dive made within the past 12 hours.

residual nitrogen time—An amount of time that must be added to the actual bottom time (ABT) of a repetitive dive to determine the total bottom time (TBT). RNT compensates for residual nitrogen remaining in a diver's tissues from previous dives.

rest stop—A precautionary decompression stop during ascent.

reverse block—Discomfort that occurs when the pressure in the middle ear is above normal during an ascent due to blockage of the Eustachian tube.

reverse thermocline—The point of transition from a layer of cold water toward the surface of a lake to a layer of warmer water toward the bottom. This state exists in winter.

rip current—The narrow, strong current that moves away from shore as a result of water flowing back to sea through a narrow opening in an underwater obstruction.

sawtooth dive profile—A dive that progresses from deep to shallow and back to deep.

scissors kick—A fin kick that can be used as a resting kick. While lying on the side, the diver slowly extends one leg backward while extending the other leg forward, and then pulls the legs together quickly.

scombroid—A type of fish poisoning that can result if you eat fish that have not been kept chilled. It produces nausea and vomiting within an hour.

scrolling—A method used by dive computers to provide advance-planning information through a sequential display of time limits for various depths.

scuba—Self-contained underwater breathing apparatus.

semi-closed-circuit—Refers to a scuba system that combines the benefits of closed-circuit and open-circuit systems. Small amounts of used gases are released periodically.

set—The direction assumed by a current.

shallow-water blackout—The sudden loss of consciousness near the surface of the water.

shorty—A one-piece dive suit with short arms and legs used for diving in warm water.

sink—The area formed when the ground collapses into an underground cave system.

siphon—An opening where water is channeled from a sink back into the system.

skip breathing—An attempt to extend one's air supply by holding each breath for several seconds.

slack water—The period of time between flow and ebb when the water has minimal movement.

Spare Air unit—A backup scuba unit consisting of a small scuba cylinder with a special regulator integrated directly into the valve. A Spare Air unit is smaller than a pony tank and provides only enough air to permit an ascent from shallow depths.

spike dives—A dive with a short actual bottom time (ABT), such as a dive to free a fouled anchor.

spring tides—The twice-monthly period of highest tides, which occurs when the moon and sun are aligned with the earth.

square compass course—A series of headings that allows the diver to travel in a square pattern so that the dive ends where it began.

squeeze—A condition that occurs when the pressure on the outside of an air space in or on the body is greater than the pressure inside the air space. This condition may cause pain and injury and may be avoided by keeping the pressures equal (see equalization).

stages—The two parts of a scuba regulator that perform the two steps in the pressure reduction process.

stand—A brief period of time during which the tide neither rises nor falls.

step dive—A dive that is made in a series of steps.

stipes—Long strands of kelp.

subcutaneous emphysema—A lung injury in which air is present in the tissues under the skin. The air swells the tissues around the neck.

submersible pressure gauges—An instrument that measures scuba cylinder pressure.

surf—Breaking waves that occur when the water within the wave moves forward and gives up its energy. This occurs when the depth of the water is about the same as the wave height.

surface interval time—The elapsed time from when a diver surfaces after a dive to the time the diver begins the descent of a repetitive dive.

surge—The back-and-forth subsurface motion of the water within waves when the waves enter shallow water.

swells—The rounded, undulating forms that waves take as they move away from the area in which they were created.

tetrodotoxin—A type of fish poisoning that results from eating exotic fish such as puffer fish or blowfish. Tetrodotoxin is the most serious form of fish poisoning and can cause death within minutes.

thermocline—An abrupt transition from a warmer layer of water to a colder layer of water.

total bottom time—The sum of actual bottom time and residual nitrogen time.

Toynbee maneuver—A method of opening the eustachian tubes by blocking the nostrils, closing the mouth, and swallowing.

trail line—A long line with a float attached that is deployed from the stern of a boat. Divers use the trail line to pull themselves to the boat against the current.

trapdoor effect—A condition that exists when pressure prevents the Eustachian tube from opening. This condition may be overcome by ascending to reduce pressure.

trough—The bottom of a wave.

tsunami—Gigantic seismic waves caused by an underwater earthquake.

turbid—Water that is unclear or murky because of stirred-up sediment.

upwelling—The replacement of warm water at the surface with colder water flowing up from the depths as a result of a strong wind blowing along the shore for a sustained time.

Valsalva maneuver—A method of opening the eustachian tubes by blocking the nostrils, closing the mouth, and gently trying to exhale.

valve seat—The portion of the cylinder valve that closes and stops the flow of air.

vasoconstriction—Narrowing of the blood vessels.

vertigo—A subjective feeling of movement perceived as a spinning sensation.

wave height—The distance from a wave crest to the trough.

wave period—The time it takes two waves to pass a given point.

wave train—A long series of waves.

wavelength—The distance between waves.

Bibliography

Auerbach, P. (1987). *A medical guide to hazardous marine life.* Jacksonville, FL: Progressive Printing.

Barnhart, R., & Steinmetz, S. (1986). *Dictionary of science.* Maplewood, NJ: Hammond.

Bascom, W. (1964). *Waves and beaches.* Garden City, NY: Anchor Books.

Bove, A., & Davis, J. (1990). *Diving medicine.* Philadelphia: W.B. Saunders.

Divers Alert Network. (1989). *Medical requirements for scuba divers.* Durham, NC: Author.

Edmonds, C., Lowry, C., & Pennefather, J. (1981). *Diving and subaquatic medicine.* Mosman, NSW, Australia: Diving Medical Centre.

Foley, B. (1989). *Physics made simple.* New York: Doubleday.

Graver, D. (2004). *Aquatic Rescue and Safety.* Champaign, IL: Human Kinetics.

Lee, P., Lidov, M., & Tyberg, T. (1986). *The sourcebook of medical science.* New York: Torstar.

Lehrman, R. (1990). *Physics the easy way.* Hauppauge, NY: Barron's Educational Series.

Lippmann, J. (1992). *The essentials of deeper sport diving.* Locust Valley, NY: Aqua Quest.

Maloney, E. (1983). *Chapman piloting seamanship and small boat handling.* New York: Hearst Marine Books.

McGraw-Hill Professional Publishers (1998). Concise encyclopedia of science. Camden, Maine: McGraw-Hill.

Miller, J. (Ed.). (1979). *NOAA diving manual* (2nd ed.). Washington, DC: U.S. Government Printing Office, U.S. Department of Commerce.

National Association of Underwater Instructors (NAUI). (1991). *Advanced diving technology and techniques.* Montclair, CA: Author.

Professional Association of Diving Instructors (PADI). (1998). *The encyclopedia of recreational diving.* Santa Ana, CA: Author.

Sebel, P., Stoddart, D., Waldhorn, R., Waldmann, C., & Whitfield, P. (1985). *Respiration: The breath of life.* New York: Torstar.

Taylor, E. (Ed.). (1985). *Dorland's illustrated medical dictionary.* Philadelphia: W.B. Saunders.

Whitfield, P., & Stoddart, D. (1984). *Hearing, taste, and smell: Pathways of perception.* New York: Torstar.

This page intentionally left blank.

Index

Note: The italicized *f* and *t* following page numbers refer to figures and tables, respectively.

A
AAS. *See* alternate air source
abrasions 114, 116*t*
absolute pressure 23, 26-27
ABT. *See* actual bottom time
accessories 101-104, 101*f*-102*f*
accidents 180-181, 189
actual bottom time (ABT) 194, 199-202
adjustments. *See* diving adjustments
advance preparation 185-187
AGE (arterial gas embolism) 50, 57
air
  composition 16, 16*f*
  consumption 28, 30-31, 34
  environment 19-23, 19*f*, 20*t*, 21*f*-22*f*, 118
  supply, loss of 49, 174-177, 175*f*-176*f*
alternate air source (AAS) 64, 94-96, 94*f*-95*f*
alternobaric vertigo 52
altitude 200, 202-203, 202*t*
aluminum cylinders 83-85
ambient (surrounding) pressure 53
anatomy 12-15, 13*f*, 15*f*
animals, dangerous 114-117, 114*f*-115*f*, 116*t*, 180
aquatic biology 110-117, 111*f*-115*f*, 116*t*
aquatic conditions 121-132, 123*f*-125*f*, 127*f*, 129*f*-131*f*
Archimedes' principle 21
area orientations 189-190
arterial gas embolism (AGE) 50, 57
ascents
  emergency 175-176, 175*f*
  scuba diving 159-160, 166, 174-176, 174*f*-175*f*, 200-201
  skin diving 146-147, 147*f*
atmospheric pressure 22-23, 22*f*

B
backpack 79, 149, 149*f*
back-roll entry 155, 155*f*
backup scuba units 94-95, 95*f*
barotrauma 50
BC. *See* buoyancy compensator
BEA. *See* buoyant emergency ascent
the bends. *See* decompression illness
bezel 97
biology, aquatic 110-117, 111*f*-115*f*, 116*t*
bites, animal 115, 116*t*
blooms 110
blowout plug 99
boat diving 132-135, 133*f*-134*f*, 153-154
boots 73, 73*f*, 76, 77*f*, 78
bottom dwellers 113
bottom time (BT) 200
bounce dive 198, 198*f*
Bourdon tube 96-97, 96*t*
Boyle's law 23-24, 24*f*, 27, 96
breathing 15-18, 16*f*-17*f*, 19*f*, 28, 47
  adjustments 46-51, 48*f*
  buddy 175-177, 175*f*-176*f*
BT (bottom time) 200
buddy breathing 175-177, 175*f*-176*f*
buddy check 152
buddy line 162
buddy system 152, 162-163, 172, 173*f*, 175-177, 176*f*-177*f*
buoyancy 21-22, 21*f*, 59, 60*f*
  adjustments 41-43, 42*t*
  control 119, 159-160, 173-174
  equipment and 66, 70, 73, 75-76, 78-83, 80*f*-81*f*, 80*t*, 85-86, 86*t*
  neutral 21, 142, 158-159, 161
  testing 142, 158
buoyancy compensator (BC)
  equipment 64, 80-83, 80*f*-81*f*, 80*t*, 138-139, 150-151, 153, 157-160, 174
  inflating and deflating 152-153, 157-160, 174
buoyant emergency ascent (BEA) 175-176
burst disk 88

C
calculators, dive 204-206, 204*t*
California 216
capillary gauge 96-97, 96*t*
cardiorespiratory system 16, 17*f*
CARE. *See* cognizance, assessment, rescue, and evacuation
career opportunities 218
Caribbean 217
carotid sinuses 18, 18*f*
cavern 124, 125*f*
caves 124, 125*f*
C-card 4
CCR. *See* closed-circuit rebreather
ceiling 99
certification 4
charter boat diving 133-134, 133*f*-134*f*, 190
ciguatera 112
circulation 15-18, 17*f*-18*f*
closed-circuit rebreather (CCR) 3, 4*t*, 105-106, 105*f*
cognizance, assessment, rescue, and evacuation (CARE) 178-179
cold 32, 51, 201
collapsed lung 51
communication 178
community, diving 3-5
compartments 54-55
compass course 164-165
compasses, dive 97-98, 98*f*, 164-165, 164*f*-165*f*
compass heading 164
computers, dive 99, 204-206, 204*t*
congested sinuses 44, 44*f*
conservation 117-121, 119*f*
consoles 98*f*, 99-100
continental shelf 126
contingency plans 203-204, 203*f*
continuing education 210-212, 219
controlling compartment 55
coughing 172
cramps 172, 173*f*
crest 128
currents 124, 124*f*, 130-132, 130*f*-131*f*, 187, 188*f*
cuts 114, 116*t*
cylinders 83-87, 83*f*-85*f*, 86*t*, 149-150, 149*f*-150*f*
cylinder valves 87-89, 88*f*

D
Dalton's law 25-26, 26*t*
dangerous aquatic animals 114-117, 114*f*-115*f*, 116*t*, 180
decompression illness (DCI) 7, 55-57, 56*f*-57*f*, 190, 200
decompression stops 55, 57*f*, 190, 196, 196*t*, 200-201
decompression theory 53-55, 54*f*
defogging 29, 66, 139
dehydration 29, 58-59
density 19*f*, 20, 20*t*, 23-24, 24*f*
depth 200
depth gauges 96-97, 96*t*, 100
descents 146-147, 161
destinations 216-218
diaphragm gauge 96-97, 96*t*
DIN valve 88, 88*f*

dive calculators 204-206, 204*t*
dive compasses 97-98, 98*f*, 164-165, 164*f*-165*f*
dive computers 99, 204-206, 204*t*
dive courses 8, 8*f*
dive flags 101-102, 101*f*, 160, 160*f*
dive floats 102
dive kits 102-104
dive knives 100-101, 100*f*, 152
dive lights 102, 102*f*
dive planning
  advance preparation 185-187
  area orientations 189-190
  calculators for 204-206, 204*t*
  computers for 99, 204-206, 204*t*
  contingency 203-204, 203*f*
  dive profile 188, 190-191, 190*f*, 197-204, 198*f*-199*f*, 202*t*, 203*f*
  dive tables for 191-197, 192*t*-193*t*, 195*t*-196*t*, 204, 204*f*
  factors 184-185
  on-site 187-188, 188*f*
  postdive review 206
  short-term 187
  special-equipment 197
  special procedures 201-203, 202*t*
dive profile 188, 190-191, 190*f*, 197-206, 198*f*-199*f*, 202*t*, 203*f*
diver impact 118-119, 119*f*
diver's push-ups 158, 159*f*
dive slates 102-103
dive tables 191-197, 192*t*-193*t*, 195*t*-196*t*, 204, 204*f*
diving. *See also* equipment; scuba diving; skin diving
  altitude and 200, 202-203, 202*t*
  boat 132-135, 133*f*-134*f*, 153-154
  buddy 162-163, 172, 173*f*, 175-177, 176*f*-177*f*
  community 3-5
  conditions 121-132, 123*f*-125*f*, 127*f*, 129*f*-131*f*
  drift 132
  evolution of 3
  guides 4
  joys of 2, 9
  periodicals 222
  prerequisites 5-6
  risks 6-8
  surface 145, 146*f*
  training for 5-8, 8*f*, 221
  travel 213-218
diving adjustments
  breathing 46-51, 48*f*
  buoyancy 41-43, 42*t*
  dehydration prevention 58-59
  equilibrium 52-53
  heart and lungs 50-52
  importance of 38, 61
  ingassing and outgassing 53-58, 54*f*, 56*f*-57*f*
  mobility 59, 60*f*
  thermal 38-41, 39*f*, 41*f*
  visual 53
diving environment
  aquatic biology 110-117, 111*f*-115*f*, 116*t*
  aquatic conditions 121-132, 123*f*-125*f*, 127*f*, 129*f*-131*f*
  for boat diving 132-135, 133*f*-134*f*
  conservation and preservation 117-121, 119*f*
diving opportunities
  career 218
  continuing education 210-212, 219
  leadership 219
  local 212-213
diving skills
  automatic execution of 139, 191
  for emergencies 178-181, 179*f*
  physical problem management 173-177, 174*f*-177*f*
  physiological problem management 169-172, 172*f*-173*f*
  scuba diving 152-169, 153*f*-155*f*, 159*f*-160*f*, 163*f*-165*f*, 167*f*-169*f*
  skin diving 141-148, 141*f*, 143*f*-147*f*
dizziness 170
dolphin kick 145, 145*f*
downwelling 130
drag 20-21, 20*t*, 59, 60*f*
drift 132
drift dive 132
drifters 110-111, 111*f*-112*f*
dry suits 75-77, 75*t*, 76*f*-77*f*

E
EANx. *See* enriched-air nitrox
eardrum 14, 15*f*, 52
ears 14-15, 15*f*, 44-46, 45*f*, 52
ebb 127
eddies 124
education, continuing 210-212, 219
electronic gauge 96-97, 96*t*
embolism 50
emergencies 178-181, 179*f*, 188
emergency decompression 201, 203*t*
emergency swimming ascent (ESA) 175-176, 175*f*
emphysema 50-51
enriched-air nitrox (EANx) 104-105, 104*f*
entanglement 173
entry techniques 152-155, 153*f*-155*f*
environment. *See also* diving environment
  air 19-23, 19*f*, 20*t*, 21*f*-22*f*, 118
  water 19-23, 19*f*, 20*t*, 21*f*-22*f*, 28-29, 29*f*, 32-34, 32*f*
environmental organizations 121, 221
equalization 7, 14, 24, 25*f*, 43-46, 44*f*-45*f*
equilibrium adjustments 52-53
equipment. *See also* exposure suits; fins; mask
  AAS 64, 94-96, 94*f*-95*f*
  accessories 101-104, 101*f*-102*f*
  assembling 149-151, 149*f*-150*f*
  BC 64, 80-83, 80*f*-81*f*, 80*t*, 138-139, 150-151, 153, 157-160, 174
  buoyancy and 66, 70, 73, 75-76, 78-83, 80*f*-81*f*, 80*t*, 85-86, 86*t*
  checklist 82
  cylinder valves 87-89, 88*f*
  disassembling 169
  dive knives 100-101, 100*f*
  diver impact and 119
  donning 139-141, 140*f*, 151-152
  handling 147-148, 166
  inspecting 139-140, 151-152
  instrumentation 96-100, 96*f*, 98*f*, 152
  introduction to 64, 65*f*
  nitrox 104-105, 104*f*, 197
  packing 148-149, 149*f*
  preparing 138-141, 140*f*
  removing 148
  scuba cylinders 83-87, 83*f*-85*f*, 86*t*, 149-150, 149*f*-150*f*
  scuba regulators 89-94, 89*f*-92*f*, 149-152, 150*f*, 156-157
  skin diving 70-71, 70*f*, 138-141, 140*f*, 147-148
  snorkel 67-68, 67*f*-68*f*, 138, 140, 143-144, 143*f*, 152, 155-157
  specialized 104-106, 104*f*-105*f*, 197
  surface snorkeling with 155-156
  for technical diving 105-106, 105*f*
  training 8, 8*f*
  weighting systems 78-80, 78*f*, 138-140, 147-148, 152
  weight of 59, 60*f*
ESA. *See* emergency swimming ascent
eustachian tubes 14, 15*f*, 44-46, 45*f*
exit techniques 168-169, 168*f*-169*f*
exposure suits
  dry suits 75-77, 75*t*, 76*f*-77*f*
  preparing 138-139, 152
  wet suits 71-75, 71*t*, 72*f*-74*f*, 77-78
extra second stages 94-95, 94*f*

F
Farmer Johns 72*f*, 73
feet-together entry 155
fetch 128
fins 69-70, 69*f*-70*f*, 152
  donning 138, 140, 140*f*
  removing 148
  using 144-145, 144*f*-145*f*, 147
first aid 103-104, 116*t*, 178-180
flags 101-102, 101*f*, 160, 160*f*
flaring 174, 174*f*, 176
floats 102

flood 127
Florida 217
flutter kick 144, 144*f*
flying 200, 202, 202*t*, 215
food cycle, underwater 110-111, 111*f*
freshwater diving conditions 122-126, 123*f*-125*f*
fronds 111

G
gases 16, 16*f*, 18, 19*f*, 26-27, 26*t*
gas laws 23-28, 24*f*-25*f*, 26*t*, 96
Gay-Lussac's law 24-25, 27
gear bags 101
giant-stride entry 154, 154*f*
Great Lakes 217
guides 4
gyres 130

H
habits 191
half-time 54, 99
hand coverings 73-74, 74*f*, 76, 77*f*, 78
hand signals
  scuba diving 166, 167*f*
  skin diving 141, 141*f*
Hawaii 217
head-to-toe buddy check 152
hearing 14, 15*f*, 34
heart 50-52
heat
  exhaustion 40, 41*f*
  loss 28-29, 29*f*, 39-40, 39*f*
heatstroke 40, 41*f*
Henry's law 25-26, 26*t*
high altitude diving 200, 202, 202*t*
hoods 74, 74*f*, 76, 78, 139
humidity 29
hydroids 113-114, 113*f*, 116
hyperthermia 38
hyperventilation 18, 19*f*
hypothermia 38, 40
hypoventilation 18

I
ingassing 26, 53-58, 54*f*, 56*f*-57*f*
injuries 50, 114-117, 116*t*, 179-181
instrumentation
  equipment 96-100, 96*f*, 98*f*, 152
  monitoring 165-166

J
job opportunities 218
jumpsuit 72*f*, 73
J-valve 88

K
kelp 110-111, 112*f*, 216
kicks 144-145, 144*f*-145*f*, 164
kits 102-104
knives 100-101, 100*f*, 152
K-valve 87, 88*f*

L
lacerations 114-115, 116*t*
laws 4
leadership opportunities 219
lifesaving scuba 178-179, 179*f*
lift 59, 60*f*
light 32-33, 32*f*
lights, dive 102, 102*f*
local diving opportunities 212-213
lubber line 98
lungs 12, 13*f*, 47, 48*f*, 50-52, 176

M
magazines 222
mask 46, 65-67, 65*f*-66*f*, 138-140, 147-148, 152
  clearing 142-143, 143*f*, 162
  defogging 29, 66, 139
maximum-depth indicator 97
mediastinal emphysema 50
menstruation 6
middle ear 14, 15*f*, 52
Middle East 218
mobility adjustments 59, 60*f*
modified frog kick 144, 145*f*
multilevel dive profile 197, 198*f*

N
navigation 97-98, 98*f*, 164-165, 164*f*-165*f*
NDSL. *See* no decompression stop limit
neap tides 126
neutral buoyancy 21, 142, 158-159, 161
New England 217
nitrogen narcosis 16, 58
nitrox equipment 104-105, 104*f*, 197
no decompression stop limit (NDSL) 191, 194-197, 195*t*, 199-200, 202
nonreference descents 161

O
octopus 94
on-site planning and preparation 187-188, 188*f*
open-circuit scuba 3, 4*t*
open-valve ascent 159-160, 166
organizations 121, 221
O-ring 88-89, 150-151
outgassing 26, 28, 53-58, 54*f*, 56*f*-57*f*, 166
overexertion 47-48, 172
overheating 40-41, 41*f*
overturn 122, 123*f*
overweighting 163, 163*f*

P
packing 148-149, 149*f*
panic 170-172, 172*f*
partial pressure 26-27, 26*t*
periodicals 222
physical problems, managing 173-177, 174*f*-177*f*
physiological problems, managing 169-172, 172*f*-173*f*
plankton 110, 111*f*
planning. *See* dive planning
pneumothorax 51
pollution 117-118
pony tank 95, 95*f*
ports 91
postdive review 206
preparation
  scuba diving 148-152, 149*f*-150*f*, 185-188, 188*f*
  skin diving 138-141, 140*f*
prerequisites, diving 5-6
preservation 117-121, 119*f*
pressure
  absolute 23, 26-27
  ambient 53
  atmospheric 22-23, 22*f*
  equalization 7, 14, 24, 25*f*, 43-46, 44*f*-45*f*
  gas laws and 23-24, 24*f*
  injury from 50
  measurement 22-23, 22*f*
  partial 26-27, 26*t*
  reduction, stages of 89-95, 90*f*-92*f*, 94*f*
proficiency testing 5
Puget Sound 216
pulmonary barotrauma 50
punctures 114-115, 116*t*

R
Rankine 25
reciprocal compass course 165
recompression chamber 56, 56*f*
recreational diving 3-4
Red Sea 218
red tide 110
reference descents 161
regulators, scuba 89-94, 89*f*-92*f*, 149-152, 150*f*, 156-157
repetitive dive 190-191, 190*f*, 194, 200
repetitive group designation (RGD or RG) 191, 194, 200
reserve valve 88
residual nitrogen 190, 190*f*, 194-197, 195*t*
residual nitrogen time (RNT) 194-202, 195*t*
respiration 15-18, 16*f*-17*f*, 19*f*
responsibilities 9
rest stops 55, 57*f*, 190, 196, 196*t*, 200-201
reverse blocks 24, 25*f*
reverse thermocline 122, 123*f*
RG. *See* repetitive group designation
RGD. *See* repetitive group designation
rip current 131, 131*f*

risks 6-8
RNT. *See* residual nitrogen time

S

safety stops 55, 57*f*, 190, 196, 196*t*, 200-201
saltwater diving conditions 126-132, 127*f*, 129*f*-131*f*
save-a-dive kit 102-103
sawtooth dive profile 197, 198*f*
scissors kick 144, 144*f*
scombroid 112
scrolling 204-205
scuba (self-contained underwater breathing apparatus)
  backup 94-95, 95*f*
  cylinders 83-87, 83*f*-85*f*, 86*t*, 149-150, 149*f*-150*f*
  lifesaving 178-179, 179*f*
  regulators 89-94, 89*f*-92*f*, 149-152, 150*f*, 156-157
  systems 3, 4*t*
scuba diving
  ascents 159-160, 166, 174-176, 174*f*-175*f*, 200-201
  descents 161
  entry techniques 152-155, 153*f*-155*f*
  exit techniques 168-169, 168*f*-169*f*
  hand signals 166, 167*f*
  at high altitude 200, 202, 202*t*
  laws 4
  navigation 97-98, 98*f*, 164-165, 164*f*-165*f*
  organizations 221
  preparation for 148-152, 149*f*-150*f*, 185-188, 188*f*
  prerequisites 5-6
  recreational 3-4
  responsibilities 9
  rules 156, 200
  skills 152-169, 153*f*-155*f*, 159*f*-160*f*, 163*f*-165*f*, 167*f*-169*f*
  technical 105-106, 105*f*
  underwater swimming in 163-164, 163*f*
  wreck diving 217
sculling 119, 119*f*
seasickness 52-53, 170
seated entry 154, 154*f*
self-contained underwater breathing apparatus. *See* scuba
semi-closed-circuit scuba 3, 4*t*
set, of current 132
shallow-water blackout 18
short-term planning and preparation 187
shorty 72*f*, 73
signaling devices 102-103
signals. *See* hand signals
silting 163, 163*f*
simple valve 87-88, 88*f*
sink 125
sinuses 12, 13*f*, 43-44, 44*f*
siphon 125
SIT. *See* surface interval time
skills. *See* diving skills
skin diving
  ascents 146-147, 147*f*
  equipment 70-71, 70*f*, 138-141, 140*f*, 147-148
  hand signals 141, 141*f*
  preparation 138-141, 140*f*
  prerequisites 5-6
  recreational 4
  skills 141-148, 141*f*, 143*f*-147*f*
skip breathing 47
slack water 127
slates 102-103
small-boat diving 134-135
snorkel 67-68, 67*f*-68*f*, 138, 140, 143-144, 143*f*, 152, 155-157
snorkeling 155-156
snorkel–regulator exchanges 157
sound 34
South Pacific 217
Spare Air unit 95, 95*f*
specialized equipment 104-106, 104*f*-105*f*, 197
SPGs. *See* submersible pressure gauges
spike dive 198, 198*f*
spring tides 126, 127*f*
square compass course 164-165
squatting back-roll entry 155, 155*f*
squeezes 24, 25*f*
stages, of pressure reduction 89-95, 90*f*-92*f*, 94*f*
stand 126
steel cylinders 83-85
step dive 197, 198*f*
stings, animal 115-116, 116*t*
stipes 110
stress 170-172, 172*f*
subcutaneous emphysema 51
submersible pressure gauges (SPGs) 88, 98-100, 98*f*, 150, 152, 165
surf 128-130, 129*f*, 153, 153*f*, 169, 169*f*
surface dives 145, 146*f*
surface interval time (SIT) 194-196, 195*t*, 200
surface snorkeling 155-156
surge 128
surrounding pressure. *See* ambient pressure
swells 128
swimmers 112-113, 112*f*
swimming
  ESA 175-176, 175*f*
  kicks 144-145, 144*f*-145*f*, 164
  surface dives 145, 146*f*
  underwater 146-147, 147*f*, 163-164, 163*f*

T

tanks. *See* cylinders
task-relevant instructional self-talk (TRIST) 171
TBT. *See* total bottom time
technical diving 105-106, 105*f*
teeth 15
temperature 20, 23-27, 32, 34. *See also* thermal adjustments
tetrodotoxin 112
thermal adjustments 38-41, 39*f*, 41*f*
thermocline 122, 123*f*
throat 12, 13*f*
thrust 59, 60*f*
tides 126-128, 127*f*
total bottom time (TBT) 194-202
Toynbee maneuver 44
trail line 133, 134*f*
training 5-8, 8*f*, 210-212, 221
trapdoor effect 45, 45*f*
travel 213-218
TRIST (task-relevant instructional self-talk) 171
trough 128
tsunami 126
turbid water 33

U

underwater food cycle 110-111, 111*f*
underwater swimming 146-147, 147*f*, 163-164, 163*f*
underwater timers 97
upwelling 123

V

Valsalva maneuver 44
valves, cylinder 87-89, 88*f*
valve seat 87
vasoconstriction 39
venomous injuries 114-115, 116*t*, 180
vertigo 33, 52
vests 74, 74*f*, 138-139, 142, 148
visibility 33, 162
vision 32-33, 32*f*, 67
visual adjustments 53
volume 23-24, 24*f*
vomit 52, 133, 170

W

wading entry 153, 153*f*
Washington 216
water
  environment 19-23, 19*f*, 20*t*, 21*f*-22*f*, 28-29, 29*f*, 32-34, 32*f*
  slack 127
wave height 128
wavelength 128
wave period 128
waves 128-130, 129*f*
wave train 128
weighting systems 78-80, 78*f*, 138-140, 147-148, 152
wet suits 71-75, 71*t*, 72*f*-74*f*, 77-78, 139, 148
wreck diving 217

About the Author

Dennis Graver has more than 30 years of experience as a scuba instructor and instructor trainer. He has authored 27 books and manuals on scuba diving, including three previous editions of *Scuba Diving* from Human Kinetics. In his position as director of training for the Professional Association of Diving Instructors (PADI), he designed the PADI modular scuba course and wrote the *PADI Dive Manual*, which revolutionized scuba instruction. During his tenure as director of education for the National Association of Underwater Instructors (NAUI), Graver wrote several diving texts, including the *NAUI Openwater I Scuba Diver Course Instructor Guide*. He has also contributed hundreds of articles on diving to such magazines as *Skin Diver*, *Sources*, and *Undercurrents* as well as several NAUI technical publications.

Since 1977 Graver has been photographing many wonders under the water, from the Red Sea off the coast of Egypt to the barrier reefs of Australia. He has won numerous awards from the Underwater Photographic Society, and his photos have graced the covers of numerous magazines and illustrated several diving texts and audiovisual educational programs.

Graver and his wife, Barbara, live in Camano Island, Washington.

You'll find other outstanding
outdoor and adventure resources at

www.HumanKinetics.com/outdoorandadventure

In the U.S. call 1-800-747-4457
Australia 08 8372 0999 • Canada 1-800-465-7301
Europe +44 (0) 113 255 5665 • New Zealand 0064 9 448 1207

HUMAN KINETICS
The Premier Publisher for Sports & Fitness
P.O. Box 5076 • Champaign, IL 61825-5076 USA

eBook
available at
HumanKinetics.com

EYEWITNESS COMPANIONS

Scuba Diving

MONTY HALLS & MIRANDA KRESTOVNIKOFF

AQUA LUNG
FIRST TO DIVE

TECHNIQUES • EQUIPMENT
MARINE LIFE • DIVE SITES

EYEWITNESS COMPANIONS

Scuba Diving

MONTY HALLS &
MIRANDA KRESTOVNIKOFF

DK

“WE FORGET THAT THE
WATER CYCLE AND THE LIFE
CYCLE ARE ONE.”

Jacques Cousteau

LONDON, NEW YORK,
MUNICH, MELBOURNE, DELHI

Project Editor Richard Gilbert
Project Art Editor Mark Cavanagh

Managing Editor Stephanie Farrow
Managing Art Editor Lee Griffiths

Publishing Director Jonathan Metcalf
Art Director Bryn Walls

DTP Designer Vania Cunha
Production Controller Melanie Dowland

Produced for Dorling Kindersley by

cobaltid
The Stables, Wood Farm, Deopham Road,
Attleborough, Norfolk NR17 1AJ
www.cobaltid.co.uk

EDITORS
Marek Walisiewicz,
Jamie Dickson, Maddy King,
Kati Dye, Steve Setford

ART EDITORS
Paul Reid, Lloyd Tilbury,
Claire Oldman, Darren Bland,
Rebecca Johns

Commissioned photography by Dan Burton

First American Edition, 2006
Published in the United States by DK Publishing, Inc.,
375 Hudson Street, New York, NY 10014

06 07 08 09 10 10 9 8 7 6 5 4 3 2 1

Copyright © 2006 Dorling Kindersley Limited

This companion guide is intended to help you understand the key principles that enable divers to practice their sport enjoyably and safely. It is not a training manual, and it is recommended that you read this guide in conjunction with an accredited course of diving instruction and official training literature. Diving centers around the world will ask to see evidence of formal qualifications before allowing you to rent equipment, have your tank filled, or join a diving trip. The authors and publishers have made every effort to ensure that the information in this book is correct at press time. However, they accept no responsibility for any injury, accident, or inconvenience sustained by any person using this book or following advice presented in it.

All rights reserved under International and Pan-American Copyright Conventions. No part of this publication may be reproduced, stored in a retrieval system, or transmitted in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, without the prior written permission of the copyright owner. Published in Great Britain by Dorling Kindersley Limited.

A Cataloging-in-Publication record for this book
is available from the Library of Congress.

ISBN-13: 978-0-7566-1949-7
ISBN-10: 0-7566-1949-1

DK books are available at special discounts for bulk purchases for sales promotions, premiums, fund-raising, or educational use. For details, contact: DK Publishing Special Markets, 375 Hudson Street, New York, NY 10014 or SpecialSales@dk.com
Color reproduction by GRB, Italy
Printed in China by Leo

Discover more at
www.dk.com

Introduction
10

Chapter One

HISTORY OF DIVING
20

The story of diving's evolution, describing the pioneering figures, scientific breakthroughs, and record descents that have helped to shape the modern sport.

Chapter Two

GETTING STARTED
30

How and where to learn diving, including information on training agencies and clubs, advanced and specialized training, and what to expect from instruction.

CONTENTS



Chapter Three

EQUIPMENT

40

Information on essential items of diving gear, including what you need, how things work, and how to assemble and maintain your scuba equipment.

Chapter Four

THE DIVING ENVIRONMENT

90

The physical principles that underpin the sport of diving, including perception underwater, decompression theory, and how currents and tides work.

Chapter Five

DIVING SKILLS

104

Key diving techniques, procedures, and safety measures, featuring step-by-step instructions on how to master fundamental skills, and advice on fitness for divers.

Chapter Six

GOING DIVING

156

How to research, plan, and conduct independent dives, plus information and advice on popular diving activities and specialty pursuits.



Chapter Seven

UNDERWATER LIFE

198

A natural history of the world's marine and freshwater zones, with detailed information on key environments, animals, and natural processes.

Chapter Eight

PLACES TO DIVE

234

An illustrated directory of the world's best dive destinations, including famous wrecks, marine life hot spots, and adventure dives.

Useful Resources
328

Glossary
331

Index and Acknowledgments
336

THE IDEA THAT PEOPLE COULD BREATHE UNDERWATER WAS ONCE A FANTASY. BUT TODAY, DIVING HAS LEFT THE REALMS OF IMAGINATION AND GROWN INTO A WORLDWIDE SPORT WITH MILLIONS OF FOLLOWERS. THOSE WHO TAKE PART IN IT ARE GRANTED PRIVILEGED ACCESS TO A MYSTERIOUS YET BEAUTIFUL WORLD, AND EVERY DIVE IS AN ADVENTURE INTO THE UNKNOWN.

Since prehistoric times, people have been drawn to explore the incredible world that lies underwater, whether in pursuit of food or lost riches, or from sheer inquisitiveness. There is evidence, for example, that people were holding their breath and diving for shellfish by about 3,000 BCE (*see p.22*).

Despite this long relationship with the undersea world, the human body is not designed to remain underwater for prolonged periods of time. Only comparatively recently, with the development of rudimentary diving bells and helmets from the Middle Ages onward, did it become possible to stay submerged for longer than a single breath allows. During the 18th and 19th centuries, there were remarkable advances in diving technology, such as full diving suits supplied by air pumped from the surface. These advances, which were often spurred on by the lucrative rewards of salvage work, extended dive times and gave access to ever greater depths.

THE DAWN OF AN ERA
Diving pioneer Jacques Cousteau (*right*) models early scuba equipment.

The invention of the Aqua Lung in the mid-20th century permitted divers to explore the depths of the world's oceans freely for the first time. This truly remarkable apparatus enables people to take their own air supply with them when they dive, eliminating the need to be connected to the surface by an airline. The system that evolved from it—scuba—is today widely used in recreational and professional diving.

GLOBAL APPEAL

As scuba technology became cheaper, diving opened up to the general public. What was once the realm of experts and professionals gradually became a sport with global appeal. Even in countries

WRECK DIVING
Divers inspect a wreck in tropical waters. Such underwater relics offer a glimpse into maritime history, and are home to colonies of sea life.

A NEW GENERATION
Trainee instructors receive a group briefing at a dive center in Egypt. For many, a job in diving represents the ultimate career move.

without a coastline, you will find divers who spend time underwater at inland sites, such as lakes and rivers, or who travel abroad to experience the beauty of the oceans. Once you are qualified, you can dive virtually anywhere in the world. Language is no barrier underwater, since divers use standard hand signals that are understood internationally.

It is difficult to estimate how many divers there are worldwide, but well over a million people qualify each year. Since its inception in 1966, over 13 million divers around the world have been certified by PADI (the Professional Association of Diving Instructors), and PADI is just one of many training agencies. Diving is one of the fastest-growing hobbies in the world today.

SILENT ODYSSEY
Clown fish shelter in an anemone while a diver swims by. The underwater world can be a uniquely serene environment.

THE WORLD'S OCEANS

Covering approximately 71 percent of the Earth's surface, or 140 million sq miles (361 million sq km), the vast size of the world's oceans is difficult to comprehend. The total volume of sea water is about 322,300,000 cu miles (1,347,000,000 cu km), equivalent to around 97 percent of all the Earth's water—the rest exists as glaciers, rivers, lakes, groundwater, and atmospheric vapor. The average depth of the world's oceans is 2.3 miles (3.8 km); the deepest point is in the Pacific Ocean's Mariana Trench, where the seabed plunges to a depth of nearly 7 miles (11 km). With only about 5 percent of the ocean floor having been mapped in detail, we know more about the surface of the Moon than the bottom of our oceans.

The oceans teem with wildlife, from giant kelp and the mighty blue whale (the largest animal alive) to microscopic plankton that form the basis of the oceanic food chain. Scientists estimate that there may be between 500,000 and 10 million marine species yet to be discovered. While much of the oceans' biological wealth is concentrated between continental shelves and coastal margins, the open sea also abounds with life. Even the mud on the floor of the Mariana Trench is home to single-celled organisms called foraminiferans.

NATURAL WONDERS
Diving can lead to encounters with many intriguing and beautiful marine creatures, such as this leafy sea dragon.



GETTING READY
Buddy pairs prepare for a beach dive. By working in pairs, donning awkward gear becomes considerably easier and safer.

EXPLORING THE UNDERWATER WORLD

What will I see? What will it feel like? Will I feel claustrophobic? These are all questions you will ask as a novice diver entering the underwater world for the first time. Everyone feels different about being underwater; some people take to it immediately, but others need more training and experience before they feel at ease. Either way, it is an unforgettable experience. There is the initial thrill of being able to breathe underwater, and also the novelty of moving freely in three dimensions, thanks to the buoyancy provided by the water, which is a denser medium than air. This same buoyancy can enable those with mobility problems on land to feel relaxed and move more easily in water, and give what some divers call a “womblike” experience.

Imagine the thrill of being the first person to see a sunken ship or coral reef, or of coming face to face with a wild dolphin, or diving under ice. Whatever excites you—whether it be encounters with fascinating creatures, investigating shipwrecks, or just diving into the unknown—you will not fail to be satisfied by what the oceans have to offer.

CAPTURING THE MOMENT
Underwater photography is an absorbing activity in its own right, and offers the chance to record your dive experiences for posterity.

CONSERVATION WORK
A diver jots down his observations of marine life at a conservation site. Divers can play an active role as "stewards of the seas."

BUT IS IT SAFE?

Many people new to the sport worry about the safety aspect. It is true that a small number of divers die every year while pursuing their sport. The majority of these incidents are not due to equipment failure, as some people might suppose, but rather to inadequate training, diving in extreme conditions, or diving beyond the limits of safe practice.

Diving today is safer than it has ever been. If you undertake the correct training and adhere to recommended safety procedures, you will rarely encounter problems. Dive training is thorough, and a great emphasis is placed on rescue skills and the importance of diving in a buddy pair (*see pp.110–11*). Good communication with your buddy is essential, as most minor difficulties can be easily resolved with the help of another diver.

NEW SKILLS, NEW DIRECTIONS

You may find that you enjoy diving so much that you want to pursue it beyond the hobby level. Some people use their underwater knowledge and skills for voluntary or charitable work, or in a full-time career. The directions in which diving can take you are endless, from environmental projects, marine archaeology, historical research, and working with disabled divers, to filming and photography, and even training to be a diving instructor yourself.

RECOGNITION GUIDE
A pair of divers consult a species identification slate. Becoming familiar with marine life, in all its fascinating variety, is part of the fun.

RESPECT AND RESPONSIBILITY

Ask any group of divers what inspired them to take up the sport and you will hear a range of different answers, from a love of the sea to a desire to challenge their personal limits. One thing they all have in common is the fact that they return again and again to the water—the magical environment that Jacques Cousteau (*see p.26*) described as the "Silent World." Divers should be custodians of the world's oceans, and respect what they contain: "take only pictures and leave only bubbles" is a good maxim for low-impact diving.

Many of the marine ecosystems around the world are today in decline. Hopefully education and investment will help to reverse this trend, so the divers of tomorrow will have healthy oceans to explore. By taking part in conservation work and diving responsibly, you can become a force for the good in preserving the oceans' natural treasures.

DISCUSSING A DIVE
Diving is a social sport, and the diving community is a supportive one. Experienced divers are often willing to offer advice to novices.

MARINE LIFE
A diver examines a beautiful and delicate sea pen—a colonial polyp organism—growing out of white sand next to the Great Barrier Reef.

GLIMPSE OF A GIANT
Anticipation of a dive can be almost as thrilling as the dive itself. Sighting large animals, such as rays, from the boat adds to the excitement.

UNDERSEA GARDEN
Coral thrives in clear, shallow water, because it needs plenty of light to live. Such reefs are an ideal environment to explore while snorkeling.

REEF SAFARI
Coral reefs are home to diverse marine species, offering sheltered areas for sedentary animals, and feeding grounds for predators and foragers.







CRYSTAL WATERS
Exploring the shallows above reefs is a perfect pastime between dives. Many thousands of fascinating marine species live in these areas.

CLOUDS OF FISH
Shoals of orange antheas are a common sight on the reefs of the Indo-Pacific. They appear to move as one when startled.

FROM WRECK TO REEF
In tropical waters, a wreck provides a firm platform for coral growth. Wrecks are swiftly colonized by marine life, creating eerie reefs.

LONE VOYAGER
If approached cautiously and respectfully, turtles will happily tolerate the presence of divers. Many species migrate for thousands of miles.

History of diving



Diving through the ages

The search to free divers from the limitations of breath-holding began in ancient times with the use of reed snorkels. Developing from diving bells and diving suits supplied with air from the surface, it evolved into modern scuba, in which divers carry their own air supply.

EARLY DIVERS AND DIVING BELLS

It is hard to trace the origins of diving, but mummified human remains dating back more than 5,000 years have been found in Chile alongside fish bones and mussel shells. Small growths in the humans' ears, resembling the modern condition called surfer's ear, suggest that these people may have been divers.

Hollow reeds or breathing tubes that extended to the surface were used in ancient times to enable divers to stay submerged for longer. Herodotus recorded that in 500 BCE, a Greek diver named Scyllias used a reed snorkel to swim unnoticed and cut the moorings of Persian ships. Salvage diving was well known in the ancient world, and laws regulating those who dived for treasure were in operation in Greece as early as the 1st century BCE.

An important milestone in helping divers to overcome the restrictions of breath-holding was the invention of an apparatus to hold air underwater. At the siege of Tyre in 332 BCE, Alexander the Great reportedly used such a device, descending beneath the waves in a glass barrel. In the 4th century BCE, Aristotle described a bell-shaped diving chamber that took the form of an overturned cauldron filled with air, in which divers made trips to retrieve objects from the seabed. From the Middle Ages onward, diving equipment became more sophisticated. During the Renaissance, speculative designs for diving suits began to appear, although nearly all



ALEXANDER'S GLASS BARREL
Surprisingly, Alexander the Great used his glass barrel to make observations of fish, rather than as an aid to his military campaigns.

KEY DATES

***c.* 3000 BCE** Early divers collect oysters from the sea bed, developing a bone deformity caused by frequent exposure to cold water—a condition today known as "surfer's ear."

***c.* 2800 BCE** A Sumerian epic detailing the exploits of King Gilgamesh reports that he used weights to sink to the seabed in search of a plant granting immortality.

9th/8th century BCE Homer's *Iliad* refers to the use of military divers in the Trojan War, *c.* 1250 BCE.

***c.* 500 BCE** Herodotus recounts the story of Scyllias diving to cut ships' anchor lines on the seabed.

***c.*4th century BCE** Aristotle records the first use of a diving bell, made from an overturned cauldron filled with air. The diver within could venture out for short periods before returning for air.

***c.* 332 BCE** Alexander the Great descends to the seabed inside a glass barrel during the siege of Tyre.

3000 BCE
1000 BCE
0

would have proved ineffective if put to use. Nonetheless, Spaniard Diego Ufano described the use of leather diving helmets during salvage work in his *Treatise on Artillery*, published in 1612.

Diving bell technology also improved during this period. In 1691, English astronomer Edmund Halley produced an advanced bell that was linked by a hose to weighted barrels of air, which were periodically replenished at the surface. Stale air was vented from the top of the bell. Halley and his bells were widely employed for commercial salvage work.



HALLEY'S BELL, 1691
A diver could swim out from under Halley's bell with an air line linked to a smaller bell over his head—a precursor of the modern diving helmet.

DIVING FOR PEARLS
The earliest divers relied only on breath-holding. Using this technique, female divers in Japan have been harvesting pearls for 4,000 years.

1500 Leonardo da Vinci designs equipment for underwater exploration, including snorkel tubes and bags intended to supply a diver with air.

1660 Robert Boyle identifies the relationship between water pressure and gas volumes, furthering the understanding of buoyancy.

1691 Edmund Halley develops a diving bell with a glass top to admit light, and an air replenishment system using barrels lowered from the surface. An umbilical tether supplies air to the bell's operator when venturing outside the bell.

1715 Inventor John Lethbridge uses a modified barrel as a diving vessel to recover salvage from the sea floor. The barrel has a glass viewing port and holes with watertight leather sleeves, through which the operator's arms protrude. The barrel reaches depths of 60 ft (18 m) in trials.

1500 1600 1700 1800

DEVELOPMENT OF THE DIVING SUIT

In 1715, Englishman John Lethbridge devised a pressure-proof wooden diving barrel. Reinforced and clad in leather, the barrel had a glass viewing porthole and arm holes with watertight leather sleeves. Lowered from a ship to depths of 66 ft (20 m), the barrel enabled the diver inside to use his arms freely, pulling his way around a site and retrieving objects. Lethbridge was commissioned by the Dutch East India Company to recover treasure from wrecks around the world using these diving barrels.

The barrel was a forerunner of the armored diving suit. Its usefulness, however, was limited by the inability to replenish the air in the barrel without hauling it back to the surface. Three other developments would be required before diving suits became a reality. The first of these occurred in 1779, when John Smeaton, another Englishman, used a steam-powered pump to supply air to a diving bell. Air pumps allowed diving bells to stay down considerably longer than before, and would later supply the first diving suits. The next development, by the Scot Charles Mackintosh in 1818, was the production of a rubber-based coating for waterproofing canvas, providing an ideal material for a diving suit. The third innovation, in 1820, was the patenting by British salvage operators John and Charles Dean of a diving helmet—a modified firefighting helmet into which air could be pumped. The helmet rested on the



SALVAGE IN ARMORED DIVING SUITS, 1932
Lethbridge's barrel was a precursor of armored diving suits. Initially too clumsy, they now have a niche for specialized work at great depth.

CAISSON DISEASE

Improved air-pump designs in the mid-19th century made it possible to build underwater chambers in which several men could work at depth. Called caissons, these chambers were ideal for tasks such as building bridge footings and excavating tunnels. Air-pumps delivered sufficient pressure to keep water entirely out of the chamber. However, workers often felt ill at the end of a shift. This was decompression sickness (DCS), or "the bends."



An illustration of a caisson chamber

KEY DATES

1779 Englishman John Smeaton pioneers the use of a pump system to replenish submerged diving bells with fresh air.

1788 German diver Peter Kreeft successfully demonstrates the use of a leather diving helmet in the Baltic sea, witnessed by the king of Sweden.

1800

1818 Naphtha, a coal-tar derivative, is discovered. When mixed with melted rubber, it forms a waterproof coating, and is soon used in the manufacture of lightweight diving suits.

1825

1829 Brothers Charles and John Dean undertake wreck salvage work in Britain using a modified firefighting helmet to supply air during dives to the seabed.

1839 British Army divers develop the practice of diving in pairs during salvage work on the warship *Royal George*.

diver's shoulders, held in place by its own weight, and air passed out from under the edge of the helmet. However, if the diver stumbled, it could easily fill with water.

In the 1840s, German-born inventor Augustus Siebe perfected a "closed dress" design, with the helmet sealed to a waterproof canvas diving suit. An exhaust valve was incorporated into the helmet, which was supplied with air by a pump at the surface. With a few modifications—such as neck and foot weights to help divers stay upright, and thick woolens under the suit to combat cold—Siebe's closed dress design remained standard for deep-sea divers for more than a century.

DECOMPRESSION SICKNESS

In the mid-19th century, the consequences of breathing highly compressed air were being seen among divers and caisson workers, who suffered what we now know as decompression sickness (DCS). In 1878, French physiologist Paul Bert realized that these ill-effects were caused by nitrogen damaging the body during rapid decompression, and recommended that caisson workers and divers return to normal atmospheric conditions slowly.

Nearly 30 years later, Scottish physiologist J. S. Haldane devised the first decompression tables after researching the effects of gas poisoning and DCS. Haldane pushed diving to new limits, sending divers down to 210 ft (65 m) in 1906. The divers avoided DCS by performing decompression stops.

DEEP-SEA DIVING GEAR
The helmet and suit worn by this diver in 1954 are remarkably similar to those designed by Augustus Siebe in 1840.

1865 French inventors Benoit Rouquayrol and August Denayrouze invent compressed-air breathing apparatus that allows short periods of autonomy from surface air supply.

1869 Author Jules Verne popularizes diving with his novel *20,000 Leagues Under the Sea*, in which characters explore the seabed with compressed air breathing apparatus.

1850

1875

1878 French scientist Paul Bert publishes a paper explaining the causes of "Caisson Disease" (later known as Decompression Sickness), a condition associated with breathing pressurized air for long periods of time.

1878 English merchant seaman Henry Fleuss designs the first fully autonomous breathing apparatus. The device uses compressed oxygen as a breathing gas.

1893 The first underwater camera is designed by Frenchman Louis Boutan.

1900

SCUBA DIVING IN THE 1960s
As other manufacturers introduced their own versions of Cousteau and Gagnan's scuba apparatus, the cost of equipment fell, and the 1960s became a boom-time for scuba.

AUTONOMOUS DIVING

In the 19th century, inventors strove to devise self-contained breathing systems that would allow autonomous diving—diving without an air line to the surface. In 1865, Frenchmen Benoit Rouquayrol and Auguste Denayrouze devised a compressed-air tank with a primitive regulator, which adjusted the air flow to meet the diver's breathing requirements. In this "open-circuit" apparatus, air was inhaled from the tank and waste gases vented into the water. Although the diver was tethered to the surface by a hose that pumped air into the tank, he could disconnect the hose for a few minutes, and breathe from the tank alone.

In 1878, Englishman Henry Fleuss produced the first fully autonomous system, using a breathing bag fed by a copper tank of pressurized oxygen. This was a "closed-circuit" system, or "rebreather," in which the exhaled air is recirculated. Carbon dioxide was removed from the exhaled breath and oxygen injected to replace that consumed by the diver, allowing it to be breathed again.

In 1911, the German firm Draeger began producing oxygen rebreathers, soon developing these to use enriched air (compressed air with added oxygen). Rebreathers were used by naval divers during both world wars, in preference to open-circuit systems, which emitted a telltale stream of bubbles.



WWII NAVAL DIVER'S MASK
Air from a rebreather was supplied via a hose to a rubber hood.

SCUBA GEAR

The type of equipment used by divers today first began to take shape in the 1930s and 40s. American Guy Gilpatric created the first modern mask in the early 1930s, and the first diver's snorkel was

KEY DATES

1908 John Scott Haldane, Arthur C. Boycott, and Guybon Damant publish a landmark paper on "compressed air sickness." The first decompression tables are based on this research.

1910

1917 The Draeger company of Germany manufactures an enriched air rebreather (a respirator that recycles exhaled air) that can be operated to a depth of 130 ft (40 m).

1917 The liner *Laurentic* sinks off the Irish coast after hitting a mine. Its cargo includes 35 tons of gold bullion. Royal Navy salvage divers succeed in recovering 3,189 ingots from the wreck over a period of seven years.

1920

1925 French naval officer Yves Le Prieur develops an open-circuit (non-recycling) compressed-air respirator—a forerunner of modern scuba.

developed by Englishman Steve Butler at about the same time. Fins were patented in France by Louis de Corlieu in 1933.

Open-circuit scuba (Self-Contained Underwater Breathing Apparatus) as we know it today was pioneered by two Frenchmen, engineer Emile Gagnan and naval officer Jacques Cousteau. In 1943, they combined a two-stage regulator, from which the diver breathed, with a high-pressure air tank. The regulator supplied air to the diver on the slightest intake of breath. Other self-contained breathing apparatus used at the time either supplied air continuously or had to be manually turned on and off. (The primitive regulator design of Rouquayrol and Denayrouze had fallen out of use.) Efficient, reliable, and comparatively cheap to produce, Cousteau and Gagnan's "Aqua Lung," as it was known, went on sale in France in 1946. By the early 1950s, Aqua Lungs were available throughout the world.

JACQUES COUSTEAU
From the 1950s to the 1970s, Cousteau's groundbreaking films and TV programs revealed the wonders of the deep to a worldwide audience, and persuaded many to start diving.

The first commercially successful buoyancy compensator, which allowed divers to adjust their buoyancy in the water, was patented in 1961 by Frenchman Maurice Fenzy.

1930 American William Beebe descends to a depth of 1,426 ft (435 m) in a bathysphere—a tethered diving vessel launched from a ship.

1933 French inventor Louis de Corlieu patents rubber fins to aid underwater swimming.

1938 American Guy Gilpatric's book *The Complete Goggler* popularizes spear-fishing underwater.

1941 Italian navy divers use rebreathers to mount underwater attacks on moored Allied shipping during World War II.

1942 Jacques Cousteau and Emile Gagnan design and test the Aqua Lung compressed-air breathing apparatus. The design's ease of use helps to encourage recreational diving.

1948 Aqua Lung first exported to the US.

1930 1940 1950

DIVING TODAY

The Aqua Lung caused a revolution in diving, making it accessible to the public for the first time. In 1950, there were some 30,000 scuba divers globally; ten years later, there were in excess of one million. There are now estimated to be tens of millions of divers worldwide.

Modern diving equipment seems a world away from that used by Jacques Cousteau, yet the basics remain the same. Like Cousteau, we dive with a tank of compressed air, and use a mask, snorkel, and fins. Today, however, there is also a host of other equipment and gadgets to make diving even safer and more enjoyable. Mixed-gas diving (*see pp.194–95*), which allows deeper and longer dives, is becoming increasingly commonplace, and there are computers that give us data such as depth, water temperature, dive times, and breathing rate. Some dive computers even allow divers to play games during lengthy

DIVING FOR PLEASURE
Two divers prepare to explore beneath the surface of a tropical lagoon. The rebreather units on their backs allow very long dive times.

KEY DATES

1950

1951 *Skin Diver* magazine goes on sale in the US, and plays a central role in popularizing diving.

1953 Dr. Hugh Bradner develops the first neoprene wetsuit for the US Navy.

1956 Jacques Cousteau's diving film *The Silent World* (based on his book of the same name) wins an Academy Award.

1959 The first nationally organized scuba training program is established in the United States by the YMCA.

1960

1961 Frenchman Maurice Fenzy patents an inflatable safety jacket for divers, which becomes the first commercially available buoyancy compensator (BC).

1967 American Bob Croft is the first man to free dive (breath-hold dive) below 200 ft (60 m).

HUMAN TORPEDO
A diver clings to a battery-powered propulsion unit. These devices enable divers to explore large areas in a single dive.

decompression stops. Scooters eliminate the need to use our legs for propulsion, and waterproof MP3 players enable us to listen to music underwater. It may not be long before divers can take cell phones underwater and send text messages and photographs from the bottom of the sea.

THE FUTURE OF DIVING

Many divers believe that the future of diving lies with using rebreathers (*see pp.82–83*). Once used only commercially, these devices are now available to leisure divers and are becoming increasingly commonplace. Rebreathers greatly extend the time divers can spend at the bottom, and reduce the need for multiple tanks of breathing gas to be taken on a dive. Fifty years from now, it is possible that we may all be diving with sophisticated rebreathers.

There is also increasing interest in submersible vehicles for the private market. Billed as the ultimate rich person's toy, such craft may open up extended explorations of the seabed to their owners. Diving limits are also being extended every year.

In the sport of free diving, where competitors use no scuba gear but simply hold their breath (*see pp.190–91*), records of more than 500 ft (150 m) have now been set. Scuba divers have reached similar depths breathing compressed air, and have descended to below 1,100 ft (330 m) using mixed gases. Will we one day be able to dive to the bottom of the Pacific Ocean—6.8 miles (11 km) underwater? Only time will tell, but it would be surprising if advances in technology and our understanding of the human body did not grant some extension of today's limits.



DIGITAL DIVE PLANNING
Sophisticated computers record and process vital dive information.

1968 Americans Neal Watson and John Gruener dive to 437 ft (133 m) breathing compressed air.

1970

1971 Scubapro markets a "stabilization jacket" for divers. Its waistcoat-style design sets the trend for modern BCs.

1979 Sylvia Earl walks untethered on the sea floor at a depth of 1,250 ft (381 m) in a special pressure suit.

1980

1980 Divers Alert Network, a nonprofit organization for promoting dive safety, is founded.

1983 The first commercially available dive computer, the Orca Edge, goes on sale.

1990

1993 Italian free diver Umberto Pelizzari sets a depth record of 403 ft (123 m).

1999 Briton Mark Andrews dives to 500 ft (152 m) on air.

2000

2003 Briton Mark Ellyat dives to 1,024 ft (313 m) on Trimix scuba.

Getting started

Introduction

Learning to dive is an adventure in itself. There are many different training agencies offering basic scuba qualifications, with branches in nearly all parts of the world. Though dive tuition makes demands on both your body and mind, it can be a very rewarding experience.

LEARNING TO DIVE

Diving is a safe sport provided that you have undergone formal training before taking to the water. It would be extremely foolhardy to proceed on your own, as there is no substitute for a proven program of instruction. Moreover, no dive center or charter boat will take you diving without recognized qualifications. Considerations of safety apart, you will feel more confident, relaxed, and prepared for the underwater experience if you are fully trained. Basic "open water" training qualifies you to go diving without supervision. It will not, however, teach you to dive under ice, in a cave, or beyond certain depth limits. For these activities, you need to attain further qualifications and gain more experience.

WHO CAN BE A DIVER?

Practically anyone can learn to dive, but there are a few basic health requirements. For instance, if you suffer from asthma, you will need to consult your doctor beforehand, although the condition need not be a barrier. Diving is not a strenuous sport, but you will encounter situations that require you to be reasonably fit:

EXPERT GUIDANCE
During basic training, the instructor will tutor students in how scuba equipment works, as well as its use and assembly.

lifting yourself out of the water onto a boat, for example. Diving when pregnant is not advisable, but it is possible to pick up the theory and basic snorkeling skills during pregnancy, and continue with full training after your child is born.

There are special junior courses for those under 14 who wish to learn to dive, and advancing years are not necessarily a barrier to learning either, given a fair level of fitness and approval from a doctor. Many disabled people also enjoy the sport of diving, and dive training programs have been adapted to embrace a wide range of disabilities.



FITNESS FOR DIVING
While it is not necessary to be an athlete to go diving, a basic level of fitness is required (*see p.150*) for both safety and enjoyment.

HOW MUCH WILL IT COST?

Taking up a new hobby always involves a degree of investment, and diving is no exception. New diving equipment can be expensive, but second-hand gear is widely available, though it should be serviced before use. Equipment is almost always available to rent from dive centers and shops. and it is advisable to try out a few different pieces of gear before investing in your own.

Dive training is fairly expensive, but learning with a club can make it cheaper, and most training organizations offer trial lessons to help you decide if you enjoy diving before paying for a full course of instruction.

NOVICE IN SHALLOW WATER
An instructor guides a student through his first dive, maintaining contact the whole time to ensure a safe learning experience.

Where to learn

There are a number of different diving organizations around the world with whom you can train. Other divers may recommend the one they learned with—which is not a bad start—but investigate all the training agencies, since each offers a different approach to tuition.

LEARNING THE BASICS
Be aware that courses abroad may have an instructor whose first language is not yours.

TAKING THE PLUNGE

The first question you should consider is whether to learn to dive with a school or with a club. A diving school (confusingly, also called a diving club in mainland Europe) is a commercial venture—you pay to learn to dive. A diving club is a nonprofit venture where members donate their time training other members. You might think that a school sounds like a more professional option, but in truth, instructors in clubs are equally highly trained, and the fact that they are giving their time free of charge says much about their love for diving and desire to pass on their knowledge to others. Clubs also add a social dimension to learning, arrange talks and trips both at home and abroad, and may offer a longer-term framework for gaining diving experience. However, clubs tend to run training sessions on just one day of the week, and it can take a few months to become qualified.

By contrast, diving schools offer greater flexibility, and offer you the chance to learn the basics at home,

possibly over a couple of weekends, and then complete the rest of your course in warmer waters on vacation. Alternatively, they allow you to complete your training beforehand (and on your own schedule), then depart for your trip abroad as a fully qualified diver.

TRAINING ORGANIZATIONS

The world's largest training organization is PADI (Professional Association of Diving Instructors). They operate all over the world, and most dive sites you visit around the globe will be affiliated to PADI. Several other training organizations are prominent in the US, including NAUI (National Association of Underwater Instructors) and SSI (Scuba Schools International).

In the UK, most diving clubs are affiliated to BSAC (British Sub-Aqua Club), and their training is tailored to the waters around the UK. You may also come across the SAA (Sub-Aqua Association) and the SSAC (Scottish Sub-Aqua Club); the CFT/IUC (Irish Underwater Council) in Ireland; and CMAS (Confédération Mondiale des Activités Subaquatiques) in Europe. There are other organizations for more advanced diving (*see pp.329–30*).

CLUB BOAT WITH DIVERS
Diving clubs usually pool resources to arrange group trips that can cement long-lasting and rewarding dive buddy relationships.

THE CHOICE IS YOURS

For the beginner, the various training agencies offer broadly similar courses in terms of content and standards. The best course of action is to take advice from experienced divers and do what suits you. Always ask to see a trainer's qualifications before starting a course, and try to get a recommendation for a diving school or club before enrolling.

RESORT INSTRUCTOR WITH TRAINEES
Many people choose to learn diving on vacation, and there are thousands of diving schools around the world that offer training at all levels of ability.

Basic training

Learning to dive involves gaining some knowledge of essential theory as well as training in practical skills. Sometimes these skills are practiced in a pool before getting into open water but, depending on where you learn, they can be taught in a lagoon or in the shallows.

MASTERING THE THEORY

Your dive training will always start with theory. You will be taught about basic diving equipment, the principles involved in breathing gas at depth and under pressure, safety skills, communication, navigation, and much, much more. You will learn to carry out simple calculations relating to the physics of diving. Don't worry—none of the theory is difficult, but it does demand a few hours of study.

Dive agencies run this part of the training in different ways—some rely on traditional classroom teaching, others present materials on DVD or online—so choose the way that suits you best. In all cases, you will be provided with a reference manual containing all the material you need to know.

GOING DEEPER INTO DIVING
Learning to dive involves understanding some of the theory that underpins the sport. This training is given either in classes or one-to-one tutorials.

GETTING WET

Basic practical skills are taught in "confined water"—usually a swimming pool or shallow water just off a beach. You will be expected to pass a simple swimming test to show your instructor

TAKING THE PLUNGE
A trainee learns the basics in safe, shallow waters, under the guidance of an instructor.

that you are safe and comfortable in the water before they begin to teach the fundamental skills (*see below*). After this initial stage, you will progress into open water, where you will undertake a few introductory dives in order to get used to diving in deeper water and build your confidence to swim in the open sea.

SUITING UP
Trainees are not expected to buy a full set of equipment. Gear can be rented from most diving schools.

STAYING SAFE

Recreational diving is an extremely safe activity as long as you receive the correct training and keep your skills up to date. Choosing the right training agency, course, and instructor is therefore vital. Most instructors are highly trained and dedicated to their job, but there will always be a few "bad apples" in any profession, so take advice from friends, diving clubs, and specialty magazines and websites before you enroll. Do not be afraid to ask questions during your training, simple as they may seem; you can even request a different instructor if you do not feel comfortable.

Many people take up diving as a vacation activity and only get a chance to practice once or twice a year. If you have not dived for a while, it is a good idea to take a refresher course, and carry out a trial dive (with your buddy) to check all your gear and your skills before venturing into deeper water.

BUILDING CONFIDENCE

Fundamental skills and safety procedures are taught in the security of confined water before you can venture into the open sea. The abilities you need to master include buoyancy control and finning techniques, out-of-air procedures, removing, recovering, and replacing your regulator, and clearing your ears and your mask underwater (*right*)—a common source of apprehension among novice divers.



1 **Water can accumulate** in your mask during diving, usually in small amounts. With practice, even a fully flooded mask can be cleared without difficulty.



2 **Blow clear** by tilting your head back and pressing in the mask's upper edge. Exhale through your nose. The water should be forced out, escaping under the mask's lower skirt.



3 **Check that your mask** is free of water. If there is any remaining, repeat the process. This simple operation is quite normal during diving, and will quickly become second nature.

Specialized training

Diving is an inclusive, accessible sport, and there are many training options for children and the disabled. If you are already qualified but wish to undertake further training, there are numerous courses of advanced tuition to make you a better and more confident diver.

TAILORED COURSES

LIBERATING EXPERIENCE
A disabled diver undergoes training in a pool, with guidance from specially trained instructors.

Though standard open-water diving qualifications have a minimum age requirement (usually 14), children are now well catered to in diving. This means it can be a family sport—not one that is just for adults. For younger children, introductory courses are available, such as PADI's Bubble-Maker program, or diving clubs for children, such as the Scuba Ranger organization. These programs are designed to teach basic skills that lead to full open- water diving qualifications. Junior diving permits, available for children between 10 and 14 years old, are similar to basic open-water qualifications, but place special restrictions on the maximum depth to which the holder can dive.

Advances in training techniques mean that more disabled people are able to take up diving than ever before.

BUBBLE-MAKER TRAINING
Special courses for children are taught by most schools. Clubs also offer training for budding junior divers.

BECOMING INDEPENDENT
Your experience and judgment will build as qualifications are gained. Comprehensive training makes for a confident, safe diver.

Diving makes you effectively weightless, and the freedom of movement this offers makes the sport especially beneficial for those with limited mobility. The only condition that is an automatic bar to becoming a diver is epilepsy, due to the risk of seizures while submerged. However, blindness, paraplegia, cerebral palsy, and many other conditions have all been accommodated by adaptive training programs. The general rule is that if you have been cleared to dive by a doctor specializing in dive medicine, then training can begin.

DEEPER INTO DIVING

All the major training organizations offer courses that aim to take you a step onward from the basic open-water qualification. Such courses serve to refine your basic skills and introduce you to new challenges, such as deep diving, or diving in conditions of low visibility. They will also cover rescue and survival skills, and can be the first step on the path toward becoming a diving instructor. In addition to these skills development courses, there are also numerous specialty courses, which teach the technique and theory of activities such as cave diving, wreck diving, and mixed-gas diving. Such courses include dives to put new skills into practice, and help to improve your general diving experience. For more details, visit the websites of the various training organizations (*see pp.329–30*), or ask at your local diving center.

CAVERN DIVING
Specialized and difficult types of diving, such as cavern diving, ice diving, and other skilled activities, can be enjoyed after proper training.



Equipment

3086234
SCUBAPRO

Introduction

The wide array of equipment available is often bewildering to a novice diver. Some items are essential in all circumstances, while others are used only in specific diving environments. The more research you do and advice you seek, the more likely you are to buy safe, suitable gear.

BUYING AND RENTING GEAR

You could begin dive training with as little as a swimsuit, but it may be advisable to at least obtain a good-quality mask, snorkel, and fins. This means that you always have three key pieces of gear that fit perfectly, and with which you are comfortable.

Many divers own no more than this basic gear, preferring to rent the rest. There are pros and cons to this approach: it frees you from carrying heavy gear around, but it can also mean using ill-fitting equipment that has been worn by many people, and which may not have been well cared for. The alternative is to buy and transport all your own gear. This is recommended if you are likely to be diving regularly in your local area (although a local club or shop may have gear you can rent). It is not so practical if you plan to dive any farther afield—taking your own gear overseas can be expensive, although most dive tour operators are fairly generous with their excess baggage allowances. You can rent a tank and weights from any dive center, so you need never travel with these items.

The best places to buy equipment and obtain advice are dive shows or local dive shops. Second-hand gear is worth investigating, but inspect it for signs of wear and corrosion before making a purchase, and make sure that it is serviced before use.

DIVERS TOURING A REEF
Knowledge and care of gear is vital, since your equipment is your life-support system for exploring the underwater world.

BASIC EQUIPMENT CONFIGURATION



BC CONTROLS
This is the primary means by which you inflate and deflate your BC.

SECOND STAGE
Also called the demand valve, this is your breathing device.

KNIFE
A sharp knife or line-cutter should be carried in case of entanglement.

COMPUTER
A dive computer enables you to monitor depth and safe dive times.

Regulator first stage

AIR TANK
This straps on to your BC and attaches to the regulator first stage.

CORE EQUIPMENT

There are several items of gear that are essential, in addition to your mask, fins, and snorkel. A buoyancy compensator (BC) is an inflatable jacket that keeps you afloat at the surface, helps you adjust your buoyancy underwater, and supports other vital pieces of equipment. Weights, and a belt to mount them on, are another necessity, although weights can also be carried on some BCs (*see p.59*). You will also need some kind of dive suit (*see pp.50–55*) depending on the water temperature—and boots.

A regulator (the device that supplies air to the diver) is also necessary, preferably one that incorporates an alternative air source (an octopus) and an instrument console with a compass. Dive computers are a useful aid to safe diving, and you should also carry a knife to cut yourself free if you become snagged underwater.

DIVING ACCESSORIES

There is a range of equipment and accessory items designed for specialized diving. Try to borrow or rent specialty gear that you may only use infrequently.

Slates are useful accessories, since they allow you to write messages to your buddy, or to make notes from your dive—for example, on species that you do not recognize—or to sketch a site.

Flashlights are essential for diving at night, in murky water, and in low-light environments, such as caverns and wrecks.

If you will be doing a lot of open-water diving, especially in currents, you should purchase a marker buoy, either a surface marker buoy (SMB) or an inflatable surface marker buoy. These indicate your position to observers on the surface, and also aid your ascent.

EQUIPMENT FOR COLD WATER

Cold seas make extra demands on diving equipment, and additional peripheral items may be needed to ensure safe diving. Thermal protection is a priority.

MASK
The glass lenses should be tempered and offer a good field of view.



GAUGES
Gauges with large, clear dials are easier to read in low-light environments.

FLASHLIGHT
Temperate waters tend to be murky, so a flashlight may be required.

BUOY AND REEL
A marker buoy and reel are useful for guiding an ascent to the surface.

DEMANDING ENVIRONMENT
Diving in cold water requires extra equipment, and appropriate training in how to use it. Safety devices are especially important in such waters.

Lastly, you may wish to record your dive experiences with a camera. Digital cameras in housings are now small enough to fit into pockets in your kit.

DIVING IN COLD WATER

If you plan to dive frequently in cold water, you might want to invest in a drysuit (*see pp.54–55*). A good thermal underlayer is essential with a drysuit, since loss of body heat can result in poor decisions and lead to exhaustion, speeding the onset of hypothermia. Dive clothing manufacturers make special thermal undersuits with wicking properties to draw moisture away from the skin. If you are planning on doing any extreme cold water diving or ice diving (*see pp.188–89*) you will need to use an environmentally sealed regulator, because these are more resistant to freezing.

Also necessary in cold water are a hood and gloves, the thickness of which will depend on the water temperature. The thicker the neoprene, the more insulation it offers, but the more it will restrict movement. Thick gloves or mittens reduce dexterity considerably, which is worth bearing in mind if you intend to use smaller items of gear.

MAKING THE RIGHT CHOICE

Don’t rush into buying the first bit of new gear you see—always look at a range of products and compare prices. Take advice from fellow divers and shop staff, but remember that everyone has their favorite brands. Reviews in magazines and on the Internet can give you more information, so that you can weigh the options before you buy.

Masks

A well-fitting mask is arguably your most important piece of diving gear, so take time to choose one that is right for you. There are many styles and designs to choose from, but above all you need one that fits correctly, and suits your personal diving requirements.

SEEING UNDERWATER

Human eyes cannot focus in water, which is why you have to wear a mask when diving. The way masks work is to trap a pocket of air in front of the eyes, allowing them to focus normally. A standard mask consists of a single or double panel of tempered glass inside a frame, with a silicone skirt forming an airtight seal against the face. A strap and buckles hold it all in place.

If you take care of your mask and keep it in a sturdy case to avoid damage, it should last for many years. The lenses of new masks have a protective coating from the manufacturers that should be removed before use. This can be wiped off using a nonabrasive cloth and non-gel toothpaste (or a fine abrasive cleaner) to clean the coating off without scratching the glass. If in doubt, consult the manufacturer's instructions. Make sure you rinse your mask in fresh water after use and store it away from direct sunlight in a dry place.

TESTING FOR FIT

There are lots of shapes and sizes of mask, so take time to find one you like that fits. A simple test is to hold it up to your face and inhale gently through your nose. If you then lean forward, it should remain in place.



1 **Hold the mask** in front of your face with the strap hanging loose.



2 **Place it on** your face. Inhale through your nose—the mask should stay on without support.

MASK DESIGNS

CLASSIC This is a slightly old-fashioned design, but it is still popular with photographers because it gives a clear view of the diver's face. It offers a good field of view, but its high internal volume of air makes clearing the mask a little harder.


Single tempered glass lens
Oval metal outer frame

EXTENDED VISION Many new designs of mask are constructed to give the diver an extended field of view, especially downward. This model is a multi-lens design, which also allows corrective lenses of different strengths to be fitted.


Removable lenses
Lower lenses enhance downward view

MATTE FINISH Some divers prefer to use a mask with a black silicone skirt to avoid confusing reflections on the inner surface of the glass. This is especially useful to marine photographers. However, this feature does reduce peripheral vision.


Opaque silicon skirt
Single-lens design

SIDE VIEW Some designs offer improved peripheral vision through glass panels on either side of the main lens, but are still low-volume, so are easy to clear. When choosing, make sure that additional lenses do not distort perspective.


Side lenses widen view
Clear, light-permeable skirt

FULL FACE Mostly used in commercial diving, full-face masks are advantageous in very cold or polluted water. Some recreational models have intercom radio units so divers can communicate.


Quick-release faceplate
Primary lens
Radio intercom system

EYE TO EYE
Evolution has equipped fish with eyes that focus underwater, but divers must rely on masks for clear vision.

CORRECTIVE LENSES

Some masks can be fitted with prescription lenses, so if you wear glasses you will still be able to see underwater. Contact lens wearers can use normal masks—they provide an adequate degree of protection from water, unless accidentally removed.


Lightweight plastic frame
Corrective lens
Outer lens bracket
Inner lens gasket

Snorkels and fins

Along with a mask, a snorkel and a pair of fins are probably the first pieces of gear you will buy. Snorkels vary very little, but there are plenty of styles of fins to choose from, depending on your budget. As always, look for a good fit and features that suit your diving needs.

CHOOSING A SNORKEL

A snorkel is simply a tube that allows you to breathe easily at the surface without needing to raise your head from the water. When diving, you do not need a snorkel underwater; however, you may use one before and after submerging. A good snorkel should be easy to breathe through, and should not be too long—ideally no more than 17 in (43 cm)—so it is easy to clear. Attach your snorkel to the left-hand side of your mask, leaving the right-hand side free for your regulator hose (*see pp.60–61*). Always rinse your snorkel after use and store out of direct sunlight.

DESIGN FEATURES

Basic snorkels are little more than a curved tube, but some models have a splash-guard at the top of the tube to prevent ingress of water, and a drainage valve at the lower end. Collapsible types are easy to stow away when not in use.



Snorkel with splash-guard

Collapsible snorkel with case

FITTING FINS

Sometimes incorrectly referred to as flippers, fins are used to aid propulsion when diving. A standard fin consists of a shoe made of rubber and a blade made of a stiffer material, often with ridges and vents to enhance performance. The shoe can either fit the whole foot like a slipper or leave the heel exposed. The latter is held on with a strap, and is designed to be worn over neoprene boots. When buying fins of this type, it is advisable to take your boots along with you, since their thickness will need to be taken into account when testing for fit.

SELECTING THE RIGHT PAIR

Advances in fin technology mean that there is a wide range for the diver to choose from, depending on their specific preferences. For example, split fins offer a high degree of agility underwater, but many divers believe traditional models deliver more outright thrust. Before deciding which pair to buy, consider the kind of diving you will be doing, and seek advice from store staff or other divers.



FIN POWER
A diver employing the “frog kick” with conventional fins.

TYPES OF FINS

CONVENTIONAL A basic fin with a single, fairly rigid blade, the conventional design is a good starter fin, but you may want to try other types to see if they offer features that suit you better.


Ridges to reinforce blade
Flexible plastic blade

FORCE FINS Made exclusively by a California manufacturer, this range of fins is designed to minimize the water turbulence produced, and reduce the diver's kicking effort.


Open-toed foot pocket
Blade curves upward
Polyurethane blade

PIVOTING A design that has been adopted by two manufacturers, this fin features a flex-point in its structure and a V-shaped area of softer plastic to scoop water for better traction and speed.


Hinged area to allow flexing
Softer plastic to scoop water

SPLIT A popular style, split fins offer better agility than standard fins. However, some divers believe they are less effective than conventional fins in strong currents.


Soft, flexible construction
Split blades

SNORKELING Fins designed for snorkeling are lighter than scuba fins, and of a foot-pocket design, so they can be used with bare feet. Some also have shortened blades.


Foot pocket
Lightweight build
Short blades



Foot-pocket fin Heel-strap fin

FIT AND FASTENING
Fins are held on the foot in two basic ways: in a form-fitting foot pocket, or by a strap over the heel.

Diving suits

In all but the very warmest waters, you will need some kind of thermal protection during your dive. Good diving suits (which are technically known as "exposure suits") are available in every price range, but always look for comfort, fit, and quality of construction.

BEATING THE CHILL

Water conducts heat away from the body much more efficiently than air. Unless the water you are in is the same temperature as the surface of your skin—about 90°F (32°C), which is hotter than most corals can withstand—your body will lose heat, and you will get cold. This means that in almost all diving environments, thermal protection is required. If you are diving in warm waters, a normal wetsuit will be sufficient. Only in the warmest waters should you consider a non-insulating or "skin" suit. Never be tempted to dive in just a swimming suit; even if you don't need insulation, a thin layer will prevent stings and abrasions. If you are diving in cooler waters, you should consider the heavyweight options: a semi-dry suit or a drysuit.

SECOND SKIN
Modern wetsuits are made of materials that offer highly efficient heat insulation.

WHICH SUIT?

Personal warmth requirements vary. If possible, take various suit options—you can layer these to give you the best protection. It is rare to be too hot underwater, but in tropical climates you may overheat in your suit before you enter the water. This can be prevented by wetting the suit before putting it on.

Buying a suit for every temperature range is too expensive for most divers, but most suits will suffice for a variety of waters. Although in the tropics you would be too warm in a drysuit, you could opt for a full-length wetsuit, as its extra warmth would be welcome in the cooler depths.

In addition to a suit, you may need accessories such as gloves, boots, a hood, and talcum powder, which is useful for easing entry into suits.

EXPOSURE PROTECTION

There are guidelines for the type and thickness of suit needed in different conditions. For the tropics, where the waters rarely drop below 68°F (20°C), a 2–3-mm wetsuit is fine. In the Mediterranean in summer, a 5–6-mm full wetsuit is more appropriate, rising to 7–8 mm during winter months. A semi-dry suit of 10–15-mm thickness, with a hood and thick gloves, will cope with most conditions in colder temperate waters, but in waters below 50°F (10°C), a drysuit is necessary.



SUIT LAYERS

Wetsuits and drysuits keep the diver warm in different ways. In wetsuits, a thin film of water is trapped next to the diver's skin and acts as an insulator. Drysuits seal a layer of air inside the suit, and this permits the use of thermal undergarments for extra insulation.



Wetsuit

Skin
Insulating film of water
Neoprene shell
Sea



Drysuit

Skin
Air layer
Undersuit
Air layer
Outer shell
Sea

SKINSUITS AND SHORTIES

In warm, tropical waters, you will probably not require any thermal insulation, but a thin layer over your body will prevent your equipment from rubbing on your skin, as well as giving protection from the Sun before and after dives and providing a barrier to stings and scrapes.

The thinnest skinsuits are made of Lycra, but some manufacturers offer suits made from 0.5-mm neoprene. Lycra suits can also be used as a base layer under a heavier suit, so they are a good add-on option if you are not sure how warm or cold your destination will be.

So-called "shortie" wetsuits offer slightly more thermal protection than skinsuits, typically being constructed of 3-mm neoprene. However, they do leave the arms and legs exposed and unprotected from stinging plankton and jellyfish or abrasions on rocks or coral.



SHORTIE WETSUIT
This type of wetsuit is a good choice in warm waters, and does not cost as much as a full suit.

Non-chafing collar
Tough plastic zipper
Thin neoprene

Leather palms

Light gloves

Light material

Skinsuit vest

TROPICAL DESCENT
Even in warm waters, a full-length wetsuit may prove invaluable, because water temperatures drop as the diver ventures deeper.

FULL-LENGTH WETSUITS

The next level of thermal protection after shorties and skinsuits is a full-length wetsuit. These offer increased thermal protection for the arms and legs, and are typically made from 2–8-mm neoprene. But thickness is not the only factor in thermal efficiency—a close-fitting suit provides better insulation. A correctly fitting wetsuit should not only be easy to put on, but should follow the contours of your body as closely as possible. Wetsuits rely on trapping a thin film of water next to the body, which gradually becomes warm. If the suit fits badly, water flows more freely between the body and the suit, and chills—rather than insulates—the diver.

CARING FOR YOUR WETSUIT

A simple maintenance regimen is vital to prolong the life of your wetsuit. After every dive, wash your suit to remove salt and debris, which can cause it to rot. It is best to use special wetsuit shampoo, which helps to maintain the suppleness of the neoprene and prevent mildew. Once the suit is fully dry, place it on a hanger and store it in a cool, dry place.

FULL-LENGTH WETSUIT
Scuba wetsuits are available in a range of styles, categorized by the thickness of neoprene they are made from.


Torso area has extra insulation
Side panels for better flexibility
Thin neoprene
Gloves
Zipper for easy access
Boots

SEMI-DRY SUITS

Though intended for colder temperate waters, where they are worn with a hood and gloves, semi-dry suits are a versatile style that can be used even in warm Mediterranean seas. Like standard wetsuits, semi-dry suits are made of neoprene and work by trapping an insulating layer of water between the body and the suit. However, they have more efficient seals at the wrists and ankles and around the neck or hood, which stops water from flushing through the suit and allows the trapped water to warm up. They also tend to be made of thicker neoprene and are often designed to be used in layers (with a jacket fitting over a coverall-style base layer).

The thickness of the neoprene in some semi-dry suits has a tendency to restrict movement on land (although not in water). However, suits made of super-flexible material are available that offer an equivalent degree of thermal protection, but are much easier to put on and move around in. Although a semi-dry suit offers protection similar to a drysuit (*see p.54*), some divers prefer a drysuit, because a damp body can be uncomfortable after the dive, especially in cold weather.



SEMI-DRY SUIT WITH EQUIPMENT
Good-quality semi-dry suits are suitable for a range of dive environments and conditions, and allow you to withstand the chill of greater depths.

DIVE COMPUTER
Often no bulkier than a wrist watch, a dive computer may need a strap extension when worn with thicker suits such as a semi-dry suit.

FLASHLIGHT
In the colder and deeper waters accessible with a semi-dry suit, visibility can be impaired, so a light should always be carried.

DIVING IN DRYSUITS

Drysuits are the most expensive type of diving suit but offer excellent thermal protection. They use trapped air, not water, as an insulating barrier. Drysuits are available off the rack, but it is worth spending a little extra to get a made-to-measure garment, because a well-fitting suit will be more comfortable and more likely to avoid buoyancy problems caused by unequal air distribution.

Drysuits are made from a variety of materials, including crushed neoprene and membrane materials. Crushed neoprene suits are tough and offer a good degree of thermal insulation. Membrane drysuits are made from strong, thin, waterproof fabrics, which offer less inherent thermal insulation than crushed neoprene, and are designed to be used with a thermal undersuit. They are more supple than neoprene types, and so easier to move around in. However, they can be looser-fitting, and allow excess air to move around inside, which can shift buoyancy to the legs, and tip the diver upside down.

KEEPING WARM
Even in conditions as extreme as those encountered diving under ice, drysuits provide good thermal protection, ensuring the diver stays comfortable.



CRUSHED NEOPRENE SUIT
The inherent buoyancy of a suit made of neoprene that has been "crushed"—treated with heat and pressure to flatten its internal air cells—remains the same at any depth.

INFLATOR VALVE
This is connected to the regulator first stage (*see p.61*) and allows air to be introduced into the suit.

USING A DRYSUIT

Drysuits are more challenging to use than wetsuits, as they have variable buoyancy, due to their air-inflation mechanism. If you plan to use one for the first time, take an orientation course in a pool before diving in open water. A drysuit should be serviced once a year (or after long periods of storage) by an approved repair technician.

FASTENINGS AND SEALS

Drysuits generally have an “across the shoulder” zipper to allow entry. You will need help from your buddy to do this up. These zippers need regular coating with wax or “zip slip” to keep them lubricated and protected from corrosion.

To prevent water from entering the suit, drysuits have watertight seals—made of thin neoprene or latex—at the wrist and neck. Latex seals are generally less likely to leak than neoprene versions, but do not offer any insulation and are more fragile, so there is the risk that they may tear. Neoprene seals, by contrast, are tough, easy to repair, and warm, but it can be difficult to get a good fit.

INFLATING WITH AIR

Drysuits have an inflator valve on the chest that injects air to reduce the “shrink wrap” sensation caused by water pressure squeezing the suit against the body. This air expands on ascent and must be dumped via a valve, normally located on the shoulder, which can be manual or automatic. Cuff dumps are also available that work by raising your arm to release excess air.

TOP COVER
A neoprene hood is necessary in cold waters to insulate the head.



MEMBRANE SUIT
The tough, lightweight fabric of a membrane suit is more flexible than neoprene and so allows greater ease of movement.

THERMAL UNDERSUIT
Specialty garments, undersuits can be worn under drysuits for extra insulation and comfort.

High-tech fibers trap heat inside

Thick neoprene

Heavy wetsuit gloves

Buoyancy compensators

Unlike fish, humans have no natural way to adjust their buoyancy, or floating ability, when underwater. Divers wear a buoyancy compensator (BC)—a jacket that can be filled and emptied of air—to control their buoyancy underwater and at the surface.

HOW A BC WORKS

The BC (also known as BCD, or buoyancy compensation device) offers flotation at the water's surface and fine adjustment of buoyancy underwater, and acts as a harness for equipment items. At the surface, a fully inflated jacket will keep your head well out of the water. Underwater, buoyancy can be increased by inflating the BC with small amounts of air.

All BCs are connected via an air hose to the regulator first stage (*see p.61*), which supplies pressurized air from the tank for inflating the jacket. BCs can also be inflated orally, via a corrugated hose that hangs down over the left shoulder. Controls for automatic inflation and deflation are usually located at the end of this hose.

Of course, BCs must be able to reduce buoyancy as well as increase it. This is achieved by venting air from the jacket via dump valves at various points. Air can be released through the oral inflation hose by depressing a button, and can also be vented by using a pull-cord dump valve, which acts more quickly. These are often located on the opposite shoulder from the oral inflation hose, and at the bottom edge of the jacket. They should be used cautiously, since they alter buoyancy rapidly. Many BCs also vent air when the oral inflation hose is tugged sharply.

STOWING KIT
Buoyancy compensators (*right*) are fitted with handy stowage points for peripheral gear.

SURFACING IN SAFETY
When fully inflated, BCs allow the diver to float effortlessly at the surface. Here, two divers signal OK after a dive.

FIXINGS AND FASTENINGS

The tank (*see p.68*) is also attached to the BC. A strap attached to a rigid backplate wraps around the tank and holds it in place with a cam-action buckle. It is important that your tank is fastened securely and does not move during the dive. A well-designed BC will have various adjustable straps around the waist and at the shoulders, to ensure that it fits snugly. These can be easily re-adjusted underwater. Steel or plastic D-rings (*see below*) can be used to attach smaller items of gear.


FRONT VIEW OF BC JACKET
Pillar valve of air tank
Air bladder
Corrugated hose
Waist belt
Lumbar support pad

D-RING
Used for clipping on items of peripheral equipment, like a flashlight or reel.

WHISTLE
A safety feature for attracting attention. Here, it is tied to the oral inflation hose.

HARNESS RELEASE CLIPS
For quick release from the harness, and easy donning of the jacket.

BUOYANCY CONTROL
The inflation and deflation controls and oral inflator are at the end of the hose.


SIDE VIEW OF BC JACKET
Low-pressure inflator hose
Tank held securely in place
Hose-end air dump
Harness straps
Plastic boot is part of tank
POSEIDON
BESEA W-10
Nitrox

AIR DUMP
Valve allowing air to be vented rapidly from the air bladders.

TANK STRAP
Cam-action buckle locks air tank in place. BCs may have one or two.

SPECIALTY JACKETS
High-volume “wing” style BCs (*top*) are used in advanced diving (*left*). The large air capacity of these jackets provides extra lift for heavily laden divers.

CHOOSING A JACKET

A basic BC is like a padded vest, and these are often only adjustable at the waist. More advanced models have adjustable straps to make sure the jacket fits as snugly as possible underwater. Ideally, you should buy one that fits like a glove and does not roll around with a tank attached. You should also find it easy to take on and off. If possible, you should try it on with your wetsuit (or drysuit) to check the fit, and to ensure that there is room for more adjustment on every strap in case of changes in your suit or your body shape. Beyond the basic models of BCs there are the more specialized features available on some jackets, such as weight integration, or a “wing” style design (*see opposite page*). Whatever the features of the jacket you decide to buy, make sure they suit the type of diving you will be doing the most. Try out several different jackets before deciding.

SERVICING YOUR BC

Careful maintenance of your BC will keep it in good working order for many years. It should be serviced at least once a year, or after it has been stored unused for more than six months. Take it to a recommended dive shop. Only service it yourself if you have been trained to do so. Do not take risks by diving with old or unserviced gear.

CARING FOR YOUR BC

As with all items of equipment, your BC should be rinsed with fresh water after every dive. The inside should also be rinsed by flooding it through the corrugated hose. The jacket should then be emptied again by turning it upside-down and draining it through the same hose. After this, you should reinflate it to help locate and remove any remaining water, which will rattle around inside when the BC is shaken. The jacket should be stored in a cool, dry place in a partially inflated state.

BUOYANCY COMPENSATOR DESIGNS

INTEGRATED WEIGHT BC Some BCs feature integral weight systems. Many people find these quick-release weight pockets more comfortable to use than a traditional weight belt. The weights should be removed before putting the BC on and taking it off.

Inflator mechanism incorporates a backup regulator


High-lift air bladder
Tough plastic backplate
Quick-release weight pouches

INTEGRATED BREATHING BC The Mares HUB (Human Underwater Breathing) system was the first to integrate the regulator into the design of the BC. A great advantage of this top-of-the-line product is its simplified profile, which reduces drag in the water.

Regulator integrated with jacket design


Regulator built into BC
Reflective shell for visibility
Ergonomic inflator controls

WING / SEMI-WING BC Favored by technical divers (*see p.194*), these offer high lift capacity. The air bladder is rear-mounted: this aids horizontal posture under the water, but can push the diver face-forward at the surface. A semi-wing offers better surface support.



Semi-wing


Rear-mounted air bladder
Steel D-rings for attaching gear
Padded waist belt for comfort

Wing

WOMEN'S BC Women divers are increasingly well catered to with special jacket designs to give a comfortable fit without the usual tension points across the chest. Such jackets offer other convenient options like weight integration.

Specially shaped harness


Tough nylon-weave fabric
Padded backplate
Quick-release weight pouches

TRAVEL BC If you travel often, it is a good idea to consider a lightweight BC without a rigid back, which can be rolled up. These designs have a lower lift capacity, as they are mostly used in warm-water sites, where minimal weight is carried by the diver.

Toggle for jettisoning weight pouches


Lightweight, foldable form
Inflator controls

Regulators

One of the most important items of diving gear is a regulator. This two-stage gas-supply system provides you with air from your tank at the correct pressure for you to breathe underwater. Since it is a key life-support device, most divers buy their own regulator.

BREATHING UNDERWATER

Your tank can store large amounts of air in a small space because the air it contains has been highly compressed (*see pp.68–69*). Before you can breathe this stored air, it must be reduced to a safe pressure, which varies according to how deep you are underwater. The deeper you go, the greater the weight of water pressing on your chest cavity from outside (*see pp.94–95*). This is called ambient pressure. Air for breathing must be supplied at an equivalent pressure, otherwise your lungs will not be able to inflate properly.

STORING REGULATORS
Regulators are tough, but they should be well cared for. Hang them up in a cool, dry place away from sunlight.

HOW REGULATORS WORK

Supplying air at the right pressure is the job of the regulator, which is made up of the first stage (which fits on to the tank) and the second stage (the piece you put in your mouth), which is also known as the demand valve. The first stage reduces the air passing out of the tank to a lower pressure of around 116–145 psi (8–10 bar) above ambient. A valve in the first stage allows some of this low-pressure air to pass into a hose, and then closes again. When the air in the hose has been inhaled by the

UNDERSEA EXPLORER
The regulator reduces the pressure of the highly compressed air in the tank to a level that is safe to breathe.

diver, the first stage detects a decrease in pressure in the hose, and allows more air to flow in, to replace that which was used. It automatically alters air-pressure in the hose when depth changes occur. The first stage also supplies air for BC and drysuit inflation (via separate hoses).

The second stage reduces the low-pressure air in the hose to the same pressure as the water you are swimming through, allowing normal breathing. The second stage houses a diaphragm that is subject to equal forces of water pressure on one side, and air pressure from your breathing passages on the other. When you inhale, the diaphragm flexes inward, causing an inlet valve to open, and air flows into your mouth. Exhaling causes the diaphragm to flex outward and triggers an exhaust valve to open, allowing used air to be expelled. The unit can be cleared of water by using the purge button, which is located on its front surface.

A-CLAMP FIRST STAGE
A common and convenient clamp-style first stage, suitable for most recreational diving requirements. Less secure than DIN.

DIN-TYPE FIRST STAGE
A screw-in first stage that can handle high tank pressures of more than 3,000 psi (200 bar). Highly secure.



SECOND STAGE
Designed to supply air safely at all depths, your second stage should fit comfortably in your mouth.

INSTRUMENT CONSOLE
A high-pressure hose from the first stage feeds directly into a pressure gauge, indicating remaining air supplies.

OCTOPUS SECOND STAGE
The octopus is for use in the event that your main second stage fails, or for donation to other divers.

BC JACKET
A low-pressure hose from the first stage supplies air to your BC to inflate the jacket underwater.

THE OCTOPUS SECOND STAGE

Most recreational regulators are set up in an "octopus" configuration (so called because of the multiple hoses emerging from the first stage). This incorporates a backup second stage, which is intended for use if your main one fails, or if your buddy needs a donated air supply. Over time, this backup air source has become known as the octopus second stage, or simply the octopus.

The octopus and the hose to which it is attached are usually finished in a bright yellow color for easy location in an emergency, and to distinguish them from your main second stage (which ordinarily has a black hose). The octopus hangs unused from your BC most of the time, and for this reason it is often detuned (adjusted) to prevent "free-flow"—an accidental discharge of air that occurs more easily when the mouthpiece of the regulator is left continually flooded. Some types of octopus are attached to the hose via a swiveling joint, so that they can be easily and safely donated to your buddy regardless of whether they are beside you, or face-to-face.

The hose supplying an octopus should be longer than the one feeding the main second stage. This will allow it to be offered to a buddy easily and for the buddy pair to remain face-to-face during a shared-air ascent (*see p.140*). Practice air-sharing procedures regularly.

STOWING THE OCTOPUS

Consider where to stow your octopus so that it can be easily located in an emergency by either you or your buddy. You can buy specialized clips of various designs to attach the octopus to your BC, which allow it to be freed easily when required, and replaced again afterward. Many divers hang their octopus near their midriff, but others mount it higher up on the chest, so it remains constantly within sight and close at hand. You can also buy regulator retainers made from rings of surgical tubing. These go around your neck, meaning the octopus is always right under your chin, though some find this arrangement constricting.

SAFE STOWAGE
Attach your octopus to your BC at a point where you can easily access it, and where it will be clearly visible at all times.



EMERGENCY ACCESS
Special quick-release clips are available for fastening your octopus to your gear.

TYPES OF REGULATORS

BASIC REGULATOR Simple, inexpensive regulators at the budget end of the market can be very reliable and durable. However, some may deliver air a little less smoothly than high-performance models.

Plastic construction

OCTOPUS SECOND STAGE Octopus second stages are often just standard second stages with high-visibility color schemes. However, some designs can be swiveled to any angle for easy access.

High-visibility covering

HIGH-PERFORMANCE REGULATOR At the top end of the market are regulators that combine high build quality with low inhalation effort and toughness. Many are environmentally sealed for cold-water use.



OXYGEN-COMPATIBLE REGULATOR Divers who wish to use nitrox mixes (*see pp.194–95*) that are very rich in oxygen will need a regulator designed to handle high oxygen concentrations without risk of combustion.

Colors denote oxygen rating

VINTAGE-STYLE REGULATOR In twin-hose regulators, the valve of the second stage is separated from its mouthpiece, and sits behind the diver's head, where it releases bubbles out of the diver's field of vision.



CHOOSING A REGULATOR

As with all items of dive equipment, prices vary enormously, but the regulator is one piece of gear worth investing decent money in. Basic regulators use a piston valve in the first stage and can be very reliable but often feature rather chunky second stages. The more expensive models use a diaphragm in the first stage and tend to have more streamlined second stages. Top-of-the-line models may be designed specifically for cold water diving, or be optimized for efficient air delivery on deep dives. They may also have dials to adjust the inhalation effort required to open the valve and deliver air. These can be used either to tune the unit to free-flow less easily, or maximize air delivery during a normal dive. Always rinse your regulator in fresh water after use, and have it serviced annually by a qualified dive-equipment technician.

DEEP BREATH
Regulators are designed to stringent standards, and are very reliable if well-maintained.

Gauges and consoles

To stay within safe time and depth limits and avoid running out of air, you must carry instruments that monitor your air consumption, time underwater, and depth. There are various devices on the market to help with this, from simple gauges to complex digital consoles.

BASIC INSTRUMENTS

You should never dive without some means to measure the time you spend underwater, the amount of air you have left in your tank, and your depth. A waterproof watch with a bezel—a rotatable outer ring—allows you to mark significant times, and thus keep track of how much time has elapsed. It also serves as a backup in case of failure of digital equipment used to monitor time, such as a dive computer.

INDICATING REMAINING AIR SUPPLY
The air-pressure gauge allows you to keep track of the amount of air in your tank; let your buddy know (*see p.145*) when your supply is running low.

Depth gauges allow you to monitor your depth even if you cannot see the water's surface. They are usually analog (needle-and-dial) devices, although digital versions are also available. Both work in the same way: they measure the pressure of the water around you, and convert this into an accurate reading of your depth. Make sure you buy one that records the maximum depth of your dive, and remember to reset it after every dive. Equally important is an air-pressure gauge, also known as a submersible pressure gauge (SPG) or contents gauge. This is connected to your regulator first stage via a high-pressure hose and measures the pressure of the air in the tank. You should check your air-pressure gauge every few minutes during the dive to carefully monitor your air consumption.

CHOOSING A CONSOLE

Your console is your dive information center, so you must be happy with the way it handles. Different consoles need to be held at different angles to read the dials; experiment before you buy to find out which is easiest for you to use. Choose one with large, easy-to-read numbers. Some are equipped with other instruments, such as a compass; these can be either on top of the console or on the back.



GAUGE CONSOLES

Depth and air-pressure gauges are often combined in a single integrated console that attaches to your regulator first stage and hangs by your side during a dive. Mounted together like this, the gauges are easy to locate and can be

TYPES OF GAUGES AND CONSOLES

STAND-ALONE DEPTH GAUGE A depth gauge is usually oil-filled and reacts to ambient pressure changes. Mostly analog, these gauges are accurate and durable.



STAND-ALONE AIR-PRESSURE GAUGE Typically analog, this type of gauge contains a tube that expands or contracts according to the air pressure inside your tank.



DEPTH AND AIR-PRESSURE CONSOLE This option allows at-a-glance checking of both depth and tank pressure, and also registers your maximum dive depth.



DIGITAL CONSOLE This console has an integrated computer and displays a range of information, such as air consumption, temperature, depth, time, and ascent rate.



read simultaneously, like a "diver's dashboard." They can sometimes also include other instruments, such as a compass or a thermometer.

Consoles should be rinsed with fresh water after use and stored away from direct sunlight, and kept in a padded or protective case to avoid damage.

ADVANCED CONSOLES

Some manufacturers offer instrument consoles with digital rather than analog gauges. Consoles are also available that perform the same advanced functions as a dive computer (*see pp.66–67*). As well as indicating dive time, depth, and decompression schedules like a normal computer, these also incorporate a digital air-pressure gauge. For divers who use a wrist-mounted computer to monitor dive information, console instruments can provide an essential backup.

ANALOG VERSUS DIGITAL
Although less easy to read, analog gauges sometimes give slightly more accurate readings than digital ones, particularly at shallow depths.

Dive computers

To avoid decompression sickness, it is critical to monitor your depth and time underwater on every dive. In the past, this would have been done using a watch and a depth gauge, but these functions and many others can now be performed by a dive computer.

USING A DIVE COMPUTER

The main functions of a dive computer are to monitor your dive time and depth and calculate safe dive schedules. A basic model uses this data to assess the level of nitrogen absorption in your body while you are under the water, and also displays information about your ascent rate, including any stops you may need to make during an ascent to avoid decompression sickness (*see pp.100–01*). More advanced models also inform you about the temperature of the water and your air consumption (if linked via a transmitter to your regulator first stage), both for normal air and technical gas mixes (*see pp.194–95*).

Computers are more flexible than dive tables (*see pp.100–01*). Dive tables show how long you can spend at different depths before needing decompression stops. Most tables assume that you spend your entire dive at the greatest depth; computers can make more complicated calculations, including the time spent at all the different depths reached on a dive. Some computers will also schedule deep decompression stops. These reduce the risk of nitrogen microbubbles forming in your body, meaning that less time is spent decompressing in shallow water. When making repeat dives, especially in places where you are not limited by times of tides and slack water, using dive

TYPES OF DIVE COMPUTERS

MULTI-GAS This type of computer can calculate dive schedules for several different mixtures of breathing gas, from normal air to various oxygen-enriched blends of nitrox.



Computer can be linked to rebreather

Detailed display, which uses icons as well as numbers

CONSOLE-INTEGRATED This computer is built into the diver's instrument console (*see p.65*), which is attached to the high-pressure hose from the regulator. As such, it also displays remaining air supplies.



Integrated compass

Hand-held device with finger-tip controls

WRIST-MOUNTED This instrument is typical of a basic level, watch-style dive computer. It provides data on depth, dive time, ascent rate, and safe dive schedules, and is for use with normal breathing air.



Data displayed in basic form

Push-button controls alter information displayed

RADIO-UPDATED This wrist-mounted computer also displays how much air remains in the diver's tank by means of radio updates from a module screwed into the regulator's first stage (*see pp.60–61*).



Wrist strap

Radio module

SAFETY CHECKS
As you ascend, keep a close watch on your dive computer to make sure that you are not exceeding the maximum ascent rate it recommends.



DIGITAL INTERFACE
Peripheral devices are available that link dive computers to PCs, enabling you to download dive profiles and create dive logs.

tables instead of a computer may not give you the maximum number of dives you can safely make each day.

Computers are also able to monitor your ascent rate accurately. In your dive training, you will be taught to ascend no faster than the smallest exhaled bubble, but it is more accurate to follow a digital readout that tells you the safe ascent rate.

BUYING A DIVE COMPUTER

A key consideration when buying a computer is the readability of the display. Too many figures on a small screen are difficult to read—the simplest models are often the best. Choose one with digits that are large enough to read with ease, without any nonessential data on the primary screen. It is also advisable to opt for a brand with a proven track record.

Computers are the most precise way of monitoring your dive, but they are not a foolproof means of avoiding DCS. It is impossible for data from a computer to exactly reflect your body's requirements. All models have built-in safety margins, but to be sure of avoiding problems, you should always dive conservatively, and not push your depths and times to the limit.

MALFUNCTION PRECAUTIONS

Never rely solely on a computer. As a precaution against malfunction, it is always worth practicing how to calculate dive times using tables. Although your computer will give early warning of a low battery, make sure you carry back up devices—either a watch and depth gauge, or a second computer, which can be mounted on your console.

Tanks

Also referred to as “cylinders” and “bottles,” tanks contain pressurized air for breathing underwater and have a valve that delivers this air to the regulator. Requiring regular testing and inspection, they can almost always be rented from dive centers.

SIZE AND MATERIALS

Different sizes of tanks are available, but most commonly they have a volume, or capacity, of 72, 80, or 95 cubic feet. The maximum pressure to which these can be filled varies—it can be as much as 4,350 psi (300 bar), but is more commonly 3,000 psi (206 bar). These figures are stamped on the neck of the tank, along with the dates of manufacture and most recent testing. Visual inspection at a certified dive shop must be carried out annually, and hydrostatic testing (for metal fatigue) is required at different intervals (from one to five years) in different countries. Your test stamps must be in date for your tank to be filled by any reputable dive center.

Many recreational divers use an 80 cubic foot tank, but if you find you usually run low on air before your buddies do, you should consider using a larger size. On deeper, or more lengthy dives, two tanks (a “twin-set”) may be needed. Compact “pony bottles” are often used as a backup air source; mounted next to the main tank, these are equipped with an independent regulator.

AIR
33
INSTRUCTOR ONLY
MIX

SECURED AGAINST MOVEMENT Tanks stored upright must be secured. Always store them out of direct sunlight.

TYPES OF TANKS

Tanks may be made of aluminum or steel. Steel is heavy and corrodes in salt water, but if well maintained it is durable and long-lasting. Aluminum is a lighter metal, but because tank walls must therefore be thicker, this adds bulk, and largely negates any weight advantage; they are also more prone to damage.


Pillar valve
Contains inert gas

Suit inflation tank


O-ring within valve
Nitrox content warnings

3-liter pony bottle


Knob to turn air supply on
Black/white indicates oxygen enrichment
Standard hazard symbols

Nitrox tank


Pillar valve
Test date is stamped on shoulder
Steel body galvanized then painted against corrosion
Rubber “boot” on base prevents rolling when laid down

A steel tank

Tanks are most commonly filled with compressed air. For technical diving (*see pp.194–95*), however, they can be filled with special gas mixes, such as nitrox and trimix. Drysuit inflation tanks, used mainly by technical divers, are filled with the inert gas argon, which, being denser than air, retains body heat for longer.

Because the air inside the tank is used up during the course of a dive, it gradually becomes lighter. Most people forget that air weighs a certain amount too, and compression packs a great deal of it into one tank. Aluminum tanks may even become positively buoyant as air is used up.

THE TANK VALVE

A valve screwed into the neck of the tank provides an attachment for the regulator first stage, for either an A-clamp or a DIN (*see pp.60–63*), and a means of turning the gas supply on and off. Always check that there is a sound O-ring in the valve before fitting your regulator. Without one, or with a damaged one, the fitting won't seal.

MAINTENANCE AND STORAGE

Fill your tank at reputable dive shops or centers and make sure it is "in date" and regularly serviced. If you are storing your tank on a boat, do not leave it standing up (especially if gear is attached) unless secured in a rack. Take care to lay it down and secure it so that it does not roll around. Tanks are full of highly-pressurized gas, so handle with care. Store tanks out of direct sunlight, especially when full, as this can cause a pressure buildup inside. If you have not used your tank for more than six months, have it refilled to get rid of any stale air.



DOUBLE CAPACITY
A twin-set is ideal for deep dives that require long, scheduled decompression stops.

Weight systems

When diving, your suit, BC, and even your own body all add to your buoyancy. There are many systems for carrying the lead ballast used to offset this, and they can be tailored to the environment you will be exploring. Comfort and ease of use should be a consideration.

STAYING DOWN

When wearing a drysuit or thick wetsuit (*see pp.50–55*), you will need to wear a considerable amount of weight to counteract the buoyancy of the suit. The most inexpensive way of wearing ballast is on a belt carrying hard lead tablets. Other systems use lead shot as the ballast, which is more comfortable to wear around your waist, as it molds to your contours. This is of most relevance to women, who often find that a standard weight belt is uncomfortable on the hips.

PASSING A WEIGHT BELT
When handing over a belt, always hold it with the buckle down, so that the weights cannot slide off.

Many BCs now feature integrated weight pockets, offering a more adjustable approach to weight distribution and trim. The lead carried by such BCs is mostly stored in quick-release pockets, but there are usually secondary stowage areas that are inaccessible during a dive. It is important to make sure the amount of releasable lead in the BC will give you sufficient positive buoyancy to guarantee an unassisted return to the surface if you have to jettison it.

WEIGHT SYSTEMS

STANDARD WEIGHT BELT A basic nylon belt carries lead tablets that have two slits through which the belt is threaded. The entire belt is dumped in an emergency, via a rapid-release cam buckle.



POUCH-STYLE WEIGHT BELT Some belts have pouches that hold bags filled with lead shot, which are easy to pull out and discard. A variation on this is a belt with a single compartment to which you add loose shot.



WEIGHT HARNESS Taking weight off your waist and suspending it from both shoulders makes carrying the load more comfortable. Quick-release catches allow dumping in an emergency.



WEIGHT-INTEGRATED BC This is perhaps the most comfortable way of carrying weight. The weight can be distributed around your body, aiding correct posture in the water (*see also* BCs, *pp.56–59*).



SECURING WEIGHTS TO A BASIC BELT

To prevent the lead tablets from sliding along your belt and altering your stability during a dive, you can secure them in place with plastic keepers. Alternatively, you can twist the belt to hold them in place. Insert the belt through the first slit in the weight, make a half turn, and then run the belt through the second slit.


Securing weights by twisting the belt


1 **To use a keeper** on a basic weight belt, thread the belt through the weight tablet, and locate in the desired position.


2 **Take the belt** up through the keeper, bend and thread back through the keeper, then through the weight.


3 **Pull the belt** taut on each side of the weight. Be careful to avoid kinking the webbing as you do so. Repeat as necessary.

REFINING YOUR WEIGHT SYSTEM

Weights are something you will not want to travel far with—and you do not need to, because they can be rented at dive centers. You will find that when you dive in different environments and in different suits, your weight requirements change. Record the configurations that work best for you somewhere handy, such as at the back of your log book. Whichever way you decide to wear your weights, it is vital that you can release them quickly and safely in an emergency.

ANKLE WEIGHTS

When a diver wears a drysuit (*see pp.54–55*), the air within the suit can become trapped around the legs and feet, inverting the diver. Ankle weights will help to counteract this undesirable effect.

Weights mounted in ankle strap

LEAVING GRAVITY BEHIND
Heavy weights, though awkward on land, will not be a burden underwater.

Dive flashlights

A flashlight is an essential item of dive gear. Although primarily used when diving at night and in conditions of reduced visibility, such as in caves or in murky water, flashlights also have other useful roles, including illuminating subjects for underwater photography.

LIGHTING UNDERWATER

Lights vary enormously in design and cost, but the basic function is to provide reliable illumination when submerged. There are good designs in nearly every price range, but flashlights, especially hand-held ones, are easy to lose and damage, so it is worth weighing up carefully how much you want to spend. It is also wise to obtain an equally reliable backup flashlight, such as a smaller pencil-style model, to stow in a pocket, for use if your primary light fails during a dive.

BURN TIME AND BATTERIES

One of the most important factors to consider when buying a flashlight is burn time—you do not want to run out of battery charge halfway through a dive,

USING A DIVE TORCH

Flashlights are easy to lose, especially during dives in strong currents. Wrist straps offer a degree of security, but it is safer to clip them on with a flexible leash. Stow them close to your body to minimize the risk of being hit on rocks. Also, try not to switch the light on and off too often during the dive, because this may cause the bulb to fail.





LIGHT IN THE DARKNESS
A cavern diver surveys the inside of a sea cave. Lights are an essential piece of diving safety equipment.

TYPES OF FLASHLIGHTS

HIGH-INTENSITY DISCHARGE This type of light burns brighter than a halogen bulb and, because it requires less power, has a long burn time. Such lights can be heavy and expensive, however.


Long casing for batteries
Powerful, intense beam

BACKUP A range of flashlights have evolved that are intended for use if the diver's primary light fails. As such, they are small and lightweight, but only generate enough light for emergency use.


Holster can be clipped onto mask strap
Twisting collar activates light
Plastic casing

PISTOL-GRIP This is probably the most widely used style of light among recreational divers. They are fairly inexpensive and usually use conventional non-halogen filament flashlight bulbs.


Pistol grip for ease of use
Wide reflector for broad beam

UMBILICAL An umbilical light has the battery housed in a separate case. This model uses high-intensity light-emitting diodes (LEDs) to generate a beam. Umbilicals have long burn times.


Battery pack worn by diver
Six LEDs for efficient burn

HIGH-TECH RECHARGEABLE This model can be charged via a special "wet" contact that means the case does not have to be opened, minimizing the risk of flooding through careless reassembly.


Rigid metal handle
Precision-engineered case
kowalski

Rear of light

which could compromise safety. There is usually a trade-off between output and burn time. Some lights are very bright and offer an excellent field of illumination for a short duration. But many lower-output models can outlast much brighter competitors, so consider carefully which would be more useful for you before making a purchase.

Rechargeable flashlights are more cost-effective than those requiring battery replacements, and tend to offer the greatest light output but the shortest burn time. Also consider the recharge time, especially if you are diving from a liveaboard boat and the vessel's generator is run only for short periods of time.

BUOYANCY AND BEAM

Another factor to consider is buoyancy. Some flashlights are positively buoyant, because they have a large airspace within the reflector. This makes them unbalanced in the water and difficult to handle. A positively buoyant light cannot be laid down, for example, if you need to light a subject for photography.

Lamps also vary in the size of the hotspot (central area of beam) and peripheral halo. The halo can be useful because it lights up a wider area than just the main hotspot. The hotspot is the brightest part of the beam, and is best for highlighting specific objects or for illuminating murky surroundings.

Surface marker buoys

Marker buoys may be used either during a whole dive or just before you ascend, to let those at the surface or on the shore know where you are, and also to aid your ascent. These devices offer a sense of security for both diver and surface cover, and aid safe recovery.

SMB OR DSMB?

A surface marker buoy (SMB) is an inflatable float linked to the diver by a line. It allows an observer at the surface to monitor the diver's position underwater. SMBs should be in a high-visibility color—most are orange.

The line to which the float or buoy is attached is usually stowed on a special reel. The reel should be held in one hand, with not too much slack on the line. You should use an SMB when your boat cover needs to be aware of your position at all times, such as during drift dives (where undersea currents propel the diver along), or where there is a likelihood of heavy boat traffic overhead.



STANDARD REEL AND LINE
Reels are available for both right- and left-handers for ease of winding.

REEL AND DSMB
Line and buoy can be wound and clipped together for compact storage.

Another type of buoy is deployed only at the end of a dive, or in an emergency. The delayed SMB (or DSMB) is carried deflated during the dive, then inflated underwater (*see pp.130–31*) before ascent, carrying a line from the reel up to the surface. When it pops up,

DIVER WITH DSMB INFLATED
By the time you surface, your boat cover should be en route to pick you up.



DIVER WITH SURFACE MARKER BUOY
Only one SMB, inflated before the dive, is needed per buddy pair, provided you remain together during the dive.

it shows where you are about to surface. Its line also acts as a guide for making a slow, safe ascent and for decompression stops (*see p.101*). Always make sure you are some distance from other divers using buoys before deploying, or you risk fouling each other's lines.

USING A REEL

Both SMB and DSMB lines should be tied with a bowline knot to the reel. A reel should be compact enough to fit into a pocket or clip onto your BC, but not so small that it is difficult to operate, especially if gloves are worn. Some reels have a ratchet action to stop the line from unwinding on its own, and this helps to avoid tangles. The length of line you use should correspond to the depth you are expecting to dive to; this may be 130 ft (40 m) or even more. If the line is too short, then when it runs out, the DSMB will yank you upward at a dangerously fast rate until the buoy reaches the surface. This can also happen if the reel jams, which is why you must never deploy a DSMB while the reel is still clipped to your BCD: you must hold the reel in your hand so that in an emergency you can simply let it go.


Lifting bag
Self-sealing
Self-inflating
Tough nylon fabric
Webbing straps
Small air cylinder for auto-inflation
Dump valve for venting air
Internal baffle stops air from escaping

TYPES OF DSMBS
The cheapest lifting bags have an open base from which air can escape after inflation. Self-sealing types are more reliable.

Safety and signaling devices

It is rare to be lost at the surface, but you must be equipped for such an eventuality. To guide rescuers to your position, you should carry high-visibility surface location aids. The boat crew must know what color equipment you are wearing, and which aids you are likely to be using.

SIGNALING OPTIONS



SURFACE OBSERVATION SIGNAL This tall, inflatable signal is easily seen by boats or aircraft. It is inflated using compressed air from your cylinder.

Even on a relatively straightforward dive, the current can take you a long way away from your boat cover, and heavy swell can make you difficult to locate. If this happens, stay close to your buddy, and, if possible, secure yourself to them. Signaling to the boat will speed up recovery, and there are various gadgets available for this. The devices that are most commonly used are inflatable surface marker buoys (*see pp.74–75*). It is best to use the long "safety sausage" type, which stands up in the water, and remains inflated once deployed, rather than an open-ended one. If you opt for the latter, make sure you also carry an alternative device, such as a collapsible flag. Surface horns and power whistles are also used. They are of limited range, but can help to attract

SIGNALING DEVICES

FLAG Collapsible plastic flags in high-visibility or fluorescent colors are excellent for signaling at the surface, especially in a swell. They can be rolled and stowed alongside your cylinder.


Folding or telescopic handle for easy storage
Fluorescent for maximum visibility

STROBE LIGHT Strobes are particularly effective when attached to the top of a folding flag. If attached to your BC, the flash may only be intermittently visible as waves lap over and around it.

Strobe gives up to 8 hours constant use
Battery housed in waterproof casing

DISTRESS FLARES Aerial flares do not pinpoint your position, so they are best used in conjunction with other devices. They can be difficult to operate when wearing gloves, or with cold hands.

MINIFLARE 3
Unbreakable plastic box
Box houses firing mechanism

PERSONAL LOCATOR BEACON (PLB) Devices that broadcast radio distress signals can be used to alert surface and air searchers to your presence. Some are also equipped with bright lights for close-range visual detection.

PLB antenna flashes to aid location
Signal from beacon has range of at least 35 miles (55 km)

attention if the boat is not too far away. You should always carry a flashlight, since the beam can be easily spotted at night, especially when moved slowly in a scanning motion, both vertically and horizontally (*see pp.184–85*). Make sure you also carry a backup light. Strobe lights are even more effective, since their flashing light travels in all directions, eliminating the need for scanning. Flashlights and strobes must be robust and reliable; regular inspection and maintenance is vital, with special attention to sealing surfaces and O-rings.

Reflective signals are useful in bright weather. It is worth carrying an old CD or mirror to use as a reflective device to attract attention. Reflective patches on your hood and upper body may be visible to aircraft searching overhead. Dye markers stain the water and can help a search from the air, but should only be used once the aircraft is overhead, since the dye rapidly dissipates.

If you find yourself on the surface with no signaling devices whatsoever, waving your arms or even your fins and shouting may help to alert attention if your boat cover is nearby. Keep calm and persist with signaling.

INTEGRATED SAFETY DEVICES

Some safety devices can be integrated into existing gear. Air-horns, for example, attach to the low-pressure hose on your BC. These are far louder than whistles, and are useful if you are out of breath or under stress. Safety sausages can also be inflated with your BC.

BLACK DIAMOND
SEAQUEST

Standard BC



Air horn attachments

RESCUE FLAGS
A brightly colored flag is a cheap, simple-to-carry, easy-to-deploy, and highly visible location device.

Knives

A dive knife is essential for freeing yourself if you get snagged on fishing lines and other obstacles. The simplest dive knife—little more than a basic blade in a plastic mount—will get you out of most tangles, but a good one will prove an invaluable multipurpose tool.

SELECTING A KNIFE

Knives must be rustproof, but the better the rust-proofing of stainless steel, the harder it is to maintain a sharp edge. Titanium knives, while expensive, are light, rust-resistant, and stay sharp. Knives come in various sizes. Small ones can be mounted on your BC or belt, where they are easy to reach and out of the way.



TITANIUM KNIFE
This state-of-the-art blade has a tough sheath and an integral line cutter.

Standard knives with 4½ in (11.5 cm) blades are most popular. Blades may be serrated for sawing rope or smooth for slicing monofilament line, and may have a line-cutter notch. Blunt-ended blades are ideal for tasks that need leverage, such as prying open containers. It is worth choosing a knife with a metal pommel on the end, which can be used as a hammer.

SHEARS AND MULTI-TOOLS

Multi-tools incorporate both types of knife blades, for slicing and sawing—useful for rope and monofilament line. Underwater shears are only really needed if diving in very hazardous conditions or for use as tools in salvage.

Underwater shears



KNIFE SIZE
Large knives are popular, but a smaller blade can be just as useful on a dive.

Bags

Whenever you move to and from a dive location, you will need a bag to carry all your gear. Ideally, your chosen dive bag should be capacious and light, but it must also be durable enough to survive the rigors of transporting heavy equipment.

BUYING A BAG

When choosing a bag, check that it has strong seams, sturdy handles, and no parts that are likely to rust. Also consider security, especially when travel will involve your being separated from your baggage. Thin bags can be cut open, so a padlock will not guarantee that the contents stay safe. You may want to invest in a rigid or semi-rigid bag (*see p.238*).

Many divers use a large duffel bag for travel, and a smaller day bag (or even two) for dive days. Duffel bags range in size from 6,000 to 10,000 cu in (100 to 180 liters), day bags from 1,800 to 5,000 cu in (30 to 80 liters). There are countless “extra” bags, such as fin bags, mask bags, tool pouches, and pony-bottle pouches. While useful, most of these are not essential if you pack your gear carefully into one large duffel bag.

FLIGHTS TO FAR-AWAY LOCATIONS
Dive baggage has to be hard-wearing and tough, especially as several transfers are often needed to reach a dive location.

BAGS FOR DIVERS

MESH BAG Perforated bags can be used to rinse all your gear at once in fresh water, or to carry small items aboard a boat without fear of water ruining the bag.



Water-permeable mesh fabric

DUFFEL BAG These can accommodate most of your gear, and also have various compartments where you can stow small items, such as slates and carabiners.

Rustproof plastic zippers

REGULATOR BAG Your regulator is valuable, and needs its own padded bag. It can be put in your main bag, but when flying, most divers stow it safely in their carry-on.

Protective padded sides

DRY BAG When you reach the dive site, a watertight bag or case is essential to protect clothing and electrical equipment, such as cameras, from moisture and salt.

Aperture can be sealed

TRAVEL CASE A secure, rigid-sided case gives extra protection to your gear while in transit. Wheels and a telescoping handle make transportation easier.

Outer pockets for nonvaluable items

Gadgets and accessories

There are a host of diving gadgets on the market, including fun items such as underwater MP3 players. Other accessories, however, have more practical uses. Clips and retractors are very useful for securing equipment, and may save you the loss of a camera or flashlight.

DIVER PROPULSION DEVICES

Underwater scooters, usually referred to as DPVs (diver propulsion vehicles), make great toys, but they can be practical and useful, too—for example, when exploring a large wreck site. There are two basic types: those that you sit astride, and those you hold on to, which tow you along. It is safest to use DPVs only to travel on a horizontal plane. Descending or ascending under power can be very dangerous, due to rapid pressure changes. DPVs are not cheap, but there are less expensive models suitable for general recreational use—that is, where failure of the device would hardly constitute an emergency. More expensive but tougher, more reliable machines are generally not aimed at the leisure diver but intended for expeditions, such as cave explorations, where failure of the unit mid-dive would be a more serious development.

Jetboots, made by a California diving company, also propel the diver along effortlessly: they comprise a pair of propellers that attach to your legs, controlled by a switch at your waist. Jetboots can propel you as fast as some DPVs, and leave your hands free.



DIVER USING SCOOTER
A diver propulsion vehicle, or DPV, takes the effort out of exploring large dive sites.

BANDS, CLIPS, AND FASTENINGS

Cam bands—webbing straps that hold your cylinder to your BC—are available with a number of different buckle mechanisms that ensure that the tank is secure and held close to your body. Retractors are very useful for attaching items, such as a flashlight or slate, to your BC because they pull the item close to your body when not in use. Carabiners and bolt-snap clips (as used on dog leashes) are useful for attaching equipment securely to your BC during the course of a dive.



SAFE STOWAGE
When you have your hands full, retractor lanyards retain loose items, such as flashlights.

ATTRACTING ATTENTION

There is a range of gadgets that you can use to attract your buddy's attention underwater. Some BCs have a buzzer that uses a small amount of compressed air to generate a sound. Slightly more low-tech are tank pingers—a piece of elastic with a hard plastic ball attached. This is slipped around the cylinder and can be stretched and released to "ping" against it, creating a metallic sound that travels well underwater. Shakers are tubes filled with metal balls. When agitated, these create a clearly audible rattle.

WRITING UNDERWATER

Slates are handy for mapping dive sites or making notes on any unusual species encountered on your dive. They are made of white plastic, with a matte surface that can be written on with a pencil. Flat slates can be attached to a BC or slipped into a pocket; wrist-mounted slates are contoured to fit around your arm. The latter are especially useful when making technical dives with various decompression stops: you can read your computer and the list of stops from the same arm. A compass can be mounted on a flat slate, enabling you to look at navigational notes while checking your bearings.

AIR-LOCK TANK CAM BAND
Some dive gadgets are labor-saving devices. Tank band buckles that can be tightened using compressed air are a useful example.

New technology

In the 1950s, development of the scuba unit revolutionized diving, and its technology continues to develop apace. Modern equipment is sleek, lightweight, and colorful, and advances in the efficiency of rebreather systems are transforming diving once again.

MASKS AND VEHICLES

One of the most notable recent advances in modern dive equipment is the use of head-up displays in masks, which are similar to those used by military pilots. Essential dive information is sent via radio frequency from the tank to the mask, where it is presented on an LCD. Masks with an integral radio communication system, which allows divers to talk directly to one another, are also available.

Advanced synthetic materials have made dive equipment stronger and lighter, and have been used in the development of diver propulsion vehicles (DPVs; *see p.80*) that are smaller and easier to handle.



MASK TECHNOLOGY New mask developments include head-up displays of critical information (*top*) and masks that correct optical distortion underwater (*left*).

FROM SCUBA TO REBREATHER

In the last decade, rebreather technology has become available to the recreational diver, representing the most dramatic leap forward in diving equipment since the development of scuba itself.

In contrast to scuba—an “open circuit” system that discharges most of a diver’s air supply into the water with the exhaled breath—rebreathers recycle the diver’s exhaled breath, using chemicals to remove waste (mainly carbon dioxide) and allowing the diver to inhale the gas again. Each breath uses about 4 percent of the oxygen in the inhaled gas mix, so one of the main tasks of a rebreather is to maintain oxygen levels in the breathing loop, generally by adding extra oxygen.



UNDERWATER SCOOTER DPV The breathing observation bubble (BOB) is powered by an electric motor and has a top speed of 2.5 knots.

Rebreathers using pure oxygen were used by frogmen in World War II, for whom the absence of bubbles was vital to hide their presence. Dive depths were limited to 20 ft (6 m), at which point pure oxygen becomes toxic. A revolution in rebreather technology occurred in the mid-1980s, allowing the use of nitrogen–oxygen gas mixes rather than pure oxygen. Modern rebreathers electronically monitor the concentration of oxygen in the mix and adjust it to safe levels for a given depth.

Rebreathers offer longer dive times and fewer decompression stops. They remain costly, and need careful maintenance and specialized training.

REBREATHER TECHNOLOGY

Modern rebreathers are divided into two categories—semi-closed rebreathers (SCRs) and closed-circuit rebreathers (CCRs). SCRs expel a small quantity of exhaled gas into the water, whereas CCRs only dump gas into the water on ascent. Both types clean exhaled gas in a scrubbing unit, which removes CO_2. They also ensure that the oxygen content of the inhaled gas is at a suitable level for the diver, and monitor toxicity, which the diver can check manually on a gauge, or on a computer display. Computer control has dramatically increased the efficiency and safety of rebreathing devices.

HOW A REBREATHER WORKS

A chemical in the scrubbing unit absorbs carbon dioxide from exhaled gas, while pure oxygen is introduced to the breathing loop to replace that consumed by the diver.


Exhaled gas from mouthpiece flows into scrubbing canister
Pure oxygen cylinder replaces O_2 used by diver
Absorbent chemical in scrubbing unit removes CO_2
Air from cylinder maintains volume of gas in breathing loop
Data cable
Breathing Air
Oxygen O_2
Oxygen flow
Inhaled gas flow
Exhaled gas flow

Mouthpiece

Computer display

REBREATHER BENEFITS

Because gas is recycled in a rebreather, you use it up at a slower rate than with scuba gear, and so can spend longer underwater. The consistently high levels of O_2 help reduce post-dive fatigue.

Equipment assembly

The gear assembly process is a key part of any dive. During your training, you will be taught the basics of assembling dive gear. With experience and a few simple tips, you can perfect this process and make it efficient, rapid, and—most importantly—consistently safe.

THE IMPORTANCE OF PREPARATION

With clear, blue water beckoning, the Sun shining, and the dive site awaiting you, you may find that there is a great temptation to rush the gear assembly process. However, the equipment used for diving is nothing less than life-support gear, and should be treated with a corresponding level of respect. It is reasonable to say that putting dive gear together safely before jumping into the sea is as important as packing a parachute correctly before jumping out of a plane.

CHECKING FOR DAMAGE

The first stage in assembling your gear is to carry out a visual inspection. This is particularly important if the equipment is unfamiliar or rented. It is essential to examine the test dates (*see p.68*) for the

1 **Lay out equipment** on a mat or other clean, grit-free surface where you can assemble the gear easily.

2 **Wet the tank** band on your BC, if possible, since this helps improve its grip on the tank's metal surface.



3 **Position the tank** with the pillar valve O-ring facing the backplate of the BC, then fasten the band around it.



4 **Attach the regulator** first stage to the tank. Do not overtighten the clamp (or screw thread, on a DIN fitting).

5 **Pass the inflator hose** from your regulator's first stage (*see pp.60–61*) through the jacket's guides and straps before connecting it to the BC's inflator valve. Make sure the valve has engaged securely with the hose coupling.



INFLATOR VALVE

The spring-loaded collar on the end of the hose fits on to the inflator valve.

tank and also the integrity of the O-ring (*see p.88*). Any nicks or cuts in the O-ring may lead to serious problems during the dive, yet replacing a damaged O-ring before the dive takes only seconds. Also look for wear and tear on the regulator hoses, particularly where they join the ports of the first stage. This is a common point of strain for regulator hoses, resulting in cracks and splits in the hose with sustained use. If the integrity of a hose has degraded, it may rupture when the air supply is turned on.

Check for signs of damage to the BC. With regular diving, there will be inevitable signs of wear and tear, but be sure to check the integrity of the buckles and load-bearing straps. These must be completely sound.

ASSEMBLING YOUR GEAR

When you are satisfied that your equipment is in good order, follow the steps below to make it ready. Take particular care to ensure that the band securing the tank to the BC is neither too high (resulting in the tank possibly coming free), or too low (resulting in the pillar valve restricting movement of your head during the dive, or actually striking it on entry).

6 **Turn on the air** supply, opening the tank's pillar valve all the way. Then turn the knob a quarter-turn back.

7 **Test air supply** by breathing from both your primary and secondary air sources. Check air quality and delivery.

8 **Secure the gear,** if you are not diving immediately, by tucking any loose parts inside the BC for protection. Most breakages occur in transit.

Disassembly

The end of a dive is an exciting time, and neglecting your dive gear at this stage is an easy trap to fall into. Take a little time, however, to clean and store your equipment properly: not only will it last much longer, but everything will be in order at the start of your next dive.

DEVELOPING A ROUTINE

As with so many things in diving, routine is the key. Many experienced divers attend to their gear the moment the dive is finished, and regard the dismantling, rinsing, and storage of their gear as an integral part of the dive itself. This is particularly true for diving from a boat, where a shortage of space frequently leads to cluttered decks and broken gear. Diving equipment can cost a considerable amount of money, so it is worth taking a few moments to make sure it is properly dismantled and safely stowed.

The first stage of disassembly is to turn the tank off and purge any remaining air from the hoses using the purge button on the second stage (*see also pp.60–63*). The regulator first stage may then be removed from the pillar



1 **Shut off the gas** supply, turning the knob on the tank's pillar valve all the way off before disassembly.



2 **Purge gas from** the system using the purge button on the regulator to vent any air remaining in the hoses.



3 **Disconnect the inflator** hose from your BC's inflator valve, and the hose from the drysuit inflator, if worn.



4 **Disengage the regulator first stage** from the pillar valve of the tank, and free the hoses from the BC by undoing all the clips and straps.



A-CLAMP FIRST STAGE
Remove this type of first stage by loosening the clamp first.



DIN-TYPE FIRST STAGE
Turn the knurled collar to unscrew the regulator first stage from the pillar valve.

valve of the tank. It should take no more than finger pressure to turn the clamp or collar; any more resistance indicates that compressed air remains in the system. You will need to check that the tank is completely turned off, then purge the hoses again.

After removing the regulator first stage from the tank, use a blast of air from the tank to dry the dust cap and filter. Fit the dust cap securely, then rinse the regulator thoroughly in fresh water. Never forget to put the dust cap on, otherwise water will enter the delicate mechanism of the first stage: this is to be avoided at all costs. Hang the regulator up to dry, ensuring that the hanging method does not put strain on the hoses at any of the points of attachment to the first stage. You can then detach your BC from the cylinder and drain it of any saltwater. Rinse the BC inside and out with fresh water, and inflate it orally to allow quick drying and prevent the formation of salt crystals inside.

Dive gear must be dried thoroughly between dives, ideally by hanging it up out of direct sunlight. Do not store it where it is compressed or where moisture may accumulate, such as in a boat deck locker or a diving bag.



5 **Remove the BC** from the cylinder by undoing the cam buckle on the strap, and then sliding the BC upward until it is clear.



6 **Drain the BC** of saltwater by depressing the deflator button at the end of the corrugated hose. This allows the water to escape through the oral inflation point.

Equipment maintenance

Diving equipment is your life-support system underwater, yet many divers take a worryingly relaxed approach to maintaining their gear. A few simple steps will increase the life span of your dive gear, avoid the expense of constant replacements, and increase your safety.

TOOL KITS

Most divers carry a set of Allen keys, screwdrivers, or adjustable wrenches. Scuba multi-tools are all-in-one alternatives that incorporate virtually every basic tool that a diver might need on a dive boat or at a dive site. These include a range of hexagonal Allen keys designed to fit dive equipment and standard wrenches for regulator adjustment, as well as screwdrivers and a marlin spike.

Diving shops also sell “save-a-dive” kits, which consist of a set of lubricants, parts, and tools that can be used in the majority of equipment-related incidents on site. O-ring replacement and adjustments to hose configuration, for example, are simple, commonly required tasks that can be undertaken by anyone with such a kit.

Experienced divers also carry spare parts with them. This is sensible diving practice, and while the range of items differs from diver to diver, it usually includes items such as spare O-rings, silicone grease, tape, adhesive, an O-ring extractor, spare plugs for the regulator first stage, and any spare buckles or straps that might be necessary.

SCUBA MULTI-TOOL
A useful gift for any diver, this contains tools for most small maintenance jobs.

O-RING MAINTENANCE

The most disappointing reason for having to cancel a dive is the lack of a spare O-ring for a cylinder. O-ring malfunction may be indicated by air escaping once the regulator is fitted, but even in the absence of this you should make regular inspections to check that the O-ring has not degraded. In many cases, simply cleaning the O-ring and the valve groove with a lint-free towel will solve the problem. Pull the O-ring through your fingers—if you can feel cracks, it should be replaced. When removing an O-ring, never use a sharp tool, as this is likely to damage the ring.



1 **To remove the O-ring** from a cylinder’s pillar valve (*see pp.68–69*), use a specially designed extractor tool. Alternatively, use the rounded end of a tie-wrap or even a credit card.



2 **Inspect the O-ring closely** and replace it if any cracks or tears are visible. Clean the valve groove with a lint-free towel, then press the new O-ring in carefully with your fingertips.

ADDING A REGULATOR HOSE

To add a hose to your regulator or change an existing hose is a simple process. You must avoid attaching a low-pressure hose to the high-pressure port, as this will rupture the hose. Most regulators now make this impossible by having different- sized ports, although older models may not have this feature. The high-pressure port is for the pressure gauge, while other ports are for a second stage or the inflator hoses. It is worth taking time to ensure that the hose configuration is practical and comfortable, to avoid strain on the base of the hoses and reduce drag.



1 **When adding a hose,** be careful to select the correct port (high/low pressure). If the ports are not clearly differentiated, or if you are in any doubt, consult the manufacturer's manual.



2 **Remove the plug** from the regulator port using the correct-sized Allen key. Some regulators still have raised bolts—these can be loosened with a wrench.



3 **Attach the hose** by simply screwing it into place. Tighten the nut with a wrench of the appropriate size—hose nuts are soft and can easily be damaged by pliers.

4 **Exactly the same** procedure can be used to attach further hoses to the other ports, and to replace damaged hoses. Always check hoses for cracks, fraying, and abrasion.

EQUIPMENT MAINTENANCE
Post-dive, wash all of your gear in clean, fresh water, and check out any problems you may have noticed.

The diving environment

Introduction

When you go diving, you are introducing your body to an alien environment. Evolution has not equipped our bodies for the underwater world, and you will encounter unusual sensory phenomena when you descend into the depths for the first time.

LIGHT AND VISION

Our eyes are designed to focus in air; underwater, our vision blurs unless we wear a mask, which puts an air space in front of our eyes. However, light travels more slowly in water than it does in air, and as it passes through the mask from water to air it bends, causing refraction—an optical effect that makes objects appear bigger and closer than they are.

Colors also look different to us as depth increases (*see p.183*). Objects near the surface look as colorful as they would above water, but as you go deeper, first reds disappear, then oranges, yellows, greens, and blues, until all light is lost. Colors can be revived by illuminating a submerged object with a flashlight.

SOUND AND HEARING

Above the surface, sound travels at approx 1,150 ft (350 m) per second, but underwater it travels four times faster. This makes it hard to identify the direction of a sound source: if your buddy signals to you by tapping his tank, you will hear the sound easily but may not be able to pinpoint where it is coming from. The range of audible sounds is also reduced, but the underwater environment is not as quiet as is popularly supposed: you can hear the scratching and snapping sounds made by fish and crustaceans, along with the sound of your breathing and any



ANATOMY OF A DIVER
The land-based development of the human frame means that your body is not adapted to many aspects of the underwater environment.

Direction of sounds harder to discern

Objects appear closer to the observer

Verbal communication impractical

Exposed skin radiates heat more quickly into water, which is an efficient conductor

Internal cavities, such as the gut, are subjected to external water pressure as depth increases

Lungs must adapt to a longer, slower breathing cycle underwater boat noise close by. However, you will find it difficult to communicate verbally underwater, even if you remove your regulator and shout, which is why divers use hand signals (*see pp.144–45*).

Sounds made above water do not easily penetrate below the surface, so any noises made to alert divers must be made underwater. A typical recall signal from a dive boat is to bang on the metal ladder on the craft's stern, which, as its lower part is in the water, transmits sound to divers beneath.

SEA CHANGE
Divers patrol a reef wall in the Red Sea. As depth increases, physiological effects become more profound and numerous.

HEAT AND PRESSURE

Water conducts heat 25 times more efficiently than air, so the human body loses heat quickly underwater. In extreme cases, a diver may lose heat faster than it can be generated by their body, leading to hypothermia. When diving, it is important to always wear thermal protection appropriate to the conditions.

The airspaces in the body—not just the lungs, but the inner ear, sinuses, and gut—will be increasingly affected by pressure as you make your descent. This can lead to uncomfortable sensations (*see pp.98–99*) that must be relieved by equalizing internal and external pressure manually using the Valsalva maneuver.

Depth and pressure

To understand the principles of diving, it helps to have a grasp of basic physical laws. When you dive, water exerts pressure on your body, and this pressure increases with depth. This simple fact influences all aspects of diving, from buoyancy control to safety considerations.

UNDERSTANDING PRESSURE

On land, your body is constantly subjected to external pressure from the weight of all the gases in the atmosphere. This is called atmospheric pressure, and it is measured in pounds per square inch (psi) or bar. Atmospheric pressure at sea level is 14.7 psi (1 bar)—that is, 14½ lb pressing on every square inch (1 kg per square centimeter) of your body's surface. This pressure is not fixed; it varies slightly with weather conditions and decreases with altitude. At the summit of Mount Everest (29,028 ft/8,848 m), atmospheric pressure is only 4.5 psi (0.31 bar).

When you dive underwater, pressure is also exerted on your body by the weight of the water above and around you. Because water is denser than air, the pressure generated by just 33 ft (10 m) of seawater is equal to that generated by all the gases in the atmosphere above sea level. Seawater is denser than fresh water, because it contains dissolved salts and minerals. This increased density means that pressure increases slightly faster with depth in seawater than in fresh water.

When you dive, you are subject to the cumulative weight of both atmospheric pressure and water pressure. The combined total is known as absolute pressure. Your depth gauge translates pressure into an accurate depth reading, but it is calibrated to ignore atmospheric pressure, so it indicates zero depth when you are at the surface. This is known as gauge pressure. Always use absolute pressure to calculate the total pressure at a given depth.

HOW PRESSURE RELATES TO DEPTH

Because water is much denser than air, pressure increases quickly with depth underwater. Water cannot be compressed and transmits pressure freely, so pressure increases cumulatively, and at a constant rate, as you dive deeper. At a depth of 33 ft (10 m) of seawater, absolute pressure is 29.4 psi (2 bar). This figure is the sum of the pressure generated by the atmosphere (14.7 psi) and by 33 ft of water (14.7 psi). At 66 ft (20 m) absolute pressure is 44.1 psi (3 bar), and so on, rising by 14.7 psi for every additional 33 ft of water depth.

If diving at a high altitude site, like a mountain lake, atmospheric pressure is reduced; consequently, absolute pressure is lower, too. You must use special dive tables at such sites.



PRESSURE GRADIENTS
Normal recreational dives take place within a 100-ft (30-m) depth range from the surface.

HOW PRESSURE AFFECTS GASES

In the 17th century, scientist Robert Boyle made an important discovery. He found that at a constant temperature, the volume of a gas is inversely proportional to the pressure exerted on it—meaning that as pressure increases, the volume that a gas occupies decreases. This relationship is known as Boyle's law.

Boyle's discovery has important implications for divers. Buoyancy devices such as BCs contain bladders filled with air. These provide upward lift to help you float weightlessly underwater. As you descend, however, increasing water pressure compresses the air inside the BC. This means it displaces a smaller volume of water, and so generates less buoyancy (*see p.97*), causing you to sink. You must then inject more air into the BC to boost volume to its former level. On ascent, this must be released again, because as pressure decreases, the extra air inside the BC expands, causing you to become very buoyant and rise too quickly. For the same reason, you should never hold your breath underwater. Compressed air inhaled at depth expands as you ascend, and if it is not exhaled, it can burst delicate vessels in your lungs.


Descent
Ascent with added gas
Balloon bursts when it can no longer contain expanding gas
Gas expands during ascent
Additional compressed gas added at depth
KEY
● Gas particle

If you took a volume of gas, like that contained within a balloon, and submerged it, the space the gas occupied would get smaller with increasing depth.

If you added extra gas to the same balloon at depth, it would expand slightly. During ascent, the gas inside would expand to more than the balloon's original volume.



IN DEEP
Diving exposes you to pressure effects not encountered on land.

Breathing compressed gas

On land, we seldom need to worry about the availability of air, its composition, or the pressure it is supplied at. But when you venture underwater, things are very different. Being aware of how the diving environment affects your respiration cycle is of prime importance.

BREATHING UNDERWATER

Scuba divers draw breath from a tank of highly pressurized air, via a regulator. The regulator (*see pp.60–61*) reduces the pressure of the air in the tank to that of the water around you (ambient pressure), allowing it to be inhaled safely. As depth increases, so does ambient pressure, meaning that the regulator must adjust the pressure of the air it delivers to match.

Air, like any gas, is compressible, and becomes denser when pressurized. This means that at depth you will be inhaling more air per breath than you would at the surface (because the gas molecules are packed in more tightly). Because air is mainly composed of oxygen and nitrogen, this means you will be breathing higher concentrations of both gases than you would be at the surface, though the percentage of each in the mixture does not change. Both of these gases can have toxic effects on the body when pressurized. Nitrogen enters your body's tissues, and can have a narcotic effect (*see pp.100–01*). Oxygen is vital for supporting life, but becomes toxic if inhaled in sufficient concentrations. As the pressure of the air you are breathing rises, there are more and more molecules of oxygen packed into each breath you take. Beyond a depth of 200 ft (60 m), there is a risk that the concentration of oxygen in pressurized air could have a



WHAT AIR IS MADE OF
Air is mainly composed of nitrogen, with oxygen forming nearly 21 percent. Inert gases like argon and freon form the remainder.

DEPTH AND AIR CONSUMPTION

Most divers consume approximately 1 cubic foot of air per minute at the surface, though this rate varies between individuals, and is also dependent on how much you exert yourself, and what your mental state is. An anxious or excited diver will consume more air than a calm one.

Because your regulator supplies you with denser air as you go deeper, your air consumption will also increase as you descend. In seawater, your Surface Consumption Rate (SCR) will have doubled by the time you reach a depth of 33 ft (10 m), tripled by 66 ft (20 m), and so on. There are various methods of obtaining an accurate calculation of your SCR, which you will find in your diving manual. Once you know this you will be able to establish how long the air in different sizes of tank (filled to maximum operating pressure) will last at different depths, and plan your dive accordingly.



toxic effect on the body, leading to convulsions, loss of consciousness, and even death, in extreme cases.

To get around these problems, “technical” divers going beyond the limits of normal recreational diving (*see pp.194–95*) use special gas mixes. These contain altered percentages of oxygen and nitrogen, and also include helium. These mixes are used during dives in excess of 165 ft (50 m).

WASTE GASES

One by-product of the respiration cycle is carbon dioxide. The more you exert yourself, the more carbon dioxide is produced. Since your body’s breathing reflex is triggered by a build-up of carbon dioxide in the blood, not by falling oxygen levels, overexertion underwater will make you feel short of breath. On the surface, your body would respond to this by breathing faster, thus flushing out carbon dioxide. Your regulator, while efficient, cannot process the same volume of air as you can breathe on land. Always rest for a moment if you begin to feel breathless.

BREATHING AND BUOYANCY

An object immersed in water is subject to an upward thrust equal to the weight of the water it has displaced. You will only float, therefore, if your weight is less than that of the water you displace. If it is greater, you will sink; if the two are equal, you will do neither—you will have neutral buoyancy. The compressed gas you breathe underwater alters your buoyancy. When you inhale, the volume of your chest gets larger—you displace more water without becoming any heavier, and so become more buoyant.

A diver displays buoyancy control

DEEP BREATH
Slow, even breathing patterns promote low air consumption and help prevent hyperventilation.

Pressure and the body

When you dive, your body is subjected to pressure generated by the weight of the water around you. As you descend, you will feel the increase in pressure in some of your body's internal air spaces, chiefly your ears. If you do not act to correct this, you may be injured.

EQUALIZING PRESSURE

The body contains four major air spaces that are affected by pressure underwater: the ears, the sinuses, the airways and lungs, and the stomach and gut. Air spaces in our respiratory and digestive systems are compressible, in that they are contained by soft tissue that can expand or contract to accommodate pressure changes. However, your regulator (*see pp.60–63*) ensures that the air pressure in your lungs and airway is always in equilibrium with external water pressure, so pressure effects are never felt here. You should barely notice any effect on your stomach and gut, although you may break wind, especially on ascent.

The air spaces in your head, however, such as the ears and sinuses, are rigid and cannot be compressed. When the pressure outside them is greater than that within, a "squeeze" is created, which can cause pain and damage, especially to the eardrum. You must equalize the pressure in these cavities with the ambient pressure of the water around you as you descend. Equalizing is simple, using a procedure that clears the ears called the Valsalva

ROUTINE MANEUVER
Equalize pressure in your ears and sinuses every 3 ft (meter) or so, during your descent to the bottom. Don't wait until your ears begin to hurt.

THE IMPORTANCE OF EQUALIZATION

The ear is divided into the outer, middle, and inner ear. The eardrum separates the middle and inner ear from the outside world, and it is this membrane that is most vulnerable to pressure changes. If you do not equalize as you descend to raise the pressure behind your eardrum—by sending air to the ear from your throat via your eustachian tubes—then the eardrum will eventually rupture and let water into your middle ear, leading to possible infection and deafness. Your sinuses are pairs of cavities within the bones of your face. Under normal circumstances they are open, via your nasal passages, but if you have a cold, or congestion caused by allergies, they fill with mucus and become blocked. Failure to equalize will cause blood vessels in the lining of the sinuses to rupture and bleed into the sinuses, which can be quite painful.



Air spaces involved in equalization

maneuver. You just have to hold your nose and breathe out against your nostrils. This will send air from your throat through the eustachian tubes into the middle ear so that the pressure there becomes equal to that of the water outside, thus easing the discomfort. This maneuver should also equalize the pressure in your sinuses, and in addition resolve any problems of dizziness or vertigo you may be experiencing (as balance is also controlled within your ears). Some people get the same result by simply swallowing repeatedly.

You need to equalize regularly on descent, but on ascent equalization should occur automatically. If you have problems equalizing on the way down, ascend a little to reduce the pressure slightly, and try again. This equalization process is vital for comfort when diving; never dive with ear plugs or with anything tight over your ears. Check that your hood does not fit too tightly, as this can hinder efficient equalization. If you have any problems with your sinuses or ears, do not attempt to dive, since this may make them worse. A cold, or any nasal congestion, may cause blockages in your airways and you will not be able to clear your ears and sinuses. If you notice a slight nosebleed after a dive, this is a common sign that you have a mild sinus blockage and you should not dive again until it has cleared up. Decongestants will not necessarily help once you are at depth, and you should not dive while you are taking them.

SAFE DESCENT
To adapt safely to the underwater world, you must understand how depth affects the human frame, especially internal cavities.

Nitrogen and decompression

When you dive using scuba gear, nitrogen gradually accumulates in your body, and is released when you ascend. In order for this to happen safely, you must plan your dive carefully and employ diving procedures that minimize the risk of decompression sickness (DCS).

BOTTOM TIME
The longer you spend at depth, the more nitrogen builds up in your body.

GAS ABSORPTION

Gases are soluble in liquids, and dissolve more easily when they are pressurized. When you breathe compressed air underwater, the two main gases it is composed of (nitrogen and oxygen) enter and dissolve in your bloodstream. This "gas exchange" takes place in the lungs, via tiny saclike vessels called alveoli.

Nitrogen is particularly easily absorbed into the blood and body tissues. Your regulator supplies denser and denser air as depth increases (*see also p.60*), which means that every breath you take is loaded with more nitrogen molecules than an equivalent breath at the surface. This surplus of nitrogen rapidly accumulates in the tissues of your body. If you ascend too quickly, the nitrogen in your tissues can reenter the blood in the form of harmful bubbles. It is therefore very important for you to manage your dive time and depth,

NITROGEN AND BODY TISSUES

When you breathe compressed air underwater, its nitrogen content enters the blood and begins to penetrate the body's tissues. When you ascend, ambient pressure drops and nitrogen starts to come out of the tissues again. If your ascent is slow and controlled, the nitrogen reenters the blood and exits the body harmlessly, via your lungs. If your ascent is too fast, the escaping nitrogen can form harmful bubbles, leading to decompression sickness (DCS; *see pp.142–43*). DCS can cause minor discomfort if the bubbles are lodged under the skin or in the joints, but if they are in the brain or nervous system, it can lead to paralysis or even death.



NITROGEN ENTERS BODY TISSUES
Pressurized air dissolves in blood and its nitrogen content enters tissues, especially fatty areas, where it is temporarily stored.



FORMATION OF NITROGEN BUBBLES
If pressure drops too quickly during ascent, nitrogen forms bubbles in the bloodstream, which can lead to decompression sickness.

PERFECT PERCH
Dive boats sometimes lower a “trapeze” for divers to hold on to while making decompression stops, with a spare air tank attached for safety.

using either dive tables or a dive computer, to ensure that nitrogen does not build up to levels that cannot be safely dissipated during ascent.

Dive tables help you to calculate how long you can safely dive at a given depth, and what the safe limits are for any following dives that day (excess nitrogen takes 24 hours to fully leave the body). The tables will also tell you if you need to perform a decompression stop. This is a scheduled pause in your ascent that allows nitrogen to dissipate safely. It is a good idea to stop at 16 ft (5 m) for three minutes during ascent, even if your dive tables do not require it, just as a precautionary measure. This is called a “safety stop.” Dive computers also generate safe diving schedules, by making continuous calculations during the dive (*see pp.66–67*).

NITROGEN NARCOSIS

The nitrogen in compressed air can also have a narcotic effect at depth, ranging from a feeling of euphoria to anxiety. Nitrogen narcosis rarely causes death directly but at depths below 30m (100ft) it causes divers to make increasingly bad judgments. If you feel the effects of narcosis during a dive, ascend to a shallower depth and the narcosis should rapidly disappear. Keep an eye on your buddy for symptoms of narcosis, such as sluggish responses and irrational behaviour.

USING DIVE TABLES
An understanding of the use of dive tables is a key element in all dive training programs.

Tides and currents

The tides have a huge impact on the marine life and conditions of many dive sites, and localized currents can create unseen offshore hazards. Knowing how tides and currents work and how they affect diving procedures is essential for safe diving at any location.

TIDAL MOVEMENT

Water levels at the shoreline can vary considerably over the tidal cycle, in extreme cases by as much as 50 ft (15 m). The region between the highest and lowest tide marks is called the intertidal zone.

Make a thorough check of local tidal conditions and coastal topography when planning a dive, otherwise you may encounter unexpected hazards, like areas of strong tidal flow. Water clarity varies from site to site, but it is often best at high tide, while incoming tides tend to bring marine species closer in to shore with them. The most important tidal event for divers is "slack water," a short interval when tidal flow halts at the changeover of every tide. Tidal currents mean that some sites are only safe for diving during the slack water period.



INTERTIDAL ZONE
Sometimes submerged and sometimes exposed, this is a harsh habitat for marine life.

HOW TIDES ARE FORMED

The Earth's seas are subject to the gravitational pull of both the Sun and the Moon. Although the Moon is smaller than the Sun, it is much closer to the Earth, so its influence is stronger. The gravitational pull of the Moon draws water into a bulge on the side of the planet closest to it. A counter-bulge forms on the opposite side of the Earth because the water there is pulled less toward the Moon than the planet is itself. As the Earth rotates, the two opposing bulges of water move across the face of the planet, creating two high tides and two low tides in just over 24 hours.

NEAP TIDES: FIRST AND THIRD QUARTER MOONS
With the Sun and Moon at right angles, high tides are at their lowest, as they are subject to the gravitational pull of the Moon alone, but low tides are at their highest, pulled by the Sun.

SPRING TIDES: NEW AND FULL MOONS
Twice a month, the Sun and Moon are in line with the Earth. Their combined gravitational pull creates the highest high tides, and low tides are at their lowest.



TYPES OF CURRENTS

Currents are created by winds, tides, the rotation of the Earth, and the confluence of bodies of water of differing salinity and temperature. Tidal currents occur when local topography, such as a narrow channel, creates an area of unusually strong flow when the tide is coming in (flooding) or going out (ebbing). These currents can be powerful enough to carry away even strong swimmers.

DIVERS EXITING SEA
Plan your entrance and exit so that you avoid swimming against the tide. The best time to dive is usually at "slack tide"—at high or low tide, when the tidal pull is weakest.

Standing currents are permanent currents independent of tides. Longshore currents, which flow in one direction along the coast, are localized standing currents. There are also standing currents in the open ocean, such as the Gulf Stream, which flows northward from the Gulf of Mexico, driven by the prevailing southwest winds, to the mid-North Atlantic, where it divides into two lesser currents.

Rip currents occur when incoming waves force the backwash from previous waves sideways. The backwash streams along the shore until it finds a route back to the open sea, such as a gap in a sandbar, and surges out in a strong, narrow current, perpendicular to the shore. To escape a rip current, swim across the current, parallel to the shore. You may find that trying to swim out of a rip current leads you into a longshore current, which pushes you back into the rip current. If this happens, swim out of the rip current in the opposite direction.

WAVE SURGE
Underwater topography and weather conditions can combine to create dangerously strong water movement where surf breaks on the shore.

Diving skills

Introduction

Good basic skills are key to being a competent diver. Some techniques, such as buoyancy control, may seem difficult to master at first, but with practice they will become second nature, allowing you to relax and enjoy your dives. Skilled divers are also safer divers.

SUPPLEMENTING YOUR TRAINING

This chapter of the book discusses diving skills, but is not intended to be, or in any way replace, a training manual. While it covers the skills and techniques that are taught in the basic dive training offered by approved agencies, it must not be used in place of any element of that training. There is no substitute for comprehensive dive training with a certified instructor.

In this chapter, therefore, we outline the skills you need in order to be a safe and competent diver. Many people only dive once a year on vacation, or even less frequently, so it is very important to keep up to date with your diving skills. If you have been away from diving for any length of time, take a refresher course or an easy trial dive.

STEPPING OUT
Knowing how to enter the water properly will help you get your dive off to a good start.

USING A COMPASS
Don’t forget to practice navigation skills regularly. Getting lost can ruin a dive, and may hinder your return to a safe exit point.

You will find that most of your basic skills are still familiar to you after a break, or will come back in due course. However, if you are put in a stressful situation, you may not be able to react quickly and effectively if your skills are rusty. Even experienced divers can benefit from regular practice of basic skills, and you should always be thinking about how to improve your equipment configuration and technique.

KEEPING SKILLS CURRENT

A great way of keeping your skills up to date is to practice in a pool (*see pp.146–49*). This might not be as much fun as getting out into the open water, but it will certainly provide you with a safe environment in which to perfect key skills such as buoyancy. Regular training in a pool or sheltered water can help you to meet the challenges of open-water diving more confidently. If your local waters are cold and stormy in winter, use the off-season to brush up drills and procedures. Joining a diving club may give you access to a nearby pool.

DEPLOYING A BUOY
Diving requires the use of many items of special equipment that you must learn how to use safely.

Pre-dive skills

Good organizational skills will help ensure a trouble-free diving trip. A successful dive begins before you even leave your home, with checks on weather conditions and equipment. Even if someone else is organizing the dive, make sure you are well prepared and informed.

GETTING OFF TO A GOOD START

On the morning of the dive, get a detailed, up-to-date weather forecast specific to the site you are diving, and double-check tide times if appropriate. If you don't feel well for any reason, make an honest assessment of whether you are fit to dive that day. It is better to sit out a dive than to feel ill underwater and have to abort. Illnesses affecting lung or circulatory efficiency also increase the risk of decompression sickness (*see p.142*)—a very good reason for skipping the dive.

Always check your gear before you set off on a diving trip. Before you leave home, you must be sure that you have everything you need. It is good practice to make a checklist of all the items you will need, and keep this in your bag. When you arrive, be sure to transfer all your gear from the initial mustering point to the actual dive site, or onto the boat you are diving from. All too often, divers leave a vital piece of

BRIEFING FROM DIVE LEADER TO GROUP
While a group leader will take overall charge of the dive plan, you must take responsibility for your own fitness and equipment readiness.

DIVING WITH A NEW BUDDY

Diving abroad often means that you will dive with strangers. Make sure you give the dive organizer an honest assessment of your level of ability and interests, so they can pair you with a suitable buddy. Even if you don't know your buddy, give them all the respect and assistance you would offer a familiar dive partner.

gear on the dock, such as a weight belt or mask, and only realize their mistake when the dive boat reaches its destination—by which time it is too late.

DIVING FROM A BOAT

The boat should have been booked in advance, but even so, it is polite to call the skipper again before you arrive. He or she will be able to confirm that weather and conditions are favorable for diving. When you board, check that the boat has adequate first aid and safety signaling devices on board, and appears to be in a seaworthy condition. Before you leave shore, notify the coastguard or relevant authority—and do not forget to inform them of your safe return when you get back. Ensure that the skipper reviews safety procedures, including the location of lifejackets, flares, and life rafts, and demonstrates the underwater recall signal.

GETTING READY TO DIVE
If you have organized your day efficiently, you will be able to relax and concentrate on getting yourself ready to dive.

COMFORT AFLOAT
Remember to bring seasickness tablets with you on boat trips. Test them 24 hours beforehand to make sure they have no adverse effect on you.

DIVING FROM THE SHORE

If you are diving from the shore, always check for the easiest possible access to your dive site on arrival (or before) to avoid long walks down to the beach with heavy gear. You may need permission to drive to the water's edge to unload.

WATCHING THE WEATHER

Obtain a forecast that includes the wind speed and direction, sea state, and visibility (fog, mist, etc). Do not take any risks with diving in bad weather—it is better to miss the dive than dive in surging seas or in visibility so poor your boat cover will not be able to locate you. You should also check tide tables to establish the timings of slack water. This is critical when diving areas affected by strong tidal currents.

Rough seas

Final checks

Diving with a partner (or buddy) means that there is someone to help if you encounter problems underwater. For the system to work properly, however, you and your buddy need to conduct your own briefing before a dive and check that all equipment is functioning properly.

MAKING BUDDY CHECKS

Just before the start of the dive, get together with your buddy and assemble your gear (*see pp.84–85*) and put it on. There is no particular order in which to do this, but most divers find that to avoid overlooking anything, it is useful to develop a routine. When you are both suited up and before either of you enter the water, you should carry out a buddy check—sit or stand next to your buddy and carefully check each other's gear, following the sequence shown below. Do not be tempted to rush these vital checks—you may regret it later. They ensure that you know how each other's gear is assembled, how it works, and that it is functioning. They also serve as a double-check that neither of you has overlooked anything before you dive.



1 **Check BCs** so that you and your buddy know where each other's inflation and deflation points are, and ensure that they are working. Do the same for drysuits, if worn.



2 **Check that weights** are present and securely fastened. You and your buddy must be especially aware of how each other's weights are released, in case either diver is incapacitated.



3 **Check harness is secure** and note where, on your buddy's kit, key fastening points and harness release clips are located, and how they are operated.



4 **Check air contents** gauges and breathe from your regulators to check they are working. Test each other's octopus second stage.



BUDDY BRIEFING

Suiting up provides a good opportunity to talk over a dive plan with your buddy. Ensure first that you are both agreed, as a pair, on the aim and course of the dive, your entry and exit points, and your predicted maximum depth and time for the dive. Check that you both have the required amount of air for your plan (including a reserve for emergencies). Agree on who will lead the dive and on whether you will dive to the left or right of your buddy. Decide on all communication signals, including how and when you will signal for the end of the dive, and on what you will do if you become separated. Once you have agreed a plan, stick to it unless it becomes impossible to do so. If circumstances change during the dive, use hand signals to discuss how, as a pair, you are going to modify the dive.

5 **Ready to dive?** Give each other a last once-over to establish who is carrying any miscellaneous pieces of gear, such as reels and slates, and where they are fastened. When you are ready to dive, make a final OK signal.

PREVENTING FOGGING

Mask fogging is a very common inconvenience, and is caused by oils on the mask's lens allowing moisture to bead. The traditional way to prevent fogging is to rub saliva onto the inside of the lens glass, then lightly rinse clear, before putting on the mask for a dive. Anti-fogging sprays are also available.


Using an anti-fogging spray

Entry

Every site will require a different method of entry, and the easiest method possible at each site is the best one to use. In all cases, it is safer to enter without large, heavy equipment, such as cameras, so if conditions allow, have them passed to you once you are in the water.

SHORE ENTRY

When entering the water from a beach, make sure your gear is assembled and on your back, then carry your mask and fins to the water's edge. There, put on your fins and mask with your buddy's help and walk backward into the water (walking forward with your fins on is difficult). As soon as you are deep enough, lower your center of gravity by bending down, then start to swim, or "fin," out into open water. If there is surf, make sure your BC is partially inflated and wait until a big wave approaches; lean into it, and let the return surge take you away from shore.

ENTERING FROM THE SHORE
If entering through surf, be careful not to lose your fins as you put them on. Breathe from your regulator throughout entry.

CONTROLLED SEATED ENTRY

This is the easiest method of entry into a pool or from a platform just above water level, and an especially useful method if you have difficulty with mobility on land or with keeping your balance when standing on a floating platform. It also enables you to put on your gear while seated.



1 **Turn from the waist** to place both hands on the hard surface to one side of your body, ready to take your weight.



2 **Pivot your body around,** using your hands to support you, so that you turn to face the side while easing yourself into the water.

GIANT STRIDE ENTRY

Stepping into the water is a good entry method to use from a large diving boat or off a dock or platform, provided there is sufficient depth of water. Partially inflate your BC, place your regulator in your mouth and hold it and your mask in place with one hand, and take a large stride out into the water.



Hold on to any gear, such as a flashlight or camera, that could rise up on impact and hit your face

1 **Take a giant stride,** holding your mask and regulator in place. Keep looking forward, not down.

2 **On splashdown** the splayed-scissor position of your legs will cushion the impact and keep you at the surface.



ENTRY POSITION
Hold your mask and regulator in place with one hand and ease yourself backward until your tank is hanging over the water.

BACKWARD ROLL

Use this entry from small boats with a low freeboard (distance from deck to waterline). With your regulator in place, check that your fins are free from obstruction, and that the water behind you is clear. Ease yourself over the edge and roll over backwards, aiming to hit the water first with your upper back.

BUDDY PROCEDURE AND SIGNALS

After entering the water, meet on the surface and make an OK signal (hand on head or fingertips together) to shore or boat cover. One exception to this is when making a negatively buoyant entry through strong surface currents. In this case, descend as quickly as possible, and rejoin your buddy on the seabed.



Standard "OK" signals

Descent

Descending to the seabed is always an exciting experience, but while you may want to get there quickly, you must always descend in a controlled manner. The method you use will depend partly on the site and prevailing conditions, and partly on your own preferences.

MAKING YOUR DESCENT

Having met up with your dive buddy in the water, follow the preparatory steps below. If you find that you do not sink, check that no air remains in your BC (and drysuit, if applicable). If the problem persists, you probably do not have sufficient weight on your belt (*see pp.70–71*), and should return to the boat or the shore to get some more. It is a good idea to note how much weight you need each time you try a different equipment configuration—record the details in your logbook for reference.

At a depth of 10 ft (3 m) you should carry out a bubble check. This involves briefly stopping so that you and your buddy can check each other's equipment for signs of air leaks—for example, from an incorrectly fitted hose. This will allow you to return to the surface to resolve the issue before you resume the dive. By fixing minor problems now, you may avoid bigger problems during the dive that could lead to an emergency.

As you descend, you will feel pressure in your ears. Release this regularly by swallowing or holding your nose and

1 **Meet up with your buddy** on the surface, well clear of any boat cover. If using a snorkel, remove it, and switch to breathing from primary regulators.



2 **Give an OK signal** to each other when ready to begin the dive. If using a "buddy line" to link yourselves together (useful when one buddy is a novice), ensure now that you are both attached.



3 **The "down" signal** confirms your intention to descend immediately. If your buddy is a novice or nervous, reassure them by holding their hand and helping them to descend.

4 **Both you and your buddy** should deflate your BCs and exhale together, so that you become negatively buoyant and start to sink simultaneously. If you have a problem sinking, address it now.

BUBBLE CHECK
Buddy pairs check each other’s gear for telltale air leaks before descending further.

blowing against the closed nostrils—a process called “equalization” or “ear-clearing” (*see also pp.98–99*). If you feel you are descending too fast, allow a little air into your BC. Your mask will also start to press on your face; relieve this by exhaling gently through your nose. If you are wearing a drysuit, you will feel the water pressing it against your body. Ease this by letting air into the suit, but not so much that it alters your buoyancy too greatly—and remember to release it again on ascent.



EQUALIZATION
Pinch your nose and blow at intervals to equalize pressure in the skull with that of the water.

DESCENT OPTIONS

Many divers prefer to descend feet-first so that they can remain face to face with their buddy and maintain eye contact. This is good practice, unless you need to descend quickly through a current and therefore have to use your fins.

A free descent is where no line is used and you descend freely (head- or feet-first) to the seabed. If you are using an SMB (*see pp.74–75*), ensure before descent that the buoy is fully inflated and the line is free. Your buddy should stay on the same side throughout the descent to avoid confusion and tangling in the line. On group dives there may already be a weighted guideline in place, attached to a buoy and leading to a wreck or fixed point on the seabed, which will give you and your buddy a handy point of reference. Do not use the line to pull yourself down, since it may not be anchored securely at the base.

FINAL CHECK
A group of divers meeting at the bottom of a guideline give a last “OK” signal to each other before exploring the dive area.

Breathing underwater

Swimming freely underwater for the very first time can be exhilarating, but also potentially unnerving and even frightening. Learning and perfecting good breathing techniques allows the novice diver to become calm and relaxed in this new environment.

LEARNING TO RELAX

The sheer thrill of your very first dive will cause your heart rate to increase and make you breathe faster than normal. You may be alarmed at how quickly your air supply runs out, but after a few dives, you will learn to be calmer and more relaxed, and your air consumption will decrease. When you feel comfortable underwater, take a few moments to concentrate on your breathing and remind yourself of the dos and don'ts of underwater breathing.

CONSERVING AIR
The more relaxed you are, the less air you will use and the longer your dive will last.

First, and most important, never hold your breath underwater, because you will run the risk of bursting a lung. Inhale and exhale more deeply than you would normally do on land. Try to maintain neutral buoyancy (*see pp.118–21*), since this will decrease your need for leg and arm movements to maintain a constant position, and thus reduce air consumption. Furthermore, avoid

BREATHING OUT
If you remove your regulator, exhale slowly to minimize the risk of lung expansion injury.

CLEARING THE REGULATOR
A regulator can be cleared of water by simply exhaling, or by pressing the button on the front to purge the water.

FREQUENT CHECKS
Buddies should regularly check each other's air reserves, to maintain a good awareness of the remaining levels of both members of the team.

swimming unnecessarily against currents—it is better to go with the flow than to waste your air by overexertion.

Always be aware of where your buddy is and what he or she is doing; many novice divers lose sight of their buddy and rapidly become anxious. If there is a problem, stop, breathe, and think before taking action. Acting too quickly and without thought could lead to panic and further problems.

Make sure that you are familiar with your equipment and fully understand how it works. You must know exactly where each item is stored to avoid panic if things go wrong during a dive—for example, if you lose your regulator or your mask begins to fill up. Regularly practice emergency procedure drills (*see pp.136–43*), either in the pool or in open water, to ensure confidence in a real crisis.

PLANNING YOUR AIR CONSUMPTION

On an open-water, fairly shallow dive, the rule of air consumption is to plan your dive so that you can carry out your descent, exploration, and ascent, and still surface with a reserve of 725 psi (50 bar). If you have to come back to a given point to exit, such as a guideline or anchor line, start your return when you have 1,500 psi (100 bar) left. If there is a current, swim out against it and swim back with it, so that the return is never longer than the outward trip. It is also wise to swim back to your point of entry or shotline at a shallower depth than on the outward journey, since this reduces air consumption. In difficult environments, follow the "Rule of Thirds" (*below*).

THE RULE OF THIRDS

When planning a dive in an environment that is covered overhead—such as a wreck, cave, or under ice—or when making deeper dives, always apply the Rule of Thirds. The rule states that you should use a third of your air for descent and exploration, and a third returning to your guideline or point of entry and for ascent. The remaining third is an emergency reserve.



Buoyancy control

Without doubt, the most important skill for a diver to master is that of buoyancy control. Until you achieve this, you will be constantly expending effort in order to maintain your position in the water, wasting air resources and distracting you from your dive.

SUITS AND WEIGHTS

Wearing any type of exposure suit will make you more buoyant in the water, and thus make it more difficult to dive. Drysuits contain an airspace between the suit fabric and the diver's body. Wetsuits have air cells within their neoprene fabric, and so the thicker the neoprene, the more buoyant you will be. The function of weights is to counteract the buoyancy your suit gives you so that, with your lungs full of air but your BC uninflated, you float at the correct level at the water's surface.

Correct assessment of how much weight you need to carry for a given dive is very important. Spend time conducting weight tests for different suit and equipment combinations, and note your findings for future use. Remember, saltwater is denser than fresh water, so you will require more weight when you dive in the sea than in fresh water.

USING YOUR BC

At the start of a dive, you will usually enter the water with your BC inflated, as having positive buoyancy allows you



Too high



Too low

CONDUCTING A WEIGHT TEST
Empty your BC, and take a deep breath and hold it. Float in an upright position. If you are wearing the right amount of weight, you will float at eye-level to the waterline. Add or discard weights as necessary until this is achieved.



Correct level

to float at the surface effortlessly while you meet up with your buddy—the only exception to this is at sites where there are strong surface currents, when it is important to get to the bottom quickly.

In order to descend, you must be negatively buoyant, which you achieve by deflating your BC and exhaling (*see pp.114–15*). However, as you sink, you will find that your descent rate accelerates as your suit—and the remaining air in your BC—becomes compressed. To counteract this, you must add air to your BC. If this halts you before you have reached the desired level, let air out. Repeat the process, letting small amounts of air in and out of your BC until you become stationary at the desired depth.

When this happens, you will have achieved neutral buoyancy underwater—a state in which you neither float nor sink. Achieving this perfect equilibrium of weight ballast and lifting forces means you do not waste effort and air using your fins to maintain a certain depth.

When you want to ascend, the same control principles apply, but in reverse. As you go up, the air in your suit and BC expands as external water pressure decreases, making you increasingly buoyant, and causing you to rise rapidly. As it is important to ascend at a slow,

LEARNING THE BASICS
An instructor looks on as a student diver practices fin pivots (*see pp.146–49*), an exercise designed to improve basic buoyancy control.

HOVERING OVER A REEF
Buoyancy control is critical when diving over delicate coral that can be damaged by physical contact.

steady rate (*see pp.128–31*), you'll need to vent air accordingly as you rise. To descend and ascend as smoothly as possible, you must become familiar with how your BC responds to inputs of air, and how quickly it vents air.

Drysuits have independent inflation and deflation controls (*see pp.54–55*). If you are diving in a drysuit, the air space between your suit and your body will become compressed, and you will need to inject a little air into the suit to avoid discomfort from being "shrink-wrapped" by external water pressure. This will make you more buoyant, so you will need to vent air from your BC to counteract it. On ascent, you will need to dump the excess air from your drysuit.

FINE CONTROL OF BUOYANCY

Small movements up and down—to look at different parts of a reef, for example—are best achieved through breath control, rather than letting air in and out of your BC. Good buoyancy control only comes with practice, and is worth perfecting. Take time at the start of each dive to practice fine control of buoyancy before you set off exploring. From a neutrally buoyant position on the seabed, slowly inhale—you should rise up and hover just above the seabed. Breathe out a little—you should sink. Practice breathing in and out and become familiar with how it influences your gentle rise and fall. You should be able to hover over the seabed and control your buoyancy by breathing alone, without constantly filling and

JETTISONING YOUR WEIGHTS

In extreme circumstances, such as being caught in a powerful downcurrent, it may be necessary—as a last resort only—to dump your weight belt. You will instantly start to rise up rapidly through the water, so be ready to vent air from your BC to slow your ascent. Breathe out on the way up, to minimize the risk of lung expansion injury (*see p.95*).



Efficient finning style maintains correct horizontal posture

Correct choice of suit for temperature conditions keeps diver warm and contributes extra buoyancy

Horizontal posture minimizes drag and hence kicking effort, as well as downward and upward depth fluctuations emptying your BC. Once you have mastered this, you will be able to float at any depth without effort.

TRIM AND WEIGHT DISTRIBUTION

The position of your weights and equipment has an important part to play in maintaining good "trim" (correct posture and balance) underwater. Distribution of weight is key in achieving a good horizontal attitude, which makes buoyancy control easier and helps you to propel yourself along with the minimum of drag. A streamlined profile also helps posture and ease of movement, which helps to reduce air consumption. Experiment with different weight systems and stowage points until you find a comfortable combination that helps you achieve the best position in the water. Some designs of BC allow you to stow weight at different points, not just on a belt. For example, some have special quick-release pouches that are designed to take moderate weight loads (*see p.59*). Always check that you are able to jettison the bulk of your weight load in case of emergency.

ACHIEVING PERFECT BUOYANCY
Thinking about buoyancy as a system of influences to be harmonized, rather than just weights and BC, will help you perfect the art of moving underwater.



BC filled with correct amount of air for depth and weight load

Additional weight to fine-tune weight distribution

Relaxed mental attitude helps maintain buoyancy; tense divers make too many corrective movements and find it hard to adopt a horizontal posture

Weights evenly spaced and held in place with retaining buckles

Console and octopus second stage clipped close to body to minimize drag and avoid damage or entanglement

Moving underwater

The duration of your dive is limited by your rate of air consumption, which in turn depends on how much energy you expend. Good finning technique, buoyancy control, and a streamlined profile will all make your movement underwater more energy-efficient.

EFFICIENT PROPULSION

Your movement through the water should be driven and controlled by your legs. If you watch experienced divers, you will notice that they use their arms very little, and move effortlessly through the water, saving energy, minimizing air consumption, and avoiding damage to reefs and the marine environment.

Swimming with fins should be an extremely efficient way of propelling yourself through the water, but many divers are let down by a poor finning technique. There are several different strokes you can use, but all should be carried out with strong, rhythmic movements, fully extending the leg (or legs) with each kick. Uncontrolled thrashing and incomplete kicks will simply waste energy. It is worth asking your buddy to give you feedback on your technique—even to photograph or film you. You may be surprised at the results.

Scuba diving is not a race, and the faster you go, the less you see. Learning to pace yourself and move at a leisurely speed will help you to relax, and a relaxed diver is an aware, efficient, and safe one.



MINIMIZING ARM USE
To practice with your legs only, cross your arms in front of you or let them hang by your side.



EFFORTLESS PROPULSION
The less strenuous your movements, the less energy and air you will use, and the longer your dive will be.

PROFILE AND BUOYANCY

To achieve the most streamlined (and therefore most energy-efficient) swimming position, you should be almost horizontal in the water. Your hips will be slightly lower than your upper body due to that area being weighted. During a dive, you should look forward and downward most of the time—raising your head too much will lift your upper body and make your profile less streamlined.

Carrying the correct amount of weight is important. Being overweighted will drag your hips and lower body downward. Swimming will then require greater effort due to your unnatural angle in the water, which will produce increased drag. You can improve your profile by repositioning the weights in your BC, or refining your weight requirements (*see pp.118–21*).

Achieving neutral buoyancy (*see pp.118–21*) is the key to maintaining a good dive profile with ease, and also increases your efficiency. If you are positively buoyant, you will be constantly swimming downward; if negatively buoyant, you will have to swim upward all the time or crawl along the bottom—all of which require more effort than horizontal, neutrally buoyant, swimming.

POOR PROFILE
Swimming with the wrong profile may mean that your fins kick up silt, impairing visibility.

TYPES OF KICKING STROKES

With the flutter kick (*below*), all fin movement takes place above the body's centerline, reducing the amount of water directed downwards. This can be useful when you wish to avoid stirring up sediment on the seafloor. The frog kick is also ideal for use where fine silt can ruin visibility if disturbed, because it directs thrust horizontally behind you. The swimmer kick is good for power, but uses up energy quickly. Most divers tend to drift slightly when using the flutter kick or the swimmer's kick, because one leg is slightly stronger than the other.


Fins force water behind them as they come together
Knees straighten with stroke

FROG KICK
Spread your legs and bring up your knees. Rotate your fins so that the bottoms of the blades face behind you. Bring the fins together in an arc, thrusting out behind.


Ankle relaxes as knee moves up to starting position
Power is in the downstroke

FLUTTER KICK
Bend the knees slightly, shorten the stroke of the kick, and keep the hips fairly static. The stroke ends when the knee is straight.


Straight legs make large up-and-down strokes

SWIMMER KICK
Lock your legs straight and kick from the hips with long strokes. This technique exploits the power in your thigh and hip muscles.

Exploring and navigating

Learning how to use instruments and natural features to find your way around underwater is important. Accurate navigation will help you to reach your planned exit point at the end of a dive, and will also help you find and explore features of interest, such as wrecks.

MAPPING THE SITE

It is easy to become disoriented in poor visibility, but good navigation skills will help you find your way, even when conditions are against you. Developing such skills will make you less dependent on other divers for your own safety—if you always rely on your buddy to lead the way, you could find yourself in trouble if you become separated.

On first entering the water, make mental notes of the surrounding features, such as unusual rocks, coral, or your position on a wreck site. As you progress through the dive, try to build up a map of the site in your mind. At every turning point, note nearby features and which direction you turned in relation to them.

FOLLOWING A REEF WALL
In clear conditions, a reef wall makes an easy navigational reference point. Try to remember distinctive features as you go along.

MENTALLY MAPPING THE DIVE SITE
Reef, rock, and seabed features, sunlight, and even shoals of fish can all help you to orient yourself at the dive site.

Look at the seabed geology, too: rocks often have features or show strata that make memorable visual markers. It may be helpful to jot notes down on a slate.

NATURAL NAVIGATION AIDS

A compass (*see pp.126–27*) gives the most accurate directional information, but there are also clues in nature. If the water is clear and shallow enough, or if there are any shadows cast by rocks, you can use the Sun as a directional reference. On a morning dive, for example, the Sun will be in the east. Take note of which way the current is running. (If you are diving close to slack water (*see pp.102–03*), at high or low tide, this may change by as much as 180° as the tide begins to turn.) Even if you cannot feel the current, you can find visual clues to its direction. Plankton, for example, drift along with the current, so shoals of fish station themselves facing into the current so that they can feed on them. Kelp fronds flow in the direction of the current. Exhaust bubbles will rise up toward the surface (unless you are in a down current).

READING SAND RIPPLES

Sand ripples run parallel to the shore, at 90 degrees to the path of incoming and outgoing tidal currents. Sand ripples get closer together nearer to shore, providing a useful reference point for underwater navigation. If the spacing of sand ripples underneath you appears to be getting narrower, you are swimming toward shallow water and a possible exit point.

Sand ripples on the seabed



FOLLOWING A REEF

On a basic reef dive, swim out with the reef wall on one side of your body and then return with the wall on your other side. When diving around a wreck, try to maintain either a clockwise or counter-clockwise motion, especially if the wreckage is fragmented. Keep the main part of the wreck to one side of your body during the dive, so that you return to your starting point after one circuit.

USING A HANDHELD COMPASS
In case you are separated for any reason, both you and your buddy should carry and be confident at using a magnetic compass.

USING A COMPASS

A compass has a circular body, often divided into 360-degree increments, and a needle that swivels to point to magnetic north. Many also have a "bezel"—an outer ring, also marked with increments and the points of the compass, that can be rotated independently to the body. This can be used in conjunction with the "direction of travel" arrow (known as the "lubber line"), which is marked on the compass body, to establish the direction you want to travel in relation to magnetic north. Point the lubber line in the direction in which you wish to travel, then turn the bezel so that its "north" mark matches the direction in which the needle is pointing. If you ensure that the needle always points to the north mark, as you move in the direction indicated by the lubber line you will maintain your intended direction. Digital compasses work in the same way, but display the information on an LCD.

A compass is a fairly basic device, but it is easy to use it incorrectly. If it is a wrist-mounted model, ensure that your



MEASURING DISTANCE
When navigating underwater, you can judge relative distances by counting how many fin strokes you have made in a given direction, or by timing your progress along a course.

wrist is held square to the direction of travel, and not at an angle. It is simpler to use a compass mounted on a console or a retractable lanyard, which can be held out straight in front of you. Use both compass readings and environmental observations, so that you can correct any inaccuracies in either method. Mark readings down on a slate as you go, and try to integrate these into your mental map of the dive site. In slack water, timing how long it takes to get from one point to the next gives you an idea of your position if you return along the same compass course. Combining this information with depth readings taken along the way will help you navigate with more accuracy.

LAYING A DISTANCE LINE

In low-visibility environments—such as murky temperate waters—it may be necessary to lay lines to aid navigation back to a convenient point. Lines can also be used to search an area: if you know the approximate position of a specific site, natural object, or artifact, you can use a line, in arcs of different lengths, to scan a large area of seabed efficiently.



1 **Find a solid anchor point** to attach the line to. Make a couple of turns around the object for extra security. Do not secure a line to jagged edges that will fray or cut through it.



2 **Secure the line** to the anchor point. If you have a reel and line you use regularly, fit a spring clip to the end of the line so that it can wrap around the anchor point and clip back on to itself.

3 **Unspool the line** as you explore, making sure that your buddy keeps clear to one side. The line should be tied off again wherever you change heading.

Ascent

All good things come to an end, and at some point your dive will be over. Ascending at the end of a dive should be carried out with great care. This is the part of the dive where decompression sickness (*see pp.142–43*) can develop, so your ascent must not be hurried.

WHEN TO ASCEND

Dives often end when you reach a prearranged time to surface, either to meet the boat cover or to account for changing tides. However, you may decide to ascend before this if the site proves uninteresting, or if you or your buddy are cold or tired. You may also be forced to ascend if you have only 725 psi (50 bar) left in your tank, if you are making a decompression dive (*see pp.130–31*) and reach the scheduled minimum volume of air in your tank, or if problems cause you to abort the dive.



SIGNALING TO ASCEND
To ask your buddy if they are ready to ascend, or to signal your intent, raise your thumb.

Before ascent, you and your buddy should signal the "thumbs up" to each other that you are both able and ready to ascend to the surface.

If possible, avoid making a "free ascent," with no visual reference to guide you. If you can follow a reef wall or a permanent mooring line, for example, this will give you a natural sense of your ascent rate, in addition to your computer readings, and can help avoid disorientation. Sometimes, though, it is not possible to ascend up a line or along a natural feature, and it can be helpful to deploy an delayed surface

MONITORING A DIVE COMPUTER
Dive computers (*see pp.66–67*) help the diver judge ascent rate. Some devices give audible warnings if safe limits are exceeded.

BUDDY PAIR ASCENDING A GUIDELINE
A buoyed line moored to a wreck or seabed feature offers one of the safest guides for an ascent, especially in a strong current.

marker buoy (DSMB; *see pp.130–31*)—this will give you a vertical reference and also signals your position at the surface. Ideally, both members of the buddy pair should carry a DSMB. If you are diving on a wreck or a site with a guideline, aim to get back to the line for your ascent—not only will boat cover know where to pick you up at the surface, but the line will assist you in making decompression stops and, in a current, can provide something to hold on to. If you do not manage to get back to the guideline, send up a DSMB.

MAKING YOUR ASCENT

To start your ascent, slowly breathe in or let a little air into your BC—this should cause you to rise up. Rise up next to, and ideally face-to-face with, your buddy so that you can check each other's rate of ascent and condition. As ascent continues, carefully monitor the amount of air in your BC (and drysuit if relevant)—the air will expand as the pressure decreases during your ascent, causing your rate of ascent to increase rapidly. Keep one hand on the BC exhaust hose in order to vent air from

FOLLOWING A SLOPE
Ascending next to a natural feature, such as a reef, offers a reassuring reference point.

MAKING A SAFETY STOP
Divers make a precautionary safety stop at 16 ft (5 m) to allow nitrogen to exit the body's tissues at a safe rate.

it as you ascend. You may also need to dump air from your drysuit. You can fin to assist your ascent, especially to gain momentum to begin with, but this will not be necessary if you are correctly weighted and positively buoyant. Keep breathing normally and do not hold your breath.

A conservative estimate of a safe rate of ascent is 50 ft (15 m) per minute (or slower) up to 16 ft (5 m) in depth. At this point many divers make a 3-minute safety stop. Whether you do or not, the last 16 ft (5 m) to the surface should take another full minute. If making a decompression dive, make all your scheduled safety stops and check with your buddy as you do so.

DEPLOYING AN INFLATABLE BUOY

Since ascent must be conducted in a controlled way, it is helpful to carry your own portable guideline—an inflatable buoy, or safety sausage. These highly visible tubes are launched using air from your second stage, and allow you to ascend up an attached line. Using them is a real skill, so seek training before your first attempt. Remember to reel the line in as you ascend, since slack line can get wrapped around your gear.



1 **Unfurl the buoy**, which should be attached to a reel. Unclip the reel from yourself, taking care not to drop it.



2 **Partially inflate** with a small burst of purged air from your octopus (*see p.61*) to stand the buoy upright.



3 **Hold the reel** in one hand, and with the other, hold your octopus valve under the buoy's inflation point.

4 **Launch the** buoy by purging a long blast of air into it with your octopus. Release the spool, holding tight to the reel, and the buoy will shoot upward.



5 **When the** spool stops spinning, start to ascend, reeling in the line as it slackens. Ascend at a safe pace: do not tug on the line to pull yourself up. During ascent, keep one hand ready to vent air from your BC if required.



6 **Await recovery** at the surface from your boat cover, which will have sighted the buoy at the start of your ascent. The buoy should be left in its inflated state until you have been recovered.

Surface skills and recovery

Once you and your buddy have completed your dive and are at the surface, you need to head back to shore or wait to be picked up by your boat cover. Always remember that the dive isn't over until you and your buddy are back on dry land or on your dive vessel!

EXITING ON TO THE SHORE

If completing a shore dive, you and your buddy should swim to the shore and find a safe, appropriate method of getting back on to dry land. If you are diving from a sandy beach, it is usually best to keep your fins on for as long as possible and walk backward up the beach until you are well out of the way of any swell. Removing your fins too early can lead to problems if you are swept off your feet or back out to sea, since you will have no propulsion.

If diving from a rocky shore, try to find an easy route back on to the rocks. Again, aim to keep your fins on for as long as possible. As you take off your gear, place it clear of any swell that could carry it back into the water.

EXITING ON TO A BEACH
Only remove your fins and walk forward when exiting the shallows of a calm sea, or once you are out of the way of any swell.

SIGNALING TO A BOAT
Your dive plan should ensure that your boat cover knows roughly when you will surface. If you need help quickly, shout and wave a signaling flag.

SIGNALING TO BOAT COVER

If you are diving from a boat, remain close to your buddy with your regulator in place and signal to your boat that you are OK and awaiting recovery. If there is a problem or emergency (*see p.141*) and you or your buddy require immediate recovery, wave to the boat, or draw extra attention to yourselves by blowing a whistle, shouting, or waving



BOARDING A BOAT
It is usually easiest to hand up any small items first, then hoist yourself up the ladder while still suited up.

a flag. As the boat approaches, move to it with caution, keeping your distance until you have a signal from the boat that it is in neutral and safe to approach.



DIVER GIVES "OK" SIGNAL
A standard signal for "I'm OK" at the surface is to put your hand on top of your head, forming a closed arc.

EXITING ON TO A BOAT OR RIB

To get into a rigid inflatable boat (RIB), you should first get a hold on the boat, either by a rope or by a handle on the side. Make sure your BC is inflated, hand your weight belt in first, and then slip out of your BC by unclipping one of its shoulder straps. Keep hold of it until someone from the boat can pull it in, along with your tank. You should then be able to kick with your fins and pull yourself up on to the RIB.

If returning to a hard boat, head for the ladder and hold on to the bottom. Take great care in a swell—the ladder will move in the water. The skipper or dive master will probably tell you whether to de-kit in the water or to enter the boat wearing your gear. You may be able to hand in your weight belt, BC and tank, but often it is easy enough to remove just your fins at the base of the ladder, hand them up to someone in the boat or hold on to them, and simply climb the ladder fully kitted up. If you feel you are not strong enough to do this, let someone on board know (preferably before you dive).

Once on the boat, be aware that others may be waiting in the water to get on board. Stand back to let others on, stow your gear quickly and neatly, and then offer assistance if it is needed.

Post-dive and debriefing

Your dive is over, and there is equipment to be cleaned and stowed, and records to write up while your dive is still fresh in your mind. Problems may have occurred during the dive, and questions may have arisen that need to be addressed. Now is the best time to do this.

PRACTICAL MATTERS

The first post-dive task is to wash your gear. You need to ensure that it is clean and free from mud or sand. If you have been diving in saltwater, then this also needs to be thoroughly rinsed off before the salt starts to corrode metal parts. Large dive boats and liveaboards usually have one facility for washing electronic equipment, such as computers and cameras, and another for your BC, regulator, and other gear. Rinse all items thoroughly to remove excess salt and sand, which can easily work itself into O-rings and regulators. There may also be facilities on board to dry your gear before stowing it away in a bag or box for your next dive. Make sure you follow instructions and do not leave gear lying around—this can lead to loss or damage, which may impede your next dive. If you are diving from a rigid inflatable boat (RIB) or small dive boat, you will need to find a water source back on land to rinse your gear, and then leave it to dry or stow it for transport.

ANALYZING THE DIVE

DIVER CLEANING GEAR
Rinsing, drying, checking, and stowing your gear should become a post-dive routine.

There will normally be some sort of debriefing with your dive leader after a dive. This gives you an opportunity to ask questions about the dive (for example, to identify fish species that you did not recognize, or discuss problems with gear, navigation, or currents). This is a time when you can learn about the site for a future dive and share with others ways to improve skills.

You should always fill in a log book after every dive, recording the depth, time, and conditions (including visibility, water temperature, and currents), as well as key features of the dive—details of a wreck, species encountered, equipment configuration, the type of suit you were wearing and the weights you used, and any problems you experienced. The log will be a valuable reference for future dives.

Finally, ensure that after every dive you are well rehydrated. You will have expended a high level of energy and will have lost fluids. Choose non-fizzy soft drinks or, ideally, water, to ensure that you rehydrate your body properly. Keep your energy levels up, especially if you are diving again soon, by having a good meal or eating a snack with a high energy content. If you are cold after a dive, get warm and dry—have a hot drink and get out of your wetsuit, if possible.

REACHING THE SHORE
Eager as you may be to talk about what you have seen, attend to your gear first.

LOOKING FORWARD

If you are planning to make more than one dive in the same day, consider beforehand what your surface interval will be between dives. Aim to do your deepest dive first, and shallower dives subsequently. Make sure you are in good shape to dive again—if you have become cold or fatigued on the first dive, it is better to spend time recovering than to dive again too soon.

DIVERS DEBRIEFING
Talking to other divers in the post-dive get-together will help broaden your knowledge of diving, and you may pick up some handy tips.

Problem solving

Diving is a safe sport if you follow the rules, avoid taking unnecessary risks, and always dive with a buddy. But that does not mean you will never encounter difficulties during a dive. Learning how to anticipate and solve problems is part of becoming an accomplished diver.

KNOW YOUR LIMITS

One of the most exciting things about diving is that no two dives are ever the same. Even consecutive dives on the same dive site, with the same buddy, will be different due to changes in currents, visibility, and your own attitude. Some days you will feel great, and everything will work out perfectly, and other days you might be tired, have a slight headache, perhaps, and there may be minor problems underwater that you have to deal with. In this unpredictable sport, you must be mentally and physically prepared for every eventuality.



REGULAR SIGNALING
Remain in close communication with your buddy at all times, and signal to each other regularly that you are OK.

To minimize the likelihood of problems and incidents occurring during a dive, do not dive without preparation in conditions with which you are unfamiliar. For example, if you have never dived in a cave, wreck, or under ice, make sure that you undergo the relevant training before attempting to do so. Diving in conditions for which you are unprepared will lead to anxiety, and sometimes to panic—and that is when problems often arise.

The buddy system is important for your safety, but as a diver you must ultimately take responsibility for your own welfare. If you feel uneasy during a dive, tell your buddy, and either change or abort the dive. Never let peer pressure push you beyond your limits and training, even if this means that your buddy's dive may be unsatisfactory. Buddy compatibility is important, since accidents can occur when two egos clash.

LOOKING OUT FOR YOUR BUDDY
Your buddy is your underwater lifeguard, but it is a two-way relationship—you also have to support your buddy when problems arise.

MENTAL AND PHYSICAL FITNESS
Confidence, a positive mental attitude, good health, and good levels of fitness are essential ingredients for a safe, successful dive.

ANTICIPATING EQUIPMENT PROBLEMS

It is rare that equipment fails during a dive, but you should nevertheless take great care when assembling, storing, and servicing your gear. After all, this is what keeps you alive underwater, so it is worth spending time and money on keeping it in perfect working order.

Consider "what if" situations ahead of a dive, and think through how you will deal with the failure of any element of your gear. Do you have a spare if your buddy is not close by? Your regulator should always have an octopus second stage (*see p.61*), to use as a backup in case your main second stage fails.

HANDLING INCIDENTS CALMLY

Many things can go wrong on a dive, but most are minor issues that can be solved without aborting the dive. Even serious problems can be dealt with if you remain focused and positive. Be persistent, and say "no" to failure. When you become aware of a problem, stop, think, breathe, and then act. Whatever happens, do not panic—remember that your buddy is there to help. Make sure you are there for your buddy, too, and be quick to reassure or assist them if they appear disoriented or anxious.

THE INCIDENT PIT

Minor problems can escalate into major ones if you do not stay calm and deal with them methodically. Imagine that you lose your regulator while trying to ease cramp in your foot, and then fumble as you try to retrieve it. If you panic, you may inhale water, choke, and become disorientated. This type of scenario is known as the "incident pit"—stay out of it by thinking clearly and acting methodically.

TROUBLE-SHOOTING

The equipment problems you will encounter most commonly will involve your regulator, mask, and inflator hose.

If your regulator comes away from your mouth and you cannot retrieve it, reach for your octopus second stage (*see p.61*) and breathe from it. If your octopus is not accessible for any reason, signal to your buddy, who should offer you their own octopus to use. Take a few breaths from this to calm down and, with your buddy's help, locate your main regulator and replace it.

Should air start to flow uncontrollably from your regulator, take the regulator out of your mouth and push the purge button, which should clear any grit that may be jamming the valve open. If this does not work, switch to your octopus second stage and signal to your buddy that your air supply is running down more quickly than normal. Monitor your air supply carefully, and ascend immediately with your buddy. Note that in very cold fresh water, freezing up of the regulator will probably be the cause of any free-flow, in which case purging will not help. In this scenario, you may need to breathe from your buddy's octopus while performing a shared-air ascent together (*see p.140*).

RETRIEVING LOST REGULATOR
A lost regulator is usually easy to retrieve, but if your buddy is finding this difficult, go to their aid and, if necessary, offer them your octopus.

CALMING YOUR BUDDY
Reassuring physical contact can help to calm a disoriented buddy and prevent panic from setting in.

SECURING A BUDDY'S LOOSE TANK
Some problems are difficult to solve alone, and you should not hesitate to alert your buddy if you need assistance.

REMOVING YOUR WEIGHT BELT
You must be competent at removing your weight belt underwater, in case you need to adjust your weights or if your belt becomes snagged.

SOLVING MASK AND HOSE ISSUES

If your mask is dislodged or starts to fill with water, simply clear it in the normal way. Lean your head back, press in the upper edge of the mask, and breathe out through your nose. The air bubbles you exhale will clear any excess water in your mask. At depth, this can seem daunting, so be prepared to practice this procedure until you are comfortable with it and can execute it confidently.

On occasion, you may find that the inflator hose for your BC or drysuit fails to work. This is usually caused by grit becoming lodged in the valve. If necessary, BCs can be inflated orally, both underwater or at the surface.



LOCATING A LOST BUDDY

During a dive, you may find you lose sight of your buddy, especially in low visibility conditions. The correct procedure is to look around for a minute or two, and then surface independently. If your buddy is using a surface marker buoy (*see p.74*), it will indicate their position. Having located it, you can then follow the line down to find your buddy again.

If neither buddy nor buoy is visible, signal to any boat cover to recover you; alert the coastguard if your buddy has not appeared after a few minutes. In all probability, your buddy will surface shortly after you do. You can then decide whether or not to resume the dive.

FREE AND BUOYANT ASCENTS

If you run out of air, locate your buddy and follow the procedure below. If you cannot find your buddy, you will need to make a rapid "free ascent" by finning to the surface. This can be aided by ditching your weights, but be ready for a sudden increase in buoyancy. Breathe out slowly during ascent to prevent lung expansion injury. If, however, you have a little air left, you can make a more controlled "buoyant ascent." Let some air into your BC to kick-start your ascent, and tilt your head back to watch for the surface. Again, breathe out during the ascent. Control your ascent rate by venting air from the BC, but not so much that you lose buoyancy. Do not rise any faster than

---

OUT-OF-AIR PROCEDURE WITH BUDDY

If you have not kept track of your air consumption and find that you are out of air, locate your buddy and ascend using their octopus or pony bottle. If no alternate air source is available, then buddy breathe. This involves both divers using the same regulator, with each diver taking two breaths before passing it to their buddy. This is a complex procedure, however, that needs to be practiced if it is to succeed in a real-life crisis.



1 **Signal to your buddy** that you are out of air by making a chopping motion at your neck with the flat of your hand.



2 **Your buddy will offer** you their octopus second stage, or, if they have one, a separate regulator attached to a pony bottle.



3 **When your buddy is** sure that you are OK and your breathing has settled, you should lock arms and ascend to the surface.

4 **Hold on to one another** as you rise to the surface. Make any decompression stops as you would do during a normal ascent.

your exhaled bubbles. At the surface, signal to boat cover immediately. If there is no boat, swim to the shore. Your buddy will need to be found and, as you have ascended without safety stops, you will need to be monitored for DCS (*see p.142*).

MAKING EMERGENCY LIFTS

If your buddy is unconscious or injured, keep their regulator in their mouth and perform a buoyant lift to get them to the surface. This means holding on to your buddy's harness as you ascend, using their BC to adjust buoyancy for both of you. Alert any boat cover once at the surface. If your buddy is not breathing, artificial ventilation (AV) may be needed until medical help arrives. If there is no cover, or if you are close to shore, you may decide to tow your buddy to safety. Both towing and AV require special training; if your dive training did not cover them, a lifesaving course is recommended.

OVERCOMING PANIC

If you feel panic coming on, alert your buddy, stop moving, and steady your breathing. If your buddy panics, reassure them with hand signals but observe them from a safe distance, since a flailing arm can knock your regulator from your mouth or injure you. When they have calmed down, hold their hand or arm, make sure their regulator stays in place, and remain close until normal breathing resumes.



SIGNALING FOR HELP
Supporting your buddy at the surface, wave one arm in a wide arc and shout to alert boat cover.

Decompression sickness

If a diver ascends too quickly, the rapid pressure change causes bubbles of nitrogen to form in tissues and blood vessels *(see pp.100–01)*, resulting in decompression sickness (DCS). This condition must be watched closely and treated quickly, since in extreme cases it is fatal.

DCS SYMPTOMS

Severe DCS may cause impaired vision and balance, convulsions, and even unconsciousness. Nitrogen bubbles can form under the skin, or become trapped in capillaries and restrict the blood supply to the lungs, slowing breathing, lowering blood pressure, and causing shock. If a bubble enters the brain or spinal cord, it can lead to paralysis or even death. Symptoms usually appear between one and six hours after surfacing, but occasionally do not manifest themselves until 24 hours later. They start with minor aches in joints, rashes, and itching. These will disappear after a few hours in mild DCS, but with severe DCS they will be precursors of serious complications. At the first sign of symptoms, request emergency medical attention (from the coast guard, if you are at sea) and give basic first aid: supply the patient with 100 percent oxygen; keep them warm and still (lying down if possible); provide nonalcoholic fluids (ideally sports or rehydrating drinks); and apply pressure to joints to alleviate pain. The patient should be referred for medical attention and may need to be treated in a recompression chamber.

If so, provide those in charge of the chamber with the diver's symptoms and details of the dive. In the chamber, the pressure is raised until it causes gas bubbles in the diver's tissues and blood to shrink. The diver is decompressed under controlled conditions, allowing any residual nitrogen to dissipate safely.

EMERGENCY OXYGEN
It is vital that the dive boats carry an oxygen administration kit in case of emergencies.

LOOKING FOR SYMPTOMS
Skin rashes and joint pains may be precursors of more serious problems.

DCS AT SEA
Record the symptoms, give first aid, and get to shore if feasible—or wait for the coast guard to arrive.

Hand signals

Good communication with your dive buddy is important, not just in an emergency, but also to monitor each other's progress, share underwater experiences, and agree when to end the dive. The most effective method of communication is to use hand signals.

USING HAND SIGNALS

Verbal communication is not an option underwater (*see p.92*) unless you are wearing a full-face mask, but most messages can be conveyed using a combination of hand signals and drawings on a slate. Using hand signals will allow you to exchange information with your dive buddy and even ask each other questions underwater. They can also be reassuring.

Signal to your buddy regularly during a dive, as this will ensure that you remain in close contact and can easily notify each other of any problems that may develop. Repeat any sign that is not clear to your buddy, and acknowledge every signal that he or she makes with an "OK" to show you understand. If your buddy is slow to respond to a signal, check that they are OK. If you are diving at depth, sluggish responses may indicate the onset of nitrogen narcosis (*see pp.100–01*), which impairs reaction times and mental acuity.

Signals are not just limited to showing each other how much air you have left or highlighting problems. They can also be used to inform your buddy of interesting things you have seen, or to alert them to something you are both looking for, such as a particular marine organism. There are numerous signals for marine animals, and you can develop your own within your buddy pair. A common example is the use of a straight, upright hand (representing a fin) on top of your head, meaning "I've seen a shark." Signals for animals like turtles and rays can be readily improvised.



QUALIFYING THE SIGNAL
To make it clear that a signal refers specifically to yourself—for example, "watch me"—point to yourself first.

COMMON HAND SIGNALS

There are a number of standard hand signals that are essential to all divers, and you can also improvise new signals with friends. Always review signals at the start of a dive, especially if you are diving with a new buddy. Give signals to your buddy slowly and clearly, to ensure that they are understood. Use combinations of signals to convey messages more precisely (for example, something is wrong/I can't clear my ears). Below are some of the most important and common diving signals.



OK/Are you OK?
Form an O with thumb and index finger. Point the other fingers up.



Something is wrong
Tilt the flat of your hand from side to side, palm down.



Up/Let's ascend
Point thumb straight upward with fingers clenched in a fist.



Down/Let's go down
Point thumb downward with fingers clenched in a fist.



1,500 psi (100 bar) left
Form T-shape with hands to indicate 1,500 psi remaining.



750 psi (50 bar) left
Make a fist, with palm outward, to indicate 750 psi remaining.



I am out of air
Make a horizontal chopping motion across base of neck.



Stop
Present flat of hand, palm outward, to halt buddy or other divers.



Slow down
Move palms slowly downward together (pivoting at elbows).



Stay/Move together
Move index fingers together, until touching side by side.



Stay at this depth
Hold both hands horizontally and move one over the other.



Watch/Look
Point at your eyes, then at subject of interest, or self, or another diver.



I am cold
Hug yourself with both arms crossed to indicate chill.



I can't clear my ears
Point at ear to indicate you are having difficulty equalizing.



Feeling breathless
If you are feeling out of breath and need to rest for a moment, you should use the flat of your hand to mimic your chest rising and falling.

Developing your skills

With any skilled pastime, it is important to keep your technique sharp. Many divers only dive once a year (or even less frequently), and it is easy to forget even basic skills during your time off from diving. Honing your skills in sheltered water is a good way to stay proficient.

PERFECTING BUOYANCY

Beginners, occasional divers, and even those who dive regularly will benefit from practicing key skills in a pool or sheltered water. Buoyancy is the most fundamental diving skill of all, so it is a good place to start when reviewing your technique. Refamiliarize yourself with buoyancy control with "fin pivots," using inhalations and exhalations to make the upper part of your body rise and fall. Keep your fins on the bottom and your legs apart. They will act as the "hinge" of your upward and downward movements. The value of this exercise is that it trains you to use breathing to adjust your buoyancy, rather than controlling it only with your BC. Also, try swimming through a hoop with your arms folded—this will test your buoyancy control and give you an idea of the space you can squeeze through with your equipment on.



1 **To practice fin pivots,** breathe in gently and feel your upper body rise, keeping your fin tips on the floor. Stop at a 45° angle to the bottom.



2 **Slowly release the air** in your lungs until your body begins falling. Then, before you hit the bottom, begin inhaling again.

CONFIDENCE-BUILDING EXERCISES

Mask clearing is one of the most basic, yet important, skills in diving. Building coordination and confidence by removing and replacing your mask, and even performing tasks without it, will improve your diving. It will also prepare you for minor upsets like your mask being accidentally dislodged. Begin building up your confidence slowly by removing and replacing your mask in shallow water, before repeating the exercise in deeper water. Repeat while swimming, and then try it with your regulator removed. You can also try swapping masks with your buddy. This is simply a variation on the solo exercises but also helps you to develop useful cooperative skills.

Giving yourself other handicaps can also help improve your confidence underwater. Try swimming with just one fin, for example. Losing a fin can happen on an open-water dive, but if you are already prepared, you will be able to cope with the situation calmly and effectively. Practice all of these exercises in a pool or sheltered water.

REDUCED VISIBILITY
Most divers feel uncomfortable swimming with their mask removed, but with practice, you will become confident performing tasks without it.



1 **To exchange masks**, kneel on the bottom facing each other. Give each other the “OK” signal, then remove your masks, while continuing to breathe normally.



2 **Swap masks** with your partner. It is much easier to keep your eyes open throughout the exchange, but perfecting this by touch, with your eyes closed, is a very useful exercise.



3 **Don each other’s masks**, and blow them clear (*see p.139*). Ignore any urge you feel to hurry when putting the mask on. In particular, make sure the strap is not twisted.



4 **Adjust the mask** for comfort, then open your eyes and signal OK to indicate a successful swap. The masks can then be swapped back again for further practice.

VARYING THE ROUTINE

Skills exercises don’t have to be simple drills. Introducing an element of fun or setting an objective can motivate you to train for longer. Games for the pool or sheltered water include “hide the mask,” which forces you to navigate and search without your mask; or you can practice breath control by performing simple exercises without breathing apparatus, such as retrieving objects from the bottom, or swimming through a series of hoops, extending the course as your stamina improves.

1 **“Hide the mask”** begins with an “OK” signal from the seeker, once the diver who is going to hide the mask has removed it.

2 **The seeker closes his eyes** while the hider finds a corner of the pool to put the mask in, and returns to signal the seeker to start searching.

3 **The seeker opens his eyes** and starts to methodically search the pool bottom until the mask is found and replaced.

REMOVING AND REPLACING GEAR

Familiarity with your basic gear is a vital skill. One exercise that helps to foster confidence in this area is to remove your scuba unit—that is, your BC and breathing apparatus, all fully connected—and put it back on underwater, keeping your regulator in your mouth throughout. This exercise should be carried out at the bottom of a pool or in sheltered water, and if you are a beginner or haven’t tried this before, it may be useful to have an instructor present who can guide you through the process. Start by undoing all fastening clips on the front of your BC and pull your left arm out of it first (even if you are left-handed), using your right arm to pull it around to your right. The BC jacket should now be in front of you, between you and the tank. Keep the hose for your regulator second stage between your arms (otherwise it may get caught under your shoulder strap when you put the unit back on). Then put the scuba unit back on by reversing the operation.

For an extra challenge, once you have removed your BC, try removing your regulator from your mouth and swimming away to a distance of about 30 ft (10 m), before returning and putting your gear back on again.

Alternatively, try entering the water without your gear, then putting it on while treading water, keeping your head above the surface. This is a much more difficult exercise, and should only be carried out under the guidance of an instructor.



1 **To take off** your scuba unit underwater, undo all clips and take your left arm out of the BC, gripping the jacket with your right hand. Breathe normally through your regulator.



2 **Pull the whole unit around** in front of you. Keep a firm grip on your BC to avoid losing hold of the scuba unit.

3 **To put gear back on,** reverse the operation, making sure all clips and fastenings are reconnected.

Dive fitness

As a diver, you are reliant on your body as well as your gear for a safe and enjoyable dive—so make sure both are well maintained. Diving regularly helps keep you in shape, but it is important to maintain your fitness levels if you go for long periods without diving.

HOW FITNESS AFFECTS DIVING

Staying in shape reduces some of the risks associated with diving, and makes it more enjoyable. Having healthy lungs and an efficient circulatory system means you will use less air, so dives last longer. A good level of cardiovascular fitness will also help to prevent panic attacks, which can be triggered by a buildup of carbon dioxide in the blood. A fit body will expel this by-product of respiration more efficiently, reducing that risk. General strength is required for lifting equipment and other incidental tasks. Maintaining a healthy weight for your size is also advisable. When you dive, nitrogen builds up in the tissues of your body with each intake of breath, and fat retains nitrogen longer than all other tissue types. Therefore, if you are overweight and breathe rapidly because you are out of shape, you expose yourself to an increased risk of DCS (*see pp.142–43*).

Weight loss and gain can also alter your buoyancy. Fat is inherently buoyant, so if you have put on or lost a lot of weight since your last dive, you must adjust how much lead weight you carry as ballast (*see pp.118–21*).

TALKING THINGS THROUGH
If you have any injuries or physically weak areas, let those diving with you know before you dive. Don't be afraid to ask for assistance if this will help prevent injury.

DEVELOPING A FITNESS REGIMEN

There is no quick fix for getting and staying fit. Aim to exercise regularly, tailoring your routine to strengthen the muscles you use most during diving: those of your back, legs, shoulders, and arms. If you do not already exercise regularly, seek medical advice before embarking on a fitness routine. Start gently with easy exercises, and build up slowly. A routine based on the exercises overleaf could start, for example, with ten repetitions of each, building up to 50, three times a week. You should also aim to undertake regular cardiovascular exercise (such as walking or cycling), for 30 minutes two or three times a week to improve your general fitness and respiratory health.

Whatever exercise routine you decide to adopt, try to incorporate it into your normal daily routine wherever possible. A walk to work every day does more good than a monthly gym session. Never exercise after diving. This is a time when it is important not to do any strenuous activities—there is still residual nitrogen in your body, and this may form bubbles if you exercise too hard. Do some gentle stretches and take it easy for the rest of the day. Avoid hot baths or showers after diving, since these can also raise your vulnerability to DCS.

GOING AGAINST THE FLOW
Finning into strong currents places demands on your leg muscles and lungs.

PROTECT YOUR BACK

Be very careful when carrying and loading heavy equipment. A poor lifting technique can result in pulled muscles, and possibly long-term back problems. A back injury can spoil a trip, but diving with a weak back can also be a safety risk: surface maneuvers, climbing onto boats, and exiting surf, for example, are all compromised by weakness in this area. If your lower back is vulnerable, consider transferring your weights from a belt to a harness (*see p.70*).

Loading dive equipment

WARMING UP

Always warm up and stretch—especially your thighs, calves, and upper and lower back—before exercising, and spend a few minutes gently stretching and cooling down afterward. Many sporting injuries are caused by failure to warm up properly, so treat it as an important part of your fitness routine.

ARM AND LEG EXERCISES

Basic squats build up strength in your legs. Standing upright with your feet shoulder-width apart and your knees soft, place your hands on your hips and shift the weight back into your heels. Keeping your head and chest pointing forward and your back straight, bend at the hip and knees, as if you were sitting down onto a chair. Keep your heels on the floor; you should be able to move your toes, since all your weight is on your heels. Straighten and repeat.

Lunges are a more advanced exercise for legs. Stand upright with one foot a good stride in front of the other, with your hips parallel and your toes forward. Your back heel should be off the ground and your front foot flat on the floor. Both knees should be bent and your back straight. Drop your body weight toward the floor until your front knee is bent at a 90° angle. You may have to tilt your pelvis forward to get this position right. Rise up and repeat.

BASIC PUSH-UP
The push-up is a great all-around exercise for the upper body and arms. Beginners can start with their knees resting on the ground.

Biceps curls strengthen the biceps—muscles in the upper arms that are used whenever you lift anything. Using hand weights or a weighted bar, stand upright,



HEALTHY LUNGS
Cardiovascular training builds up lung capacity, making snorkeling feel even more effortless.



LUNGE EXERCISE
Practicing lunges in front of a mirror will help you to get the position of your front leg right: knee directly over foot, bent to a right angle.



ABDOMINAL CRUNCH
Always keep your lower back flat on the floor and never arched. For a harder workout, aim your right elbow to your left knee, and vice versa.

with your back straight and knees slightly soft, and hold the weights in your hands with your palms facing upward. Without rocking or moving your shoulders, bend the arms toward the chest and then lower, taking care not to lock the elbows.

EXERCISING YOUR TORSO

Push-ups strengthen your shoulders, upper body, and core muscles. Lying on your front, bend your knees, curl your toes under your feet, and place your hands shoulder-width apart below your shoulders. Press your body weight up and down from this position. Keep your back straight at all times and your elbows pointing out to the sides.

Crunches strengthen abdominal muscles, which will help protect your lower back. Lying on your back, bend your knees slightly and place the soles of your feet on the floor. Place your fingertips behind your ears and lift your upper torso and shoulders off the floor. Hold this for three to five seconds while looking forward, then lower and repeat.

HYDRATION AND NUTRITION

During a dive, you can burn as much energy as you would playing an aerobic sport, such as squash or badminton. The precise amount will vary according to your fitness, the temperature of the water, and any prevailing currents. But while it is tempting to stoke up on a big fried breakfast in preparation for a day's diving, better food choices before a dive are complex carbohydrates, which will keep you feeling fuller for longer and provide a steady supply of blood sugar to maximize energy levels while you are diving. Some foods may make you feel uncomfortable on a dive—commonly, greasy or hot and spicy dishes—so these are best avoided.

After a dive, you need to replace the energy you have burned with foods that release energy into your blood relatively quickly, such as refined carbohydrates. Have something to eat within an hour of surfacing, if possible. Energy-replacement drinks can be a quick fix, but avoid those with a high caffeine content.

GOOD DIVING FOODS
Whole-wheat bread, legumes, and unrefined cereals and pasta release energy slowly during a dive. Dried fruit and nuts make good snacks.

Above all, the most important thing is to remain well hydrated before and after a dive. Your physical performance will be reduced if you become even mildly dehydrated, and this is a big issue if you are diving in warm waters where the outside temperature is also high. Aim to drink at least 2 quarts (liters) of water during the course of the day (more if it is hot). This will help to reduce muscle cramps and fatigue, and also helps decrease the risk of DCS.

AVOIDING PROBLEMS

It is important to get plenty of sleep before and after diving, to give your body a chance to recharge. Diving is physically demanding, and if you are run down, you are more susceptible to catching colds. If you do have a cough or a cold, you should not dive, because some symptoms of respiratory illness can prevent you from being able to equalize and may increase your vulnerability to DCS (*see pp.100–01*). Avoid taking decongestants, since these can impair your performance underwater.



STAYING HYDRATED
Make sure you drink plenty of still water to maintain good hydration. Tea, coffee, and carbonated drinks are no substitute.

FOODS TO EAT WHEN DIVING

The following list gives examples of the kinds of foods it is good to include in meals and snacks before and after a dive:

BEFORE A DIVE Multigrain, whole-wheat, or rye bread; whole-wheat pasta; sweet potatoes; brown rice; oatmeal; bran-based cereals; legumes and nuts; beans; leafy vegetables; and plain yogurt.

AFTER A DIVE Pasta and rice (ideally in a salad or low-fat sauce); potatoes; fresh fruit; white bread or bagels.

So can alcoholic drinks, which are best avoided the night before a dive because they can also contribute to dehydration. Divers sometimes experience minor ear infections, especially after days of continuous diving or if diving in slightly polluted waters. There are various ways of avoiding ear problems, including rinsing the ears with fresh water after every dive, or using an alcohol-based fluid designed for swimmer's ear.

Lastly, you should have a regular dive medical to check that you are in good enough shape to dive. If, between medicals, there have been any changes in your health since you last dived, then it is always best to have a checkup.

AFTER A DIVE
It's tempting to head for the bar after a day's diving, but have something to eat, too. Even standing still in cold water burns calories.

Going diving

Introduction

Becoming a qualified diver is a tremendously exciting experience, but the range of choices facing you post-qualification can be daunting. The joy of diving is that within one sport lies a host of different specialties, all requiring different skills, knowledge, and planning techniques.

RECREATIONAL DIVING

Upon qualification, the world of diving opens up to you. Whether you become a casual resort diver or an advanced technical diver with a liking for the more extreme elements of the sport, only time and experience will tell.

The broad spectrum of recreational diving encompasses many different environments and experiences, including reefs, caves and caverns, wreck diving, ice diving, freshwater diving, and night diving. There are also various specialty activities in which you can participate, such as filming and photography, wildlife and conservation diving, underwater archaeology, and free diving (diving without an air supply). The majority of divers find that they derive most enjoyment from sampling a range of different environments and activities, rather than limiting themselves to one specific aspect of diving.

BEACH BRIEFING
Becoming confident enough to conduct your own dives without a guide or instructor gives you greater freedom. Always plan and brief dives thoroughly before entering the water.

Many new divers aim to acquire further specializations, pins, and qualifications from the moment they pass their initial training course. This urge, while understandable, should be tempered by the need to gain general diving experience. There is no substitute for time spent in the water—what was once intimidating becomes familiar, helpful routines start to emerge, skills and safety consciousness improve, and knowledge increases. You will also feel more confident and comfortable in the water as you learn to tailor your equipment to your own needs.

Only when you have served your “apprenticeship” by gaining experience of different environments and diving skills should you make any decisions about future specializations. Without putting in the hours underwater, you will find further training and courses more difficult, no matter how well structured and delivered they are. In addition, the more experience you have, the more aware you will be of your own likes, dislikes, and aptitudes, allowing you to make more informed choices for the future direction of your diving.



Fortunately, gaining general diving experience is relatively easy, with dive groups and clubs springing up in abundance to meet the sport's growing appeal. Furthermore, dive travel is so well established that almost any region of the world is now accessible, and opportunities to dive exist in virtually every coastal resort around the world. A whole range of diving encounters are available—from a casual beach dive through to full-blown expeditions—all easy to arrange via the Internet or through dedicated dive travel agencies.

PLOTTING YOUR FUTURE COURSE
The more experience you gain, the better informed you will be when deciding whether or not to pursue a particular aspect of diving.

PROFESSIONAL DIVING

The enjoyment of diving leads some people to consider a full-time career in which diving plays an essential part. Diving professionals range from recreational instructors and dive masters, whose main role is to introduce others to diving, through to military experts, commercial specialists, scientific divers, fishermen, and underwater cameramen and photographers.

Further skills are always needed to succeed in your chosen career—an underwater filmmaker, for example, must be an accomplished camera operator as well as a superb diver, and an instructor needs good communication and teaching skills, in addition to first-class abilities in the water.

Professional diving can offer excellent rewards, both personal and financial, but they tend to be well earned. Professionals must dive in all conditions and at all times, and the work is often arduous and sometimes dangerous.

PREPARING FOR AN ICE DIVE
Diving under ice is thrilling, but it is not for beginners. The hazards of enclosed surroundings and extreme cold mean that special training is required.



Identifying your aims

Time spent researching a dive is time well spent. Not only does it help you to unearth new attractions and clarify the aims of the dive, but it is also likely to heighten anticipation, enhance safety, and maximize the pleasure and interest you derive from the trip.

ASSESSING AIMS

The nature of dive research will vary from trip to trip, but certain core issues should always be taken into consideration.

Identifying the divers is obviously one of the first items to be addressed. Diving is not, as a rule, an individual sport, so of necessity others will be involved in the dive itself. The experience and qualifications of divers within a group will vary, and what may be a comfortable dive for one person may be extreme for another. Time spent discussing qualifications and experience levels may well prove invaluable in establishing the ideal dive location and activity for the group as a whole.

Along with making sure that you have the right mix of divers, you will need to ensure that their aims are not likely to conflict. Imagine the scenario, for example, of an avid photographer preparing to take an

BEGINNING RESEARCH
Use magazines, books, and maps to highlight basic issues that you can then investigate in depth on the Internet.



TROPICAL CONSIDERATIONS
When planning tropical dives, consider the effect of local weather patterns. Runoff from tropical islands in the wet season, for example, may impair visibility.

DIVING WEBSITE
The Internet is an invaluable research resource, allowing you to access the opinions and advice of authoritative dive organizations.

award-winning image of a sunken ship, when an impatient wreck enthusiast swims in front of the camera lens and ruins the shot. Establishing the main aim of the dive at the outset, or even allocating buddy teams with the same interests, should prevent such problems.

When diving with a local operator, try to check out their credentials. In many parts of the world there are associations set up by groups of respectable operators to govern the local dive industry. Failing that, many tourist boards and even government agencies require dive operators to register—it is always worth getting an independent view of your potential host from these organizations.

LOCATION AND TIME

Conditions can vary greatly along even the most bland section of coastline or within the most innocuous-looking body of water. Choosing an exact site in advance has the benefit of allowing very specific research into local issues. Key questions to be answered include: what are the hazards involved? Where are the established entry and exit points? What are the divers likely to encounter during the dive? What is the tidal range? What are the prevailing currents?

The timing of the trip is also important. Tides, for example, may affect not only visibility, but also the marine life present, as well as entry and exit considerations. Marine life will also be influenced by seasonal variations, as will water temperatures. Furthermore, a different range of marine animals may well be present at night than during the day, while boat traffic and use of the area for other watersports will vary throughout the day and the week. Diving at the wrong time can make the event a disappointing experience.

Safety is the most important area of your research. You will need to assess the conditions you are likely to encounter—waves, currents, depth, temperature—and the facilities available to you should an accident occur. You should not show up at a dive site unless you know the exact location of the nearest hospital, recompression chamber, and casualty evacuation facilities. Knowing how to contact these agencies in an emergency is also crucial—researching phone numbers in the comfort of your own home is infinitely better than trying to do it on a rocking boat while caring for an injured diver.

UNDER THE ICE
The possibilities for thrilling diving trips around the world are almost endless, limited only by time, budget, and imagination.

Planning a trip

Armed with the fruits of your research, you will have a clear idea of where you want to dive, when you want to go, who you will be diving with, and what you will see when you get there. The final task before your departure is to plan the trip in as much detail as possible.

REALISTIC TIMETABLING

Most trips revolve around a key moment in time—the instant when the divers enter the water. This is often determined by a certain phase in the tide when the diving is most favorable, or by the desire to dive at a specific time of the day or night, such as when the Sun is high for photography, or in the gathering dusk when the reef is at its most active. A realistic, workable timetable is thus vital to achieve such time-specific goals.

Devising a timetable, such as the chart below, by working backward from the moment you aim to enter the water is the best way to plan your diving day. This method is used by many divers to ensure that their diving is as stress-free and as enjoyable as possible.

PACKING YOUR EQUIPMENT Checklists and routines will help to ensure that all your gear makes it to the dive site.

PRESSURE TEST

Before you start packing your equipment for a dive, carry out a pressure test. This involves rigging the gear to a tank, and ensuring that the seals and regulators are all functioning as they ought to be. This is also a useful means of ensuring that your tank is full prior to departing for the dive site. There is no more sickening sensation than journeying to a dive site, looking out over perfect conditions, assembling your dive gear, and turning on the air to be greeted by a cacophony of hissing regulators and seals—or, indeed, the tank itself being empty.

REVERSE TIMETABLING

A diver knows they must enter the water at 3:00 pm to dive during slack water between the tides. They work backward from this to calculate a realistic departure hour, building in a contingency to ensure arrival at the dive site in good time.

Activity	Time Taken	Actual time
Entering the water		3:00 pm
Suiting up and buddy checks	25 min	2:35 pm
Site inspection and briefing	40 min	1:55 pm
Arrival and parking	10 min	1:45 pm
Driving to site	1 hour	12:45 pm
Loading car	30 min	12:15 pm
Checking and packing dive gear	30 min	11:45 am
Contingency time	30 min	11:15 am



CAVE DIVING
For more complicated trips, such as cave dives, special equipment may be necessary, and this must be factored into your planning.

PACKING WITH CARE

The greatest cause of the postponement or cancellation of dives is forgetting pieces of gear. A fool-proof method of guaranteeing that you pack all of your equipment is to load your gear into your dive bag at home in the order that you will be putting it on at the dive site. Visualizing your arrival at the site and suiting up will lead you to load your dive bag in the following sequence: suit, boots, knife, weight belt, tank, BC, regulator, computer, hood, mask, snorkel, fins, gloves, and finally any ancillary items (safety sausage or DSMB, flashlight, slate, and so on).

An alternative packing technique is to run through a checklist from head to toe, and again pack your gear in that order. The list then runs: hood, mask, snorkel, suit, regulator, BC, tank, computer, gloves, weight belt, knife, boots, fins.

There are innumerable ways of trying to ensure that no item of equipment is forgotten, but the most effective are those that are convenient, quickly become a habit, and take little time.

DIVERS ENTERING THE WATER
A realistic timetable will ensure that suiting up and briefing on site is not rushed, and that you do not miss your window of opportunity with the tide.



Site-specific planning

Pre-dive research is important, but there is no substitute for a thorough assessment of the site on the day of the dive. This may highlight issues not raised by your research, and allow you to make adjustments to accommodate changes in conditions before the dive starts.

FINALIZING YOUR PLAN

Once you know when and where you are going to dive, you must devise a practical plan for each of the dives you mean to conduct on the day. Whether you are planning for just yourself and a friend, or for a larger group, always take local conditions into account before settling on a final dive plan.

You must address a number of key points in your dive plan. First, it should broadly define the aim of the dive, the dive's entrance and exit points, and its general route, as well as describing an alternative exit in case the main choice is inaccessible. It should also define the dive's maximum depth and time, as well as decompression restrictions, and should specify the minimum reserve of air that divers must surface with at the conclusion of the dive.

Depending on the aim of the dive and the experience of the group, special signals may be required. It is imperative to select diver recall systems—the signals or sounds that will be used to indicate that the dive should be aborted. Your plans for the dive should also identify any potential hazards that may be encountered. If an incident occurs, what procedures should be followed? Define what action to take if divers become separated—in murky waters, this is one of the most common reasons for dives being aborted. Make sure that the divers you intend to pair together as buddies share similar interests or levels of experience, so that there are no conflicts of interest during the dive.

Assess local conditions and examine weather reports; worsening weather conditions might dictate a move to a more sheltered site nearby, or rule out the use of a boat. Finally, ensure that the designated shore marshal or dive supervisor understands their duties, including recording tank pressures and the times that divers enter the water, and responding to incidents. Provide them with contact details of local agencies to be informed in the event of an emergency.

INSPECTING THE DIVE SITE
Resist the temptation to enter the water as quickly as possible. Assess the conditions and inspect the site, noting the dive's entry and exit points.

UNLOADING THE GEAR
Even if you feel sure that every item of gear was packed before the trip, double-check on site that you have everything you need.



OUTLINING THE PLAN
If it helps, you can always draw simple sand maps to clarify the route to the other divers.

THE DIVE BRIEFING

The final task is to brief the entire dive crew. The briefing, which should ideally take place overlooking the dive site, must cover all aspects of the dive plan, and include not only divers, but also shore marshals, deck hands, and anyone else associated with the dive. At the end of the briefing, ensure that all the divers clearly understand the constraints of the dive plan, and are fully prepared for the dive. After any final questions from the group, the dive can begin.

The simple maxim “plan the dive, and dive the plan” is an old one, but its worth has been proven over time. Following it means that all of the divers will get the most they can from the dive, and, importantly, will enjoy it in safety.

ENTERING THE WATER
By the time you enter the water, everyone involved with the dive should be fully aware of the dive parameters.

Wreck diving

Exploring wrecks is—for many people—the main reason to dive. This activity is particularly popular in countries without coral reefs to dive on. However, it also has a general appeal, because wrecks give a historical context for a dive and demand mastery of special skills.

DIVING ON WRECKS

Sunken ships have an obvious attraction as sites of archaeological and historical interest. A wreck is a time capsule from a given period, and the waters around most countries contain thousands of them.

Although most known wrecks are metal-hulled vessels, unusual conditions will sometimes preserve wooden-hulled ships dating back hundreds of years. These provide an excellent opportunity to examine past shipbuilding techniques, and sometimes hold interesting and unusual artifacts. To explore significant wrecks, you should be properly trained and, preferably, work within an archaeological organization.

Information on recent wrecks, such as warships sunk during the two world wars, is usually readily accessible. It is often possible to research the specifications and history of the vessel, along with details of its crew and mission. Historical records may give details of the events surrounding the sinking of the ship.



DESCENDING A GUIDELINE
Popular wrecks often have a buoy moored to their structure to make location and descent easier.

Wrecks also make for good diving because they act as artificial reefs, attracting all sorts of marine life. Over time, the structure becomes encrusted with marine growth, especially filter-feeders, if it lies in a tidal stream. Fish exploit the safety and shelter that wrecks offer: smaller fish tend to shoal around wrecks; larger fish, such as moray or conger eels, can hide safely in nooks and crannies; and predators, such as sharks, may be found in the wreck's surroundings, because they feed off the smaller fish.

PREPARATION AND SKILLS

Wreck diving can be a fascinating activity, but it is not without risks. Under no circumstances go inside a wreck if you lack appropriate training and equipment; the danger of entrapment is very real, and specialist knowledge and skills are required to enter wrecks safely. Exploring the outside of wrecks is safer, but always treat such sites with respect.

TANK IN TRUK LAGOON, SOUTH PACIFIC
Wreck diving is not just about ships; crashed aircraft and military vehicles carried by sunken vessels provide equally enthralling alternatives.

SUNKEN LEVIATHAN
The sight of a major wreck, such as the *Giannis D* in the Red Sea, rarely fails to send shivers down the spine.

DIVING IN CONFINED SPACES
Wreck penetration often involves exploring in dark, confined spaces. It is not recommended for those with claustrophobic tendencies.

FINNING TECHNIQUE

Wrecks often contain a lot of static silt and mud, which is easily disturbed by changes in water currents caused by divers finning overhead. Good visibility can suddenly and dramatically change to almost zero, so using a frog kick (*see p.123*), which generates relatively little turbulence, is recommended to minimize disruption of the silt. The best time for wreck diving is at slack water, but a small current can help sweep away any disturbed silt.

USING GUIDELINES

When you arrive at the dive site, ensure that your boat cover is moored to the wreck's marker buoy. If it doesn't have one, an experienced diver needs to swim down and attach a guideline directly to the wreck, to act as a guide for other divers to follow. If you intend to return to the surface via the same guideline, it can be useful to use a distance line (*see p.127*) to help you find your way back to the bottom of the guideline, especially in poor visibility. If you plan to ascend from another part of the wreck, deploy an inflatable marker buoy (*see pp.130–31*).

PENETRATING WRECKS

When wreck diving, you should carry backups of certain pieces of gear, such as your reel and your flashlight, as well as an independent air source, such as a pony bottle (*see p.68*), in case of emergencies. You must also ensure that you follow the "Rule of Thirds" (*see p.117*) with your air consumption—a third of your air is used to get to the site and explore, a third



LEVEL POSITIONING
The frog kick is a gentle swimming stoke that mainly causes turbulence in the water behind and not below you, and so does not kick up silt.



to return to the point of entry, and a third is left in reserve as a contingency. Allow extra time at the end of the dive to find the guideline, and do not take any unnecessary risks with your dive time, depth, or penetration.

EXPLORATION TIPS

It is a good idea to investigate the area around a wreck, since artifacts may have spread over time and pieces of wreckage may have been knocked off that might be of interest, but take great care. Always be aware that the structure (both inside and outside a wreck) may be much degraded and potentially dangerous. Wear protective gloves, even in warm waters, as corroded metal can be sharp. Wrecks are often heavily fished, so carry a knife in case you become entangled in fishing line. You also need a powerful flashlight (and a backup) to illuminate your way in poor visibility, and to signal to your buddy. In some very enclosed wrecks, it is advisable to wear a helmet and head lamp.

THE GOLDEN RULE

Never remove items from a wreck. As with any artifact, marine finds are more useful to archaeologists when examined *in situ*, and their context provides more information about the wreck than if they are handed in without details of where they were located. Worse still is if they are lost forever in a diver's personal artifact collection.

US troop ship artifacts

RESPONSIBILITIES WHEN DIVING

Wrecks are historical sites, and just as you would not remove artifacts from a historical site on land, such as a castle or monument, you should also respect a wreck and not damage it in any way. Be considerate of the enjoyment of others who may dive the wreck after you. Dive responsibly and with care, and do not remove anything without being given permission to do so. When you find an artifact, such as a ship's bell, after a long,

DIVER USING WRECK KIT

Carrying extra air and nitrox is a failsafe, and can help to extend dive times and shorten decompression stops. Good light sources and dive plan information are also essential.



hard search, you may feel that you deserve to be able to take it away as a trophy, but all such discoveries should remain where they were found, or be raised by trained archaeologists for preservation in a museum.

WOODEN-HULLED VESSELS

Most of the wrecks that you are likely to explore will be metal-hulled, but wooden ships are also preserved under some conditions. Avoid touching the wooden structure, as it is likely to be extremely fragile. Historic wooden vessels may have been lying protected under sand or silt for many hundreds of years. If you want to expose parts of the wreckage for any reason, you should do so by wafting your hand over it to remove the silt, creating a current to take the silt away.

WRECKED BY DESIGN
The former US Coastguard cutter *Keith Tibbetts* was sunk deliberately at Cayman Brac to provide an artificial reef for divers to explore.

LIVE AMMUNITION

Wrecks from the two world wars can provide fascinating dive experiences for military history buffs, but remember at all times that they may also contain live ammunition that could potentially be very dangerous. Never touch anything that resembles a shell or mine, and research what you are likely to find on the wreck before diving.

ARTIFICIAL REEFS

At some popular dive sites, wrecks have been sunk deliberately to provide a safe, interesting dive at a reasonable depth for recreational divers. Such wrecks quickly become colonized by marine life and provide a fantastic opportunity for diving and marine research. They are generally a good place to start wreck diving, since the structure will be intact and any hazards will have been removed. At some wreck sites there are special diving trails with underwater display boards to



RESPECTING HISTORY
Many wrecks sunk during conflict are official war graves and may not be dived.

FINDING OUT MORE

If your interest in a wreck goes beyond merely diving it and you wish to enhance your dive by finding out more about the wreck's history, there are a number of available sources of information. Good starting points include books on wrecks in the area that you are diving, and using the Internet to do some background research. There are numerous websites and forums where you can discover more about wrecks, and also make contact with other divers interested in finding new wrecks. Furthermore, local museums may have displays of artifacts recovered from wrecks in the area, and local divers and boat skippers may be able to reveal information about the history of a wreck.

explain the layout. There may also be laminated booklets that you can take with you on the dive, which enable you to read about the most interesting features of the wreck while on site.

VIRGIN WRECKS

Every wreck diver's dream is to find a previously undiscovered wreck—and there are certainly still plenty to be found. Before you embark on such a search, you should familiarize yourself with the law regarding wrecks, and any wreck you find should be reported to the authorities. Generally speaking, you can dive any wreck around the world apart from those that are designated as historic wrecks and war graves, which are restricted and require special permission to dive.

Locating a virgin wreck can be a difficult, lengthy task, and is likely to be expensive. But a modern hardboat with an experienced skipper and high-tech equipment such as an echo sounder, 3-D imaging of the seabed, and a GPS system, combined with charts and some good background research on your part, could help you hit the jackpot. Many undiscovered wrecks are found in very deep water, so make sure you are fully qualified and appropriately trained before undertaking deep wreck dives.

EXPLORING VIRGIN WRECKS

If you are searching for a particular undiscovered wreck, it is important to start your research in the archive. Studying the ship's specifications and plans will help you identify any remains that you find, and determine whether they belong to the subject of your search. It is a good idea to take video footage of anything you find on a dive, as this is a nonintrusive method of recording the remains, and the footage will be critical in identifying the wreck and for showing to experts.



Navigational chart



Nature and conservation diving

Recreational divers represent a huge pool of manpower that can potentially contribute to conservation work. Many divers take up the sport due to an inherent fascination with nature, and more and more are now applying their skills to organized conservation projects.

DIVING RESPONSIBLY

Most divers have a certain level of knowledge and enthusiasm for marine life and the ocean environment, and realize that along with the thrill of exploration comes responsibility. Divers are in a unique position to observe the deterioration of busy coastal margins around the world and, with the development of the modern ecotourism market, are now also able to actively contribute to conservation projects in the same regions.

At the most basic level, conservation work simply means responsible diving by anyone taking up the sport in the first place. Always adhere to a "no-touch" rule when diving delicate reef systems; you will find this vigorously enforced by most dive operations around the world. Good buoyancy control, streamlined equipment, and a respect for the varied inhabitants of the sea are now widely taught as the only way to dive, and as a result even heavily dived areas experience less habitat disturbance than they used to.

GOOD PREPARATION
A group of divers at a conservation site discuss the work they will be conducting.



USING IDENTIFICATION SLATES
To familiarize themselves with marine life during a dive, divers use species identification slates—waterproof cards with pictures of the species likely to be found at the dive site.

MAKING A DIFFERENCE

Voluntary work, though often conducted at the most basic level, can nonetheless be extremely significant at a local and even international level. The efforts of one voluntary organization alone—Coral Cay Conservation—contributed greatly to the establishment of the Belize Barrier Reef (*see pp.316–17*) as a World Heritage Site, and have seen eight Marine Protected Areas (MPAs) established around the world in the last 20 years.

Formally observing and recording marine life is not just the preserve of the scientific expedition. Significant work has been done by enthusiastic amateurs. Organized conservation and monitoring projects range from casual one-day beach cleanups run by local diving clubs, to multi-national operations setting up nature

reserves throughout the world. Diving conservation is now big business, with hundreds of organizations around the world claiming (with varying levels of accuracy) to run projects that contribute to scientific knowledge or the establishment of marine reserves and protected areas. Most organizations put volunteers through an intense training period before allowing them to take part in even relatively simple sampling or monitoring programs.



REEF EXPOSED
A healthy reef at low tide. Rising global temperatures are harming coral, and sights like this may become less common in future years.

FIRST PRINCIPLES

There are two principal considerations that must be borne in mind by anyone working as a diver on a marine conservation project. The first is safety. You need good diving skills, and enough experience to be able to keep a watchful eye on the ever-present factors of depth, time, and potential hazards while simultaneously making meticulous observations. Enthusiasm for the work being undertaken must not distract you

PRESERVING HABITATS
Carrying out conservation work not only allows you to give something back to the marine environment, but may give you the opportunity to visit exotic destinations.



from the normal rules of safe diving. The second factor is consideration for marine life. Unless you are working under the direction of a well-recognized conservation group, you must only gather data without touching or harming the marine environment. Both marine algae and animals should be recorded only *in situ*.

FINDING A PROJECT

Conservation, to paraphrase an old adage, begins at home. There are marine ecology programs in most countries, and interested divers can usually find groups in their area that contribute to protecting the local marine environment. Search the Internet and specialty diving magazines to find suitable organizations local to you.

WORKING TOWARD OBJECTIVES

Good science starts with a clear means to identify the subject of the research. In the case of most amateur enthusiasts, this means reading up in accurate reference works and guides about the dive environment in question. A further, essential part of any observation program is the need to record data effectively, requiring not only a means of noting down results, but a framework of headings and categories that remain the same for the entire observation program. Only by combining these two important factors—accurate identification and consistent record-keeping—can you accomplish truly effective research and monitoring. Repeated observation of species populations within a given area, for example, can provide invaluable data for analysis by research groups. Your recordings may help local initiatives, or possibly go forward to form part of a much larger-scale project, in which

CORAL MONITORING PROGRAM
Advanced or potentially invasive techniques should only be used under the direction of a recognized conservation group.

DIVING AT A MARINE RESERVE
Even a little research into how and why an area is protected will add food for thought to your enjoyment of the dive.

complex statistical techniques may be used to draw conclusions with far greater significance than you perhaps imagined when gathering your data.

EQUIPPED FOR THE JOB

Although this is the age of the computer and of instant global communications, most scientific expeditions still use some fairly basic equipment to record data in the field. Observation strategies can begin with nothing more than a sharp pair of eyes, an underwater slate, and a good guidebook. An additional item that can be extremely useful is a magnifying glass. This simple tool greatly enhances enjoyment and has become essential for many divers around the world when diving complex reefs.

Underwater photography and videography, if correctly documented, can provide potentially valuable information. In an organized program, you may receive training in advanced techniques, such as the use of catch bags, nets, and quadrats, or in ways to ensure that the target region is sampled effectively, such as GPS systems and datum lines. Effective sampling and observation does not necessarily require high-tech gadgets, but an effective strategy to ensure scientific integrity in the results you achieve is essential.

A CAREER IN CONSERVATION

Should you wish to develop your interest in conservation techniques, there are many courses and reference works available. Formal qualifications may be sought at undergraduate and postgraduate level, although demand for places is extremely high. Jobs in this area are also relatively difficult to come by. However, the rewards for persisting in either scientific or conservation work can be immense.

The loggerhead turtle, an endangered species

Photography and videography

Since the dawn of diving, there has been interest in capturing images of the remarkable ecosystems and animals of the sea. Although underwater photography was initially a complex process, advances in technology have seen it become an accessible, absorbing pastime.

EARLY PIONEERS

The development of underwater filming and photography has mirrored the evolution of diving itself. Early pioneers made their own waterproof housings for cameras, but the invention of the O-ring (enabling watertight hydraulic seals) in 1937 and the Aqua Lung in 1943 convinced camera companies that they should make and sell their own designs.

What prompted this was the huge appetite for images of the underwater world. The rapid growth of recreational diving, and growing interest in underwater films among movie audiences, spurred the development of underwater film and stills photography equipment. Although the first underwater film was made in 1939 by diving pioneer Hans Hass—an instructional documentary for spear-fishermen called *Stalking Underwater*—the first truly commercial underwater movie was made by Jacques Cousteau in 1956. His feature film *The Silent World* was an Oscar-winning sensation that established him as the world's premier underwater filmmaker and explorer.

MINUTE SUBJECTS
One of the most interesting aspects of underwater photography is macro (close-up) work. Tiny creatures can make dramatic subjects.

GROWING MOVEMENT

Until the early 1980s, underwater stills photography and filming was seen as the preserve of either the dedicated amateur or full-time professional diver. Underwater photography was brought to the masses with the development of the Nikonos series of amphibious cameras—culminating in the Nikonos V, still viewed by many as the best underwater camera ever made. Underwater filming did not become a popular pastime until the mid-1990s, when digital video cameras came onto the market, making moving pictures cheaper and technically easier for amateurs to produce. Digital imaging also revolutionized stills photography underwater. Small, easy-to-use digital cameras with

STALKING A SUBJECT
Photographing marine species underwater requires guile and a good understanding of animal behavior and habitats.



many automated functions have made it simpler for divers to record high-quality images of their underwater experiences.

Despite this, the jump to producing professional-standard material remains as great as ever. Light behaves very differently underwater than in air (*see p.183*), and there are myriad extra factors to take into consideration when aiming for truly professional results. The work that you see on the page or the screen may well have involved lengthy planning, complex equipment, and the specialized skills of a professional post-production studio.

CAMERA CONTROL
Though cameras, especially digital models, have become smaller and easier to use, it still takes great skill to wield one effectively underwater, especially for video footage.

However, the same principles that guide professionals can enhance amateur work. You must have knowledge of the underwater environment and the behavior of target animals, and possess impeccable diving skills. Add to this mix some tips on technique when photographing and filming underwater, and you will be well placed to get the best from the dazzling range of camera and video gear available to divers.

USING LIGHT CREATIVELY
An understanding of how light behaves underwater is essential to capture a mood effectively.

STILLS PHOTOGRAPHY

The advent of the digital age has seen an explosion in the popularity of underwater photography, with more and more divers creating images of their dives for posterity. However, producing good results consistently is a craft, and this is what separates the professional from the amateur photographer.

CAMERA SYSTEMS

Underwater camera systems for stills photography can be divided into two categories. The first consists of truly amphibious cameras that do not require a housing to be used underwater, and can also operate on dry land. The pioneering Nikonos V camera is a famous example of the type. Amphibious cameras often have interchangeable lenses, and are available in both film and digital formats. These highly specialized cameras feature oversized controls for ease of operation underwater.

The second category, housed systems, are conventional cameras in waterproof cases. The cameras themselves can be divided into two subcategories: compact devices, and SLR (single lens reflex) models.

Compacts come in film and digital formats, and are light and convenient to carry and use. Most models offer fully automated focus and exposure control. You cannot change the lens on a compact, but some have variable focal length (zoom) lenses. After-market add-on lenses that attach to the outside of camera housings are also available.

ANIMAL MAGIC
To capture the vibrant colors of marine creatures and environments, you will need a purpose-designed strobe lighting system.

SLR cameras, which are available in both digital and film versions, allow the use of a range of lenses and offer complete creative control over key functions such as aperture, shutter speed, and focus. For this reason they are invariably the choice of professional underwater photographers, although SLR-compatible ports, housings, and lighting systems can be very expensive.

CAMERA HOUSINGS

Both compacts and SLRs require a housing to protect them from water damage. These are normally made of plastic, though aluminum housings are also available for SLRs. Aluminum housings are strong and durable but expensive and bulky, and hide the camera within, making it harder to operate. Plastic housings are cheaper and allow you to see the camera, but can be less durable. They are especially vulnerable to scratches and abrasion.

NIKONOS CAMERA
Amphibious cameras like the Nikonos V have an integral water-resistant housing.

DIGITAL COMPACT
Fully automated functions make digital compacts easy to use, but limit creative control.

SLR CAMERA
Available in film and digital formats, SLRs are bulky but offer superior image control.




Flash
hot-shoe
Flexible
joint
Shutter-
sync wire
Strobe
arm mount
Strobe
unit
Hand grip
Shutter
trigger
Dome
port

SLR HOUSING (FRONT VIEW)
Serious investments in their own right, large SLR housings offer excellent access to key controls.


Watertight controls
Viewing
screen

COMPACT IN PLEXIGLAS HOUSING
The housing features push-button mechanical controls for taking, reviewing, and even editing images underwater.

COMPACT WITH STROBE
A diffuser lens placed over the strobe softens the light it casts.

Bare strobe unit


Add-on wide-
angle lens

UNDERWATER LIGHTING SYSTEMS

Lighting is one area where compact digital cameras fall short. Their built-in flashes are too close to the lens to avoid backscatter (*see p.183*). You can distance the light source from the lens by using an auxiliary strobe light, bolted to the housing. SLR-based and amphibious systems often use strobes in pairs, mounted on flexible arms to allow the subject to be lit from different angles. Knowing how to position strobes to best advantage and manipulate power settings is essential, though many cameras will automatically trigger the strobe to fire for the correct duration for the exposure.

HOUSING MAINTENANCE

Maintaining a housing is relatively straightforward. O-ring integrity should always be checked and the ring lightly lubricated with silicone grease. Make a final visual check before diving. Housings should be rinsed in fresh water as soon as possible after a dive. Operate the mechanical controls during rinsing to prevent a build-up of salt crystals. If water penetrates the housing, it will ruin the camera, so a few moments taken to prepare and rinse gear can prevent expensive damage.


Optical
viewfinder
Shutter
trigger
O-ring
Display
screen
View port
Release
catch

Digital compact in Plexiglas housing



MAKING FILMS UNDERWATER

Like underwater stills photography, videography has been revolutionized by the advent of digital cameras, which are small and easy to use, compared to film or analog video. Basic point-and-shoot underwater videography is quite easy with consumer-grade digital cameras. To advance beyond the novice stage, however, you need special skills, more advanced equipment, and a flair for using video editing software.

A robust housing will be necessary to protect the camera from water damage, while a basic underwater lighting system is essential for capturing good color footage, since water filters out various colors from natural light as depth increases (*see p.183*).



PRECISE POSITIONING
To be a good underwater film-maker, you need to perfect your buoyancy control and finning.

CHOOSING A VIDEO SYSTEM

Choice of camera is the first decision for novice videographers. Though analog video cameras are still available, digital is now the dominant technology. Digital cameras are available in digital tape, flash media, HDD (hard disk drive), and DVD recording formats. Look for cameras with three-chip processors (called 3CCD cameras). These divide red, green, and blue color information into separate processing paths, offering richer colors than cheaper one-chip models. At the top end of the market are cameras with HD (high definition) imaging, which produce video of astonishing clarity, due to the high rate at which they scan visual information.

FILMING SKILLS

Creating high-quality underwater video requires you to do more than merely jump in with everything set to automatic, press record, and film throughout the dive. Many automatic systems perform poorly underwater. For example, autofocus becomes inaccurate in low-contrast environments, resulting in hazy images. Careful manual control of focus and manipulation of white balance (which sets the baseline for color values in different light conditions) are key skills.

Your diving skills also must be excellent; you need to be a steady platform for the camera—camera shake is a common cause of ruined footage. The camera and housing should also be neutrally buoyant (they should neither sink nor rise underwater) for ease of



BASIC VIDEO CAMERA
Affordable cameras for home use usually feature automatic focus and exposure control, but may also have some manual options for skilled users.



ADVANCED DIGITAL CAMERA
Top-end video cameras have advanced features like high definition, multi-chip processing, plus image stabilization systems for sharp images.

Basic light



Housing with lights



Bare housing

PRESSURE HOUSING AND LIGHTS
Housings fall into two categories—electronic or manually controlled. The latter use plungers, rods, pins, and cogs to allow the camera controls to be manipulated from outside the housing; they require more skill, but have the advantage of avoiding electronic systems that can go wrong or short out in the event that the housing is flooded.

handling, and you should familiarize yourself completely with how your camera is operated, so its use becomes second nature underwater.

PRODUCTION AND EDITING

Thorough planning is the secret to good filmmaking, and video should be shot with an audience or editor in mind. Building a story around a given dive is not a complex process, but creates a target shoot list for the camera operator to work from, and gives the finished film an engaging narrative. You can place scenes in order and polish the results to a professional standard using video editing software that is commercially available for use on home computers.

KEEPING CLEAR
While filming, be careful to avoid causing physical damage to the organisms you have come to film. Avoid touching, or kneeling on, reefs.



KEY PRINCIPLES

Modern cameras and housings allow even the novice to achieve consistently good photographs and video footage. One key development of the last ten years has been the ability to immediately view the results—even during the course of the dive—and then make adjustments accordingly before the next shot. But throughout the history of underwater photography and videography, certain principles have applied as much to hardened professionals as they have to happy snappers. Following these simple rules can immeasurably improve even your first forays into photography and filmmaking underwater.

LINING UP FOR A SHOT
Good positioning relative to your subject can help make subjects stand out from the background.

GETTING CLOSER

The first principle when shooting underwater is to get as close to the subject as is feasibly possible. Even the most crystal-clear water contains a mass of suspended particles, and even if your eyes cannot pick them out, you can be sure your lighting system or lens will. Getting close to the subject means greater clarity of the resulting image, and this is one of the reasons why "close-up wide-angle" is such a popular approach. This uses a wide-angle lens at close range, allowing the whole subject to be viewed with the lens only a short distance away. For the same reason, "macro" (close-up) photography is often a good place to start if you are a beginner, since clear, well-lit macro images are relatively easy to achieve.

For the novice photographer or videographer, another excellent principle is to remember to take shots with an upward orientation. There is nothing worse than viewing an endless series of dull blue or green shots where the subject is lost in the background of reef or seabed. Shooting upward isolates the

SUNLIGHT THROUGH WATER
The shifting light patterns encountered underwater can make for dramatic photography, but are challenging to expose correctly.



WAITING FOR A SHOT
Many fish are inquisitive, but easily alarmed; good buoyancy control will allow you to hold still until a subject presents itself.

subject against the background of the open water, and creates a more striking contrast. The composition of such shots can still include reef or coral, wall or wreck; however, the subject itself should be consistently easier to spot.

USING LIGHT SOURCES

Effectively lighting a subject is one area where most amateurs struggle. It is also one of the areas where modern compact digital cameras built-in flashes will let a picture down. If the light source is too close to the lens, particles in the water will reflect the flash directly back into the lens. This creates a phenomenon known as “backscatter,” a snowstorm effect of white dots on the photograph. One of the most basic prerequisites of taking good underwater images in anything other than perfect underwater conditions is an ability to position a strobe away from the lens. This allows the flash to come in at an obtuse angle, and helps to prevent backscatter from spoiling a shot.

These simple principles do not, unfortunately, guarantee good images every time, but they are useful for anyone starting out in photography or filming. Trial and error will help to refine your skills over time, and the best advice is to jump in, remember the basics, snap or film away, and enjoy!

DEPTH AND COLOR LOSS

Water absorbs different wavelengths of light as depth increases, causing images taken without artificial illumination to seem washed-out and dominated by blue tones. Reds fade from visibility at a depth of 10–15 ft (3–5 m), oranges at 35 ft (10 m), and yellows around 50 ft (15 m); by 80 ft (25 m) greens have almost disappeared, and by 100 ft (30 m) everything appears deep blue or black to the naked eye.





Night diving

To many, the idea of diving at night may seem a little crazy, but there is far more to it than just the thrill of exploring in the dark. Night diving reveals a whole host of underwater organisms that lie hidden during the day and only become active at dusk.

NIGHT ON THE OCEAN
When diving on a clear, moonlit night such as this, you may be surprised at just how effectively the Moon is able to illuminate the underwater environment.

LIGHT AND COMMUNICATION

Night diving is obviously less simple than diving during the day, but when properly organized, it is relatively straightforward. A powerful flashlight will easily light your way and the creatures around you, revealing marine life in its true colors. However, if you cover your flashlight (never switch it off; the bulb may blow when you turn it back on), you will be surprised at how much light there is underwater. Many creatures use phosphorescence at night, and as you move through the water, you will cause plankton to release tiny pulses of light, leaving beautiful glowing wakes trailing behind you.

The main restrictions compared to daytime diving relate to communication, not only between divers, but also—and perhaps more importantly—between divers and boat cover. You will be able to monitor your buddy's location from the position of their flashlight beam. Signaling to your buddy can be done in the normal way, but while shining your light on to your hand as you make the sign. Attract your buddy's attention by waving your light, but take great care not to shine it at their face, since it can take as long as 15 minutes for their eyes to fully readjust to the near-darkness and restore night vision.

LIGHTING TIPS

It is vital that all divers carry a flashlight, and at least one other as a backup. Take spare batteries; if using rechargeables, make sure they are fully charged. Use hand-held lights, not head-mounted ones: one look at your buddy with a head-mounted light will ruin their night vision. A glow-stick attached to the back of your suit, while not essential, will increase your own visibility.

Hand-held flashlight

At the surface, avoid flashing your light unless you need to alert the surface cover in an emergency. If you are diving from the shore, leave a light source there—for example, a bright boat light, flashlight, or beacon—so you can easily find your way back to land after surfacing. Exit points should be marked with colored lights, to distinguish them from any other light sources.

You will find that most gauges and computers are easily readable by flashlight, and just shining the beam directly on to your gauge will make it luminous for a while.

DIVING INTO DISCOVERY
A very different “night shift” of marine life can be seen during nocturnal dives, like this outlandish basket star.

TAKING PRECAUTIONS

Night-diving buddy pairs often link themselves together with a short line. While not essential, this is recommended for novice night divers and in poor visibility. If you are diving on a wreck to which a guideline and buoy are attached, secure a strobing marker light to the base of the line so it can be easily located in the dark. When choosing a dive site, opt for something simple, such as a shallow wreck or reef with plenty of distinctive features. An interesting daytime dive may be worth revisiting to investigate marine life that emerges at night. To minimize the risk of incidents, do not dive too deep, since any problems will be much harder to cope with in the gloom. If diving a more open site, use a surface marker buoy with marker light attached to identify it to any boat cover. Be careful not to lose contact with surface cover: getting lost at night could mean you are not recovered until morning.

FLASHLIGHT SIGNALS

During a dive, your torch beam will alert your buddy to your position. You can also make simple signals with your flashlight beam on the seabed to communicate with your buddy. At the surface, wave your torch vigorously from side to side if you require immediate assistance.



SIGNALING “OK”
Tracing a large circle on the seabed communicates to your buddy that you are OK.



SIGNALING FOR ATTENTION
A rapid side-to-side movement means that you want to show or tell your buddy something.

Cavern diving

Rich with opportunities for dramatic dives, caverns offer a bridge between ordinary open-water diving and the far more specialized activity of cave diving. Nonetheless, diving in caverns demands careful preparation and respect for potential risks.

WHAT IS CAVERN DIVING?

A cavern is a large, enclosed area of rock or coral that is of sufficient size to allow a diver to enter and move around. These fascinating environments can be extremely dramatic, are often eerily lit, and may play host to an array of animals not encountered on the open reef.

Unlike the more extreme sport of cave diving, in which divers penetrate beyond the reach of natural light, in cavern diving the exit is always clearly within view. However, cavern diving still carries inherent risks because the diver does not have direct access to the surface in the event of an emergency. If simple safety drills are not followed at all times, there is the potential for very serious problems to develop when diving even in simple caverns.

ON THE THRESHOLD

A diver hovers at the entrance of a freshwater cavern in Australia. Following basic safety rules is essential at such sites.

CAVERN DIVING EQUIPMENT

A flashlight is an essential item for cavern diving, but it is also sensible to bring along a backup light. This need not be a large, bulky model but must be able to provide enough light if your main flashlight malfunctions. Be sure to keep batteries freshly charged. An alternative air source, such as a pony bottle (*see p.68*), is also an excellent idea in caverns, since the diver cannot ascend directly to the surface if the primary air source suffers an unexpected failure.

A backup flashlight

SAFETY AND SKILLS

The first rule of cavern diving is to prevent your natural curiosity from turning a cavern dive into a cave dive! The exit should be clearly visible at all times—if not directly in your line of sight, then at least the natural light of the cavern entrance should remain visible. For many divers, the temptation to explore deep into cave systems is strong; however, the moment the exit is lost from view and natural light fades, the dive becomes a cave exploration, which should not be attempted without appropriate equipment and special safety and skills training.

Certain skills are essential when diving larger caverns. Buoyancy control is important, particularly when there is a silty substrate on the cavern floor.

INNER SPACE
A diver shines light on the interior of a sea cave. Caverns have a mysterious ambience quite different from that of open diving environments.

It is also advisable to use a finning technique known as the frog kick (*see p.123*). This is a gentle, circular fin-stroke that helps you avoid stirring up sediment. One misplaced kick from a fin can turn a cavern into an impenetrable soup of silt and lead to disorientation and panic. For this reason, and as a matter of plain common sense, it may also be appropriate to tie off a line at the entrance of larger caverns (*see p.127*) to provide a direct route to the exit in case of reduced visibility. It is also strongly advisable not to enter a cavern without local knowledge or a guide; there may be specific issues about a cavern system and the hazards it contains—such as seasonal changes in visibility—that do not appear in any standard dive guidebooks.

Ice diving

Diving under ice might not sound like an attractive proposition, but it is a uniquely exciting experience. Visibility is typically excellent beneath ice, with soft light filtering through from the world above. Ice diving can also take you to breathtakingly beautiful parts of the world.

UNIQUE ENVIRONMENT

Ice diving can be done in the sea or in frozen lakes. The aquatic life you encounter will depend on where you are in the world and whether you are in a marine or freshwater environment. Visibility is often stunning; the ice provides a protective layer over the water, so it is not churned up by the wind, and low light levels under the ice also help to inhibit algal growth.

COLD-WATER GEAR

A diver waits to enter the water wearing special equipment designed to cope with conditions of extreme cold.



KNOWING THE ROPES

If you are planning to go ice diving, you will need to undergo special training. This will teach you not only the safety aspects of diving while tethered on a rope under ice, but also how to cut the ice hole through which you enter the water, and how to tend safety ropes for other divers while you remain on the surface in a support role.

Ice diving requires a minimum of four to six people per dive. There will normally be two divers operating as a buddy pair (*see pp.110–11*), and two people to tend their lines. It is advisable to have at least one extra person on standby. It is standard practice for each diver to be tethered separately, and it is not advisable to tether two divers on one line, because if anything happens to this rope, then both divers can be lost. Lines should always be tied using a bowline knot, which is very secure.

SIGNALS AND SAFETY

Signaling to your tender is an important part of ice diving. Since you are diving in extreme conditions, it is vital that he or she knows you are OK throughout the dive. You will learn about giving rope signals during training.

Apart from the obvious dangers of diving in an enclosed environment, you must also be careful to monitor your core body temperature. Repeat dives

SPECIAL PROCEDURES
Ice divers rely on a surface support team (*above*) for safe diving under the ice.

should only be undertaken when you are fully warmed up. You should also ensure that you eat high-energy, hot food to replace the calories you will burn during the dive and in keeping warm afterward.

SPECIAL GEAR

Ice diving requires special equipment. You will need an environmentally sealed regulator set (*see p.63*), which is designed to be less susceptible to freezing. You will be taught to submerge this in the water before diving, to acclimatize it to the temperature. You must only breathe from it when submerged, to reduce the risk of free-flow (an uncontrolled release of air due to a frozen mechanism). It is also recommended that your primary air source and octopus are mounted on separate first stages (*see p.61*) to ensure that one will work if the other freezes. Your cylinder will need a special pillar valve to accommodate this.

You will need to wear warm undergarments beneath your drysuit, thick neoprene gloves or a pair of waterproof dry gloves (*see p.54*), and two thick hoods for extra warmth.

FROZEN DEPTHS
A diver films the fascinating world beneath the surface. Many unique animals live in cold seas.



Freediving

Once simply a fishing technique, freediving—diving using only the air carried in the lungs—has become increasingly popular as a sport. Extreme athletes now constantly push the perceived limits of human performance, diving to remarkable depths on a single breath of air.

PURE SPORT

Freediving is not exclusively the preserve of the extreme athlete: anyone who has snorkeled and duck-dived to explore the seabed could describe themselves as a freediver, making this the most accessible of all diving disciplines. Many would argue that it is also the purest form of diving, requiring only the minimum amount of equipment and relying entirely on discipline, courage, and physical conditioning.

The roots of freediving stretch back to when the human race took its first tentative steps into the sea, diving into the water to harvest food and explore the seabed. Modern freediving, by contrast, is a disciplined sport, with record attempts highly regulated by the two governing bodies—A.I.D.A. (Association Internationale pour le Développement de l'Apnée) and F.R.E.E. (Freediving Regulations and Education Entity). Divers compete in a number of categories, two of which usually take place in a swimming pool: static breath-hold—a simple endurance test with a timed immersion in a shallow pool—and dynamic breath-hold, a test of the distance divers can swim using only a single breath. In open water, competitors are judged on the depths they can reach and return from safely.

Freediving naturally carries inherent risks—the most advanced and extreme disciplines demand that the body's supply of oxygen is completely used on a dive, and losing consciousness is always a danger. Exploration of freediving limits should never be conducted alone, and only after attending one of the many introductory courses available to those interested in taking up the sport.

EQUIPMENT

Freediving does not require much equipment, but specialized items, such as streamlined suits and fins of variable flexibility, are used to maximize the speed of movement through the water. Masks with low internal volume are also useful, as they allow divers to conserve air that would otherwise be used to exhale into a standard mask to counteract mask squeeze (*see p.115*).

Specialist mask

STATIC BREATH-HOLD COMPETITION
Divers compete for the length of time they can hold their breath. World-class competitors can achieve times of over seven minutes.

TOUCHING THE DEEP
A freediving competitor reaches for the tag that proves that the designated target depth has been reached—this must be presented at the surface for inspection by judges.

DIVING DEPTHS

Competitive depth records are judged in strict categories, defined by precise parameters such as the use of weights or fins. In "No Limits"—the category in which the highest-profile records are set—the diver is dragged down by a weighted sled, and rockets to the surface using an airbag.



Depth obtainable by an average club freediver.

100 ft (30 m)

Depth obtainable by a competitor in the "Constant Weight" category, which allows the use of fins and ballast. Top divers can reach 330 ft (100 m)—roughly the height of the Statue of Liberty in New York or Big Ben in London.

330 ft+ (100 m+)

Depth obtainable by the top "No Limit" class of freedivers.

650 ft+ (200 m+)



Underwater archaeology

While marine archaeology is mainly confined to the academic and scientific world, it could be said that every diver who explores a wreck has an archaeological interest and responsibility. Both the seabed and many freshwater sites hold compelling historical secrets.

RULES FOR THE AMATEUR

Although every dive has the potential to reveal historic artifacts, targeted methodical surveying is an altogether more serious business, as is the correct means of excavating and recording any finds. Archaeological divers can therefore be placed in one of two distinct categories—the serious professional diving archaeologist, and the enthusiastic amateur.

Although this is a field in which amateurs can make a very valuable contribution, it is essential that they do so only through involvement in an organized project, conducted by a recognized and authorized group. Far too many sites have been destroyed, and artifacts removed, by what amounts to vandalism and theft—the equivalent on land might be digging a historic site or burial ground without permission, which is unthinkable, of course.

There are many organizations that welcome help from amateur volunteers, and will supervise and guide you. The thrill of discovery really does reach a new level when it is shared with individuals who understand the full significance of a find. You may find that more scope for joining an organized project exists if you first undertake some training, perhaps by volunteering on digs on land.

Learning professional marine excavation and recovery techniques can be fascinating for the amateur. Archaeologists go to great lengths to avoid damaging a surveyed location, and even when they locate an item of interest, try to avoid intrusive collecting techniques or digging.

MORE THAN YOU BARGAINED FOR

By taking an artifact from a dive site, you destroy its integrity and hinder efforts to learn about past peoples. And that may not be the end of the matter. In many parts of the world, sites of marine archaeological interest are strictly regulated. The recovery of artifacts is—quite rightly—taken very seriously, and penalties for illegal activity and for removing items can be severe.

Amphorae, used to store oil and wine, recovered from a Turkish site

RELIC OF CONFLICT
Divers inspect the remains of a Japanese fighter aircraft shot down in the Pacific during World War II.

WHAT TO EXPECT

Marine archaeological expeditions are usually initiated because research or local knowledge has pointed to a region that has archaeological potential. Modern GPS (Global Positioning System) equipment has made pinpointing such sites much easier. On reaching the site, a detailed survey is generally first carried out. This may involve using a datum line (a fixed reference line on the seabed from which measurements are taken), or pegging out a grid. Precise recording of the location and state of the site before digging is vital, and is usually conducted through photography or extensive sketching. Small test digs may take place before a full-scale excavation occurs, with the exact site of each find carefully logged, and the finds themselves sketched or photographed. Preservation and restoration techniques are extremely specialized for such finds. Marine archaeology is a long way from the derring-do of Indiana Jones, requiring organization, attention to detail, fine diving skills, and persistence.

CAREFUL SURVEY
Meticulous recording of survey data is one way in which amateurs can help on a professional dig.



Technical diving

The desire for ever-deeper dives and longer periods underwater has led to the development of special gas mixtures. The use of these in technical diving offers an exciting range of new skills and marine environments for qualified technical divers to explore.

PUSHING BACK BOUNDARIES

Scuba divers are limited, by simple physical laws, to a certain amount of time under water (dependent on the depth of the dive) and an overall maximum depth. Training agencies recommend that recreational divers using compressed air go no deeper than 130–165 ft (40–50 m). Beyond this, nitrogen can build up dangerously quickly in the body, greatly increasing the risk of decompression sickness (DCS; *see pp.142–43*). In addition, the increased levels of nitrogen in the bloodstream below 165 ft (50 m) can lead to severe nitrogen narcosis (*see pp.100–01*). The oxygen content of air, too, becomes increasingly toxic to the nervous system the deeper you dive (*see pp.96–97*).

To extend dive times and allow exploration to greater depths, special mixtures of gas have been developed in which the balance of oxygen and nitrogen has been altered, or that contain new gases to dilute the impact of either oxygen or nitrogen. The use of these mixes is known as technical diving, and involves three types of gas mixes: nitrox, which allows longer dive times, and trimix and heliox, to reach greater depths.

EXTENDING DIVE TIMES

Normal air is composed of around 21 percent oxygen and 79 percent nitrogen. Nitrox is a gas mixture that contains a higher percentage of oxygen and a lower nitrogen content than normal, allowing longer dive times before the diver's body stores up too much nitrogen, and also reducing diver fatigue after the dive. Nitrox can be mixed in various proportions, from


Multiple light sources
Complex fastenings for extra gear
Heavy-lift BC jacket
Tanks contain gas mixtures for specific depth ranges
Heavy-duty drysuit worn over a thermal undersuit insulates the diver from the low temperatures of extreme depths

UNDERGROUND ODYSSEY
A diver emerges from the water wearing the complex equipment required for cave diving, including tanks filled with special gas mixes, and sophisticated dive computers.

BEYOND NORMAL LIMITS
A diver explores deep within a flooded cave system. Technical diving procedures enable divers to go farther than ever before.

TECHNICAL KIT

Diving at extreme depths or in extreme environments, like deep caves, requires special gear. Technical divers meticulously analyze their equipment, and try to eliminate weak points—there is little margin of error during a deep technical dive. To support the extra gas tanks used during technical dives, most divers opt for high-lift "wing"-style buoyancy compensators (*see p.59*). They also choose high-performance regulators that can handle the task of supplying breathing gas at extreme depths. Sophisticated dive computers are used to monitor how technical gas mixes are metabolized during a dive.

A multi-gas computer

22 to 50 percent oxygen. However, beyond a certain depth the increased oxygen in the nitrox mix becomes toxic and can cause seizures. The more oxygen in the blend, the shallower this will occur. For this reason, diving with nitrox requires special training, although courses are readily available to recreational divers.

GOING DEEPER

Divers wishing to travel deeper than 165 ft (50 m) use either heliox or trimix, both of which introduce helium into the breathing mixture. Heliox contains only helium and oxygen, whereas trimix is a three-gas combination of helium, oxygen, and (usually) nitrogen. Heliox is used mainly by military and commercial divers, while trimix is more often used by leisure divers. Both succeed in reducing the likelihood of nitrogen narcosis (*see p.101*), oxygen toxicity, and DCS. However, since helium conducts heat six times faster than air, these mixes can cause the diver to feel very cold. Helium is also absorbed rapidly into the body, so lengthy decompression is necessary. Divers wishing to use these gas mixes must undergo appropriate training.



Careers in diving

Lots of people grow to love recreational diving and consider turning their passion into a profession. Work in diving is demanding, and earnings are often modest, but the personal satisfaction to be gained from a career in diving may make the hard work worthwhile.

GOING PROFESSIONAL

There are two common factors in the life of any diving professional: the work is invariably challenging, and there are always many more candidates for jobs than there are vacancies.

As a growth sector, the recreational diving industry offers the most career opportunities. Qualifying as a divemaster or instructor with a recognized training agency means that you will be able to work at dive centers in every corner of the globe. However, qualified instructors are responsible for the safety of their students, and the selection process is necessarily a rigorous one. Being a highly skilled diver is just one of the qualities an instructor must possess; strong communication skills, maturity, and in-depth technical knowledge are also required. Becoming an instructor with a commercial agency can also be an expensive process, but it is a crucial first step towards gaining work in diving, and may open the door to a lifelong career.

COMMERCIAL DIVING

The world of commercial diving covers all activities outside of recreational instruction, and includes scientific, media, and industrial diving. The last of these represents the best-known face of the commercial diver—the hard-hatted aquanaut working on the rigs and pipelines of the oil industry. The demands of the job have changed from

DEEP-SEA EXPLORER
A diver in a mechanized pressure suit works on the deep ocean bed. Such jobs are very demanding, and competition for new positions is high.



EXPERT GUIDANCE
An instructor shepherds a new student through his first dive. Resort guides are sought after in many areas.



UNDERWATER WORKER
A commercial diver repairs a steel frame on the sea floor. Such jobs require advanced knowledge of marine engineering techniques.

the pioneering days of oil exploration, and today's commercial divers must be able to master advanced surveying and engineering skills while working in the most difficult of environments.

SAFEGUARDING THE SEAS
A navy diver prepares to submerge for mine-clearance duties. Military divers face dangerous tasks and are trained to exacting standards.

JOINING THE SERVICES

Military and police diving present a different set of challenges for the aspiring professional, often requiring diving in appalling conditions, such as in confined spaces or very low visibility. Demand for diving jobs in the military or police is invariably high, and only the best candidates are accepted after a careful and strict selection process.

Underwater life

Introduction

Oceans cover 70 percent of the world, yet we remain ignorant of much of what lives beyond the relatively shallow regions explored by humans. The sea is a vast depository of life holding a bewildering array of animals and plants, from the massive to the microscopic.

PLUMBING THE DEPTHS

Although the majority of our planet is covered in water, only about 16 percent of all known species live in the sea. This is more a reflection of our own inadequate knowledge than of a lack of diversity in the oceans: there are undoubtedly many thousands of unknown species lurking in the vastness of open sea that we have yet to encounter. Much of our exploration of the sea has, by necessity, taken place only in the shallow margins around land. The limits of our own physiology and technology make sustained exploration below 330 ft (100 m) both demanding and expensive, but the average depth of the ocean is in the region of 2.3 miles (3.8 km), leaving vast tracts of our own planet totally unexplored.



MARINE MELTING POT
The ocean contains a diverse range of life-forms, such as this bizarrely patterned nudibranch.

The coastal fringes that are the realm of the recreational diver reveal a wealth of life. Only two percent of known marine species live in the open ocean, with the remaining 98 percent burrowing, swimming, scuttling, and crawling over reef, rock, and muddy sea bed. Although recreational divers are confined to depths of around only 130 ft (40 m), the first 650 ft (200 m), known by scientists as the neritic province, hosts the greatest diversity of life in the sea.

ZONES OF LIFE

Four temperature bands define the basic zones of marine life on the planet. At the northern and southern extremities of the Earth are the polar seas, capped with ice. These graduate into temperate seas, which mostly range from 39 to 68°F (10–20°C). Subtropical seas form a loosely-defined buffer zone around the tropical seas of the equator, which are the world's warmest, rarely dropping below 68°F (20°C).

THERMAL RANGE
Sea surface temperatures vary from freezing point at the poles to more than 30°C (86°F) in the tropics.

KEY

- Polar
- Temperate
- Subtropical
- Tropical



ENDLESS VARIETY

Water is the perfect medium to support life, at once a means of transportation, communication, support, and reproduction. The lives of countless numbers of people worldwide are dependent on the world's oceans and the life they support, which ranges from microscopic plankton to the immense bulk of the largest animal alive today—the blue whale.

Types of marine environments and the species that inhabit them vary with location around the world. The open ocean is roamed by giants, with large migratory species, filter feeders, and opportunistic predators. The latter, bold and inquisitive, provide many of the "big-animal encounters" that divers find so rewarding. Closer to shore, the warm, clear waters around the tropics are home to coral reefs, the most spectacular of all marine systems. More temperate coastal regions have richly populated marine "forests" of kelp—seaweeds that grow to immense lengths to reach the sunlit upper reaches of the water.

ENVIRONMENTAL CONCERNS
The sea supports countless livelihoods, and it is perhaps no surprise that overexploitation occurs. Here, an official apprehends shark-finners.

Colder waters are the province of migratory marine species, traveling the seas in search of new feeding opportunities as the seasons change. And although we tend to think of migrations taking place over great distances laterally, there is also a great vertical movement in the oceans. As the day and night change, a range of animals migrate through the water column, creating the largest daily movement of animals on Earth.

FLIGHT PATH
With a massive wingspan of up to 10 ft (3 m), the eagle ray is a magnificent marine species.

Tropical seas

If ever there was an image that sums up the magic of diving, it is that of a coral reef. Although coral reefs are the most famous feature of tropical seas, these warm clear waters have much more to offer, such as mangrove swamps, sea-grass beds, and vast tracts of open ocean.

WARM BELT



PERFECT SNORKELING CONDITIONS
By happy chance for divers, tropical coral reefs require clear warm water with little seasonal variation to grow at an optimum rate.

Tropical waters occupy the region within the "20°C isotherm"—the irregular band of water north and south of the equator that seldom drops below 68°F (20°C). Although undeniably appealing to the diver, they actually present a less attractive environment for marine life. The warm equatorial sun heats the upper layers of the water column, creating a marked temperature difference between the surface water and deeper colder water. Such temperature stratification prevents mixing of the water column, so nutrients are not passed up from deeper water. Marine animals and plants have therefore had to adapt and evolve numerous strategies to cope with the lack of nutrients in the water around them. Perhaps the most remarkable of these is the coral reef. Primary production—the formation of organic compounds from inorganic material—is up to 100 times greater in coral reefs (*see p.204*) than in open tropical waters, and although they cover only 0.2 percent of the ocean environment, they are home to 25–30 percent of all fish species.

LIFE ON THE REEF

The diversity of tropical regions is based to a large extent on coral reefs, although these vary in their diversity depending on location. The reefs with the most vibrant marine life are found in the Indo-Pacific, with up to 700 coral species playing host to 2,000 fish species. In contrast, Atlantic coral reefs have only 70 coral species and about 600 fish species.



Raccoon butterflyfish



CORAL FORMATION
These complex and often huge structures are built by the tiniest of marine creatures.

The reefs of the Indo-Pacific are the richest marine environments on Earth. Their beautiful structure and bright colors, combined with the splendor and variety of animals that inhabit them, make reefs irresistible to divers, and it is no coincidence that many of the world's best dive sites are found on coral reefs.

PARADISE ISLAND
Tropical beaches draw ever-increasing numbers of tourists, creating intense development pressures which, if uncontrolled, pose a significant threat to tropical seas.

COASTAL NURSERIES

Tropical waters are also home to mangrove swamps and sea grass beds, both arguably as important as coral reefs in the overall health of tropical seas. There are 40 species of mangroves—tropical trees and shrubs that grow in shallow and intertidal coastal waters—and they form flooded forests that act as nurseries for various reef and open-water fish species. The 50 species of sea grass form "meadows" in shallow waters that are feeding grounds and nurseries for many fish species. The eradication of sea grass beds and mangrove swamps around the world is a real concern, with undeniable impacts on coastal ecology as animal populations are denied crucial areas for the growth and development of their young.

REEFS UNDER THREAT

Coral reefs worldwide are under intense pressure. The continued development of coastal regions has caused silty water to run into the seas, smothering these delicate systems, and, coupled with the damage caused by destructive fishing methods, it is thought that up to 90 percent of reefs have been impacted by humankind. There is also evidence that rising water temperatures are causing a phenomenon known as bleaching, which is fatal to reefs. This occurs when the coral polyps eject the minute algae that sustain them as a response to stress.

Diving a reef can be the highlight of a diver's life, but we have a very real responsibility when exploring reefs not to harm or disrupt them in any way. A considerate approach is vital if we are to preserve these wonderfully vibrant ecosystems.

BLEACHED CORAL
Coral bleaching is one of the more vivid consequences of global warming and increased pollution.

THE CORAL CYCLE

Reefs are formed because of the extraordinary symbiotic relationship between tiny animals—polyps—and minute algae. Polyps are colony-forming animals that construct coral reefs. The polyp has a hard exoskeleton made of calcium carbonate, and this forms the physical structure of reef systems. Minute single-celled algae called zooxanthellae live within the polyp, protected by its hard skeleton, and nourished by its waste products. In turn, the zooxanthellae provide the polyp with nutrients and oxygen, which they produce, like plants, through photosynthesis. This process requires light, which is why tropical reefs are found only in waters less than 330 ft (100 m) deep—the so-called "photic zone", penetrated by sunlight. This relationship is vital: warm, clear water tends to be low in oxygen and nutrients, but the partnership of algae and polyp creates a highly efficient nutrient recycling system, and, in turn, sustains a rich array of marine life.



CORAL HEADS
The presence of algae is revealed by the faint greenish coloration within the polyp's soft tissues.

REEF DISTRIBUTION
Over 90 percent of coral reefs are clustered in the Indo-Pacific region. Reefs do not form on coasts that experience cold or strong currents.

KEY
● Reef



REEFS AND RESPONSIBILITY Low-impact “hands-off” diving techniques are essential to avoid damaging coral reefs.

Subtropical seas

Although there is no strict definition, subtropical seas can be described as waters too consistently warm to support temperate marine life, but too cold for coral reefs to flourish. Also known as warm temperate waters, subtropical seas are found in all of the world's oceans except the Arctic.

BETWEEN TWO WORLDS

Subtropical waters are sandwiched between tropical ecosystems (generally identified by the presence of coral reefs and mangroves), and the temperate zone (identified by cold, rich waters supporting complex systems such as kelp forests). In subtropical marine systems, the water temperature is too high to contain large amounts of oxygen and nutrients (*see pp.208–09*), and yet too low to promote the recycling properties of coral reefs (*see pp.204–05*).

The most popular subtropical areas for diving are the Mediterranean and parts of the Gulf of California (also known as the Sea of Cortez). Other key sites include South Africa's Aliwal Shoal (*p.259*), Fernando de Noronha (*see p.318*) off the Brazilian coast, and the islands of Cocos, Malpelo (*see p.319*), and Roca Partida (*see p.320*) in the eastern Pacific.

RED GROUPER
These large predatory fish are typical of Mediterranean seas, but overfishing has depleted their numbers.

In terms of their marine life, there is a stark contrast between the Gulf of California and the Mediterranean. The former is famed throughout the diving world for its big-animal encounters, while the latter is a somewhat barren system. The cause of this difference is their topography. The Mediterranean is in effect an isolated bowl of deep water,



MEDITERRANEAN COASTLINE
The beauty of the coast and its clear waters are some recompense for a relative dearth of marine life.

whereas the Gulf of California is less enclosed and relatively shallow, with water and animals able to move freely to and from the Pacific.

Plankton, which are at the base of the food chain, thrive in waters in which mixing of the water layers brings nutrient-rich deep water to the surface (*see pp.214–15*). Most of the cold, nutrient-rich water from the Atlantic that enters the Mediterranean does so through the narrow Straits of Gibraltar, creating a plume of colder water that extends to the Sicilian Channel. The best dive sites in the Mediterranean lie along this plume. Much of the rest of this sea experiences very little mixing of the water column, and while the result is very clear water, there is little to support life.

The Gulf of California is open at the southern end, with the Baja peninsula to the west and the Mexican mainland over 125 miles (200 km) to the east. Much of it is less than 985 ft (300 m) deep, and these shallow waters are regularly mixed by water entering from the Pacific to the south and are rich in marine life. This is one of the finest locations to encounter large animals such as humpback whales and manta rays.

OCTOPUS ENCOUNTER
Various species of this cephalopod can be encountered in subtropical waters worldwide.

Temperate seas

The richest of all marine ecosystems, temperate waters are the stretches of ocean between the poles and the tropics. These waters are hugely changeable, offering a seasonal range of conditions at any one dive site, often accompanied by a variety of visiting migratory species.

THE TEMPERATE ZONE

It is difficult to define the temperate zone precisely, because major ocean currents can artificially extend temperate waters into tropical regions, or push temperate species into near-polar regions. The best definition is perhaps found in the temperature range of the water: true temperate waters rarely sink below about 39°F (10°C) or rise above 68°F (20°C).

The positioning of the temperate zone means that its waters see a greater change of conditions from season to season than tropical and subtropical seas. In particular, the amount of light hitting the surface of temperate waters varies considerably between winter and summer, and this leads to a seasonal variation in productivity—the sheer amount of life that an ecosystem can support. At the base of the food chain in the marine ecosystem are tiny organisms called plankton, which are dependent on light and nutrients for growth and reproduction. In the winter, when even water near the surface receives little light, conditions are poor for plankton growth, and so productivity is low. However, during the stormy winter months there is considerable mixing of cold, nutrient-rich deep water with the

FILTER-FEEDER
The basking shark moves through the water with its huge mouth open, filtering plankton from the water.

surface layer (*see pp.214–15*), and so in spring, when the amount of light hitting the surface of the water vastly increases, conditions are perfect for the growth of plankton. Huge spring blooms develop, attracting plankton-feeding species and their predators, and the waters become rich in marine life. Productivity drops again in summer, because, even though light conditions are perfect for plankton growth, there is little mixing between the surface layer and deeper water, and so nutrients become scarce.

ROUGH SEAS
Temperate seas can be rougher and colder than tropical and subtropical waters, but those who brave them are rewarded by the wealth of marine life on display.

TEMPERATE DIVING

Diving in temperate waters is not the crystal-clear, warm-water experience beloved of the coral reef diver, and requires more equipment (*see p.45*) than diving in tropical regions. However, some of the localized ecosystems within temperate seas, such as the majestic kelp forests (*see pp.210–11*) found in certain coastal regions, are extremely dramatic. When dived at optimum times in the season, temperate waters are rich in life. The seasonal blooms of plankton draw a range of migratory species, and also attract impressive predatory species, such as shark and tuna.

PLANKTON BLOOMS

Plankton are free-floating animals (zooplankton) and plants (phytoplankton) at the base of the marine food chain. When environmental conditions are optimal for their reproduction, they can multiply very rapidly, creating huge “blooms” of many millions of individual plankton. Where massive blooms of phytoplankton develop, the sea can literally turn green.

***Cyclops* zooplankton**

UNDERWATER FORESTS

The forests of giant kelp that grow in temperate seas are considered by some to be the most impressive marine environment of all. Although kelp—a brown alga—is extremely abundant in temperate waters throughout the world, true kelp forests are specific to the areas with marine conditions that support the growth of two kelp genera: *Macrocystis* and *Nereocystis*. These require reasonably clear water, a degree of water movement, a suitable substrate making up the sea bed, and a maximum temperature: most kelp forests will not flourish in water that exceeds 68°F (20°C) on a regular basis. Some species of kelp grow at a phenomenal rate, and to a truly colossal size. *Macrocystis pyrifera*, or giant kelp, can reach in excess of 165 ft (50 m), and can grow up to 25 in (60 cm) in a single day, making it the fastest-growing alga on Earth.

The best areas for the growth of kelp forests are off the west coast of the US and Canada; in the Cape region of South Africa; in Southern Australia; along almost the entire length of the west coast of South America; around much of New Zealand; and in southern Japan. For the diver, the attraction of these biological wonders is not simply the forests themselves, but also their numerous residents. The analogy with a terrestrial forest is a good one: activity takes place from the seabed up to the canopy, from specialist mollusks that bore into the kelp itself, through to pelagic animals such as rays that soar through the upper levels. As well as permanent residents, a kelp forest provides a nursery for many open-ocean species and a hunting ground for impressive predators. To dive a kelp forest on a day with good visibility as the sun dapples through the canopy overhead is an unmatchable experience.

SEA OTTER
Vital residents of kelp forests, sea otters help control populations of sea urchins, which if left to multiply would decimate the kelp.

SUBMERGED CANOPY
Invariably dramatic and teeming with aquatic life, kelp forests are the temperate water equivalent to the bustling reefs of tropical seas.

KELP BEDS
Huge numbers of marine creatures, large and small, make their home among kelp.

Polar waters

Although both the Arctic and the Antarctic conjure up visions of frozen desolation, below the ice and water surface lie regions of staggering abundance. Possibly the most challenging of all marine environments, the polar regions offer many surprises for the intrepid diver.

FROZEN ENVIRONMENT

Polar waters are found in the regions around the Arctic and Antarctic, though the precise lines of demarcation are blurred. Where polar waters start and temperate waters end varies between the poles. For the Arctic it is the 50°F (10°C) above-water July temperature boundary, while for the Antarctic it is seen as the line of the Antarctic Convergence, a zone where cold Antarctic waters sink below warmer northern currents.

BELUGA WHALE
Arctic diving "safaris" provide opportunities to dive with animals such as beluga whales and a number of seal species.

Both the Antarctic and Arctic have quite consistent water temperatures, because the low angle of the sun and the reflective qualities of the ice minimize the impact of solar radiation. The temperature of the water hovers around an extremely chilly 32°F (0°C), only just above the freezing point for seawater, which is 29°F (–1.8°C). However, although they may seem similar, the Antarctic and Arctic are actually quite different in terms of their physical geography and marine ecosystems.

POLES APART

The plants and animals of the Arctic and Antarctic differ considerably, situated as they are on opposite sides of the world. Antarctica has its own species of krill (some seven of them)—the small shrimplike creatures that are the bedrock of the food chain here. Swarming in huge numbers on the surface, they draw in a host of feeders—including the mighty baleen whales—during seasonal migrations.



Krill



The Antarctic is an isolated continent covered largely in ice: its nearest land masses are over 600 miles (1,000 km) away, and the entire continent is circled by an ocean current. The Antarctic Circumpolar Current is extremely significant, as it essentially cuts the Antarctic waters off from warmer waters farther north. The Arctic, by contrast, is mainly an area of ocean covered in a thick layer of ice, bordered by the land masses of North America, Europe, and Asia, and as such its waters are affected by temperature changes, land runoff, and shallow coastal currents.

ICE DIVER
There are more diving opportunities in the Arctic than in Antarctic waters. Diving under the ice demands a high level of expertise and special skills (*see pp.188–89*).

LIFE ON THE ICE

The adaptations that have evolved in animal life to cope with extreme polar environments are remarkable. There is a tendency toward gigantism—a larger body size keeps the relative body surface area to a minimum, and therefore the effects of heat loss through the skin are less pronounced. Fish have a high body fat content, and mammals have blubber and fur to insulate them, while behavior such as migration in the winter months means the worst conditions are avoided. The most extraordinary adaptations exist, perhaps, in the fish and invertebrates of polar waters: many have special “antifreeze” proteins in their blood to keep it liquid at low temperatures.

ICE SHELF CALVING SMALL ICEBERG
Up to 70 percent of all fresh water on Earth is held in the Antarctic ice cap. It sits on a huge land mass, while the Arctic is largely floating ice.

The open ocean

Only a tiny proportion of the world's oceans cover the shallows around land. Beyond, great tracts of open water plunge to abyssal depths. At first glance a featureless marine desert, this is actually a fascinating ecosystem containing some of the most impressive marine creatures.

A LAYERED WORLD

The oceans of the world are divided not only geographically, but also vertically, descending through the water column in distinct zones defined by temperature. Only the upper 650 ft (200 m) or so are heated by the Sun. Below this warmer surface layer, the temperature of the water can fall dramatically with depth in a layer of water called the thermocline. This layer of rapid temperature change is present in tropical waters year-round and in temperate waters in summer, but is not found in polar waters. Below the thermocline, the temperature continues to fall, but more slowly. Many animals find the dramatic change in temperature at the thermocline stressful, and are confined to either the warmer water above it, or the deep, cold water below it.

The deeper layers of the ocean are richer in nutrients than the surface layer; they are also colder, and so have a greater capacity for holding oxygen. Mixing of the layers—bringing oxygen-and nutrient-rich water into the surface layer—can be

LIFE IN THE OPEN SEA

Even in remote areas of open ocean, communities of living creatures thrive. In the Sargasso Sea in the North Atlantic, a vast rotating current propels floating *Sargassum* weed in an endless circular procession. The weed supports many invertebrate species and juvenile fish.

Sargassum weed



CAUGHT ON CAMERA
Open-water predators, like this blue shark, will investigate any new visitor to the environment.

caused by currents, storms, or other natural patterns of water circulation. When the nutrient-rich water is hit by sunlight, an explosion in plankton growth, or "bloom," occurs, creating regions of abundance as plankton feeders, and in turn their predators, congregate.

BUILT FOR SPEED
With their streamlined bodies and powerful sickle-shaped tails, dolphins are perfectly designed to hunt even the fastest-moving prey.

LIFE AT THE DEEP END

Pelagic animals (those of the open ocean) have developed remarkable physical and behavioral adaptations to suit their demanding environment. Massive vertical migrations take place at night, when marine animals move into the well-stocked surface layers, hidden under cover of darkness from predators that hunt by sight. However, many of the predators of the open ocean boast a battery of senses for detecting prey at long range, and investigate any object in their vast territory for its food potential. These opportunistic hunters include the blue shark, marlin, and tuna, some of the most awesome and beautiful animals in the oceans. The cold-blooded tuna can heat its blood to warm its muscles, allowing deadly bursts of speed.

Freshwater environments

Branching out from the sea to explore freshwater environments opens up a whole new range of dive sites to discover, from Icelandic ravine lakes to Mexican caverns or the Florida swamps, each with fascinating, freshwater-specific animal and plant life.

LAKES AND RIVERS

The first thing any diver accustomed to seawater will notice in a freshwater system is the difference in buoyancy. The salt content of seawater—around 35 parts per thousand—makes it denser, and thus a naturally more buoyant environment for the diver than freshwater. Consequently, you will find that you need to carry considerably less weight. The lower salt content also means that equipment suffers less damage through corrosion.



PRIVATE PROPERTY
Some of the most scenic rivers and lakes are privately owned, so it is important to check whether permission is required before you dive.

There are a number of logistical and safety issues specific to freshwater diving. Some of the more adventurous dive sites are high-altitude lakes, and require the use of special tables or a dive computer to avoid decompression issues. Lakes are susceptible to land runoff, and may quickly become murky in poor weather, while rivers may swell rapidly in adverse conditions, creating dangerous currents. Rivers and lakes may also support disease, notably Weil's disease and bilharzia, particularly in regions of dense human population.

African lake fish

Despite these drawbacks, with some research and strategic preparation before a dive, local rivers and lakes can provide a perfectly viable and exciting alternative to sea diving. Freshwater systems become anoxic (lacking in oxygen) at depth, and subsequently support very little life. This means that shipwrecks do not deteriorate as quickly—because the organisms that would usually destroy them cannot function—so deep lakes can offer impressive collections of well-preserved wrecks.

NATURE ON DISPLAY
Freshwater species are generally unaccustomed to divers, creating wonderful opportunities for close observation and encounters.

LAKE DIVING
Exploring a freshwater lake can provide a fascinating and exhilarating alternative to sea diving. Here, in the beautiful Blindsee mountain lake in Austria, divers can explore an underwater forest of fallen trees.

Mammals

Of the 5,000 species of mammals on Earth, around 2.5 percent are found in marine environments. These warm-blooded aquatic animals are perhaps among the most charismatic and approachable creatures you will encounter on any dive.

WARM-BLOODED LIVING

Mammals have a number of features that make them unique in the animal kingdom. First, they are warm-blooded, which means that they are able to regulate their internal body temperature. Most are covered in hair (apart from Cetaceans) and all, except monotremes like the duck-billed platypus, give birth to live young and feed them on milk produced by milk-secreting glands. At least three orders of mammals include species that spend the majority, if not all, of their lives in water: Cetaceae, which includes whales, dolphins, and porpoises; Carnivora, including the pinnipeds (seals, sea lions, and walruses) and otters; and Sirenia—manatees and dugongs.

WHALES, PORPOISES, AND DOLPHINS

Cetaceans spend their entire life in water, even though, like other mammals, they have lungs and need to breathe air to live. They are divided into two main subgroups—Mysticeti and Odontoceti—based on their adaptations for feeding. Mysticeti are filter-feeding baleen whales, such as northern and southern right whales, humpback whales, and blue whales.

SOUTHERN RIGHT WHALE
There are few more impressive sights than a whale's flukes breaking the ocean's surface.

SUPREME PREDATOR
The majestic orca or killer whale is a versatile hunter, catching a range of prey from fish to seals and even whales and birds.

Odontoceti, by contrast, have teeth and include some species of whales and all dolphins and porpoises.

AQUATIC CARNIVORES

Pinnipeds are aquatic mammals that spend some time on land, particularly for breeding. There are 33 species, including seals and fur seals, sea lions, and walruses. These carnivorous mammals have webbed feet, enabling them to move on land and in the water. With their long front flippers, fur seals and sea lions are able to walk on all four flippers on land.

Sea otters are the largest members of the mustelid or weasel family and are most commonly found off the coasts of California, Alaska, and Russia. Unlike other marine mammals, they have no insulating layer of blubber, but have the thickest fur in the animal kingdom. They are one of the only mammals, other than primates, known to use tools, utilizing stones and other items to crack open shellfish and pry prey from cracks in rocks.

THE SIRENIANS

It is rare to encounter manatees (*see also p.309*) and dugongs. These fascinating migratory mammals, belonging to the order Sirenia, typically reach adult sizes of around 10 ft (3 m) in length, and have front limbs in the shape of flippers and no hind limbs. Despite their imposing size, manatees and dugongs are placid, herbivorous creatures that spend most of their time grazing.

SEALS

Commonly seen on dives and at the water surface, seals tend to be found close to shore and in the more remote areas of the world, such as the Arctic and Antarctic, where they can feed and reproduce without disturbance. There are 18 species, the largest of which is the elephant seal. Seals are efficient swimmers, using their rear flippers for propulsion and their front flippers for steering. These lively mammals are fun to swim with but have sharp teeth and can be aggressive during the pupping season.

Harbor seal

Sharks, skates, and rays

Like other cartilaginous fish (also known as the Chondrichthyes), sharks, skates, and rays have a skeleton made of flexible cartilage rather than bone. Collectively known as the elasmobranchs, they have between five and seven paired gill openings, and nostrils beneath the snout.



SHARK SPECIES

There are around 500 known species of sharks, ranging in size from the giant whale shark, at up to 65 ft (20 m) in length, to the minute lantern shark, which measures just 12 in (30 cm). All sharks have pectoral fins attached behind the gill openings, a large caudal (tail) fin, and one or two dorsal fins—a basic body plan that has changed very little in hundreds of thousands of years. The jaws are lined with many rows of teeth, which are continually renewed throughout the shark's life. The tough, rough skin of a shark is covered by dermal denticles—tiny scales that minimize drag (friction with the water) when swimming. Sharks propel themselves by sweeping their caudal fin from side to side. Unlike most other fish, sharks have no swim bladder, so they must swim continuously or they will sink. They also need to maintain the flow of seawater over their gills so that they can extract oxygen for respiration.

Sharks have extraordinary sensory powers. Their highly developed senses of smell and taste are used to detect potential prey, and they have excellent vision. In addition, they can sense changes in water pressure caused by the movement of other animals using their lateral line system. This consists of fluid-filled channels along the sides of the body that are lined with sensory hair cells. Sharks can also detect the minute electrical fields produced by other living animals, using electrosensory organs called ampullae of Lorenzi, which are located on the head.

LEOPARD SHARK
The leopard shark can be found at depths of up to 100 ft (30 m) and is often seen lying on sandy bottoms.

TIGER SHARK
Although rarely encountered, the tiger shark is one of the most voracious shark species. It feeds on large fish, turtles, and sea birds.

FOOD AND FEEDING

All sharks are carnivores, but they feed on a wide range of prey and use a variety of feeding techniques. Filter-feeders, such as basking, megamouth, and whale sharks, sift plankton from the water as they swim. Many bottom-dwellers, including wobbegongs and angelsharks, lie camouflaged on the seabed ready to ambush passing fish, while others, such as leopard sharks, feed largely on seabed invertebrates. Some species, such as white-tip reef sharks, feed cooperatively, hunting in packs and actively pursuing prey. The mako and the great white shark tackle large prey such as seals, swordfish, other sharks, porpoises, and sea turtles.

Although sharks are the top marine predators, only a few species are potentially dangerous to people, and attacks on humans are rare. In fact, humans pose far more of a threat to sharks, with many shark species currently endangered, and some even facing extinction, due to overfishing.

SHARK REPRODUCTION



Egg case

During mating, the male uses his claspers (modified extensions to the pelvic fins) to transfer sperm to the female. The majority of sharks, including dogfish and leopard and tiger sharks, are viviparous, giving birth to fully formed offspring. Oviparous (egg-laying) species lay their eggs on the seabed, where the embryos are nourished by the yolk within the egg case. Catshark egg cases have long tendrils that twist around objects on the seabed. In other species, such as epaulette sharks, sticky filaments glue the egg cases to a secure site. All young sharks fend for themselves from birth or hatching.



Spiny dogfish

SKATES AND RAYS

The 600 skate and ray species share many of the features of sharks, but have a very different body plan. The gill slits are on the underside of the body. The pectoral fins are positioned above the gill openings, not behind them as in sharks, and are greatly enlarged and flattened to form "wings," while the caudal fin is reduced or absent.

Most skates and rays are bottom-dwellers, and are well adapted for life on the seafloor. Their flat body shape enables them to lie on the seabed unnoticed, and they have a downward-pointing mouth and eyes on top of the head. Spiracles (breathing holes) behind the eyes enable them to "breathe"—take in water to extract oxygen—when half-buried in the substrate. Most rays and skates eat invertebrates, such as mollusks and crustaceans, and small fish, but some are plankton feeders. They swim with strokes from their modified pectoral fins, in an undulating movement similar to a bird flapping its wings. Their tails are used for defense rather than propulsion: they have a stinger at the base of their tail, with short barbs that can inject venom into aggressors. Skates lack this tail barb.

Skates tend to be more common in temperate waters, and rays in the tropics, but the main distinction between them is in their reproduction. Rays produce live young, while skates lay eggs in leathery cases (often called "mermaid's purses").



THORNBACK RAY
Many species, such as this thornback ray, have a mottled or speckled coloring that camouflages them against the seabed.

MANTA RAYS
These large, filter-feeding rays sieve microscopic plankton from the water with their gill-rakers. Manta rays also eat small shoaling fish.



SPOTTED EAGLE RAY
This species uses its flattened, duckbill-like snout to dig up food from the seabed.

DIVING WITH RAYS

Manta rays, with their elegant, dancelike swimming motion, are perhaps the most popular ray species. They are also the largest of the rays, measuring up to 20 ft (6 m) across. They often congregate at special cleaning stations on the reef, where they allow smaller reef fish to pick tiny parasites off their skin. The flaplike lobes on either side of the mouth funnel plankton between their jaws as they swim. When not in use, the lobes are coiled up to make the ray more streamlined.

Other types of rays seen during dives include guitarfish, which have pointed heads and elongated bodies, and electric rays, which possess organs that can deliver an electric shock to incapacitate prey. Torpedo rays can discharge more than 200 volts—enough to stun a diver. Circular-bodied stingray species should also be treated with caution, since they have venomous barbs at or near the base of the tail. The sting's effect can be mildly painful to potentially fatal, depending on the species. Eagle rays, which also have venomous barbs, can be identified by their distinctive beak-shaped snout. They have powerful crushing teeth, large "wings," and a long tail.

Rays are docile animals, and despite their self-defense mechanisms, pose no real threat to the diver if unprovoked.

Bony fish

Bony fish, or Osteichthyes, make up about 95 percent of all fish species—more than 23,500 in number. These vary in every ocean that you will dive in, and there is a wealth of shapes, sizes, and colors, and intriguing behaviors and interactions for you to discover.



ROLE REVERSAL
Male seahorses have a pouch in which they incubate the eggs produced by the female.

COMMON FEATURES

Typical bony fish are torpedo-shaped and streamlined with a muscular tail. They have a caudal fin at the base of the tail for propulsion; a pair of pectoral fins, just behind the gills, for steering; an anal fin just below the tail; a pair of pelvic fins on the lower side; and, normally, one to three dorsal fins on the back. They are covered in a slimy secretion that reduces drag, and nearly all species have a covering of protective scales. They breathe using gills, although a few have evolved to use lungs as well as gills, and they are cold-blooded.

Bony fish are the most diverse and numerous of all the vertebrates. The earliest fossilized fish remains date from around 395 million years ago. All fish have a bony skeleton and a swim

NAPOLEON WRASSE
These lumbering open-water dwellers can become relatively tame in frequently dived sites.

bladder—an air-filled sac that aids buoyancy. The sexes are separate; most lay eggs, and fertilization is usually external.

There are two groups of bony fish. The Sarcopterygii (lobe-finned fishes), which have a fleshy lobe at the base of their fins that is leglike in appearance, form a small group that includes the coelacanth and Australian lungfish. These ancient fish probably gave rise to the amphibians. But by far the majority of bony fish belong to the Actinopterygii (ray-finned fishes). These fish have jointed bony rays that support their fins, and a symmetrical caudal fin.

The species you see will vary depending on your location. Fish identification can be rather like bird-watching, and many divers make checklists of what they have seen on each dive. An identification guide to the fish in the area that you are diving in will help to identify them correctly.

SAFETY IN NUMBERS
Moving as part of a large group means that each member of this shoal of barracuda—a ray-finned species of bony fish—is less likely to be eaten.

A WORLD TO DISCOVER

One of the greatest attractions of diving is the opportunity to observe an amazing range of fish species in their natural habitat. Bony fish display a wide variety of colors and patterns, especially those species found around coral reefs. As in some bird species, the male is often brightly colored and the female is drab in contrast. A male's vivid coloring may be used to attract a female in courtship displays. For example, the vivid markings of the male cuckoo wrasse become even more colorful in spring to attract females.

On reefs, you may also have the opportunity to observe some fascinating interactions between species. Animals such as manta rays and turtles regularly visit "cleaning stations," where smaller fish, such as cleaner wrasse, pick off algae, parasites, and dead tissue from their skin and even from inside their mouths. Anemonefish (also called clownfish) are able to live among the stinging cells of host sea anemones because they secrete a special mucus that protects them from being stung. In return for their sheltered home, they drop pieces of food and attract other fish that the anemone can feed on.

AVOIDING PREDATORS

You'll need keen eyes to spot some of the many fish species that are camouflaged or have unusual ways of avoiding predators. Some of these species are so elusive that they have only recently been discovered. Masters of disguise include the scorpion fish, which hides on reefs and is virtually indistinguishable from the coral and algae that surround it, but can deliver a nasty sting should you step on it. You may encounter flatfish, such as plaice and flounder, when diving in areas with a sandy bottom, but many are so well camouflaged to match the seabed that they are extremely hard to spot.

The holes and crevices in many reefs and wrecks provide ideal hiding places for fish such as moray and conger eels, with their slender body shape, large mouths, and menacing-looking teeth. Their hiding place is revealed when they gape to breathe (they have restricted gill openings). Eels have no pectoral or pelvic fins and use their long, muscled bodies to dart in and out of their lairs.



BLUE RIBBON EEL
This small, elegant moray eel from the Indo-Pacific is a shy creature: although it seems to gape threateningly, in fact, it is simply breathing.

ADAPTIVE CAMOUFLAGE

Bizarrely, flatfish start off life with a "normal" fish shape but then undergo a metamorphosis into their characteristic flat body form. One eye migrates to the other side of the head, the skull deforms, and the mouth becomes asymmetrical. The side of the body that sits on the sea floor becomes lighter and the upper side becomes darker, camouflaging itself in the color of the substrate.



SOCIABLE FISH

In open water you may encounter incredibly large fish like the Napoleon wrasse, which can reach a weight of nearly 300 lb (135 kg). In some areas the wrasse have been hand fed so often that they are friendly toward divers, though feeding them is discouraged. In more open water and around wrecks, you will see great shoals of fish such as sardines, barracuda, glassfish, and mackerel. Such ocean-going, or pelagic, fish tend to have pale bellies, silvery flanks, and dark-colored backs. This makes it hard for prey and predators to spot them—when viewed from above, the darker shade blends in with the color of the deep sea; viewed from below, the pale coloring merges with the light from the sky.



IMMUNE TO STINGS
A covering of protective mucus allows the anemonefish to shelter from danger among its host's tentacles.

Reptiles

Most reptiles live on land, but some are aquatic, notably turtles, terrapins, crocodiles and the related alligators and gavials, and sea snakes. These cold-blooded, or ectothermic, animals are mostly found in tropical areas, but some live in temperate regions.

BIRTH AND HATCHING

Reptiles are typically oviparous (the females lay eggs in which the young develop), although a few species are ovoviviparous (the young hatch from eggs within the mother's body). Egg-laying reptiles often build a nest in which to incubate their clutch.

One of the most prolific reptilian egg-layers is the turtle (order Chelonia), which has a hard shell that encloses and protects its vital organs. The head, tail, and flippers protrude, but many species can draw them in when threatened. Although they are air-breathing creatures, they only leave the water to breed and can lay as many as 200 eggs in nests excavated in sandy beaches.

THE SNEEZING IGUANA

The only lizard that forages for its food in the sea, the marine iguana has a curious habit of "sneezing" salt. The marine algae that forms the main part of its diet contains a lot of salt. A gland connected to the nostrils removes the salt from the body, and the iguana then expels it by sneezing, leaving its face white. This is one of the unique adaptations that allows marine iguanas to live and feed in seawater.



DIVER AND BANDED KRAIT
Related to cobras, sea snakes are venomous, but fortunately they are quite timid and if unprovoked are not inclined to attack humans.

SEA SNAKES AND LIZARDS

Although many snakes, such as the banded krait, swim in the sea, they usually return to land to breed. The yellow-bellied sea snake is the only true sea snake, the female giving birth in the water to up to ten live young, each about 10 in (25 cm) long. It can grow up to 3 ¼ ft (1 m) in length, and is black or dark brown in color with a bright yellow underside. This sea snake has spread across the Pacific from Southeast Asia to America, and gathers in huge numbers during the breeding season: a really big swarm can stretch for 70 miles (115 km). Marine iguanas, from the Galápagos Islands, are the only lizards that can tolerate salt water. Males may grow to a length of 4 ft (1.2 m) or more (almost half of which is the tail). They are harmless herbivores, feeding exclusively on algae growing on rocks near the shore. When feeding, they can remain submerged for up to an hour, especially in the warmer shallows, though dives of five or ten minutes are more common.

SALTWATER CROCODILES

The saltwater crocodile is the world's largest living crocodile; record lengths have been up to 23 ft (7 m), but 13–16 ft (4–5 m) is more common. This is the most dangerous species of crocodile, responsible for most crocodile attacks on people. It is found from eastern India and Bangladesh through Southeast Asia to Papua New Guinea and Australia, usually in brackish water in tropical estuaries, rivers, and swamps. The female lays eggs under a large mound of vegetation and stands guard over them for about 100 days. When the young hatch, she digs them out and carries them to the water. The hatchlings then live in nursery groups for about eight months, guarded by the adults.

RETURNING TO THE SURFACE
Turtles breathe air, like land-based reptiles. This one has a parasitic remora fish attached.

Marine invertebrates

Of all animal species on Earth, 95 percent are invertebrates (animals with no backbone), forming an incredibly numerous but often overlooked section of the animal world. Every major invertebrate group has an array of marine representatives.

AQUATIC ARTHROPODS

An arthropod is a type of invertebrate that has its body encased in a hard outer casing (the exoskeleton) and jointed appendages. Land-based arthropods include insects and arachnids, whereas most underwater species are crustaceans, a group that includes crabs, shrimp, lobsters, water fleas, copepods, and barnacles. There are about 39,000 species of crustaceans, most of which are marine, though some live in freshwater environments. They vary in size from the massive Japanese spider crab, with its leg span of 12 ft (3.7 m), to the tiny water flea, only about 9/1000 in (0.25 mm) long. But large or small, crustaceans all have certain things in common. They possess two pairs of antennae, three pairs of mouth appendages, and compound eyes on stalks. They also have three body segments—the head and the thorax, which are almost always fused and covered by a carapace (an outer shield), and the abdomen.

DRAWING NOURISHMENT FROM THE SEA
Bivalve mollusks, such as these mussels, feed by filtering organic matter from the water. Mussels live in nutrient-rich tidal areas.

MOLLUSKS

All mollusks, except the octopus, possess some form of calcium carbonate shell. There are three major marine classes of this group of invertebrates. Gastropods, with some 35,000 species, include whelks, limpets, sea slugs, and conchs. Many possess a shell but some, like the sea slug (or nudibranch), have lost theirs completely. Bivalves, such as clams, mussels, oysters, and scallops, have a shell in two pieces. There are 20,000 marine and freshwater species, the largest being giant clams up to 4 ft (1.2 m) across. Cepahalopods comprise around 600 species, including nautilus, squid, cuttlefish, and octopus. The cephalopods



SEA SCAVENGER
Crabs have a varied diet; these crustaceans feed on carrion, mollusks, and even other crabs.

DELICATE DRIFTERS
Transparent and serene, jellyfish are members of the cnidarian group of invertebrates.

include the largest invertebrate of all, the giant squid, which grows to a size of 52 ft (16 m). Cephalopods can swim in short bursts by squirting water from their bodies, but many, like the squid, use undulating fins for locomotion. The only shelled species of cephalopod is the nautilus: squid and cuttlefish have internal shells and the octopus has no shell at all.

CREEPING BEAUTY
Nudibranchs are colorful mollusks related to the common garden snail.

ECHINODERMS

Marine bottom-dwelling invertebrates, echinoderms have a hard, spiny skin and five-part radial symmetry. They lack a head, are often brightly colored, and are distributed throughout most of the world's seas. There are approximately 6,000 species of echinoderms, including starfish, brittle stars, sand dollars, sea urchins, and sea cucumbers, among others.

Most species of echinoderms reproduce sexually and have separate sexes. Fertilization is external—the eggs and sperm are shed into the water at spawning time. The floating embryo develops into a planktonic larval form. A few species reproduce asexually by fission (genetic copying of the parent organism into two or more clones).

Starfish may be circular, pentagonal, or the familiar star shape, with radiating arms. Under each arm are tiny tube feet, which the animal uses for walking.

UNDERWATER CHAMELEON
Cuttlefish are mollusks that can camouflage themselves by changing the color and texture of their skin.

The mouth is on the underside and the starfish feeds on living and dead animals as it moves along rocky surfaces and muddy bottoms.

Sea urchins, on the other hand, do not have arms. Instead, they have a shell of tightly fused plates, forming a sphere. They have long, prominent spines that protect them from predators, and have tube feet on their undersides, which are used for locomotion, respiration, and for trapping drifting particles of food.

CNIDARIANS

The cnidarian group of invertebrates, which includes the jellyfish, sea anemones, corals, and hydroids, are species with one of two basic body forms: medusae or polyps. Medusae, such as adult jellyfish, are bell-shaped with tentacles hanging down from the margins. They tend to be free-floating and solitary. Polyps, such as coral, sea anemones, and hydra, are tubular-shaped animals topped with tentacles. They frequently form colonies. Corals (*see also pp.204–05*) are unusual in that they depend on symbiotic algae to provide life-sustaining sugars. Medusae reproduce sexually, whereas most polyps reproduce by asexual fission. Cnidarians are unique in manufacturing cell-based stinging mechanisms, called nematocysts, in their tentacles, which are used to catch prey and in defense.

OTHER INVERTEBRATES

Comb jellies, which are bell-shaped creatures with vertical combs over their bodies, form another class of invertebrates—the ctenophores. The 5,000 species of sponges that live in both salt and fresh water belong to the phylum Porifera. Finally, there are over 8,000 species of segmented worms, which are classed as annelids.

PLANTS OR ANIMALS?

Many marine creatures stay rooted to a single spot for life. They posed a dilemma for early biologists who believed that mobility defined the animal state; this explains the common names of animals like the "lily of the sea" – in fact a crinoid. Other stationary animals include polyps, sponges, feather stars, and annelids such as fanworms. They are filter-feeders, and contain toxins to deter predators.

Feather star

Places to dive

Introduction

With increasing numbers of dive centers opening up around the globe, virtually the entire world is now accessible to the traveling diver. Following a few basic travel tips can stand you in good stead when transporting yourself and your dive gear to your destination.

TRAVEL OPTIONS

Most vacation destinations in coastal regions around the world provide some sort of diving facility. Indeed, the sport is now so convenient that you can turn up on the day, certification card in hand, and be decked out from head to toe with rented gear, before being guided around local dive sites. This is one of the greatest joys of the sport—the ability to visit different parts of the world and explore local sites with relative ease.

A step up from the more casual "just-passing-through" diving experience is the dedicated diving vacation. This is usually arranged through a resort-based dive operator, most of which will run a series of dives to local dive sites and offer a range of equipment for rent.

ICE DIVING
With many divers looking for more adventure in their diving, travel companies are offering challenging experiences, such as ice diving.

Developments in diving equipment over the last decade mean that most dive centers worldwide can offer a reasonable caliber of gear for rent. With the addition of local knowledge from a divemaster

who knows the waters well, you should be assured of a reasonable diving experience, regardless of the location. While most dedicated dive operators work to a high standard, there are a few rogue operators around, and you should be wary of any that show a cavalier approach.

Liveaboards provide an even more intense diving vacation. These are dive vessels designed for long-range trips to more inaccessible places, and they provide nonstop diving throughout the voyage. Liveaboards often offer supplementary courses, such as photography or natural history, hosted by resident experts. There are few marine dive destinations on Earth that are not accessible via liveaboards, and for many this is the finest way to experience extensive reef systems, remote sites, or sprawling island groups.

There is also a range of diving expeditions available in the modern travel market. Some are conservation-oriented and others more adventurous, such as seeking out big animal encounters or spectacular wrecks. Take the time to investigate the results and credibility of the group coordinating your project, since some that claim high ethical standards in conservation and research fall well short of expectations. There are others, of course, who perform genuinely valuable work, and for many divers this is the most rewarding and educational aspect of their entire diving career.

LIVEABOARD DIVE VESSEL
A liveaboard is essentially a floating dive center, and as such should have all the facilities on board to guarantee safety, comfort, and a memorable diving adventure.

LOCAL KNOWLEDGE
Most dive centers will be able to take you out on a boat and show you the best of the local dive spots.

EQUIPMENT RENTAL
Renting gear when you reach your destination is one way of lightening your travel burden and avoiding penalties for carrying excess baggage.

TIPS AND PRECAUTIONS

Diving overseas involves putting a great deal of trust in your host, be it a local guide or dive operator, or a leader of a trip or expedition. Following a few simple rules and precautions will make this a less daunting prospect, and may also ease the logistical problem of transporting expensive equipment across the world.

Deciding on a destination is the first step in planning a successful trip. Finding a location that really appeals to you, yet stays within your budget, will make your trip more rewarding than simply opting for the best-known sites or the cheapest deals. A brief period of research can reap huge rewards, and the range of information sources now available makes this a relatively simple exercise.

CHOOSING A DIVE BAG

While you can pack your gear in any case or bag you wish, most divers use bags specially designed to stand up to the rigors of dive traveling (*see p.79*). Soft bags, such as duffle bags, can fold up and be stashed away at your destination. Semirigid wheeled cases make carrying easier, but they are less flexible. Rigid bags are heavier, but offer better protection for your gear.

mares
mares

Semirigid wheeled bag

After identifying the aim of the dive trip, and the location to be visited, the next stage is to choose a host operator. Many local tourist boards can recommend registered operators who are known to work to a high standard. In addition, the PADI website (*see pp.34–35*) lists dive operators who have met a series of demanding criteria. This independent evaluation is invaluable in identifying the most professional centers and boats.

While rental equipment is generally of a good quality, many divers prefer to travel with their own gear. This is prudent, since unfamiliarity with rented gear can create an uncomfortable (and occasionally unsafe) diving experience. The diver also has the assurance of knowing that their own gear fits well, is functional, and has been tested recently.

Most airlines do not officially offer excess baggage allowances for dive gear (the dive industry is lobbying hard for a more reasonable approach to this issue), but a phone call in advance of the trip often works wonders—as does a courteous approach when checking in. Carry delicate items, such as regulators and dive computers, in your carry-on; the latter, in particular, may be affected by pressure changes in the hold of the plane.

Special diving insurance is vital, since you will not be covered by general travel policies. You need cover for damage to equipment in transit, medical care abroad (such as recompression treatment) and repatriation in the event of a serious diving incident. Policies usually cover divers to a depth of 100 ft (30 m)—more than adequate for most trips.

ONWARD TRAVEL
If the final leg of your trip or any travel between islands involves flights on small aircraft, check if the carrier imposes their own luggage restrictions.



RECOMPRESSION CHAMBER
The costs of recompression—if it is available at all—can be exorbitant, and many chambers will not treat divers without proof of insurance.

On arrival at your target destination, it is always advisable to carry out a few simple checks when diving with the host operator. All dive operators should have emergency oxygen supplies appropriate to the range and scale of diving they provide, as well as first-aid facilities and effective communications. It is worth making a quick visual inspection of the compressor facility—air certificates should be on display, but it is relatively easy to tell a clean, well-maintained compressor from a neglected one.

Europe

As a dive destination, Europe tends to be greatly underestimated by the international diving community. With an excellent diving infrastructure and well-established resorts and travel networks, Europe offers an eclectic mix of dive environments and a host of wrecks to explore.

TEMPERATE ZONE

Europe is, on the whole, a region of temperate waters, and this provides tremendous seasonal variation in the marine life around its coasts. The waters of western Europe are cold and rich in nutrients, and historically have been some of the richest fishing grounds on Earth. Migratory species move around the western edge of the continent, many borne on the undersea highway of the Gulf Stream. Consequently, the same dive site can be unrecognizable from winter to summer.

In diving terms, Europe is a continent of extremes, with Arctic diving to be had in the dramatic Norwegian fjords to the north, while subtropical diving can be enjoyed in the warm waters of the Mediterranean Sea to the south.

FISHING BOATS AT ALBUFEIRA, PORTUGAL
Europe's fish stocks have been an important resource for millennia, but overfishing has now put the populations of some species at risk.

Europe has long been the scene of intense shipping activity, a fact reflected in the thousands of wrecks that today dot the seabed. These wrecks represent a history of seafaring itself—from Viking longships, to all types of fishing vessels, and merchant fleets that foundered in violent storms. Sunken warships from virtually all of the continent's navies bear witness to the many wars that have ravaged Europe through the ages.

NORWEGIAN FJORD
Carved by glaciers millions of years ago, the fjords offer excellent dives in crystal-clear water, against a superb backdrop of snow-capped mountains.



WRECK OF THE *ZENOBIA*, CYPRUS
The Swedish ferry *Zenobia*, which sank in 120 ft (40 m) of water off Cyprus in 1980, is one of Europe's most impressive wrecks.

Wreck of the *Zenobia*

LARNACA HARBOR, CYPRUS

Mediterranean Sea
CYPRUS
Larnaca
Zenobia

A wreck for all grades of divers, the *Zenobia* offers shallow and deep dives, and a range of penetrations from gentle investigations through to technical explorations. Readily accessible, this wreck is one of the most popular dive sites in Europe.

ACCIDENTAL SINKING

In June 1980, the 10,000-ton Swedish passenger ferry *Zenobia* ran into difficulties off the coast of Cyprus. A problem with the autopilot caused the vessel to heel over and sink over the course of several days, giving plenty of time for the passengers to be evacuated, but leaving the cargo, including 135 trucks, to sink with it.

ESSENTIAL INFORMATION

WATER TEMPERATURE 70–79°F (21–26°C)

ECOSYSTEM Subtropical

WHEN TO VISIT Divers can visit year-round, but diving is at its best between March and October.

MUST-SEES Vehicle hold Number One; the bridge; the accommodations area.

REVERED WRECK

The *Zenobia* has become one of the most popular wrecks in diving because of its accessibility and the range of dives it offers. Divers can access the two main vehicle decks, the bridge, the accommodations area, and the restaurant. More extreme penetrations of the wreck include the engine room, although this is a multilevel, technical dive that requires careful planning and training. While not suitable for the novice, such dives are thrilling challenges. For those seeking a more sedate experience, the exterior of the wreck also provides a dramatic spectacle, with its props, huge hull, and superstructure still in excellent condition.

METAL MONSTER
The huge deck and holds are littered with fascinating debris from the ship's former life as a ferry, including many intact vehicles.



Medas Islands

CATALONIA, SPAIN



The Medas Islands offer a glimpse of how Mediterranean marine life was in days of old—large fish shoals, passing pelagics, densely colonized reefs, and fine coral formations. Closely protected, the islands have much to offer visiting divers.

CONSERVATION AREA

The Medas Islands were granted the status of a Nature Reserve in 1983, and have therefore enjoyed more than 20 years of official protection. The life around the islands reflects this, with perhaps a greater abundance of marine life and range of species than anywhere else in the western Mediterranean.

OUTWARD BOUND
A dive boat prepares to embark on the short voyage to the islands. Divers flock to the area to enjoy the profusion of marine life sheltering in the clear blue waters of the nature reserve.

DIVING THE ISLANDS

Located only 1 mile (1.6 km) off the north-eastern coast of Spain, the islands benefit from the nutrient rich runoff from the nearby Ter River. In addition, cold water upwellings on the craggy reefs around the islands create an oxygen-rich environment that allows marine life to thrive. As well as the usual Mediterranean species, such as scorpionfish, octopuses, and moray eels, local residents include large shoals of barracuda and bream, and there have even been sightings of eagle rays around the islands. Diving highlights include the famous Dolphin Cave—a 150-ft (46-m) tunnel set in a rock face—and the tiny islet of Carall Bernat. It is also reassuring to note the return of red coral to the seas around the islands, a natural resource that was for many years exploited by the jewelry industry. Though a small fee is levied by the authorities for diving around the Medas Islands, the success of the ongoing conservation policy justifies the extra expense.

ESSENTIAL INFORMATION

WATER TEMPERATURE 57–77°F (14–25°C)

ECOSYSTEM Subtropical

WHEN TO VISIT The best time to visit the Medas Islands is between March and September.

MUST-SEES Dolphin Cave; Carall Bernat; red coral formations; rare sightings of eagle rays.



Dusky groupers are just one of the species living under protection around the islands

Sardinia

CENTRAL MEDITERRANEAN, ITALY

ITALY
CORSICA
Rome
Sardinia
Cagliari

A rugged island in the middle of the Mediterranean, Sardinia has a dramatic geological past reflected in the caverns and caves that dot its coast. Although these are impressive features, Sardinia also has unique marine life and fascinating wrecks.

ROCKY COAST

The sharp reefs, dark overhangs, and craggy shoreline of Sardinia play host to an unusual array of marine life for the Mediterranean—a body of water not particularly famed for its marine diversity. Sardinia's geographical position means that it receives species from the Red Sea to the east (thought to be due to animals traveling through the Suez Canal), and the Atlantic to the west. Divers may encounter any of six species of wrasse, two species of groupers, wonderfully colorful sponges and corals encrusting rock walls, and a unique giant mollusk called the noble pen shell.

LOCAL CHARACTER
The common octopus is one of the key species found off the rocky Sardinian shoreline. This highly intelligent invertebrate is a common sight for divers.

NETWORK OF CAVERNS

This coastline is also famed for its caves and caverns. One system—Nereo Cave on the northwest coast—is particularly impressive, stretching for over 1,000 ft (300 m). As with all caves, caverns, and overhangs in Sardinia, such areas of low light are festooned in thick growths of red coral, for which the island is particularly well known.

There are also a number of fine wrecks to be dived. The best known of these is the wreck of the *Angelica*, a 4,400-ton freighter that ran aground on the island's jagged reefs in 1983, at Capo Falcone. The wreck lies at a maximum depth of 65 ft (20 m), so represents a relatively easy dive. The shallow location means that wind and weather have taken their toll on the wreck's structure over the years, but the site is worth a visit should you desire a change of pace from the sea caverns that dominate Sardinian diving. With many attractive beaches and towns along the coast, there is much to enjoy on shore, as well as beneath the waves.

ESSENTIAL INFORMATION

WATER TEMPERATURE 66–77°F (19–25°C)

ECOSYSTEM Subtropical

WHEN TO VISIT Sardinia can be dived year-round, but the summer months offer warmer, if more crowded, seas.

MUST-SEES Red coral; Nereo Cave; noble pen shells; wreck of the *Angelica*.

Ustica Island

SICILY, SOUTHERN ITALY



Ustica Island was described by no less an authority than Jacques Cousteau as the most beautiful island dive site in the Mediterranean. A tiny volcanic outcrop off the coast of Sicily, its qualities have seen it established as a Marine Nature Reserve.

SMALL IS BEAUTIFUL

Ustica Island may owe its undisturbed ecosystem to the fact that it was a penal colony until 1950. A tiny island—it has a total surface area of 3 sq miles (8 sq km)—it is nonetheless one of the most significant sites in the Mediterranean, to the extent that Italy's Academy of Underwater Sciences and Techniques is based here. The volcanic origins of the island (seen in the name itself—the Latin *usta* translates as a burnt red color) mean that the reefs around the island are particularly dramatic—with a craggy underwater topography featuring numerous caves, caverns, and overhangs.

ESSENTIAL INFORMATION

WATER TEMPERATURE 59–77°F (15–25°C)

ECOSYSTEM Subtropical

WHEN TO VISIT Diving takes place on Ustica Island year-round, but in winter the seas are relatively chilly.

MUST-SEES Red coral formations; the Colombara Bank; Medico Tunnel.

TOP DIVES

One of the best sites is Medico Tunnel, off the northwest of the island, which consists of a tall pinnacle with a tunnel passing directly through it. Another site of particular note around the island is the Colombara Bank—well known for its beautiful reefs and aggregations of large fish, such as barracuda and tuna.

SILVER SHOAL
Barracuda shoal in large numbers in the waters off Sicily, and are frequently sighted by divers visiting the Marine Reserve at Ustica.

The Hebrides

WESTERN SCOTLAND

Stornoway
North Sea
Hebrides
SCOTLAND
Glasgow
Edinburgh

The islands of the Hebrides have the feel of genuine wilderness about them. Precipitous mountains plunge into dark bays and craggy lochs, and white beaches lead to waving kelp forests, creating one of the finest diving regions in Europe.

RICH SEAS

The topography of the Hebrides lends itself readily to abundant marine life, with steep walls in the lochs, convoluted rocky reefs in the open water, and strong tidal movements through numerous narrow channels connecting the islands. Washed in oxygen-rich cold water, the islands are host to a dazzling array of marine life both large and small. Notable sites in the region include dives around Skye (particularly the small island of An Dubh Sgeir), the wrecks and reefs of the Sound of Mull, the famous dives around Oban (home to one of the most established and respected dive operations in the UK), and the newly discovered dive sites of the remote Summer Isles. The last include the wreck of the *Fairweather V*, a fishing vessel that sank in 1991 and is still intact and in good condition.

SURVIVING WILDERNESS
The characteristic rocky coastlines of the Hebrides are perhaps one of the last truly wild places in the United Kingdom.

TEMPERATE-WATER ECOSYSTEM

The Hebridean islands provide one of the richest and most complete insights into the marine life of a temperate-water zone. Visitors to the islands' rocky shores include itinerant whale and dolphin species, ling, conger eel, and a profusion of smaller native fish species. Colonial and encrusting organisms coat the rock walls, with anemones and sponges creating colorful and dramatic reefs. These are patrolled by otters—the Hebrides is one of the few dive sites in the United Kingdom where these fascinating mammals have largely taken to the sea. If conditions do not permit diving, the Scottish Sealife and Marine Sanctuary near Oban is well worth a visit. It has a spectacular aquarium and a busy otter and seal sanctuary.

A diver examines an undersea wall covered in dead men's fingers and plumose anemones

In the winter months, the islands of the Hebrides are subject to wild weather and cold water, with many dives becoming very demanding due to dark water and strong tides. In the summer months, the region really comes to life, with some of the beaches on the more remote islands becoming gateways to absolutely top-class shallow dives.

ANIMAL MAGIC

The shallow reefs just offshore in the Hebrides are some of the busiest temperate reefs anywhere in Europe, playing host to large edible crabs and lobsters, various species of cephalopods including cuttlefish and octopus, colorful nudibranches, and an array of fish species including some spectacular wrasse.

Larger animals encountered in the open seas around the Hebridean archipelago, as well as in its many dramatic coves and bays, include both the common and the Atlantic seal. Bottlenose dolphins are regular visitors to these shores, as are the more rarely seen rissos and white-beaked dolphins. Whale species that can be spotted include minke and pilot whales, orcas, especially around the islands of Coll and Tiree, and, if you are very lucky, sperm whales and humpback whales. There are large gatherings of basking sharks late in the year, although predicting when and where these will take place is almost impossible. Occasionally, sunfish and leatherback turtles also visit the region.

It is not only the animals that provide the excitement for divers visiting this region. The third largest whirlpool on Earth can be seen at the Gulf of Corryvreckan, between the islands of Scarba and Jura.

ESSENTIAL INFORMATION

WATER TEMPERATURE 46—64°F (8–18°C)

ECOSYSTEM Temperate

WHEN TO VISIT Diving is possible all year, but can be stormy in winter.

MUST-SEES Otters; wreck of the *Fairweather V* in the Summer Isles; An Dubh Sgeir in Skye.

Scapa Flow

ORKNEY ISLANDS, GREAT BRITAIN

Orkney Islands
Scapa Flow
North Sea
SCOTLAND
Glasgow
Edinburgh

The most famous wreck-diving location in Europe, Scapa Flow is a huge natural harbor amid the islands of Orkney off northern Scotland. Its fame stems from the fact that it was the site of the largest ship-scuttling action in maritime history.

ANCIENT HARBOR

Although Scapa Flow has been used as an anchorage since Viking times (the name derives from the Old Norse *Skalpeidfloi*, "Bay of the Long Isthmus"), one event ensured its fame in the diving world. After World War I, the German High Seas Fleet was impounded in Scapa Flow by the Allies. The fleet, consisting of 79 vessels, was imprisoned there for over a year. On June 21, 1919, Admiral Ludwig von Reuter, the German commanding officer, misread a newspaper headline and assumed that hostilities were about to resume and ordered his ships to be sunk by their own crews rather than let them fall into the hands of Allied forces.

GRAVEYARD OF SHIPS

The subsequent mass scuttling saw the majority of the fleet sunk, although the Allies managed to save 22 vessels by towing them into the shallows. Several of the German ships were salvaged in the intervening years, but three battleships, four light cruisers, and five torpedo boats still lie on the seabed. In addition to this rich array of wrecks, the British Admiralty sank 50,000 tons of shipping during World War I and II as blockships in the narrow entrances of the Flow to prevent raids by German submarines.

With several other wrecks of varying origins scattered throughout the Flow, the site has become a mecca for serious wreck divers. Although the larger German wrecks can be demanding dives, there are many easier options for the less experienced. The blockships in particular are splendid dives, sitting in shallow tidal channels, washed by cold nutrient-rich waters and teeming with marine life.

Notable wrecks in Scapa are the *Kronprinz Wilhelm*, the *Brummer*, and

ESSENTIAL INFORMATION

WATER TEMPERATURE 46–68°F (8–20°C)

ECOSYSTEM Temperate

WHEN TO VISIT Best diving conditions are between March and September.

MUST-SEES Wrecks of *Koln*; *Kronprinz Wilhelm*; *James Barrie*; *Gobernador Bories*; basking sharks; seals.

RUST IN PEACE
Not all of Scapa Flow's historic wrecks lie beneath the sea. Sandy beaches also bear witness to the past.

the *Koenig*. Amongst the blockships the *Gobernador Bories* has become particularly renowned, and the wreck of the trawler *James Barrie* is a magnificent sight at 131ft (40m)—sitting almost perfectly preserved on the sea floor.

WILD SCAPA

Scapa Flow has an extensive array of marine life, with the shallow wrecks in particular playing host to huge numbers of ballen and cuckoo wrasse, lobsters, conger eels, octopuses, and beautiful nudibranchs. Larger residents include grey seals, dolphins, and basking sharks in the summer months, and also the occasional visiting pod of orcas. Though the wrecks of Scapa Flow are, naturally, its greatest attraction, the marine life here is a welcome bonus.

VALUABLE SALVAGE

During the 1920s, the British salvage firm Cox & Danks raised many of the scuttled German battleships for scrap. Metal from the wrecks is still used today to make sensitive scientific instruments; their steel was forged before the age of atomic weapons tests, and so is a rare source of high-grade metal that is completely free of radioactive particles.

Salvage work at Scapa Flow

GLIMPSE INTO HISTORY
Divers at Scapa Flow can inspect the urchin-covered remains of German battleships scuttled shortly after the close of World War I.

The Isles of Scilly

ENGLISH CHANNEL, GREAT BRITAIN



Something of a well-kept secret among British divers, the Isles of Scilly are a cluster of tiny islands that sit at the tail end of the Gulf Stream. Rich marine life, lively reefs, and an abundance of wrecks make this archipelago a diver's paradise.

AZURE WATERS
The seas around the Scillies have a clarity more typical of southern France than southern England. This makes for excellent diving.

SPARSELY POPULATED

The Isles of Scilly (or the Scillies, as they are universally known) consist of 300 granite islands 28 miles (45 km) off the southwestern tip of England. Only six of the islands are inhabited, and even these could hardly be described as crowded. The islands are low-lying and very beautiful, with white sandy beaches fringing green islands.

The islands' position in one of the world's busiest shipping channels means that wrecks are abundant. The most recent wreck here was the cargo ship *Cita*, which foundered on March 26, 1997, leading to a bonanza of free goods for enterprising locals. This vessel is now an excellent dive, lying in 115 ft (35 m) of clear water. By contrast, the wreck of the *Eagle*, a British warship that sank in 1707, offers a glimpse into naval history, with cannons still visible on the seabed.

ESSENTIAL INFORMATION

WATER TEMPERATURE 46–64°F (8–18°C)

ECOSYSTEM Temperate

WHEN TO VISIT Diving is possible year-round, although in winter there can be violent storms.

MUST-SEES Inner Gilstone Rock; *Cita* and *Eagle* wrecks; gray seals.

OTHER ATTRACTIONS

As well as numerous wrecks to explore, divers also have access to splendidly busy reefs, and may even encounter larger species such as seals, as well as seasonal visitors, including basking sharks.

Seals are often encountered by divers off the Scillies

The Skelligs

COUNTY CORK, IRELAND

REPUBLIC OF IRELAND
Dublin
The Skelligs
Cork

Two rocks that jut out of the Atlantic at the eastern end of the Gulf Stream, the Skelligs are a beacon for wildlife in the rich seas off southwestern Ireland. This has created a world-class dive site in one of the finest dive regions to be found anywhere in Europe.

TWIN ISLANDS

The Skelligs sit 11 miles (18 km) off the southwestern coast of Ireland, and rise almost 700 ft (200 m) above the wild Atlantic waters below. They consist of two huge rocks—Skellig Michael and Little Skellig—around 1 mile (1.5 km) apart. The craggy faces and reefs of the rocks are washed by the waters of the North Atlantic Current, a flow of water that carries the tail end of the Gulf Stream. This brings warm waters from the mid-Atlantic, accompanied by occasional large species, such as dolphins. This current is the secret of the area's richness.

ESSENTIAL INFORMATION

WATER TEMPERATURE 48–72°F (9–22°C)

ECOSYSTEM Temperate

WHEN TO VISIT The best time of year to dive on the Skelligs is between April and September.

MUST-SEES The Pinnacle dive site; seal colony; gannets on Little Skellig.

HAVEN FOR MARINE LIFE

The rock faces of the Skelligs are coated in colorful encrusting organisms, such as anemones, sponges, and dead man's fingers. Every nook and cranny has an occupant, with huge edible crabs, lobsters, conger eels, and rocklings all jostling for position. In the kelp forests, wrasse and dogfish lurk, while mackerel and bass cruise the open waters. Larger residents include a healthy gray seal colony, as well as visiting basking sharks.

SHELTERING STONE
The isolated, rugged setting of Skellig Michael may look inhospitable, but beneath the water's surface, the area teems with vibrant marine life.

Lundy

BRISTOL CHANNEL, SOUTHWESTERN ENGLAND

IRELAND
ENGLAND
WALES
London
Lundy
English Channel

Lundy Island sits amid the powerful tidal stream of the Bristol Channel. Washed constantly by waters rich in nutrients, it is host to wonderfully busy reefs and the occasional larger visitor arriving from the great waters of the Atlantic, to the west.

PIONEERING RESERVE

Lying 10 miles (16 km) off the coast of Devon, Lundy is a craggy granite outcrop approximately 3 miles (5 km) in length. The richness of its reefs and the abundance of marine life saw Lundy established as the first Marine Nature Reserve in the United Kingdom.

There are two distinct faces to Lundy—the more exposed western shore, which faces the swells and storms of the Atlantic, and the more benign eastern shore. The topography of the granite creates wonderfully dramatic cliffs and reefs, with the regular tidal movement in the channel bathing these rock faces in nutrient-rich water.

GENTLE GIANT
The gaping mouth of the basking shark nets only the tiniest plankton for its food. The species is often encountered off Lundy in summer.

REEF POPULATIONS

Divers will encounter an array of British reef life around the island—lobsters, several species of wrasse, huge shoals of bib and pollack, bass, conger eel, and octopus. More unusual Lundy residents include anglerfish and red-banded fish—the latter being unique to the island. The island is also frequently visited by basking sharks and dolphins during summer months.

The wreck of the British warship *Montague* can be found on Shutter Reef at a depth of 15–50 ft (5–15 m). A 14,000-ton battleship, it ran aground in fog in 1906 while on exercises in the Bristol Channel. Intensive efforts to refloat it failed. Although the wreckage is scattered and broken, there remain piles of armor plate amid the kelp. The *Montague* was armed when it sank, so beware of live shells.

ESSENTIAL INFORMATION

WATER TEMPERATURE 46–72°F (8–22°C)

ECOSYSTEM Temperate

WHEN TO VISIT Visit Lundy from April to September for the best diving.

MUST-SEES Basking sharks and dolphins; the wreck of the *Montague*; Gannets Rock; Knoll Pins.

Norwegian Fjords

NORTHWESTERN COAST, NORWAY



Cold water, steep walls, and strong currents may not be everyone's ideal diving experience, but for some marine life, these are ideal conditions. Diving the Norwegian fjords is not for the faint-hearted, but the rewards are well worth the effort.

WILD COASTLINE

Norway's convoluted coast stretches for around 14,000 miles (22,000 km) in a series of jagged inlets, bays, and fjords, and is dotted with over 50,000 islands. Norway also has, in Sognefjord, the longest (140 miles/225 km) and deepest (4,430 ft/1,350 m) fjord on Earth.

There are many great dive sites along this gloriously wild coastline: one of the finest regions—and one that is gaining an international reputation for the quality of its diving—is Ryfylke, to the southwest. Diving the fjords requires previous experience and competence in cold-water diving, along with the relevant cold-water gear. The topography of the fjords creates steep walls colonized by kelp, dead men's fingers, sponges, and some rare deep water corals. Piked dogfish, skate, catfish, and numerous crustaceans are particularly abundant in Ryfylke. Seasonal highlights include migratory visits from salmon and their attendant predators, such as orcas.

ESSENTIAL INFORMATION

WATER TEMPERATURE 36–68°F (2–20°C)

ECOSYSTEM Temperate

WHEN TO VISIT The fjords can be dived year-round, but winter months can present cold, challenging conditions.

MUST-SEES Pulpit Rock; Kjerag Wall; Lysefjord; visiting orcas.

DRAMATIC HORIZON
The plunging walls of the fjords, both above and below the water's surface, set the tone for this rugged and beautiful destination.

Iceland

NORTH ATLANTIC

Akureyri
ICELAND
Höfn
Reykjavík

Born from the depths of the sea itself, Iceland is still a youngster in geological terms. The country's volcanic past provides some unique dive sites, including the opportunity to explore the marine life around a hydrothermal vent.

VOLCANIC BIRTH

Iceland was formed by volcanic action on the Mid-Atlantic Ridge, and has a surface area of just over 38,600 sq miles (100,000 sq km). The island is still experiencing an extraordinary level of volcanic activity, with 30 eruptions recorded in the last 200 years. Iceland's coastline is classically volcanic, bristling with craggy inlets, dramatic cliff and rock formations, and fissured reefs.

There are two diving experiences in Iceland that are not found anywhere else in the world. The first is the legendary Strytan hydrothermal vent, which rises from a depth of 230 ft (70 m) to within 50 ft (15 m) of the water's surface. Divers can see—and indeed feel—the hot water rising from the vent while enjoying the diverse invertebrate and fish life drawn into this oasis of warmth in an icy sea. The second is Silfra, a water-filled ravine in Thingvellir National Park. This is another dive that gives a marvelous insight into Iceland's fiery origins. Part of a huge rift in Earth's crust between the Eurasian and American continental plates, Silfra is filled with glacial meltwater that has been filtered through lava for decades, giving famously crystal-clear visibility.

ESSENTIAL INFORMATION

WATER TEMPERATURE 34–46°F (1–8°C)

ECOSYSTEM Temperate

WHEN TO VISIT Diving in Iceland is at its best in summer, between June and September.

MUST-SEES Strytan hydrothermal vent, Silfra in Thingvellir National Park.

ICELANDIC COASTLINE
The dramatic geological eruptions that gave birth to Iceland are evident in its craggy and forbidding cliffs and wild shores.

White Sea, Russia

NORTHEASTERN RUSSIA

Barents Sea
White Sea
Arkhangelsk
FINLAND
RUSSIA

The White Sea is one of the most beautiful of the seas of northern Russia, and the only place in Russia where you can dive under the ice. The marine environment here is relatively untouched by human activity and the diving is superb.

FROZEN WORLD

Diving beneath ice is exciting and adventurous, and the visibility—anything from 50 to 165 ft (15–50 m)—can be stunning. The water is not affected by waves (due to the protection of the ice), and low light conditions mean that algal growth is minimal. The water in the White Sea, which lies across the Arctic Circle, is frozen from November until April, but the best time to go is in mid-March. Any earlier and the temperatures are very cold, far below zero; any later and the ice has retreated and you cannot get to the best dive sites. The Gulf Stream warms some of the waters farther north, preventing them from freezing over.

DENIZEN OF THE ICY DEEP
A diver comes face to face with a gorgonocephalus—or, more dramatically, "gorgon's head"—a bizarre form of basket star common in the White Sea.

RARE ORGANISMS

The White Sea offers plenty of life to see and photograph: for example, there are some 80 species of fish, around 30 species of nudibranchs, and five species of seals. Shoals of tiny comb jellyfish also form an extraordinary sight, the light glinting off them in a million tiny rainbows. It is possible to encounter beluga whales, and occasionally orcas and Greenland sharks, which venture into these waters.

In addition to some great diving, there are possibilities of ice snorkeling in fast-flowing rivers and among the icebergs and, looking to the skies, witnessing the stunning beauty of the atmospheric phenomenon known as the aurora borealis, or northern lights. Also within excursion distance of dive sites on the east coast is Star City, the Russian cosmonaut training facility; you can even arrange to dive at the hydrospace laboratory at the MIR Space Center, used to prepare cosmonauts for the weightless conditions of space.

ESSENTIAL INFORMATION

WATER TEMPERATURE 31°F (–0.5°C) at the surface to 27°F (–3°C) deeper down

ECOSYSTEM Polar

WHEN TO VISIT Diving is best in mid-March (*see also, above*).

MUST-SEES Beluga whales; seals; aurora borealis; cosmonaut facility.

Africa and the Middle East

A continent synonymous with adventure and exploration, Africa offers spectacular shark encounters and many miles of unexplored reef. The Middle East boasts the Red Sea, perhaps the most famous of all places to dive, with a highly developed dive industry to match.

AFRICAN HIGHLIGHTS

South Africa is renowned throughout the world for big animal encounters—in particular with the great white sharks of the Cape—and for the epic shark dives to be had off Natal. The latter is also the scene of one of the greatest spectacles in the marine world—the legendary Sardine Run, where gigantic sardine shoals move slowly up the coast, harried by dolphins, whales, sharks, seals, and gannets.

DESERT MEETS SEA
At many sites in Africa, the warm blue sea laps against a harsh, arid landscape of bleached rock.

Lying to the northeast of the African coast are the magnificently wild beaches and reefs of Mozambique and the islands off Kenya and Tanzania. Farther out to sea lie Mauritius, the Seychelles, and the Comoros, all offering diving of real quality on reefs influenced by the abundant marine life of the Indo-Pacific region to the east.

VIBRANT ECOSYSTEM
Africa’s varied reefs sport a profusion of colorful soft corals, which play host to a stunning array of marine life.

RED SEA RICHES

The outstanding gem of the Middle East is the Red Sea, perhaps the most heavily dived body of water in the world. From the northern resorts of Eilat, Ras Mohammed, Sharm El Sheik, and Dahab, through to the wilder southern sites like the Brothers and the coast of Sudan, this region provides superb reef diving, as well as varied wrecks, such as the famous *Thistlegorm.*

Despite its popularity, the Red Sea still has unexplored regions, and new dive sites continue to be opened, so it will always have much to attract divers.

CRYSTAL-CLEAR WATERS
One of the saltiest bodies of water in the world, the Red Sea is also renowned for its superb visibility.

Gansbaai

WESTERN CAPE, SOUTH AFRICA



Gansbaai offers a rare chance to see the ultimate marine predator. With an island packed with breeding seals just offshore, Gansbaai is one of the finest locations on Earth to get up close and personal with the great white shark.

AWESOME ANIMAL
Great white sharks cruise the cold waters near Dyer Island, on the hunt for their preferred prey, fur seals.

SHARK CENTER

Gansbaai initially appears to offer little as a dive destination, with a small harbor on a rocky shore that is frequently battered by large swells. It is only when the diver stands on the wharf and squints into the middle distance that the reason for this site's global fame emerges. A low island several miles offshore is the home of 60–90,000 fur seals, and proves irresistible to the great whites that cruise this region of South Africa. Great whites are one of the ocean's most formidable predators, growing up to 20 ft (6 m) in length. The great white's notoriety as a man-eater, however, is a misrepresentation of this fascinating creature, about which surprisingly little is known.

ESSENTIAL INFORMATION

WATER TEMPERATURE 52–63°F (11–17°C)

ECOSYSTEM Temperate

WHEN TO VISIT Year-round shark activity; numbers peak May to September.

MUST-SEES Cage diving with great white sharks at Dyer Island, plus seal dives in a few recommended areas.

MAIN ATTRACTION

The presence of the sharks has spawned a thriving industry, with thrill-seekers coming from all over the world to dive with the great whites. Only cage diving is permitted with the sharks, but it is possible to dive within the seal colonies around the island in certain regions that are considered safe by local dive operators. Farther afield, there are beautiful cold-water reefs covered in swaying fields of kelp, but there is really only one reason why divers visit Gansbaai—that most magnificent of marine predators, the great white shark.

Aliwal Shoal

KWAZULU-NATAL, SOUTH AFRICA



Aliwal Shoal is one of the greatest adventure dive sites on Earth. The excitement begins on the beach, with perhaps the most dramatic surf launch in the diving world, and ends with outstanding shark encounters above a thriving reef system.

CROSSROADS IN THE SEA

Aliwal Shoal is a mountain of sandstone that juts into the underwater highway of the Agulhas Current. The site is renowned for shark encounters, in particular the famous ragged-tooth sharks that lurk within the caves and caverns of the reef. There are also Zambezi sharks in great numbers at the right time of year, as well as more occasional encounters with tiger sharks, and, thrillingly, there are a few rare sightings of great whites. However, Aliwal Shoal has much more to offer than shark encounters, since the mixture of both warm water reef fish and temperate species creates one of the most diverse reef systems in all of southern Africa.

VISITING SPECIES

Added to the array of life are transient visitors, such as migrating humpback and right whales, as well as turtles and huge brindle bass. The dive site is also directly in the path of the Sardine Run, one of the most impressive marine migrations anywhere in the world's oceans. Sardine shoals travel more than 1,000 miles (1,600 km) in this great annual exodus.

ESSENTIAL INFORMATION

WATER TEMPERATURE 66–79°F (19–26°C)

ECOSYSTEM Subtropical

WHEN TO VISIT Ragged-tooth sharks in residence from July to October; Zambezi sharks can be seen October–April.

MUST-SEES Ragged-tooth sharks; Sardine Run; migrating whales.



SURF SAFARI
Dive boats often encounter heavy surf on their way to Aliwal Shoal, some distance off shore. Launching in these conditions is exhilarating.

Sodwana Bay

KWAZULU-NATAL, SOUTH AFRICA



The only coral reef dive site in South Africa, Sodwana is set in the heart of a national park in northern Natal. The reefs host more than 1,000 species of fish, as well as impressive transients, such as whale sharks, billfish, manta rays, and whales.

REMOTE REEFS

Sodwana lies in a beautifully remote region of South Africa, nestling right up against the border with Mozambique to the north. Simply getting to the site is something of an adventure, requiring a journey by four-wheel drive vehicle through wild bush on bumpy dirt tracks. Although the dive industry in Sodwana is well established, it is also closely monitored. Only three dive centers are allowed to operate in the region, to limit the number of divers on the reef and so protect the delicate coral reef ecosystem.

DIVERSE ATTRACTIONS

The four established reefs off Sodwana are named after their distance from the launch site, and are called Two, Five, Seven, and Nine Mile Reef. Each offers something slightly different, ranging from the most delicate of hard corals through to encounters with large ocean-going species including whale sharks. Although the journey to Sodwana is a considerable undertaking, the reward is nothing less than the finest coral reef dives on the continent.

ESSENTIAL INFORMATION

WATER TEMPERATURE 70–84°F (21–29°C)

ECOSYSTEM Tropical reef

WHEN TO VISIT Year-round diving, but visit October to February for a chance of sighting whale sharks at Sodwana.

MUST-SEES Seven Mile Reef; Nine Mile Reef; surf launch; whale sharks, mantas, and other visiting species.

Turtles of several species visit Sodwana

SURF AND SAND
Despite the fact that Sodwana Bay is fairly remote, the site can be busy. Dive boats often launch with an audience of waiting divers.

Protea Banks

KWAZULU-NATAL, SOUTH AFRICA



Even within the singularly robust South African diving community, Protea Banks is a dive site famed for thrills. A reef cut with deep gullies, overhangs, and caverns, and notable for its shark encounters, this is not a site for the faint-hearted.

ON THE PROWL
The tiger shark is a species quite regularly sighted around Protea Banks, often with remora fish in tow.

CHALLENGING SITE

Although Protea Banks does not boast the dramatic topography of nearby Aliwal Shoal (*see p.259*), it lacks none of the excitement. Indeed, there are many in the local diving community who consider Protea Banks more extreme than Aliwal—the reasons being the depth, the currents, and the terrific shark encounters. The top of the reef is, on average, deeper than Aliwal Shoal, with several dives in excess of 100 ft (30 m). The currents that sweep over the flat reef crest are also stronger, and several of the dives are exhilarating drifts over a considerable distance of undersea terrain.

SHARK SPOTTING

The final reason Protea Banks is so revered among the dive community in South Africa is its shark encounters. Not only can large numbers of ragged-tooth sharks be found here during their mating season, but there is a strong possibility of encountering tiger sharks or hammerheads. For several months of the year, divers can also be confronted in mid-water by large numbers of the Zambezi sharks. These magnificent predators follow game fish that arrive during the summer months.

ESSENTIAL INFORMATION

WATER TEMPERATURE 66–79°F (19–26°C)

ECOSYSTEM Subtropical

WHEN TO VISIT Ragged-tooth sharks can be seen from July to October; Zambezi sharks from October to April.

MUST-SEES Ragged-tooth sharks; Zambezi sharks; migrating whales.

Mozambique

SOUTHEAST AFRICA

AFRICA
Mozambique
Maputo
Indian Ocean
Cape Town

Wracked by decades of civil war, Mozambique was once a forgotten destination in world diving. The end of the conflict in 1992 prompted the gradual return of divers, and revealed the riches that lie in the blue waters off one of Africa's wildest coastlines.

ESSENTIAL INFORMATION

WATER TEMPERATURE 70–82°F (21–28°C)

ECOSYSTEM Subtropical

WHEN TO VISIT Year-round, but conditions are best from September to March.

MUST-SEES Potato bass; ragged-tooth sharks; bull sharks; humpback whales; whale sharks; manta rays.

NURTURING SEAS

The fast-moving waters of the Agulhas Current, which passes through the gap between the east coast of Mozambique and the island of Madagascar, are the source of much of Mozambique's great marine diversity. The reefs in this region are teeming with life, and although the entire coastline has dive sites of merit, there are certain regions that stand out, including Inhaca Island, Ponta do Ouro, the Bazaruto Archipelago, and Cabo San Sebastian.

FAR-FLUNG LOCATION

Mozambique is by no means an easy dive destination to access. Many of the sites to the south of the country require a sturdy four-wheel drive vehicle to cope with the dirt and sand roads, and the isolated operators and resorts are tucked in behind long stretches of deserted beach. However, Mozambique's dive sites offer ample reward. The southern region of the country has become well

known for encounters with huge potato bass and ragged-tooth sharks, whereas farther north, encounters with bull and tiger sharks are a distinct possibility. Humpback whales move through the area in the summer months, and the occasional dugong is sighted in the shallow estuaries along the coast.

The Bazaruto Archipelago on Mozambique's central coast is an excellent place to see whale sharks, while nearby Vilnaculos is an excellent site to encounter manta rays and dolphins.

BRIGHT FUTURE

Mozambique still has a primitive tourist infrastructure, particularly in the northern regions of the country. Malaria is also a significant factor, with most of the country affected at certain times of the year. Nonetheless, Mozambique is making tremendous progress as a tourist destination, with the country's diving rapidly establishing itself as truly world-class. Diving here can present challenges for the intrepid traveler, but the isolation and low tourist traffic can be seen as a real advantage in one of Africa's most rapidly developing dive destinations.

WAVE-SWEPT WILDERNESS

Mozambique has over 1,500 miles (2,400 km) of coastline, much of it sparsely inhabited. The southern stretches of coast are dominated by sandbars, estuaries, and swamps, while the wilder north is characterized by long beaches and cliffs. The entire coastline is tremendously dramatic and wild, and even the capital Maputo has the famous Inhaca Island—a site famed in the diving world for its large animal encounters—directly offshore. Dolphins, whale sharks, and manta rays all frequent this site.

Surf breaks on a stretch of coast

LARGER THAN LIFE
Enormous potato bass are often found patrolling the bustling reefs of Mozambique. This imposing species can be extremely inquisitive, and individuals often approach divers.

Seychelles

WESTERN INDIAN OCEAN



The clear waters of the Seychelles teem with abundant marine life, and offer those prepared to travel a bit farther a range of gentle reef dives on the inner islands. The outer islands have big walls, wild drifts, and large animal encounters.

A PATTERN OF ISLANDS

The Seychelles archipelago numbers 115 islands in total, although these are spread over a vast area of ocean hundreds of miles off the east coast of Africa. The Seychelles is divided into the inner islands and the outer islands, with the two groups over 680 miles (1,100 km) apart. The inner islands—including Mahe, the main island in the Seychelles—sit on a huge natural platform rising from the deep ocean around them. As such, diving here tends to be within the 30–100-ft (10–30-m) range, and takes place on shallow protected reef systems. Farther afield are the outer islands, including the Aldabras, a group of islands known as the “Galápagos of the Indian Ocean” due to their isolation and diversity of marine life. The diving here is more intense and suitable only for experienced divers. The reef cuts and walls create opportunities for tremendous drift-dives, in which divers are carried along by underwater currents.

ESSENTIAL INFORMATION

WATER TEMPERATURE 81–84°F (27–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT May to October.

MUST-SEES Large pelagic species in the Aldabra Group; shallow reefs and marine life around the inner islands, including Mahe.

Powder blue tang

TROPICAL VISTA
Balmy tropical beaches are typical of the Seychelles. Though remote, the islands offer tremendous attractions for the diver.

Mauritius

WESTERN INDIAN OCEAN

AFRICA
Indian Ocean
MADAGASCAR
Mauritius

The islands of Mauritius in the Indian Ocean are a popular vacation destination, but are not well known for diving. This is something of an oversight, since the islands' stark volcanic reefs harbor a rich tropical ecosystem and offer dives of real quality.

PLACE IN THE SUN
The shallow coastal waters and white sands of Mauritius make it a leading vacation destination, but it also offers great diving experiences.

VOLCANIC ORIGINS

Mauritius consists of two islands, and numerous smaller islets, 500 miles (800 km) east of Madagascar. Although relatively small, the islands have nearly 250 miles (400 km) of undulating coastline due to the craggy nature of the volcanic rock that makes up the island group. The seas are colonized by over 200 species of coral, creating reefs inhabited by around 450 fish species—a rich tropical ecosystem.

ESSENTIAL INFORMATION

WATER TEMPERATURE 70–82°F (21–28°C)

ECOSYSTEM Tropical

WHEN TO VISIT Diving takes place in Mauritius year-round.

MUST-SEES The Rempart Serpent and Cathedral dive sites; the unspoiled reefs around Rodrigues Island.

TOP LOCATIONS

Most diving in Mauritius takes place on the western coast of the main island; the eastern end of the island is exposed to the wind and waves of the open ocean. The Cathedral cavern with its resident porcupine fish is a must-see, and the Rempart Serpent site boasts a huge number of moray eels (it is reputed that 32 species have been seen here!). The region north of the main island, however, is becoming known as a good spot for encounters with some of the larger pelagic species, with regular sightings of tuna, wahoo, and marlin. The remote island of Rodrigues to the east offers a glimpse of some of the region's most pristine reefs—making an excursion well worth the effort.

The Brothers

NORTHERN RED SEA, EGYPT



Spectacular coral gardens have grown undisturbed around these two remote pinnacles of rock for thousands of years. Only accessible by liveaboard (*see p.237*), the Brothers dive site offers steep drop-offs and some terrific shark action.

REMOTE ROCK
Big Brother, the larger and more northerly of the two islands, is 1,300 ft (400 m) long and 295 ft (90 m) wide, and dominated by a lighthouse.

ISOLATED OUTCROPS

The Brothers consist of two large rocks, named Little Brother and Big Brother, around 1 mile (1.6 km) apart and 36 miles (58 km) offshore in the northern Red Sea. Rising from deep water, they provide dramatically steep walls as a foundation for bustling reefs, and the upwellings of nutrient-rich waters and swirling currents draw in fish species both large and small.

SHARK SPOTTING

In addition to the diversity and color of the reefs themselves, there are some tremendous shark encounters off the walls of the Brothers. Common species in the area include white-tip and gray reef sharks, although silver-tips, scalloped hammerheads, and oceanic white-tips are also frequently seen. If you are lucky, you may even encounter a thresher shark. Its scythe-shaped tail fin makes this species an unmistakable, if very infrequent, sight.

ESSENTIAL INFORMATION

WATER TEMPERATURE 70–84°F (21–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT Diving takes place on the Brothers all year.

MUST-SEES Oceanic white-tip sharks; scalloped hammerheads; wreck of the *Numidia*; (occasionally) thresher sharks.

WRECKED ON THE REEF

As an additional attraction to the site, two wrecks—the *Aida* and the *Numidia*—cling to the precipitous sides of Big Brother. The *Numidia*, a former cargo vessel, lies at a very steep angle on the northern tip of the rock, with which it collided in 1901. Its bow can be found in just 26 ft (8 m) of water, but its stern lies in the depths, at 262 ft (80 m).

Another victim of Big Brother was the Italian supply ship *Aida*, which sank in 1957 while carrying troops. Almost as impressive as *Numidia* and surprisingly intact, *Aida* is now heavily colonized.

Dahab

NORTHERN RED SEA, EGYPT



The coastal town of Dahab in southern Sinai is ringed by mountains and desert. The inhospitable landscape is in striking contrast to the splendid reefs and coral formations to be found just offshore—among which is the infamous Blue Hole.

DESERT HAMLET

Dahab lies on the Gulf of Aqaba, in the northeast of the Red Sea, only 50 miles (80 km) north of the busy dive resort of Sharm El Sheik. Clinging to the shore in a harsh, arid landscape, the town has a faintly frontier feel to it. There are several dive centers in Dahab, offering training to all levels of ability.

DIVING IN DAHAB

Within a short drive of Dahab are many excellent sites accessible from the shore, including the Canyon and the Bells. Both of these sites are dramatic examples of the twisted coral formations that seem to characterize this stretch of coastline, with deep gullies, impressive overhangs, arches, and swim-throughs. The legendary Blue Hole site is actually the top of a massive shaft that sinks 985 ft (300 m) into the reef. The lure of diving through a long passage to the outer reef at a depth of 165 ft (50 m) has caused many divers to perish in the Blue Hole, and the conventional wisdom for diving this deep arch is that it should only be attempted using technical dive techniques and equipment (*see pp.194–95*).

ESSENTIAL INFORMATION

WATER TEMPERATURE 70–82°F (21–28°C)

ECOSYSTEM Tropical

WHEN TO VISIT Diving takes place in Dahab all year, with water temperatures high throughout.

MUST-SEES The Blue Hole; The Canyon and The Bells; Gabr El Bint (by boat only).

SHELL GAME
A diver follows a turtle—at a respectful distance—as it conducts a slow tour of one of Dahab's colorful reefs.

Wreck of the *Thistlegorm*

NORTHERN RED SEA, EGYPT



Packed full of artifacts and lying in the clear waters of the Red Sea, the *Thistlegorm* is perhaps the most famous of all shipwrecks for divers. Its fame comes at a price, however, with great numbers of divers clambering through the structure every day.

THE CLASSIC WRECK

The *Thistlegorm* first came to the attention of the global diving community in the 1950s, when it was discovered and filmed by Jacques Cousteau. However, its location remained a secret until 1992, when it was rediscovered by recreational divers, and it has since become one of the most popular diving wrecks in the Red Sea.

The *Thistlegorm* was a World War II armed merchant vessel, 413 ft (126 m) in length, carrying supplies to the British 8th Army in North Africa. Packed with machinery and ammunition, it was spotted in the northern Red Sea by a German bomber on October 6, 1941. Two bombs entered its Number Four hold, causing a huge explosion that cut it in half; it sank immediately with the loss of nine souls.

TIME CAPSULE

A diver examines military hardware inside the wreck of the *Thistlegorm*

For many years after the *Thistlegorm* was sunk, British vessels would lower their flag as they passed its wreck, but today it has a happier role, having become a focus for diving in the Red Sea. The vessel's real treasure is its outstanding cargo of military equipment, which ranges from Lee Enfield Mark 3 rifles, wellington boots, Bedford trucks, and two Rolls Royce armored cars, to—perhaps most famously of all—racks of BSA motorcycles. On the deck stands one locomotive; another lies on the sea bed beside the wreck.

DIVE EXPERIENCE

In many ways, the *Thistlegorm* is the perfect wreck dive. Its bow lies just 50 ft (15 m) below the surface in clear waters, and no part of the vessel is below 100 ft (30 m); however, currents may be strong, and descent is usually made down mooring lines tied by the guide. Once inside the wreck there is a vast, serene, yet poignant underwater museum to explore, and the sheer size of the vessel means that thorough exploration requires several visits.

ESSENTIAL INFORMATION

WATER TEMPERATURE 68–84°F (20–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT Year-round. The wreck is best dived from a liveaboard.

MUST-SEES The captain's bath; BSA motorcycles; locomotive on deck; Bedford trucks; armored cars.

The *Thistlegorm* holds a unique place in divers' affections, though its popularity has become a drawback. It is only a five-hour cruise away from the Red Sea's busy diving center of Sharm el Sheikh, and in peak season it is not uncommon for more than 20 diving vessels to be moored over it at one time. The best time to explore the *Thistlegorm* is at dawn, when there is a chance to see this grand wreck with few others around, although this means finding a skipper who will travel through the night.

Although not as densely colonized as one might expect, the *Thistlegorm* wreck still has abundant marine life. This region has approximately 1,000 fish species, 17 percent of which are endemic to the Red Sea. Of particular note on the *Thistlegorm* are large numbers of lionfish, which lie in wait ready to ambush shoals of unsuspecting glassy sweepers, while overhead jack and barracuda sweep the superstructure for prey.



WEAPON OF WAR
A diver hovers above the distinctive deck gun on *Thistlegorm's* stern. There are strict penalties for wreck-stripping, so never be tempted to take a souvenir.

Asia

The tropical regions of this vast continent have always been highly praised by divers for the staggering richness of their marine life and their glorious reefs, but adventurous new diving opportunities are also beginning to open up to the north—even in Siberia.

REEFS UNDER THREAT

The geographical span of Asia, the largest continent, is reflected in the vast range of diving available. For many divers and marine biologists, the highlight is the famed "Triangle of Diversity"—a region in the Indo-Pacific that boasts the world's greatest diversity of coral and fish species.

The many thousands of islands of the Philippines, Indonesia, Papua New Guinea, and Malaysia are host to some legendary dive sites, with evocative names such as Sipadan, Lembeh, Tubbutaha, Komodo, and Kimbe. Sadly, while these are all dream destinations for any diver, destructive fishing techniques in the Indo-Pacific region, such as dynamite and cyanide fishing, are damaging some of these delicate ecosystems. In the Philippines, only 4 percent of all reefs remain unaffected by human activity, with up to 30 percent reported to be impacted beyond recovery. Beautiful pristine reefs can still be found in the Indo-Pacific, but when diving on these threatened reef systems, be mindful of your responsibility to minimize any impact your presence could have.

BEACH BASE
A dive base on a sun-kissed tropical beach can provide the ideal "chill-out" spot after an exhilarating dive.

RESPONSIBLE REEF DIVING
With Asia's reefs at risk, it is vital that divers follow the rules of responsible reef diving to conserve them for future generations.

BEYOND THE TROPICS

The classic perception of Asian diving tends to be the archetypal tropical island chain fringed by glorious technicolor reefs. Dive sites throughout the region, including the Maldives, the Andaman Islands, and the Similan Islands, are all justifiably famed for their extraordinary diversity and beauty, both above and below the surface.

However, although much of the diving in Asia tends to be concentrated in the tropics, there are some excellent dive sites to be explored farther north. One of the most notable is Lake Baikal in Siberia. This is the world's deepest lake, and the largest reservoir of fresh water on the planet's surface. Because of its size and varying depths, Lake Baikal contains a huge variety of ecosystems.

PYGMY SEA HORSE
A rare species found only on *Muricella* coral in Southeast Asia and Australia, the pygmy seahorse wraps its tail around coral branches and lies in wait for tiny crustaceans and larvae.

The Maldives

INDIAN OCEAN

Arabian Sea
INDIA
Maldives
SRI LANKA
Indian Ocean

Coming to prominence as a dive destination in the 1970s, the Maldives swiftly became established as a dream diving location. The extent of the archipelago, and its range of dive sites, ensures that it remains an essential stop-off at least once in a diver's lifetime.

ESSENTIAL INFORMATION

WATER TEMPERATURE 75–84°F (24–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT Diving takes place year-round in the Maldives.

MUST-SEES Gray reef sharks; hammerhead sharks; manta rays; whale sharks; turtles.

RICH ARCHIPELAGO

The islands of the Maldives are the crests of an undersea mountain range that plunges over 1¼ miles (2 km) into the deep waters of the Indian Ocean. The archipelago extends 475 miles (764 km) from north to south, and is 80 miles (129 km) across. This vast collection of islands is loosely divided into 26 major atolls, and although the islands are spread over 38,000 sq miles (98,000 sq km) of ocean, their land mass covers only 115 sq miles (300 sq km).

The Maldives offer a huge range of diving activities for those lucky enough to visit. Such is the abundance and delicacy of the remarkable reef systems throughout the Maldives that there are no less than 25 nature reserves and protected areas within the island group. The marine life around the islands is colorful and diverse, and includes over 700 fish species.

TOUGH CHALLENGES

Tourism and diving are vital to the economy of the Maldives, but both industries have had to recover from major natural disasters in the late 20th and early 21st centuries. El Niño—a periodic warming event in the Pacific Ocean—had a severe impact in 1997–98, when the hard coral on many reefs was bleached and killed by the rise in ocean temperatures. The islands were also hit by the 2004 tsunami, which destroyed much of the tourist infrastructure.

Fishing and diving boats ready for business on a Maldives quayside

Diving in the Maldives tends to be divided into drift dives on the outer reef, and dive sites within the atolls. The latter contain thilas, a local word meaning a coral platform rising almost to the water's surface, and kandus, which are smaller isolated coral outcrops and coral heads. The best drift diving is where cuts in the coral walls leading to the open sea channel tidal water through narrow gaps.

Most dives in the Maldives seem to include at least one encounter with white-tip reef sharks, and there are several sites where gray and black-tip reef sharks, as well as hammerheads, may be seen. Eagle rays and manta rays, too, are regularly encountered at the right time of year at certain sites, with whale sharks also returning to the same sites to make the most of seasonal feeding grounds. There are also five different species of turtles in the Maldives, the most common of which are the green and hawksbill turtles.

COLORFUL CORAL
A diver examines soft corals on one of the region's flourishing reef systems. The Maldives offer an incredible variety of quality dives.

Similan Islands

ANDAMAN SEA, INDIAN OCEAN

INDIA
THAILAND
Bangkok
Similan Islands
MALAYSIA
Indian Ocean

A tiny string of granite islands sitting off the coast of Thailand, the Similans are best explored by liveaboard dive boat, but with some of the best beaches in Thailand, they have a great deal to offer both above and below the water.

STONE AND SEA

The Similan Islands consist of nine large granite outcrops sitting 40 miles (64 km) off the coast of Thailand. They rise from the depths of the Andaman Sea, and run for 15 miles (24 km) north to south. Although the islands do have individual names, they are commonly known simply by numbers, starting in the south with Number 1 (Koh Huyong), and continuing to Number 9 (Koh Bangu) in the north.

They are characterized by steep granite undersea cliffs on their western shores, with more gentle slopes to the east, where, sheltered from the summer monsoon winds, the coral growth is particularly lush. Over 1,000 fish species swarm over reefs colonized by a dazzling array of soft corals. Brightly colored species, such as coral grouper, sweetlips, snapper, and blue triggerfish are present in great numbers and, from October to May, whale sharks and manta rays are frequently encountered.



SHARK SPOTTING
A diver observes a leopard shark, hovering above this beautifully patterned predator, which frequents the waters of the Similans.

The thriving reef systems around the islands were once threatened by overfishing as well as "dynamite fishing"—the use of explosives to kill and collect large numbers of fish—but the islands were declared a national park in 1982, and commercial fishing is now banned. The sweeping coral fields of Christmas Point are particularly spectacular, although they were slightly damaged in the tsunami of 2004. Other notable attractions include a dramatic maze of huge boulder formations at Elephant's Head Rock. The Similans remain well worth every hour of sea crossing required to visit them.

ESSENTIAL INFORMATION

WATER TEMPERATURE 79–84°F (26–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT Visit the Similan Islands between October and May.

MUST-SEES Whale sharks and manta rays; boulder formations at Elephant's Head Rock; Christmas Point.

Andaman Islands

ANDAMAN SEA, INDIAN OCEAN



One of the last great diving wildernesses, the Andamans are a truly unspoiled string of volcanic islands in the Bay of Bengal. Cloaked in rain forest and home to some of the last untouched tribes on Earth, they offer genuine diving exploration.

ISOLATED IDYLL

The Andaman Islands are sprinkled over 435 miles (700 km) of ocean, and define the western edge of the Andaman Sea. Although the archipelago consists of 572 islands, only 36 are inhabited. Over 80 percent of the land mass is covered in rain forest, home to tribes that have had very little contact with the outside world—in some cases, none at all.

The islanders do not run any commercial fishing operations to speak of, and therefore the steep walls and rich reefs of the region are home to a range of large marine animals in healthy populations not encountered anywhere else in the Andaman Sea.

ESSENTIAL INFORMATION

WATER TEMPERATURE 82–88°F (28–31°C)

ECOSYSTEM Tropical

WHEN TO VISIT The best time to visit is between November and May.

MUST-SEES Barren Island; Passage Island; large manta ray aggregations; steep lava walls; dogtooth tuna.

Diving takes place from November to May, and can either be from liveaboard dive vessels, or through a small number of operators based in the islands. Notable sites include the outlying islands of Passage Island, Narcondam, and Barren Island, which have barely been dived at all. Expect encounters with a range of shark species, huge dogtooth tuna, and feeding manta rays.

DIVER'S PARADISE
With no large-scale fishing fleet, the Andaman Islands have well-preserved reefs stocked with a fascinating diversity of marine life.



North Sulawesi

CELEBES SEA, INDONESIA



Indonesia has been termed the "Cradle of Diversity" by marine biologists, and with good reason. A recent survey counted more than 3,000 fish species here. Crowning it all is North Sulawesi, and the jewel in that crown is the Lembeh Straits.

CONSERVATION IN ACTION

North Sulawesi is formed by the long, thin peninsula that juts out from Sulawesi Island into the Celebes Sea. The marine species diversity of this region is unparalleled, a fact recognized by the locals, who have set up a number of reserves, and by the divers who flock here. The careful approach to the marine environment here by local government means that 90 percent of the coral cover is alive and in good condition, a remarkable statistic considering the pressure the remainder of the Indonesian archipelago experiences from destructive fishing methods.

NATURAL TREASURES

The Lembeh Straits is the channel between the island of Lembeh and the northern tip of Sulawesi. It is quite a shallow body of water—ranging in depth from 16 ft (5 m) to 98 ft (30 m)—so divers need to be aware of the large vessels that pass regularly overhead, as well as the periodic strong currents.

But while at first glance this may seem merely an unprepossessing shipping channel, closer inspection reveals a world of tiny riches.

ESSENTIAL INFORMATION

WATER TEMPERATURE 74–82°F (23–28°C)

ECOSYSTEM Tropical

WHEN TO VISIT Year-round; optimum period between May and November.

MUST-SEES Panguilingan; Lejuan II; Mandolin; muck diving for ghost pipefish; pygmy sea horses; mimic octopus.

Camera in watertight plastic housing

MACRO LIFE IN SULAWESI

The magic that draws divers to this area is the extraordinary range of tiny but beautiful reef animals that can be found in the shallow coastal seas off North Sulawesi. The sheer diversity of "macro life" (small marine creatures) here, and the sometimes bizarre forms it takes, has led to the area being dubbed "God's wastebasket." Outlandish species like the hairy frogfish make amazing photographic subjects.

A hairy frogfish gapes in the current

The Straits have a big name for small things—this is the finest site in the world for encountering the most exquisite, delicate, and unusual inhabitants of tropical seas. Diving in the Lembeh Straits goes by the unpromising name of "muck diving"—so called because of the dark sand that covers the seabed and the necessity to examine it closely for target species during the course of a dive. But the effort involved in diving here is well rewarded. Mimic octopus, pygmy sea horses, ghost pipefish, leaf fish, frogfish, and blue-ringed octopus can all be found here.

CONSERVATION AREA

The Bunaken Marine Park is one of the driving forces for conservation on North Sulawesi. It surrounds five islands, on which are a few small fishing villages, and covers over 290 sq miles (750 sq km). The park offers fantastic muck diving and also some tremendous walls, the most notable of which are Lekuan II and Mandolin on Bunaken, and Panguilingan in Mahado Tua.

VOYAGE OF DISCOVERY
An indigenous fisherman setting out in a traditional canoe. Many divers eschew the clear surface waters for the pleasures of muck diving.

Papua New Guinea

WESTERN PACIFIC



A location that still epitomizes diving exploration, Papua New Guinea offers a hugely exciting experience for the intrepid dive tourist. A vast region with numerous undived reefs and islands, Papua New Guinea is a real adventure.

OUTER LIMITS

For many years, Papua New Guinea drew only the very boldest pioneers of adventure diving and extreme tourism. Made up of 600 islands, the reputation of this region as a wild and untamed part of the world is well founded. Papua New Guinea has 4 million inhabitants, divided into 1,000 tribes that speak 700 different languages. Spread over the 177,600 sq miles (460,000 sq km) of the island group, many of these indigenous tribes knew nothing of the modern world until very recently, with one tribe only making contact with the outside world in the late 20th century. Doubtless, others—as yet unknown—exist in the rugged Highlands, with much of the main island of New Guinea consisting of mountainous rainforest with a maximum elevation of 14,760 ft (4,500 m). While most visits to Papua New Guinea are trouble-free, travel after dark is not advised, and in towns such as the capital, Port Moresby, the risk of robbery and violent crime must be taken seriously. Trips are best arranged with well-established diving operations who can provide guides and transportation to the coastal diving regions, where the risks are significantly lower than in poor urban areas.

PRISTINE REEFS

The shallower regions of Papua New Guinea's coastline are the site of some fantastically complex reef formations, with perhaps the most famous being Kimbe Bay on the western coast of New Britain. Another dive site that has gained a reputation for providing particularly dramatic reefs and tremendous diversity is Eastern Fields, in the northern limits of the Coral Sea. This remote site can only be reached by ocean-going vessels and remains relatively unexplored.


Vibrant coral reef in Papua New Guinea

RICH SEAS

The good news is that the rugged terrain of the land frequently extends below the surface of the water, and Papua New Guinea is notable for the fact that its seas reach abyssal depths only a short distance from shore. This creates tremendous drop-offs and steep walls, which are inhabited by a bewildering array of species. The region has twice the number of fish species as the Red Sea, and ten times the coral species of the Caribbean.

SUNKEN HISTORY

In addition to this extraordinary species diversity, the area has some extremely fine wrecks, most of them relics of fierce



ESSENTIAL INFORMATION

WATER TEMPERATURE 75–82°F (24–28°C)

ECOSYSTEM Tropical

WHEN TO VISIT Diving takes place all year in Papua New Guinea.

MUST SEES Submerged atoll at Eastern Fields; marine life in Kimbe Bay; World War II aircraft wrecks in Milne Bay.

fighting in the region during World War II. Rabaul, Kavieng, Loboata, and Madang all provide excellent wreck diving, with aircraft debris littering the seabed in certain areas, like Milne Bay.

Diving throughout the archipelago is becoming more accessible due to the presence of a number of established diving operators in the more renowned dive sites, and the increasing range of liveaboard operators now pushing into some truly remote regions. Nonetheless, there are still underwater areas of this extraordinary island group that remain completely unexplored. In a world that seems to become smaller and smaller with each passing day, it is an exciting thought that such places still exist for us to discover. By taking a responsible approach to venturing off the beaten track, divers can help preserve this region, and by doing so ensure a steady stream of new adventures for many years to come.

GHOSTLY REMAINS
Wreckage of aircraft lost during World War II is a notable sight in the waters off Papua New Guinea. The area was the scene of battles between Allied and Japanese forces.

The Philippines

SOUTHEAST ASIA

Manila
Philippines
VIETNAM
MALAYSIA
BORNEO

The Philippines undoubtedly offer a world of diving possibilities. Although destructive fishing techniques have taken their toll on many reefs, local legislation and a realization of the benefits dive tourism can bring to the local economy offer a chance of recovery.

ESSENTIAL INFORMATION

WATER TEMPERATURE 75–81°F (24–27°C)

ECOSYSTEM Tropical

WHEN TO VISIT Best diving conditions are between April and November.

MUST-SEES Tubbutaha Reef; Jessie Beazley reef; Coron Bay; Apo Island; Puerto Galera.

RESTORING LOST REEFS

Consisting of 7,107 islands spread over 116,000 sq miles (300,000 sq km), the Philippines comprise one of the most bountiful regions on Earth in terms of species diversity, with at least 2,000 fish species recorded throughout the archipelago. However, in many areas, complex and delicate reef systems have been almost completely destroyed by dynamite and cyanide fishing. A recent survey noted that "excellent" reefs—those classified as having more than 75 percent healthy coral cover—are now present in only 4.3 percent of the total reef area surveyed. This is an issue that the Philippines authorities are, thankfully, attempting to address, and certain regions now have energetic conservation programs in place.

VACATION HOTSPOT
Indigenous watercraft pulled up at a palm-fringed beach in the region. The Philippines appeal to both divers and non-divers alike.

LIVEABOARD EXCURSIONS

The remote Tubbutaha and Jessie Beazley Reefs in the Sulu Sea remain relatively undamaged, and provide some world-class diving. All diving at Tubbutaha is from liveaboards, although many of the shallow reef crests provide excellent snorkelling opportunities. The steep walls of Tubbutaha are swept by strong currents and have crystal-clear visibility. Of particular quality is North End, a dive that combines spur and groove reef formations with some classic walls. Jessie Beazley Reef is essentially a massive pillar of rock rising from deep water, providing a beacon for groupers, manta rays, barracuda, and eagle rays.

Quality diving can also be found at the Visayas, a small cluster of islands accessed via Cebu City. Malapuscua

HISTORIC FINDS
A diver inspects a wreck off the Philippines. Palawan Island is the departure point for Coron Bay, with its extensive World War II wrecks.

has become particularly famous for providing one of the most unusual of all shark dives, at a site where thresher sharks congregate to be "groomed" by cleaner fish (*see pp.225–26*). Apo Island is a fine example of a progressive conservation project, where local people have become involved in policing the reefs around the island.

MUCK AND WRECK DIVING

Farther north at Puerto Galera, readily accessible from Manila, is some of the finest diving in the Philippines, with some outstanding "muck diving" (*see p.279*). Palawan also offers some wilder diving, with Coron Bay containing some particularly fine Japanese wrecks sunk during an attack by US aircraft on September 24, 1944.

Barracuda Lake offers a genuinely different diving experience, requiring a short jungle hike that is rewarded by an exploration of a system in which freshwater sits on top of seawater. A large barracuda in the lake is said to guide divers through his territory.

MARINE LIFE

The diversity of this archipelago is truly remarkable, with 1,499 crustacean species, 462 types of mollusks, and 22 different types of beach vegetation. Of the 500 known coral species worldwide, 488 are found here. This biological diversity was recognized in 1993, when the Tubbataha Reef Marine Park was made a World Heritage site.

The mandarin fish, one of over 2,000 fish species recorded in the Philippines

Australasia

The vast coastline of Australia offers superb coral reefs as well as spine-tingling cold-water encounters with giant marine predators. New Zealand, to the southeast, is rapidly emerging as a dive destination of real quality, with some of the world's best temperate dive sites.

BARRIER REEF AND MORE

For the uninitiated, the notion of diving in Australasia is limited to exploring the Great Barrier Reef, which lies on the northeastern coast of Australia. One of the most impressive natural features on the planet, it is a site of remarkable species diversity.

While the fame of the reef is fully justified, there are also many other rewarding dive sites in Australia and New Zealand. East of the tourist hotspots of the Great Barrier Reef lies the Coral Sea, equally beautiful and with fabulous marine life to be seen. To the south of Australia, the cold waters of Dangerous Reef and the Neptune Islands offer thrilling encounters with great white sharks. Farther south still is Tasmania, home to lush kelp forests. On the sparsely populated western coast of Australia is Ningaloo Reef, one of the best locations for encountering the mighty whale shark.

VOLCANIC REEF
The temperate reefs of New Zealand's Poor Knights Islands teem with colorful marine life.

NEW ZEALAND

The jewel in New Zealand's diving crown is the Poor Knights Islands, which for many (including the late Jacques Cousteau) ranks as the finest temperate-water dive site in the world. The unique topography of the site means that this is a breathtaking place to dive, with vast shoals of fish swarming over craggy volcanic reefs and through atmospheric cavern systems. Protected by both traditional Maori law and modern legislation, the islands are a magnet for divers the world over.

New Zealand boasts some impressive wrecks, including the world-famous *Rainbow Warrior* and the dramatic *Mikhail Lermentov*. It is also rapidly developing a reputation for providing big animal encounters with numerous whale species, as well as with iconic sharks such as the mako and the bronze whaler. To top it all off, New Zealand also offers stunning scenery, crystal clear rivers and springs, and magnificent fjords.

SOUTHERN FJORDS
The fauna of New Zealand's fjords includes red and black corals, penguins, fur seals, and bottlenose dolphins.

LIFE ON THE REEF
The Great Barrier Reef hosts a vast array of flora and fauna, including more than 1,500 fish species and 4,000 different types of mollusks.

Great Barrier Reef

QUEENSLAND, AUSTRALIA

Great Barrier Reef
Cairns
AUSTRALIA
Perth
Sydney
Southern Ocean

One of the true natural wonders of the world, the Great Barrier Reef is the longest reef of its kind on Earth. Home to a spectacular diversity of animal and plant life, recent legislation has granted even greater protection for this abundant natural habitat.

VAST ECOSYSTEM

The Great Barrier Reef is so extensive that its precise size has never been recorded, although it is estimated that it stretches for 1,400 miles (2,250 km), and covers around 135,000 sq miles (350,000 sq km)—about the same surface area as Ireland. It is made up of 2,000 individual reefs, and around 71 coral islands are spread along its length.

In broad terms, the Great Barrier Reef can be said to be divided into two regions—the inner reef, known as the Great Shallow, and the outer reef, consisting of deeper reef systems and sloping walls leading to the open sea beyond. The reef itself is made up of over 400 species of coral, and supports around 1,500 species of fish. Approximately 4,000 species of mollusks inhabit the flats and nooks and crannies of the reef, while 23 species of marine mammals may be encountered along the vast length of this complex ecosystem.

ESSENTIAL INFORMATION

WATER TEMPERATURE 77–84°F (24–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT The Great Barrier Reef can be dived throughout the year.

MUST-SEES Ribbon Reefs (particularly Ribbon Reef Number 10); Cod Hole; Pixie's Pinnacle.

GLOBAL IMPORTANCE

Certain areas of the Great Barrier Reef have enjoyed protected status since 1973, when it was established as a marine park. This was enhanced in 1981 when the reef was recognized as a World Heritage Site. More recent legislation has seen 71 percent of the total area of the reef covered by some sort of

WORLD OF COLOR
The range of marine life inhabiting the Great Barrier Reef is staggering in its variety and splendor, but divers must be careful not to touch delicate corals.

DEEPER INTO THE REEF

Certain parts of the Great Barrier Reef have been noticeably degraded or damaged by the high volume of dive traffic. This is no great surprise, given the delicacy of the reef's ecosystem and the inexperience of the many divers exploring it. Although there are still some fine dives to be had in these busy areas—especially for those new to the sport—many dive operators have moved further out into the reef system, offering packages on liveaboard boats that allow more experienced divers to explore remote and less spoilt sites.



Eye-stripe surgeonfish

protective status—an optimistic sign for the future of a reef that is larger than any other coral system, but just as vulnerable to misuse and exploitation.

DIVING IN THE REGION

There is a mass market for diving the Great Barrier Reef, operating out of Cairns and Townsville in day boats containing very large numbers of divers. There have been a number of well-publicized incidents where divers have been missed when boats have departed back to shore, and although this is now very well regulated, it is still worth, on the larger vessels at least, ensuring that the correct procedures are in place before diving. The other main diving activity on the reef takes place from liveaboards that venture farther afield to more remote sites.

Divers on the reef are assured of reasonable hard coral and colorful fish life almost anywhere along its length, but there are also a number of notable individual sites. Ribbon Reef Number 10 is particularly rich and diverse, even by the Great Barrier Reef's high standards, and is the location for dive sites such as Cod Hole—famous for encounters with giant potato cod—and Pixie's Pinnacle, renowned for its diversity of large animal encounters.

ARTIFICIAL ISLAND
Some sites on the Great Barrier Reef have a permanently anchored observation platform, which visitors can travel to by tour boat.

The Coral Sea

WESTERN PACIFIC OCEAN

Coral Sea
Cairns
AUSTRALIA
Perth
Sydney
Southern Ocean

In the early 1970s, the first liveaboard operators began to explore the waters to the east of the Great Barrier Reef. Here they found the Coral Sea—a region of beautiful pristine hard coral formations and precipitous drop-offs.

REMOTE LOCATION

The Coral Sea begins about 100 miles (160 km) east of Townsville, in the territory of Queensland, Australia. It stretches for another 100 miles (160 km), covering an area of 38,000 sq miles (98,500 sq km). The dive sites consist of a series of undersea mountaintops that rise from a great depth, creating atolls, ridges, and reefs. The visibility in the region is some of the best in the diving world.

TEEMING WITH LIFE

The crossing to the Coral Sea through the rough waters of the inner reef can be demanding; however, divers with the budget and time to make the journey are rarely disappointed. The area is renowned for its big animal encounters, with tiger sharks and hammerheads mixing with more abundant species, such as gray reef sharks and white-tips. Manta and eagle rays are frequently seen off the steeper reef walls, while sea snakes can be seen on Marion Reef.

ESSENTIAL INFORMATION

WATER TEMPERATURE 75–81°F (24–27°C)

ECOSYSTEM Tropical

WHEN TO VISIT Conditions are suitable for diving year-round, but a lengthy boat trip is required to reach the area.

MUST-SEES Cod Wall; Watnabe Bommie; Marion Reef; manta rays; sea snakes.

REEF DWELLERS
Bumphead wrasse cruise over the sandy seafloor of the Coral Sea. These large fish graze in "herds" over the area's reefs.

Wreck of the *Yongala*

QUEENSLAND, AUSTRALIA

Cairns
Wreck of *Yongala*
AUSTRALIA
Perth
Sydney
Southern Ocean

The *Yongala* is a biological wonder—one of the most heavily colonized shipwrecks on Earth. Sitting amid miles of featureless plains of sandy seabed next to the Great Barrier Reef, over time it too has become a teeming coral reef.

FATAL STORM

Lost in a typhoon on March 24, 1911, the *Yongala* was a 357-ft (109-m) steamer carrying 121 passengers north along the Queensland coast. All hands were lost as it foundered, and now it lies in 100 ft (30 m) of water, listing to starboard but still resolutely facing its original northerly direction of travel. Its isolated position, and the fact that it lay undiscovered for over 40 years after sinking, means that it is very heavily colonized with marine life.

MARINE SANCTUARY

The entire food chain of the coral reef is packed into the length of the *Yongala's* short hull. Schools of jack and trevally hunt clouds of bait fish on its port hull, while in its superstructure lurk turtles, morays, coral trout, and huge numbers of sea snakes. Potato cod skulk beneath the bow of the wreck, and very large bull rays nestle in the sand beside the wreck, ever watchful for the tiger and bull sharks that circle out in the blue, just beyond sight.

ESSENTIAL INFORMATION

WATER TEMPERATURE 75–82°F (24–28°C)

ECOSYSTEM Tropical reef

WHEN TO VISIT There is year-round diving on the *Yongala*, but conditions can be rough from May to August.

MUST-SEES Sea snakes; potato cod by the wreck's bow; bull rays; bull sharks.

OCEAN WILDERNESS
Divers can encounter potato cod patrolling the bow section of the *Yongala*. The wreck is a magnet for marine life, attracting a range of species from sharks to turtles.

PROTECTED STATUS

Despite the popularity of the *Yongala* wreck among divers, exploration of the wreck's interior is strictly forbidden by Australian authorities under the country's Historic Shipwrecks Act. It may be, however, that the resident population of grouper are protection enough. In 2002 it was reported that a 6½-ft- (2-m-) long giant grouper had seized a diver's head before releasing him, shaken, but without serious injury, shortly afterward.

Tasmania

TASMAN SEA, AUSTRALIA

Cairns
AUSTRALIA
Perth
Sydney
Tasmania
Hobart

Tasmania offers a diving experience far removed from that of the usual coral reefs and warm waters of Australia. Nonetheless, this tiny island off the southern coast holds a host of diving possibilities for those prepared to travel a little farther afield.

UNSUNG ISLAND

Tasmania is a small island dwarfed by the immensity of mainland Australia to the north. It measures only 186 miles (300 km) from north to south, and is frequently overlooked by divers visiting Australia, distracted by the magnitude of the Great Barrier Reef and the big animals of Ningaloo Reef.

Tasmanian divers are delighted at this relative anonymity, since the island offers some of the finest kelp forests on Earth and some gloriously colorful and diverse cold-water dives. Currents rich in oxygen and nutrients sweep up from the icy waters to the south, giving life to wonderfully dense kelp forests and heavily colonized rock walls.

ESSENTIAL INFORMATION

WATER TEMPERATURE 54–64°F (12–18°C)

ECOSYSTEM Temperate

WHEN TO VISIT The best time to visit Tasmania for diving is between June and September.

MUST-SEES Red handfish; kelp forests; Eaglehawk Neck.

SMALL WONDERS

Of particular note is the abundance of smaller animals, such as red handfish, although the island also plays host to numerous penguins, Australian fur seals, a number of different types of sharks, and a variety of visiting whale and dolphin species. This rich diversity means that divers visiting Tasmania come to appreciate the true breadth of Australia's natural heritage.



PERFECT CONCEALMENT
Sea dragons, such as this leafy variety, can be found in the kelp forests off Tasmania and South Australia. Its shape mimics the plant fronds.

Ningaloo Reef

WESTERN AUSTRALIA



A beautiful coral reef stretching for 175 miles (280 km) off the coast of Western Australia, Ningaloo has much to offer the diver. Its fame, however, lies in the abundance of a single animal—Ningaloo is the whale shark capital of the world.

MAGNET FOR DIVERS

Ningaloo Reef is approximately 750 miles (1,200 km) north of Perth, Australia, and lies along a beautifully remote stretch of coastline.

The diving on the reef is centered around the small town of Exmouth—the population of which doubles during whale shark season, as divers flock there from around the world. Ningaloo Reef is splendidly rich in its own right—with 500 fish species and 200 types of coral. Such is the scale of diversity here and the integrity of the ecosystem, that the region was declared a national park in 1987, and now over 1,500 sq miles (3,885 sq km) enjoys protected status.

ESSENTIAL INFORMATION

WATER TEMPERATURE 75–84°F (24–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT Year-round diving, but whale sharks present March to June.

MUST-SEES Whale sharks; manta rays; migrating whales; shore dive at Point Murat Navy Pier.

WEALTH OF WILDLIFE

Although the whale sharks are less abundant from July through to February, they are replaced by other great attractions—between May and October, huge numbers of manta rays can be seen, and from July to November, migrating whales pass along the coast. In addition, a survey in 1994 counted more than 1,000 dugongs along this stretch of coast—one of the most significant populations on Earth.

CLOSE ENCOUNTER
Touching whale sharks may distress them, and only those with special training, such as this marine biologist, should do so.

Poor Knights Islands

NORTH ISLAND, NEW ZEALAND

Poor Knights Islands
Auckland
NEW ZEALAND
Wellington

A mystical set of islands, sacred in Maori legend, the Poor Knights lie 14 miles (23 km) off the coast of North Island in New Zealand. Honeycombed with caves and caverns, they are host to some truly remarkable gatherings of marine animals.

FORBIDDEN LAND

The Poor Knights Islands consist of stark volcanic rock pockmarked with overhangs, ridges, caves, and arches. The dramatic topography of the islands evokes their bloody history, as they were the site of a terrible Maori massacre in 1820, causing them to be declared *tapu* (forbidden) in Maori law. No one has set foot on the islands since, and this, combined with marine park status since 1977, has created a wonderfully pristine environment both above and below the waves, which has drawn divers to this site from all over the world. Boats run to the islands from nearby Whangerai.

REMOTE LOCATION

The islands are only accessible by boat, so visits involve a short voyage aboard one of the many dive charter boats based on the mainland.

ESSENTIAL INFORMATION

WATER TEMPERATURE 59–75°F (15–24°C)

ECOSYSTEM Temperate reef

WHEN TO VISIT Year-round diving, but rainy season runs from July to October.

MUST-SEES Gatherings of southern stingrays; Blue Mao Mao Arch; bronze whaler sharks on deep ridges.

WEALTH OF MARINE LIFE

There are approximately 120 fish species around the Poor Knights, but it is the sheer numbers of fish present that are the main attraction. Vast shoals of species such as blue mao mao inhabit the overhangs and caverns around the islands, while the stark reefs are coated in an extraordinary diversity of

encrusting organisms, with brightly colored sponges jostling for position with sea squirts and bryozoans. Thick carpets of kelp provide perfect hunting grounds for brightly colored wrasse species, scorpion fish, and several different types of moray eels. In March, the dark waters under the Southern Arch host huge mating congregations of short-tailed southern stingrays. As well as this spectacular annual gathering, there is also a resident population of bronze whaler sharks, and regular transient visitors including orcas, dolphins, and several whale species.

Jacques Cousteau was so impressed when he visited the Poor Knights in the 1960s that he described the islands as the finest temperate-water dive destination on Earth, and one of the top ten overall. The range of dive sites and sheer abundance of marine life provide a compelling argument that this applies as much today as it did then. This is an essential dive site if visiting New Zealand.

ODD ONE OUT
A lone wrasse swims at the center of a swirling shoal of blue mao mao. The Poor Knights Islands are famous for their abundance of fish life.

EXPLORING CAVERNS

The marine life of the Poor Knights Islands teems amid dramatic underwater caves and arches, including the largest sea cave in the world—Rikoriko Cave. Visiting divers should carry flashlights, including a reliable backup, and ensure that basic cavern safety rules are followed (*see pp.186–87*).

A diver explores a sea cave

Wreck of the *Rainbow Warrior*

CAVALLI ISLANDS, NEW ZEALAND

Rainbow Warrior
Auckland
NEW ZEALAND
Wellington

Perhaps no other shipwreck on Earth has the poignancy of the *Rainbow Warrior*. Sunk in an act of international espionage that shocked the world, it now lies off the Cavalli Islands, in one of the most beautiful regions of New Zealand.

TRAGIC FATE

The conservation vessel *Rainbow Warrior* was moored in Auckland harbor on the night of July 10, 1985. Shortly before midnight, two explosions ripped through it, killing the vessel's photographer, Fernando Pereiro. This senseless act of terrorism was traced to the French Secret Service, leading to international condemnation and lengthy jail sentences for the two agents who planted the explosives.

PEACEFUL RELOCATION

The *Rainbow Warrior* wreck remained in Auckland for many months, before being refloated and towed farther north to the Cavalli Islands, a beautiful marine sanctuary granted sacred status in Maori law. Here it was sunk as an artificial reef, and has become a popular dive site.

The *Rainbow Warrior* is a small vessel, and so can easily be covered in a single dive. It sits almost upright on the bottom, and its superstructure rises to within 50 ft (15 m) of the surface, with the seabed below at 85 ft (26 m). Its bow section is still largely intact, creating the illusion that it is sailing across the white sands of the seafloor beneath its hull.



FINAL RESTING PLACE
A diver surveys the wreckage of the former Greenpeace vessel *Rainbow Warrior*, which was badly damaged by a violent act of sabotage.

REFUGE FOR MARINE LIFE

The *Rainbow Warrior's* hull is covered in a multicolored carpet of jewel anemones, and the vibrancy of color on display here is remarkable. Its superstructure is now a home for scorpionfish, blue cod, and shoals of golden snapper, plus kingfish, and the distinctively shaped John Dory. It seems fitting that this former conservation vessel now serves as a home for so many fascinating marine species.

ESSENTIAL INFORMATION

WATER TEMPERATURE 57–75°F (14–24°C)

ECOSYSTEM Temperate

WHEN TO VISIT Year-round, but September to April is best.

MUST-SEES Scorpionfish; the prow; the Rainbow Warrior Memorial; the ship's propeller and stern.

Wreck of the *Mikhail Lermentov*

MARLBOROUGH SOUND, NEW ZEALAND



The gloomy passageways and silty spaces of the *Mikhail Lermentov* are mute witnesses to one of the great mysteries of modern sea travel. Sunk under the strangest of circumstances, it now lies in the cold waters of Marlborough Sound, New Zealand.

ENIGMATIC WRECK

The 20,000-ton Russian cruise liner *Mikhail Lermentov* was driven hard onto rocks by an experienced local pilot on February 16, 1986. It was a clear, calm day, and theories abound as to the factors behind the sinking—bribes, alcohol, and espionage have all been blamed at one time or another. The mystery remains to this day, but the wreck represents a tremendous diving experience, although perhaps not one for the faint-hearted.

DIVING THE *LERMENTOV*

It lies on its starboard side in 121 ft (37 m) of water, although the sheer size of the vessel means that its port side can be reached at only 66 ft (20 m). Dives on its external superstructure are recommended, with highlights including the magnificent bow, the bridge, and the stern. For the more adventurous there is the famous ballroom, although this dive should only be undertaken by those with appropriate training and equipment (*see pp.166–71*). Marine life on the wreck includes scorpionfish, conger eels, and blue cod; occasionally pods of orcas hunt in the Sound itself.

ESSENTIAL INFORMATION

WATER TEMPERATURE 57–72°F (14–22°C)

ECOSYSTEM Temperate

WHEN TO VISIT Year-round, but September to April is best.

MUST-SEES Bridge; swimming pool; stern; ballroom, provided you have the right gear and level of experience.



SERIOUS ADVENTURE
A diver explores in conditions of reduced visibility, often encountered on the *Mikhail Lermentov*. The wreck lies in deep coastal waters.

Oceania

The beauty of the estimated 20,000 islands that make up Oceania is unmatched anywhere else on Earth. The region holds tremendous riches, particularly for those confident enough to venture off the beaten track to visit the more far-flung islands and reefs.

WRECK DIVING IN PARADISE

Oceania is the collective name for the islands of the Pacific, generally considered synonymous with the South Sea Islands of Melanesia, Micronesia, and Polynesia. The region is typified by tranquil beaches with sugar-white sand and swaying palms, and, below water, powerful and intense diving experiences. Some of the world's most diverse reefs are in Micronesia, and the fierce fighting that raged through much of the region during World War II has created some impressive wreck sites.

Truk Lagoon in Micronesia, with its array of sunken Japanese ships, was viewed by many as the finest of all wreck diving locations until the establishment of a dive operation on Bikini Atoll in the Marshall Islands in 1996. From Bikini Atoll, divers can explore the remains of the fleet of ships sunk during the testing of hydrogen bombs by the US from 1946.

Palau has many magnificent dive sites, including Blue Corner, a coral ridge that juts out into the ocean and

VOLCANIC CREATION
Many of the world's atolls are located in the Pacific Ocean. These are created as a coral reef builds up around a subsiding volcanic island.

UNDERWATER WONDERS
The coral gardens of Micronesia, among the healthiest on the planet, are home to butterflyfish, wrasse, angelfish, and puffers.

plunges more than 1,000 ft (300 m), and the Ngemelis Wall, one of the best wall dives in the world. There is also Jellyfish Lake, an inland saltwater lake swarming with jellyfish that have lost their ability to sting. The nearby island of Yap boasts one of the finest sites for manta ray encounters. Yap is one of the more popular destinations in Micronesia, yet 80 percent of the reefs remain undived. For those who have the time to explore the remote islands of Oceania, they offer a truly original dive experience.

TRADITIONAL ISLAND LIFE
Unspoiled islands offer the possibility of fascinating cultural encounters and more fulfilling diving experiences.

Palau

MICRONESIA, SOUTH PACIFIC

PHILIPPINES
Palau
INDONESIA
AUSTRALIA

Divers constantly argue about what they consider to be the ultimate dive destination, but Palau will always be a strong contender. Consisting of 307 scattered islands, Palau has it all—wrecks, caves, and some of the busiest coral reefs on Earth.

A WORLD OF VARIETY

One of the great draws of Palau is the vast range of diving available. Like other island groups in Micronesia, it has colorful reefs cruised by large predators and impressive oceanic species. What gives Palau the edge over other sites in the region is that the geology and recent history of the islands have combined to create a diver's paradise. Caves and caverns honeycomb walls and reefs throughout the island chain; and fierce battles between American and Japanese forces during World War II mean that aircraft and shipwrecks abound.

Palau also has a number of rare natural phenomena, the most famous being Jellyfish Lake. This is a large volcanic crater filled with brackish water containing the pulsating forms of over 20 million mastigia jellyfish. To snorkel there is a surreal experience.

DIVING PALAU

Perhaps the most famous of all dive sites in Palau is Blue Corner. Jutting into deep water at the western edge of the island chain, this site has it all: swirling schools of barracuda, patrolling sharks, elegant eagle rays, and bustling Napoleon wrasse. Close to Blue Corner is another highlight, showing off Palau's renowned cavern diving—the Blue Holes. Here, divers enter a vast chamber illuminated only by pillars of light streaming through great gaps in the reef above. The Temple of Doom chamber, found at the rear of the Blue Holes, is a more serious dive that requires considerable experience and skill. The floor here is littered with the shells of sea turtles that were unable to find their way out of the chamber and perished. Chandelier Cave in Malakal Harbor is a more sedate alternative for those wishing to explore an easy cave system.

RELICS OF CONFLICT

In addition to the great natural diversity on show at Palau, there are many fascinating relics from World War II.

One of the best shipwrecks from that era is that of the Japanese fleet tanker *Iro*. At 475 ft (145 m) in length, the *Iro* is large and exceptionally well preserved. It lies in moderate depths in a lagoon near the central town of Koror. Visiting divers should also see the wreck of the Aichi E13-A1 (codename "Jake") seaplane. Discovered a decade ago, this wonderfully intact aircraft lies in shallow water, and is an easy dive with many layers of interest.

The wreck of the "Jake" seaplane

ESSENTIAL INFORMATION

WATER TEMPERATURE 77–82°F (25–28°C)

ECOSYSTEM Tropical

WHEN TO VISIT Year-round diving. Rainy season between July and October.

MUST-SEES Blue Corner; Blue Holes; Jellyfish Lake; the wreck of the *Iro*; the “Jake” seaplane wreck.

PATTERN OF ISLANDS An aerial view of a cluster of islets at Palau, ringed with white coral sand and azure seas.

Yap

CAROLINE ISLANDS, NORTH PACIFIC



A remote island paradise, Yap has become a magnet for divers seeking close encounters with manta rays. However, there is a great deal more to this tiny Micronesian island, with plenty of sharks on patrol, including gray, white-tip, and black-tip reef species.

PACIFIC IDYLL

With its lush mangroves and rolling green hills, Yap lies in clear waters that abound with tuna and dolphins. It has one of Micronesia's most vibrant indigenous cultures, and retains a genuinely remote island feel in all aspects of daily life.

MEETINGS WITH MANTAS

The real attraction, however, lies beneath the waves. Yap is one of the very few dive destinations on Earth where encounters with manta rays are guaranteed. Two shallow tidal channels cut through the islands, and it is here that the mantas gather at cleaning stations that dot the sandy sea floor. At these sites, divers can observe the activity of smaller fish called remoras, which use suckers to attach themselves to the rays and remove irritating parasites by nibbling them off. Divers crouch by the stations—normally isolated coral heads—and await the arrival of the star attraction. Manta rays can grow to more than 2,200 lb (1,000 kg) in weight, and their wingspan can sometimes exceed 20 ft (6 m) from tip to tip.

ESSENTIAL INFORMATION

WATER TEMPERATURE Around 82°F (28°C) year-round.

ECOSYSTEM Tropical

WHEN TO VISIT Year-round, but December to April is best.

MUST-SEES Manta rays visiting cleaning stations; shark dives; Yap Caverns.

PROTECTED ENVIRONMENT

Other dives in Yap should not be overlooked—there is some tremendous shark action here, and the reefs are in pristine condition due to a strictly-adhered-to agreement to use traditional fishing techniques. Such forward-thinking legislation is of great benefit to both marine life and visiting divers, and is an admirable example of responsible stewardship of the seas. Nearly 80 percent of the reefs around Yap remain undived due to local conservation by-laws, although the remaining 20 percent are well worth exploring.

ON THE WING
Despite their impressive and imposing size, manta rays are a docile species that feed on microscopic plankton life.

Bikini Atoll

MARSHALL ISLANDS, CENTRAL PACIFIC

Bikini Atoll
Pacific Ocean
AUSTRALIA
NEW ZEALAND

Bikini Atoll vies with Truk Lagoon to be the finest wreck diving location on Earth. This tiny collection of coral islands and lagoons is the site of spectacular and dramatic wrecks, with a truly extraordinary story behind their sinking.

ATOMIC TEST SITE

As World War II ended and the Cold War began, the US chose a tiny atoll at the northern end of the Marshall Islands to conduct a massive program of nuclear weapons testing. Ships of varying size, nationality, and vintage made up the 84 vessels of a dummy fleet, the vast majority of which were sunk in tests running from 1946 to 1958. Included in the fleet was the US aircraft carrier *Saratoga*—weighing 33,000 tons and now the largest shipwreck accessible to divers anywhere on Earth. Also at Bikini is the *Nagato*, the flagship of the Japanese fleet, and the first warship in the world to be armed with 16-inch guns. The last active Japanese battleship, the *Nagato* saw action as late as July 1945, when it was attacked by US torpedo bombers.

The ships lie in deep water, with depths averaging 160–180 ft (50–55 m), but with 1,500 or so fish species swarming over the stunning remains, the rewards are well worth it for divers with sufficient training and experience. No dive site can offer a more dramatic insight into history.

ESSENTIAL INFORMATION

WATER TEMPERATURE Around 84°F (29°C) year-round.

ECOSYSTEM Tropical

WHEN TO VISIT Best time to visit is between April and September.

MUST-SEES The US carrier *Saratoga*; Japanese battleship *Nagato*.

GHOSTS FROM THE PAST
The wreckage of a naval aircraft destroyed during US nuclear bomb tests (*inset*) at Bikini Atoll. Residual radiation has since dropped to negligible levels at this dive site.



Bora Bora

SOCIETY ISLANDS, SOUTH PACIFIC

Pacific Ocean
Bora Bora
AUSTRALIA
NEW ZEALAND

Renowned as one of the most beautiful islands in the Pacific, Bora Bora is a huge lagoon dominated by an island at its center. The lagoon and the surrounding reef provide a dazzling array of dives against the stunning backdrop of volcanic peaks.

PACIFIC PARADISE

Bora Bora is part of the Society Islands, and is located 170 miles (274 km) northwest of Tahiti. An atoll of sparkling beauty that has long entranced writers and artists alike, the main island is only 6 miles (10 km) long, and sits at the heart of a lagoon three times its size. The reef around the lagoon has only one navigable channel, which is crisscrossed by smaller channels and gullies, most of which provide excellent dive sites.

ABUNDANCE OF LIFE

Bora Bora's lagoon and surrounding reefs are home to a huge variety of fish—a recent survey documented 500 different species, although the real number is almost certainly higher. Larger animals encountered on the outer reef and in the cuts in the atoll walls are gray reef sharks, white-tip reef sharks, groups of black-tip reef sharks, lemon sharks, and silvertips. Numerous species of rays can be encountered in the central lagoon, including the groups of manta rays for which the site has become justifiably famous.

ESSENTIAL INFORMATION

WATER TEMPERATURE 79–84°F (26–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT Thanks to its balmy climate, diving in Bora Bora can be enjoyed year-round.

MUST-SEES Manta ray encounters at Anua; shark dives at Tupitipiti.



ANATOMY OF AN ISLAND
Bora Bora is dominated by the jagged remains of a volcano, and encircled by a great lagoon. This remote atoll is widely considered to be one of the most beautiful spots on Earth.

Wreck of the *President Coolidge*

VANUATU, SOUTH PACIFIC

Pacific Ocean
Vanuatu
AUSTRALIA

A relic of an elegant age of sea travel, the *President Coolidge* is a strong candidate for the most exciting wreck now accessible to recreational divers. Perched on a reef in Vanuatu, it hides one of the most famous icons in diving in its dark interior.

BEACHED BEHEMOTH

The *President Coolidge* sank on October 26, 1942 while carrying 4,800 American troops to the Pacific during World War II. It struck floating mines, laid by “friendly” forces in the area, and when it became clear the ship would not make it into the nearby harbor of Luganville, the captain beached the huge vessel on a reef. Here it remains today, with its stern submerged in 236 ft (72 m) of water, although the bow lies at a depth of just 49 ft (15 m).

DIVING THE *COOLIDGE*

The wreck is accessed directly from the shore. Within its bulk is a network of passageways and enormous holds containing the paraphernalia associated with equipping an army for war. Although converted for duty as a troop ship, there are still traces of its time as one of the world’s most luxurious ocean liners.

An essential stop for any diver visiting this magnificent wreck is the statue of the Lady, in one of the first-class dining rooms. This once stood on the mantelpiece of the smoking room, but a small earthquake dislodged it from its perch, and it was later moved farther up the wreck. Other highlights include the promenade deck and a beautiful mosaic fountain, once the centerpiece of a gracious lobby.

ESSENTIAL INFORMATION

WATER TEMPERATURE 75–82°F (24–28°C)

ECOSYSTEM Tropical

WHEN TO VISIT There is year-round diving on the wreck.

MUST-SEES The Lady; the swimming pool; lobby mosaic; the promenade deck; lampfish dive.



CASUALTY OF CONFLICT
The *President Coolidge* ran aground at Vanuatu during World War II. The wreck is still filled with corroding relics from that era.

Truk Lagoon

CAROLINE ISLANDS, NORTH PACIFIC

Truk Lagoon
INDONESIA
Pacific Ocean
AUSTRALIA

Regarded by many as the finest of all wreck sites, Truk Lagoon is the resting place for an eclectic mix of Japanese vessels sunk in a single raid by American aircraft in 1944. With many wrecks still in good condition, Truk Lagoon offers unforgettable diving.

WITNESS TO WAR

Truk Lagoon is a massive natural atoll almost 40 miles (65 km) across; it is ringed by 140 miles (225 km) of reef and small coral islands, forming one of the largest natural harbors of this type on Earth. The presence of 15 larger islands in the center of the lagoon made it an ideal base for military operations, a fact not lost on the Japanese Imperial Navy, which amassed a vast number of warships, merchant vessels, and fleet tenders here in the latter stages of World War II, in readiness for further deployment.

ESSENTIAL INFORMATION

WATER TEMPERATURE 84°F (29°C)

ECOSYSTEM Tropical

WHEN TO VISIT Year-round diving, but rainy season from July to October.

MUST-SEES The wrecks of the *Fujikawa Maru*, *Shinkoku Maru*, *San Francisco Maru*, and the “Betty” bomber aircraft.

Such an assembly of enemy vessels proved irresistible to American forces, which carried out a daring raid on February 17–18, 1944, launching 450 aircraft from nine aircraft carriers beyond the horizon. The raid was a complete success, with over 60 Japanese vessels sunk in a savage 48 hours.

SECRET SITES

The “ghost fleet” of Japanese ships lies on the seabed in Truk Lagoon, although only 38 of them have been charted. The others have been left unmarked for fear of looting and illegal diving (to dive the wrecks in Truk, a local guide is a legal and practical necessity). Highlights include the *Fujikawa Maru*, complete with Zero fighter aircraft still in its holds, and the *San Francisco Maru*—a huge freighter with an array of cargo including two tanks on its deck, so outstanding it is known as the “Million Dollar Wreck.”

DIVING TRUK LAGOON

Wreck diving in Truk is deep, with the majority of the wrecks lying in depths of 100 ft (30 m) or more. Local operators are, however, well set up to cope with deep air diving, and have established effective drills and techniques to cope with repeated deep dives. Nonetheless, a certain level of qualifications and experience is advisable before diving the fascinating wrecks of Truk Lagoon. Contact local operators for details.

Marine life at Truk

RELICS FROM THE PAST
A diver hovers over the ghostly remains of a Japanese ship sunk at Truk Lagoon. Aircraft and submarines also fell victim to aerial attack here.

Fiji

SOUTH PACIFIC



Simply hearing the name “Fiji” summons up images of an exquisite tropical paradise. With 800 islands sprawling over 80,000 sq miles (207,000 sq km) of ocean, the reality is just as exciting. Fiji offers a wealth of different experiences for the diver.

IDYLLIC ISLANDS

Perhaps one of the most notable features of Fiji for the visiting diver is that only 12 percent of the islands in the archipelago are inhabited—and 75 percent of the entire population lives on just one island, Viti Levu. Fiji truly offers a wealth of different diving opportunities around a huge variety of reefs, channels, and islands. Coral reefs cover a staggering 6,000 sq miles (15,540 sq km); they include at least 398 species of coral and are home to over 1,200 species of fish.

UNDERSEA GARDENS

Fiji is particularly famous for its beautiful soft-coral gardens, the most renowned of which is the White Wall in the Somosomo Strait. The region’s rich waters mean that filter-feeding invertebrates thrive in the coral lagoons. Sea fans, whip corals, and a myriad of other species vie for space on the brilliantly colored reef walls.

ESSENTIAL INFORMATION

WATER TEMPERATURE 79–88°F (26–31°C)

ECOSYSTEM Tropical

WHEN TO VISIT Year-round, but the best time to visit Fiji is between April and November.

MUST-SEES Somosomo Straight and the White Wall; Beqa Lagoon; Naingora Pass.

Anemonefish

REEF RESIDENT
Sharks of many species, including gray reef sharks, patrol the soft-coral reefs of Fiji’s scattered islands.

There are also many spectacular fish species in Fijian waters. For the thrill-seeker, there is plenty of large-animal action. The best-known shark dive here is known as “Aqua Trek 3-D,” after the operator that runs it, and offers the opportunity to see up to seven species of sharks on a single dive, including bull, black-tip reef, white-tip, and lemon sharks. The dive is one of 100 recognized dive sites in Beqa Lagoon—an indication of the sheer variety of diving in this beautiful tropical archipelago. Happily, the area has been designated a Marine Park and enjoys protection from overfishing; the small fees asked of divers who experience its underwater environment are used to help fund conservation measures. Such careful stewardship ensures that Fiji’s diving will remain outstanding for years to come.

Tonga

FRIENDLY ISLANDS, SOUTH PACIFIC

Pacific Ocean
AUSTRALIA
Tonga
NEW ZEALAND

Tonga is a dramatic chain of volcanic islands to the east of Fiji. The grandeur of its scenery is matched by one of the most amazing encounters with a marine mammal that a diver can have anywhere on Earth—snorkeling with humpback whales.

PACIFIC OUTPOST

Diving in Tonga is based mainly in the central island group of Ha'apai, and in Vava'u farther to the north. Port of Refuge in Vava'u, which for many divers is their first experience of Tongan diving, contains a particularly fine wreck in the form of the *Clan McWilliam*, a large merchant vessel sunk in the 1920s.

STAR SITES

Other sites of note in the region are Tuangasika Island, the location of an exciting cavern called Mariners Cave, and the steep walls of Hunga Magic—an undersea peninsula jutting into the blue water from Hunga island. Tonga's fame in the diving world is, however, based on encounters with humpback whales. From July through to October, around 700 humpbacks move into warm waters around the island group. Although local conservation groups do not allow scuba diving with the whales (to minimize disturbance to them), snorkeling alongside these amazing mammals is a unique experience.

ESSENTIAL INFORMATION

WATER TEMPERATURE 72–86°F (22–30°C)

ECOSYSTEM Tropical

WHEN TO VISIT July to October for humpback whales; avoid typhoon season from November to April.

MUST-SEES Humpback whales; Hunga Magic; Mariners Cave; *Clan McWilliam*.

ANNUAL MIGRATION
A humpback whale raises its massive flukes above the surface. Large numbers of this magnificent animal pass by Tonga each year.

The Americas

As befits a landmass that spans virtually all latitudes of the globe, the Americas boasts a staggering range of dive sites. Great ocean currents beset both North and South America, combining with local conditions to create something for divers of every level of expertise.

COASTAL DIVIDE

The coasts of the North American continent offer very different, but equally thrilling, diving environments. To the west, you can enjoy magnificent wild diving in the fjords of Alaska and British Colombia, explore vast kelp forests off the California coast, and experience glorious encounters with humpback whales and whale sharks in the Gulf of California.

The eastern coast features wrecks and raggedtooth sharks on the Outer Banks off North Carolina—the region where technical diving made its greatest leaps forward. The Florida Keys provide reef diving of the highest quality, and are popular as a training ground for thousands of divers who try the sport while on vacation.

The Caribbean offers classic coral reef diving. With its well-developed diving infrastructure, it has long been a favorite dive destination. To the south, in Central America, is the Belize barrier reef—the longest in the Northern Hemisphere. Off the coast of Venezuela lies Bonaire, in the Dutch Antilles, a beacon of marine conservation. Farther south still is the island of Fernando de Noronha off Brazil, perhaps the finest dive site in the whole of South America.



EASILY EXPLORED
The superb visibility and calm, warm waters of the Caribbean provide ideal conditions for reef diving.

SEA SAFARI
Even snorkeling over sandbars in the Cayman Islands, western Caribbean, can bring you face to face with fascinating marine animals.

ENCHANTED FOREST
The towering kelp forests in the shallow waters off California are among the most beautiful and biologically rich of all marine habitats.

Florida Keys

FLORIDA, UNITED STATES

US
Atlantic Ocean
Gulf of Mexico
Miami
Florida Keys

The Florida Keys are a string of coral and limestone islands stretching 120 miles (193 km) into the Gulf of Mexico. For many, this popular vacation destination represents a first introduction to diving, and there are dive sites of real quality and variety here.

SUNKEN TREASURES
The wreck of a tugboat lying in clear blue water. The Keys are famed for good underwater visibility and excellent areas for training.

PROTECTED ECOSYSTEM

The Florida Keys consist of 200 small islands, the largest of which are connected by the 42 bridges of US Highway 1. The importance of the Florida Keys as a vibrant marine ecosystem was recognized as long ago as 1960, with the John Pennecamp Coral Reef State Park established as the first-ever marine park in the US. More followed, and the region now boasts 18 protected areas, providing cover out to 3 miles (5 km) beyond the reef.

ESSENTIAL INFORMATION

WATER TEMPERATURE 70–84°F (21–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT Year-round diving, but hurricane season October to November.

MUST-SEES Molasses Reef, wreck of the *Adolphus Busch Sr.*; the Christ of the Deep statue in Key Largo.

UNDERSEA ATTRACTIONS

The reef itself runs parallel to the island chain, roughly 5 miles (8 km) offshore. As such, most of the diving here is from boats, and there are many experienced operators. There are some excellent wrecks, as well as classic spur and groove reef formations, with the outer reef inhabited by a diverse range of Caribbean species. The shallow inner reef also hosts manatees, as well as providing a nursery for smaller species and huge numbers of trainee divers.

Crystal River

FLORIDA, UNITED STATES



The Crystal River in northwest Florida is parent to a network of channels and tributaries snaking through the swamps. What draws divers to the region is the chance to swim with manatees—one of the great animal encounters in the underwater world.

WEB OF WATERWAYS

The Crystal River stems from a series of inland upwellings through porous rock, creating a natural filtering system that results in some of the clearest water on Earth. What this meeting of rock and water also creates is a honeycomb of caverns, caves, and tunnels. Although these are frequently occupied by huge catfish (a draw in themselves), the real attraction for the diver is the presence of the West Indian manatee.

GENTLE GIANTS

These huge and placid animals—measuring up to 14 ft (3 m) long and weighing up to a ton and a half—have been using the shallow pools and warm streams of the Crystal River to feed and breed for thousands of years. Speedboats and habitat destruction have exacted a terrible toll on the manatees, which are now on the endangered list. Diving with the manatees is not permitted, but nonetheless, snorkeling next to one of these huge animals in crystal-clear water is a tremendous experience.

ESSENTIAL INFORMATION

WATER TEMPERATURE 68–81°F (20–27°C)

ECOSYSTEM Freshwater

WHEN TO VISIT Crystal River can be visited year-round, but for snorkeling with manatees, the best time is between the months of December and April.

MUST-SEES Devil's Den, King's Cavern; swimming with manatees.



A manatee

CLEAR ADVANTAGE
The stunning clarity of the water at Crystal River stems from geological conditions in the area. Such waters are perfect for observing manatees.

Little Bahamas Bank

BAHAMAS, WESTERN ATLANTIC



The Little Bahamas Bank would appear to be the most unpromising of dive sites—a vast patch of featureless, shallow sand bank. One animal has, however, made this area irresistible to divers. Dolphin encounters here are uniquely memorable.

WILD ENCOUNTER
Spotted dolphins have frequented the Little Bahamas Bank for many years, and these inquisitive animals freely interact with snorkelers in the shallow waters of the Bank.

SHALLOW SEA

The Little Bahamas Bank lies between the islands of Grand Bahama and Great Abaco, two of the larger islands of the 700 that make up the Bahamas archipelago. The northern end of the bank lies 70 miles (113 km) east of the Florida coast, allowing access to the region from the mainland US as well as the Bahamas. The bank is relatively featureless, consisting of shallow white sand dotted with low-lying reefs and the occasional wreck. Marine life is relatively sparse compared to other regions in the Bahamas, although there is the possibility of encounters with some enormous barracuda, several species of turtles, and a number of shark species.

ESSENTIAL INFORMATION

WATER TEMPERATURE 75–82°F (24–28°C)

ECOSYSTEM Tropical

WHEN TO VISIT Year-round, but hurricanes may strike later in the year.

MUST-SEES Spotted dolphin snorkeling encounter; the Bull Pit (shark dive); the Sugar Wreck.

STARS OF THE SEA

Both bottlenose and spotted dolphins visit the bank, but it is the guaranteed encounters with the latter that have made the site famous. These wild pods of dolphins have been interacting with divers for 20 years, and now a booming industry has grown up around these wonderful animals. Although only snorkeling is permitted with the dolphins, divers who have the privilege to encounter them in these clear, shallow seas take away lifelong memories.

Bonaire

DUTCH ANTILLES

US
Atlantic Ocean
CUBA
Bonaire
CENTRAL AMERICA
Caracas
VENEZUELA

For conservationists, Bonaire is a beacon of hope in the Caribbean. More than 40 years ago, the island's authorities realized that good reef management could promote tourism and boost the local economy. Bonaire is particularly noted for fine shore diving.

FORWARD THINKING

Bonaire is the most eastern island in the group that makes up the Dutch Antilles. It has always demonstrated an enlightened attitude toward conservation, with protective laws first passed in 1961 (to protect turtles), followed by a steady stream of additional measures over subsequent years that eventually resulted in the establishment of a marine park that now encircles the island. This extends down to 200 ft (60 m).

ESSENTIAL INFORMATION

WATER TEMPERATURE 77–84°F (25–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT There is year-round diving on Bonaire, but hurricane season begins in the later part of the year.

MUST-SEES Town Pier at Kralendijk; the wreck of the *Hilma Hooker*.

SANDY SHORES

Bonaire offers a wealth of shore diving possibilities. Many divers simply turn up on the island, rent a car, and go exploring. The spontaneity of this kind of diving has a charm all of its own. As well as splendidly pristine reefs, Bonaire also has two notable wrecks in the *Hilma Hooker*, a freighter lying at 100 ft (30 m), and the *Red Slave*. Diving under the Town Pier at Kralendijk, and Salt Pier (on the other side of the island), is also very rewarding.

LEISURELY PACE Divers join a turtle in a tour over the lush reefs of Bonaire's shallow coastal waters.

Cayman Islands

SOUTHERN CARIBBEAN



The Caymans are three low-lying islands 150 miles (240 km) south of Cuba. Views of the islands above the water belie the riches that lie beneath—steep walls, fine reefs, and a very shallow dive that is famed among the diving fraternity.

CLEAR WATERS

The Cayman Islands have two key characteristics that make them a classic dive area: they lack any mountains or large rivers, and the limestone bedrock absorbs water. Consequently, there is very little sedimentary runoff from the land when it rains, which ensures that the visibility underwater is excellent. Added to this are steep walls, sandy lagoons, and 18 protected marine life reserves that ensure excellent diving.

ESSENTIAL INFORMATION

WATER TEMPERATURE 81–84°F (27–29°C)

ECOSYSTEM Tropical

WHEN TO VISIT Diving takes place in the Caymans year-round, although hurricane season starts late in the year.

MUST-SEES Stingrays in North Sound; the mantas of Bloody Bay Wall.

REEFS AND RAYS

The underwater environment is typified by shallow fringing reefs extending some way from shore, leading to busy reef crests and steep drop-offs. Large pelagics, such as mantas, eagle rays, and several species of sharks, drift past walls characterized by healthy fish populations and rich coral and sponge growth. The Caymans are famous for one particular stingray feeding site in North Sound, Grand Cayman, where as many as 200 stingrays cluster around divers in the shallows.

CLOSE ENCOUNTER
Stingrays gather to be fed at North Sound. Contact with them should always be on their terms.

Turks and Caicos

BAHAMAS, NORTHERN CARIBBEAN

US
Turks and Caicos
CUBA
Caribbean Sea
CENTRAL AMERICA

These two tiny island groups at the southeastern end of the Bahamas chain offer the diver true variety within a small area—from safe, shallow lagoons to steep walls and strong currents—with big animal encounters always possible.

DIVE PARADISE

The Turks and Caicos consist of two small clusters of islands on either side of the abyssal Turks Island Passage. To the west are the Caicos Islands, epitomized by shallow lagoons and gentle slopes. To the east, the smaller Turks Islands offer access to stunning drop-offs only a short boat ride from shore—although both sets of islands do have a range of dives within these broad categories, catering to the tentative beginner through to the hardened veteran.

THRIVING REEFS
A diver inspects growths of colorful tube sponges, which are a common sight on the reefs of the Turks and Caicos region.

PROTECTED STATUS

There are 33 protected areas within the Turks and Caicos, and these islands were the first in the entire Caribbean to ban spearfishing. As such, the marine life here is very impressive indeed, with healthy reefs dotted with huge sponges, and impressive pelagic activity in the form of dolphin encounters, gray reef, bull, and tiger sharks, as well as three resident species of turtles. In addition to these animals, large migrants also create excitement. From December through to April, the entire humpback whale population of the Atlantic passes through Turks Island Passage.

For wreck fans, the remains of the *Endymion*—a British warship that ran aground in 1790—offer a fascinating glimpse into naval history. Cannonballs and other relics can still be found on the seabed around the site. The wreck lies in shallow water 18 miles (30 km) south of Salt Cay; the site is readily accessible by boat.

ESSENTIAL INFORMATION

WATER TEMPERATURE 81–86°F (27–30°C)

ECOSYSTEM Tropical

WHEN TO VISIT Visit the Turks and Caicos between November and August

MUST-SEES Humpback whale migration, dolphin encounter; Northwest Point dives; the Tunnel; *Endymion* wreck.



Giant squirrelfish

Cuba

WESTERN ATLANTIC

US
THE BAHAMAS
Havana
CUBA
CENTRAL AMERICA
JAMAICA

It did not take long for Cuba's developing dive industry to draw the attention of the international diving community. Certain classic sites have been well known for years, but Cuba's vast and varied coastline has much more to offer traveling divers.

GIANT COASTLINE

Cuba is a huge island 90 miles (155 km) south of Florida, with 3,500 miles (5,630 km) of coastline bordered by the Gulf of Mexico to the west, the Atlantic to the north, and the Caribbean to the south. The scale of the island is such that each of the three reefs along the coast of Cuba exceeds the length of the entire Florida Keys.

ESSENTIAL INFORMATION

WATER TEMPERATURE 75–81°F (24–27°C)

ECOSYSTEM Tropical

WHEN TO VISIT Diving continues year-round in Cuba, but hurricane season begins late in the year.

MUST-SEES The Isle of Youth; bull shark dive at Santa Lucía; *Cristóbal* wreck.

MARINE DIVERSITY

A recent survey noted over 1,000 fish species around Cuba—tremendous diversity for this part of the world. There are also some excellent big-animal encounters to be experienced here, including some classic shark dives and large groups of tarpon.

CLASSIC CUBAN DIVES

Cuba has an abundance of riches in terms of dive sites, and some consider the diving here to be the best in the world. Diving on the Isle of Youth is particularly popular, but Santa Lucía, Guardalavaca, and Santiago de Cuba also offer excellent dives. The last of these boasts a particularly fine shore dive with the wreck of the *Cristóbal Colón*. This former Spanish warship was attacked by the US navy in 1898, during a brief conflict between the two countries provoked by the sinking of a US ship in Havana harbor. The *Cristóbal Colón* was run aground by its commander, and is now a splendid historical dive site.

SOFT OPTION
Soft corals and sponges grow in profusion in Cuban waters, which enjoy unusually high diversity in marine species.

Cenotes

YUCATÁN PENINSULA, MEXICO



A network of flooded caves filled with crystal-clear water, the Cenotes offer the novice a chance to dive caverns in relative safety. For the more intrepid, and appropriately trained, the honeycomb of tunnels and passages offers advanced exploration opportunities.

INNER SPACE
A diver surveys the eerie interior of the Cenotes cave network. Though the system offers difficult technical challenges, it also has easier dives.

GEOLOGICAL WONDER

In Mexico's Yucatán Peninsula, the best dives are not at the coast but take place some distance inland, within the honeycombed heart of the Earth itself. The term "Cenotes" (from the Mayan word *tzonot*) refers to the entrances to the network of flooded passages and caverns that riddle this region.

Over 60 million years ago, this entire region was beneath the sea, creating rock strata of limestone from compressed coral and marine organisms. In the intervening period, this soft rock has been shaped by rain and rivers, creating one of the finest cave and cavern diving locations on Earth.

DIVING THE CENOTES

Although explorations are still ongoing in the Cenotes, many of the systems are accessible even for novice divers, with guides taking groups into vast caverns where an exit to the surface is always available if required. Sea diving at Cancún and Cozumel is available nearby.

ESSENTIAL INFORMATION

WATER TEMPERATURE 66–77°F (19–25°C)

ECOSYSTEM Freshwater cave

WHEN TO VISIT The best time of year to dive the Cenotes is between November and March.

MUST-SEES Gran Cenote; Car Wash Cenote; coastal resorts nearby.



A SAFETY LINE
Special equipment helps ensure safe, enjoyable diving in caverns (*see pp.186–87*).

Belize Barrier Reef

BELIZE, CENTRAL AMERICA

CUBA
Yucatán
Belize City
Belize Barrier Reef
CENTRAL AMERICA

Belize is a small Central American country that has the good fortune to have a true natural marvel off its coastline. The Belize Barrier Reef is the longest in the Northern Hemisphere, and offers a vast range of diving possibilities for all skill levels.

SECLUDED COUNTRY

Belize covers around 8,880 sq miles (23,000 sq km) and has only 220,000 inhabitants. The country is renowned for its marine life, and due to the efforts of various voluntary organizations and its government, over 40 percent of Belize has been classified as a nature reserve.

THE BARRIER REEF

Belize also boasts a World Heritage Site—the Belize Barrier Reef. Extending for 174 miles (280 km) and ranging from 9 miles (14 km) to 19 miles (30 km) offshore, the reef offers a huge variety of divable sites to explore. Three of the four atolls in the Caribbean are found along the length of the reef. An atoll is a circular island that surrounds a lagoon, and is formed when coral reefs grow around the perimeter of a collapsed volcano. Linear sand and coral islands—known locally as cayes—also run

ESSENTIAL INFORMATION

WATER TEMPERATURE 77–82°F (25–28°C)

ECOSYSTEM Tropical

WHEN TO VISIT Diving in Belize takes place year-round, but the hurricane season begins around October.

MUST-SEES Whale sharks at Gladden Spit, Blue Hole, Shark Ray Alley.

along the length of the Barrier Reef, and provide a base for much of the area's dive activity. Of these, Ambergris Caye is the most popular location.

DIVING HIGHLIGHTS

Around 500 fish species swarm over the reef, including five different species of butterfly fish. Some larger animal species can also be seen, including huge jewfish and manta rays on the outer reef, and stingrays and nurse sharks at Shark Ray Alley. There are also healthy populations of reef sharks, as well as manatees (*see p.219*) in the shallow inshore waters and estuaries of the country.

While the most famous site in Belize is undoubtedly the Blue Hole, the area has a great deal more to offer, with classic reef dives, magnificent spur and groove reef formations, and some notable seasonal gatherings of big animals. At Gladden Spit in the south of the country, large numbers of whale sharks meet in feeding aggregations during the early part of the year. These huge ocean-going plankton-feeders grow to as much as 60 ft (18 m) in length.

THE BLUE HOLE

Perhaps the most famous site in Belize is the Blue Hole. Famously explored by Cousteau in 1972, this vast cavern lies 50 miles (80 km) off the east coast of Belize in the middle of Lighthouse Reef. Its perfectly circular entrance measures some 985 ft (300 m) in diameter, with the cavern plunging to a depth of 410 ft (125 m) beneath. The resident population of bull and lemon sharks in the interior of the Blue Hole is an eerie sight for divers visiting the stalactite formations found 130 ft (40 m) below the surface.

Aerial view of the Blue Hole



CYCLE OF LIFE
Whale sharks come to Belize to feed on the vast numbers of eggs generated by the mass spawning of a number of reef fish species, such as dog and cubera snappers, in spring.

Fernando de Noronha

WESTERN ATLANTIC



Rising up from the wild waters of the Atlantic, 250 miles (400 km) off the eastern coast of Brazil, is Fernando de Noronha. This tiny group of volcanic islands plays host to one of the largest resident pods of dolphins on Earth.

ATLANTIC TREASURE

The stark island group of Fernando de Noronha was for many years a well-kept secret among the Brazilian diving fraternity. The sea around the islands plunges to depths of over 2,300 ft (700 m), creating rich upwellings and swirling currents.

CLOSE ENCOUNTERS

Although the reefs here are relatively bare—only 95 fish species have been recorded on them—it is the big animal encounters that have made the site famous. Stories of extraordinary interactions with the huge resident pods of spinner dolphins around the islands have attracted divers who now travel here from around the world. Some 14 species of sharks, including nurse sharks and gray reef sharks, cruise over dark ridges, and two turtles are commonly sighted; one—the hawksbill—actually breeds here. The islands have been a World Heritage Site since 1981, a well-deserved status for this exciting site.

ESSENTIAL INFORMATION

WATER TEMPERATURE 70–79°F (21–26°C)

ECOSYSTEM Subtropical

WHEN TO VISIT Diving is best at Fernando de Noronha between September and March.

MUST-SEES Spinner dolphins at Baia dos Golfinhos; gray reef sharks at Laje dos Dois Irmãos.

WILD BEAUTY
Green, nutrient-rich Atlantic waters break against the rocky shores of Fernando de Noronha, a remote group of islands.



Cocos and Malpelo

EASTERN PACIFIC



Considered by many to be among the finest big animal dive sites on Earth, the two volcanic islands of Cocos and Malpelo sit several hundred miles from land amid the wild currents and big swells of the eastern Pacific ocean.

DOUBLE IDENTITY

Although Cocos and Malpelo are generally referred to in the same breath by divers, the two islands are actually 250 miles (400 km) apart—Cocos off the coast of Costa Rica, and Malpelo off the coast of Colombia.

MARINE SANCTUARY

Rising from the deep waters of the Pacific in a series of serrated volcanic reefs and craggy pinnacles, the two islands provide a fantastic opportunity to experience larger marine animals at close range. Schooling hammerheads, hunting white-tip reef sharks, patrolling silky and Galápagos sharks—are all virtually guaranteed. Spotted moray eels are present in huge numbers, and itinerant visitors include whale sharks, mantas, and a number of bill-fish species. Both islands have a protected status—Cocos is a World Heritage Site, and Malpelo a Colombian Flora and Fauna Sanctuary.

ESSENTIAL INFORMATION

WATER TEMPERATURE 63–75°F (17–24°C)

ECOSYSTEM Subtropical

WHEN TO VISIT Conditions are best from December to September.

MUST-SEES Hammerhead schools; spotted morays in Malpelo; white-tip reef sharks hunting prey.

MEETING PLACE
Sharks of many species congregate in numbers off Cocos Island. Use of a rebreather (*left*) allows close approaches.

TOUGH CONDITIONS

Diving on Cocos and Malpelo is demanding, with big swells, swirling currents, occasional limited visibility, and stark reefs. The rewards for braving the challenging conditions, however, are immense, given the ample opportunities for big animal encounters. Some shark species, especially hammerheads, are naturally wary of divers, but a careful approach can work wonders. Specialist equipment can help, too—rebreathers (*see pp.82–83*), which do not create bubbles, allow the diver to make an unobtrusive approach and thus give the best chance for close encounters.

Roca Partida

COLIMA STATE, MEXICO

US
Gulf of Mexico
La Paz
MEXICO
Guadalajara
Roca Partida

This stark volcanic pinnacle rises from the depths of the Pacific 200 miles (320 km) off the tip of the Baja Peninsula. This is truly wild diving, with powerful swells, big currents, and large marine species at one of the most isolated dive sites in the world.

SHEER DIVING

The most remote outcrop of the Archipelago of Revillagigedo (a group of four islands), Roca Partida rises starkly from the wild surface of the Pacific Ocean, its rugged silhouette reflecting the characteristics of the reefs beneath. Steep walls plunge into deep, dark water, with very little life encrusted on their barren surfaces.

BOUNTIFUL SEAS

The rich upwellings from deep water around Roca Partida provide plentiful nutrients and oxygen for circling fish shoals, including huge black jacks and dense schools of barracuda. These in turn attract silky, white-tip, silver-tip, and hammerhead sharks in great numbers. What makes this dive site so special, however, are the manta ray encounters, which are among the best to be had anywhere; these magnificent animals almost seem to seek out divers, resulting in some extraordinary interactions.

The reputation of Roca Partida is spreading, and it is rapidly becoming an iconic site in the diving world. Divers willing to make the journey to this remote and wild location will find themselves amply rewarded.

ESSENTIAL INFORMATION

WATER TEMPERATURE 66–77°F (19–25°C)

ECOSYSTEM Subtropical

WHEN TO VISIT Roca Partida has good, year-round diving, but cooler winter water is best for shark diversity.

MUST-SEES Manta rays; sleeping white-tip and silver-tip sharks; black jacks.

SHARK ENCOUNTERS
Divers at Roca Partida can count on being buzzed by many different sharks, such as the normally shy scalloped hammerhead.



Hawaii

CENTRAL PACIFIC OCEAN



The underwater terrain of Hawaii reflects its volcanic origins, with twisted lava formations and steep drop-offs into abyssal depths. The oceanic island group is world-renowned for its surfing, but offers exceptional diving, too.

ISLAND PARADISE

Hawaii is the world's longest island chain, extending more than 1,500 miles (2,400 km), and situated over 2,500 miles (4,000 km) from the mainland. It comprises eight main islands—each the top of a submerged volcano—as well as another 124 tiny areas of uninhabited land that amount to no more than 3 sq miles (8 sq km). The stark ridges and bizarre rock formations that epitomize Hawaii's terrain above sea level extend beneath the water's surface, offering exciting dive opportunities, and great wildlife encounters. Hawaii's extreme isolation means it is visited by nomadic species from the vast expanse of the Pacific Ocean. The most notable of the pelagic animals are humpback whales, pygmy pilot whales, manta rays, and oceanic white-tip sharks. Humpbacks have been hunted globally almost to extinction, and have become rare even in the waters around Hawaii. Excellent dive sites can be found on the island of Hawaii—or Big Island—at the eastern end of the island chain, as well as Maui, Kauai, and Oahu.

ESSENTIAL INFORMATION

WATER TEMPERATURE 75–81°F (24–27°C)

ECOSYSTEM Tropical

WHEN TO VISIT Year-round, but winter months at this busy site are less crowded.

MUST-SEES Manta rays at Kona Beach; pygmy pilot whales; Shark's Cove, Oahu; Molokai; Long Lava Tube, Big Island.

WAVE-SWEPT COASTLINE
Hawaii lies at the same latitude as central Mexico. Clean waters, pure sands, and a tropical climate add to its appeal as a dive destination.

Catalina Island

CALIFORNIA, UNITED STATES

US
Los Angeles
Catalina Island
MEXICO

Lying only 22 miles (35 km) off the coast of California is a spectacular island of dramatic scenery above the water, and tremendous beauty beneath. Catalina Island has been a nature reserve since 1974, with huge rewards for the diver.

PROTECTED ISLAND

Catalina Island is 20 miles (32 km) in length and 8 miles (13 km) wide, and has been owned by the Wrigley family since 1919. Avid conservationists, they have consistently refused permission for development on the island, and now 86 percent of it is an established nature reserve. The rugged topography of the island extends below the waterline, with tremendous diving on craggy reefs and steep underwater pinnacles.

RICH SEAS

The island is swept by the cold waters of the California Current as it moves down from British Colombia. This creates oxygen-rich waters where kelp forests flourish—some of the larger specimens stretch from surface to seabed, 100 ft (30 m) below. Cruising these underwater forests is a wide range of fish species, the most famous of which is the garibaldi. Fiercely territorial, these brightly colored fish will stand their ground as divers approach—a photographer's dream. The kelp forests are also home to huge black sea bass, eagle rays, California morays, and two-spot octopuses. The black sea bass is a particularly welcome sight, since it was once heavily overfished but is now making a comeback. Larger residents include the California sea lion, a species known for its curiosity and willingness to approach divers. The occasional blue shark can be encountered off Catalina's shores, rounding off an exhilarating list of animals waiting to be discovered here.

FOREST BENEATH THE WAVES
A rich variety of marine life is supported by the giant kelp stands of Catalina Island. Garibaldi fish are familiar residents of the kelp.

ESSENTIAL INFORMATION

WATER TEMPERATURE 54–68°F (12–20°C)

ECOSYSTEM Temperate

WHEN TO VISIT Diving takes place year-round off Catalina, but winter diving can be very cold.

MUST-SEES The Casino Point Underwater Park; The Farnsworth Banks.



California sea lions

The Outer Banks

NORTH CAROLINA, UNITED STATES



Famed in seafaring lore as the graveyard of ships, the Outer Banks are thought to be the site of up to 5,000 shipwrecks. Big ocean currents and an abundance of large pelagic animals combine to make this region one of the most exciting in the diving world.

HISTORIC WATERS

The Outer Banks are identified by a dramatic chain of islands and sandbars that extend for 130 miles (35 km) up the coast of North Carolina. Within this barrier is a vast area of estuary, shallow lagoons, and enclosed water. This ecological gem is a crucial breeding ground for many fish species, and 70 percent of the region enjoys protected status. The Outer Banks beyond the island chain are the real draw for the diver. With three great ocean currents meeting off this coastline, and the continental shelf only 40 miles (65 km) to the east, this is dramatic diving territory. The Outer Banks are littered with wrecks—many of them sunk by U-boats in World War II. Many of these are home to some of the larger residents of the banks, including numerous sand tiger sharks (also known as ragged-tooth sharks). These fierce-looking animals are in fact quite approachable if not provoked.

ESSENTIAL INFORMATION

WATER TEMPERATURE 54–75°F (12–24°C)

ECOSYSTEM Temperate

WHEN TO VISIT For the most favorable diving conditions, visit the Outer Banks between July and September.

MUST-SEES Wrecks of the *Papoose* and *Proteus*; sand tiger sharks.

FEARSOME APPEARANCE
Despite its looks, the sand tiger shark is relatively docile. However, like all large predators, it should be treated with respect.

The Great Lakes

CANADA/UNITED STATES



Straddling the border between Canada and the US, the five Great Lakes make up the largest expanse of fresh water on Earth. Conditions in the lakes can be demanding, but the reward is access to some of the best-preserved wrecks in the diving world.

WORLD-CLASS WRECKS

The Great Lakes cover an area of 95,000 sq miles (246,000 sq km), and offer a range of diving experiences and conditions. Many of the more densely populated regions around the lakes have always been significant industrial zones and have suffered through pollution and overexploitation. The water is cold, and visibility can be limited, although in the lower lakes it has improved through the accidental (and in all other respects unwanted) introduction of the zebra mussel—a voracious filter-feeder that has cleaned the lakes of algae. There are many wrecks on the various lake beds. The very low temperatures and the lack of salt in the water have kept metal hulls relatively free of rust, while wooden vessels and even rope can be found in a remarkably good state of preservation.

ESSENTIAL INFORMATION

WATER TEMPERATURE 32–64°F (0–18°C)

ECOSYSTEM Temperate

WHEN TO VISIT Year-round, but northern dives may be under ice in winter.

MUST-SEES Sea caves along Lake Superior coast; the *Arabia* and other well-preserved wrecks.

PRESERVING THE PAST

In the early days of diving the lakes, numerous artifacts were plundered from otherwise pristine wreck sites. This malpractice was quickly stamped out through the establishment of a number of preserves. Lake Michigan alone has nine such special areas, covering 1,900 sq miles (4,920 sq km). Notable wrecks throughout the lakes include the *Arabia*, a sailing vessel sunk in 1884 and still perfectly intact; the *Bermuda*, sunk in 1870; and the more contemporary *Mesquite*, sunk in 1989.

FRESHWATER OASIS
The pine-flanked shores of Lake Michigan, where nine preserves protect sensitive underwater resources.

Vancouver Island

BRITISH COLUMBIA, WESTERN CANADA

CANADA
British Columbia
Vancouver
US

The cold waters and strong tides around Vancouver Island create a glorious mix of wildlife, and there are also vessels sunk as artificial reefs to add extra interest for the visiting diver. Some of the most popular dives lie between the island and the mainland.

CHANNEL CROSSING

The standard means of reaching Vancouver Island is via a ferry from the city itself, a 90-minute journey that gives you a glimpse of the abundant waters of this region. Cold waters are rich in oxygen and nutrients, and the channel between the island and the mainland is no exception. The addition of strong tidal movements creates an irresistible draw for marine plants and animals, and although the diving can be demanding at times—for example, in the fast-running Dodds Narrows channel—there is much to make the experience worthwhile. One of the most famous residents of these waters is the inquisitive giant octopus, although more elusive wolf eels, harbor seals, various whale species (including orcas), and huge numbers of salmon may also be encountered at the right time of year.

ARTIFICIAL REEFS

The vessel *Saskatchewan* was sunk in 1997 as an artificial reef, and has proved a real hit with both local and visiting divers. It is just one of a number of decommissioned warships, all well worth a dive, sunk off the coast by the Artificial Reef Society of British Columbia—a society formed by a group of underwater archaeologists in 1990 to turn warships into dive sites.

EXTRAORDINARY ENCOUNTER
A diver makes contact with a giant octopus, a fascinating species that thrives in the nutrient-rich waters.

ESSENTIAL INFORMATION

WATER TEMPERATURE 48–64°F (9–18°C)

ECOSYSTEM Temperate

WHEN TO VISIT Year-round, but winter can be chilly.

MUST-SEES Giant octopuses; whales; wreck of the *Saskatchewan*; Dodds Narrows channel.

Galápagos Islands

EASTERN PACIFIC



The Galápagos were known as the Enchanted Isles by early mariners, baffled by the currents that swirled around them. The name has changed, but the experience remains the same for divers fortunate enough to visit this unique archipelago.

RUGGED AND REMOTE

The Galápagos Islands are named after the Spanish word for "saddle"—*galápago*—after the shape of the shells of the giant tortoises that provided a food source for the early explorers and whaling ships that visited the islands. The island group consists of 13 main islands situated 600 miles (970 km) off the west coast of Ecuador. These stark islands, only a few million years old, still show the contorted rock formations—twisted reefs and pitted ridges—caused by their volcanic birth. These provide an excellent substrate for busy marine communities, replenished by the seven ocean currents that converge on this island group from all directions.

ESSENTIAL INFORMATION

WATER TEMPERATURE 61–81°F (16–27°C)

ECOSYSTEM Temperate

WHEN TO VISIT Diving continues year-round in the Galápagos.

MUST-SEES Hammerheads and white-tips at Wolf and Darwin; whale sharks; sea lions; marine iguanas; penguins.

MARINE LIFE

Although there are only 13 reef-building species of coral in the Galápagos, meaning that the reefs are stark affairs clinging to the dark volcanic rock, the life that swarms over them is spectacular.

The fame of the Galápagos as a dive site lies in its gatherings of large marine animals, including magnificent schools of scalloped hammerheads. Sadly, overfishing has had a serious impact on shark populations in the waters around the islands, and unless circumstances change, such sightings may become increasingly rare. Groups of cow-nosed rays and eagle rays are regularly sighted off the more exposed reefs, as well as gatherings of manta rays and the occasional whale shark.

UNIQUE SPECIES

A visit to the Galápagos offers animal encounters that cannot be experienced elsewhere. The islands have evolved in isolation, and are home to a number of remarkable species. Perhaps the most famous of these is the marine iguana, although the islands also have colonies of the most northerly penguin species on Earth—the tiny Galápagos penguin. It is possible to snorkel with both of these species if accompanied by a knowledgeable local guide and with the right sea conditions.

WILD GALÁPAGOS

Visiting California sea lion

It is not surprising that the Galápagos Islands provided inspiration for Darwin's theory of evolution—they are rich in all kinds of life. There are well over 300 fish species in the region, including 30 species of sharks. Larger residents include nearly 80,000 seals and sea lions. There are also 600 species of mollusks and 100 different types of crabs! Larger visitors include sperm whales, humpbacks, and Bryde's whales, as well as many species of dolphins. The islands are a naturalist's paradise.

BARREN APPEARANCE
The bleak contours of the Galápagos Islands might seem to suggest a region devoid of life. The appearance is deceptive, however—life thrives here both above and below the green waters of the surrounding Pacific Ocean.

Useful resources

PADI: DIVE SAFETY CHECKLIST

- Divers should limit their depths according to their training, certification level, and experience.
- Regardless of level of training, any increase in diving depth should be incremental.
- Further training and/or supervision is needed when diving in a new type of environment.
- Avoid overweighting; carry out a buoyancy check whenever using new equipment. Remember to reduce weighting when going from salt to fresh water.
- Ensure that all weight systems used have a quick release and that each buddy is familiar with its operation.
- Always review emergency procedures prior to each dive.
- Have regular medical checkups and stay in shape for diving.
- If surface conditions, currents, or visibility deteriorate, consider aborting a dive.
- Consult tide tables where appropriate and seek local advice on prevailing diving conditions.
- Use surface marker buoys and ascent/descent lines wherever appropriate.
- Always inform a non-diver where you are going and when you expect to return.

Visit www.padi.com

PROJECT AWARE FOUNDATION: TEN WAYS A DIVER CAN PROTECT THE UNDERWATER ENVIRONMENT

Divers and snorkelers are obvious ambassadors for the underwater environment. Let's make sure we:

1. Dive carefully in fragile aquatic environments
Although at first they may look like rocks or plants, many aquatic organisms are fragile creatures that can be damaged or harmed by the bump of a tank, knee, or camera, a swipe of a fin, or even the touch of a hand. It is also important to know that some aquatic organisms, such as corals, are extremely slow-growing. By breaking off even a small piece, you may be destroying decades of growth. By being careful, you can prevent devastating and long-lasting damage to magnificent dive sites.

2. Streamline yourself
Much damage to the environment is done unknowingly. Keep your gauges and alternate air source secured so they don't drag over the reef or bottom. By controlling your buoyancy and taking care not to touch coral or other fragile organisms with your body, diving equipment, or camera, you will have done your part in preventing injury to aquatic life.

3. Continue your education
If you haven't dived in a while, your skills (particularly buoyancy control) may need sharpening. Before heading to the reefs, seek bottom time with a certified assistant or instructor in a pool or other environment that won't be damaged by a few bumps and scrapes. Better yet, take a diving continuing education course such as PADI Scuba Review, the PADI Adventures in Diving program, or a PADI Specialty Diver course. AWARE continuing education diving courses provide you with the skills practice and practical application of environmentally sound diving techniques.

4. Consider your impact on aquatic life through your interactions
Very few forms of aquatic life pose a threat to us. In fact, some creatures even seem friendly and curious about our presence. As we become bolder and more curious ourselves, we may even feel compelled to touch, handle, feed and even hitch rides on certain aquatic life. However, our actions may cause stress to the animal, interrupt feeding and mating behavior, introduce food items that are not healthy for the species, or even provoke aggressive behavior in normally nonaggressive species. Interact responsibly with the aquatic environment.

5. Understand and respect underwater life; resist the urge to collect souvenirs
Through adaptation to an aquatic environment, underwater life often differs greatly in appearance from life we are used to seeing on land. Many creatures only appear to look like plants or inanimate objects. Using them as "toys" or food for other animals can leave a trail of destruction that can disrupt a local ecosystem and rob other divers of the pleasure of observing or photographing these creatures. Consider taking part in a Project AWARE program to become more familiar with the importance of, and the interdependent nature of, worldwide aquatic

ecosystems. Dive sites that are heavily visited can be depleted of their resources in a short time. Collecting specimens, coral, and shells in these areas can strip their fascination and beauty. If you want to return from your dives with trophies to show friends and family, you may want to consider underwater photography instead.

6. Be an ECO-Tourist
Protected areas, such as parks, reserves, and sanctuaries, are one of the best tools for conserving the aquatic environment. Support the creation of protected areas, follow all local laws, and learn to appreciate that all aquatic habitats (such as grass beds, mangroves, and rubble zones) are important and interesting environments. Do not confine your diving only to sites highlighted in brochures and articles. When planning a diving trip, choose ECO Tour Operators involved with ECO-resorts and ECO-operators. Make informed decisions when selecting a destination, and support the Project AWARE Go ECO environmental campaign.

7. Respect the underwater cultural heritage
Divers and snorkelers have the privilege to access dive sites that are part of our cultural heritage or maritime history. You should help preserve these sites for future generations by obeying local laws, diving responsibly, and treating wrecks with respect. Wrecks can serve as important habitats for fish and other aquatic life.

8. Report environmental disturbances or destruction of your dive sites
Divers and snorkelers are in a unique position to monitor the health of local waterways, lakes, and coastal areas. If you observe an unusual depletion of aquatic life, a rash of injuries to aquatic animals, or strange substances or objects in the water, report them to your department of natural resources or similar entity.

9. Be a role model
As a diver or snorkeler, you realize that when someone throws a plastic wrapper or other debris overboard, it is not out of sight, out of mind. You see the results of such neglect. Set a good example in your own interactions with the environment, and other divers and non-divers will follow suit.

10. Get Involved
There are plenty of opportunities to show your support of a clean aquatic environment, including local beach cleanups, surveys, and attending public hearings on matters that impact local coastal areas and water resources. Divers' skills in particular are always needed and appreciated by many environmental organisations.

Visit www.projectaware.org for more details

Copyright Project AWARE Foundation 2004. All rights reserved.
Used with permission from Project AWARE Foundation.

USEFUL CONTACTS

Training organizations

International groups offering both basic and specialized dive instruction, including training organizations based on an amateur footing.

Professional Association of Dive Instructors (PADI)
www.padi.com

PADI Americas: 30151 Tomas Street, Rancho Santa Margarita, CA 92688-2125

PADI Europe: Oberwilerstrasse 3 CH-8442, Hettlingen, Switzerland

PADI Canada: 107 – 1680 Broadway Street, Port Coquitlam, BC V3C 2M8

National Association of Underwater Instructors (NAUI)
Worldwide headquarters: PO Box 89789,
Tampa, FL 33689-0413
www.naui.org

British Sub Aqua Club (BSAC)
Telford's Quay, South Pier Road,
Ellesmere Port, Cheshire, CH65 4FL, UK
www.bsac.com

Sub Aqua Association
Space Solutions Business Centre, Sefton Lane,
Maghull, Liverpool, L31 8BX, UK
www.saa.org.uk

Scottish Sub Aqua Club
The Cockburn Centre, 40 Bogmore Place,
Glasgow, G51 4TQ, UK
www.scotsac.com

Scuba Schools International
2619 Canton Court, Fort Collins,
CO 80525-4498
www.ssiusa.com

World Underwater Federation
Viale Tiziano, 74 00196, Roma, Italia
www.cmas2000.org

Technical Diving International
18 Elm Street, Topsham, Maine, 04086
www.tdisdi.com

International Association of Nitrox and Technical Divers
5609 Power Road, Ottawa, Ontario,
K1G 3N4
www.iantd.com

USEFUL CONTACTS (CONTINUED)

National Association for Cave Diving (NACD)
P.O. Box 14492, Gainesville, FL 32604
www.safecavediving.com

ACUC International (American Canadian Underwater Certifications)
379 West Street, Brantford, ON
N3R 3V9
www.acuc.ca

Governing bodies

Organizations promoting and regulating recreational diving activities.

World Underwater Federation
Viale Tiziano, 74 00196, Roma, Italy
www.cmas2000.org

International Association for the Development of Freediving (AIDA)
Rue du Petit-Beaulieu 4
CH 1004 Lausanne, Switzerland
www.aida-international.org

Freediving Regulations and Education Entity (FREE)
7480 NW 175 St., Miami, FL 33015
www.divingfree.com

International Association for Handicapped Divers
http://www.iahd.org

Conservation and heritage organizations

Charitable and nonprofit organizations promoting marine wildlife conservation, and groups involved in preserving maritime heritage.

Coral Cay Conservation
40-42 Osnaburgh Street, London,
NW1 3ND, UK
www.coralcay.org

World Wildlife Fund
1250 Twenty-Fourth Street, N.W.
P.O. Box 97180, Washington, DC
20090-7180
www.worldwildlife.org

Marine Conservation Society
Unit 3, Wolf Business Park, Alton Road,
Ross-on-Wye, Herefordshire, HR9 5NB, UK
www.mcsuk.org

British Divers Marine Life Rescue
Lime House, Regency Close Uckfield,
East Sussex, TN22 1DS, UK
www.bdmlr.org.uk/donate

Marine Fish Conservation Network
600 Pennsylvania Avenue, SE, Suite 210,
Washington, DC 20003
www.conservefish.org/site

Nautical Archaeology Society
The Nautical Archaeology Society,
Fort Cumberland, Fort Cumberland Road,
Portsmouth, PO4 9LD, UK
www.nasportsmouth.org.uk

Whale and Dolphin Conservation Society
Brookfield House, 38 St Paul Street,
Chippenham, Wiltshire, SN15 1LJ, UK

The Shark Trust
National Marine Aquarium, The Rope Walk
Coxside, Plymouth, PL4 OLF, UK
www.sharktrust.org/sharkconservation.html

Parks Canada (National Marine Conservation Areas of Canada)
25 Eddy Street, Gatineau, QC
K1A 0M5

Historical Diving Society
Historical Diving Society USA , PO Box 2837,
Santa Maria, CA 93457
www.hds.org

Historical Diving Society UK
www.thehds.com

Maritime Archaeological and Historical Society
P.O. Box 44382, L'Enfant Plaza, Washington,
DC 20026
www.mahsnet.org

Diving medicine and safety organizations

Expert advisory groups on diving medicine and safety issues.

Divers Alert Network (DAN)
The Peter B. Bennett Center, 6 West Colony
Place, Durham, NC 27705
www.diversalertnetwork.org

British Diving Safety Group
West Quay Road, Poole, BH15 1HZ, UK
www.bdsg.org

London Diving Chamber
Hospital of St John and St Elizabeth,
60 Grove End Road, St John's Wood,
London, NW8 9NH, UK

Glossary

ABSOLUTE PRESSURE The total *pressure* acting on a body, equal to the sum of *atmospheric pressure* and *gauge pressure*.

A-CLAMP FITTING A *regulator first stage* that attaches to the *pillar valve* of a *tank* by means of a yoke that clamps it securely in position.

AIR CONSUMPTION The depletion of oxygen in air through respiration; the rate at which air is used by a diver during the course of a dive.

ALTERNATE AIR SOURCE A redundant source of air supply, in the form of either an *octopus second stage*, or a completely independent *tank* and *regulator*.

AMBIENT PRESSURE The total *pressure* acting on a body at a given depth. See also *absolute pressure*.

ANCHOR LINE A rope, cable, or chain that attaches a ship to its anchor.

ANOXIA A medical condition caused by a lack, or severe deficiency of, oxygen in the human body.

AQUA LUNG The first underwater breathing apparatus to use compressed air and a two-stage *regulator*, designed by Emile Gagnan and Jacques Cousteau.

ARCHIPELAGO A group or chain of islands.

ARTIFICIAL REEF A human-made object deliberately scuttled to create a haven for marine life, and for the enjoyment of divers.

ASCENT Returning from depth to the surface at the end of a dive. This must always be performed carefully to avoid *decompression sickness*.

ATMOSPHERIC PRESSURE The *pressure* exerted by the gases in the atmosphere. At sea level, this is equal to 14.7 psi (1 bar).

ATOLL Circular *coral reef*, often surrounding a lagoon, that has formed around a submerged extinct volcano.

BALLAST Lead weights carried to offset the inherent *buoyancy* of the diver's *exposure suit*.

BENDS See *decompression sickness*

BEZEL A rotatable, notched, or marked outer ring on instruments, such as watches and compasses, used to mark key datum points, such as a bearing.

BLOCK SHIP A vessel sunk deliberately across the approaches to a naval harbor to bar entry to hostile submarines and surface ships.

BOMMIE An isolated outcrop of coral growth on the seabed.

BOYLE'S LAW Physical law stating that at a constant temperature, the volume of a gas is inversely proportional to the *pressure* exerted on it.

BRACKISH Water that is not as salty as seawater, but has a higher salt content than fresh water.

BREATH-HOLD DIVING See *freediving*

BUBBLE CHECK A precautionary visual inspection of another diver's gear (conducted underwater) to determine if it has any air leaks.

BUDDY A diver who assumes an informal duty of care over the other member of their assigned "buddy pair" during diving.

BUDDY LINE A safety line for tethering a *buddy* pair together.

BUOYANCY An upward thrust exerted on an immersed object, which is equal to the weight of the water that has been displaced by the object.

BUOYANCY COMPENSATOR (BC) A jacket that can be inflated and deflated to allow the diver to control their *buoyancy*.

BUOYANCY CONTROL Manipulation of *buoyancy* through the use of devices such as a *BC*, and the breathing cycle.

CAISSON A pressurized, watertight chamber used to undertake construction work underwater.

CERTIFICATION CARD Accreditation proving that a diver has achieved a certain level of dive training with one of the recognized agencies.

CORAL HEAD Protrusions on a *coral reef* formed by a colony of living coral polyps feeding and growing.

CORAL ISLAND Portion of a *coral reef* that is permanently out of water, its surface usually eroded to a flat top of white coral rock and sand. May occur in a chain along a reef.

CORAL REEF A massive, marine, rocklike ridge or outcrop created by the gradual accretion of the skeletons of generations of coral polyps.

DATUM LINE A line used as a fixed reference to aid in an accurate survey of an area.

DECOMPRESSION Returning to conditions of normal *atmospheric pressure* by controlled means.

DECOMPRESSION SCHEDULE A plan describing the number, duration, and depth of *decompression stops* required for a given dive.

DECOMPRESSION SICKNESS (DCS) A potentially dangerous medical condition resulting from the formation of bubbles of nitrogen in the bloodstream and tissues of a diver's body. Also known as decompression injury (DCI) and the bends.

DECOMPRESSION STOP A scheduled pause in a diver's ascent to allow nitrogen to pass from body tissues back into the blood at a safe rate.

DEHYDRATION A medical condition resulting from excessive loss of water from the body.

DELAYED SURFACE MARKER BUOY (DSMB) Marker buoy deployed just before ascent. It is inflated underwater, then released to indicate where a diver will surface.

DEMAND VALVE See *second stage*

DEPTH GAUGE An analog or digital gauge that measures *ambient pressure*, and uses this to give a reading of depth.

DESCENT Traveling from the surface to depth.

DIN FITTING A screw-thread fitting for attaching a *regulator first stage* to a compatible *pillar valve*. Allows higher working pressures than *A-clamp* fittings.

DISPLACEMENT The displacement of water that occurs when an object is submerged in it.

DISTANCE LINE A line fastened to a submerged feature and deployed from a *reel* as a navigational guide, especially in areas of low visibility.

DIVE CENTER A commercially run diving school and rental center, frequently offering organized trips and guides to local *dive sites*.

DIVE COMPUTER A digital device that provides the diver with a range of information, such as depth, time, and ascent rate.

DIVE CONSOLE An instrument panel incorporating a *tank contents gauge*, *depth gauge*, and sometimes also a compass, or a *dive computer*.

DIVE GUIDE An employee of a *dive center* or school who guides qualified divers around local *dive sites*.

DIVE LEADER The diver in a *buddy* pair who is designated (by agreement) as the principle pace-setter and decision-maker underwater.

DIVE MARSHAL A senior diver whose role on a dive trip is to allocate *buddy* pairs, approve *dive plans*, ensure that complete records of dives are kept, and initiate and direct rescue efforts in the event of a diving accident.

DIVE PLAN The outline of a proposed dive, including its depth, duration, intended goals, entry and exit points, signaling conventions, and contingency plans.

DIVE SITE Any location where diving is conducted.

DIVE SLATE A plastic tablet used for making notes underwater.

DIVE TIME The duration of a dive, starting at the moment the diver leaves the surface and ending with their return to the surface.

DIVEMASTER A person qualified to act as a *dive guide*, assist diving instructors, and oversee the organization of dives for paying customers.

DIVING CLUB An organization offering diving instruction and social events on an amateur basis. It can also refer to continental European diving centers offering instruction on a commercial basis.

DIVING SCHOOL A center for instruction in diving skills (usually on a commercial basis).

DPV (DIVER PROPULSION VEHICLE) A propulsion device either ridden or clung to by a diver to minimize swimming effort or aid in the exploration of large *dive sites*.

DRAG Frictional resistance to the motion of an object through a fluid.

DRIFT DIVE A dive in which the diver is propelled along a route by undersea currents.

D-RING A D-shaped ring of metal or plastic used as an anchor point for tethering equipment to your *BC* during a dive.

DROP-OFF A falling-away of the ground or seabed, such as a *reef wall* or rock shelf that descends steeply.

DRYSUIT An *exposure suit* designed for use in very cold waters, in which trapped air is the principle insulating medium, and that offers a high degree of thermal protection.

DSMB (DELAYED SURFACE MARKER BUOY) A tubular buoy designed to be deployed at the end of a dive to aid *ascent* and alert observers at the surface.

DUMP VALVE One-way valve used to release air from an inflatable device.

DYE MARKERS A fluorescent dye designed to be released into the water to alert rescue craft to the position of a drifting diver.

ECOSYSTEM The interactions between a community of living organisms and the environment they inhabit.

EL NIÑO A warming of the eastern tropical Pacific occurring every few years that has a pronounced effect on both the local and wider climate. Often occurs around Christmas time—"*El Niño*" in Spanish refers to the Christ child.

EQUALIZATION The process of "clearing" the ears and sinuses until the pressure within them matches the pressure of the water surrounding the body. See also *Valsalva maneuver*.

EXPOSURE SUIT Any suit worn by a diver in order to prevent excessive loss of body heat. See *wetsuits*, *semi-dry suits*, and *drysuits*.

FILTER-FEEDER An aquatic animal that feeds by straining minute organisms and other suspended food particles from the water.

FINNING Kicking the feet rhythmically while wearing fins to achieve forward motion.

FIRST STAGE A major component of the *regulator* that reduces the *pressure* of air from the tank to 8–10 bar above *ambient pressure*, then allows it to pass to the *second stage* for inhalation by the diver. It also supplies air for inflatable items such as the *BC*, and to *pressure gauges* displaying the remaining contents of the *tank*.

FOOD CHAIN A sequence of organisms, each depending on the next as a source of food.

FOOT POCKET A style of fin shoe that covers the whole foot.

FREE ASCENT An *ascent* that is carried out without the use of a line or any other point of reference.

FREEDIVING A form of diving in which divers do not carry an air supply but remain underwater only as long as they can hold their breath.

GAUGE PRESSURE The surrounding water pressure, as measured by a gauge that does not take *atmospheric pressure* into account.

GLOBAL POSITIONING SYSTEM (GPS) A navigation system that uses satellite signals to determine an exact longitude and latitude position.

GUIDELINE A line with a weight at one end and a buoy at the other, chiefly used to mark the position of wrecks and provide a guide for descending and ascending divers.

HELIOX A mixture of helium and oxygen, used for diving beyond *recreational diving* limits.

HYDROSTATIC TESTING A method of testing a *tank* for serviceability by filling it with pressurized water.

HYPERVENTILATION A medical condition caused by rapid or deep breathing, resulting in lowered carbon dioxide levels in the blood.

HYPOXIA A medical condition caused by a deficiency of oxygen in the human body.

INFLATOR VALVE A manually operated valve that admits compressed air into the buoyancy bladders of a *BC*, or into a *drysuit*.

KELP FOREST A marine *ecosystem* based around dense growths of seaweed belonging to the kelp family.

LIVEABOARD A recreational diving vessel equipped to conduct extended diving trips without returning to port.

LOG BOOK A record containing the details of individual dives made by a diver.

LONGSHORE CURRENT A current running parallel to the shoreline.

MANGROVE Assorted coastal tree and shrub species with aerial roots that grow in dense thickets along tidal shores in the tropics.

MARINE PARK An area of sea or coastline in which marine species are protected by government legislation.

MASK FOGGING Misting caused by the accumulation of oils on the lens (or lenses) of a diving mask, permitting moisture to condense there more readily.

MASK SQUEEZE Discomfort caused by increasing water *pressure* acting on the diver's mask, pressing its frame into the face.

MUCK DIVING Informal term for diving in areas where the bottom sediments are dark and coarse but where small marine species proliferate (such as Sulawesi's Lembeh Straits).

NEAP TIDE The point in the monthly cycle of tides where the gravitational influences of the Sun and Moon are least aligned, resulting in the lowest high tides and the highest low tides.

NEOPRENE A synthetic rubber fabric with good heat insulation properties used to make *wetsuits*.

NITROGEN NARCOSIS Intoxication caused by breathing nitrogen at elevated *partial pressures* (such as during deep dives), resulting in the impairment of reasoning and motor skills, feelings of irrational anxiety or elation, and perceptual narrowing.

NITROX Any mixture of nitrogen and oxygen prepared for use as a breathing gas, but normally one containing a greater percentage of oxygen than that found in air.

OCTOPUS SECOND STAGE A redundant *second stage*, carried by divers as a contingency against failure of the main second stage, and to enable air-sharing with a diver whose own air supply has been depleted.

OFF-GASSING The gradual release of gases (especially nitrogen) that have accumulated in a diver's body during the course of a dive. Off-gassing occurs as *ambient pressure* decreases during *ascent* and at the surface.

OPEN WATER A body of water that is not sheltered from the influence of naturally developing weather conditions and currents, and whose depth may exceed safe training limits.

O-RING A ring-shaped gasket, used to seal interfaces between one pressurized piece of equipment and another, such as in the *pillar valve* of a *tank*.

OVERHANG A projection from the face of a reef, cliff, etc.

OVERHEAD ENVIRONMENT Any diving environment where direct access to the surface is restricted, such as inside a cave or under ice.

OXYGEN TOXICITY Acute nervous system dysfunction caused by breathing oxygen at elevated pressures. Can cause loss of consciousness and convulsions.

PARTIAL PRESSURE The *pressure* of a single gas in a mixture of gases, measured as if that gas alone were present (the total pressure of a gas mixture being the sum of the *partial pressures* of its constituent gases).

PELAGIC ANIMALS Creatures that dwell in the *open ocean*, rather than coastal waters.

PILLAR VALVE The valve that transfers gas from the diver's *tank* to the *regulator first stage*.

PLANKTON Minute free-floating plant and animal organisms inhabiting seas and lakes, which form the basis of the *food chain* in many environments.

PLB (personal locator beacon) A submersible device that emits a radio signal on an internationally recognized search-and-rescue homing frequency, enabling emergency services to pinpoint its location.

POLAR SEAS The cold seas at the polar extremities of the planet, which vary in temperature from 29°F to 50°F (–1.8°C to 10°C).

PONY BOTTLE A small *tank* of breathing gas with an independent *regulator*, intended for emergency use if the diver's main breathing apparatus fails.

PRESSURE The exertion of force by one surface, substance, or gas onto another.

REBREATHER A breathing apparatus that recycles exhaled gas by filtering out carbon dioxide and replacing any oxygen metabolized by the diver.

RECOMPRESSION CHAMBER A pressure chamber used in the treatment of divers suffering from *decompression sickness*.

RECREATIONAL DIVING Sports diving that takes place within certain depth and environmental limitations, as defined by the various training agencies.

REEF WALL A vertical face of coral growth, often descending into deep waters.

REEL A spooling device used to store and deploy line.

REFRACTION The change in the velocity of light (or any propagating wave) that occurs when it passes from one medium to another (e.g., from air to water).

REGULATOR The mechanism that supplies breathing gas from the *tank* to the diver via a two-stage process of *pressure* reduction. The regulator is made up of two parts: the *first stage* and the *second stage*.

RIB (rigid inflatable boat) A fast utility boat characterized by a V-shaped hull with an inflatable tube running around its upper edge.

RIP CURRENT A fast-moving current running perpendicular to the shore, caused by the action of incoming waves.

RULE OF THIRDS, THE A rule of thumb used when calculating air requirements for a dive, especially one requiring a conservative approach, such as a cavern exploration.

SAFETY SAUSAGE See *SMB*

SAFETY STOP A precautionary pause in a diver's *ascent* to prevent the formation of nitrogen bubbles in the bloodstream. Its purpose is as a failsafe against *decompression sickness* even when no scheduled *decompression stops* need to be made.

SALINITY The salt content of a measure of water.

SCUBA Acronym for "self-contained underwater breathing apparatus."

SECOND STAGE The part of the *regulator* that regulates the *pressure* of a diver's gas supply to the same pressure as its immediate environment.

SEMI-DRY SUIT A thick *neoprene exposure suit*, similar to a *wetsuit*, designed for use in cold waters.

SHELTERED WATER A shallow body of water protected from currents and weather conditions, used for training divers in a controlled environment.

SILTING A rapid reduction in underwater visibility that occurs when fine sedimentary particles are stirred up.

SKINSUIT A thin *exposure suit*, typically made of Lycra, designed for use in tropical waters.

SLACK WATER A period of reduced water movement that occurs between incoming and outgoing tides.

SMB (surface marker buoy) An inflatable buoy designed to be towed behind a diver to indicate their position to observers on the surface. Long, cylinder-shaped SMBs are known as safety sausages.

SNORKELING Swimming face-down at the surface using a short, curved tube to draw breath.

SPG (SUBMERSIBLE PRESSURE GAUGE) See *tank contents gauge*

SPRING TIDE The point in the monthly cycle of tides when the highest high tides, and lowest low tides occur. Spring tides occur when the gravitational forces of the Sun and the Moon are aligned.

SPUR AND GROOVE REEF FORMATION A typical growth structure of coral reefs, in which outcrops of coral are separated by linear depressions.

STANDING CURRENT A continuous directional movement of water generated by prevailing weather, sea, and climatic conditions.

STROBE A beacon that emits high-intensity flashes of light at short intervals.

SUBTROPICAL SEAS Warm seas within a loosely defined zone between *temperate* and *tropical* climatic conditions.

SWELL The undulating motion of surface waters in areas of open sea.

SWIM-THROUGH A submerged arch, or short passage of rock, where direct access to the surface is restricted, but in which the exit is clearly visible at all times.

TANK A steel or aluminum container designed to hold compressed gas.

TANK CONTENTS GAUGE An instrument that displays the remaining quantity of air or other breathing gas in a diver's *tank*. Also known as a submersible pressure gauge (SPG) or pressure gauge.

TECHNICAL DIVING The use of special breathing-gas mixtures, such as *Nitrox*, *Trimix*, and *Heliox*, to extend depth limits and dive durations beyond *recreational diving* limits.

TEMPERATE SEAS Seas of an intermediate temperature between *tropical* and *polar*, typically 50–68°F (10–20°C).

TEST DATE The date when a compressed gas *tank* was last subjected to *hydrostatic testing*.

THERMOCLINE A layer in a body of water in which temperature changes rapidly with depth. This is usually between a warm surface layer and colder deep water.

TIDAL CURRENT A current generated by the action of the tides.

TIDAL CYCLE The cyclic rise and fall of shoreline sea level, caused by the gravitational influence of the Moon and Sun.

TOPOGRAPHY The shape or form of a region of land or seabed.

TRIMIX A mixture of oxygen, helium, and nitrogen commonly used as a breathing gas for dives deeper than 165 ft (50 m).

TROPICAL SEAS The seas found within the boundaries of the 68°F (20°C) isotherm—a band of warm equatorial water.

VALSALVA MANEUVER A method of manually increasing *pressure* on the inside of the eardrum by closing the nasal passage and exerting expiratory effort, forcing air through the eustachian tubes into the inner ear.

WATER COLUMN The zone of water between the surface and the bottom of a lake, sea, or river.

WEIGHT SYSTEM The means by which a diver's lead *ballast* is secured.

WETSUIT An *exposure suit* made of *neoprene* rubber, which traps a thin layer of water against the skin as an insulating medium.

WICKING The absorption of moisture into a fabric by capillary action.

WORKING PRESSURE The normal *pressure* at which an equipment item is designed to operate.

WORLD HERITAGE SITE An area of natural or cultural importance protected by a United Nations treaty.

WRECK Remains of ships, aircraft, or other vehicles found on the seabed.

INDEX

A

absolute pressure 94
accessories 80–81
Africa 256–65
aims of dive 160–61
air, composition 96
air tanks *see* tanks
air dumps, buoyancy compensators 56, 57
air-horns 76–77
air leaks 114
air-lock tank bands 81
air pressure
  equalizing 98–99, 114–15
  gauges 64, 65
  pressure tests 162
  regulators 60–61
  tanks 68
air-pumps 24
air supply
  air-sharing procedures 62, 140
  breathing compressed gas 96–97
  calculating consumption 96, 117, 168–69
  problem-solving 138, 140
  rebreathers 26, 29, 82–83
  see also tanks
air travel 239
alcohol 155
Alexander the Great 22
Aliwal Shoal 206, 259
Allen keys 88
aluminum tanks 68
ambient pressure, regulators 60
Americas 306–27
ammunition, wreck diving 170
Andaman Sea
  Andaman Islands 275
  Similan Islands 274
ankle weights 71, 123
Antarctic 212–13
Aqua Lungs 27–28
archaeology 192–93
  wreck diving 166, 169–70
Arctic 212–13
argon, suit inflation tanks 69
Aristotle 22
arm exercises 152–53
arthropods 230
artificial reefs 19, 325
artificial ventilation (AV) 141
ascent 128–31
  buoyancy control 119–20
  controlled buoyant ascents 140–41
  decompression dives 128, 130
  decompression stops 101, 129, 130
ascent *cont'd.*
  dive computers 66, 67
  equalizing pressure 98–99
  free ascents 128, 140
  nitrogen in bloodstream 100
  safe rate of 130
  water pressure and 95
Asia 270–81
asthma 32
Atlantic Ocean
  Cuba 314
  Fernando de Noronha 318
  Little Bahamas Bank 310
atmospheric pressure 94
Australasia 282–93
Australia
  Great Barrier Reef 282, 284–85
  Ningaloo Reef 289
  Tasmania 288
  wreck of the *Yongala* 287
autonomous diving, history 26

B

back exercises 153
back injuries 151
backup flashlights 72, 73
backward rolls 113
bags 79, 238
Bahamas
  Little Bahamas Bank 310
  Turks and Caicos 313
Baikal, Lake 271
ballast *see* weights
batteries, flashlights 72, 73, 184
beaches, exiting on to 132
beacons, personal locator 76
Belize Barrier Reef 172, 316–17
belts, weight 43, 70, 71
"the bends" *see* decompression sickness
Bengal, Bay of
  Andaman Islands 275
  Similan Islands 274
Bert, Paul 25
Bikini Atoll 299
blood vessels
  decompression sickness 142
  nitrogen bubbles 100
Blue Hole, Belize 317
boats 109
  depth indicators 101
  entering water from 113
  exiting on to 133
  liveaboards 237
  signaling to 132–33
body
  effects of water pressure 93, 98–99
  nitrogen accumulation 100–01
Bonaire 311
bony fish 224–27
boots 43, 48, 50
Bora Bora 300
bottles *see* tanks
Boyle's law 95
brain, decompression sickness 142
Breathing Observation Bubble (BOB) 82
breathing underwater 116–17
  artificial ventilation 141
  ascents 130
  buddy breathing 140
  buoyancy control 120–21, 146
  compressed gas 96–97
  decompression sickness 142
  freediving 190
  overcoming panic 141
briefing
  buddy 111
  debriefing 135
  pre-dive 165
Bristol Channel, Lundy 252
Britain
  Hebrides 246–47
  Isles of Scilly 250
  Lundy 252
  Scapa Flow 248–49
British Columbia 325
The Brothers 266
BSAC (British Sub-Aqua Club) 35
bubble check 114, 115
buddies 136
  air-sharing procedures 62, 140
  ascents 128, 129
  attracting attention 81
  briefing 111
  buddy breathing 140
  buddy check 110
  descents 114–15
  diving with new buddies 108
  emergency lifts 141
  entering water 113
  exchanging masks with 147
  hand signals 144–5
  ice diving 188
  losing sight of 139
  night diving 185
buoyancy
  breathing and 97
  buoyancy control 118–21
  cavern diving 186–87
  developing skills 146
  drysuits 54
  emergency lifts 141
  flashlights 73
  freshwater environments 216
  neutral buoyancy 97, 116, 118, 119
  swimming profile 123
  and weight loss or gain 150

buoyancy compensators (BCs) 28, 43, 56–59
  ascents 129
  buddy check 110
  buoyancy control 118–20
  caring for 58
  checking for damage 85
  controlled buoyant ascents 140–41
  designs 59
  disassembly 87
  fixings and fastenings 57
  history 27
  inflating and deflating 56
  integrated safety devices 77
  problem-solving 139
  removing and replacing 148–49
  servicing 58
  signaling devices 81
  technical diving 195
  water pressure and 95
  weight distribution 121
  weight pockets 70
buoys *see* surface marker buoys
Butler, Steve 27
buzzers 81

C

caissons 24, 25
California 322
California, Gulf of 206–207
cameras 45, 176–83
camouflage, flatfish 226
Canada
  Great Lakes 324
  Vancouver Island 325
carbohydrates 154
carbon dioxide
  closed-circuit systems 26
  and overexertion 97
  panic attacks 150
  rebreathers 82, 83
cardiovascular fitness 150, 151
careers in diving 196–97
Caribbean
  Bonaire 311
  Cayman Islands 312
  Little Bahamas Bank 310
  Turks and Caicos 313
Caroline Islands
  Truk Lagoon 302–303
  Yap 298
Catalina Island 322
Cavalli Islands 292
cave diving 80, 186
cavern diving 72, 186–87
  Blue Hole, Belize 317
  Cenotes 315
  Sardina 244
Cayman Islands 312
Celebes Sea 276–77
Cenotes 315
Central America 316–17
cephalopods 230–32
CFT/IUC (Irish Underwater Council) 35
children, learning to dive 38
clips 81
closed-circuit rebreathers (CCRs) 83
closed-circuit systems 26
CMAS (Confédération Mondial des Activités Subaquatiques) 35
cnidarians 233
Cocos 206, 319
cold-water diving
  equipment 44–45
  hypothermia 45, 93
  ice diving 188–89
  Norwegian fjords 253
  regulators 63
colds 99, 154
colors, underwater 92, 183
comb jellies 233
commercial diving 196–97
communication *see* signals
compasses 43, 65, 81, 125, 126–127
compressed air *see* air pressure; air supply
computers *see* dive computers
confidence-building exercises 147
conservation diving 172–75
consoles 64–65
  with dive computers 66
  regulators 61
  types of 65
contact lenses 47
controlled buoyant ascents 140–41
Coral Cay Conservation 172
coral reefs *see* reefs
Coral Sea 286
corals 233
Corlieu, Louis de 27
corrective lenses, masks 47
Cortez, Sea of 206–207
Cousteau, Jacques 15, 27, 28, 176, 291
crocodiles 229
crushed neoprene drysuits 54
crustaceans 230
Crystal River 309
Cuba 314
currents 102–03
  descents 119
  drift dives 74
  guidelines 129
  navigational aids 125
  safety 117
Cyprus 242

D

Dahab 267
damage, checking gear for 84–85
day bags 79
Dean, John and Charles 24–25
debriefing 135
decompression
  ascents 128, 130
  decompression stops 101, 129, 130
  high-altitude diving 94, 216
  technical diving 195
decompression sickness (DCS) 24, 25, 142–43
  deep decompression stops 66
  dive computers 66, 67
  overweight divers 150
decongestants 99, 154
dehydration 154, 155
delayed surface marker buoys (DSMB) 44, 74–75, 76
  ascents without a line 128–129
  deploying 130–31
  reels 75
  types of 75
demand valves *see* second stages
Denarouze, Auguste 26, 27
depths
  depth gauges 64, 65
  depth indicators 101
  distance lines 75
  dive computers 66
  dive tables 66–67
  freediving 29, 191
  mixed-gas diving 29
  rebreathers 83
  technical diving 194, 195
  using compressed air 29
  and water pressure 94–95
descents 114–15
  buoyancy control 118–19
  equalizing pressure 98–99
  water pressure and 95
diaphragms, regulators 61, 63
diet 154, 155
disabled divers 33, 38–39
disassembling gear 86–87
distance, measuring 126
distance lines 75, 127
distress flares 76
dive computers 28–29, 43, 53, 66–7
  ascents 128
  avoiding decompression sickness 101
  choosing 67
  consoles 65
  night diving 184
  technical diving 195
  types of 66

- dive operators 236–37, 238, 239
- dive tables 66–67, 101
- divemasters 236–37
- Diver Propulsion Devices (DPVs) 29, 80, 82
- diving barrels 24
- diving bells 23
- diving clubs 34
- diving environment 91–103
- diving helmets 24–25
- diving schools 34–35
- diving suits 43, 50–55
  - exposure protection 50
  - history 22–23, 24–25
  - layers 51
- dizziness 99
- dolphins 215, 218, 219, 310
- down signal 114
- Draeger company 26
- drift dives, surface marker buoys 74
- drinks 135, 154
- dry bags 79
- drysuits 45, 50, 54–55
  - ankle weights 71
  - buoyancy control 118, 120
  - fastenings and seals 55
  - inflating with air 55
  - layers 51
- dugongs 218, 219
- dust caps, regulators 87
- Dutch Antilles 311
- Dutch East India Company 24
- dye markers 77

E

- ears
  - equalizing pressure 98–99, 114–15
  - infections 99, 155
  - pressure underwater 93
  - surfer's ear 22
- echinoderms 232–33
- ecosystems 201
- Egypt
  - The Brothers 266
  - Dahab 267
  - wreck of the *Thistlegorm* 268–69
- emergency lifts 141
- emergency signals 132, 141
- English Channel 250
- entry into water 112–13
- epilepsy 39
- equipment 41–89
  - accessories and advanced gear 44
  - anticipating problems 137
  - bags 79, 238
  - buddy check 110
  - buoyancy compensation devices 56–59
  - cold-water diving 44–45
  - confidence-building exercises 147–49
  - core equipment 43
  - costs 33
  - disassembly 86–87
  - dive computers 66–67
  - diving suits 50–55
  - fins 48–49
  - flashlights 72–73
  - freediving 190
  - gadgets and accessories 80–81
  - gauges and consoles 64–65
  - gear assembly 84–85, 110
  - ice diving 189
  - knives 78
  - maintenance 88–89
  - masks 46–47
  - new technology 82–83
  - packing 163
  - post-dive tasks 134
  - regulators 60–63
  - renting 33, 42, 238–39
  - safety and signaling devices 76–77
  - snorkels 48
  - surface marker buoys 74–75
  - technical diving 195
  - tanks 68–69
  - weight systems 70–71
- Europe 240–55
- exercise 151–53
- expeditions 237
- extended vision masks 47
- extreme cold-water diving 45
- eyes, masks 46–47

F

- facemasks *see* masks
- fastenings 81
- Fernando de Noronha 206, 318
- Fiji 304
- films 176–77, 180–83
- fin pivots 119, 146
- fins 27, 48–49
  - cavern diving 187
  - exiting on to shore 132
  - finning technique 122
  - freediving 190
  - swimming with one fin 147
  - types of 49
  - wreck diving 168
- first stages, regulator 43, 60–61, 63
- fish
  - bony fish 224–27
  - coral reefs 202
  - as navigational aids 125
  - polar waters 213
  - sharks 220–21
  - skates and rays 222–23
  - wreck diving 166
- fitness 32–33, 150–55
- fjords, Norwegian 253
- flags 76, 77
- flares, distress 76
- flash, underwater photography 183
- flashlights 44, 53, 72–73
  - burn time 72–73
  - cavern diving 186
  - night diving 184, 185
  - signaling devices 77
  - wreck diving 169
- Fleuss, Henry 26
- flippers *see* fins
- floating *see* buoyancy
- Florida
  - Crystal River 309
  - Florida Keys 308
- flutter kick 123
- fogging, masks 111
- food 135, 154, 155
- Force Fins 48, 49
- free ascents 128, 140
- free descents 115
- freediving 29, 190–91
- Frenzy, Maurice 27
- freshwater environments 216–17
- Friendly Islands 305
- frog kick 123, 168, 187
- frogmen, World War II 83
- full-face masks 47

G

- gadgets 80–81
- Gagnan, Emile 27
- Galápagos Islands 326–27
- games, confidence-building 148
- Gansbaai 258
- gases
  - effect of water pressure on 95
  - *see also* carbon dioxide; nitrogen; oxygen
- gauges 64–65
  - cold-water diving 44
  - gauge pressure 94
  - night diving 184
  - types of 65
- giant stride entry 113
- Gilpatric, Guy 26
- glasses, wearing masks 47
- gloves 50, 55
  - cold-water diving 45
  - ice diving 189
  - reef gloves 51
- Great Barrier Reef 282, 284–85
- Great Lakes 324
- group dives, guidelines 115
- guidelines 115, 129, 168
- Gulf Stream 103, 240
- gut, pressure underwater 93, 98

H

Haldane, J. S. 25
Halley, Edmund 23
hand signals *see* signals
harnesses 70, 110
Hass, Hans 176
Hawaii 321
hearing, underwater 92–93
heat, underwater 93
Hebrides 246–47
heliox 194, 195
helium, technical diving 195
Herodotus 22
high-altitude lakes 94, 216
high-intensity discharge lights 73
hinged fins 49
history of diving 21–29
hoods 50, 99
  cold-water diving 45, 55, 189
horns, signaling devices 76–77
hoses
  checking for damage 85
  octopus 62
  problem-solving 139
  regulators 89
hydration 154
hydrostatic testing, tanks 68
hydrothermal vents, Iceland 254
hypothermia 45, 93

I

ice diving 188–89
  equipment 45, 189
  polar waters 213
  signals and safety 188–89
  White Sea 255
Iceland 254
iguana, marine 228–29
illness 108, 154
"incident pit" 137
Indian Ocean
  Andaman Islands 275
  Maldives 272–73
  Mauritius 265
  Seychelles 264
  Similan Islands 274
Indonesia 276–77
industrial diving 196–97
inflator valves 54, 55, 84
instructors 34
instrument consoles 43
insulation
  drysuits 51, 54
  semi-dry suits 53
  wetsuits 51, 52
insurance 239
integrated breathing buoyancy compensators 59
integrated weight buoyancy compensators 59
invertebrates 230–33
Ireland 251
Isles of Scilly 250
Italy
  Sardinia 244
  Ustica Island 245

J

jackets *see* buoyancy compensation devices
jellyfish 231, 233
jetboots 80

K

kelp forests 12, 125, 209, 210
kicking strokes 123
knives 43, 78
krill 212

L

ladders, exiting onto 133
lakes 94, 216–17
lamps *see* flashlights
lanyards 72, 81
Larnaca harbor 241, 242
lead weights 70
learning to dive 32–39
  basic training 36–37
  special training courses 38–39
  where to learn 34–35
leg exercises 152
lenses
  camera 182
  mask 47
Lethbridge, John 24
lifting techniques 151
light
  night diving 184
  photography 179, 183
  strobe lights 76, 77
  underwater 92
  see also flashlights
lines
  and ascents 128–29
  cavern diving 187
  decompression stops 129
  delayed surface marker buoys 130–31
  and descents 115
  distance lines 75, 127
  guidelines 115, 129
  ice diving 188
  surface marker buoys 74, 75
  wreck diving 168
Little Bahamas Bank 310
liveaboards 237
lizards 228–29
log books 135
longshore currents 103
Lundy 252
lungs
  decompression sickness 142
  fitness 150
  pressure underwater 98
Lycra skinsuits 51

M

Mackintosh, Charles 24
magnifying glasses 175
maintenance, equipment 88–89
Maldives 272–73
Malpelo 206, 319
mammals 218–19
manatees 218, 219, 309
mangrove swamps 203
mapping sites 124–25
Mariana Trench 12
Marine Protected Areas (MPAs) 172
marine wildlife *see* wildlife
marker buoys *see* surface marker buoys
Marlborough Sound 293
marlin 215
Marshall Islands, Bikini Atoll 299
masks 46–47
  clearing water from 37, 139
  cold-water diving 44
  designs 47
  exchanging with buddy 147
  fogging 111
  freediving 190
  head-up displays 82
  "hide the mask" 148
  history 26
  integral radio systems 82
  removing and replacing 147
matte finish masks 47
Mauritius 265
Medas Islands 243
medical checks 155
Mediterranean 206–207
  Medas Islands 243
  Sardinia 244
  Ustica Island 245
  wreck of the *Zenobia* 241, 242
membrane drysuits 54, 55
mesh bags 79
Mexico
  Cenotes 31
  Roca Partida 206, 320
Micronesia 296–97
Middle East 256, 266–69
Mikhail Lermontov, wreck of 293
military diving 197
mixed-gas diving *see* technical diving
mollusks 230–32
moon, tides 102
moving underwater 122–23

Mozambique 262–63
MP3 players 29
multi-gas dive computers 66
multi-tools 78, 88
muscles, exercises 151–53
music, MP3 players 29

N

narcosis, nitrogen 96, 101, 144, 195
Natal 260, 261
nature diving 172–75
NAUI (National Association of Underwater Instructors) 35
navigation underwater 124–27
neoprene
  drysuits 54, 55
  gloves 45
  semi-dry suits 53
  skinsuits 51
  wetsuits 52
neutral buoyancy 97, 116, 118, 119
New Zealand 282
  Poor Knights Islands 290–91
  wreck of *Mikhail Lermontov* 293
  wreck of *Rainbow Warrior* 292
night diving 184–85
Ningaloo Reef 289
nitrogen
  accumulation in body tissues 100–01
  breathing compressed gas 96
  decompression sickness 25, 142–43
  narcosis 96, 101, 144, 195
  overweight divers 150
  rebreathers 83
  technical diving 97, 194–95
nitrox
  tanks 68, 69
  oxygen-compatible regulators 63
  technical diving 194–95
North America 306
Norwegian fjords 253
nosebleeds 99
nutrition 135, 154, 155

O

O-rings
  cameras 176, 179
  checking for damage 85
  maintenance 88
  tank valves 69
Oceania 294–305
oceans 12
  marine wildlife 200–201
  open oceans 214–15
  tides and currents 102–03
octopus second stages 43, 61, 62, 63
  malfunctioning regulators 138
  out-of-air procedure with buddy 140
OK signal 113, 114, 133
open-circuit systems 26, 27
Orkney Isles 248–49
out-of-air procedure with buddy 140
Outer Banks 323
overweight divers 150
oxygen
  breathing compressed gas 96
  for decompression sickness 142
  freediving 190
  rebreathers 82–83
  technical diving 97, 194–95
  toxic effects 96–7
oxygen-compatible regulators 63

P

Pacific Ocean
  Bikini Atoll 299
  Bora Bora 300
  Cocos 206, 319
  Coral Sea 286
  Fiji 304
  Galápagos Islands 326–27
  Hawaii 321
  Malpelo 206, 319
  Oceania 294–305
  Palau 296–97
  Papua New Guinea 278–79
  Tonga 305
  Truk Lagoon 302–303
  wreck of the *President Coolidge* 301
  Yap 298
packing equipment 163
PADI (Professional Association of Diving Instructors) 11, 35, 238
Palau 296–97
panic attacks 141, 150
Papua New Guinea 278–79
pearl diving 23
personal locator beacons (PLBs) 76
Philippines 280–81
phosphorescence 184
photography 175, 176–83
physics, depths and pressure 94–95
phytoplankton 209, 214
pinnipeds 218, 219
pistol-grip flashlights 73
plankton 201
  as navigational aids 125
  open oceans 214–15
plankton *cont'd.*
  phosphorescence 184
  subtropical seas 207
  temperate seas 208, 209
planning dives 160–65
poison, stingrays 223
polar waters 212–13
police diving 197
pony bottles 68, 186
Poor Knights Islands 290–91
porpoises 218, 219
post-dive tasks 134
pouch-style weight belts 70
pre-dive briefing 111, 165
pre-dive checks 108–11
pregnancy 33
President Coolidge, wreck of 301
pressure *see* air pressure; water pressure
problem-solving 136–41
professional diving 159, 196–97
propulsion underwater 122–23
Protea Banks 261

Q

qualifications 32
Queensland
  Great Barrier Reef 282, 284–85
  wreck of the *Yongala* 287

R

radio
  distress signals 76
  integral systems in masks 82
  radio-updated dive computers 66
Rainbow Warrior, wreck of 292
rays 201, 222–23
rebreathers 26, 29, 82–83
recall signals 93
rechargeable flashlights 73
recreational diving 158–59
Red Sea 256
  The Brothers 266
  Dahab 267
  wreck of the *Thistlegorm* 268–69
reeds, breathing through 22
reefs 16–17, 202–203
  artificial 19, 325
  Asia 270
  Belize Barrier Reef 316–17
  Cayman Islands 312
  destruction of 204–205
  Florida Keys 308
  Galápagos Islands 326–27
  Great Barrier Reef 282, 284–85
  Hebrides 247
  Lundy 252

reefs *cont'd.*
  as navigational aids 125
  Ningaloo Reef 289
  "no-touch" rule 172
  Sodwana Bay 260
reels, surface marker buoys 44, 74, 75
reflective signals 77
refraction, light 92
regulators 43, 60–63
  air-pressure gauges 64, 65
  bags 79
  buddy check 110
  buoyancy compensators 56
  checking for damage 85
  choosing 63
  clearing 116
  development of 27
  disassembly 86–87
  environmentally sealed 45, 189
  first stages 43, 60–61, 63
  functions 96
  gear assembly 84
  hoses 89
  ice diving 45, 189
  pressure tests 162
  problem-solving 138
  second stages 43, 60–66, 69
  technical diving 63, 195
  types of 63
  see also octopus second stages
renting equipment 33, 42, 238–39
reptiles 228–29
research
  nature and conservation diving 174
  planning a trip 160–61
  wrecks 171
rigid inflatable boats (RIBs) 133, 134
rip currents 103
rivers 216
Roca Partida 206, 320
rocks, exiting onto 132
Rouquayrol, Benoit 26, 27
Rule of Thirds, air consumption 117, 168–69
Russia, White Sea 255

S

SAA (Sub-Aqua Association) 35
safety 15
  ascents 130
  cavern diving 186
  dive computers 67
  ice diving 188–89
  learning to dive 37
  night diving 185
  planning dives 161
  rays 223
safety *cont'd.*
  safety and signaling devices 76–77
sailfish 215
salt, washing gear 134
sand ripples, navigational aids 125
Sardinia 244
Sargassum weed 214
Scapa Flow 248–49
Scilly Isles 250
scooters 29, 80
Scotland
  Hebrides 246–47
  Scapa Flow 248–49
Scuba Rangers 38
Scyllis 22
sea grass beds 203
sea otters 218, 219
sea urchins 233
seals, drysuits 55
seals, wildlife 219
seasickness tablets 109
seated entry 112
seawater, density 94, 118, 216
seaweed 209
second stages 43, 60–66, 69
  octopus 61, 62, 63
security, bags 79
semi-closed rebreathers (SCRs) 83
semi-dry suits 53
semi wing buoyancy compensators 59
Seychelles 264
shakers 81
sharks 209, 220–21, 258, 261, 266
shears 78
ships *see* wreck diving
shore
  diving from 109, 112
  exiting onto 132
shortie wetsuits 50, 51
shoulder exercises 153
Sicily 245
side view masks 47
Siebe, Augustus 25
signals
  ascents 128
  attracting buddy's attention 81
  emergencies 132, 141
  entering water 113
  hand signals 93, 144–45
  hearing underwater 92–93
  ice diving 188
  night diving 184, 185
  OK signal 113, 114, 133
  out-of-air 140
  recall signals 93
  signaling devices 76–77
  signaling to boats 132–33
Similan Islands 274
sinking problems 114
sinuses, pressure underwater 93, 98–99
sirenians 218, 219
sites
  choosing 161
  site-specific planning 164–65
skates 222
The Skelligs 251
skinsuits 51
slack water 102, 125, 127
slates 44, 81
Smeaton, John 24
snakes, sea 228
snorkeling fins 49
snorkels 26–27, 48
Society Islands 300
Sodwana Bay 260
sound, underwater 92–93
South Africa
  Aliwal Shoal 259
  Gansbaai 258
  Protea Banks 261
  Sodwana Bay 260
South America 306
Spain 243
special gas mixes *see* technical diving
split fins 48, 49
sponges 233
SSAC (Scottish Sub-Aqua Club) 35
SSI (Scuba Schools International) 35
standing currents 103
starfish 232–33
steel tanks 68
stills photography 178–79
stomach, pressure underwater 98
storage, dive gear 87
strobe lights 76, 77
submersible pressure gauges (SPG) 64
submersible vehicles 29
subtropical wildlife 206–07
suit inflation tanks 68, 69
suits *see* diving suits
Sulawesi, North 276–77
Sun, as navigational aid 125
surf, entering water through 112
surface marker buoys (SMB) 44, 74–75
  cold-water diving 44
  delayed surface marker buoys (DSMBs) 44, 74–75, 76, 128–29, 130–31
  night diving 185
surface skills 132–33
surfer's ear 22
swimmer kick 123
swimmer's ear 99, 155
swimming underwater 122–23

T

talcum powder 50
tank pingers 81
tanks 43, 68–69
  air-lock tank bands 81
  air-pressure gauges 64, 65
  attaching to buoyancy compensators 57
  cavern diving 186
  checking for damage 85
  disassembly 86–87
  gear assembly 84–85
  ice diving 189
  maintenance 69, 88
  pressure tests 162
  problem-solving 139
  storage 69
  tank pingers 81
  technical diving 195
  types of 68
  valves 69
Tasmania 288
technical diving 158
  equipment 195
  special gas mixes 69, 97, 194–95
temperate wildlife 208–11
temperatures 93
  choosing diving suits 50
  cold-water diving 44–45, 63, 253
  hypothermia 45, 93
  ice diving 188–89
  open oceans 214
  polar waters 212
  temperate seas 208
test stamps, tanks 68
thermal undersuits 45, 55
thermometers 65
Thistlegorm, wreck of 268–69
tides 102–03, 125, 161
time, extending dive times 194–95
timetabling trips 162
Tonga 305
tool kits 88
torso exercises 153
tour operators 238
training *see* learning to dive
travel, air 239
travel buoyancy compensators 59
travel cases 79
trim, buoyancy control 121
trimix 69, 194, 195
tropical wildlife 202–05
Truk Lagoon 302–3
tuna 209, 215
Turks and Caicos 313
turtles 19, 228, 229
twin-set tanks 68, 69

UV

Ufano, Diego 23
umbilical flashlights 73
unconsciousness, emergency lifts 141
undersuits, thermal 45, 55
United States of America
  Catalina Island 322
  Crystal River 309
  Florida Keys 308
  Great Lakes 324
  Outer Banks 323
Ustica Island 245
vacations 236–39
Valsalva maneuver 93, 99
valves
  demand valves 43, 60–61, 69
  inflator valves 54, 55, 84
Vancouver Island 325
Vanuatu 301
vertigo 99
videography 175, 180–83
vintage-style regulators 63
virgin wrecks 170–71
voluntary work
  conservation diving 172–74
  underwater archaeology 192

W

washing equipment 134
watches 64
water
  density 94, 118, 216
  entry into 112–13
water pressure
  depth and 94
  effect on body 93, 98–99
  effect on gases 95
weather forecasts 108, 109
weights 43, 70–71
  buddy check 110
  buoyancy control 118
  descents 114
  harnesses 70
  jettisoning 120, 121, 140
  refining 148
  removing belt underwater 139
  securing weights 71
  swimming profile 123
  weight distribution 121
  weighted lines 115
wetsuits 50
  buoyancy control 118
  caring for 52
  full-length 52
  layers 51
  shortie 50, 51
whales 212, 218–19
wheeled dive bags 238
whistles 76–77
White Sea 255
wildlife 12, 199–233
  fish 220–27
  freshwater environments 216
  invertebrates 230–33
  mammals 218–19
  nature and conservation diving 172–75
  open oceans 214–15
  polar waters 212–13
  reptiles 228–29
  subtropical seas 206–07
  temperate seas 208–11
  timing dives 161
  tropical seas 202–05
  wreck diving 166
wing buoyancy compensators 59, 195
women's buoyancy compensators 59
wooden ships, wreck diving 170
World War II, frogmen 83
worms, segmented 233
wreck diving 18, 166–71
  Bikini Atoll 299
  Bonaire 311
  The Brothers 266
  Cuba 314
  Europe 240
  freshwater environments 216
  Great Lakes 324
  Isles of Scilly 250
  Mikhail Lermontov 293
  navigational aids 125
  New Zealand 282, 292–3
  night diving 185
  Oceania 294
  Palau 296
  Papua New Guinea 278–9
  Philippines 281
  President Coolidge 301
  Rainbow Warrior 292
  Sardina 244
  Scapa Flow 248–9
  Thistlegorm 268–9
  Truk Lagoon 302
  Yongala 287
  Zenobia 241, 242
writing underwater 81

XYZ

Yap 298
Yongala, wreck of 287
Yucatan Peninsula 315
Zenobia, wreck of 241, 242
zippers, drysuits 55

ACKNOWLEDGMENTS

Authors' Acknowledgments

Monty Halls (www.montyhalls.co.uk) would like to thank: Oceanic, Gates Housings, Fourth Element, Ed Poore of Poseidon Diving, the Hilton Hotel in Dahab, Dave Moore—the finest diver I have ever met—and in particular Dr. Antje Steinfurth.

Miranda Krestovnikoff would like to thank: Bristol University Sub Aqua club for introducing me to the world of diving, and Damian Wozniak and Tim Walsh for their thorough training and inspiration; DIVER magazine for giving me opportunities to visit exotic diving destinations and for publishing the resulting articles; and Dave Shaw, Dive Services UK, Phil Bullen, and Richard Bull for attentive and solid buddy support when diving commercially. Both Monty and I would like to thank Dan Burton for his spectacular photography in this book and for making initial contacts with DK to make it all possible. Thanks also to the editors for working with Monty and me, taking our abstract scribbles and turning them into this dive guide. Most importantly, a huge thank you to my husband, Nicholas, who has been immensely patient and supportive during book writing, and for my baby daughter, Amélie, who waited to emerge until after my deadlines were met!

Publisher's Acknowledgments

Dorling Kindersley and cobalt id would like to thank the following for their invaluable help with this book: Dr. Kim Bryan and Letitia Luff for editorial assistance; Hilary Bird for indexing; Christine Heilman for Americanization; and Stephen Dye for specialist advice. Special thanks to Poseidon Divers (www.poseidondivers.com) for their generous provision of diving equipment and expert advice during the photographic shoot in Dahab, and for the help of Mark Rogers, Katie Rogers, and Sophia Crook, who kindly agreed to act as models; and to Dan Burton for technical guidance throughout the production of this book. Many thanks also to John Womack of Otter Watersports (www.drysuits.co.uk) for allowing us to use his products and premises for photographic purposes; Vicky Boateng and Catwalk Model Management; the team at PADI UK for kindly arranging permission for us to reprint PADI advisory texts; Coral Cay for providing images of their work in marine conservation; and Fraser Bathgate for advice on, and images of, adaptive training techniques.

We also extend our thanks to the following manufacturers who kindly contributed images and products for the production of this book: Mares, Tabata USA (TUSA), Aqua Lung, Apeks Marine Equipment, AP Valves, Delta P Technology, Seemann, Diving Unlimited International Inc., Bob Evans Designs Inc., Mazin Submersible Technology Inc., SpecialFins Ltd, Northern Diver, Inon Inc., Sea & Sea, Canon Inc., Pentax, DZ Active Systems, HydroOptix LLC, Ocean Reef, Nikon Corporation, McMahon Precision Engineering Ltd, Ambient Pressure Diving Ltd, Bright Weights, Fujifilm, Ikelite, and Underwater Kinetics. Jetboots™ are manufactured by Mazin Submersible Technology, Inc. (www.jetboots.com). Force Fins are manufactured by Bob Evans Designs Inc. (www.forcefin.com).

Picture credits

The publisher would like to thank the following for their kind permission to reproduce their photographs:

Abbreviations key: t = top; b = bottom; l = left; r = right; c = center; rh = running header.

4 Dan Burton; **6–7** Kevin Davidson; **8–9t** Kevin Davidson; **8cr** Dorling Kindersley/Dave King/Courtesy of the North Wind Undersea Institute, New York; **9cl** iStockphoto/Andy Lim; **9cr** iStockphoto/Ian Scott; **10–19rh** Dan Burton; **10bl** Linda Pitkin; **10c** Alamy/POPPERFOTO; **11b** Ross & Diane Armstrong; **11tr** Dan Burton; **12–13b** Tony White; **13br** Ross & Diane Armstrong; **13tl** Dan Burton; **14** Dan Burton; **15bl** Linda Pitkin; **15tr** Dan Burton; **16b** Dan Burton; **16tl** Dan Burton; **16tr** Kevin Davidson; **18** Linda Pitkin; **19b** Kevin Davidson; **19tl** Kevin Davidson; **19tr** Linda Pitkin; **20–21** Getty/Hulton Archive/Fox Photos; **22–29rh** Dorling Kindersley/Dave King/Courtesy of the North Wind Undersea Institute, New York; **22cl** Mary Evans Picture Library; **23c** Alamy/POPPERFOTO; **23tr** Mary Evans Picture Library; **24c** Mary Evans Picture Library; **24tr** Mary Evans Picture Library; **25c** Corbis/Bettmann; **26c** Dorling Kindersley/Alex Wilson/Courtesy of the Charlestown Shipwreck and Heritage Centre, Cornwall; **26tl** Mary Evans Picture Library/Dr David Lewis Hodgson; **27t** Corbis/Bettmann; **28c** Kevin Davidson; **29tr** Dan Burton; **30–31** Dan Burton; **33tr** Dorling Kindersley/John Davis; **34–35b** Dan Burton; **34c** Kevin Davidson; **35tr** Kevin Davidson; **38–39b** Dan Burton; **38tc** Fraser Bathgate; **39br** Alamy/David Fleetham; **40–41** Dan Burton; **45t** Dan Burton; **46–47b** Kevin Davidson; **47b** Mares; **47c1** Mares; **47c2** Northern Diver; **47c3** Ocean Reef; **47c4** Ocean Reef; **47t1** Mares; **47t2** Mares; **48cr1** Tabata USA (TUSA); **48cr2** Aqua Lung; **49c1** Mares; **49c2** Tabata USA (TUSA); **49c3** Tabata USA (TUSA); **49t1** Aqua Lung; **49t2** Bob Evans Designs Inc. (Force Fin); **51bl1** Tabata USA (TUSA); **51bl2** Tabata USA (TUSA); **52bc1** Mares; **52bc2** Mares; **52t** Dan Burton; **54br** Diving Unlimited International Ltd; **54tr** Nataliya Chervyakova; **55cr2** Mares; **56b** Dan Burton; **58c** Kevin Davidson; **58t** Kevin Davidson; **59l1** AP Valves; **59l2** Mares; **59l3** Mares; **59l4** Tabata USA (TUSA); **59l5** Aqua Lung; **59r1** AP Valves; **59r2** Mares; **59r3** Apeks Marine Equipment; **59r4** Tabata USA (TUSA); **59r5** Aqua Lung; **60b** Kevin Davidson; **61br** Aqua Lung; **63br** Kevin Davidson; **63tr1** Tabata USA (TUSA); **63tr2** Aqua Lung; **63tr3** Mares; **63tr4** Apeks Marine Equipment; **63tr5** Aqua Lung; **64bc** Mares; **64bl** Mares; **65b** Corbis/Todd Gipstein; **65tr1** Apeks Marine Equipment; **65tr2** Mares; **65tr3** Apeks Marine Equipment; **65tr4** Mares; **66b2** Mares; **66b3** Tabata USA (TUSA); **67cl** Mares; **68c** Dan Burton; **69b** Kevin Davidson; **70br1** Seemann; **70br2** Mares; **70cr1** Mares; **71bl** Bright Weights; **72tr3** Kevin Davidson; **74b** Alamy/GUILLEN PHOTOGRAPHY; **75bl1** AP Valves; **75bl2** AP Valves; **75bl3** AP Valves; **75t** Dorling Kindersley/Demetrio Carrasco/Rough Guides; **76c** Dan Burton; **77b** Dan Burton; **77cl1** Aqua Lung; **77cl2** AP Valves; **79br1** Mares; **79br2** Mares; **79br5** Apeks Marine Equipment; **79cr** Alamy/Jack Sullivan; **80b** Dan Burton; **81br** Mares; **81c** Alamy/GUILLEN PHOTOGRAPHY; **82bl** Alamy/Stephen Frink Collection; **82c** HydroOptix LLC; **82tr** Ocean Reef; **83bl** Dan Burton; **90-91** Dan Burton; **92–103rh** iStockphoto/Dennis Sabo; **92bc** Alamy/Chris A Crumley; **95bc** Kevin Davidson; **97cr** Kevin Davidson; **98cr** iStockphoto/Daniel Gustavsson; **99c** Kevin Davidson; **100tc** iStockphoto/Dennis Sabo; **101tc** Kevin Davidson; **102tc** iStockphoto/Kevin Bergen; **103bc** Kevin Davidson; **109br** iStockphoto/

Joe Gough; **109tr** Alamy/Nick Hanna; **113bl** Dorling Kindersley/Brian Pitkin; **117br** Mares; **122bl** Kevin Davidson; **125tc** Linda Pitkin; **129tl** Dan Burton; **132tr** Dan Burton; **135tc** Paul Reid; **136bc** Kevin Davidson; **137tc** Kevin Davidson; **141tr** Dan Burton; **152-153c** Kevin Davidson; **152tr** Dorling Kindersley/John Davis; **153tl** Dorling Kindersley/John Davis; **153tr** Dorling Kindersley/John Davis; **154cr** Dorling Kindersley/Sian Irvine; **154tc** Dorling Kindersley/Andrew Whittuck; **156-157** Dan Burton; **159cl** Nataliya Chervyakova; **160b** Ross & Diane Armstrong; **160tc** Marek Walisiewicz; **161br** Nataliya Chervyakova; **161tl** Poseidon Divers; **162c** Marek Walisiewicz; **163t** Dan Burton; **164bl** Dan Burton; **165tl** Dan Burton; **166bl** Kevin Davidson; **166tc** Kevin Davidson; **167** Linda Pitkin; **168t** Kevin Davidson; **169b** Dan Burton; **169tr** Dan Burton; **170b** Alamy/Stephen Frink Collection; **171br** iStockphoto/Lara Seregni; **171tl** Alamy/POPPERFOTO; **172tc** Coral Cay Conservation; **173b** Kevin Davidson; **173tr** Coral Cay Conservation; **174b** Coral Cay Conservation; **175br** Alamy/Sarkis Images; **175t** Dan Burton; **176bl** Ross & Diane Armstrong; **176tr** Tony White; **177b** Dan Burton; **177tr** Kevin Davidson; **178bc** Pentax; **178bl** Nikon Corporation; **178br** Fujifilm; **178tr** iStockphoto/Dennis Sabo; **179c** Inon Inc.; **179cl** Pentax; **179cr** Inon Inc.; **179t** Sea & Sea; **180bl** Canon Inc.; **180br** Canon Inc.; **180tc** Alamy/Roger Munns; **181b** Dan Burton; **181tc** Sea & Sea; **181tl** Sea & Sea; **181tr** Sea & Sea; **182b** Kevin Davidson; **182tc** Kevin Davidson; **184bl** Sea & Sea/Underwater Kinetics; **184tr** iStockphoto/Rob New; **185t** Dan Burton; **186bl** Dan Burton; **186cr** Tabata USA (TUSA); **187t** Ross & Diane Armstrong; **188bl** Dan Burton; **188c** Mares; **189c** Dan Burton; **189t** Dan Burton; **190bl** Dan Burton; **190c** Mares; **190cr** SpecialFins Ltd; **191br2** Dorling Kindersley/Michael Moran; **191** Dan Burton; **192-193b** Dan Burton; **192bl** Alamy/Hugh Sitton Photography; **193tl** Dan Burton; **194bl** Dan Burton; **195br** Dan Burton; **195t** Dan Burton; **196-197b** Dan Burton; **196bl** Alamy/Henry Owen; **197tl** Dan Burton; **197tr** Corbis/The Cover Story; **198-199** Dan Burton; **200–233rh** iStockphoto/Johnny Lye; **200tc** Tony White; **201b** Kevin Davidson; **201tr** Kevin Davidson; **202bl** iStockphoto/Dan Schmitt; **202tr** iStockphoto/Steven Tulissi; **203b** Linda Pitkin; **203tr** Kevin Davidson; **204cr** Alamy/STOCK IMAGE/PIXLAND; **205** Linda Pitkin; **206b** Dorling Kindersley/Demetrio Carrasco; **206tr** Alamy/GUILLEN PHOTOGRAPHY; **207bc** Alamy/Reinhard Dirscherl; **208-209b** Dan Burton; **209br** Dorling Kindersley/Kim Taylor and Jane Burton; **209tr** iStockphoto/Sue Loader; **210b** Ross & Diane Armstrong; **210tr** Alamy/Robert E. Barber; **211** Linda Pitkin; **212-213b** iStockphoto/vera bogaerts; **212bl** Dorling Kindersley/Harry Taylor; **212tr** iStockphoto/sandra minarik; **213tr** Nataliya Chervyakova; **214-215b** Linda Pitkin; **214cl** Alamy/Michael Patrick O'Neill; **215tr** Tony White; **216bl** iStockphoto/George Hoeylaerts; **216c** Dorling Kindersley/Jerry Young; **216tr** iStockphoto/Vera Bogaerts; **217** Alamy/Visual&Written SL; **218b** Dorling Kindersley/Ken Findlay; **219br** Dorling Kindersley/Frank Greenaway; **219t** Alamy/George McCallum Photography; **220-221tc** Tony White; **220bl** Kevin Davidson; **221br2** Dorling Kindersley/Frank Greenaway; **222-223b** Kevin Davidson; **223tr** Kevin Davidson; **224b** Kevin Davidson; **224c** iStockphoto/Steffen Foerster; **225t** Kevin Davidson; **226bl** Alamy/Reinhard Dirscherl; **226tr** Tony White; **227** Kevin Davidson; **228bl** Linda Pitkin; **228cr** Tony White; **229bc** Kevin Davidson; **230bl** Tony White; **230tr** iStockphoto/Simon Edwin; **231** Kevin Davidson; **232-233b** Ross & Diane Armstrong; **232tc** Tony White; **233br** Linda Pitkin; **234-235** Linda Pitkin; **236–327rh** Dan Burton; **236-237b** Dan Burton; **236cr** Nataliya Chervyakova; **237tr** Dan Burton; **238bl** Mares; **238t** Dan Burton; **239b** iStockphoto/Lisa Kyle Young; **239tr** Dan Burton; **240b** Dorling Kindersley/Frits Solvang; **240tr** Dorling Kindersley/Francesca Yorke; **241** Dan Burton; **242b** Dan Burton; **243bc** Alamy/Wolfgang Pölzer; **243cr** Dorling Kindersley/Ian Aitken/Rough Guides; **244cr** Alamy/Reinhard Dirscherl; **245b** iStockphoto/Dan Schmitt; **246bc** Alamy/Worldwide Picture Library; **247tr** Dan Burton; **248bl** Alamy/Worldwide Picture Library; **249bc** Dan Burton; **249tr** Corbis/Bettmann; **250bl** Dorling Kindersley/Frank Greenaway; **250c** Alamy/Trevor Smithers ARPS; **251b** Alamy/David Lyons; **252cr** Dan Burton; **253b** Dorling Kindersley/Linda Whitwam; **254b** iStockphoto/Nancy Barr-Raper; **255cr** Nataliya Chervyakova; **256bl** Dan Burton; **256c** Linda Pitkin; **257** Linda Pitkin; **258c** Tony White; **259b** Dan Burton; **260b** Dan Burton; **260c** Alamy/Peter Pinnock; **261c** Tony White; **262–263b** Dan Burton; **263tr** Dan Burton; **264b** Linda Pitkin; **265c** Alamy/Jon Arnold Images; **266c** Dan Burton; **267b** Dan Burton; **268tr** Dan Burton; **269bc** Dan Burton; **270bl** Dan Burton; **271bc** iStockphoto/Chartchai Meesangnin; **271tr** Ross & Diane Armstrong; **272-273c** Dan Burton; **273tr** Dan Burton; **274tr** Alamy/Reinhard Dirscherl; **275bc** Dan Burton; **276br** Linda Pitkin; **276c** Ikelite; **277bc** Tony White; **278bl** Linda Pitkin; **279bc** Ross & Diane Armstrong; **280bl** iStockphoto/Erik de Graaf; **281br** Kevin Davidson; **281tc** Alamy/F. Jack Jackson; **282bl** Dan Burton; **282tc** Ross & Diane Armstrong; **284bl** Dan Burton; **285bc** Alamy/Iconsinternational.Com; **285tl** Dorling Kindersley/Alan Williams; **286bc** Dan Burton; **287tr** Dan Burton; **288bc** Tony White; **289bc** Andy Salmon; **290bc** Dan Burton; **291br** Ross & Diane Armstrong; **291tc** Ross & Diane Armstrong; **292tr** Corbis/Greenpeace/Sygma; **293br** Dan Burton; **294-295c** Dan Burton; **294bl** Dan Burton; **295tr** Kevin Davidson; **296br** Dan Burton; **297** Kevin Davidson; **298bl** Dan Burton; **299bc** Corbis/Claude Rives/Mer Images; **299br** Alamy/POPPERFOTO; **300b** Alamy/Chad Ehlers; **301br** Dan Burton; **302bl** Dan Burton; **303** Dan Burton; **304bc** Alamy/Stephen Frink Collection; **304cr** Alamy/David Fleetham; **305b** Tony White; **306b** Alamy/Chris A Crumley; **306c** Linda Pitkin; **307** Linda Pitkin; **308c** Dan Burton; **309b** Dan Burton; **309cr** iStockphoto/Wayne Johnson; **310c** Alamy/Stephen Frink Collection; **311b** Linda Pitkin; **312b** Dan Burton; **313bc** Alamy/ImageState; **313cr** Alamy/OceanPix.com; **314bl** Linda Pitkin; **315c** Alamy/Gavin Newman; **316–317b** Alamy/Brandon Cole Marine Photography; **317cr** Alamy/Brandon Cole Marine Photography; **318b** Alamy/Andre Seale; **319c** Ambient Pressure Diving Ltd; **319cr** Alamy/Jeff Rotman; **320b** Alamy/Wolfgang Pölzer; **321b** Dorling Kindersley/Rob Reichenfeld; **322bc** iStockphoto/William Smith; **322cr** Linda Pitkin; **323b** Tony White; **324b** Alamy/Visions of America, LLC; **325br** Alamy/Wolfgang Pölzer; **326–327b** iStockphoto/Dan Cooper; **327tr** Linda Pitkin.

All maps on pages 200, 204, and 242–326 are Mountain High Maps® copyright © 1993 Digital Wisdom, Inc.

Every effort has been made to trace the copyright holders. The publisher apologizes for any unintentional omissions and would be pleased, in such cases, to place an acknowledgment in future editions of this book.

All other images © Dorling Kindersley
For further information, see **www.dkimages.com**

IMST-00005709-001 - Copyright 2007 photolibrary.com

Surveying

Rai University

EVOLVING THINKING MINDS

Chapter 1

CHAIN, COMPASS AND PLANE TABLE SURVEYING

Structure of this unit

CHAIN, COMPASS, PLANE TABLE SURVEYING

Learning Objectives

1. CHAIN
2. field and office work
3. Ranging and Chaining
4. Reciprocal ranging
5. Well-conditioned triangles.
6. COMPASS
7. Prismatic compass
8. Surveyor’s compass
9. Bearing systems and conversions
10. Local attraction – Magnetic declination dip
11. Traversing – Plotting – Adjustment of error.
12. PLANE TABLE SURVEYING : Plane table instruments and accessories – merits and demerits – methods – Radiation- Intersection – Resection – Traversing.

1.1 Surveying

Surveying techniques have existed throughout much of recorded history. Under the Romans, land surveyors were established as a profession, and they established the basic measurements under which the Roman Empire was divided, such as a tax register of conquered lands (300 AD). In the 18th century in Europe triangulation was used to build a hierarchy of networks to allow point positioning within a country. Highest in the hierarchy were triangulation networks. These were densified into networks of traverses (polygons), into which local mapping surveying measurements, usually with measuring tape, corner prism and the familiar red and white poles, are tied.

Surveying or **land surveying** is the technique, profession, and science of accurately determining the terrestrial or three-dimensional position of points and the distances and angles between them, commonly practiced by licensed **surveyors**, and members of various building professions. These points are usually on the surface of the Earth, and they are often used to establish land maps and boundaries for ownership, locations (building corners, surface location of subsurface features) or other governmentally required or civil law purposes (property sales).

To accomplish their objective, surveyors use elements of mathematics (geometry and trigonometry), physics, engineering and law.

An alternative definition, from the American Congress on Surveying and Mapping (ACSM), is the science and art of making all essential measurements to determine the relative position of points or physical and cultural details above, on, or beneath the surface of the Earth, and to depict them in a usable form, or to establish the position of points or details.

Furthermore, as alluded to above, a particular type of surveying known as "land surveying" (also per ACSM) is the detailed study or inspection, as by gathering information through observations, measurements in the field, questionnaires, or research of legal instruments, and data analysis in the support of planning, designing, and establishing of property boundaries. It involves the re-establishment ofcadastral surveys and land boundaries based on documents of record and historical evidence, as well as certifying surveys (as required by statute or local ordinance) of subdivision plats or maps, registered land surveys, judicial surveys, and space delineation. Land surveying can include associated services such as mapping and related data accumulation, construction layout surveys, precision measurements of length, angle, elevation, area, and volume, as well as horizontal and vertical control surveys, and the analysis and utilization of land survey data.

Surveyors use various tools to do their work successfully and accurately, such as total stations, robotic total stations, GPS receivers, prisms, 3D scanners, radio communicators, handheld tablets, digital levels, and surveying software.

Surveying has been an essential element in the development of the human environment since the beginning of recorded history (about 6,000 years ago). It is required in the planning and execution of nearly every form of construction. Its most familiar modern uses are in the fields of transport, building and construction, communications, mapping, and the definition of legal boundaries for land ownership.

History of surveying

Surveying techniques have existed throughout much of recorded history. In ancient Egypt, when the Nile River overflowed its banks and washed outfarm boundaries, boundaries were re-established by a rope stretcher, or surveyor, through the application of simple geometry. The nearly perfect squareness and north-south orientation of the Great Pyramid of Giza, built c. 2700 BC, affirm the Egyptians' command of surveying.

A brief history of surveying:

- The Egyptian land register (3000 BC).
- A recent reassessment of Stonehenge (c. 2500 BC) suggests that the monument was set out by prehistoric surveyors using peg and rope geometry.
- The Groma surveying instrument originated in Mesopotamia (early 1st millennium BC).
    - Under the Romans, land surveyors were established as a profession, and they established the basic measurements under which the Roman Empire was divided, such as a tax register of conquered lands (300 AD).
    - The rise of the Caliphate led to extensive surveying throughout the Arab Empire. Arabic surveyors invented a variety of specialized instruments for surveying, including
    - Instruments for accurate leveling: A wooden board with a plumb line and two hooks, an equilateral triangle with a plumb line and two hooks, and a reed level.
    - A rotating alhidade, used for accurate alignment.
    - A surveying astrolabe, used for alignment, measuring angles, triangulation, finding the width of a river, and the distance between two points separated by an impassable obstruction.
- In England, The Domesday Book by William the Conqueror (1086)
    - Covered all England
    - Contained names of the land owners, area, land quality, and specific information of the area's content and inhabitants.
    - Did not include maps showing exact locations.

In the 18th century in Europe triangulation was used to build a hierarchy of networks to allow point positioning within a country. Highest in the hierarchy were triangulation networks. These were densified into networks of traverses (polygons), into which local mapping surveying measurements, usually with measuring tape, corner prism and the familiar red and white poles, are tied. For example, in the late 1780s, a team from the Ordnance Survey of Great Britain, originally under General William Roy began the Principal Triangulation of Britain using the specially built Ramsden theodolite. Large scale surveys are known as geodetic surveys.

- Continental Europe's cadastre was created in 1808
  - Founded by Napoleon I (Bonaparte)
  - Contained numbers of the parcels of land (or just land), land usage, names etc., and value of the land
  - 100 million parcels of land, triangle survey, measurable survey, map scale: 1:2500 and 1:1250
  - spread fast around Europe, but faced problems especially in Mediterranean countries, Balkan, and Eastern Europe due to cadastre upkeep costs and troubles.

A cadastre loses its value if register and maps are not constantly updated. Because of the fundamental value of land and real estate to the local and global economy, land surveying was one of the first professions to require Professional Licensure. In many jurisdictions, the land surveyors license was the first Professional Licensure issued by the state, province, or federal government.

1.1.1 Surveying techniques

Historically, distances were measured using a variety of means, such as with chains having links of a known length, for instance a Gunter's chain, or measuring tapes made of steel or invar. To measure horizontal distances, these chains or tapes were pulled taut according to temperature, to reduce sagging and slack. Additionally, attempts to hold the measuring instrument level would be made. In instances of measuring up a slope, the surveyor might have to "break" (break chain) the measurement- use an increment less than the total length of the chain.

Historically, horizontal angles were measured using a compass, which would provide a magnetic bearing, from which deflections could be measured. This type of instrument was later improved, with more carefully scribed discs providing better angular resolution, as well as through mounting telescopes with reticles for more-precise sighting atop the disc (see theodolite). Additionally, levels and calibrated circles allowing measurement of vertical angles were added, along with verniers for measurement to a fraction of a degree—such as with a turn-of-the-century transit.

The simplest method for measuring height is with an altimeter – basically a barometer – using air pressure as an indication of height. But surveying requires greater precision. A variety of means, such as precise levels (also known as differential leveling), have been developed to do this. With precise leveling, a series of measurements between two points are taken using an instrument and a measuring rod. Differentials in height between the measurements are added and subtracted in a series to derive the net difference in elevation between the two endpoints of the series. With the advent of the Global Positioning System (GPS), elevation can also be derived with sophisticated satellite receivers, but usually with somewhat less accuracy than with traditional precise leveling. However, the accuracies may be similar if the traditional leveling would have to be run over a long distance.

Triangulation is another method of horizontal location made almost obsolete by GPS. With the triangulation method, distances, elevations and directions between objects at great distance from one another can be determined. Since the early days of surveying, this was the primary method of determining accurate positions of objects for topographic maps of large areas. A surveyor first needs to know the horizontal distance between two of the objects. Then the height, distances and angular position of other objects can be derived, as long as they are visible from one of the original objects. High-accuracy transits or theodolites were used for this work, and angles between objects were measured repeatedly for increased accuracy. See alsoTriangulation in three dimensions.

Turning is a term used when referring to moving the level to take an elevation shot in a different location. When land surveying, there may be trees or other obstructions blocking the view from the level gun to the level rod. In order to "turn" the level gun, one must first take a shot on the rod from the current location and record the elevation. Keeping the level rod in exactly the same location and elevation, one may move the level gun to a different location where the level rod is still visible. Record the new elevation seen from the new location of the level rod and use the difference in elevations to find the new elevation of the level gun. Turning is not only used when there are obstructions in the way, but also when drastically changing elevations. You can turn up or down in elevation but the gun must always be at a higher elevation than the base of the rod. A level rod can usually be raised up to 25 feet high, which enables the gun to be set much higher. However, if the gun is lower than the base of the rod, you will not be able to take a shot because the rod cannot be lowered beyond the ground elevation.

Surveying equipment

As late as the 1990s, the basic tools used in planar surveying were a tape measure for determining shorter distances, a level to determine height or elevation differences, and a theodolite, set on a tripod, to measure angles (horizontal and vertical), combined with the process of triangulation. Starting from a position with known location and elevation, the distance and angles to the unknown point are measured.

A more modern instrument is a total station, which is a theodolite with an electronic distance measurement device (EDM). A total station can also be used for leveling when set to the horizontal plane. Since their introduction, total stations have made the technological shift from being optical-mechanical devices to being fully electronic.

Modern top-of-the-line total stations no longer require a reflector or prism (used to return the light pulses used for distancing) to return distance measurements, are fully robotic, and can even e-mail point data to the office computer and connect to satellite positioning systems, such as a Global Positioning System. Though Real Time Kinematic GPS systems have increased the speed and precision of surveying, they are still horizontally accurate to only about 20 mm and vertically accurate to about 30–40 mm.

Total stations are still used widely, along with other types of surveying instruments, however, because GPS systems do not work well in areas with dense tree cover or constructions. One-person robotic-guided total stations allow surveyors to gather precise measurements without extra workers to look through and turn the telescope or record data. A faster but expensive way to measure large areas (not details, and no obstacles) is with a helicopter, equipped with a laser scanner, combined with a GPS to determine the position and elevation of the helicopter. To increase precision, surveyors place beacons on the ground (about 20 km (12 mi) apart). This method reaches precisions between 5–40 cm (depending on flight height).

1.1.2 Types of surveys and applicability

ALTA/ACSM Land Title Survey: a surveying standard jointly proposed by the American Land Title Association and the American Congress on Surveying and Mapping that incorporates elements of the boundary survey, mortgage survey, and topographic survey.

- Archaeological survey: used to accurately assess the relationship of archaeological sites in a landscape or to accurately record finds on an archaeological site.
- As-built survey: a survey carried out during or immediately after a construction project for record, completion evaluation and payment purposes. An as-built survey also known as a 'works as executed survey' documents the location of the recently constructed elements that are subject to completion evaluation. As built surveys are typically presented in red or redline and overlayed over existing design plans for direct comparison with design information.
- Bathymetric survey: a survey carried out to map the topography and features of the bed of an ocean, lake, river or other body of water.
- Boundary survey: a survey that establishes boundaries of a parcel using its legal description, which typically involves the setting or restoration of monuments or markers at the corners or along the lines of the parcel, often in the form of iron rods, pipes, or concrete monuments in the ground, or nails set in concrete or asphalt.
- Deformation survey: a survey to determine if a structure or object is changing shape or moving. The three-dimensional positions of specific points on an object are determined, a period of time is allowed to pass, these positions are then re-measured and calculated, and a comparison between the two sets of positions is made.
- Engineering surveys: those surveys associated with the engineering design (topographic, layout and as-built) often requiring geodetic computations beyond normal civil engineering practice.
- Foundation survey: a survey done to collect the positional data on a foundation that has been poured and is cured. This is done to ensure that the foundation was constructed in the location, and at the elevation, authorized in the plot plan, site plan, or subdivision plan.
- Geological survey: generic term for a survey conducted for the purpose of recording the geologically significant features of the area under investigation. .
- Hydrographic survey: a survey conducted with the purpose of mapping the coastline and seabed for navigation, engineering, or resource management purposes.
- Measured survey : a building survey to produce plans of the building. such a survey may be conducted before renovation works, for commercial purpose, or at end of the construction process "as built survey"
- Mortgage survey or physical survey: a simple survey that delineates land boundaries and building locations. In many places a mortgage survey is required by lending institutions as a precondition for a mortgage loan.
- Soil survey, or soil mapping, is the process of determining the soil types or other properties of the soil cover over a landscape, and mapping them for others to understand and use.

- Structural survey: a detailed inspection to report upon the physical condition and structural stability of a building or other structure and to highlight any work needed to maintain it in good repair.
- Tape survey: this type of survey is the most basic and inexpensive type of land survey. Popular in the middle part of the 20th century, tape surveys while being accurate for distance lack substantially in their accuracy of measuring angle and bearing standards that are practiced by professional land surveyors.
- Topographic survey: a survey that measures the elevation of points on a particular piece of land, and presents them as contour lines on a plot.

Surveying as a career

The basic principles of surveying have changed little over the ages, but the tools used by surveyors have evolved tremendously. Engineering, especiallycivil engineering, depends heavily on surveyors.

Whenever there are roads, railways, reservoir, dams, pipeline transports retaining walls, bridges or residential areas to be built, surveyors are involved. They establish the boundaries of legal descriptions and the boundaries of various lines of political divisions. They also provide advice and data forgeographical information systems (GIS), computer databases that contain data on land features and boundaries.

Surveyors must have a thorough knowledge of algebra, basic calculus, geometry, and trigonometry. They must also know the laws that deal with surveys, property, and contracts.

In addition, they must be able to use delicate instruments with accuracy and precision. In the United States, surveyors and civil engineers use units of feet wherein a survey foot is broken down into 10ths and 100ths. Many deed descriptions requiring distance calls are often expressed using these units (125.25 ft). On the subject of accuracy, surveyors are often held to a standard of one one-hundredth of a foot; about 1/8 inch. Calculation and mapping tolerances are much smaller wherein achieving near-perfect closures are desired. Though tolerances such as this will vary from project to project, in the field and day to day usage beyond a 100th of a foot is often impractical.

Licensing

In most of the United States, surveying is recognized as a distinct profession apart from engineering. Licensing requirements vary by state, but they generally have components of education, experience and examinations. In the past, experience gained through an apprenticeship, together with passing a series of state-administered examinations, was required to attain licensure. Now, most states insist upon basic qualification of a degree in surveying, plus experience and examination requirements.

The licensing process typically follows two phases. First, upon graduation, the candidate may be eligible to take the Fundamentals of Surveying (FS) exam, to be certified upon passing and meeting all other requirements as a surveying intern (SI),(formerly surveyor in training (SIT)). Upon being certified as an SI, the candidate then needs to gain additional experience to become eligible for the second phase. That typically consists of the Principles and Practice of Land Surveying (PS) exam along with a state-specific examination.

Licensed surveyors usually denote themselves with the letters P.L.S. (professional land surveyor), P.S. (professional surveyor), L.S. (land surveyor), R.L.S. (registered land surveyor), R.P.L.S. (Registered Professional Land Surveyor), or P.S.M. (professional surveyor and mapper) following their names, depending upon the dictates of their particular jurisdiction of registration.

In Canada, land Surveyors are registered to work in their respective province. The designation for a land surveyor breaks down by province, but follows the rule whereby the first letter indicates the province, followed by L.S. There is also a designation as a C.L.S. or Canada lands surveyor, who has the authority to work on Canada Lands, which include Indian Reserves, National Parks, the three territories and offshore lands.

In many Commonwealth countries, the term Chartered Land Surveyor is used for someone holding a professional license to conduct surveys.

A licensed land surveyor is typically required to sign and seal all plans, the format of which is dictated by their state jurisdiction, which shows their name and registration number. In many states, when setting boundary corners land surveyors are also required to place survey monuments bearing their registration numbers, typically in the form of capped iron rods, concrete monuments, or nails with washers.

Building surveying

Building surveying **emerged in the 1970s as a profession in the United Kingdom by a group of technically minded general practice surveyors.[7] Building surveying is a recognised profession in Britain, Ireland, Australia and Hong Kong. In Australia in particular, due to risk mitigation and limitation factors, the employment of surveyors at all levels of the construction industry is widespread. There are still many countries where it is not widely recognized as a profession.**

Building Surveyors are trained to some extent in all aspects of property but with specific training in Building Pathology, as such they have a wide understanding of the end implications of decisions taken by more specific professions and trades during the realisation process, thus making them suitable for employment as Project and Property Managers on the client side (i.e. managing external contractors).

Services that building surveyors undertake are broad but can include:

- Construction design and building works
- Project management and monitoring
- Property Legislation advice
- Insurance assessment and claims assistance
- Defect investigation and maintenance advice
- Building surveys and measured surveys
- Handling planning applications
- Building inspection to ensure compliance with building regulations
- Pre-acquisition surveys
- Negotiating dilapidations claims[8]

Building surveyors also advise on many aspects of construction including:

- design
- cost
- maintenance
- sustainability
- repair
- refurbishment
- restoration and preservation of buildings and monuments.

Clients of a building surveyor can be the government agencies, businesses and individuals. Surveyors work closely with architects, planners, quantity surveyors, engineers, homeowners and tenants groups. A building surveyor may be called to act as an expert witness. It is usual for building surveyors to earn a university degree before undertaking structured training to become a member of a professional organisation.

With the enlargement of the European community, the profession of the building surveyor is becoming more widely known in other European states, particularly France, where many English-speaking people buy second homes.

Lidar Surveying – Three-dimensional laser scanning provides high definition surveying for architectural, as-built, and engineering surveys. Recent technological advances make it the most cost-effective and time-sensitive solution for providing the highest level of detail available for interior and exterior building work.

Land surveyor

One of the primary roles of the land surveyor is to determine the boundary of real property on the ground. That boundary has already been established and described in legal documents and official plans and maps prepared by attorneys, engineers, and other land surveyors. The corners of the property will either have been monumented by a prior surveyor, or monumented by the surveyor hired to perform a survey of a new boundary which has been agreed upon by adjoining land owners.

Monuments are categorized into two groups which are known as natural and artificial. Natural monuments are things such as trees, large stones and other substantial, naturally occurring objects that were in place before the survey was made. An artificial monument is anything within the regulations that are usually placed at corner points by landowners, surveyors, engineers and others. They may be referred to as iron pins or pipes, stakes, trees, concrete monuments or whatever the surveyor decides to use at the time, within the regulations for the area. The courts have held that natural monuments control over artificial monuments because they are more certain in identification and less likely to be disturbed.

Over time, construction and maintenance of roads and many other acts of man, along with acts of nature such as earthquakes, movement of water, and tectonic shift can obliterate or damage the monumented locations of land boundaries. The land surveyor is often compelled to consider other evidence such as fence locations, wood lines, monuments on neighboring properties and recollections of people. This other evidence is known as Extrinsic Evidence and is a fairly common principle. Extrinsic evidence is defined as evidence outside the writings, in this case the deed. Extrinsic evidence is held to be synonymous with evidence from another source.

Today's land surveyor sets monumentation at actual physical points on the ground that define angle points of boundary lines that divide neighboring parcels. These monuments are most often 1/2" or 5/8" iron rebar rods or pipes placed at 18" minimum depth, but varies state by state. The more recent rods or pipes may have an affixed plastic cap over the top bearing the responsible surveyors' name and license number. Older monuments may exist such as old pipes, gun barrels, axles, mounds of stone, whiskey bottles, or even wooden stakes. In addition to rods and pipes, surveyors might use 4x4" concrete posts at corners of large parcels or anywhere that would require more stability (e.g. beach sand). They place them three feet deep. In places where there is asphalt or concrete, it is common to place nails or aluminum alloy caps to re-establish boundary corners. Marks are meant to be durable, stable, and as "permanent" as possible. The aim is to provide sufficient marks so some marks will remain for future re-establishment of boundaries. The material and marking used on monuments placed to mark boundary corners are often subject to state laws. Many states have laws that protect existing monuments and can have civil penalties if disturbed or destroyed.

Cadastral land surveyors are licensed by governments. In the United States, cadastral surveys are typically conducted by the federal government, specifically through the Cadastral Surveys branch of the Bureau of Land Management (BLM), formerly the General Land Office(GLO). They consult with USFS, Park Service, Corps of Engineers, BIA, Fish and Wildlife Service, Bureau of Reclamation, etc. In states that have been organized per the Public Land Survey System (PLSS), surveyors carry out BLM Cadastral Surveys in accordance with that system.

A common use of a survey is to determine a legal property boundary. The first stage in such a survey, known as a resurvey, is to obtain copies of the deed description and all other available documents from the owner. The deed description is that of the deed and not a tax statement or other incomplete document. The surveyor should then obtain copies of deed descriptions and maps of the adjoining properties, any records from the municipality or county, utility maps and any records of surveys. Depending on which region the survey is located in some or most of this information may not be available or even exist. Whether the information exists or not a thorough search should be conducted so that no records are neglected. Copies of deeds usually can be located in the county recorder's office and maps or plats can usually be found at the county recorder or surveyor's office. These arrangements will vary state to state and survey system to survey system so some familiarity maybe needed. When all the records are assembled, the surveyor examines the documents for errors, such as closure errors. When a metes and bounds description is involved, the seniority of the deeds must be determined. The title abstract usually gives the order of seniority for the deeds related to the tract being surveyed and should be used if available. After this data is gathered and analyzed the field survey may commence. The initial survey operations should be concentrated on locating monuments. In urban regions or a city, monuments should be sought initially but in the absence of monuments property corners marked by iron pins, metal survey markers, iron pipes and other features that may establish a line of possession should be located. When the approximate positions for the boundaries of the property have been located a traverse is run around the property. While the control traverse is being run, ties should be measured and all details relevant to the boundaries should be acquired. This includes but is not limited to locating the property corners, monuments, fences, hedge rows, walls, walks and all buildings on the lot. The Surveyor then takes this data collected and compares it to the records that were received. When a solution is reached the property corners that are chosen as those that best fit all the data are coordinated and ties by direction and distance are computed from the nearest traverse point. Once this has been established the features on the lot can be drawn, dimensions can be shown from these features to the boundary line and a map or plat is prepared for the client.

The art of surveying

Many properties have considerable problems with regards to improper bounding, miscalculations in past surveys, titles, easements, and wildlife crossings. Also many properties are created from multiple divisions of a larger piece over the course of years, and with every additional division the risk of miscalculation increases. The result can be abutting properties not coinciding with adjacent parcels, resulting in hiatuses (gaps) and overlaps. Many times a surveyor must solve a puzzle using pieces that do not exactly fit together. In these cases, the solution is based upon the surveyor's research and interpretation, along with established procedures for resolving discrepancies. This essentially is a process of continual error correction and update, where official recordation documents countermand the previous and sometime erroneous survey documents recorded by older monuments and older survey methods.

1.2 Establishing the framework

Most surveying frameworks are erected by measuring the angles and the lengths of the sides of a chain of triangles connecting the points fixed by global positioning. The locations of ground features are then determined in relation to these triangles by less accurate and therefore cheaper methods. Establishing the framework ensures that detail surveys conducted at different times or by different surveyors fit together without overlaps or gaps.

For centuries the corners of these triangles have been located on hilltops, each visible from at least two others, at which the angles between the lines joining them are measured; this process is called triangulation. The lengths of one or two of these lines, called bases, are measured with great care; all the other lengths are derived by trigonometric calculations from them and the angles. Rapid checks on the accuracy are provided by measuring all three angles of each triangle, which must add up to 180 degrees.

In small flat areas, working at large scales, it may be easier to measure the lengths of all the sides, using a tape or a chain, rather than the angles between them; this procedure, called trilateration, was impractical over large or hilly areas until the invention of electromagnetic distance measurement (EDM) in the mid-20th century. This procedure has made it possible to measure distances as accurately and easily as angles, by electronically timing the passage of radiation over the distance to be measured; microwaves, which penetrate atmospheric haze, are used for long distances and light or infrared radiation for short ones. In the devices used for EDM, the radiation is either light (generated by a laser or an electric lamp) or an ultrahigh-frequency radio beam. The light beam requires a clear line of sight; the radio beam can penetrate fog, haze, heavy rain, dust, sandstorms, and some foliage. Both types have a transmitter-receiver at one survey station. At the remote station the light type contains a set of corner mirrors; the high-frequency type incorporates a retransmitter (requiring an operator) identical to the transmitter-receiver at the original station. A corner mirror has the shape of the inside of a corner of a cube; it returns light toward the source from whatever angle it is received, within reasonable limits. A retransmitter must be aimed at the transmitter-receiver.

In both types of instrument, the distance is determined by the length of time it takes the radio or light beam to travel to the target and back. The elapsed time is determined by the shift in phase of a modulating signal superimposed on the carrier beam. Electronic circuitry detects this phase shift and converts it to units of time; the use of more than one modulating frequency eliminates ambiguities that could arise if only a single frequency had been employed.

EDM has greatly simplified an alternative technique, called traversing, for establishing a framework. In traversing, the surveyor measures a succession of distances and the angles between them, usually along a traveled route or a stream. Before EDM was available, traversing was used only in flat or forested areas where triangulation was impossible. Measuring all the distances by tape or chain was tedious and slow, particularly if great accuracy was required, and no check was obtainable until the traverse closed, either on itself or between two points already fixed by triangulation or by astronomical observations.

surveying, a means of making relatively large-scale, accurate measurements of the Earth’s surfaces. It includes the determination of the measurement data, the reduction and interpretation of the data to usable form, and, conversely, the establishment of relative position and size according to given measurement requirements. Thus, surveying has two similar but opposite functions: (1) the determination of existing relative horizontal and vertical position, such as that used for the process of mapping, and (2) the establishment of marks to control construction or to indicate land boundaries.

Surveying has been an essential element in the development of the human environment for so many centuries that its importance is often forgotten. It is an imperative requirement in the planning and execution of nearly every form of construction. Surveying was essential at the dawn of history, and some of the most significant scientific discoveries could never have been implemented were it not for the contribution of surveying. Its principal modern uses are in the fields of transportation, building, apportionment of land, and communications.

Except for minor details of technique and the use of one or two minor hand-held instruments, surveying is much the same throughout the world. The methods are a reflection of the instruments, manufactured chiefly in Switzerland, Austria, Great Britain, the United States, Japan, and Germany. Instruments made in Japan are similar to those made in the West.

History

It is quite probable that surveying had its origin in ancient Egypt. The Great Pyramid of Khufu at Gizawas built about 2700 BCE, 755 feet (230 metres) long and 481 feet (147 metres) high. Its nearly perfect squareness and north–south orientation affirm the ancient Egyptians' command of surveying.

Evidence of some form of boundary surveying as early as 1400 BCE has been found in the fertile valleys and plains of the Tigris, Euphrates, and Nile rivers. Clay tablets of the Sumerians show records of land measurement and plans of cities and nearby agricultural areas. Boundary stones marking land plots have been preserved. There is a representation of land measurement on the wall of a tomb at Thebes(1400 BCE) showing head and rear chainmen measuring a grainfield with what appears to be a rope with knots or marks at uniform intervals. Other persons are shown. Two are of high estate, according to their clothing, probably a land overseer and an inspector of boundary stones.

There is some evidence that, in addition to a marked cord, wooden rods were used by the Egyptians for distance measurement. There is no record of any angle-measuring instruments of that time, but there was a level consisting of a vertical wooden A-frame with a plumb bob supported at the peak of the A so that its cord hung past an indicator, or index, on the horizontal bar. The index could be properly placed by standing the device on two supports at approximately the same elevation, marking the position of the cord, reversing the A, and making a similar mark. Halfway between the two marks would be the correct place for the index. Thus, with their simple devices, the ancient Egyptians were able to measure land areas, replace property corners lost when the Nile covered the markers with silt during floods, and build the huge pyramids to exact dimensions.

The Greeks used a form of log line for recording the distances run from point to point along the coast while making their slow voyages from the Indus to the Persian Gulf about 325 BCE. The magneticcompass was brought to the West by Arab traders in the 12th century CE. The astrolabe was introduced by the Greeks in the 2nd century BCE. An instrument for measuring the altitudes of stars, or their angle of elevation above the horizon, took the form of a graduated arc suspended from a hand-held cord. A pivoted pointer that moved over the graduations was pointed at the star. The instrument was not used for nautical surveying for several centuries, remaining a scientific aid only.

The Greeks also possibly originated the use of the groma, a device used to establish right angles, butRoman surveyors made it a standard tool. It was made of a horizontal wooden cross pivoted at the middle and supported from above. From the end of each of the four arms hung a plumb bob. By sighting along each pair of plumb bob cords in turn, the right angle could be established. The device could be adjusted to a precise right angle by observing the same angle after turning the device approximately 90°. By shifting one of the cords to take up half the error, a perfect right angle would result.

About 15 BCE the Roman architect and engineer Vitruvius mounted a large wheel of known circumference in a small frame, in much the same fashion as the wheel is mounted on a wheelbarrow; when it was pushed along the ground by hand it automatically dropped a pebble into a container at each revolution, giving a measure of the distance traveled. It was, in effect, the first odometer.

The water level consisted of either a trough or a tube turned upward at the ends and filled with water. At each end there was a sight made of crossed horizontal and vertical slits. When these were lined up just above the water level, the sights determined a level line accurate enough to establish the grades of the Roman aqueducts. In laying out their great road system, the Romans are said to have used theplane table. It consists of a drawing board mounted on a tripod or other stable support and of a straightedge—usually with sights for accurate aim (the alidade) to the objects to be mapped—along which lines are drawn. It was the first device capable of recording or establishing angles. Later adaptations of the plane table had magnetic compasses attached.

Plane tables were in use in Europe in the 16th century, and the principle of graphic triangulation and intersection was practiced by surveyors. In 1615 Willebrord Snell, a Dutch mathematician, measured an arc of meridian by instrumental triangulation. In 1620 the English mathematician Edmund Gunterdeveloped a surveying chain, which was superseded only by the steel tape beginning in the late 19th century.

The study of astronomy resulted in the development of angle-reading devices that were based on arcs of large radii, making such instruments too large for field use. With the publication of logarithmic tables in 1620, portable angle-measuring instruments came into use. They were called topographic instruments, or theodolites. They included pivoted arms for sighting and could be used for measuring both horizontal and vertical angles. Magnetic compasses may have been included on some.

The vernier, an auxiliary scale permitting more accurate readings (1631), the micrometer microscope (1638), telescopic sights (1669), and spirit levels (about 1700) were all incorporated in theodolites by about 1720. Stadia hairs were first applied by James Watt in 1771. The development of the circle-dividing engine about 1775, a device for dividing a circle into degrees with great accuracy, brought one of the greatest advances in surveying methods, as it enabled angle measurements to be made with portable instruments far more accurately than had previously been possible.

Modern surveying can be said to have begun by the late 18th century. One of the most notable early feats of surveyors was the measurement in the 1790s of the meridian from Barcelona, Spain, to Dunkirk, France, by two French engineers, Jean Delambre and Pierre Méchain, to establish the basic unit for the metric system of measurement.

Many improvements and refinements have been incorporated in all the basic surveying instruments. These have resulted in increased accuracy and speed of operations and opened up possibilities for improved methods in the field. In addition to modification of existing instruments, two revolutionary mapping and surveying changes were introduced: photogrammetry, or mapping from aerial photographs (about 1920), and electronic distance measurement, including the adoption of the laser for this purpose as well as for alignment (in the 1960s). Important technological developments starting in the late 20th century include the use of satellites as reference points for geodetic surveys and electronic computers to speed the processing and recording of survey data.

The planning and design of all Civil Engineering projects such as construction of highways, bridges, tunnels, dams etc are based upon surveying measurements.

Moreover, during execution, project of any magnitude is constructed along the lines and points established by surveying.

Thus, surveying is a basic requirement for all Civil Engineering projects.

Other principal works in which surveying is primarily utilised are

- to fix the national and state boundaries;
- to chart coastlines, navigable streams and lakes;
- to establish control points;
- to execute hydrographic and oceanographic charting and mapping; and
- to prepare topographic map of land surface of the earth.

1.3 Basic Principle Of Surveying.......

The following two basic principles should be considered while determining relative position of points on the surface of earth:-

1. determining suitable method for locating a point:- it is always practicableto select two points in the field to measure the distance between them. These can be represented on paper by two points placed in a convenient positions.

2.working from whole to the part:- in surveying an area, it is essential to establish first of all a system of control points with great precision. Minor control points can then be established by less precise method and the details can be located afterwards by method of triangulation or traversing between control points.

levelling...............

IT is a branch of survey which helps in determination of elevation of a given point or object with espect to some specified point or object.

. Common levelling instruments include the spirit level, the dumpy level, the digital level, and the laser level.

The dumpy level is an older style of optical instrument. It is commonly believed that dumpy levelling is less accurate than other types of levelling, but such is not the case. Dumpy levelling requires shorter and therefore more numerous sights, but this fault is compensated by the practice of making foresights and backsights equal.

survey.........

surveying is the art of determining the relative positions of objects on the surface of earth.Surveying or land surveying is the technique, profession and science of accurately determining the terrestrial or three-dimensional position of points and the distances and angles between them.Surveying has been an essential element in the development of the human environment since the beginning of recorded history (about 5,000 years ago). It is required in the planning and execution of nearly every form of construction..

1.3.1 Classification of survey

Based on the purpose (for which surveying is being conducted), Surveying has been classified into:

- **Control surveying :** To establish horizontal and vertical positions of control points.

- **Land surveying :** To determine the boundaries and areas of parcels of land, also known as property survey, boundary survey or cadastral survey.

- **Topographic survey :** To prepare a plan/ map of a region which includes natural as well as and man-made features including elevation.

- **Engineering survey :** To collect requisite data for planning, design and execution of engineering projects. Three broad steps are

1) Reconnaissance survey : To explore site conditions and availability of infrastructures.

2) Preliminary survey : To collect adequate data to prepare plan / map of area to be used for planning and design.

3) Location survey : To set out work on the ground for actual construction / execution of the project.

- **Route survey :** To plan, design, and laying out of route such as highways, railways, canals, pipelines, and other linear projects.

- **Construction surveys :** Surveys which are required for establishment of points, lines, grades, and for staking out engineering works (after the plans have been prepared and the structural design has been done).

- **Astronomic surveys :** To determine the latitude, longitude (of the observation station) and azimuth (of a line through observation station) from astronomical observation.

- **Mine surveys :** To carry out surveying specific for opencast and underground mining purposes.

Surveying is the process by which a surveyor measures certain dimensions that generally occur on the surface of the Earth. Surveying equipment, such as levels and theodolites, are used for accurate measurement of angular deviation, horizontal, vertical and slope distances. With computerisation, electronic distance measurement (EDM), total stations, GPS surveying and laser scanning have supplemented (and to a large extent supplanted) the traditional optical instruments. This information is crucial to convert the data into a graphical representation of the Earth's surface, in the form of a map. This information is then used by civil engineers, contractors and even realtors to design from, build on, and trade, respectively. Elements of a building or structure must be correctly sized and positioned in relation to each other and to site boundaries and adjacent structures. Although surveying is a distinct profession with separate qualifications and licensing arrangements, civil engineers are trained in the basics of surveying and mapping, as well as geographic information systems. Surveyors may also lay out the routes of railways, tramway tracks, highways, roads, pipelines and streets as well as position other infrastructures, such as harbors, before construction.

Land surveying

In the United States, Canada, the United Kingdom and most Commonwealth countries land surveying is considered to be a distinct profession. Land surveyors are not considered to be engineers, and have their own professional associations and licencing requirements. The services of a licenced land surveyor are generally required for boundary surveys (to establish the boundaries of a parcel using its legal description) and subdivision plans (a plot or map based on a survey of a parcel of land, with boundary lines drawn inside the larger parcel to indicate the creation of new boundary lines and roads), both of which are generally referred to as cadastral surveying.

Construction surveying

Construction surveying is generally performed by specialised technicians. Unlike land surveyors, the resulting plan does not have legal status. Construction surveyors perform the following tasks:

- Survey existing conditions of the future work site, including topography, existing buildings and infrastructure, and even including underground infrastructure whenever possible;

- Construction surveying (otherwise "lay-out" or "setting-out"): to stake out reference points and markers that will guide the construction of new structures such as roads or buildings for subsequent construction;
- Verify the location of structures during construction;
- As-Built surveying: a survey conducted at the end of the construction project to verify that the work authorized was completed to the specifications set on plans.

Transportation engineering

Transportation engineering is concerned with moving people and goods efficiently, safely, and in a manner conducive to a vibrant community. This involves specifying, designing, constructing, and maintaining transportation infrastructure which includes streets, canals, highways, rail systems, airports, ports, and mass transit. It includes areas such as transportation design, transportation planning, traffic engineering, some aspects of urban engineering, queueing theory, pavement engineering, Intelligent Transportation System (ITS), and infrastructure management.

Municipal or urban engineering

Municipal engineering is concerned with municipal infrastructure. This involves specifying, designing, constructing, and maintaining streets, sidewalks, water supply networks, sewers, street lighting, municipal solid waste management and disposal, storage depots for various bulk materials used for maintenance and public works (salt, sand, etc.), public parks and bicycle paths. In the case of underground utility networks, it may also include the civil portion (conduits and access chambers) of the local distribution networks of electrical and telecommunications services. It can also include the optimizing of waste collection and bus service networks. Some of these disciplines overlap with other civil engineering specialties, however municipal engineering focuses on the coordination of these infrastructure networks and services, as they are often built simultaneously, and managed by the same municipal authority.

Forensic engineering

Forensic engineering is the investigation of materials, products, structures or components that fail or do not operate or function as intended, causing personal injury or damage to property. The consequences of failure are dealt with by the law of product liability. The field also deals with retracing processes and procedures leading to accidents in operation of vehicles or machinery. The subject is applied most commonly in civil law cases, although it may be of use in criminal law cases. Generally the purpose of a Forensic engineering investigation is to locate cause or causes of failure with a view to improve performance or life of a component, or to assist a court in determining the facts of an accident. It can also involve investigation of intellectual property claims, especially patents.

Control engineering

Control engineering or control systems engineering is the branch of Civil Engineering discipline that applies control theory to design systems with desired behaviors. The practice uses sensors to measure the output performance of the device being controlled (often a vehicle) and those measurements can be used to give feedback to the input actuators that can make corrections toward desired performance. When a device is designed to perform without the need of human inputs for correction it is called automatic control (such as cruise control for regulating a car's speed). Multi-disciplinary in nature, control systems engineering activities focus on implementation of control systems mainly derived by mathematical modeling of systems of a diverse range.

1.4 Chain survey

Chain survey is the simplest method of surveying. In this survey only measurements are taken in the field, and the rest work, such as plotting calculation etc. are done in the office. This is most suitable adapted to small plane areas with very few details. If carefully done, it gives quite accurate results. The necessary requirements for field work are chain, tape, ranging rod, arrows and some time cross staff.

Procedure in chain survey

Reconnaissance: The preliminary inspection of the area to be surveyed is calledreconnaissance. The surveyor inspects the area to be surveyed, survey or prepares index sketch or key plan.

Marking Station: Surveyor fixes up the required no stations at places from where maximum possible stations are possible.

Some of the methods used for marking are:

Fixing ranging poles

Driving pegs

Marking a cross if ground is hard

Digging and fixing a stone.

Then he selects the way for passing the main line, which should be horizontal and clean as possible and should pass approximately through the center of work.

Then ranging roads are fixed on the stations.

After fixing the stations, chaining could be started.

Make ranging wherever necessary.

Measure the change and offset.

Enter in the field the book.

Survey Station:

Survey stations are of two kinds

Main Stations

Subsidiary or tie

Main Stations:

Main stations are the end of the lines, which command the boundaries of the survey, and the lines joining the main stations re called the main survey line or the chain lines.

Subsidiary or the tie stations:

Subsidiary or the tie stations are the point selected on the main survey lines, where it is necessary to locate the interior detail such as fences, hedges, building etc.

Tie or subsidiary lines:

A tie line joints two fixed points on the main survey lines. It helps to checking the accuracy of surveying and to locate the interior details. The position of each tie line should be close to some features, such as paths, building etc.

Base Lines:

It is main and longest line, which passes approximately through the centre of the field. All the other measurements to show the details of the work are taken with respect of this line.

Check Line:

A check line also termed as a proof line is a line joining the apex of a triangle to some fixed points on any two sides of a triangle. A check line is measured to check the accuracy of the framework. The length of a check line, as measured on the ground should agree with its length on the plan.

Offsets:

These are the lateral measurements from the base line to fix the positions of the different objects of the work with respect to base line. These are generally set at right angle offsets. It can also be drawn with the help of a tape. There are two kinds of offsets:

1) Perpendicular offsets, and
2) Oblique offsets.

The measurements are taken at right angle to the survey line called perpendicular or right angled offsets.

The measurements which are not made at right angles to the survey line are called oblique offsets or tie line offsets.

A chain is made up of steel or iron pieces of wire known as links which are joined together with circular or oval rings that make for flexibility. It has a brack handle at both ends which is part and parcel of the total length of the chain known as chain length. A typical chain is made up of 100 links and has a bran tag at every 10th link called a teller. This makes for operating of length as the letters are numbered and differentiated from the next one for easy identification. Different kinds of chains exist including Equnter’s chain, Engineers chain and metric chains.

Generally, chains have been replaced with chains for linear surveys. Chains are now being studied to get the historical perspective of the development of survey equipments over the years.

To surveyors and collectors alike, the link chain symbolizes a rugged era, when surveying tools and techniques were literally defining America. The chain was a precision part of a surveyor's equipment and, as such, had to be calibrated and adjusted frequently, yet was sturdy enough to be dragged through rough terrain for years.

Owning a link chain now captures a bit of this glorious past; to heft it enhances the kinship one feels with the surveyor who toiled in the field long ago. As collectors, we need to identify the type of chain we own, in order to understand its history. Each chain bears the clues of its use, such as the wire gauge used, the materials and design used, the lengths of the whole and of each link, the manufacturer's stamps, the presence or absence of brazing, the tally-tags, and the presence or absence of linking rings. Noting these components will make it possible to approximate the date and purpose of your link chain with the aid of period manufacturer's catalogs. The following is a nicely detailed account from the 1910 Manual of the Principal Instruments used in American Engineering and Surveying, published by the W. & L. E. Gurley Company of Troy, New York.

Sizes of Wire - The sizes and diameters of iron and steel wire commonly used in making surveyor's and engineer's chains are as follows: No. 8, .162 inch; No. 10, .135 inch; No. 12, .105 inch; No. 15, .072 inch; and No. 18, .047 inch.

Land Surveyor's Chain - The ordinary Gunter's or surveyor's chain is sixty-six feet or four poles long, and is composed of one hundred links, connected each to each by two rings, and furnished with a tally mark at the end of every ten links. A link in measurement includes a ring at each end, and is seven and ninety two one hundredths inches long. In all the chains which we make the rings are oval and are sawed and well closed, the ends of the wore forming the hook being also filed and bent close to the link, to avoid kinking. The oval rings are about one third stronger than round ones.

Handles - The handles are of brass and form part of the end links, to which they are connected by a short link and jam nuts, by which the length of the chain is adjusted.

Tallies - The tallies are of brass, and have one, two, three or four notches, as they mark ten, twenty, thirty or forty links from either end. The fiftieth link is marked by a rounded tally to distinguish it from the others.

Half Chains - In place of the four pole chain just described, many surveyors prefer a chain two rods or thirty three feet long, having only fifty links, which are counted by tallies from one end in a single direction.

Iron and Steel Wire - Our surveyors' chains are made of Nos. 8 and 10 refined iron wire, and of Nos. 8, 10, 12 and 15 best steel wire. Steel chains are preferred on account of their greater strength, although they are more expensive than those of iron.

Engineers' Chains - Engineers' chains differ from surveyors' chains, in that a link including a ring at each end is one foot long, and the wire is of steel Nos. 8, 10 and 12. They are either fifty or one hundred feet long, and are furnished with swivel handles and tallies like those just described.

Brazed Steel Chains - A very light and strong chain is made of No. 12 steel wire, the links and rings of which are securely brazed. The wire is of a low spring temper, and the chain, though light, is almost incapable of being broken or stretched in careful use.

Our brazed steel chains have been found exceedingly desirable for all kinds of measurement, and for the use of engineers upon railroads and canals have very generally superseded the heavier chains.

Vara Chains - The meter is used as a standard measure of length in many countries, and chains of ten and twenty meters are often ordered. The chains are made of iron or steel wire, each meter being divided into five links. As a meter is 39.371 inches long, a link, including a ring at each end, measures 7.874 inches.

A ten meter chain has fifty links and a twenty meter chain one hundred links. Each meter is marked with a round brass tally numbered from one to nine in the ten meter chain, and from one to nineteen in the twenty meter chain.

Marking Pins - In chaining, eleven marking pins are needed, made either of iron, steel or brass wire, as preferred. They are about fourteen inches long, pointed at one end to enter the ground, and formed into a ring at the other end for convenience in handling.

Marking pins are sometimes loaded with a little mass of lead around the lower end, to serve as a plumb when the pin is dropped to the ground from the suspended end of the chain.

Chain survey is suitable in the following cases:
(i) Area to be surveyed is comparatively small
(ii) Ground is fairly level
(iii) Area is open and
(iv) Details to be filled up are simple and less.
In chain surveying only linear measurements are made i.e. no angular measurements are made. Since triangle is the only figure that can be plotted with measurement of sides only, in chain surveying the area to be surveyed should be covered with a network of triangles. Figure 12.11 shows a typical scheme of covering an area with a network of triangles. No angle of the network triangles should be less than 30º to precisely get plotted position of a station with respect to already plotted positions of other station. As far as possible angles should be close to 60º. However, the arrangements of triangles to be adopted depends on the shape, topography, natural and artificial obstacles in the field.



Figure 1.4

Technical Terms
Various technical terms used in connection with the network of the triangles in surveying are explained below:
Station: Station is a point of importance at the beginning or at the end of a survey line.
Main station: These are the stations at the beginning or at the end of lines forming main skeleton. They are denoted as A, B, C etc. Subsidiary or tie stations: These are the stations

selected on main lines to run auxiliary/secondary lines for the purpose of locating interior details. These stations are denoted as a, b, c, …., etc., or as 1, 2, 3, … etc. Base line: It is the most important line and is the longest. Usually it is the line plotted first and then frame work of triangles are built on it.

Detail lines: If the important objects are far away from the main lines, the offsets are too long, resulting into inaccuracies and taking more time for the measurements. In such cases the secondary lines are run by selecting secondary stations on main lines. Such lines are called detail lines.

Check lines: These are the lines connecting main station and a substation on opposite side or the lines connecting to substations on the sides of main lines. The purpose of measuring such lines is to check the accuracy with which main stations are located.

Selection of Stations

The following points should be considered in selecting station points:

(i) It should be visible from at least two or more stations.

(ii) As far as possible main lines should run on level ground.

(iii) All triangles should be well conditioned (No angle less than 30º).

(iv) Main network should have as few lines as possible.

(v) Each main triangle should have at least one check line.

(vi) Obstacles to ranging and chaining should be avoided.

(vii) Sides of the larger triangles should pass as close to boundary lines as possible.

(viii) Tresspassing and frequent crossing of the roads should be avoided.

Offsets

Lateral measurements to chain lines for locating ground features are known as offsets. For this purpose perpendicular or oblique offsets may be taken. If the object to be located (say road) is curved more number of offsets should be taken. For measuring offsets tapes are commonly used.



(a)



(b)

For setting perpendicular offsets any one of the following methods are used:
(i) Swinging
(ii) Using cross staffs
(iii) Using optical or prism square.
Perpendicular Offset by Swinging



(b)

Chain is stretched along the survey line. An assistant holds the end of tape on the object. Surveyor swings the tape on chain line and selects the point on chain where offset distance is the least and notes chain reading as well as offset reading in a field book on a neat sketch of the object.

Perpendicular Offsets Using Cross Staffs



(a) (b) (c)

Above Figure shows three different types of cross staffs used for setting perpendicular offsets. All cross staffs are having two perpendicular lines of sights. The cross staffs are mounted on stand. First line of sight is set along the chain line and without disturbing setting right angle line of sight is checked to locate the object. With open cross staff it is possible to set perpendicular only, while with french cross staff, even 45º angle can be set. Adjustable cross staff can be used to set any angle also, since there are graduations and upper drum can be rotated over lower drum.

Perpendicular Offsets Using Optical Square and Prism Square

These instruments are based on the optical principle that if two mirrors are at angle ‘θ’ to each other, they reflect a ray at angle ‘2θ’. In below Figure shows a typical optical square.



Optical square consists of a metal box about 50 mm in diameter and 125 mm deep. In the rim of the box there are three openings:
(i) a pin hole at E
(ii) a small rectangular slot at G, and
(iii) a large rectangular slot at F.

A and B are the two mirrors placed at 45º to each other. Hence the image of an object at F which falls on A gets reflected and emerge at E which is at right angles to the line FA. The mirror A which is opposite to the opening at F is fully silvered. It is fitted to a frame which is attached to the bottom plate. If necessary this mirror can be adjusted by inserting a key on the top of the cover. The mirror B which is in the line with EG is silvered in the top half and plain in the bottom half. It is firmly attached to the bottom plate of the box.
The ranging rod at Q is directly sighted by eye at E in the bottom half of the B which is a plain glass. At the same time in the top half of B, the reflected ray of the object at P is sighted. When the image of P is in the same vertical line as the object at Q, then the lines PA is at right angles to the line EB. This instrument can be used for finding foot of the perpendicular or to set a right angle. In prism square, instead of two mirrors at 45º to each other a prism which has two faces at 45º to each other is used. Its advantage is it will not go out of adjustment even after long usage.





Field Book

All observations and measurements taken during chain surveying are to be recorded in a standard field book. It is a oblong book of size 200 mm × 120 mm, which can be carried in the pocket. There are two forms of the book (i) single line and (ii) double line. The pages of a single book are having a red line along the length of the paper in the middle of the width. It indicates the chain line. All chainages are written across it. The space on either side of the line is used for sketching the object and for noting offset distances. In double line book there are two blue lines with a space of 15 to 20 mm is the middle of each book. The space between the two lines is utilised for noting the chainages. in below Figure shows typical pages of a field books.


Line AB ends
station B
92.4
71.7
67.3
26.5
22.3
3.2
2.8
2.2
10.8
7.3
2.7
To H
To C
Station A
line AB starts
Line AB ends
station B
92.4
71.7
67.3
26.5
3.2
22.3
2.8
10.8
7.3
To H
To C
Station A
line AB starts

Field Work

As soon as the survey party arrives in the field the following details are entered in the field book:

(i) Title of the survey work
(ii) The date of survey
(iii) The names of the members of the party.

The field work may be divided into the following:

(i) Reconnaissance survey.
(ii) Marking stations, drawing reference sketches.
(iii) Line by line surveying.

Reconnaissance survey consists in going round the field and identifying suitable stations for the network of triangles. Neat sketch of network is drawn and designated. The typical key plan drawn is similar to one shown in above figure.

All main stations should be marked on the ground. Some of the methods used for marking are:

(a) Fixing ranging poles
(b) Driving pegs
(c) Marking a cross if ground is hard
(d) Digging and fixing a stone.

Then reference sketches are drawn in the field book so as to identify stations when the development works are taken up. For this measurements with respect to three permanent points are noted. The permanent points may be

(a) Corner of a building
(b) Posts of gates
(c) Corners of compound walls
(d) Electric poles
(e) A tree.

After that, line by line surveying is conducted to locate various objects with respect to chain lines.

Office Work

It consists in preparing the plan of the area to a suitable scale making use of measurements and sketches

noted in the field book.

1.5 COMPASS

Compass surveying is a branch of surveying in which directions of surveying lines are determined with a compass and the length of lines are measured with a tape or chain. In practice the compass si generally used to run a traverse.

In surveying,"Traverse" consists of a series of straight lines connected together to form a open or a closed polygon.

Methods of traversing: Depending on the type of instrument used for the measurement of angles the method of Traversing can be classified as under;

1.Chain Traverse

2.Compass Traverse.

3.Plane Table Traverse.

4.Stadia Traverse.

5.Theodolite Traverse.

In Compass Traverse the direction of the traverse lines are determined with a magnetic compass.

The magnetic Compass may be "SURVEYOR COMPASS" OR "PRISMATIC COMPASS"

The types of compass that are used commonly are: (i) prismatic compass; and (ii) surveyor compass.
The essential parts of both type are:
(i) a magnetic needle,
(ii) a graduated circle,
(iii) a line of sight, and
(iv) a box to house them.
There are some differences in the essential parts of the two type of compass. The construction of the two types of compass is explained and the difference in them is pointed out in this article.

Prismatic Compass

in below Figure shows the cross-section of a typical prismatic compass. A magnetic needle of broad form (1) is balanced on a hard and pointed steel pivot (2). The top of the pointed pivot is protected with agate cap (3).


7
11
9
6
5
8
14
13
16
15
4
3
10
17
1
2
12
18
1. Needle
2. Pivot
3. Agate cap
4. Graduated disc
5. Slit metal frame
6. Horse hair
7. Mirror
8. Reflecting prism with cap
9. Eye vane
10. Focussing stud
11. Dark sunglasses
12. Box
13. Glass cover
14. Lifting pin
15. Light spring
16. Brake pin or knob
17. Lifting lever
18. Support to fit on tripod

Prismatic compass

An aluminium graduated disk (4) is fixed to the top of the needle. The graduations are from zero to 360° in clockwise direction when read from top. The direction of north is treated as zero degrees, east as 90°, south as 180° and west as 270°. However, while taking the readings observations are at the other end of line of sight. Hence, the readings are shifted by 180° and graduations are marked as shown in below figure. The graduations are marked inverted because they are read through a prism.



The line of sight consists of object unit and the reading unit. Object unit consists of a slit metal frame hinged to the box. In the centre the slit is provided with a horse hair or a fine wire or thread The metal frame is provided with a hinged mirror , which can be placed upward or downward on the frame. It can be slided along the frame. The mirror can be adjusted to view objects too high or too low from the position of compass. Reading unit is provided at diametrically opposite edge. It consists of a prism with a sighting eye vane . The prism magnifies the readings on the graduation disk just below it. For focussing, the prism is lowered or raised on the frame carrying it and then fixed with the stud. Dark sunglasses provided near the line of sight can be interposed if the object to be sighted is bright (e.g., sun). The bottom of the box which is about 85 mm to 110 mm supports the pivot of needle firmly at its centre. The object vane and the prism are supported on the sides of the box. The box is providedwith a glass lid which protects the graduation disc at the same time permit the direct reading from the top. When the object vane is folded on the glass top it presses a lifting pin which activates lifting lever lifts the needle off the pivot. Thus, it prevents undue wear of pivot point. While taking reading, if graduation disc vibrates, it can be dampened with a spring. For pressing spring a knob or brake pin is provided on the box. When not in use prism can be folded over the edge of the box. The box is provided with a lid to close it when the compass is not in use. The box is provided with a socket to fit it on the top of a tripod.

Surveyors Compass

In this type of compass graduation disc is fixed to the box and magnetic needle is free to rotate above it. There is no prism provided at viewing end, but has a narrow slit. After fixing the line of sight, the reading is directly taken from the top of the glass cover. Hence, graduations are written directly (not inverted). In this compass graduations are from zero to 90°, zero being to north or south and 90° being to east and west. An angle of 20° to north direction to the east is written as N 20° E, and an angle of 40° to east from south is written as S 40° E. Always first direction indicated is north or south and the last letter indicates east or west direction. In this system graduated circle rotates with line of sight and magnetic needle is always towards north. The reading is taken at the tip of needle. Hence, on the compass east and west are marked interchanged and marked shows the photograph of a surveyors compass.



(a) (b)

Fig. 13.3



Difference Between Prismatic Compass and Surveyors Compass
The difference between prismatic and surveyor’s compass are listed in below Table.



Sr. No.	Prismatic Compass	Surveyors Compass
1.	Graduation circle is fixed to broad type needle. Hence, it will not rotate with the line of sight.	Graduation circle is fixed to the box. Hence, it rotates with the line of sight.
2.	There is a prism at viewing end.	At viewing end there is no prism. There is only a slit.
3.	Sighting and reading can be done simultaneously.	Sighting and viewing cannot be done simultaneously.
4.	The magnetic needle do not act as an index.	Magnetic needle acts as index while reading.
5.	The graduations are in whole circle bearing.	The graduations are in quadrantal system.
6.	Graduations are marked inverted since its reflection is read through prism.	Graduations are marked directly. They are not inverted.
7.	The reading is taken through a prism.	The reading is taken by directly viewing from top glass.
8.	Tripod may or may not be used. It can be held on a stretched hand also.	Tripod is essential for using it.

Bearing

As stated earlier a bearing of a line is the angle made by the line with respect to a reference direction, the reference direction being known as meridian. The direction shown by a freely suspended and properly balanced magnetic needle is called magnetic meridian and the horizontal angle made by a line with this meridian is known as magnetic bearing. The points of intersection of earth's axis with surface of the earth are known as geographic north and south pole. The line passing through geographic north, south and the point on earth is called true meridian at that point and the angle made by a line passing through that point is called truebearing. While traversing along lines A, B, C, D …, the bearing of lime AB is called fore bearing of AB and the bearing of BA is called back bearing. Fore bearing and back bearing differ by 180°.

1.6 PLANE TABLE SURVEYING

In this method of surveying a table top, similar to drawing board fitted on to a tripod is the main instrument. A drawing sheet is fixed on to the table top, the observations are made to the objects, distances are scaled down and the objects are plotted in the field itself. Since the plotting is made in the field itself, there is no chance of omitting any necessary measurement in this surveying. However the accuracy achieved in this type of surveying is less. Hence this type of surveying is used for filling up details between the survey stations previously fixed by other methods. In this chapter, accessories required, working operations and methods of plane table surveying are explained. At the end advantages and limitations of this method are listed.

Plane Table and Its Accessories

The most commonly used plane table is shown in below Fig. It consists of a well seasoned wooden table top mounted on a tripod. The table top can rotate about vertical axis freely. Whenever necessary table can be clamped in the desired orientation. The table can be levelled by adjusting tripod legs.



Adjusting the tripod

Plane table with stand

The following accessories are required to carry out plane table survey:

1. Alidade
2. Plumbing fork with plumb bob.

3. Spirit level
4. Trough compass
5. Drawing sheets and accessories for drawing.

Alidade

It is a straight edge ruler having some form of sighting device. One edge of the ruler is bevelled and is graduated. Always this edge is used for drawing line of sight. Depending on the type of line of sight
there are two types of alidade:
(a) Plain alidade (b) Telescopic alidade

Plain Alidade: in below Figure shows a typical plain adidate. A sight vane is provided at each end of the ruler. The vane with narrow slit serves as eye vane and the other with wide slit and having a thin wire at its centre serves as object vane. The two vanes are provided with hinges at the ends of ruler so that when not in use they can be folded on the ruler. Plain alidade is not suitable in surveying hilly areas as the inclination of line of sight in this case is limited.


Eye vane
Object vane
Fiducial edge/Bevelled edge

Plane alidade


Bubble tube
Vertical circle
Telescope
Focussing screw
Straight edge ruler

Telescopic alidade

Telescopic Alidade: It consists of a telescope mounted on a column fixed to the ruler. The line of sight through the telescope is kept parallel to the bevelled edge of the ruler. The telescope is provided with a level tube and vertical graduation arc. If horizontal sight is required bubble in the level tube is kept at the centre. If inclined sights are required vertical graduation helps in noting the inclination of the line of sight. By providing telescope the range and the accuracy of line of sight is increased.



Plumbing fork and plumb bob.

Plumbing Fork and Plumb Bob

Figure shows a typical plumbing fork with a plum bob. Plumbing fork is a U-shaped metal in frame with a upper horizontal arm and a lower inclined arm. The upper arm is provided with a pointer at the end while the lower arm is provided with a hook to suspend plumb bob. When the plumbing fork is kept on the plane table the vertical line (line of plumb bob) passes through the pointed edge of upper arm. The plumb bob helps in transferring the ground point to the drawing sheet and vice versa also.



Spirit level

SpiritLevel

A flat based spirit level is used to level the plane table during surveying. To get perfect level, spirit level should show central position for bubble tube when checked with its positions in any two mutually perpendicular direction.

TroughCompass

It consists of a 80 to 150 mm long and 30 mm wide box carrying a freely suspended needle at its centre . At the ends of the needle graduations are marked on the box to indicate zero to five degrees on either side of the centre. The box is provided with glass top to prevent oscillation of the needle by wind. When needle is centred (reading 0–0), the line of needle is parallel to the edge of the box. Hence marking on the edges in this state indicates magnetic north–south direction.



Fig. 14.6. Trough compass

Drawing Sheet and Accessories for Drawing
A good quality, seasoned drawing sheet should be used for plane table surveying. The drawing sheet may be rolled when not in use, but should never is folded. For important works fibre glass sheets or paper backed with thin aluminium sheets are used.
Clips clamps, adhesive tapes may be used for fixing drawing sheet to the plane table. Sharp hard pencil, good quality eraser, pencil cutter and sand paper to keep pencil point sharp are other accessories required for the drawing work. If necessary, plastic sheet should be carried to cover the drawing sheet from rain and dust.

1.6.1 Working Operation

After fixing the table top to the stand and drawing sheet to the table, the following operations are to be
carried out before map making:

1. Centering
2. Levelling
3. Orientation.

1 **Centering**
Centering is the process of setting the plane table on the point so that its plotted position is exactly over the position on the ground. This is achieved by moving the legs of the tripod and checking the position of the point on the ground and on the paper with the help of plumbing fork and plumb bob.

2 **Levelling**
The level of the plane table should be ensured in two positions of spirit level which are at right angles to each other. The legs of tripod are moved radially or along the circumference to adjust the plane table and get levelled surface.

3 **Orientation**
Orientation is the process of setting plane table over a station such that all the lines already plotted are parallel to corresponding lines on the ground. Accuracy of plane table survey mainly depends upon the
accuracy of orientation of plane table at each station point. It can be achieved by any one of the following methods:
(a) using trough compass
(b) by back sighting
(c) by solving two point or three point problems.
The first two methods are commonly used while the third method is used occationally. The third method is explained under the article methods of plane tabling by resection.

(a) Orientation Using Trough Compass: When the survey work starts, the plane table is set on first station and the table is oriented by rough judgement such that the plotted position of the area falls in the middle portion of the paper. Then the table is clamped and the north direction is marked on right hand side top corner of drawing sheet. Trough compass is used to identify north direction. This orientation is to be maintained at all subsequent stations. After centering and levelling the table trough compass is kept along the marked north direction and the table is rotated to get freely suspended magnetic needle centred. After achieving it the table is clamped.
This method of orientation is considered rough, since the local attraction to magnetic needle affects the orientation. This method is used as preliminary orientation and finer tuning is made by observing the already plotted points.

(b) Orientation by Back Sighting: It is the commonly used method in plane table surveying. After completing surveying from plane table set at A, if table is to be shifted to next station B, a line is drawn from the plotted position of station A towards station B. Then distance AB is measured, scaled down and plotted position of station B is obtained. Then table is shifted to station B, centred, levelled. Then keeping alidade along BA, station A is sighted and the table is clamped. Thus the orientation of the table is achieved by back sighting. Orientation may be checked by observing already plotted objects.

Method of planning table

The following four methods are available for carrying out plane table survey:
1. Radiation
2. Intersection
3. Traversing
4. Resection.

The first two methods are employed for locating details while the other two methods are used for locating position of plane table station on drawing sheet.

1 Radiation

After setting the plane table on a station, say O, it is required to find the plotted position of various objects A, B, C, D ….. . To get these positions, the rays OA, OB, OC ….. are drawn with soft pencil. Then the distances OA, OB, OC ….., are measured scaled down and the positions of A, B, C ….., are found on the drawing sheets. This method is suitable for surveying small areas and is convenient if the distances to be measured are small. For larger areas this method has wider scope, if telescopic alidade is used, in which the distances are measured technometrically.



Radiation method of plane tabling

Intersection

In this method the plotted position of an object is obtained by plotting rays to the object from two stations. The intersection gives the plotted position. Thus it needs the linear measurements only between the station points and do not need the measurements to the objects. In below Figure shows the method for locating objects A and B from plane table positions O1 and O2.



Intersection method of plane tabling

This method is commonly employed for locating:

(a) details

(b) the distant and inaccessible points

(c) the stations which may be used latter.

Traversing

This is the method used for locating plane table survey stations. In this method, ray is drawn to next station before shifting the table and distance between the stations measured. The distance is scaled down and next station is located. After setting the plane table at new station orientation is achieved by back sighting. To ensure additional checks, rays are taken to other stations also, whenever it is possible. In below Figure shows a scheme of plane table survey of closed area. This method can be used for open traverses also.



Plane table traversing

Resection

This method is just opposite to the method of intersection. In the method of intersection, the plotted position of stations are known and the plotted position of objects are obtained by intersection. In this method the plotted position of objects are known and the plotted position of station is obtained. If a, b and c are the plotted positions of objects A, B and C respectively, to locate instrument station P on the paper, the orientation of table is achieved with the help of a, b, c and then resectors Aa, Bb, Cc are drawn to get the ‘p’ , the plotted position of P. Hence in the resection method major work is to ensure suitable orientation by any one of the methods. The following methods are employed in the method of resection:

(a) by compass
(b) by back sighting
(c) by solving two point problem
(d) by solving three point problem.

(a) Resection after Orientation by Compass: Let a and b be the plotted positions of A and B of two well defined points in the field. Keeping the through compass along north direction marked on the drawing sheet table is oriented on station P, the position of which is to be found on paper. The resectors Aa and Bb are drawn to locate ‘p’ the plotted position of station point P. This method gives satisfactory results, if the area is not influenced by local attractions. It is used for small scale mapping only.



Station P
Resection after orientation with compass

(b) Resection after Orientation by Back Sighting: in below Figure shows the scheme of resection after orientation by back sighting. From station A, the position of B is plotted as ‘b’ and ray has been taken to station P as ap′. Then plane table is set at P and oriented by back sighting A, line AP is not measured but the position of P is obtained on the paper by taking resection Bb.



Resection after back sighting

(c) Resection after Solving Two Point Problem: The problem of finding plotted position of the station point occupied by the plane table with the help of plotted positions of two well defined points is known as solving two point problem. In below Figure shows the scheme of solving this.



Two-point problem

Let A and B be two well defined points like lightening conductor or spire of church, the plotted positions a and b already known. Now the problem is to orient the table at P so that by resection its plotted position p can be obtained. The following steps may be followed to solve this problems:
(i) Select a suitable point Q near P such that the angles PAQ and PBQ are not accute.
(ii) Roughly orient the table at Q and draw the resectors Aa and Bb to get the point ‘q’.
(iii) Draw the ray qp and locate p1 with estimated distance QP.
(iv) Shift the plane table to P and orient the table by back sighting to Q.
(v) Draw the resector Aa to get ‘p’.
(vi) Draw the ray pB. Let it intersect line bq at b1.

(vii) The points b and b1 are not coinciding due to the angular error in the orientation of table. The angle bab, is the angular error in orientation. To correct it,
* Fix a ranging rod at R along ab, * Unclamp the table and rotate it till line ab sights ranging rod at R. Then clamp the table. This gives the correct orientation of the table which was used in plotting the points A and B. (viii) The resectors Aa and Bb are drawn to get the correct plotted position ‘p’ of the station P.

(d) Resection after Solving Three Point Problem: Locating the plotted position of a station point using observations to three well defined points whose plotted positions are known, is called solving three point problem.

Let A, B, C be three well defined objects on the field whose plotted positions a, b and c are known. Now the problem is to locate plotted position of the station point P. Any one of the following methods can be used.

(i) Mechanical (Tracing paper) method,
(ii) Graphical method, or
(iii) Trial and error method (Lehman’s method).

(i) Mechanical Method: This method is known as tracing paper method since it needs a tracing paper. The method involved the following steps



* Set the table over station P and by observation approximately orient the table.
* Fix the tracing paper on the plane table and select P approximately, say as p′. From p′, draw p′ A, p′ B and p′ C. These lines may not pass through the plotted positions a, b and c since the orientation is not exact.
* Loosen the tracing paper and rotate it so that the rays pass through respective points a, b and c. Now prick the point p′ to get the plotted position ‘p’ of the station P.
* Keep the alidade along pa and sight A. Then clamp the table. This is correct orientation. Check the orientation by observing along pb and pc.

(ii) Graphical Method: The following two graphical methods are available to solve three point problem:
* Bessel’s solution
* Method of perpendiculars.

Bessels Solution: It involves the following steps:
1. Keep the bevelled edge of alidade along ba and sight object at A. Clamp the table and draw bc′ along the line bc.
2. Keep bevelled edge of alidade along ab, unclamp the table and sight B. Clamp the table. Draw line ac intersecting bc′ at d.
3. Keep the alidade along dc and bisect C. Clamp the table. This gives the

correct orientation.

4. Draw resectors to get ‘p’.



Graphical solution (Bessel’s method)

Method of Perpendiculars

This is another graphical method. It involves the following steps.

1. Draw line ae perpendicular to ab. Keep alidade along ea and turn the table till A is sighted. Clamp the table and draw the ray Bb to intersect the ray Aac at e.
2. Draw cf perpendicular to bc and clamp the table when fcC are in a line. Draw Bb to intersect Ccf at F .



Method of perpendiculars of solve three point problem

3. Join cf drop bp perpendicular to ef to get the plotted position ‘p’.
4. Orient the table such that pbB are in a line. Clamp the table to place it in correct orientation. Resections Aa and Cc may be used to check the orientation.

Trial and Error Method

This method is also known as ‘triangle of error method’ and ‘Lehman’s Method’. It involves the following steps:

1. Set the table over point P and orient the table approximately, just by observation.
2. Draw the rays aA, bB and cC. If the orientation was perfect, the three rays would have intersected at a single point, i.e. at point ‘p’. Otherwise a triangle of error is formed.
3. To eliminate the triangle of error an approximate position, ray p′, is selected near the triangle of error. Then keeping alidade along p′a object A is sighted and the table is clamped. Draw the

resectors cC and bB to check the orientation.

4. Above step is repeated till triangle of error is eliminated.



Lehman presented the following guidelines to select 'p′' so that triangle of error is eliminated quickly.

Rule 1: The distance of point sought 'p' is in the same proportion from the corresponding rays as the distance of those from the plane table station.

Rule 2: The point sought 'p' is on the same side of all the three resectors.

Defining the triangle ABC on the field as great triangle and the circle passing through them as great circle, from the above two rules of Lehman, the following sub-rules may be drawn.



* If 'P' lies within the great triangle, the point 'p' is within the triangle of error

* If the plane table station P lies outside the great triangle the point sought 'p' is outside the triangle of errors (p2).

* If the 'P' is on the great circle, the correct solution is impossible (p3 and p4).

* If 'P' is outside the great circle, 'p' is nearer to the intersection of rays to the nearest two points (P5).

* If point P is outside the great circle and the two rays drawn are parallel to each other the point sought is outside the parallel lines and on the same side of the three rays (P6).

1.6.2 Error in Plane Table Serveying

The errors may be grouped into the instrumental and personal errors.

Instrumental Errors
1. The surface of plane table not perfectly plane.
2. Bevelled edge of alidade not straight.
3. Sight vanes of alidade not perfectly perpendicular to the base.
4. Plane table clamp being loose.
5. Magnetic compass being sluggish.
6. Drawing sheet being of poor quality.

Personal Errors
1. Centering errors
2. Levelling errors
3. Orientation errors
4. Sighting errors
5. Errors in measurement
6. Plotting errors
7. Errors due to instability of tripod.

Advantages are
1. Possibility of omitting measurement is eliminated.
2. The surveyor can compare the plotted work in the field then and there only.
3. Irregular objects are plotted more accurately, since they are seen while plotting.
4. Booking errors are eliminated.
5. Local attractions do not influence the plotting.
6. No great skill is required to produce satisfactory maps.
7. Method is fast.
8. No costly instruments are required.

Limitations are
1. Survey cannot be conducted in wet weather and rainy days.
2. Plane table is cumbersome and heavy to carry.
3. It needs many accessories.
4. It is less accurate.
5. Reproduction of map to different scale is difficult.

Review Questions

1. **Describe chain principle and classification with example?**
2. **What is surveying explain in detail?**
3. **Explain the chaining in reciprocal ?**
4. **What is the technique of compass in surveying ?**
5. **What is pessimistic compass explain with example?**
6. **What is adjustment of error explain?**
7. **Explain Local Attraction?**
8. **Explain the technique of Plain Table Serveying ?**
9. **What are the merit and demerit of plane table surveying?**
10. **What are the radiation intersection and radiation traversing explain?**

Chapter 2

LEVELLING AND THEODOLITE SURVEYING

Structure of this unit

LEVELLING, THEODOLITE

Learning Objectives

1. LEVELLING
2. Level line
3. Horizontal line
4. Levels and Staves
5. Spirit level
6. sensitiveness
7. Bench marks
8. Temporary and Permanent adjustments
9. Fly and check levelling – Booking
10. Reduction
11. Curvature and Refraction
12. Reciprocal levelling
13. Longitudinal and Cross sections – Plotting .
14. THEODOLITE
15. Theodolite
16. Vernier and Microptic
17. Description and uses
18. Temporary and Permanent adjustments of vernier transit
19. Horizontal angles – Heights and Distances
20. Traversing – Closing error and distribution.

2.1 LEVELLING

Elevation measurements involve measurements in vertical plane. It is also known as levelling. It may be defined as the art of determining the elevations of given points above or below a datum line or establishing given points of required heights above or below the datum line.

Levelling (or **leveling** in American spelling) is a branch of surveying, the object of which is to

1. Find the elevation of a given point with respect to the given or assumed Datum.
2. Establish a point at a given elevation with respect to the given or assumed Datum.

Levelling is the measurement of geodetic height using an optical levelling instrument and a level staff or rod having a numbered scale. Common levelling instruments include the spirit level, thedumpy level, the digital level, and the laser level.

Spirit (Optical) levelling

Spirit levelling employs a spirit level, an instrument consisting of a telescope with a crosshair and a tube level like that used by carpenters, rigidly connected. When the bubble in the tube level is centered the telescope's line of sight is supposed to be horizontal (i.e. perpendicular to the local vertical).

The spirit level is on a tripod midway between the two points whose height difference is to be determined. A leveling staff or rod is held vertical on each point; the rod is graduated in centimetres and fractions or tenths and hundredths of a foot. The observer focuses in turn on each rod and reads the value. Subtracting the "back" and "forward" value provides the height difference.

We can't expect the instrument to be in perfect adjustment, but we can hope that when the bubble is centered the telescope's line of sight is always the same small angle off of horizontal. If it is, we can still level accurately by setting the instrument equidistant from the points to be measured, so the errors cancel.

2.1.1 Leveling Procedure

A typical procedure is to set up the instrument within 100 metres (110 yards) of a point of known or assumed elevation. A rod or staff is held vertical on that point and the instrument is used manually or automatically to read the rod scale. This gives the height of the instrument above the starting (backsight) point and allows the height of the instrument (H.I.) above the datum to be computed.

The rod is then held on an unknown point and a reading is taken in the same manner, allowing the elevation of the new (foresight) point to be computed. The procedure is repeated until the destination point is reached. It is usual practice to perform either a complete loop back to the starting point or else close the traverse on a second point whose elevation is already known. The closure check guards against blunders in the operation, and allows residual error to be distributed in the most likely manner among the stations.

Some instruments provide three crosshairs which allow stadia measurement of the foresight and backsight distances. These also allow use of the average of the three readings (3-wire leveling) as a check against blunders and for averaging out the error of interpolation between marks on the rod scale.

The two main types of levelling are single-levelling as already described, and double-levelling (Double-rodding). In double-levelling, a surveyor takes two foresights and two backsights and makes sure the difference between the foresights and the difference between the backsights are equal, thereby reducing the amount of error. Double-levelling costs twice as much as single-levelling.

Refraction and Curvature

The curvature of the earth means that a line of sight that is horizontal at the instrument will be higher and higher above a spheroid at greater distances. The effect may be significant for some work at distances under 100 meters.

The line of sight is horizontal at the instrument, but is not a straight line because of refraction in the air. The change of air pressure with elevation causes the line of sight to bend toward the earth. The amount of refraction depends slightly on air temperature and pressure.

The combined correction is approximately:

$$\Delta h_{meters} = 0.067 D_{km}^2 \text{ or } \Delta h_{feet} = 0.021 \left(\frac{D_{ft}}{1000}\right)^2$$

For precise work these effects need to be calculated and corrections applied. For most work it is sufficient to keep the foresight and backsight distances approximately equal so that the refraction and curvature effects cancel out.

Leveling loops and Gravity Variations

If the Earth's gravity field were completely regular and gravity constant, leveling loops would always close precisely:

$$\sum_{i=0}^{n} \Delta h_i = 0$$

around a loop. In the real gravity field of the Earth, this happens only approximately; on small loops typical of engineering projects, the loop closure is negligible, but on larger loops covering regions or continents it is not.

Instead of height differences, geopotential differences do close around loops:

$$\sum_{i=0}^{n} \Delta h_i g_i,$$

where g_i stands for gravity at the leveling interval i. For precise leveling networks on a national scale, the latter formula should always be used.

$$\Delta W_i = \Delta h_i g_i$$

should be used in all computations, producing geopotential values W_i for the benchmarks of the network.

Levelling Instruments

Older Instruments

The wye level is the oldest and bulkiest of the older style optical instruments. A low-powered telescope is placed in a pair of clamp mounts, and the instrument then leveled using a spirit level, which is mounted parallel to the main telescope.

The dumpy level was developed by English civil engineer William Gravatt, while surveying the route of a proposed railway line form London to Dover. More compact and hence both more robust and easier to transport, it is commonly believed that dumpy levelling is less accurate than other types of levelling, but such is not the case. Dumpy levelling requires shorter and therefore more numerous sights, but this fault is compensated by the practice of making foresights and backsights equal.

Precise Level designs were often used for large leveling projects where utmost accuracy was required. They differ from other levels in having a very precise spirit level tube and a micrometer adjustment to raise or lower the line of sight so that the crosshair can be made to coincide with a line on the rod scale and no interpolation is required.

Automatic level

Automatic levels make use of a compensator that ensures that the line of sight remains horizontal once the operator has roughly leveled the instrument (to within maybe 0.05 degree). The surveyor sets the instrument up quickly and doesn't have to relevel it carefully each time he sights on a rod on another point. It also reduces the effect of minor settling of the tripod to the actual amount of motion instead of leveraging the tilt over the sight distance. Such levels became standard in the later part of the twentieth century. Three level screws are used to level the instrument.

Digital Level

Digital levels electronically read a bar-coded scale on the staff. These instruments usually include data recording capability. The automation removes the requirement for the operator to read a scale and write down the value, and so reduces blunders. It may also compute and apply refraction and curvature corrections.

Laser level

Laser levels project a beam which is visible and/or detectable by a sensor on the leveling rod. This style is widely used in construction work but not for more precise control work. An advantage is that one person can perform the levelling independently, whereas other types require one person at the instrument and one holding the rod.

The sensor can be mounted on earth-moving machinery to allow automated grading.

2.1.2 Object and use of leveling

As stated in the definition of levelling, the object is
(i) to determine the elevations of given points with respect to a datum
(ii) to establish the points of required height above or below the datum line. Uses of levelling are
(i) to determine or to set the plinth level of a building.
(ii) to decide or set the road, railway, canal or sewage line alignment.
(iii) to determine or to set various levels of dams, towers, etc.
(iv) to determine the capacity of a reservoir.

2.1.3 Term used in leveling

Before studying the art of levelling, it is necessary to clearly understand the following terms used in levelling:

1. Level Surface: A surface parallel to the mean spheroid of the earth is called a level surface and the line drawn on the level surface is known as a level line. Hence all points lying on a level surface are equidistant from the centre of the earth. In below Figure shows a typical level surface.


Mean spheroid of earth
A level surface
Centre of earth
A level surface

A level surface

2. **Horizontal Surface**: A surface tangential to level surface at a given point is called horizontal surface at that point. Hence a horizontal line is at right angles to the plumb line at that point


P
Horizontal line at P
Level line through P
Vertical line at P
Centre of earth

Vertical and horizontal lines

3. Vertical Line: A vertical line at a point is the line connecting the point to the centre of the earth. It is the plumb line at that point. Vertical and horizontal lines at a point are at right angles to each other.

4. Datum: The level of a point or the surface with respect to which levels of other points or planes are calculated, is called a datum or datum surface.

5. Mean Sea Level (MSL): MSL is the average height of the sea for all stages of the tides. At any particular place MSL is established by finding the mean sea level (free of tides) after averaging tide heights over a long period of at least 19 years. In India MSL used is that established at Karachi, presently, in Pakistan. In all important surveys this is used as datum.

6. Reduced Levels (RL): The level of a point taken as height above the datum surface is known as RL of that point.

7. Benchmarks: A benchmark is a relatively permanent reference point, the elevation of which is known (assumed or known w.r.t. MSL). It is used as a starting point for levelling or as a point upon which to close for a check. The following are the different types of benchmarks used in surveying:

(a) GTS benchmarks (b) Permanent benchmarks

(c) Arbitrary benchmarks and (d) Temporary benchmarks.

(a) GTS Benchmark: The long form of GTS benchmark is Great Trigonometrical Survey benchmark. These benchmarks are established by national agency. In India, the department of Survey of India is entrusted with such works. GTS benchmarks are established all over the country with highest precision survey, the datum being mean sea level. A bronze plate provided on the top of a concrete pedastal with elevation engraved on it serves as benchmark. It is well protected with masonry structure built around it so that its position is not disturbed by animals or by any unauthorised person. The position of GTS benchmarks are shown in the topo sheets published.

(b) Permanent Benchmark: These are the benchmarks established by state government agencies like PWD. They are established with reference to GTS benchmarks. They are usually on the corner of plinth of public buildings.

(c) Arbitrary Benchmark: In many engineering projects the difference in elevations of neighbouring points is more important than their reduced level with respect to mean sea level. In such cases a relatively permanent point, like plinth of a building or corner of a culvert, are taken as benchmarks, their level assumed arbitrarily such as 100.0 m, 300.0 m, etc.

(d) Temporary Benchmark: This type of benchmark is established at the end of the day’s work, so that the next day work may be continued from that point. Such point should be on a permanent object so that next day it is easily identified.

2.1.4 Levelling Instruments

A level is an instrument giving horizontal line of sight and magnifying the reading at a far away distance. It consists of the following parts:

(i) A telescope to provide a line of sight

(ii) A level tube to make the line of sight horizontal and

(iii) A levelling head to level the instrument.

The following types of levels are available:

(i) Dumpy level (ii) Wye (or, Y) level

(iii) Cooke’s reversible level (iv) Cushing’s level
(v) Tilting level and (vi) Auto level.

DumpyLevel

It is a short and stout instrument with telescope tube rigidly connected to the vertical spindle. Hence the level tube cannot move in vertical plane. It cannot be removed from its support. Hence it is named as dumpy level. The telescope rotates in horizontal plane in the socket of the levelling head. A bubble tube is attached to the top of the telescope. Figure 15.3 shows a typical dumpy level. In below shows its photograph.

Dumpy level



1. Telescope
2. Eyepiece
3. Shade
4. Objective end
5. Longitudinal bubble tube
6. Transverse bubble tube
7. Bubble tube adjusting screws
8. Diaphragm adjusting screws
9. Focusing screws
10. Foot screws
11. Upper parallel plate (tribrach)
12. Foot plate (Trivet stage)

Dumpy level

Telescope is a tube with object glass and eyepiece. Object glass can be adjusted using the focussing screw before sighting the graduated staff held on the object. Eyepiece can be adjusted by rotating it to see that parallel is removed and cross hairs appears distinctly. Eyepiece once adjusted needs no change as long as the same person takes the readings.

Level tube is a glass tube with slightly curved shape provided over the level tube. The tube is filled with ether or alcohol leaving a little air gap, which takes the shape of a bubble. The air bubble is always at the highest point. The level tube is fixed with its axis parallel to telescope tube, so that when bubble is centred, the telescope is horizontal. The tube is graduated on either side of its centre to estimate how much the bubble is out of centre. The glass tube is placed inside a brass tube which is open from top and on lower side it is fixed to telescope tube by means of capston headed nuts. The bubble tube is adjusted with these nuts, if it is out of order.

Levelling head consists of two parallel plates with three foot screws. The upper plate is known as tribratch plate and the lower one as the trivet. The lower plate can be screwed on to the tripod stand.
By adjusting the screws the instrument can be levelled to get perfect horizontal line of sight. Dumpy level is to be fitted to a tripod stand to use it in the field. The tripod stand consists of three legs connected to a head to which the lower plate of level can be fitted. The lower side of the legs are provided with metal shoes to get good grip with ground. In below Plate shows typical level stands.

Levelling stands (adjustable and non-adjustable)

Wye or Y-Level
In this type of level, the telescope is supported in two Y-shaped supports and can be fixed with the help of curved clips. Clips can be opened and telescope can be reversed end to end and fitted. The advantage of this level is some of the errors eliminated, if the readings are taken in both the direction of telescope.

Cooke’sReversibleLevel
In this instrument the telescope is supported by two rigid sockets into which telescope can be introduced from either end and then screwed. For taking the readings in the reversed position of telescope, the screw is slackened and then the telescope is taken out and reversed end for end. Thus it combines the rigidity of dumpy level and reversibility of Y-level.

CushingsLevel
In this reversing of telescope end for end is achieved by interchanging the eyepiece and the objective piece since both collars are exactly the same.

TiltingLevel
In this, telescope can be tilted through about four degrees with the help of a tilting screw. Hence bubble can be easily centered. But it needs centering of the bubble before taking every reading. Hence it is useful, if at every setting of the instrument number of readings to be taken are few.

AutoLevel
The auto-level or the automatic-level is a self aligning level. Within a certain range of tilt automatic levelling is achieved by an inclination compensating device. The operational comfort, high speed and precision are the advantages of this instrument.

Levelling Staff

Along with a level, a levelling staff is also required for levelling. The levelling staff is a rectangular rod having graduations. The staff is provided with a metal shoes at its bottom to resist wear and tear. The foot of the shoe represents zero reading. Levelling staff may be divided into two groups:
(i) Self reading staff (ii) Target staff.
(i) Self reading staff: This staff reading is directly read by the instrument man through telescope. In a metric system staff, one metre length is divided into 200 subdivisions, each of uniform thickness of 5 mm. All divisions are marked with black in a white background. Metres and decimetres are written in red colour. The following three types of self reading staffs are available:
(a) Solid staff: It is a single piece of 3 m.
(b) Folding staff: A staff of two pieces each of 2 m which can be folded one over the other.
(c) Telescopic staff: A staff of 3 pieces with upper one solid and lower two hollow. The upper part can slide into the central one and the central part can go into the lower part.
Each length can be pulled up and held in position by means of brass spring. The total length may be 4 m or 5 m .



(a) Self-reading staff


(b) Telescopic staff



(c) Target staff

(ii) Target staff: If the sighting distance is more, instrument man finds it difficult to read self reading staff. In such case a target staff shown in may be used. Target staff is similar to self reading staff, but provided with a movable target. Target is a circular or oval shape, painted red and white in alternate quadrant. It is fitted with a vernier at the centre. The instrument man directs the person holding target staff to move the target, till its centre is in the horizontal line of sight. Then target man reads the target and is recorded.

2.1.5 Method of Levelling

The following methods are used to determine the difference in elevation of various points:
(i) Barometric levelling (ii) Hypsometric levelling
(iii) Direct levelling and (iv) Indirect levelling.

Barometric Levelling
This method depends on the principle that atmospheric pressure depends upon the elevation of place.
Barometer is used to measure the atmospheric pressure and hence elevation is computed.
However it is not accurate method since the atmospheric pressure depends upon season and temperature also. It may
be used in exploratory surveys.

Hypsometric Levelling
This is based on the principle that boiling point of water decreases with the elevation of the place.
Hence the elevation difference between two points may be found by noting the difference in boiling point of water in the two places. This method is also useful only for exploratory survey.

Direct Levelling
It is common form of levelling in all engineering projects. In this method horizontal sight is taken on a graduated staff and the difference in the elevation of line of sight and ground at which staff is held are found. Knowing the height of line of sight from the instrument station the difference in the elevations of instrument station and the ground on which staff is held can be found. This method is thoroughly explained in next article.

Indirect Methods
In this method instruments are used to measure the vertical angles. Distance between the instrument and staff is measured by various methods. Then using trigonometric relations, the difference in elevation can be computed. This is considered beyond the scope of this book. One can find details of such methods in books on surveying and levelling.

2.1.6 Terms Used in Direct Levelling Methods

The following terms are used in direct method of levelling:
(i) Plane of Collimation: It is the reduced level of plane of sight with respect to the datum selected. It is also known as ‘height of instrument’. It should not be confused with the height of telescope from the ground where the instrument is set.
(ii) Back Sight (BS): It is the sight taken on a level staff held on the point of known elevation with an intension of determining the plane of collimation. It is always the first reading after the instrument is set in a place. It is also known as plus sight, since this reading is to be added to RL of the point (Benchmark or change point) to get plane of collimation.
(iii) Intermediate Sight (IS): Sights taken on staff after back sight (first sight) and before the last sight (fore sight) are known as intermediate sights. The intension of taking these readings is to find the reduced levels of the points where staff is held. These sights are known as ‘minus sights’ since the IS reading is to be subtracted from plane of collimation to get RL of the point where staff is held.
(iv) Fore Sight (FS): This is the last reading taken from the instrument station before shifting it or just before ending the work. This is also a minus sight.
(v) Change Point (CP): This is also known as turning point (TP). This is a point on which both fore sights and back sights are taken. After taking fore sight on this point instrument is set at some other convenient point and back sight is taken on the staff held at the same point. The two readings help in establishing the new plane of collimation with respect to the earlier datum. Since there is time gap between taking the two sights on the change point, it is advisable to select change point on a well defined point.

2.1.6 Temporary Adjustments of Level

The adjustments to be made at every setting of the instrument are called temporary adjustments. The following three adjustments are required for the instrument whenever set over a new point before taking a reading:

(i) Setting (ii) Levelling and
(iii) Focussing.

Setting
Tripod stand is set on the ground firmly so that its top is at a convenient height. Then the level is fixed on its top. By turning tripod legs radially or circumferentially, the instrument is approximately levelled.

Some instruments are provided with a less sensitive circular bubble on tribrach for this purpose.
Levelling The procedure of accurate levelling with three levelling screw is as given below:

(i) Loosen the clamp and turn the telescope until the bubble axis is parallel to the line joining any two screws.



(ii) Turn the two screws inward or outward equally and simultaneously till bubble is centred.

(iii) Turn the telescope by 90° so that it lies over the third screw and level the instrument by operating the third screw.

(iv) Turn back the telescope to its original position and check the bubble. Repeat steps (ii) to (iv) till bubble is centred for both positions of the telescope.

(v) Rotate the instrument by 180°. Check the levelling.

Focussing
Focussing is necessary to eliminate parallax while taking reading on the staff. The following two stepsare required in focussing:
(i) Focussing the eyepiece: For this, hold a sheet of white paper in front of telescope and rotate eyepiece in or out till the cross hairs are seen sharp and distinct.
(ii) Focussing the objective: For this telescope is directed towards the staff and the focussing screw is turned till the reading appears clear and sharp.

2.1.7 Types of Direct Levelling

The following are the different types of direct levelling:
(i) Simple levelling (ii) Differential levelling
(iii) Fly levelling (iv) Profile levelling
(v) Cross sectioning and (vi) Reciprocal levelling.
Simple Levelling
It is the method used for finding difference between the levels of two nearby points. Figure 15.6 shows one such case in which level of A is assumed, say 200.00 m. RL of B is required.



RL of A = 200.00 m
Back sight on A = 2.7 m.
∴ Plane of collimation for setting at station = 200 + 2.7 = 202.7 m
Fore sight on B = 0.80 m
∴ RL of B = 202.7 – 0.80 = 201.9 m

It may be noted that the instrument station L1 need not be along the line AB (in plan) and RL of L1 do not appear in the calculations.

Differential Levelling

If the distance between two points A and B is large, it may not be possible to take the readings on A and B from a single setting.

In such situation differential levelling is used. In differential levelling the instrument is set at more than one position, each shifting facilitated by a change point. Figure 15.7 shows a scheme of such setting.



(a) Elevation

(b) Plan

RL of A is 200.00 m. Instrument is set up at L1 and back sight on A is 1.35 m. The fore sight on change point CP1 is 1.65 m. Then instrument is shifted to L2 and back sight on CP1 is 1.40 m. Fore sight on CP2 is 1.70 m. After this instrument is shifted to L3 and back sight on CP2 is 1.3 m. The work ended with a fore sight of 1.85 m on B. The RL of B is to be found.

RL of A = 200.00 m Back sight on A = 1.35 m
∴ Plane of collimation at L1 = 200 + 1.35 = 201.35 m
Fore sight on CP1 = 1.65 m
∴ RL of CP1 = 201.35 – 1.65 = 199.70 m
Back sight to CP1 from L2 = 1.40
∴ Plane of collimation at L2 = 199.70 + 1.40 = 201.10 m
Fore sight to CP2 = 1.70 m
∴ RL of CP2 = 201.10 – 1.70 = 199.40 m
Back sight to CP2 from L3 = 1.30 m
∴ Plane of collimation at L3 = 199.40 + 1.30 = 200.70 m
Fore sight to B = 1.85 m
∴ **RL of B** = 200.70 – 1.85 = **198.85 m Ans.**

If there are intermediate sight to the points E1 and E2, the RL of those points may be obtained by subtracting readings for E1 and E2 from the corresponding plane of collimations.

Booking and Reducing the Levels

The booking of readings and reducing the levels can be carried out systematically in the tabular form.

There are two such methods:

(i) Plane of collimation method (ii) Rise and fall method.

For the above problem, with intermediate sights to E1 = 0.80 m and E2 = 0.70 m is illustrated below by the both methods.

Booking and reducing levels by plane of collimation method



Station	*BS*	*Reading* *IS*	*FS*	*Plane of Collimation*	*RL*	*Remarks*
A	1.35			201.35	200.00	Benchmark
E_1		0.80			200.55	Plinth of building
CP_1	1.40		1.65	201.10	199.70	CP_1
E_2		0.70			200.40	Plinth of building
CP_2	1.30		1.70	200.70	199.40	CP_2
B			1.85		198.85	B

Check Σ BS = 4.05 Σ FS = 5.20 Diff in RL of A and B

Σ BS – Σ FS = – 1.15 (Fall) = 198.85 – 200.00 = –1.15

In this method note the following:

1. Plane of collimation for first setting
= RL of BM + BS
2. Subtract IS from plane of collimation to get RL of intermediate station and subtract FS from plane of collimation to get RL of change point.
3. Add back sight to RL of change point to get new plane of collimation.
4. Check: Σ BS – Σ FS = RL of Last point – RL of first point.

If it is –ve, it is fall and if +ve it is rise.



Booking and reducing level by rise and fall method

Station	BS	IS	FS	Rise	Fall	RL	Remarks
A	1.35					200.00	Benchmark
		0.80		0.55		200.55	E_1
	1.40		1.65		0.85	199.70	CP_1
		0.70		0.70		200.40	E_2
	1.30		1.70		1.00	199.40	CP_2
			1.85		0.55	198.85	B

Σ BS = 4.05 Σ FS = 5.20 Σ Rise = 1.25 Σ Fall = 2.40

Check: Σ BS – Σ FS = –1.15 Σ Rise – Σ Fall = –1.15 RL of last point – RL of first point = –1.15

Note the following:

1. From A to E1, difference = 1.35 – 0.80 = 0.55, rise
2. From E1 to CP1, difference = 0.80 – 1.65 = – 0.85, fall
3. From CP1 to E2, difference = 1.40 – 0.70 = 0.70, rise
4. From E2 to CP2, difference = 0.70 – 1.70 = –1.00, fall
5. From CP2 to B, difference = 1.30 – 1.85 = – 0.55, fall.

Fly Levelling

If the work site is away from the benchmark, surveyor starts the work with a back sight on the benchmark by setting instrument at a convenient point. Then he proceeds towards the site by taking fore sights and back sights on a number of change points till he establishes a temporary benchmark in the site. Rest of the levelling work is carried out in the site. At the end of the work again levelling is carried out by taking a set of convenient change points till the bench work is reached. This type of levelling in which only back sight and fore sights are taken, is called fly levelling, the purpose being to connect a benchmark with a temporary benchmark or vice versa. Thus the difference between fly levelling and differential levelling is only in the purpose of levelling.

Profile Levelling

This type of levelling is known as longitudinal sectioning. In high way, railway, canal or sewage line projects profile of the ground along selected routes are required. In such cases, along the route, at regular interval readings are taken and RL of various points are found. Then the section of the route is drawn to get the profile. In below fig (a) shows the plan view of the scheme of levelling and in below fig (b)

shows the profile of the route. For drawing profile of the route, vertical scale is usually larger compared to scale for horizontal distances. It gives clear picture of the profile of the route.



(a)



(b)

The typical page of field book for this work will be having an additional column to note distances as shown in above table

Page of level book for profile levelling



Station	*Distance*	*BS*	*IS*	*FS*	*Plane of Collimation*	*RL*	*Remark*

Cross-Sectioning

In many engineering projects, not only longitudinal profile but also the profile of cross-sections at regular intervals are required. These profiles help in calculating the earth works involved in the projects.

in below Figure shows the scheme of such work in which longitudinal profile is found by taking readings at 20 m interval along chain lines AB, BC and readings are taken at an interval of 3 m on either side. The distances on the cross-sections are treated as left or right of the lines as they are found while facing the forward station of survey. The cross-sectional length depends upon the nature of the project.



shows a page of level book required for this type of levelling.

A typical page book for cross-section levelling



Station	Distance in m			Readings			Plane of Collimation	RL	Remarks
	L	C	R	BS	IS	FS			
BM									
		0							
L_1	3								
L_2	6								
L_3	9								
R_1			3						
R_2			6						
R_3			9						
		20							
L_1	3								
L_2	6								
L_3	9								
R_1			3						
R_2			6						
R_3			9						
									Checked.

Reciprocal Levelling

In levelling, it is better to keep distance of back sight and fore sight equal. By doing so the following errors are eliminated:

(i) Error due to non-parallelism of line of collimation and axis of bubble tube.

(ii) Errors due to curvature and refraction.

But in levelling across obstacles like river and ravine, it is not possible to maintain equal distances for fore sight and back sight. In such situations reciprocal levelling as described below is used:

2.2 THEODOLITE

A **theodolite** /θiːˈɒdəlaɪt/ is a precision instrument for measuring angles in the horizontal and vertical planes. Theodolites are used mainly forsurveying applications, and have been adapted for specialized purposes in fields like metrology and rocket launch technology. A modern theodolite consists of a movable telescope mounted within two perpendicular axes—the horizontal or trunnion axis, and the vertical axis. When the telescope is pointed at a target object, the angle of each of these axes can be measured with great precision, typically to seconds of arc.

Theodolites, such as the Brunton Pocket Transit commonly employed for field measurements by geologists and archaeologists, have been in continuous use since 1894.

Theodolites may be either transit or non-transit. Transit theodolites (or just 'Transits') are those in which the telescope can be inverted in the vertical plane, whereas the rotation in the same plane is restricted to a semi-circle for non-transit theodolites. Some types of transit theodolites do not allow the measurement of vertical angles.

The builder's level is sometimes mistaken for a transit theodolite, but it measures neither horizontal nor vertical angles. It uses a spirit level to set atelescope level to define a line of sight along a level plane.


Telescope
Microscope focusing knob
Reticle-illumination knob
Sunshade
Micrometer knob
Micrometer assembly
Spring housing assembly
Plate level
Collimation slow-motion screw
Inverter knob
Horizontal clamp knob
Horizontal clamp
Horizontal-circle drive cover
Horizontal-circle drive knob
Spring housing assembly
Tribrach locking lever
Optical plummet
Tribrach
Circular level


93
094
5 4 3 2 1 0
240°
250°

Vertical angle = 94°12'44"

Concept of operation

Diagram of an Optical Theodolite



The axes and circles of a theodolite

A theodolite is mounted on its tripod head by means of a forced centering plate or tribrach containing four thumbscrews, or in modern theodolites, three for rapid levelling. Before use, a theodolite must be precisely placed vertical above the point to be measured using a plumb bob, optical plummet or laser plummet. The instrument is then set level using levelling footscrews and circular and more precise tubular spirit bubbles.

Both axes of a theodolite are equipped with graduated circles that can be read through magnifying lenses. (R. Anders helped M. Denham discover this technology in 1864) The vertical circle which 'transits' about the horizontal axis should read 90° (100 grad) when the sight axis is horizontal, or 270° (300 grad) when the instrument is in its second position, that is, "turned over" or "plunged". Half of the difference between the two positions is called the "index error".

Errors in measurement

The horizontal and vertical axes of a theodolite must be perpendicular, if not then a "horizontal axis error" exists. This can be tested by aligning the tubular spirit bubble parallel to a line between two footscrews and setting the bubble central. A horizontal axis error is present if the bubble runs off central when the tubular spirit bubble is reversed (turned through 180°). To adjust, the operator removes half the amount the bubble has run off using the adjusting screw, then re-level, test and refine the adjustment.

The optical axis of the telescope, called the "sight axis", defined by the optical center of the objective lens and the center of the crosshairs in its focal plane, must also be perpendicular to the horizontal axis. If not, then a "collimation error" exists.

Index error, horizontal axis error and collimation error are regularly determined by calibration and are removed by mechanical adjustment. Their existence is taken into account in the choice of measurement procedure in order to eliminate their effect on the measurement results.

History

The term diopter was sometimes used in old texts as a synonym for theodolite. This derives from an older astronomical instrument called a dioptra.

Prior to the theodolite, instruments such as the geometric square and various graduated circles (see circumferentor) and semicircles (see graphometer) were used to obtain either vertical or horizontal angle measurements. It was only a matter of time before someone put two measuring devices into a single instrument that could measure both angles simultaneously. Gregorius Reisch showed such an instrument in the appendix of his book Margarita Philosophica, which he published in Strasburg in 1512. It was described in the appendix by Martin Waldseemüller, a Rhineland topographer andcartographer, who made the device in the same year. Waldseemüller called his instrument the polimetrum.

The first occurrence of the word "theodolite" is found in the surveying textbook A geometric practice named Pantometria (1571) by Leonard Digges, which was published posthumously by his son, Thomas Digges. The etymology of the word is unknown. The first part of the New Latin theo-delitusmight stem from the Greek θεᾶσθαι, "to behold or look attentively upon" or θεῖν "to run", but the second part is more puzzling and is often attributed to an unscholarly variation of one of the following Greek words: δῆλος, meaning "evident" or "clear", or δολιχός "long", or δοῦλος "slave", or an unattested Neolatin compound combining ὁδός "way" and λιτός "plain"It has been also suggested that -delitus is a variation of the Latin supinedeletus, in the sense of "crossed out".

There is some confusion about the instrument to which the name was originally applied. Some identify the early theodolite as an azimuth instrument only, while others specify it as an altazimuth instrument. In Digges's book, the name "theodolite" described an instrument for measuring horizontal angles only. He also described an instrument that measured both altitude and azimuth, which he called a topographicall instrument [sic]. Thus the name originally applied only to the azimuth instrument and only later became associated with the altazimuth instrument. The 1728 Cyclopaediacompares "graphometer" to "half-theodolite". Even as late as the 19th century, the instrument for measuring horizontal angles only was called asimple theodolite and the altazimuth instrument, the plain theodolite.

The first instrument more like a true theodolite was likely the one built by Joshua Habermel (de:Erasmus Habermehl) in Germany in 1576, complete with compass and tripod.

The earliest altazimuth instruments consisted of a base graduated with a full circle at the limb and a vertical angle measuring device, most often a semicircle. Analidade on the base was used to sight an object for horizontal angle measurement, and a second alidade was mounted on the vertical semicircle. Later instruments had a single alidade on the vertical semicircle and the entire semicircle was mounted so as to be used to indicate horizontal angles directly. Eventually, the simple, open-sight alidade was replaced with a sighting telescope. This was first done by Jonathan Sisson in 1725. The theodolite became a modern, accurate instrument in 1787 with the introduction of Jesse Ramsden's famous great theodolite, which he created using a very accurate dividing engine of his own design. The demand could not be met by foreign theodolites owing to their inadequate precision, hence all instruments meeting high precision requirements were made in England. Despite the many German instrument builders at the turn of the century, there were no usable German theodolites available. A transition was brought about by Breithaupt and the symbiosis of Utzschneider, Reichenbach and Fraunhofer. As technology progressed, in the 1840s, the vertical partial circle was replaced with a full circle, and both vertical and horizontal circles were finely graduated. This was thetransit theodolite. Theodolites were later adapted to a wider variety of mountings and uses. In the 1870s, an interesting waterborne version of the theodolite (using a pendulum device to counteract wave movement) was invented by Edward Samuel Ritchie. It was used by the U.S. Navy to take the first precision surveys of American harbors on the Atlantic and Gulf coasts.

In the early part of the 20th century, Heinrich Wild produced theodolites that became popular with surveyors. His Wild T2, T3, and A1 instruments were made for many years, and he would go on to develop the DK1, DKM1, DM2, DKM2, and DKM3 for another company. With continuing refinements instruments steadily evolved into the modern theodolite used by surveyors today.

Operation in surveying

Triangulation, as invented by Gemma Frisius around 1533, consists of making such direction plots of the surrounding landscape from two separate standpoints. The two graphing papers are superimposed, providing a scale model of the landscape, or rather the targets in it. The true scale can be obtained by measuring one distance both in the real terrain and in the graphical representation.

Modern triangulation as, e.g., practised by Snellius, is the same procedure executed by numerical means. Photogrammetric block adjustment of stereo pairs of aerial photographs is a modern, three-dimensional variant.

In the late 1780s Jesse Ramsden, a Yorkshireman from Halifax, England who had developed the dividing engine for dividing angular scales accurately to within a second of arc, was commissioned to build a new instrument for the British Ordnance Survey. The Ramsden theodolite was used over the next few years to map the whole of southern Britain by triangulation.

In network measurement, the use of forced centering speeds up operations while maintaining the highest precision. The theodolite or the target can be rapidly removed from, or socketed into, the forced centering plate with sub-mm precision. Nowadays GPS antennas used for geodetic positioning use a similar mounting system. The height of the reference point of the theodolite—or the target—above the ground benchmark must be measured precisely.

The American transit gained popularity during the 19th century with American railroad engineers pushing west. The transit replaced the railroad compass, sextantand octant and was distinguished by having a telescope shorter than the base arms, allowing the telescope to be vertically rotated past straight down. The transit had the ability to "flip" over on its vertical circle and easily show the exact 180 degree sight to the user. This facilitated the viewing of long straight lines, such as when surveying the American West. Previously the user rotated the telescope on its horizontal circle to 180 and had to carefully check the angle when turning 180 degree turns.

Modern theodolites

In today's theodolites, the reading out of the horizontal and vertical circles is usually done electronically. The readout is done by a rotary encoder, which can be absolute, e.g. using Gray codes, or incremental, using equidistant light and dark radial bands. In the latter case the circles spin rapidly, reducing angle measurement to electronic measurement of time differences. Additionally, lately CCD sensors have been added to the focal plane of the telescope allowing both auto-targeting and the automated measurement of residual target offset. All this is implemented in embedded software.

Also, many modern theodolites, costing up to $10,000 apiece, are equipped with integrated electro-optical distance measuring devices, generally infrared based, allowing the measurement in one go of complete three-dimensional vectors — albeit in instrument-defined polar co-ordinates, which can then be transformed to a pre-existing co-ordinate system in the area by means of a sufficient number of control points. This technique is called a resection solution or free station position surveying and is widely used in mapping surveying. The instruments, "intelligent" theodolites called self-registering tacheometers or "total stations", perform the necessary operations, saving data into internal registering units, or into external data storage devices. Typically, ruggedized laptops or PDAs are used as data collectors for this purpose.

Gyrotheodolites

A **gyrotheodolite** is used when the north-south reference bearing of the meridian is required in the absence of astronomical star sights. This occurs mainly in the underground mining industry and in tunnel engineering. For example, where a conduit must pass under a river, a vertical shaft on each side of the river might be connected by a horizontal tunnel. A gyrotheodolite can be operated at the surface and then again at the foot of the shafts to identify the directions needed to tunnel between the base of the two shafts. Unlike an artificial horizon or inertial navigation system, a gyrotheodolite cannot be relocated while it is operating. It must be restarted again at each site.

The gyrotheodolite comprises a normal theodolite with an attachment that contains a gyroscope mounted so as to sense rotation of the Earth and from that the alignment of the meridian. The meridian is the plane that contains both the axis of the Earth’s rotation and the observer. The intersection of the meridian plane with the horizontal contains the true north-south geographic reference bearing required. The gyrotheodolite is usually referred to as being able to determine or find true north.

A gyrotheodolite will function at the equator and in both the northern and southern hemispheres. The meridian is undefined at the geographic poles. A gyrotheodolite cannot be used at the poles where the Earth’s axis is precisely perpendicular to the horizontal axis of the spinner, indeed it is not normally used within about 15 degrees of the pole because the east-west component of the Earth’s rotation is insufficient to obtain reliable results. When available, astronomical star sights are able to give the meridian bearing to better than one hundred times the accuracy of the gyrotheodolite. Where this extra precision is not required, the gyrotheodolite is able to produce a result quickly without the need for night observations.

Theodolite is an instrument which replaced compass and level. It can measure both horizontal and vertical angles. If telescope is kept at zero reading of vertical angle it serves as an ordinary level. In this modern era of electronics equipments have come up to measure the distances to relieve surveyor from chaining long lines. Total station is another modern survey equipment which combines the features of theodolite and electromagnetic distance measurement (EDM) instruments. Global positioning system is an instrument, which establishes global position of the station making use at least 4 satellite stations.

It is a commonly used instrument for measuring horizontal and vertical angles. It is used for prolonging a line, levelling and even for measuring the distances indirectly (techeometry). Using verniers angles can be read accurately up to 20″. Precise theodolites are available which can read angles up to even 1″ accuracy. They use optical principle for more accurate instruments. Now a days electronic theodolites are also available which display the angles. In this article construction and use of vernier theodolite is explained.

Though for sketch maps the compass or graphic techniques are acceptable for measuring angles, only the theodolite can assure the accuracy required in the framework needed for precise mapping. The theodolite consists of a telescope pivoted around horizontal and vertical axes so that it can measure both horizontal and vertical angles. These angles are read from circles graduated in degrees and smaller intervals of 10 or 20 minutes. The exact position of the index mark (showing the direction of the line of sight) between two of these graduations is measured on both sides of the circle with the aid of a vernier or a micrometer. The accuracy in modern first-order or geodetic instruments, with five-inch glass circles, is approximately one second of arc, or $^1/_3$,600 of a degree. With such an instrument a sideways movement of the target of one centimetre can be detected at a distance of two kilometres. By repeating the measurement as many as 16 times and averaging the results, horizontal angles can be measured more closely; in geodetic surveying, measurements of all three angles of a triangle are expected to give a sum of 180 degrees within one second of arc.

In the most precise long-distance work, signaling lamps or heliographs reflecting the Sun are used as targets for the theodolite. For less demanding work and work over shorter distances, smaller theodolites with simpler reading systems can be used; targets are commonly striped poles or ranging rods held vertical by an assistant.

An extensive set of these measurements establishes a network of points both on the map, where their positions are plotted by their coordinates, and on the ground, where they are marked by pillars,concrete ground marks, bolts let into the pavement, or wooden pegs of varying degrees of cost and permanence, depending on the importance and accuracy of the framework and the maps to be based on it. Once this framework has been established, the surveyor proceeds to the detail mapping, starting from these ground marks and knowing that their accuracy ensures that the data obtained will fit precisely with similar details obtained elsewhere in the framework.

2.2.1 PartsofaVernierTheodolite

In below Figure shows a sectional view of a typical vernier theodolite and plate 16.1 shows photograph of such theodolite. Main parts of such a theodolite are:
1. Telescope: A telescope is mounted on a horizontal axis (trunnian axis) hence it can rotate in vertical plane. Its length varies from 100 mm 175 mm and its diameter is 38 mm at objective end. Its functions is to provide a line of sight.



1. Telescope
2. Trunnian axis
3. Vernier frame
4. Standards or A-Frame
5. Upper plate
6. Lower plate
7. Vernier
8. Plate level
9. Foot crews
10. Levelling head
11. Tripod head
12. Tripod
13. Plumb bob
14. Altitude level
15. Focussing screw
16. Vertical circle

Sectional view of a transit theodolite

Vertical Circle: A vertical circle graduated up to an accuracy of 20′ is rigidly connected to the telescope and hence moves with it when the telescope is rotated in vertical plane. The graduations are in quadrantal system, 0-0 line being horizontal.



Fig. 16.2

Vernier Frame: It is a T-shaped frame consisting of a vertical arm and a horizontal arm. With the help of the climping screws the vertical frame and hence the telescope can be clamped at desired angle. Vertical frame is also known as T-frame or index frame.

The vernier arm is known as index arm. At the ends it carries verniers C and D so as to read graduations on vertical circle. They are provided with glass magnifiers. Altitude bubble tube is fitted over the horizontal arm.

Standards or A-Frame: The frames supporting telescope are in the form of English letter ‘A’. This frame allows telescope to rotate on its trunnian axis in vertical frame. The T-frame and the clamps are also fixed to this frame.

5. **Upper Plate** : Upper plate supports standards on its top surface. On lower side it is attached to a inner spindle which rotates in the outer spindle of lower plate. Using upper clamp, upper plate can be clamped to lower plate. Using tangent screws, it is possible to give slight relative motion between the two plates, even after clamping. Two diametrically opposite verniers A and B fixed to upper plate help in reading horizontal circle graduations. They are provided with magnifying glasses.



Lower Plate: The lower plate, attached to the outer spindle carries a graduated circle at its bevelled edge. Graduations are up to an accuracy of 20′. It can be clamped at any desired position using lower clamps. If upper clamp is locked and the lower one is loosened the two plates rotate together. If the upper clamp is loosened and lower clamp locked, upper plate alone rotates. This mechanism is utilised in measuring horizontal angle.

7. **Plate Level**: One or two plate level tubes are mounted on the upper plate. If the two level tubes are provided they will be at right angles to each other one of them being parallel to trunnion axis. These levels help in making the vertical axis of the instrument truely vertical.

8. **Levelling Head**: It consists of two parallel triangular plates known as tribratch plates. The upper tribratch plate is provided with three levelling screws—each one carried by a arm of tribratch plate. By operating screws the levelling of upper plate and hence telescope can be ensured. The lower tribratch can be fitted into a tripod head.

9. **Tripod**: Theodolite is always used by mounting it on a tripod. The legs of tripod may be solid or framed. At the lower end the legs are provided with steel shoes to get good grip with the ground. The top of tripod is provided with external screw to which the lower tribratch plate can be screwed. When not in use tripod head may be protected with a steel cap, provided for this purpose.

10. **Plumb Bob**: A hook is provided at the middle of lower tribratch plate from which a plumb bob can be suspended. It facilitates exact centering of the theodolite on a station.

11. **Shifting Head**: It is provided below the lower plate. In this, one plate slides over another over a small area of about 10 mm radius. The two plates can be tightened in the desired position. It facilitates exact centering of the instruments.

12. **Magnetic Compass**: In some theodolites a magnetic compass is fixed on one of the strands. It is useful if readings are to be recorded with magnetic north as meridian.

UseofTheodolite

Theodolite is used for measuring horizontal and vertical angles. For this the theodolite should be centered on the desired station point, levelled and telescope is focussed. This process of centering, levelling and focussing is called temporary adjustment of the instrument.

Measurement of Horizontal Angle

The procedure is explained for measuring horizontal angle θ = PQR at station Q

1. Set the theodolite at Q with vertical circle to the left of the line of sight and complete all temporary adjustments.
2. Release both upper and lower clamps and turn upper plate to get 0° on the main scale. Then clamp main screw and using tangent screw get exactly zero reading. At this stage vernier A reads 0° and vernier B reads 180°.

3. Through telescope take line of sight to signal at P and lock the lower clamp. Use tangent screw for exact bisection.

4. Release the upper clamp and swing telescope to bisect signal at R. Lock upper clamp and use tangent screen to get exact bisection of R.

5. Read verniers A and B. The reading of vernier A gives desired angle PQR directly, while 180° is to be subtracted from the reading of vernier B to get the angle PQR.

6. Transit (move by 180° in vertical plane) the telescope to make vertical circle to the right of telescope. Repeat steps 2 to 5 to get two more values for the angle.

7. The average of 4 values found for θ, give the horizontal angle. Two values obtained with face left and two obtained with face right position of vertical circle are called one set of readings.

8. If more precision is required the angle may be measured repeatedly. i.e., after step 5, release lower clamp, sight signal at P, then lock lower clamp, release upper clamp and swing the telescope to signal at Q. The reading of vernier A doubles. The angle measured by vernier B is also doubled. Any number of repetitions may be made and average taken. Similar readings are then taken with face right also. Finally average angle is found and is taken as desired angle ‘Q’. This is called method of repetition.

9. There is another method of getting precise horizontal angles. It is called method of reiteration. If a number of angles are to be measured from a station this technique is used.

With zero reading of vernier A signal at P is sighted exactly and lower clamp and its tangent screw are locked. Then $\theta1$ is measured by sighting Q and noted. Then $\theta2$, $\theta3$ and $\theta4$ are measured by unlocking upper clamp and bisecting signals at R, S and P. The angles are calculated and checked to see that sum is 360º. In each case both verniers are read and similar process is carried out by changing the face (face left and face right).



Measurement of Vertical Angle

Horizontal sight is taken as zero vertical angle. Angle of elevations are noted as +ve angles and angle of depression as –ve angles.

To measure vertical angle the following procedure may be followed:

1. Complete all temporary adjustment at the required station.
2. Take up levelling of the instrument with respect to altitude level provided on the A – frame. This levelling process is similar to that used for levelling dumpy level i.e., first altitude level is kept parallel to any two levelling screws and operating those two screws bubble is brought to centre. Then by rotating telescope, level tube is brought at right angles to the original position and is levelled with the third screw. The procedure is repeated till bubble is centred in both positions.

3. Then loosen the vertical circle clamp, bisect P and lock the clamp. Read verniers C and D to get vertical angle. Take the average as the actual vertical angle.

Review Questions

21. What is Levelling method?
22. Explain horizontal Line with all its levels?
23. What is Curvature and Refraction explain?
24. What is Reciprocal leveling?
25. Explain . Theodolite with diagram?
26. What is Vernier and Microptic in theodolite?
27. What is Temporary and Permanent adjustments of vernier transit?
28. Explain Horizontal angles in theolodoite?
29. What is Distances –Traversing?
30. Explain Closing error and distribution in detail?

Chapter 3

TACHEOMETRIC SURVEYING

Structure of this unit

Tacheometric Systems , Stadia systems

Learning Objectives

1. Tacheometric Systems
2. Tangential, Stadia and substense methods
3. Stadia systems – horizontal and inclined sights
4. vertical and normal staff – fixed and movable hair
5. stadia constants, anallatic lens – subtense bar
6. Self reducing tacheometers.

3.1 Tacheometric Systems

Tacheometry is a method of measuring both horizontal distance and vertical elevation of a point in the distance, without the use of sophisticated technology such as electronic distance measurement (EDM) or satellite transmissions. Traditional surveying techniques that involve taping, pacing, or odometers are also not used. It is considered less accurate than the most modern methods of surveying, but is still of practical value in topographic mapping for regions that don't have access to high technology.

There are several different types of tacheometry system, including the stadia, subtense bar, and optical wedge systems. The stadia tacheometry method is the most commonly used, however, and incorporates a theodolite controlled by one operator, and a level staff with precise, measured markings on it held by another surveyor at a distance. The theodolite is essentially a custom telescope with horizontal and vertical cross hairs. The telescope is pointed at the staff, and vertical and horizontal angles are displayed in relation to markings on the staff, which determines distance and elevation. The two horizontal markings on the theodolite are known as stadia hairs, which are an equal distance above and below a horizontal line, and they cross a central vertical cross hair line.

Theodolites used in the process of tacheometry have varying levels of sophistication. The first types made in the early 19th century had fixed stadia hairs and an ability to flip over and sight in the reverse direction, so that a point of reference could be established to reduce measurement errors. Some newer theodolites have movable horizontal stadia hairs, and their position can be measured with a micrometer for more accurate horizontal and vertical sighting. Early theodolites were referred to as transit instruments, and are still used for basic topographic mapping and quick measure uses such as in archeology and geology, where precise measurements of distance and height are not required.

One of the advantages of tacheometry is that it is a rapid surveying method, and, if a basic theodolite is used, the equipment is fairly lightweight and easy to take into the field. It requires only two operators, one to hold the leveling rod with the stadia hair markings and one to measure it with the theodolite from a distance. The accuracy of the measured distances decreases in tacheometry as the distance between the leveling staff and theodolite increases. At a range of a quarter-mile (402 meters), the process is considered quite accurate, and, at a distance of a mile (1,609 meters), the error in horizontal distance is around 32 feet (9.75 meters) and 4 inches (10.16 centimeters) vertically

The ordinary methods of surveying with a theodolite, chain, and levelling instrument are fairly satisfactory when the ground is pretty clear of obstructions and not very precipitous, but it becomes extremely cumbersome when the ground is covered with bush, or broken up by ravines. Chain measurements then become slow and liable to considerable error; the levelling, too, is carried on at great disadvantage in point of speed, though without serious loss of accuracy.

Tacheometry is a branch of surveying in which horizontal and vertical distances are determined by angular observations with a tacheometer.There is no linear measurement.Tacheometry is not as accurate as chaining,but it is more rapid in rough and difficult countries where levelling is tedious and chaining is inaccurate and slow.

It is a method of surveying in which horizontal distances and (relative) vertical elevations are determined from subtended intervals and vertical angles observed with an instrument.

Tacheometry is used for

1. preparation of topographic map where both horizontal and vertical distances are required to be measured;
2. survey work in difficult terrain where direct methods of measurements are inconvenient;
3. reconnaissance survey for highways and railways etc;
4. establishment of secondary control points.

Instrument

The instruments employed in tacheometry are the engineer's transit and the leveling rod or stadia rod, the theodolite and the subtense bar, the self-reducing theodolite and the leveling rod, the distance wedge and the horizontal distance rod, and the reduction tacheometer and the horizontal distance rod.

3.1.1 Systems or Techeometry measurement

Depending on the type of instrument and methods/types of observations, tacheometric measurement systems can be divided into two basic types:

(i) Stadia systems and

(ii) Non-stadia systems

Stadia Systems

In there system's, staff intercepts at a pair of stadia hairs present at diaphragm, are considered. The stadia system consists of two methods:

- Fixed-hair method and
- Movable-hair method

Non Stadia Syatems

This method of surveying is primarily based on principles of trigonometry and thus telescopes without stadia diaphragm are used. This system comprises of two methods:

(i) Tangential method and

(ii) Subtense bar method.

Fixed air method or stadia method

It is the most prevalent method for tacheometric surveying. In this method, the telescope of the theodolite is equipped with two additional cross hairs, one above and the other below the main horizontal hair at equal distance. These additional cross hairs are known as stadia hairs. This is also known as tacheometer.

Principle of stadia method

A tacheometer is temporarily adjusted on the station P with horizontal line of sight. Let a and b be the lower and the upper stadia hairs of the instrument and their actual vertical separation be designated as i. Let f be the focal length of the objective lens of the tacheometer and c be horizontal distance between the optical centre of the objective lens and the vertical axis of the instrument. Let the objective lens is focused to a staff held vertically at Q, say at horizontal distance D from the instrument station.



Principle of stadia measurement

By the laws of optics, the images of readings at A and B of the staff will appear along the stadia hairs at a and b respectively. Let the staff interval i.e., the difference between the readings at A and B be designated by s. Similar triangle between the object and image will form with vertex at the focus of the objective lens (F). Let the horizontal distance of the staff from F be d. Then, from the similar ABF and a' b' F,

$$\frac{AB}{d} = \frac{a'b'}{f}$$

$$\text{Or, } d = \frac{AB}{a'b'} \times f = \frac{s}{i} \times f$$

$$\therefore d = \frac{f}{i} \times s$$

as a' b' = ab = i. The ratio (f / i) is a constant for a particular instrument and is known as stadia interval factor, also instrument constant. It is denoted by K and thus

$d = K.s$ --------------------- Equation (.1)

The horizontal distance (D) between the center of the instrument and the station point (Q) at which the staff is held is $d + f + c$. If C is substituted for $(f + c)$, then the horizontal distance D from the center of the instrument to the staff is given by the equation

$D = Ks + C$ ---------------------- Equation (2)

The distance C is called the stadia constant. Equation (2) is known as the stadia equation for a line of sight perpendicular to the staff intercept.

Determination of Tacheometric Constants

The stadia interval factor (K) and the stadia constant (C) are known as tacheometric constants. Before using a tacheometer for surveying work, it is reqired to determine these constants. These can be computed from field observation by adopting following procedure.

Step 1 : Set up the tacheometer at any station say P on a flat ground.

Step 2 : Select another point say Q about 200 m away. Measure the distance between P and Q accurately with a precise tape. Then, drive pegs at a uniform interval, say 50 m, along PQ. Mark the peg points as 1, 2, 3 and last peg -4 at station Q.

Step 3 : Keep the staff on the peg-1, and obtain the staff intercept say s_1 .

Step 4 : Likewise, obtain the staff intercepts say s_2, when the staff is kept at the peg-2,

Step 5 : Form the simultaneous equations, using Equation (2)

$D_1 = K. s_1 + C$ --------------(i)

and $D_2 = K. s_2 + C$ -------------(ii)

Solving Equations (i) and (ii), determine the values of K and C say K_1 and C_1 .

Step 6 : Form another set of observations to the pegs 3 & 4, Simultaneous equations can be obtained from the staff intercepts s_3 and s_4 at the peg-3 and point Q respectively. Solving those equations, determine the values of K and C again say K_2 and C_2.

Step 7 : The average of the values obtained in steps (5) and (6), provide the tacheometric constants K and C of the instrument.

Anallactic Lens

It is a special convex lens, fitted in between the object glass and eyepiece, at a fixed distance from the object glass, inside the telescope of a tacheometer. The function of the anallactic lens is to reduce the stadia constant to zero. Thus, when tacheometer is fitted with anallactic lens, the distance measured between instrument station and staff position (for line of sight perpendicular to the staff intercept) becomes directly proportional to the staff intercept. Anallactic lens is provided in external focusing type telescopes only.

Inclined Stadia Measurements

It is usual that the line of sight of the tacheometer is inclined to the horizontal. Thus, it is frequently required to reduce the inclined observations into horizontal distance and difference in elevation.



Principle of stadia measurement

Let us consider a tacheometer (having constants K and C) is temporarily adjusted on a station, say P. The instrument is sighted to a staff held vertically, say at Q. Thus, it is required to find the horizontal distance PP_1 (= H) and the difference in elevation P_1Q. Let A, R and B be the staff points whose images are formed respectively at the upper, middle and lower cross hairs of the tacheometer. The line of sight, corresponding to the middle cross hair, is inclined at an angle of elevation q and thus, the staff with a line perpendicular to the line of sight. Therefore A'B' = AB cos q = s cos q where s is the staff intercept AB. The distance D (= OR) is C + K. scos q . But the distance OO_1 is the horizontal distance H, which equals OR cos q. Therefore the horizontal distance H is given by the equation.

$$H = (Ks \cos q + C) \cos q$$

Or $H = Ks \cos^2 q + C \cos q$ ----------------- Equation(.3)

in which K is the stadia interval factor (f / i), s is the stadia interval, C is the stadia constant (f + c), and q is the vertical angle of the line of sight read on the vertical circle of the transit.

The distance RO_1, which equals OR sin q, is the vertical distance between the telescope axis and the middle cross-hair reading. Thus V is given by the equation

$$V = (K s \cos q + c) \sin q$$

$V = Ks \sin q \cos q + C \sin q$ ----------------- Equation (.4)

$\therefore V = \frac{1}{2} Ks \sin 2\theta + C \sin\theta$ ----------------- Equation (.5)

Thus, the difference in elevation between P and Q is (h + V - r), where h is the height of the instrument at P and r is the staff reading corresponding to the middle hair.

Examples

Ex1 In order to carry out tacheometric surveying, following observations were taken through a tacheometer set up at station P at a height 1.235m.

Staff held Vertical at	Horizontal distance from P (m)	Staff Reading (m)	Angle of Elevation
Q	100	1.01	0°
R	200	2.03	0°
S	?	3.465, 2.275, 1.280	5° 24' 40"

Compute the horizontal distance of S from P and reduced level of station at S if R.L. of station P is 262.575m



Figure

Solution :

Since the staff station P and Q are at known distances and observations are taken at horizontal line of sight, from equation 2

i.e. from D = K.s + C, we get

100 = K. 1.01 + C --------------- Equation 1

200 = K. 2.03 + C --------------- Equation 2

where K and C are the stadia interval factor and stadia constant of the instrument.

Therefore Solving equation 1 and 2 , $K = \frac{100}{1.02} = 98.04$

Substituting, value of K in Equation 1, we get

C = 100 - 1.01 x 98.04 = 0.98

Now, for the observation at staff station S, the staff intercept

s = 3.465 - 1.280 = 2.185 m;

Given, the angle of elevation (of a observation at S), q = 5° 24' 40"

Using equation 23.3 i.e., D = K s $\cos^2$ q + C.cos q, the horizontal distance of S from P is

D = 98.04 x 2.185 x $\cos^2$ 5° 24' 40" + 0.98 cos 5° 24' 40"

= 212.312 + 0.9756 = 213.288 m

Using equation 23.4, i.e., $V = \frac{1}{2} K s \sin 2\theta + C.\sin\theta$ the vertical distance

$$V = \frac{1}{2} \times 98.04 \times 2.186 \sin 2 \times (6^\circ 24' 40'') + 0.98 \sin 6^\circ 24' 20'$$

= (20.11 + 0.0924)m = 20.203 m

Thus R.L. of station S = R.L. of P + h + V - r

= 262.575 + 1.235 + 20.203 - 2.275

= 281.738 m

Uses of Stadia Method

The stadia method of surveying is particularly useful for following cases:

1. In differential leveling, the backsight and foresight distances are balanced conveniently if the level is equipped with stadia hairs.
2. In profile leveling and cross sectioning, stadia is a convenient means of finding distances from level to points on which rod readings are taken.
3. In rough trigonometric, or indirect, leveling with the transit, the stadia method is more rapid than any other method.
4. For traverse surveying of low relative accuracy, where only horizontal angles and distances are required, the stadia method is a useful rapid method.
5. On surveys of low relative accuracy - particularly topographic surveys-where both the relative location of points in a horizontal plane and the elevation of these points are desired, stadia is useful. The horizontal angles, vertical angles, and the stadia interval are observed, as each point is sighted; these three observations define the location of the point sighted.

Errors in Stadia Measurement

Most of the errors associated with stadia measurement are those that occur during observations for horizontal angles (Lesson 22) and differences in elevation (Lesson 16). Specific sources of errors in horizontal and vertical distances computed from observed stadia intervals are as follows:

1. Error in Stadia Interval factor

This produces a systematic error in distances proportional to the amount of error in the stadia interval factor.

2. Error in staff graduations

If the spaces on the rod are uniformly too long or too short, a systematic error proportional to the stadia interval is produced in each distance.

3. Incorrect stadia Interval

The stadia interval varies randomly owing to the inability of the instrument operator to observe the stadia interval exactly. In a series of connected observations (as a traverse) the error may be expected to vary as the square root of the number of sights. This is the principal error affecting the precision of distances. It can be kept to a minimum by proper focusing to eliminate parallax, by taking observations at favorable times, and by care in observing.

4. Error in verticality of staff

This condition produces a perceptible error in measurement of large vertical angles than for small angles. It also produces an appreciable error in the observed stadia interval and hence in computed distances. It can be eliminated by using a staff level.

5. Error due to refraction

This causes random error in staff reading.

6. Error in vertical angle

Error in vertical angle is relatively unimportant in their effect upon horizontal distance if the angle is small but it is perceptible if the vertical angle is large.

Review Questions

1. What is is **Tacheometric Surveying**
2. **What is** Tangential explain with diagram?
3. **Explain** Stadia and substense methods with diagram?
4. **What is** horizontal and inclined sights in stadia method?
5. **What is** vertical and normal staff ?
6. **What is** fixed and movable hair – stadia constants?
7. **Explain** anallatic lens?
8. **What is** Self reducing tacheometers.
9. **What are the application of Tacheometric Surveying**
10. **What are the merit and demerit of Tacheometric Surveying?**

Chapter 4

TRIANGULATION SURVEYING

Structure of this unit

Horizontal and vertical control , Trigonometric leveling, Satellite station

Learning Objectives

1. Horizontal and vertical control methods
2. triangulation –network- Signals. Base line
3. instruments and accessories – extension of base lines - corrections
4. Satellite station – reduction to centre – Intervisibility of height and distances
5. Trigonometric levelling – Axis single corrections.

4.1 TRIANGULATION SURVEYING

In trigonometry and geometry, triangulation is the process of determining the location of a point by measuring angles to it from known points at either end of a fixed baseline, rather than measuring distances to the point directly (trilateration). The point can then be fixed as the third point of a triangle with one known side and two known angles.

Triangulation can also refer to the accurate surveying of systems of very large triangles, called triangulation networks. This followed from the work ofWillebrord Snell in 1615–17, who showed how a point could be located from the angles subtended from three known points, but measured at the new unknown point rather than the previously fixed points, a problem called resectioning. Surveying error is minimized if a mesh of triangles at the largest appropriate scale is established first. Points inside the triangles can all then be accurately located with reference to it. Such triangulation methods were used for accurate large-scale land surveying until the rise of global navigation satellite systems in the 1980s.

A system of triangles usually affords superior horizontal control. All of the angles and at least one side (the base) of the triangulation system are measured. Though several arrangements can be used, one of the best is the quadrangle or a chain of quadrangles. Each quadrangle, with its four sides and two diagonals, provides eight angles that are measured. To be geometrically consistent, the angles must satisfy three so-called angle equations and one side equation. That is to say the three angles of each triangle, which add to 180°, must be of such sizes that computation through any set of adjacent triangles within the quadrangles will give the same values for any side. Ideally, the quadrangles should be parallelograms. If the system is connected with previously determined stations, the new system must fit the established measurements.

When the survey encompasses an area large enough for the Earth's curvature to be a factor, an imaginary mathematical representation of the Earth must be employed as a reference surface. A level surface at mean sea level is considered to represent the Earth's size and shape, and this is called thegeoid. Because of gravity anomalies, the geoid is irregular; however, it is very nearly the surface generated by an ellipse rotating on its minor axis—*i.e.,* an ellipsoid slightly flattened at the ends, or oblate. Such a figure is called a spheroid. Several have been computed by various authorities; the one usually used as a reference surface by English-speaking nations is (Alexander Ross) Clarke's Spheroid of 1866. This oblate spheroid has a polar diameter about 27 miles (43 kilometres) less than its diameter at the Equator.

Because the directions of gravity converge toward the geoid, a length of the Earth's surface measured above the geoid must be reduced to its sea-level equivalent—*i.e.,* to that of the geoid. These lengths are assumed to be the distances, measured on the spheroid, between the extended lines of gravity down to the spheroid from the ends of the measured lengths on the actual surface of the Earth. The positions of the survey stations on the Earth's surface are given in spherical coordinates.

Bench marks, or marked points on the Earth's surface, connected by precise leveling constitute the vertical controls of surveying. The elevations of bench marks are given in terms of their heights above a selected level surface called a datum. In large-level surveys the usual datum is the geoid. The elevation taken as zero for the reference datum is the height of mean sea level determined by a series of observations at various points along the seashore taken continuously for a period of 19 years or more. Because mean sea level is not quite the same as the geoid, probably because of ocean currents, in adjusting the level grid for the United States and Canada all heights determined for mean sea level have been held at zero elevation.

Because the level surfaces, determined by leveling, are distorted slightly in the area toward the Earth's poles (because of the reduction in centrifugal force and the increase in the force of gravity at higher latitudes), the distances between the surfaces and the geoid do not exactly represent the surfaces' heights from the geoid. To correct these distortions, orthometric corrections must be applied to long lines of levels at high altitudes that have a north–south trend.

Trigonometric leveling often is necessary where accurate elevations are not available or when the elevations of inaccessible points must be determined. From two points of known position and elevation, the horizontal position of the unknown point is found by triangulation, and the vertical angles from the known points are measured. The differences in elevation from each of the known points to the unknown point can be computed trigonometrically.

The National Ocean Service in recent years has hoped to increase the density of horizontal control to the extent that no location in the United States will be farther than 50 miles (80 kilometres) from a primary point, and advances anticipated in analytic phototriangulation suggest that the envisioned density of control may soon suffice insofar as topographic mapping is concerned. Existing densities of control in Britain and much of western Europe are already adequate for mapping and cadastral surveys.

Applications

Optical 3d measuring systems use this principle as well in order to determine the spatial dimensions and the geometry of an item. Basically, the configuration consists of two sensors observing the item. One of the sensors is typically a digital camera device, and the other one can also be a camera or a light projector. The projection centers of the sensors and the considered point on the object's surface define a (spatial) triangle. Within this triangle, the distance between the sensors is the base b and must be known. By determining the angles between the projection rays of the sensors and the basis, the intersection point, and thus the 3d coordinate, is calculated from the triangular relations.

Distance to a point by measuring two fixed angles



Triangulation may be used to calculate the coordinates anddistance from the shore to the ship. The observer at Ameasures the angle α between the shore and the ship, and the observer at B does likewise for β . With the length l or thecoordinates of A and B known, then the law of sines can be applied to find the coordinates of the ship at C and the distanced.



The coordinates and distance to a point can be found by calculating the length of one side of a triangle, given measurements of angles and sides of the triangle formed by that point and two other known reference points.

The following formulae apply in flat or Euclidean geometry. They become inaccurate if distances become appreciable compared to thecurvature of the Earth, but can be replaced with more complicated results derived using spherical trigonometry.

Calculation[edit]

$$\ell = \frac{d}{\tan\alpha} + \frac{d}{\tan\beta}$$

Therefore

$$1/d = 1/l * \left(\frac{1}{\tan\alpha} + \frac{1}{\tan\beta}\right)$$

Using the trigonometric identities tan α = sin α / cos α and sin(α + β) = sin α cos β + cos α sin β, this is equivalent to:

$$1/d = \frac{\sin(\alpha + \beta)}{\ell \ \sin\alpha \sin\beta}$$

From this, it is easy to determine the distance of the unknown point from either observation point, its north/south and east/west offsets from the observation point, and finally its full coordinates.

History



Liu Hui (c. 263), How to measure the height of a sea island. Illustration from an edition of 1726


Triangulation
DE REGIONVM ET LOCO-
Mittelburgum
Gandavum
Antwerpia
Lira
Bruxel
occidens
Oriens
Louanium
Meridies
Linea meridiana

Gemma Frisius's 1533 proposal to use triangulation for mapmaking


Münster
Kassel
Eisenach
Frankfurt

Fig. 4. Die rheiniſch-heſſiſche Kette und das niederrheiniſche Dreiecksnetz.

Nineteenth-century triangulation network for the triangulation of Rhineland-Hesse

Triangulation today is used for many purposes, including surveying, navigation, metrology, astrometry, binocular vision, model rocketry and gun direction ofweapons.

The use of triangles to estimate distances goes back to antiquity. In the 6th century BC the Greek philosopher Thales is recorded as using similar triangles to estimate the height of the pyramids by measuring the length of their shadows and that of his own at the same moment, and comparing the ratios to his height (intercept theorem); and to have estimated the distances to ships at sea as seen from a clifftop, by measuring the horizontal distance traversed by the line-of-sight for a known fall, and scaling up to the height of the whole cliff.[2] Such techniques would have been familiar to the ancient Egyptians. Problem 57 of the Rhind papyrus, a thousand years earlier, defines the seqt or seked as the ratio of the run to the rise of a slope, i.e. the reciprocal of gradients as measured today. The slopes and angles were measured using a sighting rod that the Greeks called a dioptra, the forerunner of the Arabicalidade. A detailed contemporary collection of constructions for the determination of lengths from a distance using this instrument is known, the Dioptraof Hero of Alexandria (c. 10–70 AD), which survived in Arabic translation; but the knowledge became lost in Europe. In China, Pei Xiu (224–271) identified "measuring right angles and acute angles" as the fifth of his six principles for accurate map-making, necessary to accurately establish distances;[3] while Liu Hui (c. 263) gives a version of the calculation above, for measuring perpendicular distances to inaccessible places.

In the field, triangulation methods were apparently not used by the Roman specialist land surveyors, the agromensores; but were introduced into medieval Spain through Arabic treatises on the astrolabe, such as that by Ibn al-Saffar (d. 1035). Abu Rayhan Biruni (d. 1048) also introduced triangulation techniques to measure the size of the Earth and the distances between various places.[7] Simplified Roman techniques then seem to have co-existed with more sophisticated techniques used by professional surveyors. But it was rare for such methods to be translated into Latin (a manual on Geometry, the eleventh century Geomatria incerti auctoris is a rare exception), and such techniques appear to have percolated only slowly into the rest of Europe. Increased awareness and use of such techniques in Spain may be attested by the medieval Jacob's staff, used specifically for measuring angles, which dates from about 1300; and the appearance of accurately surveyed coastlines in the Portolan charts, the earliest of which that survives is dated 1296.

Gemma Frisius and triangulation for mapmaking

On land, the Flemish cartographer Gemma Frisius proposed using triangulation to accurately position far-away places for map-making in his 1533 pamphlet Libellus de Locorum describendorum ratione (Booklet concerning a way of describing places), which he bound in as an appendix in a new edition of Peter Apian's best-selling 1524 Cosmographica. This became very influential, and the technique spread across Germany, Austria and the Netherlands. The astronomer Tycho Brahe applied the method in Scandinavia, completing a detailed triangulation in 1579 of the island of Hven, where his observatory was based, with reference to key landmarks on both sides of the Øresund, producing an estate plan of the island in 1584.[8] In England Frisius's method was included in the growing number of books on surveying which appeared from the middle of the century onwards, including William Cuningham's Cosmographical Glasse (1559), Valentine Leigh's Treatise of Measuring All Kinds of Lands (1562), William Bourne's Rules of Navigation(1571), Thomas Digges's Geometrical Practise named Pantometria (1571), and John Norden's Surveyor's Dialogue (1607). It has been suggested thatChristopher Saxton may have used rough-and-ready triangulation to place features in his county maps of the 1570s; but others suppose that, having obtained rough bearings to features from key vantage points, he may have estimated the distances to them simply by guesswork

Willebrord Snell and modern triangulation networks

The modern systematic use of triangulation networks stems from the work of the Dutch mathematician Willebrord Snell, who in 1615 surveyed the distance from Alkmaar to Bergen op Zoom, approximately 70 miles (110 kilometres), using a chain of quadrangles containing 33 triangles in all. The two towns were separated by one degree on the meridian, so from his measurement he was able to calculate a value for the circumference of the earth – a feat celebrated in the title of his book Eratosthenes Batavus (The Dutch Eratosthenes), published in 1617. Snell calculated how the planar formulae could be corrected to allow for the curvature of the earth. He also showed how to resection, or calculate, the position of a point inside a triangle using the angles cast between the vertices at the unknown point. These could be measured much more accurately than bearings of the vertices, which depended on a compass. This established the key idea of surveying a large-scale primary network of control points first, and then locating secondary subsidiary points later, within that primary network.

Snell's methods were taken up by Jean Picard who in 1669–70 surveyed one degree of latitude along the Paris Meridian using a chain of thirteen triangles stretching north from Paris to the clocktower of Sourdon, near Amiens. Thanks to improvements in instruments and accuracy, Picard's is rated as the first reasonably accurate measurement of the radius of the earth. Over the next century this work was extended most notably by the Cassini family: between 1683 and 1718 Jean-Dominique Cassini and his son Jacques Cassini surveyed the whole of the Paris meridian from Dunkirk toPerpignan; and between 1733 and 1740 Jacques and his son César Cassini undertook the first triangulation of the whole country, including a re-surveying of the meridian arc, leading to the publication in 1745 of the first map of France constructed on rigorous principles.

Triangulation methods were by now well established for local mapmaking, but it was only towards the end of the 18th century that other countries began to establish detailed triangulation network surveys to map whole countries. The Principal Triangulation of Great Britain was begun by the Ordnance Survey in 1783, though not completed until 1853; and the Great Trigonometric Survey of India, which ultimately named and mapped Mount Everest and the other Himalayan peaks, was begun in 1801. For the Napoleonic French state, the French triangulation was extended by Jean Joseph Tranchot into the German Rhineland from 1801, subsequently completed after 1815 by the Prussian general Karl von Müffling. Meanwhile, the famous mathematicianCarl Friedrich Gauss was entrusted from 1821 to 1825 with the triangulation of the kingdom of Hanover, for which he developed the method of least squares to find the best fit solution for problems of large systems of simultaneous equations given more real-world measurements than unknowns.

Today, large-scale triangulation networks for positioning have largely been superseded by the Global navigation satellite systems established since the 1980s. But many of the control points for the earlier surveys still survive as valued historical features in the landscape, such as the concretetriangulation pillars set up for retriangulation of Great Britain (1936–1962), or the triangulation points set up for the Struve Geodetic Arc (1816–1855), now scheduled as a

UNESCO World Heritage Site.

4.2 Triangulation network

The horizontal positions of points is a network developed to provide accurate control for topographic mapping, charting lakes, rivers and ocean coast lines, and for the surveys required for the design and construction of public and private works of large extent. The horizontal positions of the points can be obtained in a number of different ways in addition to traversing. These methods are triangulation, trilateration, intersection, resection, and satellite positioning. The method of surveying called triangulation is based on the trigonometric proposition that if one side and two angles of a triangle are known, the remaining sides can be computed. Furthermore, if the direction of one side is known, the directions of the remaining sides can be determined. A triangulation system consists of a series of joined or overlapping triangles in which an occasional side is measured and remaining sides are calculated from angles measured at the vertices of the triangles. The vertices of the triangles are known as triangulation stations. The side of the triangle whose length is predetermined, is called the base line. The lines of triangulation system form a network that ties together all the triangulation stations.



Fig. 1.1 Triangulation network

Triangulation network

A trilateration system also consists of a series of joined or overlapping triangles. However, for trilateration the lengths of all the sides of the triangle are measured and few directions or angles are measured to establish azimuth. Trilateration has become feasible with the development of electronic distance measuring (EDM) equipment which has made possible the measurement of all lengths with high order of accuracy under almost all field conditions. A combined triangulation and trilateration system consists of a network of triangles in which all the angles and all the lengths are measured. Such a combined system represents the strongest network for creating horizontal control.

Since a triangulation or trilateration system covers very large area, the curvature of the earth has to be taken into account. These surveys are, therefore, invariably geodetic. Triangulation surveys were first carried out by Snell, a Dutchman, in 1615. Field procedures for the establishment of trilateration station are similar to the procedures used for triangulation, and therefore, henceforth in this chapter the term triangulation will only be used.

Principle of triangulation

shows two interconnected triangles *ABC* and *BCD*. All the angles in both the triangles and the length *L* of the side *AB*, have been measured.



Principle of triangulation

Also the azimuth θ of *AB* has been measured at the triangulation station *A*, whose coordinates (X_A, Y_A), are known.

The objective is to determine the coordinates of the triangulation stations *B*, *C*, and *D* by the method of triangulation. Let us first calculate the lengths of all the lines.

By sine rule in ΔABC, we have

$$\frac{AB}{\sin 3} = \frac{BC}{\sin 1} = \frac{CA}{\sin 2}$$

We have $AB = L = l_{AB}$

or $BC = \frac{L \sin 1}{\sin 3} = l_{BC}$

and $CA = \frac{L \sin 2}{\sin 3} = l_{CA}$

Now the side *BC* being known in ΔBCD, by sine rule, we have

$$\frac{BC}{\sin 6} = \frac{CD}{\sin 4} = \frac{BD}{\sin 5}$$

We have $BC = \frac{L \sin 1}{\sin 3} = l_{BC}$

or $CD = \left(\frac{L \sin 1}{\sin 3}\right)\frac{\sin 4}{\sin 6} = l_{CD}$

and $BC = \left(\frac{L \sin 1}{\sin 3}\right)\frac{\sin 5}{\sin 6} = l_{BD}$

Let us now calculate the azimuths of all the lines.



Let us now calculate the azimuths of all the lines.

Azimuth of $AB = \theta = \theta_{AB}$

Azimuth of $AC = \theta + \angle 1 = \theta_{AC}$

Azimuth of $BC = \theta + 180° - \angle 2 = \theta_{BC}$

Azimuth of $BD = \theta + 180° - (\angle 2 + \angle 4) = \theta_{BD}$

Azimuth of $CD = \theta - \angle 2 + \angle 5 = \theta_{CD}$

From the known lengths of the sides and the azimuths, the consecutive coordinates can be computed as below.

Latitude of $AB = l_{AB} \cos\theta_{AB} = L_{AB}$

Departure of $AB = l_{AB} \sin\theta_{AB} = D_{AB}$

Latitude of $AC = l_{AC} \cos\theta_{AC} = L_{AC}$

Departure of $AC = l_{AC} \sin\theta_{AC} = D_{AC}$

Latitude of $BD = l_{BD} \cos\theta_{BD} = L_{BD}$

Departure of $BD = l_{BD} \sin\theta_{BD} = L_{BD}$



Latitude of $CD = l_{CD} \cos\theta_{CD} = L_{CD}$

Departure of $CD = l_{CD} \sin\theta_{CD} = D_{CD}$

The desired coordinates of the triangulation stations B, C, and D are as follows :

X-coordinate of B, $X_B = X_A + D_{AB}$

Y-coordinate of B, $Y_B = Y_B + L_{AB}$

X-coordinate of C, $X_C = X_A + D_{AC}$

Y-coordinate of C, $Y_C = Y_A + L_{AC}$

X-coordinate of D, $X_D = X_B + D_{BD}$

Y-coordinate of D, $Y_D = Y_B + L_{BD}$

It would be found that the length of side can be computed more than once following different routes, and therefore, to achieve a better accuracy, the mean of the computed lengths of a side is to be considered.

4.2.1 OBJECTIVE OF TRIANGULATION SURVEYS

The main objective of triangulation or trilateration surveys is to provide a number of stations whose relative and absolute positions, horizontal as well as vertical, are accurately established. More detailed location or engineering survey are then carried out from these stations.

The triangulation surveys are carried out

(i) to establish accurate control for plane and geodetic surveys of large areas, by terrestrial methods,

(ii) to establish accurate control for photogrammetric surveys of large areas,

(iii) to assist in the determination of the size and shape of the earth by making observations for latitude, longitude and gravity, and

(iv) to determine accurate locations of points in engineering works such as :

(a) Fixing centre line and abutments of long bridges over large rivers.

(b) Fixing centre line, terminal points, and shafts for long tunnels.

(c) Transferring the control points across wide sea channels, large water bodies, etc.

(d) Detection of crustal movements, etc.

(e) Finding the direction of the movement of clouds.

4.2.2 CLASSIFICATION OF TRIANGULATION SYSTEM

Based on the extent and purpose of the survey, and consequently on the degree of accuracy desired, triangulation surveys are classified as first-order or primary, second-order or secondary, and third-order or tertiary. First-order triangulation is used to determine the shape and size of the earth or to cover a vast area like a whole country with control points to which a second-order triangulation system can be connected. A second-order triangulation system consists of a network within a first-order triangulation. It is used to cover areas of the order of a region, small country, or province. A third-order triangulation is a framework fixed within and connected to a second-order triangulation system. It serves the purpose of furnishing the immediate control for detailed engineering and location surveys.

Triangulation system



S.No.	Characteristics	First-order triangulation	Second-order triangulation	Third-order triangulation
1.	Length of base lines	8 to 12 km	2 to 5 km	100 to 500 m
2.	Lengths of sides	16 to 150 km	10 to 25 km	2 to 10 km
3.	Average triangular error (after correction for spherical excess)	less than 1″	3″	12″
4.	Maximum station closure	not more than 3″	8″	15″
5.	Actual error of base	1 in 50,000	1 in 25,000	1 in 10,000
6.	Probable error of base	1 in 10,00,000	1 in 500,000	1 in 250,000
7.	Discrepancy between two measures (k is distance in kilometre)	$5\sqrt{k}$ mm	$10\sqrt{k}$ mm	$25\sqrt{k}$ mm
8.	Probable error of the computed distances	1 in 50,000 to 1 in 250,000	1 in 20,000 to 1 in 50,000	1 in 5,000 to 1 in 20,000
9.	Probable error in astronomical azimuth	0.5″	5″	10″

presents the general specifications for the three types of triangulation systems.

TRIANGULATION FIGURES AND LAYOUTS

The basic figures used in triangulation networks are the triangle, braced or geodetic quadilateral, and the polygon with a central station



Triangle Braced quadrilateral Polygon with central station

Basic triangulation figures

The triangles in a triangulation system can be arranged in a number of ways. Some of the commonly used arrangements, also called layouts, are as follows :

1. Single chain of triangles

2. Double chain of triangles

3. Braced quadrilaterals

4. Centered triangles and polygons

5. A combination of above systems.

4.2 Single chain of triangles

When the control points are required to be established in a narrow strip of terrain such as a valley between ridges, a layout consisting of single chain of triangles is generally used as shown in. This system is rapid and economical due to its simplicity of sighting only four other stations, and does not involve observations of long diagonals. On the other hand, simple triangles of a triangulation system provide only one route through which distances can be computed, and hence, this system does not provide any check on the accuracy of observations. Check base lines and astronomical observations for azimuths have to be provided at frequent intervals to avoid excessive accumulation of errors in this layout.



Fig. 1.4 Single of triangles

Double chain of triangles

A layout of double chain of triangles is shown in Fig. 1.5. This arrangement is used for covering the larger width of a belt. This system also has disadvantages of single chain of triangles system.



Double chain of triangles

Braced quadrilaterals

A triangulation system consisting of figures containing four corner stations and observed diagonals shown in below Fig. is known as a layout of braced quadrilaterals. In fact, braced quadrilateral consists of overlapping triangles. This system is treated to be the strongest and the best arrangement of triangles, and it provides a means of computing the lengths of the sides using different combinations of sides and angles. Most of the triangulation systems use this arrangement.



Braced quadrilaterals

Centered triangles and polygons

A triangulation system which consists of figures containing interior stations in triangle and polygon as shown in below Fig., is known as centered triangles and polygons.



Centered triangles and polygons

This layout in a triangulation system is generally used when vast area in all directions is required to be covered. The centered figures generally are quadrilaterals, pentagons, or hexagons with central stations. Though this system provides checks on the accuracy of the work, generally it is not as strong as the braced quadrilateral arrangement. Moreover, the progress of work is quite slow due to the fact that more settings of the instrument are required.

A combination of all above systems

Sometimes a combination of above systems may be used which may be according to the shape of the area and the accuracy requirements.

LAYOUT OF PRIMARY TRIANGULATION FOR LARGE COUNTRIES

The following two types of frameworks of primary triangulation are provided for a large country to cover the entire area.

1. Grid iron system

2. Central system

Grid iron system

In this system, the primary triangulation is laid in series of chains of triangles, which usually runs roughly along meridians (northsouth) and along perpendiculars to the meridians (east-west), throughout the country. The distance between two such chains may vary from 150 to 250 km. The area between the parallel and perpendicular series of primary triangulation, are filled by the secondary and tertiary triangulation systems. Grid iron system has been adopted in India and other countries like Austria, Spain, France, etc.



Grid iron system of triangulation

Central system

In this system, the whole area is covered by a network of primary triangulation extending in all directions from the initial triangulation figure ABC, which is generally laid at the centre of the country (Fig. 1.9). This system is generally used for the survey of an area of moderate extent. It has been adopted in United Kingdom and various other countries.



Central system of triangulation

CRITERIA FOR SELECTION OF THE LAYOUT OF TRIANGLES

The under mentioned points should be considered while deciding and selecting a suitable layout of triangles.

1. Simple triangles should be preferably equilateral.

2. Braced quadrilaterals should be preferably approximate squares.

3. Centered polygons should be regular.

4. The arrangement should be such that the computations can be done through two or more independent routes.

5. The arrangement should be such that at least one route and preferably two routes form wellconditioned triangles.

6. No angle of the figure, opposite a known side should be small, whichever end of the series is used for computation.

7. Angles of simple triangles should not be less than 45°, and in the case of quadrilaterals, no angle should be less than 30°. In the case of centered polygons, no angle should be less than 40°.

8. The sides of the figures should be of comparable lengths. Very long lines and very short lines should be avoided.

9. The layout should be such that it requires least work to achieve maximum progress.

10. As far as possible, complex figures should not involve more than 12 conditions.

It may be noted that if a very small angle of a triangle does not fall opposite the known side it does not affect the accuracy of triangulation.

4.3 WELL-CONDITIONED TRIANGLES

The accuracy of a triangulation system is greatly affected by the arrangement of triangles in the layout and the magnitude of the angles in individual triangles. The triangles of such a shape, in which any error in angular measurement has a minimum effect upon the computed lengths, is known as well-conditioned triangle. In any triangle of a triangulation system, the length of one side is generally obtained from computation of the adjacent triangle. The error in the other two sides if any, will affect the sides of the triangles whose computation is based upon their values. Due to accumulated errors, entire triangulation system is thus affected thereafter. To ensure that two sides of any triangle are equally affected, these should, therefore, be equal in length. This condition suggests that all the triangles must, therefore, be isoceles. Let us consider an isosceles triangle ABC whose one side AB is of known length. Let A, B, and C be the three angles of the triangle and a, b, and c are the three sides opposite to the angles, respectively.

As the triangle is isosceles, let the sides a and b be equal



Triangle in a triangulation system

Applying sine rule to ΔABC, we have

$$\frac{a}{\sin A} = \frac{c}{\sin C} \qquad \text{...(.1)}$$

or

$$a = c\,\frac{\sin A}{\sin C} \qquad \text{...(.2)}$$

If an error of δA in the angle A, and δC in angle C introduce the errors δa_1 and δa_2, respectively, in the side a, then differentiating Eq. (1.2) partially, we get

$$\delta a_1 = c\,\frac{\cos A\;\delta A}{\sin C} \qquad \text{...(.3)}$$

and

$$\delta a_2 = -c\,\frac{\sin A \cos C\;\delta C}{\sin^2 C} \qquad \text{...(.4)}$$

Dividing Eq. (1.3) by Eq. (1.2), we get

$$\frac{\delta a_1}{a} = \delta A \cot A \qquad \text{...(5)}$$

Dividing Eq. (1.4) by Eq. (1.2), we get

$$\frac{\delta a_2}{a} = -\delta C \cot C \qquad \text{...(.6)}$$

If $\delta A = \delta C = \pm\alpha$, is the probable error in the angles, then the probable errors in the side a are

$$\frac{\delta a}{a} = \pm\alpha\sqrt{\cot^2 A + \cot^2 C}$$

But $C = 180° - (A + B)$

or $= 180° - 2A$, $\quad A$ being equal to B.

Therefore

$$\frac{\delta a}{a} = \pm\alpha\sqrt{\cot^2 A + \cot^2 2A} \qquad \text{...(.7)}$$

From Eq. (7), we find that, if $\frac{\delta a}{a}$ is to be minimum, $(\cot^2 A + \cot^2 2A)$ should be a minimum.

Differentiating $\cot^2 A + \cos^2 2A$ with respect to A, and equating to zero, we have

$$4\cos^4 A + 2\cos^2 A - 1 = 0 \qquad \text{...(.8)}$$

Solving Eq. (1.8), for $\cos A$, we get

$$A = 56°14' \text{ (\textit{approximately})}$$

Hence, the best shape of an isoceles triangle is that triangle whose base angles are 56°14′ each. However, from practical considerations, an equilateral triangle may be treated as a well-conditional triangle. In actual practice, the triangles having an angle less than 30° or more than 120° should not be considered.

4.4 STRENGTH OF FIGURE

The strength of figure is a factor to be considered in establishing a triangulation system to maintain the computations within a desired degree of precision. It plays also an important role in deciding the layout of a triangulation system. The U.S. Coast and Geodetic Surveys has developed a convenient method of evaluating the strength of a triangulation figure. It is based on the fact that computations in triangulation involve use of angles of triangle and length of one known side. The other two sides are computed by sine law. For a given change in the angles, the sine of small angles change more rapidly than those of large angles. This suggests that smaller angles less than 30° should not be used in the computation of triangulation. If, due to unavoidable circumstances, angles less than 30° are used, then it must be ensured that this is not opposite the side whose length is required to be computed for carrying forward the triangulation series.

The expression given by the U.S. Coast and Geodetic Surveys for evaluation of the strength of figure, is for the square of the probable error (L^2) that would occur in the sixth place of the logarithm of any side, if the computations are carried from a known side through a single chain of triangles after the net has been adjusted for the side and angle conditions. The expression for L^2 is

$$L^2 = \frac{4}{3} d^2 R \qquad \ldots\ldots\ldots\ldots\ldots\ldots..9$$

where d is the probable error of an observed direction in seconds of arc, and R is a term which represents the shape of figure. It is given by

$$R = \frac{D-C}{D} \Sigma(\delta_A^2 + \delta_A \delta_B + \delta_B^2) \qquad \ldots(\ \ 10)$$

Where D = the number of directions observed excluding the known side of the figure,

A B C δ ,δ ,δ = the difference per second in the sixth place of logarithm of the sine of the distance angles A, B and C, respectively. (Distance angle is the angle in a triangle opposite to a side), and C = the number of geometric conditions for side and angle to be satisfied in each figure. It is given by

$$C = (n' - S' + 1) + (n - 2S + 3) \qquad \ldots(\ \ 11)$$

where

n = the total number of lines including the known side in a figure,

n' = the number of lines observed in both directions including the known side,

S = the total number of stations, and

S' = the number of stations occupied

For the computation of the quantity $\Sigma(\delta_A^2 + \delta_A\delta_B + \delta_B^2)$ in Eq. (10) , may be used.

In any triangulation system more than one routes are possible for various stations. The strength of figure decided by the factor R alone determines the most appropriate route to adopt the best shaped triangulation net route. If the computed value of R is less, the strength of figure is more and vice versa.

4.5 ACCURACY OF TRIANGULATION

Errors are inevitable and, therefore, inspite of all precautions the errors get accumulated. It is, therefore, essential to know the accuracy of the triangulation network achieved so that no appreciable error in plotting is introduced. The following formula for root mean square error may be used.

$$m = \sqrt{\frac{\Sigma E^2}{3n}}$$

where m = the root mean square error of unadjusted horizontal angles in seconds of arc as obtained from the triangular errors, ΣE = the sum of the squares of all the triangular errors in the triangulation series, and n =the total number of triangles in the series.

It may be noted that

(i) all the triangles have been included in the computations,

(ii) all the four triangles of a braced quadrilateral have been included in the computations, and

(iii) if the average triangular error of the series is 8", probable error in latitudes and departures after a distance of 100 km, is approximately 8 m

Example .1 If the probable error of direction measurement is 1.20″, compute the maximum value of *R* for the desired maximum probable error of (*i*) 1 in 20,000 and (*ii*) 1 in 10,000.

Solution: (*i*) *L* being the probable error of a logarithm, it represents the logarithm of the ratio of the true value and a value containing the probable error.

In this case $L = \text{the 6th place in } \log\left(1 \pm \frac{1}{20000}\right)$

$= \text{the 6th place in } \log\,((1 \pm 0.00005)$

$\log(1 + 0.00005) = 0.0000217$

The 6th place in the log value $= 21$

Hence $L = \pm 21$

It is given that $d = 1.20''$

From Eq. (9), we have

$$L^2 = \frac{4}{3} d^2 R$$

$$R_{\max} = \frac{3}{4}\frac{L^2}{d^2}$$

$$= \frac{3}{4} \times \frac{21^2}{1.20^2} = \mathbf{230}.$$

(*ii*) $L = \text{the 6th place in } \log\left(1 \pm \frac{1}{10000}\right)$

$\log(1 + 0.0001) = 0.0000434$

The 6th place in the log value $= 43$

Hence $L = \pm 43$

$$R_{\max} = \frac{3}{4} \times \frac{43^2}{1.20^2} = \mathbf{963}.$$



Example .2 The probable error of direction measurement is 1″. Compute the maximum value of R if the maximum probable error is

(*i*) 1 in 25000
(*ii*) 1 in 5000.

Solution:

(*i*) $$\log\left(1+\frac{1}{25000}\right) = 0.0000174$$

The 6th place in the log value = 17

Hence $L = \pm 17$

From Eq. (9), we get

$$R_{\max} = \frac{3L^2}{4d^2}$$

The value of d is given as 1″

$$R_{\max} = \frac{3\times 17^2}{4\times 1^2} = \mathbf{217}.$$

(*ii*) $$\log\left(1+\frac{1}{50000}\right) = 0.0000086$$

The 6th place in the log value = 9

Hence $L = \pm 9$

$$R_{\max} = \frac{3\times 9^2}{4\times 1^2} = \mathbf{61}.$$

Example 1.5Compute the strength of the figure ABCD for all the routes by which the length CD can be computed from the known side AB. Assume that all the stations were occupied.

Solution:

[illegible] we have

$$R = \frac{D-C}{D}\Sigma(\delta_A^2 + \delta_A\delta_B + \delta_C^2)$$



For the given figure in Fig. 1.16, we have

$$n = 6$$
$$n' = 6$$
$$S = 4$$
$$S' = 4$$
$$D = 2 \times (n-1)$$
$$= 2 \times (6-1) = 10$$

Hence
$$C = (n' - S' + 1) + (n - 2S + 3)$$
$$= (6-4+1) + (6 - 2 \times 4 + 3) = 4$$

and
$$\frac{D-C}{D} = \frac{10-4}{10} = \mathbf{0.60}.$$

(*a*) Route-1, using $\Delta^s\, ABC$ and ADC with common side AC

For ΔABC the distance angles of AB and AC are 26° and $100° = 44° + 56°$, respectively.

From Table 1.2,

$$\delta_{100}^2 + \delta_{100}\delta_{26} + \delta_{26}^2 = 17$$

For ΔADC, the distance angles of AC and DC are $112° = (44° + 68°)$ and 38°, respectively,

$$\delta_{112}^2 + \delta_{112}\delta_{38} + \delta_{38}^2 = 6$$

$$R_1 = 0.6 \times (17+6) = 13.8 \simeq 14$$

(*b*) Route-2, using $\Delta^s\, ABC$ and BCD with common side BC

For ΔABC the distance angles of AB and BC are 26° and 54°, respectively,

$$\delta_{54}^2 + \delta_{54}\delta_{26} + \delta_{26}^2 = 27$$

For ΔBCD, the distance angle of BC and CD are 68° and 56°, respectively,

$$\delta_{68}^2 + \delta_{68}\delta_{56} + \delta_{56}^2 = 4$$

$$R_2 = 0.6 \times (27+4) = 18.6 \simeq 19$$

(*c*) Route-3, using $\Delta^s\, ABD$ and ACD with common side AD

From ΔABC the distance for both the sides AB and AD is 44°.

$$\delta_{44}^2 + \delta_{44}\delta_{44} + \delta_{44}^2 = 13$$

From ΔACD, the distance angles of AD and CD and 30° and 38°, respectively,

$$\delta_{38}^2 + \delta_{38}\delta_{30} + \delta_{30}^2 = 31$$

$$R_3 = 0.6 \times (13+31) = 26.4 \simeq 26$$

(*d*) Route-4, using $\Delta^s\, ABD$ and BCD with common side BD.

From ΔABD, the distance angles of AB and DB are 44° and $92° = (38° + 54°)$, respectively,

$$\delta_{92}^2 + \delta_{92}\delta_{38} + \delta_{38}^2 = 7$$

From ΔBCD, the distance angles of BD and CD are $56° = (30° + 26°)$ and 56°, respectively,

$$\delta_{56}^2\delta_{56}\delta_{56} + \delta_{56}^2 = 7$$

$$R_4 = 0.6 \times (7 + 7) = 8.4 \simeq 8$$

Since the lowest value of R represents the highest strength, the best route to compute the length of CD is Route-4, having $R_4 = 8$.

4.6 ROUTINE OF TRIANGULATION SURVEY

The routine of triangulation survey, broadly consists of (a) field work, and (b) computations.

The field work of triangulation is divided into the following operations :

(i) Reconnaissance

(ii) Erection of signals and towers

(iii) Measurement of base line

(iv) Measurement of horizontal angles

(v) Measurement of vertical angles

(vi) Astronomical observations to determine the azimuth of the lines

4.7 RECONNAISSANCE

Reconnaissance is the preliminary field inspection of the entire area to be covered by triangulation, and collection of relevant data. Since the basic principle of survey is working from whole to the part, reconnaissance is very important in all types of surveys. It requires great skill, experience and judgement. The accuracy and economy of triangulation greatly depends upon proper reconnaissance survey. It includes the following operations:

1. Examination of terrain to be surveyed.

2. Selection of suitable sites for measurement of base lines.

3. Selection of suitable positions for triangulation stations.

4. Determination of intervisibility of triangulation stations.

5. Selection of conspicuous well-defined natural points to be used as intersected points.

6. Collection of miscellaneous information regarding:

(a) Access to various triangulation stations

(b) Transport facilities

(c) Availability of food, water, etc.

(d) Availability of labour

(e) Camping ground.

Reconnaissance may be effectively carried out if accurate topographical maps of the area are available. Help of aerial photographs and mosaics, if available, is also taken. If maps and aerial photographs are not available, a rapid preliminary reconnaissance is undertaken to ascertain the general location of possible schemes of triangulation suitable for the topography. Later on, main reconnaissance is done to examine these schemes. The main reconnaissance is a very rough triangulation. The plotting of the rough triangulation may be done by protracting the angles. The essential features of the topography are also sketched in. The final scheme is selected by studying the relative strengths and cost to various schemes.

For reconnaissance the following instruments are generally employed:

1. Small theodolite and sextant for measurement of angles.

2. Prismatic compass for measurement of bearings.

3. Steel tape.

4. Aneroid barometer for ascertaining elevations.

5. Heliotropes for ascertaining intervisibility.

6. Binocular.

7. Drawing instruments and material

8. Guyed ladders, creepers, ropes, etc., for climbing trees.

4.8 Erection of signals and towers

A signal is a device erected to define the exact position of a triangulation station so that it can be observed from other stations whereas a tower is a structure over a station to support the instrument and the observer, and is provided when the station or the signal, or both are to be elevated. Before deciding the type of signal to be used, the triangulation stations are selected. The selection of triangulation stations is based upon the following criteria.

Criteria for selection of triangulation stations

1. Triangulation stations should be intervisible. For this purpose the station points should be on the highest ground such as hill tops, house tops, etc.

2. Stations should be easily accessible with instruments.

3. Station should form well-conditioned triangles.

4. Stations should be so located that the lengths of sights are neither too small nor too long. Small sights cause errors of bisection and centering. Long sights too cause direction error as the signals become too indistinct for accurate bisection.

5. Stations should be at commanding positions so as to serve as control for subsidiary triangulation, and for possible extension of the main triangulation scheme.

6. Stations should be useful for providing intersected points and also for detail survey.

7. In wooded country, the stations should be selected such that the cost of clearing and cutting, and building towers, is minimum.

8. Grazing line of sights should be avoided, and no line of sight should pass over the industrial areas to avoid irregular atmospheric refraction.

Determination of intervisibility of triangulation stations

As stated above, triangulations stations should be chosen on high ground so that all relevant stations are intervisible. For small distances, intervisibility can be ascertained during reconnaissance by direct observation with the aid of binocular, contoured map of the area, plane mirrors or heliotropes using reflected sun rays from either station. However, if the distance between stations is large, the intervisibility is ascertained by knowing the horizontal distance between the stations as under.

Case-I Invervisibility not obstructed by intervening ground

If the intervening ground does not obstruct the intervisibility, the distance of visible horizon from the station of known elevation is calculated from the following formula:

$$h = \frac{D^2}{2R}(1-2m)$$

where h = height of the station above datum,

D = distance of visible horizon,

R = earth's mean radius, and

m = mean coefficient of refraction taken as 0.07 for sights over land, and. 0.08 for sights over sea.

Substituting the values of m as 0.071 and R as 6370 km , the value of h in metres is given by

$$h = 0.06735\ D^2$$

where D is in kilometres.

the distance between two stations A and B of heights h_A and h_B, respectively, is D. If D_A and D_B are the distances of visible horizon from A and B, respectively, we have

$$D_A = \sqrt{\frac{h_A}{0.06735}} = 3.853\ \sqrt{h_A}$$



Fig. 1.17 Intervisibility not obstructed by intervening ground

We have $D = D_A + D_B$

or $D_B = D - D_A$

For the known distance of visible horizon D_B as above, the height of station B is computed. If the computed value is h'_B, then

$$h'_B = 0.06735\, D_B^2$$

The computed value of height h'_B is compared with the known value h_B as below :

If $h_B \geq h'_B$, the station B will be visible from A, and

if $h_B < h'_B$, the station B will not be visible from A.

If B is not visible from A, $(h'_B - h_B)$ is the required amount of height of signal to be erected at B. While deciding the intervisibility of various stations, the line of sight should be taken at least 3 m above the point of tangency T of the earth's surface to avoid grazing rays.

Case-II Intervisibility obstructed by intervening ground

In Fig. 1.18, the intervening ground at C is obstructing the intervisibility between the stations A and B.

$$D_A = 3.853\sqrt{h_A}$$

The distance D_T of the peak C from the point of tangency T, is given by

$$D_T = D_A - D_C$$



Intervisibility obstructed by intervening ground

and
$$h'_C = 0.06735\, D_T^{\,2}$$
$$h'_B = 0.06735\, D_B^{\,2}$$



If $h'_C > h_C$, the line of sight is clear of the obstruction, and it becomes Case-I discussed above. If $h'_C < h_C$ then the signal at B is to be raised. The amount of raising required at B is computed as below.

From similar $\Delta^s\, A'C'C''$ and $A'B'B''$ in Fig. , we get

$$\frac{h''_C}{D_C} = \frac{h''_B}{D}$$

or
$$h''_B = \frac{D}{D_C}\, h''_C \qquad ..$$

where
$$h''_C = h_C - h'_C\,.$$

The required height of signal above station B_0 is

$$B_0B'' = (BB' + B'B'') - BB_0$$
$$= (h'_B + h''_C) - h_B$$

Alternate method (Captain G.T. McCaw's method)

A comparison of elevations of the stations *A* and *B* (Fig. 1.20) decides whether the triangulation stations are intervisible or not. A direct solution suggested by Captain McCaw is known as Captain McCaw's method.



Fig. 1.20 Captain McCaw's method of ascertaining intervisibility

Let h_A = elevation of station *A*

h_B = elevation of station *B*

h_C = elevation of station *C*.

$2S$ = distance between *A* and *B*

$(S+x)$ = distance between *A* and *C*

$(S-x)$ = distance between *C* and *B*

h = elevation of the line of sight at *C*

ξ = zenith distance from *A* to *B*

= (90°-vertical angle).

From Captain McCaw's formula

$$h = \frac{1}{2}(h_3 + h_A) + \frac{1}{2}(h_B - h_A)\frac{x}{S} - (S^2 - x^2)\operatorname{cosec}^2 \xi \frac{(1-2m)}{2R}$$

Practically in most of the cases, the zenith distance is very nearly equal to 90° and, therefore, the value of $\operatorname{cosec}^2 \xi$ may be taken approximately equal to unity.

However, for accurate calculations,

$$\operatorname{cosec}^2 \xi = 1 + \frac{(h_B - h_A)^2}{4S^2}$$

In Eq. (1.23), the value of $\left(\frac{1-2m}{2R}\right)$ is usually taken as 0.06735.

Therefore

$$h = \frac{1}{2}(h_B + h_A) + \frac{1}{2}(h_B - h_A)\frac{x}{S} - (S^2 - x^2) \times 0.06735$$

If $h > h_C$, the line of sight is free of obstruction. In case $h < h_C$, the height of tower to raise the signal at *B*, is computed

$$B_0B'' = (BB' + B'B'') - BB_0$$
$$= (h'_B + h''_C) - h_B$$

Example 6 Two stations *A* and *B*, 80 km apart, have elevations 15 m and 270 m above mean sea level, respectively. Calculate the minimum height of the signal at *B*.

It is given that

$$h_A = 15\,\text{m}$$
$$h_B = 270\,\text{m}$$
$$D = 80\,\text{km}$$



Fig. 1.21

we get

$$D_A = 3.853\sqrt{h_A} = 3.853 \times \sqrt{15} = 14.92\,\text{km}$$

We have

$$D_B = D - D_A$$

or

$$= 80 - 14.92$$
$$= 65.08\,\text{km}$$

$$= (h'_B + h''_C) - h_B$$

Therefore

$$h'_B = 0.06735\ D_B^2$$
$$= 0.06735 \times 65.08^2 = 285.25\,\text{m}$$

Hence, since the elevation of *B* is 270 m, the height of signal required at *B*, is

$$= 285.25 - 270 = 15.25 \simeq \mathbf{15.5\ m}.$$

Example 7 There are two stations *P* and *Q* at elevations of 200 m and 995 m, respectively. The distance of *Q* from *P* is 105 km. If the elevation of a peak *M* at a distance of *38* km from *P* is 301 m, determine whether *Q* is visible from *P* or not. If not, what would be the height of scaffolding required at *Q* so that *Q* becomes visible from *P* ?

we get

$$PT = 3.853 \times \sqrt{200} = 54.45 \text{ km}$$

Therefore
$$MT = PT - PM$$
$$= 54.45 - 38 = 16.45 \text{ km}$$

the value of *MT*, we get

$$MM' = 0.06735 \times 16.45^2 = 18.23 \text{ m}$$

The distance of *Q* from the point of tangency *T* is

$$QT = 105 - 54.45 = 50.55 \text{ km}$$

Therefore
$$QQ' = 0.06735 \times 50.55^2 = 172.10 \text{ m}$$


M''
P'
M₀
T
Q₀
301m
M'
M
h'ₙ
Q'
995m
h'g
200m
38m
105 km
P
Q

From similar $\Delta^s P'M'M''$ and $P'Q'Q''$, we have

$$\frac{M'M''}{PM} = \frac{Q'Q''}{PQ}$$

$$Q'Q'' = \frac{PQ}{PM} M'M''$$

$$= \frac{PQ}{PM} (MM'' - MM')$$

From similar $\Delta^s P'M'M''$ and $P'Q'Q''$, we have

$$\frac{M'M''}{PM} = \frac{Q'Q''}{PQ}$$

$$Q'Q'' = \frac{PQ}{PM}\, M'M''$$

$$= \frac{PQ}{PM}\,(MM'' - MM')$$

$$= \frac{105}{38} \times (301 - 18.23) = 781.34\ \text{m}$$

We have

$$QQ'' = QQ' + Q'Q''$$

$$= 172.10 + 781.34 = 953.44\ \text{m}$$

As the elevation 995 m of Q is more than 953.44 m, the peak at M does not obstruct the line of sight.

Alternatively, from the similar $\Delta^s P'M'M_o$ and $PQ'Q_o$, we have

$$\frac{M'M_o}{PM} = \frac{Q'Q_o}{PQ}$$

$$= \frac{PM}{PQ}\,(QQ_o - QQ')$$

$$= \frac{38}{105} \times (995 - 172.10) = 297.81$$

The elevation of line of sight $P'Q_o$ at M is

$$MM_o = MM' + M'M_o$$

$$= 18.23 + 297.81 = 316.04.$$

Since the elevation of peak at M is 301 m, the line of sight is not obstructed by the peak and, therefore, no scaffolding is required at Q.

Example 8 Solve the problem given in Example 7 by Capt. McCaw's method.

Solution:

the elevation of line of sight at M joining the two stations is

$$h = \frac{1}{2}(h_Q + h_P) + \frac{1}{2}(h_Q - h_P)\frac{x}{S} - (S^2 - x^2) \times 0.06735$$

It is given that

$$h_P = 200\ \text{m}$$

$$
\begin{aligned}
h_Q &= 995\,\text{m}\\
h_M &= 301\,\text{m}\\
2S &= 105\,\text{km or } S = 52.5\,\text{km}\\
S + x &= 38\,\text{km or } x = -14.5\,\text{km}
\end{aligned}
$$

Therefore

$$
\begin{aligned}
h &= \frac{1}{2}\times(995+200)+\frac{1}{2}\times(995-200)\times\frac{(-14.5)}{52.5}\\
&\quad -(52.5^2-14.5^2)\times 0.06735\\
&= \mathbf{316.24\ m}.
\end{aligned}
$$

The elevation of the line of sight $p'Q_0$ at M is 316.24 m, and the elevation of the peak is 301 m, therefore, the line of sight is clear of obstruction.

Example 9 In a triangulation survey, the altitudes of two proposed stations *A* and *B*, 100 km apart, are respectively 425 m and 750 m. The intervening ground situated at *C*, 60 km from *A*, has an elevation of 435 m. Ascertain if *A* and *B* are intervisible, and if necessary find by how much *B* should be raised so that the line of sight must nowhere be less than 3 m above the surface of the ground. Take *R* = 6400 km and *m* = 0.07.

From the given data we have

$$
\begin{aligned}
h_A &= 425\,\text{m},\ h_B = 750\,\text{m},\ h_C = 435\,\text{m}, R = 6400\,\text{km}, m = 0.07\\
2S &= 100\,\text{km, or } S = 50\,\text{km}\\
S + x &= 60\,\text{km or } x = 10\,\text{km}
\end{aligned}
$$

$$
h'_C = \frac{1}{2}(h_B+h_A)+\frac{1}{2}(h_B-h_A)\frac{x}{S}-(S^2-x^2)\operatorname{cosec}^2\xi\,\frac{(1-2m)}{2R}
$$

Taking $\operatorname{cosec}^2\xi = 1$, and substituting the values of the given data in the above equation, we have

$$
\begin{aligned}
h &= \frac{1}{2}\times(705+425)+\frac{1}{2}\times(705-425)\times\frac{10}{50}-(50^2-10^2)\\
&\quad\times 1\times\frac{(1-2\times0.07)}{2\times6400}\times1000 = 431.75\,\text{m}
\end{aligned}
$$

As the elevation of the line of sight at *C* is less than the elevation of *C*, the line of sight fails to clear *C* by

$$435-431.75 = 3.25\,\text{m}$$

To avoid grazing rays, the line of should be at least 3m above the ground. Therefore, the line of sight should be raised to $3.25 + 3 = 6.25$ m at *C*.

Hence, the minimum height of signal to be erected at *B*

$$= \frac{6.25}{60}\times100 = \mathbf{10.42\ m}.$$

4.9 Station Mark

The triangulation stations should be permanently marked on the ground so that the theodolite and signal may be centered accurately over them. The following points should be considered while marking the exact position of a triangulation station :

(*i*) The station should be marked on perfectly stable foundation or rock. The station mark on a large size rock is generally preferred so that the theodolite and observer can stand on it. Generally, a hole 10 to 15 cm deep is made in the rock and a copper or iron bolt is fixed with cement.

(*ii*) If no rock is available, a large stone is embeded about 1 m deep into the ground with a circle, and dot cut on it. A second stone with a circle and dot is placed vertically above the first stone.

(*iii*) A G.I. pipe of about 25 cm diameter driven vertically into ground up to a depth of one metre, also served as a good station mark.

(*iv*) The mark may be set on a concrete monument. The station should be marked with a copper or bronze tablet. The name of the station and the date on which it was set, should be stamped on the tablet.

(*v*) In earth, generally two marks are set, one about 75 cm below the surface of the ground, and the other extending a few centimeters above the surface of the ground. The underground mark may consist of a stone with a copper bolt in the centre, or a concrete monument with a tablet mark set on it

(*vi*) The station mark with a vertical pole placed centrally, should be covered with a conical heap of stones placed symmetrically. This



Station mark

4.10 SIGNALS

Signals are centered vertically over the station mark, and the observations are made to these signals from other stations. The accuracy of triangulation is entirely dependent on the degree of accuracy of centering the signals. Therefore, it is very essential that the signals are truly vertical, and centered over the station mark. Greatest care of centering the transit over the station mark will be useless, unless some degree of care in centering the signal is impressed upon.

A signal should fulfil the following requirements :
(*i*) It should be conspicuous and clearly visible against any background. To make the signal conspicuous, it should be kept at least 75 cm above the station mark.

(*ii*) It should be capable of being accurately centered over the station mark.

(*iii*) It should be suitable for accurate bisection from other stations.

(*iv*) It should be free from phase, or should exhibit little phase

Classification of signals
The signals may be classified as under :
(*i*) Non-luminous, opaque or daylight signals
(*ii*) Luminous signals.

(*i*) Non-luminous signals

Non-luminous signals are used during day time and for short distances. These are of various types, and the most commonly used are of following types.

(*a*) **Pole signal**: It consists of a round pole painted black and white in alternate strips, and is supported vertically over the station mark, generally on a tripod. Pole signals are suitable upto a distance of about 6 km.

(*b*) **Target signal**: It consists of a pole carrying two squares or rectangular targets placed at right angles to each other. The targets are generally made of cloth stretched on wooden frames. Target signals are suitable upto a distance of 30 km.



Pole signal



Target signal

(*c*) **Pole and brush signal** It consists of a straight pole about 2.5 m long with a bunch of long grass tied symmetrically round the top making a cross. The signal is erected vertically over the station mark by heaping a pile of stones, upto 1.7 m round the pole. A rough coat of white wash is given to make it more conspicuous to be seen against black background. These signals are very useful, and must be erected over every station of observation during reconnaissance.

(*d*) **Stone cairn**: A pile of stone heaped in a conical shape about 3 m high with a cross shape signal erected over the stone heap, is stone cairn. This white washed opaque signal is very useful if the background is dark.



Pole and brush signal



Stone cairn

(*e*) **Beacons**: It consists of red and white cloth tied round the three straight poles. The beacon can easily be centered over the station mark. It is very useful for making simultaneous observations.



Beacon

(*ii*) Luminous signals Luminous signals may be classified into two types :
(*i*) Sun signals
(*ii*) Night signals.

(*a*) **Sun signals**: Sun signals reflect the rays of the sun towards the station of observation, and are also known as heliotropes. Such signals can be used only in day time in clear weather.

Heliotrope : It consists of a circular plane mirror with a small hole at its centre to reflect the sun rays, and a sight vane with an aperture carrying a cross-hairs. The circular mirror can be rotated horizontally as well as vertically through 360°. The heliotrope is centered over the station mark, and the line of sight is directed towards the station of observation. The sight vane is adjusted looking through the hole till the flashes given from the station of observation fall at the centre of the cross of the sight vane. Once this is achieved, the heliotrope is disturbed. Now the heliotrope frame carrying the mirror is rotated in such a way that the black shadow of the small central hole of the plane mirror falls exactly at the cross of the sight vane. By doing so, the reflected beam of rays will be seen at the station of observation. Due to motion of the sun, this small shadown also moves, and it should be constantly ensured that the shadow always remains at the cross till the observations are over.



Heliotrope

The heliotropes do not give better results compared to signals. These are useful when the signal station is in flat plane, and the station of observation is on elevated ground. When the distance between the stations exceed 30 km, the heliotropes become very useful.

(b) Night signals: When the observations are required to be made at night, the night signals of following types may be used.

1. Various forms of oil lamps with parabolic reflectors for sights less than 80 km.
2. Acetylene lamp designed by Capt. McCaw for sights more than 80 km.
3. Magnesium lamp with parabolic reflectors for long sights.
4. Drummond’s light consisting of a small ball of lime placed at the focus of the parabolic reflector, and raised to a very high temperature by impinging on it a stream of oxygen.

5. Electric lamps.

4.11 TOWERS

A tower is erected at the triangulation station when the station or the signal or both are to be elevated to make the observations possible form other stations in case of problem of intervisibility. The height of tower depends upon the character of the terrain and the length of the sight. The towers generally have two independent structures. The outer structure is for supporting the observer and the signal whereas the inner one is for supporting the instrument only. The two structures are made entirely independent of each other so that the movement of the observer does not disturb the instrument setting. The two towers may be made of masonary, timber or steel. For small heights, masonary towers are most suitable. Timber scaffolds are most commonly used, and have been constructed to heights over 50 m. Steel towers made of light sections are very portable, and can be easily erected and dismantled. Bilby towers patented by J.S. Bilby of the U.S. Coast and Geodetic Survey, are popular for heights ranging from 30 to 40 m. This tower weighing about 3 tonnes, can be easily erected by five persons in just 5 hrs. A schematic of such a tower is shown in Fig. 1.30.



PHASE OF A SIGNAL

When cylindrical opaque signals are used, they require a correction in the observed horizontal angles due an error known as the *phase*. The cylindrical signal is partly illuminated by the sun, and the other part remains in shadow, and becomes invisible to the observer. While making the observations, the observer may bisect the bright portion or the bright line. Thus the signal is not bisected at the centre, and an error due to wrong bisection is introduced. It is, thus, the apparent displacement of the signal. The phase correction is thus necessary so that the observed horizontal angles may be reduced to that corresponding to the centre of the signal.

Depending upon the method of observation, phase correction is computed under the following two conditions. Windows Lamp Screen Outer tower (with bracings) Inner tower (without bracings



(*i*) Observation made on bright portion

a cylindrical signal of radius *r*, is centered over the station *P*. The illuminated portion of the signal which the observer from *O* is able to see, is *AB*. The observer from the station *O*, makes two observations at *A* and *B* of the bright portion, *AB*. Let *C* be the midpoint of *AB*.

Let θ = the angle between the sun and the line *OP*

α_1 and α_2 = the angles *BOP* and *AOP*, respectively

D = the horizontal distance *OP*

$$\alpha = \text{half of the angle } AOB = \frac{1}{2}(\alpha_2 - \alpha_1)$$

$$\beta = \text{the phase correction} = \alpha_1 + \alpha = \alpha_1 + \frac{1}{2}(\alpha_2 - \alpha_1)$$

or
$$= \frac{1}{2}(\alpha_1 + \alpha_2) \qquad \dots (1.26)$$

From ΔOAP we get

$$\tan \alpha_2 = \frac{r}{D}$$

Phase correction when observation made on the bright portion

α_2 being small, we can write

$$\alpha_2 = \frac{r}{D} \text{ radians}$$

As the distance *PF* is very small compared to *OP*, *OF* may be taken as *OP*. Thus, from right angle ΔBFO, we get

$$\tan\ \alpha_1 = \frac{BF}{OF} = \frac{BF}{OP} = \frac{BF}{D}$$

From ΔPFB, we get

$$BF = r\sin(90 - \theta) = r\cos\theta$$

Substituting the value of *BF* in Eq. (1.28), we get

$$\tan\ \alpha_1 = \frac{r\cos\theta}{D}$$

α_1 being small, we can write

$$\alpha_1 = \frac{r\cos\theta}{D} \text{ radians}$$

Substituting the values of α_1 and α_2 , we have

$$\alpha_1 = \frac{r\cos\theta}{D} \text{ radians}$$

Substituting the values of α_1 and α_2 we have

$$\begin{aligned}\beta &= \frac{1}{2}\left(\frac{r}{D} + \frac{r\cos\theta}{D}\right) = \frac{r}{D}\left(\frac{1+\cos\theta}{2}\right) \\ &= \frac{r}{D}\cos^2\frac{\theta}{2} \text{ radians} \\ &= \frac{r}{D\sin 1''}\cos^2\frac{\theta}{2} \text{ seconds} \\ \beta &= \frac{206265r}{D}\cos^2\frac{\theta}{2} \text{ seconds}\end{aligned}$$

(*ii*) Observations made on the bright line

In this case, the bright line at C on the cylindrical signal of radius r, is sighted from O

Let CO = the reflected ray of the sun from the bright line at C

β = the phase correction

θ = the angle between the sun and the line OP


S
S
A
r
P
C
F
B
$90° - \frac{1}{2}(\theta - \beta)$
$90° - \frac{1}{2}(\theta - \beta)$
D
β
S_1
θ
O

The rays of the sun are always parallel to each other, therefore, SC is parallel to S_1O.

$$\angle SCO = 180° - (\theta - \beta)$$

$$\angle PCO = 180° - \frac{1}{2}\angle SCO$$

or

$$= 180° - \frac{1}{2}[180° - (\theta - \beta)]$$

$$= 90° + \frac{1}{2}(\theta - \beta)$$

Therefore,

$$\angle CPO = 180° - (\beta + \angle PCO)$$

Substituting the value of $\angle PCO$ and after simplification, we get

$$\angle CPO = 90° - \frac{1}{2}(\theta + \beta)$$

As β is very small compared to θ, it can be ignored, Therefore

$$\angle CPO = 90° - \frac{1}{2}\theta$$

From the right angle ΔCFP, we have

$$\frac{CF}{CP} = \sin CPO = \sin\left(90° - \frac{1}{2}\theta\right)$$

or

$$CF = r\sin\left(90° - \frac{1}{2}\theta\right)$$

From ΔCFO, we get

$$\tan\beta = \frac{CF}{OF}$$

PF being very small compared to *OP*, *OF* may be taken as *OP*. Substituting the value of *CF* and taking *OF* equal to *D*, we get

$$\tan\beta = \frac{r\sin\left(90^\circ - \frac{1}{2}\theta\right)}{D}$$

From the right angle ΔCFP, we have

$$\frac{CF}{CP} = \sin CPO = \sin\left(90^\circ - \frac{1}{2}\theta\right)$$

or

$$CF = r\sin\left(90^\circ - \frac{1}{2}\theta\right)$$

From ΔCFO, we get

$$\tan\beta = \frac{CF}{OF}$$

or

$$\beta = \frac{r\cos\frac{\theta}{2}}{D} \text{ radians}$$

$$\beta = \frac{206265r}{D}\cos\frac{\theta}{2} \text{ seconds} \quad \text{... (1.36)}$$

The phase correction β is applied to the observed horizontal angles in the following manner.

Let there be four stations S_1, S_2, *P*, and *O* as shown in (Fig. 1.33). The observer is at *O*, and the angles S_1OP and POS_2 have been measured from *O* as θ_1' and θ_2', respectively.



If the required corrected angles are θ_1 and θ_2, then

$$\theta_1 = \theta_1' + \beta$$

and

$$\theta_2 = \theta_2' - \beta$$

when β is the phase correction.

While applying the corrections the directions of the phase or $$\beta = \frac{r\cos\frac{\theta}{2}}{D} \text{ radians}$$

$$\beta = \frac{206265r}{D}\cos\frac{\theta}{2} \text{ seconds}$$

The phase correction β is applied to the observed horizontal angles in the following manner.

Let there be four stations S_1, S_2, P, and O. The observer is at O, and the angles S_1OP and POS_2 have been measured from O as θ_1' and θ_2', respectively.

If the required corrected angles are θ_1 and θ_2, then

$$\theta_1 = \theta_1' + \beta$$

and $$\theta_2 = \theta_2' - \beta$$

when β is the phase correction.

While applying the corrections the directions of the phase correction, and the observed stations with respect to the line *OP*, must be noted carefully.



Applying the phase correction to the measured horizontal angles

Example _10 A cylindrical signal of diameter 4 m, was erected at station *B*. Observations were made on the signal from station *A*. Calculate the phase corrections when the observations were made

(*i*) on the bright portion, and

(*ii*) on the bright line.

Take the distance *AB* as 6950 m, and the bearings of the sun and the station *B* as 315° and 35°, respectively.

Solution: Given that θ = Bearing of sun – bearing of B

$$= 315° - 35° = 280°$$

$$r = \frac{\text{Diameter}}{2} = \frac{4}{2} = 2\,\text{m}$$

$$D = 6950\,\text{m}$$

(*i*)

the phase correction

$$\beta = \frac{206265r}{D}\cos^2\frac{\theta}{2} \text{ seconds}$$

$$= \frac{206265 \times 2}{6950} \times \cos^2\frac{280°}{2} = \mathbf{34.83\ seconds}.$$

(*ii*)

the phase correction

$$\beta = \frac{206265r}{D}\cos\frac{\theta}{2} \text{ seconds}$$

$$= \frac{206265\times 2}{6950}\times\cos\frac{280^\circ}{2} = \mathbf{45.47\ seconds.}$$

Example 11 The horizontal angle measured between two stations *P* and *Q* at station *R*, was 38°29′30″. The station *Q* is situated on the right of the line *RP*.

The diameter the cylindrical signal erected at station *P*, was 3 m and the distance between *P* and *R* was 5180 m. The bearing of the sun and the station *P* were measured as 60° and 15°, respectively. If the observations were made on the bright line, compute the correct horizontal angle *PRQ*.



Solution:

From the given data

$$\theta = 60^\circ - 15^\circ = 45^\circ$$
$$D = 5180\text{m}$$
$$r = 1.5\text{m}$$

, we get

$$\beta = \frac{206265r}{D}\cos\frac{\theta}{2}$$

$$= \frac{206265\times 1.5}{5180}\cos\frac{45^\circ}{2}$$

$$= 55.18 \text{ seconds}$$

The correct horizontal angle *PRQ* $= 38^\circ\,29'\,30'' + \beta$

$$= 38^\circ 29' 30'' + 55.18'' = \mathbf{38^\circ 30' 25.18''}.$$

4.11.1 MEASUREMENT OF BASE LINE

The accuracy of an entire triangulation system depends on that attained in the measurement of the base line and, therefore, the measurement of base line forms the most important part of the triangulation operations. As base line forms the basis for computations of triangulation system it is laid down with great accuracy in its measurement and alignment. The length of the base line depends upon the grade of the triangulation. The length of the base is also determined by the desirability of securing strong figures in the base net. Ordinarily the longer base, the easier it will be found to secure strong figures. The base is connected to the triangulation system through a base net. This connection may be made through a simple figure , or through a much more complicated figures discussed in the base line extension. Apart from main base line, several other check bases are also measured at some suitable intervals. In India, ten bases were measured, the length of nine bases vary from 6.4 to 7.8 miles, and that of the tenth base is 1.7 miles.



Base net

Selection of site for base line

Since the accuracy in the measurement of the base line depends upon the site conditions, the following points should be taken into consideration while selecting the site for a base line.

1. The site should be fairly level or gently undulating. If the ground is sloping, the slope should be uniform and gentle.
2. The site should be free from obstructions throughout the length of the base line.
3. The ground should be firm and smooth.
4. The two extremities of the base line should be intervisible.
5. The site should be such that well-conditioned triangles can be obtained while connecting extremities to the main triangulation stations.
6. The site should be such that a minimum length of the base line as specified, is available.

Equipment for base line measurement

Generally the following types of base measuring equipments are used :

1. Standardised tapes : These are used for measuring short bases in plain grounds.
2. Hunter’s short base: It is used for measuring 80 m long base line and its extension is made by

subtense method.
3. Tacheometric base measurements : It is used in undulating grounds for small.
.
4. Electronic distance measurement: This is used for fairly long distances and has been discussed in **Standardised tapes :** For measuring short bases in plain areas standardised tapes are generally used. After having measured the length, the correct length of the base is calculated by applying the required corrections. For details of corrections,. If the triangulation system is of extensive nature, the corrected lengths of the base is reduced to the mean sea level.

Hunter's short base :

Dr. Hunter who was a Director of Survey of India, designed an equipment to measure the base line, which was named as Hunter's short base. It consists of four chains, each of 22 yards (20.117 m) linked together. There are 5 stands, three-intermediate two-legged stands, and two three-legged stands at . A 1 kg weight is suspended at the end of an arm, so that the chains remain straight during observations. The correct length of the individual chains is supplied by the manufacturer or is determined in the laboratory. The lengths of the joints between two chains at intermediate supports, are measured directly with the help of a graduated scale. To obtain correct length between the centres of the targets, usual corrections
such as temperature, sag, slope, etc., are applied. To set up of the Hunter's short base the stand at the end *A* (marked in red colour) is centered on the ground mark and the target is fitted with a clip. The target *A* is made truly vertical so that the notch on its tip side is centered on the ground mark. The end of the base is hooked with the plate *A* and is spread carefully till its other end is reached. In between, at every joint of the chains, two-legged supports are fixed to carry the base. The end *B* (marked in green colour) is fixed to the *B* stand and the 1 kg weight is attached at the end of the lever. While fixing the end supports *A* and *B* it should be ensured that their third leg should face each other under the base. Approximate alignment of the base is the done by eye judgement.

For final alignment, a theodolite is set up exactly over the notch of the target *A*, levelled and centered accurately. The target at *B* is then bisected. All intermediate supports are set in line with the vertical cross-hair of the theodolite. At the end again ensure that all the intermediate supports and the target *B* are in one line. In case the base is spread along undulating ground, slope correction is applied. To measure the slope angles of individual supports, a target is fixed to a long iron rod of such a length that it is as high above the tape at *A* as the trunion axis of the theodolite. The rod is held vertically at each support and the vertical angles for each support are read.



Hunter's short base

Example 12 A tape of standard length 20 m at 85° F was used to measure a base line. The measured distance was 882.10 m. The following being the slopes for the various segments of the line.

Segment	Slope
100 m	2°20′
150 m	4°12′
50 m	1°06′
200 m	7°45′
300 m	3°00′
82.10 m	5°10′

Find the true length of the base line if the mean temperature during measurement was 63°F. The coefficient of expansion of the tape material is 6.5×10^{-6} per °F.

Solution:

Correction for temperature

$$
\begin{aligned}
C_t &= \alpha(t_m - t_0)L \\
&= 6.5 \times 10^{-6} \times (63 - 65) \times 882.10 \\
&= 0.126 \text{ m (subtractive)}
\end{aligned}
$$

Correction for slope

$$
\begin{aligned}
C_s &= \Sigma[(1 - \cos\alpha)L] \\
&= (1 - \cos 2°20') \times 100 + (1 - \cos 4°12') \times 150 + (1 - \cos 1°06') \times 50 \\
&\quad + (1 - \cos 7°48') \times 200 + (1 - \cos 3°00') \times 300 + (1 - \cos 5°10') \times 82.10 \\
&= 3.079 \text{ m (subtractive)} \\
\text{Total correction} &= C_t + C_s \\
&= 0.126 + 3.079 \\
&= 3.205 \text{ m (subtractive)} \\
\text{Corrected length} &= 882.10 - 3.205 \\
&= \mathbf{878.895\ m}.
\end{aligned}
$$

Example 13. A base line was measured between two points *A* and *B* at an average elevation of 224.35 m. The corrected length after applying all correction was 149.3206 m. Reduce the length to mean sea level. Take earth's mean radius as 6367 km.

Solution:

The reduced length at mean seal level is

$$L' = \frac{R}{(R + h)} L$$

$$= \frac{6367}{6367 + \left(\frac{224.35}{1000}\right)} \times 149.3205$$

$$= \mathbf{149.3152\ m}.$$

4.11.2 Extension of base line

Usually the length of the base lines is much shorter than the average length of the sides of the triangles.

This is mainly due to the following reasons:
(*a*) It is often not possible to get a suitable site for a longer base.
(*b*) Measurement of a long base line is difficult and expensive.

The extension of short base is done through forming a base net consisting of well-conditioned triangles.There are a great variety of the extension layouts but the following important points should be kept in mind in selecting the one.

(*i*) Small angles opposite the known sides must be avoided.
(*ii*) The length of the base line should be as long as possible.
(*iii*) The length of the base line should be comparable with the mean side length of the triangulation net.
(*iv*) A ratio of base length to the mean side length should be at least 0.5 so as to form well-conditioned triangles.
(*v*) The net should have sufficient redundant lines to provide three or four side equations within the figure.
(*vi*) Subject to the above, it should provide the quickest extension with the fewest stations.

There are two ways of connecting the selected base to the triangulation stations. There are
(*a*) extension by prolongation, and
(*b*) extension by double sighting.

(a) Extension by prolongation

Let up suppose that *AB* is a short base line which is required to be extended by four times. The following steps are involved to extend *AB*.



Base extension by prolongation

(*i*) Select *C* and *D* two points on either side of *AB* such that the triangles *BAC* and *BAD* are wellconditioned.

(*ii*) Set up the theodolite over the station *A*, and prolong the line *AB* accurately to a point *E* which is visible from points *C* and *D*, ensuring that triangles *AEC* and *AED* are well-conditioned.

(*iii*) In triangle *ABC*, side *AB* is measured. The length of *AC* and *AD* are computed using the measured angles of the triangles *ABC* and *ABD*, respectively.

(*iv*) The length of *AE* is calculated using the measured angles of triangles *ACE* and *ADE,* and taking mean value.

(*v*) Length of *BE* is also computed in similar manner using the measured angles of the triangles *BEC* and *BDE*. The sum of lengths of *AB* and *BE* should agree with the length of *AE* obtained in step .

(*vi*) If found necessary, the base can be extended to *H* in the similar way.

(*b*) Extension by double sighting
Let *AB* be the base line. To extend the base to the length of side *EF*, following steps are involved.

(*i*) Chose intervisible points *C*, *D*, *E*, and *F*.

(*ii*) Measure all the angles marked in triangles *ABC* and *ABD*. The most probable values of these angles are found by the theory of least-squares discussed in Chapter 2.
(*iii*) Calculate the length of *CD* from these angles and the measured length *AB*, by applying the sine law to triangles *ACB* and *ADB* first, and then to triangles *ADC* and *BDC*



Base extension by double sighting

(*iv*) The new base line *CD* can be further extended to the length *EF* following the same procedure as above. The line *EF* may from a side of the triangulation system.

If the base line *AB* is measured on a good site which is well located for extension and connection to the main triangulation system, the accuracy of the system is not much affected by the extension of the base line. In fact, in some cases, the accuracy may be higher than that of a longer base line measured over a poor terrain

4.11.3 MEASUREMENT OF HORIZONTAL ANGLES

The horizontal angles of a triangulation system can be observed by the following methods:

(*i*) Repetition method
(*ii*) Reiteration method.

The procedure of observation of the horizontal angles by the above methods has been discussed in

(*i*) Repetition method

For measuring an angle to the highest degree of precision, several sets of repetitions are usually taken.

There are following two methods of taking a single set.

(*a*) In the first method, the angle is measured clockwise by 6 repetitions keeping the telescope normal.

The first value of the angle is obtained by dividing the final reading by 6. The telescope is inverted, and the angle is measured again in anticlockwise direction by 6 repetitions. The second value of the angle is obtained by dividing the final reading by 6. The mean of the first and second values of the angle is the average value of the angle by first set.

For first-order work, five or six sets are usually required. The final value of the angle is the mean of the values obtained by different sets.

(*b*) In the second method, the angle is measured clockwise by six repetitions, the first three with telescope normal and the last three with telescope inverted. The first value of the angle is obtained by dividing the final reading by 6. Now without altering the reading obtained in the sixth repetition, the explement angle (i.e., 360°– the angle), is measured clockwise by six repetitions, the first three with telescope inverted and the last three with telescope normal. The final reading should theoretically be zero. If the final reading is not zero, the error is noted, and half of the error is distributed to the first value of the angle. The result is the corrected value of the angle by the first set. As many sets as desired are taken, and the mean of all the value of various sets, is the average value of the angle. For more accurate work and to eliminate the errors due to inaccurate graduations of the horizontal circle, the initial reading at the beginning of each set may not be set to zero but to different values. If *n* sets are required, the initial setting should be sucessively increased by 180°/*n*.

For example, for 6 sets the initial readings would be 0°, 30°, 60°, 90°, 120° and 150°, respectively.

(*ii*) Reiteration method or direction method

In the reiteration method, the triangulation signals are bisected successively, and a value is obtained for each direction in each of several rounds of observations. One of the triangulation stations which is likely to be always clearly visible may be selected as the initial station or reference station. The theodolites used for the measurement of angles for triangulation surveys, have more than one micrometer. One of the micrometer is set to 0° and with telescope normal, the initial station is bisected, and all the micrometers are read. Each of the successive stations are then bisected, and all the micrometers are read. The stations are then again bisected in the reverse direction, and all the micrometers are read after each bisection. Thus, two values are obtained for each angle when the telescope is normal. The telescope is then inverted, and the observations are repeated.

This constitutes one set in which four value of each angle are obtained. The micrometer originally at 0° is now brought to a new reading equal to 360°/*mn* (where *m* is the number of micrometers and *n* is the number of sets), and a second set is observed in the same manner. The number of sets depends on the accuracy required. For first-order triangulation, sixteen such sets are required with a 1″ direction theodolite, while for second-order triangulation four, and for third-order triangulation two. With more refined instrument having finer graduations, however, six to eight sets are sufficient for the geodetic work.

4.12 MEASUREMENT OF VERTICAL ANGLES

Measurement of vertical angles is required to compute the elevation of the triangulation stations.

4.12.1 ASTRONOMICAL OBSERVATIONS

To determine the azimuth of the initial side, intermediate sides, and the last side of the triangulation net, astronomical observations are made. For detailed procedure and methods of observation

4.12.2 SOME EXTRA PRECAUTIONS IN TAKING OBSERVATIONS

To satisfy first-second, and third-order specifications, care must be exercised. Observer must ensure the following:

1. The instrument and signals have been centred very carefully.
2. Phase in signals has been eliminated.
3. The instrument is protected form the heating effects of the sun and vibrations caused by wind.
4. The support for the instrument is adequately stable.
5. In case of adverse horizontal refraction, observations should be rescheduled to the time when the horizontal refraction is minimum. Horizontal angles should be measured when the air is the clearest, and the lateral refraction is minimum.

If the observations are planned for day hours, the best time in clear weather is from 6 AM to 9 AM and from 4 PM till sunset. In densely clouded weather satisfactory work can be done all day. The best time for measuring vertical angles is form 10 AM to 2 PM when the vertical refraction is the least variable. First-order work is generally done at night, since observations at night using illuminated signals help in reducing bad atmospheric conditions, and optimum results can be obtained. Also working at night doubles the hours of working available during a day. Night operations are confined to period from sunset to midnight.

4.12.3 SATELLITE STATION AND REDUCTION TO CENTRE

To secure well-conditioned triangles or to have good visibility, objects such as chimneys, church spires, flat poles, towers, lighthouse, etc., are selected as triangulation stations. Such stations can be sighted from other stations but it is not possible to occupy the station directly below suchexcellent targets for making the observations by setting up the instrument over the station point. Also, signals are frequently blown out of position, and angles read on them have to be corrected to the true position of the triangulation station. Thus, there are two types of problems:

1. When the instrument is not set up over the true station, and
2. When the target is out of position.

In below Fig., *A*, *B*, and *C* are the three triangulation stations. It is not possible to place instrument at *C*. To solve this problem another station *S*, in the vicinity of *C,* is selected where the instrument can be set up, and from where all the three stations are visible for making the angle observations. Such station is known as *satellite station.* As the observations from *C* are not possible, the observations form *S* are made on *A*, *B*, and, *C* from *A* and *B* on *C*. From the observations made, the required angle *ACB* is calculated. This is known as *reduction to centre.*



Reduction to centre

In the other case, *S* is treated as the true station point, and the signal is considered to be shifted to the position *C*. This case may also be looked upon as a case of *eccentricity of signal.* Thus, the observations from *S* are made to the triangulation stations *A* and *B*, but from *A* and *B* the observations are made on the signal at the shifted position *C*. This causes errors in the measured values of the angles *BAC* and *ABC*. Both the problems discussed above are solved by reduction to centre. Let the measured

$$\angle BAC = \theta_A$$
$$\angle ABC = \theta_B$$
$$\angle ASB = \theta$$
$$\angle BSC = \gamma$$

Eccentric distance $SC = d$

The distance AB is known by computations form preceding triangle of the triangular net. Further, let

$$\angle SAC = \alpha$$
$$\angle SBC = \beta$$
$$\angle ACB = \phi$$
$$AB = c$$
$$AC = b$$
$$BC = a$$

As a first approximation in ΔABC the $\angle ACB$ may be taken as

$$= 180^\circ - (\angle BAC + \angle ABC)$$

or $$\phi = 180^\circ - (\theta_A + \theta_B)$$

In the triangle ABC we have

$$\frac{c}{\sin\phi} = \frac{a}{\sin\theta_A} = \frac{b}{\sin\theta_B}$$

$$a = \frac{c.\sin\theta_A}{\sin\phi}$$

and $$b = \frac{c.\sin\theta_B}{\sin\phi}$$

Compute the values of a and b by substituting the value of ϕ obtained and respectively.

Now, from $\Delta^s SAC$ and SBC we have

$$\frac{d}{\sin\alpha} = \frac{b}{\sin(\theta + \gamma)}$$

$$\frac{d}{\sin\beta} = \frac{a}{\sin\gamma}$$

$$\sin\alpha = \frac{d\sin(\theta + \gamma)}{b}$$

$$\sin\beta = \frac{d\sin\gamma}{a}$$

As the satellite station S is chosen very close to the main station C, the angles α and β are extremely small. Therefore, taking $\sin\alpha = \alpha$, and $\sin\beta = \beta$ in radians, we get.

$$\alpha = \frac{d\sin(\theta+\gamma)}{b\sin 1''}$$

or $$= \frac{d\sin(\theta+\gamma)}{b}\times 206265 \text{ seconds}$$

and $$\beta = \frac{d\sin\gamma}{a}\times 206265 \text{ seconds}$$

θ, γ, d, b and a are known quantities, therefore, the values of α and β can be computed. Now a more correct value of the angle $\angle ACB$ can be found.

We have

$$\angle AOB = \theta+\alpha = \phi+\beta$$

or $$\phi = \theta+\alpha-\beta$$

the value of ϕ when the satellite station S is to the left of the main station C. In the general, the following four cases as shown in Fig. 1.40a, can occur depending on the field conditions.

Case I: S towards the left of C (Fig. 1.39)

$$\phi = \theta+\alpha-\beta$$

Case II: S towards the right of C (Fig. 1.40b), the position S_2.

$$\phi = \theta-\alpha+\beta$$

Case III: S inside the triangle ABC (Fig. 1.40c), the position S_3.

$$\phi = \theta-\alpha-\beta$$

Case IV: S outside the triangle ABC (Fig. 1.40d), the position S_4.

$$\phi = \theta+\alpha+\beta$$







(c) (d)

Locations of satellite station with reference to triangulation stations C

4.13 ECCENTRICITY OF SIGNAL

When the signal is found shifted from its true position, the distance between the shifted signal and the station point *d* is measured. The corrections α and β to the observed angles *BAC* and *ABC,* respectively, are computed and the corrected values of the angles are obtained as under

$$\text{Correct } \angle BAS = \theta_A + \alpha$$
$$\text{Correct } \angle ABS = \theta_B - \beta$$

4.14 Trigonometrical Levelling

Trigonometric Levelling is the branch of Surveying in which we find out the vertical distance between two points by taking the vertical angular observations and the known distances. The known distances are either assumed to be horizontal or the geodetic lengths at the mean sea level(MSL). The distances are measured directly(as in the plane surveying) or they are computed as in the geodetic surveying.

The trigonometric Leveling can be done in two ways:

(1) Observations taken for the height and distances (2) **Geodetic Observations.**

In the first way, we can measure the horizontal distance between the given points if it is accessible.We take the observation of the vertical angles and then compute the distances using them. If the distances are large enough then we have to provide the correction for the curvature and refraction and that we provide to the linearly to the distances that we have computed.

In the second way, i.e geodetic observations, the distances between the two points are geodetic distances and the principles of the plane surveying are not applicable here. The corrections for the curvature and refraction are applied directly to the angles directly.

Now we will discuss the various cases to find out the difference in elevation between the two.

(1) The two points are at known distance: The base of the object is accessible.

When the two points are at a known horizontal distance then we can find out the distance between them by taking the vertical angle observations.
If the vertical angle of elevation from the point to be observed to the instrument axis is known we can calculate the vertical distance by taking the help of the trigonometry.
Horizontal distance*Tan(verticle angle) = Vertical difference between the two.
If the points are at small distance apart then there is no need to apply the correction for the curvature and refraction else you can apply the correction as given below:
C= 0.06728D*D
Where D is the horizontal distance between the given two points in Kilometers.
but the Correction is in meters (m).
(2) The base of the object is not accessible :
(a)(***When the instrument is shifted to the nearby place and the observations are taken from the same level of the line of sight:*** In such case we have to take the two angular observations of the vertical angles. The instrument is shifted to a nearby place of known distance, and then with the known distance between these two and the angular observations from these two stations, we can find the vertical difference in distance between the line of sight of the instrument and the top point of the object.
(b) When the line of sights of the two instrument setting is different : Here again there are two cases: (i) When the line of sights are at a small vertical distance which can be measured through the vertical staff readings. (ii) When the difference is larger than the staff height.
***(i)* In first case,** It is advised to apply the formula for the difference in the height of the top of the object from these two lines of sights. The difference in lines of sights is same as the staff readings difference, when the staff is kept at a little distance from these two points. So we can get the solution for the vertical distance easily.
(ii) In the second case, there is a need to put a vane staff at the first instrument station and the angle of elevation is measured from the second point of observation. This gives us the difference in the line of the sights between the two points of instrument station. Then again we do the same.
(c) When the instrument station and the top of object are not in same vertical plane: In this case there is a need to measure at-least two horizontal angles of the horizontal triangle formed by the two instrument stations and the base of the object. Again we will take the vertical angular observations from the two instrument stations also and then we can apply the sine rule to solve the horizontal distances of the triangle. With the help of these angles and the distances we can get the vertical distance between any two point(Instrument station and the top of object).

For rapid leveling or leveling in rolling ground or for inaccessible points, trigonometric method of leveling is being used. In this method, theodolite (an instrument which can measure angle) is being generally used as an instrument for taking different measurements.



Let us consider two stations T an by trigonometric method of leveling. At T, a theodolite instrument is set up. TT ' is the height of the instrument above the point T (to be recorded at the time of observation). A leveling staff is held at X. At the vertical angle of elevation of the actual line of sight a, let x_1 is the observed staff reading. The difference in level between T and X is given by

$$\Delta H_{TX} = TT' + x_{t'} x_h + x_h x_1 - x_1 X$$

where $x_{t'} x_h$ is deviation of the horizontal line of sight due to curvature of the earth and refraction of light (given by $0.0675\ T' x_h^2$). $x_h x_1$ is $T' x_1$ sina or $T' x_h$ tana , $T' x_1$ is the inclined distance from the instrument to the staff and $T' x_h$ is the horizontal distance between the points, $x_1 X$ is the staff reading at X.

Example

In order to eliminate the uncertainty due to refraction, observations for vertical angle are made at both ends of the line as close in point of time as possible. The vertical angle at the lower of the two peaks to the upper peak is +3° 02' 05"?. The reciprocal vertical angle at the upper peak is -3° 12' 55"?. The height of instrument are kept to be same in all observation. The slope distance between two mountain peaks determined by EDM measurement is 21,345m. Compute the difference in elevations between the two peaks.

Solution :

Average vertical angle a = (3° 02' 05" + 3° 12' 55") / 2 = 6° 15' 00 "

Difference in elevation = 21.345 sin 3° 07' 30 " + 0.0675 (21.345 cos 3° 07' 30 ")^2

= (1.163 + 30.662) m

= 31.825 me

Reciprocal leveling

To find accurate relative elevations of two widely separated intervisible points (between which levels cannot be set), reciprocal leveling is being used.

To find the difference in elevation between two points, say X and Y, a level is set up at L near X and readings (X_1 and Y_1) are observed with staff on both X and Y respectively. The level is then set up near Y and staff readings (Y_2 and X_2) are taken respectively to the near and distant points. If the differences in the set of observations are not same, then the observations are fraught with errors. The errors may arise out of the curvature of the earth or intervening atmosphere (associated with variation in temperature and refraction) or instrument (due to error in collimation) or any combination of these.



The true difference in elevation and errors associated with observation, if any, can be found as follows:

Let the true difference in elevation between the points be rh and the total error be e. Assuming, no error on observation of staff near the level (as the distance is very small)

Then, rh = $X_1 \sim (Y_1 - e)$ [From first set of observation]

and rh = $(X_2 - e) \sim Y_2$ [From second set of observation]

$$\text{or, } \Delta h = \frac{(X_1 \sim Y_1) + (X_2 \sim Y_2)}{2}$$

$$\text{or, } \Delta h = \frac{\text{First difference in observations + Second difference in observation}}{2}$$

Thus, the true difference in elevation between any two points can be obtained by taking the mean of the two differences in observation.

$$\text{Total error, } e = \frac{(X_1 \sim Y_1) \sim (X_2 \sim Y_2)}{2}$$

$$\text{or, } e = \frac{\text{First difference in observations - Second difference in observation}}{2}$$

Thus, total error in observations can be obtained by taking the difference of the two differences in observation. The total error consist of error due to curvature of the earth, atmospheric errors (due to temperature and refraction) and instrumental errors (due to error in collimation) etc.

Example

In order to transfer reduced level across a canyon, a reciprocal leveling campaign was conducted. Simultaneous readings were observed using two levels one at each side of the canyon. Each of the levels are having same magnifying power and sensitiveness of level tube. With instruments interchanged during leveling operation yielded the following average readings:

Instrument station	**Average near readings, meter**	**Average distant, readings, meter**	**R.L of X = 101.345 m** **Distance, XY = 1.025Km** $\mathbf{e_{curvature} = 0.0785\ XY^2}$
X	1.780	2.345	
Y	2.435	1.870	

Find out the R.L. of unknown point. Comment on the errors associated with observations.

Solution :

The difference in elevation between X and Y is

$$\Delta h = \frac{(2.345 - 1.780) + (2.435 - 1.870)}{2} = 0.565 \text{ m (Y lower than X)}$$

R.L. of Y (unknown Point) = R.L. of X - Dh = 101.345 - 0.565 = 100.780 m

Since two leveling rods are used and the elapsed time between reading in a set observation is little, the error due to change in atmospheric condition can be neglected. Moreover, since readings were taken with instruments interchanged, instrumental errors get cancelled between different set of observation. As the observations are repeated and averages of the readings have been considered for further calculation, it is expected that error associated with observation is minimized thus removed. Only error present in the observation is that associated with the curvature of the earth.

4.15 Trilateration



In above Figure . The plane $z = 0$, showing the three sphere centers, $P1$, $P2$, and $P3$; their$x$,y-coordinates; and the three sphere radii, $r1$, $r2$, and $r3$. The two intersections of the three sphere surfaces are directly in front and directly behind the point designated intersections in the $z = 0$ plane.

In geometry, **trilateration** is the process of determining absolute or relative locations of points by measurement of distances, using the geometry of circles, spheres or triangles. In addition to its interest as a geometric problem, trilateration does have practical applications in surveying and navigation, including global positioning systems (GPS). In contrast to triangulation it does not involve the measurement of angles.

In two-dimensional geometry, it is known that if a point lies on two circles then the circle centers and the two radii provide sufficient information to narrow the possible locations down to two. Additional information may narrow the possibilities down to one unique location.

In three-dimensional geometry, when it is known that a point lies on the surfaces of three spheres then the centers of the three spheres along with their radii provide sufficient information to narrow the possible locations down to no more than two (unless the centres lie on a straight line).

This article describes a method for determining the intersections of three sphere surfaces given the centers and radii of the three spheres.

Contents

- 1 Derivation
- 2 Preliminary and final computations

Derivation

The intersections of the surfaces of three spheres is found by formulating the equations for the three sphere surfaces and then solving the three equations for the three unknowns, x, y, and z. To simplify the calculations, the equations are formulated so that the centers of the spheres are on the $z = 0$ plane. Also the formulation is such that one center is at the origin, and one other is on the x-axis. It is possible to formulate the equations in this manner since any three non-colinear points lie on a unique plane. After finding the solution it can be transformed back to the original three dimensional Cartesian coordinate system.

We start with the equations for the three spheres:

$$r_1^2 = x^2 + y^2 + z^2$$

$$r_2^2 = (x - d)^2 + y^2 + z^2$$

$$r_3^2 = (x - i)^2 + (y - j)^2 + z^2$$

We need to find a point located at (*x*, *y*, *z*) that satisfies all three equations.

First we subtract the second equation from the first and solve for *x*:

$$x = \frac{r_1^2 - r_2^2 + d^2}{2d}.$$

We assume that the first two spheres intersect in more than one point, that is that

$$d - r_1 < r_2 < d + r_1.$$

In this case substituting the equation for *x* back into the equation for the first sphere produces the equation for a circle, the solution to the intersection of the first two spheres:

$$y^2 + z^2 = r_1^2 - \frac{(r_1^2 - r_2^2 + d^2)^2}{4d^2}.$$

Substituting $z^2 = r_1^2 - x^2 - y^2$ into the formula for the third sphere and solving for *y* there results:

$$y = \frac{r_1^2 - r_3^2 - x^2 + (x - i)^2 + j^2}{2j} = \frac{r_1^2 - r_3^2 + i^2 + j^2}{2j} - \frac{i}{j}x.$$

Now that we have the *x*- and *y*-coordinates of the solution point, we can simply rearrange the formula for the first sphere to find the *z*-coordinate:

$$z = \pm\sqrt{r_1^2 - x^2 - y^2}.$$

Now we have the solution to all three points *x*, *y* and *z*. Because *z* is expressed as the positive or negative square root, it is possible for there to be zero, one or two solutions to the problem.

This last part can be visualized as taking the circle found from intersecting the first and second sphere and intersecting that with the third sphere. If that circle falls entirely outside or inside of the sphere, *z* is equal to thesquare root of a negative number: no real solution exists. If that circle touches the sphere on exactly one point, *z* is equal to zero. If that circle touches the surface of the sphere at two points, then *z* is equal to plus or minus the square root of a positive number.

Preliminary and final computations

The *Derivation* section pointed out that the coordinate system in which the sphere centers are designated must be such that (1) all three centers are in the plane $z = 0$, (2) the sphere center, $P1$, is at the origin, and (3) the sphere center, $P2$, is on the x-axis. In general the problem will not be given in a form such that these requirements are met.

This problem can be overcome as described below where the points, $P1$, $P2$, and $P3$ are treated as vectors from the origin where indicated. $P1$, $P2$, and $P3$ are of course expressed in the original coordinate system.

$\hat{e}_x = \frac{P2 - P1}{\|P2 - P1\|}$ is the unit vector in the direction from $P1$ to $P2$.

$i = \hat{e}_x \cdot (P3 - P1)$ is the signed magnitude of the x component, in the figure 1 coordinate system, of the vector from $P1$ to $P3$.

$\hat{e}_y = \frac{P3 - P1 - i\,\hat{e}_x}{\|P3 - P1 - i\,\hat{e}_x\|}$ is the unit vector in the y direction. Note that the points $P1$, $P2$, and $P3$ are all in the $z = 0$ plane of the figure 1 coordinate system.

The third basis unit vector is $\hat{e}_z = \hat{e}_x \times \hat{e}_y$. Therefore,

$d = \|P2 - P1\|$ the distance between the centers $P1$ and $P2$ and

$j = \hat{e}_y \cdot (P3 - P1)$ is the signed magnitude of the y component, in the figure 1 coordinate system, of the vector from $P1$ to $P3$.

Using i, d and j as computed above, solve for x, y and z as described in the *Derivation* section. Then

$$\vec{p}_{1,2} = P1 + x\,\hat{e}_x + y\,\hat{e}_y \pm z\,\hat{e}_z$$

gives the points in the original coordinate system since $\hat{e}_x$, $\hat{e}_y$ and $\hat{e}_z$, the basis unit vectors, are expressed in the original coordinate system.

Resection method

Resection is a method for determining a position (position finding) using a compass and topographic map (or nautical chart)

Resection versus intersection

Resection and its related method, intersection, are used in surveying as well as in general land navigation (including inshore marine navigation using shore-based landmarks). Both methods involve taking azimuths or bearings to two or more objects, then drawing lines of position along those recorded bearings or azimuths.

When intersecting lines of position are used to fix the position of an unmapped feature or point by fixing its position relative to two (or more) mapped or known points, the method is known asintersection.[3] At each known point (hill, lighthouse, etc.), the navigator measures the bearing to the same unmapped target, drawing a line on the map from each known position to the target. The target is located where the lines intersect on the map. In earlier times, the intersection method was used by forest agencies and others using specialized alidades to plot the (unknown) location of an observed forest fire from two or more mapped (known) locations, such as forest fire observer towers.

The reverse of the intersection technique is appropriately termed resection. Resection simply reverses the intersection process by using crossed back bearings, where the navigator's position is the unknown. Two or more bearings to mapped, known points are taken; their resultant lines of position drawn from those points to where they intersect will reveal the navigator's location.

Fixing a position

When resecting or fixing a position, the geometric strength (angular disparity) of the mapped points affects the precision and accuracy of the outcome. Accuracy increases as the angle between the two position lines approaches 90 degrees. Magnetic bearings are observed on the ground from the point under location to two or more features shown on a map of the area. Lines of reverse bearings, or lines of position, are then drawn on the map from the known features; two and more lines provide the resection point (the navigator's location). When three or more lines of position are utilized, the method is often popularly (though erroneously) referred to as triangulation (in precise terms, using three or more lines of position is still correctly called resection, as angular law of tangents (cot) calculations are not performed). When using a map and compass to perform resection, it is important to allow for the difference between the magnetic bearings observed and grid north (or true north) bearings (magnetic declination) of the map or chart.

Resection continues to be employed in land and inshore navigation today, as it is a simple and quick method requiring only an inexpensive magnetic compass and map/chart.

Resection in surveying

In surveying work, the most common methods of computing the coordinates of a point by resection are Cassini's Method and the Tienstra formula, though the first known solution was given byWillebrord Snellius (see Snellius–Pothenot problem). For the type of precision work involved in surveying, the unmapped point is located by measuring the angles subtended by lines of sight from it to a minimum of three mapped (coordinated) points. In geodetic operations the observations are adjusted for spherical excess and projection variations. Precise angular measurements between lines from the point under location using theodolites provides more accurate results, with trig beacons erected on high points and hills to enable quick and unambiguous sights to known points.

Caution: When planning to perform a resection, the surveyor must first plot the locations of the known points along with the approximate unknown point of observation. If all points, including the unknown point, lie close to a circle that can be placed on all four points, then there is no solution or the high risk of an erroneous solution. This is known as observing on the “danger circle”. The poor solution stems from the property of a chord subtending equal angles to any other point on the circle.

4.16 GPS

The **Global Positioning System** (**GPS**) is a space-based satellite navigation system that provides location and time information in all weather conditions, anywhere on or near the Earth where there is an unobstructed line of sight to four or more GPS satellites. The system provides critical capabilities to military, civil and commercial users around the world. It is maintained by the United States government and is freely accessible to anyone with a GPS receiver.

The GPS project was developed in 1973 to overcome the limitations of previous navigation systems, integrating ideas from several predecessors, including a number of classified engineering design studies from the 1960s. GPS was created and realized by the U.S. Department of Defense (DoD) and was originally run with 24 satellites. It became fully operational in 1994. Bradford Parkinson, Roger L. Easton, and Ivan A. Getting are credited with inventing it.

Advances in technology and new demands on the existing system have now led to efforts to modernize the GPS system and implement the next generation of GPS III satellites and Next Generation Operational Control System (OCX). Announcements from Vice President Al Gore and the White House in 1998 initiated these changes. In 2000, the U.S. Congress authorized the modernization effort, GPS III.

In addition to GPS, other systems are in use or under development. The Russian Global Navigation Satellite System (GLONASS) was developed contemporaneously with GPS, but suffered from incomplete coverage of the globe until the mid-2000s. There are also the planned European UnionGalileo positioning system, Chinese Compass navigation system, and Indian Regional Navigational Satellite System.

History

The design of GPS is based partly on similar ground-based radio-navigation systems, such as LORAN and the Decca Navigator, developed in the early 1940s and used during World War II.

Predecessors

In 1956, the German-American physicist Friedwardt Winterberg proposed a test of general relativity (for time slowing in a strong gravitational field) using accurate atomic clocks placed in orbit inside artificial satellites. Without the use of general relativity to correct for time running more quickly by 38 microseconds per day in orbit, GPS would suffer gross malfunction. Additional inspiration for GPS came when the Soviet Union launched the first man-made satellite, Sputnik, in 1957. Two American physicists, William Guier and George Weiffenbach, at Johns Hopkins's Applied Physics Laboratory (APL), decided to monitor Sputnik's radio transmissions. Within hours they realized that, because of the Doppler effect, they could pinpoint where the satellite was along its orbit. The Director of the APL gave them access to their UNIVAC to do the heavy calculations required. The next spring, Frank McClure, the deputy director of the APL, asked Guier and Weiffenbach to investigate the inverse problem—pinpointing the user's location given that of the satellite. (The Navy was developing the submarine-launched Polaris missile, which required them to know the submarine's location.) This led them and APL to develop the Transit system. In 1959, ARPA (renamed DARPA in 1972) also played a role in Transit. The first satellite navigation system, Transit, used by the United States Navy, was first successfully tested in 1960. It used a constellation of five satellites and could provide a navigational fix approximately once per hour. In 1967, the U.S. Navy developed the Timation satellite that proved the ability to place accurate clocks in space, a technology required by GPS. In the 1970s, the ground-based Omega Navigation System, based on phase comparison of signal transmission from pairs of stations, became the first worldwide radio navigation system. Limitations of these systems drove the need for a more universal navigation solution with greater accuracy.

While there were wide needs for accurate navigation in military and civilian sectors, almost none of those was seen as justification for the billions of dollars it would cost in research, development, deployment, and operation for a constellation of navigation satellites. During the Cold War arms race, the nuclear threat to the existence of the United States was the one need that did justify this cost in the view of the United States Congress. This deterrent effect is why GPS was funded. It is also the reason for the ultra secrecy at that time. The nuclear triad consisted of the United States Navy's submarine-launched ballistic missiles (SLBMs) along with United States Air Force (USAF) strategic bombers and intercontinental ballistic missiles (ICBMs). Considered vital to the nuclear-deterrence posture, accurate determination of the SLBM launch position was a force multiplier.

Precise navigation would enable United States submarines to get an accurate fix of their positions before they launched their SLBMs.[14] The USAF, with two thirds of the nuclear triad, also had requirements for a more accurate and reliable navigation system. The Navy and Air Force were developing their own technologies in parallel to solve what was essentially the same problem. To increase the survivability of ICBMs, there was a proposal to use mobile launch platforms (such as Russian SS-24 and SS-25) and so the need to fix the launch position had similarity to the SLBM situation.

In 1960, the Air Force proposed a radio-navigation system called MOSAIC (MObile System for Accurate ICBM Control) that was essentially a 3-D LORAN. A follow-on study, Project 57, was worked in 1963 and it was "in this study that the GPS concept was born". That same year, the concept was pursued as Project 621B, which had "many of the attributes that you now see in GPS" and promised increased accuracy for Air Force bombers as well as ICBMs. Updates from the Navy Transit system were too slow for the high speeds of Air Force operation. The Naval Research Laboratory continued advancements with their Timation (Time Navigation) satellites, first launched in 1967, and with the third one in 1974 carrying the first atomic clock into orbit.

Another important predecessor to GPS came from a different branch of the United States military. In 1964, the United States Army orbited its first Sequential Collation of Range (SECOR) satellite used for geodetic surveying. The SECOR system included three ground-based transmitters from known locations that would send signals to the satellite transponder in orbit. A fourth ground-based station, at an undetermined position, could then use those signals to fix its location precisely. The last SECOR satellite was launched in 1969. Decades later, during the early years of GPS, civilian surveying became one of the first fields to make use of the new technology, because surveyors could reap benefits of signals from the less-than-complete GPS constellation years before it was declared operational. GPS can be thought of as an evolution of the SECOR system where the ground-based transmitters have been migrated into orbit.

Development

With these parallel developments in the 1960s, it was realized that a superior system could be developed by synthesizing the best technologies from 621B, Transit, Timation, and SECOR in a multi-service program.

During Labor Day weekend in 1973, a meeting of about 12 military officers at the Pentagon discussed the creation of a Defense Navigation Satellite System (DNSS). It was at this meeting that "the real synthesis that became GPS was created." Later that year, the DNSS program was named Navstar, or Navigation System Using Timing and Ranging. With the individual satellites being associated with the name Navstar (as with the predecessors Transit and Timation), a more fully encompassing name was used to identify the constellation of Navstar satellites, Navstar-GPS, which was later shortened simply to GPS. After Korean Air Lines Flight 007, a Boeing 747 carrying 269 people, was shot down in 1983 after straying into the USSR's prohibited airspace, in the vicinity of Sakhalin and Moneron Islands, President Ronald Reagan issued a directive making GPS freely available for civilian use, once it was sufficiently developed, as a common good. The first satellite was launched in 1989, and the 24th satellite was launched in 1994. The GPS program cost at this point, not including the cost of the user equipment, but including the costs of the satellite launches, has been estimated to be about USD$5 billion (then-year dollars). Roger L. Easton is widely credited as the primary inventor of GPS.

Initially, the highest quality signal was reserved for military use, and the signal available for civilian use was intentionally degraded (Selective Availability). This changed with President Bill Clintonordering Selective Availability to be turned off at midnight May 1, 2000, improving the precision of civilian GPS from 100 meters (330 ft) to 20 meters (66 ft). The executive order signed in 1996 to turn off Selective Availability in 2000 was proposed by the U.S. Secretary of Defense, William Perry, because of the widespread growth of differential GPS services to improve civilian accuracy and eliminate the U.S. military advantage. Moreover, the U.S. military was actively developing technologies to deny GPS service to potential adversaries on a regional basis.

Over the last decade, the U.S. has implemented several improvements to the GPS service, including new signals for civil use and increased accuracy and integrity for all users, all while maintaining compatibility with existing GPS equipment.

GPS modernizationhas now become an ongoing initiative to upgrade the Global Positioning System with new capabilities to meet growing military, civil, and commercial needs. The program is being implemented through a series of satellite acquisitions, including GPS Block III and the Next Generation Operational Control System (OCX). The U.S. Government continues to improve the GPS space and ground segments to increase performance and accuracy.

GPS is owned and operated by the United States Government as a national resource. Department of Defense (DoD) is the steward of GPS. Interagency GPS Executive Board (IGEB) oversaw GPS policy matters from 1996 to 2004. After that the National Space-Based Positioning, Navigation and Timing Executive Committee was established by presidential directive in 2004 to advise and coordinate federal departments and agencies on matters concerning the GPS and related systems. The executive committee is chaired jointly by the deputy secretaries of defense and transportation. Its membership includes equivalent-level officials from the departments of state, commerce, and homeland security, the joint chiefs of staff, and NASA. Components of the executive office of the president participate as observers to the executive committee, and the FCC chairman participates as a liaison.

The DoD is required by law to "maintain a Standard Positioning Service (as defined in the federal radio navigation plan and the standard positioning service signal specification) that will be available on a continuous, worldwide basis," and "develop measures to prevent hostile use of GPS and its augmentations without unduly disrupting or degrading civilian uses."

Basic concept of GPS

A GPS receiver calculates its position by precisely timing the signals sent by GPS satellites high above the Earth. Each satellite continually transmits messages that include

- the time the message was transmitted
- satellite position at time of message transmission

The receiver uses the messages it receives to determine the transit time of each message and computes the distance to each satellite using the speed of light. Each of these distances and satellites' locations define a sphere. The receiver is on the surface of each of these spheres when the distances and the satellites' locations are correct. These distances and satellites' locations are used to compute the location of the receiver using the navigation equations. This location is then displayed, perhaps with a moving map display or latitude and longitude; elevation or altitude information may be included, based on height above the geoid (e.g. EGM96). Many GPS units show derived information such as direction and speed, calculated from position changes.

In typical GPS operation, four or more satellites must be visible to obtain an accurate result. Four sphere surfaces typically do not intersect. Because of this, it can be said with confidence that when the navigation equations are solved to find an intersection, this solution gives the position of the receiver along with the difference between the time kept by the receiver's on-board clock and the true time-of-day, thereby eliminating the need for a very large, expensive, and power hungry clock. The very accurately computed time is used only for display or not at all in many GPS applications, which use only the location. A number of applications for GPS do make use of this cheap and highly accurate timing. These include time transfer, traffic signal timing, andsynchronization of cell phone base stations.

Although four satellites are required for normal operation, fewer apply in special cases. If one variable is already known, a receiver can determine its position using only three satellites. For example, a ship or aircraft may have known elevation. Some GPS receivers may use additional clues or assumptions such as reusing the last known altitude, dead reckoning, inertial navigation, or including information from the vehicle computer, to give a (possibly degraded) position when fewer than four satellites are visible.

Structure

The current GPS consists of three major segments. These are the space segment (SS), a control segment (CS), and a user segment (US). The U.S. Air Force develops, maintains, and operates the space and control segments. GPS satellites broadcast signals from space, and each GPS receiver uses these signals to calculate its three-dimensional location (latitude, longitude, and altitude) and the current time. The space segment is composed of 24 to 32 satellites in medium Earth orbit and also includes the payload adapters to the boosters required to launch them into orbit. The control segment is composed of a master control station, an alternate master control station, and a host of dedicated and shared ground antennas and monitor stations. The user segment is composed of hundreds of thousands of U.S. and allied military users of the secure GPS Precise Positioning Service, and tens of millions of civil, commercial, and scientific users of the Standard Positioning Service (seeGPS navigation devices).

Space segment

The space segment (SS) is composed of the orbiting GPS satellites, or Space Vehicles (SV) in GPS parlance. The GPS design originally called for 24 SVs, eight each in three approximately circular orbits, but this was modified to six orbital planes with four satellites each. The six orbit planes have approximately 55° inclination (tilt relative to Earth's equator) and are separated by 60° right ascension of the ascending node (angle along the equator from a reference point to the orbit's intersection). The orbital period is one-half a sidereal day, i.e., 11 hours and 58 minutes so that the satellites pass over the same locations or almost the same locations every day. The orbits are arranged so that at least six satellites are always within line of sight from almost everywhere on Earth's surface. The result of this objective is that the four satellites are not evenly spaced (90 degrees) apart within each orbit. In general terms, the angular difference between satellites in each orbit is 30, 105, 120, and 105 degrees apart which sum to 360 degrees.

Orbiting at an altitude of approximately 20,200 km (12,600 mi); orbital radius of approximately 26,600 km (16,500 mi), each SV makes two complete orbits each sidereal day, repeating the same ground track each day. This was very helpful during development because even with only four satellites, correct alignment means all four are visible from one spot for a few hours each day. For military operations, the ground track repeat can be used to ensure good coverage in combat zones.

As of December 2012, there are 32 satellites in the GPS constellation. The additional satellites improve the precision of GPS receiver calculations by providing redundant measurements. With the increased number of satellites, the constellation was changed to a nonuniform arrangement. Such an arrangement was shown to improve reliability and availability of the system, relative to a uniform system, when multiple satellites fail. About nine satellites are visible from any point on the ground at any one time (see animation at right), ensuring considerable redundancy over the minimum four satellites needed for a position.

Control segment

The control segment is composed of

1. a master control station (MCS),
2. an alternate master control station,
3. four dedicated ground antennas and
4. six dedicated monitor stations

The MCS can also access U.S. Air Force Satellite Control Network (AFSCN) ground antennas (for additional command and control capability) and NGA (National Geospatial-Intelligence Agency) monitor stations. The flight paths of the satellites are tracked by dedicated U.S. Air Force monitoring stations in Hawaii, Kwajalein Atoll, Ascension Island, Diego Garcia, Colorado Springs, Colorado and Cape Canaveral, along with shared NGA monitor stations operated in England, Argentina, Ecuador, Bahrain, Australia and Washington DC.[65] The tracking information is sent to the Air Force Space Command MCS at Schriever Air Force Base 25 km (16 mi) ESE of Colorado Springs, which is operated by the 2nd Space Operations Squadron(2 SOPS) of the U.S. Air Force. Then 2 SOPS contacts each GPS satellite regularly with a navigational update using dedicated or shared (AFSCN) ground antennas (GPS dedicated ground antennas are located at Kwajalein, Ascension Island, Diego Garcia, and Cape Canaveral). These updates synchronize the atomic clocks on board the satellites to within a few nanoseconds of each other, and adjust the ephemeris of each satellite's internal orbital model. The updates are created by a Kalman filter that uses inputs from the ground monitoring stations, space weather information, and various other inputs.

Satellite maneuvers are not precise by GPS standards. So to change the orbit of a satellite, the satellite must be marked unhealthy, so receivers will not use it in their calculation. Then the maneuver can be carried out, and the resulting orbit tracked from the ground. Then the new ephemeris is uploaded and the satellite marked healthy again.

The Operation Control Segment (OCS) currently serves as the control segment of record. It provides the operational capability that supports global GPS users and keeps the GPS system operational and performing within specification.

OCS successfully replaced the legacy 1970s-era mainframe computer at Schriever Air Force Base in September 2007. After installation, the system helped enable upgrades and provide a foundation for a new security architecture that supported the U.S. armed forces. OCS will continue to be the ground control system of record until the new segment, Next Generation GPS Operation Control System (OCX), is fully developed and functional.

The new capabilities provided by OCX will be the cornerstone for revolutionizing GPS's mission capabilities, and enabling[67] Air Force Space Command to greatly enhance GPS operational services to U.S. combat forces, civil partners and myriad domestic and international users.

The GPS OCX program also will reduce cost, schedule and technical risk. It is designed to provide 50%[68] sustainment cost savings through efficient software architecture and Performance-Based Logistics. In addition, GPS OCX expected to cost millions less than the cost to upgrade OCS while providing four times the capability.

The GPS OCX program represents a critical part of GPS modernization and provides significant information assurance improvements over the current GPS OCS program.

- OCX will have the ability to control and manage GPS legacy satellites as well as the next generation of GPS III satellites, while enabling the full array of military signals.
- Built on a flexible architecture that can rapidly adapt to the changing needs of today's and future GPS users allowing immediate access to GPS data and constellations status through secure, accurate and reliable information.
- Empowers the warfighter with more secure, actionable and predictive information to enhance situational awareness.
- Enables new modernized signals (L1C, L2C, and L5) and has M-code capability, which the legacy system is unable to do.
- Provides significant information assurance improvements over the current program including detecting and preventing cyber attacks, while isolating, containing and operating during such attacks.
- Supports higher volume near real-time command and control capabilities and abilities.

On September 14, 2011, the U.S. Air Force announced the completion of GPS OCX Preliminary Design Review and confirmed that the OCX program is ready for the next phase of development.

The GPS OCX program has achieved major milestones and is on track to support the GPS IIIA launch in May 2014.

User segment

The user segment is composed of hundreds of thousands of U.S. and allied military users of the secure GPS Precise Positioning Service, and tens of millions of civil, commercial and scientific users of the Standard Positioning Service. In general, GPS receivers are composed of an antenna, tuned to the frequencies transmitted by the satellites, receiver-processors, and a highly stable clock (often a crystal oscillator). They may also include a display for providing location and speed information to the user. A receiver is often described by its number of channels: this signifies how many satellites it can monitor simultaneously. Originally limited to four or five, this has progressively increased over the years so that, as of 2007, receivers typically have between 12 and 20 channels.

GPS receivers may include an input for differential corrections, using the RTCM SC-104 format. This is typically in the form of an RS-232 port at 4,800 bit/s speed. Data is actually sent at a much lower rate, which limits the accuracy of the signal sent using RTCMReceivers with internal DGPS receivers can outperform those using external RTCM data] As of 2006, even low-cost units commonly include Wide Area Augmentation System (WAAS) receivers.

Many GPS receivers can relay position data to a PC or other device using the NMEA 0183 protocol. Although this protocol is officially defined by the National Marine Electronics

Association (NMEA), references to this protocol have been compiled from public records, allowing open source tools likegpsd to read the protocol without violating intellectual property laws. Other proprietary protocols exist as well, such as the SiRF andMTK protocols. Receivers can interface with other devices using methods including a serial connection, USB, or Bluetooth.

Applications

While originally a military project, GPS is considered a dual-use technology, meaning it has significant military and civilian applications.

GPS has become a widely deployed and useful tool for commerce, scientific uses, tracking, and surveillance. GPS's accurate time facilitates everyday activities such as banking, mobile phone operations, and even the control of power grids by allowing well synchronized hand-off switching.

Civilian

Astronomy: Both positional and clock synchronization data is used in Astrometry and Celestial mechanics calculations. It is also used in amateur astronomy using small telescopes to professionals observatories, for example, while finding extrasolar planets.

- Automated vehicle: Applying location and routes for cars and trucks to function without a human driver.
- Cartography: Both civilian and military cartographers use GPS extensively.
- Cellular telephony: Clock synchronization enables time transfer, which is critical for synchronizing its spreading codes with other base stations to facilitate inter-cell handoff and support hybrid GPS/cellular position detection for mobile emergency calls and other applications. The first handsets with integrated GPS launched in the late 1990s. The U.S. Federal Communications Commission (FCC) mandated the feature in either the handset or in the towers (for use in triangulation) in 2002 so emergency services could locate 911 callers. Third-party software developers later gained access to GPS APIs from Nextel upon launch, followed by Sprint in 2006, and Verizon soon thereafter.
- Clock synchronization: The accuracy of GPS time signals (±10 ns)[71] is second only to the atomic clocks upon which they are based.
- Disaster relief/emergency services: Depend upon GPS for location and timing capabilities.
- Fleet Tracking: The use of GPS technology to identify, locate and maintain contact reports with one or more fleet vehicles in real-time.
- Geofencing: Vehicle tracking systems, person tracking systems, and pet tracking systems use GPS to locate a vehicle, person, or pet. These devices are attached to the vehicle, person, or the pet collar. The application provides continuous tracking and mobile or Internet updates should the target leave a designated area.[72]
- Geotagging: Applying location coordinates to digital objects such as photographs (in exif data) and other documents for purposes such as creating map overlays with devices like Nikon GP-1
- GPS Aircraft Tracking

- GPS for Mining: The use of RTK GPS has significantly improved several mining operations such as drilling, shoveling, vehicle tracking, and surveying. RTK GPS provides centimeter-level positioning accuracy.
- GPS tours: Location determines what content to display; for instance, information about an approaching point of interest.
- Navigation: Navigators value digitally precise velocity and orientation measurements.
- Phasor measurements: GPS enables highly accurate timestamping of power system measurements, making it possible to compute phasors.
- Recreation: For example, geocaching, geodashing, GPS drawing and waymarking.
- Robotics: Self-navigating, autonomous robots using a GPS sensors, which calculate latitude, longitude, time, speed, and heading.
- Surveying: Surveyors use absolute locations to make maps and determine property boundaries.
- Tectonics: GPS enables direct fault motion measurement in earthquakes.
- Telematics: GPS technology integrated with computers and mobile communications technology in automotive navigation systems

Restrictions on civilian use

The U.S. Government controls the export of some civilian receivers. All GPS receivers capable of functioning above 18 kilometres (11 mi) altitude and 515 metres per second (1,001 kn) or designed, modified for use with unmanned air vehicles like e.g. ballistic or cruise missile systems are classified as munitions (weapons) for which State Department export licenses are required.

This rule applies even to otherwise purely civilian units that only receive the L1 frequency and the C/A (Coarse/Acquisition) code and cannot correct for Selective Availability (U.S. government discontinued SA on May 1, 2000, resulting in a much- improved autonomous GPS accuracy), etc.

Disabling operation above these limits exempts the receiver from classification as a munition. Vendor interpretations differ. The rule refers to operation at both the target altitude and speed, but some receivers stop operating even when stationary. This has caused problems with some amateur radio balloon launches that regularly reach 30 kilometres (19 mi).

These limits only apply to units exported from (or which have components exported from) the USA – there is a growing trade in various components, including GPS units, supplied by other countries, which are expressly sold as ITAR-free.

Military

As of 2009, military applications of GPS include:

- Navigation: GPS allows soldiers to find objectives, even in the dark or in unfamiliar territory, and to coordinate troop and supply movement. In the United States armed forces, commanders use the Commanders Digital Assistant and lower ranks use the Soldier Digital Assistant.

- Target tracking: Various military weapons systems use GPS to track potential ground and air targets before flagging them as hostile.]These weapon systems pass target coordinates to precision-guided munitions to allow them to engage targets accurately. Military aircraft, particularly in air-to-ground roles, use GPS to find targets (for example, gun camera video from AH-1 Cobras in Iraq show GPS co-ordinates that can be viewed with specialized software).
- Missile and projectile guidance: GPS allows accurate targeting of various military weapons including ICBMs, cruise missiles, precision-guided munitions and Artillery projectiles. Embedded GPS receivers able to withstand accelerations of 12,000 g or about 118 km/s^2 have been developed for use in 155 millimetres (6.1 in) howitzers. Search and Rescue: Downed pilots can be located faster if their position is known.
- Reconnaissance: Patrol movement can be managed more closely.
- GPS satellites carry a set of nuclear detonation detectors consisting of an optical sensor (Y-sensor), an X-ray sensor, a dosimeter, and an electromagnetic pulse (EMP) sensor (W-sensor), that form a major portion of the United States Nuclear Detonation Detection System. General William Shelton has stated that this feature may be dropped from future satellites in order to save money. Communicati**o**

Demodulation and decoding



Demodulating and Decoding GPS Satellite Signals using the Coarse/Acquisition Gold code.

Because all of the satellite signals are modulated onto the same L1 carrier frequency, the signals must be separated after demodulation. This is done by assigning each satellite a unique binary sequence known as a Gold code. The signals are decoded after demodulation using addition of the Gold codes corresponding to the satellites monitored by the receiver.

If the almanac information has previously been acquired, the receiver picks the satellites to listen for by their PRNs, unique numbers in the range 1 through 32. If the almanac information is not in memory, the receiver enters a search mode until a lock is obtained on one of the satellites. To obtain a lock, it is necessary that there be an unobstructed line of sight from the receiver to the satellite. The receiver can then acquire the almanac and determine the satellites it should listen for. As it detects each satellite's signal, it identifies it by its distinct C/A code pattern. There can be a delay of up to 30 seconds before the first estimate of position because of the need to read the ephemeris data.

Processing of the navigation message enables the determination of the time of transmission and the satellite position at this time. For more information see Demodulation and Decoding, Advanced.

Navigation equations

The receiver uses messages received from satellites to determine the satellite positions and time sent. The x, y, and z components of satellite position and the time sent are designated as [x_i, y_i, z_i, t_i] where the subscript i denotes the satellite and has the value 1, 2, ..., n, where $n \geq 4$. When the time of message reception indicated by the on-board clock is $\tilde{t}_\text{r}$, the true reception time is $t_\text{r} = \tilde{t}_\text{r} + b$ where b is receiver's clock bias (i.e., clock delay). The message's transit time is $\tilde{t}_\text{r} + b - t_i$. Assuming the message traveled at the speed of light, c, the distance traveled is $(\tilde{t}_\text{r} + b - t_i)\,c$. Knowing the distance from receiver to satellite and the satellite's position implies that the receiver is on the surface of a sphere centered at the satellite's position with radius equal to this distance. Thus the receiver is at or near the intersection of the surfaces of the four or more spheres. In the ideal case of no errors, the receiver is at the intersection of the surfaces of the spheres.

The clock error or bias, b, is the amount that the receiver's clock is off. The receiver has four unknowns, the three components of GPS receiver position and the clock bias [x, y, z, b]. The equations of the sphere surfaces are given by:

$$(x - x_i)^2 + (y - y_i)^2 + (z - z_i)^2 = \left([\tilde{t}_\text{r} + b - t_i]c\right)^2,\ i = 1, 2, \dots, n$$

or in terms of pseudoranges, $p_i = \left(\tilde{t}_\text{r} - t_i\right) c$, as

$$p_i = \sqrt{(x - x_i)^2 + (y - y_i)^2 + (z - z_i)^2} - bc,\ i = 1, 2, ..., n.$$

These equations can be solved by algebraic or numerical methods.

Least squares method

When more than four satellites are available, the calculation can use the four best or more than four, considering number of channels, processing capability, and geometric dilution of precision(GDOP). Using more than four is an over-determined system of equations with no unique solution, which must be solved by a least-squares method. Errors can be estimated through the residuals. With each combination of four or more satellites, a GDOP factor can be calculated, based on the relative sky directions of the satellites used. The location is expressed in a specific coordinate system or as latitude and longitude, using the WGS 84 geodetic datum or a country-specific system.

$$\left(\hat{x}, \hat{y}, \hat{z}, \hat{b}\right) = \underset{(x,y,z,b)}{\arg\min} \sum_i \left(\sqrt{(x - x_i)^2 + (y - y_i)^2 + (z - z_i)^2} - bc - p_i\right)^2$$

Bancroft's method

Bancroft's method involves an algebraic as opposed to numerical method and can be used for the case of four or more satellites. Bancroft's method provides one or two solutions for the four unknowns. However when there are two solutions, only one of these two solutions will be a near earth sensible solution. When there are four satellites, we use the inverse of the B matrix in section 2 of. If there are more than four satellites then we use the Generalized inverse (i.e. the pseudoinvers) of the B matrix since in this case the B matrix is no longer square.

Error sources and analysis

GPS error analysis examines the sources of errors in GPS results and the expected size of those errors. GPS makes corrections for receiver clock errors and other effects but there are still residual errors which are not corrected. Sources of error include signal arrival time measurements, numerical calculations, atmospheric effects, ephemeris and clock data, multipath signals, and natural and artificial interference. The magnitude of the residual errors resulting from these sources is dependent on geometric dilution of precision.

Artificial errors may result from jamming devices and threaten ships and aircraft.

Review Questions

1. What is Triangulation Surveying In **detail?**
2. **What is horizontal and vertical control method explain?**
3. **What is signals explain in detail?**
4. **Explain base line?**
5. **What are the** instruments and accessories extension of base lines?
6. **What is** Satellite station explain with digram?
7. **What is** Intervisibility of height and distances in satellite explain?
8. **What is** Trigonometric leveling ?
9. **What is** Axis single corrections explain?
10. **What are the application of satellite?**

Chapter 5

ENGINEERING SURVEYS

Structure of this unit

Reconnaissance, CURVES, CONTOUR

Learning Objectives

1. Reconnaissance
2. Preliminary and location surveys for engineering projects – layout – setting out works
3. CURVES : Curve ranging – Horizontal and Vertical curves – Simple curves –setting with chain and tapes,
4. Tangential angles by theodolite.
5. CONTOUR : Contouring – Methods – Characteristics and uses of contours – Plotting – Calculation of areas and volumes.

.

5.1 ENGINEERING SURVEYS

Engineering Surveys are a single source provider of survey services to the construction and Building industries. Operating from our base in Hong Kong we have a peak workforce of over 120 staff and have been involved in some of the largest infrastructure and building projects undertaken in the region over the last 10 years.

In addition to providing site surveying staff and equipment our vision is one of converging technologies where surveyors provide an increasingly diverse range of products and deliverables driven by the huge increase in quality and quantity of spatial data being collected.

From Topographic and Building Surveys to High Definition Laser Scanning and from CAD Drafting to 3D BIM Models the market for collecting and presenting spatial data has never been larger.

Engineering Surveys, as a multi-disciplined, single source provider of survey services are well placed to serve this market.

5.2 Reconnaissance

Reconnaissance is the military term for exploring beyond the area occupied by friendly forces to gain vital information about enemy forces or features of the environment for later analysis and/or dissemination.

Often referred to as recce (British and Canadian English) or recon (American English, Australian English), the associated verb isreconnoitre in British and Canadian English or reconnoiter in American English.

Examples of reconnaissance include patrolling by troops (LRRPs, Rangers, scouts, or military intelligence specialists), ships orsubmarines, manned/unmanned aircraft, satellites, or by setting up covert observation posts. Espionage normally is not reconnaissance, because reconnaissance is a military force's operating ahead of its main forces; spies are non-combatants operating behind enemy lines.

History

Traditionally, reconnaissance was a role that was adopted by the cavalry. Speed was key in these maneuvers, thus infantry was ill suited to the task. From horses to vehicles, for warriors throughout history, commanders procured their ability to have speed and mobility, to mount and dismount, during maneuver warfare. Military commanders favored specialized small units for speed and mobility, to gain valuable information about the terrain and enemy before sending the main (or majority) troops into the area, screening, covering force, pursuit and exploitation roles. Skirmishing is a traditional skill of reconnaissance, as well as harassment of the enemy.

Overview

Reconnaissance conducted by ground forces includes special reconnaissance, armored reconnaissance, amphibious reconnaissance and civil reconnaissance.

Aerial reconnaissance is reconnaissance carried out by aircraft (of all types including balloons and unmanned aircraft). The purpose is to survey weather conditions, map terrain, and may include military purposes such as observing tangible structures, particular areas, and movement of enemy forces.

Naval forces use aerial and satellite reconnaissance to observe enemy forces. Navies also undertake hydrographic surveys and intelligence gathering.

Reconnaissance satellites provide military commanders with photographs of enemy forces and other intelligence. Military forces also use geographical and meteorological information from Earth observation satellites.

Discipline

5.2.1 Types of reconnaissance:

1. **Terrain-oriented reconnaissance** is a survey of the terrain (its features, weather, and other natural observations).
2. **Force-oriented reconnaissance** focuses on the enemy forces (number, equipment, activities, disposition etc.) and may include target acquisition.
3. **Civil-oriented reconnaissance** focuses on the civil dimension of the battlespace (areas, structures, capabilities, organizations, people and events or ASCOPE).

The techniques and objectives are not mutually exclusive; it is up to the commander whether they are carried out separately or by the same unit.

Reconnaissance-in-force

Some military elements tasked with reconnaissance are armed only for self-defense, and rely on stealth to gather information. Others are well-enough armed to also deny information to the enemy by destroying their reconnaissance elements.

Reconnaissance-in-force (RIF) is a type of military operation or military tactics used specifically to probe an enemy's disposition. By mounting an offensive with considerable (but not decisive) force, the commander hopes to elicit a strong reaction by the enemy that reveals its own strength, deployment, and other tactical data. The RIF commander retains the option to fall back with the data or expand the conflict into a full engagement.

Other methods consist of hit-and-run tactics using rapid mobility, and in some cases light-armored vehicles for added fire superiority, as the need arises.

Reconnaissance-by-fire

Reconnaissance by fire (or speculative fire) is the act of firing at likely enemy positions, in order to cause the enemy force to reveal their location by moving or by returning fire.

Reconnaissance-pull

Reconnaissance-pull is a tactic that is applied at the regiment to division level and defined as locating and rapidly exploiting enemy weaknesses. It is the ability to determine enemy positions and create exploitable gaps through which friendly forces can pass while avoiding obstacles and strong points.

A textbook example of reconnaissance-pull was documented during the Tinian landings during World War II, utilized by the United States Marine Corps's Amphibious Reconnaissance Battalion, from V Amphibious Corps. Aerial photography, and the confirmation by the amphibious reconnaissance platoons determined that the Japanese defenders had largely ignored the northern beaches of the island focusing most of their defensive effort on beaches in the south-west which were more favorable for an amphibious landing. American forces quickly changed their landing location to the northern beaches and planned a small and hasty "deception" operation off the southern beach, which resulted in a complete surprise for the Japanese forces. As a result, American forces were able to fight the Japanese force on land where they had the advantage leading to light losses and a relatively short battle that lasted only 9 days.

Types

When referring to reconnaissance, a commander's full intention is to have a vivid picture of his battlespace. The commander organizes the reconnaissance platoon based on: 1) mission, 2) enemy, 3) terrain, 4) troops and support available, (5) time available, (6) and civil considerations. This analysis determines whether the platoon uses single or multiple elements to conduct the reconnaissance, whether it pertains to **area**, **zone**, or **route reconnaissance**, the following techniques may be used as long as the fundamentals of reconnaissance are applied.

Scouts may also have different tasks to perform for their commanders of higher echelons, for example: the engineer reconnaissance detachments will try to identify difficult terrain in the path of their formation, and attempt to reduce the time it takes to transit the terrain using specialist engineering equipment such as a pontoon bridge for crossing water obstacles. Sanitary epidemiological reconnaissance implies collection and transfer of all data available on sanitary and epidemiological situation of the area of possible deployment and action of armed forces, the same data for the neighboring and enemy armed forces. The aim for the reconnaissance is to clear up the reasons of the specific disease origin- sources of the infection in various extreme situations, including local wars and armed conflicts, the ways of the infection transfer and all factors promoting to the infestation.

After the armed forces have become stationary during wartime and emergency of peace time the sanitary epidemiological reconnaissance turns into sanitary and epidemiological surveillance and medical control of vital and communal activity of the armed forces .

Area

Area reconnaissance refers to the observation, and information obtained, about a specified location and the area around it; it may be terrain-oriented and/or force-oriented. Ideally, a reconnaissance platoon, or team, would use surveillance or vantage (static) points around the objective to observe, and the surrounding area. This methodology focuses mainly prior to moving forces into or near a specified area; the military commander may utilize his reconnaissance assets to conduct an area reconnaissance to avoid being surprised by unsuitable terrain conditions, or most importantly, unexpected enemy forces. The area could be a town, ridge-line, woods, or another feature that friendly forces intend to occupy, pass through, or avoid.

Within an Area of operation (AO), area reconnaissance can focus the reconnaissance on the specific area that is critical to the commander. This technique of focusing the reconnaissance also permits the mission to be accomplished more quickly. Area reconnaissance can thus be a stand-alone mission or a task to a section or the platoon. The commander analyzes the mission to determine whether the platoon will conduct these types of reconnaissance separately or in conjunction with each other.

Civil

Civil Reconnaissance is the process of gathering a broad spectrum of civil information about a specific population in support of military operations. It is related to and often performed in conjunction with infrastructure reconnaissance (assessment and survey). Normally the focus of collection in the operational area for civil reconnaissance is collecting civil information relating to the daily interaction between civilians and military forces. Civil information encompasses relational, temporal, geospatial and behavioral information captured in a socio-cultural backdrop. It is information developed from data related to civil areas, structures, capabilities, organizations, people, and events, within the civil component of the commander's operational environment that can be processed to increase situational awareness and understanding. The type of civil information that is needed in order to support military operations varies based on the environment and situation.

Route

Route reconnaissance is oriented on a given route: e.g. a road, a railway, a waterway; a narrow axis or a general direction of attack, to provide information on route conditions or activities along the route. A military commander relies on information about locations along his determined route: which those that would provide best cover and concealment; bridge by construction type, dimensions, and classification; or for landing zones or pickup zones, if the need arises.

In many cases, the commander may act upon a force-oriented route reconnaissance by which the enemy could influence movement along that route. For the reconnaissance platoons, or squads, stealth and speed —in conjunction with detailed intelligence-reporting—are most important and crucial. The reconnaissance platoon must remain far enough ahead of the maneuver force to assist in early warning and to prevent the force from becoming surprised.

Even it is paramount to obtain information about the available space in which a force can maneuver without being forced to bunch up due to obstacles.Terrain-oriented route reconnaissance allows the commander to obtain information and capabilities about the adjacent terrain for maneuvering his forces, to include, any obstacles (minefields, barriers, steep ravines, marshy areas, or chemical, biological, radiological, and nuclear contamination) that may obstruct vehicle movement—on routes to, and in, his assigned area of operations. This requirement includes the size of trees and the density of forests due to their effects on vehicle movement. Route reconnaissance also allows the observation for fields of fire along the route and adjacent terrain. This information assists planners as a supplement to map information.

Zone

Zone reconnaissance focuses on obtaining detailed information before maneuvering their forces through particular, designated locations. It can be terrain-oriented, force-oriented, or both, as it acquire this information by reconnoitering within—and by maintaining surveillance over—routes, obstacles (to include nuclear-radiological, biological, and chemical contamination), and resources within an assigned location.

Also, force-oriented zone reconnaissance is assigned to gain detailed information about enemy forces within the zone, or when the enemy situation is vague by which the information concerning cross-country traffic-ability is desired. The reconnaissance provides the commander with a detailed picture of how the enemy has occupied the zone, enabling him to choose the appropriate course-of-action.

As the platoon conducts this type of zone reconnaissance, its emphasis is on determining the enemy's locations, strengths, and weaknesses. This is the most thorough and complete reconnaissance mission and therefore is very time-intensive

The survey which is conducted for determining quantities and for collecting data for the designing of engineering works such as roads, railways, etc., is known as Engineering Survey.
Engineering survey have following types:

Reconnaissance* Survey

The Survey which is done for the feasibility* and rough cost of the project is known as Reconnaissance Survey.

Preliminary Survey

The survey in which more precise information is required for the choice of best location for the project and to estimate the exact quantities and costs of project is known as Preliminary Survey.

Location Survey

The survey for setting out the work on the ground is known as location survey.

Reconnaissance means military observation of an area to gain information.
Feasibility means either the project will complete or not.

5.3 Horizontal and Vertical curves

The center line of a road consists of series of straight lines interconnected by curves that are used to change the alignment, direction, or slope of the road. Those curves that change the alignment or direction are known as **horizontal curves,** and those that change the slope are **vertical curves.**

5.3.1 Horizontal Curve

When a highway changes horizontal direction, making the point where it changes direction a point of intersection between two straight lines is not feasible. The change in direction would be too abrupt for the safety of modem, high-speed vehicles. It is therefore necessary to interpose a curve between the straight lines. The straight lines of a road are called **tangents** because the lines are tangent to the curves used to change direction.

In practically all modem highways, the curves are **circular** curves; that is, curves that form circular arcs. The smaller the radius of a circular curve, the sharper the curve. For modern, high-speed highways, the curves must be flat, rather than sharp. That means they must be large-radius curves. In highway work, the curves needed for the location or improvement of small secondary roads may be worked out in the field. Usually, however, the

horizontal curves are computed after the route has been selected, the field surveys have been done, and the survey base line and necessary topographic features have been plotted. In urban work, the curves of streets are designed as an integral part of the preliminary and final layouts, which are usually done on a topographic map. In highway work, the road itself is the end result and the purpose of the design. But in urban work, the streets and their curves are of secondary importance; the best use of the building sites is of primary importance.

The principal consideration in the design of a curve is the selection of the length of the radius or the degree of curvature (explained later). This selection is based on such considerations as the design speed of the highway and the sight distance as limited by headlights or obstructions. Some typical radii you may encounter are 12,000 feet or longer on an interstate highway, 1,000 feet on a major thoroughfare in a city, 500 feet on an industrial access road, and 150 feet on a minor residential street.



.—Lines of sight

5.3.1.1 TYPES OF HORIZONTAL CURVES

There are four types of horizontal curves. They are described as follows:

1. SIMPLE. The simple curve is an arc of a circle. The radius of the circle determines the sharpness or flatness of the curve.

2. COMPOUND. Frequently, the terrain will require the use of the compound curve. This curve normally consists of two simple curves joined together and curving in the same direction

3. REVERSE. A reverse curve consists of two simple curves joined together, but curving in opposite direction. For safety reasons, the use of this curve should be avoided when possible

4. SPIRAL. The spiral is a curve that has a varying radius. It is used on railroads and most modem highways. Its purpose is to provide a transition from the tangent to a simple curve or between simple curves in a compound curve.

5.3.1.2 ELEMENTS OF A HORIZONTAL CURVE

The elements of a circular curve are shown in figure 11-3. Each element is designated and explained as follows:

PI POINT OF INTERSECTION. The point of intersection is the point where the back and forward tangents intersect. Sometimes, the point of intersection is designated as *V (vertex).*

I INTERSECTING ANGLE. The intersecting angle is the deflection angle at the *PI.* Its value is either computed from the preliminary traverse angles or measured in the field. A CENTRAL ANGLE. The central angle is the angle formed by two radii drawn from the

Figure



A SIMPLE CURVE B COMPOUND CURVE



C REVERSE CURVE D SPIRAL CURVE

Figure.—Horizontal curves.



Figure.—Elements of a horizontal curve.

center of the circle *(O)* to the *PC* and *PT.* The value of the central angle is equal to the *I* angle. Some authorities call both the intersecting angle and central angle either *I* or A. RADIUS. The radius of the circle of which the curve is an arc, or segment. The radius is always perpendicular to back and forward tangents.

POINT OF CURVATURE. The point of curvature is the point on the back tangent where the circular curve begins. It is sometimes designated as *BC* (beginning of curve) or *TC* (tangent to curve).

POINT OF TANGENCY, The point of tangency is the point on the forward tangent where the curve ends. It is sometimes designated as *EC* (end of curve) or *CT* (curve to tangent).

POC POINT OF CURVE. The point of curve is any point along the curve.

LENGTH OF CURVE. The length of curve is the distance from the *PC* to the *PT,* measured along the curve.

TANGENT DISTANCE. The tangent distance is the distance along the tangents from the *PI* to the *PC* or the *PT.* These distances are equal on a simple curve.

LONG CHORD. The long chord is the straight-line distance from the *PC* to the *PT.* Other types of chords are designated as follows: *C* The full-chord distance between adjacent stations (full, half, quarter, or onetenth stations) along a curve. *c]* The subchord distance between the *PC* and the first station on the curve.

c? The subchord distance between the last station on the curve and the *PT.*

EXTERNAL DISTANCE. The external distance (also called the external secant) is the distance from the *PI* to the midpoint of the curve. The external distance bisects the interior angle at the *PI.*

MIDDLE ORDINATE. The middle ordinate is the distance from the midpoint of the curve to the midpoint of the long chord. The extension of the middle ordinate bisects the central angle.

DEGREE OF CURVE. The degree of curve defines the sharpness or flatness of the curve.

DEGREE OF CURVATURE

The last of the elements listed above (degree of curve) deserves special attention. Curvature may be expressed by simply stating the length of the radius of the curve. That was done earlier in the chapter when typical radii for various roads were cited. Stating the radius is a common practice in land surveying and in the design of urban roads. For highway and railway work, however, curvature is expressed by the degree of curve. Two definitions are used for the degree of curve. These definitions are discussed in the following sections.

Degree of Curve (Arc Definition)

The arc definition is most frequently used in highway design. This definition, , states that the degree of curve is the central angle formed by two radii that extend from the center of a circle to the ends of an **arc** measuring 100 feet long (or 100 meters long if you are using metric units). Therefore, if you take a sharp curve, mark off a portion so that the distance along the arc is exactly 100 feet, and determine that the central angle is 12°, then you have a curve for which the degree of curvature is 12°; it is referred to as a 12° curve.

By studying, you can see that the ratio design speed and allowable superelevation. Then the between the degree of curvature *(D)* and 360° is the radius is calculated. same as the ratio between 100 feet of arc and the circumference *(C)* of a circle having the same radius. That may be expressed as follows:

$$\frac{D}{360^\circ} = \frac{100}{C}.$$

Since the circumference of a circle equals $2\pi R$, the above expression can be written as:

$$\frac{D}{360^\circ} = \frac{100}{2\pi R}.$$

Solving this expression for *R:*

$$R = \frac{5729.58}{D}$$

and also *D:*

$$D = \frac{5729.58}{R}.$$

For a 1° curve, *D* = 1; therefore *R* = 5,729.58 feet, or meters, depending upon the system of units you are using. In practice the design engineer usually selects the 5,729.65 feet, or meters, depending upon the system of degree of curvature on the basis of such factors as the design speed and allowable superelevation. Then the between the degree of curvature *(D)* and 360° is the radius is calculated.

Degree of Curve (Chord Definition)

The chord definition is used in railway practice and in some highway work. This definition states that the degree of curve is the central angle formed by two radii drawn from the center of the circle to the ends of a **chord** 100 feet (or 100 meters) long. If you take a flat curve, mark a 100-foot chord, and determine the central angle to be 0°30’, then you have a 30-minute curve (chord definition). From observation of figure 11-5, you can see the following trigonometric relationship:

$$\sin\left(\frac{D}{2}\right)=\frac{50}{R}.$$

Then, solving for R:

$$R=\frac{50}{\sin \frac{1}{2} D}.$$

For a 10 curve (chord definition), $D = 1$; therefore $R =$ In practice the design engineer usually selects the 5,729.65 feet, or meters, depending upon the system of degree of curvature on the basis of such factors as the units you are using. **Degree of curve (chord definition). 11-**



.—Degree of curve (chord definition).

Notice that in both the arc definition and the chord definition, the radius of curvature is inversely proportional to the degree of curvature. In other words, the larger the degree of curve, the shorter the radius; for example, using the arc definition, the radius of a 1° curve is 5,729.58 units, and the radius of a 5° curve is 1,145.92 units. Under the chord definition, the radius of a 1° curve is 5,729.65 units, and the radius of a 5° curve is 1,146.28 units.

5.4 CURVE FORMULAS

The relationship between the elements of a curve is expressed in a variety of formulas. The formulas for radius *(R)* and degree of curve *(D),* as they apply to both the arc and chord definitions, were given in the preceding discussion of the degree of curvature. Additional formulas you will use in the computations for a curve are discussed in the following sections.

Tangent Distance

Length of Curve By studying, you can see that the solution for the tangent distance *(T)* is a simple right-triangle solution. In the figure, both *T* and *R* are sides of a right triangle, with *T* being opposite to angle N2. Therefore, from your knowledge of trigonometric functions you know that

$$\tan\frac{\Delta}{2}=\frac{T}{R}$$

and solving for *T,*

$$T=R\tan\frac{\Delta}{2}.$$

Chord Distance

By observing figure 11-7, you can see that the solution for the length of a chord, either a full chord *(C)* or the long chord *(LC),* is also a simple right-triangle solution. As shown in the figure, *C/2* is one side of a right triangle and is opposite angle N2. The radius *(R)* is the hypotenuse of the same triangle. Therefore,

$$\sin\frac{\Delta}{2}=\frac{C/2}{R}$$

and solving for *C:*

$$C=2R\sin\frac{\Delta}{2}.$$

Length of Curve

In the arc definition of the degree of curvature, length is measured along the arc, In this figure the relationship between *D, & L,* and a 100-foot arc length may be expressed as follows:

$$\frac{L}{100} = \frac{\Delta}{D}.$$


PI
T
T
PC
90°
PT
R
Δ
Δ/2

–Tangent distance.


PC
C
PT
C/2
R
Δ/2

—Chord distance.


100'
L
Δ
D
A
100'
L
Δ
D
B

-Length of curve.

Then, solving for *L,*

$$L = 100 \frac{\Delta}{D}.$$

This expression is also applicable to the chord definition. However, *L.,* in this case, is not the true arc length, because under the chord definition, the length of curve is the sum of the chord lengths (each of which is usually 100 feet or 100 meters), As an example, if, as shown in view B, , the central angle (A) is equal to three times the degree of curve *(D),* then there are three 100-foot chords; and the length of “curve” is 300 feet.

Middle Ordinate and External Distance

Two commonly used formulas for the middle ordinate *(M)* and the external distance *(E)* are as follows

$$M = R\left(1 - \cos\frac{\Delta}{2}\right)$$

$$E = T\tan\frac{\Delta}{4} = R\left(\frac{1}{\cos \Delta/2} - 1\right).$$

DEFLECTION ANGLES AND CHORDS

From the preceding discussions, one may think that laying out a curve is simply a matter of locating the center of a circle, where two known or computed radii intersect, and then swinging the arc of the circular curve with a tape. For some applications, that can be done; for example, when you are laying out the intersection and curbs of a private road or driveway

with a residential street. In this case, the length of the radii you are working with is short. However, what if you are laying out a road with a 1,000- or 12,000- or even a 40,000-foot radius? Obviously, it would be impracticable to swing such radii with a tape. In usual practice, the stakeout of a long-radius curve involves a combination of turning **deflection angles** and measuring the length of chords *(C,* Cl, or CZ as appropriate). A transit is set up at the PC, a sight is taken along the tangent, and each point is located by turning deflection angles and measuring the chord distance between stations. This procedure In below figure, you see a portion of a curve that starts at the PC and runs through points (stations) A, B, and C. To establish the location of point A on this curve, you should set up your instrument at the PC, turn the required deflection angle (all/2), and then measure the required chord distance from PC to point A. Then, to establish point B, you turn deflection angle D/2 and measure the required chord distance from A to B. Point C is located similarly. As you are aware, the actual distance along an arc is greater than the length of a corresponding chord; therefore, when using the arc definition, either a correction is applied for the difference between arc



.-Deflection angles and chords.

length and chord length, or shorter chords are used to make the error resulting from the difference negligible. In the latter case, the following chord lengths are commonly used for the degrees of curve shown:

100 feet—0 to 3 degrees of curve
50 feet—3 to 8 degrees of curve
25 feet—8 to 16 degrees of curve
10 feet-over 16 degrees of curve

The above chord lengths are the maximum distances in which the discrepancy between the arc length and chord length will fall within the allowable error for taping. The allowable error is 0.02 foot per 100 feet on most construction surveys; however, based on terrain conditions or other factors, the design or project engineer may determine that chord lengths other than those recommended above should be used for curve stakeout. The following formulas relate to deflection angles: (To simplify the formulas and further discussions of deflection angles, the deflection angle is designated simply as *d* rather than *d/2.)*

$$d = \left(\frac{D}{2}\right)\left(\frac{C}{100}\right)$$

Where:

d = Deflection angle (expressed in degrees)
C = Chord length
D = Degree of curve
$d = 0.3\ CD$
Where:
d = Deflection angle (expressed in minutes)
C = Chord length
D = Degree of curve

$$\sin d = \frac{C}{2R}$$

5.5 SOLVING AND LAYING OUT A SIMPLE CURVE

Now let's solve and lay out a simple curve using the arc definition, which is the definition you will more often use as an EA. let's assume that the directions of the back and forward tangents and the location of the *PI* have previously been staked, but the tangent distances have not been measured. Let's also assume that stations have been set as far as Station 18 + 00. The specified degree of curve *(D) is* 15°, arc definition. Our job is to stake half-stations on the curve.

Solving a Simple Curve

We will begin by first determining the distance from Station 18 + 00 to the location of the *PI.* Since these points have been staked, we can determine the distance by field measurement. Let's assume we have measured this distance and found it to be 300.89 feet. Next, we set up a transit at the *PI* and determine that deflection angle *I* is 75°. Since *I* always equals A, then A is also 75°, Now we can compute the radius of the curve, the tangent distance, and the length of curve as follows:

$$R = 5{,}729.58/D = 381.97 \text{ ft}$$

$$T = R \tan \Delta/2 = 293.09 \text{ ft}$$

$$L = 100\ \Delta/D = 500 \text{ ft}$$

5.6 VERTICAL CURVES

In addition to horizontal curves that go to the right or left, roads also have vertical curves that go up or down. Vertical curves at a crest or the top of a hill are called **summit curves,** or **oververticals.** Vertical curves at the bottom of a hill or dip are called **sag curves,** or **underverticals.**

5.6.1 COMPUTING VERTICAL CURVES

As you have learned earlier, the horizontal curves used in highway work are generally the arcs of circles. But vertical curves are usually **parabolic.** The parabola is used primarily because its shape provides a transition and, also, lends itself to the computational methods described in the next section of this chapter. Designing a vertical curve consists principally of deciding on the proper length of the curve. the length of a vertical curve is the **horizontal distance** from the beginning to the end of the curve; the length of the curve is NOT the distance along the parabola itself. The longer a curve is, the more gradual the transition will be from one grade to the next; the shorter the curve, the more abrupt the change. The change must be gradual enough to provide the required sight distance. The sight distance requirement will depend on the speed for which the road is designed; whether passing or nonpassing distance is required; and other assumptions, such as one's reaction time, braking time, stopping distance, height of one's eyes, and height of objects. A typical eye level used for designs is 4.5 feet or, more recently, 3.75 feet; typical object heights are 4 inches to 1.5 feet. For a sag curve, the sight distance will usually not be significant during daylight; but the nighttime sight distance must be considered when the reach of headlights may be limited by the abruptness of the curve.



Elements of a vertical curve.

5.6.2 ELEMENTS OF VERTICAL CURVES

the elements of a vertical curve. The meaning of the symbols and the units of measurement usually assigned to them follow:

PVC	Point of vertical curvature; the place where the curve begins.
PVI	Point of vertical intersection; where the grade tangents intersect
PVT	Point of vertical tangency; where the curve ends.
POVC	Point on vertical curve; applies to any point on the parabola
POVT	Point on vertical tangent; applies to any point on either tangent
gI	Grade of the tangent on which the *PVC* is located; measured in percent of slope
g2	Grade of the tangent on which the *PVT* is located; measured in percent of slope.

The **algebraic difference** of the grades: G = g2 -g,, wherein plus values are assigned to uphill grades and minus values to downhill grades; examples of various algebraic differences are shown later in this section. Length of the curve; the **horizontal** length measured in 100-foot stations from the *PVC* to the PVT. This length may be computed using the formula ***L = G/r,*** where *r* is the rate of change (usually given in the design criteria). When the rate of change is not given, *L* (in stations) can be computed as follows: for a summit curve, **L = 125** x G/4; for a sag curve, **L = 100** x G/4. If *L* does not come out to a whole number of stations using these formulas, then it is usually extended to the nearest whole number. You should note that these formulas for length are for road design only, NOT railway.

L1 Horizontal length of the portion of the *PVC* to the *PVI;* measured in feet.
L2 Horizontal length of the portion of the curve form the *PVI* to the *PVT;* measured in feet. e Vertical (external) distance from the *PVI* to the curve, measured in feet. This distance is computed using the formula e **= LG/8,** where *L* is the total length in stations and G is the algebraic difference of the grades in percent.

5.7 Contour

CONTOUR

- Defined as the line of intersection of a level surface with the surface of ground.
- Lines drawn on the map to join points of the same height on the earth surface.
- The best method of representation of features such as hills etc.

CONTOUR INTERVAL

1. The constant height difference between two contour lines.
2. Depends upon the following factors:
    - The nature of the ground
    - The purpose and Extent of the survey
    - The scale of the map
    - Time and Expense of Field and Office work.

EXAMPLE OF CONTOUR INTERVAL

1. For large scale maps of flat country, for building sites for detailed design work
    - 0.2m to 0.5m
2. For reservoirs and town planning scheme.
    - 0.5m to 2m
3. For location surveys
    - 2m to 3m
4. For small scale maps of broken country and General Topographical work
    - 3m, 5m, 10m or 25m.

CHARACTERISTICS OF CONTOUR LINES

1. CONSAVE
2. CONVEX
3. VERTICAL SLOPE
4. CLIFF
5. VALLEY
6. HILL SPUR

USE OF CONTOUR MAP AND CONTOUR PLAN

1. Study original shape of the earth surface
2. Identify most suitable site and saving cost for engineer works
3. Identify water catchments area
4. Calculate capacity or volume of a pond
5. Identify volume of cut and fill
6. Identify intervisibility between two points
7. Identify the slope of road
8. Draw longitudinal section and cross section to view the shape of earth surface.

9. Calculate horizontal distance between contour lines.

METHOD OF CONTOURING

1. DIRECT METHOD

- The contours to be located are directly traced out in the field by locating and making a number of points on each contour

2. INDIRECT METHOD

- The points located and surveyed are not necessarily on the contour lines but the spot levels.
- GRID LEVEL METHOD
- CROSS SECTIONING METHOD
- SPOT HEIGHT METHOD

GRID LEVEL METHOD

- This method is most systematic and favoured by many because the contouring process is easy to understand.
- Suitable for flat and open survey area.

Contour maps are very useful since they provide valuable information about the terrain. Some of the uses are as follows:

i) The nature of the ground and its slope can be estimated

ii) Earth work can be estimated for civil engineering projects like road works, railway, canals, dams etc.

iii) It is possible to identify suitable site for any project from the contour map of the region.

iv) Inter-visibility of points can be ascertained using contour maps. This is most useful for locating communication towers.

v) Military uses contour maps for strategic planning.

the contour map, a common type of drawing in civil engineering. It is an ideal means of representing a threedimensional surface using a single two-dimensional view. Contour maps not only convey a qualitative impression of the features of the surface but also enable, using a single view, complete quantitative information to be extracted from the drawing. Although they are often used for topographic maps, contour maps have other applications that will be briefly mentioned in the article.

1. what it is

We will define what a contour map actually is by considering a simple example of representing a three-dimensional landform using only two dimensions.A three-dimensional surface is given. For example, we can consider a the landform shown in the figure to the right. The perspective view shown is obviously a two-dimensional representation of a threedimensional object. This conveys a reasonable qualitative impression of the overall characteristics of the landform, but it does have the following shortcomings:

1. Depending on the point from which the view is taken, we may miss valuable information. For example, when the landform is viewed to obtain the upper of the two views shown to the right, we have no information on what lies beyond the red line. We need to rotate to a different viewpoint to obtain this information.

2. There is no reliable way of extracting quantitative information from this drawing. For example, we may wish to know the elevation of a specific point on this landform or the difference in elevation between two given points. Not only is it difficult to locate a given point exactly in a horizontal plane, it is likewise difficult to gain more than a general impression of its elevation. It is thus not possible to use this drawing to answer questions such as "What is the elevation of a point 400 m to the north and 300 m to the east of Point A".We can solve the first problem to some extent by using multiple views of the same landform. This is shown in the figure to the right, where we have rotated the original viewpoint by approximately 90 degrees to obtain a second view. With the help of the second view, we can see what lies beyond the ridge. By selecting a sufficient number of views, we can generally provide a correct qualitative impression of the entire landform. The problem with this approach is that it is not compact, in the sense that one view is generally not enough. Furthermore, to be of value as a basis for extracting quantitative information, this approach also requires a means of relating one view to another. This is not a straightforward task

We can solve the second problem to some extent by identifying specific points and writing in the elevation of these points on the drawing. This has been done for two points in the drawing to the right. Elevations are given in metres above sea level. This increases the quantitative content of the drawing. If a sufficiently large number of such elevations were given, it would be possible to estimate, at least approximately, elevations of other points by interpolation. There is still no reliable quantitative basis, however, for locating points in the horizontal plane. It is practically impossible, for example, to know the distance and bearing of the point with elevation 1019 relative to the point with elevation 1178. Reliable answers to questions relating to the elevation of a point of known coordinates relative to a given point thus remain difficult to obtain. Neither providing multiple perspective views nor providing elevation values for given points thus allows us to represent the three dimensional surface using a single two-dimensional drawing that enables quantitative information to be extracted (i.e., the z coordinate of a point given its x and y coordinates).

To accomplish this objective, we need a more suitable two dimensional representation of the three dimensional surface. To develop this representation, we return to the previous perspective views. We first imagine that the landform has been sliced by a horizontal plane of constant elevation. In this case, say its elevation is 1000 m. Where this plane cuts the landform defines one or more curves in a horizontal plane. We can erase the plane itself but leave the line created by the intersection of the plane and the landform. This curve joints points of equal elevation. We define any curve joining points of equal elevation a contour line, or simply a contour

We can repeat this construction for planes at other elevations. For example, we can do so for planes with elevation 1100 m and 900 m. We can provide greater detail by showing more contour lines. In the lower view to the right, we have shown contours at increments of 20 m. We say that the contour interval in this drawing is 20 m. This contour interval appears to cover the landform reasonably well and capture the changes in topography. Although this drawing conveyssignificantly more information than the original perspective view given on the first page of this article, it is in itself is not particularly useful, since it has most of the shortcomings of the drawings developed initially. But it can be transformed into a powerful drawing by representingthis information on a horizontal plane

We do this by viewing the landform, with the contour lines, looking directly down from a point above it. By choosing this viewpoint, we gain a dimensionally true representation of the horizontal plane, which permits us to use true x-y coordinates to locate points. The vertical dimension disappears visually but is now represented in a more abstract way through the contour lines, which now appear to be drawn on a horizontal plane.A given point can now be located and measured in x-y coordinates from any other point on the map. Its elevation can be read directly from the contour that intersects the point or, for points located in between contours, by interpolation. For example, a point 500 m to the east and 500 m to the north of the origin in the lower left portion of the drawing (shown with the red dot) is found to have an elevation of approximately 1008 m

It is important that contour maps always incorporate a constant contour interval. By doing this, we can get a visual sense of the threedimensional properties of the surface, even when the shading of the original landform has been removed, by considering the patterns formed by the contours.The closest path from one contour line to an adjacent contour gives the steepest path. This follows directly from the definition of slope, which is equal to rise over run. For a constant rise (fixed contour interval), the greatest slope corresponds to the smallest value of run(closest distance between contours). It therefore follows that closely spaced contours denote regions that are steep and widely spaced contours are regions that are relatively flat.Closed curves denote either “hills” or “depressions”. We distinguish between the two by considering whether the contours are increasing or decreasing. In the case of the map shown to the right, the change of the contours indicates that the triangular figure enclosed by the green rectangle would be the top of a hill.



Landform with contours viewed from above. Contour interval is 20 m.

A series of adjacent contours that all “point” in the same direction often indicates the path of a river, since this corresponds to the landform created by the flow of water through the earth. The blue line drawn onto the map to the right indicates one possible river.We can summarize the essence of contour maps as follows. Contour maps allow us to represent three-dimensional surfaces using a single two-dimensional drawing. They maintain the ability to locate points accurately in two horizontal dimensions. Everything in these two dimensions is drawn to scale. We lose a direct means of visualizing the third dimension, but are able to represent it accurately through lines joining points of equal elevation, called contour lines. These are equivalent to the curve formed by intersecting the surface of the given landform with planes of constant elevation. By working with a constant contour interval, we gain the ability to visualize the three dimensional characteristics of the surface. The data used to generate the landform considered in this example originate from the National Map of Switzerland. The corresponding section of this map is shown in the figure to the right. The contour interval in this case is 10 m

2. suitable applications

Contour drawings are not the best way to represent all threedimensional objects. They are best suited to representing objects that have a single surface, a significant and well defined reference plane, and a significant third coordinate perpendicular to the reference plane.It follows from these conditions that contour drawings are well suited to the representation of landforms with a single two-dimensional drawing. They have a single surface (the surface of ground), a well defined reference plane (the horizontal plane) and a significant third coordinate perpendicular to the reference plane (the z coordinate represents elevation, which is of primary significance).Contour drawings are not suitable for representing other types of three dimensional objects when at least one of these conditions is not satisfied. The bridge pictured in the figure to the right, for example, does not have a single surface, but rather several including a near vertical surface, a far vertical surface, and an upper surface. A single contour diagram cannot adequately represent all of these surfaces. This type of object is best represented in other ways, such as with multiple views based on standard viewing planes. In these drawings only two dimensions are depicted in each view. No quantitative (and often no qualitative) information regarding the third coordinate can be extracted from a given view. For this reason, more than one view is required to describe the object completely.


TO CUMBERLAND
TO ROYSTON
PLAN
General Notes:
SECTION AT WEST ABUTMENT (LOOKING WEST)
100% COMPLETE RE-ISSUED JUNE 14, 1996
Province of British Columbia
MINISTRY OF TRANSPORTATION AND HIGHWAYS
VANCOUVER ISLAND HIGHWAY PROJECT
NORTH ISLAND DISTRICT
ROYSTON ROAD UNDERPASS BRIDGE NO. 3080
GENERAL ARRANGEMENT
BUCKLAND & TAYLOR LTD.

Bridge represented by multiple two-dimensional views

3. how to do it

There are several ways to produce contour drawings from a set of x, y, and z coordinates describing a given three-dimensional surface. This section describes one way that is relatively straightforward. Given:

1. A regular square grid of points, with x, y, and z coordinates of the surface defined for each point of the grid. This grid is shown in the image to the right. It has nine points. The scale in the horizontal plane is given graphically. Elevations in metres are given for each grid point.
Required: Produce a contour drawing representing the surface defined by the given x, y, and z coordinates.
How to proceed:

1. Set the contour interval. To do this, it is necessary first to scan the z coordinates to extract the minimum and maximum values. Within this range, define an interval that is regular and that captures the relevant features of the surface with good fidelity. In this case, regular means taken from the series 1 m, 2 m, 5 m, 10 m, 20 m, 50 m, 100 m, etc. When working with a set of several diagrams, it is usually preferable to use a constant contour interval over the entire set of diagrams to enable comparisons across the set of drawings. In such cases, the choice of interval should be made in consideration of the properties of the entire set of data.



Given information for contour map

For this example, the minimum and maximum elevations are 12 and 45 m respectively. For simplicity, we will use a contour interval of 10 m for this example. So relevant contours will be at the 20, 30, and 40 m elevations.

2. Draw the grid to a suitable scale. As always, use regular scales (i.e., from the series 1:1, 1:2, 1:5, 1:10, 1:20, 1:50, 1:100, etc...). In this case, this has already been done for us.

3. For easy reference, write in the z values next to the corresponding points of the grid. This has already been provided.

4. For each segment joining adjacent points of the grid, identify points of intersection of contour lines with the segment, based on the assumption that the change in z within a given segment of the grid is linear. Proceed according to the following example:

(a) Given: The top left horizontal segment AB of the grid has the following z values: z(A)=19.0 m, z(B)=22.0 m.

(b) So one contour will intersect this segment. It is the 20 m contour, since 19 < 20 < 22.



Locating intersection of contour and gridline

(c) Locate the point of intersection of the contour within this segment by linear interpolation. One straightforward way to accomplish this is to use a scale in a way similar to the method used to subdivide a line into several equal segments:

(i) On the vertical gridline passing through the left end point, align the scale to a value corresponding to the elevation at that location. In this case, the scale is set to 90.

(ii) On the vertical gridline passing through the right end point, align the scale to a value corresponding to the elevation at that location. In this case, the scale is set to 120. The scale remains at 90 along the left gridline. The series 90, 100, 110, 120 defined by the scale is similar to the series 19, 20, 21, 22 defined by the given elevations. So the intersection of the 20 m contour with the given line segment will correspond to 100 on the scale.

(iii)Draw a line perpendicular to the given segment corresponding to the point of intersection identified with the scale. This locates the intersection of the contour with the given segment.

(iv)Write the value of the contour next to the intersection point.

(v) Note: the accuracy of this procedure increases as the angle between the scale and Segment AB gets smaller. So it is usually helpful to try fitting several scales to the given segment to minimize this angle.

(vi)The outcome of this phase of the process is shown in the figure to the right.



Irregular situation: contour intersects grid square on four sides. There are several possible arrangements of contours, only one of which correctly represents the three dimensional figure shown

(d) When all of the points of intersection of contours and segments have been thus identified, draw the contour lines. Proceed on a square by square basis. For a given square bounded by four adjacent grid points, the following two cases must be considered:

(i) A given contour intersects exactly two bounding segments of the square. This is the case, for example, for the 20 m contour in the upper left-hand square. In this case, simply draw a line joining the points of intersection. This line is the path of the contour within the square. The image to the right shows the 20 m and the 30 m contours drawn for the upper left hand square in the grid.

(ii) A given contour intersects all four bounding segments of the square. In this case, it is not clear how to draw the contours. The figure to the right shows that a single arrangement of intersecting points can correspond to several arrangements of contours. In this case, only one arrangement (the middle one) corresponds to the given three-dimensional figure shown.

(e) The completed contours are shown in the figure to the right.

(f) Once the complete contour diagram has been drawn, trace the contours onto a new sheet of paper. This leaves only the contours and does not show the working grid and other marks that were made to produce them. It is generally necessary to label specific contours and spot elevations. As with all plan views (i.e. top views), a north arrow is required.



Completed contours (before tracing)

4. variations

In some cases, it is preferable to draw smooth curves for the contours. This will often provide a more realistic rendition of the features of a given landscape. All of the contour maps we will draw in this course will be done by straight line segments linking points of equal elevation along gridlines, as described in the previous section.It is common to create contour maps from survey data obtained in the field. In such cases, it is sometimes difficult to get elevation values for a square grid of points in the plane.

It is also possible to create a contour map following the principles outlined in the previous section for an irregular collection of points. In such a case, it is necessary to establish a triangular network of lines joining the available points in the plane. This is shown in the leftmost diagram. Along these lines, contour values are interpolated, as shown in the middle diagram. Finally, for a given triangle, straight line segments are drawn linking points on the boundary of identical contour value. This is shown in the rightmost diagram, where contour lines have been highlighted in green.



Contour mapping when points are not arranged on a square grid

5. examples from practice This section describes several types of contour drawing in common use in engineering.

5.1. Standard Topographic Maps Topographic maps describe, with a high level of detail and accuracy, the topography (i.e., the shape) of a given geographical area. The standard way of representing the three dimensional features of landforms is contour lines.

The first example is from Canada’s National Topographic System of maps. The most detailed scale available is 1:50 000.

The second example is from the National Map of Switzerland. This map is drawn to a scale of 1:50 000.

The third example is also from the National Map of Switzerland, this time from their 1:25 000 series.

The Swiss maps are produced with much greater detail and with additional visual cues to help the user gain a qualitative impression of the three-dimensional landforms from the contours.

This is accomplished by: (1) a relatively small contour interval (in this case 10 metres), (2) subtle shading that corresponds to the shadows that would be cast on the landforms when the sun shines from the northwest quadrant of the map, and (3) pictorial symbols such as the cliff symbol, which is used when the slope of the land is so steep as to cause excessive bunching of the contour lines

5.2. Project-specific topographic plans and diagrams When the level of detail given on standard topographic maps is insufficient, it is possible to produce topographic plans for a given site based on specific survey data. These plans are used, for example, for the layout of bridges. Inthis diagram, for example, the contour interval is 5 m, which is considerably less than the contour interval used on standard topographic maps.

This type of map will generally be prepared by a specialist land survey firm.Although contour diagrams are most often used to represent natural features such as topography, they are sometimes used to represent features of the facility to be built. Contour maps are sometimes made,
for example, of bridge decks to validate that drainage will work properly.

5.3. Contour graphs

It is also common to use contours to represent abstract surfaces, i.e., mathematical functions of two variables z=f(x,y). In such cases, x and y need to be spatial coordinates in a well defined and meaningful plane. Function z then defines a three-dimensional surface, similar to a landform.The same principles used to draw contour maps of physical landforms can be used to draw contour graphs of such functions.

The figure to the right shows one such application. This diagram is called an influence surface for a slab free along the bottom, fixed in shear and bending along the top, and extending to infinity in the other two directions. It is based on the function z = Ma(x,y), where A is a given fixed point and Ma is the bending moment at Point A due to a unit load applied at Point (x,y). It is the two-dimensional analog of the one-dimensional influence line.

This type of diagram can be used to calculate bending moments in bridge deck slabs due to loads applied by the wheels of a heavy truck. Its use is illustrated in the figure to the right.



Use of influence surfaces in calculating bending moments in cantilever bridge deck slabs

6. applications: cutting sections from contour maps

Contour maps are useful in and of themselves, but they are also used as a basis for producing relevant two-dimensional drawings. These can be visualized as the curve formed by the intersection of the given three dimensional surface and a vertical plane. The curve thus formed is often referred to as a section. The process of drawing this curve from a given contour map is referred to as cutting a section.



Setting up to cut section from contour map along Line A-A

A common application of sections cut from contour maps is the production of the elevation of a valley to be crossed by a bridge. The procedure for cutting such a section is relatively straightforward.

Given:
1. Contour map of the area under consideration
2. A straight line drawn on the contour map locating the vertical plane that defines the section (Line A-A).Required:

A two-dimensional drawing (x-z view) showing the shape of the landform along the given line.
How to proceed:

1. Draw a line parallel to Line A-A on a blank portion of the page. This will be the horizontal datum of the section to be cut.

2. Based on these maximum and minimum elevations intersected by Line A-A, draw a vertical scale of elevations to the left of, and perpendicular to, the horizontal datum. Provide suitable labels to this axis. Draw horizontal gridlines based on the labels given on the axis. The drawing to the right represents the progress thus far. The area just created is called the section diagram.

3. For each contour that intersects Line A-A, do the following:

(a) Identify the points of intersection of the contour and Line A-A. We will call one such point Point P1.

(b) Draw lines perpendicular to Line A-A from Points Pi to the section diagram. The outcome of this step is shown in the diagram to the right.

(c) Draw horizontal lines in the section diagram corresponding to the contour elevations.

(d) Identify the points of intersection Q1 for specific perpendiculars originating from the contours and the corresponding elevation in the section diagram.

4. Join the points Qi to form a continuous curve. The resulting curve is the section cut along Line A-A. The figure to the right shows the finished section cut along Line A-A. The location of one point of the profile is highlighted. It corresponds to the 1000 level contour.

Review Questions

1. Explain engineering surveyes?
2. What is Reconnaissance in detail?
3. What is Preliminary and location surveys for engineering projects explain?
4. What is curves?
5. Explain the all types of curves?
6. What is horizontal and vertical curves?
7. What is CONTOUR?
8. Describe the Contouring – Methods with detail?
9. What are the characteristics of contour method?
10. What are the uses of contour method?

“The lesson content has been compiled from various sources in public domain including but not limited to the internet for the convenience of the users. The university has no proprietary right on the same.”

Rai University
EVOLVING THINKING MINDS
Saroda Post, Dholka Taluka, District - Ahmedabad, Gujarat - 382260, India
www.raiuniversity.edu

U. S. DEPARTMENT OF COMMERCE
CHARLES SAWYER, Secretary

COAST AND GEODETIC SURVEY
LEO OTIS COLBERT, Director

Special Publication No. 242

DEFINITIONS OF TERMS USED IN GEODETIC AND OTHER SURVEYS

By

HUGH C. MITCHELL
Principal Mathematician (retired)

QB
275
.U35
no.242
1948

UNITED STATES
GOVERNMENT PRINTING OFFICE
WASHINGTON : 1948

For sale by the Superintendent of Documents, U.S. Government Printing Office
Washington, D.C. 20402 - Price $1

National Oceanic and Atmospheric Administration

ERRATA NOTICE

One or more conditions of the original document may affect the quality of the image, such as:

Discolored pages
Faded or light ink
Binding intrudes into the text

This has been a co-operative project between the NOAA Central Library and the Climate Database Modernization Program, National Climate Data Center (NCDC). To view the original document, please contact the NOAA Central Library in Silver Spring, MD at (301) 713-2607 x124 or www.reference@nodc.noaa.gov.

LASON
Imaging Contractor
12200 Kiln Court
Beltsville, MD 20704-1387
January 1, 2006

DEFINITIONS OF TERMS USED IN GEODETIC AND OTHER SURVEYS

INTRODUCTION

Recognizing the need for authoritative definitions of surveying and mapping terms, the Federal Board of Surveys and Maps in 1938 appointed a special committee to prepare such definitions. Confronted with an apparent choice of making a complete examination of the terminology employed in the large and ever-widening fields of surveying and mapping or of limiting its attention to terms for which there appeared a current need of definition, the committee decided to do both: to gather for study and future action material relating to any terms in which the members of the Board might have even a slight interest, but to give priority in its discussions and determinations to those terms for which there appeared a present need of definition. In following this program, a number of definitions were completed and reported to the Board. At the same time there was gathered into the files of the chairman of the special committee considerable material, diverse in character and incomplete, relating to other terms which it was hoped would eventually come before the committee for study and action.

The Federal Board of Surveys and Maps was abolished in March 1942 by Executive Order (No. 9094), and its Committee on Definitions of Surveying and Mapping Terms thereby discharged. At that time, comparatively few definitions in geodesy and geodetic surveying had been completed, and it was to provide such definitions that the work which the Committee had previously been performing was continued under the direction of Captain H. W. Hemple, Chief of the Division of Geodesy, U. S. Coast and Geodetic Survey. This publication was prepared in that Division, with the major part of the work being done by Hugh C. Mitchell. After Mr. Mitchell's retirement, a few minor changes and additions were made to incorporate suggestions received after the submission of copies of the manuscript to various authorities and interested persons.

It will be noted that for each term presented there is a basic definition or description directly following the name of the term. This is intended to contain all the elements and only the elements which are essential to a complete and accurate definition or description. For many terms there are also supplementary statements (set off in separate paragraphs), designed to facilitate the interpretation of the basic definition and to call attention to other uses that may have been made of the terms defined. A few supplementary statements also contain information of historical character which is sometimes desired but not always easy to find. The object of the supplementary statements is to make the report generally more useful. *Terms defined under another heading are italicized.*

Included in the publication are definitions which had been completed by the Committee on Definitions of the Federal Board of Surveys and Maps before its dismissal. These are identified by an asterisk (*). They were not acted upon by the Board. Included also are terms which might appear to have little relation to geodetic surveying, but the great advances of recent years in the use of geodetic data for the control of other surveys make it desirable that the geodetic engineer be familiar with the language of those who may use the data which he determines.

A

aberration: annual.—See under *aberration of light (astronomy)*.

chromatic.—See under *aberration of light (optics)*.

diurnal.—See under *aberration of light (astronomy)*.

spherical.—See under *aberration of light (optics)*.

aberration of light (astronomy).—The apparent displacement in position of a heavenly body which is due to the progressive motion (velocity) of light combined with the motion of the earth itself.

Aberration of light due to the *rotation* of the earth on its axis is termed diurnal aberration; its effect is considered in first-order determinations of *astronomical azimuth* and *longitude*, but not of *latitude*. Aberration due to the *revolution* of the earth about the sun is termed annual aberration.

aberration of light (optics).—The failure of light from a point on an object, after passing through a lens, to converge to a point on the image.

In a single lens having spherical surfaces, *aberration* may be caused by differences in the *focal lengths* of the various parts of the lens: rays passing through the outer part of the lens come to a *focus* nearer the lens than do rays passing through its central part. This is termed spherical aberration and, being due to the faulty figure of the lens, is eliminated by correcting that figure. A lens so corrected is called an *aplanatic lens*. Aberration may also result from differences in the wave lengths of light of different colors: light of the shorter wave lengths (violet end of the spectrum) comes to a *focus* nearer the lens than light of the longer wave lengths (red end of the spectrum). This is termed chromatic aberration, and is practically eliminated over a moderate range of wave lengths by using a composite lens, called an *achromatic lens*, composed of parts having different *dispersive powers*. See *refraction: index of refraction*.

absolute unit.—See under *unit*.

acceleration.—Rate of change of speed.

In the *c. g. s. system* of physical measurements, acceleration is expressed in terms of centimeters per second per second. See *gal*.

accessories: corner (United States public-land surveys).*—Physical objects adjacent to *corners*, to which such *corners* are referred for their future identification or restoration.

Accessories include *bearing trees*, mounds, pits, ledges, rocks, and other natural features to which distances or directions, or both, from the *corner* or *monument* are known. Strictly speaking, such accessories are a part of the monument.

accidental error.—See under *error*.

accumulated discrepancy.—See under *discrepancy*.

accumulated divergence (leveling).—See under *divergence*.

accuracy.*—Degree of conformity with a *standard*.

Accuracy relates to the quality of a result, and is distinguished from *precision* which relates to the quality of the operation by which the result is obtained.

The standard of reference may be (1) an exact value, such as the sum of the three *angles* of a plane triangle is 180°; (2) a value of a conventional *unit* as defined by a physical representation thereof, such as the *international meter*, defined by the *International Prototype Meter* (bar) at the National Bureau of Standards; (3) a survey or map value determined by refined methods and deemed sufficiently near the ideal or true value to be held constant for the control of dependent operations, such as the *adjusted elevation* of a *permanent bench mark* or the *graticule* of a *map projection*. The accuracy attained by field surveys is the product of the instructions to be followed in the execution of the work and the *precision* with which those instructions are followed.

achromatic lens.—A lens which transmits light without separating it into component colors.

An achromatic lens transmits light with a negligible amount of *chromatic aberration*. This is accomplished by means of lens elements of glass having different *indices of refraction*, so proportioned that the *chromatic aberration* in one element is compensated by that in another. Lenses that are made achromatic are usually also made *aplanatic*, that is, free of *spherical aberration*.

achromatic telescope.—A telescope having an *achromatic lens* for its object glass.

adjusted angle.—See under *angle*.

adjusted elevation.—See under *elevation*.

adjusted position.—See under *position*.

adjusted value.—See under *value*.

adjustment (leveling).—The determination and application of *corrections* to orthometric differences of elevation or to *orthometric elevations*, to make the *elevations* of all *bench marks* consistent and independent of the *circuit closures*.

adjustment: angle method of adjustment (triangulation and traverse).—A method of *adjustment of observations* which determines *corrections* to *observed angles*.

The angle method of adjustment may be used where a chain of single triangles is to be adjusted. For an extensive *triangulation* figure with overlapping triangles, the *direction method of adjustment* is preferred.

adjustment: collimation.—See under *collimation adjustment*.

adjustment: direction method of adjustment (triangulation and traverse).—A method of *adjustment of observations* which determines *corrections* to observed directions.

In the direction method, each *angle* is considered as the difference between two *directions,* for each of which a separate *correction* is determined. The direction method is used in the adjustment of *triangulation* figures which are composed of overlapping triangles, but for some work, where the survey consists of a chain of single triangles, the *angle method of adjustment* may be preferred.

adjustment: local.—See under *adjustment: station adjustment.*

adjustment: station.—The satisfying of conditions existing among *angles* as measured at a survey station. Also called local adjustment.

In a station adjustment, two kinds of conditions may require consideration: the sum of a series of measured *angles* closing the *horizon* may not equal exactly 360°; the sum of several contiguous *angles* measured separately may not equal the sum angle measured as a single *angle.* The term *observed angles* may be applied to the measured *angles* after they have been corrected by station adjustment.

adjustment correction (leveling).—See under *correction.*

adjustment of observations.—The determination and application of *corrections* corresponding to *errors* affecting the observations, making the observations consistent among themselves, and coordinating and correlating the derived data.

The object of *adjustment* is to provide the best (most probable) values of results obtainable from a series of survey observations, and to coordinate and correlate those results within the survey itself and with previously existing basic data. This is accomplished by mathematical analysis, as by the use of the *method of least squares;* or mechanically by graphical methods such as employed in plane-table surveying. The mathematical adjustment involves the solution of certain *condition equations* or *observation equations,* such as *angle equations, side equations, length equations,* and *latitude, longitude,* and *azimuth equations.* See, also, *adjustment: station.*

aerial map.—See under *chart: aeronautical chart.*

aerial navigation map.—See under *chart: aeronautical chart.*

aeronautical chart.—See under *chart.*

aeronautics.*—The science and art of navigation through the atmosphere.

air navigation chart.—See under *chart: aeronautical chart.*

air navigation map.—See under *chart: aeronautical chart.*

Airy theory of isostasy.—See under *isostasy.*

Aitoff equal-area map projection.—See under *map projection.*

Albers conical equal-area map projection.—See under *map projection.*

alidade.—The part of a surveying instrument which consists of a sighting device, with index, and reading or recording accessories.

The alidade of a *theodolite* or surveyor's *transit* is the upper part of the instrument: the *telescope, micrometer microscopes,* or *verniers,* and accessories, mounted on what is called the "upper motion" of the instrument, and used in observing a direction or angle on the graduated circle, which is mounted on the "lower motion."

The alidade used in topographic surveying consists of a straight-edge ruler carrying a *telescope* or other sighting device, and used in recording a direction on the *plane-table* sheet, which corresponds to the graduated circle of the *theodolite.* If a *telescope* is used, the instrument is often termed a *telescopic alidade.*

The movable arm of a sextant is an alidade.

alidade: telescopic.—A usual designation for an instrument composed of a *telescope* mounted on a straight-edge ruler, and used with a *plane table* in *topographic surveying.* See *alidade.*

alignment (alinement).—The placing of points along a straight line. Also, the location of points with reference to a straight line, or to a system of straight lines.

The use of the term alignment in surveying should be limited to operations associated with straight lines.

alignment: curve of.—See under *curve of alignment.*

alignment correction, tape.—See under *tape.*

almucantar.—Any small circle on the *celestial sphere* parallel with the *horizon.* Also termed parallel of altitude and circle of equal altitude.

alt-azimuth instrument.—An instrument equipped with both horizontal and vertical graduated circles, for the simultaneous observation of horizontal and vertical directions or angles.

The alt-azimuth instrument derives its name from the combination of the terms *altitude* and *azimuth.* Many *theodolites* and engineer's and surveyor's *transits* are alt-azimuth instruments; the *vertical circle* (instrument) used by the Coast and Geodetic Survey has a small horizontal circle as well as a larger, more *precise vertical circle,* and may be considered an alt-azimuth instrument, but the term is little used for surveying and mapping instruments. Its use may properly be restricted to designating an instrument of the *theodolite* type constructed for use in astronomical work, and sometimes called an astronomical theodolite or the universal instrument.

altimeter.—An *aneroid barometer* used for determining *elevations.*

altitude.—The *vertical angle* between the plane of the *horizon* and the line to the object which is observed or defined.

In astronomy and surveying, the altitude is positive if the object is above the *horizon,* and negative if below it. In surveying, a positive altitude is also termed an angle of elevation; a negative altitude, an angle of depression. In astronomy, altitude is the *complement* of the *zenith distance.* In photogrammetric surveying, altitude applies to *elevation* above *datum* of points in space.

altitude: circle of equal.—See under *almucantar.*

altitude: parallel of.—See under *almucantar.*

amplitude of vibration (pendulum).—The *arc* passed over by a *pendulum* in executing one *vibration.*

In the present use of the *Mendenhall pendulum,* the amplitude of vibration is measured in millimeters. In mathematics (harmonic analysis), the amplitude is the semi-arc or distance out from the mean position.

aneroid barometer.—See under *barometer.*

angle (general).—That relationship of lines or surfaces which is measured by the amount of *rotation* necessary to make one coincide with or parallel to another. See, also, *angle: solid.*

An angle may be expressed as a difference in directions of lines which lie: (1) In a plane, giving a *plane angle.* (2) In a curved surface, giving a *spherical angle, a spheroidal angle,* etc. (3) In two planes, measuring the inclination of one plane to the other, giving a *dihedral angle.*

In each case the magnitude of the angle is reckoned in units derived from a complete circumference of a circle. There are several systems of such units, of which the following are the most commonly used:

a) The degree ($^\circ$) is 1/360th part of a circumference, and is the unit of the sexagesimal system used in this country. The degree is divided into 60 minutes ($60'$), and the minute into 60 seconds ($60''$).

b) The hour (^{h}) is 1/24th part of a circumference, and is the unit used in the angular expression of time. The hour is related to the degree by the equation: $1^h=15^\circ$. The hour is divided into 60 minutes (60^m), and the minute into 60 seconds (60^s). [Note that in the sexagesimal system the symbols for minutes and seconds are ($'$) and ($''$), and in the time system the symbols for minutes and seconds are (^{m}) and (^{s}).] An angle expressed in $\_\_^\circ\ \_\_'\ \_\_''$ is said to be in *arc* measure; expressed in $\_\_^h\ \_\_^m\ \_\_^s$, in time measure.

c) The *grad* or *grade* (^{g}) is 1/400th part of a circumference, and is the unit of the centesimal system used in France. It is related to the degree by the equation: $100^g=90^\circ$. The *grad* is divided into 100 centesimal minutes (100‵); and a centesimal minute is divided into 100 centesimal seconds (100‶). While, as indicated above, the prime and double prime with reverse slant (‵,‶) are used to designate centesimal minutes and seconds, the common forms of the prime and double prime (′, ″) are used by some authors for the same purpose.

d) The radian (^{r}) is the angle at the center of a circle subtended by an *arc* having exactly the same length as the radius of the circle. One *radian* equals 360° divided by 2π or 57.30° approximately. Its value in seconds of *arc* is 206,205″. It is used in astronomy and navigation.

e) The mil is $\frac{1}{6400}$ part of a circumference; it subtends 0.98 (approximately 1) linear unit at a distance of 1000 such units. It is related to the degree by the equation: $1\ \text{mil}=0.05625^\circ$. It is used in military operations.

Sometimes, a particular angle may be defined by giving the length of chord which subtends the angle at a stated distance. Thus, the angle which 1 foot subtends at a distance of 39 miles is equal to 1″. This is often expressed by the following saying "A second is a foot at forty miles."

In surveying operations, an angle is classified in various ways, as follows:

1) According to the position or character of the surface in which it lies: *horizontal angle, vertical angle,* oblique angle, *spherical angle, spheroidal angle.*

2) According to the method by which it is obtained: *observed angle, concluded angle, adjusted angle.*

3) According to the function which it serves in the computation of the survey data: *distance angle, azimuth angle.*

4) According to the relative position it occupies in a geometric figure: *interior angle, exterior angle.*

angle: adjusted.—An *adjusted value* of an *angle.*

An adjusted angle may be derived from either an *observed angle* or from a *concluded angle.*

angle: azimuth (astronomy).—The *angle* less than 180° between the plane of the *celestial meridian* and the *vertical plane* containing the observed object, reckoned from the direction of the elevated pole.

In astronomic work, the azimuth angle is the *spherical angle* at the *zenith* in the *astronomical triangle,* pole-zenith-star. In geodetic work, it is the *horizontal angle* between the celestial pole and the observed terrestrial object.

angle: azimuth (surveying).—An *angle* in *triangulation* or in *traverse* through which the computation of *azimuth* is carried.

In a simple *traverse,* every *angle* may be an azimuth angle. Sometimes, in a *traverse,* to avoid carrying *azimuths* over very short lines, supplementary observations are made over comparatively long lines, the *angles* between which form azimuth angles.

In *triangulation,* certain *angles,* because of their size and position in the figure, are selected for use as azimuth angles, and enter into the formation of the *azimuth condition equation* (*azimuth equation*).

angle: complement of.—The difference between an *acute angle* and one right *angle* (90°).

angle: concluded.—An *interior angle* between adjacent sides of a closed figure, which is obtained by subtracting the sum of all the other *interior angles* of the figure from the theoretical value of the sum of all the *interior angles.*

The concluded angle is most frequently met with in triangulation, where it is obtained by subtracting the sum of two known *angles* of a triangle from 180° plus the *spherical excess* of the triangle.

angle: deflection.—A *horizontal angle* measured from the prolongation of the preceding line, right or left, to the following line.

angle: dihedral.—An *angle* between two planes.

A dihedral angle is measured in a plane perpendicular to the line of intersection of the planes forming the *angle,* and is acute, right, oblique, or straight according to the nature of the plane angle which represents it.

angle: direct.—See under *angle to right.*

angle: distance.—An *angle* in a triangle opposite a side used as a base in the solution of the triangle, or a side whose length is to be computed.

In a chain of single triangles, as the computation proceeds through the chain, two sides in each triangle are used: a known side and a side to be determined: the *angles* opposite these sides are the distance angles.

angle: explement of.—The difference between an *angle* and four right angles (360°).

angle: exterior.—The *angle* between any side of a polygon and adjacent side extended.

Exterior angle is also used to designate the outside *angles* formed by a line intersecting two parallel lines. It has likewise been used in surveying to designate the *explement* of an *angle.* This latter use is rare.

angle: horizontal.—An *angle* in a horizontal plane.

The directions may be to objects in the horizontal plane; or they may be the lines of intersection of the horizontal plane with the *vertical planes* containing the objects.

angle: interior.—An *angle* between adjacent sides of a closed figure, measured by the *arc* connecting those sides on the inside of the closed figure.

The three *angles* of a triangle are interior angles.

angle: observed.—An *angle* obtained by direct instrumental observation.

A measured *angle* which has been corrected for local conditions (see *adjustment: station*) only at the point of observation, is considered an observed angle.

angle: parallactic.—See under *astronomical triangle.*

angle: refraction.—See under *refraction angle.*

angle: solid.—The integrated angular spread at the vertex of a cone, pyramid, or other solid figure.

The unit of measure of a solid angle is the steradian, a solid angle at the center of a sphere which is subtended by a portion of the surface of the sphere having an area equal to the square of the radius of the sphere.

angle: spherical.—An *angle* between *great circles* on a sphere.

A spherical angle is measured either: a) by the *dihedral angle* of the planes of *great circles* or b) by the plane angle between tangents to *great circles* at their intersection.

angle: spheroidal.—An *angle* between two curves on a *spheroid,* measured by the *angle* between their tangents at the point of intersection.

angle: supplement of.—The difference between an *angle* and two right angles (180°).

angle: vertical.—An *angle* in a *vertical plane.*

In surveying, one of the directions which form a vertical angle is usually either (a) the direction of the *vertical* (*zenith*), and the *angle* is termed the *zenith distance;* or (b) the line of intersection of the *vertical plane* in which the *angle* lies with the plane of the *horizon,* and the *angle* is termed the *angle of elevation* or *angle of depression,* or simply the *altitude* (plus or minus, as the case may be). The vertical angle between two directions, neither of which lies in the plane of the *horizon* or coincides with the *vertical,* is usually obtained from the combination of two vertical angles as defined above.

angle equation.—See under *equation.*

angle method of adjustment (triangulation and traverse).—See under *adjustment.*

angle of depression.—See under *altitude.*

angle of elevation.—See under *altitude.*

angle of incidence.—See under *refraction of light.*

angle of inclination.—An *angle of elevation* or an *angle of depression.* See *altitude.*

angle of refraction.—See under *refraction of light.*

angle to right.—The *horizontal angle* measured clockwise from the preceding line to the following one.

angles: repetition of.—See under *repetition of angles.*

annual aberration.—See under *aberration of light* (*astronomy*).

annual parallax.—See under *parallax.*

anomalistic month.—See under *month.*

anomalistic year.—See under *year.*

anomaly (astronomy).—The *angle* at the sun between the radius vector of a planet and the *line of apsides* of its orbit, reckoned from *perihelion.*

The term defined above is also called the true anomaly, when it is desired to distinguish it from the eccentric anomaly, which is the corresponding angle at the center of the orbit; or from the mean anomaly, which is what the true anomaly would become if the planet had a uniform angular motion.

anomaly (general).—A deviation from a norm.

anomaly (geodesy).—A deviation of an observed value from a theoretical value, due to an abnormality in the observed quantity.

anomaly: Bouguer.—A difference between an observed value of *gravity* and a theoretical value at the point of observation, which has been corrected for the effect of *topography* only, the topography being considered as resting on a plane of indefinite extent.

In practice, a Bouguer *anomaly* is obtained through a series of approximations. First, the *topography* is treated as an indefinite slab of a thickness equal to the elevation of the station above *sea level,* the rate of change of *gravity* with elevation depending upon the assumed density of the slab, and being about five-eighths the normal value of that ratio. This first approximation gives the main part of the *anomaly.* The determination of the effect of this indefinite slab is the first step in the Hayford-Bullard (or Bullard) method of isostatic reduction.

Second, allowance is made for the departure of the actual *topography* from the indefinite slab. This correction is usually small. The distance out from the station for which it is computed is a matter of convenience; while no precise rule has been adopted for selecting this distance, it has been suggested that it should increase with elevation of station. The practice in the United States Coast and Geodetic Survey is to compute this second correction out to Zone O of the Hayford divisions of the surface of the earth, that is, 166.7 kilometers or about 100 miles out from the station. See *template* (*templet*).

A third approximation is sometimes made by taking account of the curvature of the sea-level surface. The numerical value of this correction is small, unless the computation is carried to a great distance from the station. In the work of the United States Coast and Geodetic Survey, no account is taken of this correction and, according to Helmert, it should not be used. However, reasons have been advanced favoring its inclusion in a complete computation of a Bouguer anomaly.

For use in reducing *gravity* observations to obtain even an approximate approach to a theoretical value, the Bouguer method has proved of little or no value. It ignores *isostatic compensation* and creates large fictitious *anomalies;* it neglects large amounts of matter existing between the *geoid* and the *spheroid;* and it takes no account of actual *topography* beyond the limited distance used in the computation of the second correction (above). It has, however, proved useful to oil companies in their geophysical investigations: if Bouguer anomalies are available at a number of stations within a limited area, values of this *anomaly* at other points within the area can be obtained by interpolation, and from these, serviceable values of *gravity* are obtained by computation.

The use of the pendulum in determining the figure of the earth came in at about the beginning of the nineteenth century, and with that use came the application of Bouguer's rule for the reduction of gravity observations. The method continued in favor until Clarke and Helmert, applying the theories of Pratt and Airy which are now known as the principle of *isostasy,* showed that it did not come anywhere near producing reliable values of theoretical gravity. Its present use is limited to theoretical studies and to the practical application given above.

The Bouguer anomaly derives its name from the French mathematician, Pierre Bouguer (1698–1758), who did not develop the method itself, but who proposed the rule or formula expressing the effect of a slab of indefinite extent, as considered in making the first approximation (above). In its time, the Bouguer rule has also borne the names of Young (Thomas Young, 1773–1829) and Poisson (Simon Denis Poisson, 1781–1840).

anomaly: deflection.—The difference between an uncorrected value of the *deflection of the vertical* as determined by observation and the value after being corrected in accordance with certain assumptions made with reference to the physical condition of the *geoid.*

The term deflection anomaly is seldom used. As it applies to the *residuals* obtained from solutions of equations set up in conformity with some adopted theory of distribution of mass in the outer part of the earth's crust, the term *residual* is more generally used, qualified, if need be, by a designation of the particular solution through which it was obtained.

anomaly: free-air.—The difference between observed gravity and theoretical gravity which has been computed for latitude and corrected for elevation of the station above the geoid, by application of the normal rate of change of gravity for change of elevation, as in free air.

The elevation correction is for height above the *geoid,* not the *spheroid,* the relation of which to the *geoid* is practically always unknown. No correction is applied for the effect of topography and isostatic compensation.

anomaly: gravity.—The difference between the observed value of gravity at a point and the theoretical value, in the sense, observed minus theoretical.

The theoretical value may be obtained in various ways. See *anomaly: free-air; anomaly: Bouguer; anomaly: isostatic.* The point at which the two values of gravity are compared is commonly either the point of observation or a point on the geoid directly under (or above) the point of observation.

The value of the gravity anomaly is the same for either point of comparison. However, in framing a definition, it is desirable to adopt one convention or the other. In the United States, since one of the purposes of the isostatic studies of the U. S. Coast and Geodetic Survey has been to explain observed gravity, the point of observation has been used as the point of comparison. Elsewhere, the almost universal practice has been to take the point on the *geoid* directly below (or above) the point of observation, even for isostatic studies, since the original use of gravity observations was to determine the *flattening of the earth:* this fact has determined the convention adopted for defining gravity anomaly.

If we knew the relation between the geoid and the spheroid of reference (a formula for theoretical gravity implies a spheroid of reference), we could reduce gravity to the spheroid of reference: this is often done in theoretical investigations.

When it is desired to explain the observed value of gravity by some theory, it is natural to take the point of observation as the point of comparison. If, on the other hand, it is desired to use observations of gravity to determine the figure of the earth, the natural point of comparison is the point on the geoid directly below (or above) the point of observation. For studies of this sort, it is necessary to reduce all observations to a common level surface.

anomaly: isostatic.—The difference between an observed value of *gravity* and a theoretical value at the point of observation which has been corrected for elevation of the station above the geoid and for the effect of *topography* over the whole earth and for its *isostatic compensation.*

The present procedure is to compute the *isostatic compensation* according to the *Pratt theory of isostasy* as developed by Hayford, using various depths for purposes of comparative analysis. Isostatic anomalies obtained by the above procedure are sometimes called Hayford gravity anomalies or, simply, Hayford anomalies. Other types of isostatic anomaly may be distinguished by the author's basic assumptions and designated by the author's name, as Meinesz anomaly, Heiskanen anomaly, etc.

Antarctic Circle.—The *geographic parallel* having a south *latitude* equal to the *complement* of the *declination* of the *winter solstice.*

The *obliquity of the ecliptic* is steadily changing, so that the *winter solstice* is not a point of fixed *declination,* and the Antarctic Circle as defined above is not a line of fixed position. When the Antarctic Circle is to be shown on a *map,* it is desirable that it be treated as a line of fixed position, and a conventional value adopted for its *latitude.* For this purpose, the value 66°33′ south *latitude* is here proposed. This is the *complement* of 23°27′, proposed for the *latitude* of the *Tropic of Capricorn.*

The area enclosed by the Antarctic Circle is called the "South Frigid Zone," and at all points in this area, at the time of the *winter solstice,* the sun is above the *horizon* at local midnight. The belt of the earth's surface bounded by the Antarctic Circle and the *Tropic of Capricorn* is called the "South Temperate Zone." See *Arctic Circle.*

aphelion.—The point in an elliptical orbit of a planet or comet remotest from the sun.

aplanatic lens.—A lens which transmits light without *spherical aberration.*

apparent (visible) horizon.—See under *horizon.*

apparent solar day.—See under *day.*

apparent solar time.—See under *time.*

apparent time.—See under *time.*

approximate.—Approaching closely but not attaining a specified *accuracy* or a *precision* conformable with the quality of the observations.

Too few observations or observations made with an inferior instrument will give an approximate result.

Omitted corrections or the neglect of terms having significant values will produce an approximate result, even where the observations themselves are satisfactory.

apsides: line of.—See under *line of apsides.*

arc (general).—A portion of a mathematically defined curve.

A circular arc is part of a circle; an elliptical arc, part of an ellipse; etc.

arc correction (pendulum).—The quantity which is applied to the period of *vibration* of a *pendulum* to allow for the *pendulum's* departure from simple harmonic motion.

With a *pendulum,* the *acceleration* is proportional to the sine of the *amplitude,* while the displacement is proportional to the *amplitude* itself. The *arc* is the quantity obtained by observation, and it is slowly changing; the *acceleration* is the quantity sought. By limiting the size of the *amplitude,* the correction required to take account of this non-isochronous condition is kept quite small.

arc triangulation.—See under *triangulation.*

Arctic Circle.—The *geographic parallel* having a north *latitude* equal to the *complement* of the *declination* of the *summer solstice.*

The *obliquity of the ecliptic* is steadily changing so that the *summer solstice* is not a point of fixed *declination,* and the Arctic Circle as defined above is not a line of fixed position. When the Arctic Circle is to be shown on a *map,* it is desirable that it be treated as a line of fixed position, and a conventional value adopted for its *latitude.* For this purpose, the value 66°33′ north latitude is here proposed. This is the *complement* of 23°27′, proposed for the *latitude* of the *Tropic of Cancer.*

The area enclosed by the Arctic Circle is called the "North Frigid Zone," and at all points in this area, at the time of the *summer solstice,* the sun is above the *horizon* at local midnight. The belt of the earth's surface bounded by the Arctic Circle and the *Tropic of Cancer* is called the "North Temperate Zone."

Actually, when an observer sees the sun at a *solstice* just touch the *horizon* at local midnight, without setting, he is probably much nearer to the 66th parallel of latitude than to the one proposed above for cartographic use. This is an effect of *atmospheric refraction.* It is modified by local conditions, including *dip of horizon.*

area triangulation.—See under *triangulation.*

arithmetical mean.—The value obtained by dividing the sum of a series of values by the number of values in the series. See *weighted mean.*

artificial horizon.—See under *horizon.*

A-stations (traverse).—*Subsidiary stations* established between *principal stations* of a *survey traverse,* for convenience of measuring, to obtain the distance between the *principal stations.*

A-stations are established along a route which is not straight, as along a curved section of a railroad, where the length measures must be carried through a series of short *straight lines,* while *azimuth* control may be carried through widely spaced *stations.* The A-stations form a traverse loop with the line connecting the *principal stations,* the distance between which is obtained by projecting the measured lengths of the short lines onto that main line. See *equation: perpendicular* (*traverse*). A-stations are so-called because in a given series, these stations are designated by the name of a *principal station* followed by the letters A, B, C, etc., in order of distance from the *principal station.* They are sometimes referred to as "A, B, C stations."

astrolabe.—An instrument for measuring *altitudes* of celestial objects. See under *astrolabe: pendulum astrolabe; planispheric astrolabe; prismatic astrolabe.*

Derived from Greek words meaning "to take a star," the term astrolabe has been used to designate a great variety of instruments, of which the three named above are of especial interest to surveyors and map makers.

astrolabe: pendulum.—An astronomical instrument using a constant altitude for position determination. Its distinctive feature is a mirror suspended on top of a pendulum to form the *artificial horizon.*

The instrument consists of a V-shaped casting carrying the objective and eyepiece lenses at the ends of the arms. The mirror, which rests on top of the pendulum and forms the level surface (artificial horizon), is located at the intersection of the V. The pendulum is suspended so that it is free to swing in either of two planes at right angles to each other, such as north-south and east-west planes. The pendulum is highly damped so that the mirror comes to rest quickly and remains steady under normal observing conditions.

astrolabe: planispheric.—An *astrolabe* of ancient origin, consisting of a full graduated circle with a centrally mounted *alidade,* and accessory adjustable plates on which are engraved *stereographic projections* of the heavens and of the sphere for local *latitudes.*

The instrument is held suspended in a *vertical plane,* the *altitude* of a star is observed with the aid of the *alidade,* and the projection-bearing plates are so adjusted that, with the data available, what are essentially graphical solutions of astronomical problems are effected.

astrolabe: prismatic.—An *astrolabe* consisting of a *telescope* in a horizontal position, with a prism and *artificial horizon* attached at its objective end, used for determining *astronomic positions.*

The usual form of this instrument employs a 60° prism, with the face nearest the objective perpendicular to the *line of collimation* of the *telescope;* a small mercurial horizon is attached to the instrument beneath the prism. In observing, two images of a star are seen: one reflected directly into the *telescope* by the lower face of the prism; the other reflected first by the mercurial horizon, then by the upper face of the prism into the *telescope.* These two images of the same star are moving in opposite directions, and at the instant of the coincidence, the star is at the apparent *altitude* of the prism angle. Prismatic astrolabes may be made with the angle between the two inclined at other than 60° An English instrument employs a 45° *angle,* and has accessory means of obtaining more than one observation for a given setting.

astronomic; astronomical.—Of or pertaining to astronomy, the science which treats of the heavenly bodies, and the art based on that science.

For particular usage of the two forms, astronomic, astronomical, see *-ic*; *-ical.*

astronomic azimuth.—See under *azimuth.*

astronomic azimuth mark.—See under *azimuth mark.*

astronomic coordinates.—See under *coordinates.*

astronomic equator.—See under *equator.*

astronomic latitude.—See under *latitude.*

astronomic longitude.—See under *longitude.*

astronomic meridian.—See under *meridian.*

astronomic parallel.—See under *parallel.*

astronomic position.—See under *latitude: astronomic; longitude: astronomic.*

astronomical day.—See under *day.*

astronomical leveling.—See under *leveling.*

astronomical refraction.—See under *refraction.*

astronomical theodolite.—See under *alt-azimuth instrument.*

astronomical time.—See under *time.*

astronomical transit.—See under *transit.*

astronomical traverse.—See under *traverse.*

astronomical triangle.—The triangle on the *celestial sphere* formed by *arcs* of *great circles* connecting the celestial pole, the *zenith,* and a celestial body.

The *angles* of the astronomical triangle are: at the pole, the *hour angle;* at the celestial body, the parallactic angle; at the *zenith,* the *azimuth angle.* The sides are: pole to *zenith,* the *co-latitude; zenith* to celestial body, the *zenith distance;* and celestial body to pole, the *polar distance.*

astronomical unit.—The mean distance of the earth from the sun; that is, the semi-major axis of the elliptical orbit described by the earth around the sun, equal to about 149,500,000 kilometers (Smithsonian Physical Tables, 1934).

While the above simple definition is generally used in technical and popular publications, mathematical astronomers find it convenient to adopt a highly technical definition involving the use of a constant (k^2) introduced by Gauss to define the *acceleration* of the sun's gravitational field, and in particular the exact value of k^2 used by Gauss, although the astronomical data used by him to determine it differ slightly from the best modern values.

The *solar parallax* is a measure of the astronomical unit, and in some astronomical calculations it is convenient to use the *solar parallax* in place of the astronomical unit.

asymmetry of object (target).—Lack of symmetry in the visible aspect of an object as seen from a particular point of observation.

A square or rectangular pole may so face the observer that the line bisecting its tangents does not pass through its geometrical center. With a square cupola or tower, the *error* resulting from observing tangents and taking a mean may be quite large. The *error* due to asymmetry of object observed on is of the same character and requires the same treatment as *error* due to observing on an *eccentric object.* Asymmetry and *phase* are closely associated, but are not identical.

atmospheric refraction.—See under *refraction.*

authalic (equal-area) latitude.—See under *latitude.*

autogonal map projection.—See under *map projection.*

autumnal equinox.—See under *equinox.*

auxiliary guide meridian (United States public-land surveys).—See under *meridian.*

auxiliary standard parallel (United States public-land surveys).—See under *parallel.*

average error.—See under *error.*

aviation chart.—See under *chart: aeronautical chart.*

aviation map.—See under *chart: aeronautical chart.*

axis of lens (lens axis).—See under *principal axis.*

axis of level; axis of level bubble.—See under *level axis: spirit level axis.*

azimuth (general).——The *horizontal direction* reckoned clockwise from the meridian plane. See specific definition for *azimuth: astronomic; azimuth: geodetic; azimuth: grid;* etc.

In the basic control surveys of this country, azimuths are measured clockwise from south following the continental European geodetic practice. However, this practice is not followed in all countries.

azimuth: astronomic.—At the point of observation, the *angle* measured from the *vertical plane* through the celestial pole to the vertical plane through the observed object.

Astronomic azimuth is the *azimuth* which results directly from observations on a celestial body: it is measured in the plane of the *horizon,* and is usually reckoned from south (0°), through west (90°), north (180°), and east (270°), back to south (360° or 0°). It is affected by the local *deflection of the vertical* (*station error*) which, in the United States, produces differences between astronomic and *geodetic azimuths* of as much as 26″ in the mountain regions of the west, and of 10″ in the less rugged eastern States.

Astronomic azimuths may also be reckoned clockwise from north through 360°. In navigation, they are sometimes reckoned clockwise or counter-clockwise through 180°, from the south in the southern hemisphere, and from the north in the northern hemisphere. In recording an astronomic azimuth it is essential that both the initial and the direction of reckoning be indicated.

azimuth: back.—See under *azimuth: geodetic.*

azimuth: direction method, determination of astronomic azimuth.—The determination of the *astronomic azimuth* of a line by measuring with a *direction theodolite* the *horizontal angle* between a selected star and a suitable mark, and applying that *angle* to the *azimuth* of the star computed for the epoch of the observation.

In the horizontal *control surveys* of continental United States, the direction method of azimuth determination is preferred over other methods. A circumpolar star is observed at any *hour angle,* the mark being a signal light on a *main-scheme station* or at a station, called an *azimuth mark,* established for the purpose. A *correction for inclination of the horizontal axis,* depending upon the *altitudes* of the star and of the mark, is applied to the observed *angle,* and *curvature correction* and *corrections* for *variation of the pole* and for *diurnal aberration* also enter into the computation.

azimuth: forward.—See under *azimuth: geodetic.*

azimuth: geodetic.—For the *geodesic line* from A to B, the angle between the tangent to the *meridian* at A and the tangent to the geodesic line at A. In the U. S. Coast and Geodetic Survey, this angle is measured clockwise from south, but see under *azimuth (general).*

This azimuth is called the forward azimuth for the line AB. The angle between the tangents to the meridian and to the geodetic line at B is called the back azimuth for the line AB. Because of the *convergence of the meridians,* the forward and backward azimuths of a line do not differ by exactly 180°, except where the two end points have the same *geodetic longitude* or where the *geodetic latitudes* of both points are 0°.

The geodesic line is not, except in special cases, a plane curve, but for short lines (of the length commonly used in triangulation) one may neglect the small difference between the geodesic line and the plane curve actually observed.

azimuth: grid.—The *angle* in the plane of projection between a straight line and the central meridian (axis of Y) of a *plane-rectangular coordinate system.*

In the *State plane-coordinate systems* established by the U. S. Coast and Geodetic Survey, grid azimuths are reckoned from south (0°) clockwise through 360°. While essentially a *map* quantity, a grid azimuth may, by mathematical process, be transformed into a *survey* or ground quantity. See *gisement.*

azimuth: Laplace.—A *geodetic azimuth* derived from an *astronomic azimuth* by means of the *Laplace equation.*

It is proposed that the symbol a_L be adopted to designate a Laplace azimuth, to distinguish it from a *geodetic azimuth* derived by computation through the triangulation, which is represented by the symbol a_G.

See *Laplace equation.*

azimuth: magnetic.—At the point of observation, the *angle* between the *vertical plane* through the observed object and the *vertical plane* in which a freely suspended symmetrically magnetized needle, influenced by no transient artificial magnetic disturbance, will come to rest.

Magnetic azimuth is generally reckoned from magnetic north (0°) clockwise through 360°. Such an *azimuth* should be marked as being magnetic, and the date of its applicability be given.

azimuth: method of repetitions, determinations of astronomic azimuth.—The determination of the *astronomic azimuth* of a line by accumulating on the horizontal circle of a *repeating theodolite* the sum of a series of measures of the *horizontal angle* between a selected star and a suitable mark, and applying the mean of such measures to the *azimuth* of the star computed for the mean epoch of the observations.

The method of repetitions for the determination of *azimuth* is theoretically susceptible of great *accuracy* and *precision,* but in practice is not as satisfactory as the *direction method.*

A *correction for inclination of the horizontal axis,* depending on the *altitudes* of the star and of the mark, is applied to the observed *angle,* and *curvature correction* and *corrections* for *variation of the pole* and for *diurnal aberration* also enter into the computations.

azimuth: micrometer method, determination of astronomic azimuth.—The determination of the *astronomic azimuth* of a line by measuring indirectly with an *ocu-*

lar micrometer attached to a *theodolite* or *transit* the *horizontal angle* between a selected star at its elongation and a suitable ground mark (light) placed close to the *vertical plane* which passes through the star, and applying that *angle* to the *azimuth* of the star computed for the epoch of the observation.

At elongation, the apparent motion in *azimuth* of a close circumpolar star like Polaris is very small for an appreciable period of time, and a series of observations can be made by the micrometer method without reorienting the instrument. A *correction for inclination of the horizontal axis,* depending on the *altitudes* of the star and of the mark, is applied to the *observed angle,* and *curvature correction* and corrections for *variation of the pole* and for *diurnal aberration* also enter into the computations. Recently, difficulties in determining *astronomic azimuth* in Alaska, due to the large *altitude* of circumpolar stars, were overcome by employing the micrometer method with a *Bamberg broken-telescope transit.*

azimuth: normal section.—For the *normal section line* from A to B, the *angle* at A between the meridian plane and the normal section which passes through B.

azimuth angle (astronomy).—See under *angle.*

azimuth angle (surveying).—See under *angle.*

azimuth equation.—See under *equation.*

azimuth line.—See under *azimuth plane.*

azimuth mark: astronomic.—A signal or target whose *astronomic azimuth* from a survey station is determined from direct observations on a celestial body.

The mark may be a lamp or illuminated target placed especially for the purpose; or it may be a signal lamp at another survey station.

azimuth mark: geodetic.—A marked point established in connection with a *triangulation* (or *traverse*) *station* to provide a starting *azimuth* for dependent surveys.

The *geodetic azimuth* from the station to the azimuth mark is determined instrumentally; its distance is often determined only approximately, but should be sufficiently great to render negligible the angular effect of the ordinary *errors* of centering instrument and target. Since 1928, azimuth marks consisting of bronze tablets set in concrete or stone have been established in connection with the basic horizontal *control survey* of the United States. These marks are usually so located as to be readily available without special construction to elevate either instrument or target. At a station having an established azimuth mark, both the *geodetic azimuth* and the *grid azimuth* of the mark on the *State coordinate system* are computed and published.

azimuth mark: Laplace.—An *astronomic azimuth mark* at a *Laplace station.*

azimuth plane.—Any *vertical plane.*

Such a plane cuts an azimuth section from the *spheroid,* and traces an azimuth line on its surface. These terms are rarely seen and their use should be avoided. Although the *vertical planes* containing the prime vertical and the *meridian* are sometimes regarded as not being azimuth planes, they are special cases of that term as here defined.

azimuth section.—See under *azimuth plane.*

azimuthal (zenithal) map projection.—See under *map projection.*

azimuthal equidistant map projection.—See under *map projection.*

B

Bache-Wurdeman base-line measuring apparatus.—See under *base apparatus.*

back azimuth.—See under *azimuth: geodetic.*

backsight (general).—A sight on a previously established survey point.

backsight (leveling).—A reading on a rod held on a point whose *elevation* has been previously determined, and which is not the closing sight of a level circuit.

In leveling, a *backsight* is sometimes called a plus sight, because it is usually added to the *elevation* of the rod point to obtain the height of the instrument (H. I.). This is not always the case: the pointing may be on a mark on a wall or in the roof of a mine tunnel, with the instrument at a lower *elevation.* In such a case, the *backsight* will be subtracted from the known *elevation* to obtain the height of instrument. The term *backsight* is preferred over plus sight.

backsight (transit traverse).—A sight on a previously established survey point, which is not the closing sight of the *traverse.*

balancing a survey.—Distributing *corrections* through a *traverse,* to eliminate the *errors of closure.*

Errors of closure may arise when a *traverse* closes upon itself or when it extends between points of known *position.* *Corrections* to balance the *closing errors* are distributed through the *traverse* according to some approved method, so that the resulting survey figure will be geometrically consistent: the *position* and *azimuth* at the closing point as derived by computation carried through the balanced *traverse* will agree with the starting data for a *closed traverse* or with the fixed data where the *traverse* extends between fixed points. For an extended *traverse,* the elimination of errors may be made by the *method of least squares,* and the operation is termed an *adjustment.* For local work, the elimination of *errors* may be made by one of two standard methods, and is termed balancing the survey. These methods are termed *compass rule* and *transit rule.*

balancing a survey, compass rule.—*Corrections* corresponding to the *closing errors* in *latitude* and *departure* are distributed according to the proportion: length of line to total length of *traverse.*

The compass rule is used when it is assumed that the *closing errors* are as much due to *errors* in *observed angles* as to *errors* in measured distances.

balancing a survey, transit rule.—*Corrections* corresponding to the *closing errors* in *latitude* and *departure* are distributed according to the proportion: *latitude* and *departure* of each line of the *traverse* to the arithmetical sums of the *latitudes* and *departures* of the entire *traverse.*

The transit rule is used when it is assumed that the *closing errors* are due less to the *errors* in the *observed angles* than to *errors* in the measured distances.

Bamberg broken-telescope transit.—See under *transit: broken-telescope.*

bank of stream.—The continuous margin along a river where all vegetation ceases.

The right bank of a stream is the bank on the right-hand side, and the left bank, the one on the left-hand side, as one proceeds in the direction in which the current flows (downstream).

Barlow leveling rod.—See under *leveling rod.*

barometer.—An instrument for measuring atmospheric pressure.

There are two general types of barometers: those in which atmospheric pressure is balanced by the weight of a column of liquid (usually mercury); and those in which atmospheric pressure is balanced by some elastic device. The latter are termed *aneroid* (without liquid) *barometers.* A third kind of device for measuring atmospheric pressure is the *hypsometer,* which is not classed as a barometer.

barometer: aneroid.—A *barometer* which balances the atmospheric pressure against a mechanically elastic device.

The usual form of aneroid barometer consists of a thin box of corrugated metal, almost exhausted of air. When the atmospheric pressure increases, the box contracts; when the pressure lessens, the box expands. By mechanical means these movements are amplified and communicated to an index hand which registers on a graduated dial. The *graduations* on the dial are usually such as will show the atmospheric pressure in terms of height of a corresponding column of mercury. The aneroid barometer may be equipped with an auxiliary dial, graduated to show *elevations* in feet corresponding to atmospheric pressure.

barometer: cistern.—A *mercury barometer* in which a column of mercury is enclosed in a vertical glass tube, the upper end of which is sealed and exhausted of air, and the lower end placed in a cistern or reservoir of mercury which is exposed to atmospheric pressure.

The amount of the atmospheric pressure on the free surface of the mercury in the cistern determines the height to which the mercury will rise in the vertical tube. This may be measured, and the pressure reported in terms of that height, as so many *inches* of mercury.

barometer: mercury.—A *barometer* in which atmospheric pressure is balanced against the weight of a column of mercury.

There are two types of mercury barometers, differing in the form of apparatus used, but not in the underlying principle. See *barometer: cistern; barometer: siphon.*

barometer: mountain.—A *barometer* constructed for use in leveling operations.

Mountain barometer is a general term, little used, for a *barometer* of any type which is constructed for safe transportation under difficult field conditions, so that it may be used in survey work. See *barometer: aneroid, altimeter.*

barometer: siphon.—A *mercury barometer* consisting of a column of mercury in a glass tube which is so bent as to have two vertical branches, one about one-fourth the length of the other. The end of the longer branch is closed and the air in it is displaced by the mercury, but the shorter branch is left open and the mercury thereby subjected to atmospheric pressure. The difference of the height of the mercury in the two branches is a measure of the atmospheric pressure.

barometric hypsometry.—See under *hypsometry.*

barometric leveling.—See under *leveling.*

base apparatus (geodetic surveying).—Any apparatus designed for use in measuring with *accuracy* and *precision* the length of a *base line* in *triangulation,* or the length of a line in *first-* or *second-order traverse.*

Various kinds of apparatus have been designed for use in measuring *base lines,* including the following general types:

(1) Apparatus having a length unit composed of simple bars or tubes of wood, metal, or other material, suitably constructed for making *alignment,* contact, and temperature determination. The earliest bars used in *geodetic* work were of wood. The most effective apparatus of this type is the *iced-bar.*

(2) Apparatus consisting of bars or tubes of different metals having unequal *coefficients of thermal expansion,* so arranged that (a) the temperature effects on the lengths of the component parts are largely neutralized and the effective length of the apparatus remains almost constant, or (b) the component parts form a metallic thermometer, by means of which the temperature of the apparatus is obtained and its effect on the length of the apparatus determined.

(3) Apparatus consisting of tapes or wires of metal, usually steel or a nickel-steel alloy. Because of its large *coefficient of thermal expansion,* steel tapes can be used in *precision* measures of *base lines* only under favorable temperature conditions. In this country, they have been replaced almost entirely by tapes of nickel-steel (*invar* or nilvar), having very small *coefficients of thermal expansion,* and capable of giving good results through a wide range of temperature. While tapes or bands are used in this country, wires have been used in base-line operations in Mexico and in Europe.

base apparatus: Bache-Wurdeman base-line measuring apparatus.—A *compensating base-line measuring apparatus* having a measuring element composed of a bar of iron and a bar of brass, each a little less than 6 meters in length, held together firmly at one end, with the free ends so connected by a compensating lever as to form a *compensating apparatus.*

Described in Appendix No. 25, U. S. Coast and Geodetic Survey Report for 1854; description reprinted in Appendix No. 12, U. S. Coast and Geodetic Survey Report for 1873.

base apparatus: compensating base-line measuring apparatus.—A *base apparatus* having a length element composed of two metals having different *coefficients of thermal expansion,* so arranged and connected that the differential expansion of its components will maintain a constant length of the element, under all temperature conditions of use.

base apparatus: contact base-line measuring apparatus.—*A base apparatus* composed of bars whose lengths are defined by the distance between their end faces or points.

In use, the bars are laid end to end, one bar being kept in position while another bar is being moved ahead. There are various mechanical refinements connected with the moving of the bars into position, bringing the end of the new bar into contact with the end of the bar which is already in position without disturbing it.

base apparatus: contact-slide base-line measuring apparatus.—A modified *contact base-line measuring apparatus* consisting of two steel measuring bars (rods), each 4 meters in length, so mounted that contact is effected by coincidence of lines on a rod and a contact-slide. Each rod forms a metallic thermometer with two zinc tubes, one on each side of the bar: opposite ends of the bar are fastened to the ends of the tubes, the other ends of which are free to move with changes of temperature. Described in Appendix 17, U. S. Coast and Geodetic Survey Report for 1880.

base apparatus: duplex base-line measuring apparatus.—A *contact base-line measuring apparatus,* composed of two disconnected bars, one of brass and the other of steel, each 5 meters in length and so arranged as to indicate the accumulated difference of length of the measures from the brass and steel components.

The duplex base apparatus was designed by Wm. Eimbeck of the U. S. Coast and Geodetic Survey. It is described in Appendix No. 11, U. S. Coast and Geodetic Survey Report for 1897.

base apparatus: Hassler base-line measuring apparatus.—An *optical base-line measuring apparatus* consisting of four rectangular iron bars mounted end to end in a wooden box. Each bar is 2 meters long, the combined length of the apparatus being 8 meters.

Described in Transactions of the American Philosophical Society of Philadelphia, Pennsylvania, new series, 1825, Vol. II, pages 1273–1286. See also Appendix No. 21, U. S. Coast and Geodetic Survey Report for 1865.

base apparatus: iced-bar apparatus.—An apparatus for measuring linear distances with great *precision* and *accuracy,* and consisting essentially of a steel bar which is maintained at a constant temperature by being surrounded with melting ice.

The iced-bar apparatus is also called the Woodward base apparatus, after its designer, Dr. R. S. Woodward (1849–1924), of the U. S. Lake Survey. The bar is rectangular in cross-section, and is carried in a Y-shaped trough which is filled with melting ice and mounted on a car which moves on a track. Bar lengths are observed with *micrometer microscopes,* mounted on stable supports. The iced-bar apparatus is used in the laboratory in standardizing tapes, and it has also had some use in establishing *field comparators.*

base apparatus: optical base-line measuring apparatus.—A *base apparatus* composed of bars whose lengths are defined by distances between lines at or near their ends, which are observed by suitably mounted and adjusted microscopes.

In using any optical base-line measuring apparatus, the positions of the bars are controlled by microscopes on stable supports, whose *reticle* lines may be brought into coincidence with the *fiducial marks* on the bars, either by adjusting a bar or a microscope.

base apparatus: Repsold base-line measuring apparatus.—An *optical base-line measuring apparatus,* composed of a steel bar approximately 4 meters long, whose exact length at any temperature is known, and whose temperature is determined by means of a metallic thermometer composed of the steel measuring bar and a similar bar of zinc, the two being fastened together at their middle points. Described in Professional Paper No. 24, Engineering Corps, United States Army.

base apparatus: Schott base-line measuring apparatus.—A *contact, compensating base-line measuring apparatus* composed of three parallel bars, the middle bar of zinc, the outer bars of steel. One end of each steel bar is free; the other end is fastened to an end of the zinc bar, a different end for each steel bar. The lengths of the bars are so proportioned with respect to their *coefficients of thermal expansion* that a constant distance is maintained between the free ends of the steel bars. Described in Appendix No. 7, U. S. Coast and Geodetic Survey Report for 1882.

base apparatus: Woodward base-line measuring apparatus.—See under *base apparatus: iced-bar apparatus.*

base line (general).—A surveyed line established with more than usual care, to which surveys are referred for *coordination* and *correlation.*

Base lines are established for specific purposes, the more important ones, defined elsewhere, being as follows: *base line (triangulation)*; base line (echo sounding); *base line (United States public-land surveys)*; *base line (construction).*

base line (United States public-land surveys).*—A line extending east and west along the *astronomic parallel* passing through the *initial point,* along which *standard township, section,* and *quarter-section corners* are established.

As may be inferred from its designation, the *base line* is the line from which is initiated the survey of the meridional *township* boundaries and *section* lines. Auxiliary governing lines, known as *standard parallels* or *correction lines,* are established along the *astronomic parallel* usually at intervals of 24 miles north or south of the *base line.* In some of the very early surveys the base line is referred to as the "basis parallel."

base line: construction.—The center line of location of a railway or highway; often termed the "base line of location." A reference line for the construction of a bridge or other structure.

base line: triangulation.—The side of one of a series of connected triangles, the length of which is measured with prescribed *accuracy* and *precision,* and from which the lengths of the other triangle sides are obtained by computation.

Base lines in *triangulation* are classified according to the character of the work they are intended to control, and the instruments and methods used in their measurement are such that prescribed *probable errors* for each class are not exceeded. These *probable errors,* expressed in terms of the lengths, are as follows: first-order base line, 1/1,000,000; second-order base line, 1/500,000; third-order base line, 1/250,000.

base map.—See under *map.*

base tape.—A tape or band of metal or alloy, so designed and graduated and of such excellent workmanship that it is suitable for measuring the lengths of lines (*base lines*) for controlling *triangulation,* and for measuring the lengths of *first-* and *second-order traverse* lines.

In use, a base tape is subject to certain physical conditions which influence its effective length, and which must be taken into account in computing the length of a measured *base line.* These conditions include tension, temperature, method of support, sag, *grade, alignment,* and *standardization* length. See *tape corrections.* At one time, base tapes were made of steel, a metal having a high *coefficient of thermal expansion.* They are now made of *invar,* nilvar, or some other alloy having a very small *coefficient of thermal expansion.* See *invar.*

basic control.—See under *control.*

bathygraphic.*—Descriptive of ocean depths.

bathymeter.*—An instrument used for determining ocean depths.

Any deep-sea sounding apparatus. There are a number of designs of such instruments.

bathymetric.*—Relating to the measurement of ocean depths.

bathymetric chart.—See under *chart.*

bathymetry.*—The art or science of determining ocean depths.

bearing: grid.—The *angle* in the plane of the projection between a line and a north-south grid line.

bearing: true.—The *horizontal angle* between the *meridian line* and a line on the earth.

The term true bearing is used in many of the early descriptions of land boundaries in this country. It is associated with true north, referring to the direction of the north point as determined by astronomical observations. For future use, if an astronomically determined bearing is used, the term astronomic bearing is preferred over true bearing.

bearing of line (plane surveying).—The *horizontal angle* which a line makes with the *meridian* of reference adjacent to the quadrant in which the line lies. Bearings are classified according to the *meridian* used as *true bearings,* magnetic bearings, *grid bearings.*

A bearing is identified by naming the end of the *meridian* (north or south) from which it is reckoned and the direction (east or west) of that reckoning. Thus, a line in the northeast quadrant making an angle of 50° with the *meridian* will have a bearing of N. 50° E. In most survey work, it is preferable to use *azimuths* rather than *bearings.*

bearing tree (United States public-land surveys).*—A tree forming a *corner accessory,* its distance and direction from the *corner* being known.

Bearing trees are identified by prescribed marks cut into their trunks; the species and sizes of the trees are also recorded.

bed (mining).—A stratum in the earth's crust which has been formed in an approximately horizontal layer. If of rock, it is termed *bedrock.*

bed of stream.—The area within the *high-water lines* of a stream or river.

It is the area which is kept practically bare of vegetation by the wash of the waters of the stream from year to year.

bedrock.—A stratum of rock in the earth's crust which has been formed in an approximately horizontal position.

Large, deeply embedded *boulders,* with upper surfaces planed and leveled through exposure, are sometimes erroneously reported as bedrock in descriptive writing.

bench mark.—A relatively permanent material object, natural or artificial, bearing a marked point whose *elevation* above or below an adopted *datum* is known.

Usually designated as a B. M., such a mark is sometimes further qualified as a P. B. M. (*permanent bench mark*) to distinguish it from a T. B. M. (temporary bench mark), or *supplementary bench mark,* a mark of less permanent character intended to serve for only a comparatively short period of time.

bench mark: first-order.—A bench mark connected to the *datum* (usually mean sea level) by continuous *first-order leveling.*

bench mark: junction.—A *bench mark* selected as the common meeting point for *lines of levels* or *links of levels.*

bench mark: permanent.—A *bench mark* of as nearly permanent character as it is practicable to establish.

Usually designated simply as a *bench mark* or B. M., a permanent bench mark is intended to maintain its *elevation* with reference to an adopted *datum* without change over a long period of time. Concrete or stone posts, with suitable marks in their tops, such as inscribed disks, are used. Such a mark is set in firm ground, deep enough to be free from frost action, and in a location where disturbing influences are believed to be negligible.

bench mark: second-order.—A bench mark connected to the *datum* (usually mean sea level) by continuous *second-order leveling* or by a continuous combination of *first-order leveling* and *second-order leveling.*

bench mark: supplementary.—A *bench mark* at a junction of sections of a line of levels, at which no *permanent bench mark* is established.

A supplementary bench mark may be classed as a *temporary bench mark,* established to hold the end of a completed section of a line of levels and serve as an initial from which the next section is run. Spikes and screws in poles, bolts on bridges, and chisel marks on masonry are used for the purpose and may last for years.

bench mark: tidal.—A *bench mark* set to reference a tide staff at a tidal station and the elevation of which is determined with relation to the local *tidal datum.*

Bilby steel tower.—A *triangulation tower* consisting of two steel tripods, one within the other, designed by J. S. Bilby of the U. S. Coast and Geodetic Survey.

The Bilby steel tower was put into use in 1927 and is standard equipment in triangulation executed by the U. S. Coast and Geodetic Survey. The Bilby steel tower is demountable; it is easily erected, and as easily taken down and moved to a new location. Some of these towers have each been used at more than one hundred different stations.

blaze (United States public-land surveys).*—A mark made upon a tree trunk at about breast height, in which a flat scar is left upon the tree surface.

blunder.—A mistake.

A blunder is not an *error,* though a small blunder may remain undetected in a series of observations and have the effect of an *error* in determining a result. Examples of blunders are: reading a horizontal circle wrong by an even degree; neglecting to record a tape length in a measured *traverse*; reversing the numerals in recording an observation; etc.

Bonne map projection.—See under *map projection.*

Borda scale.—A *metallic thermometer* composed of two metals having different *coefficients of thermal expansion.*

The Borda scale was devised by the French scientist, Jean Charles Borda (1733–1799), who placed a strip of copper on a strip of platinum, fastened the two together at one end, and by measuring the relative movement of their free ends, determined their temperature. He used this means for determining the temperature of bars used in measuring the length of a geodetic *base line.* Later, Bessel used a combination of zinc and iron for the same purpose.

Boston leveling rod.—See under *leveling rod.*

Bouguer anomaly.—See under *anomaly.*

boulder.—A large rounded rock which has been separated from the mass of which it was originally a part.

Deeply embedded boulders may show an exposed surface which through weathering has the appearance of *bedrock.*

boundary: land.—A line of demarcation between adjoining parcels of land.

The parcels of land may be of the same or of different ownership, but distinguished at some time in the history of their descent by separate legal descriptions. A land boundary may be marked on the ground by material monuments placed primarily for the purpose; by fences, hedges, ditches, roads, and other service structures along the line; or defined by astronomically described points and lines; by *coordinates* on a survey system whose position on the ground is witnessed by material monuments which are established without reference to the boundary line; and by various other methods.

boundary line.—A line along which two areas meet.

In specific cases, the word "boundary" is sometimes omitted, as in "State line"; and sometimes the word "line" is omitted, as in "International boundary," "county boundary," etc. The term "boundary line" is usually applied to boundaries between political territories, as "State boundary line," between two States. A boundary line between privately owned parcels of land is termed a *property line* by preference, or if a line of the U. S. public-land surveys, is given the particular designation of that survey system, as *section line, township line,* etc.

boundary map.—A *map* constructed for the purpose of delineating a *boundary line* and adjacent territory.

boundary monument.—A material object placed on or near a *boundary line* to preserve and identify the location of the *boundary line* on the ground.

Where it is impracticable to establish a *monument* on or very close to a *boundary line,* the position of the *boundary line* on the ground is preserved by means of *reference marks.* The term *monument* is sometimes used to include both the mark on the *boundary line* and the *reference mark.* See also *monument* (*U. S. public-land surveys*).

boundary survey.—A survey made to establish or to reestablish a *boundary line* on the ground, or to obtain data for constructing a *map* or *plat* showing a *boundary line.*

The term boundary survey is usually restricted to surveys of *boundary lines* between political territories. For the survey of a *boundary line* between privately owned parcels of land, the term *land survey* is preferred, except that in surveys of the *public lands* of the United States, *cadastral survey* is used.

boundary vista.—A lane cleared along a *boundary line* passing through a wooded area.

A boundary vista is used for readily identifying a *boundary line,* and aiding in civil administration relating thereto.

Bowie effect (gravity).—The indirect effect on *gravity* due to the warping of the *geoid,* or the elevation of the *geoid* with respect to the *spheroid* of reference.

Also known as the Bruns term, the Bowie effect was discussed by Stokes, Bruns, Clarke, Helmert, and others, but it was under the direction of Bowie that a practical means was provided for computing its value for a given station. The *correction* for the Bowie effect is applied to the theoretical value of gravity, with the sign reversed. Values of the Bowie effect are tabulated in the *fundamental tables: deformation of the geoid and its effect on gravity.* The symbol $\Delta_2 g$ has been used to represent the Bowie effect.

Bowie Method (of adjustment).—A method devised in the U. S. Coast and Geodetic Survey under the direction of William Bowie for the *adjustment* of large networks of *triangulation.*

A description of the method is given in Special Publication No. 159, The Bowie Method of Triangulation Adjustment.

break-circuit chronometer.—See under *chronometer.*

broken grade (tape).—The change in *grade* when the middle point of a tape is not on *grade* with its ends.

If the middle support for the tape is not on the same *grade* as the end supports, the fact is noted with a reference "broken grade at —," naming the particular tape length which contains the broken grade.

broken-telescope transit.—See under *transit.*

bronze pendulum.—See under *pendulum.*

Brown gravity apparatus.—An apparatus for measuring the *acceleration of gravity* which utilizes the *Mendenhall pendulum,* but has a clamping device for holding the *pendulum* in the *receiver* when being transported from *station* to *station,* and which utilizes an electrical pick-up and amplifying device for recording the *oscillations* (*pendulum*) on the *chronograph* sheet.

The clamping device makes it unnecessary to remove the *pendulum* from the *receiver,* and thus avoids the necessity of breaking the vacuum seal each time a move is made. The recording of the *pendulum oscillations* on the *chronograph sheet* permits a direct time comparison of those *oscillations* with the radio time signals. One improvement of the Brown gravity apparatus over the *Mendenhall gravity apparatus* relates to the supporting of the *receiver* by leveling screws placed near the top of the *receiver,* making the *flexure* (*pendulum support*) less than in the earlier type of apparatus which had the leveling screws at the bottom of the *receiver,* and thus much further from the point of support of the *pendulum.*

Another improvement was the use of a cast aluminum chamber in which the *receiver* was hung as indicated above, and which was set directly in a mass of plaster of Paris placed at the bottom of a hole dug in the ground, and constituted a satisfactory stable support which was made ready more quickly than a concrete pier.

A third improvement over the old order consisted of the permanent installation in trucks of a greater portion of the electric wiring and auxiliary equipment. These improvements considerably reduced the time required by the earlier methods and apparatus for the determination of the *acceleration of gravity.* It was named for its designer, E. J. Brown of the U. S. Coast and Geodetic Survey, and was first used in the field in 1932.

bubble sextant.—See under *sextant.*

Bullard method of isostatic reduction.—See under *Hayford-Bullard* (or *Bullard*) *method of isostatic reduction.*

bulls-eye level.—See under *level: circular.*

bus and truck map.—See under *map.*

C

cadastral control (United States public-land surveys).—Lines established and marked on the ground by suitable *monuments,* which are used as starting and closing points in surveys of the *public domain of the United States.*

The fundamental control of the public-land surveys of the United States consists of *base lines, standard parallels* (*correction lines*), *principal meridians,* and *guide meridians.*

cadastral map.—See under *map.*

cadastral survey.—See under *survey.*

Calendar: Gregorian.—The calendar established by Pope Gregory XIII in 1542 A. D., to correct the *Julian Calendar* by introducing the more *precise* value of the length of the *tropical year,* 365 days 5 hours 48 minutes 46.0 seconds *mean solar time.*

The Gregorian Calendar modified the requirement of the *Julian Calendar* that every fourth year be given an additional day by providing that, for centurial years, this would be done only where such years were divisible by 400. The calendar was brought into harmony with the seasons as they were at the time of the Council of Nice (A. D. 325) by dropping 10 days at the time of its becoming effective; October 4, 1582, being followed immediately by October 15. See *Calendar: Julian; double dating.*

Calendar: Julian.—The calendar devised by Julius Caesar in 45 B. C., and based upon the assumption that the true length of the *tropical year* was exactly 365¼ *mean solar days.*

The Julian Calendar provided that the ¼ day be absorbed by giving every fourth year one additional day; it made the *year* begin on January 1, a provision that was not universally followed even where other provisions of the calendar were followed; it was effective for the year 44 B. C., which was known as the "Year of Confusion" because, in order to bring the calendar into harmony with the seasons, two additional months were intercalated between November and December, giving it 14 months with a total of 445 days. See *Calendar: Gregorian; double dating.*

calendar month.—See under *month.*

calendar year.—See under *year.*

calibration.—The determination, in terms of an adopted *unit* and by mechanical interpolation based on values obtained by *standardization*, of the supplementary marks on a measuring instrument or device. Also the determination of the values of the *divisions* of a circle as proportional parts of a circumference.

When the length of a tape has been determined by standardization, the value of its intermediate marks may be determined by calibration, it being assumed that the tape has been divided into parts which are directly proportional to its length. See *standardization.*

Camp Colonna datum.—See under *datum.*

cardinal.*—The astronomical *directions* on the surface of the earth: north, south, east, west.

The term cardinal, without qualification, is sometimes used to indicate any or all of the above *directions*, the context giving exact meaning to its use.

Cassini map projection.—See under *map projection.*

catenary correction, tape.—See under *tape: sag* or *catenary correction.*

celestial equator.—See under *equator.*

celestial latitude.—See under *latitude.*

celestial longitude.—See under *longitude.*

celestial meridian.—See under *meridian.*

celestial refraction.—See under *refraction: astronomical refraction.*

celestial sphere.—A sphere of indefinitely large (infinite) radius, described around an assumed center, and upon which positions of celestial bodies are projected along radii passing through the bodies.

In surveying operations which include observations on a celestial body, the *direction* but not the distance of the celestial body from the point of observation is important. For observations on bodies within the limits of the solar system, the center of the celestial sphere is taken as coinciding with the center of the earth. For bodies outside those limits, the *annual parallax* is negligible in surveying operations, and the center of the celestial sphere may be taken as coinciding with the point of observation.

Celsius scale.—A temperature scale in which 100° marks the freezing point and 0° the boiling point of water at 760 mm. barometric pressure.

The Celsius scale is the predecessor of and is equal to the *centigrade scale* inverted. Some use has been made of Celsius scale as synonomous with *centigrade scale.*

center: reduction to.—The amount which must be applied to a *direction* observed at an *eccentric station* or to an *eccentric signal*, to reduce such *direction* to what it would be if there were no such *eccentricity.*

The computation of the reduction to center is quite similar for the two cases, the same computation form being adapted for the *correction* to a *direction* observed at an *eccentric station* as to a direction to an *eccentric signal.*

center line (United States public-land surveys).*—The line connecting opposite *quarter-section corners*, or opposite sixteenth-section corners.

center of instrument.—The point on the vertical axis of *rotation* of an instrument at the same *elevation* as the *axis of collimation* when that axis is in a horizontal position.

In a *transit* or *theodolite*, it is close to or at the intersection of the horizontal and vertical axes of the instrument.

center of oscillation (pendulum).—The position in a *compound pendulum* of the particle which corresponds to the heavy particle of an equivalent *simple pendulum.*

The *centers of suspension* and oscillation are interchangeable. If the center of oscillation is made the *center of suspension*, the former *center of suspension* becomes the new center of oscillation. This principle is the basis of design of *compound reversible pendulums.*

center of suspension (pendulum).—The fixed point about which a pendulum *oscillates.* See *center of oscillation.*

center of transit or level.—A manufacturer's term for the spindle or spindles which are in a vertical position when the instrument is in use, and about which the instrument, or part of the instrument, *rotates.*

The engineer's *transit* has two such centers; an inner center to which the *alidade* is attached, and an outer center to which the horizontal circle is attached; it is hollow and *rotates* on the inner center. The rotation of the *alidade* is spoken of as the upper motion, and the rotation of the horizontal circle as the lower motion of the instrument.

centigrade scale.—A temperature scale in which 0° marks the freezing point and 100° the boiling point of water at 760 mm. barometric pressure. See *Celsius scale.*

central meridian (State plane-coordinate system).—See under *meridian.*

centrifugal force.—The force with which a body moving under constraint along a curved path, reacts to the constraint.

Centrifugal force acts in a direction away from the center of curvature of the path of the moving body. As a force caused by the *rotation* of the earth on its axis, centrifugal force is opposed to *gravitation*, and combines with it to form *gravity.*

c. g. s. system.—The system of physical measurements in which the fundamental units of length, mass, and time are the centimeter, the gram, and the *mean solar second.*

chain.—The *unit of length* prescribed by law for the survey of the *public lands of the United States.* The chain is equivalent to 66 feet.

The chain derives its name from the *Gunter's chain*, which had the form of a series of *links* connected together by rings, a form which has been superseded by metal tapes or ribbons graduated in chains and links. The General Land Office uses steel tapes of 1, 2, 5, or 8 chains length.

chain: Gunter's.—A measuring device used in land surveying, composed of 100 metal *links* fastened together with rings, the length of the *chain* being 66 feet.

It was invented by an English astronomer, Edmund Gunter, about 1620, and is the basis for the *chain* and *link, units of length* used in the survey of the *public lands of the United States.* An advantage in measuring in *chains* is that 10 square *chains* equals 1 acre.

chaining.—The operation of measuring a distance on the earth, using a chain or tape. See *taping.*

While the *chain* as an instrument used in making land and other surveys has been superseded by the metal tape, the term chaining has continued in use where reference is to surveys of the *public lands of the United States.* For the corresponding operation in other surveys, the term *taping* is preferred. In chaining, the men who mark the tape ends are termed *chainmen.*

chainmen.—The men who mark the tape ends in *chaining.*

chambered spirit level.—See under *level.*

chart.*—A *special-purpose map* designed for purposes of navigation.

The term chart is applied chiefly to *maps* made primarily for nautical and aeronautical navigation, and to *maps* of the heavens, although the term is sometimes used to describe other *special-purpose maps.*

chart: aeronautical.*—A *chart* designed for use in navigation through the air above land or water.

An aeronautical chart shows aids and hazards to navigation. In the past, an aeronautical chart has been variously designated as an aerial navigation map, air navigation map, aerial map, aviation map, aviation chart, and air navigation chart. The use of these terms is disapproved.

chart: air navigation.—See under *chart: aeronautical chart.*

chart: aviation.—See under *chart: aeronautical chart.*

chart: bathymetric.*—A *topographic map* of the bed of the ocean.

As now published, bathymetric charts show depth curves, with areas between curves given significant color tints. Bathymetric charts are designed especially for geophysical (oceanographic) studies, but may also be used for navigation purposes.

chart: magnetic..—A *special-purpose map* depicting the distribution of one of the magnetic elements, as by isogonic lines, or of its secular change.

chart: nautical.*—A *chart* designed for use in navigation in water areas.

A nautical chart shows aids and hazards to navigation.

chromatic aberration.—See under *aberration of light (optics).*

chronograph.—An instrument for producing a graphical record of time as shown by a clock or other device.

In use, a chronograph produces a double record: the first is made by the associated clock and forms a continuous time scale with significant marks indicating periodic beats of the time keeper; the second is made by some external agency, human or mechanical, and records the occurrence of an event or of a series of events. The clock times of such occurrences are read on the time scale made by the clock. In observations for *time* and *longitude,* the clock times of star observations are recorded on the chronograph either manually by pressing a key at the instant a star is bisected by a line of the *reticle* of the telescope used in the observing, or automatically, by keeping a star bisected by a movable wire as it travels across the field of view. See *micrometer: transit.* In longitude work, the chronograph also records the time signals received from the station of known *longitude* which is used as a base.

chronometer.—A portable timekeeper with compensated balance, capable of showing *time* with extreme *precision* and *accuracy.*

Chronometers are used in scientific and engineering work (astronomy, navigation, geophysics, etc.) where *accuracy* and *precision* in the timing of observations are demanded. Chronometers are usually constructed with a special type of balance and escapement, and beat to half seconds.

chronometer: break-circuit.—A *chronometer* equipped with a device which automatically breaks an electric circuit, the breaks being recorded on a *chronograph.*

In some *chronometers,* the breaks occur every other second, on the even seconds, and a break occurs also on the fifty-ninth second to identify the beginning of the minute; in other *chronometers,* breaks occur every second except at the beginning of the minute. By recording the occurrence of events (such as star *transits*) on a *chronograph* sheet along with the *chronometer* breaks, the *chronometer* times of those occurrences are obtained.

chronometer: hack.—A *chronometer* used for visual reference, and not usually for record purposes.

In astronomical and other work, where a time recording on a *chronograph* is made, the *chronometer* controlling the recording is placed in a position as free from disturbance as possible. For use in meeting the schedule of the observations, making the necessary settings of instruments, etc., another *chronometer,* called a hack, is kept in a position where it may be easily observed.

chronometric method of determining longitude.—See under *longitude: astronomic longitude.*

circle of equal altitude.—See under *almucantar.*

circle of position.—A small circle on the *globe* (earth) at every point of which, at the instant of observation, the observed celestial body (sun, star, planet) has the same *altitude* and therefore the same *zenith distance.*

At the instant of observation the observed body is in the *zenith* of the center of the circle of position, and the point of observation is somewhere on that circle. A second observation on the same object at a different time or on a different object at the same time will determine a second and different circle of position, and if the point of observation has not been moved, it will be at an intersection of these circles. If the point of observation has moved, as may occur when on a moving ship, allowance is made for the direction and amount of the movement, and a *position* obtained for either point of observation. In navigation, a short portion of a circle of position is plotted as a straight line and termed a *Sumner line* or *line of position.*

circuit (leveling).—A continuous *line of levels,* a series of lines of levels, or a combination of lines or parts of lines of levels, such that a continuous series of measured differences of elevation extends around the circuit or loop and back to the starting point.

circuit closure (leveling).—The amount by which the algebraic sum of the measured differences of elevation around a *circuit* fails to equal the theoretical closure, zero.

circular level.—See under *level.*

cistern barometer.—See under *barometer.*

civil day.—See under *day.*

civil time.—See under *time.*

clamping error.—See under *error.*

Clarke spheroid of 1866.—See under *spheroid.*

clinometer.—A hand instrument consisting of a tube with cross-hair, with *vertical circle* and attached *spirit level* so mounted that the inclination of the *line of sight* can be read on the circle by centering the level bubble at the instant of observation.

By means of a prism, the level bubble is viewed when looking through the observing tube at the cross-hair and object observed.

clock correction.—The quantity which is added algebraically to the time shown by a clock to obtain the time of a given *meridian.*

If the clock is slow, the *correction* is positive; if fast, negative.

clock rate.—The rate of change of a *clock correction.*

Clock rate is usually expressed as the increase or decrease of the *clock correction* per day, hour, or minute as shown on the clock face. It is called the daily or hourly rate, or rate per minute. If the *clock correction* is decreasing algebraically, the clock is gaining, and the rate is negative; if the *correction* is increasing, the clock is losing, and the rate is positive.

closing corner (United States public-land surveys).—See under *corner.*

closing error.—See under *error of closure.*

closing horizon.—See under *horizon.*

closure (leveling).—See *circuit closure (leveling).*

closure of horizon.—See under *error of closure of horizon.*

closure of traverse.—See under *error of closure, traverse.*

closure of triangle.—See under *error of closure of triangle.*

co-declination.—The complement of the *declination (astronomic)*, or 90° minus the *declination.* Also called the *polar distance.*

coefficient of refraction.—See under *refraction.*

coefficient of thermal expansion; coefficient of expansion.—The relative change (expansion or contraction) in a linear dimension of a material body corresponding to a change of 1° in the temperature of the body, expressed as a ratio.

The coefficient of expansion, as it is generally called, may be in terms of the *Centigrade, Fahrenheit,* or other thermometer scale. To a very great extent, its magnitude is peculiar to the material: a steel tape has a coefficient of expansion about 25 times as great as that of an *invar tape.* It is usually expressed as a decimal fraction, and in a measure of distance, as of a *base line,* enters as a *correction* which is a product of the coefficient of expansion of the length apparatus, the distance measured, and the difference between the temperature at which the measure was made and the temperature at which the length of the apparatus is known.

coincidence (pendulum).—An exact agreement in occurrence of a prescribed phase of a *free-swinging pendulum* beat and a prescribed phase of a clock or *chronometer* beat.

The *free-swinging pendulum* being either slightly longer or slightly shorter than the clock *pendulum,* vibrates at a different speed from the clock *pendulum,* and loses or gains a whole beat between coincidences. The elapsed time between coincidences as shown by the clock or *chronometer,* enables an observer to know the number of *vibrations* made by the *free-swinging pendulum* during that time, and thus the number made during a period between precise time determinations.

In the *gravity* work of the U. S. Coast and Geodetic Survey, coincidences are observed by noting when two lines of light come into exact agreement: one is a moving line reflected by a mirror attached to the head of a *free-swinging pendulum;* the other, a fixed line of light reflected from a mirror attached to the *pendulum* support and becoming visible each second through a shutter controlled by the *chronometer.*

coincidence method (pendulum).—The determination of the period of a *free-swinging pendulum* by observing the time interval between *coincidences* with a clock *pendulum* or *chronometer* beat.

colatitude.—The complement of the *latitude,* or 90° minus the *latitude.*

Colatitude forms one side, *zenith* to pole, of the *astronomical triangle.* It is opposite the celestial body.

collimation.—The act of making a *collimation adjustment.*

This use of the term collimation may lead to confusion, which would be avoided by employing a more extended expression.

collimation: error of.—The *angle* between the *line of collimation (line of sight)* of a telescope and its *collimation axis.*

When the *collimation adjustment* of an instrument is perfect (which is never the case), the *line of collimation* and the *collimation axis* will coincide, and the error of collimation will be zero. In practical work, the adjustment is carried to where the *error* is so small that it may be considered negligible in many classes of work; or in *precise* work, after the adjustment is made, the *residual error* is either determined by observation and applied as a *correction,* or is eliminated from the result by a suitable program of observing. Error of collimation is a *systematic error,* and in a series of observations is usually treated as being of the *constant error* type.

collimation: line of.—The line through the *second nodal point* of the objective (object glass) of a *telescope* and the center of the *reticle.* It is variously called the line of sight, sight line, pointing line, and aiming line of the instrument.

The center of the *reticle* of the *telescope* of a *transit* may be defined by the intersection of cross-hairs or by the middle point of a fixed vertical wire or of a micrometer wire in its mean position. In a leveling instrument, the center of the *reticle* may be the middle point of a fixed horizontal wire.

collimation adjustment.—The process of bringing the *line of collimation* of a *telescope* into close agreement with the *collimation axis.* Also called adjustment for collimation.

collimation axis.—The line through the *second nodal point* of the objective (object glass) perpendicular to the axis of *rotation* of the *telescope.*

In a surveyor's *transit,* the collimation axis is perpendicular to the *horizontal axis* of the *telescope.* In a leveling instrument it is perpendicular to the *vertical axis* of the instrument. When the *telescope* of a *transit* is *rotated* about its *horizontal axis,* the collimation axis describes a plane, called the *collimation plane.*

collimation plane.—The plane described by the *collimation axis* of a *telescope* of a *transit* when rotated around its *horizontal axis.*

collimation position.—A term defined in Manual of Engineering Practice No. 15, A. S. C. E., as follows: "The ideal position of the line of sight of a telescope; that is, the optical axis. See, also, Line of Sight." The ideal position of the line of sight is known as the *collimation axis.* The term collimation position as defined by the A. S. C. E. seems unnecessary, and its definition appears contradictory.

collimator.—A device consisting of a convergent *achromatic lens* with a mark placed in the plane of its principal focus, so that rays from the mark through the lens emerge along parallel lines.

The mark in a collimator may be viewed from very short distances as if it were at an infinite distance, and may therefore be used in place of a distant mark when making any adjustment of the *line of sight* (*line of collimation*) of an instrument. In adjusting a surveying instrument, the *telescope* of another surveying instrument may be used as a collimator, the *reticle* furnishing the mark; or the *telescope* of a discarded instrument may be placed on a special mounting to form a permanent installation. In some astronomical instruments, a vessel of mercury, placed directly under the instrument, is used as a collimator. A prismatic eyepiece used with such an instrument is sometimes called a collimating eyepiece.

A collimator may also be constructed of special design for a particular purpose: see *collimator: vertical.*

collimator: vertical.—A *telescope* so mounted that its *collimation axis* may be made to coincide with the *vertical* (or direction of the plumb line).

The vertical collimator serves as an optical plumb line, and may be designed for use in placing a mark on the ground directly under an instrument on a high tower; or in centering an instrument on a high tower directly over a mark on the ground.

colure: equinoctial.—The *hour circle* through the *equinoxes.*

colure: solstitial.—The *hour circle* through the *solstices.*

colures.—The *hour circles* through the *equinoxes* and the *solstices.* See *colure: equinoctial; colure: solstitial.*

comb (micrometer).—A notched scale placed at right angles to the movable wire of a *micrometer,* and so designed that one turn of the micrometer screw will move the micrometer wire across one notch of the comb; the central notch of the comb in conjunction with the zero of the micrometer head furnishes a fiducial point from which all micrometer readings are reckoned.

The comb is used for keeping count of whole turns of the micrometer screw, parts of turns being read on the graduated micrometer head.

Committee Meter.—See under *meter.*

comparator.—An instrument or apparatus for measuring a dimension in terms of a *standard.*

In *plane* and *geodetic surveying,* a comparator may be an instrument for comparing *standards of length;* for subdividing such *standards;* or for determining a standard length of a measuring device (bar, tape, etc.). A field comparator or comparator base is a short line whose length is measured with accuracy and *precision,* and used to check the lengths of apparatus (tapes) used in the actual field operations.

There are special types of comparators used in astronomic and photogrammetric work, and in various kinds of laboratory work.

comparator: field.—See under *comparator.*

comparator base.—See under *comparator.*

compass: prismatic.—A small magnetic compass held in the hand when in use, and equipped with peep sights and glass prism so arranged that the *magnetic bearing* or *azimuth* of a line can be read at the same time that the line is sighted over.

compass: solar.—A surveying instrument which effects the instantaneous mechanical solution of the *astronomical triangle* (sun-zenith-pole), and permits the establishment and surveying of the *astronomic meridian* or *astronomic parallel* directly by observation.

Originally invented and used for the establishment of *astronomic meridians* and *parallels* in the survey of the *public lands of the United States,* the solar compass has been replaced by the *solar attachment* in combination with a *transit,* or by the *solar transit.*

compass: sun.—A navigation instrument for determining the direction of the *astronomic meridian* mechanically and instantaneously from an observation on the sun.

A good example of a sun compass is the one designed by A. H. Bumstead of the National Geographic Society and used by R. E. Byrd in aeronautical navigation in the polar regions. It consists of a mean-time clock with a 24-hour dial, an hour hand with a shadow pin at one end, and graduated circles for *latitude* and *azimuth* setting. In use, the clock is set for *latitude* so that the plane of its face is parallel to the plane of the *equator,* the hour hand (it has only the one hand) is set to show local time, and the whole is oriented till the pin on the hour hand casts a shadow down the middle of the hand. In this position, the lubber line will be in the local *meridian.* The term sun compass is preferred for the navigation instrument, to distinguish it from the *solar compass,* a surveying instrument which attains a similar result.

compass: surveyor's.—An instrument for determining the *magnetic azimuth* of a line of sight by means of a sighting device, a graduated horizontal circle, and a pivoted magnetic needle.

The surveyor's compass used on the early land surveys in this country employed a pair of peep sights to define the *line of sight,* and was usually mounted on a single leg, called a *Jacob's staff.* This instrument has been completely displaced by the surveyor's *transit,* and the *solar transit.*

compass rule, balancing survey.—See under *balancing a survey.*

compensated géoid.—See under *geoid.*

compensating base-line measuring apparatus.—See under *base apparatus.*

compiled map.—See under *map.*

complement of angle.—See under *angle.*

composite map.—See under *map.*

compound pendulum.—See under *pendulum.*

compression (of the earth).—See under *flattening of the earth.*

concluded angle.—See under *angle.*

condition equation.—See under *equation.*

conformal (isometric) latitude.—See under *latitude.*

conformal map projection.—See under *map projection.*

conformality.—The unique property of *conformal map projections,* in which all small or elementary figures on the surface of a sphere retain their original forms (shapes) on the *map.*

conic map projection.—See under *map projection.*

constant: level.—The amount by which the actual *line of sight* through a *leveling instrument* (when the bubble is centered in its vial) departs from the truly horizontal line through the center of the instrument, computed in millimeters per millimeter of *stadia interval.*

In case leveling rods graduated in yards instead of meters are used, the level constant, *C,* would be expressed in milliyards per milliyard of *stadia interval.*

constant: stadia (leveling).—The constant which is multiplied by the *stadia interval* to obtain the length of a sight in meters. Also the constant by means of which the sum of the stadia intervals for all sights of a *running* is converted to the length of the running in kilometers.

In case yard rods are in use, the resulting lengths will be in yards and kiloyards.

constant error.—See under *error.*

constant of gravitation.—See under *gravitation.*

contact base-line measuring apparatus.—See under *base apparatus.*

contact correction, transit micrometer.—A quantity applied to the *chronograph* record of a star *transit* observed with the aid of a *transit micrometer* to allow for the time required for the contact spring to cross one-half of the width of a contact strip in the head of the *micrometer.*

In order to insure a satisfactory record, the contact strips are given appreciable width, and as the micrometer wire travels from different sides of the instrument for *upper* and *lower culmination stars,* and also before and after reversal of the instrument, the contact spring produces a record sometimes from one edge of a contact strip and sometimes from the other. The contact correction is intended to reduce each observation to the middle of the contact strip which records it.

contact-slide base-line measuring apparatus.—See under *base apparatus.*

contact vernier.—See under *vernier.*

contour.—An imaginary line on the ground, all points of which are at the same *elevation* above a specified *datum* surface.

A contour is illustrated by the shore line of an imaginary body of water, whose surface is at the *elevation* represented by the contour. A contour forming a closed loop around lower ground is called a depression contour. The datum surface most generally used for contours in this country is *mean sea level.*

contour interval.—The difference in *elevation* of two adjacent *contours.* The difference of *elevations* represented by adjacent *contour lines.*

contour line.—A line on a *map* representing a *contour.*

contour map.—See under *map.*

control: basic.—In general, coordinated and correlated position data forming a framework to which detail surveys are adjusted.

Basic control may be either horizontal or vertical; it is usually executed with greater *precision* and *accuracy* than is required for dependent surveys. The basic control for the *Topographic Map of the United States* consists of *first-* and *second-order triangulation* and *traverse* and *first-* and *second-order leveling.*

control: cadastral (United States public-land surveys).—See under *cadastral control (United States public-land surveys).*

control: geodetic.—A system of *control stations* established by *geodetic* methods.

Geodetic control data are first determined in the form of *geodetic coordinates* and *azimuths,* which are now sometimes transposed into plane-coordinate data on a State system, before being used as bases for local surveys.

control: national control survey nets.—The two *control survey* nets being extended over the area of the United States by the U. S. Coast and Geodetic Survey for the control of *nautical charts* and *topographic maps,* and comprising:

1. The horizontal control survey net consisting of arcs of *first-* and *second-order triangulation,* and lines of *first-* and *second-order traverse,* a few of which have been executed by the U. S. Geological Survey, the Corps of Engineers, and other organizations. The data derived in this survey are being coordinated and correlated on the *North American datum of 1927.*

2. The vertical control survey net consisting of lines of *first-* and *second-order spirit leveling* which determine the *elevations* of thousands of *bench marks* above a common *datum, mean sea level.* This net includes lines of levels run by the U. S. Geological Survey, the Corps of Engineers, and other organizations.

control station.—A point on the ground whose *position* (horizontal, vertical) is used as a base for a dependent survey.

control survey.—A survey which provides *positions* (horizontal, vertical) of points to which supplementary surveys are adjusted.

The fundamental control survey of the United States provides the *geographic positions* (and *plane coordinates*) of thousands of *triangulation* and *traverse stations* and the *elevations* of thousands of *bench marks* which are used as the bases for *hydrographic surveys* of the coastal waters, for the control of the *topographic survey* of the United States, and for the control of many State, city, and private surveys.

control surveys: first-order.—See under *first-order work (control surveys).*

control surveys: second-order.—See under *second-order work (control surveys).*

convergence of meridians.—See under *meridian.*

conversion factor.—See under *factor.*

Conybeare leveling rod.—See under *leveling rod.*

coordinate protractor.—See under *protractor.*

coordinates (general).—Linear or angular quantities, or both, which designate the *position* of a point in relation to a given reference frame.

There are two general divisions of coordinates used in surveying: *polar coordinates* and *rectangular coordinates.* These may each be subdivided into three classes: *plane coordinates, spherical coordinates,* and *space coordinates.*

coordinates: astronomic.—Quantities which define the *position* of a point on the *geoid* with reference to the planes of the *celestial equator* and of a selected *celestial meridian.* See *latitude: astronomic; longitude: astronomic.*

coordinates: geocentric (terrestrial).—Quantities defining the *position* of a point on the earth by means of the *angles* made by a line from the center of the earth to the point with the planes of the *celestial equator* and of a selected initial *geodetic meridian.*

See *latitude: geocentric.* The term geocentric longitude is never used, as the quantity which it would designate is the same as *geodetic longitude.*

coordinates: geodetic.—Quantities which define the horizontal *position* of a point on the *spheroid of reference* with respect to the planes of the *geodetic equator* and of a selected *geodetic meridian.* See *latitude: geodetic; longitude: geodetic.*

coordinates: geographic.—An inclusive term, used to designate both *geodetic coordinates* and *astronomic coordinates.*

coordinates: grid.—Two distances which fix the *position* of a point on a *grid:* the perpendicular distance to the point from the Axis of *Y,* termed the abscissa or *x* coordinate; and the perpendicular distance from the Axis of *X,* termed the ordinate or *y* coordinate.

In surveying operations, the nominal *origin* at the intersection of the axes is usually given large numerical *coordinates,* so the inconvenience of using negative *coordinates* will be avoided. *Geodetic coordinates* (*latitudes* and *longitudes*) may be transformed into grid coordinates, and all survey computations relating to them then made by the methods and formulas of *plane surveying*. See *State coordinate systems*.

coordinates: origin of.—A point in a system of *coordinates* which serves as an initial in computing its elements or in prescribing its use.

The term, origin of coordinates, has several definitions, each so well-established in use that a single definition cannot be prescribed to the exclusion of the others. However, the following are given in the order of preferred use, but to avoid misunderstanding the use should be defined by stating the *position* of the origin in the system and giving the numerical *coordinates* assigned it.

1. The origin of coordinates is the point of intersection of the coordinate axes, from which the *coordinates* are reckoned. In mathematical treatises this origin is usually given the *coordinates* 0, 0; in surveying work, however, it is standard practice to give this origin *coordinates* having large positive numerical values, thereby avoiding the use of negative *coordinates*. See *State coordinate systems*.

2. The origin of coordinates is the point to which the coordinate values 0, 0 are assigned, irrespective of its *position* with reference to the axes.

3. The origin of coordinates is the point from which the computation of the elements of the coordinate system (projection) proceeds.

coordinates: plane-rectangular.—The perpendicular distances (*coordinates*) of a point from a pair of axes which intersect at right angles, reckoned in the plane defined by those axes.

Plane-rectangular coordinates are usually calculated from data which are in the form of *polar coordinates*, that is, distance and *direction* (*bearing* or *azimuth*) from a previously determined point. For example, the computation of *latitudes* and *departures* in land surveying. The methods used are based on plane trigonometry and geometry. The *position* of a point on the earth may be defined by plane-rectangular coordinates on a tangent plane (*local system of plane coordinates*), or on a so-called *conic* or *cylindrical map projection*, such as are used in the *State plane-coordinate systems*.

coordinates: polar (general).—The distance and *direction* from a central point of reference to a point whose position is being defined.

The point of reference is termed the pole or origin; the line (distance) connecting the origin with the point whose position is being defined is the radius vector; and the *angle* between the fixed line to which the *direction* is referred and the radius vector is the vectorial angle. In surveying operations, observations are usually put in the form of polar coordinates as a first step in the computation of *plane* or *spherical coordinates*. For example, computations of *geodetic positions* (*latitudes* and *longitudes*) are based on *azimuths* and distances from known positions.

coordinates: rectangular.—*Coordinates* on any system in which the axes of reference intersect at right angles.

A system of rectangular coordinates may be plane, curved (spherical), or spatial. See *coordinates: plane-rectangular; coordinates: geodetic; coordinates: rectangular space; etc.*

coordinates: rectangular space.—The perpendicular distances of a point from planes defined by each pair of a set of three axes which are mutually perpendicular to each other at a common point or origin.

In photogrammetry, space coordinates are also termed survey coordinates, and are the x and y *coordinates* which define the horizontal position of a point on a ground system, and the z coordinate, which is the *elevation* of the point with reference to the ground system.

coordinates: spherical.—Two quantities, angular or linear, or both, on a sphere, defining the *position* of a point with reference to two *great circles* which form a pair of axes, or with reference to an *origin* and a *great circle* through the point.

The term spherical coordinates includes *coordinates* on any surface approximating a sphere. See *coordinates: geographic; coordinates: geodetic; coordinates: astronomic.*

coordinates: vertical.—The vertical distance (*elevation*) of a point above or below a surface of reference (*datum*).

The vertical coordinate of a point may be plus or minus, according to whether the point is above or below the *datum;* the *datum* may be assigned a large positive *elevation,* so that all *elevations* referred to it will be plus. Instead of *elevation,* the term height is sometimes used.

coordination.—The placing of survey data on the same coordinate system or *datum.*

Coordination does not imply the *adjustment* of observations to remove *discrepancies.* Two field surveys over the same area may be coordinated by computation on the same *datum,* but there may remain between them *discrepancies* that can be removed only by *correlation.*

corner.—A point on a *land boundary,* at which two or more boundary lines meet.

Not the same as *monument,* which refers to the physical evidence of the corner's location on the ground.

corner (United States public-land surveys).*—A point on the surface of the earth, determined by surveying process, marking an extremity of a boundary of a subdivision of the public lands, usually at the intersection of two or more surveyed lines; often incorrectly employed to denote the physical structure, or *monument,* erected to mark the corner point.

Corners are described in terms of the points they represent. Thus:

township corner.—A corner at the extremity of a *township* boundary.

section corner.—A corner at the extremity of a *section* boundary.

quarter-section corner.—A corner at an extremity of a boundary of a *quarter section,* midpoint between or 40 chains from the controlling section corners, depending on location within the *township.*

sixteenth-section corner.—A corner at an extremity of a boundary of a *quarter-quarter section;* midpoint between the controlling corners on the *section* or *township* boundaries.

meander corner.—A corner marking the intersection of a *township* or *section* boundary and the *mean high-water* line of a body of water.

standard corner.—A corner on a *standard parallel* or *base line.*

corner: closing (United States public-land surveys).*—A *corner* at the intersection of a surveyed boundary with a previously established *boundary line.*

In the survey of the public land of the United States, when the line connecting the last *section corner* and the objective corner on an established *township* boundary departs from the *astronomic meridian* by more than the allowable deviation, the line being surveyed is projected on *cardinal* to an intersection with the *township* boundary, where a closing corner is established and connection made to the previously established corner. Closing corners are established at the intersection of a line being surveyed with a previously established *township* boundary in order to avoid excessive deviation from *cardinal* which might be required to connect with the objective corner on that boundary. Closing corners are also established at the intersection of a *township, range,* or *section line* with the boundary of a previously surveyed and segregated tract of land, such as a private land claim, mineral claim, etc.

corner: existent (United States public-land surveys).*—A *corner* whose *position* can be identified by verifying the evidence of the *monument,* or its *accessories,* by reference to the description that is contained in the field notes, or where the point can be located by an acceptable supplemental survey record, some physical evidence, or testimony.

Even though its physical evidence may have entirely disappeared, a *corner* will not be regarded as lost if its *position* can be recovered through the testimony of one or more witnesses who have a dependable knowledge of the original location.

corner: lost (United States public-land surveys).*—A *corner* whose *position* cannot be determined, beyond reasonable doubt, either from traces of the original marks or from acceptable evidence or testimony that bears upon the original *position,* and whose location can be restored only by reference to one or more inter-dependent corners.

corner: obliterated (United States public-land surveys).*—A *corner* at whose point there are no remaining traces of the *monument,* or its *accessories,* but whose location has been perpetuated, or the point for which may be recovered beyond reasonable doubt, by the acts and testimony of the interested landowners, competent surveyors, or other qualified local authorities, or witnesses, or by some acceptable record evidence.

A position that depends upon the use of collateral evidence can be accepted only as duly supported, generally through proper relation to known corners, and agreement with the field notes regarding distances to natural objects, stream crossings, *line trees,* and off-line tree blazes, etc., or unquestionable testimony.

corner: witness (United States public-land surveys).*—A monumented survey point near a *corner,* established as a *reference mark* when the corner is so situated as to render its monumentation or ready use impracticable.

A witness corner is marked in a prescribed manner, comparable with that for the true *corner.*

corner accessories (United States public-land surveys).—See under *accessories.*

correction.—A quantity which is applied to an observation or function thereof, to diminish or eliminate the effects of *errors* and obtain an improved value of the observation or function. It is also applied to reduce an observation to some arbitrary standard.

The correction corresponding to a given *error* is of the same magnitude but of opposite sign. The signs are given by the following equation: improved value = observed value + correction.

See under *error: residual error.*

correction: adjustment (leveling).—That correction which is applied to an *orthometric elevation* to produce an *adjusted elevation,* for the purpose of eliminating the effects of *circuit closures.*

correction: index (leveling).—That correction which must be applied to an observed difference of elevation to eliminate the *error* introduced into the observations when the zero of the graduations on one or both *leveling rods* does not coincide exactly with the actual physical foot or bottom surface of the rod.

correction: level (leveling).—That correction which is applied to an observed *difference of elevation* to correct for the *error* introduced by the fact that the *line of sight* through the *leveling instrument* is not absolutely horizontal when the bubble is centered in its vial.

correction: orthometric.—That correction which is applied to a *preliminary elevation* to correct for the *error* introduced by the fact that level surfaces at different *elevations* are not exactly parallel.

correction: rod (leveling).—That correction which is applied to an observed difference of elevation to correct for the *error* introduced when the *leveling rods* are not actually of the length indicated by the *graduations.*

correction: temperature (leveling).—That correction which is applied to an observed difference of elevation to correct for the *error* introduced when the temperature at which the *leveling rods* are used in the field is different from the temperature at which they were standardized. See, also, *standardization.*

correction for inclination of the horizontal axis.—See under *inclination of the horizontal axis.*

correction for run of micrometer.—See under *micrometer.*

correlate equation.—See under *equation.*

correlation.—The removal of *discrepancies* that may exist among survey data, so that all parts are interrelated without apparent *error.*

The terms *coordination* and correlation are usually applied to the harmonizing of *surveys* of adjacent areas or of different *surveys* over the same area. Two or more such *surveys* are coordinated when they are computed on the same *datum;* they are correlated when they are adjusted together.

county map.—See under *map.*

course (general).—This term has many meanings. In *surveying* it has been used to designate the *bearing* of a line; the length of a line; and the combination, *bearing* (or *azimuth*) and length of a line. In *control surveying,* its use can and should be avoided, but if used, it should be with the inclusive meaning, *azimuth* and length of line. It is better to use the two distinct and definite terms, *azimuth* and length of line. The following are definitions of course as used in current technical literature:

course (geography).—A route on the earth along which a river flows; the river itself.

course (land surveying).—The *bearing* of a line.

course (navigation).—The *azimuth* or *bearing* of a line along which a ship is to travel or does travel.

course (transit traverse).—The *azimuth* and length of a line, considered together.

crystal clock.—The crystal clock is a relatively new device for keeping accurate *time.* It consists essentially of a generator of constant frequency controlled by a resonator made of quartz crystal, with suitable means for producing continuous *rotation* controlled by it to operate time indicating and related mechanisms.

The above description is quoted directly from a paper, The Crystal Clock, by W. A. Marrison, published in the Proceedings of the National Academy of Sciences, July 15, 1930. The crystal clock has been used with considerable advantage over other types of portable clocks and *chronometers* in scientific work, such as *gravity* observations, where *time* intervals must be measured with the greatest possible *accuracy* and *precision.*

culmination.—The position of a heavenly body when at highest apparent *altitude;* also, for a heavenly body which is continually above the *horizon*, the position of lowest apparent *altitude.*

Culmination occurs when the body *transits* the local *meridian:* upper culmination at the upper branch of the *meridian;* lower culmination at the lower branch. As an observer approaches a pole of the earth, culmination of the fixed stars becomes less noticeable, disappearing when the pole is reached. Under some conditions, for bodies within the solar system, culmination may be largely obscured by changes in *declination.* At one time, moon culminations were extensively used in determining *astronomic longitude.*

cumulate.—A term proposed for a type of *error* which tends to accumulate in direct proportion to occurrence.

This type of *error* is covered by the expression *systematic error,* and there is no need for a new term. The use of cumulate should be avoided.

curvature correction (astronomy).—A *correction* applied to the mean of a series of observations on a star or planet, to take account of the divergence of the apparent path of the star or planet from a straight line.

Observations on a star for the purpose of determining the value of a *micrometer* are subject to a correction for curvature, as also are some *azimuth* observations. The *correction* to reduce a *latitude* observation on a star close to but not on the *meridian* to what it would be if the star were on the *meridian* may be considered a correction for curvature.

curvature correction (geodesy).—The *correction* applied in some *geodetic* work to take account of the divergence of the surface of the earth (*spheroid*) from a plane.

In *geodetic spirit leveling,* the effects of curvature and of *atmospheric refraction* are considered together, and tables have been prepared from which combined *corrections* can be taken.

curve: degree of.—The number of degrees of angular measure at the center of a circle subtended by a chord 100 feet in length.

In highway surveying, a 100-foot arc is sometimes used instead of a 100-foot chord in defining degree of curve.

curve: easement.—A *spiral curve.*

curve: point of compound curvature.—The point on a line survey where a circular curve of one radius is tangent to a circular curve of a different radius, both curves lying on the same side of their common tangent. Also termed the P. C. C.

curve: point of curvature.—The point in a line survey where a tangent ends and a circular curve begins. Also called point of curve, and P. C.

It is the point where a straight line in a survey changes to a circular curve. See *curve: point of tangency.*

curve: point of intersection.—The point where the two tangents of a circular curve meet. Also called the vertex of curve, and the P. I.

curve: point of tangency.—The point in a line survey where a circular curve ends and a tangent begins. Also called point of tangent, and P. T.

The point of tangency and point of curve are both points of tangency, their different designations being determined by the direction of progress along the line. The *point of curvature* is reached first.

curve: spiral.—A curve of varying radius connecting a circular curve and a tangent, or two circular curves whose radii are respectively longer and shorter than its own extreme radii. Also called a transition curve and an easement curve.

curve: transition.—A *spiral curve.*

curve: vertex of.—See under *curve: point of intersection.*

curve of alignment.—A line connecting two points on the surface of the *spheroid,* and defined by the condition that at every point the *azimuths* of the two end points of the line differ by exactly 180°.

A curve of alignment is a line of double curvature slightly less in length than the *normal section lines* connecting its two end points.

cut-off cylinder.—An accessory apparatus, used in *standardization* operations to refer the end of a base tape or bar standard to a ground mark.

The cut-off cylinder is a laboratory device, consisting essentially of a short rigid bar, so equipped and mounted that it forms a direct connection between the apparatus being tested and a permanent ground monument; its length and inclination provide the means for determining the relative positions of the *fiducial marks* on the base tape or bar and on the ground monument.

cylindrical equal-area map projection.—See under *map projection.*

cylindrical equal-spaced map projection.—See under *map projection.*

cylindrical map projection.—See under *map projection.*

D

datum.—Any numerical or geometrical quantity or set of such quantities which may serve as a reference or base for other quantities.

For a group of statistical references, the plural form is data: as *geographic* data for a list of *latitudes* and *longitudes.* Where the concept is geometrical and particular, rather than statistical and inclusive, the plural form is datums, as, for example, two *geodetic datums* have been used in this country in recent years.

datum (geodetic).*—A *datum* consisting of 5 quantities: the *latitude* and the *longitude* of an initial point, the *azimuth* of a line from this point, and two constants necessary to define the terrestrial *spheroid.*

It forms the basis for the computation of horizontal *control surveys* in which the curvature of the earth is considered.

datum (leveling).—A *level surface* to which heights are referred.

The *elevation* of the *datum* is usually, but not always, zero (0). The generally adopted *datum* for leveling operations in the United States is *mean sea level.* For local surveys, where a sea-level connection is not available, an arbitrary *datum* may be adopted and defined in terms of an assumed *elevation* for some physical mark (*bench mark*). A *datum* for *spirit leveling* is not a plane, and the term datum plane is incorrectly used in such connection. See, also, *datum: tidal.*

datum: Camp Colonna.—The *geodetic datum* defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866*:

	°	′	″
Latitude of Camp Colonna	67	25	05.11 N.
Longitude of Camp Colonna	140	59	13.50 W.
Azimuth from Camp Colonna to South Meridian	0	00	00

The above position and *azimuth* are based on astronomical observations made in 1890, the *longitude* being determined by the moon-culmination method.

datum: Golofnin Bay.—The *geodetic datum* defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of Golofnin Bay long. station	64	27	11.461 N.
Longitude of Golofnin Bay long. station	162	52	13.700 W.
Azimuth from Golofnin Bay long. station to azimuth mark	180	00	42.9

The above position and *azimuth* based on astronomical observations made in 1899, the *longitude* being determined by the *chronometric method.*

datum: Kripniyuk-Kwiklokchun.—The *geodetic datum* defined by the following *geographic position* and *azimuths* on the *Clarke spheroid of 1866*:

	°	′	″
Latitude of Kripniyuk astro. station	62	20	06.58 N.
Longitude of Kripniyuk astro. station	165	19	27.12 W.
Azimuth from Kripniyuk astro. station to station Tent	180	00	00.0
Azimuth from Kwiklokchun astro. station to station Camp	0	00	00.0

The above position is based on *weighted means* of astronomical determinations made in 1898, the *longitudes* by the *chronometric method.*

datum: Luzon.—The *geodetic datum* which is defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of triangulation station Balanacan	13	33	41.000 N.
Longitude of triangulation station Balanacan	121	52	03.000 E.
Azimuth, triangulation station Balanacan to triangulation station Baltasar	9	12	37.000

The Luzon datum was adopted in 1911 and was derived from observations on the Island of Luzon. It has been extended to all parts of the Philippine Islands, except a few remotely situated islands. See U. S. Coast and Geodetic Survey Field Engineers Bulletin, December 1938, page 20.

datum: New England.—Identical with the *geodetic datum* for which the name *United States standard datum* was adopted in 1901, which name was later changed to *North American datum.* Before 1901 this *datum* was defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of triangulation station Principio	39	35	36.692 N.
Longitude of triangulation station Principio	76	00	16.407 W.
Azimuth, triangulation station Principio to triangulation station Turkey Point	1	34	36.413

See U. S. Coast and Geodetic Survey Report for 1879, Appendix 8, pages 112–114.

datum: North American.*—The *geodetic datum* which is defined by the following *geographic position* of triangulation station Meades Ranch and the *azimuth* from that station to station Waldo, on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of Meades Ranch	39	13	26.686 N.
Longitude of Meades Ranch	98	32	30.506 W.
Azimuth, Meades Ranch to Waldo	75	28	14.52

The North American datum is identical with the *United States standard datum,* the name of the *datum* being changed in 1913 when its adoption by the governments of Canada and of Mexico for their control surveys gave it an international character.

datum: North American datum of 1927.*—The *geodetic datum* which is defined by the following *geographic position* of triangulation station Meades Ranch and the *azimuth* from that station to station Waldo, on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of Meades Ranch	39	13	26.686 N.
Longitude of Meades Ranch	98	32	30.506 W.
Azimuth, Meades Ranch to Waldo	75	28	09.64

Geodetic positions on the North American datum of 1927 are derived from the above *geographic position* and *azimuth* through a readjustment of the *triangulation* of the entire country, in which *Laplace azimuths* were introduced, and new methods of adjustment were used (*Bowie method*).

datum: Old Hawaiian.—The *geodetic datum* which is defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of triangulation station Oahu west base	21	18	13.89 N.
Longitude of triangulation station Oahu west base	157	50	55.79 W.
Azimuth, triangulation station Oahu west base to triangulation station Oahu east base	291	29	36.0

The Old Hawaiian datum is based on an adjusted *latitude* derived from a number of *astronomic latitudes* in various parts of the islands, and an *astronomic longitude* obtained from observations of lunar *culminations,* star *occultations,* etc. See U. S. Coast and Geodetic Survey Special Publication No. 156, Triangulation in Hawaii.

datum: Panama-Colon.—The *geodetic datum* which is defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of triangulation station Balboa Hill	9	04	57.637 N.
Longitude of triangulation station Balboa Hill	79	43	50.313 W.
Azimuth, triangulation station Balboa Hill to triangulation station Salud	185	02	39.54

See U. S. Coast and Geodetic Survey Field Engineers Bulletin, December 1938, page 23.

datum: Port Clarence.—The *geodetic datum* defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866*:

	°	′	″
Latitude of Port Clarence astro. station	65	16	40.18 N.
Longitude of Port Clarence astro. station	166	50	08.065 W.
Azimuth from Port Clarence astro. station to azimuth mark	**0**	**06**	**17.0**

The *latitude* was determined astronomically in 1900; the *longitude* is an assumed value, the astronomically-determined value being 166° 50′ 45.60″; the *azimuth* was derived from *time* observations.

datum: Pribilof Islands datums.—See under *datum: St. George Island: St. Paul Island.*

datum: Puerto Rico.—The *geodetic datum* which is defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of triangulation station Cardona Island lighthouse	17	57	31.400 N.
Longitude of triangulation station Cardona Island lighthouse	66	38	07.530 W.
Azimuth, triangulation station Cardona Island lighthouse to triangulation station Ponce southwest base	128	36	26.2

Adopted in 1901 or soon thereafter, the Puerto Rico datum is derived from observations on the Island of Puerto Rico and the Virgin Islands. See U. S. Coast and Geodetic Survey Field Engineers Bulletin, December 1938, page 22.

datum: St. George Island.—The *geodetic datum* defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866*:

	°	′	″
Latitude of St. George Island astronomic station	56	36	11.31 N.
Longitude of St. George Island astronomic station	169	32	36.00 W.
Azimuth from St. George Island astronomic station to meridian mark	0	00	06

The above *latitude* and *azimuth* are based on independent astronomical determinations. The *longitude* is based on *longitudes* of St. George Island and St. Paul Island astronomic stations, which were determined by the *chronometric method*, a *weighted mean* being obtained through *triangulation* connecting the two *islands*.

datum: St. Michael.—The *geodetic datum* defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866*:

	°	′	″
Latitude of St. Michael astro. station	63	28	41.51 N.
Longitude of St. Michael astro. station	162	01	06.00 W.
Azimuth from St. Michael astro. station to azimuth mark	359	59	55.6

The above position depends on astronomical observations made in 1891, the *longitude* being determined by moon-*culmination* and star-*occultation* methods.

datum: St. Paul Island.—The *geodetic datum* defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866*:

	°	′	″
Latitude of St. Paul Island astro. station	57	07	16.86 N.
Longitude of St. Paul Island astro. station	170	16	24.00 W.
Azimuth from St. Paul Island astro. station to azimuth mark	179	59	12

The above *latitude* and *azimuth* are based on independent astronomical determinations. The *longitude* is based on *longitudes* of the St. Paul Island and St. George Island astronomic stations, which were determined by the *chronometric method*, a *weighted mean* being obtained through *triangulation* connecting the two *islands*.

datum: Standard (California) astronomical datum of 1885.—The *geodetic datum* which is defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of triangulation station Mt. Helena	38	40	04.260 N.
Longitude of triangulation station Mt. Helena	122	38	01.410 W.
Azimuth, triangulation station Mt. Helena to triangulation station Mt. Diablo	324	01	31.04

The determination of this *datum* is described in U. S. Coast and Geodetic Survey Report for 1885, Appendix 9, page 464. Its designation is taken from the so-called "old registers" of the Division of Geodesy. It is identical with the "Yolo base datum" used in the report on the California-Nevada boundary line, U. S. Coast and Geodetic Survey Report for 1900, Appendix 3, note on page 346.

datum: tidal.—A *datum* defined by a phase of the tide. See *datum (leveling)*.

When used as reference surface for hydrographic surveys, tidal datums are termed datum planes; however, they are not planes and are not treated as planes, but as level surfaces, which are curved. The tidal datum in most general use in *geodetic* work is *mean sea level.* In *land surveying,* where boundaries and riparian rights are involved, *mean high water* and *mean low water* are sometimes tidal datums of considerable importance. See *island; shore.*

datum: Transcontinental Triangulation.—The *geodetic datum* which is defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of triangulation station Hays	38	54	50.18 N.
Longitude of triangulation station Hays	99	16	16.73 W.
Azimuth, triangulation station Hays to triangulation station La Crosse	359	44	19.00

The determination of this *datum* is described in U. S. Coast and Geodetic Survey Special Publication No. 4, The Transcontinental Triangulation and the American Arc of the Parallel, 1900, and was adopted and used for scientific studies reported in that publication and in Special Publication No. 7, The Eastern Oblique Arc of the United States and the Osculating Spheroid, 1902. It served no other purposes than stated above and no formal designation was given it.

datum: Unalaska.—The *geodetic datum* which is defined by the following *geographic position* and *azimuth* on the *Clarke spheriod of 1866:*

	°	′	″
Latitude of Unalaska astronomic station	53	52	36.45 N.
Longitude of Unalaska astronomic station	166	32	05.55 W.
Azimuth, Unalaska astronomic station to Observatory station	180	00	00

The above *datum* is based on astronomical observations made in 1896, the *longitude* being determined by the *chronometric method.*

datum: Valdez.—The *geodetic datum* defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of station Pete	60	22	44.440 N.
Longitude of station Pete	145	23	48.560 W.
Azimuth from station Pete to azimuth mark	179	44	35. 4

The *geographic position* of Pete is derived through triangulation connections from the astronomic latitude of Orca astronomic station, 1898, and the astronomic longitude of Valdez longitude station, determined by telegraph in 1905. The azimuth, Pete to azimuth mark, is an astronomic azimuth.

datum: Yakutat.—The *geodetic datum* defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of Yakutat astronomic station	59	33	50.50 N.
Longitude of Yakutat astronomic station	139	47	15.60 W.
Azimuth from Yakutat astronomic station to azimuth mark	0	00	19.5

The above position and *azimuth* were determined astronomically in 1892, the *longitude* by the *chronometric method.*

datum: Yukon.—The *geodetic datum* which is defined by the following *geographic position* and *azimuth* on the *Clarke spheroid of 1866:*

	°	′	″
Latitude of triangulation station Boundary	64	40	51.42 N.
Longitude of triangulation station Boundary	141	00	00.00 W.
Azimuth, triangulation station Boundary to triangulation station Bald	270	00	00.0

This *datum* is based on a single astronomic *station* near the crossing of the 141st Meridian and the Yukon River, and was adopted for use in computing the *triangulation* along that part of the Alaska-Canada boundary defined as being the 141st Meridian.

Davidson meridian instrument.—See under *meridian telescope.*

day.—A measure of *time* based upon the *rotation* of the earth on its axis with respect to (1) the *vernal equinox,* giving the sidereal day, and (2) the sun, giving the solar day.

day: apparent solar.—The interval of *time* from a *transit* of the sun across a given *meridian* to its next successive *transit* across the same *meridian.*

As the motion of the sun is not uniform, apparent solar days vary in length through the *year,* the maximum deviation from a *mean solar day* amounting to not quite a half minute in either direction.

day: astronomical.—A *solar day* beginning at noon.

The astronomical day may be based on either *apparent solar time* or on *mean solar time.* It begins 12 hours later than the *civil day* of the same date. Prior to 1925, the astronomical day was used as a reference in the American Ephemeris and Nautical Almanac. In 1925, and since then, the *civil day* has been used instead. An exception to the above practice is found in the American Practical Navigator (Bowditch), in the 1936 edition of which astronomical day is defined as above, while in the 1938 edition it is defined as commencing at midnight, agreeing with the *civil day.* This second definition of the term is not needed, and its use is apt to produce confusion.

day: civil.—A *solar day* beginning at midnight.

The civil day may be based on either *apparent solar time* or *mean solar time;* it begins 12 hours earlier than the *astronomical day* of the same date.

day: mean solar.—The interval of *time* from a *transit* of the *mean sun* across a given *meridian* to its next successive *transit* across the same *meridian.*

The mean solar day is derived from the average length of the *apparent solar day* throughout the *year.* See *time: mean solar.*

day: sidereal.—The interval of *time* from a *transit* of the (true) *vernal equinox* across a given *meridian* to its next successive *transit* across the same *meridian.*

The length of the sidereal day is subject to slight irregularities on account of small differences between the positions of the true *equinox,* which is affected by *precession* and *nutation,* and the mean *equinox,* which is affected by *precession* but not by *nutation.* See *time: sidereal; equinox: vernal.*

day: solar.—The interval of *time* from the *transit* of either the sun or the *mean sun* across a given *meridian* to the next successive *transit* of the same body across the same *meridian.* See *day: apparent solar; day: mean solar.*

The term *day* is frequently used in connection with a particular period in one of the longer scales, as "day of month"; in most cases, the term date is preferred.

daylight-saving time.—See under *time.*

Decca.—A continuous wave electronic navigation system for measuring distance differences with respect to fixed transmitters of known position.

A ship or aircraft starting from a known point makes use of two receivers which indicate the number of nodes encountered as it moves through the fixed phase patterns of two pairs of synchronized transmitters. The phase readings are plotted on a Decca chart containing hyperbolic lines of position.

declination (astronomy).—The *angle* at the center of the celestial *sphere* between the radius passing through a celestial body and the plane of the *celestial equator.*

Declination (astronomy) is measured by the *arc* of the *hour circle* between the celestial body and the *equator;* it is plus when the body is north of the *equator,* and minus when south of it. It corresponds to *latitude* on the earth, and with *right ascension* forms a pair of *coordinates* which defines the position of a body on the *celestial sphere.*

declination: magnetic.—See under *magnetic declination.*

declination: parallel of.—A small circle on the *celestial sphere* parallel to the *celestial equator.*

declination arc (solar compass).—A graduated *arc* on a surveyor's *solar compass* or on the *solar attachment* of an engineer's *transit,* on which the *declination* of the sun (corrected for *refraction*) is set off.

This represents one side (*polar distance*) of the *astronomical triangle,* which is solved mechanically by means of the *solar compass* or *attachment.*

declination arc (surveyor's compass).—A graduated *arc* attached to the *alidade* of a *surveyor's compass* or *transit,* on which the *magnetic declination* is set off.

When the *magnetic declination* is set off on the declination arc of a *surveyor's compass* or *transit,* a reading of the needle will give a bearing corrected for that *declination.*

declination vernier.—The *vernier* used in reading the *declination arc* on a *solar compass* or *attachment,* or the *magnetic declination* on a *surveyor's compass* or *transit.*

deflection angle.—See under *angle.*

deflection anomaly.—See under *anomaly.*

deflection of the plumb line.—The *angle* at a point on the earth (*geoid*) between the *vertical* (direction of the plumb line) and the direction of the *normal* to the *spheroid of reference* through the point. Also called deflection of the vertical or station error.

It is also equal to the *angle* between the tangents to the *geoid* and the *spheroid;* and equivalent to the *topographic deflection* corrected for the effects of *isostasy.*

deflection of the vertical.—See under *deflection of the plumb line.*

degree of curve.—See under *curve.*

dep.—The usual abbreviation for *departure* (*plane surveying*).

departure (plane surveying).—The *orthographic projection* of a line on an east-west axis of reference.

The departure (dep.) of a line is the difference of the *meridian distances* or *longitudes* of the ends of the line. It is east or positive, and sometimes called the easting, for a line whose *azimuth* or *bearing* is in the northeast or southeast quadrant; it is west or negative, and sometimes called the westing, for a line whose *azimuth* or *bearing* is in the southwest or northwest quadrant. Departure is also a term used in navigation.

depression contour.—See under *contour.*

depth of isostatic compensation.—See under *isostatic compensation.*

desk outline.*—An *outline map* of sufficiently *small scale* to be suitable for use at a desk.

This term is not recommended for use.

detail: junction.—A sketch or working diagram showing the details of the various levelings at a junction.

detailed surveys and maps.—See under *surveys and maps.*

diaphragm (surveying).—The thin glass disk on which etched lines forming a *reticle* are placed.

difference of latitude (plane surveying).—See under *latitude.*

dip of horizon.—See under *horizon.*

direct angle.—See under *angle to right.*

direct leveling.—See under *leveling.*

direct observation.—See under *observation.*

direction.—In surveying and mapping, the *angle* between a line or plane and an arbitrarily chosen reference line or plane.

At a *triangulation station,* observed *horizontal angles* are reduced to a common initial, and termed *horizontal directions.* They are usually collected into a single list of directions, with the direction of 0° placed first, and the other directions arranged and increasing in clockwise order.

direction instrument.—See under *theodolite.*

direction method, determination of astronomic azimuth.—See under *azimuth.*

direction method of adjustment (triangulation and traverse).—See under *adjustment.*

direction of gravity.—See under *gravity.*

discrepancy.—A difference between results of duplicate or comparable measures of a quantity. The difference in computed values of a quantity obtained by different processes using data from the same *survey.*

Examples: The difference in the length of two measures of the same line. The amount by which the values of a *position* of the third point of a triangle as computed from the two other points may fail to agree, when the triangle has not been corrected for closure. Discrepancy is closely associated with, but not identical with, *closure.* See *discrepancy: accumulated.*

discrepancy: accumulated.—The sum of the separate *discrepancies* which occur in the various steps of making a survey or of the computation of a *survey.*

Example: If two independently run lines of leveling over the same series of *bench marks* are computed separately, differences or *discrepancies* between the two sets of values of *elevations* will accumulate. This does not mean that the accumulated *discrepancy* will necessarily increase in magnitude.

dispersion; dispersive power.—See under *refraction: index of refraction.*

distance angle.—See under *angle.*

distribution map.—See under *map.*

diurnal aberration.—See under *aberration of light* (*astronomy*).

diurnal parallax.—See under *parallax.*

diurnal variation.—That component of a determinable magnitude which passes through a complete cycle in one day.

Such a component is said to have a periodicity of one day. Example: the diurnal variation of *magnetic declination.*

divergence (leveling).—The difference between the numerical values of two *runnings* over the same *section* of a *line of levels.* Divergence and "partial" are practically the same thing.

divergence: accumulated (leveling).—The algebraic sum of the *divergences* or "partials" for the *sections* of a *line of levels,* from the beginning of the line to any section end at which it is desired to compute the total divergence.

division; graduation.—The placing of marks on an instrument or device to represent *standard* values thereon. Also, the marks so placed.

The term division is applied especially to a circle, the value of a complete circle being absolute, that is, not depending upon an adopted *standard.* Graduation is more often applied to the placing of intermediate marks on an instrument or device (tape, thermometer) where interpolation is made between marks which represent conventional or standard values. However, no exact distinction is made between the two terms, division and graduation, as generally used. See *calibration; standardization.*

Doolittle Method.—A modification of Gauss' method of solving *normal equations.*

The Doolittle Method, with further modifications made in recent years, is used in the adjustment of survey data by members of the U. S. Coast and Geodetic Survey. It is named for M. H. Doolittle, for many years a member of the Computing Division of that Bureau, and author of a description and explanation of the method which appeared in the U. S. Coast and Geodetic Survey Report for 1878, pages 115–118.

double dating.—Dating an event according to both the *Julian* and the *Gregorian Calendars.*

In Great Britain and her colonies, the *Julian Calendar,* with March 25 as the beginning of the year, was officially replaced in 1752 by the *Gregorian Calendar,* with January 1 as the beginning of the year. The difference between the two calendars having increased from 10 days in 1582 to 11 days, the change was made by having September 2, 1752, followed immediately by September 14. To avoid confusion resulting from the change, dates according to the *Julian Calendar* were marked "old style" or "(O. S.)"; those on the *Gregorian Calendar,* "new style" or "(N. S.)". In double dating early American records, not only the day and the month, but also the year, are subject to change. In England, at the time of the change, the official year commenced on March 25, so that March 24, 1730 (O. S.) corresponded to April 4, 1731 (N. S.), but the next day was March 25, 1731 (O. S.) or April 5, 1731 (N. S.). This practice was not universal, for there was some popular use of January 1 as the beginning of the year.

double meridian distance.—See under *meridian distance.*

double zenith distance.—See under *zenith distance.*

doubly azimuthal map projection.—See under *map projection.*

draconitic (nodical) month.—See under *month.*

drag (theodolite).—A slight movement of the graduated circle of a *theodolite* produced by the *rotation* of the *alidade.*

Drag may be due to excessive friction in the instrument *centers,* to undue *tolerance* in the fit of the *centers,* or to instability in the instrument supports.

dummy pendulum.—See under *pendulum.*

dumpy level.—See under *leveling instrument.*

duplex base-line measuring apparatus.—See under *base apparatus.*

duplicate level line.—See under *level line.*

dynamic correction.—The quantity that must be added to the *orthometric elevation* of a point to obtain its *dynamic number.*

dynamic map.—See under *map.*

dynamic number.—The work required to raise a unit mass from *sea level* to a given point, expressed in *absolute units.*

For all points in a given *level surface* the dynamic number is the same, and is not very different from the height (in the unit chosen) of any point in the surface. In the metric system, the dynamic number of a point is the work required to raise a mass of 1 kilogram against the force of *gravity* from *sea level* to the *level surface* passing through the point, the work being measured in standard kilogram-meters at *sea level* in latitude 45°. In the English system, the pound and standard foot-pound are employed instead of the *meter* and standard kilogram-meter.

dynamic temperature correction (pendulum).—The *correction* to the observed period of a *pendulum* for the rate of change of its temperature.

The dynamic temperature correction is definitely related to the type of pendulum apparatus used, and is dependent especially on the mounting of the thermometer and the shape of the *pendulum.* It may vary not only in magnitude but may even change sign when the type of apparatus is changed.

dyne.—A force which, acting on a mass of one gram, imparts to that mass an *acceleration* of one centimeter per second per second. See *gal.*

The dyne is the unit of force of the *c. g. s. system* of units. Until about 1930, the dyne was used by the U. S. Coast and Geodetic Survey in stating values of gravity. Since that time, *gravity* has been reported in terms of the *gal,* the c. g. s. unit of *acceleration.*

E

easement curve.—See under *curve.*

easting.—See under *departure* (*plane surveying*).

eccentric object observed.—See under *eccentric signal.*

eccentric reduction (triangulation).—The *correction* which must be applied to an observed *direction* made with instrument or signal, or both, eccentric, to reduce the *observed value* to what it would have been if there had been no *eccentricity.*

eccentric signal.—A signal (target) which is not in the same vertical line with the *station* which it represents.

An observed *direction* to an eccentric signal is reduced by the application of a computed *correction* to what it would be if the signal were in the same vertical line with the station center which it represents. See *center: reduction to center.* The eccentric signal is known as the eccentric object observed.

eccentric station.—A *survey* point over which an instrument is centered and observations made, and which is not in the same vertical line with the *station* which it represents and to which the observations will be reduced before being combined with observations at other *stations.*

In general, an eccentric station is established and occupied when it is impracticable to occupy the station center, or when it becomes necessary in order to see points which are not visible from the station center. As the data resulting from the occupation of an eccentric station are referred to the station center, which should be marked with a permanent *monument,* the mark at an eccentric station is usually of a temporary character. See *center: reduction to center.*

eccentricity.—Amount of deviation from a center.

See *eccentricity of instrument; eccentric station; eccentricity of alidade.*

eccentricity (surveyor's compass).—An effect due to one or a combination of the following conditions: a straight line through the ends of the magnetic needle fails to pass through the center of *rotation* of the needle; the center of *rotation* of the needle is not coincident with the center of figure of the graduated circle; the *line of sight* fails to pass through the vertical axis of the instrument.

eccentricity of alidade.—The distance between the center of figure of the index points on an *alidade* and the center of figure of the graduated circle.

The index points (of *vernier* or *micrometer microscope*) are carried by the *alidade,* and any eccentricity of alidade combines with *eccentricity of circle* to form *eccentricity of instrument.*

eccentricity of circle.—The distance between the center of figure of a graduated circle and its center of *rotation.*

Eccentricity of circle is usually expressed in terms of its equivalence in seconds of *arc* on the circle. It may be made quite small by instrument-shop adjustment. Its effect on an observed *direction* is eliminated by reading the circle at equidistant points around its circumference. See *eccentricity of instrument.*

eccentricity of ellipse.—The ratio of the distance between the center and a focus of an ellipse to the length of its semi-major axis.

The semi-major and semi-minor axes are represented by a and b, respectively, and the eccentricity by e, then

$$e=\sqrt{\frac{a^2-b^2}{a^2}}.$$

eccentricity of instrument.—The combination: *eccentricity of circle* and *eccentricity of alidade.*

The effect of eccentricity of instrument on an observed *direction* is eliminated by having the *verniers* or *micrometer microscopes* with which the circle is read spaced at equal distances around the circle.

eccentricity of spheroid of revolution.—The *eccentricity of an ellipse* forming a meridional section of the *spheroid.*

eclipse.—1. The reduction in visibility or disappearance of a non-luminous body by passing into the shadow cast by another non-luminous body. 2. The apparent cutting off, wholly or partially, of the light from a luminous body by a dark body coming between it and the observer.

1. The first type of eclipse is exemplified by a lunar eclipse, the moon passing through the shadow cast by the earth; or by the passage of a satellite into the shadow cast by its planet; but when the satellite actually passes directly behind its planet, it may properly be termed an *occultation.*

2. The second type of eclipse is exemplified by a solar eclipse, caused by the moon passing between the sun and the earth. If the relative positions and distances are such that at a point on the earth the sun is completely obscured, the eclipse is total; if the distances are such that when in line with the sun, the moon is surrounded by a ring of light, the eclipse is annular; and when the moon passes to one side of a straight line from sun to observer, and shows a crescent of light, it is a partial eclipse.

ecliptic.—The *great circle* of the *celestial sphere* traced by the plane of the earth's orbit (path of center of gravity of earth-moon system).

The ecliptic represents very closely, but not exactly, the apparent path of the sun in the sky. The points in which the ecliptic intersects the *celestial equator* are the *equinoxes,* and the *angle* of intersection is the *obliquity of the ecliptic.*

ecliptic: obliquity of the.—The acute *angle* of intersection between the *ecliptic* and the *celestial equator.*

The obliquity of the ecliptic is slightly less than 23½° and is decreasing at the rate of about ½″ per year.

Egault level.—See under *leveling instrument.*

elevation.—The vertical distance of a point above or below a reference surface or *datum.*

In the fundamental horizontal *control survey* of this country, the *datum* for elevations is *mean sea level.*

elevation: adjusted.—The *elevation* resulting from the application of an *adjustment correction* to an *orthometric elevation.* Also the *elevation* resulting from the application of both an *orthometric correction* and an *adjustment correction* to a *preliminary elevation.*

elevation: field.—An *elevation* taken from the field computation of a *line of levels.*

elevation: fixed.—An *elevation* which has been adopted, either as a result of tide observations or previous adjustment of spirit leveling, and which is held at its accepted value in any subsequent *adjustment.*

elevation: orthometric.—A *preliminary elevation* to which the *orthometric correction* has been applied.

elevation: preliminary.—An elevation arrived at in the office after the *index, level, rod,* and *temperature corrections* have been applied to the observed differences of elevation and new *elevations* have been computed.

elevation: standard.—An *adjusted elevation* based on the Sea Level Datum of 1929.

ellipse: eccentricity of.—See under *eccentricity of ellipse.*

ellipse: ellipticity of.—See under *ellipticity of ellipse.*

ellipsoid.—See under *spheroid.*

ellipsoid: triaxial.—An *ellipsoid* having three unequal axes, the shortest being its polar axis, while the two longer ones lie in the plane of its *equator.* See *gravity formula, longitude term.*

elliptic arc: plane.—See *plane elliptic arc.*

ellipticity of an ellipse.—The ratio between the difference in length of the semi-axes of an ellipse and its semi-major axis.

The semi-major and semi-minor axes are represented by a and b, respectively, and the ellipticity by ϵ, then $\epsilon = \frac{a-b}{a}$. The *ellipticity of the spheroid,* referring to the earth, is called the *flattening of the earth,* or its *compression,* and is also represented by f.

ellipticity of the spheroid.—See under *flattening of the earth.*

engineering map.—See under *map.*

engineering survey.—See under *survey.*

ephemeris.—A statement presenting positions and related data for a celestial body for given epochs (dates) at uniform intervals of *time.* Also a publication containing such data for a number of celestial bodies.

Such a publication is the American Ephemeris and Nautical Almanac: this contains for specified instants of *time* the numerical values of *coordinates* of the principal celestial bodies referred to circles whose positions are independent of the diurnal *rotation* of the earth; also the elements of the positions of the reference circles, and numbers used in computing the effects upon those *coordinates* of changes in the *position* of an observer; and in general, all those phenomena relating to the heavenly bodies which may be regarded as functions of *time.* While custom has approved the use of the singular form, ephemeris, to designate a publication containing data relating to a number of celestial bodies, where specific mention is made of those bodies, the plural form, ephemerides, is used; for example, the ephemerides of the planets. For a single body, the singular form is used: for example, the ephemeris of the sun.

equal-area (authalic) latitude.—See under *latitude.*

equal-area map projection.—See under *map projection.*

equation: angle.—A *condition equation* which expresses the relationship between the sum of the measured *angles* of a closed figure and the theoretical value of that sum, the unknowns being the *corrections* to the observed *directions* or *angles,* depending upon which are used in the *adjustment.*

Sometimes called a triangle equation, an angle equation is used to make the sum of the three observed *angles* of a triangle, with *corrections* applied, equal to 180° plus the *spherical excess* of the triangle.

equation: azimuth.—A *condition equation* which expresses the relationship between the fixed azimuths of two lines which are connected by triangulation or *traverse.*

When a *survey* (*triangulation* or *traverse*) connects two lines whose *azimuths* are fixed by direct observation or by previous *surveys,* an azimuth equation is used to make the *azimuth* of either line as computed through the adjusted *survey* from the other line agree with its *azimuth* as previously fixed.

equation: condition.—An equation which expresses exactly certain relationships that must exist among related quantities, which are not independent of one another, exist a priori, and are separate from relationships demanded by observation.

Example: in measuring the *angles* of a triangle, no condition exists until all three *angles* are measured. The condition equation will then express the condition that the three measured *angles* plus certain *corrections* must equal 180° plus the *spherical excess* of the triangle. The various condition equations set up in *survey* work are defined under terms which are descriptive of the conditions: as, *angle equation, side equation, length equation, latitude equation, longitude equation, azimuth equation.*

equation: correlate.—An equation derived from an *observation* or *condition equation,* employing undetermined multipliers, and expressing the condition that the sum of the squares of the *residuals* (or *corrections*) resulting from the application of these multipliers to the *observation* or *condition equations* shall be a minimum.

In the *least-squares* adjustment of *triangulation,* correlate equations are formed directly from the *observation* or *condition equations,* there being as many correlate equations as there are *corrections* to be determined, but only as many undetermined multipliers (correlates or correlatives) as there are *observation* or *condition equations.* From these correlate equations, the *normal equations* are formed, equal in number to the undetermined multipliers which constitute the unknowns in the *normal equations.* The solution of the *normal equations* determines values for the multipliers which, when substituted in the correlate equations, give values for the corrections which will satisfy the *observation* or *condition equations,* make the observations and their functions consistent among themselves, and at the same time make the adjusted values the most probable that can be derived from the given observations.

equation: error.—The probability equation which expresses the laws of the occurrence of *accidental errors.*

The error equation is the basis of the method of *least squares,* used in the *adjustment of observations* for determining the *most probable value* of a result from those observations.

equation: Laplace.—See under *Laplace equation.*

equation: latitude.—A *condition equation* which expresses the relationship between the fixed *latitudes* of two points which are connected by *triangulation* or *traverse.*

When a *survey* (*triangulation* or *traverse*) connects two points whose *latitudes* have been fixed by direct observation or by previous *surveys,* a latitude equation is used to make the *latitude* of either point as computed through the *survey* from the other point agree with its *latitude* as previously fixed.

equation: length.—A *condition equation* which expresses the relationship between the fixed lengths of two lines which are connected by *triangulation.*

When a section of *triangulation* connects two lines whose lengths are fixed by direct measurement or by previous *triangulation,* a length equation is used to make the length of either line as computed through the adjusted *triangulation* from the other line agree with its length as previously fixed.

equation: longitude.—A *condition equation* which expresses the relationship between the fixed *longitudes* of two points which are connected by *triangulation* or *traverse.*

When a *survey* (*triangulation* or *traverse*) connects two points whose *longitudes* have been fixed by direct observation or by previous *surveys,* a longitude equation is used to make the *longitude* of either point as computed through the *survey* from the other point agree with its *longitude* as previously fixed.

equation: normal.—An equation derived from *observation* or *condition equations* or from *correlate equations,* expressing the condition that the sum of the squares of the *residuals* (or *corrections*) resulting from the substitution in the *observation* or *condition equations* of factors obtained from the normal equations either directly or through the *correlate equations* shall be a minimum.

In a *least-squares* adjustment, *corrections* are desired to observed values which are connected together by a series of *observation* or *condition equations,* the number of such equations being smaller than the number of observed values on which they depend. The basic equations are transformed into normal equations, either directly or through the medium of *correlate equations,* which express the condition stated above and which contain the same number of unknowns as there are equations. Factors obtained from the solution of normal equations, either directly or through the *correlate equations,* are applied to the *observation* or *condition equations* to obtain the desired *corrections.*

equation: observation.—A *condition equation* which connects interrelated unknowns by means of an observed function.

Example: An *angle equation:* the unknowns are the *corrections* to the *observed angles;* the function is the sum of those *observed angles* expressed as a *closing error.*

Alternate definition: A *condition equation* connecting the function observed and the unknown quantity whose value is sought.

equation: perpendicular (traverse).—A *condition equation* to reduce to zero the algebraic sum of the *projections* of the separate lines of a *traverse* upon perpendiculars to a fixed line with which the *traverse* forms a closed figure.

The perpendicular equation and the *azimuth equation* together provide for the removal of *errors of closure* of a *traverse* which forms a loop with some fixed line such as a line of adjusted *triangulation,* by determining *corrections* to the *observed angles* of the *traverse.* The *projections* of the lines of the *traverse* upon lines which are perpendicular to a fixed line correspond to *departures* of those lines when the fixed line is considered the *meridian* of reference.

equation: side.—A *condition equation* which expresses the relationship between the various sides in a *triangulation* figure as they may be derived by computation from one another.

A side equation is used to make the computed length of a triangle side the same for all routes through the *triangulation* whereby it may be derived.

equation of time.—See under *time.*

equator: astronomic.—The line on the surface of the earth whose *astronomic latitude* at every point is 0°. Also termed the terrestrial equator.

Due to the *deflection of the plumb line,* the astronomic equator is not a plane curve. However, the *verticals* at all points on it are parallel to one and the same plane, the plane of the *celestial equator;* that is, the *zenith* at every point on the astronomic equator lies in the celestial equator.

equator: celestial.—The *great circle* on the *celestial sphere* whose plane is perpendicular to the axis of *rotation* of the earth.

In astronomic work, because parallel lines meet at infinity, the plane of the celestial equator is sometimes assumed to pass through the point of observation.

equator: geodetic.—The circle on the *spheroid* midway between its poles of *revolution.*

The geodetic equator is the line of 0° *geodetic latitude,* from which *geodetic latitudes* are reckoned, north and south, to 90° at the poles. The plane of the geodetic equator cuts the *celestial sphere* in a line coinciding with the *celestial equator,* because the axis of the *spheroid* of reference is by definition parallel to the axis of rotation of the earth.

equator: terrestrial.—See under *equator: astronomic equator.*

equatorial horizontal parallax.—See under *parallax: diurnal parallax.*

equatorial intervals.—The *angles,* expressed in units of *time,* between the various lines which compose the *reticle* of an astronomical *transit* and the mean position of those lines.

The equatorial interval for a given line of a *reticle* is equal to the time interval required for the image of a star on the *equator* (*declination,* 0°) to travel from the line in question to the mean line of the *reticle,* or from the mean line to the line in question, the instrument being adjusted in the *meridian.* In *time* determinations with an *astronomical transit,* equatorial intervals are used in reducing incomplete observations to a mean value.

equiangular spiral.—See under *rhumb line.*

equiangulator.—An *astrolabe.*

equinoctial colure.—See under *colure.*

equinox.—A point of intersection of the *celestial equator* and the *ecliptic.*

There are two equinoxes: the *vernal equinox,* apparently traversed by the sun at the beginning of spring; and the *autumnal equinox,* apparently traversed by the sun at the beginning of autumn.

equinox: autumnal.—The point of intersection of the *celestial equator* and the *ecliptic,* apparently traversed by the sun in passing from north to south.

equinox: vernal.—The point of intersection of the *celestial equator* and the *ecliptic,* apparently traversed by the sun in passing from south to north.

The vernal equinox is also called the "first point of Aries" and "first of Aries." It is the point from which *right ascension* is reckoned along the *celestial equator* and *celestial longitude* along the *ecliptic.* The position of the true *equinox* is affected by *precession* and *nutation,* while the position of the mean *equinox* is affected by *precession* but not by *nutation.* See *day: sidereal; time: sidereal.*

equipotential surface (geodesy).—A surface having the same potential of *gravity* at every point.

Having the same potential of *gravity* at every point, no work is done when a body is moved about in such a surface. When bodies of the same mass are moved from one equipotential surface to another, the same amount of energy is developed or expended, accordingly as the bodies are lowered or raised, and regardless of the route followed. In lifting a unit mass from *sea level* to any other specified equipotential surface, the amount of work required is the same at the *equator* as at the poles: at the *equator* the height of any equipotential surface above *sea level* is greater and the force of gravity at that surface less than for the same equipotential surface at the poles. An equipotential surface is a *level surface.* A particular equipotential surface is identified by its *dynamic number.*

equivalent map projection.—See under *map projection: equal-area map projection.*

error (general).—The difference between an observed or calculated value of a quantity and the ideal or true value of that quantity.

Since the ideal or true value of a quantity, with few exceptions (see below), cannot be known with exactness, the term error is applied to a difference between an observed or calculated value of a quantity and some value determined by established procedure and used in lieu of the ideal or true value. Exceptions: the ideal or true value of a quantity can be known with exactness when it is (a) mathematically determinable, independent of observation, as for example, the sum of the three angles of a plane triangle is 180°; and (b) when it is a conventional value established by authority, as for example, the length of the *meter* (unit) defined by the *International Prototype Meter* at the International Bureau of Weights and Measures. Errors are of various kinds, depending upon how and where they originate. The term error with appropriate adjective or qualifying clause is used to designate the kind of error: as, *accidental error, error of observation,* etc.

error: accidental.—An error, sometimes designated as an irregular *error,* produced by irregular causes whose effects upon individual observations are governed by no fixed law connecting them with circumstances and which therefore can never be subjected to a priori computation.

Theoretically, an accidental error is composed of an infinite number of independent infinitesimal *errors,* all of equal magnitude, each as likely to be positive as negative. In practice, an accidental error is composed of an indefinitely large number of elemental *errors,* each as apt to be positive as negative.

It is upon the probabilities expressed in the above definition that the principle of *least squares* is based; and it is to the elimination of accidental errors only that *least squares* may properly be applied.

error: average.—The mean of all the *errors* taken without regard to sign.

Average error is sometimes defined as the mean without regard to sign of the mean of the plus *errors* and the mean of the minus *errors.* Since there will be about the same number of plus *errors* as of minus *errors* in a well-balanced series of observations, the two methods of obtaining the average error will give practically the same result. In computing the average error, the *residual errors* (residuals) are used.

error: clamping.—A *systematic error* in observations made with a *repeating theodolite* due to strains set up by the clamping devices of the instrument.

error: constant.—A *systematic error* which is the same in both magnitude and sign through a given series of observations.

Constant errors are sometimes considered as forming a class distinct from *systematic errors,* but the distinction is unimportant, and in practice constant errors are treated as a type of *systematic error.* A constant error tends to have the same effect upon all the observations of the series or portion thereof under consideration, and therefore does not usually have any influence on the computed *probable error* of the series. An example of a constant error is the index error of a *precision* instrument.

error: external.—See under *error: theoretical* (or *external*) *error.*

error: instrumental.—A *systematic error* arising from imperfect condition of the instrument used.

Instrumental errors may arise from conditions that are constant with an instrument, as *errors* of graduation of a circle; or they may arise from lack of complete adjustment of some part of the instrument, as the *error of collimation.* Instrumental errors are susceptible of laboratory determination; they may be eliminated from a result by a suitable program of field procedure.

error: mean.—See under *error: mean-square error.*

The use of mean error should be avoided because of possible confusion with *average error,* which has a different meaning.

error: mean of the errors.—See under *error: average error.*

The use of mean of the errors should be avoided because of possible confusion with *mean error,* which has a different meaning.

error: mean-square.—The quantity whose square is equal to the sum of the squares of the individual *errors* divided by the number of those *errors.*

In the computation of the mean-square error from observations of unequal weight, account must be taken of the *weights.* In practice, *residual errors* are used in determining a mean-square error. The use of *mean error,* in place of mean-square error, should be avoided, because of possible confusion with *average error* which has a different meaning.

error: parallactic.—An *error* due to *personal* or *instrumental parallax.*

error: personal.—A *systematic error* caused by an observer's personal habits in making observations, or due to his tendency to react mentally and physically in the same way under similar conditions.

A *systematic error* arising from personal habits of an observer, such as standing in the same position relative to the end of a tape when measuring the length of a line, may be eliminated from a result by an observing program (shift of position) which makes the *error* positive for half of the observations and negative for the remainder of the observations. See *parallax: instrumental.*

A *systematic error* arising from the mental or motor reaction of an observer to the sensory perception of a phenomenon may be eliminated from a result either by an observing program which neutralizes positive values with negative values, or by determining the size and sign of the *error* by some mechanical means. In the determination of *time,* the personal error is termed *personal equation.*

error: probable.—A quantity of such size that the probability of the occurrence of an *error* larger than that quantity is the same as the probability of the occurrence of an *error* of lesser magnitude.

If the *errors* in a series of observations be arranged in order of magnitude without regard to sign, and if the series be indefinitely large, the probable error will fit the middle place in that list of errors.

Expressed in another way, the probable error of a result is a quantity such that the probability that a second determination obtained under the same conditions as the first will differ from the first determination by less than the probable error is the same as the probability that such difference will be greater than the probable error.

The probable error of the result of a series of observations is a function of the *accidental errors* attending the individual observations of the series. A *systematic error* may often remain in the series with little effect on the size of the probable error. Probable error does not mean an *error* that is more apt to occur than an *error* of any other size. Theoretically, a probable error is derived from the *errors* in an indefinitely large series of observations; in practice, a probable error is calculated from the *residual errors* in a series of limited length. Probable errors are useful in comparing the *accuracy* of similar observations, and serve as criteria in prescribing degrees of *accuracy* and *precision* to be attained.

error: residual.—The difference between any value of a quantity in a series of observations, corrected for known *systematic errors,* and the value of the quantity obtained from the combination or adjustment of that series.

Residual errors correspond to the *corrections* obtained in a *least-squares* adjustment. They are sometimes called simply *errors,* and sometimes residuals. The latter term is generally used in referring to actual values in a specific computation. In practice, it is the residual errors which enter into a computation of *probable error.*

error: systematic.—An *error* whose algebraic sign and, to some extent, magnitude bear a fixed relation to some condition or set of conditions.

In its broadest sense, the term systematic error includes *constant errors.* Under similar conditions, systematic errors tend to be repeated; if the conditions do not change, the *error* will be constant. The inclusive definition is preferred.

Systematic errors are regular, and therefore are subject to a priori determination. They are generally eliminated from a series of observations by a suitable observing program or by computation, before the application of *least-squares* for the elimination or reduction of *accidental errors.* Systematic errors are divided into *theoretical* or *external errors, instrumental errors,* and *personal errors,* according to their origin and nature.

error: theoretical (or external).—A *systematic error* arising from natural physical conditions, outside the observer.

Theoretical errors are exemplified by the effect of *atmospheric refraction* in *spirit leveling;* by the changes in the length of a tape due to its thermal expansion; by the effects of atmospheric pressure on *elevations* determined with a *barometer.* Theoretical errors may be controlled to some extent by making observations only when natural conditions are favorable, as measuring the length of a line with a steel tape at night or in cloudy weather.

Theoretical errors are determined by means of formulas and observed data obtained especially for the purpose, as determining the length of a metal tape by suitable formula using the *coefficient of thermal expansion* and the observed temperature of the tape.

error: true.—See under *error (general).*

True error corresponds to *error (general)* defined above; its use should be avoided.

error equation.—See under *equation.*

error of closure.—The amount by which a value of a quantity obtained by *surveying* operations fails to agree with another value of the same quantity held fixed from earlier determinations or with a theoretical value of the quantity.

See *error of closure, traverse; error of closure, triangle; error of closure, levels; error of closure, horizon.*

error of closure, angles.—The amount by which the actual sum of a series of *angles* fails to equal the theoretically exact value of that sum. See *error of closure of horizon; error of closure of triangle.*

error of closure in azimuth.—The amount by which two values of the *azimuth* of a line, derived by different *surveys* or along different routes, fail to be exactly equal to each other.

Generally, one value is derived by computations carried through the *survey* (*triangulation* or *traverse*) ; the other is an *adjusted* or fixed value determined by an earlier or a more *precise survey,* or by independent *astronomical* observations.

error of closure in leveling.—The amount by which two values of the *elevation* of the same *bench mark,* derived by different *surveys* or through different *survey* routes or by independent observations, fail to be exactly equal to each other.

The closure may be developed in a line of *leveling* which starts and ends on different *bench marks* whose *elevations* are held fixed; or it may start and close on the same *bench mark.*

error of closure of horizon.—The amount by which the sum of a series of *horizontal angles* measured between adjacent lines in a complete circuit of the *horizon* fails to equal exactly 360°. See *horizon: closing the horizon.*

error of closure of triangle.—The amount by which the sum of the three *observed angles* of a triangle fails to equal exactly 180° plus the *spherical excess* of the triangle. See *equation: angle equation.*

error of closure, traverse.—The amount by which a value of the *position* of a traverse station as obtained by computation through a *traverse* fails to agree with another value of the same station as determined by a different set of observations or route of *survey.*

The *traverse* may run between two stations whose *positions* are held fixed, or it may start from and end on the same station. In either case there are two values for the *position* of the final station; one known before the *traverse* was computed, the other obtained by computations carried through the *traverse;* the difference between these is the *error of closure.* It may be resolved into closure in latitude, and closure in longitude (or departure). The total closure is also spoken of as closure in position.

error of collimation.—See under *collimation.*

error of observation.—The difference between an observed value of a quantity and a value adopted as representing the ideal or true value of that quantity.

Errors of observation are composed of either one or both of two general classes of *error; accidental errors* and *systematic errors.* Sometimes *constant errors* are considered as forming a third class, but more often these are treated as belonging with the *systematic errors.* Errors of observation are also classified for study according to their origin, as *theoretical errors* or *external errors, instrumental errors,* and *personal errors.* The algebraic sign of an error of observation is determined from the equation: error = observed value − adopted ideal value.

The sign of the *error* is opposite that of the corresponding *correction.*

existent corner (United States public-land surveys).—See under *corner.*

explement of angle.—See under *angle.*

exploratory survey.—See under *survey.*

exterior angle.—See under *angle.*

extra foresight.—See under *foresight.*

eyepiece micrometer.—See under *micrometer: ocular.*

F

factor: conversion.—That factor by which the numerical value of a measurement made in one system of units must be multiplied to arrive at the numerical value of the same measurement in another system of units.

Fahrenheit scale.—A temperature scale in which 32° marks the freezing point and 212° the boiling point of water at 760 mm. barometric pressure.

falling (United States public-land surveys).*—The distance, measured along an established line from its intersection with a *random line,* to a *corner* on which the *random line* was intended to close.

fathometer.—An echo-sounding instrument used for depth measurements in water.

For descriptions of several types of fathometers, see U. S. Coast and Geodetic Survey Special Publication No. 143, Hydrographic Manual.

fiducial mark.—An index line or point. A line or point used as a basis of reference.

field elevation.—See under *elevation.*

field position.—See under *position.*

figure of the earth.—See under *geoid, spheroid.*

finder circle.—A small *vertical circle* with coarse *graduations* and accessory *spirit level* of low sensitivity attached to an astronomical *telescope* in a plane perpendicular to its *horizontal axis,* and used in placing the *telescope* in approximate position for observing.

With a computed *altitude* at the proposed time of observation, the *telescope* is pointed in the direction of the object to be observed; when that object comes into the field of view, the finder circle will have served its purpose, and the observations will be made with the more precise apparatus provided for the purpose.

finder telescope.—A small *telescope* of low power and wide angular field of view, attached to and parallel with a larger *telescope* of much higher power and very restricted field of view, and used in pointing the larger *telescope* at a celestial object.

The finder telescope serves as a sighting device; a celestial object is easily sighted in the finder telescope, and brought to the center of its *reticle,* when it will be visible in the large *telescope* also.

first-order bench mark.—See under *bench mark.*

first-order control surveys.—See under *first-order work* (*control surveys*).

first-order level.—See under *leveling instrument.*

first-order leveling.—See under *leveling.*

first-order traverse.—See under *traverse.*

first-order triangulation.—See under *triangulation.*

first-order work (control surveys).—The designation given *survey* work of the highest prescribed order of *precision* and *accuracy.*

Such *surveys* were formerly called primary; in 1921, representatives of the various Federal map-making and map-using organizations changed the designation to *precise;* and in 1925, the Federal Board of Surveys and Maps adopted the present designation (first-order), and established *standards* for it by prescribing criteria for acceptable work. See under *triangulation; leveling.*

Fischer level.—See under *leveling instrument.*

fix.—The position on a *map* of a point of observation obtained by *surveying* processes. Also, the act of determining such a *position.*

fixed elevation.—See under *elevation* and also *position: adjusted.*

fixed position.—See under *position: adjusted.*

flare triangulation.—See *triangulation: flare.*

flash apparatus.—An auxiliary apparatus used in timing a *pendulum* during observations for *intensity of gravity.*

The flash apparatus used in *pendulum* observations is composed of a *telescope* for observing, an electric light for illumination, and an electro-magnet which is operated by a break-circuit *chronometer* and which controls a system of shutters admitting periodic flashes of light into the *receiver* and onto the mirror of the *pendulum* whence they are reflected back into the *telescope,* and coincidences between *pendulum* and *chronometer* observed.

flattening (of the earth).—The ratio of the difference between the equatorial and polar radii of the earth (major and minor semi-axes of the *spheroid*) and its equatorial radius (major semi-axis).

The flattening of the earth is the *ellipticity* of the *spheroid* and equals the *ellipticity of an ellipse* forming a meridional section of the *spheroid.* If a and b represent the major and minor semi-axes of the spheroid, and f is the flattening of the earth,

$$f=\frac{a-b}{a}.$$

The magnitude of the flattening is sometimes expressed by stating the numerical value of the reciprocal of the flattening, $\frac{a}{a-b}$. The flattening of the earth is also termed its compression.

flexure (pendulum).—The bending of a swinging *pendulum,* due to its lack of perfect rigidity.

The effect of the bending of a swinging *pendulum* due to its lack of perfect rigidity is to increase the period of vibration; that is, the flexible *pendulum* swings less rapidly than the rigid *pendulum.* The effect may be regarded either as due to the change in the moment arm of the various parts of the *pendulum* as it bends, or to energy storage in the bent *pendulum.*

The effect of the bending is to increase the period of vibration in both positions of the reversible *pendulum.* The sign of the resulting correction depends upon the exact geometrical construction of the *pendulum.* In relative determinations of gravity, account is not taken of the bending of the *pendulum,* but the term flexure is applied to the movement of the pendulum support, communicated to it by the swinging *pendulum.* See *flexure* (*pendulum support*).

flexure (pendulum support).—The forced movement of a pendulum support caused by the motion of the swinging *pendulum.*

The horizontal component of the force acting on the *knife edge* of a swinging *pendulum* causes the support to move in unison with the *pendulum,* thereby affecting the period of its *vibration.* Though very small, this *flexure* of the *pendulum* support necessitates the application of a *correction* to the *pendulum* period. There are several methods of ascertaining the amount of the *flexure,* of which two have been used in the work of the U. S. Coast and Geodetic Survey: the static method, by which the displacement caused by a known force is measured in linear units; and the optical method, using an *interferometer* to measure the actual displacement in terms of wave lengths of light. The term *flexure* is also applied to the bending of a swinging *pendulum,* account of which is taken in absolute determinations of the value of *gravity.* See *flexure* (*pendulum*).

focal length.—See under *focus* (*lens*).

focus (lens).—The point to which rays of light converge after passing through a lens system.

If the incident rays are parallel they come to a focus in the (primary) focal plane, and it is the distance along the axis of the lens system from the *second nodal point* of the lens to this plane which is called the focal length of the lens.

focus: sidereal.—The position of the principal focal plane of a lens system.

A camera or *telescope* is said to be in sidereal focus when incident rays from a great distance come to a *focus* in the plane of the photographic plate or of the *reticle.* Sometimes called the solar focus.

foot.—A *unit of length* equal to 12 *inches* exactly or to one-third of a *yard.*

foot plate (leveling).—A disk of metal used as a rod support at a *turning point* in *leveling operations.*

One type of foot plate had a rod point, such as a knob, attached to its upper side, while the lower side had small projections to prevent lateral motion of the foot plate when it was pressed against the ground. In another type, the upper surface of the foot plate was dish-shaped (concave). The use of foot plates as rod supports has been superseded by metal pins driven firmly into the ground.

foresight (general).—A sight on a new survey point, made in connection with its determination; or a sight on a previously established point, to close a circuit.

foresight (leveling).—A reading on a rod held on a point whose *elevation* it is intended to determine.

The foresight may be on a point of unknown *elevation,* or on a previously established *bench mark* to close a circuit. Foresights are sometimes called minus sights, as they are usually subtracted from the *elevation* of the instrument (H. I.) to obtain the *elevation* of the rod point. This is not always the case, as the new point may be at a greater *elevation* than the instrument, as a mark on a wall, or a point on the roof of a tunnel. The term foresight is preferred over minus sight.

foresight: extra (leveling).—The rod reading made at an *instrument station* in a *line of levels* and on a *leveling rod* standing on a *bench mark* or other point NOT in the continuous *line of levels.*

In spirit leveling there may be one or more extra foresights from a single *instrument station* or *set-up,* but there can be only one *backsight* and one *foresight* from any one *instrument station.*

forward azimuth.—See under *azimuth: geodetic.*

fourth-order traverse.—See under *traverse.*

fractional section (United States public-land surveys).—See under *section.*

fractional township (United States public-land surveys).—See under *township.*

free-air anomaly.—See under *anomaly.*

free-swinging pendulum.—See under *pendulum.*

French legal meter.—See under *meter.*

fundamental tables: deformation of the geoid and its effect on gravity.—Tables giving the deformation of the *geoid* and its effect on *gravity,* computed for masses of unit density extending to various distances above and below the surface of the *geoid.*

Fundamental tables serve as the basis for the preparation of special tables corresponding to particular assumptions respecting density, *isostasy,* etc. Several such fundamental tables have been prepared, each designed for a particular effect:

a). Fundamental Tables for Reducing Observed Gravity Values, by G. Cassinis and P. Dore (1937) determine the direct effect on *gravity* of masses of unit density extending to various distances above and below *sea level.* This direct effect is known as the Hayford effect; it neglects the differences of *elevation* between the *spheroid* and the *geoid.*

b). Fundamental Tables: The Deformation of the Geoid and its Effect on Gravity (U. S. Coast and Geodetic Survey Special Publication No. 199) by Walter D. Lambert and Frederic W. Darling (1936) determine the indirect effect of masses of unit density extending to various distances above and below *sea level;* this indirect effect is known as the *Bowie effect;* it takes into account the differences of *elevation* between the *spheroid* and the *geoid.*

c). Fundamental Tables for the Deflection of the Vertical (a U. S. Coast and Geodetic Survey publication now in press) by Frederic W. Darling give the horizontal effect (*deflection of the vertical*) of masses of unit density extending to various distances above and below *sea level.* For mathematical development and formulas, see Bulletin Geodesique: No. 57, January-February-March 1938 and New Series No. 9, July 1, 1948.

G

gal.—An *acceleration* of one centimeter per second per second.

The gal is the unit of *acceleration* of the c. g. s. system of units and, since about 1930, has been used by the U. S. Coast and Geodetic Survey in stating values of *gravity.* Before that date, the *dyne,* a unit of force, was used for the purpose. (The real unit was dyne/gram.) While the term gal has not been formally adopted by the International Association of Geodesy, it is now in general use in those countries where *gravity* observations are being made. It is expressed symbolically by cm/sec.^{2} A milligal is 0.001 gal. The term gal is not an abbreviation; it was invented to honor the memory of Galileo.

geländereduktion.—See *terrain correction.*

general base map.—See under *map: Topographic Map of the United States.*

general highway and transportation map.—See under *map: Transportation Map of the United States.*

general topographic map.—See under *map: Topographic Map of the United States.*

general utility map.—See under *map: Topographic map of the United States.*

general utility map of the United States.—See under *map: Topographic Map of the United States.*

general utility topographic map of the United States.—See under *map*: *Topographic Map of the United States.*

geocentric coordinates.—See under *coordinates.*

geocentric latitude.—See under *latitude.*

geocentric parallax.—See under *parallax: diurnal parallax.*

geodesic.—A *geodesic line.*

geodesic line.—A line of shortest distance between any two points on any mathematically defined surface. Also termed a *geodesic.*

While, in *geodetic* work, a geodesic line on a *spheroid* of reference is sometimes called a *geodetic line, geodetic* as applied to lines is going out of use, and *geodesic* is preferred.

geodesy.—The science which treats mathematically of the figure and size of the earth.

The term geodesy is often used to include both the science which must depend upon determinations of the figure and size of the earth from direct measurements made on its surface (*triangulation, leveling,* astronomic and *gravity* determinations), and the art which utilizes the scientific determinations in a practical way and is usually termed *geodetic surveying* or geodetic engineering.

geodetic.—Signifying basic relationship to the earth in which the curvature of its *sea-level* surface is taken into account.

In horizontal *control surveys,* the term geodetic is applied to operations and results based on the *ellipsoid of revolution* (*spheroid*). In *spirit leveling, elevations* are referred—or intended to be referred—to the *geoid.* In determining *elevations* by *vertical angles, elevations* are referred (in the ideal case where *deflections of the vertical* are available) to the *ellipsoid of revolution.* In ordinary practice, since *deflections of the vertical* are not usually available, the results are a mixture, and are referred to neither surface exactly.

geodetic azimuth.—See under *azimuth.*

geodetic azimuth mark.—See under *azimuth mark.*

geodetic control.—See under *control.*

geodetic coordinates.—See under *coordinates.*

geodetic datum.—See under *datum.*

geodetic equator.—See under *equator.*

geodetic latitude.—See under *latitude.*

geodetic leveling.—See under *leveling.*

geodetic line.—The shortest-distance line between any two given points on the surface of the *spheroid.*

Sometimes called a *geodesic line,* a geodetic line is a line of double curvature, and usually lies between the two *normal section lines* which the two points determine. If the two terminal points are in nearly the same latitude, the geodetic line may cross one of the normal section lines. It should be noted that, except along the equator and along the meridians, the geodetic line is not a plane curve and cannot be sighted over directly. However, for conventional triangulation the lengths and directions of geodetic lines differ inappreciably from corresponding pairs of normal section lines.

geodetic longitude.—See under *longitude.*

geodetic meridian.—See under *meridian.*

geodetic parallel.—See under *parallel.*

geodetic position.—See under *position.*

geodetic survey.—See under *survey.*

geodetic surveying.—See under *surveying.*

geographic; geographical.—Signifying basic relationship to the earth considered as a globe-shaped body.

The term geographic is applied alike to data based on the *geoid* and on a *spheroid.* In *geodetic surveys* in this country, coordinated data consisting of *latitudes, longitudes, azimuths,* and lengths of lines, are recorded and published under the general title of *geographic positions.* For particular usage of the two forms, geographic, geographical, see *-ic; -ical.*

geographic center.—The geographic center of an area on the earth has been defined as that point on which the area would balance if it were a plate of uniform thickness. In other words, it is the center of gravity of that plate.

The geographic center of continental United States (exclusive of Alaska) is in the eastern part of Smith County, Kansas, latitude 39°50′, longitude 98°35′. The geographic centers of the various States are given in the U. S. Geological Survey Bulletin 817, "Boundaries, Areas, Geographic Centers, and Altitudes of the United States and the Several States."

geographic coordinates.—See under *coordinates.*

geographic exploration survey.—See under *survey.*

geographic latitude.—See under *latitude.*

geographic longitude.—See under *longitude.*

geographic meridian.—See under *meridian.*

geographic parallel.—See under *parallel.*

geographic position.—See under *position.*

geographic survey.—See under *survey.*

geographical mile.—See under *mile: nautical.*

geoid.—The figure of the earth considered as a *mean sea-level* surface extended continuously through the continents.

The actual geoid is an *equipotential surface* to which, at every point, the plumb line (direction in which *gravity* acts) is perpendicular. It is the geoid which is obtained from observed *deflections of the vertical,* and is the surface of reference for astronomical observations and for geodetic leveling. Theoretical geoids obtained with computed values of *deflections of the vertical* include the *compensated geoid* and the *isostatic geoid.*

geoid: compensated.—A theoretical *geoid* derived from the actual *geoid* by the application of computed values of the *deflection of the vertical* which depend upon the *topography* and *isostatic compensation.*

The data upon which to base the effect of *topography* and *isostatic compensation* are obtained from readings of *topographic maps;* the effect is then computed in accordance with the assumptions made with respect to *isostasy,* that is, the depth and distribution of *isostatic compensation.* A method for accomplishing this was developed by Hayford, who accepted the *Pratt theory of isostasy.* If the theory and assumptions with respect to *isostasy* were exact and there were no *anomalies,* the compensated geoid would agree with the *spheroid* of reference.

geoid: isostatic.—An ideal *geoid* derived from the *spheroid* of reference by the application of computed values of the *deflection of the vertical* which depend upon the *topography* and *isostatic compensation.*

The computed values of the *deflection of the vertical* used in obtaining the isostatic geoid are similar to those for the *compensated geoid,* but of opposite signs. If the theory and assumptions with regard to *isostasy* were exact and there were no *anomalies,* the isostatic geoid would agree with the actual *geoid.*

geoid contour.—A line on the surface of the *geoid* of constant *elevation* with reference to the surface of the *spheroid* of reference.

Geoid contours represent differences in *elevation* between the *geoid* and the *spheroid.* Geoid contours depend on the surface of reference. The same *geoid* referred to different surfaces of reference will give different sets of geoid contours.

geologic survey.—See under *survey.*

geological survey.—See under *survey.*

geometric latitude.—See under *latitude: parametric (geometric or reduced) latitude.*

geometric map projection.—See under *map projection: perspective map projection.*

geophysics.—The science of the earth with respect to its structure, composition, and development.

Geophysics is a branch of experimental physics dealing with the earth, including its atmosphere and hydrosphere. It includes the sciences of dynamical geology and physical geography, and makes use of *geodesy,* geology, seismology, meteorology, oceanography, magnetism, and other earth sciences in collecting and interpreting earth data. Geophysical methods have been applied successfully to the identification of underground structures in the earth and to the search for structures of a particular type, as for example, those associated with oil-bearing sands.

gisement.—The *angle* between the *grid meridian* and the *geographic meridian.*

The term "gisement" is used in connection with the *military grid,* sometimes being called the "declination of grid north," and reckoned east and west from geographic north. Gisement is not used with the *State coordinate systems,* where the corresponding *angle* on the *transverse Mercator grid* is the convergence of the local with the central geographic meridian, and is designated by $\Delta\alpha$. In the *Lambert grid,* the angle is known as the "mapping angle," designated by θ, and called the "theta angle."

globe.—A spherical body. See under *globe: celestial globe; terrestrial globe.*

globe: celestial.—A sphere, on the outer surface of which, by means of symbols and reference lines, stars are shown in positions and magnitudes determined from the earth.

Usually shown also are the outlines of the constellations or star groups. Essentially, a celestial globe is a sphere to the outside of which star maps have been fitted.

globe: terrestrial.—A sphere, on the outer surface of which, by means of symbols and reference lines, the features of the surface of the earth are shown in relative positions.

Essentially, a terrestrial globe is a sphere to the outside of which *maps* of the surface of the earth have been fitted. See *globe, gore.*

globe, gore.—A lune-shaped *map* which may be fitted to the surface of a *globe* with a negligible amount of distortion.

A *terrestrial* or *celestial globe* may be constructed by covering a sphere with a complete set of *maps,* each having the form of a lune of such narrow width that it may be mounted on the sphere without appreciable stretching or shrinking.

globe, horizon ring.—A graduated ring fitted to a *globe* in such manner that its plane contains the center of the *globe,* and it can be adjusted into the plane of the *horizon* for any point on the *globe.*

The horizon ring is used in scaling *angles* around the *horizon* for a given point.

globe, meridian ring.—A graduated ring fitted to a *globe* in such manner that its plane contains the poles of the *globe,* and it can be adjusted into the plane of any given *meridian* on the globe.

A meridian ring is used for scaling *angles* along a *meridian.*

globe, time dial.—An adjustable circular disk, graduated in time units (0 hours to 24 hours), attached to a *globe* with its center coincident with a pole of the *globe.*

A time dial can be adjusted to show the relation between local *time* and the *time* of any other *meridian.*

globular map projection.—See under *map projection.*

gnomonic map projection.—See under *map projection.*

Golofnin Bay datum.—See under *datum.*

goniasmometre.—A compact surveying instrument for observing *horizontal angles* and *bearings,* and consisting of a vertical cylinder divided horizontally into two parts: the lower edge of the upper part is graduated in circular measure and revolves on the lower part, which carries a *vernier* on its upper edge. A magnetic needle is centered in the upper part, which is also provided with slits or a *telescope* for sighting purposes.

An instrument used in France, and serving the same purposes as a *surveyor's compass* or *transit.*

goniometer.—In *surveying,* an instrument for measuring *horizontal angles* or *directions,* such as a *theodolite.*

In general, goniometer is a term applied to various instruments for measuring *angles,* as in crystallography, anthropology, etc.

grad (grade).—An *angle* at the center of a circle, subtended by one four-hundredth part of its circumference. See *angle (general).*

grade.—Rate of slope or degree of inclination. See *gradient.* Example: a 1 to 100 grade; a 1-percent grade.

grade correction, tape.—See under *tape.*

gradient (topography).—A *grade* expressed as a tangent of the *angle of inclination.*

Example: a 1 to 100 *grade* is a gradient of .01.

gradienter.—An attachment to an engineer's *transit* with which an *angle of inclination* is measured in terms of the tangent of the *angle* instead of in degrees and minutes.

A gradienter may be used as a telemeter in observing horizontal distances.

graduation.—See under *division.*

graticule.—A network of lines representing geographic parallels and meridians forming a *map projection.*

Gravatt level.—See under *leveling instrument.*

Gravatt leveling rod.—See under *leveling rod.*

gravimeter (geodesy).—A weighing device or instrument of sufficient sensitivity to register variations in the weight of a constant mass when the mass is moved from place to place on the earth and thereby subjected to the influence of *gravity* at those places.

A typical gravimeter consists of a spring which changes in length under the load of a constant mass as the instrument is moved from place to place and thereby affected by changes in *gravity.* Gravimeters are employed in determining differences in the intensity of *gravity* between an initial or base station at which the value of gravity is known or assumed and at nearby points for which values of *gravity* are desired. Gravimeters are also termed gravity meters.

gravitation.—In general, the mutual attraction between masses of matter (bodies). In *geodesy,* the mutual attraction between the earth and bodies on or near its surface.

Gravitation is the component of *gravity* which acts towards the earth.

gravitation: constant of.—The Newtonian constant of gravitation, being the constant G in the formula $F=G\frac{m_1 m_2}{r^2}$, where F is the attractive force between two bodies of masses m_1 and m_2 expressed in grams, r is the distance in centimeters between the two bodies, and the time unit is the *mean solar second.*

Various values of the constant of gravitation which have become available in recent years are as follows:

(a) $(6.670 \pm 0.005) \times 10^{-8}$ c. g. s. units

This is by Paul R. Heyl, reported in the Bureau of Standards Journal of Research, December 1930. It is the value used in U. S. Coast and Geodetic Survey Special Publication No. 199, Tables for Determining the Form of the Geoid and its Indirect Effect on Gravity, 1936.

(b) $(6.664 \pm 0.002) \times 10^{-8}$ dyne. $\text{cm}^2.\text{g}^{-2}$

This is the value adopted in the Smithsonian Physical Tables, edition of 1934.

(c) $(6.673 \pm 0.003) \times 10^{-8}$ $\text{cm.}^3\text{g}^{-1}.\text{sec}^{-2}$

This is the most recent determination by Heyl, reported in the Journal of Research of the National Bureau of Standards, July 1942. It agrees so well with the 1930 result that the conclusion is reached that, for the method used (the *torsion balance*), the limit of possibilities for increasing the *precision* has been reached.

gravity.—That force which tends to pull bodies towards the earth: that is, to give bodies weight.

Gravity is the resultant of two opposing forces: *gravitation* and the *centrifugal force* due to the *rotation* of the earth. See *gravity: intensity of gravity.*

gravity: Clairaut's Theorem.—A theorem connecting the *ellipticity* of the earth with the coefficient of $\sin^2 \phi$ of the *formula for theoretical gravity* or with the difference between *gravity* at the poles and *gravity* at the equator.

This means that every *gravity* formula implies a particular value for the *ellipticity* of the *spheroid* of reference. Let g_p and g_e represent *gravity* at the poles and at the *equator,* respectively, and let the *formula for theoretical gravity* be written $g=g_e\,(1+\beta \sin^2 \phi + \text{smaller terms})$. Also, assume values for ϕ of 90° and 0°, and neglect the smaller terms.

Then $\beta=\frac{g_p-g_e}{g_e}$ and Clairaut's Theorem is written as follows: $\beta=\frac{g_p-g_e}{g_e}=\frac{5m}{2}-f+\text{smaller terms}$, f being the *ellipticity* and m the ratio of *centrifugal force* at the *equator* to *gravity* at the equator, or $\frac{\omega^2 a,}{g_e}$, where ω is the angular velocity of *rotation* of the earth in *radians* per second and a is the semi-major axis (equatorial radius) of the *spheroid.*

As originally stated by Clairaut, the smaller terms were neglected. For an exact *ellipsoid* we have, to a high degree of *accuracy,* the formula

$$\beta=\frac{5m}{2}-f+\frac{17}{14}mf.$$

Upon first consideration, Clairaut's Theorem may seem paradoxical: an increase in the *flattening of the earth, f,* apparently diminishing the increase in *gravity* from *equator* to pole. This is explained by the fact that the theorem applies, not to values on the physical surface of the *ellipsoid,* but to values on a *level surface*—any *level surface* lying outside all attracting matter. In the case of the *geoid,* or *sea-level surface,* which has a comparatively small amount of matter outside it, Clairaut's Theorem is applied by means of certain conventions in the reduction to that surface of values of *gravity* observed outside the physical surface of the earth. If the *ellipticity* of the physical surface of the earth is conceived to change but that surface still remain a *level surface,* the distribution of density within the *level surface* must change accordingly, and Clairaut's Theorem will still hold.

The increase in *gravity* from *equator* to poles according to the *International Gravity Formula* has been analyzed by Hammer as follows:

Centrifugal acceleration	+3.39 *gals*	
Free-air effect	+6.63	net +1.78 *gals*
Mass-shape effect	−4.85	
Total change, *equator* to poles	+5.17 *gals*	

The free-air effect is due to the difference of the distances from the center of the earth of the attracted particle when at a pole and when at the *equator,* the attractions being in the inverse ratio of the squares of the respective distances. But the inverse-square law is correct only when the dimensions of the attracting body are negligible in comparison with the distances involved, a condition that does not hold in the present instance. Near its surface, the terrestrial *ellipsoid* does not attract in exact accordance with the inverse-square law. The *correction* which is applied to the free-air effect to care for this condition is the mass-shape effect given in this and the next paragraph.

If the terrestrial *ellipsoid* were homogeneous, the free-air effect and the mass-shape effect would be more nearly equal, and the increase in *gravity* from *equator* to poles would be composed as follows:

Centrifugal acceleration $= mg =$	+3.39 *gals*	
Free-air effect $= 2fg = 5mg/2 =$	+8.48	net +0.85 *gal*
Mass-shape effect $= 9mg/4 =$	−7.63	
Total change, *equator* to poles $= 5mg/4 =$	+4.24 *gals*	

gravity: direction of; direction of the force of gravity.—The direction indicated by a plumb line.

It is perpendicular to the surface of the *geoid.* See *nadir, zenith.*

gravity: formula for theoretical.—A formula expressing *gravity* on the *spheroid* of reference in terms of *geographic position,* it being assumed that the *spheroid* of reference is a *level surface.*

If the *spheroid* of reference is one of *revolution,* all *meridians* are alike and the *longitude* can not appear in the formula (see *gravity formula, longitude term*); furthermore, since the *spheroid* is symmetrical with respect to the *equator,* only even functions of the *latitude* can appear in the formula. *Gravity* increases toward the poles, both because the centrifugal *acceleration* due to the earth's *rotation* decreases as a pole is approached and because the mass-attraction of the *spheroid* is greater at the poles than at the equator.

Gravity on the surface of a *spheroid of revolution* is expressed by either of the following commonly used formulas:

$$g = g_e\ (1 + \beta \sin^2 \phi + \text{smaller terms})$$

$$g = g_{45}\ (1 - \gamma \cos 2\phi + \text{smaller terms})$$

where g is *gravity* on the surface of the *spheroid* in *geographic latitude* ϕ, g_e is *gravity* at the *equator,* g_{45} is gravity at *latitude* 45°, and β and γ are constants. For numerical values of g_e and constants appearing in the first formula above, see *gravity: Clairaut's Theorem; Helmert's gravity formula of 1901; International Gravity Formula;* and *gravity formula, longitude term.*

In the approximate formulas, the smaller terms are often omitted. If this is done, our surface of reference is a *spheroid of revolution* lying, at latitude 45°, 19 *meters* above an exact *ellipsoid* of *revolution* having the same axes as the spheroid.

gravity: Helmert's gravity formula of 1901.—A development of the *formula* for *theoretical gravity* utilizing the *gravity* observations available at the time (1901), but not fitted to any preassigned value of the earth's *ellipticity.*

Referred to the Potsdam value of absolute *gravity,* Helmert's gravity formula of 1901 is as follows:

$$g = 978.030\ (1 + 0.005302 \sin^2 \phi - 0.000007 \sin^2 2\phi).$$

While the *International Gravity Formula* was based on a preassigned value of the earth's *ellipticity,* the above formula was not, but it was used in determining a value for that *ellipticity,* namely 1/298.2. The coefficients $g_e = 978.030$ and $\beta = 0.005302$ were determined from the observations.

Attempts made to determine the coefficient of $\sin^2 2\phi$ in the same way were abandoned because of the large *probable errors* obtained, and the value 0.000007 was assumed from theoretical considerations based on the work of Darwin and Wiechert on a self-attracting rotating mass of the size of the earth. Such a mass, unless homogeneous, will not take on the form of an exact *ellipsoid,* but will be depressed in middle *latitude* below an exact *ellipsoid* having the same major and minor axes. The amount of this depression will depend upon the law used for the variation of density with respect to distance from the center of the earth. Darwin and Wiechert assumed different laws, but both found a depression of 3 meters in *latitude* 45°. This depression corresponds to the difference between 0.0000059 and 0.000007, the corresponding coefficients in the International and Helmert formulas.

gravity: Helmert's gravity formula of 1915.—A development of the *formula for theoretical gravity,* based on a *triaxial ellipsoid,* and including a *longitude term.* See *gravity formula, longitude term.*

gravity: intensity of.—The force with which *gravity* acts, expressed in suitable units.

Intensity of gravity may be expressed either as a force (*force of gravity*) expressed in *dynes;* or as an *acceleration* expressed as centimeters per second per second. In the geodetic work of the U. S. Coast and Geodetic Survey, before 1930, intensity of gravity was stated as a force, in *dynes;* since then, it has been stated as an *acceleration,* in *gals.*

gravity: International Gravity Formula.—A development of the *formula for theoretical gravity,* based on the assumptions that the *spheroid* of reference is an exact *ellipsoid* of *revolution* having the dimensions of the International Ellipsoid of Reference (Madrid, 1924), rotating about its minor axis once in a *sidereal day;* that the surface of the *ellipsoid* is a *level surface;* and that *gravity* at the *equator* equals 978.049 *gals.*

Omitting terms which are so small as to be negligible for practical purposes, the International Gravity Formula is as follows:

$$g = 978.049\ (1 + 0.0052884 \sin^2 \phi - 0.0000059 \sin^2 2\phi).$$

The International Gravity Formula was adopted by the International Association of Geodesy at the Stockholm meeting, 1930. The purpose was not primarily to represent the *gravity* observations then available, although the $g_e = 978.049$ *gals* was based on those observations, but rather it was intended to put the determination of the *figure of the earth* from *gravity* data on the same basis as the determination of its figure from *deflections of the vertical.* This formula is based on the Potsdam value for absolute *gravity.*

gravity anomaly.—See under *anomaly: free-air anomaly.*

gravity apparatus: Brown gravity apparatus.—See under *Brown gravity apparatus.*

gravity formula.—See under *gravity: formula for theoretical gravity.*

gravity formula, longitude term.—A suggested additional term for the *formula for theoretical gravity,* derived from the *longitude* on a *spheroid* of reference having three unequal axes.

With this additional term, the *formula for theoretical gravity* would be as follows:

$g = g_e\ [1 + \beta \sin^2 \phi - \beta_1 \sin^2 2\phi + c \cos^2 \phi \cos 2\ (\lambda - \lambda_0)]$
where g_e is the mean value of *gravity* at the *equator,* and c, like β and β_1 is a dimensionless number.

As always, the *formula for theoretical gravity* implies a *spheroid* of definite shape. When a longitude term of the type indicated above is included, the *spheroid* is no longer an *ellipsoid* of *revolution,* but an *ellipsoid* having three unequal axes (*triaxial ellipsoid*), the shortest of which is its polar axis (corresponding to the axis of *rotation* of the earth), while the two longer ones lie in the plane of the *equator.* The longer equatorial axis lies in the *meridian* plane λ_0 and $\lambda_0 \pm 180°$; the shorter in the *meridian* plane $\lambda_0 \pm 90°$. These two equatorial axes or diameters differ by $\pm 4\ ca$; the difference of each semiaxis from a mean is $\pm ca$, and from each other $\pm 2\ ca$.

The form of the longitude term is not arbitrary. In theoretical investigations on the attraction of nearly spherical bodies, it is convenient to work with spherical harmonics. These are mathematical expressions involving *latitude* and *longitude.* They are of different degrees, the harmonics increasing in complexity as their degree increases.

The additional term involving *longitude* in the *gravity formula* is the spherical harmonic term of lowest degree not already present, though in partly disguised form, in the ordinary *gravity formula* and not excluded from it for sufficient theoretical reasons. (The excluded terms are proportional to $\cos \phi \cos \lambda$, $\cos \phi \sin \lambda$, $\sin \phi$, $\sin 2\phi \cos \lambda$, and $\sin 2\phi \sin \lambda$.) The idea of an *ellipsoid* of three unequal axes as a possible surface of reference is by no means new. There was, however, no continuing interest in the idea until Helmert and his assistant, Berroth, each published in 1915 his calculations on which were based *gravity formulas* containing a longitude term of the type given above. *Helmert's gravity formula of 1915* is as follows:

$g = 978.052\ [1 + 0.005285 \sin^2\phi - 0.000007 \sin^2 2\phi + 0.000018 \cos^2 \phi \cos 2\ (\lambda + 17°)]$.

In the formula, east *longitude,* λ, is positive. The maximum equatorial semiaxis (radius) is 115 *meters* longer than the mean equatorial semiaxis (radius) and 230 *meters* longer than the minimum. The maximum axis lies in the *meridian* plane of $\lambda = 17°$ west and 163° east of Greenwich. The minimum axis lies in the meridian plane $\lambda = 73°$ east and 107° west of Greenwich. The mean *ellipticity* of a *meridian* is 1/296.7.

Since 1915, various discussions of the accumulating mass of *gravity* data have tended to confirm the reality of a longitude term of the same general size and character as that proposed by Helmert. Studies of the *deflections of the vertical* have likewise tended to confirm that general result. This does not mean, however, that a *triaxial ellipsoid* is likely to find favor as a surface of reference for *triangulation* and *deflections of the vertical.* The mathematical complications of such a surface are too great. And since one of the purposes of studying *gravity* observations is to determine the *figure of the earth* and to compare the results with those obtained from *deflections of the vertical,* it is convenient to use the same surface of reference for both and therefore omit the longitude term from the *formula for theoretical gravity.*

It would appear from the most recent study of the longitude term (Jeffreys, 1942–3), that a longitude term of the type derived by Helmert and others is not the only spherical harmonic term needed to represent existing widespread variations of *gravity.* Jeffreys confirmed the existence of a longitude term of the general character and magnitude just discussed, and tentatively determined a few other spherical harmonic terms of low degree; he found, however, that the number and distribution of existing *gravity* observations were inadequate for a satisfactory determination of those terms.

The argument against including a longitude term in the *formula for theoretical gravity* applies with even greater force to the additional terms found by Jeffreys. The mathematical complexities attending the use of a figure of reference which these additional terms would imply are too great for practical problems. The significance of the longitude term and of the other terms proposed by Jeffreys, which are also longitude terms of a sort, is mainly geophysical. These terms represent widespread systematic variations in *gravity* and in *deflections of the vertical.* They represent also general widespread departures from isostatic equilibrium and therefore imply the existence of long-continuing stresses in the earth's crust. The problems they represent are geological and geophysical: problems of how the configuration of the continents and oceans on the known geological structures are related to the departures from equilibrium which are implied by the additional terms.

While it is of great geological and geophysical interest to improve the *formula for theoretical gravity* by the addition of spherical harmonic terms of low degree, the question of how far to continue the addition of such terms must be left to the future. It seems probable, however, that consideration of the usefulness of this procedure will limit such additions to spherical harmonic terms of rather moderate degree.

gravity meter.—See under *gravimeter.*

gravity station.—A *station* at which observations are made to determine the value of *gravity.*

great circle.—The line of intersection of the surface of a sphere and any plane which passes through the center of the sphere.

The shortest distance between any two points on a sphere is along the *arc* of a great circle connecting the two points. Great circles on the *celestial sphere* which are given particular designations are the *equator,* the *ecliptic, meridians, hour circles, prime verticals, colures,* and *horizons.* The shortest distance on an *ellipsoid* of *revolution* is a *geodetic line* (a *geodesic*), which is not a plane curve except for the *equator* (a circle) and the *meridians* (ellipses). In *cartography,* the *gnomonic* is the only *map projection* on which a great circle is represented, in all instances, as a straight line. The *gnomonic projection* for a *map* of the United States computed by the U. S. Coast and Geodetic Survey is based on a sphere having the same volume as the *ellipsoid of reference* (*Clarke spheroid of 1866*).

great circle line.—In *land surveying,* the line of intersection of the surface of the earth and the plane of a *great circle* of the *celestial sphere.*

The term great circle line is proposed for use in descriptions of methods for establishing *parallels* of *latitude* (*standard parallels* and correction lines) in *surveys* of the public lands of the United States. Since the earth is not a sphere, a great circle line is but an approximation to a *great circle* and, due to the *deflection of the vertical,* will not, as surveyed, lie in a single plane.

Greenwich Civil Time.—See under *time.*

Greenwich Meridian.—See under *meridian.*

Greenwich Sidereal Time.—See under *time.*

Gregorian Calendar.—See under *calendar.*

grid.—A network composed of two sets of uniformly-spaced straight lines intersecting in right angles.

In surveying and mapping, the term grid is applied to a *plane-rectangular coordinate system* imposed upon a *geographic coordinate* system. See *State coordinate systems.*

grid: military.—See under *military grid.*

grid azimuth.—See under *azimuth.*

grid bearing.—See under *bearing.*

grid coordinates.—See under *coordinates.*

grid distance.—See under *grid length.*

grid inverse.—The computation of *grid length* and *grid azimuths* from *grid coordinates.*

grid length.—The distance between two points as obtained by computation from the *plane rectangular coordinates* of the points.

In the *State coordinate systems,* a grid length differs from a *geodetic length* by the amount of a correction based on the *scale factor* for the given line.

grid meridian.—See under *meridian.*

guide meridian (United States public-land surveys).—See under *meridian.*

Gunter's chain.—See under *chain.*

H

hack (United States public-land surveys).*—A horizontal V-shaped notch, cut into the trunk of a tree at about breast height.

hack chronometer.—See under *chronometer.*

half section (United States public-land surveys).—See under *section.*

hand level.—See under *leveling instrument.*

hanging level.—See under *level.*

Harrebow-Talcott method, latitude determination.—See under *zenith-telescope method, latitude determination.*

Hassler base-line measuring apparatus.—See under *base apparatus.*

Hayford-Bowie method of isostatic reduction.—A method of computing the effect of *topography* and *isostatic compensation* on *gravity* by which the effect of *topography* is computed directly and then corrected for the effect of *isostatic compensation.*

The mechanics of this method involve the use of the *Hayford gravity templates.*

Hayford-Bullard (or Bullard) method of isostatic reduction.—A method by which the topographic effect of an infinite slab of density 2.67 and a thickness equal to the *elevation* of the *gravity station* is first computed, and then corrected for curvature of the *sea-level* surface and for difference of *elevation* between the station and the *topography.*

The first step in the computation gives the ordinary Bouguer correction for *topography:* the second step takes account of the departure of the actual *topography* from a smooth cap or plate of thickness equal to the *elevation* of the station.

The application of the *curvature correction* for the lettered zones reduces the effect of the plane slab to that of a plateau or cap extending to the outer limits of those zones and curved to the mathematical surface of the earth. Account is taken of the *topography* by applying a *correction* for the deviations of the *topography* from the surface of the plateau or cap.

This method was devised by E. C. Bullard as a substitute for the *Hayford-Bowie method of isostatic reduction* for the lettered zones of the *Hayford gravity templates;* it is described in U. S. Coast and Geodetic Survey Special Publication No. 232, Pendulum Gravity Measurements and Isostatic Reductions, by Clarence H. Swick, 1942.

Hayford deflection templates.—See under *template (templet).*

Hayford effect (gravity).—See under *fundamental tables: deformation of the geoid and its effect on gravity (a).*

Hayford gravity anomalies; Hayford anomalies.—See under *anomaly: isostatic anomaly.*

Hayford gravity templates.—See under *template (templet).*

height of instrument.—1. In *spirit leveling:* the height of the *line of sight* of a *leveling instrument* above the adopted *datum.* 2. *Stadia surveying:* the height of the center of the *telescope* (*horizontal axis*) of *transit* or *telescopic alidade* above the ground or station mark. 3. *Trigonometrical leveling:* the height of the center of the *theodolite* (*horizontal axis*) above the ground or station mark.

heliocentric parallax.—See under *parallax: annual.*

heliotrope.—An instrument composed of one or more plane mirrors, so mounted and arranged that a beam of sunlight may be reflected by it in any desired direction.

Placed over a survey station, a heliotrope is used to direct a beam of sunlight toward a distant survey station, where it can be observed with a *theodolite.* It provides an excellent target in observing *horizontal directions,* such targets having been observed on at distances of over 150 miles and approaching 200 miles. There are several types of heliotropes, carrying various names, but differing only in details of mechanical arrangement and construction. Heliotropes are sometimes used for sending messages, using the Morse code conveyed by short and long flashes of light; when especially equipped for the purpose, such instruments are termed heliographs.

hemispherical map.—See under *map.*

high-water line.—The place on the bank or shore up to which the presence and action of water is so usual and long continued as to impress on the *bed of the stream* a character distinct from that of the *banks* with respect to vegetation and the nature of the soil.

The high-water line is the *boundary line* between the *bed* and the *bank of a stream*. The mean high-water line usually determines the boundary of the land of the riparian proprietor.

highway map.—See under *map*.

homalographic map projection.—See under *map projection*.

horizon.—A *great circle* on the *celestial sphere* whose plane is perpendicular to the direction of the plumb line.

The direction of the plumb line is sometimes referred to as the *direction of gravity*, and *direction of the force of gravity*. In *surveying*, the plane of the horizon is determined by means of a *spirit level*. See *horizon: apparent (visible) horizon*.

horizon: apparent (visible).—The irregular line along which rays from the point of observation are tangent to the surface of the earth.

The apparent horizon is the line where the visible surface of the earth appears to meet the sky. When the apparent horizon is formed by the surface of a body of water, it is sometimes used as a reference in observing *vertical angles*. See *horizon: dip of*.

horizon: artificial.—A device consisting of a plane reflecting surface which can be adjusted to coincide with the plane of the *horizon*.

One form of artificial horizon consists of a dish or trough filled with mercury, or an amalgam of mercury and tin, the upper surface of which is free, and assumes a horizontal position. Another form is a plane mirror of glass or other material, equipped with *spirit levels* and leveling screws so that it can be adjusted into the plane of the *horizon*.

In observing a celestial body such as a star or the sun, the *angle* is measured between the body as seen direct (with *transit* or *theodolite*) or reflected (in the horizon glass of a *sextant*) and its image as seen reflected in the artificial horizon: this is a *vertical angle*, and is double the *altitude* of the body.

horizon: closing the.—Measuring the last of a series of *horizontal angles* at a station required to make the series complete around the *horizon*.

At any station, the sum of all *horizontal angles* between adjacent lines should equal 360°. The amount by which the sum of the *observed angles* fails to equal 360° is the *error of closure*. This is distributed as a *correction* for closure among the *observed angles* to bring their sum to exactly 360°. The *error* and the *correction* are of opposite signs.

horizon: dip of.—The *vertical angle* between the plane of the *horizon* and a line tangent to the *apparent (visible) horizon*.

horizontal angle.—See under *angle*.

horizontal axis (theodolite or transit).—The axis about which the *telescope* of a *theodolite* or *transit* rotates when moved vertically.

It is the axis of *rotation* which is perpendicular to the *vertical axis* of the instrument and to the *axis of collimation* of the *telescope*. It should coincide with the line through the centers of the pivots which support the *telescope*. For an instrument in complete adjustment, it occupies a horizontal position, and when the *telescope* is rotated around it, the *axis of collimation* will define a *vertical plane*: deviations from this condition are measured with a *striding level* or with a *hanging level*.

horizontal direction.—A *direction* in a horizontal plane.

horizontal parallax.—See under *parallax: diurnal parallax*.

Horrebow-Talcott method, latitude determination.—See under *zenith-telescope method, latitude determination*.

hour angle.—The angle between the plane of the *hour circle* passing through a celestial body and the plane of the *celestial meridian*.

The hour angle is reckoned from the *meridian* (0 hours or 0°) westward through 24 hours (360°). It may be measured by the *angle* at the pole between an *hour circle* and the *meridian*, or by the *arc* of the *equator* which is intercepted by those circles.

hour circle.—Any *great circle* on the *celestial sphere* whose plane is perpendicular to the plane of the *celestial equator*.

Hour circles are also called circles of *declination*. The hour circle which contains the *zenith* is identical with the *celestial meridian*.

hygrometric.—Relating to the relative humidity or comparative amount of moisture in the atmosphere.

Since the atmosphere penetrates the pores or cells of material bodies in varying degrees depending upon the substances of which they are composed, the amount of moisture which it contains will affect the shapes and dimensions of certain instruments and equipment used in *surveying* and mapping. For this reason it is necessary to select materials which are not sensitive to hygrometric conditions for the construction of *leveling rods*, *plane-table* sheets, etc., and for the construction and printing of maps.

hypsographic feature.*—A *topographic feature* with *elevations* portrayed with reference to *sea level*.

hypsographic map.—See under *map*.

hypsography.*—*Topography (relief)*, referred to a *sea-level datum*. The science or art of describing *elevations* (heights) of land surfaces with reference to *sea level*.

hypsometer.*—An instrument used in determining *elevations* of points on the earth's surface in relation to *sea level* by determining atmospheric pressure through observation of the boiling point (temperature) of water at each point. Also an instrument used in forestry for determining heights of trees.

Determination of heights of mountain summits by observing the boiling point of water on the summits has been much used by explorers.

The term hypsometer is also used to designate one who measures *elevations* of the land, or who constructs *maps* or models to show land *elevations*. This is a rare use.

hypsometric.—Relating to *elevation* above a *datum*, usually *sea level*.

In a limited sense, hypsometric relates to *elevations* above *sea level* determined with a *hypsometer*.

hypsometric feature.*—Disapproved. See under *hypsographic feature*.

hypsometric map.—See under *map: hypsographic*.

hypsometry.*—The art of determining, by any method, surface *elevations* on the earth with reference to *sea level*.

The determination of *elevations* by means of either *mercurial* or *aneroid barometers* is sometimes called barometric hypsometry.

hypsometry: barometric.—See under *hypsometry*.

I

-ic; -ical.—Suffixes employed to convert certain terms into adjective form, the two adjectives derived from the same root word sometimes having slightly different meanings, but often employed according to custom or personal preference, without differentiation.

While it seems desirable to employ the shorter suffix, -ic, for adjectives having a direct and intimate relationship to the root word, and the longer form, -ical, to form adjectives of more general and broader applicability, this cannot be adopted as an exact procedure, and it is proposed that custom be considered, and in the work of this Bureau, the forms be used as recommended below.

1. geodetic, geodetical; geodesic, geodesical.—Each of these terms has appeared in technical literature. The longer forms, geodetical, and geodesical, are now practically obsolete. Geodesic was at one time employed to designate a class of *spirit leveling,* but at present is largely limited to use in a mathematical sense. The following forms, defined elsewhere, are proposed for use in this Bureau: *geodetic azimuth; geodetic equator; geodetic latitude; geodetic longitude; geodetic meridian; geodetic parallel; geodetic position; geodetic survey;* and *geodesic line.*

2. astronomic; astronomical.—Astronomers have preferred and used the longer form, *astronomical.* Surveyors have employed both forms, often without apparent differentiation in meaning, though they have accepted the astronomers' use of *astronomical* for terms of general applicability. In the publications of this Bureau, with some exceptions, the shorter form, *astronomic,* has been employed in recent years where there is an intended contrast with the term *geodetic,* and it is believed that this practice should be adopted insofar as is compatible with established practice. The following terms, defined elsewhere, are accordingly proposed for use in this Bureau: *astronomic azimuth; astronomic coordinates; astronomic equator; astronomic latitude; astronomic longitude; astronomic meridian; astronomic parallel;* astronomic station; and *astronomical day; astronomical leveling;* astronomical methods; *astronomical refraction; astronomical theodolite; astronomical time; astronomical transit; astronomical traverse; astronomical triangle; astronomical unit.*

3. geographic; geographical.—The following forms are proposed for use in this Bureau: *geographic center; geographic equator; geographic latitude; geographic longitude; geographic meridian; geographic parallel; geographic position; geographic survey;* geographical boundary; *geographical mile;* geographical organization, survey, or society.

4. geologic; geological.—The following forms are proposed for use in this Bureau: geologic data; geologic investigation or survey; geological organization, survey, or society; geological era; geological time.

5. geophysical.—The form geophysical is used to the exclusion of any other that might be derived from the term *geophysics.*

iced-bar apparatus.—See under *base apparatus.*

identification posts.—Posts of wood or other suitable material, appropriately marked and inscribed, and placed near *survey stations* to aid in their recovery and identification.

Identification posts also serve as guard posts, calling attention to the stations which they serve, thus giving protection against their accidental destruction. Designated as supplemental posts for survey monuments, identification posts were recommended for use in a report of the Committee on Control adopted by the Federal Board of Surveys and Maps, March 14, 1939.

idle pendulum.—See under *pendulum.*

impersonal micrometer.—See under *micrometer: transit micrometer.*

inch.—A *unit of length* defined by the equivalence: 1 *meter* equals 39.37 inches exactly.

The relationship, 1 meter equals 39.37 inches, was established by Act of Congress, July 28, 1866, but was put into practical effect only after the United States had received copies of the *International Prototype Meter.* In 1893, the Superintendent of Standard Weights and Measures, with the approval of the Secretary of the Treasury, declared the *International Prototype Meter* to be the *standard* of length, with the customary unit, the *yard,* to be derived therefrom in accordance with the Act of July 28, 1866. The *yard* is accepted as equal to 36 inches exactly. See under *meter: National Prototype Meter.*

inclination of the horizontal axis.—The *vertical angle* between the *horizontal axis* of a surveying or astronomical instrument and the plane of the *horizon.*

Inclination of the horizontal axis is measured with a *striding level* or a *hanging level.* It causes the *axis of collimation* of a *theodolite* or *transit* to describe an inclined plane instead of a *vertical plane* when the *telescope* is rotated about the *horizontal axis* of the instrument. This produces an *error* in an observed *horizontal direction* of an object not situated in the plane of the *horizon,* and requires the application of a *correction for inclination of the horizontal axis.*

inclination of the horizontal axis: correction for.—A *correction* applied to an observed *horizontal direction* to eliminate any *error* that may have been caused by the *horizontal axis* of the instrument not being exactly horizontal.

If the *horizontal axis* of the instrument is not exactly horizontal, the *axis of collimation* will not cut the *horizon* at a point directly underneath (or above) an observed point: that is, a plane described by the *axis of collimation* when the *telescope* is rotated about its *horizontal axis* will not be a *vertical plane.* As the *inclination of the horizontal axis* may involve two conditions: the failure of the *horizontal* and *vertical axes* of the instrument to meet exactly at a right angle, and a possible deviation of the *vertical axis* from the direction defined by the plumb line, a determination of this *correction* requires that both the inclination of the axis and the *altitude* of the observed object be known.

index correction (leveling).—See under *correction.*

index map.—See under *map.*

index of refraction.—See under *refraction.*

indirect leveling.—See under *leveling.*

indirect observations.—See under *observation.*

initial point (United States public-land surveys).*—The point from which is initiated the survey of the *principal meridian* and *base line* controlling the survey of the public lands within a given area.

For list of initial points, *principal meridians,* and *base lines,* and the areas governed thereby, see page 138, section 141, General Land Office Manual of Instructions for the Survey of the Public Lands, edition 1930.

instrument station (leveling).—See under *station.*

instrumental error.—See under *error.*

instrumental parallax.—See under *parallax.*

intensity of gravity.—See under *gravity.*

interferometer.—An optical instrument which employs the principle of the interference of light waves to determine the amount of displacement. It is used in length standardizations, in comparing end standards, etc.

The interferometer employed in observations with the *pendulum* is a slightly modified form of the instrument used by Michelson, its inventor. With this instrument the slight movement (*flexure*) of the *receiver* which is caused by the swinging *pendulum* is measured.

interior angle.—See under *angle.*

International Map of the World map projection.—See under *map projection: International Map of the World.*

international meter.—See under *meter.*

International Prototype Meter.—See under *meter.*

intersection: point of.—See under *curve.*

intersection station.—See under *station*

interval: stadia (leveling).—The length of rod subtended between the top and bottom cross wires in the *leveling instrument* as seen projected against the face of the *leveling rod.*

invar.—An alloy of nickel and steel having a very low *coefficient of thermal expansion.*

Invar was discovered by C. E. Guillaume of the International Bureau of Weights and Measures, Paris. Having a *coefficient of thermal expansion* of about one-twenty-fifth that of steel, it has replaced steel in the construction of tapes for measuring geodetic *base lines,* and is used in other places where a metal of that characteristic is desired. Invar is used in the construction of some *leveling rods* and *first-order leveling instruments.* Invar is also used in the construction of *pendulums.*

invar pendulum.—See under *pendulum.*

invar rod.—See under *leveling rod.*

invar tape.—See under *base tape.*

invariable pendulum.—See under *pendulum.*

inverse: geographic.—See under *inverse position computation.*

inverse position computation.—The derivation of the length, and the *forward* and *back azimuths* of a *geodetic line* by computation based on the known *geodetic positions* of the ends of the line.

This is called an inverse position computation (or an inverse) because it reverses the usual order of computation, where a new *geodetic position* is derived by computation, using its *azimuth* and distance from a known *geodetic position.*

island.*—A body of land extending above and completely surrounded by water at *mean high water.*

The above definition is of universal application in *surveying* and mapping operations in the United States, and is fully supported by federal court decisions relating to the ownership of land. In foreign affairs, however, international negotiations are affected by various and different conceptions of what constitutes the boundary line between the land and the water.

isometric (conformal) latitude.—See under *latitude.*

isoperimetric curve.—A line on a *map projection* along which there is no variation from exact *scale.*

There are two isoperimetric curves passing through every point on an *equal-area map projection.* This characteristic gives that class of projections some preference for *engineering maps.*

isostasy.—A condition of approximate equilibrium in the outer part of the earth, such that the gravitational effect of masses extending above the surface of the *geoid* in continental areas is approximately counterbalanced by a deficiency of density in the material beneath those masses, while the effect of deficiency of density in ocean waters is counterbalanced by an excess of density in the material under the oceans.

The basic principle of isostasy is that the masses of prismatic columns of the outer part of the earth extending to some constant depth below the surface of the *geoid* are proportional to the areas of their *sea-level* sections, regardless of their surface *elevations.* The depth below *sea level* to which these hypothetical columns extend is known as the *depth of isostatic compensation,* and is somewhere between 60 and 70 *statute miles.* The area of the *sea-level* section of a unit hypothetical column for which *isostatic compensation* is ordinarily complete has not been determined; it may be uniform for all parts of the earth, or may vary with the character of the *relief* in the same continental regions.

While isostasy is generally accepted as a proven principle, there are several theories as to the relative distribution of the matter producing this condition of equilibrium, the two principal ones being those of Airy and of Pratt.

The Pratt theory, announced by J. H. Pratt in 1855, assumed that the continents and islands project above the average *elevation* of the solid surface of the earth because of material of less density beneath them: the higher the surface, the lesser the density below. Under the Pratt theory, complete equilibrium exists at some uniform depth below sea level: the same depth for ocean areas as for land masses. It is the theory accepted by geodesists and by many geologists, and used in the investigations of isostasy by Hayford and Bowie of the U. S. Coast and Geodetic Survey.

The Airy theory, announced by G. B. Airy in 1855, postulated the continents and islands as resting hydrostatically on highly plastic or liquid material, with roots or projections penetrating the inner material of the earth, just as icebergs extend downward into the water. The greater the *elevation,* the deeper the penetration. It has been called the "Roots of Mountain Theory," and has the support of some geologists. The fundamental difference between the two theories is that Pratt postulated uniform depth with varying density, while Airy postulated uniform density with varying depth. The term "isostasy," meaning equal pressure, was first proposed by C. E. Dutton in a paper entitled "On Some of the Greater Problems of Physical Geology," delivered before the Philosophical Society of Washington on April 27, 1889, and printed in Bulletin No. II of that Society.

isostatic adjustment.—The process of restoring and maintaining that condition of equilibrium in the so-called crust of the earth which is known as *isostasy.*

The distribution of material in the outer part of the earth is undergoing continual change by the operation of erosion, sedimentation, and other natural forces. The unbalanced condition which would naturally result from such disturbing processes is offset by the movement of material at considerable depths below the surface of the earth. See *isostatic compensation: depth of isostatic compensation.*

isostatic anomaly.—See under *anomaly.*

isostatic compensation.—The departure from normal density of material in the lower part of a column of the earth's crust which balances (compensates) land masses (*topography*) above *sea level* and deficiency of mass in ocean waters, and produces the condition of approximate equilibrium of the earth's crust known as *isostasy*.

isostatic compensation: depth of.—The depth below *sea level* at which the condition of equilibrium known as *isostasy* is complete.

Investigations of geodetic and gravimetric data in the United States determine a depth of isostatic compensation of between 60 and 70 *statute miles*.

isostatic geoid.—See under *geoid*.

isostatic reduction: Bullard method of.—See under *Hayford-Bullard* (*or Bullard*) *method of isostatic reduction*.

isostatic reduction: Hayford-Bowie method of.—See under *Hayford-Bowie method of isostatic reduction*.

isostatic reduction: Hayford-Bullard (or Bullard) method of.—See under *Hayford-Bullard* (or *Bullard*) *method of isostatic reduction*.

J

Jacob's staff.—A single staff or pole used for mounting a *surveyor's compass* or other instrument.

Used in place of a tripod, a Jacob's staff was fitted with a ball-and-socket joint at its upper end, by means of which the instrument was adjusted to a level position; the foot was fitted with a metal shoe which facilitated pressing the staff firmly into the ground. Many of the early *land surveys* in this country were made with *surveyor's compasses* mounted on Jacob's staffs.

Julian calendar.—See under *calendar*.

junction (leveling).—The place where two or more lines of levels are connected together.

junction bench mark.—See under *bench mark*.

junction detail.—See *detail: junction*.

junction figure.—A triangulation figure in which three or more *triangulation arcs* meet, or two or more *arcs* intersect.

K

knife edge (pendulum).—A suspension bearing used in the support of a *pendulum*.

The knife edge bears on a plane. The *Mendenhall pendulum* used in the work of the U. S. Coast and Geodetic Survey originally had an agate knife edge mounted in its head, which was stirrup-shaped; this agate knife edge rested on an agate *plane* which was rigidly mounted in the *receiver*. In apparatus made since 1898, the positions of knife edge and *plane* are reversed, the plane being attached to the *pendulum*, and the knife edge mounted in the *receiver*.

Kripniyuk-Kwiklokchun datum.—See under *datum*.

L

Lambert azimuthal polar map projection.—See under *map projection*.

Lambert central equivalent map projection upon the plane of the meridian.—See under *map projection: Lambert zenithal* (*azimuthal*) *equal-area*.

Lambert conformal map projection.—See under *map projection*.

Lambert equal-area meridional map projection.—See under *map projection*.

Lambert grid.—An informal designation for a *State coordinate system* based on a *Lambert conformal map projection* with two *standard parallels*.

Lambert zenithal (azimuthal) equal-area map projection.—See under *map projection*.

land boundary.—See under *boundary*.

land court.—A tribunal established for the purpose of administering legislative statutes relating to *land boundaries* and titles.

There are land courts in Massachusetts and in Hawaii.

land forms.*—The shapes into which the earth's surface is sculptured by natural forces.

A land form is subject to portrayal by various means or to the interpretation of its probable origin, cause, or history. The form in all cases is the same. Whether it is a *topographic form* or a *physiographic form* depends upon the use for which it is considered. The term land form is used extensively in place of and with the meaning of the more restricted term, *physiographic form*. It is sometimes written as one word, landform, but the two-word spelling, land form, is preferred.

land survey.—See under *surveying: land surveying*.

land surveying.—See under *surveying*.

landmark.—Any *monument* or material mark or fixed object used to designate the location of a *land boundary* on the ground. Any prominent object on land which may be used in determining a location or a *direction*.

Laplace azimuth.—See under *azimuth*.

Laplace azimuth mark.—See under *azimuth mark*.

Laplace condition.—See under *Laplace equation*.

Laplace equation.—The equation which expresses the relationship between *astronomic* and *geodetic azimuths* in terms of *astronomic* and *geodetic longitudes and geodetic latitude*. A usual form is

$$\alpha_A - \alpha_G = -(\lambda_A - \lambda_G)\sin \phi_G$$

in which α_A and λ_A are *astronomic azimuth* and *longitude*, α_G, λ_G, and ϕ_G are *geodetic azimuth, longitude*, and *latitude* respectively. The signs depend upon convention. As written above, north *latitudes* and west *longitudes* are considered positive.

The Laplace condition (expressed by the Laplace equation) arises from the fact that a *deflection of the vertical* in the plane of the *prime vertical* will give a difference between *astronomic* and *geodetic* *longitude* and between *astronomic* and *geodetic azimuth;* or, conversely, that the observed differences between *astronomic* and *geodetic* values of the *longitude* and of the *azimuth* may both be used to determine the *deflection* in the plane of the *prime vertical.* This *deflection* cannot have two values at the same place, and the imposition of the Laplace condition forces a consistency between them. Since *longitudes* can be carried through *triangulation* with very good *accuracy* and *azimuths* cannot, the practice is to compute the value of the *deflection* for *azimuth* from the *deflection* in the *prime vertical* obtained from the *longitude.* The value of the *azimuth* thus obtained is known as a *Laplace azimuth.*

The symbol α_L is proposed for *Laplace azimuths,* for use in formulas and wherever a special symbol is desirable. In computing a *control survey,* the *deflection of the vertical* at the initial station will affect any Laplace equations in the net. In the readjustment of the horizontal *control survey net* of the United States which introduced the *North American datum of 1927, azimuth control* was furnished by *Laplace azimuths* distributed throughout the net. In the investigation of the *figure of the earth* and *isostasy* which produced the International Ellipsoid of Reference, the Laplace condition was expressed as follows:

$$\cos \phi' (\lambda_A - \lambda') = -\cot \phi' (\alpha_A - \alpha')$$

The symbols marked with a prime (′) represent geodetic values, those with a subscript letter $(_A)$ represent astronomic values. The use of a subscript letter $(_G)$ for geodetic values is preferred.

The Laplace equation is so-called after Pierre Simon Laplace (1749–1827), who derived a general form for it when comparing the shape of the earth with a mathematical figure. (Mécanique Céleste, 1799, by Marquis de Laplace. English translation by Nathaniel Bowditch, published in 1832, vol. 2, p. 385.)

Laplace station.—A *triangulation* or *traverse station* at which a *Laplace azimuth* is determined.

At a Laplace station both *astronomic longitude* and *astronomic azimuth* are determined.

large scale.—See under *map scale: fractional.*

lat.—See under *latitude: difference of latitude (plane surveying).*

latitude (general).—A coordinate distance, linear or angular, from an east-west reference line.

latitude (on a sphere).—The *angle* at the center of a sphere between the plane of the *equator* and the line to the point on the surface of the sphere.

Some problems of *geodesy* and *cartography* are greatly simplified by the use of latitudes on a sphere which has some definite relationship (as equal area or equal volume) to the *spheroid.*

latitude (plane surveying).—The perpendicular distance in a horizontal plane of a point from an east-west axis of reference.

The *difference of latitude* of the two ends of a line is frequently called the latitude of the line, and defined as the *orthographic projection* of the line on a reference *meridian.* The latitude (as above defined) of the middle of a line is also referred to as the latitude of the line.

latitude: astronomic.—The *angle* between the plumb line and the plane of the *celestial equator.* Also defined as the *angle* between the plane of the *horizon* and the axis of *rotation* of the earth.

Astronomic latitude is the *latitude* which results directly from observations on celestial bodies, uncorrected for *deflection of the vertical (station error)* which, in the United States, may amount to as much as 25″. Astronomic latitude applies only to positions on the earth, and is reckoned from the *astronomic equator* (0°), north and south through 90°.

latitude: authalic (equal-area).—A *latitude* based on a sphere having the same area as the *spheroid,* and such that areas between successive *parallels of latitude* are exactly equal to the corresponding areas on the *spheroid.*

Authalic latitudes are used in the computation of *equal-area map projections.* For mathematical definition and discussion consult U. S. Coast and Geodetic Survey Special Publication No. 67, Latitude Developments Connected with Geodesy and Cartography, by O. S. Adams, 1921.

latitude: celestial.—The *arc* of a *great circle* perpendicular to the *ecliptic,* intercepted between the *ecliptic* and the object whose *latitude* is to be defined.

Celestial latitude is not the same as *astronomic latitude,* and does not enter into usual problems of *surveying.*

latitude: difference of latitude (plane surveying).—The *orthographic projection* of a line on a *meridian* of reference.

By custom, this term has been shortened to *latitude* or *lat.,* which is frequently used where difference of latitude is intended. It is north or positive, and sometimes termed the northing, for a line whose *azimuth* or *bearing* is in the northwest or northeast quadrant; it is south or negative, and sometimes termed the southing, for a line whose *azimuth* or *bearing* is in the southeast or southwest quadrant.

latitude: geocentric.—The *angle* at the center of the earth between the plane of the *celestial equator* and a line to a point on the surface of the earth.

Geocentric latitude is used as an auxiliary *latitude* in some computations in astronomy, geodesy, and cartography, in which connection it is defined as the *angle* formed with the major axis of the ellipse (meridional section of the *spheroid*) by the radius vector from the center of the ellipse to the given point. In astronomic work, geocentric latitude is also called *reduced latitude,* a term that is sometimes applied to *parametric latitude* in *geodesy* and cartography. The geocentric and *isometric latitudes* are approximately equal.

latitude: geodetic.—The *angle* which the *normal* to the *spheroid* at a point makes with the plane of the *geodetic equator.*

Geodetic latitudes are reckoned from the *equator,* but in the horizontal *control survey* of the United States they are computed from the latitude of station Meades Ranch as prescribed in the *North American datum of 1927.* In recording a *geodetic position,* it is essential that the *geodetic datum* on which it is based be also stated. A geodetic latitude differs from the corresponding *astronomic latitude* by the amount of the meridional component of the local *deflection of the vertical (station error)* which, in this country, may amount to more than 25″.

latitude: geographic.—A general term, applying alike to *astronomic latitudes* and *geodetic latitudes.*

latitude: isometric (conformal).—An auxiliary *latitude* used in the conformal mapping of the *spheroid* on a sphere.

By transforming *geographic latitudes* on the *spheroid* into isometric latitudes on a sphere, a *conformal map projection* (the Mercator) may be calculated, using spherical formulas, for the plotting of *geographic* data. For a mathematical definition of isometric latitude see U. S. Coast and Geodetic Survey Special Publication No. 67, Latitude Developments Connected with Geodesy and Cartography, by O. S. Adams, 1921. The *isometric* and *geocentric latitudes* are approximately equal.

latitude: parametric (geometric or reduced).—The *angle* at the center of a sphere which is tangent to the *spheroid* along the *geodetic equator,* between the plane of the *equator* and the radius to the point intersected on the sphere by a straight line perpendicular to the plane of the *equator* and passing through the point on the *spheroid* whose parametric latitude is defined.

Parametric latitude is an auxiliary *latitude* used in problems of *geodesy* and *cartography.* For mathematical definition see U. S. Coast and Geodetic Survey Special Publication No. 67, Latitude Developments Connected with Geodesy and Cartography, by O. S. Adams, 1921. In astronomical work, when the term reduced latitude is used, *geocentric latitude* is meant.

latitude: rectifying.—The *latitude* on a sphere such that a *great circle* on it has the same length as a *meridian* on the *spheroid,* and such that all lengths along a *meridian* from the *equator* are exactly equal to the corresponding lengths on the *spheroid.*

Rectifying latitude is an auxiliary *latitude* used in problems of *geodesy* and *cartography.* For mathematical definition see U. S. Coast and Geodetic Survey Special Publication No. 67, Latitude Developments Connected with Geodesy and Cartography, by O. S. Adams, 1921.

latitude: variation of.—A small periodic change in the *astronomic latitude* of points on the earth, due to *variation of the pole.*

latitude equation.—See under *equation.*

latitude level.—See under *level.*

least squares.—A mathematical method of determining the most probable values of a series of quantities from a set of observations greater in number than are necessary to determine those quantities.

Credit for the discovery in 1770 of the method of least squares is sometimes given to Lagrange, although his method was lost or forgotten for some time. Credit for the discovery is more often given to Gauss, who used it in 1795 but did not publish his results until 1809, while it had been demonstrated by Adrain in 1808. Laplace demonstrated it in 1810 and in 1812, and its theory was compared with practice by Bessel in 1818. It rests upon the mathematical demonstration that where each of a very large number of observations of any quantity is of the same quality as the others, the most probable value of the quantity is the one for which the sum of the squares of the *residual errors* (or *corrections*) is a minimum. If the observations are of unequal *weight,* then the most probable value is the one for which the sum of the squares of the weighted residuals is a minimum. In survey work, the method of least squares provides a means of obtaining the most probable values of position and associated data, and at the same time fully coordinating and correlating those data. The adjusted survey data distributed by the U. S. Coast and Geodetic Survey are obtained by the method of least squares. Least squares have also been designated as "minimum squares."

left bank.—See under *bank of stream.*

Legendre's theorem.—The *angles A, B,* and *C* of a spherical triangle whose sides are *a, b,* and *c,* supposed very small with respect to the radius of the sphere, are equal to the corresponding *angles* of a plane triangle whose sides are *a, b,* and *c,* increased each by one-third the *spherical excess* of the triangle.

(Alternate definition.)

In two triangles, one a spherical triangle whose sides a, b, and c are very small in comparison with the radius of the sphere and the other a plane triangle having sides of the same length as the spherical triangle, the *angles* A, B, and C of the spherical triangle are greater than the corresponding *angles* of the plane triangle, each by one-third of the *spherical excess* of the spherical triangle.

The use of Legendre's theorem greatly simplifies the treatment of spherical triangles in *geodetic* work, by permitting their solution as plane triangles. This theorem is named after the French mathematician, Adrien Marie Legendre (1752–1833), who demonstrated it.

length correction: tape.—See under *tape.*

length equation.—See under *equation.*

lens: achromatic.—See under *achromatic lens.*

lens: aplanatic.—See under *aplanatic lens.*

lens axis.—See under *principal axis.*

level: bull's-eye.—See under *level: circular.*

level: chambered spirit.—A level tube with a partition near one end which cuts off a small air reservoir, so arranged that the length of the bubble can be regulated.

level: circular.—A *spirit level* having the inside surface of its upper part ground to spherical shape, the outline of the bubble formed being circular, and the *graduations* being concentric circles.

This form of *spirit level* is used where a high degree of precision is not required, as in plumbing a *level rod* or setting an instrument in approximate position. Also termed universal level; bulls-eye level.

level: first-order.—See under *leveling instrument.*

level: hand.—See under *leveling instrument.*

level: hanging.—A *spirit level* so mounted that, when in use, its level tube is lower in elevation than its points of support.

A hanging level literally hangs from the member of the surveying or astronomical instrument whose position with reference to a horizontal line it measures. It is used in place of a *striding level* to measure the inclination of the *horizontal axis* of the *broken-telescope transit.*

level: latitude.—A sensitive *spirit level* attached to the *telescope* of an instrument employed for observing *astronomic latitude,* in such manner that when the *telescope* is clamped in position, the level measures, in a *vertical plane,* variations in the direction of the *line of collimation.*

A latitude level is of greater sensitivity than the level which is attached to the *finder circle* of an astronomical instrument to aid in placing its *telescope* at the proper inclination for bringing a selected celestial object into the field of view at the expected time.

level: precise.—See under *leveling instrument.*

level: spirit (general).—A small closed vessel of transparent material (glass), having the inside surface of its upper part curved (circular) in form; the vessel is nearly filled with a fluid of low viscosity (alcohol or ether), enough free space being left for the formation of a bubble (blister) of air and gas, which will always assume a position at the top of the vessel.

Many *surveying* operations depend upon the instrumental establishment of the plane of the *horizon,* which is accomplished with the aid of a spirit level. For work of high *precision,* where exact establishment of the plane of the *horizon* is desired, a spirit level of great sensitivity is employed to determine deviations from that plane, and corresponding *corrections* are then applied to the observations.

There are two types of spirit levels used in surveying: one having the curved surface spherical in form, producing a bubble of circular outline, and defined under the term *circular level.* The other, and much more generally used type, has a vessel in the form of a circular tube, the longitudinal axis of which is also circular in form. It is defined under the term spirit level, and is the type usually referred to when that term is used.

level: spirit.—A closed glass tube (vial) of circular cross section, its center line also forming a circular *arc,* its interior surface being ground to precise form; it is nearly filled with ether or other liquid of low viscosity, enough free space being left for the formation of a bubble of air and gas.

This is the type of spirit level used on those surveying and astronomical instruments which make use of the *horizon* (or *zenith*) as a reference of observations, and which require more than an *approximate* adjustment to such reference. When in adjustment, a tangent to the center of the level bubble defines a horizontal line in the plane of the longitudinal axis of the level tube, with an *accuracy* and *precision* which depend upon the quality of the workmanship and the sensitivity of the level. The sensitivity, sometimes termed sensibility, of a *spirit level* depends upon the radius of curvature of its longitudinal section: the longer the radius, the more sensitive the level. The sensitivity is rated by equating the linear length of a division between graduation marks on the level tube and its angular value at the center of curvature of the tube. Example: stride level of *meridian telescope* No. 9 (U. S. Coast and Geodetic Survey), 1 division=2 mm.=1.884″ at 12° C. A usual value for the sensitivity of the long level on a surveyor's *transit* is: 1 division=3/20 inch=30″.

level: striding.—A *spirit level* so mounted that it may be placed above and parallel with the *horizontal axis* of a surveying or astronomical instrument, and so supported in use that it may be used to measure the inclination of the *horizontal axis* to the plane of the *horizon.*

Generally, the *spirit level* of a striding level is of greater than average sensitivity, and its mounting has supports in the form of inverted wyes which rest directly upon the pivots on which the *telescope* of the instrument rotates. It is used to make the inclination of the *horizontal axis* quite small and then to measure the magnitude of any remaining inclination.

level: universal.—See under *level: circular level.*

level: wind, spirit level.—Lack of parallelism between the axis of a *spirit level* vial and the line joining the centers of its supports.

When wind (pronounced to rhyme with find) is present, if the *spirit level* is rocked on its supports, the bubble will respond with a longitudinal movement.

level axis: spirit.—The line tangent to the surface of a spirit-level tube (vial) against which the bubble forms, at the center of the graduated scale of the level, and in the plane of the tube (vial) and its center of curvature. Also called axis of the level, axis of the level bubble.

When the level bubble is in the center of the *graduations,* and the plane through the center line of the level tube and its center of curvature is vertical, the spirit level axis will be horizontal.

level constant.—See under *constant.*

level correction (leveling).—See under *correction.*

level line: duplicate.—A line of *spirit leveling* composed of two single lines run over the same route, but in opposite directions, and using different *turning points.*

level line: multiple.—Two or more single lines of *spirit leveling* run between the same terminal points, but along different routes.

level line: simultaneous.—A line of *spirit leveling* composed of two single lines run over the same route, both in the same direction, but using different *turning points.* Also called a simultaneous double line.

level net.—See under *survey net.*

level surface.—A surface which at every point is perpendicular to the plumb line or the direction in which *gravity* acts.

A level surface is an *equipotential surface.* The surface of a body of still water is a level surface (see *water leveling*). The surface of the ocean, if changes caused by tides, currents, winds, atmospheric pressure, etc., are not considered, is a level surface. The surface of the *geoid* is a level surface. Any line lying in a level surface is a *level line.* In a *survey* of a limited area, a level surface is sometimes treated as a plane surface. Level surfaces are approximately spheroidal in shape, the distance between any two level surfaces decreasing with increase of *latitude.* For example: a level surface which is 1,000 *meters* above the mean surface of the sea at the *equator* is 995 *meters* above that surface at the poles.

level trier.—An apparatus for use in measuring the angular value of the *divisions* of a *spirit level.*

A level trier may consist of a beam mounted on a stable base: one end of the beam is hinged to the base, the other end can be moved vertically by means of a micrometer screw, the angular amount of the movement being measured with the *micrometer.* The *spirit level* is mounted on the beam, and the angle through which the beam moves while the bubble of the *spirit level* travels the length of a *division* is measured with the *micrometer.*

leveling: astronomical.—The determination of the figure of the *geoid* from *deflections of the vertical.*

leveling: barometric.—A method of determining differences of *elevation* from differences of atmospheric pressure observed with a *barometer.*

By the application of certain *corrections* and the use of what is sometimes called the "barometric formula," a difference of atmospheric pressure at two places is transformed into a difference of *elevations* of those places. If the *elevation* of one station above a *datum* (as *sea level*) is known, the approximate *elevations* of other stations connected with it by barometric leveling can be known. By using *barometers* of special design, and including several stations of known *elevation* in a series of occupied stations, the *accuracy* of the *elevations* determined for the new stations is increased. *Corrections* are applied for temperature, *latitude,* index of barometer, closure of circuit, *diurnal variation* in atmospheric pressure, etc.

leveling: direct.—The determination of differences of *elevation* by means of a continuous series of short horizontal lines, the vertical distances from which to adjacent ground marks are determined by direct observations on graduated rods with a *leveling instrument* equipped with a *spirit level.*

leveling: first order.—*Spirit leveling* conforming to the following criteria: all first-order leveling to be divided into sections of 1 to 2 kilometers in length; each section to be leveled over in both forward and backward directions; the results of the two runnings over a section not to differ by more than 4.0 millimeters times the square root of the length of the section in kilometers (4.0 $mm.\sqrt{K}$), the equivalent of which is 0.017 foot times the square root of the length of the section in miles (0.017 $ft.\sqrt{M}$).

The above designation and criteria were recommended by the Federal Board of Surveys and Maps in May 1925. First-order leveling was formerly called precise leveling and leveling of high precision.

leveling: geodetic.—*Spirit leveling* of a high order of *accuracy,* usually extended over large areas, to furnish accurate vertical *control* as a basis for the control in the vertical dimension for all surveying and mapping operations.

Spirit leveling follows the *geoid* and its associated *level surfaces* which are irregular, rather than any mathematically determined *spheroid* or *ellipsoid* and associated regular level surfaces.

leveling: indirect.—The determination of differences of *elevation* from (1) *vertical angles* and horizontal distances, as in *trigonometric leveling;* (2) comparative *elevations* derived from values of atmospheric pressure determined with a *barometer,* as in *barometric leveling;* and (3) *elevations* derived from values of the boiling point of water determined with a *hypsometer,* as in *thermometric leveling.*

leveling: precise.—See under *leveling: first-order leveling.*

leveling: second-order.—*Spirit leveling* which does not attain the quality of *first-order leveling,* but does conform to the following criteria: lines between *bench marks* established by *first-order leveling* to be run in only one direction, using first-order instruments and methods; or other lines to be divided into sections, over which forward and backward runnings are to be made; the closure in either case not to exceed 8.4 millimeters times the square root of the length of the line (or section) in kilometers (8.4 $mm.\sqrt{K}$), the equivalent of which is 0.035 foot times the square root of the length of the line (or section) in miles (0.035 $ft.\sqrt{M}$).

The above designation and criteria were recommended by the Federal Board of Surveys and Maps in May 1925.

leveling: spirit.—The determination of *elevations* of points with respect to each other, or with respect to a common *datum,* by means of an instrument using a *spirit level* to establish a horizontal *line of sight.*

A *spirit level* is attached to a *telescope* in such a way that the *axis of the level* and the *line of collimation* may be made parallel, and the level adjusted so that its axis is horizontal. The difference of readings on vertical rods held on two different points is the difference in *elevation* of the points. If the *elevation* of one point is known, the other also becomes known. By a series of progressive *level lines,* each comprising the observed values at a single station, the *elevations* of a series of points (*bench marks*) are determined. Instruments used in spirit leveling are of various designs, to satisfy needs based on speed, cost, *accuracy,* and *precision.* Among such types are the *hand level,* the *wye level,* the *dumpy level,* the *Fischer level,* etc. Spirit leveling has been classified by the Federal Board of Surveys and Maps according to the *accuracy* of the results obtained as follows: *first-order leveling, second-order leveling,* and *third-order leveling.*

leveling: thermometric.—The determination of *elevations* above *sea level* from observed values of the boiling point of water.

The temperature at which water boils at any point on the earth depends upon the weight of the incumbent atmosphere at that point. See *hypsometer.*

leveling: third-order.—*Leveling* which does not attain the quality of *second-order leveling,* but does conform to the following criteria: lines of third-order leveling shall not be extended more than 30 miles from lines of *first-* or *second-order leveling,* and must close upon lines of equal or a higher order of *accuracy;* closing errors must not exceed 12 millimeters times the square root of the length of the line in kilometers (12 $mm.\ \sqrt{K}$), the equivalent of which is 0.05 foot times the square root of the length of the line in miles (0.05 $ft.\ \sqrt{M}$).

The above designation and criteria were recommended by the Federal Board of Surveys and Maps in May 1925. Third-order leveling is used for subdividing loops of *first-* and *second-order leveling,* and to provide local vertical control for detailed surveys.

leveling: trigonometric.—The determination of differences of *elevations* by means of observed *vertical angles,* combined with lengths of lines. See *vertical angulation.*

leveling: water.—A method of obtaining relative *elevations* by observing heights with respect to the surface of a body of still water.

The surface of a body of still water, as of a lake, is a *level surface* (*equipotential surface*), and the relative *elevations* of objects along its shores may be obtained by taking the differences of their heights with respect to the surface of the water. It is with this meaning that the term *"water levels"* is generally used.

leveling instrument: dumpy level.—A leveling instrument in which the *telescope* is permanently attached to the leveling base, either rigidly or by a hinge that can be manipulated by means of a micrometer screw.

The dumpy level takes its name from the dumpy appearance of the early type of this instrument, the *telescope* of which was short and had a large object glass. Dumpy levels constitute one of two principal classes of leveling instruments in which most leveling instruments used in surveying belong. The other class is represented by the *wye* (Y–) *level.* The *Fischer level* used by the U. S. Coast and Geodetic Survey on *first-* and *second-order work* is a dumpy level. Method of mounting the *telescope* and not its shape is the identifying characteristic of a dumpy level.

leveling instrument: Egault level.—A French instrument having the *spirit level* attached to a level bar which also carries wyes in which the *telescope* rests.

In the so-called *wye level,* the *spirit level* is attached to the *telescope,* and is reversed with it. In Egault's level, the *telescope* is reversed in the wyes without disturbing the *spirit level.*

leveling instrument: first-order level.—A leveling instrument designed for the attainment of first-order results. See under *leveling: first-order.*

A first-order instrument is generally characterized by special features of design, and by superior workmanship in construction. A general, but not always exact, distinction between instruments used in *first-order* and *second-order leveling* and other leveling instruments is the following: a first-order level is carefully adjusted, and any *instrumental errors* remaining are determined by observation and applied as *corrections* to the observed differences of *eleva-*

tion; in using other leveling instruments, a careful adjustment of the instrument is made, and thereafter no account is taken of *errors* remaining in the instrument. An important characteristic of leveling instruments used in *first-order work* at the present time is a mirror and prism arrangement by means of which the level bubble and the level rod can be viewed at the same time, while a micrometer-screw control of the *telescope* makes it possible to bring the level bubble to the center of its tube at the instant of reading the rod. There have been a number of different designs of leveling instruments used in this country on *first-order leveling* (formerly called *precise leveling*), but all such work by the U. S. Coast and Geodetic Survey is now done with a *Fischer level.*

leveling instrument: Fischer level.—The official designation of the instrument used by the U. S. Coast and Geodetic Survey in the execution of *first-order leveling.* It is a *dumpy level,* constructed of *invar,* binocular in design, having the *spirit level* placed in the tube of the main *telescope,* quite close to the *line of collimation.* The main *telescope* is on the right. A suitable arrangement of mirror and prisms brings an image of the bubble to the left-hand eyepiece. The *telescope* is so mounted that, by means of a micrometer screw, its inclination can be changed through a small *angle* without altering its *elevation.*

In use, the observer sights the rod with the right eye, and at the same time views the bubble with the left eye. By means of the micrometer screw, the inclination of the *telescope* is changed until the bubble is seen in the middle of its tube; the rod is read with the bubble in the mean position. The *collimation error,* made quite small by instrumental adjustment, is then determined, and a *correction* is applied to eliminate its effect from the results. An *invar* rod is used, and the effects of rod temperature and index error considered. In the computations, allowance is made for curvature of the earth and *atmospheric refraction.* The Fischer level was designed by E. G. Fischer, formerly Chief of the Instrument Division, U. S. Coast and Geodetic Survey, and adopted by that Bureau in 1899. The use of *invar* in its construction is of more recent date.

leveling instrument: Gravatt level.—A *dumpy level* with the *spirit level* mounted on top of a short *telescope* tube having a large object glass. Later made with wyes.

This is said to be the original *dumpy level,* which is also claimed for the *Troughton level.*

leveling instrument: hand level.—A small leveling instrument in which the *spirit level* is so mounted that the observer may view the bubble at the same time that he observes an object through the *telescope.*

The instrument is held in the hand when in use, and the viewing of the bubble is accomplished by means of a prism or mirror in the *telescope* tube. The instrument is used in *reconnaissance surveys,* and in cross-section and other work where a high degree of *precision* and *accuracy* is not required.

leveling instrument: Lenoir level.—An instrument which has the *telescope* passing through steel blocks, one near each end, whose upper and lower faces are plane and closely parallel: the lower faces rest upon a brass circle; the upper faces support a spirit level, which is reversed in leveling the instrument.

leveling instrument: Locke hand level.—The generally known design of a *hand level.*

leveling instrument: precise level.—A leveling instrument for use where results of a high order of *accuracy* and *precision* are required. See *leveling instrument: first-order level.*

leveling instrument: Stampfer level.—A name given a type of leveling instrument having the *telescope* tube so mounted that it could be moved in a *vertical plane* about a horizontal axis, involving the use of a *striding level* and a micrometer screw. This type of instrument was also termed a Vienna level.

The mechanical principle involved was apparently quite similar to that of the present-day *first-order level.* See *leveling instrument: Fischer level.*

leveling instrument: Troughton level.—An English instrument having the *spirit level* permanently attached to the top of the telescope tube.

This is said to be the original *dumpy level,* which is also claimed for the *Gravatt level.*

leveling instrument: U. S. Geological Survey level.—A level of the dumpy type, constructed of stainless steel. It has an internal-focusing *telescope;* the level bubble is centered by the end-coincidence method, effected with the aid of a prism device and stellite mirror which can be adjusted by the observer.

This instrument is used by the U. S. Geological Survey in *second-* and *third-order leveling.* By substituting a more sensitive *spirit level* and a more powerful eyepiece for the regular equipment, it may be used for *first-order work.* The interval between *stadia* wires is such that the half-interval intercept on the rod, multiplied by 1,000, will give the distance to the rod in feet.

leveling instrument: wye (Y) level.—A leveling instrument having the *telescope* with attached *spirit level* supported in wyes (Y's), in which it may be rotated about its longitudinal axis (*collimation axis*), and from which it may be lifted and reversed, end for end.

The instrumental adjustments made possible by this mounting are peculiar to the instrument. It forms one of two general classes of leveling instruments, the other class being represented by the *dumpy level.*

leveling of high precision.—See under *leveling: first-order leveling.*

leveling rod (general).—A straight rod or bar, designed for use in measuring a vertical distance between a point on the ground and the *line of collimation* of a leveling instrument which has been adjusted to a horizontal position.

A leveling rod is usually of wood, and has a flat face which is graduated in terms of some linear unit and fractions thereof, the zero of the *graduations* being at one end of the rod. Some rods have the *graduations* on a metal face (*invar* rod). On some rods the *graduation* marks are designed to be read by the observer at the leveling instrument: such a rod is termed a speaking rod or self-reading rod. Another type of rod, called a target rod, carries a target which is moved into position by the rodman in accordance with signals given by the man at the instrument: when the target is bisected by the *line of collimation,* it is read by the rodman. There are many different designs of rods, which will be found defined under leveling rod, followed by the identifying name of the rod.

leveling rod: Barlow.—A *speaking rod* marked with triangles each 0.02 foot in height.

leveling rod: Boston.—A two-piece rod with fixed target on one end.

The target is adjusted in *elevation* by moving one part of the rod on the other. Read by *vernier.*

For heights greater than 5½ feet, the target end is up; for lesser heights, the target end is down. It is a little-used rod.

leveling rod: Conybeare.—A *speaking rod* having tenth-of-foot *divisions,* alternately black and white, each *division* having on it three hexagons in the contrasting color, white or black.

leveling rod: Gravatt.—A *speaking rod,* marked with rectangles each 0.01 foot high, the rectangles at the tenths of foot being longer, and those at the half-tenths being identified by dots.

leveling rod: invar.—A *leveling rod* having the *graduations* painted on a strip of *invar.*

The strip of *invar* is set into the face of the wooden rod, firmly attached to the bottom of the rod (rod shoe), and held in place by guides and by a tension spring at the top of the rod. Invar rods are used in *first-order leveling.*

leveling rod: Molitor precise.—A *speaking rod* of T-shaped cross section, with *graduation* marks shaped as triangles and rectangles, the smallest division being 2 millimeters.

Read by estimation to single millimeters. Equipped with thermometer and *circular level.*

leveling rod: New York.—A two-piece rod with movable target.

For heights greater than 6½ feet, the target is clamped at 6½ feet and raised by extending the rod. Graduated to hundredths of a foot and read by *vernier* to thousandths.

leveling rod: Pemberton.—A *speaking rod* marked with alternate rows of circular and diamond-shaped dots, running diagonally across the rod.

Read to hundredths of a foot.

leveling rod: Philadelphia.—A two-piece *target rod,* with *graduation* marks so styled that it may also be used as a *speaking rod.*

For heights greater than 7 feet the target is clamped at 7 feet, and raised by extending the rod. As a *target rod* it is read by *vernier* to thousandths of a foot; as a *speaking rod,* to half-hundredths.

leveling rod: self-reading or speaking.—See under *leveling rod (general).*

leveling rod: Stephenson.—A *speaking rod* having *graduations* forming a diagonal scale, with horizontal lines through the tenth-of-foot marks.

This rod is read to hundredths of a foot.

leveling rod: target.—See under *leveling rod (general).*

leveling rod: U. S. Coast and Geodetic Survey first-order.—Adopted in 1916, the rod now used in *first-* and *second-order leveling* is a *speaking rod* having a strip of *invar* set in one face, and held in place by a tension spring at the top of the strip, its bottom being firmly attached to the shoe of the rod. The *invar* strip carries centimeter *divisions,* alternately black and white, and is read by estimation to millimeters. The back side of the rod is graduated in feet and tenths. It is equipped with thermometer and *circular level.* Sometimes called an *invar rod.*

leveling rod: U. S. Coast and Geodetic Survey rods.—*Leveling rods* used in the execution of *first-order* (formerly *precise*) and *second-order* (formerly *primary*) *leveling,* before 1895. A *target rod* having *graduations* on a metal strip about 3 meters long set in a wooden rod of plus-sign (+) cross section, the lower end of the strip firmly attached to the wooden rod, the upper end free to respond to changes of temperature. Pointings made on target equipped with small metal scale.

About 1894, a rod of plus-sign (+) cross section was constructed, having *graduation* marks painted to show 1-centimeter intervals, brass plugs being set at 2-centimeter intervals. The rod carried a target and was read to millimeters by means of a 2-centimeter scale. It was equipped with a thermometer and a *circular level.* This rod was replaced with a *speaking rod* of plus-sign (+) cross section, having painted on it *graduation* marks of 1 centimeter, read by estimation to millimeters. Two metal plugs set in the rod 3 meters apart were used in its standardization. It was equipped with thermometer and *circular level.* In 1916 the rod now in use was adopted. See under *leveling rod: U. S. Coast and Geodetic Survey first-order leveling rod.*

leveling rod: U. S. Engineer precise.—A *speaking rod* of T-shaped cross section, 12 feet long, graduated in centimeters.

leveling rod: U. S. Geological Survey precise.—1. A *speaking rod* graduated in *yards* and fractions of a *yard.* It is read for each of three cross wires to the nearest thousandth of a yard. The sum of the three readings is then the mean reading in feet to the nearest thousandth. 2. A *target rod* of plus-sign (+) cross section, a little over 12 feet in length.

There are two forms of this rod: the single-target rod, having *graduations* on one face only; and the double-target rod, with *graduations* on two opposite faces.

line of apsides.—The major axis of an elliptical orbit extended indefinitely in both directions.

line of collimation.—See under *collimation.*

line of levels.—A continuous series of measured differences of elevation. The individual measured differences may be single observations in the case of single-run leveling or the means of repeated observations in the case of double-run leveling.

line of levels: spur.—A *line of levels* run as a branch from the main line of levels, either for the purpose of determining the *elevations* of marks not conveniently reached by the main line of levels or to connect with *tidal bench marks* or other previously established *bench marks* in obtaining checks on old leveling either at the beginning or end of a line of levels or at intermediate junctions along the new line of levels.

line of position.—Any line on which a position is known to be located. A *Sumner line.*

Line of position or position line is a more general term than *Sumner line,* which it includes.

line of sight.—See under *collimation: line of collimation.*

line tree (United States public-land surveys).*—A tree intersected by a surveyed line on which legal *corners* are established, and reported in the field notes of the survey. Also termed a sight tree, fore-and-aft tree.

lines on a spheroid.—See under *spheroid.*

link.—A *unit* of linear measure, one one-hundredth of a *chain,* and equivalent to 7.92 inches.

See under *chain: Gunter's chain.*

link (leveling).—A line, a part of a line, or a combination of lines or parts of *lines of levels,* which, taken as a unit, make a continuous piece of leveling directly from one *junction bench mark* to another junction bench mark without passing through or over any other junction bench marks.

link of levels.—See *link (leveling).*

local adjustment.—See under *adjustment: station adjustment.*

local apparent time.—See under *time.*

local mean time.—See under *time.*

local sidereal time.—See under *time.*

location survey.—See under *survey.*

Locke hand level.—See under *leveling instrument.*

long chord.—The chord which extends from the point of curvature to the point of tangency. See under *curve: point of curvature; point of tangency.*

In descriptions of a circular land boundary, the length and bearing of the long chord is an important feature.

longitude (general).—A coordinate distance, linear or angular, from a north-south reference line.

longitude: astronomic.—The *angle* between the plane of the *celestial meridian* and the plane of an initial *meridian,* arbitrarily chosen.

Astronomic longitude is the *longitude* which results directly from observations on celestial bodies, uncorrected for *deflection of the vertical,* the *prime vertical* component of which, in the United States, may amount to more than 18″. Astronomic longitude is measured by the *angle* at the celestial pole between the tangents to the local and the initial *meridians,* or by the *arc* intercepted on the *equator* by those *meridians.* At an international convention held in Washington, D. C., in 1884, the *Meridian of Greenwich* was adopted as the initial or *prime meridian* for all *longitudes,* and is now generally so used. An expression of longitude is sometimes accompanied by a statement of the method used in its determination, often in adjective form, as "wireless longitude," This may serve as an indication of its *precision.* Among the various methods used are the following:

celestial signals.—The local *time* at the new station of the occurrence of celestial phenomena is compared with the corresponding *time* of the occurrence at a base station. Among such phenomena are *eclipses* of the Moon, *eclipses* of Jupiter's satellites, *occultations* of stars, etc.

chronometric.—The local *time* at the new station is compared with the *time* at a base station by transporting *chronometers* from one station to the other.

lunar-distance, moon-altitude, moon-culmination, etc.—The local *time* at the new station is compared with the *time* at a base station, both *times* being determined from the position of the moon relative to other celestial bodies.

telegraphic.—The local *time* at the new station is compared with the *time* at a base station by means of the electric-telegraph land-lines and sea cables.

terrestrial signals.—Local *times* noted at new and base stations of the occurrence of such signals as a flash of gunpowder.

wireless.—The local *time* at the new station is compared with the *time* at a base station by means of radio.

longitude: celestial.—The *arc* of the *ecliptic* intercepted between the *vernal equinox* and the foot of a *great circle* perpendicular to the *ecliptic* and passing through the object whose *longitude* is to be defined.

Celestial longitude is measured along the *ecliptic* from west to east. It is not the same as *astronomic longitude* and does not enter into usual problems of *surveying.*

longitude: geodetic.—The *angle* between the plane of the *geodetic meridian* and the plane of an initial *meridian,* arbitrarily chosen.

A geodetic longitude may be measured by the *angle* at the pole of revolution of the *spheroid* between the local and initial *meridians,* or by the *arc* of the *geodetic equator* intercepted by those *meridians.* In the United States, geodetic longitudes are numbered from the *Meridian of Greenwich,* but are computed from the *meridian* of station Meades Ranch as prescribed in the *North American datum of 1927.* In recording *geodetic position* it is essential that the *geodetic datum* on which it is based also be stated. A geodetic longitude differs from the corresponding *astronomic longitude* by the amount of the *prime-vertical* component of the local *deflection of the vertical* divided by the cosine of the *latitude.* In this country, this may amount to as much as 26″.

longitude: geographic.—A general term, applying alike to *astronomic* and to *geodetic longitudes.*

longitude equation.—See under *equation.*

longitude signal.—See under *signal.*

longitude term.—See under *gravity formula.*

loran.—A pulse-type electronic navigation system for measuring distance differences with respect to fixed transmitters of known geographic position.

A loran receiver may be located on a particular hyperbola by measuring the difference in arrival times of pulses sent in a synchronous manner from a single pair of loran transmitters. The receiver may also be located on another hyperbola by a similar time measurement relative to another pair of transmitters. Intersection of the hyperbolas fixes the location of the receiving point. Loran fixes may be obtained at a range of 750 nautical miles in daylight and 1,400 nautical miles at night, and are very nearly independent of weather conditions. The *precision* of a loran *fix* is comparable to that obtained by high grade celestial observations with a *sextant.*

lost corner (United States public-land surveys).—See under *corner.*

lower culmination.—See under *culmination.*

low-water line.—The line defined by the boundary of a body of water at its lowest stage (elevation).

As there may be appreciable variation with time in the elevation of the low-water surface at a designated locality, a mean value of the low-water elevation should be used in determining the ground position of the low-water line. See *mean low water.*

loxodrome: loxodromic curve.—See under *rhumb line.*

lunar month.—See under *month.*

lunation.—See under *month: synodical month.*

Luzon datum.—See under *datum.*

M

magnetic chart.—See under *chart.*

magnetic declination.—The *bearing* (reckoned east or west from the north branch of the celestial meridian plane) of magnetic north as determined by the positive pole of a freely suspended magnetic needle which is subject to no transient artificial disturbance.

In nautical and aeronautical navigation the term *variation* is used instead of *declination,* and the *angle* is called variation of the compass or *magnetic variation.*

magnetic variation.*—Regular or irregular change with time of *magnetic declination,* dip, or intensity.

In nautical and aeronautical navigation, and in some localities *surveying,* the term variation is used instead of, and meaning, *magnetic declination.* The regular variations are secular, the change from year to year which usually extends for many decades in the same direction; annual, having a period of one *year;* and diurnal, having a daily period. The irregular variations are known, when severe, as magnetic storms. Locally the magnetic field may be affected by direct-current electricity and other artificial disturbances. It was once a common practice of surveyors to denote as variation the net amount by which the compass departed from the direction taken as north in the description of a particular line, even when this was known to be slightly at variance with the *celestial meridian.*

main-scheme station.—See under *station: principal station.*

manometer.—A gage for measuring the pressure of a gas.

In observing the *Mendenhall pendulum,* the *receiver* in which it is swung is exhausted of air to a prescribed maximum pressure. A manometer composed of a U-shaped tube, closed at one end and containing mercury, is placed in the *receiver* to register the air pressure.

map.*—A representation on a plane surface, at an established *scale,* of the physical features (natural, artificial, or both) of a part or the whole of the earth's surface, by means of signs and symbols, and with the means of *orientation* indicated. Also a similar representation of the heavenly bodies.

A map may emphasize, generalize, or omit the representation of certain features to satisfy specific requirements. The type of information which a map is designed primarily to convey is frequently used, in adjective form, to distinguish it from maps of other types. A map should carry a record of the *projection* upon which it is constructed.

map: aerial.—See under *chart: aeronautical chart.*

map: aerial navigation.—See under *chart: aeronautical chart.*

map: air navigation.—See under *chart: aeronautical chart.*

map: aviation.—See under *chart: aeronautical chart.*

map: base.*—A map on which information may be placed for purposes of comparison or geographical correlation.

The term base map was at one time applied to a class of *maps* now known as *outline maps.* It may be applied to *topographic maps,* also termed mother maps, which are used in the construction of many types of *maps* by the addition of particular data.

map: bus and truck.*—A *special-purpose map* showing routes used or suitable for use in commercial transportation by motor vehicles.

map: cadastral.*—A *map* showing the boundaries of subdivisions of land, usually with the bearings and lengths thereof and the areas of individual tracts, for purposes of describing and recording ownership.

A cadastral map may also show culture, drainage, and other features relating to the value and use of land.

map: compiled.*—A *map* incorporating information collected from various sources, not developed by *surveys* made for the special purpose of the *map* in question.

Most *small-scale maps* of large areas are compiled.

map: composite.*—A *map* which portrays information of two or more general types.

A composite map is usually a *compiled map,* bringing together on one *map,* for purposes of comparison, data which were originally portrayed on separate *maps.*

map: contour.*—A *topographic map* which portrays relief by means of *contour lines.*

The form "contoured map" is disapproved.

map: county.*—A *map* of the area of a county as a unit.

map: distribution.*—A *map* which shows the *geographic* arrangement of a specific product, commodity, or formation.

Distribution maps may be nonquantitative or quantitative. Nonquantitative distribution maps may be simple, compound, dominant, etc., depending upon the character of the detail portrayed. Quantitative distribution is statistical in character.

map: dynamic.*—A map designed to show motion, action, or change.

A dynamic map involves an element of *time.* The term may be applied to *maps* depicting traffic flow, migration, military movement, progress in an engineering project, historical geography, etc. Various symbols, such as flow lines and arrows, are employed to depict movement, or a dynamic map may be a composition of two or more *static maps,* depicting comparable data at stated dates or times. A plan of a proposed development is not a *map.* Therefore, the use of the term dynamic map to describe such a plan is disapproved.

map: engineering.*—A *map* showing information that is essential for planning an engineering project or development and for estimating its cost.

An engineering map is usually a large-scale *map* of a comparatively small area or of a route. It may be entirely the product of an engineering survey, or reliable information may be collected from various sources for the purpose and assembled on a *base map.*

map: hemispherical.*—A *map* of one-half of the earth's surface, bounded by the *equator,* or by *meridians.*

The earth is usually considered divided either at the *equator,* into the northern and southern hemispheres, or along some *meridian* between Europe and America and continued around the globe, into eastern and western hemispheres. The division used in *cartography* is usually along the *meridian* of *longitude* 20° west of Greenwich. The Americas are in the Western Hemisphere. The division of the surface of the earth into hemispheres of political significance is not a determined matter.

map: highway.*—A map on which the location of improved roads and highways is shown.

map: hypsographic.*—A *topographic map* on which *elevations* are referred to a *sea-level datum.*

Sometimes called a hypsometric map, the use of which term is disapproved.

map: hypsometric.*—Disapproved. See under *map: hypsographic map.*

map: index.*—A *map* which shows the location of collections of related data, whether in the form of other *maps,* or statistical tables, or descriptive in character.

Index maps may be used to show references to the origin, place of deposit or filing, and other common characteristics (identifying quality) of such data.

map: large scale.—See under *map scale: fractional.*

map: outline.*—A *map* which presents just sufficient geographic information to permit the correlation of additional data placed upon it.

Outline maps correspond to what were at one time known as *base maps.* Outline maps usually show only coast lines, principal rivers, major civil boundaries, and large cities, leaving as much space as possible for the reception of particular data. An outline map presents less detail than a *base map.*

map: planimetric.*—A *map* which presents the horizontal *positions* only for the features represented; distinguished from a *topographic map* by the omission of *relief* in measureable form.

The natural features usually shown on a planimetric map include rivers, lakes, and seas; mountains, valleys, and plains; forests, prairies, marshes, and deserts. The cultural features include cities, farms, transportation routes, and public utility facilities; political and private boundary lines. A planimetric map intended for special use may present only those features which are essential to the purpose to be served.

map: postal.*—Any *special-purpose map* published primarily for the use of the Postal Service.

Postal features are emphasized and the *maps* are composed to show postal information to the best advantage. A list of "Official Postal Maps" is published by the Post Office Department, Washington, D. C.

map: post route.*—Any *postal map* of a State, Territory, or island possession of the United States, published by the Post Office Department.

Each post route map shows all post offices within the area which it represents, indicates the method and frequency of mail supply, and gives intermediate distances on mail-supply routes. County boundaries are delineated, and all county names are shown. Also shown are the principal drainage features, but no highways, and only those railroads which carry mail.

map: reconnaissance.*—A *map* incorporating the information obtained in a *reconnaissance survey*, and data obtained from other sources.

A reconnaissance map differs from a *map* based on an *exploratory survey* by providing greater detail, selected to serve a special or general purpose. See also *reconnaissance sketch.*

map: rural delivery.*—A *postal map* of a county or locality on which roads travelled by rural carriers are distinguished, and on which are shown the location of post offices, houses, schools, and churches at the time the *map* was drawn.

Rural delivery maps are on a *scale* of about 1 *inch* equals 1 *mile*, and are divided into two groups: *county maps* and local *maps*. Where much of the area of a county is covered by rural-delivery service and adequate survey data are available, a *county map* is prepared showing all routes served from the post offices within the county. Where no *county map* has been prepared, a local *map* is constructed for each post office and the area which it serves.

map: school and bus.*—A *map* showing schools and the routes of busses serving them.

map: small scale.—See under *map scale: fractional.*

map: special-purpose.*—Any *map* designed primarily to meet specific requirements.

Usually the *map* information portrayed on a special-purpose map is emphasized by omitting or subordinating other information of a general character which is not essential or is of less importance to the purpose to be served. The special purposes for which *maps* are designed and used are numerous and are increasing with the trend toward the graphic portrayal of factual information in relation to the areas of origin or application. The *map*, in most cases, serves as a base on which special information is correlated. A word or phrase is usually employed to describe the type of information which a *map* is designed to present, whether for general or special use. Definitions for a number of special-purpose maps will be found under their specific names.

map: State.*—A *map* of the area of a State as a unit.

map: State base.*—A *base map* of the area of a State as the unit.

Emphasizing no one type of information, such a *map* is suitable for overprinting information for special purposes. The term is frequently used to describe *State maps* that are issued by agencies of the Federal Government, which are not copyrighted, and are used by government and private agencies as bases on which to portray special information.

map: static.*—A *map* that portrays information as of a single date or time.

Most *maps* are static maps, presenting information as of a given date. Static maps presenting comparable data as of different dates may be combined into a *dynamic map.*

map: topographic.*—A *map* which presents the horizontal and vertical *positions* of the features represented; distinguished from a *planimetric map* by the addition of *relief* in measurable form.

A topographic map usually shows the same features as a *planimetric map*, but uses contours or comparable symbols to show mountains, valleys, and plains; and, in the case of hydrographic charts, symbols and numbers to show depths in bodies of water.

map: Topographic Map of the United States.*—The recommended designation for the *topographic map* of the United States being prepared of quadrangle areas in atlas sheet form, chiefly by the United States Geological Survey.

This *map* portrays all basic information about location, *elevation*, and extent of physical and cultural features that are required for preliminary economic and engineering studies, and for incorporation in a base for *maps* prepared for special purposes. The use of various other terms which have been applied to this map is disapproved. These include the following: standard topographic map of the United States; general base map; general topographic map; general utility map; general utility map of the United States; general utility topographic map of the United States; and possibly others.

map: Transportation Map of the United States.*—The official designation of the *map* which is being prepared (1942) for the Public Roads Administration by the United States Geological Survey, on which are shown, as of a specified date, all improved transportation routes in the United States, including highways, railroads, air, and inland water routes.

The *map* will consist of 438 regular sheets, 26 by 36 *inches* in size, *scale* 1 : 250,000 (approximately 1 *inch* to 4 *miles*), and of special *maps* of large cities, *scale* 1 : 125,000, which may be published as separate sheets or as inserts on the regular sheets. The designation general highway and transportation map, which has been used for this *map*, is disapproved.

map projection (general).—An orderly system of lines on a plane representing a corresponding system of imaginary lines on an adopted terrestrial or celestial *datum* surface. Also the mathematical concept of such a system.

For *maps* of the earth, a projection consists of a network (*graticule*) of lines representing parallels of *latitude* and meridians of *longitude*, or of a *grid* based on such *parallels* and *meridians*. A map projection may be derived by geometrical construction or by mathematical analysis. The mathematical concept of map projection is the mathematical principle upon which it is based, expressed as formulas for computing the elements of the *projection* and tables used in constructing its graphical representation (*graticule* or *grid*). *Projections* derived by mathematical analysis are generally used for *maps* constructed with survey data. Map projections vary considerably in their characteristics, according to the qualities which they preserve in the mapping, and the methods by which this is accomplished. They are classified (1) according to the characteristics which they preserve, as *conformal, equal area, azimuthal,* etc.; (2) according to the methods used in their development, as *polyconic, gnomonic, stereographic,* etc.; and (3) according to the names of their authors, often coupled with some characteristic, as *Mercator, Bonne, Lambert with two standard parallels,* etc. The various map projections are defined under their particular designations.

map projection: Aitoff equal-area.—A *Lambert equal-area azimuthal projection* of a hemisphere converted into a *map projection* of the entire sphere by a manipulation suggested by Aitoff. It is a *projection* bounded by an ellipse in which the line representing the *equator* (major axis) is double the length of the line representing the *central meridian* (minor axis).

Tables for constructing this *projection* are prepared arithmetically from the tables for the *Lambert equal-area meridional map projection.*

map projection: Albers conical equal-area.—An *equal-area map projection* of the so-called conical type, on which *geographic meridians* are represented by straight lines which meet at a common point; this common point serves as the center of a series of arcs of circles which represent the *geographic parallels. Meridians* and *parallels* intersect in right angles. Along two selected *parallels,* called *standard parallels,* the *scale* is held exact; along the other *parallels,* the *scale* varies with the *latitude,* but is constant along any given *parallel.* Between the *standard parallels,* the meridional *scale* is too great; beyond them, too small. At any point on the *projection,* the departure from exact *scale* along a *parallel* is of the opposite sign from the departure from exact *scale* along the *meridian,* and the two are so related as to produce an *equal-area map projection.* Passing through every point are two lines of true-length *scale* which intersect in right *angles;* these are called *isoperimetric curves.*

This projection was devised by Dr. H. C. Albers in 1805.

map projection: aphylactic.—A map projection which is neither a *conformal map projection* nor an *equal-area map projection.*

map projection: authalic.—An *equal-area map projection.*

map projection: autogonal.—A *conformal map projection.*

The term autogonal, meaning *conformal,* is seldom used. Its future use should be avoided.

map projection: azimuthal (or zenithal).—A *map projection* on which the *azimuths* or *directions* of all lines radiating from a central point or pole are the same as the *azimuths* or *directions* of the corresponding lines on the sphere.

As a class, azimuthal map projections include a number of special *projections;* these are described under their particular designations. An azimuthal map projection may be constructed having two poles or points, lines from which are shown in correct *azimuth.* Such a projection is termed a *doubly azimuthal map projection.*

map projection: azimuthal equidistant.—An *azimuthal map projection* on which straight lines radiating from the center or pole of *projection* represent *great circles* in their true *azimuths* from that center, and lengths along those lines are of exact *scale.*

This projection is neither *equal-area* nor *conformal.*

map projection: Bonne.—A modified *equal-area map projection* of the so-called conical type, having lines representing a *standard parallel* and a *central meridian* intersecting near the center of the *map.* The line representing the *central meridian* (*geographic*) is straight and the *scale* along it is exact. All *geographic parallels* are represented by *arcs* of concentric circles at their true distances apart, divided to exact *scale,* and all *meridians,* except the central one, are curved lines connecting corresponding points on the *parallels.*

This *projection* is strictly *equal-area.* A particular form of this *projection* is the *Sanson-Flamsteed* or *sinusoidal map projection,* in constructing which the *equator* is used as the *standard parallel.*

map projection: Cassini.—A conventional *map projection* constructed by computing the lengths of arcs along a selected *geographic meridian* and along a *great circle* perpendicular to that *meridian,* and plotting these as *rectangular coordinates* on a plane.

map projection: conformal.—A *map projection* on which the shape of any small area of the surface mapped is preserved unchanged.

Conformal map projections are sometimes termed *orthomorphic map projections,* "orthomorphic" meaning "right-shape"; this is misleading because, if the area mapped is large, its shape will not be preserved, but only the shape of each small section of it. The exact condition for a conformal map projection is that the *scale* at any point be the same in all *directions:* the *scale* may change from point to point, but at each point it will be independent of the *azimuth.* Among the more important conformal map projections are the *Mercator,* the *stereographic,* the *transverse Mercator,* and the *Lambert conformal map projections:* the latter two are used in the *State coordinate systems.*

map projection: conic.—A *map projection* produced by projecting the *geographic meridians* and *parallels* onto a cone which is tangent to (or intersects) the surface of a sphere, and then developing the cone into a plane.

There are several methods of passing from the sphere to the cone, most of which are analytical in character and do not admit of graphical construction. For example: the *Lambert conformal conic map projection.* A *perspective map projection* from the center of the sphere would admit of graphical construction. Conic map projections may be considered as including *cylindrical map projections* when the apex of the cone is at an infinite distance from the sphere, and projections on a tangent plane when that distance is zero. Conic map projections may be illustrated with a single cone which is tangent to the sphere, or which cuts the sphere along two *parallels;* or there may be a series of tangent cones, all with apices on an extension of the axis of the sphere, at constantly increasing (or decreasing) distances from the sphere. While a cone or cones may be used in illustrating the conic map projections, care must be taken not to consider such *projections* as geometrical concepts, which most of them are not.

map projection: cylindrical.—A *map projection* produced by projecting the *geographic meridians* and *parallels* onto a cylinder which is tangent to (or intersects) the surface of a sphere, and then developing the cylinder into a plane.

There are several methods of passing from the sphere to the cylinder. Some of these are analytical in character, and do not permit of graphic construction. For example, the computation of the *Mercator map projection.* Other methods may be defined geometrically, and the *projection* constructed graphically. For example, the *cylindrical equal-spaced map projection.* Both groups of projections are spoken of as cylindrical projections. All of them may be illustrated, and some of them demonstrated, by means of a cylinder tangent to a sphere, cut along an element, and flattened into a plane.

map projection: cylindrical equal-area.—A *cylindrical map projection* upon a cylinder tangent to a sphere, showing the *geographic meridians* as a family of equal-spaced parallel straight lines perpendicular to a second family of parallel straight lines which represent the *geographic parallels,* and which are so spaced as to produce an *equal-area map projection.*

The equal-area condition preserves a constant ratio between corresponding ground and *map* areas. This *projection* must not be confused with the *Mercator projection* to which it bears some general resemblance.

map projection: cylindrical equal-spaced.—A *cylindrical map projection* upon a cylinder tangent to a sphere, showing the *geographic meridians* as a family of equal-spaced parallel straight lines perpendicular to a second family of equal-spaced parallel straight lines which represent the *geographic parallels.*

The spacing of the *parallels* need not be the same as that of the *meridians.*

map projection: doubly azimuthal.—An *azimuthal map projection* having two poles.

map projection: equal-area.—A *map projection* on which a constant ratio of areas is preserved: that is, any given part of the *map* on an equal-area projection bears the same relation to the area on the sphere which it represents as the whole *map* bears to the entire area represented.

On an equal-area map, a definite area such as a square *inch,* will represent a constant area on the sphere, no matter on what part of the *map* the square *inch* is located. Also called an equivalent map projection, equal-area map projections comprise an extensive class of particular projections, some of them of considerable usefulness.

map projection: equivalent.—See under *map projection: equal-area map projection.*

map projection: geometric.—See under *map projection: perspective map projection.*

map projection: globular.—A *map projection* representing a hemisphere, on which the *equator* and a central *geographic meridian* are represented by straight lines intersecting at right *angles;* these lines are divided into equal parts. All *meridians,* except the central one, are represented by circular *arcs* connecting points of equal division on the *equator* with the poles. The *parallels,* except the *equator,* are circular *arcs* dividing the central and extreme outer *meridians* into equal parts. The extreme outer *meridian* limits the *projection* and is a full circle.

map projection: gnomonic.—A *perspective map projection* on a plane tangent to the surface of a sphere, having the point of projection at the center of the sphere.

The *projection* is neither *conformal* nor *equal-area.* It is the only *projection* on which *great circles* on the sphere are represented as straight lines.

map projection: homolographic (homalographic).—An *equal-area map projection.*

This term is found in the designations given some particular *map projections,* such as the *Mollweide homalographic projection.*

map projection: International Map of the World.—A *modified polyconic map projection,* with two *standard meridians* along which the *scale* is held exact. The *scale* of the *map* is 1 : 1,000,000 ; the *geographic meridians* are represented by straight lines connecting corresponding points on the top and bottom *geographic parallel* lines of the *projection* which are truly divided. These lines representing the *parallels* are *arcs* of circles, not concentric.

Up to latitude 60°, each sheet of the International Map of the World includes 4° of *latitude* and 6° of *longitude;* above latitude 60°, the sheets are double width, that is, each covers 4° of *latitude* and 12° of *longitude.* It is also called the millionth scale map of the World. The *projection* was devised by Lallemand in about 1909.

map projection: Lambert azimuthal (polar).—A *Lambert equal-area map projection* with the pole of projection at the pole of the sphere, and the radii of the circles which represent the *geographic parallels* corresponding to the chords of those *parallels.*

map projection: Lambert central equivalent map projection upon the plane of the meridian.—See under *map projection: Lambert zenithal (azimuthal) equal-area.*

map projection: Lambert conformal conic.—A *conformal map projection* of the so-called conical type, on which all *geographic meridians* are represented by straight lines which meet in a common point outside the limits of the *map,* and the *geographic parallels* are represented by a series of arcs of circles having this common point for a center. *Meridians* and *parallels* intersect in right *angles,* and *angles* on the earth are correctly represented on the *projection.* This *projection* may have one *standard parallel* along which the *scale* is held exact; or there may be two such *standard parallels,* both maintaining exact scale. At any point on the *map,* the *scale* is the same in every direction. It changes along the *meridians,* and is constant along each *parallel.* Where there are two *standard parallels,* the *scale* between those *parallels* is too small ; beyond them, too large.

The Lambert conformal conic map projection with two *standard parallels* is the base for the *State coordinate systems* devised by the U. S. Coast and Geodetic Survey for zones of limited north-south dimension, and indefinite east-west dimension. In those systems, the *standard parallels* are placed at distances of one-sixth the width (north-south) of the *map* from its upper and lower limits.

map projection: Lambert equal-area meridional.—See under *map projection: Lambert zenithal (azimuthal) equal-area.*

map projection: Lambert zenithal (azimuthal) equal-area.—An *azimuthal map projection* having the pole of the *projection* at the center of the area mapped. The *azimuths* of *great circles* radiating from this center (pole) are truly represented on the *map;* equal distances on those *great circles* are represented by equal linear distances on the *map,* but the *scale* along those *great circle* lines so varies with distance from the pole of the *projection,* that an *equal-area projection* is produced.

When the pole of the *projection* is on the *equator,* the *projection* is called the Lambert central equivalent projection upon the plane of the meridian; also, the Lambert equal-area meridional projection.

map projection: Mercator.—A *conformal map projection* of the so-called cylindrical type. The *equator* is represented by a straight line true to *scale;* the *geographic meridians* are represented by parallel straight lines perpendicular to the line representing the *equator;* they are spaced according to their distance apart at the *equator.* The *geographic parallels* are represented by a second system of straight lines perpendicular to the family of lines representing the *meridians,* and therefore parallel with the *equator. Conformality* is achieved by mathematical analysis, the spacing of the *parallels* being increased with increasing distance from the *equator* to conform with the expanding *scale* along the *parallels* resulting from the *meridians* being represented by parallel lines.

The Mercator map projection is considered one of the most valuable of all *map projections,* its most useful feature being that a line of constant *bearing* (*azimuth*) on a sphere is represented on the *projection* by a straight line. It is not a perspective *projection* on a cylinder, and is not developed geometrically.

map projection: Mercator equal-area.—The *sinusoidal map projection.*

map projection: Mercator, transverse.—See under *map projection: transverse Mercator map projection.*

map projection: meridional orthographic.—See under *map projection: orthographic map projection.*

map projection: millionth-scale map of the World projection.—See under *map projection: International Map of the World projection.*

map projection: modified polyconic.—A *map projection* obtained from the regular *polyconic projection* by so altering the *scale* along the central *meridian* that the *scale* is exact along two *standard meridians,* one on either side of the *central meridian* and equidistant therefrom. Also a *rectangular polyconic map projection.*

A modified polyconic map projection is used for the *International Map of the World,* the *scale* being exact along *meridians* located 2° from the *central meridian.* A modified polyconic map projection is also used for some State maps published by the U. S. Geological Survey.

map projection: Mollweide homalographic.—An *equal-area map projection* showing the *equator* and *geographic parallels* as straight lines, and the *geographic meridians* as elliptical *arcs,* with the exception of the *central meridian,* represented by a straight line, and the *meridian* 90° from the center, shown as a full circle.

This *projection* is used to show the entire surface of the earth, in which case it is bounded by an ellipse whose major axis, representing 360° of *longitude,* is double the length of its minor axis, representing 180° of *latitude.* It is also used to map a hemisphere, when the boundary of the *projection* will be a full circle.

map projection: orthembadic.—An *equal-area map projection.*

map projection: orthographic.—A *map projection* produced by straight parallel lines through points on the sphere and perpendicular to the plane of the *projection.*

The orthographic map projection corresponds to a *perspective projection* with the point of projection at an infinite distance from the sphere. As used for *maps* of the earth, this *projection* is classified as (a) a polar orthographic map projection, having the plane of the projection perpendicular to the axis of *rotation* of the earth (parallel with the plane of the *equator*); in this *projection,* the *geographic parallels* are full circles, true to *scale,* and the *geographic meridians* are straight lines; (b) the meridional orthographic map projection, having the plane of the projection parallel to the plane of some selected *meridian;* the *geographic parallels* and the central *meridian* are straight lines, the outer *meridian* is a full circle, and the other *meridians* are arcs of ellipses.

map projection: orthomorphic.—A *conformal map projection.*

Orthomorphic is a little-used term, meaning "right-shape."

map projection: perspective.—A *map projection* produced by straight lines radiating from a selected point and passing through points on the sphere to the plane of projection. Sometimes called a geometric projection.

The plane of projection is usually tangent to the sphere which represents the earth at the center of the area being mapped; the point of projection is on the diameter of the sphere which passes through the point of tangency, and at some selected point on that diameter. If the point of projection is at the center of the sphere, there results the *gnomonic map projection;* if at the opposite end of the diameter from the point of tangency of the plane of projection, it becomes a *stereographic map projection;* if at an infinite distance, an *orthographic map projection.*

map projection: perspective map projection upon a tangent cylinder.—A *cylindrical map projection* upon a cylinder tangent to a sphere, by means of straight lines radiating from the center of the sphere.

The *geographic meridians* are represented by a family of equally spaced parallel straight lines, perpendicular to a second family of parallel straight lines which represent the *geographic parallels.* The spacing, with respect to the *equator,* of the lines which represent the *parallels,* increases as the tangent of the *latitude;* the line representing 90° *latitude* is at an infinite distance from the line which represents the *equator.* This *projection* must not be confused with the *Mercator projection* to which it bears some general resemblance.

map projection: polar orthographic.—See under *map projection: orthographic map projection.*

map projection: polyconic.—A *map projection* having the central *geographic meridian* represented by a straight line, along which the spacing for lines representing the *geographic parallels* is proportional to the distances apart of the *parallels;* the *parallels* are represented by *arcs* of circles which are not concentric, but whose centers lie on the line representing the central *meridian,* and whose radii are determined by the lengths of the elements of cones which are tangent along the *parallels.* All *meridians* except the central one are curved.

This *projection* is neither *conformal* nor *equal-area,* but it has been much used for *maps* of small areas because of the ease with which it can be constructed. It is the *map projection* used for the *Topographic Map of the United States* (U. S. Geological Survey), and in a modified form is used for *maps* of large areas. It was devised by F. R. Hassler, organizer and first superintendent of the U. S. Coast Survey (now the U. S. Coast and Geodetic Survey).

map projection: polyconic, modified.—See under *map projection: modified polyconic map projection.*

map projection: polyconic, rectangular.—See under *map projection: rectangular polyconic map projection.*

map projection: polyconic, transverse.—See under *map projection: transverse polyconic map projection.*

map projection: rectangular polyconic.—A modified *polyconic map projection* having a line representing a *standard parallel* divided to exact *scale,* through whose division points pass the lines representing the *geographic meridians,* intersecting the lines which represent the *geographic parallels* in right *angles.*

map projection: Sanson-Flamsteed.—The *sinusoidal map projection.*

map projection: sinusoidal.—A particular type of the *Bonne map projection,* employing the *equator* as the *standard parallel,* and showing all *geographic paral-*

lels as truly spaced parallel straight lines, along which exact *scale* is preserved.

This is an *equal-area map projection.* It is also known as the *Mercator equal-area map projection* and as the Sanson-Flamsteed map projection. It was employed in the Mercator-Hondius atlases as early as 1606.

map projection: stereographic.—A *perspective map projection* having the point of projection at the opposite end of the diameter of the sphere from the point of tangency of the plane of projection.

It is *conformal,* and is the only *azimuthal map projection* having that quality. It is one of the most widely known of all *map projections,* and has been much used for *maps* of a hemisphere. When the center of the projection is located at a pole of the sphere, it is called a stereographic polar projection; when on the *equator,* a stereographic meridional projection; and when on some other selected *parallel* of *latitude,* a stereographic horizon projection. The stereographic map projection dates back to the days of ancient Greece, having been used by Hipparchus (160–125 B. C.).

map projection: transverse Mercator.—A *map projection* of the so-called cylindrical type, being in principle equivalent to the regular *Mercator map projection* turned (transversed) 90° in azimuth.

In this *projection,* the *central meridian* is represented by a straight line, corresponding to the line which represents the *equator* on the regular *Mercator map projection.* Neither the *geographic meridians,* except the central *meridian,* nor the *geodetic parallels,* except the *equator* (if shown) are represented by straight lines. It is a *conformal projection,* and is the base used in the *State plane-coordinate systems* for the *grids* of those zones whose greater dimension is in a north-and-south direction.

map projection: transverse polyconic.—A *polyconic map projection* which is turned (transversed) 90° in *azimuth* by substituting for the *central meridian,* a *great circle* perpendicular to the *geographic meridian* to provide a control axis for the *projection,* along which axis will lie the centers of the circular *arcs* representing lines of tangency of cones with the surface of the sphere.

This is a difficult projection to construct, but it is useful in showing, with comparatively small distortion, a narrow area of large east-and-west dimension.

map projection: Werner.—A particular case of the *Bonne map projection,* in which the *standard parallel* is at the pole, and the tangent cone becomes a tangent plane.

Any one *geographic meridian* is chosen as the *central meridian* and represented by a straight line, divided to exact *scale.* The *geographic parallels* are represented by circular *arcs,* also divided to exact *scale,* and the other *meridians* are curved lines.

map scale.*—The relationship which exists between a distance on a *map* and the corresponding distance on the earth.

A map scale may be expressed as an equivalence, as a numerical fraction or ratio, or shown graphically. On large-scale *maps,* the distance on the earth is on a designated *datum,* as *sea level* or ground level.

map scale: equivalent.*—An equivalent scale is the relationship which a small distance on the *map* bears to the corresponding distance on the earth, expressed as an equivalence.

Usually, but not necessarily, the equivalence is expressed in different specified units; for example, 1 *inch* (on the *map*) equals 1 *mile* (on the ground).

Of the abbreviated forms, "*inch* to the *mile*" and "*mile* to the *inch,*" the former is preferred. Infrequently called verbal scale.

map scale: fractional.*—A fractional scale is the ratio which any small distance on the *map* bears to the corresponding distance on the earth.

It may be written in the form of a fraction: 1/10,000; or as a proportion, 1 : 10,000. Very infrequently called numerical scale, natural scale, and linear scale. These terms are not recommended.

Fractional scales are representative in any linear units. Usually the term representative fraction, however, is applied to a fractional scale whose numerator is unity (1) and is frequently referred to as the "R. F." of the *map.*

For a map of large scale, the representative fraction has a small denominator; for a map of small scale, the representative fraction has a large denominator.

map scale: graphic (or bar).*—A line on a *map* subdivided and marked with the distance which each of its parts represents on the earth.

mapping plan: national.—A program for the completion of the *Topographic Map of the United States.*

The Federal Board of Surveys and Maps in 1934 and again in 1936 adopted plans which proposed a time schedule for the completion of the *control surveys* and topographic mapping of the United States, and a fiscal budget for those operations. The *Temple Act* (H. R. 4522, 68th Congress), approved 1925, was the forerunner of the various national mapping plans.

mean: arithmetical.—See under *arithmetical mean.*

mean: weighted.—See under *weighted mean.*

mean error.—See under *error.*

mean high water.—The mean height of all *high waters* at a particular point or station over a considerable period of time.

For tidal waters, the cycle of change covers a period of about 18.6 years, and the mean high water is the mean of all *high waters* for that period. For any body of water, it is the mean of all *high waters* over a period of time of such length that increasing its length does not appreciably change the mean.

mean low water.—The mean height of all *low waters* at a particular point or station over a considerable period of time.

For tidal waters, the cycle of change covers a period of about 18.6 *years,* and the mean low water is the mean of all *low waters* for that period. For any body of water, it is the mean of all *low waters* over a period of time of such length that increasing its length does not appreciably change the mean.

mean of the errors.—See under *error.*

mean sea level.—The average height of the sea for all stages of the tide.

Mean sea level is obtained by averaging observed hourly heights of the sea on the open coast or in adjacent waters having free access to the sea, the average being taken over a considerable period of time.

mean solar day.—See under *day.*

mean solar time.—See under *time.*

mean-square error.—See under *error.*

mean sun.—See under *time: mean solar time.*

meander line (United States public-land surveys).*—A *traverse* of the margin of a body of water.

Meander lines are not run as *boundary lines,* but are run for the purpose of defining the sinuosities of the bank or shore line, and for ascertaining the quantity of land remaining after segregation of the water area. In General Land Office practice, only permanent natural bodies of water are meandered.

memorial (United States public-land surveys).*—A durable article deposited in the ground at the position of a *corner,* to perpetuate that position should the *monument* be removed or destroyed.

The memorial is usually deposited at the base of the *monument* and may consist of anything durable, such as glass or stoneware, a marked stone, charred stake, or quantity of charcoal.

Mendenhall pendulum.—See under *pendulum.*

Mercator bearing.—The *bearing* of a straight line plotted on a Mercator *chart* as taken from the *chart.*

It is the *angle* between the straight line and the chart meridians.

Mercator equal-area map projection.—See under *map projection.*

Mercator map projection.—See under *map projection.*

Mercator map projection, transverse.—See under *map projection.*

Mercator track.—A *rhumb line* on a *map* or *chart* constructed on a *Mercator map projection.*

mercury barometer.—See under *barometer.*

meridian (general).—A north-south line from which *longitudes* (or *departures*) and *azimuths* are reckoned; or a plane, normal to the *geoid* or *spheroid,* defining such a line.

meridian: astronomic.—A line on the surface of the earth having the same *astronomic longitude* at every point.

Because the *deflection of the vertical* is not the same at all points, an astronomic meridian is an irregular line, not lying in a single plane. The astronomic meridian and the line whose *astronomic azimuth* at every point is south or north (0° or 180°) are not necessarily coincident, although in *land surveying* the term astronomic meridian is sometimes applied to the north-south line which has its initial on a prescribed astronomic meridian.

meridian: auxiliary guide (United States public-land surveys).*—A new *guide meridian* established, when required, for control purposes where the original *guide meridians* were placed at greater intervals than 24 miles.

Auxiliary guide meridians may be required to limit *errors* of old or to control new surveys; they are surveyed in all respects like regular *guide meridians,* and may be assigned a local name, as "Grass Valley Guide Meridian," or "Twelfth Auxiliary Guide Meridian West."

meridian: celestial.—The *hour circle* which contains the *zenith.* Also defined as the *vertical circle* which contains the celestial pole.

The plane of the celestial meridian is parallel with, but, due to the *deflection of the plumb line,* usually does not contain the axis of *rotation* of the earth; its intersection with the plane of the horizon is the *meridian line* used in *plane surveying.*

meridian: central (State coordinate system).—The *meridian* used as Axis of *Y* for computing projection tables for a *State coordinate system.*

The central meridian of the system usually passes close to the center of figure of the area or zone for which the tables are computed, but to avoid the use of negative values, is given a large positive abscissa, thus requiring that a large constant quantity be added to all *x coordinates.*

meridian: convergence of meridians.—The angular drawing together of the *geographic meridians* in passing from the *equator* to the poles.

At the *equator,* all *meridians* are mutually parallel; passing from the *equator,* they converge until they meet at the poles, intersecting in *angles* that are equal to their differences of *longitude.* The term convergence of meridians is used to designate also the relative difference of direction of *meridians* at specific points on the *meridians.* Thus, for a *geodetic line,* the *azimuth* at one end differs from the *azimuth* at the other end by 180° plus or minus the amount of the convergence of the meridians at the end points.

meridian: double meridian distance (plane surveying).—The sum of the *meridian distances* of the ends of a survey line.

In practice, assuming a closed *traverse* with the *meridian* of reference passing through the initial station, the double meridian distance (D. M. D.) of the first *course* (line) is equal to the *departure* of that *course;* the double meridian distance of each succeeding *course* (line) is equal to the double meridian distance of the preceding *course,* plus the *departure* of the preceding *course,* plus the *departure* of the *course* itself.

Meridian: Ferro (Hierro).—The conventional Ferro Meridian is 17°37′45″ west of Greenwich, being originally chosen exactly 20° west of the Paris Meridian.

Many European geographers used to reckon longitude from this meridian which was taken as the dividing line between the Eastern and Western Hemispheres.

The conventional Ferro Meridian does not coincide with the neighboring island of the same name.

meridian: geodetic.—A line on a *spheroid* which has the same *geodetic longitude* at every point.

If the *spheroid* is an ellipsoid of revolution, as used for purposes of *triangulation,* a geodetic meridian is an ellipse whose plane contains the minor axis of the *spheroid,* and whose *geodetic azimuth* at every point is 0° (south) or 180° (north).

meridian: geographic.—A general term, applying alike to an *astronomic* or a *geodetic meridian.*

Meridian: Greenwich.—The *astronomic meridian* through the center of the *transit instrument* of the Observatory of Greenwich, England.

meridian: grid.—A line through a point parallel to the central *meridian* or Axis of Y of a system of *plane-rectangular coordinates.*

meridian: guide (United States public-land surveys).*—An auxiliary governing line projected north along an *astronomical meridian,* from points established on the *base line* or a *standard parallel,* usually at intervals of 24 miles east or west of the *principal meridian,* on which *township, section,* and *quarter-section corners* are established.

meridian: magnetic.—The vertical plane in which a freely suspended, symmetrically magnetized needle, influenced by no transient artificial magnetic disturbance, will come to rest. Also, a curve on the earth's surface tangent to such a plane at each place it touches.

meridian: prime.—An initial or zero *meridian* from which other *meridians* are reckoned.

At an International Meridian Conference held in Washington, D. C., in 1884, the adoption of the *Greenwich Meridian* as the prime meridian for the earth was approved by the representatives of 22 governments, there being one objector, while two representatives abstained from voting. See also, *meridian: Washington Meridian.*

meridian: principal (United States public-land surveys).*—A line extending north and south along the *astronomical meridian* passing through the *initial point,* along which *township, section,* and *quarter-section corners* are established.

The principal meridian is the line from which is initiated the *survey* of the *township* boundaries along the *parallels.* Auxiliary meridional governing lines, known as *guide meridians*, are established along the *astronomical meridian* usually at intervals of 24 *miles* east or west of the principal meridian. In some of the very early surveys the principal meridian is referred to as the "basis meridian."

meridian: terrestrial.—An *astronomic meridian.*

For particular use, the term *astronomic meridian* is preferred over terrestrial meridian. For general use, the preferred term is *geographic meridian*, which applies alike to *astronomic* and *geodetic meridians.*

Meridian: Washington.—The *astronomic meridian* through the center of the dome of the old Naval Observatory in Washington, D. C.

The Washington Meridian was used in defining the meridional boundaries of several western States. An Act of Congress, September 28, 1850, provided "That hereafter the meridian of the observatory at Washington shall be adopted and used as the American meridian for astronomic purposes and . . . Greenwich for nautical purposes." This Act was repealed August 22, 1912. See *meridian: Greenwich Meridian.*

meridian distance (astronomy).—The *hour angle* of a celestial body when close to but not exactly on the *astronomic meridian.*

This term appears to be limited to computation forms where it is used to designate the *hour angle* of a star observed slightly off the *meridian* in making *latitude* observations by the *zenith telescope method.*

meridian distance (plane surveying).—The perpendicular distance in a horizontal plane of a point from a *meridian* of reference.

The difference of the meridian distances of the ends of a line is called the *departure* of the line.

meridian line (plane surveying).—The line of intersection of the plane of the *celestial meridian* and the plane of the *horizon.*

It is a horizontal *direction* used in surveying; its *astronomical azimuth* is 0° or 180°.

meridian telescope.—A portable instrument so designed that it can be used as an *astronomical transit*, or quickly converted for use as a *zenith telescope.*

The meridian telescope has a base which is divided horizontally into two parts; the upper part rotates upon the lower part about a short vertical axis. The upper part carries two folding uprights (standards) with wyes which support the horizontal axis of the *telescope.* The *telescope* is equipped with a *vertical circle* to which is attached a sensitive *spirit level.* The *telescope* has a fixed *reticle* for use in making *time* observations, and an *ocular micrometer* for *latitude* work. When used as an *astronomical transit*, the two parts of the base are clamped together. It is converted for use as a *zenith telescope* by removing the clamps, and permitting the upper part to rotate through 180°, stops being placed to bring the *telescope* to rest in the plane of the *meridian.* The meridian telescope is also known as the Davidson meridian instrument, after George Davidson of the U. S. Coast Survey, who designed it in 1858.

meridional orthographic map projection.—See under *map projection: orthographic.*

meridional parts: table of.—A table listing lengths of the *meridian* from the *equator* to the various *parallels* of *latitude* increased in the proportion required to show lengths along the *parallels* equal to the corresponding length along the *equator.*

On a sphere, at the *equator*, the length of a minute of *longitude* is equal to the length of a minute of *latitude*, but on receding from the *equator* and approaching the poles, the minutes of *latitude* remain always the same, while the length of a minute of *longitude* steadily decreases.

Because the earth is not a sphere, the above conditions do not exactly fit it. However, in the *Mercator map projection*, the minutes of *longitude* are made to appear of the same length for all *latitudes*, and it becomes necessary in order to preserve existing proportions between lengths of the *parallel* and of the *meridian* at various *latitudes* to increase the lengths along the *meridian*, such increase being greater and greater, the higher the *latitude.* The length of the *meridian*, thus increased, constitutes the number of the meridional part corresponding to that *latitude.*

Such a table, found in books on navigation, affords facilities for constructing a *Mercator map projection*, and for solving problems in Mercator sailing. A close value of a meridional part on an ellipsoid for a given *geographic latitude* is obtained by computing the meridional part for the corresponding *geocentric latitude.*

metallic thermometer.—A device utilizing the difference of the *coefficients of thermal expansion* of the metals of which it is constructed to determine the temperature of those metals.

The measuring rods used on the *base lines* of the Dunkirk-Barcelona *triangulation* (1791–2) were themselves metallic thermometers. Each rod was composed of a strip of copper lying on a strip of platinum; these were fastened together at one end, leaving their other ends free to move in response to changes in their temperature. A scale on the free end of the copper strip was read by means of a *vernier* on the free end of the platinum strip, thus affording a means of determining the temperature of the bars. This apparatus was constructed by Borda. See *Borda scale.*

meter; metre.—A *unit* of length equivalent in the United States to 39.37 *inches* exactly.

The meter was originally defined (in 1791) as the equivalent of one ten-millionth of the length of the *quadrant* of the *meridian* through Paris (from the *equator* to the North Pole). A *unit* derived by this proportion from several *arcs* of *triangulation* became known as the *French legal meter*, the *standard* constructed to represent it being known as the *Metre des Archives.* Under an International Convention in 1875, the *international meter* was derived from the *Metre des Archives*, and the *International Prototype Meter* adopted as a *standard* by the subscribing governments. Copies of this new *standard*, of the same form and alloy as the original, were furnished the governments which subscribed to the Convention of 1875. The United States received two such copies in 1889, one of which was adopted as the national standard of length, and is known as the *National Prototype Meter.* These two copies are in the custody of the National Bureau of Standards, Washington, D. C. The equivalence, 1 meter equals 39.37 *inches* exactly, was prescribed by Act of Congress in 1866.

At the Seventh General (International) Conference on Weights and Measures (Paris, 1927), the following supplementary value of the meter was temporarily adopted:

1 meter = 1,553,164.13 wave-lengths of the red ray of Cadmium vapor, in dry air, at a temperature 15° Centigrade, at a pressure of 760 millimeters of mercury and under normal conditions of *gravity.* Since this determination was made, the necessity for mak-

ing several slight corrections to the result has been realized and the following relation obtained:

1 meter = 1,553,163.7 wave-lengths. The earlier value continues the official value.

meter: Committee Meter.—An iron bar *standard* of one *meter* length, which was brought to America in 1805 by Ferdinand R. Hassler, the first superintendent of the U. S. Coast Survey.

It was one of sixteen such bars which were standardized by the Committee on Weights and Measures in Paris in 1799. It served as the *standard* of length for *geodetic surveys* in this country until 1889 or 1890, when it was replaced by the present *standard,* the *National Prototype Meter.* The Committee Meter was presented by Hassler to the American Philosophical Society in Philadelphia.

meter: French legal.—The *unit* of length defined by the *Metre des Archives.* See *meter; metre.*

meter: international.—The *unit* of length defined by the *International Prototype Meter.* See *meter; metre.*

meter: International Prototype Meter.—A bar *standard* of platinum-iridium which defines the length of the *unit,* the *international meter.*

The International Prototype Meter was produced under the authority and direction of an International Conference held in Paris in 1875, signed by the representatives of 17 governments. It is a line *standard* and was derived from the *Metre des Archives,* an end *standard.* The International Prototype Meter and two other similar bars of the same origin are maintained at the International Bureau of Weights and Measures at Sevres, France, and are used in standardizing the representative copies which were supplied to the governments supporting the Convention of 1875. As a signatory of that convention, the United States received two such representative copies, one of which is known as the *National Prototype Meter.* These copies are in the custody of the National Bureau of Standards, Washington, D. C.

meter: Metre des Archives.—A bar *standard* defining the length of the *French legal meter.*

It is an end *standard,* of platinum, and was used in determining a length for the *International Prototype Meter.* It is now preserved as a museum piece in the International Bureau of Weights and Measures, Sevres, France. See *meter; metre.*

meter: National Prototype Meter.—A *standard* copy of the *International Prototype Meter* which defines the *international meter* as a *unit* of length.

It is a bar of platinum-iridium, of the same form and alloy as the *International Prototype Meter,* and one of the pair received in 1889 from the International Bureau of Weights and Measures, Sevres, France. These bars are in the custody of the National Bureau of Standards, Washington, D. C. They are line *standards.*

method of repetitions, determination of astronomic azimuth.—See under *azimuth.*

micrometer: correction for run of.—A *correction* applied to an observed reading of a graduated circle made with a *micrometer microscope* to compensate for *run of micrometer.*

Specific application of this correction is not required in present-day observations with a *direction instrument,* being neutralized by instrumental adjustment and method of observing.

micrometer: eyepiece.—See under *micrometer: ocular.*

micrometer: filar.—A device attached to a *telescope* or microscope, consisting of a wire thread (filament) connected with a screw in such manner that as the screw is turned, the wire moves through a continuous succession of parallel positions, all in the focal plane of the instrument.

The screw has a fine thread, accurately cut, and calibrated in terms of angular measure (seconds of *arc*): one turn of the screw moves the wire a distance that may be expressed as a certain number of seconds, corresponding to the *angle* at the instrument between two objects which would be bisected by the wire in its two positions. Any small *angle* may be measured by noting the number of turns and fractions of a turn of the screw which are made in moving the wire from one bisection to another, and multiplying this by the value of one turn. See *micrometer: ocular; micrometer microscope.*

micrometer: impersonal.—See under *micrometer: transit micrometer.*

micrometer: ocular.—A *filar micrometer* so placed that its wire moves in the principal focal plane of a *telescope.* Also termed an eyepiece micrometer.

The ocular micrometer is used in *surveying* and astronomic work for making accurate and precise measures of small *angles* between lines to objects viewed with the *telescope.* It is mounted in a frame which is perpendicular to the longitudinal axis of the *telescope,* and can be rotated to measure an *angle* in any plane containing that axis. It may be adjusted to measure *angles* in a plane which contains the longitudinal and horizontal axes of the *telescope,* as in observing *time* using the *transit micrometer* (which is an ocular micrometer); or it may be adjusted to measure *angles* in a plane containing the longitudinal axis but perpendicular to the *horizontal axis* of the *telescope,* as in observing *latitude* with the *zenith telescope.*

micrometer: run of.—The difference in seconds of *arc* between the intended value of one complete turn of a micrometer screw used in reading a graduated circle and its actual value as determined by measuring with the micrometer the space between two adjacent *graduation* marks on the circle.

This quantity has sometimes been called the error of run, but the above designation is more generally used and is preferred. It is an *error,* but is kept quite small by instrumental adjustment, and its effect on observed values is neutralized by methods of observing. See *micrometer: correction for run (of micrometer).*

micrometer: transit.—A form of registering micrometer with its movable wire placed in the *focal plane* of an *astronomic transit* and at right *angles* to the direction of motion of the image of a star which is observed at or near *culmination.* Certain contact points on the micrometer head (wheel) serve to make an electric circuit as they pass a fixed contact spring, thus producing a record on the *chronograph* sheet at each separate instant when the micrometer wire reaches a position corresponding to a contact.

The transit micrometer is also called an impersonal micrometer, because it almost completely eliminates the effect of *personal equation* from time observations made with it.

micrometer method, determination of astronomic azimuth.—See under *azimuth.*

micrometer microscope.—A *filar micrometer* so placed that its wire moves in the focal plane of a microscope.

Using a micrometer microscope, readings of a graduated circle are made with a high degree of *accuracy* and *precision*. The micrometer is so adjusted that an even number of turns will carry the wire exactly the distance between adjacent *graduation* marks on the circle. Any intermediate point on the circle may then be read with the micrometer by interpolation. If the adjustment is imperfect, the amount by which an even number of turns of the screw fails to carry the wire exactly the distance between *graduation* marks is treated as a *systematic error* and is termed by preference the *run of micrometer*. The designation error of run of micrometer is also applied to it.

middle ordinate.—The distance from the middle point of a chord to the middle point of the corresponding circular *arc*.

middle point (M. P.).—That point on a circular curve which is at the same distance from both ends of the curve.

mil.—See under *angle* (*general*), (e).

mile.—A unit of distance. See under *mile: nautical mile; statute mile.*

The term mile is derived from the Latin "mille," meaning a thousand, and applied to the double *pace* of 5 *feet*. The mile of the Romans was 5,000 *feet*, a value that suffered many changes as the mile came into use among the western nations.

mile: geographical.—See under *mile: nautical mile.*

mile: nautical.—A length of *mile* used in ocean navigation.

The United States nautical mile is defined as equal to one-sixtieth of a degree of a *great circle* on a sphere whose surface is equal to the surface of the earth. Its value, calculated for the *Clarke spheroid of 1866*, is 1,853.248 *meters* (6,080.20 feet). The international nautical mile is 1,852 *meters* (6,076.10 feet). The United States nautical mile is also called a sea mile or a geographical mile, and may be taken as equal to the length of a minute of *arc* along the *equator* or a minute of *latitude* on the *map* which is being measured.

mile: sea.—See under *mile: nautical mile.*

mile: statute.—A length of *mile* used in distance measurements on land, and equal to 5,280 feet (1,609.35 *meters*).

military grid.—A quadrillage or system of squares determined by rectangular coordinates on a spherical *map projection*, referred to one origin, and extended over the whole area of the original *map projection*.

A military grid is designed to make data presented on a *map* more readily available for military purposes.

milligal.—See *gal.*

millionth-scale map of the World.—An informal designation for the *International Map of the World* which is being constructed on a scale of 1 : 1,000,000.

minus sight.—See under *foresight* (*leveling*).

missing triangle (pendulum).—A triangle which represents the failure of the two sides of a *knife edge* to reach a perfect intersection in a geometric line.

In the most nearly perfect *knife edge* that can be made, the two planes of the *knife edge* will not quite meet. The base of the missing triangle which is thereby formed is found by optical means to be less than one micron.

modified polyconic map projection.—See under *map projection.*

Molitor leveling rod.—See under *leveling rod: Molitor precise leveling rod.*

Mollweide homalographic map projection.—See under *map projection.*

month.—A measure of *time* based on the motion of the moon in its orbit.

There are various kinds of month defined by the references which determine them. See *month: anomalistic month; calendar month; nodical month; sidereal month; synodical month.*

month: anomalistic.—The interval of *time* between two successive passages of the moon in her orbit through *perigee.*

The length of the anomalistic month is 27.55455 *mean solar days.*

month: calendar.—A division of the *year* as determined by a calendar, approximately one-twelfth of a *year* in length.

While arbitrary in character, the calendar month is based roughly on the *synodical month*. The calendar month ranges in length from 28 to 31 *mean solar days.*

month: lunar.—A *synodical month.*

month: nodical.—The interval of *time* between two successive passages of the moon through the same node of her orbit.

The length of the nodical month averages 27.21222 *mean solar days.*

month: sidereal.—The interval of *time* it takes the moon to make its *revolution* from a given star back to the same star again.

The sidereal month may be measured by the interval of *time* it takes the moon to revolve from a given *celestial longitude* back to the same longitude again, reckoned from a fixed *equinox*. The length of the sidereal month averages 27.321661 *mean solar days*. Because of perturbations, the actual length varies some 7 hours. The difference between the lengths of the sidereal and *tropical months* is due to the *precession of the equinoxes*. The above definition is not precise : the moon will not return to the same *declination* at the end of a sidereal month.

month: synodical (ordinary).—The interval of *time* between two successive conjunctions (new moons) or oppositions (full moons) of the moon. Also called a lunation.

The length of the synodical month is 29.530588 *mean solar days*. It is the *month* intended when a *lunar month* is specified. Synodical is preferred over synodic, which is sometimes used.

month: tropical.—The interval of *time* it takes the moon to make its *revolution* from a given *equinox* back to the same *equinox* again.

The tropical month may be measured by the interval of *time* it takes the moon to revolve from a given *celestial longitude* back to the same *longitude* again, reckoned from an *equinox* affected by precession. The length of the tropical month averages 27.321582 *mean solar days*. Because of perturbations, the actual length varies some 7 hours. The difference between the lengths of the *sidereal* and tropical months is due to the *precession of the equinoxes.*

monument.—Any material object or collection of objects which indicates the position on the ground of a survey station or land corner.

The term monument may include the mark at the center or station and all marks which are directly related to it by surveying processes and are aids in its recovery and identification. In *land surveying* the term may include also objects such as roads, ditches, fences, etc., which form a bound for the land. It is well therefore in treating of survey stations to use the designations station mark or center mark, *reference mark*, and *witness mark* for the separate marks; and in *land surveying*, unless monument is used in a general sense, to use the particular terms, *corner*, or corner mark, *reference mark*, and *witness mark*. Note that a *witness mark* has more authority in *land surveying* than in *control surveying*.

monument (United States public-land surveys).*—A physical structure which marks the location of a *corner* or other survey point.

Monument and *corner* are not synonomous, though the two terms are often used largely in the same sense.

mountain barometer.—See under *barometer*.

multiple level line.—See under *level line*.

N

nadir.—The point where the direction of the plumb-line extended below the *horizon* meets the *celestial sphere*.

The nadir is directly opposite the *zenith*.

national control survey nets.—See under *control*.

national mapping plan.—See under *mapping plan*.

National Prototype Meter.—See under *meter*.

nautical chart.—See under *chart*.

nautical mile.—See under *mile*.

navigable waters.—The waters which are used or are susceptible of being used, in their ordinary condition or after reasonable improvements have been made, as highways for commerce in the customary means of travel on water.

net (leveling).—A series of *lines of levels* which have been interconnected in such a manner that closed loops or *circuits* have been formed.

network (leveling).—See *net (leveling)*.

New England datum.—See under *datum*.

Newtonian constant of gravitation.—See under *gravitation: constant of gravitation*.

New York leveling rod.—See under *leveling rod*.

nodal point of a lens, first and second.—The intersections of the *principal axis* with the (produced) incident and emergent parts, respectively, of any ray having those parts parallel to each other.

nodical month.—See under *month*.

nomogram.—A chart or drawing showing, to scale, the relationship between known and dependent variables, in such manner that a value of a dependent variable corresponding to a stated value of the known variable can be scaled from the chart.

Nomograms are used in the graphical solution of formulas where the *precision* of the result does not require numerical computation.

nomograph.—A *nomogram*.

Although the term nomograph is given the preference in Webster's International Dictionary, *nomogram* is preferred in the several texts consulted.

normal.—In general, a straight line perpendicular to a surface or to another line. Also, a condition of being perpendicular to a surface or line. In *geodesy*, a straight line perpendicular to the surface of the *spheroid*.

While the term normal is correctly used to designate also a line perpendicular to the surface of the *geoid*, the term *vertical* is preferred for such a line. The term normal, in general, applies to a line of unspecified length, but some writers use it to designate the length of line between the surface of the *spheroid* and the minor axis, giving it the designation "N". To this particular line the French apply the term "great normal". This length is the radius of curvature of a *prime vertical* section of the spheroid.

normal equation.—See under *equation*.

normal section azimuth.—See under *azimuth: normal section*.

normal section line.—A line on the surface of the *spheroid*, connecting two points on that surface, and traced by a plane containing the *normal* at one point and passing through the other point.

There can be two such lines connecting any two points (as A and B) on the *spheroid:* one defined by the plane containing the *normal* at A and passing through B; the other containing the *normal* at B and passing through A. Where the two points are on the same parallel of *latitude* or on the same meridian of *longitude*, the two lines will be coincident.

North American datum.—See under *datum*.

North American datum of 1927.—See under *datum*.

north star.—See under *Polaris*.

northing.—See under *latitude: difference of latitude (plane surveying)*.

nutation.—A periodic motion of the celestial poles.

O

obliquity of the ecliptic.—See under *ecliptic*.

obliterated corner (United States public-land surveys).—See under *corner*.

observation: direct.—A measure of the quantity whose value is desired.

Example: a single measure of a *horizontal angle*.

observation: indirect.—A measure of a quantity which is a function of the quantity or quantities whose value is desired.

Example: an observed difference of *elevation* with a *spirit level*, used to obtain the *elevation* of a *bench mark*.

observation equation.—See under *equation*.

observed angle.—See under *angle*.

observed value.—See under *value*.

occultation.—The disappearance of a body behind another body of larger apparent size.

When the moon passes between the observer and a star, the star is said to be occulted. The three associated terms, occultation, *eclipse*, and *transit*, are exemplified by the motions of the satellites of Jupiter. An *eclipse* occurs when a satellite passes into the shadow cast by the planet; an occultation occurs when a satellite passes directly behind the planet, so that it could not be seen even if it were illuminated; and a transit occurs when a satellite passes between the observer and the planet, showing against the disk of the planet. The occultation of stars by the moon furnishes a method of determining *latitude* and *longitude* used in early *surveys,* particularly those of an exploratory character.

odometer.—A *revolution* counter which is attached to the wheel of a vehicle and registers the number of turns made by the wheel in traveling over the ground.

An odometer is used in obtaining an *approximate* value of the distance traveled, the number of *revolutions* being multiplied by the circumference of the wheel. See *passometer.*

offset.—A short line perpendicular to a surveyed line, measured to a line or point for which data are desired, thus locating the second line or point with reference to the first or surveyed line. An offset is also a jog in a *survey* or other line, the line having approximately the same direction both before and after passing the jog.

Offsets are measured from a surveyed line or lines to the edges of an irregular-shaped body of water, or to any irregular line which it is desired to locate.

offset (United States public-land surveys).—A perpendicular distance measured from a *great circle line* to a *parallel* of *latitude,* to locate a *section corner* on that *parallel.* See *secant method (United States public-land surveys); tangent method (United States public-land surveys).*

offset line.—A supplementary line close to and roughly parallel with a main line, to which it is referred by measured *offsets.*

Where the line for which data are desired is in such position that it is difficult to measure over it, the required data are obtained by running an offset line in a convenient location and measuring *offsets* from it to salient points on the other line.

Old Hawaiian datum.—See under *datum.*

optical axis (lens).—See under *principal axis.*

optical base-line measuring apparatus.—See under *base apparatus.*

optical parallax.—See under *parallax: instrumental parallax.*

optical square.—A small hand instrument used in setting off a right *angle.*

One form of optical square employs two plane mirrors placed at an *angle* of 45° to each other. In use, one object is sighted direct, and another object is so placed that its twice-reflected image appears directly in line with the first object. The lines to the point of observation from the two observed objects will then meet in a right *angle.* In another form of optical square, a single plane mirror is so placed that it makes an *angle* of 45° with a sighting line; one object is sighted direct, and the other so placed that its reflected image is seen also in the sighting line.

optical vernier.—See under *vernier.*

orientation.—The act of establishing correct relationship in direction with reference to the points of the compass; the state of being in correct relationship in direction with reference to the points of the compass.

A *map* is in orientation when the *map* symbols are parallel with their corresponding ground features. A *plane table* is in orientation when lines connecting positions on the *plane table* sheet are parallel with the lines connecting the corresponding ground objects. A surveyor's *transit* is in orientation if the horizontal circle reads 0° when the *line of collimation* is parallel to the direction it had at an earlier (initial) position of the instrument, or to a standard line of reference. If the line of reference is a *meridian,* the circle will show *azimuths* referred to that *meridian.*

A photograph is in orientation when it correctly presents the perspective view of the ground directly in front of the observer; or when images on the photograph appear in the same direction from the point of observation as do the corresponding map symbols.

origin of coordinates.—See under *coordinates.*

orthodrome.—An obsolete term descriptive of a *great circle.*

orthographic map projection.—See under *map projection.*

orthometric correction.—See under *correction.*

orthometric elevation.—See under *elevation.*

orthomorphic map projection.—See under *map projection.*

oscillation (pendulum).—A double motion, one in each direction, of a *pendulum.* An oscillation is composed of two consecutive *vibrations.*

In some texts, a *vibration* is called a simple oscillation, and an oscillation is called a double or complete oscillation.

outcrop.—The exposed portion of a rock stratum or vein at the surface of the earth.

In describing a *survey* station, the exposed portion of a large boulder is sometimes mistaken for an outcrop.

outline map.—See under *map.*

P

pace.—The distance a pedestrian moves in taking one step.

See *stride.*

Panama-Colon datum.—See under *datum.*

parallactic error.—See under *error.*

parallax (general).—1. The difference in the direction of an object as seen by an observer and as seen from some standard point of reference. 2. An apparent displacement of the position of the body with respect to a reference point or system caused by a shift in the point of observation.

Parallax enters into many problems of astronomy, *surveying,* and mapping. It is an inclusive term, and wherever clarity demands, it should be accompanied by a defining adjective. See *annual parallax, diurnal parallax, secular parallax, instrumental parallax,* and proposed new terms, *optical parallax,* and *personal parallax.* Parallax is also a basic term in photogrammetry, being qualified as "linear parallax," "stereoscopic parallax," etc.

parallax: annual.—The difference between the direction from the earth to a star and the direction from the sun to the same star. Also termed heliocentric parallax.

The annual parallax of a given star is equal to the *angle* at the star subtended by the radius of the earth's orbit. See *parsec.* Annual parallax does not enter into any *surveying* problems.

parallax: diurnal.—The difference between the direction from a point on the surface of the earth to a planet, star, or other celestial object, and the direction from the center of the earth to the same object. Also termed geocentric parallax.

Diurnal parallax at a given point on the surface of the earth changes in magnitude as the earth rotates on its axis: it is greatest when the celestial object is in the *horizon* of the given point, when it is equal to the *angle* at the object subtended by the semidiameter of the earth, and is termed horizontal parallax. The *angle* at a celestial object subtended by the equatorial semidiameter of the earth is termed equatorial horizontal parallax, and is used to indicate the distance of the object from the earth.

Of less importance to the surveyor is *annual* or *heliocentric parallax,* the difference of directions to a star from the earth and from the sun, and of no importance whatever is secular parallax, due to the slow progressive motion of the solar system through space.

parallax: equatorial horizontal.—See under *parallax: diurnal parallax.*

parallax: geocentric.—See under *parallax: diurnal parallax.*

parallax: heliocentric.—See under *parallax: annual parallax.*

parallax: horizontal.—See under *parallax: diurnal parallax.*

parallax: instrumental.—A change in the apparent position of an object with respect to the reference mark(s) of an instrument which is due to imperfect adjustment of the instrument or to a change in the position of the observer.

When a *telescope* is poorly focused, so that the image of the object does not lie in the plane of the *reticle* (cross hairs), a movement of the eye transverse to the *line of collimation* will cause an apparent movement of the image of the object with respect to the cross hairs. This is a usual form of instrumental parallax, and for it the term optical parallax is proposed. *Parallax* may also result from the position in which an observer stands with respect to the *fiducial marks* on an instrument, as when reading a *vernier* or marking a tape end; for this type of *parallax* the term personal parallax is proposed.

parallax: optical.—See under *parallax: instrumental parallax.*

parallax: personal.—See under *parallax: instrumental parallax.*

parallax: secular.—See under *parallax: diurnal parallax.*

parallax: solar.—The *equatorial horizontal parallax* of the sun.

Solar parallax is the basis for the determination of the *astronomical unit,* and is used in some astronomical calculations as a measure of distance in place of that unit.

parallel: astronomic.—A line on the surface of the earth which has the same *astronomic latitude* at every point.

Because the *deflection of the vertical* is not the same at all points on the earth, an astronomic parallel is an irregular line, not lying in a single plane. The astronomic parallel of 0° *latitude* is called the *astronomic equator;* also called the *terrestrial equator.*

parallel: auxiliary standard (United States public-land surveys).*—A new *standard parallel* or *correction line* established, when required, for control purposes where original *standard parallels* or *correction lines* were placed at intervals of 30 or 36 miles.

Auxiliary standard parallels are used in the extension of old *surveys* and for the control of new *surveys.* Such a line may be given a local name, as "Cedar Creek Correction Line," or "Fifth Auxiliary Standard Parallel North."

parallel: geodetic.—A line on the *spheroid* which has the same *geodetic latitude* at every point.

A geodetic parallel, other than the *equator,* is not a *geodetic (geodesic) line.* In form, it is a small circle whose plane is parallel with the plane of the *geodetic equator.*

parallel: geographic.—A line on the earth having the same *latitude* at every point.

The term is applicable alike to an *astronomic parallel* or to a *geodetic parallel.*

parallel: standard (cartography).—A *parallel* of *latitude* which is used as a control line in the computation of a *map projection.*

In illustrations of *map projections* of the conic type, a standard parallel usually represents a line of tangency or of intersection of a cone with the surface of the *spheroid.* Such illustrations are not exact.

parallel: standard (United States public-land surveys).*—An auxiliary governing line established along the *astronomic parallel,* initiated at a selected *township corner* on a *principal meridian,* usually at intervals of 24 miles from the *base line,* on which *standard township, section,* and *quarter-section corners* are established; also known as a "correction line."

Standard parallels, or "correction lines" are established for the purpose of limiting the convergence of *range lines* from the south.

parallel of altitude.—See under *almucantar.*

parallel of declination.—See under *declination.*

parametric latitude.—See under *latitude.*

Parkhurst theodolite.—See under *theodolite.*

parsec.—The distance at which the *annual parallax* is equal to one second of *arc* (1").

partial (leveling).—See *divergence (leveling).*

passometer.—A pocket-size instrument which registers the number of steps taken by the pedestrian carrying it.

The passometer is housed in a case resembling a watch case and is carried in an upright position attached to the body or to a leg. The distance walked is obtained by multiplying the number of steps taken by the length of a *pace,* or of a *stride,* if double steps are registered. See also *pedometer.*

pedometer.—A pocket-size instrument which registers the distance in linear units traversed by the pedestrian carrying it.

The term pedometer was formerly applied also to an instrument which registered the number of steps taken, but for which the term *passometer* is now used. The pedometer, like the *passometer,* is housed in a case resembling a watch case, and is carried in an upright position attached to the body or to a leg. It registers the linear distance traveled in miles or other units, the number of steps taken being mechanically transformed into linear units. This transformation depends upon the length of a *pace,* which may be different for different persons. The pedometer can be adjusted to the length of the *pace* of the person carrying it.

peg adjustment.—A method of adjusting a *leveling instrument* of the *dumpy level* type, to make the *line of collimation* parallel with the *axis of the spirit level,* and employing two stable marks (pegs) the length of one instrument sight apart.

The peg adjustment can be used with a *wye level,* but such an instrument is more readily adjusted by reversing the *telescope* in its wyes. A form of peg adjustment is used in determining the *collimation error* of *first-order leveling instruments* of the *dumpy level* type.

Pemberton leveling rod.—See under *leveling rod: Pemberton rod.*

pendulum.—In general, a body so suspended as to swing freely to and fro under the influence of *gravity* and momentum. See *pendulum: simple pendulum; compound pendulum.*

pendulum: bronze.—A quarter-meter *pendulum* used by the U. S. Coast and Geodetic Survey, and made of aluminum bronze consisting of one part of aluminum and nine parts of copper.

Beginning in 1920, bronze pendulums were replaced by *invar pendulums* in the *gravity* work of the U. S. Coast and Geodetic Survey.

pendulum: compound.—Any actual *pendulum.*

A compound pendulum may be considered as composed of an indefinitely large number of material particles, at different distances from the *center of suspension,* each constituting a *simple pendulum.* The period of *vibration* (*oscillation*) of the compound pendulum may be taken as a resultant of the periods of the *simple pendulums* of which it is composed.

pendulum: dummy.—A *pendulum* of similar construction to the *working pendulums* except that it is equipped with a thermometer and is fastened rigidly in the *receiver* so that it cannot swing during observations.

The dummy pendulum is subject to the same temperature conditions as the *working pendulums,* and is used in determining their temperature when in use.

pendulum: free-swinging.—A *pendulum* moving wholly under the influence of *gravity* and an initial momentum imparted to it by mechanical or other means.

In *gravity* work, the initial momentum may be imparted by drawing the *pendulum* slightly out of plumb and then releasing it.

pendulum: idle.—A *working pendulum* placed in the receiver in advance of its being used, so that it may assume the same temperature as the *dummy pendulum.*

pendulum: invar.—A quarter-meter *pendulum* used by the U. S. Coast and Geodetic Survey, and made of an alloy consisting of approximately one part of nickel and two parts of iron.

Beginning in 1920, invar pendulums have replaced *bronze pendulums* in the *gravity* work of the U. S. Coast and Geodetic Survey. The invar pendulum is subject to magnetization, and has a *coefficient of thermal expansion* about one-fifteenth that of the *bronze pendulum* which it replaced. In general, the two *pendulums* are quite similar, the weight of the invar pendulum being somewhat greater and its bob a little thicker at the middle.

pendulum: invariable.—A *pendulum* so designed and equipped with means of support that it can be used in only one position.

With an invariable pendulum, the *centers of suspension* and *of oscillation* are not interchangeable in use. *Pendulums* of this type have been constructed by Kater, Peirce, and Mendenhall. They may be used only for relative measurements of the *intensity of gravity.*

pendulum: Mendenhall.—An *invariable pendulum,* one-quarter meter in length, with a *vibration* period of one-half second, composed of a lenticular-shaped bob on a thin stem, swung in an airtight case from which the air has been largely exhausted.

This *pendulum* was designed in 1890 by Superintendent Mendenhall and assistants of the U. S. Coast and Geodetic Survey. It is the form of *pendulum* used since then by that Bureau in determinations of the *intensity of gravity,* but has undergone various improvements in mounting, methods of observation, etc.

pendulum: reversible.—A *pendulum* so designed and equipped with means of support that it may be used with either end up or down.

With a reversible pendulum, the *centers of suspension* and *of oscillation* are interchangeable in fact. This type of *pendulum* is exemplified by *pendulums* constructed by Kater, by Peirce, and by Repsold. Reversible pendulums may be used for absolute measurements of the *intensity of gravity* at base stations. See *pendulum: invariable.*

pendulum: simple.—A theoretical concept: a heavy particle suspended from a fixed point by a fine thread which is inextensible and without weight.

A simple pendulum cannot be realized in actual work. A simple pendulum is, however, the basis of reductions of observations made with an actual *pendulum.* Those observations have *corrections* applied to them to obtain results which would have been produced by an equivalent simple pendulum.

pendulum: temperature correction.—The quantity that is applied to the period of *vibration* of a *pendulum* to allow for the difference in the length of the *pendulum* at the temperature of observation and its length at some other temperature which has been adopted for purposes of *standardization* or for combining or comparing corresponding values.

In the work of the U. S. Coast and Geodetic Survey, the temperature adopted for these purposes is 15° centigrade.

pendulum: working.—A *pendulum* which is used (swung) in a determination of the *intensity of gravity.*

perigee.—The point in the orbit of the moon nearest to the earth.

perihelion.—The point in the orbit of a planet or comet closest to the sun.

Perihelion of the earth's orbit provides the index for the *anomalistic year.*

permanent bench mark.—See under *bench mark.*

perpendicular equation (traverse).—See under *equation.*

personal equation.—The *time* interval between the sensory perception of a phenomenon and the motor reaction thereto.

Personal equation may be either positive or negative, as an observer may anticipate the occurrence of an event, or wait until he actually sees it occur before making a record.

This is a *systematic error,* treated as of the constant type. It is a *personal error,* for which the term personal equation is reserved. It is of especial significance in observations of *time,* made to determine *clock correction.* For example, it is the elapsed *time* between the seeing of the event, star bisected by wire, and the recording of that event by mechanical (*chronograph*) means or by other method (eye-and-ear). Because of its significance in such work, special means have been developed for its control. See *micrometer: transit.*

personal error.—See under *error.*

personal parallax.—See under *parallax: instrumental.*

perspective map projection.—See under *map projection.*

perspective map projection upon a tangent cylinder.—See under *map projection.*

phase.—The visible aspect of an object.

In astronomy, phase is a stage in a cycle of recurring aspects, caused by a systematic variation of the illumination of an object. The moon passes through its phases, new moon to full moon and back to new moon, as its position relative to the sun and earth changes. In *surveying,* phase is applied to a signal which presents areas of varying brightness to the observer: a round pole, illuminated from the side; a square pole, of which the observer sees two sides, one more strongly illuminated than the other. The *error* in pointing due to phase is of the same character and requires the same treatment as an *error* due to observing an *eccentric object.* Phase may be closely associated with *asymmetry of object* (target), but the two terms are not identical.

Philadelphia leveling rod.—See under *leveling rod: Philadelphia rod.*

physiographic feature.*—A prominent or conspicuous *physiographic form* or salient part thereof.

physiographic form.*—A *land form* considered with regard to origin, cause, or history.

physiography.*—The classification of the genesis of *land forms.*

pivot inequality.—Any difference in the diameters or any irregularities in the form of the pivots of the *horizontal axis* of a surveying or astronomical instrument (*theodolite, transit,* etc.).

Though formerly taken into account in the computation of astronomical observations made in connection with *geodetic surveys,* corrections for pivot inequality have been rendered unnecessary by the production of instruments having pivots which are *accurate* and *precise* in size and form.

plane (pendulum).—A suspension bearing used in the support of a *pendulum.*

In the *Mendenhall pendulum,* an agate plane is mounted in the head of the *pendulum;* this bears on an agate *knife edge* which is mounted in the *receiver.* Since 1940, the positions of plane and *knife edge* in some *pendulums* have been reversed.

plane coordinates: State coordinate system.—See under *State coordinate systems.*

plane elliptic arc.—Any part of the line formed by the intersection of a plane and an *ellipsoid.*

plane rectangular coordinates.—See under *coordinates.*

plane survey.—See under *surveying: plane.*

plane surveying.—See under *surveying.*

plane table (surveying).—A device for plotting the lines of a *survey* directly from the observations.

A plane table consists essentially of a drawing board on a tripod, with a ruler, the ruler being pointed at the object observed by means of a telescope or other sighting device.

planimeter.—A mechanical integrator for measuring the area of a plane surface.

Using a planimeter, the *map* area within a given perimeter can be measured; by application of a factor derived from the *map scale,* the *map* area can be transformed into the corresponding area on the earth. There are several forms of planimeters, depending on the same mathematical principles, but differing in their mechanical design and operation. The one most generally used in map work is the polar planimeter; other well-known forms are the rolling planimeter and the suspended planimeter.

planimetric map.—See under *map.*

planimetry.—The mensuration of plane surfaces.

In mapping, planimetry is the determination of horizontal distances, *angles,* and areas, by measurements on a *map.*

planisphere.—A representation on a plane of the circles (*parallels, meridians,* etc.) of a *sphere.*

A particular form of a planisphere is a *polar map projection* of the *celestial sphere,* with movable parts which can be adjusted to show the visible aspect of the heavens at any given time, thereby aiding in the selection and identification of stars for various purposes. The planisphere is the basis of the *planispheric astrolabe.*

planispheric astrolabe.—See under *astrolabe.*

plat (general).*—A diagram drawn to *scale* showing all essential data pertaining to the boundaries and subdivisions of a tract of land, as determined by *survey* or protraction.

A plat should show all data required for a complete and accurate description of the land which it delineates, including the *bearings* (or *azimuths*) and lengths of the boundaries of each subdivision. A plat may constitute a legal description of the land and be used in lieu of a written description.

plat (United States public-land surveys).*—The term *plat,* as employed technically by the U. S. General Land Office, refers to the drawing which represents the particular area included in a survey, such as a *township,* private land claim, or mineral claim, and the lines surveyed, established, retraced, or resurveyed, showing the direction and length of each such line; the relation to the adjoining official surveys; the boundaries, descriptions, and area of each parcel of land subdivided; and, as nearly as may be practicable, a representation of the *relief,* and improvements within the limits of the *survey.*

A public-land survey does not obtain complete official or legal status until the field notes and the *plat* have been approved by the proper supervising officer, and accepted by the Commissioner of the General Land Office.

plot.—To place *survey* data upon a *map* or *plat.*

In past use, no clearly defined difference existed between *plat* and plot. It is suggested that a difference be established by limiting *plat* to the graphical representation of a *survey,* and plot to the cartographic operations involved in the construction of a *map* or *plat.*

plus distance.—The distance along a *survey* line from a *survey station* or the last even-numbered *survey* point to a supplementary point.

A stake is set at 515.56 feet from the initial point of a *survey* line and is not the terminal of that line: the even 500-foot point is station No. 5; the stake is a *plus station* (No. 5+15.56), and 15.56 feet is a plus distance.

plus sight.—See under *backsight* (*leveling*).

plus station.—An intermediate point on a *survey* line, not at an even tape length distance from the initial point. See *plus distance.*

point.—A position on a reference system determined by a *survey.* A *fix.*

point: turning (leveling).—A point on which a *foresight* is taken from one *instrument station* in a *line of levels* and on which a *backsight* is taken from the next instrument station in the *running* and which is established simply for the purpose of allowing the *leveling instrument* to be moved forward along the line of levels without a break in the series of measured differences of elevation.

A turning point may be a steel pin driven in the ground, the head of a hold-down spike on a railroad track, a nail driven in a tie of a railroad track, a ball bearing set in a small dent in a concrete pavement, etc.

point of compound curvature.—See under *curve.*

point of curvature.—See under *curve.*

point of intersection.—See under *curve.*

point of tangency.—See under *curve.*

pointers: the pointers.—The second-magnitude stars, Alpha and Beta, in the constellation Ursa Major (Big Dipper), the line through which points to *Polaris.*

The pointers facilitate the finding and identification of *Polaris.* They are in the outer side of the "bowl" of the Big Dipper, away from the handle.

polar coordinates.—See under *coordinates.*

polar distance.—The complement of the *declination* (*co-declination*) or 90° minus the *declination.*

Polar distance forms one side, celestial body to pole, of the *astronomical triangle.* It is opposite the *zenith.*

polar orthographic map projection.—See under *map projection: modified polyconic.*

Polaris.—The second-magnitude star, Alpha, in the constellation Ursa Minor (Little Dipper).

Also known as the polestar, or north star, because of its proximity to the north pole of the *celestial sphere,* Polaris is well situated for determinations of *astronomical azimuth,* and for the determination of the direction of the *celestial meridian.* It is at the extreme outer end of the handle of the "Little Dipper." See *pointers: the pointers.*

polestar.—See under *Polaris.*

polyconic map projection.—See under *map projection.*

polyconic map projection, modified.—See under *map projection.*

polyconic map projection, transverse.—See under *map projection: transverse polyconic.*

Port Clarence datum.—See under *datum.*

position.—1. Data which define the location of a point with respect to a reference system. The place occupied by a point on the surface of the earth. The *coordinates* which define the location of a point on the *geoid* or *spheroid.*

2. A prescribed setting (reading) of the horizontal circle of a *direction theodolite* to be used for the observation on the initial station of a series of stations which are to be observed on.

The term as defined under 2 (above) indicates a definite position of the horizontal circle. For example, in *first-order triangulation,* using a two-micrometer *direction theodolite,* in Position No. 1, the circle is set to read 0° 00′ 40″ when the initial station is observed; in Position No. 2, the circle is set to read 11°01′50″ when the initial station is observed; etc.

position: adjusted.—An *adjusted value* of the coordinate position of a point on the earth.

In the adjustment of a horizontal *control survey, discrepancies* arising from *errors* in the observational data are removed, and position data of the survey stations are correlated and coordinated on an adopted reference system (*geodetic datum* or *plane-coordinate system*). The positions which are obtained by the adjustment are called adjusted positions, and when used as control for other work are referred to as fixed positions. In the adjustment of a vertical control survey, the values obtained are adjusted elevations, called fixed elevations when used to control other work.

position: field.—A *position* computed while field work is in progress to determine the acceptability of the observations or to provide a *preliminary position* for other purposes.

position: fixed.—See under *position: adjusted position.*

position: geodetic.—A position of a point on the surface of the earth expressed in terms of *geodetic latitude* and *geodetic longitude.*

A geodetic position implies an adopted *geodetic datum.* In a complete record of a geodetic position, the *datum* must be stated.

position: geographic.—The position of a point on the surface of the earth expressed in terms of *latitude* and *longitude,* either *geodetic* or *astronomic.*

The U. S. Coast and Geodetic Survey uses the term geographic positions for positions on a *geodetic datum.*

position: preliminary.—See under *preliminary.*

position: relative.—The location of a point with respect to other points.

The relative position of two points whose positions are given on the same coordinate system is the difference of their *coordinates,* which may also be expressed by a *direction* and distance.

position line.—See under *line of position.*

postal map.—See under *map.*

post route map.—See under *map.*

Pratt theory of isostasy.—See under *isostasy.*

precession.—See under *precession of the equinoxes.*

precession of the equinoxes.—A slow western movement of the *equinoxes.*

Precession of the equinoxes amounts to about 50″ per year and causes the difference in length between the *sidereal* and *tropical years.*

precise level.—See under *leveling instrument.*

precise leveling.—See under *leveling: first-order.*

precise triangulation.—See under *triangulation.*

precision.*—Degree of refinement in the performance of an operation or in the statement of a result.

Precision relates to the quality of execution, and is distinguished from *accuracy* which relates to the quality of the result. The term precision not only applies to the fidelity with which required operations are performed, but by custom has been applied to methods and instruments employed in obtaining results of a high order of *accuracy.* Precision is exemplified by the number of decimal places to which a computation is carried and a result stated. In a general way, the *accuracy* of a result should determine the precision of its expression. Precision is of no significance unless *accuracy* is also obtained.

preliminary.—Not of the desired *accuracy* and *precision,* and adopted for temporary use with the proviso of later being superseded.

In the *adjustment* of *triangulation,* the term preliminary is applied to triangles and *geographic positions* derived from selected observations for use in forming *latitude* and *longitude condition equations.*

preliminary elevation.—See under *elevation.*

preliminary position.—See under *preliminary.*

preliminary survey.—See under *survey.*

preliminary triangle.—See under *preliminary.*

Pribilof Islands datums.—See under *datum: St. George Island datum; St. Paul Island datum.*

primary triangulation.—See under *triangulation.*

prime meridian.—See under *meridian.*

prime vertical.—A *vertical circle* perpendicular to the plane of the *celestial meridian.*

The plane of the prime vertical cuts the *horizon* in the east and west points.

principal axis (of a lens).—The line *normal* to both surfaces of a lens.

In a well-centered lens system, for which the principal axes of the components are in the same straight line, that line is termed the optical axis of the system, or simply the axis. It should never be called the optic axis, which is a term used in crystallography.

principal meridian (United States public-land surveys).—See under *meridian.*

principal station.—See under *station.*

prismatic astrolabe.—See under *astrolabe.*

prismatic compass.—See under *compass.*

probable error.—See under *error.*

probable value: most probable value.—See under *value: most probable value.*

profile.—A section cut from the surface of the earth by a line moving along a fixed line as a directrix, and showing the line of intersection with that surface or with some underlying stratum.

Usually the moving line will be a vertical straight line, and the directrix will be a straight line or a regular curve (as the center line of a railroad or highway). The surface of intersection will be a plane surface or a regular curved surface that can be developed on a plane.

progress sketch.—A *map* or sketch showing work accomplished.

In *triangulation* and *traverse surveys,* each point established is shown on the progress sketch, and also lines observed over and *base lines* measured. In a *leveling survey,* the progress sketch shows the route followed and the towns passed through, but not necessarily the locations of the *bench marks.*

projection (surveying).—The extension of a line beyond the points which determine its character and position. The transfer of a series of *survey* lines to a single theoretical line by a series of lines perpendicular to the theoretical line.

In surveying a *traverse,* a series of measured short lines may be projected onto a single long line, connecting two main *survey* stations, and the long line then treated as a measured line of the *traverse.*

projection: map.—See under *map projection.*

protractor.—An instrument consisting of a plate marked with units of circular measure.

A protractor is used in laying out on a flat or curved surface an *angle* of desired magnitude; or in determining the magnitude of the *angle* made by two intersecting lines on a flat surface. Protractors are made in many sizes and forms to suit the purpose and convenience of the ones using them. See *protractor: three-arm protractor; coordinate protractor.*

protractor: coordinate.—A square-shaped *protractor* having graduations on two adjacent edges, with the center at one corner. It is equipped with a movable arm turning about the center, and graduated to show linear quantities on a given *scale.* The *protractor* is covered with a *grid* of the same *scale* and units as the arm.

In use, the arm is set for a given *azimuth* or *bearing,* and the length of a line marked on the arm: a reading of the *grid* at this point will give the *latitude* and *departure* of a line of the given length and *bearing.*

protractor: three-arm.—A full-circle *protractor,* equipped with three arms, the fiducial edges (extended) of which pass through the center of the circle. The middle arm is fixed, and reads 0° on the graduated circle. The other arms are movable, and their positions on the circle are read with the aid of *verniers.*

The two movable arms may be set to two *angles* observed between three fixed signals of known position, and the position of the point of observation obtained by a graphical solution of the *three-point problem.* Also called a station pointer.

public domain (United States).*—The territory ceded to the Federal Government by the Original Thirteen States, together with certain subsequent additions by cession, treaty, and purchase.

At its greatest extent, the public domain aggregated over 1,820,000,000 acres and included the present States of Alabama, Arizona, Arkansas, California, Colorado, Florida, Idaho, Illinois, Indiana, Iowa, Kansas, Louisiana, Michigan, Minnesota, Mississippi, Missouri, Montana, Nebraska, Nevada, New Mexico, North Dakota, Ohio, Oklahoma, Oregon, South Dakota, Utah, Washington, Wisconsin, Wyoming, and the Territory of Alaska.

public land (United States).*—The portion of the *public domain (United States)* to which title is still vested in the Federal Government.

public land States.*—Those States and Territories created out of the *public domain (United States).*

For list of public-land States see *public domain (United States).*

Puerto Rico datum.—See under *datum.*

Q

quadrant.—Mathematics. A *sector* having an *arc* of 90°. Surveying. A *surveying* or astronomical instrument composed of a graduated *arc* about 90° in length, equipped with a sighting device (*alidade*).

The quadrant may be considered a form of *sector (surveying).* Some quadrants combine both *surveying* and astronomical functions, having two *arcs,* one horizontal and one vertical.

quarter section (United States public-land surveys).—See under *section.*

quarter-quarter section (United States public-land surveys).—See under *section.*

R

radar.—The art of detecting by means of radio echoes the presence of objects, determining their direction and range, and employing the data obtained for navigational or military purposes.

Radar information is commonly obtained from the plan position indicator (PPI), a form of oscilloscope on which the direction and range of an echoing object are represented graphically.

radian.—See *angle (general), (d).*

random line.—A trial line run as nearly as circumstances permit from one survey station toward another survey station which cannot be seen from the first station.

The *error of closure* (amount by which the second station is missed) permits the computation of a *correction* to the initial *azimuth* of the random line; it also permits the computation of *offsets* from the random line to establish points on the line between the survey stations.

random traverse.—See under *traverse.*

range.—In general, two points in line with the point of observation.

The following are practical exemplifications of a range:

1. The line defined by the side of a building or by a fence may be extended visually to its intersection with a survey line: the point of intersection

thus determined is said to be in range with the side of the building or with the fence.

2. In hydrographic surveying, a range formed by two shore objects, if suitably located, aids in keeping a boat moving in a straight line; the line defined by the range.

3. In navigation, specially constructed aids mark ranges defining channels which are to be followed by vessels and keep them clear of dangers. Such ranges are often permanently marked by suitably lighted structures which are given identifying names, as: Honolulu Channel Front Light; Honolulu Channel Rear Light.

4. Boundary lines across water areas and boundary corners in water areas where permanent marks cannot be established, are sometimes defined by intersection of range lines or by a range line and distance from a mark, the range lines being marked by permanent *monuments* on the land.

range (United States public-land surveys).*—Any series of contiguous *townships* situated north and south of each other; also *sections* similarly situated within a *township*.

Ranges of townships are numbered consecutively east and west from a *principal meridian:* thus "range 3 east" indicates the third *range* or row of *townships* to the east from a *principal meridian.* The word *range* is used in conjunction with the appropriate *township* to indicate the *coordinates* of a particular *township* with reference to the *initial point;* thus "township 14 north, range 3 east" indicates the particular *township* which is the 14th *township* north of the *base line* and the 3rd *township* east of the *principal meridian.*

range finder.—An instrument for finding the distance from a single point of observation to other points at which no instruments are placed. See *tachymeter.*

In general, a range finder employs a very short *base line,* of fixed length, which is part of the instrument, and is utilized according to the principle of *triangulation.* The *precision* of the optical and other parts of the instrument is very great, but because of the small magnitude of the *angle* of intersection of the lines of sight at the object observed on, the distances obtained are not of a high order of *precision.*

range line (United States public-land surveys).*—An exterior boundary of a *township* extending in a north-south direction.

Réaumur scale.—A temperature scale in which 0° marks the freezing point and 80° the boiling point of water at 760 mm. barometric pressure.

In some of the earliest *geodetic* work, the Réaumur scale was used in stating the temperature of base-line measuring apparatus (*base apparatus*).

receiver (pendulum).—A heavy cast-metal box within which the *pendulum* is suspended and some auxiliary equipment placed when making observations for the *intensity of gravity.*

The receiver used with the *Mendenhall pendulum* is a heavy brass casting which can be made airtight and exhausted of air, mounted on foot screws for leveling, and provided with appliances for manipulating the *pendulums* and auxiliary equipment which are placed in it. It is provided with glass windows through which observations are made.

reciprocal of the flattening (of the earth).—See under *flattening of the earth.*

reconnaissance map.—See under *map.*

reconnaissance sketch.*—A drawing which resembles a *reconnaissance map* but is lacking in some *map* element.

reconnaissance survey.—See under *survey.*

recovery of station.—A survey *station* is considered as recovered when its mark (*monument*) is identified as authentic and proved to be occupying its original site.

The recovery of station is tested by checking the measurements for distance and *azimuth* (or *bearing*) from the station to a *reference mark. Witness marks* are aids to the recovery, but afford only secondary evidence of the position of the recovered mark. Sometimes, exact recovery requires that the original survey connections between the *station* and at least two adjacent *stations* of the same survey and class be tested and found unchanged.

rectangular coordinates.—See under *coordinates.*

rectangular polyconic map projection.—See under *map projection.*

rectifying latitude.—See under *latitude.*

reduced (parametric) latitude.—See under *latitude: parametric.*

reduction to center.—See under *center.*

reference mark.—A supplementary mark of permanent character close to a survey *station,* to which it is related by accurately measured distance and *azimuth* (or *bearing*).

The connection between a survey *station* and its reference mark(s) should be of sufficient *precision* and *accuracy* to permit the reestablishment of the *station* on the ground should its marks be destroyed, or the use of the reference mark in place of the survey *station* in the extension of surveys. Reference marks are used to define positions of boundary corners which may be so situated (as in water) that permanent marks cannot be placed exactly at the corners. See *corner: witness corner* (*United States public-land surveys*).

referencing.—The process of measuring the horizontal distances and directions (*azimuths* or *bearings*) from a survey *station* to nearby *landmarks, reference marks,* and other objects which may be used in the *recovery of the station.*

refraction: angle of.—See under *refraction of light.*

refraction: angle of incidence.—See under *refraction of light.*

refraction: astronomical.—The refraction by the earth's atmosphere of light from a source outside the atmosphere.

Light from a celestial body, as a star or planet, passes entirely through the atmosphere in reaching the earth, and follows a curved path which is concave to the surface of the earth. The *angle* between the direction of a ray where it enters the atmosphere and its direction at the point of observation is the astronomical refraction of the ray, or simply its refraction. It is also called celestial refraction. Its magnitude is greatest when the observed body is near the *horizon;* with slight irregularities, it decreases to a minimum near the *zenith,* being zero when the path of the ray is *normal* to the surfaces of the atmospheric layers. Astronomical refraction must be considered in many problems of astronomy, *surveying,* and navigation. See *refraction of light.*

refraction: atmospheric.—The *refraction of light* passing through the earth's atmosphere.

Atmospheric refraction includes both *astronomical refraction* and *terrestrial refraction.*

refraction: coefficient of.—The ratio of the *refraction angle* at the point of observation to the angle at the center of the earth subtended by the *arc* connecting the point of observation and the observed point.

refraction: index of.—The ratio of the sine of the *angle of incidence* to the sine of the *angle of refraction.*

When a ray of light passes from a vacuum into some medium or from some medium into a vacuum, the index of refraction is the absolute index of the medium. When a ray of light passes from one medium into another medium, the index is the relative index of those media. The index of refraction is slightly different for different wave lengths. This deviation, by refraction, of different wave lengths, is known as dispersion and, for any given medium, the amount of the deviation is a measure of the dispersive power of the medium. *Chromatic aberration* is overcome over a moderate range of wave lengths by using a composite lens (*achromatic lens*) composed of elements having different dispersive powers. A lens made achromatic for visual observation is not strictly achromatic for photographic work.

refraction: terrestrial.—The refraction by the earth's atmosphere of light from a terrestrial source.

The path of light from a terrestrial source is usually not far from horizontal; it passes through only the lower strata of the atmosphere, and suffers refraction throughout its entire length. The *angle of refraction*, or simply the refraction, of a survey line is the *angle* at the point of observation between the true *direction* of the observed object and the *direction* as shown by light coming from it (*direction* of object as seen).

Terrestrial refraction must be considered in many problems of *surveying*, and enters into some problems of astronomy and navigation which involve observations on terrestrial objects. Because the arrangement of the air strata is not exactly symmetrical in form and density, the path of a ray of light through the atmosphere is not a smooth curve in a *vertical plane*. Its curvature is greatest, however, in or close to a *vertical plane*, where its magnitude is of considerable importance in observations which are referred to the *zenith* or to the plane of the *horizon*, as are some *vertical angles* and *spirit levels*. Its effect is usually to make the apparent altitude of an object greater than its true *altitude*, though under special atmospheric conditions, this effect may be reversed.

In *triangulation*, a station which is normally just below the *apparent horizon* may, under certain conditions of the atmosphere and because of refraction, become visible for a short period of time and be observable. A line which can be observed over only with the aid of refraction is termed a *refraction line*. Refraction in a *direction* which is approximately horizontal is termed lateral refraction, and under some conditions can be of such magnitude as to seriously affect observed values of *horizontal* directions. A careful *reconnaissance* is required, especially for city surveys, to prevent the inclusion of lines so affected in a survey net. In some publications of the U. S. Coast and Geodetic Survey, terrestrial refraction is considered under the title of *atmospheric refraction*.

refraction angle.—That portion of an observed *zenith distance* which is due to the effect of *atmospheric refraction*.

The refraction angle may be taken as the difference between the observed and geometrically determined values of the *zenith distance*.

refraction line.—A line of sight to a *survey signal* which becomes visible only by the effect of *atmospheric refraction*.

Refraction lines are often over bodies of water, the observed signal normally being below the *apparent horizon*, but becoming visible at the time of greatest refraction during the day, when it appears to rise out of the water, disappearing back into the water as the refraction decreases.

refraction of light.—The change in direction of a ray of light passing obliquely from one medium into another, its speed in the two media being different.

The ray of light, before being refracted, is termed the incident ray; after refraction, the refracted ray. The *angle* between the incident ray and the *normal* to the surface separating the media at the point of refraction and on the same side of that surface as the incident ray is the angle of incidence; the corresponding *angle* between refracted ray and *normal* is the angle of refraction.

Refraction of light by the earth's atmosphere is termed *atmospheric refraction*, and is divided into two classes; *astronomical refraction*, also termed celestial refraction, and *terrestrial refraction*. Refraction of light must be considered in many problems of astronomy, *surveying*, and navigation. See *refraction: astronomical refraction; terrestrial refraction*.

relative position.—See under *position*.

relief.—See under *topography* (*or relief*).

repeating theodolite.—See under *theodolite*.

repetition of angles.—The accumulation of a series of measures of the same *angle* on the horizontal circle of a *repeating theodolite* or surveyor's *transit*, in making which the final reading of one measure is used as the initial setting of the next measure of the *angle*. The observed value of the *angle* is obtained by dividing the total *arc* passed over by the number of observations.

representative fraction.—See under *map scale: fractional*.

Repsold base-line measuring apparatus.—See under *base apparatus*.

resection.—The determination of the horizontal position of a *survey station* by observed *directions* from the station to points of known position.

The most usual problem in resection is the determination of a point of observation by measuring two *angles* between three fixed points; this is the *three-point problem*, which is solved by computation (in *triangulation*), by mechanical means (with a *three-arm protractor* in hydrographic work), or graphically (on a plane-table survey). Its solution gives what is often termed a *fix*, a position for the point of observation. As employed in photogrammetry, resection refers to position determination from measurements on photographs.

residual error.—See under *error*.

resurvey.—See under *survey: resurvey*.

reticle (reticule).—A system of wires, hairs, threads, etched lines, or the like, placed *normal* to the axis of a telescope at its principal *focus*, by means of which the telescope is sighted on a star, signal, or target, or by means of which appropriate readings are made on some scale, such as a leveling or stadia rod.

reticle ring.—The ring across which the system of wires, hairs, threads, or the like of a *reticle* are stretched; or the ring which supports the glass *diaphragm* in case the reticle is a system of lines etched on glass.

reversible pendulum.—See under *pendulum*.

reversing point, micrometer screw (geodetic level).—That setting of the micrometer head at which the bubble remains in the center of the level vial, when the instrument is level and is *rotated* about its axis.

On some geodetic levels, a horizontal line on the micrometer head index piece indicates the position of the reversing point, within one turn of the micrometer screw, when the top of the micrometer-screw head is made level with it.

revolution.—Astronomy. A turning of a body about an exterior point or axis. See *rotation.* Mathematics. A turning of a geometrical figure about an axis.

We say that the earth *rotates* on its axis and revolves around the sun. However, in usage, such clear distinction between rotate and revolve is not always made with complete consistency. For example, in geodetic surveying, a *spheroid* adopted to represent the earth is termed an *ellipsoid* of revolution, though according to exact terminology it is an *ellipsoid* developed by the *rotation* of an ellipse around its minor axis. It may be desirable to disregard custom and speak of such a figure as an *ellipsoid* of rotation. The expression, *spheroid* of revolution, is of such general use that its use is continued in this publication.

rhumb line.*—A line which crosses successive *meridians* at a constant angle.

The *Mercator* is the only *map projection* on which a rhumb line is represented by a *straight line.* Other names for rhumb line are: loxodrome, loxodromic curve, equiangular spiral, and *Mercator track.*

right ascension.—The *angle* between the plane of the *hour circle* passing through a celestial body and the plane of the *hour circle* passing through the *vernal equinox.*

Right ascension may be measured by the *angle* at the celestial pole between the tangents to the *hour circles* of the body and of the *vernal equinox,* or by the *arc* of the *equator* intercepted by those *hour circles.* Right ascension is measured eastward from the *vernal equinox* through 24 hours (360°). It corresponds to *longitude* on the earth, and with *declination* forms a pair of *coordinates* which defines the position of a body on the *celestial sphere.*

right bank.—See under *bank of stream.*

river bed.—See under *bed of stream.*

river crossing (leveling).—Carrying a *line of levels* across a stream or other body of water, when no suitable bridge is available and the width of the body of water is greater than the maximum allowable length of sight for the leveling, requires a special series of observations which taken collectively is known as a river crossing.

rod correction (leveling).—See under *correction.*

rotation.—Astronomy. A turning of a body about a self-contained axis. See *revolution.* Surveying. A turning of an instrument or part of an instrument about an axis.

The earth rotates on its axis. The *alidade* of a *theodolite* rotates about a vertical axis.

run of micrometer.—See under *micrometer.*

running (leveling).—A continuous series of measured differences of elevation, made *set-up* by set-up in one direction along a *section* of a *line of levels,* which results in a measurement of the difference of elevation between the *bench marks* or other points, either temporary or permanent, at the ends of the section.

rural delivery map.—See under *map.*

S

sag correction, tape.—See under *tape.*

St. George Island datum.—See under *datum.*

St. Hilaire Method (Method of Marcq St. Hilaire).—An adaptation of the *Sumner line* method of position determination which employs assumed *altitudes* (*vertical angles*) in the computation of an astronomical position, and applies a simple *correction* for the difference between the observed and assumed values of the *altitudes.*

This method simplifies the usual method of computing a position from *Sumner lines;* it is especially effective and simple near the geographic poles. It was invented in 1874 by Marcq de St. Hilaire, a French naval officer.

St. Michael datum.—See under *datum.*

St. Paul Island datum.—See under *datum.*

Sanson-Flamsteed map projection.—See under *map projection: sinusoidal.*

scale: equivalent map.—See under *map scale.*

scale: fractional map.—See under *map scale.*

scale: graphic (or bar) map.—See under *map scale.*

scale: map.—See under *map scale.*

scale factor.—A multiplier for reducing a distance obtained from a *map* by computation or scaling to the actual distance on the *datum* of the *map.* Also, in the *State coordinate systems,* scale factors are applied to *geodetic* lengths to obtain *grid lengths,* or to *grid lengths* to obtain *geodetic* lengths; both are lengths on a *sea-level datum,* but the *grid lengths* are affected by the distortion of the *map projection.*

school and bus route map.—See under *map.*

Schott base-line measuring apparatus.—See under *base apparatus.*

sea level.—In general, the surface of the sea used as a reference for *elevation.* In *surveying* and mapping, a curtailed form of *mean sea level.*

In *surveying* and mapping, the use of sea level should be avoided; but if used, it should be with the meaning of *mean sea level.*

sea level datum.—A determination of *mean sea level* that has been adopted as a standard *datum* for heights. The sea level is subject to some variations from year to year, but as the permanency of any datum is of prime importance in engineering work, a sea level datum after adoption should in general be maintained indefinitely even though differing slightly from later determinations of mean sea level based upon longer series of observations.

The sea level datum now used for the U. S. Coast and Geodetic Survey level net is officially known as the "Sea Level Datum of 1929," the year referring to the last general adjustment of the net. The datum itself may be considered as an adjustment based upon tide observations taken at various tide stations along the coasts of the United States over a number of years. See also under *mean sea level.*

sea mile.—See under *mile: nautical.*

secant method (United States public-land surveys).*—A method of determination of the *parallel* of *latitude* for the survey of a *base line* or *standard parallel* by *offsets* from a *great circle line* which cuts the *parallel* at the first and fifth mile corners of the *township* boundary.

The secant method is a modification of the *tangent method,* so arranged that minimum *offsets* need be made from the projected *great circle line* to the *parallel;* at the first and fifth mile stations on the secant the *offsets* are zero; between those stations the *offsets* are measured to the south; before and after those stations the *offsets* are measured to the north.

secondary triangulation.—See under *triangulation.*

second-order bench mark.—See under *bench mark.*

second-order control surveys.—See under *second-order work (control surveys).*

second-order leveling.—See under *leveling.*

second-order traverse.—See under *traverse.*

second-order triangulation.—See under *triangulation.*

second-order work (control surveys).—The designation given survey work of next-to-the-highest order of *accuracy* and *precision.* See *traverse; triangulation;* and *leveling.*

section (leveling).—That portion of a *line of levels* which is recorded and abstracted as a unit.

A section always begins and ends on a *bench mark,* either temporary or permanent, when in the main *line of levels* or on a *spur line of levels.* In the case of a *spur* to a point the *elevation* of which is determined by means of an *extra foresight,* the section must begin on a temporary or permanent *bench mark* and end on the point on which the *leveling rod* was held when the *extra foresight* was taken.

section (United States public-land surveys).*—The unit of subdivision of a *township;* normally a quadrangle 1 mile square, with boundaries conforming to *meridians* and *parallels* within established limits, and containing 640 acres as near as may be.

A normal *township* is divided into 36 sections by lines 1 mile apart measured from the southern and eastern boundaries; any excess or deficiency in measurement is placed in the northern *tier* or western *range* of sections. The sections within a normal *township* are numbered consecutively commencing with number 1 in the northeast section and progressing west and east alternately with progressive numbers in the *tiers,* to number 36 in the southeast section.

section: fractional (United States public-land surveys).*—A *section* containing appreciably less than 640 acres, usually due to invasion by a segregated body of water, or by other land which cannot properly be surveyed or disposed of as part of that *section.*

Sections are also frequently rendered fractional in closing the *surveys* on the north and west boundaries of the *township,* for the reason that deficiencies in measurement caused by *error* of *survey* or *convergence of meridians* are placed in the half mile closing against these *township* boundaries.

section: half (United States public-land surveys).*—One-half of a normal *section,* formed by dividing a *section* into two parts by a line connecting opposite *quarter-section corners,* and containing 320 acres as near as may be.

The half section is a unit of description of the *public lands;* thus the "east half, section 10" is the legal description of that portion of *section* 10 of a given *township* lying east of the north-south *center line* of the *section.*

section: quarter (United States public-land surveys).*—One-fourth of a normal *section,* formed by dividing a *section* into four parts by lines connecting the opposite *quarter-section corners,* and containing 160 acres as near as may be.

The quarter section is a unit of description of the *public lands;* thus the "northeast quarter, section 10" is the legal description of that portion of section 10 of a given *township* lying east of the north-south *center line* and north of the east-west *center line* of that *section.*

section: quarter-quarter (United States public-land surveys).*—One-sixteenth of a normal *section,* formed by dividing a *quarter section* into four parts by lines connecting the midpoints of opposite sides, and containing 40 acres as near as may be.

The quarter-quarter section is a unit of description of the *public lands;* thus the "northeast quarter of the northeast quarter, section 10" is the legal description for that portion of section 10 of a given *township* lying east of the north-south *center line* and north of the east-west *center line* of the northeast quarter of that *section.*

sector.—Mathematics. A geometrical figure bounded by an *arc* and two radii. Surveying. An instrument composed of a graduated *arc* equipped with a sighting device (*alidade*).

In *surveying,* the sector and the *quadrant* were the immediate predecessors of the *theodolite,* both being mentioned in reports of early *geodetic* surveys in connection with the measurement of horizontal angles. These instruments were constructed with *arcs* having radii several feet in length. Combined with other words, sector is used to designate certain *map* features, as red sector; and special types of instruments, as *zenith sector; track sector.*

sector: track.—See under *track sector.*

sector: zenith.—An astronomical instrument for measuring *zenith distances,* in which a plumb line is read against a short vertical *arc.* Also, a modern form of such an instrument, employing *spirit levels* and an *ocular micrometer.*

In its early form, before the invention of the *telescope,* the zenith sector consisted of a *quadrant* with plumb-line control. With the coming of the *telescope,* zenith sectors used in astronomical work in connection with surveying operations employed *telescopes* up to five or six feet in length with short vertical *arcs,* the *vertical angle* being read by means of a plumb line suspended from the horizontal axis of the instrument.

A later form of zenith sector, employing *spirit levels* and an *ocular micrometer,* is a *precision instrument.* These instruments were used in measuring *zenith distances* and differences of *zenith distances* of stars close to the *zenith.* In making determinations of *astronomic latitude,* the zenith sector has been superseded by the *zenith telescope.*

secular parallax.—See under *parallax: diurnal parallax.*

selenotrope.—An instrument similar to the *heliotrope,* but adapted for reflecting moonlight for signal purposes.

The selenotrope differs from the heliotrope only in the greater size of the mirror used, being operated in exactly the same way. In tests made in 1883 and 1887, selenotropes with mirrors of the sizes stated furnished satisfactory lights on which to observe at the following distances: 22 miles, 6- by 6-inch mirror; 48 miles, 6- by 8-inch mirror; and 70 miles, 8- by 10-inch mirror.

set-back.—The horizontal distance from the *fiducial mark* on the front end of a tape or part of tape which is in use at the time back to the point on the ground mark or monument to which the particular measure is being made.

A set-back is usually a very small distance in base-line measures where tape supports in the form of stakes are placed in advance of the measure; if the distance between the stakes is too small, the tape will over-run the stakes, and set-backs must be measured. If portable supports, such as bucks, are used, there will seldom be need for measuring set-backs. Set-backs are minus corrections to tape distances. In the work of the U. S. Coast and Geodetic Survey, the use of set-backs is avoided. See *set-up.*

set-up.—The horizontal distance from the *fiducial mark* on the front end of a tape or part of tape which is in use at the time, measured in a forward direction to the point on the ground mark or *monument* to which the particular measure is being made. Also, a surveying instrument in position at a point of observation.

A set-up is usually a very small distance in base-line measures where tape supports in the form of stakes are placed in advance of the measures; if the distance between the stakes is too great, the tape will not reach from stake to stake, and set-ups must be measured. If portable supports, such as bucks, are used, there will seldom be need for measuring set-ups. Set-ups are plus *corrections* to tape distances. See *set-back.*

set-up (leveling).—The actual physical placing of the *leveling instrument* over an *instrument station.*

The terms *instrument station* and set-up, especially in leveling, are often used interchangeably with little loss of accuracy of statement. However, if any distinction is to be made, set-up is considered to be the instrument when mounted or set up over the *instrument station* or point on the ground which is in the vertical axis of rotation of the instrument.

sextant.—A hand instrument for measuring the *angle* between two objects in the plane defined by the two objects and the point of observation, and based on the optical principle that if a ray of light suffers two successive reflections in the same plane by plane mirrors, the *angle* between the first and last directions of the ray will be twice the *angle* between the plane mirrors.

The sextant has a graduated arc of 60°, from which it derives its name. Each degree division represents a 2° *angle* between the first and last directions of the ray of light, and is so marked: the 60° arc is marked 120°. The last reflection of the ray is made parallel with the direction of the second object, hence the *angle* between the two objects, one seen by double reflection and the other viewed directly, is registered on the sextant. The instrument is used in navigation for measuring *elevations* of celestial objects, in hydrographic surveying for measuring *horizontal* angles at a point in a moving boat between shore objects, and wherever instability of support makes it impossible to use a *theodolite* or *transit.* The sextant has been in use since around 1730. It is capable of use as a *precision* instrument.

sextant: bubble sextant.—A *sextant* in which the bubble of a *spirit level* serves as the *horizon.*

A simple form of bubble sextant was designed by R. E. Byrd and used by him in aerial navigation, on expeditions to the North and South Poles and on other arctic and antarctic expeditions. It has a *spirit level* with a circular bubble attached to the *sextant* quite close to the horizon glass; the *elevation* of a celestial object is measured by bringing its image into contact with the image of the bubble as seen in the horizon glass.

ship-shore triangulation.—See *triangulation: ship-shore.*

shoran.—A pulse-type electronic ranging system originally designed for the positioning of bombing aircraft and later adapted for use in aerial photography, geophysical exploration, hydrography, and long-range geodetic surveying.

Fundamentally, the system consists of a mobile transmitter-receiver-indicator unit and a fixed receiver-transmitter unit (transponder). Pulses are sent from the mobile transmitter and returned to the originating point by the transponder. The indicator measures the time interval required for travel of a pulse between stations and converts this information into distance to the nearest thousandth of a mile. Shoran range is approximately limited to direct-path transmission as a consequence of the carrier frequency used (200–300 megacycles).

shore.—The land which is covered and uncovered by the rise and fall of the normal *tide.*

It is the strip of land between the *mean high-water* and *mean low-water lines.* In its strictest use, the term applies only to land along tidal waters.

shore line.—The land-side *boundary line* of the *shore;* the *mean high-water line.*

Along a river, the shore line is the line along the river bank which is washed by the water without overflowing it.

shore of stream.—The area between the *bank* of a stream and its *low-water line.*

side equation.—See under *equation.*

side shot.—A reading or measurement from a survey *station* to locate a point which is not intended to be used as a base for the extension of the *survey.*

A side shot is usually made for the purpose of determining the *position* of some object which is to be shown on the *map.*

sidereal day.—See under *day.*

sidereal focus.—See under *focus.*

sidereal month.—See under *month.*

sidereal time.—See under *time.*

sidereal time: Greenwich.—See under *time.*

sidereal time: local.—See under *time.*

sidereal year.—See under *year.*

signal: longitude.—A sign indicating a time event, observable at different stations, and used in comparing local times of those stations, and determining the difference of their *longitudes.* See *longitude* (various methods).

signal: survey.—A natural or artificial object or structure whose horizontal and sometimes vertical position is obtained by *surveying* methods.

Signals are given special designations according to the kind of *survey* in which they are determined, or which they may later serve.

signal: triangulation.—A rigid structure erected over or close to a *triangulation* station and used for supporting instrument and observer, or target, or both instrument and observer and target, in a *triangulation* survey. Also any object, natural or artificial, whose position is obtained in a *triangulation* survey.

The term may be applied to a structure whose position is determined by *triangulation,* but whose primary purpose is to serve later in a *hydrographic* or *topographic survey,* when it may become known as a hydrographic or topographic signal.

simple pendulum.—See under *pendulum.*

simultaneous double line.—See under *level line: simultaneous level line.*

simultaneous level line.—See under *level line.*

sinusoidal map projection.—See under *map projection.*

siphon barometer.—See under *barometer.*

slope stake.—A stake set on the line where a finished side slope of an excavation (cut) or embankment meets the original ground surface.

small scale.—See under *map scale: fractional.*

solar attachment.—An auxiliary instrument which may be attached to an engineer's *transit,* permitting its use as a *solar compass.*

solar compass.—See under *compass.*

solar day.—See under *day.*

solar focus.—See under *focus: sidereal focus.*

solar parallax.—See under *parallax.*

solar time.—See under *time: apparent solar time; mean solar time.*

solar transit.—An engineer's *transit* designed for use in place of a *solar compass.*

solenoid.—A coil of wire, often helical in form, which becomes an electromagnet when an electric current is passed through it.

When tests show an *invar pendulum* to be magnetized beyond a prescribed limit, a solenoid is used to demagnetize it. The standard equipment for a party engaged in determinations of *gravity* includes a suitably mounted solenoid, with compass needle, battery, and control switches.

solid angle.—See under *angle.*

solstice.—A point on the *ecliptic* midway between (90° from) the *equinoxes.* See *solstice: summer; solstice: winter.*

solstice: summer.—The point on the *ecliptic,* north of the *equator* and midway between (90° from) the *equinoxes.*

The summer solstice is the point where the sun attains its greatest north *declination,* a position which marks the beginning of the season of summer.

solstice: winter.—The point on the *ecliptic,* south of the *equator* and midway between (90° from) the *equinoxes.*

The winter solstice is the point where the sun attains its greatest south *declination,* a position which marks the beginning of the season of winter.

solstitial colure.—See under *colure.*

southing.—See under *latitude: difference of latitude (plane surveying).*

speaking rod.—See under *leveling rod (general).*

special-purpose map.—See under *map.*

spherical aberration.—See under *aberration of light (optics).*

spherical angle.—See under *angle.*

spherical coordinates.—See under *coordinates.*

Spherical excess.—The amount by which the sum of the three *angles* of a triangle on a sphere exceeds 180°.

In *geodetic* work, in the computation of triangles, the difference between *spherical angles* and *spheroidal angles* is generally neglected, *spherical angles* are used, and *Legendre's Theorem* applied to the distribution of the spherical excess. That is, approximately one-third of the spherical excess of a given spherical triangle is subtracted from each *angle* of the triangle.

spheroid.—In general, any figure differing but little from a sphere. In *geodesy,* a mathematical figure closely approaching the *geoid* in form and size, and used as a surface of reference for *geodetic surveys.*

In *geodetic surveying,* the spheroid is usually an ellipsoid of revolution, but there is some disadvantage in using the term spheroid as synonomous with such a figure. Until the adoption of the International Gravity Formula (Stockholm, 1930), none of the *gravity* formulas in general use corresponded to an exact ellipsoid of revolution. Helmert's formula of 1917 and some later ones included a term that implied a spheroid with an elliptical *equator,* and *meridians* which were not exact ellipses. Ellipsoids of three unequal axes and spheroids with non-elliptical *meridians* have been proposed by geodesists to secure better representation of observed *deflections of the vertical.* The mathematical difficulties of fitting *triangulation* to any such surface have firmly established the use of an ellipsoid of revolution for that purpose. A spheroid which corresponds to an ellipsoid of revolution may be defined by stating the lengths of the semiaxes (a and b) of the generating ellipse, or the length of one of the semiaxes and the *flattening* (*ellipticity*) $[(a-b)/a]$ of the ellipse.

A spheroid serves as a base for the mathematical reduction (*correlation* and *coordination*) of surveying observations where account must be taken of the curvature of the earth's surface. It is such a figure as would be produced by an ellipse revolving around its minor axis, that is, an oblate ellipsoid. A particular spheroid may be defined by stating the lengths of its semiaxes, a and b, or the length of one semiaxis and the *flattening* (ellipticity), $(a-b)/a$. In the *geodetic* work of this country, the following spheroids have been used: the Bessel spheroid of 1841, for which $a=6{,}377{,}397.2$ meters and $b=6{,}356{,}079.0$ meters; the Clarke spheroid of 1866, adopted in 1880, and in continuous use since that time. For it, $a=6{,}378{,}206.4$ meters; $b=6{,}356{,}583.8$ meters.

Of interest also is the Hayford spheroid, based upon observations over this entire country, in computing which account was taken of the local *deflections of the vertical* by applying corrections for the effects of *topography* and *isostatic compensation.* The Hayford spheroid is defined by $a=6{,}378{,}388$ meters; $b=6{,}356{,}909$ meters. In 1924, the General Assembly of the Section of Geodesy of the International Geodetic and Geophysical Union, meeting in Madrid, adopted the Hayford spheroid as the basis for the International Ellipsoid of Reference, defined as follows: $a=6{,}378{,}388$ meters; *flattening* (ellipticity), $(a-b)/a=1/297$; and by computation, $b=6{,}356{,}911.946$ meters.

While for reasons of expediency, the International Ellipsoid of Reference has not been adopted for survey work in this country, it has considerable scientific value and tables for its use have been computed and published.

spheroid: eccentricity of.—See under *eccentricity of spheroid.*

spheroid: ellipticity of.—See under *flattening of the earth.*

spheroid: lines on a.—Any direct line between two positions on a *spheroid,* represented by two points on the earth.

Such a line may be one of mathematical definition, or it may result from a direct *survey* between the points on the earth. Eight such lines, connecting two points, A and B, are listed in U. S. Coast and Geodetic Survey Report for 1900, pages 369–370, as follows:

(a) A *normal section line* from A to B.

(b) A *normal section line* from B to A.

(c) A *curve of alignment.*

(d) A *geodetic line.*

(e) A forward straight line starting in the plane of the *normal* through A and through B, and in advancing keeping B constantly sighted.

(f) A line similar to (e) above, but starting in the plane of the *normal* through B and through A, and in advancing keeping A constantly sighted.

(g) A forward and backward sight line over limited distances, starting from A.

(h) A forward and backward sight line over limited distances, starting from B.

(Lines (a), (b), (c), and (d) are defined elsewhere.)

spheroidal angle.—See under *angle.*

spheroidal excess.—The amount by which the sum of the three *angles* of a triangle on a *spheroid* exceeds 180°.

In *geodetic* work, *spherical angles* are used instead of *spheroidal angles,* the difference between such *angles* being quite small for the largest triangles, and considered negligible for ordinary triangulation work.

spiral curve.—See under *curve.*

spirit level.—See under *level.*

spirit level axis.—See under *level axis.*

spirit level, chambered.—See under *level.*

spirit leveling.—See under *leveling*.

spur (leveling).—See under *line of levels*.

spur line of levels.—See under *line of levels*.

stadia.—A graduated rod used in the determination of distance by observing the intercept on the rod subtending a small known *angle* at the point of observation.

In practice, the *angle* is usually defined by two fixed lines in the *reticle* of a *telescope* (*transit* or *telescopic alidade*). The term stadia is also used in connection with *surveys* where distances are determined with a stadia, as, stadia survey, stadia method, stadia distance, etc.; also used to designate parts of instruments used, as, stadia wires. In its strictest use, stadia refers to the graduated rod.

stadia (length).—The plural form of stadium, a Greek measure of length somewhat greater than 600 feet.

stadia constant (leveling).—See under *constant*.

stadia interval (leveling).—See under *interval*.

Stampfer level.—See under *leveling instrument*.

standard.*—An exact value, or concept thereof established by authority, custom, or common consent, to serve as a model or rule in the measurement of quantity, or in the establishment of a practice or procedure.

Standard, as it pertains to any specific term, is considered in the supplementary statement of that term.

Standard (California) astronomical datum of 1885.—See under *datum*.

standard elevation.—See under *elevation*.

standard line (United States public-land surveys).*—Any *base line, standard parallel, principal meridian,* or *guide meridian*.

The term standard line is not in general use.

standard of length.—A physical representation of a linear *unit* that is approved by competent authority.

A standard of length is not independent of temperature, pressure, and other physical conditions to which it is subjected, but is an exact embodiment of the *unit* which it represents only under definite, prescribed conditions. See *meter: International Prototype Meter*.

Standards of length are classified according to the *accuracy* and *precision* of their representation of the given *unit,* and these are prescribed by their intended use and are designated accordingly, as follows:

1. Primary standards. International and national prototype *standards* of the highest possible *accuracy* and *precision*.

2. Secondary standards. Laboratory *standards* that are compared directly with the national *standards*.

3. Reference standards. *Standards* suitable for use in the construction of *precision* apparatus to be used in scientific investigations.

4. Working standards. *Standards* suitable for all ordinary *precision* work, as in college laboratories, the general manufacture of *precision* instruments, and for the use of State and city sealers of weights and measures.

5. Commercial standards. *Standards* satisfying the requirements of local sealers of weights and measures, drafting, machine work, etc.

Standards of length are also classified according to their design: 1. Line standards. A *standard* in which the *unit* of length is defined as the distance between lines or marks on the surface of the *standard,* under prescribed conditions. 2. End standard. A *standard* in which the *unit* of length is defined as the distance between the end surfaces of the *standard,* under prescribed conditions. Also termed a contact standard.

standard parallel (United States public-land surveys).—See under *parallel*.

standard survey.—See under *survey*.

standard time.—See under *time*.

standard topographic map of the United States.—See under *map: Topographic Map of the United States*.

standardization.—The comparison of an instrument or device with a *standard* to determine the value of the instrument or device in terms of an adopted *unit*.

A tape is standardized when the distance between its *fiducial marks* in terms of a *unit* of length is determined by comparing it, under prescribed conditions, with a *standard* which represents that *unit*. See *calibration*. A *pendulum* is standardized by determining its period at a base station at frequent intervals of time, care being taken each time to swing the *pendulum* under as nearly the same conditions as practicable, and correcting the results to the adopted references of temperature, air pressure in the *receiver, amplitude of vibration,* and *flexure*.

standardization.—(Alternate definition.) The determination of the physical characteristics of a gage or measuring device by comparing it with a *standard*.

A gage or measuring device is standardized so that measures made with it may be reported and used in terms of the *unit* which the *standard* exemplifies. The term "standardization" may include the determination of a quantity which is required in reducing the direct results of a standardization to corresponding values under changing conditions. For example, when a *base tape* is standardized, its length is determined at a definite temperature, under prescribed conditions of tension and support. Its use in the field requires also that its *coefficient of thermal expansion* be known.

State base map.—See under *map*.

State coordinate systems.—The *plane-rectangular coordinate* systems established by the U. S. Coast and Geodetic Survey, one for each State in the Union, for use in defining *positions* of *geodetic* stations in terms of *plane-rectangular* (x and y) *coordinates*.

Each State is covered by one or more zones, over each of which is placed a *grid* imposed upon a *conformal map projection*. The relationship between the *grid* and the *map projection* is established by mathematical analysis. Zones of limited east-west dimension and indefinite north-south extent have the *transverse Mercator map projection* as the base for the State coordinate system; while zones for which the above order of magnitude is reversed use the *Lambert conformal conic map projection* with two *standard parallels*. For a zone having a width of 158 *statute miles,* the greatest departure from exact *scale* (scale error) is 1 part in 10,000. Only *adjusted positions* on the *North American datum of 1927* may be properly transformed into *plane coordinates* on a State system. All such *geodetic positions* which are determined by the U. S. Coast and Geodetic Survey are transformed into State *plane-rectangular coordinates* on the proper *grid,* and are distributed by that Bureau with the *geodetic positions*. State *plane coordinates* are extensively used in recording *land surveys,* and in twenty-two States such use has received approval by legislative enactment.

State map.—See under *map*.

static map.—See under *map*.

station.—A definite point on the earth whose location has been determined by *surveying* methods. A point on a *traverse* over which an instrument is placed (a *set-up*). Also, on a *traverse*, a length of 100 feet measured on a given line, broken, straight, or curved.

A station may or may not be marked on the ground. A station is usually defined by the addition of a term which describes its origin or purpose, such as *triangulation station*, topographic station, magnetic station, etc. A station is often marked on the ground by a *monument* of special construction, or by a natural or artificial structure.

station: instrument (leveling).—The point over which a *leveling instrument* is placed for the purpose of taking a *backsight*, a *foresight*, and such *extra foresights* as may be necessary from that instrument station. See, also, *set-up*.

Except in rare instances, the instrument stations in a *line of levels* are not marked points such as traverse *stations*, triangulation *stations*, etc.

station: intersection.—An object whose horizontal *position* is determined by observations from other survey stations, no observations being made at the object itself.

Where the object is observed from only two *stations*, the position is termed a "no check position," as there is no proof that such observations are free from *blunders*. Intersection stations are either objects which it would be difficult to occupy with an instrument, or survey signals whose positions can be determined with sufficient *accuracy* without being occupied.

station: principal.—A *station* through which basic data are carried in the extension of a survey system.

Also called a main-scheme station, a principal *station* serves primarily for the continued extension of a *survey*. This requires a higher order of *accuracy* and *precision* in its determination than if its purpose were limited to the control of local surveys or the establishment of *supplementary stations*.

station: subsidiary.—A *station* established to overcome some local obstacle to the progress of a *survey*, and not to determine position data for the *station* point.

The term subsidiary station is usually applied to *A-stations* of a *traverse survey*. Subsidiary stations are usually temporary in character and not permanently marked. If serving the additional purpose of supplying control for a local *survey*, such a *station* may be permanently marked and it is then a *supplementary station*.

station: supplementary.—An auxiliary survey *station*, established to increase the number of control *stations* in a given area, or to place a *station* in a desired location where it is impracticable or unnecessary to establish a *principal station*.

Supplementary stations are permanently marked, and are established with an *accuracy* and *precision* somewhat lower than is required for a *principal station*, since they do not serve as bases from which extensive *surveys* are run. See *station: subsidiary*.

station adjustment.—See under *adjustment*.

station error.—See under *deflection of the plumb line*.

station pointer.—See under *protractor: three-arm protractor*.

statute mile.—See under *mile*.

Stephenson leveling rod.—See under *leveling rod*.

steradian.—See under *angle: solid*.

stereographic horizon projection.—See under *map projection: stereographic map projection*.

stereographic map projection.—See under *map projection*.

stereographic meridional projection.—See under *map projection: stereographic map projection*.

stereographic polar projection.—See under *map projection: stereographic map projection*.

strength of figure (triangulation).—The comparative *precision* of computed lengths in a *triangulation net* as determined by the size of the *angles*, the number of *conditions* to be satisfied, and the distribution of *base lines* and points of *fixed position*.

Strength of figure in *triangulation* is not based on an absolute scale but rather is an expression of relative strength. The number expressing the strength of a *triangulation* figure is really a measure of its weakness, since the number determined by formula increases in size as the strength decreases.

The strength of figure is derived from that portion of the formula for *probable error* of a triangle side, which is independent of the *accuracy* of the observations, as follows:

$$\frac{N_d-N_c}{N_d}\sum\left[\delta_A^2+\delta_A\delta_B+\delta_B^2\right]$$

in which N_d and N_c are the numbers of directions observed and of *conditions* to be satisfied, and δ_A and δ_B are the rates of change of the sines of the *distance angles* A and B, usually expressed by the differences of the logarithms of the sines for a difference of 1″ in the *angles*, the sixth decimal place being the unit place.

By summing up the values obtained by formula for the simple figures composing a *triangulation net*, the strength of figure of the net is obtained. As a *triangulation net* is usually composed of several different systems of simple figures, comparable values of the different systems are obtained, and the strongest route can then be selected through which to carry a computation of length.

Reconnaissance for a proposed *triangulation net* is usually executed under instructions which specify limiting values of strength of figure for the best and second-best chains of triangles between adjacent *base lines*, the sites for stations and for *base lines* being selected accordingly. Where desirable, the length of section may be reduced by the insertion of an additional *base line*, and the numbers representing the strength of figure reduced accordingly.

stride.—The distance a pedestrian moves in taking two steps.

Formerly, the stride and the *pace* were largely synonomous; if there was a difference, it was that the stride was a long *pace*. The above definition conforms to present-day teaching, and satisfies the need for a term expressing the distance moved in taking a double step. Hence, one stride equals two *paces*.

striding level.—See under *level*.

subsidiary station.—See under *station*.

summer solstice.—See under *solstice*.

Sumner line (line of position).—A short portion of a *circle of position* represented as a *straight line*.

The Sumner line was named for Captain Thomas H. Sumner, an American sea captain, who discovered its use in 1843. The St. Hilaire Method is a special adaptation of the use of the Sumner line in navigation.

sun compass.—See under *compass*.

supplement of angle.—See under *angle*.

supplemental posts for survey monuments.—See under *identification posts*.

supplementary bench mark.—See under *bench mark*.

supplementary station.—See under *station*.

survey.—1. The orderly process of determining data relating to any physical or chemical characteristics of the earth. 2. The associated data obtained in a survey (1, above). 3. An organization engaged in making a survey (1, above).

1. The list of orderly processes which may be properly called surveys is long; it may be divided into

classes according to the type of data obtained, the methods and instruments used, the purposes to be served, etc. Examples: *geodetic survey, topographic survey, hydrographic survey, land survey, geologic survey,* geophysical survey, soil survey, *mine survey, engineering survey,* etc.

2. The data obtained in a particular project may be designated by the name of the project, as, "the topographic survey of the District of Columbia."

3. An organization making a survey is often given an official name which includes the word survey; examples, "The United States Geological Survey," "The Massachusetts Geodetic Survey."

survey: cadastral.*—A *survey* relating to *land boundaries* and subdivisions, made to create units suitable for transfer or to define the limitations of title.

Derived from "cadastre," meaning register of the real property of a political subdivision with details of area, ownership, and value, the term cadastral survey is now used to designate the *surveys* of the *public lands* of the United States, including retracement *surveys* for the identification, and *resurveys* for the restoration, of property lines; the term may also be applied properly to corresponding *surveys* outside the *public lands,* although such *surveys* are usually termed *land surveys* through preference.

survey: engineering.*—A *survey* executed for the purpose of obtaining information that is essential for planning an engineering project or development and estimating its cost.

The information obtained may, in part, be recorded in the form of an *engineering map.*

survey: exploratory.*—A *survey* executed for the purpose of obtaining general information concerning areas about which such information was not, theretofore, a matter of record.

The U. S. Geological Survey executes exploratory *surveys* in remote regions of Alaska which are used in the construction of *maps* on *scales* of 8 or more *miles* to an *inch.*

survey: geodetic.—1. A *survey* in which account is taken of the figure and size of the earth. 2. An organization engaged in making geodetic surveys.

a. Geodetic surveys are usually prescribed where the areas or distances involved are so great that results of desired *accuracy* and *precision* can be obtained only by the processes of geodetic surveying.

b. The Massachusetts Geodetic Survey is an example of an organization engaged in making geodetic surveys.

survey: geographic.—A general term, not susceptible of defined limitation, covering a wide range of *surveys* lying between and merging into *exploratory surveys* on the one hand and basic *topographic surveys* on the other.

Geographic surveys usually cover large areas, are based on coordinated control, and are used to record physical and statistical characteristics of the area surveyed.

survey: geologic.—A *survey* or investigation of the character and structure of the earth, of the physical changes which the earth's crust has undergone or is undergoing, and of the causes producing those changes.

survey: geological.—A general term used to designate an organization making *geologic surveys* and investigations.

survey: hydrographic.—A *survey* having for its principal purpose the determination of data relating to bodies of water.

A hydrographic survey may consist of the determination of one or several of the following classes of data: depth of water and configuration of bottom; directions and force of currents; heights and times of tides and water stages; location of fixed objects for *survey* and navigation purposes.

survey: inventory.—A *survey* for the purpose of collecting and correlating engineering data of a particular type (or types) over a given area.

An inventory survey may be recorded on a *base map.*

survey: land.—See under *surveying: land surveying.*

survey: location.—The establishment on the ground of points and lines in positions which have been previously determined by computation or by graphical methods.

The plans for an engineering project (road, canal, etc.) are prepared in the office from *survey* data obtained in the field. These plans form a paper location, and are the basis for the location survey.

survey: mine.—A *survey* to determine the positions and dimensions of underground passages of a mine; also of the natural and artificial features, surface and underground, relating to the mine.

The data include both horizontal and vertical *positions,* lengths, and directions (slopes) of tunnels; topographic and geological characteristics of the particular vicinity; ownership of the land and of the mine; etc.

survey: plane.—See under *surveying: plane surveying.*

survey: preliminary.—The collection of survey data on which to base studies for a proposed project.

A triangulation reconnaissance is a preliminary survey, securing data on which to base plans for the execution of the *triangulation.*

survey: reconnaissance.*—A *preliminary survey.*

A reconnaissance survey is usually executed rapidly and at relatively low cost. The information obtained is recorded, to some extent, in the form of a *reconnaissance map* or *sketch.* The form reconnaissance is preferred to reconnoissance.

survey: resurvey.—A retracing on the ground of the lines of an earlier *survey,* in which all points of the earlier *survey* that are recovered are held fixed and used as a control.

If too few points of the earlier *survey* are recovered to satisfy the control requirements of the resurvey, a new *survey* may be made. A resurvey is related directly to an original *survey,* though several resurveys may interpose between them. The terms original *survey,* resurvey, and new *survey* are of considerable significance in *land surveying.*

survey: standard.—A *survey* which, in *scale, accuracy,* and content, satisfies criteria prescribed for such a *survey* by competent authority.

survey: topographic.—A *survey* which has for its major purpose the determination of the configuration (*relief*) of the surface of the earth (ground), and the location of natural and artificial objects thereon. Also the designation of an organization making such a *survey.*

A topographic survey is usually published as a *topographic map.*

survey: transit-and-stadia.—A *survey* in which *directions,* horizontal and vertical, are observed with a *transit* (engineer's), and distances are measured with a *transit* and *stadia.*

A transit-and-stadia survey is usually processed in the office, thus differing from a *survey* made with *alidade* and plane-table, where the *map* is made in the field as the observations are taken. An exception is found in the *topographic survey* of Baltimore, made in the 1890's, where *transit* and plane-table were used together in the field, and the *map* constructed as the observations were made.

survey net.—1. Horizontal control survey net: arcs of *triangulation,* sometimes with lines of *traverse,* connected together to form a system of loops or circuits extending over an area. Variously spoken of as a triangulation net, traverse net, etc.

2. Vertical control survey net: lines of *spirit leveling* connected together to form a system of loops or circuits extending over an area. Also called a level net. See *control: national control survey nets.*

survey signal.—See under *signal.*

survey traverse.—See under *traverse.*

surveying.—The art of making a *survey.*

surveying: geodetic.—That branch of the art of *surveying* in which account is taken of the figure and size of the earth. Also called geodetic engineering.

In geodetic surveying, prescribed *precision* and *accuracy* of results are obtained through the use of special instruments and field methods, and formulas based on the geometry of a mathematical figure approximating the earth in form and size.

surveying: land.—The determination of boundaries and areas of tracts of land.

Land boundaries are usually defined by ownership, commencing with the earliest owners, and descending through successive ownerships and partitions. Land surveying includes the re-establishment of original boundaries, and the establishment of such new boundaries as may be required in the partition of the land. The term *"cadastral survey"* is sometimes used to designate a land survey, but in this country its use should be restricted to the surveys of the *public lands of the United States.*

surveying: plane.—A branch of the art of *surveying* in which the surface of the earth is considered a plane surface.

In plane surveying, curvature of the earth is neglected and computations are made using the formulas of plane geometry and plane trigonometry. In general, plane surveying is applied to *surveys* of land areas and boundaries (*land surveying*), where the areas are of limited extent or the required *accuracy* so low that *corrections* for the effect of curvature would be negligible as compared with the *errors* of observation. For small areas, precise results may be obtained with plane-surveying methods, but the *accuracy* and *precision* of such results will decrease as the area surveyed increases in size.

surveying: trilinear.—The determination of the position of a point of observation by measuring the *angles* at that point between lines to three points of known position. See under *resection.*

This determination involves the solution of the *three-point problem,* which is accomplished analytically by computation or graphically by the use of chorograph or *station pointer,* such as the *three-arm protractor.*

surveyor's compass.—See under *compass.*

surveys and maps: detailed.—*Surveys* and *maps* which take account of the smaller features and variations of features in the area surveyed.

A detailed *survey* implies a large-scale *map* of a small area, with increased *accuracy* and *precision* in both field and office work.

synodical (ordinary) month.—See under *month.*

systematic error.—See under *error.*

T

tachymeter, tacheometer, tachometer.—A surveying instrument designed for use in the rapid determination of distance, direction, and difference of *elevation* from a single observation, using a short base, which may be an integral part of the instrument.

There are several forms of instruments which might be called tachymeters. 1. An instrument in which the base line for distance determinations is an integral part of the instrument. It is to this type of instrument that the term "tachymeter" is usually applied. The so-called *range finders* with self-contained bases belong to this class, but are usually spoken of as *range finders,* and do not usually afford the means for the determination of elevation. 2. An instrument equipped with *stadia* wires or *gradienter,* the base for distance determination being a graduated rod held at the distant point.

tachymetry; tachometry.—A method of *surveying* for the rapid determination of distance, *direction,* and relative *elevation* of a point with respect to the instrument station, by a single *observation* on a rod or other object at the point.

The stadia method of *surveying* is the best example of tachymetry in this country, but the term tachymetry is little used here. Little used, too, are the associated terms given types of instruments used in this work, namely, *tachymeter* (or *tacheometer, tachometer*), and tacheographometer.

Talcott method, latitude determination.—See under *zenith-telescope method, latitude determination.*

tangency, point of.—See under *curve.*

tangent (surveying).—1. A straight line that touches a given curve at one and only one point, and does not intersect it.

2. That part of a *traverse* or *alignment* included between the *point of tangency* of one curve and the *point of curvature* of the next curve.

3. In the *surveys of the public lands of the United States,* a *great circle line* tangent to a *parallel* of *latitude* at a *township corner.*

tangent distance.—The distance from the *point of intersection* (vertex) of a curve to its *point of tangency* or *point of curvature.*

tangent method (United States public-land surveys).*—A method of determination of the *parallel* of *latitude* for the survey of a *base line* or *standard parallel* by *offsets* from a *great circle line* initiated at an established *township corner* and tangent to the *base line* or *standard parallel* at that corner.

The tangent *great circle* is projected at an angle of 90° from the *meridian* at the *township corner* from which initiated, and proper *offsets* are measured north from the tangent to the *parallel* upon which the *corners* are established.

tangent plane.—A plane that touches a curved surface at one and only one point.

In *geodetic* work, a plane tangent to the *spheroid* at any point is perpendicular to the *normal* at that point. Tangent planes have been used in computing *map projections* for small areas (local systems of *map projections*).

tape: alignment correction.—A *correction* applied to the measured length of a line to allow for the tape not being held exactly in a *vertical plane* containing the line.

Though the *vertical planes* at the two ends of a line which contain the *direction* of the line at those points are not coincident, they are practically so for all *surveying* purposes, and any method of aligning a base between its end points will serve in determining an alignment correction.

tape: base.—See under *base tape.*

tape: grade correction.—A *correction* applied to a distance measured on a slope to reduce it to a horizontal distance between the vertical lines through its end points. Also called slope correction, correction for inclination of tape.

As the vertical lines through the end points of a line are not parallel, the reduction should be such that the length at the average *elevation* will be obtained. In practice this is accomplished by considering each tape length a separate line, and reducing it individually. In *base line* measures, the difference in *elevation* of the ends of the tape are used in computing the grade correction, rather than the *grade* or inclination of the line expressed in angular form. In effect, this treatment applies the grade correction to the nominal length of the tape in determining its effective length in measuring a distance.

tape: invar.—See under *base tape.*

tape: length correction.—The difference between the nominal length of a tape and its effective length under conditions of *standardization.*

The standard length of a tape is usually expressed by a number of whole units (the nominal length) plus or minus a small distance which is the length correction defined above. Provision is also made for determining any changes of length caused by thermal expansion (or contraction) of the tape.

tape: sag correction (catenary correction).—The difference between the effective length of a tape (or part of a tape) when supported continuously throughout its length and when supported at a limited number of independent points.

Base tapes are usually used with 3 or 5 points of support, and hang in curves (catenaries) between adjacent supports. Correction for sag is not required when the method of support in use is the same as was used in the *standardization* of the tape. A *base tape* may also be used supported throughout or with 4 points of support, as on a railway rail.

tape: temperature correction.—The quantity applied to the nominal length of a tape to allow for a change in its effective length due to its being used at a temperature other than that for which its *standard* length is given.

Temperature correction is applied when the temperature of the tape in use is different from the temperature given in a statement of its standard length.

tape: tension correction.—The *correction* applied to the nominal length of a tape to allow for a change in effective length due to its being used at a tension other than that for which its standard length is known.

A tension correction is not required when the tape is used in the field at the tension of *standardization.*

tape corrections.—*Corrections* applied to a distance measured with a tape to eliminate *errors* due to the physical condition of the tape, and to the manner in which it is used.

Tape corrections which are functions of the physical condition of the tape are *length correction, temperature correction,* and *tension correction.* A *correction* which may be required because of the method of using the tape is the *catenary correction* (*correction for sag*). Closely associated with these are *corrections* which depend upon the position of the line on the ground, as actually measured. These include *grade correction,* and *alignment correction,* which are sometimes treated as *corrections* to the tape itself as used. Reduction to a *datum* (such as *mean sea level*) is not considered as a tape correction.

tape stretcher.—A mechanical device which facilitates holding a tape at a prescribed tension and in a prescribed position.

taping.—The operation of measuring a distance on the earth, using a tape or ribbon of metal or other material. See *chaining.*

The term taping is used for all *surveys* except those of the *public lands of the United States;* for those, due to historical and legal reasons, the term *chaining,* and its related term *chainmen,* are preferred. The men who mark the two ends in taping are termed contact men.

target rod.—See under *leveling rod (general).*

telescope.—An optical intrument consisting essentially of two systems of lenses: an objective or object glass which brings rays of light from a distant object to a *focus* within the telescope tube; and an eyepiece or ocular with which the image of the distant object formed by the objective is magnified and examined.

By means of a *reticle* placed in the principal *focus* of a telescope, definite lines of sight are established, and the telescope thereby made into a *precision* instrument for *surveying* and astronomic work. The magnifying power of a telescope depends upon the ratio of the *focal lengths* of the objective and eyepiece lenses.

telescope: achromatic.—See under *achromatic telescope.*

temperature correction (leveling).—See under *correction.*

temperature correction, pendulum.—See under *pendulum.*

temperature correction, tape.—See under *tape.*

template (templet).—A gage or pattern to guide certain work that is to be done.

A template is often a thin sheet of transparent material upon which suitable guide lines are drawn. Examples: the ordinary *protractor* or, in photographic mapping, a transparent celluloid overlay made over a photograph, showing the center and all radial lines from the center through images of control points, as well as (azimuth) lines connecting the center with images of points which show on the photograph and are themselves the centers of other photographs. In obtaining *elevation* readings from *maps* in connection with *topographic* and *isostatic* reductions, templates of celluloid are used. The templates used in connection with *deflection of the vertical* studies have circles and radial lines drawn upon them, so proportioned with reference to *scale of map* and *azimuth* that land *elevations* and ocean depths within each compartment formed by adjacent arcs and radii can be easily averaged and the effect of the mass therein upon a plumb line at the station (center of circles), under various hypotheses, can be computed. The templates used in connection with *gravity* studies are similar to those described above, except that no account is taken of *azimuth,* all compartments bounded by a given pair of circles being of the same size and shape. A given template can be used only on maps of the *scale* and *projection* for which it is constructed. Devised by J. F. Hayford in connection with studies for the figure of the earth and *isostasy,* these templates are known as the Hayford deflection templates and the Hayford gravity templates.

Temple Act.—An Act of the Congress of the United States to adopt a program for the completion of the *Topographic Map of the United States.*

Known as H. R. 4522, 68th Congress, 1st Session, the bill which later (1925) became the Temple Act, was introduced in 1924 by Dr. Henry W. Temple, a

Representative from Pennsylvania. No appropriations were made for carrying out its provisions.

temporary bench mark.—See under *bench mark.*

tension correction, tape.—See under *tape.*

terrain correction (geländereduktion).—The correction for the effect, upon the acceleration of gravity at a point, of the departure of the actual topography from an assumed plateau at the elevation of the point.

The correction has the same sign whether the topography lies above or below the plateau.

terrestrial equator.—See under *equator: astronomic.*

terrestrial meridian.—See under *meridian.*

terrestrial refraction.—See under *refraction.*

tertiary triangulation.—See under *triangulation.*

thalweg.—The line following the lowest part of a valley, whether under water or not.

The intricacy of detail in ordinary *relief* often makes difficult a practical location of a thalweg; in a survey of a political *boundary line* this difficulty may assume considerable weight. A thalweg may also be defined as the line down the center of the main channel of a stream; or as the line of greatest slope, cutting all *contours* at right *angles.*

theodolite.—A *precision surveying* instrument consisting of an *alidade* with *telescope,* mounted on an accurately graduated circle, equipped with necessary levels, and reading devices. Sometimes, the *alidade* carries a graduated *vertical circle.*

There are two general classes of theodolites: *direction theodolites,* often referred to as *direction instruments,* and *repeating theodolites.*

theodolite: astronomical.—See under *alt-azimuth instrument.*

theodolite: direction instrument.—A *theodolite* in which the graduated horizontal circle remains fixed during a series of observations, the *telescope* being pointed on a number of signals or objects in succession, and the *direction* of each read on the circle, usually by means of *micrometer microscopes.*

In measuring *horizontal angles* with a direction instrument, *angles* are not repeated (accumulated) on the circle, but *precision* and *accuracy* are obtained by having the circle of high quality, by using *precision* methods of reading the circle, and by shifting the circle between sets, so that each *direction* is measured on a number of different parts of the circle. Direction instruments are used almost exclusively in *first-* and *second-order triangulation.*

theodolite: Parkhurst.—A *direction theodolite* designed by and named for D. L. Parkhurst, and used on *first-* and *second-order control surveys.*

The distinctive features of the Parkhurst theodolite are its non-binding center, ball-bearing clamp ring, illumination through the central axis, discontinuous conical bearings, illuminated glass micrometer drums, and improved designs for tangent-screw assembly, clamp-block assembly, and micrometer mountings.

theodolite: photo.—An instrument used in terrestrial photogrammetry, and consisting of a combination of *theodolite* and camera, using the same tripod.

In some models, the theodolite and camera can be used separately; in other models, the two are combined in a single instrument.

theodolite: repeating.—A *theodolite* so designed that successive measures of an *angle* may be accumulated on the graduated circle, and a final reading of the circle made which represents the sum of the repetitions.

The observed value of the *angle* is obtained by dividing the total *arc* passed through in making the series of observations by the number of times the *angle* has been observed. The total *arc* passed through may include several complete circuits of the circle, which must be added to the circle reading before making the division. The repeating *theodolite* is also called a repeating instrument. Theoretically, it is an instrument of great *precision,* but in its mechanical operation it does not give as satisfactory results as the *direction instrument.*

theodolite: Wild.—A make of *theodolite* which has the horizontal and *vertical circles* graduated on glass, and read by an arrangement of prisms which brings the images of opposite portions of either of the circles into the field of view of a reading microscope mounted alongside the *telescope.* By mechanical means the graduation marks in the two images are brought into coincidence, and the circle read by means of an auxiliary seconds scale.

The seconds scale is read to single seconds or to a decimal part of a second without moving from the eye end of the *telescope.* A single reading thus obtained is the mean of two readings of diametrically opposite points on the graduated circle and is therefore free from *errors* due to *eccentricity of circle.* The Wild theodolite is well adapted for use in *triangulation* of any order.

theoretical (or external) error.—See under *error.*

thermometric leveling.—See under *leveling.*

third-order leveling.—See under *leveling.*

third-order traverse.—See under *traverse.*

third-order triangulation.—See under *triangulation.*

third-order work.—See under *traverse; triangulation;* and *leveling.*

thread of river, middle.—The line equidistant between the *low-water* lines on the two sides of a river, extending from headland to headland without considering arms, inlets, creeks, and affluents as parts of the river.

thread of stream.—The line equidistant from the edge of the water on the two sides of the stream at the ordinary stage of the water. See under *thread of river, middle.*

three-arm protractor.—See under *protractor.*

three-point problem.—The determination of the horizontal *position* of a point of observation from data comprising two observed *horizontal angles* between three objects of known *position.*

The problem is solved graphically by means of a *three-arm protractor,* and analytically by trigonometrical calculation. See *resection.* In plane-table surveying it is solved graphically by trial and error.

tidal bench mark.—See under *bench mark.*

tidal datum.—See under *datum.*

tideland.—Land along tidal waters that is below *mean high water* and above *mean low water,* that is, the *shore.*

tie.—A survey connection from a point of known *position* to a point whose *position* is desired.

A tie is made to determine the *position* of a supplementary point whose *position* is desired for mapping or reference purposes, or to close a *survey* on a previously determined point. To "tie in" is to make such a connection. The point to which the connection is made is called a "tie point."

tie point.—See under *tie.*

tier (United States public-land surveys).*—Any series of contiguous *townships* situated east and west of each other; also *sections* similarly situated within a *township.*

time.—The measurable aspect of duration.

Time makes use of scales based upon the happening of periodic events, as follows:

1. The *day,* depending upon the *rotation* of the earth.
2. The *month,* depending upon the *revolution* of the moon around the earth.
3. The *year,* depending upon the *revolution* of the earth around the sun.

When one says it is a certain time, one expresses a length on a duration scale measured from an index on that scale.

For example: 4 p. m. local *mean solar time* means that 4 mean solar hours have elapsed since the *mean sun* was on the *meridian* of the observer.

time: apparent.—See under *time: apparent solar time.*

time: apparent solar.—*Time* measured by the apparent diurnal motion of the (true) sun. Also termed true solar time, and often, apparent time.

At any given instant, the apparent solar time is the *hour angle* of the (true) sun. In civil life, apparent solar time is counted from the two branches of the *meridian* through 12 hours; the hours from the lower branch are marked "A. M." (ante meridian); those from the upper branch, "P. M." (post meridian). In astronomic work, before 1925, apparent solar time was counted from the upper branch of the *meridian* through 24 hours (see *astronomical time*); since 1925, the count has been from the lower branch, and the *civil day* has taken the place of the *astronomical day* in astronomical work. Naming the *meridian* of reference is essential to the complete identification of the *time.* For example, 75th meridian apparent solar time; Greenwich apparent solar time; local apparent solar time (for the *meridian* of the observer). Because of variations in the apparent motion of the sun, a clock or watch cannot be adjusted to show apparent solar time. Apparent solar time is *time* determined by observations on the (true) sun. It is the *time* shown by a sun dial. See *time: equation of time.*

time: astronomical.—*Solar time* in a *day* (*astronomical day*) that begins at noon.

Astronomical time may be either *apparent solar time* or *mean solar time.* It is counted from noon in a single series of 24 hours. Astronomical time appears in the American Ephemeris and Nautical Almanac prior to 1925; but in the volumes for 1925 and later, *civil time* is used instead.

time: civil.—*Solar time* in a day (*civil day*) that begins at midnight.

Civil time may be either *apparent solar time* or *mean solar time;* it may be counted in two series of 12 hours each, beginning at midnight, marked "A. M." (ante meridian), and at noon, marked "P. M." (post meridian), or in a single series of 24 hours beginning at midnight.

time: daylight-saving.—A substitute for *standard time,* exactly 1 hour fast on that *time.*

Clocks showing *standard time* are changed to daylight-saving time by moving the hands ahead exactly 1 hour. Until 1942, it was not adopted by the railroads, nor generally throughout the country; and where adopted, it was for use only during the summer months. In 1942, it was adopted by Congress for general use, and unofficially given the name of *war time.* The time in a given time belt is identified by the particular designation of the belt: Eastern Daylight Saving Time; Central Daylight Saving Time; etc.

time: equation of.—The difference in *hour angle* between *apparent solar time* and *mean solar time.*

The sun is sometimes before and sometimes behind the *mean sun* by an amount that ranges from 0 to about 16 minutes of *time.* As the equation of time may be expressed as a *correction* to either *apparent solar time* or to *mean solar time,* its sign must be carefully observed.

Time: Greenwich Civil.—*Mean solar time* for the *Greenwich Meridian,* counted from midnight. Also called *Universal Time* (U. T.).

Greenwich Civil Time (G. C. T.) is a reference used in the American Ephemeris and Nautical Almanac for 1925 and thereafter. It is counted from midnight through 24 hours.

Time: Greenwich Sidereal.—The *sidereal time* for the *Greenwich Meridian.*

time: local apparent.—The *apparent solar time* for the *meridian* of the observer.

time: local mean.—The *mean solar time* for the *meridian* of the observer.

time: local sidereal.—The *sidereal time* for the *meridian* of the observer.

time: mean solar.—*Time* measured by the diurnal motion of a fictitious body, called the mean sun, which is supposed to move uniformly in the *celestial equator,* completing the circuit in one *tropical year.* Often termed simply mean time.

The mean sun may be considered as moving in the *celestial equator* and having a *right ascension* equal to the mean *celestial longitude* of the true sun.

At any given instant, mean solar time is the *hour angle* of the mean sun. In civil life, mean solar time is counted from the two branches of the *meridian* through 12 hours; the hours from the lower branch are marked "A. M." (ante meridian); those from the upper branch, "P. M." (post meridian). In astronomical work, before 1925, mean solar time was counted from the upper branch of the *meridian* through 24 hours (see *astronomical time*); since 1925, the count has been from the lower branch. Naming the *meridian* of reference is essential to the complete identification of the *time.* For example, 75th meridian mean solar time; Greenwich mean solar time; local mean solar time for the *meridian* of the observer. By using the same reference *meridian* over a belt or zone of the earth, watches and clocks are adjusted to show the same mean solar time throughout the area (see *standard time*). The *Greenwich Meridian* is the reference for a world-wide standard of mean solar time, called *Greenwich Civil Time* or *Universal Time.* The mean sun being a fictitious body, mean solar time cannot be determined directly by observation. See *time: equation of time.*

time: sidereal.—*Time* measured by the apparent diurnal rotation of the (true) *vernal equinox.*

At any instant, sidereal time is the *hour angle* of the *vernal equinox.* It is counted from 0 hours, when the *vernal equinox* is on the *meridian,* through 24 hours. Naming the *meridian* of reference is essential to its complete identification. For example, 75th meridian sidereal time; *Greenwich sidereal time; local sidereal time* for the *meridian* of the observer.

On account of small differences between the positions of the true and mean *equinoxes,* sidereal time, like the *sidereal day,* is subject to slight irregularities. These irregularities are absent from (uniform) sidereal time, which is measured by the motion of the mean equinox, and is used in rating clocks of the highest *precision*.

time: solar.—See under *time: apparent solar time; mean solar time.*

time: standard.—*Mean solar time* for a selected *meridian* adopted for use throughout a belt (zone).

In the continental United States, the *meridians* of reference for standard time are 15° (1 hour) apart, and multiples of 15° from the initial *meridian, Greenwich Meridian.* The standard time for each belt is designated by the number of its *meridian,* and also by some name of *geographic* significance: 75th meridian or Eastern Standard Time; 90th meridian or Central Standard Time; 105th meridian or Mountain Standard Time; and 120th meridian or Pacific Standard Time. The standard time meridians for Alaska are 150° and 165° west *longitude;* for Hawaii, 150° west *longitude;* for the Philippine Islands, 120° east *longitude.* Standard time was established in 1883 to correlate train schedules of various railroads over the same areas. The standard time belts were planned to be roughly symmetrical with respect to the *meridians* of reference, and to extend 7½° to either side thereof. Practical considerations, such as the need of time correlation of cities outside the original boundaries of a time belt with cities within the belt, have caused a gradual shifting of those boundaries until some of them now exhibit large irregularities. See *time: daylight-saving time; war time.*

time: true solar.—See under *time: apparent solar time.*

Time: Universal (U. T.).—The same as *Greenwich Civil Time (G. C. T.).*

The first use of Universal Time as a reference in the American Ephemeris and Nautical Almanac is in the volume for the year 1939.

time: war.—*Daylight-saving time* as prescribed in 1942 by Act of Congress.

The use of war time throughout the country was inaugurated on February 9, 1942, clocks being set ahead 1 hour at 2 A. M. standard time on that date (Public Law 403, 77th Congress). Its use by State and local agencies was not mandatory, except where State legislation so directed. The time in any given *time* belt was identified by the particular designation of that belt: Eastern War Time; Central War Time; etc. The use of war time was discontinued on September 30, 1945, at 2 A. M.

toise.—A unit of length used in early *geodetic surveys* and equal to about 6.4 English feet.

The Toise of Peru was an iron *standard* used in measuring the *base lines* which controlled the lengths of the Peruvian Arc (of *triangulation*), executed in 1736–1743, in connection with a determination of the figure and size of the earth. The Toise of Peru became the legal *standard* of length in France, and from it was derived the *French legal meter,* as follows: the toise was divided into 6 pieds (feet); each pied was divided into 12 pouces (inches); each pouce was divided into 12 lignes (lines); and one *French legal meter* was equal to 443.296 lignes exactly at a temperature of 13° Réaumur. The Peruvian Arc does not lie in modern Peru, but in Ecuador, which was included in the old Spanish presidency of Peru.

Toise of Peru.—See under *toise.*

tolerance (general).—The permissible deviation from a *standard.*

In *surveying* operations the prescribed limiting *probable error* may be regarded as an expression of tolerance, though the term tolerance is seldom used in connection with *survey* results. Its use may well be confined to stating the permissible deviation from exactness in the fitting together of the component parts of physical apparatus: for example, the *pivot inequality* of an *astronomical transit.*

topographic deflection.—That portion of the *deflection of the plumb line* which is due to the gravitational pull exerted by topographic masses.

Topographic deflection is not the same as *deflection of the plumb line* or *station error,* but is the theoretical effect produced by the resultant gravitational pull of the unevenly distributed topographic masses around the station, no allowance being made for *isostatic compensation.*

topographic feature.*—A prominent or conspicuous *topographic form* or salient part thereof.

topographic form.*—A *land form* considered without regard to origin, cause, or history.

topographic map.—See under *map.*

Topographic Map of the United States.—See under *map.*

topography (or relief).*—The features of the actual surface of the earth, considered collectively as to form.

A single feature, such as a mountain or valley, is called a *topographic feature.*

torsion balance.—A device for measuring very small forces of attraction due to *gravitation,* magnetism, etc., and consisting of a bar suspended horizontally by an elastic filament, one end of the bar being subjected to the influence of the attracting force in a much greater degree than the other end. The attracting force is balanced and its comparative strength measured by the torsional reaction of the filament.

In geophysical prospecting, a form of torsion balance is employed in determining the gradient of *gravity,* the *horizontal direction* in which the intensity of *gravity* increases or decreases most rapidly, so that in a *survey* of a large area, any existing large mass of abnormal density may be discovered. For example, the oil fields of the Gulf Coast are associated with salt domes—plugs of salt of such size and density that they are easily discovered and located by geophysical methods. Among the instruments used in making such discoveries is the torsion balance.

township (United States public-land surveys).*—The unit of survey of the *public lands* of the United States, normally a quadrangle approximately 6 miles on a side with boundaries conforming to *meridians* and *parallels,* located with reference to the *initial point* of a *principal meridian* and *base line.*

Townships are numbered consecutively north and south from a *base line;* thus "township 14 north" indicates a township in the 14th *tier* north of a *base line.* The word township is used in conjunction with the appropriate *range* to indicate the *coordinates* of a particular township with reference to the initial point; thus "township 14 north, range 3 east" indicates the particular township which is the 14th township north of the *base line* and the 3rd township east of the *principal meridian* controlling the surveys in that area. The plural form, townships or tps., is used whenever more than one unit is indicated; "townships 14 north, ranges 3, 4, and 5 east"; "townships 14 and 15 north, range 3 east."

township: fractional (United States public-land surveys).*—A *township* containing appreciably less than 36 normal *sections,* usually due to invasion by a segregated body of water, or by other land which cannot properly be surveyed as part of that *township.*

Townships may be rendered fractional also in closing the public-land surveys on State boundaries, or other limiting lines.

township line (United States public-land surveys).*—An exterior boundary of a *township* extending in an east-west direction.

track level.—See under *track sector.*

track sector.—An instrument composed of a half-circle *protractor* with a single movable arm which carries a *spirit level,* and is so constructed that when the *protractor* base is parallel with a railway rail and the *spirit level* bubble is in the center of its tube, the movable arm will register the slope (angle of inclination) of the rail. Also called track level.

The track sector was designed and used for determining the slope of the tape when used in *traverse* measures along a railway. Not proving satisfactory, its use was abandoned.

Transcontinental Triangulation datum.—See under *datum.*

transit.—1. The apparent passage of a star or other celestial body across a defined line of the celestial *sphere,* as a *meridian, prime vertical,* or *almucantar.* The apparent passage of a star or other celestial body across a line in the *reticle* of a *telescope,* or some *line of sight.* The apparent passage of a smaller celestial body across the disk of a larger celestial body.

2. A surveying instrument composed of a horizontal circle graduated in circular measure and an *alidade* with a *telescope* which can be reversed in its supports without being lifted therefrom. Also, the act of making such reversal.

3. An astronomical instrument having a *telescope* which can be so adjusted in position that the *line of sight* may be made to define a *vertical circle.*

1. When no line is specified, a transit across the *meridian* is usually intended. The transit of a star across the *meridian* occurs at the moment of its *culmination,* and the two terms are sometimes used as having identical meanings; such usage is not correct, even where the instrument is in perfect adjustment. At the poles, a star may have no *culmination,* but it will transit the *meridians.* The transit of a small celestial body across a larger one is exemplified by the transit of the planet Mercury across the disk of the Sun, or of a satellite of Jupiter across the disk of that planet. See *eclipse, occultation.*

2. A *theodolite* having a *telescope* that can be transited in its supports is a transit, and is sometimes termed a transit theodolite.

3. A transit used in astronomical work is usually called either an astronomical transit or a transit instrument.

transit: astronomical.—See under *transit,* 3.

transit: Bamberg.—See under *transit: broken-telescope transit.*

transit: broken-telescope.—An *astronomical transit* having its *telescope* so shaped that a ray of light entering the objective is reflected at right angles by a prism placed within the *telescope,* the reflected ray passing to the eyepiece which is in the *horizontal axis* of the *telescope* and outside its supporting wyes.

One make of broken-telescope transit, called the Bamberg broken-telescope transit or the Bamberg instrument, is described in two Special Publications of the U. S. Coast and Geodetic Survey: No. 35, Determination of the Difference in Longitude Between Each Two of the Stations Washington, Cambridge, and Far Rockaway, by Fremont Morse and O. B. French, 1916; and No. 109, Wireless Longitude, by George D. Cowie and E. A. Eckhardt, 1924. The term "bent transit" has also been applied to this instrument. The design of this instrument permits its use in the determination of *latitude* by the *zenith-telescope method.* It is given considerable weight without producing undesirable flexure. This and the unusually long distance between the supporting wyes make for stability. The *striding level* used with straight-telescope instruments is replaced with a *hanging level.* The position of the eyepiece being independent of the *altitude* of the object observed promotes convenience in observing. This instrument is used in first-order determinations of *astronomic longitude, astronomic latitude,* and recently has been used in first-order determinations of *astronomic azimuth* at stations in high *latitudes.* See *azimuth: micrometer method, determination of astronomic azimuth.*

transit: solar.—See under *solar transit.*

transit-and-stadia survey.—See under *survey.*

transit instrument.—See under *transit, 3.*

transit micrometer.—See under *micrometer.*

transit micrometer, contact correction.—See under *contact correction.*

transit rule: balancing survey.—See under *balancing a survey.*

transit traverse.—See under *traverse.*

transition curve.—See under *curve: spiral curve.*

Transportation Map of the United States.—See under *map.*

transverse Mercator grid.—An informal designation for a *State coordinate system* based on a *transverse Mercator map projection.*

transverse Mercator map projection.—See under *map projection.*

transverse polyconic map projection.—See under *map projection.*

traverse.—See under *traverse: survey traverse.*

traverse: astronomical.—A *survey traverse* in which the *geographic positions* of the stations are obtained from astronomic observations, and lengths and *azimuths* of lines are obtained by computation.

traverse: closed.—A *survey traverse* which starts and ends upon the same station, or upon stations whose *relative positions* have been determined by other *surveys.*

traverse: first-order.—A *survey traverse* which by itself forms a closed loop or which extends between *adjusted positions* of other *first-order control surveys,* and has a *closing error* in *position* not greater than 1 part in 25,000 of its length. The criteria prescribed for attaining the required *accuracy* and *precision* are as follows: The *probable error* of any main-scheme *angle* shall not exceed ±1.5″; the number of *angle* stations between *astronomic-azimuth* stations to be 10 to 15 in number; the *discrepancy* per main-scheme *angle* station between *astronomic azimuths* not to exceed 1.0″; the *probable error* of the *astronomic azimuths* not to exceed ±0.5″.

Formerly known as *precise traverse,* the present designation of first-order traverse was recommended by the Federal Board of Surveys and Maps in May 1925. Lacking the geometrical checks obtainable in *triangulation,* first-order traverse, though formerly used in the fundamental *control survey* of the country, is no longer so used.

traverse: fourth-order.—A *survey traverse* of an *accuracy* less than *third-order traverse.*

In fourth-order traverse, *angles* are observed with a *transit* or *sextant* or are determined graphically, and distances are measured with tape, *stadia,* or wheel.

traverse: geographical exploration.—A route followed across some part of the earth, approximate *positions* along which are determined by *surveying* or navigational methods.

traverse: open.—A *survey traverse* which starts from a station of known or adopted *position,* but does not end upon such a station.

traverse: random.—A *survey traverse* run from one station to another survey station which cannot be seen from the first station, in order to determine their *relative positions.* See *random line.*

traverse: second-order.—A *survey traverse* which by itself forms a closed loop or which extends between adjusted stations of *first-* or *second-order control surveys,* and has a *closing error* in position of between 1 part in 10,000 and 1 part in 25,000 of its length. The following additional criteria are prescribed for the attainment of the required *accuracy* and *precision: probable error* of main-scheme *angles* not to exceed ±3.0″; number of *angle* stations between *astronomic-azimuth* stations, 15 to 25; *discrepancy* per main-scheme *angle* station between *astronomic azimuths,* not to exceed 2.0″; *probable error* of *astronomic azimuths,* not to exceed ±2.0″.

The present designation, second-order traverse, was recommended by the Federal Board of Surveys and Maps in May 1925.

traverse: survey.—A sequence of lengths and *directions* of lines between points on the earth, obtained by or from field measurements, and used in determining *positions* of the points.

A survey traverse may determine the *relative positions* of the points which it connects in series, and if tied to *control stations* on an adopted *datum,* the *positions* may be referred to that *datum.* Survey traverses are classified and identified in a variety of ways: according to methods employed, as, *astronomical traverse;* quality of results, as, *first-order traverse;* purpose served, as, *geographical exploration traverse;* according to form, as, *closed traverse,* etc.

traverse: third-order.—A *survey traverse* which by itself forms a closed loop or which extends between adjusted stations of other *control surveys,* and has a *closing error* in *position* of between 1 part in 5,000 and 1 part in 10,000 of its length. The following additional criteria are prescribed for attaining the required *accuracy* and *precision: probable error* of main-scheme *angles* not to exceed ±6.0″; number of *angle* stations between *astronomic-azimuth* stations, 20 to 35; *discrepancy* per main-scheme *angle* station between *astronomic azimuths,* not to exceed 5.0″; *probable error* of *astronomic azimuths,* not to exceed ±5.0″.

The present designation, third-order traverse, was recommended by the Federal Board of Surveys and Maps in May 1925.

traverse: transit.—A *survey traverse* in which the *angles* are measured with an engineer's *transit* or *theodolite* and the lengths with a metal tape.

A transit traverse is usually executed for the control of local surveys and is of *second-* or *third-order* quality.

traverse net.—See under *survey net.*

traverse tables.—Mathematical tables listing the lengths of the sides opposite the oblique *angles* for each of a series of right-angle plane triangles, as functions of the length and *azimuth* (or *bearing*) of the hypotenuse.

Traverse tables are used in computing *latitudes* and *departures* in surveying and of *courses* in navigation. One argument of such a table is the *angle* which the line or *course* makes with the *meridian* (its *azimuth* or *bearing*), and the other argument is a distance. In tables used in *land surveying,* the distance argument is usually a series of integers, from 1 to 9, with which lines of greater length may be composed. In navigation, the distance argument may run to several hundred miles.

triangulation.—A method of *surveying* in which the stations are points on the ground at the vertices of a chain or network of triangles, whose *angles* are observed instrumentally and whose sides are derived by computation from selected triangle sides called *base lines,* the lengths of which are obtained from direct measurements on the ground.

Triangulation permits the selection of sites for stations and *base lines* favorable for use both from topographic and geometric considerations (see *strength of figure*); it is well adapted to the use of *precision* instruments and methods in all its operations, and susceptible of great *accuracy* and *precision* in its results. Triangulation is generally used where the area surveyed is large and requires the use of *geodetic methods.* Triangulation may be considered as including not only the actual operations of observing *angles* and measuring *base lines,* and their mathematical processing, but also the *reconnaissance* which precedes those operations, and the astronomic observations which are required in the establishment of a *geodetic datum* and in the control of the triangulation.

triangulation: arc.—A system of *triangulation* of limited width designed to progress in a single general direction.

Arc triangulation is executed for the purpose of connecting independent and widely separated *surveys, coordinating,* and *correlating* local surveys along the arc, furnishing data for the determination of a *geodetic datum,* providing a network of control points for a country-wide *survey,* etc. See *area triangulation.*

triangulation: area.—A system of *triangulation* designed to progress in every direction.

Area triangulation is executed to provide survey control points over an area, as of the city or county; or for filling in the areas between *arcs* of *triangulation* which form a network extending over a county or State. See *arc triangulation.*

triangulation: first-order.—*Triangulation* conforming to the following criteria: the average *error of closure* of the main-scheme triangles shall not exceed 1″; the maximum *error of closure* of the main-scheme triangles shall not exceed 3″; the *error of closure* in length on a measured *base line* or on a line of adjusted first-order triangulation shall not exceed 1/25,000 of the length of the line after the *angle* and *side* equations have been satisfied in the *adjustment.*

First-order triangulation was at one time known as *primary triangulation;* this was changed in 1921 to *precise triangulation;* and in May 1925 the present designation was recommended for adoption by the Federal Board of Surveys and Maps. The report of that Board recommended that the four grades of horizontal and vertical control ordinarily used be designated as first order, second order, third order, and fourth order, respectively, the first-named being the most *accurate.*

triangulation: flare.—A method of *triangulation* in which simultaneous observations are made on parachute flares. This method is used for extending triangulation over lines too long to be observed by ordinary methods.

triangulation: precise.—The designation which, from 1921 until the present terminology was adopted in 1925, was applied to what is now called *first-order triangulation.*

triangulation: primary.—The designation which, prior to 1921, was given to what is now called *first-order triangulation;* and thereafter and until the present terminology was adopted in 1925, was applied to what is now called *second-order triangulation.*

triangulation: secondary.—The designation which, prior to 1921, was given to what is now called *second-order triangulation;* and thereafter and until the present terminology was adopted in 1925, was applied to what is now called *third-order triangulation.*

triangulation: second-order.—*Triangulation* which does not attain the quality of *first-order triangulation* but does conform to the following criteria: the average *error of closure* of the main-scheme triangles shall not exceed 3″; the maximum *error of closure* of the main-scheme triangles shall not exceed 5″; the *error of closure* in length on a measured base line or on a line of adjusted first- or second-order triangulation shall not exceed 1/10,000 of the length of the line after the *angle* and *side equations* have been satisfied in the *adjustment.*

Second-order triangulation was at one time known as *secondary triangulation;* later (1921) the name was changed to *primary triangulation;* and in May 1925 the present designation was recommended by the Federal Board of Surveys and Maps.

triangulation: ship-shore.—A method of extending *triangulation* along a coast by making simultaneous observations from three or more shore stations on a target mounted on an anchored ship.

This method is used only when it is impractical to establish a chain of triangles or quadrilaterals.

triangulation: tertiary.—The designation which, prior to 1921, was given to what is now called *third-order triangulation.*

triangulation: third-order.—*Triangulation* which does not attain the quality of *second-order triangulation,* but does conform to the following criteria: the average *error of closure* of the main-scheme triangles shall not exceed 5″; the maximum *error of closure* of the main-scheme triangles shall not exceed 10″; and the closure in length on a measured *base line* or on a line of adjusted *triangulation* shall not exceed 1/5,000 of the length of the line after the *angle* and *side equations* have been satisfied in the *adjustment.*

Third-order triangulation was at one time known as *tertiary triangulation;* later (1921) the name was changed to *secondary triangulation;* and in May 1925 the present designation was recommended by the Federal Board of Surveys and Maps.

triangulation arc.—A system of *triangulation* forming a band or belt on the surface of the earth. Or the corresponding system of *positions,* lines, and *angles* on the surface of the *spheroid.*

The axis of a triangulation arc may *approximate* in position an *arc* on the spheroid, following a *meridian* of *longitude,* a *parallel* of *latitude,* or an oblique *arc;* it may follow a natural feature as a river; or it may follow an artificial feature, as a civil boundary. It is usually given an identifying name corresponding to its general or particular location, or having other geographic significance: as Ninety-eighth Meridian Arc, Mississippi River Arc, etc.

triangulation net.—See under *survey net.*

triangulation signal.—See under *signal.*

triangulation station.—A point on the earth whose *position* is determined by *triangulation.*

triangulation tower.—A *triangulation signal* consisting of two separate structures, independent of one another; an inner structure which supports the *theodolite* and sometimes the target or signal lamps, and an outer structure which supports the observer and his assistants and sometimes the target or signal lamps.

Triangulation towers are used to elevate the *line of sight* above trees, *topographic features,* and other obstacles that might interfere with the observing. Before 1927, towers of wood were used, the inner structure being a tripod and the outer structure a four-leg scaffold. In 1927, the *Bilby steel tower* was put into use. Triangulation towers more than 100 feet in height are not unusual.

triaxial ellipsoid.—See under *ellipsoid.*

tribrach.—The three-arm base of a surveying instrument which carries the foot-screws used in leveling the instrument.

Many surveying instruments have a four-screw base or quadribrach. Such an instrument is not suitable for third- or higher-order horizontal control, for the leveling process may introduce strains in the base of the instrument which will tend to change the instrument in *azimuth* while the observations are being made.

trigonometric leveling.—See under *leveling.*

trilateration.—A method of extending horizontal control where the sides of triangles are measured rather than the angles as in triangulation.

trilinear surveying.—See under *surveying.*

trivet.—A device for use in place of a tripod in mounting a *transit* or *level.* It is essentially a tripod head with three very short legs cast as a single piece of metal.

It is used for placing a *transit* or *level* in a position where a regular tripod could not be conveniently used, or where greater stability is desired. When used for a *theodolite,* a trivet may include the foot-plate with V-shaped grooves cut in suitable arms to receive the feet of the leveling screws.

Tropic of Cancer.—Astronomy. The *parallel of declination* passing through the *summer solstice.* Geography. The *geographic parallel* whose *latitude* corresponds to the *declination* of the *summer solstice.*

The *obliquity of the ecliptic* is steadily changing so that the *summer solstice* is not a point of fixed *declination.* When the Tropic of Cancer is to be shown on a terrestrial *map,* it is desirable that it be treated as a line of fixed *latitude,* and for this purpose it is here proposed that the value 23°27′ north *latitude* be adopted and used.

While, in popular usage, the term "tropics" is sometimes applied to the belt of the earth's surface bounded by the Tropic of Cancer and the *Tropic of Capricorn,* in technical language, the term designates the lines themselves, the included area being known as the "Torrid Zone." "Tropics" also has a climatic connotation.

Tropic of Capricorn.—Astronomy. The *parallel of declination* passing through the *winter solstice.* Geography. The *geographic parallel* whose *latitude* corresponds to the *declination* of the *winter solstice.*

The *obliquity of the ecliptic* is steadily changing so that the *winter solstice* is not a point of fixed *declination.* When the Tropic of Capricorn is to be shown on a terrestrial *map,* it is desirable that it be treated as a line of fixed *latitude,* and for this purpose it is here proposed that the value 23°27′ south *latitude* be adopted and used. See supplementary paragraph under *Tropic of Cancer.*

tropical month.—See under *month.*

tropical year.—See under *year.*

Troughton level.—See under *leveling instrument.*

true.*—A comparative term applied to astronomical values to distinguish them from corresponding magnetic values.

The terms *true bearing,* true meridian, true north, etc., occur frequently in land survey reports, distinguishing those quantities from corresponding magnetic values. In descriptions of land boundaries, the use of true has legal significance and, except in rare instances, refers to values based directly on astronomical observations. True should never be used to indicate *geodetic* values, although in recent work, where the difference between astronomical and *geodetic* values is unimportant, the term has been applied without distinction to both in order to distinguish them from corresponding magnetic values. The use of true to indicate astronomical values should be avoided as much as possible: exact meaning is conveyed by the terms *celestial meridian, geodetic meridian, magnetic meridian,* etc.

true bearing.—See under *bearing.*

true error.—See under *error (general).*

true solar time.—See under *time: apparent solar time.*

turning point (leveling).—See under *point.*

U

Unalaska datum.—See under *datum.*

unit: absolute.—Any unit in a system that is based directly upon associated fundamental units of length, mass, and time.

In selecting a system of absolute units, the choice of the fundamental units is arbitrary. In the metric (c. g. s.) system of absolute units, the fundamental units are the centimeter, the gram, and the second. In the *leveling* work of the U. S. Coast and Geodetic Survey, the metric system is used in defining *dynamic number.*

unit: astronomical.—See under *astronomical unit.*

unit of length.—A nominal distance in space fixed by definition, and independent of temperature, pressure, and other physical conditions. See *meter: international meter; standard of length.*

U. S. Coast and Geodetic Survey leveling rods.—See under *leveling rod: U. S. Coast and Geodetic Survey rods.*

U. S. Engineer leveling rod.—See under *leveling rod: U. S. Engineer precise leveling rod.*

U. S. Geological Survey level.—See under *leveling instrument.*

U. S. Geological Survey leveling rods.—See under *leveling rod: U. S. Geological Survey precise leveling rods.*

United States standard datum.—See under *datum: North American datum.*

universal instrument.—See under *alt-azimuth instrument.*

universal level.—See under *level: circular level.*

universal time.—See under *time.*

upper culmination.—See under *culmination.*

V

Valdez datum.—See under *datum.*

value (of a quantity).—An arithmetical number which defines the size of the quantity.

value: adjusted.—A *value* of a quantity derived from observed data by some orderly process which eliminates *discrepancies* arising from *errors* in those data.

The process, called an *adjustment,* may be made by graphical (mechanical) methods or by analytical (arithmetical) methods. An analytical method involves the determination of *discrepancies* which exist among combinations of observed data; expressing those discrepancies in the form of *condition equations* or *observation equations;* and solving those equations to obtain *corrections* to the observed data. If the solution is by the *method of least squares,* the result will be the *most probable values* that can be derived from the given data. If the data used are sufficiently extensive, the values obtained by the *least-squares method* will be largely free from *accidental errors* of observation. See *position: adjusted.*

value: most probable.—That *value* of a quantity which is mathematically determined from a series of observations and is more nearly free from the effects of *blunders* and *errors* than any other *value* that might be derived from the same series of observations.

An *adjusted value* determined by the *method of least squares* is a most probable value.

value: observed.—A *value* of a quantity that is obtained by instrumental measurement of the quantity.

The term observed value is often applied to the *value* of a quantity derived from instrumental measurement after corrections have been applied for *systematic errors,* but before *accidental errors* have been taken out by some method of adjustment. An *angle* obtained with a *repeating theodolite,* after correction for *closure of horizon* has been applied, is considered an *observed angle.* See *value: most probable value; value: adjusted value.*

value: true.—That *value* of a quantity which is completely free from *blunders* and *errors.*

Since the *errors* to which physical measurements are subject cannot be known exactly, it follows that the true value of a quantity cannot be known with exactness. In *survey* work, the *most probable value* is used as best representing the true value of the quantity.

variation: magnetic.—See under *magnetic variation.*

variation of latitude.—See under *latitude.*

variation of the pole.—A wandering of the poles of figure of the earth with respect to its poles of rotation.

The direction in space of the poles of *rotation* of the earth is nearly invariable; these are the points on the *celestial sphere* reached by the axis about which the earth rotates. The axis of figure of the earth or axis within the earth about which the moment of inertia is a maximum is not coincident with its axis of *rotation,* and extended to the *celestial sphere* describes a path thereon about each pole of *rotation*—a path which is irregular, although an annual periodicity in the motion may be detected, and also one of 14 months. The maximum variation in direction of the axis of figure from a mean position with respect to the axis of *rotation* ranges between 0.1″ and 0.3″. Variation of the pole affects observed determinations of *astronomic latitude, longitude,* and *azimuth,* but account of it is taken in *first-order work* only.

vernal equinox.—See under *equinox.*

vernier.—An auxiliary scale sliding against and used in reading a primary scale. The total length of a given number of *divisions* on a vernier is equal to the total length of one more or one less than the same number of *divisions* on the primary scale.

The vernier makes it possible to read a principal scale (such as a divided circle) much closer than one *division* of that scale. If a space on the vernier is shorter than a space on the primary scale, it is a direct vernier; if a space on the vernier is the longer, it is a retrograde vernier, so-called because its numbers run in the opposite direction from those on the primary scale. The direct vernier is the usual type, and is used in reading the circles on an engineer's *transit,* and on a *repeating theodolite.* Two verniers extending and numbered in opposite directions from the same initial form a double vernier, used in reading a circle having *graduations* numbered in both directions. A single vernier so constructed and numbered that it may be read in either direction is called a folding vernier.

vernier: contact.—The usual type of *vernier,* having the *vernier* scale and the graduated circle in physical contact.

vernier: direct.—See *vernier.*

vernier: double.—See *vernier.*

vernier: folding.—See *vernier.*

vernier: optical.—A microscope with *vernier* lines ruled on a glass slide placed in the focal plane common to the objective and the eyepiece, where it is compared with the image of the graduated circle.

The microscope is so adjusted that the image of the graduated circle falls in the plane of the *vernier* lines, and the *vernier* scale subtends the proper number of *divisions* of the graduated circle. The optical vernier is superior to the usual *vernier* (*contact vernier*) in that there are no *parallactic errors* such as are caused by wear of the contact edges. Optical verniers are, however, more liable to injury and to loss of adjustment than are *contact verniers.*

vernier: retrograde.—See *vernier.*

vertex of curve.—See under *curve: point of intersection.*

vertical.—The *direction* in which the force of gravity acts.

It is the *direction* indicated by a plumb line, and does not usually coincide with the *direction* of the *normal* at a point. The term vertical uses the *geoid* as a reference; *normal* applies to the *spheroid.* See *zenith* and *nadir;* and *deflection of the plumb line.*

vertical angle.—See under *angle.*

vertical angulation.—The process of obtaining differences of *elevation* by means of observed *vertical angles,* combined with lengths of lines.

In *geodetic* work, *trigonometric leveling* is used with the same meaning.

vertical axis (theodolite; transit).—The line through the center of instrument about which the *alidade* rotates.

For an instrument in complete adjustment, this axis occupies a vertical position, passes through the center of the horizontal circle, and is perpendicular to its plane.

vertical circle.—Any *great circle* of the *celestial sphere* passing through the *zenith* (and *nadir*). Also, a divided circle mounted on an instrument in such a manner that the plane of its graduated surface can be placed in a *vertical plane.*

As a *great circle,* a vertical circle is the line of intersection of a *vertical plane* with the *celestial sphere.* As an instrument, a vertical circle may be an auxiliary attachment to a *theodolite* or *transit,* or it may be the major feature of an instrument intended primarily for use in measuring *vertical angles* in astronomical and *geodetic* work. In *geodetic* work, such an instrument is called a vertical circle.

vertical collimator.—See under *collimator.*

vertical comparator (pendulum).—A stand designed for the support of a *pendulum,* a bar of known length, and two *micrometer microscopes,* so placed with reference to one another that the length of the *pendulum* can be measured. Such an apparatus was designed by Repsold.

vertical coordinate.—See under *coordinates.*

vertical plane.—Any plane passing through a point on the earth and containing the *zenith* (and *nadir*) of that point.

Containing the *zenith,* a vertical plane must also contain the *nadir.* The planes of the *celestial meridian* and of the *prime vertical* are vertical planes.

vibration (pendulum).—A single movement of a *pendulum* in either direction, to or fro. See *oscillation (pendulum).*

vibration: amplitude of vibration (pendulum).—See under *amplitude of vibration (pendulum).*

vinculum.—A short horizontal bar placed over the seconds of a numerically expressed *angle* or *direction* to indicate that the seconds are used in connection with a value of minutes 1 less than is recorded. A double vinculum indicates association with a value of minutes 2 less than is recorded.

In recording an *angle* or a *direction* observed with an instrument provided with means of making several independent readings of the circle, as with several *verniers* or *micrometer microscopes,* the degrees, minutes, and seconds are usually recorded for only one *vernier* or microscope, and only the seconds for the other *verniers* or microscopes. Where the seconds as read for the B vernier are associated with minutes less than those recorded for the A vernier, this is indicated in the record by placing a vinculum, or rarely, a double vinculum, over the seconds reading of the B vernier, thus:

	Vernier reading			*Simplified recording*		
	°	′	″	°	′	″
A	90	11	00	90	11	00
B	270	10	50			$\overline{50}$
A	75	15	00	75	15	00
B	255	13	55			$\overline{\overline{55}}$

W

war time.—See under *time.*

Washington Meridian.—See under *meridian.*

water leveling.—See under *leveling.*

weight (surveying).—The relative reliability (or worth) of a quantity as compared with other *values* of the same quantity.

If one *value* of a quantity has a weight of 2, and another *value* of the same quantity has a weight of 1, the first *value* is worth twice the second *value,* and a mean *value* would be obtained by taking a *weighted mean:* twice the first *value* plus once the second *value,* the sum being divided by three.

weighted mean.—A value obtained by multiplying each of a series of *values* by its assigned *weight,* and dividing the sum of those products by the sum of the *weights.*

A weighted mean is sometimes called a weighted arithmetical mean. If the constituent *values* are all of the same *weight,* the *weight* of each *value* may be considered as unity, and an *arithmetical mean* taken. The present practice in *surveying* where both instruments and methods are *standard,* is to make all observations of the same (unit) *weight,* thereby simplifying the computations involved in their reduction and adjustment.

Werner map projection.—See under *map projection.*

westing.—See under *departure (plane surveying).*

Wild theodolite.—See under *theodolite.*

wind (spirit level).—See under *level.*

winter solstice.—See under *solstice.*

witness corner.—A marked point established on firm ground at a measured distance and *direction* from a property corner which may be so situated that it cannot be permanently marked.

A witness corner in *land surveying* corresponds to a *reference mark* in *control surveying.* See *corner: witness corner (United States public-land surveys).*

witness corner (United States public-land surveys).—See under *corner.*

witness mark.—A material mark placed at a known distance and *direction* from a property corner, instrument or other *survey station,* to aid in its recovery and identification.

In *surveying,* a witness mark is established as an aid in the recovery and identification of a *survey station,* or other point to which it is a witness. A mark which is established with such *precision* and *accuracy* that it may be used to restore or take the place of the original station is more properly called a *reference mark* in *control surveys,* and a *witness corner* in *land surveys.*

Woodward base-line measuring apparatus.—See under *base apparatus: iced-bar apparatus.*

working pendulum.—See under *pendulum.*

wye (Y) level.—See under *leveling instrument.*

X

x **correction.**—The *correction* to an *x direction.*

x **direction.**—An observed *direction* in a *triangulation* figure for which an approximate value is obtained and treated like an observed *direction* in the adjustment of the figure.

The work of a *least-squares* adjustment of a *triangulation* figure sometimes requires the use of an *x* direction, for which an approximate value is obtained by an *inverse position computation,* by the solution of the *three-point problem,* or by other means, and then using this *x* direction in the adjustment and obtaining a *correction* (*x correction*) for it, which makes it consistent with the adjusted values of the observed *directions.*

Y

Y (wye) level.—See under *leveling instrument: wye* (Y) *level.*

Yakutat datum.—See under *datum.*

yard.—A unit of length equal to 36 *inches* exactly.

year.—An interval of *time* based on the *revolution* of the earth in its orbit around the sun with respect to (1) the stars, giving the *sidereal year;* (2) the *vernal equinox,* giving the *tropical year;* (3) *perihelion,* giving the *anomalistic year.* There is also a *calendar year,* a conventional value based on the *tropical year.*

year: anomalistic.—The interval of *time* between two successive passages of *perihelion* by the sun.

The anomalistic year is equal to 365.25964 *mean solar days.*

year: calendar.—A conventional *year* based on the *tropical year.*

The calendar year takes account of the fraction of a *day* contained in the *tropical year,* by assigning an additional *day* to the *year* at stated periods. The calendar years of interest in this country are defined by the *Julian Calendar,* and the *Gregorian Calendar.*

year: sidereal.—The interval of *time* occupied by the sun in completing an apparent circuit of the heavens, from a given star back to the same star.

The sidereal year is equal to 365.25636 *mean solar days.*

year: tropical.—The interval of *time* between two successive passages of the *vernal equinox* by the sun.

The tropical year is the *year* of the seasons, and the basis of the conventional *calendar year* used in chronology and civil reckoning. It is equal to 365.24220 *mean solar days.*

Yukon datum.—See under *datum.*

Z

zenith.—The point where the *direction* of the plumb line produced above the *horizon* meets the *celestial sphere.*

The zenith and *nadir* are poles of the *horizon.* The plumb line is perpendicular to the surface of the *geoid,* but not (except in rare cases) to the surface of the *spheroid.* The *angle* between the plumb line (the *vertical*) and the perpendicular to the surface of the *spheroid* (the *normal*) is the *deflection of the vertical,* also called the *deflection of the plumb line.* The terms, *geodetic zenith* (or *nadir*) and *geocentric zenith* (or *nadir*) are sometimes used, and with meanings different from the above definition: their use is not recommended.

zenith: geocentric.—The point where a line from the center of the earth through a point on its surface meets the *celestial sphere.*

This term is sometimes used in astronomic work, but seldom appears in *geodetic* work. It should be used only in its entirety, the single word, *zenith,* being reserved to designate the point determined by the *direction* of the plumb line.

zenith: geodetic.—The point where the *normal* (to the *spheroid*) extended upward, meets the *celestial sphere.*

This term has some use in *geodetic* work, but should be used only in its entirety. The single word, *zenith,* is reserved to designate the point determined by the *direction* of the plumb line.

zenith camera.—An instrument for the determination of an astronomic position by taking a photograph of the sky immediately surrounding the *zenith.*

The instrument consists of a camera designed to photograph a small section of the sky. The optical axis may be set very precisely in the vertical so that the photograph is symmetrical with respect to the observer's zenith. The time of each observation is recorded on the photograph, thus furnishing the information required to compute the astronomic latitude and longitude.

zenith distance.—The *vertical angle* between the *zenith* and the object which is observed or defined. See *zenith distance: double.*

Zenith distance is the complement of the *altitude.*

zenith distance: double.—A value of twice the *zenith distance* of an object, obtained by observation and not by mathematical process.

In *trigonometric leveling* and in astronomical work, double zenith distances are observed because they are nearly free from effects of inclination of the *vertical axis* of the instrument used.

zenith sector.—See under *sector.*

zenith telescope.—A portable instrument adapted for the measurement of small differences of *zenith distance,* and used in the determination of *astronomic latitude.*

This instrument consists of a *telescope* equipped with an *ocular micrometer* and a *spirit level,* and so mounted on a *vertical axis* that it may be placed in the plane of the *meridian* for observation on a star *culminating* north (or south) of the *zenith,* and then rotated 180° in *azimuth* and a second star observed as it *culminates* south (or north) of the *zenith.* The difference of the *zenith distances* of the two stars is measured with the *micrometer;* the *spirit level* is used to determine any change that may occur in the direction of the axis of *rotation* of the *telescope* between the two observations. In its present form, this instrument is essentially the invention (in 1834) of Captain Andrew Talcott of the U. S. Engineers. It was adopted by the U. S. Coast and Geodetic Survey for *latitude* determinations and given some improvements. See *zenith-telescope method, latitude determinations.*

zenith-telescope method, latitude determination.—A *precise* method of determining *astronomic latitude* by measuring the difference of the meridional *zenith distances* of two stars of known *declination,* one north and the other south of the *zenith.*

The observations are made with a *zenith telescope,* or with an *astronomical transit* which can be converted to serve as a *zenith telescope,* such as the *meridian telescope* and the *broken-telescope transit.* The two stars have approximately the same meridional *zenith distances,* and their *culminations* occur within a few minutes of the same time. The *astronomic latitude* of the point of observation will be one-half the sum of the *declinations* of the two stars, plus or minus one-half the difference of their *zenith distances.* This method is also known as the Horrebow-Talcott method, latitude determination, and the Talcott method, latitude determination. While Peter Horrebow (not Harrebow) published an account of his method in 1732, it was buried in obscurity, and there is good reason to believe that Captain Andrew Talcott had no knowledge of Horrebow's work when he announced his own discovery of the method in 1834.

U. S. GOVERNMENT PRINTING OFFICE : 1974 O - 559-993

ELECTRONIC SURVEYING INSTRUMENTS

A Review of Principles, Problems and Procedures

J. M. RÜEGER

MONOGRAPH 18

SCHOOL OF
SURVEYING AND SPATIAL
INFORMATION SYSTEMS

THE UNIVERSITY OF NEW SOUTH WALES UNSW SYDNEY NSW 2052 AUSTRALIA

J. M. Rüeger

Electronic Surveying Instruments

A Review of Principles, Problems and Procedures

First Edition

Reprint 2010

With 81 Figures and 6 Tables

Monograph 18
School of Surveying and Spatial Information Systems
The University of New South Wales
UNSW SYDNEY NSW 2052
Australia

Published by
School of Surveying and Spatial Information Systems
The University of New South Wales
UNSW SYDNEY NSW 2052
Australia

Received October 2003

© Copyright 2003, 2010

No part may be reproduced without written permission

First published: November 2003
Reprinted with corrections: October 2010

National Library of Australia
Card Number and ISBN
0-7334-2083-4

Preface

The field equipment used in daily surveying practice has changed considerably over the last 15 to 20 years of the 20th century. The traditional optical-mechanical instruments gave way to the newer electro-optical-mechanical devices. The new technology was not always understood nor were the field procedures always amended to suit it. Sometimes, field procedures were changed incorrectly because of a lack of understanding of the new instrumentation. It is hoped that this text will improve the understanding and use of the electronic equipment that is used today.

This text evolved from more advanced undergraduate and postgraduate courses taught by the author at the University of New South Wales (UNSW, Sydney, Australia) as well as from continuing professional development courses on electronic theodolites and digital (bar code) levels. It covers theoretical and practical aspects of modern field surveying instruments, their operating principles and their differences from traditional (non-electronic) field surveying equipment. Not discussed are methods involving the Global Positioning System (GPS), photogrammetry and remote sensing and the details of electronic data recording and coding. The reader is referred to other textbooks on these topics. The principles of electronic distance measurement (EDM) are not covered either as a modern and detailed textbook is available (Rüeger 1990 1996). Some specialised instruments using EDM, however, are discussed, as is reflectorless distance measurement.

This text was written for readers that had some previous exposure to field surveying. In particular, it is assumed that the reader is familiar with the basic principles and operation of optical theodolites and spirit levels. If not, the reader should consult a standard textbook on surveying and read the chapters on theodolites, levels and on the field operations with such before reading this text. This book suits professionals, who went through tertiary courses before the widespread introduction of electronic surveying instruments, current students who wish to broaden their understanding of field instruments, and readers of standard textbooks on 'surveying', who are not satisfied with the, usually very limited, information on instruments and procedures provided by these texts.

After an introduction, Chapter 2 introduces a number of hand-held instruments, such as hand-held distance meters, compasses, clinometers (and combinations thereof) as well as different types of electronic barometers. The latter double as altimeters and can be used for heighting.

Chapter 3 discusses digital (bar code) levelling instruments and rotating laser levels. Particular emphasis is placed on the various errors that may occur in levelling with digital levels and laser levels. This chapter also contains useful advice for all professionals involved in precise levelling with digital levels.

Chapter 4 introduces the different types of electronic theodolites and tacheometers, including gyro, laser, tracking, scanning and reflectorless instruments. Electronic circle reading systems and electronic level sensors are discussed in some detail, as are their inherent errors. Some notes on the practical use of these instruments follow.

Chapter 5 presents a number of dedicated instruments or techniques that were developped for specific tasks. Reflectorless EDM is discussed in some detail, highlighting some of the problems that can occur and giving some advice on its use. Laser scanners are mentioned as is the often ignored technique of motorised levelling. The chapter concludes with sections on airborne laser profilers, laser trackers and a laser measurement system. The latter two are employed in metrology.

Exercises are given at the end of each chapter. These exercises are designed to further the understanding of the principles and concepts discussed in the text. The solutions are not provided; they can be worked out from the information given in the text.

Sydney, Spring 2003 J. M. Rüeger

Reprint 2010

The author is greatly indebted to the readers that have communicated errors in the first editions, in particular A. Young. All known errors have been corrected in this reprint of the first edition.

Sydney, Spring 2010 J. M. Rüeger

Contents

1. Introduction 1

2. Hand-Held Equipment 5
2.1 Electronic Pocket Tapes 5
2.1.1 Ultrasound Sensor 6
2.1.2 Electro-Optical Sensor 7
2.2 Hand-Held Angle-Angle-Distance Devices 8
2.2.1 Fluxgate Compass 10
2.2.2 Clinometers 12
2.2.3 Use of Hand-Held Angle-Angle-Range Devices 13
2.3 Electronic Barometers (and Altimeters) 15
2.3.1 Working Principles 15
2.3.1.1 Vibration Pressure Sensor 15
2.3.1.2 Capacitive Pressure Sensor 17
2.3.1.3 Piezo-Resistive Pressure Sensor 18
2.3.2 Performance of Digital Barometers 19
2.3.3 Heighting with Digital Barometers/Altimeters 20
2.4 Exercises 22

3. Levelling Equipment 27
3.1 Digital (Bar Code) Levelling Instruments 27
3.1.1 Introduction 27
3.1.2 How do Digital Levels Differ from Conventional Automatic Levels? 29

3.1.2.1 DC Power 29
3.1.2.2 Staffs 30
3.1.2.3 Electronic Staff Reading and Distance Measurement 30
3.1.2.4 Illumination of Staff 30
3.1.2.5 Compensator 30
3.1.2.6 Optical or Electronic Horizontal Circle 30
3.1.2.7 Electronic Data Recording 31
3.1.2.8 Computer Interface 31
3.1.2.9 Real-Time Correction of Instrument Errors 31
3.1.2.10 On-Board Computing 31
3.1.3 Principle of the Wild NA2000 32
3.1.3.1 Basic Design and Working Principle 32
3.1.3.2 Measuring Sequence 34
3.1.3.3 Signal Processing 35
3.1.3.4 Accuracy of Bar Code Levels 37
3.1.4 Bar Code Staffs 39
3.1.4.1 Leica Normal Bar Code Staffs 39
3.1.4.2 Leica Invar Bar Code Staffs 40
3.1.4.3 Errors of Normal Bar Code Staffs 40
3.1.4.4 Errors of Invar Bar Code Staffs 40
3.1.5 Errors in Precise Levelling with Bar Code (Digital) Levels 40
3.1.5.1 Errors in Bar Code (Digital) Levels 41
3.1.5.2 Errors of Invar Bar Code Staffs 46
3.1.5.3 External Influences on Line of Sight 47
3.1.5.4 Errors of the Observer 48
3.2 Laser Levels 49
3.2.1 Construction of a Rotating Laser Level 50
3.2.2 Design of a Two-Axis Compensator of a Rotating Laser Level 53
3.2.3 Major Errors of Rotating Laser Levels 53
3.2.3.1 Compensation Error 53
3.2.3.2 Adjustment Conditions of Rotating Laser Levels 54
3.2.3.3 Misalignment of Rotating Mirror 55
3.2.3.4 Secondary Height Error 56
3.2.4 Calibration of Rotating Laser Levels 56
3.2.5 Computation of Heights, Earth Curvature and Refraction 57
3.3 Exercises 59

---

4. Electronic Theodolites and Tacheometers 65
4.1 Types of Electronic Theodolites and Tacheometers 65

4.1.1 Electronic Theodolites 65
4.1.2 Electronic Tacheometers 66
4.1.3 Gyro-Theodolites 67
4.1.4 Motorised Electronic Tacheometers 68
4.1.4.1 One-Person-Survey-Systems 70
4.1.4.2 Automatic Monitoring Systems 71
4.1.5 Motorised Electronic Video Theodolites 73
4.1.6 Laser Theodolites 75
4.1.7 Tracking Electronic Tacheometers 76
4.1.8 Reflectorless Electronic Tacheometers 76
4.1.9 Scanning Electronic Tacheometers 77
4.2 Features of Electronic Theodolites and Tacheometers 78
4.2.1 Circle Types 78
4.2.1.1 Incremental Circles 79
4.2.1.2 Quasi-Absolute Circles 80
4.2.1.3 Absolute Circles 80
4.2.2 Diametrical Circle Reading 81
4.2.3 Electronic Level Sensors versus Vertical Circle Compensators 82
4.2.3.1 Definition of an Electronic Level Sensor 82
4.2.3.2 Definition of a Vertical Circle Compensator 82
4.2.4 Data Recording 83
4.2.5 On-Board Computing 84
4.2.6 Power Supply 84
4.2.7 Communication with Personal Computers 85
4.2.8 Automatic Focussing, Searching and Pointing 86
4.2.8.1 Automatic Focussing 86
4.2.8.2 Automatic Searching 86
4.2.8.3 Automatic Pointing 87
4.2.9 Computer Assisted Instrument Calibration 89
4.2.10 Modern Vertical Axis Systems 90
4.3 Circle Reading System of the Electronic Tacheometer Nikon DTM-1 91
4.3.1 Coarse Measurement 92
4.3.2 Fine Measurement 93
4.3.3 Sensing of the Direction of Rotation 95
4.4 Electro-Optical Level Sensors 95
4.4.1 Nikon DTM-1 Single-Axis Level Sensor 97
4.4.2 Leica TPS1100 Series Dual-Axis Level Sensor 97
4.4.3 Kern E2 Dual-Axis Level Sensor 98
4.4.4 Principle of the Determination of the Theodolite's Dislevelment 100

4.5 Properties of Electronic Level Sensors 102
4.5.1 Compensation Error 103
4.5.2 Scale Factor Error 103
4.5.3 Setting Error 104
4.5.3.1 Random Component 104
4.5.3.2 Systematic Component 105
4.5.4 Vertical Circle Index Error and Correction 105
4.6 Circle Graduation Errors 106
4.6.1 Periodic Errors 107
4.6.2 Interpolation Errors 107
4.7 Some Notes on the Use of Electronic Theodolites and Tacheometers 109
4.7.1 Levelling of Electronic Theodolites and Tacheometers 110
4.7.2 Selection of Measuring Unit 110
4.7.3 Use of Umbrella 111
4.7.3.1 Electronic Theodolites 111
4.7.3.2 Electronic Tacheometers 112
4.7.4 Automatic Power-Off 112
4.7.5 Two-Way Radios and Cellular (Mobile) Phones 112
4.7.6 Real-Time Corrections to Measured Data 112
4.7.7 Direction Measurements 113
4.7.7.1 Single-Face versus Dual-Face Measurements 114
4.7.7.2 Sequence of Direction Measurements 115
4.7.7.3 Elimination of Periodic Errors 115
4.7.7.4 Circle Setting 115
4.7.8 Zenith Angle Measurements 116
4.7.9 Simultaneous Direction, Zenith Angle and Distance Measurements 116
4.7.10 Plumbing of Structures 117
4.7.10.1 Plumbing Shafts and Wells 117
4.7.10.2 Plumbing a Building 118
4.8 Exercises 118

5. Specialised Equipment 121
5.1 Reflectorless Electronic Distance Measurement 121
5.1.1 Basic Properties 122
5.1.2 Beam Size and Shape 123
5.1.3 Multiple Target Problem 125
5.1.3.1 Pulse Distance Meters 125
5.1.3.2 Phase Measuring Distance Meters 127

5.1.4 Influence of the Material and Colour of Target 128
5.1.5 Target Orientation 128
5.1.6 Measurement to Corners 129
5.1.7 Some Notes on the Use of Reflectorless EDM 130
5.2 Laser Scanners 132
5.3 Motorised Levelling 134
5.4 Laser Profiling and Laser Altimeters 137
5.4.1 Laser Profiling on Land 137
5.4.2 Depth Sounders 139
5.5 Single Beam Laser Trackers for Metrology 140
5.6 Reflectorless Single Station Laser Measurement System 143
5.7 Exercises 144

References **147**

Subject Index **153**

1. Introduction

Surveying technology did change considerably during the last 30 years due to developments in computers, electro-optics and satellite technology, to name just the major influences. It has been stated (Rüeger 1995b) that surveying practice does not make full use of the new (and more efficient and cheaper) opportunities. For reasons of efficiency and economics, electronic data recording and electronic post-processing will be mandatory in any large scale survey such as setting-out, detail and contour surveys. In consequence, a number of field techniques and surveying instruments have become obsolete over the last decades. Rüeger (1995b) discussed these aspects in more detail.

The changes in the surveying instrument market indicate the new technology bought by geomatic engineers and surveyors. For simplicity, the periodical instrument surveys published by the American journal Point of Beginning (POB) are used to show the trends in the purchasing of instruments. Although these surveys reflect the US market, the detected changes would be similar to those in South-East Asia (apart of vernier theodolites, naturally).

In 1982, the journal POB reported 46 optical theodolites and 3 electronic theodolites on the market. Ten years later, POB listed 18 optical theodolites and 16 electronic theodolites. It is unlikely, that optical theodolites will be manufactured very much longer, considering that an increasing number of second hand optical theodolites becomes available.

The journal POB reported 24 electronic distance meters in 1981 and 25 in 1993. Although the number of models did not change in the 12 years, one would expect a significant drop in the numbers sold. POB listed 11 fully electronic tacheometers ('total stations') in 1983 whilst listing 68 different models in 1994. It is obvious that the electronic tacheometers slowly replace stand-alone theodolites and stand-alone distance meters.

As far as tilting and automatic levelling instruments are concerned, 27 were reported by POB in 1984 and 37 in 1994. Six digital (bar code) levels were reported for the first time in 1994. Most noticeable are the 51 different models of rotating laser levels listed in 1994. Although some rotating laser levels did exist in 1984 (but were not included in the POB survey in that year), the number of models has certainly grown significantly over the last ten years. New is that all traditional surveying instrument manufacturers now cater for this market.

The above market surveys demonstrate that the electronic tacheometer has become a universal surveying instrument, replacing theodolites, distance meters and levels. The dumpy levels on building sites are clearly being replaced by the rotating laser levels. Where levelling instruments are still required for special applications, digital (bar code) levels are being used. The market for GPS receivers will grow further once millimetre accuracy can be achieved at the same price, with the same ease and with the same speed as with electronic tacheometers. GPS receivers, however, will never work in buildings, underground and under trees, to give a few examples.

Another trend in instrumentation, which could be documented with the aid of surveys on the purchase of data recorders, is electronic data recording. This goes hand-in-hand with the other trend of using personal computers for the processing of all field data and the production of plans, maps and data bases. In the opposite sense, set-out data are pre-computed in the office and transferred in electronic form to the field instrument for the setting-out. Electronic data capture is essential if data are to be transferred in electronic form from the field to the office or if they are to be processed in the field.

The trend towards one-person-survey-systems should also be noted. For example, the rotating laser levels on building sites are very powerful one-person levelling systems. Robotic electronic tacheometers can find and track (moving) reflectors and can be operated remotely by the surveyor at the reflector. They provide efficient one-person-systems for detail and contour surveys as well as setting-out work. They are also ideally suited for repeated surveys of the same network as, for example, in around-the-clock deformation measurements of unstable terrain and structures.

Electronic distance measurement (EDM) to passive targets (now referred to as 'reflectorless' EDM) has been possible for quite some time. Stand-alone distance meters, able to measure to non-cooperative targets, became available in 1986. Zeiss released the first 'reflectorless' electronic tacheometer ('total station') in 1993. Broad acceptance by the surveying profession followed once Leica, Topcon and Trimble released their reflectorless instruments in 1998, followed by Nikon in 1999. The range of reflectorless EDM depends heavily on the type of surface that is measured to and its orientation to the measuring beam. At the time of writing, 50 - 100 m seem to be typical maximum distances to 'natural' targets.

Laser scanners are another type of instrument that measure distances to passive targets. In this case, the laser beam is deviated vertically and horizontally to scan the surrounding space in a grid pattern. The step interval can be selected. Some instruments can scan around the full circle (360°), others only in a limited sector. The typical results of a laser scan are the x, y, z coordinates of a large number of points 'seen' by the scanner. The precision of these coordinates depends on the precision of the angular measurements (directions, zenith angles) and the precision of the distance measurements. The range and accuracy specifications vary greatly between the different products, from ±0.5 mm at 5 m to ±50 mm at 1000 m at the time of writing.

Geomatic engineers and surveyors must consider the above trends and check if their current operations make the best use of current technology. If not, they may provide slower, more expensive or less sophisticated services to their customers. Also, geomatic engineers and surveyors must ensure that their personnel is competent in the use of the new technology. Although some basic principles of traditional instruments also apply to modern instruments, some new aspects arise. For example, do you know how to calibrate a rotating laser level or the electronic level sensor of an electronic tacheometer? Do you know why it is better to have diametrical circle reading on the vertical circle (rather than on the horizontal circle) of electronic tacheometers or on what kind of survey jobs the dual-axis level sensors (of electronic tacheometers) are most useful? Do you know the properties of the compensators used in automatic levels, digital levels and rotating laser levels? The answer to these and other questions can be found in this text.

2. Hand-Held Equipment

Hand-held instruments are used in many ways in geomatic engineering and surveying. For example, they may provide the traditional angle-angle-distance data with lesser accuracy but faster than electronic tacheometers. Such applications include reconnaissance surveys and surveys in support of land information systems or geographic information systems. On other occasions, a geomatic engineer or surveyor needs to measure short distances fast, such as in the case of building surveys. Finally, the ambient temperature, pressure and humidity is required in the connection with all electronic distance measurements. Electronic instruments are available for all these and other applications. Some types of instruments are briefly reviewed below.

2.1 Electronic 'Pocket Tapes'

The 'electronic pocket tapes' may replace the traditional steel pocket tapes and 30 m steel tapes. They do require a surface for the (passive) reflection of the transmitted beam. Because they measure the average distance to the 'foot print' at the target surface, they work best, if the entire area 'illuminated' by the beam (the 'foot print') is flat and at a right angle to the beam. Measuring to concave or convex corners of walls will not give the true distance. Also, any other objects in the beam between the instrument and the reflecting surface can cause a false reading (too short).

Two types are discussed further, one based on an ultrasound sensor, the other one based on the well-known principle of electronic distance measurement.

2.1.1 Ultrasound Sensor

The *Accutape-S ultrasonic distance estimator* (see Figure 2.1, on left) is one example of an ultrasound sensor. It can measure distances from 0.6 m to 13 m with a resolution of 1 cm or 1 inch. The precision is quoted as ±1% + 1 digit which is equivalent to ±(10 mm + 1000 ppm). It operates between 4°C and 38°C and weighs 57 g. The instruments uses an electro-acoustic transducer (made by Polaroid) to transmit and receive sound waves. The 'flight time' for a pulse to travel to the reflecting surface and back is measured. Knowledge of the speed of sound c permits to compute the distance d as follows:

$$d = \frac{(c \times \text{flight time})}{2} \qquad (2.1)$$

Schwarz (1985) did derive the following equation for the speed of sound c (in m/s):

$$c = 20.0533 \sqrt{\frac{T}{1 - 0.3780\,(e/p)}} \qquad (2.1a)$$

where T is the atmospheric temperature (in kelvin; = 273.15 + t), t is the atmospheric temperature in degrees Celsius (°C), e is the atmospheric partial water vapour pressure (in hPa) and p the atmospheric pressure (in hPa). The speed of sound is 325.30 m/s at –10°C and 354.86 m/s at +40°C, for example.



Figure 2.1: *Accutape-S* ultrasonic distance estimator (on left) and hand-held (electro-optical) laser meter *DISTO* by Leica (on right).

As the speed of sound depends greatly on the density of the medium (air), the *Accutape-S* is temperature compensated. Some systematic errors occur, however, with changes in pressure (altitude) and humidity. Sonic signals are not reflected by absorbing materials such as curtains, upholstery and carpets. Rough surfaces return an average distance. Because of the internal measurement of temperature (for the computation of the most appropriate speed of sound), the device must be given enough time to settle at the ambient temperature and should not be exposed to the sun or other heat sources.

2.1.2 Electro-Optical Sensor

As an example of an electro-optical sensor, the Leica hand-held laser meter 'DISTO' is discussed (see Figure 2.1, on right). The first DISTO model was released in 1994. The instrument is 235 mm long. That is much longer than the ultrasound device discussed above. It uses an visible laser diode distance meter to measure the distance to surfaces. This distance meter uses the same phase-measurement principle as most other electronic distance meters. (The unit length of the original DISTO is 3 m.) The range is quoted as 0.2 m to 30 m, without reflector. The resolution is 1 mm. Test measurements have established that all systematic errors (additive constant, periodic errors, scale errors) of the particular DISTO tested were well below the 2 mm level (Witte & Yang 1994). The fifth DISTO series was released in 2002. For the DISTO *lite*[5] and the *classic*[5], the operating range is listed as 0.2-200 m and the accuracy as ± 3 mm at 2σ (± 1.5 mm at 1σ). The display resolution is 1 mm below 100 m and 10 mm above 100 m. (Tests have shown that these two models are programmed not to measure distances longer than 200 m. Special target plates are required to achieve the maximum distance.)

The DISTO does not have an input facility for the atmospheric parameters. Like with all other electro-optical distance meters, the scale of the measurements does change at a rate of about 1 mm/100 m per 10°C change in atmospheric temperature and per 33 hPa change in atmospheric pressure. Whilst this might be ignored for distances of 0.2 m to 30 m, corrections might be appropriate for distances of 100 m. At temperatures higher than the reference ('standard') temperature of the instrument, distances are measured too short; a positive correction has to be applied. At pressures lower than the reference ('standard') pressure of the instrument, distances are also measured too short; a positive correction is required.

According to the manufacturer, the Leica DISTO measures the correct distance at 23°C, 953 hPa and 60% relative humidity. When ignoring the influence of humidity, the following correction equation can be derived from the standard conditions and the carrier wavelength of 635 nm given by the manufacturer:

$$d_{corr} = d_{meas} + \{(259.7 - \frac{80.91\ p}{T}) (10^{-6})\ d_{meas}\} \qquad (2.2)$$

where T is the atmospheric temperature (in kelvin; = 273.15 + t), t is the atmospheric temperature in degrees Celsius (°C), and p the atmospheric pressure (in hPa).

The visible laser diode projects a red dot onto the reflecting surface, so that the user knows exactly to what point the distance is being measured to. The range can be extended to 100 m (or 200 m for newer models) by using a (brown) target plate (made of reflective sheeting). As the laser dot cannot be seen by eye at longer distances, Leica sells a telescope attachment, which clips onto the DISTO and is held in place by magnets. Also, freehand operation may not provide a stable pointing at longer distances. DISTOs can be screwed onto camera tripods if better beam stability is required.

Since 1995, the instrument is available in some specialised versions, such as the Data DISTO RS232 for operation from computers for control measurements and as Data DISTO GSI for the attachment to the Leica electronic theodolites. In 1996, DISOFTmini followed. This data acquisition system links a DISTO to a penpad computer for the computer-assisted survey of buildings. A data transfer to CAD systems is possible.



Figure 2.2: Criterion hand-held Survey Laser by Laser Technology (on left) and Leica Locator (on right)

2.2 Hand-Held Angle-Angle-Distance Devices

A number of manufacturers provide binocular-type systems, that can measure the distance to a point as well as the magnetic bearing and the inclination of the corresponding line of sight. Such systems provide data similar to those of the electronic tacheometers, namely a slope distance, a horizontal angle (referenced against magnetic north in this case) and a vertical angle. In consequence, the horizontal distance and the height difference to a point can be calculated on-board. Together with the magnetic bearing, a three-dimensional positioning is possible. An RS-232 interface for the external storage and processing of the data is usually available.

Instrument	Criterion 300	LEM 300-W Laser Meter	Leica Locator	Laser Scout 1000-C
Distance				
Accuracy	±100 mm	±100 mm	±1 m	±200 mm
Minimum Distance	6 m		25 m	2 m
Range to Poles	275 m	<100 m		1200 m
Range to Buildings	455 m	300 m	1500 m	1500 m
Range to Triple Prism	12200 m	3000 m		3500 m
Measuring Time	0.3 s	???	0.3 s	0.5 s
Azimuth				
Accuracy	±0.3°	???	0.6°	0.2°
Measuring Time	1.0 s	???	0.2 s	???
Stabilisation	±15°(floating)	???	3-D sensor	±20°(gimbals)
Inclination				
Range	1x±60°	1x±65 grads	2x±45°	1x±60°
Accuracy	±0.2°	±0.1 grad	0.2°	0.1°
Measuring Time	0.75 s	???	???	???
RS-232 Port	yes	yes	yes	yes
Manufacturer	Laser Technology 7399 S Tucson Way Englewood Co 80112 USA	Jenoptik GmbH D-07739 Jena Germany	Leica Geosystems CH-9435 Heerbrugg Switzerland	Dr. Johannes Riegl Wiener Strasse 2 A-3580 Horn Austria

Table 2.1: Technical data of a selection of laser range finders

These hand-held instruments have many uses for mapping, profiling, estimating, sampling, volume, inventory, topographic, relocation and GIS/LIS measurements. They are often used to connect additional features to points which were coordinated by GPS techniques. Because the instruments measure bearings directly, no other points need to be visible, at least in principle. Specialised instruments have been designed for the timber industry. Having measured the distance to a tree, the instruments can easily determine the height (measure elevation angle to the top and the bottom) and the diameter (measure azimuth to left and right edge), after some trigonometric computations. Some application aspects are discussed by Carr (1992). Other versions of the same type of instruments permit the measurement of the velocity of objects, such as cars. Jenoptik, for example, supplies an instrument (Video-LAVEG Laser Velocity Guard) that measures speeds of 0 to 320 km/h (to 1 km/h) at distances up to 350 m and more. All particulars are overlaid on a video image of the scene for documentation purposes.

The key data of a selection of typical instruments is given in Table 2.1. Two specific instruments are depicted in Figure 2.2. All instruments use pulsed diode lasers for the distance measurements, usually operating in the near infrared (wavelengths of about 900 nm). The distance is derived from the flight time of the pulses to and from the reflecting surface (see Eq. (2.1)). The quoted distance range is for daylight measurements. At night, like with all other electro-optical distance meters, the range can be extended up to the double of the daytime range. Further information on pulse distance meters may be found in Rüeger (1990 1996). It should be noted that freehand operation of these devices may not be able to sufficiently stabilyse the beam on a distant target. In these cases, some support may be required to keep the beam on the target. The components used for the azimuth and the tilt measurements are discussed below in more detail.

2.2.1 Fluxgate Compass

All hand-held angle-angle-distance devices described above use so-called flux-gate compasses for the measurement of the magnetic bearing. This technology is not new; it has been used for many years in aircraft navigation. However, the flux-gate compasses have only recently become sufficiently small for inclusion in surveying instrumentation.



Figure 2.3: General construction of a flux detector (after Pallett 1972)

The flux-gate compass is a magnetometer which has been designed to determine the direction of the horizontal component of the vector of the earth's magnetic field. The design shown in Figure 2.3 has been the primary sensor design for more than 30 years. The flux sensor is usually gimballed so that it remains horizontal even if the host (or host vehicle) is tilted forwards and/or sideways. Naturally, the sensor has no degree of freedom about its vertical axis. To damp the vibrations induced by the host (or host vehicle), the sensor module is usually surrounded by a fluid ('floated'). The accuracy is typically 0.1°.



Figure 2.4: Path of the Earth's magnetic field through a flux detector and the signals induced in the pick-off coils on the three spokes (after Pallett 1972)

The primary coil generates an magnetic field (e.g. at 400 Hz) in the three spokes. The magnetic flux is carried by the upper and the lower part of the spokes. As the secondary (pick-off) coils include the forward and return paths of the induced magnetic flux, the total flux measured by the pick-off (at 800 Hz) will be zero in the absence of the Earth's magnetic field. As soon as the Earth magnetic field adds to the induced magnetic flux, the total flux through the secondary coil becomes non-zero and a voltage is generated in the pick-off coil due to electro-magnetic induction. The voltages from the three pick-offs are then combined to give the angle of the Earth's magnetic field with respected to the coordinate system defined by the three spokes. Figure 2.4 shows how the orientation of the flux gate sensor in the Earth's magnetic field changes the flux in the three spokes. A pick-off generates a maximum signal, when its measuring axis (spoke) is parallel to the Earth's field, and a minimum signal, when it is at right angle to it. In aircrafts, the flux detector elements were connected to the heading indicator in the cockpit. For hand-held instruments, the pick-off voltages have to be digitised and processed further by the on-board computer.

The traditional flux gate compasses are relatively large and heavy and must be stabilised in a horizontal plane. The gimbals or pivots used for the latter purpose restrict the allowable along- and across-tilts of the device. Rather than stabilise the traditional two-dimensional sensor in a horizontal position, it is possible to use a triad of three orthogonal single-axis flux gate sensors. Such a triad can measure the three components of the Earth's magnetic field in the case coordinate system. To derive the bearing of the sensor's case in a horizontal plane, the along- and across-sensor tilts must be measured. (The traditional flux-gate compass does not require this additional information as such. But in combination with the distance meter, at least the tilt in the forward direction must be measured anyway.)



Figure 2.5: Principle (on left) and possible design (in middle) of a planar parallel-gated fluxgate sensor (after Vincueria et al. 1994). On the right, the three-dimensional digital magnetic compass (DMC) designed by Leica for their 'Vector' and 'Geovid' hand-held devices (after Leica 1995).

Figure 2.5 shows the basic principle a possible design on the left (Vincueria et al 1994). The (planar) induction coil is sandwiched between two (planar) exciting coils. Two cores made from amorphous low magnetostrictive ribbons are placed between the layers with the coils. In the absence of an external magnetic field, the induction coil would register a total flux of zero, which means that no induction would occur. The diagram in the middle of Figure 2.5 shows a practical design with four exciting coils (Numbers 2 to 5) and two secondary (pick-off) coils (Numbers 1 and 6) (Vincueria et al 1994). Leica does manufacture a three-axis flux-gate sensor (Digital Magnetic Compass, DMC) triad for their binocular based measuring systems. The device is specified to operate at along- and across-tilts of ±35°. Two integrated inclination sensors determine the two components of the dislevelment of the sensor and correct the sensor reading in real-time.

2.2.2 Clinometers

Most manufacturers of hand-held angle-angle-distance devices are not specific about the tilt sensors used. All instruments require a clinometer reading in direction to the target for the reduction of the measured slope distances to horizontal. The instruments which use a triad of single-axis flux sensors require an additional tilt sensor for the measurement of the cross tilt for the correction of the azimuth readout.



Figure 2.6: Plan view of an electrolytic level sensor.

Only Riegl quotes a 'high-quality electrolytic level sensor' with a measuring range of ±60° and a resolution of 0.1°. Figure 2.6 shows the basic design of such a sensor. The electrolytic level sensors resemble the plate levels in theodolites. The glass vials are filled with an electrolyte, which is conductive. If the air bubble is centred, both differential electrodes will be covered equally by the liquid. This means that the current in both leads will be the same. If the bubble moves to one side, one differential electrode will carry a larger current than the other. The difference between the two currents is a measure of the tilt. As an alternative, the readout electronic can be based on the differential change of the capacitance.

All tiltmeters and clinometers have a number of errors requiring calibration or adjustment. The most important corrections are the additive constant (for the zero error) and the scale correction (for the vertical-angle-dependent (linear) error). The former can be easily tested by the user through the measurement of the *same* slope, forward and backward. The latter requires a comparison against true slopes and is less easily established. Errors in the additive constant of the clinometer can be eliminated in the field by measuring the *same physical slopes* (or height differences) in both directions and by taking the mean.

2.2.3 Use of Hand-Held Angle-Angle-Range Devices

The hand-held angle-angle-distance devices are promoted for the measurement to non-cooperative targets such as poles, trees, bushes, houses etc. It is clear that the measurement accuracy of the devices cannot be realised if the dimensions of the object are larger than the measurement accuracy. All distances are measured to the closest surface (on the object), and not to the centre of the object. Also, one has to make sure that the foot print of the laser beam falls fully onto the object. If a number of objects are 'hit' by the beam, the instrument may display an average distance.



Figure 2.7: Equipment used by the Forest Service of the US Department of Agriculture for the reconnaissance surveys of single lane, low-use roads. (after Moll 1993)

The fluxgate instruments can be used to build up survey networks as it was done in the past with magnetic compasses. The compass traverses are well known. The definition of the forward, backward and instrument stations becomes very important, if measurements from different stations are to be linked. Figure 2.7 shows some ancillary equipment trialed by the Forest Service of the US Department of Agriculture for the survey of forest roads. The use of (supporting) poles at the instrument and the target stations, and the use of (plastic) reflectors, ensures that the marked points can be re-occupied with an accuracy that is better than that of the final product. The data are recorded for later processing on a personal computer. The reflector rod carries a target plate at the same offset as the telescope above the distance meter. Equal instrument heights and reflector heights ensure that the forward and backward elevation differences are compatible. Having an 'active' reflector and a well defined instrument station (on rod) and target (on rod) delivers the best accuracy in all three components.

All types of flux-gate compasses make use of the Earth's magnetic field to obtain orientations (magnetic bearings). In consequence, they are subject to the same effects as the older magnetic compasses. If the measured orientations are to be referenced against true north (geographic north), then the value for the *magnetic declination* (the angle between the true north (TN) and the magnetic north MN) must be considered. The declination value must be current for the time and location of the measurement site. Most instruments have a facility to enter this value. The problem is that the Earth's magnetic field is not constant. It is well known that the magnetic declination is subject to a secular (long-term) variation, a diurnal variation (periodic error over one day) of about 8 minutes of arc, an annual variation (periodic error of less than one minute of arc) and to irregular variations due to magnetic storms. The latter can reach one degree or more. In 1970, the magnetic declination was 11.50 degrees in Newcastle (NSW) and the secular variation +1.7 minutes of arc per year (Finlayson 1973). In Carnarvon (WA) and again for 1970, the values were –1.15 degrees and –1.1 minutes per year, respectively.

If the measured orientations are to be referenced against the grid north (GN) of a map projection, then the *grid convergence* (the angle between the true north (TN) and the grid north, GN) has to be considered in addition. In practice, it might be easier to calibrate an angle-angle-distance device on a few lines of known azimuth or bearing, depending on requirements.

Less predictable are local disturbances of the magnetic field. These 'local attractions' fall into two categories, namely those due to the station environment and those introduced by the observer. The magnetic field at a particular set-up is affected by metallic objects in close proximity (such as passing or stationary cars, transmission line towers, steel street light poles, steel structures, reinforced concrete structures, to give just a few examples), mineral deposits and direct currents. The errors caused by these objects are not predictable, but are constant at a particular point. Measuring bearings forward and backwards on lines allows to detect station specific errors, unless both end points are affected. The interference caused by the observer, such as from the metal frame of glasses, the watch, the buckle of a belt, the keys and/or the pocket knife will be constant for a particular observer (if the readings are always taken the same way). The measuring devices can compensate for these errors, either as part of the declination or as a separate entry.

The problem of local disturbances should not be underestimated. In urban areas, for example, it would be extremely difficult to obtain correct magnetic bearings. In these cases, where local disturbances are unavoidable, the measured bearings can be processed as measured directions, as all bearings observed from one station would be wrong by the same amount.

2.3 Electronic Barometers (and Altimeters)

Electronic (or 'digital') barometers have two main uses in geomatic engineering. Firstly, they can be used to measure the atmospheric pressure required for the reduction of electronic distance measurements. In this case, a read-out in hectopascal (hPa, previously known as millibar, mb) or in another pressure unit is required. Secondly, barometers double as altimeters, in which case a read-out in metres (or in another length unit) is required.

2.3.1 Working Principles

All electronic barometers are built around a pressure sensor with its associated analogue and digital circuits. The devices feature on-board computers for the conversion between different units, the corrections for the calibration values and the computation of the elevations from the measured absolute pressure. The most common sensor principles are now outlined.

2.3.1.1 Vibration Pressure Sensor

Vibration pressure sensors make use of the change in the resonance frequency of, typically, a quartz beam or a metallic cylinder under varying load. They are the most accurate of the three sensor types discussed here. Figure 2.8 shows one implementation of each type. In the vibrating quartz sensor, a quartz beam is placed in an oscillator circuit and is made to oscillate at its fundamental resonance frequency by piezoelectric means. This quartz beam is compressed by a lever arm which moves with the pressure in the steel bellows. The changing force on the vibrating beam causes a change in the resonance frequency. The frequency of the oscillator circuit follows this varying resonance frequency. In consequence, the changes in the oscillator frequency become a measure for the changes in the atmospheric pressure in the bellows. The frequency can be measured as in frequency counters.

Vibrating beam pressure sensors show a good repeatability and very small hysteresis effects. (Hysteresis is present if the pressure reading at a particular pressure is different depending on the pressure being reached by a pressure reduction or by a pressure increase. In the presence of hysteresis, the pressure reading is, slightly, dependent on the preceding pressure trend.) As with frequency counters, the resolution can be increased by increasing the length of the counting interval. Because quartz crystals change their resonance frequency also with temperature, the resonance frequency of a second (equivalent) quartz is monitored for temperature compensation purposes. The long-term stability is quite good. The vibrating quartz beam pressure sensors can be classified as precision pressure sensors (Sudau 1994).



Figure 2.8: Two vibration pressure sensors. An oscillating quartz sensor (made by Paroscientific) is shown on the left and a oscillating cylinder sensor (made by Solartron) on the right. (after Sudau 1994)

The vibrating cylinder pressure sensor has a NiFe cylinder as a sensor element. A vacuum is present between the outer shell and the metallic cylinder. The drive coil causes the cylinder to vibrate at its resonance frequency. The pick-off coil is used to monitor the vibrations of the cylinder wall and to synchronise the frequency of the drive coil (in a feed-back loop). The inside of the cylinder is exposed to the pressure to be measured. As with the quartz sensor, the resonance frequency is measured and converted to the corresponding pressure by the on-board computer. The vibrating cylinder devices feature a very good repeatability, a small hysteresis and small long-term drifts. They are basically insensitive to accelerations but are susceptible to humidity (Sudau 1994). As the humidity enters into the cylinder, it is in contact with the inside of the cylinder and the drive and pick-off coils and, thus, may alter the readings.

2.3.1.2 Capacitive Pressure Sensor

The capacitive sensors are based on the principle of a capacitor, where a change in the width of the gap between the two electrodes causes a change in capacitance. Capacitive sensors are, typically, less accurate than the vibration sensors. In the case of a pressure sensor, one electrode is fixed whereas the other one is exposed to the pressure to be measured. Figures 2.9 and 2.10 show the arrangement used in the AIR-HB-1A hand-held digital barometer/altimeter. The device uses a dual-diaphragm, aneroid pressure sensor. It is highly sensitive to pressure changes and has a low susceptibility to shock and vibration. The dependence on temperature is small, almost linear and, thus, easily calibrated.

Figure 2.9 shows the two NiSpan-C diaphragms on opposite sides of a ceramic disk. The inside of the sensor is in vacuum. The two capacitors are electrically in parallel. Mechanically, they are differential. This back-to-back arrangement provides large capacitance changes in function of pressure and low susceptibility to vibrations and shocks. The sensor is placed in an oscillator circuit, the frequency of which varies with the applied pressure. For error compensation purposes, a high and a low reference capacitor and a temperature sensitive capacitor are also switched sequentially into the oscillator circuit. The frequency measured with each of the four elements is then used by the microprocessor to derive the pressure reading. The transfer function, calibrated during manufacturing, provides the temperature compensated pressure and the elevation reading (Whitaker & Call 1987; Pike & Bargen 1976; Pike et al. 1983; Whitaker & Call 1986; Pascoe & Rüeger 1989).



Figure 2.9: Capacitive pressure transducer of the AIR-HB-1A hand-held digital barometer/altimeter (after Pike et al. 1983)

According to Sudau (1994), capacitive pressure sensors feature a good resolution, a good repeatability, a good long-term stability and a good dynamic behaviour. The non-linearity between pressure change and capacitance change can be compensated by the microprocessor. The susceptibility to temperature can be calibrated and corrected for by the on-board microprocessor. See Pascoe & Rüeger (1989) for some test data.


DIAPHRAGM
SUBSTRATE
CERMET ELEMENT CONNECTION
DIAPHRAGM CONNECTION

Figure 2.10: Dual-diaphragm, capacitance, aneroid pressure sensor of the AIR-HB-1A hand-held digital barometer/altimeter (after Whitaker & Call, 1987)

2.3.1.3 Piezo-Resistive Pressure Sensor

The piezoresistive sensors are the least accurate of the three types of sensors discussed here. They consist of a silicon membrane on a silicon substrate. A vacuum exists between the membrane and substrate. On top of the silicon membrane, four resistance sensors (strain gauges), in cardinal directions, are implanted. The strain gauges are connected in a Wheatstone bridge circuit. A change in the pressure causes a strain in the silicon membrane. This changes the resistance of the four gauges through changes in the specific resistance of the semiconductor material and yields a bridge voltage which is proportional to the applied pressure.


Pressure Inlet
Diaphragm
Case
Pressure Sensor
Piezoresistive Resistors
Membrane
Vacuum Cell
Elastic Support

Figure 2.11: Construction of a piezoresistive pressure sensor (after Sudau 1994)

The silicon chips can be as small as 4 x 4 mm, with a membrane thickness of 25 micrometres and a membrane diameter of 3 mm. As shown in Figure 2.11, the measuring chip is not directly exposed to the pressure to be measured. The external pressure is applied to an outer membrane ('diaphragm' in Fig. 2.11), which pressurises the oil inside the device. The oil applies the pressure to the silicon chip. The simple construction of piezoresistive sensor, together with their long service life and their miniaturisation, have lead to a multitude of applications in a number of fields. The temperature sensitivity of the resistance measurement is largely eliminated by the bridge circuit with the four strain gauges. The temperature dependence of the pressure reading must be compensated by other means.

2.3.2 Performance of Digital Barometers

Sudau (1994) summarised the performance of the three types of sensors discussed earlier. Sudau's table is reproduced in Table 2.2 in modified form. Rather than give the performance data in percent of the full scale (measuring range) of the devices, they have been converted to hPa by assuming a range from 600 to 1100 hPa (full scale = 500 hPa) for the devices. The performance as an altimeter can be estimated from the vertical lapse rate of the atmospheric pressure of about 1 hPa per 10 m.

The vibration sensors are intrinsically digital devices (frequency output) whereas the other two types are analogue devices, which require analogue to digital conversion. Most devices designed for outdoor use and having a display for the pressure (and elevation) readings seem to be of the piezoresistive and capacitive kind. Other devices provide the data only through a serial (RS232) computer interface and, thus, must be connected to a personal computer for the readout of the pressure or altitude.

Specification	Type of Sensor		
	piezoresistive	capacitive	vibration
Resolution (hPa)	~0.1	<0.03	>0.000025
Linearity (hPa)	<2.5	<0.25	0.03
Repeatability (hPa)	0.15–2.0	<0.10	<0.03
Hysteresis (hPa)	0.15–0.5	<0.10	<0.03
Overall Accuracy (hPa)	~2.5	0.10	0.05
Long-term Stability (hPa/year)	2.5-8.5	0.25-0.50	<0.05

Table 2.2: Performance data of three types of pressure sensors (after Sudau 1994)

The specifications of some self-contained hand-held barometer/altimeter devices are given in Table 2.3. The data have been taken from the respective instrument brochures. Prices start from about AUS $350 and are, typically, lower than the prices of a mechanical aneroid barometer/altimeter of equal precision.

Manufacturer	Eschenbach Optic Germany	Atmospheric Instrument Research (AIR) USA	Thommen Switzerland	Väisälä Finland
Model	6941 Alpin EL	HB-1A	Altitronic Professional	PA 11
Range (m)	-500 to 10000	-700 to 4200	-700 to 10000	
(hPa)		600 to 1100	250 to 1100	800 to 1050
Resolution (m)	0.5	0.1	1	
(hPa)	0.1	0.1	0.1	0.1
Tolerance	±8 m	±0.5 hPa	±1.0 hPa ±10m (>500m) ±2m (<500m)	±0.3 hPa
Temperature Range (°C)	-20 to +50	5 to 40 (Option: -25 to +50)	-30 to +60	+5 to +55
Temperature output	no	no	yes (Pt-1000) ±0.3°C	no
Sensor	?	1x capacitive	1x piezoresistive	3x capacitive
Weight (g)	?	280	170	1700
Size (mm)	?	30x91x145	131x68x25	72x144x250
Supply Voltage (V)	?	9	9	4.8

Table 2.3: Specification of some commercial hand-held barometers and altimeters

2.3.3 Heighting with Digital Barometers/Altimeters

Based on the height formula for a standard atmosphere, the microprocessors of digital barometers can easily compute and display elevations. Kahmen & Faig (1988, Eq. 11.7.2) give the following formula for the height H (in metres) in a standard atmosphere:

$$H\,(m) = \frac{T_o}{a}\left(1 - (p/p_o)^{1/n}\right) \qquad (2.3)$$

where
$n = 5.256$
p_o = mean sea level pressure = 1013.25 hPa
T_o = mean air temperature at sea level = 288 K (~15°C)
a = vertical lapse rate of temperature = 0.0065°C/m

Substitution in Eq. (2.3) of $T_o = 288.15$ K and other numerical values as given above leads to the following equation used by Atmospheric Instrument Research (AIR) for their HB-1A barometer/altimeter:

$$H\,(m) = 44330.77\,\left(1.0 - \left(\frac{p}{p_o}\right)^{0.19026}\right) \qquad (2.4)$$

where p (in hPa) is the pressure measured at the elevation H. The above equation is based on many assumptions, namely that the temperature at the mean height (H/2) is $\{T_o - a\,(H/2)\}$, the humidity is zero, the mean gravity is equal to g_o and that the sea level pressure is indeed p_o. These conditions are usually not fulfilled. In consequence, correction formulæ have been used in the past to compensate for the deviation of the real atmosphere from the standard one in the computation of barometric height differences. Details on these formulae may be found in sections on barometric heighting in surveying textbooks. (See Kahmen & Faig, 1988, Sect. 11, for example.)

Practical tests have shown that a simple interpolation (proportional to the height difference) of the barometric heights between the points of given elevation can provide quite accurate elevations when using electronic barometers. The interpolation formula is given by Kahmen & Faig (1988, Eq. 11.7.7) as follows;

$$H_i - H_A = (H_E - H_A)\,\frac{h_i - h_A}{h_E - h_A} = \Delta H_{A\text{->}E}\,\frac{\Sigma\Delta h_{A\text{->}i}}{\Sigma\Delta h_{A\text{->}E}} \qquad (2.5)$$

where $\Sigma\Delta h_{A\text{->}i}$ is the measured elevation difference from the starting Point A to a Point i, $\Sigma h_{A\text{->}E}$ the measured total elevation difference between the fixed Points A and E and ΔH the given elevation difference between the fixed Points A and E.

Lechner el al. (1987) reported on a test of motorised levelling with three different electronic barometers/altimeters (two types of piezoresistive devices) in two networks. (The speed of travel was about 30 km/h between set-ups.) The first network featured height differences of 20 to 80 m over 5 to 12 km, the second one a height difference of 250 m over 6 km. The root mean square error of the interpolated barometric heights were, on average, ±0.4 m and ±1.0 in the first and second network, respectively. The worst errors in the interpolated heights did not exceed 1.1 m and 2.8 m in the first and second network. Sudau (1994) quoted results of the interpolation method in barometric heighting with the more precise vibrating quartz beam instruments. A height precision of ±0.06 m was achieved between bench marks 450 m apart and over a height difference of 43 m. It follows that barometric levelling (motorised or otherwise) with digital barometers is a powerful and simple method, particularly if points of given heights are available at the edge of the area to be surveyed.

The interpolation method is based on the assumption that the atmospheric pressure does not change with time. Unfortunately, this is usually not the case. Even in stable weather conditions, the pressure falls by about 3 hPa between 9 h and 15 h and rises a similar amount between 15 h and 9 h on the next day. A smaller rise and fall occurs during the night and early in the morning (Bureau of Meteorology 1990). Considering a pressure change of 1.145 hPa per 10 m height difference (at 500 m above sea level), this diurnal pressure change translates into a 'change' of 26 m in the altimeter reading. (At 2500 m above sea level, the lapse rate of pressure is 0.9428 hPa per 10 m.)

Larger pressure changes occur during weather changes. When a high is moving away or a depression is approaching, the pressure can easily drop by more than 7 hPa over 24 h (Bureau of Meteorology 1990). This is equivalent to a change in the altimeter reading of 74 m (at 500 m above sea level). The interpolation method with a single altimeter is therefore only appropriate during stable weather conditions and over short periods of time. Best results are achieved on uniform slopes and when starting and finishing on points with given heights at the highest and lowest points of the height 'traverse'. Naturally, changes of pressure due to weather can be monitored by a second, stationary barometer if the barometric levelling extends over a longer period of time.

If given elevations are not available at both ends of a barometric heighting run, then the normal formula of barometric heighting and the normal observation procedures should be employed. The latter includes the use of a stationary barometer to monitor the changes, due to weather, of the atmospheric pressure with time. Refer to textbooks (e.g. Kahmen & Faig 1988) for full details.

2.4 Exercises

2.1 The measurements taken with the Accutape-S ultrasonic distance 'Estimator' are corrected internally for temperature. It is assumed that these devices are calibrated for 20°C, sea level pressure (1013.25 hPa) and zero humidity.
(a) Investigate the error in a 30 m distance measured at +35°C and 100% relative humidity (56 hPa partial water vapour pressure).

(b) What is the error in a distance of 100 m measured at 20°C at an altitude of 3000 m?
Hint: Consider Eqs. (2.1), (2.2) and (2.4).

2.2 Discuss the relative merits of ultrasonic, electro-optical and steel 'pocket tapes' for the three-dimensional (length, width, height) measurement of the internal size of rooms and buildings.

2.3 The Leica 'DISTO' *classic*[5] measures distances correctly at 23°C and 953 hPa. The instrument is accurate to ±3 mm at these conditions.

(a) What error would you expect in a 100 m distance measured at +30°C and 890 hPa?

(b) Would you correct the instrument reading in any way? Why?

2.4 The manufacturer of the Criterion 300 hand-held 'Survey Laser' (angle-angle-range device) specifies the distance accuracy as ±100 mm, the bearing accuracy as ±0.3° and the vertical angle (inclination) accuracy as ±0.2°.

(a) At what range does the accuracy of the computed height difference reach ±100 mm? (Assume a horizontal line of sight.)

(b) At what range does the accuracy of both components (Easting and Northing) of the horizontal coordinates (computed from bearing and horizontal distance) of a target point attain ±100 mm? (Assume a point due East or due North from the instrument station.)

2.5 You have been asked to map (in the Map Grid of Australia 1994, MGA94) a stand of old trees on a development site. Four survey marks with given MGA94 eastings and northings are available on the site. You are using a hand-held angle-angle-range device with a flux gate compass for the purpose. How do you get the MGA94 bearings (required for the calculation of the coordinates) from the measured magnetic bearings?

2.6 You have been asked to determine the height and the diameters of the stem and spread of some trees with a hand-held angle-angle-range device.

(a) What do you measure, exactly, to each tree?

(b) How do you calculate the required tree dimensions? Derive the necessary formulae!

(c) What precision of the three elements would you expect when using a Leica Geovid at 50 m from the tree?

2.7 Standing on a survey mark, *you* measure the height difference to the top of a power line pole with a hand-held binocular based angle-angle-range device similar to the one shown in Figure 2.2 (on right). The height of the survey mark is 238.44 m above sea level (Australian Height Datum 1971, AHD71). The height difference between the device and the top of the pole is displayed as –45.6 m. What is the AHD71 height of the top of the pole?

2.8 You have mounted a reflector on a ranging rod at a height above ground which corresponds to your eyelevel. You stand on a Mark A. Your assistant holds the ranging rod on Mark B. You read a vertical angle of +10.8° with a binocular based angle-angle-range device. You then move to Mark B and your assistant to Mark A. From B, you measure the vertical angle from B to A as –12.2°C.

(a) What do you conclude?
(b) What would you do next?

2.9 List and discuss those variations of the magnetic field of the Earth which affect the magnetic bearings measured with flux-gate compasses.

2.10 The vibrating cylinder pressure sensors are said to be susceptible to humidity, whereas the vibrating quartz beam sensors (of equal precision) are not. Based on the Figures 2.8, explain the reason for this difference.

2.11 Compare the practical results of the interpolation method in barometric levelling with digital barometers/altimeters reported by Lechner (1987) and Suday (1994) with the performance parameters of the respective devices. What performance parameter corresponds best with the test results?

2.12 The motorised barometric levelling with one digital altimeter was used to determine the elevations of a number of points along a road. Given the 'true' heights of the Point 40 and the Point 51, compute the elevations of the Points 41 to 50.

Point	Given (m)	Measured (m)	Adjusted (m)	Point	Given (m)	Measured (m)	Adjusted (m)
40	256.85	251.7	256.85	46		456.7	______
41		292.6	______	47		484.3	______
42		327.3	______	48		513.9	______
43		351.8	______	49		545.2	______
44		390.1	______	50		561.5	______
45		421.4	______	51	586.28	573.3	586.28

2.13 Barometric levelling was executed with a digital barometer along a forest road. Compute the elevations of the Stations 61 to 65 based on the given elevations of Stations 60 and 66.

Point	Given Elevation (AHD) (m)	Measured Pressure (hPa)	_______ ___	Adjusted Elevation (AHD) (m)
60	1946.75	799.2	______	1946.75
61		789.7	______	_______
62		785.2	______	_______
63		780.8	______	_______
64		774.9	______	_______
65		770.1	______	_______
66	2339.42	760.5	______	2339.42

3. Levelling Equipment

3.1 Digital Levelling Instruments

3.1.1 Introduction

Digital levelling instruments ('bar code levels') were introduced in 1990 by the surveying equipment manufacturer Wild (now Leica) of Switzerland. Two other manufacturers (Topcon and Zeiss) released digital levels in 1994. Sokkia followed in 1998. Each of the manufacturers uses a proprietary design of the bar code graduations on the respective staff, so that staffs cannot be interchanged between instruments of different manufacturers. Digital levels simplify the traditional levelling by not having to read the levelling staff through the telescope and permit electronic data recording. In consequence and because larger sighting distances can be used in non-precise levelling applications, digital levelling instruments have made levelling faster. However, levelling with digital levels is still labour intensive as somebody has to operate the instrument and somebody has to hold the staff.

Considering the wide-spread use of one-person rotating laser levels on building and construction sites (discussed in the next section) and the replacement of line levelling by EDM-Height Traversing (Rüeger 1995, Rüeger & Brunner 1981) with electronic tacheometers in all but high precision 'levelling' applications, the traditional use of levelling instruments is likely to decline. The largest use of digital levels may well be in precise levelling applications in geodesy and engineering (e.g. monitoring of structures and machines) as the other possible applications are likely to be taken over by more efficient techniques.

In 2003, one manufacturer (Topcon Japan) offers three models of digital levels, two manufacturers (Leica (Wild) Switzerland, Trimble (Zeiss)

USA/Germany) offer two instruments each, and one manufacturer (Sokkia Japan) offers one. The manufacturers that sell at least two models, provide one or more for normal levelling (with fibre glass, aluminium or wooden staffs) and one for precise levelling (with invar staffs).


DiNi
1 DATA TRANSFER
2 SET INSTR. PARAM.
3 SET REC. PARAM.
ESC
YES
MENU INFO DISP
PNr REM EDIT
RPT INV INP
ON/OFF
DIST MEAS

Figure 3.1: Zeiss (Trimble) DiNi10 digital levelling instrument (on left) and Zeiss bar code (on right)



Figure 3.2: Topcon DL-102 digital levelling instrument (on left) and Topcon bar code (on right)

The precision listed by manufacturers for 1 km double run levelling (after the German DIN Standard 18723) with the less accurate instruments (and the corresponding (normal) bar code staffs) is as follows:

Leica DNA10 $s_{1\text{km double run}} = \pm 1.5$ mm
Sokkia SDL30 $s_{1\text{km double run}} = \pm 1.0$ mm

Topcon DL-102 $s_{1km\ double\ run}$ = ±1.0 mm
Topcon DL-103 $s_{1km\ double\ run}$ = ±1.8 mm
Wild NA2002 $s_{1km\ double\ run}$ = ±1.5 mm (now Leica)
Zeiss DiNi20/21 $s_{1km\ double\ run}$ = ±1.3 mm (now Trimble)

The precision listed by manufacturers for 1 km double run levelling (after the German DIN Standard 18723) with the more accurate instruments (and the corresponding invar bar code staffs) is as follows:
Leica DNA03 $s_{1km\ double\ run}$ = ±0.3 mm
Topcon DL-101/C $s_{1km\ double\ run}$ = ±0.4 mm
Wild NA3003 $s_{1km\ double\ run}$ = ±0.4 mm (now Leica)
Zeiss DiNi10/11 $s_{1km\ double\ run}$ = ±0.3 mm (now Trimble)

3.1.2 How do Digital Levels Differ from Conventional Automatic Levels?

3.1.2.1 DC Power

When using invar staffs, having no power means that no readings can be taken. When using non-invar staffs (like sectional fibre glass staffs), the digital levels can still be used as a normal level as the non-invar bar code staffs have a normal graduation on the back.
Having no power also means that no data recording is possible. It is evident that enough charged batteries must be taken into the field if no loss of time is to take place because of a lack of power.



Figure 3.3: Sokkia SDL30 digital levelling instrument (on left) and Sokkia bar code (on right)

3.1.2.2 Staffs

Digital levels require special bar code staffs, which are make specific. The staff and the digital level must be of the same make. Normal bar code staffs are made from fibreglass, aluminium or wood and have normal graduations on the back face. They are usually sectional or folding staffs. Invar bar code staffs do not have a normal staff face on the back. The invar ribbon is typically mounted inside an aluminium frame which has a steel base plate at the bottom.

3.1.2.3 Electronic Staff Reading and Distance Measurement

Digital levels not only measure the staff reading but also the distance between the instrument and the face of the staff. The latter is measured with an accuracy of a few centimetres. Both values are displayed on the read-out screen.

The electronic reading is non-personal and faster and allows to change the units of measurement between metres and feet very easily (No need to change the staff as in the past!) and the resolution of the readings can be selected.

3.1.2.4 Illumination of the Staff

The illumination of the staff is more important than in the past, as the electronic measurement requires a good contrast. An artificial (warm) light source is required for indoor or poor light conditions. (The early Wild (Leica) and the Sokkia instruments use only the infrared image of the staff for the processing.) It has been found that problems occur when observing against a bright background, against the sun and in the case of shadow patterns on the staff.

3.1.2.5 Compensator

In 1995, all digital levels are equipped with compensators similar to those in the classic automatic levels where the entire optical path of the telescope is deviated. Electronic level sensors (similar to those in electronic theodolites) could be used, but this would no longer permit the use of the instrument as a normal automatic level.

3.1.2.6 Optical or Electronic Horizontal Circle

Most bar code levels have an internal or external circle for rough angular measurements. This circle is typically read by eye as in traditional automatic levels.

In 1995, Zeiss did release a digital level with an electronic horizontal circle reading (*'Total Level Station'* DiNi10T) where the directions are measured to 6" and the distances to 1 cm/10 m. In this case, the instrument can be used for detail and contour surveys like electronic tacheometers, as long as the ground is reasonably level. It is to be noted that correct pointing to the centre of the staff is then essential as is the set-up of the staff exactly in the centre of the staffs base plate. Strictly speaking, the distance is measured to the front of the staff whereas the (fibreglass) staff is usually set-up in the centre of its cross-section.

3.1.2.7 Electronic Data Recording

This is the most important advantage of digital levels. Electronic booking speeds up the measuring process and avoids booking errors. Also, no additional person is required as 'booker'. The electronic data can be recorded on the following media, depending on instrument:

Removable memory cards: These cards may be make specific or may be PC cards, formerly known as PCMCIA-cards (**P**ersonal **C**omputer **M**emory **C**ard **I**nternational **A**ssociation). The latter may be read by inserting them into a PCMCIA port of a computer. The former need an additional memory card reader for the up or down loading of the data.

Internal (RAM) Memory: with RS-232 port for the up and down loading of data.

Hard Disk of External Notebook Computer: linked to the instrument via a RS-232 port.

3.1.2.8 Computer Interface

All digital levels feature an two-way RS-232 port for the up and down loading of data and/or the remote operation of the digital level from a computer.

3.1.2.9 Real-Time Correction of Instrument Errors

Having the measurements in electronic form and a computer on board makes it possible to correct instrumental errors by (real-time) computation rather than by physical adjustment. This requires that the instrumental errors be determined by the manufacturer and/or the user, stored in a non-volatile memory on board the instrument and removed from the raw observations by computation, prior to displaying and recording the measurements.

The manufacturers provide on-board program routines which guide the user through the determination and storage of user accessible instrument corrections, such as the (vertical) collimation error. Other on-line error corrections are only accessible to the manufacturer. This may include corrections for temperature dependent effects, which are corrected on the basis of an internally measured temperature.

3.1.2.10 On-Board Computing

The powerful computers on-board digital levels can be programmed to assist with some calculations which were previously done by hand. Manufacturers may provide on-board programs in support of:

Line Levelling: For example, carrying forward of elevations from a starting point, summation of backsight and foresight distances, height transfer to intermediate sights.

Two-Peg Test: Calibration, storage and correction for the vertical collimation error.

Users should note, that **it is impossible to adjust or calibrate the collimation error of digital and other automatic levels without error**. The two-peg test gives the collimation error at a particular instant and temperature only. The collimation error changes all the time. Experiments have shown changes of 8" between two set-ups and changes of 1" per °C! Digital levels were found to be more sensitive to temperature changes than optical automatic levels.

3.1.3 Principle of the Wild (Leica) NA200x/300x Instruments

As the WILD NA2000 was the first digital levelling instrument (released in 1990), it will be used to introduce the principle of operation of such instruments. Other makes of digital levels do employ slightly different procedures for the decoding of the bar code staffs. Most operational aspects are the same, however. The principle of the Topcon digital levels is explained in Rüeger (2000) and that of the Zeiss (Trimble) digital levels in Feist et al. (1995), for example.



Figure 3.4: Wild NA2002 digital level (on left), Leica DNA03 precision digital level (on right), Leica fibre glass staff (in middle) and Leica invar staff (under the instrument on the left)

3.1.3.1 Basic Design and Working Principle

The digital level Wild NA2000 by Leica uses the same optical and mechanical components as a traditional automatic level. (For example, the compensator is the same as in the Wild NA2 and NA24 automatic levels.) In consequence it can also be used like a conventional automatic level. Figure 3.5 shows the main components of this digital level. The image of the staff's bar code is deviated onto the detector array by the beam splitter. The beam splitter doubles as an optical filter which deviates the infrared part of the spectrum onto the detector. The maximum sensitivity of the Silicon detector is in the near infrared. The visible part of the spectrum proceeds to the reticule of the level.

The linear detector array is 6.5 mm long and features 256 pixels. The spacing and the size of the pixels is 25 μm. The viewing angle of the telescope is about 2 degrees. At the shortest measuring distance of 1.8 m, a 70 mm long staff section is projected onto the array. At the maximum measuring distance of 100 m, the detector array sees a staff section of 3.5 m length. (This arrangement is quite different from that in the Zeiss DiNi10/20 levels, where only 15 cm above and 15 cm below the line of sight are used for the measurement.) It should be noted that the *white code elements* are detected and used in the processing. They produce a light pattern on the photodiode array; the black lines become the gaps between recorded signals.

The focussing and pointing to the staff is manual. The position of the focussing lens is a measure of the distance to the staff and is recorded by a linear encoder. The focussing lens travels about 14 mm within the focussing range from 1.8 m to 100 m. The position of the compensator is checked by a monitoring system. This compensator monitor generates an error message whenever the compensator is outside its specified operating range. This check ensures that the instrument is levelled with the spot bubble before measurements are taken. The linear photodiode (CCD) array converts the received bar code image into an analogue video signal.



Figure 3.5: Schematic cross section through the Wild NA2000 digital level. The parts are described in the text. (after Ingensand 1990)

A block diagram of the electronics of the instrument is shown in Figure 3.6. A micro-processor performs the real-time image processing required. For the computation of the correlations the processor is supported by a gate array. The read-out electronic amplifies and digitises the video signal. It uses an 8-bit analogue-to-digital converter which provides 256 grey values for each of the 256 pixels.

3.1.3.2 Measuring Sequence

After pressing the measuring button, the position of the focussing lens is read and the proper functioning of the compensator is checked. The integration time for the image recording is selected according to the measured signal intensity. The image of the bar code on the photo diode array is then measured and stored. This takes 0.004 to 1.0 seconds.

The *coarse measurement* follows. Starting with the recorded position of the focussing lens (see d_f in Fi. 3.8), an approximate value for the staff reading and the image scale (distance) is determined. This is basically done by trial-and-error, namely by comparing the recorded image pattern with the simulated image pattern, which is calculated by the computer for a large number of different distances and staff readings. To assess the goodness of fit of the real and the simulated patterns for the different distance and staff readings, the correlation coefficient is computed. This (1-bit) correlation process takes 0.3 to 1.0 seconds.


Focus position
Focus encoder
Compensator control
Code image
Photo diode array
Video signal
Read-out electronics
A / D
ACCU 500 mAh
REC Module
Processor board
• 8 Bit CPU
• Gate array
GSI interface
• external power supply
• external recording
Display
Keyboard& Measure button

Figure 3.6: Block diagram of the electronic section of the Wild NA2000 digital level (after Ingensand 1990)

During the final *fine measurement*, the staff reading and the image scale (distance) are determined with full 8-bit correlation between measured and simulated readings of the 256 pixels. The final staff reading and distance are obtained through the application of stored calibration values. The time required for the fine optimisation depends on distance and the quality of the optical signal. The time varies from 0.5 to 1.0 seconds. Depending on the selected measuring mode, the measurements are then processed further and/or displayed and/or stored.

3.1.3.3 *Signal Processing*

The digital level compares the measured grey values of the 256 pixels of the photo detector with the simulated values computed from the known code pattern. Two parameters must be optimised through the correlation process, namely the *staff reading* and the *scale of the staff image*. Changes in the height difference h lead to a *shift of the bar code* image on the photo detector array. Changes in the distance d between the instrument and the staff change the *scale of the bar code* on the photo detector array.

To optimise the two unknown parameters, a two-dimensional correlation function has to be used. In the Wild NA2000, the following correlation function ρ_{PQ} (d,h) is computed between the measured signal Q(y) and the reference signal P(d,y+h) for all 256 pixel values of the array (Ingensand 1990):

$$\rho_{PQ}(d,h) = \frac{1}{N} \sum_{i=0}^{N} Q_i(y) \times P_i(d,y+h) \qquad (3.1)$$

Figure 3.7 shows a typical result of the correlation result over the measuring range of d = 1.8 – 100 m and h = 0.0 – 4.05 m. (The position of the code relative to the detector is denoted by y.) The distance (d_o in Fig. 3.7) and staff reading (h_o in Fig. 3.7) corresponding to the peak of the correlation function are the solutions for the unknown parameters d and h.



Figure 3.7: Plot of a typical result of the image correlation (ρ) in function of the distance (d) and the staff reading (h) (after Ingensand 1990)

In principle, the entire measuring range of d from 1.8 m to 100 m and of h from 0.0 m to 4.05 m must be checked to find the maximum of the correlation function. To scan the entire measuring range, the correlation coefficient would have to be computed about 50 000 times. To reduce the amount of computing (and measuring time), the search for the maximum correlation is divided in two stages.

The *coarse search* covers a band of about 80% of the total search area. The search band covers the total range of staff readings and is centred about the distance value d_f derived from the linear encoder on the focussing lens. To further reduce the amount of computing, the coarse search is carried out with a 1-bit signal of each pixel only. The original 8-bit signal of each pixel is reduced to 1-bit on the basis of a computed threshold level. In consequence, the multiplications in the above formula can be replaced by an equivalent exclusive-not-or-logic.

The correlation coefficient is computed for each intersection of the distance-height grid within the search band. A peak appears where the reference signal coincides with the measurement signal. This correlation peak is significantly above the noise level.

The *fine search* is used to find the correlation peak with the highest resolution. Within the square fine search area the correlation coefficient is computed with the full 8-bit signal values of each pixel. As the signal levels in the measurement and reference signal are different, the correlation function is normalised as follows (Ingensand 1990):

$$\rho_{PQ}(d,h) = \frac{\frac{1}{N}\sum_{i=0}^{N-1} Q_i \times P_i - \bar{Q} \times \bar{P}}{\sqrt{\frac{1}{N}\sum_{i=0}^{N-1} Q_i^2 - \bar{Q}}\ \sqrt{\frac{1}{N}\sum_{i=0}^{N-1} P_i^2 - \bar{P}}} \qquad (3.2)$$

The normalisation through Eq. (3.2) has the added advantage that the correlation coefficient ρ will be in the usual range, that is between –1.0 and +1.0, and that the quality of the measurements can be assessed.

A few other aspects must be considered during the image processing:

(1) The inhomogeneous light intensity of the bar code image must be analysed and taken into account.

(2) Missing code elements have to be detected and omitted from the subsequent correlation computations. (Partial coverage of the staff can lead to missing elements.) Tests have shown that, for sighting distances longer than 5 m, up to 30% of the staff image can be missing without loss of accuracy and reliability. It does not matter where on the image the obstruction occurs.



Figure 3.8: Definition of the coarse and fine search areas for the correlation maximum about the coarse distance d_f measured by the focus lens encoder. The final estimates of d and h are denoted by h_o and d_o. (after Ingensand 1990)

3.1.3.4 Accuracy of Bar Code Levels

The accuracy of the measurements depends on the following *internal* aspects of the measuring system (instrument and staff):

- accuracy of the code on the staff
- quantisation/sampling errors/noise
- quality of the optics
- quality and stability of the linear CCD array

The following *external* aspects also affect the accuracy of the system:

- Accuracy of the *Focussing*: Factory tests with the Wild NA2000 have shown that the accuracy of the staff reading is largely independent from the accuracy of the manual focussing. Proper focussing, however, leads to faster measurements. Since other makes of digital levels are more susceptible to poor focussing, it is advisable to properly focus at all times. One of the Topcon digital levels can be bought with an autofocus system.

- The *pointing* of the vertical hair to the centre of the staff is not critical for the reading of the staff. (Pointing becomes important, however, as soon as directions are also measured.) Over 100 m, the photo diode array views only 14.0 mm of the total width of 50 mm of the bar code pattern. Over 2 m, the photodiode array sees only 0.3 mm of the total bar code width of 50 mm. The correct orientation of the staff is also not critical. Even at an erroneous staff orientation of 45°, the apparent width of the graduation still exceed the width of the pixels.

- *Atmospheric Turbulence*: Heat shimmer reduces the contrast of the image of the bar code pattern and distorts the code pattern. Because of the averaging over a large number of graduations, the influence of turbulence is less than in conventional instruments.

- *Tripod Vibrations:* Image vibrations can be caused by the vibrations of the compensator (e.g. due to a set-up near a busy road). The effect of vibrations on measurements depends on the amplitude and the frequency of the vibrations and the speed of the readout of the photodiode array. As the whole image oscillates as a block, averaging over a large number of graduations does not help. (However, increasing the number of measurements does!)
  Like other automatic levels, there are occasions when digital levels cannot be used on vibrating platforms or ground. This case arises when the frequency of the vibrations is close to the resonance frequency of the level's pendulum compensator.

- *Staff Graduation Errors:* The errors of the individual bars are averaged because of the large number of graduations processed. However, the scale error of the staff is not eliminated!

- *Illumination* of the staff is critical. When levelling in the open air, the 'colour' of the light reflected of the staff cannot be influenced. When using artificial lighting, the spectrum of the light source should be similar to that of the sun.
  The intensity variation between full sun exposure, overcast conditions and dusk and dawn must be compensated by a variable integration time of the sensor array. The integration time is varied between 4 ms in full sun and 1 second in poor light. Inhomogeneous illumination of the staff (caused by partial shadowing) is also considered in the processing.

- *Partial Covering* of the bar code is a particular challenge to the processing software: There is no prior knowledge of where, how and how much of the code is blocked out. The software has to recognise missing patterns and ignores those sections in the correlation process. For reasons of reliability, a block out percentage of 30% has been selected as a maximum (above 5 m sighting distance). At least 30 elements (70 mm) of the bar code must be projected onto the sensor array to permit a unique height determination. At sighting distances below 5 m, no block out is acceptable.

- The *repeatability of the staff reading* is distance dependent. A number of tests have been carried out to establish the precision of staff readings. The table below gives the peak-to-peak variation of 20 observations with a Wild NA2000 (Müller 1990). The table shows that sighting distances should not exceed 50-60 m in sunny conditions.

Sighting Distance	10 m	30 m	60 m	80m
peak-to-peak variation				
at +18°C, overcast	0.0 mm	0.2 mm	0.4 mm	0.8 mm
at +27°C, heat shimmer	0.2 mm	0.5 mm	2.8 mm	not possible

Schauerte (1992) established the precision (in millimetres) of the staff reading with a Wild NA2000 digital level as ±(0.021 + 0.012 D[m]), where D is the sighting distance (in metres, not exceeding 35 m).

- The *repeatability of the distance measurement* is also distance dependent.

For the Wild NA2000 the repeatability of the distance measurements to the staff was once reported as <±3 mm for distances below 20 m, <±10 mm for sighting distances less than 40 m and ±10-30 mm for distances between 50 m and 100 m. These values give an indication of the trend with distance.

3.1.4 Bar Code Staffs

Originally, only glass fibre staffs (Wild GKNLE4) were available for the Wild NA2000. These staffs come in three sections of 1.35 m length each. The three plug-in sections give a total length of 4.05 m. Later, Leica added the invar staffs Wild GPCL3 and GPCL2 as options for the more accurate versions of the Wild NA2000 (e.g. Wild NA3000) and aluminium and wooden staffs for normal levelling. (Zeiss offers folding bar code staffs for their digital levels.)

3.1.4.1 Leica Normal Bar Code Staffs

The basic bar code element is 2.025 mm wide. The 4 m fibre glass staff features 2000 elements over 4050 mm. Leica uses a pseudo-stochastic code for their staffs. (Topcon and Zeiss use different coding principles.) On the reverse side, standard metric (10 mm) or imperial (0.1 feet) faces are available. The Wild instruments and staffs permit unique measurements for sighting distances between 1.8 m and 100 m. The manufacturer claims a coefficient of expansion of less than 10 ppm/°C for the fibre glass staffs. Based on practical measurements, the manufacturer reported coefficients of expansions of <8 ppm/°C and <0.2 ppm / (percent relative humidity).

The temperature coefficient of the fibre glass staff is worse than that of the traditional wooden staffs but better than that of aluminium staffs. On the other hand, the humidity coefficient of (poorly painted) wooden staffs can be much worse. Leica also sells 4 m wooden and aluminium staffs. The manufacturer quotes a coefficient of expansion of 10-20 ppm/°C for the former (depending on humidity) and 24 ppm/°C for the latter.

3.1.4.2 Leica Invar Bar Code Staffs

The bar code invar staffs are constructed in the same way as all modern invar staffs, namely with an invar ribbon recessed in an aluminium housing and a hardened and rust-free base plate. The usual length of the invar staffs supplied by Leica is 3.0 m or 2.0 m. (For industrial surveys, thin staffs of 60 cm, 92 cm and 182 cm length are also supplied.) The coefficient of expansion of these staffs is less than 1 ppm/°C. The errors of the individual bar code graduations (the basic interval is again 2.025 mm) are less than 10 μm because the bar code is manufactured with the aid of laser interferometry.

3.1.4.3 Errors of Normal Bar Code Staffs

The errors of the bar code staffs are no different from those of the traditional levelling staffs. These errors are listed for convenience. See surveying textbooks for a detailed discussion.

- Zero error
- Random errors of individual graduations
- Systematic graduation errors, e.g. scale errors in function of humidity, temperature and time
- Junction errors (of sectional, telescopic and folding staffs)

  Practical investigations have found errors of 0.1 mm to 1.0 mm across junctions of the Wild fibre glass sectional staff (!!!)
- Maladjustment of spot bubble
- Other errors such as bending, kinks

3.1.4.4 Errors of Invar Bar Code Staffs

The errors of invar bar code staffs are similar to those of classical invar staffs, which are also produced by modern manufacturing techniques (laser engraving under control of a laser interferometer). The support structure of modern invar staffs is made from aluminium and, thus, not sensitive to humidity changes.

It is expected that the coefficient of expansion is below the 1 ppm/°C level and the random graduation errors at the 10 μm level. Maurer & Schnädelbach (1995) quote an average coefficient of expansion of 0.75 ppm/°C for invar staffs manufactured after 1992. Although the coefficient of expansion is small, it varies from one staff to the next and needs to be calibrated for high precision levelling over large height differences.

3.1.5 Errors in Levelling with Digital Levels

The errors of digital levels are similar to those of automatic levels. Only a listing of most errors is given below. The readers are referred to textbooks for a complete discussion. The following books are suggested for further reading on this topic: Cooper, M. A. R. 1982, Modern Theodolites and

Levels, Granada, London, ISBN 0-246-11502-5, Sections 9.6 and 10, pp. 216-234 and Deumlich, F. 1982. Surveying Instruments, Walter de Gruyter, Berlin, ISBN 3-11-007765-5, pp. 179-211. The listing of the errors in levelling is based on the tables published by Schauerte (1993).

For general purpose levelling most errors of automatic and digital levelling instruments can be ignored. The collimation error must be considered, however, if the sighting distances in the foresight and backsight are not strictly the same. The scale errors of staffs and the refraction errors must be considered if large height differences are levelled. When using automatic and digital levels for precise levelling, all error sources must be considered. In consequence, the operator should be familiar with the properties of such levelling instruments.

3.1.5.1 Errors of Bar Code (Digital) Levels

- *Electronic Collimation Error*

Remedy: Observe strictly from the middle between the two adjacent staff set-ups (or determine the collimation error before and after the measurements and post-correct all measurements using the recorded sighting distances.) Note that this error is temperature and time dependent!

There is only one sure way of eliminating the effect of the collimation error on the height difference measured from one set-up: **set up in the middle**! This allows to use the same focus in BS and FS and avoids mechanical shocks between BS and FS.

Furthermore, the measuring procedures must be selected so that temperature changes at one set-up are minimised. If the **instrument is kept in the shade** at all times, there should not be any temperature induced changes of the collimation error between BS and FS.

- *Maladjustment of the Spot Bubble*

Remedy: At the beginning of a levelling run, **adjust the circular bubble** if it moves relative to its case when the instrument is turned around its vertical axis.

- *Compensation and Height Error* (leads to the 'obliquity of horizon')

Remedy: Observe in such a way that the error generates a systematic effect and eliminate it through an appropriate observation techniques such as the 'red trousers' method

BFFB (odd numbered set-ups)
FBBF (even numbered set-ups)

or the modified classical 'Wild-Zeiss' method

BFFB (at all set-ups)

(underlined = *level the spot bubble whilst the instrument is pointing to this staff* , B = *backsight,* F = *foresight*)

- *Measurements near the Top and Bottom of Staffs*

Digital levels are programmed to be able to measure near the bottom and top end of staffs since ordinary levels can measure to any graduation on a levelling staff. Users have found that digital levels can measure to a staff, even if the line of sight is slightly above the top end (or slightly below the bottom end) of a staff. Since the digital levels can use only half the measuring sector when measuring to the ends of staffs, the precision of staff readings near the ends of staffs may be reduced and systematic errors may occur.

Figure 3.9a shows some experimental results with a Leica NA3003 near the bottom end of a Leica invar staff. At 10 m sighting distance, the maximum error is about 0.4 mm and at 30 m, the error may be as large as 1.2 mm (even though the instrument displays staff readings to 0.01 mm). Figure 3.9b shows the field of view of the level should extend to a maximum of 20% (of the field of view diameter) above the highest useable staff graduation.



Figure 3.9a: Errors when measuring to the bottom end of a Leica invar staff with a digital level Leica NA3003 at a sighting distance of 10 m (left) and 30 m (right). For measurements to the right of the DP1 line, the full measuring sector falls on the staff. (after Woschitz 2003)



Figure 3.9b: Maximum reading on staffs as suggested by Leica for precise levelling with the NA2000/3000 series of digital levels (Leica 1996)

Figure 3.9c shows some experimental results with a Topcon DL-101C near the top end of a Topcon invar staff. At 10 m sighting distance, the maximum error is about 0.8 mm and at 30 m, the error may be as large as 0.7 mm. Note that, at 10 m, the staff readings are too small near the top end of the staff and, at 30 m, too large. Woschitz (2003) recorded a gross error of more than 2 metres during a similar test at the bottom end of the Topcon staff. Figure 3.9c (after Woschitz 2003) indicates what range of staff readings should be avoided with Topcon digital levels near the top of 3 m Topcon digital levelling staffs.

Similar tests by Woschitz (2003) with a Zeiss(Trimble) DiNi11 digital level showed a maximum error of about 0.2 mm at 10 m and no errors at 30 m. Ingensand (2001) reported additional errors (to 0.2 mm) of Zeiss (Trimble) DiNi levels near the top end of staffs caused by artificial lighting in tunnels.



Figure 3.9c: Errors when measuring to the bottom end of a Topcon invar staff with a digital level Topcon DL-101C at a sighting distance of 10 m (left) and 30 m (right). For measurements to the left of the DP2 line, the full measuring sector falls on the staff. (after Woschitz 2003)

- *Systematic Staff Reading Errors*

Soon after the release of the first digital levels, periodic staff reading errors were noted at sighting distances of 15 m and 7.5 m. The effect was thoroughly investigated later by Woschitz (2003). Figure 3.9d shows how the errors of the staff reading change with height in line with the projected pixel size on the staff. The largest errors occur when the fundamental staff interval coincides with the (projected) pixel interval. The largest peak-to-peak variation of 0.81 mm occurs at 14.98 m. Similar effects are found at sighting distances of around 30 m and around 7.5 m. Equivalent tests in the 'extended system accuracy mode' showed reduced peak-to-peak variations of 0.30 mm (at 15 m). At other sighting distances, the peak-to-peak variation is much less, namely 0.1 to 0.2 mm in 'standard system accuracy mode'. Clearly, these sighting distances should be avoided when using the Wild/Leica NA200x/NA300x series of instruments for precise levelling.

Woschitz (2003) also investigated the systematic errors in Topcon digital levels. Some experimental results are shown in Fig. 3.9e. The error patterns at 5 m (and below) and 11 m (and above) are quite different. It is known that the Topcon digital levels change the way they derive the staff reading at about 9 m (Rüeger 2000).

Figure 3.9e seems to indicate that the short range measuring mode is free of systematic errors. At 7.0 m, the Topcon level seems to switch occasionally to the long range measuring mode. At 9.0 m, the level seems to switch continuously between short and long range mode. Woschitz determined a mean staff reading offset between the two modes of 0.19 mm. At sighting distances of 11 m and more, the Topcon levels show a periodic error pattern with a period of 300 mm and a peak-to-peak variation of 0.18 mm.



Figure 3.9d: Systematic staff reading errors with a Leica NA3003 digital level in 'standard system accuracy mode', at sighting distances near 15 m. (after Woschitz 2003)

The amplitude of the sine pattern decreases with distance and cannot be distinguished any more at about 30 m. In practice, sighting distances between, say, 7 m and 11 m should be avoided in precise levelling since one measurement may differ from another by 0.36 mm because of the switching between the two processing modes and the 'cyclic error' of the long range mode.



Figure 3.9e: Systematic staff reading errors with a Topcon DL-101C digital level at sighting distances from 5 m to 11 m. (after Woschitz 2003)

A Zeiss/Trimble DiNi11 was also investigated by Woschitz (2003). Periodic errors similar to those in Fig. 3.9d were found, but with much smaller amplitudes. Periodic patterns were found at 5 m, 9, 11 m, 19 m and 30 m. The maximum peak-to-peak variation of 0.1 mm was recorded at a sighting distance of 19 m. These errors are sufficiently small to be ignored in levelling practice.

- *Influences on the Setting Behaviour of the Compensator* (wind, traffic)

Remedy: Increase the number of staff readings: observe at least two backsight readings (BS) and two foresight readings (FS) so that the possible influences become evident in the two height difference (BS-FS) values. In precise levelling, one would measure, for example, BB FFFF BB or even B FF BB FF B.

- *Influence of Magnetic Fields* caused by direct or alternating currents

The magnetic field of the Earth has to be considered at all times. Additional fields are present near electrical installations (e.g. transformer stations). The effect of the Earth's magnetic field on compensators of levelling instruments was first reported in 1981. Laboratory tests at a field strength of 23000 nT (nanoTesla) established the following systematic errors of particular instruments for N-S levelling runs due to the Earth's magnetic field: Zeiss Ni2 - 0.2 mm/km; Wild NAK2 –> 0.5 mm/km; Zeiss Ni002–> 1.5 mm/km; Zeiss Ni1 –> 2.2 mm/km. Since 1982, all manufacturers have reduced the susceptibility of their instruments to magnetic fields by better shielding and/or the use of non-magnetic materials for the compensators. Post-1982 automatic levels (such as all digital levels) are likely to be much less affected by the Earth's magnetic field. Recent tests with a Wild NA3000 found a residual magnetic effect of 'only' 0.15 mm/km on N-S lines.

Remedy: Test in a laboratory if magnetic fields have an effect on the collimation error.

- *Temperature Effects on the Compensator and/or the Photo Detector/CCD Array* (e.g. due to lack of temperature acclimatisation or sun exposure during transport from set-up to set-up). Temperature may change the electronic collimation error and/or generate a vertical shift of the line of sight.

Remedy:

–> Shade the instrument at each set-up (and also during transport) with an umbrella.

–> Increase the number of measurements to the staffs so that jumps in the compensator's rest position can be detected in multiple BS-FS values.

–> Measure strictly from the middle between the forward and backward staff positions and use time-symmetric measurements for the BS and the FS, such as the 'red trousers' method or the modified 'Wild-Zeiss' method (see above).

- *Sinking of the Tripod*

Remedy: Employ a measurement sequence which features time-symmetric BS and FS measurements and do not set up instruments on warm bitumen surfaces.

3.1.5.2 Errors of Invar Bar Code Staffs

- *Graduation Errors in Invar Bar Code*

Remedy: As modern invar staffs are manufactured under laser interferometer control, only small random errors are to be expected. Because of the averaging over a large number of individual code elements, this small effect is reduced even further. In consequence, line-by-line calibration is not required.

- *Difference of the Zero Errors of the two Staffs* (in precise levelling)

Remedy: Use an even number of instrument set-ups between the bench marks (BMs) and always use the same staff for the connection to BMs. Do not change the staffs for the backwards run.

- *Change of the Length of the Bar Code due to Temperature*

(leads to variable height errors which depend on the staff reading)
Remedy:
– Calibrate the composite coefficient of expansion of the bar code scale (as the sum of the expansions of the invar ribbon and the aluminium case and changes in spring tension) with the staff in a vertical position. Alternatively, the data of a factory calibration may be used or an average value of +0.75ppm/°C (after Maurer & Schnädelbach 1995).
– Measure the temperature of the invar ribbon (e.g. at three heights above ground) of each staff and at each staff set-up and correct (post-mission) all staff readings accordingly using the appropriate coefficient of expansion.

- *Sinking of the Staff during the Observations from one Instrument Set-Up*

Remedy: Ensure a stable marking of the change points. Employ an observation schedule with time–symmetric BS-FS measurements.

- *Sinking of the Staff during the Move of the Instrument to the next Set-Up*

Remedy: Ensure a stable marking of the change points. This effect becomes evident in a comparison of the total height differences obtained in the forward and the backward runs. It cannot be eliminated by any other mean than a double run (–>,<–) levelling.

- *Skewness and Non-Flatness of the Foot Plate of the Staff ('Shoe')*

Remedy: Test the flatness of the foot plate of the staff. If large variations are detected, get foot plate changed. Minimise this effect (and the possible eccentricity between the optimal set-up point and the middle of the foot plate) by setting up of the staff at the point where the centre line of the invar ribbon intersects the foot plate. The manufacturer may provide a ring to achieve a correct set-up. (Not possible for BMs in walls.)

- *Maladjusted Spot Bubble of the Staff*

Remedy: Test the state of the adjustment prior to the measurements and adjust the spot bubble of the staff, if required. With invar levelling staffs, insure that the staff is set up so that the axis of the invar ribbon is in the centre of the benchmark or change plate. Refer also to Fig. 3.17 in the exercise section at the end of this chapter.

- *Movement of the Staff* (due to Wind or Traffic)

Remedy: It is essential to support of staff in two perpendicular directions. Buy optional struts or use two ranging rods (at right angle) for the purpose.

3.1.5.3 External Influences on Line of Sight

- *Grazing Rays (–> Levelling Refraction)*

Digital levels are likely to be more susceptible to refraction than other levels because they use graduations below the line of sight for the measurements. Apart of this, the digital levels suffer from the same refraction effects as all other levels. These effects may be summarised as follows (Angus-Leppan 1984):

– Levelling on a Plain: The refraction effect can amount to 1 mm over 50 m but is cancelled if the sighting distances to the foresight and the backsight staffs are strictly the same.

– Levelling on E–W Slopes: When going uphill, the foresight is more affected by refraction than the backsight. The effect is worst on gentle slopes where the slope still permits to maintain the tolerated maximum sighting distance. Errors in of 20 to 30 mm per 100 m height difference may occur. The signs of the errors in the rise and the descend over a hill are likely to be opposite so that the error may cancel in the height difference between points on both sides of the hill.

– Levelling on N-S Slopes: The refraction effects in ascend and descend no longer cancel because the sun is predominantly north or south, depending on the hemisphere. The accumulated errors vary depending on slope, season, climate and latitude; they can reach 50 mm to 1000 mm per 1000 km N-S levelling.

Recommendation: The horizontal line of sight should be more than 1 m above ground with the Wild NA2000/3000, as is uses ±0.18 m per 10 m above and below the horizontal line of sight. Reduce the sighting distance, if this condition is not fulfilled. This procedure ensures that the refraction effect with the Wild NA2000/NA3000 is not larger than with conventional levels. The refraction errors listed above may be reduced, but not cancelled, by this procedure.

- *Terrain below the Line of Sight*

Remedy: Rough surfaces (like grass) are preferred. Avoid measuring across bitumen and concrete surfaces.

- *Obstruction of Bar Code Section in Use*

Remedy: Ensure free observation sector. With the Wild NA2000/NA3000 no obstructions are tolerated at sighting distances of less than 5 m.



Figure 3.9f: Refraction effect on levelling on a slope. The errors caused by refraction are denoted by dBS and dFS. BS and FS are the true backsight and true foresight readings, respectively. BS' and FS' are the erroneous actual readings. The 2° angles indicate the viewing angle of the Wild NA2000/NA3000 digital levels. (after Schauerte 1993)

- *Sun Exposure* (–> heat shimmer)

Remedy: Select the optimal time of the day, the best season and the most appropriate weather conditions for any precise levelling.

- *Insufficient Illumination of the Staff*

Remedy: In poor light outdoors or under artificial lighting indoors (in tunnels, halls, buildings) the staffs must be illuminated with a lamp with 'daylight' spectrum.

3.1.5.4 Errors of the Observer

- *Inaccurate Focussing*

Remedy: The tolerance range for the focussing increases with distance. At sighting distances of less than 5 m, focussing errors can lead to 0.1 mm errors in height in Wild (Leica) NA200x/NA300x instruments. Woschitz (2003) noted that poor focussing with Zeiss (Trimble) levels increases the periodic error in these instruments. For example, a peak-to-peak variation of 0.21 mm is mentioned for a pointing of 0.5 m in front or behind the staff over 10.2 m.

- *Recording of Erroneous Observations* or omission of the recording of additional information

Remedy: Book such occurrences in handwritten notes or through the storage of additional information in the measurement file.

3.2 Laser Levels

Laser levels in general and rotating laser levels in particular have become an important surveying tool in building, construction and agriculture. In fact, rotating laser levels have almost replaced the classical levels on building and construction sites. This is reflected by the fact that most manufacturers of surveying equipment now produce rotating and other laser levels in great numbers. Although they are more expensive than the normal levelling instruments, they are much more efficient as they provide effectively a one-person levelling system. The rotating laser level consist of a tripod mounted instrument which, after levelling, rotates (about a vertical axis) a visible or infrared beam in a horizontal plane. It typically rotates at a rate of a few hundred revolutions per minute (rpm). Some models have adjustable rotation rates (e.g. between 0 and 500 rpm). In the case of visible (red) beams, the red dot can be seen on any surfaces 'hit' by the beam. For laser levels, that transmit an infrared beam, a special detector has to be used to detect the beam. A similar (or sometimes the same) detector can be used to increase the range and the precision of the visible beam instruments.



Figure 3.10: Use of laser levels in construction and agriculture (after Laser Alignment Inc 1986)

This detector is usually moved up and down a wall or a levelling staff until the detector is centred on the horizontal laser plane. Most detectors provide up-down guidance in visual and acoustic form to assist the centring and to provide better precision. For example, the detector may generate a fast beeping noise, if it has to be moved down to the laser plane, a slow beeping noise, if it has to be moved up, and a continuous tone if it is centred on the horizontal plane. Some detectors may provide different sensitivity settings. A high sensitivity provides higher accuracy under good measuring conditions (e.g. short range, indoor). For their LPD2 detector, Leica quotes a setting precision of ±0.8 mm for the high sensitivity setting and ±2.4 mm for the low sensitivity setting (long range, outdoors). The overall accuracy of a well adjusted rotating laser level is quoted by Leica as ±2 mm at 50 m and ±4 mm at 100 m. Some building site rotating laser levels can be mounted horizontally to provide a vertical reference plane.

Outside building sites, laser levels can be used to guide or control precision grading machines in construction work (excavators, graders, bulldozers, scrapers) with horizontal, single or dual grade surfaces. These laser levels typically operate over longer ranges than those on building sites and can be set to mark non-horizontal planes. The detectors are mounted on the cutting tools and the results displayed in the drivers cabin. Another use of these devices is for land forming in agriculture, again with horizontal, single or dual grade surfaces.

The range of laser levels depends on the output power of the lasers or laser diodes used, on the atmospheric conditions and on the sensitivity of the laser detector used; it can be as much as 450 m. All systems have a much larger range at night. At longer distances, the effects of earth curvature and, in particular, refraction must be considered. This aspect will be discussed later.

Laser levels come in many forms and are not restricted to rotating laser levels. Linear laser levels are used for pipe laying, for example. They fit into pipes and project a laser beam at a selectable gradient. Pipe laying lasers provide not only the levelling but also the alignment of the pipes.

The simplest form of laser levels are hand-held and project a laser beam parallel to the principle axis of an attached tubular level. If the bubble of the tubular level is centred, the beam is horizontal. Mounting the pocket laser level on a (horizontal) swivel base permits to project a horizontal plane. Attachment of a right angle beam splitter even allows the setting out of right angles. The figure below shows one of these simple devices.



Figure 3.11: Pocket Laser Level with a visible laser diode emitting at 635 nm, 150 mm long, daytime range 30 m (after Leica Instruments Australia)

3.2.1 Construction of a Rotating Laser Level

Figure 3.12 shows the cross-section through a typical rotating laser level (Telamat by the German company Theis). The infrared beam is produced by a GaAlAs diode (nominal wavelength 780 nm, output power 0.3 mW) at the bottom of the housing. This diode is in the focal point of the two-lens objective directly above it. The figure shows also one of the two adjustment screws for the diode. (If the instrument is out of adjustment, these adjustment screws can be used to make the laser beam horizontal in two perpendicular planes.) The laser beam travels straight up, through the lens system and to the pentagonal prism. This prism deviates the beam by 90° and rotates at a few revolutions per second. A belt connects the rotating part to the drive motor. The horizontal beam leaves through the glass plates on all sides. These glass plates protect the rotating part form the elements.


Pentagonal-
Prism
Laser-Beam
Protective
Glas
Compensator
Housing
Drive-
Motor
Laser-Beam
Light-Barrier
Lens 1
Lens 2
Battery
Laser-Diode
Battery

Figure 3.12: Cross-Section through a rotating laser level Theis Telamat (after Wüller 1988)

Figure 3.12 also shows that the upper (concave) lens is suspended on wires, which are attached below the rotating prism. The hanging lens acts like a two-dimensional pendulum and is used as a so-called compensator. Like in the traditional automatic levelling instruments and the newer bar code levels, the compensator compensates the laser beam for any small non-verticality of the case of the instrument, which is typically levelled by a spot bubble (circular level) only. Light barriers check if the pendulum is freely hanging. Most instruments will not operate until the instrument is levelled accurately with the aid of the spot bubble.

The instrument shown has rechargeable batteries on-board, which can be charged with the appropriate charger and cables. Most manufacturers also provide cable connections and, sometimes, DC/DC converters for running the laser levels of 12 V car batteries. The range of the level is quoted as at least 120 m.


Aperture Stop
Suspension of Wires
V-Cut Disk
Tungsten – Rhenium – Wires
Light-Barrier
Pendulum Lens
Plan View of V-Cut Disk

Figure 3.13: Cross-Section through the compensator of the Theis laser level Telamat (after Wüller 1988)

3.2.2 Design of a Two-Axis Compensator of a Rotating Laser Level

A more detailed diagram of the compensator of the Theis laser level 'Telamat' is given in Fig. 3.13. Figure 3.13 shows that three wires support the pendulum lens. The correct spacing and orientation of the wires is provided by the disk with the three V-cuts. The pendulum features magnetic damping and has a working range of 0.5 degrees of arc.

Figure 3.14 explains the working principle of the two-axis compensator. The beam axis of the laser diode is not coincident with the plumbline through the diode because of the small residual dislevelment α of the instrument after levelling with the spot bubble. In consequence, the laser beam travels at an angle of α to the plumbline towards the suspension point P of the concave pendulum lens. (In a perfectly levelled instrument, the point P would be strictly above the diode.) The laser beam is then refracted in the pendulum lens. Because of the type of suspension used, the plane of the pendulum lens is at right angle to the line between the diode and the suspension point P. The centre of the lens is directly below the suspension point P. Knowing this, the focal point of the lens can be plotted at the focal distance f from the centre of the lens. Because the incident beam from the diode is parallel to the optical axis of the lens (see 'f' in figure), the laser beam exits in a direction defined by the focal point and the point of intersection between the plane of the lens and the incident laser beam. It follows from the figure that the laser beam is 'bent' by an angle β (rather than the dislevelment angle α) at the lens.

3.2.3 Major Errors of Rotating Laser Levels

3.2.3.1 Compensation Error

The compensator of the laser level corrects most of the dislevelment. Some small residual error $(\alpha - \beta)$ remains. This *compensation error* $(\alpha - \beta)$ causes the laser beam rotate in an oblique plane at an angle of $(\alpha - \beta)$ against the horizon. This is sometimes referred to as *obliquity of horizon*. The relationship between the α and β follows from Figure 3.14 as (Wüller 1988):

$$x = PL \sin \alpha = f \tan \beta \qquad (3.3)$$

$$\beta = \arctan \{(PL/f) \sin \alpha \qquad (3.4)$$

$$\alpha - \beta = \alpha - \arctan \{(PL/f) \sin \alpha\} \qquad (3.5)$$

Equation 3.5 shows that β becomes zero for zero dislevelment α. Considering the close agreement between tan and sin values for small angles, the angle β would always be close to α and the compensation error very small. Further, the designer can select the fraction (PL/f) in such a way that the compensation error is reduced further. However, as Fig. 3.14 and Eq. (3.5) show, the distance PL has to be close to the focal distance f. In the case of the WILD LNA2, the obliquity of horizon is adjusted if ($\alpha - \beta$) exceeds 1.25 mm over 30 m (8.6 seconds of arc).


Nominal Truly Vertical Beam Axis
Actual Beam Axis
Suspension Point of Pendulum (P)
α
Comp Error = α - β
α
PL
Plumline through Laser Diode
β
x
Pendulum Lens
Direction of Laser Beam Emission
f
α
β
Laser Diode
Focal Point of Pendulum Lens

Figure 3.14: Two-axis compensator principle in Theis rotating laser level Telamat (after Wüller 1988)

3.2.3.2 Adjustment Conditions of Rotating Laser Level

Before the adjustment conditions of a rotation laser level can be introduced, three axes need to be defined. The *centre of the beam* is the centre of gravity of the beam intensity in the plane perpendicular to ray. The laser *beam axis* is the line between the centre of the beam at the target and the centre of the beam in the (rotating) pentagonal prism (or mirror). (This laser beam axis corresponds to the 'line of sight' of ordinary levelling instruments.) The *rotation axis* is the axis of rotation of the pentagonal prism or mirror assembly and corresponds to the 'vertical axis' of theodolites.

An rotating laser level is in perfect adjustment when:

- the axis of the pentagonal prism coincides with the rotation axis,
- the radiation axis of the (infrared or visible) laser diode coincides with the rotation axis,

- the optical axis of the biconvex lens coincides with the rotation axis.

The first two adjustment conditions are illustrated below in Figs. 3.15 and 3.16. The non-coincidence of the two respective axes is described by an linear eccentricity error and an angular misalignment. It is evident from Fig. 3.15 that, both, the eccentricity and the angular misalignment of prism and laser beam axes have no effect on the definition of a horizontal plane.



Figure 3.15: Effects of the non-coincidence of the axis of the pentagonal prism and the rotation axis. Left: Effect of the eccentricity of the axis of the pentagonal prism relative to the rotation and the laser axes; Right: Effect of the angular misalignment between the axis of the pentagonal prism and the laser and rotation axes. (after Noack 1989)

The non-coincidence of the laser beam and the rotation axes in Fig. 3.16 are more significant. The eccentricity e of the laser beam relative to the rotation axis of the prism causes the horizontal plane projected by the laser beam to change its height by 2e over a 360° rotation of the prism. In the Theis Telamat, this *height error* is minimised by an aperture stop below the rotating prism. The angular misalignment ε of the laser beam relative to the rotation axis of the prism causes a tilt of the projected laser plane of the same angle ε and a height shift of the beam of 2k over a 360° rotation of the prism. The beam shift of 2k can be computed from the dimensions of the pentagonal prism and the incident angle ε. Considering the principle of the compensator shown in Fig. 3.14, is evident that ε corresponds to the angle β and is very close to the angle α (the dislevelment of the laser level). After accurate levelling of the laser level with a spot bubble, ε should not exceed a few minutes of arc and would cause a minimal height error k.

3.2.3.3 Misalignment of a Rotating Mirror

If the rotating laser level is equipped with a rotating mirror (at 45° to the rotating axis) rather than a rotating pentagonal prism, then any error in the 45° angle will generate an error which is analogous to a collimation error in a ordinary level. The laser beam will travel on a conical rather than plane surface. The Spectra Physics EL-1 Electronic Level System is such an instrument.



Figure 3.16: Effect of the non-coincidence of the laser beam and the rotation axis. Left: Effect of eccentricity e of laser beam relative to the rotation axis. The resulting height error amounts to ±e. Right: Effect of the angular misalignment ε of the laser beam relative to the rotation axis. The magnitude of the resulting height error is ±k. (after Noack 1989)

3.2.3.4 Secondary Height Error

Because the intensity distribution across the originally vertical laser beam is not uniform, different parts of the beam will be used by the laser detectors depending on azimuth to derive the up-down information. For the Theis Telamat the peak-to-peak variation due to this error is stated as less than 0.5 mm.

3.2.4 Calibration of Rotating Laser Levels

As the main part of rotating laser levels cannot be rotated about a vertical axis and as two components (x-y) of the compensator must be checked, the tests known from the traditional levels (e.g. Two-Peg-Test) cannot be used. The procedure outlined here only gives the principle for the testing and adjustment of the horizontal laser plane. The manufacturers of particular instruments will prescribe the exact procedures to be used.

- Set up the tripod 30 m from a house wall and make the tripod's top surface truly horizontal (in two vertical planes) by using a carpenters level. To check the latter, all readings with the carpenters level should be taken in 'two faces' (and the mean readings used). Extend and retract the adjustable tripod legs to get the tripod top truly horizontal.

- Define two vertical planes through the laser level which are at right angles to each other. Use features of the laser level to distinguish between the x and the y planes.

- Point the positive x-axis to the wall, level the instrument and switch it on. Move the detector up and down until it is centred on the beam. Mark this position, say with X1. Rotate the laser level by 180° (till the negative x axis points to the wall). Do not touch the footscrews in this process. Mark the position of the beam on the wall with X2. For the laser level Wild LNA2, the manufacturer suggests that the x-component of the instrument be adjusted if the distance between X1 and X2 exceeds 2.5 mm (at 30 m). To do so, mark the half-way point between X1 and X2, centre the detector on it and adjust the x-component of the compensator as specified by the manufacturer until the beam is centred on the detector.

- Turn the laser level by 90° and level it by centring the spot bubble. Proceed with the adjustment of the y-component of the compensator as discussed above for the x-component.

3.2.5 Computation of Heights, Earth Curvature and Refraction

It is known from the theory of trigonometric heighting (see Rüeger 1990, pp. 108 to 114, for example) that the (ground) elevation H_T of a target station can be obtained from the (ground) elevation H_{LL} of the laser level station for a line of sight which is strictly horizontal at the laser level station as follows:

$$H_T = H_{LL} + h_{LL} - h_T + \frac{1}{2R} d^2 - \frac{k}{2R} d^2 \qquad (3.6)$$

It is important to realise that the above formula gives 'heights above sea level' or 'levelled heights'. This means that water between points of the same elevation would not flow. As in traditional levelling, the laser level is usually not set up over a mark of known height. Instead, the elevation of the laser beam plane (traditionally referred to as 'collimation height') is determined backward, by setting up the laser detector on a mark of known height. In the absence of earth curvature and refraction effects, the collimation height is obtained as

Collimation Height = Elevation of reference mark + height of detector over reference mark (3.7)

Therefore, the formula for the (ground) elevation H_T at the target point can be simplified to

$$H_T = \text{Collimation Height} - h_T + \frac{1}{2R} d^2 - \frac{k}{2R} d^2 \qquad (3.8)$$

where h_T is the height of the detector above the mark (ground) at the target station, R is the earth's radius (e.g. 6370100 m for New South Wales) and k is the coefficient of refraction. The third term on the right hand side is the correction for *earth curvature.* This correction is positive because the spherical earth curves away from the horizontal laser beam. The laser plane is a parallel to a tangential plane to the spherical earth at the laser level station. The forth term on the right hand side corrects for the effects of *vertical refraction.* On clear sunny days close to the ground, the coefficient of refraction k is strongly negative (down to k = –3). This means that the laser plane is no longer a plane but a paraboloid pointing upwards. The offset from the horizontal plane increases with the square of the distance from the laser level. On clear nights, the coefficient of refraction is strongly positive (up to k = +3) , which means that the laser plane is bent downwards, towards the ground. The table below gives an indication of the magnitude of the effects of earth curvature and refraction.

Distance	50 m	100 m	200 m	300 m	400 m	500 m
	mm	mm	mm	mm	mm	mm
Earth Curv Corr	+0.2	+0.8	+3.1	+7.1	+12.6	+19.6
Refr Corr k=–3	+0.6	+2.4	+9.4	+21.2	+37.7	+58.9
Refr Corr k=–2	+0.4	+1.6	+6.3	+14.1	+25.1	+39.2
Refr Corr k=–1	+0.2	+0.8	+3.1	+7.1	+12.6	+19.6
Refr Corr k=0	0.0	0.0	0.0	0.0	0.0	0.0
Refr Corr k=+1	–0.2	–0.8	–3.1	–7.1	–12.6	–19.6
Refr Corr k=+2	–0.4	–1.6	–6.3	–14.1	–25.1	–39.2
Refr Corr k=+3	–0.6	–2.4	–9.4	–21.2	–37.7	–58.9

Table 3.1: Sample corrections of the elevation H_T of the target point for earth curvature and refraction in function of the distance from the rotating laser level. The coefficient of refraction is denoted by k.

Equation (3.8) can be written in a form where the corrections for refraction and earth curvature are applied directly to the height h_T of the laser detector at the target station

$$H_T = \text{Collimation Height} - \{h_T - \frac{1}{2R}\, d^2 + \frac{k}{2R}\, d^2\} \qquad (3.9)$$

This form shows that earth curvature causes the h_T readings always to be too large. Vertical refraction causes the h_T readings to be too small when the coefficient of refraction is positive (typically at night) and too large if the coefficient of refraction k is negative (typically during daytime).

On building sites, where the operating radius of laser levels if often below 50 m, the effects of refraction and earth curvature can be ignored. At a radius of 100 m, the corrections are still below the typical system accuracy of laser levels (±4 - 6 mm). At 400 m radius, the corrections do reach and exceed the laser level system accuracy (about ±16 to 24 mm).

For practical reasons, the above corrections are usually ignored even for the large radii used in land forming operations, for example. The effect of omitting these corrections are best explained with the aid of an example. Let us assume that a grader is used to prepared a horizontal surface of 800 by 800 m. In this case, the cutting blade of the grader would be set so that $h_T = h_{LL}$, assuming that the laser level is set up in the middle of the surface. In the absence of refraction, the graded surface would be strictly parallel to the laser plane. This means, in terms of sea level elevations, that the ground at 400 m from the level would be 12.6 mm 'higher' than the ground at the laser level. Water would therefore flow towards the laser level.

If we assume that this earth work was carried out during the night with the laser level set up very close to the ground ($k = +3.0$), then the ground at 400 m from the laser level could be 25 mm 'lower' than the ground near the laser level. If one were to check the night-time grading later on a clear sunny day, with the laser level again close to the ground ($k = -3.0$), then one might note that the ground at 400 m is 75.4 mm (2x37.7 mm) 'lower' than expected, that is 75.4 mm lower than the ground would have been if graded on a sunny day. (If the grading were carried out on a sunny day with h_T set equal to h_{LL}, then the ground at 400 m from the laser level would be 50 mm too high.)

The fact that the laser beam may wander 100 mm up and down between day and night over 500 m due to refraction must be considered if some work is carried out during the day and some during the night. *Refraction effects can be reduced by setting the rotating laser level as high as possible above ground and by measuring during windy, overcast days or around sunrise and sunset, when the coefficient of refraction is close to zero.*

3.3 Exercises

3.1 Name and discuss three key differences between digital (bar code) and conventional automatic levelling instruments.

3.2 Like conventional automatic levels, digital levels use compensators to make the line of sight horizontal even though the vertical axis might be out of plumb by a small amount.
Name three errors caused by the compensator and how they may be 'eliminated' in precise levelling.

3.3 The figure below highlights the effect of the contact point between invar staff and bench mark not being exactly in the axis of the invar ribbon. The actual staff reading L' does not correspond to the vertical separation L between the line of sight and the top of the bench mark.

(a) Derive an equation for the staff reading error δh as a function of L, e and the staff tilt α noting that $L' = L + \delta h$.

(b) What is the error δh if L = 2.600 m, α = 10' and e = 32 mm?



Figure 3.17: Error δh in a reading ($L' = L + \delta h$) on an invar staff due to the tilt of the staff (α) and the eccentricity (e) between the contact point (on the bench mark) and the axis of the invar ribbon. (after Schauerte 1995)

3.4 You have been asked to determine the heights of three bench marks (BMs), namely BM A at the foot of a hill on the eastern side, BM B on top of the hill and BM C at the foot of the hill on the western side. On a clear summer day, you then level from A to B, from B to C and from C back to A around the base of the hill. The misclosure in the level loop is consistent with the accuracy of the equipment and the techniques used. However, you are concerned about possible refraction effect.

(a) Explain why refraction can affect the height of BM B even though the loop misclosure was found to be effectively zero.

(b) By how much could the height of BM B be in error if BM B is 500 m higher than the BMs A and C?

3.5 You instruct a survey party to level a bench mark at the bottom of an open cut mine relative to a bench mark (of given height) on the rim of the mine. The field party uses a digital level with an aluminium bar code staff on a day with an ambient temperature of +40°C. The height difference of about 500 m is measured forward and backwards. The height of the BM at the bottom of the pit is obtained as H = 23.148 m.

(a) Six months later, the level run is repeated with the same equipment, but at an ambient temperature of +10°C. Assuming that both bench marks were not subjected to ground movements or settlements, what elevation would you expect to find for the bench mark at the bottom of the pit?

(b) Assuming that the staffs are at nominal length at +20°C, what would the most likely height of the bench mark at the bottom of the pit be?

(c) The mine management wants you to determine all BM heights to ±10 mm or better. What type of staff will you use in future:

(i) on the (natural) plain around the mine pit?

(ii) to level down into the pit?

Explain your selection.

3.6 In the context of the levelling of the Australian continent in the 1960s, the line from Brisbane to Cairns (about 2000 km) was levelled. Large differences were found when connecting to tide gauges along the coast. Figure 3.18 shows the mean sea level heights as determined from a free continental adjustment (solid line) and from unadjusted orthometrically corrected observed heights (non-adjusted).



Figure 3.18: Mean sea level heights as determined from a free continental adjustment (solid line) and from unadjusted orthometrically corrected observed heights (non-adjusted) (after Roelse et al. 1975, Annex C)

Explain the likely magnitude of refraction and magnetic field errors, assuming that first generation automatic levels (e.g. Zeiss Ni2) and long sighting distances (90 m) were used.

3.7 Any levelling of importance is done in double runs, that is forward and backward. This provides the only rigorous check in levelling where the over-determination (redundancy) of measurements is, by default, quite poor. Apart from improving the precision and quality assurance, double runs also eliminate some systematic levelling errors.
Explain why the 'sinking of the staff during the move of the instrument to the next set-up' is cancelled (on average) in the mean of the forward and backward height difference.
(Hint: Draw two consecutive instrument set-ups (and three consecutive staff set-ups) on sloping ground and assume some staff readings. Analyse the height differences in the forward and return direction, noting that height differences are computed as backsight BS minus foresight FS and that the staff common to both instrument set-ups sinks by a certain amount during the move on the instrument.)

3.8 Describe a few possible surveying tasks that could be carried out on a building site with a rotating laser level.

3.9 On a building site, you have been asked to check the level of the form work of a reinforced concrete plate. To do so, you set up the rotating laser level on the form work and you adjust the laser detector to the laser plane at Bench Mark A (Reduced Level = 67.045 m), getting a staff reading of 4.613 m. Similarly, at Bench Mark B (Reduced Level = 68.919 m) a staff reading of 2.738 m is obtained.

(a) What is the collimation height of your laser level?

(b) What staff reading do you expect to get for points on the formwork if the bottom edge of the concrete plate is at a reduced level of 70.100 m?

3.10 On the basis of Fig. 3.14, explain why the laser beam travels in an oblique plane in the presence of a compensation error.

3.11 Draw a cross-section through a rotating laser level in the middle of a field of 500 m radius. Using a horizontal scale of 1:10000 and a vertical scale of 1:2, plot:

(a) how the spherical earth deviates from a tangential plane through the laser level,

(b) the curve described by the laser beam in case of a coefficient of refraction of k = +3.0,

(c) the curve described by the laser beam in case of a coefficient of refraction of k = –3.0.

3.12 Figure 3.19 shows two orientations of a rotating laser level, before and after rotation by 180° about a plumbline on a strictly horizontal tripod top.

(a) in both diagrams, draw the ray path through the laser level from the erroneous positions of the laser diode (see empty diode symbols).

(b) Explain how the tilts of the laser beams exiting to the right from the rotating prism differ in the two diagrams.

(c) Discuss how this difference can be used to calibrate the rotating laser

(d) Elaborate on why it is essential that the tripod head is perfectly horizontal (= level) during such a calibration.


Nominal
Truly Vertical
Beam Axis
Actual
Beam
Axis
Suspension Point
of Pendulum
(P)
Comp
Error
$= \alpha - \beta$
α
β
PL
Plumline
through
Laser Diode
x
Pendulum
Lens
Direction of
Laser Beam
Emission
f
Focal Point of
Pendulum Lens
Laser Diode
$\alpha - \beta$
PL
Plumline
through
Laser Diode
x
f
Focal Point of
Pendulum Lens
Laser Diode

Figure 3.19: Two orientations of a rotating laser level, before and after rotation by 180° about the plumbline, on a strictly horizontal tripod top

3.13 You instructed a crew with earth moving equipment to level a field of 400 m radius around a laser level set up. The work was then carried out at night.

Later you check the work by geodetic levelling (with 50 m sighting distances) from the laser set-up to the edge of the field 400 m away.

What height difference, obtained in your levelling run, between the centre and the edge of the (nominally horizontal) field would you tolerate?

Give reasons!

4. Electronic Theodolites and Tacheometers

4.1 Types of Electronic Theodolites and Tacheometers

In the discussion below, the term 'theodolite' is used in a very broad sense. The term is applied to all devices which measure horizontal directions and zenith angles by electronic means.

This chapter deals only with the angular measurement section of electronic theodolites and tacheometers. For a complete discussion of the electronic distance measurement (EDM) aspects of electronic tacheometers, the reader is referred to the EDM textbook by Rüeger (1990 1996). The special aspects of 'reflectorless' EDM are, however, discussed in Sections 4.1.8 and 5.1.

4.1.1 Electronic Theodolites

The electronic theodolites are replacing the optical theodolites which do require a visual reading of the glass circles and do not permit real-time electronic data recording. Electronic theodolites are easier to use as the circles are read electronically and the angles displayed on a read-out screen. All electronic and optical theodolites can measure horizontal directions and zenith angles as well as distances by stadia (fixed-hair vertical staff tacheometry with the aid of the stadia hairs on the reticle).

4.1.2 Electronic Tacheometers

The electronic tacheometers (sometimes referred to as 'total stations') are replacing the older optical tacheometers (optical theodolites specialised for optical distance measurement). The latter permitted optical distance measurement with an accuracy of between ±10 mm (horizontal staff tacheometry) and ±100 mm (vertical staff tacheometry), depending on the principle used. Horizontal staff tacheometry was never widely used in Australia. Electronic tacheometers are electronic theodolites with a built-in electronic distance meter. They measure horizontal directions, zenith angles and slope distances. Using the on-board computer, height differences and horizontal distances can be computed and displayed. The electronic tacheometers can measure distances more easily and more accurately than optical tacheometers. Also, much longer distances can be measured, typically 1 to 2 km to a single prism reflector. Because of the on-board distance meter, most electronic tacheometers do not have stadia hairs on the reticle.



Figure 4.1: Two electronic tacheometers; Topcon GTS-701 on the left and Nikon DTM-720 on the right. Both instruments store data on PC-cards which slide into the side panels.

The first electronic tacheometers (or 'total stations') were the Zeiss Reg ELTA 14 (released in 1970) and the AGA Geodimeter 700 (released in 1971). These instruments were quite large and heavy. At that time, data recording was on paper tape (like in telex machines) with the Reg ELTA 14 and on (audio) cassette tapes with the Geodimeter 700. A second generation of instruments was released around 1978 by Hewlett-Packard, Wild and Zeiss, with the Zeiss Elta 2 being the first instrument with slide-in memory modules (RAM) for data recording. Today, all manufacturers of surveying instruments are producing electronic tacheometers and electronic theodolites. Most instruments sold are, however, electronic tacheometers because they allow the three-dimensional coordination of points from a single instrument set-up. (Naturally, all professionals will survey important points from two different stations, for quality assurance purposes and to improve the precision by taking the mean of the two solutions.)

Electronic tacheometers have become the workhorses of surveyors and geomatic engineers for detail and contour surveys, for control surveys and for setting-out work. EDM-Height Traversing with electronic tacheometers can replace the traditional line levelling with levelling instruments (see Rüeger 1995 and Rüeger & Brunner 1981). On slopes, EDM-Height Traversing is much less affected by refraction than line levelling. Some survey work presently carried out with electronic tacheometers will eventually be replaced by GPS survey techniques, at least where GPS signals can be received. This change is likely to happen as soon as GPS techniques can compete in terms of ease of operation, efficiency, quality assurance and cost.

4.1.3 Gyro-Theodolites

The integral gyrotheodolites and the gyroscope attachments are replacing the earlier (magnetic) compass theodolites and theodolite attachments. Compass theodolites were capable of measuring magnetic bearings to ±1 minute of arc at best. Tubular compass attachments are still available for some instruments to give magnetic bearings and, in fact, may be used for the provisional orientation of gyrotheodolites to true north. The magnetic declination must be considered when using a magnetic compass for this purpose.

After approximate orientation to geographic ('true') north, the north-seeking gyroscope determines the direction to geographic north. Once the horizontal direction to north is established, other points can be sighted to. The clockwise angle between the direction to north and the direction to another point is called azimuth. The azimuth is obtained simply by taking the difference of the directions to the point and to north.

Two types of gyrotheodolites are available. The most precise gyrotheodolites are integrated instruments, such as the Sokkia AGP1 Auto Gyro Station and the DMT Gyromat *2000* by the Deutsche Montan Technologie. Both gyrotheodolites are based on the Gyromat design and give true north to ±6 seconds of arc in about 6 minutes of time. These precision gyrotheodolites are semi-automatic and are used widely underground in tunnels or mines. In long tunnels, the measurement of the azimuths of well distributed lines in traverses greatly improves the lateral precision (across-track) of such underground traverses. For example, the Gyromat 2000 gyrotheodolites were successfully used in the 42 km long tunnel between England and France.



Figure 4.2: Gyromat 2000 with attached Zeiss electronic theodolite. Please note that this particular gyrotheodolite does not fit standard tribrachs or tripods.

Gyro attachments were available for a number of optical and, later, electronic theodolites. These were typically mounted on a bridge between the two standards of the host theodolites. The Wild GAK1 gyro attachment gives true north to ±20 seconds of arc in 20 minutes. A similar accuracy is quoted for the Sokkia GP1-2 Gyro Station (Electronic tacheometer SET 3 with GP1 Gyroscope attachment). The measurements with the gyro attachments are manual and require some skills of the observer.

4.1.4 Motorised Electronic Tacheometers

Motorised (servo-driven) electronic tacheometers and theodolites can be configured and used in many ways. Figure 4.3 gives an indication of the various implementations of servo-technology using the example of the Geodimeter Model 600. This servo-instrument offers different operating modes. 'Conventional Surveying' with a servo-instrument means that the use of the horizontal and vertical motion clamps is a thing of the past; the instrument is turned by the motors under control of the observer through the pointing knobs. Repeated measurements to targets can be programmed so that the instruments turns itself from one target to the next. Only the fine pointing is done by the observer. 'Surveying with autolock' with the Geodimeter 600 requires a tracker unit for the instrument and a special reflector, which assists the tracking. Once the instrument is pointed approximately to the reflector unit, pointing is automatic; no focussing is required and the reflector is followed automatically. Geodimeter claims that the automatic pointing is more accurate than the visual pointing by an observer.



Figure 4.3: Different options of automation with a motorised electronic tacheometer (after Geotronics 1994)

'Remote controlled surveying' means that the instrument is controlled from the reflector and that point coding, recording and calculations are carried out at the reflector. All the instrument operator has to do is to point to the reflector. A radio-link connects the instrument and the reflector in this case. 'Robotic surveying' requires a tracking unit and a communication unit for the instrument and a special reflector, a radio unit and a keyboard for the reflector. The unmanned instrument will automatically locate and follow the reflector. Pointing is automatic. A search routing will pick-up the reflector again should it be lost during tracking. Surveys can be carried out at night, as the instrument operation is fully automatic. (Light is naturally required for the operator at the reflector.)

In 2003, motorised electronic tacheometers are supplied by Geotronics, Leica, Sokkia, Topcon and Trimble (now incorporating Geodimeter and Zeiss) for some or all of the modes of operation discussed above. Two important applications of motorised theodolites and tacheometers are discussed below.

4.1.4.1 One-Person-Survey-Systems

In this case, the operator carries the reflector around and inputs point information; the instrument maintains pointing to the moving prism and executes measurements when instructed through a radio or optical communication link. The one-person-survey-systems can be used for detail and contour surveys as well as for setting out work. The great advantage of these systems is that the expertise of the operator is used at the reflector, that is at the point surveyed or set out. The routine work at the instrument is taken up by the robotic instrument. In 2001, such systems are available from Leica (TPS1100 series with RCS1100 remote control), Topcon (AP-L1A and AP-L1) and Trimble (5600 Series (Geodimeter) and Zeiss Elta S10/S20 'Space').



Figure 4.4: Implementation of the Topcon one-person-survey-system (after Topcon 1994)

The basic components of the Topcon one-person-survey-system are depicted in Figure 4.4. The figure shows the instrument, the 360° multiple prism assembly, the reflector pole, the radio communication units at both ends, the data terminal and the carrying belt for the battery packs at the reflector. The Topcon AP-L1 has a horizontal and vertical search facility, which can locate and point to a standard prism around 360°. The prism is found faster if additional information (approximate bearing) is communicated from the reflector operator via the radio link. The AP-L1 telescope axis is shared (coaxially) by the visual telescope, the EDM beam and the tracker. The fine pointing is carried out in steps of 2.5". Moving prisms can be tracked up to angular speeds of 10°/s (63.5 km/h at 100 m). The data terminal allows the remote operation of the instrument and stores the measured data, which are transmitted through the radio link. The usual field computations can also be carried out.

Investigations (Höglund 1994) have shown that one-person-survey systems allow a 30% increase in the number of points surveyed per hour and the survey of 200 points per person hour (against 77 points per person hour for a conventional electronic tacheometers with a two-person field party). When setting out with a two-person field party, the time spent per set-out point is half of that of conventional systems. The higher cost of a one-person-survey-system can be recovered in less than one year because of the saving in staff costs.



Figure 4.5: Two instrument stations of one-person-survey systems: Topcon AP-L1 on left and Geodimeter 600 on the right.

4.1.4.2 Automatic Monitoring Systems

Fully automatic systems (surveying robots) are being used for the periodic or semi-continuous monitoring of structures (buildings, bridges, walls, tunnels, railway lines), natural slopes, rock faces and mine pit walls. These systems are usually running under the control of an external computer. The latter is also used for data recording and data processing. Typically, the systems are trained by manually pointing to all targets in the desired sequence. This information is then later used to find the points again during the routine measurements. A fine pointing might be executed during the measurements in each epoch, either with the use of a separate tracker, of the EDM beam or with an on-board CCD-camera with associated image processing and pattern recognition software. A search might be launched if a point is not in the field of view after the approximate pointing.



Figure 4.6: Wild TM3000D with mounted Wild DI3000 pulse distance meter on left and Leica TCA1800 on the right. A system as shown on the left was operating at UNSW using Leica's APS software. The TM3000 does not have any slow motion screws and clamps. The telescope and alidade movements are controlled by the external computer or a joy stick. The instrument on the right is motorised, can track reflectors and can automatically point to reflectors.



Figure 4.7: Principle of the measurement lay-out in slope monitoring (after Geotronics 1989)

With the Wild TM3000D, distances are measured to mm accuracy and the directions and zenith angles (using EDM pointing) to 2–5" accuracy. The inherent angular accuracy of the TM3000 can only be realised with the use of an on-board video camera. Leica offers a software suite (APS Win) for the different configurations of its **A**utomatic **P**olar measuring **S**ystem (APS). This software supports deformation measurements, machine guidance, surface scanning and general purpose monitoring and can be adapted to other repetitive measuring tasks. The accuracy of the point determination depends on the accuracy of the hardware as well as on the sophistication of the processing software, in particular in the area of refraction corrections and corrections for instrument errors.

All motorised electronic tacheometers that feature automatic pointing and, possibly, automatic target searching, can be used for automatic monitoring tasks, provided that the control software for the field operation is available. In 2003, instruments such as the Sokkia SET4110M, the Topcon GMT-100/100L, the Trimble 5600 (ex Geodimeter?) / 3600 (ex Zeiss?) series of instruments and the Leica TCRA1100 series are available and have been (or could be) programmed for monitoring tasks.



Figure 4.8: Principle of 3D-coordination with a two-theodolite measuring system (after Leica 1992). The horizontal distance between the two instruments ('baseline') is denoted by b and the height difference by h. The horizontal angles are shown as 'Hz' and the vertical angles (90° minus zenith angle) as 'V'.

4.1.5 Motorised Electronic Video Theodolites

In video theodolites, the objective projects the image of the target not only onto the reticle but also onto the image plane of an internal CCD camera. The two ray paths are split by a beam splitter in the telescope. For search purposes, an alternative wide angle image can be switched through to the CCD camera. The CCD array of the Wild TM3000V is 8.8 mm by 6.6 mm with 500 x 582 pixels. The pixel size is 17 μm by 11 μm. The video signal is taken from a special port on the video theodolite and input into a frame grabber on a personal computer for further digital image processing. Object recognition software has to be used to locate a target on the image. Once a target has been identified on the image, the coordinates of the centre of the target can be computed. Knowing (from calibration measurements) the angular offsets of the CCD array's pixels from the centre of the cross hairs, the angular offset of the target from the crosshairs can be found and added to the instrument's readings of the horizontal direction and the zenith angle to give the angular measurements to the target.

This process can be very accurate (e.g. ±1"), so that the full resolution of the instrument is effective. In the 1990s, motorised electronic video theodolites were released by Kern and Wild (now Leica in both cases), namely the Kern E2SE and the Wild TM3000V. With video theodolites, the size, shape and illumination of the targets is very important. Sometimes, reflective targets are used and illuminated with a light on-board of the video theodolite. The Wild TM3000V could be equipped with a light which projects an infrared beam along the telescope axis. On other occasions, a strong laser beam was projected by a laser theodolite on to the object to me measured. The laser dot could then be used as a target by other (video) theodolites. Focussing was not automatic. Once a target was pointed to manually (i.e. in a 'training' session), the focus position was recorded by the computer and then reset (by a servo motor) during subsequent production runs.



Figure 4.9: Motorised laser precision theodolite Wild TM3000L (on left) and Wild TM3000V motorised precision video theodolite (on right). A special version of the video theodolite (TM3000V/D) permits the attachment of a distance meter.

Figure 4.8 shows a typical application of motorised video theodolites. After initial training, the two (or preferable more) motorised electronic video-theodolites can take repeated measurements to the points of interest on an object. The three-dimensional coordinates are obtained by intersection. The length of the baseline is not directly measured. The positions of the two (or more) theodolites are derived from measurements to marks of given coordinates or from the measurements to the object and to a scale bar of known length. The precision of the resulting object coordinates depends on the distance from the instruments, the intersection angle, the quality of the targets and the stability of the instrument set-up. Angular measurements to one second of arc can give positions to 0.01 mm over 2 m, for example.

In 2003, the video theodolites are no longer available. Depending on application, the video theodolites are now replaced by motorised electronic tacheometers (reflective targets required), by scanning reflectorless motorised electronic tacheometers or by dedicated laser scanners. The laser scanners may be able to detect traditional (non-reflecting) survey targets on objects and structures if their reflectance is sufficiently different from the surface around them.

4.1.6 Laser Theodolites

Laser theodolites have been available before the time of electronic theodolites, either as integrated systems or as a laser eyepiece attachment to standard optical theodolites. The same laser attachments can naturally be fitted to electronic theodolites and tacheometers. Laser theodolites project a visible laser beam along its line of sight (He-Ne gas laser or visible laser diode). They can be used for machine guidance, alignment or as a targeting device for non-contact measurements of structures and objects. If a motorised laser theodolite is combined with a motorised video theodolite, the system can be programmed to scan the surface of an object or structure, with the video theodolite tracking the laser dot after an initial pointing to the laser dot.

Motorised laser precision theodolites may use an on-board semiconductor laser diode for industrial applications (close range) or a helium-neon gas laser for the monitoring or measurement of larger structures (for example in civil engineering). The latter is usually attached to the motorised instrument through a glass fibre connection. The instrument shown in Fig. 4.9 is linked to such an external HeNe laser. The laser theodolites may adjust the laser output power to mach the intensity of the laser dot to the brightness of the object surface. In order to generate a laser dot of uniform intensity, the laser beam is sometimes rotated inside specialised instruments. For example, the TM3000L rotates the laser beam at 30 rpm to give a circle of 0.68 mm diameter at 5 m.

At the turn of the century, lasers are being used less and less for machine guidance. In part, they are being replaced by motorised electronic tacheometers that can measure to reflectors mounted in critical positions on machines. This allows guidance along curves as well as straight lines. If more than one reflector is mounted on the machine, the motorised electronic tacheometer can provide information on the heading (azimuth), pitch (along-track tilt) and roll (across-track tilt) of the machine, besides horizontal and vertical position. In open air, lasers are also replaced by guidance systems based on the Global Positioning System (GPS).

4.1.7 Tracking Electronic Tacheometers

Before the appearance of the one-person-survey-systems, a number of manufacturers did develop specialised tracking electronic tacheometers ('Autotrackers'). These instruments can follow a moving reflector once an initial manual pointing has been carried out. They measure horizontal directions, zenith angles and slope distance continuously and can transmit these data to the reflector, if required. These instruments are typically used in near-shore hydrographic surveys. In this case, the instrument is set up on a shore station of known coordinates and orientated to give a bearing read-out. Bearing and (horizontal) distance are transmitted to the vessel with the reflector, where the vessel position is computed and merged with the data from the echo sounder or other hydrographic instruments.

Typical instruments were the Geodimeter 140T and the Krupp Atlas 'Polarfix'. A number of other manufacturers offered similar systems. The latter had a range of 10 km, an angular precision of ±(50 mm + 50 ppm) and a distance precision of ±(150 mm + 50 ppm). These systems were also used for the position fixing of other vessels, tracking of buoys, tracking of land vehicles, tracking of helicopters, position fixing of construction vehicles and the dynamic measurement of roads and other linear features of terrain. By the turn of the century, these tracking tasks were taken over by GPS systems or appropriately configured main-stream motorised electronic tacheometers.

4.1.8 Reflectorless Electronic Tacheometers

This section gives an introduction into the historical development of electronic distance measurement (EDM) to non-cooperative targets. The particular aspects of reflectorless EDM with current surveying instrumentation are discussed later in Section 5.1. 'Reflectorless' electronic distance measurement (EDM) to passive ('non-cooperative') targets has been used in surveying for quite some time. The first geodetic pulse distance meter became available in 1982: The Fennel 2000 was a stand-alone distance meter, able to measure to non-cooperative targets. Military rangefinders with 1 - 10 m resolution have been around even longer. Zeiss released the first 'reflectorless' electronic tacheometer ('total station') in 1993. Broad acceptance by the surveying profession followed once Leica, Topcon and Trimble released their reflectorless instruments in 1998, followed by Nikon in 1999. The range of reflectorless EDM depends heavily on the type of surface that is measured to and its orientation to the measuring beam. At the time of writing, 50 - 100 m seem to be typical maximum distances to 'natural' targets although Zeiss (now Trimble) quoted a reflectorless range of their RecElta RL electronic tacheometer of 400 m.

The 'reflectorless' instruments can also be used to measure, in 'reflectorless' mode, to the traditional EDM glass prism reflectors. This allows the measurement of distances of a few kilometres, a range that was once reserved for the earlier class of medium range distance meters. Please refer to Section 5.1 for further information on reflectorless EDM.

4.1.9 Scanning Electronic Tacheometers

It has been mentioned before that motorised 'reflectorless' electronic tacheometers can be programmed to measure distances at predetermined values of horizontal directions and zenith angles. This would permit to create a three-dimensional model *of the visible surfaces* surrounding the instrument. As electronic tacheometers are optimised for accuracy rather than speed, special devices have been developed for pure scanning applications. These devices are sometimes advertised as *Laser Radar*, *Ladar* and *Lidar* with reference to the well-known *radar* (RAdio Detection And Ranging). Some of these scanners resemble motorised electronic tacheometers, others resemble the laser scanners used for laser shows in the entertainment industry. In the latter case, the (pulse) distance meter is usually installed with the beam axis straight up. The beam is then reflected by a scanning mirror with two degrees of freedom, with one vertical and one horizontal axis. Angular encoders on the two axes measure the equivalent of horizontal directions and zenith angles.

Three-dimensional scanners can be used for architectural surveys, volumetric measurements, object recognition, process control and collision protection. An early three-dimensional laser scanner (3D-Ladar) by Ibeo had a distance precision of ±20 mm and an angular resolution of 2^{14} in a full circle (80 seconds of arc). The range was up to 500 m and the rate of distance measurements 4600 per second (4600 Hz; Ibeo 1991). Special devices have also been developed for the monitoring of the wear of the lining of converters and ladles in steel making. In this case, distances are measured to the red-hot (1400°C) refractory linings inside the converters and ladles. The system manufactured by VTT Electronics (Oulu, Finland) gives an accuracy of 2 mm over 20 m with a measuring rate of one point per second (Ailisto et al 1996).

By the turn of the century, laser scanners had developed as a special class of instruments for the reflectorless measurement of indoor and outdoor spaces, objects and structures. These instruments can scan a three-dimensional space at high speed and provide 3D coordinates of all objects and surfaces in view. Powerful postprocessing software is then able to convert the data into plans, 3D-representations and computer aided design (CAD) files. This class of specialised instruments is discussed in Section 5.2.

It is mentioned again that any robotic electronic tacheometer, that is motorised and permits reflectorless EDM, can be programmed to scan a three-dimensional space like a dedicated laser scanner. However, the main-stream robotic electronic tacheometers will take much longer for the measurements. Also, it is likely that the range of main-stream robotic electronic tacheometers is smaller and that no powerful postprocessing software is available (to convert the data files to CAD files, for example) for this application of electronic tacheometers.

4.2 Features of Electronic Theodolites and Tacheometers

As far as the telescope and the mechanical construction are concerned, the electronic theodolites differ very little from second order optical theodolites. In consequence, most instrumental errors are the same and most operational procedures remain unchanged. In some respects, however, the electronic theodolites and tacheometers differ significantly from the instruments with optical circles. Some important differences and similarities are now discussed to provide a better understanding of the newer technology and its use.

4.2.1 Circle Types

The horizontal and vertical circles are read electro-optically and the readings are displayed electronically. This means that power is absolutely necessary because the circles cannot be read manually. It is preferable that the essential measurements are displayed simultaneously, for example the horizontal direction, the zenith angle and the slope distance (H, V, SD). The circle graduations used in electronic theodolites are etched onto glass disks using photolithographic techniques. They have approximately the same diameter as in optical theodolites. The Topcon ET-1 features a circle diameter of 80 mm, for example. In other disciplines, electro-optical angle measuring devices are referred to as optical encoders. Three basic types of electronic circles ('angle encoders') can be distinguished.

4.2.1.1 Incremental Circles

Pure incremental circles feature only a uniform radial line pattern. An electro-optical incremental circle is shown in Figure 4.11 (on the right). The pattern is a series of equidistant light and dark fields. The individual graduations cannot be identified as they have no 'labels'. The changes in the horizontal direction and the zenith angle are obtained by counting the number of light and dark fields passing through an electro-optical read-out during the rotation of the theodolite and telescope, respectively, and by multiplying the number of cycles with the angular equivalent of one graduation. The instrument resets the count to zero after switch-on. So, in principle, the zero of the circle (circle orientation) is lost at turn-off or in the case of a loss of power. (Some modern instruments store the last horizontal circle reading into non-volatile RAM in the on-board computer and reset this value after switch-off. If the instrument is rotated in any way whilst turned off, the horizontal circle will have a wrong orientation after re-powering the instrument.) It should be noted that most modern instruments do not have pure incremental circles. The reading of the electro-optical incremental circles is discussed in more detail later, in another section.



Figure 4.10: Part of a rotor and a stator of a circular Inductosyn (after Inductosyn Corp. and Walcher 1985)

Incremental circles do not have to be of the electro-optical type. Some Geodimeter (now Trimble) instruments are equipped with an inductive circle reading system that operates on the Inductosyn principle. Two parallel disks (rotor and stator) carry equivalent conducting square wave patterns. (Refer to Fig. 4.10.) The square wave patterns are applied to glass disks using the same principles as in the manufacture of printed circuits. One of the disks is fixed. The other one moves with the alidade (horizontal circle) or the telescope (vertical circle). When turning one disk against its opposite, the phase of the measuring signal changes. This phase change is averaged over the entire square wave pattern around the circle and is, thus, free of any circle eccentricity errors and circle graduation errors. Inductive circles reading systems can be as accurate as 2" and are less susceptible to contamination by dust than optical circles. On the other hand, they are more susceptible to electro-magnetic interference. The manufacturing tolerances are quite tight. Measuring the phase to one part in one thousand gives a resolution of 1.3 seconds of arc. Inductosyn systems are widely used for radar antennas, in engineering-works, machine-tools and coordinate measuring machines.

4.2.1.2 Quasi-Absolute Circles

In this context, quasi-absolute circles are defined as incremental circles with one additional reference mark. The reference mark (see Figure 4.11, at top, on the right) allows to start the cycle count at an absolute reference. This means that the circle readings before a power loss can be recovered after recommencement of the measurements (unless the instrument was instructed to set a specific circle reading in a particular direction before the power loss). To initialise the vertical circle, the telescope is typically tilted through the horizon (zenith angle of 90°); to initialise the horizontal circle, the user has to rotate the alidade through (a maximum of) 360°. It should be noted that all vertical circles must be at least quasi-absolute as the zenith angles could not be referenced to the zenith otherwise.



Figure 4.11: Basic layout of an absolute circle (on the left) and an incremental circle (on the right), after BEI (1987). The incremental circle also carries a reference mark (at the top). The innermost graduation of the absolute circle is equidistant, like the graduation of the incremental circle. Each graduation on the absolute circle can be identified by the unique binary code on the seven outer tracks.

4.2.1.3 Absolute Circles

On absolute circles, each circle graduation can be uniquely identified. Figure 4.11 (left) shows an absolute circle, with the incremental (equidistant) graduation on the innermost track. The outer tracks carry a binary pattern, which fully identifies each of the basic graduations. In Figure 4.11, seven code tracks are visible. This code has a resolution of 128 and, thus, fully identifies the 64 graduations on the innermost track. It is obvious that absolute circles with binary patterns must have a readout system for each track. This is expensive in manufacturing.

Not all electronic theodolites and tacheometers with absolute circles have a binary pattern for the identification of the incremental high resolution graduation. The Wild T2000/T3000 theodolites from Leica use a rotating quasi-absolute circle, which is read against the fixed part and the rotating part of the instrument. This gives the (absolute) angle between the fixed readout and the moving readout. Since the Wild TC1600 family of instruments, Leica uses a bar code pattern on the circle which uniquely identifies each position. (See Figure 4.12.) The processing (image matching) is similar to that of the Leica bar code levels.

Instruments with absolute circles do not 'lose' the circle readings in case of a power loss, be it due to a change of battery, the automatic power-off facility of modern instruments or an accidental switch off.



Figure 4.12: Part of the bar code circle of a Wild TC1600.

4.2.2 Diametrical Circle Reading

Circle eccentricities are a very important source of error in angular measurements. In the case of horizontal direction measurement, they can be eliminated by measuring in two faces. In zenith angle measurement, observation in FL and FR do not eliminate the circle eccentricity completely. A number of techniques can be used to eliminate the circle eccentricities in single face measurements with more accurate theodolites and tacheometers. (The coincidence reading micrometer was used in optical (one-second) theodolites to read the circle simultaneously at two points 180° apart and, thus, to eliminate the circle eccentricity by reading the mean). The elimination of circle eccentricities through appropriate instrument design is more important for zenith angle measurement, because the user cannot eliminate the effect by measurement in two faces.

For more accurate work (like the surveys previously done by optical 'one-second theodolites'), most surveyors and geomatic engineers use only instruments which eliminate the circle eccentricity one way or another. Several techniques are presently employed to 'eliminate' the effects of circle eccentricity on angular measurements:

- Some instruments average the circle reading all around the circle. This effectively eliminates the eccentricity error, as the sum of the error around the circle is zero. This averaging approach is used by Geodimeter with the Inductosyn circle reading and by Leica with the rotating circles in the T2000/T3000 instruments.

- Most accurate electronic theodolites and tacheometers employ the traditional diametrical circle reading, where the circles are read separately and simultaneously on opposite sides of the circle. The two readings are then merged electronically.
- Some other instruments read the circles only on one side, but use a factory calibration of the circle eccentricity to correct all measurements on-line before the readings are displayed and stored. Such instruments were the Wild TC1010/1610/1600 electronic tacheometers, for example. The accuracy of the on-line correction depends on the accuracy of the original calibration as well as the stability of the circle mounting over the life of the instrument.

4.2.3 Electronic Level Sensors versus Vertical Circle Compensators

4.2.3.1 Definition of an Electronic Level Sensor

A tilt sensor measures the dislevelment of the vertical axis in digital form and the associated computer corrects at least the zenith angles accordingly. Instruments with single-axis level sensors (parallel to the telescope) can only correct the zenith angles. Instruments with dual-axis level sensors are better for precise measurements or steep sights because they can correct the zenith angles and the horizontal directions for the two components of the measured dislevelment of the vertical axis. Most electronic theodolites and tacheometers use level sensors. Precise instruments feature dual-axis level sensors. With a dual-axis level sensor, the inclination of the vertical axis can, sometimes, be displayed and used for the levelling of the instrument.

4.2.3.2 Definition of a Vertical Circle Compensator

The optical reading of the vertical circle is deviated physically to compensate for the dislevelment (parallel to the plane of the vertical circle) of the vertical axis. This ensures that the zenith angle readings are truly referenced to the zenith. Some electronic theodolites and tacheometers may use vertical circle compensators. The Wild (Leica) TC1600 was such an instrument.

As defined above, the difference between a compensator and a level sensor is that the mechanism of a compensator optically deviates the vertical circle reading whereas a level sensor measures the dislevelment of the vertical axis and corrects the vertical circle reading in real-time by the on-board computer. Both approaches ensure that the correct zenith angle is obtained even when the vertical axis is not truly vertical. Before the introduction of vertical circle compensators, altitude bubbles were used to set the vertical circle reading index to horizontal. As this had to be done before every single zenith angle reading, it was less convenient, less accurate and quite time consuming.

Two types of compensators were used in optical instruments. One used a mechanical pendulum to define the vertical direction and the other the surface of a suitable liquid to define a horizontal plane. Vertical circle compensators are different from those in levels in the sense that they deviate only the ray path of the vertical circle readings and not the entire telescope image. The vertical circle compensators were (almost) always uni-directional. The Kern (now Leica) DKM-2AM did have a dual-axis compensator, but the trunnion axis component of the inclination of the vertical axis had to be read-out with an additional device (trunnion axis micrometer) and the corrections to the direction measurements applied by hand calculation.

As compensators are being phased out in electronic theodolites and tacheometers (and replaced by independent level sensors) they are not discussed any further in this context. Level sensors are discussed later in more detail. Instruments without level sensors (or compensators) are not up to the standard required by geomatic engineers and surveyors as they do not relate the zenith angles directly to the plumbline. In this case, the zenith angles refer to the mechanical vertical axis, the verticality of which depends entirely on the accuracy of the levelling of the instrument.

4.2.4 Data Recording

Electronic data recording saves a lot of time by replacing the manual booking (and the 'booker' assisting the observer). Data recording also avoids the well known gross errors experienced in manual booking, at least as far as the actual electronic measurements (horizontal direction, slope distance, zenith angle) are concerned. Additional input (e.g. height of instrument, height of reflector, point number, point description) through the keyboard is still subject to the well known problems.

Most electronic theodolites and tacheometers can electronically store data on one or more of the following media:

- on-board RAM
- (computer) industry standard memory (PCMCIA) cards (**P**ersonal **C**omputer **M**emory **C**ard **I**ndustry **A**ssociation), now known as PC-cards
- make specific memory cards and modules
- make specific external data recorders ('electronic field books')
- external notebook or laptop computers

The data stored in one of the four first devices need to be down-loaded to a computer for further processing. Additional cables and/or devices and software are required for this purpose. PC cards may be inserted into laptop and desktop computers, that feature a PC card port, for the transfer of data. Data can also be up-loaded, for example coordinates for setting-out work. It should be noted that some instruments, that accept PC cards, cannot record data on-line onto the cards. In these cases, the data are recorded onto RAM and have to be transferred to the PC card later, for example before moving the instrument or at the end of a day.

Unfortunately, all makes of instruments (or even different types of the same make) have different recording formats. There are also some differences between makes and types on how a full data set can be recorded (e.g. one or more key strokes). The sophistication of entering point numbers and other attributes of surveyed points varies greatly. Alpha-numeric entry is sometimes restricted or not possible.

4.2.5 On-Board Computing

Some on-board computing is available on all modern instruments. Sometimes, software modules are offered as optional items by manufacturers. A number of instruments support the personal computer industry's operating systems (initially DOS, now Windows) and programs written by the user. Some examples of what pre-stored programs can do are:

- working out the mean of FL and FR observations, and executing the error analysis in direction measurement with multiple arcs. To be useful, such programs must be able to cope with the standard procedure of direction measurement, namely the sequence $FL_1–FL_2–FL_3–$ ... $–FL_n–FR_n–$ ... $–FR_3–FR_2–FR_1$.
- computation of the co-ordinates and the elevation of the instrument station using resection (free stationing). The horizontal positioning should work with directions only as well as with directions and distances and should allow and use redundant data. The precision of the determined coordinates should be displayed. The determination of the elevation should be possible with zenith angles only or with zenith angles and slope distances and should allow and use redundant data. The precision of the determined elevation should be displayed.
- computation of bearings, for example for the purpose of orientating the instrument to 'north'.

The many on-board programs, which use the electronic distance measurement (EDM) part of the instruments, are not listed here. Some additional computations are usually available for the guided instrument calibration routines. More on these below.

4.2.6 Power Supply

All electronic theodolites and tacheometers need power to operate. Depending on the make and the type of instrument, direct current is supplied by one or more of the following sources:

- internal rechargeable (nickel-cadmium, NiCd, or nickel-metal-hydride, NiMH) batteries. These are make and type specific. The voltage varies between makes and, sometimes, different types of the same make. Common voltages are: 6 V, 7.8 V, 8.4 V, 12 V. Some surveying instrument manufacturers are now using widely available video camera ('camcorder') batteries as standard power sources for their instruments.
- external rechargeable NiCd batteries. These are also make and, sometimes, type specific.
- lead-acid 12 V car or motor bike batteries. These can be attached to electronic tacheometers and theodolites with the conversion cables supplied by the manufacturers. These make and, sometimes, type specific 12V DC battery cables may include a dc-dc converter to reduce the voltage to the level required by the instrument. As it is easy to connect the 12 V batteries the 'wrong-way-round', the 12 V battery cables should always include reverse polarity protection.


DISTOMAT DI 3000
DC-DC CONVERTER (7A max)
15V dc
12V dc
12→15V
GIF11
BATTERY
TOSHIBA T3100SX
TM3000D
RS232
GEV87
RS232
15V dc
12V dc
GEV86
12→15V
DC-DC CONVERTER (2.5A max)
GSE1 Control Unit
BATTERY

Figure 4.13: Configuration of the Wild (Leica) Automatic Polar System (APS) once used at UNSW. The Wild (Leica) T3000D/DI3000 system did operate entirely under the control of software running on the computer. The 12 V to 15 V dc-dc converter supplying the interface unit (Wild GIF11) was custom built. The dc-dc converter for the computer was supplied by Toshiba.

4.2.7 Communication with Personal Computers

A two-way communication between an instrument and a computer is often possible via a RS-232C interface. Some newer instruments support DOS commands, at least for the import and the export of files. If the instrument's command language is known, the instrument can be instructed to carry out functions which are usually triggered by buttons on the keyboard.

An example for the implementation of a communication link between an electronic tacheometer and a computer is shown in Figure 4.13. The figure shows the connections between a motorised theodolite (Wild TM3000D) with mounted pulse distance meter (Wild DI3000), a computer and a joystick unit (Wild GSE1). In this case, an interface unit (Wild GIF11) is placed between the instrument and the computer. The cable between the interface and the instrument carries not only the supply current but also the two-way communication. As the figure shows, the instrument can be run either from the computer or from the control unit (GSE1). The selection between the two modes is by either a switch on the interface (GIF11) or by software selection. (The latter requires the second RS232 link between the interface and the computer.) A 'joystick', or the arrow keys on the computer keyboard, are required for any manual pointing since the instrument does not feature slow motion screws. All data are recorded on the hard disk of the laptop computer.

4.2.8 Automatic Focussing, Searching and Pointing

4.2.8.1 Automatic Focussing

The first instruments with an automatic focus were the video theodolites. These instruments could 'remember' the position of the focussing lens only after training. Today, auto-focus as in still and video cameras is available in a few electronic theodolites and tacheometers, such as the Topçon 600AF Series and the Pentax R-100 and R-300 Series. The first Auto Focus Levels (Pentax AFL240/280/320) were released earlier in 1996. According to Pentax, the phase contrast method is used by their autofocus system.

4.2.8.2 Automatic Searching

Before an automatic pointing in the narrow sense (see the following section) can be executed by a robotic electronic tacheometer, the glass prism reflector has to be 'found' first and, typically, brought into the field of view of the telescope. Robotic electronic tacheometers, that can find a prism in a 360° sector around the instrument, are available from a number of manufacturers, such as Geodimeter (ATS, 600 Series, now Trimble), Leica (TPS1100 Series with Powersearch, Topcon (GPT8000A, GTS-800A, APL1A), Trimble (5600), Zeiss (Elta S10 'Space', now Trimble). Most instruments transmit a special beam for the fast acquisition of a (reflecting) target and rotate with a maximum speed of, typically, 45°/s. Typical acquisition times are less that 15 s over a 360° sector. Most systems allow to define smaller search sectors to speed up the search, where possible. Naturally, the search times can also be minimised by continuously following (tracking) of a (usually 360°) reflector.

Some systems require an 'active' reflector assembly, that emits a structured infrared light. Others do not absolutely need an 'active' reflector assembly, but achieve the target acquisition faster with one. The use of an active reflector assembly has the advantage that the robotic instrument does not accidentally lock onto the wrong reflector nor, for that matter, onto another 'foreign' reflecting surface in the landscape. The drawback is that batteries are required at the reflector end.

4.2.8.3 Automatic Pointing

Various forms of automatic pointing were implemented in earlier motorised electronic tacheometers, such as:

- pointing under computer control (either on-board or external) to previously established (and 'trained') points,
- recognition of the image of a target on an internal CCD camera,
- tracking (with a video theodolite) the laser dot projected by a laser theodolite onto a surface, and
- tracking the infrared beam of the EDM instrument which is returned by a reflector.

With time, manufacturers started to implement pointing systems that operate separately from the distance meter and tracking systems but use the same reflector to return the transmitted beam. Typically, these systems allow to determine the angular offset between the line of sight of a roughly pointed telescope and the reflecting target, and then use the servo motors to 'move' the cross hairs onto the (centre of the) reflector. The coarse pointing may be done manually (through the gun sight) or with an automatic search or tracking system.

Since only Leica has explained the principle of it's 'Automatic Target Recognition' (ATR) system in any detail (Haag et al. 1997), this system is discussed further. The Leica ATR uses a separate (coaxial) infrared beam and a built-in two-dimensional CCD sensor. Since this beam is of fixed focus, no focussing is required. On return from the prism, the ATR beam is split from the EDM beam and the visual image and projected onto the CCD sensor. To speed up the processing, the pixel values are summed along columns and rows. Histograms of the column-by-column values and the row-by-row values will show peaks at the centre coordinates of the returned ATR beam. Checks for multiple prisms in the ATR beam are made and the beam power and the exposure times of the CCD array are optimised for background brightness and distance. Once the coordinates of the return beam on the sensor are known, the offsets from the 'centre' of the CCD sensor can be computed. Using the servo motors, the telescope is then automatically pointed very close to the centre of the prism. This is necessary to allow electronic distance measurements and to permit a visual check by the observer.

Figure 4.14a shows the configuration during a typical measurement. The field of view of the telescope is indicated by the letter 'A', the EDM beam diameter by 'D' and the diameter of the initial ATR beam by 'C'. The ATR beam diameter is about one third of the visual field of view. If no return beam is received on the initial coarse pointing ('C' in Fig. 4.14a), the servo motors are used to drive the ATR beam around the initial pointing. This is indicated by the letter 'E' in Fig. 4.14a. The letter 'B' shows the total field of view covered by ATR, after initial pointing and fine search.



Figure 4.14a: Principle of Leica's Automatic Target Recognition (ATR) of a Leica TCA1800 for measurements to a reflector. The letters are explained in the text. (after Haag et al. 1997)

For a measurement to a reflector, the telescope is pointed with the gun sight. No focussing is required. The observer then starts the measuring routine. The instrument checks if the reflector is within the ATR field of view ('C' in Fig. 4.14a). If not, the ATR beam is driven in a spiral pattern around 'C', as indicated by 'D' and 'E' in Fig. 4.14a. After that, the automatic pointing occurs and the distance is measured. This is followed by the measurement of the direction and the zenith angle, which are then corrected for the offsets of the ATR return beam from the centre of the CCD array and 'frozen' in a buffer memory. Finally, the distance and the 'frozen' angles are recorded. The buffer memory is then cleared.

The accuracy of Leica's automatic pointing (ATR) varies between instruments. The measuring principle discussed above applies to the most accurate Leica instruments. For the Leica TCA2003 and TDA5005 precision instruments, the ATR pointing precision is quoted as 1 mm for distances less than 200 m and 2-3 mm for distances between 200 and 500 m. For the Leica TCA1800, the ATR pointing precision is given as 2 mm to 400 m. The Leica TPS700 and TPS1100 Series of instruments are likely to feature a less sophisticated ATR procedure, since the ATR precision is given as 3 mm below 300 m and 'equivalent to angular accuracy' at longer distances.

All Leica instruments with ATR provide an on-board routing to calibrate the CCD sensor's origin (or 'zero' in Fig. 4.14b) in relation to the centre of the normal crosshairs. This requires careful manual measurements in two faces to a reflector at a specified distance. Figure 4.14b shows the two calibration values that have to be determined. Once determined, the calibration values are applied to all subsequent ATR measurements. Haag et al. (1997) make a few suggestions for precision ATR measurements: Let the instrument acclimatise to ambient temperature, use only reflectors with clean glass surfaces, do a very careful ATR calibration when mixing ATR and manual pointing to targets in the same arc of directions. The latter is best done on site before critical direction measurements and, possibly, between arcs.



Figure 4.14b: Calibration of CCD array for the offset of its 'centre' or 'zero' from the centre of the (normal) crosshairs. (after Haag et al. 1997)

4.2.9 Computer Assisted Instrument Calibration

Most instruments feature built-in computerised measuring routines for the calibration of some instrumental errors. Such routines may determine and store the following instrument errors or constants (for later real-time correction): horizontal collimation error, index error of vertical circle, additive constant(s) of single-axis (or dual-axis) level sensors, trunnion axis tilt, calibration values of automatic pointing systems (e.g. V-Corr and Hz-Corr in Fig. 4.14b).

These computer assisted instrument calibrations allow some 'mechanical adjustments' to be replaced by 'electronic adjustments'. Rather than physically adjust components into their nominal positions, as in the past, the errors are now determined, then stored on-board (in non-volatile RAM) and corrected in real-time during the measurements.

Similar to the physical adjustments of the older optical instruments never being perfect, the corrections determined by the pre-programmed routines are only as good as the measurements taken. The stored corrections are thus not error free. Users are reminded that some instrument errors do change with time, temperature and shocks. In consequence, instrumental errors must still be removed by appropriate field procedures (e.g. measurement in two faces) if the specified accuracy of an instrument is to be realised, even if the instrument applies the stored corrections in real-time. Also, the users are well advised to check the stored corrections before starting single face measurements. An inexperienced observer may have stored calibration values that are totally wrong!

4.2.10 Modern Vertical Axis Systems

The construction of the vertical axes of theodolites has changed considerably over the last 50 years. The left side of Figure 4.14c shows the modern bearing used for the vertical axes of the Zeiss (Oberkochen) theodolites. The weight of the upper part is carried by the load bearing (No. 3 in Fig. 4.14c). The stability of the vertical axis is, however, provided by the second and cylindrical bearing (No. 1 in Fig. 4.14c), which extends over the full height of the bearing. This gives a better stability (less wobble) of the vertical axis than two single ball bearings (one at the top, and one at the bottom) could provide. Figure 4.14c also shows a second cylindrical bearing (No. 2 in the figure) for the rotation of the horizontal circle about the vertical axis.



Figure 4.14c: Modern vertical axis systems: Zeiss (Oberkochen) on the left and Topcon ETL-1 on the right. The parts shown on the left are: 1 = ball cage for the cylindrical vertical axis bearing, 2 = ball cage of the bearing of the horizontal circle, 3 = ball bearing carrying the full load of the alidade, 4 = vertical axis. The parts shown on the right are: A = upper plate (on which the rotating upper structure of the theodolite is mounted), B = lower plate (with carries the horizontal circle), C = non-rotating part (attached to the base of the theodolite).

The vertical axis assembly of a Topcon ETL-1 electronic theodolite, shown on the right hand side of Fig. 4.14c, gives a visual impression of a modern design. This instrument was still designed as a 'double-centre', 'double-plate' or 'repetition' theodolite, with two clamps and two slow motion drives for the horizontal motion about the vertical axis. The three layers of holes for mounting screws are testimony to that. The top most level (see 'A' in Fig. 4.14c) carries the upper part of the theodolite, the middle one (see 'B' in Fig. 4.14c) the horizontal circle and the lowest ('C' in Fig. 4.14c) is attached to the (non-rotating) base of the instrument. The upper set of clamp and slow motion drive acts between 'A' and 'B', the lower between 'B' and 'C', allowing the circle to move with the upper part of the theodolite.

Most modern electronic theodolites do no longer have a second bearing, that allows the rotation of the horizontal circle against the base of the theodolite (as explained for the axis systems shown in Fig 4.14c). This means that the horizontal circle cannot be physically turned any more (other than by turning the instrument 120° inside its tribrach) and cannot be set to a given reading (other than by electronic means).

4.3 Circle Reading System of the Electronic Tacheometer Nikon DTM-1

The Nikon DTM-1 uses an electro-optical circle reading. The light and dark increments are produced by the equidistant bars and equidistant gaps. The horizontal circle of the DTM-1 is a fully incremental circle. The vertical circle, by default, is a quasi - absolute circle. The basic principle of the horizontal circle reading is shown in Fig. 4.15. The figure shows that diametrical circle readings are used to eliminate the residual circle eccentricities. The circle of the DTM-1 has a diameter of about 92 mm and carries 10000 graduations. The radius of the circle is 46 mm and the circumference 289.0 mm. Considering the number of graduations over the circumference, the width of the gaps and the bars can be calculated as 14 μm. The radius of an atom is 0.0001 μm and may be used for comparison.

Figure 4.16 outlines the components of the circle reading system of the Nikon DTM-1. Many other instruments operate on very similar principles. On the left of the figure, the two electro-optical systems that read the circle are shown. A light emitting diode (usually infrared) is mounted in the focal point of a lens. The circle is, therefore, illuminated by parallel rays that continue through the glass circle, through the index patterns (masks on glass) onto the photodiodes. According to the mask shown in Fig. 4.15, six separate photodiodes are required to convert the light received in the six windows into electrical currents.

Whenever the readout optics move against the fixed circle (as it happens with the horizontal circle) or whenever the circle rotates through the fixed readout optics (as in the case of the vertical circle), the intensity of the light received by the photodiodes A and B varies. When an opaque field of the mask fully covers a transparent field of the circle, no light is received (= minimum of the sine curve). When a transparent field of the mask fully covers a transparent field of the circle, the maximum of light is received (= maximum of the sine curve). Between the two states, the signal will change, approximately, as a sine curve.



Figure 4.15: On left: View of the circle reading system of the Nikon DTM-1. A light emitting diode and a collimating lens are below the circle. The graduated masks and the photodiodes are above the circle. On right: graduations on the index masks. The top window is blank. This transparent part is used to monitor (and regulate) the light output of the LEDs. A and B refer to the SIN and COS masks, respectively. 'A' and B' duplicate the masks A and B, most likely to reduce systematic errors by a symmetrical lay-out. The bottom window is used on the (quasi-absolute) vertical circle for the detection of the 'zero'- (reference) mark.

The processing of the two signals is shown in Fig. 4.16, namely those of the A (sine) and the B (cosine) masks from both sides. The cosine signal has a 90° delay against the sine signal. The two signals from the other side of the circle feature phase shifts of 180° (-sin) and 270° (-cos). The output signals of the photodiodes are first amplified and then fed into a differential amplifier. The two differential amplifiers take the differences of the two input signals and amplify the result:

$$\sin\phi - \sin(\phi + 180^\circ) = \sin\phi - (-\sin\phi) = 2\sin\phi \qquad (4.1)$$

$$\sin(\phi + 90^\circ) - \sin(\phi + 270^\circ) = \cos\phi - (-\cos\phi) = 2\cos\phi \qquad (4.2)$$

The above equations show that taking the difference of the two input signals already doubles the amplitude. The resulting sine and cosine signals are split for the execution of the coarse and the fine measurement.

4.3.1 Coarse Measurement

The sine and the cosine signals are converted to square waves for the coarse measurement. The coarse measurement is obtained by counting the number of periods (full cycles) which occur between the start and the end of the rotation to be measured. The basic resolution of the coarse measurement is the angular equivalent of the period of the sine and cosine signals, namely 400 grads/10000 = 0.04 grads = 0.04 gon. The coarse measurement of any instrument or telescope rotation is obtained simply by multiplication of the number of counts with 0.0400 grads. The question on how to find out the sense of the rotation (clockwise: positive coarse measurement; anticlockwise: negative coarse measurement) will be addressed later.

The resolution of the coarse measurement (about 130 seconds of arc) is not accurate enough. To get a better resolution, it is necessary to determine the fraction ϕ of a graduation interval between a circle graduation and a graduation on the mask. This process is called interpolation or fine measurement.


DC Amplifier
LED
Lens
Photo Diodes
Index Pattern
90°
0°
Graduated Circle
Differential Amplifier 0° – 180°
sin ϕ
Triggers/ Comparators
Up/Down Counter
cos ϕ
Differential Amplifier 90° – 270°
Lens
DC Amplifier
180°
270°
LED
Index Pattern
Photo Diodes
Multiplexer
Coarse Measure-ment
8-bit Analogue-to-Digital (A/D) Converter
Fine Measure-ment
Microprocessor
April 1994 JMR

Figure 4.16: Block diagram of the circle reading system of the Nikon DTM-1.

4.3.2 Fine Measurement

The sine and cosine signals are multiplexed for the fine measurement. This means that the sine and the cosine signals are processed one after the other in a time sharing mode. The two signals are available in analogue form as voltage levels, which change for any introduced rotation. For digital processing, the voltage has to be converted to a number. This is achieved with an analogue-to-digital converter. In the DTM-1, the maximum voltage is converted in 256 increments (2^8). The 8–bit analogue-to-digital (A/D) converter changes the amplitudes of the sine and cosine signals to numbers (e_0, e_{90}) between 0 and 256. Assuming that the maximum signal voltage is very close to the maximum input voltage of the converter, the least count of the fine measurement is 1.6^{cc} or 0.00016 grads or 0.00016 gon or 0.16 mgon or 0.52". At each circle position, the phase angle ϕ between the circle and mask graduations must be evaluated. The following relationship is used:

$$\tan \phi = \sin \phi / \cos \phi \qquad (4.3)$$

Using e_0 (the digitised amplitude of the sin ϕ signal) and e_{90} (the digitised amplitude of the cos ϕ signal) and solution for ϕ leads to

$$\phi = \arctan (e_0/e_{90}) \qquad (4.4)$$

The unit of ϕ depends on how the trigonometric function is computed. The circle interpolation ϕ must be converted to grads to be consistent with the previous derivations. Because of the incremental nature of the circles of the Nikon DTM-1, the display of the angular values has to be referenced to the horizontal circle position at switch-on and to the vertical circle reading at the time of the pick up of the reference mark (quasi-absolute circle).

The *displayed direction* value at an alidade position (x) may be derived as Direction (x) = 0.0000 grads (= direction at switch-on) + {number of pulses counted (positive or negative) x 0.04 grad} + ϕ(x) – ϕ(at switch on), where ϕ(x) and ϕ(at switch-on) are the fine measurements (interpolation values) at the arbitrary (x) and 'switch on' alidade positions, respectively. Before the horizontal direction is displayed, it is converted into the unit requested by the user (degrees-minutes-seconds, decimal degrees, mils).



Figure 4.17: Direction Sensing (Up-Down) logic of the Nikon DTM-1. The horizontal axis represents the angle of rotation, positive to the right.

The zenith angle is initialised by tilting the telescope through the horizon. When doing so, the instrument picks up a reference mark on the quasi-absolute circle and 'zeros' the circle reading (setting $z = 100.0000$ grads). The *displayed zenith angle* value at a telescope position (y) can then be derived as $z(y) = z(ref)$ (= 100.0000 grads) + $\phi(y) - \phi(ref)$ + {number of pulses (+ or –) from reference mark x 0.04 grad} where $\phi(y)$ and $\phi(ref)$ are the fine measurements (interpolation values) at the arbitrary (y) and 'reference' telescope positions, respectively. Before the zenith angle is displayed, it is converted into the unit requested by the user (degrees-minutes-seconds, decimal degrees, mils).

4.3.3 Sensing of the Direction of Rotation

The only problem left is find out whether the coarse measurement pulses need to be counted positive or negative by the up/down counter. A logic is required for the detection of the clockwise (+) and the counter clockwise (–) rotation. The basic principle of the direction sensing is shown in Fig. 4.17. As discussed before, the sinusoidal signals are converted to square signals by the two triggers. The rotation sensing logic uses the square signals only. Based on the 'high' and 'low' states of the two waves, it determines if the sine-signal leads the cosine signal or vice versa. Two possible implementations are discussed below. In reality, the sense of the direction can be derived four times over the period of the square signal, namely for each rise and fall of the two signals. This provides redundant data.

In Fig. 4.17, moving to the right on the time axis corresponds to a clockwise rotation of the alidade. The logic makes use of the fact that a zero crossing (rise) of the sine signal is followed by a negative zero crossing (fall) of the cosine signal. In other words, if the sine is high and a fall of the cosine is recorded, we know that the alidade rotates clockwise. The counted pulses are thus positive and must be added by the counter.

On the other hand, a movement to the left in Fig. 4.17 refers to an anticlockwise rotation of the alidade. A positive zero crossing (rise) of the sine signal is followed by a positive zero crossing (rise) of the cosine signal. In other words, if the sine is high and a rise of the cosine signal occurs, the logic concludes that the alidade is turned anticlockwise and that the counted interval must be subtracted.

4.4 Electro-Optical Level Sensors

Level sensors are commonly used in modern theodolites and tacheometers. They provide the actual value of the dislevelment and simplify the circle reading optics. Typically, a level sensor uses a liquid surface to provide a horizontal plane and measures the tilt of the vertical axis opto-electronically. A controlling microprocessor is used to compute the tilt corrections automatically. When enabled, the displayed zenith angle readings (and, for dual-axis level sensors, the horizontal directions) are largely free of the effects of a small residual dislevelment of the vertical axis.

There are two types of level sensors, namely single-axis and dual-axis devices. To permit the real-time correction of the horizontal directions for a small dislevelment of the vertical axis, the instrument must be equipped with a dual-axis level sensor. Instruments with dual-axis level sensors are becoming more common because they are very useful whenever highly accurate directions are required to points with steep lines of sight. It is well known that, at zenith angles of 45°, a 10" levelling error (in trunnion axis direction) causes a 10" error in the horizontal direction. (For even steeper sights, the errors in the directions exceed those in the levelling.) This cannot be eliminated by measuring in two faces but can be removed by an instrument with a dual-axis level sensor and associated software.

Early instruments to use dual-axis level sensors were the Hewlett-Packard HP3820A (1978), Kern E2 (1983), Zeiss Elta 3 (1986), Geodimeter 420/440 (1986) and the Wild T2002/T3000. As dual-axis level sensors are useful whenever steep sights are involved in direction measurements (for example in engineering surveying), most modern electronic tacheometers and theodolites feature such devices.



Figure 4.18: Single-axis pendulum level sensor of the Nikon DTM-1 electronic tacheometer on the left and dual-axis liquid level sensor of Leica TPS1100 series on the right. The numbered items are defined in the text. (Figure on the right after Zeiske 1999.)

4.4.1 Nikon DTM-1 Single-Axis Level Sensor

The Nikon DTM-1 electronic tacheometer uses a pendulum–type level sensor. Like most other pendulum sensors, it is a single-axis device. It uses a light emitting diode (LED) to illuminate a transparent slit on a fixed mask. The light bar is projected through a lens onto a CCD array. The lens is attached to a conventional mechanical pendulum system that hangs vertically under the effect of gravity. The position of the light bar on the CCD array is converted into a reading of the tilt of the vertical axis parallel to vertical circle. This value is then used to correct the zenith angle reading into the true zenith. (Refer to Eqs. (4.15) and (4.17).)

4.4.2 Leica TPS1100 Series Dual-Axis Level Sensor

The Leica TPS1100 series of instruments incorporates liquid level dual-axis level sensors. The layout of this level sensor is shown on the right of Fig. 4.18. This particular design was developed to allow to install the liquid horizon in the centre of the instrument, that is in the vertical axis. This has the advantage that the rotations of the upper part of the theodolite exert minimal centrifugal forces on the liquid. In consequence, this level sensor requires less time to settle after a rotation than a level sensor mounted (as usual) in the standards of a theodolite (see Fig. 4.19 for example of the latter design). Also, centrally mounted level sensors are not affected by temperature induced deformations in the standards (Zeiske 1999).

On the right of Fig. 4.18, the ray path through the Leica TPS1100 level sensor is depicted. The prism ('1' in Fig. 4.18) carries a line pattern that is illuminated by a light emitting diode (LED, see '7' in figure). The line pattern is projected through a lens ('4') and a deviation prism ('3') onto the liquid horizon, where it is reflected twice at the surface of the liquid. The image ('5') of the line pattern falls on the linear CCD-array ('6'). Because of the use of V-type lines at both ends of the line pattern (besides the parallel lines in the centre), it is possible to measure both components of the tilt of the vertical axis with one linear ('single-axis') CCD sensor. A longitudinal tilt of the vertical axis (i.e. parallel to the vertical plane defined by the rotating telescope) changes the distance between the V-type lines of the pattern. A traverse tilt (in the vertical plane parallel to the trunnion axis) moves the centre of gravity of the line pattern on the CCD sensor.

Leica quotes the 'setting accuracy' of the level sensors of the TPS1101 and TPS1102 instruments as 0.5". Since no distinction is being made between the two components of the dual-axis level sensor, one may assume that they are equally accurate. For comparison, the angular accuracy of the TPS1001 instruments is quoted as ±1.5" (after ISO 17123-3). It is appropriate that the accuracy specification of the level sensor is only a third of the angular accuracy rating.



Figure 4.19: Cross section through the dual-axis level sensor of the Kern E2 electronic theodolite (after Lardelli 1988). A light emitting diode (1) emits a light beam that is focussed to infinity by a lens with a short focal length. The parallel rays are reflected downwards at the top surface of the liquid horizon (2). The reflected beam is then focussed onto a position sensitive quadrant photodiode (3) by a second lens with much longer focal length. To save space, the read-out ray path is bent three times.

4.4.3 Kern E2 Dual-Axis Level Sensor

The dual-axis level sensor of the electronic theodolite Kern E2 is similar to the proven liquid compensator of the Kern DKM-2A one-second theodolite. (Some Zeiss electronic theodolites use the same device in a slightly modified form.) Figure 4.19 shows a three-dimensional view of the device and explains the basic principle. Because the liquid horizon is intrinsically two-dimensional, the light beam is reflected in two dimensions, one component being parallel to the plane of the light path (parallel to the vertical circle) and the other perpendicular to it (parallel to the trunnion axis).

The quadrant photodiode measures the x-y coordinates of the light spot created by the reflected rays on the diode relative to the centre of the diode.

The two components of the diode readout are a measure of the two components of the vertical axis tilt, namely the tilt parallel to the vertical plane described by the telescope axis rotating about the trunnion axis and the tilt parallel to the vertical plane through the trunnion axis. The output currents (i_1, i_2, i_3, i_4) of the diode are used to derive the x and y coordinates of the light dot.



Figure 4.20: Side view (parallel to the plane of the vertical circle) of the Kern E2 dual-axis level sensor (on the left) and the principle of the two-component read-out on the position sensitive quadrant photodiode (on the right). The photodiode has five electrical connections, one in the centre and one each (i_1, i_2, i_3, i_4) for the four quadrants. (after George 1984)

In simple terms, the derivation can be given as follows:

$$i_1\,k\,(l-x) = i_2\,k\,(l+x) \qquad \text{and} \qquad i_3\,k\,(l-y) = i_4\,k\,(l+y) \tag{4.5}$$

where l is one half of the side length of the photosensitive area of the diode and k a constant. Solving for x and y leads to

$$x = l\left(\frac{i_1 - i_2}{i_1 + i_2}\right) \qquad \text{and} \qquad y = l\left(\frac{i_3 - i_4}{i_3 + i_4}\right) \tag{4.6}$$

The units of x and y are the same as that of l, namely a length unit. Angular units are obtained by dividing x and y by the focal length of the lens system between the liquid horizon and the photodiode. Any errors in the length of the focal distance used for this purpose will cause *scale errors* in the angular values and, eventually, in the displayed vertical axis tilts. In Fig. 4.20 it is assumed that the optical axis of the lens system intersects the centre of the photodiode. In practice, this is not exactly the case. Small corrections *(the additive constants of the level sensor)* need to be applied to the measured x-y values to reference them to the point where the optical axis intersects the photodiode.

Changing the inclination of the vertical axis (see Fig. 4.20) causes a movement of the light dot on the position sensitive photodiode. This information is used to compute the two-components of the vertical axis tilt. The next section discusses this principle in more detail for a simplified ray path.

4.4.4 Principle of the Determination of the Theodolite's Dislevelment

The unfolded ray path of a liquid level sensor is shown in Figure 4.21 for three different cases. The sensor design is a simplified version of the type shown in Section 4.4.3. In all three figures it is assumed that the optical axis of the lens on the photodiode side intersects the photodiode in the centre. Figure 4.21a depicts the ideal case where the plumbline is coincident with the vertical axis and the symmetry axis of the level sensor. In consequence, the light travels along the optical axes and is projected into the centre of the position sensitive photodiode. The angle between the symmetry axis and the optical axes of both lens systems is denoted by ϕ.

Figure 4.21b gives the same view as Fig. 4.21a, but for a dislevelled theodolite or tacheometer. The instrument is out of plumb by an angle α. The angles between the optical axes of the two lens systems and the symmetry axis of the level sensor (and the inclined vertical axis) are still the same (ϕ). Because of the tilt, the liquid horizon is no longer perpendicular to the vertical axis. This affects the reflection of the rays. The incident angle at the liquid horizon is $(\phi - \alpha)$ as is the emerging angle. The figure shows that the optical axis and the reflected rays are at an angle of 2α to each other. In consequence, the light dot is no longer in the centre of the photodiode but rather $2 \times \alpha \times f$ towards the vertical axis, f being the focal length of the photodiode optics.

The configuration, after a rotation of the alidade by 180° about the vertical axis, is shown in Fig. 4.21c. In the absence of a wobble error in the vertical axis bearing, the direction of the vertical axis will still be inclined at an angle α. The incident angle of the rays on the liquid horizon is now $(\phi + \alpha)$, because the rays are coming from the right. The emerging angle is also $(\phi + \alpha)$, whereas the angle between the optical axis on the photodiode side and the plumbline is now $(\phi - \alpha)$. The figure shows that the optical axis and the reflected rays are at an angle of 2α at the photodiode. The light dot is again not in the centre of the diode but rather at a distance of $2 \times \alpha \times f$ away from the vertical axis. If the coordinates of the light dot on the photodiode are measured in face left and in face right, then the change of the coordinates between the two faces will be equivalent to 4 times the dislevelment of the vertical axis. This rule applies to both components.


(a)
Vertical Axis and Symmetry Axis of Level Sensor
Liquid Horizon
ϕ
ϕ
Light Emitting Diode
Photodiode
(b)
Face Left
α
Liquid Horizon
2α
ϕ
2α
ϕ
ϕ − α
ϕ − α
Light Emitting Diode
Photodiode
α
Symmetry Axis of Level Sensor and Vertical Axis
Plumbline
(c)
Face Right
α
Liquid Horizon
ϕ − α
ϕ + α
ϕ + α
2α
α
Photodiode
Light Emitting Diode
Plumbline
Symmetry Axis of Level Sensor and Vertical Axis

Figure 4.21: Working principle of (one component of) a liquid level sensor

As only coordinates on the photodiodes are recorded, the angle α has to be expressed in terms of these measurements. Let S_{FL} be the coordinate reading on the photo diode in face left, S_{FR} the coordinate reading on the photo diode in face right and S_{REF} the coordinate reading for the optical axis. S_{REF} should be zero if the theodolite is truly vertical and if no index error (additive constant) of the level sensor is present. In face left, the following formula applies in the right angled triangle between the centre of the lens, the centre of the photodiode and the light dot:

$$2\alpha = \text{arc tan} \left(\frac{S_{FL} - S_{REF}}{f} \right) \tag{4.7}$$

$$\alpha = (S_{FL} - S_{REF}) \times \frac{206265''}{2\,f} \tag{4.8a}$$

$$\alpha = S_{FL} \times C - S_{REF} \times C \tag{4.8b}$$

where ($S_{FL} - S_{REF}$) is positive, S_{FL}, S_{REF} and the focal length f are taken in mm and where C is the scale factor which converts the photodiode output into the (single) vertical axis tilt α, in seconds of arc. In face right, the following relationship holds:

$$-\alpha = (S_{FR} - S_{REF}) \times \frac{206265''}{2\,f} \tag{4.9}$$

$$-\alpha = S_{FR} \times C - S_{REF} \times C \tag{4.10}$$

Taking the difference between Eqs. (4.8) and (4.10) gives the measured component of the dislevelment α of the vertical axis

$$2\alpha = S_{FL} \times C - S_{REF} \times C - S_{FR} \times C - S_{REF} \times C \tag{4.11}$$

$$\alpha = (S_{FL} \times C - S_{FR} \times C) / 2 \tag{4.12}$$

Adding Eqs. (4.8) and (4.10) gives the additive constant ($S_{REF} \times C$) of the measured component of the level sensor

$$0 = S_{FL} \times C - S_{REF} \times C + S_{FR} \times C - S_{REF} \times C \tag{4.13}$$

$$0 = S_{FL} \times C + S_{FR} \times C - 2S_{REF} \times C$$

$$S_{REF} \times C = (S_{FL} \times C + S_{FR} \times C) / 2 \tag{4.14}$$

It follows that it is very easy to determined the additive constants of level sensors: Read the level sensor in two faces and take the mean. Also, a theodolite or tacheometer is truly vertical, if the level sensor reads the same value ($S_{REF} \times C$) in all orientations of the alidade.

Please note that each coordinate is individually multiplied with C as it is the product of S_i and C that is displayed by instruments.

4.5 Properties of Electronic Level Sensors

The error patterns of mechano-optical vertical circle compensators and compensators in automatic and digital levels are similar. In theodolites, the errors are reduced, because the theodolites can be (and should be) levelled more accurately than levelling instruments. The error patterns of electronic level sensors and vertical circle compensators are also similar because the basic sensor elements are the same, namely mechanical pendulums and liquid horizons.

4.5.1 Compensation Error ε

For the traditional vertical circle compensators, the compensation error ε is defined as the residual inclination of the vertical circle reading system caused by under- or over-compensation of the compensator. It is a function of the dislevelment α of the vertical axis. Figure 4.22 demonstrates the principle of the compensation error of mechano-optical compensators and applies equally to FL and FR observations.

The compensation error is caused by the positioning tolerances (errors) in manufacturing, the inaccuracy of the optical-mechanical design and the effects of changing gravity. The compensation error may also depend on ambient temperature. The magnitude of the compensator error ε in classical instruments with compensators is usually less than 1%-5% of the dislevelment α.


Plumbline
Trunion Axis
Vertical Axis
α
ε
true circle reading
true circle reading
α
compensated circle reading
α-ε compensation angle
Uncompensated circle reading

Figure 4.22: Principle of the compensation error ε in mechanical vertical circle compensators. The dislevelment of vertical axis is denoted by α.

4.5.2 Scale Factor Error ΔC

In electronic level sensors, the scale factor error causes errors that are equivalent to the compensation errors of the vertical circle compensators. As before, the errors in the measured inclination of the vertical axis, as well as in the corrections to zenith angles and directions computed from these tilts, are a function of the dislevelment α. The scale factor C of level sensors has been defined previously (Eqs. (4.8a) and (4.8b)). It is a function of the focal length f of the sensor's optics.

An error ΔC in C may be due to the manufacturing tolerances (positioning of lens, emitting diode and photo diode) or due to the conversion of the electronic read-out of the photodiode output current to length units. The magnitude of the scale factor error in electronic level sensors is typically less than 1%-2% (of α).

The scale factor errors are dangerous (as are the compensation errors), because the measured zenith angles are affected but not the vertical circle index error. This error cannot be detected in the usual way (by checking the sum of FL and FR zenith angle readings). *The scale factor error (as well as the compensation error)* ***cannot*** *be eliminated by measurement in two faces!*

4.5.3 Setting Error

4.5.3.1 Random Component

This reflects the setting accuracy of the level sensor after a disturbance (such as a rotation of the alidade or another instrument manipulation). This repeatability is typically better than 3" – 1". The setting accuracy specified by manufacturers for some instruments is given as a guide:

Sokkia SET 2C/3C	±1"	Leica TPS1100	±0.5"
Wild T2000	±0.3"	Nikon DTM-821	±1.0"
Sokkia SET 5C	±5"	Topcon GTS-603C	1.0"
Zeiss Elta 2/3	±0.6–1.0"	Zeiss Elta S10/S20	±0.3"

It is unfortunate that some manufacturers (e.g. Sokkia, Trimble) do not specify the accuracy of their level sensors. The presumption is that, in these cases, the specifications of the angular accuracy include the level sensor uncertainty.


Hysteresis
▨ rest position when moving in from left
▧ rest position when moving in from right
▦ true rest position
Swing of the pendulum

Figure 4.23: Principle of mechanical hysteresis ('compensator drag')

The setting time of the level sensors depends on their design. The mechanical devices (pendulum) need about 1 second of time to reach an equilibrium position. The liquid level devices require longer times, typically

3 to 5 seconds. Even longer times are required in cold weather, because of the change in the viscosity of the liquid. It is likely that level sensors located in the vertical axis (see right of Fig. 4.18) need less time to settle. The observer should wait long enough before reading and/or recording measurements. This is essential for all zenith angle measurements. If dual-axis level sensors are used to correct horizontal direction measurements, then the same waiting period applies for horizontal angle measurements.

4.5.3.2 Systematic Component

Mechanical hysteresis exists if the final rest position of the pendulum depends on the direction from which the pendulum moves into its rest position. See Fig. 4.23. The error caused by the mechanical hysteresis is a function of the inclination of the vertical axis (α) and of ambient temperature. In the last version of the classic Wild T2 theodolite, a push button ensured that the compensator always 'moved in' from the same side. The hysteresis effect will then be similar for all readings and, thus, become part of the vertical circle index error. Some experiments did establish the magnitude of the hysteresis effect as less than 3" - 25" for a selection of optical third order theodolites. *Liquid level compensators and level sensors are not affect by hysteresis.*

4.5.4 Vertical Circle Index Error and Correction

As optical theodolites, electronic theodolites and tacheometers have an index error of the vertical circle reading system and require a vertical circle index correction (VCIC). This error has two components, which might be explained with reference to an instrument, which reads the zenith angle in the horizon through the trunnion axis. Firstly, the line between the 90° and the 270° mark on the circle might not be exactly parallel to the line of sight. Secondly, the reading mechanism might not be exactly in a horizontal plane trough the trunnion axis. The two components cannot be separated; the sum is determined and corrected for. The previously discussed additive constant of the electronic level sensor constitutes an additional (third) component of the total VCIC. If the level sensor correction is enabled and the VCIC is determined in the usual way, the resulting value will include the additive constant of the level sensor (component parallel to telescope axis). If the level sensor is 'switched off' during the determination of the VCIC, then the resulting VCIC value will not include the additive constant of the level sensor. See Eqs. (4.15) and (4.17) for proof.

The (total) vertical circle index error may be affected by ageing (long-term changes), shocks, lateral tilts (cross-tilts), sticking of a mechanical compensator level sensor and temperature. Only the last effect is discussed further.



Figure 4.24: Temperature dependence of the index error and temperature independence of the mean (of two faces) zenith angle (z) for a particular theodolite

Experiments have shown that the vertical circle index correction (VCIC) and/or level sensor correction can be strongly dependent on temperature. Some examples of test results may illustrate the magnitude of the problem in electronic tacheometers and level sensors:

KERN E2	+0.30"/°C
WILD T2000	–0.88"/°C
KERN DKM 2A	+0.91"/°C

As the ambient temperature changes as a function of time, the temperature effects caused by the level sensors in the zenith angle measurements can be reduced by appropriate field procedures. The linear changes with time of the index or level sensor correction may be eliminated by measuring zenith angles in the following sequence: $z_{FL} - z_{FR} - z_{FR} - z_{FL}$.

4.6 Circle Graduation Errors

There are two types of circle graduation errors, namely random errors and systematic errors. The systematic errors are usually referred to as periodic errors. All systematic circle graduation errors are caused by imperfections in the devices that produced the master circles and those used for the transfer to the instrument's circles.

First and second order theodolites read circles at diametrically opposite points on the circles. In these cases, the actual *graduation error* is of little interest. What is of interest is the sum of the opposite errors, namely the *diameter error*. In some precision theodolites, the circles are read in four positions, 90° apart.

4.6.1 Periodic Errors

Periodic errors can be modelled with sine and cosine functions. Periods vary from 360° down to multiples of the basic circle graduation interval (from 180° downwards for instruments with diametrical circle reading). Most tests are usually restricted the fundamental wave period (360° or 180°) and some of its harmonics.

The periodic errors are traditionally determined by measuring the same angle between two (or more) collimators at different zeros of the (horizontal) circle. Other methods involve comparison against a laser interferometer or against a high precision theodolite. An example of the latter technique is shown in Fig. 4.25. Periodic circle graduation errors can be eliminated to a certain degree by appropriate observation procedures. These are discussed later.



Figure 4.25: Periodic error of a specific electronic tacheometer Zeiss Elta 6. As the instrument does not feature diametrical circle reading, the fundamental period is 360° (or 400 grads; after Hennes & Witte 1991)

4.6.2 Interpolation Errors

Interpolation errors are the systematic errors of the fine measurement during the circle reading. As discussed previously, the circle interpolation is the measurement of the position of the reading index between two graduations of the circle. The interpolation errors are equivalent to the errors of the micrometer reading ('micrometer errors') in the classical instruments with visual circle reading.

The error patterns across the interpolation interval depend on the type of the interpolation system used. They may be due to errors in the index patterns on the mask, unequal illumination, a deviation of the actual signal from the (assumed) sinusoidal wave shape, and any errors in the spacing of the multiple reading indices (e.g. the spacing of the diodes that generate the 0°, 90°, 180° and 270° signals).

The interpolation errors can be determined in laboratories and modelled by sine and cosine curves (Fourier series). Figures 4.26a and 4.26b show the results of such tests and the fitted curves. If the calibration is done by the manufacturer, then there is a possibility of real-time correction (used in Zeiss ETh3, for example). However, if the calibration is done by the user, then post-correction is possible, in principle, but usually too cumbersome to be practical. Fortunately, the interpolation errors are usually very small. The table gives the results of some tests. For the horizontal direction measurement only, the interpolation errors could be reduced in the field, as the micrometer errors were with optical instruments. However, a physical change of the zero of the horizontal circle by a fraction of the interpolation interval is not practical and, in most cases, not possible.



Figure 4.26a: Interpolation error of an electronic theodolite Zeiss ETh3. As the circle graduation interval is 82.3" (0.0254 grad), the interpolation error repeats a few times over the circle section shown. The peak-to-peak (p-p) variation is 5.2". (after Hennes and Witte 1991)

The interpolation error of another instrument (Nikon DTM-750) is shown in Fig. 4.26b. This electronic tacheometer features 16200 graduations over the full circle (360°) and, thus, has an interpolation interval of 80" exactly (in Fig. 4.26b shown as 24.69 mgon or 0.0247 grads). In this case, the peak-to-peak variation of the circle reading is 3.05" (or 0.94 mgon). The angular accuracy quoted by the manufacturer is ±2" (after the German industry standard DIN 18723). The curve shown in Fig. 4.26b (Schauerte et al. 1994) is the sum of a first order (period = 80") and a second order periodic error (period = 40") fitted by least squares. The corresponding amplitudes are 0.55" and 0.96", respectively.



Figure 4.26b: Interpolation error of an electronic tacheometer Nikon DTM-750. Since the circle graduation interval is 80.0" (0.02469 grad, 24.69 mgon), the figure shows the interpolation error without repeats across one interpolation interval. The peak-to-peak (p-p) variation is 3.05". The dominant periodic error term has a period of 40.0" and an amplitude of 0.96". One second of arc is equivalent to 0.3 mgon or 0.0003 grads. (after Schauerte et al. 1994)

Instrument	Peak-Peak Variation	Interpolation Interval
Nikon DTM-750	3.0 "	80.0 "
Topcon GTS-6B	1.7 "	80.0 "
Topcon GTS-301	3.3 "	80.0 "
Zeiss ETh3	5.2 "	82.3 "

Table 4.1: Measured interpolation errors for a selection of individual instruments.

4.7 Some Notes on the Use of Electronic Theodolites and Tacheometers

It has been mentioned before that, in principle, the electronic theodolites and tacheometers should be used in the same way as the older optical instruments in general, and the one-second theodolites in particular. A few aspects have changed however and need to be considered. Only some aspects are discussed here. The aspects relating to electronic distance measurement are not covered. Readers may refer to the EDM textbook by Rüeger (1990, 1996), for example.

4.7.1 Levelling of Electronic Theodolites and Tacheometers

If an electronic tacheometer or theodolite is equipped with a dual-axis level sensor, and if the level sensor and the correction function for zenith angles and directions are enabled, then and only then is the levelling less critical than in the past. Because of the scale factor error of level sensors, it is suggested that the instruments be levelled to about ±20" to ±30" (one division on most plate levels) all the same.

Some instruments with dual-axis level sensors have displays like the one shown in Fig. 4.27. For instruments with identical displays on both sides, an operator can completely level an instrument without moving around the tripod. This saves time. The operator starts by levelling the fictitious bubble on the display in the first alidade orientation. After each turn on the footscrews, one should let the values settle for about three to five seconds (to a 'constant' value). This is equivalent to getting the values for the x and y tilts to zero. (Normally, it is not possible (nor necessary) to make the x and y tilts exactly zero as the pitch of the footscrews is not fine enough and the tripod often not stable enough.) The alidade is then rotated 180° about its vertical axis. If the fictitious bubble moves out of the centre position (and the x and/or y tilt values change), the levelling is changed half-way back (to the mean values/position of both 'faces'). The theodolite or tacheometer is truly vertical, if the level sensor reads the same values of x and y in all orientations of the rotating upper part ('alidade') of the theodolite.



Figure 4.27: Level sensor read-out and levelling display on an electronic tacheometer Topcon GTS-6

4.7.2 Selection of Measuring Units

Since the introduction of the electronic theodolites and tacheometers, the units of the angular (and distance) measurements can be changed easily by the observer. Typically, 400 grads (gon), 360° decimal, 360° sexagesimal

(° ' ") and 6400 mils are offered. Many users don't realise that the resolution can be quite different, depending on the selected unit. For example, the Wild TC1610 has the following resolutions: 1^{cc} (0.33"), 1", 0.0001° (0.36"), 0.001 mil (0.20"). Note that 1^{cc} = 0.1 mgon = 0.0001 gon = 0.0001 grad. Clearly, the best resolution is achieved in the military mil setting.

When recording data, users of electronic instruments should ascertain that the post-processing software can use the selected units. Unfortunately, this may greatly limit the choice available in the field. *When booking by hand* and doing the post-processing by hand, it is suggested to use a decimal unit, like decimal degrees (or grads(gon) for that matter). This simplifies the field reductions and avoids the cumbersome conversions from degrees, minutes and seconds to decimal degrees on calculators.

4.7.3 Use of Umbrella

There are many good reasons why an umbrella should be employed to provide shade for the observer, the instrument and the tripod. Some of these are given below.

4.7.3.1 Electronic Theodolites

- Australia has the highest incidence of skin cancer in the world. (One in 45 Australians is affected by melanoma!) Similarly, extensive exposure to sun can cause permanent eye damage. To provide shade for field parties is, thus, essential and an occupational health and safety (OHS) requirement.
- The operating temperatures of instruments are specified as ambient, shadow temperatures. In full sunlight, the inside of the instrument can be 20°C higher. Some instruments cut-out automatically when the upper limit of the specified operating temperature is reached. A shaded instrument may work whilst an unshaded may not!
- The pointing to targets, either manually or automatically, can be very difficult, if not impossible, when the sun is shining into the optics. This increases the time required for the pointing and may reduce the accuracy of the measurements.
- A change of the temperature of the instrument leads to temperature gradients through the mechanical and optical components. Temporary misalignments and changes of instrument errors occur. Typically, about 5 minutes per °C temperature change are required for an instrument to reach a dimensional equilibrium at a new temperature. This waiting time after temperature changes (e.g. after moving the instrument from an air-conditioned car into 40°C heat) should be observed before beginning high precision measurements. Proper acclimatisation of instruments is particularly important when using automatic pointing systems. In consequence, it is advisable not to leave instruments in a hot, stationary car;

rather, they should be unloaded and stored in a shadowed area in the open air (e.g. under an umbrella).

- The level sensors are usually mounted in one of the two standards and thus fully exposed to heating by the sun in the absence of an umbrella. Changing face alternates the level sensor between the sun and the shadow side, with all the negative effects on it temperature equilibrium.

4.7.3.2 Electronic Tacheometers

- Do not aim the telescope at the sun: You may burn out the transmitting and receiving diodes in doing so and, thus, permanently damage the instrument. Do not carry out sun azimuth observations with an electronic tacheometers unless a *sun filter* (approved by the manufacturer) is *always attached* to the objective. (Not on the eyepiece, as in the past!)

4.7.4 Automatic Power-Off

To extend the charge of batteries in the field, some instruments switch themselves off after being idle for a specified time. For *measurements of highest precision*, the instrument should **not** be turned off during measurements. This ensures that the temperature inside the instrument remains as constant as possible.

4.7.5 Two-Way Radios and Cellular (Mobile) Phones

It is advisable not to transmit from walkie-talkies and cellular phones during actual measurements. Since mobile phones respond to incoming calls without user input, they should be totally switched off when operating an electronic theodolite or tacheometer. Transmitting devices may interfere with measurements, leading to an erroneous result or to a total failure of the measurements. Instances of the latter were reported at UNSW with respect to distance measurements.

4.7.6 Real-Time Corrections to Measured Data

The vertical axis tilt(s) is(are) computed by electronic tacheometers and theodolites and used to correct the zenith angles (single-axis level sensors) or the zenith angles and the horizontal directions (dual-axis level sensors). These corrections are combined with other on-line corrections. For example, for face left:

$$z_{FL} = z'_{FL} + S^{TE}_{FL} \times C - S^{TE}_{REF} \times C + VCIC \qquad (4.15)$$

$$r_{FL} = r'_{FL} + \frac{c}{\sin(z_{FL})} + (S^{HA}_{FL} \times C - S^{HA}_{REF} \times C + TAI) \times \cot(z_{FL}) \tag{4.16}$$

where z is the corrected and z' the raw zenith angle measurement, r is the corrected and r' the raw horizontal direction measurement, VCIC is the vertical circle index error correction, c is the collimation error correction, TAI is the correction for the trunnion axis inclination and where the 'exponents' TE and HA denote the **te**lescope and the **h**orizontal **a**xis components of the level sensor measurements. In face right, the formulae are a function of the face right zenith angle:

$$z_{FR} = z'_{FR} + S^{TE}_{FR} \times C - S^{TE}_{REF} \times C + VCIC \tag{4.17}$$

$$r_{FR} = r'_{FR} + \frac{c}{\sin(z_{FR})} + (S^{HA}_{FR} \times C - S^{HA}_{REF} \times C + TAI) \times \cot(z_{FR}) \tag{4.18}$$

The Equations (4.15) and (4.17) highlight that the electronic theodolites and tacheometers have two 'index errors', one for the vertical circle reading mechanism (VCIC) and one for the level sensor (S_{REF}). Please note that any errors in S_{REF} will be cancelled if the mean of face left and face right is taken in zenith angle and horizontal direction measurements. Any errors in C will **not** be cancelled by this procedure.

The correct sign of the level sensor readings will depend on the construction of the level sensor and the position inside the instrument. When using a liquid level sensor for the measurement of the vertical axis tilt, it should be noted that it takes longer to settle down than a mechanical pendulum device, due to the viscosity of the liquid. It takes about 3-4 seconds to settle in normal conditions, longer in cold conditions. This waiting time must be observed (for zenith angles **and** direction measurements) if the above on-line corrections are enabled.

The Eqs. (4.16) and (4.18) are not defined when pointing to the zenith because of the division through zero. If Eqs. (4.15) and (4.17) are not applied, the displayed and recorded zenith angles will not refer to the plumbline but rather to the (inclined) vertical axis. The real-time corrections after Eqs. (4.15) and (4.17) may have to be disabled in cases, where the instrument is set-up on a moving or vibrating platform. Measurements are then taken in a coordinate system defined by the instrument's vertical axis and the zero direction of the horizontal circle.

4.7.7 Direction Measurements

The electronic theodolites and tacheometers are, as far as the mechanical design and the telescope are concerned, not very different from classical theodolites with visual reading of circles. In consequence, most of the existing rules of measurements with classical theodolites still apply. These accepted procedures are part of good professional practice and have been established over decades if not centuries.

The new technology used in electronic theodolites may require a revision of some of the accepted procedures, a drop of others and an introduction of new procedures. Only the observation rules that relate to the circle reading (resolution), the circle zero and the level sensors (replacing compensators and altitude bubbles) need to be reassessed. All other rules are still valid and should be adhered to.

4.7.7.1 Single-Face versus Dual-Face Measurements

The decision between single-face (FL only) and dual-face (FL & FR) measurements is the same as in the past. *Single-face observations* are acceptable whenever:

- the combined effects of all residual instrument errors are smaller than the required angular accuracy,
- the validity of the values of the corrections for instrumental errors stored on-board for real-time correction are confirmed in the field,
- the required angular accuracy is less than the resolution of the instrument and
- the gross errors can be detected by means other than a second measurement.

The fact that some instrument errors are corrected by computations in real-time, does not change much. In fact, the errors in the corrections for the physical errors can be quite large if the calibration measurements were not carried out properly. (In other words, the correction for an error might be a bigger problem than the error as such.) The stored corrections (like the mechanical adjustments in the past) may also change with temperature and time.

Single-face measurements are typically used in tacheometry, detail surveys and setting-out. When measuring in FL only, the speed of surveys increases considerably. However, the accuracy and reliability of single face measurements must be assured always. Quality assurance requires that all data are checked one way or another.

Dual-face measurements are executed whenever:

- the accuracy of the measurements is to approach the resolution of the instrument,
- as many as possible instrument errors are to be truly eliminated on the spot, and
- any gross errors are to be avoided or detected immediately by a second set of data.

Dual-face measurements are used for control surveys (traversing, trilateration) and for high precision surveys, usually in engineering applications. Dual-face measurements improve the reliability of the data considerably, as all points are pointed to at least twice. The errors of identification are reduced.

4.7.7.2 Sequence of Direction Measurements

If an arc of direction is to be measured to targets 1,2,3,4 .. ,t, then the accepted sequence of the direction observations is:

- {rotate alidade clockwise by 360°}
- in clockwise (cw) direction: FL(1)–>FL(2)–>FL(3)–>....–>FL(t)
- change face {and rotate alidade counterclockwise by 540°}
- in ccw direction (read from right): FR(1)<–FR(2)<–FR(3)<–....<–FR(t)

Actions listed in { } brackets are suggested for high precision measurements for the lubrication of the bearings. The sequence of the points is selected in such a way that the smallest sector is covered (FL(t) – FL(1) = minimum). This minimises the walking around the tripod or the pillar. The accepted sequence does also eliminate most of the effect of the tripod or pillar rotations (the so-called 'tripod twist'). The assumption for this is that the time spent on measuring to each point is about the same.

A *horizontal angle* is an arc of direction with two rays and is measured the same way. In traverses, the clockwise angle from the backsight to the foresight station is measured, irrespective of it being the smaller of the two possible angles or not.

4.7.7.3 Elimination of Periodic Errors

For high precision direction measurements, the periodic graduation errors and diameter errors should be eliminated by a physical change of the circle's orientation between multiple arcs. (A real *change of the zero* of the circle is required. Changing the circle reading through the keyboard *does not help*!) When measuring n arcs, the circle orientation should be changed physically by 180°/n for electronic theodolites with diametrical circle reading and 360°/n for electronic theodolites with a single index.

Unfortunately, most electronic theodolites and tacheometers do no longer feature a horizontal circle setting screw. The rotation (by 120°) of the whole instrument inside its tribrach between arcs is then the only feasible approach. This should be done for high precision direction measurements.

4.7.7.4 Circle Setting

With optical theodolites and manual booking, it was appropriate and beneficial to set the circle to a little bit more than zero to the left most target, in face left, in the first arc. For subsequent arcs, the 180°/n or 360°/n rule (see previous paragraph) was employed. If manual booking is used with electronic theodolites and tacheometers, this procedure is still appropriate, even if the (virtual) change of the circle reading is achieved through keyboard entry of the desired value.

When using *electronic instruments with electronic data recording*, however, setting of the circle to zero (or any other value) is a waste of time. It is suggested to start at whatever orientation the circle is after the set-up. When measuring multiple arcs of directions in precision work, the procedure outlined in the previous section on the *Elimination of Periodic Errors* should be used. If the circle cannot be rotated physically one way or another, multiple arcs might as well be measured with the same circle orientation and readings when using data recording. Entering a new starting value for each arc through the keyboard does not change any errors and is, thus, a waste of time.

4.7.8 Zenith Angle Measurements

Good levelling of the theodolite is required, despite (and because of) the fact that an electronic level sensor or a compensator is being used. For more precise work, all zenith angle readings should be done in a certain sequence, e.g. FL-FR-FR-FL, to offset time varying changes of the vertical circle index correction (VCIC) and the additive constant of the level sensor. In this routine, the corresponding FL and FR readings follow each other immediately. It can be assumed that any errors in the additive constant of the level sensor are the same and, thus, cancelled. Also, the vertical refraction is unlikely to change significantly in the few seconds that elapse between the FL and FR readings. The FL and FR readings are, thus, subject to the same refraction error.

Large magnetic fields can affect mechanical pendulum level sensors. A liquid level sensor is recommended for measurements in electro-magnetic fields. The liquid level sensors take longer to settle down due to the viscosity of the liquid. On average they take 3-4 seconds in normal conditions to settle, longer in cold conditions.

As the zero of the zenith angle is traditionally fixed, the only way to eliminate the periodic graduation or diameter errors is to determine them and to correct the measurements later in the office or on-line, through a linked personal computer. As the circle graduation errors of vertical circles are not easily determined, the calibration and the post-correction are usually not carried out. This is another reason why zenith angles, typically, are less precise than horizontal directions.

4.7.9 Simultaneous Direction, Zenith Angle and Distance Measurements

With electronic tacheometers, the cross hairs **must** be pointed to the centre of the reflector for a distance measurement. On longer distances, where the apex of the glass prism cannot be seen, the pointing occurs to a target plate symmetric to the reflector. It is convenient (also for recording purposes), to use the same pointing for the directions and the zenith angles. The errors caused in angular measurements by an erroneous pointing of the apex of the reflector are not discussed here. Please refer to Rüeger (1978, 1990, 1996), for example.

If the standard measuring routine for arcs of directions is followed (see above), the quality of the zenith angles will depend on the elapsed time (and any changes in the ambient temperature) between the corresponding FL and FR readings. The vertical refraction and the additive constant of the level sensor do change with time. This is because the ambient temperature and the vertical temperature gradient also change with time. Simultaneous direction, zenith angle and distance measurements might be possible for precise measurements, if the temperature and the refraction conditions remain the same. One such case arises in close range three-dimensional (3D) industrial measurements indoors. Otherwise, simultaneous direction, zenith angle and distance measurements are not recommended for precision work.

4.7.10 Plumbing of Structures

Theodolites can be used for the plumbing of structures in two major ways. The first technique establishes a point directly above the instrument, for example in a vertical shaft or well. The second is used to establish the verticality of the corners of a building.

4.7.10.1 Plumbing Shafts and Wells

Plumbing from the bottom to the top of a shaft or well is possible, if a diagonal ('broken') eyepiece is attached to the electronic theodolite or tacheometer. These attachments are offered as accessories for most instruments. To establish a point directly above the intersection of the vertical and trunnion axes of an instrument, level the instrument in the normal way, switch the level sensor and the tilt corrections on, turn the alidade to read 0° on the horizontal circle, tilt the telescope until a zenith angle of 0° 00' 00" is read. Mark the intersection of the line of sight on a suitable target at the top of the shaft or well. Then turn the alidade to read 90° on the horizontal circle, reset the telescope to a zenith angle of 0° 00' 00" and mark the intersection of the second line of sight on the target at the top. Turn the alidade to read 180° on the horizontal circle, reset the telescope to a zenith angle of 0° 00' 00" and mark the intersection of the third line of sight on the target at the top. Then turn the alidade to read 270° on the horizontal circle, reset the telescope to a zenith angle of 0° 00' 00" and mark the intersection of the fourth line of sight on the target at the top. These four measurements are taken in the same face. Because of instrumental errors, the line of sight travels on a cone when rotating the alidade about the vertical axis and 'draws' a circle on the target. The centre of the (imaginary) circle is the (error free) plumbing point. The accuracy of the plumbing depends on the accuracy of the level sensor, how accurately the plumbing points are marked and on how accurately the zenith angle can be set to zero (exactly). The latter also depends on the stability of the tripod.

4.7.10.2 Plumbing a Building

When checking the verticality of building corners, for example, instruments with dual-axis level sensors are preferred since they correct the direction measurements for (residual) tilts of the vertical axis. This is important for steep sights. (The diagonal eyepieces mentioned in the previous paragraph may also be useful.) To check the verticality of a corner in one direction, set up the instrument in line with one of the two facades and sufficiently offset from the corner to avoid zenith angles less than 45°. Level the instrument in the usual way, switch on the dual-axis level sensor and the tilt corrections, point (in FL) to the corner at the top, read the (corrected) direction, point (in FL) to the corner at the bottom, read the (corrected) direction, point (in FR) to the corner at the top, read the (corrected) direction, point (in FR) to the corner at the bottom and read the (corrected) direction. Calculate the mean direction to the top and the mean direction to the bottom. The building is vertical (at the corner and in the direction measured), if the two values are the same. The accuracy depends on the angular accuracy of the instrument, the pointing accuracy and the accuracy of the level sensor. The latter has to be multiplied with cot(z), since the tilts of the vertical axis, measured by the level sensor, are multiplied with cot(z) to derive the corrected directions. Refer to Eqs. (4.16) and (4.18) for details.

4.8 Exercises

4.1 List three important differences between optical and electronic tacheometers ('total stations') and briefly explain their significance.

4.2 Explain the major differences between two robotic surveying systems, namely a one-person-survey-system and an automatic monitoring system.

4.3 Describe two completely different types of incremental circles used in electronic tacheometers.

4.4 Explain how the field operations differ between instruments with electro-optical incremental and absolute horizontal circles.

4.5 Describe the key differences between vertical circle compensators and electronic level sensors in electronic tacheometers.

4.6 What are dual-axis level sensors good for? How valuable are these activities?

4.7 An electronic tacheometer, designed according to Fig. 4.15, features an incremental circle with 21600 graduations.

(a) What is the resolution of the coarse measurement on the circle?

(b) At what intervals would you expect the interpolation error to repeat itself?

(c) Assuming that the instrument employs a 6-bit analogue-to-digital converter, what would the resolution of a single circle reading be?

4.8 Based on Fig. 4.17, design two other logical tests for the determination of the sense of the rotation, one each for the clockwise and the counterclockwise movement.

4.9 Redraw the window (b) of Figure 4.20 for the case, where the vertical axis is tilted the other way (by the same amount).

4.10 Using Eqs. (4.12) and (4.14), investigate the effect of a 1% error in C on α and S_{REF}, respectively.

4.11 How significant is the systematic component of the setting error in liquid level sensors?

4.12 You have been measuring zenith angles with an electronic theodolite with a dual-axis liquid level sensor. The corrections for the dislevelment were 'switched-on'. At +20°C, you noted a total vertical circle index correction (VCIC) of −12". At +35°C, you found a VCIC of +2". What do you attribute this change to? Why?

4.13 Would you prefer to level a theodolite with the procedure outlined in Figure 4.27 or with the traditional method with the plate level? Give reasons!

4.14 (a) Considering Figs. 4.21(b) and 4.21(c), Eqs. (4.15) and (4.17) and assuming that $S_{REF}^{TE} = 0.000$, how do S_{FR}^{TE} and S_{FL}^{TE} relate to each other?

(b) Noting that the mean zenith angle is $\overline{z} = 0.5\,(z_{FL} + (360° - z_{FR}))$, how would an error of 2% in C affect $\overline{z}$ for $S_{FL}^{TE} \times C = 20"$ and for $S_{FL}^{TE} \times C = 100"$, respectively?

4.15 Considering Eq. (4.16) and Eq. (4.18), $\overline{r} = 0.5\,(r_{FL} + (r_{FR} \pm 180°))$ and $z_{FR} = 360° - z_{FL}$ and assuming $c = 0.0"$, $TAI = 0.0"$, $S_{REF}^{HA} \times C = 0.0"$,

(a) prove that the level sensor readings $S_{FL}^{HA} \times C$ and $S_{FR}^{HA} \times C$ are not cancelled in $\overline{r}$, and

(b) discuss the effect of $S_{FL}^{HA} \times C = +10"$ on $\overline{r}$ for zenith angles z_{FL} of 90°, 70°, 50°, 30° and 10°.

4.16 You have been asked to check the verticality of a hight rise building. For this purpose, you have set up an electronic theodolite with a dual-axis level sensor. You are pointing in face left (FL) to a point at ground level on the building as a reference and you set the direction reading to 0°00'00". (Here, it is assumed that the zenith angle to this point is 90° exactly.) You then check the verticality of points above the reference (in FL) by tilting the telescope to zenith angles of 70°, 50° and 30°.

(a) Assuming that your instrument employs the Eqs. (4.16) and (4.18) to correct directions in real-time and that $c = +15"$, $TAI = -8"$, $S_{REF}^{HA} = 0.0$ exactly, $S_{FL}^{HA} \times C = -15"$, what direction would you read after tilting the telescope (without any alidade rotation) from the reference mark to $z=70°$, $z=50°$ and $z=30°$?

(b) What would you do next, at each zenith angle setting ($z=70°$, 50°, 30°) before assessing the verticality?

(c) Give reasons why you would repeat the process in face right (FR) afterwards?

5. Specialised Equipment

5.1 Reflectorless Electronic Distance Measurement

The evolution of reflectorless EDM in surveying has been discussed in Section 4.1.8. In this section, the special aspects of measuring to non-cooperative targets with modern instruments are discussed.

Since reflectorless EDM relies on the spurious reflectance of features of the landscape, the range is much reduced in comparison to measurements to normal EDM glass prism reflectors. To increase the range of reflectorless EDM instruments, manufacturers have to increase the power output of the emitting diodes, use the pulse distance meter principle, where short and powerful pulses are separated by idle times (low duty cycle), increase the sensitivity of the receiving diodes, focus the EDM beam (noting that most electronic tacheometers feature fixed focus distance meters) or any combination thereof. Reflectorless instruments measure the distance to the area ('footprint') on the target that is illuminated by the distance meter's beam. If the distance meter uses a visible beam, then the footprint may be visible trough the telescope, at least on close range If the distance meter uses an infrared beam, then the observer has to assume that the optical line of sight is properly aligned with the EDM beam. Should the EDM beam be out of alignment, then the distance is not measured to the point indicated by the crosshairs on the object. Note that some instruments transmit a visible light beam for target identification, even though the distance measurement is carried out with an infrared beam. In such cases, the same uncertainties arise as between the optical line of sight and an infrared EDM beam.

5.1.1 Basic Properties

Figure 5.1 shows some of the basic properties of reflectorless EDM. At the top left of Fig. 5.1, the ideal case for reflectorless EDM is shown where the beam hits a flat surface that is at a right angle to the central ray (i.e. angle of incidence is zero) and where the footprint of the beam is well within the surface. This is clearly the preferred configuration for reflectorless measurements. The average distance across the footprint will be measured. At the top right of Fig. 5.1, the flat surface is not at a right angle to the beam any more. The angle of incidence on the surface is no longer zero and the footprint is now an ellipse. It is likely that less light will be returned to the distance meter, when compared to the first case, and that the measuring range is reduced. Again, the average distance across the footprint is measured. Unfortunately, the centre of gravity of the illuminated area ('footprint') does not coincide with the point where the central ray intersects the surface. This error was calculated by Köhler (1994) for a Zeiss Reg Elta RL as 3 mm at 60 m for an (extreme) angle of incidence of 81°. For angles of incidence closer to zero, this error is insignificant.

The case of a rough (structured) surface is illustrated at the bottom left of Fig. 5.1. Again the average distance across the illuminated area is measured. Note that tape measurements would be to the 'highest' point of the structured surface rather than the average and, thus, will differ from reflectorless measurements. Reflectorless EDM measures to a point inside the structured surface. Shiny surfaces (bottom right of Fig. 5.1) may act as mirrors and reflect the EDM beam. Typically, the reflectorless measurement will fail to such surfaces. Should the *deflected* EDM beam hit another surface of sufficient reflectivity, then an (erroneous) distance may be measured to the other target surface, through the shiny surface. In consequence, glass and shiny surfaces should be avoided.



Figure 5.1: Basic properties of (reflectorless) distance measurements to natural targets (after Ibeo 1986)

Since a reflectorless EDM instrument illuminates a circular area (footprint) rather than a dimensionless point, all distance measurements to corners and rounded surfaces will be wrong to a certain extent. Distances to convex corners (on left in Fig. 5.2) will be measured too long and distances to concave corners (in the middle of Fig. 5.2) too short. The magnitude of the error depends on the angle of incidence, the diameter of the footprint and, thus, on the instrument used and the distance to the corner. The distance to rounded surfaces, such as cylinder and spheres (see right of Fig. 5.2), are also measured too long. Typically, the errors will be less than those to corners.



Figure 5.2: Measurement to corners and round surfaces (after Buchmann & Scherer 1994)

5.1.2 Beam Size and Shape

Because reflectorless EDM instruments do measure to the area that is illuminated by the instrument, it is important for the user to be fully aware of the dimensions and shape of the beam of the reflectorless distance meter when measuring to surfaces. Nikon, for their NPL-821 reflectorless pulse distance meter, write that the reflectorless EDM beam is circular and has the same diameter as the central circle present on the crosshairs of the instrument. The latter is 5.00 minutes of arc. The beam diameter, thus, increases linearly with distance. Nikon also states that focussing the telescope of the NPL-821 onto a target also focusses the reflectorless EDM beam. (As far as known, the other manufacturers use fixed focus EDM beams.) Leica quotes different beam cross-sections and dimensions for different distances for their instruments operating in reflectorless mode. Figure 5.3 gives the information for the reflectorless mode of the Leica 1100 Series of instruments. The reflectorless EDM beam is coaxial with the telescope when properly adjusted.

In normal EDM, the knowledge of the EDM beam dimensions is less critical, since the glass prism reflector has the same diameter as the objective lens of the instrument. As long as no strongly reflecting surfaces are located behind the prism, only that part of the EDM beam, that illuminates to prism, will be reflected back to the instrument and used for the distance measurement. In contrast to reflectorless EDM, it is quite clear in normal EDM to what point a measurement refers to, namely the intersection of the reflector's horizontal and vertical axes.



Figure 5.3: Beam shape and dimensions of Leica Series 1100 reflectorless electronic tacheometers (after Leica 2001)

The effective beam size and shape can be easily determined by the user. Since this information is essential for reflectorless measurements, tests should be carried out at a number of distances and vertically and horizontally. The principle is shown in Fig. 5.4.



Figure 5.4: Scanning across an edge to determine the (horizontal) beam width of a reflectorless distance meter. Front view on the left, plan view on the right. On the right, the dots represent possible changes in distance measurements across the edge (after Meier-Hirmer 1996). The EDM footprints at the direction readings Hz(L) and Hz(R) are shown on the left.

To determine the horizontal width of the EDM beam, two blocks (for example, of wood) are arranged in such a way that their front faces are approximately perpendicular to the beam and separated by 0.1 m or so. On the right hand side of Fig. 5.4, the block on the right is closer than the block on the left. The view from the distance meter is shown on the left hand side of Fig. 5.4. The vertical edge that separates the left and the right block should be about vertical, as shown. To determine the horizontal beam width, one points the vertical crosshair to the edge and records the distance and the horizontal direction. (Since half the beam hits the back target and half the front, one expects to read the average distance to the two surfaces.) Then, the scan to the left starts by measuring distance and direction at appropriate angular intervals. Once the distance readings stabilise (at the distance reading to the back block on the left), the left hand scan is terminated. Point the vertical hair again to the edge, and record direction and distance. Then, start the scan to the right, using the same angular intervals as before. Once the distance readings stabilise (at the distance reading to the front block on the right), the right hand scan is terminated. As a check, point the vertical hair again to the edge, and record direction and distance. As Fig. 5.4 shows, the positions Hz(L) and Hz(R) are the closest points to the edge, where the beam is still fully on the front or back target. The beam width (in angular units) is obtained as Hz(R) - Hz(L).

The test should then be repeated in a vertical direction, across a horizontal edge. Afterwards, the beam width should also be determined at another distance. As a minimum, the beam width should be established at the shortest and longest distance experienced in daily practice. The beam width test discussed here allows to check if the EDM beam is properly aligned to the telescope's crosshairs. For a EDM beam, that is properly aligned in the horizontal direction, the direction readings to the edge (at the beginning, middle and end of the test) should be the mean of Hz(R) and Hz(L), to use the example of Fig. 5.4.

5.1.3 Multiple Target Problem

Since reflectorless instruments are usually pointed to non-cooperative targets in the landscape, it can happen that the EDM beam exceeds the diameter of the target. It is then possible that the part of the beam, that overlaps the intended target, is returned by a surface behind the target. A similar case arises if small reflecting surfaces (such as leaves), located between the instrument and the intended target, interfere with the beam. The effect of multiple targets on the distance displayed by the instrument is different for phase measuring reflectorless instruments (e.g. Leica instruments) and pulse reflectorless distance meters (e.g. Nikon and Topcon instruments, Zeiss Rec Elta RL).

5.1.3.1 Pulse Distance Meters

The effect of multiple targets for pulse distance meters varies with the distance between the two targets as well as the relative strength of the signals returned by the two targets. Figure 5.5 shows experimental results obtained by Meier-Hirmer (1995) with a Zeiss Reg Elta RL. The closer target was 22 m (distance s_0) from the instrument. The second one was set up behind the first one so that both targets were visible from the instrument. The more distant target was then shifted in steps (distance s_1) until it was 4.000 m behind the first target. Each time, the instrument was pointed to the edge between the two targets, focussing to the closer target in all cases. The back dots in Fig. 5.5 represent the measurements. In Fig. 5.5, the abscissa shows the distance ($s_1 - s_0$) between the two targets (in the direction of the EDM beam). The ordinate shows the difference between the EDM measurement (s) and the distance (s_0) to the first target. Since half of the footprint is on the forward target and half on the backward target, one expects to measure the average distance, that is $(s - s_0) = 0.5\ (s_1 - s_0)$. This line is shown in Fig. 5.5. The measurements follow the line up to a step interval of 0.3 m. After that, the distant target has lesser influence. As soon as the step interval exceeds 3.000 m, the distance meter readout approaches again the distance value (s_0) to the closer target.



Figure 5.5: Measurements with a pulse distance meter (Zeiss Reg Elta RL) to two targets, the separation of which changes from 0 to 4 m. The closer target was steady at 22 m. See text for explanation. (adapted from Meier-Hirmer 1995)

The pattern shown in Fig. 5.5 may be caused by the pulse length of the Zeiss Reg Elta RL. Assuming a 50% return by each target, a type of average distance is measured if the double of the difference in the distances to the two targets is less than the distance equivalent of the length of the pulse transmitted by the instrument. This is because the leading edge of the return pulse from more distant target arrives at the instrument before the return pulse from the closer target has died down. Once this critical separation is exceeded, it is likely that only the distance to the closer target is measured. Experiments have established this critical separation at about 3 m for the Zeiss Rec Elta RL (Meier-Hirmer 1996 and Fig. 5.5) and at about 1.8 m for the Nikon NPL-821.

5.1.3.2 Phase Measuring Distance Meters

As with the pulse distance meters, the effect of multiple targets for reflectorless phase measuring distance meters varies with the distance between the two targets as well as the relative strength of the signals returned by the two targets. The effect was investigated by Scherer (1999) with a Leica TCRM electronic tacheometer. The experimental set up was similar to the one discussed in the previous section. The closer target was always at 4.3 m and the more distant target at distances from 4.3 to 7.3 m. At each target separation, Scherer (1999) carried out a lateral scan across the edge of the targets, like the test explained in Fig. 5.4. This means, when scanning to the right, the return from the distant target increased from 0% to 100%. Figure 5.6 depicts the results on two scans only. The left part of Fig, 5.6 shows the result of the scan with the second target at 6.6 m, the right part the scan with the second target at 5.2 m.



Figure 5.6: Scanning across two targets with a (phase measuring) Leica TCRM instrument. The first target is at 4.300 m. The second target is 2.300 m (on the left) and 0.900 m (on the right) behind the first. Scanning (from left to right) begins with the full beam on the closer target (on left) and continues then in equidistant lateral steps until the beam is fully on the back target. (from Scherer 1999)

It follows from Fig. 5.6 that the displayed distances are either close to the distance to the closer target or close to the distance to the more distant target, but never half way in between, if the separation does not exceed the unit length of the instrument (1.5 m in this case). The matter of concern is that the displayed distances may be shorter than the distance to the closer target, or longer than the distance to the distant target. Scherer (1999) reported magnitudes of such errors of up to 0.20 m. The behaviour of phase measuring distance meters is quite different from that of pulse distance meters. Clearly, it is best to avoid measuring to multiple targets!

5.1.4 Influence of the Material and Colour of the Target

The material, roughness, reflectivity and colour of a target affect the maximum distance and precision that can be achieved. Also, gross errors can occur in certain conditions.

The experiments by Kogoj (2001) established the following maximum distances with a Leica TCR307 to targets at 90° to the EDM beam (zero angle of incidence): sheet metal (60 m), render (85 m), wood (100 m) and styrofoam (110 m). When measuring to coloured paper with a Leica TCRM1100, which uses a visible (red) EDM beam, white, red and yellow gave the best return signal and blue and green the worst (Möser 2000).

Kogoj's (2001) experiments with a Leica TCR307 showed that the precision gets worse with distance. However, there was no noticeable difference in precision between the measurements to sheet metal, render, wood and styrofoam.

Möser (2000) investigated the variations in distance measured with a Leica TCR1100 to number of different target materials at the same physical distance. Errors of less than 0.5 mm were recorded for paper, (smooth) PVC, (smooth and rough) steel. Wood and wallpaper were within 1 mm. At 20 m, errors of 15 mm were recorded for acrylic glass, 7 mm for styrofoam and 4 mm for sandpaper. Clearly, measurements to (and through) glass should be avoided as should measurements to styrofoam and sandpaper.

5.1.5 Target Orientation

The target orientation (or, in other words, the angle of incidence) does have an effect on the maximum distances that can be achieved to a particular material. For sheet metal and render, Kogoj (2001) recorded a 5% and 6% reduction in the maximum distance, respectively, from zero to 45° angle of incidence with a Leica TCR307.

Another problem of target inclination is shown in Fig. 5.7 (Köhler 1994). The figure shows the distances measured in two faces with a pulse distance meter Zeiss Reg Elta RL to a target with different tilts about a horizontal axis. The angle of incidence is given on the abscissa (in grads). In the Zeiss Reg Elta RL, the EDM beam is transmitted coaxially. The receiver optics is, however, below the main telescope. Even though the misalignment is corrected, some adjustment errors remain. As Fig. 5.7 demonstrates, the mean of distance measurements in face left and face right is free of errors caused by the misalignment.

It should be noted that any reflectorless distance meter, with a misalignment between the line of sight and the EDM beam, will exhibit similar errors. Measuring in two faces to an target at an angle of incidence of say 45° can, therefore, be used to check for possible misalignments of the EDM beam. Rotations of the target about horizontal and vertical axes should be checked.



Figure 5.7: Errors in distance for reflectorless distance measurements with misaligned optics, measured for a Zeiss Reg Elta RL (after Köhler 1994)

5.1.6 Measurement to Corners

The fundamental problem of reflectorless EDM measurements to corners and similar shapes has already been outlined in Fig. 5.2. Since corners and other edges are one-dimensional features, the two-dimensional footprint of the EDM beam will (usually) not deliver the correct distance. Unfortunately, it is very often the edges and corners of structures and objects that are of interest to surveyors. Because of that, most manufacturers provide on-board software to remedy the problem. The solutions provided rely usually on the fact that corners are at the intersection of two planes or three planes. All one has to do is to measure in reflectorless mode to three (arbitrary and unmarked) points on one of the planes and then point to the corner. The on-board software will calculate the equation of the plane and, then, the slope distance (or coordinates) of the corner from the measured direction and zenith angle to the corner. No distance is measured to the actual corner.

The accuracy of the special measurements to corners depends on the flatness and size of the plane used for the corner definition and on where the three points are selected in relation to the corner. For example, the corner between two vertical walls of a room, halfway up the wall, is best determined by measuring to two points near the (two-dimensional) corner on the wall, one close to the floor and the other close to the ceiling, and a third point at the other end of the same wall. The accuracy of a corner determination can easily be checked by doing a second measurement using the second wall. Such a check is only useful if the corner point is (temporarily) marked.

On close range, the footprint of the reflectorless beam may be sufficiently small to allow direct measurements to corners. Small errors (see Fig. 5.2) will remain but may not be worse than the assumed flatness of walls or the verticality of wall corners.

5.1.7 Some Notes on the Use of Reflectorless EDM

(1) The target must be larger than the footprint of the reflectorless EDM beam. If the instrument used features a visible reflectorless EDM beam, note that the footprint used by the actual distance measurement may be (slightly) larger than the illuminated area seen by the eye.

(2) Avoid measuring to two targets at the same time. Make sure that there are no objects (e.g. leaves) in the beam between the instrument and the target. Make sure that there are no other reflecting surfaces behind the target.

(3) Since the knowledge of the actual beam width at different distances is essential, the user should establish the beam width using the test outlined in Section 5.1.2 and illustrated in Figs. 5.4.

(4) With instruments that do not employ a visible beam for the reflectorless measurements, it is essential that the user checks that the EDM beam is colinear with the line of sight of the instrument. Use the tests outlined in Sections 5.1.2 or 5.1.5 and illustrated in Figs. 5.4 or 5.7.

(5) Flat targets at 90° to the line of sight (at 0° angle of incidence) are preferred.

(6) Measure in two faces if there is any doubt on the accuracy of the alignment of the reflectorless EDM beam onto the telescope's line of sight.

(7) Do not measure to materials that give erroneous results, such as glass, acrylic glass, styrofoam, glazed ceramic tiles. Mirror like surfaces may deflect the beam to another surface (see Fig. 5.1).

(8) The range of reflectorless EDM is reduced when the incidence angle is large, the target is wet (see Item (7) above) and the target is in full sun light. Shading helps in the latter case.

(9) The range of all reflectorless EDM instruments can be increased considerably by measuring at night and by using cooperative rather than non-cooperative targets. Self-adhesive reflective sheeting targets are available from most manufacturers, in varying sizes (e.g. 20 by 20 mm, 40 by 40 mm, 60 by 60 mm).

(10) The additive constants of the normal distance meter and the reflectorless distance meter in the same instrument may not be the same. Calibrate the instrument separately for the two modes of operation, with the respective targets or reflectors.

(11) Non-cooperative ('natural') targets have a nil reflector constant. Most glass prism reflectors used in normal EDM have a substantial reflector constant. Never forget to change the reflector constant setting when switching between normal and reflectorless EDM. Frequent switching between reflectorless and normal EDM requires great discipline on the part of the operator.

(12) Reflectorless EDM to the normal glass prism reflectors is possible. The maximum measurable distance is typically double that of normal EDM. For example, for the Leica TPS1100 series, the reflectorless range is 5000 m (with slightly reduced precision) whereas the normal EDM range is 3000 m. For the Nikon NPL-350, the range increases from 2000 m to 5000 m.

Manufacturers may specify a minimum distance that must be observed when using glass prisms with reflectorless instruments (e.g. 10 m for Nikon NPL-350). Because of the high power of reflectorless instruments, glass prisms may reflect the EDM beam at points and surfaces other than the faces of the glass cube. Nikon suggests not to use prisms with scratches, a chipped apex or with thick edges for reflectorless EDM. Since the front surface of the prism can also reflect the beam, Nikon further suggests to mispoint the prism slightly for close range reflectorless measurements to glass prism reflectors. This is good advice for all reflectorless instruments.

(13) Reflectorless EDM through traffic (pedestrians or vehicles) can cause problems. If the cars have a similar reflectance than the intended target, and are close to the target, distances may be measured to the car and not the target, or an average distance may be displayed. It is best to measure distances across roads (or footpaths) multiple times, and to start the measurements when the line if sight is (temporarily) clear.

Nikon warns of possible errors with their NPL-350 reflectorless pulse distance meter, if the car is within three metres of the intended target. Considering Fig. 5.5, it can be inferred that an average distance will result within the three metres (length of transmitted pulse) and that the shorter distance (to the car) might be measured if the car is more than three metres in front of the target.

(14) Check the safety rating of the (lasing) diodes used in reflectorless instruments. Class I (Class 1) instruments are safe for any reasonable usage. Reflectorless instruments using visible (lasing) diodes are usually labelled as Class II (Class 2). Do not look into the transmitter (front lens) at close range.

5.2 Laser Scanners

The laser scanners are a further development of the scanning electronic tacheometers discussed in Section 4.1.9. They are optimised for speed of measurement and fast data acquisition and are supported by sophisticated software packages that allow a conversion of the data to formats readable by computer aided design packages. As discussed previously, the laser beam transmitted by the scanner is deviated vertically and horizontally to scan the surrounding space in a grid pattern. The step interval can be selected. Some instruments can scan around the full circle (360°), others only in a limited sector. The distances are measured reflectorless using the pulse method.

Company	Callidus	Cyra(Leica)	Riegl	Mensi
Country	Germany	USA	Austria	France
Model	Callidus 1.1	Cyrax 2500	LMS-Z210	GS 100
Wawelength	NIR	green (532 nm)	NIR (905 nm)	???
Safety Classification	Class 1	Class 2	Class 1	Class 2
Distance Range	0.15 - 150 m	1.5 - 100 m	2 - 350 m	2 - 100 m
Accuracy/Distance	±5 mm/32 m	±4 mm/50 m	±25 mm/200 m	±1mm/3-6 mm
Angle accuracy	±61"	±25"	±130"	6.6"
Hor Field of View	360°	40°	340°	360°
Vert Field of View	±90° & –60°	40°	80°	60°
Time for Scan	4-9 min	10 min	2 min	1000 points/s
Intensity Recording	no	yes	yes	yes
Camera	CCD	video	RGB channel	video
Can be centred	yes	no	yes	yes
Can be levelled	yes	no	yes	yes
Dimensions (mm)	460x300x300	400x330x430	435x210x210	320x420x280
Weight	13 kg	28.2 kg	13 kg	13 kg

Table 5.1: Major technical data of a selection of laser scanners

Table 5.1 gives some technical data of a small selection of laser scanning systems. Three systems are depicted in Fig. 5.8. The range and accuracy specifications of these and other systems vary greatly, from ±0.5 mm at 5 m to ±50 mm at 1000 m at the time of writing. Some systems employ infrared lasers, others visible ones. The latter have more stringent safety requirements. Of the systems listed in Table 5.1, the Mensi GS100 seems to be the most precise in its 'high precision' mode. Three of the four systems described in Table 5.1 (and all systems shown in Fig. 5.8) can be centred and levelled like conventional surveying equipment.



Figure 5.8: Riegl LMS-Z210 '3D-imaging-sensor' on the left, Leica HDS3000 'high definition surveying system' in the middle and Mensi GS200 'long range scanner' on the right.

The typical results of a laser scan are the x, y, z coordinates of the large number of points 'seen' by the scanner. The precision of these coordinates depends on the precision of the angular measurements (directions, zenith angles) and the precision of the distance measurements. Some laser scanners also record the intensity (signal strength) of the returned laser beam. This permits to generate something that resembles a photograph. A significant computing effort is required to convert the large number of measured coordinates ('point clouds') to useful plans and computed aided design (CAD) files. Some systems do record photographic images simultaneously. These can be used to render three-dimensional computer images, that may be derived, with realistic colours.

Since laser scanners mostly measure to non-cooperative targets, namely the natural and man-made features around the scanner, the problems associated with reflectorless EDM must be considered when interpreting laser scanner data. Refer to the discussions in Section 5.1 for details. In reflectorless EDM, an operator manually points to a passive target and, thus, can select suitable surfaces to a certain degree; in contrast, laser scanners measure in a grid pattern to whatever surface is found in the beam. Apart from being faster and less precise, laser scanners have typically a much narrower beam than the reflectorless EDM instruments. Some potential problems are reduced because of that, some others may be created.

Liechti & Harvey (2001) have investigated a few aspects of the Cyrax 2400 laser scanner, which features a beam diameter of 5-6 mm. They found, for example, that measurements to glass prism reflectors reveal significant errors in the distances measured, wire mesh fences in the scene (3 m in front of instrument) are being picked up (even though the wire is thinner than the laser beam) and water on surfaces can change the distance reading by up to 3 mm at 53 m.

5.3 Motorised Levelling

Motorised precision levelling is not a new technique. It has been used in the 1970s to remeasure the entire first order levelling network of the then German Democratic Republic. The method was greatly assisted with the development of the Zeiss Ni002 automatic level with its swivel eyepiece; with this instrument, the foresight and the backsight can be observed without any movement of the observer. A total of three vehicles is needed. The (invar) staffs are attached to cars and the instrument is mounted on a car. This method uses the same staffs as normal and normal sighting distances. In (East) Germany, the achieved one kilometre precision was ±0.3–0.4 mm Please note that this precision is much better than the precision specified for Class A (Order 1) vertical surveys in Australia.



Figure 5.9: Motorised precise levelling in Sweden (after Becker 1979). In this case, two instrument vehicles and three staff vehicles can be seen.

The method was further developed by the National Survey of Sweden for the re-survey of 40 000 km of double run levelling lines, beginning in 1980.

The Swedish equipment is based on cars with automatic transmission, a one-ton truck for the instrument, an electronic calculator for the data recording, an instrument tripod with extra-long legs and changeable tripod shoes (like spikes and plates), a quick level tribrach, adjustable staff supports fitting a variety of vehicles as well as wind and rain protection. In Sweden, precise levelling is carried out between April and September and between 07.00 h and 17.00 h in all weather. Sighting distances do not exceed 50 m. The measurement tolerance (maximum permissible difference between the forward and the backward run height difference) is 2 mm $\sqrt{L}$, with L in km. It is only necessary to leave the vehicle when connecting to benchmarks. The Zeiss Ni002 was the preferred instrument for motorised levelling before the introduction of precise digital levels. The Swedish equipment is shown in Figs. 5.9 and 5.10 (Becker 1979).



Figure 5.10: Instrument vehicle in motorised precise levelling in Sweden with Zeiss Ni002 (after Becker 1979)

The advantages of motorised levelling can be summarised as follows:

- better progress rates (quicker)
- less dangerous
- higher line of sight reduces refraction (avoid car exhausts)
- better stability of staff
- immediate on-board check of data

- less tedious than conventional levelling on foot

	Distance Levelled (km)	s_{1km} (mm √L)
East Germany (double run)	~5000	±0.38
Sweden (double run)	>2000	±0.32–0.55
Denmark (double run)	>46	±0.44
The Netherlands (double run)	>540	±0.58
West Germany (double run)	201	±0.24

Table 5.2: Precision of motorised double-run precise levelling (s_{1km}) over 1 km with classical automatic levels, usually of the Zeiss Ni002 type. The precision values refer to the mean of double-runs. (L in kilometres)

The Swedish National Survey did investigate the progress rates with different types of precise levelling. The following progress rates were found: on foot: 3.4 km / day, by bicycle: 5.5 km / day; fully motorised: 11.5 km / day. In Sweden, the cost of motorised levelling was about 50% of the cost of foot levelling, including the costs of setting the motorised system up. Initial tests in (West) Germany, with sighting distances of 25 m - 40 m and invar staffs attached to motor bikes, showed progress rates of 7.4 km / day when using the BFFB observation routine, and 9.4 km / day when using the BBFF routine. Table 5.2 gives a summary of the precision achieved with motorised levelling in various countries.

Since 1990, the digital levelling instruments of the types Wild NA2000 and NA3000 were also tested by the National Survey of Sweden for their suitability in motorised levelling. Because of the lack of a swivel eyepiece as a standard item, the broken eyepieces known from theodolites had to be used. The resulting image rotations were not found to be suitable for a production environment. Becker et al. (1994) also noted the problems caused by

- the fact that 70% of the measurement sector must be free (particularly when connecting to bench marks),
- measurements into a low sun (a longer sun shade did reduce but not eliminate the problem),
- shadow patterns on the staff from bare trees (measurements along some roads through forests were simply not possible),
- poor light (in spring and autumn, measurements had to stop half an hour earlier than with optical instruments due to poor lighting; time was also lost on heavily overcast days),
- rain, smoke and heat (measurements take longer to make),

- the increased workload of the observer (normally, in motorised levelling, the driver of the instrument vehicle carries out the bookkeeping).

A poor temperature stability of the line of sights of the digital levels NA2000 and NA3000 were reported by Becker et al. (1994). These authors also noted the longer set-up time required per station (in comparison to the Ni002) and the increase in the number of set-ups per kilometre (5% - 20%). They suggested a standard swivel eyepiece for the NA3000 and the removal of the lowest 30 cm of graduations on the bar code staff (to reduce the effects of differential refraction). Refer to Section 3.1.5.1 for more information on the errors of bar code levels.

5.4 Laser Profiling and Laser Altimeters

5.4.1 Laser Profiling on Land

Laser profilers for aircraft and helicopter operations have been available for a number of years. At the centre of a laser profiler is a high power pulse distance meter, usually based on a Nd:YAG laser operating at an infrared wavelength of 1064 nm. Such systems are available, for example, from:

- Azimuth, 13 Park Drive, Westford MA 01886, USA
- LH Systems / Leica Geosystems GIS & Mapping LLC, 2801 Burford Highway, Atlanta Georgia 30329, USA
- Measurements Technology and Systems, Avco Everett Research Laboratory Inc., Everett Massachusetts 02149, USA
- Optech Systems, 701 Petrolia Road, Downsville Ontario, Canada M3J 2N6

The early Avco Airborne Laser Mapping System operated at 5, 10 or 20 pulses per second. This translated to one measurement per 7.5 m on the ground at a ground speed of 275 km/h and at a pulse repetition rate of 10 Hz. The typical operating altitude was 350-600 m above ground. The vertical mapping accuracy was specified as ±1.4 m on land and ±0.15 m on water. The roughness of the ground coverage has, naturally, an effect on the accuracy. Most systems are, however, able to process multiple pulse returns, such as those for the shortest and the longest distance for each pulse. Otherwise, only an average distance in the footprint area is measured. The horizontal mapping accuracy was based on a microwave distance measuring system; the specified accuracy was ±3.2 m. The Avco system required 28 V DC supply and required 1.1 kW to run. The dimensions and weight were 1470 x 910 x 790 mm and 180 kg, respectively.

Besides the pulse distance meter, an aircraft positioning system and an attitude measurement system are required as well as powerful data recording facilities. Today, the former is typically a GPS receiver and provides the coordinates of the aircraft or helicopter. The attitude angles (roll-angle and pitch-angle) are required to transfer the coordinates of the GPS antenna to the laser system and to measure the deviation of the laser beam from the plumbline. The attitude information can be provided by an inertial navigation or reference system or, possibly, by an array of three to four GPS receivers. Rather than measure the attitude angles, the laser transmitter might be installed on a stabilised (gimballed) platform that is kept in a strictly levelled state irrespective of aircraft movements. This solution also requires inertial sensors for the platform stabilisation. Some laser profilers are able to scan the terrain (or water) sideways. In this case, a scanning mirror is required to deflect the laser beam off the vertical. The laser beam deflection introduced must be measured and recorded to be able to compute the ground position.



Figure 5.11: Longitudinal profile surveyed with a helicopter-borne laser profiler. The graduation intervals on the vertical and the horizontal axes are 25 m and 250 m, respectively. Flight time: 270 seconds. The continuous upper curve is the helicopter path and includes the take-off on the right hand side. The lower curve shows the ground level and the dots between ground and helicopter the upper foliage level. (from Nortech Surveys brochure)

The ALS50 Airborne Laser Scanner by LH Systems (Leica Geosystems) achieves rates of 52000 pulses per second, (lateral) scan rates of 70 Hz and a swath width of 75°. Flying altitudes above ground from 500 m to 4000 m are possible. The position of the helicopter or aircraft is determined by GPS and the roll, pitch and heading (azimuth) data by an inertial measuring system. The ALS50 can record up to three times per pulse; this permits to measure to tree tops and ground heights, for example. The system also records the signal intensity. This information can then be displayed in a photograph like form. The height accuracy is listed as 0.13 to 0.30 m and the horizontal accuracy as 0.11 to 0.46 m, depending on flying height and scan angle.

Figure 5.11 shows a terrain profile mapped with a helicopter based laser scanner operated by Nortech Surveys (of Calgary, Canada). The figure shows that the ground level below trees can be recovered in certain circumstances, as the system records the shortest and the longest distance measured from each pulse. The laser profiler used by Nortech Surveys has a high pulse repetition rate (4000 Hz). It is ideally suited for corridor surveys along proposed pipelines, transmission lines, roads or microwave links, either in a single profile or multiple profiles, 25 m apart. Areas are surveyed by surveying parallel profiles. Nortech Surveys quote progress rates of 160 km per day.

5.4.2 Depth Sounders

A number of agencies have developed laser profilers for hydrographic applications. These systems make use of the fact that the Nd:YAG laser's fundamental frequency of 1064 nm can be frequency doubled to the green wavelength of 532 nm. The infrared beam is reflected by the water. The green beam does penetrate the water (unless at a right angle to it) and is reflected at the sea floor. The difference of the two distances gives the depth of the water.



Figure 5.12: Principle of the Laser Airborne Depths Sounder (LADS) of the Royal Australian Navy.

A Scanning Hydrographic Operational Airborne Lidar Survey (SHOALS) system was developed by Optech in Canada for the US Army Corps of Engineers. It has a normal operating altitude of 200 m. The width of the swath of soundings is about 120 m, with 200 soundings per second. Maximum depths are 25 to 30 m in moderately clear waters. This can be doubled at night. The off-nadir scan angle is 15 to 25 degrees. The rotation rate can be varied between 0 and 5 Hz. The depth accuracy was estimated as ±0.3 m and the horizontal accuracy with 4 to 5 m.

A similar system was developed by BHP Engineering and Vision Systems for the Australian Navy. The Australian Laser Airborne Depth Sounder (LADS) is in operation with the Hydrographic service of the Royal Australian Navy. It is installed on board of a Fokker F27-200 Frienship aircraft and operates at altitudes of about 500 m. It can map the sea floor at a rate of 50 km^2 per hour. As the Fig. 5.12 shows, the swath is 240 m wide and individual soundings are spaced at 10 m intervals. Depths of 50 m can be measured. The aircraft flies at a speed of 270 km/h and can stay 7 hours in the air. Like the SHOALS system, it uses a Nd:YAG laser at two frequencies, with a pulse rate of 168 Hz, a pulse power of 1 MW and a pulse length of 5 ns. The return pulses are digitised at 2 ns intervals, which gives a resolution of 0.2 m in height. The positional accuracy is given as ±15 m; it includes the errors of the GPS positioning and the inaccuracy of the platform stabilisation. The laser platform is stabilised for roll, pitch and yaw (azimuth) with input from an inertial measurement system. Orientation data are also provided by a fluxgate compass. Data are stored on tape and post-processed on the ground, immediately after the return of the aircraft.

5.5 Single Beam Laser Trackers for Metrology

At one time, there were triple-beam and single-beam laser tracking interferometers on the market. Because of the more universal appeal and wider usage, only the latter type is discussed here. The single-beam laser tracking interferometers, of the types shown in Fig. 5.13, consist of a single laser interferometer, the beam of which is deflected in three-dimensions (about two axes, one vertical and the other horizontal) by a tilting and rotating mirror. This tracker has angular encoders fitted to both angular servo motors and, thus, delivers directions and zenith angle information very much like electronic theodolites. Together with the (slope) distances, three-dimensional coordinates can be computed for the target points. A feed-back loop ensures that the laser beam is kept on the (moving) reflector.

Figure 5.14 shows the measured quantities (on the right) and the electro-optical components of one device (on the left). The left part of Fig. 5.14 shows the interferometer and the servo loops for the servo mirror. The "Detector" near the "Interferometer's Beam Splitter" records the interference fringes between the transmitted and the returned laser beam. Whenever the reflector moves, constructive and destructive interference alternates. The number of bright fringes is counted by the "Position Electronics" and processed into the change of distance per time interval. A second beam splitter (between the "Interferometer's Beam Splitter" and the "Servo Mirror") deviates 15% of the returned laser light onto the "Position Sensor".

The latter is a position sensitive diode, which measures the position of the light spot. If the light moves out of the centre, the appropriate servo motors are switched on until the light spot is centred again. This correction mechanism occurs at a rate of 1 kHz in the case of the CMS3000 (Ruland 1993).



Figure 5.13: Chesapeake CMS3000 "Coordinate Measuring System" (on left, after Ruland 1993) and Leica "Smart 310" 3-D Laser Tracker (on right, after Kern/Leica 1990)

The interferometer of the laser tracker measures only changes in distance, not the absolute distance. To refer the distance to the tracker and its coordinate system, the reflector has to be placed on a reference mounting on the tracker or, alternatively, on two target points with a known distance in between (baseline). Another property of the laser interferometers (see Rüeger 1990 1996 for reference) is that the change of distance between two positions of the reflector can only be measured if the beam is constantly pointed to the reflector and if no beam interruptions occur. In the case of a beam interruption, the measurements have to start again from the reference point(s).

The Kern (now Leica) SMART 310 is one of the systems shown in Fig. 5.13. Its tracking range is ±240° horizontally and ±45° vertically. The working range is specified as 0.2 m to 25 m. The maximum tracking speed (at 2 m to 5 m from the tracker) is 2 m/s across the beam (horizontally and vertically) and 0.6 m/s along the beam. The resolution of the angular encoders is 0.2 mgon or 0.7". This corresponds to 0.03 mm per 10 m. The distance resolution is specified as ±0.16 μm. The coordinate accuracy in the object space depends on the tracking speed. It varies between ±20 ppm and ±50 ppm or ±20 μm/m to ±50 μm/m (three times standard deviation). The data are collected at a rate of 1000 points per second. The tracker weighs 30 kg and the control unit (under the personal computer in Figure 5.8) 15.5 kg.

The reflectors are mounted in precision fittings (usually a stainless steel sphere) for the attachment to reference and target points. This permits a centring accuracy that is compatible with the overall accuracy of the system. The reflectors are either of the corner cube type (like in EDM) or of the cat's-eye variety. The latter allows larger incidence angles.



Figure 5.14: Block diagram of the servo-controlled tracking system of the Chesapeake CMS3000 Laser Tracker (after Ruland 1993) and the basic optical-mechanical lay-out of the Leica "Smart 310" 3-D Laser Tracker (after Leica 1993)

The performance of the Chesapeake CMS3000 laser tracker was evaluated comprehensively by Ruland (1993). Ruland recommends that all measurements are taken in "two faces" (for the same reasons as with theodolites) and that measurements are taken at different reflector orientations (about the reflector axis). The latter procedure will reduce the errors due to the eccentricities between the reflectors and their mounting spheres.

Since 1997, the two major suppliers of single beam laser trackers offer special models that feature an 'absolute distance meter' (ADM) besides the usual laser interferometer ('relative distance meter'). The absolute distance meters referred to here are nothing else than high precision electronic distance measurement (EDM) instruments. The Leica LTD-500 3D-Laser Tracking System (a further development of the SMART 310 shown in Fig. 5.14) uses a distance meter that operates at an infrared wavelength of 780 nm, has an accuracy of ±0.025 mm (1 σ), a resolution of 1 μm and a range of 2 - 35 m. The firm SMX supplies the Tracker 4500 with ADM. Its EDM section uses a HeNe gas laser, has a resolution of 0.5 μm, an accuracy of ±20 μm at close range and an accuracy of ±1.1 ppm at 'long' range (to 35 m).

The single-axis laser trackers are used for robot calibration, ‘teach-in’ of manufacturing robots, automatic tracking of robots, dynamic measurements of large objects, digitising of surfaces, inspection of antennas, quality control on master-gauges, jigs and tools in mechanical engineering, alignment and assembly of machines and for the calibration of coordinate measuring machines (CMM) and numerically controlled (NC) machine tools, to name just a few examples. The 3-D laser trackers compete with the multi-theodolite 3-D measurement systems. The trackers require that the measuring points are, temporarily, marked with a reflector. If the interferometer is being used, the reflector must be moved between all measurement points without beam interruptions. Clearly, they are most appropriate in applications where the item to be measured can move the reflector automatically, under computer control.

5.6 Reflectorless Single Station Laser Measurement Systems

The previously discussed single beam laser tracking interferometers and the single beam laser trackers with absolute distance measurement require that reflectors be used to mark the points on an object. The Coherent Laser Radar (CLR) MV100B by Metric Vision, and the Leica Laser Radar LR200 now allow to scan quickly and precisely large surfaces without reflectors. Since no reflectors need to be attached to the measured objects, sensitive and non-accessible surfaces can be measured. The Leica system measures three points per second in the most accurate ('metrology') mode. In the 'pseudo vision' mode, measuring rates of up to 1000 points per second are possible. Different models are available for maximum ranges of 8 m, 24 m and 60 m.



Figure 5.15: Leica Laser Radar System LR200 (after Leica 2002), similar to Metric Vision MV100B Coherent Laser Radar (CLR)

Leica specifies the coordinate accuracy (1 σ) for 'tooling ball targets' (highly polished perfect steel spheres), as ±0.05 mm for distances below 10 m and ±5 ppm for distances longer than 10 m. Like with all other reflectorless measuring systems (refer to Sections 4.1.8, 4.1.9, 5.1, 5.2), the quality of the data will depend on the type, reflectance, roughness and orientation of the surfaces. The usefulness of such a system depends on the sophistication of the software used to convert the measured data ('point clouds') into CAD plans and files and into coordinates of specially marked points (e.g. with tooling ball targets).

The distance meter of the Leica LR200 operates at a wavelength of 1.55 μm. A visible pointing laser is also available. According to Slotwinski et al. (1989) the distance meter uses a frequency modulated continuous wave (FMCW) laser, where the optical frequency of the laser diode is changed in a saw-tooth ('chirp') pattern by thermal tuning. The distance is derived from the difference in the frequencies of the transmitted and received IR wavelengths.

5.7 Exercises

5.1 Discuss the pros and cons of two methods of checking the alignment between the beam of a reflectorless EDM instrument and the line of sight of the telescope.

5.2 Discuss the different behaviours of reflectorless phase measuring and pulse distance meters, when measuring to two targets at the same time.

5.3 Explain how to determine the horizontal and vertical beams width of an infrared reflectorless distance meter.

5.4 Discuss the pros and cons of motorised precision levelling in comparison with precision levelling on foot.

5.5 Your firm is tendering for the coordination of the centre line of a two-lane road between two cities, 500 km apart. You are evaluating a laser profiling system.
(a) Discuss the pros and cons of this system for this particular application.
(b) What accuracy could be achieved?
(c) What surveying infrastructure would you have to put in place?
(d) Approximately, how long would the actual field survey take with the laser profiler?

5.6 (a) Determine how many soundings (at 10 m spacing) are made by the Australian Laser Airborne Depth Sounder in one second of time if flying at 75 m/s and at a height of 500 m above sea level.
(b) Hydrographic survey ships, in comparison, travel at a speed of, say, 10 m/s but take continuous soundings to the sea floor. How much longer does a survey by ship take, if it is assumed that the hydrographic survey vessel runs longitudinal profiles at 10 m spacing?
(c) If the same area were mapped by LADS and by ship (as discussed in

(b)), which survey would provide more information on the sea floor?

5.7 Discuss the pros and cons of a 3-D laser tracking interferometer, in comparison with a multi-theodolite 3-D measuring system, for
(a) the dimensional measurement of a steel structure of 1 x 1 x 1 m,
(b) the calibration of the movements of a manufacturing robot.

5.8 What are the similarities of (and differences between) laser scanners and reflectorless single station laser measurement systems?

References

Ailisto, H., Kostamovaara, J., Lammasniemi, J., Myllylä, R. 1996. Lidar Measures Up. Photonics Spectra, March 1996, 96-100.

Angus-Leppan, P. V. 1984. Refraction in Geodetic Levelling. In: Brunner, F. K. (ed.), Geodetic Refraction - Effects of Electromagnetic Wave Propagation Through the Atmosphere, Springer-Verlag, Berlin, 163-180.

Bannister, A., Raymond, S., Baker, R. 1992. Surveying. 6th edition. Longman Scientific & Technical, Harlow, England, ISBN 0-470-21845-2, 482 + XII pages

Becker, J.-M. 1979. Heutige Messverfahren beim Nivellement – Erfahrungen mit dem motorisierten Nivellement in Sweden (Current Measurement Procedures in Levelling – Experiences with the Motorised Levelling in Sweden). In: Vorträge zum Seminar Präzisionsnivellement, 7 Dec 1978, Aachen, Germany. Veröffentlichung des Geodätischen Instituts der Rheinisch-Westfälischen Technischen Hochschule Aachen, No. 26, 2-18

Becker, J.-M., Andersson, B., Ericksson, P.-O., Nordquist, A. A new Generation of Levelling Instruments: NA2000 and NA3000. In: Papers, Commission 5, 20th FIG Congress, Melbourne, Australia, 5-12 March 1994, TS509.1/1 - TS509.1/11

BEI. 1987. Optical Encoder Design Guide. Doc. No. 924-08027-002, BEI Motion Systems Company, Industrial Encoder Division, 7230 Hollister Avenue, Goleta California 93117-2819, USA, 15 pages.

Buchmann, P., Scherer, M. 1994. Building Surveys with a Computer Controlled 3D-Laser Scanner. Der Vermessungs-Ingenieur, 45(5): 210-215 (in German)

Bureau of Meteorology. 1990. The Aneroid Barometer ... and how to use it. Information leaflet, 2 pages.

Carr, B. 1992. Using Laser Technology for Forestry and Engineering Applications. The COMPILER, 10(4): 5-15.

Cooper, M. A. R. 1982. Modern Theodolites and Levels. 2nd edition. Granada, London, ISBN 0-246-11502-5, 258 + XI pages

Deumlich, F. 1982. Surveying Instruments. Walter de Gruyter, Berlin-New York, ISBN 3-11-007765-5, 316 pages

Feist, W., Gürtler, K., Marold, T., Rosenkranz, H. 1995. Die neuen Digitalnivelliere DiNi10 und DiNi20 (The new Digital Levels DiNi10 and DiNi20). Vermessungswesen - Raumordnung (VR), 57: 65-89 (in German)

Finlayson, D. M. 1973. Isomagnetic Maps of the Australian Region for Epoch 1970.0. Report 159, Bureau of Mineral Resources, Geology and Geophysics. Australian Government Publishing Service, Canberra.

George, J. 1984. Large Area Photodiode yields Pinpoint Accuracy. Eureka – Innovative Engineering Design, July/August 1984, reprint, 3 pages.

Geotronics AB. 1994. Geodimeter System 600. Publ. No. 571 710 351, 8 pages.

Geotronics AB. 1989. Geodimeter 140 SMS Surveying Robot – Slope Monitoring System Description. Publ. No. Geo - 0024, 17 pages

Haag, R., Bayer, G., Zimmermann, M., Scherrer, R. 1997. Surveying with the automatic Fine-Pointing of the Leica TCA1800. Vermessung-Photogrammetrie-Kulturtechnik (VPK), 95(7): 466-471 (in German)

Hennes, M., Witte, B. 1991. Genauigkeitsuntersuchungen an elektronischen Tachymetern und Theodoliten der Baureihe E von Zeiss (Investigation of the Accuracy of Electronic Tacheometers and Theodolites of the E-Series by Zeiss). Vermessungswesen - Raumordnung (VR), 53(1): 30-45

Höglund, R. 1994. Practical Use of an One Man Total Station. Proc., Commission 5, 20th FIG Congress, Melbourne, Australia, 5-12 March 1994, TS502.1/1 - TS502.1/9

Ibeo. 1991. Ladar: 2D, 2D Linear, 3D. IBEO Ingnieurbüro für Elektronik und Optik, Fahrenkrön 125, D-2000 Hamburg 71, Germany, 4 pages

Ibeo. 1986. Survey Instruments - Laser Technology - Sensors and Systems: Sensors for Industrial Applications. IBEO Ingnieurbüro für Elektronik und Optik, Fahrenkrön 125, D-2000 Hamburg 71, Germany, 28 pages

Ingensand, H. 2001. Systematic Influences on Practical Measurements with (Electronic) Tacheometers and Digital Levels. In: Heister, H., Staiger, R. (eds.) Quality Management in Geodetic Metrology, 54th DVW Seminar, Fulda, 19/20 November 2001, Schriftenreihe des DVW, Vol. 42/2001, Verlag Konrad Wittwer, Stuttgart, pp. 120-135

Ingensand, H. 1993. Wild NA2000 - NA3000: Technical Paper Digital Levels. Leica AG, CH-9435 Heerbrugg Switzerland, Publ. No. G1 220e-V.93, 14 pages.

Ingensand, H. 1990. Das Wild NA2000 - Das erste Digitale Nivellier der Welt. Allgemeine Vermessungs-Nachrichten (AVN), 97(6): 201-210 (in German)

Kahmen, H., Faig, W. 1988. Surveying. Walter de Gruyter, Berlin-New York, 578 +xvii pages, ISBN 3-11-008303-5

Kern/Leica. 1990. Smart 310 – Measuring Movements. Publication 206e – 4.90 FA/8TE, Kern & Co. Ltd. (now Leica AG, Photogrammetry and Metrology, CH-5035 Unterentfelden, Switzerland)

Kogoj, D. 2001. Performance of Electronic Distance Meters in Reflectorless Distance Measurement. Allgemeine Vermessungs-Nachrichten (AVN), 108(5): 186-190 (in German)

Köhler, M. 1994. Some Theoretical Foundations for Reflectorless Measurements with the Zeiss Tacheometer Rec Elta RL. Der Vermessungsingenieur, 45(5): 216-221 (in German)

Lardelli, A. 1988. ECDS2 – A Mobile 3D-Measuring System – The New Standard for Metrology and Quality Control. Publ. No. 261e - 11.88, Kern & Co Ltd (now: Leica AG, Photogrammetry and Metrology, CH-5035 Unterentfelden, Switzerland)

Laser Alignment Inc. 1986. Laser Beacon 5000 Series for Construction and Machine Control. Publ. No. LAI 2002 (1-22-86), Laser Alignment Inc., 2850 Thornhills S.E., Grand Rapids Michigan 49546, USA, 6 pages

Lechner, W., Sudau, A., Wanzke, H. 1987. Motorisiertes Nivellement mit Digitalbarometern (Motorised Levelling with Digital Barometers). Zeitschrift für Vermessungswesen (ZfV), 112(8): 385-396

Leica. 2002. Leica Laser Radar System LR2002 - Non-contact 3D laser metrology advances factory automation. Publ. No. 727 644en, 1.2002, 4 pages.

Leica. 2001. RL-EDM Measurements. TPS News, 11/2001.

Leica. 1996. Wild NA2002 - NA3003: Technical Report, Digital Levels. Publ. No. G1 - 220 - 0en - IV.96 - VD, 14 pages

Leica. 1995. Leica Vector. Publication No. A1-300-0en-I.95-RVA, 4 pages.

Leica. 1993. Smart 310 – 3D Laser Tracker. Publication U1 206 e – V.93, Leica AG, Photogrammetry and Metrology, CH-5035 Unterentfelden, Switzerland

Leica. 1992. Mobile 3-D Metrology for Industry – Measurably Better. Publ. U1 241e - XI.92, Leica AG, Photogrammetry and Metrology, CH-5035 Unterentfelden, Switzerland

Leica Instruments. Pocket Laser Level – Perfect Dimensional Control. Leica Instruments Pty Ltd, 45 Epping Road, North Ryde NSW 2113, Australia, 4 pages.

Liechti, D. D., Harvey, B. R. 2002. An Investigation into the effects of Reflecting Surface Material Properties on Terrestrial Laser Scanner Measurements. Geomatics Research Australia, No. 76, 1-22.

Maurer, W., Schnädelbach, K. 1995. Laserinterferometry - Ten Years Experience in Calibrating Invar Levelling Staffs. Proc., First Int. Symp. Appl. Laser Techniques in Geodesy and Mine Surveying, Ljubljana, September 1995, 9 pages

Meier-Hirmer, B. Meier-Hirmer, R. 1996. Investigations of the Zeiss Tacheometer Rec Elta RL for Measurements to Structured Targets. Allgemeine Vermessungs-Nachrichten (AVN), 103(6): 233-240 (In German)

Moll, J. 1993. Low-Volume Roads Survey Laser. Publ. No. 9377 1202-SDTDC, Forest Service, Technology and Development Program, US Department of Agriculture, Washington DC 20250, February 1993, 11 pages

Möser, M. 2000. Close Range Distance Measurements. Zeitschrift für Vermessungswesen (ZfV), 125(11): 377-381

Noack, G. 1989. Problems with the Levelling of Rotating Laser Levels for Area Levelling of High Accuracy. Vermessungstechnik (VT), 37(2): 59-61 (in German)

Pallett, E. H. J. 1972. Aircraft Instruments – Principles and Applications. Pitman Publishing, London, ISBN 0-273-31747-4.

Pascoe, R. W., Rüeger, J. M. 1989. Testing a Precise Hand-Held Digital Barometer. The Australian Surveyor, 34(5): 502-513

Pike, J. M., Bargen, D. W. 1976. The NCAR Digital Barometer. Bulletin of the American Meteorological Society, 57(9): 1106-1111

Pike, J. M., Brock, F. V., Semmer, S. R. 1983. Integrated Sensors for PAM II. Paper 17.5, 5th Symposium on Meteorological Observations and Instrumentation, Toronto, Canada, pp. 326-333

Rizos, C. 1997. Principles and Practice of GPS Surveying. Monograph No. 17, School of Surveying and Spatial Information Systems, University of New South Wales, Sydney, Australia, 565 pages.

Rüeger, J. M. 2000. The Topcon DL-101C Digital Level. The Australian Surveyor, 45(2): 62-70 (Trans Tasman Surveyor, 1(3): 62-70).

Rüeger, J. M. 1996. Electronic Distance Measurement – An Introduction. 4th ed., Springer-Verlag, Berlin-Heidelberg-New York, xvii + 266 pages, ISBN 3-540-61159-2

Rüeger, J. M. 1995. EDM-Height Traversing Refraction Correction and Experiences. The Australian Surveyor, 40(4): 48-56.

Rüeger, J. M. 1995b. Surveying Practice, Education, Textbooks and Instrument Design in the Light of Changing Instrumentation. The Australian Surveyor, 40(3): 197-204

Rüeger, J. M. 1990. Electronic Distance Measurement – An Introduction. 3rd ed., Springer-Verlag, Berlin-Heidelberg-New York, xvii + 266 pages, ISBN 3-540-51523-2

Rüeger, J. M. 1978. Misalignment of EDM Reflectors and its Effects. The Australian Surveyor, 29(1): 28-36

Rüeger, J. M., Brunner, F. K. 1981. Practical Results of EDM-Height Traversing. The Australian Surveyor, 30(6): 363-372.

Ruland, R. E. 1993. The Chesapeake Laser Tracker in Industrial Metrology. Proceedings of the Third International Workshop on Accelerator Alignment, European Laboratory for Particle Physics (CERN), Geneva, Switzerland, 28 September to 1 October 1993, I/101–I/118

Schauerte, W. 1993. Digitalnivelliere des Typs Leica NA 3000 und ihr Einsatz beim Präzisionsnivellement (Digital Levels of the Type Leica NA3000 and their Use for Precise Levelling). BDVI-Forum, 19(3): 125-138

Schauerte, W. 1995. Effects of Special Errors on NA-3000 Measurements. BDVI-Forum, 21(1): 17-28 (in German)

Schwarz, W. 1985. Zur Ermittlung der integralen Temperatur der Atmosphäre mit Ultraschall für Refraktionsbestimmungen im Nahbereich (On the Evaluation of the Integral Temperature of the Atmosphere with Ultrasound for the Determination of Refraction on Close Range). No. 38 of the Veröffentlichungen des Geodätischen Instituts der Rheinisch-Westfälischen Technischen Hochschule Aachen, Germany, 136 pages (ISSN 0515-0574)

Slotwinski, A. R., Goodwin, F. E., Simonson, D. L. 1989. Utilizing GaAlAs Laser Diodes as a Source for Frequency Modulated Continuous Wave (FMCW) Coherent Laser Radars. In: Figueroa, L. (ed), Proc., Laser Diode Technology and Applications, 18-20 January 1989, Los Angeles, California, SPIE, Vol. 1043: 245-251

Sudau, A. 1994. Untersuchungen zur Leistungsfähigkeit elektronischer Druckaufnehmer für präzise barometrische Höhenmessungen (Investigations into the Performance of Electronic Pressure Sensors for Precise Barometric Heighting). Series C (Dissertations), No. 434, German Geodetic Commission, C. H. Beck'sche Verlagsbuchhandlung, München, 142 pages

Topcon Corporation. 1994. Auto Tracking Total Station AP-L1. Publ. No. 94-08-36W TE.TS 16-1, 8 pages

Vincueria, I., Tudanca, M., Aroca, C., Lopez, E., Sanchez, M. C., Sanchez, P. 1994. Flux-Gate Sensor Based on Planar Technology. IEEE Transactions on Magnetics, 30(6): 5042-5045

Walcher, H. 1985. Winkel- und Wegmessung im Maschinenbau (Angle and Distance Measurement in Mechanical Engineering). 2nd ed. VDI-Verlag GmbH, Düsseldorf, 218 pages

Whitaker, S., Call, D. B. 1986. Intelligent Pressure Transducers. Paper, Symposium, Instrumentation Society of America, Houston, Texas, October 1986, 8 pages

Whitaker, S., Call, D.B. 1987. A New Hand-Held Barometer/Altimeter Offers Portable Accuracy. Paper 24.1, Extended Abstracts, Sixth Symposium on Meteorological Observations and Instrumentation, American Meteorological Society (AMS), New Orleans, 12-16 January 1987, pp. 4487-451

Witte, B., Yang, J. 1994. Das Hand-Lasermeter DISTO der Firma Leica (The Hand-Held Laser Meter DISTO by Leica). Vermessungswesen und Raumordnung (VR), 56(4+5): 284-289

Woschitz, H. 2003. System Calibration of Digital Levels: Calibration Facility, Procedures and Results. PhD Thesis, Dept of Engineering Geodesy and Measuring Systems, Technical University, Graz, Austria, 142 pages

Wüller, H. 1988. Entwicklung und Untersuchung eines Rotations-Nivellierinstrumentes und einer photoelektrischen Nivellierlatte zur Automatisierung des geometrischen Nivellements (Development and Evaluation of a Rotating Laser Level and of a Photo-Electric Levelling Staff for the Automation of Geodetic Levelling). No. 41 of the Veröffentlichungen des Geodätischen Instituts der Rheinisch-Westfälischen Technischen Hochschule Aachen, Germany, 138 pages (ISSN 0515-0574)

Zeiske, K. 1999. TPS1100 Professional Series – A new Electronic Tacheometer Generation from Leica. Vermessungswesen und Raumordnung (VR), 61(2): 82-90 (in German)

Subject Index

- 3D imaging sensor 133

- angle-angle-distance devices 8
  - use of 13
- automatic focussing 86
- automatic levels 29
- automatic pointing 87
- automatic monitoring system 71
- automatic power off 112
- automatic searching 86

- bar code levelling instruments 27
- bar code levels 27
  - accuracy 37
  - errors 41
- bar code staffs 39
  - errors 40, 46
- barometer 15
  - digital 15
  - electronic 15
- batteries 29, 112

- calibration
  - computer assisted 31, 89
- capacitive pressure sensor 17
- cellular phones 112
- Chesapeake CMS3000 141, 142
- circles 30
  - absolute 80
  - incremental 79
  - quasi-absolute 80
- circle graduation errors 106
    - interpolation errors 107
    - periodic errors 106
  - circle reading 81, 91
- Accutape-S 6
- altimeter 15, 137
  - coarse measurement 92
  - diametrical 81
  - direction of rotation 95
  - fine measurement 93
  - graduation errors 106
- clinometer 12
- communication with computer 31, 85
- compensator 30, 53, 82
- compensation error 53, 103
- computer interface 31
- computing
  - on-board 31, 84
- corrections
  - of instrument errors 31, 112
- Criterion 8

- data recording 31, 83
- depth sounders 139
- diametrical circle reading 81
- digital barometer 15
- digital levelling instruments 27
- digital levels 32
  - errors 41
- direction measurement 113
- dislevelment 100

- electronic barometer 15
  - heighting with 20
  - performance 19
  - working principles 15
- electronic data recording 30
- electronic distance measurement (levelling) 30

electronic level sensor 82
  properties 82, 102
electronic pocket tape 5
  electro-optical sensor 7
  ultrasound sensor 6
electronic staff reading (levelling) 30
electronic theodolites 65
  circles 79
  features 78
  levelling 110
  use of 109, 111
electronic tacheometers 65, 66
  features 78
  levelling 110
  motorised 68
  reflectorless 76, 121
  scanning 77
  tracking 76
  use of 109, 112
electro-optical level sensors 95
errors in levelling with digital levels 40
earth curvature 57
exercises 22, 59, 118, 144

fluxgate compass 10
focussing
  automatic 86

graduation errors
  circles 106
Geodimeter 600 71
Gyromat 2000 68
gyro-theodolites 67

hand-held equipment 5
high definition surveying system 133

Inductosyn 79
instrument calibration 89
instrument errors 31
interface 85
interpolation error 107
invar bar code staffs 40

Kern E2 98

ladar 77, 132, 143
laser altimeter 137
laser levels 48
  calibration 54, 56
  computing heights, earth curvature and refraction 57
  errors of 53, 54, 55, 56
laser measurement system 143
laser profiling 137
laser scanners 132
laser theodolites 75
laser trackers 140
Leica Automatic Polar System (APS) 85
Leica invar bar code staff 40
Leica normal bar code staff 39
Leica DISTO 6
Leica DNA03 32
Leica HDS3000 133
Leica Laser Radar System LR200 143
Leica Locator 8
Leica NA2000 32
Leica NA3003 42, 44
Leica Smart310 141, 142
Leica TCA1800 72, 88
Leica TCRM 127
Leica TPS1100 96, 97
level sensor
  electro-optical 95, 97, 98
levelling
  electronic distance measurement 30
  electronic theodolites 110
  electronic tacheometers 110
  errors 40
  motorised 134
levelling equipment 27
  automatic levels 29
  barcode levels 27
  digital levels 27
levelling staffs 30
lidar 77, 132, 143
line of sight 47

measurements to corners 129
measuring units 110
Mensi GS100 133
Mensi GS200 133
MetricVision MV100B 143
metrology 140, 143
mobile phones 112
motorised electronic tacheometer 68
motorised electronic video theodolites 73
motorised levelling 134

Nikon DTM-1 91, 92, 93, 94, 96, 97
Nikon DTM-720 66
Nikon DTM-750 109

on-board computing 84
one-person-survey-system 70
periodic errors 107
personal computers
  communication 31, 85

phase measuring distance meters 127
phones
    cellular 112
    mobile 112
piezo-restistive pressure sensor 18
plumbing
    buildings 118
    shafts and wells 117
pointing
    automatic 86
power off facility 112
power supply 29, 84
precise levelling
    errors 40
pressure sensors 15
    capacitive 17
    piezo-resistive 18
    vibration 15
profiling 137
pulse distance meters 125

radar 77, 132, 143
real-time corrections 31, 112
recording
    data 83
reflectorless distance measurement 76, 121, 122
    beam size and shape 123
    measurements to corners 129
    multiple targets 125
    target material and colour 128
    target orientation 128
    use of 130
reflectorless electronic tacheometers 76, 121, 130
refraction 57
Riegl LMS-Z21 133
rotating laser levels 49

scale factor error 103
searching,
    automatic 86
setting error 104
    random component 104
    systematic component 105
single beam laser trackers 140
Sokkia SDL30 29
staff 30
staff reading 30
    electronic 30

tacheometers 65
    electronic 65
    motorised 73
    scanning 77
    tracking 76
Theis Telamat 51, 52
theodolites 65
    digital 65
    electronic 65
    gyro 67
    laser 75
    motorised 68
    video 73
Topcon AP-L1 71
Topcon DL-101C 43, 44
Topcon DL-102 28
Topcon ETL-1 90
Topcon GTS-6 110
Topcon GTS-701 66
tracking electronic tacheometers 76
two-way radios 112

ultrasound 6
ultrasound distance meter 6
umbrellas 111
use of
    digital levels 40
    electronic theodolites and tacheometers 109
    reflectorless EDM 130

vertical axis systems 90
vertical circle compensator 82
vertical circle index error 105
vertical circle index correction 105
vibration pressure sensor 15
video theodolites 73

walkie-talkies 112
Wild NA2000 32, 33, 34, 35, 36, 42
Wild TC1600 81
Wild TM3000D 72
Wild TM3000L 74
Wild TM3000V 74

Zeiss DiNi 10 28
Zeiss Elta6 107
Zeiss ETh3 108
Zeiss Reg Elta RL 126, 129
Zeiss Ni002 135
zenith angle measurement 116

Publications from the

SCHOOL OF SURVEYING AND SPATIAL INFORMATION SYSTEMS
(formerly: SCHOOL OF GEOMATIC ENGINEERING)
THE UNIVERSITY OF NEW SOUTH WALES
ABN 57 195 873 179

To order, write or fax to:
Publications Officer, School of Surveying and Spatial Information Systems,
The University of New South Wales, UNSW SYDNEY NSW 2052, AUSTRALIA
Email: survsis@unsw.edu.au Fax: +61 - 2 - 9313 - 7493

NOTE ON MAIL ORDERS: ALL ORDERS MUST BE PREPAID.
NO REQUESTS FOR RETURNS ARE ACCEPTED.
CREDIT CARDS ARE ACCEPTED. CONDITIONS APPLY. SEE ORDER FORM FOR DETAILS.
WHEN PAYING BY *CHEQUE*, THE CHEQUES MUST BE PAYABLE TO 'SCHOOL OF SURVEYING & SIS, UNSW', IN AUSTRALIAN DOLLARS AND DRAWN ON AN AUSTRALIAN BANK.

MONOGRAPHS

Australian prices include GST #. Overseas prices include delivery by UNSW's air-lifted mail service (~2-4 weeks to Europe and North America) #. Rates for air mail through Australia Post on application.

For all (local and overseas) **orders, add $11.00 for processing and handling** (once per order).

(Prices effective Oct 2010)

		Price # Australia (incl. GST)	**Price #** Overseas
M1.	R. S. Mather, "The Theory and Geodetic Use of some Common Projections", (3rd edition), 125 pp, reprint 1998, ISBN 0-85839-007-8	$ 16.50	$ 15.00
M2.	R. S. Mather, "The Analysis of the Earth's Gravity Field", 172 pp, 1971 (no ISBN)	$ 8.80	$ 8.00
M8.	A. H. W. Kearsley, "Geodetic Surveying", 96 pp, revised reprint 1988, ISBN 0-85839-036-1	$ 13.20	$ 12.00
M11.	W. F. Caspary, "Concepts of Network and Deformation Analysis", 183 pp, 3rd corrected impression, 2000, ISBN 0-85839-044-2	$ 27.50	$ 25.00
M12.	F. K. Brunner, "Atmospheric Effects on Geodetic Space Measurements", 110 pp, 1988, ISBN 0-85839-048-5	$ 17.60	$ 16.00
M13.	B. R. Harvey, "Practical Least Squares and Statistics for Surveyors", (3rd revised and extended edition), 341 pp, 2006, Reprint 2009, ISBN 0-7334-2339-6	$ 40.00	$ 36.36
M14.	E. G. Masters and J. R. Pollard (Eds.), "Land Information Management", 269 pp, 1991, ISBN 0-85839-061-2	$ 22.00	$ 20.00
M15/1	E. G. Masters and J. R. Pollard (Eds.), "Land Information Management - Geographic Information Systems - Advance Remote Sensing Vol. 1", 295 pp, 1993, ISBN 0-85939-064-7	$ 33.00	$ 30.00
M15/2	E. G. Masters and J. R. Pollard (Eds.), "Land Information Management - Geographic Information Systems - Advance Remote Sensing Vol. 2", 376 pp, 1993, ISBN 0-85839-065-5	$ 33.00	$ 30.00
M16.	A. Stolz, "An Introduction to Geodesy", 2nd extended edition, 148 pp, 2001, Reprint 2009, ISBN 0-7334-1736-1	$ 24.20	$ 22.00
M18.	J. M. Rüeger, "Electronic Surveying Instruments – A Review of Principles, Problems and Procedures", 1st ed., 166 pp, 2003, Reprint 2010 ISBN 0-7334-2083-4	$ 25.30	$ 23.00

UNISURV REPORTS - S SERIES

(Prices effective Oct 2010)

Australian Prices *:	S8 - S20	$11.00 #	S29 onwards	$33.00 #
Overseas Prices **:	S8 - S20	$10.00 #	S29 onwards	$30.00 #

* Australian prices include GST. #

** Overseas prices include delivery by UNSW's air-lifted mail service (~2-4 weeks to Europe and North America). #
Rates for air mail through Australia Post on application.

# For all (local and overseas) **orders, add $11.00 for processing and handling.**

S17. C. Rizos, "The Role of the Gravity Field in Sea Surface Topography Studies", Unisurv S17, 299 pp, 1980, ISBN 0-85839-029-9

S19. R. Coleman, "A Geodetic Basis for Recovering Ocean Dynamic Information from Satellite Altimetry", Unisurv S19, 332 pp, 1981, ISBN 0-85839-029-9

S36. A. R. Marshall, "Network Design and Optimisation in Close Range Photogrammetry", Unisurv S36, 249 pp, 1989, ISBN 0-85839-054-X

S37. W. Jaroondhampinij, "A Model of Computerised Parcel-Based Land Information System for the Department of Lands, Thailand", Unisurv S37, 281 pp, 1989, ISBN 0-85839-055-8

S39. C. Bosloper, "Multipath and GPS Short Periodic Components of the Time Variation of the Differential Dispersive Delay", Unisurv S39, 214 pp, 1990, ISBN 0-85839-057-4

S40. J. M. Nolan, "Development of a Navigational System Utilising the Global Positioning System in a Real Time, Differential Mode", Unisurv S40, 163 pp, 1990, ISBN 0-85839-058-2

S41. R. T. Macleod, "The Resolution of Mean Sea Level Anomalies along the NSW Coastline Using the Global Positioning System", Unisurv S41, 278 pp, 1990, ISBN 0-85839-060-4

S42. D. A. Kinlyside, "Densification Surveys in New South Wales - Coping with Distortions", Unisurv S42, 209 pp, 1992, ISBN 0-85839-062-0

S43. A. H. W. Kearsley (ed.), Z. Ahmad, B. R. Harvey and A. Kasenda, "Contributions to Geoid Evaluations and GPS Heighting", Unisurv S43, 209 pp, 1993, ISBN 0-85839-063-9

S44. P. Tregoning, "GPS Measurements in the Australian and Indonesian Regions (1989-1993)", Unisurv S44, 134 + xiii pp, 1996, ISBN 0-85839-068-X

S45. W.-X. Fu, "A Study of GPS and Other Navigation Systems for High Precision Navigation and Attitude Determinations", Unisurv S45, 332 pp, 1996, ISBN 085839-069-8

S46. P. Morgan et al, "A Zero Order GPS Network for the Australia Region", Unisurv S46, 187 + xii pp, 1996, ISBN 0-85839-070-1

S47. Y. Huang, "A Digital Photogrammetry System for Industrial Monitoring", Unisurv S47, 145 + xiv pp, 1997, ISBN 0-85839-072-8

S48. K. Mobbs, "Tectonic Interpretation of the Papua New Guinea Region from Repeat Satellite Measurements", Unisurv S48, 256 + xv pp, 1997, ISBN 0-85839-073-6

S50. M. D. Subari, "Low-cost GPS Systems for Intermediate Surveying and Mapping Accuracy Applications", Unisurv S50, 179 + xiii pp, 1997, ISBN 0-85839-075-2

S51. L.-S. Lin, "Real-Time Estimation of Ionospheric Delay Using GPS Measurements", Unisurv S51, 199 + xix pp, 1997, ISBN 0-7334-1664-0

S53. D. B. Lemon, "The Nature and Management of Positional Relationships within a Local Government Geographic Information System", Unisurv S53, 273 + xvi pp, 1997, ISBN 0-7334-1678-0

S54. C. Ticehurst, "Development of Models for Monitoring the Urban Environment Using Radar Remote Sensing", Unisurv S54, 282 + xix pp, 1998, ISBN 0-7334-1679-9

S55. S. S. Boey, "A Model for Establishing the Legal Traceability of GPS Measurements for Cadastral Surveying in Australia", Unisurv S55, 186 + xi pp, 1999, ISBN 0-7334-0685-X

S56. P. Morgan and M. Pearse, "A First-Order Network for New Zealand", Unisurv S56, 134 + x pp, 1999, ISBN 0-7334-0685-8

S57. P. N. Tiangco, "A Multi-Parameter Radar Approach to Stand Structure and Forest Biomass Estimation", Unisurv S57, 319 + xxii pp, 2000, ISBN 0-7334-0786-2

S58. M. A. Syafi'i, "Object–Relational Database Management Systems (ORDBMS) for Managing Marine Spatial Data: ADCP Data Case Study", Unisurv S58, 123 + ix pp, 2000, ISBN 0-7334-1704-3

S59. X.-Q. Lu, "Strategies for Improving the Determination of Displacements of Sea Surface Temperature Patterns Using Consecutive AVHRR Thermal Images", Unisurv S59, 209 + xiii pp, 2000, ISBN 0-7334-1721-3

S60. G. Dickson, "GPS-Controlled Photography: The Design, Development and Evaluation of an Operational System Utilising Long-Range Kinematic GPS", Unisurv S60, 417 + x pp, 2000, ISBN 0-7334-1725-6

S61. J. Wang, "Modelling and Quality Control for Precise GPS and GLONASS Satellite Positioning", Unisurv S61, 171 + x pp, 2001, ISBN 0-7334-1766-3

S62. Y. Wang, "Knowledge-Based Road Extraction from Aerial Images", Unisurv S62, 178 + xi pp, 2001, ISBN 0-7334-1767-1

S63. L. Ge, "Development and Testing of Augmentations of Continuously-Operating GPS Networks to Improve their Spatial and Temporal Resolution", Unisurv S63, 230 + xvi pp, 2001, ISBN 0-7334-1841-4

S64. H.-Y. Chen, "A Study on Real-Time Medium-Range Carrier-Phase-Based GPS Multiple Reference Stations", Unisurv S64, 182 + xxiv pp, 2001, ISBN 0-7334-1842-2

S65. G. Y. K. Shea, "A Web-Based Approach to the Integration of Diverse Data Sources for GIS", Unisurv S65, 233 + xv pp, 2001, ISBN 0-7334-1845-7

S66. M. Mirbagheri, "Analysis of Interferometric SAR for Topographic Mapping", Unisurv S66, 135 + xvii pp, 2001, ISBN 0-7334-1856-2

S67. P. Wang, "Applying Two-Dimensional Kalman Filtering Techniques to Digital Elevation Models for Terrain Surface Modelling", Unisurv S67, 175 + xi pp, 2001, ISBN 0-7334-1857-0

S69. C. Satirapod, "Improving the GPS Data Processing Algorithm for Precise Static Relative Positioning", Unisurv S69, 131 + viii pp, 2002, ISBN 0-7334-1901-1

S70. R. Mason, "Developing Australian Spatial Data Policies – Existing Practices and Future Strategies", Unisurv S70, 258 + xv pp, 2002, ISBN 0-7334-1941-0

S71. C. Ogaja, "A Framework in Support of Structural Monitoring by Real Time Kinematic GPS and Multisensor Data", Unisurv S71, 191 + xiii pp, 2002, ISBN 0-7334-1958-5

S72. L. Dai, "Augmentation of GPS with GLONASS and Pseudolite Signals for Carrier Phase Based Kinematic Positioning", Unisurv S72, 188 + viii pp, 2002, ISBN 0-7334-1975-5

S73. C. Roberts, "A continuous Low-Cost GPS-Based Volcano Deformation Monitoring System in Indonesia", Unisurv S73, 271 + xvi pp, 2002, ISBN 0-7334-1976-3

S74. V. Janssen, "A Mixed-Mode GPS Network Processing Approach for Volcano Deformation Monitoring", Unisurv S74, 199 + viii pp, 2003, ISBN 0-7334-2059-1

S75. Y. H. Lu, "Automatic Building Extraction for 3D Terrain Reconstruction Using Image Interpretation Techniques", Unisurv S75, 175 + xii pp, 2004, ISBN 0-7334-2141-5

S76. Y. K. Lee, "Integration of GPS/Pseudolites/INS for High Precision Kinematic Positioning and Navigation", Unisurv S76, 200 + xiv pp, 2004, ISBN 0-7334-2149-0

Note: Since 1 January 2005, the School's PhD and MEng theses are nor longer published in this series. See www.ssis.unsw.edu.au for information on post 2004 theses.

School of Surveying and Spatial Information Systems
The University of New South Wales
ABN 57 195 873 179

ORDER FORM

To order, mail or fax this form to: Publications Officer, School of Surveying and Spatial Information Systems, The University of New South Wales, UNSW SYDNEY NSW 2052, AUSTRALIA Fax: +61 - 2 - 9313 - 7493

Name and postal address of ordering person/organisation:

____
____
____
____
____

Email : ____________________ Fax : ____________________

Day time phone number : ____________________ Date : ____________

Note: All orders must be prepaid. No requests for returns are accepted.

I/We order herewith:

____________________ $ ____________
____________________ $ ____________
____________________ $ ____________

Postage and Handling (from 1 July 2004) $ **11.00**

Total $ ____________

Payment Details:

☐ A cheque, drawn on an Australian Bank, in Australian Dollars and payable to 'School of Surveying & SIS, UNSW' is enclosed

☐ Please debit my credit card: ☐ Mastercard ☐ Visa

Name on Card: ____________________ Signature: ____________________

Card No: ☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐☐ Expiry Date : ________

IF THE PIE'S NOT BIG ENOUGH, MAKE A BIGGER PIE



THE STRONGEST COMPETITIVE FORCES DETERMINE THE PROFITABILITY OF AN INDUSTRY

ELIMINATE UNNECESSARY STEPS

6
2
9
7
1
4
10
3
8
5

NONE OF US IS AS SMART AS ALL OF US



THERE'S A GAP IN THE MARKET, BUT IS THERE A MARKET IN THE GAP?

THE BUSINESS BOOK

BIG IDEAS SIMPLY EXPLAINED

NO GREAT MANAGER OR LEADER EVER FELL FROM HEAVEN

TEAMWORK IS THE FUEL THAT ALLOWS COMMON PEOPLE TO ATTAIN UNCOMMON RESULTS

BORROW SHORT, LEND LONG



BE FIRST OR BE BETTER



ONLY THE PARANOID SURVIVE

YOU DON'T NEED A HUGE COMPANY, JUST A COMPUTER AND A PART-TIME PERSON

BE AN ENZYME— A CATALYST FOR CHANGE

IF YOU'RE DIFFERENT, YOU WILL STAND OUT

TECHNOLOGY IS THE GREAT GROWLING ENGINE OF CHANGE

THE BUSINESS BOOK

THE
BUSINESS
BOOK

DK

**LONDON, NEW YORK, MELBOURNE,
MUNICH, AND DELHI**

DK

SENIOR EDITOR
Sam Atkinson

PROJECT ART EDITOR
Amy Child

EDITORS
Scarlett O'Hara, Alison Sturgeon

US EDITORS
Margaret Parrish, Jane Perlmutter

PICTURE RESEARCHER
Sumedha Chopra

MANAGING EDITOR
Esther Ripley

MANAGING ART EDITOR
Karen Self

PUBLISHER
Sarah Larter

ART DIRECTOR
Phil Ormerod

ASSOCIATE
PUBLISHING DIRECTOR
Liz Wheeler

PUBLISHING DIRECTOR
Jonathan Metcalf

JACKET DESIGNER
Laura Brim

JACKET EDITOR
Manisha Majithia

JACKET DESIGN
DEVELOPMENT MANAGER
Sophia Tampakopoulos

ILLUSTRATIONS
James Graham

PRODUCER, PRE-PRODUCTION
Rebecca Fallowfield

PRODUCER
Gemma Sharpe

original styling by

STUDIO8 DESIGN

produced for DK by

COBALT ID

ART EDITORS
Darren Bland, Paul Reid

EDITORS
Richard Gilbert, Diana Loxley,
Sarah Tomley, Marek Walisiewicz

First American Edition, 2014

Published in the United States by
DK Publishing
375 Hudson Street
New York, New York 10014

11 12 13 14 15 10 9 8 7 6 5 4 3 2 1
001 - 192364 - Feb/2014

Copyright © 2014
Dorling Kindersley Limited
All rights reserved

Without limiting the rights under copyright reserved above, no part of this publication may be reproduced, stored in or introduced into a retrieval system, or transmitted, in any form, or by any means (electronic, mechanical, photocopying, recording, or otherwise), without the prior written permission of both the copyright owner and the above publisher of this book.

Published in Great Britain by
Dorling Kindersley Limited.

A catalog record for this book is available from the Library of Congress.

ISBN: 978-1-4654-1585-1

Printed and bound in China by
Leo Paper Products Ltd

**Discover more at
www.dk.com**

CONTRIBUTORS

IAN MARCOUSE, CONSULTANT EDITOR

Ian Marcousé lectures in business and economics education at the Institute of Education in London. He has written a host of business text books for A-level and BTEC students, including the popular *A–Z Business Studies* handbooks, and is the founder and director of A–Z Business Training Ltd.

PHILIPPA ANDERSON

Philippa Anderson is a communications consultant and business writer who has authored articles, magazine features, and books on numerous aspects of business, from market research to leadership. She also provides communications consultancy for multinational firms, including 3M, Anglo American, and Coca-Cola.

ALEXANDRA BLACK

Alexandra Black studied business communications before embarking on a writing career that led her to Japan and stints with financial newspaper group Nikkei Inc. and investment bank J. P. Morgan. She later worked for a direct marketing publisher in Sydney, Australia, before moving to Cambridge, UK. She writes on a range of subjects, from business to history and fashion.

DENRY MACHIN

Denry Machin is an associate tutor at Keele University, UK, and is working at doctoral research on the application of business thinking within education. He also works for Harrow International Management Services as projects manager, assisting in the development of Harrow School's presence in Asia. He is the author of several business books, journals, and magazine articles.

NIGEL WATSON

Nigel Watson has taught business and economics for A-Level and International Baccalaureate students for 25 years. He has authored and co-authored books and magazine articles in both subjects.

CONTENTS

10 INTRODUCTION

START SMALL, THINK BIG
STARTING AND GROWING THE BUSINESS

20 **If you can dream it, you can do it**
Beating the odds at start-up

22 **There's a gap in the market, but is there a market in the gap?**
Finding a profitable niche

24 **You can learn all you need to know about the competition's operation by looking in his garbage cans**
Study the competition

28 **The secret of business is to know something that nobody else knows**
Stand out in the market



32 **Be first or be better**
Gaining an edge

40 **Put all your eggs in one basket, and then watch that basket**
Managing risk

42 **Luck is a dividend of sweat. The more you sweat, the luckier you get**
Luck (and how to get lucky)

43 **Broaden your vision, and maintain stability while advancing forward**
Take the second step

44 **Nothing great is created suddenly**
How fast to grow

46 **The role of the CEO is to enable people to excel**
From entrepreneur to leader

48 **Chains of habit are too light to be felt until they are too heavy to be broken**
Keep evolving business practice

52 **A corporation is a living organism; it has to continue to shed its skin**
Reinventing and adapting

58 **Without continuous growth and progress, success has no meaning**
The Greiner curve

62 **If you believe in something, work nights and weekends—it won't feel like work**
The weightless start-up

LIGHTING THE FIRE
LEADERSHIP AND HUMAN RESOURCES

68 **Managers do things right, leaders do the right thing**
Leading well

70 **None of us is as smart as all of us**
The value of teams

72 **Innovation must be invasive and perpetual: everyone, everywhere, all of the time**
Creativity and invention

74 **Dissent adds spice, spirit, and an invigorating quality**
Beware the yes-men

76 **No great manager or leader ever fell from heaven**
Gods of management

78 **A leader is one who knows the way, goes the way, and shows the way** Effective leadership

80 **Teamwork is the fuel that allows common people to attain uncommon results** Organizing teams and talent

86 **Leaders allow great people to do the work they were born to do** Make the most of your talent

88 **The way forward may not be to go forward** Thinking outside the box

90 **The more a person can do, the more you can motivate them** Is money the motivator?

92 **Be an enzyme—a catalyst for change** Changing the game

100 **The worst disease that afflicts executives is egotism** Hubris and nemesis

104 **Culture is the way in which a group of people solves problems** Organizational culture

110 **Emotional intelligence is the intersection of heart and head** Develop emotional intelligence

112 **Management is a practice where art, science, and craft meet** Mintzberg's management roles

114 **A camel is a horse designed by committee** Avoid groupthink

115 **The art of thinking independently, together** The value of diversity

MAKING MONEY WORK

MANAGING FINANCES

120 **Do not let yourself be involved in a fraudulent business** Play by the rules

124 **Executive officers must be free from avarice** Profit before perks

126 **If wealth is placed where it bears interest, it comes back to you redoubled** Investment and dividends

128 **Borrow short, lend long** Making money from money

130 **The interests of the shareholders are our own** Accountability and governance

132 **Make the best quality of goods at the lowest cost, paying the highest wages possible** Your workers are your customers

138 **Utilize OPM—Other People's Money** Who bears the risk?

146 **Swim upstream. Go the other way. Ignore the conventional wisdom** Ignoring the herd

150 **Debt is the worst poverty** Leverage and excess risk

152 **Cash is king** Profit versus cash flow

154 **Only when the tide goes out do you discover who's been swimming naked** Off-balance-sheet risk

155 **Return on equity is a financial goal that can become an own goal** Maximize return on equity

156 **As the role of private equity has grown, so have the risks it poses** The private equity model

158 **Assign costs according to the resources consumed** Activity-based costing

WORKING WITH A VISION
STRATEGY AND OPERATIONS

164 Turn every disaster into an opportunity
Learning from failure

166 If I had asked people what they wanted, they would have said faster horses
Leading the market

170 The main thing to remember is, the main thing is the main thing
Protect the core business

172 You don't need a huge company, just a computer and a part-time person
Small is beautiful

178 Don't get caught in the middle
Porter's generic strategies

184 The essence of strategy is choosing what not to do
Good and bad strategy

186 Synergy and other lies
Why takeovers disappoint

188 The Chinese word "crisis" is composed of two characters: "danger" and "opportunity"
Crisis management

190 You can't grow long-term if you can't eat short-term
Balancing long- versus short-termism

192 Market Attractiveness, Business Attractiveness
The MABA matrix

194 Only the paranoid survive
Avoiding complacency

202 To excel, tap into people's capacity to learn
The learning organization

208 The future of business is selling less of more
The long tail

210 To be an optimist ... have a contingency plan for when all hell breaks loose
Contingency planning

211 Plans are useless, but planning is indispensable
Scenario planning

212 The strongest competitive forces determine the profitability of an industry
Porter's five forces

216 If you don't have a competitive advantage, don't compete
The value chain

218 If you don't know where you are, a map won't help
The capability maturity model

220 Chaos brings uneasiness, but it also allows for creativity and growth
Coping with chaos

222 Always do what is right. It will gratify half of mankind and astonish the other
Morality in business

223 There is no such thing as a minor lapse in integrity
Collusion

224 Make it easier to do the right thing and much harder to do the wrong thing
Creating an ethical culture

SUCCESSFUL SELLING
MARKETING MANAGEMENT

232 Marketing is far too important to leave to the marketing department
The marketing model

234 Know the customer so well that the product fits them and sells itself
Understanding the market

242 Attention, Interest, Desire, Action
The AIDA model

244 **Marketing myopia** Focus on the future market

250 **The cash cow is the beating heart of the organization** Product portfolio

256 **Expanding away from your core has risks; diversification doubles them** Ansoff's matrix

258 **If you're different, you will stand out** Creating a brand

264 **There is only one boss: the customer** Make your customers love you

268 **Whitewashing, but with a green brush** Greenwash

270 **People want companies to believe in something beyond maximizing profits** The appeal of ethics

271 **Everybody likes something extra for nothing** Promotions and incentives

272 **In good times people want to advertise; in bad times they have to** Why advertise?

274 **Make your thinking as funny as possible** Generating buzz

276 **E-commerce is becoming mobile commerce** M-commerce

278 **Trying to predict the future is like driving with no lights looking out of the back window** Forecasting

280 **Product, Place, Price, Promotion** Marketing mix

DELIVERING THE GOODS

PRODUCTION AND POSTPRODUCTION

288 **See how much, not how little, you can give for a dollar** Maximize customer benefits

290 **Costs do not exist to be calculated. Costs exist to be reduced** Lean production

294 **If the pie's not big enough, make a bigger pie** Fulfilling demand

296 **Eliminate unnecessary steps** Simplify processes

300 **Every gain through the elimination of waste is gold in the mine** Juran's production ideal

302 **Machines, facilities, and people should work together to add value** Kaizen

310 **Learning and innovation go hand in hand** Applying and testing ideas

312 **Your most unhappy customers are your greatest source of learning** Feedback and innovation

314 **Technology is the great growling engine of change** The right technology

316 **Without big data, you are blind and deaf and in the middle of a highway** Benefitting from "big data"

318 **Put the product into the customer's hands—it will speak for itself** Quality sells

324 **The desire to own something a little better, a little sooner than necessary** Planned obsolescence

326 **Time is money** Time-based management

328 **A project without a critical path is like a ship without a rudder** Critical path analysis

330 **Taking the best from the best** Benchmarking

332 **DIRECTORY**

340 **GLOSSARY**

344 **INDEX**

351 **ACKNOWLEDGMENTS**

INTRODU

CTION



From the time that goods and services began to be traded in early civilizations, people have been thinking about business. The emergence of specialized producers and the use of money as a means of exchange were methods by which individuals and societies could, in modern terms, gain a “business edge.” The ancient Egyptians, the Mayans, the Greeks, and the Romans all knew that wealth creation through the mechanism of commerce was fundamental to the acquisition of power, and formed the base on which civilization could prosper.

The lessons of the early traders resonate even today. Specialism revealed the benefits of economies of scale—that production costs fall as more items are produced. Money gave rise to the concept of “value added”—selling an item for more than it cost to produce. Even when barter was the norm, producers still knew it was advantageous to lower costs and raise the value of goods. Today’s companies may use different technologies and trade on a global scale, but the essence of business has changed little in millennia.

> “The art of administration is as old as the human race.”
>
> **Edward D. Jones**
> **US investment banker**
> **(1893–1982)**

An era of change

However, the study of business as an activity in its own right emerged relatively recently. The terms “manager” and “management” did not appear in the English language until the late 16th century. In his 1977 text *The Visible Hand*, Dr. Alfred Chandler divided business history into two periods: pre-1850 and post-1850. Before 1850 local, family-owned firms dominated the business environment. With commerce operating on a relatively small scale, little thought was given to the wider disciplines of business.

The growth of the railroads in the mid-1800s, followed by the Industrial Revolution, enabled businesses to grow beyond the immediate gaze of friends or family, and outside the immediate locale. To prosper in this new—and increasingly international—environment businesses needed different, and more rigorous, processes and structures. The geographic scope and ever-growing size of these evolving businesses required new levels of coordination and communication—in short, businesses needed management.

Managing production

The initial focus of the new breed of manager was on production. As manufacturing moved from individual craftsmen to machinery, and as ever-greater scale was required, theorists such as Henri Fayol examined ever-more-efficient ways of operating. The theories of Scientific Management, chiefly formulated by Frederick Taylor, suggested that there was “one best way” to perform a task. Businesses were organized by precise routines, and the role of the worker was simply to supervise and “feed” machinery, as though they were part of it. With the advent of production lines in the early 1900s, business was characterized by standardization and mass production.

While Henry Ford’s Model T car is seen as a major accomplishment of industrialization, Ford also remarked “why is it every time I ask for a pair of hands, they come with



a brain attached?” Output may have increased, but so too did conflict between management and staff. Working conditions were poor and businesses ignored the sociological context of work—productivity mattered more than people.

Studying people

In the 1920s a new influence on business thinking emerged—the Human Relations Movement of behavioral studies. Through the work of psychologists Elton Mayo and Abraham Maslow, businesses began to recognize the value of human relations. Workers were no longer seen as simply “cogs in the machine,” but as individuals with unique needs. Managers still focused on efficiency, but realized that workers were more productive when their social and emotional needs were taken care of. For the first time, job design, workplace environments, teamwork, remuneration, and nonfinancial benefits were all considered important to staff motivation.

In the period following World War II, business practice shifted again. Wartime innovation had yielded significant technological advances that could be applied to commerce. Managers began to utilize quantitative analysis, and were able to make use of computers to help solve operational problems. Human relations were not forgotten, but in management thinking, measurability returned to the fore.

Global brands

The postwar period saw the growth of multinationals and conglomerates—businesses with multiple and diverse interests across the globe. The war had made the world seem smaller, and had paved the way for the global brand. These newly emerging global brands grew as a result of a media revolution—television, magazines, and newspapers gave businesses the means to reach a mass audience. Businesses had always used advertising to inform customers about products and to persuade them to buy, but mass media provided the platform for a new, and much broader, field—marketing. In the 1940s US advertising executive Rosser Reeves promoted the value of a Unique Selling Proposition. By the 1960s, marketing methods had shifted from simply telling customers about products to listening to what customers wanted, and adapting products and services to suit that.

> “Entrepreneurship is about survival, which nurtures creative thinking. Business is not financial science, it’s about trading—buying and selling.”
>
> **Anita Roddick**
>
> **UK entrepreneur (1942–2007)**

Initially, marketing had its critics. In the early 1960s hype about the product became more important than quality, and customers grew dissatisfied with empty claims. This, and competition from Japanese manufacturers, had Western companies embracing a new form of business thinking: Total Quality Management (TQM) and Zero Defects management. Guided by management theorists, such as W. Edwards Demming and Philip B. Crosby, quality was seen as the responsibility of the entire company, not just those on the production line. Combining Human Relations thinking and the customer-focused approach of marketing, many companies »

adopted the Japanese philosophy of *kaizen*: "continuous improvement of everything, by everyone." Staff at all levels was tasked with improving processes and products through "quality circles." While TQM is no longer the buzzword it once was, quality remains important. The modern iteration of TQM is Six Sigma, an approach to process improvement that was developed by Motorola in 1986 and adapted by Jack Welch during his time as CEO of General Electric.

Gurus and thinkers

Business history itself emerged as a topic of study in the 1970s. Dr. Alfred Chandler progressed the study of business history from the purely descriptive to the analytical—his course at Harvard Business School stressed the importance of organizational capabilities, technological innovation, and continuous learning. Taking their cue from Chandler, in the 1980s and 1990s management experts—such as Michael Porter, Igor Ansoff, Rosabeth Moss Kanter, Henry Mintzberg, and Peter Drucker—encouraged businesses to consider their environments, to consider the needs of people, and to remain adaptable to change. Maintaining the conditions for business growth, and the correct positioning of products within their market, were considered key to business strategy. Moreover, what distinguished these gurus from their predecessors—who had tended to focus on operational issues—was a focus on leadership itself. For example, Charles Handy's *The Empty Raincoat* revealed the paradoxes of leadership, and acknowledged the vulnerabilities and fragilities of the managers themselves. Leadership in the context of business, these writers recognized, is no easy undertaking.

Digital pioneering

Just as television and mass media had done before, the growth of the Internet in the 1990s and early 2000s heralded a new era for business. While early hype led to the failure of many online start-ups in the dot-com bubble of 1997 to 2000, the successful e-commerce pioneers laid the foundations for a business landscape that would be dominated by innovation. From high-tech garage start-ups—such as Hewlett-Packard and Apple—to the websites, mobile apps, and social-media forums of the modern business environment, technology is increasingly vital for business.

> Business can be a source of progressive change.
>
> **Jerry Greenfield**
>
> **US businessman, co-founder of Ben and Jerry's ice cream (1951–)**

The explosion of new businesses thanks to technology also helped to expand the availability of finance. During the 1980s and 1990s finance had grown into a distinct discipline. Corporate mergers and high-profile takeovers became a way for businesses to grow beyond their operational limits; leverage joined marketing and strategy as part of the management lexicon. In the late 1990s this expanded to venture capital: the funding of small companies by profit-seeking investors. The risk of starting and running a business remains, but the opportunities afforded by technology and easier access to finance have made taking the first step a little easier. With micro-finance, and the support of online

networks and communities of like-minded people dispensing business advice, enterprise has never been more entrepreneurial.

Recent business thinking has brought diversity and social responsibility to the fore. Businesses are encouraged, and increasingly required by law, to employ people from diverse backgrounds and to act in an ethical manner, wherever they operate in the world. Businesses such Nike and Adidas require suppliers to prove that labor conditions in their factories meet required standards. Sustainability, recycling, diversity, and environmentalism have entered business thinking alongside strategic management and risk.

New horizons

If business thinking has shifted, so too has the nature of business itself. Where once a company was constrained by its locality, today the opportunities are truly global. Globalization does, however, mean that business is more competitive than ever. Emerging markets are creating new opportunities and new threats. They may be able to outsource production to low-cost countries, but as their economies grow, these emerging nations are breeding new competition. China, for example, may be "the world's factory," but its home-grown companies are also starting to represent a threat to Western businesses. As the global recession of 2007–08 and ongoing economic uncertainty have proven, business in the 21st century is increasingly more interdependent and more challenging than ever before. Starting a business might be easier, but to survive entrepreneurs need the tenacity to take an idea to market, the business acumen to turn a good plan into a profitable enterprise, and the financial skill to maintain success.

Continual change

For centuries social, political, and technological factors have forced companies and individuals to create new ways of generating profits. Whether bartering goods with a neighboring village or seeking ways to make profits from social networking, business thinking has changed, shifted, and evolved to mirror the wants and needs of the societies whose wealth it creates. Sometimes, as in the 2008 financial crisis, business failed in its efforts. In other examples—the legacy of Apple's game-changing products, for example—companies have been spectacularly successful.

Business is a fascinating subject. It surrounds us and affects us daily. A walk down the street, a wander around a supermarket, an Internet search on almost any topic will reveal commerce in its many and varied forms. At its core business is, and always has been, about survival and surplus—about the advancement of self and of society. As the world continues to open up, and as opportunities for enterprise multiply, an interest in business has never been more relevant, or more exciting. Moreover, for those with entrepreneurial spirit, business has never been more rewarding. ■

> Business, more than any other occupation, is a continual dealing with the future; it is a continual calculation, an instinctive exercise in foresight.
>
> **Henry R. Luce**
>
> **US magazine publisher** (1898–1967)

START S
THINK B

STARTING AND GROWING THE BUSINESS

MALL,
IG

All businesses start from the same point: an idea. It is what happens to that idea that determines business success.

According to *Entrepreneur* magazine, nearly half of all new start-ups fail within the first three years. Beating the odds at start-up is tough. First and foremost an idea, no matter how good, must be combined with entrepreneurial spirit, defined as the willingness to take risk. Without entrepreneurial spirit a great idea might never be pursued. Not all ideas are good ones though; it would be a foolish entrepreneur who rushed a product to market without careful thought, research, and detailed planning. Risk might be inherent in business enterprise, but successful entrepreneurs are those who are not only willing to take risks, but are also able to manage risk.

Realistic propositions

Having an idea is the first step—the next hurdle is finance. Some start-ups require very little capital, and a few require none at all. However, many require significant backing, and most will need to seek funding at some stage in the growth process. An entrepreneur must be able to convince financial backers that the concept is valid and that they have the skills and knowledge to turn the original concept into a successful business.

It follows that the idea must be profitable. Sometimes, an idea may look great on paper, but turn out to be uncommercial when put into practice. Determining whether an idea has potential requires a study of the competition and the relevant market. Who is competing for customers' time and money? Are these competitors selling directly competitive products or possible substitutes? How are competitors perceived in the market? How big is the market?

Most markets are increasingly global, crowded, and competitive. Few companies are lucky enough to find a profitable niche—to succeed, companies need to do something different in order to stand out in the market. The strategy for most companies is to differentiate; this means demonstrating to customers that they offer something that is not available from competitors—a Unique or Emotional Selling Proposition (USP or ESP).

> The only thing worse than starting something and failing … is not starting something.
>
> **Seth Godin**
>
> **US entrepreneur** (1960–)

Such attempts to stand out are everywhere. Every business, and at every stage of production, from raw-material extraction to after-sales service, tries to distinguish its products or services from all others. Walk into any bookstore, for example, and you will see countless examples of books, often on the same topic, using design, style, and even size (large or small) to stand out from the competition.

Gaining an edge often depends on one of two things: being first into a new market niche, or being different from the competition. For example, in 1995 eBay was first into the online auction market, and has dominated it ever since. Similarly, Volvo was first to identify the opportunity for luxury bus sales in India, and has enjoyed healthy sales. In contrast, Facebook was by no means the first social network, but it is the most successful; its edge was having a better product.



Once a company is established, the challenge shifts: the objective now is to maintain sales and grow in the short- and long-term.

Adapting to survive

Long-term business survival depends upon the company constantly reinventing and adapting itself in order to remain ahead of the competition. In dynamic markets, which are growing and evolving all the time, the idea on which the company was founded may become irrelevant over time, and rivals will almost certainly copy it. The ecosystem in which a business operates is rarely, if ever, static. Corporations exist in these ecosystems as living organisms that must adapt to survive. In their 2013 book, *Reinventing Giants*, Bill Fischer, Umberto Lago, and Fang Liu noted that the Chinese home appliances company Haier had reinvented itself at least three times in the past 30 years. In contrast, Kodak, a US giant of the 20th century, was slow to react to the rise of digital photography, and went bankrupt.

Moreover, just as the enterprise must adapt, so too must the owner. Most businesses start small, and remain small. Few entrepreneurs are willing or know how to take the second step of employing people who are neither family nor previously known friends. This is the start of a move from entrepreneur to leader, and it requires a new set of skills, as new demands are placed on the business founders. Where once energy, ideas, and passion were enough, evolving businesses require the development of formal systems, procedures, and processes. In short, they require management. Founders must develop delegation, communication, and coordination skills, or they must employ people who have them.

As Larry Greiner described in his 1972 paper, "Evolution and Revolution as Organizations Grow", as a business grows, the demands on it change. The Greiner Curve is a graphic that shows how the initial stages of growth rely on individual initiative, and that evolving ad-hoc business practice into sustainable and successful growth can only be achieved by experienced people and rigorous systems. Professional management, as opposed to entrepreneurial spirit, becomes essential to business evolution.

Some leaders, such as Bill Gates and Steve Jobs, for example, are able to make the transition from entrepreneurial founder to corporate leader. Many others, however, struggle to make the necessary changes; some try and fail, while others decide to remain small.

Finding a balance

Determining how fast to grow is, therefore, a balance of the founder's skills and desires. But in order to survive, the idea must be unique enough to define its own niche, and the individual or group behind it must demonstrate entrepreneurial spirit. They need the flexibility to adapt the idea—and themselves—as business and market pressures demand. Luck will play a part, but it is the balance of these factors that determines whether a small start-up becomes a giant. ■

> When you have to prove the value of your ideas by persuading other people to pay for them, it clears out an awful lot of woolly thinking.
>
> **Tim O'Reilly**
>
> **Irish entrepreneur (1954–)**

IF YOU CAN DREAM IT, YOU CAN DO IT

BEATING THE ODDS AT START-UP

IN CONTEXT

FOCUS
Business start-ups

KEY DATES
18th century The term "entrepreneur" is used to describe someone who is willing to risk buying at certain prices and selling at uncertain prices.

1946 Professor Arthur Cole writes *An Approach to Entrepreneurship*, sparking interest in the phenomenon.

2005 The micro-finance, nonprofit site Kiva.com launches to make small loans to very small businesses.

2009 Crowdfunding websites, such as Kickstarter.com, allow individuals to provide funding for businesses.

2013 A study by Ross Levine and Yona Rubinstein finds that as teenagers, many successful entrepreneurs exhibited aggressive behavior, broke the rules, and got into trouble.



Beating the odds at start-up requires...

...a **good idea** allied to a **great business plan**.

...an **entrepreneurial spirit**: a willingness to take risks.

...**business acumen** to put the plan into action.

...**determination** to deal with setbacks.

The reasons for starting a business are many. Some people dream of being their own boss—of turning their hobby into a profitable enterprise, of expressing their creativity, or of being richly rewarded for their hard work. Although Walt Disney's maxim "if you can dream it, you can do it" holds true for some, pursuing the dream is risky. Those who attempt it must have the entrepreneurial spirit to fearlessly quit a well-paid job, go it alone, and face a future filled with uncertainty. Others might need a push; often being laid off (and its associated lump-sum payment) can be a springboard.

See also: Finding a profitable niche 22–23 ▪ Managing risk 40–41 ▪ Luck (and how to get lucky) 42 ▪ Take the second step 43 ▪ From entrepreneur to leader 46–47 ▪ Learning from failure 164–65 ▪ Small is beautiful 172–77

Younger entrepreneurs are increasingly a part of the start-up scenario. They may have gained the necessary skills for business by their early twenties, and enjoy the excitement and freedom of running their own venture.

Keeping the faith

While the reasons for start-up may vary, what all entrepreneurs have in common is the willingness to take risks. Few entrepreneurs get it right first time—it takes resilience and tenacity to keep going in the face of failure, and it takes perseverance to remain positive when customers, banks, and financial backers repeatedly say "no." Faith in the idea is essential. While some start-ups require very little capital, most require funding during their early growth phases. A business owner must be able to convince banks, or other financial backers, that their concept is valid and that they have the skills to turn the idea into a profitable venture, even though this may take some time. It took Amazon six years to make a profit.

In recent years, securing finance for start-ups has become a little easier. Many governments offer loan plans or grants. Entrepreneurs with big ideas can access large funds of money and managerial support from venture capitalists, whose sole purpose is to incubate start-ups. For smaller start-ups, and for people with very little of their own capital, micro-loans and crowdfunding finance—such as that offered by Kickstarter.com—are increasingly popular.

The business plan

The key to securing financing is a business plan. A good plan will outline the idea itself, detail any supporting market research, describe operational and marketing activities, and give financial predictions. The plan should also outline a strategy for long-term growth and identify contingencies (alternative ideas or markets) if things do not go as planned.

Most importantly, a good business plan will acknowledge that the biggest reason for business failure is a lack of cash. While loan capital can help for a while, eventually a business must fund its operations from revenue. A good business plan will analyze future cash flows and identify any potential shortfalls.

Beating the odds at start-up is defined by the tenacity to take an idea to market, the ability to secure sufficient finance, and the business acumen to turn a good plan into a long-term, profitable enterprise. ■

> “Sustaining a business is a hell of a lot of hard work, and staying hungry is half the battle.”
>
> **Wendy Tan White**
>
> **UK business executive (1970–)**

"Tony" Fernandes

Tan Sri Anthony "Tony" Fernandes was born in Kuala Lumpur in 1964 to an Indian father and Malaysian mother. He went to school in England and graduated from the London School of Economics (LSE) in 1987. He worked briefly for Richard Branson at Virgin Records as a financial controller before becoming Southeast Asia Vice President for Warner Music Group in 1992. In 2001, Fernandes left Warner to go it alone. He mortgaged his home to raise the finance needed to buy the struggling young airline, AirAsia. His low-cost strategy was clear in the company's tagline: "Now everyone can fly." One year after his takeover, the airline had cleared its debts of $11 million and had broken even. Fernandes estimates that around 50 percent of its travelers are first-time flyers. The company is now widely regarded as the world's best low-cost airline.

In 2007 Fernandes founded Tune Hotels, a low-cost hotel chain that promises "Five-star beds at one-star prices." He advises potential entrepreneurs to "dream the impossible. Never take no for an answer."



THERE'S A GAP IN THE MARKET, BUT IS THERE A MARKET IN THE GAP?

FINDING A PROFITABLE NICHE

IN CONTEXT

FOCUS
Positioning strategy

KEY DATES
1950s and 60s Markets are dominated by large companies offering mass-produced items, such as Coca-Cola. Choice is limited, but the scope for products targeted at new sectors of the market is high.

1970s and 80s Markets become more segmented as companys generate new products and market them toward narrower groups.

1990s and 2000s Companies and brands position themselves ever-more aggressively and distinctively in the overcrowded marketplace.

2010s Finding and sustaining market niches is assisted by the promotional capabilities of the Internet, which allow "one-to-one" marketing and customization of products.

Many markets are crowded, with multiple sellers chasing the same customers.

↓

For these sellers, **competition lowers profitability**.

↓

Market gaps—a new product or sector of the market—offer the enticing prospect of **healthy profitability**.

↓

But does the gap contain enough business to **generate a profit**?

↓

There's a gap in the market, but is there a market in the gap?

Finding a space in the market that is unchallenged by competition is the Holy Grail of positioning strategy. Unfortunately these spaces—known as market gaps—are often illusive, and the benefits of finding one are often equally illusory.

Although competition is a fact of life, it makes business difficult, contributing to an ever-downward pressure on prices, ever-rising costs (such as the funding of new product development and marketing), and an incessant need to outmaneuver and outsmart rivals. In contrast, the benefits of finding a market gap—a small niche segment of a market that is unfettered by competition—are obvious: greater control over prices, lower costs, and improved profits.

The identification of a market gap, combined with a dose of entrepreneurial spirit, is often all that is needed to launch a new business. In 2006, Twitter founder Jack Dorsey combined short-form communication with social media, providing a service that no one else had spotted. Free to most users, revenue comes from companies who pay for promotional tweets and profiles: Twitter earned advertising revenues of $582 million in 2013.

See also: Stand out in the market 28–31 ▪ Gaining an edge 32–39 ▪ Reinventing and adapting 52–57 ▪ Porter's generic strategies 178–83 ▪ Good and bad strategy 184–85 ▪ The value chain 216–17 ▪ Marketing mix 280–83

Not all gaps are lucrative, however. The Amphicar, for instance, was an amphibious car produced in the 1960s for US consumers who wanted to drive on roads and rivers. It was a quirky novelty, but the market was too small to be profitable. This was also true for bottled water for pets—launched in the US in 1994, Thirsty Cat! and Thirsty Dog! failed to entice pet owners.

A sustainable niche

Snapple, the manufacturer of healthy tea and juice drinks, is a company that has successfully found a sustainable and profitable niche. A glance at the beverage counter of any supermarket reveals that dozens of brands compete for sales. Many companies have failed in this ultra-competitive market: for example, Pepsi tried to capture a nonexistent market for morning cola with its short-lived, high-caffeine drink, AM.

Success for Snapple came from positioning the product as a unique brand—Snapple was one of the first companies to manufacture juices and drinks made completely from natural ingredients. Its founders ran a health store in Manhattan, and the company used the slogan: "100% Natural." Snapple targeted students, commuters, and lunch-time office workers with a new healthy "snack" drink, combining its Unique Selling Proposition (USP) with irreverent marketing and small bottles that were designed to be consumed in one sitting. Distribution was through small, inner-city stores where customers could "grab-and-go." These tactics helped to secure a profitable and sustainable niche, distinguishing Snapple from its rivals in the 1980s and 1990s. In 1994 sales peaked at $674 million.

Unoccupied market territory can present major opportunities for companies, but the challenge lies in identifying which gaps are profitable and which are traps. During the 1990s, many companies became excited about the potential of the "green" market, across a whole range of goods. But this market has failed to materialize in any profitable way. This marks one of the potential pitfalls in identifying market gaps based on market research: sometimes consumers have strong attitudes or opinions on trends or issues—such as ecology—that they are disinclined to consider when purchasing products, especially if they affect cost. Many market gaps, it seems, are tempting, but illusory. ■

Snapple's positioning in the crowded US beverage marketplace was the key to its success. By focusing on a niche healthy product and marketing itself as a quirky company, Snapple was able to wrestle a large market share (indicated here by circle size) from its rivals.



Snapple

A contraction of the words "snappy" and "apple," Snapple was launched in 1978 by Unadulterated Food Products Inc. The company was founded in 1972 by Arnold Greenberg, Leonard Marsh, and Hyman Golden in New York, US.

Such was the popularity of Snapple that the company has been subject to numerous buyouts. Unadulterated was purchased by Quaker Oats for $1.7 billion in 1994 but, following differences in strategic vision that led to falling sales, was sold to Triarc in 1997 for $300 million. Triarc then sold the Snapple brand to Cadbury Schweppes for $1.45 billion in September 2000, with a further deal in May 2008 seeing Snapple become part of what is now the Dr Pepper Snapple Group.

Marketed as "Made From the Best Stuff on Earth," Snapple's unusual blends of ready-to-drink teas, juice drinks, and waters are sold in more than 80 countries around the world.

YOU CAN LEARN ALL YOU NEED TO KNOW ABOUT THE COMPETITION'S OPERATION BY LOOKING IN HIS GARBAGE CANS

STUDY THE COMPETITION

IN CONTEXT

FOCUS
Analytical tools

KEY DATES

1950s Harvard academics George Smith and C. Roland Christensen develop tools to analyze companies and competition.

1960s US management consultant Albert Humphrey leads a research project that yields SOFT analysis, the forerunner to his later SWOT analysis.

1982 US professor Heinz Weihrich develops the TOWS matrix which uses the threats to a company as the starting point for formulating strategy.

2006 Japanese academics Shinno, Yoshioka, Marpaung, and Hachiga develop computer software that combines SWOT analysis with AHP (Analytic Hierarchy Process).

Whether a company is long established or in its start-up phase, a key strategic issue is its competitive advantage—the factor that gives it an edge over its competitors. The only way to establish, understand, and protect competitive advantage is to study the competition. Who is competing with the company for its customers' time and money? Do they sell competitive products or potential substitutes? What are their strengths and weaknesses? How are they perceived in the market?

For Ray Kroc, the US entrepreneur behind the success of fast-food chain McDonalds, this reportedly involved inspecting competitors'

See also: Stand out in the market 28–31 ▪ Gaining an edge 32–39 ▪ Thinking outside the box 88–89 ▪ Leading the market 166–69 ▪ Porter's generic strategies 178–83 ▪ The MABA matrix 192–93 ▪ Porter's five forces 212–15


SWOT analysis helps a company **analyze its position** by focusing on...
...key **internal factors**, such as:
...key **external factors**, such as:
Strengths (**S**).
Weaknesses (**W**).
Opportunities (**O**).
Threats (**T**).

trash. But there is a range of more conventional tools to help companies to understand themselves, their markets, and their competition.

SWOT analysis

The most popular such tool is SWOT analysis. Created by US management consultant Albert Humphrey in 1966, it is used to identify internal strengths (S) and weaknesses (W), and to analyze external opportunities (O) and threats (T). Internal factors that can be considered as either strengths or weaknesses include: the experience and expertise of management; the skill of a work force; product quality; the company's financial health; and the strength of its brand. External factors that might be opportunities or threats include market growth; new technologies; barriers to entering markets; overseas sales potential; and changing customer demographics and preferences.

SWOT analysis is widely used by businesses of all types, and it is a staple of business management courses. It is a creative tool that allows managers to assess a company's current position, and to imagine possible future positions.

A practical tool

When well-executed, a SWOT analysis should inform strategic planning and decision-making. It allows a company to identify what it does better than rivals (or vice versa), what changes it may need to make to minimize threats, and what opportunities may give the company competitive advantage. The key to strategic fit is to make sure that the company's internal and external environments match: its internal strengths must be aligned with the external opportunities. Any internal weaknesses should be addressed so as to minimize the extent of external threat.

When undertaking a SWOT analysis, the views of staff and even customers can be included—it should provide an opportunity to solicit views from all stakeholders. The greater the number of views included, the deeper the analysis and the more useful the findings. However, there are limitations. While a company may be able to judge its internal weaknesses and strengths accurately, projections about future events and trends (which will affect opportunities and threats) are always subject to error. Different stakeholders will also be privy to different levels of information about a company's activities, and therefore its current position. Balance is key; »

> “If you go exactly where your competitors are, you're dead.”
>
> **Thorsten Heins**
>
> **German-Canadian former CEO of Blackberry (1957–)**

senior managers may have a full view of the company, but their perspective needs to be informed by alternative views from all levels of the organization.

As with all business tools, the factor that governs the success of SWOT analysis is whether or not it leads to action. Even the most comprehensive analysis is useless unless its findings are translated into well-conceived plans, new processes, and better performance.

Market mapping

A slightly narrower but more sophisticated tool for analyzing a company's position and competition is "market mapping" (also known as "perceptual mapping"). Market maps are diagrams that represent a market and the placement of products within that market, providing a visual means of studying the competition. The process is useful both internally (to help an organization understand its own products) and externally (to chart how consumers perceive the brand in relation to the competition).

To draw up a market map, a company identifies several consumer purchase-decision factors that stand in opposition to one another. In the fashion market, an example might include "technology" *vs.* "fashion," and "performance" *vs.* "leisure." Additional factors could include the item's price (high *vs.* low), quality of production (high *vs.* low), stylish *vs.* conservative, or durable *vs.* disposable. Two of these dimensions, or opposing pairs, are then plotted onto a horizontal or vertical axis.

Based on market research or the knowledge of managers, all of the products within a particular market can be plotted onto the map. The market share of each product can be represented by the size of its corresponding image on the map, but more often, analysts choose to simply make a rough sketch of the market, ignoring market size.

A company may choose to compile several market maps, each of which depicts a different set of variables, and then analyze them—individually and in combination—to gain an overall view of the company's position in the market.

Market mapping plots opposing qualities of products along two axes. By identifying the two main oppositional factors for any product, it is easy to see gaps in the market.



Finding the gap

The goal of market mapping is to identify opportunities where a company can differentiate itself from its competitors. These are areas where the company offers unique value, and they can be used to inform marketing messages. The map will also reveal overcrowded segments, which signify heightened competitive threat.

For a new start-up, a market map can be used to identify a viable gap in the market—a good place to position a company when it is struggling to establish itself. Established businesses can use market mapping combined with SWOT analysis to discover opportunities and decide whether the company has the strengths to exploit one of those opportunities. The market map helps to inform the strategy (the need to reposition a product away from competitors'

The apparel market is a competitive sector with a host of finely delineated fashion brands. Speedo's market positioning is built around producing high-performance, technical products.

offerings, for example) and the tactics (moving from conservative to sporty, for example) that will help the company to achieve that strategic goal.

Market analysis such as this may, for example, have helped luxury Singaporean tea shop TWG Tea to identify an opportunity in the market. Launched in 2008, TWG targets a slightly older, wealthier customer base than coffee shops and other "lifestyle" cafés. TWG has opened new locations across the world, based on studying the competition, identifying a market gap, and designing its products and services to fill that gap.

Internal focus

As a company grows it might choose to draw up a map including just its own products. Analysis of the results can help identify any overlap between different products (informing decisions about which products to drop, and which to concentrate research and development and marketing spend, for example). It can also be used to ensure that the company's marketing message stays on track, helping to avoid strategic drift.

Perceived as a technical performance product, Speedo, for example, needs to ensure that its marketing reflects that view; a campaign that promotes Speedo as a fashionable label would risk confusing customers and could damage the brand.

The key to successful market mapping is market research. While it can be useful to compare internal and external perceptions of a product, and the products of the competition, it is the customers' views that matter most. When based on such data, even though managers may disagree, the market map cannot be "wrong"—it simply represents, for better or worse, how the brand is perceived. The challenge for management is to use the map, and knowledge of internal strengths and weaknesses, to plan the appropriate strategic response.

Both SWOT analysis and market mapping allow a company to better understand itself, its market, and, most importantly, the competition. Equally, being aware of weaknesses can help avoid costly strategic mistakes, such as producing overly ambitious products or making an entry into a crowded market position. An appreciation of the opportunities and threats of the market, and the relative and shifting positions of competing products, is essential to long-term successful strategic planning. To plan where you are going, it helps to know where you are—and where your competitors are too. ■

Albert Humphrey

Born in 1926, Albert Humphrey was educated at the University of Illinois, US, and at the Massachusetts Institute of Technology (MIT), where he gained a master's degree in Chemical Engineering. He later went on to earn an MBA from Harvard University. While working with the Stanford Research Institute (now SRI International) between 1960 and 1970, Humphrey came up with the Stakeholder Concept, which has since been used by business leaders and politicians. He also undertook research to identify why corporate planning failed, by holding interviews with more than 5,000 executives at over 1,100 companies. As a result of the findings, he invented SOFT analysis: "what is good in the present is Satisfactory, good in the future is an Opportunity; bad in the present is a Fault, and bad in the future is a Threat." Fault was later softened to the more acceptable Weaknesses, and Satisfactory became Strengths. The now-ubiquitous acronym SWOT was born.

THE SECRET OF BUSINESS IS TO KNOW SOMETHING THAT NOBODY ELSE KNOWS

STAND OUT IN THE MARKET

IN CONTEXT

FOCUS
Differentiation

KEY DATES

1933 US economist Edward Chamberlin's *Theory of Monopolistic Competition* describes differentiation as a means for a company to charge more for its products or services by distinguishing them from the competition.

1940s The concept of the Unique Selling Proposition (USP) is put forward by Rosser Reeves, advertising executive at New York advertising agency Ted Bates, Inc.

2003 US marketing professor Philip Kotler outlines the need for USPs to be superseded by Emotional Selling Propositions (ESPs) in his book *Marketing Insights from A to Z.*

Few businesses enjoy the privileges of monopoly power in their chosen fields of operation. Most markets are increasingly global, increasingly crowded and, therefore, increasingly competitive. In order to achieve commercial success companies need to do something different—as Greek shipping magnate Aristotle Onassis recommended, they need to "know something that nobody else knows" in order to stand out from the competition.

Unique Selling Propositions

Faced with competition, the strategy for most companies is to differentiate. This involves offering

See also: Finding a profitable niche 22–23 ▪ Gaining an edge 32–39 ▪ Reinventing and adapting 52–57 ▪ Porter's generic strategies 178–83 ▪ Good and bad strategy 184–85 ▪ The value chain 216–17


Few companies enjoy the **monopoly privileges** afforded by market gaps.
To achieve success, especially in its early stages of growth, a company must **stand out**...
...which requires differentiation in **product, service, process, or marketing**.
But **difference can be easily copied** by competitors.
Enduring difference can only be maintained through a **Unique Selling Proposition**.
Only then will companies truly **stand out in the market**.

customers something that the competition cannot or does not offer—a Unique Selling Proposition (USP). The concept was developed by US advertising executive Rosser Reeves in the 1940s to represent the key point of dramatic difference that makes a product salable at a price higher than rival products. Tangible USPs are hard to acquire and hard to copy, which is what makes them unique.

Companies must distinguish their product or service from the competition at every stage of production—from raw material extraction to after-sales service. Products such as Nespresso coffee-makers and Crocs footwear, and service providers such as majority Asian-owned hotel group Tune Hotels, are all heavily differentiated, each having a strong USP.

The primary benefit of uniqueness, however it is achieved, is greater customer loyalty and increased flexibility in pricing. Differentiation guards products and services from low-priced competition; it justifies higher prices and protects profitability; and it can give businesses the competitive advantage needed to stand out in the market.

The challenge of difference

By definition, not all products can be unique. Differentiation is costly, time consuming, and difficult to achieve, and functional differences are quickly copied—"me-too" strategies are commonplace. Touchscreen technology was introduced to the cell-phone market as a point of differentiation for Apple's iPhone, but is now a feature of most smartphones. Differentiation often does not remain a point of difference for long.

With functional uniqueness being so elusive, marketing guru Philip Kotler suggested that companies focus instead on an Emotional Selling Proposition (ESP). In other words, that the task of marketing is to generate an emotional connection to the brand that is so strong that customers perceive difference from the competition. For example, while the design and functionality of Nike and Adidas sneakers are distinct, the differences are so small that they amount to only a marginal difference in performance. The products' differences are, however, magnified in the perception of the consumer through marketing and the power of branding—uniqueness is achieved through brand imagery, promotion, and sponsorship.

Apple achieved differentiation in the fledgling digital-music market by combining easy-to-use software »

> There is no such thing as a commodity. All goods and services are differentiable.
>
> **Theodore Levitt**
>
> **US economist (1925–2006)**

with well-designed hardware and a user interface that integrated the two. The product itself—the iPod portable music device—was functionally little different than existing MP3 players, but combined with the iTunes software to create a unique customer experience. This experience is Apple's ESP, which the company promoted with its "Think Different" advertising campaign.

Standing out

One company that has achieved uniqueness is the British fashion label Superdry, which has grown to include more than 300 stores in Europe, Asia, North and South America, and South Africa. Drawing a novel, international influence from Japanese graphics and vintage Americana, combined with the values of British tailoring, Superdry quickly established a strong position in the hypercompetitive clothing market from its launch in 2004. The business started life in university towns across the UK, a positioning that gave the brand a youthful appeal. Despite limited advertising and abstaining from celebrity endorsements, Superdry's popularity rapidly grew. The company's distinctive look quickly caught the eye of celebrities (a jacket worn by soccer player David Beckham became one of its best-selling products, and Beckham himself became an unoffical talisman of the brand), providing free publicity.

Superdry focused on offering clothing with a fashionably tailored fit and attention to detail (even down to garment stitching). Worn by off-duty office workers, students, sports stars, and celebrities alike, the brand was able to appeal to a broad customer base. Most differentiation strategies involve targeting one segment of the market; Superdry chose to target them all. The brand's unique blend of fashion with ease of wear, comfort with style, and the presence of mysterious but meaningless Japanese writing, has proved a difficult mix for competitors to replicate.

Maintaining uniqueness

As many companies discover, popularity can be the enemy of difference. While Superdry clothing has become increasingly ubiquitous around the world, its uniqueness and difference have declined. The challenge for Superdry, like all companies, is to protect its uniqueness while also expanding its reach—to stand out from the crowd, while welcoming those crowds into its stores.

Differentiation can occur at any point in the value chain. Standing out is not limited to products or services—it can occur in any number of internal processes that translate into an improved customer experience. Swedish furniture retailer IKEA, for example, differentiates itself not only through contemporary design and low prices, but through the entire customer retail experience. The company's low prices are achieved, in part, through its self-picking and self-assembly retail model—the customer experience involves picking products from the company's vast showrooms and warehouses and then, once they have transported the goods home, assembling the furniture.

Even the way IKEA "guides" shoppers on a one-way, defined route through its showrooms is unique. While this tactic encourages spontaneous purchases, it also helps to reinforce IKEA's points of difference—customers are exposed to predesigned rooms and furniture layouts that emphasize the brand's contemporary style. Price is kept low since fewer store assistants are required to direct customers around the store.

Different but the same

Paradoxically, familiarity can also be a source of differentiation. The entire McDonald's organization revolves around providing almost identical fast-food products, with the same service, in identical

Fashion label Superdry is a young company that has successfully carved out market share. Rapid growth since its founding in 2004 is thanks in part to a highly differentiated, faux-vintage look.


✓ High sales
✗ Low sales
? High scope for differentiation
What your company does well
What the consumer wants
What your competitors do well
✓
✗
?
✗

Differentiation is not so important when a company's products match the desires of the customer and do not overlap with the competition. Although the risks might be high, differentiation is most effective when your products are popular, but overlap with those of the competition.

restaurants the world over. This familiarity differentiates McDonald's from unknown local offerings, and from other global competitors who cannot maintain the same degree of consistency across their operating territories.

In a market in which rival companies promote the uniqueness of their products in ever-louder and more complex ways, consumers have become increasingly savvy when it comes to distinguishing reality from rhetoric. While differences do not have to be tangible—the evidence shows that an Emotional Selling Proposition (ESP) is often enough—the challenge for businesses is that points of differentiation do have to be genuine and believable. Developing an emotional connection with the customer requires that the differentiation is understood and consistently delivered throughout the organization. Well-defined core principles that celebrate a company's uniqueness should inform the customer experience at every point of contact—difference has to be believable, and it is only believable if it is dependable.

Sustaining differentiation

Once established, uniqueness—whether functional or emotional—requires nurturing and protecting. Standing out from the crowd is a constant battle that is fought in the hearts and minds of the company's staff, as well as customers. As legal clashes between rivals—such as Apple and Samsung—demonstrate, uniqueness might also have to be contested in the courtroom.

Every industry has leaders and followers—what separates them is that the leaders are usually those with the most defensible points of differentiation. Whether in features and functionality, brand image, service, process, speed, or convenience, uniqueness must be established and communicated for a company and its offerings to stand out in the market. The key to long-lasting success is making that differentiation sustainable. ■

Rosser Reeves

US advertising executive Rosser Reeves (1910–84) held the maxim that an advertisement should show off the value of a product, not the cleverness of the copywriter. After a brief spell at the University of Virginia, from where he was expelled for drunken misconduct, Reeves worked as a journalist and then copywriter before joining advertising agency Ted Bates, Inc. in New York in 1940. His exceptional talent saw him rise to become Chairman of the company in 1955. He is credited with redefining television advertising and, among many others, for formulating slogans such as "It melts in your mouth, not in your hand" for chocolate confectionary brand M&Ms. Reeves's Unique Selling Proposition, first outlined in the 1940s, was described in his 1961 book *Reality of Advertising*. Such was his impact on the advertising industry that his legacy lives on long after his death—his pioneering style of leadership was the inspiration for the lead character in US television series *Mad Men*.

> “In order to be irreplaceable one must always be different.”
>
> **Coco Chanel**
>
> **French fashion designer** (1881–1971)

BE FIRST OR BE BETTER

GAINING AN EDGE

IN CONTEXT

FOCUS
Competitive advantage

KEY DATES

1988 US scholars David Montgomery and Marvin Lieberman write "First-Mover Advantage," outlining the competitive advantages of being first to market.

1995 Amazon.com launches, the first of a new breed of online retailers.

1997–2000 Adopting the "be first" mantra, dot-com companies race to market; many fail when the promised advantages do not materialize.

1998 Montgomery and Lieberman question their original findings in their paper, "First-Mover (Dis)Advantages."

2001 Amazon.com returns its first profit. The company's first-mover advantages were significant, but a good business model mattered more.

First-movers have no competition and have the potential to **become market leaders**...

...but **unless the market is static**, and technological innovation is limited, **the risk of failure is high**.

Later entrants enter a recognized market and **know what mistakes to avoid**.

They stand to benefit most in a **rapidly changing market**, in which **technological innovation** is advanced.

In order to gain an edge, either be first, or be better.

If you need to buy a book online, which website do you visit first? If you want to research the author of the book, which search engine do you use? The answers, most probably, are Amazon and Google, respectively. Such is the dominance of these two Internet giants that their names define their respective markets.

Both organizations have a significant edge in the markets they lead, but they achieved that dominance by different means. Amazon, launched in 1995, gained its advantage by being the first business to enter the online retail market, establishing its brand name, and building a loyal customer base. Google, by contrast, was by no means first. When Google launched in 1998, the market was already dominated by several large players; Google's edge came from offering a superior product—not only was it faster, but it produced more accurate search results than any of its competitors.

Getting into a market first has significant advantages, but there are also benefits to being second. The key is that in order to gain a competitive edge in the market, a business needs either to be first, or it needs to be better.

Market pioneers

The benefits of being first into a market are known as "first-mover advantage," a term popularized in 1988 by Stanford Business School professor David Montgomery and his co-author, Marvin Lieberman. Although introduced a decade previously, Montgomery and Lieberman's idea took particular hold during the dot-com bubble between 1997 and 2000. Spurred

See also: Beating the odds at start-up 20–21 ▪ Stand out in the market 28–31 ▪ How fast to grow 44–45 ▪ The Greiner curve 58–61 ▪ Creativity and invention 72–73 ▪ Changing the game 92–99 ▪ Balancing long- versus short-termism 190–91

Rate this packaging: www.amazon.co.uk/packaging
amazon.co.uk
amazon.de
ama

Amazon.com was a first-mover in the online retail market. It has dominated the industry since its launch in 1995, creating strong brand recognition and a loyal customer base.

on by the example of Amazon, businesses spent millions pitching themselves headlong into new online markets. Conventional wisdom was that being first ensured that the company's brand name became synonymous with that segment, and that early market dominance would create barriers to entry for subsequent competition.

In the end, however, overspending, overhype, and overreaching into markets where little demand existed was the downfall of many fledgling dot-coms. With notable exceptions, businesses found that promised returns were not being realized and funds quickly ran short—and for many of these first-movers, failure followed.

First-mover advantage

Being first out of the block undoubtedly has its advantages, and in the case of the dot-coms, those advantages were exaggerated to the extreme. First-movers often enjoy premium prices, capture significant market share, and have a brand name strongly linked to the market itself. First-movers also have more time than later entrants to perfect processes and systems, and to accumulate market knowledge. They can also secure advantageous physical locations (a prime location on a main street of a city, for example), secure the employment of talented staff, or access beneficial terms with key suppliers (who may also be eager to enter the new market). Additionally, first-movers may be able to build switching costs into their product, making it expensive or inconvenient for customers to switch to a rival offering once an initial purchase has been made. Gillette, for example, having invented the safety razor in 1901, has consistently leveraged its first-mover advantage to create new products, such as a "shaving system" that combines cheap handles with expensive razor blades.

> “First-mover advantages accrue when a company gains a first-mover opportunity (through proficiency or luck) and is able to maintain an edge despite subsequent entry.”
> **David Montgomery and Marvin Lieberman**

Market strategies

In the case of Amazon.com, first-mover advantage consisted of a combination of factors. In the newly emerging e-commerce market, customers were eager to try online purchasing, and Amazon was well placed to exploit this growing curiosity. Books represented a small and safe initial purchase, and Amazon's simple web design made buying easy and enjoyable. Early sales enabled the organization to adapt and perfect its systems, and to adjust its website to match customer needs—adding, for example, its OneClick ordering system to enable purchases without entering payment details.

Amazon was also able to build distribution systems that ensured quick and reliable delivery of its products. Although competitors could replicate these systems, customers already trusted Amazon, and the brand loyalty »



That delightful feeling of freshness after a *comfortable* shave is enjoyed by the multitude of New Improved Gillette users—men critical of razor service who demand the utmost in shaving results.

The price is $5 and up

"Three Reasons" is the title of a convincing booklet sent upon request

The New Improved

Gillette

SAFETY Gillette RAZOR

GILLETTE SAFETY RAZOR CO., BOSTON, U. S. A.

Gillette invented the safety razor in 1901 and later consolidated its first-mover advantage by developing a "shaving system" that made it difficult for customers to switch brands.

the organization enjoyed created significant emotional switching costs; even today, Amazon enjoys the benefits of this trust and loyalty, and almost a third of all US book sales are made via Amazon.com.

A recent example of how important first-mover advantage remains are the "patent wars" contested between most of the leading smartphone makers (including Apple, Samsung, and HTC). Patents help a company to defend technological advantage. In the hypercompetitive smartphone industry, being first to market with a new technological feature offers critical, albeit short-term, advantage. In an industry in which consumers' switching costs are high, even short-term advantages can have a significant impact on revenue.

Since the publication of Montgomery and Lieberman's original paper in 1988, academic research has indicated that significant advantages accrue to market pioneers, which can be directly attributable to the timing of entry. The irony is that in a retrospective paper that appeared in 1998, "First-Mover (Dis) Advantages," Montgomery and Lieberman themselves backed off their original claims concerning the benefits of being the first to enter a market.

Building on the work of, among others, US academics Peter Golder and Gerard Tellis in 1993, Montgomery and Lieberman's 1998 paper questioned the entire notion of first-mover advantage. In their research, Golder and Tellis had found that almost half the first-movers in their sample of 500 brands, in 50 product categories, failed. Moreover, they found that there were few cases where later entrants had not become profitable or even dominant players—in fact, their research identified that the failure rate for first-movers was 47 percent, compared to only 8 percent for fast followers.

Learning from mistakes

The challenge for first-movers is that the market is often unproven; industry pioneers leap into the dark without fully understanding customer needs or market dynamics. First-movers often launch untried products onto unsuspecting customers; and it is rare that they get it right first time. Large companies may be able to take the losses of such early-market entry mistakes; small companies, on the other hand, may soon find that their cash is running out and their tenuous business models are collapsing.

Later entrants have the advantage of learning from the mistakes of the first-movers, and from entering a proven market. They are also able to avoid costly investment in risky and potentially flawed processes or technologies; first-movers, by contrast, may have accrued significant "sunk costs" (past investment) in old, less-efficient technologies, and may be less able to adapt as the industry matures. Followers can enter at the point at which technology and processes are relatively well established, with both cost and risks being lower.

Followers may have to fight to overcome the first-movers' brand loyalty, but simply offering a superior product that better addresses customer needs is often sufficient to secure a market. Brand recognition is one thing, but technical and product superiority can give that all-important competitive edge. Moreover, with investment costs being much lower, followers often have surplus cash to use on marketing, thereby offsetting the branding advantages of the first-mover.

When Google, for example, entered the Internet search business in 1998, the market was dominated by the likes of Yahoo, Lycos, and AltaVista, all of whom had established customer bases and brand recognition. However, Google was able to learn from the

> “Good artists copy;
> great artists steal.”
> **Steve Jobs**
> **US former CEO of Apple** (1955–2011)

> If later entrants can leapfrog pioneers, companies could be better off entering late.
> **Peter Golder and Gerard Tellis**

mistakes of these earlier entrants and, quite simply, build a better product. The organization realized that with so much information on the Internet people wanted search results that were comprehensive and relevant; the various market incumbents offered a variety of systems for filtering search results, but Google was able to take the best of these systems and build its own unique algorithm that led to market dominance.

First-mover failures

There are numerous examples in corporate history of first-movers that were unable to achieve or maintain a competitive advantage. Famous failures in the online sphere include Friends Reunited and MySpace. Although both companies still exist, their first-mover advantage was not sufficient to offset the might (and product superiority) of Facebook. Similarly, eToys.com, launched in 1999, was one of a new breed of online retailers, but first-mover advantage was not enough to sustain the business and the company declared bankruptcy in 2001—by coincidence, the same year that Amazon started to sell toys. (Resurrected some years later, etoys.com is now owned by Toys R Us.) The online clothing retailer boo.com is an example of a first-mover that had technological superiority, but was ahead of its time—the site was too resource-heavy for most consumers' slow Internet connections. Launched in 1999, boo.com went into receivership the following year—being first is not a guarantee of success if the basic business model is flawed.

Despite the evidence presented by Golder and Tellis, and examples such as Google, it remains the case that first-mover advantage has captured corporate imagination. Mirroring the earlier dot-com gold rush, the recent boom in the market for web-based smartphone- and tablet-accessed applications (the "app" market) is fueled by a desire to be first. Thousands of apps have launched in the hope of staking their claims on lucrative segments of this new market. But success is not guaranteed—a 2012 study revealed that on average, 65 percent of users delete apps within 90 days of installing them.

Timing is everything

The reason a first-mover does not always yield its promised advantages is that much depends on timing, and therefore luck. In their 2005 paper, "The Half-Truth of First-Mover Advantage," US business scholars Fernando Suarez and Gianvito Lanzolla identified technological innovation and the speed at which the market is developing as crucial in determining whether or not being a first-mover is advantageous.

Their findings suggest that when a market is slow-moving and technological evolution is limited, first-mover advantage can be »



Launched just two years later, Commodore's "fast-follower" GUI computer yielded a shareholder return of 80 percent.

Apple's pioneering GUI computer was a commercial failure, with a shareholder return of -61 percent.

Being the first-mover in a new, untried market does not always result in success. Apple's Lisa was the first computer with a Graphical User Interface (GUI)—a version of which now forms the user interface of every computer, smartphone, and digital device—yet sales were far exceeded by later offerings from Commodore, IBM, and HP.

significant. They give the example of the market for vacuum cleaners, and, in particular, of the long-term market leader, Hoover. Until the relatively recent introduction of Dyson cleaners, the market was benign and technological advancement slow. Having been first to market in 1908, Hoover enjoyed several decades of advantage—an advantage that was (and, in some places, still is) reflected in the widespread use of the company's brand name as the verb "to hoover."

In other industries, however, where technological change or market evolution is rapid, first-movers are often at a disadvantage. The first search engines are examples of businesses that had too much invested in early iterations of a technology to keep up with the rapid pace of change.

Early advantage quickly becomes obsolete in changeable markets. As the market evolves, later entrants are those that seem to be cutting edge, offering innovative features that build on the market-knowledge as well as learning from the mistakes of the first-mover. The first-mover may have enjoyed short-lived advantage but in dynamic markets such an advantage is rarely durable. Even Apple, who enjoyed significant early-entrant advantage in the smartphone market with the iPhone, is not immune from first-mover disadvantage. Competitors, Samsung in particular, were able to listen to customer complaints about iPhones, analyze customer needs, and produce products with features and functionality welcomed by the market. Apple, locked into previous technology iterations, took time to react and iPhone sales suffered as a result.

Customer needs

To gain an edge, therefore, you do not always need to be first. Indeed, US multinational Procter & Gamble, for example, prefers only to enter those markets in which it can establish a strong number one or number two position over the long-term—rarely is this achieved in a blind rush to be first.

Procter & Gamble seeks markets that are demographically and structurally attractive, with lower capital requirements, and higher margins. But most importantly, the organization insists on a deep understanding of customer needs in any market they enter. In other words, they would rather enter mature markets than be first into new ones.

> If you do things well,
> do them better.
> **Anita Roddick**
> **UK entrepreneur (1942–2007)**

The company values long-term relationships with its customers and suppliers; its view of innovation is different from small companies who, in attempting to capture market share, strive to gain an edge through the introduction of disruptive technology—innovative technology that seeks to destabilize the existing market. Procter & Gamble, perhaps heeding the research, considers such strategies to be short-lived. They realize that overly rapid innovation runs the risk of cannibalizing their own sales and reducing the returns on new product investment. In the market for disposable baby diapers, for example, Procter & Gamble was more than ten years behind the first mover. The company's now famous Pampers brand was launched in 1961, following some way behind Johnson & Johnson's Chux brand,

The PalmPilot, launched in 1997, was a successful fast-follower product. It followed Apple's unsuccessful Newton, which was the first personal digital assistant (PDA) to enter the market.

which was launched in 1949. At the time, disposable diapers were a new innovation, and customers were wary of their use. Procter & Gamble waited until customers had come to accept the product before entering the market. Moreover, they spent nearly five years researching and addressing each of the major problems with Chux and developed a product that was more absorbent, had lower leakage, was more comfortable for the baby, offered two sizes, and could be produced at a significantly lower cost. Today, *Forbes* magazine lists Pampers as one of the world's most powerful brands, valued at over $8.5 billion, with the diapers being purchased by 25 million consumers in over 100 countries. By contrast, Chux was phased out by Johnson & Johnson in the 1970s due to shrinking sales.

Securing a foothold

In reality, then, while it is readily assumed that speed is good when entering a market, gaining an edge might depend less on timing than it does on appropriateness. Whether a company is first, second, or last to market is important; but it is less important than the suitability of a company's products or services to that market, and its ability to deliver on brand promises. Both these factors can have a profound impact on long-term viability and business success.

Amazon may have enjoyed lasting first-mover advantage, but that alone is insufficient to account for its phenomenal success. Amazon leverages its first-mover advantage into a sustainable competitive edge; its website is continually made easier to use, it offers a range of complimentary products, and it continues to drive down costs, enabling it to offer market-beating prices. Most notably, Amazon did not return a profit until 2001—the company spent its earlier years building a better product. The foundations of success may have been laid by first-mover advantage, but Amazon's edge has been built on long-term good business practice.

First-movers undoubtedly have a natural competitive edge. Whether it is a lasting impression on customers, strong brand recognition, high switching costs, control of scarce resources, or the advantages of experience, that edge can help to secure a strong, and long-term, foothold in the market. But as research shows, second-movers, and their followers, may sometimes be in an advantageous position. Learning from the mistakes of early entrants, they frequently offer superior products at lower prices. With the aid of skillful marketing, these benefits can be leveraged to offset the advantages enjoyed by first-movers. To become a market leader, a business needs either to be first, and impressive, or it needs to be better. The companies we remember, the Amazons and the Googles, are those that were either first or better—the ones we forget are those that had no edge at all. ■

> To suffer the penalty of too much haste, which is too little speed.
>
> **Plato**
>
> **Greek philosopher (429–347 BCE)**

Jeff Bezos



Born on January 12, 1964 in Albuquerque, New Mexico, US, Jeff Bezos had an early love of science and computers. He studied computer science and electrical engineering at Princeton University, and graduated *summa cum laude* in 1986.

Bezos started his career on Wall Street, and by 1990 had become the youngest senior vice-president at the investment company D. E. Shaw. Four years later, in 1994, he quit his lucrative job to open Amazon.com, the online book retailer—he was barely 30 years old at the time.

As with many Internet start-ups, Bezos, with just a handful of employees, created the new business in his garage; but as operations grew, they moved into a small house. The Amazon.com site was launched officially on July 16, 1995. Amazon became a public limited company in 1997; the company's first year of profit was 2001. Today, Bezos is listed by *Forbes* magazine as one of the wealthiest people in the US; and Amazon stands as one of the biggest global success stories in the history of the Internet.

PUT ALL YOUR EGGS IN ONE BASKET, AND THEN WATCH THAT BASKET

MANAGING RISK

IN CONTEXT

FOCUS
Risk management

KEY DATES
1932 The American Risk and Insurance Association is established.

1963 Robert Mehr and Bob Hedges publish *Risk Management in the Business Enterprise*, claiming that the objective of risk management is to maximize a company's productive efficiency.

1970s Inflation and changes to the international monetary system (the ending of the Bretton Woods agreement) increase commercial risks.

1987 Merrill Lynch becomes the first bank to open a risk-management department.

2011 The US Financial Crisis Inquiry Commission says that the 2008 financial crisis was caused partly by financial companies "taking on too much risk."

Entrepreneurs are defined by their willingness to bear risk—particularly the risk of business failure. This is especially true for those starting new companies, because more than half of start-ups fail within the first five years. Lesser risks in established businesses include the possible failure of new products, or damage to the brand or a manager's reputation. Whatever the level or type, however, risk is something that all businesses need to be aware of and manage carefully. US businessman Andrew Carnegie was pondering these issues when he suggested that in terms of


Risk is an **inevitable part** of business.
But it **can be quantified** and action taken...
...through **oversight and good management**.
Part of this process involves deciding **what level of risk is "acceptable"**...
...and **where to place the risk**—on all the "eggs in the basket," or just one?
Managing risk is a **strategic process**, balancing cost against reward.

See also: How fast to grow 44–45 ▪ Hubris and nemesis 100–103 ▪ Who bears the risk? 138–45 ▪ Leverage and excess risk 150–51 ▪ Off-balance-sheet risk 154 ▪ Avoiding complacency 194–201 ▪ Contingency planning 210 ▪ Scenario planning 211

managing risk, it might be best to put all your eggs in one basket, then watch that basket.

From the collapse of Lehman Brothers (2008), to BP's Deepwater Horizon disaster (2010), events of the early 21st century fundamentally changed how organizations perceive risk. Companies now think in terms of two factors: oversight and management. "Risk oversight" is how a company's owners govern the processes for identifying, prioritizing, and managing critical risks, and for ensuring that these processes are continually reviewed. "Risk management" refers to the detailed procedures and policies for avoiding or reducing risks.

Inherent risks

Risk is inherent in all business activity. Start-ups, for example, face the risk of too few customers, and therefore insufficient revenue to cover costs. There is also the risk that a competitor will copy the company's idea, and perhaps offer a better alternative. When a company has borrowed money from a bank there is a risk that interest rates will rise, and repayments will become too burdensome to afford. Start-ups that rely on overseas trade are also exposed to exchange-rate risk.

Moreover, new businesses in particular may be exposed to the risk of operating in only one market. Whereas large companies often diversify their operations to spread risk, the success of small companies is often linked to the success of one idea (the original genesis for the start-up) or one geographic region, such as the local area. A decline in that market or area can lead to failure. It is essential that new businesses are mindful of market changes, and position themselves to adapt to those changes.

The Instagram image-sharing social-media application, for example, started life as a location-based service called Burbn. Faced with competition, the business changed track into image-sharing. Had Instagram not reacted to the risks, and been savvy enough to diversify its offering (regularly adding new features), it may not have survived.

> It's impossible that the improbable will never happen.
> **Emil Gumbel**
> **German statistician (1891–1966)**

At its heart, risk is a strategic issue. Business owners must carefully weigh the operational risk of start-up, or the risks of a new product or new project, against potential profits or losses—in other words, the strategic consequences of action *vs.* inaction. Risk must be quantified and managed; and it poses a constant strategic challenge. Fortune favors the brave, but with people's lives and the success of the business at stake, caution cannot simply be thrown to the wind. ■

BP's Deepwater Horizon incident led to huge fines and US government monitoring of its safety practices and ethics for four years.

In deep water

Even large and diverse organizations can find it hard to successfully balance risk against potential financial reward. On April 20, 2010, Deepwater Horizon, an offshore oil rig chartered by British Petroleum (BP), exploded, killing 11 workers and spilling tens of thousands of barrels of crude oil into the Gulf of Mexico.

The incident was blamed on management failure to adequately quantify and manage risk; the official hearing cited a culture of "every dollar counts." Analysts who examined the disaster claimed that BP had prioritized financial return over operational risk. Chief executive Tony Hayward, who took the post in 2007, had suggested that the organization's poor performance at the time was due to excessive caution. Coupled with increasing pressure from shareholders for better returns, the bullish approach that followed led to significant cost cutting and, eventually, risk-management failures.

LUCK IS A DIVIDEND OF SWEAT. THE MORE YOU SWEAT, THE LUCKIER YOU GET

LUCK (AND HOW TO GET LUCKY)

IN CONTEXT

FOCUS
Maximizing opportunity

KEY DATES

1974 3M employee Art Fry uses the adhesive developed—and rejected as defective—by a colleague six years earlier to attach a bookmark in his hymnbook. This chance usage leads to the Post-it Note.

2009 A *Harvard Business Review* article "Are 'Great' Companies Just Lucky?" reports that in only half of the 287 high-performing companies surveyed could success be attributed to distinguishable practices or features of the organizations themselves.

2013 Five years' hard work yields music group Daft Punk's aptly titled song "Get Lucky". A result of industry collaboration, market research, and strong marketing and publicity, the song's commercial success demonstrates the value of business planning.

Luck is usually regarded as something over which businesses have no control. Yet, as McDonald's CEO Ray Kroc said, "the more you sweat, the luckier you get," suggesting that luck can be created. The reality is that both are true. As global markets become more volatile and less predictable, luck plays an inevitable part in business success. Launch a start-up at the same time as a rival and it may be luck that determines who succeeds, and who fails.

Making your own luck

A well-considered business plan is designed to dispense with reliance on luck. A good idea, underpinned by detailed market research and solid financial planning, may help a start-up to ride the whims of the market. A good plan charts a course of action in turbulent markets, protects against the unknown, and prepares the company for contingencies.

In addition, a well-conceived plan can ensure that a company is in a position to benefit from favorable market conditions. In other words, what might seem like luck is often the result of planning. Take the famous example of 3M Post-it Notes. The invention of a reusable glue was accidental, but it was business insight that turned the lucky discovery into a commercial success.

With so many variables, luck is likely to play a part in the survival of a start-up. But a good plan reduces how much luck a company needs. ■

> “The first rule of luck in business is that you should persevere in doing the right thing. Opportunities will come your way if you do.”
> **Ronald Cohen**
> **UK venture capitalist** (1945–)

See also: Beating the odds at start-up 20–21 ▪ Gaining an edge 32–39 ▪ Understanding the market 234–41 ▪ Forecasting 278–79

BROADEN YOUR VISION, AND MAINTAIN STABILITY WHILE ADVANCING FORWARD

TAKE THE SECOND STEP

IN CONTEXT

FOCUS
Expanding the business

KEY DATES
1800 French cotton manufacturer Jean-Baptiste Say popularizes the term “entrepreneur,” which is taken from the French for the verb “to undertake.”

1999 Chinese business magnate Li Ka-shing underlines the importance of vision for business growth, stating “Broaden your vision, and maintain stability whilst advancing forward.”

2011 *The Lean Startup* by US technology entrepreneur Eric Ries encourages new businesses to utilize resources as efficiently as possible to encourage growth.

2011 The number of active entrepreneurs in mature countries grows by about 20 percent, reflecting job losses due to the economic downturn.

The business landscape may appear to be dominated by corporate goliaths, but the reality is that small businesses outnumber large companies by a significant margin. In fact, most businesses never grow beyond the scope of the owner—they start small and stay small. In the US, more than 99 percent of companies employ fewer than 500 people. In 2012, there were almost 5 million small businesses (with fewer than 49 employees), but only 6,000 companies employing more than 250 people.

Aspiration, or its lack, is a key factor for small-scale companies. Many small-business owners are content with the lifestyle the business allows them, and have no desire for growth. But he biggest reason for a lack of growth is finance. Growth requires access to capital, which is difficult and expensive to access for small companies. Moreover, unlimited liability means that an owner’s personal assets (such as the family home) are at risk if the business fails—a risk that many are unwilling to take. Entrepreneurial spirit is defined as the willingness to take risks. Business owners who do aspire to growth must be willing to take the risky but important second step. For most small-business owners, this means employing the first nonfamily member and beginning to acquire the necessary leadership and management skills to scale the business and manage the people, systems, and processes. ■

Large businesses might appear to be towering oaks, but most have acornlike beginnings. A common difference between them and companies that stay small is the willingness to take risks.

See also: Beating the odds at start-up 20–21 ▪ Managing risk 40–41 ▪ The Greiner curve 58–61 ▪ Who bears the risk? 138–45 ▪ Small is beautiful 172–77



NOTHING GREAT IS CREATED SUDDENLY

HOW FAST TO GROW

IN CONTEXT

FOCUS
Business growth

KEY DATES

1970s McKinsey & Company consultants develop the MABA matrix to help conglomerates decide which divisions to grow, and how quickly.

2001 Neil Churchill—professor at INSEAD business school, France and John Mullins—professor at London Business School, UK—write *How Fast Can Your Company Afford to Grow*, introducing the self-financeable growth rate (SFG).

2002 Toyota announces plans to be the world's largest car producer. Eight years later, after recalling more than 8 million cars due to quality issues, it admits to growing too fast.

2012 Edward Hess writes *Grow to Greatness: Smart Growth for Entrepreneurial Businesses*, describing growth as recurring change.



"Grow or die" thinking can lead to **overtrading** and **business failure**.

When the market is growing, **a company must grow too**...

...but that growth must be **balanced and controlled**.

Nothing great is created suddenly.

One reason many new businesses fail is, perhaps surprisingly, because they grow too fast. Excessively rapid growth can cause companies to overreach their ability to fund growth: they simply run out of cash to pay for day-to-day operations. A major challenge for any manager is to balance income with expenditure, ensuring that there is sufficient cash to meet the rising costs of the business.

In 2001, business professors Neil Churchill and John Mullins created a formula for calculating the pace at which a company can expand from internal financing alone. Known

See also: Managing risk 40–41 ▪ Luck (and how to get lucky) 42 ▪ The Greiner curve 58–61 ▪ Hubris and nemesis 100–03 ▪ Profit versus cash flow 152–53 ▪ Small is beautiful 172–77 ▪ The MABA matrix 192–93

as the self-financeable growth rate (SFG), it helps managers to strike the right balance between consuming and generating cash. It does this by measuring three things: the amount of time a company's money is tied up in inventory before the company has paid for its goods or services; the amount of money needed to finance each dollar of sales; and the amount of cash that is generated by each dollar of sales.

Sustainable growth

When accurately applied, the SFG formula determines the rate at which a company can sustain growth through only the revenues it generates—without needing to approach external funding agencies for more cash. Essentially, it predicts a sustainable growth rate and helps to avoid overtrading. When a market is growing faster than a company's SFG, Churchill and Mullins identified three ways for managers to exploit the growth opportunity: speed up cash flow; reduce costs; or raise prices. Each of these "levers" helps to generate the cash needed to fuel faster growth.

As a young start-up business, the fashion brand Superdry enjoyed phenomenal growth. From its inception in the UK in 2004, the company rapidly added new stores throughout the world. In 2012, however, after several profit warnings, it became clear that Superdry had become a victim of its own success. Critics suggested that the brand was so focused on growth that it had forgotten its fashion roots, failing to update products on a seasonal basis. Other reasons for the decline included supply issues, accounting mistakes, and an inability to react quickly enough to fierce competition. In a tacit acknowledgement that excessive growth was to blame, the company announced plans to review its new store openings.

Business-growth expert Edward Hess suggests that growth can add value to a company, but if it is not properly managed, it can "stress a business's culture, controls, processes and people, eventually destroying its value and even leading the company to grow and die." Growth is not a strategy, he claims, but a complex change process, which requires the right mindset, the right procedures, experimentation, and an enabling environment. ■

The fate of the exploding Helix Nebula resembles the decline of a company that has expanded too rapidly: after using up all its energy resources, the star collapses on itself and dies.

> A profitable company that tries to grow too fast can run out of cash—even if its products are great successes.
> **Neil Churchill and John Mullins**

Edward Hess

A graduate of the universities of Florida, Virginia, and New York, Edward Hess has been teaching and working in the world of business for more than 30 years. He began his career at the oil company Atlantic Richfield Company, and later became a senior executive at several other leading US organizations, including Arthur Andersen.

Hess specializes in business growth, and especially in debunking the "myths" that growth is always good and always linear. Contrary to the dictum that companies must "grow or die," he suggests that they are likely to "grow and die."

Hess is the author of ten books and more than 100 practitioner articles and case studies. He is currently professor of business administration at the University of Virginia, US.

Key works

2006 *The Search for Organic Growth*
2010 *Smart Growth*
2012 *Grow to Greatness*

THE ROLE OF THE CEO IS TO ENABLE PEOPLE TO EXCEL

FROM ENTREPRENEUR TO LEADER

IN CONTEXT

FOCUS
Business growth

KEY DATES
1972 Professor Larry Greiner suggests the various stages of business growth are preceded by crisis, the first being a crisis of leadership.

2001 Leadership and change expert John Kotter writes the paper "What Leaders Really Do." Published in *Harvard Business Review*, it draws a distinction between the roles of manager and leader.

2008 Indian business scholar Bala Chakravarthy and Norwegian economist Peter Lorange's paper "Driving Renewal: The Entrepreneur-Manager" is published in *Journal of Business Strategy*. In it, the authors calls for a new breed of entrepreneurship in management, in order to manage business renewal.



As a business grows, its **demands change**.

Entrepreneurship is needed to spark a business into life, but...

...**management discipline** is required to support that growth...

...and **leadership skills** are required to maintain **long-term growth**.

Founders must adjust from being the sole decision-maker to **delegating**...

...and **make the transition** from entrepreneur to **leader**.

In the early days of a new business the most valuable skill a founder can have is entrepreneurship—the vision to identify opportunities, and the willingness to take risks. But as the business grows, demands change. Disciplined management skills and corporate expertise are required to co-ordinate a growing enterprise. Some entrepreneurs are able to make the transition to leadership successfully, while others struggle.

An Ernst & Young report in 2011 identified entrepreneurs as people who are nonconformist, driven and tenacious, passionate and focused, with an opportunist mind-set.

See also: Take the second step 43 ▪ The Greiner curve 58–61 ▪ Leading well 68–69 ▪ Effective leadership 78–79 ▪ Develop emotional intelligence 110–11 ▪ Mintzberg's management roles 112–13 ▪ The value chain 216–17

Other studies report entrepreneurs as mavericks, unafraid of failure and driven by a passion for success. While there is some overlap, absent from these findings are the traits that define good leaders and managers: organization, an eye for detail, communication, emotional intelligence, and the ability to delegate. And as Indian executive Vineet Nayar advised, effective leadership involves encouraging others within the company to realize their potential, and excel.

Making the transition

Canadian business guru Professor Henry Mintzberg proposed that management can be broken down into three categories: managing by information, through people, and through action. Many entrepreneurs have difficulty managing through information—they often lack the skills to build the systems and communication networks on which large businesses are built.

Cyprus-born Stelios Haji-Ioannou, entrepreneur and founder of easyGroup, is known for rarely staying still. His company launched in 1998 with a low-cost airline, easyJet, and now includes more than 20 "easy" businesses that operate on a similar low-cost model. Haji-Ioannou has shown an aptitude for strategy, and an eye for detail; but he has also been criticized for lacking leadership skills, for micromanaging, and, common to entrepreneurs, for an inability to delegate and let managers manage.

US professor Larry Greiner identified leadership—the ability of a start-up founder to transition from entrepreneur to leader—as one of the major crises that businesses face as they grow. Greiner suggests that successful growth often requires the employment of professional managers who bring to the business an understanding of the requirements of financial markets, banks, and—most importantly—have the leadership skills needed to manage complex organizations. Entrepreneurs may possess bountiful ideas, but it takes management discipline to turn those ideas into successful ventures, and leadership skills to move the start-up beyond its entrepreneurial roots.

Start-ups require the spark of entrepreneurship; but growth requires a different set of skills: a founder must transition from being sole decision maker to being a disciplined manager and a successful leader. Those who are unable to make this transition often need to step aside and let the professionals take over. But this is often easier said than done. ■

> “The function of leadership is to produce more leaders, not more followers.”
>
> **Ralph Nader**
>
> **US political activist (1934–)**

Zhang Yin

Chinese entrepreneur and paper-recycling tycoon Zhang Yin was born in Guangdong in 1957. Recognizing that the Chinese export sector faced a shortage of paper-packaging materials, Zhang (her Cantonese name is Cheung Yan) opened a paper-trading business in Hong Kong in 1985.

Quickly moving from entrepreneur to established business leader, Zhang moved to Los Angeles, US, where she co-founded the paper-exporting company America Chung Nam in 1990. The business quickly became the leading paper exporter in the USA, and the largest overall exporter to China. In 1995, after returning to Hong Kong, Zhang cofounded Nine Dragons Paper with her husband and her brother. The company went on to become the world's largest maker of packaging paper.

In 2006, at the age of 49, Zhang became the first woman to top the list of richest people in China, according to the magazine *Hurun Report*. The following year, Ernst & Young awarded her "Entrepreneur of the Year in China 2007."

CHAINS OF HABIT ARE TOO LIGHT TO BE FELT UNTIL THEY ARE TOO HEAVY TO BE BROKEN

KEEP EVOLVING BUSINESS PRACTICE

IN CONTEXT

FOCUS
Middle management

KEY DATES
Pre-1850 The business landscape is dominated by small, family-run firms.

1850s and 60s A rapid expansion of the railroad systems and new industrial technology in Europe and America create greater possibilities for entrepreneurial businesses.

From 1880s As family businesses grow ever larger, administration becomes important and they begin to employ professional managers.

1982 UK economist Norman Macrae predicts a future trend of "intrapreneurs": managers with entrepreneurial thinking.

People are important in organizational life. Whether it is the initiative of a single entrepreneur or the combined energy of thousands of employees, it is people who get things done. However, that energy and initiative would count for little without managers to foster it. The creation, implementation, and management of organizational processes is what molds individual energies into a coherent whole—and as a company evolves, it is the experience of management that is essential in redefining those processes.

While management experience can liberate a business, it can also enslave it. Experience quickly gives

See also: Beating the odds at start-up 20–21 ▪ Take the second step 43 ▪ Reinventing and adapting 52–57 ▪ The Greiner curve 58–61 ▪ The weightless start-up 62–63 ▪ Beware the yes-men 74–75 ▪ The capability maturity model 218–19

> It is the structure of the organization, rather than the employees alone, which holds the key to improving the quality of output.
>
> **W. Edwards Deming**
>
> **US business professor** (1900–93)



As a business matures and grows it will require **systems, procedures, and protocols**.

Those systems are the **purview of middle management**.

But **too much process** can stifle innovation and, therefore, growth.

Companies must **balance structure with flexibility**.

This requires **experienced** handling.

Companies must **look to the experience of middle managers** for growth.

way to the comfort of habit, and in ever-dynamic markets habit can too easily lead to stasis and stagnation. The danger for management is that, as US investor Warren Buffet warned, “chains of habit are too light to be felt until they are too heavy to be broken.”

Middle management

The importance of middle management was described by business historian Alfred Chandler in his 1977 text, *The Visible Hand*, a play on economist Adam Smith’s “invisible hand” metaphor, which explains the self-regulating forces of the market. Chandler noted that before 1850, family firms dominated business in the USA. These firms had poor communication networks and limited access to educated staff, so rarely grew beyond groups of family and friends who could be educated, trained, and trusted to manage the business.

However, with the growth of national railroad networks in the 1850s, the management landscape began to change. Improvements in transportation and communication allowed firms to grow beyond the immediate gaze of friends or family, and beyond the immediate locale. But to prosper in this new environment, companies needed more rigorous processes and structures. The increasing geographic scope and size of businesses required new levels of coordination and communication. Businesses had grown too unwieldy for one person to manage; they required the oversight of a team of people. This marked the emergence and rise of the professional manager.

As standardization and mass production emerged in the early 20th century, the role of management grew. Business was taking place on an increasingly global scale. Even before mechanization, coordination from managers enabled mass production. Standardization turned management into a science, and managers into a vital cog in the organizational machine.

Enablers and enterprise

In a 2007 *Harvard Business Review* article “The Process Audit,” US businessman Michael Hammer » summarized the science of management (which is essentially the management of business process) into two factors: enablers and enterprise capabilities. Enterprise capabilities stem from senior management, and include culture, tight governance mechanisms, and strategic vision. Enablers, however, are the task of middle management. They include design, infrastructure, process, protocol, responsibilities, and performance management. The enablers turn vision into reality.

Realizing the vision

Hammer claimed that while the aspiration for business growth might come out of the boardroom, it is a company's infrastructure—designed and implemented by middle management—that makes growth possible. Vision without infrastructure is just a dream—it cannot become a reality. Leaders of growing companies know that, regardless of their own aspirations, the building blocks of growth are laid by middle management.

At the Japanese brewer Asahi, for example, it was a team of middle managers who developed Super Dry Beer, starting a craze in Japan for dry beer and allowing the company to capture more market share. Similarly, a group of Motorola middle managers was lauded for successfully developing a new wireless digital system for a client in under one year (the process usually takes two to three years).

Sitting between senior leaders and operational staff, middle managers are the communications conduit through which executives remain attuned to day-to-day business and personnel issues. Middle managers, as the Asahi and Motorola examples show, are often at the heart of corporate inspiration and perspiration—they generate ideas and they work to realize ideas in practice. Middle management is also the driver of functional efficiency: improvements in cost, quality, speed, and reliability are delivered by middle management and the processes it introduces.

Growing the business

As a business evolves, so must the management processes that enable it. Whereas initial stages of growth rely on individual initiative and entrepreneurial spirit, evolving ad-hoc practices into sustainable growth needs to be based on lessons learned through business experience. The true science of management is the conversion of experience into repeatable and reliable process—today's problems become tomorrow's processes and next year's capabilities.

Process is the "stuff" of management. Business processes are essential to maintaining order; like a country's rail system and the rules that accompany it, processes are the infrastructure around which a company organizes. Business practice must evolve as the business grows from a single outlet to a chain, from one staff member to many, and from national to multinational.

> Middle management as a technology enables the organization as we know it.
>
> **Alfred Chandler**
>
> **US business historian (1918–2007)**

Cath Kidston

English fashion designer, author, and entrepreneur Catherine Kidston was born in 1958. Raised with her three siblings near Andover in Hampshire, she was educated at a number of English boarding schools, before moving to London at 18.

After working as a store assistant, she ran a vintage curtain business with a friend on London's King's Road for five years. In 1992 she sold the business and a year later opened a store selling vintage home goods, wallpaper, and fabric. With about $23,000 in her pocket, she had to buy her stock carefully, mixing her own fabrics and wallpaper with items from tag sales and fabric from eastern Europe. Gingham ordered from Europe arrived already made into duvet covers and pillowcases, rather than as a fabric bolt. Kidston realized she would have to improvise, so decided to "cut it up and make it into other things." She kept some of the bedding, but altered most items into products such as toiletry bags. The Cath Kidston brand was born.

The development of infrastructure and the strength of a new layer of middle management were key factors in the evolution of UK retailer Cath Kidston from a single store in 1993 to more than 120 global branches and concessions by 2013, with stores throughout Europe and Asia, and plans to expand into North America. Widely renowned for its vintage fabrics, wallpapers, and brightly painted junk furniture, Kidston's initial growth, as is common with many single-founder start-ups, was slow. In the early days, monthly accounts took six weeks to prepare and clashes between IT systems caused issues with cash-flow projections and supply-chain management. It took nine years to open a second branch, and another two before the third.

Following a buy out in 2010, Cath Kidston became partly owned by a US private-equity group, with Kidston herself retaining about 20 percent of stock. As expansion took hold, the company started to move from ad-hoc processes to a more planned approach. Specialized managers and consultants were brought in to help build capacity for growth. New departments were added, including design, buying, and merchandising, and systems were introduced. Most importantly, middle management gained experience of what it takes to open and run a new store. The lessons from earlier mistakes were integrated into procedures and policies; by building on experience, every new store opening became easier than the last.



Enablers are the realm of middle managers, according to Michael Hammer's analysis of the science of management. When implemented and maintained efficiently, they foster growth and turn the vision of senior executives into reality.

Excess and habit

The dangers of processes and of hierarchy (if it becomes excessive) are that they may begin to grip the organization too tightly. Protocol and bureaucracy can wear people down, stifling innovation and hindering growth. As markets and technology move ever faster, process must not blind managers to opportunity, and systems must not restrict strategic agility. For example, Motorola continued to invest in satellite technology throughout the 1990s even after competitors had switched to cheaper, more effective ground-based cell towers.

Habit can also twist logic. So habitual, for example, were the claims of ethical behavior from Dennis Kozlowski, CEO of Swiss security company Tyco International, that he seemed able to divorce the reality of his own behavior from his rhetoric—in 2005 he was convicted of corporate fraud. Habit can also lead to hubris. Buoyed by his business's accomplishment in electronics, in 1994 Samsung CEO Lee Kun-Hee believed that the same approach would lead to success in the car market, but the venture struggled and was rescued in 2000 by Renault. The experience (and habits) of Renault's managers have since helped Renault Samsung Motors gain a footing within the South Korean automotive market.

Business leaders dismiss the value of middle management, and the value of process, at their peril. Without middle managers who are able to evolve a leader's vision into reality, many businesses would be stuck like those of the pre-railroad era, destined to remain small, local, and family run. It is the science of management that enables business evolution and growth. ■

> If you can't describe what you are doing as a process, you don't know what you're doing.
> **W. Edwards Deming**

A CORPORATION IS A LIVING ORGANISM IT HAS TO CONTINUE TO SHED ITS SKIN

REINVENTING AND ADAPTING

IN CONTEXT

FOCUS
Process and product

KEY DATES
1962 US professor Everett Rogers writes *Diffusion of Innovations*, showing how innovation moves through social systems.

1983 US business consultant Julien Phillips publishes the first change-management model in the journal *Human Resource Management*.

1985 In *Innovation and Entrepreneurship*, Peter Drucker describes the best approach to managing change as one that "always searches for change, responds to it, and exploits it."

1993 US change expert Daryl Conner uses the metaphor of "the burning platform" to describe the high cost of a business that stays the same.

Just as human beings are organisms that grow, change, and adapt, so do successful businesses. In 1970, the US futurist Alvin Toffler published *Future Shock*, a book that predicted the coming phenomenon of "a perception of too much change in too short a period of time." The pace of change, he said, would also spread to the world of business, as companies were forced to adapt their products and processes to maintain advantage in an increasingly competitive market.

Toffler's ideas of the effects of rapid technological change were viewed at the time as far-fetched, but with the invention of computers and the Internet, change has accelerated even more rapidly than he predicted. Toffler presciently claimed that we would live in a state of "high transience," in which we would give ideas, organizations, and even relationships an ever-shorter amount of our time. Social media websites are witness to this idea in action, providing a platform for the new ways we have begun relating to one another; they also demonstrate new ways of starting, growing, and building businesses.

> The reinvention of daily life means marching off the edge of our maps.
> **Bob Black**
> **US activist** (1951–)

In 1989, US computer scientist Alan Kay claimed that it took 10 years for an innovation to go from the laboratory to everyday life, but by 2006 Twitter had managed to cut this down to just four years. Products can now be bought online from anywhere in the world, and customer feedback is instant and global. The challenge for companies to adapt and reinvent is huge.

Products and processes

The personal and business landscape has changed so radically since the 1960s that no industry or corporation has proved immune to



Markets are never static—**change is inevitable** and continuous.

Businesses must respond to change through **innovation**...

...in **thinking, product, and process**.

This flexibility allows companies to respond to the market and gives them a **competitive edge**.

Adaptation and reinvention are necessary for business survival.

See also: Gaining an edge 32–39 ▪ Keep evolving business practice 48–51 ▪ Creativity and invention 72–73 ▪ Thinking outside the box 88–89 ▪ Changing the game 92–99 ▪ Avoiding complacency 194–201

its effects. Consider, for example, the music and movie industries. New technology has completely, and very rapidly, changed the way that movies and music are purchased and consumed. For the big movie and music businesses (and all their associated suppliers and producers), survival has required a high level of reinvention and adaptation.

This reinvention has come in the form of both new products and new processes. Product adaptation involves updates and redesign—essentially, innovation and invention. The movie industry has undergone many transformations since the early days of black-and-white moving pictures, or "movies." It has reinvented itself through technology (from adding sound to creating "impossible" computer-generated images); marketing devices, such as monthly access cards; events, such as outdoor screenings; and the growth of the multiplex to multiply visitor numbers and reduce turnaround times. The newest product aimed at luring viewers away from illegal downloads and back into movie houses is Stereoscopic-3D—itself a reinvention of an older idea.

Around the turn of the 21st century, the music industry was also struggling because of the drop in sales of CDs, and began to refocus on live music and merchandise. However, both the music and movie industries found new life through digitization, such as Apple's iPod and iTunes. This revolutionary combination of product and process—Apple's hardware and software—made legal downloads of music and movies more attractive than illegal versions. In 2013 the Apple iTunes store offered 60,000 movies across 119 countries, and 35 million songs.

Innovative methods

Process adaptation involves finding new ways to do things; it involves introducing or removing processes. Competition from online sales and pirate streaming continue to affect movie distribution companies such as Netflix. The response of this highly popular video streaming service was to make all the episodes of one television series (*House of Cards*) available for download simultaneously; the rationale being that the risk of piracy would be lower if consumers were able to legally buy all episodes at once.

For Netflix this bold strategy was not just a radical new process; it was also an adaptation of the company's entire business model. Still in the adolescent stages of growth, in 2012 Netflix was primarily an online streaming service, but for *House of Cards* it entered the world of production. By producing and distributing, Netflix was able to capture more profit and gain more control over content. Netflix did not »

> Excellent companies don't believe in excellence—only in constant improvement and constant change.
>
> **Tom Peters**
>
> **US business expert** (1942–)

Product adaptation in the music industry demonstrates the steady use of new technology—from gramophone to vinyl, cassette, CD, minidisc, and MP3 digital music file—as companies have sought to broaden the market for music.



know if the *House of Cards* experiment would work. It did know, however, that in order to maintain the momentum of early growth, it needed to adapt and reinvent—in this case reinvention as television producers as well as distributors.

Internal changes

Reinvention and adaptation can also be internally focused on systems, recurrent tasks, or operational activities. Whether improvement of this type is based on data from formal process improvement frameworks (such as Total Quality Management) or simply on the experience and intuition of managers, internal process adaptation allows companies to maximize revenue while also reducing costs.

The McDonalds McSnack Wrap, for example, takes staff only 21 seconds to make—the shorter the preparation time, the greater the number of customers that can be served by the fewest staff. At R Griggs Group Ltd, manufacturer of Dr. Martens shoes, a reinvention of internal systems allowed the company to exploit global sales opportunities. In 1994, due to the brand's growing popularity, demand far exceeded manufacturing capability. Poor planning and coordination led to delayed production and lost sales. The solution was a reinvention of internal systems based around an integrated IT system. The product itself—the classic "1460" eight-laced leather boot—changed very little, although more designs were later added to the product range. The key change was the adaptation of internal processes, which ensured supply could match demand.

Dr. Martens footwear grew from a niche fashion item to an international mainstream hit within a matter of years. R Griggs, the brand's producer, had to reinvent processes to match demand.

Adapting in a recession

Internal process adaptation is even more important in markets where demand is static or falling. Operational efficiencies, rather than revenue growth, are the key to profit. For insurance companies, for example, scope for new product adaptation is limited, so competition is price-based—especially in a recession, when customers are particularly price sensitive. The key to maintaining profitability while remaining price competitive is continual process improvement—the reinvention of internal systems that deliver the same product to customers, but at a lower cost and, therefore, increased profitability. The days of the door-to-door insurance salesperson have long since been replaced by telesales and an e-commerce approach.

Reinventing the company

A notable company that has successfully reinvented itself is Samsung Electronics. Established in 1969, Samsung Electronics is a subsidiary of the Samsung Group, which aimed to exploit opportunities in the emerging technology industry. The company began with black-and-white televisions and moved into home appliances during the 1970s. In the 1980s, production grew to PCs and semiconductors.

> “
>
> Those who initiate change will have a better opportunity to manage the change that is inevitable.
>
> **William ("Bill") Pollard**
>
> **US businessman (1938–)**
>
> ”

In 1986, Samsung released its first car phone, the SC-100. The product was a disaster—the quality was so poor that many customers complained. This reputation for poor quality blighted Samsung for much of its early life, since consumers regarded its goods as inferior to premium Japanese products.

On June 7, 1993, chairman Lee Kun-Hee gathered senior Samsung executives and declared that the company needed to reinvent itself. His famous instruction "Change everything except your wife and children" shows how seriously he took the situation. Lee also recognized shifting market dynamics, telling colleagues that the company needed to "produce cell phones comparable to Motorola's by 1994 ... or Samsung will disengage itself from the cell-phone business." The "new management" initiative that followed, supported by product and process innovation, put the emphasis on the quality and innovation that Samsung is now renowned for, and galvanized



When processes evolve they may create new jobs or cause existing ones to disappear. The manual switchboards of the old ztelephone system were soon replaced by faster, automatic ones.

its foundation for future growth. Samsung's transformation was not yet complete, however—the Asian financial crisis of the late 1990s forced the company to reinvent itself yet again. Adapting its process turned Samsung into a more market-focused and consumer-friendly brand. Since then the company's efforts, particularly in the cell-phone industry, have been based on constant attrition, reinvention, and adaptation.

Long-term survival

Few businesses survive without adaptation or reinvention. Products such as Kellogg's Cornflakes and Heinz Beans—products that have not changed in decades—are rare. Even when a product has not changed, many of the processes used in its manufacture, distribution, and marketing have altered dramatically. The factories of 100 or 50 years ago were very different than today's, where many tasks are automated and fulfilled by computers and robots. Promotions have also adapted to fit changed consumer demographics, globalized markets, and customer preferences. Even established brands cannot avoid reinvention.

Truly successful business transformation is rarely due solely to discovering and commercializing bold new ideas, technologies, and products. The most successful businesses know that reinvention is a continual process. Social media, for example, has created a market shift that has required businesses of all types to adapt; even record labels now embrace the promotional value of websites such as YouTube.

The ecosystem in which a business operates is rarely, if ever, static. Corporations exist in these ecosystems as living organisms that must adapt to survive; great leaders know that failure to adapt leads to extinction. ■

Lee Kun-Hee

Born on January 9, 1942, Lee Kun-Hee is Chairman of the South Korean conglomerate Samsung. Holding an economics degree from Waseda University in Tokyo, Japan, and an MBA from George Washington University in the US, Lee Kun-Hee joined the Samsung Group in 1968 and succeeded his father as Chairman on December 1, 1987.

Samsung is the quintessential example of a *chaebol*, a uniquely Korean conglomerate that mixes Confucian values with family ties and government influence. Under Lee's stewardship, the company has been transformed from a Korean budget brand into a major international force and, alongside Sony, is one of the world's most prominent Asian businesses. Samsung Electronics, the conglomerate's most famous subsidiary, is a leading developer of semiconductors, TV screens, and cell phones—with its smartphones even outselling the iPhone in many markets.

The *Forbes* 2013 Rich List recorded Lee as the world's 69th richest billionaire, and the richest Korean.

WITHOUT CONTINUAL GROWTH AND PROGRESS, SUCCESS HAS NO MEANING

THE GREINER CURVE



IN CONTEXT

FOCUS
Business growth

KEY DATES
1972 Larry Greiner outlines five stages of business growth, and their related crises, in "Evolution and Revolution as Organizations Grow."

1988 Macedonian business expert Ichak Adizes writes *Corporate Lifecycles*, in which he describes the growth of corporations as a series of five "S" curves.

1994 Professor David Storey claims that all forms of "stage" models have limitations. He suggests looking at growth through categories of companies instead: failures, trundlers, and flyers.

1998 In a reprint of his 1972 article, Greiner updates his theory and adds a sixth stage to the Curve.

Aside from the financial rewards that they offer to entrepreneurs, start-ups can be exciting places to work. Amid the chaos, continual change, ever-evolving policies and procedures, and the abundance of work required, these environments buzz with energy, initiative, and ideas. But as business growth places increasing pressure on people and systems, excitement can turn into frustration.

Periods of chaos often occur in a start-up's early life. As it matures, the new business will pass through various conceptual thresholds. In 1972 Larry Greiner identified these as "crises of growth," which he

See also: Beating the odds at start-up 20–21 ▪ Take the second step 43 ▪ How fast to grow 44–45 ▪ From entrepreneur to leader 46–47 ▪ Keep evolving business practice 48–51 ▪ The weightless start-up 62–63

Start-ups are **exciting places** to work...

...but growth brings inevitable **crises**.

These crises **are predictable and can be managed** by using the Greiner Curve.

illustrated on a graph that came to be known as the Greiner Curve. He noticed that companies of all types go through periods of growth followed by inevitable crises, when major organizational change is needed to maintain momentum.

Stages of growth

Greiner initially identified five stages of growth, but later added a sixth. The first of these stages is "growth through creativity." During this stage, the start-up is small and growth is fueled by the enthusiasm of its founders. Management procedures, communications—and even interactions with customers—are usually informal and ad hoc. However, as more staff joins and production expands, more capital will be required (perhaps from banks or venture capitalists), and the need for formal systems and procedures increases. The founders—who are likely to be technically or entrepreneurially oriented—find themselves faced with their first crisis, as they become burdened by management responsibilities that they are ill-equipped to deal with. This first crisis is therefore one of leadership: who will lead the company out of confusion and solve the new management problems?

Change of leadership required for phase two may only be a question of internal reorganization and a change in style, abandoning the casualness of the company's early days in favor of greater formality and more rigid systems and procedures. But in many cases the original founders have neither the skills nor the desire to take on more formal leadership. In 2002, chef Jamie Oliver founded Fifteen, a chain of restaurants that also provide training opportunities for disadvantaged young people. As the chain grew, he handed over the management to a CEO, so that he could return to doing what he does best: being a commercially successful celebrity chef.

Under professional managers, business growth continues in an environment of more formal structures and budgets, and with the establishment of separate functions, such as production and marketing. This is the second stage of growth, known as "growth through direction." As the new »

The Greiner Curve illustrates the six stages of growth that any company might undergo during its development. Each growth phase generates a crisis, the resolution of which leads to the next growth stage.



manager takes responsibility for direction, mid-level supervisors or managers act more as functional specialists, but after a while they begin to demand more freedom to make decisions, leading to the second crisis: "autonomy." This crisis can be solved by freeing the mid-level managers from bureaucracy and allowing the company to achieve "growth through delegation"—Greiner's third stage of growth. Unburdened by the need to manage day-to-day issues, senior management can shift its attention to strategy and long-term growth.

Stay small or grow?

At this point a start-up faces perhaps the biggest crisis of all: a crisis of control. The founders or senior management may find it hard to give up responsibility for decision making, even to trusted boards. When this happens, the founder may decide to remain small—in essence, to limit growth to the extent of their own control.

Such decisions are laudable. Not all companies can be global and all-conquering, and in fact, small- and medium-sized enterprises dominate the business landscape. Some entrepreneurs start a small company to escape the stresses, politics, and office-bound purgatory of corporate life and so, for them, it may make sense to limit growth at this stage.

> One can choose to go back towards safety or forward towards growth.
>
> **Abraham Maslow**
>
> **US psychologist (1908–70)**

Other entrepreneurs—such as Virgin chief, Richard Branson—are enthused by the early phases in the life of a new business, but become bored as the bureaucratic demands increase. Branson likes to guide a business through its start-up phase then hand it over to professional managers, so he can move on to new, more exciting, projects. Choosing to remain small does not mean that a business will be crisis-free. All businesses, of all sizes, and regardless of growth aspirations, will face uncertainties and challenges. It does mean, however, that the business will avoid the requirements of the next stage: "growth through coordination."

During this fourth stage, increasing centralization is common. By this time the company may be relatively large, with operations controlled through a head office. The company may appoint executives with experience of managing large, diverse businesses and introduce standard operating procedures.

However, the introduction of standard policies eventually leads to the next crisis: a "red-tape crisis," in which increasing bureaucracy stifles operations, and growth falters as a result.

A return to informality

Paradoxically, the fifth stage, "growth through collaboration," requires, in part, a return to the earlier days of flexibility. Systems allow greater spontaneity, teamwork is introduced, and matrix (network) structures are used to recapture the collaborative nature of a start-up—in other words, the organization tries to operate like a lean, creative company once again.

Once this has been attained, the next crisis relates to the limits of internal growth. Under pressure from shareholders to continually improve returns, further growth can only be achieved by developing partnerships with complementary organizations. By this sixth stage a company is already big, possibly very big. "Growth through alliances" therefore suggests that expansion will continue through mergers, outsourcing, or joint ventures—the company needs to look beyond its own internal

Larry Greiner

Larry Greiner is a professor of management and organization at the University of Southern California, US. He received a BA degree from the University of Kansas, and an MBA and doctorate from Harvard Business School.

Greiner is the author of numerous publications on the growth and development of organizations, management consulting, and strategic change. His 1972 article, "Evolution and Revolution as Organizations Grow", is regarded as an all-time classic. Greiner has acted as a consultant to companies and government agencies in the US and abroad, such as Coca-Cola, Merck, Andersen Consulting, Times Mirror Company, and KinderCare.

Key works

1972 "Evolution and Revolution as Organizations Grow"
1998 *Power and Organization Development*
1999 *New CEOs and Strategic Change, Across Industries*



Spotify CEO Daniel Ek worked with co-founder Martin Lorentzon to build a large but agile company. It avoids Greiner's growth problems by working in small squads overseen by "tribes."

capabilities, and the capacity of its core markets, and seek external growth.

The actual rate of growth—in terms of customer numbers, revenue, or profits—within each phase of the Greiner Curve will vary, depending on the individual company. Organizations such as Facebook were already large by the time they started to face crises of delegation and control. Others may remain small for many years, perhaps never even reaching the leadership-crisis stage.

Using the Greiner Curve

Knowledge of the Greiner Curve can help start-up founders to predict and manage the inevitable crises of growth. Even when enjoying the heady days of early growth, entrepreneurs need to be mindful of the steps required to build the business further. They must put structures in place as soon as possible; the earlier that formal systems and professional management are introduced, the less they will be resented and resisted, and the stronger the foundations for continued growth. In this regard, the various crises identified by the Greiner Curve can be seen as natural transitions. An organization must manage its way through such transitions and growing pains as it continually defines and redefines the scope of its operations, its values, and its overall purpose. As Benjamin Franklin observed, "without continual growth and progress, such words as improvement, achievement, and success have no meaning."

Large but agile

One company that seems to have heeded the lessons of the Greiner Curve is the Internet music-streaming service, Spotify. The organization's Swedish founders, Daniel Ek and Martin Lorentzon, knew at the company's inception in 2008 that their aim was growth. They also knew that they were not willing to compromise the benefits that accompany the excitement of a start-up business.

Spotify organizes itself around project-based teams, called "squads." The organization is divided into small clusters of squads, with each squad running as a start-up business. Mirroring the benefits enjoyed by companies in Greiner's first stage, every squad is fully autonomous, has direct contact with its stakeholders, and operates with minimal dependency on other squads.

To deal with the various crises of growth (such as autonomy and red-tape), related squads are grouped into "tribes." The function of the tribe is to support and enable the activities of each squad, in essence mirroring the role of venture capitalists in incubating new start-ups. The operation is kept small and agile by limiting the head count for each tribe to 100.

Spotify appears to have managed to maintain a balance between the benefits of growth and the feel-good elements of a start-up. The founders nevertheless admit that the system is not flawless, and as the demand for an organization-wide strategy grows, it may be that even Spotify will not escape the crises of growth predicted by the Greiner Curve. ■

> All growth depends upon activity. There is no development physically or intellectually without effort, and effort means work.
>
> **Calvin Coolidge**
>
> **US former President** (1872–1933)

IF YOU BELIEVE IN SOMETHING, WORK NIGHTS AND WEEKENDS—IT WON'T FEEL LIKE WORK

THE WEIGHTLESS START-UP

IN CONTEXT

FOCUS
Start-ups

KEY DATES
1923 Walt Disney starts making professional cartoons in his uncle Robert's garage.

1976 The first 50 Apple computers are built in the spare room of Steve Jobs's parents' house. A few months later Apple moved "upscale" to his parents' garage.

1978 Indian master brewer Kiran Mazumdar-Shaw founds biotechnology company, Biocon, in the garage of her rented house in Bangalore, India.

2004 Kevin Rose quits his television job to found Digg, a news aggregator website that attracts 38 million users a month during its peak. The "office" is his bedroom.


Many start-ups require skill, not capital outlay.
In a weightless start-up, the risk is time, not money.
The work can be done initially on weekends and evenings, but...
...if you believe in what you're doing, it won't feel like work.

Starting a business requires almost boundless energy, unwavering commitment, and the resilience to deal with risk. But increasingly, the commercial potential of the Internet is allowing a growing number of "weightless" start-ups to take flight. These ventures are low on financial resources, but high on individual skill and the investment of time to bring an idea to fruition.

Personal passion is an essential ingredient in a successful start-up. As Kevin Rose, founder of Internet start-ups Digg, Revision3, and Milk, put it: "If you believe in something, work nights and weekends—it won't feel like work." Even global greats such as Nestlé foods and Siemens electronics grew from the dreams and aspirations of a small group of people. These entrepreneurs faced the risk of a new business because they deeply believed in something, and were driven to realize their dream, despite long hours, stress, and, often, a string of failures large or small. These are quickly forgotten when people are doing something they love.

Traditionally, the main barriers to enterprise were time and capital. Entrepreneurs from nonwealthy

See also: Beating the odds at start-up 20–21 ▪ Luck (and how to get lucky) 42 ▪ The Greiner curve 58–61 ▪ Changing the game 92–99 ▪ Small is beautiful 172–77



Hewlett-Packard (HP) began life in Dave Packard's garage. The company has restored the garage, which in 1987 was named a California landmark as "the birthplace of Silicon Valley."

backgrounds usually needed a full-time job to meet the living costs of themselves and their families. Without sufficient savings, few people could risk a new business venture in the 20th century, but today, starting a business is easier.

Micropreneurism

In the mid-2000s, the notion of a micropreneur began to emerge. This was an individual who ran a very small business, often in addition to full-time employment. The concept gained popularity alongside the rise of e-commerce, which made it possible to launch a commercial website and manage it nights and weekends. Sales platforms, such as those provided by eBay and the Chinese online marketplace Taobao, made it even easier, since they dispensed with the need for a website or payment systems. These micropreneurs, who sell everything from homemade fashion items to antiques and secondhand electronics, are risking very little other than their own time—the capital outlay can be as much or as little as they are willing to risk. The micropreneur's skill lies in spotting the right opportunity. In this way the business can be as small or large as time, and desire, allows.

For those who aspire to more than running a business as a part-time hobby, the lean start-up path is well trodden. Large companies such as Hewlett-Packard and Indian biotech Biocon both started in their founders' garages. Passion was key—with very limited capital, essential equipment was begged and borrowed; friends and family were used as (free) staff; and sleep was sacrificed. The main resources were time, skill, and tenacity.

The path is not straightforward, however, and requires a deep commitment, often in the face of failure. As Jeff Bezos warned, "invention requires a long-term willingness to be misunderstood." ■

Hewlett-Packard

Bill Hewlett, born 1913, and Dave Packard, born 1912, were close friends who graduated as electrical engineers from Stanford University. After his marriage, Packard moved into an apartment in Palo Alto, California, with his wife, while Hewlett camped out in a shed on the grounds. A garage belonging to the property became a decidedly low-tech workshop. From 1938 to 1939 the garage served as home, think tank, lab, office, and production department. Bill and David developed the 200A and 200B audio oscillators, which became Hewlett-Packard's first products.

Believed to be the first US technology company to launch in a garage, Hewlett-Packard was founded by the two friends on an investment of just $538. Today the organization is one of the world's largest technology companies, with sales in excess of $27 billion in 2012. The garage is designated a historic landmark and is listed on the United States National Register of Historic Places.

> “You have to really believe in yourself and know that, in the worst-case scenario, if it doesn't work out, you still built something really cool.”
>
> **Kevin Rose**

LIGHTIN
THE FIR

LEADERSHIP AND
HUMAN RESOURCES

G

E

Growth from a small start-up to a large multinational company cannot be achieved without leaders who are passionate about their business and who are inspirational to their staff. Leading a business is, at its core, about harnessing the power of people.

One popular business aphorism claims that "there are no business problems, only people problems." Managing people is not easy; every organization is a collection of individuals, each with their own philosophies, vulnerabilities, drives, strengths, and weaknesses. Effective leadership embraces these differences and creates a culture in which people can make the most of their talent. In other words, leadership is about creating capacity in others. It is about imagining the future, determining strategic direction, and aligning the organization and its people to a particular vision.

> Good leadership consists of showing average people how to do the work of superior people.
>
> **J. D. Rockefeller**
>
> **US industrialist (1839–1937)**

Leaders and managers

The very best leaders, as Steve Jobs said, "put a dent in the universe." These leaders are not bound by convention; they are able to think outside the box, embracing one-of-a-kind ideas that disrupt the status quo in their favor. In today's hypercompetitive markets, the leaders we celebrate do not only outthink, outsmart, and outcompete their rivals, they disrupt entire industries. They change the game.

Rarely, though, do leaders achieve greatness alone. Leaders rely on managers. While leadership is about vision, management is about process, planning, budgeting, structuring, and staffing—tasks that help an organization to keep doing what it does. In *The Manager's Job* (1975), Henry Mintzberg identified three broad management roles: informational (managing by information); interpersonal (managing through people); and decisional (managing through action). Importantly, Mintzberg noted that none of these roles is exclusive or privileged. Leading well often involves shifting seamlessly between leadership and management, and knowing when, contextually, each role is most appropriate to adopt.

Creating the organizational capacity for continued success also means putting together teams and managing talent. An effective team is a powerful thing. Individuals perform better in teams; they are more productive and more innovative. Teams can also be self-managing; individuals support each other and strive not to let the team down. Effective teams require less supervision and less direction than individuals, and performance is guided by group norms, not by one individual's expectations.

It is not surprising, then, that great organizations recognize the value of teams. Google, for example, designs workstations so that staff can easily collaborate. "Hangout spaces" are adorned with funky furniture and supplied with food to allow teams to work and socialize. Leaders at Google want employees to interact; they recognize that by encouraging teamwork, employees enjoy greater job satisfaction and creativity, and as a result, innovation rises. To the benefit of

its staff and its bottom line, Google knows that the best workplaces feel like playgrounds—places where people can imagine and invent.

Satisfaction and challenge

Creating an organizational culture that embraces teamwork and encourages creativity helps companies address the perennial question: “is money the motivator?” Most find the answer is “no.” Higher pay might encourage an individual to take a new job, it might encourage people to move a little faster or to work a little harder, but people soon forget about the money and start to focus on other things—such as job satisfaction, challenge, and respect from managers. Virgin Atlantic airline, for example, is not known as one of the highest payers, but is regarded as a great place to work.

A strong organizational culture is, therefore, essential to success. Through tradition, history, and structure, companies build a sense of identity—a unique personality defined by the characteristic rituals, beliefs, stories, meanings, values, norms, and language that determine the way in which “things are done around here.”

Importantly for leaders, managing people also means managing oneself. Business history is littered with examples of leaders who, blinded by success, leapt into ill-conceived initiatives or made “bet-the-farm” decisions that proved disastrous. “Deal fever” can mean that warning signs are ignored by leaders who feel they can do no wrong. Successful leaders, however, know that they must fight against the illusion of invulnerability. They also realize the dangers of wanting to be liked or to conform. Great leaders know that they must guard against groupthink and “yes-man” mentalities in themselves and others, because such approaches leave decisions unchallenged, and allow ill-judged projects to proceed without sufficient due diligence. The best leaders accept that they are not gods of management, and that, in fact, occasionally being told “no” can be more important than always hearing “yes.”

> “Everyone experiences tough times; it is a measure of your determination and dedication how you deal with them.”
>
> **Lakshmi Mittal**
> **Indian entrepreneur** (1950–)

Emotionally intelligent

Creating a culture where this kind of challenge is the norm depends upon diversity. In companies with employees from diverse backgrounds, where gender, race, and age are balanced, the different perspectives mean decisions are more likely to be questioned.

Perhaps most importantly then, and as recent research indicates, the single most important trait for successful leaders is emotional intelligence. In his bestselling book, *Emotional Intelligence* (1995), Daniel Goleman describes five domains of Emotional Intelligence (EQ): knowing your emotions; managing them; motivating yourself; recognizing and understanding other people’s emotions; and managing relationships. Without EQ, a leader can be technically brilliant and full of great ideas, but still ineffective. This is because a sole trader may be able to survive on intuition alone, but as soon as someone else is employed, EQ becomes key. Lighting the fire means keeping the sparks flying for everyone. ■

MANAGERS DO THINGS RIGHT, LEADERS DO THE RIGHT THINGS

LEADING WELL

IN CONTEXT

FOCUS
Organizational roles

KEY DATES

1977 US professor Abraham Zaleznik writes an article asking "Managers and Leaders: Are They Different?"

1985 In *Leaders: Strategies for Taking Charge*, Warren Bennis and Burt Nanus suggest four leadership strategies to help leaders do the right things.

1990 US leadership expert John Kotter publishes *What Leaders Really Do.*

1997 Robert House and Ram Aditya claim that management consists of implementing the vision and direction provided by leaders.

2005 Warren Bennis publishes *Reinventing Leadership: Strategies to Empower the Organization.*



Leaders **develop a vision** for the organization.

They **conquer** in any context—even in the most turbulent of times.

Leaders advocate **change and new approaches**...

...that **managers then implement** to make a new, stable environment.

Managers do things right, leaders do the right things.

Good managers do not necessarily make good leaders, and good leaders can be poor managers. This is because the two jobs are not the same, despite sharing similar characteristics—principally the need to drive human (and therefore organizational) capacity. As Warren Bennis and Burt Nanus noted in 1985, "managers do things right; leaders do the right thing." Leaders "conquer" their surroundings—the competitive environment—through vision and strategy, and it is the role of managers to then implement these strategies effectively.

Effective management is crucial to organizational success. It takes care of processes, planning,

See also: The value of teams 70–71 ▪ Gods of management 76–77 ▪ Effective leadership 78–79 ▪ Organizing teams and talent 80–85 ▪ Develop emotional intelligence 110–11 ▪ Mintzberg's management roles 112–13

budgeting, structure, and staffing; tasks that help an organization to keep doing what it does. Without management, no matter how well led, an organization would disintegrate into disorganized chaos. However, management is not leadership—it will not lead the company in new directions.

Decisive leadership

In 1990, John Kotter argued that leadership is about dealing with change and developing a vision for the organization, often within turbulent times. Leaders then communicate their vision to the rest of the company, and motivate staff—especially managers—to act in ways that will bring about the required change. Leadership is about setting the agenda and empowering people to produce useful change.

"Leading well" does not always mean making people happy; likability and success rarely go together. The direct, tough, and sometimes even rude leadership styles of some of the most highly regarded leaders—such as Jack Welch of General Electric, Steve Jobs of Apple, and Jill Abramson of *The New York Times*—have been well documented.

Leaders have to be brave in the face of uncertainty, standing firmly behind their vision for the company. They need to hold staff accountable when things do not go as planned, and make difficult decisions about who to hire or fire in order to develop an organizational culture capable of achieving their strategic vision.

The next generation

Truly great leaders know that they will not be around forever, and one of their most important tasks is to hire, train, and nurture their successor. They lead well by making sure somebody is ready and waiting to take over from them. Nine years before his retirement, General Electric CEO Jack Welch said, "from now on, choosing my successor is the most important decision I'll make. It occupies a considerable amount of thought almost every day."

Jill Abramson was the first woman to become executive editor of *The New York Times*. She found that unpopularity came "with the territory," as *Times*' chairman Arthur Sulzberger had warned.

It is common practice in many companies to privilege leadership over management, but it is unwise. Great organizations value both: leaders who can spot opportunities, and managers who can make those opportunities a reality. ■

> Leadership is lifting a person's vision to high sights, raising their performance to a higher standard, building a personality beyond its normal limitations.
>
> **Peter Drucker**
>
> **US management consultant (1909–2005)**

Blending leadership and management

Inspirational leadership skills are the hallmark of Portuguese soccer coach José Mourinho. His teams won two European Cups and 14 trophies in eight years, elevating him to sit alongside some of the greats of soccer management.

Successful sports teams, like great organizations, are a blend of good management and good leadership, and Mourinho achieves the rare feat of excelling in both. As a leader, he makes his mark immediately. When he first took over Chelsea Football Club in London, England, he called a team meeting and urged any naysayers to speak up, or stay silent from then on. He learned his management skills from Bobby Robson and Louis van Gaal, for whom he worked as an assistant coach and translator at the Spanish soccer team FC Barcelona. Under their guidance he also learned how to study opponents, form strategies, and build strong, winning teams.

NONE OF US IS AS SMART AS ALL OF US

THE VALUE OF TEAMS

IN CONTEXT

FOCUS
Teamwork

KEY DATES
1924–1932 The Hawthorne Studies, conducted by Elton Mayo, highlight the importance of groups in affecting the behavior of individuals at work.

1930s The Human Relations Movement is sparked by Mayo's work. It proposes that worker satisfaction and productivity depend on careful management and consideration of groups.

1940s As a result of Abraham Maslow's findings, and the earlier work of Mayo, businesses begin to recognize the value of teamwork.

21st century Workplace design moves from the solo workspaces and closed offices of the 20th century to open layouts that encourage collaborative working.



Human beings like to **belong**.

Teams help to **generate a sense of place** and counter anomie.

None of us is as smart as all of us.

Organizations can be thought of as a **collection of teams**.

Successful teams **provide an environment** for new ideas.

We might complain about routine and familiarity, but research shows that human beings have an innate need for some degree of stability. Without rules, norms, values, and expectations, people begin to feel anxious, rootless, and confused. This is termed "anomie," and it is the reason that humans often self-organize into groups. The routine and familiarity of belonging to a group helps people to avoid anomie, and find security and purpose.

The existence of groups serves two purposes. Organizations, and the groups within them, can be seen as an expression of the human desire to belong. As psychologist Abraham Maslow identified in his 1943 paper "A Theory of Human Motivation", groups give us a sense

See also: Creativity and invention 72–73 ▪ Organizing teams and talent 80–85 ▪ Make the most of your talent 86–87 ▪ Organizational culture 104–09 ▪ Avoid groupthink 114 ▪ The value of diversity 115

of belonging. Maslow believed that there is a hierarchy of human needs; once we have met the most basic of needs—the physiological ones, such as hunger and thirst—we progress to the next: security. When these needs are satisfied, we move to the third basic need: a sense of belonging. Once this is met, we will proceed toward increasing self-esteem through achievement, and ultimately toward self-actualization, by using our inner talents with creativity.

When Maslow's theory is applied to the workplace, working in groups and gaining a sense of belonging make employees more effective. With the need to belong already addressed, individuals are able to focus on other things, such as a desire for achievement and the practicing of inner talents. In this way, the movement through the stages of satisfying needs can benefit a company. Free from anomie, groups are places where human beings, and therefore ideas, can flourish. Teams that are carefully chosen and supervised will increase an individual's security and encourage collaborative, creative, work—as US management expert Ken Blanchard said, "none of us is as smart as all of us." In turn, commitment toward a project creates ties that strengthen the bond between individuals and, ultimately, the company's communal purpose.

Cisco Systems uses workspaces that can be transformed from small groups of work pods to large open spaces for conferences. Cisco aims to be flexible for connectivity and a sense of community.

Places to belong

Great organizations recognize the value of teams and the importance of the working environment. Cisco Systems, the Internet infrastructure company, has created what it calls the "Connected Workplace", which offers employees great flexibility in working practice and environment, while ensuring that they always feel part of the Cisco community.

Business success is rarely achieved through individual genius, and the greatest leaders are those who recognize the value of maximizing talent through teams. ■

Abraham Maslow

The American psychologist Abraham Maslow was born in 1908. He grew up in Brooklyn, New York, and earned a degree, masters, and PhD in psychology from the University of Wisconsin. Maslow started his career as a teacher, working at Brooklyn College from 1937 to 1951, after which he became chair of the psychology department at Brandeis University, US. Here he met Kurt Goldstein, the originator of the idea of self-actualization, and Maslow became fascinated with the path of human development toward "being all you can be." Contrary to many of his peers, Maslow focused on the positive side of mental health. The hierarchy of human needs, which Maslow outlined in "A Theory of Human Motivation", remains influential even today in fields as diverse as social work and management theory.

Key works

1943 "A Theory of Human Motivation"
1954 *Motivation and Personality*
1962 *Toward a Psychology of Being*



INNOVATION MUST BE INVASIVE AND PERPETUAL: EVERYONE, EVERYWHERE, ALL OF THE TIME

CREATIVITY AND INVENTION

IN CONTEXT

FOCUS
Creativity

KEY DATES

17th century Polish poet Maciej Kazimierz Sarbiewski applies the word "creativity" to human activity. For more than a century and a half, the idea of human creativity is resisted—"creation" is reserved for describing God's creative act.

1970s Influenced by the work of psychologists Abraham Maslow and Frederick Herzberg on the subject of motivation, businesses begin to design jobs that allow employees space for creative freedom.

2010 IBM lists creativity as the most sought-after trait in business leaders.

2013 Bruce Nussbaum's book *Creative Intelligence* states that creativity is the greatest source of economic value.

Our fondest childhood memories are often those that involve the freedom of play, and the unbridled use of imagination to create and live out fantasies. As human beings we never lose the inner joy of creativity, but it tends to be suppresed by the responsibilities of adult life—we trade the playground for the office.

Like the playgrounds of our childhoods though, companies that embrace creativity and innovation as "invasive and perpetual"—as consultant Stephen Shapiro puts it—are exciting places to be. Google, Facebook, and Procter & Gamble, for example, are renowned for hiring and nurturing creative people, and for rewarding


The desire to **create and invent** is deeply embedded in all of us.
As children, creativity comes naturally...
...but for many adults, **it has to be worked at**.
For businesses, establishing a climate of perpetual creativity **motivates staff**...
...and improves the company's **competitiveness**.

See also: Stand out in the market 28–31 ▪ Gaining an edge 32–39 ▪ Thinking outside the box 88–89 ▪ Changing the game 92–99

imagination and invention. They attract thousands of applicants as a result. Moreover, creativity is not only a potential source for ideas that can yield economic value, but is a vital asset for individuals and companies operating in increasingly changeable global markets.

Defining creativity

Creativity involves the generation of ideas, alternatives, or possibilities, and the consideration of situations or problems in novel ways. Invention is the practical application of creative thought. When successfully realized, creativity and invention are highly motivating. They allow us to combine our innate desire for autonomy, purpose, and mastery. They also produce a sense of achievement, which is a key element in what Abraham Maslow described as the "Higher Order Needs" of motivation—the factors that allow us to feel value and self-actualization.

For businesses, establishing a climate of creativity has the dual benefit of enhancing employee satisfaction and improving its competitiveness. Excited by the pursuit of invention, employees will often work harder, longer, and more productively, yielding innovative solutions to problems, new cost-saving processes, or profitable new products.

So significant is the competitive edge that can be gained that a 2010 IBM survey listed creativity as the most sought-after trait in leaders. When it was announced that the Creative Director of Mulberry, Emma Hill—who was largely credited with the fashion label's renaissance—was stepping down in 2013, the company's shares fell by more than 9 percent. As Steve Jobs proved at Apple, "thinking differently" is not just cool or quirky—it matters to staff, to customers, and to investors.

> When you innovate, you've got to be prepared for everyone telling you you're nuts.
>
> **Larry Ellison**
>
> **US co-founder, Oracle Corp. (1944–)**

Fostering creativity

The challenge is for companies to balance creativity with financial prudence. Unbridled creativity rarely leads to commercial success, yet businesses are required to make profits in order to survive.

For Mulberry, it was a clash of these values that resulted in Hill's departure. When the joined company in 2007, Hill was responsible for some of the label's biggest hits—notably its Alexa and Bayswater handbags—and presided over a period of significant innovation and growth. In 2013 though, with sales falling, the brand's management decided it needed a new creative direction—even the most creative brands feel the need for reinvention.

As creative organizations know, to the benefit of their staff and the bottom line, creativity and invention—by everyone, everywhere, and all of the time—are vital ingredients for business success. ■

Emma Hill

UK-born fashion designer Emma Hill studied at the Wimbledon School of Art in 1989 before graduating from Ravensbourne College of Design and Communication in 1992. Starting her fashion career at luxury brand Burberry, Hill also worked for UK retailer Marks & Spencer, US fashion designer Marc Jacobs, and US retailer Gap, before moving to Mulberry—which has stores in Europe, US, Asia, and Australia—as Creative Director in 2007.

At Mulberry, Hill's creative talent for designing handbags carried by the likes of model Kate Moss and musician Lana Del Rey resulted in waiting lists for purchases. Thanks to her expansion of the brand into small leather goods (such as brightly colored card holders) in order to appeal to the more price-conscious end of the market, the brand enjoyed stellar growth. When she joined Mulberry the company's shares had stood at $1.78 (111 pence); at the time of her departure in 2013 they were worth nearly 10 times as much. In 2010, thanks to Emma Hill's work, Mulberry won the "Best Designer Brand" prize at the British Fashion Awards.

DISSENT ADDS SPICE, SPIRIT, AND AN INVIGORATING QUALITY

BEWARE THE YES-MEN

IN CONTEXT

FOCUS
Behavioral management

KEY DATES
1992 Indian economist Abhijit V Banerjee looks at how decision makers refer to the choices made by previous decision makers for guidance, in his book *A Simple Model of Herd Behavior.*

1993 US economist Canice Prendergast writes *A Theory of Yes Men*, identifying the tendency of subordinates to agree with their superiors as a "market failure."

1997 US psycholinguistics expert Suzette Elgin writes *How to Disagree without Being Disagreeable.*

2000s Leadership theory encourages leaders to embrace constructive conflict as a healthy, and necessary, part of the business environment.



If managers are only brought **good news**...

...they are forced to make decisions based on **incomplete or inaccurate** information.

Leaders should **beware "the yes-men"** and embrace constructive conflict in their companies.

Sometimes **"no" is ultimately more useful** than "yes."

For many employees, working within an organization means forever saying "yes." Fearful of losing their jobs, eager to please, and ambitious for promotion, subordinates are often happy to pass on good news, but reluctant to deliver bad news. This might be good for their manager's ego but it can be damaging for the business—if bad news is hidden, managers lack vital information and can make bad decisions as a consequence.

This can happen at the highest levels with catastrophic results. A Financial Services Report in 2012 on the Royal Bank of Scotland (RBS) suggested that the bank's failure in 2008 was, in part, due to "a lack of effective challenge by the board and senior managers to the CEO's proposals, resulting in risks being overlooked and strategic mistakes being made."

A tolerant business culture

Being an effective leader involves recognizing that it is impossible to be right all of the time. Seeking, and graciously accepting, critical feedback from trusted colleagues can help maintain a balanced perspective. The challenge for

See also: The value of teams 70–71 ▪ Hubris and nemesis 100–03 ▪ Effective leadership 78–79 ▪ Ignoring the herd 146–49 ▪ Learning from failure 164–65 ▪ Avoiding complacency 194–201 ▪ Creating an ethical culture 224–27

> In an organization where innovation happens, very often people ignore orders.
> **Robert Sutton**
> **US professor of management**

leaders is to create an environment where bad news is tolerated, and even encouraged. If leaders react to unwelcome news without screaming or recrimination, staff is more likely to be confident about delivering it. Good leaders tend to address the problem, rather than simply apportioning blame, helping to prevent a repeat scenario.

An important way of preventing a yes-men culture is to create a culture of collective responsibility. Often, the most valuable employees are those who are courageous and caring enough to tell the truth, no matter how bad it might be.

For employees, delivering bad news is a skill in itself. It is better if the news comes with a proposed solution attached, and with causes of the problem acknowledged rather than ignored. The news should be delivered promptly; the sooner a problem is identified, the sooner it can be solved, and the better a manager's reaction is likely to be.

Testing your ideas

Jean Paul Getty, founder of the Getty Oil Company, recognized the value of outspoken employees, claiming that "dissent adds spice, spirit, and an invigorating quality."

Ken Olsen, founder of Digital Equipment Corporation, built dissent into company culture, using debate and conflict resolution as the primary ways of decision making. Jack Welch, CEO of General Electric (GE), encouraged no-holds-barred debates, saying, "if the idea can't survive a spirited argument, the marketplace will surely kill it."

Saying yes to every task and giving only good news to a leader might result in popularity, but will soon overload the employee and risks blinded decision making by the leader.

Management teams that can challenge each other's thinking develop a richer understanding of strategic options, and, ultimately, make better decisions. The best business leaders attempt to harness criticism and debate. If everybody is saying "yes," something is seriously wrong. ■

Jean Paul Getty



Jean Paul Getty was born in Minneapolis in 1892. His father was a lawyer who moved into the oil business in 1903. Getty studied at universities in the US and UK before joining his father's business, The Minnehoma Oil Company. He set out to make a million dollars within his first two years, and did so by buying and selling oil leases.

Because Getty married five times, his disapproving father bequeathed him only $500,000 from his $10-million estate. Undeterred, Getty combined this with his own amassed earnings to buy several oil companies and build these into a pyramid of corporations, with the Getty Oil Company at the top. In 1949, he purchased a 60-year concession in a tract of land between Saudi Arabia and Kuwait that was thought to be barren of any oil. His company struck oil in massive quantities in 1953, making Getty a billionaire. He died in 1976 at the age of 83.

Key works

1953 *My Life and Fortunes*
1965 *How to be Rich*

NO GREAT MANAGER OR LEADER EVER FELL FROM HEAVEN

GODS OF MANAGEMENT

IN CONTEXT

FOCUS
Organizational dynamics

KEY DATES
20th century Typologies emerge to help management thinkers sort organizations into identifiable classifications, and individuals into distinct types. What motivates each person is thought to be determined by their "type."

1978 Charles Handy's *Gods of Management* proposes that understanding which classification an organization fits into is key to understanding the type of people it contains and, thus, the way to lead them.

1989 In *The Age of Unreason*, Handy puts forward the theory of the Shamrock Organization.

21st century Management thinking increasingly acknowledges that stylistic typologies are just one of many methods of understanding and managing companies and staff.

In his influential 1978 book *Gods of Management*, Charles Handy used the allegory of the gods of ancient Greece to describe the nature of organizations. Handy proposed that four management styles could be identified, a combination of which are likely to be present in every organization. Zeus represents the "club culture," in which relationships with the leader are more important than formal titles or positions. Apollo's "role culture" is defined by functions, divisions, rules, and rationality. In Athena's "task culture," power lies within teams who have the expertise to solve problems. In Dionysus's "existential culture," the organization exists to support the individual's needs.

Handy's typology provided an entirely new and original method for managers to analyze a company's dynamics, and to understand culturally embedded behaviors, biases, and beliefs. However, it soon became clear that because organizations are vast and diverse entities, and are seldom static, organizational behavior evolves over time. Under pressure externally and internally, most companies operate in a constant



Handy's Gods of Management reveals **different types of organizational dynamic**...

...but **organizations are complex** at institutional and the individual level.

Effective leadership requires God-like omniscience, but **no great leader ever fell from heaven.**

Therfore, **typologies can still be helpful** for understanding organizational and individual complexity.

See also: Leading well 68–69 ▪ Effective leadership 78–79 ▪ Organizational culture 104–09 ▪ Mintzberg's management roles 112–13



Charles Handy's Gods of Management

Zeus—
Club Culture
As the ruler of the Greek gods, Zeus was at the center of power and influence. Club cultures are built on affinity; proximity to the center of the club reflects an individual's standing within it. Investment banks often have dominant club cultures.

Apollo—
Role Culture
Apollo was the god of order and rules. Successful in times of stability, role cultures tend to flounder when rapid change is required. Insurance companies are among those typically led along Apollonian principles.

Athena—
Task Culture
Athena, the goddess of wisdom, was a problem-solver. Task cultures thrive where innovation is required, but struggle with routine. Advertising agencies and consultancies often display task cultures.

Dionysus—
Person Culture
Dionysus, the god of wine, stood for individual freedom. In person cultures, professional opinion is privileged and management is seen as an unnecessary burden. Professional service companies, such as legal firms, mirror Dionysian cultures.

state of flux—they adapt and change in unforeseen, unplanned, and unpredictable ways.

Accounting for complexity

Organizational complexity is often measured by the number of countries a company operates in, or the number of brands under a manager's control. Such institutional complexity is not insignificant; it pales though compared to individual complexity. For example, something novel that motivated a member of staff one year may not motivate them the next. When a company consists of a staff of thousands, it is clear that people, and therefore organizations, are more complex than the stylistic Gods of Management suggest.

Handy later wrote of the Shamrock Organization—a flexible organization made of core employees, peripheral outsourced staff, and an external, flexible work force. Each category of worker has a different commitment to the organization, a different understanding of its vision, and their own motivations for work. The job of leadership is to align these differences toward a common, organizational goal.

Organizational dynamics are important because people matter. Typologies only take a leader so far. Leaders must recognize that each employee perceives the company differently, and has unique drivers (and barriers) to effectiveness. As US businessman Tom Northup said, great leaders do not "fall from heaven," but God-like omniscience is a useful—albeit unreachable—goal to strive for. ■

Charles Handy

Professor Charles Handy, born in 1932, is Britain's best-known management guru. After graduating from Oxford University he joined the Massachusetts Institute of Technology in 1965, moving to the London Business School (LBS) in 1967 to run the only Sloan School of Management program outside the USA. Handy's challenging ideas, articulate style, and use of provocative imagery—such as his text *The Empty Raincoat*, a critique of the "impersonal mechanics of business organizations"—set him apart from his contemporaries. Handy sees himself as a social philosopher rather than management guru—his writings, he believes, are commentaries rather than manuals for success. His opinions have influenced business thinking for decades.

Key works

1976 *Understanding Organizations*
1978 *Gods of Management*
1994 *The Empty Raincoat*

A LEADER IS ONE WHO KNOWS THE WAY, GOES THE WAY, AND SHOWS THE WAY

EFFECTIVE LEADERSHIP

IN CONTEXT

FOCUS
Leadership

KEY DATES
1520s Italian diplomat Niccolò Macchiavelli's *The Prince* discusses the perils of leadership in political life.

1916 French executive Henri Fayol's work *General and Industrial Management* defines a leader as someone who "should possess and infuse into those around him courage to accept responsibility."

1950s and 60s The authoritative "Command and Control" school of management becomes popular. Charismatic leaders dominate organizations through force of personality.

1980s and 90s Leadership thinkers, such as US professor Warren Bennis, encourage a leadership style based on integrity, trust, and the ability to build an organization's capacity for change.



Effective leadership **builds capacity in others**.

A leader's charisma alone is not enough. **Effective leadership** requires the establishment of…

…**integrity, trust, empathy, and empowerment**.

Effective leadership requires **action from the leader**, not just brainpower.

For centuries scholars have attempted to determine the definitive styles, characteristics, and personality traits of great leaders. Yet, despite thousands of studies, effective leadership remains a subject of debate. However, one common theme is that effective leadership requires action, not just intellect.

Leaders cannot simply rely on charisma. While charismatic leadership has its place—for example, Henry Ford was renowned for his charismatic leadership style—there is a danger that rhetoric can exceed reality. Rather than empowering their employees, charismatic leaders often micromanage tasks and prevent their staff from gaining a sense of achievement from their work. Charismatic leaders are often heralded as champions of organizational success, but that charm can be a blessing and

See also: Leading well 68–69 ▪ Gods of management 76–77 ▪ Changing the game 92–99 ▪ Develop emotional intelligence 110–11 ▪ Mintzberg's management roles 112–13

Actively participating in business life, from the boardroom to the factory floor, is vital for effective leadership. Carlos Ghosn visited car assembly lines to build integrity and trust with staff.

a curse—the void created by the departure of a charismatic leader can be hard to fill. It may flatter the ego to be proclaimed a hero, but great leaders know that success involves building long-term organizational capacity that will outlast their own tenure.

Keys to effectiveness

To be effective, a leader must be confident and secure, and at the same time open and empathetic. Effective leadership involves the ability to create capacity in others through the process of interacting, informing, listening, developing, and trust-forming. Credibility of the leader is achieved through collaboration, not domination. Central to effective leadership is empowerment—the art of enabling other people to get things done.

One of the most effective contemporary business leaders is Carlos Ghosn, CEO of car makers Renault and Nissan. Within a year of his appointment in 1999, Ghosn returned Nissan to profitability and was credited with saving the company from collapse. This proved to be one of the most dramatic turnarounds in modern business history.

Among the leadership traits that contribute to Ghosn's effectiveness is his belief that leadership is learned "by doing." On joining Nissan as CEO he walked around every factory, meeting and shaking hands with every employee. To this day he remains a common sight on factory floors. Integrity and trust, Ghosn believes, are built when leaders are seen to be willing to "get their hands dirty" and remain in touch with the factory floor of the business.

Empowering staff

Leaders must communicate a strong vision but, above all, they must empower staff to make decisions themselves. In large, diverse organizations a leader cannot, and should not, make all the decisions—helping others to understand the necessity for change, and giving them the tools to manage that change is key to the leader's role. The success of Nissan is also attributed to Ghosn's ability to manage cross-cultural teams. Leaders, Ghosn suggests, require the ability to listen and to empathize, not just with employees from their own countries, but also with people from different countries and cultures.

Ghosn's insights illustrate that effective leadership requires putting vision into action. Achieving this requires more than just rhetoric: effective leaders must "talk the talk" and "walk the walk." ▪

Carlos Ghosn

Born in 1954, Carlos Ghosn, a French-Lebanese Brazilian, started his career with Michelin, moved to Renault in 1996, and was appointed the CEO of Nissan in 1999 following Renault's purchase of a substantial stake in the ailing Japanese company. At the time, Nissan's debts had reached $20 billion and only three of its 48 car models were generating a profit. Promising to resign if the company did not reach profitability by the end of the year, he defied Japanese business etiquette, cut 21,000 jobs, and closed unprofitable domestic plants. Within three years Nissan became one of the most profitable automakers, with operating margins of higher than 9 percent—more than twice the industry average.

Having presided over what has been described as one of the greatest turnarounds in business history, Ghosn was named "the hardest-working man in the global car business" by *Forbes* magazine in 2011.

> The universe rewards action, not thought.
> **Russell Bishop**
> **US executive coach**

TEAMWORK IS THE FUEL THAT ALLOWS COMMON PEOPLE TO ATTAIN UNCOMMON RESULTS

ORGANIZING TEAMS AND TALENT

IN CONTEXT

FOCUS
Teamwork

KEY DATES

1965 US professor Bruce Tuckman proposes that teams go through five stages: forming, storming, norming, performing, and adjourning.

1981 British management theorist Meredith Belbin writes *Management Teams: Why they succeed or fail*, describing nine distinct roles that are essential to team success.

1992 Peter Drucker describes three kinds of team in "There's more than one kind of team," published in *The Wall Street Journal*.

1993 Jon Katzenbach and Douglas Smith write *The Wisdom of Teams*, claiming that forming a team leads to greater success than individual efforts.

Effective teams are the key to great organizations. This is especially true in business, where teamwork merges individual talent into something greater than the sum of its parts, enabling "common people to attain uncommon results" in the words of US industrialist Andrew Carnegie.

Manufacturing companies in Europe and the US began to explore the idea of teamwork in the 1960s and 1970s, in response to the success of Japanese team-based working methods such as *kaizen* (staff are responsible for a company's continuous improvement) and "quality circles" (groups of staff tasked with improving quality). In the 1980s, as many companies adopted "total quality management" (organization-wide quality), teamwork began to spread beyond its genesis in manufacturing. Today, it would be rare to find an organization, of any type or size, that did not value teamwork.

The benefits of teamwork

Teamwork has been credited with bringing about substantial reductions in absenteeism, lower staff turnover, significant increases in profit, and improved job satisfaction. In Honeywell's commercial flight division in Minneapolis, for example, teamwork was credited with achieving an 80 percent market share in flight and navigation systems—and for generating profits that were 200 percent higher than projections.

> Members of a team seek out certain roles and they perform most effectively in the ones that are most natural to them.
> **Meredith Belbin**

Teams succeed because they provide an environment where weaknesses can be balanced out and individual strengths multiplied. Teams also safeguard against individual shortcomings, such as underperformance and personal agendas. Projects are more likely to stay on track when peers support each other and review each other's and the team's work. Teams also create an environment that most people enjoy. The security of a group makes each individual feel less exposed and, in turn, more likely to take risks, be more creative, and therefore be better able to perform.

Storming and norming

Effective teams take time to develop. It is rare that a group of people can come together and begin to perform immediately; most teams go through a series of stages before effectiveness is achieved. Bruce Tuckman, a US professor of

Meredith Belbin

Meredith Belbin was born in Beckenham, UK, in 1926. He earned a degree in Classics at the University of Cambridge, and then a doctorate in psychology, during which he did research on the importance of teamwork. He then took a research fellowship at Cranfield—where he studied the benefits of ergonomics (designing tools and systems that fit best with people's needs) and improving efficiency in production lines—before becoming a management consultant. Belbin studied teamwork in the UK, US, and Australia, and in 1981 wrote *Management Teams: Why they succeed or fail*, which became one of the world's best-selling management books. Belbin has advised the US government, the European Union, companies and public service bodies.

Key works

1981 *Management Teams: Why they succeed or fail*
1993 *Team Roles At Work*
2000 *Beyond the Team*

See also: Leading well 68–69 ▪ The value of teams 70–71 ▪ Effective leadership 78–79 ▪ Make the most of your talent 86–87 ▪ Organizational culture 104–09 ▪ Avoid groupthink 114 ▪ The value of diversity 115 ▪ Kaizen 302–09

educational psychology, described these stages as forming, storming, norming, performing, and adjourning. During forming, the group comes together, and members get to know one other. It then moves into a storming stage, where members challenge each other for coveted group roles, and group processes begin to emerge through trial and error. The middle stage—norming—marks a period of calm, where agreement is reached on roles, processes, and group norms. By the fourth stage, members have become familiar with each other, with their roles, and with the processes involved. At this stage, team performance hits its most effective level. Once their work is done, the group moves to adjourning, or disbanding.

Businesses are eager for teams to move quickly through the early stages, reaching "performing" as soon as possible. This is why companies invest so much in team-building activities, where teams face and solve artificial challenges, often in a different environment. Many companies also use the architecture of their building to encourage team interaction. For example, at Pixar, the movie animation studio based in California, the cafeteria, meeting rooms, employee mail boxes, and bathrooms are located around a centralized atrium designed for collaborative working. The building design and layout encourages members of teams to meet and interact with one another, even when they are based in different departments within the company.

Research has shown that team-building activities and collaborative work spaces help to improve team work because the most effective teams are those where members trust one another, share a strong sense of group identity, and have confidence in their effectiveness as a team.

Effective team building

In 2005, US researchers Jon Katzenbach and Douglas Smith identified a series of factors that seem to be essential for effective teamwork. First, team members must be chosen for their skills, not their personality. The team then needs to get off to a good start; setting the right tone is essential. The tone should not be too casual—teams perform better when challenged, so a sense of urgency needs to be imparted.

The team should agree on clear rules for group behavior and norms, and meet often, both formally and informally. If possible, the team should be allowed to enjoy some early success; a few easy wins early on has been found to boost performance later. Likewise, the group—and its individual members—needs to be lavished with praise. Continuing motivation »


Mutual support encourages team members to **reach their potential**.
Teams produce **more creative solutions** to problems.
Teams provide an **environment to manage talent**.
Effective teams provide synergy. **2 + 2 = 5**
Individual **shortcomings are balanced out** in a team.
Teams provide security, so members feel free to **take risks**.
Teams establish **positive group norms** that encourage openness and flexibility.

Belbin Team Inventory

Team role	Talent	Weakness
Plant	Creative, unconventional thinker who excels at solving problems	Not good at managing (or communicating with) less creative people
Resource investigator	Communicative extrovert who develops contacts and explores opportunities	Loses interest once initial enthusiasm has passed
Coordinator	Mature, confident person who is able to clarify goals and promote decision making	Can be manipulative and appear aloof
Shaper	Dynamic, outgoing, highly strung person who will challenge, pressure, and find ways around obstacles	Prone to provocation and short-lived bursts of temper
Monitor/ evaluator	Sober, strategic, discerning person able to see and judge options objectively	Lacks drive and ability to inspire others
Teamworker	Social, mild, perceptive and accommodating, this teamworker averts friction	Indecisive in crunch situations
Implementer	Disciplined, reliable, conservative, efficient person who can turn ideas into practical actions	Somewhat inflexible, slow to respond to new possibilities
Completer/ finisher	Painstaking, conscientious person who is always able to meet deadlines	Inclined to worry unduly, reluctant to delegate
Specialist	Single-minded, dedicated self-starter who brings knowledge or technical skills that are in rare supply	Contributes only on a narrow front

is encouraged by new challenges, since they help to keep the work fresh and engaging.

Successful roles

Individuals offer different talents and attributes, and these need to be taken into account when putting together teams. UK management theorist Meredith Belbin claims there are nine distinct roles within a team that are essential to team success, and that the key to a well-organized team is balance. For example, Belbin found that teams without Plants (creative, unconventional thinkers) struggle to come up with ideas; but if there are too many Plants, idea generation starts to take precedence over action. Similarly, if there is no Shaper (a dynamic, driven person who pushes the group toward decisions), teams lack drive and direction. But in a team with too many Shapers, arguments occur frequently and will lower morale.

Now an established business tool, the Belbin Team Inventory is frequently used by companies to maximize team effectiveness. However, many companies make the mistake of using it after teams have been formed; to work successfully, it must be used before creating a team.

Managing talent

Sir Alex Ferguson, former manager of Manchester United, one of the world's best-known soccer teams, is a master of building winning teams over and again, and his methods can be applied to the business environment. His team was bonded by a strong sense of shared mission—a desire to win. Players were cohesive on the field, because Ferguson demanded cohesiveness off the field. An exceptional team culture ran through the veins of every player

> Teams develop direction, momentum, and commitment by working to shape a meaningful purpose.
> **Jon R. Katzenbach**
> **Douglas K. Smith**

and every staff member. Ferguson realized the value of positive group norms. He was, for example, one of the first managers to ban the consumption of alcohol. Moreover, alongside a host of team-building activities—quizzes on the team bus, for example—he demanded ferocious loyalty. Players could expect unfailing public support from Ferguson and the team. Equally, players were expected to observe a code of media silence in regard to teammates. Anyone breaching this team ethic was quickly ousted.

Team management often involves dealing with large egos and highly talented people. Ferguson recognized that it was folly to rein in significant talent—players Eric Cantona and Cristiano Ronaldo were both encouraged to express their soccer-playing flair—but he also transferred highly skilled players who felt themselves to be more important than the team. Talent management is a source of frustration for many executives, because talented people often resist being managed, and it can be difficult to find challenges that keep them sufficiently motivated, while at the same time aligned with organizational goals. However, teams provide an environment where talent can thrive. By giving talented staff teams to manage, or—although risky—grouping talent together in teams, it is possible to stretch even the most gifted member of staff. Teams provide a framework and value system to which all members, however skilled or talented, must adhere.

Collective products

Businesses, like sports teams, face performance challenges for which teams are a powerful solution. This is because teams are not simply a group of people who work together; they are judged not by individual performance, but by their "collective work products." These are the pieces of work—which might be products, surveys, or experiments—that come about as a result of joint contributions. In *The Wisdom of Teams*, Jon Katzenbach and Douglas Smith defined a team as "a small number of people with complementary skills who are committed to a common purpose, set of performance goals, and approach, for which they hold themselves mutually accountable." No individual is responsible for success or failure, because no one acts alone. Teamwork encourages listening, responding constructively to the views of others, providing support, and recognizing the interests, skills, and achievements of the other team members.

Most successful teams are formed in response to a perceived threat or opportunity. When these arise, the role of senior leaders is to organize teams with clear purpose, balanced membership, disciplined procedures, and strong bonds, while giving them enough flexibility to develop their own timing and approach. By doing so, leaders create environments where individuals—and therefore the organization—are able to succeed and flourish. ■

Flying geese demonstrate the power of teamwork. By flying together, each one reduces air resistance for the ones behind. They rotate leadership and "talk" continuously by honking.

LEADERS ALLOW GREAT PEOPLE TO DO THE WORK THEY WERE BORN TO DO

MAKE THE MOST OF YOUR TALENT

IN CONTEXT

FOCUS
Work-force effectiveness

KEY DATES
1959 US psychologist Frederick Herzberg defines factors in job satisfaction in his study *The Motivation to Work*.

1960 In his book *The Human Side of Enterprise*, US academic Douglas McGregor proposes Theory Y, urging companies to adopt a participatory management style that motivates workers to strive to achieve their potential.

1989 US management guru Rosabeth Moss Kanter's *When Giants Learn to Dance* suggests that employees are most productive when empowered to make their own decisions.

Staff in many organizations reports feeling undervalued, overstretched, and forced to work in areas beyond its competence. Because of this they feel ineffective—they want to work better, but feel that the organization is constraining them. The best companies allow staff to build careers around what they excel at—in leadership expert Warren Bennis's words "to do the work they were born to do."

Contemporary organizations, faced with dynamic, fast-moving markets, favor employees who are flexible and multiskilled. Yet in a 2012 Global Work force Study only 35 percent of employees reported engagement with their jobs, revealing a disconnect with what employers want and what employees are willing to give. Studies have found engaged employees—those devoted to their jobs and committed to the company's values—are significantly more productive, provide better customer service, and outperform those who are less engaged. But many companies treat staff as little more than pieces on an organizational chessboard that can be moved around at will.

Effective people create **effective organizations**.

↓

Great leaders allow great people to excel at what they do well.

↓

They **value the factory floor** as much as the shareholders.

See also: Leading well 68–69 ▪ Creativity and invention 72–73 ▪ Effective leadership 78–79 ▪ Organizing teams and talent 80–85 ▪ Is money the motivator? 90–91

Google's innovative, dynamic culture, in which staff are encouraged to work to their strengths and explore projects that they are passionate about, is one of the reasons for the company's success.

In his two-factor theory, US psychologist and management thinker Frederick Herzberg identified a sense of achievement as being closely linked to motivation to work. Effectiveness is intrinsically rewarding; even the most generous salary cannot, over the long term, replace the satisfaction of a job well done. The same generous salary will not offset the dissatisfaction of underachievement. Consequently, equipping employees with the tools to develop effective habits can lead to more effective performance, happier, more productive staff, and, in turn, improve a company's results.

Working better, not harder

Google, borrowing from a practice introduced by US conglomerate 3M in 1948, encourages staff to spend 20 percent of their time on projects of their own choosing. Rather than distract from directed projects, Google found that their staff works better on all tasks—when people are passionate about their work, it does not feel like work. Such discretionary effort, the willingness of employees to "go the extra mile," can be the difference between good and great. Great businesses focus on getting the best out of people, not the most out of them. Gmail, one of Google's most popular products, is a result of the company's 20-percent time.

Enabling staff to work better, not harder, requires an enlightened leadership approach that looks down to the factory floor as well as up to the shareholders. Companies that value effectiveness over volume, and performance over presenteeism (when staff works despite illness, instead of taking sick leave) often find themselves at the top of best-employer lists. Leaders of these companies realize that shareholder value is driven by staff performance; allowing staff to build careers around what they excel at is good for employees and the bottom line. ■

> “The man who does not work for the love of work, but only for money, is likely to neither make money nor find much fun in life.”
>
> **Charles M. Schwab**
>
> **US industrialist** (1862–1939)

Warren Bennis



Born on March 8, 1925, Warren Bennis is an American scholar, organizational consultant, and management author. Enlisting in the US Army in 1943, Bennis was one of the youngest infantry officers to serve in World War II, and was awarded the Purple Heart and Bronze Star for service in action. After leaving the military, Bennis studied at Antioch College, Ohio, and later became a professor at the Massachusetts Institute of Technology's Sloan School of Management. Widely regarded as the pioneer of the contemporary field of leadership studies, Bennis was named one of the ten greatest influencers on business thinking by *BusinessWeek* magazine in 2007. The *Financial Times* lists his classic 1985 book *Leaders* as one of the top 50 business books of all time.

Key works

1985 *Leaders: Strategies for Taking Charge*
1997 *Why Leaders Can't Lead: The Unconscious Conspiracy Continues*
2009 *On Becoming a Leader*

THE WAY FORWARD MAY NOT BE TO GO FORWARD

THINKING OUTSIDE THE BOX

IN CONTEXT

FOCUS
Innovation

KEY DATES
1914 The nine-dots puzzle is published in Sam Loyd's *Cyclopedia of Puzzles*.

1967 Edward de Bono coins the term "lateral thinking" to describe the process of the "horizontal imagination," which has a broad sweep but is unconcerned with detail.

1970s There is a surge of management consultants encouraging creativity. Strategic thinking is said to embrace retrenchment and retreat.

2012 Jeff Bezos of Amazon claims that "if you're inventing and pioneering, you have to be willing to be misunderstood for long periods of time."

The competitive pressures that businesses face are constantly in flux: new ideas and disruptive technologies emerge, the economic power of countries shifts, and market dynamics change. Yet business history is littered with companies that ignored change and pushed forward with flawed strategies based on the old environment. To avoid this, the idea of "thinking outside the box" is used to challenge precepts and assumptions—to consider that sometimes, the way to move forward is not to move forward at all.

The idea of thinking outside the box emerged in the 1960s and is based on the nine-dots puzzle, a game that was used by management



Markets are dynamic; technologies and competitive pressures **change**.

For businesses to survive, leaders must motivate staff to **avoid fixed thinking**.

Thinking outside the box is a leadership tool that encourages **creative responses** to problems.

Sometimes the way to move forward is not to move forward at all.

See also: Gaining an edge 32–39 ▪ Keep evolving business practice 48–51 ▪ Creativity and invention 72–73 ▪ Changing the game 92–99 ▪ Forecasting 278–79 ▪ Feedback and innovation 312–13

Nintendo's Wii console is a product of lateral thinking. Rather than taking on their industry rivals head on, the Wii's designers redefined gaming as a family-friendly, social activity.

The nine-dots puzzle challenges players to connect the nine dots with four straight lines or less, without lifting pen from paper or tracing the same line twice. The solution involves drawing lines "outside the box."



consultants to encourage lateral thinking. Several of its solutions involved drawing lines that were literally outside the puzzle's box. The phrase was adopted to represent any kind of creative thinking that goes beyond the obvious. Today, thinking outside the box represents innovation, the need to be aware of market changes, and the need to avoid fixed ways of thinking.

The bold retreat

Linear thinking—the opposite of thinking outside the box—has been responsible for the downfall of many businesses. MySpace, a website that dominated the online social-media market in the early 2000s, is an example of a business that fell victim to strategic *retrenchment*—sticking to a failing strategy rather than adapting to new competition or a changing marketplace. Purchased by News Corp for $580 millon in 2005, the business was sold in 2011 for $35 million, having failed to match the creative vision of Mark Zuckerberg's hugely successful Facebook. The future survival of MySpace depended on new thinking—it turned its business around by successfully refocusing on a core market of creative music professionals, leaving the social-media mass-market to Facebook.

Other companies have employed leaders with a more radical approach to guide them through fast-changing times. Nintendo's response to the technological superiority of the X-Box and Playstation, for example, was to think differently. Instead of competing on the usual grounds of price and increasingly sophisticated games, the Nintendo Wii created a whole new market. Its unique player interface—with a range of handheld, wireless controllers—and focus on group-based gaming made it family-friendly; suddenly gaming was a social activity for gamers of all ages and experience levels. The console quickly outsold the competition in almost every territory.

> BT should have invented Skype. But they didn't because the concept of a free platform totally disrupts their business model.
>
> **Alan Moore**
>
> **US systems expert**

Leaders taking this kind of "bold retreat" willingly cede technological advantage or market position to the dominant player, pursuing instead less vulnerable (and often more profitable) market positions.

Rethinking the box

Some business leaders believe that even creative thinkers may take certain things—such as organizational structure—for granted. They are therefore encouraging their staff to think literally "beyond the building" for new ideas. Procter & Gamble CEO A G Lafley sent employees to live temporarily in the homes of consumers to better understand their needs and identify product opportunities. The box itself, it seems, is perhaps a distraction. ■

THE MORE A PERSON CAN DO, THE MORE YOU CAN MOTIVATE THEM

IS MONEY THE MOTIVATOR?

IN CONTEXT

FOCUS
Motivation

KEY DATES
1914 Henry Ford doubles wages at Ford Motor Company in an effort to reduce labor turnover. Thousands apply for jobs with the company.

1959 Fredrick Herzberg proposes his theory that "motivators" and "hygiene factors" lead to satisfaction or dissatisfaction at work. He stresses that pay demotivates, but it does not motivate.

2000s "Best Employer" lists reveal that the highest ranked companies are often not those offering the biggest salaries.

2012 *Fortune* magazine cites Google as the best organization to work for in the US, and it also tops the list of employers in developing countries, including India. High salaries and a range of perks contribute to staff satisfaction.

When present, **motivators**—such as recognition, professional growth, and responsibility—can contribute to job satisfaction.

If poorly managed, **hygiene factors**—such as pay, conditions, supervision, and security—can increase job dissatisfaction.

Money matters, but **workplace motivation** is much more complex than financial reward alone.

If you were paid more, would you work harder? The answer is probably partly yes, and partly no. Higher pay might encourage you to move to a new job or to work a little faster or harder, but this focus is soon eroded—or equally, magnified—by other factors, such as job satisfaction, respect from managers, and the challenge presented by the work itself.

Financial gain can move us to do things, but motivation is more complex than money alone. US psychologist Professor Frederick Herzberg began to study workplace motivation in the 1950s while teaching at Case Western Reserve University, OH. In 1959 he proposed the "two-factor theory"—that a series of "motivators" encourage job satisfaction, while aspects of work termed "hygiene factors" contribute to dissatisfaction in the workplace if they are poorly managed.

Removing dissatisfaction

Hygiene factors include working conditions, job security, relationships with other workers, and salary.

See also: Leading well 68–69 ▪ The value of teams 70–71 ▪ Creativity and invention 72–73 ▪ Effective leadership 78–79 ▪ Make the most of your talent 86–87



Herzberg's two-factor theory illustrates the dichotomy of workplace motivation—that for the most part, job satisfaction derives from fulfilment of a different set of factors (“motivators”) than those that cause dissatisfaction (“hygiene factors”).

Motivators include recognition, responsibility, the opportunity for advancement, a sense of personal achievement, and potential for growth—as Herzberg put it “the more a person can do,” the more easily they can be motivated.

Herzberg argued that job dissatisfaction is as important as satisfaction. He believed that unless hygiene factors were well managed, no matter how good the motivators, staff would not be inclined to work hard. They would, he suggested, be so dissatisfied as to be demotivated. He also believed that hygiene factors do not, in themselves, motivate; but when fulfilled, they reduce dissatisfaction and provide a foundation for motivation. On the other hand, motivators have great potential to increase job satisfaction, but when lacking, actually only result in low levels of employee dissatisfaction.

Motivators in practice

Herzberg's findings are significant for business leaders. The two-factor theory proposes that job design is crucial—it must create conditions in which employees can feel a sense of achievement, enjoy responsibility, and gain recognition for their work. Levels of pay may be important for recruitment and retention, but it is less important in encouraging staff to work effectively.

Every day, thousands of people around the world apply for jobs at fast-food outlet McDonald's. Frequently rated at the top of “best employer” lists, the chain is popular because of a friendly working environment and flexible working policies. Initiatives such as the “friends and family contract”—in which employees from the same family or friendship group can cover each other's shifts—give staff a sense of shared responsibility, and enhance loyalty to the company.

The top-paying companies are rarely ranked as the best employers. Money matters, but job satisfaction, career advancement, management attitude, and personal relations are the workplace factors that most motivate us to work harder. ■

Frederick Herzberg

US psychologist Frederick Herzberg was born on April 18, 1923. He attended City College of New York and later held a professorship at the University of Utah, USA. Herzberg's service in the US Army, in particular his observation of conditions at the Dachau concentration camp in Germany during World War II, is thought to have inspired his interest in motivational theory.

Challenging the notion that workers are driven only by money and other benefits, Herzberg suggested that achievement and recognition are powerful motivators. He believed that managers should create safe, happy workplaces and make tasks interesting, challenging, and rewarding. His work influenced a generation of managers.

Key works

1959 *The Motivation to Work*
1968 *One More Time: How do you Motivate Employees?*
1976 *The Managerial Choice: To Be Efficient and to Be Human*

BE AN ENZYME— A CATALYST FOR CHANGE

CHANGING THE GAME

IN CONTEXT

FOCUS
Innovation

KEY DATES

1997 US professor Clayton M. Christensen introduces the concept of "disruptive technologies"—major and unforeseen technological advances that cause companies to redefine how they operate.

2000s Global Positioning System (GPS) navigational technology emerges as a disruptive innovation in a range of industries, from travel and fitness to recreation and smartphone applications.

2014 US professor of business administration David McAdams writes *Game-Changer: Game Theory and the Art of Transforming Strategic Situations*. McAdams uggests that game-changers are those who are "determined enough to change the game to their own advantage."

The business people we remember are those who do things differently—people such as Facebook CEO Sheryl Sandberg, US investor Warren Buffett, Hong Kong business magnate Stanley Ho, British entrepreneur Richard Branson, and US media giant Oprah Winfrey. Similarly, the companies we remember are those whose products and services stand out. Companies that shuffle along with the crowd, doing the same thing in the same old way, are soon forgotten; those that disrupt industries and change the game are celebrated, sometimes even idolized.

In today's global market, competition is fierce and every percentage point of market share is hard fought and precious. Operating in these markets is often a zero-sum game: competition drives prices down and costs up. Gaining a significant competitive advantage requires more than gradual improvement, it demands radical and disruptive shifts—if you cannot win the game, move the goalposts. Redefining the rules and boundaries of an industry is the essence of game-changing business strategy.

> “
> I want to put a dent in the universe.
> **Steve Jobs**
> ”

Thinking one step ahead of customers and competitors disrupts the status quo in a business's favor.

Disruptive innovation

Harvard Business School scholar Clayton Christensen identified two types of technology that can influence businesses: "sustaining technologies," or advances in technology that help companies make gradual improvements to product performance; and "disruptive technologies," radical advances in technology that disrupt the industry and force companies to rethink their entire mode of being. Christensen later changed the term "disruptive technology" to

Steve Jobs



Entrepreneur and inventor Steven Paul Jobs was born on February 24, 1955 in San Francisco, California, US. In 1976, at the age of 21, he and Steve Wozniak started Apple Computers (from the garage in Jobs's home). The business went public in 1980, with a market value of $1.2 billion.

In 1985, after disagreements with the board, Jobs was fired by recently appointed CEO John Sculley. Jobs nevertheless went on to found NeXT Computer and invest in Pixar Animation Studios, which was to become hugely successful. In a twist of corporate fate, Apple bought NeXT in 1996 and Jobs returned to Apple later that year, becoming CEO in 1997. In 1998 Jobs launched the iconic iMac computer and went on to preside over one of the most famous corporate renaissances in history. Under his guidance, Apple led the way with innovative product design and technology to become one of the most valuable technology businesses in the world.

In 2010, Steve Jobs was 61st in *Time Magazine*'s "100 People who Changed the World." He died on October 5, 2011.

See also: Stand out in the market 28–31 ▪ Gaining an edge 32–39 ▪ Creativity and invention 72–73 ▪ Thinking outside the box 88–89 ▪ Leading the market 166–69 ▪ The value chain 216–17 ▪ Creating a brand 258–63

Today's markets are increasingly **global**...

...and increasingly **competitive**.

Gradual change can only bring **gradual improvement** to a company.

But successful leaders **embrace** radical, **disruptive thinking**...

...they **redefine the markets** in which they operate.

They are catalysts for change.

"disruptive innovation" to reflect the fact that it is not so much technology itself that is disruptive as how that technology is applied.

One such product that has changed the game by adapting technology for new purposes is GlowCap. A screw-on top that can be attached to prescription medicine containers, GlowCap contains a glowing LED and audio alert that signal when medication should be taken. It also connects via Wi-Fi to the user's smartphone, sending a text message or an email alert if a dose is missed. Like many game changers, it utilizes lateral thinking to present a solution to an existing problem, effectively meeting the consumer's needs. Disruptive innovation creates the need for a product, even before customers realize such a need exists, and opens up new, untapped markets with significant first-mover advantages—not least of which is brand association with the new market segment. The German company Siemens, for example, built the world's first electric elevator in 1880, and in 1881 provided power for the world's first electric street lights (in

Exploring tomorrow's cities today
Crystal

The Crystal is one of the world's most sustainable buildings. Built in the UK by Siemens, it symbolizes the spirit of innovation that has been the hallmark of the company since the 1880s.

Disruptive innovation refers to an innovation that transforms the market. When an existing product boasts more features or services than customers require, it may become too complex or difficult to use. As the gap between the existing product's performance and customer requirement grows, it creates a gap in the market that can be exploited by a new, "disruptive" product. Over time, the new product can redefine the market.



Godalming, England). More recent game-changing products in lighting, energy, transportation, and healthcare have ensured that the Siemens name is associated with quality and innovation.

Leaders like the company's founder, Werner von Siemens—those with the vision and courage to pursue game-changing strategies—are, however, all too rare. It takes great courage to break from tradition; and charisma and conviction to lead individuals, organizations, and entire industries away from the status quo. Success is met with reward and celebration; failure with ridicule and scorn. For would-be game changers, the line between fame and infamy is often thin.

Rewriting the rules

Another company that has changed the game in its favor, on several occasions, is Apple. Under the guidance of its co-founder and CEO, Steve Jobs, the organization disrupted the desktop computer industry, the music industry, the cell-phone industry, and the tablet-computer industry.

Apple's iMac, with its focus on user-friendly design and software, made a significant impact on the personal computer industry. However, Apple's first major game changer was the iPod, first introduced in 2001. The product was met with scepticism—but this, according to Christensen, is a classic reaction to a game changer. A product that is accepted at first glance as a "winner" is unlikely to have shifted the market very far—true game changers raise eyebrows and prompt questions.

> You cannot lead from the crowd.
> **Margaret Thatcher**
> **UK former Prime Minister (1925–2013)**

Interfacing technologies

The iPod was a cross between the early crop of low-storage MP3 players and the large, hard-drive-based players that provided several gigabytes of storage. Amid a sea of bland competing products, the iPod stood out thanks to its stylish and distinctive design. It was small, easy to use, and came with the promise of "1,000 songs in your pocket."

The real disrupter, however, was the combined power of the iPod and its software interface, iTunes. Customers could now access a huge amount of music from one place, buy it, download it, and "sync" music from their computer to their devices with ease. The iPod could also be charged while syncing. The fact that we now take such features for granted demonstrates the extent to which Apple transformed the market for personal-music devices.

The iTunes Music Store (now the iTunes Store) redefined the music industry in 2003. At the time, digital music piracy was on the rise; record labels were fighting against digital distribution for fear of losing control and further damaging already declining revenues. Jobs exploited the record executives' nervousness to his advantage, offering people a way to purchase music legally but easily and instantly.

Apple's software changed the music industry's business model forever. In addition to changing the way we access and listen to music, iTunes enabled people to buy single tracks from albums. Artists no longer needed to slave for months on albums, but could release a steady stream of singles instead. Consumers no longer felt trapped into album purchases and felt less need to search for free, pirated downloads in place of legal versions.

The iTunes Store and the iPod system, quite simply, worked for consumers, who had been baffled by the many MP3 players and online methods of finding music. Apple simplified the process, and made its solution aesthetically appealing at the same time. By 2013, its strategy had brought sales of around 400 million iPods and more than 25 billion iTunes Store downloads.

Continually game-changing

Such radical disruption, if achieved only once, could be put down to good luck, but true game changers are those who persistently seek to separate themselves from the competition. Steve Jobs was not content merely to have changed the music industry: in 2007 he turned his attention to the cell-phone industry. Cell phones had been getting smarter for a while, but the iPhone was a giant leap forward. Offering users access to a suite of computer-like applications and, in particular, seamless Internet access, it was an instant hit. The real breakthrough was the iPhone's touch-screen technology. Jobs called the iPhone "a revolutionary product," claiming it was "five years' ahead of any other cell phone." His words were prophetic: for some years after, the iPhone remained the standard against which all other cell phones were assessed and defined.

Shortly before his death in 2011, Jobs did it again—this time with the iPad. Launched in April 2010, to confusion and some cynicism, the iPad came to (re)define the industry. It extended access to technology beyond its accepted business, educational, and »

> It's kind of fun to do
> the impossible.
> **Walt Disney**
> **US entrepreneur (1901–1966)**

The Apple logo has become a global emblem of the modern age—an indication of the extent to which the organization has revolutionized technology and product development.

> What today seems odd, unnecessary, offbeat—maybe even outrageous—may prove integral to solving tomorrow's problems.
> **Pierre Omidyar**

desktop-bound roots, in a format that few, at first, expected to be popular. The iPad ushered in a new era of computing, and remains, even in an increasingly crowded tablet-computer marketplace, the industry standard.

Corporate culture

Apple has changed the game so significantly that the brand has entered the cultural zeitgeist: its products are seen everywhere—from coffee shops and classrooms to television shows. Apple's technology has made its products ubiquitous and its customers fanatically brand loyal. With such a competitive edge, it is no surprise that the company's prices are able to sit well above industry averages.

But the challenge for any organization is to ensure that such game-changing mentality informs the spirit of the whole company. As French businessman Pierre Omidyar, founder of the online auction site eBay, suggests, a leader must be "a catalyst for change." But to be truly successful, and to outlive the tenure of a highly driven leader, the desire to disrupt must be pervasive. The energy, innovation, and courage required to repeatedly disrupt industries must be deeply ingrained in the corporate culture, which must also allow for flexibility to change.

In the case of eBay, Omidyar realized that the future was unpredictable and nonlinear, and decided to structure his new venture with the approach of a software engineer (his former job), "who has learned to strive for flexibility in design." While a software program might seem initially to provide more than its customers need, this is what gives it the flexibility to change and "prepare for the unexpected." Ebay's self-sustaining system required little intervention and was able to adapt and grow according to customer needs. Its design effectively embedded disruption within the core structure. The idea of allowing users to rate each other was both new and risky—as was a business model that required users to do most of the work. These features nevertheless ensured that eBay evolved not only around Omidyar's ideas and energy, but also around the requirements of the entire eBay community.

> Problems cannot be solved at the same level of awareness that created them.
> **Albert Einstein**
> **German-born physicist** (1879–1955)

Embracing failure

However, such deeply embedded game-changing mentality is rare. Heroic leaders—game changers and risk takers—are difficult to find and even more difficult to replace. With fewer than one in ten new product ideas making it to market, people

eBay
eBay Live!

Pierre Omidyar, chairman and founder of the popular auction site eBay, has embedded the desire for innovation and dramatic change within his company's corporate culture.

are rarely brave enough, or confident and committed enough in their ideas, to stake their careers and reputations on risky game-changing innovations. The heroic leader's strength lies not just in their vision, but also in their willingness to stand in the spotlight when things go wrong.

Corporate history is littered with examples of failed products. Most businesses are therefore, by nature, risk averse. Even Apple has made mistakes—and, again, its example is instructive. Jobs may be best remembered for transforming the music, computer, and phone industries, but he'll also be remembered as the poster boy for embracing failure, and bouncing back from it. He has reigned over a long list of failures. The Pippen games console, for example, was unable to compete with the likes of Sony's Playstation, and was quickly dropped. The Apple III computer suffered major design faults, and the Lisa—a computer that would eventually provide the basis for the iMac—had poor sales. The Apple Newton, a forerunner of today's smartphones, was a flop.

These failures led to Jobs being fired in 1985. In a speech to students graduating from Stanford University in 2005, Jobs stated that the dismissal triggered him to change his own game: "The heaviness of being successful was replaced by the lightness of being a beginner again, less sure about everything. It freed me to enter one of the most creative periods of my life."

History is filled with examples of trailblazers who stumbled before finding success. KFC chicken, invented by Harland David Sanders, was rejected by more than 1,000 restaurants; R. C. Macy opened and closed many stores before founding the largest department store in the world; Walt Disney's Laugh-O-Gram studio went bankrupt in 1923; and Henry Ford had three failed businesses before finding success. Game changers such as Albert Einstein (labeled "slow" by his teachers) and billionaire Oprah Winfrey (told she was not "fit to be on screen") seem to defy the future mapped out for them.

Challenging the status quo

African-American businessman John H. Johnson had the acumen to recognize the untapped potential for publications aimed at the African-American market. Excelling at high school despite an impoverished upbringing, Johnson won a scholarship to the University of Chicago and supported himself with an office job at an insurance company. It was while at work that he came up with the idea for *Negro Digest* (later renamed *Black World*), a magazine that would feature African-American history, literature, arts, and culture. It was a rapid success, reaching a circulation of 50,000 in only six months. A second magazine, *Ebony*, was founded in 1945, and at its height reached a circulation of more than 2 million. Thanks to his willingness to challenge the status quo, Johnson built a publishing empire that included radio, television, and books. He was named in the *Forbes* 400 list of wealthy Americans in 1982.

Long-term thinking

It is the ability to recover from failure, and maintain the courage and conviction to keep changing the game, that sets great leaders apart from the rest. From a strategic point of view, a focus on game-changing innovation encourages long-term thinking. Adopting such a strategy means that shareholders must be tolerant of risk and uncertainty, and patient with regard to returns; payback periods may be long, and rewards difficult to measure. But if allowed to flourish, this longer-term approach enables a business to build a stronger brand, invest in research and development, create better business processes, and avoid taking (possibly damaging) actions to boost short-term profits.

> You have to be willing to be misunderstood.
>
> **Jeff Bezos**
>
> **US entrepreneur (1964–)**

As Christensen's *The Innovator's Dilemma* suggests, game-changing leaders are not bound by incremental change and "me-too" thinking: they rewrite the terms of competition by embracing unique ideas, and recognize that in a corporate world characterized by the mantra "change or die," disrupting the status quo in your own favor puts you not just one step, but several steps ahead of the competition. In today's hypercompetitive markets, game-changing leaders do not simply outthink, outsmart, and outcompete their rivals—they move the goalposts and redefine the rules of the game. ■

THE WORST DISEASE THAT AFFLICTS EXECUTIVES IS EGOTISM

HUBRIS AND NEMESIS

IN CONTEXT

FOCUS
Success and failure

KEY DATES
c.500 BCE The ancient Greeks coin the term "hubris" to describe a form of pride that loses touch with reality and leads to "nemesis"—a fatal retribution or downfall.

2001 Kenneth Lay, CEO of Enron, sends employees an email saying "our performance has never been stronger." Four months later, Enron files for bankruptcy.

2002 US activist Herbert London claims that hubris is as great a danger in the 21st century as in ancient Greece.

2009 Jim Collins identifies five stages of corporate decline in *How the Mighty Fall*.

Even iconic companies can falter, fail, and become irrelevant. History repeatedly shows that successful corporate goliaths—such as Swissair, Enron, and Lehman Brothers—can fall from greatness. The list of possible causes is long and includes management complacency, poor marketing, poor products, strategic blindness, a weak economic environment, or simply bad luck. However, in many cases, paradoxically, success is the catalyst for failure.

This is because success can lead to an overconfidence that blinds business owners and managers to the real state of affairs. Meanwhile, they also start to

See also: Reinventing and adapting 52–57 ▪ Beware the yes-men 74–75 ▪ Good and bad strategy 184–85 ▪ Avoiding complacency 194–201


Success breeds confidence.
Great success can lead to **overconfidence**.
This can **make managers blind** to changes that begin to affect the company.
Greedy for more success, managers force the company to **overreach**.
Problems and pitfalls are swept aside as irrelevant or mere blips.
By the time management realizes there is a **major problem**...
...it may be **too late** to save the company.
The worst disease that afflicts executives is egotism.

believe their own hype. Internal warning signs may be present long before management—buoyed by seemingly unstoppable success—notices or chooses to do anything about them. Hubris, a kind of blind pride, can shield people from seeing that a company is already on the path to corporate catastrophe.

Five stages of decline

Jim Collins identified five stages of corporate decline. In stage 1, the business is doing well, perhaps exceptionally well. Press coverage is positive, finances are good, and morale is high. However, as a result of such success, during stage 1 the first warning sign appears—the company's directors and staff start to become overconfident. In highly successful companies there is a risk that staff members will become arrogant, and will begin to regard their success as a right or entitlement. Managers lose sight of the underlying factors that created success in the first place, overestimating their own strengths and those of the business.

If stage 1 is a feeling that "we're so great, we can do anything!" stage 2 is characterized by the feeling that "we should do more!" Collins calls this stage the "undisciplined pursuit of more": more sales, more stores, more growth, more of everything. »

Jim Collins

Business consultant, author, and self-titled "student of great companies" Jim Collins was born in the US in 1958.

Collins holds degrees in business administration and mathematical sciences from Stanford University, and several honorary doctoral degrees. He has worked alongside senior executives and CEOs at corporations of all types—from health care, education, and the arts, to religious organizations and government. His interest lies in the difference between good and great: how do companies attain such superior performance?

In 1995 he founded a management laboratory in Boulder, Colorado, to do further research into business excellence. His books have sold more than 10 million copies globally and have been translated into 35 languages.

Key works

1994 *Built to Last*
2001 *Good to Great: Why Some Companies Make the Leap … And Others Don't*
2009 *How the Mighty Fall: And Why Some Companies Never Give In*

Continued management arrogance breeds indiscipline; decisions are made out of greed and warning signs are ignored. Companies at stage 2 make indisciplined leaps into areas where they have little competitive advantage; diversify into areas in which they have no expertise; or undertake ill-conceived mergers and takeovers. The complacency of stage 1 turns into the overreaching of stage 2.

By stage 3, problems begin to mount, staff begins to question management decisions, and disturbing data suggest things might not be all that they seem. However, as Collins points out, it is possible to be in stage 3 of decline and not yet realize that it is happening. Anomalies in performance at this stage tend to be explained away; any problems are blamed on "difficult trading conditions." Management holds firm in the view that the company is strong and nothing is fundamentally wrong. They believe that once the markets pick up, their business brilliance will ensure that the company regains market leadership.

"Rogue trader" Jérôme Kerviel claimed his company, Société Générale bank, was aware of his dangerously large trades, but turned a blind eye because they were focused on profits.

Now or never

Stage 3 represents the turning point. Many companies reach this stage but manage to avert collapse. If management listens to the views of its staff (especially from the front lines, such as sales staff), heeds shareholder concerns, and changes strategy in line with the changing reality, it is likely to recover. Andy Grove famously pulled Intel back into profitability by pursuing this strategy. However, the same cannot be said for Lehman Brothers. In 2007, with its stock price at a record high, the US investment bank ignored the early warning signs of collapse. Even as cracks in the US housing market became apparent, with subprime mortgage defaults rising to a seven-year high, Lehman continued to expose itself to mortgage-backed financial products. Management, particularly the chief executive, Richard Fuld, were blinded by hubris and deep in denial. They pressed on with ill-conceived strategies and quickly found themselves in stage 4.

Dealing with disaster

By stage 4 a company's difficulties become undeniable—even the most headstrong and arrogant manager has to acknowledge that there are problems. The question now is how to respond. Unfortunately, as the Lehman example shows, acknowledgment does not always result in appropriate action.

As the global credit crisis erupted in August 2007, Lehman's stock fell sharply. Having grown Lehman to become the fourth biggest bank on Wall Street, Fuld could not accept that it was time to adopt a new strategy. When uncertainty started to grip the bank and journalists asked questions about its future, Fuld was reluctant to countenance any capital infusion. Selling parts of the bank was not an option he felt he could consider. Although Fuld eventually revoked this decision, it was too late: the bank declared bankruptcy on September 15, 2008.

> “The best leaders never presume they've reached ultimate understanding of all the factors that brought them success.”
> **Jim Collins**

The way in which management responds to a crisis brought about by success and accompanying hubris is critical. Inevitably, "band-aid" solutions that do not address the underlying problems rarely succeed. Quick fixes based on the same overconfidence that brought crisis in the first place—such as a bold but risky strategy, a hoped for blockbuster product, or a "market-changing" acquisition—usually result in the company moving to stage 5: capitulation to irrelevance, or death.

Capitulating to irrelevance

In stage 5, reality finally hits home. Expensive failed strategies erode financial strength and accumulated setbacks damage the individual spirits trying to repair the damage. Key managers generally leave the company at this stage, and the few customers that remain migrate to

US homeowners were prey to companies such as Lehman, which made big profits in mortgage-backed securities in the 2000s. Lehman's managers ignored warnings of unrepayable mortgages.

other brands. The once-mighty company has finally fallen. A management buy out, merger, or takeover may save the business and protect some jobs, but the company is unlikely to ever recapture its former glory. Most, having slipped this far, survive (if they survive at all) as niche brands trading on past history.

Return to glory

Decline is, of course, not inevitable for all successful companies. Those that reach the later stages of corporate decline do so because managers failed to heed the early warning signs of change or were irrationally sure of their ability to "beat the odds." However, it is possible to reach stage 4 and recover. According to Collins, this involves taking a calm, clear-headed approach and reaching not for savior strategies, but for the basic core values and disciplines that made the organization great in the first place.

Steve Jobs did just that at Apple. In the late 1980s and early 1990s, the company's management perceived Apple as vastly superior, ignored increasing competition from PC manufacturers, and expected customers to dismiss quality and compatibility issues as "quirks." After the 1995 release of Microsoft's Windows 95 operating system, Apple fell into decline. Sales, profits, and Apple's image tumbled. *BusinessWeek* called it "the fall of an American icon." The CEO, Gil Amelio, cut costs, reorganized the company, and added a new Internet Services Group. By 1997, Apple was months from bankruptcy, as the business continued to spiral out of control. A new board assembled and called for the return of one of the cofounders—Steve Jobs—as CEO. Many expected him to respond with a slew of new products, but he did the opposite. He shrank the company to a size that reflected its niche position, and cut back the desktop computer models from 15 to one. He ended production of printers, cut software development, and moved production abroad. He redesigned the company around a simplified product line, sold through a limited number of outlets. He stabilized Apple and allowed a return to its core values—a focus on innovation and quality—that later brought iconic products such as the iMac, iPod, iPhone, and iPad.

> Success comprises in itself the seeds of its own decline.
>
> **Pierre de Coubertin**
> **French educator (1863–1937)**

The pursuit of less

Hubris is not the single cause of business failure. Even the most skilled management may fail when faced with turbulent markets, the collapse of a key supplier, or other factors beyond their control (the 2008 credit crunch, for example, was the final blow for an already struggling Woolworths). Hubris may occasionally be a factor in corporate decline, but failure may also result from poor business practice or simply from bad luck.

However, if overconfidence leads to an "undisciplined pursuit of more," the remedy seems to be the disciplined pursuit of less—a return to a company's strategic roots. Ego, though, is a powerful thing, and humility is too rarely the tool managers reach for when fighting for survival. ■

CULTURE

IS THE WAY IN WHICH A GROUP OF PEOPLE SOLVES PROBLEMS

ORGANIZATIONAL CULTURE



IN CONTEXT

FOCUS
Organizational structure

KEY DATES
1980 Geert Hofstede draws attention to the importance of organizational culture in his book *Culture's Consequences*.

1982 US business consultants Terrence Deal and Allan Kennedy argue that culture is the single most important factor in determining success.

1992 Harvard professor John Kotter claims that in an 11-year period, organizations with rich cultures see net income growth of 756 per cent, compared to one per cent in those with less-defined cultures.

2002 Watson Wyatt develops the Human Capital Index, demonstrating the economic value of business cultures that maintain good practice in human resources.


Culture is "the way we do things around here."
Organizations are **collections of different cultures**.
Culture is exemplified by a company's **language, routines, and rituals**.
Culture is **subject to variation**.
Culture impacts **every aspect of business behavior**.
Culture is a significant determinant of organizational success or failure.

Organizations build a sense of identity through tradition, history, and structure. This identity is kept alive through the organization's culture: its rituals, beliefs, legends, values, meanings, norms, and language. Corporate culture determines how "things are done around here."

Culture provides a shared view of what an organization is (the intangibles) and what it has (the tangibles). It is the "story" of the organization: a narrative reinforced through idiosyncratic languages and business-specific symbols. In the 1940s, human relations experts began to consider organizations from a cultural point of view, drawing inspiration from earlier sociological and anthropological work associated with groups and societies. However, the term "organizational culture" only became part of the business lexicon in the early 1980s, following the publication of *Culture's Consequences* by the Dutch cultural psychologist and management expert Geert Hofstede.

Looking closely at organizational structure for the first time, Hofstede observed that it is shaped by and overlaps with societal culture. He identified five dimensions of culture that influence business behavior: power distance, individualism *vs.* collectivism, uncertainty avoidance, masculinity *vs.* femininity, and long- *vs.* short-term orientation.

Five cultural dimensions

The first of Hofstede's dimensions—power distance—refers to the distance in authority between manager and subordinates. Business cultures that have a high power distance tend to be rule-driven and hierarchical (everyone "knows their

See also: Creativity and invention 72–73 ▪ Gods of management 76–77 ▪ Hubris and nemesis 100–103 ▪ Avoid groupthink 114 ▪ Balancing long- versus short-termism 190–91 ▪ The learning organization 202–07 ▪ Creating an ethical culture 224–25



Hofstede's five cultural traits can be measured across companies in different countries. Hofstede's research allocated a score between 1 and 120 for each trait. For example, companies in China received the highest score—118—for long-term orientation, while companies in the USA had a much shorter-term focus, receiving a score of 25 (in Russia, data for this trait was unavailable).

place"). In Russia, for example, employees have little access to executives (power distance is high). Conversely, in low power-distance cultures, such as many companies in Australia, decision making is distributed more evenly throughout the organization.

Anthropologists have long theorized that collectivist cultures control members through external societal pressure (shame), whereas individualistic cultures control their members more through internal pressure (guilt). In his second dimension, Hofstede proposed that this tendency toward collectivism or individualism can be most clearly seen in the difference between Asian and US companies. When problem-solving, US businesses tend to look to the individual for a solution, whereas Asian companies prefer to pose the problem to a group.

Masculinity and femininity, Hofstede's third cultural dimension, are viewed differently from one organization to another. Some place great emphasis on masculine traits (such as status, assertiveness, and advancement), while others accord feminine traits (such as humanism, cooperation, collegiality, and nurturance) greater value. Italian organizations, for example, tend to have assertive, competitive cultures.

The fourth of Hofstede's dimensions is known as uncertainty avoidance. This is the extent to which workers feel threatened by ambiguous situations. The more uncomfortable people are with "not knowing" how to react in a certain scenario, the more rules and policies the company will need to introduce to reduce that uncertainty. Companies with a low degree of uncertainty avoidance are likely to thrive in more uncertain and ambiguous situations. British organizations, for example, are considered fairly at ease with unstructured and unpredictable situations.

Hofstede's fifth dimension, long- *vs.* short-term orientation, is the extent to which organizations privilege the short-term (profit) over the long-term (value generation). »

> The thing I have learned at IBM is that culture is everything.
>
> **Louis V Gerstner Jr**
>
> **US businessman (1942–)**

Japanese businesses, for example, think very much in the long-term: Toyota Motor Corporation has a 100-year business plan.

Why culture matters

Every organization's culture has varying degrees of these different dimensions. The best leaders know which cultures operate within different parts of their organization (and within different parts of the world), and adjust their leadership style to suit—valuing collective approaches, for example, when dealing with Asian subsidiaries.

Today, organizational culture is more important than ever before. Increasingly competitive markets, globalization, the prevalence of mergers, acquisitions, and alliances, and new modes of working (such as teleworking) require coordination across vast numbers of staff and huge geographic distances. Hofstede's observations highlight the difficulties that leaders face in maintaining unified business cultures, whether operating across multiple national or international cultures. The challenge is to balance the promotion of "one culture" within an organization against the influences of local cultures in the external world.

Companies with strong cultures, such as Nike and India's Tata Motors, are intensely aware of their history and image. At Nike it is not unusual for employees to have the company's "swoosh" logo tattooed on their body. At these businesses, culture encompasses an internalized sense of "who we are" and "what we stand for" to such an extent that many of the staff are able to recite corporate maxims from memory. Similarly, the UK smoothie company Innocent has worked hard to create a corporate culture based on communication. Dan Germain, the brand's Head of Creative, explains: "if people aren't involved in all decisions, big and small, then they start to feel unloved and removed from the business and its success."

Visible aspects of culture, such as an organization's rituals, stories and symbols, are only the tip of the iceberg. Its beliefs, values, attitudes, and basic assumptions are hidden but definitive.



Cultural benefits

Strong cultures give staff a sense of belonging, which in turn brings benefits, such as job satisfaction and staff retention. At Nike, staff are considered rookies if they have been at the company for less than a decade. Moreover, culture defines "the rules of the game," simplifying priorities. Decision making is faster and easier if everyone understands company values, beliefs, and vision. Deeply embedded cultures also improve the customer experience; if staff believes in the product, they will transfer this belief to customers.

Culture also protects an organization from the whims of charismatic leadership and the fickleness of fashion. A leader may influence corporate culture, but a successful culture should endure even when management changes.

Features of culture

Strong organizational cultures can suffer from problems of groupthink (everyone is too like-minded), insularity (too narrow a vision), and arrogance (a belief that everything the company does is right). Culture can become a source of power and resistance; necessary change may be resisted simply because "that's not the way we do things."

Terrence Deal and Allan Kennedy's 1982 publication *Corporate Cultures* outlined a range of cultural phenomena. The authors suggested that culture is composed of a framework of six interlocking elements: a company's history; its values and beliefs; its rituals and ceremonies; its stories; the heroic figures whose words and actions embody corporate values; and the cultural network.

The cultural network, devised by Deal and Kennedy, refers to the informal channels in a company—storytellers, gossipers, and whisperers—through which culture is formed and passed on.

Deal and Kennedy also defined four types of organizational culture, which emerge from the interplay between a company's attitude to risk, and the speed of feedback and reward. In the tough-guy, "macho" culture, rapid feedback and reward are combined with a high tolerance of risk, as in the advertising industry. In the work-hard, play-hard culture —such as a sales company—risk is less prevalent, but rapid feedback and reward produce a high-pressure environment. In the "bet-your-company," high-stakes culture, the risk attached to decisions is high, but feedback on success or failure is slow. The oil industry is typical of the high-stakes culture. In a process culture, such as an insurance company or government agency, feedback is slow and risks are low.

Leadership and culture are interwoven and interdependent. If a leader does not protect or redefine the core values that made a company successful, culture can erode. In 2012, a Goldman Sachs employee bemoaned the investment bank's "toxic culture" in an open letter to *The New York Times*, claiming: "the culture was the secret sauce that made this place great and allowed us to earn our clients' trust for 143 years ... I look around today and see virtually no trace of [that] culture." The letter made headlines, and the company's shares fell by 3.4 percent.

Culture in practice

The desire by leaders for some sort of standardized culture—one that is fixed, visible, and stable—is understandable, but it likely to operate only in the imaginations of leaders than in the experiences of employees. Companies rarely have one culture; they are usually a combination of many, which overlap across departments, countries, and business units. The task for leaders is to ensure that these cultures do not diverge too far from core organizational values.

Organizational culture is not static. Every type of culture is dynamic and shifts, incrementally and constantly, in response to internal and external pressure. Managing culture, especially through periods of deliberate change, is one of the most difficult business tasks a leader can face.

The advice for leaders seeking to change culture is start small. Culture is slippery, and trying to change everything at once often results in failure. Bold new mission statements, big office redesigns, or exhortations that "working here is fun" rarely have the desired impact. Cultural change requires long-term investment in employees, not in buildings and branding. This is because culture may be led from the top, but it grows from the bottom; it requires patient nurturing over time. Leaders must understand the dynamic of an organization's culture so that they can usefully draw on its strengths, rather than be overcome by its constraints. ■

Geert Hofstede

Born in 1928 in Haarlem, the Netherlands, Geert Hofstede went to technical college then gained an MSc in mechanical engineering from Delft Technical University. He spent two years in military service with the Dutch army, before going into industrial management and beginning a PhD. In 1965, while studying part-time, he joined IBM and founded a personnel research department. His years at IBM were to prove formative; the data and insight gleaned there formed his research base and his "bottom-up" view of organizations. Hofstede became a professor of management in 1973, and was named one of the world's most influential thinkers by the *Wall Street Journal* in 2008. The ideas in his 1980 book *Culture's Consequences* continue to inform global debates on organizational culture.

Key works

1980 *Culture's Consequences*
2010 *Cultures and Organizations: Software of the Mind*

> Culture eats strategy for breakfast.
> **Peter Drucker**
> **US management consultant**
> **(1909–2005)**

EMOTIONAL INTELLIGENCE IS THE INTERSECTION OF HEART AND HEAD

DEVELOP EMOTIONAL INTELLIGENCE

IN CONTEXT

FOCUS
Emotional intelligence

KEY DATES

c.400 BCE The philosopher Plato says that all learning has an emotional base.

1930s US psychologist Edward Thorndike describes the concept of "social intelligence"—the ability to get along with other people.

1983 US psychologist Howard Gardner suggests that people have multiple intelligences, including interpersonal, musical, spatial-visual, and linguistic.

1990 US psychologists Peter Salovey and John Mayer publish the first formal theory of emotional intelligence.

1995 Daniel Goleman publishes *Emotional Intelligence: Why It Can Matter More Than IQ*, which becomes a global best seller.

Emotional intelligence (commonly abbreviated as "EQ", for emotional quotient) is the ability to perceive, control, and evaluate emotions, both in oneself and in others. The concept emerged from research into social intelligence in the 1930s, and from work in the 1970s on different forms of intelligence. In the 1990s, US psychologist Daniel Goleman published the highly influential *Emotional Intelligence: Why it Can Matter More Than IQ*. In the book he identified the five "domains" of emotional intelligence: knowing your emotions; managing your emotions; motivating yourself; recognizing and understanding other people's emotions; and managing relationships.

> The most effective leaders are alike in one crucial way: they all have a high degree of emotional intelligence.
> **Daniel Goleman**

Goleman pinpoints high EQ as a common trait among effective business leaders. Without emotional intelligence, he argues, a leader can have limitless energy and ideas, a perceptive and logical mind, and impressive qualifications, but still be ineffective and uninspiring.

Goleman cites Bob Mulholland, head of client relations at Merrill Lynch during the 9/11 attacks, as a leader with high EQ. After his staff saw a plane hit the twin building opposite their own, they began to panic—some ran from window to window, and others were paralyzed with fear. His first response was to "unfreeze" their panic by addressing each of their concerns individually. He then calmly told them that they were all going to leave the building, via the stairs, and that they all had time to get out. He remained calm and decisive, but did not minimize people's emotional responses. All his staff escaped without injury. This was a rare and unusual context, but Mulholland's approach shows the value of EQ in managing staff in any form of volatile situation.

See also: From entrepreneur to leader 46–47 ▪ Effective leadership 78–79 ▪ Organizing teams and talent 80–85 ▪ Avoiding complacency 194–201 ▪ The learning organization 202–07 ▪ Kaizen 302–09


Emotional intelligence has **five components**:
Self-awareness (the ability to recognize and understand emotions)
Self-regulation (the ability to control impulses and emotions)
Motivation (a desire to pursue goals with energy)
Empathy (the ability to understand other people's emotions)
Social skills (an ability to find common ground and build rapport)

Goleman suggests that high EQ facilitates other essential leadership traits. For example, the ability to recognize accurately what another person is feeling (empathy) enables one to manage that feeling and any behaviors that arise from it.

What makes a good leader?

One persistent debate within the business world is whether leaders are born or made. Goleman suggests that the answer is both: inherent personality traits are important in leadership, but EQ—which grows with age, experience, and self-reflectiveness—is just as important.

Today, the development of EQ lies at the heart of leadership coaching. New and aspiring leaders are mentored by experienced ones; together, they discuss past and future scenarios, various possible responses, and what the emotional trigger points might be. This procedure seeks to increase emotional maturity. A 1999 study showed that partners in a multinational consulting company who scored highly on EQ delivered $1.2 million more profit than other partners. Other studies have shown similar correlations between EQ and effectiveness. Emotional balance, it seems, is a key factor in commercial success. ■

Daniel Goleman



Psychologist Daniel Goleman was born in 1946 in California, US. His parents were both college professors, and Goleman was president of his high school before receiving a scholarship to study at Amherst College, MA. During the course, he transferred to the University of California, Berkeley, for a year, where he studied the rituals of social interaction under sociologist Erving Goffman.

Goleman then took a doctorate at Harvard University, where he studied under David McClelland, best known for his theories on the drive to achieve. After completing his PhD, he traveled widely in India and Sri Lanka, studying meditation and mindfulness. He taught briefly as a visiting lecturer at Harvard University before becoming a journalist and author. His bestselling book, *Emotional Intelligence,* has sold more than 5 million copies in 40 languages.

Key works

1995 *Emotional Intelligence*
1998 *What Makes a Leader?*
2011 *Leadership: The Power of Emotional Intelligence*



MANAGEMENT IS A PRACTICE WHERE ART, SCIENCE, AND CRAFT MEET

MINTZBERG'S MANAGEMENT ROLES

IN CONTEXT

FOCUS
Management roles

KEY DATES
1949 French engineer and business theorist Henri Fayol develops what becomes known as "the classical theory of management." This claims that managers have five key functions: planning, organizing, coordinating, commanding, and controlling.

1930s Australian psychologist Elton Mayo publishes the *Hawthorne Studies*, which ushers in an era of people-oriented management, rather than managing according to business objectives alone.

1973 In *The Nature of Managerial Work*, Henry Mintzberg dismisses Fayol's claims about the management process as "folklore."



Managers perform a **multitude of roles**, which can be divided into three categories...

...**Informational**:
Monitor
Disseminator
Spokesperson

...**Interpersonal**:
Figurehead
Leader
Liaison

...**Decisional**:
Entrepreneur
Disturbance handler
Resource allocator
Negotiator

Management is a blend of these often conflicting roles, where art, science, and craft meet.

The question "What do managers do?" has vexed experts, and many front-office staffs, since organizations came into existence. In his 1975 paper "The Manager's Job," business guru Henry Mintzberg argues that managers are not the reflective, systematic planners that people assume; instead, "their activities are characterized by brevity, variety, and discontinuity." He finds them to be strongly oriented to action, and disliking of reflection.

Mintzberg suggests that there are ten basic management roles, which fall into three categories: informational roles (managing through the use of information); interpersonal (the management of people); and decisional (managing decisions and action).

See also: From entrepreneur to leader 46–47 ▪ Leading well 68–69 ▪ Gods of management 76–77 ▪ Learning from failure 164–65 ▪ Crisis management 188–89 ▪ Simplify processes 296–99 ▪ Kaizen 302–09

The informational role is possible because, although managers do not know everything, they tend to know more than their subordinates. "Scanning the environment" and processing information is a key part of the manager's job. In this sense, Mintzberg claims, they are "the nerve center of the organizational unit." They monitor what is going on, disseminate it to others in the companies, and act as a spokesperson for the business in the world at large.

Information is easily available to the manager because the role connects him or her to many people. In this sense, the manager plays an interpersonal role, which also involves acting as a figurehead for the companies, providing leadership, and acting as a liaison point between a large group of people. The group may include subordinates, clients, business associates, suppliers and peers (managers of similar organizations).

The third role of management, is decision making. Managers must oversee financial, material, and personnel resources and decision making (be a "resource allocator"), encourage innovation (act as an entrepreneur); and seek conciliation or pacification when the company is unexpectedly upset or transformed (be a "negotiator" and "disturbance handler").

None of these roles is exclusive or privileged. Mintzberg claims that effective managers shift seamlessly between these different functions and know when each role is most appropriate for the given context.

Fact and fiction

The traditional view held that management was a science, where managers controlled a company's constituent parts—people and machinery—both of which acted in predictable and scientifically controllable ways. Mintzberg argues, however, that management is a practice in which art, science, and craft meet. It involves sorting and processing of information, organization of systems and, most importantly, highly subjective, nonscientific management of people.

> “Organizational effectiveness does not lie in that narrow-minded concept called rationality. It lies in the blend of clearheaded logic and powerful intuition.”
> **Henry Mintzberg**

Mintzberg argues that the answer to the question "what do managers do?" is not simple. He concludes that management is complex and contradictory in its demands, relying as much on intuition, judgment, and intellectual agility as on technical skill, planning, and scientific logic. All these come into play, he says, since a manager designs, monitors, and develops the ways in which things are done. ■

Henry Mintzberg

Born on September 2, 1939 in Montreal, Canada, Henry Mintzberg's background was in mechanical engineering. After graduating in 1968 from the Massachusetts Institute of Technology (MIT), US, he moved to McGill University in Montreal, where he joined the faculty of management. He later took a joint appointment as professor of strategy and management at both McGill in Montreal and INSEAD, in Singapore and Fontainebleu, France.

Mintzberg is the author or co-author of 15 books and more than 150 articles, and is best known for his work on management and managers. His *Harvard Business Review* paper "The Manager's Job: Folklore and Fact" won a McKinsey award in 1975. In 1997 he was made an Officer of the Order of Canada and of l'Ordre national du Quebec; and in 2000 he was awarded Distinguished Scholar of the Year by the Academy of Management. In 2013, he was awarded the first honorary degree ever given by the Institut Mines-Télécom in France.

Although he has been teaching since 1968, Mintzberg's interest in organizations and managers emerged during his first degree, when he spent time at the Canadian National Railway. His memoirs describe the catastrophic result of two boxcars colliding as an excellent metaphor for corporate mergers.

Key works

1973 *The Nature of Managerial Work*
1975 "The Manager's Job"
2004 *Managers not MBAs*

A CAMEL IS A HORSE DESIGNED BY COMMITTEE

AVOID GROUPTHINK

IN CONTEXT

FOCUS
Group dynamics

KEY DATES
1948 US advertising guru Alex Osborn promotes the practice of "brainstorming"—generating ideas in groups, without criticism.

1972 US research psychologist Irving Janis publishes *Victims of Groupthink*.

2003 An investigation into the Columbia space-shuttle explosion cites a culture where it was "difficult for dissenting opinions to percolate up."

2005 Robert Baron publishes the academic paper "So Right it's Wrong," claiming that groupthink tendencies may be confined to the early stages of the formation of a group.

2006 Steve Wozniak, the inventor of the first Apple computer, advises creative thinkers: "Work alone. Not on a committee. Not on a team."

The desire to belong is a powerful human emotion. We want to be accepted and to be part of a group, which explains why individuals may set aside their opinions, remain silent in meetings, and nod in agreement even when they disagree. This deterioration of individual "mental efficiency, reality testing, and moral judgment" was outlined by US psychologist Irving Janis in 1972, and is known as "groupthink."

Groupthink is the idea that concurring with others is the sole overriding priority. It can become so strong that it precludes realistic assessment and analysis. Insulated from contrary perspectives, groups displaying groupthink self-justify their own conclusions. Irrational decisions may be made based on false or incomplete information.

Irving noted that groups displayed a series of characteristics when groupthink gains hold. The group begins to feel invulnerable, which encourages extreme risk taking. It collectively rationalizes decisions, fails to check the reality of assumptions, and ignores warnings. It begins to assume a position of moral superiority, and fails to consider the ethical consequences of its actions.

The challenge for managers is to recognize groupthink and take action to prevent it. Encouraging dissent, assembling groups with diverse demographics, and listening to others' opinions before airing their views are means of doing so. ■

Swissair went into liquidation in 2001. Once labeled "the flying bank" due to its profitability, the airline's executive structure displayed groupthink traits, such as a sense of invulnerability.

See also: The value of teams 70–71 ▪ Beware the yes-men 74–75 ▪ Hubris and nemesis 100–03 ▪ Organizational culture 104–09



THE ART OF THINKING INDEPENDENTLY, TOGETHER

THE VALUE OF DIVERSITY

IN CONTEXT

FOCUS
Work-force diversity

KEY DATES
2005 Car maker Daimler targets 20 percent of management roles be filled by women by 2020. It sets similar targets for other diversity measures, such as age mix, socio-demographic mix, and nationality mix.

2009 A survey analyzing the value of female representation on corporate boards ranks companies with more females higher than male-dominated rivals.

2012 A *Harvard Business Review* article by business consultants Jack Zenger and Joseph Folkman finds that women are rated higher in 12 of the 16 competencies that define outstanding leadership.

2013 New Italian law requires a third of a company's board members be women by 2015.

As with most clichés, it is also a truism that managers often tend to recruit in their own image—males, for example, have a tendency to employ males. If left unchallenged, such behavior can lead to companies staffed with homogenous clones—people from the same backgrounds and with the same view of how the business should be run.

In contrast, when organizations actively pursue diversity—by employing people from different cultures and socio-economic backgrounds, and of different genders and ages—the more dynamic and stimulating they are as places to work.

The case for diversity

Greater diversity means greater scope for creativity—the more varied are the sources of an organization's views, the more likely that out-of-the-box thinking and problem solving will occur. Studies have shown that diversity can also combat groupthink, a malaise in group dynamics that can stifle innovation and growth. In diverse teams, opinions are less likely to go unchallenged.

> Diversity management isn't merely nice to have, it's a business must.
> **Daimler company statement (2005)**

Diversity is not confined to employee demographics. It might simply involve creating cross-functional teams that incorporate the views of people from across a company—the marketing team, for example, might benefit from the insight of operations or finance. But whatever the context, monochrome recruitment can lead to stasis—diversity fights against it. ■

See also: The value of teams 70–71 ▪ Beware the yes-men 74–75 ▪ Thinking outside the box 88–89 ▪ Organizational culture 104–09

MAKING WORK

MANAGING FINANCES

MONEY

Finance has always been seen as having two distinct functions: recording what has happened (financial accounting) and helping businesses to make decisions about the future (management accounting). Today, it has a third function: financial strategy. This incorporates judgments about risk, which some companies (especially banks) have realized must play a larger part in financial decision-making.

Understanding risk

Fundamental to an understanding of financial strategy are the concepts of leverage and excess risk. "Leverage" is a measurement of the extent to which a business is dependent upon borrowings. The higher the leverage, the greater the level of risk. In good times, directors come under pressure to produce impressive profit growth, and one easy way to achieve it is to borrow money and invest in the most profitable parts of the business. However, if the economy turns downward, toward recession, heavy borrowings turn into an overwhelming burden. Leverage becomes toxic.

The risk level generated by leverage is worsened when businesses use off-balance-sheet finance, in other words, when they do not report loss-making investments on the company's balance sheet, thereby appearing to boost profits. This leads to an important question in relation to modern business: who bears the risk? Traditionally it was assumed that the risk taker was the shareholder, because it is the shareholders who collectively own the business. However, in Europe and the US especially, the desire to encourage entrepreneurship has led to generous rules that reduce the extent to which losses are borne by business owners. Since 2008, many business collapses have proved expensive for customers, staff, and suppliers, but less so for the business owners, particularly when the failing institution has been a bank. Some financial commentators wonder whether the balance has swung too far away from tradition.

> “The bonus mania which caused the recession could never have happened without corrupted accounting rules.”
>
> **Nicholas Jones**
>
> **UK film maker, ex-accountant**

Director involvement

When times are tough, directors have to make difficult decisions about investment and dividends. Usually the directors will have an agreed policy in place—perhaps that half the after-tax profit will be paid as dividends to shareholders, while the other half will be retained to invest in future growth. But during recessions it is wise to keep more cash within the business, so directors may decide that dividends should be cut. If the business also cuts its investment plans, it can keep more cash in its current account, providing the liquidity to survive difficult trading conditions.

So who is responsible when things go wrong? This depends on the systems of accountability and governance within each company. Ideally, the directors of the business should be sufficiently involved to know when things start to go wrong, and call for discussion of a change in strategy. If the directors are too hands-off, they may feel unable to hold the CEO fully accountable when things do go wrong. Alert,



hands-on directors should also spot when rewards for staff are so out-of-control as to threaten the profits being made for shareholders and for the future financial health of the business. “Profit before perks” should be the mindset.

Important to good governance is a willingness to ignore the herd. For example, if every US bank began to expand into South America, a smart South Korean bank would refuse to copy. However, in practice, this proves hard to do. Directors meet each other in the same clubs and conferences, and like to be part of the same pack. Nevertheless, US investment guru Warren Buffett has become one of the world’s wealthiest men by ignoring the herd instinct among investors.

The mass market

Some modern boards of directors accept that if there is wisdom among crowds, there may be even greater wisdom among staff. Henry Ford was one of the first to realize that your workers are your customers, but it has taken a century for others to see the potential in this phrase. Not only is there value in drawing ideas from staff who care about the products they both produce and use, but there is also strategic value in understanding the huge potential of the mass market. When looking at China today, the most exciting opportunities are for products that would appeal to the hundreds of millions of potential consumers who are workers, not managers.

Using money wisely

In management accounting, two factors are of particular importance: cash and costs. A management accountant works hard to provide accurate data on production costs, so that managers can make informed decisions about pricing, on outsourcing, and on which products to back with marketing spending. Activity-based costing, which provides the most complete data on costs per unit, is the best way to do this. When trading is poor, however, management accountants place their tightest focus not on costs but on cash flow, following the maxim that “cash is king.” This arises because the worse the trading conditions, the more that companies try to hold onto the cash they have—making it much harder to get paid if they are your customers. The flow of cash dries up, so an early focus on cash flow makes sense: start your own cash hoard before others begin trying to create their own.

For financial accountants, the traditional stance has long been “playing by the rules.” Integrity and adhering to accounting principles such as prudence and consistency were seen as most important. More recently, career opportunities have arisen for accountants who are willing to be more creative. This way of thinking stems from the scope for “making money from money,” by lending the company’s cash deposits to other companies at high rates of interest, or speculating on future trends in exchange rates or commodity markets. In a world where a quicker, bigger buck can be made from money than from manufacturing, playing by the rules may seem a poor choice. ■

> “I am incredibly nervous that we will implode in a wave of accounting scandals.”
>
> **Sherron Watkins**
> **US executive, former vice president of Enron** (1959–)

DO NOT LET YOURSELF BE INVOLVED IN A FRAUDULENT BUSINESS

PLAY BY THE RULES

IN CONTEXT

FOCUS
Governance and ethics

KEY DATES

1978 US scholars Ross Watts and Jerold Zimmerman write *Towards a Positive Theory of the Determination of Accounting Standards*.

1995 French professor Bernard Colasse claims that "there isn't any true result, but a result arranged using creative accounting techniques."

2001–02 Telecoms giant WorldCom overstates earnings by more than $3.8 billion.

2009 UK professor David Myddelton publishes *Margins of Error in Accounting*.

2012 Directors of US discount website Groupon identify a "weakness" in financial reporting, five months after becoming a public company.

Business accountants have two roles: to record profits and cash flow and to provide tightly estimated data about costs to help make strategic decisions. The accountant's instinct is to be cautious and prudent—costs and cash-outflow figures generally err on the high side, while revenues and cash inflows tend to be on the low side. Any surprises should be positive. For example, in January 2009, Honda Motor Company warned that dramatic falls in sales worldwide—due to the global downturn and the strong Yen—would force the company into a $3.7 billion loss in the fourth quarter of its financial year. However, the loss

See also: Hubris and nemesis 100–03 ▪ Profit before perks 124–25 ▪ Making money from money 128–29 ▪ Accountability and governance 130–31 ▪ Morality in business 222 ▪ Creating an ethical culture 224–27 ▪ The appeal of ethics 270


The rules set out **minimum standards**...
...but some rules **ignore morality**—"playing by the rules" may not be enough.
The alternative to rules is a principled approach based on a "**true and fair view**" of a company's accounts.
But without **statutory protection**, individuals can ignore principles and profit from **immoral actions**.
Good companies and accountants consider **rules plus morality**.

turned out to be $3.3 billion, demonstrating that the company had erred on the side of caution.

Accounting for profit

An accountant who follows safe practices sleeps well, but may struggle to climb the corporate ladder. When the stock market is full of optimism (a "bull market"), there are intense pressures within companies to push the stated profit level to the highest feasible point. This could be considered an odd statement, since profit might seem to be a simple matter of fact. However, the calculation of profit (which is effectively an estimation) is underpinned by a series of assumptions, and a company's stated profit is effectively a moveable figure. Different accounting teams may come up with different figures, even though the underlying data that they are analyzing is the same.

In 1992, British banking analyst Terry Smith published a book called *Accounting for Growth*. This publication set out the remarkable array of opportunities for publicly traded companies to provide an artificial boost to their stated profit levels. The book had a huge impact, and influenced the UK's newly formed Accounting Standards Board, which in turn developed new accounting rules in an attempt to minimize the scope for "creative accounting."

Today, most countries around the world follow the rules laid down by the International Financial Reporting Standards (IFRS). As a consequence, the income statements and balance sheets of companies in most countries follow the same format. »

Accountants must decide how cautious they are going to be when reporting a company's financial status, since they may be under pressure to boost the stated level of profits.

Mark-to-market accounting is a risky method of valuation, since it values a company's assets according to current market value. Historic cost valuation is a more reliable, and cautious, measure of value.


During a **stock-market boom**, valuing a company's assets and investments according to their **current market value** can lead to an **overinflated balance sheet**.
If the **stock market falls**, the value of the **balance sheet will shrink**, leaving the company in a **vulnerable position**.

Although the time frame for implementation is unclear, a widely supported plan is in place to merge the IFRS with the US's Generally Accepted Accounting Principles (GAAP) to provide globally recognized accounting rules.

Although the rules are becoming clearer, important areas for debate remain. These might be raised internally, in arguments between company accountants and directors; or the debate might be between independent auditors and the organization. When UK bank Halifax Bank of Scotland (HBOS) collapsed in 2008, the UK government bailed it with $32 (£20) billion, before the bank was acquired by Lloyds Bank. In 2008 the gap between the bank's loans and its deposits was $341 (£213) billion. The bank's auditor, KPMG, was heavily criticized over the HBOS collapse, although KPMG had consistently raised warnings over the risks involved. When the UK's regulator, the Financial Services Authority, published a report on HBOS in 2012 it noted that KPMG had "consistently suggested that a more prudent approach would be to increase the level of provision" against bad debts. Ultimately, the directors of HBOS had decided to take an optimistic view of the bank's lending. They chose to play beyond the rules.

Cautious accounting

Professor David Myddelton, a UK management scholar, argues strongly against the expansion of rules in accounting. He believes in traditional accounting principles, because these supply the required flexibility for accountancy across many different types of companies. He claims that the idea that there is a "single correct answer" when preparing a company's accounts is nonsense. Nevertheless, this idea lies behind the call for increased regulation. "People want it to seem as if we're doing something about scandals," he says; they think that greater regulation will make a difference, "but it never does." Myddelton also believes that directors should gain a "true and fair view" of their accounts, instead of being forced to rely on a picture produced by someone else's idea of the accountancy rules.

Some "creative accountancy" practices stretch the flexibility within the rules so far that they can produce potentially misleading accounts. "Mark to market" accounting, for example, values assets at their current market value. This means that when the stock market is booming, any investment (such as shares in another business) will also be booming. This boosts the value of the company's balance

Moral duty

Julian Dunkerton is the founder and major shareholder in the fashion business SuperGroup plc, whose leading brand is the popular street-wear label Superdry. Based in Britain, but with business and outlets worldwide, SuperGroup could easily follow the lead set by other organizations and manipulate accounts to minimize its tax liabilities.

Instead, the business plays by the spirit of the tax rules, paying about 30 percent of its profit to the tax authorities. Not that Dunkerton wants to claim the moral high ground—in its annual report, SuperGroup plc explains that "We recognize the commercial value, as well as the moral duty, of consistently operating with integrity, honesty, and a commitment to responsible and ethical business practices." Dunkerton has the wisdom to appreciate that acting responsibly can yield financial benefits, particularly in the long term.

Major accounting misconduct was unearthed by US company Caterpillar Inc. in a Chinese business it purchased in 2012. Irregularities included overstated profits and falsified stocks.

sheet and may encourage it to expand beyond its means. All it takes is a fall in the stock market for this valuable shareholding to become worth considerably less. Myddelton suggests that it is better to use "historic cost" accounting than "mark to market," since this provides a more stable set of figures; it values assets at their cost at time of purchase, minus any depreciation that has taken place, rather than at their current market value.

The argument of rigid rules *vs.* looser-based principles will be heard repeatedly when the merger talks between the US's rules-based GAAP system and the IFRS become serious. Even though the IFRS is far more rule-based than its predecessors, it retains a greater reliance on principles than the US's GAAP system.

Ethical conduct

Whether rules based or rooted in principles, no accounting methods can prevent a deliberate attempt by directors to mislead. In June 2012, for example, US construction-equipment giant Caterpillar Inc. completed a $650-million purchase of Chinese company ERA Mining Machinery Ltd. and its wholly owned subsidiary Zhengzhou Siwei Mechanical and Electrical Equipment Manufacturing Co. This was part of Caterpillar's long-standing strategy of growth in China. Unfortunately, a series of black holes in Siwei's accounts soon emerged, including the discovery in November 2012 that the company did not hold the stock levels it had claimed. In January 2013 Caterpillar said it was writing off $580 million from the value of ERA, thereby virtually admitting that the purchase was a complete waste of money. Caterpillar then accused the previous management at Siwei of deliberately creating misleading accounts, but let the matter drop in May 2013 when a financial settlement was reached.

In other circumstances, directors can find solace in the rules. Operating in South Africa, Canada, and Europe, short-term money-lender Wonga.com sets its annual percentage rate (APR) on "payday loans" as high as 5,800 percent. This is perfectly legal because the countries in which it operates have no legislated cap on interest rates, so the directors are playing by the rules. However, a report by the UK Citizens' Advice Bureau in 2013 stated that three out of four "payday loan" customers struggle to repay. In contrast to the UK, countries such as France and the US have rules that set maximum interest levels for consumer credit loans.

> Mark-to-market accounting is like crack. Don't do it.
>
> **Andrew Fastow**
>
> **US former Enron executive** (1961–)

Ultimately, no set of rules can substitute for ethical behavior nor safeguard the system from a determined attempt to manipulate accounting figures in a misleading way. In the hands of principled accountants, flexibility within the rules is useful; but if someone seeks to gain huge financial advantage no matter what, that flexibility will enable him or her to do so, even if this entails acting immorally.

Rules help to ensure that companies operate at an acceptable minimum standard. The argument revolves around where this standard lies, balanced as it is between useful standards and costly overregulation. Rules also encourage those with ethical principles to go further than the minimum. ■

EXECUTIVE OFFICERS MUST BE FREE FROM AVARICE

PROFIT BEFORE PERKS

IN CONTEXT

FOCUS
Equity and performance

KEY DATES

1776 Adam Smith says that managers will not watch over a business with the same vigilance as partners in a private company would watch over their own.

1932 US professor Adolf Berle and US economist Gardiner Means coin the phrase “the separation of ownership and control.”

1967 Canadian-American economist J. K. Galbraith says that shareholders no longer control the organizations they legally own.

2012 Larry Ellison of US computing corporation Oracle Inc. becomes the world’s highest-remunerated CEO, when he receives $96.5 million in pay, shares, and perks.



In a public company, the **shareholders are the owners** of the company.

Multiple shareholders cannot run a company, so they must **employ executive officers** to do this for them.

It is **not possible to oversee**, in detail, everything that these managers do…

… so it is essential that managers can be trusted to act **in the interests of the company**, not themselves.

Executive officers must be free from avarice.

In an ideal business, directors pursue the company’s objectives without undue consideration for personal gain. Upon election to the board, they negotiate their salary and standard perks, and from then on, their focus is on the success of the business. Yet there is a risk that bosses can be dazzled by the wealth generated around them, and work toward boosting personal gain instead of the profits due to shareholders.

This situation, known as “the divorce of ownership and control,” first arose in the late 19th century,

See also: Beware the yes-men 74–75 ▪ Is money the motivator? 90–91 ▪ Organizational culture 104–109 ▪ Avoid groupthink 114 ▪ Play by the rules 120–23 ▪ Accountability and governance 130–31

FABER-CASTELL
since 1761
FINEST ARTISTS' QUALITY

German *mittelstand* companies— such as Faber-Castell, a world-leading producer of pencils—are usually family-owned. Directors of such firms are more likely to focus on long-term performance.

with the creation of large, public limited companies (plcs) that allowed senior management more freedom to operate beyond effective shareholder scrutiny. As long as the company profits were satisfactory, directors were free to conduct their business functions as they saw fit. However, if a business enterprise comes to reflect the aims of its managers, will the business be focused on profit maximization (for its owners, the shareholders) or on increasing the status, financial rewards, and power of its managers?

Personal interests

Some directors act opportunistically; they seem to be more interested in personal gain than in the company's financial well-being. The banking crisis of 2008 led the shareholders of many companies to question corporate governance mechanisms and executive pay. The shareholders of Barclays Bank, for example, were stirred into taking action just before the bank's 2012 AGM. They had discovered that in the previous year, profits had fallen by 3 percent, shares had dropped by 26 percent, but chief executive Bob Diamond was due to receive a bonus of $4.2 (£2.7) million and total pay in excess of $10 (£6.3) million.

Restricted ownership

In private limited companies, the situation is simpler. Since share ownership is restricted (often within a single family), the directors and the shareholders are usually the same people. In any case, it is unusual for people to take advantage financially of those within their own circle of family and friends. For example, the problem of perks before profits is rarely an issue in Germany, where the *mittelstand* (medium-sized) companies—which are mainly family companies—are the dominant business model. A recent study of the different performances of family-owned and publicly owned companies in Spain found that family-owned companies performed better, in terms of financial equity, than nonfamily companies of the same size in the same industry. Countries such as the UK and US, however, have a larger proportion of plcs than many other countries. After decades of noninterference, shareholders are once again becoming interested in corporate governance and gain. ■

> Leadership is a privilege to better the lives of others. It is not an opportunity to satisfy personal greed.
>
> **Mwai Kibaki**
>
> **Former President of Kenya (1931–)**

Fewer perks, more profits

Several companies have taken positive steps to eliminate perks as part of a cost-cutting strategy. At the German company T-systems International, an ICT subsidiary of Deutsche Telekom AG, all workers must now fly in coach class, regardless of the traveler's position within the company, or the distance and duration of their journey. The change from business- to economy-class travel is thought to have saved T-systems $1.5 million annually. Executives were told that the choice was between a reduction in travel expenses, or a cut in their annual bonuses.

Since the 2008 financial downturn, there has been an increase in the trend of organizations tightening their purse strings. Even the mighty entertainment company Walt Disney is phasing out executive car allowances. Cost cutting and eliminating perks puts greater pressure on managers to boost their company's profitability.



IF WEALTH IS PLACED WHERE IT BEARS INTEREST, IT COMES BACK TO YOU REDOUBLED

INVESTMENT AND DIVIDENDS

After calculating the year's profit, a company's directors can choose whether to pay a dividend to shareholders or reinvest the sum. A dividend is the annual payment to shareholders that most businesses manage each year. It might amount to a 3 percent return on the sum invested, which would make it comparable to the interest a saver might receive from a bank deposit.



How much a company **pays in dividends** or **reinvests in the business** is decided…

…according to **growth prospects** and the **health of the balance sheet**.

When growth is high, or the balance sheet is weak, companies should **retain cash for reinvestment**.

When the balance sheet is strong, or growth is slowing, companies should **pay dividends** to shareholders.

Directors must balance the need for **reinvestment in the business** with **shareholder returns**.

IN CONTEXT

FOCUS
Financial strategy

KEY DATES

1288 The first recorded share certificate is issued to the Bishop of Vasteras in Sweden by Stora Enso, a pulp and paper company.

17th century The Dutch East India Company issues shares, heralding the emergence of organized share trading.

1940 Peter Drucker writes on the need for businesses to balance short-term dividends and long-term reinvestment.

1961 Modigliani and Miller claim that paying or retaining dividends does not affect a business's long-term performance. Their seminal work is later disputed, with several studies showing that dividend increases boost a company's share price.

See also: Accountability and governance 130–31 ▪ Who bears the risk? 138–45 ▪ Ignoring the herd 146–49 ▪ Profit versus cash flow 152–53

The Dutch East India Company was the first public company to offer shares. Investors put up money for voyages in return for a share of the profits made from successful trips.

In 2012, for example, Honda Motor Company of Japan paid out just under half its $2.7 million profit in dividends, leaving just over half to reinvest in the company.

The first dividend payments were made in the 17th century by the Dutch East India Company, which was the world's first company to issue shares in exchange for capital. To encourage investors to buy shares, a promise of an annual payment (called a dividend) was made. Between 1600 and 1800 the Dutch East India Company paid annual dividends worth around 18 percent of the value of the shares.

Invest or pay out?

Dividend payouts are entirely the gift of the directors. Their decision is simple: what proportion of after-tax profit should be paid in dividends, and what should be retained inside the company for reinvestment? The higher the company's growth prospects, the greater the incentive to keep money within the business. Slow-growing companies should therefore pay out a high proportion of profits in dividends, whereas booming organizations are more likely to keep the cash within the business. There is no safer source of capital than retained profit: it does not need to be repaid, nor does it require the payment of interest. Another factor to consider is the health of the company's finances. If they are weak, profits should be retained; only if the balance sheet is strong should generous dividends be paid to the shareholders.

Dividend payouts must be considered carefully. In 2006, the Royal Bank of Scotland (RBS) declared a 25 percent increase in dividends to shareholders. Market commentators praised the move, with one team of analysts issuing the note: "Thanks Fred [Goodwin, CEO of RBS], we love you." The dividend increase put money directly into the hands of the shareholders. Just two years later RBS was forced to ask shareholders to buy shares at 200p ($3.13) each, in order to raise £12 ($18) billion. Six months later, those shares were worth only 65p ($1.03); three months after that, just 11p (¢17). The company's generosity in 2006 cost its shareholders dearly.

In contrast, Apple did not pay dividends from its formation in 1977 until 2013. The directors, led by Steve Jobs, argued that shareholders would benefit in the long term by allowing Apple to reinvest profits. Only in 2013, with its growth rate beginning to fall, did the company announce dividend payouts, which it projected would average $30 billion a year until 2015. ■

John Kay

Professor John Kay is a British economist born in 1948. Best known for his sceptical support for free-market business behavior, he is a visiting professor at the London School of Economics and regular contributor to the *Financial Times*. In 2012 he presented a detailed report to the UK government on the stock market, which emphasized that the normal purpose of stock markets is not speculation, but to provide companies with access to capital and to provide savers with an opportunity to share in economic growth. He also highlighted concern about excess dividend payouts.

Key works

1996 *The Business of Economics*
2003 *The Truth About Markets*
2006 *The Hare and the Tortoise*

BORROW SHORT, LEND LONG

MAKING MONEY FROM MONEY

IN CONTEXT

FOCUS
Financial products

KEY DATES
c.1650 A rice market in Osaka, Japan issues the first standardized futures contract, agreeing to prices for goods not yet delivered.

1970s and 80s Deregulation gives banks and companies more ways to use money to make money.

1973 US economists Fischer Black and Myron Scholes devise a mathematical formula that appears to take the risk out of futures contracts.

1980s Large corporations begin to use derivatives to make money from money.

2007–08 Financial markets collapse around the world, threatening the continued existence of banks and banking-type ventures.



Companies with a good cash flow and **liquidity** can make money from money, by…

…**investing in financial products** such as derivatives and futures contracts.

…**borrowing short-term** and lending to customers long-term, like a bank.

But this can prove to be a **money-losing exercise** if there is a crash in markets or the economy.

Making money from money is a **risky, short-term strategy**.

Some companies opt to "make money from money." This means they use their cash assets not only to further the development of their products, but also to generate money through the financial markets. Some companies believe that by making hedges (bets) on the fluctuations of the currency markets, for example, they can gain access to a new source of profit. The two terms that exemplify the idea of making money from money are "treasury function" and "shadow banks."

Hedge betting

"Treasury function" is a term that emerged in the late 1970s in the wake of economic challenges, such

See also: Managing risk 40–41 ▪ Hubris and nemesis 100–03 ▪ Investment and dividends 126–27 ▪ Who bears the risk? 138–45 ▪ Leverage and excess risk 150–51

Fibria
Unidade
Aracruz

Many manufacturing companies, such as Brazilian paper company Aracruz (known as Fibria since 2009), used the treasury function to make money, not just manage it, from the 1980s onward.

as quadrupled oil prices and "stagflation" (where inflation and unemployment are both high at the same time). The idea emerged that the goal of a company's treasury function (the department responsible for stewarding its finances) should be to achieve the optimum balance between liquidity and income from the company's cash flows.

During the decades leading up to the 2007–08 financial crisis, large companies steadily added greater responsibilities to the treasury function. Often, these began as ways to minimize risk, but the opportunities for profitable trading became very tempting—to the point that some companies took out contracts on financial hedges that were worth more than all their export earnings. For example, in 2008, the Brazilian paper and pulp company Aracruz used cash assets to make bets on currency futures (the value of currencies at a future date). Specifically, it bet that the Brazilian currency would continue to rise, but in fact it underwent a sharp devaluation and the company ended up losing $2.5 billion.

As a result, some companies now spell out their opposition to making money from money. Mining multinational Rio Tinto, for example, stated in its 2013 annual report that its treasury "operates as a service to the businesses of the Rio Tinto group and not as a profit center."

Shadow banks

Other companies, however, have extended the treasury function to become a major, or even majority, profit center for the business. Companies such as US conglomerate General Electric (GE) have developed this function into an effective "shadow bank." In 2007, GE's treasury function GE Capital held over $550 billon of assets, making it larger than some of America's top ten banks. It contributed 55 percent of GE's profits, mainly by borrowing money short-term to lend to customers over the long-term ("borrowing short and lending long"). GE was able to flourish as a member of the shadow banking system without having to bear the regulatory burdens of banks. By 2008, however, it was forced to ask to participate in the US government's banking sector bail-out program.

Making money from money carries serious risks, whether the bets go wrong or not. This is because the more profits a company's treasury generates, the less willing the board may be to invest in research and development for the future growth of the company. This way of making money from money is strongly correlated with short-termism in business. ■

Treasury in focus

For the decade prior to the financial crisis of 2007–08, many companies began to use short-term financing to fund long-term capital expenditure. However, the financial crisis of 2007–08 changed conditions dramatically, as banks collapsed or came close to doing so. CEOs demanded to know where their company's cash was, and the real-time cash position. Not all treasurers were able to provide immediate answers, since some of their investments were in local, manually operated, less-than-transparent systems.

As a result, the treasury function has moved to the forefront for many companies, with an increased need for transparency and up-to-the-minute accountability. Boards expect treasurers to be prepared for the unexpected—such as by increasing cash reserves to reduce liquidity risk. However, this brings up a new problem for the treasury function: if more cash is kept in reserve, how can this surplus liquidity be used most effectively to fund growth?

> “The line separating investment and speculation is never bright and clear.”
>
> **Warren Buffett**
> **US investor** (1930–)



THE INTERESTS OF THE SHAREHOLDERS ARE OUR OWN

ACCOUNTABILITY AND GOVERNANCE

IN CONTEXT

FOCUS
Executive control

KEY DATES
1981 Australian-born US management consultant Peter Drucker suggests that chief executives "have not yet faced up to the fact that they represent power—and power has to be accountable."

1991 The Cadbury Committee is established in the UK to investigate scams, failures, and accountability in corporate governance. Its influential report, *Financial Aspects of Corporate Governance*, is published a year later.

2002 The US government's Sarbanes-Oxley Act sets out much stricter guidelines to govern accounting practices and the publication of previously confidential data (such as operational business risks).


Good governance relies on...
...proactive, ethical, **well-informed directors**.
...clear, traceable **lines of responsibility**.
...**alert board members**.

Accountability is the obligation of an individual or organization to accept responsibility (be accountable) for their actions. In business, it is often used to trace chains of responsibility: staff may be held to account for their actions by those above them in the organization's hierarchy; or higher tiers of management may be held accountable for those below them. Ultimately, the way the company is governed is the responsibility of the directors; their governance should therefore be proactive and ethical.

Following a series of business disasters (from Enron through to Lehman Brothers and numerous banks), corporate governance has become a major issue worldwide. To achieve effective accountability, directors need to make sure that roles and lines of authority are clear. This makes it possible to trace the cause of a mistake to its source—and attribute responsibility to the right person or group. For governance to work well, board members must be well-informed, fully independent, and should work together for the long-term interests

See also: Profit before perks 124–25 ▪ Who bears the risk? 138–45 ▪ Profit versus cash flow 152–53 ▪ Balancing long- versus short-termism 190–91

Companies that bury their heads in the sand—like the proverbial ostrich—may be reluctant to be held accountable for actions and decisions, with damaging consequences for business ethics.

of the business and its owners—the shareholders. Nonexecutive directors have an important role to play in corporate governance: they are not company employees and should be able to quiz executives with impunity.

Board-level scrutiny

In 2011, consultants McKinsey & Company published findings from a survey of 1,597 board directors, providing fascinating insights into the proceedings of board meetings. The survey showed that in Asia, no more than a third of a board's meeting time was spent scrutinizing management actions and decisions; far longer was spent on strategic planning. Although this sounded sensible, it suggested that accountability and governance received less time. By contrast, in North America nearly two-thirds of board time was spent on scrutiny.

More surprisingly, the same sample showed a lack of satisfaction with fellow board members. Directors thought that more than 30 percent of their peers had limited or no understanding of the risks their company faced. This suggested a flaw in the ability of the board to hold executives to account.

Most of the time, in most companies, executives make sound decisions that require minimum scrutiny. However, good governance ensures that the board is always alert—so it will be fully aware of what is happening when a mistake is made. Such a mistake might be related to strategy (an overpriced takeover bid, for example), or to the ethics of a particular situation. Independently minded nonexecutive directors should be in a prime position to question, for example, whether the company is right to be using very low-cost suppliers, or whether a contract has been won using questionable means.

When things go wrong

The importance of good governance was made clear in the case of Japan's mighty Olympus camera business in 2011. Newly appointed Chief Executive Michael Woodford found that a $1.7 billion cover-up of losses had been made when acquiring other companies. The Olympus directors had hidden these losses from the published accounts and therefore from public scrutiny. The board responded by firing Woodford. Only after a successful campaign by Woodford did the Japanese authorities charge key Olympus directors with fraud. Eventually the whole board resigned. The case demonstrated how ineffective Olympus's nonexecutive directors had been in holding the board to account, and how important good governance and accountability are to the well-being of every company. ■

Jamsetji Tata

Born on March 3, 1839 in South Gujarat, India, Jamsetji Tata might have appeared an unlikely candidate to be the founder of a business that would grow to be one of the largest conglomerates in the world. Tata followed his father—who had broken the family tradition of being a Brahmin priest—into business at 14 and soon showed potential, graduating from Elphinstone College in Mumbai in 1858. After working for his father, Tata took on his first enterprise—a cotton mill—in 1868. One of his dreams was to found a steelworks, and although this business aim would not be achieved in his lifetime, Tata Iron and Steel Company was set up in 1907 by his son Dorabji. The steel industry went on to be the foundation for Tata Group's global success.

One of Jamsetji Tata's overriding principles was fairness, which permeated his entire business approach. In terms of accountability, his vision was simple: "We started on sound and straightforward business principles, considering the interests of the shareholders as our own."

> Accountability breeds response-ability.
>
> **Stephen R. Covey**
>
> **US management consultant** (1932–2012)

MAKE THE BEST QUALITY OF GOODS AT THE LOWEST COST PAYING THE HIGHEST WAGES POSSIBLE

YOUR WORKERS ARE YOUR CUSTOMERS

IN CONTEXT

FOCUS
Market expansion

KEY DATES

1914 Henry Ford doubles his employees' wages to $5 a day.

1947 US psychologist Alfred J. Marrow finds that productivity increases when employees are involved in decision making, and introduces the concept of participative management.

1957 Douglas McGregor publishes *The Human Side of Enterprise*, claiming that organizations thrive best by trusting staff to apply their creativity and ingenuity to the enterprise in which they work.

1993 Ricardo Semler of Brazil's Semco writes *Maverick!*.

2011 Google is revealed to have the highest job satisfaction in the US high-tech sector; young "Googlers" are both employees and customers of the company.

Most economic models state that during the early stages of economic development, low-wage workers find themselves making products that are bought by middle- and upper-class consumers. The workers tend to eat simple food, such as potatoes, rice, or corn, and travel on foot or—if they are lucky—use a bicycle as a means of transportation. Meanwhile, their employers eat expensive meat-based meals, and travel in luxurious transportation—from the fine horse carriages of the 17th century to the sleek, "dream machine" automobiles of today.

However, economic growth takes a huge step forward when workers are able to buy the products that they make; when they, too, can afford to eat meat and purchase household and leisure goods. This is now starting to happen rapidly in China, where the the sales of staple products—such as toilet paper and refrigerators—are growing quickly.



The Ford Motor Company quickly realized that its production line was efficient but made workers unhappy. By giving them a large pay rise, Ford created a market of staff-customers.

Building a market

Workers were recognized as potential customers by US car-making pioneer Henry Ford. Ford's Model T automobile was priced at $825 in 1908, at a time when Ford workers earned less than $2 a day. In 1913, Ford introduced a system of conveyor-belt mass production, reducing the time taken to make a Model T from 750 to 93 minutes. With this improvement in efficiency, the company could afford to cut the price of one of its vehicles to $550.

One problem remained, however. The repetitive jobs required to run the Model T production line made



Companies should focus on providing consumers with **good products and services at low prices**.

They should also reward their employees with the **highest wages** possible.

This enables employees to **buy the company's products** or services.

They can then provide management with **valuable insights** and ideas, as well as **boosting sales**.

If your workers become your customers, your **business will thrive**.

See also: Changing the game 92–99 ▪ Organizational culture 104–09 ▪ Understanding the market 234–41 ▪ Focus on the future market 244–49 ▪ Make your customers love you 264–67 ▪ Maximize customer benefits 288–89

workers dissatisfied, and pushed labor turnover to higher than 370 percent—the average employee stayed for only three months before quitting. To counter this, Ford announced that wages at the company's factories would be more than doubled, to $5 a day. His actions made headlines around the world, and in the factory, labor turnover fell to 16 percent annually, helping the output per worker (a measure of overall productivity) to rise by around 40 percent.

By 1914, it took a Ford worker just three months to save enough money to purchase a Model T. By 1924, the price of a Model T fell again to $260, making it possible to buy a brand new car with a month's pay. By 1924, the Ford Motor Company sold more than 50 percent of the world's cars.



Household spending data from 2011 shows that US spending on luxury goods (such as chocolate) outstripped spending on essentials (like toilet paper). The data from China shows that as an economy develops, spending on essential items rises the most.

Learning from employees

Although Henry Ford generated excellent publicity by making his policy of paying high wages sound like altruism, his practical need to lower the labor turnover helped him stumble upon an important fact: when your workers earn enough to afford to be your customers, there can be huge benefits for the business. Along with increases in staff pride and commitment, managers are likely to be given valuable insights into the company's products and processes.

In Toyota City, Japan, more than half the work force owns a Toyota vehicle. This is a significant factor in helping to generate the 400,000 work force suggestions per year on how the company might improve production efficiency and quality.

Emerging markets

In 1924, the US government published a report titled *Cost of Living in the USA*. It showed that the average family spent 38 percent of its $1,430 annual expenditure on food. This is interesting because, in the past five years, India's family spending pattern has slipped below this level, to 36 percent, indicating that the average wealth of Indian families is increasing. When China's proportion of spending on food fell toward 30 percent of income, households could afford to increase their wider spending on nonfood items, such as consumer goods. In the US today, just 7 percent of household income is spent on »

Farm wages in India increased by 17.5 percent annually from 2007 to 2012. Since farm labor is at the bottom of the economic pyramid in India, this signifies a very fast overall rise in wages.



Car sales in China and India grew steadily from 2005 to 2012. The potential for sales is huge—percentage ownership in both countries is tiny compared to the US, where ownership is high and sales remained static.

food, leaving the average family with a huge surplus with which to buy nonessential items that quickly become "necessities," such as cosmetics and gym membership. India is perhaps about to embark on this stage of economic development. If so, this will have an impact on the sales of a huge range of everyday items.

The significance of this trend lies in the numbers of people involved. If India, over the next five years, boosts its spending on toilet paper to China's per-capita spending, the market growth in India will be $8.4 billion ($6.72 x 1.25 billion population). For China to catch up with the US would imply market growth of $24.3 billion ($17.98 x 1.35 billion population). And that's just the increase in market size—not the total market.

> I will build a car for the great multitude … [that] will be so low in price that no man making a good salary will be unable to own one.
>
> **Henry Ford**
>
> **US industrialist (1863–1947)**

Exactly the same logic applies across the market for ordinary household goods throughout the developing world. Already, China is the world's biggest market for luxury items, such as Swiss watches, jewelry, and cars. Over the coming decades, China is also likely to dominate sales of ordinary items (such as toothpaste), and services (such as insurance). The potential sales volumes involved are huge. Today, China is the world's largest car market, even though fewer than 10 percent of households own a car.

In touch with reality

The television show *Undercover Boss* sends senior executives into low-level jobs in their own companies, under alias and disguise, to find out what the business looks like from that perspective. The show clearly illustrates how those in charge of a business are often unaware of the opinions, insights, and feelings of their customers and staff. Despite a world of online praise and blame, some companies are able to remain in a bubble of self-delusion.

However, this is unlikely to be true of an organization in which the worker is also the customer. These employees care about the product or service because they experience it themselves and realize that their job security relies on customer satisfaction and the company's commercial success. If a customer waiting room becomes messy and dirty, for example, staff-customers will quickly draw attention to it.

In Europe, fashion retailer Primark enjoys huge success in the mainstream market. The company turns runway fashion speedily into low-priced garments with a target market of 15–35-year-olds. However, its growth was instigated by an unusually elderly senior management team. By

Clothing retailer Primark has built a reputation for low-cost fashion in the European ready-to-wear market. Its success is due in no small part to the opinions of its workers.

the time Primark had reached its strongest phase of growth in the 2000s, its senior executives were in their 60s and 70s. It was critical, therefore, for directors to listen to the young work force, who could give insights into customer views.

Democratic management

Ricardo Semler, head of Brazil's Semco Group, is perhaps the world's most radical employer. He believes that bosses need to move beyond empowerment toward worker fulfilment, even delight. Born in 1959, Semler took over the business from his father at the age of 21. Between 1982 and 2003, he drove Semco's sales turnover from $4 million to $200 million. On his first day in the office, he fired nearly two-thirds of the senior management team, who he believed were too rooted in his father's autocratic management style. In the late 1980s, he backed a proposal by three of his engineers to start a special new business division. This became the nucleus of a new Semco, developing new ideas that soon generated 66 percent of the company's business.

Semler's leadership approach is to encourage his work force to manage themselves in terms of time-keeping, work-scheduling, and career development. By doing so, he believes that workers will truly care about what they do; this means that they will inevitably be taking care of not just the business, but its customers too.

Semler describes his methods in his book *Maverick!* (1993) and outlines how much companies can benefit from the staff engagement that results. This approach has become known as participative management. It holds that people are naturally capable of self-direction if they are committed to corporate goals. And when your workers are your customers, the two sets of goals become perfectly aligned. ■

> Work should be a pleasure, not an obligation …
> We believed that people working with pleasure could be much more productive.
>
> **Clóvis da Silva Bojikian**
> **Brazilian former HR officer of Semco**
> **(1934–)**

Arthur Ryan

Born in Ireland in 1935, Arthur Ryan is the founder of Primark. After leaving school, Ryan worked at a department store and then a fashion wholesaler in London before returning to Dublin, where he worked for retailer Dunnes Stores. In 1969, Garfield Weston, CEO of Associated British Foods (ABF), hired Ryan to set up a discount clothing chain with a seed fund of $80,000 (£50,000). The first store, Penneys, opened later that year in Dublin, but Ryan changed the name to Primark for the business model that he was to use in the UK, the Netherlands, and Spain. From 1973 until his retirement in 2009, Ryan built up the business to change it from being a "bargain" store to an inexpensive, on-trend fashion retailer. In 2013, Primark employed more than 43,000 staff in stores in Ireland, Spain, the UK, Austria, Belgium, Portugal, Germany, and the Netherlands. ABF is still its parent company. In the recessionary year of 2009, Primark's like-for-like sales grew by more than 7 percent.

UTILIZE OPM
OTHER PEOPLE'S
MONEY

WHO BEARS THE RISK?

IN CONTEXT

FOCUS
Financial risk

KEY DATES

1950s US economist Harry Markowitz advocates gathering a portfolio of investments to protect against losses due to financial risk.

1990s Research on types of financial risk identifies ways of measuring and managing different kinds of risk, including market risk (changes in the value of equity, interest rates, currency, and commodities) and credit risk (the risk of nonpayment of debts).

1999 UK conglomerate General Electric Company (GEC) is renamed Marconi plc, and its traditional businesses are sold off. The directors' gamble on this change in strategy fails—the business collapses in 2001 and shares are suspended. Nearly 25 percent of staff is laid off.



When a business is financed with **debt**, or with **other people's money**...

...a small **investment in shares** can yield control of the company.

This increases the chances of **huge profits for the business owners**...

...while the **costs of failure** are largely borne by the work force...

...and the company's middle managers, who take the blame for **poor performance**.

Heads I win; **tails you lose**.

The degree of financial risk borne by a company has profound implications for the long-term viability and success of the business, its employees, and its shareholders. A business structured in a traditional manner would put the most risk on the shareholders, since they stand to lose their investment if the venture fails. But the proliferation of increasingly complex financial mechanisms and means of accounting have, to a degree, insulated a business's owners from the worst effects of failure.

Greek shipping magnate Aristotle Onassis built a business empire that stretched across the world and incorporated dozens of industries, and was underpinned by complex financial arrangements. Onassis recommended utilizing "other people's money," and while this approach might yield financial success, it may end with others bearing the costs of failure.

Traditional risk

In theory, the risk takers in a market economy are the shareholders, who effectively "own" the business. The shareholders' capital finances the business start-up, and remains at risk until it is repaid in full. If the business liquidates, the holder of "ordinary" shares (as opposed to "preferred" shares, which are higher in ranking and yield dividends before ordinary shares) is the last in the line to be paid. The ordinary shareholder is therefore the least likely to recover his or her investment. Because of the risks they take, entrepreneurs are held in high esteem. So are early-stage, venture-capital investors, who invest in start-ups in return for equity.

See also: Managing risk 40–41 ▪ Play by the rules 120–23 ▪ Accountability and governance 130–31 ▪ Leverage and excess risk 150–51 ▪ Off-balance-sheet risk 154 ▪ Balancing long- versus short-termism 190–91 ▪ Morality in business 222



Venture capitalists, such as Indian-born Vinod Khosla of Sun Microsystems, invest in companies at an early stage and risk bearing the brunt of failure. But returns can be high with success.

The burden of risk associated with a business is spread wider as its financial affairs grow more complex. Executives and staff stand to lose financially and perhaps even punitively—with prison sentences possible—if the company fails. Creditors and shareholders can lose financially, while in the worst-case scenario taxpayers may bear the heaviest burden of all—in the form of high taxation and low economic growth—if their government chooses to rescue the business.



The association of risk with the shareholder is beneficial in many respects. A risk-bearing shareholder in a large, multinational bank would be inclined to discourage senior management from taking large risks with the bank's capital or reputation. Calculated risks may be considered, but not risks that threaten the existence of the business. The shareholder can play a significant part in the business process, acting as a natural check on the company's propensity to take risks. This view of business has been held since the foundations of modern capitalism in the 18th century.

Suppliers and creditors

The traditional view may be threatened due to effects of new rules and practices. In an attempt to encourage entrepreneurship, Chapter 11 of the US bankruptcy code gives a struggling business substantial protection from those to whom it owes money (its creditors, such as suppliers of raw materials, ingredients, or subsidiary services). This protection is intended to allow a company to rethink its business plan and perhaps find a more profitable business model.

In the UK, a struggling company can choose to enter a phase of "pre-pack administration," in which the business's assets are sold after it has entered bankruptcy. The assets and operating model are sold to new owners, leaving the original business entity behind. Suppliers and other creditors may receive no more than a token payment, such as 10 percent of the value of their claims on the business. The new shareholders then have a debt-free business with all the assets of the old company, but with none of the »

Suppliers are among the last to receive compensation for their goods or services if a business goes bankrupt. If, in the UK, it enters "pre-pack administration," suppliers might receive nothing at all.

liabilities. This method can be especially controversial, since it can allow the owners of the original business to sell the "pre-packaged" new entity and still be involved in the business. In August 2008 the London-based restaurant business of Michelin-starred chef Tom Aikens went into administration. It was bought by TA Holdco Ltd., of which Aikens was appointed partner and shareholder. Around 160 suppliers were left nursing losses that would never be recovered. However, by early 2010 Tom Aikens' business achieved a financial turnaround, and opened three new ventures in London.

When pre-pack administration is utilized, suppliers are revealed to be in a much more vulnerable position than might otherwise be expected. The financial losses incurred by Aikens's restaurants were effectively absorbed by suppliers, not shareholders. In a world of pre-pack administration and Chapter 11 bankruptcy protection, the creditors can find themselves in a riskier position than the shareholders.

Employees at risk

Staff employed by a business is also at risk when a company fails. When US energy company Enron collapsed in 2001, an extraordinary feature of the unfolding story was the plight of many employees. Unlike the senior executives, rank-and-file staff had been part inspired and part browbeaten into "showing faith in Enron" by investing personal pension funds in Enron shares. When the business was liquidated, employees not only lost their jobs, but also their pensions. When the collapse of the business was becoming clear, Enron froze its pension fund, preventing employees switching their pension holdings out of Enron shares.

Employees can also be vulnerable due to the predations of the investment market. If a company is bought through private equity, employees can find themselves worse off if the business fails. A private-equity purchase is when a publicly traded company is bought by a "private-equity group," often through a leveraged buy out, where the assets of the purchased company are used as security to borrow funds with which to finance the purchase. In so doing, the burden of risk is on the business (and its employees), not on the owners.

The UK franchise of Canadian underwear business La Senza collapsed in 2012, with 1,100 employees losing jobs. In cases like this, the staff has little to gain when things go well, but everything to lose when they go wrong. Suppliers

"Heads I win"—in good times, the business owner stands to gain, whereas the position of employees changes little.

"Tails you lose"—in bad times, the owner is protected from losses, but the business and its employees suffer.

Private-equity ownership is typically structured in an asymmetric way. If things go well the private-equity owner gains, and if things go badly the subsidiary business loses.

are in the same position. Only the private-equity shareholders are protected—by limited liability.

When publicly traded soccer team Manchester United was purchased by US businessman Malcolm Glazer and his family in 2005, the transaction was effectively a private-equity deal. The Glazers followed standard practice, buying the publicly-listed company for $ 1.3 billion, then put the debts onto the balance sheet of the new Manchester United Ltd. Private-equity owners suggest that debt is an effective means of forcing employees to work efficiently to make a profit and meet interest payments. More plausibly, though, it is a way of transferring risk from the private-equity owner to a limited liability subsidiary. If Manchester United Ltd. were to enter financial trouble, the liability of the Glazers would be minimal due to the protection of “limited liability,” which limits the owners’ liability to the value of their investment, not the total debts of the business.

Research published in 2013 compared the performance of 105 companies purchased through private equity and 105 “control” companies in the same industries. They were investigated over a ten-year period—the six years leading up to the buy out, and the four years after it. The researchers found that in the year following the buy out, 59 percent of the private-equity owned businesses cut their staffing levels, compared with 32 percent in the control group. In the following years, private-equity ownership was associated with falling average wage levels among staff. In the short term employees appear to lose out—and in the medium to long term their chances of losing their jobs are higher due to the greater level of debt of the companies they work for.

> “We have corporate CEOs who raise their pay 20 percent or more in years when they lay off thousands of people. It’s obscene.”
>
> **Charles Handy**
>
> **UK management expert (1932–)**

Private-equity iniquity

Not everyone loses out under private equity. In 2003 the British retailer Debenhams was purchased by three private-equity companies. The businesses paid themselves a dividend of $1.9 (£1.2) billion before floating the publicly traded Debenhams onto the stock market in 2006—laden with debt. Years later, in its 2012 annual accounts, the financial strain still showed. The degree of “gearing” (debt as a percentage of capital employed in the business) at Debenhams was a high 51.5 percent, and its liquidity (as measured by the “acid test ratio,” which determines whether a company has enough short-term assets to cover its immediate liabilities) was a very weak 0.175. Yet for the private-equity owners, the deal was highly profitable—they made $1.9 (£1.2) billion very quickly and still retained shares in Debenhams (a stake that was sold in the years that followed). Their overall profits exceeded 200 percent.

For the bosses of private-equity companies, the rewards can also be impressive. Bernard Schwarzman of US private-equity investment company Blackstone Group earns $130 million a year. He is closely followed by the bosses of Carlyle Group, Apollo Global, and KKR—who each earn in excess of $100 million a year. Remarkably, all these bosses enjoy favorable tax treatment in both the US and the UK. This became an important issue in the 2012 US presidential election, when Republican candidate Mitt Romney (a former private-equity boss) had to admit that his income tax rate, at 14 percent, was lower than that of average, working Americans.

> “There is a simple way of avoiding excess risk taking by the managers of our financial institutions. It is to make it a crime.”
>
> **Paul Collier**
>
> **UK economist (1949–)**

Executives on the hot seat

In the world of public limited companies and corporations, the CEO might be in the riskiest position of all. They may have the most to gain from their business’s success, but also the most to lose from its failure. These risks may be partly financial, but even more they are reputational. Richard Fuld, chief executive of Lehman Brothers at the time of its 2008 bankruptcy, went from being an award-winning CEO to a nominee for a range of “worst ever…” awards. From being a director of the Federal Reserve Bank of New York, he became a pariah. »

NATURA PREMIUM
Latte
PARZIALMENTE SCREMATO UHT
parmalat

Italian food giant Parmalat's 2004 $1.6-billion accounting cover-up was primarily due to fraud. The effects were sharply felt by shareholders and the many employees who lost their jobs.

In the UK, a similar fate awaited figures such as Fred Goodwin (CEO of Royal Bank of Scotland when it collapsed in 2008) and James Crosby (CEO of Halifax Bank of Scotland until 2006). Both were blamed for the dramatic collapses of their banks in 2008, and for their part in the subsequent economic turmoil.

Is it fair that a company's bosses should have to take the blame for failure so personally? After all, it is inconceivable that the CEO is the only one to blame for the failure of a business. Objectively, the answer is clear, because business failure is certainly the responsibility of more than just the CEO. Yet high-profile executives often strive to associate themselves so closely with the company—making it seem as though they personally are the business—and are so eager to back this up with massive remuneration packages, that it can be no surprise when the public and the media turn on them.

Taxpayers to the rescue

In mature, developed economies, businesses are supposed to take risks in pursuit of reward. Failure should, on this basis, lead to the death of the business. Austrian-American economist Joseph Schumpeter, in his classic 1942 book *Capitalism, Socialism, and Democracy*, made the famous statement: "The process of Creative Destruction is the essential fact about capitalism." Schumpeter, like many others, viewed recessions as a cleansing mechanism, allowing the weak to fall back and new, stronger companies to emerge.

Yet modern governments seem to see things differently, certainly in relation to large businesses. The term "too big to fail" illustrates that business risks have been transferred to the taxpayer. Faced with the bankruptcy of General Motors and Chrysler in 2009, the US government—in other words, US taxpayers—took on billions of dollars' of debt to give the companies a fresh start. In the UK and Europe, bank bailouts in 2008 and 2009 saved the private sector from huge losses. In Europe, what was put forward as a Eurozone government problem was in fact a private-sector problem, as banks faced nonrepayment of loans to businesses within Greece, Portugal, or Italy. The bailouts were arranged and financed by governments, meaning that taxpayers turned out to be the risk takers, even though nobody asked their opinion. American economist Nouriel Roubini summed this up by saying: "This is again a case of privatizing the gains and socializing the losses; a bailout and socialism for the rich, the well-connected, and Wall Street."

This issue has stretched far wider than the US and Europe, influencing the economic situation in both Japan and China in recent decades. From the start of its 20-year depression in 1990, land prices in Japan fell by more than 80 percent, and today remain far below the levels reached in 1988 before the recession began. In effect, almost every bank in Japan was insolvent as a result of vast portfolios of nonperforming loans—loans that were made to companies that could neither repay the debt, nor pay the interest on that debt. Only the support of the Japanese central

> “
> Risk comes from not knowing what you are doing.
> **Warren Buffett**
> **US investor (1930–)**
> ”

bank kept these commercial banks alive. The taxpayer took on the risks that are supposed to be taken by the private sector. Many analysts suggest that the same is true in China at present, although the opacity of the Chinese banking system makes this hard to verify.

Who bears the risk?

Roubini's statement that losses are "socialized" (borne by the public) while profits remain in the private sector appears to be true. Income inequality has widened considerably around the world in recent decades, in countries including the US, UK, China, and India. For instance, between 1979 and 2007 in the US, the income of the top 1 percent of earners rose by 266 percent, while that of the bottom 20 percent rose by only 37 percent. Government bailouts for big business effectively mean that taxpayers are providing support for those who benefit most from today's economic system. In the long run, businesses may enjoy substantial profits, and accept the rewards as recompense for the risks they take. But if the risks (and losses) are borne by the taxpayer, it is fair to question why only shareholders gain the profits in the good times.

Often, employees and suppliers bear higher levels of risk than seems fair—shareholders, who enjoy the rewards of success, should bear the primary risk of failure. Even trade-union protection for workers has been eroded in recent decades—in the US and many countries around the world, unions account for no more than 10 percent of private-sector employees, which leaves workers unprotected when things go wrong. Although labor flexibility has its merits, imbalance between "my risk" and "your reward" has perhaps gone too far. ■

Greek citizens protest in Athens against austerity measures in 2011. Rescue loans from the European Union to Greek banks mean that the country faces years of economic hardship.

Richard Fuld

Richard "Dick" Fuld was born in 1946 in New York City, NY. He graduated from the University of Colorado in 1969, and received an MBA from the Stern School of Business in 1973. He was CEO of Lehman Brothers investment bank from 1994 to the day of its collapse in 2008, and during that time, he received more than $500 million. Known as the "Gorilla of Wall Street," Fuld was the domineering boss who pushed the company into the subprime mortgage business. For many critics, the decision that illustrated his hubris was his refusal of bailout funds from investor Warren Buffett and the Korea Development Bank, even though Lehman Brothers was in the throes of being toppled by the 2008 credit crunch. His reasoning was that the offers of cash did not match his own valuation of Lehman Brothers. Following the company's bankruptcy in September 2008, *Time Magazine* named Fuld as one of the "25 People to Blame for the Financial Crisis," and *Condé Nast Portfolio* magazine ranked him number one on its list of "Worst American CEOs of All Time."

SWIM UPSTREAM. GO THE OTHER WAY. IGNORE THE CONVENTIONAL WISDOM

IGNORING THE HERD



IN CONTEXT

FOCUS
Business behavior

KEY DATES
1841 Scottish journalist Charles MacKay documents herd behavior in his book, *Extraordinary Popular Delusions and the Madness of Crowds*.

1992 Indian economist Abhijit V. Banerjee publishes *A Simple Model of Herd Behaviour*.

1995 In "Herd Behaviour, Bubbles and Crashes," German professor Thomas Lux claims prices and sentiment affect one another, so feelings of the herd affect prices (for example, faith in the housing market pushes up prices).

2001–06 The housing bubble in the US and parts of Europe gathers pace before collapsing in the 2007–08 financial crisis.

The herd instinct is clear in nature and just as clear in business. Most people feel more comfortable following what others are doing than standing out as a "loner" or maverick. Ignoring the herd takes great psychological strength. When stock markets rise steeply, new—perhaps first-time—investors get sucked in by the apparently easy pickings. These latecomers to a booming "bull market" cause share prices to propel upward for a last time before they slump back toward their previous value. By following the herd in this way, most first timers invest when share prices are near the top and usually sell when they find that their

See also: Stand out in the market 28–31 ▪ Gaining an edge 32–39 ▪ Beware the yes-men 74–75 ▪ Thinking outside the box 88–89 ▪ Avoid groupthink 114 ▪ Protect the core business 170–71 ▪ Forecasting 278–79



Companies follow **herd instincts** when they…

…**stampede to buy** shares in high-trend businesses, or buy them completely.

…buy other businesses because of a **current market trend** in **diversification**.

…develop **"me too" products** rather than follow logical strategy.

These actions are unlikely to be financially beneficial.

Swim upstream. Go the other way. Ignore the conventional wisdom.

assets have dropped in value. They often suffer serious losses. A contrarian investor—or a savvy company that holds a portfolio of investments—does the opposite. When share prices rise and new investors are attracted into the market, they sell, and if the market slumps, they buy. However, few investors show the foresight required to know when a boom is turning to bust. Warren Buffet, a legendary investor, says: "We simply attempt to be fearful when others are greedy and to be greedy only when others are fearful." Between 1965 and 2013, Buffet's investment company gave investors a capital gain of more than 900,000 percent.

An example of the risks of following the herd came with the dot-com bubble, between 1998 and 1999. Among numerous examples of extraordinary share-price gains followed by equally huge losses, was the business eToys.com, which was opened in 1997. In May 1999 it was launched onto the New York Stock Exchange at $20 per share, raising $166 million. Buyers piled in, pushing the price up to $76 by the end of the first day. By fall 1999, the share price was $84, giving the business a higher market value than the retail giant Toys R Us. As the market turned downward, the experts started to sell, leaving the herd with the shares. And by February 2001, the share price had fallen to 9 cents. A little later the business was declared bankrupt. »

> “The herd instinct among forecasters makes sheep look like independent thinkers.”
>
> **Edgar R. Fielder**
>
> **US economist (1930–2003)**



Global market shares of smartphones in 2009–13 varied greatly: Apple stayed relatively stable; Nokia and RIM, who had responded with herd instincts to the iPhone's success, saw huge losses; Samsung's shares soared, reflecting its development of products that would stand the test of time.

It makes sense for the share-buying public not to follow mass trends, but is the same true for business leaders? In 2008, US mass-media corporation AOL, noticing the growth in social network sites, bought the social-networking site Bebo for $850 million. It joined the herd and lost out badly. In 2013, it sold the same business back to its founders for $1 million.

Following trends

Business leaders, then, must be as cautious as anyone else about treading the same path as the majority. There are three main types of herd to ignore. The first, as mentioned, is the occasional stampede to make takeover bids. In this case, business leaders worry that if they do not buy a rival, someone else will and perhaps create a bigger, more difficult competitor. At such times, there is much talk of synergies (the sum being worth more than the parts) but little mention of long-standing research, which suggests that 60 to 66 percent of all takeovers destroy shareholder value for the winning company. In other words, most takeover bids prove to be a disappointment.

The second herd behavior to ignore is the strategic clash between focus and diversification, and the way the market tends to concentrate on one of these two at any one time. When "focus" is the market mantra, share prices rise in companies that sell off peripheral assets or divisions of the business. This is what happened to British Aerospace (BAe) when it sold its 20 percent stake in the Airbus aircraft business in 2006. At the time, the stock market liked its $2.99 (£1.87) billion sale of the largely civilian aircraft maker, since it focused BAe on the defense and military sector. By 2013, this view looked absurd, as Airbus powered ahead but governments—especially the US—cut back on military spending. A worried BAe then approached the owner of Airbus, suggesting a merger and implying that a mix of civilian and military businesses was a preferable focus. Could things really have changed that much between 2006 and 2013, or was BAe responding to the trend for diversification? Strong business leaders look to the long-term and ignore fads and fashions among stock-market analysts and management consultants.

Following the leader

The third herd behavior to avoid is "followership." This occurs when companies develop "me-too" products to imitate market innovators. Of course, if a business already has a genuinely differentiated offering, it is wise to follow a new trend. Often, though, businesses rush out copycat products to demonstrate that they are staying competitive in a sector. When the iPhone was launched in 2007, Nokia could boast more than 40 percent of the global smartphone market. Despite a series of new product launches by the company,

> Those entrapped by the herd instinct are drowned in the deluges of history. But there are always the few who observe, reason, and take precautions, and thus escape the flood.
> **Anthony C. Sutton**
> **UK economist (1925–2002)**

> We find that whole communities suddenly fix their minds upon one object, and go mad in its pursuit.
> **Charles MacKay**

its share of smartphone sales collapsed to around 3 percent in the first quarter of 2013. Throughout this period, Nokia was desperately trying to catch up with Apple's iPhone—but doing no more than throwing new products at the problem, instead of taking a deep strategic breath and deciding what innovations might earn it a stake of the market.

The contrast between Nokia's behavior and that of Apple's could not be greater. In 2008 and 2009 the big trend in mobile computing was away from laptops and toward "netbooks." In 2009, global netbook sales rose by 72 percent. The herd instinct of businesses such as Dell was to produce their own netbook. At Apple, by contrast, boss Steve Jobs announced that "the problem with netbooks is that they're not better than anything." He worked to develop a superior alternative to netbooks—the iPad. By mid 2013 the iPad had sold more than 145 million units and the original makers of netbooks (Taiwan's Asus) had halted production completely.

Those who ignore the herd can apply cool logic to their situation and think ahead to possible future scenarios. The herd tends to think that tomorrow will mean more and more of today. Those who ignore the herd can identify fundamentals that persist over time, while looking toward what might be different tomorrow. As US entrepreneur Sam Walton advised, it often makes sense to "swim upstream." ■

The success of the iPad reflected Apple's resolve to develop a superior alternative to the "netbook." Companies like Apple and Samsung need to be ahead of the herd, not behind it.

Warren Buffett

Generally considered the most successful investor of the 20th century, Warren Edward Buffett was born on August 30 in 1930 in Omaha, NE. He demonstrated an early ability with mathematics and was able to add large columns of numbers in his head. His father was a stockbroker and congressman.

Buffett began investing at the age of 11. He started several small businesses while still a teenager, before going to the universities of Pennsylvania, Nebraska, and Columbia to study business. In 1956 he formed the company Buffett Partnership, where his investment successes led to his nickname, "the Oracle of Omaha." In 2006 he announced that he would be giving his entire fortune to charity. In 2012 his net worth was estimated at $44 billion.

Key works

2001 *The Essays of Warren Buffett: Lessons for Corporate America* (with Lawrence A Cunningham)
2013 *The Essays of Warren Buffett: Lessons for Corporate America, Third Edition* (with Lawrence A Cunningham)

DEBT IS THE WORST POVERTY

LEVERAGE AND EXCESS RISK

IN CONTEXT

FOCUS
Managing risk

KEY DATES
1970–2008 Banks in developed countries double the ratio of loans that they issue compared to the value of money they hold.

2002 The Global Executive Forum report on the collapse of the Enron corporation says that "the genius of Enron was infinite leverage."

2007–08 Increasing numbers of people access credit to finance mortgages, but later default on their loans. Global financial markets collapse.

2013 The UK government forces banks to publish their leverage ratios. Among the highest leveraged is Barclays, which has loans worth 35 times its (equity) capital base.

In 2012, US theoretical physicist Mark Buchanan wrote *Forecast*, a book detailing his investigations into the workings of the economy. In assessing the variables that affect economic growth and decline, he noted the importance that central banks (and governments) place on inflation, interest rates, exchange rates, and consumer confidence. He was puzzled by the absence of one variable that had proved a central factor in past extremes of boom and



Increasing leverage allows companies to...

...focus on **growth** and convert **short-term debt into long-term loans**...

...and pay **increased dividends** to shareholders.

However, it can leave businesses **vulnerable to cash-flow problems**.

Decreasing leverage allows companies to...

...focus on **increasing profit** through minimizing costs and **repay** long-term loans...

...and issue **more shares**.

However, the company may **fall behind rivals** who can boost growth through higher leverage.

See also: Who bears the risk? 138–45 ▪ Profit versus cash flow 152–53 ▪ Maximize return on equity 155 ▪ The private equity model 156–57

Borrowing on credit cards can lead to financial ruin. In 2007–08 many homeowners borrowed on credit to pay their mortgages, but had insufficient income to meet loan repayments.

bust—leverage. This is a measure of indebtedness, or the extent to which people or companies finance their future by borrowing money. Society and business had ignored the warning of UK historian Thomas Fuller: "debt is the worst poverty."

When high leverage is widespread in the economy—as occurs when lots of people borrow large amounts of money—the degree of debt can create a short-term boom. But this often comes at the cost of a subsequent bust.

Taking risks

The financial crisis of 2007–08 was largely caused by high leverage. Individuals borrowed large amounts on credit cards and took out 100 percent mortgages, both against inadequate levels of income. When the debts could not be met and house prices fell, huge numbers of people defaulted on their debts. The equally highly leveraged banks stumbled; their problems were made worse by the large-scale use of complex financial products (also based around leveraging), and the financial system crashed.

Leverage carries similar risks for businesses. During good times, when demand is rising and profit margins are high, borrowing capital to finance extra growth may seem an attractive means to boost profits. But leaders often ignore the increase in risk that accompanies an increase in borrowings. Paying back debt is not optional (unlike the payment of dividends, for example). Highly leveraged businesses can suddenly find that their high levels of debt are no longer serviced by sales. The borrowings that had driven profits can begin, instead, to drive the company into severe cash-flow problems.

Broadly speaking, it is wise to restrict borrowings to around 25 to 35 percent of the total long-term capital employed in the business. Any higher than 50 percent is regarded as carrying too high a risk level for a normal business. After all, while the directors need to aim for maximum profits, they are also responsible for the long-term health of the business, together with the welfare and security of staff, customers, and suppliers. ■

The leveraged buy-out

In a leveraged buy-out, a business is acquired by a company or group of individuals using a large amount of borrowed money, most often from bank loans or bonds (interest-bearing loans that are used to raise capital). Typically, the buy-out may be paid for with a ratio of around 90 percent debt to 10 percent equity, and the assets for the loans are those of the company being acquired. In other words, the theory is that the debt is later repaid by money raised from the acquired business. Leveraged buy-out investment companies are today known as private-equity companies.

In the 1980s, leveraged buy-outs became notorious, as some acquirers used a borrowing ratio level of 100 percent, and the interest levels on debt repayment were so large that cash flows crashed and companies went bankrupt. More recently, a $2.85 billion leveraged buy-out and subsequent restructure was used to rescue struggling US film-production giant Metro-Goldwyn-Mayer (MGM).

> When you combine ignorance and leverage, you get some pretty interesting results.
>
> **Warren Buffett**
>
> **US investor (1930–)**

CASH IS KING

PROFIT VERSUS CASH FLOW

IN CONTEXT

FOCUS
Financial management

KEY DATES
1957 John Meyer and Ed Kuh publish "The Investment Decision," the first study to look at cash flow and investment in businesses.

1987 The US Financial Accounting Standard Board (FASB) introduces a new requirement: companies must now complete an annual "statement of cash flows" in addition to a balance sheet, income statement, and retained earnings statement.

2013 The UK's Co-operative Bank abandons its plans to purchase 632 branches of Lloyds Bank, because it has insufficient cash to buy the business and run the branches.

For new businesses, fast-growing companies, and in times of recession, cash is king. In other words, profit takes a back seat, while cash flow becomes the critical factor. In accounting, profit is an abstract concept based on matching costs to the revenues generated within a period of trading. This sounds fine, but in practice it can lead to a huge cash shortfall. For example, if a construction business links its costs to the time when the finished houses are ready for purchase, it has ignored the huge cash outflows that are incurred during the building process, and might run out of cash before the houses are sold. When times are good, a



In times of **economic stability** companies focus on profit; **credit is cheap** and readily available.

Companies with weak cash flow operate by using **supplier credit** and **overdrafts**.

But in times of **recession**, relying on **credit is dangerous**.

Cash is king.

See also: How fast to grow 44–45 ▪ Investment and dividends 126–27 ▪ Making money from money 128–29 ▪ Leverage and excess risk 150–51 ▪ Maximize return on equity 155 ▪ Balancing long- versus short-termism 190–91

company may rely on dipping into an overdraft to make up for a cash shortfall. But when times are tough, a reliance on the bank may be too risky. A business needs to manage its finances well enough to avoid periods of negative cash flow.

A business receives a $24,000 order, and has to plough cash into making the goods. By week six, $20,000 has been spent by the company; the customer is invoiced, but is not required to pay until week 13. This means the company faces serious negative cash flow for 12 to 13 weeks.



How good companies fail

Cash is a constant pressure for every new business. Even if the company keeps to its start-up budget, it takes time for trading to reach a high enough level to generate positive cash flows. For example, a sports' equipment store may take three years to build up the regular clientele that will enable it to start making money. Until then, the business faces negative cash flow. So it is crucial for new businesses to prioritize cash flow from the beginning. This may mean leasing equipment, or buying it secondhand rather than new, and choosing suppliers that provide the same credit period as the store gives to its customers, even if these suppliers cost a little more. Cash-flow problems can also cause well-established companies to stumble and even collapse. In 1998, South Korea's Daewoo Group encountered growing problems because of "increasing difficulties in arranging working capital and investment funds." The group had been aggressively expanding, and admitted that its overall financial stability had been seriously undermined by a new reliance on borrowings, but insisted that it was a brief moment of crisis. Despite being one of the largest conglomerates in the world, the group collapsed the following year due to massive cash shortfalls. ■

Money scams

US investment advisor and financier Bernard Madoff was sentenced to 150 years in prison in 2009 following a money scam that is believed to have led to about $18 billion of losses to investors. Although hailed as a distinguished and expert financier, capable of generating very high returns for investors, Madoff was in fact responsible for running a "Ponzi scheme," in which cash from new investors is used to pay generous returns to earlier investors. The delight of these early customers led them to recommend the scheme, which then continued to pay earlier investors with the cash put into the company by subsequent investors.

This type of financial pyramid is able to stay afloat as long as sufficient numbers of new savers put cash into the scheme. If the flow of funds dries up, the scheme collapses. Madoff's scam collapsed due to a loss of investor confidence following the 2008 financial crisis.

Farmers buying livestock at market must—like many business owners—pay up front. Costs, such as feed and storage, will mount before they see a return on their investment.



ONLY WHEN THE TIDE GOES OUT DO YOU DISCOVER WHO'S BEEN SWIMMING NAKED

OFF-BALANCE-SHEET RISK

IN CONTEXT

FOCUS
Financial risk

KEY DATES

1992 Terry Smith publishes *Accounting for Growth*, an insider exposé of accounting practices in big businesses.

2001 The spectacular collapse of Enron shows that practices such as off-balance-sheet accounting are not just obscure talking points.

2010 Lehman Brothers bank is revealed to have used "Repo 105" and "Repo 108" repurchase transactions to temporarily remove some loans and investments from its balance sheet for 7 to 10 days, creating a misleading picture of its activities and value.

2011 UK care provider Southern Cross collapses due to off-balance-sheet debts to the value of $8 (£5) billion.

The balance sheet is a snapshot of a company's assets and liabilities and should show any financial risks that a company is facing. Yet in reality, not all of the company's liabilities appear there. This means that when calculating the debts of a business, it may not be possible to account for everything. This was the case when Enron failed in 2001, and it was also true for the Western retailers and banks that struggled from 2007–08.

Operating off balance sheet was at the heart of the 2011 scandal at Japanese camera company Olympus. To hide poor management decisions, such as overpaying in takeover bids, the board set up unconsolidated subsidiaries to hold the transactions that were causing losses. As unconsolidated losses, the figures did not have to appear in the its annual accounts. Analysts and auditors should have spotted that something was wrong when profits appeared "healthy" while cash was draining out of the business. But nothing was spotted until new CEO Michael Woodford blew the whistle.

Enron used off- balance-sheet accounting to hide overvalued assets in subsidiary businesses. Its financial records continued to look perfect even as it spiraled toward bankruptcy.

Off-balance-sheet finance has been increasingly used by governments in recent decades. In China, the National Audit Office has warned that local government may have as much as three times its official debt of $600 billion in off-balance-sheet unofficial debt. This will add greatly to future interest charges—and may carry significant risk if China experiences a credit crunch similar to that in the US and Europe from 2007–08 onwards. ■

See also: Play by the rules 120–23 ▪ Accountability and governance 130–31 ▪ Who bears the risk? 138–45 ▪ Leverage and excess risk 150–51

RETURN ON EQUITY IS A FINANCIAL GOAL THAT CAN BECOME AN OWN GOAL

MAXIMIZE RETURN ON EQUITY

IN CONTEXT

FOCUS
Business goals and risks

KEY DATES
1978 Legendary investor Warren Buffett claims that ROE is not likely to stray from a level of 12 percent for very long.

1995: *The Warren Buffett Way* by Robert Hagstrom introduces the public to Buffett's approach to investment, including the importance he places on ROE.

1997 The US's S&P (Standard and Poor) index of industrial companies reveals an average ROE of 22 percent.

2012 Among international clothing retailers, ROE varies from 40 percent at Gap and 39 percent at H&M, to -139 percent at American Apparel. Based on its ROE alone, American Apparel should no longer exist in its current form.

Many stockmarket analysts regard "return on equity" (ROE) as a vital measure of business success. ROE measures profit as a percentage of the shareholder's equity on the balance sheet. This "equity" is comprised of share capital (capital raised from selling shares) and reserves (the company's accumulated, retained profit).

ROE is affected by trading conditions. Still recovering from a tsunami and floods, Toyota achieved an ROE of 3.9 percent in 2012. Rival General Motors (GM), unaffected by the natural disasters, managed 16.7 percent. Based on its ROE, GM appeared to be four to five times better at generating profit from shareholders' investment.

A misleading measure

As an indicator of investment potential, ROE can be problematic. The percentage outcome is a function of two things: how high the profit is, and how low the shareholders' equity is. Toyota and GM both made a similar pretax profit in 2012, but the amount of shareholders' equity in the two companies creates a misleading picture. Toyota has a huge balance sheet with high shareholder equity, bolstered by decades of high profits. GM's bankruptcy in 2009 had wiped out its reserves, leaving it with a small equity base. GM's high ROE was largely due to its collapse and US government bailout.

In the 2000s, many banks cut their balance sheets through "share buybacks." Cash was used to buy shares back from shareholders, reducing the equity at the bottom of the formula. This increased the ROE, but led to a risky capital structure. By maximizing ROE, the banks left too little cash to deal with the 2007–08 financial crash. ■

ROE is calculated by dividing profit by average shareholder equity. The higher the figure, the more efficient the company is at generating shareholder returns.

$$\textbf{ROE (\%)} = \frac{\textbf{Profit}}{\textbf{Average shareholder equity}} \times 100$$

See also: Investment and dividends 126–27 ▪ Accountability and governance 130–31 ▪ Who bears the risk? 138–45 ▪ Ignoring the herd 146–49

AS THE ROLE OF PRIVATE EQUITY HAS GROWN, SO HAVE THE RISKS IT POSES

THE PRIVATE EQUITY MODEL

IN CONTEXT

FOCUS
Profit and risk

KEY DATES
1959 Fairchild Semiconductors, the first venture-capital-funded start-up, is created.

1978 US investment group KKR pays $380 million to take manufacturer Houdaille Industries Inc. private; this is probably the first private-equity transaction.

1988 KKR buys conglomorate RJR Nabisco for $25 billion in the biggest private-equity purchase the world has yet seen.

2006–07 A peak year for private equity—in the US alone, private equity companies buy 654 companies for a total of around $375 billion.

At first, private equity came only from **large investors** wanting long-term gains.

↓

But in the 1980s, smaller investors used **leveraging and debt** to buy companies.

↓

This type of private equity requires high **short-term profit** (to service debts).

↓

Long-term opportunities are likely to be overlooked in favor of short-term profit.

↓

As the role of private equity has grown, so have the risks it poses.

Some economists believe that "private equity" is misnamed, since it is a model based on debt, not equity (the value of assets owned outright by an individual or company). Private equity involves "leveraging" a balance sheet by loading debt onto the business. This is similar to the controversial practice of "leveraged buy-outs" (LBO), in which a company is acquired using a high percentage of borrowed funds, loading it with a high level of debt.

Such levels of debt pose inherent risk, as US politician Jack Reed highlighted. Pressure on managers increases—good profits are necessary in order to minimize interest charges on the company's debt. The theory is that this forces managers to perform better, but critics claim that a company run on the private-equity model is likely to maximize short-term profit at the cost of long-term business growth.

Less pressure, more focus

To its supporters, the main strength of the private-equity model is in what it removes. First, it removes the regular profit pressure from shareholders that is faced by bosses of a publicly traded company. For

See also: Beating the odds at start-up 20–21 ▪ Who bears the risk? 138–45 ▪ Leverage and excess risk 150–51 ▪ Balancing long- versus short-termism 190–91

example, in 2012, the US department-store chain JC Penney was given a facelift and a new, more upmarket strategy. A sharp downturn in sales forced a quick rethink, including firing the recently hired CEO. Short-term underperformance is unacceptable to a public company, and can even attract the attention of private-equity investors seeking new acquisitions.

The second strength of the private-equity model is said to be the focus it provides. The boards of publicly traded companies often direct a diverse range of businesses. For example, in 2012, the Sumitomo Corporation of Japan sold a 50 percent stake in its Jupiter Shopping Channel subsidiary to US private-equity group Bain Capital. This effectively separated Jupiter from Sumitomo, ensuring that the Jupiter directors could focus on just one area of business. This enabled them to play a more hands-on role in decisions and strategy. In the long term, there are two critical questions about private equity: does it produce a better profit performance? And is it better for the long-term success of the business, taking into account innovation, staff commitment, and customer satisfaction?

In 2013, a combined study by three UK universities found that a company's performance falls after being subject to a private-equity buyout, based on profits and employment levels. The research showed that four years after a private-equity purchase, revenue per employee rose from $190,000 to $252,000, while in a control group it increased from $190,000 to $295,000. However, other studies have suggested the opposite—that private equity boosts profits—so the research is inconclusive.

It might seem that when "private equity" is used as a term to describe debt-fueled growth, years of success can be followed by spectacular losses. However, the majority of companies making private-equity purchases are institutional investors, who want to invest large sums of money over long periods. ■

Jupiter Shopping Channel is Japan's most popular television shopping company. Now 50 percent privately owned, it benefits from an increased focus on call-center efficiency.

Alec Gores

Perhaps the richest private-equity businessman in the world, Alec Gores's personal fortune was estimated at $1.9 billion in 2013. Gores was born in Israel in 1953 to a Greek father and Lebanese mother. He emigrated to the US in 1968, where he attended high school in Michigan.

After earning a degree in computer studies from Western Michigan University, he founded a computer retail business (Executive Business Systems) selling computers from his basement in 1978. Within seven years, he employed more than 200 people. Gores sold the company for $2 million at the age of 33 and used the capital to start the Gores Group in 1987.

The Gores Group private-equity fund specialized in acquiring and operating undervalued and under-performing noncore businesses from major corporations, and turning them into profitable concerns. These included loss-making divisions from large companies, including Mattel and Hewlett-Packard. Since its founding, the company has acquired more than 80 businesses.

ASSIGN COSTS ACCORDING TO THE RESOURCES CONSUMED

ACTIVITY-BASED COSTING

IN CONTEXT

FOCUS
Costs and efficiency

KEY DATES
1911 F. W. Taylor—one of the first management "gurus"—writes *The Principles of Scientific Management*. In it, he suggests methods for creating an accurate costing model.

1971 US professor George Staubus writes *Activity Costing and Input-Output Accounting*. His book encourages interest in activity-based costing among US manufacturers.

1987 US business experts Robert Kaplan and Robin Cooper define activity-based costing in their book, *Accounting and Management*.

Cost accounting seeks to determine a company's costs of production by measuring direct costs (such as raw materials) and adding an estimate of overhead or fixed costs (such as utilities). According to Professor David Myddelton of Cranfield School of Management in the UK, the inherent inaccuracy of this method often means that companies know far less than they

Activity-based accounting calculates the **actual overhead cost** of products and services.

↓

These are exact, so the company is able to calculate **accurate unit costs**.

↓

This accuracy allows the company to make **good decisions** about how best to use resources.

↓

Assign costs according to the resources consumed.

See also: Play by the rules 120–23 ▪ Profit versus cash flow 152–53 ▪ Good and bad strategy 184–85 ▪ The value chain 216–17 ▪ Product portfolio 250–55 ▪ Benefitting from "big data" 316–17

should about their costs. They may be relatively clear about direct costs, but vague about the overhead costs that should be attributed to specific products. The commercial consequence of this is that a business may allocate marketing spending to a product that is not very profitable. In the long run, a business that makes wrong decisions like this will struggle to keep up with its rivals.

Activity-based accounting

Ideally, an accounting system measures every aspect of every transaction and decision related to a particular product or service. The most effective way of achieving this is through activity-based costing. Whereas traditional accounting systems estimate the overheads (perhaps by assuming that every unit produced at a factory should have the same share of the total overhead bill), activity-based costing is much more precise: it breaks down the overhead costs to find out which activities create which costs. This allows the company to realize that the cost of making a chocolate product, for example, is not "about 65 cents," but exactly "59 cents."

This level of accuracy tends to be especially important when considering nonstandard products, such as the completion of a special order of merchandise for the Brazil Olympics in 2016. Activity-based costing might show that the costs associated with this special order are higher than they would be for standard products. This would help the business to set the right prices for the Olympic items.

To perform effective activity-based costing, a company needs to: first, identify all the direct and indirect activities and resources; second, determine the costs per indirect activity; and third, identify the "cost drivers" for each activity. A cost driver is a factor that influences or creates costs. For example, a bank teller has many activities—when measuring the cost driver of an activity such as handling incoming checks, the bank should figure out how long the teller spends on this task alone. From these three calculations, a company can calculate the total direct and indirect costs for a product or service. By dividing these costs by the quantity produced, an accurate unit cost can be obtained. The company can then establish reliable break-even points, identify the products with the profit margins that make them worth backing (with advertising support, perhaps), and allow clear comparisons for making sound investment decisions. ■

> “Keeping of costs with a reasonable degree of accuracy can be made a matter of very great profit to the company.”
>
> **F. W. Taylor**

Frederick Winslow Taylor

Born in 1856 in Philadelphia, PA, F. W. Taylor trained as a mechanical engineer. He later became famous for his study of "Scientific Management," which was based on the idea that effective management is a science with clearly defined laws. Taylor was also known as the "father" of cost accounting.

In the late 19th century, he established new accounting systems involving the "monthly determination of unit costs." He highlighted the value of cost data as information that managers could use to set prices and decide what to produce. His belief was that if accounting information is to be valuable, it must be useful, timely, and formed into comparable statements, so that progress (or decline) can be identified quickly. F. W. Taylor died of pneumonia in 1915 at 59.

Key works

1911 *The Principles of Scientific Management*
1919 *Two Papers on Scientific Management: A Piece-rate System and Notes on Belting*

WORKIN A VISION

STRATEGY AND OPERATIONS

G WITH

In Lewis Carroll's *Alice in Wonderland* the Cheshire cat tells Alice that if you don't know where you are going, "it doesn't matter which way you go." This is a trap that businesses must avoid—the starting point for any new venture is having a goal and there must be a clear strategy as to how to get there. It is also essential to have a vision of what success will be like once that goal has been reached. This vision must be shared and understood by everyone so that the company has a common objective.

Following a vision

Making decisions about a good business strategy starts with critical analysis, such as SWOT analysis, but it should also involve identifying which actions not to take. Strategy is also vital for companies who want to lead the market—most do so by offering a product or service that is either the cheapest or the best. There are numerous business models and theories that can be followed to devise a successful strategy. Leading US strategist Michael Porter, for example, has provided organizations with ideas to help them analyze their market, understand the competitive forces at play, and position themselves for competitive advantage.

> Determine that the thing can and shall be done, and then we shall find the way.
>
> **Abraham Lincoln**
>
> **US former president** (1809–65)

Once the board of a company has agreed a strategic direction, it must be prepared to change course if the need arises—but always keeping the original vision in mind. In addition, business leaders should be on continual alert for changes in the external environment. Avoiding complacency is crucial, since the pace of business and change is constantly increasing. Competition is fierce, and companies must innovate if they want to stay at the top and avoid being overtaken or becoming outdated. There are many examples of companies who failured to do this, such as Research in Motion (now known as BlackBerry Ltd), the Canadian technology company whose business suffered when sales of its BlackBerry smartphones fell sharply—bosses had failed to anticipate Apple's more advanced iPhone.

Keeping a balance

Companies should always balance long- and short-term objectives. The board must keep the long-term vision in sight, but in the short term they need to make decisions that allow them to create enough profit to stay in business—a precarious balancing act, particularly in an uncertain world. It is impossible to predict what the future will bring, so executives often use scenario planning by asking "what if?" questions. Assessing the likelihood of unwanted events does not remove uncertainty, but it does help to avoid complete surprises.

The trend of diversification into unrelated businesses has declined recently, and companies now focus on the core business. Management experts C. K. Prahalad and Gary Hamel argued that a company's ability to consolidate its strengths into core competencies can provide a competitive edge over rivals.

Flexibility

Globalization, technology, and a changing world order have made business far more complex.

Hierarchical structures tend to be inflexible, so the emphasis today is on nonhierarchical structures, empowering people, and teamwork. Flexible businesses ensure that everyone is involved and can adapt swiftly to change. Such organizations collaborate with external partners, rather than merely transact with them, thus encouraging shared learning. US scholar Peter Senge introduced the concept of the "Learning Organization," whereby a company facilitates the learning of its employees and is able to transform itself on a continual basis. Control by management is replaced by leadership and direction.

Organizations with a learning culture and a shared vision enable people with different functions to work together to develop ideas, make decisions, and create new products and services more quickly. Staff act as a group of entrepreneurs rather than as paid employees. Being able to learn from failure requires a culture in which people are not criticized for mistakes, since this impairs initiative and new ideas.

Companies have to learn not just to deal with chaos but to thrive. In the ever-changing environment of the 21st-century's digital economy, companies have to manage chaos and use it as an opportunity to grow and refresh the business.

Business today

Business may be complex in the modern world, but it has never been more interesting or exciting. Physical size no longer equates with success. The Internet changed everything—now small can be beautiful. Businesses that spring up offering customized products in niche markets are often able to compete effectively in the global economy. Some of today's most successful businesses started with just one person, often in a garage or at a kitchen table. The important thing is that companies should not only offer what people want, but also make it easy for consumers to reach them online.

> “You have to have vision. It's got to be a vision you articulate clearly and forcefully on every occasion. You can't blow an uncertain trumpet.”
>
> **Father Theodore Hesburgh**
>
> **US priest and scholar (1917–)**

In addition to this is the overall importance of ethics. "Profit at any cost" is no longer an acceptable maxim. There is growing regulation on financial reporting and on issues such as bribery. Today's consumers are increasingly demanding and discerning: they want to know how raw materials are sourced, how products are made, and how the company impacts the environment. Some companies have policies and procedures in place to help create an ethical culture. In this way, employees know what standards are expected. And yet there are still numerous cases of corporate tax avoidance, price-fixing through collusion, and excessive risk taking. These issues persist because individuals are often motivated by personal gain. High-profile cases include the 2008 collapse of the US financial-services organization Lehman Brothers early in the global economic crisis.

However, many of the examples in this chapter suggest that companies who hold a clear vision and do the right thing, in the right way, are most likely to succeed. ■



TURN EVERY DISASTER INTO AN OPPORTUNITY

LEARNING FROM FAILURE

IN CONTEXT

FOCUS
Management thinking

KEY DATES

c.560 BCE Chinese philosopher Lao Tzu says that failure is the foundation of success and the means by which it is achieved.

1960s Soichiro Honda, founder of the Honda Motor Company, says that "success can only be achieved through repeated failure and introspection."

1983 Apple Computer Inc. releases the Lisa computer. It is a commercial failure, but plays a vital role in the development of the Apple Mac.

1992 US management professor Sim Sitkin introduces the idea of "intelligent failure" in *Learning Through Failure: The Strategy of Small Losses*.



When a company performs an activity, it **gains experience**.

The experience gained provides **useful feedback**, whether the activity succeeded or not.

The company must analyze the feedback to find out what could be done **differently and better**.

The company implements these **better methods and approaches** in new projects.

Every disaster is an opportunity for learning.

There are many stories of success built on failure: the US inventor Thomas Edison failed to register patents for his ticker tape machine so felt compelled to continue inventing, eventually perfecting the incandescent light bulb. British inventor James Dyson produced more than 5,000 prototypes before he came up with a successful bagless vacuum cleaner. Success for entrepreneurs always involves trial and error, and resilience. US industrialist J. D. Rockefeller, the world's first dollar-billionaire, looked

See also: Managing risk 40–41 ▪ Luck (and how to get lucky) 42 ▪ Reinventing and adapting 52–57 ▪ Creativity and invention 72–73 ▪ Beware the yes-men 74–75 ▪ Thinking outside the box 88–89 ▪ The learning organization 202–07

to "turn every disaster into an opportunity." As the world turned to electric lighting from kerosene oil lamps, his business was threatened. However, he quickly saw the potential of Ford's automobile and realized that oil could just as easily be converted to gasoline as kerosene. His fortune rocketed.

Constant learning

Personal experience is recognized as the way individuals learn, and it is much the same for organizations; they gain knowledge and capability from corporate experience. The pace of change in the global market means that constant improvement has become the norm. The greatest challenge, however, is for companies to recognize failure and learn from it. In order to do this, an organization needs to build a culture in which people are not criticized or penalized for mistakes, but are actively encouraged to gain useful insights from them.

Some companies recognize that it is only through failure that success can be found, and build this principle into their culture. US corporation 3M, for example, allows technical staff to allocate 15 percent of their time to experimenting with ideas, understanding that there will be occasional winners (such as the Post-it Note) along with the repeated failures.

Recognizing error, cutting losses, spotting new opportunities, and changing course is a test of leadership and also sends out a positive message to those who work in the organization. It requires rational, unemotional thought that focuses on the costs and benefits of changing direction.

In the mid-1980s, the Coca-Cola Company decided to replace its original formula with a sweeter product: New Coke. In the US, this prompted consumer protests. The company learned that US consumers were protective of Coca-Cola and felt unhappy about any tampering with the recipe. The CEO quickly reintroduced the original formula as Coke Classic. By responding quickly, he grasped an opportunity for significant publicity; sales soared.

> “I have not failed.
> I've just found 10,000 ways
> that won't work.”
> **Thomas A. Edison**
> **US inventor (1847–1931)**

The world's third-largest retailer, Tesco, opened its Fresh & Easy stores in the US in 2007. After six years and $2.27 billion in costs, it admitted failure and pulled out. The stores were unsuccessful because Tesco misjudged the shopping habits of its target customers. Chairman Richard Broadbent said they had learned the value of remaining open-minded about projects. Flexibility, feedback, and fast response are key to finding a new path via failure. ▪

J. D. Rockefeller

John Davidson Rockefeller was born in 1839 in Richford, NY. At age 16, he took a job as an assistant bookkeeper with a commission-merchants business. Just four years later, he set up his own, similar company with a partner: it grossed $450,000 in the first year. He then opened his first oil refinery in 1863, founding Standard Oil.

Rockefeller's business interests made him the richest person in the world at the time, but his practices were unpopular. Realizing the value of effective distribution, he arranged an exclusive deal with the railroad company to transport his oil, putting all his competitors out of business. Standard Oil gained a monopoly position first in Cleveland and then in the US. In 1902 his monopoly in refining, transporting, and marketing oil made headline news and the company was broken up by the US Supreme Court in 1911.

Rockefeller then became the world's greatest philanthropist, giving away around $350 million, and setting up many charitable institutes. He died in 1937, at 97 years old.

IF I HAD ASKED PEOPLE WHAT THEY WANTED, THEY WOULD HAVE SAID FASTER HORSES

LEADING THE MARKET

IN CONTEXT

FOCUS
Market leaders

KEY DATES
1780s British inventor Richard Arkwright devises a complete mechanized system for the production of yarn on an industrialized scale.

1860s US general Nathan Bedford Forrest claims the key to military success is “to get there first with the most men.”

1989 Dutch businessman Arie de Geus suggests that a company’s only sustainable competitive advantage is its ability to learn faster than its competitors.

1994 Al Ries and Jack Trout publish *The 22 Immutable Laws of Marketing*, in which they outline the advantages of being first to market.

Business logic often dictates: hold back; let someone else go first, incur the costs, and make mistakes. But there are many examples of significant advantages for companies first off the mark.

A company that leads the way into a new market gains a competitive advantage, which might enable it to dominate over the long term. Richard Arkwright, the inventor of the modern factory system, is an example. He devised the first complete mechanized system for the spinning of cotton yarn in the 18th century in Britain. His patents were overturned just five years after they were filed, but his head start ensured that he

See also: Stand out in the market 28–31 ▪ Gaining an edge 32–39 ▪ Balancing long- versus short-termism 190–91 ▪ The value chain 216–17



Consumers do not innovate—they are **happy with a better version** of an existing product.

When a company introduces a **totally new concept**, it creates a new market and is "first" in consumers' minds.

The company gains the **competitive advantage** of being first to market.

Even if competition arrives, consumers **continue to associate** the first company with the concept.

A company that leads the way can **dominate the market**.

continued to dominate the market. The knowledge he had gained enabled him to improve his water-powered spinning frame.

Moving ahead

Henry Ford did not invent the automobile, but he did develop the first affordable car for middle-class Americans at the beginning of the 20th century. Most people had never aspired to owning a car because they were seen as a luxury item for the wealthy, and, as Ford said at the time, most people would have been happier with "a faster horse."

Ford, like Arkwright, succeeded because of a technical edge. His idea was that of mass production, using a moving assembly line to reduce production costs. By 1918, Ford Motor Company was the clear leader in the US automobile market —the Model T made up half of all cars in the US. Ford continued to lead the market until the mid-1930s.

Moving ahead of others in a market involves risk. By taking the initiative—with an innovative product, new technology, lower prices, better distribution, promotional offers, or forceful advertising campaigns—a company creates an opportunity to seize the leadership position. Organizations may seek such an advantage because their strategy and approach is always to lead into »



Henry Ford

Henry Ford was born in Michigan, US, in 1863. He was always fascinated by machines, and as a child built rudimentary steam engines. He left school at 15 to work on his father's farm, but in 1879 he moved to Detroit to work as an apprentice at the Michigan Car Company, which made railroad cars. He moved home for a while, and did several engineering jobs, before returning to Detroit to work as an engineer for the Edison Illuminating Company.

At the same time, Ford began to make a gasoline-driven car, Thin Lizzie, in his garden shed. He persuaded a group of businessmen to back him, but a lack of experience led to business failure—twice. His third business—the Ford Motor Company—was formed in 1903. Its first car, the Model A, was followed by several other models until the company struck gold with the Model T: "a motorcar for the multitude." By 1925 Ford was producing 10,000 cars every 24 hours, producing 60 percent of the US's total output of cars. His last great innovation—at the age of 69—was the V8 engine. He died in 1947.

Yarn spinning was the first activity to become entirely mechanized. The British government restricted export of this technology, maintaining its first-mover advantage for as long as possible.

a new market, such as Gillette, the men's grooming business, with its long-held policy to be the "first to get it right." Some companies choose not to do this; Samsung, for example, aims to be a fast follower, having learned from competitors.

First-mover advantage

Being first to market gives a company "first-mover advantage," which can be long-lasting or short-lived. Long-term advantage brings durable benefits, either by creating an entirely new market, or by improving a company's market share over a long period. Companies that succeed in building long-term advantage often dominate their product categories for many years. Hoover and Post-it Notes, for example, were so successful in their market sectors that their brand names have become generic terms.

Short-term advantage typically occurs because it is based on new technology. Today, innovation is exceptionally fast in many sectors, with increasingly shorter gaps between new introductions and superior products. Sony is one example of a technology company that led the market for around 20 years, until competition from new technology arrived.

Sony's corporate philosophy is built on "doing things that no one else is willing to do." The business was set up in the ruins of Tokyo after World War II, and the founder Ibuka Masaru was determined to develop leading-edge products and get them to market faster than the competition. This idea became a personal obsession for Ibuka and his successor, Morita Akio.

> It's not the consumers' job to know what they want.
>
> **Steve Jobs**
>
> **US former CEO of Apple** (1955–2011)

In 1979 Sony introduced the Sony Walkman, the first portable music-listening device. Just as Ford had changed the way people traveled, Sony changed music-listening habits—and lifestyles. Its launch coincided with the aerobics craze, and millions used the Walkman to add music to their exercise workouts. Between 1987 and 1997, the height of the Walkman's popularity, the number of people starting to walk as exercise increased by 30 percent, according to *Time* magazine. Sony sold 200 million of their portable cassette players, and by 1986 the word "Walkman" had entered the Oxford English Dictionary.

The Walkman evolved from cassette to CD technology, and consumers were happy with their portable music players until 2001, when Apple CEO Steve Jobs said: "The coolest thing about the iPod is that your whole music library fits in your pocket." So began a new industry, based on portable digital music, and dominated by market-leader Apple.

Being first is everything

Leading the way often depends on the product being embraced by "early adopters"—consumers who are willing to pay a price premium to be the first to own something. This happened with the launch of Apple's iPhone in the summer of 2007. Even though the price was reduced a few months after launch, those who had bought at the higher launch price did not resent it due to the cachet of being at the forefront of the latest trends and fashion.

As long as products remain the only one of their kind available, the company that is first to market has a monopoly position; this means it can set the price, establish loyalty, and build a reputation before competitors catch up. When competition does arrive, the first-mover still has the advantage, because it has established itself. This is generally the case even when subsequent products are better than the first.

It's all in the mind

Al Ries and Jack Trout, authors of *The 22 Immutable Laws of Marketing,* developed a theory of why the first company to market can continue to dominate. They proposed that the customer's perception of where a product or service sits in the market is of utmost importance, claiming that "it is better to be first than it is to be better." It is easier to get into the consumers' minds first than to dislodge a product or service from their minds and convince them that your company has a better product. Ries and Trout argued that most marketing stems from the assumption that companies are fighting a product battle rooted in reality. But consumers are not concerned with reality; they make purchases based on perception. "Being first in the mind is everything in marketing. Being first into the marketplace is important only to the extent that it allows you to get into the mind first," say Ries and Trout.

The car in front

Japanese car manufacturer Toyota tries to be first to market, and imparts this message in the minds of consumers with the slogan: "The car in front is a Toyota." Toyota was the first company to introduce a hybrid car—with an engine drawing power from both gas and electricity—to market. Its Prius went on sale in Japan in 1997. Several manufacturers were considering the concept of a hybrid car in the 1980s, but combining an internal combustion engine and an electric motor required significant investment. Despite this, Toyota knew that if they could lead the way, there would be a number of advantages for the company. First, Toyota would gain early-adopter consumers who were looking for an environmentally friendly driving option. Second, creating a hybrid car would increase access to new and existing markets, such as the US, where emissions legislation would favor a hybrid car. Third, it would enhance Toyota's image, because of its clear message of the company's commitment to environmental protection, while at the same time generating excitement about Toyota's new products and the company's innovative capabilities.

> The key to success for Sony, and to everything in business … is never to follow the others.
>
> **Ibuka Masaru**
>
> **Japanese co-founder of Sony (1908–99)**

The Prius went on sale worldwide in 2001, and more than ten years later Toyota continued to lead the hybrid market. The Prius was the top-selling car in California in 2012, giving Toyota a 21.1 percent market share, compared to closest rival Honda's 12.5 percent. Although other companies, such as Ford and Nissan, have now developed their own hybrid models, Toyota's first move into the market continues to yield benefits in an ever-growing market. ■

The Prius gas-electric hybrid has won a sizable share of the low-emissions market for Toyota. The company was willing to invest significant development funds in return for a market-leading position.

THE MAIN THING TO REMEMBER IS, THE MAIN THING IS THE MAIN THING

PROTECT THE CORE BUSINESS

IN CONTEXT

FOCUS
Business strategy

KEY DATES

1900s–1950s Growth of large, vertically integrated corporations that control and own their assets, requiring complex and multilayered management structures.

1950s–1990s Organizations begin to expand by acquiring unrelated businesses.

1990 Business experts C. K. Prahalad and Gary Hamel introduce the idea of "core competencies" in their *Harvard Business Review* article "The Core Competence of the Corporation".

1995 US companies start to outsource functions to companies "offshore," such as businesses located in India.

2000s Companies begin to sell off unrelated businesses to refocus on their core.



Businesses are usually **very good at one thing**, such as making computer chips.

This skill gives the company a **competitive advantage**.

If the company **diversifies** into noncore businesses or **outsources** some functions to unreliable third parties...

...the core business may **begin to fail**.

The main thing to remember is, the main thing is the main thing.

The expression "Jack of all trades" refers to someone who can do many things, but is not particularly good at any one thing. Unless a company is able to maximize its competitive advantage over its competitors, the same can also be true in the world of business. Success usually relies on using that advantage rather than branching out with something new. The core business is the "main thing" at the heart of a company's operation, and organizations must remember that "the main thing is the main thing," according to Brigadier General Gary Huffman of the US Army. When a company

See also: Study the competition 24–27 ▪ Stand out in the market 28–31 ▪ Gaining an edge 32–39 ▪ Porter's generic strategies 178–83 ▪ Why takeovers disappoint 186–87 ▪ The MABA matrix 192–93

is struggling to win sales for its core product, it may be tempting to consider diversifying, but this often ends up being a distraction.

During the second half of the 20th century, there was a trend for companies to acquire unrelated businesses. Gillette, a leader in razors, bought PaperMate pens; Dalgety, which made Homepride Flour, acquired a pig-breeding company; and Cadbury, best known for candy, took control of Schweppes beverage business. The trend began to turn in 2003, when McDonald's began to sell off diverse restaurant chains it had acquired, including a pizza brand purchased during the 1990s. This was because it wanted to focus on its core business: McDonald's. Other companies soon began to divest unrelated businesses to protect the core.

Understanding the core

The theory behind selling secondary interests is that the business should focus its energy and resources on what it is good at. This idea was taken further during the 1990s, when some companies decided to "outsource"—contracting a business activity to an outside company—peripheral activities that they had previously performed internally. The trend of outsourcing gathered momentum as companies realized they could cut their business back to the core and achieve leaner, more efficient, cost-effective operations.

For example, a company that manufactures refrigerators may decide that its core business is simply the design, manufacture, and marketing of those refrigerators. It might outsource delivery (which it sees as not adding value), and its information technology (IT) needs (which it views as a specialized function). In the short term, handing over these activities to a third party would seem to make sense. But in the long term, it could be a mistake. Delivery might be an important part of customers' perceptions of the product, and the business could suffer if the outsourced delivery company is unreliable. Similarly, IT is increasingly integral to the success of a business, both for internal functions and customer interaction. Outsourcing is useful for lesser functions, but only as long as it works well—if it fails, it can adversely affect the core business.

Whenever companies outsource or acquire a separate business to take over a peripheral function, it is vital that management take steps to protect the "main thing." Any secondary units or third parties must be fully aligned with the vision and values of the organization. ■

McDonald's acquired several food chains, such as Donatos Pizzeria, during the 1990s in an attempt to enter new market sectors. In 2003, it sold them to refocus on its core business—burgers.

> If you cannot be the best in the world at your core business, then your core business absolutely cannot form the basis of a great company.
> **Jim Collins**
> **US business expert (1958–)**

Core competencies

An organization has a particular set of diverse production skills and individual technologies. These are its core competencies, according to business experts C. K. Prahalad and Gary Hamel. Unlike physical assets, which inevitably deteriorate over time, competencies become enhanced, because they are applied and shared. They are strengthened by involvement, communication, and a shared commitment to working across an organization's boundaries. Prahalad and Hamel describe the corporation as a tree. Its roots are its unique competencies, and from these roots grow the organization's core products, which in turn nourish separate business units. From these business units come the end products. The idea of core competencies can be used to identify those things within an organization that are not "at the core," which might be a distraction, consuming a company's valuable resources.

YOU DON’T NEED A HUGE COMPANY JUST A COMPUTER AND A PART-TIME PERSON

SMALL IS BEAUTIFUL

IN CONTEXT

FOCUS
Internet business

KEY DATES
1974 US computer scientists Vent Cerf and Bob Kahn design the first Transmission Control Program, enabling computers to talk to each other.

1977 The first electronic mail ("email") is sent, via the US Department of Defense's ARPANET.

1991 The World Wide Web (WWW), the first widely accessible system to share data files via the Internet, is released by Tim Berners-Lee.

1993 Netscape launches Mosaic, the first commercial Internet browser.

2013 More than two million third-party sellers use Amazon to reach their customers.

When British computer scientist Tim Berners-Lee harnessed the Internet to develop the World Wide Web, he was simply creating a way of sharing information. It was not viewed as a money-making exercise. However, the Internet's disruptive power soon became clear: it would change business and our way of life, enabling commerce to be conducted by a profusion of individuals and organizations.

Early search engines were invented as an increasing amount of information became available on the web. Larry Page and Sergey Brin, two US computer science students, designed a search engine that could quickly search all the available documents and generate highly relevant results. In September 1998 they set up a work space in a friend's garage and opened a bank account in the name of Google Inc. The soon-to-be giant company began, as Page said, with no more than "a computer and a part-time person."

Within a year Google had 40 employees, and in June 2000 announced its first billion-URL index, making it officially the world's largest search engine. By 2013, Google employed 30,000 people worldwide, of whom around 53 percent worked in research and development, which may explain the company's phenomenal growth.

Doing business on the web

As two-way communication over the Internet became a reality during the 1990s, organizations began to see the potential offered by the new e-commerce platform. The first books were sold online in 1992, and in 1994 Pizza Hut in Santa Cruz, California enabled people to order a pizza delivery via the Internet.

The idea of online selling took off in 1995 when Jeff Bezos dispatched the first book sold by Amazon.com, then located in his Seattle garage. Around the same time, software programmer Pierre Omidyar was starting a simple website called AuctionWeb from his San Jose living room. The first product he posted for sale was a broken laser pointer. It sold for $14.83. Omidyar recognized the Internet's power to reach individual customers, anywhere in the world, when he checked whether the buyer

Larry Page

Born in 1973 in Michigan, Lawrence (Larry) Page was exposed to computer technology at an early age; his father was a pioneer in computer science and his mother taught computer programming. Page studied engineering at the University of Michigan and then completed a Masters in computer engineering at Stanford University.

On his first visit to the campus, Page was shown around by fellow postgraduate student Sergey Brin, who would later be the co-founder of Google. During a research project in 1997, Page and Brin created a search engine called BackRub, which operated on Stanford servers until it outgrew their capacity. The pair worked together on a bigger and better version, which they named Google after the mathematical term "Googol"—the number 1 followed by 100 zeros. Page and Brin were jointly awarded the Marconi Prize in 2004, and Page was elected to the US National Academy of Engineering in 2004. Today Google is the world's most popular search engine, handling more than 5 billion search queries every day.

See also: Beating the odds at start-up 20–21 ▪ How fast to grow 44–45 ▪ The weightless start-up 62–63 ▪ Creativity and invention 72–73 ▪ The long tail 212–13 ▪ M-commerce 276–77 ▪ Feedback and innovation 312–13



A seller in Japan can source and sell a blue, customized widget.

A buyer in India wants to buy a green, customized widget.

The **Internet connects** buyers and sellers, and manufacturers and suppliers; it acts as a global marketplace.

You don't need a huge company, just a computer and a part-time person.

A seller in Poland can source and sell a green, customized widget.

A buyer in France wants to buy a blue, customized widget.

understood that the pointer was broken. The buyer assured him that he was a collector of broken laser pointers. One year later, with two full-time employees, the soon-to-be-renamed eBay sold goods to the value of $7.2 million. By acting as an auction service, eBay sees itself as in the business of linking users, not selling them things.

> A business succeeds not because it is long established or because it is big, but because there are men and women in it who live it, sleep it, dream it.
>
> **J. W. Marriott**
>
> **US businessman (1932–)**

Starting small

Both eBay and Amazon started small, and their platforms have empowered countless other small businesses around the world. Their pioneering use of the Internet changed the way that businesses and consumers interact, putting buyers and sellers in touch with one another in a way that had not been possible before. Amazon and eBay demonstrate the power of the idea that "small is beautiful." Anyone can sell products from their platforms, from individuals selling unique items to "power sellers" who set up virtual stores, either within the platform or linked to it. In the online marketplace the same opportunities exist for every business, whether large or small.

Before the existence of the Internet, if someone wanted to sell their products, a physical presence was necessary: a store, market stall, or going door-to-door. Generally, the bigger the presence, the more successful the business. Success »

In the pre-Internet age, vast numbers of people were often necessary for administration. The combined power of computing and the Internet changed organizational structures forever.

In the digital, networked economy, people can work anywhere, at any time. This shift in working habits is changing the face of business environments and staff distribution.

in retail, for example, traditionally relied on a prominent store on a town's main street, where the retailer could attract the largest number of customers through the door. Companies often depended on a large sales force, who visited customers to build relationships. Businesses held significant amounts of stock in warehouses, and had a large office staff to take phone calls and handle paperwork. That has all changed.

Consumers can now find retailers large or small via the Internet from a laptop, smartphone, or tablet. The physical scale of a business no longer correlates with success. Many businesses no longer need large offices. Paperwork has diminished, while online communication—email, instant messaging, and social media —allows sole-traders and employed people alike to work remotely, from home, anywhere in the world.

Large companies used to be more competitive than small companies because they had better economies of scale (the cost advantages that enterprises obtain due to size). When computers were first developed, this continued to be true, because large, costly servers were required for file storage. Today, however, the Internet is free and technology prices are relatively inexpensive. Cloud computing—whereby organizations share virtual infrastructure, software, and storage —has enabled small businesses to have access to the power of integrated networks and computing at a very low cost, and with no use of physical space.

Just as scale is no barrier to success, neither is geography. A small business can now reach customers all over the world just as effectively as a large one. It is possible to live on one side of the globe and sell items from an entirely different continent. The introduction of PayPal in 2000 allowed simple payment and money transfers in a wide range of currencies via the Internet, furthering opportunities for small companies to operate as global e-commerce businesses.

Competing with giants

With an increasing choice of goods and services available online for consumers, small businesses must offer something more than the giants in order to compete. Price is critical because consumers can easily compare prices online. But it is not the only factor that affects an online purchase; cost and speed of delivery are critical too. Free shipping and free returns are attractive incentives to purchase. Time of delivery is also important: retailers who can offer one-hour time slots and deliver beyond the traditional working day gain a competitive edge. Customer service is more important than ever.

Feedback is king

Whatever the goods being sold, they must be of the quality stated, because feedback on the Internet can have a powerful effect on the market. For hotels and restaurants, feedback and ratings by customers are now the norm, and many consumers base their purchasing decisions on other people's comments. A well-run, small, family-owned hotel, which focuses on excellent service and delighting its guests, can build a reputation as the number one place to stay in a particular town—ahead of a big chain hotel—because of review websites such as Trip Advisor.

> “The Internet is really about highly specialized information, highly specialized targeting.”
>
> **Eric Schmidt**
> **US former CEO of Google**
> **(1955–)**

> The Web does not just connect machines, it connects people.
>
> **Sir Tim Berners-Lee**
>
> **UK inventor of the World Wide Web (1955–)**

Organizations recognize the power of feedback and often encourage customers to post comments online. Fashion retailers, furniture manufacturers, and retail stores—even dental and medical practices—invite customers to comment on and share their experiences. Small companies benefit from this trend, since their personal service is more likely to generate positive reviews.



Small businesses can receive market information just as quickly as large companies thanks to the Internet, but due to their size are often better placed to respond quickly and adapt to changes in demand, supply niche products, and deliver a more personalized approach.

A more personal service

The Internet has removed the “middle man” from many areas of business. The travel industry is one example, since travelers can now book direct with airlines. Another example is the book industry, where authors can self-publish via the Internet, taking their fiction straight to readers without the need for literary agents or big publishing houses. The runaway success *Fifty Shades of Grey* by E.L. James began life as a free ebook on the Internet.

Previously, mass production and limited space in brick-and-mortar stores dictated the range of goods a business could stock. Now, small businesses selling niche products or services can thrive because the Internet connects them to consumers looking for exactly these offerings. People wanting to buy a spare part for an old car, or a rare edition of a book, can search and buy from anywhere in the world.

Small companies can also thrive through customization. Digital methods of production and online retailing enable narrowly targeted goods and services to be profitable. Customized production of a single item is possible—from personalized books, mugs, and clothing to customized cars, furniture, and even houses, which can be designed and tailored online.

Customers can get exactly the item they want, delivered at the right time and at a price they are willing to pay. Websites offering personalized printed items are small businesses with software that allows consumers to approve the final design and send it straight to print, so employees are only needed for packing and shipping.

Although small businesses can thrive on the Internet through their own websites, many now use portal websites as a “store window” to reach a wider audience. The British company Not on the High Street is one such portal. Started by two working mothers as a marketplace for personalized creative items, it launched in 2006 with 100 small businesses (many of them women working at home). In 2013, the business had grown to include 1,600 partners and had a turnover of more than $23 million.

Not on the High Street is successful because it combines the idea of personalized products with an awareness of the producer, giving buyers the chance to select a local maker. Although it promotes global trade, the Internet can enable a very personal form of communication between buyer and seller, regardless of size or scale. ■

DON'T GET CAUGHT IN THE MIDDLE

PORTER'S GENERIC STRATEGIES

IN CONTEXT

FOCUS
Business strategy

KEY DATES
1776 UK economist Adam Smith introduces the concept of comparative advantage, where one party has the ability to produce a particular good or service at a lower marginal cost than another.

1960 US economist Theodore Levitt says that rather than finding a customer for their existing product, businesses should find out what customers want, and produce it for them.

1985 Michael Porter publishes *Competitive Advantage*.

2005 Professors W. Chan Kim and Renée Mauborgne recommend a "blue ocean" strategy for generating growth and profits, in which new demand is created in an uncontested market space.


Companies need to find a **competitive advantage**.
They can do this by offering customers...
...the **cheapest product or service on the market**. This is the strategy of cost leadership.
...a product or service that is **outstandingly good in some way**. This is the strategy of differentiation.
Be the cheapest or the best; don't get caught in the middle.

Consumers have choice. And different consumers will choose differently—some like to pay the most for the luxurious option, while others will always opt for the cheapest. Companies recognize this and pitch their business at a particular group of consumers. This is because it is never wise for a company to be caught between groups of customers.

Harvard Business School professor Michael Porter proposed "generic strategies" for gaining competitive advantage, explaining his idea in *Competitive Advantage: Creating and Sustaining Superior Performance* (1985). Porter used a four-celled matrix to represent the four different generic strategies in his theory.

Companies generally choose between two generic strategies: either "cost leadership," where they aim to be the cheapest in the market; or "differentiation," where they create unique products or services. However, there is another element that can be added to these two generic strategies: a company might choose to pursue a "focus strategy," offering a specialized service in a niche market. This position can be applied to both of the initial generic strategies, resulting in a cost-focus strategy (where the company aims to be cheapest within a niche market) or a differentiation-focus strategy (where the company offers unique products or services within a niche market).

Cost-leadership strategy

Companies pursuing a cost-leadership strategy have two options. They can choose to sell products at average industry prices

See also: Gaining an edge 32–39 ▪ Leading the market 166–69 ▪ Good and bad strategy 184–85 ▪ The MABA matrix 192–93 ▪ Porter's five forces 212–15 ▪ The value chain 216–17

> Once stuck in the middle, it usually takes time and sustained effort to extricate the company from this unenviable position.
> **Michael Porter**

to earn a greater margin than competitors; or sell at below industry prices to gain more market share. Some supermarkets, such as German retailer Aldi and UK company Tesco, take the low-price approach to cost leadership. They achieve this by purchasing large volumes from close-relationship suppliers, and offer the customer "deep discounts." Their slogans— Tesco's "Every little helps" and Aldi's "Like brands, only cheaper"—convey their drive to pass savings on to the consumer.

Porter suggests that to pursue a cost-leadership strategy, a company has to be the leader in terms of cost in their industry or market, rather than be among a group of low-cost producers, because this makes them vulnerable. With fierce competition there is always the chance for other low-cost producers to reduce prices, and so take market share. Companies that choose cost leadership have to be confident that they can both achieve the number one position, and also maintain it. Several requirements must be met to achieve this, including: a low cost base (across labor, materials, and facilities); efficient technology; efficient purchasing; well-organized and cost-effective distribution; and access to capital for any required investment, to keep costs down.

These low-cost principles are not exclusive to any one company, however, and the risk is that they are easily replicated. Companies pursuing a cost-leadership strategy have to build in continuous improvement in all their processes to ensure the company can keep costs below those of other competitors.

Differentiation strategy

A company that pursues a differentiation strategy has to make markedly different products or services from competitors, so they have greater appeal to consumers. This strategy is more appropriate in markets where products are not price sensitive, and customers' needs are typically underserved. It also means being able to satisfy those needs in ways that are difficult to copy.

Bose Systems is a company that pursues a differentiation strategy. A privately owned US audio electronics company, it consistently reinvests profits to fund innovation. Customer-focused research has led to Bose's dominant position; their noise-canceling headphones and stylish speakers have become aspirational items.

The approach to differentiation will vary according to the products and services, and the nature of the particular industry, but typically involves additional features and functionality, enhanced durability, and better customer service. Companies that choose to pursue this strategy require certain fundamentals in place, including »

Bose Systems is an audio specialist that pursues a differentiation strategy. It distinguishes itself from competitors through research and development, which results in innovative technology.

good research and development, an innovative culture, and the ability to deliver consistently high-quality products or services. This needs to be supported by effective marketing, so that the differentiation is positioned and communicated to customers. Brand image is integral, and is often strengthened by the nature of the differentiation.

Focus strategy

Companies pursuing a focus strategy choose a particular niche market. They have to understand the dynamics of that market and the unique needs of customers within it, and then develop either low-cost or well-specified products or services. They also tend to serve their customers well, and so build strong brand loyalty. This makes their particular market segment less attractive to potential new entrants.

Ferrari is an example of a company in a niche market that has chosen to differentiate itself. The company targets the limited high-performance sports-car segment, and its cars are differentiated through high-spec design, high-performance, and the company's Grand Prix association.

Whichever focus a company chooses, it must do so on the basis that it can successfully compete on the strength of a particular ability or competence that will help it in its chosen market niche. If the company aims for cost leadership in a niche market, for example, it has to be based on distinctive relationships that have been developed with specialized suppliers. If the company goes for differentiation in a niche market, on the other hand, it has to be on the strength of a deep understanding of customer needs. However, a company that chooses to focus on a small market segment because it is too small to serve the larger market risks being sidelined by bigger companies with distinctive abilities, which enable them to better position their offerings.

Airline strategies

The airline industry illustrates Porter's idea. Consumers have a choice when they book an airline ticket. They can choose between a no-frills airline or a more expensive operator offering better service, quality, and comfort. There may also be a third option: a small airline that offers only a few routes. Airlines tend to focus on a particular group of travelers as an effective way of achieving competitive advantage in a crowded market, for example by offering discounted travel or a more luxurious traveling experience.

> “
>
> Every company competing in an industry has a competitive strategy, whether explicit or implicit.
>
> **Michael Porter**
>
> ”

Low-cost, Ireland-based airline Ryanair has championed the idea of cost leadership, and describes itself as “Europe's only ultralow cost carrier.” The notion of a low-cost airline was pioneered by Texas-based Southwest Airlines, and Ryanair followed with similar principles: use a single plane type to keep costs down, constantly review overheads, turn aircraft around as quickly as possible, and do not offer a loyalty plan.

Ryanair bought 100 Boeing 737-800 passenger jets at a significant discount in 2002. Starting with newer, more fuel-efficient planes than many rivals, Ryanair could afford to fill its planes with passengers buying low-price tickets. However, Ryanair could make a profit because passengers would also spend money on areas such as on-board food and hotel reservations.

Ryanair is able to increase profits year after year since it continually looks for ways to keep costs down and charge customers for extras.



Porter's generic business strategies fall within two basic categories: lowest cost or marked differentiation. Companies can choose between these approaches whether they are small or large, and whether they are operating in broad target markets, or niche ones.

Singapore Airlines' customer service ethic is personified by "The Singapore Girl," who portrays the idea of Asian hospitality. Her image has become a successful brand icon.

These include being the first airline to implement baggage charges; working to eliminate the need for check-in desks (by offering online check-in facilities); and charging for options such as seat reservation and priority boarding. This consistent search for new ways to transform costs is the essence of the cost-leadership strategy. In the 12 months ending March 31, 2013, Ryanair transported nearly 80 million passengers and announced record profits of $753 million, despite a rise in fuel costs.

Singapore Airlines (SIA) by contrast, pursues a differentiation strategy. The brand's major drivers are groundbreaking technology, innovation, quality, and excellent customer service. It maintains the youngest fleet of aircraft among major air carriers, and keeps to a stringent policy of replacing older aircraft with newer, better models. SIA has always been first to take delivery of new aircraft types. Singapore Airlines recognizes that innovation is short-lived in the airline industry. New features and ideas can easily be copied by other airlines, so it continues to invest heavily in innovation and technology as an integral part of achieving its differentiation strategy. The airline runs a comprehensive and rigorous training program for cabin- and flight-crew to ensure the customer's in-flight experience is consistently excellent. The success of its brand strategy and its entire positioning around service excellence mean that customers are more than happy to pay a premium price.

Porter's generic business strategies can be used by any company to achieve a competitive advantage. However, the competitive environment consists of more than just present rivals; changes in the industry and environment add to a constantly changing business context. For this reason, strategy choice must be regularly reviewed and checked. ■

Ben & Jerry's ice cream is now part of the Unilever brand, but continues to use the differentiation strategy it adopted to become a market leader.

Ice cream with a difference

Quirky flavor names—such as Imagine Whirled Peace, Chubby Hubby, and Brownie Chew Gooder—set Ben & Jerry's ice creams apart. Ben Cohen and Jerry Greenfield started the company in 1978 and wanted it to be alternative. According to Jerry, "if it's not fun, why do it?" Ben claims to have no sense of taste, so he relied on texture (what he called "mouth feel")—big chunks of added ingredients such as fruit, chocolate, or cookies therefore became the brand's signature. Consumers are prepared to pay a premium price because of the ice cream's all-natural, high-quality ingredients and innovative flavors—months of research go into perfecting the taste. The company's strategy to differentiate itself from the competition extends beyond the product. The organization is active in social campaigns such as gay marriage, buys only from fair-trade suppliers, and considers environmental aspects in production and delivery.

THE ESSENCE OF STRATEGY IS CHOOSING WHAT NOT TO DO

GOOD AND BAD STRATEGY

IN CONTEXT

FOCUS
Strategic thinking

KEY DATES

1960s Strategic planning grows in popularity, and is enthusiastically adopted in the new field of management consultancy.

1962 Alfred Chandler's *Strategy and Structure* sets out a model in which a company's structure matches its strategy, not vice versa.

1985 Michael Porter's *Competitive Advantage* redefines business thinking on competition, repopularizing the ailing field of strategic thinking in the process.

1990s/2000s Strategy is increasingly practiced as a continuous process by all in a business, not just by those at boardroom level. Nokia says that strategy should be "a daily part of a manager's activity."

Strategy is a concept with its roots in military history, when army generals planned campaigns of war. Today, it is an overused and often misunderstood word in business theory. Put simply, strategy is the way a business gets from where it is to where it wants to be; it involves identifying the choices that must be made to overcome the obstacles that lie in the way. Often, choosing what not to do is as important as what to do. Strategy guru Michael Porter first drew attention to this in 1985, then specifically explored it in his 1996 article "What is Strategy?"

For businesses, it is just as possible to follow bad strategy as good. Richard Rumelt's *Good Strategy/Bad Strategy* (2012) explained that good strategy should emerge out of an analysis of the company itself, and its goals. SWOT analysis (strengths, weaknesses, opportunities, and threats) is one of the most popular systems for such audits, and to be effective it should be conducted among middle managers and people across the organization, not just those at the top. Good strategy requires analysis of the competition and any threats to the organization, and may involve painful decisions. It should result in a strategy based on clear goals that capitalizes on the company's strengths and can be flexible if external factors change.

Kodak failed to recognize that film-based photography was effectively "what not to do." Choosing to move away from this area could have made Kodak a market leader in digital technology.

Bad strategy often goes hand in hand with setting a simplistic goal or vision. Leaders in organizations may use powerful rhetoric about "winning" to motivate staff, but empty goals are easy to set—formulating the strategy required to achieve them is much more difficult. Executives bent on pursuing a bad strategy will ignore problems and

See also: Protect the core business 170–71 ▪ Avoiding complacency 194–201 ▪ Porter's five forces 212–15 ▪ The value chain 216–17

Company A sets out to define its strategy for the coming years. It conducts analysis to understand...

...its **strengths**, such as quality of manufacturing...

...its **weaknesses**, such as manufacturing capacity or the availability of skilled labor...

...its **opportunities**, such as developing new products or going into different markets...

...and its **threats**, such as the strength of the competition, or shortage of raw materials.

Company A must **set clear goals** and decide **where to focus its efforts**.

The essence of strategy is choosing what not to do.

be blinded to the choices available. Rather than making tough decisions, they will try to accommodate a multitude of conflicting demands and interests to stick to a plan. Managers in these circumstances risk following old ideas and paths that no longer work, rather than leading with new ones.

Film is dead

The demise of Kodak is a prime example of a company following bad strategy. Founded in 1890, by the 1970s Kodak was the US market leader in the photographic sector, with nearly 90 percent of the film and camera market. It was rated as one of the world's top brands. In 1975 Kodak engineers invented the digital camera, but the senior management of Kodak ignored the opportunity presented by this new technology. They believed they were in the chemistry-based film business and were not prepared to "kill the golden goose." Executives failed to see that digital photography would make film redundant and challenge their near-monopoly business. Japanese company Fujifilm, however, recognized the threat and diversified successfully. Kodak began its shift to digital cameras too late, as smartphones and tablets replaced cameras. The senior executives' inability to make the tough decision to change course led to the company being declared bankrupt in 2012. ■

Richard Rumelt

Professor Richard Rumelt (1942–) studied electrical engineering at the University of California, Berkeley, before going on to receive a doctorate in business administration from Harvard Business School in 1972. He worked as a systems engineer at NASA's Jet Propulsion Laboratories while also serving on the faculty of Harvard Business School. In 1976 he joined the Anderson School of Management at the University of California, where he has remained ever since, rising to become Professor of Business and Society. From 1993 to 1996 he taught at INSEAD, the leading French business school at Fontainebleau, near Paris. Rumelt also works as a consultant to several companies and governments.

Key works

1982 *Diversity and Profitability*
1991 *How Much Does Industry Matter?*
2012 *Good Strategy/Bad Strategy*

> “Good strategy honestly acknowledges the challenges being faced and provides an approach to overcoming them.”
> **Richard Rumelt**

SYNERGY AND OTHER LIES

WHY TAKEOVERS DISAPPOINT

IN CONTEXT

FOCUS
Mergers and takeovers

KEY DATES
1890–1905 The first "takeover wave" occurs in the US and Europe, triggered by an economic depression and new legislation.

1960s Abraham Maslow applies the idea of "synergy" to the way that employees in organizations work together.

2001 US companies AOL and Time Warner merge in a deal worth $182 billion. It does not work out, and in 2009 the companies become separate entities.

2007 In the US alone, 144 takeover deals worth more than $1 billion take place.

2009 Only 35 takeover deals worth more than $1 billion take place in the US.

Companies have to grow in order to survive. One way to make an organization bigger is to buy (acquire) another and make it part of the original company. Alternatively, two businesses can agree to merge, forming another organization with an entirely new identity. The purpose of an acquisition or merger is often to increase shareholder value beyond the sum of the two companies. These benefits are known as "synergy"; the concept being that one plus one equals three.

The reasons for two businesses joining together might seem compelling. The new, combined company increases sales, market share, and revenue. It should also be a more efficient operation. Bigger companies also enjoy economies of scale: overhead costs are shared and money can be saved from increased buying power. Fixed costs can also be reduced because the combined business needs less staff in functions such as finance, human resources, and marketing, than the two separate entities. Companies' also buy businesses to acquire new technology, reach new markets, or increase distribution.

Corporate divorce

In practice, takeovers and mergers are rarely marriages made in heaven, a fact underlined by Harold Geneen in the books he co-authored in 1997 and 1999 on the pretence of synergy. Mergers can fail to deliver the value promised, with one plus one often equaling less than two. There are many reasons for failure. Hidden



Synergy is the additional value that is created when two business units are joined. A holy grail in business circles, academics Campbell and Goold concluded that "synergy initiatives often fall short of management's expectations".

See also: The Greiner curve 58–61 ▪ Organizing teams and talent 80–85 ▪ Organizational culture 104–09 ▪ Protect the core business 170–71



Company A makes widgets and sells them in the north.

Company A **agrees to buy** Company B. The legal processes are completed.

Company B makes widgets and sells them in the south.

Company A has a **formal, hierarchical culture** with highly defined roles and levels of management.

New company "AB" is formed from two companies with **mismatching cultures**.

Company B has an **informal, democratic culture** where staff forms teams to match skills to projects.

The new company does not deliver synergy. Takeovers disappoint.

problems might be discovered after the deal is done because of the limitations on sharing commercially sensitive information prior to common ownership. The focus at the time of the deal is often on the event of joining together rather than planning what will happen next. Effective integration requires quick, courageous decision making so that time and momentum are not lost. However, the most common reason for failure is that the two organizations have different approaches and lack synergy.

In 1998, German car producer Daimler-Benz bought US automotive business Chrysler for $38 billion. The logic seemed obvious: create a trans-Atlantic powerhouse that would dominate motor markets. The new company, DaimlerChrysler, was dubbed a "merger of equals." But the reality was a classic culture clash. Daimler was a formal, hierarchical organization, while Chrysler favored a more team-oriented approach. Chrysler operated in a market where low price and catchy design were important; high-end Daimler was focused on quality and luxury.

Chrysler executives felt undermined in the new alliance because Daimler tried to dictate the terms on which the new business should work and to place its people in key positions. The result was a costly corporate divorce with Daimler-Benz selling Chrysler to a private-equity firm for a mere $7 billion in 2007. ■

Harold Geneen

Harold Geneen was born in Dorset, UK, in 1910, but his parents emigrated soon after his birth and he was raised in the US. He studied accounting at NYU (New York University) and went on to become a highly successful businessman in the US. He is best known as the father of the conglomerate concept, where a large corporation is created from seemingly unrelated businesses. In 1959 he became president and CEO of International Telephone and Telegraph Corporation (ITT), and grew the company from a medium-sized business to a multinational conglomerate. His 18-year tenure included 350 acquisitions and mergers in more than 80 different countries, including Sheraton Hotels in the US, and telecommunications companies in Europe and Brazil. Despite his success and wealth, he was known for his no-nonsense values and plain talking. He died in 1997.

Key works

1997 *The Synergy Myth* (with Brent Bowers)
1999 *Synergy and Other Lies* (with Brent Bowers)

THE CHINESE WORD “CRISIS” IS COMPOSED OF TWO CHARACTERS: “DANGER” AND “OPPORTUNITY”

CRISIS MANAGEMENT

IN CONTEXT

FOCUS
Business crises

KEY DATES
1987 Ian Mitroff, Paul Shrivastava, and Firdaus Udwadia publish the paper “Effective Crisis Management.”

1988 Shrivastava, Mitroff, Danny Miller, and Anil Miglani say that organizational crisis requires an interdisciplinary approach, using psychological, technological-structural and social-political perspectives.

1995 A. Gonzalez-Herrero and C. Pratt suggest a model for crisis management: diagnosis of impending trouble; decision and actions; implementation of change; and monitoring.

2000s Business continuity planning is introduced to deal with terrorism and major technology failure.

2010s Social media allows a crisis to be publicized rapidly, often to a company’s detriment.

Mankind has faced crises throughout history, from natural disasters to man-made calamities. Businesses face similar crises—internal or external events can pose major threats to the organization. Unpredictable in nature, they require quick decision making and action from leaders.

Globalization has increased the complexity of the business world, so an event in one country can affect businesses across the world. Digital, 24/7 communication means that news travels far and fast. The result is that crises may seem to be more prevalent than they were during the predigital age.

Responding to crisis

The random nature of crises means that they can strike anywhere. Typical crises include technological failure; employee actions, from



A company develops a **crisis management plan** covering “who, what, when, where, and how” for the first critical hours.

An unpredictable, **major crisis hits the company**, requiring immediate decisions and actions.

Leadership takes control and **puts the crisis management plan into action**.

The crisis is effectively managed and, if possible, **turned into an opportunity**.

See also: Managing risk 40–41 ▪ Hubris and nemesis 100–03 ▪ Learning from failure 164–65 ▪ Contingency planning 210 ▪ Coping with chaos 220–21

Tylenol was the top pain reliever in the US when it was hit by a crisis: lethally contaminated capsules. Over 30 million bottles were recalled at huge cost, but consumer faith was retained.

walkouts to fraud; sudden supplier loss or rising prices in raw materials; and environmental disasters. Every crisis has the potential to damage a company's profits and reputation. The extent to which it is able to withstand a crisis and limit the damage is determined by its ability to respond fast and appropriately.

Planning and decisions

Effective crisis management involves careful planning, so that if a crisis strikes it can be addressed in a calm, professional way. This involves quickly establishing the "who, what, when, where, and how" of the crisis within the critical first few hours. Any crisis—no matter how small—is newsworthy, so a company's public response must be fast. Public perception affects consumer trust.

Leadership during a crisis is particularly important, since swift, effective decision making is critical. Every company recognizes that if it handles a crisis well, damage can be minimized and its reputation even enhanced. As president John F Kennedy said, "in Chinese, the word 'crisis' is composed of two characters—one represents danger and one represents opportunity."

Handling a crisis

In 1982, Johnson & Johnson reacted to a crisis effectively when Tylenol pain-relief capsules sold in the Chicago, IL, area had been laced with cyanide. The company recalled the product, stopped advertising, and reintroduced Tylenol in a triple-seal, tamper-resistant package. The public felt reassured by the move, and once again trusted the product.

At around the same time, another US company tried to contain a similar crisis using a very different approach. A woman returned a jar of Gerber Product's baby food to her local supermarket, saying that it contained a shard of glass. Gerber ran laboratory tests and found nothing; the store had lost the shard, and the company decided there was no problem on its production line. However, customers in 30 different states then said they too had found glass in the baby food. The company could find no evidence to support these claims, so announced that they were "being had" by people wanting to file false liability claims. They did not recall any products. Public confidence in the company fell; some states demanded other Gerber products be removed from stores. Although the company's position was evidence-based, it seemed callously indifferent to the welfare of babies. It lost sight of the essential rule in any crisis: always show commitment to the safety and well-being of your consumers. ■

Supplier roles in crisis

In their article "The Toyota Group and the Aisin Fire," authors Toshihiro Nishiguchi and Alexandre Beaudet demonstrated the importance of supplier relationships during a crisis. In 1997, a fire at the plant of one of Toyota's most trusted suppliers, Aisin Seiki, threatened to halt Toyota-group operations for weeks. Aisin Seiki was the sole source for a small but crucial part used in all Toyota vehicles. Only two or three days' worth of stock was on hand. Toyota's manufacturing plants shut down but were reopened after only two days. The recovery was achieved through an immediate and largely self-organized effort by companies from within and outside the Toyota group, who set up alternative production sites. The collaborative effort of more than 200 companies was orchestrated with limited direct control from Toyota and with no haggling over technical proprietary rights or financial compensation.

> “Effective crisis management is a never-ending process, not an event with a beginning and an end.”
>
> **Ian Mitroff, Paul Shrivastava, Firdaus Udwadia**

YOU CAN'T GROW LONG-TERM IF YOU CAN'T EAT SHORT-TERM

BALANCING LONG- VERSUS SHORT-TERMISM

IN CONTEXT

FOCUS
Managing objectives

KEY DATES
1938 US author F. Scott Fitzgerald writes that "intelligence is the ability to hold two opposed ideas in the mind at the same time, and still retain the ability to function."

1994 US business experts James Collins and Jerry Porras publish *Built To Last: Successful Habits of Visionary Companies*.

2009 In *The Opposable Mind*, Canadian business professor Roger Martin claims that great business leaders are able to use "integrative thinking" to creatively resolve the tension in opposing ideas and models.



If a company only thinks **short-term**...

...about **immediate issues** with customers, wages, suppliers, and staff...

...it becomes outdated and creates **no new opportunities for growth**.

If a company only thinks **long-term**...

...about new products, new markets, **innovation, and growth**...

...it **runs out of capital** to fund investment.

Successful companies have to balance short-term and long-term thinking.

A successful business has to balance two different time horizons: short-term and long-term. In the short term, a company needs cash to pay its wages and bills. But if it focuses too much on the immedate present, it risks missing opportunities. Conversely, if a company's sole focus is on new prospects, it will soon become unprofitable. As Jack Welch, CEO of GE, said: "You can't grow long-term if you can't eat short-term. Anybody can manage short. Anybody can manage long. Balancing those two things is what management is."

See also: Take the second step 43 ▪ How fast to grow 44–45 ▪ Effective leadership 78–79 ▪ Investment and dividends 126–27 ▪ Accountability and governance 130–31 ▪ Profit versus cash flow 152–53

In 1994, James Collins and Jerry Porras studied companies such as General Electric, Marriott, and 3M that had been in business for more than a century and that consistently outperformed the stock market. They used the Chinese yin-yang sign—symbolizing complementary opposites—to explain how successful businesses maintain control of both the short- and long-term. The organizations they studied were able to manage contradictory ideas at the same time, by focusing on "both … and …" rather than "either … or …" They also demonstrated the concept by performing well both in the short-term and in the long-term.

Public and private

In a private limited company (Ltd), managers can plan for different time horizons without scrutiny from shareholders. Sir Anthony Bamford, for example, runs JCB, a privately owned British company. JCB was started by his father, Joseph Cyril Bamford, who began making agricultural tipping trailers in 1945. Today JCB is the third-largest manufacturer of earth-moving machinery in the world, with 22 factories in Europe, Asia, and North and South America. Bamford can invest when and where he chooses. He decided to invest in India by opening a factory in 1978, a long-term prospect that paid off; JCB is now market leader there. In 2012, JCB opened a factory in Brazil.

Unlike many CEOs, who hold a post for a few years then move on, Bamford saw that balancing the short- and long-term is critical. His dual focus has paid off: despite the worldwide recession, JCB sales grew 40 percent in 2011 and topped £2.75 ($4.3) billion in 2012.

In contrast, a typical public limited company (plc), owned by shareholders and quoted on a stock exchange, is under greater scrutiny. These investors look for returns, in the form of dividends, on an annual basis. This can become a strategic issue, since institutional shareholders may put pressure on directors of limited companies to return cash, rather than to reinvest in the business, without regard to the impact on long-term prospects. This happened in 2013 at Apple.

To ensure the right balance between short- and long-term, companies often split planning responsibility between different management teams. This allows the organization to manage the immediate operation, while looking ahead for growth and innovation. ■



The yin-yang symbol reflects the dual nature of visionary companies, according to Collins and Porras. They suggest replacing the "tyranny of the 'OR'" with the "genius of the 'AND.'"

Jack Welch

Born in 1935, John F. Welch studied chemical engineering at the University of Massachusetts, then gained an MSc and PhD in chemical engineering from the University of Illinois. In 1960, he joined General Electric (GE), rising to become the company's chairman and CEO from 1981 until his retirement in 2001. During this time, Welch increased the value of the business from $13 billion to several-hundred billion. His management skills became legendary; he had little time for bureaucracy and managers were given free reign as long as they followed the GE ethic of constant change and striving to do better. In 1999, *Fortune* magazine named him Manager of the Century, and the *Financial Times* claimed he was one of the three most admired business leaders in the world. He founded the Jack Welch Management Institute at Strayer University, US, in 2009.

Key works

2001 *Jack: Straight from the Gut* (with John A Byrne)
2005 *Winning*

MARKET ATTRACTIVENESS, BUSINESS ATTRACTIVENESS

THE MABA MATRIX

IN CONTEXT

FOCUS
Business strategy

KEY DATES

Early 1970s The Boston Consulting Group develops the Growth-share matrix to help companies decide how to allocate resources to products or business units on the basis of their relative market shares and growth rates.

1970s McKinsey & Company consultants develops the MABA matrix.

1979 Michael Porter develops the Five Forces model to enable companies to analyze the structure of their industry and develop a more profitable position.

2000 The Market-Activated Corporate Strategy (MACS) framework is introduced by McKinsey to measure each business unit's stand-alone value within the corporation and health for sale.

An organization must **allocate capital** between its different business units, or to different products.

A consistent method for a company to **identify where to invest, and where to cut back,** is to analyze...

...**Market Attractiveness** (the size of the market, its growth potential, and pricing), and...

...**Business Attractiveness** (the competitive strength of the unit or product in that market).

Using the MABA matrix can help a company **plot the relative profitability of its business units or products.**

Until the mid-20th century, many businesses were simple companies selling one product. However, from around 1950, large corporations emerged, which were divided into business units. It was difficult to manage these different units profitably, so management consultants began to develop frameworks to address the new complexity. One such model to arise during the early 1970s was MABA—the market attractiveness/business attractiveness framework. It is also known as the GE-McKinsey nine-box framework and the GE-McKinsey Matrix, because it was developed by consulting

See also: Study the competition 24–27 ▪ Protect the core business 170–71 ▪ Good and bad strategy 184–85 ▪ Porter's five forces 212–15 ▪ The value chain 216–17 ▪ Product portfolio 250–55 ▪ Ansoff's matrix 256–57

company McKinsey & Company for conglomerate General Electric, which had 150 business units.

The MABA matrix is a systematic, consistent method for a decentralized corporation to decide how to share its capital among the various business units by assessing each unit's profitability and market position. Past methods of budget allocation relied on each business unit's forecasts for growth and profitability, which were subject to error. Although designed for large companies, the matrix can also be used by smaller companies to assess the strength of a product line or brands, rather than business units.



MARKET ATTRACTIVENESS	High	Medium	Low
High	**GROW**— invest and grow	**GROW**— invest and grow	**HOLD**— invest selectively if cash allows
Medium	**GROW**— invest and grow	**HOLD**— invest selectively if cash allows	**HARVEST** for cash, then sell
Low	**HOLD**— invest selectively if cash allows	**HARVEST** for cash, then sell	**HARVEST** for cash, then sell

The MABA matrix provides a means of identifying which business units should be grown, held at their current level, or sold. Those at the top left of the matrix have a high business and market attractiveness, and should be grown. Those in the center have medium ratings for both factors, and may warrant selective investment. Those at the bottom right have low scores for both factors, and should be harvested for cash, and sold or liquidated.

Using the matrix

The matrix allows a company to judge each business unit on two factors to determine its future success: the attractiveness of its industry or market, and the business unit's competitive strength within that industry. Market attractiveness is rated according to the market size, growth rate, profitability, and level of competition. Business attractiveness is rated according to the unit or product's current and growth level of market share, its brand strength, and its profit margins relative to rivals.

By plotting the attractiveness of an industry on one axis and the competitive position of a business unit in that industry along the other, large corporations can compare the strengths of diverse business units. The matrix condenses the value-creation potential of multiple business units into a single, digestible chart.

Each business unit or product must be evaluated, using data analysis, and placed within the matrix according to their market and business attractiveness. This sorts units into three categories: those that should be "grown" through investment, "held" (invested in selectively), and "harvested" for cash and either sold or liquidated.

Sorting units into these three categories provides a starting point for strategic analysis, and for determining where to invest to yield the highest growth. Over the years, the criteria for assessing industry attractiveness and competitive strength have grown more sophisticated. But even today, most large organizations with a formal approach to modeling their businesses use the MABA matrix or one of its derivatives. ■

Why Kraft gobbled up Cadbury

When Illinois-based Kraft Foods bought British chocolate manufacturer Cadbury for more than $19 billion in 2010, it was because it saw Cadbury's competitive strength in an attractive industry. Cadbury would be positioned at the top left of the MABA matrix. Kraft was already the world's second-biggest food business with strong brands of its own, but it was generating 80 percent of its sales from the US and it was eager to capitalize on the potential for growth elsewhere in the world. In the first half of 2009 alone, 69 percent of Cadbury's sales growth came from emerging markets. The British company offered Kraft greater access to these markets, including the BRIC economies—Brazil, Russia, India, and China. Cadbury also had some of the world's leading chocolate, candy, and chewing gum brands. Cadbury's Chocolate, for example, was already a leading brand in India.

ONLY THE PARANOID SURVIVE

AVOIDING COMPLACENCY



IN CONTEXT

FOCUS
Business change

KEY DATES
1979 Michael Porter writes *How Competitive Forces Shape Strategy*, saying that managers must always be aware of what the competition is doing.

1994 In *The Empty Raincoat: Making Sense of the Future*, Charles Handy uses a graph to illustrate how organizations have to be alert and respond to threats.

1996 Andy Grove writes *Only the Paranoid Survive*.

2010 In *The Black Swan: The Impact of the Highly Improbable*, Nassim Nicholas Taleb explains that we cannot predict the future from the past, so must expect (and prepare for) the unexpected.

It is often easier for people outside a company to spot complacency than it is for those inside; executives are sometimes blind to it until their company plunges into a downward spiral. Research in Motion (RIM), manufacturer of the once-iconic BlackBerry, developed the idea of sending and receiving emails on mobile phones, and their innovation helped them to become the market leader. However, RIM rested on its success instead of continuing to innovate, and did not notice or foresee the direction in which Apple's products were developing. The rival technology company's iPhone delivered mobile emails and a range of other features. RIM quickly went from being the market leader into a period of decline, because it had become complacent instead of remaining alert to technological change, or threats from competitors.

It is human nature to relax when things are going well, but history shows this is the very moment to be wary. Former CEO of Intel, Andy Grove, believes that "Success breeds complacency. Complacency breeds failure. Only the paranoid survive." The latter phrase was framed by five questions (see below), and became the title of one of Grove's books. Grove had fled the communist regime in Hungary, and learned from a young age that paranoia could be a useful survival skill. Many years later, when he joined Intel, he transferred the skills of watching out for himself to monitoring the company, steering it safely through a series of threats.

> A strategic inflection point is a time in the life of a business when its fundamentals are about to change.
> **Andy Grove**

Strategic inflection point

Every business faces change. Occasionally change can be massive, and positions once taken for granted can shift dramatically. Grove calls

Grove's Five Questions

Do you think your **competition has changed**?

Is your old rival **no longer the biggest threat**?

Are you **relying on a complementary company** to make your company attractive?

Is everyone **talking about someone new**?

Where would you **point a gun** if you had one?

Only the paranoid survive.

See also: Reinventing and adapting 52–57 ▪ Changing the game 92–99 ▪ Hubris and nemesis 100–03 ▪ Learning from failure 164–65 ▪ Porter's five forces 212–15 ▪ Coping with chaos 220–21 ▪ Forecasting 278–79 ▪ Feedback and innovation 312–13

such a moment a "strategic inflection point." This is not necessarily a single point in time, but it is usually accompanied by a noticeable period of unrest within the organization. It may be initiated by changes in the external environment, or by new competition, and senior managers are often among the last to notice what is happening.

Intel's first strategic inflection point came when Japanese companies began to produce better-quality, lower-cost memory chips than US companies in the 1980s. It took Grove three years and huge losses to realize that only through rethinking and repositioning could Intel again become a market leader.

A strategic inflection point is the point at which a major change (such as the arrival of the Internet) takes place in the competitive environment. If the company recognizes it and adjusts, the company may soar; if it ignores the change, the company will decline.


Business goes on to new heights
Inflection point
The arrival of new technology, new industry regulations, or a change in customer values or preferences
Business declines

10X change

In the 1970s, US professor Michael Porter summarized five competitive forces that face companies: competition, substitute products, new entrants, suppliers, and buyers. Grove added a sixth force: complementary products. This is the impact of other businesses that sell a product or service that complement a company's own product or service by adding value to mutual customers; for example, software products complement those produced by computer hardware manufacturers.

Grove describes all these forces as "a steady wind," but if one force becomes ten times stronger it acts more like a typhoon. Leaders have to be alert to such major change—a "10X" change—because it requires a fundamental change in strategy. Depending on the actions leaders take at this point, the change can either take the organization to new heights or send it spiraling down into oblivion. The important thing for leaders is to discern between expected change and profound change, when the balance of forces shifts from old to new.

In his book, Grove uses the example of the growth of the Internet. The Internet was a "10X" change for every company, but some failed to recognize its force or were complacent and did not take action to exploit it. Many companies in the book industry were guilty of these failures—even those who had been extremely »

intel
2200 Mission College Blvd.
NO PHOTOS

The Intel Corporation in California, US, became the world's largest computer-chip maker under Andy Grove's leadership. He encouraged employees to bring him bad news.

> It is not the strongest
> of the species that survive,
> nor the most intelligent,
> but the one most
> responsive to change.
> **Leon C. Megginson**
> **US management professor (1921–2010)**

proactive. In 1974, US company Barnes & Noble was the first bookseller to advertise on television, in 1975 it was the first to discount books, and in 1989 it opened a "book superstore." Its innovations helped it to hold a large share of the retail market. By 1995 it had 358 book superstores—but by 1996, the Internet had changed everything. Amazon—a master at Internet selling—suddenly outstripped it in sales and market valuation.

Staying alert

Points of sizable change are hard to spot, so executives must constantly scan the horizon, like a ship's watchmen looking for an iceberg that could sink the business. Companies today use many different approaches to monitor the competition and market. Typically, a large organization employs a team of people to scrutinize the company's sales, compare them to the competition, and analyze market trends. They may also have a team responsible for risk management, which covers far more than operational risks (such as safety). In recent times, such teams tend to monitor far-reaching global concerns, including weather extremes resulting from climate change, political change, and human-rights issues.

Successful negotiation of change relies not just on scanning the environment, but also making sense of the incoming information. Senior executives need to be particularly wary of understanding events and making decisions based solely on data or past events. In *The Black Swan: The Impact of the Highly Improbable*, Nassim Nicholas Taleb explains how individuals, businesses, and governments place too much weight on the odds that past events will be repeated. Forecasting the future from the past ignores the fact that the future holds different possibilities, as yet unseen. For example, if you have only ever seen white swans, you might assume that all swans are white; unless you traveled to Australia and chanced upon a black swan. Taleb used the metaphor of the black swan to discuss major scientific discoveries and historical events. These "black swan events" combine low predictability and high impact. Examples include the 9/11 terrorist attacks in the US and the stock market crash of 1987. Taleb states that companies can never predict black swan events, but they do need to build robustness against potential negative eventualities, and be ready to exploit positive ones.

Listening to the front line

Grove claimed that business data (like white swans) is relevant only to the company's past, and cannot be used to predict the future. He suggests that when searching for clues about how to deal with the future, executives should look elsewhere, such as scrutinizing any misalignment between the company's strategy statements and its strategy actions. What is the difference between what the company says it is planning to do,

Black swans are rare but they do exist, which comes as something of a surprise to people who have only seen white ones. This demonstrates the error of basing predictions on past experiences.

Black Monday—October 19, 1987, when stock markets across the world suffered huge losses—was a strategic inflection point that caused massive change in the business environment.

and what it is actually doing? Actions are driven by the stark reality of having to win business in the marketplace against the competition; a company's front-line personnel are likely to see and adapt to a new reality first. They are the people best positioned to identify critical issues.

This means that leaders in the organization have to be prepared to listen to people dealing with customers and suppliers—who often tend to be at the lower level of a company's hierarchy—and absorb what they are saying. It helps to have an organizational culture that encourages this and ensures that people are not afraid to speak out.

For the same reasons, it is just as important for senior management to listen to the kind of information being exchanged in corridor conversations, networking functions, and the general office grapevine as it is for them to use competitive analysis and modeling.

The "5-why" technique

To ensure they understand what is driving or impacting a company's performance, and what is happening in the market and the wider world, senior executives have to constantly ask questions. They also need to understand not just "what" is happening, but "why." One method to achieve this is the "5-why" technique, invented in the 1930s by the father of Kiichiro Toyoda, the founder of Toyota, and used by Toyota during the 1970s. By asking "why?" five times, you can move from the symptoms to the root cause of a problem. For example, the first question might be "why did we miss the deadline?" to which the answer might be "it took longer to complete the project than we thought it would." Why? "Because we underestimated the complexity of the task." Why? "Because we did a quick time estimate, without going through the project requirements in detail." Why? "Because we were already running behind on four projects." Why? "Because we are not allowing enough lead time when quoting." The technique can be used to interrogate internally and externally caused problems.

> “
> It is extremely important to be able to listen to the people who bring you bad news.
> **Andy Grove**
> ”

It is also important to ask the right questions. Management guru Peter Drucker claims that "the most serious mistakes are not made as a result of wrong answers. The truly dangerous thing is asking the wrong question."

Which questions to ask

Questioning goes beyond looking at the competitive environment. Sales bring in revenue, but companies also have to look at costs, because profit lies in the gap between these two. Managers must question their processes, to see where they can drive efficiencies, reduce costs, and so improve their profit margins.

Managers also need to constantly question whether there might be a better way to do something. For example, perhaps nonessential functions could be outsourced. Managers have to be restless, not complacent, and look for every opportunity to increase the profit margin and improve the business.

Managers have to use their knowledge and experience to connect all the information they gather, and try to anticipate what the world will look like in five or ten years' time. What changes might take place in that new world? They then have to position the company to take advantage. This requires thinking through several different scenarios and being able to think "outside the box." »

Victorinox's business model relied on the sales of its Swiss Pocket Knives, but a strategic inflection point—the prohibition of knives on planes—forced it to add luxury products to its range.

The impact of the 9/11 terrorist attacks on the US in September 2001 was felt across the world; for some businesses it proved to be a strategic inflection point. One such company was Victorinox, manufacturer of the ubiquitous Swiss Pocket Knife. The company had been producing pen knives since 1884, but it was hit by new airline safety regulations that prohibited knives to be carried on board aircraft following the 9/11 attacks. This had a drastic effect on Victorinox, because purchases of its products at airports around the world accounted for a significant portion of its annual sales.

Corporate sales also tumbled. By the beginning of 2002, pocket-tool sales had fallen 30 percent in just a few months. The company recognized that this could represent the start of a long decline, and that to survive, action would have to be taken. The development of other products—including watches, travel gear, fragrances, and fashion—that could be sold at airports was accelerated. The company also began to explore new market opportunities, such as selling in China, India, and Russia.

Victorinox also took action to preserve one of its core strengths—a skilled and loyal Swiss work force. Layoffs were prevented by taking crisis measures such as reducing shift times, canceling overtime, encouraging planned vacations, and temporarily lending workers to other Swiss companies. Victorinox not only survived, but thanks to its new products, was able to enhance its high-quality brand image. More than 60 percent of the company's turnover now comes from items other than pocket knives.

Averting catastrophe

To detect the approach of a strategic inflection point, the CEO of a company, in conjunction with the board, must analyze all the available hard data, listen to the softer information, and then take decisive action. British Petroleum (BP), once owned by the British government, became publicly owned in 1987. Its new CEO was John Browne, a nonexecutive director of Intel, who was influenced by Andy Groves's thinking on the importance of paranoia. Browne was concerned about something far bigger than rival companies—something that could harm the business of not just BP, but the entire oil industry.

Browne reviewed the available data on climate change, listened to experts in the field, and considered the impact on the business of BP. He recognized climate change as a slow-manifesting issue, but realized it could impact the oil industry. In 1997 he gave a seminal speech at Stanford University, CA, publicly acknowledging climate change as a reality and committing BP to do something about it.

This was a bold move for an oil company at a time when rival companies were trying to ignore the issue. BP pursued a strategy of investing in alternative energy, and it was the first oil company to set targets for reducing its own greenhouse gas emissions. Employees were asked to find ways

> Real sustainability is about simultaneously being profitable and responding to the reality and the concerns of the world in which you operate.
> **John Browne**
> **UK former CEO of BP (1948–)**

to help meet targets. Browne caused more of a stir when BP launched a new brand identity in 2000. The bright green Helios logo, named after the sun god of ancient Greece, was accompanied by the slogan: “Beyond Petroleum”. It represented the company’s acknowledgement that it needed to provide more, and smarter, types of energy. It also sent a clear message that the company was not complacent; it was prepared to confront and adapt to difficult issues.

However, after Browne left BP in 2007, the new CEO pursued a different strategy, and the alternative energy business was closed down. Any environmental credibility the company had built was lost when an oil well exploded in the Gulf of Mexico in 2010.

BP’s Helios logo demonstrated its commitment to finding new types of energy sources. Company responses to 10X changes, such as climate change, need to be communicated to the market.

Conquering complacency

In the late 1990s, UK retailer Marks & Spencer (M&S) took almost the opposite stance to John Browne at BP. Board members largely ignored the changing UK and global retail environments, and chose to focus on internal issues. The company was hierarchical and employees were expected to follow orders. In *The Rise and Fall of Marks & Spencer*, author Judi Bevan describes a traditional business environment with carpeted executive offices, waiters with white gloves, and staff rules governing punctuality, efficiency, and politeness. M&S did not have a marketing department and its executives believed it did not need to advertise. Stores did not accept credit cards, and payment was possible only with cash or M&S’s own charge card.

When rival retailers appeared with a more modern vision and fresh, contemporary designs, M&S’s clothes and stores began to look old-fashioned. Consumers started to shop elsewhere, but still M&S did not change course, despite a sudden drop in sales and profits. UK profits continued to tumble from a record high of $1.6 (£1) billion in 1997 to $232 (£146) million four years later, and the share price dropped by two-thirds. It was not until the emergency appointment of CEO Stuart Rose in 2004 to fend off a takeover that the dramatic decline was halted.

However, the recovery did not last: M&S once again risked complacency with a run of eight successive quarters of falling clothing sales to 2013. In response, the company announced it would invest in store revamps, logistics, and IT, and unveiled plans to turn M&S into an international, multichannel retailer, connecting with customers through stores, the Internet, and mobile devices.

This is the challenge for all organizations. Businesses must contend with accelerated change in a highly competitive, multichannel, global market, and guard against complacency—or risk losing out to competitors who are able to stay one step ahead. ■

Andy Grove

Andrew (“Andy”) Stephen Grove was born in 1936 to a Jewish family in Budapest, Hungary, as András István Gróf. He hid from the Nazis during their occupation of Hungary, survived the Siege of Budapest by the Soviet Red Army, then fled to the US during the uprising of 1956. Once there, he took the name Andrew Grove, graduated first in his engineering class at college and then studied for a PhD in chemical engineering at the University of California, Berkeley. He relocated his parents to San Francisco, and worked at Fairchild Semiconductor (1963–67), before helping to found the Intel Corporation in 1968. He became its president in 1979, CEO in 1987, and was Chairman from 1998 to 2005. He is credited with the company’s success; during his tenure as CEO, Intel’s stock value rose by 2,400 percent, making it one of the world’s most valuable companies.

A dedicated philanthropist, Grove has donated millions of dollars to cancer and neuro-degenerative disease research. He also serves on the board of overseers of the International Rescue Committee.

TO EXCEL TAP INTO PEOPLE’S CAPACITY TO LEARN

THE LEARNING ORGANIZATION

IN CONTEXT

FOCUS
The personal approach

KEY DATES

1920s Charles Allen develops a training program for shipbuilders in the US, which involves personal teaching intended to develop loyalty.

1950s Job training becomes individualized, replacing the teacher with programed materials that employees work through at their own pace.

1984 Professor Richard Freeman proposes that workers are "stakeholders" and are vital to the survival of the organization.

1990 Peter Senge publishes *The Fifth Discipline*, advocating "the learning organization."

When a company is devoted to the development and education of its employees it will be able to reinvent itself constantly, adapting to the market due to the intellectual skills and commitment of its employees. If the key to success in a rapidly changing marketplace is adaptability and foresight, then it makes sense to train and foster talented individuals as a means of marshaling an entire organization.

This is the essence of what management authority Peter Senge called "the learning organization," a place "where people continually expand their capacity to create the results they truly desire, where new and expansive patterns of thinking are nurtured, where collective aspiration is set free, and where people are continually learning how to learn together." To reach this ideal a company should adopt a collective, community-minded approach so that employees feel part of a worthwhile enterprise that will nurture them, and in return those employees will show commitment to the business. Senge proposed his vision for a corporate utopia in *The Fifth Discipline* (1990). In this book he set out the five disciplines to which an organization should aspire in order to succeed in the long term: personal mastery; mental models; shared vision; team learning; and systems thinking—the fifth discipline, which incorporates the preceding four.

The five disciplines

The first two disciplines are individual. By personal mastery, Senge means that individuals should use their own interest and curiosity to improve their capabilities. Mental models refers to ingrained ways of thinking, which should be challenged so that individuals become aware of why they think in a particular way, and of the effect this has on behavior. Senge encouraged employees to analyze their own subtle mental filters and to be prepared to question and change them in order to adapt to the future.

The remaining three disciplines are collective. The goal of shared vision involves the members of an organization deciding together what they want to create and agreeing on targets and processes


To compete in a **constantly changing marketplace** a company needs...
...a **smart and adaptable** work force.
...a **responsive and insightful** approach.
The **work force** needs to **challenge itself** and the business.
The **business** must **learn from its employees** and constantly adapt.
To excel, tap into people's capacity to learn.

See also: The value of teams 70–71 ▪ Creativity and invention 72–73 ▪ Effective leadership 78–79 ▪ Organizing teams and talent 80–85 ▪ Make the most of your talent 86–87 ▪ Organizational culture 104–09 ▪ Develop emotional intelligence 110–11



The five disciplines defined by Peter Senge enable organizations to change and develop through both individual and collective learning.

to help them get there. In this way, employees will work toward a goal because they want to, not because they are told to. Team learning is the process of employees learning together through discussion and dialogue so that they become more effective as a team than they would be individually.

The fifth discipline is the ability to see the organization as a whole, with its own behavior patterns. This capability is crucial in order for people to recognize potentially counterproductive behaviors that have come about simply through repetition and have remained unchallenged over the years.

Employee turnover

It is pertinent that Senge's proposal appeared against a backdrop of corporate brain drain. According to a 2004 paper by Arie C. Glebbeek and Erik H. Bax from Groningen University, the Netherlands, published in the *Academy of Management Journal*, when the labor market tightened and labor scarcity grew during the 1990s, businesses became concerned with the detrimental effects of turnover.

Turnover of personnel is one of the great blights of modern corporations and nations alike. A desire for further learning and development motivates talented individuals to move in search of a better environment with more opportunity for advancement. It is estimated that the cost of replacing an employee is between 10 percent and 175 percent of the departing employee's salary, depending on the field of skill. Data from the OECD (Organization for Economic Cooperation and Development) showed an increase in skilled labor migration around the world starting in the early 1990s. Much of this drain was from developing countries, and became gain for host countries in North America, Australasia, and Europe. But even in advanced economies, brain drain was a feature of corporate life.

During the 1990s, the highest voluntary staff turnover rates in Asia were in Singapore. The Singapore hotel industry, for example, had an average annual turnover rate of 57.6 percent in 1997, while average annual turnover rates in the retail industry ranged from 74.4 percent to 80.4 percent between 1995 and 1997. One study by Singapore's Nanyang Business School in conjunction with the UK's Cardiff Business »

> Productivity … comes from challenged, empowered, rewarded teams of people.
>
> **Jack Welch**
>
> **US former CEO, General Electric**
>
> **(1935–)**

School concluded that poor management practices were the major reason for employee turnover. The problem of high turnover in lower-paid jobs is still an issue. In the January 2012 edition of the *Harvard Business Review*, Harvard Business School professor Zeynep Ton wrote about companies that had found a way to invest in their staff while keeping product costs low: "Highly successful retail chains ... not only invest heavily in store employees but also have the lowest prices in their industries, solid financial performance, and better customer service than their competitors. They have demonstrated that, even in the lowest-price segment of retail, bad jobs are not a cost-driven necessity but a choice. And they have proven that the key to breaking the trade-off is a combination of investment in the work force and operational practices that benefit employees, customers, and the company."

Learning by listening

Peter Senge's theory about corporate learning went beyond just minimizing labor turnover. He intended it to be a model by which companies could maximize their success by actively fostering the education of all employees in order to innovate and adapt. In this respect, Japan's Honda Motor Company is often cited in case studies as a perfect example of a "learning organization."

In the 1980s, while professor of business studies at Stanford University, Richard Pascale analyzed the management style of Japanese companies, Honda in particular. He concluded that "organizational agility" was the reason for Honda's success. As evidence he cited the entry of the Japanese company into the US market in 1959.

Honda had been preparing to launch its larger 250 cc and 350 cc motorcycles in Los Angeles, but the advance sales team soon realized that the big Japanese bikes were inadequate for road conditions and the vast distances traveled in the US. The team reluctantly sent the models back to Japan for testing. Meanwhile, the three Japanese salespeople had been zipping around Los Angeles on the 50 cc Super Cub, a best seller at home but considered inappropriate for the power-hungry American biker. Nevertheless, US interest in the Super Cub grew and Sears department store approached the Honda team to ask if it could sell the smaller bikes. The sales team reported back to head office and advised that instead of launching the larger bikes, the Super Cub should be the focus of Honda's debut in the US. Instead of dismissing the underlings, the managers took notice and agreed to go with the advice of the sales team. The result for Honda was phenomenal success in the US market. In Peter Senge's model, Honda is an example of how "every level of an organization should feel included and valued."

> There is no organizational learning without individual learning.
> **Chris Argyris, Donald Schön**

Questioning precedents

In essence, Senge's "learning organization" draws on earlier ideas, including those of Harvard's Chris Argyris. In 1977 Argyris published his theory of "double loop learning," showing that companies and their employees can assess and modify underlying ways of thinking to improve their capacity to learn and perform effectively. The following year

The Honda Super Cub became enormously successful in the US, thanks to managers who listened to their sales staff and broke away from the standard "macho biker" approach.


BELIEFS
ACTIVITIES OR TASKS
RESULTS
Single-loop learning
Results show what needs to be fixed or improved.
Double-loop learning
Results also reveal the bigger picture: the culture of the organization—the values and assumptions that govern behavior.

Organizational learning involves both single-loop learning, where errors are identified and corrected, and double-loop learning, in which the assumptions that underlie specific actions are questioned and improved.

Argyris joined forces with MIT professor Donald Schön to write the highly influential book *Organizational Learning: A Theory of Action Perspective*, which explored theories such as double-loop learning.

Going further back, the first scientific studies of learning within an organization were conducted in the mid-20th century. Two theories in particular emerged to dominate thinking in this area. The first, from Yale professor Charles Lindblom in 1959, was that action taken in organizations is based on historical precedent rather than on anticipating the future. The second was set out by Richard Cyert and James March, who in 1963 published their observation that behavior in organizations is based on routines: the procedures, conventions, or technologies through which companies operate. These perceived negatives became the focus of scholars such as Argyris and Senge. Interest in the concept of the learning organization grew in the 1990s, as business conditions became more uncertain and companies more dependent on technology.

In 1993 management innovation expert Mark Dodgson, then senior fellow at the Science Policy Unit of the University of Sussex, UK, linked economic uncertainty and rapid technological change to an increased need for learning at all levels in a company, citing the view of psychologists that learning is the highest form of adaptation. Dodgson, like other scholars, made a distinction between "organizational learning"—when organizations learn a lesson from a particular event—and "the learning organization," which embraces a continual process of education and implements strategies to initiate that process. In Senge's opinion, organizations focused on continued learning will gain a competitive advantage in the marketplace. ■

Peter Senge

A world-renowned expert on management and organizational learning, Peter Senge was born in Stanford, CA, in 1947 and studied aerospace engineering at Stanford University. He went on to obtain an MA in social systems and a PhD in management at MIT, and is now a senior lecturer at MIT's Sloan School of Management. He is also the founding chair of the global Society for Organizational Learning (SoL).

Senge pioneered the concept of "the learning organization"—an organization structured in a way that is conducive to new ideas, reflection, and engaging its employees. As he said on one occasion, a learning organization "is continually expanding its capacity to create its future."

In 1999, the *Journal of Business Strategy* named Peter Senge a "Strategist of the Century"—one of the 24 people who had had the greatest influence on business strategy in the 20th century.

Key works

1990 *The Fifth Discipline*
1999 *The Dance of Change*



THE FUTURE OF BUSINESS IS SELLING LESS OF MORE

THE LONG TAIL

IN CONTEXT

FOCUS
Internet business

KEY DATES

1838 French mathematician Antoine Augustin Cournot produces a graph to represent supply and demand.

1890 British economist Alfred Marshall introduces the concept of demand curves in his book *Principles of Economics*.

20th century Most companies sell a limited number of goods, with the bulk of sales and profits coming from their top-selling items.

1990s The introduction of the Internet proves to be a disruptive technology that changes economic and social traditions.

2004 Chris Anderson coins the term “Long Tail” to describe the concept that a larger proportion of sales is likely to come from the tail, rather than the head, of the demand curve.



Today, companies are **no longer constrained** by physical space or costs of reaching their market.

They can now **offer a large number of niche products** to many individual customers.

Consumers have increasing choice and want to express their **individuality**...

...by buying **niche items from online sellers**.

The future of business is selling less of more.

The “Long Tail” theory challenges basic principles of economics. In the past, successful businesses often sold high volumes of a limited number of products. Now, according to author Chris Anderson, the future of business is in selling less of more—low volumes of an increasingly large number of products.

A primary factor in today’s global economy is the Internet, which is shifting the focus from mainstream products and markets—represented by the “head” of the demand curve—toward a large number of niche or low-volume products and markets, as seen in the “tail” of the curve. A conventional demand curve is drawn with price on the

See also: Beating the odds at start-up 20–21 ▪ Gaining an edge 32–39 ▪ The weightless start-up 62–63 ▪ Thinking outside the box 88–89 ▪ Small is beautiful 172–77 ▪ M-commerce 276–77 ▪ Benefitting from "big data" 316–17

vertical axis, and quantity on the horizontal axis, and demonstrates that people buy more as the price falls. Anderson represents sales on the vertical axis and the number of products on the horizontal axis, showing that growth in many industries will come from the niche end of demand—the Long Tail.

Removing barriers

Supply was once constrained by factors such as cost of production, physical space for storage, and cost of distribution. Digital processing, online ordering, and electronic distribution have removed many of these barriers. Selling smaller numbers of a greater range of items can result in higher overall sales and profit than selling common items.

Books, music, and movies are classic examples of the Long Tail theory. A traditional bookstore can only stock books that are likely to sell. Amazon, however, can list every book, even though some may never be sold. Less popular titles that are not stored in its vast warehouses can be shipped direct from a publisher to meet individual demand. Combined sales of one-of-a-kind books may be larger than that of bestsellers, and so may equal more profit. Similarly, iTunes can offer a longer list of music than any physical store, and Netflix can stream almost any film into your living room. When offered almost limitless choice, consumers exert their preferences and spend money.

Asia is a large and growing market, but it is fragmented by many different cultures. Individual countries offer numerous niche opportunities for companies that can tailor products and services by language and ethnicity, rather than offering to the mass market. Start-ups are recognizing the Long Tail benefits and using the region's diversity to their advantage. One example is Brandtology, an online company that analyzes social media and online chat, in local languages, for clients in Singapore and Hong Kong. Native speakers of languages such as Mandarin, Japanese, and Korean offer social-media analysis to provide localized insights and interpretation of key issues within a particular culture. ■



The Long Tail is based on a representation of a demand curve of the future marketplace (sales are shown vertically, products horizontally). Author Chris Anderson suggests that overall sales of niche products at the thin "tail" of the curve may be greater than more popular products at the "head."

Chris Anderson



Author and entrepreneur Chris Anderson was born in London in 1961 and moved with his family to the US at five. He studied physics at George Washington University, then quantum mechanics and science journalism at the University of California, Berkeley; he later was a researcher at Los Alamos National Laboratory. After working on two leading scientific journals, *Nature* and *Science*, he joined *The Economist*, holding various positions (in London, Hong Kong, and New York), from technology editor to US business editor. Chris Anderson joined *Wired* magazine in 2001, where he was editor-in-chief until 2012. He currently lives in Berkeley, California, and is the CEO of 3D Robotics, a drone manufacturing company.

Key works

2004 "The Long Tail" (published in *Wired* magazine)
2006 *The Long Tail: Why the Future of Business is Selling Less of More*
2012 *Makers: The New Industrial Revolution*

TO BE AN OPTIMIST… HAVE A CONTINGENCY PLAN FOR WHEN ALL HELL BREAKS LOOSE

CONTINGENCY PLANNING

IN CONTEXT

FOCUS
Operational risk

KEY DATES
1947–1991 Governments and multinational businesses develop contingency plans for potential nuclear attack during the Cold War.

Late 1990s Countries around the world put contingency plans in place for the Y2K or "millennium bug"—an anticipated computer failure due to the millennial date change (from 1999 to 2000).

2010 A lack of contingency planning leads to closure of northern European air space for the first time, following the eruption of a volcano in Iceland. Businesses lose revenue due to the transportation restrictions.

2012 Due to the ongoing financial crisis, businesses around the world draw up contingency plans for the breakup of the Eurozone.

In business, things rarely go as planned. Companies have to prepare for sudden changes to markets or the environment to ensure that day-to-day business can continue "when all hell breaks loose," as US professor Randy Pausch put it.

Contingency planning sets a course of action to deal with a crisis, whether this is industrial (such as the financial collapse of a key supplier), human, natural, or technical in nature. It requires identifying possible disasters, assessing the likelihood of occurrence, and developing a course of action to minimize the impact. Having a plan enables a company to manage the crisis and recover quickly.

Identify key tasks

A contingency plan has to be based on critical business activities. A utility company that relies on a call-center team to manage customer inquiries should identify alternative premises in case of flood. A marketing company planning for the same incident may need to allow staff to work remotely.

> He who fails to plan is planning to fail.
> **Winston Churchill**
> **UK former Prime Minister (1874–1965)**

In 2011, a devastating earthquake struck Japan's east coast, followed minutes later by a large tsunami. The Japanese government's contingency plans for earthquakes—from earthquake-resistant buildings to an early-warning system and rapid-response coordination—saved countless lives. Many companies, such as NEC, were able to restore operations within minutes thanks to their prepared emergency plans. Even natural disasters as large as earthquakes can be managed with good contingency planning. ■

See also: Managing risk 40–41 ▪ Learning from failure 164–65 ▪ Avoiding complacency 194–201 ▪ Scenario planning 211 ▪ Coping with chaos 220–21

PLANS ARE USELESS, BUT PLANNING IS INDISPENSABLE

SCENARIO PLANNING

IN CONTEXT

FOCUS
Business planning

KEY DATES

Early 19th century Prussian military strategist Carl von Clausewitz formulates the principles of strategic planning.

1940s The US Air Force considers opponents' possible actions in order to prepare alternative strategies.

1950s US futurist and military strategist Herman Kahn encourages governments and individuals to "think the unthinkable" by imagining possible future scenarios.

1967 French philosopher Bertrand de Jouvenel coins the term *futurible* to mean "a fan of possible futures."

21st century Companies and governments use scenario planning for wide-ranging issues including food, water, and energy supply, and population growth.

In addition to contingency planning, which involves preparing for sudden disaster, companies also need to prepare for the many alternative futures they face. This is known as scenario planning. It has its roots in military planning, and companies start the process by asking: "what if…?"

What is likely to happen in the next two, five, or ten years? Companies have to consider local, national, and international events, and must try to identify underlying trends. They have to determine the probability of future scenarios, how they might be affected, and how they can prepare to mitigate the effects, or even to reap the benefits. Scenario planning does not remove uncertainty, but it can help a company adapt to change.

Prepared for change

Oil company Royal Dutch Shell has used scenario planning for nearly half a century. Its early work was based on intuition, but it has now developed sophisticated techniques to create scenarios, which it shares publicly. However, it never comments on the scenarios it discloses, since this might guide other companies' or governments' decisions.

Shell's scenario planning allowed it to minimize the impact of an oil embargo on Western countries in October 1973. Within weeks, the price of crude oil had soared and stock markets tumbled. Although Shell was hit by these events, it had already begun to diversify into other energy sources, allowing it to recover more quickly than competitors. ■

During the OPEC oil embargo of 1973, Shell's scenario planning meant it had already decided what it would do in the case of price hikes, allowing its executives to act fast and effectively.

See also: Managing risk 40–41 ▪ Learning from failure 164–65 ▪ Avoiding complacency 194–201 ▪ Contingency planning 210 ▪ Coping with chaos 220–21

THE STRONGEST COMPETITIVE FORCES DETERMINE THE PROFITABILITY OF AN INDUSTRY

PORTER’S FIVE FORCES

IN CONTEXT

FOCUS
Competitive strategy

KEY DATES
1921 US economist and statistician Harold Hotelling says that as long as there are profits to be had in a market, more and more vendors will arrive to serve it, until it reaches saturation point.

1979 Michael Porter’s “How Competitive Forces Shape Strategy” is published in *Harvard Business Review*.

2005 W. Chan Kim and Renée Mauborgne publish *Blue Ocean Strategy*, suggesting that companies should aim for uncontested markets rather than compete with each other in existing markets.

2008 Michael Porter writes *The Five Competitive Forces That Shape Strategy*.

In order to survive, companies have to understand and respond to competition. So it is natural to look at immediate competitors and established rivals to develop a strategy. However, this can restrict thinking, define competition too narrowly, and ignore other strategic forces. In the 1970s, economist and strategist Michael Porter changed people’s thinking on strategy.

Porter’s 1979 article “How Competitive Forces Shape Strategy” showed that awareness of wider competitive forces—those beyond the obvious competing companies—can help an organization understand the structure of its

See also: Study the competition 24–27 ▪ Gaining an edge 32–39 ▪ Leading the market 166–69 ▪ Porter's generic strategies 178–83 ▪ Good and bad strategy 184–85 ▪ The value chain 216–17

The **profitability of an industry** is shaped by five competitive forces...

...the bargaining power of **suppliers**.

...the bargaining power of **buyers**.

...**rivalry** among existing competitors.

...the threat of **new entrants**.

...the threat of **substitute** products or services.

The strongest competitive force—which varies according to the industry—determines the overall profitability of the industry.

industry and develop a position that is more profitable and less vulnerable to attack. According to Porter, there are five competitive forces that collectively define an industry's structure, shape the nature of competitive interaction within an industry, and ultimately determine profitability. Now referred to as Porter's Five Forces, this model places existing competitors at the center, surrounded by four other forces: customers, suppliers, potential entrants, and substitute products.

Using Porter's model

Porter used commercial aviation as an example to explain the model in action, because the strength of all five forces makes the airline business one of the least profitable industries of all. At the center are established rivals (such as Qatar Airways, Virgin, and Qantas), who all compete intensely on price. Customers can search easily for the best deal. Suppliers—in this case aircraft and engine manufacturers and unionized labor forces—take the lion's share of profits. New players enter the industry on a regular basis. Substitutes are available in other forms of transportation, such as trains, buses, and cars.

Where the forces are much weaker—for example in the software, soft drinks, and toiletries industries—companies can make a bigger profit. In all industries, profit can be affected by weather or cyclical change in the short term, but in the medium and long term, it is the structure of the industry that drives competition and profitability. Porter is adamant that other factors—such as the type of product or service, the maturity of the market, regulation, or level of technical complexity—are not defining factors for profitability.

The force of "rivalry"

Of the five forces, rivalry among existing competitors is the major determinant of competitiveness and profitability within an industry. In a very competitive industry, market share is tough to win and so profits are harder to make. Intense competitor rivalry occurs when there are many competitors, growth in the industry is slow, products are not differentiated and can be easily substituted, competitors are of equal size, customer loyalty is low, and it is difficult and costly to exit the industry.

The hotel business is just such an industry. In a city such as New York, there are many hotels. Guest numbers are relatively static, so »

> The first one gets the oyster, the second gets the shell.
> **Andrew Carnegie**
> **US industrialist (1835–1919)**

> Industry structure, as manifested in the strength of the five competitive forces, determines the industry's long-run profit potential.
> **Michael Porter**

similar growth is slow; within a specific star-rating the hotels are all fairly similar, as are the sizes of the big hotel chains. Customers can choose to go to any hotel, and have good access to prices. Exit from the industry is difficult because of the upfront investment. Many large hotel groups have introduced loyalty programs as part of their strategy to differentiate their brand.

Substitutes

The most significant of the five forces is not always the most obvious one. For example, even though rivalry is often fierce in commodity industries, that may not be the factor that ultimately limits profitability. The "threat of substitutes" force is surprisingly important here—buyers in these markets can easily find substitute raw materials or products that have attractive prices or are higher quality. What's more, buyers can switch from one product or service to another with little cost. For example, it costs relatively little for a consumer to switch from tea to coffee, unlike switching from traveling by bicycle to car.

In some industries, companies try to limit the threat of potential substitutes by ensuring wider product accessibility. For example, soft-drink manufacturers have achieved this by introducing branded vending machines, so competitors are unable to offer their products at that particular place.

Buyer power

Buyers can demand lower prices or higher product quality from producers when their bargaining power is strong. Both scenarios result in lower profits for producers, because lower prices mean lower revenues, and higher-quality products usually incur higher production costs. Buyers exert strong bargaining power when there are few of them; they buy in large quantities; they are price sensitive; they control distribution to the final customer; there are many subsititutes; and switching to another supplier can be done at low cost. Buyers may also be able to produce the product themselves—so may use this as a threat.

Buyers for big supermarkets have huge bargaining power in the food and drink industry. Fresh milk is often at the heart of supermarket price wars, because the big chains have significant buying power over suppliers. UK farmers have claimed that they are so pressured to reduce prices that they often make a loss on each bottle of milk produced.

Supplier power

When the bargaining power of suppliers is strong, it allows them to sell higher priced or lower quality raw materials. This directly affects the profits of the company that is buying, because it has to pay more for its raw materials. Suppliers have strong bargaining power when there are few of them (but many buyers); they hold scarce resources; the cost of switching raw materials is high; and when there are few substitute raw materials or suppliers. Their power is increased if they are large and can threaten to step in and produce themselves.

Oil is an example of a scarce resource that is controlled by a few countries. OPEC (Organization of the Petroleum Exporting Countries) represented the political power of oil-exporting countries in 1973 when it placed an oil embargo on the US. OPEC's action disrupted supply and forced up the price of oil four-fold.

New entrants

If an industry is profitable and there are few barriers to entry, Porter says that competition will increase and profits will fall. Typically, existing organizations try to create ways to deter new entrants. The threat of new entrants is high when the cost of entering the market is low; there is little government regulation; customer loyalty is low; existing businesses can do little to retaliate; and economies of scale can be easily achieved. Risk is increased if existing companies have not established brand reputation and do not possess patents, and when

Buyer power is high in the food and beverage industry because consumers can easily find a substitute that may be cheaper or differentiated, such as by offering increased nutritional benefits.

The hotel industry is characterized by intense competitor rivalry. Some hotel chains have introduced loyalty schemes to try to increase customer preference and encourage return visits.

products are nearly identical. An example of a market with a low threat of new entrants is the software market for personal computers. Microsoft came to dominate the market with its Windows 95 operating system. New entrants found it hard to break in because programs such as Excel, PowerPoint, and Word are universally used.

Choosing a position

Porter used the US heavy-truck manufacturer Paccar to illustrate the principles of choosing how to position a company within a given industry structure. In a crowded market, Paccar wanted to find a space where competitive forces were weak, and where it could avoid buyer power and price-based rivalry.

In the heavy-truck industry, where large fleet buyers dominate, it is hard to create a niche based on differentiation. Paccar, based in Washington state, chose to focus on one group of customers: owner-operators. Personal pride in their own trucks and the fact that they were economically dependent on their vehicles made them less price-sensitive as purchasers. Paccar therefore decided to invest in developing an array of features with owner-operators in mind, such as luxurious sleeper cabins, leather seats, noise-insulated cabins, and sleek exterior styling. They offered thousands of options for owners to put their personal signature on their trucks, by simply inputting them on computers at network dealers. They also offered roadside assistance and fuel-efficient, aerodynamic designs. As a result, Paccar has been profitable for more than 68 years in succession, and delivers better-than-average returns.

No matter how different industries appear on the surface, Porter's model offers any company a way of assessing profitability through analyzing five easily calculated, competitive forces. In revealing an industry's underlying structure, Porter's model simplifies a mass of information, providing managers with a clear process for making sense of industry data and using it to form effective strategy. ■

Michael Porter

Born in 1947 in Michigan, Michael E. Porter was the son of a US Army officer, and lived in different places around the world as a child. Porter served in the US Army Reserve following graduation. He received a BSE with high honors in aerospace and mechanical engineering from Princeton University, in 1969, an MBA in 1971 from Harvard Business School, and a PhD in business economics from Harvard University in 1973. The author of 18 books and more than 125 articles in the fields of competitiveness and management, Porter's academic studies encompass competitiveness in national, regional, social, and health-care arenas. He has served as an advisor to governments, corporations, nonprofit organizations, and academics across the globe.

Key works

1980 *Competitive Strategy*
1985 *Competitive Advantage*
1990 *The Competitive Advantage of Nations*

> Defending against the competitive forces and shaping them in a company's favor are crucial to strategy.
> **Michael Porter**

IF YOU DON'T HAVE A COMPETITIVE ADVANTAGE, DON'T COMPETE

THE VALUE CHAIN

IN CONTEXT

FOCUS
Competitive Advantage

KEY DATES
1933 US economist Edward Chamberlin introduces the concept of product differentiation in *Theory of Monopolistic Competition*.

1970s The idea of competitive advantage takes hold as Japanese companies begin to outsell US and European rivals. This is later attributed to superior management.

1979 US marketing consultants Al Ries and Jack Trout write *Positioning: the Battle for Your Mind*, outlining how companies should build a strategy around their competitors' weaknesses.

1985 Michael Porter introduces his theories of competitive advantage and the value chain in *Competitive Advantage: Creating and Sustaining Superior Performance*.

The interconnected activities through which a company delivers products or services can be viewed as a **"value chain."**

The chain consists of **primary and secondary value activities**.

Primary value activities include inbound logistics, manufacturing, outbound logistics, marketing and sales, and after-sales service.

Secondary value activities include procurement, HR, technology, and infrastructure.

Through analysis of its value chain, a company can identify where to achieve **cost or differentiation advantage** on its products.

The goal of every company is to create and sustain a competitive advantage so that it can sell more products and generate higher profits than its rivals. As Jack Welch, CEO of US multinational General Electric and celebrated business guru, advised: "If you don't have a competitive advantage, don't compete."

US professor Michael Porter's "generic strategies" consist of two types of competitive advantage: cost advantage and differentiation

See also: Leading the market 166–69 ▪ Porter's generic strategies 178–83 ▪ Good and bad strategy 184–85 ▪ Porter's five forces 212–15

advantage. Porter identified a set of activities that businesses can use to better understand how to achieve these forms of differentiation. These interrelated activities—dubbed the "value chain" by Porter—describe the flow of a product from its initial supply to the final customer.

A company can add value to the product at each stage of the chain, through product-related activities—its inbound logistics (supply of parts or materials), manufacturing, and after-sales service—and market-related activities: outbound logistics (the delivery of products to the end user), and marketing and selling the product.

Gaining the advantage

To achieve competitive advantage, a company cannot focus on one activity alone, but needs to consider each of the activities in the chain. For example, Mercedes-Benz pursues a differentiation strategy, first through producing a high-end product, but also through providing outstanding after-sales service. Analyzing the value chain can also help companies to identify what areas of their business might be suitable for outsourcing, which can help the company to achieve a cost advantage.

Primary value-chain activities in a company are supported by a series of secondary activities, which can also be used to achieve competitive advantage. These activities vary by industry, but typically include: purchasing (procurement); human resource (HR) management; technology development, including research and development (R&D); and infrastructure functions, such as finance and legal. Although support activities may be viewed as "overheads," secondary value can be generated, for example, through better use of technology.

> “When you've got only single-digit market share—and you're competing with the big boys—you either differentiate or die.”
>
> **Michael Dell**
>
> **US founder of Dell Computers (1965–)**

In addition to their horizontal activities, companies operate in a "value system" of vertical activities, such as a manufacturer who buys parts from suppliers and outsources its distribution. Competitive advantage relies not only on the company's value chain, but on the value system of which it is a part.

Reinventing value

Porter's theories on competitive advantage were highly influential, and have been built upon by other business theorists. Management scholars Richard Norman and Rafael Ramirez argued in 1993 that the market complexity of the 1990s required companies to "reinvent" the notion of value beyond the linear thinking of the "chain." In 1995, US executives Jeffrey Rayport and John Sviokla drew parallels with the emerging world of the Internet, suggesting that value could be added to online activities and products in a "virtual" value chain. ■

Red, yellow, or purple?

Fashion retailer Benetton, launched by the Benetton family in Italy in the 1960s, pursues a differentiation strategy with its bold brand image. To achieve this, the company has focused on every aspect of its value chain, from supply to satisfying the latest consumer fashions. To ensure Benetton garments are up-to-the-minute, the company manufactures many of its clothes in gray, then dyes them to meet the demand for whatever colors are in fashion. Although this is costly in production, it minimizes stock, reduces wastage, and enables the company to respond quickly to changing consumer tastes. Benetton stores are run by agents, and garments are shipped directly to the stores and immediately placed on the shelves. This creates a strong value system, keeps costs lower, and allows each part of the chain to absorb fluctuations in demand. Benetton has more than 6,500 stores in more than 120 countries, and its turnover exceeds $3.2 (€2) billion a year.



Benetton's value chain boosts its differentiation advantage. Clothes can be dyed in fashionable colors to match customer taste.

IF YOU DON'T KNOW WHERE YOU ARE, A MAP WON'T HELP

THE CAPABILITY MATURITY MODEL

IN CONTEXT

FOCUS
Business processes

KEY DATES

1899 US engineer and management consultant Henry Gantt develops the Gantt chart to illustrate a project schedule.

1970s Data-flow diagrams are developed to allow structured analysis of how data moves from one process to another.

1979 Philip B. Crosby develops a quality-management maturity grid in his book *Quality is Free*.

1988 The Capability Maturity Model (CMM) is described by Watts S. Humphrey in an article published in the journal *IEEE Software*.

2003 In *Business Process Management is a Team Sport*, Andrew Spanyi claims that strategy should drive business process design, which, in turn, should drive organizational design.

In level 1 of the Capability Maturity Model, **initial processes are ad hoc** and poorly controlled.

↓

In level 2, processes **start to be applied to projects** and are repeatable.

↓

In level 3, processes become **defined and can be proactively implemented**.

↓

In level 4, processes are measurable and **can be managed**.

↓

By the time level 5 is reached, processes can be **optimized through careful monitoring**.

Business processes are a series of actions taken to achieve an outcome. The objective might be to produce a product, to pay an invoice, or to serve a customer, for example. Adam Smith was one of the first people to describe business processes, when he dissected the many manufacturing processes used in an 18th-century pin factory. From describing the different actions, he developed the idea of division of labor, where work can be divided into a set of simple tasks performed by specialized workers, in sequence.

Continuous improvement

The sequence of steps in a process can often be visualized as a flow chart. As Watts Humphrey, inventor of the capability maturity model (CMM), pointed out, it is always "good to know where you are" in the process. Humphrey developed the idea that continuous process improvement is based on many small evolutionary steps, rather than large, revolutionary innovations. His CMM provides a framework for organizing these evolutionary steps into five levels of development, each of which prepares the way for the next. The CMM was developed

See also: Keep evolving business practice 48–51 ▪ Reinventing and adapting 52–57 ▪ Simplify processes 296–99 ▪ Kaizen 302–09 ▪ Critical path analysis 328–29 ▪ Benchmarking 330–31

Adam Smith observed workers making pins in a pin factory and realized that if the process were split into separate, specialized steps, productivity would increase by 240 to 4,800 times.

with funding from the US Air Force, and was used as a model for the military to evaluate software subcontractors. The model's original goal was to improve software-development processes, but it is now applied as a general model of the maturity of processes. It is often used in evaluating IT service management, for example, or more widely across organizational systems.

The CMM describes five levels of increasing maturity through which an organization or team manages its processes: in the first level, work is conducted in a chaotic and ill-defined way; in the second level, processes are put in place and adhered to with some discipline, and previous successes can be repeated; in the third level, processes are defined, standardized, and can be proactively implemented; in the fourth level, they are managed and monitored; and in the fifth level, they undergo regular improvement through monitoring and feedback.

Comparing industries

The CMM can be used to compare different organizations in similar industries. For example, two companies could be compared on the basis of their software-development processes. Increasingly, IT projects, which involve complex software development and new system implementation, can impact a company's operation and profitability, as they affect all of the company's departments.

The strength of CMM is its effective measurement of the standardization of an organization's processes. This is why the model moved from being used to assess software development, to applications in project management, risk management, personnel management, and systems engineering. It provides a starting point for managers looking to improve a company's processes and a framework for prioritizing actions. It also offers a way of defining what "improvement" might really mean. ■

> “The whole idea was to motivate people to think about how they're working, and how to improve it.”
> **Watts S. Humphrey**

Watts S. Humphrey

Software engineer Watts S. Humphrey, known as the "father of software quality," was born in 1927 in Michigan, US. He credited his father with his approach to problem solving. After high school, where he struggled with dyslexia, he joined the US Navy to serve during World War II.

Humphrey then studied for a BSc and MSc in physics before completing an MBA in manufacturing at the University of Chicago Graduate School of Business. After graduating, he joined the Software Engineering Institute (SEI) at Carnegie Mellon University, Pennsylvania, where he founded the Software Process Program, which focused on understanding and managing the software engineering process. This work resulted in the development of the Capability Maturity Model (CMM), for which he is best known, and inspired the subsequent development of the Personal Software Process (PSP) and the Team Software Process (TSP), which was later adopted by IT companies Adobe, Intuit, and Oracle. Humphrey was awarded a National Medal of Technology in 2003 for his work in software engineering. With his wife, Barbara, he had seven children, and died at his home in Florida on October 28, 2010, at 83.

Key works

1995 *A Discipline for Software Engineering*
1999 *Introduction to the Team Software Process*
2005 *PSP, A Self-Improvement Process for Software Engineers*

CHAOS BRINGS UNEASINESS, BUT IT ALSO ALLOWS FOR CREATIVITY AND GROWTH

COPING WITH CHAOS

IN CONTEXT

FOCUS
Change and uncertainty

KEY DATES
1992 M. Mitchell Waldrop writes *Complexity*, which explains the theory of the science of complex systems.

1997 Researcher Shona Brown says that the edge of chaos has a structure that allows companies to be malleable enough to change but not fall apart.

1999 In *Surfing the Edge of Chaos*, Richard Pascale, Mark Millemann, and Linda Gioja say a too-rigid management system can have nothing original or innovative emerge from it.

2000 The dot-com bubble bursts, causing turmoil in financial markets.

September 2001 The 9/11 terror attacks in the US have far-reaching financial and business impacts around the world.

The top-down, hierarchical organization of businesses dates back to the industrial revolution, when management was all about control. Today's companies need a radically different approach.

The first decade of the 21st century saw many disruptive events across the world. These, combined with accelerated technological developments, the rise of developing nations, and a changing world order, make living with uncertainty a reality for business today. This means that companies now need a flatter structure, incorporating flexibility instead of direct control. Rather than being overwhelmed by chaos, chaos can be managed and even embraced. US politician Tom Barrett acknowedged the value of working in an unstable world, noting that "chaos brings uneasiness, but it also allows for creativity and growth."



Chaos theory proposes that complex systems are highly sensitive to initial conditions. A butterfly's flapping wings in Japan might start a chain of reactions that leads to a hurricane in the US.

Managing chaos

Scientific chaos theory, which investigates the patterns in complex systems such as the weather, can be related to organizations. Effective leadership, clear vision, open communication, and strong values are necessary to deal with such complexity. Leaders need to set clear boundaries, then allow individuals and teams enough space to self-organize, self-regulate, and make their own decisions. Creativity and growth are enabled because employees have a higher level of responsibility and accountability for their work, as well as a bigger investment in the outcome.

A company also has to revisit its strategy continually, with the focus on delivering increased value to the customer, to ensure that it remains relevant in the changing external environment. A more flexible company helps to ensure that staff is involved and can adapt

See also: Managing risk 40–41 ▪ Reinventing and adapting 52–57 ▪ Creativity and invention 72–73 ▪ Avoiding complacency 194–201


Economic, social, and political events **create chaos**.
New technology **adds uncertainty**.
Rigid control no longer works—businesses need to be **flexible**.
If employees are given more information and involvement, they become **more creative**, helping the company to be flexible and change.
Chaos brings uneasiness, but it also allows for creativity and growth.

swiftly to change. Such companies collaborate more readily with external partners, rather than merely transacting with them, to encourage adaptability and shared learning.

Creativity from chaos

A potential source of chaos is internal change and reorganization of a company. Involving and engaging the employees is the answer to managing this. In the most complex financial services integration ever to occur in Europe, Halifax Bank of Scotland (HBOS) was acquired by Lloyds TSB following the financial crisis of 2008. External chaos (unprecedented economic turbulence) was mirrored by internal chaos—6,000 branches and 30 million customers had to be brought together to form the biggest retail bank in the UK. The new company had to create one new identity, one new way of doing things, and streamline its IT systems and differing organizational cultures. It also needed ways of communicating positively to customers.

But the biggest challenge of all was common to many situations of business chaos—motivating employees who were harassed by customers and worried about their own jobs. Through constant communication (including daily team briefings on internal changes), workshops on team problem solving and vision building, and measures for gathering ideas from staff and customers, the combined companies showed that chaos can not only be managed, but may be a rich source of growth for a business in flux. ■

Thriving on chaos

Thriving on Chaos, written by US business expert Tom Peters, was published on "Black Monday" (October 19, 1987), when stock markets around the world crashed. His timing could not have been better. In the book Peters laid out a future of change, stating that everything known "for sure" about management would be challenged—and that 100-year-old traditions of mass production and mass markets would be threatened. His forecast was correct. What had been a fairly predictable business environment disappeared; organizations and managers had to embrace change, or face collapse.

Peters correctly predicted that the business winners of the future would deal proactively with chaos, seeing it as a source of market advantage. Successful companies would be those who could create and add quality and value continually to their products and services in response to the ever-shifting desires of their customers. He described this as "a revolution."

> There is no sense in pining for the past—the stability we took for granted for so long will never return.
> **Tom Peters**



ALWAYS DO WHAT IS RIGHT. IT WILL GRATIFY HALF OF MANKIND AND ASTONISH THE OTHER

MORALITY IN BUSINESS

IN CONTEXT

FOCUS
Business ethics

BEFORE
1265 Italian philosopher and theologian Thomas Aquinas states: “no man should sell a thing to another man for more than it is worth.”

1807 The UK and US outlaw the Atlantic slave trade.

1948 The United Nations (UN) adopts the Universal Declaration of Human Rights.

1970 US economist Milton Friedman claims: “the social responsibility of business is to increase its profits.”

1970s The term “business ethics” comes into common use in the US.

2011 The UN Human Rights Council endorses *Guiding Principles for Business and Human Rights*, which sets global standards for human rights and business activity.

The US author Mark Twain said we should “always do what is right,” but this has not always been the case in business. High-profile scandals such as Enron and Lehman Brothers in the 2000s have led to a collapse of public trust in companies.

Individuals are often tempted to use immoral means to further their aims. J. D. Rockefeller controlled the US oil industry in the 19th century because of underhanded methods to put competitors out of business. Today, some corporate companies are, in essence, a collection of individuals who want their company to get ahead of the competition, but are also alert to opportunities for personal gain. They may even go as far as illegal phone hacking or price collusion. For example, in 2013 Dow Chemicals was ordered to pay $1.2 billion for price-fixing.

Executives may be tempted to break the law because of pressure from shareholders for results or for performance-related bonuses. Gains from share prices and the value of the business overall pose additional temptations. In the 1980s, for example, the price of Guinness shares was inflated to assist the company’s takeover bid for Distillers, a leading Scotch whisky company.

Businesses worldwide are under greater scrutiny to be ethical in their practices. In 2011–13 several multinational companies came under fire for shifting profits between countries, thereby avoiding large tax liabilities. Though not illegal, many regard it as immoral, and consumer perception can affect profit. ■

In 2013, several oil companies came under investigation by the EU antitrust authority for preventing other companies from entering the price assessment process, thereby distorting oil prices.

See also: Play by the rules 120–23 ▪ Profit before perks 124–25 ▪ Collusion 223 ▪ Creating an ethical culture 224–27

THERE IS NO SUCH THING AS A MINOR LAPSE IN INTEGRITY

COLLUSION

IN CONTEXT

FOCUS
Ethics of competition

KEY DATES

11th century Legislation in England outlaws monopolies and restrictive practices.

13th century King Wenceslaus II of Bohemia passes a law to prohibit iron-ore traders from working together to increase prices.

1790s After the French Revolution, agreements by members of the same trade to fix prices are declared void, unconstitutional, and "hostile to liberty."

1890s The Sherman Act in the US makes it illegal for large companies to cooperate with rivals to fix their outputs, prices, or market shares.

2000s The Treaty of Lisbon prohibits anticompetitive agreements, including price-fixing, in the European Union.

In a market economy, companies are in commercial competition with one another. It is illegal for them to "collude" to fix prices or make secret trade agreements. However, collusion and collaboration are close relatives, and sometimes companies argue that the way in which they "work together" does not constitute collusion. Rival companies have been known to "collaborate" in order to gain advantage over other competitors, or to increase profit. They might do this by sharing restricted information, limiting the supply of goods to influence the price, or fixing prices. Two airlines hit the media in 2007 when they were accused of price-fixing. Staff at British Airways had tipped off staff at competitor Virgin Atlantic over fuel surcharges. British Airways admitted to collusion, and was fined $195.5 (£121.5) million.

Accountability

Individuals in large organizations sometimes consider themselves infallible. In the mid-1990s, five businesses in the US, Korea, and Japan secretly colluded to raise the price of lysine (an ingredient in animal feed) above its average price in the international market. Within nine months the illegal cartel had raised prices by 70 percent. Gains for the companies and individuals would have been significant if they had not been caught. Several executives went to prison and US company, Archer Daniels paid the largest antitrust fine in US history. ■

> We have always known that heedless self-interest was bad morals; we now know that it is bad economics.
> **Franklin D. Roosevelt**
> **US former President (1882–45)**

See also: Play by the rules 120–23 ▪ Profit before perks 124–25 ▪ Morality in business 222 ▪ Creating an ethical culture 224–27

MAKE IT EASIER TO DO THE RIGHT THING AND MUCH HARDER TO DO THE WRONG THING

CREATING AN ETHICAL CULTURE



IN CONTEXT

FOCUS
Business ethics

KEY DATES
44 BCE Roman lawyer Marcus Tullius Cicero writes *De Officiis*, discussing ideals of public behavior.

1200s Italian philosopher and theologian Thomas Aquinas argues that price has a strong moral aspect.

Early 1900s US president Theodore Roosevelt declares that businesses should "act for the interests of the community as a whole."

1987 "Ethical Managers Make Their Own Rules," a *Harvard Business Review* article by Adrian Cadbury, highlights the conflict between ethical and commercial considerations, and the increasingly close scrutiny of corporate decisions.

The fundamental assertion of business is that it exists to make a profit. However, the way that companies make a profit has come under intense scrutiny, particularly in the global economy.

The first recorded reference to moral principles was Cicero's *De Officiis*, written in 44 BCE, which stated that "right is based, not upon men's opinions, but upon Nature." In the 13th century, the philosopher and theologian Thomas Aquinas defined the principle of natural law, saying that as a reflection of God's rational plan, our idea of what is naturally right is also rational: an action is ethical if it is judged to be rational, or reasonable. This is still

See also: Leading well 68–69 ▪ Effective leadership 78–79 ▪ Organizational culture 104–09 ▪ Avoid groupthink 114 ▪ Profit before perks 124–25 ▪ Morality in business 222 ▪ The appeal of ethics 268


The company's **leader demonstrates ethical behavior**.
The company **recruits new people for their values** as well as their skills.
The company **orients new people to its ethical culture**.
The company publishes and communicates its **code of conduct**.
The company **recognizes and rewards** ethical behavior.
A company must be proactive across its entire operation in order to make it easier to do the right thing and harder to do the wrong thing.

the basis for ethical conduct today. Aquinas also asserted the first principles for the marketplace, pointing out that the price set for a product is a moral issue.

A more moral world

The notion of what is acceptable in the business world today has changed radically from earlier centuries. Slave labor was the norm for cotton and sugar plantations in the US until the mid-19th century. At the same time, workers (including children) were exploited during the industrial revolution in Europe, being forced to work long hours, at low wages, in unhealthy conditions. A pioneer in showing that business could make a profit while pursuing an ethical path was Welsh social reformer Robert Owen, whose New Lanark Mill, near Glasgow, Scotland, became world famous for its moral rather than commercial values.

Today, companies have to consider every aspect of their operation—from sourcing ingredients to marketing policies—in order to be judged ethical by their consumers. Employment policies are very important. The Institute for Ethical Leadership, based in Canada, defines an ethical business as "a community of people working together in an environment of mutual respect, where they grow personally, feel fulfilled, contribute to a common good, and share in the personal, emotional, and financial rewards of a job well done." There is a shared understanding that success depends on a myriad of relationships—both internal and external—not all of which are under the organization's control, but which it can influence through the ethical way it operates.

An ethical business that employs people from diverse backgrounds starts by agreeing and documenting its own principles or standards, which are often termed the company's "charter" or "code of conduct." These standards become the reference point for decision making in the working environment, particularly when employees are faced with difficult decisions.

However, it takes more than a written pledge to ensure an ethical business. Organizations have to foster a culture in which it is far easier for people "to do the right thing and much harder to do the »

Stephen Covey

Born in Salt Lake City, Utah, in 1932, Dr. Stephen Covey was an internationally respected leadership authority, teacher, organizational consultant, and author. He grew up on a farm in Utah and was bound for an athletic career, but in his late teens he was struck by a degenerative disease that led him to require crutches while walking for several years. He studied business administration at the University of Utah, then spent two years as a Mormon missionary in Britain before earning an MBA at Harvard and then a PhD at Brigham Young University. In 1983 he opened the Covey Leadership Center in Provo, Utah, which later became the Franklin Covey Company. Covey died in 2012, at 79.

Key works

1989 *The 7 Habits of Highly Effective People*
1991 *Principle-Centered Leadership*

Fashion businesses use materials and labor from all around the world. Consumers increasingly demand transparency about goods and policies, so they can buy with a clear conscience.

wrong thing," according to US leadership expert Stephen Covey. Faced with daily decisions about the right way to behave, employees have to know what "doing the right thing" actually means. A company's policies covering everything from safety to accepting gifts from suppliers exist to ensure that people understand how they are expected to conduct business appropriately.

Driven from the top

Companies that prioritize an ethical culture often select employees for their values as much as their skills, and ensure that new employees are made aware of their role and responsibilities, and also how things are done in the organization. Such companies are eager to ensure that new staff both hears the company's values and sees them affirmed in the actions of people around them. Such a culture has to be driven from the top. US economist Milton Friedman famously said that the social responsibility of business is to increase its profits "subject to the limits of law" and "rules of the game" that ensure "open and free competition without deception or fraud." However, the 2007–08 financial crisis showed clearly that codes, laws, and regulations are not enough to maintain ethical business standards. Leaders with personal integrity are vital to enact and encourage ethical behavior throughout an organization. By espousing the company's principles at every opportunity and at every level, leaders can continually demonstrate their importance within organizational culture.

In *Principle-Centered Leadership*, Stephen Covey describes trust, respect, integrity, honesty, fairness, equity, justice, and compassion as the "laws of the universe," classing them as essential values for ethical leaders. Covey is best known for his book *The 7 Habits of Highly Effective People*, in which he proposed that ineffective people try to manage their time around priorities, whereas effective people lead their lives and manage their relationships according to principles. These natural laws and governing values are universally valid.

> We're pioneers and we want to show that this model works, that it can become self-sustaining.
>
> **Ali Hewson**
>
> **Irish ethical businesswoman (1961–)**

Ethical leadership

Typically, leaders in ethical organizations are not domineering. They are likely to have an open, engaging style and to be good listeners, able to tune in to issues across the business. The company they create will have a clear structure with well-defined roles and responsibilities, be transparent, with promotion based on merit, and a well-communicated strategy, so that employees know what they have to do and where they fit in.

Leaders with personal integrity are a powerful influence on others. Numerous studies have shown that good people can make bad decisions when acting in groups, particularly in stressful situations. To avoid the risk of unethical "groupthink," the CEO has to set the right tone for everyone in the organization. Effective governance is critical, and relies on good teamwork and communication between the board and the CEO. A board that has a defined structure and a healthy culture of debate will be more likely to recognize emerging problems and take timely, appropriate action.

This was not the case at Enron, a company that has become one of the most infamous examples of unethical leadership. The Enron Corporation started as a small gas-pipeline business in the US and grew to become the nation's seventh-largest publicly held corporation. CEO Jeffery Skilling actively cultivated a culture that would push limits; his mantra was "do it right, do it now, and do it better." But despite a clear set of values for employees to espouse, executives manipulated accounting rules and disguised enormous losses and liabilities. Enron collapsed in 2001; Skilling and chairman Ken Lay were tried together on 46 counts, including money laundering, bank fraud, insider trading, and conspiracy.

Doing the right thing

British fashion brand Ted Baker began life as a shirt specialist in Glasgow, Scotland, in 1988, and now has stores in the Americas, Europe, Asia, and the Middle East. The company is known for its irreverent designs, but in contrast to its styling, it strives to be an exemplar in the way it runs its business. To make this a reality rather than just a statement on its website, Ted Baker strives to ensure that environmental, social, and ethical matters are integral to its business operations, so that employees are always in tune with its high standards.

Ted Baker has set targets to continuously improve the overall sustainability of its collections, so employees know what they have to achieve. It is also committed to measuring and publishing its progress against sustainability targets and has a full-time "green guardian" to focus on improvement. The company also has a "Conscience Team," made up of people from across the organization, which is responsible for addressing social, environmental, and ethical issues.

Ethical companies often demonstrate ethical commitment by partnering with organizations that can help them to improve their standards. Ted Baker is a member of Made-by, a European not-for-profit organization that strives to improve social and environmental conditions in the fashion industry and to make sustainable fashion common practice. Any company partnering with Made-by must analyze the ethics of every aspect of operations, from the fibers used in products to factory conditions for workers. Companies can also inspire customers to act in a socially conscious way: some garments carry a symbol of a crossed-out trash can, encouraging consumers to recycle them.

Ethical business is also good business. Customers are attracted to companies they can feel good about, more talented staff is attracted and stays longer, and shareholders are shielded from the type of share-price falls that overtook Enron. ■

Ethical trading depends on more than internal business practices and culture: a company's materials, suppliers, and business partners must also be ethically sound. To aid transparency, some companies and organizations publish data on aspects of their business, such as production locations, energy mix, recycling levels, and diversity among employees.



SUCCES SELLING

MARKETING MANAGEMENT

SFUL

By definition, marketing is the field of management devoted to selling. It is the link between production and profit, providing the expertise for taking a product or service through the most appropriate channels to find the people most likely to buy it. To fulfil this goal, it is crucial to become adept at understanding the market. This means closely studying the behavior and lifestyle of the customer so that a product or service can be developed to be irresistible in every way, from the purpose, function, quality, and look of it, to the speed at which it is delivered, the places it is sold, its price, and the level of customer service support offered.

Knowing the customer

That is the theory. In practice, making your customers love you by always putting them first and fulfilling their needs and desires is the biggest challenge of marketing. Collecting data about the purchase history of customers is a starting point. Combined with analyzing any available demographic and lifestyle statistics, such data can be used to build a marketing model—essentially a mathematical formula that indicates potential purchase rates for a given set of variables. Naturally there are dangers inherent in trying to predict the future using this type of forecasting. The marketer must also be aware of changing tastes, technology, politics, and economic conditions, so that the business can adapt quickly, avoiding what management scholar Theodore Levitt famously called "marketing myopia." For example, as consumers have become increasingly reliant on mobile phones and tablets, businesses with foresight have developed mobile-commerce channels and reaped the benefits.

In the quest to anticipate customer needs and wants, some of the most progressive companies gather data and examine it on a daily basis so that key elements of the "marketing mix"—such as the product or service itself, the places where it is sold, its price, and any promotional offers—can be adjusted accordingly. Japanese camera company Konica Minolta, for example, uses specialized technology to monitor sales data, competitor activity, and market trends in real time so that it can respond effectively.

> Marketing takes a day to learn. Unfortunately it takes a lifetime to master.
>
> **Philip Kotler**
>
> **US marketing expert** (1931–)

Marketing strategies

Arguably the product or service offered is the most critical component of the marketing mix. For most companies, each product or service in its product portfolio has its own cycle of growth, and can be managed to maximize profit by prioritizing the marketing spend. For example, for food group Mars, its best-selling namesake chocolate bar has been a long-standing source of profits, funding the corporation's expansion into other areas, such as ice cream and pet food.

To help decisions about diversifying into such new markets, companies can use a diagrammatic tool such as Ansoff's Matrix, which plots existing and potential products or services according to the risk factors involved. If a business decides to develop and



market something new, how it presents the offering and gets the message to consumers is an important consideration. In planning a launch, another valuable tool, the AIDA Model, provides clear-cut criteria for defining the features of any new product or service: how it grabs consumers' attention, holds their interest, generates desire, and is perceived to be attractive.

Concurrent with developing a specific product or service for a particular market, creating a brand is equally important. The goal should be to make the brand synonymous with a set of unique product qualities. In the words of marketing expert Seth Godin: "A brand is the set of expectations, memories, stories, and relationships that, taken together, account for a consumer's decision to choose one product or service over another. If the consumer ... doesn't pay a premium, make a selection, or spread the word, then no brand value exists for that consumer."

Promoting the product

Once the optimal product or service has been developed in conjunction with brand identity, there is the question of how to get the word out to potential customers. Promotions and incentives—such as special offers, sweepstakes, and price discounting—can be deployed in the short term to garner initial interest. They can be especially effective for product launches in areas where many rivals fight for shelf space, such as household cleaning and candy.

One of the oldest strategies for communicating with customers is word of mouth. In the age of social media, generating buzz about a new product or service increasingly relies on reaching specific groups through Facebook, Twitter, YouTube, and other online means, and encouraging them to spread the word. When a branded video goes viral, the potential global reach runs into tens of millions. If relatively low-cost communications methods like this are effective, it can lead marketers to ask, why advertise? But for long-term image building, and for reinforcing brand values, advertising still has a role to play. For example, a sustained advertising plan can take an audience from children to adults with recognizable slogans, jingles, and formats.

Staying on message

Businesses must carefully consider the messages that they send to customers and their rivals, since the marketplace can judge them harshly. Companies found to have acted dishonestly or conveyed partial truths about their eco-credentials can be accused of "greenwashing," and will find it hard to win back public opinion. In fact, no matter how appealing a company's sales proposition, consumers increasingly want the people they buy from to have a social conscience. For this reason, it is vital for management to consider the role of ethics within the organization, and to develop the company's code of behavior toward suppliers, employees, consumers, and the community. Although shareholders may see corporate responsibility as the least important commercial priority, it is now an integral part of the marketer's strategy for successful selling. ■

> Don't find customers for your products, find products for your customers.
>
> **Seth Godin**
>
> **US entrepreneur (1960–)**

MARKETING IS FAR TOO IMPORTANT TO LEAVE TO THE MARKETING DEPARTMENT

THE MARKETING MODEL

IN CONTEXT

FOCUS
Marketing models

KEY DATES
1961 The Marketing Science Institute is founded.

1969 US academic Frank Bass publishes a seminal marketing model that can be used to predict demand.

1970s Complex measurement models and decision-making models are developed.

1980 The launch of in-store scanners at checkouts gives marketers new data and prompts the development of sophisticated new models.

1982 The journal *Marketing Science* launches, focusing on mathematical models for marketing purposes.

1990s Intelligent marketing-information systems computerize many routine modeling functions, providing daily updates and projections.

Marketing is too important to leave to the marketing department.

It affects **key decisions** about products, planning, and expenditure.

It must be **rational**, based on data gathered **from all areas of the business.**

This data can then be processed by the marketing department to calculate a **model of potential product performance.**

Companies need to study their customers' buying habits carefully in order to plan business marketing strategies. Using a mathematical model to plan product strategies and aid decision making is an integral part of any modern marketing practice. Marketing computer programs use sets of numerical data about the buying patterns of consumers, along with other variables relating to the product. These are entered into a mathematical model or equation programmed to make a customized calculation. The results will help to quantify the potential performance of products in different channels aimed at various market segments. By examining the data,

See also: Managing risk 40–41 ▪ How fast to grow 44–45 ▪ Organizational culture 104–09 ▪ Avoid groupthink 114 ▪ Good and bad strategy 184–85 ▪ Forecasting 278–79 ▪ Marketing mix 280–83 ▪ Benefitting from "big data" 316–17

> Marketing is inherently about producing results.
> **Geoff Smith**
> **VantagePoint Marketing (1962–)**

marketers and others in an organization can measure projected product growth, or return on investment, and make informed decisions on how to optimize the combination of factors most likely to generate market success.

Gathering the required data for modeling is crucial. Information is needed from all areas of the business so that every step in the process of getting the product from the drawing board to the customer is factored in. When David Packard, the co-founder of Hewlett-Packard, said that "marketing is far too important to leave to the marketing department," he was implying that the plans made by marketers can come to nothing if the rest of the organization is not fully engaged. In addition to getting approval on plans and budgets, marketers should communicate with all departments to gather data and share it once decisions have been made.

Using the data, the marketer can simulate product tests and input variations using different assumptions about elements of the marketing mix, such as market conditions and consumer behavior. The greater the amount of relevant data and the longer the historical period it covers, the more accurate the results will be. Models reassure members of the business that every scenario has been investigated. Marketers can choose from different models or design their own, but the key to making the model work is data.

Gathering and using data

Consumer goods maker Procter & Gamble (P&G) has invested heavily in data gathering and modeling, implementing digital processes from the factory to the shelf in order to capture data and feed it back. The data can be used to make immediate adjustments to product planning and distribution, as well as added to a massive database for future use. According to CEO Robert McDonald in 2011, "Data modeling, simulation, and other digital tools are reshaping how we innovate."

P&G focuses on internal data-gathering processes and also relies heavily on market information from external partners. The leadership team around the world confers once a week to examine data and make decisions in response to buying behavior. As McDonald says, "it's the data sources that help create the brand and keep it dynamic." ■

Market research is valuable, but it can be very time consuming to gather data that is representative of the age, gender, and background of consumers. Computer models do the work faster.

The origin of marketing models

Models of consumer behavior date from the 1960s. They grew out of a need to make marketing more scientific and less driven by instinct or unproven ideas.

In the 1960s US scholar Robert Ferber advocated the use of mathematical simulation techniques and models. These became known as measurement models because they were devised to measure demand for a product as a function of various independent variables—for example, if the selling price is raised by one percent how might this affect demand? Then in 1969 Stanford University's Frank Bass devised his Bass model, which is still used to predict how fast new products will be adopted and spread through a market.

Decision Support Systems (DSS) use measurement models to project the outcome of new decisions, adding variables—such as previous outcomes in similar contexts—to help marketers make optimal choices.

KNOW THE CUSTOMER SO WELL THAT THE PRODUCT FITS THEM AND SELLS ITSELF

UNDERSTANDING THE MARKET

IN CONTEXT

FOCUS
Focused marketing

KEY DATES
1920s The concept of market research emerges in the US.

1941 Robert K. Merton invents the idea of the focus group.

1953 Peter Drucker says the first step for any business is to ask: "Who is the customer?"

1970 US economist Milton Friedman puts forward the business model of shareholder maximization.

1998 Marketing professor Robert V. Kozinets coins the term "netnography" to refer to the theory of ethnography as applied to Internet users.

1990 US professor Gerald Zaltman develops the first neuromarketing technology, ZMET, to analyze consumers' subconscious reactions to advertising imagery.


Every successful business...
...gathers data about the needs of its present and potential customers.
...assesses the market environment—including competitors, distributors, the economy, technology, and social trends.
It can then develop the products that will solve customer problems, and so meet an existing demand.
A product that fits the customer will sell itself.

To be successful in a market, an enterprise needs to understand both the environment in which it wants to do business, and the way consumers in that environment think and act. The marketing environment is the world beyond the confines of the organization—the world that its customers live in—and includes the state of the economy, government regulations, social attitudes, current issues, competing companies, distribution infrastructure and partnerships, and technological changes. At the core of this market is the prospective customer, who will be influenced by many of those environmental factors, but will also be driven by individual needs and preferences, which will affect what products and services he or she buys.

This means that to understand the market, a company must make sense of the "broad brush" of the external environment and, at the same time, fathom the psychological profile and personality of the consumer. The end purpose of these investigations is to identify the biggest problems that consumers are struggling with. Once these are identified, a business needs to respond innovatively, to deliver the products and services that will be seen as perfect solutions.

Gathering data

This analysis may sound simple, but given that any particular market might number thousands or millions of individuals, how does a marketer go about understanding how those people think and behave—let alone what problems or unfulfilled wants they have, both

See also: Stand out in the market 28–31 ▪ Focus on the future market 244–49 ▪ Make your customers love you 266–69 ▪ Forecasting 278–79 ▪ Marketing mix 280–83 ▪ Maximize customer benefits 288–89

individually and collectively? The starting point is to fully explore the world in which the customer lives. What are the basic motives that drive buying decisions? What value does the customer place on price, quality, and design? Among all the social, cultural, financial, and technological forces in the environment, which ones particularly affect the customer? A marketer wants to know the practical details of the customer's daily life. How does that person live on a day-to-day basis? Does he or she have tasks that could be made easier? What other kinds of problems could the company potentially solve? The goal of all this research, according to influential management thinker Peter Drucker, "is to make selling unnecessary."

> Being customer driven … is about building a deep awareness of how the customer uses your product.
>
> **Ranjay Gulati**
>
> **Harvard business professor**

Beating the recession

In 1973, Drucker advised business leaders to "know and understand the customer so well the product or service fits him and sells itself." At that time, the corporate world was in turmoil as recession took hold across all of the major economies of the West, bringing to an end the upward growth that had, with the exception of a few slow years, persisted since the end of World War II. Everyone in business was thinking about how to survive the lean times ahead.

Recession struck in the very same year that Drucker published the work that would later be hailed as a masterpiece, *Management: Tasks, Responsibilities and Practices* (1973), in which he advised that a business centered on the customer was the only sure way to realize growth. "There is only one valid definition of business purpose," he wrote, and that is "to create a customer." By this he meant that a customer's willingness to pay for goods or services is the catalyst that propels businesses to turn raw materials and resources into products for sale. Without the customer's desire or need, there is no impetus for commercial activity; and conversely, without commerce, nothing can be produced to meet the customer's demand.

Drucker suggested that when customers buy something, they are not thinking about the product or service itself, but about the usefulness of it to themselves. For them, value lies in the problem-solving ability of the purchase.

Although Drucker's idea is now at the core of most modern marketing theory and practice, at the time it was a counter to the prevailing management approach of the 1970s, which advocated the maximization of shareholder value. »

Peter Drucker



One of the most quoted experts in management and marketing, Peter Drucker was exposed to big ideas during his childhood years in Vienna, Austria. Born in 1909, his father was an economist and lawyer, and his mother was one of the first women in Austria to study medicine. The couple regularly held salons in their home and the young Drucker was encouraged to sit in on these discussion evenings, which were regularly attended by prominent professionals.

Armed with a degree in Law from Hamburg University, and with a budding journalistic career unfolding, he moved to England as the Nazis rose to power, before settling in Los Angeles, where he became a professor of politics, and later a professor of management. Drucker wrote 39 books on the subjects of economics, leadership, and management. He died in 2005.

Key works

1946 *The Concept of the Corporation*
1954 *The Practice of Management*
1973 *Management*

Skaterboarders are a niche market, and have a specific set of requirements from equipment and fashion brands. Micromarketing can help businesses reach niche markets such as this one.

This theory placed the wealth of the corporation, rather than the needs and wants of the customer, at the core of a business. It held that business should be run solely to increase profits, which would boost the value of stock prices and allow the company to return value to the shareholders—who, after all, own the business. This way of thinking had been introduced by economist Milton Friedman in an article he wrote for *The New York Times* in 1970, and it was later developed further by business professors Michael Jensen and William Meckling in their paper, "Theory of the Company." As the title implies, Jensen and Meckling's thesis was not generally concerned with the world beyond the company—it focused on the relationship between upper management and shareholders, rather than the relationship between management and the market.

21st-century thinking

The concept of shareholder maximization was a dominant force in the last few decades of the 20th century, but the importance of understanding the market and of customer-centered management has gradually gained favor, partly because the corporate-centered strategy has proved no guarantee of longevity. Business in the 21st century has become more people-centered with a number of huge success stories helping to sway management further toward customer-oriented strategies.

In 2010, business professor Richard Martin wrote an article for the *Harvard Business Review*, heralding "The Age of Consumer Capitalism." He claimed that we are now living in an era in which shareholder value is no longer the primary goal. "For three decades, executives have made maximizing shareholder value their top priority," he wrote. "But evidence suggests that shareholders actually do better when firms put the customer first."

An example of a serious failure to prioritize the customer is that of the British jewelry company, Ratners. By the late 1980s, Ratners was the world's biggest jeweler, with 2,000 stores on two continents. The stores sold jewelry at low prices and were very popular—until the disastrous speech by the company's chief executive, Gerald Ratner, at the Institute of Directors in 1991. In his talk, supposedly about the company's success, he instead insulted one of his own products, joking that its low price was possible due to its poor quality. Offended customers abandoned the store and $800 (£500) million was wiped off the value of the company, which nearly went under. This notorious example shows how businesses who treat customers with contempt can pay a very high price.

Knowing the market

Since Drucker's initial proposition that a business must get to know the customer intimately, the market place has matured, making the task of understanding the consumer, customer groups, and the market as a whole, far more complex. One of the reasons is fragmentation, meaning that consumers are now divided among many small markets that are constantly in flux, and may suddenly emerge from nowhere. These micromarkets are defined by the common aspirations, likes, or needs of the consumers within them. Each consumer is subject to

> “Whether it's Google or Apple or free software, we've got some fantastic competitors and it keeps us on our toes.”
>
> **Bill Gates**
>
> **CEO of Microsoft** (1955–)

> Research is formalized curiosity. It is poking and prying with a purpose.
> **Zora Neale Hurston**
> **US anthropologist (1891–1960)**

a wide spectrum of external factors, so it is crucial to understand these to get to their hearts and minds.

Price cutting by competitors, for example, can divide the customer's attention, providing enticement but also potentially damaging a brand's value in the eyes of the consumer. A business therefore needs to know how sensitive their existing and potential customers are to price.

The distribution system, which determines how products and services get to potential buyers, is also a vital aspect to consider. A business should figure out how to deliver products and services in a way that best suits purchasers. The Internet has transformed how this happens, and customers now expect sellers to understand where, when, and how they want to buy.

Types of research

The state of the economy, level of interest rates, regulatory law, and technological change can sway customers, while social and cultural forces are arguably the most important in the marketing environment. These encompass gender, life stage, income, trends, current issues, and the influence of key individuals in the public eye.

The challenge for the marketer is finding out how all of these things influence customers and, consequently, what motivates them to buy. The obvious starting point is to ask questions. This basic premise developed during the 1960s and 1970s into a formal process of question-and-answer known as market research. Researchers gathered both quantitative evidence (from simple questions directed toward a large audience) and qualitative evidence (through direct observation or in-depth discussion with a small sample of individuals). Qualitative research is usually regarded as the more valuable of the two in getting a grasp of why a customer accepts or rejects a product, and in understanding the realities of customers' lives.

Personalized marketing

Since the 1990s, business has forged a direct path of communication with the customer via the Internet. Marketers have developed new strategies for online information gathering, such as personalized, or one-on-one, marketing, in which a single consumer's interests and wants can be recorded and compiled to create a detailed profile.

Psychographic profiling is one way that marketers attempt to make sense of diverse consumer interests, by corralling individuals with shared interests and motivations into groups that can be targeted. Whereas businesses used to define their customers demographically, for example as Baby Boomers or Generation X, a psychographic profile is much more detailed. It is put together by using information about a consumer's daily habits; favorite brands, music, and athletic personalities; media habits; leisure activities; vacation destinations; and much more.

Social media and online communities have encouraged people to define themselves by an ever-more specific set of characteristics, likes and dislikes. At the same time, the Internet has allowed businesses to glean »

Focus groups were used extensively in the late 20th century to gather informal comments and opinions on products, as shown here in a scene from the TV show, *Mad Men*.



Personalized marketing makes use of information gathered from social media and other platforms to create tailor-made advertising. Consumer A is an active, athletic individual, and would respond to marketing that speaks to this lifestyle.

Customer relationship marketing makes use of historical data to produce individual marketing. Consumer B is an avid TV watcher; an online retailer could make recommendations for DVDs based on previous purchase history.

Psychographic profiling allows marketers to find common ground among a diverse group of individuals. A canny marketer aiming for consumers A, B, and C could use their shared taste in music as a way forward for a campaign.

access to much of this information, providing companies with copious amounts of data for marketing purposes. Software that tracks and analyzes customer preferences via their online and mobile activities has enabled companies to engage in what is called customer relationship marketing (CRM)—using the data extracted about customers and their preferences to sell more products and services to them. Amazon, for example, uses a customer's shopping history to recommend similar products and to show online browsers what other customers with the same interests have recently bought.

Real-time data

Telephone customer service sits at the other end of the spectrum from social media. Pioneered in the 1980s, it began to prove even more useful in the 1990s with the increase in call centers. Management can divert calls from customer service—or listen in—to learn what issues consumers may be having, what could be improved, and what problems they have that need to be solved. Marketers have dubbed this "customer experience management" (CEM), because it captures the customer's immediate interaction with the seller, whereas CRM uses a customer's history.

> People are unlikely to know that they need a product which does not exist.
>
> **John Harvey Jones**
>
> **UK industrialist (1924–2008)**

The field of neuroscience has taken the idea of customer understanding to the next level, advancing Drucker's premise that businesses needed to drill down into the customer psyche and discover how decisions are made. Several studies by branding guru Martin Lindstrom have caused a sensation by proposing that, no matter how consumers may answer in face-to-face research, the only way to know what subconsciously motivates them to buy is to measure changes to their brainwaves when exposed to certain images, sounds, and smells. According to Peter Drucker, "the main objective of neuromarketing is decoding the process that take place in the customers' mind, in order to discover the desires, wishes, and the hidden causes of their options, so that there is a possibility to get them what they want."

Neuromarketing is one way of understanding the customer, and it is actively used by companies such as Google and Disney to test consumer impressions. However, it is not in itself a solution to knowing what customers want to buy. A broader perspective is needed to truly understand a market and the elements that shape it. In some cases it is pure innovation, driven by a desire to transform the way people live through technology, that gives customers something they didn't realize they wanted, though the need for it was there. Apple's iPad is an example of how forward thinking about what customers lives could be like can lead to market success.

Innovative solutions

When the iPad was unveiled in 2010, investors and the press were sceptical, wondering who would want one, given that a laptop computer had more functions and was only slightly bigger. The iPad was a sellout because customers loved using it—it was fun and fast, and allowed them to do all the things they enjoyed on their iPod touch but with a bigger screen and a keyboard that was easier to use.

Apple CEO Steve Jobs claimed in an interview with *Fortune* magazine never to have done consumer research. "It isn't the consumer's job to know what they want," he reportedly said. "That doesn't mean we don't listen to customers, but it's hard for them to tell you what they want when they've never seen anything remotely like it."

> "Did Alexander Graham Bell do any market research before he invented the telephone?
> **Steve Jobs**"

Steve Jobs instinctively understood what the consumer wanted because he had the same problem: the lack of a well-designed, portable device that would make communication and information-gathering fun and easy.

Although Peter Drucker emphasized the importance of knowing the customer, he did not narrow this to just asking the customer what they want; he intended that business should also think ahead and find ways to innovate. "The "want" a business satisfies may have been felt by the customer before he was offered the means of satisfying it," he reasoned. "It remained a potential "want" until the action of businessmen converted it into effective demand. Only then is there a customer and a market."

Professor Ranjay Gulati maintains that the first step in understanding the new, highly competitive market of the 21st century is asking customers the right questions; the most important ones being what problems and issues they are dealing with. But he says that a business must make a creative leap to figure out the innovations that will serve those customer needs, if they want to survive in the market place. ■

Steve Jobs of Apple encouraged the company to consider the changing technological world and people's existing daily habits to provide an innovative solution to an unfelt need: the iPad.



ATTENTION, INTEREST, DESIRE, ACTION

THE AIDA MODEL

IN CONTEXT

FOCUS
Marketing models

KEY DATES
1898 E. St. Elmo Lewis describes the principle that would become AIDA.

1925 US psychologist Edward Kellogg Strong Jr. refers to AIDA in *The Psychology of Selling and Advertising*.

1949 US marketing executive Arthur F. Peterson expresses AIDA as a sales funnel, in *Pharmaceutical Selling, Detailing and Sales Training*.

1967 US professors Charles Sanclage and Vernon Fryburger propose the EPIA model: Exposure, Perception, Integration, Action.

1979 US academics Robert L. Anderson and Thomas E. Barry propose adding brand loyalty to the various hierarchy of effects models based on AIDA.

The AIDA model is the foundation of modern marketing and advertising practice. It outlines the four basic steps that can be used to persuade potential customers to make a purchase. The first three steps lie in creating attention (A), developing interest (I), and building desire (D) for the product, before the fourth step—the "call to action" (A)—tells them exactly how and where to buy.

AIDA is often expressed as a funnel, because it channels the customer's feelings through each stage of the communication process toward reaching a sale.

AIDA in practice

Attracting the customer's attention is the first challenge, and this may be achieved by using an arresting catchphrase, offering a discount or something for free, or demonstrating how a problem can be solved. Once someone's attention has been seized, it must be turned into genuine interest. This is best done by providing a succinct assessment of the product's benefits to the consumer, rather than simply listing the product's main features. Problem-solving claims, results-based advice, or testimonials can be used to create desire, before finally laying out a simple way for that desire to be met—the means to buy. On website advertising, this might be a direct link; on TV, print, or billboards it may be a website, store name, or telephone number.

Commercial potential

In the movie industry, the stages of AIDA are used to great effect. Movie studios often begin their marketing campaigns months in advance with giant billboard posters to attract attention to the new movie. Short "teaser" trailers follow, which provoke interest by offering a tantalizing glimpse of the movie without giving too much away. Desire is instilled by the release of the full trailer, which is carefully crafted to show the highlights of the movie, from big explosions and special effects to witty lines of dialogue. On the opening weekend, advertisements in newspapers and on television spotlight the movie's release, provoking action by inviting the consumer to go and buy a ticket.

One of the movie hits of 1999, *The Blair Witch Project*, had an innovative approach to AIDA that made use of new viral marketing

See also: Stand out in the market 28–31 ▪ Creating a brand 258–63 ▪ Promotions and incentives 271 ▪ Why advertise? 272–73 ▪ Generating buzz 274–75

techniques. Before the movie's first showing, the filmmakers created a website that offered an intriguing insight into the background to the movie. It presented snippets of movie as "found film footage," and left viewers wondering whether the story of the movie was fiction or reality. The website grabbed attention, and continued to gain interest as more video clips and audio files were added. The buzz around the "myth" of the Blair Witch grew, creating further desire to see the movie. The call to action came in the form of a very limited release; moviegoers were urged to buy tickets before those few showings sold out. The movie cost just $35,000 to make, but generated revenues of more than $280 million worldwide.

E-marketing and AIDA

The advent of e-commerce prompted award-winning UK copywriter Ian Moore to suggest NEWAIDA as a more relevant model for e-marketing: AIDA preceded by navigation, ease, and wording. It seems that as markets have become more complex, marketers require ever-clearer ways of perceiving the customer journey. ■

The AIDA model



ATTENTION
Make the customer aware of the product or service using an eye-catching advertisement or an arresting offer.

INTEREST
Hold the customer's interest by providing infomation about the advantages of the product or service and its benefits to the customer.

DESIRE
Generate the customer's desire to buy by convincing them that the service or product will meet their needs.

ACTION
Make it as easy as possible for the customer to make the purchase.

SALE

Who invented AIDA?

Management expert Philip Kotler references Edward Kellogg Strong Jr.'s book *The Psychology of Selling and Advertising* (1925) as the source of AIDA. However, Strong's book gives credit for the idea to advertising pioneer Elias St. Elmo Lewis (1872–1948), maintaining that Lewis formulated the slogan "Attract attention, maintain interest, create desire" in 1898 and that he later added the fourth term "get action."

The first use of the AIDA acronym is commonly attributed to C. P. Russell's article "How to Write a Sales-Marketing Letter," published in the US advertising trade magazine *Printers' Ink* in 1921—Russell was also one of its editorial staff. He outlined the basis of the four-step process and pointed out that "reading downward, the first letters of these words spell the opera *Aida*." He advised, "When you start a letter ... say 'AIDA' to yourself and you won't go far wrong ..."

> In practice, few messages take the consumer all the way from awareness to purchase, but the AIDA framework suggests the qualities of a good message.
>
> **Philip Kotler**
> **US marketing guru** (1931–)

MARKETING MYOPIA

FOCUS ON THE FUTURE MARKET

IN CONTEXT

FOCUS
Customer service

KEY DATES
1874 French mathematical economist Leon Walrus recognizes that small changes in consumer preferences have a big impact on business.

1913–1914 Henry Ford, US industrialist, installs the first production line, and informs companies that cheaper per-unit costs are the key to their sustained growth.

1957 US marketing theorist Wroe Alderson stresses that a business needs to grow and adapt to changes in order to survive and thrive.

1981 US marketing thinkers Philip Kotler and Ravi Singh coin the term "marketing hyperopia" to describe the problem of businesses having a clear view of distant issues but not of close ones.


Demand for Product A dries up and growth slows.
The company cuts production costs and boost profits.
Product B is already in development; customers say this will suit them better than Product A.
Demand for Product A continues to fall.
Production of Product A is replaced by Product B.
The company struggles to survive.
The company continues to grow.

When a company has a fixed idea of what products or services it wants to sell, and a narrow idea of who it is selling to, it runs the risk of failure because it is not easily able to adapt to changes in market conditions. It will miss opportunities to expand and conquer new market areas. Harvard Business School professor Theodore Levitt dubbed this lack of foresight "marketing myopia," a term he first used in an article of the same name, published in the *Harvard Business Review* in 1960. He stressed that a company needs to look ahead and constantly evaluate new openings in the market. If it does not, growth will stagnate and, ultimately, decline.

In Levitt's view, when a business is concentrating on how to sell its products and is blind to the changing circumstances and desires of customers, it will not be prepared for shifts in the market. For example, a sudden change in the economy or government policy, a new technology, or a social crisis can have an almost immediate effect on the buying public. If a company is prepared for such changes, and flexible enough to adjust, it can find ways to tempt customers and prosper. The astute approach, Levitt said, is to build a business around the customer, rather than around the company. He proposed that "an industry is a customer-satisfying process, not a goods-producing process."

Grow or die

Underlying Levitt's idea is the inevitable growth pattern of a business. At first a business enters the market with a product or service and may enjoy rapid

See also: Finding a profitable niche 22–23 ▪ Make your customers love you 264–67 ▪ Maximize customer benefits 288–89 ▪ Feedback and innovation 312–13

growth. But all growth eventually tapers off because the market has already bought enough of the product or service, or develops different priorities. The company with marketing myopia turns inward to see how it can trim the costs of manufacturing or make other internal cost-saving measures. These tactics may offset a decline in profits for a while, but eventually they will not be enough to save the business from failing. Levitt, however, reasoned that an industry can continue to grow long after the obvious marketing strategies have been used, if the management is totally focused on the customer.

Levitt asked the corporate heads of America in 1960, "What business are you in?", demanding that they shift their focus from manufacturing to customer satisfaction. This concept is taken for granted in the current age geared to customer analysis and niche marketing, but given that the US economy had boomed in the 1950s, enjoying its most prosperous era for several decades, Levitt's idea may not have seemed very relevant at the time. Still, he cited convincing examples in US industry to support his case. In particular, he accused automobile manufacturers of marketing myopia.

> Selling is not marketing.... the entire business process [is] a tightly integrated effort to discover, create, arouse, and satisfy customer needs.
> **Theodore Levitt**

The automobile industry

On the surface, the US auto industry appeared unstoppable. By 1960 the "Big Three" in the city of Detroit (General Motors, Ford, and Chrysler) dominated the domestic and global markets. They produced 93 percent of the automobiles sold in the US, and controlled 48 percent of world sales. One-sixth of the US work force was employed directly or indirectly by the industry. Nevertheless, cracks were beginning to show.

In 1955, the Big Three had enjoyed a record year. However, demand fell dramatically in 1956 and 1957 because so many consumers had already bought cars. This sales slump was partly responsible for the recession of 1958, during which manufacturing as a whole declined. This was the first economic downturn in the US since the Great Depression. Meanwhile, car manufacturers in Germany, the UK, France, and Japan were threatening the dominance of the Big Three.

"Detroit never really researched the customer's wants," alleged Levitt. "It only researched the kinds of things which it had already decided to offer." By the time US carmakers realized what had happened, they found it difficult to adjust. After a series of dud models and marketing failures, they finally rebounded in 1965 with the ubiquitous "muscle" cars such as the Ford Mustang—but they would never again have such an iron grip on the market.

Before Theodore Levitt's groundbreaking article in 1960, marketing was not considered a »

Abandoned automobile factories in Detroit are a reminder of the US economic downturn in the late 1950s. Theodore Levitt argued that carmakers failed to adapt to their customer's needs.



Shortsighted marketing focuses on current customers and their needs but overlooks potential new markets, leading to missed opportunities and more modest profits.

Farsighted marketing is adaptable, allowing businesses to shift their focus to reach a wider range of consumers with a broader product offering. Returns can then be much greater.

serious endeavor worthy of management attention; instead it was a formulaic task left to the sales or production departments. But "Marketing Myopia" prompted both the corporate and academic worlds to start thinking differently.

Taking marketing seriously

Around the same time that Levitt was writing that pivotal article, he inspired a student, Philip Kotler, who would take his proposition further to cement a fundamental change in the way managers approached business. Kotler studied at Harvard in 1960 for his postdoctoral work in mathematics, having already completed a PhD in economics at the Massachusetts Institute of Technology (MIT). Exposed firsthand to the ideas of Levitt and other marketing professors, he began to develop a rigorous outline for the role of marketing in any organization. The result was published in 1964, and *Marketing Management* is still regarded as the seminal textbook on the subject. It is credited with being the first book to take a scholarly and scientific approach to marketing. Kotler's key teachings are that the customer should be at the center of any business, and that profit is derived not merely from selling but from delivering satisfaction to customers: thinking which is still at the core of most MBA programs.

The effect of Levitt and Kotler's ideas on the corporate world was almost immediate. In 1962, executive Robert Townsend had just been lured from American Express to take up the position of CEO at struggling car rental company Avis. He rebuilt the business by focusing on two interdependent principles: put customers first; and create a working environment in which employees love what they do. For the first time the business began to make a profit.

> “The entire corporation must be viewed as a customer-creating and customer-satisfying organism.”
> **Theodore Levitt**

Customer service

By 1964 Avis was expanding. The man appointed as manager of operations in Europe, Africa, and the Middle East, Colin Marshall, was another believer in Levitt's customer-centered approach, and deployed it with great success. Within ten years he was running the entire company from New York, overseeing innovations that gave customers better service, and making Avis the market leader. In 1981, when he was recruited to help save British Airways (BA), he turned around the fortunes of the airline in a tough environment, creating a successful model of service-oriented business. His tactic was not to cut air fares but to offer better customer service. Marshall saw that the customer experience went beyond check-in, in-flight, touchdown, and passport control, and he introduced the world's first arrivals lounges.

Customer experience

Other full-service airlines have adapted the BA model. Most airlines now rely on optimizing customer relationships in order to gain a long-term, competitive advantage. United Airlines, for example, has implemented a system that lets staff identify high-value frequent flyers and proactively offer them special services if their flight is canceled. American Airlines has promoted its use of technology to make the flight experience more appealing for customers, becoming the first with permission from the Federal Aviation Administration (FAA) to allow flight attendants to use tablets to help them manage the onboard experience more efficiently. It was the first major commercial airline to provide branded tablets to First Class and Business passengers for inflight use. Enhancing a customer experience through internet access and applications on iPads, tablets, and cell phones is now a vital consideration in many sectors of industry, something on which Google has capitalized.

Airport arrivals lounges were offered to BA passengers to enhance their experience of traveling with the airline. Rather than cutting prices, BA chose to focus on customer service.

> Marketing is not the art of finding clever ways to dispose of what you make. It is the art of creating genuine customer value.
> **Philip Kotler**

In 2005, Google purchased a little-known company called Android Inc., which was developing a smartphone platform. Two years later Apple released its iPhone and rapidly dominated the market; customers loved it since they could replicate the world of the Internet on a handheld device. Online search giant, Google, saw that it risked becoming beholden to Apple for access to sell its applications so, with other cell-phone makers, it developed an alternative—an open-source operating system that would work on all mobile devices. Google now had a platform through which it could generate profit with sales of applications and in-app advertising.

Kotler cites Google as a model of innovation, always seeking new ways to solve customers' problems and help them manage vast amounts of information. Levitt would have agreed with the first line of Google's corporate philosophy: "Focus on the user and all else will follow." ■



Theodore Levitt

Acknowledged as one of the most original management thinkers of the modern age, Theodore "Ted" Levitt was born in Vollmerz, Germany but emigrated to the US with his family at ten. He served in the US Army during World War II, returning to enroll at Ohio University. With his PhD in Economics, he joined the faculty of Harvard Business School in 1959, writing his famous article "Marketing Myopia" just a year later. For the next 30 years he taught at Harvard, contributing 26 articles to the *Harvard Business Review*, of which he was chief editor from 1985 to 1989. In its 2004 edition, the journal cited marketing myopia as the most influential marketing idea of the past 50 years. Levitt created a similar stir in 1983 with another article, "The Globalization of Markets," which led to him being credited with popularizing the term "globalization."

Key works

1960 "Marketing Myopia," *Harvard Business Review*
1983 *The Marketing Imagination*

THE CASH COW IS THE BEATING HEART OF THE ORGANIZATION

PRODUCT PORTFOLIO

IN CONTEXT

FOCUS
Product assessment

KEY DATES

9000 BCE Cattle, including cows, are used as the first form of currency.

Mid-1960s Peter Drucker uses the term "cash cow" in the context of business management.

1968 The Boston Consulting Group devises the growth-share matrix: a model for categorizing a company's products according to its market share and growth potential.

Early 1970s Consultancy company McKinsey & Company develops alternative GE–McKinsey matrix with client General Electric.

1982 H. C. Barksdale and C. E. Harris publish their new matrix in "Portfolio analysis and the PLC."

The term "cash cow" refers to an investment or area of business that provides a dependable source of revenue. In a corporate context, the cash cow is the product or service that buoys profits year in, year out and provides funds so the business can grow. It brings cash in, which becomes the lifeblood: contributing most of the operating expenses; paying for development, launch, and support of new products; and propping up it's less profitable ventures.

Cash generator

The cash cow is typically a product that has reached maturity in its life cycle. Like its real-life counterpart, its initial cost has been paid off, it needs little maintenance, and it can be "milked" for the rest of its life. Although such products may no longer be growing, they still generate substantial revenue because they have good market share and no longer require much capital outlay to keep them going.

Management veteran Peter Drucker is said to have first used the "cash cow" metaphor in the mid-1960s; he certainly referred to it throughout his career to describe a product that is an easy cash generator. He was drawing on the history of commerce in his analogy: livestock such as cows, goats, and camels served as currency from around 9,000 BCE. While Drucker understood the value of the cash cow, at the same time he cautioned against overreliance on it. He advocated a strategy of planned abandonment when the cash cow is challenged by another product, potentially a rival within the company's portfolio, which is growing faster.

> “As entrepreneurs, we adore shiny new things. But don't forget to give some love to the (cash) cows that keep the business going.”
>
> **John Warrillow**
> **UK entrepreneur (1971–)**

The Boston Consulting Group

In 1875, the Boston Safe Deposit and Trust Company was set up in its home port in New England to offer safekeeping services to local merchants and ship owners. Run by several generations of the prominent Bostonian family, the Lowells, the company had grown by the 20th century to become a prominent financial institution.

In 1963, a chance meeting between the Boston Safe Deposit and Trust Company CEO John Lowell and one of the US's brightest management thinkers Bruce Henderson (1915–1992) led to the founding of the Boston Consulting Group (BCG). This management consultancy was essentially a one-man band with Henderson at the helm.

Henderson had been a Bible salesman before completing an engineering degree at Vanderbilt University, Nashville, and going on to study at Harvard Business School. He joined Westinghouse Corporation before graduating, becoming one of the youngest vice-presidents in the history of the company. Initially finding it difficult to land clients and compete against larger consultancies, Henderson came up with the idea of offering "business strategy" as a unique service. A few years later, with a team of 36, Henderson devised the now-famous growth-share matrix (1968). His company, BCG, has since grown to become a significant global management consultancy employing more than 2,000 staff in 75 offices around the world.

See also: Managing risk 40–41 ▪ How fast to grow 44–45 ▪ The Greiner curve 58–61 ▪ Profit versus cash flow 152–53 ▪ Leading the market 166–69 ▪ The MABA matrix 192–93 ▪ The marketing model 232–33 ▪ Marketing mix 280–83

The cash cow **generates a good income** and has a **good share of the market.**

→

It does not require any further outlay and it **funds the development** of new products.

→

The cash cow is the beating heart of the organization.

→

However, it is a mature product and growing **star products** are also necessary in a **balanced portfolio.**

Peter Drucker cited the case of IBM in the mid-1970s. The mainframe computer was its cash cow, but the newly launched PC was its fastest-growing product; in fact, IBM dominated the PC market at first. However, the company deliberately restricted sales of PCs for fear of jeopardizing its cash cow, and in doing so, allowed time for clones to flood the market. In fact, IBM lost so much ground that its PC business never recovered. IBM's product portfolio continued to be subordinate to its cash cow. With investors in mind, they avoided the risks that come with innovation and developing new, leading-edge products and ended up being unable to compete amid the rapid technological and marketplace changes of the 1990s.

> A company should have a portfolio of products with different growth rates and different market shares. The portfolio is a function of the balance between cash flows.
> **Bruce Henderson**

Drucker may have been the first to use the term in a business context, but the Boston Consulting Group (BCG), founded by Bruce Henderson, first incorporated the cash cow into a business model in 1968. Referred to as the BCG matrix, Boston Box, or growth-share matrix, this model graphically depicts the relationship between market growth and market share. It quickly became a popular business tool for making decisions about which products to wind down and which ones to invest in.

The product portfolio

The starting point for the BCG matrix is the concept of a product portfolio—the total mix of products offered by an organization. These can be categorized according to their share of the market, revenues, and growth potential. Each one can also be assessed by its position in the "product life cycle," which tracks the path of a product from initial growth to maturity and then decline. When making decisions about which products it should continue to manufacture, an organization needs to consider the life cycle of each product and the balance or synergy between all the products in their portfolio.

The BCG matrix provides an analytical tool for assessing the effectiveness of the product mix and its profitability. A business »

IBM launched its PC in 1981 and it sold well. However, the company failed to capitalize on its success, focusing instead on its mainframe computers.


MARKET GROWTH
Low
High
MARKET SHARE
Low
High
Dog
products have low market share and growth prospects; they may be ripe for divestment.
Question mark
products, sometimes also referred to as "Infants," have the potential for growth.
Cow
products have a strong presence in the market and generate a solid revenue.
Star
products are high-selling items in a market that is expanding.

The BCG matrix can be used to categorize products in terms of growth and market share, so companies can check that they have a well-balanced product portfolio. Products with a high market share are plotted into cells on the left-hand column, and those with low market share on the right. The top row is home to products with high potential for growth, while those in the bottom row are in declining markets.

can use this information to make sure it has a mix of products that will satisfy its short- and long-term needs, and to think about the priority and resources they should allocate to each product. The matrix assesses products on two levels: first, the potential growth in the market for that product; second, the market share held by each product.

Using the Boston matrix

By using the matrix, managers can see where their products fall among four categories: dogs, question marks, stars, and cows. "Dogs" are products that have low growth prospects and a low market share. These products may be making a loss, barely breaking even, or possibly generating a tiny amount of profit. Because they are in a slow-growing market, there is little chance that performance will improve under current conditions. Products that fall into this cell of the matrix are candidates for culling from the product portfolio. However, before the dog is sold off or disposed of, management must consider if it is worth keeping for strategic reasons. For example, if it is blocking a competitor product or the market for that industry is likely to pick up in the future, it might be worth retaining. Or it may play an important role in complementing another product in the portfolio and providing customers with a stepping stone to that product.

Like the dog, the "question mark" product also has a low share of the market, but it is in a high-growth industry. Products in this box can create a dilemma for the company. If it is new, does the product need more time to prove itself, and more investment in manufacturing or marketing? Or does it need more market share, which could be arranged by buying up competitors? Perhaps it needs repositioning in the market. Or should it be dropped entirely?

"Stars" are products that have a large market share in a growing market. These require investment to maintain their position and help them grow into the dominant product in the market. They have the potential to be a future cow.

"Cows" are products that were once stars. They continue to hold a large market share, but they are mature products in an established market that has little potential for growth. They no longer need much investment, because they have reached their growth potential, and as market leaders they sell in large numbers of units, giving them the advantage of economies of scale. This means they generate cash while costing very little.

The matrix in practice

Nestlé is often cited by management theorists as a textbook example of how a company might arrange its product portfolio according to the BCG matrix. The world's largest food company, with some 8,000 brands, Nestlé has developed a strategy of building its long-term cows and keeping them as fresh as possible, devoting capital to product areas that have a prospect of high returns, and shedding

> High-growth products require cash inputs to grow. Low-growth products should generate excess cash. Both are needed simultaneously.
> **Bruce Henderson**

products with limited potential. The coffee brand Nescafé has continued to perform well since its 1938 launch, thanks in part to the company's strategy of investing in and expanding the range. At different times in the company's history it has been a cow and a star product. Instant coffee is now a reliable cow, funding expansion in other areas. However, the company's organic food range has suffered low market share in a growing market, making it a question mark. Nestlé's large share of the food seasonings sector, a low-growth area, could be seen as a cow.

Through a series of acquisitions, Nestlé has become the leading pet-food maker in a globally high-growth market, elevating food products for real dogs and cats into star products.

Nescafé coffee is Nestlé's largest brand, a cash cow valued at $17.4 billion. Growing since World War II, the product generated sales of $10 billion in 2012.

Portfolio management

Other models have evolved from the BCG. In the 1970s, General Electric consulted with business advisors McKinsey & Company to develop an alternative known as the GE–McKinsey matrix. This nine-cell model enables a more complex analysis of the product portfolio, and allows companies to plot market attractiveness and competitive strength. In 1982, H. C. Barksdale and C. E. Harris proposed two new product classifications to add to the original BCG matrix: "warhorses" and "dodos." Warhorses lead the market but are threatened by a negative market growth, so a business must gauge whether to ride out the storm in the belief that it will pick up, or work the horse as long as possible with minimal outlay. Dodos are about to become extinct, with low share in a negative growth market.



Barksdale and Harris created a matrix that added two new classifications known as warhorses and dodos, both of which were expected to decline.

Although they lead the market, **warhorses** are threatened by the prospect of negative growth.
On their way to extinction, **dodos** have a low share of a market that has an outlook of negative growth.

Using the matrices

A 1981 study by management professors Richard Bettis and W. K. Hall, and supported by P. Haspeslagh in 1982, found the BCG matrix was used by 45 percent of companies ranked in the *Fortune* 500.

However, the BCG matrix has attracted criticism for being overly simplistic and basing judgements on cash flow rather than return on investment. A study by Colorado State University in 1992 discovered that companies using the BCG matrix and similar models had lower shareholder returns than companies not using such models. Despite its detractors, the BCG provides an easy way to make sense of the product portfolio and the strategies involved in managing it successfully. ■

EXPANDING AWAY FROM YOUR CORE HAS RISKS; DIVERSIFICATION DOUBLES THEM

ANSOFF'S MATRIX

IN CONTEXT

FOCUS
Strategic planning

KEY DATES
500 BCE The concept of "strategic planning" is first used in military campaigns in ancient Greece.

1920s Harvard Business School develops the Harvard Policy Model, one of the first strategic planning approaches to private businesses.

1965 Igor Ansoff's *Corporate strategy: an analytic approach to business policy for growth and expansion* is the first book on corporate strategy.

1980 Michael Porter introduces his theory of competitive strategy.

1989–90 Concepts of core competence and strategic intent are developed by Gary Hamel and C. K. Prahalad.

An organization needs to **develop and grow**...

↓

...but moving away from **existing products** is risky...

↓

...and developing **new products** to sell in **new markets** doubles that risk.

↓

Expanding away from your core has risks, diversification doubles them.

First published in 1957 in the *Harvard Business Review*, Ansoff's matrix is a marketing tool for planning the strategic growth of an organization. Created by mathematician Igor Ansoff, it is intended for businesses that are ready to expand and have the resources to fund growth. The matrix offers four possible strategies that a company might adopt, depending on the status of its product and the conditions of the market: market penetration, market development, product development, and diversification. In addition to presenting these four strategic options, the matrix also attaches an inherent risk factor to each one. It is crucial for decision makers to take the risk factor into consideration, lest it gamble too heavily with the company's existing resources.

The four strategies

Each approach is differentiated by whether products or services are unchanged or new, and whether they remain in the existing market or are entering a new one. The least risky of the four strategies is "market penetration"—maximizing sales of an existing product in an existing market. In this approach,

See also: Managing risk 40–41 ▪ Take the second step 43 ▪ How fast to grow 44–45 ▪ Protect the core business 170–71 ▪ The MABA matrix 192–93



Ansoff's matrix is expressed as a square divided into four equal cells, each of which represents different marketing strategies, with different combinations of product status and market conditions. Market penetration is clearly the least risky, while the quadrant of diversification presents the highest risk.

greater sales might be achieved through competitive pricing, advertising, loyalty programs, or by driving out competitors.

"Market development" entails selling the same product in different markets. Additional spending may be unnecessary unless localization is required, but the cost of setting up distribution channels in the new market poses some risk. In this model, different geographic or demographic markets, or alternative sales channels—such as online or direct—might be tapped.

"Product development" strategy is the sale of new or significantly improved products to an existing market. Here, the cost of product development, associated distribution, and marketing support poses a risk. Companies adopting this strategy might offer variants of the product, or develop related goods.

The final, and riskiest strategy, is that of "diversification"—moving into new product areas and new markets. This strategy reduces risk in the long term by alleviating a company's reliance on core products. However, a company can risk a great deal, depending on the initial outlay, and needs to have plenty of resources if the strategy fails.

A risky venture

UK supermarket Tesco's venture into the US shows the risks of diversification. After 10 years' preparation, it launched its Fresh & Easy stores in 2007, but misread the market. Positioning itself in the middle, it was neither upscale nor discount, with most of its outlets in working-class suburbs where consumers looked for bargains. Critically, Tesco's small-scale, walk-in stores did not suit the average car-dependent US shopper. The investment did not pay off, costing Tesco over $1.9 (£1.2) billion. The outcome may not have been forecast by Ansoff's matrix, but the risk would have been clear. ■

Is Ansoff's matrix still relevant?

Igor Ansoff (1918–2002) is remembered as the father of modern marketing strategy. His matrix has generated many variations over the decades and became one of the foundation stones of business strategy, underpinning ideas such as core competence and competitive strategy.

In the 1970s Ansoff recognized the problem of "paralysis by analysis"—the overthinking of a problem and subsequent failure to act. He advocated a more flexible approach, based on local conditions and a company's individual cirumstances.

Ansoff's matrix has limitations. Because it focuses on market potential and strategies for growth, it is not able to support other factors and scenarios, such as the resources available, or if a company's priority is survival rather than growth. However, used with other marketing tools, it remains valuable and is still used to gauge actual and expected growth.

> As companies became increasingly skillful strategy formulators, the translation of strategy into results … created paralysis by analysis.
> **Igor Ansoff**

IF YOU'RE DIFFERENT YOU WILL STAND OUT

CREATING A BRAND

IN CONTEXT

FOCUS
Brand creation

KEY DATES

1850s During the industrial revolution products are mass-produced for the first time, so supply outstrips demand.

1880s and 90s In the US and Europe, brand names—including Coca-Cola, Kelloggs, and Kodak—become popular for promoting products.

1950s TVs become popular in the home, providing a new way for companies to send sales messages to the mass market.

2002 The average number of brands in a US supermarket is 32,000, compared to 20,000 in 1990.

2013 Brand advocates—members of the public who recommend products or services online—are estimated to number 60 million in the US alone.

Brands are how organizations make their product or service stand out from the competition. In ancient times, cattle and slaves were branded to show ownership, and in the Middle Ages paper manufacturers could be identified by a watermark in the paper. However, our modern idea of the brand—which includes every part of the perceived identity of a company, from logo to affiliations—did not emerge until the mid-to-late 19th century.

The increasing number of middle-class, literate consumers in Western societies were able for the first time to choose from a range of items rather than buy from necessity. In the US and Europe, as the supply of packaged goods continued to grow, manufacturers saw the importance of differentiating their products. Coca-Cola launched in 1886 with its name in a distinctive script, backing up the brand 30 years later with a now-famous contoured bottle. Quaker Oats used a man in Quaker clothing on its 1896 advertisment, holding a package of oats in one hand, and a scroll saying “Pure” in the other. Clothing manufacturers such as Levi’s began to stamp their name on products. These companies were seeking to build a direct relationship with the customer.

> Products are made in the factory, but brands are created in the mind.
>
> **Walter Landor**
> **German brand expert**
> **(1913–95)**

The dawn of advertising

Brands took off in the 1950s, when there was a postwar boom in mass production and televisions became a common item in homes. Businesses such as Unilever and Procter & Gamble began to create identities for otherwise indistinguishable soaps and laundry detergents. They needed to package their product so that consumers would reach for it



A person or company has an idea that is **different**.

Vision and values form part of the idea.

These are integrated into one “**personality**” for the product or service.

In this way, the idea and all its elements **become the brand**.

Packaging and promotion **communicate and reinforce** the brand image.

The brand stands out because its positive differences from the competition are clear.

See also: Finding a profitable niche 22–23 ▪ Stand out in the market 28–31 ▪ Understanding the market 234–41 ▪ Make your customers love you 264–267 ▪ Generating buzz 274–75 ▪ Feedback and innovation 312–13

easyJet
easyJet.com
easyJet

The "easy" brand began as an airline, but its brand essence—"more value for less!"—has been successfully applied to more than a dozen businesses, from pizza delivery to office-space rental.

first. With the rise in self-service stores and supermarkets, brands had to catch the consumer's eye on the shelf and also appeal on an emotional level. Persil, for example, played on a housewife's pride in the whiteness of her laundry with the slogan: "Get your whites right."

Creating a brand

Today, a brand is more than just a logo or attractive packaging. Brand creation has to start with an idea, and the idea is more likely to be successful if it is different than the competition's. Typically, it starts with the customer and what they want or need. It might also be based on the way the new company or product is fulfilling a gap in the market. Pret A Manger, for example, launched its healthy fast-food cafés as an alternative to the ubiquitous burger chains. The brand revolves around the concept of fresh, additive-free food prepared daily at every branch. Alternatively, a new product might be something that improves on the existing technology through new and innovative design, such as Dyson's bagless vacuum cleaners. Or the idea might be something that no one has thought of before, and did not even know they wanted, like the iPad, which has become indispensible to millions.

One of the key things about a successful brand, such as Apple or Dyson, is that they build an affiliated community—people who like iPads or prefer Dysons, and are happy to be identified with the other members of that group. The most powerful brands even have identifiable "nonbelievers"—think Coke *vs.* Pepsi, or Mac *vs.* PC. The sense of belonging to a group that seems to share your own values is a key part of consumer loyalty.

Translatable brands

It is often hard to tell whether the product makes the brand, or the brand makes the product. EasyJet, for example, was a simple idea. Company founder Sir Stelios Haji-Ioannou wanted to make air travel easy, cheap, and different than the large airline approach. The "easy" brand, which started in the UK with the launch of an airline in 1995, is now used by more than a dozen different businesses all over the world. The "easy" idea had many different elements that brought it to life—from the way people book their tickets online to the no-frills service onboard—but the essential idea of selling a basic service at an affordable price was translatable to many other forms of business.

> “A product can be quickly outdated; a successful brand is timeless.”
>
> **Stephen King**
>
> **UK advertising executive**
>
> **(1931–2006)**

Vision and values

The different elements that make up a company's vision and values are integrated to create a brand's personality. Companies look to this "personality" to provide the Unique Selling Proposition (USP) that will make their product or service stand out from the competition, while » the individual values and vision take the brand from an idea on a piece of paper to a commercial reality. The vision for the company reflects where the founders or directors want to take the idea. The vision of the furniture store IKEA, for example, is to create "a better everyday life for the many people." The business idea that supports this vision is to offer good-quality furniture at affordable prices. IKEA has become a global brand because all aspects of their business support this idea, from the unique layout of the shopping environment—such as family-oriented restaurants and children's play areas—to advertising. Today IKEA is the world's largest furniture retailer.

What kind of brand?

Values are another subtle element of the brand, and summarize what the brand stands for. It is important that companies don't just state their values; they should be reflected in the way the company operates.

The three founders of the fruit-smoothie company Innocent, which started life at a British music festival in 1999, decided they wanted one of the key values of their innovative company to be openness. Each fruit drink carries a label inviting customers to "call the bananaphone" with their views, or to drop in to the company headquarters, Fruit Towers, at any time. The Innocent website also invites visitors to join the Innocent "family" and make suggestions for what the company should do next, "as we sometimes get confused." Their chatty, informal approach suggests that the company prioritizes openness and dialogue with customers, whose values and opinions it respects. The tone of language, informal website, and quirky offices at Fruit Towers also help create Innocent's personality, conveying a bold, irreverent brand.

> A brand that captures your mind gains behavior.
> A brand that captures your heart gains commitment.
> **Scott Talgo**
> **US brand strategist**

The third place

Howard Schultz, who built Starbucks into a global brand, had the idea of a coffee company with a distinctive personality that could create a sense of connection. When Schultz joined in 1982, Starbucks was a single store in Seattle selling fresh-roasted, whole-bean coffees. The name, taken from a character in Melville's *Moby Dick*, evoked the seafaring tradition of early coffee traders. Schultz traveled to Italy the following year and observed that in Italian coffee bars, coffee was more than just a hot drink: it was an experience that sparked daily exchanges. He decided to bring the Italian coffeehouse tradition back to the US, where he had seen limited casual social interaction.

The concept of the "third place" was born—a place between work and home where you can enjoy conversation and a sense of community. This idea became an essential part of the brand and was carried through in the café design:

Anita Roddick

Born to an Italian immigrant couple in an English seaside town in 1942, Anita Roddick described herself as a "natural outsider." She started The Body Shop, a retail cosmetics and beauty business, in 1976, with one store in Brighton. Drawing on her own diverse experience and travels in Europe, Africa, and the South Pacific, she created natural cosmetic products in recyclable bottles. The Body Shop went on to shape ethical consumerism because of Roddick's personal drive and the campaigns that were promoted within her stores. Roddick's firm belief was that businesses have the power to do good, and she pioneered the prohibition of animal testing for cosmetic products, pushed the adoption of fair trade, and lent business support to political causes such as Greenpeace and Amnesty International.

In 2000 she published her autobiography *Business as Unusual,* followed by a series of activist publications. She was made Dame Commander of the Order of the British Empire in 2004. In 2006 The Body Shop was purchased by US giant L'Oreal. Roddick died in 2007.


REVENUE POTENTIAL
Bonding
This is definitely my kind of brand.
Advantage
I can see how this brand fits me better than others.
Performance
How well does it compare with other brands?
Relevance
Does this brand fit my needs and budget?
Presence
I have noticed the brand.
LOYALTY

The brand pyramid was created by the consulting company Millward Brown in the mid-1990s to illustrate the five key stages of building customer loyalty. Revenues increase as customers move from an awareness of the product to complete commitment.

relaxing leather sofas, comfy chairs, and freely available newspapers. In the 1990s, the rise of the coffee bar on street corners became a social phenomenon that spread from North America to Asia, Europe, and beyond, because they met people's needs for a friendly gathering place.

Ethics and branding

Anita Roddick started the cosmetics store The Body Shop in the 1970s when her husband was traveling across the Americas, and she needed to support herself and her family while he was away. She had little business experience, but had a gut instinct that her products had to be different to sell. Mass production had brought choice to consumers, but interest in the sourcing of ingredients, how products were made, and broader ethical issues was growing. Roddick sold natural products in refillable bottles, and aligned the brand with a number of causes. The Body Shop became globally successful because it was uniquely associated with social responsibility; respect for human rights, the environment, and animal protection; and fair trade for suppliers. Despite the strength of branding, there has been a backlash against the dominance of some brands. Naomi Klein's 1999 book *No Logo* sparked the no-brand movement, which highlights globalization and the exploitation of workers in less-developed countries who make branded goods, such as sneakers.

Japanese retailer Muji has consistently followed a no-brand strategy. At the heart of its ethos is *kanketsu* ("simplicity"). Product packaging is plain and the company spends little on marketing of advertising, relying on word of mouth. Ironically, this has served to differentiate the company and its products, creating a loyal following.

Today, technology is changing the way that consumers perceive brands. Social media and the Internet encourage consumers to share feedback and interact. Big global brands, such as Apple, can influence consumer behavior and have the potential to change society. But organizations also recognize that consumers have greater choice than ever before, and are focused on creating brands that can engage with them on a personal level. ■

STARBUCKS COFFEE

The Starbucks brand is instantly recognizable. In the 1990s Starbucks marketed itself as a relaxing spot between work and home, as well as a place to drink fresh coffee.

THERE IS ONLY ONE BOSS: THE CUSTOMER

MAKE YOUR CUSTOMERS LOVE YOU

IN CONTEXT

FOCUS
Customer loyalty

KEY DATES
1891 Trading stamps are introduced in the US to encourage repeat shopping. Customers are rewarded with stamps that can be collected and redeemed for goods.

1962 Sam Walton opens Wal-Mart, with the slogan "Satisfaction Guaranteed."

1967 The first toll-free 1-800 customer service centers are launched in the US.

1981 American Airlines offers the industry's first frequent-flyer program to reward customer loyalty.

1996 With the growth of the Internet, live-chat and email customer support is introduced for online shoppers.

The idea that the customer determines how successful a business becomes has been accepted by numerous entrepreneurs and management experts since the late 19th century. Logically, if customers are happy with a product or service they will make repeat purchases and give recommendations to their friends and family. This helps the business to grow, and in effect pays the wages of employees.

Like any love affair, the intensity of a relationship between supplier and buyer is emotional as well as physical. The process involved in building passion and trust between the two parties

See also: Porter's generic strategies 178–83 ▪ Understanding the market 234–41 ▪ Focus on the future market 244–49 ▪ Promotions and incentives 271 ▪ Maximize customer benefits 288–89 ▪ Fulfilling demand 294–95


Customers will reward **good quality and service** with brand loyalty.
Therefore companies must **give customers what they want**...
...if they are to cultivate a **loyal customer base**.
There is only one boss: the customer.

> Exceed your customers' expectations. If you do, they'll come back over and over.
> **Sam Walton**

requires not just creativity on the part of the business to promote an emotional connection with the customer, but also practical know-how to ensure streamlined production and distribution systems. These practical aspects include such things as: order cycle time; availability of products; convenience of ordering; flexibility of delivery times; the look of the packaging and the ease of opening it; the simplicity of the returns process; and the accessibility of customer service personnel to deal with problems or questions.

Customer satisfaction

Historically, the process of wooing customers took place face-to-face on the store floor, and department stores led the way at the turn of the 19th century. Selfridges in London was designed from scratch to give shoppers, especially women, a rush of excitement. The store not only offered desirable products to buy, but a complete experience that allowed customers to fantasize about a more luxurious lifestyle.

One of the most powerful emotional drivers in wooing a customer is money—the promise of getting more for less is hard for most people to resist. Coca-Cola is credited with introducing the first such enticement in 1887, with a coupon for a free glass of cola.

In the case of Wal-Mart founder Sam Walton (1918–92), saving the customer money was at the core of his business plan and this strategy is credited with making him one of the most successful merchants of the late 20th century. "The idea was simple," he explained. "When customers thought of Wal-Mart, they should think of low prices and satisfaction guaranteed. They could be pretty sure they wouldn't find it cheaper anywhere else, and if they didn't like it, they could bring it back."

The importance of quality

The quality of the product or service being sold is another emotional force for customers. Unlike price, which must be consistently kept low for sustained customer commitment, quality »



Selfridges department store was a destination as well as a place to shop. It featured cafés and a roof garden, and Harry Selfridge exhibited items such as John Logie Baird's television in the store.

must be kept high for a long and happy marriage between producer and end user. The founder of Selfridges, Harry Gordon Selfridge, advised: “Remember always that the recollection of quality remains long after the price is forgotten. Then your business will prosper by a natural process.”

In the early 1980s, industries first quantified the impact of product quality on profitability through studies such as PIMS (Profit Impact of Market Strategy). Before this time, “quality” was not usually a high priority for industry leaders, but as research continued to show the clear link to profitability, product quality became an essential factor in strategies for attracting and keeping customers.

Customers are willing to line up for bargains, such is their loyalty to particular brands. In Italy, shoppers wait outside a Burberry store in Milan on the first day of the sale.

Paying a premium

Even though a company may not have the biggest share of the market, it can still generate the biggest profit if its customers perceive the product quality to be so high that they are willing to pay more for it. In the smartphone market, for example, Apple’s iPhone has a relatively small share but garners around 50 percent of the profit. Making a desirable product and building an emotional experience around it can be enough to make customers love you—so much so that they are prepared to pre-order, wait, and line up. This is demonstrated most clearly in the fashion world, where customers willingly suffer the indignity of scrambling for limited-edition handbags or shoes, or—in the case of luxury brand Hermès—wait years for a bag. However, for most businesses this is the exception.

Customers expect providers of goods and services to do everything possible to win them over and keep them happy through all the stages of the buying process. Although acquiring new customers is always an important part of marketing strategy, more income is usually generated by existing customers. These customers will continue to buy the same product or service, or may begin purchasing other products from the same provider. The business world has come to recognize that some customers are more profitable than others, and it pays to woo profit-inducing customers and entice them to spend more.

The Likert scale, created by US psychologist Rensis Likert in the 1930s, is designed to measure attitudes. The five-point scale offers responses to a statement, and participants pick the response they most agree with. Considered a good way to get customer feedback, the scale has been criticized for giving skewed results due to its forced set of choices.



In online retail, repeat purchase can be encouraged by email campaigns tailored to the buying history of the customer. In the mail order or direct mail industry, mailings with special offers or cross-selling promotions for complementary products serve a similar function, while in a store the astute involvement of the sales staff can directly provide an emotional rationale for an additional sale, though they are also a cost to the business. Making your customers love you therefore hinges on both the quality of the product or service and the benefits for the customer in remaining loyal to a particular brand or company, whether that's for convenience, a bargain, or a feel-good factor.

Cultivating loyalty

Pioneered by the airline industry with its frequent-flyer programs, the idea of loyalty programs is especially important to retailers. A successful loyalty program will not only offer customers a "money-back" type of incentive, but will also enable the business to gather data about customer preferences, spending habits, favored brands, and reaction to promotions. Retailers use this data to make decisions about what products to stock. Through its loyalty program, US department store Nordstrom records the size and color preferences of customers, as well as birthdays, anniversary dates, and other personal information. It offers "Fashion Rewards"—points earned for every dollar spent with its store card. When a customer has accumulated a certain number of points, they receive "Nordstrom Notes," which can be redeemed against future purchases. Many other stores around the world run similar loyalty programs.

> The customer can fire you by simply deciding to do business elsewhere.
>
> **Michael Bergdahl**
>
> **US director for people, Wal-Mart**
>
> **(1954–)**

Online challenges

Retailers who exist online potentially have more to gain from loyal customers, but first they have to overcome the lack of an immediate emotional connection provided by the ambiance of a physical store.

For example, Zappos, the online shoe seller, uses its call center to forge relationships with customers and win their loyalty. For founder Tony Hsieh the call center is not a running cost, but an opportunity to market. Call center employees do not read from scripts—they seek to make an emotional connection with customers. Their reputation for going out of their way for customers is now enshrined as part of the brand. Simple tactics such as sending goods ahead of schedule, and a 365-day returns period, have helped to build a repeat purchase rate reported at about 75 percent.

CEO of Amazon Jeff Bezos paved the way for the development of customer satisfaction in the digital era. Bezos was able to overcome some of the potential stumbling blocks of Internet retailing, such as customers not being able to touch the products and having to wait for delivery, since its customer service includes next-day delivery and free returns. The company has consistently ranked at the top of the American Customer Satisfaction Index. As Bezos asserts, "If you make customers unhappy in the physical world, they might each tell six friends. If you make customers unhappy on the Internet, they can each tell 6,000." ■

Customer loyalty and store cards encourage repeat purchase of products and also provide businesses with the opportunity to gather data about their customers' shopping habits.

Is the customer always right?

Department store owners Harry Gordon Selfridge (1857–1947), who founded Selfridges in London in 1909, and Marshall Field (1834–1906), who in 1865 started the store bearing his name in Chicago, are both credited with coining the phrase, "the customer is always right," which has come to mean that it is cheaper to retain a customer than find a new one. In an era of overblown product claims it was an approach designed to attract the burgeoning middle classes. However, since the 1990s, marketers have adopted a more discriminating approach to customers in the belief that the customer is not always right.

Each customer can be measured by their individual return on investment (ROI) or lifetime value, allowing customer-service efforts to focus on the more profitable patrons. Using ROI, some businesses differentiate between customers who are always right and those who are not worth listening to.

WHITEWASHING, BUT WITH A GREEN BRUSH

GREENWASH

IN CONTEXT

FOCUS
Business ethics

KEY DATES
1985 Scientists announce that they have discovered a hole in the ozone layer.

1986 First use of the term "greenwash" in an essay by US environmental activist Jay Westerveld.

1990 By the 20th annniversary of Earth Day, a quarter of all new household products coming on to the US market are advertised as "recyclable," "biodegradable," "ozone friendly," or "compostable."

1992 The Federal Trade Commission, in association with the US Environmental Protection Agency, publishes "Guidelines for Environmental Marketing Claims."

1999 The word "greenwash" enters the *Oxford English Dictionary*.



When an **environmental issue** or disaster becomes public knowledge, many consumers want to help by **shopping responsibly**.

To **attract** these customers…

…Company A implements **fundamental environmental reforms**.

…Company B makes minimal changes in order to **claim green credentials**.

…Company C misleads the public on its **environmental policies**.

Some companies take **environmental issues seriously**.

Some companies use environmental issues as a marketing tool—whitewashing, but with a green brush.

See also: Crisis management 188–89 ▪ Avoiding complacency 194–201 ▪ Morality in business 222 ▪ Creating an ethical culture 224–27 ▪ The appeal of ethics 270

The notion of "greenwashing" emerged during the rise of the environmental movement in the 1990s, and it refers to the perceived practice by corporate and government sectors of adopting an environmentally friendly veneer. In the same way that public-interest issues are described as "whitewashed" when they gloss over difficult aspects or cover them up, so "greenwashing" is defined as putting a surface gleam over environmental topics to detract from any serious discussion or definitive action.

Environmental activist and New Yorker Jay Westerveld was the first to use the word in print, in a 1986 essay about the practice of hotels asking guests to avoid using too many towels, in order to reduce laundering and help the environment. Westerveld interpreted this as a ploy to save money rather than the planet.

Growing movement

Until the 1980s, business managers mostly treated environmental issues as potential obstacles to be circumvented or public relations problems to be solved. However, in 1985, news of the hole in the ozone layer led to a successful consumer boycott of aerosols propelled by chlorofluerocarbons (CFCs), which were considered one of the main threats to the ozone layer. As the ground swell of consumer support for the environmental movement grew, marketers saw an advantage in aligning their products and corporate identity with green issues.

The marketing world first seemed to embrace the concept of safeguarding the environment after the release of the Brundtland Report in 1987 (see box). The 1990s were forecast as heralding a green revolution, and businesses rushed to associate themselves with environmentally friendly products and processes.

Green companies

Businesses such as The Body Shop and Volvo had already adopted green strategies as early as the 1970s, and because the media were looking for stories with an environmental angle, these companies frequently appeared in the press. Their publicity made the adoption of green policies and products even more alluring.

At the same time, there was growing evidence that consumers did not believe everything they read or saw and had developed a general scepticism about the business world's green intentions. However, the corporate world still saw a commercial advantage in being green, and marketers began to adopt strategies to try to connect with eco-aware consumers.

Greenwashing has appeared in surprising places. The nuclear industry has tried to dispel its reputation for being dangerous by presenting nuclear power as a remedy for global warming. Arms manufacturer BAe announced in 2006 that it was making "lead-free bullets." Marketers need to remember that the public is generally able to distinguish between policies and practices that are genuinely eco-friendly, and those that are simply greenwashing. ▪

Shades of green

In the years after the release of the 1987 United Nations Brundtland Report calling for protection of the environment, the volume of green advertising and campaigns increased dramatically. Between 1989 and 1990, green product launches in the US doubled. They continued to expand through the early 1990s, buoyed by market research showing that consumers were interested in environmentally responsible products.

By the mid-1990s, however, several key studies revealed that there was an inconsistency between consumer intent and consumer action when it came to paying higher prices for green products. There were also worries over the negative effect that green strategies might have on the attitudes of shareholders.

These factors may have led to a form of greenwashing where organizations make genuine but minor changes to products or processes to present a green face, but do not let environmental issues dent the bottom line.

> "The incidence of … greenwash—outright, purposeful untruths … is probably not that high. But there's an awful lot … that gets close."
>
> **Andrew Winston**
>
> **US environmental strategist**



PEOPLE WANT COMPANIES TO BELIEVE IN SOMETHING BEYOND MAXIMIZING PROFITS

THE APPEAL OF ETHICS

IN CONTEXT

FOCUS
Business ethics

KEY DATES

1867 Karl Marx claims that capitalism was built on the exploitation of labor.

1962 US president John F. Kennedy outlines the Consumer Bill of Rights: the right to safety, the right to be informed, the right to choose, and the right to be heard. This is extended and adopted by the United Nations in 1985.

1988 The Fairtrade Foundation is launched.

2008 A study in the journal *Psychological Science* claims that humans are neurally programmed to prefer fair treatment.

2012 The London Olympic Games restricts its food retailers to using only Fairtrade brands of tea, coffee, sugar, wine, chocolate, and bananas.

The appeal of ethics is based on a basic human preference for a fair deal. Business ethics—the moral principles and rules of trade—has been an area of study since the early 1900s. Early attention focused on workers' rights and conditions, and whether they were paid a "fair wage." In the 1960s, consumers also demanded rights too, and they wanted to know more about a company's reputation and approach.

However, it was not until the 1980s that ethics began to be reflected in the market, with the founding of the Fairtrade Foundation. This introduced a labeling system for products that had been produced and traded without exploitation. It gave consumers the ability to choose products on ethical grounds when making a purchase.

Mayan coffee sold under the Fairtrade label provides consumers with a guarantee that coffee farmers have been fairly paid for their product.

From the 1990s, as corporations pursued globalization strategies and increasingly outsourced production to low-wage economies, consumers became more aware of the issues involved, and the implications of their buying choices.

Unilever publicized its ethical goals in its 2010 "Sustainable Living Plan," which promised it would halve its environmental footprint and source all of its raw products sustainably by 2020. Others have since followed suit. Although consumers know that some companies may fail to make good on these kinds of promises, they often choose to believe them, because, as Facebook founder Mark Zuckerberg observed, "people want to use services from companies that believe in something beyond simply maximizing profits." ■

See also: Play by the rules 120–23 ■ Morality in business 222 ■ Creating an ethical culture 224–27 ■ Understanding the market 234–41 ■ Greenwash 268–69

EVERYBODY LIKES SOMETHING EXTRA FOR NOTHING

PROMOTIONS AND INCENTIVES

IN CONTEXT

FOCUS
Marketing incentives

KEY DATES
1895 Postum Cereals in the US introduces "penny-off" coupons to promote its cereal.

1912 The offer of "a prize in every box" is used to tempt US customers to buy Cracker Jack popcorn.

1949 US grain producer Pillsbury devises a marketing campaign based around a product-linked cooking competition.

1975 The "Pepsi Challenge Taste Test" helps the soft-drink brand outsell Coca-Cola in supermarket sales.

1992 Electrical goods maker Hoover offers a free flight to any UK customer spending $160 (£100) on a product. The offer is so popular that it costs the company almost $79 (£50) million.

Marketers often use the offer of a free gift, prize, discount, or bonus to sway customers into buying merchandise. This strategy is known as "incentive marketing" or "sales promotion." It is commonly used to launch a new product, regenerate interest when sales growth is flat, or to help build the company's reputation or brand.

US industrialist William Wrigley was a pioneer of incentives aimed at encouraging purchases. In 1892 he started marketing his chewing gum offering gifts, or "premiums," to successfully woo customers away from the established brands. It was a tactic he returned to often to stimulate sales growth.

Push and pull

In modern marketing terminology, Wrigley used "pull" incentives: gifts or price reductions that stimulate consumer demand, so that retailers are forced to stock more of the product. Marketers can also use "push" incentives: these are compensations targeted toward the retailer or wholesaler, so that they will, in turn, direct consumer attention toward certain products.

Both push and pull incentives can cause a short-term lift in sales, but over time their impact wears off; promotion fatigue sets in, or the incentives become too expensive. The success of a promotion is measured by looking at return on investment (ROI). When this begins to fall, or the company's reputation suffers from a surfeit of promotions, the strategy is no longer working. ■

> One thing I've learned is that you can't push technology. It has to be pulled.
>
> **Bill Ford**
>
> **US industrialist** (1957–)

See also: Understanding the market 234–41 ▪ Creating a brand 258–63 ▪ Generating buzz 274–75 ▪ Marketing mix 280–83



IN GOOD TIMES PEOPLE WANT TO ADVERTISE; IN BAD TIMES THEY HAVE TO

WHY ADVERTISE?

IN CONTEXT

FOCUS
Advertising

KEY DATES
1729 Benjamin Franklin, scientist and Founding Father of the United States, advertises his company's inventions in the *Pennsylvania Gazette*.

1840 The world's first advertising agency is founded in Philadelphia, PA.

1939 Coca-Cola uses Santa Claus in its ad campaign, helping to create the rotund figure so well known today.

1955 The iconic Marlboro Man ad is launched and is hugely successful, despite research that links lung cancer to smoking.

1994 HotWired becomes the first website to sell banner ads; a year later the first server able to track and manage ads is released.


When a recession begins, consumers cut back.
Makers of Brand A cut advertising spend to bolster profit.
Makers of Brand B maintain or increase advertising spending, risking profit shrinkage.
Profit may be maximized in the short term but customers forget about the brand.
Profit may suffer in the short term but customers stay aware of the brand.
In bad times people have to advertise.

In the corporate landscape advertising is sometimes seen as a waste of money, and expenditure on it is often the first part of the budget to be cut back during a recession. The point that advertising executive Bruce Barton (1886–1967) was making with his much-quoted statement "In good times people want to advertise; in bad times they have to" is that advertising should be employed as part of an ongoing effort to build relationships with existing and prospective customers.

Barton, who was responsible for some of the key American advertising campaigns of the 1920s

See also: Stand out in the market 28–31 ▪ The AIDA model 242–43 ▪ Focus on the future market 244–49 ▪ Creating a brand 258–63 ▪ Make your customers love you 264–67 ▪ Generating buzz 274–75

KitKat
KitKat
KitKat
KitKat
Have a break—have a Kit Kat

Kit Kat advertisements in the UK like this one from the 1960s have used the slogan "Have a break—have a Kit Kat" for almost 60 years. The phrase is now synonymous with the brand.

through the 1940s, believed that cutting advertising spend was foolhardy. Instead he pointed out the advantages of a continual presence in the market through constant advertising. To survive commercial ups and downs, a business needs to maintain a constant presence in the mind of the consumer.

Barton believed that it is a false economy to advertise only when the market is booming and the company has the budget for it, and then to cut back when profit margins are reduced. If a company withdraws from advertising, the consumer may forget about them, making it a tough job to win them back later when the economy is buoyant again.

Building a brand

Barton was not the first to prize the value of advertising in developing an indelible image for a company or product. Thomas Barratt (1841–1914), sometimes dubbed the "father of modern advertising," created a number of campaigns for the UK soap maker Pears in the late 19th century. These advertisements helped make the brand synonymous with soap. While owner Francis Pears was extremely wary about spending money on advertising, Barratt, his son-in-law, was more of a risk taker. He understood the importance of staying in the public arena and of constantly evaluating changing tastes in the market.

An outstanding example of image building through long-term advertising is Nestlé's Kit Kat. Most people in the countries where this slogan was used will probably be able to finish the product's tagline, "Have a break—have a Kit Kat." One reason the slogan is so well known in the UK is that it has been in use since 1957, forming an important part of the brand's advertising and marketing ever since.

Staying power

It could be argued that the company that stops advertising risks disappearing from the public consciousness, perhaps even more so today when most people are bombarded with information and images on a daily basis. Research into viewer reactions to television commercials has shown that even when consumers have been overloaded with information, and are ostensibly uninterested in, or immune to, advertising messages, they are still likely to register positive feelings toward advertisements that reinforce previous brand preferences. This would seem to support Barton's view that effective advertising requires an enduring commitment. ■

> Early to bed,
> early to rise. Work like hell
> and advertise.
> **Ted Turner**
> **US media mogul (1938–)**

Edward Bernays

Remembered as a pioneer of public relations, Edward Bernays (1891–1995) was able to link special events, press releases, and the influence of third parties to promote his client's products.

A nephew of Sigmund Freud, Edward Bernays was fascinated by psychology, often employing psychoanalysts to provide evidence for his campaigns.

He famously conducted a successful campaign for the American Tobacco Company in the 1920s, which radically altered opinion, lifting the taboo on women smoking in public.

Bernays loved competitions and to promote soap for Procter & Gamble he created a soap-sculpting contest for children.

He set up surveys, gathered expert opinions, and arranged business luncheons to change public opinion. Other clients included car manufacturer General Motors and Philco, an early pioneer of television.

Bernays also sought to raise the profile of public relations and establish it as a serious profession in its own right.



MAKE YOUR THINKING AS FUNNY AS POSSIBLE

GENERATING BUZZ

IN CONTEXT

FOCUS
Word-of-mouth marketing

KEY DATES

Early 1970s US psychologist George Silverman pioneers the study of WOMM. He noted the persuasive power of peers within research groups testing new pharmaceutical products.

1976 UK biologist Richard Dawkins articulates how trends spread through a natural process of imitation.

1997 The spread of the webmail service Hotmail becomes one of the first examples of online viral marketing.

2012 Beverage manufacturer Red Bull sponsors Felix Baumgartner to make the highest-ever skydiving jump, which attracts 8 million views of the live feed on YouTube—a social-media record.



Word-of-mouth marketing is the most effective.

Using online communities and social media, marketers can **generate buzz** for their product.

The best ideas “catch on” and **spread quickly**.

Although the catchphrase is contemporary, the idea of “generating buzz” is a long-standing concept in sales. In a sophisticated market populated by savvy consumers who no longer trust most of the messages presented by advertisers, word-of-mouth marketing, or WOMM, has become a vital tool for anyone in business. The strategy is to use the consumer’s own voice—the words of the ordinary person—to do the selling, rather than the voice of the big brand or the omnipotent mass communicator.

Back in 1973, Madison Avenue advertising legend David Ogilvy recognized that ad campaign jingles, catchphrases, and fashions could “catch on” and become part of social culture. “Nobody knows how to do it on purpose,” he believed, though he was certain that word-of-mouth marketing was valuable, calling it “manna from heaven.” He also knew the power of a good laugh. “The best ideas come as jokes,” he mused. “Make your thinking as funny as possible.”

Spreading the message

In the 21st century, WOMM strategies are predominantly used online via social media. Modern marketers are able to purposefully spark word-of-mouth campaigns within online communities, but they also understand the impact of Ogilvy’s advice about using humorous, quirky, and offbeat ideas to get a reaction. Today, people still share their firsthand experiences with friends, but they also share

See also: Understanding the market 234–41 ▪ Creating a brand 258–63 ▪ Why advertise? 272–73 ▪ Benchmarking 330–31

From a single user sharing images or opinions with friends, and those friends passing the data to their friends, with modern technology ideas can spread rapidly and ultimately reach millions of users.



pictures and videos online, so information is easily spread. Tactics to manipulate this trend include guerrilla marketing, which uses low-cost unconventional methods with a surprise element to provoke comment, and viral marketing, which typically employs social media to spread a brand-sponsored video, or encourages influential bloggers and others to recommend products.

In *The Tipping Point* (2000), British social commentator Malcolm Gladwell outlines the power of social epidemics and how the smallest impetus can trigger a mass phenomenon. According to Gladwell, the title of his book refers to a "magic moment when an idea, trend, or social behavior crosses a threshold, tips, and spreads like wildfire." This describes modern "word-of-mouth" marketing, though it originates in broader ideas about how ideas replicate in human culture. As Gladwell explains, "ideas and products ... messages and behaviors spread just like viruses do."

Kick-starting the process

Marketers can mimic this process by encouraging customers or influential members of online communities to kick-start the imitation process and become "brand champions," sometimes by offering incentives in return for reviews and recommendations. Industries in which trends are paramount for success are at the forefront of WOMM online. Fashion e-tailer ASOS utilizes Twitter and Facebook to propagate customer recommendations and provide entertainment. In its 2011 "Urban Tour" campaign, ASOS marketers created videos showcasing the world's best street dancers and in-line skaters. The videos enabled click-through shopping and were platform-neutral to ease their spread on social-media channels.

Sneaker brand Nike has been at the forefront of the trend, producing videos with enough "wow" factor to send them viral. The two-minute "Touch of Gold" video (2008) featured soccer player Ronaldinho showing off his skills wearing Nike cleats. ■

Memes and imitation

In 1976 evolutionary biologist Richard Dawkins put forward the theory that, just as genes are responsible for replicating physical characteristics, cultural information such as ideas, behavior, or style, can also be transferred from person to person. Dawkins referred to this cultural data as "memes." These memes, like genes, can spread, mutate, or die out in society. As Dawkins describes it, "Just as genes propagate themselves in the gene pool by leaping from body to body via sperm or eggs, so memes propagate themselves in the meme pool by leaping from brain to brain via a process which, in the broad sense, can be called imitation."

Marketers have applied the theory to online behavior. An Internet meme can be a photo, image, video, website, word, or symbol, which originates from a single user or group of users and builds momentum when it is imitated by other Internet users. By piggybacking on existing memes, brands can gain massive exposure for relatively little cost.

> Today, the potential to persuade is in the hands of millions...
>
> **B. J. Fogg**
>
> **US behavioral scientist**



E-COMMERCE IS BECOMING MOBILE COMMERCE

M-COMMERCE

IN CONTEXT

FOCUS
Mobile commerce

KEY DATES
1983 US inventor Charles Walton patents the first radio frequency identification (RFID) device, paving the way for m-commerce and near field communication (NFC).

1997 The first m-commerce transaction takes place in Helsinki, Finland, with the installation of two Coca-Cola vending machines that accept payment via SMS.

1999 The first national commercial platforms for m-commerce are launched: i-Mode in Japan and Smart Money in the Philippines.

2007 Nokia launches its first commercial NFC-enabled cell phone.

2011 The Google Wallet app enables stored credit card data to be used for purchases via a cell phone.


Buying and selling on the Internet (**e-commerce**) has grown enormously…
…but so has the market for **web-enabled smartphones**.
The Internet is now accessed by **mobile devices** more often than by desktop devices.
E-commerce is becoming mobile commerce.

The term e-commerce (electronic commerce) refers to all buying and selling done on the Internet. M-commerce (mobile commerce) specifically involves transactions that are made through a mobile telecommunications network. These transactions can range from the small, such as making an eBay purchase, to the potentially huge, such as trading stocks and shares.

M-commerce works in a similar way to e-commerce, with websites and apps adapted or originated for mobile and handheld devices. It can also include direct carrier billing, when purchases can be added to a cell-phone bill. Another function is tap-to-pay, where a customer makes payments using a mobile device that has been installed with credit card information via a program such as Google Wallet.

See also: Reinventing and adapting 52–57 ▪ Understanding the market 234–41 ▪ Lean production 290–93 ▪ Applying and testing ideas 310–11 ▪ The right technology 314–15

> Consumers no longer go shopping, they always *are* shopping.
>
> **Chuck Martin**
>
> **US CEO of Mobile Future Institute**

The customer holds the device against a paypoint enabled with a technology called near field communication (NFC); this establishes a radio connection between the two devices to complete a transaction.

Growth of m-commerce

The value of online sales made on mobile devices is predicted to grow exponentially. North American research specialist Forrester forecasts US m-commerce sales to show compound annual growth of 48 percent in the five years from 2012 to 2017, with the value of m-commerce over the same period increasing by 250 percent on smartphones and more than 425 percent on tablets.

In the UK, which leads Europe in the growth of m-commerce, Barclays PLC expects m-commerce to grow by 55 percent over the same five-year period, while traditional online sales will grow by only 8 percent and in-store sales by 1.6 percent.

Emerging markets

The sudden and explosive growth of m-commerce can be attributed to several factors. Consumer adoption of smartphones and tablets is increasing; more and more people access the Internet with mobile devices rather than with desktop computers; and customers have become more used to shopping on the move, enjoying the convenience and immediacy it provides. People are also placing more trust in the service. Given that the biggest increase in smartphone sales has been in emerging markets such as China, India, and Africa, it is not surprising that these regions are considered growth hubs for m-commerce. In China, expanding ranks of middle-class youths are fueling a rapid expansion of mobile transactions, while in Africa, e-commerce has been virtually bypassed in favor of m-commerce. In some African countries, in the absence of a conventional banking infrastructure, cell phones have created an informal banking system.

In 2007, the leading mobile network provider in Kenya, Safaricom, set up a mobile banking service called M-Pesa. Money loaded onto the phone can be used to make purchases or transfer funds. Currently, M-Pesa operates in Kenya, Tanzania, Afghanistan, South Africa, and India, with plans by Safaricom stakeholder Vodafone to roll out the service internationally. As this example indicates, the long-term implication of m-commerce could be a global cashless society. ■

Mobile banking

The banking sector has helped to power m-commerce from the start, when Merita Bank of Finland launched the first cell-phone-based banking service using SMS in 1997. Since then, the key challenges for developers have been security (providing a safe environment for transactions); technology (developing cross-platform banking apps that will work on any cell phone); and innovation (finding new and improved ways to link digital banking with retail suppliers and provide a personalized service for consumers).

La Caixa bank in Spain has introduced contactless ATMs, allowing customers to withdraw cash with a tap of their cell phone. They can also buy tickets to events, select seats, and show a QR code to access venues. In Australia, Commonwealth Bank customers can make tap-and-go payments at retailers. Mobile banking is evolving so users can make payments irrespective of which bank they use or which retailers they go to.



Using M-Pesa, the cell-phone money-transfer service, is common in Kenya. Funds are transferred by SMS into an electronic wallet on the phone to be used at stores and agents nationwide.

TRYING TO PREDICT THE FUTURE IS LIKE DRIVING WITH NO LIGHTS LOOKING OUT OF THE BACK WINDOW

FORECASTING

IN CONTEXT

FOCUS
Forecasting

KEY DATES

1939 A quantitative method of forecasting is developed, using past sales correlation.

1959 Project RAND, a think tank assembled by the US Air Force, creates the Delphi technique for forecasting using expert opinions.

1970 British mathematicians George Box and Gwilym Jenkins develop a sophisticated model for picking out trends from historical data.

1980s Computerized forecasting models appear, such as INFOREM and E3.

2003 Sunil Chopra and Peter Meindel at Northwestern University, IL, emphasize the link between accurate forecasting and supply-chain management.



Predicting the performance of a product in the market relies on…

…**qualitative analysis** of behavior in the market.

…**quantitative analysis** of sales data.

…simulations of the effect of **external factors** on sales.

However, forecasting can never take **unforeseen events** into account.

Forecasting sales is one of a marketer's most important roles. Other management departments in a company will make critical decisions that affect the entire organization, based on the information that the marketer provides about the anticipated performance of a company's products in the marketplace.

Marketers first suggested the idea of using economic models to forecast regional sales in the 1930s, and from the 1950s onward the idea of quantitative and qualitative approaches emerged. Qualitative forecasting relies on the expertise of managerial staff and their acquired knowledge about market reactions. Quantitative forecasting

See also: Crisis management 188–89 ▪ Balancing long- versus short-termism 190–91 ▪ Contingency planning 210 ▪ The marketing model 232–33 ▪ Lean production 290–93 ▪ Time-based management 326–27

uses numerical data such as sales patterns. Also in this category are equations that make assumptions about future sales by drawing on a company's historical data, and market research that indicates the number of potential customers for a particular product or service. In addition, marketers look at external factors beyond the company's control, such as the state of the economy, and make simulations of how quantitative forecasts would be affected by external factors.

Unforeseen circumstances

Even the most carefully planned forecast can be thrown out by unforeseen events. In the travel industry, for example, it is difficult to predict performance because factors such as weather and world events have a significant impact on customer choices.

The effect of world events can be seen in the sale of luxury watches to China. From 2009 to 2011, high-end watchmakers in Europe enjoyed growing sales in China, but from late 2012 a dramatic decline began—as much as 24 percent in a single quarter. This was partly due to a slowdown in China's economic growth, which exporters might have been able to take into account; but what could not have been expected was a high-profile incident in the Communist Party's crackdown on corruption. A party official in Shaanxi province was fired after images of him wearing various luxury watches were found on the Internet; one timepiece was worth more than $32,000. The story made front-page news across China in September 2012. Luxury watches became publicly associated with corruption, and demand slumped.

> ❝
> The only thing we know about the future is that it will be different.
> **Peter Druckerr**
> ❞

Is forecasting worthwhile?

Management consultant Peter Drucker was scornful of forecasting. "We must start out with the premise that forecasting is … not worthwhile beyond the shortest of periods," he wrote in *Management: Tasks, Responsibilities, Practices* (1973). He had reason to be wary, having declared in a 1929 economic journal that stock prices were bound to keep rising, just a few weeks before the Wall Street Crash. International auditing company KPMG maintains that most companies produce unrealistic forecasts that can be off by up to 13 percent on average.

According to KPMG, better data management, scenario planning, and forecasts that are continually updated rather than made long-term can increase accuracy. Despite the difficulty of accurate forecasting, it remains the primary means by which marketers drive the business decisions of a company. ■

Shares on the stock market are affected by many factors, including some that are difficult to predict—such as world events, severe weather, and global economic forecasts.

Accurate forecasting

Producing an accurate forecast depends on the company's required lead time—the time from order placement to customer delivery. The longer the lead time, the greater the error in forecasting figures. One theory holds that if lead times are reduced by 50 percent, forecasting errors will also be reduced by 50 percent.

Since the 1990s management theorists, including Dr. Edmund Prater at the University of Texas, have advocated that forecasting accuracy can be optimized by creating a demand-driven supply chain, which uses information and technology to shrink lag times between supply decisions and actual demand. Thus the need for forecasting is reduced when business activities become more demand driven. For example, when Wal-Mart asked stores to place orders every two weeks rather than monthly, inventories reduced because accurate forecasting increased in line with the shorter time frame.

PRODUCT PLACE PRICE PROMOTION

MARKETING MIX



IN CONTEXT

FOCUS
Marketing strategy

KEY DATES

1910 Professor Ralph Butler introduces the term "marketing" in the title of his university course.

1920s Marketing becomes further established as a recognized field of study.

1948 James Culliton identifies the idea of the marketer as a "mixer of ingredients."

1953 Neil Borden coins the phrase "marketing mix."

1960 E. J. McCarthy sets out the Four Ps as the ingredients of the marketing mix.

1990 Robert Lauterborn advocates the Four Cs in place of the Four Ps.

2013 Philip Kotler keeps the Four Ps alive, adding a fifth P—Principle.

The marketing mix concept is a theoretical framework designed to help businesses plan, and put into practice, effective strategies for launching and selling their products and services. The crystallization of goals helps define a clear role for the marketer, separating the marketing function from other activities within a company.

Businesses need to consider a number of factors when bringing a product or service to the market. They must make decisions about aspects of the product (such as its type), its place of distribution, price, and promotion. These factors are the "ingredients" that together make up the "marketing mix" and

See also: The marketing model 232–33 ▪ Product portfolio 250–51 ▪ Promotions and incentives 271 ▪ Fulfilling demand 294–95 ▪ Quality sells 318–23



When an organization decides to **launch a new or updated product,** marketers must figure out the **selling strategy**.

They must carefully calculate the **proportions of the elements** (such as product, place, price, promotion) in the **marketing mix**.

They must also consider the **external market forces** that affect the marketing mix.

The marketer must **weigh the forces** and **juggle the elements** within the constraints of the **resources available**.

each can be adjusted by the marketer to influence the reaction of the consumer to the product or service being sold. The marketer must also take into account external market forces, such as customer behavior or competition, which will have an impact on the marketing mix.

Building the mix

Harvard Business School professor Neil Borden first coined the term "marketing mix" in 1950, using it in 1953 in his presidential address to the American Marketing Association. Borden credited fellow professor James Culliton as being the first to introduce the idea of the marketer as a "mixer of ingredients" in 1948. Inspired by Culliton's ideas, Borden began using the term to describe what Culliton's "mixer of ingredients" should design.

In an article in 1964 titled "The Concept of the Marketing Mix," Borden advised that when marketing managers build a marketing program, they should make two lists: the first one itemizes the important elements or "ingredients" that make up marketing programs; the second outlines the external forces that may have a bearing on the first list.

The first list includes ingredients deemed essential if the company is to win sales—product planning, pricing, branding, distribution, promotion, and so on. The second list includes market forces, such as the behavior of consumers, retailers, competitors, government policy, and other external factors.

> “The marketing manager, as head chef, must creatively marshal all his marketing activities to advance the short and long term interests of his firm.”
>
> **Neil Borden**

In Borden's model, the marketing manager should weigh the effect of external forces, then juggle the marketing elements from the first list to achieve the best possible program to fit the resources of the company. Borden advocated that to really get a grasp of all the marketing considerations, the manager should draw up a chart showing the elements of the marketing mix.

Both Culliton and Borden inspired further development of the concept within the academic community. In 1960, a marketing professor at Michigan State University, Edmund Jerome McCarthy, set out what would become the definitive word on the marketing mix. He condensed the mix ingredients into an easily remembered mnemonic, the Four Ps: Product, Place, Price, Promotion. In his classic text, *Basic Marketing* (1960), McCarthy elaborates on »

The Four Ps, key ingredients of the marketing mix, need to be in careful balance with each other and the mix as a whole. Alternative "ingredients" have been proposed as necessary components of the marketing mix, but the core Four Ps have endured.



THE MARKETING MIX

PRODUCT
Evaluate customer needs; establish where and how the product will be used; decide on branding and packaging, and how the product will differ from others in the market.

PLACE
Decide how the product will reach the market; the channels of distribution; methods of storage; handling and transportation; and how to emulate or differentiate from the competition.

PRICE
Set the price point based on market norms; perceived value by the customer and how sensitive they are to price; and competitors.

PROMOTION
Look at when and where to reach the target market; the optimum medium (television, radio, or press); and evaluate the techniques of competitors.

the nature of the Four Ps. "Product" refers to developing the right product or service for the target market, whether it is a laundry detergent, an accountancy service, or a political party's policy, and also includes branding, packaging, warranties, and anything else related to the product offering. "Place" refers to how the product will get to the target market, so it is available when and where it is needed—in other words, the channel of distribution and the logistics of transportation, storage, and handling. "Promotion" is communication about the product with the target market and others in the distribution chain—public relations, advertising, sales promotions, and so on. "Price" includes price-setting based on competition within the market, the cost of the entire marketing mix, and what price level the customer will accept. If price is rejected then the marketer's efforts are wasted.

An enduring formula

From the 1960s, the Four Ps became the undisputed means by which marketers made their strategic decisions. The approach has become an institution, mentioned in almost every marketing textbook, and still dominates management thinking. Other additions or alternative mixes have been proposed, though none has yet replaced McCarthy's original premise.

In the 1990s, for example, advertising professor at the University of North Carolina, Robert Lauterborn, argued that the Four Ps articulated the seller's view rather than the buyer's view, and was therefore outdated in the customer-centered marketing of the late 20th century. He reimagined the Four Ps as the Four Cs: Customer solution, Convenience, Communication, and Customer cost.

Professors Jagdish Seth and Rajendra Sisodia then posited the Four As: Acceptability, Affordability, Availability, and Awareness. By 2005, academics Chekitan Dev and Don Schultz claimed that the Four Ps were no longer relevant; that consumer decisions were motivated by emotion and a desire for value, rather than for a specific product to fill a need or a particular price point. Other commentators have also pushed for a framework more applicable to e-commerce. On the other hand, Carolyn Siegel, author of *Internet Marketing*, states: "Although many attempts have been made to replace or expand the

> Marketing mix is the pack of four sets of variables, namely product, price, promotion, and place variables.
> **E. J. McCarthy**

> Marketing mix represents the setting of the company's marketing decision variables at a particular point of time.
> **Philip Kotler**

Ps, they've endured as an effective method for organizing the major tactical tools marketers can deploy in a competitive marketplace."

The four Ps in practice

In an industry such as fashion, which by its nature needs to be forward thinking and to embrace e-commerce and m-commerce, the Four Ps are still in evidence. To cater for the immediacy demanded by fashion-conscious customers, UK street-wear fashion brand Bench has focused on "Place"—in this instance the speed at which the product can reach retail outlets. Rather than relying on the usual trade-show route and showroom invitations, Bench uses a more direct approach. Sales people take samples to retailers, and send orders directly to headquarters while still with the retailer. An automated system then generates purchase orders to the manufacturing site within hours. From the customer's point of view (both individual consumers and retail outlets), styles arrive quickly, keeping the brand fresh. For the company it means greater efficiency, more accurate revenue forecasting, and a greatly reduced risk of being overstocked at the end of the season.

The marketing mix of fashion chain Zara embodies the Four Ps. Because of an emphasis on "Place" (distribution), new products are delivered twice a week, and there are only 10–15 days from the sketching of a new design to the item's arrival on the store floor. Such a streamlined approach to "Place" means that "Product" reflects immediate trends; "Promotion" happens on the instant channel of the Internet; and "Price" is kept low due to the emphasis on "Place."

Marketing guru Philip Kotler has acknowledged alternatives to the Four Ps, but maintains that they still make a useful framework. More recently, in 2013, he suggested a fifth P—Purpose. This is not only the purpose of a business to make money, but also a higher purpose of being a good corporate citizen. This fifth element is a concept embraced by Zara, a company that has kept 50 percent of manufacturing in Spain rather than subcontracting it to Asia. Not only can the business react more quickly to changing fashions, it can also be applauded for keeping employment local. ■

Marketing pioneers

Neil Borden recognized the importance of creating a marketing methodology—a set of stated intentions for marketers to follow. When he put forward his marketing mix concept in 1953, he drew on theories developed by earlier marketing thinkers.

Ralph Butler, professor at the University of Wisconsin, pioneered the use of the term "marketing" by developing a course on selling called "marketing methods" in 1910. A few years later in 1915, H. W. Shaw wrote *Some Problems in Marketing Distribution*, in which he identified the tasks of production and distribution.

Paul Cherington and Paul Ivey, among others in the 1920s, further consolidated marketing as a field of scholarly pursuit, laying the groundwork for marketing as a college course in its own right. In the 1920s and 1930s, Paul Dulaney Converse described key elements of the marketing mix—distribution, pricing, and advertising—and emphasized the need to coordinate marketing activities.

Fashion store Zara concentrates its marketing mix on "Place." It is able to deliver new designs to its store floors in just under two weeks.

DELIVER THE GOO

PRODUCTION AND POSTPRODUCTION

ING
DS



Market globalization and fast-paced technological change have raised customer expectations, and companies can succeed or fail depending on their ability to deliver the right goods at the right price, at the right time, via the right distribution channels.

If getting it wrong can be costly, getting it right takes time. It means constantly evaluating every part of the production process to see where it can be made more efficient without a perceived drop in quality or sales. Henry Ford was the first industrialist to recognize the value of offering customers "more for less," and made it his business to make improvements to his cars every year, while simultaneously dropping their price. Today, many use a "low cost, good quality" strategy to attract customers, especially during times of recession.

Low-cost efficiency

One of the most effective ways of lowering costs while maintaining value is to reduce waste. Known as "lean production," it entails identifying and cutting waste across the process, from production to delivery. Lean production developed from the ideas of Joseph Juran, a management consultant who developed innovative ways of improving quality and efficiency at the same time. In the 1950s, the Union of Japanese Scientists and Engineers invited him to lecture to hundreds of top-level executives, who quickly put his ideas to practical use. Toyota was among the many businesses who implemented his methods. The company's approach ultimately grew into the "just-in-time" production system that is widely used today.

Stock control plays a large part in the "just-in-time" system, and is vital to a balanced cash flow. Too much stock in the warehouse represents money that is doing nothing; if there is not enough stock to meet demand, customers may search out alternative suppliers.

Cost reduction is the holy grail of production managers, and one way to achieve this is to simplify production methods. This involves removing unnecessary and costly steps, or innovating so that stages become faster or less wasteful. Entrepreneur Michael Dell saved time and money by cutting out the retailer and letting customers design their own computers; these were produced to order ("just in time") and sold directly to the end user.

> "Manufacturing is more than just putting parts together. It's coming up with ideas, testing principles and perfecting the engineering, as well as final assembly."
>
> **James Dyson**
>
> **UK inventor (1947–)**

Creativity and innovation

Innovation can come from any part of the business. The Japanese idea of kaizen—meaning continuous improvement—is an ancient philosophy, but it was first used in an industrial setting by Toyota in the 1950s. Founder Elji Toyoda expected all employees—from the factory floor to senior executives—to constantly come up with ideas for improving products or production.

This idea took hold around the world. Companies recognized value in setting up teams to increase creativity. However, large companies often limit innovation—or at least the testing of its validity—to an R&D (research and development)





department. They can focus on the changing needs of markets and respond appropriately, making sure they benefit from the premium price of innovative products, and build a brand loyalty.

More recently, companies have also begun to value the creativity of their customers. Using an approach known as "open innovation," new ideas are welcomed from all sources, and customer feedback is valued in the product-development process. The opportunity for customers to post product ratings and reviews online allows ready access to customer feedback. Some even use online crowdsourcing to refine the design of products.

The rise of "big data"

Computer systems can collect and yield vast amounts of accurate data, which can translate into valuable information about employees, production lines, and markets.

Data collected about customers is often referred to simply as "big data." Customer buying preferences and habits can now be tracked with incredible accuracy—from their movements around a website, to where and how they like to buy products and services, both online and in stores. This gives an accurate picture of their overall market, while also targeting individual customers, offering them products in tune with their preferences.

The cost of quality

Companies aim to satisfy customers to get repeat business and good "word-of-mouth," which can hugely boost sales. Those that operate in the fast-moving-consumer-goods (FMCG) market, selling such things as chocolate, beer, and cereals, rely on quality for creating customer loyalty. In the service industries, following this "added-value" approach can be problematic. If competing companies raise the quality of their product or service to a level that would be unprofitable to match, this would signal the need for new strategic thinking.

However, high-quality goods can last for a long time without needing replacement, and this was a problem addressed by industrial designer Brooke Stevens. He suggested that companies could increase sales by creating in consumers the "desire to own something a little better, a little sooner than necessary." This seems especially true today, when new models of products such as smartphones are produced regularly—well before their predecessors are defunct.

For a smooth, fast route to a high-quality product, companies need to make best use of time and resources. This has led to the development of a way of working known as "time-based management," which involves utilizing time in the same way as raw materials. It is often used with critical-path analysis, which identifies all the stages of a project and puts them into a logical order, saving companies time and money.

Finally, businesses can improve processes and sales by observing the best practice of competitors in their field, using a process known as benchmarking, which takes the "best from the best" so companies can deliver the best products in the best way to satisfy customers. ■

> Improvement usually means doing something that we have never done before.
>
> **Shigeo Shingo**
>
> **Japanese industrial engineer (1909–90)**

SEE HOW MUCH, NOT HOW LITTLE, YOU CAN GIVE FOR A DOLLAR

MAXIMIZE CUSTOMER BENEFITS

IN CONTEXT

FOCUS
Raising quality

KEY DATES
1850 Consumer choice theory is developed by UK economist William Jevons—according to this theory buyers seek out products that offer the best value for money.

1915 US businessman Vincent Astor establishes the first supermarket, in Manhattan, NY.

1971 Businessman Rollin King and lawyer Herb Kelleher set up Southwest, the world's first low-cost airline, in Texas.

1995 The Liberal government in Canada, under the leadership of Jean Chrétien, manages to cut public spending by nearly 10 percent in their attempt to provide taxpayers with more for less.



The customer expects...

...**high-quality goods**.

...**value for money**.

But any **extra features and benefits** included will help to maximize customer satisfaction.

See how much, not how little, you can give for a dollar.

Henry Ford spotted a gap in the market for a mass-produced car that ordinary Americans could afford. The Model T Ford was launched in 1908 and was still selling well nearly 20 years later. During this period, Ford regularly improved the car. For example, the first version of the Model T required the driver to crank the engine by hand to start it, but later models had an electric starter. Ford did not opt to make customers pay more for this better product. In fact, he did the opposite. The price of a Model T Ford fell every year from 1909 until 1916. Ford saw the importance of offering more for less. When cost-savings were made on the production line, they were

See also: Your workers are your customers 132–37 ▪ Porter's generic strategies 178–83 ▪ Lean production 290–93 ▪ Applying and testing ideas 310–11

immediately passed on to his customers by way of lower prices, which helped to boost sales.

Successful companies are able to attract customers by supplying high-quality goods and services at prices the buyer is willing to pay. Companies such as Dollar Tree in the US or Poundland in the UK base their business model on offering their customers as much as possible for $1 or £1—for example, in June 2013 Poundland launched the world's cheapest bra, which retailed at £1. Offering more for less can be an effective business strategy, provided that the price covers costs. Low prices that offer excellent value for money attract customers away from rivals.

More for less

Budget supermarket chains, such as Lidl and Aldi in Europe, have used this strategy to great effect. These businesses have been able to grow their market share at the expense of larger supermarket chains. Since the financial crisis, inflation has regularly outstripped pay raises, and households have responded by seeking out retailers that offer them more for less.

Lidl's supermarkets are basic, with a limited range of products, some of which are displayed on warehouse pallets. However, the products themselves can be of a high quality.

> I don't understand why anyone would hold something up and proudly say, 'I paid more for this than I needed to.'
>
> **Paul Foley**
>
> **Managing director Aldi UK** (1958–)

The secret to Lidl and Aldi's success is not solely due to their low prices. They also offer high-quality products. For example, in 2012, Lidl launched its own designer aftershave called G.Bellini X-Bolt for $6.35 (£3.99). In blind tests the fragrance beat famous brand names, such as Dior Homme, D&G The One, and Hugo Boss Bottled, which cost up to ten times more.

The stores focus on offering good value stock rather than an attractive shopping experience. They offer products on pallets direct from the warehouse, and do not spend time or money displaying their goods attractively. They also do not stock popular brands that shoppers will find elsewhere; most stock comes from less well-known suppliers that the stores can obtain at competitive prices.

The challenge for entrepreneurs is to offer outstanding value for money, while also keeping costs low enough to trade profitably. ■

HYUNDAI
experience Hyundai
i40

Hyundai

The car manufacturer Hyundai is the fourth-largest in the world and the third-largest *chaebol* (conglomerate) in South Korea. Its success is a direct result of its policy of offering customers a good deal at a competitive price.

One way Hyundai has grown its market share is by offering the longest warranties in the auto industry. Long warranties are an obvious selling point, because if a new car breaks down during the warranty period the buyer can return it to the manufacturer, who will repair it free of charge. Hyundai's warranties guarantee the engine for ten years, cover the bodywork for seven years, and offer free roadside assistance in the event of a breakdown for five years. Despite these long warranties, Hyundai still charges relatively low prices for its vehicles.

Hyundai cars are also well equipped. Features such as Bluetooth connectivity, heated side-view mirrors, air conditioning, and LED running lights are all standard. Hyundai competes by offering its customers as much as possible for the price charged.

COSTS DO NOT EXIST TO BE CALCULATED. COSTS EXIST TO BE REDUCED

LEAN PRODUCTION

IN CONTEXT

FOCUS
Waste reduction

KEY DATES
1908 The Model T Ford automobile is mass produced on an assembly line by the Ford Motor Company in Detroit, MI.

1950 W. Edwards Deming trains engineers and managers (including Akio Morita, the co-founder of Sony) in process and quality control in Japan.

1961 Robots are first used on an assembly line at a General Motors plant in Ewing Township, NJ.

2006 US management consultants McKinsey & Company publish an influential report urging governments to apply lean production techniques to the delivery of public services so taxpayers get more for less.

In business, ideas for new products and production techniques tend to emerge during times of crisis when the old products and methods have become unprofitable. This is the case with "lean production," a method of planning for demand by reducing waste, developed in Japan by the Toyota Motor Corporation in the 1950s. At that time, Toyota was a relatively inefficient producer of cars. Like many other Japanese companies, Toyota was struggling to overcome the shortages created by an economy that had been devastated by war. Looking for ideas, Toyota sent a young engineer, Eiji Toyoda, to the US to

See also: Reinventing and adapting 52–57 ▪ The value of teams 70–71 ▪ Creativity and invention 72–73 ▪ Leading the market 166–69 ▪ Maximize customer benefits 288–89 ▪ Simplify processes 296–99 ▪ Time-based management 326–27


Waste is anything that adds to a company's cost which is **not valued by the customer**, including...
...**overproduction**.
...**inventory**.
...**movement**.
...**waiting**.
...**transportation**.
...**overprocessing**.
...**defects**.
Lean producers try to **eliminate these wastes** to boost profits.

visit Ford's Rouge plant in Detroit, MI. Toyoda spent three months studying the mass-production technique pioneered by Ford at the Rouge. On his return, Eiji reported that he was impressed by the scale of production that Ford achieved—the Rouge was so big that it required its own railroad, hospital, and several fire stations. However, he also believed that the factory was riddled with *muda*—the Japanese term for wasted effort, materials, and time. Toyoda and his colleagues set about developing a new production system that sought to replicate the output and economies of scale achieved by Ford, but in a less wasteful manner.

Seven types of waste

Shigeo Shingo, a Japanese industrial engineer who worked with Toyota in the 1970s, identified seven types of waste, or *muda*.

The first type is overproduction. Traditional manufacturers have a tendency to mass produce in advance of sales. These companies try to forecast what they think demand will be for their product, then they make the goods that they expect to sell. The main problem with this system of manufacturing, however, is that it relies on accurate forecasting of demand. If the forecast does not accurately match demand, the company could be left with mountains of unsold stock.

The second example of *muda* is inventory waste. In addition to stockpiles of unsold finished goods, many mass producers keep stocks of raw materials and work-in-progress to reduce the risk of production being halted. Stocks of raw materials are held in case a supplier fails to make a delivery, or to protect against the possibility that some of the raw materials might be defective and unusable. Stocks of work-in-progress, or semi-completed products, are held just in case a machine on the production line breaks down. These can then be inserted into the process to ensure that production continues. However, holding stocks of raw »

Holding goods in stock is a cost for a company, since warehouse space and employees need to be paid for. In addition, cash tied up in stock could be in the bank instead, earning interest.

materials and work-in-progress is considered wasteful because of the associated space and staff costs.

The third type of *muda* that Shingo identified is movement. In some factories, workstations are badly designed, and employees spend time doing things that do not add value to the product, such as looking for tools, walking from one part of the factory to another, or bending to pick up parts. This type of waste increases cycle time—the time taken to produce a unit of output. Longer cycle times lead to lower productivity, which in turn drives up unit labor costs.

The fourth *muda* is time spent waiting. Delays may occur when machines on a production line are poorly coordinated, resulting in bottlenecks. Time might also be wasted resetting machinery to produce a different part.

The fifth *muda* is transportation. Time and money spent moving work-in-progress from one factory to another will drive up costs, and this is unlikely to add value to the product, so it is wasteful.

The sixth example of *muda* is overprocessing. Consumers will only pay for the product features that they value. Producing complex, overengineered products is wasteful because it creates additional costs without any extra revenue.

The final *muda* is the production of defective items. Substandard products signify waste of time and resources, and mean that further inspection processes are required and the products must be reworked.

In addition to the seven types of *muda*, Toyota identifies two other potential problems: *mura* and *muri*. *Mura* is uneven flow in a process, leading to unbalanced working practices. *Muri* is the overburdening of people or equipment.

Lean strategy

Using these insights, production engineer Taiichi Ohno developed the Toyota Production System (TPS). This lean production method counters waste in the production process by producing more using less. It enables a manufacturer to increase output without having to pay for extra labor, raw materials, or capital. Alternatively, a business can use lean production techniques to make a better-quality product that will sell for a higher price.

Muri*, *mura*, and *muda are three Japanese terms identified by the Toyota Production System as problems to avoid. *Muri* refers to the overburdening of individuals or teams, which is inefficient; *mura* means an unbalanced work flow, which can cause bottlenecks in supply; and *muda* are all the areas of waste in a system.



JUST-IN-TIME

A just-in-time supply system eliminates *muri*, *mura*, and *muda* from the production system, so that teams receive materials as they need them and waste is avoided.

Lean producers try to eliminate overproduction and waste stock by using the just-in-time (JIT) system, in which production only happens in response to a customer order. Companies that use just-in-time never produce output for stock, and if there are no orders from buyers, production stops. Thus, production is pulled through by the consumer, rather than being pushed through by the manufacturer. The same principle is extended to raw materials and bought-in components. Lean producers run with minimal buffer stocks, relying instead on daily, or even hourly, deliveries from suppliers. However, the absence of a stock of raw materials means that a faulty shipment of components could bring an entire factory to a halt. So to make just-in-time work, lean producers require reliable suppliers that produce zero defects.

Lead times

If products are to be made to order rather than supplied from stock, there is a risk that a long lead time (the time between an order being made and delivery to the consumer) could result in customer dissatisfaction and consequently falling sales. Therefore, to run lean production effectively, companies need to shorten the cycle time taken to make their products. To accelerate the pace of production, managers will need to control the movement *muda*, the waiting *muda*, and the transportation *muda*. At its simplest, this could be achieved by redesigning workstations and production lines so that employees have all the tools and components to complete the task close at hand. Likewise, bottlenecks in production can be eliminated by deploying more machinery or more labor at the problem area.

> All we are doing is looking at the time line, from the moment the customer gives us an order to the point when we collect the cash.
> **Taiichi Ohno**

Workers on a production line will be much more efficient if all the components they need are within easy reach. Time spent searching for items increases the movement *muda*, which incurs a cost to the business.

Overprocessing

Lean producers tackle wasteful overprocessing, the sixth *muda*, by applying a process called value analysis at the product design stage. Companies using value analysis attempt to identify product features that create cost but have no value for the consumer. If these features can be removed to create a simpler, cheaper product, profit margins will rise. At the same time, revenues should not fall, because the features that have been removed were not valued in the first place.

It could be argued that the business model of a no-frills hotel, as seen in the Malaysian company Tune Hotels, is based on value analysis. For Tune Hotels, affordable rooms are its priority. To achieve this, services that push up the price of a room but are viewed as nonessential by customers, such as air-conditioning or toiletries, have become optional add-ons. The chain focuses solely on core qualitites such as cleanliness and safety, valued highly by the customer.

To eliminate the seventh *muda*, defective products, lean producers seek to create high-quality items. This requires managers to trust workers to spot any fall in quality. Employees have the authority to stop the production line in order to solve the problem, and production only restarts once the source of the problem has been found and fixed.

High product quality, achieved by lean production, leads to lower costs. By solving problems at their source, companies spend less time and money on reworking defective products to bring them up to the required standard. ■

> Regardless of how much workers move, it does not mean work has been done. Working means that progress has been made.
> **Taiichi Ohno**

IF THE PIE'S NOT BIG ENOUGH, MAKE A BIGGER PIE

FULFILLING DEMAND



IN CONTEXT

FOCUS
Stock management

KEY DATES
10,000 BCE Better farming techniques allow the creation of surplus food. Grain is stored for times of scarcity or trade.

4100–3800 BCE Early Sumerian culture develops one of the earliest writing systems in order to keep track of goods.

1889 US statistician Herman Hollerith invents the first machine-read punch card. Merchants who had previously relied on handwritten notes and stock counting can now record complex data.

1974 The scannable, modern bar code is introduced, revolutionizing the ability to manage inventory.

2000s Inventory management software programs can instantly update databases using bar-code readers.



During peak periods, demand **exceeds current production**.

Stock is released to supplement current production.

If the pie's not big enough, make a bigger pie.

The success of a company can depend in large part on the effective management of its stock. Customer demand in most markets varies throughout the year. During busy periods, companies may not be able to produce enough to satisfy consumers. If companies fail to match supply to demand, potential buyers have to find alternative suppliers and sales will be lost. Additionally, once consumers have tried out the opposition, they may switch loyality and never return. Sales may never regain previous levels, even after supply has been addressed, leading to lower profits.

Types of stock

Companies keep stock as an insurance policy—it enables them to deal with sudden surges in sales or a sudden drop in output. In addition to inventories of finished goods, manufacturers may hold stocks of raw materials, to create parts of the

See also: Luck (and how to get lucky) 42 ▪ How fast to grow 44–45 ▪ Avoiding complacency 194–201 ▪ Promotions and incentives 271 ▪ Why advertise? 272–73 ▪ Forecasting 278–79 ▪ Lean production 290–93 ▪ Simplify processes 296–99

final product or to replace defective materials. This strategy ensures that production can continue in the event of a delay from the supplier; companies are more likely to hold stocks of raw materials if their supplier is unreliable. They may also keep stocks of "work-in-progress," or semicompleted products. Work-in-progress stock can keep production flowing even if a machine on the assembly line breaks down.

Stock control

Good stock management balances meeting product demand with minimizing stock-holding costs. If a company runs out of stock, it may have to turn orders away, or deliver late and risk losing returning customers. In 1993 toy manufacturer Bandai was caught off guard by the popularity of its Power Rangers figures, and had to impose a "one figure per customer" rule in the UK until manufacturing could catch up with the huge demand.

On the other hand, if a company is overly cautious and holds too much stock, it incurs unnecessary costs: warehouse space is expensive, and employees are needed to manage it. It can also lose value if it perishes or becomes technologically obsolete. There is also an opportunity cost associated with holding stock; the cash tied up in stock could be earning interest, or be invested elsewhere.

The goal is to hold just enough stock to meet demand, with minimum delay to the customer and at minimum cost to the company. A sophisticated computer program at McDonalds, called Manugistics, helps the chain forecast sales and ensure the correct quantity of stock is ordered for the week ahead.

Buffer stock

Most companies hold buffer stock—stock that exceeds the amount needed to meet current demand. It takes time to replenish stocks, so companies will reorder from suppliers well before their inventory falls below the buffer level. The longer the lead time—the time between placing an order and the goods arriving—the greater the amount of buffer stock needed. If demand is stable and predictable, the need for large quantities of buffer stock is reduced.

Online companies may not need a storefront. However, unless their product can be digitally downloaded, many will still require a physical storage facility, with the same need to manage inventory and keep buffer stock. ■

> Because of our inventory management, Dell is able to offer some of the newest technologies at low prices while our competitors struggle to sell off older products.
>
> **Paul Bell**
>
> **US former senior executive, Dell, Inc.**

Surplus buses and other London and Olympic-themed models went unsold after optimistic oversupply caused a glut in retail outlets.

Hornby

To help recover the nearly $14 (£9) billion cost of staging the London 2012 Olympics, the UK sold rights to produce Olympics merchandise. Hornby paid for the right to produce official 2012 toys, including Corgi models of London taxis and buses, its model trains marked with the Olympics logo, and the Olympic mascots Wenlock and Mandeville.

Hornby produces most of its products in China and India to take advantage of low costs. However, outsourcing production has lengthened its lead times: it takes six weeks to transport freight by sea from China to the UK. Hornby has to supply customers from stock, rather than current production, so sales of Olympic products had to be predicted well in advance.

Forecasts proved to be extremely optimistic. Hornby hoped to make a profit of $3.2 (£2) million from the Olympics. In the end, the contract cost it $2 (£1.3) million. To sell off stock, Hornby was forced to cut its prices by as much as 80 percent, ruining its profit margins.

ELIMINATE UNNECESSARY STEPS

SIMPLIFY PROCESSES



IN CONTEXT

FOCUS
Streamlining processes

KEY DATES
3rd century BCE The Romans mass-produce lamps. Instead of hand making them, they use two-part molds.

1760 The Industrial Revolution begins, moving from hand-production methods to specialized machines.

1730s US statesman Benjamin Franklin writes about waste reduction in industry in *Poor Richard's Almanack*.

1900s Ford revolutionizes car manufacturing with mass production and standardization.

2010 In *The Art of Invention,* US inventor Steven J. Paley states that it is easier to innovate by adding complexity, but the best results come from simplification.

There are several ways that companies can improve their profits: they can increase their revenue, reduce their costs, or use a combination of both methods. If the cost of producing goods or services can be reduced, without negatively impacting revenue, total profits will rise.
A good way to lower costs is to simplify the method of production by removing any expensive and nonessential steps that will not adversely affect the consumer's perception of the quality of the product. More straightforward—and therefore more cost-effective—production methods have been a goal for centuries. An early example

See also: Stand out in the market 28–29 ▪ Creativity and invention 72–73 ▪ Thinking outside the box 88–89 ▪ The learning organization 202–07 ▪ The value chain 216–217 ▪ Lean production 290–93 ▪ Kaizen 302–09



In competitive markets, consumers look for **value for money**.

To reduce the price of their products, companies may choose to **lower their production costs**.

Costs can be reduced by **streamlining processes** or **simplifying products**.

Eliminate unnecessary steps.

of a process that was successfully simplified is steel manufacturing. During the Industrial Revolution, huge quantities of steel were needed to build bridges, ships, and railroads. Steel was in short supply because it was expensive to produce. In Britain, steel had been made in high-temperature, coke-fired furnaces since the 1740s. Small quantities of iron were loaded into small clay crucibles (containers that withstood heat) and placed inside the furnace. After three hours, impurities were scraped from the crucibles, leaving the steel behind.

Simplifying the process

In the 1850s the production method was simplified by the British engineer Henry Bessemer. His so-called Bessemer process did not require crucibles. Instead, the impurities generated from heating iron to create steel were removed from the metal by blowing air through the iron during the production process. Bessemer's simpler production method was more fuel efficient. As a result, the cost of making steel fell from as much as $97 (£60) per ton to $11 (£7) per ton.

In some cases, simplifying a process can mean using different materials. In 1946 in the US, James Watson Hendry invented plastic-injection-molding technology, which was used to produce one-piece chairs and tables much more cheaply than wood.

Mass production

In the early 1900s, Henry Ford revolutionized manufacturing by standardizing the method used to make cars. Before Ford's »



Steelmaking was revolutionized by Henry Bessemer's new converter. It raised the temperature of the iron so that more impurities could be removed during the oxidation process.

assembly line, cars were made by teams of highly skilled craftsmen who produced custom-made cars using little more than hand tools. The components used by early manufacturers were usually nonstandardized. This meant that workers would spend time adjusting components so that they could be assembled. Ford removed this stage by designing the world's first standardized car. Mass production of the Model T, made from a standard set of components, began in 1910 in Highland Park, Michigan.

Ford's second great innovation was the conveyor belt. In the past, skilled workers had to move around the factory locating raw materials, components, and tools. In some factories workers were hired to push partially assembled cars from one workstation to another. Ford believed these were unnecessary steps that could easily be removed. People were taken out of the production process and were replaced by specialized machinery, including a conveyor belt that took the work to the worker. Each employee was asked to perform a single task, using the same tool, over and over again. As a result, there was no time wasted searching for, picking up, and putting down an array of tools.

Henry Ford made use of the conveyor belt on the assembly line at his factory producing the Model T. Workers specialized in one task with one set of tools, which lay within easy reach.

> “Almost all quality improvement comes via simplification of design, manufacturing, layout, processes, and procedures.”
> **Tom Peters**

Finally, Ford removed variety from the production process. Each Model T produced was identical; Ford believed in simplicity of product, even down to the paint color, which speeded up production. Time spent resetting and cleaning machines between batches was avoided. A standard product made it possible to institute continuous-flow production, and the amount of time taken to produce a car dropped from over 12 hours to just over one and a half hours.Ford's decision to simplify production by removing skilled labor and time from the process enabled him to produce his cars at a lower cost, which he then used to reduce the price, and that created a mass market for the Model T.

Custom production

In more recent times, computer manufacturer Dell achieved stratospheric rates of growth in the 1990s by streamlining its supply chain. Michael Dell, the founder of the company, based his business model on gaining a cost advantage over his rivals. He did this in two ways. First, Dell specialized in selling custom-made computers; customers could design their own machine, which Dell assembled in response to a specific customer's order. Dell held virtually zero stock and production was pulled through by the buyer. The main advantage of this just-in-time method was that Dell no longer had to pay the costs associated with storing stock. When a product was finished, it was sent straight to the customer.

Going direct to the buyer

Dell's second cost advantage was that, unlike other PC suppliers, it did not sell its products to specialized retailers; instead, it sold directly to the consumer via the Internet. This meant that the company no longer had to lose some of its profit margin to third parties. When Dell sold a computer for $400, it received $400. Eliminating retailers did not have an adverse effect on Dell's market share. In fact, the reverse was true. Most computer buyers preferred the flexibility of being able to build exactly the sort of computer that they wanted, and also appreciated the convenience of home delivery.

> “Simple can be harder than complex: you have to work harder to get your thinking clean.”
> **Steve Jobs**
> **US Co-founder of Apple** (1955–2011)

Dell computers were not sold by computer retailers; instead they were available directly from the manufacturer. Dell took the bold step of cutting out retailers to undercut the competition.

Dell's simplified business model delivered lower costs, enabling the company to gain market share by undercutting the prices charged by rival computer suppliers.

The success of Dell's model of selling directly to consumers was adopted by companies in other industries. In 1996, Amazon, now the world's biggest online store, began selling books online without the need—or costs—of running a bookstore.

However, since 2000 Dell has lost ground to a revitalized competition. Some companies copied Dell's idea to sell computers directly to customers, while others, such as Hewlett-Packard, were able to nullify Dell's price advantage by making their production process more efficient. The resurgence of Apple has also dented Dell's market share. Apple produces a range of products to suit different budgets, and also allows its customers to make some adjustments to the computer's specifications.

Simpler services

Companies that sell services also work to improve efficiency by trying to remove unnecessary steps from their production systems. Sometimes these changes are needed to ensure a company's survival. For example, in the past, many independent food venues offered meals produced in a traditional, labor-intensive manner, cooked from scratch with fresh ingredients. Some business chains, looking to capitalize on the growing demand for low-cost food, adopted a simpler approach. They began to serve food that had been bought in a prepared state and simply heated in a microwave in response to a customer order. There was no need for trained cooks, and no time spent preparing fresh ingredients. Removing these steps cuts costs and enables the establishment to offer lower prices to consumers without losing profit margins.

However, innovations such as these can be cyclical. A rising market for freshly prepared food has led to new fast-food chains selling meals prepared on the premises. In the current climate, many companies are looking to cut costs by streamlining processes. But the businesses most likely to survive are those that can lower prices, but not quality, for the consumer. ■

> Simplicity—the art of maximizing the amount of work not done—is essential.
>
> **Principles behind The Agile Manifesto (2001)**

Michael Dell

Born in 1965 in Houston, Texas, to an orthodontist father and a stockbroker mother, Michel Dell was a natural entrepreneur. He made his first $1,000 by dealing in stamps at 12-years-old, and sold newspaper subscriptions for the now-defunct *Houston Post*. Dell attended pre-medical college in Texas in 1983, but soon left to focus on his computer business, which he named PC's Limited. Dell opened his first international subsidiary in the UK two years later, and in 1998 changed the business's name to Dell Computer Corporation, making it a public company and raising $30 million. In 1992, Dell became the youngest-ever CEO of a *Fortune* 500 business at 27. By 2000, the company's direct-sales website (launched in 1996) was generating revenue of $18 million per day. Dell resigned as CEO in 2004 to focus on his charitable work, but returned in 2007, taking the business private in 2013.

Key works

1999 *Direct from Dell: Strategies That Revolutionized an Industry*

EVERY GAIN THROUGH THE ELIMINATION OF WASTE IS GOLD IN THE MINE

JURAN'S PRODUCTION IDEAL

IN CONTEXT

FOCUS
Waste reduction

KEY DATES
1969 The Spittelau incineration plant in Vienna opens to burn trash collected from the city. The award-winning design means that the energy created can be used to provide hot water to a local hospital.

1931 Walter Shewhart summarizes his work on process quality control at Western Electric in his book *Economic Control of Quality of Manufactured Product*.

1994 In *The Empty Raincoat*, Charles Handy predicts the rise of telecommuting, whereby employees work from home to reduce office space.

1999 Salesforce.com and Google develop cloud computing. This foregoes the need to run expensive servers on which to store their data.

Reducing waste increases efficiency by **improving the productivity** of capital and labor.

Efficiency gains created from cutting waste cause **average unit costs to fall**.

Lower unit costs can **help a company grow** because lower costs can be used to either:

Fund **price cuts**, which will hopefully **boost sales**.

Or **improve profit margins**, which can be used to finance **new product development**.

Every gain through the elimination of waste is gold in the mine.

See also: How fast to grow 44–45 ▪ The value chain 216–17 ▪ Make your customers love you 264–67 ▪ Lean production 290–93 ▪ Simplify processes 296–99 ▪ Kaizen 302–09 ▪ Quality sells 318–23

In business, waste is anything that adds to a company's costs that does not create a higher output level, or lead to improved customer satisfaction. Any money generated from a reduction in waste can help a business grow by improving its competitiveness.

Joseph Juran (1904–2008) was born in Romania and moved to the US when he was a child. He became an expert in quality in business after working at Western Electric in the 1920s and being trained in statistical sampling and quality control. Juran identified waste as a factor that undermined profit. He urged businesses to constantly look out for opportunities to reduce waste. For Juran, the best way to do this was to improve product quality and the reliability of the production process.

Reducing waste

Waste in business ranges from investing in expensive machinery that does not meet the required output level because it breaks down regularly, to producing finished products that fail internal quality audits and are not good enough to be sold. If waste of this type can be reduced it should be possible to raise output without having to hire extra workers, spend more capital, or buy in additional raw materials and components.

According to Juran, lower costs can help a company grow in two ways. First, if average costs can be decreased, the business could choose to pass on the reduction by lowering prices to consumers. For example, if an initiative to reduce waste leads to a 10 percent fall in average costs, the management could opt to cut its retail prices by the same magnitude, and still earn the same profit margin. Cutting prices can help a business grow: undercutting the competition on price is likely to attract market share. Furthermore, even in markets where there is little competition, price cuts will make a product more affordable. The lower price will widen the brand's appeal, and potentially create growth by enlarging the target market.

Reinvesting profits

Reduced unit costs can help a company to enlarge its profit margins. If such savings are not passed on to the consumer, they could be used to increase the profit earned from the company's current sales volume. The additional profits made from reducing wastage could be reinvested into the business—the goal being to increase sales and to achieve growth. An efficient way to make use of the cash saved by reducing waste might be to fund a new advertising campaign.

Alternatively, companies might reinvest a significant proportion of their profits into scientific research and new product development. Theories about the life cycle of products, technological advances, and changing consumer tastes suggest that most products have finite selling lives in the market. If these investments pay off, the next generation of products will incorporate the latest must-have features and benefits that will appeal to consumers and translate into high sales. ■

Paint robots at this Volkswagen factory help reduce employee costs, and can be programed to use the minimum amount of paint required.

Volkswagen

In 2012, Volkswagen announced its intention to become the world's most environmentally friendly car manufacturer by 2018. To achieve this goal, the German company set out to reduce waste during the production process.

When cars are produced, sheet steel is cut out to form parts of the chassis. If this process if not managed effectively, expensive steel can end up being wasted as off-cuts. The management at Volkswagen achieved a 15 percent reduction in the amount of steel used to produce each car by investing in new cutting machinery and by changing the dimensions of the steel sheets to reduce off-cut waste. In the paint shop, the amount of paint used to produce a vehicle was halved by installing state-of-the-art painting robots.

These savings meant that Volkswagen could reduce their prices. For example, the price of a Golf Cabriolet was reduced by approximately $10,600 in June 2013. Reductions like this contributed to a 6 percent rise in global sales by May 2013.

MACHINES, FACILITIES, AND PEOPLE SHOULD WORK TOGETHER TO ADD VALUE

KAIZEN



IN CONTEXT

FOCUS
Improving efficiency

KEY DATES
1882 Scottish shipbuilders William Denny and Brothers Ltd. becomes the first company to use a suggestion box to garner ideas from its work force.

1859 English naturalist Charles Darwin publishes *On the Origin of the Species*, and outlines his theory of evolution as a process of gradual changes.

1990 In "Re-engineering work: don't automate, obliterate" in the *Harvard Business Review*, MIT professor Michael Hammer argues that to stay ahead, companies need to periodically redesign production methods.

1997 Japanese founder of the Kaizen Institute, Masaaki Imai, writes *Gemba Kaizen*, stressing that kaizen works best when factory-floor workers provide ideas for ongoing improvement.

In Japan, *kaizen* is an ancient idea that has become part of the culture. In its everyday usage, the word means an enhancement or a change for the better. In a business context, kaizen is more of a philosophy; according to the kaizen way of thinking, companies should strive to increase efficiency through a process of continuous improvement.

The majority of kaizen advances are built around people and their ideas, rather than investment in new machinery. Employees use kaizen to produce hundreds of new ideas every year, aimed at improving the efficiency of the business. In isolation, each kaizen idea might only have a marginal effect on productivity and general efficiency, but together these changes add up, creating a critical competitive advantage. Ideas for continuous improvement should come from all quarters—from managers and employees alike.

The Toyota Way

Kaizen was first deployed on an industrial scale by car manufacturer Toyota in the 1950s, as part of the now famous Toyota Production System (TPS). This system was designed to reduce *muda*—the Japanese word for waste. One of the forms of *muda* identified by Toyota was wasted employee talent; Eiji Toyoda wanted more from his work force than just blind obedience and hard work. At Toyota employees were valued and trusted—so much so that the company expected their factory-floor workers to fix problems associated with quality, and come up with ideas to improve efficiency. According to the Kaizen Institute, founded by Masaaki Imai to implement the philosophy, the goal of any kaizen plan should be to

> “
> Before you say you can't do something, try it.
> **Sakichi Toyoda**
> ”

Toyota

The Toyota Motor Company (TMC) was established in 1937. It produced several models of sedan cars at its Honsha production plant following business precepts set down by founder Sakichi Toyoda, which included, "Always strive to build a homelike atmosphere at work that is warm and friendly."

Following World War II, the company faced a financial crisis and, for the first time in its history, had to layoff employees. In 1951, Toyota implemented a creative ideas suggestion system based on the principles of kaizen. This, along with its principles of "customer first" and "quality first," helped the company thrive, and they began exporting their first cars to the US in 1957.

In 1962 management and unions signed a joint declaration stating that their relationship should be based on "mutual trust and respect."

By 1999 production in Japan had reached 100 million vehicles. Today the company continues to be guided by the twin pillars of continuous improvement and teamwork.

See also: Take the second step 43 ▪ Reinventing and adapting 52–57 ▪ Beware the yes-men 74–75 ▪ Make the most of your talent 86–87 ▪ Is money the motivator? 90–91 ▪ Lean production 290–93


Efficiency is a process of **continuous improvement**.
Hands-on employees can **identify problems** that need fixing.
When management **involves its workers** in the decision-making process...
...problems can be solved **efficiently**.
...the workers' **bond with the company** is strengthened.
Machines, facilities, and people should work together to add value.

persuade all workers that they have been hired for two jobs—doing their job, and then looking for ways to do it more efficiently.

Gemba is a Japanese word meaning "the real place," in a business context *gemba* refers to the place where value-added is created. Kaizen is founded on the conviction that the production-line worker is the *gemba* expert who knows where the problems are. Therefore, most of the ideas for kaizen change should come from the factory-floor workers, rather than from management. This is because difficulties and abnormalities can only be analyzed and fixed at the *gemba*, not from the desk. Kaizen philosophy recognizes that a company's greatest resource is its employees.

Quality circles

Kaizen is more likely to be effective if workers are asked to work as teams, rather than as isolated individuals. The process of coming up with good ideas and solutions is often the product of the synergy created by people that have different skill sets, qualifications, or ways of seeing the world. Working as a team on kaizen projects is known as being part of a "quality circle." The quality circle consists of a group of people who usually work together—for example, on the same part of an assembly line—as well as individuals from other parts of the business who can bring different perspectives. For example, an engineer could provide advice on technical matters, while sales-team members can give the group an insight into the customer's point of view.

In 1964, Toyota established quality circles at its factory in Toyota City, Japan. The quality circles still meet regularly, at least once a week, to discuss any of the problems they have noticed on their section of the production line. Each morning employees are expected to attend an *asa-ichi* (morning) meeting with a positive attitude, before the regular working day begins. At this meeting they discuss quality problems and possible solutions to those problems. One of the main tools used by Toyota's quality circles to generate kaizen ideas is the "fish-bone" diagram. This is a graphic device that uses the outline of a fish skeleton to plot all the various aspects of a problem and then explore a number of solutions. Quality circle members are asked to identify possible causes for the problem, and each suggestion is classified into one of six categories: Manpower, Methods, Machines, Materials, Measurement (inspection), and Mother Nature »



A fish-bone diagram has the problem to be solved on the right-hand side. An arrow, like a spine, leads to it. The causes of the problem are split up between the six categories.

(environmental factors). Solutions to each of the possible causes of the problem are evaluated by the circle using the "five Ws," which are the five questions: Why, When, Where, Who, and What.

Japanese companies do not tend to give cash bonuses to workers in return for their ideas. In order for kaizen to be truly effective, workers must feel a sense of pride and fulfillment when contributing their suggestions. New employees are told when they start working with the company that kaizen is an expectation: an everyday part of company life. In businesses that use kaizen successfully, employees' commitment to contributing ideas is usually secured via programs of job enrichment, which tend to produce high levels of employee motivation. According to motivational theorists such as Frederick Herzberg, workers enjoy problem solving, decision making, and the opportunity to advance and grow psychologically while at work. Therefore, it follows that workers should enjoy taking part in kaizen improvements and, consequently, financial bonuses should not be necessary.

Empowerment

One way managers empower their workers is giving them the authority to make decisions that affect their working lives. Empowerment is more far-reaching than delegation, which merely involves giving permission for an employee to perform a specific task. An employee who is empowered has been given the freedom to decide what to do and how it should be done. Empowerment is essential to any kaizen program because it enables good ideas from the factory floor to be implemented immediately. Once the kaizen philosophy is in place, good ideas and their subsequent improvements should keep on flowing through—the number of ideas made every week increases because workers are able to observe the effects of their own solutions. To work effectively, kaizen requires a business culture where trust, loyalty, and mutual respect exists between the management and the work force. This avoids a potential downside to the philosophy: the fact that in a market where sales are flat, employee ideas that lead to an increase in productivity could represent a threat to jobs. Workers are hardly likely to discuss labor-saving or cost-cutting measures if they are talking themselves out of a job. In many Japanese companies the kaizen culture used to incorporate a promise from the

> A company will get nowhere if all the thinking is left to management.
>
> **Akio Morita**
>
> **Japanese founder of Sony** (1921–99)

> We will try to create the conditions where persons could come together in a spirit of teamwork, and exercise to their heart's desire their technological capacity.
> **Akio Morita**

management that workers would have a job for life with the company. Throughout the 1980s and 1990s this was the case at Sony. During economic downturns, when sales fall, most companies try to protect their profit margins by making layoffs that are designed to cut costs. Sony rejected this approach because it felt that laying off its own workers would break the bond of trust needed to make kaizen work. According to Sony's co-founder, Akio Morita, "The most important mission for a Japanese manager is to develop a healthy relationship with his employees, to create a familylike feeling within the corporation, a feeling that employees and managers share the same fate." During the boom years Sony used the productivity increases made possible by kaizen to increase output, enabling the company to branch out into new markets.

Kaizen heads west

In the fall of 1984, following US concerns at the growing dominance of the Japanese car industry, the Massachusetts Institute of Technology (MIT) undertook a five-year, $5 million research program into the global car industry. The study produced a new way of looking at production, a new buzzword, and a best-selling book—*The Machine That Changed the World,* authored by James Womack, Dan Jones, and Dan Roos. The study confirmed the US car industry's worst fears; Japanese car producers led the way in terms of minimizing the assembly hours per car, the amount of stock held, and the assembly defects per 100 cars. The book attributed Japanese success to a process called "lean production"—a vital component of which was kaizen.

Managers that had read *The Machine That Changed the World* tried to incorporate the kaizen way of thinking into their business model, and gradually the kaizen philosophy spread to North America and Europe. One of the early British adoptors was Rover. Under the guidance of Honda, who at the time held a 20 percent stake in Rover, the company introduced *gemba* walks at its Longbridge factory in 1991. Under Rover's *gemba* program, managers, supervisors, and assembly-line workers walked along the production line together, at least once a week, in order to look for inefficiencies, and to find solutions to the problems they had identified. *Gemba* walks were designed »

> Excellent companies don't believe in excellence—only in constant improvement and constant change.
> **Tom Peters**
> **US management writer** (1942–)

Discussing a problem with others is a more effective way to come up with solutions. Consulting people from other parts of the business brings different viewpoints and a wider range of options.

to remove the divide between managers and workers, the underlying philosophy being that managers, supervisors, and assembly-line workers should learn, discover, teach, grow, and make improvements together.

Kaizen in action

One of the first British companies to adopt quality circles was the pottery company, Wedgwood. From 1980 onward, 80 quality circles representing different parts of the business met for an hour a week. Each quality circle was empowered to identify its own problem, which it then spent up to six months solving. The solution devised by the circle was presented to the management and most were approved and then implemented. Employee motivation improved, which increased productivity. In addition, employee ideas reduced costs by cutting the amount of clay and paint wasted during the production process. According to Dick Fletcher, the man who led Wedgwood's quality circle program, for every $1.60 (£1) the business spent on quality circles, Wedgwood's costs fell by $4.85 (£3).

Another business that has employed kaizen techniques to good effect is India-based Tata Steel. The company made improvements to the productivity of its gear-cutting machinery, which led to increased production.

The antithesis of kaizen

A very different approach from kaizen is Business Process Reengineering (BPR). This is based on infrequent—but very capital-heavy—investment programs that are designed to create a great leap forward in terms of productivity, reductions in unit costs, or improvements in product quality. Unlike kaizen, companies that use BPR do not endeavor to make regular small changes. Instead the goal is to radically rethink the whole production process every five years or so to make it more efficient. Typically, this is in response to a crisis. Once the company using BPR has caught up with its rivals, a period of stability follows, until complacency sets in again, and the next crisis arrives, and prompts another round of BPR.

Investment in robots in the workplace can be a large-scale, costly undertaking, which frequently results in job losses. This sort of BPR activity can alienate the work force.



The effects of kaizen and BPR on productivity are shown here over a 30-year time span. Overall, kaizen increases output with consistent steady improvements while BPR brings a series of sharper boosts to productivity followed by periods of flat growth.

Rather than approaching employees for ideas that lead to improvements in efficiency, companies that use BPR only use ideas that originate from managers and highly qualified consultants. The work force is relatively passive: change is imposed from the top and often includes large-scale layoffs. This is because companies that use this approach often try to boost efficiency by investing in automated production systems that replace labor with capital. Those that favor kaizen argue that it is better to try to improve efficiency by making small but regular changes, rather than by instigating less frequent but more radical BPR changes. In competitive markets, companies that rely on BPR struggle to match the less dramatic but steadier growth achieved by kaizen. Companies using BPR can be slow to catch up because during the time it takes to develop, install, and test new systems, companies using kaizen have moved on, boosting productivity to an even higher level. This may be seen as analagous to the fable by Aesop in which the plodding tortoise trumps the sprinting—then delaying—hare. Increased productivity achieved by kaizen tends to be cheaper to obtain than productivity growth achieved by BPR. The source of kaizen improvement is people. Employee ideas are essentially free, unlike expensive new machinery for a new production system.

Is kaizen always effective?

However, in some companies kaizen does not work. Middle managers and supervisors who are inclined toward an autocratic leadership style typically resent kaizen: they enjoy making all the decisions and are sometimes resistant to change. Individuals with this mind-set will not want to delegate decision making to factory-floor workers. If their good ideas are constantly ignored by managers, employees will quickly become disillusioned and stop contributing. A company's industrial relations history can also affect the outcome of kaizen. In general, the chances of success with kaizen fall if there is a lack of trust between the management and the work force. Employees may see kaizen in a cynical way—feeling that the plan is just another management ruse to get more out of the work force without offering anything in return.

Kaizen is built on the premise that no production method is perfect; systems can always be improved through employee suggestions. But is this always true? Logically, businesses will try to use kaizen to fix key problems first. It could be argued that, over time, the benefits of kaizen are likely to fall steadily as any new problems that are tackled will be those previously considered less significant.

The rewards of risk

Technology and consumer tastes change. From time to time the old product, and with it the old methods of production, will need to be discarded in favor of something new and radical. Companies that favor kaizen may tend to eschew radical overhauls in favor of less dramatic change. The danger here is that they can end up being left behind by their bolder rivals. A good example of a company that suffered as a result of this approach is Nokia. For many years the Finnish cell-phone company enjoyed great success by sticking to its classic design of "Candybar" phones. However, in the meantime rival companies such as Samsung and Apple took greater risks, and as a result, out-innovated Nokia, taking away their market lead. ■



Aesop's fable tells how the tortoise wins a race against the hare by slowly advancing to the finish while the hare sprints and then riskily naps. Kaizen can be viewed as the tortoise, making minor adjustments daily, while the hare can be viewed as BPR, making rapid, dramatic changes.

The tortoise demonstrates that **steady progress**, such as that achieved using **kaizen methods**, can be the better approach to winning the race.

The hare's overconfidence causes him to lose the race, much as the big, **bold changes wrought by BPR** can prove less effective in the long run.



LEARNING AND INNOVATION GO HAND IN HAND

APPLYING AND TESTING IDEAS

IN CONTEXT

FOCUS
Research and development

KEY DATES
1790s In postrevolutionary France the government works with scientist Claude Chappe to develop a nationwide semaphore system.

1806 Isambard Kingdom Brunel is born. The British scientist and engineer goes on to design and build the first propeller-powered ship and the first tunnel under a river.

1939–45 During World War II, jet engines, the mass-production of medicines such as penicillin, and blood transfusions are all developed.

1942 Austrian economist Joseph Schumpeter uses the term “creative destruction” to describe how innovation in industry creates new societies by destroying old ones.

Scientific research leads to **technological breakthroughs**, which businesses use to...

...create new products.

...improve existing products.

...update processes.

To **innovate for the future**, companies must be **willing to learn** about new technologies and how they can be harnessed.

Learning and innovation go hand in hand.

Research and development (R&D) is any investigative and creative work intended to lead to new discoveries or to improvements in existing products or processes. Some companies, in areas such as computer software and pharmaceuticals, depend on scientific research to bring about technological breakthroughs and keep themselves on the cutting edge of their industry. Others apply R&D to improve existing products.

Filling a gap

In some cases, the direction of R&D is driven by market research findings that uncover a gap in the

See also: Gaining an edge 32–39 ▪ Kaizen 302–09 ▪ Quality sells 318–23 ▪ Planned obsolescence 324–25 ▪ Time-based management 326–27

market, as it did for the cereal manufacturer Kellogg's. Market research showed that there was a desire in the UK for a sweeter breakfast cereal made from nuts, which people perceived to be healthy. To meet this need, Kellogg's instructed its R&D department to design a new breakfast cereal; the result was Kellogg's Crunchy Nut, which has become the second most popular cereal in the UK.

There have been some cases in which market research pointed companies in the wrong direction. A prime example can be seen in the creation of Sony's Walkman. This portable audio cassette player was invented in 1978 by Nobutoshi Kihara, an audio engineer working for Sony. According to market research, the Soundabout (the name for the prototype Walkman) would never sell because focus groups declared that listening to music was a social rather than a solitary activity. However, Akio Morita, Sony's co-founder, told his R&D department to continue its work and ignore these findings. The Walkman went on to be one of Sony's most successful products.

> Innovate or die.
>
> **Damon Darlin**
>
> **Business editor, *The New York Times***
>
> **(1956–)**

More products, more often

Intense competition resulting from globalization, alongside rapid technological advances, has shortened the selling lives of many products. To stay in business in this tough trading environment, companies need to launch new products more regularly; those that are complacent and fail to innovate will be overtaken by their rivals. It could be argued that managers who do not invest in R&D are setting up businesses to fail.

Companies such as BMW devote a sizable percentage of their turnover to R&D for motives that extend beyond self-preservation. Those that launch a new product first can charge premium prices and will benefit from monopoly profit until the competition arrives. In addition, consumers' brand loyalties are usually established early on. Companies that underinvest in R&D, fine to imitate rather than innovate, may have problems establishing a strong customer base.

There is more to effective R&D than spending money on technical breakthroughs. According to Akio Morita, converting these advances into products that provide value and benefits for consumers is more important than the breakthrough itself. Therefore, it makes sense for R&D to be done by a multi-disciplinary team that includes a representative from marketing, who understands the way the consumer's mind works. ■

Satellites orbiting the Earth are able to provide data on time and location to a variety of GPS receivers based on or near the planet.

The global positioning system

Global positioning system (GPS) technology was developed by the US government during the 1960s and 1970s to enable the US Navy and Air Force to get an accurate geographical fix on submarines and aircraft.

In 1983, US President Reagan decided to give businesses access to GPS so that they could use it for commercial purposes. A number of companies saw the opportunities in this and began designing GPS satellite navigation systems for motorists.

GPS is an excellent example of a revolutionary, technology-driven innovation. However, in practice, most new product innovations are based on tweaking existing products to make them better. Companies such as TomTom, who make GPSs, use R&D to achieve evolutionary, rather than revolutionary, product development. The goal is to launch new products every year that are cheaper and better designed, and that have new updated features.

YOUR MOST UNHAPPY CUSTOMERS ARE YOUR GREATEST SOURCE OF LEARNING

FEEDBACK AND INNOVATION

IN CONTEXT

FOCUS
Open innovation

KEY DATES
1989 The Berlin Wall falls. Companies inside the former Iron Curtain must now respond to customer complaints.

2000 The travel website Trip Advisor, which enables users to rate hotels and restaurants, is founded by Stephen Kaufer.

2003 Organizational theorist Professor Henry Chesbrough publishes *Open Innovation: the new imperative for creating and profiting from technology,* which urges businesses to be open to learning from internal and external sources.

2009 US crowd-funding website Kickstarter is set up to encourage individual investment in small-scale business projects.



A business **asks its customers** how it could improve a product or service.

Customers or the public **submit their feedback**, both positive and negative, to the company.

Good **ideas to** improve processes or products **are incorporated** into the business.

Your customers are your greatest source of learning.

In the past, companies required their own employees to design and develop new products. The knowledge was developed internally by the in-house research and development (R&D) department, and tended to be a closely guarded secret. This belief that a company should be in sole control of the creation of its intellectual property is known as closed innovation. In more recent times, a new approach has emerged. Open innovation is based on the idea that companies should be less private with their product-development programs, reflecting the view that its customers can make valuable contributions to the product-development process.

Internet feedback

The Internet has kick-started a sea change in how businesses get feedback from customers. Online

See also: Finding a profitable niche 22–23 ▪ Understanding the market 234–41 ▪ Make your customers love you 264–67 ▪ Why advertise? 272–73 ▪ Applying and testing ideas 310–11 ▪ Benefitting from "big data" 316–17

ratings and reviews allow companies to see what their customers like and dislike about a product.

In the IT industry, companies such as Apple and Microsoft use beta testing to enhance the quality of their new products. This process involves the software developer prereleasing copies of new software via the Internet. Members of the public who are interested in software and programing have the opportunity to road test the new product. They might point out bugs they encounter and offer possible solutions to the problems they have identified. The developer has the opportunity to improve the software before it is released, increasing the probability of the new product succeeding in the marketplace.

Crowdsourcing

The belief that companies can, and should, learn from their customers is growing. One example is the rise of crowdsourcing—a practice where companies get ideas, or even finance for a new product (crowd funding), from the public. There are different types of crowdsourcing. For example, some independent filmmakers finance their movies as crowdsourcing projects. Carmakers such as Citroën and Nissan have used crowdsourcing to enable car buyers to contribute ideas for the kind of product features that should be built into new vehicles. Citroën ran its crowdsourcing project via a Facebook app. Members of the general public were free to join the Facebook group—called C1 Connexion—and add their thoughts on six key aspects of the new car's design, including the number of doors, the color of the interior, and the equipment specification. Citroën kept its promise to build the car in line with the preferences expressed via the Connexion Facebook app.

There are several advantages to incorporating positive and negative feedback from members of the public and customers into the product-development process. The most obvious is that it is very cheap. In many cases companies do not pay for the ideas and opinions of crowdsourcers; interested volunteers offer the information free of charge. If cash is offered in exchange for feedback, the amounts tend to be small. Those who use crowdsourcing as part of the product-development process also recognize that there will be experts outside the company who are not on the payroll, but who have valuable ideas and knowledge that should be harnessed. ■

Ozzy Osbourne's official website hosted a poll for fans to vote for the next single from his 2007 album *Black Rain*. They were offered three tracks to choose from—the title song "Black Rain" won.

> The more you engage with customers the clearer things become and the easier it is to determine what you should be doing.
>
> **John Russell**
>
> **Harley Davidson president** (1950–)

Wikipedia

The online encyclopedia, Wikipedia, was set up in 2001 by Larry Sanger and Jimmy Wales as a crowdsourcing project. Rather than hiring paid writers and editors, the founders of Wikipedia asked members of the public to create the product themselves by submitting their articles electronically.

By July 2013 Wikipedia comprised over 22 million articles, written in 285 languages by 77,000, largely anonymous and unpaid, authors. Wikipedia is an open-source project, meaning that everyone with access to the Internet is able to write or make changes to it. Wikipedia does not charge its customers for using its product. Instead, the project is financed by donations from supporters. Many of these supporters argue that Wikipedia is superior to conventional encyclopedias because, unlike them, articles can be updated quickly and easily. Wikipedia has taken the concept of crowdsourcing to the limit—the entire product has been created by consumers.



TECHNOLOGY IS THE GREAT GROWLING ENGINE OF CHANGE

THE RIGHT TECHNOLOGY

IN CONTEXT

FOCUS
Managing change

KEY DATES

1822 English mathematician Charles Babbage designs "the difference engine"—the world's first mechanical, programmable, computer.

1951 The British food manufacturer J. Lyons & Co starts using LEO (Lyons Electronic Office), the first computer designed specifically for a business use—in this case, to track sales figures.

1981 US software company Microsoft develops the MS-DOS operating system.

1998 Banks and hedge funds in the US design computer programs to buy and sell shares, bonds derivatives, and other financial assets. This is the origin of high-frequency trading.



With **clear objectives** and a shared vision...

...**new IT systems** can increase revenue, improve safety, and boost morale.

Technology is the great growling engine of change.

No business today can survive without some form of computer system, but continual investment in new IT (information technology) can enhance a company in previously unimagined ways. IT can be used to boost productivity or increase reliability, or to decrease the risk of human error. Air India set out to improve efficiency in 2013 with a new computerized Crew Management System (CMS) that was designed to deploy pilots and cabin crew more effectively than a manual system. Under the previous system, some crew worked longer hours than others for the same salary, which created friction between crew members. CMS has enabled management to monitor crew deployment more closely. The hope is that by ensuring that staff are employed more equitably and

See also: Stand out in the market 28–31 ▪ Gaining an edge 32–39 ▪ The value chain 216–217 ▪ Forecasting 278–79 ▪ Kaizen 302–309 ▪ Feedback and innovation 312–13

> To err is human—and to blame it on a computer is even more so.
>
> **Robert Orben**
>
> **Comedy writer** (1927–)

eliminating favoritism, the airline will improve morale, which should have a positive effect on customer service, and eventually boost revenues. Air India also anticipates that CMS will enhance safety by improving the company's ability to meet strict international regulations relating to working hours.

However, not all new IT projects are successful. US investment bank JP Morgan lost $6 billion in 2012 because a new IT program, designed to help traders assess the risks of holding a range of financial derivatives, failed to work properly.

Managing change

So, how can big IT projects be best managed in order to achieve progress, rather than disaster? In 2005, research carried out by Lancaster University in the UK established that the chances of successfully implementing a new large-scale IT project increase when senior management is clear about what they hope to achieve from it. A clear set of objectives will help the IT designers to produce a system that effectively benefits the end user. Features that are not needed add to the cost of the project, and, in all probability, make the system less usable.

In Australia in 2005, a plan was introduced to improve productivity of traffic police by getting them to spend more time on the road, and less in the office. State governments equipped police cars with relatively inexpensive Automatic Number Plate Recognition (ANPR) cameras. Real-time information collected by police cars was fed, on the road, into the national database—CrimTrac. The system made policing more efficient because officers could use CrimTrac to identify, and pull over immediately, stolen cars or vehicles that had not been taxed or insured.

Factors for success

A new IT project also needs to be a shared vision. Customer-facing and factory-floor employees should know why the new IT system has been introduced, have a clear vision of the benefits of the system, and receive adequate training. In some organizations systems might fail because there is resistance to change—employees may fear losing expertise, or even their jobs. To overcome this, management needs to communicate openly and honestly about why the new IT system is needed. ■

> As a rule, software systems do not work well until they have been used, and have failed repeatedly, in real applications.
>
> **David Parnas**
>
> **Canadian software engineer** (1947–)

Police cars in many countries run Automatic Number Plate Recognition (ANPR) software. Suspicious vehicles are checked immediately and can be intercepted without delay.

WITHOUT "BIG DATA," YOU ARE BLIND AND DEAF AND IN THE MIDDLE OF A HIGHWAY

BENEFITTING FROM "BIG DATA"

IN CONTEXT

FOCUS
Analyzing data

KEY DATES

1995 US company Netscape Communications Corporation develops Internet cookies.

1997 NASA scientists Michael Cox and David Ellsworth devise the term "big data" to describe the challenge of processing and visualizing the vast amounts of information generated by supercomputers.

2000 Francis X. Diebold, an economist at the University of Pennsylvania, publishes his paper *Big data, dynamic factor models for macroeconomic measurement and forecasting*.

2012 Barack Obama's team uses "big data" to get him reelected to the White House.

2013 US whistle-blower Edward Snowden reveals that the National Security Agency was authorized to use "big data" to spy on US citizens.

A huge amount of **information** is gathered whenever **digital interactions** take place.

When this **"big data"** is organized and analyzed...

...it reveals the **viewing and shopping habits** of millions of people.

Without "big data," you are blind and deaf and in the middle of a highway.

Nowadays there is a huge amount of information that is routinely collected, stored, and analyzed by businesses and government. This "big data" includes sales data collected from credit or debit cards swiped at checkouts; web-browsing histories of actual and potential customers; information obtained from social media; and usage patterns collected from smartphones, digital video recorders, games consoles, and other personal devices that are connected to the Internet. Due to its size, "big data" can be expensive to store and organize on conventional databases.

Using "big data"

"Big data" can be used for market-research purposes to track and target consumers and identify profitable gaps in the market. One company that has made use of "big data" to increase revenue is Progressive Corp. The US insurance company has tried to increase its market share by offering lower car insurance premiums to drivers who install a device into the car's diagnostic port. The device measures how the car is driven—its speed, and the number of times the

See also: Finding a profitable niche 22–23 ▪ Study the competition 24–27 ▪ Gaining an edge 32–39 ▪ Forecasting 278–79 ▪ The right technology 314–15

"Big data" comprises the huge amount of information consumers give away whenever they use their credit or debit cards, play games or browse online, or stream TV. This information is analyzed by companies to target their products more specifically.


Customer transaction details
Web-browsing histories of actual and potential customers
BIG DATA
Personal data mined from TV-viewing, video-gaming, and smartphones
Attitudes and values revealed to companies via social media

car has braked suddenly or accelerated rapidly. The collected data is then sent, via a GPS signal, to the insurer for analysis. In theory, Progressive's use of "big data" will help them cherry-pick the most profitable customers in the market—those with safer driving habits, who pay their premiums but are unlikely to make expensive claims.

TiVo, a US company that makes digital video recorders, has used "big data" to create a new revenue stream. TiVo's boxes are connected to the Internet. This enables the business to collect huge volumes of data on TV-viewing habits at a relatively low cost. The data is subsequently sold by TiVo to advertisers. By correlating this data with sales figures collected from barcode readers at checkouts, retailers can assess the effectiveness of their TV advertising campaigns.

Product development

Netflix, the US media-streaming provider, has used "big data" to drive product development. In 2011, after evaluating the viewing habits of its 33 million subscribers, the company decided to remake a BBC series called *House of Cards*. Netflix knew from its "big data" that it would be wise to spend $100 million on a US version of the show because the original had been heavily downloaded. "Big data" was also used to make production decisions, including choosing director David Fincher. Fans of *House of Cards* also enjoyed watching Kevin Spacey movies, so he was cast in the lead role. ■

Internet cookies

Sales figures are an excellent example of "big data." US online retailer Amazon collects the browsing histories and purchasing data of its 152 million customers on a daily basis. Amazon uses "cookies," text files saved in a customer's browser, which help to track what kind of items each of its customers are interested in. This information is used to send recommendations that are likely to appeal to the customer, and so are likely to create additional sales for the company.

Cookies are used to create a unique ID that stores the customer's name, address, and credit-card number on the hard drive of their computer. When a customer returns to the website, the ID stored on the customer's computer is sent back to the business, which enables it to identify the customer and greet him or her by name. The ID also enables the online retailer to recall the customer's address and credit-card details quickly, speeding up the transaction and increasing customer satisfaction with the site.

> It is a capital mistake to theorize before one has data.
>
> **Arthur Conan Doyle**
> **UK author and physician** (1859–1930)

PUT THE PRODUCT INTO THE CUSTOMER'S HANDS IT WILL SPEAK FOR ITSELF

QUALITY SELLS



IN CONTEXT

FOCUS
Defining quality

KEY DATES
1924 German pen maker Montblanc launches its luxury *Meisterstück* ("masterpiece") fountain pen, which is still an icon of superior quality today.

1970 The Hamilton Watch Company develops the first digital watch. It succeeds despite its $2,100 price tag.

1985 Management guru Peter Drucker publishes *Innovation and Entrepreneurship,* which states that quality is the most important factor to affect sales. Drucker says that the consumer is the ultimate arbiter of a product's quality.

2005 Entrepreneur Richard Branson announces that he plans to offer the first trips into space. The price of $120,000 fails to deter rich and famous potential customers.

There is an adage that quality sells, and many companies believe that the best way to attract buyers is to produce a superior product. Businesses that put quality first believe that the other factors affecting demand, such as promotion, distribution, and the price, are much less important than the product itself.

At first this approach may seem irrational. In some markets, after all, low prices are critical. For example, Ryanair's competitive advantage over its rivals is based on its low-cost business model, which enables the airline to charge lower fares than its rivals. Yet some low-cost goods or services can represent a false economy for customers, especially if the goods are of poor quality, necessitating extra costs for the customer to repair or replace them.

Another possible way to boost revenue is to increase the volume of goods sold. Some companies attempt to achieve this goal by using advertising campaigns to steal market share from their rivals. However, the problem with trying to grow revenue through promotion is that it is usually expensive. In the UK, for example, in 2013 a 30-second television commercial cost up to $80,000 (£50,000).

Offering a quality product is an alternative to these low-cost or high-volume approaches. This strategy can achieve the same goal of boosting a company's revenues, improving customer retention by offering clients a product of a high standard that they will want to keep or to buy again and again.

What is quality?

To appreciate the role played by quality, it is first necessary to understand what is meant by this term. In a manufacturing context, quality is achieved when a company is able to supply reliable, durable goods that meet or surpass consumer expectations and are free of defects.

High-quality products inspire trust. Take, for example, high-quality car tires. They often have deeper treads than poor-quality tires, making cars that have them less likely to skid in emergencies or bad conditions. In this case the quality of a car tire could be the


High-quality components and design...
...plus **added value** that the customer was not expecting...
...results in a product or service that will sell itself.

See also: Finding a profitable niche 22–23 ▪ Gaining an edge 32–39 ▪ The weightless start-up 62–63 ▪ Leading the market 166–69 ▪ The marketing model 232–33 ▪ Creating a brand 258–63 ▪ Fulfilling demand 294–95

difference between life and death. Superior-quality tires, made from harder-wearing rubber compounds, also last longer than tires of lesser quality, which means that the driver will not have to face the cost and inconvenience of replacing them as frequently.

Great quality is not just about using the best components. Design is also crucial to achieving a superior-quality product, because design can offer the consumer new benefits for which they are willing to pay a price premium. In 2011 the Japanese tire manufacturer Bridgestone launched its new range of flat-run tires, based on an innovative design that enabled motorists to run a car with a flat tire for 50 miles (80 km) at a speed of 50 mph (80 kph). This feature enabled drivers to reach the closest garage to change a flat tire, rather than having to change it on the side of the road.

Businesses that have managed to incorporate differentiating features into their products can exploit the added value that these features provide by charging higher prices. If in other aspects (such as function) the products are equal to their competitors, adding price premiums to products that are especially valued by consumers should lead to greater revenues and profits.

> Profit in business comes from repeat customers, customers …that bring friends with them.
> **W. Edwards Deming**

Quality wins out

Estée Lauder adopted the “quality sells” philosophy when she set up her cosmetics business in New York in 1946. When she was a child, her mother had lectured her relentlessly on how exposure to the sun led to premature aging of the skin. The young Lauder took note and began making her own skin creams with her uncle, a chemist. Like many other successful entrepreneurs, Lauder genuinely believed that there was a need for her product, and in 1935 she began selling her first preparations: super-rich, all-purpose crème; crème pack; cleansing oil; and skin lotion.

In the beginning Estée Lauder did not use any advertising; she thought her products were so good they would sell themselves. She relied on her customers to promote the products. Customers would try her preparations, like them, and continue buying them. Furthermore, they would then recommend Estée Lauder’s products to their friends. She gave this form of promotion a name: tell-a-woman marketing.

In more recent times, Samsung has also used the quality-led approach to great effect. The South Korean electronics manufacturer does not rely on glitzy advertising campaigns to create its competitive advantage. Instead, it appeals to a market segment who favors product quality over brand image.

In April 2013 the Samsung Galaxy 4 was launched. Very quickly it gained market share over the market leader—Apple’s iPhone—because it was seen as a more technologically advanced product than Apple’s latest model, the iPhone 5. The display offered around 100 more pixels per inch than the iPhone 5, and its built-in »

Customers who are loyal purchasers of a specific brand are valuable even if that product is a low-cost one. Quality is one feature that can inspire trust in and generate repeat business.

camera also surpassed the iPhone 5 in terms of functionality and pixels. In addition, according to research by the UK consumer magazine *Which?*, the Samsung processor was nearly twice as fast as that in the iPhone.

Samsung's prices were slightly lower than Apple's, but there were other producers of Android mobile phones that substantially undercut Samsung's prices without taking any of its market share. The key to Samsung's Galaxy 4 success was its superior quality.

Brand loyalty

Quality can be an important selling point even for low-cost products, since it helps build brand loyalty and thus ensures repeat customers. In markets for fast-moving consumer goods (FMCGs), manufacturers use superior product quality to preserve and extend their customer base. FMCGs are nondurable products, such as beer, toothpaste, chocolate, and breakfast cereal, that are bought frequently by households and consumed immediately. Since FMCGs are purchased regularly throughout the year, the sales volumes achieved by a successful product can be immense.

A good example of an FMCG market is the one for toilet paper. According to research by US toilet paper manufacturer Charmin, 126 billion rolls of toilet paper are bought every year in the US. In a market this large, even a small share will translate into multimillion-dollar revenues. If consumers habitually purchase the same brand of a particular product over and over, rather than switching between rival brands, their brand loyalty will be invaluable.

High-quality brands are more likely to win brand loyalty than brands of an inferior quality. For example, households are more likely to buy Charmin toilet paper again and again if the product is softer and stronger than the brands sold by its rivals, generating higher volumes of sales and greater revenues. This means the business has increased its revenues without having to pay any of the marketing costs usually associated with acquiring customers.

> Quality means fitness for use. Fitness is defined by the customer.
>
> **Joseph Juran**
>
> **US expert on quality management (1904–2008)**



Even a small market share of these **repeat-buy, low-cost** items will represent vast profits.

Consumers tend to **stick with their favorite brands** of fast-moving consumer goods (FMCGs), which are bought regularly.

Household items such as toothpaste, toilet paper, and laundry detergent represent low-cost, high-volume items that are bought regularly and generate huge revenues for manufacturers.

Service and quality

Another indicator of good quality is providing a service in a manner that exceeds customer expectations. This might manifest as efficiency, or rapid response to customer concerns. The Zurich Insurance Group operates in over 170 countries and each month handles over 600,000 customer interactions via phone, mail, and the Internet. Its ambition is to be the best global insurer as measured by customers, employees, and shareholders, and it actively pursues quality assurance. Its iQuality program sets out how employees can pay more attention to customers, and find out more about their changing needs and expectations. It performs regular checks on the quality of employees' work and uses extensive market research to gain feedback on customer experience.

Hotel guests are pleasantly surprised to discover luxury extras that they were not expecting. These could be complimentary services or products.

Zurich also has protocols for reacting to unhappy customers; when several customers complained that payment was too slow when their policies matured, Zurich used the "five whys" to discover that the problem lay in a delay in sending out claim forms. The company put in an automatic system to send out the forms 10 days before policies matured, resulting in a 78 percent drop in complaints. Zurich has won many service awards, including two "Five-star Service Awards" based on 25,000 completed questionnaires.

Added value

Businesses can also create high-quality products by adding value. Value added is the difference between a product's price and the raw material cost of making the product. Companies can add value to their products with new features, innovative functions, or add-ons designed to benefit, and appeal to, actual and potential buyers.

In the hotel business, Ibis adds value by promising customers that their specially designed beds, mattresses, comforter, and pillows will give them a better night's sleep. The cost of these items is balanced against improvement in retention of customers, or by higher prices that create extra revenue.

Other hotels have been even bolder in pursuing value added. In the premium segment of the market, hotels create additional value by redefining their core function. These hotels do not just sell a comfortable place to sleep; they sell an "experience," in which guests are offered a range of "delighters"—aspects of the hotel's service that delight the guest, but which are not usually expected. Examples include HD televisions; branded, high-end shower gel and shampoo; free champagne; and free slippers that guests can take home with them.

Adding value is a constant battle because a "delighter" can soon become an expectation. If a hotel fails to meet the constantly rising requirements of its guests, it will lose customers to its rivals. Successful hotels are constantly on the lookout for new "delighters" that will surprise their guests without becoming too expensive. Low-cost delighters are the ideal way to create value added, generate repeat purchases, and ultimately produce healthy profits. ■

> "Quality … is not what the supplier puts in. It is what the customer gets out and is willing to pay for."
>
> **Peter Drucker**
> **US management guru** (1909–2005)

W. Edwards Deming

William Edwards Deming was born in 1900 in Sioux City, IA. He studied physics at the University of Wyoming before going on to receive a PhD from Yale. After leaving full-time education he worked for Bell Telephones, where he was part of a team working to improve quality control.

One of his key ideas was that the quality of bought-in raw materials and components matters more than their price because their quality will be a major factor in determining the quality of the finished product. Consequently, he argued, manufacturers should not choose their suppliers solely on the basis of the price charged. Ideally, companies should try to develop a long-running relationship with a single supplier, which is based on trust. This approach would be more likely to lead to better-quality materials.

In addition, Deming also believed that quality came from a production process that was stable and consistent.

Key works

1982 *Out of the Crisis*
1993 *The New Economics*



THE DESIRE TO OWN SOMETHING A LITTLE BETTER, A LITTLE SOONER THAN NECESSARY

PLANNED OBSOLESCENCE

IN CONTEXT

FOCUS
Maintaining sales

KEY DATES
1924–39 Lightbulb makers Osram, Phillips, and General Electric form a cartel, working together to prevent any product development that would produce lightbulbs that could burn for more than 1,000 hours.

1932 Bernard London writes a leaflet titled *Ending the Depression through Planned Obsolescence*, urging the UK government to pass laws to limit the useful lives of products to increase demand.

1959 Volkswagen uses the tagline: “We do not believe in planned obsolescence, we don’t change a car for the sake of change,” to criticize rival car manufacturers who allegedly did not build cars to last.

2013 Apple declares that the original iPhone, launched in 2007, is now obsolete.



Products are **more durable** than they were in the past.

To **maintain profits**, companies have to find ways to encourage **replacement purchasing**.

New versions of existing products are regularly restyled and given **added features**...

...to create products that **existing owners** will want to buy.

Built to last may sound like an essential in any form of production, yet some manufacturers produce items that they know will become obsolete in just a few years. This policy ensures that customers continue to buy new goods. Products are replaced either because their components wear out or because they are surpassed by products with new features.

In the past, items such as lightbulbs or stockings were made to fail sooner rather than later. Nowadays, items such as printer ink cartridges, batteries, and components for appliances can be difficult or expensive to replace, making it tempting to buy a new version of the product instead. Many goods, such as pens or razors, have become disposable—cheap to make and easy to replace.

See also: How fast to grow 44–45 ▪ Thinking outside the box 88–89 ▪ Protect the core business 170–71 ▪ Morality in business 222 ▪ Greenwash 268–69

Updated styling

US industrial designer Brooke Stevens defined the term “planned obsolescence” as instilling in consumers “the desire to own something a little better, a little sooner than necessary.” The strategy of planned obsolescence was originally developed by General Motors, who realized that advancing technology would adversely affect its future business. During the 1950s, it began updating the styling of radiator grills, taillights, and bodywork every few years to encourage drivers to replace their cars more often.

Over the last 30 years, as technology has advanced, cars have become even more durable and reliable. Today, new cars are built to last. With regular servicing the engine and transmission of a new car will still provide reliable service for over 250,000 miles (402,000 km). Typically, with average usage, this equates to an expected useful life of more than a decade. If drivers only replace their vehicle once every ten years, this would lead to low sales for car manufacturers.

To generate higher sales levels, many carmakers now set out to create planned obsolescence to speed up replacement purchase, by giving cars regular face-lifts. The redesigns are intended to encourage status-conscious motorists to ditch their still perfectly good vehicles for the latest body shape.

> I believe in status symbols.
> **Brooks Stevens**
> **US industrial designer** (1911–95)

> Obsolescence never meant the end of anything, it’s just the beginning.
> **Marshall McLuhan**
> **Canadian media theorist** (1911–80)

New features

Car manufacturers also employ various other tactics to persuade consumers to update their vehicles. New car models incorporate cutting-edge features such as touch-screen multimedia control systems for in-car entertainment, or additional safety systems, such as technology that warns about lane departure and potential collisions.

Phone manufacturers, such as Samsung and Apple, use planned obsolescence to increase revenue by persuading consumers to replace still-usable cell phones or tablets with something newer and better. In this highly competitive market, the rewards go to the company that creates planned obsolescence soonest, which gives them the fastest rates of replacement purchase. Samsung has used this strategy to great effect to boost profits. In July 2013 the South Korean company posted record profits of $8.9 billion, up 47 percent from the year before. Over the same period, Apple’s share of the smartphone market in Europe dropped from 30.5 to 25 percent. This was no doubt partially due to the popularity of Samsung’s Galaxy S4, whose new features included the S-Translator, which enables the user to translate nine languages either from speech to text, or from text to speech.

Status anxiety

Soccer teams also take advantage of planned obsolescence. At the beginning of each season, most teams release at least two replica uniforms for fans to buy. The home and away shirts are restyled to be noticeably different from last year’s uniform. This type of planned obsolescence is based on status anxiety. Many fans will choose to buy the new shirt to keep up with other fans, or to show loyalty to their team, even though the shirt that they bought a year ago may still look as good as new. ■

Children in Zimbabwe wear soccer shirts donated by English soccer teams. Soccer fans in Europe will not buy last season’s shirts because the styling is updated each season.

TIME IS MONEY

TIME-BASED MANAGEMENT

IN CONTEXT

FOCUS
Product development

KEY DATES
5th century BCE The ancient Greeks use discounted cash flow to take into account the amount that money devalues during lengthy investment appraisal decisions.

1764 English inventor James Hargreaves invents the “spinning jenny”—a device that enables textile workers to spin eight spools of cotton at once, rather than just one.

1994 Nissan executive Chris Baylis claims that “simultaneous engineering” is the quickest and most effective way of achieving “optimum design solution.”

2001 Software developers in Utah, US, produce a manifesto for the agile software development approach.



Traditionally, new products have been developed in a **linear sequence**, moving from one stage of design to the next.

By forming **multidisciplinary teams**, all elements of product design can be completed simultaneously.

This **reduces** design costs.

This allows for **faster development**.

Time has a monetary value. For example, if employees spend an afternoon in an unproductive meeting, their time costs the company money. There is also an “opportunity cost,” since the meeting prevents them from doing other tasks that are potentially more productive. This is a typical concern of time-based management, which appraises the use of time in the same way that other models focus on raw materials and overheads. A time-based approach allows companies to manage labor effectively across the company, to gather true-cost data, and to cut costs by reducing the amount of time to develop and launch new products.

One way to reduce time costs on a project is to use a process called “simultaneous engineering.” This

See also: Creativity and invention 72–73 ▪ Profit versus cash flow 152–53 ▪ Leading the market 166–69 ▪ The value chain 216–17 ▪ Lean production 290–93 ▪ Simplify processes 296–99 ▪ Critical path analysis 328–29



In a linear process of new product development, the evolving prototype or individual parts move separately, back and forth, between departments. This is time-consuming and costly.



In a simultaneous engineering approach, all departments are represented in one multidisciplinary team, working together to solve new problems, and saving time and money.

strategy involves working on all the design processes required to launch a new product at the same time, rather than in a linear sequence, and can reduce new product development time by months or even years.

Comparing approaches

Traditionally, companies have pushed new products through a linear sequence of development, where each department involved in the design works in isolation, completing their task before passing the product to the next department. In this way, the part-made product might move between design, engineering, and production departments.

However, this approach can lead to time-consuming mistakes. For example, when new cars are being designed, different departments might work on various parts in isolation and in a certain sequence. When the various subassemblies are finally put together at the prototype stage, the result is often unsatisfactory. And in order to correct one thing—such as a beautiful seat creating visibility problems once in position—parts may have to bounce back through several departments.

The alternative approach, chosen by time-based manufacturers, is to use a team of people from different departments, all working together on a new product from the beginning. Project managers play a key role, since they must ensure that the multidisciplinary team members agree to the necessary design trade-offs at a very early stage in the development process. Design integrity is achieved the first time around without any reworking, slashing the amount of time taken to launch the new product.

Time-based management only works effectively in companies that employ flexible, multiskilled staff, who, in turn, respects each another's skills and value each other's input. A nonlinear process means that managers must be willing to work with a less rigid structure, and encourage a culture of trust.

This management approach forms the basis of many technology companies today, since it allows them to respond more quickly to changes in the market and customer needs, while providing employees with a more autonomous, creative, and productive work environment. ■

Agile software development (ASD)

Within the software industry, changes in components and customer demands happen rapidly and repeatedly. This means that developers have had to find ever-faster and better ways of managing projects.

In 2001, a group of software developers met in Utah, to discuss how this might be done, and their conclusions form the basis of the agile software development approach. This recognizes the customer as the highest priority, and embraces changing requirements (even at late stages of development) in order to give the customer the greatest competitive advantage. However, the founders note that this can only be achieved when "business people" take a flexible and trusting approach, hold daily face-to-face conversations with developers, and provide all the support they need. Coupled with regular reflection on team practice, these conditions will allow self-organizing teams to produce fast, brilliant designs.

A PROJECT WITHOUT A CRITICAL PATH IS LIKE A SHIP WITHOUT A RUDDER

CRITICAL PATH ANALYSIS



IN CONTEXT

FOCUS
Planning procedures

KEY DATES
1814 Napoleon's invasion of Russia fails because the Grande Armée is not equipped with the type of clothing needed to survive the winter.

1910 US mechanical engineer Henry Gantt invents the Gantt chart, which shows start and finish dates for all activities that need to be completed in order to finish a project.

1959 Morgan Walker and James Kelley publish their groundbreaking paper "Critical Path Planning and Scheduling."

1997 In his book *Golden Chain*, Israeli physicist Eliyahu Goldratt advises managers to plan for uncertainties by creating "resource buffers," which can be deployed to solve problems when they arise.

In a good strategy plan, **all the activities** that must be completed in order to finish a project **are identified**.

These activities are ordered in a **logical sequence**.

When possible, activities are planned to **run simultaneously** to save time.

Critical activities that, if delayed, will stop the project from being completed on time **are highlighted**.

A project without a critical path is like a ship without a rudder.

To minimize the amount of time needed to complete a complex project, managers frequently use a process known as critical path analysis (CPA). CPA was developed by mathematicians Morgan Walker and James Kelley, and was first used in 1957 by the chemical manufacturer, DuPont, to schedule a program of factory closures in the most cost-effective way. By following Walker's and

See also: Gaining an edge 32–39 ▪ The value chain 216–17 ▪ Lean production 290–93 ▪ Simplify processes 296–99 ▪ Time-based management 326–27

On this critical path network for a 20-day project, the nodes (circles) record finish times. The time the task should take is recorded at the top, while the time it must be completed by to keep the project on track is recorded at the bottom. Tasks B, D, and G form the critical path since they must be completed promptly; the other tasks all have more time than they need.



Kelley's advice, DuPont saved 25 percent in the shutdowns. In the early 1960s, NASA used critical path analysis to defeat Soviet Russia in the Space Race. Through careful project scheduling, NASA was able to advance its spacecraft and rocket-development programs.

Planning tool

CPA is a planning tool that plots a project's stages in a logical sequence, indicating which of the component activities need to be finished before others can start. It allows for activities to be scheduled simultaneously to save time. Activities that are critical to the project are identified—these are steps, which if delayed, will hold up the completion of the whole project.

Project managers illustrate this information visually, using a step-by-step network diagram. The most important part of the diagram is the critical path, which shows the activities where there is no float (spare) time. If a critical activity looks like it could be delayed, management will need to act, probably by employing extra people and machinery. These resources can be moved from noncritical activities that have float time.

Saving time and money

Manufacturers might use CPA to plan the launch of a new product. By identifying jobs that can be performed simultaneously, the manufacturer should be able to reduce the amount of time needed for development, allowing it to launch onto the market sooner. Completing projects earlier also reduces costs. For example, a company might use CPA to reduce the amount of money spent on hiring expensive machinery. By studying the network the manager can predict when to rent a piece of machinery and for how long. ▪

Sydney Opera House

One of the modern world's architectural wonders, the Sydney Opera House is a dramatic example of what can go wrong when projects are not properly planned and managed. When the world-famous performing arts center was opened in 1973, it was ten years late, and had cost 14 times more than its original budget.

In an attempt to open the building to the public as soon as possible, the government ordered building work to commence in 1959, before the Danish architect, Jørn Utzon, had finalized his drawings.

The decision to start construction work early led to a series of problems. For example, the podium columns that were initially used proved to be too weak to support the roof. As a result, time and money were wasted replacing these columns. Unfortunately for Utzon, it was initially his design that was unfairly blamed for the delays and cost overruns, rather than poor project management.

Architectural icon The Sydney Opera House is a feat of engineering and design, despite the difficulties encountered during its construction.



TAKING THE BEST FROM THE BEST

BENCHMARKING

IN CONTEXT

FOCUS
Competitive advantage

KEY DATES
240 BCE The Romans capture a Carthaginian ship during a storm. They build new boats based on this design and defeat the Carthaginians at the Battle of Aegus.

1819 Scottish industrialist James Finlayson sets up a textile factory in Tampere, Finland. His production methods are modeled on those used by Lancashire's world-class cotton mills.

1972 Ajax, the Dutch soccer team, wins the European Cup playing "total soccer," which allows outfield players to take any position on the field. Spanish team FC Barcelona subsequently adopts the same strategy and goes on to achieve great success.



To become an **industry leader**...

...a company must identify its **most-successful competitor**...

...and adopt the **best practices** of its rival.

Take the best from the best.

If the performance of a company is adequate but unspectacular, it may seek to identify areas that would help it rise above the competition. The process of benchmarking allows a business to improve efficiency by comparing its performance against other organizations. The goal is to identify, and then learn from, best practice in the industry. Best practice might come, for example, from a competitor who achieves the lowest unit costs, the best customer satisfaction ratings, or the shortest lead times. The rival's approach is then carefully evaluated, including such factors as the equipment, training, and production methods used. Once understood, best practice can be adopted in the hope that it will raise the performance of the company to the level of the industry leader.

Cost effective

Some companies try to become more efficient via simple trial and error, but this can be slow and costly. One of the advantages of benchmarking is that it is a relatively cheap way to improve performance, because there is no need to replicate the expensive mistakes made by other

See also: Study the competition 24–27 ▪ Keep evolving business practice 48–51 ▪ Avoid groupthink 114 ▪ Ignoring the herd 146–49 ▪ Avoiding complacency 194–201 ▪ Simplify processes 296–99 ▪ Applying and testing ideas 310–11

businesses. Improvements can come quickly so that once the process of benchmarking has identified effective practices, these methods can be adopted. The changes should lift performance to the level achieved by the industry leader, so that any competitiveness gap is eliminated quickly. In the future, benchmarking can be repeated on a regular basis.

Benchmarking in practice

In the 1980s, the US photocopier manufacturer Xerox used benchmarking to restore its market share. For ten years, it had been losing customers to its Japanese rivals Canon and Ricoh. These companies had been gaining ground because they were able to undercut the prices charged by Xerox, without compromising on product quality. To identify what they were doing wrong, Xerox bought their rivals' products and took them apart. They discovered that Canon and Ricoh designed their machines so that they were made from a relatively small number of common components. Design simplicity enabled the competition to benefit from economies of scale; bulk-buying components reduced operating costs, making it possible for Canon and Ricoh to offer consumers lower prices. Xerox responded by simplifying its designs, so that the commonality of components across Xerox models rose from 20 to 70 percent.

Xerox's US management team also visited Japanese photocopier factories to learn more about their production methods. Upon their return, the team members adopted many of the production methods they had seen. Benchmarking also enabled Xerox to improve the reliability of its products. From 1981 to 1990, customer complaints fell by 60 percent. Over the same period Xerox's manufacturing costs fell by more than 50 percent, which enabled the company to match the prices charged by the Japanese, while maintaining its profit margins.

> Benchmarking provides an inventory of creative changes that other companies have enacted.
>
> **John Langley**
>
> **UK Barclays Bank executive**

Raising standards

Governments have also used benchmarking to improve performance. For example, from 2000 to 2009, the Organization for Economic Cooperation and Development (OECD) surveyed education standards in 65 countries and identified that Finland achieved the highest rankings in reading, mathematics, and science. Teachers from around the world now visit Finland every year to learn more about the Finnish educational success. ■

Ferrari's pit-stop crew has a clear chain of command, allowing them to refuel the car and change all four tires in less than seven seconds.

Benchmarking across industries

Some companies learn from another organization that operates in a completely different market. For example, in 2005, two doctors from London's Great Ormond Street children's hospital were struck by the efficiency of the Ferrari pit crew during a Formula 1 race.

Alan Goldman and Martin Elliot observed that only one person in the crew gave orders, avoiding time lost in discussion, and pit-stop routines were standardized. Crew members specialized in one task, which they practiced over and over, until it was perfect.

Goldman and Elliot changed working arrangements at Great Ormond Street by applying Ferrari best practice: clear job descriptions meant that each member of staff knew what their role was, and a leadership position was assigned for each shift. As a result, patient handover errors between the operating room and intensive care unit unit fell by 70 percent.

DIRECTO

RY

DIRECTORY

Business is all about succeeding, often against considerable odds, and to do so its practitioners have drawn on a range of insights from a number of related disciplines. It requires an understanding of people, numbers, and systems, so it is perhaps not surprising that a large proportion of its key thinkers come from the fields of psychology, mathematics, and engineering. Some of them have proved adept at turning theory into practice, building large businesses that continue to evolve and grow over the long term. The main part of this book has examined the work of some of those key thinkers in detail; here we look at others whose impact on the business environment is marked, from industrial designers and theorists to inspirational leaders and management gurus.

RICHARD BRANSON

1950–

Founder of the Virgin Group of businesses, Richard Branson was born in 1950 in Surrey, UK. In 1969 he started a mail-order record company called Virgin, which then expanded into retail stores. In 1972 he built a recording studio, and began his own record label. The Virgin brand expanded into diverse areas, and the Virgin Group today consists of more than 200 companies in more than 30 countries, including Virgin Atlantic airlines, Virgin Radio, and Virgin Galactic.
See also: Beating the odds at start-up 20–21 ▪ Creating a brand 260–65 ▪ Generating buzz 276–78

SUBIR CHOWDHURY

1967–

An expert on quality management, Subir Chowdhury was born in Chittagong, Bangladesh in 1967. He earned a degree in aeronautical engineering at the Indian Institute of Technology, Kharagpur, before studying industrial management at Central Michigan University, MI. His consulting work within diverse industries led him to develop the LEO (Listen, Enrich, Optimize) solution, popularized in his book, *The Ice Cream Maker*. This approach says that by making "quality" the responsibility of every employee, individual quality leads to process quality and organizational success.
See also: Quality sells 318–23

CLAYTON CHRISTENSEN

1952–

Clayton Christensen is considered one of the world's top management thinkers. Born in Utah in 1952, he worked as a missionary for the Church of Jesus Christ of Latter-day Saints in South Korea from 1971 to 1973. On his return to the US, he studied economics at Brigham Young University, Utah, and Oxford University, UK, before earning an MBA and doctorate at Harvard Business School. While working as a management consultant he helped found Innosight, a public policy think tank. Now a professor of business administration at Harvard Business School, Christensen has published widely; his first book, *The Innovator's Dilemma*, is an international best seller.
See also: Changing the game 92–99 ▪ Crisis management 188–89 ▪ Avoiding complacency 194–201

ROBERTO CIVITA

1936–2013

Brazilian media baron Roberto Civita was born in Milan, Italy, in 1936. His family moved to the US shortly after his birth, then to Brazil around 10 years later, where his father founded the Abril publishing company. Civita studied for several degrees at various US universities, in subjects as diverse as nuclear and particle physics, journalism, economics, and sociology. After stints working at *Time* and Abril, in 1968 he started *Veja*, Brazil's best-selling weekly magazine. His successful media and educational enterprises led *Forbes* magazine to estimate his net worth as $4.9 billion at his death in 2013.
See also: Rupert Murdoch 337

KATHLEEN EISENHARDT

1947–

Stanford University professor Kathleen Eisenhardt is a leading expert in strategy within high-velocity markets and industries, such as Silicon Valley. Originally trained in mechanical engineering (studying at Brown University, RI), Eisenhardt then earned an MSc in computer science and a PhD in business at Stanford. Her 1998 book *Competing on the Edge* (co-written with Shona Brown) is a classic text.
See also: Avoiding complacency 194–201 ▪ Coping with chaos 220–21

HENRI FAYOL

1841–1925

Born in Istanbul, Turkey, in 1841, Henri Fayol studied engineering at the Ecole des Mines de Saint Etienne in France before becoming a mining engineer. His innovative approach to technical problems and management led him to develop organizational theories that altered contemporary thinking. He was the first person to conceptualize the organization of an industrial company, and conducted groundbreaking work on operational excellence.
See also: Simplify processes 296–99 ▪ Critical path analysis 328–29

BILL GATES

1955–

William Henry Gates was born in Seattle, WA, in 1955. His father was a lawyer and his mother was active in the civic and corporate world. Gates began programming computers at 13 with his friend Paul Allen, with whom he later co-founded Microsoft. Gates studied law at Harvard University for two years before pulling out to set up Microsoft with Allen in 1975. As CEO, Gates built Microsoft into one of the world's largest companies. In 1994 he set up the William H. Gates charitable foundation, with an initial contribution of $28 billion.
See also: Leading the market 166–69 ▪ The right technology 314–15

PANKAJ GHEMAWAT

1959–

Born in Jodhpur, India, Pankaj Ghemawat lived in the US for 30 years before moving to Spain. He demonstrated academic excellence at any early age; he was accepted for a PhD at Harvard Business School at 19, finishing it in just three years. After working for a short time at consulting company McKinsey & Company, he returned to Harvard to become its youngest-ever professor. An expert on global strategy, he controversially questioned the idea of globalization, claiming that companies need to find a balance between "local" and "global."
See also: Understanding the market 234–41

SUMANTRA GHOSHAL

1948–2004

Organizational expert Sumantra Ghoshal was born in Kolkata, India. He studied physics at Delhi University and worked as a manager at Indian Oil before completing PhDs at MIT and Harvard Business School in the US. In 1994 he joined London Business School, where he became professor of strategic management. He wrote 12 books, two of which revolutionized corporate management: *Managing Across Borders* and *The Individualised Corporation*.
See also: Organizational Culture 104–09

GARY HAMEL

1954–

Strategist Gary Hamel got his PhD at the University of Michigan, MI, before joining the faculty of the London Business School in 1983. Ten years later he founded a consulting business in Silicon Valley, CA, to gain experience at the cutting edge of high-tech companies. Today he also works as a visiting professor at Harvard and Oxford universities. In 1995 he co-authored a best-selling book with C. K. Prahalad called *Competing for the Future*, which introduced the concepts of "core competence" to the business world.
See also: Protect the core business 170–71 ▪ C. K. Prahalad 338

JOHN H. JOHNSON

1918–2005

Media magnate John Harold Johnson was born in Arkansas City, AR. The grandson of slaves, he was unable to further his education because local high schools would not accept black students, but shone academically after his family moved to Chicago. After winning a scholarship to the University of Chicago, he became the editor of a corporate magazine. In 1942, using a loan secured against his mother's furniture, he began a black-oriented magazine that later became known as *Ebony*. In 1951 he started *Jet*

magazine, and by 1982 his holdings in book and magazine publishers, TV, radio, and cosmetic companies were large enough to make him the first African-American to appear on the *Forbes* 400 Rich List.
See also: Gaining an edge 32–39 ▪ Changing the game 92–99

JOSEPH JURAN
1904–2008

Born in Romania, Juran emigrated with his family to the US at eight years old. Academically brilliant, he skipped four grades at school, then completed a BSc in electrical engineering. By 1937 he was chief of Industrial Engineering at Western Electric but he was seconded to Washington, DC, to improve the efficiency of the lend-lease program (by which the US lent funds to the Allied Forces). He then returned to academia; in 1951 he published *The Quality Control Handbook*, which became a management classic.
See also: Lean production 294–95 ▪ Quality sells 318–23

INGVAR KAMPRAD
1926–

Swedish businessman Ingvar Kamprad is the founder of furniture retailer IKEA. Born in Pjätteryd, Småland, he started trading for fun as a boy, selling matches then stationery in his neighborhood. When he was 17, he was rewarded by his parents with money for good school grades, and the teenager used this to start his own business. Kamprad began by selling door-to-door, then started a mail-order service. In 1948 he began selling locally made furniture and the company expanded. Renowned for products that are both stylish and inexpensive, IKEA has grown to encompass 284 stores in 26 countries by aiming to "allow people with limited means to furnish their houses like rich people."
See also: Changing the game 92–99 ▪ Anticipating demand 290–91

ROSABETH MOSS KANTER
1943–

Harvard professor of business studies Rosabeth Moss Kanter was born in Cleveland, OH. She studied sociology to PhD level before pursuing a career in business research. Kanter has taught at Harvard and Yale universities, and published many books on business management techniques, including *Men and Women of the Corporation*, which is regarded as a classic in critical management studies.
See also: Organizational culture 104–09 ▪ The value of diversity 115

PHILIP KOTLER
1931–

Generally regarded as the founder of modern marketing management, Kotler was born in Chicago in 1931. He earned his PhD in economics at MIT, and did postdoctoral work at Harvard University. Kotler was responsible for repositioning marketing within companies, moving it from a peripheral to a more central position. He also shifted emphasis away from price and toward meeting customer needs. Kotler is the author of more than 50 books, including the classic *Marketing Management* (1967).
See also: The marketing model 232–33 ▪ Understanding the market 234–41 ▪ Marketing mix 280–83

JOHN KOTTER
1947–

Harvard professor John Kotter is an expert on leadership and change. He initially trained in electrical engineering and computer science, but followed his first degree with a doctorate in business administration from Harvard Business School. Ranked number one "leadership guru" by *BusinessWeek* magazine in 2001, Kotter has written 17 books, including the best-selling *Leading Change* (1996).
See also: Leading well 68–69 ▪ Changing the game 92–99

ESTEE LAUDER
1908–2004

Estée Lauder was born to a family of Jewish immigrants in Queens, NY, in 1908. She was taught how to make beauty products by her uncle, a chemist. Beginning by selling her own products at local beauty salons, Lauder built a business that was valued at approximately $3.2 billion in 1995.
See also: Quality sells 318–23

KONOSUKE MATSUSHITA
1894–1989

The founder of Panasonic, Konosuke Matsushita was born in Wakayama, Japan. Following family financial misfortunes, Matsushita was sent to Osaka at nine to become an apprentice. In 1917, at 22, he set up his own business making electrical sockets, and in 1918 started a new company, which was later renamed "National" and then "Panasonic." His leadership style was extolled by

John Kotter in his book *Matsushita Leadership* (1997).
See also: John Kotter 336 ▪ Leading well 68–69

ELTON MAYO

1880–1949

Australian management guru and industrial psychologist Elton Mayo was born in Adelaide. At the city's university he studied medicine, philosophy, and psychology, and his research into the psychological causes of industrial unrest led to an invitation to join Harvard Business School, where he was part of the team that performed the celebrated Hawthorne experiments. These demonstrated that the perfomance of employees is influenced as much by their surroundings as by their skills.
See also: The value of teams 70–71 ▪ Is money the motivator? 90–91 ▪ Kaizen 302–09

ROSALIA MERA

1944–2013

Co-founder of Zara clothing retailer, Rosalía Mera was born in La Coruña, Spain, to a working-class family. She dropped out of school at 11 to work as a seamstress. At 13, she went to work in a clothing store where she met Amancio Ortega, who was to become her husband. Nine years after their marriage in 1966, they opened the first Zara store, selling inexpensive clothes based on couture designs. By 2013 there were 1,700 Zara stores around the world, and *Forbes* magazine named her "the wealthiest self-made woman on the planet."
See also: Gaining an edge 32–39 ▪ Reinventing and adapting 52–57

AKIO MORITA

1921–99

The founder of Sony was born in Kosugaya, Japan. He showed a love of mathematics from an early age, and studied physics at Osaka Imperial University. While in the navy in World War II, he met Masaru Ibuka, with whom he later set up the Tokyo Telecommunications Engineering Corporation. Renamed "Sony" in 1958, the company produced the first transistor TV and the game-changing Sony Walkman. Morita was an early champion of building an international business; It was the first Japanese company to build factories in the US and to have US members on the board.
See also: Gaining an edge 32–39 ▪ Keep evolving business practice 48–51 ▪ Changing the game 92–99

RUPERT MURDOCH

1931–

Media baron Keith Rupert Murdoch was born in Melbourne, Australia. He went to boarding school in Geelong, Australia, then traveled to Oxford, UK, to study economics. When his father died in 1952, Rupert was bequeathed a regional newspaper, *the Adelaide News*. Murdoch learned the trade through an apprenticeship at the *Daily Express* in London, then returned to Australia to take control of his paper. He drove circulation higher by delivering a more dramatic mix of crime and scandal; the increased revenues allowed him to begin buying more papers. Between 1968 and 2000 he created a global empire of mass media. Despite being involved in the newspaper "hacking scandal" of 2011–12, his business—News Corp—reported revenues of $34 billion in 2012.
See also: Stand out in the market 28–31 ▪ Roberto Civita 334

VINEET NAYAR

1962–

Indian businessman Vineet Nayar was born in Pantnagar, in the foothills of the Himalayas. He studied mechanical engineering, earned a MBA, then entered business. In 2007 he became CEO of HCL Technologies, where he practiced his controversial approach to management of "employees first," inverting the standard operational pyramid. Using this approach, detailed in a book of the same name, Nayar has transformed HCL into a $4.6-billion company with offices in 31 countries.
See also: Organizing teams and talent 80–85 ▪ Is money the motivator? 90–91

HENRI NESTLE

1814–90

Heinrich "Henri" Nestlé was born in Frankfurt-am-Main, Germany. He trained as a pharmacist, but in 1833 fled local riots to settle in Vevey, Switzerland. He continued to experiment, and in the mid-1860s began to produce a baby food that combined milk with wheat flour. The popularity of his "farine lactee" (the first formula for babies) allowed him to open sales offices and factories in the UK, France, Germany, and the US, while also acquiring local companies. Nestlé went on to invent the first form of milk chocolate and soluble coffee.
See also: Creativity and invention 72–73 ▪ Ignoring the herd 146–49

INDRA NOOYI

1955–

Indra Krishnamurthy Nooyi was born in Madras (now Chennai), India. After graduating with a masters in finance and marketing from the Indian Institute of Management, Nooyi completed a masters at Yale Management School, funded by working as a nighttime receptionist. She then spent six years as an international strategy consultant, before joining the telecommunications company Motorola as a director of strategy. In 1994 she became the chief strategy officer at PepsiCo, and was instrumental in positioning the company for growth in China, the Middle East, and India. She became the company's CEO in 2006, and chairperson in 2007. **See also:** Balancing long- versus short-termism 190–91

TAIICHI OHNO

1912–90

Taiichi Ohno was a self-taught engineer whose insights and methods helped Toyota become one of the largest motor companies in the world. Born in Dalian, China, in 1912, Ohno started work at Toyota when he left school, and spent the rest of his working life there. He is best known for devising the "just-in-time" production system, where parts or products are not ordered until just before they are needed, rather than having large stock holdings on hand. He also advocated flexible manufacturing methods to allow tailoring for different international markets and to reduce waste. He is regarded as one of the production geniuses of the 20th century. **See also:** Anticipating demand 290–93 ▪ Lean production 294–95

PIERRE OMIDYAR

1967–

Founder of eBay Pierre Omidyar was born in Paris, France, to Iranian parents. He moved to the US with his family as a child, where he studied computer science at Tufts University. After graduating, he worked in software development for Apple before co-founding a company that developed business-to-business e-commerce software in 1991. Omidyar left to work for a mobile communication business in 1994, but continued to explore the possibilities of e-commerce for consumers in his spare time. In 1995 he launched Auction Web, which later became eBay. In 2012 it reported revenues of $22.6 billion. **See also:** The weightless start-up 62–63 ▪ Changing the game 92–99

TOM PETERS

1942–

US management authority Tom Peters was born in Baltimore, MD. He studied civil engineering at Cornell University at a masters level, then earned an MBA and PhD in business at Stanford Business School. From 1966 to 1970 he served in Vietnam for the US Navy, then worked for the US government. From 1974–81 he was a consultant for McKinsey and Company, before leaving to work independently after the publication of his book *In Search of Excellence*, the business classic he wrote with Robert Waterman. **See also:** Coping with chaos 220–21

C. K. PRAHALAD

1941–2010

Coimbatore Krishnarao Prahalad was born in Tamil Nadu, India. After completing a degree in physics at the University of Madras, Prahalad joined Union Carbide, and worked there for four years (he described this as a major "inflection point" in his life). He then studied for an MBA at the Indian Institute of Management followed by a PhD at Harvard Business School. En route to becoming a professor of business administration, he became renowned as a consultant, after his advice invigorated the failing Philips electronics business. He has published many best-selling books, including *Competing for the Future*, co-authored with Gary Hamel. He is considered one of the world's top management thinkers. **See also:** Protect the core business 170–71 ▪ The learning organization 202–07 ▪ Gary Hamel 335

CARLOS SLIM HELU

1940–

Mexican business magnate Carlos Slim Helú was born in Mexico City. After studying civil engineering at the Universidad Nacional Autónoma, Mexico, he founded his own business, Inmobiliaria Carso, at 25. Through acquisition and shrewd management, he built on this to establish a large group of businesses—Grupo Carso—which included companies in the food, retail, construction, mining, and tobacco industries. International acquisitions and mergers followed, with partnerships with companies such as Microsoft, with whom Slim Helú joined forces in 2000 to launch

the Spanish portal, T1msn (now ProdigyMSN.com). In March 2013, *Forbes* magazine stated that Helú was the world's richest person, with a net worth of $73 billion.
See also: Effective leadership 78–79 ▪ Bill Gates 335

ALFRED SLOAN
1875–1966

Alfred Sloan was a groundbreaking industrialist who radically changed the ways that companies were organized in the early 20th century. He was born in New Haven, CT, and studied electrical engineering at MIT before joining a small company that manufactured ball bearings. By the age of 24 he was its president, and within another four years had led it from near-bankruptcy to an annual profit of $60 million. The company was bought by General Motors, which went on to make Sloan its president in 1923. He famously reorganized GM into separate, autonomous divisions, in a decentralizing process that was much copied. He was also the first to introduce a systematic approach to strategic planning. A renowned philanthropist, he died aged 90 of a heart attack.
See also: Simplify processes 296–99 ▪ Critical path analysis 328–29

BROOKS STEVENS
1911–95

Industrial designer Brooks Stevens was born in Milwaukee, WI. He had polio as a child, and occupied himself during long stays in bed by drawing. He later studied architecture at Cornell University, NY, before opening his own furnishings business. He said that "planned obsolescence" was the mission of industrial design, and that design should make consumers want something "a litte newer, a little better, a little sooner than is necessary." Stevens was one of the most influential industrial designers of the 20th century.
See also: Planned obsolescence 324–25

ALVIN TOFFLER
1928–

American futurologist and writer Alvin Toffler was born in New York City, where he grew up and went to university. He and his wife, Heidi, embarked on many collaborative research projects, identifying current and future societal shifts. In Toffler's best-known book, *Future Shock* (1970), he envisaged a post-industrial future in which companies outsource labor, technology displaces the worker, and change takes place so fast that people cannot adapt fast enough to thrive.
See also: Reinventing and adapting 52–57 ▪ Focus on the future market 244–49 ▪ Forecasting 278–79

CHER WANG
1958–

Entrepreneurial thinker Cher Wang was born in Taiwan and sent to the US for school. She studied economics at University of California, Berkeley. After graduating, she worked for a computer company, where the heavy computer cases inspired her to wonder if computing could be made "smaller." In 1997 she co-founded technology company HTC based on this idea. By 2013 the company was making one in six of all smartphones used in the US. An avid philanthropist, Wang is renowned for her remarkable insights into technology trends.
See also: Creativity and invention 72–73 ▪ The right technology 314–15

YANG YUANQING
1964–

Yang Yuanqing was born in Anhui province, China. While studying for a masters in computer science, he took a sales job at technology company Legend (now Lenovo). By 29 years old he headed up the company's personal computer business, and in 2009 he became CEO. Yang transformed the traditional company into a performance-oriented business with a diverse staff, supplier network, and customer base. In 2012 and 2013 he famously redistributed his bonus among the company's employees.
See also: Effective leadership 78–79 ▪ Changing the game 92–99

ZHANG XIN
1965–

Businesswoman Zhang Xin was raised in Hong Kong, and took on factory work as a teenager to save for an education in the UK. She received an MA from the University of Cambridge in 1992, then worked in investment banking. In 1995 she and her husband co-founded SOHO China, a property development company, offering prime properties to Beijing's new super-rich class. Success was not immediate, but SOHO China is now the country's largest and most profitable property company. In 2013 Zhang's net worth was $3.6 billion.
See also: Beating the odds at start-up 20–21

GLOSSARY

Acquisition The purchase of the whole or part of a business by another business.

Activity-based costing (ABC) A method of business accounting that analyzes overhead costs to determine which activities create which costs. This results in a more accurate analysis of costs than traditional **cost accounting**, which measures direct costs and then adds an estimate of **overheads**.

Asset Any economic resource that is owned by a company that can be used to generate value for the business.

Balance sheet A summary of a company's financial value, incorporating its **assets**, **liabilities**, and **equity** of the owners, which is usually published at the end of its financial year.

Bankruptcy A legal declaration that an individual or a company is insolvent, meaning that they cannot repay their debts.

Benchmarking A method of evaluating a company by comparing its perfomance and practices with those of the **market-leading** business or businesses.

Board In business, a term that refers to the board of directors of a company or organization. Board members are either elected or appointed to oversee the company's activities and performance.

Brand The perceived "identity" of a company or product that distinguishes it from the competition. This can include many things, from name, design, logo, and packaging to broader, external affiliations that may set it apart from its rivals (such as ethical trading standards and production initiatives).

BRIC economies An acronym for the four emerging economies of Brazil, Russia, India, and China. They are considered by some to pose a challenge to Western economic supremacy.

Budget A financial plan that lists all planned expenses and incomes of business unit, project, or venture.

Bull market A financial term describing a period in which **share** values increase, leading to optimism and economic growth.

Buy out Taking control of a company by purchasing a controlling interest of its **stock**.

Capital The money and physical **assets** (such as machinery and infrastructure) used by a company to produce an income.

Cartel A group of businesses that agrees to cooperate in such a way that the output of their goods or services is restricted, and prices are driven up.

Cash flow The incomings and outgoings of cash in a business, representing its operating activities.

CEO An acronym for Chief Executive Officer, the highest executive in a company. Appointed by and reporting to the **board**.

Closed innovation The idea, popular in the 20th century, that innovation in a company should take place strictly within its own walls, by its own employees, rather than drawing on knowledge, ideas, and expertise from outside.

Collusion An agreement between two or more companies not to compete, so that they can fix prices.

Commodity A term for any item, product, or service that can be freely bought, sold, and traded.

Comparative advantage The ability to produce goods or services at a lower opportunity cost than rivals.

Competitive advantage A strategy whereby companies position themselves ahead of competitors either by charging less or by **differentiating** their services or products from those of their rivals.

Conglomerate A **corporation** that is made up of two or more businesses that may operate across different fields and sectors.

Corporation An independent legal entity, owned by **shareholders**, that is authorized to conduct business. Corporations exist separately and apart from their employees and shareholders and have their own rights and **liabilities**: they can borrow money, own **assets**, and sue or be sued.

Cost accounting A method of business accounting that aims to determine costs by measuring direct costs and then adding an estimate of **overheads**.

Cost leadership A strategy whereby companies aim to offer the cheapest product(s) or service(s) in their industry or market and thereby gain a **competitive advantage** over their rivals.

Creative accounting Accounting practices that seek to portray a company's finances in either a positive or negative light through a range of accounting techniques. Although unconventional, and often used to depict artificial **profit** levels, such practices are generally legal.

Credit crunch A sudden reduction in the availability of credit in a banking system. A credit crunch often occurs after a period in which credit is widely available.

Crowdsourcing Tapping into collective online knowledge by inviting large numbers of people, via the Internet, to contribute ideas on different aspects of a business's operations. A related concept is "crowdfunding," which involves funding a project or venture by raising **capital** from individual investors via the Internet.

Default The failure to repay a loan under the terms agreed.

Deficit A financial situation in which a business's expenditure exceeds its **revenue**.

Demand The desire, willingness, and ability of consumers to purchase a product or service.

Differentiation A strategy whereby companies distinguish their products or services from the offerings of rival companies through cost, improved features, or marketing and promotion in order to achieve a **competitive advantage** in a crowded market sector.

Distribution The movement of goods and services from the producer or manufacturer through a distribution channel (such as a vendor or agent) to the end consumer, customer, or user.

Diversification A strategy to minimize **risk** and raise **revenue** by distributing expenditure across a number of different business units or products, and across a range of different **markets** and even geographical areas.

Dividend An annual payment made by a company to its **shareholders**, usually as a portion of its **profits**. Dividend payouts are made at the discretion of a company's directors.

Early adopter A business or a customer who uses a new product or new technology before others.

E-commerce Abbreviated from "electronic commerce," the buying and selling of products and services by businesses and consumers via the Internet and electronic systems.

Emotional intelligence (EQ) The ability to perceive, control, and evaluate emotions in oneself and in others. US psychologist Daniel Goleman noted that high EQ is common in business leaders and facilitates other leadership traits.

Emotional Selling Proposition (ESP) A **marketing** strategy that creates an emotional connection (such as pride, humor, or desire) between the customer and the **brand**, impelling them to purchase.

Entrepreneur A person who takes commercial **risk** in the hope of making a **profit**.

Equity In **investment**, the value of **shares** issued by a company; "equity" also denotes part or full ownership in a company. In accounting, the net worth of a company or individual, calculated by subtracting total **liabilities** from total **assets**.

First-mover advantage The benefits resulting from being the first business to enter a **market**.

Fixed cost A cost, such as rent or salaries, that does not change according to the number of goods or services produced.

Forecasting The use of past data to predict future trends and assess the likely **demand** for a business's goods and services.

Free market An economy in which decisions about production are made by private individuals and businesses on the basis of **supply** and **demand**, and in which prices are determined by the **market**.

Groupthink A quirk of group dynamics, in which individuals in a group place higher priority on achieving a consensus with one another than on effective and rational decision-making.

Hygiene factors A series of workplace factors identified by US psychologist Frederick Herzberg that, if poorly managed, contribute to job dissatisfaction. A separate set of factors—motivators—encourage job satisfaction.

Inflation The steady increase in the overall prices of goods and services in an economy.

Interest rate The amount of interest—the charge for borrowing a sum of money—paid annually by a borrower, measured as a percentage of the total amount borrowed.

Inventory Goods and materials that are held in **stock** in a warehouse or in any other similar premises. The term can also refer to the total value of a company's **assets**, including raw materials, and unfinished and finished products.

Investment In business terms, the activity of purchasing bonds or **shares** in a company. Can also refer to a company's expenditure on items intended to yield an increase in operational performance, such as new tools.

Kaizen The Japanese term for "good change," in business. It refers to continuous improvement to enhance productivity.

Leverage The extent to which people or companies fund their activities with borrowed money. When high leverage is widespread in the economy, the degree of debt can create a short-term boom; but this is often followed by a crash.

Leveraged buy-out (LBO) The acquisition of a business by a company or group of individuals using a large proportion of borrowed money.

Liability The financial obligations of a company to outsiders or claims against its **assets** by outsiders.

Liquidity The ease with which an **asset** can be bought or sold, without adversely affecting the asset's value. Cash is the most liquid asset, since its value remains constant.

Long tail A term coined by UK writer and entrepreneur Chris Anderson to describe how the overall sales of niche products at the thin "tail" of a demand curve may be greater than sales of the most popular products at the "head."

Market The consumers who buy a product or service. Also refers to any physical or virtual location where buyers and sellers trade goods, such as a store or a website.

Marketing Promoting the sale of products or services to consumers or other businesses. Effective marketing identifies, anticipates, and responds to customers' needs.

Market leader A product or company that has the largest **market share**.

Market share A business's percentage of sales in a specific industry or sector.

Merger The combining of two or more businesses to form a separate organization with a new identity. The goal of a merger is often to increase **shareholder** value beyond the sum of the two (or more) companies.

Micro loan A small loan made to entrepreneurs or small businesses.

Micropreneur An entrepreneur who starts and builds a small business of their own, often while on salaried employment.

M-commerce An abbreviation of "mobile commerce," the use of portable devices such as laptops and smartphones to conduct business transactions online.

Monopoly A **market** in which only one company is active. Monopoly companies generally have low product diversity, which they can sell at a high price due to lack of competition.

Niche market A small group of people with an interest in a product or service that is not addressed by mainstream providers.

Off-balance-sheet finance Accounting methods whereby some **liabilities** or **assets** are not recorded on a company's **balance sheet**.

Open innovation The idea that a business's talent base, and consequently its insight into new products and services, can be expanded by drawing on expertise from outside the company, often via social media and the Internet.

Operating margin A measure of profitability—the ratio of a company's operating **profit** to its **revenue**.

Outsourcing The contracting out of specific tasks or functions in a business to outside companies.

Overhead Any ongoing expense of a business, such as rent of premises; also known as "operating expense."

Positioning A **marketing** strategy that establishes a distinct position for a **brand** in the **market**.

Private equity A type of **investment** in which private **assets** or borrowed funds are used to finance private companies (those not listed on a public **stock** exchange).

Private limited company (Ltd) A company in which the **liability** of members is limited to the value of their **investment** in the company. The company's **shares** cannot be bought and sold by the public. Private limited company is a term used primarily in the UK. The closest US equivalent is limited liability company.

Product portfolio A strategy that involves assembling a diverse range of products or business units.

Profit The surplus of a company's **revenue** after all expenses, taxes, and operating costs have been met.

Publicly traded company In a publicly traded company the **liability** of members is limited to the value of their **investment** in the company. A publicly trated company's **shares** are traded on the **stock market** and can be bought and sold by the general public.

Recession The period of time in which the total output of an economic area decreases.

Reserves In business, **profits** retained by a company for future use and not distributed to **shareholders**.

Return on Equity (ROE) A measure of a company's financial performance, based on **profit** and the **equity** of **shareholders**.

Return on Investment (ROI) The ratio of money gained to the amount invested in the company.

Revenue Also known as sales and turnover, the income earned by a business over a period of time. The revenue earned depends on the price and number of items sold.

Risk In **investment** terms, risk is the uncertainty associated with an investment or **asset**. A high-risk investment, for example, may yield a high return; but if unsuccessful, it could cause the investor to lose everything. Operational risk is the risk of failure due to shortcomings in procedures, people, or systems.

Securities An umbrella term for a range of **investment** instruments that are traded on **stock markets**, such as bonds, options, and **shares**.

Shadow bank A nonbank financial institution—such as the treasury function of a business—that lends money to businesses. Shadow banks offer similar services as traditional banks, but are not subject to supervisory and regulatory burdens.

Share A unit of ownership in a company, signifying ownership of **stock**.

Shareholder An individual or organization that holds **shares** in a company. A shareholder is also known as a stockholder.

Speculating Making high-risk **investments** that could yield large returns, but bear a high **risk** of resulting in loss.

Start-up A business that has—or is being—launched from scratch.

Stock The **equity** stake of the **shareholders** in a business. The term also describes goods owned by a business that are held on its premises or in a warehouse, and are available for sale or **distribution**.

Stock market A place where bonds and **stocks** or **shares** in a company are bought and sold.

Supply The amount of a product or service that is available for consumers to buy.

Supply chain The people and processes involved in the production and **distribution** of goods or services.

Surplus An excess in **supply** over **demand**—when the production of goods, services, or resources exceeds their consumption.

Sustainability A strategy in which the business ensures that the resources it uses will be replaced, such as a paper manufacturer planting trees.

Synergy The supposed additional performance benefit that is achieved when two companies or units of a business are joined together.

Takeover The purchase of one business by another.

Treasury function Using a company's treasury (its financial operations department) to achieve the optimum balance between **liquidity** and income from the company's **cash flows**. Other activities can include **profit** generation, **risk** management, planning and operations, and **shareholder** relations.

Unique Selling Proposition (USP) A **marketing** strategy whereby companies distinguish their products from their rivals by offering customers something that their competitors do not or cannot offer.

Value chain The theory of US professor Michael Porter that the chain of a company's interrelated activities can be exploited to add value to its products or services. These activities relate to the flow of a product from production to purchase by the customer.

Venture capital Funds invested in a **start-up** at its earliest phase.

Viral marketing The launching of a product or service via the Internet or social media to attract rapid and widespread consumer interest.

Working capital The **capital** available for use in the day-to-day operations of a business, calculated as the difference between current **assets** and current **liabilities**.

INDEX

Numbers in **bold** refer to main entries

A

accountancy and playing by the rules 120–23
- *see also* business ethics; financial strategy

adaptation *see* business adaptation and growth
advertising 272–73
- big data analysis 316–17
- and brand creation 260–61
- *see also* marketing

agile software development (ASD) 327
AIDA marketing model 242–43
Air India 314–15
Amazon **34–36**, **39**, 174, 175, 209, 240, 267, 317
Anderson, Chris 208–09
Ansoff's matrix 256–57
- *see also* strategic planning

Apple 37, **96–99**, 127, 191
- iPad **97–98**, 149, **241**
- iPhone 29, 38, **97**, 148–49, 168, 196, 249, 266, 325
- iPod and iTunes 29–30, 55, **96–97**, 168

Aquinas, Thomas 224–25
Aracruz 129
Argyris, Chris 206–07
Arkwright, Richard 166–67
ASOS 275
Australia
- CrimTrac system 315
- Sydney Opera House 329

Avis 248

B

Barnes & Noble 198
Barratt, Thomas 273
Barton, Bruce 272–73
Bass, Frank 233
Belbin, Meredith **82**, 84
Ben & Jerry's ice cream 183
Bench 283
Benetton 217
Bennis, Warren 69, 86, **87**
Bernays, Edward 273
Berners-Lee, Tim **174**, 177
Bezos, Jeff **39**, 63, 99, 174, 267
black swan events and future forecasting 198
The Body Shop 262, **263**
Borden, Neil 281, **283**
Bose Systems 181
Boston Consulting Group 252–55
BP 41, **200–01**
brand creation
- and advertising 260–61
- differentiation and focus strategies 182
- and ethics 263
- and social media 263
- "third place" concept 262–63
- translatable brands 261
- unique selling proposition (USP) 261–62

brand loyalty 35–36, 98, **322**
Branson, Richard 60, 320, **334**
Brin, Sergey 174
British Aerospace (BAe) 148
British Airways 223, **248–49**
Buffet, Warren 49, 129, 144, 147, **149**, 155
business adaptation and growth
- business practice, evolution of 48–51
- capability maturity model 218–19
- enablers and enterprise capabilities 49–50
- Greiner curve 47, **58–61**
- growth rate, deciding on 44–45
- growth-share matrix and product portfolio 253–55
- learning organization 204–07
- long-term survival 57
- overexpansion dangers 45
- process adaptation 55–57
- recession and adaptation 56–57
- self-financeable growth rate (SFG) 44–45
- shareholders *see* shareholders
- sustainability **31**, **45**, 50–51, 57
- technological change 54–55
- vision broadening and realization 43, 50
- *see also* leadership; management; marketing; strategic planning

business ethics 222, **224–27**
- accountability and governance 130–31
- accountancy and playing by the rules 120–23
- appeal of 270
- and brand creation 263
- "creative accountancy" practices 122–23
- greenwashing 268–69
- leadership 226–27
- legal standards 226
- "mark to market" accounting 122–23
- price-fixing and collusion 223

C

Cadbury 171, **193**
Carnegie, Andrew **40–41**, 213
Caterpillar 123
chaos theory, and financial crises 220–21

China, economic development **134–36**, 154, 279
Chowdhury, Subir 334
Christensen, Clayton **94–95**, 96, 99, **334**
Cisco Systems 71
Citroën 313
Civita, Roberto 334
Coca-Cola **165**, 260, 265, 271, 272, 276
Collins, Jim 101–03
competitive advantage
  benchmarking 330–31
  and brand loyalty 35–36, 98, **322**
  and copycat products 148–49
  creativity and invention 72–73
  customer needs, understanding 38–39
  and customer service 249
  failure, dealing with 98–99
  first-mover advantage 34–36
  first-mover advantage, and disruptive innovation 94–96
  first-mover advantage, timing considerations 37–39
  first-mover mistakes, learning from 36–37
  Five Strategic Forces model 212–15
  Internet business **34–36**, 176
  MABA (market attractiveness/business attractiveness) framework 192–93
  market mapping 26–27
  and secondary activities 217
  start-up phase 24–27
  substitutes, threat of 214
  SWOT analysis **25–27**, 184
  technical and product superiority 36–37
  value chain 216–19
  see also innovation; marketing; strategic planning
competitiveness
  and organizational culture 108
  and price-fixing **222–23**, 239
  and waste reduction 301
complacency avoidance
  "5-why" technique 199
  10X (major) change, awareness of 197–98
complacency avoidance *(cont)*
  black swan events and future forecasting 198
  catastrophe, averting 200–01
  complementary products 197
  front line, importance of listening to 198–99
  thinking outside the box 199–200
  see also risk management; strategic planning
corporate culture *see* organizational culture
Covey, Stephen 131, **225**, 226
crisis management 59–60, 102, **188–89**
  see also leadership; management
customer loyalty 264–67
  Likert scale 266
  loyalty programs 267
  offering more for less 288–89
  online challenges 267
  product quality, importance of 265–67
customer service
  agile software development (ASD) 327
  choice, and business strategy 180, 181
  and competitive advantage 249
  customer relationship marketing (CRM) 240
  feedback and Internet business 176–77, 312–13
  fragmentation and micromarkets 238–39
  needs, understanding **38–39**, 136–37
  and quality provision 322–23

D

Daewoo Group 153
DaimlerChrysler 115, **187**
Dawkins, Richard 275
debt levels
  borrowing and lending 128–29
  and leverage 150–51
  see also financial crises; financial strategy
Dell 149, 295, **298**
demand
  lean production **290–93**, 307–08
  stock management 294–95
Deming, W. Edwards 49, 51, 323
Dr. Martens shoes 56
Drucker, Peter 69, 109, 126, 130, 199, **237**, 240–41, 252–53, 279, 323
DuPont 328–29
Dunkerton, Julian 122
Dutch East India Company 127
Dyson 38, 164, **261**

E

e-commerce *see* Internet business
easyJet 47, **261**, 263
eBay 63, **98**, 174–75, 338
Eisenhardt, Kathleen 335
emotional intelligence 110–11
Emotional Selling Propositions (ESP) **29–30**, 31
  see also marketing
employees
  company failures and risk management 142–43
  developing countries, labor migration 205
  front line, importance of listening to 198–99
  involvement, and chaos management 220–21
  involvement, and participative management 137, **304–06**
  job satisfaction and "hygiene factors" 90–91
  job satisfaction and organizational culture 108
  kaizen and efficiency improvement 304–09
  learning organization 204–07
  satisfaction, and productivity 136–37, **206**
  staff empowerment 79, **86–87**, **306–07**
  staff turnover and learning and development motivation 205–06
  wage levels and turnover 134–35

Enron **142**, 150, 154, **227**
entrepreneurship 20, 21, 43, **46–47**
  micropreneurism, start-up phase 63
  see also start-ups
equity and performance
  cost-cutting measures 125
  opportunistic behavior by directors 125
  ownership, control and personal gain 124–27
  return on equity (ROE), maximizing 155
  risk assessment 142–43, 156–57
  see also organizational culture; shareholders
Estée Lauder 321
ethics *see* business ethics
executive officers
  accountability and governance 130–31
  customers and employees, awareness of needs 136–37
  and perks 124–27
  risk management 143–44
  travel expenses and cost-cutting measures 125
  see also leadership; management

F

Facebook 37, **72–73**, 89
Fayol, Henri 78, 112, **335**
Ferguson, Sir Alex 84–85
Fernandes, "Tony" 21
Ferrari 182, **331**
financial crises
  and chaos theory 220–21
  contingency planning 210
  global credit crisis 102, 125, **129**
  Japan 144–45
  leverage and debt 150–51
  oil crises and scenario planning 211
  and risk management 151, 154
financial strategy
  accountancy and playing by the rules 120–23
financial strategy *(cont)*
  activity-based accounting 159
  borrowing and lending 128–29
  capital management, MABA (market attractiveness/ business attractiveness) framework 192–93
  cost accounting 158–59
  employee wage levels and employee turnover 134–35
  gain as motivation 90–91
  hedge betting 128–29
  International Financial Reporting Standards (IFRS) **121–22**, 123
  investment and dividends 126–27
  and marketing 134–37
  price-fixing and competitiveness **222–23**, 239
  risk, and other people's money 140–45
  shadow banks 129
  see also profit levels; shareholders; strategic planning
first-mover advantage *see* under competitive advantage
Five Strategic Forces model 212–15
"5-why" technique, and complacency avoidance 199
Ford, Henry 78, 99, 136, **166–67**, 246, 290–91
Ford Motors **134–35**, 247, 288–89, **297–98**
Four Ps and marketing mix concept 280–83
  see also marketing
Fuld, Richard 102, 143, **145**
future forecasting, and black swan events 198

G

Gates, Bill 238, **335**
Geneen, Harold 186, **187**
General Electric (GE) **129**, 190, 191
  GE-McKinsey matrix **192–93**, 255
General Motors (GM) 144, **155**, 247, 325
Gerber 189
Getty, Jean Paul 75
Ghemawat, Pankaj 335
Ghoshal, Sumantra 335
Ghosn, Carlos 79
Gillette **35**, 36, 168, 171
GlowCap 95
Goleman, Daniel 110–11
Google 34, **36–37**, 72–73, 87, **174**, **249**, 276, 300
Gores, Alec 157
GPS technology 311
Greiner, Larry 47, **58–61**
Grove, Andy 102, **196–99**, 200, 201
growth *see* business adaptation and growth

H

Hamel, Gary 171, 256, **335**
Hammer, Michael **49–50**, 51
Handy, Charles **76–77**, 143, 300
hedge betting 128–29
  see also financial strategy
Herzberg, Frederick 87, **90–91**, 306
Hess, Edward 45
Hill, Emma 73
Hofstede, Geert **106–08**, 109
Honda 120–21, 127, **206**, 307–08
Hoover **38**, 271
Hornby 295
Humphrey, Albert 25, **27**
Humphrey, Watts S. 218–19
Hyundai 289

I

IBM 107, 109, **253**
IKEA **30**, 262, **336**
India, economic growth 135–36
Innocent 108, **262**
innovation
  collaboration and creativity, encouragement of 71, **206–07**
  and differentiation strategy **181–82**, 183

innovation *(cont)*
  and diversity management 115
  and invention 72–73
  kaizen and efficiency improvement 304–09
  learning from failure 164–65
  nine-dots puzzle 88–89
  open 312–13
  patent wars and first-mover advantage 36
  production improvement 296–99
  solutions and knowing what the customer wants 241
  thinking outside the box 88–89
  see also competitive advantage; market leaders; R&D
Instagram 41
Intel 102, **196–97**, 201
International Financial Reporting Standards (IFRS) **121–22**, 123
Internet business
  as 10X (major) change 197–98
  big data analysis 316–17
  brand creation *see* brand creation
  competitive advantage **34–36**, 176
  customer loyalty challenges 267
  customer relationship marketing (CRM) 240
  e-commerce 34–36, 174–76
  e-commerce and AIDA marketing model 243
  and feedback 176–77, 312–13
  “Long Tail” theory 208–09
  mobile commerce 276–77
  niche marketing 177
  personal service, importance of 177
  small is beautiful 174–77
  supply barriers, removal of 209
  see also social media; technological change
investment *see* financial strategy

J

Japan
  earthquakes and contingency planning 210
Japan *(cont)*
  economic crisis 144–45
  kaizen, and efficiency improvement 304–09
JCB 191
Jobs, Steve 73, **94**, 95, 97, 99, 103, 127, 149, 168, 241, 298
Johnson, John H. 99, **335–36**
Johnson & Johnson **38–39**, 189
Jupiter Shopping Channel 157
Juran, Joseph 300–01, **336**

K

kaizen, and efficiency improvement 304–09
Kamprad, Ingvar 336
Kanter, Rosabeth Moss 336
Kay, John 127
Kellogg’s 311
Kidston, Cath 50, 51
Kodak 184, **185**
Kotler, Philip 29, 243, 248, 249, 283, **336**
Kotter, John 46, 69, **336**
Kraft Foods 193

L

Lauder, Estée 336
leadership
  behavioral management 74–75
  chaos management 220–21
  charismatic 78–79
  cost-leadership strategy 180–83
  credibility, importance of 79
  crisis management 59–60, 102, **188–89**
  effective 78–79
  egotism, dangers of 100–03
  emotional intelligence 110–11
  ethical 226–27
  personality traits 111
  qualities 68, 69
leadership *(cont)*
  skills, and business growth 46–47
  staff empowerment 79, **86–87**, **306–07**
  successor training 69
  yes-men, dangers of 74–75
  see also executive officers; management; organizational culture, business adaptation and growth; teamwork
learning organization 204–07
Lee Kun-Hee 51, 56, **57**
Lehman Brothers **102**, 143, 145, 154
Levitt, Theodore 29, 180, 246–48, **249**
Likert scale, customer loyalty 266
“Long Tail” theory 208–09
loyalty *see* brand loyalty; customer loyalty
lysine cartel 223

M

MABA (market attractiveness/business attractiveness) framework 192–93
McCarthy, Edmund Jerome 281–82
McDonald’s 24–25, **30–31**, 56, 91, 171, 295
McKinsey matrix (General Electric) **192–93**, 255
Made-by 227
Madoff, Bernard 153
management
  accountability and governance 130–31
  arrogance leading to indiscipline 102
  change management and information technology (IT) 314–15
  chaos management 220–21
  club culture 76, 77
  complacency avoidance *see* complacency avoidance
  consultants, and innovation 88–89
  crisis management 59–60, 102, **188–89**
  effective 68–69, **112–13**

management *(cont)*
  egotism, dangers of 100–03
  experience, and business practice 48–49
  failure, learning from 164–65
  groupthink, avoiding 114
  kaizen and efficiency improvement 304–09
  long- versus short-termism 190–91
  middle management 49–50, 51
  Mintzberg's management roles 47, **112–13**
  participative management 137
  project management, critical path analysis 328–29
  public and private companies, contrast between 191
  qualities 69
  risk management *see* risk management
  staff empowerment 79, **86–87**, **306–07**
  stylistic typologies 76, 77
  time-based 326–27
  see also business adaptation and growth; executive officers; leadership; organizational culture; teamwork
Manchester United 143
marketing
  AIDA model 242–43
  Bass Model 233
  big data analysis 316–17
  brand champions 275
  customer experience management (CEM) 240
  customer perception and market leaders 169
  customer relationship marketing (CRM) 240
  and customer service 246–49
  customers' needs and preferences, understanding 236–39
  Emotional Selling Propositions (ESP) **29–30**, 31
  familiarity as source of differentiation 30–31
  financial strategy 134–37
marketing *(cont)*
  focused 236–41
  four Ps and marketing mix concept 280–83
  functional uniqueness, elusive nature of 29
  market gaps 22–23
  market leaders 166–69
  market mapping 26–27
  market research 239–40
  Measurement Models 233
  myopia 246–48
  neuromarketing 240–41
  niche markets **22–23**, 177, 180, 182
  promotions and incentives 271
  psychographic profiling 239
  sales forecasting 278–79
  stand-out 28–31
  strategies 232–33
  technological advantage 167–68
  uniqueness, maintaining 30, 31
  word-of-mouth 274–75
  see also advertising; business adaptation and growth; competitive advantage
Marks & Spencer (M&S) 201
Maslow, Abraham **70–71**, 73
Matsushita, Konosuke 336–37
Mayo, Elton 70, 112, **337**
Mera, Rosalie 337
mergers and takeovers 60–61, **186–87**
Merrill Lynch 110
Microsoft 215
Mintzberg, Henry 47, **112–13**
mobile commerce 276–77
  see also Internet business
morality *see* business ethics
Morita, Akio 311, **337**
Motorola **50**, 51
Mourinho, José 69
Muji 263
Mulberry 73
multinationals and profit shifting 222
Murdoch, Rupert 337
MySpace 89

N

Nayar, Vineet 47, **337**
Nestlé 62, **254–55**, 273
Nestlé, Heinrich 337
Netflix **55–56**, 209, 317
new entrants *see* start-ups
Nike 29, 108, 275
nine-dots puzzle 88–89
  see also innovation
Nintendo 89
Nissan **79**, 313, 326
Nokia **148–49**, 184, 276, 309
Nooyi, Indra 338
Nordstrom 267
Not on the High Street 177

O

Ohno, Taiichi 292–93, **338**
Oliver, Jamie 59
Olympus cameras **131**, 154
Omidyar, Pierre **98**, 174–75, **338**
organizational culture
  arrogance problems 108
  benefits of 108
  capability maturity model (CMM) 218–19
  collectivist and individualist cultures, differences between 75, **107**
  competitiveness *see* competitiveness
  corporate governance and accountability 130–31
  cultural dimensions 106–08
  groupthink problems 108
  hierarchy and power 106–07
  and job satisfaction 108
  learning organization 204–07
  long- versus short-term orientation 107–08
  masculinity and femininity, differences between 107
  non-static nature of 109
  organizational dynamics 76–77

organizational culture *(cont)*
  risk management *see* risk management
  Shamrock Organization theory 77
  tolerant 74–75
  visual aspects 108
  see also equity and performance; leadership; management; shareholders

P

Paccar 215
Page, Larry 174
Pears soap 273
performance, and equity *see* equity and performance
Peters, Tom 55, **221**, 298, 307, **338**
Pixar 83
Ponzi schemes 153
Porter, Michael **180–82**, 184, 197, **212–15,** 218–19
Post-it Notes 42, 165
Prahalad, C. K. 171, 256, **338**
price-fixing, and competitiveness **222–23**, 239
Primark 136–37
Procter and Gamble **38–39**, 72–73, 89, 233, 260, 273
production
  Business Process Reengineering (BPR) programs 308–09
  cash cow and product assessment 252–55
  custom production 298
  direct-selling 298–99
  distribution system 239
  growth-share matrix and product portfolio 253–55
  improvement and innovation 296–99
  lean production **290–93**, 307–08
  mass production 297–98
  new features, promotion of 325

production *(cont)*
  planned obsolescence 324–25
  process simplification 296–99
  product quality and customer loyalty 265–67
  product superiority and technological change 36, 37–38
  quality products and design 320–23
  simultaneous engineering 326–27
  time-based management 326–27
  see also waste reduction
profit levels
  and business ethics 122–23
  multinationals and profit shifting 222
  price-fixing and competitiveness **222–23**, 239
  pushing to highest feasible point 121
  quality and premium prices 266–67
  reinvesting profits 301
  shareholders and profit maximization 124–25, **237–38**
  stock management 294–95
  versus cash flow 152–53
  see also financial strategy
Progressive Corp. 316–17

Q

quality
  circles and teamwork **305–06**, 308
  and premium prices 266–67
  product quality and customer loyalty 265–67
  product superiority and technological change 36, 37–38
  products and design 320–23
  products and value analysis 323
  provision and customer service 322–23
  Total Quality Management 56

R

R&D
  applying and testing ideas 310–11
  big data analysis 316–17
  and differentiation strategy **181–82**, 183
  and market research 310–11
  multidisciplinary aspect 311
  reinvesting profits 301
  see also innovation
Ratners 238
Reeves, Rosser 29, **31**
risk management 40–41, 157
  bankruptcy, protection against 141–42
  black swan events and future forecasting 198
  capability maturity model 218–19
  contingency planning 210
  diversification 257
  employees, and firm failures 142–43
  equity and performance 142–43, 156–57
  executives and CEOs 143–44
  feedback, relevance of 109
  and financial crises 151, 154
  financial risk and other people's money 140–45
  and income inequality 145
  and learning organization 207
  leverage and debt levels 150–51
  micropreneurism 63
  off-balance-sheet risk 154
  organizational culture *see* organizational culture
  pre-pack administration 141–42
  return on equity (ROE), maximizing 155
  sales forecasting 278–79
  scenario planning 211
  shareholders **140–41**, 144, 145
  start-ups 20–21, 41
  taxpayer bailouts and too-big-to-fail firms 144–45
  unconsolidated subsidiaries 154
  see also complacency avoidance; strategic management

Rockefeller, J. D. **164–65**, 222
Roddick, Anita **262**, 263
Rover 307–08
Royal Bank of Scotland 74, **127**, 144
Royal Dutch Shell 211
Rumelt, Richard 184, **185**
Ryan, Arthur 137
Ryanair 182–83

S

Samsung 31, 38, 51, **56–57**, 321–22, 325
Selfridges **265–66**, 267
Semco 137
Senge, Peter 204–05, 206, **207**
Shamrock Organization theory 77
  see also organizational culture
shareholders
  boom and bust markets 146–47
  bull market **121**, 146–47
  and corporate accountability 130–31
  customer priority, importance of 238
  dividends 126–27
  herd instinct, ignoring 146–49
  pressure and partnership development, start-ups 60–61
  private limited companies 125
  and profit maximization 124–25, **237–38**
  public limited companies 191
  risk management **140–41**, 144, 145
  share buybacks 155
  share certificates, first 127
  see also equity and performance; financial strategy; organizational culture
Shingo, Shigeo 291–92
Siemens 62, **95–96**
Singapore Airlines (SIA) 183
Slim Helú, Carlos 338–39
Sloan, Alfred 339
Smith, Adam 124, 180, **218**, 219
Snapple 23
social media
  and crisis management 188
  crowdsourcing 313
social media *(cont)*
  websites **54**, 57
  word-of-mouth marketing 274–75
  see also Internet business; technological change
Sony **168**, 307, 311, **337**
Speedo 27
Spotify 61
Starbucks 262
start-ups
  bureaucracy and red tape 60
  business expansion 43–45
  business plan 21
  commitment of time and effort 62–63
  competitive advantage *see* competitive advantage
  crisis of control 60
  focus strategy 182
  growth crises and Greiner Curve 58–59
  Long Tail benefits 209
  micropreneurism 63
  new entrants, strategic planning threat to 214–15
  opportunism, and luck 42
  risk management 20–21, 41
  self-financeable growth rate (SFG) 44–45
  shareholder pressure and partnership development 60–61
  see also entrepreneurship
Stevens, Brooks 339
strategic planning 184–85
  Ansoff's matrix 256–57
  buyer power 214
  chaos theory 220–21
  and consumer choice 180, 181
  core business protection 170–71
  cost-leadership strategy 180–83
  crisis management 188–89
  critical path analysis 328–29
  differentiation strategy **181–82**, 183
  Five Strategic Forces model 212–15
  focus strategy 180, 182
  industry positioning 215
  MABA (market attractiveness/ business attractiveness) framework 192–93
  new entrants, threat to 214–15
  outsourcing 171
strategic planning *(cont)*
  secondary interests, selling off 171
  statements and actions, differences between 198–99
  strategic inflection point **196–97**, 200–01
  substitutes, threat of 214
  supplier power 214
  takeover bids 148
  see also business adaptation and growth; competitive advantage; complacency avoidance; financial strategy; risk management
Superdry 30, 45, **122**
sustainability **31**, **45**, 50–51, 57
  see also business adaptation and growth
Swiss Pocket Knife 200
SWOT analysis **25–27**, 184

T

T-systems International 125
Tata Group 108, **131**, 308
Taylor, Frederick Winslow 159
teamwork
  and anomie 70, 71
  Belbin Team Inventory 82, **84**
  benefits 82
  collaboration and creativity, encouragement of 71, **206–07**
  collective work products 85
  effectiveness factors 83–84
  group dynamics (groupthink) 114, 115
  groups and sense of belonging 70–71
  and learning organization 205
  quality circles **305–06**, 308
  storming and norming 82–83
  talent management 84–85
  time-based management 326–27
  see also leadership; management
technological change
  Apple *see* Apple
  business adaptation, importance of 54–55

technological change *(cont)*
  information technology (IT) 314–17
  marketing and technological advantage 167–68
  and product superiority 36, 37–38
  see also Internet business; social media
Ted Baker 227
terrorism, impact of 200
Tesco 165, 181, **257**
TiVo 317
Toffler, Alvin 54, **339**
Total Quality Management 56
Toyota 44, 108, 135, 155, **169**, 189, 199, **290–93**, **304–06**
Toys R Us 37, **147–48**
Tune Hotels 21, 29, **293**
TWG Tea 27
Twitter **22**, 54

U

UK
  bank bailouts 122
  pre-pack administration 141–42
UN, Brundtland Report 269
Unique Selling Proposition (USP) 29, 31
US
  family spending pattern 135–36
  Generally Accepted Accounting Principles (GAAP) 122, 123

V

value analysis
  kaizen and efficiency improvement 304–06
  and lean production **290–93**, 307–08
  and quality products 323
  value chain and competitive advantage 216–19
Victorinox 200
vision
  brand creation 261–62
  broadening and realization 43, 50
  crisis management 188–89
  and leadership *see* leadership
  shared, and learning organization 204–05
Volkswagen **301**, 324

W

Wal-Mart **265**, 279
Wang, Cher 339
waste reduction
  and competitiveness 301
  Juran's production ideal 300–01, **336**
  lean production **290–93**, 307–08
  see also production
Wedgwood 308
Welch, Jack 69, 75, 190, **191**, 206, 216
Wikipedia 313
Wonga.com and payday loans 123

XYZ

Xerox 331
Yang Yuanqing 339
Zappos 267
Zara 283
Zhang Xin 339
Zhang Yin 47
Zurich Insurance Group 322–23

ACKNOWLEDGMENTS

Dorling Kindersley would like to thank Chris Westhorp for proofreading; Margaret McCormack for the index; Harish Aggarwal for jacket design; Alex Lloyd and Ankita Mukherjee for design assistance; and Alexandra Beeden, Henry Fry, and Miezan van Zyl for editorial assistance.

PICTURE CREDITS

The publisher would like to thank the following for their kind permission to reproduce their photographs:

(Key: a-above; b-below/bottom; c-center; f-far; l-left; r-right; t-top)

21 Getty Images: Bloomberg (bl). **27 Getty Images:** Al Bello (tl). **30 Getty Images:** Bloomberg (bl). **35 Alamy Images:** DPA Picture Alliance (tl). **36 Corbis:** Bettmann (tl). **38 Corbis:** Lucidio Studio Inc. (bl). **39 Corbis:** Karen Moskowitz (bl). **41 Alamy Images:** Everett Collection Historical (bl). **43 Alamy Images:** Ashway (br). **45** NASA: JPL-Caltech (tr). **47 Getty Images:** MN Chan (bl). **50 Corbis:** Jenny Lewis (bl). **56 Alamy Images:** Eddie Linssen (bl). **57 Corbis:** Bettmann (tr). **Getty Images:** Chung Sung-Jun (bl). **61 Getty Images:** Charles Eshelman (tl). **63 Corbis:** Kimberly White (tl). **69 Getty Images:** WireImage (tr). **71 Corbis:** Ann Kaplan (bl). **Getty Images:** View Pictures / UIG (tr). **73 Getty Images:** Dave M. Benett (tr). **75 Corbis:** Bettmann (bl); Jade / Blend Images (tr). **79 Corbis:** Catherine Cabrol (tl). **85 Getty Images:** Paul Taylor (br). **87 Corbis:** James Brittain (tl). Warren Bennis: (bl). **89 Getty Images:** Godong / UIG (tl). **94 Corbis:** Kim Kulish (bl). **95 Corbis:** David Cabrera / Arcaid (br). **97 Getty Images:** Bloomberg (b). **98 Getty Images:** Bloomberg (br). **101 Getty Images:** WireImage (tr). **102 Corbis:** Gonzalo Fuentes / Reuters (bl). **103 Corbis:** Porter Gifford (tr). **109 Getty Images:** Britt Erlanson (tl). **111 Getty Images:** Kris Connor (bl). **114 Corbis:** Arnd Wiegmann / Reuters (br). **121 Alamy Images:** Wavebreakmedia Ltd. PH07 (br). **123 Getty Images:** Bloomberg (tr). **125 Getty Images:** AFP (tl). **127 Corbis:** The Gallery Collection (tl). **129 Getty Images:** Bloomberg (tl). **131 Corbis:** Martin Harvey (tl). **134 Alamy Images:** Everett Collection Historical (tr). **135 Getty Images:** Yawar Nazir (bl). **137 Alamy Images:** Islandstock (tl). **141 Getty Images:** Bloomberg (tl). **142 Corbis:** Monty Rakusen / Cultura (tr). **144 Getty Images:** Giuseppe Cacace (tl). **145 Corbis:** Endiaferon / Demotix (bl). **Getty Images:** Bloomberg (tr). **149 Corbis:** Brooks Kraft (tr). **Getty Images:** Phil Boorman (bl). **151 Corbis:** Roderick Chen / First Light (tl). **153 Corbis:** John Eveson / Frank Lane Picture Library (br). **154 Getty Images:** James Nielsen (cr). **157 Corbis:** Alan Levenson (tr). **Getty Images:** Bloomberg (bl). **159 akg-images:** (bl). **165 Corbis:** (bl). **167 Corbis:** Frank Moore Studio (tr). **168 Corbis:** George Grantham Bain (tl). **169 Corbis:** Tony Savino (bl). **171 Alamy Images:** Lilyana Vynogradova (tr). **174 Corbis:** James Leynse (bl). **175 Alamy Images:** Allan Cash Picture Library (br). **176 Corbis:** Juice Images (tl). **181 David Tenser:** (br). **183 Alamy Images:** Allstar Picture Library (bl). **Getty Images:** AFP (tr). **184 Getty Images:** Cavan Images (cr). **187 Corbis:** Bettmann (tr). **189 Corbis:** Leif Skoogfors (tl). **191 Getty Images:** WireImage / R. Born (bl). **197 Alamy Images:** SiliconValleyStock (bl). **198 Corbis:** Ocean (br). **199 Corbis:** Bettmann (tl). **200** Courtesy of **Victorinox,** Switzerland: (tl). **201 Alamy Images:** PhotoEdit (tc). **Corbis:** Brooks Kraft / Sygma (bl). **206 Alamy Images:** Brett Gardner (bl). **207 TopFoto.co.uk:** (bl). **209 Getty Images:** Tim Klein (bl). **211 Getty Images:** AFP (br). **214 Corbis:** Imagerie / The Food Passionates (br). **215 Getty Images:** Allan Baxter (tl). **217 Fotolia:** Africa Studio (br). **219 Dreamstime.com:** Adistock (tl). **220 Getty Images:** Diana Kraleva (bc). **222 Getty Images:** Image Source / Dan Bannister (br). **226 Alamy Images:** Newscast (tr). **233 Getty Images:** wdstock / E+ (cra). **237 Corbis:** Steve Smith (bl). **238 Alamy Images:** Ashley Cooper (tl). **239 Rex Features:** Everett Collection (br). **241 Getty Images:** Justin Sullivan (br). **247 Corbis:** Timothy Fadek (bl). **249 Corbis:** C. Devan (bl). **Getty Images:** Duane Howell (tr). **253 Science Photo Library:** Hank Morgan (crb). **255 Alamy Images:** Interfoto (bl); The Natural History Museum (bc). **Getty Images:** Bloomberg (tr). **261 Getty Images:** AFP / EADS (tr). **262 Corbis:** Colin McPherson (bl). **263 Corbis:** Brendan McDermid / Reuters (br). **265 Rex Features:** Daily Mail (bc). **266 Getty Images:** Marco Secchi (tr). **267 Corbis:** Fotodesign Holzhauser (bl). **270 Alamy Images:** Guatebrian (cb). **273 The Advertising Archives:** (tl). **277 Alamy Images:** Benedicte Desrus (br). **279 Getty Images:** Junko Kimura / Bloomberg (bl). **283 Corbis:** James Leynse (br). **289 Alamy Images:** Marc MacDonald (bl). **Corbis:** Alexander Demianchuk / Reuters (tr). **292 Alamy Images:** Chris Pearsall (tl). **293 Getty Images:** Gerenme / E+ (tc). **297 Getty Images:** Science & Society Picture Library (br). **298 Corbis:** Bettmann (bl). **299 Getty Images:** George Frey / Bloomberg (tl); Andrew Harrer / Bloomberg (tr). **301 Alamy Images:** CoverSpot (bl). **304 Getty Images:** Kurita Kaku / Gamma-Rapho (bl). **307** 123RF.com: Hongqi Zhang (bl). **308 Getty Images:** Peter Macdiarmid (tr). **311 Alamy Images:** World History Archive / Image Asset Management Ltd. (bl). **313 Getty Images:** Jo Hale (tr). **315 Corbis:** George Steinmetz (br). **321 Getty Images:** Buena Vista Images / Stockbyte (bl). **322 Alamy Images:** Photosindia Batch11 / PhotosIndia.com LLC (cb). **323 Corbis:** Catherine Karnow (tr). **Dreamstime.com:** Weixin Shen (tl). **325 Getty Images:** Tom Shaw / Allsport (br). **329 Dreamstime.com:** Mishkacz (br). **331 Alamy Images:** DPA Picture Alliance Archive (bl).

All other images © Dorling Kindersley.

For more information see:
www.dkimages.com

The Gun Digest Book of

$7.95

GUNSMITHING TOOLS ...and Their Uses


BROWNELLS Inc.
MONTEZUMA, IOWA 50171
BROWNELL'S INC., MONTEZUMA, IOWA

The how, when and why of tools for amateur and professional gunsmiths and gun tinkerers—choosing and using practically every tool available today.

By John E. Traister

ABOUT THE AUTHOR

John E. Traister has been a firearm enthusiast for most of his life, having fired his first gun—a Remington Model 6 .22 caliber rimfire—at the age of 4. He graduated to a 20 gauge side-by-side double shotgun at age 8 and busted pigeons on his grandfather's farm nearly every weekend for years to follow. He took his first whitetail deer at age 13 and since that time has hunted extensively from New York state to Texas and in the Far East.

John blued his first gun the same year he shot his first deer. At about the same time, he also built a .32 caliber muzzle-loading pistol that featured a mainspring made from a heavy rubber band. With some practice, he was able to group the .32 caliber round balls within a 2-foot circle at 10 feet!

After attending Boston University and Berklee College (in Boston), John enlisted in the U. S. Marine Corps and was Platoon High Shooter, selected for the Parris Island rifle team, and later was a member of the Camp Cortney Skeet Team while serving with the 3rd Marine Division on Okinawa.

Traister sold his first article to the American Rifleman in the early 1960s and since that time has written over 200 articles and over 30 books. He presently divides his time between writing and working in his gun-shop in rural Virginia.

THE GUN DIGEST BOOK OF GUNSMITHING TOOLS ... and Their Uses

by JOHN E. TRAISTER

DBI BOOKS, INC., NORTHFIELD, ILL

STAFF
EDITOR
Robert S. L. Anderson
PRODUCTION MANAGER
Pamela J. Johnson
COVER PHOTOGRAPHY
John Hanusin
PUBLISHER
Sheldon L. Factor

About Our Cover

Pictured on our cover are but a few of the many, many gunsmithing tools made and/or distributed by Brownells, Inc. The Montezuma, Iowa, firm has long been the best (and often the only) source of tools, equipment and supplies for the amateur and professional gunsmith. Brownells lists over 14,000 items in a catalog that should be called the "wish book" for craftsmen; it's used by gunsmiths, stock makers, knife makers, jewelry makers and hobbyists of all sorts.

Copyright © MCMLXXX by DBI Books, Inc., #1 Northfield Plaza, Northfield, 111 60093, a subsidiary of Technical Publishing, a company of the Dun and Bradstreet Corporation. Printed in the United States of America. All rights reserved. No part of this book may be reproduced, stored in a retrieval system or transmitted in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, without prior written permission of the publisher.

The views and opinions of the author expressed herein are not necessarily those of the publisher, and no responsibility for such views will be assumed.

ISBN 0-910676-08-9 Library of Congress Catalog Card #80-67743

CONTENTS

CHAPTER 1: Tools to Get You Started

CHAPTER 2: A Place to Work

CHAPTER 3: A Workbench for Everyone

CHAPTER 4: Portable Electric Drills

CHAPTER 5: The Third Hand

CHAPTER 6: Rx for Long Gun Life

CHAPTER 7: Files and Their Kin

CHAPTER 8: Woodworking Tools

CHAPTER 9: Bluing Equipment

CHAPTER 10: The Multi-Purpose Moto-Tool

CHAPTER 11: Soldering and Welding

CHAPTER 12: Mini-Lathes for Gun Work

CHAPTER 13: The Drill Press
CHAPTER 14: The Bench Grinder
CHAPTER 15: Lathes for Metal Work
CHAPTER 16: Milling Machines
CHAPTER 17: Miscellaneous Gunsmithing Tools
CHAPTER 18: Plating Firearms
CHAPTER 19: Gunsmithing: Continuing Education
CHAPTER 20: Introduction to Pro Gunsmithing
CHAPTER 21: Gun Parts
CHAPTER 22: Gunning Calculations
CHAPTER 23: Gunsmith's Library
CHAPTER 24: Glossary of Firearms Terms
CHAPTER 25: Directory of Trade Sources (removed as it would be out-of-date)
Appendix (removed, conversion factors are easily obtained)

1 - TOOLS TO GET YOU STARTED

HIGH-QUALITY work in any trade or profession can be accomplished only with high-quality tools and a proper knowledge of their use. The gunsmithing profession is no exception. Therefore, the main objective of this chapter is to introduce the basic gunsmithing tools that are required for high-quality work. Further objectives include the proper use of these tools and how to select the best ones available for gun repair and maintenance in general.

The basic gunsmithing tools described in the paragraphs to follow are found on the workbench of practically all professional gunsmiths. This tool list below covers the minimum essential tools needed to do good work on the usual kind of firearm in need of repair. They are the "rock" on which to build or expand your professional assortment of fine tools and instruments. They should be the best quality that you can afford.

Gunsmith screwdrivers
Pin punch set
Pliers
Hammers
Knife
Spring vise
Bench vise
Sight base file
Pillar file
Scribe hook
Brushes
Wood rasp
India stones
Allen wrench set

Gunsmith Screwdrivers



This common double-wedge type screwdriver (front and side view) is not the best choice for gun work.

The selection of gunsmith screwdrivers should be given careful consideration since a marred or otherwise damaged screwhead is a sure indication that an amateur has tackled the job. The efficient holding power of a screwdriver depends upon the quality of steel in its blade, the design of the blade, and the external force that may be applied to the screwhead. The blade should also be fitted to the width of the slot for best results.

For instance, if a common double-wedge type screwdriver were used in a deep screw slot, the blade would transmit its torque to the top of the screw slot. With such a small slot area coming in contact with the blade, there is a good chance that the screw will be scored or worse yet, cause one section of the screwhead to break off. Wedge-shape tips also tend to back the driver out of the screw slot—again causing damage to the screwhead.

A screwdriver tip, ground to properly fill a screw slot, is ideal for gun repair work since the torque is applied at the bottom of the slot where the screw is the strongest; also, that blade will fill the slot completely (and should be the same width as the shank).



(Left) Here's the double wedge screwdriver in use. Note the lack of close fitting—the blade transmits its torque only to the top of the screw slot. As can be seen, this screw slot (right) was damaged by improper blade fit.



(Left) This particular blade is ideal for gun work. It has been cut to conform perfectly to a screw of specific dimensions. (Right) Notice that this screwdriver blade fits the screw slot perfectly.



A set of Grace Metal Products screwdrivers has long been a favorite with knowledgeable gunsmiths.

A set of 8 Grace gunsmith screwdrivers is shown in the photo above. They are made from standard taper bit screwdrivers with the tip of each bit ground parallel for a short distance back to give a better fit to gun screwheads. They have a high-quality feel and will handle 95% of your needs around the gunshop. If you select this set, you will also need a stock bolt screwdriver with a ½″ blade, about 15″ long. A set of jeweler’s screwdrivers will also come in handy.

″



This particular screwdriver has a long shank and ½″ blade. It’s ideal for removing stock bolts.



A set of fine jeweler’s screwdrivers will come in handy for the many small screws you will encounter during normal gunsmithing chores.

A CHAPMAN TOOL CMH-3

The Chapman screwdriver set is another popular item. It comes with 15 different tips, a screwdriver handle, ratchet and extension — all packed in a form-fitting box.

Depending upon your strength, you may find the use of the Chapman ratchet handy when it comes to cinching down larger screws such as the tang screw on the Winchester Model 94. The best method of tightening down these sorts of screws may amount to using the regular screwdriver handle for preliminary tightening followed by the ratchet for final torquing.

Another good set of screwdrivers is made by Chapman Manufacturing Company. This set contains one screwdriver handle, an extension, 12 slotted head adapters, 2 phillips head adapters, a midget ratchet and 1 Allen hex-type adapter. This kit will handle nearly all of your gun repair needs, but you'll still need a long-shank bolt screwdriver as described previously.

The adapters for the Chapman screwdriver handle are relatively inexpensive and should be reshaped (if necessary) to conform to a specialized job such as an extra thin screw slot. When grinding adapters, however, be careful not to let the temperature get too hot (above 400°F) or they will lose their hardness.

Reshape the adapter so that it fits the screw slot exactly. Then inspect each adapter under a magnifying glass before use. Also carefully dress off any burrs which may be present before attempting to remove any screw. Use great care at all times as one slip can damage the finish on an expensive firearm.

Strength of the individual adapter relates closely to its size, diameter, width of blade, thickness and the like. In general, the smaller the adapter, the weaker it is, and therefore, the less torque that can be applied. The chart below shows the realistic torque for Chapman slotted gun screw adapters.

Even with a fine set of gunsmith screwdrivers, you must understand that there are some screws which cannot be removed with a screwdriver. All screws are not made, fitted or installed in the exact same manner. Neither are all screws manufactured with a proper "thread-to-thread" tolerance. Few of them are ever visually inspected before use and, therefore, they can carry a burr or chip which may jam them in position. Some screws — especially those used to secure gun sights — have a holding compound applied to them so they will not back out under recoil. It also makes them difficult, or impossible, to remove with a screwdriver.

Tapping the screwdriver in the screw slot will sometimes help to loosen the screw. This tends to drive the screw forward in the thread slot affording movement—in most cases. Liquid Wrench or WD-40 (commercial products used for loosening rusted metal screws and bolts) may also be tried. Heat applied to the surrounding area (not the screw itself) should be tried only as a last resort as intense heat will draw the hardness from most metals.

Remember, once a screw is broken, it is too late for common sense or judgment. The broken screw must then be drilled out and replaced the best way possible—often taking much time and effort.



REALISTIC TORQUE

for CHAPMAN slotted gun screw adapters.

Size	Average Working Torque	Average Breaking Torque	
CM-88	15 in. lbs.	17 in. lbs.	Finger Pressure
CM-89	31 in. lbs.	35 in. lbs.	Full Hand Pressure
CM-90	31 in. lbs.	35 in. lbs.	
CM-25	45 in. lbs.	50 in. lbs.	
CM-26	67 in. lbs.	75 in. lbs.	Full Hand or Ratchet
CM-93	67 in. lbs.	75 in. lbs.	
CM-17	94 in. lbs.	105 in. lbs.	
CM-97	99 in. lbs.	110 in. lbs.	
CM-95	103 in. lbs.	115 in. lbs.	
CM-96	135 in. lbs.	150 in. lbs.	
CM-98	144 in. lbs.	160 in. lbs.	
CM-19	180 in. lbs.	200 in. lbs.	



“Torque” doesn’t necessarily mean brute force. In many cases, the right amount of torque can be applied with the fingers alone.



Here’s an example of a fair amount of torque being used to secure the tang screw to a Winchester Model 94.



Here’s an example of how-not-to-do-it. The screw visible on this collectable Remington 4-barrel pistol has been badly buggered through the use of an improper-size screwdriver. This sort of damaged screw head is indicative of work done by the rankest amateur.



When it comes to the removal of frozen screws, the light tapping of the screw itself (as shown) will sometimes do the trick.

Pin Punch Set



For any firearm disassembly/assembly chore a quality set of drift punches is indispensable. Sets like the one shown to the left and to the right are available from any of the gunsmithing supply houses.

A set of punches is required for removing the assembly pins used in most firearms. A Grace pin punch set will handle 90% of your shop needs. Each punch is made to fit a certain pin in a gun action and the kit consists of 5 pin punches, 1 starter punch and 1 center punch.

Brownell’s offers a special gunsmith’s replaceable punch set that allows the tips to be replaced should they bend or break. The handles are made of steel with a removable knurled-chuck to hold the pins. The pins may be ground down to the exact length required for each job—giving the user a set of custom punches with a minimum investment.

There are four types of pins used in firearm assembly: the common steel pin, serrated pins, roll or spring pins and flared-tip pins. Before attempting to remove any pin, examine it carefully to determine just what type it is. Then use the appropriate punch to remove it. The object is to remove the pin without damaging it, the surrounding finish, or internal parts.

THE FOUR TYPES OF PIN PUNCHES
FLARED PIN - ROLLED PIN - SERRATED PIN - COMMON STEEL PIN



You must first position the gun so the pin will have clearance to be driven out. A padded vise works most of the time, but sometimes this is going to a lot of trouble just to remove one pin. I use a piece of a shotgun stock that was sawed off prior to installing a recoil pad—it keeps the gun high enough off the bench for driving out pins. A starter punch is used to get the pin started. This is the short, tapered, flat nose punch found in most gunsmith pin punch sets. I hold the punch squarely on the pin and then give it a short, medium-heavy tap. If it resists, I give it a harder blow. Once the pin moves, a pin punch just a bit smaller than the pin is used to drive it the rest of the way out.

If you suspect that the pin is serrated, you obviously must hit the pin on the opposite end from the tiny serrations to avoid damaging the pin or the gun parts. A close examination will reveal which is the serrated end; use a magnifying glass if necessary.

The increasing use of roll or spring pins in modern firearms makes it necessary to use special roll pin punches for removal. They permit the removal and re-use of the same pin without glaring damage to the pins. A kit of punches in sizes from $^1/_{16}''$ to $^3/_{16}''$ will take care of most of your needs in the gunshop.



When removing pins, work on a flat surface and be sure the pin won’t meet any resistance on its way out. To avoid resistance, the author used a piece of cut-off buttstock that has a stock-bolt hole in it — the pin will slide right through.



Roll-pin punches come (by necessity) in a number of sizes and shapes. It pays to have a good selection on hand.



If a screw head has been worn to the point where you can't get any purchase with a screwdriver blade, a pin punch will often do the trick when accompanied by some light tapping with a hammer.

Select the proper size punch for the pin and then insert the pilot into the hollow pin until the driving shoulders rest on the end of the pin. Then drive out the pin as discussed previously. Be sure to clean and oil the pin before replacing it.

Besides removing gun pins and using center punches for drilling, punches in general have many other uses around the gunshop. For example, a stuck screw can sometimes be loosened by tapping it with a pin punch to get it moving. Secure the firearm in a padded vise, then place the tip of the punch inside the outer edge of the screw slot and tap it with a hammer. This will usually start the screw turning when other methods have failed.

A center punch can also be used to raise metal in the bottom of dovetail slots when they are too loose to hold the sights properly. Merely rest the barrel on a solid object that won't mar the finish, and then give several hits with the center punch (a dozen or so should do it). Try the dovetail sight and, if it's still not tight enough, raise more metal with the center punch. A ballpeen hammer may also be used to *lightly* peen the shoulders of the slot downward to hold the sight tighter.



A center punch can be used to raise metal in the bottom of dovetail slots when they are too loose to hold the sights properly.



A rectangular bronze punch gives a far superior surface than round punches when it comes to removing dovetail sight bases.



For finding material to make your own parts, try searching around junk yards—you'll be amazed at the number of useful items to be found.

While we're on the subject of dovetail sights, you'll need some special punches for removing and installing dovetail sights. Conventional pin punches will mar its finish every time.

A nylon drift punch is very handy for installing and removing dovetail sights. The perfect size is a 4″ long piece of nylon $^{5}/_{16}$″ in diameter. This will take care of the majority of front-sight removals. Sometimes, however, you will encounter an extremely tight dovetail sight and the nylon drift punch is going to bend. In these cases, you'll need a rectangular bronze punch as it provides a far superior surface than round punches with which only a small portion of the punch contacts the piece—often resulting in upsetting and deformation. By contrast, on many parts, such as sights, the square-end punch gives almost 100% contact—reducing tool and part damage. A good size is ¼″ x ¼″ square. Most come in 12″ lengths and can be cut into several punches.

Of course you can make your own custom punches to fit any size hole from discarded twist drills and other hardened pieces of cylindrical stock. If you need larger punches, try searching around old car junk yards. Besides being able to purchase all the old automobile valve stems you need to grind into drift pin punches, you'll find many other useful scraps that can be made into other gunsmithing tools... and usually at next to nothing in cost.

Pliers


A good selection of pliers is imperative. The assortment shown is used daily.


Common, adjustable "combination" pliers can be purchased almost anywhere. Several sets in various sizes are a must.


Combination pliers come in handy when it comes to holding any small part against any buffing or grinding wheel.

Perhaps no other tool on the workbench is required to do more jobs than the various pairs of pliers that should be in any gunshop. The assortment shown is the one I use for nearly all gun shop requirements... from reaching inside a small action and inserting a small part, to holding red-hot screws while being blued by the oil-heat method. Insist on the steel varieties and not the cast-iron models found in dime stores and discount houses. Those manufactured by M. Klein & Co. are the best I have used, although I'm certain that other good brands are available.

Adjustable combination pliers have been around a long time. They are a common household tool and have been used for everything from driving tacks to pulling teeth, but they have a definite place in the gunshop. In general, a slip joint holds the two parts of the pliers together so that the jaws can be opened or closed to hold large or small objects. Most adjustable combination pliers have two cutting edges at the back of the jaws for wire cutting, but their main purpose is for gripping— like holding a small part against a grinding wheel.

Longnose pliers—often called "needlenose pliers"—are used with small objects in hard-to-get-at locations, such as starting the replacement of a pin or spring inside of an action. The tips of these pliers are easily bent if they are misused and they should never be used for loosening or tightening a screw or nut. Starting them, yes; but tightening them, no!

Other types of pliers similar to longnose pliers include roundnose pliers, half-roundnose pliers and flatnose pliers. All three types are used for similar situations as the longnose pliers.

Side-cutting pliers are used in gunsmith work for cutting wire—like black iron stove pipe wire used to hold barreled actions and parts while hot bluing—and other small wire-type items. Their use, however, on hardened steel or heavy material will quickly nick or dull the cutting edge.

Pump pliers (often called Channel-Locks) have a quick adjustment for widening or narrowing the jaws to hold various materials, especially round objects. The interlocking tongues and grooves on the two parts of the pliers enable the jaws to be moved closer together or farther apart.

Self-adjustable locking pliers act as a small portable vise. These pliers have a toggle and floating wedge arrangement that automatically adjust the jaws of the pliers to the size of the object they are being used on. Pressure on the handle then enables the jaws to lock around the object very tightly and remain in this position until reverse pressure is applied to release the vise grip.

The variety of cutting and gripping pliers just discussed come in a number of sizes and each has a specific purpose. Any of them can be ruined if they are used for the wrong job.

Hammers


A no-mar hammer should be one of the first items purchased by the gunsmith.


If you have a dovetail slot that's loose, you can tighten it up by lightly peening the overhang of the slot downward. This will provide a firm grip on the sight base.



(A) Ball peen. (B) Straight peen. (C) Cross peen.

(Above) This illustration provides apt descriptions of the different types of peening hammers frequently used by gunsmiths.

Hammers will find a variety of uses in bench-work: driving pins; installing or removing sights; seating inlays; peening dovetail sight bases to tighten sights; and a host of other jobs. One of the first hammers purchased by the gunsmith should be a no-mar type. These nylon, rubber or leather-headed hammers may be used for a multitude of jobs around the shop where you have to pound but don't want to mar the metal or wood you are working on. Of the several sizes available, you'll probably want to get the 1″ diameter tip size first. You can also purchase a brass hammer tip that will screw into the 1″ no-mar hammer. When this is used in combination with a no-mar plastic, nylon or phenolic tip, it makes an excellent all-purpose gunsmith hammer.

Metal working hammers may be classified with respect to peen as:

1. Ballpeen.
2. Straightpeen.
3. Crosspeen.

They are used mainly to hammer metal; that is, to indent or compress it, to expand or stretch, that portion of the metal adjacent to the indentation. One use of peening hammers is to tighten dovetail sights. Remove the sight base and lightly peen the top of the dovetail slot—forcing the overhang downwards to grip the sight base tighter. Marred metal areas can sometimes be peened back into their original condition if care is taken; and, of course, a gun part—such as a bar or shaft—may be straightened by peening with the convex portion of the hammer.

You may eventually find need for a wooden mallet and also a rawhide mallet for pounding on parts where none of the other hammers seem to work. The wooden mallet will be useful in tapping wood chisels for carving and stock inletting, and the rawhide mallet will be helpful when trying to loosen stubborn gun parts. You'll also find the rawhide mallet handy for several other uses.

Bench Vise


TURNS A FULL CIRCLE...
VERSA-VISE
STANDING UP OR LAID FLAT...

The Versa-Vise is one of the most useful items a gunsmith can have. It turns a full 360° in either the upright or laid-flat position.

Eventually, every hobbyist and professional gunsmith will want a heavy machinist's vise. However, this is sometimes not practical for the beginner. One reason is the lack of a good sturdy workbench. Obviously, if the bench will not stand the strain, a heavy vise is not much good. If the work area has to be temporary—like on the kitchen table—then a portable vise should be purchased.

One completely portable vise goes by the trade name Vacu-Vise. This vise fastens instantly to any non-porous surface with super vacuum power. To attach, merely apply slight pressure to the top of the vise and push the side lever down. It then acts as a "third hand" in any gunsmith's shop, kit or on the range.

The Versa-Vise is also very popular in the gun repair trade. It gives both vertical and horizontal holding positions and also rotates in a full 360° circle in either position. The vise automatically locks in the desired position when the jaws are clamped tight. Serrated pipe jaws for round objects up to 1½″ diameter are provided as well as a built in anvil.

Gunsmith's Knives



A set of Xacto knives will find extensive use in the gun repair trade. Every gunsmith should have one.



One of the most common uses for the Xacto knife in the gunsmithing trade is for cutting clean screwdriver slots in recoil pads.

The gunsmith will eventually need several kinds of knives in his shop—especially if he is involved with much wood work. I personally like a set of Xacto knives as they fulfill over 90% of my cutting needs; that is, cutting rifle slings, cutting holes in recoil pads (to get to the screw slots) and many other applications.

Sight-Base File

A sight-base file comes in mighty handy for widening dove-tail slots in gun barrels without the danger of deepening the slot or damaging any edges not being worked on. This type of file is always a true parallel 3-square file with only one side doing the cutting. The other two sides are smooth or safe. Being a true parallel file you have absolute control over the angle of the dovetail. Every gunsmith—either hobbyist or professional —should have one of these files in his tool kit.

Pillar File



Both edges of the pillar file are safe so cuts may be made right up to the faces without undercutting the sides of the work.

The pillar file is considered the standard gunsmithing file since they are parallel as to width, but taper somewhat in thickness toward the point. Both edges are safe so cuts may be made right up to the faces without undercutting the sides of the work. These files are made in narrow and extra-narrow patterns and are usually double-cut. Pillar files are especially useful when fitting new parts to firearms.

Scribe Hook



A scribe hook is especially useful for installing or removing small parts of any kind.



A scribe hook is also handy for engraving "trim lines" on parts that are too long. A good example is this shotgun sight bead that's protruding into the bore.

Anyone anticipating assembling and disassembling firearms will quickly learn the value of a scribe hook. It's especially useful whenever small inside springs are to be installed or removed or for slipping out or locating small parts of any kind.

The scribe portion of the instrument is used for marking metal such as a shotgun bead sight shank, that protrudes into the bore. In this case, the sight bead is removed after having been marked, and then cut off (preferably with an emery cutting wheel used in conjunction with a Moto-Tool). The sight bead is then reinstalled and polished flush with the bore with a felt polishing tip.

Brushes



Toothbrushes are excellent cleaning devices for getting down into hard-to-get-at-places.



The stainless steel brush shown is excellent for both cleaning hardened grease from parts and for carding off rust during hot-water bluing.

Besides conventional bore cleaning brushes as described in Chapter 6, the gunsmith will want to obtain a selection of toothbrushes for getting down into actions and for cleaning other hard-to-get-at-places. The bristles should be rather stiff and should be solvent-proof. Brownell's Inc. carries an M-16 cleaning brush that has been tested in practically every oil and solvent available on the market with no damage to the bristles. They cost less than a dollar and are an exceptionally good, practical cleaning brush for use on your bench or in the field.

A stainless steel brush is of special value for cleaning hardened grease and dirt from parts and actions. I also find much use for mine when bluing firearms by the hot-water method. The .005″ hand-tied stainless steel wire varieties are excellent for carding off the rust in hard-to-get-to-areas.

You'll also want one of the old-time scrub brushes—the kind with the wooden handle and hemp bristles. You'll find it useful for scrubbing down barrels and actions. I also keep one of these brushes handy for the sole purpose of cleaning tanks prior to bluing.

An old fashioned horsehair brush is still the best bench brush you can use to sweep away fine dust and particles—keeping the gunshop bench top clean and free from grit and grime that can scratch the finish on firearms. The brush part should be about 8″ long with about a 5″ handle. It should also be fully set with about 2″ of black horsehair bristles.

Wood Rasp



This 4-in-1 hand rasp is a good first tool for working on gunstocks, pistol grips and the like.

The 4-in-l hand rasp is a good first tool for working on gun stocks, pistol grips, etc. This versatile tool is made in a half-round style with parallel sides and no taper in thickness. The flat side of the file has one-half of its surface cut with rasp teeth, and the other half cut with file teeth. The rounded side has half of the surface cut with a rasp section and the other half cut with file teeth. This little tool will handle many of the woodworking jobs around the shop.

India and Arkansas Stones



A hard Arkansas stone is being used to hone a trigger sear to provide a smooth trigger pull. A set of these stones is a must.

Arkansas stones are often used to sharpen wood carving chisels and other similar cutting tools found on the gunsmith's bench.

India and Arkansas stones are needed in the gun shop for precision trigger and sear work, accurizing, close fitting and for other parts where fine stoning is needed. Arkansas stones are also used extensively for sharpening gunsmithing tools such as knives, chisels, gravers and other precision cutting tools. Each grade of Arkansas stone has a special sharpening application as recommended below.

Washita: Most rapid cutting stone. Used to start edges on knives, and by wood carvers, commercial knife sharpeners, butchers and sportsmen who desire a keen edge in minimum of time. It will sharpen a knife to the point where you can shave hair from your arm.

Soft Arkansas: Best general purpose stone. Produces and maintains very sharp, polished edges on all knives and tools. Smoother, even sharper edge than from Washita.

Hard Arkansas: Touches up and final-polishes an already sharp edge. Sharpening with this superb stone takes a little while longer, but the truly polished, razor sharp edge is well worth the effort.

Black Hard Arkansas: Supreme ultimate in a finishing whetstone; used on already sharp blades by the perfectionist. Final step in sharpening high quality cutlery or straight razors.

The sizes and grades listed are those stones I personally prefer to use, plus the ones most often seen on the benches of gunsmiths, knifemakers and woodcarvers. Each stone is hand cut with a diamond saw, then carefully finished and graded. To protect the precision ground cutting surfaces, each stone usually comes in a nicely finished and varnished cedarwood box.

Allen Wrenches

The gunsmith will need a complete set of Allen head bits in both English and metric sizes. One good set is offered by Chapman which fits their screwdriver set handle and extension. This assortment contains 11 Allen head bits from $^1/_{16}$″ to $^5/_{16}$″ and 6 metric Allen head bits along with 14″ square drive adapter.

Most telescopic sights—especially as sold by the discount houses, etc. —use Allen head screws, primarily for the scope mounts. I remember one scope repair that should have been relatively simple. However, I didn't have a metric Allen tip and wound up grinding down an inch Allen tip (the next size larger than the metric size) until I had a fit. Therefore, a ten minute job took nearly two hours!

You will probably see more and more metric Allen tips in use in the firearms industry, so be sure you have a set of both types of Allen wrenches. They are inexpensive and you'll find many daily uses for them around your shop. Set screws for handloading equipment are also of the Allen type.

Miscellaneous Tools



Brownell's Basic Gunsmithing Kit consists of a good selection of tools ideal for the hobbyist or professional. At the top is a brass/nylon headed hammer; to the left is a pair of needle nose pliers with a pair of parallel pliers just below. Underneath the hammer is a Magna Tip screwdriver and bits. Below the screwdriver set and to the right and left can be found such items as jeweler's screwdrivers, pin punches, Allen wrench set, bench knife, screw-chart, scribe hook, starter punches, drift, honing stones, M-16 brush, spring vise, a file and a 4-in-1 hand rasp.

The tools previously described are the bare minimum with which you can perform gun repairs. You'll also quickly find that this set is incomplete and more tools will be needed as you progress in the field. This is especially true when you start disassembling firearms. Certain firearms will require specialized tools, for without them, assembly and disassembly steps can be difficult. One example is removing the retaining caps on Winchester Model 12's and similar shotguns. A retaining cap wrench will greatly simplify the removal. The extra wide tips of this wrench fit the slots in the cap exactly; it's available from Brownell's Inc.

If you're a professional (or intend to be one) a big part of your business will be working on Colt handguns. A special Colt tool is made for removing the ejector from the cylinder prior to bluing, polishing or servicing—it's darn handy. This tool also makes it easier to remove or install tight .38 or .45 auto bushings.

Bolt extractor pliers will also be appreciated when you begin fighting the removal and installation of a stiff extractor on an Enfield, Springfield, Mauser or similar bolt.

A lot of other service tools for special models of firearms can be found in the gunsmith's service manuals provided by firearm manufacturers. In fact, these catalogs should be one of your first "tools." They have helpful troubleshooting information, assembly and disassembly instructions (plus schematic drawings) and much, much more helpful data. You'll also want *The Encyclopedia of Modern Firearms Parts & Assembly* compiled by Bob Brownell because, according to the Dec. 1959 issue of *The American Rifleman*:

> "The publication of this outstanding work is an event of great importance for the gunsmith, the firearm hobbyist, and serious gun workers in the small arms field . . . something that every gun enthusiast and firearms hobbyist will want, and that every gunsmith will find to be an indispensable tool of his trade."

I concur. There is hardly a day that goes by that I don't need to use this reference for some reason—assembling a firearm, looking in the diagrams to see what parts are missing from a firearm in for repairs, troubleshooting data, and much much more. It's paid for itself in my shop time and time again.

While we're on the subject of books, I'd suggest you take a long, hard look at Chapter 23, *Gunsmith's Library*. In that chapter you'll find a thorough list of superb titles devoted to the subject of gunsmithing. Many, if not most of those books, should be near your workbench for fast reference. I find mine indispensable.



When removing the pump handle retaining cap on a Winchester Model 12, use the special tool shown—Brownells can provide one.



Brownell's Assembly/Disassembly Tool Kit will make gun repair a lot easier, as you'll have a good basic set of assembly/disassembly tools to start off with. At the top is a nylon/brass headed hammer; just below the hammer is a Magna-Tip screwdriver and bits. To the left of the hammer is a set of parallel pliers, below those a spring vise and a Colt pistol wrench. Tools to the right of the spring vise and Colt wrench include: M-16 brush, pin punches, stones, screw chart, drift, bench knife, files, jeweler's screwdrivers, bolt spring extractor pliers, Model 12 wrench and a speed-head wrench. Tools like these help conserve the gunsmith's most valuable resource — time.



This Colt tool is very helpful in removing the ejector from the cylinder prior to bluing, polishing or servicing.



Bolt extractor pliers will be appreciated when removing and installing extractors on an Enfield, Springfield, Mauser or similar bolt action rifles.

2 – A PLACE TO WORK

WITHOUT a doubt, everyone who tinkers with guns needs a shop. The professional, of course, needs the shop for his livelihood and while the hobbyist may save a little money on his own gun repairs, the home shop is noted more for the pleasure it offers.

There are at least ten good locations for a gun shop. There are countless ways to create space where there seems to be none. But in planning a location for a gunshop, you must first decide what type of work you will be performing. For example, if you plan to get your Federal Firearms License and work on guns for others, one room or area in the home must be set aside exclusively for the gun business. If it's in the basement, the room can't also be used for a recreation room nor can Mommy do her ironing in this area. The space must be devoted entirely to gun business.

On the other hand, if you plan to work on firearms only for yourself, you can locate the "shop" any place you like—even in your living room!

Shops for gun work involve troubleshooting, stock finishing, rebluing, stock checkering, cleaning, rebarreling, chambering (just to name a few), and, again, the person must decide just what types and how much of this work he plans to do. One gunsmith may specialize in metal work — doing rebarreling and rechambering jobs mostly. Then his shop will be centered around a lathe and perhaps a milling/drilling machine. Another may specialize in stock work, requiring mostly woodworking tools. Another may want to do only rebluing, and so on. However, the average gunsmith will perform a variety of work on firearms covering the entire field. He may have to farm out some of his lathe work (because he can't afford a lathe at this time) but he's expected to be able to handle most jobs that come along.

Basement Shops

Most home gunshops are located in the basement. This location has several advantages over other locations and the few drawbacks can be usually overcome. The chief advantages include:

1. Easy to heat in winter.
2. Cool in summer.
3. It's out of the way of most family activities.
4. It's quiet and it can be made relatively soundproof from the living area.
5. If you have to, you can leave it messed up overnight without worrying about guests seeing it.



Fluorescent fixtures are normally the best light source for gunshops. Get the best you can afford—it will save your eyes.

The basement area also has several disadvantages, but as mentioned previously, most can be overcome. Most basement areas (as finished by the builder) are poorly illuminated. This gives a dark, dingy appearance. So, if the basement is the area chosen for the shop location, one of the first projects should be the installation of adequate lighting. Fluorescent fixtures are ideal. However, if an acoustical T-bar ceiling is used, you may want to go with recessed fixtures—either incandescent or fluorescent.

One of the major disadvantages of a basement is dampness which of course, creates rust problems. To overcome this problem, epoxy waterproofing may be applied to basement walls from the inside and then foam boards can be used to insulate basement walls and check dampness. A good dehumidifier is added insurance.

Flooding is another problem with some basements that can be a disaster. However, if the home owner will grade all slopes away from basement walls, repair all gutters and downspouts, and install a good sump pump, the chance of basement flooding is greatly reduced.

Another major problem with basement areas (especially those in older homes) is the low ceiling height. Many basement ceilings are only about 6' 10″ above the floor. This not only gives a cramped-in feeling but also causes trouble with guns, tools and other items accidentally hitting the ceiling as you're working on them. Cove lighting around the perimeter of low ceilings will give the affect of a higher ceiling; it's also a very good indirect lighting method for general illumination. Lowering the basement floor or raising the ceiling are expensive operations and are not (usually) economically feasible in this day and time. It would be better to utilize another area in the home or else build a new shop in your backyard.

One gunsmith near Berryville, VA opened a professional gunshop in the basement of his home. A separate outside entrance and show windows were installed and the interior was completely finished. A partition separates the showroom from the shop area where all phases of gun work are performed. The show room walls are lined with a gun rack which is always full of new and used guns which are for sale. Other shooting items such as reloading manuals, reloading components and other firearm accessories are also on display. The shop contains a bench lathe, drill press, barrel vise and hundreds of other useful gunsmithing tools. A firing range was built in back of the shop for testing weapons by the gunsmiths and also the customers.

This shop has several advantages. One is that of low overhead; that is, a separate place of business does not have to be leased or built and otherwise maintained. Secondly, someone is usually at home at all times which discourages intruders. Having a place of business in one's home is also convenient. For example, if business is slow, the owner can mow his grass or perhaps paint the wood trim or any number of other activities normally performed at home while waiting for customers to come. The chief disadvantage of such a setup is being bothered by customers after closing hours. A gun owner, for example, may decide that he must have a particular firearm looked at in the evening—after regular business hours. If the gunshop were located away from one's residence, chances are the customer would not bother to call at the gunsmith's home. However, with the shop in one's home, it's very tempting for the gun owner to merely go to the front door and knock, even though the gunshop may be closed. This is good for business, but hell on one's privacy.

If you're building or buying a house in which a basement workshop is planned, here are a few things to look for:

1. The basement walls should be built of concrete blocks at least 12 blocks high. Many are built only 11 blocks high and this produces a ceiling about 7' high which is too low for a good gunshop.
2. Be sure the basement is waterproofed correctly. In general, the exterior block walls should have a coating of cement plaster as well as a heavy coating of asphalt waterproofing compound over this. The first two or three courses of block should be of the solid type and a line of drain tile placed in a bed of loose gravel should be installed around the basement footings to lead off excess water.

In remodeling a basement for a workshop area, try to rework all plumbing pipes and electrical cables so that they are run between joists instead of below them. Some warm air ducts may also be run between joists, but some will be too large for this type of installation. Those which are too large to be run between joists should be run at the perimeter of the basement and then boxed in to give more head room.

Attic Shops

Attics are probably the worst places to put a gun shop around the home. They are often hot in summer, cold in winter and short on head room. Add to this the difficulty of transporting materials to and from the attic, plus the noise and vibration that carries down into the living area and the disadvantages are quickly realized.

Of course, if there is no other place available, these disadvantages can be somewhat remedied. First of all, insulation in the walls, roof and floor will help to keep a more controlled, comfortable temperature and muffle noises. An attic ventilating fan will reduce attic temperatures considerably as will the installation of several windows if they're currently absent.

Noise and vibration produced by power tools can be overcome by mounting them on rubber mats and/or rubber washers. Tightly sealed attic doors will also help retain the shop noises in the attic and also cut down on dust escaping into the living area.

Garage Shops

A gunshop in a garage is one of the best places to locate it. Although garages are often drafty and hard to heat in winter, they can be made into excellent shops having advantages that other areas in the home cannot offer. First of all, a garage shop lets you work into the wee hours of the morning, usually without disturbing anyone in the home. If it's located far enough away from the house and other neighbors, even power tools can be operated without bothering anyone. You don't have to worry about fumes from hot bluing and other operations smelling up the home, and if you are faced with leaving a temporary mess, no one is going to care.

Even if you still plan to use the garage to park your cars, there are ways to also use it as a shop. The nearby floor plan, for example, shows a two-car garage with a large workbench worked into a nook on the side of the garage. A hinged, folddown bench may also be used, but this of course requires that the bench be cleared before it can be folded out of the way.

The ideal set-up is to use one-half of a two-car garage as a shop and the other half for parking a car. If you still want shelter for a second car, build a carport—it's much cheaper than building an enclosed shop.

Even if you don't have a garage on your property, and you're an apartment dweller with no other possibilities for locating a shop where you live, look around town for the possibility of renting a garage. Then set up your shop in this rented structure and work away in your spare time.



This floor plan of a two-car garage has a large workbench installed in a nook on the side of the garage.

Outbuildings

My own home has no basement, no garage and my attic space was converted into an office some years ago. Therefore, my only possibility—or so I thought—was to build a shop in my backyard. First of all, I got hold of some plans for a two-car garage (with storage space above) that matched our Dutch Colonial home, but when I received the bid from a local contractor, I knew this garage would have to wait—$21,000 is a lot of money to spend for a garage!


An old outbuilding in back of author's house was going to be torn down until he decided to convert it into a gunshop. This is a good example of utilizing available space.


Once the grape arbor was removed, and the brush cleared away, the outbuilding started to show promise as a gunshop.

The next possibility were two outbuildings that I had considered too far gone to save. One had been used at one time as a smoke house and the other for a meat house. In fact, they still had the smell of Virginia hams when I moved to this farm. But when I received the bid of over twenty thousand dollars for a garage shell, I decided to take another look at these buildings.


The first chore was to jack up and level the building.


Then, the interior of the building was stripped of all the junk and the entire building was hosed down with water.

The author's next chore was to start framing the old outbuilding and install the electrical wiring.



Inexpensive paneling and a plywood floor was installed; and, a U-shaped workbench was put in along with fluorescent lighting, cabinets, tools, etc.

Although not complete when this picture was taken, it didn't take long for the area to become filled up with gun repairs.

My first step was to tear the old grape arbor down and jack up the building to level it. All the junk that was in the building when I moved on the property was then removed and the building interior then thoroughly washed down with a garden hose. I then decided upon a layout (after several tries on my drawing board) and started the electrical wiring and the insulation of the sidewalls. Inexpensive panelling was then erected, while ⅜″ plywood was laid on the floor to level it and to better accept the tile flooring.

A U-shaped workbench was then constructed as is described in Chapter 3, fluorescent lighting installed, cabinets, tools, etc. No, I'm not quite finished with the shop at this writing. I'm beginning to paint the exterior and build tool racks above the benches, but I'm really in no big hurry since I'm able to use the shop now. It will just be more convenient when all the drawers and shelves are completed.

The other building was half torn down before I decided to leave it for awhile. This building houses my hot-bluing operation. The cracks in the boards provide excellent ventilation!

Porches

Does your home have a porch that is seldom used? If so, you can probably convert it to a very good shop with comparatively little expense. In most cases, the roof, floor and at least one wall is already there so all you have to do is fill in the other two or three walls, add a workbench and you're ready to start working.

Since the walls that are added will usually be exposed to the weather, be sure to insulate well. The floors and ceiling should be considered also. If you can't get to existing void spaces to install insulation, consider having insulation blown in — after boring holes to reach the void spaces between studs.

Conventional framing can be used to enclose the open walls of a porch, but perhaps jalousie windows would provide a better arrangement. A jalousie window consists of a series of operable overlapping glass louvers which pivot in unison —usually by a crank-and-gear system. Such windows are best used in southern climates, where maximum ventilation and flush exterior and interior appearance is desired. These windows may be arranged so that an entire wall—from, say, a foot below the ceiling to two feet above the floor — is constructed of windows.

Spare-Room Shop

A possibility for apartment dwellers is a spare room—like an extra bedroom that hasn't been used since Junior decided to tie the knot. Such a place, however, is not without drawbacks. Apartment rooms are difficult to soundproof, which will definitely limit your activities to certain hours each day. Can you imagine what your neighbors would say if you started your 1 hp buffer/grinder at 2 AM? If you weren't evicted, you'd certainly get the cold shoulder from all your neighbors the following day.

You will also have the problem of tracking debris into the living area of your home, but probably not any worse than tracking dust in a basement shop. Just provide a rug at the room entrance to clean your feet well when you leave. A tight-fitting door will help eliminate dust and chemical odors from the room and also cut down on the noises to the rest of the apartment.

The main advantages of a spare-room shop are lighting and electrical outlets are already provided. Such rooms are also heated and air conditioned for greater comfort than if you selected your garage or outbuilding for the shop location.

Closet Shops

Highly productive gun-tinkering shops have been hung on the back of a closet door, with a workbench that folds down from a neat-looking wall panel, but this is not the ideal situation— although it is a beginning. You won't be able to do too many repairs requiring power tools, but with a little Moto-tool or ¼-inch electric drill with attachments, you could make trigger repairs and adjustments, install sights, do touch-up bluing and a host of other minor gun repairs.

One person I know, built a sawhorse-type bench with an elevated section at one end, on which he secured a bench vise. A small piece of plywood with a 2 x 4 screwed into its bottom about center provided a work surface. The 2 x 4 was gripped in the vise to hold the plywood securely while using it as a work table. The person's weight on the sawhorse provided extra rigidity while working. A checkering cradle could also be secured in the vise, and gun stocks could be checkered while sitting on the sawhorse. Tools were stored on the back of the closet door, and the sawhorse with its attachments was stored in the closet when not in use.

In mild climates a carport may be used for a work area. Tools can be kept in a storage wall or closet at one end of the carport and can be pulled out and used on the platform. Many homeowners use this set-up for storing table saws and lathes, so why not use the same set-up for gun repair work.

Trailer-Shops

If you can't find space in your garage or basement for a suitable work shop, and you don't want to lay out a pile of cash to construct a new outbuilding on your property. —especially if you're renting—consider a small travel trailer. Sometime ago, I was able to purchase a used travel trailer for less than $1000. It was about 25 feet long and 8 feet wide. The existing LP gas range provided all the heat I needed for the hot water bluing operation, and the bedroom area made an excellent bench location. Of course the ingenious built-in drawers, cabinets, etc., provided me with all the storage space needed for tools and materials. The gas-fired furnace heated the area snugly, and it really was an ideal set-up.

If you choose to go this route, I'd suggest substituting the small 20-pound gas tanks that come with most Rv's with larger LP gas tanks if you don't plan to move it often. It doesn't take long to use up the gas in the small tanks and nothing is quite as discouraging as finding yourself out of fuel right in the middle of a bluing operation.

3 – A WORKBENCH FOR EVERYONE

WHEN THE hobbyist gunsmith begins to think of graduating from the tool-box/repair-kit stage to a full-fledged workshop, his first thoughts undoubtedly turn to a suitable workbench. Unfortunately, there are not very many commercial workbenches to choose from—and those that are available will make your pocketbook look like a sieve.

The next alternative is to build one, but again, workbench plans designed expressly for gun repair work are few and far between; or else the benches are so complicated that it would take a complete woodworking shop to put them together.

The workbench ideas given in this chapter are of simple—yet functional—design and most can be built with conventional hand tools in a relatively short period of time. The reader should find one design that will come close to filling his immediate needs—and at a price he can afford.

Basic Bench Requirements

In general, a workbench should be 30″ wide and from 5' to 12' long. Don't skimp on the length, however, because you'll soon find that there is really no such thing as too much bench space—it will become cluttered in a very short time.

The height of the workbench will vary depending on your height. My own workbench is 33½″ high and suits me fine. However, you may want yours anywhere from 30″ to 35″. Above all, the bench must be sturdy and firm. You can not do your best work if the bench moves every time you take a file stroke, or tap a drift pin out of its hole. Therefore, the workbench should be amply reinforced and legs and top should be made of heavy timber.

In addition to the main workbench, it is nice to have an auxiliary bench for special projects. A description of one such bench follows and will come close to fulfilling all of the requirements for an auxiliary workbench. In small shops, this bench will also suffice as a main bench, and although the legs are constructed of 2 x 4's, the plywood bracing makes it very sturdy.

The exploded drawing seen on the next page shows that the frame is made of 2 x 4's, solidly interlocked and secured with glue and ¼″ x 3″ FH wood screws. The top consists of two layers of ¾″ plywood with one layer of ⅛″ hardboard nailed to the top layer of plywood with finishing nails; the shelf also consists of ¾″ plywood (only one layer). For maximum rigidity, ⅜″ plywood is nailed to the backs and sides. With this arrangement, and with the legs anchored to the floor, the table will not budge under almost any treatment you may want to subject it to.

WORKING PLANS FOR A WORKBENCH


60"
24"
¾" plywood glued to bottom layer
⅛" hardboard nailed to next layer with finishing nails
¾" plywood nailed to framework with 6d nails leaving 2" overhang in front and 1" overhang in back
48"
21⅜"
28"
32"
21⅜"
8"
2" X 4" cut to length


TO SECURE LEGS TO FLOOR
Wood screws
Steel "L" bracket
Floor line


Top
Shelf
Top

Here is the layout of the ¾″ plywood pieces for the basic workbench.

To begin, lay out the diagram for the top pieces and shelf on a piece of 4' x 8' x ¾″ plywood. Use a straightedge and square for the lines, and then cut out the various pieces with a hand saw.

Next cut all 2 x 4's, notching the legs as shown in the exploded drawing. Mark and drill screw holes as indicated and then assemble the two end frames with glue and wood screws. You may want to countersink the screw holes for a neat appearance. Join the two end frames with the four long 2 x 4's, again using glue and wood screws.

Insert the lower shelf as indicated after notching all four corners to fit the bench legs. Nail and glue them in place. At this point, the work should be taking the form of a work bench.

Continue by marking the cutting diagram on the ⅜″ plywood for the sides and back—again using a straightedge and square. When they are cut out, nail and glue these panels to the sides and back as shown.

Now nail and glue the lower ¾″ top panel to the top rails of the frame, followed by the next panel and the sheet of ⅛″ hardboard (nailed only). Keep all of these panels under pressure (using C-clamps) until glue dries.

You could probably get away without nailing the top plywood panel and hardboard (using only glue), but when nailed only, the ⅛″ hardboard top may be removed in case it became stained, scratched or damaged.

Tool rack



Once you've completed your workbench you might want to make the simple tool rack shown here. It can be made of simple 2 x 4's or even 2 x 6's and drilled to accommodate those tools you use most often.

A simple tool rack, such as the one shown in the diagram may be added to the top of the bench (at the rear side) for a useful addition. This rack may be constructed of either 2 x 4's or 2 x 6's and drilled any way you like to accommodate screwdrivers, drift punches, wood chisels and similar tools.

If you prefer shelves over your bench, a shelving unit may be hung on a wall directly in back of the bench or mounted to the bench top. The top, sides, and shelves may be made from ¾″ plywood or 1″ shelving boards of a width to suit your needs. A pegboard area is also handy for tool hanging. The overall size of the unit, spacing of shelves, etc. can be varied to suit your needs.

At one time I had a bench vise fitted at the left front corner of the bench and the entire setup served me well for all types of gun repair over a period of several months. However, when I setup my new shop and constructed a new U-shaped built-in workbench, the bench just described was put in my bluing room where it is used mainly for hot water bluing operations.



Shelving is often a handy addition to any bench. The shelving shown can be made of ¾″ ply or 1″ shelving boards of sufficient width to suit your own needs.



Other handy storage sources are prefabricated wall cabinets that are usually a snap to assemble and darned easy on the pocketbook.


"B"
9'-2"
2'-6"
"B"
5'-2"
13'-11"
U-SHAPED
WORKBENCH
(PLAN VIEW)
"A"
"A"
2'-0"
2'-0"
WALL
2'-0"
2"x4"
7½"
2"x4" LEADERS
4"x4" WOOD POST
2"x4"
6"
SIDE VIEW SECTION A-A
2'-6"
2"x4"
SIDE VIEW SECTION B-B
4"x4"
3/4" PLYWOOD
2"x4"
6"

SHELVING UNIT PLAN FOR U-SHAPED WORKBENCH



Wall-Mounted Workbench

My current shop area is approximately 9' x 13' in size and due to the small area, I had to make every inch of space useful. To do so, I designed and constructed a U-shaped workbench to accommodate my reloading equipment, power tools and for general gun repair operations. The design can be modified to fit practically any size area as may be required.

The basic dimensions of the U-shaped workbench are shown in the illustration. Note in the plan and elevated view that the counter top consists of two different widths: 30″ wide for the main section of the bench (under the window) and 24″ wide for the side wings. Note also that this bench is wall-mounted which required less labor, materials, and time to complete as compared to a freestanding workbench.

Once the pieces are cut to the dimensions shown, nail a 2″ x 6″ board securely fastened to the wall studs. Also secure a 2″ x 4″ board in the same manner, along with the length of the bench, for attaching the bottom shelf to. These ledgers support one side of the workbench very securely and also saves using 4″ x 4″ legs in the back of the bench. Framing consists of 2″ x 4″ boards, while the bench legs are made from 4″ x 4″ timber. All joints are secured with ¼″ x 4″ lag screws.

When the basic framing has been completed, the top is constructed from two sheets of ¾″ plywood, glued together, and secured to the bench framing and ledger with finishing nails and counter-sunk lag screws. The ¼″ masonite top is then secured on top of the plywood with finishing nails. This hardboard is really not necessary, but it facilities clean-up since it is smooth, hard and relatively impervious to oils and solvents. Should the top become stained or damaged, merely replace it with another relatively inexpensive piece of hardboard; thus, saving the wooden bench top and protecting it from damage.

Drawers and plywood doors may be added, if desired, for neat storage of tools and supplies. You will also want shelving for storing and arranging tools, parts, and components. Your own ingenuity and available space will determine the best arrangement. A typical over-bench shelving set-up utilizing l″ x 8″ boards with space for pegboard is illustrated, or use the design previously described for the free-standing workbench.

My shop utilizes both shelves and wall cabinets. The cabinets were obtained at a very reasonable cost from one of the mail-order houses, and although unassembled, they were quite easy to put together. After assembling the cabinets, all that is left to complete them is to either paint or varnish the exterior surfaces. In fact, you can make an entire workbench utilizing these prefabricated components that are designed to be used as kitchen cabinets. Look through the pages of Sears and Montgomery Ward catalogs for a complete description and prices. Then decide if you would rather take this route than building a bench.

Apartment Workbench

Apartment dwellers in cities are usually handicapped by not having sufficient space in which to do gun repairs. However, it is possible to have a complete workshop in a handsome cabinet that looks like a respectable piece of furniture. John W. Sill, editor and publisher for Outdoor Life/Popular Science Books designed and built such a cabinet when he was cramped for space in his New York apartment. The details of construction are shown in the illustration. While this mini workshop was designed primarily for small woodworking projects, it may easily be adapted for gun repair work.

The hinged top opens to display an ample assortment of gunsmithing hand tools which are held securely in place by hold clips fastened to the bottom of the ¾″ plywood top. The narrow panel on the front of the cabinet hinges outward and up to provide access to the 24″ x 27¾″ workbench top which is supported by rollers fitted into slots as shown in the drawing. Stops cut from l″ x 2″ wood blocks keep the workbench top from coming all the way out from the cabinet while 2″ x 2″ screw-in legs are used to support the work surface.

A raised platform on the bottom shelf of the cabinet can be used to house power tools such as an electric drill motor and Moto-Tool. Note also that an electric cord runs through a hole cut through the bottom to a power outlet. A 24″ x 18″ drawer may be used for other heavy tools while the inner sides of the cabinet doors hold bits, blades, sandpaper and other gunsmithing supplies.

John Sill also designed a frame that is supported by a pole and cross arm that holds plastic sheeting over the workbench for controlling saw dust when sanding. Holes cut at the proper position in the plastic provide access for hand and electric cord for power sander. You will want to reinforce these holes with heavy masking tape. You may also want to cut a hole for a vacuum cleaner hose and then allow the vacuum cleaner to run during the sanding operation; this will cut down on the dust even more.

PLANS FOR AN APARTMENT WORKBENCH


1/2" PLYWOOD PARTITION 34 1/2" x 31"
BENCH TOP SUPPORTS 18" x 1 1/2" W/ ROLLERS FITTED INTO 1" x 1 1/2" SLOTS
2 1/4" BEVELED MOULDING
TOP OF 3/4" PLYW'D TO HOLD CLIPS FOR TOOLS
30" PIANO HINGE
2 1/4"
34 1/2" x 11" 1/2" PLYW'D SHELVES ON 1/4-ROUND SUPPORTS
LOCK ARM
34" x 5 1/2" x 29" BIN FOR SCRAP LUMBER
HOOKS FOR HAND SAWS
DOOR HINGED OUTWARD
24" x 18" DRAWER W/ HARDB'D BOTTOM FOR HEAVY TOOLS
STOPS CUT FROM 1" x 2" SCREW THROUGH CENTER
36 1/2"
3"
1"
8 1/2"
24 3/4"
36"
ELECTRIC CORD ONE END THROUGH BOTTOM TO OUTLET
2 1/2"
CUT FEET FROM 1" x 3" MITER CORNERS
2 1/2"
1" x 6" FOR DRAWER SLIDE
RAISED PLATFORM FOR POWER TOOLS
2" x 2" SCREW-IN LEGS
WORKBENCH TOP 3/4" PLYW'D 24" x 27 3/4"



Here's a good look at an apartment workbench made from the plans. As you can see, once the unit is finished you’ve got a very practical, and handsome, work-spot. Note the hinged top and the assortment of tools.

PLANS FOR A "SHOP IN A BOX"



Most gunsmiths have a sturdy tool box—it not only keeps the tools organized, it keeps them protected. The plans shown may be modified to suit your own needs; however, the plans (if followed) provide a box similar to the old Stoeger tool kit the author favors.

A gunsmith's tool or utility kit is necessary for repairs and adjustments of firearms in the field or at the range. Some years ago Stoeger Arms Corporation offered a gunsmith's utility kit, all items of which were carefully packed in a specially designed and constructed hardboard kit box, which measured approximately 16″ x 9″ x 6″. The box had two decks—each one partitioned—and was built with two locks, brass corners and a luggage handle. The contents of the chest represented an answer to the many requests for an assortment of tools and equipment necessary to maintain and make all minor repairs and alterations of firearms. The kit was prepared primarily for use by the gunsmith on the range, or for repairs in the field, but it also contained sufficient materials to satisfy the home requirements of the amateur gunsmith and repairman. An idea of the completeness of the tools and accessories are seen from the following list:

Stock polisher
Stoegerol
Barrel grease
No. 1 patches
No. 4 patches
London Oil finish
Noshine
Tutchup Bluer
No. 1 barrel restorer
No. 2 barrel restorer
X-ring paste
Stock wax
Rustoff
Steel wool
Emery cloth
Carbide lamp
Carving tool set
Swiss needle files
Hand vice
Magnet
Jeweler's loupe
Sportsman's stone
Set of jeweler's screwdrivers
6″ screwdriver
8″ screwdriver
10″ screwdriver
Knife file
Wood rasp
Scale rule
Calipers
1 curved needle nose pliers No. 888
1 heavy-duty slip joint combination
1 short chain nose mechanics pliers
6 punches
Scriber
Christy knife
1 India stone round

1 India stone square
1 hard Arkansas stone (round)
1 hard Arkansas stone (diamond)
1 hard Arkansas stone (square)
1 hard Arkansas stone (triangular)
1 tweezers
1 .22 pistol rod
1 .38 pistol rod
1 rifle and shotgun rod
1 hammer
1 bull dog end cutting nippers

A similar kit may be made up by anyone using current cleaning materials, cold bluing solution, and the tools as described in the list. I would also add one other tool—the popular Dremel Moto-Tool with several accessories. If electric power is not available in the field or on the range, you can still use the tool if you have an automobile close by. An apparatus that runs AC/DC (universal) equipment from DC outputs of cars, trucks and other vehicles equipped with alternators is available at a very reasonable price. Besides operating many power tools such as saws, drills, Unimat 3 lathes, it will also operate appliances such as refrigerators, hot plates and lights.

One model offered by Montgomery Ward and called the Auto/Pod provides 3,750 watts of power at 120 volts DC. To operate this device, connect it to the car's electrical system as per instructions supplied with the kit. Start the engine and plug in the power tool. The tool will receive 120-volt DC - power directly from the car's alternator.

A kit to contain your tools may be obtained from several places. You may wish to build your own using the plans above. You can also check the mail-order catalogs for their line of tool boxes. Some tool box/kits are designed on the order of an attache case for a real neat appearance. Several compartments are provided to contain practically any tool you may wish to carry.

4 – PORTABLE ELECTRIC DRILLS



Portable electric drills are suitable for many gunsmithing jobs; it's one of the handiest tools you can purchase.

IF YOU should ask what power tool is considered the most versatile and the most useful in any gunshop, the answer from most experts would probably be the electric hand grinder such as the Moto-Tool manufactured by Dremel. However, if you should ask these same gunsmiths what would be the one power tool they would keep if they had to get rid of all others, the answer would have to be the portable electric drill motor—with the many available accessories.

Once the gunshop is equipped with several other power tools such as a good drill press, a disc sander, bench grinder and a Moto-Tool, the portable electric drill will probably take a back seat and be used infrequently. But until this time occurs, the portable drill should be the hobbyist's first power equipment without reservation.

Portable electric drills vary in size and horsepower rating, but the most common sizes are those that take shanks up to ¼″ or ⅜″ diameters. The tool is equipped with a trigger switch and most have a locking pin that holds the trigger ON until disengaged. Some even have a speed control and can be reversed. Chucks are of the *geared type* that require a special key for opening and closing.

One problem in using a portable drill with a metal housing is the danger of electric shock, especially when working around damp areas like a basement floor. This is where the third grounding prong on the plug cap comes in handy. If properly connected, by means of a third grounding wire in the cord, to the frame of the drill, a ground fault in the metal housing will cause the circuit breaker, fuse or other means of over-current protection in the main electric panel to trip or blow, or otherwise open the circuit. Many portable drills are now equipped with heavy-duty plastic housings to prevent the user from coming into contact with electric shock. In most cases, these drills do not have a third grounding wire in the cords or caps.

A good choice for the gunshop would be a drill motor that will accept ⅜″ diameter shanks and has a variable speed from 0 to 1200 rpm or faster. Such a drill motor will cost you a bit. Less expensive ones can be obtained but you're going to get what you pay for.

In this instance, a shotgun barrel has been clamped in a padded vise and is ready for polishing with the portable drill and polishing head.

Polishing Shotgun Bores

One of the most frequently encountered problems with a shotgun barrel is the scratched or pitted bore. Removing these defects must be done with care lest the choke be damaged.

To correctly polish a shotgun bore, the barrel(s) is (are) first removed from the receiver and inserted in a vise with padded jaws to enable the polishing head to be inserted from the breech end of the barrel. If the shotgun happens to be one of the rare non-takedown types, the polishing can be done from the muzzle end as explained later.

A shotgun barrel polishing head is available from Frank Mittermeier, Inc.. This head comes attached to a 34″ long steel rod, which is chucked in an electric hand drill. The head consists of slots to fasten four polishing strips centrally. When the head is revolved at a rapid speed, centrifugal force forces the strips of polishing cloth to the walls of the bore. Only the ends of the strips touch the bore; this allows air to freely circulate inside of the bore which in turn prevents overheating the barrel.

Coarse polishing strips should be used for scratch removal while fine strips or crocus cloth should be used for polishing. The strips are easily changed by unscrewing the slotted bolt, removing the old strips, and then inserting new ones before tightening the bolt.

To polish, chuck the polishing head and steel rod in a portable drill motor; then insert the polishing head in the breech end of the barrel, and start the motor. The polishing head (with polishing strips attached) is slowly pushed forward and back through the bore.



Shotgun barrel polishing heads usually hold several strips (4, in this case) of polishing cloth. The head comes attached to a 34″ steel rod and the entire unit is available from Frank Mittermeier.

When it is necessary to insert the polishing head in the muzzle of the barrel, carefully push the head all the way down the barrel to the chamber area before starting the motor. Also finish up in this area and pull the head out with the drill motor OFF.

If the polishing head described herein is not available, fair results can be obtained with a conventional cleaning rod chucked in a drill motor with crocus strips inserted through the eye in the cleaning tip. Many shotgun barrels have also been polished by wrapping steel wool around a cleaning brush (attached to a cleaning rod) and then revolving the assembly through the bore with a drill motor.

Installing Rifle Slings



For best results, sling swivels should be located approximately 27″ apart, the rear stud (A) about 3″ from the toe of the stock.



When it comes to accurately installing sling swivels, the B-Square swivel installation kit is superb. Not only does the kit assure accuracy, it speeds up the entire swivel-installation process.

Sling studs are normally placed at varying distances apart, usually between 26″ and 28″, with the rear stud located about 3″ from the toe of the stock.

If no studs have been previously fitted to the stock, two holes will have to be drilled to accept the studs and swivels. In general, the rear stud screws directly into the wood, while the front studs require a special retaining nut which presses firmly into the wood of the forearm so as not to protrude against the barrel. Therefore, the front hole must be drilled completely through the stock; both holes must be countersunk.

An excellent swivel installation tool kit is available from B-Square Co. This kit enables sling swivels to be installed quickly on any stock without risk of damage. The “V” jig has a hardened drill guide bushing and will automatically locate the $^5/_{32}$″ diameter drill (furnished with the kit) the correct distance from the fore-end or from the toe. Furthermore, it will guide the drill on the exact center of the stock edge or in the exact center of the barrel channel.

To install the rear swivel turn the rifle upside down and clamp it in a suitable padded vise—a Decker gun vise works nicely for this job. Place the swivel jig over the edge of the stock so that its end is flush with the butt; this puts the pilot drill about 2½″ from the butt. Insert the $^5/_{32}$″ pilot drill in an electric hand drill and align the swivel jig to drill a hole approximately 1″ deep.

Exchange the $^5/_{32}$″ pilot drill for the $^7/_{32}$″ diameter safety counter-bore and counter-bore the $^5/_{32}$″ hole just drilled. This last operation provides for the unthreaded portion of the swivel screw.

Before inserting the swivel screw into the gun stock, it should be dipped in linseed oil to seal the wood and bind the fibers. Then, using a swift punch or a common nail as a wrench, screw the swivel screw into the gun stock until its cross hole is correctly positioned when tight down against the stock. Never use the swivel itself as a wrench.

To install the front swivel screw on most one-piece rifle stocks, remove the barreled action from the stock and clamp the stock in a padded vise so that the barrel channel is *up*. Place the swivel jig in the barrel channel with the “V” down. Its end should be flush with the fore-end tip so that the drill will be approximately 2½″ back from the tip. The jig is designed to center the $^5/_{32}$″ pilot drill in the barrel channel, so use this drill in the drill motor and hole completely through the gun stock. Then enlarge this hole with the No. 10 safety drill which will counter-bore for the swivel nut all in one operation. Again, coat the counter-bored hole with linseed oil and press the swivel screw nut into the counter-bore. A small amount of Loc-Tite should be placed on the screw threads before tightening the swivel screw into the nut. Use a drift punch or a nail to tighten. Be sure that the front swivel installation is permanent; an improper installation can greatly affect accuracy not to mention the damage that could be caused to the gun should it be dropped.

(Above) One of the author’s favorite “tools” for many gunsmithing chores is the Decker Vise. As shown, it’s perfect for bore cleaning or scope mounting. By inverting the rifle and clamping it in place, the Decker Vise is perfect for sling swivel installation.



When using the B-Square jig for swivel installation, simply place the jig over the edge of the stock so that it's flush with the butt.



When installing the front swivel, place the B-Square jig directly in the barrel channel with the “V” downward.

Installing Recoil Pads



Adding a recoil pad is a job most gunsmiths will be called to do. A Dem-Bart layout guide is perfect for accurately scribing the portion of the butt to be removed prior to pad installation.

A disc sander attachment is available for portable electric drills and will find much use around any gunshop that does not have a combination belt and disc sander. One use of the disc sander is for working down new recoil pads to fit the stock.

In most cases, some of the stock will have to be cut off prior to installing the pad. If the stock “feel” is right with a conventional hard rubber butt plate and you want to add a thicker recoil pad, first measure the thickness of the two pads, subtract the difference, and this will be the amount to cut off. One word of caution. A stock that feels long may not be as long as it feels. Therefore, cut off only about ⅛ to ¼-inch at a time until the gun feels right and shoulders properly.

Once the amount to be cut off has been determined, mark the distance with some type of scriber and depth gauge. I find that a layout guide is ideal for this marking. Although designed for insuring that checkering patterns come out properly positioned and truly parallel to the top line of the fore-end, when the arm is laid across the butt of the stock and the scriber adjusted to score a line around the butt, a true parallel is assured for use as a guide for sawing.

Before sawing, however, apply masking tape around the butt of the stock, even with the scribed line. This will prevent the wood from splintering and will also act to protect the stock finish when the recoil pad is worked down.

You may secure the stock in a padded vise and make the cut with either a hack saw or a regular hand saw, but a deep miter box is better and cleaner cuts can be obtained if you use a hack saw. Regardless of the type of saw you use, it should be fine-toothed with at least ten teeth per inch to minimize splintering.



When removing a section of buttstock for recoil pad installation, be sure to mask off the area of the stock immediately adjoining the cut-line.



The masking tape will help prevent splintering or marring during the actual cutting of the stock and the final shaping of the pad.

After sawing off the end of the stock, true-up the surface with a rasp, but be careful not to cause splinters, shorten the stock or bevel the edges. Make sure the pad selected is large enough to permit the bottom plane of the stock to continue through the toe of the pad. You may also want to apply Prussian blue or some other marking material to the inside surface of the pad before the preliminary mounting of the pad. When removed, the color transfer and lack of color on the wood indicates high spots which should be corrected for a perfect pad/butt contact. In other words, those spots on the stock butt that show color should be trimmed down.

To mount the pad, scribe a line down the exact center of the stock butt, from heel to toe. Then center the pad in position on the butt and mark the top screw hole with an ice pick or similar sharp object. Drill a starter hole 1″ deep with a ⅛″ bit on the centerline and as near to the mark made by the ice pick as possible. Depending upon the size of screw, widen the hole enough so that the threads of the recoil pad screw will make firm contact with the wood; make this second cut about ½″ deep, then insert the top screw, position the pad and tighten it down.

Now mark the bottom screw hole in the same manner as the top hole, before loosening the top screw and swinging the butt plate aside so that the bottom hole may be drilled. Tighten down both screws and with a sharp scribe, trace the outline of the stock on the inside of the recoil pad. This line is for the disc sanding that follows.

Secure the electric drill in a vise or drill bench stand so that the sanding disc, chucked into the drill, is readily accessible. Then remove the recoil pad from the butt of the stock and remove all but about ⅛″ of the recoil-pad material on the outside of the scribed line. Be absolutely *certain* that you leave enough material on the toe so that the plane of the stock may be continued when you finish up the fitting. Leave this part of the shaping until later.

The rough-shaped pad is then remounted on the stock and tightened down. Make sure that sufficient masking tape is still on the stock to help prevent scratching or marring the stock or finish. You may even want to apply another layer of glass tape over the masking tape for further protection. Install a fine sanding disc on the drill, and finish trimming the recoil pad until it is exactly even with the stock. For the last few thousandths of an inch, you might want to switch over to a fine-toothed file to insure accuracy; or perhaps to garnet paper wrapped around a file.

USING B-SQUARE’S RECOIL PAD JIG



When using a B-Square recoil pad installation jig, the procedure is as follows: (1) Carefully centering the pad on the butt of the gun, scribe a line on the pad that follows the outside dimensions of the butt. Next (2), place the butt pad upside down on the jig; and (3) set the toe and heel angles with a square prior to final disc sanding.

The B-Square Co. of Fort Worth, Texas, offers a recoil pad jig that makes installing a recoil pad easier and with less risk to wood damage. To use, just scribe the exact outline of the stock butt on the pad back and place it upside down on the pad jig. Set the toe and heel angles with a square and completely finish it by sanding with a disc sander as described previously. You can do a perfect job every time with absolutely no risk to a gun stock. All shaping and finishing is done completely off the stock.

The pad jig comes with complete illustrated instructions. These instructions are easy to follow and are detailed step-by-step. They will show you how to fit the gun to the shooter, how to cut off the stock, how to shape the pad, and many other useful details.

If you don’t have a disc sander, you can purchase the appropriate accessories for your portable drill. By securing the drill with sanding attachments in a vise, you'll have a sturdy sanding unit perfectly suited for finishing off any recoil pad installation job.

Jewelling



One of the most common jobs a gunsmith will get requests for is bolt-body jewelling. The bolt jig shown holds the bolt securely and insures the job will be accurately and attractively done. (Jigs such as this one can be obtained from any of the major gunsmith-tool houses.)

When the electric hand drill is set up in an inexpensive drill press—available from most tool supply houses, hardware stores, etc. —the little drill becomes an altogether handier tool. One of the operations consists of jewelling bolts for rifles and shotguns.

Jewelling is a form of decorating the metal surface in a series of fine concentric circles on a polished surface. Its purpose is decorative, but it provides a wear indicator and a possibility of “holding oil” for protection. It’s a relatively simple operation and adds class to fine guns. The process is done with many different devices such as rubber abrasive rods (pencil erasers will work fine), dowels with abrasive paper glued to the end, or a fine wire brush “charged” with oil or abrasive compound.

When jewelling bolts, it is recommended that a specially designed fixture be used to hold the bolt to be decorated. The fixture containing the bolt is placed on a drill press table so that the bolt body is centered under the jewelling tool which is held in the drill chuck. The bolt is coated with abrasive compound; then the pattern may be started at either end of the bolt, but each row of concentric circles must start from the same end. The drill motor should run at medium speed as it is brought down onto the bolt. Then the fixture is moved approximately one-half diameter of the circle and again the brush is brought down to overlap spots on the surface of the bolt. This continues for one row, then the bolt is rotated approximately one-half circle diameter and the process repeated. This continues until the bolt has been fully jeweled in the areas desired.

Scope Mounting



Drilling and tapping a Winchester Model 94 receiver for a side mount can be quite a chore unless you happen to have the B-Square jig shown. It cuts the time down and insures accurate drilling/tapping.

The electric hand drill is also a valuable tool for mounting scope sights on rifles—especially when used in combination with a drill press and the scope jigs offered by B-Square. One such B-Square jig is made for the Winchester Model 94. This jig accurately locates the holes for Weaver side mount bases on the Winchester Model 94 lever action rifle. It is precision made and has four hardened No. 28 drill jig bushings correctly spaced to match the Weaver base and provides for its shoulder. It automatically locates (without measuring) the mounting holes to provide clearance with holes already in the gun. A clamp bolt, nut and special washer are provided to hold the jig to the gun while drilling.

When drilling holes for scope bases, use a new standard high speed drill bit for each job as this will save time. The shorter screw machine drill bits are best since the longer ones tend to wander. Use cutting oil sparingly. The holes should be of the proper depth to allow the holes to be tapped-, but not so deep as to protrude into the bore, chamber or other undesirable area.

Use a new tap for each job as this is cheap insurance against a broken off tap in the drilled hole. Three or four flute hand taps should be used as these are stronger than the 2-flute types. The 2-flute taps will also cut oversize if not guided. U se a special tapping oil such as Tap Magic supplied by Brownell’s Inc. Tap Magic prevents any weldment of any type metal to the cutting tool. It permits the tool to cut freely and produces a finer chip with a minimum of galling and friction. The extremely high rate of evaporation of Tap Magic also makes it act as a refrigerant, thus keeping the tool cool, sharp and cutting.

Some guns may have to have their hardened receivers annealed before you’re able to drill them. Polish the spot(s) to be drilled—usually an area the size of a dime—and proceed to heat the polished spot with the tip of a needle point acetylene torch. Heat the spot until the metal turns dark blue. Remove the torch and, with a piece of 400 wet or dry sandpaper, polish the blue spot (while hot) with a few quick strokes till the blue is removed. Repeat the process. About the third time around, and after you’ve given the blue spot a few quick strokes with the 400 wet or dry, you’ll notice that after you knock the blue off, the polished spot will suddenly turn blue again. This lets you know the annealing job has been completed and the receiver’s ready for drilling.

Once the receiver is drilled and tapped, provisions must be made so that the scope tube can be clamped without bending, binding, twisting, collapsing, etc. Any deflection will change the point of impact and any change in temperature will change the stress and deflect the scope. Therefore, it is important that the scope be mounted without any stress or strain. Since high magnification scopes require the most corrective adjustment in mounting, only the Redfield and the Leupold type bases and rings will be considered. To install scopes in these type mounts:

1. Install base without bending. Tighten with perfect fitting screwdriver. Any chemical screw retention liquid is considered a “crutch” and if it is a good screw (and threads are correctly tightened) it will stay tight. Most important, it can be removed without damage.
2. Install rear ring with slight “play” so it will be partially self-aligning.
3. Lubricate front ring “key” and install in its base “key hole.”
4. Rotate and/or oscillate ring in its base by using a lever until it is just free enough to turn by hand only.
5. Remove the top halves of the rings. Place the scope in the saddles by adjusting the front saddle until the scope is free to enter and “touch bottom” completely.
6. Replace caps, lightly tighten screws and align cross hairs.
7. Tighten all cap screws even and tight with a screwdriver that fits.
8. Bore sight and line up scope using base windage adjustment screw. Finally adjust both windage and elevation using scope’s internal adjustments.

It is important to use only a minimum of the scope’s internal adjustment to prevent stress and strain. If the scope is strained by excessive internal adjusting, re-machine or re-adjust the base to attempt to zero the scope using its mount only.

When using Weaver type rings and bases, no adjustment is possible other than shimming, and this method is not recommended for professional work. However, if this is the only way, use a pair of small tin snips to cut and shape the needed shims—use thin brass shim material. Be sure to cut a piece wide enough to offer good support, yet not show from under the scope or mount. Place under scope in rings and tighten down.



Often times, you’ll find yourself in a position where you’ll need some shim stock for jobs such as scope mounting. A small pair of tin snips are ideal for cutting up brass sheeting when shim stock is needed.

5 – THE THIRD HAND

THE BENCH VISE should be one of the first tools considered by anyone who anticipates working on firearms. Without a good vise even the better mechanics are near helpless when it comes to some types of gun repairs.

A vise is a clamping device, usually consisting of two jaws which close and open on a threaded shaft which is turned by a lever. Most attach to a bench and are used for holding a piece of work firmly. There are a great variety of vises used by gunsmiths and a description of each follows.

Vises

Pin Vises



A set of pin vises are useful for holding rods and pin stock for filing.

A screw head polishing vise is used to hold gun screws and pins while polishing on a buffing wheel.

A set of pin vises is useful for holding rods and pin stock for filing. They are also useful for holding scriber points, small files, taps, drills and the like. A hole extends through the set manufactured by Starrett so that wires or a rod of any length may be held. The handle is reduced in size so that it may be rapidly rotated between the thumb and finger when filing small work. The jaws are hardened and close fitting, and with a few turns of the binding nut a firm grip may be obtained with them. The handle and binding nut on the set shown are nickel plated. The entire set will handle work from 0 to .187″.

A similar vise, the *screw head polishing vice*, is used to hold gun screws and pins while polishing the screw heads to get them ready for bluing. Obviously, this tool saves burned fingers not to mention those screws that snap out of the fingers while they’re being polished and become lost in the shop. This particular vise will handle screws up to ¼″ in diameter. To “load,” merely loosen the chuck, insert the screw (thread end first) and the screw head is exposed for polishing. This vise may also be used for holding screws while they are being blued by the heat/oil-dip method as described in Chapter 9 on bluing equipment.

Combination Vise



A combination vise is ideal for home workshops as well as gunshops.



Eventually the gunsmith will need a heavy machinist's vise for the type of work he'll be called upon to do.

The combination vise is ideal for home workshops and will also find use around professional shops that are not too demanding. This vise is furnished with replaceable steel serrated jaws, an anvil surface, auxiliary jaws for clamping round stock, an anvil horn for forming and bending and a swivel base with locking clamp and handle.

Eventually the gunsmith will need a heavy *machinist's* vise. These almost indestructible vises have been a favorite of the serious gunsmith for longer than most of us can remember. If you select a machinist's vise that is strong and heavy enough, it will also double as a barrel vise if a few accessories are added. Clamp two hardwood blocks in the vise and drill a hole at the joint of the smallest diameter of a tapered barrel. Then contour the hole to the barrel shape (you may need several such blocks). Powdered rosin is then sprinkled onto the barrel to prevent it from slipping and the barrel is clamped between the two blocks which are held by the vise jaws.



For barrel removal, B-Square's impact wrench is ideal when used in conjunction with a sturdy barrel vise.

Once you have the barrel tightly clamped in the vise, you'll need some type of wrench to grasp the action securely without damaging the finish on the action. The B-Square action wrench is designed especially for this job. This wrench consists of a heavy steel bar made to fit both flat-bottomed and rounded receivers. For flat-bottomed actions, the flat part of the wrench bears against the flat bottom of the action; if the action is rounded, the clamp ring fits into the bottom grooves.

Some barrels are nigh onto impossible to remove, but the application of some penetrating oil will help tremendously. Once the wrench is secured to the action, tests have shown that a single impact blow with a 5-lb. hammer against the wrench will often loosen a barrel when brute force will not.



Special wrenches designed for PVC pipe can also be used on some gun actions for barrel removal providing the barrel has not rusted to the action.

Another wrench that will work on some barreled actions is the type that's designed for working on PVC (plastic) pipe without marring the pipe. If a piece of 2-in. pipe, about 5' long, is wedged over the short pipe handle, the leverage provided will remove a number of pistol and rifle barrels. However, if the barrel has rusted to the receiver, as is often the case with old military rifles, chances are you're going to break the web "jaws" before loosening the barrel. Due to the price, however, this little wrench is worth a try— especially for the hobbyist. It's available from Brookstone Tool Company and costs about one quarter of a standard barrel wrench.

Versa-Vise

I've seen this vise advertised in the American Rifleman way back when I was still hunting with my Daisy Red Ryder BB gun. It is easily the most universal vise ever built for the hobbyist or a second vise for the professional gunsmith. The Versa-Vise gives both vertical and horizontal holding positions and rotates in a full circle in either position. The vise automatically locks in any position when the jaws are clamped tight for holding the workpiece at the most favorable position when filing, grinding, polishing, soldering, etc. Such vises, however, are not designed for rough treatment and should be used only as a second vise for gun repair work.

Vise Accessories

To prevent marring of blued metal surfaces as well as wood finishes the bench vise should be equipped with removable copper, brass, lead, leather or wood vise jaws.

Leather Vise Jaw Pads



Leather vise jaw pads are indispensable when working on gun parts that are subject to marring.

Leather vise jaw pads have been the standby to use when working with gun parts or other items that are subject to marring. The pads may be glued to the vise jaws or may be backed with masonite providing removable pads that rest on the vise frame slide. Of course, they may be used as separate pads as shown in the photo.

Lead Vise Jaw Faces

Lead sheets are easily shaped to fit your precision machinist vise or heavy shop vise jaws. They prevent rough vise jaws from marring delicate or polished parts while holding them firmly in place. They also help to hold parts so they will not slip at a lower vise-jaw pressure.

Bronze Vise Jaws



Bronze vise pads are generally shaped from 60-to 40-degrees of angle and make excellent working jaws for all types of bench vises.

Bronze jaws are best shaped at 60-to 40-degree angles to make perfect working jaw faces for your heavy bench vise, drill press vise or precision machinist vise. They may be readily formed to fit any vise top contour and they prevent marring of parts being held. Such jaws also act as a heat sink (draws off heat) when holding parts to be heated. They are available from Brownell's in three lengths—3″, 4″ and 12″.

Slide-on Rubber Jaws



Slide-on rubber jaws, as found on this Dremel 0-Vise, are used to protect easily marred items.

Jaws that are made of materials such as nylon or rubber must either be removed or protected with wood blocks before applying heat to any part being held in the vise.

The Dremel vise can be set up with slide-on rubber jaws that protect easily marred items you may be working on. Similar protection is offered by the nylon jaws on the swivel vise. Either pair of these jaws must be removed or protected with wood blocks before applying heat to any part being held in these vises.

Wood Jaws



As can be seen here, it's pretty easy to make a set of vise-jaw pads from ¼″ plywood.

Jaws made from ¼″ plywood will come in handy around the gunshop for holding specific items without marring the finish. You can make a set from scrap lumber. Such jaws give a little firmer grip than leather and offer about the same degree of protection.

Octagon Barrel Holding Vise Jaws



B-Square octagon barrel holding jaws are made to fit any conventional bench vise. They are particularly handy for the gunsmith who does a fair amount of black powder gun work.

Aluminum holding jaws can be made to fit any conventional bench vise, and should be specially machined with a "V"-shaped groove that matches the angle of octagon barrels. Two self-adjusting pins keep the holding jaws in alignment in the vise. Such jaws are highly recommended for safe, strong, non-slip holding of any octagon barrel that needs to be locked-up securely in the vise to be worked on.

Super-Hold Vise Jaw Pads

Brownell's recently offered a set of superhold vise jaws that are made of new space-age elastomerics that grip the work piece and hold it securely without any slipping, marring or straining. They don't even require excessive clamping pressure to insure a non-slip grip. The pad material was developed for missile launch tube liners, so it is obviously tough and does not readily impregnate. They'll give years of useful service.

Each pad measures 3″ x 4″ and is permanently bonded to ¼″ aluminum plate that measures 5″ x 4″ wide. They may be custom fitted to your vise by notching the bottom of the plate for the adjusting bar on the vise. Two types are available: Red— for wood, plastic, and other soft materials. Green —for metals and other hard materials.

Drill and Bench Vise

A drill vise is a very versatile tool with unlimited uses. It may be secured to a rotary compound table or clamped into a conventional bench vise for holding work firmly at any angle for cutting, drilling or filing. The jaws of this vise have one cross groove and one perpendicular groove for holding round work, yet these grooves do not effect flat work.

The drill vise is an absolute must for positioning and rigidly holding work that must be drilled with wobble-free precision and accuracy. The jaws on the vise pictured are $2^{7}/_{16}$″ wide and have a maximum opening of 2½″. It will tilt up to 90 degrees.

Rotary Compound Table

The rotary compound table provides compound slides as well as rotary feed in one compact unit. Cross-feed screws are ½″ Acme thread, and provide transverse and longitudinal travel of 4¼″. Cross-feed dials are 1″ diameter, graduated in thousandths. The rotary feed dial is 1¾″ diameter, and is calibrated in 3 minute intervals. Such a table makes possible the finest of precision drilling as the three adjustments will center the drill exactly. For scope and sight work it is unequalled, and when used in combination with the drill and bench vise described above, provides an even more versatile arrangement. Detailed indexing operations may be found in Chapter 16, Milling Machines.



This drill and bench vise is a very versatile tool with unlimited uses around the gunshop.

In this instance, a bolt has been secured in a padded vise and is ready for any number of gunsmithing chores (trigger-pull improvement in this case).

Practical Applications

The following are a few of the practical uses of vises—of different types—in the gunshop. While the list is not nearly complete, those listed should stir the imagination enough to bring to light many other uses that may be applied daily to gun work. Remember that nearly all work in the gunshop requires the work to be held in a certain position, and the vise—or its kin—is necessary for most of them.

Bore Sighting

Bore sighting is essential for quickly adjusting a telescopic sight. By doing so, you'll be putting the first test shot "on paper." Here's another use for the bench vise.

Obtain some leather vise jaw pads to prevent marring the firearm when it is tightly clamped in the jaws of the vise. A bore sighting kit like the Bushnell Bore Sighter is ideal for the gunsmith who must bore sight a variety of different rifle calibers. This kit comes with three expandable arbors which provide exceptional flexibility where several different calibers are involved. With these arbors the user can bore sight the full range from .22 to .45 caliber. The smallest arbor fits any bore from .22 to .270 caliber; the middle-sized arbor fits any bore from 7mm to .35 caliber, and the largest fits bores from .35 to .45 caliber.



Bushnell Bore Sighter makes quick work out of sighting in scopes.



When bore sighting any rifle, be sure it's firmly tied down. The rifle being bore-sighted here has been secured in a padded vise.

To bore sight a rifle, place the gun in a padded vise and select the proper arbor from the kit. Make sure the expandable tips are completely closed by turning the arbor's locking nut counter-clockwise as far as it will go. Insert the small end of the arbor into the bore sighter mount with the locating spot down, so the end of the clamp screw will bear against the flat surface. Turn the screw clockwise until it is finger-tight to hold the arbor and bore sighter in position.

Now, with the bore sighter in an upright position, gently insert the arbor into the barrel and push it forward carefully (so as not to damage the lands) until the muzzle rests against the tapered section of the arbor. With the arbor locking nut loosened and while looking through the scope, swing the bore sighter to align the vertical grid lines with the scope reticle. When aligned perfectly, turn the arbor locking nut clockwise until the arbor holds firmly to the bore; the expandable tips prevent the bore sighter from turning of its own weight.

Remove the caps over the adjustment mechanism on the riflescope and sight through the scope. Move the elevation and windage adjustments until the reticle aligns with the crosshairs of the graduated grid reticle in the bore sighter. For best results, the bore sighter should be held close to a well-lighted area such as a window or an adjustable lamp. You are now ready for sighting-in on the range.

To remove the arbor from the barrel, simply loosen the arbor locking nut and push inward to retract the tips; pull the unit from the barrel.

For rifles or handguns with iron sights, secure the bore sighter into the bore as described before. Then, viewing through the rear sight, adjust the sights to align with the crosshairs on the graduated grid reticle in the bore sighter. When you have completed the bore sighting as described previously, the iron-sighted firearm is ready for sighting-in on the range.

Using the scope or iron sight adjustments, you can make correction for bullet drop at a specific distance provided the trajectory of the specific load is known. Each graduation on the bore sighter grid is equivalent to 4 inches at 100 yards. But watch what you're doing as this is as confusing as looking through a twin-lens reflex camera— everything is opposite from what it seems. For example, when the scope reticle is above the grid center, the firearm will shoot low. When below the grid center, the gun will shoot high!

How many times have you started to drill and tap a receiver for a riflescope and couldn't find a flat place on the gun to level it before drilling? One solution to this problem is to use only the bore sighter's arbor—inserted into the bore—and you've got a ready-made flat surface to place your small machinist's level on that will be exactly in line with the bore.



When using the Bushnell Bore Sighter, insert the small end of the arbor into the bore sighter mount with the locating spot down, so the end of the clamp screw will bear against the flat surface.



With the bore sighter in an upright position, carefully insert the arbor into the barrel and push it forward gently until the muzzle rests against the tapered section of the arbor.

For best results when using any optical bore-sighting device, an adjustable lamp should be used to illuminate the bore-sighter grid.



A Bushnell bore sight arbor is perfect for leveling a rifle prior to drilling and tapping holes for mounting a scope.

Smoothing Up Trigger Pulls

In most cases, trigger pull may be smoothed to the point where it feels lighter by simply honing all bearing surfaces to reduce friction. These surfaces include the cocking piece sears and trigger sears. When these surfaces are honed smooth, the apparent trigger pull weight will usually be reduced. Begin by mounting the trigger sear in a vise with jaws that are protected with leather pads. Polish surfaces with a hard, rectangular Arkansas stone held at a right angle to the sear surface. Be *extremely* careful not to change the angle of the original sear (unless it is incorrect when you start) or to bevel or round the edges. Usually, a *few light strokes* is all that is necessary.

You'll want to check your work frequently with a magnifying glass to make certain you're not rounding the corners or removing too much metal. Any rounded edges that may be present should be trued up or flattened with a soft, faster cutting Arkansas stone first, and then polished with a hard stone.

A cocking piece may also be secured in a vise and polished. Work at a right angle to the notch— using a hard Arkansas stone. Be sure to follow the exact contour of the notch and move the stone in as straight a line as possible. Again, don't round the edges or remove too much metal.

Soldering on New Sights



This gunsmithing tool is called a “3-V” clamp and is used to hold a sight base in place during silver soldering. Brownells or Mittermeiers can supply you with this one.

When soldering on a new front sight ramp— using the techniques described in Chapter 11, Soldering and Welding—both the barrel and the sight base must be securely held in place during the operation. One of the best ways to hold the parts to be soldered is to use wooden blocks in the vise jaws to hold the barrel securely, and then use a 3-V clamp to hold the ramp in place for soldering as shown. Note that the front clamp foot rests on the flat surface on the top of the ramp while the rear clamp foot rests on the barrel.

When mounting a new front sight ramp, it is absolutely necessary that the ramp be aligned correctly and centered on the barrel. Use a square and level to true up the barrel/action assembly as the barrel must first be straight in the vise before you can line up the sight. Once the barrel and action are straight and level, the ramp is aligned and then secured by soldering as described in Chapter 11.

Fitting the Shotgun Stock

Proper stock “pull” is one requirement that is vitally important to the shotgun owner’s shooting proficiency, yet few shooters understand what it is, or why a stock may either fit right when it is purchased or have to be lengthened or shortened to fit him personally. To find the correct pull for a shooter, he must be measured—the Brownell Pull & Drop Gauge is the tool to use. This gauge is designed to accurately, easily and quickly measure the pull and drop of the gunstock and the pull of the shooter’s forearm-trigger-finger.

To measure the shotgun stock, mount the gun in a vise with padded jaws and then place the Pull and Drop gauge in proper position as indicated by the directions that come with this handy tool. The zero mark at the inside of the ring bored in the gauge should be aligned exactly with the edge of the gun’s trigger (the edge that your finger rests on). Then the length may be read directly by moving the slide snug against the butt plate.

Characteristics of improperly-fitted stocks include shooting to either the right or left of a target. For example, if the stock is too short, chances are you’ll shoot to the right; if too long, you’ll shoot to the left of the target. Recoil will also be felt differently when the stock is improperly fitted.

The drop at the heel of a stock is another important area to consider for fitting shotgun stocks to a particular shooter. Heel drop is the distance between the heel of the butt and a line extending straight back from the sighting plain of the barrel. The Brownell gauge is also used here to measure the drop of heel while the shotgun is firmly secured in a vise with padded jaws.

When the stock has to be lengthened or shortened, the vise is used to hold the stock for cutting or to install a recoil pad as discussed elsewhere in this book. Here is a list of other operations where the vise should be used:

1. Assembling and disassembling guns of all types.
2. Removing stuck cases from rifle chambers.
3. Removing burrs from action feed ramps.
4. Cleaning firearms.
5. Hand fitting new barrels to revolver frames.
6. Securing barreled actions for chambering or freeboring.
7. Holding barrels for chamber cast or lapping.
8. Holding metal guide bar while wrapping spring wire to make magazine spring.
9. Stock work/checkering.
10. Inletting gun stocks.
11. Shaping gun stocks.
12. Repairing gun stocks.
13. For holding guns and parts for nearly all gun repair work.



Brownells Pull and Drop gauge is the sort of tool that will come in handy if you plan on doing any amount of stock work.

6 - RX FOR LONG GUN LIFE

BENCH REST shooters have known for years that a well cleaned bore is imperative in attaining the ultimate in rifle performance. Gunsmiths know that the cause of 90% of malfunctions in autoloading rifles and shotguns is due to dirt and/or corrosion in the action, chamber and/or gas piston. Proper cleaning and care of a firearm is also an important factor in extending its usefulness and preserving its appearance. Other reasons could be cited, but these should suffice to convince every gun owner that his guns should be cleaned periodically—both at home, in the field or on the range.

Cleaning Tools

Outers
SHOTGUN
CLEANING
KIT
Shotgun Cleaning Procedure
PATCHES

A simple commercial gun cleaning kit is suitable for the general gun cleaning chores most gunsmiths will encounter.

Silicone
GUN & REEL CLOTH

A silicone impregnated cloth is excellent when it comes to rust prevention or the removal of finger prints.

Cleaning kits are available on the market for cleaning rifles, shotguns, handguns and black powder weapons. Most contain a cleaning rod, a bronze bristle brush, slotted patch tip, patches, powder solvent, gun oil and gun grease. These kits are fine for cleaning guns in the field or on the range, but the average gun owner will need more equipment for thoroughly cleaning the guns at home.

For general field cleaning with the kit, soak one of the patches with powder solvent (bore cleaner) and place it through the slotted tip on the cleaning rod. Insert the tip into the barrel (preferably from the breech end) and run the patch the full length of the barrel and return. Repeat this operation many times—usually 15 or 20. Then use a dry patch to dry the bore. Keep changing patches until the last one comes out clean. Finish the bore cleaning by lightly oiling a clean patch and running it up and back through the bore.

Stubborn bores will require the use of the bronze bristle brush. Soak a patch as before with bore cleaner and run it up and down the bore until it is saturated with the bore cleaner. Remove the slotted patch tip from the cleaning rod, insert the brush and dip it in the bore cleaner. Push this brush up and down the bore about a dozen times to loosen all dirt and grime. Finish up as before by drying the bore with clean patches until the last patch comes out clean.

The outside of the gun should be wiped off with a Silicone cloth. This cloth prevents rust and corrosion and also removes finger prints and eliminates salt spray damage. This cloth may also be used on wood.

Cleaning Rods



Sectioned aluminum cleaning rods have a tendency to bend and/or break from the pressure needed to force cleaning brushes/patches through most barrels. As a result. I'd suggest you keep a sturdy 1-piece rod near the workbench.

In general, cleaning rods are made of wood (hickory), aluminum, or other metals such as brass or steel. Most are made of sectioned aluminum and are fine for shotgun and pistol rods, but I've broken several over the years when used in rifles. They have a tendency to bend and break at the joints from the pressure needed to force the proper-size cleaning brushes through the barrel.

Cleaning rods for use on rifle and pistol barrels should have swivel handles so that the rods revolve freely, allowing the patch or brush to follow the rifling of the barrel. Without this rotation, the patch will drag at right angles across the lands and will eventually destroy the sharp edges of the rifling. A shotgun cleaning rod does not require a swivel joint since the bore is smooth.

Cleaning Accessories for Rifles and Pistols



SINGLE SLOTTED TIP

FLEXIBLE JAG

PLAIN JAG

ROLL JAG

BRASS BRUSH

Here's a good selection of common cleaning rod tips. From top to bottom: single slotted tip; flexible jag; plain jag; roll jag and a brass bristle brush.

Several types of cleaning tips are commonly used on rifle and pistol cleaning rods. The single slotted tip is the simplest and holds onto a patch under all conditions. The patch used with these tips should be of such a size as to require about 4 pounds of pressure to force it through the bore of the rifle or pistol. Slotted tips do sometimes jam when reversed inside the bore; also, the cleaning action is often one-sided, permitting the bare sides of the tip to rub the bore.

The plain jag tip gives uniform cleaning action and reverses perfectly inside the barrel. The patch sticks to the tip as long as it is inside the barrel, but will come loose should the tip be pushed beyond the muzzle or chamber. A pointed jag tip has the advantage of centering the patch before it is inserted in the bore.

For cleaning rifles and pistols that have to be wiped out from the muzzle end, the roll jag tip is far safer because the patch does not have to be dragged in. Consequently, the rifling is preserved instead of being worn away at a most vital spot.



The Lewis Lead Remover has long been recognized as the best tool for cleaning out badly leaded bores.



To assemble the Lewis rod, pass the rod body through the barrel and screw the cone tip (C) through the brass cloth patch (B) into the rod body (A). You then bend the patch back over the taper of the screw cone tip and you're ready to remove lead from a revolver's forcing cone using the tip shown.



Be sure to firmly hold the revolver when pulling the cone tip and patch of the Lewis Lead Remover into the forcing cone.



When using the Lewis Lead Remover to clean out the cylinders of a revolver, be sure to insert the rod from the forward end of the cylinder.

Other than powder fouling, the shooter must sometimes give consideration to metal fouling. This is a deposit of metal left by the bullet in the bore. If lead bullets are used, the problem is more specifically designated as "leading." Even the best match ammunition will cause leading in the finest target handguns and this leading can affect accuracy to a disastrous degree. However, a perfect cleaning job on handguns can be accomplished in a few minutes with a Lewis Lead Remover distributed by L. E. M. Gun Specialties. This tool will remove lead from the forcing cone, chamber(s) and bore with ease.

In revolvers the forcing cone (or bullet seat) may be cleaned by first swinging the cylinder out of the firing position and then inserting the handle (with the tip and cloth patch removed) through the barrel from the muzzle end. Screw the cone tip with attached cloth patch into the handle hand tight. Hold the revolver with fingers around handle and thumb through the frame, and with the right hand, pull the cone tip and patch snug into the forcing cone. It won't go very far, so don't get excited if you think it's not going in. Holding this pressure, turn the handle in a clockwise direction four or five turns; then push the cone back and examine the brass cloth patch. If the forcing cone is badly leaded, repeat this operation after flipping the lead off the patch with the thumb nail, pocket knife or similar object.

Clean the revolver barrel with the rubber tip unit. First remove all grease and solvent from the barrel. Then insert the handle through the barrel from the muzzle end as before. Screw the rubber tip with formed brass cloth patch into the handle hand tight and examine the knurled nut to see that it is backed one-half turn away from the rubber portion of the tip to allow the assembly to turn with the rifling. Hold the revolver as described before and pull the tip through the barrel, allowing handle and tip assembly to turn with rifling. Repeat this operation until all lead is removed.

Revolver cylinders may be cleaned in a similar way to the barrel; that is, insert the handle from the forward end of the cylinder, screw the rubber tip with formed brass cloth patch into the handle. Hold the cylinder with the left hand and pull the rubber tip with formed patch into the cylinder. When the tip engages the front end (reduced diameter) of the cylinder, begin turning in a clockwise direction.

The brass cloth patch should be good for several cleanings. Should it become clogged with grease and lead, it may be cleaned with lighter fluid and a toothbrush. If any of the above operations tighten either tip too tight to release with the fingers, a key is provided to loosen them.

Cleaning Accessories for Shotguns



These rod tips (for cleaning shotguns) are, from left, a brass bristle brush, single loop tip and the cotton mop or swab — be sure to use the proper gauge of brush loop or mop.



A slotted jag is also perfect for holding abrasive paper when polishing out shotgun bores.



This slotted, flexible brass jag is ideal for cleaning shotguns when used with a patch centered in the slot.



Leather-washer bore polishers are perfect for putting the final touches on any shotgun bore — only the leather washers touch the metal.

The shotgun cleaning swab is useful for oiling the bores or applying powder solvent, but they must be kept clean as otherwise much harm can be done by the fouling on the wool swab neutralizing the preserving powers of the oil. The brass or bronze bristle brush of the proper size for the bore is used to remove as much of the fouling and powder residue as possible by pushing it down and back through the bore 4 or 5 times. The slotted tip is then used to hold patches to remove all the debris that has been loosened. Several patches should be used until the last one comes out clean. Then oil a clean patch and run it through the bore several times.

Metal fouling in shotgun barrels or any condition of rusting or pitting can be removed (usually) by mechanical methods as the smooth bore permits almost any type of polishing. The flexible brass jag, for example, was designed for cleaning shotguns with a patch. The patch is slipped into the slot of the jag and wrapped around it; the slot imparts a measure of flexibility, which causes the patch to press evenly on the bore thereby squeezing the oil into the pores of the steel. The flexible slot also permits the jag to be compressed by the choke thus ensuring a thorough cleaning of the bore throughout its length. This jag is also ideal for holding abrasive paper strips when you have to polish shotgun bores. For faster results, attach the jag to a metal cleaning rod, cut the handle off so that it will fit into the chuck of a drill motor, and polish the bore. Steel brushes and polishing heads designed expressly for the purpose of polishing shotgun bores are available.

The leather shotgun bore polisher shown here is built up of seven buff leather discs that absorb polishing materials such as Clover abrasive compound, and aid in repolishing the bores of shotguns that have been neglected. Since no metal touches the bore, they can be used on the most expensive shotguns without fear of damage.

Holding Guns for Cleaning



Gun cleaning can be made one heck of a lot easier by using the Decker Rifle Vise. It holds the rifle or shotgun firmly in place and you thereby run less risk of damaging anything with a fast-moving cleaning rod.

The Decker vise is also well suited for bore sighting.

Cleaning operations may be greatly simplified if some type of vise is used to hold the guns. One such vise is the Decker Shooting Vise. When used properly, all scratching, marring, etc., are eliminated as the Naugahide covering the sponge padding is all that comes in contact with the gun.

The entire base may be permanently mounted to a table or else temporarily secured with C clamps. This tool will quickly pay for itself if only used in bore cleaning. However, the vise has many other uses. For example, a rifle may be inserted in the vise in an inverted position for loosening and tightening guard screws. A semi-inletted stock may be secured in the vise while fitting a barreled action. This vise is unsurpassed for bore sighting. By removing the two cap nuts that secure the rear section, the vise becomes a completely adequate substitute for a zeroing rest—provided a sandbag is used under the butt stock.

Of course, rifles and shotguns may be clamped in a standard bench vise, but care must be exercised in exerting too much clamping pressure and the jaws of the vise must be well padded.

Professional Gun Cleaning

A good part of the professional gunsmith's business consists of cleaning guns for customers, usually before and after the regular hunting season in the fall. For such cleaning, special equipment and cleaning solutions are needed.

The simplest and quickest setup is to use a clean bluing tank to hold the cleaning solution. The plastic tanks supplied by Birchwood Casey are ideal. You will also need brushes of various types to get to the hard-to-reach places. Tooth brushes, baby bottle brushes and the like should be purchased just for gun cleaning.

A fast, efficient soak cleaner for guns and parts that is non-hazardous, non-flammable, odor-free and not too expensive is called d'SOLVE Gunsmith Cleaner and is available from Brownell's Inc. The grimiest parts left soaking in a bench tray of d'SOLVE while doing other work on a gun come out clean, ready to dry, oil and assemble. Used as a brush-on cleaner, actions and chambers are rapidly rid of crusted dirt and grime. Wiped on, it's an excellent pre-cleaner for touch-up bluing.

Add a can of WD-40, with needle applicator, and you're all set for cleaning. Squirt WD-40 onto the gun and parts and let it soak for a couple of minutes while you're mixing one part d'SOLVE to 5 parts water in the clean bluing tank. Mix enough to thoroughly cover the gun and all parts. Now place all the parts in the solution and let soak for several minutes. The WD-40 will have started loosening the dirt and dissolving the grease, and the d'SOLVE will finish the job. Use the tooth brush to get any stubborn grime off the parts. Of course, all wood should be removed from the gun prior to soaking in the cleaning solution.



The Water Pic®, with its fluid reservoir filled with cleaning solution can be used for cleaning out dirt and debris from any action. (Don't use the family unit for the shop!)



When cleaning guns, put a light coat of WD-40 or other quality gun oil on the metal parts to be cleaned. Allow the oil to soak in for a few minutes. This "soaking" will help loosen grime and make overall cleaning an easier chore.

After the parts have been cleaned thoroughly, dry all the parts and lubricate them with a good gun oil or give the entire gun a light coat of WD-40.

If you want to go a bit further, nothing beats compressed air for blowing gun parts clean. Once the parts are lifted out of the cleaning tank, all the loose grime is quickly blown out with a compressed air gun set at about 50 psi of pressure. The air gun is also a quick way to dry parts.

A friend, Alan Eldridge of Potomac Arms Corp. in Alexandria, Virginia suggests using a Water Pic® for cleaning guns—the same kind that a lot of us use for cleaning our teeth! With this gadget sitting next to the cleaning tank, fill the reservoir with the cleaning solution, turn the spray gauge to high, and go to work on the gun parts and action. The tiny, forceful jets of cleaning fluid will do wonders for cleaning them properly. The only problem that I can see with this method is you must be careful what you run through the Water Pic as some chemicals will obviously ruin the mechanism.



If you’ve got a rust-removal problem, a soft-wire carding wheel mounted on a buffer can remove a pile of rust in a hurry; however, consider this approach to rust removal carefully unless you’re working on small, unseen parts. If you take great care, spot rebluing may not be necessary when removing small amounts of rust from exposed metal parts.

World’s Finest
G 66 BRAND
GUN
SILICONE MITT
Contains GE Silicones, New Rust Inhibitor Formula - Displaces Moisture, Prevents Rust, Fingermarks and Salt Water Corrosion.
CLEANS — Triple treated to absorb and hold dirt, residues, etc.
POLISHES — Produces a deep “Like New” lustre on all metal surfaces and on gun stock.
PROTECTS — Spreads invisible shield over all metal surfaces that repels dirt, prevents fingermarks and displaces moisture.

Fingerprints can leave a chemical deposit on metal that will, in time, provide an unwanted coating of rust. Keep a silicone impregnated rag on hand for wiping down guns after they’ve been handled.

One of the most difficult problems confronting the gunsmith is removing heavy rust without damaging the bluing. The best first attempt is to coat the area with WD-40 and rub vigorously with a rough towel to scrub the rust off. The process is repeated until a clean patch wiped over the surface comes up clean. If a lot of rust is present, use No. 0000 steel wool dampened with WD-40, rubbing lightly until the rust is removed.

If you run into deep heavy rust that the steel wool won’t remove, try using a soft wire carding wheel on your buffer. If care is taken, you can remove quite a lot of rust without harming the blue underneath.

When all else fails, and it seems that no other way but removing both the rust and blue will solve the problem, I take a piece of No. 0 steel wool and dip it in a container of Brownell’s OXPHO-BLUE and rub the rusted area vigorously with the solution-soaked piece of steel wool. The chemical (in most cases) goes through the oil on the gun, removes the rust and blues the steel underneath to replace whatever was removed by the steel wool.

7 - FILES AND THEIR KIN

Files



Files are primarily designed as metal-cutting tools that have a large number of cutting teeth.



Parts of a typical file.

FILES are simply metal cutting tools with a large number of cutting teeth. They have many uses, and consequently, there are hundreds of types of files available. With a full assortment of files in the workshop, an expert gunsmith can make practically any tool necessary from scrap metal as well as parts and other metal work.

The cuts made across the face of a file to form the file teeth are either fine, course or some degree in between. In general, the coarser the file, the more metal it removes with each file stroke, and consequently, the rougher it leaves the filed surface. Naturally, a coarse file is normally used for rough cutting a part and the part then finished with a fine-cut file.

When only one series of parallel cuts has been taken across the face of the file, the file is known as a *single-cut file*. When two series of cuts are used, it is known as a *double-cut file*. In addition to single- and double-cut classifications—and their coarseness—files are classified according to their shape and purpose. For example, they may be *flat, triangular, square, half-round*, etc.

Due to the numerous styles and types of files, it is difficult for the amateur to even begin selecting a set that will handle most of his gun repair work without overbuying. The brief description that follows should be of some help.



BASTARD SECOND CUT SMOOTH

(A) Single cut.



BASTARD SECOND CU SMOOTH

(B) Double cut.

Files have either single- or double-cut file teeth. When only one series of parallel cuts appear on the face of the file, it is known as a single-cut file. When two series of cuts in a cross-hatch pattern appear on the face of the file, it is known as a *double-cut file.*

Pillar file: This type is considered the standard gunsmithing file and many jobs can be done with it which could not even be attempted with standard files. A pillar file is parallel as to width, but tapers somewhat in thickness toward the point. They are "safe" on both edges so that a cut may be made right up to the faces without undercutting the sides of the work. Number 0 is the coarsest and is used for fast removal of wood or untempered soft metal. The Number 2 cut is good for final fitting of fine parts and the like. Number 4 cut is very smooth and is for finishing. They are double-cut and are applicable to general gunsmithing work, especially in connection with fitting new parts.

Round file: Common cuts for round files are 00 to No. 4. The coarser size (00) is used for fast removal of metal or as a rasp to slightly enlarge or adjust accessory holes in wood stocks. Cuts 2 and 4 are for adjusting screw and pin holes, scope mount holes, fine cuts on tightly curved parts and all types of parallel round cuts.

Lathe file: The lathe file is rather heavy with about twice as much slant on the teeth as a standard file. This characteristic produces a sort of shearing cut and is excellent for filing old rough military rifle barrels as they turn in a lathe.



The lathe file is rather heavy with about twice as much slant on the teeth as a normal file.

Hand file: Hand files are parallel in thickness from the heel to the middle, and are tapered, as to thickness, from the middle to the point. This type of file will find many uses around the gunshop for dressing, striking off, shaping, cleaning up and removing all types of metal. This should be one of the first files added to your list of tools after purchasing a No. 2 cut pillar file.

Mill file: Mill files are parallel in thickness from the heel to the point and usually tapered so that the width at the end equals about three-fourths the width of the stock. They are also made of equal width and thickness throughout their length. The teeth are ordinarily single-cut, bastard; however, they can have rows of teeth that cross each other in somewhat of a diamond or cross-hatch pattern. In this case, it's a double-cut bastard mill file. Other cuts include No. 2 cut and smooth. This file is used in the gunshop for lathe work, draw filing and for filing brass and bronze.

Knife file: This type of file, with its narrow knife-blade type section, is ideal for getting down into sharp angles and tight corners where no other file will reach. The teeth are double-cut, and normally come in three sizes—bastard, 2nd cut and smooth.

Barrette file: This is another type of file designed for getting into tight places; that is, coming right up to right angles, working over dovetails, slots, and other tight or critical areas where precision work is a must. Common cuts include No. 0, No. 1, etc.

Needle files: A set of needle files should be in every gunshop as they will find regular use. The set pictured consists of 12 assorted files in four types: equalling, square, three square, and half round. Cuts are medium and fine.



Every gunshop should have a good set of needle files on hand. This particular set has 12 assorted files.

Sight base file: The sight base file is specially designed to safely widen or cut new dovetail slots for sight bases. It's a true parallel, 3-square file with only one side cutting; the other two sides are safe (smooth). This means the file can be used to widen dovetail slots in gun barrels without danger of deepening the slot or damaging the edge not being worked on. Since it is a true parallel file, absolute control is had over the angle of the dovetail—very difficult, if not impossible, with any other type of file.

Screw head file: Gunsmiths are often called upon to make or alter a screw slot, and for this purpose, a screw head file is hard to beat. Such files cut only on the edge because the wide flat sides are safe or smooth. Therefore, the screw head will not be damaged during filing. Three slot sizes are commonly available for perfect width every time: .043″ .035″ and .027″.

Clock maker's file: Did you ever wonder how those tiny screw slots in many European firearms could ever be touched up except with a gnat's hair? Clock maker's files are ideal for that purpose. Brownell's sell a No. 5 (fine) cut clock maker's file with or without tang. These are especially useful for the European-type "V" screw slots.

Metal checkering files: These files are used for checkering hammer spurs, back straps or fore straps on pistol grips or serrating ribs. They are manufactured in sizes from 20-75 lines per inch.



Metal checkering files are used for checkering hammer spurs, pistol grips and a host of other gun parts.



To file, position the work so that it's about level with the elbows for light work, and a bit lower for heavy work. Right-handed persons hold the file with the right hand, thumb on top of the handle, fingers below.

Filing may seem to be an easy operation, but nothing could be farther from the truth. First of all, filing depends on the motion of the hands for the cutting action and without a means of guiding the tool, which is always the case, it is difficult to move over the work with the correct pressure and in the right direction. The only way to obtain proficiency in filing is to practice using proper methods.

To file, the correct position and method of holding the file must be learned. Position the work so that it's about level with the elbows for light work, and just a bit lower for heavy work. The feet should be about eight inches apart and at a comfortable angle to each other. The left foot should be parallel with the file. Right-handed persons should hold the file with the right hand—thumb on top of the handle and the fingers below. When the filing action begins, pressure should be exerted on the forward stroke only as pressure on the return stroke produces no cutting action and tends to dull the teeth which are pointed toward the end of the file.



Working down and smoothing rough surfaces can be accomplished in less time when a special draw file is used. This is the way you should hold the file for best results.



Keeping the file clean is the key to smooth, clean cutting. Use a file card or a stiff steel brush (like the one shown) to remove metal chips from the teeth. Before actually using the file, it's a smart move to rub a piece of chalk over the teeth—this makes the cleaning job a lot easier.

The gunsmith will often be called upon to remove tool marks from rifle barrels and other gun parts. This operation is commonly accomplished by draw filing. To perform this operation, grasp the file by the ends and move the file sideways across the work. This produces a smooth finish and removes tool marks when a second cut or smooth file is used. A single-cut file is better than a double-cut file, as it is less likely to scratch the surface of the work.

The ultimate finish on gun parts such as old rough military barrels is to start with a coarse file and continue using successively finer grades of file, finishing with a smooth or dead-smooth file, according to the degree of finish desired. This procedure is sometimes called "striking" in the trade.

Use padded vise-blocks and secure the barrel, barreled action, or whatever you're working on in the vise. Select a wide, and very fine cut file unless the barrel is very rough, then use a coarse file to start out. Use the file in both hands and run every stroke the full length of the barrel, maintaining a constant firm pressure, so that the file takes a cut both ways. Don't make the cuts too deep, however, just enough pressure to barely make the file take hold is all that is necessary. Neither should the pressure be too light as this will scratch the metal rather than cut it.

When the correct pressure is applied to the work, the cuts will be relatively even, with no flats visible on the surface. However, the flat spots will be there nonetheless and will have to be removed by polishing as discussed in Chapter 9 on bluing. Of course, when the barrel is turning in a lathe and draw filed, much less polishing is necessary.

Particles of metal often remain in the teeth of the file, and they either reduce the cutting qualities or scratch the work. Keep a piece of chalk handy, and chalk the cutting side of the file all over at frequent intervals to prevent the metal build-up. Also use a stiff brush or a file card frequently, for cleaning the file thoroughly. Then re-chalk and continue the operation. Frequent pinning or clogging of the teeth can sometimes be prevented by using oil on the work when filing; that is, on steel, but never on cast iron as grease on the latter material tends to cause the file to slide over the work without cutting into the metal.

Working down and smoothing rough barrels can be accomplished in less time when a special draw file is used. A barrel draw file is available from Frank Mittermeier, Inc., and has the following features:

1. Its usefulness is not limited; it can be used on single and double barrel guns, on straight and taper barrels and close to fixed sight bases, ribs and places otherwise inaccessible.
2. Its concave shape means elimination of nearly all "flats" thus doing away with most cross-polishing.
3. Its 3½″ length allows a firm grip and for those preferring to mount it to a wooden handle, there are two countersunk screw holes.
4. Its circular cut teeth work fast and are spaced at the right intervals to prevent pinning and with its nasty deep scratches.
5. It's the greatest tool for working down and smoothing barrels when a lathe isn't available.

Files Used in Rebarreling Work

In rebarreling either a rifle or handgun, many times the barrel can not be turned snug by hand so that it is within ¼ of a turn of coming to alignment. When this occurs, metal must be removed from either the barrel shoulder or the action shoulder. This operation can be accomplished by careful filing with a safe-edge file. Begin the operation by masking the barrel threads with tape. Then, use some type of marking element—like smoke, chalk or inletting black—to mark the surface of the barrel to be filed. With the barrel held securely in a vise, use short, overlapping file strokes to work completely around the barrel shoulder until all of the marking disappears. Remark the surface and repeat the operation. Then try the barrel on the action or frame. If it does not fit, repeat the filing operation until it does, but be extremely careful not to take too much metal off the barrel shoulder. Furthermore, be *extremely* careful to maintain squareness of the shoulder. In the event that too much metal is removed, use a machinist's hammer with a smoothly polished face to peen the barrel shoulder until the barrel fits snugly.

Another common use for a double-cut smooth bastard file is for squaring and leveling the muzzle surface of an amputated barrel. To shorten a rifle barrel, mount the barreled action in a vise, trueing up the entire assembly with a level. If you can't find a level spot on the barrel or action, use a bore sighter spud without the optic bore sighter and you can then level the bore with a conventional small machinist's level. This will help assure a right-angle barrel cut.

Measure, mark and scribe the cutoff point on the barrel. Then, making sure the cut will be perfectly square, saw off the barrel with a hacksaw, using a standard, good quality, hacksaw blade with about 18 teeth per inch. After sawing, smooth and crown the muzzle end with a metal file. Finish up by removing metal burrs turned inward toward the bore; polish and blue by conventional methods.

Hacksaws



In this case, the author is sawing off a portion of damaged muzzle with a hacksaw. This "tool" is one of those "must-have" items for every gunshop—don't be cheap, buy the best you can afford.

Since hacksaws are cutting tools, a description of their use is in order. The best hacksaw frame is not expensive, so only the best should be purchased. It will be used a great deal around the shop. Likewise, only the best tungsten high-speed hacksaw blades can be expected to hold up for all kinds of gun work. A quality hacksaw frame will help eliminate blade twist or wobble. The blade may be inserted in a conventional manner for cutting stock down to the surface and may also be inserted for cutting flush with the surface.

The choice of teeth per inch on the blades will depend on the type of work the saw is used on. In general, the thinner the material to be cut, the higher the number of teeth. Soft material requires fewer teeth per inch than hard material. (Round, wire-type hacksaw blades are also available for cutting wood, metal, plastics, tile, rubber, linoleum, leather, etc. The roundness of the blades also permits a cut along any line that can be drawn.)



When any muzzle has been cut off, you won't have to do a lot of squaring-up (left) if the barrel was cut cleanly. Smoothing the face of the cut (right) with a file is your next step.



This particular hacksaw frame (above) is called the “Challenger” and is available from Brownells. With this frame design, the user can cut metal stock in a conventional manner (top right) or adjust the blade to cut in a horizontal position (bottom right). (Drawings courtesy of Brownell’s Inc.)

When sawing, the workpiece must be held securely in a vise and positioned so that the cutoff is near the vise jaws to prevent shattering. To start a cut, use the thumb as a guide and saw slowly with short strokes until the cut is well started. As the cut deepens, grip the front end of the frame firmly and take a full-length stroke.



To start a cut with the hacksaw, use the thumb as a guide and saw slowly using short strokes until the cut is started. (Courtesy Diston, Inc.)



A deep hacksaw frame will come in handy when slicing through a large workpiece. A good example would be the removal of a portion of butt stock prior to the installation of a recoil pad.

Face the work while sawing with one foot in front of the other and approximately 12″ apart. Pressure should be applied on the forward stroke only because the blade only cuts on the forward stroke. On the backstroke don’t let the teeth drag as this will dull the teeth and may cause the blade to break.



This diagram shows the proper stance and working height when using the hacksaw. (Courtesy Diston, Inc.)

Besides cutting metal, I also use a hacksaw to make fine, splinter-free cuts in wood—such as when sawing off a portion of a butt stock to install a recoil pad. Masking tape is first applied to the stock, the exact amount of wood to be removed marked, and then the cut is made. The only drawback is that the hacksaw frame is too shallow to make this in one cut. Therefore, a cut must be started on both the top and bottom and it is very difficult to align the cuts exactly. However, this problem can be overcome by using a hacksaw with a deep frame. Such a frame permits a deep enough cut so that the blade will only have to be started once when sawing through a butt stock.

Wood Files

Wood files and rasps are similar in design to metal files except that they are obviously used (only) on wood. They are certainly kin to metal files in all respects—the main difference being that wood files have coarser and different shaped teeth. Woodworking equipment is covered in detail in the next chapter.

Engraving Tools

Every gunsmith, gun lover or craftsman—no matter what his other calling—has the soul of an artist. This personal creative urge can be easily directed into the highly remunerative field of gun engraving through the proper learning techniques and much practice. This statement does not mean that anyone can become an expert engraver overnight. On the contrary, master engravers are the product of skill, devotion and hard work— tempered with a will for perfection. There is a machine, however, capable of infinite control in supplying impact power to a hand piece which is suited for the beginner who hasn't a lifetime to learn, or for the quality-oriented master who is production minded. It's called the Gravermeister and is manufactured by GRS Corporation. It's regulated through a foot pedal which serves the same function as the foot throttle in an automobile. Control is so precise that with the proper tool chucked into the hand piece, the operator can vary the power in ranges from stipple engraving on delicate crystal to the task of hogging out metal from a steel die.



If you can afford the cash outlay, and have a sincere desire to enter the field of engraving, you might want to consider the Gravermeister engraving system. Many professional engravers have adopted this machine as it greatly speeds up production. Before buying any engraving equipment, the novice should consider his own artistic talents (and temperament) and try to discuss the field of engraving with someone who is experienced in the art.



Gravermeister has a totally new concept in engraving pattern layout. Each numbered square has around 20 different design segments which are easily transferred to the metal surface you wish to engrave.

Delicate control of speed and power of this machine makes it ideal for gun engraving. It moves gravers, liners, beading tools, files, stones, etc., effortlessly in ranges from cutting steel dies to the delicate task of carving and finishing jewelry. Bright smooth cuts are obtained in both ferrous and precious metals. The alternating vacuum and pressure system does not permit the hand piece to heat as happens if operated by air pressure alone.

Florentine and matt finishing will be the types most used on gun engraving. Such finishes are applied with a tool installed on the Gravermeister called a liner, which is essentially a flat graver with equidistant V-shaped grooves cut into the bottom to produce parallel lines. Liners are categorized by width and number of lines per tool. The lower the width number, the narrower the tool; therefore, a #14-6 and a #18-6 would both cut six lines, but the #14 would be closer spaced because of its narrower width. Many different width and line combinations are available, but the liner generally favored by gun engravers for florentining is the #18-10.

Florentining consists of cutting crossed sets of lines. First, all of the lines in one direction are cut; then cross lines are applied at the preferred angle. A somewhat similar effect can be obtained by dragging the tip of the liner across the desired area. This action produces lines with no material removal. The stroke-speed setting and the speed with which the Gravermeister is pulled determine the spacing effect. If you drag the tool at a constant speed, increasing the stroke speed results in closer spaced lines.

The liner is sharpened the same as a flat graver; that is, the face of the tool is held at about a 45-degree angle and like most gravers should be polished after sharpening. In addition, the tip of the liner should be gently wiped a time or two on a sheet of crocus cloth to remove burrs thus permitting polished cuts.

In talking with Don Glaser, President of GRS Corp., I understand that few people have been able to take the tool and start turning out work rapidly without some personal preliminary instruction from someone who is familiar with the tool's operation. However, Don tells me that many have started engraving only after an hour's time when they got started right with some personal guidance.

The machine is like a piano. Those people who show an interest in the instrument and practice religiously start producing faster. Those who aren't willing to practice don't seem to do very well. Therefore, if you decide to purchase one of these machines, you'll do well to purchase several engraver's practice plates from Brownell's Inc. They sell cheaply in lots of five plates, so you can practice, practice, practice for very little money.

The tool itself is of very little use without certain other tools. First of all, you'll need an engraving block. One such block is offered by GRS and was designed by a master engraver who was tired of block movement when making precision cuts. This massive, 28½ pound engraving block is a precision, stable work-holder for all engraving including heavy cutting and chipping. The fully adjustable pivot drag will never develop looseness as the radial and thrust needle bearing between the crown and ball uses the entire mass of the block to absorb any undesirable shock or force on the cutting tool.

Besides an assortment of gravers, you'll need some means of sharpening them, as the tools will have to be sharpened often. The power honing tool—also offered by GRS—is ideal for this use. The power hone tool sharpener provides the same benefit for the task of sharpening that the Gravermeister does for engraving. It is faster and easier for the beginner to learn and saves valuable time for the experienced engraver. The fully shrouded motor is carefully balanced and trued to turn the 4″ silicon carbide stone, or the long-lasting, fast cutting 600 grit diamond lap smoothly and without wobble. The 115-V, 60 Hz motor rotates the stone at a smooth 200 rpm for fast, no-heat tool sharpening. High position of the stone gives ample clearance to sharpen all graver points and tip angles. Flat top surface provides ideal platform for combined use with the GRS sharpening fixture to maintain consistent angles.

The Graver Sharpening Fixture provides accuracy for sharpening the tools. It enables gravers to be located exactly every time, assuring that your tool will cut the same after each sharpening.

The example provided above shows a totally new concept in engraving pattern layout designed by GRS Corp. Each numbered section contains about 20 individual design segments or motifs which are molded into a transparent rubber-stamp material. You simply cut out the pieces you need to make up the final design you want to lay out on the gun you are working on; ink them on a standard ink pad and transfer the inked pattern to the metal. Since they are completely flexible, you can bend a piece to fit the complex curves of the gun; and being transparent you can butt one segment correctly to another one and see that you are getting it right.

When properly sharpened chisels are used, the Gravermeister can also be used for stock carving. Sharp, rapid blows of the machine render smooth, polished cuts in all kinds of wood. For relief carving on wood, first layout the design. Next, with a scalpel-like chisel gripped in the hand piece, follow the design outline backwards, not forward as one would in a normal cutting manner, at the same time applying power to the hand piece. Depth of the cut depends on the power supplied to the hand piece. Insert a scoop or gouge into the hand piece chuck and remove the background. As in metal work, the background can be stamped with a variety of punches, which of course are held in the jaws of the hand piece. Rasps, files and cutters held in the hand piece speed up the work without compromising control.





Engraving, such as the coverage shown on this Remington rolling block pistol, is a real work of art. You can be assured that the gentleman who did this job didn't do it overnight. A degree of artistic talent, the ability to take constructive criticism and more than a modicum of patience are necessary to pursue a career in engraving.

For wood carving, this machine cart be very useful for stock designs and the process may not be as difficult as one might imagine. Stan de Treville offers decal carving patterns that are easily applied to the gun stock, where they provide outlines and guidelines for use in carving.

Just because you have a pattern, don't install it on your favorite, most expensive gun stock and start carving away until you have gained some experience. It would be a smart move to buy two patterns of the same design and try the first on an old, broken or otherwise useless gun stock. When you have gained confidence in your carving ability, use the other pattern on a good gun stock.

8 - WOODWORKING TOOLS



All of these woodworking tools are available from Frank Mittermeier — it's called the Stock-Finisher's Kit.

THERE ARE many, many special woodworking tools available to the stock maker which you'll eventually want in your shop to speed up the stock finishing procedure. These include chisels, gouges, bottoming tools, rasps, inletting tools, curl scrapers and the like. You can, of course, stock up all at one time, but for openers, Frank Mittermeier's stock finishers kit will handle most of your needs. This set consists of one 8″ smooth cut cabinet rasp for shaping and smooth finishing the stock; a chisel and two gouges to cut away the extra wood during the semi-inletting of the action and trigger guard; a bottoming file for flat bedding the action; and, a barrel inletting rasp, to shape the barrel channel to the exact dimensions of the barrel is also included. The kit also comes with sandpaper for a smooth exterior of the stock and three checkering tools—one each single, 2 line and border tool. A diamond shaped lay-out template of the checkering pattern and full instructions on the whole procedure of inletting, shaping, finishing and checkering of the gun stock completes the set.

This kit contains all the tools necessary to completely finish a semi-inletted/finished stock. You can of course start with a walnut blank and do all the "bull work" yourself, but a lot of time can be saved if you start out on a semi-finished stock. Even if you have the time, you'll want to have several semi-finished stocks under your belt before attempting a complete stock from scratch. To do the latter satisfactorily, much talent and experience is necessary. On the other hand, anyone with a little patience and knowledge of what has to take place, can expertly stock a rifle or shotgun with one of the semi-inletted and approximately shaped blanks as offered by Bishop, Herter's, Fajen, and a host of others.

In general, the manufacturers of semi-finished stock blanks offer the blanks in two different ways: 1) for a standard model gun, they inlet the barrel channel to match the standard barrel; and 2) for a re-barreled gun (or an action that is commonly re-barreled), they generally provide a ½″ barrel channel. The final inletting of a semi-finished stock is a relatively simple matter, and if executed with a little care, even the most inexperienced gun craftsman can achieve professional results.


When it comes to tapping barreled actions into a semi-inletted stock, use a No-Mar hammer like this one.

Constant fitting of the metal parts to the wood with slow and careful removal of the excess wood is necessary to achieve the best results. In doing so, it is suggested that a spotting compound be used to indicate where the metal parts are touching; this provides a "map" to show the stock-maker where the excess wood must be removed.

The spotting compound commercially available is called Prussian blue inletting black such as the type sold at Brownell's, Inc. You can also make your own by mixing Vaseline with lamp black oil paint, obtainable at any hardware store. The main point for the beginner to realize is to proceed with caution—removing only a little wood at a time. Remember, once the wood is gone it cannot be replaced. If you do remove too much wood, you'll be faced with having to build up that area with epoxy or some type of wood filler.

To begin work on a semi-inletted stock, tighten the action down into the stock, allowing the barrel to settle down as far as it will go into the barrel channel. Because of the excess wood, this won't be very far. Outline the outside contours of the barrel and receiver; this will tell you how high your barreled action is riding in the stock. A gouge is used for preliminary shaping and deepening of the barrel channel and then a barrel inletting rasp is used to complete the channel. Final smoothing is accomplished with sandpaper wrapped around the inletting rasp.

Any excess wood at the sides of the receiver is removed with a small chisel. Then coat the bottom of the barrel and the receiver with spotting compound before it is carefully placed in the stock and tightened down. The receiver should be tapped solidly into place with a plastic hammer. You then carefully remove the entire barrel/receiver assembly. Any irregularities or high spots, as indicated by the spotting compound, should be removed with a small chisel so that the action fits snugly into the wood. As the job progresses, the proper tool to be used should become obvious. Final touch up and cleaning is done with a bottoming file. Lastly, it should be said that most suppliers of semi-inletted stocks can provide explicit instructions for inletting their stocks. Certainly, that information can prove invaluable in using the tools described.

STOCK REFINISHING


Old stock finish can be easily removed by using commercial preparations available from any paint store or gunsmith supply house. When removing finish from areas covered with checkering, a toothbrush will help make the job a lot easier.

If you're faced with removing the oily finish from old military stocks, mix a few ounces of whiting (available at most paint stores) with some AWA 1-1-1 and paint a thin layer onto the stock. As the solvent penetrates the wood, it dissolves any impregnated oil and brings it to the surface where it is absorbed by the whiting.



Once the old stock finish has been removed, any surface dents may be removed by applying a hot soldering iron to a dampened cloth placed directly over the dent. If the dent is severe, you may have to repeat the operation until the dent is raised completely or has risen to a point where a small amount of sanding will do the rest.





Before applying a new finish stock defects must be repaired. All of these stock defects may look hopeless, but, they can all be corrected by carefully splicing new wood to old. When splicing, great care should be taken to match up the grain flow of the new piece of wood to the grain flow of the stock itself.



BIRCHWOOD CASEY
TRU-OIL
GUN STOCK FINISH
STOCK FINISH
ADSCO
FLECTO
Varathane
Poly-Glo

The range of popular stock finishes seems almost unlimited. The choice of which finish to use is often a matter between you and the man whose stock is being refinished.



After sanding and filling has taken place it's time to select the finish you (and your customer) want and proceed following the instructions that come with the finish. In this instance, Birchwood-Casey s Tru-Oil is being used and applied with the hand. Applying an oil finish by hand makes the oil "stretch and flow" evenly.



As the coats of stock finish are applied, they must be given a proper place to dry out. A "drying closet" can be constructed out of plywood. A light bulb located at the bottom of the closet will help speed the drying time.

Depending upon me type of finish you use, you may find that the instructions advise sanding in between coats. If this is the procedure you are following, be sure to get a "Tac Rag" from one of the gunsmith supply houses. The Tac Rag is used to wipe down and remove sanding dust in between coats of finish.

This stock has received three coats of finish and is ready to be rubbed out. One of the most popular stock rubbing compounds is rottenstone. It can be found at any hardware store.

Checkering Tools and Equipment



"V" CUTTER



SPACING CUTTER



BORDER CUTTER

If you plan on doing any amount of stock work, chances are you'll want to get some checkering tools. The three basic cutting tools you'll need are the "V" cutter, a spacing cutter and a border tool.

Basic checkering tools are simple and inexpensive. This fact may lead one to believe that the process is just as simple. Checkering isn't difficult if you have patience. If you don't, you'll find the project impossible.

The basic tool used to checker wood is the "V" cutter which is used to cut the first or master lines. The other checkering tools used are the 2-line spacer and the border tool. The spacer tool determines the size of the checkering; that is the number of lines per inch. Generally, the 12, 14, 16, 18 and 20 lines-per-inch checkering is the most common on rifle stocks. The 20, 22 and 24 lines per inch are common on shotgun stocks.

In general, a checkering pattern is outlined on the forearm and pistol grip (both sides) of the stock and the outline and master lines are then cut with the "V" tool. This first pass should not exceed more than ½ the finished checkering depth. Now, working with the 2-line spacer, start at the end and work the spacer forward in short thrusts. Cant the tool enough to keep one row of teeth in firm contact with the line previously cut. After finishing the spacing in one direction within your checkering pattern, follow the same procedure in the other direction. When the spacing is complete, a second pass over the lines is performed with the spacer tool to remove the remaining wood.



Once the border of a checkering pattern is cut, take the 2-line spacer and, starting at the end of a border line, move the spacer forward in short thrusts, moving in one direction.



When cutting your borders, the use of a 2-line border cutter will provide you with a wide, concave border that's quite attractive.

On the second pass, cut the line deep enough so that the crest of the diamond will be nearly to a point. Keep brushing the saw dust out of your work as you progress because it can be very deceiving when it fills the diamonds or the grooves in between. A bordering tool may be used to obtain a wide, concave border if one so desires.

You may want to lay out your own patterns— perhaps using the book, *Checkering and Carving of Gunstocks* by Kennedy (Stackpole Books)—or use decal patterns as supplied by Stan De Treville. Stan has about two dozen different patterns from very simple to complex designs. All can be ordered direct or from gunsmith supply houses.



To start the checkering job, use a straight edge (or French curve where appropriate) and knife to outline the border on the stock. Once this has been done, take a single-edge checkering tool and deepen the cuts made with the knife.



After using your 2-line cutter in one direction, reverse field and cut the lines once again. When the spacing is complete and even in both directions, a second pass over the lines will cut them to full depth.



Checkering patterns or templates help simplify the layout of any checkering job. A wide variety of decal patterns are available from Stan De Treville.

When using the patterns, it may be desirable to make minor modifications so that the design will fit better on certain gun stocks. This is accomplished by shortening or lengthening the designs by overlapping or filling in respectively. Design modifications of this type are limited only by the creativity of the user.

To apply the decal pattern, cut the decal pattern sheet apart so that the forearm pattern and both grip patterns are separate. Soak them in water just long enough for the decal to begin to loosen from the backing paper. Dampen the areas on the gun stock where the designs are to go, and apply the decal by carefully sliding them off the backing paper into the desired position. Make sure the patterns on each side of the stock are in alignment, then swab smooth with a piece of cotton and wipe off excess water. Let it dry before attempting to checker.

At this point, three basic styles of checkering may be used. *American checkering* is the type most generally used on gunstocks made in the United States. In this type the lines are first scored lightly with a spacing tool starting with the "guide lines" on the decal pattern and working in both directions until the design is completed. The lines are gone over again with a "V" tool—as discussed previously—which deepens the cuts and bevels the edges of the diamonds. *English checkering* is similar to American checkering except the "V" tool is not used, leaving the diamonds flat on top instead of pointed. *French or Skip-line checkering* is most frequently used on fine custom made guns as it gives a more distinctive look than ordinary checkering. It is achieved by using two different width spacing tools. In the example shown, a regular spacing tool is used to cut three lines, then a spacing tool with twice the width is used to cut one line; then three more regular width lines are cut and so on. The effect may be varied by changing the number of regular lines cut, the number of lines skipped or both.


AMERICAN CHECKERING ENGLISH CHECKERING FRENCH CHECKERING

The most commonly found checkering styles are (from left to right) American, English and French—the latter referred to in this country as "Skip-line" checkering.

Once the checkering job is completed, place a damp cloth over the checked area. Then press a piece of Scotch tape firmly over the area and peel up; the tape will pick up the tiny pieces of decal which are left sticking to the wide flat-topped diamonds in a skip-line checkering job.

To start the checkering job, use a straightedge (or French curves where the lines curve) and knife to cut the border lines and the guidelines on the decal. Then use a single cutting tool to deepen the cuts made with the knife. Make certain that these initial lines are precisely cut as they will be your "guide" for all other lines cut in the pattern.

If hand checkering tools are used, the spacing cutter is then used to cut parallel lines to the guidelines as discussed previously. However, there are at least two types of power checkering tools on the market that will make the job go a little faster. The Burgess Vibro-Tool is an excellent tool to have around the gunshop. Besides the checkering tools, other accessories include engraving points, saw blade, abrasive point for frosting glass and sharpening tools, wood chisels, etc. Frank Mittermeier furnishes special checkering heads to fit the Vibro-Tool, and regardless whether you use the hand checkering tools or the faster MMC Power Checkering Head, you'll want the Vibro-Tool to checker up to border lines. Since the tool requires no back-and-forth motion, the cutter may be worked up precisely to border lines without overcutting.

For most checkering jobs, the Vibro-Tool should be used on its HI position; that is, 7200 strokes per minute. This speed gives a smooth even hum and is best for the delicate work of stock checkering. There is also a "Depth-of-Stroke" adjuster that controls the length of the stroke from a minimum of zero to a maximum of over ⅛-inch. To lengthen the stroke, turn the knob counterclockwise.


Power checkering tools can be helpful if you end up doing any volume of checkering work. The Burgess Vibro-Tool is very useful, especially when cutting near border lines.



One of the most popular power checkering tools is made by MMC — it’s used by many shops where checkering production is high. Above is a shot of the handle and power head; to the left is the entire unit, complete with motor.



When you want to adjust the width of the lines on the MMC power head, you simply turn the guide adjusting nut (arrow) clockwise for a coarser cut, counterclockwise for finer checkering. The schematic drawing shows the relationship of the adjusting nut to the rest of the power head.

Maximum finger control of the tool may be had by holding it like a pencil, but for checkering, the tool should be held more firmly. Don’t bear down too hard, as this will only shorten the stroke somewhat and tire the hand. Let the tool do the work for you. Also make certain that the stock is secured firmly in a checkering cradle or vise (in the case of small pistol grips, etc.). Always experiment with a piece of scrap material before trying out the Vibro-Tool on a new job.

One of the most popular power checkering tools in the industry is one developed by Bob Sconce of MMC. The outfit consists of a power checkering head and a Foredom industrial grade CC motor, flexible shaft, rheostat and a hand piece. The checkering head is a beautiful, precision high-performance instrument that has proven to be a popular money maker for anyone who checkers guns—whether he be manufacturer, full-time stockmaker, gunsmith or serious hobbyist. The fast, true-cutting operation, non-fatiguing ease of handling and simplicity of adjustment makes any checkering job a pleasure.



The handle of the MMC checkering unit is knurled just above the power head to provide a firm, sure grip.



The width of checkering with a power tool should be set by experimenting on a piece of flat scrap walnut and then measuring the results with a screw-thread gauge.

The checkering tool is set and tested at the factory for 18-lines-per-inch checkering. However, it may readily be adjusted to cut any other width checkering from 16 to 24 lines per inch by turning the guide adjusting nut clockwise for coarser and counterclockwise for finer checkering. Special thin cutters are even available for cutting checkering finer than 24 lines per inch. The depth adjusting screw should be adjusted so that the guide, when depressed, is level with the cutter. The width of checkering is set by experimenting on a piece of flat scrap walnut and measuring with a screw-thread gauge.

The guidelines should be cut to full depth as discussed previously. The remaining lines may be cut to full depth on the first two or three passes by tilting the head slightly to the left while making the passes. Subsequent lines will be cut to full depth and will require little, if any, "finishing up" with a hand tool. Of course, the proficiency of the operation comes with practice.

The speed at which the machine is operated is determined by conditions such as width of checkering, hardness of wood, and speed of the operator. Sufficient speed should be maintained to avoid chatter but excessive speeds accomplish nothing and might cause the cutter to heat. Too low a speed can cause the load on the flexible coupling to exceed the manufacturer's design and cause trouble.

If this is your first attempt at using the MMC Power Checkering Tool, don't expect to get a professional job the first time around. I experienced trouble in getting even lines the first few minutes of experimenting. However, like practically all new tools I have used, a few hours practice has made its use second nature. Again, practice on scraps of flat and curved pieces of walnut until some skill in manipulating the tool is acquired. Then you'll be ready to tackle a checkering job on a quality piece of walnut.

Miscellaneous Checkering Tools

You'll need some type of device for holding the gunstock firmly without damaging the finish and which permits the stock to be rotated or positioned at almost any angle for easy checkering. You can build your own like the one shown or from plans in The American Rifleman or other gunsmith books, but you'll probably do better by buying Brownell's Checkering Cradle. (This cradle sells for very little, and if you value your time at all, you won't come close to building one for twice the amount.) The Brownell Checkering Cradle is simple in design, low in cost, of rugged wood construction and highly practical. It's adjustable to hold stocks up to 33″ long. Stocks are held firmly without marring the finish, yet turning of the stock is permitted as the work progresses. It can be bolted to a bench or secured in a vise, the choice is yours.

I've experienced some difficulty in holding shotgun butt stocks in this device as the butt sometimes slips in the plastic holder. However, if you remove the existing wing nuts and screws and replace this with pointed screws you'll solve the problem.

When doing any checkering, you should be sure that the stock being worked on is securely held. A stock cradle is the answer; and, they are available from any of the gunsmith supply houses.

PLANS FOR A CHECKERING CRADLE

If you need a stock cradle and don't want to spend the money for a ready-made version, you can follow these plans and build your own.


3/8 HOLES - DRILLED 2" APART
ROD 1/2" x 13 T.P.I - 10" LONG
48"
3/8 BOLTS 3" LONG
2"
4"
GRIND TO FIT 3/8" COPPER BUSHING
WING NUT- STAKED OR BRAZED IN PLACE
10"
LOCK NUT
THIS NUT MAY BE BRAZED OR LEFT LOOSE
1/2" HOLE - 1" FROM TOP
STEEL UPRIGHT- 1/4" THICK
6"
1"
2"
3/8" HOLES
4"
2"
2 1/2"
6"
2x4 BASE
1/4" PLYWOOD SIDES
THE DEPTH OF THIS BOX SHOULD BE 1" TO HOLD THE STOCK.
BUTT STOCK HOLDER
FOREND HOLDER
3"
3"
DRILL THIS HOLE 1" DEEP USING A 3/8" DRILL. THEN INSERT A PIECE OF 3/8" COPPER TUBING, AS A BUSHING. A 3/8" WASHER IS USED AS A BEARING PLATE AT THE BOTTOM OF THE HOLE.
"2x2 PORE-BOY" CHECKERING CRADLE
DRAWING BY: LS MOCRER

Magnifying Visor: An optical glass binocular magnifier of 1½ to 2½ power is a big help in preventing overruns and for doing some of the more intricate checkering and carving. The most popular among gunsmiths is the OptiVISOR distributed by Brownell's. It magnifies 1¾ times at 14 inches. The next most popular size is the type that magnifies times at 8 inches.

Xacto Knife: Xacto knives have various shapes of blades available to make them very useful for cutting guidelines and for doing much of the carving on the fancier patterns.



One of the most useful "tools" a woodworker can have in his shop is a set of Xacto knives. For checkering work, they are handy for cutting guidelines. As you can see there are a variety of Xacto knife blade profiles.

Set of Small Carving Tools: Small chisels and gouges of various shapes are very useful in carving the small circles and scrolls found in some of the more ornate designs. Included in the category of carving tools is a layout guide and a checkering pounce wheel. The former insures that your checkering pattern comes out properly positioned and truly parallel to the top line of the fore-end as well as exactly matching the position of the pattern on the other side. The marking quill is fully adjustable to mark both top and bottom lines of the pattern, and the fixed arm is long enough to lay across the flats of the widest barrel channel.

The checkering pounce wheel is preferred by many for transferring patterns from paper drawings (or the Stan De Treville decals) to the stocks. With a little practice, you'll discover that by drawing the tool along, you can follow tight curves and sharp angles. The results are a series of deep, fine, easy-to-follow dots in the wood, which are a good guide for the knife or gouge to follow.



A Dem-Bart layout guide will help insure that your checkering pattern will come out properly positioned and truly parallel to the top line of the fore-end.



When laying out checkering patterns, or marking the lines on a checkering template, the checkering "pounce" wheel comes in handy. By first running this tool along the desired border lines, you will get a series of equally-spaced dots that serve to lay a path for your first border line cutting strokes.

Needle or Pattern Maker Files: These small files will come in handy for truing-up checkering and for finishing carved surfaces. Veiners, for example, are excellent for making curved lines, *fleur de lis* or any border work. They are also used for border clean-up at border junctions.

Checkering rifflers are used by many gunstock checkerers and stockmakers for pointing-up checkering, cleaning up damaged or old checkering and for border work. The No. 131 riffler offered by Brownell's has a 3-square shape, cutting a perfect 60° angle, and it will make the finest hair-line cut at the bottom of the diamond grooves.

Bent needle files that are "V" shaped and bent at 90 degrees are used to point-up 90-degree diamonds and normally come in medium or fine cut. The back of the file should be "safe"; that is, will not cut.

Three-square bent needle files are used for pointing-up new checkering and cleaning out old. This is the favorite of stock checkerers for getting true, sharp diamonds. Most are available in three cuts: *coarse*—for cleaning out old checkering; *medium*—for pointing up new diamonds; and *fine*—also for pointing up new diamonds.

You'll want to purchase needle file handles for use with all your files. Good needle file handles help the file become a part of your hand. They also help to control the direction of cuts and eliminate canting.

9 - BLUING EQUIPMENT

FEW gunsmithing projects can be as rewarding as the bluing of firearms. First of all, as the guns are dismantled, the operating characteristics of the guns become instilled in one's mind. Further handling of the more popular guns soon leads the gunsmith to know—almost instantaneously and without thinking—just what parts are worn, broken or need replacing. This knowledge is obviously invaluable when troubleshooting firearms.

Also, few operations are more pleasing than to see a rusted and badly-worn firearm turn into a thing of beauty with rich, blue-black finish instead of the reddish rust. For those who are not familiar with the bluing operation, the process seems like magic; that is, turning a worn firearm into one that looks brand new. But for the person doing the bluing, he knows that the process was not a magic act. Rather, it was accomplished by knowing what he was doing, a masterful job of polishing all the surfaces true and bright, keeping the corners sharp, and not funnelling the screw holes. Furthermore, he made absolutely certain that all parts were thoroughly cleaned with a degreasing solution before bluing. The results were rewarding—a perfect blue-black finish on the steel that will last for years to come.

Cold Bluing

AWA 1-1-1
WD-40

For cold bluing, you'll need some 3-0 steel wool, cold blue solution, clean cotton swabs, a degreaser and some quality gun oil.



If you plan on cold bluing an entire rifle or shotgun, you might want to consider buying a Birchwood-Casey cold blue immersion tank. It will help to make a neat job out of a chore that can sometimes become a shade messy.

There are dozens of cold or instant bluing solutions on the market that will blue or blacken gun metal. Some are superior to others, but all of them will produce good results if care is taken. Regardless of the bluing solution used, you will need a cleaner-degreaser solution, steel wool, applicators and for other than touch-up jobs, a blue remover cloth. One of the best kits on the market is supplied by Birchwood Casey and called Perma-Blue Kit. This kit contains everything needed for a quick touch-up or a complete rebluing job. It is also one of the easiest bluing solutions to use. It gives a deep blue-black finish with few problems.

The equipment shown is essential for good cold bluing results. Rubber gloves should be worn to keep finger prints off the metal parts and to avoid any possible skin irritation. The large wire ring-handled dauber-type swabs are excellent for applying the blue and rust remover, the cleaner-degreaser and the cold blue solution. Steel wool is used for removing rust, scouring, polishing and burnishing the metal surfaces of the firearm. The oil is applied for lasting protection from rust. All of these supplies are available from Brownell's.

To cold blue a firearm, first clean all parts to be blued with a cleaner-degreaser to remove all grease, oil and dirt. This cleaner may be one of the commercial cleaner-degreasers like those manufactured by Birchwood Casey or any of the substitutes for old-fashioned carbon tetrachloride (such as chlorothene). Wood alcohol may also be used to clean the metal surfaces. Once clean, wipe the surface of the metal dry.

The old blue is removed with a liquid blue and rust remover such as those supplied by Herter's, Brownell's, Birchwood Casey, etc. Use a piece of steel wool to apply and scrub all parts to be reblued. However, before using the steel wool, it must be thoroughly degreased with RIG III (or some other suitable degreaser) as most steel wool comes from the factory soaked in oil to prevent rusting.

Once most of the old blue is removed, brighten all areas to be blued with abrasive cloth (320 followed by 400 wet and dry sandpaper strips will work nicely). Work around the barrel from the muzzle to the breech with a rapid "shoe-shine" motion—removing as many rough spots and pits as possible.

Once again clean all of the metal parts with the cleaner-degreaser and afterwards do not touch any of the metal parts, not even with the rubber gloves if at all possible. Apply the cold blue with the swabs in long even strokes. Do this as quickly as possible and try not to let the bluing solution run all over the metal; it should be carefully applied, not splashed on. After the solution has worked about one minute, it should be wiped off with a clean, oil-free cloth. Polish the reblued surface with clean (degreased) steel wool and then reapply the bluing solution at least three times to obtain a rich dark blue and to thoroughly cover all areas.

After the desired results (depth of color) have been obtained, oil the metal thoroughly with a good gun oil or Birchwood Casey's Sheath Take-Along—a polarized rust preventative which neutralizes the corrosive action of moisture, sweat and salt water. It dries to a thin, non-gumming film.

For mere touch-ups, good results can usually be obtained by just degreasing the metal and applying the cold blue until the area blends in with the surrounding metal. Of course, wipe clean and oil.

One of the disadvantages of cold bluing is the difficulty in obtaining an even finish over the entire surface. Streaks and uneven surfaces are common if great care is not taken. Birchwood Casey offers an immersion cold blue kit that greatly simplifies the process and eliminates streaks and uneven surfaces. The kit comes with a plastic tank and the necessary chemicals and materials to blue 10 or more guns. All parts are dipped in the chemicals rather than applying them with swabs as discussed previously. The operation, however, is otherwise similar to the conventional cold bluing process. The result is an even, rich blue-black finish that closely resembles the color obtained from the hot bluing salts method.

Even professional gunsmiths are finding a use for this cold blue kit. Double barreled shotguns and those with soft soldered ribs are seldom blued by the hot-dip process as the chemicals react on the solder to soften it. A time-consuming rusting process is normally used—requiring several hours (if not days) to complete the job. This cold bluing immersion kit enables these jobs to be performed in a short time with good results.

The plastic tank that comes with this kit is also excellent for using blue and rust remover solutions prior to hot bluing.

Professional Hot Bluing

The hot bluing method is used by all leading firearm manufacturers in their finishing operations. It is also the common method employed by gunsmiths doing a large volume of bluing jobs. The resulting black oxide finish is handsome, extremely durable and "takes" well on modern steels. At this point it should be stated that the bluing process is an oxidization process intended for ferrous metals (steel) only. Many of today's firearms utilize aluminum components. A good example is Smith & Wesson's Model 39, 9mm autoloader. The frame of that pistol is made of aluminum alloy. It *cannot* be blued by conventional cold or hot blue methods. In fact, any attempt to *hot blue* any aluminum alloy part will result in that parts total destruction. When it comes to "bluing" aluminum, *don't*.

If you're not sure if a part is aluminum or steel, keep a small magnet handy and you'll get your answer fast. (Blackening aluminum is covered further on in this chapter.)

The steps required to perform this steel bluing are as follows:

1. Remove old finish.
2. Polish all surfaces to be blued.
3. Clean metal surfaces in hot alkali cleaner.
4. Rinse in cold water.
5. Suspend parts to be blued in bluing solution.
6. Rinse in cold water.
7. Soak in hot soluble oil or boil in water for about 10 minutes and then oil all surfaces thoroughly.

The following are the essentials for a good professional quality blue job:

Polishing Equipment: A two-wheel buffer with one cutting wheel and one finishing wheel is a minimum set-up for polishing metal parts to be blued—if the operation is to be handled on a profitable basis. Many firearms have been blued with hand polishing only, but the time involved prohibits its use in this day and time.

The Baldor buffer seems to be the most popular for use in gunshops. For the professional shop doing a substantial business, a 1 HP motor at 1725 rpm is recommended. For an occasional bluing job, a smaller buffer will give complete satisfaction as will a muslin buffing wheel attached to a conventional bench grinder or even a drill motor held in a vise.

A heavy cast iron buffer pedestal will help keep the buffer perfectly steady during operation and gives free access to both polishing wheels for best polishing results. The ideal mounting location is away from walls so that both shafts are exposed for full 360-degree polishing on all parts of guns including barrels and receivers.

My own buffer consists of a modified bench grinder obtained from Montgomery Ward. It is mounted on the corner of my work bench to expose the left-hand shaft of the grinder. The left-hand grinding wheel was removed, as well as the guards and 6″ and 8″ buffing wheels are used for buffing. The speed of the shaft is 3600 rpm. This setup gave me a combination buffer/grinder that takes up little space and didn't cost me an arm and leg. For the occasional bluing job, I consider this setup to be ideal.

A very satisfactory finish for hunting guns may be obtained by using 3 stitched muslin wheels and 3 loose muslin wheels on the buffer. On one end of the buffer's double shaft, place 3 stitched wheels and on the other end, place the 3 loose muslin wheels. Before applying any polish, however, make certain that the wheels are in proper condition to receive the polish. A crystolon rubbing brick may be used for dressing, cleaning and/or truing felt and muslin wheels. These bricks are ideal for breaking in new muslin cloth wheels prior to applying the first application of polish.



Baldor's 2-wheel buffing unit is popular with many gunshops across the country. It's an item—when properly used—that's essential to any bluing operation.



If you opt to go the power-buffer route and are short on rigid bench space, a mounting pedestal like this one will do the trick.

The author's own metal polishing system is simply a modified bench grinder complete with buffing wheel.



When your buffing wheels become overloaded with buffing compound, you will have to dress them down a bit. A crystolon rubbing brick is perfect for the job.



When applying polishing compound to a buffing wheel, the best way to do so is to get the wheel running full tilt, then, after turning the motor off, apply the compound until the wheel stops.

With the wheels in shape, start the buffer and bring it up to full speed; then shut it off. As the wheel speed is slowing down, touch the tube of polishing compound, to the wheel until it stops. Several applications will give a smooth even coating, which should be allowed to dry about 5 minutes prior to using. Grit size 140 should be applied to the stitched wheels and 240 grit to the loose muslin wheels.

The buffing wheels are now ready for cutting and polishing, but in doing so, be careful at all times not to round corners on frames and actions or to funnel screw holes. Either lowers the value of the firearm and is certain to curtail future bluing jobs for you.

The hot bluing method is used by leading firearm manufacturers in their finishing operations and is also the common method employed by gunsmiths doing a substantial volume of bluing jobs. The resulting black oxide finish obtained by this method is handsome, extremely durable and “takes” well on modern steels. Simply put, it’s a professional finish.

The steps required to perform the hot bluing operation are as follows:

Remove Old Finish: A rust and blue remover, such as the type offered by Brownell’s, is the easiest and fastest way to remove the old finish. Follow directions carefully and don’t leave the metal parts in the solution too long.

Polish All Surfaces: A very satisfactory finish for hunting guns may be obtained by using 3 stitched muslin wheels and 3 loose muslin wheels on the buffer. Grit size 140 polishing compound should be applied to the stitched wheels and 240 grit to the loose muslin wheels.

Clean Surfaces in Hot Alkali Cleaner: A cleaning solution such as Dicro-Clean No. 909 should be heated in one of the tanks and all metal surfaces soaked in this compound for about 15 minutes.

Rinse in Cold Water: Remove the parts from the hot cleaner solution and quickly transfer to a cold water tank for rinsing. Scrub thoroughly with a soft (not metal) bristle brush to remove all of the cleaner, making sure that all parts are submerged at all times.

Suspend Parts in Bluing Solution: Bluing solution should be kept at a temperature from between 285 degrees F. to 292 degrees F. and the parts suspended in this solution from 15 to 30 minutes. Parts should not be allowed to touch sides or bottom of tank.

Rinse in Cold Water: Again, rinse the parts in cold water. Make the transfer from the bluing tank to the cold water rinse as quickly as possible.

Boil Parts to Stop Bluing Action: The parts may be soaked in a hot oil solution or boiled in water for about 10 minutes and then oiled.

More detailed directions accompany the bluing salts and these should be followed exactly as instructed. Salts are available from Brownell’s; Knife & Gun Finishing Supplies; or Heatbath Corp.



The multi-tank bluing setup is the most professional way to go about any hot-bath bluing operation. In this setup, each tank has its own water and heat source. Multitank bluing operations insure thorough degreasing, rinsing and bluing steps.

The initial equipment required to set up a bluing operation on a professional basis will cost approximately $1200 to $1500. Some gunsmiths have blued firearms for much less money, but to do the job right, you’re going to require about $1200 worth of equipment.

There are two basic ways to go about setting up for bluing firearms: You can purchase 6 individual 6″ x 6″ x 40″ long tanks, build your own frames and then have pipe burners installed under four of them. The other way is to order a complete bluing unit (requiring very little installation time) from Heatbath Corp. Their 6-tank model is shipped complete and includes 100 pounds of Nickel Pentrate bluing salts, 25 pounds of Pentrate Cleaner, rubber gloves, a thermometer, water soluble oil, water reservoir and splash guards. This outfit and the polishing equipment described previously will put you in business immediately. All that is left to purchase is a tank or two of bottled gas for fuel.

Of course you will still need to acquire some experience. You may be lucky and have your first attempt come out perfectly, but if you’re like me, my first attempts were like playing a slot machine in Vegas—I never knew just what color the metal was going to be next. They came out green, plum, red, and some even blue-black, but eventually I got the hang of it and haven’t had a failure in quite some time.

You’ll need an area of at *least* 8' x 8' for your bluing and buffing operation and the area should be away from your normal business or shop area because of the harmful effects of the bluing fumes; that is, odor and the ability of the fumes to rust any metal that it should come in contact with.

Pure water is another necessity for good bluing jobs—especially when using the hot water method discussed next. Some of the chemicals that are found in city water prove harmful to some bluing solutions and cause less-than-par jobs. I use rain water that runs off my shop roof, catching it in a barrel from the downspouts. Fifty gallons will go a long way!



In his own shop, the author has installed a Heatbath 6-tank bluing outfit.

Supreme
Supreme

When using the "hot-water" bluing method you will need the following items: a clean glass jar, cotton balls, steel wool, rubber gloves, degreaser, carding wheel, stainless steel brush and some Herter's Belgian Blue.

Hot Water Bluing for the Hobbyist

For the hobbyist or the professional who has only an occasional gun to blue, the hot water bluing method is the easiest to set-up for and with the least expense. If care is taken, an excellent velvet blue-black finish will result.

You can get by with one tank for this method, but you'll obtain better (and faster) results by using three separate tanks—two of them with heat. One tank is used to degrease the metal parts as discussed previously; one tank is used for rinsing parts, and the third is used to boil water to bring the parts to a temperature to accept the bluing solution.

The basic formula for bluing guns by the hot water process was developed in the late 1800s and consisted, basically, of sodium and potassium nitrates, potassium chlorate, and bichloride of mercury, mixed in distilled water. If you'd like to mix your own, or have it mixed by a local chemist, here's what you need.

750 grains (avoirdupois weight) Mercuric chloride
1000 grains (avoirdupois weight) Potassium chlorate
1200 grains (avoirdupois weight) Potassium nitrate
300 grains (avoirdupois weight) Ferric chloride
150 grains (avoirdupois weight) Cupric chloride
300 grains (avoirdupois weight) Sodium nitrate

Weigh and mix these chemicals in a clean glass jar then heat 1700 cc's of distilled water to 130 degrees F. and pour the heated distilled water into the glass jar containing the six previously-mixed chemicals, agitating continuously until all ingredients are completely dissolved. Let cool and after 24 hours, add 175 cc's of sweet spirits of niter (ethyl nitrate) and shake well. Place solution in a dark glass bottle (blue or brown) and let stand 24 hours before using. Label the bottle *POISON*.

If you don't care to go to all the trouble, commercial bluing solutions are available. Herter's Belgian Blue is excellent; so is Brownell's Dicropan IM and Stoeger's Yankee Blue, although the latter is becoming hard to find. All of these solutions may be used for the hot water method of bluing firearms.

Besides bluing tanks and a source of heat, the equipment needed for the hot water bluing process is as follows:

Dicro-Clean No. 909: Used to remove all grease, traces of bluing compound and dirt. It is added to water and brought to a temperature of approximately 180 degrees F. before submerging parts to be cleaned.

Glass Jar: To be used to heat the bluing solution. It is suspended by an iron wire in a corner of the hot water tank and the bluing solution poured directly into it.

Herter's Belgian Blue: Bluing solution used for the hot water method of bluing firearms.

Swabs: Used to apply the bluing solution to the metal. The large wire ring handles on the swabs make it easy to flood the surfaces with the solution after they are heated in the hot water.

Stainless Steel Brush: Used for carding (removing rust) from hard-to-get-to places on the guns.

Steel Wool: Used for general carding of metal surfaces.

Carding Wheel: Used on the electric buffer for carding metal surfaces.

Rubber Gloves: Used to protect hands from chemicals and hot surfaces; also protect metal surfaces from finger prints. Many experts of the past have recommended white cotton gloves to handle guns during the hot water bluing process, but this writer has found cotton gloves to become soiled quickly. Rubber gloves are best.

Clean water and an appropriate amount of the Dicro-Clean No. 909 is added to a tank and the metal parts boiled for about 15 minutes.

Meanwhile, a tank of clean distilled or rain water is being heated in another tank. The clean jar containing the bluing solution is suspended in one corner of the tank so that part of the jar is underwater. Be careful not to let any of the water in the bluing tank splash into the jar to mix with the bluing solution.

After the cleaning period is completed, remove the parts from the cleaning tank and quickly transfer them to the rinse tank, and then immediately into the hot water tank. The water must be kept at a slow, rolling boil from here on out. Nothing else will do. The parts should be suspended from iron wires from above or else placed on U brackets within the tank. Just be sure that none of the parts touch the sides or bottom of the tank. If they do, "hot spots" and blotchy bluing will be the result. Small parts may be individually suspended by wires or else placed in a wire basket which is then suspended in the tank.

Let the parts boil for a full 15 minutes the first time to insure an even heat throughout. Then remove the largest part from the tank and shake excess water from the metal. If the surfaces do not dry immediately of their own heat, put the part back in the tank and let it heat for at least another 5 minutes (the part is not hot enough). When the part is hot and dry, set the part on clean V-blocks, on clean paper, or suspend the part in mid-air with wire. Then quickly, before it cools too much, dip a swab into the hot bluing solution and dampen the swab. Don't "load" the swab, just dampen it. Then swab the solution on the hot metal with long, light strokes, avoiding runs and puddles. Allow the fluid to "work" about five minutes and then return the part to the hot water tank for another five minutes. Again remove the part and swab more of the solution onto the hot metal surfaces. Do this to each of the other parts in turn, returning that part to the hot water tank after the solution has been allowed to work for about 4 or 5 minutes. Reheat and apply the solution twice to each part. The bluing solution should dry almost instantly upon application.

Following the second application, you'll see a grayish coat, flecked with rust, forming on the metal. Now, before returning the part to the hot water tank, rub it briskly lengthwise with fine 00 steel wool. Use the stainless steel brush to get into tight places. As the gray disappears you'll see a blue-black finish begin to develop. Then put the part back into the tank.

Continue this process as many times as necessary to obtain the finish desired. Five or six passes should be sufficient for most metals. When you have obtained a satin, blue-black finish, return all parts to the hot water tank and boil for at least 15 minutes to halt all of the rusting process. During the final few passes, you may want to use a soft wire carding wheel on your buffer to card the rust from the parts. Oil all parts thoroughly and the job is finished.

When cleaning/degreasing prior to using the "hot-water" method, the author uses a small, portable tank and heat source. In this instance, a set of barrels is being readied for a 15-minute boiling hot-water bath in a solution of degreaser and water.

Following the second application of Herter's Belgian Blue, the set of barrels are rubbed briskly with fine steel wool to remove the rust formed by the bluing solution. (Note the use of rubber gloves.)


Once the barrels have been removed from the final bath, you may want to finish the job off by lightly using a soft-wire carding wheel along the barrel's exterior.


One way to remove anodizing from aluminum parts is to use some steel wool and alcohol.

Blackening Aluminum

Some trigger guards and other parts on modern firearms are made of aluminum. The bluing methods previously described will not blue aluminum, and therefore, some other means of blackening the metal must be used. One method is to use Brownell's Aluma-Hyde which is a spray-on lacquer which gives the appearance of bluing.

To refinish an aluminum gun part, use steel wool saturated with alcohol to remove the old finish. Then apply the Z/C primer on all surfaces and allow to dry. Follow with two light coats of black lacquer. The result is a beautiful, tough, scratch resistant, semi-gloss finish that wears almost as well as the original anodizing. The color is also a close match to the original.



After removing the old finish from an aluminum part, you can apply a couple of coats of Aluma-Hyde. It provides an attractive finish that's almost as tough as the original anodizing.

Engraving Inlay Kit

Gold Lode, Inc., offers a 23 kt. gold engraving inlay kit that enables you to enrich all engravings with genuine gold. Each kit contains enough gold to do one or two lavishly engraved firearms and the steps are simple. The kit contains Agent No. 1, brush, cloth, dropper and a jar of gold crystals, everything necessary for a complete job.

Using the soft cloth and Agent No. 1, carefully clean the engraved areas, removing any grease or dirt. Then add Agent No. 1 to the gold mixture (about 40 drops) and mix with the brush to a smooth mixture. (Work with the mixture on the thin side.)

Brush a thin coat of gold over a section of the engraving and before it dries work the gold into the engraving with the index finger. Repeat this operation until all of the engraving is filled.

Wrap a portion of the wiping cloth around your index finger and dampen the cloth with Agent No. 1. It is important that the cloth is damp only. You can be sure of this if you apply the dampened section to a piece of paper towel to remove the excess. Gently work your finger and dampened cloth over the engraved area to remove the gold from the smooth sections leaving the gold in the engraving. A felt block is provided with the kit to be used in the same way as the cloth to remove the gold from the hard-to-get-at areas.

After you have completed the entire area, inspect for any spots that might have been missed. Allow the inlaid area to dry for 30 minutes and then polish with a smooth cloth.



When using Gold Lode's engraving inlay kit you must first remove all grease and dirt from the engraved recesses to be filled.

Your next step in using the Gold Lode kit is to add about 40 drops of that kit's "Agent No. 1" to the gold mixture that's provided.



Next, brush on a thin coat of gold over a section of engraving.



After the gold coat has been applied—and before it dries—work the gold mixture into the engraving as shown.



Now that the gold mixture is fully into the engraving, take a cloth dampened with Agent No. 1 and lightly go over the engraving to remove excess gold mixture from the surrounding nonengraved surfaces. Once the excess mixture has been removed, allow the inlaid areas to dry for about 30 minutes and finish up by polishing with a soft cloth.

Plating

Many firearms—especially handguns—are nickel plated for appearance and to protect the metal surfaces. Conventional methods of plating are often beyond the reach of the average gunshop and many gunsmiths bypass this operation. However, there is one kit, offered by Texas Platers, especially designed for the gunsmith. All you need, besides the kit, are three 1½-volt ignition batteries. The batteries are connected in series with the negative terminal connected to the gun or part and the positive (+) terminal connected to the brush holder or handle. The brush is then dipped into the solution (nickel, gold, brass, etc.) and merely brushed onto the surface. Of course, all surfaces must be clean—just like before bluing a firearm—and several coats will have to be applied to obtain a durable finish.



Here, the Texas Plater's nickel plating apparatus has been set up and is ready to go.



When using the Texas Plater's kit, you get a quality finish by simply brushing on the plating solution as shown.

Parkerizing

Parkerizing has long been the metal finishing process used by the armed forces since it is highly rust resistant and wears longer than most hot bluing processes. The old method consisted of boiling the parts to be finished in a solution of Parko Powder composed of specially prepared powdered iron and phosphoric acid. During the process, minute particles of the gun's surface are dissolved and replaced by insoluble phosphates which are rustproof. The result is a slight etching of the surface, giving a dull, non-reflecting finish.

To Parkerize a firearm, you will need a stainless steel tank large enough to accommodate the gun parts; a thermometer that will measure up to 180°F (± 5°F) and a measuring cup (graduated in ounces) and a pair of tongs with at least 8″ handles.

Degreasing Parts: Clean grease and oil from parts with gasoline, perchlorethylene (dry cleaning fluid) or mineral spirits.

Rust or Scale: Rust or scale must be removed by dry abrasive blasting using glass beads. If you don't have the equipment, most automobile body shops will do this operation for a small fee. Glass bead all parts until a chrome look is obtained and no dark spots remain.

After the abrasive blasting, do not handle parts with bare hands as this will leave body oil on the parts and cause spotting. Use rubber gloves, just as for bluing, for handling parts. Treat the parts as quickly as possible after abrasive blasting—never more than 3 hours.

If you don't have a sand blasting machine and the glass beads, an alternate rust or scale removal method will work with reasonably good results. U se a 50/50 solution of muriatic acid and water in a plastic or glass container. Place the parts to be parkerized in this solution, and while keeping all parts submerged, brush off all rust and scale, using a bristle brush. Do not, however, leave the parts in the acid solution for a prolonged time as the acid will dissolve the metal parts.

Remove the parts from the acid and immediately rinse in running water for not less than 30 seconds and not more than 1 minute. Then immediately place parts in the treating solution. Do not let the parts dry after the rinse. As with any chemicals, wear safety goggles or a face shield and avoid contact of acid with skin.

Treating: Prepare enough solution to cover all parts sufficiently at a concentration of 4 ounces of parkerizing solution per gallon water (3% by volume). Put the solution in the stainless steel tank and bring the solution to a temperature of between 160 and 170 degrees F. The parts are placed in the solution with the tongs, taking care not to touch the parts with the bare hands. Allow the metal to react, turning the parts periodically so as to get an even treatment. However, be careful not to agitate the parts where they will rub or grind against each other.

The parts should be left in the solution for about 40 minutes, maintaining the prescribed temperature at all times. Then remove the parts with the tongs and immediately rinse in cool running water for one minute. Drain excess water and dry with a clean absorbent cloth. Once the parts have dried, immediately dip them in a light oil or spray the part with WD-40. Wipe off excess oil and the job is completed.

The bath can be used as long as the solution is clear. A cloudy solution indicates depletion of its active ingredients. However, once the solution has cooled, do not attempt to reheat and use. If you'd like to try the process described above, the solution is available from Marion Owens in Greenville, SC.

Slow Rust Bluing

All of you have probably seen the TV advertisement where an American car is supposed to look so much like a much more expensive European car that it fools an entire police escort. Well, I happen to own the American version and my brother owns the European car, and while both cars do look similar, from a distance, a closer examination quickly reveals the higher quality of workmanship in the more expensive model. The same is true with gun bluing methods.

For the past 40 years, all firearm manufacturers and professional gunsmiths have turned almost 100% to the caustic nitrate hot bath method of bluing firearms since this method is much faster and gives more uniform results than any other method known. Furthermore, labor is cut to a minimum and fairly good results may be obtained if an expert polishing job is done and the salt bath is maintained at the correct temperature. However, the initial setup is generally too expensive for the amateur with only a couple of guns to blue from time to time, and the dangers of the bluing solution is too risky for use in the home. It'll ruin floor tile, take enamel off the kitchen stove (the prime source of heat for bluing in the home), eat through leather shoes and wool clothing, and cause blindness if any of the solution should splash in your eyes. In my opinion, it's a method that should be left strictly to the professional.

On the other hand, any gun owner who is willing to spend from 8 to 12 hours of hard work, and about $50 cash can obtain a rich, velvet blue-black finish that will surpass any of the factory jobs by using the cold-rusting process. This is not the same method as the "instant" or "touch-up" bluing solution. It's a slow, cold-rusting process used only on expensive rifles and shotguns.

It's difficult to explain the difference in the cold-rusting process from the hot bath bluing method, but once you have compared the two side by side, no other type finish than the cold-rust process will seem satisfactory. For durability, it can't be beat; it resists wear better than any other type of bluing known. To prove this to yourself, compare a modern firearm that has seen, say, 10 years of normal use to the one that was manufactured around the turn of the century when the cold rusting process was used by many of the manufacturers. Chances are, the older gun will have more remaining blue than the modern firearm.

Materials Needed for Slow Rust Bluing

If you have a bench vise and two water-tight metal containers large enough to hold the gun parts, you'll be able to blue several guns for a relatively small investment. You could buy two 6″ x 6″ x 40″ bluing tanks but to save quite a bit of money you can substitute with two 3″ x 6″ x 36″ chicken feeding troughs—available at your local farm supply store. Just make sure that the tanks are made of ferrous metal or stainless steel; don't buy galvanized tanks.

A 10″ mill bastard file and file card is needed if the gun has rust pits, nicks, scratches, etc., too deep for the abrasive paper to remove. Otherwise, these two items can be eliminated. The method of applying the bluing solution can vary, depending on your preference, from cotton balls, to ring-handled dauber-type swabs, to small sponges. If you choose the easy-to-find cotton balls, you'll also need a pair of needle nose pliers to hold them.

Purchase three sheets each of the following grit of aluminum oxide (open coat) abrasive paper. If your local hardware or automotive supply store doesn't have them, order them from Brownells: 80 grit, 150 grit, 240 grit, 320 grit. You'll also need three sheets each of 400 and 500 grit silicon wet and dry paper for the final polishing.

A package of 00 steel wool and stainless steel brush made of .005″ hand-tied stainless steel wire is necessary for carding the rust from the gun. Most steel wool, however, comes from the factory soaked in oil to prevent rusting and this oil must be completely removed before using it to card the rust from the gun.

Most experts recommend wearing clean white cotton gloves during the bluing operation to insure that your hands, which contain oil, will not come into contact with the gun metal. White gloves are fine for the boiling and application process, but tend to become rather soiled during the carding operation. For this reason, I use rubber gloves during the carding process after they have been thoroughly degreased in the degreasing solution along with the gun parts. There are several good degreasing solutions on the market, but a can of household lye (sodium hydroxide) will do the job just as well. If you use a commercial cleaner, follow the directions on the package.

A source of heat can be the kitchen range, but to keep on good terms with your wife, you'll do better to take the work to the basement or garage and use a camp stove or gas hot plate.

There has been a lot of controversy over the effects of ordinary tap water on the bluing job. Chemicals added to city water supplies are said to have an adverse effect on the final results. "Hard" well water can also do the same thing. I've always used cistern water for my bluing jobs and this is about as pure as you can get outside of distilled water. You might try catching 8 to 10 gallons of water the next time it rains by placing plastic dish pans out in the yard; or if you want the purest, distilled water may be purchased at your friendly drug store.

Another way to get pure water is to have your pharmacist get you a water "deionizing column." A deionizing column is nothing more than a clear plastic cylindrical container packed with purification crystals. There are couplings at either end for surgical tubing; and, you simply run tap water (slowly) through a column into a clean receptacle —a gallon jug works well. Deionizing columns come in various sizes; the larger the column the greater the expense. If you plan to do a fair amount of bluing the money spent will be worth it.

(If your pharmacist bridles at acquiring a deionizing column for you, don't be surprised— that's probably how he makes his "distilled" water. Just assure him you're not going into competition with him and you'll notice the color return to his face.)

You'll need some tapered dowels to plug the bore of the barrel and also some gun grease to lubricate the inside of the barrel to prevent it from rusting during the bluing process. You can mix your own bluing solution from chemicals available from your local drug supplier, but you'll be money ahead if you buy a solution from Dixie Gun Works already mixed for the purpose.

Now that you have all of the materials at hand, get ready for some hard work, but keep remembering that you are getting the best blue job that can be obtained.

Draw filing light rust off of shotgun barrels is acceptable; however, remember that those tubes are thin and you can only go so far without weakening the barrel itself. Also, you should remove any dents with a dent removing tool, not a draw file — those shotgun barrels are thin.



Prior to bluing, be sure to remove any dovetailed parts from the barrel, slide or action assembly. If you leave those parts in place, the bluing solution will work its way in between the dovetail and the part it holds. The solution may oxidize the sightblade to the dovetail, making later removal or adjustment difficult, if not impossible.

Polishing

Aside from keeping the metal surfaces free from oil, polishing is the most important step in obtaining a rich, velvet finish on your gun. Without proper polishing, you might as well forget bluing the gun and leave it as is. The coloring of the metal will never cover up pits, scratches, and the like. The surface of the metal must be perfect before the bluing solution is applied. Nothing less will do.

Most professional shops utilize power buffers for polishing, but most hobbyists will have to do the polishing by hand. So much the better! Only by hand polishing can all contours, lettering, markings and square edges be properly preserved. About 5 hours of hand polishing is required for the proper polishing of a bolt action rifle; a little more for a pump or double barrel shotgun.

Roy Dunlap points out in his book, *Gunsmithing*, that a hand-polished gun of course, looks better than a power polished one, since corners and angles can be maintained with no loss of profile. A rather surprising fact is that an excellent final finish can be obtained on metal polished by hand, while metal polished by power to the same apparent finish before bluing will not turn out as well.

The first step is to completely disassemble the gun down to the last screw and drift pin. If you're unfamiliar with the take-down procedure, exploded views and instructions are available from the manufacturer on modern arms. The *Gun Digest Book of Exploded Firearm Drawings* and Brownell's *Encyclopedia of Modern Firearms Parts & Assembly* are two good sources, as well as the new Gun Digest Firearms Assembly & Disassembly series. For guns with no printed instructions, I'd suggest making notes as you disassemble the gun and perhaps even taking close-up photos of intricate parts. You'll then have some reference to go by when you're reassembling the firearm.

Wipe each part clean and examine for wear and to insure that no aluminum alloy parts are present. This can easily be determined by using a toy magnet. If the magnet doesn't react, then the part is nonferrous—aluminum, brass or similar alloy— and these parts should be set aside with other parts not to be blued by the cold rust process. Steel parts normally not rust blued are springs and other small parts not visible when the gun is assembled.

With all the parts to be blued in one pile, thoroughly clean each one with a solvent such as acetone AWA 1-1-1—the safe substitute for carbon tetrachloride. Start with the barrel or the barreled action, and clamp this assembly in a padded vise. Care must be taken, however, not to "clamp down" too hard and damage the gun parts.

Prior to any bluing, inspect the gun for any major pitting. Depending upon



Heavy nicks in gun barrels can sometimes be peened back into shape prior to the depth and coverage, you may want to remove the pitting with a draw file.

polishing; however, draw filing is usually the answer.

If the gun requiring bluing has rust pits, nicks or scratches that are too deep for the abrasive paper to remove, use a 10″ mill bastard file to smooth all metal surfaces. With the tang of the file in the left hand, and the tip in the right hand “draw” the file on the metal toward yourself over the surface to be smoothed.

The amount of pressure used on the file is very important; too little will only scratch the metal, while too much will clog the file and also cause scratches. On the return stroke, do not let the file touch the metal; cutting should be done only on the “draw” stroke. In other words, with the file positioned at the most distant spot on the barrel, draw the file smoothly toward you using enough pressure to smooth the metal without scratching it. At the end of the stroke, lift the file from the metal and sort of arc it back to its starting position; then again use pressure and draw the file toward you. Repeat this procedure until all pits and scratches are removed.



After removing any old finish, and the pits or dings are dressed out to your satisfaction, you can start to polish the parts with 80-grit paper. The author suggests using the shoe-shine approach when polishing barrels or other parts with contoured surfaces.



When polishing metal in a lengthwise direction (above), fold the abrasive cloth in this fashion (below) for best results and control.

The barrel is now ready for cross polishing to remove the many “flats” that will be left after draw filing. With a pair of scissors or your bench knife, cut a strip of 80 grit abrasive paper about 1½″ wide (cut the long way) and polish with a shoe-shine motion. Your first few strokes will reveal the flats left by the draw filing. Continue this operation over the entire length of the barrel with the 80 grit paper until all of the flats disappear, and the barrel looks like it has just been “turned down” in a metal turning lathe. You may have to use several pieces of the abrasive paper to obtain this polished condition.

Cut a 1½″ strip of the 150 grit paper and fold it as shown below. With the open edges in the direction of the axis of the bore, commence polishing the barrel lengthwise. Continue polishing in this manner until all cross polishing marks from the previous operation are removed.

Those procedures are repeated alternately with each next finer grit until the final “draw” is completed with the 500 grit silicon wet and dry, i.e.: 80 grit—cross polish; 150 grit—draw polish; 240 grit—cross polish; 320 grit—draw polish; 400 grit—cross polish; 500 grit—draw polish. (With the silicon wet and dry paper, apply a drop of oil to the paper when polishing.) Insure that all polishing marks from the previous polishing are removed before proceeding to the next finer grade of paper.

Once the barrel is polished, the position of it in the vise is reversed, and the receiver is polished in a similar manner, but make certain that the newly polished areas are well protected from the vise jaws. Heavy leather padding offers good protection. Then continue with the trigger guard, trigger, floor plate and other parts. Most of the smaller parts, however, are most adaptable to cross polishing all the way because of their configuration, and not lengthwise polishing. Just make certain that all polishing marks from the previous grit size are completely removed before using a finer grit size. Protect all of the newly polished surfaces from rusting with a light coat of oil until you are ready to apply the bluing solution.

Screw heads are best polished by securing them in a screw holder, and then using a power buffing wheel (with different size grits) for polishing. If a buffing wheel is not available, insert the screw in the chuck of a! 4-inch drill motor (held in a vise) and while the screw is rotating, lightly run a fine file over the head to remove any dings or minor pits. Complete the polishing in this manner with the different grit sizes of abrasive paper. The gun is now ready for bluing.

Besides eye protection, the gunsmith should wear a filter mask when polishing off old blue or rust.



Screw heads are best polished by securing them in a screw holder and then using a power buffing wheel.



The polishing job on this reblued barrel still shows some buffing marks; however, some customers may not want, nor be willing to pay for, a blue job with a high degree of polish. It's all a matter of personal choice.



The "hot-water" and "slow-rust" methods of bluing are the only ways to blue old double barrel guns that have had their barrels and ribs joined by soft soldering.

In using this or any other method of bluing gun metal, it is very important that the metal be absolutely free of all grease, oil, foreign matter, etc. Furthermore, once the procedure starts, be careful not to touch any of the parts to be blued with your hands, or with anything that could transfer foreign matter to it, or you may have to start the procedure over. Many experts recommend wearing absolutely clean white gloves during the entire bluing operation, but I have found these to quickly collect dirt and grime during the carding operation and prefer to wear clean rubber gloves instead.

Once more, clean all parts to be blued with a solvent such as AWA 1-1-1. Wipe out the bore thoroughly, then coat the inside of the bore lightly with a heavy gun grease—a thin coat of RIG works well. Tap the wooden plugs tightly into each end of the barrel so that the bore is water tight and the heat of boiling water will not cause the air in the bore to expand and blow the plugs out. A piece of black iron stove pipe wire should be attached to each wooden plug and then both wires attached to a wooden hanger—a broom handle will do the trick— to suspend the barrel in the boiling water and to hang the barrel while applying the bluing solution. On the small parts such as screws, a small spool of No. 22 iron wire (available at any hardware store) will be adequate.

Fill each tank with enough water to completely cover all parts. To the cleaning tank, add a cleaning solution such as Brownells Dicro-Clean No. 909 according to instructions on the package, or conventional household lye (sodium hydroxide) in proportions of 2 tablespoons of lye per gallon of water. Either of these solutions will degrease the parts to be blued. Insert all parts into the tank and suspend them so that none touches the bottom of the tank. Bring the solution to a boil, and leave the parts in the boiling solution for about 15 minutes. After this, immediately transfer the parts into the tank containing the clean boiling water. Let the parts remain in the clear water for two minutes, then remove them and hang them up to dry and cool. At this point, the hands must never touch any portion of the metal which is to be blued. Also make certain that the clean boiling water is kept at a hard, rolling boil—nothing else will do.

When the parts are dry and cool, take a clean cotton swab, saturate it with the bluing solution, and squeeze out any excess solution from the swab. With long even strokes, and moderate pressure, swab the solution over all areas to be blued. Do not use an excessive amount of solution. After all areas have been covered, hang the parts in a damp, humid place for 24 hours to rust. I hang guns to be blued in this manner in my utility shower. Using a rubber drain stopper, I fill the shower base with about 2 inches of water and then suspend the gun parts across the top of the shower stall with a broom handle so the parts hang down inside the stall.

After 24 hours, one of the tanks is again filled with clean water and brought to a rolling boil. Then all of the rusted parts are returned to this tank to boil for about 15 minutes. After boiling, they are hung up to dry and cool, but before completely cool, all accumulated water droplets in contours, screw holes, etc. are blown away. When cool, all of the oxide covering (rust) is removed with new, clean (grease free) steel wool. For tight places, I use a clean stainless steel brush. This process is called "carding." This first carding may give you any color from a light gray to a light blue; it may be splotched, or it may be uniform. Don't let any of this bother you. Each succeeding pass will deepen the color and make it more uniform. When all parts are thoroughly carded with steel wool and the brush, repeat the application of the bluing solution; that is, boiling, applying the solution, rusting, boiling and carding as before.

The number of passes necessary to obtain the desired depth and uniformity of color will depend on the hardness of the metal. You may get by with as little as 3 passes on .22 caliber rim fire rifles, or it might require as many as 10 or 12 on nickel steel shotgun barrels, but let's say that the average will be 5 passes. After the metal reaches the depth of color desired, give the just-carded parts one more carding, this time with a steel wool pad saturated with an oil such as WD-40. Don't be afraid of wearing the bluing off with steel wool—it's so tough that you won't phase it with 00 steel wool.

When the job is completed, you'll agree that it was hard, meticulous, work, but if you did your part, you'll also agree there is no bluing job equal to this method.

10 – THE MULTI-PURPOSE MOTO-TOOL



The speed dial on the Dremel No. 380 Moto-Tool gives instant positive control from 5,000 to 25,000 rpm.

MOST gunsmiths would be lost without their Moto-Tool and the dozens of accessories and attachments that go with them. In fact, I would dare say that this is the most useful and the most used of any tool in the gunshop—with the possible exception of the screwdriver.

There are various sizes of the Moto-Tool, but mine happens to be the Dremel No. 380 variable speed Moto-Tool. The built-in variable speed control brings out the full versatility and workability of the Moto-Tool by matching motor speed to the job at hand. The speed dial on this unit gives instant, positive control from 5,000 to 25,000 rpm permitting more accurate, precise grinding on all materials from soft woods to the hardest steels and alloys. It incorporates a heavy-duty combination of ball and oil impregnated bronze bearings with a .9 amp motor.

The smallest Dremel tool is their No. 260. It's a compact, palm-size versatile tool that is at its best with light delicate work. The 270 is the middle size and the 280 is the largest. The 370 and the 380 are variable speed versions of the 270 and 280 models.

The best way to buy one of these Moto-Tools is in kit form. For a bit extra, you get a 34-piece accessory set consisting of a good universal assortment of most-used items at a big savings over purchasing them separately. Rather than describing all of the accessories and attachments available for this Moto-Tool, let's get right into the nitty-gritty of gun repair and put some of them to use.

Installing Shotgun Bead Sights

It may seem like a simple matter indeed to unscrew an old shotgun sight bead from the muzzle of the barrel and then, just as easy, screw in a bright new silver or gold one in its place. Not so! When you start shooting away, chances are the barrel is going to split or even be blown completely off if the threaded shank of the sight is allowed to protrude down into the bore. The result is almost as bad as if the barrel were tightly stuffed with cleaning patches.

The installation of a shotgun sight bead is certainly within the reach of almost any shotgun owner provided he has access to a few simple tools (the Moto-Tool being the handiest) and more important, follows certain procedures. I've never run across a shotgun bead that gave any problems when it was being removed; most unscrew easily. However, if you should run across a stubborn thread, don't hesitate to use a good penetrating oil like Liquid Wrench. Apply the lubricant as per the instructions on the container, wait about 15 minutes, and then try removing the sight with conventional pliers.

Should you accidentally wrench off the bead from the threaded shank, or if the bead is already off when you start the project—eliminating any gripping surface—the old threaded shank will have to be drilled out and a new thread tapped. You're probably going to have to drill and tap a new hole anyway because most shotgun sight beads come in two sizes, 3 x 56 and 6 x 48 and these seldom fit factory drilled sight threads... or at least this has been my experience. Out of 30 or 40 guns that have been in my shop this year for new bead installations, I'll bet not three out of the bunch had either a 3 x 56 or 6 x 48 thread.

When drilling, use short screw machine drills as long ones tend to wander. Also use a B-Square barrel sight drill jig if available. To use the jig, merely "square-up" the barrel under the drill bit, place the jig on the barrel and line up the jig hole and bushing with the sight hole in the barrel (or the spot where the hole is to be drilled if no hole exists). Tighten the jig clamp and you're ready to start drilling, without using a center punch and with no further measuring. Since you'll be using either #45 or #31 drill bits, the Moto-Tool can be used to drill the hole if you wish.

Tap the hole with hand taps of 3 or 4 flute— preferably with the use of a tap guide. The guide—available from Brownell's—is expensive but is well worth the price. It insures the tap is perfectly square with the hole to be threaded and works on contoured or flat surfaces. Use a special tapping compound such as Tap Magic. Do not use conventional cutting oil.

With the sight hole drilled, tapped, and cleaned, be sure to select a bead with the proper size thread. This may seem like a silly statement to make, but many persons have gotten the threads mixed up and tried to install a bead with the wrong size thread. In doing so, you'll end up with a jammed sight. Select one too small, and you have a sight that wobbles and will eventually work out or else protrude down into the bore.



Shotgun sight installers like the ones here are available from any of the gunsmith supply houses.



When the shotgun bead is installed, take a scribe hook and mark off the protruding portions of threaded shank— this mark will serve as the cut-off point and insure that the bead shank doesn't extend into the bore.



After the bead threads have been marked for cutting, you can remount the bead in a sight installer, secure the installer in a vise, and cut the thread to the desired length.



Here, the new bead has been properly trimmed and installed.

Once the proper sight has been selected (proper thread, finish, size, etc.) start the sight by hand or with a special shotgun sight installer as offered by a number of gunsmith supply houses. Run the threads to full depth, and then scribe a line on the shank threads where they are flush with the inside of the bore.

Remove the sight and cut the shank off at the scribed line. This is best accomplished with the Moto-Tool using a narrow emery wheel. These wheels work similarly to large industrial abrasive cutting discs and will slice through the threaded sight shank in seconds. This cut-off wheel will also find a lot of use in shaping new parts and truing up the slots in screws. Be sure to buy plenty. They're cheap and although tough, they do break frequently. While doing the cutting with the Moto-Tool and cut-off wheel, the sight may be held in the sight installer and the holder clamped in a small vise, for additional rigidity. The cut-off wheel will make a fast, smooth cut.

Once again, install the sight into the threaded hole. If you have the slightest amount of projection into the bore, remove the bead and smooth up the remaining shank with a small file or emery polishing wheel in the Moto-Tool. Reinstall the bead and finish up with a cloth polishing tip coated with 140 grit polishing compound until the shank is *exactly* flush with the contour of the bore. If you've done your final trimming properly, your inside-the-bore polishing will be a quick 2 or 3 second job and you won't damage the choke.

If the old screw comes out easily and you can find a sight that exactly fits the existing screw hole, then a new hole will not have to be drilled and tapped; the entire operation should not take longer than 15 minutes. If you have to drill and tap, the job may take another 10 or 15 minutes. If the procedures just given are followed, the job is easy and perfectly safe.

Polishing for Rebluing or Plating



Polishing hard-to-get-at areas like triggers and trigger guards is made easy through the use of a Moto-Tool.



With the sanding drum attached to the Moto-Tool, you can easily remove excess material on butt plates quite quickly and easily.

SERVICE CHARGES

The replacement grips on this revolver (prior to finishing and installation) were rough shaped with a Moto-Tool.

Any gunsmith that does rebluing or replating will find the small Moto-Tools with their cloth polishing wheels and tips indispensable for getting into tight places like trigger guards, triggers and similar irregular, close places. The cloth tips are impregnated with polishing grits— the same as you use on your regular buffing wheel. You also apply the abrasive on the tiny felt tips just about like you do on the larger wheels; that is, turn the motor on to about half speed (12,000 rpm), then turn it off and quickly push the felt tip against the abrasive, allowing it to stop the rotation of the Moto-Tool. This allows the wheel to fill with abrasive compound and prevents excessive throw-off. However, when performing this operation, as in polishing, remember to wear safety goggles or glasses. The tip traveling at 12,000 rpm can throw grit and sparks all over the place. I've been hit a few times in the face, and from the sting I got on the cheek, I'm sure eye damage would have occurred if it had hit my eyes.

When using the Moto-Tool to polish parts prior to bluing, you don't have to use very heavy pressure, just a light touch will usually do the job. Also, I've found that you get smoother results when you use the higher speeds; it also cuts more quickly into the old finish. Nicks and pits are also more easily removed when using a speed of around 25,000 rpm.

The sanding drums and discs that come in the 34-piece kit are also good for polishing metal— although the name leads one to believe that they are to be used only on wood. The sanding drums are useful on wood, but they will also cut and polish metal. The inside of a trigger guard is one place you will find them invaluable. The thin disc will allow you to reach into tiny cracks for polishing and smoothing. You will also find hundreds of other uses for these sanding wheels, discs and polishing tips. For example, for minor fitting of a butt plate—where only a very small amount of material needs to be removed—the sanding drum attachment is very useful. If the operator uses care, no taping of the finished stock is necessary. With the sanding drum rotating at high speed, excess material on the butt plate can be removed very rapidly and accurately in only a few minutes.

The hard rubber grips on the old Hopkins & Allen, .22 rimfire handgun shown here were rough-shaped entirely with the Dremel 380 tool using a sanding drum. A fine sanding disc (or drums) can be used for final finishing although these particular grips were finished by hand.

Need to de-burr a delicate piece of metal where it's necessary to constantly observe the part being polished? Again the Dremel tool comes in handy. A round polishing head can, for example, be used to remove burrs on small parts such as rimfire cartridge lifters or extractors. These and other jobs are performed easily with the Dremel tool as very little setup time is required, and the smallness of the tool gives the operator a special "feel" unobtainable with the larger power tools.



One accessory Dremel offers for the Moto-Tool is a handy drill press frame. It's most useful for small, delicate drilling jobs.



These dental burrs were obtained from a local dentist. They find many uses around my shop when used in conjunction with a Moto-Tool.



When drilling Springfield, Arisaka, Enfield (or similar) receivers for scope bases, the B-Square drill jig will accurately align mount-hole spacing.

There are also special attachments suitable for use with the Dremel tool that are available from other sources. Dental burrs or drills, for example, are excellent for cutting very tiny grooves in wood or steel and you can obtain all you want for nothing! A dentist must use only very sharp drills when working on teeth and must discard them when they become only slightly dull. Even the dull drills discarded are probably sharper than your average tool bit and these drills can be had for the asking. The next time you're at your dentist, ask him to save all the old burrs or drills. Believe me, they'll come in handy. The dental burrs I obtained from my own dentist would cut through screw steel like the steel was hot butter, yet they were supposed to be dull. I didn't have the proper size chuck collet to accept the ultra-small shank— although they are available from Dremel—so I merely wrapped one layer of electrical tape around the shank and they fit perfectly.

One application of dental burrs is cutting a new slot in a screw that had the screw head broken off. The most recent example was an F. I. Mauser that was brought into the shop with one of the scope base screws broken. Of course the screw could have been removed by drilling a $^{17}/_{64}$″ hole in the center of the broken screw and then using a screw extractor to remove the screw. Such extractors have left-hand spirals that grip the metal inside of the drilled hole and allow right-handed screws to be unthreaded without damaging the threads. This of course takes a certain amount of setup time, and since I was rushed this particular morning, I merely laid the rifle in a Decker gun vise and grabbed my Moto-Tool. I used a magnifying glass to examine the work as I cut a new screw slot in the top of the broken screw and then used the appropriate size screwdriver to back the damaged screw out.

One word of caution. This operation sounds simpler than it actually is. It takes a lot of patience to guide the tiny dental burr straight across the top of a broken screw, so I'd advise practicing on a few old screws first. Also make sure the hole is deep enough for the screwdriver blade to get a firm grip. If the slot is too shallow, you'll winch it off on the first try.

It is possible to make a template for cutting new screw slots and then use the Dremel router attachment. This will make the job easier. However, if you have to go to all this trouble, you might as well drill a hole in the broken screw and use a regular screw extractor.



Lathe set-up for bolt-face opening with the Dremel Moto-Tool; lathe dog holds plug, threaded to replace bolt sleeve; tailstock center in firing pin opening centers bolt body. Steady rest must be positioned between bolt lugs and extractor collar; back off tailstock and move toolpost held grinder into place.



Completed lathe set-up for opening bolt face, with variable-speed Moto-Tool grinder in tool-post; compound feed handles grinding depth; crossfeed controls amount of bolt face opening.

When using any power tool, it's a smart idea to securely tie the work piece down. This is especially true when working on larger assemblies, or, the entire gun as shown here.


In this instance a Moto-Tool is being used to polish off a burr on a rimfire cartridge lifter.

Polishing Odd Contours

Many polishing accessories are available for the Moto-Tool that will easily polish the short, small and shielded surfaces found on rifles and shotguns. The basic polishing accessories consist of felt polishing wheels (½″ and 1″ diameter); felt polishing tips (⅜″ diameter); a ⅞″ diameter polishing wheel impregnated with fine emery (ideal for polishing metals); a 1″ diameter cloth polishing wheel for polishing all metals and plastics; a polishing point impregnated with emery for polishing metals; and, No. 421 polishing compound to apply to polishing wheels and tips. Other felt bobs, both mandrel mounted and unmounted, are available for the Moto-Tool; (just specify ⅛″ mandrel) which can be sized and shaped as needed. All may be used to polish such surfaces as the inside of trigger guards, and the endless other contours impossible to reach adequately with the big conventional buffing wheels.

Wire and bristle brushes in various shapes and sizes are also available for use in the Moto-Tool and are excellent for removing rust and corrosion as well as polishing metal surfaces. The wire brushes are especially suited for carding hard-to-reach places when bluing guns by the hot-water method.

Notching Stocks for Bolt Handles

When altering a military bolt to allow a scope sight to be mounted on the action, the stock usually has to be notched to accept the lower-fitting bolt handle. These cuts can be made with the Moto-Tool using ¼″ x $^7/_{16}$″ rotary files of cone, ball, or tear-drop shape mounted on an ⅛″ shank.

To notch the stock, mount it securely in a vise with padded jaws or use a Decker gun vise. The action should be stripped with only the bolt body remaining and the assembly then placed in the stock. The bottom 30 degrees of the bolt handle should be coated with inletting black before the bolt is lowered, and pressed firmly against the stock several times to leave a dark print. Remove the action and bolt from the stock and start the grinding-inletting work. Take only small amounts of wood from the stock at a time before repositioning the action and bolt in the stock, and sharply lower the bolt onto the handle notch already started. Repeat these operations until the notch is deep enough, and of the correct fit so that the bolt will barely clear the wood as it bottoms against the metal of the action. There must be a slight clearance between the bolt handle and the wood, because if there isn't, the recoil of the firearm may cause the stock to crack or split at this area.

Router Attachment

An inexpensive router attachment is available for the Dremel Moto-Tool that easily mounts to the tool. It has a calibrated depth-control adjustment for precision routing and shaping. The edge guide can be quickly removed for free hand and surface routing. The fence adjusts from 0 to 3¾″.

You'll find many uses for the router attachment if you do much stock work. They're excellent for gouging, countersinking, and roughing-in stock fore-ends and other work on gun stocks, such as inletting shotgun or muzzle loading side locks.



The Moto-Tool is also capable of small (wood) routing jobs. The routing bits shown are just a sample of the available bits from Dremel.



In this case, a Dremel Moto-Tool router attachment is being used to inlet new side locks on this old, exposed-hammer shotgun.

11 – SOLDERING AND WELDING

PERSONS working on firearms will soon discover that they need equipment and a working knowledge to perform silver soldering and brazing— especially when working on some of the older firearms where parts are absolutely not available; or when you get into some of the more exotic conversions and alterations.

When using any form of heat on firearms, extreme caution must be used. Barrels, actions and other parts are subject to heavy stress when fired and all are heat treated when manufactured to withstand the pressure. Any application of heat on these areas can deteriorate the original hardness and can then render the firearm dangerous. The most critical area is around the chamber; that is, the barrel area in the immediate vicinity of the chamber, the action, and the bolt face. Therefore, a front sight ramp, for example, can be silver soldered with relative safety around the muzzle of a rifle, but heat applied farther back—like when welding on a new bolt handle—can mean trouble if certain precautions are not taken.

Soldering Equipment and Its Uses



Soldering irons have been used for decades to perform soft soldering on all types of metal.



This electric soldering gun may be used for small soft soldering jobs as well as removing dents from gunstocks when used in conjunction with a wet rag.

Soft soldering—generally with a lead-and-tin alloy— has very little use on firearms. The process requires as much skill and care as silver soldering; has much less strength than silver soldering; will contaminate hot bluing solutions quicker than silver solder; and is nearly as expensive as silver solder. The only advantage that I can see in soft soldering is that it requires less heat than silver solder and therefore can be controlled better in tight areas.

Soft soldering may be performed with soldering irons, electric soldering guns or a controlled gas flame such as the Bernz-O-Matic propane torch. Of these three heat sources, the Bernz-O-Matic torch will find the most use around the gunshop, not only for soldering, but for many other uses where a source of heat is required.

One use of the propane torch is for bluing small gun parts like screws and drift pins. This method is especially useful when replacing one screw or pin and not bluing the whole gun; or when using the hot-water method of bluing. It is extremely difficult to blue smaller parts by the hot-water method, and the oil-and-heat method is perfectly acceptable for small parts.

To blue small screws and pins, polish the parts as usual. Then dip the part in a container of oil (conventional gun oil will work fine). Heat the part until the oil is burned off and the part is a deep blue. Then quench in oil to cool. Repeat the process until the desired color is achieved.

When bluing small parts by the heat-and-dip method, first dip the parts to be blued into a container of conventional gun oil.



Heat the part until the oil is burned off and the part starts to turn a deep blue.

A propane torch is also useful when repairing dents in gunstocks with shellac sticks. These shellac sticks are available from Brownell's and come in an assortment of colors including white, ivory, transparent, medium walnut, light walnut, dark walnut, Circassian walnut and black.

The ideal tool for this work is a pallet knife. You can make one by taking an old table knife (preferably one with an insulated handle) and cutting the blade down to about 3 inches. Round off the end on your grinder and taper it slightly from the handle to the rounded end. Remove the burrs and polish the blade until you have a smooth, flexible tool.

Hold the knife in the flame of the propane torch until it's hot enough to melt the shellac when pressed against the end of the shellac stick. When a small quantity of melted shellac has formed on the end of the blade, immediately wipe it across the area to be repaired. This is best done by turning the blade so the melted shellac will be on the bottom of the blade and then, holding the knife at a 45° angle, draw it over the scratch, dent, tool mark, crack, etc. The motion should be quick yet gentle. If the first pass doesn't completely fill the defect, repeat.

When the shellac has thoroughly hardened, sand down to the level of the stock and finish in the same manner as you would for the wood itself. The shellac repair will have a glossy appearance and is best used on stocks with a glossy appearance. (A London oil finish will show the repairs more readily.)



Dimensions for making a pallet knife to use on stock repairs.



Hold the pallet knife in the flame of the propane torch (above) until it's hot enough to melt the shellac when pressed against the end of the shellac stick which can be seen to the left of the knife (below).

The gunsmith's first propane torch should be one like the Bernz-O-Matic. This brand was my first, and since it has served me so well, I haven't had any need to try another. When using this type of torch, light in the following manner:

1. Open valve ¼ turn.
2. After five seconds, close valve.
3. Light match, lighter, or spark lighter. When using the latter, open the valve 1 full turn and ignite ½-inch away from the nozzle.
4. Open valve slowly until pilot flame is lit.
5. For the hottest, most efficient flame, adjust the blue flame so that it is 1 to 1½ inches in length.

The lightweight steel cylinder of fuel has a self-sealing valve that pops shut when you thread off any burner unit to replace it with another. Extra cylinders may be stored indefinitely without any loss of fuel.

If you don't want to be bothered with changing the cylinders so often, a propane shop torch kit is offered by RIDGID. A unique design and construction of burner assembly and nozzle propels the propane/air mixture with a high-velocity whirling action to produce a very hot, pointed flame that actually encircles the work you are heating.

This torch is ideal for both soft and silver soldering jobs and provides a 2600-degree flame for brazing also, although it is not recommended for brass brazing. The assembly attaches to a tank of LP gas, available from your local bottle gas dealer. A 20-pound tank is recommended unless you anticipate moving the apparatus very much. Then a 10-pound tank should suffice.

The Bernz-O-Matic torch will find the most use around the average gunshop. Besides soldering, it can be used for bluing small parts, melting shellac sticks to make stock repairs, and a number of other jobs.

Silver Soldering

Experience is the greatest teacher when it comes to soldering, but there are a few guidelines that can be useful to the beginner. The main concern should be with the basic principles. In general, silver soldering is the process of uniting two pieces of metal by means of an alloy having a melting point of between 1000 degrees F. to 1150 degrees F. (depending upon the type of alloy used). When applying the silver solder, it should be spread evenly over the work to be joined, and when so applied, its holding strength is surprisingly high—25,000 PSI strength or more!

Of the various techniques available, the one known as "sweating" is the most value to the gunsmith. This process enables sight ramps to be soldered to barrels, ribs may be attached, even barrels of side-by-side and over-and-under shotguns are joined together by experts using this method of soldering. Broken parts may be repaired and many other jobs around the gunshop may be candidates for silver soldering.

The equipment needed for this operation is simple. You'll need only a propane torch, a file or scraper for cleaning the surfaces, suitable solder, a felt or woolen rag for wiping joints, and, some small clamps for holding the work. That's just about all that's needed. Just about, but not quite! One of the most common problems encountered by the beginner is making the solder stick to the surface. Chances are you're going to have the whole mess form into little shiny balls and roll everywhere except where you want it. To solve this problem, you'll need some type of soldering flux.

Dyna-Flux solder flux is available from Brownell's and promotes smooth, even solder flow that results in neat, professional looking and stronger solder joints. This type of flux is formulated with a special wetting agent that works through capillary action to assure total coverage of work surfaces. It is for use on practically all metals but aluminum. This flux is excellent for all soft solders and Brownell's Hi-Force 44 solder which contains 4% silver and 96% tin. More importantly, it shows no effects when immersed in hot bluing solutions.

For true silver soldering, AMCO 45 silver brazing flux is recommended. This is a creamy brush-on paste that will not separate, harden or crystallize. It wets the surfaces, removes oxides and prevents oxidation. The heat range is in the neighborhood of 850 to 1600 degrees F. It may be removed with warm water. Another problem is when the solder flows on surfaces where it is not wanted. A common talc crayon may be used on areas where the solder is not wanted. Merely rub the crayon around ramps, bases, etc., and the solder will not stick to any area rubbed with it. It washes off with soap and water or detergents.

Here's one method of soldering a front sight ramp on a rifle barrel. Position the ramp in its proper position on the rifle barrel and hold it firmly with a C-clamp. Double check the ramp for proper alignment, etc., and then mark around the lower edges of the ramp with a scriber. Remove the ramp, and polish the area within the scribed boundaries with a Moto-Tool using a polishing tip and 240 polishing compound. Tin the barrel within these scribed lines, and wipe off excess solder with a wool or felt rag. Then tin the underside of the sight ramp—again wiping excess solder away. The solder on both parts should be as thin as possible for greatest strength.

Again, locate the ramp on the top of the barrel, aligning it very carefully, and secure it by means of a small clamp. Heat the assembly (the barrel and the ramp) sufficiently to melt the solder and then let it cool. If the two areas were only lightly tinned with solder, the sight will be tight with very little run-out.

With a little practice, such ramps may be installed with little or no exposed solder showing. However, in some cases, there will be a little hairline of solder around the bottom edges of the sight base that you'll probably want to touch-up. Birchwood Casey has two types of solder blacks on the market. One is for. tin-lead solders and the other is especially for silver solder. The application of either requires no heat; they react with the solder for a long-lasting finish without damaging the surrounding finish. There is also no after rust or corrosion.


When soldering a front sight ramp on a barrel, first position the ramp in place and then secure it with a C-clamp.


Mark around the lower edges of the ramp with a scriber. Then remove the sight and polish the area within the scribed lines.


Once again secure the sight in place with a small clamp and then heat the area sufficiently to melt the solder.

BROWNELLS
HEAT STOP
HEAT CONTROL PASTE
BROWNELLS Inc
Brownell's Heat Stop acts as a heat sink when applied to metal surfaces.

Broken gun parts may be repaired by silver soldering in much the same way as described for installing the ramp. Clean both surfaces of the parts to be joined, but do not try to smooth them. Leave them just as they are; the irregularities will help align them and will add strength to the joint. Clamp the two pieces separately in a vise and apply the flux to the surfaces and carefully heat until the flux melts. Apply the silver solder to each piece and while it is still molten, wipe off the excess with a rag or soldering brush.

When both pieces are cool, clamp them together if possible, or clamp one piece in a vise while holding the other with pliers or tweezers. If the latter method is used, be sure to rest your hand or forearm on something solid so you'll be able to keep the parts perfectly steady and aligned. Apply just enough heat to melt the solder, then remove the torch and let cool. When the part is cool, scrape away any excess solder, clean the joint and finish. The job is done if you did your part. Should the part be out of alignment, reheat the part and reposition the parts for another try—it will only take about 5 minutes.

Under no circumstances should silver soldering or brazing be done on heat-treated parts unless certain precautions are taken and you are equipped to reharden the parts. For example, you should never heat the receiver ring of a bolt-action rifle which has its locking system within this area. Heat that is low enough so that the bluing shows no discoloration is usually considered safe, but anything above this temperature can be dangerous. Even when welding a bolt handle that is a good 4 inches away from the locking lugs, precautions must be taken. One method is to use wet rags to surround the bolt while the heat is being applied to keep the bolt cool. This will confine the heat to the part being welded and will not escape to the critical areas of the bolt; but, be sure to keep the rags wet at all times.

A heat control paste called HEAT STOP is offered by Brownell's that will absorb heat and prevent damage of adjacent parts during welding, brazing, heat-treating and soldering. This chemical acts as an antiflux when soldering, will not harm blued finishes and cleans off easily and completely. Although I've never tried it, the manufacturer claims that when this compound is applied to a steel bar, one end of the bar may be heated red hot while holding the other end in your bare hand! This is some heat control.

Even when silver soldering in less critical areas—like the front sight ramp—certain precautions must be taken. One is to apply the heat evenly over the barrel and not just to one spot. For example, when installing a front sight ramp to the muzzle end of the barrel, the barrel should be heated all around and not just on top where the ramp is to be soldered. If heat is applied only to the top of the barrel, the barrel could become warped.

Bolt Alterations

If you ever take a notion to install a telescopic sight on some of the older military rifles, chances are the angle of the bolt handle will have to be changed to clear the scope when the action is opened. In some cases, you might even want to alter the bolt handle when using iron sights, just for appearance sake.


A set of bolt-bending blocks come in handy when altering bolt handles.



These are the necessary steps for cutting and welding a bolt handle to lower its swing.

There are three basic ways to alter bolt handles. All require extreme heat that cannot be adequately supplied by propane torches. An arc or oxyacetylene welder must be used. Extreme care must be taken so as not to let too much heat reach and soften the critical locking lugs, the cocking sears, and the bolt body itself. As much of the heat as possible must be confined to the area of the bolt handle.

The first method is the use of bending blocks, like the ones shown. These are two-piece casts, hollowed or contoured on the inside to grip the bolt body securely while permitting the bolt handle to protrude from the blocks. These blocks are also designed to shield the bolt body from heat generated during welding. HEAT STOP placed in the block will accomplish this task as well as heat-dissipating aluminum construction of the blocks.

BOLT WELDING JIG


Brownell's bolt welding jig incorporates a protractor supplied with the kit so that the jig can be set for any desired angle or sweepback.


Notching the bolt handle is the simplest of all methods for lowering it to accept a telescopic sight.

To alter the bolt, heat is applied with the welding unit until the exposed handle glows cherry red or about 1400 degrees F. The handle may then be easily hammered or bent into the desired contour with a wrench or lever.

Cutting and welding the bolt is also very popular in gunshops. Before most bolts can be cut, however, they must be annealed by applying moderate heat to the handle only. Again, I recommend using HEAT STOP on the remaining portion of the bolt. Also be sure to remove all parts from the bolt such as safety, firing pin, screws, etc. A dull red or approximately 1000 degrees F. should be sufficient for most bolt handles. Once annealed, the bolt should be allowed to cool slowly; *never quench it in water* as this is likely to make the metal brittle.

As the diagrams show, the bolt is cut off with a hack saw about ¼″ from the bolt body. With the bolt handle off, it is now ready for rewelding or a new commercial bolt handle welded to the bolt handle stub. If the existing bolt handle is to be used, grind off portions of the handle as shown.

Aligning the altered bolt handle with the bolt handle stub can be a touchy situation. The best tool to use here is Brownell's bolt welding jig. This jig is unique in that it incorporates a protractor supplied with the kit so that you can set the jig for any desired angle or sweepback. It then locks the bolt handle into position against the stub ready for welding. When welding, again use the same precautions as you did for cutting the handle off; that is, wrap the bolt body with wet rags or else use HEAT STOP during the welding process.

The final method is the simplest of all. All you have to do is notch the bolt handle as shown (after annealing it as discussed earlier), apply HEAT STOP to the bolt body and position the entire bolt in a vise so that the handle may be tapped down and back with a metal hammer. Apply heat over the notch with your torch and when the metal glows bright red, tap the handle into the desired position. Then let it cool slowly.

After any of the above methods have been used, grind and polish the entire handle, devoting special attention to the altered area. The handle may be left bright and shiny or else blued by any of the methods described in Chapter 9.

12 - MINI-LATHES FOR GUN WORK

A FULL-SIZE metal lathe costs a lot of money and requires considerable floor space—not to mention the skill required on the part of the operator. Such a lathe does have a place in the gunshop for turning barrels, chambering barrel blanks for a specific cartridge, and threading barrels for installation in actions or receivers. But all of these operations can be "farmed" out until such time as the gunsmith feels such an investment is justified.

On the other hand, a miniature (but mighty) lathe is available and deserves consideration by anyone who does work on firearms. It's called the Unimat 3 and costs considerably less than the full-size models; however, it duplicates all of the more important functions of the larger varieties, except, of course, the capability of working full-length rifle barrels.

The Unimat 3 does have a few features of its own, and with the proper accessories, the gunsmith can perform such work as barrel turning for handguns, boring, threading, sanding and buffing, grinding, etc. It can also be set up as a miniature drill press and milling machine, and it requires little bench space—about 13 x 22 inches. When the time comes that you feel like you need a lathe, the Unimat deserves consideration for your first one. It's easy to learn on, and you'll get the feel of lathe work with only a comparatively small investment. Then, as the need arises, and business picks up, you may want to invest in a full-size lathe with, say, a 14″ swing and 36 inches between centers as described in Chapter 15 on full-size lathes. (Even if you already have a full-size lathe, you'll find many uses for the Unimat 3 on small gun-part work. It makes an excellent second lathe.)

The Unimat 3 and other metal working tools are manufactured in Austria by the Messrs. Maier & Co., but marketed in the U. S. by EMCO-LUX Corp. The Unimat comes ready to use, complete with motor, Jacobs chuck, centers, tool holder, cutting bit and other accessories. For the hobbyist or beginning professional, it is one of the handiest tools you can own, even if you have one of the larger lathes.

Naturally being of this small size, you cannot expect it to take off as much metal per whack as the larger lathes; it will take off as much, but it just takes more passes. Since a large percentage of lathe work in gunshops consists of machining small parts and accessories—such as firing pins, drift pins, etc. —the Unimat will shine in this type of work. Here are the basic specifications:

Distance between centers: 8″
Center height: 1.75″
Swing over bed: 3.6″
Travel of cross slide: 2.1″
Required space: 21.7″
New weight: 15.4 pounds
HEADSTOCK
Hole through spindle: 0.4″
Spindle nose: M 14 x 1
Spindle speeds: 6 (130, 200, 350, 560, 920 40000 rpm)
AUTOMATIC FEED GEAR
Longitudinal feed 0.0008″/rev.
TAILSTOCK
Barrel diameter: 0.7″
Tranverse of barrel: 0.9″
Drill chuck mounting: M 14 x 1
DRIVE UNIT
Ac/Dc motor: 95 watts
Motor speeds: 2100 to 3600 rpm
VERTICAL HEAD
Maximum working height: 5.5″
Drilling stroke: 1.0″
Spindle nose: M 14 x 1
THREADS
Metric: (0.5-1.5mm)
Inch: 16 (16 - 56tpi)



The small Unimat lathes have long been popular with gunsmiths. To the left is the new Unimat 3. Right is the Unimat being used to drill a center hole with the stock held in the lathe chuck and a drill secured in the tailstock spindle chuck.

The operations that the Unimat will perform within its limitations are governed only by the skill of the operator and his imagination. The following comments will give you some idea as to some of the uses you'll find for it around the gunshop. Set up as a lathe, the Unimat will machine firing pins, make gun screws, turn drift pins all day and do just about anything desired up to a length of 8″, which includes most pistol barrels.

Recently, a customer brought in a Raven .25 auto pistol with a broken firing pin to be repaired. Of course, a factory firing pin is available for nominal cost, but time was of the essence and the customer was willing to pay a premium price to have the gun repaired sooner than it would take to order a firing pin.

A small piece of round stock was found in my "junk" pile, and after measuring and marking the centers of each end, the piece was mounted in the 3-jaw chuck and turned at a speed of 560 rpm. A combination center drill and countersink was used for drilling the center holes with the drill secured in a Jacobs chuck screwed onto the tailstock spindle chuck and a center rest used to support the work.

When drilling center holes, much care should be exercised to prevent breaking off the point. Never crowd the drill and chances are you'll never experience a broken drill. However, if the point should break and become stuck in the work, heat the end of the shaft to a cherry red and allow it to cool slowly so that the drill point will be annealed and can be drilled out.



This center hole has been poorly drilled — it's too shallow and at an incorrect angle.



This center hole is also improperly done — it's drilled too deeply to fit the center.



Here's a correctly drilled and counter-sunk center hole—it fits the lathe center perfectly.

One of the most common causes of poor lathe work is incorrectly drilled center holes. For example the diagram shows a shallow center hole with incorrect angle and no clearance for the tip of the center point. Another diagram shows a center hole that has been drilled too deep, while a third diagram shows a correctly drilled and countersunk hole that fits the lathe center perfectly.





Roughing tools (diagram above) are used to remove large amounts of metal. In the photo to the right, a roughing tool is being used to turn a firing pin to approximate dimensions.



On the firing pin made by the author, the rough shape of the pin itself was marked on the workpiece with an outside thread cutting tool.



The parting tool shown in the diagram above is used for grooving, or simply parting a piece of metal. To the right is the firing pin — it has been parted at one end of the shaft.

Where the broken firing pin was concerned, the pin itself was used as a guide; that is, measurements were taken to apply to the new work. The pin point was, of course, broken and exact dimensions of this were unknown, but could be guessed at and then fitted perfectly by trial and error. The dimensions and rough shape of the firing pin were marked on the work piece with an outside thread cutting tool and then turned to approximate dimensions with a roughing tool.

At a point in the work where the firing pin began to take shape, a round nosed tool was used to smooth the surface and bring the work to final shape as shown. Then a parting-off tool was used to cut one end of the firing pin away from the shaft. Since the work was getting to the point of having only very thin metal to support the piece, one slight mistake could ruin the entire project. Therefore, the remaining work was then held only by the 3-jaw chuck around a part of the pin that had sufficient metal.

Once the pin was shaped (except for rounding the firing pin end), the pin was tried in the gun to see if the fit was okay; it fit perfectly. The only remaining work was to shape the firing pin nose and heat treat the part. When heat-treating parts such as these, I hold them with a wire. Pliers should not be used to hold such parts when heat treating as the pliers will conduct heat away from the parts and even heat will not be applied. The part was heated to a cherry red and then dipped (and allowed to cool) in conventional motor oil.





In the diagram above, a round-nose tool can be seen. To the right, that tool is being used to bring the firing pin into final smooth shape.

When the firing pin was completed, the author tried it in the Raven autoloader to see if the fit was precise.



Once the firing pin was completed, and the fit assured, the author hardened the pin by heat treating.

Missing gun screws are always a problem and occur in every gunshop. Many common fillister head screws can be modified or altered to serve in a gun mechanism such as turning the screw head to a smaller diameter, but the finished product does not always look right. The threads often get mashed up from being held in the 3-jaw chuck. The best way to replace missing screws (if manufactured replacements are not available) is to make your own on the Unimat 3 from cold-rolled steel.

If an existing screw is not available for reference, Brownell's book, *The Encyclopedia of Modern Firearms Parts and Assembly Vol. I*, contains detailed measurements in chart form of thousands of pins, screws, helical springs, etc., for many different guns. It is also good practice for the gunsmith to make sketches of each different part made and dimensioned for future reference should the part have to be duplicated. Whenever an unusual or rare gun comes into my shop for repair and the gun has to be dismantled, I try to make sketches of all parts and carefully take dimensions should the part ever have to be duplicated.

The procedure for making a screw on the Unimat 3 amounts to taking a piece of cold-rolled steel stock and securing it in the 3-jaw lathe chuck, allowing enough room to work the tool up to, and including, the screw head. Then the head and body are turned, and the end of the screw is chamfered with a 45-degree chamfering tool. Next, thread the screw body with the proper size stock and die. You can do this by hand, or hold the die up to the bolt and run the lathe at its slowest speed (130 rpm). The parting-off tool is then used to cut the screw head away from the steel stock.

At this point, some means of protecting the threads should be provided while rounding, slotting and polishing the screw head. With little difficulty a screw adapter can be turned on the Unimat from tool steel and then drilled and tapped and marked as to what thread it is for. A slot in the adapter comes in handy for removing the smaller screws. It is not absolutely necessary to cut a square end on the adapter, but by doing so, it may be held more positively between the vise jaws when the screw head is slotted.

The screw, fitted in the adapter, is then secured in the lathe chuck and the head rounded and polished. The adapter is then removed, secured in a bench vise, and the head slotted. A screw head slot can be cut with a standard hack saw, but a Starrett screw slotting blade can save much time. They fit any adjustable hack saw frame, eliminating time needed to set up a machine. Several thicknesses of teeth are available and they may also be used for undercutting inside corners and cutting flats on shafts for set screws.

Each blade is hardened throughout for maximum rigidity plus keen cutting edge. Straight milled teeth provide smooth cutting action and nice finish. Each blade tapers in thickness from cutting edge to back to prevent binding and allow quick, easy cutting.

Once the slot is cut, the head is polished again and blued in any conventional manner. If just one screw needs to be blued, the heat-and-oil-dip method described in Chapter 11 is the fastest.

These examples of the Unimat's use does not even skim the surface of those possible. The milling attachment, for example, will allow you to perform many useful milling jobs, some of which are discussed in Chapter 16 on milling machines. Drillings can be performed as discussed in Chapter 13 on the drill press.



If you’ve got a screw that has the proper threads, but the head is too large, you can turn the head down to proper dimensions in a Unimat.



Screw slotting hacksaw blades are available in a number of thicknesses. They are also handy for under cutting inside corners and cutting flats on shafts for set screws.

Accurate Measurements

When parts are turned or milled on the Unimat 3, certain measurements are necessary to obtain usable finished products. Careful and accurate measurements are also necessary in other areas of the gunsmithing profession and can be acquired only by practice and experience. All measurements should be made with an accurately graduated steel scale or a micrometer. Never use a cheap scale or a wood ruler, as they are likely to be inaccurate and may cause spoiled work.

An experienced gunsmith can take measurements with a steel scale and calipers to a surprising degree of accuracy. This is accomplished by developing a sensitive “caliper feel” and by carefully setting the calipers so that they split the line graduated on the scale.



The proper application of the outside caliper when measuring the diameter of a shaft is to hold the caliper exactly at right angles to the center line of the work. Push the caliper back and forth across the diameter of the cylinder to be measured. When adjusted properly, the caliper should easily slip over the shaft. Never force the caliper as you might deform it.



When setting an outside caliper, hold an accurate steel rule in the left hand while the right hand holds and adjusts the caliper to the desired measurement.



In this diagram, a caliper is being set for a definite dimension by placing the end of the scale against a flat surface while the ends of the caliper are respectively placed at the edge and at the point of the scale desired.

A good method for setting an outside caliper to a steel scale is to hold the scale in the left hand while the caliper is held against the end of the scale and supported by the finger of the left hand—adjustment is made with the thumb and first finger of the right hand.

The proper application of the outside caliper when measuring the diameter of a shaft is to hold the caliper exactly at right angles to the center line of the work and push it gently back and forth across the diameter of the cylinder to be measured. When the caliper is adjusted properly, it should easily slip over the shaft due to its own weight. Never force a caliper or it will deform the instrument and the measurement will not be accurate.

To set an inside caliper for a definite dimension, place the end of the scale against a flat surface and the end of the caliper at the edge and end of the scale. Hold the scale square with the flat surface. Adjust the other end of the caliper to the required dimension.

To measure an inside diameter, place the caliper in the hole as shown and raise your hand slowly. Adjust the caliper until it will slip into the hole with a very slight drag. In doing this be sure to hold the caliper square across the diameter of the hole.

In transferring measurement from an outside caliper to an inside caliper, the point of one leg of the inside caliper rests on a similar point of the outside caliper, as shown. Using this contact point as a pivot, move the inside caliper along the dotted line shown in the illustration, and adjust with the thumb screw until you feel your measurement is right.



To measure the inside diameter of any hollow or recessed object, place the caliper inside as shown and adjust it so it will slip in and out of the hole with a slight amount of drag.



In this diagram an inside caliper measurement is being transferred to an outside caliper.



Dial calipers (top) and a micrometer (bottom) are two measuring devices gunsmiths rely on daily.

How To Read A Micrometer

The main parts of the micrometer include the following:

A. Frame
B. Anvil
C. Spindle
D. Hub or barrel
E. Thimble

Micrometers measure either in inches or in millimeters. but for our purpose, those graduated in inches will be discussed. Each graduation on the micrometer barrel represents one turn of the spindle or 0.025 inch. Every fourth graduation is numbered and the figures represent tenths of an inch since 4 x 0.025 = 0.1000 inch or $^1/_{10}$ of an inch. The marks on the thimble are numbered 1 through 24 and the 25th mark is the return to 0. Usually, 0, 5, 10, 15 and 20 are in larger print.



This diagram provides you with a breakdown of the parts of an outside micrometer.

When the spindle of a 0″-l″ micrometer is in contact with the anvil, you will find that the 0 graduation of the thimble aligns with the 0 mark of the hub—meaning that there is no clearance between the spindle and the anvil.

The rotation of the thimble counterclockwise one complete turn will move the spindle .025″ away from the anvil, giving this amount (.025″) of clearance. Three more complete turns (4 total) will expose a “1” mark on the barrel which indicates .100″ or $^1/_{10}$ of an inch.

As each subsequent mark on the thimble passes the line of the barrel, one thousandth of one inch is added. Therefore, if the thimble is rotated to align the number 10 mark, ten one-thousandths are added to the exposed marks on the barrel. So, if we went to 10 on the thimble beyond .5, our measurement would be .510 as shown in the photograph below.



In the setting shown, this micrometer shows a reading of .510″.

The fit of the part being measured between the spindle and anvil should be snug—not too tight or too loose. Most micrometers are equipped with a ratchet stop to provide a measuring force. When applying the measuring force on the workpiece by the ratchet stop—

1. Bring the measuring face of the spindle just in contact with the workpiece resting on the anvil.
2. Stop feeding the spindle.
3. Turn the ratchet stop by 1.5 or 2 turns, which are made in 3 or 4 finger snaps.

The ratchet stop has a spiral spring and two gears engaging each other to provide specified measuring force. The gears may wear and the spring may weaken after long term use, resulting in unconstant or out-of-specified measuring force. Such a ratchet stop must be replaced with a new one.

A device for a constant measuring force other than the ratchet stop is a friction stop (friction thimble). The friction thimble has a device for a constant measuring force inside the thimble. The friction thimble will produce a constant measuring force irrespective of the operator’s practice of operation. It is recommended to use the friction thimble to ensure the highest measuring accuracy without human error.

In addition to the marks which denote .025″, .10″, etc., on the barrel, some micrometers also have ten other lines, numbered 0 to 10 that run the length of the barrel. This is a Vernier scale. These lines measure fractions of one thousandth. To illustrate its use, suppose that you were measuring the diameter of a bullet and the barrel reading was .35 and the thimble read somewhere between 7 and 8. If you wanted to know the exact measurement between 7 and 8, you’d use the Vernier scale.

To use the Vernier scale, look at the lines of the barrel numbered 0 to 10 and find the one line that aligns with one of the one-thousandth marks around the thimble. Only one of the ten lines on the barrel will align exactly with one of the lines on the thimble. The line on the barrel which aligns with a line around the thimble indicates how many tenths of one-thousandths are being measured. Therefore, in our example, if the “7” line on the barrel lined up exactly with one of the lines on the thimble, the bullet diameter would be .3577.

After using a micrometer, care for it as you would any other precision instrument. Clean it and apply anti-corrosives. Apply oil of high quality on the screws when assembling.



In addition to the marks which denote .025″, .10″, etc., on the barrel, some micrometers also have ten other lines (numbered 0 to 10) that run the length of the barrel. This is, in fact, a Vernier scale—the lines measure fractions in one thousandths of an inch.

13 – THE DRILL PRESS

Rockwell drill press has four speeds for drilling a variety of materials. It's adjustable 8½″ x 9″ table has slots and side ledges to facilitate work clamping.



For stationary tables, a tilting drill press vise may be used to tilt the work.

GUNSMITHS will frequently use drilling tools in their work. The drill may be a small ¼″ portable drill motor or a full-size drill press. Regardless of the type used, all have one thing in common—a spiral bit that rotates at a relatively high speed for drilling through wood, metal, plastic, etc.

The heart of a drill press is the spindle which rotates inside a hollow sleeve called the quill. A feed handle moves the spindle up and down for drilling. The chuck attached to the spindle is designed to grip a variety of twist drills (usually up to ½″ in diameter) and other accessories.

Drill press tables are designed to be moved up and down on a column to adjust the distance of the chuck from the work. Speeds on most drill presses range from about 700 to 4700 rpm. The lowest speeds are used for drilling metal and large holes in wood while the higher speeds are best for sanding, routing, shaping, etc.

Some drill presses are equipped with a tilting table that permits angle drilling. If the press is not equipped with such a table, a tilting drill press vise may be used to tilt the work. When drilling on an angle, it is very important that the work be securely clamped to the table, otherwise the work is likely to slide as the bit drills into the material.

The operator should never wear gloves when operating a drilling tool, especially while operating a drill press with the operator holding the object being drilled. Just a slight touch of a gloved hand to the rotating drill bit can entangle the glove material in the drill which can damage the fingers, even cut them completely off!

Another mistake often made when using a drill press is using one known to be defective; that is, one with a faulty switch, an improperly grounded frame, and the like. Here are a few precautions to follow when operating any power drilling tool:

1. Use a clamp or vise when drilling with a drill press. It is much safer than using your hands and it frees both hands to operate the tool.
2. Make sure the electric power cord does not become entangled in the drill bit.
3. Keep drill bits sharp. Dull tools cause rough cuts and excessive slipping.
4. Keep hands, clothing, key chains, etc. clear of all moving parts such as pulleys, belts, bits, and the like.
5. When drilling metal, safety glasses should be worn. Spiralled metal shavings, which can damage the eyes, often fly off from the bit.
6. Always turn the power off when the tool is not in use.
7. Watch the environment. Flammable gases and fumes can be ignited by the arcing electric motor. Never stand in water or on damp surfaces when operating any electric power tool.

Bolt Jewelling

One operation that gunsmiths normally use a drill press for is Damascening metal (often called jewelling or engine turning). This process involves overlapping spot-polish marks on metal that give a hammered effect. To perform this operation, you will need an engine turning chuck. This tool consists of a steel holder with a ⅛″ shank and an abrasive charged rubber tip. The specially made abrasive tip gives an even impression on steel and simplifies the work of engine turning and eliminates the danger of cutting deep rings.



Engine turning gives a hammered effect on metal surfaces: it's attractive, and to some degree, helps hold oil.



To perform jewelling or engine turning, you will need an engine turning chuck and abrasive tips. (Brownell's can supply both.)

Many shops use engine turning brushes rather than the tips. These brush wires follow the contours of the rounded gun parts better, giving a complete jeweled pattern. They are also reported to be superior on flat surfaces with long tool life. Silicon carbide abrasive and oil are used in conjunction with the wire brush to obtain the pattern. Drill press rpm should be fairly high; above 2000.

When performing engine turning designs on gun bolts, it is recommended that a specially designed fixture be used to hold the bolt (or other object) to be decorated. B-Square's bolt jewelling jig is an excellent tool and holds rifle bolts in position for symmetrically jeweled patterns. The bolt is secured between an arbor inserted into the rear of the bolt and a centering pin in the firing pin hole. The fixture containing the bolt is placed on a drill press table against a straight-edge fence and clamped to the table so that the bolt body is centered under the engine turning tool held in the drill chuck. Coat the bolt with abrasive compound and start the pattern. Start at either end of the bolt, but once started, start from this same end for all rows. Bring the engine turning tip or brush down on the bolt and make the first spot. Then move the fixture along the straight-edge fence approximately one-half the diameter of the spot and bring the brush down again on the bolt to over-lap the first spot. Continue this procedure until one row of spots is completed. Then the bolt is rotated approximately ½ spot diameter and the process repeated for another row. This continues until the entire bolt has been fully jeweled in the areas desired.



After one row of jeweled spots has been completed, you now turn the bolt approximately ½ spot diameter and repeat the process for another row.



The B-Square bolt jewelling jig (left) holds rifle bolts in position for symmetrically jeweled patterns. On the right, the jig and bolt have been secured to the drill press table.

The turning knob on the jewelling fixture utilizes an indexed scale to give additional visual checks as the jewelling progresses. The B-

Square Jewelling Jig comes complete with one small and one large wire brush, extension holder to clear bolt handle and a small sample can of polishing compound... enough to do several jewelling jobs on bolts, hammers, triggers, plates and other gun parts.

Drilling for Scope Mounting

When drilling or tapping an action for scope mounting, a sight jig is a great time-saving device that will greatly simplify the process. One of the best is manufactured by Forster Products of Lanark, Illinois. The use of this device makes drilling and tapping for scope mounts almost foolproof, provided the instructions are followed closely.

This fixture is especially suited for the accurate drilling and tapping of rifle actions and barrels for top mounts and target scope blocks, receiver sights, ramp sights and beads on single-barreled shotguns, as well as side mounts whenever the mounting holes are in line with the centerline of the barrel. The V-blocks align the gun by the barrel so that the drill guide and bushings are exactly centered with the bore. Even if the action is not exactly in line with the barrel, the fixture automatically corrects this error and drills the holes true with the barrel.

The amount of disassembly required to mount the gun in the fixture will depend upon the type of firearm. For example, it is not usually necessary to remove the trigger mechanism on bolt action firearms. The Savage Model 99 requires only the removal of the forearm; the Remington Model 760 requires the removal of the slide bolt as well as the bolt mechanism. Tubular magazine rifles must have the magazine tube removed prior to the drilling operation.


The Forster Universal sight mounting fixture is perfect for drilling and tapping barrels and receivers.


The barreled action is positioned in the fixture with the barrel resting on the V-blocks.


Next, raise the rear V-block up to bring the action in contact with the correct size drill bushing.


The diameter of the barrel is then measured at the points of contact at the front and rear V-blocks with a micrometer. Next, measure and adjust the front V-block to compensate for the smaller diameter of the barrel. Once level, use aluminum pads under the clamp screws as shown to avoid marring the barrel finish.


On bolt action rifles, raise the flat top support pad on the sight mounting fixture into firm contact with the flat bottom of the action.


When drilling for a ramp front sight, the barrel is positioned so that the muzzle is at the notched end of the fixture.

Once the gun is stripped as required, the barrel and action is positioned in the fixture with the barrel resting on the V-blocks; that is, with the action over the end of the fixture having the clearance slot. Whenever possible, the barrel to be drilled should be positioned so that the action is close to the rear V-block, with the cylindrical or straight portion of the barrel supported by the V-block.

Slide the overarm in place over that portion of the action to be drilled and raise the rear V-block up to bring the action in contact with the correct size drill bushing. Next, measure the diameter of the barrel with a micrometer at the points of contact at the front and rear of the V-blocks. As most rifle barrels are tapered it will be necessary to raise the front V-block so that the barreled action is perfectly level. To arrive at this exact difference in height, subtract the small diameter from the larger diameter (found by your micrometer measurements), multiply this value by 0.707 and raise the front V-block that much higher than the rear V-block. This can be done very satisfactorily by measuring the distance with a machinist's rule or, if extreme accuracy is desired, by means of a dial caliper or feeler gauges between the top of the machined boss and the bottom of the V-block. When you have ascertained that the barrel and action is perfectly level, clamp the barrel lightly, using the aluminum pads under the clamp screws to avoid marring the barrel.

On bolt actions, raise the flat top support pad into firm contact with the flat bottom of the action. This squares the action and acts as a support during the drilling operation. The clamp on top of the leveling block is used to hold the action when it is desirable to remove the clamp from the rear V-block so that the overarm may be moved over any part of the action. Now tighten the clamps.

Actions that have no flat bottom surface can be aligned by means of a square from either the top of the overarm or any other machined surface on the fixture. The gun also can be aligned by use of a level, but in this case be sure the fixture is level before lining up the gun.

One method used by many gunsmiths to locate mounts is to place the mount on the action or barrel in the desired position and mark the forward hole on the gun with a scriber or pencil. Next, with the locator pin point down in the front hole of the overarm, slide it over the gun so the point lines up with the mark and lock in place. Drill and tap this hole. Now screw the mount to the gun with one screw. Loosen the overarm and with the tapered point of the locator pin, locate the overarm over the second hole in the mount and lock in place. Lock the spacer block against the overarm. The overarm then can be moved out of the way, the mount removed and the overarm set against the spacer block. The second hole is then drilled and tapped. Other holes in the mount can be located and drilled in the same way. Do not drill the holes with the mount in place as they may prevent drilling the holes on the true center of the action.

When drilling for receiver sights, line up the barrel in the V-blocks in the usual way, but turn the action sideways and square it by means of a small square laid on top of the overarm. Locate the first hole and proceed as previously outlined. The same procedure is then followed when mounting side mounts, but holds true only if all holes are in line with the center line of the barrel.

If the desired holes are not on the center line of the barrel, the fixture can still be used to hold the gun squarely and steadily in the drill press. In this case the overarm is not used.

When drilling and tapping for a ramp sight, the gun is turned around, the muzzle end being at the notched end of the fixture. The V-blocks in this case are raised high enough so the drill bushings will contact the barrel. Allowance must be made for the taper in the barrel as previously explained. In this case, it will be necessary to square the gun with a level. Shotgun beads are mounted by following the same procedure.

Go easy at first and double-check your setups to be sure that you are drilling the holes exactly where you want them. Make sure also that the V-blocks align squarely, by tightening the screws gently at first so that the flat of the screw contacts the flat of the shaft squarely. A twisted V-block will throw you off due to the taper in the barrel, and especially so if the barrel is supported at a point where the taper is abrupt. Extreme care should be used to prevent chips from getting between the finished surfaces of the overarm and the body of the fixture when the overarm is moved. This is equally true of the spacer block. If chips are allowed to lodge between the two surfaces they will impair the inherent accuracy of the fixture. Brush away all chips with a small dry brush before loosening the overarm and spacer block. Also, don’t use too much force when tightening the screws holding the overarm and spacer block.

Forster Products also offers a labor-saving auger bit that will bore any arc of a circle leaving a true polished surface. It can be guided in any direction—so necessary in the inletting of gun stocks—without regard to grain of the wood or knots. The bit is guided by its circular rim instead of its center, which is the reason for its special adaptability in hard wood. This bit when used in a drill press will enable the gunsmith to do most of the inletting of stock blanks and save considerable time over the drill and chisel method.

General Procedures for Using the Drill Press

The following are guidelines for using the drill press on all types of work.

1. Select the correct kind of bit or drill and fasten it securely in the chuck.
2. Make sure the proper layout has been made and that the position of the hole is well marked.
3. Check to see if the drill or bit is free to go through the table opening in the drill-press table. Also, when drilling through wood, place an auxiliary piece of scrap wood under the material. This will help prevent splintering when the drill goes through the underside of the work.
4. Adjust the drill press for the correct speed of cutting. The speed should vary with the type of bit, the size, the kind of material and the depth of the hole. In general, the smaller the cutting tool and the softer the material, the higher the speed. Select the approximate speed and then use good judgment when feeding the tool into the material. If the tool smokes, reduce the speed and the feed.
5. Clamp the work securely when necessary, especially when using larger drilling and boring tools, hole cutters, and similar cutting devices. Clamping is a must if the tool has only one cutting edge, such as a hole cutter.

Drill Jigs



This B-Square scope jig is designed especially for military bolt action rifles.

B-Square offers several excellent drill jigs for mounting scope sights to various guns. One such jig is for the Winchester Model 94; but one of the most versatile—and probably the most used—is a scope drill jig designed for use on many types of military bolt action rifles.

To use a B-Square scope jig insert the bore aligning arbor into the rifle receiver placing both “V” bushings with their “V” over the arbor holes. Place the jig bar recesses (counterbores) on the “V” bushings and also place the base block against the bottom flat of the receiver and insert the alien screws. Before tightening the screws, slide the whole assembly forward until the jig bar stop pin contacts the rear of the front receiver ring. This locates the holes so that the scope mount recoil shoulder will bear against the ring, then place the drill bushing in the hole you want to drill.

The rear hole spacing in both bars will provide .504 (½-inch) spacing for both front and rear Weaver blocks. On some guns the forward Weaver block hole spacing is .860-inch center to center. Use the same hole spacing as for front Redfield holes.

To install Weaver blocks on the rear bridge of the Springfield A-3 rifle, use the Redfield bar marked “S.” This will locate the single hole required through the rifle dovetail. B-Square recommends that the rear hole in the front ring Weaver blocks be located using the Redfield spacing. This will enable Redfield or similar mounts to be installed later if desired by drilling additional rear holes only.

On Mauser type rifles the Weaver block must be filed or ground on its forward end to fit the rear bridge and clear the bolt handle. Clamp the whole unit in a large drill press vise or just hold the barrel and keep the base block flat on the table while drilling. A large base plate can be made to be attached to the base block existing threaded holes.

On all Japanese military rifles, install the base block with the narrowest “hole edge” distance forward. Also, remove triggers when drilling these rifles.

On Springfield A-3 rifles, slide the assembly rearward until the stop pin contacts the edge of the old rear sight dovetail. The scope mounts are located by this dovetail. The rear stop pin in Bar “S” is for this purpose.

On Mexican Mauser rifles check your scope mount before drilling. On most mounts, the recoil shoulder is such that the holes must be drilled .090 ($^3/_{32}$) farther forward than other Mausers. Press or drive the jig bar stop pin up so the bar can go forward the correct amount. (Check the jig location.)

On Argentine Mausers, be careful of a large radius on the rear of the front ring. If a large radius is on the ring of any rifle, press or drive the stop pin up so that it will contact the exact same spot as the mount recoil lug or the mount holes will be located too far to the rear.

On Mauser receivers be sure there is clearance between the “V” bushing and left-hand side of the receiver. On some Mausers, particularly a few small-ring models, it is possible that interference with the “V” bushing will deflect the jig. File or grind the “V” bushing side until it clears. (Be careful not to disturb the arbor contact area of the “V”)

On Springfield 03-A3 rifles the old rear sight dovetail is not centered on the receiver, nor are the serrations on top of the sight dovetail. Also the groove for the bolt, directly under the dovetail bridge, may not be on the vertical bore center line. Your jig should correctly locate the hole(s). Be careful on all holes, that the drill does not deflect and drill off the correct location.

Redfield (and other) recoil shoulders must contact the gun to prevent shearing off the mounting screws when firing heavy loads.



When starting any drilling job, it’s a joy to have a good selection of drill bits on hand. When you've finished drilling, return that bit to it’s proper place — you won’t have to search the next time!

14 – THE BENCH GRINDER

A BENCH grinder is essential in most gunshops— it's nice to have and useful for working on both metal and wood. Grinders are used to sharpen tools, drill bits and to maintain the use of several other tools used in gunsmithing work. They will also grind down metal surfaces rapidly and are excellent for such purposes prior to final finishing with a file or buffing wheel.



The bench grinder seen here is typical of those you'll find in many gunsmith shops. The unit shown is pulling double duty as the wheel on the left is of stitched muslin for polishing while the wheel on the right is for grinding.



The author suggests adjusting the distance between the grinding wheels and the work rests to maintain ⅛″ or less of separation before using.

Safety Precautions

Grinders, like all power tools, are potentially dangerous and certain precautions should always be taken when they are used. To illustrate, not too long ago I was carding down a double barrel shotgun during the hot-water bluing process. I had attached a piece of black stove pipe wire through one of the barrels for dipping them into the tank of boiling water. After applying the acid rusting compound to the metal and letting the rust build up, I would buff or card the rust off with a wire carding wheel attached to my bench grinder. Keeping the wires out of the way of the revolving wheel, I began carding the rust off and I was beginning to get a good blue-black color underneath when a person startled me as he poked his head through my shop door. I turned for an instant to see who he was and the next thing I knew the set of barrels went flying across the room, as I quickly jerked my hand out of the rubber glove that had become entangled in the mess of wires around the carding wheel. My right rubber glove had all four fingers cut off by the stove pipe wire that had wrapped tightly around the grinder shaft. Fortunately, my own fingers were intact—only one was slightly cut.

This incident taught me a very good lesson: never let anything that can become entangled in a revolving power tool come close to it—it's going to cause trouble. Furthermore, when using grinders, first make sure that the grinding wheels are not cracked; replace immediately if a cracked wheel is found. Always use guards and eyeshields on a grinding wheel, and do not over-tighten the wheel nuts. Use only approved flanges, preferably those furnished with the grinder.

Here are some other safety pointers to keep accidents to a minimum when using bench grinders.

1. Remove all adjusting keys and wrenches from the tool prior to use. Form a habit of checking to see that adjusting wrenches are removed from the tools before turning it on.
2. Keep work area clean. Cluttered areas and benches invite accidents.
3 Keep work area well lighted.
4. Don't force a grinder to work. It will do the job better and safer at the rate for which it was designed.
5. Wear proper apparel. Wear protective hair covering to contain long hair.
6. Use safety glasses. Also use face or dust mask if the cutting operation is dusty such as buffing or polishing gun metal.
7. Don't over reach. Keep proper footing and balance at all times.
8. Maintain tools with care. Follow the manufacturer's instructions for lubricating and changing accessories.
9. Always disconnect power tools before servicing.
10. Use proper voltage and connections for power tools and make sure that the tool is properly grounded as discussed later on in this chapter.
11. Keep hands in sight and clear of all moving parts.
12. Never leave power tools unattended. Turn power off just as soon as the job is finished.
13. Watch the environment. *Never stand in water or on damp surfaces when operating an electric power tool*. Be aware that explosive gases can be ignited by arcing electric motor.



Whenever you're operating electric tools, be sure those tools have a three-prong plug. The third plug serves to ground the tool you work with.



If your power tools don't have a three-prong plug, you can purchase the adapter shown at most any hardware store.

Grounding

All power tools operated by electric current and containing metal housings should be grounded during use to protect the operator from electric shock. Most 120-volt electric power tools are equipped with an Underwriters' Laboratories approved 3-conductor cord with a 3-prong grounding type plug to fit conventional grounding type receptacles. The green-covered wire in the cord should be the grounding wire. Never connect this green wire to a "live" terminal.

Adapters are available for connecting the 3-prong plugs to a 2-prong outlet. When using this type of adapter, the grounding terminal from the adapter must be connected to a permanent ground such as to a properly grounded outlet box. To insure that the outlet box is properly grounded, use a voltage tester, and connect one of the test leads to the "hot" (usually black wire) side of the outlet, and the other test lead to the box or cover screw. The meter should show a reading of between 110 and 120 volts. Repair or replace worn or damaged power cords and/or plugs immediately.

With these preliminary safety precautions out of the way (but not out of your mind) let's see some of the uses the bench grinder has in the gunsmith shop.

Sharpening Chisels and Gouges

Stockmakers know that their chisels and gouges must be kept sharp for them to do their best work. This consists of hand whetting, honing and stropping the tool for a keen edge. However, prior to these operations, a bench grinder can be used to grind a sharp cutting edge on the tool—saving much hand work. Frank Mittermeier offers a tool holder and stand for sharpening gouges, chisels and V-tools on the bench grinder, and enables the operator to get the proper bevel (cutting angle)— 12 to 15 degrees—whether they are straight or long spoon or backbend.

To set up the fixture (consisting of stand and tool holder), place it on the workbench with the convex curve of the cross bar approximately ¼″ from the grinding surface. A C-clamp may be used to firmly secure the fixture to the bench. Adjust height of the tool holder to about ½″ to ¾″ below the axis of the grinding wheel. For proper results, it is imperative to adjust the cross bar so that it is square with the grinding surface and level to the bench.

In grinding chisels and skews, the straight edge of the cross bar should face the operator. The tool holder should face the grinding surface from the flat side, and the tool should be placed in the holder as square and centered as possible. In the case of skew chisels, set them in the holder with the cutting edge parallel to the edge of the grinding surface.

When setting up V-tools and gouges, the curved side of the tool holder should face the grinding surface with the convex curve side of the cross bar facing the operator. All tools should be placed as square and centered as much as possible in the tool holder. Tools, depending on their size and shape, should extend approximately 2″ from the face of the tool holder to get a cutting bevel from 12 to 15 degrees. Constant back and forth motion should be exercised in the grinding of all tools to avoid overheating and loss of hardness. This movement will also result in a better sharpening job. To further prevent overheating, have a container of water nearby to dip the tools into as the sharpening process progresses. Most bench grinders have a water reservoir built in for this purpose. Curved cutting tools, such as gouges, should be moved over convex surfaces for uniform curves, concentric sharpening and for keeping an even bevel.

The grinding fixture, as shipped from Frank Mittermeier, is set for use on the left wheel of the grinder. Should the fixture be used on the right wheel, unscrew the cross bar and attach the crossbar's other end to the holder. The heavy part of the crossbar's convex curve should be at the lower front side when sharpening gouges.

Whetting, Honing and Stropping

After the proper bevel and sharp cutting edge have been ground on the grinding wheel, the carving tool has to be hand whetted, honed and stropped for a keen edge.

A carving tool should have two cutting bevels —outside and inside. The outside bevel should be ground on the grinder while the inside bevel must be hand whetted or honed. The amount of whetting to be done, depends on the sharpness of the cutting edge after grinding. In other words, if you do a good job on the grinding operation, less work is required during the whetting operation.

Chisels: Whet the 12- to 15-degree bevel in a circular, Figure "8" movement on a flat India oilstone until a fine burr (wire edge) has turned up. The other side of the stone—with the blade almost flat—should be rubbed on the oilstone until a short bevel can be noticed. Follow with honing the chisel by holding the tool in one hand and the Arkansas oilstone in the other hand. Rub the oilstone in an up and down movement with the pressure on the downstroke—against the cutting edge. Hone the large bevel first and then the small bevel. The bevels should be flat and the cutting edges square, so don't round the comers.

Straight Skew Chisel: This type of chisel should have a 12- to 15-degree angle on both sides, as the tool has to cut right and left in sharp corners. Whetting and honing is the same as on the chisel, except that both angles should be equal.

Gouges: The outside bevel can best be whetted by rocking it back and forth on the inside of an India gouge slip. For the inside bevel, use an India round edge slip and stroke the oilstone up and down until the bevel has been formed all around the curve of the tool. On gouges with the No. 9, 10 or 11 sweep, use a round or pointed oilstone to prevent rounding the corners of the tool. For honing, use a hard Arkansas round edge slip. The flat side of the stone should be used for the outside bevel and the rounded edge for the inside bevel. When honing, apply the pressure on the downstroke.

V or Parting Tool: After the outside bevels have been carefully ground to be alike, the bevels should be whetted until they form a burr at the inside of the V. To form the inside bevel use a diamond or knife shaped India oilstone. By grinding and whetting the outside bevel, a sharp edge is being produced where the two sides of the bevel meet, and a small protruding point will appear at the apex of the V. To prevent the tool from digging in and, for smoother pushing in the wood, the sharp edge should be rounded. The protruding point's outside corner has to be rounded until it conforms with the inner angle. For honing the outside bevels and for removing all traces of roughness at the rounded edge, use the round-edge slip. For the inside bevels use a diamond or knife shaped hard Arkansas oilstone. All honing is done against the cutting edge. When a burr has formed which cannot be easily removed by honing, draw the edge of the tool a few times across the corner of a woodblock or cork; that will remove the burr completely.

To prevent glazing of India and Arkansas oilstones, use a light oil mixed with kerosene. A few extra drops of the oil on the stone is better than letting the stone get dry. Clear the oilstone frequently to avoid accumulation of the black glazing (metal particles). All tools should be stropped before using. The tool is drawn across the strop with the cutting edge trailing to prevent the tool from cutting into the strop.

If you have trouble keeping the proper cutting angle on chisels and gouges during sharpening or honing, make a small box with one sideboard slightly higher to hold a flat oilstone. Lay the beveled side of the tool flat on the oilstone, hold the tool firmly in your hand with the index finger at the outside edge of the higher sideboard. By sliding the tool back and forth, you can keep the bevel at the same angle. Flat chisels, skew chisels and V-tools require only straight sliding. Gouges require a pendulum movement, so that the whole sweep of the tool is equally sharpened and honed.

How To Use a Mittermeier Grinding Fixture

The diagrams below show examples of using a Mittermeier grinding fixture. They are as follows:

1. Chisel, on the flat side of the tool holder.
2. Gouge, on the curved side of the tool holder.
3. Spoon chisel, with the cutting edge square to the grinding wheel.

4., 5., 6. A series of gouges in the different positions necessary to get uniform curve and bevel.



1



4



2



5



3



6



These diagrams show the proper sharpening angles for both chisels and gouges: A & B depict the proper angles for sharpening both sides of a chisel — about 12 to 15 degrees for diagram A, about 4 degrees for B. (C) & (D) The use of an India gouge slip (C) on the outside edges of a gouge; the same slip being used on the inside edges (D). Diagram E shows the final honing of the gouge with a hard Arkansas stone. Diagrams F, G & H depict the sharpening of "V" or "Parting" tools as discussed by the author.



If you have difficulty keeping the correct cutting angle on any chisel or gouge during the sharpening or honing processes, you might want to construct a small wooden box to hold the stone. The high sideboard gives you a constant angle for sharpening.

Drill Pointing

Elimination of drill breakage depends to a great extent on the correct point of the drill bit. When the drill is worn down by use, it must be reground or breakage will result. Here is another use for the bench grinder in the gunsmith's shop.

Not only must a drill be reground in time, but it must be properly ground to assure maximum drilling life. It has been estimated that 90% of all drill breakage is caused by incorrect regrinding, and for this reason, too much emphasis cannot be laid on the importance of this operation.

Point-grinding by hand requires great skill and care on the part of the operator, and therefore, a bit grinding attachment is recommended. The grinding attachment locks the drill bit at the proper angle for sharpening and makes the otherwise difficult operation quite simple. Also, if the drill is accidentally allowed to get too hot during the grinding operation, it should never be cooled off in water, but allowed to cool of its own accord. A sudden cooling is almost sure to result in a cracked drill.

When re-pointing a drill, four things must be carefully considered: lip-clearance, point-angle, cutting edges, point-thinning.



The point angles of this drill bit are ground equally but the chisel point is off center.



These are the proper angles for drill lip clearance and a chisel edge.

Lip-clearance: The lip-clearance is one of the most important features of the drill point. The angle of lip-clearance should be within 12 to 15 degrees, measured at the circumference of the drill. If the angle is greater, it weakens the cutting edge; if smaller, there is not sufficient clearance to allow the cutting lip to enter the work. The usual result is that the drill splits up the center.

Point-angle: The angle of a drill point is measured on the axis of the drill. The proper point-angle of a drill depends upon the material being drilled. However, all standard drills are furnished with 59-degree points, as this angle has proven to be the most suitable for the average class of work. In general, the harder the material the greater the point-angle should be. For example, a point-angle of 75 degrees is recommended for manganese steel, while for wood, fiber and similar materials, a point-angle of 30 degrees is recommended.

Cutting Edges: The two cutting edges of a drill must make exactly the same angle with the center line of the drill; that is, while the 59-degree angle may vary a little one way or the other, the variation must be uniform in both cutting edges. A difference in angle will cause one edge to cut differently from the other, causing an unequal strain on the two edges.

If the cutting edges are of unequal length, the chisel-point will be off-center and will cause the drill to cut oversize. If the point-angle is changed from 59 degrees, as originally made, it will be found that, due to this change, the cutting edges are no longer straight but have become either convex or concave. If the point-angle is changed appreciably, it may be necessary to grind the flutes of the drill in order to produce straight cutting edges.

Point-Thinning: The web of a drill increases in thickness toward the shank and a web-thinning operation becomes necessary when the drill has been shortened by repeated grindings. This operation is essential to minimize the pressure required to make the drill penetrate. The point-thinning operation must be carried out equally on both sides of the web, otherwise the web will be off-center and the drill will produce an oversize hole. Care must also be taken to see that the thinning operation is not carried too far up the web, thus weakening the point of approximately ⅛ of the drill diameter.

Grinding Wheels

A soft, medium grain wheel, approximately 8″ x 2″, should be used for sharpening drills. Drills should be ground on the face and not on the side of the wheels, although this is sometimes practiced in gunshops. The face of the wheel should be trued by proper dressing before drills are ground, otherwise correct results cannot be obtained. A grinding wheel dresser is the simplest, surest and most practical way to restore a true flat face on a grinding wheel. This tool will even level out gouges and grooves and also clean out loading from grinding soft metals.

The drill should be held at an approximate angle of 45 degrees to the vertical and all point grinding must be dry. If during the grinding, the drill is accidentally allowed to get too hot, allow it to cool of its own accord. If the drill has been re pointed, it should be examined to make sure that the margin shows no sign of wear, particularly at the extreme corners of the drill point.



A grinding wheel dresser is the simplest way to restore a true flat surface to a grinding wheel.





When regrinding a drill bit (above), it should be held at an approximate angle of 45 degrees to the vertical (Right) All point grinding must be dry. If the drill gets too hot during grinding, set it aside and let it cool on its own.

Cut-Off Wheels

Cut-off wheels may be secured in a bench grinder and are useful in gunshops for fast and easy completion of all sorts of cutting jobs. Most are manufactured in sizes from 2″ to 6″ diameter. The part being cut, however, must not be clamped rigidly for the cut. Rather, the part should be hand-held. Such a tool is useful for cutting such items as drift pins from a single rod and similar applications. High tensile strength man-made textiles reinforce these wheels to resist breakage under twisting pressures and impact. Obtain Brownells catalog for description and prices.

15 – LATHES FOR METAL WORK

THE SCREW cutting engine lathe is the oldest and most important of machine tools and, from it, practically all other machine tools have been developed. They vary in size from the small jeweler's lathes for making very fine, miniature parts to the large gap-bed lathes and special-purpose lathes used in high-production work. In between these extremes are many models of varying lengths and capacities. You must select the size that best suits your needs. The maximum size of work that can be handled by the lathe is used to designate the size of the lathe; that is, the diameter and length of the work. For example, a 10″ x 36″ lathe is one having a swing over the bed sufficient to take work up to 10 inches in diameter and having a bed length or distance between centers of 36 inches.

When selecting a lathe for gunsmithing work, the most important point to consider is the size and amount of work that you anticipate doing. The lathe should be large enough to accommodate the various classes of work that will be handled. This is determined by the greatest diameter and length of work that will be machined in the lathe. Ideally, the lathe selected should have a swing capacity and distance between centers at least 10% greater than the largest job that will be handled.

There are, of course, further considerations that everyone should take into account before purchasing a lathe. For example, if you lack experience at operating a lathe and you don't anticipate very many conversion jobs, then you could probably get by very nicely with the Unimat 3. The small parts such as firing pins, drift pins, screws and the like can be easily turned on the small, inexpensive Unimat.

On the other hand, if you are an experienced machinist and plan to do a lot of conversion work which requires barrel turning, bolt facing, chambering and threading of barrels, then you will need a larger lathe like the Jet Model 1236p bench lathe. This lathe is manufactured by JET Equipment & Tools and is an excellent choice for the average gunsmith doing conversion work and other gunshop machine work. The only change that I would like to see on this lathe is a slightly larger hole in the headstock spindle to insure that rough barrel blanks and shotgun barrels can be held close to the chuck face for chambering, sleeving and the like.

Each type of lathe has its advantages and disadvantages, and the final decision to purchase one should be made only after the gunsmith has thoroughly and truthfully analyzed his abilities, anticipated specialty, and most probably future desires. Then he should write for and study all the lathe manufacturer catalogs available or, better yet, visit some dealers close by. Then, and only then, would I recommend buying a lathe. When you shell out thousands of dollars for a lathe these days, you certainly want one that will best suit your current and future needs.

The lathe is the oldest of the machine tools, and they vary in size. Only the gunsmith can determine the type and size of lathe best suited for his needs.



Depending upon your experience and needs, one of the smaller lathes, like the Unimat, might serve your needs adequately. However, if you are an experienced machinist and plan on doing barrel turning, chambering, etc., the Jet Model 1236p shown would serve you better.

Parts of a Lathe

A lathe is made up of many parts. The principle parts include: bed, headstock, tailstock, carriage, feed mechanism, thread-cutting mechanism.

Bed: The lathe bed is the foundation on which the lathe is built, so it must be substantially constructed and scientifically designed. Prismatic V-ways have been found to be the most accurate and serviceable type of ways for lathe beds and have been adopted by most of the leading machine-tool manufacturers. The two outer V-ways guide the lathe carriage, while the inner V-ways and flat way align the headstock and tailstock.

Headstock: The headstock is the most important unit of the lathe and should be back-geared. The back gears provide a means of controlling the spindle speed. A back gear lever engages the back gear for slow spindle speeds (75 to 280 rpm) or disengages back gear for high spindle speeds (295 to 1100 rpm).

Tailstock: The tailstock assembly is movable on the bed ways, and carries the tailstock spindle. The tailstock spindle has a standard Morse taper at the front end to receive a dead center. The tailstock handwheel is at the other end to give longitudinal movement when mounting the workpiece between centers.

Carriage: The lathe carriage includes the apron, saddle, compound rest and tool post. Since the carriage supports the cutting tool and controls its action, it is one of the most important units of the lathe.

Feed Mechanism: Quick change gear lathes are preferred in gunshops where frequent changes of threads and feeds are required. On most lathes, the quick-change gear box is located directly below the headstock on the front of the lathe bed. A wide range of feeds and threads per inch may be selected by positioning the gears. The index plate is an index to the lever settings required to position the gears for the different feeds and numbers of threads per inch. The distance, in thousandths of an inch, that the carriage will move per revolution of the spindle is given in each block for the corresponding gear setting.

The reversing lever is used to reverse the direction of rotation of the screw for chasing right- or left-hand threads, and for reversing the direction of feed of the carriage assembly. Levers on the quick-change gear box should never be forced into position.



The machinist is adjusting the headstock on this lathe — the tailstock is to the left. The workpiece is in the machinist's right hand.

Installation

One of the most important ways to ensure maximum performance from your new lathe is to ensure that it is properly cleaned and accurately installed before use. Before starting a new lathe, the operator should carefully study the action of the various parts and become thoroughly familiar with the operation of all control levers and knobs.

Do not operate the lathe under power until it is properly set up and leveled. Also make sure that all bearings have been oiled and that the belt tension, between the motor and the lathe pulley, is correct. Always give the lathe pulley a twist by hand to make sure the lathe runs freely before starting a lathe under power.

In order to machine metal accurately and efficiently, it is necessary to have the correct type of lathe tool with a sharp, well-supported cutting edge (ground for the particular kind of metal being machined) and set at the correct height. Highspeed steel cutter bits mounted in forged steel holders are the most popular type of lathe tools.



These are some of the common cutting tools used on a lathe. From left: cutter bit for rough turning; side tool; planing tool; parting-off tool and thread-cutting tool.



Knurling is a metal-displacement process normally applied to metal with the lathe. The pattern of the knurl is the same on all three examples shown; however, the grade of the knurl is not. From left: coarse, medium and fine knurling.

The cutting tools shown are the most common in use. Each has a specific purpose and the descriptions to follow give the application of each.

Cutter Bit for Rough Turning: Used for removing a large amount of material in a short time.

Side Tools: Used for longitudinal and transverse turning and for turning acute corners.

Planing Tool: Used to obtain a smooth transverse surface.

Parting-Off-Tool: Used for grooving and parting-off workpieces. In using this type of bit, the tool bit point must be mounted to the exact center height and the slowest speeds must be used. Also use lubrication.

Thread-Cutting Tool: Used for cutting screw threads. When using this type of cutter bit to cut screw threads, always keep the work flooded with oil in order to obtain a smooth thread. Machine oil may be used, but lard oil is better.

Inside Boring Tool (not shown): Used for turning inside work.

Special Lathe Work and Tools

There are also classes of work involved in gunsmithing that require special tools, the most important of which are described below.

Knurling

Knurling is the process of embossing the surface of a piece of work in the lathe with a knurling tool secured in the tool post of the lathe. The pattern of the knurl is the same as in the examples shown, but is of different grades—coarse, medium and fine.

For all knurling operations, the lathe should be arranged for the slowest back-geared speed. After starting the lathe, force the knurling tool slowly into the work at the right end until the knurl reaches a depth of about $^1/_{64}$ of an inch. Then engage the longitudinal feed of the carriage and let the knurling tool feed across the face of the work. Plenty of oil should be used on the work during this operation.

When the left end of the knurl roller has reached the end of the work, reverse the lathe spindle and let the knurling tool feed back to the starting point. Do not remove the knurling tool from the impression but force it into the work another $^1/_{64}$ of an inch, and let it feed back across the face of the work. Repeat this operation until the knurling is finished.

Filing and Polishing

All tool marks can be removed from metal gun parts, such as rifle barrels, and a smooth, bright finish obtained on the surface by filing and polishing. Use a fine mill file and file with the lathe running at a speed so that the work will make two or three revolutions for each stroke of the file. File just enough to obtain a smooth surface. If too much filing is done, the work will be uneven and inaccurate.

Keep the left elbow high and the sleeves tightly rolled up so there will be no danger from being dragged into the headstock or workpiece as it revolves. Also keep the file clean and free from chips; use a file card frequently.

Once the filing has been completed, a very smooth, bright finish may be obtained by polishing the work with several grades of emery cloth. Use oil on the emery cloth and run the lathe at high speed. Be careful not to let the emery cloth wrap around the revolving work.

Lapping

Certain hardened gun parts are often finished in the lathe by lapping. Emery cloth, emery dust and oil, diamond dust and other abrasives are used. Usually the lathe spindle is operated at high speed.

The lap may be very simple—consisting of a strip of emery cloth attached to a shaft—or it may be elaborately constructed of lead, copper, etc. Some very fine and precise work may be accomplished by careful lapping.

Spring Winding

Coil springs of all kinds may be wound on the lathe. Special mandrels are used for irregularly shaped springs. The lead screw and half nuts of the lathe are usually used to obtain a uniform lead so that the coils are all equally spaced.

The Use of the Center Rest

The center rest is used for turning long shafts like gun barrels and for boring and threading spindles. To mount work in the center rest, first place the center rest on the lathe, then place the work between centers, slide the center rest to its proper position, and adjust the jaws upon the work. Careful adjustment is required because the work must revolve in these jaws. When the jaws are adjusted properly so that the work revolves freely, clamp the jaws in position, fasten the work to the head spindle of the lathe and slide the tailstock out of the way. One end of the work may be held in a chuck, but for fine accurate work, the chuck should not be used. Rather, work should be mounted on centers, using a lathe dog.



This is an end view of a lathe's center rest; it's used to center and hold long shafts of metal (gun barrels) or boring or threading spindles.



In this diagram the workpiece is being held in place by a 3-jaw scroll chuck secured to the headstock.



This is an example of a workpiece mounted on its centers using a "lathe dog" and a wet leather thong. The face of the head spindle plate is unscrewed from the shoulder about three or four turns and the work tied securely to the face plate with several heavy, wet leather thongs. The face plate is then screwed onto the spindle which tightens the lacing and holds the workpiece firmly.

The Use of the Follower Rest

The follower rest is attached to the saddle of the lathe to support work of small diameter that is liable to spring away from the cutting tool. The adjustable jaws of the follower rest bear directly on the finished diameter of the work. As the tool feeds along the work, the follower rest (being attached to the saddle) travels with the tool.



The adjustable jaws of the follower rest are bearing directly on the finished diameter of the work.

Manufacturing Duplicate Parts in the Lathe

The modern back-geared screw cutting lathe can be fitted with rapid production attachments and used to advantage on many manufacturing operations. The accuracy of the lathe combined with the efficiency of the special attachments make it ideal for production work requiring special accuracy.

When the lathe is equipped with special tools, it serves as a special machine. Then when the job is finished, the special tools can be removed and the lathe used for regular work. I'd recommend writing to the larger lathe manufacturers stating your specific needs. They will be able to tell you of the availability of such special attachments and also make a cost quotation.

Milling in the Lathe

A milling and keyway cutting attachment will take care of a great deal of milling in the gunshop that does not have enough work to warrant the installation of a milling machine. The cut is controlled by the hand wheel of the lathe carriage, with the cross feed screw of the lathe and the vertical adjusting screw at the top of the milling attachment. All milling cuts should generally be taken with the rotation of the cutter against the direction of the feed.



Generally, milling cuts should be taken with rotation of the cutter running against the direction of the feed. However, when removing large amounts of metal — rough cutting — the feed and direction of the cutter are, perhaps, best set up identically as shown here. Cutter type, direction of rotation and speed are all dependent upon the job at hand.



The milling and keyway cutting attachment will take care of a great deal of milling in the gunshop that does not have enough work to warrant the installation of a milling machine.

The Lathe in the Gunshop

The back-geared, screw cutting lathe is frequently called the "universal tool," and this applies in gun repair work as well as in the industry in general. Most of the parts used in firearm mechanisms, and especially the barrel, bolt, etc., were originally made on lathes or in special machines which are adaptations of the lathe.

A lathe with 9″ or 11″ swing is very practical for handling such jobs as threading rifle barrels; chambering barrel blanks for a specific cartridge; turning barrels to contour, and a host of other operations. Special attachments used on the lathe greatly increase its versatility.

One of the operations commonly done in a lathe is turning down rifle barrels. This is especially true of certain military rifle barrels that are going through the process of being sporterized. The original barrels are often rough, ugly, uneven. Such a barrel may be placed in a lathe and turned smooth if the work is done carefully.

Put the breech end of the barrel in the chuck or live center, attach a lathe dog to the barrel, and tighten up the faceplate with dog and rawhide belt lacing as discussed previously. When the barrel is running true in the lathe, turn, use a second-cut flat file or a mill file and smooth the rough portion of the barrel. The file should be moved at right angles to the axis of the barrel, and with light uniform pressure. Then finish up with a very fine file.

When a barrel must be turned down to obtain a lighter-weight barrel, warping sometimes occurs as the strains are released during the removal of metal. This is especially true of old military rifle barrels. On the other hand, modern steel barrels have little tendency to warp even when large amounts of metal are removed.

To turn a barrel in the lathe, make certain that the barrel is turned concentric with the bore if it is to be held in the three-jaw chuck. A muzzle plug must be made for the tailstock, which should fit the bore at the muzzle as closely as possible—without binding. A round-nose (finishing) cutting tool should be used, and only a small amount of metal should be removed on each pass.

Pressure caused by the cutting tool, heat from friction, etc., is going to cause the barrel to expand during the turning operation, so be sure to compensate for this expansion by adjusting the tailstock frequently; that is, relieve the pressure so that the barrel does not spring or bow.

Cutting and Crowning Barrels

The best way to cut and crown rifle barrels is to use the lathe. This way, you reduce a time-consuming operation (when done by hand) to only a few minutes of easy work. Secure the barrel in the lathe by the methods described previously and make certain that the bore is concentric with the outside of the barrel. Then using a cut-off tool, and the lathe running at low speed, cut the barrel at the desired location. (Be sure to use plenty of cutting oil during this process.) Once cut, the barrel may then be trued with the right-hand side tool, feeding it outward from the center. The tool, of course, must be sharp and ground to an angle of 58 degrees to prevent interference with the tailstock center. You should be careful not to bump the end of the tool against the lathe center, as this will break off the point.

Once the barrel is cut and trued, a special crowning bit may be used in the tool holder to form the correct curvature on the muzzle. A barrel crowning lathe bit may be purchased from Brownell's. They are professionally ground to give maximum cutter strength and proper clearance as the cutter tip enters the bore and the shank approaches the barrel. By taking careful cuts and moving the table back and forth, any degree of crown shape can be cut. The cutter should be placed in the tool holder and drawn straight toward the barrel to cut the rounded profile desired. Then a round brass ball may be used in a hand grinding tool to add the finishing touches. (The ball should be coated with abrasive powder and oil such as Clover abrasive compound.)



When crowning a barrel, the muzzle (left) is trued up — cut square — and then, using a right-hand side tool, the muzzle is trued by feeding the tool outward from the center as shown. Once the barrel is cut and trued, a special crowning bit (below) — available from Brownells — may be used in the tool holder to form the correct curvature on the muzzle.



After the curvature has been properly formed on the muzzle, a round brass ball is coated with abrasive powder and oil — Clover Brand compound works perfectly for this job — and worked against the muzzle with a hand grinding tool. This puts the finishing touches on a proper crowning job.

Chambering Rifle Barrels

Chambering rifle barrel blanks for a specific cartridge or rechambering a barrel for a new cartridge goes hand in hand with barrel threading and headspace, and all three operations will be discussed here.

In general, chambering consists of reaming out the breech of a barrel with chambering reamers forming the exact chamber dimensions into which the cartridge fits. The body of the reamer is sharpened by grinding and honing the face of the flutes. Repeated grinding, however, will eventually cause the reamer to become undersize, but a lot of metal can be cut before this happens if care is exercised in storing, grinding and using the reamers.

A roughing reamer is used only to rough out chambers, and therefore, no attempt is made with these reamers to carry out the exact form of the chamber. They have a solid pilot and are usually made with four flutes. The leads are backed up with plenty of metal to give strength so that they can really hog out metal during the chambering operation. Reamers may be used by hand with extension handles, but are usually used in lathes for convenience and speed. When using the lathe, the barrel is secured in the lathe chuck and the reamer is forced into the bore, being held in the tailstock. Therefore, the barrel turns and the reamer remains stationary. It is kept from moving by using a lathe dog when held by the tailstock center, or the Jacobs chuck when held in this manner.

Starting with the roughing reamer, it is run into the barrel bore up to its stop. Stops consist of collars or merely grease pencil marks on the reamer. Light cutting oil should be used during this operation. Then the finishing reamer is used, again using light cutting oil and cleaning out all metal chips frequently. At this point the chamber is checked by headspace gauges in the usual manner, and the chamber deepened by cut-and-try methods until the desired headspace is achieved.

Threading rifle barrels is definitely a job for the lathe. To set up the lathe for cutting a barrel thread, first determine the number of threads per inch to be cut, and adjust the lathe accordingly. Secure the barrel in the lathe and use a center or thread gauge to set the threading tool point at an exact right angle to the work.

Before starting the actual cutting of a right-hand thread, be sure that the change gear train is assembled properly and that the reverse lever is in the correct position to feed the carriage toward the headstock. Adjust the lathe for the lowest possible speed. Use a compound rest and advance the tool with the rest so that the first cut will be about .003″.

Start the lathe and engage the half-nut lever on the carriage. The angle of the compound rest should allow the back of the tool to take a fine chasing cut on the finished side of the thread while the cutting edge does the work of forming the thread. Apply plenty of lubricant to the work. When the point of the tool reaches the groove at the end of the thread, raise the half-nut lever on the carriage, back out the cross feed a turn or two, and return the carriage by hand to the starting point. Advance the cross feed to its original position then advance the compound rest for the desired depth of cut, and engage the half-nut lever for the second cut. Follow the same routine on all succeeding cuts.

The first few cuts should be approximately .005″ advance of the compound feed and the following cuts gradually reduced until the last few cuts taken are only about .001″. A final pass through the thread with no advance whatever will usually clean up any remaining high spots.



This particular Clymer chambering reamer is for the big .458 American.

16 - MILLING MACHINES

A MILLING machine can certainly be a worthwhile tool in any gunshop, but unless the shop specializes in making a lot of gun parts from patterns or duplicates, a milling machine is certainly not absolutely necessary to carry out general gun repair. By today's standards, a milling machine is really not too expensive if there is enough work for it. But the machine itself is only part of the story. If a lot of different cutters are needed, we're talking about quite an investment.

In general, a milling machine is a power-driven machine that cuts metal by means of a multitooth rotating cutter. The machine is constructed in such a manner that the workpiece is fed to a rotary cutter—instead of revolving as on a lathe, or reciprocating as on a planer.



Either of the two milling machines shown—the Jet 15 (left) and the Jet 16 (right)—would find good use in the gunshop. Obviously, the unit on the left is somewhat abridged compared to the unit on the right. The size of unit eventually selected will depend upon the type of work currently being done—or anticipated—in your own shop.

A variety of gunsmithing operations can be performed on the JET-15 machine which is ideal for the professional gunshop. First of all, you have a complete drill press and all of the operations described in Chapter 13 can be performed on this machine. Furthermore, many kinds of workpieces can be machined on this unit: hammers, trigger guards, almost any small gun part you can name—including receivers!

The multitooth milling cutters used with a milling machine remain sharp much longer than a single cutting tool and the cutting action of a milling machine is continuous, as compared to the intermittent cutting when using a hand file or even a shaper or planer. The milling machine has a power-driven spindle, and an arbor for holding multitooth cutters fits into this spindle. The cutting edges or teeth of revolving circular cutters remove a controlled amount of metal at each revolution of the cutter. The workpiece is mounted on a movable table, and is fed against the cutter. The table can be moved either by hand feed or by power feed. When several cutters are mounted on the arbor, several surfaces can be machined in one operation.

The milling machine was originally developed for manufacturing the small and irregularly-shaped parts used in the construction of firearms, and the milling process is still employed very extensively in the production of similar work, especially when intricate profiles are required and the parts must be interchangeable. Obviously, this same machine can produce replacement parts for firearms and can even be used to make complete firearms.

Operators of milling machines should again be aware of certain safety precautions. The following suggestions should be noted and remembered:

1. Do not move an operating lever without knowing in advance the action that is going to take place.
2. Never play with the control levers or carelessly turn the handles of the milling machine while it is stopped.
3. Do not lean against, or rest the hands on a moving table; if it is necessary to touch a moving member, make sure of the direction it is moving.
4. Do not attempt a cut without being sure that the work is held securely in the vise or fixture and that the holding member is fastened to

the machine table.

5. Remove chips with a brush or other suitable means—never with the fingers or hands.
6. Before operating a milling machine, study it thoroughly; then, if an emergency should arise, the machine can be stopped immediately.
7. Stay clear of the milling cutters; never touch a cutter.
8. Keep your milling machine cleaned and properly oiled at all times.

Workpieces must be mounted properly and securely. Clamping devices, such as T-bolts, toe dogs, screw pins and the like are used to hold milling machine workpieces. Always keep cutters clean and sharp as dull cutters wear more rapidly than sharp ones, and do not last as long as cutters kept in proper condition.

Proper speed and feed rates are governed by several factors which include material, cutter width, depth of cut, surface finish, power and speed available, and cutting fluid. The amount of material to be removed per minute and the relationship between depth of cut and feed influence cutter speed. The feed rate is the rate at which the work advances past the cutter, which is commonly referred to as "inches per minute."



In general, a milling machine is a power machine that cuts metal by means of a multi-toothed cutter. The cutter shown is called a "convex" cutter—the cutter itself is on the left, the type of cut it makes is on the right.



One of the beauties of a milling machine is the fact that the machine does the work, not your hands. It's just a matter of plugging in the right information, a degree of patience and some metal-working experience.



In this instance (left), a custom 1-piece trigger guard is being turned out on a milling machine. The cutter being used is an end-mill cutter—it's used for general purpose end-milling operations in all types of materials. A close-up of the cutters can be seen to the right.

Practical Applications

A course on milling machine operation would take many volumes which is much more space than we have available in this book. Then again, experience is the best teacher of all, and working under an expert machinist is probably the best way to learn the use of a milling machine. Therefore, the remaining pages in this chapter will be devoted to the many attachments available for the milling machines and how they are put to practical use in the modern gunshop.

Double-angle cutter: Double-angle cutters are used for such operations as fluting taps, reamers, and the like. The teeth on one side have an inclination of 48 degrees and on the other, 12 degrees— giving an included angle of 60 degrees for the tooth spaces. This is the preferred cutter for milling helical teeth as the 12-degree side will clear the radial faces of the teeth and produce a smooth surface.

End mill: An end mill cutter is used for general purpose end-milling operations on all types of materials, and is suited for surface milling, profiling, slotting, etc. It is made for either right-hand or left-hand rotation.

Several types of cutting ends for end mills are available which make them adaptable to a variety of uses such as profiling, end milling, slotting, surface milling, and many other milling-machine operations. Some different types of end mills are as follows:

1. Two flute
2. Shell end
3. Multiple flute
4. Carbide-tipped
5. Single end
6. Double end

7. Ball end
8. Hollow

Fly cutter: Can be used to mill intricate shapes that do not warrant the expense of formed cutters.

Formed cutters: These cutters are specially made to meet various milling requirements such as for cutting curved or irregular surfaces. One type of formed cutter is the convex cutter which is used to mill half-circles in all types of materials. A concave cutter is used to mill convex half-circles while corner-rounding cutters are used to mill convex quarter-circles.

Half side cutter: These cutters are plain milling cutters of cylindrical form that have teeth around the periphery on one or both sides. Side mills are used for side milling, for slotting, and for straddle milling work. If the cutter has teeth on only one side, it is a *half side milling cutter*.

Helical cutter: This type of cutter is especially adapted for milling thin work or intermittent cuts where the amount of slack to be removed varies.

Slotting cutter: Used to mill shallow slots, such as screw-head slots. Thin, straight-toothed, plain milling cutters are generally called slitting saws. A plain metal-slitting saw is used for general-purpose slotting, parting, or cutting-off operations of moderate depth in both ferrous and non-ferrous materials.

The staggered-tooth metal-slitting saw is made with alternate helical teeth for shear cutting action and chip clearance between the side teeth. They are used for heavy-duty slotting in all types of materials. This type of saw can make deeper cuts under coarser feeds than other types of saws.

The screw-slotting cutter shown is ground with side clearance and is used for slotting screw heads made of all materials. They are used only for making short, shallow slots.



The “slotting cutter”—often called a slitting saw—is used for general purpose slotting or cutting-off chores.

Woodruff cutters: The Woodruff cutter is used for cutting Woodruff keyseats, slots and grooves in all types of materials.



Screw-slotting cutters like the one shown are ground with side clearance. It’s made to cut screw slots in all materials.



A “Woodruff” cutter is used to cut keyseats, slots and grooves in most materials.

The selection of the type of milling cutter used is also influenced by the following factors:

1. Milling cutters with comparatively few widely spaced teeth can remove more metal in a given time without stressing the cutter or overloading the machine than cutters with a comparatively large number of teeth.
2. Fine-tooth cutters are inferior to coarse-tooth cutters, so far as their relative tendency to “chatter” is concerned.
3. The free cutting action of coarse-tooth cutters is due chiefly to the fact that less cutting action is required to remove a given amount of metal; that is, each tooth takes a larger, deeper cut.
4. Wide spaces between the teeth allow the cutting edges to be backed up as needed, which is not always possible with teeth that are closely spaced.
5. Moderate rake angles reduce power consumption, and are desirable on cutters that are used on mild steel. Large rake angles are undesirable because of the tendency to chatter.
6. The helical angle has little effect on power consumption. However, a large helical angle is desirable because it requires few cutter teeth, gives smoother cutter action, and reduces the tendency to chatter.
7. With few exceptions, coarse-tooth cutters are superior to fine-tooth cutters for production work.

Indexing

The index head on the milling machine is used to rotate a piece of work through given angles — usually equal divisions of a circle. An indexing head, in combination with the longitudinal feeding movement of the table, is used to impart a rotary motion to a workpiece for helical milling action, such as in milling the helical flutes of a cutter.

To operate the index head, the spindle is rotated through a desired angle by turning the index crank which controls the interposed gearing. In most dividing or indexing heads, 40 revolutions of the index crank are required for one revolution of a spindle. The dividing head can be used for several different methods of indexing and index tables are provided by the machine manufacturers to aid in obtaining angular spacings and divisions.

The simplest method is called *direct or rapid indexing* in which the spindle is turned through a given angle without interposition of gearing. Plain indexing is an operation in which the spindle is turned through a given angle with the interposition of gearing between the index crank and the spindle. This gearing usually consists of a worm on the index crankshaft which meshes with a worm wheel on the spindle.



Dividing heads can be used for several different methods of indexing. Proper index tables are provided by the milling machine maker and aid in obtaining angular spacings and divisions. The dividing head shown is for a Unimat-SL miniature machine tool.

Compound indexing is performed by first turning the index crank to a definite setting as in plain indexing, and then turning the index plate itself to locate the crank in the correct position. Compound indexing can be used to obtain divisions that are required for gun work and goes beyond the range of plain indexing.

Differential indexing is a method of indexing where the spindle is turned through a desired division by manipulating the index crank; the index plate is rotated, in turn, by proper gearing that connects it to the spindle. As the crank is rotated, the index plate also rotates a definite amount, depending on the gears that are used. The result is a differential action of the index plate, which can be either in the same direction or in the opposite direction in relationship to the direction of crank movement, depending on the gear setup. As motion is a relative matter, the actual motion of the crank at each indexing is either greater or less than its motion relative to the index plate.

In compound indexing, the index plate is rotated manually, with a possibility of error in counting the holes. This is avoided in differential indexing; therefore, chances for error are greatly reduced. In the differential indexing operation, the index crank is moved relative to the index plate in the same circular row of holes in a manner that is similar to plain indexing. As the spindle and index plate are connected by interposed gearing, the index plate stop pin on the rear of the plate must be disengaged before the plate can be rotated.

Angular indexing is the operation of rotating the spindle through a definite angle (in degrees) by turning the crank. Sometimes, instead of specifying the number of divisions or sides required for the work to be milled, a given angle, such as 20 degrees, 45 degrees, etc., may be specified for indexing. The number of turns of the index crank required to rotate the spindle one degree must first be established to provide a basis for rotating the spindle through a given angle. Usually, 40 turns of the index crank are required to rotate the spindle one complete revolution (360 degrees). Thus, one turn of the crank equals 360÷40=9 degrees; or one ninths turn of the crank rotates the spindle one degree. Accordingly, to index one degree, the crank must be moved as follows:

1. On a 9-hole index plate, 1 hole.
2. On an 18-hole index plate, 2 holes.
3. On a 27-inch index plate, 3 holes.

Block indexing (sometimes called multiple indexing) is adapted to gear cutting. In this operation, the gear teeth are cut in groups separated by spaces; the work is rotated several revolutions by the spindle while the gear teeth are being cut.

The chief advantage of block indexing is that the heat generated by the cutter (especially when cutting cast-iron gears with coarse pitch) is distributed more evenly around the rim of the gear; thus, distortion due to local heating is avoided, and higher speeds and feeds can be used.

Milling on the Unimat 3 Machine

For hobbyists or gunshops without sufficient work to keep a full-scale milling machine in operation, the Unimat 3 (as discussed in Chapter 12) can be set up for many practical milling operations at relatively low cost. A few of the practical applications follow.



For small milling jobs, don't overlook the Unimat. This Unimat has been set up for just that purpose.

Scope Mounts for Lee-Enfield

Obtaining a low, tight-fitting scope mount for the .303 Lee-Enfield rifle has always been a challenge since the only rear support on the action is the charger guide bridge, and the top of this bridge is quite a bit higher than the front receiver rings. The Unimat 3 can be used to adapt two regular scope mounts for this rifle.

A Weaver No. 53 top mount is used as a starting basis. The rear of this mount is carefully marked so that it can be cut and squared to fit inside the recess of the charger guide bridge. The Unimat 3 is then set up for milling by transferring the power drive from the headstock to the drilling and milling attachment, securing the milling table to the cross feed base, and clamping the scope base to the milling table. During the milling operation, the workpiece must be held tightly. In this case, the scope mount is clamped to the milling table with T-nut screws and flat clamps. This setup gives sufficient tightness to avoid excessive vibrations during the milling operation and also to keep the work from moving.



This Weaver No. 53 sight base has been milled and squared to fit snugly into the charger-guide recess on the bridge of a .303 Lee-Enfield. With the mount placed in the receiver bridge as shown, note the mount ring screw slot. It's too close to the guide for use; this s lot will have to be recut about ½″ further forward before a proper fit is obtained.



At this point (left), the rear end of the Weaver base has been secured in the charger slot via two screws through the sides of the charger bridge—now the two main screw holes on the receiver ring can be located, drilled and the base installed and the scope mounted (right).

An end mill cutter is used in the Jacob's chuck for removing the required metal from the rear of the base so it will butt tightly inside the charger guide bridge recess. At this point, you'll notice that the mounting screw guide slot in the base is located too close to the charger guide for proper mounting, so this slot will have to be recut about ½″ toward the front of the sight from its original location. This operation may be performed with a taper pin router chucked in the milling attachment. These cutters take the place of routing cutters and drills, as they will start without first drilling. They also cut freely without build up, and are easily guided along the pattern.

Drill and tap two small holes for screws through the charger guides to anchor the rear end of the mount. Then locate the two main screw holes on the front receiver ring and drill and tap these as required. These four holes will hold the scope tightly during firing providing you properly located the two rear holes (through the charger guides). Those holes must be perfectly centered into the sides of the scope base, as you don't have too much metal to play with.

Dovetailing Rifle Barrels

Universal sight base cutters are made for factory sights with a 60-degree shoulder and ⅜″ base. They are available from most gunsmith suppliers, and if you have a milling/drilling attachment for your mini-lathe, you can perform this operation with the precision of a more expensive full-size milling machine. Here's how I used the Unimat 3 to dovetail a front sight slot on a 24″ rifle barrel.

The tailstock on the lathe bed is removed, as well as the tool holder on the cross slide. Then a milling and fixture table is secured to the cross slide and the vertical drill and milling attachment along with the drive unit is positioned in place for milling.



To cut out a front dovetail slot in a barrel using a Unimat, make sure the action is properly leveled and cut a ¼″ slot about .085″ deep across the barrel as shown.



You next run a wider end-mill cutter (about $^5/_{16}$″) through the same slot and finish up with a standard ⅜″ dovetail cutter.

The rifle is leveled horizontally and held in place by T-nuts and clamps on the milling table so that the barrel is parallel to the lathe bed. If the lathe is solidly mounted to a bench, the milling table and clamps will support the barrel and action securely without further supports. However, for long barrels and heavy actions, you'll probably want to support the action end also, but make sure this end is free to move back and forth (about 1″) when the cross feed is used during the milling operation.

Leveling the rifle is done with a level placed against a flat surface on the rifle. If you cannot find a flat place from which to orient the rifle, you can use a spud or an expandable arbor from a bore sighter. Merely insert the arbor into the bore without the bore sighter attached, and use the flat surface on this arbor to place a small level. When a barrel is to be shortened, mark the barrel and the slot for the new sight position before cutting off the barrel.

With the rifle leveled and the new slot position placed directly under the vertical drill/milling attachment spindle, use a ¼″ end mill cutter to cut a straight slot across the barrel to a depth of about .085″. A second pass is made with a wider end mill cutter (about $^5/_{16}$″) to cut the slot as wide as the top part of the dovetail sight. Then the slot is checked for accuracy and cut to full depth of the dovetail involved. All passes are made with the cross feed on the lathe bed.

The standard four-fluted ⅜″ dovetail cutter will not fit in the Jacob's chuck that comes with the Unimat 3, but the universal 3-jaw lathe chuck may be screwed onto the spindle and used to hold the cutter. Most of these sight base cutters are made .010″ undersize with a plus or minus .005″ tolerance so that the slot can be precision-cut to the exact size on the second cut.

You'll find that the initial cutting with the end-mill cutters is extremely slow on the Unimat 3, so be patient and take it easy so as not to bind the machine. The sight-base cutter, however, will go through the slot like a hot knife cutting butter.

The procedure just described is for cutting dovetail slots for front sights only. We haven't found a practical way to use the Unimat 3 for cutting rear sight slots as yet. You could obtain an extra cross feed attachment and secure the barrel to the milling table mounted on one of the cross feeds (with the barrel perpendicular to the lathe bed) and the vertical drill and milling attachment secured to the other cross feed, but the setup time involved would make it more profitable to cut the slot by hand.

17 – MISCELLANEOUS GUNSMITHING TOOLS

THERE IS a class of tools that may be classified as a luxury; that is, while not essential to general gunsmithing work, these tools are mighty nice to have around. In compiling this list, it was noted that a luxury item in one person's shop may be a very essential tool in another's—depending upon the type of work normally done. Such tools will include power hacksaws, band saws, testing facilities, heat-treating furnaces and the like.

Power Hacksaw

Power hacksaws are designed to make sawing of metal a mechanical rather than a hand operation. One type of power hacksaw commonly found in some of the larger gunsmithing shops has a drive shaft that's connected by a V-belt and gears to the electric motor mounted on the machine. The work table is equipped with a vise that can be mounted either straight or at an angle to the blade. The mechanism raises the hacksaw blade on the return stroke so as to prevent dulling of the blade by dragging it over the work as the blade is returned to the starting position. Another important feature on this power hacksaw is a blade safety switch that automatically stops the machine if the blade should break during operation of the saw. This feature prevents any damage that could result if the machine continued operation with a broken blade.

Small power hacksaws can be used on square or round stock up to 3 or more inches—quite sufficient for any gun barrel that will be encountered. High speed tungsten steel and high speed molybdenum steel are the most commonly used materials in power hacksaw blades. The common tooth types are described as follows:

Regular tooth blades are for cutting and contouring most ferrous and hard non-ferrous metals used in the shop. Straight-faced teeth continuously rake chips out of the saw cut.

Hook tooth blades have a 10-degree positive rake angle, making fast cutting rates possible at reduced feed pressures. For non-ferrous metals, non-metallics and tough alloys of 3″ section and larger. Rounded gullets allow fast chip removal.

Skip tooth blades have a 0-degree rake angle. Widely spaced teeth provide extra chip clearance. Shallow gullets increase band strength. It is recommended for cutting large sections.

There are also different tooth sets for various cutting jobs. In general, there are two types: the raker set and the wavy set. Both have a right and left positioning of teeth to provide clearance for the back of the blade and prevent binding in the saw cut. These tooth sets are described as follows:

Raker Set: Teeth are set alternately right and left, followed by a straight raker tooth to remove chips (and load) and improve cutting action. *Wavy Set*: Groups of teeth are set in the shape of a curve alternating right and left to distribute the chip load over many teeth.



Power hacksaws are designed to make the sawing of metal a "power" process, not a hand operation. The power hacksaw shown is typical of those found in some of the larger gunsmithing shops.



Hacksaw blades come in two types of "tooth sets" — raker set or wavy set. The raker teeth are set alternately right and left, followed by a straight raker tooth to remove the chip and load and improve cutting action. The wavy set has groups of teeth set in the shape of a curve alternating right and left to distribute the chip load over many teeth.



These hacksaw blades represent the more common tooth varieties. From top to bottom: regular; hook; skip. Each has its own particular use around the gunshop.

To operate the power hacksaw, secure the work in the vise so that the blade will saw at the desired place. The blade is then lowered on to the work carefully to start the cut. Never allow the blade to strike the work as this will damage or break the teeth. The machine should be adjusted so that the blade lifts about ⅛″ on the return stroke. Otherwise the blade will be damaged if allowed to be dragged back across the work.

The cutting speed of a power hacksaw varies with the material being cut. Power blades with 3, 4 or 6 teeth per inch are for cutting soft materials and heavy, solid bars of stock. Power blades with 10 and 14 teeth per inch are for cutting harder materials and stock of smaller size. Selection of teeth per inch based on saw contact area can be made from the following table:

No. of Teeth Per Inch	Saw Contact Area
3	4″ to 12″
4	2″ to 6″
6	⅜″ to ¼″
10	¼″ to ½″
14	Less than ¼″

Data on selecting speed and feed is given below:

Material	Speed, Strokes Per Minute	Feed, Sq. Inches Per Minute
Aluminum	120 to 150	2.0 to 4.5
Brass	120 to 150	1.5 to 3.5
Bronze	90 to 120	0.5 to 1.5
High Density Alloys (Udimet, Waspaloy, Inconel, etc.)	30 to 60	0.2 to 0.7
Cast Iron	90 to 120	1.5 to 3.0
High Nickel Alloys	60 to 90	0.8 to 1.5
Low to Medium Carbon Steel	120 to 150	2.0 to 3.0
Tool Steel	60 to 90	0.5 to 2.0
High Speed Steel	60 to 90	0.5 to 1.0
Stainless Steel	60 to 90	0.5 to 1.5
Structurals	120 to 150	—

Without proper mounting tension, a power hacksaw blade cannot deliver the cutting efficiency built into it by its manufacturer. Not enough tension will result in blade runout, accelerated wear and/or a poor finish on the work. Too much tension can also cause the blade to break, especially at the pinholes.

Use the chart below to tension power blades correctly. Check your reading after one or two cuts and increase the tension slightly as the blade becomes stabilized in position. With machines where the saw blade is tensioned by lever action, use approximately 50% of these readings.

A power hacksaw blade cannot deliver its best cut-off performance on a machine in poor mechanical condition, so the machine should be maintained on a regular basis with emphasis on such items as yoke alignment, blade tensioning, fit of pins in pinholes, dirt between blade and holder, feed pressure, belts and hydraulic system. When a blade is installed on the machine, care should be exercised to see that the right amount of tension is used.

Blade Width	Redstripe and Bluestripe High Speed	Greenstripe High Speed
Direct Pull Recommended Torque Wrench Readings (Approx.)		
1″	125 ft./lbs.	150 ft./lbs.
1-¼″	175 ft./lbs.	200 ft./lbs.
1-½″	200 ft./lbs.	225 ft./lbs.
1-¾″	225 ft./lbs.	250 ft./lbs.
2″	250 ft./lbs.	275 ft./lbs.
2-½″	275 ft./lbs.	300 ft./lbs.
Direct Pull Recommended Fixed Tension Device Readings (Approx.)		

1″	1000 in./lbs.	1200 in./lbs.
1-¼″	1800 in./lbs.	2000 in./lbs.
1-½″	2000 in./lbs.	2250 in./lbs.
1-¾″	2250 in./lbs.	2500 in./lbs.
2″	2500 in./lbs.	2750 in./lbs.
2-½″	2750 in./lbs.	3000 in./lbs.

Some of the reasons for blade *breakage* are:
1. Blade contacting work before in motion
2. Cutting with a new blade in slot cut by dull blade
3. Not enough blade tension
4. Feed pressure too heavy when cutting thin section
5. Using a dull blade
6. Material loose in machine vise
7. Blade too thin or too narrow for feed and material

Some of the reasons for power hacksaw blades *not cutting straight* are:
1. Not enough blade tension
2. Dull blade
3. Hard spot in material forcing blade out of path
4. Feed pressure too heavy
5. Feed mechanisms not functioning
6. Saw frame out of alignment
7. Machine capacity inadequate

Premature dulling of teeth can be caused by:
1. Cutting speed too great
2. Blade fails to lift on return stroke
3. Feed pressure too heavy
4. Teeth facing wrong way
5. Incorrect blade selection
6. Lack of (or wrong) coolant

When hacksaw blade teeth start *ripping* out, the reason may be one or more of the following:
1. Too many teeth for cutting large work section
2. Too few teeth for cutting thin section
3. Sawing against a corner or sharp edge
4. Sawing a large cross section of soft material with too fine teeth at too heavy a feed or too slow a speed

Bandsaws

Like power hacksaws, power bandsaws are designed to make the sawing of metal a mechanical operation. Rather than having a single blade secured in a frame, the bandsaw utilizes a flexible, thin, narrow ribbon of steel which forms a loop to ride on two wheels. One of these wheels is powered by an electric motor mounted on the machine. They are used for heavy-duty sawing of metals.

One of the most important factors in operating a bandsaw is a proper cutting speed. If the machine is operated at too fast a speed, the teeth are not allowed sufficient time to cut into the material. As a result, they merely rub over the surface of the work creating friction that rapidly dulls the cutting edge and wears out the blade.

Many variations of power bandsaws are available, but all of them can be grouped into three classifications; that is, horizontal machines for cut-off sawing, vertical machines for straight and profile sawing at conventional speeds, plus vertical machines for non-ferrous and friction cutting.



This power bandsaw is typical of those suitable for gunsmithing chores. Before buying one, be sure to consider the type and amount of work you'll be doing that would require a power tool such as this.

Shapers

The gunsmith who does a lot of specializing might find it necessary to purchase a shaper for turning out parts such as hammers, triggers and the like. The cutting tool is moved in a horizontal plane by a drive shaft having a reciprocating motion, and it cuts only on the forward stroke. The work is usually held in a vise bolted to a table that can be moved either vertically or horizontally. Any device that can be attached to a work table for holding and positioning the work piece is considered to be a fixture. Numerous fixtures can be used to set up castings having odd shapes for machining.

When a gun part is to be cut out, the operator must decide on the number of cuts necessary. However, usually one or two roughing cuts and one or two finishing cuts are all that's required— depending on the shape of the work and finish desired.



A shaper is used for turning out such gun parts as hammers, triggers, trigger guards and other such items. The gunsmith who specializes in this sort of work will find the shaper a necessity.

Gunsmiths' Furnaces

The gunsmith who makes a lot of his own tool's and parts will find a heat-treating furnace very useful. Several types are available ranging in price from a few hundred dollars to over $1,000. The Huppert electric heat-treating furnace is designed specifically for precision heat-treating in gun-shops. It is simple to operate and service.

In the gunshop, pins, sears, reamers, springs, hammers and many other parts and tools require proper hardening. Many gunsmiths are able to accomplish this hardening with a gas flame, but the process can not be controlled this way. The odds against one obtaining the correct hardness every time are high. The investment in an electric heat-treating furnace insures complete control over hardening, tempering and annealing. Complete instructions are normally furnished with each furnace.

Most heat-treating furnaces are not very large because they will be used mainly for small parts. One with a capacity to handle parts up to 8″ in length and 4″ wide should be quite adequate for most gunsmithing needs. The largest one listed in Brownell's catalog has a chamber 5½″ high by 5″ wide by 13″ deep, but its cost is high—requiring quite a lot of heat-treating business to make it economically worthwhile.

For removing parts from the hot furnaces, one or more sets of tongs are necessary. Special tongs, available from Frank Mittermeier, Inc., are specially designed for small parts being handled in heat-treating furnaces. They are made from! 4″ stock and are about 16″ long. They provide a means of insuring a positive grip on various objects and permit the operator to exert leverage from such a distance that his hands will not be affected by the heat of the object being held. Many gunsmiths seem to get by with a pair of pliers, but when used to handle hot objects, pliers will quickly lose their temper and consequently their usefulness—much the same as many gunsmiths themselves!



Heat-treating furnaces will be found handy by gunsmiths who make a lot of their own tools, or reharden certain gun parts. The cost of these furnaces ranges from a few hundred dollars to over $1,000. The furnace shown is made by Huppert and is designed for precision heat treating.



When handling small parts that are being heat treated in a furnace, tongs like these are necessary.

Shooting Facilities and Chronographs

Every gunsmith should have shooting facilities to test various firearms and loads. Ideally, the gunsmith should have a bench rest and a 100-yard range for testing, sighting-in, chronographing, etc. One of the handiest items you can have for the above purposes is a shooting bench. My own shooting bench was built from a design supplied from Jim Carmichel. This bench is only for right-hand shooters; however, plans for a right- and left-handed bench are shown here.

PLANS FOR A SHOOTING BENCH



(Above) If you follow these working drawings, you can come up with your own shooting bench. This particular bench is designed to accommodate the needs of both left- and right-handed shooters.

Here is the finished shooting bench. It is designed for right-handed shooters. Made from a design supplied by gun writer Jim Carmichel, it's well suited for sighting-in chores.

This particular bench was built from plans similar to the author's; and, while it is decidedly in need of repair, it should be mentioned that this bench pretty well withstood the elements, and served the needs of many shooters for over 30 years!

Another item of interest—especially for gunsmiths who handload—is an electronic chronograph. At one time these instruments were very expensive and only factories or other professional outfits could justify the expense of purchasing such equipment. However, recent miniaturization of electronic components has brought the chronograph within the budget of many serious shooters.

In general, chronographing is the determination of the speed of a projectile, usually expressed in feet per second (fps). This is accomplished by recording the time the bullet takes to pass from one point to another—the "start-stop" points being screens of either paper, plastic or simply light activated. One of the better chronographs, and the easiest to use, is the Model 33 manufactured by Oehler Research. It includes new-design "Sky-screens" that cost very little each to replace if damaged. I've been using this chronograph for the past several months and have found it very convenient, accurate and a pleasure to use. It reports recorded velocity immediately after each shot is fired plus the number, in sequence, of the shot. The hooded readout is easy to see, and the instrument can be set (internally) for a variety of screen spacings. At the end of a test session, pushing the "Summary" button successively gives: lowest velocity, highest velocity, extreme spread, standard deviation and average velocity.

In the Oehler Model 33, time is measured by counting the ticks of a very accurate electronic clock. The clock ticks at the rate of one million pulses per second. As the bullet passes over the first skyscreen, a signal is sent to the chronotach telling it to start counting the pulses. When the bullet passes over the second skyscreen, a signal is sent telling the chronotach to stop counting the pulses and to then display the time or convert the distance and time to velocity for the display. All this takes less than one-tenth of a second after the shot is fired. Not only does the Model 33 compute velocity from time and distance, but it automatically examines the data from each round recorded and computes the essential statistics for velocity at the end of a test lot. While this may seem radical for a handloader's chronograph, the best industrial units used this technology for years before it was extended to the handloader's market.

The Oehler Model 33 Chronograph is the author's choice for an accurate, easy-to-use chronograph. Its cost is within the reach of most hand loaders and shooters.



When mounting your chronograph's sky screens, you might want to consider this set up — it's easy to erect, take down and transport.

To use the Model 33 chronograph, remove the cover by first removing the two screws on each side. The distance switch is at the center of the electronic circuit board and is usually set at 10 feet when the unit is shipped from the factory. The distance shows in little windows as you look at the switch from the rear and can be readily changed by rotating the switch elements using the knurled grip showing just above the numbers. Set the numbers for your spacing in feet.

While the cover is off, install six size "D" flashlight batteries. Alkaline batteries are suggested for best performance and long-range economy, but ordinary zinc-carbon batteries will normally work well for a few hours. Install three batteries in each tube. The positive tips of the batteries fit into the red insulating washers on the battery holders. If the total battery voltage drops below 6.6 volts, the decimal point in the lower right corner of the display will appear. This is a positive indication that the batteries are low and the system will soon fail to work properly. If you see no digits displayed when the unit is turned on, it's time for fresh batteries.

The initial setting-up of the skyscreens is a little troublesome, but once in place, actual chronographing is very simple. The bases of the skyscreens should be mounted so that they are 3 to 5 inches below the bore line and between the gun and the downrange target; therefore, any shot that comes close to hitting the target will not hit the skyscreens.

Connect the cables from the skyscreens to the input jacks of the chronograph so that the screen nearest the muzzle is connected to the start input. (Make sure that the plugs are pushed all the way into the jacks.)

Turn the chronograph on and the unit will immediately display 0 for velocity and 00 for round number. Shoot over the screens and the display will immediately show the velocity at the left side with round number 01 at the right side of the window. Six-tenths of a second after the velocity is displayed, the system is reset and ready for the next round even though the display continues.

After firing a test lot of ammo, the chronograph will display the summary. The summary is started by pushing the *summary* button. You can request a summary at any time. The first number displayed after pushing the display button is the lowest velocity encountered in the lot and will be identified by "LO" in the display window. After observing and recording the low figure, push the button again and the display will show the high denoted by "HI." Push the button again to display the velocity range or extreme spread denoted by "ES." Push the button again to display the average velocity denoted by an "A." Push the button again to display the standard deviation denoted by "SD."

If you push the button one more time, the display will show a velocity of zero and the number of valid rounds included in the summary. At this point you can either fire more rounds to be included in a composite summary or cycle through the summary display again. The system will not recognize signals from the skyscreens during the display of the summary until you reach the point where the round number and zero velocity is displayed. Turning the unit off will clear all the statistical information and it will be ready for a new lot when you turn it back on.

Band Sanders

A new motorized table top disc/belt sander has been recently offered by Dremel which should be ideal for sanding, shaping, polishing, cleaning, sharpening and many other uses around the gunshop. The new Dremel Model 730 is only 15-inches high by 10-inches wide by 11-inches deep and features a 1-inch wide by 30-inches long aluminum oxide sanding belt and 5-inch diameter sanding disc with adhesive backing. The sanding disc rotates at 4400 rpm and the sanding belt moves at 2700 square feet per minute. The unit weighs approximately 11 pounds.

The work table for the disc sander can be tilted 45 degrees to align the work piece to the desired angle and an adjustable miter gauge provides for accurate disc sanding at most angles. Other features include a removable platen which provides a rigid belt sanding surface, an easily accessible front/mounted ON/OFF switch, Universal 110- 120V, 60 Hz belt driven 2.2 amp motor with self-limiting brushes, and an attractive black shock-resistant molded plastic housing. The unit is approved by Underwriters Laboratories.



Dremel’s combination disc/belt sander is a handy, small unit that's only 15 inches high. It fits on just about any workbench and handles chores ranging from sanding to polishing and sharpening.

Superwelder



For small welding jobs around the shop, the “Superwelder” comes in handy. The entire Superwelder kit comes with everything you’ll need except a 12-volt battery. To the right, the Superwelder has been hooked up and is ready to start welding.

There is little doubt that an arc welder in any shop that works with metal is handy, if not indispensable, depending upon the type of work done—and how much. Few shops, however, have enough welding jobs to warrant the purchase of an outfit. They’d do better to take their few jobs to a professional welding shop and let them do it.

For small welding jobs around the gunshop, such as building up hammer sears, there’s a little outfit called the Superwelder. For your investment you’ll receive an electrode holder, two lead wires with battery and work clips, and an assortment of carbon, brass, and copper electrodes along with several pieces of solder. Although small, this outfit is not a toy. The same precautions must be taken as you would with one of the larger outfits; that is, you’ll be working with molten steel and fire. Wear heavy gloves and a long sleeved shirt or jacket to protect your hands and arms. You’ll want a welder’s helmet for eye and face protection, or if you work behind a shield, at least wear safety goggles. Always work in a well ventilated area and do not breathe the fumes.

All you need to put this outfit in operation is a regular 12-volt auto storage battery. One of the wire leads is connected to the negative terminal of the battery and to the work. The lead to which the electrode holder is connected is secured to the positive battery terminal. You’re now ready to use the arc torch for spot welding, cutting, heating, marking and soldering. As with any other job, practice is needed to do satisfactory work, so use plenty of tin cans and other scrap metal to practice on before you attempt to repair a broken gun part.

One of the best ways to learn cutting and welding with this outfit is with carbon electrodes. Connect the positive lead clip to the carbon electrode and your work to the negative lead clip. With your eye protection in place, slowly draw the carbon electrode across a tin can’s surface, not touching the surface, but keeping the electrode near enough to maintain an arc. You will find that the arc will cut through the metal just like a hot knife cuts butter. At first you’ll probably have an uneven cut, but after some practice at maintaining an arc, you’ll find the cuts will be smoother and easier.

To spot weld with the carbon arc torch, place the two work pieces together and join them tightly with a C-clamp. Connect the negative wire to the work and quickly touch the carbon torch end to the work itself. You will find that you’ll have joined the two pieces permanently.

When spot welding, always be certain that the surfaces to be joined are clean and dry. Failure to weld and fuse together are usually due to dirt, water or insufficient contact between the metals to be joined. It is necessary to just touch the carbon to the work—don't hold it there for any length of time. However, if you don't maintain contact enough, the work will not join; too much contact will melt or burn the work.

This carbon torch may also be used for marking metals—even hardened steel. Merely connect the leads as described previously and write across the surface of the metal and the surface will be marked. When necessary, you can sharpen the carbon tip with a file to provide a better tip for finer marking. Again, battery life will be much longer between charges if you maintain an arc and do not make direct contact between the carbon and the work.

To solder with this outfit, first make certain that the surfaces to be joined are clean and dry. Then, using the carbon tip, heat the work so the solder flows. (Both soft and silver solder may be used with this outfit.) The carbon arc torch may also be used to heat any metal to soften it so it can be worked better, marked or annealed.

For your first practice welding jobs with this outfit, the manufacturer recommends that you use copper or brass. These electrodes will be used in the same way you welded, cut or marked with the carbon arc torch. Metal electrodes will take much more practice than the arc torch and requires a well-charged battery. Flux can be sprinkled on the work but you must be careful that only enough is used. If too much flux is used, contact is lost between the work and the electrode.

Striking and maintaining an arc is very similar to striking a match and requires a lot of practice for some individuals, while others get the hang of it more quickly. Practice will enable you to do much or even all of your own welding.

As mentioned previously, this Superwelder will not handle large welding jobs as will the more expensive models. However, with practice, you will find yourself using it to repair broken gun parts and for building up surfaces on metal parts. Even if you use this as an instructional device—and later go to the larger models for your actual work—it's still worth the money. There are several good books on the market that will help you become a better welder. One is *Welding Technology* published by Howard W. Sams, Inc. You'll probably find it at your local library.

Brownell's Acraglas



Brownell's Acraglas (above) is not only used for glass-bedding jobs, it's one of the best "tools" you can use for mending broken stocks or grips. The little Winchester Model 60A (right), came into the author's shop with its stock broken into two pieces — the repair was made with Brownell's Acraglas.

You may be wondering why we are mentioning a material such as Acraglas in a book on gunsmithing tools. We are doing so because Acraglas has become a "tool" in nearly every professional gunshop in the country. Besides glass bedding for a 100% wood-to-metal contact for improving accuracy, Acraglas is one of the best "tools" I know of for making stock repairs.

A few months ago, a customer brought in a Winchester Model 60A, .22 caliber rim fire single shot rifle with a broken stock. The stock had been broken completely in two when the owner ran between two trees with the rifle in his hands. The butt stopped abruptly on the tree to the left while the barrel did the same on the tree to the right; the result was a completely broken stock at the forward end of the pistol grip. The owner then tried gluing it, but after being subjected to a little dampness, the stock again separated.

This little rifle had been given to the owner by his favorite uncle, and he wanted it preserved (as near as possible) in its original condition. A replacement stock was not readily available, and he didn't want to go to the expense of making a new one from a walnut blank. This is where Brownells Acraglas kit came in.

I re-broke the stock where it had been broken previously and then removed all of the old finish with G96 Finish Remover. Dents were raised with a soldering gun and a damp cloth while scratches were removed with abrasive paper and the sharp edge of a piece of broken glass. The rough edges of the break were cleaned with a toothbrush dipped in AWA 1-1-1; next came the mixing of the Acraglas components.

The mixing ratio of Acraglas is 4:1; that is, pour 1-oz. of Acraglas resin into the graduated cup that comes with the kit. Stop pouring, however, just before the 1-oz. mark is reached and allow the resin to level in the cup. Then slowly pour the balance needed to the 1-oz. mark on the cup. Add one-quarter ounce of Acraglas hardener, using the same pouring procedure as before. Be sure the cup is level so you'll obtain an accurate reading, and don't add more than ½-oz. as too much hardener prevents proper hardening.

Acraglas in itself is glass-clear, but a tube of special duPont dye is furnished with each kit. With this you can color the Acraglas mix to blend with the color of the individual stock. It is better, however, when repairing stocks to have the Acraglas a little lighter rather than darker than the wood.

Open the small pack of dye and pour a sufficient amount into the mix to obtain the color desired. Stir the mixture gently, smoothing out the lumps of stain against the side of the cup with the paddle furnished with the kit. (At this point, add more stain if needed.) After two minutes (timed) stirring, add one-half of the packet of "Floe" to the mix if you're using the mixture for bedding. (In this case of a stock repair, no Floe was used.) The mixture was then applied to the broken gunstock and the two parts were carefully joined—aligning the jagged edges of each piece precisely. Then the entire assembly was clamped tightly in a padded vise. Excess solution that emerged from the crack during compression was wiped off the outside of the stock before letting it set and harden further.

A couple of hours after the application, the stock was removed from the vise, and surplus exposed Acraglas was removed with a dull knife, being careful not to scratch the wood in the process. The stock was finished in the normal way. Although a hair line is visible where the break was (if you look closely), the stock is as strong—if not stronger—than it was originally.

When used in conjunction with inletting, allow $^{1}/_{6}$″ to ⅛″ clearance in the barrel channel and behind the recoil lug. The wood in the barrel channel should be left rough rather than sanded smoothly to add strength to the wood itself by creating more exposed wood surface and therefore realizing the full advantages of Acraglas' strength-giving qualities. Be sure to use sufficient release agent on all metal surfaces which might come in contact with the Acraglas solution. Shake vigorously while in the jar and then apply to the metal surfaces.

One of my customers recently purchased an Acraglas kit from me to bed his Winchester Model 70. The next day, he came back to the shop with the barrel permanently attached to the wood. He had not read the first page of the instructions accompanying the kit and had failed to use the release agent. By saturating the area with Acetone, and striking the barrel with a rubber hammer, we were finally able to break the barrel loose from the stock.

For bedding, mix Acraglas as described before; use the Floe and stir the mixture two minutes longer to assure that this mixes thoroughly with the solution. Then with the paddle, spread the prepared Acraglas in a ridge down the center of the barrel channel to prevent air from being trapped when the barrel is seated. Also fill the recoil lug recess sufficiently to completely fill the recess when fitted. Firmly press in the release-agent coated barrel and action to the desired depth.

When Acraglas shows signs of hardening after an hour or two, remove all surplus exposed solution with a dull knife or spatula, being careful not to scratch the gun's metal or wood finish. Leave a small bead of Acraglas above wood between the stock and metal to be sanded to contours of stock after final curing.

Under normal conditions, the barrel and action can be removed from the stock within 24 to 36 hours. In cases of extremely tight fits, the careful use of a soft rubber mallet will help in getting the metal and wood separated. Should you find bubbles or the like between the metal and Acraglas, these can be filled by applying fresh mixed Acraglas in minute quantities and re-bedding the barrel and action. Bonding will be complete and as strong as if the void had not existed. Be sure that all voids to be filled are completely free of the release agent before filling.

Locating Top Dead Center of Gun Barrels

Every gunsmith is called upon from time to time to install sights on shotgun and rifle gun barrels, and there's always the problem of finding the exact top dead center of the barrel. The T. D. C. Company of Portland, Oregon offers a handy device that is designed to determine the exact top dead center on secured round stock such as gun barrels, providing the barrel and action are level. This can be checked using the T. D. C. tool as a level.

The device is placed on the barrel as shown. The hook is designed to determine the exact distance from the muzzle to the front sight. When the centering bubble is precisely aligned between the reference lines, the hole in the top of the device is exactly top dead center of the barrel. Then, using the "dimpler punch", lightly tap that spot with a hammer to mark the barrel. The level in the T. D. C. is extremely sensitive—again, just a slight tap with the hammer or you might dislodge the T. D. C. setting. A standard center punch may then be used to enlarge the "dimple" if necessary.

The imaginative gunsmith will find many uses for the T. D. C. centering device. For instance, it can be used for layouts on extractor slots or as a common level in "free" setups, etc. If you can't find this device locally, they can be ordered from Frank Mittermeier.



The T. D. C. center-finding device (above) is used to find the exact dead center of round stock (barrels) as can be seen to the right. It's precise, and it allows you to accurately locate front sight screws or sight holes.

18 – PLATING FIREARMS

NICKEL PLATING has long been a favorite finish for many handguns. It provides decorative effects-, protection against rust and corrosion, and a wear-resisting surface. Although nickel has been the traditional favorite, other metals have included chromium, gold, silver, brass and copper. Chromium, for example, when applied to metal gun parts provides a surface harder than the hardest steel, which protects the base metal, reduces wear, lessens friction and, at the same time, provides an attractive appearance.

Most metal plating is accomplished by a process called "electroplating" which uses an electric current to deposit the plating over the base metal. In general, the object to be plated becomes the cathode (negative plate) in an electrolyte cell that contains (in some chemical compound) the type of metal which is to be plated onto the base material. Anodes are used on all sides of the object so that electricity may flow from all directions to the article being plated and cause an even deposit of the plated metal.

The exact chemicals, currents, voltages, temperatures and general procedure will vary with the kind of metal being plated and the type of method being used. For example, nickel plating often is done with an electrolyte containing nickel sulphate or nickel ammonium sulphate, to which is added ammonium sulphate to increase the conductivity; some acid to help keep the anode rough, and something like glue or glucose to make the plating extra bright.

The anodes may be of some material, such as carbon, which is not affected by the electrolytic action. When using this method, all the plated metal must come from the electrolyte and chemicals containing this metal must be added to the liquid at various intervals. In other plating methods, the anode is made of the plating metal. As an example, in plating with brass, the anode is of brass. Then brass dissolves from the anode into the electrolyte which is deposited from the electrolyte onto the cathode or object to be plated. The object of this method is to get metal dissolved into the bath (electrolyte) as quickly as it plates out. As the anode metal dissolves, it generates a voltage just as dissolving a metal generates a voltage in a conventional storage battery. Under ideal conditions, this generated voltage would equal the voltage consumed in depositing metal on the cathode, so the external source would need to provide only enough voltage to overcome the resistance in the cell and the connections.

Before we get into the plating process, it should be observed that you may not want certain areas of a gun plated. A good example would be the sear engagement areas on a handgun hammer and trigger. Until recently, you had to plate those parts and then redress them to work as perfectly as they did prior to plating. Brownell's now offers what they call their Stop-Off Lacquer. You simply apply the lacquer to the portion of any part you don't want plated and plate the entire part normally.

When the plating process is done, take some Brownell's Stop-Off Stripper and wipe it on to the area lacquered prior to plating—that lacquer and any build up of plating comes right off. Believe me, it's a super system for keeping the trigger pull "just the way you had it."





(Top) When plating, anodes are used on all sides of the object being plated so that the electricity may flow from all directions, to that object, so that an even deposit of plating metal results. In this case, the electrolyte solution contains the plating material. (Above) In other plating methods, the anode is made of the plating metal. In this case, the anodes are of copper and dissolve into the electrolyte which in turn deposits the copper plate on object.

Stripping

Stripping is used to remove old plating, and to brighten up oxidized surfaces and also to clean inaccessible places. In general, there are four ways to take nickel plating off a gun. First, the finish may be removed electrically; that is, the object to be stripped becomes the anode, and a piece of metal such as brass or stainless steel is used as a cathode. Secondly, you can polish it off in much the same way as you would in polishing off old blue on firearms.

Pure nitric acid will also strip nickel from iron or steel without attacking the base metal as long as it is pure. However, such conditions as humidity in the air changes the purity of the acid, and then it can literally dissolve a gun in a very few minutes. Nitric acid is also very dangerous to handle.

The fourth stripping system uses chemicals for the process. It's a companion system to the electroless nickel plating system offered by Brownell's. It will not pit or etch steel. It has excellent stability and a long, active solution life. Because of an easy replenishment system, solution life can be further extended which cuts the operating costs. The components contain no cyanide so they can be shipped easily via UPS. The solution operates at a slower rate of stripping than most other systems which give complete control, and it will remove most nickel plating on firearms.

To strip, the gun should be disassembled and heavy emphasis placed on cleaning. This thorough cleaning prior to beginning the stripping sequence removes all gunk, gun oils and so on. The cleaning must be thorough to allow the stripping operation to work efficiently. The stripping steps are as follows; detailed steps follow the general outline below:

(1) *Pre-clean*: Use trichloroethane on cotton swabs and brushes to remove as much foreign matter, powder residue, gun oils, etc., as

possible. Do not use a petroleum based cleaner such as gas, kerosene, mineral spirits, or gun cleaners; they will leave a residue on the part.

(2) *Flowing Water*: (Use same tank as used for plating process.) Submerge parts for ten seconds and agitate to float away loosened residue.

(3) *Acid-Cleaning Tank*: Submerge parts for three seconds and agitate. This further cleans parts and removes foreign residue, especially oil.

(4) *Flowing Water*: Submerge parts for five seconds to flush acid cleaner from surface of metal.

(5) *Nickel-Stripping Tank*: Submerge parts in stripping tank until all nickel is removed from the bright steel base metals. The stripping solution must operate at 200-210 degrees Fahrenheit. Water lost by evaporation should be replaced during the stripping cycle in order to maintain the original volume of solution. Parts will have to be removed from the stripping tank to be thoroughly checked to see that they are completely clean of the nickel plating.

(6) *Flowing-Water Tank*: Submerge parts for two minutes to flush away all of the stripping solution. Allow stripped parts to air dry normally, or use compressed air to speed dry. The gun can now be polished or put back through the plating cycle. If you are not going to polish or plate immediately, be sure to oil gun surfaces with water displacing oil (nye oil, “HOLD,” Brownell’s No. 2 or some other basic rust preventative which does not contain any of the exotic penetrants which could contaminate future bluing or plating of the gun).

Two tanks are required for the stripping operation, and must be different ones from those used for plating to avoid cross-over contamination. Be sure to mark them plainly “FOR STRIPPING ONLY,” and preferably keep them in a different storage area (or on a different shelf). The stripping tanks can be fairly small in size since you will rarely strip more than one gun at a time. The tank can be stainless steel (Grades 304 or 316 only), ceramic, pyrex, quartz or other suitable materials that can withstand the 200-degree Fahrenheit operating temperature. Because of their convenience and availability, pyrex/laboratory tanks in both round and square styles may be used and are available from Brownell’s.



Plating jars, like this gallon pyrex jar, can be obtained from Brownells. Works for either electroless or electrolytic plating and is large enough to contain most pistol frames, barrels or rifle actions or trigger guards.



If you anticipate doing much plating, you might want to consider getting one of Brownell’s Nouva-7 electric stir/hot plates. The unit gives you a constant source of heat and controlled agitation. It's also designed for chemically stripping gun parts.

If a direct gas flame is used for the heat source, the pyrex tank must be protected from thermal shock. (Special instructions are included with each pyrex tank ordered from Brownell’s and explain in detail how to make a “sand bath” to protect the tank and keep it from breaking.) If you anticipate much plating, however, it is recommended that you purchase the Electric Stir/Hot Plate, also available from Brownell’s. This unit provides a reliable source of constant, even heat plus thoroughly controllable agitation. It is specially designed for chemically stripping gun parts as well as their electroless nickel plating system.

The large 7⅛″ square, heavy cast aluminum top has embedded heating elements and is machined flat for optimum heat transfer and uniform top plate temperatures. A “demand” thermostat maintains close temperature control and compensates for room temperature or line voltage fluctuations, holding surface temperatures within ± 3 degrees C. Heat indicator light tells when top is heating.

The stirring part of the unit features an extremely strong stirring torque from 60 to 1000 rpm. The Alnico V-drive magnet is located close to the top plate to assure strong magnetic coupling and to prevent jitterbugging. A solid state speed control gives excellent slow speed control, high starting torque and is independent from voltage changes, maintaining constant stirring action. Controls for the Electric Stir/Hot Plate are up front, easy to use and isolated from the heat of the top plate to assure long trouble-free life. When heating a one gallon jar of solution, the unit is capable of raising the temperature of the solution approximately 1 degree per minute. The unit is fully guaranteed to give excellent service. When using this heating unit, the pyrex tank can be placed directly on the heating plate.

The purpose of the acid cleaning tank is to clean only, and the solution should consist of 50% hydrochloric acid and 50% pure (distilled) water. The tank must be covered when not in use again, and, must be marked “STRIPPING ONLY” to prevent any mix-up with the plating tanks. To mix one gallon of solution for the acid cleaning tank, measure 2 quarts (64 fluid ounces) of clean water and pour into the tank. Measure 2 quarts (64 fluid ounces) of hydrochloric acid and pour very slowly into the water already in the tank. Remember, *always add the acid to the water and not vice versa*. When mixing this solution, always wear goggles and rubber gloves.

To mix one gallon of stripping solution, first wash the stripping tank with clean water to remove any residue or possible contaminate. Pre-measure 1 gallon of clean water in the tank, and make note of its depth by measuring it with a dip stick. Measure 51 fluid ounces of clean water (hot or cold) and pour into the stripping tank. Measure 32 fluid ounces of Brownell’s Concentrate 778, and pour slowly into the water already in the tank. Immediately begin mechanical agitation of the solution at a moderate rate. Begin heating the solution, and bring it up 120 degrees F.

Continue by measuring 1.25 pounds (dry weight) of Concentrate 778-R. Slowly add this concentrate to the solution allowing the heat and agitation to dissolve the powder. It will probably take about 10 minutes before the powder is completely dissolved and the bath changes to a clear light-yellow color. Now add sufficient clean water to bring the total solution volume up to one gallon, and then bring the solution up to the operating temperature of 200 to 210 degrees F. Do not, however, exceed the 210-degree maximum. Check the thermometer several times to be sure that the heat setting is holding the temperature constant. When it is, the stripping solution is ready for use.

During use, the stripping solution will darken noticeably and, after 2 to 3 hours of use, it will become the color of deep mahogany, or very strong tea. This is normal and doesn't seem to affect anything. Parts should be suspended on iron wire, just as in the plating process as discussed later. Do not use any other kinds of wire. Once parts are submerged in the stripping solution, they should not be removed until stripping is complete to avoid contamination.

As water is evaporated out of the stripping tank, it should be replaced. Use the dip stick method, or make a mark on the side of the pyrex tank. Do not allow parts to stick above the solution level as the fumes from the stripping solution cause very rapid rusting and pitting—which does not happen to parts that are left submerged. The rate of stripping will vary greatly depending upon the type and thickness of plate that is being removed along with other factors. Most will fully strip between 45 minutes and 1½ hours. If parts do not strip in 2 to 2½ hours, the solution is too weak and must be replenished. On some guns the nickel plate is deposited on top of a copper plate which was put on the metal first as an undercoat for the nickel. These pieces will strip slowly, and the solution will turn the copper dark in color. However, as the copper is stripped away, the dark surface will disappear and all the plating will be removed down to the bare steel surface.

Agitation of the solution is important and is done at the same rate as for plating. If the solution is not agitated, stripping will be much slower because the stripping solution (remaining close to the metal) becomes saturated with removed nickel and slows down in removing more. Fresh solution must flow by the metal surfaces at all times to distribute the dissolved nickel throughout the full gallon of stripping solution. One gallon of fresh stripping solution will remove the nickel plating from about four Colt .45 semi-automatic pistols. After this, the solution normally must be replenished. To replenish the stripping solution, first make certain that no guns or parts are in the stripping tank. Then be sure the agitation system is working and the solution is being agitated thoroughly. Also, be sure the temperature is between 200 and 210 degrees F. Add 2 ounces (by dry weight) of Concentrate 778-R to the stripping solution and continue agitation until all the concentrate 778-R is dissolved.

This replenishment will normally allow the stripping of approximately the same amount of nickel as did the original fresh solution. However, after six replenishments of the stripping solution with Concentrate 778-R, the solution will become super-saturated with dissolved nickel and will fail to strip any more. Dump the solution, wash the tank thoroughly with clean water and mix up a fresh batch.

After stripping is completed, turn off the heat, leave the solution in the pyrex tank and allow both to cool to normal room temperature while still sitting on the source of heat. If you take the pyrex tank off the hot plate and set it on a cold bench or counter top, it's possible that the thermal shock will break the tank. Once cooled, do not store the stripping solution in the stripping tank. Pour it into a clean brown plastic chemical jug. Be sure to mark the jug "STRIPPER" and "POISON." Also, label that jug as to how many times the solution has been replenished. To reuse, simply pour back into the thoroughly clean stripping tank, bring up to heat with agitation to correct operating temperature and begin the cycle.

Stripping is a slow process and, of all the sequences involved with nickel plating, it's the most worrisome, so don't expect instant results. It must work slowly so as not to pit or etch the steel.

Plating Operation

Twelve steps are required to properly plate a gun. These are outlined below and in the flow chart provided on page 199. Do not take any shortcuts. Do each in turn, as given, for the time specified. Then go on to the next step. Layout of the plating room is completely optional, but do try to set up your tanks so a logical progression from tank to tank can be done handily. (The steps to follow are for Brownell's Electroless Nickel Plating; however, further information may be obtained from Brownell's directly.)

Polishing: Polish and prepare the metal exactly as for bluing. As in bluing a firearm, plating will not hide or fill scratches or pitting. A high gloss nickel finish requires metal preparation equal to "master-grade" bluing preparation; that is, polishing right on down to No. 555 grit. A satin nickel finish can be achieved by using glass beading (very fine sand blasting), or a coarse wire scratch wheel with light pressure on the gun.

Pre-Clean: While this step is not an absolute must, it is highly recommended for best plating results. Use AWA 1-1-1 and saturated cotton swabs to thoroughly clean all surfaces areas including holes, crevices, and the like. This removes any old grease and accumulated crud, silicone oils and other gun oils plus polishing residue; especially residue left by wax- or grease-based polishing compounds. Do not use petroleum based solutions like gas, kerosene, mineral spirits or gun cleaners. If at all possible thoroughly blow all parts clean with a medium to high pressure air gun to help clean off loosened gunk.

Flowing-Water Rinse: Submerge parts in the flowing-water tank for about 10 seconds to help float away any particles of foreign matter loosened by the pre-clean step.

Pickling Tank: Submerge parts for 3 seconds. The parts will start to "gas" (similar to Alka Seltzer tablets) and this further removes any foreign contamination.

Flowing-Water Tank: Submerge in tank for 3 seconds and agitate to flush pickling solution from surface of metal.

Hot Cleaner Bath: Submerge parts in tank for 10 to 15 minutes with operating temperature at 180 degrees F. Agitate occasionally to ensure good surface cleaning.

Flowing-Water Tank: Submerge for 5 seconds and agitate to flush cleaning solution from surface of metal.

Pickling Tank: Submerge for 5 seconds to "activate" the surface of metal for plating. Parts will start to "gas" indicating surface is activated. This step, in addition to cleaning, will make the nickel "strike" the metal surface quickly assuring a good initial bonding to the surface.

Flowing-Water Tank: Submerge for 3 seconds and agitate to flush pickling solution from surface of metal.

Nickel Plate Tank: First determine thickness of the plate you wish to apply. For optimum results, ⅜-mil plating depth is considered to be the best for guns. This thickness will require 45 minutes of submersion in the plating solution.. Start the agitation system and submerge the parts to be plated into the plating solution. (Make sure they do not touch each other or the sides of the tank.) Be sure that agitation is thorough, and that whirlpooling does not develop. The solution must operate between 190 and 195 degrees F. optimum. Once the pieces are in the plating solution, do not remove them until the desired length of time has elapsed. If you do, even for an instant, you will ruin the plating job and have to start over. When the predetermined time has elapsed to plate the thickness desired, remove the parts from the plating solution.

Flowing-Water Tank: Submerge the parts for a minimum of 2 minutes and agitate to flush the nickel solution from the metal surface. There is no maximum time limit in this tank as the nickel plating process has been completed. Remove the parts from tank and allow them to dry normally or use compressed air for faster drying.

Inspection: Check all parts and components carefully to assure an even plate of all desired surfaces prior to assembly of the gun. However, if a part or component is not nickel plated as desired, it cannot be put back into the nickel tank. The part must be stripped of all nickel and reprocessed from bare metal! If all parts and components are satisfactory, wipe all parts clean and dry with a soft cloth to remove water spotting or lingering wet areas in holes, etc. If a high-gloss finish is desired, you can buff the parts lightly on a loose muslin wheel to bring up the luster, or use a Professional Nickel Final Polishing Cloth. If the buffing wheel is used, use only No. 555 white Polish-O-Ray *and very light pressure* as any form of polishing will remove metal, and you will be removing the nickel plate you just put on. Simichrome polish can also be used to increase the luster of a high gloss finish. Reassembly of the gun is the final step.

The complete plating procedure consists of two phases, both equally important. First is a preparation of the metal to enter the plating solution and second, the actual plating of the metal. Any attempt at short cuts in the procedure usually results in a poor plating job, wasted time and material. At first the process will seem lengthy, especially the cleaning steps prior to putting the piece into the plating tank. However, with a little practice you can complete the plating process in about the same amount of time required for a good blue job.

The preparation phase is a step-by-step sequence in getting the metal absolutely clean of all foreign residue and down to the bare metal. When metal is stripped of all protective coating, it absorbs oxygen and oxidizes very quickly when in the open air. Oxidation on the metal surface prevents good initial bonding of nickel to metal. Therefore, the time between each step should be as short as possible. Work quickly but at a steady pace between each step. Timing in the tanks, in seconds, does not require a stop watch. If you say the words, “One thousand and one” it takes one second. Hence “one thousand and one, one thousand and two, one thousand and three,” will take three seconds. Try it, it works.

Equally important is the flushing step between each tank. It prevents the carrying or “drag out” of chemicals from one tank to another tank with resulting chemical contamination of the second tank.


ELECTROLESS NICKEL PLATING STEPS
1 POLISH
2 PRE-CLEANER
10 seconds
3 FLOWING WATER TANK
3 seconds
4 PICKLING TANK
3 seconds
5 FLOWING WATER TANK
10 - 15 minutes 180°
6 HOT CLEANER BATH
5 seconds
7 FLOWING WATER TANK
5 seconds
8 PICKLING TANK
3 seconds
9 FLOWING WATER TANK
45 Min. for 3/8-mil 195°
10 NICKEL PLATING TANK
2 minutes
11 FLOWING WATER TANK
12 INSPECTION
NICKEL STRIPPING STEPS
1 PRE-CLEANER
10 seconds
2 FLOWING WATER TANK
3 seconds
3 ACID CLEANING TANK
5 seconds
4 FLOWING WATER TANK
Until Fully Stripped 200°
5 NICKEL STRIPPING TANK
2 minutes
6 FLOWING WATER TANK

TROUBLESHOOTING CHART

MALFUNCTION	
Probable Cause	Remedy
NEW BATH DOES NOT PLATE	
1. Improper make-up.	Bring bath into specs if can determine mistake. If not, discard bath.
2. Incorrect bath volume.	Adjust bath if can do so correctly. If not, discard.
3. Temperature too low.	Check Thermometer; heat source. Must operate between 190 - 200°F with 195°F optimum.
POOR SURFACE ACTIVATION	
1. Acid too old or too weak.	If so, remake.
2. Oil contamination in tanks.	Find source, clean up, then remake all baths.
3. Poor rinsing between cleaning steps.	Increase agitation or water flow.
4. No nickel strike on stainless steel or hardened steels.	See special note on “Wood's Nickel Strike” to activate surface.
“SMUT” FORMS ON SURFACE AFTER PICKLING	
Result of over-activation of surfaces by pickling solution.	Wipe off parts with cloth and repickle for shorter time and/or reduce strength of pickling solution.
CONTAMINATIONS	
1. Check for galvanized, aluminum, copper or brass in tanks, racks, hanging wires, stir rods. Check for leaded steel, heavily soldered or brazed parts.	Discard contaminating metals & remake baths.
2. Residual acid left from stripping.	Generally will have to discard bath.
3. Containers, mixing cups, stir rods, etc. mixed between plate bath, cleaning bath, pickle bath.	Generally have to discard solutions. Always use separate mixing/measuring cups and label for which bath used.
RAPID DEPLETION OF A-1, B-1, 778	
Poor chemical reaction: result of storage below 50° F.	Return to solution as described below. Ideal storage is 60° - 90° F.
WORKING LIFE DEPLETES TOO SOON	
Plating solutions stored in tanks, open containers, and not light proof containers.	MUST ALWAYS be kept in dark brown chemical jugs when not actually in use to. preserve working life.
SURFACE ROUGH WITH SCRATCHES	
Probably not polished to fine enough grit before plating.	Plating will not hide anything!
ROUGH AND SCRATCHY SURFACE	
Dirt on surface of metal entrapped under plating.	Strip, realty clean this time and replate.
“PEBBLEY” SURFACE	
Plating solution agitation too slow.	Increase speed to just before cavitation or whirlpooling starts. Surface can be cleaned up with 555 White polish on loose muslin wheel and very light pressure.
“CRATERED” SURFACE	
Plating solution agitation too fast.	Slow down agitator with speed control. Part must be stripped and replated. Will not polish out.
“SANDY” ’SURFACE	
Took part out of plating bath and put back in during plating cycle.	Do Not Remove Parts Once Put into Plating Tank. You will get a “false plate” which must be stripped and replated if careful polishing does not remove.
DISCOLORATION ON SURFACE	
1. Shaded “grey” streaks caused by parts touching, hanging loops too tight, too large a part in too small a tank.	Use larger tank; run more than one batch. Use “O” shaped hanging loops.
2. Adding water during time part is in plating tank.	Water to top-off volume can be done only when no parts are in plating tank; then temperature must be restabilized to 195°F.
SMEARS, STREAKING	
Surface not clean.	Remember, Clean - Clean - Clean and Clean again. Strip and replate.
PLATING CAME OFF	
1. Surface not clean.	Strip, reclean and plate.
2. Tried to plate Stainless Steel or hardened steels.	See special note on “Wood's Nickel Strike” to activate surface.
3. You took it out of the plating bath to look at it and put it back in for some more plating.	You cannot do this for it will “false plate” and may come off. Strip and replate.
PLATING TOO THIN	
1. Tried to plate with depleted solution.	Check mil-usage record on storage jug. Make new solution then strip and replate.
2. Check surface area-to-volume of plating bath ratio. 1 gallon does only 114 square inches ½-mil thick.	May require larger container and more solution volume.
PLATING TOO THICK	
Too long in plating bath.	Reduce time in plating bath. 1 hour gives ½-mil; 45 minutes gives ⅜-mil; ½ hour gives ¼-mil. Generally thick plating can be polished off with 555 White on loose muslin wheel adjusting pressure and checking fit often. Be sure not to cut thru plating.
CASE HARDENED/CAST STEEL PLATES UNEVENLY	
1. Many Case hardened surfaces do not activate as well as unhardened steels.	Leave in pickle tank longer than normal until good gassing occurs.
2. High silicone content of some cast steels may inhibit plating.	Pre-clean to the point of “over-kill” with Trichloroethane to remove silicone.
3. Cast parts will usually not polish well enough for “Bright” Nickel Plating.	Suggest sandblasting cast surfaces before plating for a deluxe “Satin” Nickel Finish.

If you can blue guns, you can plate guns. It’s only a matter of familiarization and practical experience. The major difference is that plating requires extreme measure to assure parts are clean prior to entering the plating solution. As with all types of metal finishes, it is best to make a test run by using scrap parts until you become familiar with the process instead of making the first plating job on a new gun. According to Brownell’s, the most common cause of poor plating jobs can be directly traced to lack of cleaning or contamination of solutions.

It is possible to plate one or two parts for two hours and give them a one-mil plate build-up if desired. This can occasionally be done to tighten up loose fitting screws, pins and other slightly worn parts. Plating past this one-mil thickness is not practical. And, be sure to remember that every surface will receive the same amount of plate and increase by the same thickness. So, while you may tighten up threads of a screw, you may also keep the head from fitting flush, or fitting the counterbore at all.

Agitation of the plating solution is critical for too great an agitation will result in whirlpooling, which draws air into the plating solution. This extra air will "crater" the nickel plating being put on the metal surface and you will have to strip the piece and start over because the poor plating cannot be saved. Too little agitation will result in "pebbling" of the plated surface (little humps and random bumps). This is more easily remedied, for the part need only be polished carefully with 555 white Polish-O-Ray on a loose muslin wheel to remove the "pebbles."

Sand blasting of parts prior to plating is one of the most universally appealing finishes you can give your guns. Especially consider decorative use of sand blasting; for instance, sand blast the entire cylinder, then polish just the outside back up to bright, leaving the flutes sand blasted. Once plated, the contrast between bright and satin is very handsome.

Polishing prior to plating is more important than you can realize as you read this chapter. Every scratch, rough spot, wobble or nick is highlighted by the plating; it will hide absolutely nothing, not even those things bluing will sometimes hide. So, consider the satin finish if you don't want to go to the trouble of doing the high degree of polishing required for a mirror-bright finish.

Do not mix and add more fresh plating solution to a partially used batch. This is a tempting idea, but don't do it, for you then lose track of the plating capacity of the total solution.

Solution heat-up in the pyrex tanks can be greatly hurried by making a "tank jacket" from fiberglass furnace duct insulating panels. Cut those panels to fit like an open-ended box and seal the corners with duct tape. Make a lid from a pyrex glass sheet or hi-temp plastic, and be sure to use that lid on any enamel tanks. It will cut evaporation and shorten heat-up time.

Because of the acids used, parts not directly under the surface of the plating bath will rust badly—worse than in the bluing room. The small amount of water that condenses on hanger rods and falls back into the plating bath is of no consequence. But, do take precautions by keeping all easily rustable equipment and items out of the plating room.

If you are working on a rusty gun that you want to put through a rust or bluing remover solution, you must do so before you polish the gun. Most removers contain phosphoric acid which acts as a "passifier" to steel, and will prevent it from plating. Polishing will remove this passified surface, so you must polish thoroughly and completely. Then the pre-cleaning, pickling and cleaning steps in the plating sequence should properly "activate" the steel surface. If you notice that the part does not "gas" in the pickling tank immediately, you may have to leave it in for a few more seconds to be sure that the surface is sufficiently activated for the nickel plating to "strike" the surface and adhere correctly.

The troubleshooting chart provided in this chapter will help you to correct problems that may arise when using Brownell's Electroless Plating Method. When the chart advises to "strip and plate," it does not mean run the part through the stripper and then directly back into the plating tank. It means to take the part through the stripping sequence, then through the entire 12 steps of the plating sequence! If you skip a step and put a dirty part back into the plating tank, it will not plate correctly that time either. *You cannot skip any step of any sequence.*

Most of the material in this chapter came from Brownell's instructions for plating firearms which were compiled by Ralph Walker and the crew at Brownell's. We are, indeed, indebted to them.

19 - GUNSMITHING: CONTINUING EDUCATION

GUN REPAIR isn't something you can learn quickly by simply buying a few tools, studying a couple of gunsmithing books, and then start tearing your favorite pride-and-joy apart. Not that it isn't possible to teach yourself this way, but you'll save a lot of time—not to mention spoiled work from trial and error—if you start with some professional instruction.

Ideally, the best way to learn gun repair is to attend one of the bona fide gunsmithing schools. Some of them include:

Colorado School of Trades 1545 Hoyt Lakewood, CO 80215
Lassen Community College P. O. Box 3000 Susanville, CA 96130
Montgomery Technical Institute P. O. Drawer 487 Troy, NC 27371
Murray State College Tishomingo, OK 73460
Oregon Institute of Technology Small Arms Dept. Klamath Falls, OR 97601
Pennsylvania Gunsmith School 812 Ohio River Blvd. Avalon, Pittsburgh, PA 15202
Trinidad State Junior College Trinidad, CO 81082

For some of you, attending one of these colleges or schools may not always be possible. You have to earn a living and therefore, full-time instruction is out of the question. In this case, you may find that one of the home study schools can solve the problem; location, working hours, age, and educational background provide no barriers for the serious, motivated home study student. Furthermore, a person taking a home study course can progress at his own pace—as fast as he or she can master the lessons or as slowly and irregularly (within reason) as necessary. Two gunsmithing correspondence schools are:

Modern Gun Repair School 4225 North Brown Avenue Scottsdale, AZ 85251
North American School of Firearms 4500 Campus Drive Newport Beach, CA 92663

Another way to learn the profession is to work as an apprentice under a professional gunsmith, but most firms are not too eager to hire a person as an apprentice unless he knows a little basic gun repair already; that is, they should be able to start earning the firm money at the beginning.

Any person who finishes any of these courses and obtains a comprehensive reference library (and knows how to use it) should have the basic knowledge required to start in gun repair work. What follows is a look at the curriculum's of two on-campus gunsmithing schools and a review of the courses offered by two correspondence schools. As a gunsmith, I'm constantly asked about the courses these schools offer; the following will, indeed, give you an in-depth look at a few solid gunsmith training programs.

Montgomery Technical Institute

Montgomery Technical Institute is located in Montgomery County in the Piedmont section of North Carolina. Montgomery (a rural area) is in the hunting and fishing center of the Uwharrie Reservation. Approximately 75% of the county's 488 square miles is forest. (The Uwharrie National Forest encompasses over 46,000 acres.) Montgomery is the home of at least 21 hunt clubs and three bass fishing clubs.

Troy, the county seat, is less than 100 miles from the major cities of Charlotte, Durham and Winston-Salem. Montgomery Technical Institute is accredited by the Southern Association of Colleges and Schools and the North Carolina State Board of Education. The school provides day or night classes, financial aid and is approved for veterans.

The gunsmithing curriculum at MTI provides the student with instruction in metal machine operation, metallurgy, finishing, and woodwork. Specific instruction focuses on the use of hand and machine tools in metalwork: lathes, milling machines, bench grinders and surface grinders. Additionally, the gunsmithing student learns the principles of buffing, polishing and bluing; inlays, checkering and finishing stocks; barrel fitting and chambering. Repair work, consisting of diagnosis and correction of problems, is greatly stressed since this work is a substantial source of income for the gunsmith. Once these gunsmithing skills are learned, instruction focuses on the methods of manufacturing rifle, handgun and shotgun ammunition.

The gunsmithing curriculum consists of 24 months of study, divided into eight quarters of eleven weeks each. Classes meet 27 hours per week. At the conclusion of study, the student will not be a master gunsmith, but he will be a very advanced apprentice prepared to work with a master or establish his own shop.

The "art" of hot bluing is taught at all of the gunsmithing schools.



Lathe operation is also part of what the gunsmithing student will learn at one of the professional schools.

First Quarter
GSM 1001 (Gunsmithing I)

Introduction: The introductory period will familiarize the student with the use of hand tools as he begins metal work. With metal files and hacksaws, each student will make a center gauge, drill gauge, butt plate templates and pistol grip templates for future use. As he works, he will be taught blueprint reading and layout and will become proficient in transferring dimensions from blueprint to metal.

Since patience and precision are two of the most important qualities of a gunsmith, this period will give the instructor the opportunity to appraise the student's abilities. Depending on the ability of the individual, this phase should require about 54 hours of classwork.

Introduction to Machine Tools: Students will learn the basic skills involved in operating lathes, milling machines, bench grinders, surface grinders and the drill press. They will be taught the principles of operation and set-up of each machine. Safety measures will be stressed at every step of operation. As the student learns to properly use the machine tools, he will learn to correctly sharpen tool bits and drill bits.

Second Quarter
GSM 1002 (Gunsmithing II)

Machine Tools: Machine tool operation will continue and become more specialized as the students participate in the selection and manufacture of basic hand tools. Jigs and fixtures common to the trade. They will be given blueprints to read and interpret to make jigs, fixtures (holding devices), and specialized tools for use during the learning process and in future employment. The following projects will be required:

Bolt forging blocks
Bolt welding blocks
Barrel vise
Bushings
Action wrench and bolts for action wrench (2)
Bolt forging inserts
Adapter for action wrench for Remington, Savage, and Jap
Rear guard screw drilling jig
Buttstock clamp for shotgun inletting
Burnishing reamer, .22 Rim Fire
L. C. Smith mainspring compressor
Spanner wrench for pump shotgun fore-ends
Spring-winding fixture
Colt ratchet wrenches
Soldering clamp for front ramps
Colt crane extractor bushing wrenches (3)

Swivel counterbores (2 sets)
Revolver frame wrenches (5)
Reamer extensions for Clymer reamers (2)
Reamer wrench for chambering
Barrel centering tool for crowning
Barrel spinner
Action mandrels for barrel spinner (2)
Front guard screw bushing counterbore
Mauser guard screw counterbore
Turning rings for rifle barrel shanks (6)
Checkering cradle
Drift pin block
Shotgun magazine tube dent remover
Bushing Wrench, .45 auto

Oxyacetylene welding, soldering, brazing, hardening and tempering of metal will be taught in conjunction with completing the projects. This segment begins with lectures on nomenclature and safety procedures and continues through individual instruction in using the oxyacetylene torch. Successful completion of projects in butt joint, lap, fillet, built-up and bolt welding, soft soldering, silver soldering and brazing are required.

Heat treating of steel, including hardening and tempering, will be taught. Students will use the electric furnace to heat-treat under controlled temperature and the oxyacetylene torch and forge for visual heat-treat by watching the color of the steel.


Heat treating of certain gun parts is something the professional gunsmith must learn; either at the elbow of a master, or, at one of the professional schools.

Stock making and inletting are vital parts of learning the gunsmith's trade. This student is inletting a trigger guard in a stock blank. Note the carpet-padded bench.

Third Quarter
GSM 1003 (Gunsmithing III)

Bluing of 10 firearms will be required. Students should obtain firearms that are in good operating condition as repair work will not be permitted in this phase of the course. These should consist of two-bolt action high power rifles, two pump shotguns, two semi-automatic shotguns or rifles, and two handguns. In addition, two double barrel shotguns will be included to teach the rust bluing method.

Buffing instruction will involve the use of the four-wheel method and the belt sander. In addition to buffing, polishing, and bluing procedure and formulae, this unit will include the operations, construction and maintenance of modern firearms in the commercial field. Various actions and their principles will be explained as students disassemble and reassemble firearms. Two methods of bluing, *Baker* and *Immersion*, and the formula and procedure for each, will also be taught.

Fourth Quarter
GSM 1004 (Gunsmithing IV)

Stocks: Students will begin by learning about the types of wood suitable for stocks and the reasons for their suitability. The choice of wood will be determined by individual preference.

Students will construct two sporting rifles custom made from stock blanks and one sporting rifle custom made from a semi-inletted stock. Construction of these three rifles is required. During the process, they will be taught the correct procedures for inletting by the use of hand chisels and rasps for the first rifle. Use of the router will be introduced in the construction of the second rifle. Using different colors and varieties of wood, students inlay designs of their choice in rifle stocks.

Checkering is an important step in stock construction. Students will learn to lay out checkering patterns and to transfer these patterns to the wood with proper checkering tools, using both hand tools and a power checkering head. This unit includes refinishing old stocks as well as finishing new ones. Students will learn to correctly remove old finish, sand, and apply new finish. They will sand, seal and hand rub to bring out the natural color of the wood. Oil, lacquer, and varnish finishing methods will be taught.

Fifth Quarter
GSM 1005 (Gunsmithing V)

Stocks: Students will use the procedures learned in constructing rifle stocks and will construct one each of the three basic types of shotguns: stock bolt, box lock, and side lock stocks. As shotgun stocks are in two pieces, students will construct butt stock, s and forearms. Forearm construction will include standard type and beavertail.

Custom handgun grips for revolvers and semiautomatic handguns will be made. The student will also learn to install contrasting wood, fore-end tips, and pistol grip caps. Finishing will be done according to procedures learned the previous quarter. Installation of recoil pads is also taught.

Sixth Quarter

GSM 1006 (Gunsmithing VI)

Barrel Fitting and Chambering: Students will learn to thread barrels, chamber, and set proper head space for military and commercial actions, and to adjust head space on rifles that need head space corrections. They will learn to correctly crown rifle barrels in the standard crowns and target crowns. This unit will also include taper turning to change the diameter of barrels, and contouring to replace old barrels with new barrels having the exact dimensions.

Students will be taught to install poly-chokes and to modify existing chokes on shotguns. Installation of poly-choke ribs will also be included. Depending on individual ability, this unit should require about one month of class work to complete.



This student is setting up a lathe for a chambering job.

Sight Mounting: Approximately two weeks of class will be spent on installation of scope mounts. This will include two-piece mounts, one-piece mounts, side mounts, and target mounts. Students will learn to install receiver sights and open sights, and must be able to cut dovetails in the barrel for the installation of sights on rifles and handguns. They will also be taught how to bore sight in the shop and how to install shotgun beads.

Introduction to Repair Work: Since repair work is the gunsmith's major source of income, emphasis will be on diagnosis and correction of malfunction problems, manufacture of parts and the installation of factory parts. For the remainder of this quarter, students will begin to repair firearms. The instructor will verify each diagnosis and procedure for repair before any work is done. All repair work will then be double checked by the instructor and must be done to his satisfaction.

Seventh Quarter

GSM 1007 (Gunsmithing VII)

Students will continue to diagnose and correct malfunction problems under the direct supervision of the instructor. They will be given progressively more advanced problems to solve and more complicated parts to manufacture.

Students will be instructed in accurate record keeping of time and expense involved, particularly concerning the manufacture of parts in the shop. The instructor will continue to verify malfunctions, diagnoses, and procedure for repair, and double check to be sure the work is properly done.

Eighth Quarter

GSM 1008 (Gunsmithing VIII)

Students should have enough experience and training to quickly recognize common malfunction problems and should be able to work with a minimum of supervision.

The instructor will continue to verify malfunctions, diagnoses, and procedures for repair and double check to see that the work is properly done. The more time students spend in practice and repetition of repairs, the more proficient and skilled gunsmiths they will become.

Gunsmiths are required to have a Federal Firearms License. There will be class lectures and instructions on procedures for applying for this license and the necessary record keeping involved to satisfy the requirements of the Bureau of Alcohol, Tobacco, and Firearms. In anticipation of opening his own shop, the student will be instructed on applying for and obtaining various city, county, and state licenses required, and the federal, state, and local laws governing the establishment of a gunsmith shop and the sale of firearms. On file in the classroom will be copies of firearms legislation from each state.

Reloading: Approximately one week of the final quarter will be spent learning to assemble reloading components into rifle, handgun, and shotgun ammunition. Students will also review ballistics, bullet weights and powder charges.

Special Note on Related Courses

Gunsmithing students will be required to take communication skills, human relations, and one elective before they are eligible for graduation. Also, they may be required to take a course in the fundamentals of mathematics if such a need is determined. Additionally, students in gunsmithing may take courses in beginning typing, small business operations, business law, small business taxes, the metric system, and any other course that is taught in the individualized instruction center in which they might have an interest. The students may take these courses at their convenience.

The student will be required to obtain the following tools during the periods indicated.

Introduction:

1. Tool box (such as Kennedy Machinists Chest 526)
2. 6″ steel rule

3. Scribe
4. Hacksaw (18 teeth per inch)
5. Flat file 6″
6. Flat file 8″
7. Flat file 10″
8. Half round file 10″
9. Triangular file 4″
10. Triangular file 6″
11. Needle file set
12. File card (file cleaning brush)
13. Machine tools textbook

Bluing:
1. Ball peen hammer 8 oz.
2. Plastic tip hammer 6 oz.
3. Pin punch set (4 piece)
4. Brownell’s screwdriver and tips, #81 solid handle
5. Pin vise
6. Safety glasses

Stock Tools:
1. Wood chisel set
2. Surform round
3. Surform half-round
4. Surform blase—flat
5. Cabinet rasps 8″
6. Cabinet rasps 10″
7. Cabinet rasps 12″
8. Half-round bastard cut 8″
9. Half-round bastard cut 12″
10. Round file 6″
11. Round file 8″
12. Stock wood—2 blanks
13. Semi-inlet stock (1)
14. Tip wood (3)
15. Actions (3)
16. Barrels (3)
17. Shotgun blanks (3)
18. Block hand sander
19. Sights
20. Recoil pads
21. Sling swivels

Machine Tools (optional):
1. 0-1 micrometer
2. Lathe centergauge
3. V-thread gauge

At all of the gunsmithing school's, the students have a full opportunity to discuss the progress being made on a particular project with their instructors.

In this instance the instructor is discussing the merits of a student s repair job on a Winchester pump action rimfire.

Colorado School of Trades

The Colorado School of Trades was founded in Denver, Colorado, on July 15, 1947. The school has given students interested in guns the opportunity to learn "gunsmithing" in a reasonable amount of time. To learn gunsmithing would take many years of apprentice training. The Colorado School of Trades has grown and expanded over the years and is considered by leaders in the firearms industry to be one of the finest schools of gunsmithing in the country.

At the present time the school is situated in Lakewood, a suburb of Denver. The area is in the heart of a business district which affords students the opportunity to seek employment while attending school. The Institution is situated in a 18,500 square foot building; approximately 15,000 square feet is devoted to shop area. The building has fluorescent lighting throughout the shop, classrooms and office areas. The building is heated by natural gas and ample doors and windows provide adequate ventilation.

Included in the school's equipment is a 42 unit power machine shop, bluing department, 164 metal student work benches, a handloading room that is equipped with up-to-date equipment for teaching handloading of ammunition and a student library. Welding benches are provided for teaching eight students at a time, with complete oxyacetylene welding equipment. For heat treatment, a 3.4, kw electric furnace is provided for heat treating carbon steel. The work bench facilities and equipment accommodate 164 students per session; however, there are additional benches for miscellaneous purposes. Classrooms, which accommodate 40 students at a time, are available for class lectures and course theory.

An annex building is provided that contains 4,200 square feet of shop space and an air-conditioned classroom. Included are 100 steel work benches, eight power machines and gun bluing equipment, all lighted by fluorescent lights. The annex can accommodate 100 students at a time. The Colorado School of Trades' philosophy is; "To teach the design, function and use of different types of small sporting arms, their repair, making of parts, proper shop procedure and techniques to prepare students to conduct their own business or as employees in the gunsmithing trade."

The Colorado School of Trades' curriculum is as follows:

Related Subjects
(Class Room 1 hour per 9 hours of shop time)

1. Orientation and General Safety 4 hours
2. Hand Tools 5 hours
3. Mathematics 6 hours
4. Blueprint Reading 10 hours
5. Drills, Taps and Sharpening 10 hours
6. Grinding, Sanding, and Polishing 10 hours
7. Gun Bluing and Browning 10 hours
8. Stockmaking 18 hours
9. Ballistics and Handloading 15 hours
10. Use of Firearms Theory 5 hours
11. Gun Sights 7 hours
12. Welding 12 hours
13. Heat Treatment 10 hours
14. Engine Lathe 20 hours
15. Milling Machine 5 hours
16. Universal Grinder 5 hours
17. Design and Function 65 hours
18. Trigger Assemblies 5 hours
19. Conversion 20 hours
20. Business Training 20 hours
21. Special Hand Tools 5 hours

Related Subjects
Total Hours (approximately) 267

Shop Operations (7 hours per day)

22. Bench 300 hours
23. Drill Press 25 hours
24. Grinding, Sanding Polishing 24 hours
25. Gun Blue and Brown 225 hours
26. Stockmaking 500 hours
27. Handloading 12 hours
28. Welding 100 hours
29. Heat Treatment 25 hours
30. Use of Firearms Practice 30 hours
31. Engine Lathe 185 hours
32. Milling Machine 24 hours
33. Universal Grinder 8 hours
34. Barrel Fitting and Headspacing 35 hours
35. Gunsight and Mounts 15 hours
36. Chokes 10 hours
37. Bolt Action Guns 100 hours
38. Single Shot Guns 30 hours
39. Lever Action Guns 60 hours
40. Pump Guns 170 hours
41. Auto loader Guns 200 hours
42. Double Barrel Guns 150 hours
43. Black Powder Guns 30 hours
44. Revolvers 100 hours

45. Auto Pistols 100 hours
46. Trigger Assemblies 20 hours
47. Conversions 25 hours
Shop Operations
Total Hours (approximately) 2493
Total estimated hours for the course (approximately) 2760

Assembly and disassembly of firearms is an important part of any gunsmithing student's course of study.

Correspondence Gunsmithing Schools

The only two gunsmithing correspondence schools that I know of at the present time are Modern Gun Repair and North American School of Firearms. Of course, there are scores of correspondence courses offered by colleges and universities throughout the country that fit in very nicely with the gunsmithing profession: welding, lathe operation, machine shop courses and blueprint reading are just a few. Most of these earn the student credit toward a degree. But let's concentrate on the two schools offering courses solely in gunsmithing.

In examining sample lessons supplied by Modem Gun Repair School and North American School of Firearms, each showed strong and weak points which were balanced out by similar variations in the other. Both schools are approved by the Veterans Administration for GI training, and both have a staff of well-known professional consultants—P. O. Ackley, Ralph Walker, etc. Also, time-payment plans are available at each.

Courses for both schools are surprisingly complete, well thought out and well written, but neither of the schools' courses are capable of turning out a finished gunsmith any more than any college or university. What these courses do offer is an educational background in gun repair and ballistics, confidence and judgment as to what jobs the students are capable of performing. Who could ask for more?

Modern Gun Repair School

Modern Gun Repair School is now operated by Mr. and Mrs. John C. Kadon in Scottsdale, Arizona. The total course consists of 40 lessons covering everything from setting up shop, stock finishing, checkering and carving and lathe lore to bluing, jewelling and polishing—even bookkeeping and advertising. A consulting service is provided for students on any gun repair problem at no additional cost.

Modern Gun Repair School has some excellent lessons on firearm disassembly and the remaining lessons were adequate to give the student a background in the subjects covered. The main drawback in the lessons I examined was the lack of suitable illustrations. Lesson 36A, for example— on inletting, fitting and shaping of stocks—was well written and accurate, but the lack of illustrations made some of the points hazy. I doubt that a student who had never inletted a stock previously could complete a stock just by reading the lesson. However, I understand that the school has recently hired Ms. Kathy Desmond to illustrate all the lessons, and if the quality of these illustrations compares with the quality of the present text, this course is going to be hard to beat by anyone.

Tests are completed after each lesson and mailed to the school where they are graded by instructors Lour Kaar and Jack Burger. I would have preferred to have seen a little more comprehensive exam, but like their brochure says: "The knowledge gained by this course is more important than the grade you get."

North American School of Firearms

When Leonard Valore, Director of Educational Services at North American School of Firearms, shipped a package of sample lessons to me, opening it was a pleasant surprise. There was Brownell's Catalog, information on how to obtain a Federal Firearms License, and loads of other goodies. The lessons were well written, factual and extremely well illustrated—leaving little doubt as to what the lessons were trying to get across.

Right off the bat, Unit 1 goes into gun bluing and the explanation of "hot water" bluing is the best I've seen anywhere. The same unit continues with detailed information (drawings and text) on building a suitable work bench for gun repair work. The lessons to follow cover ballistics, troubleshooting handguns, shoulder arms, and black powder firearms; converting military weapons to sporting arms; firearms design, checkering, stock finishing and business administration.

All of the material examined was very easy to read and understand and the many illustrations created interest throughout. NASF also provides the student with a basic set of tools, a subscription to Shotgun News, and a lifetime consultation service.

Any person who finishes either of these courses and who obtains a complete reference library (and knows how to use it) should have the basic knowledge to make any gunsmithing firm a good employee. Some of the students may even step right into a business of their own.

20 - INTRODUCTION TO PRO GUNSMITHING

THIS CHAPTER is directed mainly toward the prospective gunsmith. However, the problems of sufficient cash and credit, tools and equipment, shop location, layout and costs, as well as obtaining required training would no doubt be of great interest to the existing professional also.

Prerequisites of a Gunsmith

Gunsmithing can be a profitable business, but before entering into such a venture, one must be familiar with all the essentials for successful operation. There are many hazards of getting started— many more than most people realize—and the sooner the potential gunsmith realizes this, the sooner he will be able to operate the business with reasonable smoothness and impunity.

A person who is considering entering the gunsmithing business must first take a long hard look at himself to determine if he is in fact qualified to handle such a business. If he is not satisfying his current employer, chances are he won't satisfy his future customers in the gunsmithing business. On the other hand, a person who doesn't mind long hours and hard work and who has proven that he has a good knowledge of firearms and repair techniques, is familiar with modern shop practices and is able to get along with people, at least has one foot in the door.

Still, just because a person may be proficient in the operating principles and repair techniques of firearms doesn't mean that he is guaranteed success in the gunsmithing business. Too often, people emphasize their strong points and fail to recognize their weak ones. For example, a person may be an excellent machinist, a stickler for detail, and have a good knowledge of troubleshooting and repair of all types of firearms but, owing to lack of sufficient financing, executive ability, or general knowledge of the business, he is not qualified to operate a gunsmithing firm.

The requirements of a person entering the business are many but, aside from a knowledge of firearm repair, refinishing and maintenance techniques, *confidence* and *enthusiasm* are probably two of the most important traits a potential gunsmith can have. With confidence in himself and enthusiasm to conquer obstacles and make the business run on a profitable basis, most levelheaded, well-trained gunsmiths will have a chance.

The prospective gunsmith should further have a good knowledge of firearm regulations (federal, state and local), a relatively good knowledge of firearm design, reasonable mathematical ability, the ability to accomplish goals through men (not by men), the willingness to make sacrifices, a knowledge of cost estimating and a good knowledge of business fundamentals. Any prospective gunsmith who lacks any of the above-mentioned requirements should take steps to acquire them.

Learning the Basic Fundamentals

Gun repair isn't something you can learn quickly by simply buying a few tools, studying a couple of gunsmithing books, and then start tearing your favorite pride-and-joy apart. Not that it isn't possible to teach yourself this way, but you'll save a lot of time—not to mention spoiled work from trial and error—if you start with some professional instruction. Ideally, the best way to learn gun repair is to attend one of the bonafide gunsmithing schools.

For some of you, attending one of these colleges or schools may not be possible. You have to earn a living and therefore, full-time instruction is out of the question. In this case, you may find that one of the home study schools can solve the problem; location, working hours, age and educational background provide no barriers for the serious, motivated home study student. Furthermore, a person taking a home study course can progress at his own pace—as fast as he or she can master the lessons or as slowly and irregularly (within reason) as necessary.

Another way to learn the profession is to work as an apprentice under a professional gunsmith, but most firms are not too eager to hire a person as an apprentice unless he knows a little basic gun repair already; that is, they should be able to start earning the firm money at the beginning. Any person who finishes any of these courses and who obtains a comprehensive reference library (and knows how to use it) should have the basic knowledge required to start in gun repair work.

Proper Direction of Personnel

Most gunsmithing firms start out as a one-man operation, and this is how it should be. Expenses are kept to a minimum until the business starts to gain momentum. Eventually, however, a shop that does good work is going to be swamped with work and a decision will have to be made whether to start turning down work or hire additional personnel. Both ways have their advantages and disadvantages. The person who chooses to remain a one-man operation and turn down excessive work will continue to keep operating expenses down and probably have less worries and financial difficulties; but, if and when he decides to take a vacation, the business and work will have to stop. Furthermore, if he continues to turn down work, ill feelings may result and the local people take their business elsewhere. Eventually, his work may become slack, and he won't have enough to support even his one-man operation.

The person who decides to hire additional personnel will have more freedom (if he hires the right people) to take care of the business end of the operation; take a day off occasionally to fish for that lunker bass in a nearby stream, and to be the "front" man for the firm. He will also be able to get the work out faster, providing better relationships with his customers. But the financial burden is going to be greater. His employees have bills to pay and will have to be paid regularly and on time. If work gets slack for a few weeks, the employees payroll will have to go towards overhead if no profits are made.

Since a large gunsmithing operation entails getting a gun repair or refinishing project completed in the shortest possible time, in a workmanlike manner, and with the least possible expense, it follows that the man leading such an organization must be a rather highly qualified person. What are some of the qualifications of a gunsmith in regard to directing personnel? First, the gunsmith must be a leader. Not one who merely gives orders, but one capable of stimulating job interest and have his men turn out a good job not necessarily because they have to, but because they want to.

Ideally, the gunsmith should have the ability to do almost any gun repair job as well as, if not better than, the men under his supervision. There are some exceptions. A firm may hire an expert engraver to boost the services offered by the firm. Since gun engraving is an art in itself, the owner of the shop would not be expected to perform work as well as the master, although the master is being paid by the owner. The gunsmith should further be an organizer with the ability to organize his men, equipment and materials in an orderly manner that will produce maximum efficiency. His judgment should inspire confidence and his character should be above reproach. There are also other factors like education, physical and emotional stability, interest in the morale and welfare of his men—all of which encourage the men to respect the gunsmith, enabling him to properly direct them better.

Knowledge of Cost Estimating

In general, estimating the cost of gun work is the determination of a sound cost and proper price for a given project in advance of performing the work. While no estimate can be absolutely correct to the penny (except by accident), most can be surprisingly close to the actual cost of the project. The procedures necessary in making an estimate of a gun repair consist of calculating the necessary materials, parts, etc., and then adding labor and direct job expenses to arrive at an estimated cost. To this, overhead and profit are added to arrive at a bid price.

Those who perform gunsmithing estimates must also be aware of the many job factors that will vary from job to job. For example, a badly pitted barrel on a Winchester Model 70 in for rebluing is going to take more time than the same model gun that has no pits. The gunsmith must also take into consideration the depreciation and consumption of tools, purchasing expenses, interest on borrowed money, and so on.

Sufficient Cash and Credit

Many gunsmiths, especially those starting out in their homes, have been able to get started on less than $1,000 cash. However, for a business of any size, $10,000 to $25,000 cash should be considered the absolute minimum. There are many who have tried starting a business in gun trading and repair on less than this amount, using credit almost entirely, but many of them are still trying to get started.

Besides the cash mentioned previously, the gunsmith should also have a line of credit equal to three months' operating expenses. Therefore, if the average monthly operating expenses is $4,000, the gunsmith should have a line of credit equal to about $12,000. This is usually going to take security, and often means mortgaging one's home and other assets to obtain such credit. In any event, the prospective gunsmith should investigate the sources of his anticipated finances, and then make certain that the funds or a line of credit will be available at the time he needs them. A letter of confirmation from a bank and suppliers should be obtained.

How would you feel if you happen to sell, say, 40 new guns to customers in one weekend? You didn't have the guns in stock, but each customer gave you a deposit of $25 towards the total purchase price of, say $200, to be paid when the guns came in. The total amount paid by your customers equals $1,000, but where are you going to get the remaining money, of say $5000, to purchase the "ordered" guns? If you already have a line of credit with a supplier for this amount, you're in business. If not, you may have to forego the sales.

Shop Location

The ideal gunshop location, in my opinion, is in a rural area (with outside shooting-range facilities) that is within a 45-minute drive from a large city. Every shop that I know of in a location like this is busy seven days a week with a backlog of work running from one to two years! Of course, there are other factors involved. You have to provide good service and turn out top-quality work. But there are other locations.

My own shop is located in a rural area that is 12 miles from a town of only 7500 population. Yet, I get much work from the area—due to the good hunting and a high rate of gun enthusiasts—as well as much work from Washington, D. C., which is over 75-miles away. I would dare say that a good gunsmith who runs an honest operation will do well regardless of his location—even if most of his work comes from mail order.

In most cases, the best place to start out is in your own home. This keeps your initial investment and overhead down until you get on your feet, and you won't have an umpteen-year lease over your head if you decide to close shop after a few months (as would probably be the case if you leased a shop building).

Regardless of the shop's location, the physical arrangement of the shop is an important factor in providing for efficient servicing of the work. In some instances, because of the limitations of the type of building, floor area, type of building access, relation to streets, yard area, and so on, it may not always be possible to provide an ideal physical arrangement of facilities; however, intelligent planning can usually provide for the maximum efficiency under the given conditions.

Tools and Equipment

The type and amount of tools that a gunsmith will need to begin operation will naturally vary depending upon the type and volume of business that will be done. A one-man operation doing general repair work and some refinishing projects can get by on a surprisingly small amount of tools.

The basic gunsmithing tools listed below are found on the work bench of practically all professional gunsmiths. This tool list covers the minimum essential tools needed to do good work on the usual kind of firearm in need of repair. They are the rock on which to build or expand your professional assortment of fine tools and instruments. They should be the best quality that you can afford and should include:

Workbench
Large bench vise
Gunsmith's screwdrivers
Pliers
Hammer
Bench knife
Spring vise
Sight-base file
Pillar file
Scribe hook
Cleaning brushes
Wood rasp
India stones

Allen wrench set
Woodworking chisels
Checkering tools
Checkering cradle
Drill press
Dremel Moto-tool with attachments
Bench buffer/grinder
Bluing tanks and source of heat
Drift punches

A professional gunsmith can do a surprisingly large amount of gun repair work with only the above tools, but chances are you're going to need some additional items on your very first job. Don't let this worry you. Your first customer has probably been used to waiting from three to six months on gun repairs; and, the week or ten days it takes to get an additional tool or so should not make that much difference. From this point on, buy tools only as you need them. The above list of tools, although meager, will cost you, but all of them will be used frequently and will quickly pay for themselves. Others might not do so well, so go easy.

Parts and Materials

The subject of obtaining gun parts is covered in Chapter 20, Miscellaneous Gunsmith Tools. Materials, like gun parts and tools, are dependent upon the type of work the gunsmith plans to do and many other factors. In general, the beginning professional should obtain the following items and then add to the list as the need arises.

Cleaning materials for shotguns, rifles and handguns
Touch-up bluing solution
Bluing salts
Buffing compounds
Stock refinishing supplies
Silver solder and flux
Case hardening compound such as Brownell's
Hard 'n Tuff
Supply of WD-40
Cutting and tapping oil
Aluminum blackening solution
Cleaning pads
Shop swabs
Steel wool
De-greasing compound such as Dicro-Clean 909
Rust and Blue remover

Summary of the 1968 Gun Control Act

The Gun Control Act of 1968 covers the licensing of persons engaged in the firearms business and regulates the sales, manufacture, transfer, importation and exportation of all firearms and ammunition. All firearms including gun actions, receivers and frames, all ammunition and all reloading components except pellets and non-metallic shotgun cases without primers are covered by this act. Certain specified antiques and muzzleloading guns do not come under restrictions. Any person or business involved in the sale or transfer of guns or in the repair of guns or any other gunsmithing activity needs a license. This includes anything you do to a gun that belongs to someone else.

The Gun Control Act contains Federal licensing standards for firearms-related businesses. An example of such standards is: The applicant must have a business premises (which can be a part of his home). This business premises must be open to his clientele during the hours specified in the application.

The application shall be approved if: The applicant is 21 years or more of age; is not prohibited from shipping or receiving firearms or ammunition in interstate commerce; has not willfully violated the GCA or its regulations; has not willfully failed to disclose required material information or willfully made false statements concerning material facts in connection with application; and has premises for conducting business or collecting.

The cost for the various firearm licenses are as follows:

Firearms (other than destructive devices):

Manufacturer	$50
Importer	$50
Pawnbroker-Dealer	$25
Dealer	$10
Gunsmith	$10
Collector (only for curios and relic firearms)	$10

Destructive devices and destructive device ammunition:

Manufacturer	$1,000
Importer	$1,000
Dealer	$1,000

All ammunition except that for destructive devices:

Manufacturer	$10
Dealer	$10

All gun sales must be recorded on standard government forms plus any state or local forms as required in your area. You must maintain records showing from whom you received each gun, when you got it, to whom you sold or transferred it and when. Any gun received for repair, alteration, etc. must also be entered in your record books. Ammunition sales must also be recorded.

Following is a brief summary of the major provisions of the Federal Firearms Control Act of 1968 and the recent opinions that affect it. You should have a thorough understanding of this prior to getting your license and after getting your license, you must have an equal understanding of the entire law. A copy of the complete law will be included with your license.

1. If you work on guns for others in your home of place of business you must be licensed under the Act. It is the government's position that you are responsible for the guns while in your possession. Also, if a customer refuses to pay for services you rendered, you will take possession of the gun in lieu of payment, sell the gun to cover these charges and thus come under the Act. Or, if the guns are stolen while in your possession, there are no records if you are not licensed. This applies to all phases of work: bluing, finishing, stocking, cleaning, repairing, scope mounting—anything, except the antique, replica and muzzleloading industry as specified and enumerated under the law.
2. The guns brought to you must be entered in your firearms record in chronological order. This will be the same book in which you will keep records of new or used guns bought for re-sale. When the customer picks up his gun, it should be so noted in the "disposition" side of the record. (Actually, this is nothing more than good business procedure anyhow!) Record books for both firearms and ammunition are available at very reasonable prices from Brownells and other major suppliers to the trade.
3. If you build rifles, i.e., chamber and attach barrels to actions and then build the complete gun, you need only the Dealer's License. You are not considered "manufacturing," because you are only assembling parts made by other manufacturers. If, however, you actually make the action from scratch from a piece of steel, then you are manufacturing, and must purchase a Manufacturer of Firearms license and comply with the special marking procedures. Also, as a manufacturer, you can be shipped all items covered by the law just as though you had a standard dealer's license.
4. If you reload for anyone other than yourself you must have a Manufacturer of Ammunition license. This applies even if the customer brings you the brass, powder, primers, bullets and even lends you his tools, you are still loading for someone else and must have a license. If you use new brass cases, never fired, you must also collect and pay excise tax. With a Manufacturer of Ammunition license, you can only sell, be sold and receive ammo and ammo components covered by the law. You cannot sell or receive firearms or parts covered by the Act. To do so, you must also have a Dealer's license.
5. Military Personnel: Licenses cannot be issued to individuals living within the military compound. Those "living on the state-side economy" can be issued licenses if they meet all other requirements of the Act.

After reading the above, it all probably sounds a bit involved and complicated. Actually, this is not the case, except for the record keeping requirements for ammunition sales. This does require a bit of unnecessary time. Otherwise, if you are legitimate and your intentions are legitimate, you will experience absolutely no difficulty.

About the License: First, write to the Department of the Treasury, Bureau of Alcohol, Tobacco and Firearms at the same address where you pay your Federal Income Taxes. Ask for: "Application for License under U. S. C. Chapter 44 Firearms." Do not send money at this time. The license fee of $10 goes in with your filled-out license application.

When you get the application, study it thoroughly before starting to fill in the X's. There are a couple of questions which might throw you a little and a few others about which you might be uncertain as to what is wanted. The following are the ones the men in the trade have asked about most often:

Question 9: This asks the location of the building in which you intend to operate. Home, commercial building, or "other." Be exact on this. If you use a small building close to your home, so specify. Or if it is to be in your home, say so.

Question 11: Line number 8 covers activities of average gunsmith/dealer operations. Check the box or boxes that pertain to your business. ("NFA" stands for *National Firearms Act*, which covers such firearms as full automatics, sawed-off shotguns and rifles, silencers and machine guns, including DEWATs*.)

If you reload ammo for other than your own personal use, a Manufacturer's License (Line No. 5) is required.

Question 13: Very important. Give those hours when you will actually be doing gun work, have open shop hours, or if at home as a side-line, give the afternoon and evening hours when you intend to, or are actually working on guns. This applies to Saturdays and Sundays as well. If there are days when you are open certain hours by "appointment only" and open to the public the other days, put this in the chart. Some gunsmiths operate by appointment only and are never open to the public. This is perfectly legal—so long as you keep it that way or advise the ATF of the change.

Read very carefully the quotation from ATF, Ruling 73-13, published August 6, 1973, in ATF Bulletin No. 1973-8. Note particularly the last two paragraphs, and the requirement that if a gunsmith applicant begins buying and selling firearms, he then must comply with the "open to the public" and "regular business hours" regulations as does a regular dealer.

* Deactivated War Trophies.

21- GUN PARTS


ENCYCLOPEDIA OF MODERN FIREARMS
Parts & Assembly
Exploded Firearms Drawings
FIREARMS ASSEMBLY I
The NRA Guidebook to Shoulder Arms

There is hardly a day that goes by that at least one of these four books is not used in the author's gunshop. Those involved in gun repair will find any reference book invaluable.

ANYONE who is involved in the repair of firearms—whether hobbyist or professional—will eventually need to obtain replacement parts. While replacement parts usually present few problems for modern firearms (most are obtainable from the manufacturer), obsolete firearms are a different story. However, in this latter case, a thorough knowledge of dealers dealing in obsolete gun parts will lessen the burden tremendously.

The first step in "tooling up" for gun parts is to write all of the firearm manufacturers and request their catalog of gun parts. Their addresses may be found in the "Directory of the Arms Trade" in the *Gun Digest* (DBI Books, Inc., Northfield, IL 60093). You'll receive their current parts list along with prices. In most cases, there will be an exploded view of the firearm with all parts numbered and then a reference list or schedule giving the name of the part. Besides the information you'll need to order gun parts, these catalogs are also valuable references for assembly and disassembly of firearms.

For both modern and obsolete arms, the following reference books will be of value: *The Gun Digest Book of Exploded Firearm Drawings, Brownell's Encyclopedia of Modern Firearms* and DBI Books new series entitled *The Gun Digest Book of Firearms Assembly/Disassembly*. This 5-book series tells you how to do it all; perhaps the most complete series of assembly/disassembly books ever published. All of these books have detailed drawings or photos of both modern and antique firearms. Should you be working on a particular gun with a broken part, and you aren't sure just what it is, one of these books should tell you. However, if you still cannot find it, make a sketch of the part (or take a good close-up photo) and send it to one of the antique gun parts dealers, giving all of the details you know about the gun in question; that is, model, serial number, etc. Chances are one of their experts will know what the part is and will be able to either furnish it or tell you the best source to obtain it.



An exploded drawing of firearms not only helps in identifying parts but is also a great aid for the assembly and disassembly of firearms.

A few of the major suppliers of obsolete gun parts include:
Antique Gun Parts, Inc. 1118 S. Braddock Ave. Pittsburgh, PA 15218
Bob's Place Box 283J Clinton, IA 52732
Dixie Gun Works Hwy. 51, South Union City, TN 38261
Numrich Arms Co. West Hurley, NY 12491
Sarco, Inc. 323 Union St. Stirling, NY 07980
Walter Lovewick (Winchester Parts) 2816 N. E. Halsey St. Portland, OR 97232
Stoeger Industries 55 Ruta Court So. Hackensack, NJ 07606

British Lee-Enfield rifle obtained from local pawn shop; chamber is welded shut but there were still many parts that could be salvaged.

This assortment of handgun parts was legally obtained from confiscated weapons at a law enforcement agency. Frames and barrels had to be destroyed by law, but many useful parts were salvaged.

I've had relatively good luck obtaining obsolete spare parts by purchasing old junk guns for a very low price and then salvaging the parts. For example, I recently purchased a British Lee-Enfield rifle in .303 caliber from a local pawn shop that had its barrel and chamber welded shut. I believe I paid $10 for the gun. A short time afterwards, the brass butt plate was sold for $5; the rear sling swivel for $3; the magazine for $5 and the extractor for $2. I've already made $5 profit on the deal and I still have the stock and other parts that can be used in the future.

Another source of gun parts is your local police department. Law enforcement agencies are continually confiscating firearms (mostly handguns) from criminals to be used as evidence and other reasons. Every so often, these weapons have to be disposed of—usually by hiring a local welder to cut the weapons up with a cutting torch and then bury the hunks of metal or perhaps toss the whole batch of cut-up parts in a nearby river.

If you have a Federal Firearms License, you may be able to work out a deal with your local police department whereby you would be allowed to disassemble the guns for the minor parts (screws, cylinders, springs, etc.) and then you would be responsible for cutting up the frames and barrels and disposing of them—under the supervision of the local courts. In other words, you'd be offering to dispose of the firearms in exchange for the minor parts.

Always be on the lookout for all junk guns that can be used for spare parts. You'll find a few with missing bolts, no stocks, ruptured barrels, etc. — all of which can be used for the parts that are intact. Recently I purchased an old Western Field pump shotgun that had a ruptured barrel for which no replacement part is readily available. Of course, another barrel could be fitted, but the cost of the operation would prohibit doing so on such an inexpensive shotgun. The owner wanted the barrel cut off below the ruptured area and rechoked, but I explained that this could not be done since the barrel length would then be under the minimum prescribed by law. So the owner wound up trading the "junk" gun in on another. The ruptured barrel was removed and disposed of and now I've got complete parts for this shotgun should one come into the shop for repair.

You might try advertising in local newspapers for junk guns. There are thousands of damaged and abused firearms in attics, closets and basements all over the country that the owners might want to part with, but due to the condition of those guns, the owners think that no market is out there. A short ad in a newspaper may bring to light the fact that you want the guns regardless of their condition. Numrich Arms has, for instance, obtained many parts in just this way. Also check the newspapers for estate sales or public auctions. I've seen a bunch of damaged guns thrown in a box which brought only a dollar... and the auctioneer had to toss fifty cents out of his own pocket to get this!

Experience has proven that those dealers who are able to furnish replacement parts the quickest seem to get the most business. From this it would seem that all a dealer has to do is to buy umpteen dollars worth of gun parts, sit back and watch the cash and the customers flow in. But this is not the way it usually happens. Chances are if you would buy, say, $10,000 worth of gun parts at random, you wouldn't sell $10 worth of parts in three months from the selection you purchased. The secret is to be selective. The key is knowing what guns are used the most in your area and what parts on these guns are subject to the most wear or breakage.

For example, the Savage/Stevens Models 80 and 87A .22 rim fire semi-automatic rifles are very popular in my area (and I'm sure all over the country). Hardly a week goes by that one of these does not come into the shop with feeding problems. In almost every case, the trouble could be traced to either a worn cartridge lifter or a weak magazine spring or both. After ordering these parts for about a dozen rifles that took anywhere from three to four weeks each, and noticing the unhappy expressions on my customer's faces (when they would come in weekly to inquire about their gun), I finally decided to order a dozen or so lifters and springs for these rifles. Now I can repair the rifles, in most cases, while the customer waits. Needless to say, customer/dealer relations have been improved tremendously.

This Western-Field pump shotgun had a ruptured barrel which was removed — the remaining parts will be used for replacements on other guns.

No. 2 Firing Pin, Fits obsolete Stevens single barrels.
WILLIAMS
FIRING PIN KIT
WITH REBOUND SPRING
(For single & double barrel shotguns)
No. 5 Firing Pin, Fits Harrington and Richardson Model 48
A good assortment of firing pins for single-barrel shotguns is a necessity. Replacement of this sort of part is usually fast, and inexpensive.

Another common replacement part is a firing pin for singleshot, break-open shotguns. There are thousands (make that millions) of Iver Johnson Champion, Stevens, H&R, Western-Field single barrel shotguns in use throughout the country. All of these will eventually need a replacement firing pin. A kit is available from Brownells that contains 25 shotgun firing pins and this kit will take care of most needs. It costs very little and you can make over 100% profit if you're in the gun-repair business; it's a good investment for any gunsmith. I went one step further. After having several old single and double barrel shotguns come in for repair for which no replacement parts were available, I purchased a Unimat 3 Miniature Machine Lathe. Now I can turn out drift pins, firing pins and other simple parts for almost any firearm that comes in for repair.

You should note that when an unusual firearm comes in your shop for repair (one on which little or no reference material is available) you should take notes of the disassembly procedure as you learn it (probably by trial and error) and also list dimensions of the parts that are subject to the most wear. These notes will come in handy should another gun of this type come in later. But be sure to file the information where you can put your hands on it. Keep a separate file drawer for gun-part information only; then file the information in alphabetical order by manufacturer's name, and then by model number.

A person just starting out in the gun repair business—either working out of his home or from a commercial shop—may be somewhat at a loss as to what spare parts should be purchased initially. If I were starting from "scratch," here's a list of gun parts that I would purchase. They can be obtained from the manufacturers or one of the gunsmith supply houses.

Weaver scope parts kit
Universal rear sight elevator kit
Shotgun sight kit
Weaver top and side mount base assortment
Fillister head screw kit
Sight base screw kit
Roll-pin kit
Firing-pin kit
Spring kits
5 Cartridge lifters for Stevens 87-A Rifle
5 Remington .22 pump fore-end supports
1 Winchester Model 12 safety

To this list may be added other parts as you see a need for them.

Making Your Own Parts

In most cases, you can purchase parts from manufacturers much cheaper than you can make your own. Factories turn out thousands of each part and for a particular item that you'd pay, say, $1 for, this same part may cost you $20 or more in time. However, there are certain situations where the making of a part yourself is warranted. For example, when no factory parts are available; when the customer needs the gun repaired quickly and does not have the time to wait for a factory replacement; or perhaps when the customer wants a modification of the factory part.

With a little tinkering and patience many parts can be made right in your own home shop, and without the expense of a lot of power tools. For example, such items as hammers for handguns and shotguns can be made from flat scrap iron. Choose a piece of the correct thickness and proceed to layout the part to be made—either by tracing the original part or by careful measuring. The part may be rough shaped by drilling along the border of the part with a drill press. Then final shaping can be done with an assortment of files.

Of all the parts used in firearms, you will most likely be called upon to make more gun springs than any other. Fortunately there is a good supply of spring stock assortments available that makes the making of springs much easier. For example, Brownells offers no less than six different gunsmith spring-stock assortments and are described as follows:

Assortment No. 69 consists of compression service springs with a soft action that are mainly designed for locks, sporting equipment and the softer acting gun and camera springs.

Assortment No. 71 consists of twelve assorted compression springs of medium to hard action. This assortment is made especially, for servicing guns and will handle ninety percent of the shop needs.

Assortment No. 150 contains small spring wire (diameters from .020″ to .062″) that may be used to make gun and miscellaneous small springs.

Assortment No. 152 contains round, oil tempered spring stock in diameters from .062″ to .120″. These can be annealed and re-tempered.

Assortment No. 151 contains small flat spring stock of widths 1/16″ to ⅜″ and thicknesses from .015″ to .045″. These are ideal for making small flat springs for guns, locks, cameras, tackle, etc. Hand-bendable, they can be annealed and retempered.

Assortment No. 149 is for large flat guns and lock springs and consists of 12 assorted pieces of flat spring stock cut into 18″ lengths #1070 carbon steel, annealed and spheroidized (put into a very soft state). They will forge and temper into gun-quality spring requirements.

The Unimat 3 and other small lathes are relatively inexpensive and can be put to work making all sorts of gun parts, especially when the milling attachments are purchased for the machine. Firing pins, sight bases, drift pins, and the like are just a few of the many items that may be turned out on this machine. So long as you take your time, and don't try too large a job, this little machine will perform just like the more expensive models. In fact, for very small jobs, such as firing pins and drift pins, the Unimat 3 is usually easier to set and will perform the job better than the large lathes. With the thread-cutting attachment, you can turn out gun screws and trigger guard bolts all day and never tire the machine out. For larger parts, or where productivity is important, you should go to one of the larger lathes and milling machines. The work that can be performed on these machines is limited only by the capabilities of the operator.



A Unimat 3 miniature lathe can be used to turn out firing pins or other small parts when original parts are unavailable.

22 – GUNNING CALCULATIONS

GUNSMITHS, ballisticians, serious hobbyists, and others involved with gunning mathematics in the past have rated the slide rule as one of their most important instruments, since it helped reduce long minutes of paper-and-pencil calculations to a few simple manipulations of the "slipstick" and "runner." While the slide rule has proved indispensable since its invention in the 1850s, there is now something faster, more versatile, more compact, more accurate, and better able to solve today's gunning problems involving mathematical calculations. It's the electronic pocket calculator.

There is no need to explain the fundamentals of electronic calculator operation, since this information may readily be obtained from the handbook accompanying these devices, and since practically anyone can master the operations of an electronic calculator in a single evening. The paragraphs that follow will explain how to make specific basic gunning calculations. Actual directions will be given for pressing the required keys in each case.

A selected number of examples have been chosen. These are basic; by no means do they attempt to cover all of the possible uses of the calculator. Other examples solvable by the same processes will readily occur to the reader.

We find that the type of electronic calculator possessed by most gunsmiths and ballisticians is an inexpensive device costing less than $100. This discussion will be limited to that type. However, any calculator capable of adding, subtracting, multiplying and dividing may be employed, except for problems involving reciprocals, square root and similar functions.

Bullet Energy

To find the striking energy of a bullet when the velocity at impact and the weight of the bullet in grains is known:

A. Key in velocity value
B. Press the multiplication key
C. Key in the velocity value again (to square)
D. Press multiplication key
E. Key in bullet weight in grains
F. Press division key
G. Key in the number 450240 and press = key.
H. Read answer displayed as the striking energy in foot pounds.

Example: Let's find the striking energy of a 405-grain bullet with a velocity of 1930 feet per second. All figures are at the muzzle:

Solution:		
		See Displayed
A.	Key in velocity value 1930	1930

B.	Press the multiplication key “x”	1930
C.	Key in velocity value again 1930	1930
D.	Press multiplication key “x”	3724900
E.	Key in weight of bullet 405	405
F.	Press division key ÷	1508584500
G.	Key in number 450240	450240
H.	Press “equals” key (=) and read	3350

Therefore, the energy of the 405-grain bullet at a velocity of 1930 fps is 3350 foot pounds.

Sectional Density

Sectional density is the weight of a bullet in relation to its diameter. This figure is used as a gauge for determining flight characteristics. To determine sectional density:

A. Key in weight of bullet in grains
B. Press division key
C. Key in the number 7000 (to convert grains to pounds)
D. Press division key
E. Key in bullet diameter
F. Press division key
G. Key in bullet diameter again
H. Press equals key and read answer on panel

Example:

Find the sectional density of a 180-grain bullet with a diameter of .308″.

Solution:	
	See Displayed
A. Key in weight of bullet in grains 180	180
B. Press division key	180
C. Key in number 7000	0.0257
D. Press division key ÷	0.0257
E. Key in bullet diameter. 308	0.308
F. Press division key ÷	0.0835
G. Key in bullet diameter. 308	0.308
H. Press equals key and read answer on panel	0.271

The bullet in question has a sectional density of .271.

Telescopic Sight Adjustments

To determine the number of clicks on the scope adjustment to move a bullet on a target a certain distance:

A. Key in the distance the bullet should move in inches.
B. Press the division key.
C. Key in the number of inches that one click moves the bullet.
D. Read answer on panel as the number of clicks required.

Example:

In sighting in a .243 Winchester at 100 yards, using a Lyman 4x scope which has a ^{3}A″ click value at 100 yards, the first two shots are placed on the target 4W to the left of the point of aim.

Solution

		See Displayed
A.	Key in distance the bullet should move 4.5	4.5
B.	Press division key ÷	4.5
C.	Key in .75	0.75
D.	Press equals key and read	6

Therefore, 6 counterclockwise clicks of the windage adjustment knob should put the bullet dead center at 100 yards.

Correcting Factory Velocity Tables

Factory-published velocities of a given load are usually based on a barrel length of 26 inches (there are some exceptions). To find the actual velocity in your rifle, the following velocity correction table may be used.

Barrel Length	Multiplication Factor
26″	1.000
25″	0.993
24″	0.985

23″	0.979
22″	0.969
21″	0.964
20″	0.954
19″	0.944
18″	0.939

To use this table, merely multiply the published factory velocity of the multiplication factor opposite the barrel length in question.

Example:

The factory-published velocity of a 139-grain bullet in 6.5 x 54mm is 2580. What is the velocity in an 18-inch barrel carbine?

Solution:

		See Displayed
A.	Key in factory velocity	2580
B.	Press multiplication key x	2580
C.	Key in factor opposite 18″	0.939
D.	Press equals key (=) and read	2422

Therefore, the actual velocity in an 18-inch barrel is 2422 fps.

Calculating Bullet Drop

When a bullet leaves the muzzle of a rifle it begins to drop, just as it would if you held a bullet in your hand and then let it go. However, certain aerodynamic forces, acting upon the bullet when it is fired, keep that projectile from falling quite as fast as it would if merely dropped from one's hand. One of the more convenient devices for determining bullet drop is the Powley High-Velocity Chart. Homer Powley, former chief ballistician at Colt, introduced this chart in the mid-50s. To use this chart to calculate the drop of a particular bullet, three factors must be known:

1. The actual velocity of the bullet in the rifle in which it is fired; not the published velocity.
2. The ballistics coefficient of that bullet.
3. The height of the line of sight above the bore.

The ballistic coefficient of a bullet determines its ability to resist air drag, maintain velocity and energy as it travels to the target, and shoot flat. Two methods are commonly used to determine the ballistic coefficient of a bullet. The more popular one was introduced in the '30s by Wallace H. Coe and Edgar Beugless, ballistics engineers at du Pont. This method compares an actual bullet to a point-shape chart, and when the closest possible match is made, the chart provides a point-shape factor—a number which is then divided into the bullet sectional density to give the ballistic coefficient.

The other method is direct measurement by means of firing tests. The test range must be instrumented so that both muzzle velocity and time of flight over a known range are measured for each shot fired. A digital computer program then derives the ballistic coefficient of each test bullet from these measurements.

For the average shooter, the best and easiest way to obtain the ballistic coefficient of a given bullet is from the bullet's manufacturer. Tables are available that give the sectional density, ballistic coefficient, etc., from nearly every bullet manufacturer.

The third factor—line of sight above the bore— can vary from gun to gun, but for open sights assume ½″ for conventional scope mounted rifles, assume 1½″, and for scopes with see-thru mounts, figure 2".

Let's assume that we want to find the bullet drop of a .243, 75-grain Sierra hollow point bullet fired in a .243 Winchester rifle at an actual velocity of 3100 fps. Conventional scope mounts are used. The ballistic coefficient from Sierra's Reloading Manual is .265 for this bullet. With this data, we can now figure the bullet drop using Powley's chart.



The Powley Chart should be affixed to the wall with tape or thumb tacks so that it's at a convenient height.

The Powley chart should be affixed to the wall with tape or thumb tacks so that it's at a convenient height; that is, so that it can be easily reached as you're using it. Now you'll need a piece of heavy black thread about 40 inches long. Tie a thumb tack at each end of this thread.



Place a tack (with the thread attached) at the 1.5 inch mark on the chart.



Make a light pencil mark where curve 38 intersects the vertical line headed 200 on the chart.

In our example, we are using a rifle with a conventional scope, so we'll place one of the tacks (with the thread attached) at the 1.5″ mark on the chart as shown in the accompanying illustration. We are now ready to calculate the trajectory of the 75-grain .243 bullet from muzzle to 500 yards.

The corrected (actual) velocity of our example bullet is 3100 fps, so find the vertical column headed "MV" on the chart; 3100 will be located at the lower right section of the chart. You'll also find the ballistic coefficient numbers—minus the third decimal. So trace an imaginary line from the ballistic coefficient of this bullet (.265) straight across to the extreme right vertical line which will end at curve 38. Place a thumb tack here.

Let's assume that we wish to use a 200-yard zero, meaning the bullet will strike dead on at this distance from the muzzle. Follow curve 38 from the bottom reference mark until it intersects the vertical line headed 200 on the chart. Make a light pencil mark at this intersection point.

Pick up the loose tack at the other end of the thread and stretch it to the right so that it crosses directly over the 200-yard zero point that you just marked with an "X." Secure the tack to the wall, to right of the chart. This thread represents the line of sight relative to 200-yard zero.

Now let's calculate the bullet drop at 250 yards, 300 yards and 400 yards. Follow curve 38 to where it intersects the vertical line marked 250. Make a light pencil mark at this point. Use an engineer's scale that is calibrated in tenths of an inch and measure the distance, against the 250-yard vertical line, between the thread and the pencil mark you just made. The figure is 1.85″, but since the chart scale is 1″ = 2″ (half-scale), this figure will be doubled.

Solution:

		See Displayed
A.	Key in 1.85	1.85
B.	Press Multiplication key x	1.85
C.	Key in	2.2
D.	Press equals key = and read	3.7

Therefore, the drop of our bullet at 250 yards will be 3.7″ below the line of sight.

The distance (measured with the engineer's scale) from the thread to curve 38 where it intersects the 300-yard vertical line is 4.4″. This, doubled, would be an 8.8″ drop at 300 yards. At 400 yards the measured distance is 12.5″ actual drop if this figure were doubled.

Now let's check the Sierra Reloading Manual to see how close our figures are compared to their calculations. Sierra had no figures for 250 yards, but at 300 yards they show that this bullet will drop 7.87″ as compared to 8.8″ on our chart. Nearly an inch off! At 400 yards, Sierra shows the bullet drops 24.33 inches as compared to our 25 inches. About $^{2}/_{3}$″ off. Personally, I doubt if a groundhog at either of these ranges would know the difference if the crosshairs were held dead center of his chest.

23 - GUNSMITH'S LIBRARY

The following list of titles represents a good selection of books for both the hobbyist and professional. If your geographic location is remote, or if you just don't happen to have a book store in your immediate locale, we would suggest you contact Ray Riling Arms Book Company, 114 Greenwood Ave., Box 135, Wyncote, PA 19095. Riling's has a solid reputation for providing the hunter, shooter or gunsmith with the books he needs—even rare, or simply out-of-print books.

Advanced Gunsmithing by W. F. Vickery, Small-Arms Technical Pub. Co., Onslow Cty., N. C. As the name implies, this is a book for the professional. It gives principles and instructions on barrel making, boring, reaming, rifling and chambering—all done by means of small power tools or entirely by hand on a hand-rifling bench using rifling heads, barrel and chamber reamers which can be made in the gunshop. It further tells about headspacing, barrel changing, action alterations and barrel lining, together with some highly applicable chapters on the reboring and chambering of rusted or shot-out barrels and obsolete rifles. Extensive treatment is given the popular .22 rimfire and its peculiar problems. There is a full chapter on shotguns and their repairs or alterations.

This book is now out-of-print, but the professional will probably want to acquire this one because it takes up where the others leave off.

You'll probably be able to obtain a copy from Ray Riling, but you're going to pay dearly for it.

Black Powder Gunsmithing, by Ralph T. Walker, DBI Books, Inc., Northfield, IL. Covers everything from replica building to restoration. Also includes directory of suppliers.

Checkering and Carving of Gunstocks, by Monty Kennedy, Stackpole Books, Harrisburg, PA. This is an extensive and specialized work that covers its subject fully from both utilitarian and decorative standpoints. The full-size patterns range from easy ones to some that will take many jobs and much experience before one should attempt them.

Complete Guide to Gunsmithing, by C. E. Chapel, Barnes & Co., NY, NY. A thorough treatment of the care, repair, alteration and decoration of rifles, pistols, revolvers and shotguns. Starting with the selection of hand and power tools it moves right into checkering of stocks and engraving of metal parts and continues to range over the entire field of firearms.

Elementary Gunsmithing, by Perry D. Frazer, Small-Arms Technical Pub. Co., Onslow Cty., NC. Another out-of-print book that is intended solely as a guide to the beginner in guncraftsmanship. It is the ideal book for the boy or adult who has just become interested in firearms. (A recently published book with the same goals is Basic Gunsmithing by John Traister, published by TAB Book, Blue Ridge Summit, PA.)

Firearm Bluing and Browning, by R. H. Angier, Stackpole Books, Harrisburg, PA. While this is a qualified, practical and complete treatise covering the art of gun bluing, I've found little use for it in my own shop. It is interesting reading, but most of the techniques described are dated.

Gun Digest Books of Firearms Assembly/Disassembly, by J. B. Wood, DBI Books, Inc., Northfield, IL. At this printing, DBI Books plans a 5-part series: Part I Automatic Pistols; Part II Revolvers; Part III Rim Fires; Part IV Center Fires; Part V Shotguns. As you read this, the first four books should be available with the shotgun book (Part V) becoming available in the fall of 1980. This is, perhaps, the most comprehensive assembly/disassembly series ever undertaken. Field stripping as well as detail-stripping of most popular firearms is covered. Invaluable.

Gun Owner's Book of Care, Repair & Improvement, by Roy Dunlap with photos by Jim Carmichel, Outdoor Life—Harper & Row, NY. A good book for the beginner. Exceptional step-by-step photos of each job makes the going easier.

Gunsmith Kinks, compiled by Bob Brownell, F. Brownell & Sons, Montezuma, I A. I've read this book through three times already. It's an endless fountain of knowledge covering the care, service, repair and building of firearms. The book contains techniques, trade secrets, etc., of the country's leading full- and part-time gunsmiths. It's geared for the professional, hobbyist, hunter and the target shooter.

Gunsmithing, by Roy F. Dunlap, Stackpole Books, Harrisburg, PA. This book covers a lot of technical information and instruction on practically every phase of the gunsmithing trade. It may be a little too advanced for the raw beginner, but you'll eventually find it invaluable once you get started on gun repair work and refinishing firearms.

Gunsmithing Simplified, by Harold E. MacFarland, A. S. Barnes, NY, NY. This book has been out of print for a few years, but A. S. Barnes & Co. (the publisher) informed me that it is now being reprinted and should be available when you read this. This book presents a lot of technical information in a manner easily understood by the layman. Many professional secrets are revealed that can save you hours of work, produce better guns, and leave you with money to spare. Some of the topics include, modernizing sporting rifles, converting military rifles, handguns, shotguns, chambering, carving, stockmaking, trigger adjustment, how to make tools and small parts.

Gunsmith's Manual, by Stelle & Harrison, Rutgers Book Center, Highland Park, NJ. This is a reprint of a book originally published in 1882 and deals mainly with the fabrication, finishing and repair of flint and caplocks—although some information is given on the early breechloaders of the day. This is an excellent text for those doing work on muzzleloaders.

Gunstock Finishing and Care, by A. Donald Newell, Stackpole, Harrisburg, PA. A thorough and advanced book of more than 100 formulae for the compounding of finishes the gunstocker can make and apply correctly. All early and modern finishes pertaining to gunstocks are covered in detail.

Hobby Gunsmithing, by Ralph Walker, DBI Books, Inc., Northfield, IL. This is one of the better up-to-date works on gun repair written by a veteran gunsmith. Written in a breezy, lucid style, and profusely illustrated with step-by-step photos and drawings. Emphasis is placed on working with few tools to get a lot of projects completed. If you're willing to try, this book will tell you how.

Home Gunsmithing Digest, 2nd ed., by Robert A. Steindler, DBI Books, Inc., Northfield, IL. Here's another "must" for the beginner and professional alike. Covers complete what, how-to and why information on such items as checkering, silver soldering, heat-treating, bolt jewelling, touch-up bluing, etc.

Modern Gunsmithing, by Clyde Baker, Standard Publishing, Huntington, W. VA. Although out of print at this writing, this is still one of the best books on gunsmithing ever written for the shooting man. It's written for the ordinary gun-crank for use with the tools and facilities of the average home, farm or ranch; so you won't need access to an elaborate machine shop to carry out the many ideas and suggestions.

NRA Gunsmithing Guide, National Rifle Association, Washington, D. C. This useful guide contains many of the American Rifleman articles on gunsmithing. It's packed with information for both the amateur and professional. Metal working details are given on rebarreling, reamer making, welding, etc. Woodworking is also covered.

Pistolsmithing, by George C. Nonte, Jr., Stackpole Books, Harrisburg, PA. A comprehensive, basic book on the art of pistolsmithing.

Troubleshooting the pistol, as well as maintaining the pistol are just some of the subjects that are thoroughly covered. It's a must for any gunsmith doing handgun work.

Professional Gunsmithing, by Walter J. Howe, Stackpole Books, Harrisburg, PA. The author takes up the subject of professional gunsmithing in a broad and comprehensive manner—approaching it from the angle of basic principles and logical reasoning. While some of the information is dated, Howe treats in detail the specific jobs and types of repair work which, from experience, have shown to be most frequently encountered in the gunshop.

The Amateur Guncraftsman, by James V. Howe, Funk & Wagnalls, NY, NY. This was my first book on gunsmithing and I still enjoy reading through it from time to time. It's out of print, but you may be able to find a copy in one of the used book stores or from Ray Riling. This is a thoroughly practical handbook for the beginner.

The Modern Gunsmith, by James V. Howe, Funk & Wagnalls, NY, NY. Another excellent text by James V. Howe and also out-of-print. Two volumes are required to contain all of the information given on gun repairing, refinishing and other techniques. It's a little dated in some cases, but every gunsmith will want a set of these, if only for the many bluing formulas found in the books.

24 – GLOSSARY OF FIREARM TERMS

ACTION: The breech mechanism of a firearm through which it is loaded. The action also secures the cartridge or shell in the chamber to prevent discharge to the rear.

ACTION, BOLT: Cylindrical-shaped breech action that contains a bolt, firing pin, spring, etc., which is opened and closed, and otherwise operated by a handle.

ACTION, LEVER: A breech action that is opened, closed and operated by means of a lever, usually formed as a rearward extension of the trigger guard.

ACTION, PUMP: A breech action which is opened, closed, and operated by means of a sliding fore-end which is formed into a convenient handle for this purpose. Also termed *trombone* or *slide-action*.

AMMUNITION: Cartridges, shotgun shells or both that contain powder, bullet or shot and a cap to ignite the powder.

ANNEAL: To render metals soft by heating to a red color and allowing it to cool.

ANVIL: A small multi-legged piece of brass inserted in a primer that acts to allow the priming composition to be crushed against it, causing a spark to ignite the main powder charge..

AUTOMATIC: A term commonly used for a self-loading firearm. A better term is "semiautomatic" for these weapons since a firearm is truly automatic only when it continues to fire as long as the trigger is held back.

BARREL: The part of a firearm through which the bullet or shot is driven by the powder. It directs the projectile toward its target and allows (usually) the powder to burn completely before the projectile is on its own in flight through the air.

BORE: The hole through the barrel of a firearm measured from land to land. In rifled barrels, the groove diameter is the distance between opposite grooves.

BREECH: The rear end of the bore of a firearm where the cartridge is inserted into the chamber.

BREECH BOLT: Part of the action which closes the breech, and sustains the head of the cartridge when the gun is fired.

BULLET: The projectile fired from a rifle or pistol.

BUTT: Part of the gun stock which comes in contact with the shoulder of the shooter.

BUTT PLATE: The plate of hard rubber, steel, aluminum or synthetic material which is attached to and, protects the rear end of, the buttstock. Butt pads are also used to soften the feel of recoil from shotguns and rifles.

CALIBER: Principally the bore (or land-to-land) diameter of a barrel; not actual bullet diameter in modern usage. Also used to refer to the actual designation of a cartridge such as, "caliber .308 Winchester." Also used as a unit measure to describe bullet nose shape, i.e. "4-caliber ogive" or seating depth, "1-caliber seating depth," and in big-gun terms, barrel length in units of bore diameter. A 50-caliber 6-inch gun has a barrel 50 x 6″ or 300 inches (25 feet) long.

CANT: Leaning of a rifle to one side or the other so that the sights are not in a truly vertical plane. This results in the bullet striking the target on the side of the cant and slightly low.

CAP: A percussion cap for use with cap-and-ball guns; also the cup and priming-compound pellet of a conventional shotshell primer. Also sometimes used in place of the word "primer."

CARBINE: A short-barreled rifle like the Winchester Model 94 or the Marlin 336.

CARRIER: The mechanism in a magazine or repeating firearm which carries the cartridge or shotgun shell from the magazine into a position to be pushed into the chamber.

CAST-OFF: A slant in a gun stock away from the face of a right-handed shooter.

CAST-ON: A slant in a gun stock toward the face of a right-handed shooter.

CENTERFIRE: Term used to identify a cartridge having its primer inserted in the center of the head of the shell or case.

CENTER PUNCH: Punch with a short sharp point for marking metal, usually before drilling with bit.

CHAMBER: The enlarged portion of the bore, at the breech in which the cartridge rests when in a position to be fired.

CHECKERING: Applies to diamond-shaped patterns cut in wood or metal parts for the purposes of minimizing slippage, and for decoration.

CHEEK PIECE: A raised, carved portion of the butt stock on one side of the comb against which the shooter rests his cheek when aiming.

CHOKE: The constriction in the muzzle end of a shotgun barrel to control the shot pattern. Degree of choke is measured by the approximate percentage of shot pellets in a shot charge which hit within a 30-inch circle at 40 yards.

COCK: To ready the hammer or firing pin of a gun so that it is in a position to fire.

COMB: Top of the butt stock or part of the stock which extends from the heel to a point just back of the hand as the stock is grasped. A proper comb guides the face to a position where the eye falls quickly into the line of aim.

CONE: The slope of the forward end of the chamber of a rifle or shotgun which decreases the chamber diameter to bore diameter. Sometimes called the forcing cone.

CROSSBOLT: Transverse bolt used to lock the standing breech and barrels of a side-by-side or over-under shotgun.

CYLINDER: The part of a revolver which contains the cartridge chambers and revolves so that each cartridge lines up in turn with the barrel so that it can be fired.

DAMASCUS BARRELS: Barrels made by a special process of welding alternate strips of iron and steel together in sort of a twisting fashion. Also referred to as “twist” barrels.

DRIFT: The deviation of the projectile from the plane of departure due to rotation. The degree of drift can be affected by certain wind conditions.

DROP: The distance a projectile falls due to the force of gravity. Drop must be corrected by means of sight adjustment for the difference between the line of sight and the line of departure. Drop also refers to the height between the line of sight and the top of the stock comb or heel.

DUMMY CARTRIDGE: A cartridge case and bullet—but without powder or primer—used for testing the feed, extraction and ejection of actions.

EAR PROTECTOR: Plugs, acoustical muffs, or similar devices that help eliminate the sound of gun shots.

EJECT: The action of throwing a cartridge from the breech after extraction. This is often accomplished by spring action.

EJECTOR: A mechanism on firearms that ejects the fired or unfired shell clear of the gun.

ELEVATION: The vertical sight adjustment to bring the point of aim to the proper elevation to compensate for bullet drop.

ENGINE TURNING: The process of polishing circular spots on metal (usually rifle bolts) with a spinning abrasive rod.

ENGRAVING: The art of cutting patterns or designs into the metal parts of a firearm to improve its appearance and to increase its value.

EXTRACT: The process of removing a cartridge case from the chamber of the action.

EXTRACTOR: The hooked device which withdraws the cartridge out of the chamber when the breech mechanism is opened.

EYE RELIEF: The optimum distance the eye must be held from the ocular lens of a telescopic sight to obtain a full field of view through the scope.

FEED: The action of transferring cartridges from the magazine of a repeating or semi-auto gun into the chamber of the barrel.

FIRING PIN: The pointed nose of the hammer of a firearm—or the separate pin or plunger—that dents the primer of a cartridge or shell to fire the round.

FOREARM: The forward portion of a stock under the barrel which serves as the fore grip on the arm. Frequently called “fore-end.”

FRAME: The framework of a firearm to which the barrel and stock are fastened and in which the breech, lock and reloading mechanisms are located.

FREEBORE: The unrifled portion of the barrel between the rifling and the end of the chamber.

GALLERY: The term usually applied to an indoor rifle or handgun range.

GAS-CUTTING: The escaping of propellant gas between a bullet and the bore of the barrel— usually caused by the bullet being undersized for the bore.

GAS OPERATION: A system used in semi- or fully-automatic firearms where some of the propellant gases are vented out of the bore through a small port to operate the action.

GAUGE: The measurement of the bore diameter of a shotgun. The gauge is the number of lead balls, of the diameter of the gun bore, that make a pound of lead. Therefore, 20 balls which fit the bore of a 20-gauge shotgun would weigh one pound.

GLASS BEDDING: The reinforcing of a wooden gunstock by adding a fiberglass/epoxy compound to strengthen the stock and improve accuracy and consistency of point of bullet impact. The compound is also useful for repairing broken stocks.

GRIP: The small part of the stock—often called the “wrist”—to the rear of, or just below, the action where the hand of the shooter grasps the firearm for shooting.

GROUP: A number of consecutive shots, usually five or ten, fired at a target with constant aim and sight adjustment; their bullet holes making a group on the target.

GUARD SCREW: The screws that hold the action and trigger guard to the stock.

HAMMER: That part of a firearm which strikes either the cartridge rim or primer or strikes the firing pin, driving the latter forward so that it indents the primer or rim of the cartridge, causing it to discharge. The hammer is actuated by a mainspring and controlled by the trigger.

HAMMERLESS: Firearms having the hammer concealed within the breech mechanism, or, a firearm that literally has no hammer and is striker fired, i.e., a spring activated firing mechanism.

HEAD SPACE: That dimension in a firearm which determines whether the cartridge is tightly breeched up in the chamber when the breech, breech block or breech bolt is shut. When head space is too little, the breech will not close on the cartridge. When there is too much, misfires begin to occur, and the safety factor is lowered. Excessive headspace is dangerous and may result in serious injury. Headspace may be checked with headspace gauges available from gunsmith supply houses.

HINGE: The joint in a break-down, breech-loading rifle or shotgun connecting the barrel or barrels with the frame.

LANDS: That portion of the original bore surface of a rifle barrel which lies between the grooves.

LEADING: Deposits of lead left in the bore of a rifle, handgun or shotgun.

LENGTH OF STOCK: The distance in a straight line from the center of the trigger to a point midway between the heel and toe of the butt plate, on the surface of the plate. Required stock length depends upon the physical conformation of the shooter; men of short stature or short arms requiring shorter stocks.

LINE OF SIGHT: The straight line passing from the eye through the sights to the target.

LOCK: The combination of hammer, firing pin. sear, mainspring and trigger which serves to discharge the cartridge when the trigger is pulled.

LOCK SPEED: The time consumed between the releasing of the firing mechanism and the explosion of the cartridge.

to occur, and the safety factor is lowered. Excessive headspace is dangerous and may result in serious injury. Headspace may be checked

LOCKING BOLT: The bolt used in a breakdown, breech-loading gun to lock the breech in its closed position.

LUG: In a break-down, breech-loading shotgun or rifle a lug on the barrel which secures the barrel to the frame. Lugs on the front of a bolt or breech block which rotate into slots to lock the action for firing are termed locking lugs.

MAGAZINE: A box or tube on or in a repeating firearm, in which the cartridges are carried in a position to be fed into the chamber by means of the reloading mechanism.

MAGAZINE, BOX: One in which the cartridges are horizontally stacked.

MAGAZINE, FULL: A tubular magazine reaching the full length of the barrel.

MAGAZINE, HALF: A tubular magazine reaching half the length of the barrel.

MAGAZINE, TUBULAR: One in which the cartridges are carried end-to-end in a tube located either beneath the barrel or within the stock.

MAINSPRING: The spring, either flat or coiled, which provides the energy to carry the hammer or firing pin forward to strike the primer.

MATTED RIB: A raised, solid rib along the top length of (generally) a shotgun barrel to cut reflection and improve sighting.

METAL FOULING: A deposit of bullet-jacket metal left in the bore of a rifle.

MOUNTS: Metal bases and rings used to secure a telescopic sight to the barrel or receiver of a firearm.

OVER AND UNDER: Term used to describe a double barrel shotgun or rifle with one barrel superimposed over the other.

PISTOL: A handgun in which the cartridge is loaded into a chamber which is in the barrel. Pistols may be single shot, repeating or semiautomatic. When the cartridges are loaded in and fired from a revolving cylinder, the pistol is termed a revolver*.

PITCH OF BUTT: The angle of the butt or butt plate with relation to the gun’s barrel. If, for example, the butt of a gun is rested on a flat surface on the floor with the barrel in a vertical position, and the barrel muzzle inclines at two inches from perpendicular, the butt is said to have a pitch of two inches.

POWDER: The finely divided chemical mixture that supplies the power used in shotgun and metallic ammunition. Originally, all propellant powder was black powder, which was formed in grains of varying size, the size of the grain determining the rate of burning and suitability for various cartridges in black powder arms. Modern powders are smokeless and their base is either nitroglycerine or nitrocellulose, or a combination of the two.

PRIMER: The small cup, or cap, seated in the center of the base of a centerfire cartridge or shot shell and containing the igniting compound. When the primer is indented by the firing pin, the priming compound is crushed, and detonates, thus igniting the charge of powder. Rimfire cartridges contain the priming compound within the folded rim of the case, where it is crushed in the same manner.

PROJECTILE: A ball, shot or bullet fired from a firearm.

PUMP GUN: Common name for a slide action, repeating firearm.

RECEIVER: The frame consisting of breech, locking and reloading mechanisms of shotguns or rifles.

RECOIL: The backward movement or “kick” of the firearm caused by the discharge of the cartridge.

RECOIL PAD: A soft rubber pad which replaces the usual butt plate on a shotgun or a high power rifle. Used to ease or soften the recoil on a shooter’s shoulder.

REPEATING FIREARM: Any rifle, shotgun or pistol, other than a revolver, having a magazine in which a reserve supply of cartridges is carried, and a repeating mechanism which, when operated, ejects the fired cartridge case and replaces it with a loaded cartridge, ready to fire.

REVOLVER: A pistol in which the cartridges, usually six or more, are placed in firing position by a revolving cylinder.

RIB: The raised bar, usually slightly concave on its upper surface, and usually matted, which forms the sighting plane extending from breech to muzzle of a gun.

RIFLE: A shoulder-mounted firearm with the bore of its barrel cut or rifled with spiral grooves; the object of which is to cause the projectile to rotate on its axis when fired, thus increasing its range and accuracy.

RIFLING: The spiral grooves cut in the bore of a rifle or pistol barrel. The object of these grooves is to rotate the elongated projectile so that it will fly point-on to the target.

SAFETY: The mechanism, lever or other device which mechanically locks a firearm against the possibility of discharge.

SEAR: The device in the lock of a firearm which holds the hammer or firing pin in its cocked position. When the trigger is pulled to the rear it disengages the sear, which in turn releases the hammer or firing pin.

SELF-LOADING: A type of firearm which, by pulling the trigger, utilizes the energy of recoil or the powder gases, together with a heavy counterbalanced bolt and strong bolt spring, to eject the fired case, load a fresh cartridge from the magazine into the chamber, and close the breech ready to fire another round. The trigger must be pulled for each shot. Also termed autoloading or semiautomatic.

SHOTGUN: A smooth bore firearm which shoots a large number of small shot rather than a single large projectile.

SIDE BY SIDE: A double barrel shotgun or rifle with the barrels horizontally alongside of each other.

SIGHT RADIUS: The distance between the front and rear sights. The longer this distance, the greater the accuracy attainable.

SMOOTH BORE: A firearm without rifling.

STANDING BREECH: The face of the frame of a double barrel shotgun which closes the barrels at the breech.

STOCK: The wooden part of a shotgun or rifle, or the grip panels on the handle of a pistol or revolver.

STOCK, BUTT: The butt section of a firearm in which the forearm is separate from the butt stock.

STOCK, ONE-PIECE: The stock of a rifle in which the butt stock and fore-end are all in one piece.

TAKE-DOWN GUN OR RIFLE: A firearm in which the barrel and adjacent parts can be readily separated from the receiver or action—permitting the arm to be packed in a short container.

TANG: One of the two arms or shanks of the frame or receiver of a gun, extending to the rear, and inletted into the grip of the stock.

THROAT: The forward portion of the chamber where it tapers to meet the diameter of the bore proper.

TRIGGER: The small lever within the trigger guard. When pulled to the rear, it releases the hammer or firing pin, which discharges the cartridge in the chamber.

TRIGGER, SET: A type of trigger that can be set so that it will release the sear with a much lighter pull than the normal trigger.

TRIGGER GUARD: A guard surrounding the trigger (or triggers) of a firearm for general protection and safety purposes.

VELOCITY: The speed of the bullet or shot charge, measured in feet per second at or near the muzzle.

VENTILATED RIB: A raised sighting plane affixed to a shotgun barrel by posts, allowing the passage of air to disperse the mirage rising from a hot barrel which distorts the shooter’s view of the target. Very useful on trap guns.

WATER TABLE: This is the flat space on the under side of the barrels of a break-down, double barrel gun at the breech ^which bed on or form flat surfaces of the frame.

ZERO: The range in yards at which the sights of a rifle have been adjusted to center a group of shots at the point of aim at the same distance.

USER ADVICE
this book could save your life

THE SURVIVAL HANDBOOK

ESSENTIAL SKILLS FOR OUTDOOR ADVENTURE

THE SURVIVAL HANDBOOK

THE SURVIVAL HANDBOOK

ESSENTIAL SKILLS FOR OUTDOOR ADVENTURE

DK

LONDON, NEW YORK, MUNICH, MELBOURNE, DELHI

Senior Editors Nicky Munro, Richard Gilbert

Senior Art Editors Michael Duffy, Gillian Andrews

Editors Bob Bridle, Chris Hawkes,
Philip Morgan, Gill Pitts, Clare Weber

US Editor Chuck Wills

Designers Sarah-Anne Arnold, Katie Eke,
Brian Flynn, Phil Gamble, Sharon Spencer

Lead Illustrator Mike Garland
Assisting Illustrators Darren Awuah,
Phil Gamble, Peter Liddiard, Mark Walker

Production Editor Tony Phipps
Production Controller Norma Weir

Managing Editor Stephanie Farrow
Managing Art Editor Lee Griffiths

Art Director Bryn Walls
Publisher Jonathan Metcalf

First American Edition, 2009

Published in the United States by
DK Publishing, 375 Hudson Street
New York, New York 10014

09 10 11 12 10 9 8 7 6 5 4 3 2 1

SD308—April. 09

Copyright © 2009 Dorling Kindersley Limited
All rights reserved

Without limiting the rights under copyright reserved above, no part of this publication may be reproduced, stored in or introduced into a retrieval system, or transmitted, in any form, or by any means (electronic, mechanical, photocopying, recording, or otherwise), without the prior written permission of both the copyright owner and the above publisher of this book.

Published in Great Britain by Dorling Kindersley Limited.

A catalog record for this book is available from the Library of Congress.

ISBN 978-07566-4279-2

DK books are available at special discounts when purchased in bulk for sales promotions, premiums, fund-raising, or educational use. For details, contact: DK Publishing Special Markets, 375 Hudson Street, New York, New York 10014 or SpecialSales@dk.com.

Printed and bound in Hong Kong by Hung Hing

Discover more at
www.dk.com

IMPORTANT NOTICE

Some of the techniques desribed in this book should be used only in dire emergencies, when the survival of individuals depends upon them. The publisher cannot be held responsible for any injuries, damage, loss or prosecutions resulting from the use or misuse of the information in this book. Do not practice these techniques on private land without the owner's permission, and obey all laws relating to the protection of land, property, plants, and animals.

CONTENTS

8 Introduction

1

BEFORE YOU GO

16 **Introduction: Prepare yourself**
18 Getting into shape
20 Mental preparation
22 Planning your journey
24 Emergency plan of action
26 **Introduction: Know your environment**
28 Temperate environments
30 Tropical environments
32 Mountain environments
34 Desert environments
36 Cold environments
38 Marine environments
40 **Introduction: Get the right gear**
42 Choosing your kit
44 Choosing a backpack
46 Dressing for the outdoors
50 Extreme survival—in the wilderness
52 Sleeping systems
56 Eating on the trail
58 Camping stoves
60 Your survival kit

2 ON THE TRAIL

64 **Introduction: Find your way**
66 Maps and map-reading
68 Get your bearings
72 Route finding
74 Navigating without a compass
76 Natural navigation
78 How weather works
80 Weather phenomena
82 Understanding local weather
84 **Introduction: Make a move**
86 Traveling on foot
88 Crossing rivers
90 Scrambling and climbing
92 Extreme survival—in the mountains
94 Moving over snow
98 Using pack animals
100 Four-wheel driving
104 Kayaking and canoeing
106 Building a raft
108 Swimming

3 CAMP CRAFT

112 **Introduction: Camp essentials**
114 Organizing your site
116 Staying clean
118 Making fire
120 The elements of fire
122 Char cloth and fire can
124 Types of fire
126 Making sparks and flames
128 Extreme survival—in the desert
130 Fire by friction
134 **Introduction: Manual skills**
136 Man-made cordage
138 Natural cordage
142 Tying knots
146 Using cutting tools

4 TAKING SHELTER

154 **Introduction: Taking shelter**
156 Hollows and caves
158 Use-anywhere shelters
162 Forest shelters
166 Tropical shelters
172 Extreme survival—in the jungle
174 Desert shelters
176 Shoreline shelters
178 Snow shelters



5 WATER AND FOOD

184 **Introduction: Find and treat water**
186 The importance of water
188 Finding water: Temperate climates
192 Finding water: Hot climates
194 Finding water: Cold climates
196 Finding water: At sea
198 Carrying and storing water
200 Treating water
202 **Introduction: Find and prepare food**
204 Wild cooking
206 Edible plants
208 Catching fish
212 Preparing fish
214 Extreme survival—adrift at sea
216 Trapping animals
220 Preparing small mammals
222 Preparing large mammals
224 Preparing other animals
226 Catching birds
228 Preparing birds

6 IN AN EMERGENCY

232 **Introduction: In an emergency**
234 Assessing your situation
236 Attracting rescuers
242 Wild animals
244 Extreme survival—in cold conditions
246 Environmental hazards
250 Surviving at sea

7 FIRST AID

258 **Introduction: First aid**
260 First aid essentials
262 Flesh wounds
266 Bites and stings
268 Poisonous plants and intestinal parasites
270 Bones, joints, and muscles
272 Treating exposure
274 Treating shock
275 Breathing difficulties
276 Unconsciousness
278 Moving a casualty

APPENDIX

Wild food

280 Temperate plants
282 Desert plants
284 Tropical plants
286 Plants in cold climates
288 Coastal plants
290 Mammals
292 Birds
294 Amphibians and reptiles
296 Fish
298 Invertebrates

Natural Dangers

300 Wild animals
302 Insects and arachnids
304 Poisonous plants

306 Resources
308 Glossary
312 Index
319 About the author
319 Acknowledgements

INTRODUCTION

HAVING TAUGHT SURVIVAL SKILLS FOR MANY YEARS, I have learned that four elements must be in place for a survival situation to have the chance of a positive outcome: knowledge, ability, the will to survive, and luck. While knowledge and ability can be learned, the will to survive is hard-wired into our survival mechanism and we may not know we possess it until we're put to the test. For example, people who were fully trained and well-equipped have given up hope in survivable conditions, while others, who were less well-prepared and ill-equipped, have survived against all odds because they refused to give up.

> “Always apply the **principle** of the **least** amount of **energy expended** for the **maximum** amount of **gain**”

Anyone venturing into the wilderness—whether for an overnight camping trip or a lengthy expedition—should understand the basic principles of survival. Knowing how to survive in a particular situation will allow you to carry out the correct beforehand preparation, choose the right equipment (and learn how to use it), and practice the necessary skills. While you may be able to start a fire using a lighter, for example, what would you do if it stopped working? Equally, anyone can spend a comfortable night inside a one-man bivy shelter, but what would you do if you lost your pack? The knowledge gained through learning the skills of survival will enable you to assess your situation, prioritize your needs, and improvise any items of gear that you don't have with you.

> Treat the **wilderness** with **respect**: carry in only what you can **carry out**; leave only **footprints**, take only **pictures**

Survival knowledge and skills must be learned—and practiced—under realistic conditions. Starting a fire with dry materials on a sunny day, for example, will teach you very little. The real survival skill is in understanding why a fire won't start and working out a solution. The more you practice, the more you learn (I am yet to teach a course where I didn't learn something new from one of my students). Finding solutions and overcoming problems continually adds to your knowledge and, in most cases, will help you deal with problems should they occur again.

There are differences between teaching survival courses to civilians and teaching them to military personnel. Civilians have enrolled on (and paid for) a course to increase their knowledge and skills, not because their life may depend on it (although, should they find themselves in a life-threatening situation, it may well do), but because they are interested in survival techniques in their own right. In contrast, the majority of military personnel who undergo survival training may very well need to put it into practice, but they invariably complete the training simply because they are required to do so. While no one in the military forces would underestimate the importance of survival training, it is a fact that, if you want to fly a Harrier, or become a US Marine Mountain Leader, survival training is just one of the many courses you must undertake.

In the military, we categorize the four basic principles of survival as protection, location, water, and food. Protection focuses on your ability to prevent further injury and defend yourself against nature and the elements. Location refers to the importance of helping others to rescue you by letting them know where you are. The principle of water focuses on making sure that, even in the short term, your body has the water it needs to enable you to accomplish the first two principles. Food, while not a priority in the short term, becomes more important the longer your situation lasts. We teach the principles in this order, but their priority can change depending on the environment, the condition of the survivor, and the situation in which the survivor finds him- or herself.

> “Understanding your **environment** will allow you to select the **best equipment**, adopt the **best techniques**, and learn the **correct skills**”

We also teach advanced survival techniques to selected personnel who may become isolated from their own forces, such as when operating behind enemy lines. The four principles of survival remain the same, but we substitute “location” with “evasion”. The military definition of evasion is recognized as: “being able to live off the land while remaining undetected by the enemy”. This involves learning how to build a shelter that cannot be seen, how to maintain a fire that doesn’t give away your position, and how to let your own forces know where you are but remain undetected by the enemy.

In military training, and with most expeditions, the equipment with which you train will be specific to a particular environment—marines operating in the jungles of Belize will not pack a set of cold-weather clothing, for example; and Sir Ranulph Fiennes won't practice putting up his jungle hammock before venturing into the Arctic! However, the standard practice of being equipped and trained for a specific environment can prove to be a major challenge for some expeditions. During my career as a survival instructor, for example, I have been fortunate enough to have worked on two of Sir Richard Branson's global circumnavigation balloon challenges with Per Lindstrand and the late Steve Fossett. For these expeditions, the responsibility for selecting the survival equipment and training the pilots was a unique, if daunting, task. The balloon would be flying at up to 30,000 ft (9,000 m) and would potentially cross every type of environment: temperate, desert, tropical rain forest, jungle, and open ocean. While it would have taken some very strong winds to blow the balloon into the polar regions, we did fly—after a brief and unplanned excursion into China—across the Himalayas.

> “The more you understand **how and why** something works, the more prepared you will be to **adapt and improvise** should it be **damaged or lost**”

We also had to train for the worst-case scenario, which would be a fire in the balloon capsule. A capsule fire would leave the three pilots no option but to bail out, potentially from a great height, breathing from an oxygen cylinder, at night, and anywhere in the world, whether over land or sea. The chances of them landing in the same vicinity as each other under such circumstances would be slim to non-existent, so each pilot would need not only the necessary equipment to address the priorities of survival in each environment, but also the knowledge to be able to use it confidently and alone. We addressed this challenge by providing each pilot with survival packs devised for specific environments, a single-man liferaft (which provides shelter that's just as good in a desert as it is at sea) and realistic training with the equipment contained in each pack. As the balloon moved from one environment to another, the packs were rotated accordingly, and the pilots re-briefed on their survival priorities for each environment.

> “There is a **thin line** between **being in awe** of an environment and **being at its mercy**”

As you read this book and plan to put the skills and techniques covered here into practice, you will typically be equipping yourself for just one particular type of environment—but it's important that you fully understand that one environment. Make sure you research not only what the environment has to offer you as a traveller—so that you can better appreciate it—but also what it offers you as a survivor: there is sometimes a very thin line between being in awe of the beauty of an environment and being at its mercy. The more you understand both the appeal and dangers of an environment, the better informed you will be to select the right equipment and understand how best to utilize it should the need arise.

Remember, no matter how good your survival equipment, or how extensive your knowledge and skills, never underestimate the power of nature. If things aren't going as planned, never hesitate to stop and re-assess your situation and priorities, and never be afraid to turn back and try again later—the challenge will always be there tomorrow. Finally, always remember that the most effective method of dealing with a survival situation is to avoid getting into it in the first place.

Colin Towell

> Twenty years from now you will be **more disappointed** by the things **you didn't do** than by the **ones you did do**
>
> MARK TWAIN

BEFORE YOU GO

PREPARE YOURSELF

Most survival situations arise in one of two ways: either you are thrust into a situation not of your making and beyond your control, or (as is more often the case) a situation develops because of a sequence of events that could have been avoided had you recognized the danger signs and acted on them at the earliest opportunity. Unfortunately, most survival situations occur as a result of ignorance, arrogance, an overconfident belief in one's own ability, or because the forces of nature have been underestimated.

In the military forces, troops prepare for survival situations by learning the basic principles and techniques and then practicing them until they become second nature. The more you practice a particular survival skill, the more you'll understand how and why it works, and the more you'll understand your own strengths and weaknesses. Many helicopter crew members who have been involved in a survival situation, for example, report that, having ditched their aircraft in the sea, they could not remember how they subsequently

In this section YOU WILL DISCOVER...

- how keeping **in shape** can keep you **out of trouble...**
- the importance of a **positive mental attitude...**
- that where there's a **will to survive** there's a **way to survive...**
- the difference between a **coping strategy** and an **aggravating factor...**
- how **"show-stoppers"** could **scupper your trip...**
- why an **emergency plan of action** could **save your life...**

escaped from their aircraft and successfully boarded their liferaft. Thanks to their intense training regime, their actions had become instinctive and therefore subconscious.

Whether you're preparing for an overnight camping trip or a year in Africa, the more prepared you are to meet the challenges posed by a particular environment, the more likely you are to be able to cope—both physically and mentally—should you then find yourself confronted with a survival situation.

It would be foolish to think that the amount of prior preparation required for an expedition is directly related to the length of the trip or its perceived danger.

ACCIDENTS CAN HAPPEN anywhere. One of the most important things you can do to improve your chances of survival is to let people know where you're going and when you'll be back. Leave an itinerary of your trip with family or friends, and arrange a time when you will call to let them know you are safe.

In many instances, simply making sure you have a cell phone with you can prevent an accident becoming a major survival incident. In 2007, a professional athlete, out running with her dog in Moab, Utah, slipped on ice, fell approximately 60 ft (18 m), and broke her pelvis. Having left her cell phone in her vehicle, she managed to survive for two nights in the freezing desert before rescuers were finally lead to her by her dog.

In a separate incident in 2008, a farm worker in the UK caught his arm in machinery. Unable to attract attention and not having his cell phone with him, he was faced with a stark choice when the machinery caught fire: bleed to death, burn to death, or cut off his own arm with a pocket knife—he chose the latter.

> “Never assume that the amount of **prior preparation** required is directly related to the length of a trip or its **perceived danger**”

GETTING INTO SHAPE

IN ANY SURVIVAL SITUATION you're likely to be at your best, both physically and mentally, in the moments before the situation occurs. From that point on, through lack of sleep, food, and water, your situation will deteriorate until your rescue. Being in good physical condition will help you overcome the challenges you'll face in a survival situation.

KNOWING YOUR LIMITS

Having an idea of how fit you are and knowing how much you are capable of achieving before entering the wilderness means you can set yourself realistic goals—which will help to keep you out of danger.

THE BENEFITS OF EXERCISE

Over time, exercise induces changes such as weight loss, as well as improved posture, physique, strength, agility, mental alertness, and stamina. These are all vital attributes should you find yourself in a survival situation.

HOW FIT ARE YOU?

A fit heart pumps blood more slowly and efficiently than an unfit one. The hearts of women, children, and older people beat faster than those of young adult males. Take your pulse first thing in the morning—this is known as the "base rate." As the table below shows, the faster your pulse returns to its base rate after a period of exercise, the fitter you are. Note that < denotes "less than" and > denotes "more than".

AGE	20-29	30-39	40-49	50+
RATING	BASE RATE			
MEN				
Good	<69	<71	<73	<75
Average	70-85	72-87	74-89	76-91
Poor	>85	>87	>89	>91
WOMEN				
Good	<77	<79	<81	<83
Average	78-94	80-96	82-98	84-100
Poor	>94	>96	>98	>100

AGE	20-29	30-39	40-49	50+
RATING	BEATS AFTER EXERCISE			
MEN				
Good	<85	<87	<89	<91
Average	86-101	88-102	90-105	92-107
Poor	>101	>102	>105	>107
WOMEN				
Good	<93	<95	<97	<99
Average	94-110	96-112	98-114	100-116
Poor	>110	>112	>114	>116



Back: *strong back muscles help when you are carrying a heavy backpack*

Brain: *your ability to concentrate for long periods of time improves with increased fitness*

Heart: *improved cardiovascular fitness will enable you to walk greater distances*

Lower back: *strengthening your lower back muscles improves core strength, and your ability to carry heavy loads*

Legs: *improved leg strength is a huge benefit when you're on the trail*

Calf muscles: *lower-leg strength helps on rocky terrain*

Balance: *sure-footedness and confidence are useful qualities on rocky terrain*

FIT FOR THE CHALLENGE

Survival fitness is not about trying to run the 100 meters in 10 seconds; it's about stamina and endurance, and about knowing your physical limitations and being able to work with them. It is also about understanding that you may have to push yourself beyond your limits and that having a positive mental attitude is paramount to survival—the mind will often give up long before the body has reached its limit. Bear in mind that every task in a survival situation will sap your energy.

EXERCISING REGULARLY

Any effective training schedule must include at least three 45-minute sessions per week, with exercises that raise the heartbeat to more than 120 beats per minute.

STARTING A FITNESS PROGRAM

To spend time in the wilderness with a pack on your back requires a combination of strength and aerobic fitness. Training in the gym before you set off will strengthen your heart, lungs, and leg muscles, and will increase your stamina levels when you are out on the trail.

- Seek expert instruction and guidance wherever possible.
- Start gradually and then build up your routine progressively.
- Never try to work through injuries—rest and seek medical advice.
- Devise a relevant fitness program; there are many websites and organizations that provide you with detailed fitness programs for various levels of specific activities, from training for a trek through the jungle to mountain-biking along the Appalachian Trail.
- Duplicating in training what you'd like to be able to achieve on the trail will allow you to build up reference points about how your body works, and how it copes in different situations. The more you know about how you perform, the better equipped you'll be on the trail.

WARMING UP AND COOLING DOWN

Time spent warming up and cooling down after exercise will help to improve your endurance levels and will also accelerate the recovery process. Get into the habit of starting and ending your session with a five-minute jog.

GO FOR A CHECK-UP

It's a sad fact that the majority of us don't have regular medical check-ups. Many people work on the principle that you only need to see a doctor or dentist if something is wrong. However, you should always make sure that you start any adventure or wilderness trek in top condition. Therefore, before you set out, pay a visit to your doctor and dentist and make sure that your body and teeth are in good condition.

VISIT THE DOCTOR

- Let the doctor know of any ailments that have been a concern to you during the course of the previous year.
- Tell the doctor where you are going and enquire about relevant inoculations or medication that you should be taking with you.

VISIT THE DENTIST

- Have any problems with your teeth dealt with before you go. Any minor dental problem will almost certainly turn into full-blown toothache when you least want it to.

USEFUL EXERCISES

If you already get regular exercise, you'll find yourself far more comfortable in a survival situation than your more sedentary counterparts. Any pre-expedition training regime should include plenty of stretching, aerobic exercise, and weight-training.

STRETCHING YOUR UPPER BODY AND BACK

Regularly stretching your arms, neck, chest, and shoulders will help your body to maintain a strong core. This will be of great use when it comes to activities such as rock climbing or using trekking poles. Undergoing a regular back-stretching routine will loosen the back muscles, making them more flexible and less susceptible to injury, and will increase both the back's range of motion and its endurance.

STRETCHING YOUR LEGS

Because your leg muscles bear the brunt of the work, leg stiffness is a common complaint at the end of a long day on the trail. Stretching your legs will improve your flexibility, increase blood circulation, and relax your muscles. Concentrate on your calves, quads, and hamstrings.

AEROBIC EXERCISES

Also called cardiovascular fitness, aerobic fitness refers to the ability of your heart, blood vessels, and lungs to supply oxygen and nutrients to the rest of your body during sustained physical activity. Regular aerobic exercise—such as swimming, jogging, or cycling—will reduce the risk of developing coronary heart disease or high blood pressure, will help you to manage your weight and increase your stamina levels, and will make your heart stronger and more efficient, thus improving blood flow around your body.

WEIGHT-TRAINING

Increased muscle strength will enhance your ability to perform everyday tasks such as lifting, carrying, and walking. A regular weight-training program will improve your posture, build muscle density around the joints and bones, improve your sense of balance, help your stress management abilities, aid sleep, and reduce the chances of you sustaining an injury. In addition, research has shown that a regular resistance-training program can improve your metabolic rate by up to 15 percent, which will help you shed any unwanted weight at a faster rate.

MENTAL PREPARATION

REGARDLESS OF WHETHER you're backpacking through a remote area, or on a day hike in familiar territory, a situation may arise that changes your circumstances for the worse. Very quickly you move into the unknown, which causes tremendous psychological and emotional stress, known as "psychogenic shock." Understanding this will help you to deal with it better and reduce its impact.

INDIVIDUAL REACTIONS TO DISASTER

People react to survival situations in different ways, although you can expect to find some common emotional reactions in victims who are experiencing, or have survived, a disaster situation. You may experience one or more of them during or after any survival experience or trauma.

YOUR RESPONSE TO DISASTER SITUATIONS

Your psychological response to a survival situation is crucial. Statistics show that 95 percent of people who die with psychological trauma die within the first three days. Losing the will to survive—or suffering psychological disorders that prevent you from coping with the physical conditions—is your main concern. If you break down psychologically, your chances of overcoming a situation will be compromised.

PSYCHOLOGICAL PROGRESSION

It's useful to examine how people are likely to react in a survival situation. Using this knowledge, it's possible to prepare mentally for such eventualities and, in so doing, lessen the impact if the worst should happen to you when out on the trail. Normal psychological reactions to disaster tend to occur in a set pattern of four stages: the pre-impact period, the impact period, the recoil period, and the post-trauma period (see right). Contrary to popular belief, people don't normally panic, although it can be contagious if someone does.

AGGRAVATING FACTORS	HUNGER	THIRST
Reactions to disaster can result from a direct blow to the psychological system, such as extreme shock, but they can also be brought on, or aggravated by, other factors. As with all psychological problems, knowing what these aggravating factors are, and attempting to avoid them—or at least recognizing what they might lead to—will maximize your chances of preventing or overcoming the problem. The most common aggravating factors are: hunger, thirst, fatigue, seasickness, and hypothermia.	Initially, hunger is not a problem, but a long-term lack of food will cause psychological changes to occur. Symptoms include: ▪ Apathy ▪ Irritability ▪ Depression ▪ Lack of concentration	Thirst is a serious problem, especially for survivors at sea or in the desert, and its effects are more acute than hunger. Agitation is commonplace; other symptoms include: ▪ Irrational behavior (see box, right) ▪ Delusions ▪ Visual hallucinations

COPING STRATEGIES	TRAINING	MOTIVATION
There are many things you can do to prepare yourself psychologically for a survival situation—such as learning about what you should expect if the worst were to happen—and to cope better if you find yourself in one. As with all survival skills, prior knowledge is power, and will help you to deal with a survival situation far more successfully. The main areas to think about are: training, motivation, attachment, hope, acceptance, and helping others. Developing coping strategies is an important technique for survival.	People who are properly prepared, who know their environment and how to use their equipment, and have an understanding of what to expect in a survival situation, will be far more effective if they find themselves in one. Adequate training and practice using your equipment will help you to function effectively at an automatic level. Prior knowledge is key to your survival.	Often known as "the will to survive," motivation involves a refusal to accept death, and to hang on to the belief that you were not meant to die under these conditions. It involves overcoming the emotional and physical discomforts of extreme conditions. Linked to motivation is the ability to establish goals, work out the steps to those goals, and to follow those steps through.

PANIC

Panic arises from the fear of what might happen rather than what has happened. It tends to occur when people are trapped, or if there is a time limit to their escape.

DEPRESSION

Depressed people will sit among chaos and debris vacantly gazing and not replying to questions. They're unaware of their situation and unable to help themselves, so risk further injury.

HYPERACTIVITY

Hyperactive victims are easily distracted, and are full of chatter, ideas, and often unhelpful suggestions. Sufferers can reach this stage after a state of depression.

ANGER

Aggression, anger, and hostility are common reactions to trauma. They're often irrational and may even be directed at the rescuers or medical staff trying to help them.

GUILT

Some sufferers feel guilty for surviving, and for not having done enough for others—and some irrationally blame themselves for bringing about the incident.

SUICIDE

Disaster victims have been known to commit suicide immediately after being rescued, in some cases when they're already safe in the hospital. Victims should be closely monitored.

Pre-impact period

The "pre-impact" period is divided into two stages:

- Threat: danger exists but, though obvious to those who recognize it, those who will not accept it respond with denial and under-activity.
- Warning: threat of danger is now apparent to all; response is now likely to be over-activity.

Impact Period

This is the life-threatening stage. Statistically, individuals behave in one of three ways:

- 10–20 percent of people are calm and retain full awareness.
- Up to 75 percent of people are stunned, bewildered, and unable to react rationally.
- 10–25 percent exhibit extreme behavior, such as screaming.

Recoil period

This follows on directly from the impact period; for example, victims may have escaped a sinking ship and are in the liferafts. It can last for up to three days, but generally lasts for around three hours. In most cases, it is characterized by a gradual return to normal reasoning abilities, awareness, and emotional expression.

Post-trauma period

If the recoil period is not fully successful, individuals may develop psychiatric disorders. The full impact of the incident becomes apparent and a range of emotions—guilt, depression, anxiety, aimlessness, and a feeling of bereavement—may develop. These are often referred to as Post-Traumatic Stress Disorders (PTSD).

FATIGUE

In many cases, physical exhaustion is present from the outset. At other times, it may result from sleep deprivation and the physical hardship endured over time. Most survivors agree that fatigue overwhelms them, but when they want to sleep they can't—they have an inability to relax. Fatigue causes a deterioration in mental and physical performance, followed by a psychological and physical debility.

SEASICKNESS

Seasickness often brings about an overwhelming desire to curl up and die, which in survival situations can easily become a reality. It's important not to give in to this urge. Fight seasickness with the following methods:

- Keep a fixed point such as the horizon in sight.
- Take small sips of water (not salt water) if you have sufficient supplies—but ration them if you're in a life or death situation.

HYPOTHERMIA

Hypothermia (see p. 273) produces both physical and psychological effects—the psychological consequences occur early in the condition, and cause:

- Loss of concentration
- Loss of memory
- Motor impairment
- Faulty decision-making
- Irrational behavior

IRRATIONAL BEHAVIOR

Irrational behavior can take many forms. Examples include the earthquake victims who were found collecting flowers instead of helping the injured, and famously, the band of the *Titanic*, who played while the ship sank rather than trying to save themselves.

ATTACHMENT

One of the strongest motivating forces for survival is the desire to be reunited with principal figures of attachment in your life. These may include:

- Husbands
- Wives
- Partners
- Children
- Grandchildren
- Close friends

HOPE

To hope means to entertain ideas that a distressing situation will improve and get better. In any survival situation it's important to cling onto hope, despite information or perceptions to the contrary. Thinking positively will help to ward off psychological trauma. It's often easier to be optimistic in a group situation than it is if you're on your own, as people can support each other.

ACCEPTANCE

An inability to accept one's situation or condition leads to frustration, anger, and irrational behavior, and it's important to avoid these feelings in a survival situation. The ability to accept the situation doesn't equate to giving in to it—far from it. Those who have this ability, and know when to be active and when to be passive often have a better chance of long-term survival.

HELPING OTHERS

First, monitor your own condition and check that you're really up to the task. Determine who is genuinely disturbed rather than showing "normal" reactions. Psychological first aid is only required for those who are failing to recover. Simple words of comfort and interest will make the majority who are numbed more responsive. Those who are disturbed should be monitored closely. Avoid giving sedatives.

PLANNING YOUR JOURNEY

WHETHER YOUR TRIP involves a day out with your backpack, or a full expedition over weeks, crossing continents in four-wheel-drive vehicles, you need to plan it very carefully. The plan for your day out won't be as detailed as it would be for the longer expedition, but it's equally important. It's a good idea to have a basic planning outline for your most regular trips, to which you can add supplementary information as your trips become more involved.

WARNING!
The social customs of a country are not the same all over the world. Many cultural differences stem from ancient cultural or religious pasts, and are taken extremely seriously. While ignoring or breaking some customs may lead only to embarrassment, breaking others can result in a penalty, punishment, or even imprisonment. Cultural differences may require females in your group to dress so that they don't show bare arms or legs, or they may dictate which hand you use to greet someone politely. Always research a country's customs thoroughly when planning your trip.

MINIMIZING THE "IF ONLY"

There's no way that you can plan for every eventuality—there are just too many variables—but what you can do is look at the type of trip you intend to take, and ensure that if a situation arises you're not left wishing you'd done something differently. The time to minimize the chances of an "if only" situation is during the planning stage. Look at the potential problems and risks, plan to avoid them, and equip yourself with the knowledge and/or equipment to deal with them if they arise.

THE SIX P'S

Remember the six p's: **P**rior **P**lanning and **P**reparation **P**revents **P**oor **P**erformance. Research has shown that the longer and more complicated the trip is, the less likely there is to be a major "survival" situation. This type of trip is likely to be well organized, and potential problems will have been considered. This means that they can either be avoided, or that there will be mechanisms in place to deal with them. In many ways, simply having a good understanding of how to deal with a situation, and being able to interpret the basic principles of survival, can prevent a minor problem from escalating into a disaster. In a survival situation, it may be your knowledge, combined with your ability to improvise, that determines whether you become a survivor or a statistic.

ORGANIZATIONAL PRIORITIES

When planning for a trip always start with the most important things—known as the "show-stoppers." These are generally the things that would actually stop the trip from happening in the first place if not organized in advance. If you then work backward from the show-stoppers to items that would simply make the trip more comfortable, most other things will fall into place. The chart on the right lists the things that you definitely cannot do without.

	SHOW-STOPPERS
MONEY	▪ You'll need enough to cover your needs plus extra for emergencies. ▪ It must be in the correct currency for the country you are visiting. ▪ Ensure your ATM card is set up for use in that particular country. ▪ Make sure you have a secure way of storing your money.
PASSPORT	▪ Your passport must be valid. If you need to renew it, do so well in advance. ▪ Some countries require your passport to be valid for a number of months after your visit. ▪ Keep your passport number in several places, such as inside your survival kit. ▪ Keep your passport safe, and in a waterproof container, such as a Ziploc bag.
VISA	▪ Research the regulations regarding visas relevant to the countries you're traveling to. ▪ Find out how to apply, how far in advance you should apply, whether or not you can apply in the country, and what other documents you need. ▪ As with your passport, always keep your visa safe, dry, and in good condition.
VACCINATION	▪ Check the regulations for the country—many have strict vaccination policies. ▪ Ensure you have the vaccinations, and any boosters, within the correct timeframe. ▪ Some inoculations last only for six months, so for extended trips you might have to have more while away. This can usually be arranged through local hospitals or clinics.
TICKETS	▪ Make sure you have the correct tickets for your journey. ▪ Read the tickets and make sure they have the correct names, dates, and locations. ▪ Should you need to prove your movements, always keep your tickets in a safe place and never throw them away—often the return journey is included on the same ticket.
INSURANCE	▪ It's advisable to get insurance against your trip being cancelled. ▪ Ensure that your insurance will cover your medical expenses should the worst happen. You don't have to be climbing Everest—even a twisted or broken ankle when hill-walking could prove to be very expensive if you don't have adequate insurance.

YOUR TEAM

If you're embarking on a trip with a group, remember that team dynamics will play an important part in the success, or otherwise, of your trip. Stressful situations—and particularly survival situations—can bring out the best, or the worst, in people. When planning a long trip, it's always a good idea to plan several shorter trips beforehand, to use as practice sessions. These will not only help you decide what equipment to take, and provide you with an opportunity to practice using it, but will also allow team members to assess how they work together as a group. This can help you to organize your team more effectively.

MIXED-GENDER GROUPS

If the team has both male and female members, it's important to factor this into the planning stage. You'll need to consider sleeping and washing arrangements, who carries what, who is responsible for what, and so on. All this should be planned in detail before you set off. It should also be noted that taking it for granted that the women will cook the meals while the men make the shelters is not the best way to start an expedition.

MIXED-AGE GROUPS

When planning your trip, remember that different age groups may have different levels of fitness, which will affect the pace of your group. However, what older members may lack in pace, they may make up for in expedition experience.

PREPARATION THROUGH TRAINING

Training yourself both mentally and physically—and practicing with the equipment you'll be using—may seem like the obvious thing to do, but in many cases the obvious can often get overlooked. You'll get the most out of your trip if you're mentally and physically prepared to a level that means you can operate within your own capabilities and comfort zone. This will allow you to enjoy and appreciate the experience, as opposed to just getting yourself through it.



TRAINING YOURSELF

Duplicate in training what you intend to do on your trip. Build up your training gradually, over a period of weeks and months, and take into account the following:

- **The environment**: research the weather conditions you'll be facing, and look at the extremes as well as the average. For example, desert areas may be hot during the day, but can drop to below freezing at night.
- **Weight:** increase the amount of weight you carry until you're eventually carrying what you intend to take. This will not only condition you to the weight but also help you to decide just what's important to take and what's not.
- **Distance:** if your trip involves covering a certain distance a day, then train for that distance. This will give you an indication of whether it's achievable and sustainable.
- **Language**: if visiting a country in which your native language is not widely spoken, it will be beneficial if you can learn some useful phrases. Take a phrase book or an electronic translator.

TRAINING WITH EQUIPMENT

Use your equipment as much as you can, and find out the best way to operate it through practice under realistic conditions (see box, below). This will highlight its strengths and weaknesses, and allow you to determine both its capabilities and your own—the compass may be working perfectly, but practice may highlight the fact that you're not confident enough using it, in which case you'd need to do further training before you set off on your expedition. The wrong time to be trying to find the jack and spare wheel on your rented vehicle is at night, in the rain, with the mosquitoes looking at you as their next free meal. Before you set off, always think about the various skill demands required, and ensure that you're capable of addressing those demands.

OPERATING UNDER REALISTIC CONDITIONS

When training with new equipment, always practice using it under realistic conditions. For example, if you're going to be using your GPS in cold conditions, can you operate it using the gloves you have selected? If you're pitching a tent, have you got **all** the necessary components, and can you put it up in the dark and rain?

EMERGENCY PLAN OF ACTION

UNFORTUNATELY, EVEN THE MOST meticulously planned, thoroughly equipped, and best-executed trip can run into difficulties. Unforecasted strong winds could trap you and your kayak on an island overnight, or a sprained ankle could leave you unable to climb down the rocks you climbed up so easily. Each of these survival scenarios are difficult to predict, but could easily happen.

USING YOUR EPA

An EPA should contain up-to-date information about you as a person. This may change very little over the years, so you may only need to create a standard EPA and just update the details specific to each trip.

RUNNING INTO PROBLEMS

It's important to make sure that you have done all you can to help yourself, and help any rescue attempt that might take place if you do have any problems. Always remember that there are two sides to any survival or rescue situation: the part that you play and the part that the rescue services play. However, the effectiveness of the rescue services can be greatly increased when they have access to all relevant information—in many cases this arrives too late. It's vital to keep people informed of your intended whereabouts, so that they can raise the alarm if you deviate from your plans.



Rescuers will be able to find and help you quicker if they know you're in need of their assistance

WORST-CASE SCENARIO

In the military, every mission that's undertaken, particularly in a theater of conflict, has plans in place for the worst-case scenario. Each part of the mission is meticulously planned, and the team completes a form that states what their basic intention will be should anything happen during the various stages.

IF THE WORST HAPPENS

Having planned for the worst, should the team find themselves in difficulty, the rescue group will not have to try to second-guess what the team will do—they will have a clear indication of the team's intent and can plan effectively and decisively around this information. The team will be found quicker as a result. It's a good idea to apply this principle to your own trip.

KEEPING PEOPLE INFORMED

A good way of keeping your friends, family, and the relevant rescue services informed of your whereabouts is to write down the details of your trip, including pertinent itinerary places and dates, so that if you don't reach your destination when planned, the alarm can be raised. Similar to the "worst-case scenario" principle practised by the military (see left), an "emergency plan of action" (EPA) should be prepared by anyone venturing into the great outdoors (see right). Give a copy to your next of kin and group members, and keep a copy on your person. Where applicable, inform local services, such as park and ranger stations, of your intentions. Remember to inform these people when you arrive safely at your destination.

WRITING AN EMERGENCY PLAN OF ACTION (EPA)

The best way to determine what should be included in your plan is to look at the worst-case scenario you could find yourself in, and ask yourself what information your next of kin would need to know about you and your intentions if they felt they had to raise the alarm. In addition, if you did go missing—particularly in another country—there are many things that the relevant rescue services would need to aid their efforts, for example a recent photograph, your passport details, what equipment you have with you, what languages you can speak, and your skills. The clearer their understanding of you, your abilities, and your intentions, the easier their job will be. In addition, the more information your next of kin have, the more proactive they will feel in your rescue.

EMERGENCY PLAN OF ACTION FORM

Full name as appears on passport:
John William Smith

Date of birth:
(dd/mm/yy)
05/28/60

Height: *5′10″ (178cm)*
Weight: *168 pounds (76 kilos)*
Hair color: *Brown*



Passport number:
2008XXXXX63
Expires:
11/03/13

Driver's license number:
JHY280771smit
Expires:
12/28/22

Distinguishing marks (scars, tattoos):
Small scar—center of forehead
Large scar—right hand, middle finger
Chinese symbol tattoo—right arm

Languages spoken (fluent/basic):
English—native
French—basic
German—basic

Medication:
Medication—anti-malaria tablets

Allergies:
Amoxicillin

Swimmer: *Strong swimmer*
Outdoor skills/experience:
Attended basic military survival training.
Attended basic bushcraft course
Experienced in living outdoors



Next of kin 1: *Father*
William Smith
1018 Furlong Avenue
Brunswick, Maine,
USA 04555

Next of kin 2: *Brother*
Andrew Smith
1023 Parkglen
Ashford, Kent,
TM24 5HZ
UK

Tel: *(001) 55 555 2356*

Tel : *(0044) (0)155 555 2357*

Email: *willsmith@internet.com*

Email: *andrewsmith@internet.com*

Trip details:
Campsite 1 = Grid ST456654
Campsite 2 = Grid ST654987
Vehicles: Landrover 1 = white, reg MH55 555
Landrover 2 = blue, reg MH56 555
Group = Ben Jones, Kim Smith, and myself
Day 1: Park Landrover 2 at Campsite 2, and drive in Landrover 1 to Campsite 1
Day 2: Follow well-defined path along the Derwent Line Trail, aiming to camp overnight at Grid 4561559
Day 3: Continue along the Derwent Line Trail, aiming to be at Campsite 2 by mid-afternoon. Camp overnight at Campsite 2
Day 4: Travel in Landrover 2 to campsite 1 and retrieve Landrover 1

Foreseeable problems/intentions:
Day 1: None
Day 2: None but will use Ranger Station 18, grid 555555 (Tel. 666 6666) as an emergency rendezvous point
Day 3: None but will use Ranger Station 19, grid 666666 (Tel. 555 5555) as an emergency rendezvous point
Day 4: None

Communications plan:
Will speak to Dad on the morning of Day 1 and try to phone during the trek but am unsure of cell reception once on the trail so don't worry if you hear nothing.
Will phone Dad again when we reach campsite 2 on day 3.

My mobile: *07979 555555*
My email: *jws@internet.com*
Alt. No: *Ben 05555 555555*
Alt. No: *Kim 05555 555555*
Alt. No: *Campsite 1 555 555 55555*
Alt. No: *Campsite 2 555 555 55555*

Date: *November 23, 2009*

KNOW YOUR ENVIRONMENT

The continued survival of the human race can be attributed to our ability to adapt to our environment. While we may have lost some of our ancient ancestors' survival skills, we have, in their place, learned new skills as and when they have become necessary. The issue we face today is that the gap between the skills we once had and the skills we now have grows ever wider as we rely more heavily on modern technology. Therefore, when you head off into the wilderness, it is important to fully prepare for the environment.

Before a trip, research how the native inhabitants dress, work, and eat. How they have adapted to their way of life will help you to understand the environment and allow you to select the best gear, adopt the best techniques, and learn the correct skills. This is crucial given that most survival situations arise as a result of a sequence of events that could have been avoided—while you may have no control over the aircraft crashing, for example, you can recognize a change in the weather and choose whether to continue or turn back.

In this section **YOU WILL DISCOVER...**

- the difference between **tundra** and **taiga...**
- why you should **step-up** the size of your **survival footprint...**
- the **way to go** when it comes to **snowy peaks** or **swampy creeks...**
- how to avoid **getting lost** in the **permafrost...**
- the best way to **stay at the top** of the **food chain...**
- how to **feel at home** where the tropical **butterflies roam...**
- how a high-visibility **survival suit** could really **get you noticed...**

The four basic principles of survival are:

protection, location, water, and food. In most survival situations, this is also the order in which you should prioritize them.

P **PROTECTION** You must stay in a condition that allows you to be proactive in your continued survival and rescue. Physically, you should protect yourself against injury, the elements, and wildlife. Mentally, you should protect yourself against emotions that could rob you of the will to live: fear, guilt, despondency, and depression, for example. The best way to achieve this level of protection is to light and maintain a fire. Not only does it offer physical protection against the elements and wildlife, but it also provides a sense of security and familiarity that can help normalize even the most dire situation.

L **LOCATION** Your second priority is to recognize the importance of your location to your chances of survival and rescue. You will usually have two options: stay or go. Your preferred option should be to remain where you are and use anything at your disposal to mark your location to aid rescuers in their efforts to find you. If you can't stay where you are (perhaps because you are in imminent danger) you may have no option but to move to another location that provides either a better chance of survival or rescue, or both. Select a location aid that offers you the best chance of attracting attention in the environment in which you're traveling.

W **WATER** Put simply, water is the essence of life. While you may be able to survive for a few days without it, your ability to function and carry out even simple mental and physical tasks will be dramatically reduced in less than 24 hours. However, if you are injured, if the weather conditions are very hot, and if your workload is particularly heavy, for example, your survival time without water could be reduced to just a few hours. You should learn how to procure water in the particular environment in which you're traveling, and understand the ways in which a lack of water affects you.

F **FOOD** The importance of food is directly related to the length of time you are in a survival situation: the longer the situation lasts, the more important food will become in helping you stay fit and healthy. Even with a moderate workload, going without food for five to seven days will not kill you. You will, of course, feel hungry, you will grow tired, your movements will slow, and your body will lose its ability to repair itself. However, unless you're malnourished before you enter a survival situation, you are unlikely to starve to death within a week. Your body needs water to digest food, so always remember to prioritize water over food.

> “We rely so heavily on **modern technology**: water at the **turn of a tap**; heat at the **flick of a switch**; food raised, harvested and **prepared by others**”

TEMPERATE ENVIRONMENTS

THE TEMPERATE ZONES are the two regions between the Tropic of Cancer and Arctic circle, and the Tropic of Capricorn and Antarctic circle. Typified by seasonal variations in climate, conditions can include baking hot summers, freezing cold winters, and rainfall all year round. Landscape features range from forests and snow-covered peaks to grasslands and deserts. Although most temperate regions are highly populated, don't be lulled into a false sense of security—a worst-case scenario can still arise just a few miles from help.

WARNING!

Brown bears inhabit extensive wilderness areas in the northern temperate zone, and are the most dangerous temperate animal. The Grizzly, found in North America, is the most likely to attack humans.

TEMPERATE FEATURES

Although they contain a wide range of environmental features, the temperate zone's typical feature is forest, ranging from deciduous trees that shed their leaves in fall to coniferous trees that retain their leaves all year round. Grassland predominates where forests have been cleared, while highland areas contain hills and mountains. The abundance of rain means that rivers and lakes are common, and swampy wetlands form in areas with poor drainage.

TEMPERATE ESSENTIALS

Climate and terrain can vary widely in temperate areas, so preparation for a range of eventualities is essential:

- Don't underestimate the temperate environment. Although the vast majority of the human race lives in temperate zones, the diversity of terrain and weather means that survival equipment and knowledge must be broad enough to cope with a wide range of situations and conditions.
- Temperate weather can change very quickly, so check the local forecast before you set off, and carry a small AM/FM radio so you can listen to local weather reports.
- Plan a realistic and achievable route, and prepare an EPA (see pp. 24–25). Be ready to re-assess your route during the trip.
- Take clothing for the full range of conditions you may encounter.
- Carry a survival kit (see pp. 60–61), knife, emergency equipment, cell phone, and first-aid kit (see pp. 260–61)—and know how to use them.
- Carry adequate water, and equipment to collect and purify more if necessary.
- Carry some form of basic shelter, even if only going out for the day.
- Always take a map and compass, and consider using a GPS as an aid.



L ***High ground:*** *elevated areas afford a view of your surroundings and may indicate which area offers the best prospects for your survival, or where to go to find rescue*

P L ***High ground:*** *night-time temperatures are lowest at altitude, so descend to warmer levels before dark. Beware of rock slides and run-off during downpours*

L ***Tracks:*** *indicators of human activity, tracks may lead to rescue*

L W F ***Rivers:*** *watercourses may be a way out of the area if you have, or can improvise, a flotation aid or raft (see pp. 106–07). They also provide fresh water for drinking, cooking, and washing, and may contain fish*

WHERE TO FIND TEMPERATE AREAS

Deciduous forests are scattered throughout the temperate zones, but the largest occur in eastern North America, western Europe, and east Asia. Extensive coniferous forests are found in the higher latitudes of North America and Eurasia, while grassland is most common in continental interiors.





TYPICAL CLIMATE

Vancouver lies on the Pacific coast of Canada, and experiences a typical temperate climate of warm summers and cool, wet winters.

SURVIVING IN TEMPERATE AREAS

Most temperate environments have a relatively mild climate and good natural resources, making them favorable places for long-term survival. Water can be found in most areas, wood for building shelters and lighting fires is usually abundant, and different types of edible plants and animals can be found at different times of year if you know where to look. Potentially the greatest threat is hypothermia (see pp. 272–73), a particular problem in cold, wet and windy conditions, especially in winter and at night, when temperatures tend to fall even further.

WILDLIFE AND PLANT LIFE

Plant and animal life can be abundant in temperate areas and represents both a valuable food resource and a potential hazard. Shoots and stems, leaves, roots, nuts, or berries of some plants are edible, but only when positive identification—or at the least, the Universal Edibility Test (see p. 206)—is achieved. Small mammals, birds, insects, reptiles, and fish can also be found, but may be difficult to catch and kill, and must be prepared and cooked properly. Wildlife can also pose a threat—snakes, spiders, and scorpions may bite and, though rare, bears, wolves, and cougars may attack if cornered.



P L F ***Woodland:*** *tree cover affords protection from the elements, and wood for shelter, cooking, and signal fires. It is also a source of edible flora and fauna*

P L ***Open ground:*** *areas with no vegetation offer a clear view of dangers, and are ideal for deploying location aids, such as signal fires*

P ***Running water:*** *site your shelter a safe distance from running water. Flooding is a risk, and animals and insects are drawn to water. The noise may also hide the sound of animals or rescuers*

L ***Sheltered areas:*** *site your shelter on the lee-side of hills, but make sure the hill doesn't interfere with your radio signal. Choose a spot that faces the sun to maximize warmth and light*

FIND OUT MORE...

P **PROTECTION Shelters** pp. 156–65, 178–81 **Fire** pp. 118–33, 204–05 **Dangers** pp. 242–49, 300–05

L **LOCATION Navigation** pp. 66–77 **Movement** pp. 86–89 **Signaling** pp. 236–41

W **WATER Finding** pp. 188–91 **Purifying** pp. 200–01

F **FOOD Plants** pp. 206–07, 280–81 **Animals** pp. 208–13, 216–29, 290–99

TROPICAL ENVIRONMENTS

THE TROPICAL ZONE stretches from the Tropic of Cancer to the Tropic of Capricorn, and is centered over the Equator. A range of environmental features occurs in this area depending on the local climate, from lush, humid, biodiverse tropical rain forests to dry, more sparsely vegetated tropical scrub. With adequate preparation and caution you should be able to survive unsupported for extended periods—the jungle holds just as many resources as dangers.

WARNING!

Mosquitoes are responsible for more fatalities than any other creature in tropical areas. They carry a range of diseases including malaria and yellow fever, which kill millions of people every year.



W F ***Tropical scrub**: water can be found in the rainy season, while animal movements may reveal sources in the dry season. Edible plants and animals can be found*

L ***Tracks**: due to the rapid rate of growth in the rain forest, tracks are likely to be fresh and may lead to rescue. Even remote areas may contain tracks left by loggers, prospectors, or local people*

P L ***Tropical scrub:** provides shade from the sun and materials for fire and shelter, but may be home to dangerous wild animals. Dense vegetation during the rainy season may impede visibility*

TROPICAL ESSENTIALS

Rain forests contain everything you need to stay alive, so remember the following tips when venturing out:

- While the jungle teems with predatory wildlife (such as big cats, crocodiles, and anacondas) that sees you as part of the food chain, it is the small creatures that can make life miserable. Most animals in the jungle want to avoid you as much as you want to avoid them—making a noise will scare most away.
- High humidity encourages infections, so keep everything covered (sleeves down, gloves on), and wash at every opportunity.
- Always sleep off the ground.
- Boil or treat all water. Some water found in plants can be safe to drink, but if in doubt, and if the water is yellow, milky, or very cloudy, treat before drinking.
- Many plants have defense mechanisms and can emit toxic liquids that may sting or burn—if you can't identify it, leave it alone.
- Dry tinder can be hard to find, so if you come across any, collect it and keep it safe and dry—lighting a fire in a moist, humid environment can be challenging.
- The smoke of a signal fire must penetrate through all the layers of the jungle, so light your fire where the canopy is sparse, such as the bend of a river or a clear-cut area.
- Navigation can be difficult, as you may only be able to see a few yards in front of you. Use dead reckoning—walking a short distance to a recognizable feature on your bearing—or pace-counting (see pp. 72–73).
- Rivers in the jungle usually run downhill to civilization and, eventually, the coast.
- Don't fight the jungle—tune in to its rhythm and work with it rather than against it.

TROPICAL FEATURES

Tropical rain forest, which occurs within 10 degrees of the Equator, is the predominant environmental feature in the tropics. But there are several other environment types just a few degrees of latitude away.

VERDANT RAIN FOREST

Tropical rain forests occur in areas with steady year-round temperatures and rainfall. Annual rainfall can reach around 6$^1/_2$–10 ft (2–3 m) and daytime temperatures may reach 90°F (30°C), dropping to 70°F (20°C) during the night. Monsoon (or "seasonal") rain forests occur in areas with a wet and dry season, while montane rain forests, also known as "cloud forests," occur in mountainous areas.

SCRUB AND SWAMPS

Also known as "thorn forest," tropical scrub consists of low, woody plants with thorns, which usually grow in clusters separated by patches of bare ground (grasses are uncommon). Leaves are shed in the dry season, forming a dense, herbaceous layer in the wet season. Swamps are another common tropical feature, and may consist of fresh or saltwater. Freshwater swamps are found in low-lying, inland areas, and consist of masses of undergrowth, reeds, grasses, occasional short palms, and islands. Saltwater swamps often contain mangroves, and occur in coastal areas that are prone to tidal flooding so are best navigated by boat. Visibility in both types of swamp is poor, and movement is difficult.

SURVIVING IN THE RAIN FOREST

While natural resources are abundant in the rain forest, the heat, humidity, number of animals, and voracious rate of vegetal growth can make it an uncomfortable place. Water, materials for shelter and fire, and edible plants may all be found, although identification of plants is crucial to avoid poisonous species. Animal life is everywhere, so sleeping platforms must be built off the ground to avoid biting insects, snakes, and spiders. The greatest danger is becoming lost—navigation is difficult due to dense undergrowth at ground level, and rescuers will struggle to find you beneath the thick jungle canopy.

FIND OUT MORE...

P PROTECTION Shelters pp. 158–61, 166–71 **Fire** pp. 118–33, 204–05 **Dangers** pp. 167, 242–49

L LOCATION Navigation pp. 66–77 **Movement** pp. 106–07 **Signaling** pp. 236–41

W WATER Finding pp. 192–93 **Purifying** pp. 200–01

F FOOD Plants pp. 206–07, 284–85 **Animals** pp. 208–13, 224–29, 292–99



P L W F ***Rain forest:*** *fuel for cooking and signaling fires and material for shelter may be found, although check for deadfalls and other dangers. Water from rain and rivers, and edible plants and animals can be found*

Rain forest emergent layer: *consists of tall trees around 200 ft (60 m) high that have broken through the canopy*

Rain forest canopy: *a uniform layer of trees 60–90 ft (20–30 m) high, whose crowns form a thick canopy that blocks light from the jungle floor*

Rain forest understory: *receives 2–15 percent of sunlight, and consists of young trees and herbaceous plants*

Ground level: *receives less than two percent of sunlight, and consists of dense ferns, herbaceous plants, fungi, and a thick carpet of leaves*

P L ***Swamp:*** *hazardous due to wildlife, fast tides, and obstacles to movement, such as submerged vegetation and deep water. Move to dry land as quickly as possible, or use a raft or flotation aid to leave the area*

L W F ***Rivers:*** *lack of rain forest cover makes rivers a good choice for deploying location aids and being spotted by aerial rescuers, and can be used to leave the area. Also provide water for drinking, cooking, and washing, and fish to eat. Almost all rivers will lead you to civilization*

WHERE TO FIND TROPICAL AREAS

Tropical rain forests are clustered around the Equator. The largest rain forest areas are found in Central and South America, sub-Saharan Africa, southeast Asia, northern Australia, and several Pacific islands.



▨ Rain forest areas



TYPICAL CLIMATE

Iquitos sits on the Amazon river in the heart of the Peruvian rain forest. It lies just south of the Equator and has a typical hot, wet tropical climate.

MOUNTAIN ENVIRONMENTS

THE MOUNTAIN ENVIRONMENT is one of the harshest places for humans to survive. Defined as landmasses with a summit above 2,000 ft (600 m), mountains can be very dangerous places due to their elevation and terrain. Lower temperatures and poor weather are more likely at higher altitudes, so there is a significant risk of hypothermia, frostbite, and altitude sickness, while snow, ice, and precipitous terrain present further hazards. Survival may depend on your ability to descend to areas with better prospects of survival and rescue.

MOUNTAIN FEATURES

Above the treeline, mountain terrain is typically barren, featuring bare rocks, gravel, boulders, and snow and ice, which are most extensive during the winter but may persist at high elevations during the summer. At lower levels, coniferous forest is the predominant feature, dissected by streams and rivers fed by snowmelt. Topographical features include scree slopes, cliffs, ravines, boulder fields, snowslopes, and glaciers.

ELEVATION CHANGE

Mountains of sufficient height may have vastly different ecosystems at different elevations, due to harsh conditions at high altitude. Plant and animal life varies at different elevations, so the natural resources available for survival will differ according to height. Mixed deciduous trees are common on low slopes and conifers grow at intermediate levels, but thin out to grass, isolated shrubs, moss, and lichen higher up. At the highest levels, high winds, frost, snow, and ice discourage any growth.

WARNING!

One of the most dangerous animals in mountain areas is the cougar, also known as the puma, panther, and mountain lion. Found in North and South America, more than 20 percent of attacks are fatal.



P L ***Mountains:*** *shelter is limited and dangers include unpredictable weather and rock falls. They may require special equipment and knowledge to negotiate*

P L ***Elevated areas:*** *high areas offer good visibility for location aids, but nearby mountains may interfere with communication devices. Rescue at altitude is hazardous—helicopters struggle for lift in the thin air*

P L ***Scree and cliffs:*** *dangerous and tiring to negotiate. Offer poor protection from the elements. Descend quickly and safely*

P ***Avalanche-prone slopes:*** *avoid at all costs—the smallest noise or movement can trigger a collapse*

P L F ***Forest areas:*** *rich in resources. Offer protection from the elements, material for shelters, cooking, fires, and signaling, and edible flora and fauna*

P ***Shelter:*** *always site your shelter away from areas of avalanche risk, especially if avalanche debris is present*

W F ***Streams:*** *usually a clean and safe source of water for drinking, cooking, and washing, and may also contain fish for food. Always treat the water if you have the means. If following water courses downhill in poor visibility, take care. The route could end in a waterfall, with no means of retracing your steps*

L F ***Watercourses:*** *streams and rivers provide a quick, defined route, and may be navigable if you have, or can improvise, a raft or flotation device (see pp. 106–09)*

SURVIVING IN THE MOUNTAINS

The prospects for survival are good at lower elevations, where trees provide material for shelter and fire, rivers provide water, and edible plants and animals are likely to be present. At higher elevations vegetation is scarce, so there are fewer options for shelter and food, although water from streams or snow is likely to be available. There may be a risk of avalanche on snow-covered slopes, and crevasses pose a hidden danger in glaciated areas. Cold-related injuries pose the greatest threat (see pp. 270–71).

HIGH-LEVEL HAZARDS

The primary threats to survival at high altitude are cold-related ailments, the most dangerous of which is hypothermia. This occurs when the body's core temperature falls below 95°F (35°C)—if allowed to drop as low as 86°F (30°C), it can be fatal. Frostbite may also occur in the extremities in freezing or cold and windy weather, and may lead to permanent tissue damage. Altitude sickness, which can cause pulmonary or cerebral edema—and in extreme cases, death—is also a risk above 8,000 ft (2,500 m).



P L ***Glaciated areas:*** *inhospitable and dangerous, so avoid if possible. Crossing them should never be attempted alone. If in a group, roping up is essential*

P W ***Snow-covered areas:*** *shelters can be dug from the snow, which can also be melted for water*

FIND OUT MORE...

P PROTECTION Shelters pp. 156–65, 178–81 **Fire** pp. 118–33, 204–05 **Dangers** pp. 242–49, 300–01

L LOCATION Navigation pp. 66–77 **Movement** pp. 90–91, 94–97 **Signaling** pp. 236–41

W WATER Finding pp. 188–91, 194–95 **Purifying** pp. 200–01

F FOOD Plants pp. 206–07, 280–81, 286–87 **Animals** pp. 208–13, 216–23, 290–97

MOUNTAIN DISTRIBUTION

Mountains are found on every continent, but the major ranges are the Himalayas and Karakoram in Asia, the Andes in South America, the Rocky Mountains in North America, and the Alps and Pyrenees in Europe.



■ Mountain ranges



TYPICAL CLIMATE

Lhasa, the capital city of Tibet, lies at 11,972 ft (3,649 m) on the Tibetan Plateau, sometimes known as "the roof of the world." The high altitude means that winters are cool, and precipitation is relatively low because it mostly falls as snow, which has just 10 percent of the density of rain.

MOUNTAIN ESSENTIALS

High altitude and lower oxygen levels place higher-than-normal demands on even a fit body, so be prepared. Survival in the mountains is also tough on equipment.

- Respect nature and err on the side of caution—mountains are unforgiving, and rescue is unlikely to be quick or easy.
- Plan an achievable and safe route, and prepare an Emergency Plan of Action (see pp. 24–25).
- Dress in layers (see pp. 46–47). Start a walk lightly dressed (cold) and add or remove layers as necessary.
- Wear a hat (up to 70 percent of body heat is lost through the head) and gloves—cold fingers will hinder your functions.
- Tie loose items of clothing (hat, gloves, sunglasses) to your person—a lost glove could result in a lost hand, or life.
- Take a flashlight—weather changes and unforeseen problems may mean you are on the mountain in low light or darkness.
- Always carry basic equipment to give adequate protection if forced to camp overnight, such as a bivy sack and sleeping bag.
- Check avalanche warnings and carry an avalanche transceiver.
- Contact with snow makes clothing wet and less effective.
- If moving over snow, make a pair of improvised snow shoes (see pp. 94–95).

DESERT ENVIRONMENTS

THE DESERT ENVIRONMENT is a hostile place for human survival due to temperature extremes and the scarcity—or absence—of water. Most deserts are either hot and dry or cold and dry, and all typically receive less than 10 in (250 mm) of annual rainfall. They are areas of extremes, where heat exhaustion and hypothermia are threats, and flash floods may rapidly replace dry conditions. A harsh place to survive, the desert should only be entered by those who are prepared.

WARNING!
Desert areas are home to a range of venomous snakes, including the black mamba of eastern and southern Africa. It is particularly dangerous due to its aggressive nature and highly venomous bite.

DESERT FEATURES

The popular depiction of a desert is of a dry, sandy landscape with searing skies and temperatures among the highest in the world. Such areas do exist, but the desert environment has far greater diversity, from cold deserts in the polar regions to highlands, grassland, and broken, rocky terrain that contain "wadis" (seasonal stream beds).

HOT, DRY DESERTS

Temperate and tropical deserts are usually hot and dry due to high daytime temperatures, which leads to low precipitation and high evaporation. There may be months or even years between rainfall, which usually occurs in dramatic bursts but then quickly drains into seasonal stream beds (wadis), or evaporates either in the air or soon after touching the hot ground. Very little rain soaks into the ground, which results in sparse vegetation that has evolved to maximize water, usually via extensive root systems that collect moisture, waxy skin and leaves that prevent water loss, and stems or roots that hold water. At night, in winter, and at higher altitudes, freezing temperatures and frost may occur.

GRASSLANDS

Known as savanna in tropical areas, grasslands often border desert regions, and experience a similarly dry climate for most of the year. The key difference is that they also experience a wet season, which accounts for the more diverse and extensive vegetation. Temperate grassland features grasses, shrubs, and small pockets of trees, while savanna is typically more varied, with denser tree cover, bushes, and grasses that grow tall during the wet season but die back in periods of drought. Wildlife is more prevalent, including predators. Wildfires may spread during the dry season, and play an important role by destroying dead plant matter and adding fertile ash to the soil.



P L W F ***Oasis:*** *vegetation affords shelter, but animals drawn to the water may pose a threat. Highly visible landmarks, oases are a vital water resource and often contain edible plants and animals*

W F ***Elevated areas:*** *hills may hold pools of trapped rainwater, and may be home to edible animals*

WHERE TO FIND DESERT AREAS

Although deserts occur on every continent, the largest hot desert in the world is the Sahara in North Africa, which forms part of a desert band stretching through the Middle East and into south and central Asia.





TYPICAL CLIMATE

Tindouf lies in the heart of the Sahara, and experiences a typical hot-desert climate. Precipitation is virtually zero all year round, while temperatures peak in the summer.

SURVIVING IN THE DESERT

Hostile temperatures and few natural resources limit chances of survival in the desert. Water and shelter are scarce, if not non-existent, edible vegetation is limited, and animals hide from the sun in the day. Wadis, grasslands, and higher ground all hold better prospects. The greatest dangers are dehydration and heat exhaustion (see pp. 272–73), although African savanna areas may be home to large, dangerous mammals. The main killers are big cats, hippos, rhinos, elephants, and crocodiles.



P L W ***Sand dunes:*** *shelter from the elements is poor, but visibility for location aids and for spotting rescuers is good. Observing converging animal and bird tracks or movements may indicate the direction to a water source.*

P L ***Mountain areas:*** *higher ground is colder than surrounding areas and may be hazardous to negotiate, but visibility for location aids, and reception for communication devices are good*

P ***Wadi areas:*** *vegetated areas may be found where water has collected after rain, such as below cliffs or outcrops, providing shelter and material for fire. Beware of flash floods in stream beds*

W F ***Wadi areas:*** *rivers flow in wadis during flash floods, and water may be retained below the surface long after the flood has passed. Wadis are also the habitat of edible animals*

L W F ***Savanna:*** *visibility and reception for communication devices are likely to be good but will be reduced in the wet season when plants growth flourishes. Water sources vary depending on the season*

P ***Savanna:*** *protection from the elements is limited, although material for building shelters may be found in the wet season. Sunstroke and dehydration are killers, so seek shade during the hottest parts of the day. Beware of snakes or scorpions in shaded areas, big cats and large mammals, and nocturnal animal activity*

FIND OUT MORE...

P PROTECTION Shelters pp. 156–61, 174–75 **Fire** pp. 118–33, 204–05 **Dangers** pp. 242–49, 300–05

L LOCATION Navigation pp. 66–77 **Movement** pp. 100–01 **Signaling** pp. 236–41

W WATER Finding pp. 192–93 **Purifying** pp. 200–01

F FOOD Plants pp. 206–07, 282–83 **Animals** pp. 216–21, 224–29, 292–95

DESERT ESSENTIALS

Survival in the extreme conditions of the desert is impossible without full preparation. Consider the following:

- Always prepare an EPA to notify someone of your plans before entering a desert area (see pp. 24–25).
- Water is life. Do not underestimate your needs, carry extra just in case, and carry equipment to maximize your chances of finding and procuring more (binoculars, surgical tubing, filtration/purification pump) should the worst happen.
- Ask local people about water sources that may not be marked on maps, such as wells used by Bedouin tribes.
- If venturing into remote areas, augment your map and compass with a GPS, and consider taking a PLB or satellite phone (see pp. 236–37).
- If using a vehicle, ensure you carry jacking equipment for use in soft ground, sand mats or ladders for self-recovery, extra water, a shelter, location aids, and any relevant vehicle spares.
- Plan cut-off or safety points into your journey that can be used to divert to in case of an emergency.
- Ensure you know how to accomplish emergency repairs to your vehicle.
- Ask local people about known dangers, such as impassable roads, misleading tracks, and soft-sand areas.
- When using a ladder for self-recovery, tie it to the back of the vehicle so that it's dragged behind once crossed, and can be retrieved when you reach solid ground.
- If your vehicle breaks down, leave it only if staying is no longer safe or feasible—rescuers will search for it first.

COLD ENVIRONMENTS

LOW TEMPERATURES are a potentially lethal hazard, but as long as you can conserve body heat, survival in the cold is quite possible. The ice-covered Arctic and Antarctic polar regions, sub-polar tundra and taiga, as well as parts of most temperate zones during the winter, can all be classed as cold environments. Wet, windy weather can drive moderately cold temperatures down further, increasing the risk of the most lethal cold-weather condition—hypothermia.

WARNING!
The largest predatory land mammal on Earth, the polar bear inhabits the Arctic. Attacks are most likely when the bears are hungry, and are usually fatal.

COLD ENVIRONMENT FEATURES

Outside temperate areas, the typical cold environments are the polar areas, which feature glacial ice sheets and sea ice; tundra, which contains permafrost (permanently frozen soil), small shrubs, mosses, and lichens; and taiga, with extensive conifer forests. Almost half of the northern hemisphere's landmass can be classified as a cold region, due to the influence of cold air masses (see pp. 78–83), while ocean currents and altitude can also have a cooling effect.

POLAR WASTES

The northern polar area is situated over the Arctic Ocean, so largely consists of sea ice, the extent and depth of which varies throughout the year. Because of the lack of land, melting ice is a serious danger. The southern polar area is located over the continent of Antarctica, and contains the largest glacial ice sheet on Earth. Both areas contain ice shelves—glaciers that have extended over the sea—parts of which break off to form icebergs.

TUNDRA AND TAIGA

Latitudes that neighbor the polar areas are home to tundra, an environment of permafrost and vegetation that is stunted due to low temperatures. Taiga is located further away from the poles, where temperatures are high enough to support coniferous forests.



P L ***Mountains:*** *elevated areas give little protection from the elements, but offer good visibility for location aids. They are also ideal points from which to survey your surroundings*

P ***Taiga:*** *forests provide protection from the elements and materials for shelter and fire, although animal life may pose a threat*

P L ***Tundra:*** *during the winter, snow cover means that there is little protection from the elements, and movement is difficult without snow shoes or skis*

P ***Sea ice:*** *dangerous terrain to survive in, sea ice carries risk of exposure, falling through the ice, and polar bears (in northern polar areas). Your location may depend on the ice flow*

L W F ***Sea ice:*** *natural resources to assist signaling your location are limited or non-existent. Water may be obtained from snow or ice, and food from fishing*

SURVIVING IN THE COLD

Natural resources may be scarce in cold environments, so your survival is likely to depend on the equipment and supplies you have with you. Shelters can be dug from the snow to help you stay warm and avoid exposure to freezing temperatures, but material for making fire is limited in polar and tundra areas. Survival is more feasible in the taiga, where wood is available, and fresh water and edible flora and fauna can also be found. The greatest dangers are hypothermia (see pp. 272–73) and—in northern polar areas—polar bears.

LOW-TEMPERATURE DANGER

Heat loss occurs in several ways, and minimizing it is essential to survival in cold conditions. It's important to avoid over-exertion, since heat is lost through sweating, and to cover your head and wear layered clothing to trap radiated body heat. Heat is also lost through conduction—direct contact between the skin and a cooler surface—particularly when wet, since water conducts heat away from the body 25 times faster than air. For this reason, it's vital to wear insulated and waterproof clothing, and to stay dry. Respiration also involves heat loss—each inhaled breath contains cold air, which is warmed as it passes through the lungs, and laden with moisture when exhaled. Reduce heat loss by covering your nose and mouth with a ski-mask or scarf, or by breathing warmer air next to a fire or in a warm shelter.



L W F *Taiga: natural resources are available for making location aids, water sources may be found, and edible flora and fauna are likely to be present*

W F *Tundra: snow and ice can be melted in the winter and ground water is present in the summer, although sources are limited. Vegetation increases closer to the treeline*

COLD ESSENTIALS

The main threats in cold environments are hypothermia and exposure, so ensure you are fully prepared:

- Dress in loose-fitting layers of clothing (see pp. 46–47), avoid overheating, and ensure your clothing stays dry and clean.
- If your hands are cold, don't warm them with your breath, which will make them wet—tuck them under your armpits.
- Regularly check your extremities (face, toes, hands, and ears) for frostnip, the first stage of frostbite (see p. 273).
- Wind-chill is dangerous, so take shelter from the wind at every opportunity, particularly if you are in a survival situation.
- Always ensure that your shelter is well ventilated—keep vent holes clear and check regularly, especially when snow falls.
- Get off the cold ground, snow, or ice—sit on your pack or make a sleeping platform using boughs to avoid losing body heat.
- If fire is your primary means of warmth, triple the amount of firewood you think you need—you will need enough to last the night.

FIND OUT MORE...

P **PROTECTION** **Shelters** pp. 156–65, 178–79 **Fire** pp. 118–33, 204–05 **Dangers** pp. 242–49

L **LOCATION** **Navigation** pp. 66–67 **Movement** pp. 94–97 **Signaling** pp. 236–41

W **WATER** **Finding** pp. 194–95 **Purifying** pp. 200–01

F **FOOD** **Plants** pp. 206–07, 286–87 **Animals** pp. 208–13, 216–23, 290–91, 296–97

WHERE TO FIND COLD AREAS

The Arctic and Antarctic polar areas are the coldest places on Earth, and are found at the furthest points from the Equator. Tundra exists next to polar regions, and is bordered by taiga, which is found in northern Eurasia and North America.





TYPICAL CLIMATE

Archangelsk is a Russian port on the Barents Sea. Located in the taiga zone, it experiences below-zero temperatures for half the year and low precipitation.

MARINE ENVIRONMENTS

POTENTIALLY THE MOST HARSH and challenging of all environments, the sea is unlike any other due to the lack of the most essential requirement for human life—fresh water. Around 70 percent of the Earth's surface is covered by saltwater, ranging from the freezing, wind-torn polar oceans to the warm tropical seas. Winds and currents govern your movement, protection is limited, and natural resources are virtually nil, so reaching land is your best hope for survival.

WARNING!
There are sharks in every ocean, but those in tropical waters are the most aggressive. Around 20 of the hundreds of species have attacked humans, and the most dangerous types are the great white, tiger, and bull sharks.

MARINE FEATURES

The marine environment ranges from the coastal margins, which are shallow enough— 650 ft (200 m) or less—to support a huge array of animal and plant life, to the open oceans, the deepest of which plunge to more than 33,000 ft (10,000 m).

SHELTERED COAST TO OPEN SEA

The coastal margins are home to the majority of ocean life, and include terrestrial areas—the shoreline and intertidal zone—and aquatic—the sea up to the edge of the continental shelf. A variety of environmental features are found, such as sand, rock, and pebble beaches, dunes, cliffs, estuaries, mud flats, mangroves, lagoons, kelp forests, and coral reefs. The open ocean is a more barren environment that supports less life, and is notable for its vast extent, comprising 92 percent of all saltwater. Survival depends on your equipment, supplies, and ingenuity.

OCEAN CONDITIONS

Your protection and location at sea depends largely on the weather—you may need to deal with anything from exposure to the hot sun, to cold, wet, windy conditions and high seas. Conditions are toughest in the South Atlantic Ocean, where winds (known as the "Roaring Forties") are strong all year round, and sea ice is extensive in the winter. Severe seasonal storms occur: hurricanes in the tropical areas of the western Atlantic, typhoons in the western Pacific. India and Southeast Asia also experience severe weather during the monsoon seasons.



L W F ***Rocky shoreline:*** *signaling to rescuers may be difficult, and rescuers may not be able to reach you. Water and food will be limited to crabs, shellfish, birds, and eggs*

P ***Rocky shoreline:*** *difficult to make landfall and to survive on, and poses risk of injury when landing. Progress to safer areas may be difficult or impossible due to cliffs or slippery rocks. Protection from the elements and tides is limited*

F ***Coastal margins:*** *the majority of ocean life is found near the coasts, and most species live within 650 ft (200 m) of the surface*

WINDS AND CURRENTS

Winds and currents follow prevailing patterns, so if you know roughly where you are, you can figure out where they'll carry you. With a drift of just 1 knot, a liferaft can move 24 miles (38 km) from its last known position in 24 hours. It may also drift up to 35° either side of the wind, further widening the search area to more than 400 sq miles (1,000 sq km) in the first 24-hour period, and increasing exponentially over time. Conversely, favorable currents can also be used to help you drift to landfall faster.


Cold winds blow west from the poles to the tropics
Hot winds blow east from the tropics to the poles
Currents in northern hemisphere flow clockwise
Equator
Currents in southern hemisphere flow counter-clockwise
Warm winds
Cold winds
Warm currents
Cold currents



P L **Beach:** *above the high-tide mark, beaches may provide protection from wind and rain, and materials for building shelters, lighting fires, and improvising location aids*

W F **Beach stream:** *streams may drain on to beaches, providing water for drinking, cooking, and washing. Edible plants and animals may be present*

P W F **Liferaft:** *increases your chances of survival and rescue, providing protection against the elements and drowning, and containing essential emergency equipment, including water and food. If land is reached, your raft can be used as a ready-made shelter*

L **Liferaft:** *a highly visible location aid, although at the mercy of wind and currents. It may also contain flares*

P L **Lifejacket:** *effective protection against drowning, and also acts as a basic location aid*

L **Sea anchor:** *also known as a "drogue," it reduces drift and maintains stability. It anchors the trailing side of the liferaft to the water and prevents it from overturning, and stops it speeding down the face of swells or waves. Most importantly, it reduces drift, helping to keep you in the same location and increasing your chances of rescue*

SURVIVING AT SEA

Natural resources in the open ocean are virtually nil, so improvising shelter or location aids is limited to what you have with you. Seasickness, especially in a small liferaft, can seriously affect your ability to remain both hydrated and motivated. Unless you can reach land, your only drinking water will come from rain or mechanical desalination devices—consuming urine or saltwater will only increase your rate of dehydration. Reaching land or shipping lanes greatly increases your chances of rescue.

MARINE ESSENTIALS

Your chances of survival at sea will be greatly enhanced by good preparation, so consider the following:

- Pack sea-survival equipment as if your life depends on it—it might! Other environments allow you to improvise survival and location aids, but not the sea.
- Take emergency immersion-survival suits. They will protect you against the elements and aid flotation, and their color (high-visibility orange or red) is an aid to location.
- Always carry a Personal Locator Beacon (PLB), just in case.
- Take several means of obtaining water, such as a reverse-osmosis pump, which turns saltwater into drinking water, a saltwater desalination kit, a solar still, and rain catchers.
- Always keep a pre-packed emergency bag handy. It should contain; first aid kit, reverse-osmosis pump, emergency beacon, solar still, water, flares, fishing kit. (see pp. 250).
- If your vessel sinks, do not abandon it until absolutely necessary. Stay nearby unless it is unsafe to do so—anything that gives you a bigger "survival footprint" will increase your chances of being rescued, and you may be able to retrieve provisions from the vessel.
- If imminent rescue is unlikely, you will need to ration your water. Consider how much you have, how much can be procured, the chances of seasickness (which leads to dehydration), and the likelihood of being rescued later on.
- Protect yourself from the elements (sun, wind, cold, heat, and salt) as well as you can—prevention is better than cure.
- The sea, especially in rough conditions, can sap the will to live quicker than any other environment. Seasickness is literally draining, resulting in lost fluid, energy, and motivation. Take anti-seasickness tablets at the earliest opportunity—even before abandoning ship—so that you can keep them down, and keep taking them as recommended.

FIND OUT MORE...

P **PROTECTION** **Shelters** pp. 156–61, 176–77 **Fire** pp. 118–33, 204–05 **Dangers** pp. 250–55, 300–01

L **LOCATION** **Movement** pp. 106–07 **Signaling** pp. 236–41

W **WATER** **Finding** pp. 196–97 **Treating** pp. 200–01

F **FOOD** **Plants** pp. 206–07, 288–89 **Animals** pp. 208–13, 224–29, 292–99

GET THE RIGHT GEAR

Whether you're equipping yourself for a lengthy expedition or just a day trip, it's important to choose the correct equipment and clothing. The wrong time to realize that your gear isn't up to the job is when your life depends on it doing what it was designed to do.

When selecting gear, it's always a good idea to work backward from a worst-case-scenario survival situation. Think about what you would need to survive if the worst happened. This is your "first-line" equipment, which you should carry with you at all times. It should enable you to address the basic principles of survival relevant to the environment you are in, and consists of the clothing you would wear and your basic survival equipment—your survival tin and belt-order (see pp. 43, 61).

Once you have organized this basic equipment, you can then decide what pieces of essential gear would make your expedition enjoyable rather than just survivable. This will probably consist of a bivy or tent, a sleeping bag, cooking equipment and food, and something to carry it all in.

In this section **YOU WILL DISCOVER...**

- the **meaning** of the term "**bomb-burst gear**"...
- that it's always **good to share** when you're **in a group**...
- which **backpacks** are the **best backpacks** to pack...
- why you should **hike around the house** to **break in your boots...**
- a good reason to take a **three-season tent...**
- how to **sleep** like a **mummy...**
- what **gorp** is and **when** you should **eat it...**

It's at this stage that you should conduct a short trial to check that your chosen gear will fit in your pack and that you can comfortably carry it.

Finally, any spare capacity can be utilized for non-essential "luxury" items, such as an inflatable mattress and pillow, an MP3 player, or a book. Double-check that your gear works and that you know how to use it properly. The more you understand how and why a piece of equipment works, the better able you will be to improvise should it be damaged or lost.

With each venture into the wilderness, your confidence in your abilities and that of your equipment will increase. As it does, you may want to explore the world of ultralight camping.

ULTRALIGHT CAMPING refers to the careful selection of your three largest items of gear to dramatically reduce the load you have to carry. A standard tent, pack, and sleeping bag have a combined weight of approximately 20 lb (9kg). Ultralight camping has the potential to halve the weight of your "big three."

- Take a hooped bivy instead of a tent and choose a low season-rated sleeping bag (wear your day clothes inside the bag for extra warmth).
- You can then reduce the size of your pack because your tent and sleeping bag are smaller.

Trekking with less equipment but still staying safe allows you greater freedom to enjoy the wilderness—carrying less weight puts less strain on your body, enabling you to cover greater distances. Ultralight camping can become addictive and is safe if you use common sense—but never compromise on the quality of equipment. Try:

- Using a hexamine stove to cook food and boil water—you won't have to carry a stove and fuel.
- Taking one pot to cook food and boil water.
- Using natural materials as a mattress.

> "The **wrong time** to realize that **your equipment** isn't up to the **task in hand** is when **your life depends** on it doing what it was **designed to do**"

CHOOSING YOUR GEAR

FORWARD PLANNING IS ESSENTIAL when you're deciding on what equipment to take on your trip. You'll need to assess your own personal requirements, the likely demands of weather and terrain, and the amount of gear you'll actually be able to transport. With a little forethought, you'll be as well equipped as you can be for any situation.

PACKING FOR YOUR TRIP

You will first need to weigh up your particular kit requirements against the limitations of your chosen mode of transport (see below). It's then vital to organize and prioritize your gear (see opposite) to ensure that any items you may need in a survival scenario are always close at hand, should the worst happen.

KEY PACKING TIPS

- Pack your gear in reverse order: the things you want to get to first should be the last things you pack.
- Stash items you may need during the day in side or lid pockets, for easy access.
- Coil and tape long straps so that they aren't a snagging hazard.
- Use a dry bag inside your backpack.
- Ensure that all pockets are fully closed and zipped.
- Air out anything packed wet as soon as you stop for the day.

HOW MUCH TO PACK

The environment of the region you're traveling to will dictate the type of equipment you will need to take with you, but your proposed mode of transport is the main constraint on the quantity of kit you can take (see chart, right). The more gear you have to carry yourself, the fewer luxuries you can take: the added weight will make traveling uncomfortable, use up too much valuable energy, slow your progress, and also limit the distance you can travel each day. It's also worth considering whether you can reduce the weight and volume of the kit items you're taking (see box, below).

LIGHTENING THE LOAD

When you're going to be traveling on foot, it's important to get rid of all the excess weight and volume you can, even if it's only by a small amount. The larger and heavier your backpack, the harder you will find the journey. If you have already ruthlessly pared your gear down to the bare essentials, try to reduce the weight or volume of the kit itself. First concentrate on the big three items: tent, sleeping bag, and backpack. Consider using a hooped bivy or tarpaulin rather than a tent; look for a lighter sleeping bag—some can weigh as little as 2lb (0.9 kg); and consider buying a backpack with a lighter frame.

WEIGHT AND SPACE RESTRICTIONS

ON FOOT	Backpacks (see pp. 44–45) are available in a wide range of volumes—from 30 liters (a day pack) to 80 liters (suitable for a trip of a week or more). Bear in mind that you'll have to carry whatever gear you take with you, and that the weight of the pack will determine what you're realistically able to achieve each day in terms of distance and activity. Pack only the bare minimum: there's no room for luxuries when traveling on foot.
MOUNTAIN/ TOURING BIKE	Pannier bags for bicycles are designed to fit on front, rear, or side pannier racks, and are available in a range of shapes, sizes, and capacities (from 5 to 50 liters). Larger bags will provide you with enough space to pack essentials, such as tent, sleeping bag, cooking equipment, and spare clothes, but you'll be restricted by the weight, and also by the need to carry cycle-maintenance gear, such as spare tires, inner tubes, cables, and tools.
MOTORCYCLE	Side panniers have a capacity of up to 80 liters and tank bags up to 25 liters, and weight is not a major issue. However, you'll need to take extra protective equipment, maintenance tools (including spare tires), and, in some cases, spare fuel, all of which will impact on available space.
PACK ANIMAL	Ideal for rough terrain, such as mountains or desert, pack animals can carry serious weight. A horse can transport up to 20 percent of its body weight; a camel can carry a weight of up to 990 lb (450 kg)—although 330 lb (150 kg) is more common—but you'll need to factor in the animal's food and water.
VEHICLE	The size of the vehicle will determine the amount and the weight of gear you can take with you, but you shouldn't have to compromise; extra equipment can be packed in peli boxes—waterproof storage containers with a hard, plastic exterior—that can be strapped to the outside of the vehicle. The main issue will be the weight-versus-fuel ratio: the heavier the vehicle, the more fuel it will use.
CANOE/ KAYAK/BOAT	Some kayaks and canoes are designed to bear loads of up to 660 lb (300 kg), including the craft's occupant(s), so you should be able to take all of your essential gear, plus a few luxuries. Given your proximity to the water, keeping your gear dry is the main priority. Weight and space restrictions don't apply for larger vessels.

PRIORITIZING YOUR KIT

However much gear you decide to take, you should group individual items into one of three categories—first-line, second-line, and third-line—according to their importance to your survival in a worst-case scenario. It's very unlikely that you'll be able to carry all of your equipment all of the time, and in an emergency situation, you may not have time to gather it all together. However, by prioritizing your gear beforehand, you'll have all your essential items on your person, or close enough to grab at a second's notice.

FIRST-LINE GEAR

Known as "bomb-burst gear" in the military, first-line gear (see right) is your basic survival equipment. If something goes wrong and you have to abandon the bulk of your gear to avoid injury, or death, what you're standing in is all you'll have to help you survive. First-line gear should therefore comprise crucial items of outdoor clothing, along with essential items for navigation and safety. Your bushcraft knife, firesteel, and belt pouch make up your belt order (see pp. 60–61). You'll need to risk-assess your particular situation and adapt your kit priorities accordingly, as conditions change, meaning that your first-line gear may alter as the day progresses. Bear in mind that if a removed layer of clothing goes into your backpack, it's no longer part of your first-line kit.

SECOND-LINE KIT

Second-line gear is everything you would need to stay safe on a daily basis under normal conditions. It can either be packed in a small day pack, or contained in pouches on a belt, the idea being that you carry it at all times. For example, a climber may decide to leave the bulk of his or her equipment (third-line gear) while attempting to reach the summit of a peak. By proceeding with first- and second-line gear, the climber is sacrificing equipment for weight and speed, but is still safe, as they have the essentials on them. Examples of second-line gear can include:

- A spare set of clothes, a bivy sack, and cordage
- Emergency rations and first-aid kit (see p. 260)
- Hexamine stove (see p. 58–59) and items to make a hot drink
- Matchless fireset (see p. 118), and a metal cup

THIRD-LINE GEAR

Also known as your "sustainment load," third-line gear is essentially the equipment you need to keep yourself alive and to function for longer periods of time. How much third-line gear you have will ultimately depend on your mode of transport and the amount of equipment you can carry. Examples of third-line gear include:

- A form of shelter—a tent or a tarpaulin
- Cooking utensils, such as a stove or cooking pot
- A backpack
- Food stores
- A sleeping bag and sleeping mat
- Any large water containers or hydration packs
- Wash kit and sanitary items



Hat: *protects your face, neck, and head from the sun*

Sunglasses: *protect your eyes from the sun. Attach a neck cord for security*

Compass, whistle, flashlight, and lighter: *carry essential items around your neck for quick and easy access*

Water bottle: *strap to outside of day pack for easy access*

Wristwatch: *choose a hiking watch with a built-in compass and barometer/altimeter*

Cell phone: *keep in a secure pocket, or a waterproof bag on a cord around your neck*

Survival tin: *keep in a secure pocket*

Map: *keep at hand at all times and draw a simple copy on waterproof paper to keep in your survival tin*

FLASHLIGHTS

A flashlight is a piece of first-line gear, even if you don't intend to be out in the dark, because situations can change unexpectedly. Modern flashlights use LEDs, and are small, lightweight, powerful, and very efficient. Opt for a "hands-free" headlamp and tape a spare set of batteries to your head-band. Also include two miniature Photon (LED) flashlights in your survival kit (see pp. 60–61).



CHOOSING A BACKPACK

BACKPACKS ARE DESIGNED to enable hikers to carry large loads comfortably. They are made from a variety of materials, most of them waterproof. However, you should always use a separate waterproof bag inside your backpack to ensure your sleeping bag and spare clothes are kept dry; they are of little use in a survival situation if they get wet.

CARRY ONLY WHAT YOU NEED

Regardless of your pack size, you are the one who has to carry it. If in a group, many communal items can be shared. Try not to double up on basics (a party of four does not need four tubes of toothpaste, for example).

WHAT DO YOU NEED?

Your choice of backpack will depend on a number of factors. How long is your trip? How much do you intend to carry? What type of gear will you be taking with you? The answers to these questions will determine the size of pack—known as the "capacity"—that is right for you. Pack sizes range from 30 liters (a day pack) to 80 liters or more (suitable for trips lasting a week or more).

BACKPACK FRAMES

If you have chosen a medium- to large-sized pack, you will have to choose between an internal- or an external-frame pack.

DAY PACK

Day hikers can sometimes find themselves in trouble because they are not carrying the appropriate equipment to protect them from the elements. A day pack provides you with the means to carry essential items such as food, water, maps, compasses, and protection from cold and wet weather on a day trip.


Elastic cord strapping allows you to attach gear to the outside of the pack
Side pouch can be used to carry a water bottle

INTERNAL-FRAME PACKS

Internal-frame packs are narrower in profile than their external-frame counterparts and tend to be longer, with either one or two internal compartments and very few pockets on the outside. The frame is integrated within the pack and usually consists of stays or flat bars, about 1 in (25 mm) wide and $\frac{1}{10}$ in (3 mm) thick, made from plastic. Straps on the outside allow you to compress the pack, which prevents the items inside the pack from shifting and throwing you off-balance.


Compression straps reduce bulk and keep contents of pack in place
Additional compartment for quick access to essential items, such as wet-weather gear

EXTERNAL-FRAME PACKS

An external frame houses the pack on a lightweight tubing framework. They are great for heavy loads, as the pack sits more squarely on your hips. They are also cooler to carry than internal-frame packs, as the air can circulate between your back and the pack. External-frame packs usually have more pockets on the outside, which allows you to pack your items by category, rather than packing everything into one or two compartments. This makes locating items easier and allows you to unpack only the compartment you need, rather than the entire pack. Chest and waist straps ensure a comfortable fit.


Outside pockets provide extra storage
Extra items can be attached to the frame

FITTING A BACKPACK

Once you have chosen a backpack of the right size, design, and features for your trip, you will have to make sure that it's a comfortable fit. You will need someone's help, but here are a few tips for ensuring your new pack sits comfortably on your back.


Measure from prominent vertebrae at base of neck
Measure to the top of hip bones

1 First measure your back. The pack you choose should be based on the length of your torso.


Shoulder straps should be snug but arms should still move freely

2 Make sure the pack is a comfortable fit, allowing for any extra layers of clothing.


Load-lifter straps can be tightened to balance weight on shoulders
Chest strap keeps the shoulder straps stable
Hip belt should sit comfortably on your hips

3 You can now fine-tune the pack's fit by adjusting the shoulder and hip straps.

PACKING A BACKPACK

Always pack in reverse order: the items you need first should go in last. Heavy items should be placed close to your back to prevent the pack pulling away from your shoulders.


Use a cloth bag to hold personal items
Keep raingear at the top of the pack
Store daily essentials in outside pocket
Carry your water bottle in an upright and accessible position
Use the lower compartment for sleeping bag and mat
Secure extra water on outside of pack
Strap tent to the bottom of the pack

MAKING A SIMPLE PACK FRAME

In a survival situation, having something to carry your gear will be a huge advantage. All you need to make your own improvised backpack is a knife, some wood, some cord, and a waterproof sheet.


Attach one end of cord to the upper notch
Attach both cord ends to the central post

1 Cut a light bough about 1 ft (30 cm) below the point where it branches, leaving about 3 ft (1 m) above the fork.


Trim off any knots from the wood

2 Cut notches on all three ends of the bough and tie lengths of cord around the notches to serve as straps to go over your shoulders.


Attach gear to frame

3 Wrap your gear in a groundsheet or waterproof poncho and tie it as high as possible onto the frame on the side opposite the straps.


Make sure gear is attached securely to the frame
Hold straps away from shoulder to avoid chafing

4 Don't be tempted to overload your improvised backpack, even though it should be able to support a good weight.

DRESSING FOR THE OUTDOORS

MODERN OUTDOOR CLOTHING is technologically advanced and highly sophisticated. New materials and designs are extremely lightweight, durable, and versatile. To make the most of your gear, choose the fabrics and combinations of clothes most suited to the environment and conditions in which you are traveling.

REGULATING BODY HEAT

Don't be tempted to overdress. Sweat can soak you as much as rain, and a sudden change of temperature can leave you vulnerable to hypothermia. Wearing layers helps you to control your body temperature.

LAYERING CLOTHES

The rule of layering is simple: several light layers are better than one heavy layer. Wearing multiple layers gives you flexibility to fine-tune your temperature by taking off or putting on layers to regulate your body heat. Choose fabrics such as wool, fleece, microfleece, and down—all of which are good insulators.

HOW LAYERING WORKS

Layering is effective because it traps air between the layers of clothes and helps you stay warm in any environment. If you wear the correct layers in the right order, your clothing will move sweat away from your body, keep moisture out, and help to keep you insulated. Wear wicking fabrics, such as polypropylene, in hot and cold weather.

THE LAYERING SYSTEM

The top (outer) layer repels rain, while dampness is wicked away from the skin by the base layer closest to the skin. The mid-layers insulate the body and help retain warmth.


Raindrops are repelled by the outer layer
Perspiration is drawn away from the skin
Skin
Breathable waterproof outer layer
Fleece mid-layer
Synthetic mesh
Polypropylene base layer



Hat: *a lot of body heat is lost through the head, so a hat helps you to regulate your body temperature*

Base layer: *wicks moisture away from the skin*

Outer layer: *prevents moisture from entering while allowing sweat to escape*

Mid-layer: *provides warmth. Use insulating fabrics in cold weather*

Layered gloves: *fleece gloves worn under lightweight gloves help to protect the fingers*

Fleece: *a bulky, lightweight fabric that retains warmth, even when it's wet*

Pants: *lightweight, full-length pants shade the skin from the heat of the sun*

Boots: *choosing the right boots may be the most important decision you make when selecting gear*

WARM-WEATHER CLOTHING

It's vital to stay as cool as possible in warm weather to avoid heat exhaustion or heat stroke (see p. 272). Too much exposure to direct sunlight can cause sunburn and dehydration, and heat rashes can be exacerbated if sweat is not able to evaporate properly. Choose breathable fabrics that will keep you cool and protect your skin from the sun. Stay hydrated and always wear a hat.



Desert hat: *combines the sheltering brim of a baseball cap with the neck protection of a bandana*

Jacket: *your outer layer should be a loose-fitting jacket*

T-shirt: *choose one made from moisture-wicking fabric, which allows air flow*

Shorts: *the legs of convertible pants can be unzipped to make them into shorts*

Pants: *full-length convertible pants protect protect the skin from insects and the effects of sunburn*

COLD-WEATHER CLOTHING

In cold weather, you need to pay particular attention to your clothing layers. Use a lightweight base layer, which will wick moisture from your skin, several layers of warm, insulating clothing, and an outer shell that's windproof and waterproof. The secret to staying comfortable is to adjust your layers as your body temperature changes. Remove layers as your body temperature rises to avoid sweating.



Ski mask: *helps to keep your face warm and protect it from cold winds*

Jacket: *filled with down or a synthetic equivalent, a windproof outer layer will help you to stay warm in exposed surroundings*

Fleece: *wicking base layers come in several different weights*

Gloves: *in cold environments several layers of gloves are more efficient than a single layer. You can add or remove the different layers as required*

Leggings: *wicking insulating leggings are worn under waterproof pants*

WET-WEATHER CLOTHING

Sudden downpours can occur almost anywhere and it is easy to be caught out by them. The best fabrics to wear in such conditions are those that are breathable, waterproof, and allow sweat to escape—the best known of these is Gore-Tex®. Always carry the gear necessary to stay warm and dry, and make sure you can access it quickly if you are caught out— it can be the difference between comfort and misery.

HOW BREATHABLE WATERPROOF FABRIC WORKS

Breathable waterproof fabric is a laminate of three layers: two layers of nylon on either side of a thin layer of microporous teflon, which contains tiny pores—50 times smaller than the width of a human hair—that keep rain droplets out but allow perspiration (water vapor) to escape.


Microporous teflon
Raindrops repelled
Jacket shell
Perspiration escapes
Jacket lining



Rain hat: *the wide brim stops water from dripping on to your face and down the back of your neck*

Poncho: *an effective waterproof layer, a poncho can be made into a shelter or bed (see pp. 158–59 and 166–67)*

Waterproof jacket: *allows sweat to escape while keeping rain out*

Waterproof pants: *keep your legs dry in wet conditions*

SOCKS

Socks are a vital part of your footwear system. Their function is two-fold. Firstly, they cushion the feet and prevent boots from rubbing and causing blisters. Secondly, they keep the feet warm and dry by wicking moisture away from the feet. Note that socks made from breathable waterproof fabric can be worn with regular boots but should not be combined with breathable waterproof boots.


A good pair of wicking socks helps to prevent blisters


Cushioned for extra protection when wearing boots
Padded heel for comfort

WICKING SOCK

A lightweight inner sock that helps wick moisture away from the skin and reduces friction.

WALKING SOCK

The thick fabric of the walking sock offers maximum cushioning, comfort, and protection.

GAITERS

Gaiters are useful, both in temperate areas for keeping the feet and lower pant legs dry, and in polar regions for keeping out snow.

FOOTWEAR

A number of factors determine which type of footwear is right for you. The first concerns your personal requirements, which include the shape of your feet and the amount of support you need. You also need to consider how far you are traveling and the type of terrain you'll be covering. Then there is cost: footwear varies from the relatively cheap to the extremely costly. Bear in mind that if you intend to spend a lot of time in the wilderness, it pays to invest a little extra in comfortable, sturdy footwear.

BREAKING IN BOOTS

Your boots and feet should coexist in perfect harmony when you're on the trail. When you buy a pair of boots, wear them around the house and go on short hikes to make sure you have broken them in.

ANATOMY OF A SOLE

A boot sole has several layers to protect and support your feet. Look for a good tread on the outsole, and for cushioning beneath the heel and toe areas.


Cushioning pads absorb shock
Insole stabilizes foot and keeps it in position
Midsole
Full-length shank plate for rigidity
Outsole
Heel cup cradles the midsole


Arch straps hold the shoe in place in any terrain
An adjustable fastener ensures a snug fit
Modern sandal has solidly constructed soles

SANDALS

Modern sandal designs offer great support, and are extremely comfortable, while offering additional ventilation.


A flexible fabric upper dries quickly when wet and allows the foot to breathe
Shock-absorbing sole gives added comfort on hard terrain

LIGHTWEIGHT BOOT

Fabric and leather hybrids are increasingly popular because they combine the support and traction of a heavier shoe with the flexibility of a sports shoe, so there is less friction on the foot.


The padded ankle provides comfort and support
Sole provides grip on slippery ground

HIKING BOOTS

A compromise between weight, durability, and protection produces a good, all-round leather boot with a sole of hard-wearing rubber, such as Vibram®, water-resistant uppers, and valuable support for the ankles.


High uppers keep mud off your pants
Canvas uppers are designed to keep the feet cool
Sole contains wide, deep studs to provide grip on the wet ground

JUNGLE-TREKKING BOOT

This is a high boot made from rot-proof leather and canvas with a directly molded sole. Breather holes in the instep aid ventilation and help to drain moisture in hot or humid conditions.


Crampons can be added for extra grip on ice and snow

CLIMBING/HIKING HYBRID BOOT

More flexible than traditional climbing boots, modern hybrid boots are designed to be worn with crampons and to keep the feet warm in very cold environments.

TRUE-LIFE ACCOUNT

EXTREME SURVIVAL—IN THE WILDERNESS

USEFUL EQUIPMENT

- Walking staff
- Pocket chainsaw
- Whistle, flashlight, signal mirror
- Animal deterrent spray
- Water purifiers
- Small AM/FM radio
- Map, compass, GPS
- Survival tin, bushcraft knife
- Cell/satellite phone
- Poncho/bivy sack

BLAKE STANFIELD, 38, AND HIS 65-YEAR-OLD FATHER, Neil, endured being trapped beneath river ice, encounters with bears, and four days and nights in the Alaskan wilderness without food. They survived thanks to good survival skills, knowledge of the local area, and an abundance of water and firewood.

Father and son were dropped by floatplane on Friday, June 6, 2003, at a remote point on the Koyukuk River, deep inside Alaska. They planned to spend seven days rafting approximately 90 miles (145 km) to the town of Bettles. The trip had hardly begun when disaster struck—the raft crashed at speed into a massive sheet of ice, throwing the pair into the freezing water. They were both caught by the strong current and pulled under the ice. Somehow Blake was washed ashore, and he used a branch to haul his father to the riverbank.

Blake quickly realized that Neil was close to hypothermia, so used his waterproof lighter to light a fire of sticks and pine needles. Far from rescue, with their supplies lost and no one expecting their return for six days, their prospects looked bleak. With night approaching they built a shelter.

"THE RAFT CRASHED AT SPEED INTO A MASSIVE SHEET OF ICE"

The next morning, Blake decided to hike the 65 miles (105 km) to Bettles to get help. On Sunday his progress was brought to a halt by the confluence of two large rivers—the Tinayguk and Koyukuk. However, Blake realized that he had reached a landmark on the flight path of supply planes that frequently flew into the interior, so he built a signal fire and waited. Two days later, a pilot spotted him and radioed his position to a US Army base 200 miles (320 km) away in Fairbanks, then dropped him a two-way radio and supplies. The pilot then continued up the river to find Neil, dropping him a sleeping bag, tent, and supplies, before radioing his position to the Army. Both men were picked up the next day—exhausted, malnourished, and close to hypothermia, but alive.

WHAT TO DO



ARE YOU IN DANGER?

NO → If you are in a group, try to help any others who are in danger

YES → Get yourself out of it:
Elements—Find or improvise immediate shelter
Animals—Avoid confrontation and move away from danger
Injury—Stabilize condition and apply first aid

ASSESS YOUR SITUATION
See pages 234–35

DOES ANYONE KNOW YOU WILL BE MISSING OR WHERE YOU ARE?

NO → If no one knows you are missing or where you are, you will need to notify people of your plight by any means at your disposal

YES → If you are missed, a rescue party will almost certainly be dispatched to find you

DO YOU HAVE ANY MEANS OF COMMUNICATION?

NO → You are faced with surviving for an indefinite period—until you are located or you find help

YES → If you have a cell or satellite phone, let someone know your predicament. If your situation is serious enough to be worthy of emergency rescue, and you have a Personal Locator Beacon (PLB), you should consider this option

CAN YOU SURVIVE WHERE YOU ARE? *

NO → If you cannot survive where you are and there are no physical reasons why you should remain, you will have to move to a location that offers a better chance of survival, rescue, or both

YES → Address the Principles of Survival: Protection, Location, Water, Food

YOU WILL HAVE TO MOVE **

DO

- Make an informed decision on the best location to move to—find an elevated position from which to choose a suitable area for survival and rescue
- Regulate your clothing to avoid overheating when moving and hypothermia when static
- Use or improvise a walking staff to help reduce trips and falls
- Improvise shelter when not moving
- Plan your route around potential or known water sources. Filter and purify all water where possible
- Have aids to location accessible while moving and deployed when static

DON'T

- Ignore your fire—be on constant lookout for dry tinder/kindling and fuel
- Walk faster than the pace of the slowest person in the group
- Be careless when walking downhill—a twisted ankle could prove fatal
- Under or overdress. Start off a walk lightly dressed and add or remove layers as necessary

YOU SHOULD STAY **

DO

- Check your shelter site before building for natural hazards such as: insects, flooding, rock falls, wild animals, and deadfalls
- Inventory your supplies and ration them
- Keep a fire going: once it's established you can use it to purify water, benefit from the warmth, and signal rescue
- Fill plastic bags or spare clothing with dry foliage and use as a mattress or pillow to insulate you from the cold/damp ground
- If in a group, give everyone something to do, even the children. It will keep them occupied and lessen the worry

DON'T

- Leave food in your campsite as it will be at risk from predators
- Shelter too deep in the woods despite the protection it gives you from elements. Remember: your location aids need to be seen
- Eat unidentified food, as it could exacerbate your situation through illness. Food is not a priority in a short-term situation

* If you cannot survive where you are, but you also cannot move owing to injury or other factors, you must do everything you can to attract rescue.

** If your situation changes (for instance, you are "moving" to find help, and you find a suitable location in which you can stay and survive) consult the alternative "Do" and "Don'ts."

SLEEPING SYSTEMS

REST IS AS ESSENTIAL for survival as food. A good night's sleep can offset much of the worry and stress of a difficult situation. Making sure your shelter is suitable for the environment you're in, and choosing the right sleeping bag, can be vital factors in survival.

SLEEPING BAGS

Although there are many different shapes and styles of sleeping bag, the one you choose should have enough padding to keep you warm at night even without a tent. A sleeping bag must never be allowed to get wet, so always keep it inside a waterproof cover, such as the bag's stuff sack or a bivy sack. Always try a sleeping bag before you buy it. If it's too snug, it will be less effective.

TIPS ON BUYING A SLEEPING BAG

There are many types of bag available. Here are a few things you should consider to ensure you buy the right sleeping bag for you.

- Determine the lowest temperature you're likely to encounter on your trip and choose a bag that will perform at this temperature.
- Synthetic bags are cheaper and easier to clean than down bags, and continue to provide insulation even when wet.
- Down bags are more expensive than synthetic bags, but provide a better warmth-to-weight ratio and last longer.
- A mummy-shaped bag provides better insulation than a rectangular-shaped bag, but has less room to move around in.



Locking mechanism: *keeps the hood closed in cold weather and can be loosened in milder climates*

Zipper: *ideally it should be snag resistant and have a draft tube to prevent heat from escaping and cold air from seeping in*

Baffles: *are channels sewn into the bag to prevent the down from collecting in one area*

Extra baffles: *often added to the foot section to help eliminate cold spots. The foot area should be big enough to allow you to move your feet comfortably*

Accessory pockets: *can be used to secure essential items such as keys or wallets*

Loops: *allow you to attach sleeping bag to the sleeping mat*

Box foot: *creates a mummy shape and is designed to conform to the position of your feet when you're sleeping on your side*

DOWN OR SYNTHETIC

Sleeping bags are made with either a down or a synthetic filling. Down is made up of highly specialized insulating feathers, normally from ducks or geese, and is unsurpassed when it comes to a warmth-against-weight ratio. However, it is ineffective when wet and can cause an allergic reaction in some people. Synthetic fillings range from simple hollow fibers all the way up to complex fibers designed to mimic the structure of down. They still retain some of their insulating capacity if they get wet.

TEMPERATURE RATINGS

Because manufacturers have no standardized way of registering how warm a sleeping bag is, temperature ratings for sleeping bags remain an inexact science. Some manufacturers give a bag both a comfort rating and a survival rating—known as a "season rating.' These give some indication as to how manufacturers expect a sleeping bag to perform.



CONSTRUCTION

The principle of all sleeping bags is the same: to trap air and prevent its circulation so that the body heats the trapped air and keeps you warm while you sleep. This can be achieved in a number of ways.



BOXWALL

Used in cold-weather down bags, the filling is contained within box-like sections to minimize bunching.



SEWN-THROUGH

Filling is in separate oval channels, although heat is still lost through the stitching.



OFFSET CHANNELS

The filling is laid out in two layers to prevent bunching and heat loss through the stitching.



SHINGLE

Slanted layers of overlapping fibers that fill with warm air to aid insulation.

USING YOUR SLEEPING BAG

Before using your sleeping bag, always check inside for spiders and other dangers, and shake it to make sure the filling is distributed evenly. During use, if the bag is too warm, simply unzip it to cool down, or use the bag as a quilt. If it's too cold, either put on some clothing, or use a silk liner or waterproof bivi bag to increase its performance. Always air your sleeping bag well after using it.

SLEEPING ACCESSORIES

You'll need to get a sleeping mat as well as a sleeping bag to ensure a comfortable, dry night's sleep. Additional gear, such as bivy sacks, sleeping bag liners, and inflatable pillows, will also increase comfort.



A lightweight option, weighing as little as 1.1 lb (0.5 kg)

Folds up quickly and easily for simple storage

FOAM MATS

The lightest and simplest type of mat, foam mats are best used on soft surfaces, such as sand or pine needles.



Shorter mats may suffice in summer

Exterior is covered in waterproof, non-slip polyester material

AIR MATS

They may be heavier and more expensive than foam mats, but air mats provide superior comfort and thermal insulation.



Liners can be used on their own in hot climates

Sleeping bag liners are easier to wash than sleeping bags

SLEEPING BAG LINER

Usually made of cotton or silk, sleeping bag liners trap air between your body and the sleeping bag.



In warmer climates, bivy sacks enable you to sleep outside without a tent

BIVY SACKS

A simple waterproof bag that is used over a sleeping bag to keep it dry or used on its own as a shelter.



Outer layer of pillow is padded for extra comfort

INFLATABLE PILLOW

An inflatable pillow adds some luxury to expeditions. Alternatively, fill a stuff sack with spare clothing.



Foil prevents body heat from escaping and deflects it back to the body

SPACE BLANKET

A lightweight foil blanket for use in emergencies, space blankets can also be used as a temporary canopy.

PORTABLE SHELTERS

Shelter from the elements at night is essential for long-term survival. A variety of products are available to you, depending on the conditions you're about to enter and the amount you're prepared to carry. You can choose from lightweight options, such as hammocks and variations on bivy sacks, and the more traditional alternatives, tents, which are heavier but can accommodate up to eight people.

USING A HAMMOCK

If you have a hammock you can camp even if the ground is muddy, rocky, or on an incline. The advantage of a hammock is that it's lightweight and can be erected just about anywhere. Modern hammocks provide a shelter and bed solution in one portable package.



Always use straps to avoid damaging live trees and protect the bark

Make sure the tree or upright holding the hammock is strong enough to support it

Built-in flysheets provide extra protection from the elements

Modern hammocks are designed to enable users to sleep in an almost-flat position

USING A TARP TENT

A cross between a tarpaulin and a tent, a tarp tent is a highly versatile, extremely light form of shelter that's capable of withstanding even the most extreme conditions. Groundsheets should be laid out on the ground for added protection, and a suitable sleeping bag is essential. A one-person version can weigh as little as 18½ oz (0.52 kg).



Some tarp tents come with built-in netting for protection against insects

Trekking poles can be used to replace tent poles

Guylines give the tarp tent stability

A groundsheet provides insulation from the cold, damp ground

USING A HOOPED BIVY

The hooped bivy is a waterproof and breathable bivy sack that has been designed to form a one-person shelter. It usually incorporates pegging points and a zippered and hooped entrance that form a small vestibule for your backpack. Many incorporate a heavy-duty groundsheet and can be set up and taken down in a matter of minutes.



While they may have restricted space, hooped bivys pack small and are extremely lightweight

Limited height means you're restricted to a prone position

A small vestibule provides minimal storage for your gear

USING A TENT

Tents keep the rain and wind out while retaining warmth. The outer flysheet should be strong, impermeable, taut, and able to withstand high winds. The inner tent—which may be attached to a flysheet—is loose and made of permeable material to minimize condensation but retain heat. The inner and outer parts of the tent must not touch each other; if they do, heat may be lost and condensation may form on the underside of the flysheet, then seep into the tent.

WARNING!

In some climactic conditions, such as extreme high winds, severe storms, or heavy snow cover, stakes and guylines may not be enough to anchor the tent securely to the ground. This could result in the tent being blown away—and could have severe consequences for the tent's occupants. In such conditions, use extra means—such as rocks or logs—to anchor your tent securely.

THREE-SEASON TENT

Three-season tents are designed for use in a variety of climates. The inner layer is made of a lightweight material that offers both ventilation and protection against insects. The flysheet—which should extend about 4 in (10 cm) above the ground—and the groundsheet are made of waterproof fabric.



Pole separates inner tent from flysheet to aid ventilation

A door is mounted on a smooth-running circular zip

Swift clips attach the inner tent to poles securely, quickly, and easily

Outer door can be rolled horizontally and fixed to flysheet for easier access

WITH FLYSHEET

Guylines anchor the tent securely against high winds

Inner tent material is uncoated to aid ventilation and disperse condensation

WITHOUT FLYSHEET

Mesh door allows light to enter but keeps insects out

WINTER TENT

For cold-weather climates, look for a tent that offers extra-strong poles, storm windows, and ample pockets so that you can store your gear inside the tent. However, these extra features increase the tent's weight. The dome shape sheds snow well, and withstands high winds.



Condensation sponge absorbs moisture and stops flysheet from touching inner wall

Dome shape prevents heavy accumulation of snow

Ventilation zipper increases air circulation, which helps dry wet gear in poor weather

WITH FLYSHEET

Vestibule allows occupants to cook without leaving sleeping bag

Fully enclosed pole sleeves provide extra rigidity in poor weather

WITHOUT FLYSHEET

Heavy-duty poles provide excellent stability in strong winds

EATING ON THE TRAIL

THE FOOD YOU EAT determines how efficiently your body will function. This is never more important than when you're undertaking an expedition that will test your physical and mental endurance beyond normal levels.

FOOD FOR LIFE

Your body requires energy to fuel the chemical and biological reactions that take place within it, and to power your muscles. This, and other nutrients, comes from the food you eat (see below).

BODY FAT AND SURVIVAL

Being physically fit and active keeps you strong and less prone to injury, but being slightly overweight can actually be an advantage in a survival situation: 1 lb (½ kilo) of body fat converts to roughly 3,500 calories—the amount of energy you would usually expend during an average day.

TYPES OF NUTRITION	EXAMPLES	BENEFITS
CARBOHYDRATE	▪ Rice, pasta, bread, and cereals ▪ Fresh and dried fruit ▪ Root vegetables ▪ Chocolate and candy	▪ Major source of energy, as it converts most readily to glucose, which is your body's preferred source of fuel.
PROTEIN	▪ Meat and poultry ▪ Fish, such as tuna and salmon ▪ Eggs and dairy products ▪ Beans, legumes, and seeds	▪ Essential for growth and repair of muscle tissue. ▪ Increases your stamina and energy levels, and helps you fight fatigue. ▪ Makes you feel satisfied after eating.
FAT	▪ Nuts and seeds ▪ Dairy products, such as butter and cheese ▪ Meats, such as bacon and sausage ▪ Cooking oil	▪ Good source of energy. ▪ Makes you feel satisfied after eating.
FIBER	▪ Fresh and dried fruit, especially the skins ▪ Vegetables, beans, and seeds ▪ Whole-grain cereals ▪ Whole-meal bread, whole-meal pasta, and brown rice	▪ Provides bulk to help your digestion. ▪ Helps to make you feel full.
VITAMINS AND MINERALS	▪ Fresh and dried fruit ▪ Green vegetables ▪ Meat and fish ▪ Nuts and seeds	▪ Essential for growth and the repair of your body's tissues. ▪ Help you to maintain healthy teeth and eyes. ▪ Aids bloodflow and the production of energy.

BALANCING YOUR ENERGY LEVELS

You replace the energy that you expend on a daily basis through the food you eat. The energy obtained from food is measured in calories, and you require a certain number of calories each day to remain alive. If you consume too few calories, you will lose weight. However, eating too many calories will lead to weight gain, which can cause long-term health issues. The number of calories you require per day depends on many things, such as your age and level of activity (see right). When you don't replace the energy expended and continue to work, you start to use the energy store contained in your body's fat.



WILDERNESS DINING

Even if you're only going on a short hike, you should take food with you, such as fruit and chocolate, to replace the energy you're using. For longer expeditions, you'll need to take a number of different foodstuffs—for energy and for variety.

WARNING!

In a survival situation, don't eat for the first 24 hours unless to replace expended energy. Ration your food, as digestion uses up water.

TYPES OF FOOD	EXAMPLES	BENEFITS
BREAKFAST CEREALS AND DRIED FRUIT	▪ Trail mix—also known as "gorp" ▪ Muesli or granola ▪ Oatmeal ▪ Dried fruit	▪ Provide a vital source of carbohydrates, vitamins, and minerals to set you up at the start of the day. ▪ Contain dietary fiber to aid digestion.
TRAIL SNACKS	▪ Cookies and crackers ▪ Energy bars and cereal/granola bars ▪ Fruits, such as apples, pears, and oranges ▪ Nuts and seeds	▪ High in carbohydrates to help you maintain energy levels. ▪ Help to keep your hunger pangs at bay between main meals.
HIGH-CALORIE SNACKS	▪ Dehydrated ice cream ▪ Chocolate ▪ Hard candies ▪ Pudding mixes	▪ Provide a quick boost of energy, when required. ▪ Offer a comfort factor, although they are of limited nutritional value.
PRE-PREPARED MAIN MEALS	▪ Boil-in-the-bag meals—you can buy a wide variety of fully prepared meals, sealed in a foil bag. Cook for five to seven minutes. ▪ Freeze-dried and dehydrated meals—simply add boiling water, stir, and wait about five minutes. Extremely lightweight and take up little space. ▪ Canned meals—a great variety of them are available, but they are bulky and heavy.	▪ Provide a balanced range of food groups, vitamins, and minerals to help your body to recover and repair itself after the day's exertions. ▪ Quick and easy to prepare, and require few utensils. ▪ Many require minimal fuel to cook them, or water to rehydrate them. ▪ Can be bulked out with beans, legumes, and grains. ▪ Smaller cans may have a pull-top to open them.
MEAT, FISH, AND CHEESE	▪ Canned fish, such as sardines or tuna ▪ Cured meats, such as ham, salami, and beef jerky ▪ Hard cheese, such as cheddar and parmesan	▪ A great source of proteins and fats. ▪ Easy to store and long-lasting, although cans are heavier than other sources of food.
BEANS, LEGUMES, AND GRAINS	▪ Lentils and dried peas ▪ Dried beans and pearl barley ▪ Rice and pasta ▪ Couscous	▪ Can be used to bulk up main meals and help you to feel full. ▪ An important source of carbohydrates. ▪ Also provide fiber and protein.
MIXERS	▪ Flour ▪ Salt ▪ Suet ▪ Sugar	▪ Flour and salt can be used to make dough. ▪ Sugar and salt help to make wild food palatable. ▪ Suet is an invaluable source of fat that can be used to supplement meals.
FLAVORINGS	▪ Powdered soup ▪ Tomato puree ▪ Powdered sauces ▪ Gravy cubes	▪ Add flavor and variety to your meals. ▪ Especially useful if you're cooking with wild food.
BEVERAGES	▪ Tea ▪ Coffee ▪ Chocolate powder ▪ Dried milk	▪ Provide warmth and comfort, although they are of limited nutritional value. ▪ Chocolate powder is high in carbohydrates. ▪ Dried milk is an excellent source of calcium.

CAMPING STOVES

ALTHOUGH NOTHING CAN BEAT the satisfaction of building your own campfire, the convenience and reliability of purpose-made camping stoves make them an essential piece of cooking equipment, especially in areas where open fires are banned.

THE BENEFITS OF CAMPING STOVES

Modern camping stoves are very light and collapse down to an incredibly small, compact size. Gas-fueled stoves are by far the most common, but liquid-fueled stoves are also worth considering. Both have their own advantages and disadvantages (see below), but your choice will be dictated by space and weight constraints, the distance you're traveling, and environmental factors. A hexamine stove is a good item to have in a survival situation (see opposite).

CHOOSING A GAS- OR LIQUID-FUELED STOVE

Gas-fueled stoves are safer, cleaner, lighter, and easier to use than liquid-fueled stoves, but are less economical, and not suitable for low-temperature, high-altitude use. Liquid stoves offer greater stability, fuel versatility and economy, but you need to pump and prime (preheat) them before use, and they are less clean.

TRANSPORTING FUEL

There are many factors to consider when transporting fuel to make your expedition safer:

- When hiking, pack your fuel container upright in the middle of your backpack, and surround with clothing to protect it from knocks. Make sure you can access it easily when you reach camp. Use similar principles when traveling by other methods.
- Ensure that your fuel bottles look very different from your water bottles to prevent confusion.
- If you're going on a long expedition, check the availability of the fuel, and consider how you will dispose of cylinders safely.

	GAS-FUELED STOVES		
TYPE OF STOVE	 BUTANE OR ISOBUTENE	 PROPANE	 BLENDED FUEL
INFORMATION	▪ Both fuels sold in disposable, pressurized canisters.	▪ Fuel sold in disposable, pressurized canisters. ▪ Used in most portable stoves and barbecue grills.	▪ Fuel sold in disposable, pressurized canisters. ▪ Is a mix of butane, propane, and/or isobutene.
PROS	▪ Lightweight, sealed fuel container. ▪ Butane very efficient and burns at a high temperature. ▪ Isobutene more efficient than butane, and performs better in cold conditions.	▪ Lightweight, sealed fuel container. ▪ Fuel burns at a very hot, steady heat, and produces an almost sootless flame. ▪ Performs very well in cold conditions.	▪ Lightweight, sealed fuel container. ▪ Fuel safer than pure propane, and performs better than either pure butane or isobutene in cold conditions. ▪ Isobutene blends give a more efficient flame.
CONS	▪ Higher cost and lower heat output than liquid fuels. ▪ Fuel efficiency reduced at higher altitudes. ▪ Butane less efficient than isobutene in temperatures below 50°F (10°C).	▪ Higher cost and lower heat output than liquid fuels. ▪ Fuel efficiency reduced at higher altitudes. ▪ Highly combustible, so less safe than other fuels.	▪ Higher cost and lower heat output than liquid fuels. ▪ Fuel efficiency reduced at higher altitudes.

USING CAMPING STOVES SAFELY

Always take care when storing the fuel and using your stove. Use only the stove manufacturer's recommended fuel, and check all connections and fittings before each and every use. Also:

- Clear the cooking area of dry vegetation and leaves, in case you spill fuel or knock over your stove.
- Place your stove on a level and stable surface.
- Keep naked flames and sparks away from the fuel, especially when filling or refilling the stove. Before refilling, make sure the flame is out and the stove has cooled down.
- Use the cooker in a well-ventilated space. Liquid fuels, in particular, can give off poisonous fumes, such as carbon monoxide, and all cookers also burn vital oxygen.
- Don't use a stove inside your tent. In addition to the risk of poisonous fumes, fire is also a significant danger. A confined space with limited access, your tent can be reduced to ashes in minutes, along with everything inside, and you may not be able to escape in time to protect yourself. Losing your tent and your equipment is bad enough, without you receiving third-degree burns at the same time.
- Don't leave a burning stove unattended. If it topples over, it could easily start a fire. If the stove flame goes out, a spark or naked flame could also ignite the vapors and cause an explosion.

THE HEXAMINE STOVE

A very useful piece of emergency equipment, the hexamine stove (or hexi-stove) burns solid blocks of hexamethyl-enetetramine (also known as "methenamine"), and folds away compactly. The stove acts as a small windbreak and cooking platform, while the fuel blocks it uses provide a very reliable means of starting a fire in any conditions. The blocks produce a smokeless flame, don't liquefy while burning, and leave no ashes.



Walls act as a wind break

	LIQUID-FUELED STOVES			
	 **WHITE (COLEMAN) FUEL**	 **MULTI-FUEL**	 **DENATURED ALCOHOL**	TYPE OF STOVE
	▪ Fuel sold in disposable canisters.	▪ Stove can use a variety of fuels, from unleaded gas, kerosene (paraffin), aviation fuel, and white fuel, to diesel—most of which are readily available.	▪ Fuel sold in disposable plastic containers. ▪ Stove basically consists of a vessel to burn the fuel in, and a windshield that also acts as a cooking platform.	INFORMATION
	▪ Fuel can withstand low temperatures, high altitudes, and most weather conditions. ▪ Produces a clean flame.	▪ Stove uses a range of fuels. ▪ Fuel is non-pressurized, so can be stowed safely in almost any airtight container. ▪ Stove tends to perform reliably, efficiently, and quickly, producing a hot flame.	▪ Fuel is non-pressurized, so can be stowed safely in almost any airtight container. ▪ Economical and produces a clean flame. ▪ Stove is lightweight, stable, and safe. ▪ Usually supplied with pots and pans.	PROS
	▪ Stove must be pumped to generate required pressure for use. ▪ Fuel needs to be primed.	▪ Potential for spillage of flammable fuel. ▪ Stove must be pumped to generate required pressure for use. ▪ Fuel needs to be primed. ▪ Some fuels produce soot and noxious fumes.	▪ Potential for spillage of flammable fuel. ▪ Stove slower to heat up than other liquid stoves, because it's not pumped. ▪ Flame vulnerable to wind and other environmental conditions.	CONS

YOUR SURVIVAL KIT

A BASIC SURVIVAL KIT is an essential item to take with you on any outdoor expedition. It should be compact enough to carry on your person at all times, and its contents should address the key principles of survival: protection, location, water, and food.



LAYERS OF A SURVIVAL TIN

EXAMPLE OF A SURVIVAL KIT

Choose a tin with a waterproof seal and locking clasps. While you can buy ready-made kits, you should always adapt the contents, both to your needs and to the environment you'll be in. Ideally, items in the survival kit should be high-quality and multi-purpose—for example, the tin itself could be used as a cup, a small cooking pot, or even a signal mirror. Your kit should contain the following:

LAYER 1



- **Blister medical pads and bandages:** useful for minor cuts and blisters. Include a range of bandages (both waterproof and fabric) in a selection of sizes. Waterproof bandages can also be used to mend holes in tents and tarpaulins.

LAYER 2



- **Antiseptic wipes:** for treating wounds and cleaning bites. Can also be iginited by a spark and used to get a fire going.

LAYER 3



- **Water purification tablets:** choose from tablets or iodine (but don't use iodine if you're allergic to it, or to shellfish). Water will need to be filtered before being purified.

LAYER 6



- **Survival saw, or pocket chainsaw:** can be wrapped around the inside of the tin or cut in half, if space is limited.
- **Single-edged razor:** multi-purpose—from skinning an animal to cutting cord. Store in its packaging.
- **Needle and cotton:** use strong, waxed cotton, pre-threaded through the needle.

LAYER 7



- **Flashlights:** two small Photon (LED) lights—one white and one red—taped in "off" position.
- **Mini multi-tool:** see panel, opposite.
- **Chainsaw handles:** use with pocket chainsaw.
- **High-viz card, signal mirror:** location aids.
- **Compass:** an emergency back-up.
- **Flint, fire steel, tampons:** for starting fires.
- **Snare wire:** for animal traps and lashing.

LAYER 8



- **Waterproof matches and tinder balls:** for starting fires. Store the matches in a small, resealable plastic bag.
- **Pencil:** sharpened at both ends.
- **Potassium permanganate:** dissolve in water to sterilize water at low concentration, and to clean wounds at a high concentration. Can also be used with sugar to make fire. Store in a waterproof container.

CHOOSING A MULTI-TOOL

A useful item to carry with you on your trip, multi-tools are usually designed with a specific task or hobby in mind, and include useful features for survival, such as a small compass, pliers, saw, and various blades. Use one that has quality tools that most suit your needs, with a comfortable grip, and ensure that the blades are lockable to prevent injuries. Carry your multi-tool in a secure pocket, or in a pouch on your belt, and include a miniature version in your survival tin (see below). Bear in mind that your multi-tool should be an addition to, not a replacement for, your bushcraft knife (see p. 146).


Other tools, such as scissors, open out from the two "arms" of the multi-tool
Rotating mechanism enables the tool to fold compactly when not in use
Needle-nose pliers can be used for gripping items, or for cutting wire
Close the multi-tool when not using it for safety

LAYER 4



- **Petroleum jelly:** apply to chapped lips, rashes, and sores. Can also be smeared onto tampons to make them burn longer. Store in a small, resealable plastic bag.

LAYER 5

- **Waterproof notepaper:** for drawing maps or leaving messages.
- **Photograph of loved ones:** a psychological incentive in a survival scenario.
- **Credit card:** an effective means of extracting insect stings (see pp. 266–67).
- **Money:** wrapped in cellophane.

LAYER 9

- **Non-lubricated condoms:** can be used to carry water, or as a waterproof cover for smaller items, such as your mobile phone.
- **Mini fishing kit:** if you are near water, fish can be easier to catch, prepare, and cook than mammals. Fishing line can be also used for other survival tasks. Should contain a selection of hooks, flies, swivels, and split-shots.

TIN LID SEALED WITH TAPE

- **Sailmaker's needles:** multi-purpose—can be used as an arrow point, or for mending tents and tarpaulins. Wide eyes are best.
- **Safety pins:** for securing clothing, or mending your sleeping bag or tent.
- **Mini glowsticks (cyalumes):** useful for emergency lighting, and as a location aid.
- **Single-edged razor:** multi-purpose (see Layer 6). Store in its packaging.

ADDITIONAL USEFUL ITEMS TO INCLUDE

While your survival tin's size may be restrictive, you can always improve your kit with items that can fit on your belt, or in a belt pouch, known as a "belt order." This will form part of your first-line equipment (see p. 43).

- **Space blanket or aluminum foil:** can be used as a signaling device; for shelter; to carry, store, and heat water; or to cook in. Many are dual-sided: one silver, the other green for camouflage, or orange to stand out.
- **Plastic bags:** you can never have too many. Numerous uses—from a water carrier to a transpiration bag.
- **Medicines (such as painkillers and antibiotics):** should not replace your main first-aid kit, but ensures you have some basics if you're separated from your gear.
- **Small candle:** once lit, this will provide a reliable flame that you can build your fire around.
- **Nylon stockings:** can be used for warmth, or as an improvised water filter, mosquito net, or fishing net.
- **Small AM/FM radio:** battery- or solar-powered.
- **Surgical tubing:** enables you to reach water in otherwise inaccessible rock crevices.
- **Fire tin or matchless fire set:** self-contained methods of starting a fire, when no natural fuel is available.

2

ON THE TRAIL

FIND YOUR WAY

Before you set off on an expedition, you should have at least a basic understanding of how to read a map and use a compass. Your ability to correctly assess a map of the area you intend to visit will allow you to make informed decisions during your preparation. If you understand the area and terrain, your chances of getting lost will be reduced, and you will be able to continually evaluate your progress and therefore alter your plans as necessary. You will also be able to plan the safest and most appropriate route, and locate water, shelter, and areas that will allow you to use your location aids properly. If you're proficient with a map and compass, you'll have no cause to worry about getting lost or straying off-track and will be free to enjoy your outdoors experience.

In a survival situation, you will be faced with many tough decisions. You may have to decide whether to stay where you are and await rescue or move to an area that offers a better chance of survival and rescue. Your ability to navigate effectively—whether

In this section **YOU WILL DISCOVER...**

- how to **use your map** to tell the **lie of the land...**
- that the **path ahead** is as long as a **piece of string...**
- the difference between **eastings** and **northings** and an **ERV** and a **GPS...**
- how a **detour** could be the **most direct route...**
- how to **navigate** using your **hair...**
- why an **anvil of cumulonimbus** is no **fair-weather cloud...**

by using a map and compass or by using natural features—will play a major role in your decision-making process. Whilst a Global Positioning System (GPS) is an excellent aid, it relies on batteries and technology—both of which can fail.

An understanding of weather patterns will also allow you to evaluate conditions and make informed decisions as you travel. The ability to assess your situation and modify your plans means that you will be able to avoid many potential survival situations.

The ability to take a bearing (see pp. 68–71) and navigate using pace counting (see p. 72) could prove to be crucial skills in a survival situation.

TEST HOW ACCURATELY you can walk on a set bearing and pace out a set distance by following the exercise below. If you have stayed on your bearings and your pacing has been accurate, you should finish at your starting point. Pick a suitable area where you can walk at least 330 ft (100 m) in any direction. Don't cheat by heading for your marker! For this exercise to be useful, make sure you follow your bearings and count your paces to navigate.

1. Place a marker on the ground. Dial a bearing onto your compass (110° in our example).
2. Walk on this bearing, counting your paces until you think you have traveled 330ft (100m), then stop.
3. Add 120° to your original bearing. Dial this new bearing (230° in our example) onto your compass.
4. Pace out another 330 ft (100 m) on your new bearing, then stop.
5. Add another 120° to your latest bearing. Dial a last bearing (350° in our example) onto your compass.
6. Walk on your final bearing for a further 330 ft (100 m). You should be back at your starting point.



“Never underestimate the **combined power** of a map, a compass, a GPS unit, and the **skills and knowledge** to use them well—your life may **depend on it**”

MAPS AND MAP-READING

A MAP IS A TWO-DIMENSIONAL representation of a three-dimensional area—from a map you can determine distance and height on the ground. If you are able to read a map, and can interpret the information it contains, you can visualize what an area looks like and use these features as landmarks to make navigation easier. Your map is very important, so keep it safe.

UNDERSTANDING MAPS

Although there are many types of map available—with varying levels of detail and scale—topographic maps are best for hiking. They show important features, such as rivers, roads, railroads, paths, buildings, and forested areas, and also depict the lie of the land through the use of contour lines (see opposite) to represent height.



These symbols represent the vegetation type

Contour lines join points of equal height

Symbols represent features of interest and are decoded in the legend

Different colors show different types of ground: mud, sand etc

Grid numbers are useful for grid references

Grid lines divide the map into 1 km squares

Hiking paths are clearly marked on the map

THE LEGEND

Topographic maps incorporate a legend, or key, which deciphers the information shown on the map. It's important to familiarize yourself with the symbols used, as this will help you visualize what's being represented on the map more effectively. Some examples are listed below:

HEIGHTS AND NATURAL FEATURES

Water

Mud

Sand; sand and shingle

Vertical face/cliff

Loose rock

Boulders

Outcrop

Scree

Coniferous trees

Non-coniferous trees

Managed woodland

Orchard

Scrub

Bracken, heath, or rough grassland

Marsh, reeds, or wetlands

TOURIST AND RECREATIONAL INFORMATION

Nature reserve

Campsite

Fishing area

Walks/Trails

THE SCALE

Hiking maps are always drawn to a scale provided in the legend. This is a ratio of how much you would have to enlarge the map to reach actual size. 1:25,000—whereby 4 cm on the map equates to 1 km on the ground (2½ in to 1 mile)—is the most useful level of detail for hikers. A smaller-scale of 1:50,000, for example, will provide a more basic overview of the terrain.

MEASURING DISTANCE

Maps are drawn to scale so that you can use them to accurately estimate distances on the ground. Being able to measure distance is important because it means you can calculate the most direct—and energy-efficient—route to your destination. In a survival situation, every last bit of energy counts, so the shorter the distance, the better.



USING THE GRID LINES

The simplest method of measuring distance on a map is to use the grid lines—on a scale 1:25,000 map each grid square represents 1 km (traveling diagonally across a square, it's approximately 1.5 km). You can also lay a piece of paper between the two points, mark the start and end of your route, and place it underneath the scale line to read the distance.

USING STRING OR SOLDER

Invariably you will deviate from a straight line and will have to navigate around obstacles or bends. A far better way of measuring distance is therefore to take a piece of string, curve it around your intended route, and transfer it to the scale line. Solder wire (use wire that is lead-free) is even more accurate because it holds its shape on the map and remains flexible.

CONTOUR LINES

Topographic maps feature lines called contour lines. A contour joins points of equal height above sea level, and allows the topography of the ground to be depicted in detail. The contour interval is specified in the legend—for maps with a 1:25,000 scale you would usually expect to see a 5-meter vertical interval between each line, although for maps of mountainous regions this interval may be 10 meters. The ability to look at the contour lines, and imagine how they translate to the ground, is a skill that takes a little while to acquire, but once mastered will allow you to read a map more proficiently.

USING CONTOURS

Knowing how steep the ground is will greatly improve your navigational skills, as well as your route-planning (see p. 73). Walking up and down hills uses a lot of energy, so it is far better to follow the contour lines on your map to go around hills instead.



These numbers show the height above sea level in meters

When the lines are closer together, the land is steeper

GRID REFERENCES

Maps contain grid lines, which help you locate a specific point anywhere on a map, using a unique number known as a grid reference. The vertical grid lines are called "eastings," as they increase in value as they travel east on the map. The horizontal lines are called "northings," where these perpendicular lines cross creates the grid.

WORKING OUT GRID REFERENCES

Use the numbers on the grid lines and apply the easting number first. On a scale 1:25,000 map, where the grid lines are 1 km apart, the shaded area on the grid below would have a four-figure grid reference of 2046, and indicate a grid square that is 1 km by 1 km. To be more accurate, use a six-figure number—mentally divide the square into tenths. The cross would therefore have a grid reference of 185445.



GET YOUR BEARINGS

IN ADDITION TO understanding and reading maps, it's important to know how to orientate your map to the land so you can use it to navigate. It's possible to do this by sight, although in most cases you'll need a more reliable method and for this you should use a compass. Use your compass to determine direction, orientate your map and yourself, take and plot bearings, and navigate.

CARDINAL POINTS

The four cardinal points of the compass are:

- North (N)—0°/360°
- East (E)—90°
- South (S)—180°
- West (W)—270°

HOW A COMPASS WORKS

A compass needle is a magnetized piece of metal that, when allowed to rotate freely, will orientate itself to the North and South magnetic poles. Always hold a compass level.

STANDARD COMPASS

This standard orienteering Silva compass is a good compass for hiking. It allows you to set your map and work out distances using the printed scale on the base.


Magnifying glass is useful when reading detailed maps
Direction of travel arrow indicates the direction in which you should walk
Compass scale/ Romer measures distance on a map and helps you work out grid references
Magnetic arrow indicates north
Compass housing contains the needle and has the points of the compass marked on a circular, rotating bezel
Base plate
Liquid inside the housing dampens the needle to allow it to settle more quickly
Hole for attaching a lanyard
Read bearings from the index line, an extension of the direction of travel arrow
The orienting arrow is fixed within the compass housing and aligns with north on the housing
Rotating dial shows your potential bearings
Orienting lines are fixed within the compass housing and align with the eastings on a map
1:25 000 METERS
1:50 000
1:63 360
100mm
2 INCHES
N
E
S
W

OTHER TYPES OF COMPASS

There are many different types of compass, ranging from simple button compasses to complex instruments that include features such as sighting mirrors. Use a quality compass that suits your needs, and carry a simpler backup for emergencies.


Only the points of the compass are shown
N
E
S
W

BUTTON

The simplest compass available—its small size and basic level of detail makes it ideal as a backup compass.


Non-rotating dial
N
E
S
W

FIXED DIAL

As well as the basic points of the compass, degrees and bearings are also shown on the immovable dial.


Rotating dial
Basic scales for orienteering

BASIC ORIENTEERING

With a rotating dial, this has simpler markings than the standard compass above, and is ideal for beginners.

SETTING YOUR MAP

Walking with your map set allows you to read the ground from the map as you pass over it, and to recognize and predict features as you progress, which means that you'll soon realize if you are heading off course. In some cases, when you have a good view of the terrain around you, and know the approximate area you're in, you can simply rotate your map until the features line up with the corresponding features on the ground. However, using your compass is a far more accurate method.

1 Rotate the dial so that "N" sits under the index line. Lay your map flat on the ground and ensure there is nothing nearby that could affect your compass (see box below).
- Lay the compass on the map so its edge runs parallel with a vertical grid line (easting).



Needle will not be aligned at present

Orienting lines run parallel to the vertical grid lines on your map



2 Keeping orienting lines aligned with the grid lines on the map, rotate the entire map until the north magnetic needle on the compass sits inside the orienting arrow. The map is now set to magnetic north and should basically line up with the features that surround you.
- If magnetic variation in your area is high (+ 5°), compensate accordingly (see right).

Needle is now aligned



LENSATIC

The lensatic compass is an excellent instrument for taking very precise navigational measurements.

TAKING AN ACCURATE READING

Always hold the compass level to allow the needle to rotate easily. A compass is simply a magnetized piece of metal and, as such, is susceptible to interference. To avoid this, never use your compass near:
- Metal or other magnetized objects
- Electric currents, such as overhead high-tension power cables
- Buildings and vehicles—these often contain metal and electricity that might affect the accuracy of your compass readings

MAGNETIC VARIATION

Map legends refer to north in three ways: "true north," "grid north," and "magnetic north." The angle between magnetic north and grid north is known as "magnetic variation," and is provided in the map legend. True north is the direction of a meridian of longitude that converges on the North Pole. Grid north runs parallel to the vertical grid lines on a map and differs from true north because a map is flat. Magnetic north is the direction indicated by a magnetic compass.



This angle is the magnetic variation or "GMA" (Grid Magnetic Angle)

True north is only usually useful when navigating using the North Star

Magnetic north is important when using a magnetic compass

Grid north is relevant when using a map with grids

COMPENSATING FOR VARIATION

When converting a magnetic bearing to a grid bearing, or vice versa, you have to adjust for magnetic variation. When the variation is west, use the phrases "Mag to grid—get rid" or "Grid to mag—add." If the variation is east, the opposite applies.

1 Check the legend of your map to establish the magnetic variation. This depends on your location, and whether it is east or west of grid north.

2 If the variation is 0°, there's no magnetic variation affecting the compass, so make no adjustments.

3 If converting a magnetic bearing to a grid bearing with a 12° west variation, take off the 12°. With an east variation, add it on.

4 If converting a grid bearing to a magnetic bearing with a 12° west variation, add on the 12°. With an east variation, take it off.

TAKING BEARINGS

Always give any compass work your full attention. Rushing it, especially when working out bearings, can lead to navigational errors that could, at best, involve more walking and, at worst, get you lost.

USING A MAP

Using your map to work out the direction in which you need to walk is simple. Use your compass as a protractor to work out your bearing, and then to keep you on track.

BACK BEARING

A back bearing enables you to find your position by taking a bearing from a feature back to you. To do this, take a bearing to a point in the normal way and either add or subtract 180 degrees. You can also read the bearing exactly opposite to the index line. This is useful when working out the bearing from a feature back to you and transferring it to your map (see below).


Direction of travel arrow points toward your destination
Orienting lines are not aligned

❶ Lay your map on a flat surface, ensuring that there's nothing nearby to interfere with the compass reading (see box, p. 69).

- Lay the edge of your compass so that it runs between the point you want to navigate from and the point you want to navigate toward.
- Ensure that the direction of travel arrow on the compass is pointing in the direction you want to travel on the map.

USING FEATURES ON THE GROUND

Sometimes you may need to take a bearing to a specific point to navigate toward it. The point may be a feature that you can see at the time but may subsequently lose sight of during your journey because of the terrain. You can also plot that bearing and others on a map in order to work out your own position (see right, and panel, far right).

TAKING A BEARING ON A FEATURE

Pointing your compass at the feature, hold the base plate steady and rotate the compass housing until the orienting arrow sits directly under the north needle. Read the bearing—this is the magnetic bearing you would walk on to navigate to the feature.


Read the magnetic bearing from the index line
Point the direction of travel arrow at the feature
Ensure the map and compass are level

TRANSFERRING A MAGNETIC BEARING TO A GRID BEARING

It is important that you know how to transfer a compass bearing from a feature (a magnetic bearing) onto a map (a grid bearing). For this example, imagine that the magnetic variation is 12° west.

- Take a bearing on your chosen feature (see left). In this example it is 45° magnetic.
- You want to plot this bearing on your map, which has a grid, so remember the phrase "mag to grid—get rid." You would therefore subtract the magnetic variation (12°) from the magnetic bearing (45°), which equals 33°.
- Dial this revised bearing into your compass.



TRANSFERRING THE BEARING ONTO THE MAP

Place the top left corner of the compass base plate over the feature on your map. Keeping it there, rotate the entire compass until the orienting lines are parallel with the vertical grid lines. Draw a line from the feature down the left side of the base plate to map your bearing.


Vertical grid line
Ensure red orienting arrow points to the top of the map
The bearing on the index line reads 360° in this example
Orienting lines are now aligned with the grid lines

2 Turn the compass housing around until the orienting arrow and the orienting lines within the housing line up with the vertical grid lines on the map. Read the bearing between the two points from the index line on the compass.

- For this grid bearing to deliver you successfully to your destination, you'll need to convert it to a magnetic bearing by using the magnetic variation information on the map legend (see p. 69). Add or subtract your figure, and adjust your compass accordingly.


Walk in the direction indicated by this arrow
Orientate the compass so the north magnetic arrow sits underneath the orienting arrow

3 In order to walk on this bearing you must now orientate your compass.

- Hold the compass level and at a height that allows you to comfortably look squarely down on it (close to your chest is a good position).
- Turn your body until the north end of the compass needle sits inside the orienting arrow. The direction of travel arrow is now pointing exactly in the direction that you need to walk.

FINDING YOUR POSITION

If you are unsure of your position but can see features on the ground that you also recognize marked on your map, you can take bearings on these features with your compass and transfer them onto your map (see far left, and left) to accurately determine where you are. This process is called "triangulation" (also known as "resection" in military terminology). You'll need to transfer your compass bearings into grid bearings.

AT A KNOWN FEATURE

If you are at or on a known feature on a map—such as a river, road, or track—and you can see another recognizable feature, you can take a bearing on that feature and mark it on your map. Where that line crosses your known feature is your position. In the example below, you know you are somewhere along the banks of a river and can see a church that you can identify on your map.


Take a bearing from the church
You know you are somewhere along this river
Where the bearing crosses the river reveals your exact position

NOT AT A KNOWN FEATURE

If you are not at a known feature, but can see other recognizable features on the ground that you can identify and locate on your map, you can take bearings on these features and transfer them to your map. In order to do this you need two features that are at least 1 km (6/10 mile) away and at least 40° apart. After you have transferred both bearings onto your map, the point at which the two lines cross will reveal your exact location. For greater accuracy, plot a third feature onto your map. The lines will cross and form a triangle—your position will be inside this triangle.


Extend bearings back from both features


Where the two lines cross indicates your location

1 Using your compass, take bearings to the features on the ground.

- Transfer these bearings to back bearings (see box, above left), and draw them on the map from your chosen features.

2 Extend these lines further over the map until they cross each other.

- The point at which the lines cross shows your location.
- If you want to be more accurate, repeat the process with a third feature.

ROUTE FINDING

WHETHER YOU ARE PLANNING to walk a specific route, or are in a survival situation and need to move to a safer area or to one that offers better chances of rescue, being able to study your map and calculate what you can achieve in a certain time can mean the difference between reaching your destination or spending a night in the wilderness.

CALCULATING DISTANCE

There are several methods of calculating the distance you are walking, and a seasoned hiker will always use at least two of them at any one time.

PACE COUNTING

Pace counting involves knowing how many paces you take to cover a set distance and then counting them as you travel. It is reasonably accurate. Distances are usually calculated in meters and kilometers, and most people take approximately 60 paces (120 steps) every 100 m. Try any of these methods:

- Cut 10 notches in your walking staff. Move an elastic band down a notch every 100 m.
- Use pace counting beads (a piece of webbing with two sets of beads divided by a central knot). One side contains nine beads to count off every 100 m, and the other has four beads to count off kilometers.
- Place 10 small pebbles in your pocket. Every time you cover 100 m, transfer a pebble to the other pocket.

NAISMITH'S RULE

Naismaith's rule takes into account distance and topography, and is used for estimating the duration of hikes.

- Allow one hour for every 3 miles (5 km) you will travel
- Add 30 minutes for every 985 ft (300 m) you will climb
- Subtract 10 minutes for every 985 ft (300 m) you will descend. However, for very steep slopes you should add 10 minutes for every 985 ft (300 m) you will descend

ROUTE PLANNING

Break your route down into small sections. This will focus your navigation and make the overall distance seem less daunting. If you're in a group, designate an emergency rendezvous (ERV) point within each section—if someone gets separated you should all head there. If you can, include water sources and a safety point, such as a campsite, on your route.



When the elastic band reaches the bottom notch you have covered 1 km

USING CUT-OFF FEATURES

Use your map to choose some key features on your route, and calculate the distance between these. As you pass them, check them off mentally in your head or physically mark your progress on the map. You'll then be able to keep track of the distance you have traveled when you reach each one.

EXPERIENCE

As you gain experience you will be able to build up an idea of how long it takes you to cover a particular terrain. Naismith's Rule (see left) is an excellent starting point, but there is no substitute for picking fixed distances on your map and timing yourself over that distance. You will eventually be able to build up a frame of reference.

NAVIGATION TECHNIQUES

When navigating across land, you're less likely to get lost if you take direct bearings from one feature to another. Unfortunately this may not always be possible; obstacles such as lakes and swamps may be directly in your path and it may be easier to walk around some features rather than walk over or through them.

PRINCIPLES OF NAVIGATION

You will never get lost if you know:

- Where you started from
- What bearing or course you have been traveling on
- How far you have traveled


Aim to one side of the feature

AIMING OFF

It's easy to find yourself slightly off-course after a while. If you were aiming for a small footbridge over a stream and didn't arrive exactly at the bridge, you would need to guess whether to turn left or right to reach it. By deliberately aiming off to one side (also called "deliberate off-set") you can guarantee this direction.


Curve your route to follow the contour

CONTOURING

Climbing up and down hills can expend a lot of energy and may not be the most effective method of navigating a particular terrain. Instead, use a technique called "contour navigation." This involves walking at the same height around a feature, which will conserve energy.


Count your paces here
Clear the obstacle
Use the same number of paces to rejoin your route

DETOURING (BOXING AN OBJECT)

If an obstacle makes a straight-line bearing impossible, use your compass to calculate four 90° turns, which you will then need to walk on to pass the obstacle. Count your paces on the first and third detours to return to your original, intended route as accurately as possible.


The river is easily visible on your map

HANDRAILING

Following long linear features that run in the general direction of your travel—such as rivers, roads, or paths—can be an effective way of navigating. Because you use the features rather than your compass, navigation becomes simpler, as the features are usually easy to follow. A slight detour toward one can be worthwhile.


Head for the prominent nearby wood
Pace on the correct bearing to the exact destination

STAND OFF/ATTACK POINT

Useful when navigating to a specific point that may be difficult to locate, this technique involves aiming initially for a nearby prominent feature. Calculate a distance and bearing from it and use pacing to accurately locate the specific point. If you fail to find it, simply return to the prominent feature and start again.


Curve your route across the steep slope
The overall distance is greater but your effort is reduced

ZIG-ZAG ROUTES

You may have no alternative but to climb a steep slope and this can be exhausting. However, if you choose a zig-zag route up the slope you can reduce the effort required to achieve the climb. This will dramatically reduce the strain on your legs, ankles, lungs, and heart. It is also effective when walking down steep slopes.

NAVIGATING WITHOUT A COMPASS

IF YOU DON'T HAVE A COMPASS you can use a few simple items from your survival kit to determine direction and enable you to navigate reasonably accurately. Advances in technology have also made satellite-navigation aids more readily available.

TOOLS AND MATERIALS

You will need an improvised needle or razor blade, plus one of the following:

- Knife
- Hair
- Silk
- Magnet
- Battery and wire; paper and tape

IMPROVISING A COMPASS

It's relatively simple to make an improvised compass using a piece of magnetized ferrous metal. How accurate your compass is depends on the materials you have available to you and your own ingenuity.

SOURCING AND MAGNETIZING THE NEEDLE

If you have a compass but it's damaged, you may still be able to use the needle from it, which will already be magnetized. If this is unusable, you'll need to find a piece of ferrous metal to magnetize. Suitable items you could use include:

- A needle from your survival tin or sewing kit
- A paperclip, opened up and straightened out
- A razor blade from your survival kit
- A small nail or straightened staple taken from a fence

Once you have your improvised needle, you will need to magnetize it. The smaller and thinner the needle is, the easier this will be. Use one of the methods shown here.



You can use the blade of your survival knife to tap the needle

Tap the needle into hard wood to heighten the effect, but make sure it doesn't become embedded

THE TAPPING METHOD

Align the needle as close to the north-south line as you can determine, hold the needle at an angle of 45 degrees, and gently tap the end of it with another piece of metal. Lightly tapping it into a hard piece of wood will increase the effect.



Stroke the needle through your hair

USING YOUR HAIR

Hold the sharp end of the needle perpendicular to your head and—taking care not to hurt yourself—stroke the needle in one direction through your hair, using careful and deliberate strokes. Repeat until the needle is magnetized.

ALLOWING THE NEEDLE TO FLOAT FREELY

Once you have made your improvised needle using one of the methods above, you need to find a way to allow it to turn freely so that it is able to indicate direction. Take care to protect your needle from elements such as the wind, which will affect its movement.

SUSPENSION METHOD

The advantage of the suspension method is that the equipment is portable and can be reused. It works best with a magnetized razor blade, which will balance well. Attach the magnetized blade to a cotton thread and suspend it inside a plastic bottle. If the bottle's neck is not wide enough to fit the blade through, remove the base of the bottle instead.



The bottle protects the compass from the elements

Use the hole in the blade to attach the cotton

FLOATING METHOD

In a sheltered place, float the needle on the surface of some water—a puddle or a small non-magnetic container filled with water, for example. Balance the needle on a small, dry leaf (or piece of paper, piece of bark, blade of grass, or inside a shortened straw).



Use a puddle in a sheltered area

The needle will rotate, settle, and align itself

The leaf enables the needle to float on the surface of the water

PRINCIPLES OF MAGNETIZING

In general, the longer you work on the needle the stronger the magnetization will be and the longer it will last. To tell when it is magnetized sufficiently, hold the needle up against another metal object—if it is attracted to the metal and has enough strength to hold itself against it then it will be strong enough. Once the needle is magnetized you will need to allow it to float freely (see below), and then determine which end points north by using natural aids, such as the sun (see pp. 76–77). Mark the north end of the needle with a pen or a small scratch.


Stroke the needle 50–100 times


The end of the magnetized needle that attracts to the south pole of the magnet will point north
The more times you stroke, the more effective the magnetization

USING SILK

This works on a similar principle to the hair method but is more effective. If you have anything made from silk, such as a sleeping bag liner or thermal clothing, stroke the needle repeatedly in one direction against the silk.

USING A MAGNET

Stroke the magnet along the length of the needle repeatedly in one direction. It's a good idea to carry a magnet with you at all times, although you should never keep it near your compass as it will affect its accuracy.

USING ELECTRICITY

The most effective way to magnetize a needle is to pass a small electrical current around it. Use a battery and insulated wire; alternatively, use brass snare wire from your survival kit and insulate it using something non-conductive, such as paper.


Cover the full length of the needle with paper

1. Wrap the needle in a small piece of paper, which will insulate it from the electrical current.


Ensure no wire touches the needle

2. Wrap the wire tightly around the full length of the insulated needle.


Don't touch the wire once it's connected to the battery
1.5 volt minimum
Attach the wire using some tape

3. Attach the wire to the battery until battery starts to get warm—this indicates the process is complete.

USING GPS TECHNOLOGY

A Global Positioning System (GPS) is a hand-held unit that uses 24 orbiting satellites to triangulate your position on the Earth's surface to within meters. A GPS will allow you to work out straight-line distances and bearings to and from points, but unless it incorporates mapping it will not show you the best way to get there or take into account hazards on your route. Use it in conjunction with your map and compass.

TAKING EFFECTIVE GPS READINGS

A GPS needs to have a clear view of the sky. Anything that obstructs its signal, such as tall buildings or heavy tree canopy, will reduce its ability to lock onto satellites.


GPS
GPS 60
NORTHWEST TO FISH
CAMP
FISH
PARK
SWIM HOLE
Receiver locks onto at least four satellites to obtain a three-dimensional fix (latitude, longitude, and height) displayed as a grid reference
Durable, waterproof, buoyant case
Menus and features vary, so practice before you travel
The screen lights up for use in gloomy conditions, but avoid using this feature if you can as it will drain the batteries
Set the unit to switch off automatically after two minutes so the battery won't be drained if the GPS is switched on accidentally

NATURAL NAVIGATION

IF YOU HAVE LOST or damaged your compass and don't have the materials necessary to make an improvised version, use natural indicators to determine direction. The east-west rotation of the Earth means that you can orientate yourself according to the position of the sun, moon, and stars. All you need are some very basic materials and these simple techniques.

USING THE SUN

When visible, the sun is the clearest natural signpost to the four cardinal points (north, south, east, and west). It rises approximately in the east and sets approximately in the west and, at midday, is due south in the northern hemisphere and due north in the southern hemisphere. Use the sun's course across the sky to determine direction and approximate the time.

SHADOW STICK BASICS

Use a shadow stick to determine direction and time anywhere between the Arctic (66.5°N) and Antarctic Circles (66.5°S).

- In the northern hemisphere the shadow of the stick will be on the north side of the east-west line
- In the southern hemisphere the reverse is true: the shadow of the stick will be on the south side of the east-west line.
- When the shadow is at its shortest, it is midday.

ORIENTATION

Tracking the movement of the sun across the sky using a shadow stick will provide an indication of its direction of travel. The sun moves from east to west at 15° an hour.

1 Drive a stick into a piece of level ground, and ensure it's as upright as possible.

2 Place a stone at the tip of the stick's shadow.

3 Wait three hours and place a second stone at the new position of the shadow's tip.



The stick should be approximately 3 ft (1 m) high

A line linking the two stones will point east-west

Place the first stone on the line of the first shadow

Place the second stone on the line of the second shadow

A line at 90 degrees to the east-west line will point north-south

4 Draw a line between the stones to find east-west; the first stone will be at due west and the second at due east.

5 To find north-south, mark a line at 90° to the east-west line.

TELLING THE TIME

Once you have established the east-west and north-south lines, you can turn the shadow-stick apparatus into a sundial, to give an approximate idea of the time.

1 Place the stick at the intersection of the north-south and east-west lines

2 Tie a piece of cord to the stick. Attach a smaller stick to the other end of the cord and use it to draw an 180-degree arc between the two marker stones.



Move the shadow stick into the correct position on the ground

Draw an arc between the two marker stones

The shadow touching this notch indicates that it is roughly 5pm

The central notch represents noon

3 Divide the arc into 12 equal sections and mark each division with a notch. The notches represent one hour of time, from 6am to 6pm with noon at the middle notch.

USING THE STARS

It's possible to orientate yourself by spotting certain recognizable stars. In the northern hemisphere, Polaris is located above due north on the horizon, from which you can determine east, west, and south. Find it by locating the Plow (also known as the Big Dipper). In the southern hemisphere, you can work out the approximate position of south on the horizon by finding the Southern Cross.



NORTHERN HEMISPHERE

Find the Plow and project a line from the top of the two stars that form its front. Follow this line until you find Polaris, which is located approximately four times the distance from the Plow as the distance between its two front stars.



SOUTHERN HEMISPHERE

Project a line from the longer axis of the Southern Cross until you find a dark area of sky. Project a second line at 90° from the mid-point between two bright stars in the Centaurus constellation. Due south is below the point where these lines meet.

USING THE MOON

Reflecting the light of the sun, the moon rises in the east and sets in the west, so can be used for orientation. A shadow stick will work on a cloudless, full-moon night.



CRESCENT MOON

Although not an entirely accurate method, a line vectored between two horns of a crescent (quarter) moon will lead to a point that is approximately south on the horizon in the northern hemisphere, and roughly north in the southern hemisphere.

USING AN ANALOG WATCH

If you can see the sun, you can use an analog watch as a protractor to determine an approximate direction. Ensure it is set to the correct local time and that you have taken daylight savings (DST) into account. If you don't have a watch but know the time, simply draw a watch face on a piece of paper, marking 12 o'clock and the hour hand. This method is increasingly less effective as you near the Equator.


Bisect the angle between the hour hand and 12 o'clock
S
Point the hour hand toward the sun

NORTHERN HEMISPHERE

In the northern hemisphere the cardinal point nearest to the sun is south. Point the hour hand of your watch at the sun and bisect the angle between the hour hand and 12 o'clock. This will be due south.


N
Bisect the angle between 12 o'clock and the hour hand
Point the 12 o'clock marker toward the sun

SOUTHERN HEMISPHERE

In the southern hemisphere, the cardinal point nearest to the sun is north. Point the 12 o'clock marker on your watch at the sun and bisect the angle between 12 o'clock and the hour hand on the watch. This will be due north.

NATURAL SIGNPOSTS

Nature responds to the elements in a range of ways, some of which can be studied for orientation tips. This is useful if you know the predominant wind direction of an area.

TREES AND PLANTS

- Windswept trees point away from the wind.
- Tree growth is most lush on the side that faces the sun (south in the northern hemisphere, north in the southern hemisphere).
- Some plants, such as the barrel cacti, twist toward the sun as they grow.
- Moss and lichen grow out of direct sunlight, on the shady side of rocks or trees.

ANIMALS AND INSECTS

- In very windy areas, small animals and birds tend to nest or burrow on the lee-side of hills.
- Spiders spin webs out of the wind, so an area with a lot of broken webs could indicate a recent change of wind direction, away from the dominant wind.

SNOW AND ICE

- In powder-snow conditions, snow "dunes" often form parallel to the prevailing wind.
- Frost erosion is most severe on slopes facing the sun (south in the northern hemisphere, north in the southern hemisphere).

HOW WEATHER WORKS

CHANGES IN THE WEATHER can have a significant effect on your expedition—or chances of survival if something goes wrong—so it's important to be as prepared as possible for all the conditions you might face. Check the weather report for the days ahead thoroughly, and pack and wear appropriate clothing. If the weather forecast is so bad that it could make traveling or navigation difficult, rethink your plans.

WHAT IS WEATHER?

The term "weather" relates to current conditions on the ground—such as the temperature, and whether or not it is windy or raining—while "climate" refers to a region's conditions over a longer period of time. Changes in the weather are caused by alterations in air pressure and temperature. Extreme weather, such as a hurricane, occurs when these changes are more marked than usual. Weather is monitored by meteorologists, and very accurate predictions can be made. However, weather can still cause surprises, so always prepare for all possible scenarios when packing or dressing for an expedition.

UNDERSTANDING THE WEATHER

Weather is created by the movement of air currents, the moisture content of the air, and the meeting of warm and cold fronts. Looking at weather maps before you leave for your trip will help you track these elements. You'll then need to use your understanding to forecast the effects of these movements on the ground.

READING WEATHER CHARTS

It can be helpful to compare weather charts with regular topographic land maps. Just as the gradient is steeper where contour lines appear closer together on land maps, the wind is stronger where isobar contours appear closer together on weather charts.



Fronts move in the direction that their symbols point toward

Areas of high pressure are generally associated with warm weather

A blue line with triangles represents a cold front, and marks the leading edge of cold air

Areas of low pressure are associated with cooler weather

Occluded fronts are fronts where two air masses merge

The lower the value of the central pressure, the more severe the wind and rain

A red line with semi-circles represents a warm front, and marks the leading edge of warm air

Isobars join areas where the air pressure is the same

HIGH
1024
1016

HIGH PRESSURE

Under conditions of high pressure, air descends in a spiral formation, and warms. The water vapor does not condense into clouds and we would expect to observe fairly clear skies.



LOW PRESSURE

Under conditions of low pressure, air spirals upward—parallel to the center of the isobars—and cools. The air condenses to form clouds, and skies are usually overcast.

GLOBAL CIRCULATION

Warm air from the equator rises and moves toward the poles in each hemisphere. As it cools it descends and travels back toward the equator. Because of the Earth's rotation, three separate cells of circulating air in each hemisphere develop, which produce predictable wind and pressure patterns.

AIR MASSES

Large bodies of air with a particular temperature and humidity help weather forecasters predict the forthcoming weather and are known as air masses. They are largely defined by the area that they originated from. In general, northerly winds are colder than southerly winds, and air that has tracked over the sea ("maritime air mass") accumulates moisture and is more cloudy than air that has tracked over the land ("continental air mass"). The boundaries between tropical and polar air become warm and cold fronts.


Cells develop because of the Earth's spin
The Earth's rotation causes winds in the northern hemisphere to be deflected to the right
Air is continually heated at the equator
The Earth's rotation causes winds in the southern hemisphere to be deflected to the left

ON THE GROUND

As a weather system travels over the ground, it changes in predictable ways. Knowing how the system will progress is an important part of interpreting your weather map or forecast.


Cold front
Clouds condense and fall as rain
The region between the fronts is known as the "warm sector." The surface pressure is steady and the sky generally remains overcast with rain and drizzle
Approaching high cloud often indicates a warm front is on the way
Wind increases and moves upward. Pressure rises sharply and large clouds start to form
The air cools and water vapor condenses to form cloud and rain along the boundary
Cold air
As the warm air advances it rises over the cooler air ahead. Pressure falls steadily
As the rain falls, clouds begin to disperse behind the front
The cold air undercuts the warm air ahead and lifts it
Warm air
Warm front
Cold air

WEATHER PHENOMENA

LOOKING AT THE CLOUDS can help you to read approaching weather, which is invaluable when you're on the move with no access to weather forecasts or charts. Knowing how to recognize a storm cloud, for example, will ensure that you have enough warning to seek shelter or to change into appropriate clothing. If low cloud threatens to impair your visibility, use your compass to navigate and proceed with caution.

HOW CLOUDS FORM

Clouds form by a cooling process. This process can be compared to breathing on cold glass, when condensation appears because invisible water vapor in your breath, cooled to a temperature known as the "dew point," condenses into its visible liquid state. Clouds form in a very similar way. Air temperature falls at an average rate of two degrees celcius per 1,000 ft (300 m). When air containing moisture—perhaps because it has travelled over sea—reaches the height at which it meets its dew point temperature, the water vapor condenses to form visible cloud.

READING THE CLOUDS

Clouds are condensing masses of water vapor that provide precipitation and reflect solar radiation. They are categorized by height—into low, medium, and high clouds—and further defined by their shape. The shape of a cloud is determined by the way in which warm air rises, and is an indicator of the air stability.

HIGH CLOUDS

Fair-weather clouds are white and high in the sky. If there are no clouds, expect excellent conditions. Blankets of high cloud progressively invading the sky can signify the onset of bad weather. High clouds include:

- Anvil of cumulonimbus
- Cirrus
- Cirrustratus

MEDIUM CLOUDS

Thick layers of medium-layer cloud give heavy, persistent rain, especially if the clouds are dark and gray. The clouds you are most likely to see at this level are:

- Altocumulus
- Nimbostratus
- Altostratus

LOW CLOUDS

Low clouds have clearly defined edges and can indicate whether rain will fall in short downpours (cumulus) or persistently (stratus). Common clouds are:

- Cumulonimbus
- Stratus
- Stratocumulus
- Cumulus



*Tall **cumulonimbus** formations form an "anvil" shape, which is associated with thunderstorms and heavy rain*

***Cumulonimbus** clouds develop under deeply unstable conditions. They are large, deep clouds that start low in the sky and build upward. Moist air ascends quickly and condenses into water droplets, making rain likely*

WEATHER RISKS

The weather can have a massive impact on your trip, bringing with it added dangers. It can affect your visibility levels, and the safety of the ground you're hiking over. In a survival situation, the temperature, and whether or not it's raining, can have a huge effect on your chances.

WARNING!
Never shelter under a solitary tree during a lightning storm—get in your vehicle if possible or find low ground.

HEAVY RAIN

If heavy rain falls quickly, the ground may become saturated, slippery, or flood. Seek shelter or proceed cautiously in waterproof clothing.



If you cannot see where you are going it's best to stop walking

FOG

Essentially a cloud in contact with the ground, fog reduces visibility, so beware of dangerous terrain, especially on mountains.

LIGHTNING

Lightning is an atmospheric discharge of electricity—it will strike the first object it encounters on its route to earth, so avoid high, exposed places.



*Resembling fine strands, **cirrus** is made from ice crystals as the cloud forms at temperatures well below freezing point*

*Thick, high layers of **cirrustratus** progressively invading the sky are the first sign of an approaching warm front and deteriorating weather*

***Altocumulus** develops as small, cellular elements. It signifies fairly deep instability. When it resembles castle battlements thunderstorms are likely*

*Often following altostratus clouds, **nimbostratus** clouds can cause moderate to heavy, persistent rain*

***Altostratus** forms a vast blanket that often shrouds the sky completely and generally indicates an approaching warm front*

*Dense, gray **stratus** cloud covers the sky in a sheet. Rain can fall continuously and for long periods of time if the cloud has depth*

***Stratocumulus** cloud covers the sky in an irregular sheet that can be either gray or white in color. These clouds can lead to drizzle or snow*

***Cumulus** clouds often develop on bright sunny days in slightly unstable airmasses. As long as these billowing, puffy clouds keep their form, they—along with blue sky—indicate good weather*

UNDERSTANDING LOCAL WEATHER

WEATHER IS AFFECTED—and can be predicted—by the local geography surrounding you. High ground forces air to rise and cool, and the relative temperatures of land and sea produce predictable effects.

REGIONAL EFFECTS

It helps to understand how these predictable weather patterns occur in various geographic areas. They may influence your decisions when on the trail.

THE FOHN EFFECT

The leeward side of high ground is warmer and more sheltered than the windward side. Air rises as it travels over obstacles and, if the air contains moisture, the water vapor condenses to form cloud once cooled to a certain level. The air loses water at the summit, then descends and warms on the leeward side.


Air cools as it rises at a rate of 37 °F (3 °C) per 1000 ft (300 m)
Air cools at 35 °F (1.5 °C) per 1000 ft (300 m)
Water vapor falls as rain at the summit
Dry air descends and warms at a rate of 37 °F (3 °C) per 1000 ft (300 m)

ANABATIC AND KATABATIC WINDS

Winds that flow up and down slopes during certain atmospheric conditions are known as "anabatic" and "katabatic." They typically occur in mountainous regions.


Heated air rises, then falls as it cools

ANABATIC WINDS

During the day, the surface of sloping terrain heats up. The air rises and creates a gentle upslope breeze. Anabatic winds are lighter than katabatic winds because they act against gravity.


The flow of air is assisted by gravity

KATABATIC WINDS

Katabatic winds form on clear nights with a light breeze. Air in contact with the ground cools and its density increases, causing it to flow down the slopes of the hillside.

SEA AND LAND BREEZES

Sea breezes often develop along coastlines on clear sunny days, whereas land breezes tend to develop along coastlines on cloudless nights.


Air warmed by the land rises, then cools as it crosses the sea
In daytime, the sea is cooler than the land

SEA BREEZE

Warm air rises over land during the afternoon, drawing in cool air to replace it along the coast. The result of this coastal air circulation by day is a wind that blows from sea to land.


As the air passes over the land it cools
At night the sea is warmer than the land

LAND BREEZE

At night, the sea becomes comparatively warmer and air begins to rise. Air from the neighboring land is drawn toward the sea. The result is a wind that blows from land to sea.

NATURAL WEATHER FORECASTERS

These natural indicators are based on observation and can be useful if you have no alternative means of predicting the weather.

LOOKING AT THE SKY

- If the sky is red at dawn there is moisture in the air and a potential storm ahead. A red sky at night often indicates good weather to come.
- A rainbow usually indicates good weather is on the way, or a light shower.

PLANTS AND FLOWERS

- The scent of plants and flowers is often stronger before rain.
- Certain flowers, such as Scarlet Pimpernel and Morning Glory, are said to close up if bad weather is on the way.
- Pine cones are one of the best natural forecasters—their scales absorb moisture in the air and close up if wet weather is approaching, and unfurl in dry air.


Closed cone indicates approaching wet weather
Open cone indicates dry air

WATCHING ANIMALS

- Animals migrating from high to low areas may indicate that a storm is on the way.
- Cows often lie down before it rains.
- Wool reacts to moisture in the air by swelling and straightening. It shrivels in dry weather conditions.
- Humans can also sense atmospheric change—some people suffer headaches before a thunderstorm.

CHANGING WEATHER

Watch out for alterations in the wind direction or strength as this may lead to a change in the weather. A dry, steady wind that changes direction or decreases in strength often indicates that rain is on its way.

THE BEAUFORT SCALE

Providing visual references for the effects of wind speed on land and at sea, the Beaufort Scale was designed by Sir Francis Beaufort in 1805. It provides a simple way of estimating wind speeds without the need for equipment, and is still in common usage today. The scale ranges from calm to hurricane, and is numbered from zero to 12.

BEAUFORT NUMBER	WIND DESCRIPTION	WIND SPEED MPH (KPH)	WIND EFFECT ON LAND AND AT SEA
0	Calm	0 (0)	Smoke rises vertically. Sea like a mirror.
1	Light air	1–2 (1–3)	Smoke drifts gently. Sea ripples like scales.
2	Light breeze	3–7 (4–11)	Leaves rustle. Wind felt on skin. Small wavelets.
3	Gentle breeze	8–12 (12–19)	Leaves and twigs move. Large wavelets with scattered whitecaps.
4	Moderate breeze	13–18 (20–29)	Small branches move. Small waves with frequent whitecaps.
5	Fresh wind	19–24 (30–39)	Small trees begin to sway. Moderate waves with some foam and spray.
6	Strong wind	25–31 (40–50)	Umbrella usage is difficult. Large waves of 10 ft (3 m) with some spray.
7	Near gale	32–38 (51–61)	Whole trees sway. Sea heaps up and foam begins to streak.
8	Gale	39–46 (62–74)	Walking is difficult. Moderately high waves of more than 18 ft (5 m).
9	Severe gale	47–54 (75–87)	Damage to roofs. High waves with toppling crests.
10	Storm	55–63 (88–101)	Trees uprooted or broken off. Very high waves and sea surface appears white.
11	Severe storm	64–74 (102–119)	Houses damaged. Exceptionally high waves of more than 38 ft (11 m).
12	Hurricane	More than 75 (More than 120)	Buildings destroyed. Huge waves of more than 46 ft (14 m).

MAKE A MOVE

While some survival situations are simply unavoidable, many are entered into because basic techniques relevant to a particular mode of transport have not been followed correctly. This could be due to a lack of knowledge, a loss of concentration, an individual's over-confident belief in his or her own equipment or skills, or as a result of sheer recklessness. Therefore, before you venture into an unfamiliar environment, make sure that you carefully research the type of terrain you will be encountering and investigate the best method of traveling safely and efficiently across it. Knowing the correct techniques for scrambling up a mountain or walking down a steep hillside, for example, could mean the difference between an enjoyable day out and a life-threatening survival situation arising from a fractured ankle in a remote location. Equally, being able to regain control of your vehicle after it has entered a skid could quite simply save your life. Thoroughly researching the terrain will also allow you to select the correct

In this section YOU WILL DISCOVER...

- how to make a **paddle** (so you're never **up a creek** without one)...
- the difference between your **finger shelf** and your **hand jam...**
- how to **pull** your own **pulk** and **scramble** over **scree...**
- when to **blaze a trail** or **ski without skis...**
- how to tell your **front-wheel skid** from your **skidoo...**
- when to let the **camel train** take the **strain...**
- how **chewing gum** can stop that **sinking feeling...**

equipment and most appropriate clothing, and enable you to familiarize yourself with the survival techniques relevant to a particular environment.

Whether you’re planning to travel on foot, by boat, on horseback, in a 4WD vehicle, or by boat, you must consider not only your own capabilities and those of other members of your team, but also the capabilities of your equipment. Remember, pushing anything beyond its limits—whether that be a person, an animal, or a vehicle—will invariably lead to it failing.

A walking staff is one of the simplest yet most important survival aids you will ever need. It’s the first piece of equipment to improvise should you find yourself in a survival situation.

THE “SURVIVOR’S THIRD LEG”—as a walking staff is also known—increases your ability to support yourself by allowing you to have two points of contact with the ground at any one time. This will reduce the chance of you slipping—a crucial factor given that your ability to walk is your main means of rescue; reduce your mobility and you seriously reduce your ability to survive.

A versatile tool, your survivor’s third leg can be employed in many different survival situations. Among its many uses, it can be employed to:

- Support you as you walk
- Protect your face when you’re walking through thickets or gorse
- Check for adequate support when crossing marshy ground
- Test the ground ahead for obstructions
- Check the depth of water when you’re crossing streams and rivers
- Protect you against wild animals
- Form a ridgepole for your shelter
- Help you with your pace counting
- Spear fish or catch game
- Dig up roots or plants

> “Your ability to walk may be your **primary means of rescue**; reduce your mobility and you dramatically reduce your **chances of survival**”

TRAVELING ON FOOT

HIKING IS A GREAT WAY to explore wilderness terrain. It's important to have a decent level of fitness before you set out, and to wear and carry appropriate clothing and equipment. Hiking requires basic skills—using the correct techniques will help you move more efficiently, and ensure that your trip is safe.

BASIC WALKING SKILLS

Aim for a slow, even pace that can be maintained for the duration of the hike by all members of the group. A good way to maintain this pace is to develop a hiking rhythm. Take regular rest breaks and, if you're walking in a group, ensure everyone knows the route.

UPHILL TECHNIQUES

When traveling uphill, lean forward slightly, maintain your momentum but shorten your stride. When pushing upward, keep your feet flat on the ground.

- Carry a walking staff for support as you ascend.
- Move your legs forward from the hips.



Make sure your backback fits properly for comfort

Swing your arms for momentum and balance

Break in new boots before long hikes to avoid blisters

Deep tread grips the ground and reduces slipping



Lean backwards slightly

DOWNHILL TECHNIQUES

Walking downhill can place a lot of strain on your thighs, knees, and ankles, especially when you're carrying a heavy backpack. Be careful not to lose control or gather too much speed.

- Use your arms for balance.
- Maintain a steady rhythm.

WALKING AT NIGHT

Unless you're in the desert and it's cooler to move in darkness, avoid walking at night because of the added risks posed by navigational difficulties, and predators that hunt at night. If there's no alternative, try the following:

- Use your flashlight or improvise a torch by setting alight some birch bark or similar.
- If this isn't possible and you've time, close your eyes for 20 minutes to allow them to adjust to night vision.
- Use your walking stick or pole to feel in front of you for obstacles, tripping hazards, or sudden drops in the ground.
- Keep your pace slow and deliberate, and check your compass regularly.

NEGOTIATING DIFFICULT GROUND

One of the most challenging terrains to hike over is "scree," a mass of small rocks that slides underfoot making uphill and downhill travel difficult. The slippery nature of the surface can make progress slow, and care should be taken to avoid falling and injuring yourself. Hiking on scree is hard work, but using the correct techniques will help you to advance confidently, efficiently, and safely.

TRAVERSING SCREE

Choose a zig-zag route and look for a path that contains similar-sized rocks. Walk sideways across the slope, taking small steps and testing rocks for stability before placing your full weight on them.



Rocks at the edge of the slope are likely to be larger and more stable

ASCENDING SCREE

Tread carefully, kicking your toes into the slope and testing the step before transferring your weight to that leg. Alternatively, walk with your feet splayed, placing your weight on the inside of each foot.

DESCENDING SCREE

"Screeing" downhill combines sliding with slow-motion jogging. When you have the technique it can be great fun, but avoid larger rocks to prevent ankle injuries.



Face the direction of travel

Knees are your center of gravity

1 Ensuring the scree is fine and deep, use gentle hops to launch yourself down the slope. Keep balanced and let gravity do the hard work.



Stay as upright as possible

Use your arms for balance

2 As you build up momentum and rhythm, dig your heels into the slope and slide a short distance with each step, avoiding leaning forward.



Use your arms to break your fall

Keep your knees bent as if you're skiing downhill

3 If you lose your balance temporarily, use your arms to steady yourself, relax your knees, and continue your descent.

TRAIL MARKERS

Your map and compass should be your primary method of navigation, but keep an eye out for trail markers, or "blazes," during your hike.



Trails are coded using colors or symbols



Arrows indicate direction

ROCKS

Trail blazes painted onto rocks and boulders are especially common in rocky terrain. They may be low on the ground so look carefully.

SIGNPOSTS

Made from wood, metal, or plastic, these signposts are particularly useful in areas where there are few rocks or trees on which to blaze.



Stacks should be visible from a distance



The same sign may indicate several trails

CAIRNS

Piles of rocks, known as "cairns," are designed to be visible in thick fog. Their size can vary from a few rocks to a large stack of boulders.

DIRECTIONAL SIGNS

When reading markers, look out for painted arrows or variations in the blazing, such as a bend. This indicates a change of direction in the trail.

CROSSING RIVERS

RIVER CROSSINGS ARE DANGEROUS and should be avoided unless absolutely necessary. In a survival situation, once you are cold and wet—which can lead to hypothermia—it is hard to get warm and dry. Always check your map for routes around the river, and choose the safest available crossing point.

WADING BASICS

Wear footwear when wading to protect your feet from rocks and other dangers. Remove pants to keep them dry and decrease resistance in the water. Use a walking staff for added support.

CROSSING SAFELY

Before you get into the water, make sure you have a change of clothes or means of getting dry on the other side. In cold conditions, collect everything you need to get a fire going (tinder, kindling, and dry wood), and keep this dry as you cross.

CHOOSING YOUR CROSSING POINT

Walking upstream generally leads to shallower water, but be aware that even shallow water can have strong currents, as can water that looks calm on the surface. Always check for bridges further up- or downstream.



Trees on the opposite bank provide shelter from the wind after exiting the water

Exposed rocks can be dangerous if you slip onto them

Avoid crossing on the outside of bends where water flows faster

Watch out for unusual variations in the flow of the water—there may be rocks beneath

Always assess how fast-moving the water is, and use your walking staff to assess depth

Look for shallow banks, as they make entering and exiting the water easier

This gravel shoal can be a good halfway point, but be aware of fast-flowing water channeled around it

Cross downstream of debris or fallen trees, as it is easy to get caught up and dragged under the water

WADING WITH OTHERS

Crossing in a group is safer than crossing alone. Linking your arms together creates a stronger, more stable structure against the current and provides backup for anyone who falls. Loosen the straps of your backpack, and place only one arm through them, so you can release the pack quickly if you fall.

WARNING!

Never cross white water, or rivers that have flooded. In these situations it is safer not to cross at all than to risk injury.


Lean into the center slightly
Place your arms on each other's shoulders
DIRECTION OF TRAVEL
DIRECTION OF CURRENT
The strongest person bears the main force of the water

CROSSING IN A HUDDLE

Positioning the strongest person upstream, with the others providing stability and support, link your arms tightly and take short, deliberate steps across the river.


Loosen the straps of your backpack
The lightest person crosses in the middle
The person bearing the main force of the current takes the lead
DIRECTION OF TRAVEL
DIRECTION OF CURRENT

CROSSING IN A LINE

Keeping well balanced, cross the river perpendicular to the current. Move slowly and position each step carefully to avoid being swept away by the force of the water.

WADING ALONE

Wading across a river alone is not ideal, but if you have no option then your walking staff or "survivor's third leg" (see p. 72)—or simply any long stout stick—will provide additional support and balance. Use it as a probe to alert you to any sudden changes of depth in the river bed.


DIRECTION OF TRAVEL
Keep an eye on your overall progress, as well as on your feet
Lean on the pole as you move your feet
DIRECTION OF CURRENT
Tread firmly on the river bed to prevent yourself from being swept away by the current

USING A WALKING STAFF

Facing the current, walk diagonally across the river, placing each foot down firmly and deliberately, and leaning on your walking staff for support. Your feet and your staff are your three points of contact—keep at least two of them in contact with the river bed at all times.

CROSSING WITH ROPES

Using ropes is a good option for dangerous crossings, but they can get tangled, and drag you under the water. Always aim for the easiest and safest option—using ropes is complicated and should be your last resort.


Each rope is paid out by a person on the bank
Safety rope is attached to a tree

1 A "safety" rope is tied to a tree and then carried across by the strongest person, who also takes a "crossing" rope with a carabina tied centrally.


Safety rope is tied to a second tree
Crossing rope is wrapped around body

2 The safety rope is tied to a tree and the carabina clipped to the safety rope. The carabina is pulled back and fixed to the next person to cross.


Backpacks are transported across

3 He or she crosses upstream of the safety rope, holding it for support. Backpacks can be clipped to the carabina and transported, too.


The last person to cross is supported by the others

4 The final person unties the safety rope from the tree, wraps it around his or her body, and wades across, supported by the others.

SCRAMBLING AND CLIMBING

CLIMBING WITHOUT ROPES is known as "scrambling." As with roped techniques, the idea is to maintain three points of contact with the rock at all times—either two feet and one hand or both hands and one foot. Your legs should power the climb, with your arms used predominantly for balance. Proceed carefully, making sure you are always balanced and confident of your next move.

WARNING!
Climbing is a dangerous activity that should only be considered as a last resort. Ideally, plan ahead using your map to find a way around the obstacle.

HAND AND FOOT HOLDS

When planning your route, choose your hand and foot holds carefully. Don't reach too far, and test each hold for stability before using it to support your weight.



EDGES

For very small footholds, place the inside edge of your foot in the hold in the rock to take the pressure off your toes.



FINGER SHELVES

Curl your fingers over the rock for a secure fingerhold. The larger the fingerhold, the more secure it will be.



LARGE POCKETS

Placing your foot securely within the pocket, balance yourself so both your arms and legs take the strain.



SIDE PULLS

Side pulls can be used to maintain balance or to pull yourself across the rock. Grip the rock tightly.



PROTRUSIONS

If possible, place the entire sole of your foot on the protrusion. If only the ball of your foot will fit, keep your heel low.



HAND JAMS

Insert your hand into the crack, push your thumb into your palm, arch your hand, and wedge it tightly inside.

BASIC CLIMBING TECHNIQUES

Always climb within your capabilities. It's important not to take any risks, as it's far safer to descend and start the climb again than to chance a fall. Before you start to climb, plan the easiest and safest route.

SCRAMBLING

When moving across the rock you will need to combine a variety of techniques to negotiate different obstacles. Always plan your moves several steps in advance, and keep three points of contact with the rock at all times.



Take the weight of your backpack into account when moving

Always ensure you can move back down if you can't move up

MANTELLING

The mantelling technique is used to climb overhangs in the rock. Use your lead ankle and then your knee to lever your body up over the obstacle. It's a physically challenging technique, but useful.


Lift your ankle onto the shelf, followed by your knee
Lean your weight on your elbows until you are ready to push up with your arms
Supporting leg

CHIMNEYING

To climb up the inside of large rock clefts, or "chimneys," use the chimneying technique. To ascend, move your back and hands up the wall, and push and follow with your legs. It's easy to get stuck at the top so plan your exit route carefully.


Use your arms to push upward and guide your body
Brace your feet against the opposite wall and take small steps upward

STRADDLING

If the chimney is relatively wide, you may need to alter your body position to straddle the gap. With a leg and arm on each wall, inch yourself up the rock using your legs to push your body upward.


Use your arms to steady yourself
Wear shoes or boots with a good grip

CLIMBING WITH EQUIPMENT

The advantages of climbing with ropes cannot be underestimated as far as safety is concerned, although a lot of specialized equipment is required. As well as ropes, helmets, and harnesses, climbers can also use screws to secure themselves to the rock as they progress each stage.

BELAYING

Belaying is a technique used by climbing partners to safeguard each other during a climb. The belayer secures himself to the rock and stands on a suitable ledge while the lead climber ascends. Once at the top, the lead climber secures himself and acts as the belayer.


Lead climber's rope
Secured rope
The belayer must watch the climber at all times

ICE CLIMBING

Ice climbers utilize similar techniques to rock climbers, although they carry ice axes and wear crampons on their feet, to help them grip the ice.

MOVING UPWARD

As with rock climbing and scrambling, ice climbers ascend using power from their legs and arms. Crampons and ice axes are used to create holds in the rock.


Use the ice axe to pull yourself up
Legs power the climb
Kick the crampons securely into the ice

TRUE-LIFE ACCOUNT

EXTREME SURVIVAL— IN THE MOUNTAINS

USEFUL EQUIPMENT

- Two-way radio
- Avalanche beacon and probe
- Waterproof clothing
- Spare clothing layers
- Collapsible shovel
- Climbing equipment, if needed
- Signal flares
- Map, compass, GPS
- Survival tin, bushcraft knife
- Cell/satellite phone
- Poncho/bivy sack

STEVEN GREEN, 32, AN EXPERIENCED HILL WALKER from Dumfries, Scotland, spent four nights lying on a remote mountainside after a life-threatening fall. Suffering from a broken jaw and fractured skull, he survived via a combination of good preparation, quick thinking, and improvisation.

On Thursday, October 7, 1999, Steven set out alone for a trek in the hills of Wester Ross in the northwest Highlands of Scotland. He was well equipped with, among other things, a cell phone, bivy sack, pita bread, and water—and had taken the wise precaution (or so he thought) of informing his girlfriend of his intended route.

Following an all-day trek and an overnight camp, he was descending the mountain on Friday when he slipped on wet grass and fell down a waterfall, coming to rest in the shallow, rocky riverbed. He knew he would not survive for long in the cold water so, despite being in intense pain, he crawled to the relative safety of the bank, then wisely got into his bivy sack for warmth and waited. He sustained himself by eating pita bread, which he softened in water because he couldn't chew. His phone was damaged in the fall so he was unable to call for help. When he failed to return home on time, the alarm was raised by Steven's girlfriend, but she had forgotten to write down his intended route so no one knew his exact location.

"HE SLIPPED ON WET GRASS AND FELL DOWN A WATERFALL"

Steven experienced a further four days and nights of exposure while local and RAF rescue teams and search-and-rescue dogs combed the mountains for him. As the days passed they feared the worst, but when they located Steven on Tuesday morning—after finding his car and, inside it, his route map—they found him in good spirits. At hospital Steven was diagnosed with a fractured skull, broken jaw, missing front teeth, cuts and bruises, and a leg injury—but he was alive.

WHAT TO DO

ARE YOU IN DANGER?

NO: If you are in a group, try to help any others who are in danger

YES: Get yourself out of it:
Elements—Find or improvise immediate shelter
Animals—Avoid confrontation and move away from danger
Injury—Stabilize condition and apply first aid

ASSESS YOUR SITUATION

See pages 234–35

DOES ANYONE KNOW YOU WILL BE MISSING OR WHERE YOU ARE?

NO: If no one knows you are missing or where you are, you will need to notify people of your plight by any means at your disposal

YES: If you are missed, a rescue party will almost certainly be dispatched to find you

DO YOU HAVE ANY MEANS OF COMMUNICATION?

NO: You are faced with surviving for an indefinite period—until you are located or you find help

YES: If you have a cell or satellite phone, let someone know your predicament. If your situation is serious enough to be worthy of emergency rescue, and you have a Personal Locator Beacon (PLB), you should consider this option

CAN YOU SURVIVE WHERE YOU ARE? *

NO: If you cannot survive where you are and there are no physical reasons why you should remain, you will have to move to a location that offers a better chance of survival, rescue, or both

YES: Address the Principles of Survival: Protection, Location, Water, Food

YOU WILL HAVE TO MOVE **

DO

- Keep all clothing dry and clean
- Collect drinking water from fast-moving streams; filter and disinfect if you have the means
- Be on constant lookout for signs of cold-related injuries such as frostnip, frostbite, and hypothermia
- Regulate your clothing to avoid overheating when moving and hypothermia when static
- Use a walking staff to aid safe movement
- Watch the weather closely and be prepared to change your plans at short notice—mountain climates are highly unpredictable
- Improvise shelter when not on the move

DON'T

- Descend hills in a careless manner; zig-zagging across hills is less tiring and puts less strain on leg muscles
- Travel at too fast a pace—high altitude equals less air and this will place greater demands on even a fit person
- Sweat too much, as the moisture will chill you further
- Ignore any opportunities to collect dry tinder/kindling

YOU SHOULD STAY **

DO

- Select a shelter site that offers protection from the elements. Build it no bigger than it needs to be
- Fill plastic bags or spare clothing with dry foliage and use as a mattress or pillow to insulate you from the cold, damp ground
- Deploy all your aids to location and prepare for immediate use
- Check upstream for the quality of your water source
- Light a fire and (if in a group) take turns tending it to keep it going all night
- Continually re-assess your situation and adapt your actions as necessary.
- Be constantly alert for signs of rescue

DON'T

- Allow your extremities to get too cold as those areas are most susceptible to frostbite
- Overlook the dangers of carbon monoxide poisoning in cramped shelter. Don't let candles, stoves, or fires burn all night
- Breathe on your hands to warm them up: you are exhaling warm air that you will have to replace with cold

---

* If you cannot survive where you are, but you also cannot move owing to injury or other factors, you must do everything you can to attract rescue.

** If your situation changes (for instance, you are "moving" to find help, and you find a suitable location in which you can stay and survive) consult the alternative "Do" and "Don'ts."

MOVING OVER SNOW

PREPARATION IS ESSENTIAL when hiking over frozen terrain. Not only must you be physically fit—the conditions make for slow, exhausting progress—but you must also have the right equipment and know how to use it. Wearing snowshoes or skis, and breathable and layered clothing to regulate your temperature, is essential. With the correct techniques you can hike safely and enjoy the surroundings.

WARNING!

Walking over deep snow without snowshoes is called "post-holing" and should be avoided unless absolutely necessary. Sinking into the snow will leave you exhausted and very wet, which in cold conditions can quickly lead to hypothermia. The exertion can also cause sweating and a dangerous reduction in your body temperature when you stop.

SNOW AND ICE

Knowing how to deal with different types of snow and ice is invaluable when hiking over frozen terrain.

DEEP SNOW

- If in a group, walk in single file and take turns at the front: the most strenuous position, as you're creating the path.
- Avoid rocks—in spring, they absorb heat and the snow above becomes unstable.

FROZEN CRUST

- Use a walking staff to test the snow ahead. An ice crust above deep snow may take your weight, but progress carefully.
- Later in the day you may come across melted depressions, called "sun cups." Cross on the rims to avoid sinking into the snow.

SLOPES

- Kick firmly into the slope and test your weight before ascending. When descending, you can use a technique called "boot skiing" (skiing without your skis).
- Choose your route based on the conditions: travel in straight lines if you are able to, or in zig-zags if the terrain is steep.

ICE

- Always progress carefully, using your walking staff to test the ice, especially over rivers and lakes. If in a group, rope yourselves together for safety.
- Wear crampons for extra grip. On very steep slopes, use your ice ax to cut steps.
- Use your ice ax to halt a fall by turning to face the slope and digging it into the ice.

GLACIERS

- Never attempt to cross glaciers without a guide—glaciers require specialized skills.

WAYS OF TRAVELING

When traveling over snow, your main aim is to get to your destination as safely as possible, without expending too much energy or losing too much body heat. Methods range from improvised snowshoes to motor vehicles.

USING SNOWSHOES AND SKIS

Snowshoes and skis are an effective way of traveling over snow. They work by spreading your body weight over a larger surface area, which enables you to walk on the surface of the snow rather than sink into it. Always set off cold, as you'll warm up quickly, and add or remove layers as required.



Ski mask protects your eyes from glare

Wear a backpack to keep both arms free

Wear breathable clothing so you don't overheat

The shoe's ability to pivot reduces drag and improves maneuverability

Waterproof pants or gaiters keep your legs dry

Snowshoes stop you from sinking into the snow

Ski poles can be used to test the snow ahead

MAKING IMPROVISED SNOWSHOES

If you don't have any pre-manufactured snowshoes—for example, in a survival situation—you can make some very simple shoes to help you negotiate the snow more effectively, using your knife, some green wood, and cordage. They may take time to build, but will save time and effort in the long run.


Lash the ends together securely
Cross-piece for ball of foot

① Cut five lengths of green wood. They should be as thick as your thumb and the same length as the distance from your foot to your armpit. Cut three shorter lengths for the cross-pieces.

- Lash the ends of the five longer pieces together securely using cordage.
- Calculate where the ball of your foot will be positioned on the shoe and lash a cross-piece across the five lengths. Ensure the shoe will balance.


Additional cross-piece for your heel
Front lashing
Back lashing

② Lash the five loose lengths of wood together at the back of the shoe. It's important to make this lashing as secure as possible.

- Fix the second cross-piece roughly 2 in (5 cm) behind the first.
- Lash the third cross-piece where your heel will rest.
- Repeat steps 1 and 2 to make a second shoe before progressing to step 3.


Attach your foot so your heel can lift off the shoe slightly

③ Place your foot on top of the snow shoe, ensuring that the ball of your foot sits directly over the front cross-piece and that your heel is positioned on the back cross-piece.

- Tie your boot to the snow shoe using whatever cordage you have, but ensure the heel is allowed to remain free to pivot. Repeat for the other foot.

ALTERNATIVE METHODS

These alternative methods will also spread your weight on the snow. If you have no gaiters, tie plastic bags around the bottom of your legs to keep them dry.

USING BRANCHES

Ideal for short distances, a simple way to get you out of deep snow and to a road or track is to attach branches to your feet using cordage. Select a tree, such as pine, that has strong, close branches.


Use cordage to tie the front of your boot to the bough
Ensure the back of your foot can lift slightly as you walk

USING SAPLINGS

You will need branches that have some flexibility. Gently bend the longest branch into a teardrop shape and lash the two ends together. Heating the saplings over a fire will make them easier to bend.


Add cross-pieces and twigs or cordage to create the base.
Cross-pieces strengthen the shoe

MAKING A SLED

If you find yourself in a survival situation with heavy equipment to carry over snow, making a simple sled or "pulk" (see panel, right) will help you transport it more efficiently. You could also build one to transport an injured person or small child. You can make your sled as large or as small as you need, providing you follow these basic principles.

TOOLS AND MATERIALS

- Survival saw or pocket chainsaw
- Knife
- Cordage
- Forked branch (for bulk of sled)
- Two branches (for bracing pieces)
- Sticks (for cross-pieces)

1 Using a short saw or penknife, cut a forked branch to form the base of the sled.

- Tie the two ends of the fork to the main branch with cord. This creates tension and forces the branches to curve and act as runners.

2 Lash an additional branch to one of the runners to create a bracing piece.

- Repeat on the other side.
- The bracing pieces strengthen the branches and prevent any cord from touching the ground—if it does, it will wear out quickly and disintegrate once the sled is on the move.



Attach the cord to the main branch using a slip knot (see p. 142)

Attach the cord to the end of the fork using a taut line hitch (see p. 145)

Lash the bracing piece to the main branch

Adding bracing pieces creates a support for the carrying platform

ANIMAL POWER

Huskies, or sled dogs, are ideal for transporting people and equipment across winter terrain. Because of their thick coat they can endure very low temperatures, and their large, furred feet allow them to move quickly over snow. Huskies work well as a team and can pull heavy loads easily and efficiently.

TRAVELING WITH DOGS

Although huskies are easy to care for and relatively simple to handle, you should not undertake an expedition with dogs unless you are traveling with an expert or have first undergone extensive training. The same goes for all expeditions in snowy terrain.



Ensure the sled is well balanced and not overloaded

Tie luggage securely to the frame

HUMAN POWER

Pulling your equipment behind you using a pulk is an extremely efficient way of moving over snow. Pulks are small, low-slung toboggans, typically made from lightweight plastic, and come in many different sizes.

TRAVELING WITH A PULK

Although pulks are the most efficient method of carrying heavy loads over snow using human power, they can be hard work, especially in softer snow. Wear breathable clothing to allow excess body heat to escape. Know how to release your harness quickly in an emergency. If you are in a group, one person can be harnessed to the rear of the pulk to act as a brakeman when going downhill.


Attach the pulk to your body using a harness
A pulk can be used to carry equipment or a person

WARNING!
Take care when traveling down slopes, as the pulk can easily pick up speed and become difficult to control if you have no brakeman.


Cross piece
Curved branch acts as a runner
Lashing

3 Lay sticks across both bracing pieces and lash them together. These cross-pieces strengthen the structure.

- You can use as many sticks as you can find, but three or four should suffice.
- These cross-pieces will also form the main carrying platform of your sled.


Tie the handle securely so it can take the strain
Tie luggage tightly to the sled

4 Make a handle for the sled using a small branch. The branch should be as smooth as possible to make pulling the sled more comfortable.

- Attach the handle to the front of the sled using a long piece of cord.


Linking the dogs together helps them to power forward in unison
Harnesses allow the dogs to pull comfortably

MOTOR POWER

Snowmobiles are practical and quick, and have revolutionized arctic travel. They are easier to handle than huskies, and can reach relatively high speeds. However, although you can cover great distances in short periods of time, if anything goes wrong you may be far from help. Always carry survival equipment when you travel.

BEFORE YOU GO

Prior to a snowmobile trip, regardless of distance, it is vital to check your vehicle maintenance and ensure that you have sufficient fuel for the trip. Plan your route carefully and inform someone of your plans so that they can raise the alarm if you don't reach your destination when planned. Dress warmly, wear goggles or a ski mask to reduce glare, and drive safely.

USING PACK ANIMALS

PACK ANIMALS CAN BE USED to transport heavy loads when hiking over wilderness terrain. Ideally suited to carrying substantial loads, they can cover great distances in areas where vehicles would struggle. When you are organized, and know how to care for the animals, traveling with pack animals can be very rewarding.

PACKING TIPS

- Know the capabilities of your animal, and what weight they can safely carry over the necessary distance.
- Before loading the animal, groom it well and check for sores or ticks.
- Place heavier items at the bottom of your panniers and lighter items at the top.

LOADING THE ANIMAL

Stand on level ground, making sure that the animal has all four legs placed firmly on the ground. Before placing the loaded panniers onto the animal, lift them to ensure they are well balanced. Rearrange if one is lighter. You may need to hobble or blindfold the animal to keep it still while loading.

ANIMAL WELFARE

Remember to transport food, water, and supplies for the animal as well as for yourself. Their welfare is paramount, so treat them well.


Fit a blanket for the animal's comfort
A headcollar gives you control over the animal
Place lighter items, and items you may need to access quickly, at the top
Blindfolding while loading can calm the animal
Ensure straps are securely fastened
Any sharp objects in the bag should be cushioned from the animal
Place heavy items at the bottom of the bag

PACK TRAINS

Roping animals together on the trail is standard practice when traveling with more than one animal. When tying them together, ensure the ropes are long enough to allow the animals to walk comfortably, and short enough to prevent tripping.

THE PEOPLE

Appoint a driver to lead the group and take control of navigation. You will need sufficient people to control and care for the animals.


Driver leads the trail
Ropes need to be short enough to prevent tripping
Divide the loads equally

USING PACK ANIMALS TO SURVIVE

In an emergency situation, your priorities change significantly when using pack animals. Unpack the panniers and remove any heavy items not essential for survival. If necessary, you can climb on and ride to safety or, in a worst-case scenario, your animal can be used for food.

CARRYING INJURED PEOPLE

If a member of your group is injured, build a makeshift stretcher (see pp. 278–79) and use the animal to drag him or her to safety.


Strap the stretcher securely to the animal
Try to make the patient as comfortable as possible

WARNING!
Do not attempt to use pack animals without expert help or extensive training. The animals require a lot of care, and you will need to organize your days meticulously.

CHOOSING YOUR ANIMAL

The availability of pack animals depends on the region you are traveling in. Within any region, your choice of animal should take into account the load you are expecting them to carry, the distance you require them to travel, and the terrain you plan to cross. However, remember that individual animals' abilities can vary depending on their age and size.

ANIMAL	REGION	AVERAGE LOAD	ADVANTAGES	DISADVANTAGES
Horse	Worldwide	▪ 175–240 lb (80–110 kg) ▪ 20 percent of body weight	▪ Easy to train, with a good temperament ▪ Strong ▪ Can tolerate heat ▪ Can manage steep terrain	▪ Require grooming ▪ Can stray from camp if not securely tethered
Mule	Eurasia, Americas	▪ 120–180 lb (55–80 kg) ▪ 20 percent of body weight	▪ Will stick by a mare closely—this can be used to keep them moving and to keep them within the camp at night ▪ Very hardy and can manage steep terrain	▪ Young mules can be easily startled, so good training is essential ▪ Stubborn
Husky	Arctic	▪ 85lb (40kg) ▪ 7 dogs can pull 600lb (270 kg)	▪ Hardy—can cope well with snow and cold conditions ▪ Can travel fast	▪ Need a lot of fresh meat, which must be carried ▪ Prone to fight among themselves
Camel	Central Asia, North Africa, Australia	▪ 198–308 lb (90–140 kg) ▪ 30 percent of body weight	▪ Versatile on different terrains ▪ Can drink up to a quarter of its body weight and then go without water for several days	▪ Strong-willed and difficult to control ▪ Violent—can spit and bite
Llama	Andes	▪ 77–123 lb (35–55 kg) ▪ 25–30 percent of body weight	▪ Minimal environmental impact ▪ Travels well at high altitudes on difficult and steep terrain	▪ Makes horses and mules nervous ▪ Can be difficult to control if poorly trained
Elephant (Indian)	South Asia	▪ 1,650–2,750 lb (750–1,250 kg) ▪ 25 percent of body weight	▪ Can carry very heavy loads ▪ Can manage steep terrain	▪ Slow-moving ▪ Requires large amounts of food and water ▪ Takes time to train
Ox	Eurasia, Americas	▪ 300–450 lb (135–205 kg) ▪ 30 percent of body weight	▪ Hardworking ▪ Very strong ▪ Surefooted and can manage steep terrain	▪ Slow-moving ▪ Stubborn

FOUR-WHEEL DRIVING

A FOUR-WHEEL-DRIVE (4WD) vehicle can cover large areas of difficult terrain that would be inaccessible in a 2WD vehicle. With an experienced driver, most 4WD vehicles can tackle deep mud, water, snow, ice, and sand.

CHOOSING YOUR VEHICLE

When choosing your vehicle it's important to consider what you'll be using it for. Large vehicles have more internal space than smaller ones, but may find it harder to negotiate very rough ground without getting stuck. Similarly, very powerful vehicles can cross almost any terrain but use a lot of fuel, so may not be a viable option for long-term expeditions.

EXPEDITION CHECKLIST

- Check your map and inform others of your route and intended timeframe.
- Ensure the vehicle is fit for the journey, with all necessary spares. Check the fuel, oil, water, brakes, and hydraulic fluids, and check that there are no leaks.
- Inspect the tire treads, wheel nuts, lights, and steering arms.
- Always carry spare water, wheel(s), and fuel, as well as survival equipment, sand ladders, a 12v heavy-duty tire inflator, winching strap, and first aid kit.


Roof rack with high sides is advisable

Use a winching mechanism if the vehicle gets stuck

Load must be evenly distributed and tied down securely

Always carry a spare wheel

A high axle ensures good ground clearance

GENERAL DRIVING TECHNIQUES

Four-wheel-drive vehicles enable you to manually switch between two-wheel-drive, for driving on roads, and four-wheel-drive, for low-traction conditions, such as on soft ground. The difference is the number of wheels powered by the engine at any one time.

CHOOSING A ROUTE

When unsure about the conditions immediately ahead, walk the route first, checking for potential problems and obstacles. Where necessary, mark the route you have walked and follow these markers when you drive. Ask yourself whether you really need to go that way and, if so, which route is best to avoid getting stuck. And, if you do get stuck, what are your options for self-recovery or escape?

WHEN TO ENGAGE 4WD

Engaging 4WD uses up a lot of fuel and should not be used on hard roads because of the risk of damaging tires and gears. Always choose the four-wheel-drive option on difficult terrain. It allows you to travel in a very low gear and gives the vehicle a far superior traction. Just before starting to cross the rough ground, stop the vehicle and engage the four-wheel-drive.

WARNING!

Don't hook your thumbs around the steering wheel when driving over rough terrain. Hitting a rut can jerk the wheel and break them.

DRIVING AS A TEAM

Driving off-road over rough terrain is both mentally and physically tiring. Take regular breaks and share the driving if in a group. You should always have at least two people in the vehicle:

- A driver—who takes responsibility for powering and steering the vehicle.
- A spotter—who takes responsibility for navigation and helps the driver pick a good route across the terrain. This may involve getting out of the vehicle and guiding the driver across a difficult section of ground.

DRIVING OVER DIFFICULT TERRAIN

A 4WD vehicle handles difficult terrain well because all four wheels can be powered by the engine at any one time (gas engines are generally more powerful, but diesel engines last longer and work well at low speeds). Using a few simple techniques, you will find that you are able to drive over terrain—and to places—that would otherwise be inaccessible. Always remember that the principle behind 4WD is to reduce the chances of you getting stuck—not to allow you to go further until you do get stuck.

MAXIMUM TRACTION

Your vehicle's traction on soft surfaces can be improved by lowering your tire pressure slightly. As a guide, place a brick ½in (1 cm) away from the side of a rear tire on flat ground, deflate the tire until it touches the brick, measure this pressure, and apply to all four tires. Make sure you can reinflate them.

DRIVING ON SAND

In soft sand the tires tend to move the sand from the front of the tire to the rear of the tire. If forward movement is halted for even a few seconds the wheel can dig itself into a hole. To prevent this, continually steer from side to side, so that the tire steers out of its own ruts. Avoid rapid changes in speed.


Apply plenty of engine power
Lower your tire pressure slightly

MUDDY TRACKS

Driving in mud requires concentration and the ability to adapt your driving to suit the conditions. In deep mud, use wide tires or lower the tire pressure slightly; however, if there is a hard surface below the mud this will make things worse. Steering outside existing track ruts is most likely to ensure the best traction.


Deep tread helps the vehicle to grip the track

DRIVING ON SNOW AND ICE

Snow and ice require very smooth driving methods. Apply gradual pressure to the accelerator and brakes to avoid wheel spin, use low gears, especially when traveling downhill, and avoid changing gears unnecessarily. Using snow chains will increase traction, and you should practice fitting them before you need them.


Snow chains give tires additional traction

CROSSING WATER

Always walk your route before driving across water. If the water seems too deep or the current too fast, don't attempt the crossing. It's important to drive at the correct speed—too fast will send water everywhere, but driving too slowly may flood the engine bay.


Fit drain plugs if applicable
The water level should not rise above the top of your wheels

RECOVERY FROM SOFT GROUND

Although using the correct techniques will certainly improve your chances of crossing soft ground successfully, it's important to know what to do if you do get stuck. Ideally you should never set out on a driving expedition with fewer than two vehicles. A second vehicle can be used for winching, dealing with breakdowns, or driving for help.

EQUIPMENT LIST

- Winching mechanism and strap
- Cable or tow rope
- Spare tire (inflated)
- Shovel and saw
- Sleeping bag or blanket
- Branches or stakes
- Sand ladders or mats

BASIC RECOVERY TECHNIQUES

When you get stuck, it's tempting to keep trying to aggressively free your vehicle. However, churning up what solid ground is left—and digging yourself into deeper ruts—will only make things more difficult in the long run. Stop, evaluate your options (reversing or pushing, digging, using branches, and winching), and calmly decide how best to achieve your aim. Don't act in haste—an ill-thought-out plan could leave you in more trouble than you were in originally.

REVERSING OR PUSHING

If you can't free the vehicle using four-wheel drive, try alternating between reversing and driving forward in first gear.

- If this has no effect, ask the passengers to get out and push while you drive forward.
- If you are making the situation worse, stop immediately and try an alternative solution.



Push as hard as you can

Try not to make the holes any deeper

Dig the exhaust and chassis free if they are also stuck



Dig a slope in front of all four wheels

DIGGING

If reversing and pushing don't work, the next step toward freeing your vehicle is to dig down in front of the wheels in an attempt to create a slope that you can then drive up.

- Dig out the sand in front of each tire to create an upward slope
- Drive very gently up the slope. Avoid revving the engine as this can cause the wheels to spin and lose their grip on the ground.

USING BRANCHES

If the vehicle still won't move, place branches, wooden planks, sand ladders, or blankets—in fact, anything that will increase your traction—in front of the wheels. The idea is to give the tires something to grip, and it should get you moving fairly quickly.

- Without revving the engine too much, gently ease the vehicle forward onto the branches or other material.
- Maintain a slow, steady speed and continue until you are back on firmer ground.
- Once clear, remember to stop and pick up your equipment, and remove any obstacles from the track.



Place branches in front of the wheels

WINCHING

If none of the basic techniques work, and your vehicle is still stuck, it's time to consider winching. Use a cable attached to an electric-powered winching mechanism to pull the vehicle out of the hole via a strong anchor point. You can winch to another vehicle if you're traveling in convoy, although you do run the risk of both vehicles getting stuck. When winching, take time to assess your options—using a natural anchor point is the easiest method and should be your first approach.

NATURAL ANCHOR POINTS

Trees, rocks, roots, or deadfalls can all be used as anchor points. When using a tree, always place the strap or cable near the ground, and use a winch strap where possible to avoid damaging the tree. If the tree looks as if it may not be able to provide the required support, tie the tree to others in the vicinity. If you intend to use rocks, ensure they are large enough and firmly embedded in the ground.


Place a blanket over the cable to help reduce whiplash if the cable breaks
Use a log or rock to provide an angle for the winch

BURIED ANCHOR POINTS

If there are no natural anchor points, you can construct an improvised anchor by burying objects such as logs or a spare wheel. Dig a hole in the ground that's at least 3 ft (1 m) deep, attach your winch cable to your improvised anchor, then bury the anchor in the hole. Refill the hole to secure it. If you're using a tire, use the tire lever behind your spare wheel as an attachment point for the cable.


Refilling the hole with soil further secures the anchor
Dig a hole or, to save energy, use a natural hollow

WINCHING TO A STAKE

A series of long stakes in the ground can also provide an improvised anchor point. You will need a long, sturdy main stake—to which the winch cable is attached—and a series of supporting stakes, lashed together for additional strength. Push the stakes securely into the ground at a slight angle. Be careful not to stand near the stakes when winching, in case they come loose.


Attach the cable fairly low down the stake
Main stake
Lashing
Supporting stakes

WARNING!

When winching, don't stand within range of the cable in case it snaps under the strain. A breaking cable can cut a tree—or a person—in half. Place a blanket or sleeping bag over it to absorb some of the shock and reduce whiplash.

EMERGENCY ACTION

Knowing what to do in certain emergency situations will help you stay calm if the worst happens.

FRONT SKIDS

The term "skid" covers any kind of slide in which the wheels fail to grip the road. In a front skid—also called an "understeer"—the front wheels fail to turn when you steer so the vehicle continues to travel forward.

- Steer in the direction of the skid but be careful not to oversteer. If you're on ice and skidding straight, step on the clutch or shift to neutral.
- Once you have gained control, correct your course and continue driving. Consult your driver's manual if you have anti-lock brakes.

REAR SKIDS

In a rear skid, the back wheels lose control and the vehicle rotates more than usual and can spin.

- Steer in the direction of the skid but face toward where you want to travel.
- Once facing in the right direction, bring the steering wheel back to the center and continue to steer, regardless of what the rear is doing, until you have gained total control.

BRAKE FAILURE

Before setting out on a drive, always check to see whether there is brake fluid leaking from the vehicle. If so, don't travel. If the brakes fail when on the move, do the following:

- Without turning off the engine, shift down the gears to reduce speed while maintaining control.
- Once the vehicle reaches a speed of less than 25 mph (40 kph) apply the handbrake, keeping a firm grip on the steering wheel.

ACCELERATOR MALFUNCTION

If the accelerator sticks and your engine will not slow down, you can decelerate by putting the vehicle into neutral and applying the brakes.

- If it's safe to do so, switch off the engine, but you'll lose functions like power steering and lights.
- Steer safely to a stop. If possible, avoid using the handbrake as this may cause a skid—although it may be necessary if you need to avoid a collision.

KAYAKING AND CANOEING

TRAVELING IN A KAYAK OR CANOE is a good way of negotiating river systems and open water. With your equipment safely stowed in your boat, expeditions can range from short day trips to year-long adventures.


Double-bladed paddle increases stroke rate
Rudder aids control
Lifejacket provides flotation
Spray deck keeps you dry and stops the kayak filling with water
Water-tight hatch ensures equipment is kept dry
Closed deck conceals space for your legs and rudder pedals
Handling toggle allows you to drag the kayak easily

KAYAKING

Kayaks are an extremely efficient method of water transport, especially on open sea, rivers, and lakes. Their narrow design and light frame make them easy to maneuver.

CAPSIZING IN A KAYAK

Capsizing is an almost inevitable part of kayaking in rough water. The "wet exit"—slipping out of the kayak completely while still holding on to it—is sometimes the only option, but wherever possible use an eskimo roll instead.

ESKIMO ROLL

Mastering the eskimo roll enables you to avoid getting your legs wet and having to climb back in your kayak. With practice, it should become one fluid movement.



① From the upside-down position, twist your body to the side of the kayak.

- Gripping your paddle, firmly push your arms out of the water, then rest them on the side of the kayak.



② With your head near the surface, sweep your body and paddle away from the side of the kayak.

- At the same time, flick your hip away to start the rotation of the kayak.



③ Continue the hip flick until the kayak returns to an upright position in the water.

- Straighten your back so you are sitting upright again, and continue to paddle your course.

WARNING!

- Always wear a lifejacket. Empty water bottles in your pockets can be used as makeshift flotation devices in an emergency.
- In a survival situation, never leave your kayak or canoe unless it is life-threatening not to do so. A kayak is highly visible, especially from the air, and is far more likely to be spotted first by rescuers.

BASIC PADDLING SKILLS

Kayak paddles have two blades that sweep alternately through the water, propelling the kayak forward. To steer, paddle on the opposite side to the direction in which you want to go. Some kayaks have a foot-operated rudder.

CATCH

Place your lead blade firmly in the water so that it enters near to your feet.


Lead blade enters the water near your feet

BRACE

Rotate your torso and lead blade in preparation for the propulsive stroke.


The power comes from your torso

STROKE

Sweep your lead blade firmly through the water to propel the kayak forward.


Keep your grip loose on the following arm

TRANSITION

As the blade exits the water, repeat the catch on the other side and continue paddling.


The transition should be as smooth as possible

CANOEING

As with kayaks, canoes can hold one or two people with equipment, and are powered by the body from a seated position. They are generally wider than kayaks, however, and their decks are open. Canoe paddles have one blade as opposed to two.



Tie your gear securely to the canoe

Unlike kayaks, canoes usually have raised seats

TANDEM CANOEING

In a tandem canoe, one person should sit at the front and one at the back. Each person paddles on either side—swap sides regularly to avoid muscle fatigue and strain. The person at the back generally controls the steering, using his or her paddle like a rudder.

CAPSIZING IN A CANOE

Because canoes are open and fill with water easily when you capsize, your greatest challenge is emptying this water out when the canoe is righted. If traveling alone, always carry a pump, or head for shallower water so you can lift the canoe and tip the water out.

CANOE-OVER-CANOE RESCUE

If you are traveling with another canoe and are far from shallow water, the best option is the canoe-over-canoe rescue. The capsized canoe is rotated upside-down and pushed onto the rescue vessel, which empties the water out. The people on the rescue craft then rotate the canoe back to an upright position and return it to the water.



One person in the water supports the rescue canoe

Turn the canoe upside down to empty the water out

One person in the water pushes the capsized canoe over the rescue canoe

KAYAKING AND CANOEING TIPS

- Research your route and weather conditions thoroughly.
- Don't overload the boat, and ensure it's well balanced.
- Carry a high-volume pump so you can rescue yourself when alone.
- If watertight bulkheads are not fitted on your kayak, use airbags to add buoyancy and reduce the amount of water that can enter a compartment.
- Use waterproof dry bags to keep your kit dry.
- Clip valuables onto the boat or yourself. If they don't float, attach a float to them so they won't sink if they fall in the water.
- Carry waterproof material and bungee cord to repair blown hatches.
- Never enter a cave alone, or without head protection.
- Fit a leash to your paddle and attach it to the craft. If you then have to perform a rescue you can throw it in the water and keep both arms free.
- Chewing gum is great for the short-term repair of small holes in the craft, as is black masking tape and plumber's repair tape.

BASIC PADDLING SKILLS

When canoeing solo, use a "switch" style of paddling to ensure your canoe travels in a straight line—if the canoe starts to veer off course, switch sides.

CATCH

Sit in the middle of the canoe, ensuring that it's well balanced. Reach forward and thrust the blade into the water.



Paddle enters the water at the front of the canoe

DOWN STROKE

Drive the paddle swiftly and firmly down into the water so that it assumes a vertical position.



Use strong arm motions

PULL STROKE

Firmly pull the paddle blade backward through the water. This will propel the canoe forward.



Paddle generates forward momentum

REPEAT STROKE

Lift the blade out of the water toward the rear of the canoe and return to the starting position to repeat the stroke.



Paddle leaves the water at the rear

BUILDING A RAFT

IF VENTURING INTO the wilderness, it is useful to know how to build an improvised raft or flotation aid. You may find that a major water obstacle lies between you and rescue, or you may be in an area in which dense undergrowth makes cross-country travel difficult but river travel relatively easy. However, in a survival situation you are unlikely to have a lifejacket, so assess the risks carefully.

WARNING!
Apart from the brushwood raft (below), most improvised rafts will float half-submerged, so you'll be constantly sitting or kneeling in water. This could lead to hypothermia in certain conditions, so build an additional raised platform if necessary.

TOOLS AND MATERIALS

- Knife or small saw
- Poncho, shelter sheet, or tarpaulin
- Long sticks, brushwood, and thatch
- Cordage

1 Construct your raft near a suitable launching place.

- Lay your poncho on the ground to determine the size of the finished raft. Make sure there's enough material to come up the sides and gather on top.

2 Peg out sticks to form an oval shape, the size and shape of your intended raft.

- Interlace brushwood and thatch tightly through the sticks to form the sides of the raft. The tighter you weave the brushwood, the stronger the body of the raft will be, and the better it will float. The height of the brushwood will also determine how high the raft sits in the water.

3 Form a sitting platform by pushing a selection of long poles or sticks through the sides of woven brushwood. Weave the sticks under and over each other as much as you can to create a stable structure.

- Using your knife or a small saw, trim the sticks to size so that they don't protrude from the sides.
- Remove the pegs from around the brushwood.

MAKING A BRUSHWOOD RAFT

If you have a poncho, shelter sheet, or tarpaulin, you can construct a brushwood raft. This is a one-man raft, but if built correctly will keep you completely out of the water. Build it as close to the water as possible so you don't have to carry it far.


Peg out the shape of the raft
Weave the brushwood tightly to strengthen the body of the raft


Interweave the sticks to create a sitting platform
Trim the sticks so they sit flush with the outside edge of the brushwood

MAKING A PADDLE

In most cases, you can use the current of the river for momentum rather than having to paddle, and your walking staff to maneuver the raft. However, where there is no current you will have to provide the propulsion yourself, and will need to improvise some form of paddle.

1 Find a suitable length of green wood to form the handle. This should be as wide as possible but still comfortable to grip.

- In the end of the wood, make a split long enough to form the paddle face.
- Collect smaller branches and insert one of them into the split. Lash into place.



The length of the split determines the size of the paddle face

Lash above the split to stop it splitting further

The first small stick forms the top of the paddle

2 Continue to force smaller branches into the split, lashing each one as you progress until you have a sufficient paddle area.

- Securely lash the two open splits of the handle together.
- To make the paddle more rigid, lash the ends together.



Trim the edges with your survival saw to make them even

Lash every small branch together

4 Slide your poncho underneath the raft to form a waterproof seal.

- Push the poncho hood through to the inside and tie its neck securely to ensure it's completely water tight.
- Pull the poncho up the sides of the raft and lash securely across the top.

5 Fill the space underneath the sitting platform with natural materials, such as additional brushwood, grass, or moss. You could also use any item that would aid buoyancy—such as empty plastic bottles or waterproof bags filled with air and tied off.

- Drag or push the raft into the water, checking to see whether it floats in shallower water before loading your equipment and climbing aboard.



Add extra foliage to increase buoyancy and stability of raft

ALTERNATIVE RAFTS

Use whatever materials are available to you to make your raft. Look out for logs, bamboo, and discarded oil drums, as they are naturally buoyant materials that can be used to make an effective raft.

LOG RAFT

To make a log raft, use dry wood—ideally standing deadwood—as this will float higher in the water. Cut notches in the logs to allow the cross-pieces to sit snugly.



Cross-pieces tension the logs

Lash the cross-pieces together

Use logs that are roughly the same diameter

BAMBOO RAFT

Bamboo is made up of hollow compartmentalized sections, which means it is ideal for raft-making. Bamboo rafts are much lighter than log rafts.



Use cross-pieces, as with the log raft

Hollow sections aid buoyancy

DRUM RAFT

If oil drums are available, they make ideal rafts. Always take care when handling chemical drums, as they may once have contained toxins.



Tie the drums securely to a wooden platform

Ensure that any openings (missing filler caps, for example) sit above the water level

SWIMMING

WHEN THE WATER IS TOO DEEP to wade and you don't have the materials to build a raft, you may need to swim to negotiate a water obstacle. Before you get into the water, plan how you will get warm and dry when you get out. Making a float will help to keep clothing and equipment dry.

WARNING!
As with any survival activity involving water, try to avoid getting wet—find a way around the obstacle if possible, or find shallower water to wade across. The cold water increases your risk of hypothermia so ensure you have the necessary equipment for building a fire. Never enter water where there are likely to be dangers such as crocodiles or hippos.

SURVIVAL SWIMMING

Unless you need to cross rocky ground to enter the water, remove your boots and most of your clothing to reduce drag and keep them dry. Place them either in a waterproof survival bag or in an improvised poncho float (see opposite) and float them across.

SWIMMING ACROSS RIVERS

Choose a safe place to cross (see p. 88), and plan where you will exit the water.

- Take the current into account as you are likely to drift downstream slightly.
- Lower yourself in gently—never jump or dive into the water.
- If the water is cold, gently immerse yourself until your body has recovered from the initial shock.

THE CROSSING

Choosing a stroke you feel comfortable with (and that will expend the least energy), swim across your route with your float in one arm.


Tie the neck of the bag tightly to keep water out

Kick your legs to push yourself across the river

Use one arm to propel yourself through the water

A waterproof survival bag will keep backpacks dry and aid buoyancy

SWIMMING DOWN RIVERS

Avoid swimming up or down rivers—walking the route instead is far safer. However, if you accidentally fall in and find yourself traveling downstream in fast-moving water, there are ways of protecting yourself until you reach safety.

DEFENSIVE SWIMMING

The aim of defensive swimming is to adopt a position that keeps you as safe as possible and prevents your feet from becoming ensnared in rocks, which, in a strong current, could push you under the water. Assume the defensive swimming position until you reach shallower water, and can stand up and climb onto the bank.



In this position your feet avoid the rocks

In very fast-moving water, place your hands behind your head

SWIMMING STROKES

It's important to know what the different swimming strokes are, although you're unlikely to stick to them strictly in a survival situation. If you're a confident swimmer, always choose the stroke that will use the least amount of energy, such as breaststroke. If you're less experienced you should avoid getting in the water unless in a life-or-death situation.



DOG PADDLE

An easy stroke suitable for less confident swimmers, this involves simply paddling forward with your arms and legs. When you paddle with your left arm, kick with your right leg and vice versa.



BREAST STROKE

This is perhaps the most common stroke for crossing rivers. Your arm and leg movements should be made simultaneously and smoothly. It is a good option if you're pulling a float.



FRONT CRAWL

Also known as "freestyle," front crawl uses a lot of energy so is not the best stroke for a normal survival situation. However, you can build up a lot of speed, which may sometimes be required.



BACK STROKE

If you know the water is safe, this stroke can be a good choice, as it uses little energy. However, not being able to see where you're going can be a disadvantage, especially in rocky areas.

MAKING A PONCHO FLOAT

Constructing a poncho float will keep your belongings dry and provide limited flotation as you cross the river. If you don't have a poncho, use any large piece of waterproof material.

1. Push your poncho hood to the inner side, and tightly secure its neck with the drawstrings or cordage.

- Lay the poncho on the ground with the inner side facing upward.
- Place your gear on top.



Lay the sheet on flat ground

3. Wrap carefully to make it watertight.

- At this point, if you have a second poncho, repeat from step one, placing the float face down on top of the second sheet and wrapping again.
- If available, place brushwood inside the float for added buoyancy.



Tuck the corners in neatly

2. Bring one side of the poncho up and over the equipment that is piled together in the middle.

- Repeat with the other three sides to create a rectangular parcel.
- Fold the corners, and ensure that they won't allow water to enter the float.



Fold each side of the poncho over your equipment

4. Tie ropes, bootlaces, vines, or improvised cordage around the float to secure it.

- As you enter the water, gently lower the float in with you. Pull it along as you cross the river.



Float is now waterproof

Tie the cordage tightly

3

CAMP CRAFT

CAMP ESSENTIALS

Whether you intend to remain where you are and wait for rescue, move to a safer area and await rescue there, or walk out of the survival situation yourself, you're probably going to need to select a site on which to put up a shelter. This could be for just a single night or for a longer-term stay.

A sound understanding of what constitutes a good location will allow you to address the basic principles of survival. For example, a well-selected site will help keep you safe from danger while still allowing you to deploy your location aids effectively. It should also provide you with adequate materials for building a shelter and a fire, and offer an accessible supply of water, both for drinking and for hygiene.

A well-organized site will not only give you a sense of purpose and order, but will also provide a safe environment for yourself and your equipment. Designating an area for storing equipment and tools, for example, will help prevent vital items from being lost and will reduce the likelihood of you or members of your team being injured.

In this section YOU WILL DISCOVER...

- how to **make a shower** before you **take a shower...**
- why **keeping clean** is good for both **body and soul...**
- how to work up a **lather** with **wood ash...**
- when a **thatched screen** could **protect your modesty...**
- what turns a **hard candy** into a **firestarter...**
- the **difference** between **cattails** and **fire dogs...**

A fire is an integral part of any campsite. It can be used for warmth, for purifying water, for cooking, for signaling to potential rescuers, for protection against wild animals, and for providing light when darkness falls. It also provides a sense of security. The psychological effects of being able to start a fire in a survival situation should never be underestimated; neither should the psychological effects of *not* being able to start one. Even in a survival situation, a simple camp can give a sense of normality and "home."

You can produce a spark—and therefore light a fire—by using a device such as a firesteel or a ranger's flint and steel (see p. 127).

A FIRESTEEL COMPRISES two main parts: the material that will produce the spark (usually a rod made from ferrocerium or magnesium alloy) and a sharp striker device (usually a knife blade or short piece of hacksaw blade). When the striker is drawn over the rod, a spark is produced.

To control the spark created by these two moving parts, follow the method outlined below. It will allow you to direct the spark accurately, and reduce the chance of you knocking and scattering your tinder. This can be a problem if you hold the rod next to the tinder and strike down into it—especially if you are cold, wet, and tired and your hands are shaking.

1. Place the rod in the center of the tinder. Then position your striker onto the rod. Lock the hand holding the striker into position.

2. Pull the rod up and away from the tinder, drawing it against the striker. By drawing away from the tinder you avoid the danger of disrupting or scattering it.

3. To direct the sparks, alter the angle at which you pull the rod up and away.

> "The **psychological effects** of being able to **start a fire** should not be underestimated; neither should the effects of **not being able** to start one"

ORGANIZING YOUR SITE

WHERE YOU CHOOSE to set up your shelter depends on the environment, but always take into account the four principles of survival: protection, location, water, and food. First, make sure there are no obvious dangers, and that you're able to signal for rescue. If possible, select a location close to a water source.



Pitch your camp near a source of wood for shelter and for fuel

Select a place for a latrine that's downwind of the camp and downstream from the water source (see p. 117)

Assign an open area for location aids, such as a large "V", and as a potential landing site for a rescue helicopter (see pp. 236–41)



If predators are in your area, hang unused food in a bag 10 ft (3 m) off the ground and 3 ft (1 m) away from the trunk or branches of a tree

SITE FEATURES

Once you're happy with your chosen site—and confident it doesn't hold any forseeable dangers—you can organize the area to accommodate your needs, and to make your time in camp easier and more efficient.

CAMP ADMINISTRATION

Whether you're in a group or on your own, it's important to organize your site, and quickly establish disciplines and routines to ensure camp safety and to reduce the risk of accidents. Designate specific areas—for storing equipment, firewood, cooking, and sleeping—and specific routines for when you do things (see panel, right).



When you take off your boots, prop them upside down on a stick to ensure nothing crawls inside. Never put them too close to a fire to dry

Create a safe area for cutting wood. Use a tree stump as a platform for cutting and chopping



Collect and cut the fuel you need before it gets dark and keep it dry in an upright stack

ASSESSING YOUR ENVIRONMENT

You need to protect yourself from injury, threats, and risks, so have a good look around your campsite and assess it for any potential dangers, such as animals, unstable rocks or trees, and the likelihood of flooding.

ANIMALS

Look out for signs of animals, especially near water. If possible, pitch your camp against a rock face so it can only be approached from one direction. Keep a fire going all night. If you're in a group, organize a watch system. Keep things to hand that you can make a noise with to scare off prowling predators. Don't camp close to standing water where insects, such as mosquitoes, swarm.

WIND AND FLASH FLOODS

Position the entrance to your shelter at an angle to the wind. Gullies run the risk of flash floods or avalanches; inside river bends are prone to erosion and floods; and a river might burst its banks on an outside bend during a heavy downpour.

STANDING DEADWOOD

These are dead trees that haven't yet fallen. Heavy wind, or the weight of rain or snow, can make them fall. This is the best type of wood for kindling and fire fuel (see p. 121).

DEADFALLS

These are dangerous branches that have broken off a tree, but haven't yet fallen to the ground. Some trees, such as beech, ash, and yew, drop their branches without warning.

ROCKFALLS AND ICE FALLS

If you camp next to rocks, check for cracks and fissures. Fires below them can cause rockfalls. When it's cold, ice sheets can suddenly fall from the rocks.



If heavy rain is likely, reduce the risk of flooding by digging a small run-off trench around your shelter and diverting water away downhill

Locate a nearby water source, but check the water upstream for contamination, such as dead animals

Build three signal fires (see pp. 238–39) on open ground if you can

WHERE NOT TO CAMP

- Don't set up your shelter on sloping, poorly drained ground.
- Don't pitch your camp too close to water because of the risk of flooding and the presence of insects and animals.
- Avoid camping near noisy water sources, such as waterfalls, because they mask any other sounds that could alert you to the presence of threats, such as wild animals, or even possible rescue, such as a helicopter or emergency whistles.

CAMP TIMETABLE

In most cases, when you arrive at an area in which you intend to remain for a while (known as "going static"), start planning your activities by working back from a cut-off time—usually when it gets dark.

THREE HOURS UNTIL DARK

You arrive in the area. Drink water, stow what is no longer needed (map, compass, and so on), and change from wet clothing, but keep one set of clothes dry at all times. Scout the area for the most suitable campsite.

THEN...

Start pitching your camp. Build your shelter, including bedding. Gather tinder, kindling, and fuel and make a safe firebase and reflector. Collect water and forage for food. Prepare all aids to location (for both night and day).

ONE HOUR UNTIL DARK

During twilight, finish organizing the site and see to your personal needs—wash, use the latrine, and check your equipment. If you're in a group, make sure everyone knows where the emergency equipment is and who has been designated each task (lighting the signal fire, shining the flashlight, blowing the whistle). Set up a watch system for the fire.

STAYING CLEAN

PERSONAL HYGIENE IN THE FIELD is an important element of protection. Keeping yourself clean and healthy helps to ensure that your body is working at its most efficient and reduces the risk of illness. How you feel physically also has a direct impact on how you feel psychologically. It's a state of mind: if you let your personal hygiene slip, it's just a matter of time before everything else starts to follow.

CLEAN CLOTHING

The condition of your clothing and equipment can affect your state of mind. If your clothing is dirty and unkempt, your attitude to survival will lack discipline. Try to keep your clothing clean and in good repair.

HYGIENE CHECKLIST

Personal hygiene is about keeping clean and healthy, so develop a daily routine that ensures you correctly use personal protection aids (tablets, insect repellents, sunblock), and safely handle food, water, and cooking and eating utensils. Keep your clothes clean, and attend to your bodily functions (see opposite).

HAIR

You don't need to shampoo your hair—let it make its own oils and minerals and establish a natural balance. Wash out incidental smells, such as fire smoke, with hot or cold water.

SCALP

Check your head for insects and bites every morning and night. Local knowledge will help—for example, look for ticks if you are in a wooded area populated by deer.

EYES

Wear sunglasses or a hat to protect your eyes from bright sunlight and snow glare. Rinse your eyes with water twice a day to protect against infections like conjunctivitis.

EARS

Carefully check your ears for foreign objects with a clean, wet finger, especially if you're sleeping rough on the ground.

TEETH AND GUMS

Use clean fingers to rub your teeth and gums, or make a toothpaste from baking soda, or a mouthwash from salt and water.

BODY

Every two days wash your armpits, crotch, hands, feet, and toes with running water to keep fungal infections at bay.

MAKING A SHOWER

Standing under a shower can work wonders for your spirit—it removes accumulated dirt and sweat and makes your body feel refreshed. An improvised shower is quick and easy to make from a metal or a plastic container.



1 Turn the container upside down on a flat surface.

- Punch holes in the bottom with the bradawl on your penknife or the point of your knife.



2 Make a hole about 1 in (2.5 cm) down from the rim of the container.

- Make a matching hole on the opposite side of the container.



3 Smooth out any rough edges around the two holes.

- Thread a piece of cordage more than 2 ft (60 cm) long through the two holes.



4 Pull the cord through until you have the same length—about 1 ft (30 cm)—on either side.

- Tie the two strands together with an overhand knot (see p. 143).

BODILY FUNCTIONS

In a genuine survival situation, you don't eat as much food as usual and your toilet functions—particularly with regards to solid waste—will reduce dramatically after a day or so. Nevertheless, it's important to maintain a routine, especially if you are in a group.

IN TRANSIT

If you're moving every day or so, it's not worth making a latrine, so just attend to your bodily functions as follows:

- **Urination:** choose a tree away from the water source and downwind of the camp.
- **Defecation:** dig a hole at the base of a tree, fill the hole afterward, and mark it with stones or two crossed sticks. Clean yourself (but don't use the hand you eat with) with toilet paper, leaves, or grass, then running water. Wash your hands and fingernails. Burn or bury used toilet paper.
- **Menstruation:** if you don't have tampons or sanitary napkins with you, use something cotton and washable, or even sphagnum moss. Burn or bury whatever you have used.

GOING STATIC

If you're going static by staying in one place for more than a few days, build a latrine downwind of your camp, and downhill and away from your water source. Dig a deep trench, either next to or between two trees, and make a seat from two poles. Cover the deposits with sand or soil to reduce the smell and keep flies away. When you leave, dismantle the latrine, fill the trench, and mark the area with stones or crossed sticks.



A thatched screen can be erected for privacy
Tie a pole at the back of the two trees to lean against when you use the latrine
Cover each deposit with soil or sand and fill in the hole completely when you decamp
Attach two poles either side of the trees to use as seating



Bowed sapling
Use water warmed over the fire or leave water for washing to warm in the sun.

5 Hook the shower over a bowed sapling or a low branch.

- Pour water into the container to test the flow of the shower. If the water runs too quickly, put leaves in the bottom to slow it.

LATHERING UP

Camping soap is a concentrated antibacterial liquid soap that can be used without water. Decant a little into a small container, such as an old 35mm film container, and it will last for weeks. Alternatively, you can make soap from natural materials.

MAKING SOAP

You can make natural soap from various sources that contain a substance called saponin, which —when mixed with water—has a cleaning effect.

- **Birch leaves:** Select young leaves and place them in a container (even a plastic bag will do). Add some cold water, then add some hot or boiling water (whichever your container can handle without melting). Agitate the mixture—this allows the saponin in the leaves to dissolve into a natural soap.
- **Soapwort:** Agitate soapwort roots in water until they foam up. Let the light foam settle before using it to wash yourself and your clothes.
- **Horse chestnut:** Dip horse chestnut leaves in warm or hot water then remove. Squeeze the leaves in your hand to produce saponin.
- **Wood ash:** Mix wood ash with water. Don't use this method too often, as it can dry out your skin.

MAKING FIRE

THE ABILITY TO MAKE and maintain a fire can be a significant psychological factor between determining whether you do all you can to survive or just give up. Fire gives you a sense of "being," and, like a shelter, it can transform a clearing under a tree into a "home."

A PORTABLE KIT

It's important to gather all your materials before you start—not only your tinder, kindling, and fuel, but also your means of lighting a fire. This involves a fair amount of organization, so a portable kit that keeps it all in one place is much more convenient.

FIRE PRECAUTIONS

If you intend to have a fire in front of your shelter, bear in mind some basic rules:

- Don't build the fire too close to the shelter as it may get out of control or a spark may blow into the shelter and ignite it.
- Make sure you have fully extinguished your fire before you decamp and leave the site. Pour water (if you have enough) onto the fire and the immediate surrounding area, or use damp soil, sand, or earth.

COMPONENTS OF FIRE

Three crucial components—oxygen, heat, and fuel—need to be present in order for a fire to start and be sustained. Although you don't have any control over the resulting chemical reaction, known as combustion, you can develop the skill of lighting a fire. The key is to achieve the best balance between the components. If your fire isn't going well, get back to basics and ask yourself which one of the components is working against you.

OXYGEN

Although oxygen is vital for combustion to happen, it's all too easy to prevent it from getting to the flame by smothering the fire with too much wood. If your initial fire looks as though it's dying, try fanning it with your hand or a map to create a draft that feeds oxygen to the fire.

HEAT

Heat is essential for igniting the fuel. In most cases this heat can be generated either by a spark (such as flint and steel), by a chemical reaction and friction (such as matches or potassium permanganate), or by friction alone (such as a bow drill). (See pp. 126–27 and pp. 130–33.)

FUEL

Once the fire gets going, you need to have fuel to burn (see pp. 120–21). You should start with small, dry pieces of fuel that will catch the flame and generate enough heat to then burn increasingly large pieces of fuel.

MATCHLESS FIRESET TIN

Working on the principle of "Don't make things any harder than they need be," this matchless fireset, designed for the military, contains a one-stop solution to getting a fire going—regardless of the weather conditions.

INSIDE THE TIN

The small tin, which is waterproof when taped, contains everything you need to produce a fire: a sparking device, tinder, kindling, and fuel. Hexamine from the fuel blocks is scraped onto cotton wool, then a spark from the flint and steel ignites the cotton wool long enough for the fuel blocks to light.



The tin

Use cotton wool and tampon as tinder; keep them dry in a plastic bag once the tin has been opened

Ranger flint and steel (see p. 127)

Plastic Ziploc bag

Use a quarter of one hexamine fuel block to light a fire

Electrical tape keeps tin waterproof; it can be burned as kindling

USING THE TIN

You can use the tin itself to boil water. Raise the tin 1 in (2.5 cm) off the ground with two sticks and light a quarter of a hexamine fuel block underneath. After a while, the water boils so you can have a potentially life-saving drink.



PREPARING BEFOREHAND

More than any other survival task, starting a fire needs good prior preparation. If you don't have the correct materials and in sufficient quantities, you will probably fail in your attempts to start a fire. Preparing the ground, your materials, and your equipment will usually make firelighting much easier and more likely to succeed.

KEY POINTS TO REMEMBER

- Carry some form of firelighter with you at all times.
- Practice your skills before you need them—in different conditions and using different materials. You'll soon learn what works and what doesn't.
- Collect tinder as soon as you enter the forest. If it's wet, dry it in your pockets against your warm body.
- Collect everything you need to get a fire going, then multiply it by ten. If you're in a dire situation, you may have only one or two chances of getting a fire going before you either run out of matches or tinder, or you suffer from exhaustion or hypothermia.

CHOOSING YOUR GROUND

You need to be careful when selecting the place in which you intend to start your fire. Clear the ground before building your fire. Never light a fire directly on the ground and watch that your fire doesn't spread or burn out of control.


Construct a fire reflector to make the fire more efficient (see p. 164)
Balance the middle of a long pole on a forked stick
Keep a container of water, sand, or soil for dousing the fire
Place wet tinder, kindling, and larger pieces of wood close to the fire to dry them out once the fire is established
Hang the pot from a hook
Lay a platform of green wood to protect the fire from ground moisture and limit the heat dissipating into the ground
Contain the fire with green wood or dry, non-porous rocks that won't explode when they get hot
Tape a lighter to a cord to hang around your neck

CAMP FIRE DO'S

- Make sure you have enough wood close by to fuel your fire. Carrying wood to your fire uses energy, which may be at a premium in a survival situation.
- Rake the area around the spot where you intend to start the fire and brush away leaves or anything else that may ignite and start a forest fire.
- Check the ground for tree roots. Your fire could set an exposed root alight, or even one just under the surface. Once a root starts to burn underground, the heat works its way along the root and could start a forest fire.
- If you're trying to get rescued, choose a spot for the fire where passing vehicles and aircraft can see it.

CAMP FIRE DON'TS

- Don't use your hands as a rake to clear the ground, because you may get bitten by an insect or a snake. Use your feet or a branch instead.
- Don't build a fire next to old logs or fallen trees, as they may catch fire. They may not look alight but they can smolder for several days and a heavy breeze could subsequently fan the embers and start a blaze.
- Don't build your fire under an overhanging branch, or leaves, as the heat from the fire can soon dry them out and then set them alight.
- Don't position your fire so that the wind affects the way the fire burns, or blows smoke or flames into your shelter.

THE ELEMENTS OF FIRE

THE THREE MATERIAL ELEMENTS you need to build a fire are tinder, kindling, and fuel. They must be dry and collected in sufficient quantities. A well-made feather stick effectively provides tinder, kindling, and fuel on one piece of wood—and it needs only a spark to set it alight.

EMERGENCY TINDER

Carry tinder, such as a tampon or cotton wool balls, in a 35mm film canister or a Ziploc bag in your emergency kit. For each fire, use some cotton wool and a small piece of tampon. Cotton wool balls smeared with petroleum jelly make a flame last ten times longer.

MAKING A FEATHER STICK

Between four and six well-made feather sticks provide enough combustible material to get a fire going. Keep a few already made and packed away to use in an emergency. The best feather sticks are made from standing dead wood, but just about any type of dry wood will do. If you use small, dead branches that have snapped off a tree, remove the bark first.

1 Choose the side of a stick with an even grain and no knots. Work on a hard, flat surface to stop the stick slipping.

- Lay the blade flat on the stick and run it all the way down without cutting into the wood—do this ten times. This gives you a feel for the wood and how your knife moves over it.



Hold your knife so that you can use the part of the blade closest to the handle—this gives you more control and puts less strain on your wrist

Use sticks 10 in (25 cm) long and up to 3 fingers in diameter

TINDER

The first element you use to make a fire is dry, combustible material called tinder. You may have tinder in your equipment (see pp. 122–23), or you may need to find natural or other man-made sources. The key to success is to experiment with what's around you before you actually need it. Make sure it's dry—leave it in the sun if it's damp. When you use some tinder, replace it at the earliest opportunity.

TYPES OF TINDER

Natural sources: Feather sticks (see above), shavings from the outside of a bamboo stem, bark shavings, fine wood dust, pine pitch, plant and animal down, powdered dung, and fire dog (a charred stick). Also, birch bark (silver birch bark can be lit even when it's wet), clematis, honeysuckle, cattail, dry grass, dead and dry moss, and some fungi. The best tinder for friction methods of firelighting (see pp. 130–33) is tree bark, dry grass, fungi, lichen, plant roots, fibers, and down.

Man-made sources: Cotton wool balls, tampons, char cloth, fire tin (see p. 123), lint, tissue paper, camera film, strips of rubber, and candle wick.



Loosen the fibers so they catch alight easily

Buffed tinder looks like a mouse's nest

TINDER BUNDLE

A good way to prepare your tinder to take a spark or a coal is to make it into a tinder bundle. Vigorously tease, rub, and pull the fibers with your fingers until it becomes a ball the size of a grapefruit. Push the finest, most combustible material into the interior of the ball. Try mixing up your tinder to make it more effective—for example, dry grass, birch bark, and cattail.


Angle the blade slightly toward the wood
The shaving should curl as the blade moves down
Curled shavings collect at the bottom of the stick


Keep the stick firmly on the ground to steady your action


The stick gets thinner as you make the shavings
Collect any shavings that fall from the stick

2 Now tilt the angle of the blade slightly toward the wood.

- Keeping a part at the top of the wood to use as a handle, run the blade down the wood to cut a shaving.
- Stop just before the bottom so that the shaving stays attached to the stick.

3 Turn the stick slightly and run the knife down the edge created in step 2 to create a second shaving. Turn the stick again and repeat, working around the stick.

- Try to get a rhythm going, and put your body behind the cutting action.

4 Once you have mastered the technique, continue to feather the rest of the stick.

- When you've finished you will have a thin stick with curled shavings still attached, and ready for use as kindling.

STANDING DEADWOOD

A tree that's died but hasn't fallen over has no green foliage and the bark falls off without being replaced. This is the ultimate wood for firelighting, as it can provide kindling and fuel and, when split, makes excellent feather sticks. The bottom few inches may be wet where the tree wicks up moisture from the ground.

KINDLING

Kindling is the second material element of firelighting and, when dry, is added to burning tinder. Kindling can be as thin as a match or as thick as a finger. You should be able to snap it with your hands. If it doesn't break with a crack then it's probably not completely dry. If it's damp, remove the outer bark (this retains most of the moisture) and break the kindling down into small sticks 6 in (15 cm) long.

TYPES OF KINDLING

- Soft-wood twigs are very combustible, while wood with flammable resin, such as pine, burns hot and long.
- You can use some types of tinder as kindling—for example, bark, palm leaves, pine needles, grass, ground lichens, and ferns—but you will need larger quantities for kindling than you needed for tinder.


Strip off the bark with your knife

FUEL

Initially, your fire needs constant tending, but once it can sustain itself for five minutes it's established and you can add increasingly larger fuel to create a good heart—a bed of hot coals that sustains the fire with minimum effort on your part. The fuel should be about as thick as your wrist or forearm. At first, use dry fuel split into sticks that catch alight easily. Add green (live) wood and larger logs (whole or split) later, once when the fire is established. In wet conditions, build your fire under cover to keep off the rain.

TYPES OF FUEL

- Hard woods from mainly deciduous trees (such as oak, maple, ash, beech, and birch) burn hot and long, produce good coals, and are more efficient. But they are hard to get going.
- Soft woods from conifers (such as pine, fir, and spruce) are easier to light as they can contain resin, but burn faster and produce less heat than hard woods. They also make more smoke.
- Peat is found on well-drained moorland and can be cut with a knife. However, it needs a good air supply.
- Charcoal is lightweight, smokeless, and burns hot.
- Dried animal droppings provide a good smokeless fuel.

CHAR CLOTH AND FIRE CAN

BEFORE SETTING OFF ON A TRIP, add either some char cloth or a fire can to your backpack. These excellent forms of tinder are reliable and potentially life-saving. Alternatively, you can take some mayasticks. Char cloth is very easy to make, so keep some dry in your emergency fire kit or lining the bottom of your survival kit (see pp. 60–61).

TOOLS AND MATERIALS

- A can with a tight-fitting lid, such as a small shoe-polish can
- Nail
- 100 percent cotton cloth
- Knife or scissors
- Spark or flame

MAKING CHAR CLOTH

Char cloth is cotton cloth that's been combusted in the absence of oxygen (pyrolysis). It's lightweight, takes up almost no space, and produces an ember from even a weak spark extremely well. Char cloth works only when it's completely dry, so keep it in a watertight container.


Punch a hole into the lid, if possible using a nail
Put as many pieces of cloth as you can into the can
SUR-VVLOO
Smooth out the rough edges around the hole
Smoke comes from the hole once the can starts to heat up—don't worry if flames appear, too
You don't need a big fire—in fact, the smaller the better

1 Turn the lid of a can upside-down and hammer a nail into the center.

- Experiment with the size of the hole. Usually, the smaller the hole the better.

2 Cut 100 percent cotton cloth into pieces that fit into the can without folding.

- Vary the sizes of the pieces so they don't just stack flatly on top of each other, but at the same time don't squash them in.
- Securely place the lid on the can.

3 Place the can on a fire to burn off all the oxygen inside the can, or place it on top of some good coals scraped to the side of your camp fire.

- When the smoke stops the process is complete.
- Safely remove the can from the fire.
- Don't open the can until it's cool.

MAKING A FIRE CAN

You can use a fire can to start a stubborn fire when conditions are less than perfect, or to boil water, do some basic cooking, or warm your hands on a cold day. Once lit, a fire can burns for hours with a concentrated, controllable flame that produces no smoke. When it starts to fail, you can either replenish the existing cardboard with more wax or replace the cardboard and start again.

TOOLS AND MATERIALS

- A can with a tight-fitting lid, such as a small shoe-polish tin
- Cardboard (ribbed or plain)
- Candle and a match or lighter
- Knife or scissors



The extra 1/6 in (4 mm) of cardboard will burn down slightly and act as a wick



Angle the candle so that the flame melts the wax rather than just burning into air



The can becomes hot so don't touch it

1 Cut out a long, thin piece of cardboard that's 1/6 in (4 mm) wider than the depth of your can.

- If it's ribbed, cut it across the grain.
- Roll it tightly along its length until the roll just fits inside the can.

2 Light your candle and let the melting wax drop into the can.

- Let the wax soak the cardboard and fill up the can—it's a slow process.
- Stop when the wax nears the top.
- Allow the wax to harden.

3 When the can has cooled down, hold it at an angle and light the top of the cardboard with the candle.

- The flame should be concentrated and spread across the top of the can.



Look at the colour and texture of the char cloth to see if the process has worked

Remove the char cloth from the tin and separate the pieces to let them aerate

4 Once the tin has cooled down, remove the lid and examine the charred cloth.

- The cloth should be completely black and have a semi-rigid, but softish texture. If it's fawn or brown, put it back on the fire and leave for longer.
- Cloth that's brittle and crumbles is of no use.
- Check the cloth works by striking a spark on to a piece; the spark should create a small red ember.

FIRE WADS AND MAYASTICKS

Fire wads are rolled strips of newspaper soaked in a fuel. Once dry, they make handy waterproof tinder. Mayasticks are pieces of resinous fatwood from the highlands of Mexico and Guatemala. The pieces are easy to light, even when wet, and generate a hot flame.

MAKING FIRE WADS AND MAYASTICKS

- To make fire wads, tightly roll strips of newspaper into a tube 4 in (10 cm) long and tie them with cord. Soak them in melted wax and allow to dry. Light the center with a match.
- To light a mayastick, cut a little sliver of wood with your knife and lift it from the surface of the stick. When a little resin seeps out, set it alight with a flint and steel (see p. 127).



A little sliver of wood is half-detached from the surface of the stick

Strike the flint with your knife

Mayastick

TYPES OF FIRE

ONCE YOU HAVE COLLECTED your tinder, kindling, and fuel, and made sure it's dry and ready at hand, you can set about making your fire. There are many different types of fire to choose from, depending on what you need the fire for (see below). Before you start to build your fire, make sure you have prepared the ground so that everything is safe (see pp. 118–19).

CHOOSING A FIRE

If you have a choice of fuel, as well as time to invest in building a specific type of fire, look at the choices below and determine which one is likely to suit your immediate needs.

- Your primary consideration should be the function of the fire: warmth is probably your most urgent requirement, but other uses include cooking, signaling (see pp. 238–39), drying wet clothing, and disposing of waste. You may want a particular type of fire because it lasts all night.
- Consider the availability of the components you need to build the fire—for example, the right fuel and the best ground. A rule of thumb is to estimate how much you think you'll need, then double it.

FIRE ESSENTIALS

There's plenty of advice surrounding the pros and cons of making fires, but three general tips will help:

- Never make things any harder than they need to be. Choose a fire that requires the least effort for the maximum gain.
- It is more efficient to build a small fire and sit close to it, than to build a large fire and sit far away from it.
- If all your wood appears wet, remove the bark and split the wood—the center will usually be dry.
- Once the fire is established, place damp tinder, kindling, and larger pieces of wood close to the fire to dry out. Keep watch on them so that they don't dry out to the point where they catch fire!

TYPE OF FIRE	 **TEEPEE**	 **STONE-LINED**	 **AUTOMATIC**	 **LONG LOG**
HOW	▪ Surround the tinder ball with kindling in the shape of a teepee. Arrange small, medium, and large fuel logs in a square at the foot of the teepee.	▪ Arrange large non-porous stones in a circle, place a tinder ball in the middle, with kindling around it. Add fuel logs when the fire is established.	▪ Line a hole 3 ft (1 m) deep with non-porous stones. Put tinder and kindling inside and rest large logs against the sides so they drop down as they burn.	▪ Put tinder, kindling, and fuel logs in a depression 6 ft (2 m) long. Lay two long fuel logs on top of the burning fire.
WHERE	▪ Areas with abundant fuel, because the fire requires lots of firewood	▪ Windy locations ▪ Popular areas with existing fire rings and where low-impact camping is vital	▪ Rock-free earth or sand, because it's easy to dig	▪ Forested areas, because the fire requires long logs for fuel
WHY	▪ Quick to light ▪ Wet wood can be burned because it's dried by the heat of the inner fire	▪ Stones shelter fire from wind ▪ Using an existing fire ring reduces the fire's impact on the environment	▪ Self-feeding once lit, which means you don't need to keep adding fuel	▪ Long-lasting (the fire can stay alight all night) ▪ Emits a great deal of heat
USES	▪ Warmth ▪ Cooking ▪ Signaling (if green vegetation is burned)	▪ Warmth ▪ Cooking ▪ Signaling (if green vegetation is burned)	▪ Cooking ▪ Signaling (if green vegetation is burned)	▪ Warmth (in cold weather, build a fire either side of you). ▪ Cooking (once embers have formed)

LIGHT YOUR FIRE

There are numerous ways to build a fire and get one going, and everyone has their favorite. The following example is a tried-and-trusted method that's versatile and works well in a variety of conditions.


Tinder ball
Green wood platform
Use small amounts of kindling to start with
Arrange kindling in a "teepee"
As the kindling burns it falls into the center of the teepee
Add more fuel across the two logs to form a "log-cabin" effect
Large log

① Place your tinder ball (see p. 120) on a platform composed of green wood.

- Light the tinder with your chosen method (see pp. 126–27) and let it catch.

② Gently lay kindling by the tinder ball.

- Build a kindling "teepee", as this lets the fire breathe where the heat is strongest.
- Feather sticks also make ideal kindling (see p. 120).

③ As the kindling catches fire and the flames grow, add larger pieces of kindling.

- Continue to add kindling, gradually building up to split logs (see p. 148).

④ The fire is established when you can leave it alone for five minutes without it going out.

- Then lay a large log on the wind-facing side and one on the other side.

 **SNAKE HOLE**	 **STAR-SHAPED**	 **HUNTER**	 **DAKOTA HOLE**	**TYPE OF FIRE**
▪ Create a hole in the side of a bank and a chimney up through the earth. Light a fire inside using any fuel.	▪ Build a fire from tinder, kindling, and fuel. ▪ Arrange four logs so they meet in the middle. ▪ Push logs in as they burn.	▪ Make a fire out of tinder, kindling, and any type of fuel. Place two long logs either side of the fire in a V-shape.	▪ Dig a large hole for the fire and a slightly smaller hole for the chimney, with a tunnel linking the two. Use small logs as fuel and cook at ground level.	**HOW**
▪ Windy locations ▪ Rock-free earth or sand bank	▪ Forested areas, because of the logs the fire needs	▪ Cold or windy locations	▪ Anywhere you can dig a hole, because the fire requires very little fuel once established	**WHERE**
▪ Chimney creates a draft, giving a high-temperature fire ▪ Sheltered from the elements	▪ Long-lasting ▪ Good embers for cooking	▪ Hardwood logs shelter the fire from the wind ▪ Produces a great deal of heat	▪ Concentrated heat ▪ Flames are below ground so fire is hidden	**WHY**
▪ Warmth ▪ Cooking ▪ Waste disposal	▪ Cooking—balance a pot on the logs ▪ Heating water	▪ Warmth ▪ Cooking	▪ Cooking ▪ Keeping warm ▪ Drying wet clothing	**USES**

MAKING SPARKS AND FLAMES

LIGHTING TINDER IS THE FIRST STAGE of making a fire. Matches and lighters do this instantly, but there are a number of ways to create a spark that you can then use to coax your tinder into a flame. This is relatively easy when everything is dry, but with patience and persistence it is also possible when conditions are bad.

IGNITION DEVICES

There are various ingenious methods of creating that all-important spark or flame to ignite your fire. If you don't have matches or a lighter, you'll need to use another device, such as a flint and steel. You can also improvise by using an external energy source, such as:

- Focusing the sun's heat with a magnifying glass or beverage can.
- Making sparks with a battery.
- Creating a chemical reaction using potassium permanganate.

STRIKING A MATCH

It may seem simple enough, but there's a way of striking a match—known as "commando style"—that reliably produces a flame in all kinds of conditions.


Press your middle finger on the match

① Hold the box in one hand and a match between the thumb and first two fingers of the other.

- Strike the match firmly away from you.


Point the head of the flame down

② When the match lights, immediately cup your hands to protect the flame.

- Let the flame burn a little way along the stem before using it to light the tinder.

TYPE OF DEVICE	 **MATCHES/LIGHTERS**	 **MAGNIFYING GLASS**	 **BEVERAGE CAN**	 **BATTERY**
GEAR	▪ Waterproof box of matches. ▪ Cigarette lighter taped to a piece of cord around your neck. ▪ Dry tinder	▪ Magnifying glass ▪ Dry tinder	▪ Empty beverage can ▪ Dry tinder	▪ Flashlight and its battery ▪ Wire or wire wool ▪ Dry tinder
WHAT TO DO	▪ To light a match "commando style," strike it away from you on the box and then cup it in your hands (see above).	▪ With the magnifying glass, focus bright sunlight onto some dry tinder and create a hot spot. Hold the magnifying glass steady until the tinder catches alight.	▪ Polish the bottom of the can (see Signal mirror, p. 245). ▪ Catch bright sunlight on the shiny surface and reflect it onto tinder to create a hot spot. Hold the can steady until the tinder catches alight.	▪ Lay the wire across the battery terminals to create some sparks. ▪ Remove the bulb from the flashlight and place wire wool over the terminal. Switch on the flashlight to create sparks.
COMMENTS	▪ Waterproof matches are usually just standard matches that have been coated with wax and varnish. ▪ Always have a lighter around your neck on a piece of cord.	▪ When you choose a compass, make sure it has a magnifying glass incorporated into it (for reading the details on maps). ▪ You can also use the lens in reading spectacles.	▪ You'll need to practice this technique so that you can rely on it in a survival situation.	▪ The thinner the wire the better this will work, especially with lower voltage batteries (1.5v). ▪ Use this method for a short period only, otherwise you will drain the battery.

CREATING A CHEMICAL FLAME

Potassium permanganate is an extremely useful item to have in your survival kit, because you can use the chemical not only to sterilize water and wounds, but also to create a spark to light a fire. You will need some sugar to make it work, so use some from your survival rations or crush a hard candy.

WARNING!
Potassium permanganate is a strong oxidizer that can, when mixed with certain chemicals, create an explosive mixture. It can also stain your clothes and skin.



① On a hard surface, such as a flat piece of wood or rock, crush some potassium permanganate. Have an equal amount of sugar ready.



② Mix the ingredients. With the back of your knife, push down on the mixture and drag it along the hard surface to create friction.



③ Continue to push down and drag your blade until you get a spark.
- The flame dies down quickly so have your tinder at the ready.

FIRESTEEL	FLINT AND STEEL	ONE-HANDED STRIKER	POTASSIUM PERMANGANATE	
				TYPE OF DEVICE
▪ Ferrocerium firesteel ▪ Metal striker ▪ Dry tinder	▪ Magnesium-alloy rod ▪ Steel striker (usually a short piece of hacksaw blade) ▪ Dry tinder	▪ A magnesium-alloy rod and steel device that can be operated using only one hand ▪ Dry tinder	▪ Potassium permanganate ▪ Sugar ▪ Knife ▪ Dry tinder	GEAR
▪ Hold striker next to the tinder. ▪ Place the firesteel under the striker, directly onto the tinder. ▪ Draw the firesteel back across the striker to direct the sparks onto the tinder. The firesteel moves, not the striker.	▪ Follow instructions for the firesteel (left).	▪ Place the flint rod in the tinder. ▪ Press the thumb button onto the rod and push the handle down the length of the rod. ▪ Pushing harder creates greater friction, which leads to a more intense spark.	▪ Mix potassium permanganate and sugar in equal amounts on a hard surface. ▪ Press down on the mixture with your knife and drag the blade along to create a spark (see above).	WHAT TO DO
▪ Lasts for about 12,000 strikes. ▪ Temperature reaches 3,000°C. ▪ Works in all weathers and at any altitude.	▪ There are many variations and kits; one has a magnesium block for the holder and the striker shaves slivers of magnesium into the tinder to help with ignition.	▪ Works in all weathers. ▪ Has a safety feature that prevents accidental use. ▪ Designed for fighter pilots, who may injure an arm or hand after ejecting.	▪ You can also mix a small amount of potassium permanganate with glycol or antifreeze. Quickly wrap in paper and put on the ground. Warning: stand well clear as the combustion can be sudden and dangerous.	COMMENTS

TRUE-LIFE ACCOUNT

EXTREME SURVIVAL—IN THE DESERT

USEFUL EQUIPMENT

- Personal Locator Beacon (PLB)
- Sunglasses and sunscreen
- Cotton scarf or hat
- Signal mirror and signal flares
- Map, compass, GPS
- Survival tin, bushcraft knife
- Cell/satellite phone
- Poncho/bivy sack

DESPITE A LACK OF SURVIVAL KNOWLEDGE, a party of five survived searing temperatures, dehydration, hunger, and the threat of animal attack for six days when their plane crashed in the Kalahari Desert in Botswana.

On Wednesday, March 1, 2000, Carl du Plessis and three associates—Mike and Lynette Nikolic, and Nebojea Graorac—set off on a business flight from the capital of Botswana, Gaborone, bound for Maun, a popular tourist town in the north of the country. However, the aircraft developed engine trouble during the flight and was forced to crash-land. Critically, radio contact was lost, so no distress call was emitted before the plane went down. The pilot and all four passengers on board suffered burns during the crash and subsequent fire, but two sustained even more serious injuries—Lynette Nikolic damaged her spine and left arm, and Graorac suffered a punctured lung.

"CRITICALLY, RADIO CONTACT WAS LOST, SO NO DISTRESS CALL WAS EMITTED BEFORE THE PLANE WENT DOWN"

The following morning, Du Plessis and pilot Costa Marcandonatos decided to walk the estimated four days to Maun to find help. Their plan was misguided from the start—Maun was actually around some 190 miles (300 km) to the west, and other settlements to the east were much closer. They attempted to navigate by the sun but, lacking a machete, couldn't penetrate the dense bush. They were forced to follow elephant tracks to find watering holes, meeting elephants on one occasion, and heard the roar of lions at night. By Saturday they had walked 56 miles (90 km), but their zig-zag route had taken them only 20 miles (30 km) from the crash site.

Despite their mistakes, they stumbled upon a manned hunting lodge the following day. After their initial efforts to radio the authorities had failed, a helicopter finally reached the crash site on Monday, March 6, airlifting the casualties to hospital for emergency treatment six days after the crash.

WHAT TO DO

ARE YOU IN DANGER?

NO YES

If you are in a group, try to help any others who are in danger

Get yourself out of it:
Sun/Heat—Find or improvise immediate shelter
Animals—Avoid confrontation and move away from danger
Injury—Stabilize condition and apply first aid

ASSESS YOUR SITUATION

See pages 234–35

DOES ANYONE KNOW YOU WILL BE MISSING OR WHERE YOU ARE?

NO YES

If no one knows you are missing or where you are, you will need to notify people of your plight by any means at your disposal

If you are missed, a rescue party will almost certainly be dispatched to find you

DO YOU HAVE ANY MEANS OF COMMUNICATION?

NO YES

You are faced with surviving for an indefinite period—until you are located or you find help

If you have a cell or satellite phone, let someone know your predicament. If your situation is serious enough to be worthy of emergency rescue, and you have a Personal Locator Beacon (PLB), you should consider this option

CAN YOU SURVIVE WHERE YOU ARE? *

NO YES

If you cannot survive where you are and there are no physical reasons why you should remain, you will have to move to a location that offers either a better chance of survival, rescue, or both

Address the Principles of Survival: Protection, Location, Water, Food

YOU WILL HAVE TO MOVE **

DO

- Make an informed decision on the best location to move to
- Leave clear indications of your intent (written messages or signs) if abandoning a vehicle
- Have aids to location accessible while moving and deployed when static
- Protect yourself against glare from the sun and windburn
- Seek or improvise shelter when not moving and seize all opportunities to collect fuel for a fire—deserts get cold at night
- Be on constant lookout for signs of water or civilization—such as green vegetation, converging animal/human tracks, or circling birds

DON'T

- Sit directly on the hot ground when you stop
- Travel during the hottest part of the day
- Take risks—a twisted ankle caused by running down a sand dune could be fatal
- Force the pace—travel at the speed of the slowest person in the group
- Shelter in dry river beds, because of the potential risk of flash floods

YOU SHOULD STAY **

DO

- Seek or improvise shade and work during the coolest part of the day/night. A shelter dug even 6 in (15 cm) below ground level will provide a much cooler place to rest
- Ration sweat, not your water; you require around 1¾ pints (1 liter) per hour in temps above 100°F (38°C), half of this if it's cooler
- Continually re-assess your water situation and options for augmenting your supplies
- Leave everything out overnight that could collect dew so you can drink it
- Prepare all of your aids to location for immediate use. Be constantly alert for signs of rescue

DON'T

- Leave a broken down vehicle unless absolutely necessary—it's easier to see and is what rescuers will be looking for
- Waste energy unnecessarily—be idle unless there is something that requires doing
- Ignore your fire—use anything that burns (wood, vehicle tires) to generate heat and smoke

---

* If you cannot survive where you are, but you also cannot move owing to injury or other factors, you must do everything you can to attract rescue.

** If your situation changes (for instance, you are "moving" to find help, and you find a suitable location in which you can stay and survive) consult the alternative "Do" and "Don'ts."

FIRE BY FRICTION

THIS METHOD USES PRIMITIVE EQUIPMENT, such as a bow drill, and requires knowledge, skill, practice, the correct wood, time, and effort. However, once learned it's possibly the most rewarding of all survival skills. Your first fire created from a coal produced by a fireset that you have made yourself will be a fire you will never forget. In a genuine survival situation, however, you would always start a fire with the quickest and easiest method available.

TOOLS AND MATERIALS

- Cordage such as para cord, fishing line, shoelaces, or bailing twine
- Wood
- Knife
- Bradawl (optional)

THE FOUR SKILLS

There are many ways to make fire by friction, including a hand drill, bamboo fire saw (see p. 133), and bow drill. Each has its own advantages, depending on the materials available and your practical skills. Regardless of the method, however, there are four main elements to producing fire by friction—each a skill on its own:

- Identifying and procuring the correct types of wood.
- Manufacturing the individual pieces that make the fireset.
- Using the fireset to produce a coal.
- Nurturing the coal into a flame.

MAKING A BOW DRILL

The bow drill set is one of the most efficient methods of making fire by friction. Try to find the right type of wood for each part, especially the drill and hearth board (see Testing Wood, opposite).

1 To make the bow, cut a stick to the same length as the distance between your armpit and your fingertip.

- Cut a notch (or make a hole with a bradawl) near each end.
- Tie cord with an arbor knot (see pp. 142–43) to one notch and with half hitches (see pp. 144–45) to the other. Leave only enough slack to wrap around your finger.


The notch is a tie-off point for the cord


Shape the end that fits into the hearth board to a bluntness that maximizes friction

Hold the wood firmly in one hand and carve away from you with the other

Carve the end that fits into the bearing block to a dull point to minimize friction

2 To make the drill, cut a straight piece of wood that has no knots.

- The drill needs to be about 1 in (25 mm) in diameter and about 8 in (20 cm) long.


Make a notch with the point of your knife in the middle of the block

3 Make the bearing block from a piece of hard wood about 3–4 in (7.5–10 cm) across.

- Cut it to a length of 4–5 in (12–15 cm), split it in two, and make a notch in it.
- The drill's dull point fits into the notch, while you hold the block when you are bowing (see p. 132).

TESTING WOOD

Standing deadwood is ideal for the drill and hearth board as it's dry. Soft deadwood is easier to use than hard deadwood, but if you can't tell the difference, use these tests.

THUMBNAIL TEST

Cut through the bark of a branch, exposing a patch of wood beneath. If you dent this wood easily with your thumbnail, it's a soft wood. If you can only make a small impression, then it's a hard wood.


Remove a piece of bark
Guide the blade with your thumb

1 Hold your knife at a slight angle to the wood. Push it with a thumb on top of the blade.


Try to dent the wood with your nail

2 Press your thumbnail at an angle of 90 degrees to the wood in the exposed patch.

CHAR TEST

Each type of wood produces a distinctive char and coal. Some, such as hazel and lime, make a coal easily but the fireset will wear out quickly. The char test helps you discover which woods make a good coal. Drill into a softwood hearth board until it smokes, continue for five seconds and then stop. Look at the char produced:

- If it's like a fine powder it will probably produce a coal.
- If it's coarse, or appears to disintegrate into nothing, it probably won't make a coal.

4 Make the hearth board from a flat piece of wood about 1 in (25 mm) thick. You may have to split some wood to get what you need.

- Hold your drill so that it sits about $\frac{2}{5}$ in (10 mm) from the edge of the board.
- Mark this point with your knife and notch out a small hole to help the drill get started.


Use the tip of your knife to make a hole


Put the drill's pointed end into the hole
Twist the cord once around the drill, with the cord on the side of the bow

5 Set up the bow, drill, and bearing block (see also p. 132) and bow the drill into the hole in the hearth board until the hole is as wide as the drill. Don't go all the way through.


Make the V about an eighth of the circumference of the hole

6 Cut a V to the center of the hole through the hearth board. The bottom of this V is where the char collects and the ember forms in the ember pan (see p. 132).

THE FINISHED FIRESET

The bow drill set works best when the drill and hearth board are made from the same wood, because both parts then wear down evenly. This may not always be possible, so experiment with different woods.

- Good woods to start with are sycamore, hazel, ivy, lime, willow, and sotol (not found in Europe).
- Also useful are alder, birch, cedar, pine, spruce, maple, oak, and poplar.


Make the bow from any wood, preferably a length that has a slight curve
Make the drill from the same wood as the hearth board
Slight ridges or bumps on the drill will help prevent the cord from slipping
Cut the bearing block from hard wood to stop it burning away
BOW
DRILL
BEARING BLOCK
HEARTH BOARD
Make the hearth board from wood that heats up and ignites easily

USING A BOW DRILL

Before you use a bow drill, have your dry tinder bundle, kindling, and fuel beside you. Until you become proficient at using a drill, you will use lots of energy, so beware of overheating and dehydration. Turning a coal into a fire is a skill in itself, so use every opportunity to practice making tinder bundles and lighting them with a small coal from your camp fire.

TOOLS AND MATERIALS

- Bow drill set (see pp. 130–31)
- Thin, dry piece of bark to use as an ember pan
- Buffed tinder, kindling, and fuel

GETTING INTO POSITION

Place the ember pan on a flat, dry surface and align it with the V on the hearth board. Rest one foot on the board. Loop the bow cord once around the drill, starting on the inside. Insert the drill into the hole on the hearth board, slot the block on top (with a green leaf in the notch for lubrication), and lock your wrist into your shin as support. Kneel on the other leg and bear down on the block.

1 Hold the bow horizontal to the ground and parallel to your body.

- Lean slightly forward to apply downward pressure to the drill and back to reduce it.
- Start bowing slowly, using the full length of the bow. Aim for an even, flowing rhythm.
- Breathing steadily as you bow, gradually increase speed and pressure until smoke appears. Vigorously bow with maximum effort ten more times—this usually produces a coal in the ember pan.



Keep your head as still as you can above the bow

Bear down on the block with the weight of your body

Use your arm for bowing, not to bear down on the block

If the drill slips, move your grip further along the bow to increase the tension in the string

Steady the hearth board with your foot



Keep the drill upright as you bow

As the drill turns, friction heats the wood

A pile of black ash will collect on the ember pan

2 Gently remove the drill and lift the hearth board up and away from the smoking coal in the ember pan.

- If the coal is sticking to the board, gently tap the board with your knife to loosen it.
- Carefully lift the ember pan off the ground and hold it in the air to see if the coal is glowing.
- If the coal in the ember is just smoking, and not glowing, then gently fan it with your hand until you see it glow.



Fan the coal gently to avoid blowing it away

3 Gently transfer the glowing coal into your tinder bundle.

- The coal must touch the tinder to transfer its heat, so squeeze the tinder around the coal, but don't crush it or starve it of oxygen.


Tip the coal off the ember pan and into the center of the tinder bundle


Hold the tinder bundle away from your face (turn your back to the wind if there is any)
Don't blow too hard
Air from your breath or the breeze helps with combustion
Hold the tinder bundle up, but not too close to your face

4 Gently blow into the bundle to help fan the coal and encourage it to catch.

- You can swing the bundle down and back up in between breaths to let dry air fan the coal.
- Continue as the amount of smoke increases and eventually the bundle will burst into flames.

5 Don't throw the burning bundle on the ground, just calmly place it where you intend to have your fire. Start building the fire around the bundle (see pp. 124–25).


Once the kindling is set alight, you can add some fuel
Place kindling over the top of the burning tinder bundle

BAMBOO FIRE SAW

This friction method uses a saw technique to light tinder collected from scraping the outside of the bamboo with your knife.

MAKING THE FIRE SAW

You need a bamboo section 18 in (45 cm) long. Split it lengthways into two equal pieces.

1 Sharpen the edge of the first piece with your knife and then cut a V-shaped notch in the outside middle of the second piece.

2 Hold tinder over the notch in the second piece of bamboo with another bamboo strip that's snapped but not fully broken.

- Kneel down and brace the sharpened piece of bamboo vertically between the ground and your stomach (place a pad on your stomach for comfort).
- Place the notch and tinder over the sharp edge of the first piece, and rub the second piece up and down in a rhythmic movement.


Lean over the top of the fire saw
Rub the saw up and down
Hold the second piece horizontal in both hands
Bend down on one knee
Hold the first bamboo piece vertical

3 When the friction produces lots of smoke, continue for 20 strokes more and you should have a coal.

MANUAL SKILLS

Learning skills that you can use in the wilderness is always a “work in progress.” Having taught thousands of students over several years, I am yet to conduct a course in which I didn’t learn a new skill. For example, this could be a more efficient way to erect a shelter, how to tie a new knot, or the best way to carry out a task more safely and efficiently.

In the military, we invariably teach students how to accomplish a particular task using only the most basic gear. By learning how to perform a task using the absolute basic equipment, they will be able to understand the important elements of the task and will have no choice but to get them right in order to succeed. This in turn helps students to appreciate how and why certain techniques do and don’t work, and gives them an opportunity to use their improvisational skills to modify basic techniques in order to get the most out of them. Knowing the correct method of using a knife, for example, will not only improve safety on an expedition, but will also mean that only the minimum

In this section YOU WILL DISCOVER...

- the merits of a **hank** in **your pocket**...
- how to strip a **nettle stem** and not **get stung**...
- when **to twist** and when **to roll**...
- how to tell a **working end** from a **standing end**...
- the uses of a **sheet bend** or a **Siberian hitch**...
- the **difference** between a **parang** and a **kukri**...
- how to **fell a tree** with a **thumping stick**...

amount of valuable energy is being used to complete a task. Equally, knowing how to tie a few simple knots, which can be used in the majority of survival situations, will allow you to use whatever cordage you have in the most efficient way possible.

If you find yourself in a survival situation with more than the most basic gear, life will be much easier. However, the ability to improvise what you need when you don't have it could mean the difference between continued survival and despair.

If you give someone with little understanding of knots a length of cord and ask them to complete a task, they will invariably use the whole length of cord. If, however, you teach someone two simple knots and set them the same task, they will invariably use only the necessary amount of cord.

USING THE BEST KNOT, lashing, or hitch for a particular task means that you will use cord more efficiently and, therefore, ensure that your supply will go further. In a survival situation, where you may be moving every day, you need to be able to use the same pieces of cordage day after day.

- Use knots that don't require cutting and that can be untied quickly and easily (trying to undo a knot with cold, wet hands in the dark, and when you are tired and miserable, can be an emotional experience that usually ends in frustration and several pieces of cut cordage).
- Before you set off into the wilderness, learn a few basic knots, such as the Siberian hitch and the taut-line hitch, which are great for rigging a simple poncho shelter.
- Practice these knots until you can tie—and untie—them with your eyes closed.
- If you are trekking in a cold environment, practice tying them wearing gloves.

> “The **ability** to **improvise** what you **need** when you **don't have it** can mean the **difference** between **continued survival** and **despair**”

MAN-MADE CORDAGE

A VITAL PIECE OF SURVIVAL EQUIPMENT, man-made cordage is one of those small items that has many uses: building a shelter, repairing equipment and clothing, making traps and nets, and producing fire by friction using a bow drill. Always pack plenty.

PACKING CORDAGE

Before you set off on your travels, check how much cordage you will need. Make sure you pack it in two places—in your backpack and on your person, in case you get separated from your pack. Make sure, too, that the needle you pack in your survival kit has an eye big enough for the inner strands of the cordage.

PARACORD

Parachute cord, or "paracord," is a type of cordage originally developed for the rigging lines of parachutes and then adopted as the standard utility cordage by most of the world's military forces. It is a lightweight, nylon rope composed of 32 braided strands. Each strand contains a number of smaller threads that can also be used. In most situations, paracord is a very good option because it's readily available, strong, and packs down small.

SURVIVAL TIP

Green is the ideal color for military paracord as it remains camouflaged. In a survival situation, red is best because it stands out—it's easier to find if you drop it and can be used as an aid to location. Don't pack just one very long piece of paracord (150ft/30m, for example). It's much better to cut the paracord into 30 ft (10 m) lengths and tie each of them into a coil called a hank (see opposite and below).

TEN HANKS

A hank can fit in the palm of your hand. It takes up very little room so you can easily stuff up to 10 of them into your pack and pockets, and leave them there until you need them.



Coil lengths of paracord into palm-sized hanks

USING CORDAGE

It is vital that you use your limited supply of cordage as efficiently as possible.

- Use only the minimum cordage that is absolutely necessary to accomplish each task.
- Use simple, strong knots that, if possible, can be released without cutting. This leaves the cordage intact for the next task.



Each braid of paracord is composed of several useful inner threads

When they are cut, the ends of the braids can unravel

Paracord is a kernmantle rope with an interior core (the kern) surrounded by a woven exterior sheath (mantle)

The outer sheath is designed to optimize strength, durability, and flexibility

TYING A HANK

It's best to keep your cordage in a hank—you can untie it when you need a piece and retie it to store it again. Tying a hank is straightforward and soon becomes second nature, because you'll do it again and again.


Keep your thumb vertical, like a post
The end of the cord is held in place on the palm of your hand

1 Hold out your hand (you can use either hand) with the thumb and the fingers spread.

- Lay the end of the cord on your palm, then loop the cord in a figure-eight around your thumb and little finger.


Keep stretching your thumb and little finger to keep the cord taut
The figure-eight gradually becomes more bulky

2 Continue winding the cord until you have about 8 in (20 cm) of cord left—this is the tail.



3 Take the hanked cordage off your thumb and little finger.

- Secure the hank by tying the tail around it with a release hitch knot (see p. 143).

OTHER TYPES OF CORDAGE

In a survival situation you may have to improvise and use other types of cordage, especially if you didn't bring any paracord with you or have run out. Before you start making it from natural materials (see pp. 138–41), see what else you might have that would be quicker and easier to adapt.

SHOELACES

The normal laces of shoes and boots are often strong enough to use as cord. However, the members of many military units, who are limited to the amount of equipment they can stow or carry, replace their bootlaces with paracord. They use twice as much as they need and wrap the extra length around the top of their boots before tying it. This gives them a ready supply of extra cordage that they can cut off as needed. You can easily do the same—but never sacrifice all the cordage you are using as shoelaces as you'll need to make sure you can still walk comfortably.

BELTS, CLOTHING, AND HATS

You can cut any type of belt, whatever it's made of (leather, canvas, and so on) into strips to use as cordage. You can cut clothing into strips, too. However, you don't have to destroy a shirt completely: start at the bottom hem and cut 1 in (2.5 cm) strips all the way round. You can even use your hat—a 1 in (2.5 cm) strip from the brim of a jungle hat is just over 3 ft (1 m) long. Better still, coil paracord around the crown of your hat and stitch it in place (just the front and the back).

RAIDING YOUR KIT

You may have other items in your equipment that you could use as cordage, such as guylines from tents or draw cords from clothing or sleeping bags. Dental floss, especially the waxed type, is extremely strong and can be used effectively for lashing or sewing. If you have a vehicle, you probably have a towrope; take a part of it and unravel the rope into smaller pieces of cordage.

BE A SCAVENGER

Few places are untouched by modern man. Even in remote areas you'll come across discarded items from the "civilized world"—from plastic bottles to bailing twine. In a situation where improvisation could be the difference between life and death, collect anything you could use to your advantage.

SEALING PARACORD

Paracord can be awkward to use because its ends, if left unprotected, eventually unravel. Try to seal the ends after you have cut them by holding a flame next to them until they melt. Be careful, as the melted nylon can drip and burn.

NATURAL CORDAGE

IF YOU DON'T HAVE any man-made cordage, you may be able to make a natural substitute. Use the roots and stems of plants to produce improvised rope for erecting shelters, and use sinew from the tendons of larger animals for strong whipping and sewing.

WARNING!
Take extreme care when you collect and work with plant fibers, especially removing plants such as green ferns from the ground. Bending a stem at its base and pulling it up can expose fibers that are razor-sharp. Cut the plant with a knife or wear gloves. The juice of some plants can irritate the skin, so wash your hands when you've finished.

PREPARING NETTLE FIBERS

Old stinging nettles or wood nettles with long stems have the most fibers. Wearing gloves (or with your hands covered), strip the leaves from the nettles by grasping the stem at the base and pulling your clenched fist up the full length of the stem.



1 Sit astride a log and lay a nettle stem in front of you. Roll a smooth, rounded stick backward and forward on the stem, pressing down hard.

- Continue rolling until the whole stem is crushed.


Open the flattened nettle stem to form a long strip

2 Tease open the crushed tissue along the whole length of the stem of the nettle with your thumbnail. This exposes the spongy pith within.

CHOOSING YOUR RAW MATERIALS

Many kinds of raw material can be used to make natural cordage, from bark and roots to stems and sinews. Search your immediate environment first to see what can be used—you may not have to look too far.

	BARK	ROOTS
FACTS	■ Tree trunks have layers between the bark and heartwood called the "cambium" layers, which are best for cordage.	■ Many tree roots make good cordage and lashings, but evergreen trees, such as pine, fir, spruce, and cedar, work best.
FINDING	■ The bark of trees such as willow and linden make good cordage. ■ Use other types of bark, such as clematis or honeysuckle, as they break from the tree or vine.	■ Look for new roots near the surface of the soil; these are flexible. Cut slightly thicker roots than you need, as you have to remove the bark. Remove only a few roots from each tree and repair any damage you do to the topsoil.
PREPARING	■ Strip the bark from a dead tree, then beat it to loosen the inner cambium fibers. ■ Pull off the cambium fibers in long strips. Use them as they are (clematis and honeysuckle), or braid them into stronger lengths.	■ Cut a slit along the root. Peel the bark and let the bare root dry and shrink before splitting in half or into quarters. ■ Keep the bark for tinder or kindling. You could also put it on a fire to produce smoke that keeps away flies.


Tease the fibrous layer away with your thumb
Section of broken stem

3 Bend the stem in the middle of its length. When you bend it, the inner pith will break away from the outer skin, making it easy for you to separate them.

MAKING CORDAGE FROM PLANTS

To begin with, you must have access to enough quantities of the plant. Don't start making cordage with the only plant in the area. There should also be some basic characteristics present in order for plant material to work well as cordage.

- The fibers need to be long enough. If you have to splice them together to make workable lengths, you will weaken the line.
- If you're braiding pieces together to make a stronger line, use rougher fibers, as they will bite together better. Shiny or smooth fibers tend to unravel easily.
- The fibers need to be strong. Pull on them to see how much strain they take before breaking. They also need to be pliable enough so they don't break when you bend and tie them.

4 Carefully peel the outer skin from the inner pith.

- With the finger and thumb of one hand, gently pull the layer outward, while pushing down on it with the thumb of the other hand.
- You'll be left with long fibrous strips of outer skin, which you can make into short bindings or natural cordage (see p. 140).


Try to peel away the layer in one movement

	WITHIES	LEAVES	SINEW
FACTS	- The strong, flexible stems of willow, birch, ash, and hazel are called "withies" and are used for thatching and in gardening. - Withies make useful and robust lashing and are best used in spring or summer.	- The leaves of many plants, such as the lily family, agave, and sisal hemp, contain useful fibers.	- Animal sinew makes strong and versatile cordage—some sinews can support the weight of a man. - Sinew has been used to bind arrow heads to shafts and to sew together everyday clothing, such as leather and mulduks.
FINDING	- Choose a young sapling or branch that's long and flexible. The fewer the stems or branches the better, as they will need to be removed.	- To find out if the leaves of a plant contain useful fibers, simply tear a leaf apart to see if it breaks into stringy layers.	- Sinews are the tendons connecting bone to muscle. The largest are on both sides of the spinal column, running parallel to it. - Shorter lengths can be taken from the calves of the hind legs.
PREPARING	- Remove stems or branches. Grasp the wand at the base and twist until the fibers break, working your way to the tip. Bend the wand into an S-shape and crank the middle of the wand to loosen the fibers. Then cut the wand from the tree and use the withies.	- Soak the leaves in water to make the inner layers swell and burst. Bacteria work on the cell tissue, separating it from the fibers. - Rinse the fibers in fresh water to stop further bacterial decay and then dry them.	- Take a tendon from an animal's body, remove its outer sheath, then clean it and let it dry. Separate the dried fibers and use them as individual threads, or splice or braid them together to form stronger cords. You can soften dried sinew with water or saliva.

MAKING NATURAL CORDAGE

Once you have prepared a sufficient quantity of fibers, it's best to let them dry before using them—hang them up in the sun or near a fire. In a survival situation, you can use them before drying. Twisting or rolling the fibers are the two main methods of making natural cordage. As with most survival tasks, practice makes perfect.

TOOLS AND MATERIALS

Enough prepared natural fibers (see pp. 138–39) to give you the length of cordage that you require

TWISTED CORDAGE

Start your first length of cordage toward one end, not in the middle, to prevent all the subsequent splices from coinciding at the same point. This provides strength, as each splice is a potential weak point. If they are thin enough, the twisted cordage fibers can then be plaited to create a thicker cord that's even stronger.


Keep the fiber taut


A loop forms naturally when you twist the fiber

1 Grip the first length of fiber a third of the way along its length between your left thumb and forefinger.

- Grasp the fiber with the thumb and forefinger of your right hand 1 in (3 cm) from your left.

2 Twist the fiber with your right hand until a tight loop is formed.

- Keeping the tension in the cord, inch your left thumb and forefinger forward and clamp down on the loop.


The cord is between your middle and fourth finger


The twisted cordage emerges in your left hand

4 Sweep the middle and fourth fingers of your right hand upward, pulling the left-hand cord under the captive piece.

- Inch your left thumb and forefinger forward, and clamp down on the new twist.

5 Now that the new twist is clamped by your left hand, you can release your right thumb and forefinger, letting the lower cord fall.

- Grip the upper cord 1 in (3 cm) from your left fingers with your right thumb and forefinger.

SIMPLE ALTERNATIVE TWIST

You need to start with two fibers of different lengths so that when you splice on additional lengths the splices are staggered. Start by tying one end of one fiber with one end of the other.

- Clamp tied ends in your left thumb and forefinger and the two tails in your right thumb and forefinger about 2 in (5 cm) down.
- Roll both fibers between your fingers away from you for one complete roll. Repeat this until you have about 3 in (7.5 cm) of rolled fibers, then clamp them in your right thumb and forefinger.
- Release your left thumb and forefinger and the rolled fibers will naturally twist together to form a strand of cordage.
- Repeat the process until you have enough for your needs.


Hold the twist with your left thumb and forefinger

③ Move your right hand back so that 1 in (3 cm) of cord is visible and apply another twist.

- At the same time reach forward with the middle and fourth fingers of your right hand and grasp the cord hanging from your left fingers.



⑥ Repeat Steps 3, 4, and 5 as you work your way along the length of cord.

- To splice in an extra length, overlap the new piece 2 in (6 cm) along the existing fiber and twist the two together between your left thumb and forefinger. Then continue with the process as before.

ROLLED CORDAGE

This method of rolling cordage, which is also known as the "pygmy roll," is easier to do if you're sitting down. As with the simple alternative twist (see left), you need to start with two fibers of different lengths and tie one end of one fiber to one end of the other.


Lay the tails of the fibers side-by-side on your thigh
Tie the ends of both fibers

① Hold the tied ends between the thumb and forefinger of your left hand.

- Lay the two tails of the fibers on your right thigh.


Keep the fingers together
The fibers are twisted but remain separate

② Use the flat palm of your right hand to roll both fibers simultaneously away from you. You may find it easier to use the flat of your fingers.

- At the end of the roll, clamp the fibers down onto your thigh with the tips of your fingers.


The fibers twist together

③ Release your left thumb and forefinger and the rolled fibers will naturally twist together to form a strand of cordage.

- Repeat the process, splicing in more cordage as required.

TYING KNOTS

THERE ARE HUNDREDS of different types of knot in existence, but by practicing the handful of straightforward knots shown here and overleaf, you should be able to accomplish most survival tasks. Start by tying each knot in the situation you expect to use it—for example, erecting a poncho shelter—and then practice it at least 20 times.

THE ENDS OF A LINE

The end of a rope or line that takes the most active part in knot tying is the working end. The other end is called the standing end—it's more passive, as the knot is tied around it.

SLIP KNOT

A slip knot is a good example of a simple knot that has many practical uses in survival situations.


Hold the working end between your right thumb and forefinger
Hold the standing end between your left thumb and forefinger

1 Twist the standing line over the working line to form a loop.

- Hold the loop between your left thumb and forefinger.


Loop in the working end
Standing end

2 Make a loop with the working end and pass it into the first loop.

- Collect the second loop with your left thumb and forefinger and pull it through.


Pull to tighten the loop
Pull to loosen the loop

3 Gather both ends in your right thumb and forefinger and pull them away from the loop in your left hand.

- Put the loop over whatever you want to secure—for example, a button-tie on your bivy sack—and pull the knot tight.

ARBOR KNOT

This all-purpose knot has several survival uses. When erecting a poncho or a tarp (see Chapter Four), it can be used as a tie-off knot to secure one end of a line to a fixed point, such as a tree or peg, where no adjustment is required. It can also be used as a lashing to secure two poles together—for example, in an A-frame shelter (see p. 164)—with just one turn of cordage.


Working line passes over the standing line
Keep the standing line taut
Hold the point where the two lines cross
Hold the working line between your thumb and forefinger

1 Pass the cord around the tree with the working end in your right hand and the standing line in your left hand.

- Loop the working end over the standing line, then back and over the cord around the tree.


Overhand knot
Pull the working end with your right hand

3 Keep the standing line taut with your left hand and pull the working end down with your right.

- By pulling on the working end you will tighten the overhand knot around the standing line.

OVERHAND KNOTS

An overhand knot is the first part of the knot you use to tie the laces on your shoes. One overhand knot tied around another forms a stop knot or they can be tied as a double overhand knot around a fixture.


Pull to tighten
Pull to tighten


Pull to tighten
Pull to tighten

OVERHAND KNOT

Twist the left line over the right to form a loop. Hold it with your right thumb and forefinger.

- Pass the working end through the loop with your left forefinger and thumb and pull both ends to tighten.

DOUBLE OVERHAND KNOT

Follow the sequence for the overhand knot (left), but pass the working end through the loop twice before pulling the two ends.

- A stop knot used at the end of a line can stop the line from slipping.


Tie an overhand knot around the standing line

2 Pass the working end around the standing line, and then over itself to form an overhand loop.

- Pass the free end up through the loop. (You have now tied an overhand knot around the standing line—see above, Step 1).


Pull hard on the standing line to lock the two knots together
Pull to unlock
Two single overhand knots tightly locked

4 Tie another overhand knot in the working end as close to the first knot as possible.

- Once the two knots are locked together, give the standing line a sharp tug.

DOUBLE CHAIN FASTENING KNOT

This knot securely attaches the free end of a line to a fixture, particularly when weight is involved and you don't want the knot to slip or come loose.


Working line
Standing line

1 Loop the working end around the fixture, such as a tree or pole.

- Pass the working end over and around the standing line.


Working line
Knot forming around the standing line
Standing line

2 Pass the working end back around the fixture and then bring it back under the standing line.


Working line goes around the fixture
Working line goes over the standing line
Standing line

3 Pass the working end over the top and around the standing line again, and once more around the fixture.


Working line goes through
Working end
Standing line

4 As you bring round the working line, thread it underneath itself to complete the knot.

- Lock the knot neatly into position.

DOUBLE SHEET BEND

The sheet bend, also known as the "weaver's hitch," is an extremely useful survival knot as it securely ties together two ropes. Double sheet bends are even more secure and are recommended for tying ropes of different thickness. In this instance you use the thinner of the two ropes to tie the knot.



1 Start with two ropes and form a loop in the working end of one of them.

- Pass the end of the second rope through the loop.


The loop in the second rope
The free end of each rope must be on the same side

2 Pass the free end of the second rope first under, then up and over the loop. Pass the end through the new loop you have created.

- To finish a single sheet bend, pull the standing end of each rope to tighten it.



3 To tie a double sheet bend, pass the free end of the second rope through the loop (as in step 2) again.

- Tighten the knot as before by pulling the free end of each rope.

SIBERIAN HITCH

This knot, which is also known as the "Evenk knot," is good for attaching a rope to a fixture—for example, when securing a ridgeline to a tree for a poncho shelter (see p. 158).



1 Pass the cord around the tree with the working line in your right hand and the standing line in your left hand.



2 Lay the standing line on the palm of your left hand.

- Loop the working line one and a half times around your fingers.



3 Bring your left hand under the standing line.

- Turn the palm of your hand so that one loop twists over another.


Hook your thumb into the loop

4 Hold the working end in your right thumb and forefinger.

- Bring the loop that is around your left fingers over the standing line.



5 Pinch the working line with the fingers of your left hand.

- Pull it up through the loop to tighten the knot on itself.



6 Pull the working end again, to tighten the knot around the tree.

- To free the knot, pull the end of the standing line.

TAUT LINE HITCH

This knot is widely used in survival and outdoor activities because it can be adjusted to increase or decrease the tension in a fixed line—for example, a guide rope on a tent or a mooring on a boat in tidal waters.


Working end
Half hitch creates a loop around the tree
Standing line

1 Attach the standing line to an anchor point, such as a tent, and pass the working line around a tree.

- Tie a half hitch (see below) with the working end around the standing line.


Working end
Standing line
Two half hitches

2 Tie another half hitch next to the first one, so that the two half hitches sit side by side around the standing line.

- Don't tighten the half hitches yet.


Working end
Standing line
Another half hitch around the standing line

3 Pass the working end under the standing line and back through the new loop it created (but outside of the loops in Steps 1 and 2).


Working end
Standing line
Tight knot

4 Tighten the knot by pulling both the lines.

- Pull the knot further from the anchor point to increase the tension.

QUICK KNOT RELEASE

You can dismantle a tent or free a boat from its mooring more quickly by finishing off the taut line hitch (see left) with a quick-release knot.


Standing line
A bight in the working line
Working end

1 Repeat Step 3 of the taut line hitch (see left), but this time make a loop, known as a "bight," in the working line and pass it—rather than just the end—through the loop.


Loop in working end
Standing line
The free end of the working line

2 Tighten the knot as in Step 4 (see left).

- Leave the working end free so you can pull it quickly to release the knot.

HALF HITCH

The half hitch is a simple knot that forms the basis for other knots (see taut line hitch, above). It's not a secure knot and, when used alone, it tends to slip. You can double or treble the knot to remedy this. Two half hitches under tension can be difficult to undo without cutting the cord, especially after a few days, if the knot has dried out after being wet.


Working end
Standing line

1 Pass the cord around the fixture, such as a bar or tree.

- Pass the working end around the standing line and back through the loop.


The knot is not secure
Working end

2 Hold the standing line and push the half hitch knot toward the fixture to tighten it.

- Repeat the sequence and tie another half hitch.


First half hitch
Second half hitch
Pull working end to tighten

3 Push the second knot tight to the first hitch knot for more security.

- If you need to, finish off the working end with an overhand knot (see p. 143).

USING CUTTING TOOLS

ANYONE VENTURING INTO THE WILDERNESS should carry some kind of knife, preferably a bushcraft knife. It's probably the most important survival tool after knowledge. Although a good knife will help you through many survival situations, look at the environment you are traveling to and choose your cutting tools according to their potential uses—for example, you may need a saw as well as a knife.

WARNING!
If you drop a bushcraft knife, never attempt to catch it because there's a very good chance you will lose your fingers!

BUSHCRAFT KNIFE

An experienced person can accomplish most survival skills, such as making feather sticks (see pp. 120–21), with a quality bushcraft knife. This type of cutting tool has a number of crucial features that will stand you in good stead in every situation.



A firesteel that fits into your sheath means that, as long as you have your knife, you can also get a fire going

Fitted leather sheath holds the knife securely

Attachment point for a wrist lanyard

The handle is comfortable to hold and work for extended periods. Avoid ribbed, rubber handles

Blades that extend through to the end of the handle (full tang) have no weak points

Sharpened blade ends near the handle – working close to the handle puts less strain on your wrist

Blade is $\frac{3}{16}$ in (4 mm) thick and made of stainless or high-carbon steel

The guard is a ridge in the handle that reduces the chance of your hand slipping on to the blade

LARGE KNIVES

All over the world, people living primitive lives have two essential items: a cooking pot and a large working blade, either a parang or machete.

- Parangs and machetes are similar types of knife. The parang is associated with the Malay people and there are many varieties available. Machetes are more common—you can still see machetes being used in Africa today that were made 40 years ago from old Landrover suspension springs! The kukri is a similar knife used by the Ghurkas of Nepal.
- A parang or machete blade is about 18–20 in (45–50 cm) long and is used primarily for cutting and slashing but, like the ax, can be used for intricate work.
- Always wear a wrist lanyard when using a machete, parang, or kukri—and pay attention to what you are doing.



KUKRI



MACHETE/PARANG

KNIFE KNOW-HOW

- A bushcraft knife is used primarily for carving, cutting, and splitting small logs. If you need to chop large logs, use either a machete or a saw.
- A knife doesn't need to be longer than 8–9 in (20–22.5 cm).
- Don't use a knife with a serrated edge when working with wood, as the serrations make it hard to use the part of the blade closest to the handle (essential for making feather sticks, etc).
- Keep your knife safe when not in use. Clean and dry the blade and return it to its sheath.
- Wear your sheath on your belt or around your neck on a lanyard. Belt sheaths may be high (the handle is above the belt) or low (the handle is below the belt, which allows you to sit down without the handle poking you in the side).

SHARPENING A KNIFE

It's very important to keep the blade of your knife sharp. Blunt blades are dangerous because they are likely to bounce or slip off the wood you're working on. Also, blades that have completely lost their cutting edge are very difficult to sharpen.

SHARPENING STONES

Keep a good sharpening stone at home to ensure you always set out with a knife that is sharp.

- In the field, carry a smaller, lightweight device for quickly re-sharpening a blade that is beginning to lose its edge.
- There is a good range of small sharpening stones (medium one side, fine the other) that fit into a neat leather pouch.
- Small automatic sharpeners are available to buy that use two sets of ceramic stones to sharpen a knife pulled between them.



Lay the blade flat on the stone

Raise the back of the blade to lay the edge on the stone

1 Hold the knife in a forehand grip, with the blade pointing away from you. Support the tip of the blade with the thumb and fingers of your other hand.

- Push the knife so the full blade arcs over the stone in one sweep.
- Lift the blade and return to the start, repeating the action 6–8 times.



Draw the knife over the stone toward you

Start from the far end of the stone

2 Repeat the sequence for the other side of the blade, but reversing the crucial elements.

- Hold the knife with a backhand grip, with the blade pointing toward you at the far end of the stone.
- Pull the knife in an arc over the stone in one draw. Lift and return to the start, repeating the action 6–8 times.

WORKING WITH YOUR KNIFE

The way you hold your bushcraft knife can help you accomplish a variety of cutting tasks easily and safely. There are several essential grips, including the forehand, backhand, and chest lever. In most cases, you need to grip the handle firmly at the end nearest the blade so that you can cut with the part of the blade nearest the handle.



FOREHAND GRIP

This grip is the most natural and the one most often used. It allows your back and arm to provide the power and strength, while your wrist provides the control. Placing one or both thumbs on the back of the blade allows you additional control for finer, more detailed work. Make sure the blade is facing down. Otherwise you are likely to give yourself a serious cut.



Steady the blade with one or both thumbs



Pull the blade toward you

BACKHAND GRIP

This is the same as the forehand grip, except the blade faces up toward you. You can use it when you want to see and control exactly where the blade is going, or when you're cutting something and a follow-through would injure you—for example, when sharpening a stick.

CHEST LEVER

This is an extremely effective technique in which you hold the knife in a backhand grip and use the muscles of your arm and chest to provide power and strength. You can cut close to your body while your wrists control the cutting action.



SAFELY PASSING A KNIFE

A group may only have one good knife for everybody to use, so you'll need to pass it to each other frequently. Pass the knife handle first, with the blade up. This simple and safe method is easily learned and can be adopted by everyone.



Work the wood with the part of the blade nearest the handle

TREE-FELLING WITH A BLADE

For shelters and fuel, the largest tree you are likely to cut down will be about 4 in (10 cm) in diameter. For anything larger you'd need an ax, but for smaller ones use a saw (see pp. 150–51). If you don't have a saw, use the blade of your bushcraft knife or a machete or parang. Whichever blade you use, keep its lanyard around your wrist.

1 Figure out the lean of the tree and start your first cut on the opposite side. This stops your blade jamming in the cut as the tree leans further.

- Hit the top of the blade with a thumping stick (club).
- Move the blade about ⅝ in (15 mm) to one side of the first cut, and then angle the blade at 45 degrees toward the first cut.
- Continue to alternate this action from side to side, cutting a V into the wood.



Your thumping stick is 18 in (45 cm) long and 3 in (7.5 cm) thick

The way the tree leans is the direction in which it will fall when you cut it

As you progress, the cut will open with the weight of the tree

Place the blade of your knife at 45 degrees to the surface of the tree

Choose the smallest tree that will provide you with the wood you need

Strike the back of your knife blade into the wood

WARNING!
Ensure your blade is sharp. Keep what you're cutting between you and the blade, with the blade pointing away.

SPLITTING FIREWOOD

When you split wood into fuel for a fire, use the largest blade you have, work on a solid surface, and avoid wood that has large knots as these prevent the blade from making a clean cut.

SAFE WORKING AREA
Chop wood in a safe area that other people won't wander into and where there are no snagging hazards or objects to impede your swing and knock your knife off-target.

LARGE LOGS

If you only have a bushcraft knife to work with, and you need to split large logs into smaller pieces, the following method works well.



Solid wedge

1 Hit the back of your knife with a stick and cut a solid wedge from the side of the log.



2 Use your knife and a thumping stick to start the initial cut across the top of the log.

Hit the wedge hard with your stick until it sinks into the log



3 Hit the wedge into the initial cut. Keep doing this until the log splits. Use more wedges if you need to.

Even wet wood will be dry in the center



4 If the log does not split completely, force it open with your hands or pry it with your blade.



Make a V-shaped cut in the side of the tree trunk



STRONG BLADES

Use a full tang knife (the metal of the blade continues in one piece to the end of the handle). The rivets that hold the handle may loosen eventually, but the blade is stronger than one that doesn't go **all** the way up the handle or a knife with a folding blade.

2 Work the cut around the tree until you've almost reached the middle from every direction except from below.

- If you try to cut completely through the wood from one side it will get increasingly difficult as the blade goes deeper.

3 Once the cuts are deep enough to weaken the wood, you will be able to snap the tree in two.

- Take care that the tree doesn't fall on your feet.

SMALL LOGS

Splitting a small log can be more tricky than splitting a large log, because it's difficult to balance it safely while you hit the blade with your thumping stick.

1 Place the log on a solid surface and put your knife in the middle of the end of the log you're about to chop.

- Hit the back of the blade firmly with your stick.



Put the blade in the wood so you can steady the log



2 Keep hitting the blade until the log splits down the middle. Split each piece again to quarter the wood.

4 To trim the branches from the fallen tree, start at the bottom and work your way to the top. This allows you a clear, short swing for your thumping stick.

- Keep the tree between you and the blade, and trim each branch in the direction of its growth.
- If you're using a machete, you don't need a thumping stick, as the heavy blade has enough momentum of its own.



If you're trimming on the ground, lay the tree on a flat, solid surface

Give yourself a clear swing and make sure the blade cannot harm you if it slips

USING A SAW

A saw is much better than a bushcraft knife for larger jobs, such as preparing logs for a fire or cutting down the poles needed to build a shelter. There are several types of pocket saw available that are lightweight and take up very little room in your backpack or survival tin.

USING A POCKET CHAINSAW

Using a pocket chainsaw to cut down a small tree is safe and not especially hard work. You can use the same saw to trim the branches and then cut the wood into manageable sections.



POCKET CHAINSAW
This 28 in (70 cm) chainsaw blade is compact and has attachment rings and handles. It can cut through a 3 in (7.5 cm) diameter tree in under 10 seconds.



You can improvise handles from sticks

Insert a wedge to prevent the saw jamming

Adopt a solid stance

1 Determine the natural lean of the tree and start to saw on the opposite side.

- Pull the saw back and forth.
- Knock a wedge in behind the saw when halfway through to stop the tree from jamming the blade.



2 Slow down when the saw has nearly cut through the tree.

- Allow the weight of the tree to snap the cut and break it in two.



If you're making a ridgepole leave 3 in (7.5 cm) of branch on the tree

3 Use the same back-and-forth rhythm to trim the branches.

- Clear the branches away as you trim them from the tree.



Hold the trunk in place with your foot

4 Saw the trimmed trunk into a measured section.

- When you're halfway through, prop up the trunk to make sawing easier.

FOLDING SAWS

Folding saws are strong, light, and convenient. Some, such as the Sandvik Laplander, have a serrated blade that folds into the handle (see right). Others, such as the backpacker's (see below), can be dismantled for stowing.


The blade opens and closes at a hinge

FOLDING SAW

BACKPACKER'S FOLDING SAW

These saws are generally lightweight and strong, but are not as effective as the pocket chainsaw. If space is tight, then you can pack only the blade and improvise a bow saw, using natural materials found in the woods.


Removable blade


The tension frame and saw blade can usually be taken apart and stowed safely

BACKPACKER'S FOLDING SAW

COMMANDO SAW

This saw takes up very little space and consists of a serrated wire blade with a swivel ring at each end. It's a useful piece of survival equipment, although it tends to snag and snap easily unless you keep it completely straight. You can easily convert it into an improvised bow saw, and, with a little more effort, make it into a very effective tension saw.



COMMANDO SAW


Make a notch to secure the second swivel ring
Use the bow saw to cut saplings

MAKING A BOW SAW

Cut a sapling approx 1 in (2.5 cm) in diameter and 3 ft (90 cm) long with a forked end. Hook the swivel ring of your commando saw over the fork and place the forked end on the ground. Ease the sapling into the other ring and make a notch for the ring to fit in.

IF YOU HAVE NO TOOLS

Even without any cutting tools, it's still possible to safely break wood down to size. The answer is snapping—or even burning—the wood. Don't be tempted to stand branches and sticks against a log or rock and then stamp on them in the middle. In a genuine survival situation your feet are your only means of transportation so don't do anything that risks injuring them.

SNAPPING THE WOOD

You need to limit the size of wood you're trying to break—don't try to snap branches that are too broad. Use wood that's dead, because green living wood just bends and refuses to break completely.

- Find two trees that are 1–2 ft (30–60 cm) apart—or a tree with two trunks close together—to use as a fulcrum for the wood. Place the wood in the fulcrum.
- Adopt a firm and steady stance and, with one foot in front of the other, pull the wood toward you until it breaks. Pulling toward you keeps your center of gravity over your spread feet, while pushing away from you causes you to stumble forward when the wood breaks.


Hold firmly on to the piece of wood
Place the wood between two trees—one is a stop or buffer, the other is a leverage point

BURNING THE WOOD

If you have a fire going, place the wood on the fire where you want it to break. Leave it on the fire until it burns all the way through. Alternatively, when it has burned halfway through, use the snapping method described above—but don't work on the wood while it's still burning or hot.


4

TAKING SHELTER

TAKING SHELTER

A shelter is your primary means of protection in a survival situation. It can be somewhere to simply keep dry during a sudden downpour or a place to spend several nights while out in the wilds. It's important, therefore, that you understand how to correctly construct your shelter. After all, its effectiveness could mean the difference between relative comfort and abject misery!

In a survival situation, it's important to play a proactive role in your own continued survival and rescue. You can only achieve this effectively if you're in a good condition—both physically and mentally. A day or night spent exposed to the elements will determine how well or how badly you perform the next day. A restless and uncomfortable night, for example, will lead to sleep deprivation, which can make you moody, irritable, and easily frustrated. This in turn can lead to a lack of concentration and irrational thinking—none of which are helpful in a survival situation.

Cold nights spent in the wilderness seem to last longer than they should, so time spent ensuring that you can

In this section YOU WILL DISCOVER...

- when to **lie low** in a hollow or **camp in a cave...**
- how to **modify** your **poncho** to put up a **shelter...**
- the difference between a **bothy** and a **bivy...**
- how to **bed down** with **duck down** or **wake up** in a **wickiup...**
- the **importance** of using your **noggins** to **secure** your shelter...
- how to **configure** your **fig leaves** to keep out the **rain...**

always enjoy as warm, dry, safe, and comfortable a night as possible is rarely wasted.

With shelter-building—as with other areas of survival—you should always apply the principle of expending the least amount of energy for the maximum amount of gain. This could mean simply exploiting the options nature has already provided, such as caves or hollows. Finally, plan for the worst conditions—it may be sunny when you build your shelter but pouring with rain at three in the morning!

On any expedition, you should aim to carry equipment—such as a basic bivy or a tarpaulin—that could be used to form a shelter should you need to protect yourself from the elements.

A SPACE BLANKET, however, is quite simply an essential piece of gear—if you pack nothing else, make sure you carry one and keep it with you at all times. Space blankets pack down very small and are available with one side silver (to reflect heat) and one side bright orange (to aid location). No matter what environment you're exploring, a space blanket can offer you immediate protection from the elements.

With a little ingenuity, a space blanket can also be converted into a basic shelter. You will find instructions on how to build a variety of shelters throughout this chapter, but always remember the following general tips, too:

- First look for natural sheltering places
- Look out for hazards such as signs of flooding
- Construct your shelter well before nightfall
- Clear the ground before you start to build
- Position the entrance at right angles to the wind
- Build for the worst possible weather conditions
- Make sure your shelter is sturdy and secure
- Don't over-exert yourself as you build
- Raise your sleeping area off the ground
- If on a slope, sleep with your head higher than your feet

> “The **effectiveness of a shelter** can mean the difference between relative comfort and **abject misery**”

HOLLOWS AND CAVES

IF YOU DON'T HAVE a shelter of your own, look for shelter opportunities that nature has already provided for you, such as a cave or a natural hollow in the ground. However, avoid natural hollows in low-lying areas that may flood and, if you're on a slope, keep well away from hollows exposed to run-off water.

TOOLS AND MATERIALS

- Sturdy digging stick
- Strong branches (or poles) and logs
- Saw, such as pocket chainsaw
- Tree bark, turf, leaves, forest mulch, moss, bracken, and pine boughs for the roof

BEDDING

Cover the floor of a shelter with some form of bedding to prevent your body from losing heat to the cold ground through conduction. After all the energy you've used to build the shelter, why waste it on an uncomfortable night? Use the driest materials you can find (see list below).

MAKE YOURSELF COMFORTABLE

Here are some ideas to help you enjoy a good night's sleep in your shelter:

- Collect twice as much bedding as you think you need: 6 in (15 cm) of holly, for example, compresses to about 2 in (5 cm) after you've been lying on it for a while.
- Place logs around the bedded area to stop the bedding from shifting and spreading.
- If the ground slopes, sleep with your head higher than your feet.



Use wooden pegs to keep the side logs in place

Bedding keeps you warm

BEDDING MATERIALS

- Feathers, such as duck and goose down, are the best bedding as they retain warmth but not moisture.
- You're unlikely to find enough feathers, so also try pine and spruce boughs, dry leaves, moss, bracken, grasses, and holly (cover it to prevent it from pricking you).

NATURAL HOLLOWS

A hollow that may be too shallow to sit in can still provide shelter from the wind if you lie in it—and, with a basic roof, keep you dry too.



A digging stick is a sturdy piece of wood with a pointed end

1 If the hollow isn't deep enough to lie in, remove some soil with a digging stick.

- Beware wet soil, as it could be prone to flooding.
- If the ground is too hard to dig, build up the sides with logs for extra depth.
- Lay bedding material on the ground before continuing.



Lay a log on top of the cross poles and along the length of the hollow

Make sure the poles are resting firmly on the side of the hollow

2 With your saw, cut a number of sturdy poles or branches (see pp. 150–51) that are long enough to place across the hollow to create a supporting roof.

- Cut a thicker, longer log and place it across the poles. This will create height and slope for a pitched roof. Make sure the log isn't too heavy.

TAKING SHELTER IN CAVES

Caves are ready-made shelters that are usually dry and secure. There are some dangers, including animals, poor air quality, and water. Many caves are outlets for streams or are connected to pools. Don't go any further in than you can see, as there may be hidden drops, slippery surfaces, and crevasses. Avoid old and disused mines, as they may be prone to collapse.

ANIMAL DANGERS

Many animals, such as bears, bats, insects, spiders, and snakes, shelter in caves, so check the ground around the entrance and inside for signs of tracks and nests. Vampire bats can be dangerous as they are known to carry rabies. Bat droppings (guano) form a thick layer on the ground and, in large quantities, can be highly combustible.

LIGHTING FIRES

If you build a fire at the front of a cave the smoke can blow back inside and the fire can block your exit if it gets too big. Build a fire toward the rear of the cave, but make sure that there is a sufficient flow of air for the smoke to escape. You can erect a small fire reflector or make a pile of rocks at the entrance to reflect heat back into the cave.

POOR AIR QUALITY

If a cave makes you feel light-headed or nauseous, leave at once because the air may be foul due to excess carbon dioxide. Other warning signs are an increased pulse and breathing rate. If a flame starts to dim, or turn blue, leave the cave immediately—this may not be a sign of excess carbon dioxide but a lack of oxygen, which can be worse.

COASTAL CAVES

Coastal caves share the same dangers as any other cave, but they are also subject to the tides, which can rise very quickly—in some areas they can advance hundreds of yards in a matter of minutes.

THE DANGERS OF COASTAL CAVES

When you're assessing a coastal cave, look out for the following warning signs of flooding during high tide:

- A line of seaweed, driftwood, or flotsam and jetsam—either in the cave or further back on the beach either side of the entrance.
- A damp or wet smell. The cave may even look wet if the tide has recently gone out.
- Rock pools in the cave or in front of it.



Air currents take the smoke out of the cave

Use fuel that doesn't produce too much smoke

A pile of rocks at the entrance helps retain heat in the cave

3 Place shorter branches, sticks, or poles over the top of the log and cross branches to create the pitched roof.

- Pack these materials tightly together and make sure they're firmly in position.



Lay a covering of short branches on the roof

The space between the support and pitched roof will help retain the heat generated inside the shelter

4 Leave an entrance at one end of the shelter with enough space to get in and out without disturbing the roof.

- Ensure the entrance doesn't face the wind—an angle of 90 degrees to the wind is best.
- Insulate the pitched roof with as much foliage as possible.
- Start the final insulation layer at the ground, working up to the top of the roof to create an overlap for rainwater to run off.
- In wet conditions secure your poncho or space blanket over the top.



The entrance should allow air to circulate in the shelter

The height and slope allow water to run off the pitched roof, rather than seep through

USE-ANYWHERE SHELTERS

WITH A PONCHO OR BIVY SACK (see pp. 160–61), you can make a shelter for use in any environment and in any conditions. You can also adapt any type of material—a survival space blanket, ground sheet, or tarpaulin—in the same way.

TOOLS AND MATERIALS

- Poncho, bivy sack, groundsheet, space blanket, or tarpaulin
- Cordage or elastic bungees
- Pegs; stick or pole
- Rock or log for hammering
- Survival knife or penknife

ONE-POLE PONCHO

This shelter is very quick and easy to erect and take down—useful when energy levels are low or when you just want to get out of the rain. If you need to be rescued, put the most visible color on the outside to increase the chance of being spotted.

1 Cut three 2 ft (60 cm) lengths of cordage and one 6 ft (2 m) length.

- Tie the shorter lengths into loops using an overhand knot (see p. 143).
- Tie the long length to one corner with a Siberian hitch knot (see p. 144).
- Fasten the cordage loops to the corner grommets.

2 Tie the long cord to a tree with another Siberian hitch knot at a height of 3 ft (1 m) off the ground.

- If no tree is available, run the cordage over a stick (staked into the ground) and peg it down.



Spread the poncho flat on the ground

Tie the longer length of cord to one corner using a Siberian hitch knot

The reverse color of the poncho against the ground acts as a location aid

Make sure the top of the stick in the poncho is secure



3 Place one end of a 3-ft (1-m) long stick in the hood of the poncho.

- Seal the hood by tying a simple knot.
- Wind several turns of cordage around the knot and secure it with an arbor knot (see p. 142).



Double chain fastening knot

Let 2 in (5 cm) of cord hang from the guyline so rainwater can drip away before reaching the shelter

Place pegs at an angle of about 40°, leaning away from the shelter

Pile leaves around the edges of the shelter to keep out the wind

4 Peg out the left and right corners, then raise the stick to form a dome.

- Pull the rear corner taut and peg it out to add tension, making the structure rigid.
- To enter the shelter, curl your body around the center pole.

CORDED A-FRAME

This poncho A-frame creates a tentlike shelter between two trees. If you have enough cordage, a single ridgeline can be tied between the trees; if not, use two cordage loops, as shown below. Alternatively, you can use a ridgepole at the same height.



Spread the poncho flat on the ground



Tie one of the longer cords to a tree using a double chain fastening knot

1 Find two trees 2 ft (60 cm) further apart than the length of your poncho.

- Attach cordage loops 1 ft (30 cm) long to each grommet on the longer sides of your poncho and 3-ft (1-m) loops to the end ones.
- Tie a knot around the hood to seal it.

2 Tie the end of one of the longer cords to a tree with a double chain fastening knot (see p. 143) at a height of 3 ft (1 m).

- Tie the other long cord to the second tree with a taut line hitch knot (see p. 145) and adjust the hitch to pull it tight.



Raise the hood to prevent water from pooling

3 Peg the middle loop of each side to pull the poncho taut. Peg out the four remaining loops, pulling tight as you go.

- If you have enough cordage, raise the hood by tying it either to a second horizontal line or to a vertical line passed over a branch above.
- Place long boughs along each side of the shelter, with shorter boughs at each end to hold in bedding material.

NEED TO KNOW

- Block one end of the shelter with branches, boughs, and mulch to help retain heat.
- If your material has no grommets, use button ties instead (see p. 161).

TENT PEGS

You can make your own tent pegs and then either reuse them or replace them with new ones when necessary. Discard old pegs that naturally decompose over time.

MAKING TENT PEGS



Notch cut in shaft

Stick sharpened to a point

- Pegs should be about 9in (22.5 cm) long and 1 in (2.5 cm) in diameter. Anything less will either snap under pressure or pull out in high winds.
- Cut wood for the pegs from green trees.
- Don't use wood from the ground as it will be in some stage of decay.
- Dry out new pegs slowly over the embers of a fire to harden them. Remove them when they're a light brown color. Wet wood sounds deep and dull when you tap it; as it dries the sound gets higher and crisper.
- Never drive a peg in with your foot. Use a stone or a heavy stick instead. If you misjudge it, the peg may stab you through the ankle or pierce your boot and even your foot.

ALTERNATIVE DESIGN

If you're in a group and you each have a poncho, you can clip two ponchos together and use one as a built-in floor.

USING TWO PONCHOS

First clip the poppers of both ponchos on their two long sides to form a tube. The top one is the A-frame, the bottom one the groundsheet.

- Pack all your bedding material under the bottom poncho and hold it in place by laying branches at either end.
- Assemble the shelter with the top poncho in the same way as the single poncho version.



Ridgeline holds the hood of the top poncho

Bottom poncho forms the groundsheet

BIVY PUP TENT

A bivy sack is a lightweight, waterproof cover for a sleeping bag and is made out of a breathable material that cuts down condensation. It's an essential component of ultralight camping (see p. 52) and can very easily be turned into a single-person pup tent. The advantage of making a tent from the bivy sack is that, in wet conditions, the rain runs off the side and doesn't seep to the inside as quickly as it does when the bag is flat on the ground.

TOOLS AND MATERIALS

- Bivy sack
- Saplings
- Button ties
- Wooden pegs
- Cordage and knife
- Rock or log for hammering

1 Lay the bivy sack flat on the ground where you intend to set it up.

- If you have the flap of the hood on top it will form a door that hangs down. However, if the flap is on the bottom you can tie it up as a door.
- Attach a button tie (see panel, opposite) with a loop to each of the bottom corners of the bivy sack.
- Peg the button-tie loops into the ground.



Attach a button tie to the middle seam of the bivy sack, about 18 in (45 cm) from the bottom

2 Attach a button tie with a long length of cordage to the center of the bivy sack's opening and hold it up.

- Pull down the right and left sides of the opening and place a button tie and loop where they meet the ground.
- Peg out the button-tie loops into the ground.



Hold up the button tie to see how high the entrance can be

4 Cut a pole the same height as the entrance (you could use a hooped sapling or crossed sticks instead).

- Stand the pole at the entrance, run the middle button-tie cord over the top, and peg out the cord tightly.
- Readjust all the pegs to ensure tight and even tension.



Make sure the cord sits squarely on top of the pole

5 When you want to get into the bivy pup tent, simply remove the opening pole and climb in feet first.

- Make sure you avoid the long cord as you wriggle in.



Lift up the central button tie so you can climb in

OTHER SHELTERS

There are other temporary shelters you can erect by adapting the techniques, tools, and materials outlined for both the use-anywhere shelter and the bivy pup tent. Which shelter you choose depends on whether you have a poncho, tarpaulin, or bothy bag.



HOOPED SHELTER
If there are saplings or soft wood trees, you can form three hoops and peg out your poncho over them.



TARPAULIN
Attach one side of the tarp to a line between two trees and peg the other end down to the ground at an angle.



BOTHY BAG
A bothy bag, or storm shelter, is a large, light, nylon bag that protects one or two people from the elements.

3 Place a hooped sapling (or two crossed sticks) over the bottom of the bivy sack.

- Attach the button tie that's 18 in (45 cm) from the foot of the bivy sack to the hoop to raise it and provide more space for your feet.
- Tightly peg out the cord from the hoop.



The hooped sapling is firmly pushed into the ground

6 After you have climbed in, replace the pole under the long cord.

- Use the hood of the bivy sack as a door and open and close as necessary.



Be sure to replace the pole in a vertical position with the cord squarely on top

MAKING A BUTTON TIE

Button ties provide a simple, secure fastening for staking out ponchos and tarpaulins that have no loops or grommets to which you could attach a line. As you don't have to cut holes in the material, it remains waterproof and less prone to ripping.



1 Encase a small, round, smooth stone (or similar) in material to form a "button". Prepare cord, with the open loop of a slip knot (see p. 142) at one end.



2 Place the open loop of the slip knot over the neck of the button and pull it tight.



3 At the other end of the cord make a simple loop to place over your shelter pegs.

FOREST SHELTERS

IF YOU FIND YOURSELF in a survival situation in a temperate forest without a poncho, bivy sack, or tarp, you can make a shelter from natural materials. For example, you can construct a lean-to or an A-frame, or simply adapt a fallen tree. A forest lean-to is easier for a group to build because you can share the workload and don't have to use up too much precious energy.

TOOLS AND MATERIALS

- Poles and stakes
- Saw and knife
- Cordage
- Saplings
- Foliage for the roof covering

BUILDING A FOREST LEAN-TO

A lean-to has a sloping roof that leans against a horizontal ridgepole. It works best on a flat area between two trees or vertical supports secured firmly into the ground. If you're building a lean-to for a group, ask everyone to lie down next to each other and add an additional 6 in (15 cm) per person—this will establish how wide the shelter needs to be.



Make the ridgepole longer than the distance between the trees

A log raises the foot of the shelter to give more room for your feet

Secure log in place with pegs driven into the ground

Lash each support pole (noggin) to the ridgepole and to the tree

1 Place the ridgepole against the trees at the height you require and lash it with an arbor knot (see p. 142) to both trees.

- Place a support pole (noggin) under the ridgepole and lash to the trees.
- Firmly peg a log where you want the foot of the shelter to be.



Criss-cross more saplings over the roof poles

Lay the covering from foot to ridgepole to help the rain run off

4 Apply the covering to the woven skeleton of the roof and walls. How much you apply depends on the weather you're experiencing.

- Lay large materials—for example, pine or fir boughs, large leaves, clumps of moss—as a base to stop smaller materials from falling through.

BUILDING IN A FOREST

Temperate forests, whether they consist of deciduous or coniferous trees or both, provide many opportunities for finding or building a shelter. Expend the least amount of energy for the most amount of protection—first see what nature can provide before building a shelter yourself.

POINTS TO REMEMBER

If you do need to make a shelter in a forest, here are some tips:

- Select a place close to water but away from water hazards, such as flooding, animals, and insects.
- Before you start, check for hazards such as deadfalls (sudden branch falls), rockfalls, and flash floods.
- Select a place that gives you maximum protection from the elements and with all the materials you need nearby.
- Collect everything you need before you start building and before it gets dark.
- Make sure your aids to location can be seen or activated quickly (signal fires, heliograph, flares, radio signals).
- Think safety: if possible, wear gloves to clear leaves and debris from the ground to protect you from spiders and snakes.
- Layer down your clothing as you work to prevent overheating.
- Make your shelter as waterproof as you can and ensure your bedding raises you at least 4 in (10 cm) off the ground.

TREE SHELTERS

The branches, roots, or trunk of a fallen tree can make a basic shelter. Make sure the tree is safe before you use it, as a further fall could injure you. Dead trees are probably dry, so don't light a fire under them. Check the base of the tree for snakes, spiders, and nests of insects.



BROKEN BRANCHES

A branch that has snapped from a tree trunk but hasn't yet fallen makes a good ridgepole. Prop smaller branches and roofing material up against it.



UPTURNED ROOTS

The base of an uprooted tree can give good protection from the elements. Make sure it's safe and won't flood if it rains, then add boughs and foliage.



FALLEN TRUNK

Lay sticks or branches against a fallen trunk to form a pitched roof. Weave saplings across them and cover with bark, turf, moss, leaves, and mulch.



Roof poles should be at least as long as the shelter needs to be

Side stakes along either side of the shelter form walls

2 Place five roof poles evenly along the ridgepole so that they slope back to the foot of the lean-to.

- Keep the outside poles between the trees to stop them moving outward.
- Lash each roof pole to the ridgepole.
- Hammer in side stakes alongside the outside poles.



Lay the saplings horizontally, then criss-cross with diagonal saplings

3 Weave saplings in and out through the roof poles, working across and down from the ridgepole.

- Alternate the weave of each row of saplings, first horizontally and then diagonally.
- Weave smaller saplings through side stakes to form walls.

5 With everyone in the same lean-to shelter you need to light and tend only one fire.

- Layer the inside floor with dry material to form bedding.
- Establish a watch system during the night to ensure that the fire is maintained and controlled.



Bank the final covering against the walls to help the insulation

Erect a sturdy fire reflector (see p. 164) around the front of the shelter

Place a pole between the trees to keep the bedding in place

FOREST A-FRAME

A-frames can take several hours to build, but if you're staying in one place for a few days it may be worth expending the energy. One-person A-frames are relatively simple to construct and are easy to keep warm. They can be adapted into multi-person shelters to accommodate groups of people.

TOOLS AND MATERIALS

- Poles of various lengths
- Saplings
- Knife
- Saw (or ax)
- Cordage
- Covering for walls—such as pine boughs, leaves, and moss



The long, sturdy ridgepole needs to be at least 3 ft (1 m) longer than you

Put the bare side of the ridgepole on the inside of the shelter

Tie ridgepole and A-poles together with an arbor knot (see p. 142)

Make sure the pole is firmly in the ground



Rest side poles against branch stubs

Ensure each pole has a stable footing

Tie a pole to the "A" to form the head end

1 Smooth one side of the ridgepole with your knife, leaving one side bare and one with branch stubs.

- Hammer two poles into the ground to form an "A".
- Rest one end of the ridgepole on top of the "A" and the other end on the ground.

2 Lay a series of poles against the branch stubs on the ridgepole. These will be of decreasing height as you work your way from front (the "A") to back (the ground).

- At each junction, rest the side poles against the stubs or tie them to the ridgepole with an arbor knot (see p. 142).

FIRE REFLECTOR

A fire radiates heat in all directions—up, down, and 360 degrees around. A fire reflector makes a fire more efficient as it directs heat into your shelter.

Construct your reflector so that you can build a fire about 3 ft (1 m) from the entrance to your shelter. You can sit in the entrance and tend the fire at arms' length—any closer and you would be too hot and the shelter might catch fire; any further away and you lose too much heat. An L-shaped end to the reflector will retain more heat.



Each set should be the width of a pole apart

1 Check the air flow will be across the proposed reflector (to disperse smoke).

- Hammer two poles into the ground. Put a second set in at poles' length apart.



Stack poles to form a wall

2 If the fire is going to be close to the reflector, use green wood to prevent the heat setting it on fire.

- Put poles between the sets to form a wall.



Finish the stack when it reaches the height you require

3 Tie the top of the upright poles together.

- Make sure the wall is as long as the shelter's entrance to retain heat and keep out wind and rain.

ALTERNATIVE SHELTERS

Two other options are a front-opening A-frame and a one-person lean-to. For the former, secure a ridgepole or line to a tree at the height you want the entrance to be, then adapt the forest A-frame (see opposite). For the latter, tie the ridgepole to two forked sticks hammered into the ground and apply a cover similar to the forest lean-to (see pp. 162–63).



FRONT OPENING A-FRAME

Wedge a noggin under the ridgepole and lash it to the tree with an arbor knot to take some of the weight. Build a fire reflector to the side with the prevailing wind.



ONE-PERSON LEAN-TO

A small one-person lean-to, together with a long log fire built in front, provides you with a warm, dry, and comfortable shelter for an overnight stay.


Alternate the weave of saplings between one row and the next

3 Weave four or five rows of saplings horizontally through the side poles to make the walls into a strong framework for the covering.

- Leave an entrance in the side near the front. Make sure it's large enough for you to sit inside comfortably.


First layer prevents final layer falling through

4 Cover the framework with a thick layer of natural material, such as pine boughs, small branches, and sturdy twigs. Weave the materials into a "thatch".

- On each side, work your way gradually from the back of the shelter to the front, and from the bottom to the top.

NEED TO KNOW

Build your shelter so that the wind blows across the front of it at a slight angle, rather than into it. This maintains its effectiveness and prevents smoke entering from the fire. If the shelter backs on to the wind, there's a risk the wind will blow around it and curl into the entrance.


The covered walls provide protection from the wind and the rain
Build a fire in front of the reflector

5 Cover the first layer with leaves, moss, and mulch, starting from the ground and working up to the ridgepole.

- Build a fire reflector (see opposite) in front of the entrance to help direct heat towards you.
- Stow your equipment and pack in the front of the shelter.

TROPICAL SHELTERS

TROPICAL RAIN FORESTS CAN BE the easiest environments for building shelters because of the wealth of available materials. Once you've found a suitable location just decide what type of shelter you need. The most important thing is to raise the shelter off the ground. Make it as comfortable as you can, because quality sleep is important.

TOOLS AND MATERIALS

- Poncho fitted with press-studs
- Cordage
- Long, heavy poles or wide bamboo stalks
- Spacer bars
- Knife, saw, machete, or parang
- Needle
- Strong, waxed, cotton thread

MODIFIED PONCHO BED

Most ponchos have press-studs to allow you to clip up the edges or to clip two ponchos together. They also have grommet holes that you can use as lashing points. Here, a poncho is modified into a tropical bed.



A simple knot keeps the grommets together

Slide a pole down each side of the poncho "tube"

Make the poles at least 3 ft (1 m) longer than your poncho

Make sure that the length of pole sticking out from either end is equal

The spacer bar fork fits around the pole

Keep poncho as taut as possible

1 Clip the press-studs of the two sides of your poncho together to form a kind of "tube"."

- Tie the grommets on the clipped side with pieces of cordage so that the press-studs don't come undone.

2 Cut two strong support poles that can take your weight.

- Insert the two support poles inside the "tube" of your poncho, one down each side.

3 Cut two "spacer bars" that will fit perpendicularly across the support poles or, if you can find them, cut poles with a natural fork in them.

- Tie the spacer bars into position using an arbor knot (see p. 142).

HAMMOCKS

Many types of hammock are designed for the kind of hot weather you get in the tropics, and are often fitted with mosquito nets. In fact, hammocks make the best overnight shelter, as long as you can find two trees the right distance apart. The Hennessy hammock is a good choice because it packs down small.



HENNESSY HAMMOCK

This ultralight, quick-drying hammock is both easy to set up and comfortable to sleep in (see p. 54). It's equipped with a self-closing door.



PARACHUTE SHELTER

Fold the panels of a parachute into a triangle. Lash a spacer bar to the opening and peg it out. Tie off the apex of the triangle further up the tree.



HAMMOCK AND TARP

Tie a ridgeline above the hammock. Drape the tarp over the line and anchor it on either side to a horizontal pole tied to two uprights.

ALTERNATIVE METHODS

You can easily modify other forms of sheeting, such as a tarpaulin, shelter sheet, and groundsheet. You will need a decent needle and plenty of strong, waxed, cotton thread (see Survival kits, pp. 60–61). There are two methods, which you can do either on the trail or as part of your prior preparation. Adding spacer bars keeps the poles apart and the sleeping platform tight. Both of these methods produce an excellent emergency stretcher.


The folded sheeting forms a tubelike structure
Strong stitches on the open side of the material

METHOD ONE

Lay the material on the ground and fold it once to create a wide "tube." Stitch the length of the open sides and then insert a pole along each side of the tube.


Stitch a "tunnel" wide enough to fit a pole through
The support pole fits into the "tunnel"

METHOD TWO

Fold the sheet and stitch a "tunnel" along both sides just wide enough to take a pole that will support your weight. Push the support poles through the tunnels.


The modified poncho makes a comfortable bed
Make sure the logs are firmly in place so they don't roll away
Peg if necessary
The spacer bar keeps the poles in place when you lie on the poncho

PONCHO BED BENEFITS

A modified poncho offers a bed that's easy and quick to assemble, keeps you off the forest floor, and provides a comfortable place for quality sleep.

4 The modified poncho now looks like a stretcher—in fact, you can use it as one in an emergency.

- Raise the poncho off the ground by resting it either on thick logs or sturdy poles.

ALTERNATIVE DESIGN

If you have a second poncho, shelter sheet, or tarp you can create a shelter to keep the rain off your modified poncho (see also Corded A-frame, p. 159).

- Tie a ridgeline between two trees and hang the poncho, sheet, or tarp over the top of it.
- If you're using a second poncho, tie its hood to another ridgeline.
- Peg out the four corners of the poncho, sheet, or tarpaulin.


Make sure the height of the shelter provides enough room for you and your bed

BUILDING IN THE JUNGLE

Shelters in the rain forest need to be quick to erect, just big enough for your needs, and safe from animals.

CHECKLIST

If you're thinking about building a shelter in a tropical forest, the following tips may help you:

- Check for hazards such as deadfalls (sudden branch falls)—a major cause of injuries during military jungle training.
- You'll need a sharp cutting tool—ideally a parang or machete, but a decent bushcraft knife or small ax will suffice.
- Clear the ground around your shelter to deter animals. Use a makeshift brush, never your bare hands, to avoid being bitten by snakes or spiders.
- Build your shelter far enough off the ground to avoid being bothered by insects, snakes, or any other animals—particularly those that move around at night.
- Start building your shelter well before darkness sets in, which, in tropical zones, usually happens very quickly. Using a large knife in reduced light or by the light of a flashlight can be very dangerous.
- Work at a rate that you can manage. Humid conditions can very quickly lead to dehydration and heat-related injuries such as heat stress and heat stroke. Your body tries to keep itself cool by sweating, so don't work too fast, drink water frequently, and take regular breaks.
- Make your shelter secure—you don't want to make repairs at night.
- Inside your shelter use a full mosquito net and a mosquito head-net.
- A fire will deter insects and animals.

JUNGLE A-FRAME

An A-frame is relatively easy to make. If you have a poncho, tarpaulin, shelter sheet, groundsheet, or another type of sheet, you'll need to modify it first to make it into a bed (see pp. 166–67). If you do not have a poncho, lay branches across the poles to form a sleeping platform.

1 Cut seven long poles that will take your weight. Tie two poles together with an arbor knot (see p. 142) to form an "A" and tie the joint to a tree or branch of a tree (as shown).



The angle formed by the "A" determines how far down the legs the platform will sit

2 Tie two more poles together to form an "A" for the other end.

- Position these in line with the first "A".
- The distance between the two "A"s needs to be at least 2 ft (60 cm) longer than your height.



Make sure the poles are wedged firmly into the ground

Check the junctions are securely tied

3 Put a ridgepole on top of the two "A"s.

- Tie this to both junctions for extra stability.



Use an arbor knot (see p. 142) to secure the poles at the top of each "A"

4 Position both poles of your poncho bed (see p. 166) on the outside of the A-frame.

- Move the poles down the outside of the frame legs until the sheet is taut.



The poles of the modified poncho settle into position

Tie the poles of the modified poncho to the legs of the A-frame for extra stability

5 Place a tarpaulin or shelter sheet over the ridgepole.

- Securely tie a guyline to each corner with a Siberian hitch (see p. 144).
- Run each guyline to a peg or tree and secure it with a taut line hitch (see p. 145).



Make the tarp or sheet tight by adjusting the taut line hitches

TOOLS AND MATERIALS

- Long poles and ridgepole
- Cordage and pegs
- Knife, saw, machete, or parang
- Modified poncho bed
- Tarpaulin, groundsheet, poncho, or shelter sheet

BAMBOO LEAN-TO

If you can find enough bamboo you can make a type of lean-to shelter. Find a spot close to the bamboo supply to reduce the amount you have to carry. If you need a raised sleeping platform, adapt the method used for the jungle hut (see p. 174).

TOOLS AND MATERIALS

- Thick wooden poles and bamboo poles
- Knife, saw, machete, or parang
- Cordage and pegs
- Poncho and tarpaulin (if you have them)


Use a thick piece of wood as a hammer
Wood with bark is easier to lash than bamboo


The ridgepole sits on top of the noggin
A ridgepole at hip height will let you get in and out easily


Rest a ridgepole on the back posts and tie it to them
Make one back post slightly higher than the other

1 Cut four thick, wooden support posts.

- Hammer two posts into the ground, wide enough to let you lie lengthways between them.

2 Tie a noggin to each post for support. Make sure they are level and at the height you need for an entrance.

- Place a wooden ridgepole on top of the noggins and tie it to the posts.

3 Make two short, forked back posts to give the shelter a sloped roof.

- Align them with the front posts and far enough back so the roof is wide enough to shelter you.
- Hammer them into the ground and tie a second ridgepole to them.


Wedge in knife then hammer it down with a strong stick
Steady the bamboo stem against a rock with your foot

4 Cut lengths of bamboo long enough to reach between the two ridgepoles.

- Split these by wedging your knife into each pole and hammering it down.
- Prepare enough split bamboo lengths to cover the roof area two times.

5 Starting from one end, lay lengths of split bamboo, hollow side up, side-by-side, between the ridgepoles.

- Work your way back along the roof, this time laying the lengths of split bamboo with the hollow side down.

The two layers of split bamboo interlock with each other for strength
The split bamboo layers of the roof direct water into the gutter
A split bamboo stem slopes into a corner and acts as a gutter
Peg bamboo poles to hold bedding in place
Collect fresh rainwater for drinking

6 Lash a long split bamboo stem to the lower ridgepole to form a gutter under the bamboo roof.

- Put a pan or pot beneath the end of this sloping gutter to collect water.

JUNGLE HUT

With a little extra effort you can make a more permanent and substantial shelter than a jungle A-frame. The raised apex roof of a jungle hut allows you to sit on the platform in relative comfort. This method uses a framework of four posts, but using two trees instead of two of the poles would make it more rigid.

TOOLS AND MATERIALS

- Strong posts and poles
- Branches for platform
- Knife, saw, machete, or parang
- Digging tool
- Broad leaves for thatching the roof

1 Dig four strong posts into the ground to form a rectangle at least 1 ft (30 cm) longer and wider than yourself.


Horizontal pole fits into a notch
Use a digging tool to loosen the soil
Roof supports are secured in position with an arbor knot (see p. 142)
Support noggin
Pole is at least 1m (3ft) from the ground
Tie each branch to the poles beneath

2 With your knife or saw, cut a notch into each post deep enough to fit the curve of the horizontal pole.

- Wedge the four horizontal poles into their notches and secure the junction using an arbor knot (see p. 142).
- Lash a noggin to each post to support the poles.

3 Lay a row of stripped branches side-by-side across the horizontal poles to form a raised floor.

- To make the roof supports, cut a notch on the inside of each post about 3 ft (1 m) higher than the platform.
- Tie a pole into the notches on the posts.

THATCHING LEAVES

By taking advantage of the shapes of some tropical leaves, you can make a substantial, long-lasting roof or walls. The bigger and broader leaves involve less work. If you use rattan palm leaves you can create an alternating interweave that gives a tighter thatch than the overlapping method described above.

RATTAN LEAVES

The rattan palm has leaves that are composed of rows of smaller leaflets. You can split the leaves in two and hang the halves in layers on the framework of your roof. Alternatively, you can use them whole, by folding the leaflets from one side and individually weaving them with leaflets from the other side.


A rattan leaflet has a sharp barb on its tip
Interweaving the leaflets from two sides of the same leaf creates a tight mesh

LONG, BROAD LEAVES

Many tropical plants have long, broad leaves that are good for thatching. These include some banyan figs, rubber plants, and types of banana. Arrange these leaves side-by-side on the poles of your roof frame, tuck them over the pole, and sew them into position with strips of vine. The tips of the leaves in one row point down over the leaves of the row underneath.





ALTERNATIVE SHELTERS

Wickiups are found in various forms around the world and are adapted as local needs and materials dictate. For example, Native Americans made them as temporary shelters in the plains, where they were also known as teepees. The pygmies of the rain forest used saplings to form a hemisphere that, once covered with natural material, created a warm, dry shelter.



An opening at the top of the wickiup allows air to circulate

WICKIUP

The wickiup is a cluster of straight poles that are lashed together at the top, with an interwoven framework that's covered with animal hides or grass.



The domed shape gives plenty of room inside

PYGMY HUT

The domed pygmy hut is made from a circle of bent saplings or limber poles secured firmly in the ground, then lashed and thatched with natural materials.



The pole forms the ridge of the roof

4 Tie poles together to form two A-frames. Tie these on top of the roof support poles at each end of the framework.

- Place a ridgepole across the apex of the two A-frames and tie it in place.



Work from the bottom to the top, overlapping the leaves so the rain runs off

Secure the leaves with thin strips of vine

Hang leaves with tips pointing down and shiny side up

5 Tie a series of horizontal poles to the legs of both A-frames to create a roof.

- Cover the roof with big, broad leaves (such as palm or banana) by folding them over the horizontal roof poles.

THREE-LOBED LEAVES

Leaves with three lobes, such as the familiar fig leaf, can simply be hooked over the poles of your roof with the stem pointing upward. On each row of leaves you need to hang the left and right lobes either behind the pole or in front of it in an alternating pattern. The middle lobe then hangs down over two leaves on the row underneath.







Tie the broad leaves back when its not raining

Secure bedding with poles laid around the floor

6 During heavy downpours close off one or both ends with three or four large, broad banana leaves.

- Weave the broad leaves into the A-frame at the entrance, and let them hang down.

TRUE-LIFE ACCOUNT

EXTREME SURVIVAL—IN THE JUNGLE

USEFUL EQUIPMENT

- Machete/parang
- Tarpaulin/shelter sheet
- Hammock and mosquito net
- Insect repellant
- Signal flares and whistle
- Flashlight and batteries
- First-aid kit
- Map, compass, GPS
- Survival tin, bushcraft knife
- Cell/satellite phone
- Poncho/bivy sack

FRENCHMEN GUILHEM NAYRAL AND LOÏC PILLOIS lost their way on a 78 mile (125 km) trek through virgin rain forest in French Guiana. They survived for 51 days in the jungle by drinking rainwater and eating palm seeds, snakes, and insects—although Nayral narrowly escaped death after eating a poisonous spider.

The pair set off from the Grand Kanori rapids on the Approuague River on Wednesday, February 14, 2007, bound for Saül, a former mining village at the center of the country. They planned to spend 12 days hiking, and carried sufficient food supplies, a compass and map, machete, a tarpaulin, and two hammocks. They soon found that the going was tough—some days it would take several hours of hacking through vines to hike just one mile. On the morning of February 26, when Nayral and Pillois had been due to reach Saül, the pair found themselves far from civilization and in unexpected terrain.

Knowing that a search operation would be launched, they set up camp and waited to be rescued. They built a shelter and divided the tasks—Nayral in charge of food and Pillois the fire, which was kept alight constantly to attract rescuers. They had abundant water from rainfall, but were reduced to scavenging for palm seeds, beetles, snakes, frogs, and spiders.

"THE PAIR FOUND THEMSELVES FAR FROM CIVILIZATION AND IN UNEXPECTED TERRAIN"

Occasionally, helicopters passed overhead, but failed to spot them through the dense canopy of foliage. After waiting for three weeks, the pair decided to abandon camp and trek west toward Saül. After another week of trekking for just three hours a day, unknowingly just 3 miles (5 km) from Saül, Nayral was incapacitated after eating a still-poisonous half-cooked spider. With no choice but to leave his companion behind, Pillois pushed on and reached Saül, returning with a helicopter to rescue Nayral—dehydrated, with intestinal poisoning, and plagued by parasites—on April 5, 51 days after beginning his trek.

WHAT TO DO

ARE YOU IN DANGER?

NO YES

If you are in a group, try to help any others who are in danger

Get yourself out of it:
Sun/Heat/Humidity—Slow down to the pace of the jungle. Find or improvise immediate shelter
Animals—Only six percent of snakes are poisonous but everything in the jungle will try to protect itself
Injury—Stabilize condition and apply first aid

ASSESS YOUR SITUATION

See pages 234–35

DOES ANYONE KNOW YOU WILL BE MISSING OR WHERE YOU ARE?

NO YES

If no one knows you are missing or where you are, you will need to notify people of your plight by any means at your disposal

If you are missed, a rescue party will almost certainly be dispatched to find you

DO YOU HAVE ANY MEANS OF COMMUNICATION?

NO YES

You are faced with surviving for an indefinite period—until you are located or you find help

If you have a cell or satellite phone, let someone know your predicament. If your situation is serious enough to be worthy of emergency rescue, and you have a Personal Locator Beacon (PLB), you should consider this option

CAN YOU SURVIVE WHERE YOU ARE? *

NO YES

If you cannot survive where you are and there are no physical reasons why you should remain, you will have to move to a location that offers a better chance of survival, rescue, or both

Address the Principles of Survival: Protection, Location, Water, Food

YOU WILL HAVE TO MOVE **

DO

- Make an informed decision on the best location to move to
- Use line of sight to navigate on your bearing, as visibility may be less than 33 ft (10 m)
- Improvise shelter when not moving, and sleep off the ground, clear of the damp floor and animals
- Be on constant lookout for dry tinder and fuel
- Follow water courses downstream. Transport in the jungle relies on rivers, so settlements are most likely to be found alongside rivers
- Step onto logs so that you can see what is on the other side, rather than stepping straight over onto an unseen snake

DON'T

- Use your hands to clear undergrowth—a machete or walking staff is better suited
- Drink untreated water—boil or treat all of your water before drinking
- Leave it too late in the day to stop and make camp—three hours before sunset is recommended
- Keep too quiet. Make a noise as you progress to warn animals for your approach

YOU SHOULD STAY **

DON'T

- Let the oppressive nature of the jungle overwhelm you. Slow down to its pace, don't fight against it
- Let your firewood get damp—store dry tinder and split or quarter wood to get to the dry inner core
- Eat what you cannot identify as edible—this could result in you becoming so ill that you cannot function

DO

- Select a shelter site where you can sleep off the ground and where your location aids will be most effective
- Use a mosquito net if you have one; if not, put damp foliage on your fire to repel insects, or cover exposed skin with mud
- Deploy all your aids to location and prepare them for immediate use. Be constantly alert for signs of rescue
- Keep your flesh covered despite the heat—the high humidity encourages infections. Also wash at every opportunity
- Keep a fire going—it aids location and wards off insects

---

* If you cannot survive where you are, but you also cannot move owing to injury or other factors, you must do everything you can to attract rescue.

** If your situation changes (for instance, you are "moving" to find help, and you find a suitable location in which you can stay and survive) consult the alternative "Do" and "Don'ts."

DESERT SHELTERS

IF YOU'RE PLANNING A TRIP into the desert, take something you can use to improvise an immediate shelter from the sun—for example, a shelter sheet, tarpaulin, poncho, space blanket, or even a couple of pieces of parachute material that will pack down into almost nothing. You can either build a shelter called a "scrape" in a natural hollow or erect a quick shelter above the ground using your poncho.

TOOLS AND MATERIALS

- Cordage and pegs
- Digging tool
- Knife
- Poncho, space blanket, tarp, or parachute material
- Rocks or ballast material
- Strong posts

BUILDING IN THE DESERT

Erecting a natural shelter in the desert is a challenge because of the heat and potential lack of materials, so try to find a site that's shaded by a tree or shrub.

POINTS TO REMEMBER

The following tips will help you deal with the extremes of temperature:

- Never try to build your shelter during the hottest part of the day.
- Ration your sweat and not your water. Avoid exerting yourself. If you start to sweat then stop what you're doing and take a break in the shade (30 minutes under an unfolded map or a space blanket and have a drink). If in a group, share the work.
- Don't leave it until the last minute to find a suitable location for your shelter. Make the decision early and plan accordingly.
- Never build a shelter in a low-lying area, dry river bed, or wadi as they are potentially at risk of flash floods.
- Avoid the top of large, isolated hills or mountains because of the danger from lightning and extreme winds.
- Try to set up your shelter on a small rise, where the temperature can be as much as 10 degrees warmer at night (cold air sinks).
- Ensure the opening faces north in the Northern Hemisphere and south in the Southern Hemisphere so the sun doesn't shine directly in during the day.
- Try to dig down to create a depression, as the ground is cooler below the surface.
- Build your shelter for the worst possible conditions and not the conditions at the time. Desert weather can change very quickly and dramatically, and the ferocious winds will rip apart any shelter that is not secure.
- If your shelter sheet has a shiny side, make sure it faces up to reflect heat and act as an aid to location from above.

DESERT SCRAPE

If you have cord, you can dig a scrape and use the cord to peg out the sheet above the scrape. If you don't have cord the sheet will have to be held in place by other means, such as soil, sand, or rocks. With all layered desert shelters try to maintain tautness and separation between the layers.

CORDLESS SCRAPE

If you don't have enough cord to peg out a sheet, you can make a scrape by either digging down or building up the sides with rocks or sand mounds placed at regular intervals. Anchor your sheet with rocks.

1 If the hollow isn't deep enough to lie in, make a digging tool and scrape out the soil from the bottom to build up the sides of the hollow.


Build up the sides with rocks covered with soil

2 Spread your poncho, shelter sheet or tarp across the top of the hollow.

- Make sure the edges of the material overlap the sides of the hollow.


Weigh the poncho down with rocks


Air space helps to insulate you from the heat
Make a gap of at least 6 in (5 cm) between the layers
Weigh the top layer down with rocks

3 Use an additional sheet to make a second layer to create dead air space that helps to reduce the temperature below.

- If you only have one piece of material to use as cover, try to double it over to create the two layers.

QUICK SHELTER

If you can't find a hollow, erect a poncho shelter (see pp. 158–59) in a place that keeps you cool during the day—for example, under existing shade, such as trees or bushes, or at the top of a slight rise in order to benefit from any cool breeze.

1 Find a site beside a tree or secure a post next to where you want the shelter's opening to be.

- Rig a ridgeline to the tree or post, and peg your poncho over it to form a shelter.
- Repeat with a second poncho, shelter sheet, or space blanket to create a separate layer.


Leave sides and bottom open to air the shelter

DAY-TIME CONFIGURATION

2 At night, de-rig the outer shelter and use it as a sleeping cover for warmth.

- Prevent heat escaping by securing the sides and bottom with rocks, stones, shingle, or sand.
- Sleep on some bedding if possible.


Weigh down with rocks or sand to keep the heat in

NIGHT-TIME CONFIGURATION

PARA SCRAPE

If you have cordage you can tie your sheet to four posts. If you haven't got enough cordage for four, use your backpack or a pile of stones instead.

- Prepare the depression or hollow as for a cordless scrape (see left).
- Use trees if available, or improvise posts from wood, piles of stones, or your backpack.
- Tie the sheet to the trees or the posts above the depression, leaving a gap for air to flow over.
- Create a second layer at least 6 in (15 cm) above the first.
- If foliage is available, place it between the layers to maintain separation.


Support post can be made from sturdy piece of wood
A tree may support and provide much-needed shade
Unpack essentials from your pack before using it as a post
Use a stable pile of rocks to support the sheets
The deeper the hole the cooler it will be
Air space between layers

SUN PROTECTION

You should always carry immediate protection against the sun. You may be able to create shade using something you've brought, such as a trekking umbrella, tent, or space blanket.


Material may be used as an aid to location

TREKKING UMBRELLA

A small, lightweight umbrella protects against sun, wind, and rain, creates cool shade, and doubles as a walking stick. Some have reflective material, or a flashlight in the handle.


Twigs and branches help to raise the shelter

SPACE BLANKET

This should be part of your basic survival equipment and will afford immediate relief from the sun. Remember that it's almost impossible to pack a space blanket to its original size once it's unpacked.

SHORELINE SHELTERS

IF YOU FIND YOURSELF in a survival situation, and can make your way to a shoreline or beach, it may offer you particular benefits. Rescue is more likely here than further inland as your aids to location work better in open areas, people are more likely to live on the coasts, and useful flotsam washes up twice daily on even the remotest of beaches.

TOOLS AND MATERIALS

- Digging tool
- Driftwood and/or rocks
- Broad-leaved plants or grass, or poncho or tarp
- Knife
- Cordage and pegs

DRIFTWOOD SHELTER

If there's enough driftwood around on the shoreline, you can use it to make a variety of shelters covered in this chapter. A hole-in-the-ground driftwood shelter offers simple protection, but may need continued attention if the sand is very fine or gets wet.

BESIDE THE WATER

Shorelines vary with the environment—from tropical beaches, where sleeping out under the stars is not a problem, to rugged coasts in higher latitudes, where spending a night unprotected from the elements would be suicidal.

POINTS TO REMEMBER

If you intend to spend a night on a shoreline, exposed to the elements, the following tips may help you:

- Build the shelter above the highest high-tide mark on a seashore (see opposite) and above the highest watermark on a river or lake beach. If in doubt, move slightly further inland, where the protection may be better and materials more easily available.
- Try to establish what the weather's going to do by looking at the sky, watching the water, or detecting changes in the wind (see pp. 82–83).
- Plan for the worst, or at least have a back-up location should things not work out.
- Check the area for insects, such as midges, mosquitoes, gnats, and horseflies.
- Look for signs of wildlife, such as crabs and even turtles as sources of food.
- Finish your shelter and collect water and firewood before it gets dark.
- Beware the effects of sun and windburn, even on overcast days.
- Utilize driftwood and other building materials. Remember, any wood that's been in the sea is likely to be very heavy.



The side of a trench gives better protection than stacked driftwood

Digging tool with pointed end

1 Make a digging tool and dig a trench in the sand.

- The trench must be above the high-tide line, long enough for you and your equipment, wide enough to be comfortable, and deep enough so you can roll over without disturbing the roof.



Create the roof using a thick layer of leaves criss-crossed over the framework

Avoid leaving any gaps in the thick layer of leaves

Sand piled up on top of a driftwood pole

4 Completely cover the framework with layers of palm leaves, broad leaves, or dune grass. Avoid leaving gaps because the next layer will be sand.

- As an alternative, you can lay a poncho, tarp, or shelter sheet over the framework. Weigh it down with sand or stones, or peg it out if you have cordage.


Build a wall made from sand, rocks, and driftwood
Driftwood pole provides a firm foundation for the roof


Add bedding before you make the framework
Firmly position cross-pieces on the driftwood in the walls to prevent the roof from caving in

2 Find two pieces of driftwood that are as long as your trench. Several shorter pieces in a line will work equally well if you can't find long pieces.

- Place the driftwood beside the trench and pile on sand and rocks to build up the height of the walls.

3 Place pieces of driftwood across the trench to form the framework of a basic roof.

- Weave smaller pieces of driftwood into the framework, making sure they sit firmly on the driftwood in the walls.


Sand insulates the shelter, and protects you from the elements
Bedding material is essential for keeping warm at night

5 Once you have covered the framework sufficiently, finish the shelter with a thick layer of sand or soil.

- The more cover you put on the roof, the more protected from the elements you will be. However, take care not to put so much weight on it that it collapses.

USING A LIFERAFT AS SHELTER

Remember, if you have abandoned ship in a liferaft, it can be used as a ready-made immediate shelter—even on land.

ON THE BEACH

The best place for a shelter is the landward side of the backshore: you can watch the sea, your daily fire can be seen from the sea, and you can see your shelter as you scavenge along the beach. In bad weather, however, the landward side of the dune crest is the best place.

PARTS OF A BEACH

A beach is shaped by the tides and the berm (a natural ridge) consists of deposits of the materials that make up the changing shoreline (sand, shingle, shale, and so on).

- At the top of the berm is a crest. A slope, or face, leads down from the crest to the water. At the very bottom of the face there may be a trough.
- The storm beach extends inland and this is where the wind and storms blow small particles of sand.
- Dunes form where the wind creates larger deposits of sand behind the beach.
- Longshore bars (sandbanks) may lie further out to sea and are formed where the waves first start to break.


Beach/Shore
Shoreface
Backshore
Fore-shore
Nearshore
Dune Crest
Berm Crest
Dune
Dune scarp
Berm
Sea
Shelter position in bad weather
Ideal shelter position
Trough
Bar

SNOW SHELTERS

THE TYPE OF SNOW SHELTER you can build depends on the kind of snow, the equipment you have, and the opportunities offered by the environment—for example, wooded areas are usually better than open areas because they provide protection and natural materials. You could build a snow trench, snow cave, tree pit, snow ledge, or a quinzhee.

TOOLS AND MATERIALS

- Boughs and branches
- Bedding
- Long pole
- Spade or pan for shovelling snow
- Long knife or saw
- Knife (or other long blade)
- Tarpaulin or shelter sheet

COMPACTED SNOW TRENCH

If the snow is compact enough, and if you have a long knife or snow saw, you can cut out blocks of snow to form a trench and then use the blocks to form an apex roof. This design requires a lot of effort and a bit of practice, but gives you a solid shelter with some additional height.

1 Use the blade of your knife to cut a rectangular trench that is the width, length, and depth you require.

- Cut blocks from the rectangle and place them at the side of the trench.



Don't strain yourself when cutting and lifting the blocks

Make each block 8–12 in (20–30 cm) thick

2 Trim the ends and rest two blocks against each other at the required angle for your roof.

- Use the other blocks to complete the roof and cut a triangle for the foot end.



Carefully balance and fit the trimmed blocks, starting at the foot end

Lay bedding of evergreen boughs at least 10 in (25 cm) thick

3 Pack snow into any gaps between the blocks.

- Pile extra snow on top of the blocks to add insulation.
- Create a doorway from snow blocks or your backpack.
- Don't block the doorway completely, but allow for adequate ventilation.



Use snow to seal the joins between blocks

Your backpack can be used to partially block the entrance when you've finished

BUILDING SNOW SHELTERS

Study the snow around you to determine whether it's compacted or uncompacted before you start.

POINTS TO REMEMBER

The following tips may help if you intend to build and stay in a snow shelter:

- Make a shelter that's just big enough for you and your equipment. Don't spend hours building a shelter for only one night: do the least amount of work for the maximum amount of protection.
- If you need to peg out guylines in the snow, tie a short stick 6–12 in (15–30 cm) long to a line or cordage and bury it in the snow. Compact the snow down on top and, when the snow sinters (hardens), your peg will be held secure.
- Snow is an excellent insulator. Fresh, uncompacted snow is typically 90–95 percent trapped air. Since the air barely moves, the snow can keep you warm and dry if used correctly.
- Check your site for hazards, such as snowdrifts, freezing winds, avalanche, cornice collapse, and big animals.
- Create ventilation holes—make one near the ground to let fresh air in and one at the top to let air escape. Check the holes are clear every 1–2 hours.
- Keep tools inside the shelter in case you have to dig your way out.
- If you leave the shelter, mark the entrance. Take basic survival equipment with you: it's better to have and not need than to need and not have.
- Brush snow off your equipment and clothing before entering the shelter.
- Tie all vital equipment to yourself so that you can't accidentally drop and lose it in deep snow.

FOUND SHELTERS

If you're lucky you may find a tree that has space under it so you don't have to dig a trench. For example, under a low bough or in a tree pit—an area where a heavy and deep snowfall has built up around a tree, leaving little or no snow under the lower branches. Use your walking stick to check the depth of the snow, and also to check for pockets of air.


Keep fire controlled so it doesn't melt snow above

LOW BOUGH

Find an evergreen tree with a large branch lying on top of the snow. Dig down from the leeward side, excavate a pit, insulate the floor with boughs, and make sure you have adequate ventilation.



TREE PIT

Test the snow around a tree that has large, low, snowbound branches. Little or no resistance indicates a pit. Dig from the leeward side, place boughs on the floor, and ventilate the pit.

FIGHTER TRENCH

If the snow is soft, a fighter trench is quick and easy to build. In an emergency, you can even make a trench by kicking out the soft snow. First, find a location that protects you from the elements as much as possible, then test the depth of the snow with your walking stick or a pole.

WARMING AND COOLING TIPS

Whether you're building a shelter or resting inside it, the following tips may help you stay at the right temperature:

- Remove layers of clothing as you work, perhaps to your base layers with a waterproof layer on top. Keep clothing dry so that when you stop working you can put it on again.
- Keep shelters at a constant temperature. If snow melts and then re-freezes, it stops insulating.
- Avoid heating your shelter too much. Even a candle flame can raise the temperature inside by four degrees.


If you can, dig down through the soft snow to the ground

1 Using a spade or pan, or by simply kicking away the snow, clear a trench large enough for you and your equipment.

- Allow at least enough depth for you to be able to roll over in your sleep without disturbing the roof.


Add bedding before making the roof

2 Create a framework of branches and boughs across the trench.

- Make sure you have enough roofing material on top to stop the snow from penetrating through.


A shelter sheet or tarp makes an extra insulating layer

3 If you have a shelter sheet or tarpaulin, place it on top of the framework to form an extra insulating layer.

- Alternatively, you can use it to cover your bedding.


Inside a trench you only have enough space to lie down

4 Cover the framework with at least 12 in (30 cm) of snow to act as insulation.

- Dig a small pit at the entrance to allow easy access.
- At the entrance, you can make a small, controlled fire on a green log base.

QUINZHEE

A quinzhee is a dome-shaped shelter made by hollowing out a pile of settled snow. It's an overnight shelter that is easier to construct than the more permanent igloo ("igloo" means "home"), which is made from cut blocks of snow and requires skill and knowledge. You can't stand up in a quinzhee, but you can sit upright or just curl up.



Cover your backpack with a tarpaulin

Build up the core with small branches and twigs



Scoop up the snow with a pan and throw it on top of the core

1 Find a relatively flat area that's covered with an abundance of snow.

- Mark a circle for your quinzhee, including walls that will be about 10 in (25 cm) thick, and stamp down the snow.
- Use your backpack and boughs or leaves covered with a tarpaulin to form the core of the shelter. Site the doorway at 90 degrees to the prevailing wind.

2 Use a container, pan, snowshoe, or other suitable item to gather as much soft snow as you can.

- Pile snow on the shelter's core to form a dome of the required height. Build up layers of snow until you have a covering of at least 10 in (25 cm), smoothing out each layer as you go.



Never use your hands to smooth out the snow

Mark each guide-stick at about 12–18 in (30–45 cm) before inserting it into the snow

Scoop up snow into a small mound to form the entrance

3 Smooth out the snow on the dome and leave it to sinter (harden) for 1–3 hours, depending on the type of snow and the ambient temperature.

- Keep active during this waiting period, particularly if it's windy: collect wood, build a fire (away from the quinzhee), and prepare yourself for the night.

4 To get an even thickness in the roof and walls, push guide-sticks of equal length through the snow toward the center of the dome.

- Build a small compact mound in front of the dome.

SNOW CAVE

A snow cave provides good protection but it takes a lot of work. Suitable locations might be compact snow on the lee side of a hill or an established snowdrift with a firm crust. Avoid snow that's newly fallen, powdery, loose, or shallow and uneven. The cave should be high enough to sit up in and deep enough for you and your equipment. Locate the entrance 45 degrees downwind to keep it free of drift.

BUILDING THE CAVE

- Dig a tunnel 3 ft (1 m) long into the snow bank, then excavate a cave on two levels. The lowest is the tunnel, while the other is a ledge at least 2 ft (70 cm) higher, and wide enough to sleep on.
- Create an arched ceiling to give the cave more support. Make it at least 18 in (45 cm) thick so it can take the weight of heavy snow.
- Mark the area with boughs to warn people where the shelter is.
- Insulate the sleeping ledge with plenty of natural material.
- Make at least one ventilation hole in the roof, but not facing into the wind.


Ventilation hole to let air escape
Smooth ceiling to prevent drips
Tunnel entrance to the snow cave creates a cold sink

SNOW LEDGE

You can build a snow ledge from a well-packed drift of snow out of the wind, or at least perpendicular to it.

MAKING THE SNOW LEDGE

- Dig out blocks to form a doorway about 2 ft (70 cm) into the snow. Dig out blocks to form a horizontal rectangle above.
- Dig upward to create a sleeping platform and then form an arched ceiling.
- Place the cut blocks across the horizontal rectangle and seal any gaps with snow.
- Make a ventilation hole in the roof and one lower down to let fresh air circulate.




Remove one or two guide-sticks to encourage ventilation
Make a fist-sized ventilation hole at the top of the dome
Make a fist-sized ventilation hole 1 ft (30 cm) up from the ground and keep it clear at all times
Backpack can be used as a door

5 When the snow has hardened, burrow into the mound, remove your backpack and tarpaulin, and excavate snow from the core.

- Use the guide-sticks to keep the walls at least 10 in (25 cm) thick.
- Don't use your hands to dig as they will get cold and wet.
- Smooth out the snow on the inside to prevent drips from forming.
- Build a raised sleeping platform. This creates a cold sink (an area into which the coldest air falls), taking cold air away from your sleeping area.

CARBON MONOXIDE

Carbon monoxide is an odorless gas that's produced when there's not enough oxygen to create carbon dioxide from burning fuel. Carbon monoxide poisoning can be fatal in a well-insulated, non-ventilated environment.

PREVENTION IS BETTER THAN CURE

Create one or more holes, 3–4 in (7.5–10 cm) in diameter, at the base and top of your shelter. Make sure the air flows out unobstructed.

SIGNS OF POISONING

Carbon monoxide poisoning is cumulative and can build up over a few days. Mild effects are fatigue, faintness, and flu-like symptoms. As it progresses, the effects are severe headaches, nausea, and decreased mental coordination.

TAKE ACTION

Get into the fresh air at once. You need to breathe fresh air for at least four hours to reduce the amount of carbon monoxide in your system by half.

DETECTORS

Carbon monoxide detectors are widely available, but tend to be made for the home or RV. Some models are battery-operated, but they're too bulky for camping. You can wear a patch that changes color when carbon monoxide is in the air, giving an early visual warning.



WATER AND FOOD

FIND AND TREAT WATER

The importance of water, even in a short-term survival situation, should never be underestimated. Water is essential to life, and a regular intake of 2–3 liters (4¹⁄₅–6¹⁄₃ pints) a day is needed just to maintain your water balance and prevent dehydration. The amount required can increase dramatically depending on factors such as the temperature of the environment, your age and physical condition, your workload, and whether you have been injured. It's not unusual for UK Royal Marines operating in desert or jungle environments to require 14 liters (3³⁄₄ gallons) per day. We tend to take water for granted, not appreciating just how important it is until we don't have any—at which point it becomes the most important thing in the world.

You should always plan your treks around your need for water and your ability to replace it as required. There are many hydration systems available and many small and efficient methods of filtering and purifying water on the trail. In a survival situation, you should always strive to filter and purify any

In this section YOU WILL DISCOVER...

- that **birds** can **show you** the **way** to **water**...
- when to **suck** on a **small pebble**...
- how to **make** a **gypsy well** and a **solar still**...
- why a **Finnish marshmallow** could **save your life**...
- how to **absorb water** without **drinking it**...
- how to **improvise** a **basic bladder**...
- the **importance** of **surgical tubing**...

water before drinking it. Bringing water to the boil will kill all water-borne diseases. In the short-term, stomach bugs from contaminated water may not kill you but they can seriously affect your ability to carry out other survival tasks. However, if you have no choice, it's better to drink contaminated water than not to drink at all. That way, a doctor will at least be able to treat you, whereas dehydration will kill you—and death can't be treated! Never drink urine or salt water, as these will only dehydrate you more.

If a source of water is undrinkable, such as salt or stagnant water, or even urine, you can still produce drinking water if you have the means to start and maintain a fire.

THERE ARE MANY WAYS to purify water, but if you have a fire you will always be able to distill it—and therefore make it drinkable. Build your fire close to the water source (if the water can be poured into a container or a hole dug in the ground where it will not seep away quickly, this will make the process more efficient). When the fire is established, place rocks in it (don't use slate or other layered rocks as they might shatter). Once the rocks are heated, use a forked stick or similar to transfer them into the salt or foul water. Then, suspend a piece of absorbent material, such as a T-shirt or moss, over the hot rocks to collect the steam. The steam will condense on the material and the resulting water, which you can wring out, will be fit to drink. If you have a cooking pot or survival tin, you can simply fill it with water, boil it over a fire, and collect the steam in the same way.

If you have absolutely no means of treating or boiling water, you should try to:

- Find the clearest flowing water and collect it from the surface.
- Filter debris out, even if only through a sock.
- Remember, it's better to drink foul water than not to drink at all.

> “We tend to take **water for granted** until we don't have any—at which point it becomes the most **important thing in the world**”

THE IMPORTANCE OF WATER

YOU REQUIRE A STEADY supply of water to sustain yourself in a survival situation and without it you will dehydrate. Left unchecked, dehydration will end in death. To survive, a balance between water intake and loss must exist.

WHY YOU NEED WATER

Water is essential to life. It is needed, directly or indirectly, for every physical and chemical process that takes place in your body. Here are just a few of the functions that water performs:

- **Delivery service:** water carries oxygen, nutrients, and other essentials around the body.
- **Waste remover:** the kidneys use water to flush out toxins via urine.
- **Coolant:** water regulates the body's temperature.
- **Breathing aid:** the lungs use water to moisten inhaled air so that it doesn't irritate the sensitive pulmonary linings.
- **Sensory aid:** water helps conduct nervous impulses around the body.
- **Shock absorber:** water protects the vital organs and provides lubrication around the joints.



Brain: *water makes up approximately 80 percent of brain tissue. It protects the organ from bumps and jarring*

Soft tissue: *water moistens tissues such as those in the nose, mouth, and eyes*

Blood: *water plays a significant role in regulating blood pressure*

Heart: *higher water consumption helps remove fatty acids from the body and reduces the risk of a heart attack*

Lungs: *water helps moisten the lungs and assists breathing*

Kidneys and liver: *water lessens the burden on kidneys and liver by flushing out waste products*

Stomach: *water helps the body digest food in the stomach and turn it into energy*

Mineral absorption: *water helps dissolve minerals and other nutrients to make them accessible to the body*

Bladder: *water enables the body to flush out waste and toxins through the bladder*

Bones: *water makes up approximately 22 percent of bones*

Joints: *water provides cushioning for joints and soft tissues*

Skin: *water plays a significant role in hydrating the skin and prevents it from becoming dry*

Body temperature: *evaporation of sweat (water) from the skin helps regulate body temperature*

HOW MUCH WATER DO YOU NEED?

How much water you need to survive a particular situation is dictated by a number of factors, such as your physical state, the environment you are in, and your exertion levels. Even when resting in the shade, the average person will lose more than 1 liter (1¾ pints) of water each day just through breathing and urination, a figure that increases dramatically once loss of water through sweat is taken into account. A minimum of 3 liters (5¼ pints) per day is required to remain healthy in a survival situation, with this amount increasing for higher temperatures and heavier workloads.

WHAT IS DEHYDRATION?

Dehydration occurs when you fail to replace the water your body loses. It's vital to recognize the symptoms early. Factors that can lead to dehydration include high and low temperatures, humidity, work-rate, clothing, body size, fitness levels, and injury.

THE EFFECTS OF WATER LOSS		
1–5% LOST	**6–10% LOST**	**11–12% LOST**
▪ Thirst	▪ Dizziness	▪ Stiffness of joints
▪ Discomfort	▪ Dry mouth	▪ Deafness
▪ Urine becomes darker	▪ Blueness of extremities	▪ Defective vision
▪ Loss of appetite	▪ Slurred speech	▪ Shriveled skin
▪ Impatience	▪ Swollen tongue	▪ Lack of feeling in skin
▪ Drowsiness	▪ Blurred vision	▪ Inability to swallow
▪ Lethargy	▪ Tingling in limbs	▪ Delirium
▪ Nausea	▪ Inability to walk	▪ Unconsciousness
▪ Headache	▪ Difficulty in breathing	▪ Death

WATER-BORNE DISEASES

Water-borne diseases are caused by ingesting water contaminated by the faeces or urine of humans or animals that contains protozoa, viruses, bacteria, or intestinal parasites. Globally, they cause 10 million deaths a year.

	DISEASE	SYMPTOMS
PROTOZOA	Cryptosporidium	Loss of appetite, nausea, and abdominal pain, usually followed by profuse, foul-smelling, watery diarrhea, and vomiting.
	Giardiasis	Loss of appetite, lethargy, fever, vomiting, diarrhea, blood in the urine, and abdominal cramps.
VIRUS	Infectious hepatitis (Hepatitis A)	Nausea, loss of appetite, mild fever, aching muscles, dark-colored urine, jaundice, and abdominal pain.
BACTERIUM	Amoebic dysentery	Feeling of fatigue and listlessness. Feces may be solid, but will smell foul and contain blood and mucus.
	Bacillary dysentery (Shigellosis)	Fever, abdominal pain, muscle cramps, high temperature, and blood, pus, and mucus in stools.
	Cholera	Vomiting, poor circulation, cold and clammy skin, muscle cramps, rapid dehydration, and increased heart-rate.
	E. coliform	Diarrhea and vomiting. Can cause death in vulnerable groups such as the very young or the elderly.
	Leptospirosis	Jaundiced appearance, lethargy, high temperature, aching muscles, and vomiting. Can be fatal if not diagnosed early.
	Salmonella	Nausea, diarrhea, headaches, stomach cramps, fever, possible blood in the feces, and vomiting.
PARASITES	Bilharzia	Irritation to the urinary tract and blood in urine, rash or itchy skin, abdominal pain, cough, diarrhea, fever, and fatigue.
	Hookworms	Anaemia and lethargy. Larvae travel to lungs and are coughed up and swallowed into the stomach, where they grow into worms.

TOO MUCH WATER?

Hyponatraemia is a condition caused when excess water accumulates in the body at a higher rate than it can be excreted. It results in a diminished sodium concentration in the body's plasma and the swelling of the body's cells. It can lead to a swollen brain and other neurological problems and, in extreme cases, coma and death. The way to prevent hyponatraemia is to control the amount of water that you drink, and to regulate your body's salt intake. If you don't have salt or sodium tablets in your survival tin, you can filter saltwater through fabric to sift out the salt content.

RATIONING YOUR WATER

If your water supplies are limited, you'll have to use what rations you have efficiently until you're rescued. If your water rations will not last that long, you'll have to procure water yourself. There is much debate about the advantages and disadvantages of drinking no water for the first 24 hours of a survival situation, but at this early stage it's best to make sure you're adequately hydrated. Your particular circumstances will dictate what's best to do, but always consider the following:

- The incident that put you in the survival situation may have been both dramatic and stressful; this will make you thirsty.
- In the first 24 hours of a survival situation, you'll be addressing the principles of survival: protection (shelter) and location (see p. 27). This is hard, thirsty work.
- Physical factors—such as seasickness, injury, or the environment you're in, such as a desert—may dictate that water-rationing is not a viable option.
- If you only have a limited water supply, but drink nothing for the first 24 hours, you may end up being so dehydrated that what little water you have in your possession will have no positive effect on your dehydrated state.

FINDING WATER: TEMPERATE CLIMATES

THE ABILITY TO LOCATE drinking water can challenge even the most experienced survivor and the challenges can vary dramatically according to the environment and the local conditions. It is, therefore, extremely important that you're aware of all the potential sources of water for the environment you're in.

WARNING!
In a survival situation, even if you think your chances of rescue are high and that help is imminent, you should start to look for water sources as soon as you have addressed the immediate problems of protection and shelter (see pp. 154–81). Remember that you can survive for up to three weeks without food; without water, you won't be able to survive for more than a few days.

COLLECTING WATER

You can find water in a range of sources, which vary in terms of quality and accessibility. Your priority is to locate the best and most accessible source of water in your immediate environment.

CATCHING RAINWATER

Collecting rain as it falls is the safest way to procure drinking water. It will need no treatment prior to drinking, as long as the catchment device itself has not been contaminated. Any number of non-porous materials—such as tarpaulins, ponchos, flysheets, survival blankets, or even large leaves—can be used as a rain-catchment device. Bear in mind that the larger the surface area of the material, the more rainwater you'll be able to catch.

1. Select a place as close to your camp as possible where your catchment device will be exposed to the most possible rain.

2. Firmly secure the tarpaulin to four stakes (sticks of equal length could be used) using string. Make sure that one end is higher than the other to provide a natural run-off for the water.

3. Place a heavy stone in the middle of the tarpaulin, roughly two-thirds of the way toward the lower end, to create a channel into which the rain will run down from the tarpaulin's sides.

4. Place a container, such as a pan or can, beneath the end of the channel to collect the water as it starts to flow off the tarpaulin.

MATERIALS AND TOOLS
- Tarpaulin
- Four sticks
- String
- Heavy stone
- Container



Use sticks as improvised stakes

Collect rainwater in a tarpaulin as it falls

Place a stone in the middle of the tarpaulin two-thirds of the way toward the lower end to create a natural run-off point for the water

Catch the rainwater in a container as it flows from the tarpaulin

LOCATING OTHER NATURAL WATER SOURCES

If rainwater is not available, there may be other natural sources of water, from easily visible streams and rivers, to bores and holes, which can be hidden. Whatever your source, you should always treat the water before drinking.

SOURCE	CHARACTERISTICS
SPRINGS	These occur when the water is forced to the surface as a result of subterranean pressures or from gravitational flow from higher sources. Found in low-lying areas, springs normally provide a permanent water source. Contrasting green vegetation is an indicator of their presence.
STREAMS AND RIVERS	Rivers and streams are an invaluable source of water, but there are still a few things you need to bear in mind when collecting water from them. The closer to the mountaintop the river or stream is, the clearer the fast-running water will be. The further downstream the water travels, the more likely it is to pick up minerals, debris, and pollutants that might be harmful to you. If possible, either check upstream for dead animals that may have contaminated the water, or follow the water downstream. Always try to collect the fast-flowing water near to the surface. In arid areas, rivers and streams tend only to flow during floods and will contain more pollutants and debris.
ROCK HOLES	Usually found in high ground, rock holes are natural collectors of rainwater. If the water appears to be trapped deep down, you can use your surgical tubing to retrieve it. Make sure you filter and purify the water before you drink it.
WELLS AND BORES	In some areas, you may find wells or old bore holes. Wells, which may be featured on local maps, can be deep and covered, making water procurement more difficult. In remote areas, wells are covered and marked in certain ways by the locals—find out what the markers are for your area.
LAKES AND PONDS	Rivers, streams, and water run-offs all flow into lakes or ponds. If you're collecting water from these sources, always try to collect it as it runs into the body of water, as lakes and ponds are more static than flowing water and can, therefore, become increasingly stagnant. Try to find the cleanest-looking area and avoid areas where debris has collected or where algae has formed. Note that the presence of fish indicates that the water is still oxygenated.
SEEPAGE	Usually located at the base of cliffs, high ground, or rocky outcrops, seepage is caused by slow-running channels that drain off these features.
SOAKS	Soaks are found close to rivers and creeks in low-lying areas, and are normally lower than the existing water table. The presence of soaks is often indicated by vegetation and they may be subject to pollution as a result of their use by animals. Make sure you filter and purify the water before you drink it.

AVOIDING POTENTIAL DANGERS

Most water sources are likely to be used by animals for drinking, bathing, urinating, and defecating, so always filter and purify any water collected before use (see pp. 200–01); the only exception to this rule is if you have collected rainwater. When collecting water, you should also be aware of the following dangers.

- It is possible that you'll encounter dangerous animals either using the water source, or on the way to or from the water source.
- Almost all major water sources will have a ranking system to determine which animals can use it. If all of the small gazelles suddenly disappear, ask yourself why.
- If you're collecting water from rivers, be aware of the potential dangers of river wildlife, such as crocodiles and snakes.
- If using dry riverbeds during the rainy season, be aware that flash floods can move quicker than you can run.

LOCATING HIDDEN WATER SOURCES

The presence of water is usually indicated by signs of life, such as green vegetation, animal tracks, or human habitation. Even if the terrain you're in appears lifeless, there may be plenty of indicators of a possible water source.

USE THE TERRAIN

- Observe the landscape for patches of green. Be aware that vegetation may not need obvious surface water for survival and may get its water from deep roots that tap into moisture below the surface.
- Water is subject to gravity and is more likely to be found downhill or in low-lying areas, such as valleys, dry riverbeds, narrow canyons, gullies, and at the base of cliffs or rock formations. Green vegetation forms next to a river and decreases as the ground rises away from the water source.
- Water will often seep inland on coastlines, leaving behind wetlands that contain water with tolerable levels of salt or that can be distilled in a solar still (see p. 189) to procure fresh water.

WATCH THE ANIMALS

- The Bedouin listen to the twittering of birds at dawn and dusk and follow their flight path to discover where they drink.
- Flocks of birds circling over one spot are usually flying over a water source. This does not apply to meat-eating birds, such as vultures, eagles, or hawks, who get their fluid requirements from the meat they eat.
- All finches and grain-eaters need a regular supply of water. Observe their flight patterns to locate a water source.
- Bees need water, so beehives are never far from a water source.
- Animal tracks, especially those of herd animals, will often lead to a water source. Look for converging sets of tracks.
- Flies stay close to water and the presence of mosquitoes almost certainly means that water is nearby.
- Look out for herd animals, such as buffalo, hippos, elephants, impala, and wildebeest, as they depend on water.

PROCURING WATER

Even if you find yourself in an environment without any obvious water sources, it doesn't necessarily mean that water will not be available to you. There are a number of water-procurement techniques that may mean the difference between you making it through a survival situation or not.

SOURCING WATER FROM DEW

Dew is water in the form of droplets that form on exposed surfaces in the early morning or late evening and can provide an invaluable supply of fresh water. It occurs when the temperature of a surface is low enough to allow the moisture in the warmer air above it to condense. Dew can easily be collected from any non-porous surface—such as a car roof or a tarpaulin—with a piece of cloth that can then be wrung out into a container. You can also harvest or trap dew.

HARVESTING DEW

You can harvest dew by walking through a field of long grass before sunrise or late in the evening with a piece of absorbent material—such as rags or a T-shirt—tied around your ankles.



1 Tie the material tightly around each ankle and walk through the dew-covered grass. It will absorb the dew as you move.



2 Wring the rags to extract the water. Repeat the process until you have an ample supply of water or the dew has evaporated.

DELAYING DEHYDRATION

When water is scarce, the following points will help you delay the onset of dehydration:

- Conserve what water you have and use it as efficiently as possible.
- Work only in the coolest part of the day and avoid sweating.
- If the sun is shining, seek shade and keep covered.
- Suck a small, smooth button or pebble to help stimulate saliva and remove the sensation of thirst.
- Avoid eating protein-rich food as it requires more water to digest than those in other food groups.

MAKING A DEW TRAP

Dig a hole about 18 in (45 cm) deep, line with a plastic sheet, and fill with smooth, clean stones. Water will condense on the stones overnight. Harvest as early as possible the next morning to ensure it does not evaporate.



Weigh down lining with stone
Place stones in the hole
Line hole with non-porous material
Condensation collects in bottom of hole

SOURCING WATER FROM PLANTS

Transpiration is the evaporation of water from a plant, primarily from its leaves. You can collect this vapor to boost your fresh water supply. All you need is a clear plastic bag.

MAKING A TRANSPIRATION BAG

Place a smooth rock in the lower corner of the plastic bag, and place the bag over the leaves of a tree branch, tying the end. As water evaporates from the leaves, it will condense on the inside of the plastic bag and collect at its lowest point.



Water will collect in the bottom of the bag

MAKING A VEGETATION BAG

Cut green vegetation and place it in a plastic bag. Place a smooth rock in the lower corner of the bag and tie off the open end. Secure the bag in direct sunlight. The sun causes water in the leaves to evaporate, condensation forms on the plastic bag and drips to the lower corner of the bag.



Fill the bag with the most succulent-looking leaves you can find
Water can be retrieved from bag with a piece of surgical tubing
Water collects in the lower corner of the bag

MAKING A SOLAR STILL

A solar still works using the same principle as a vegetation bag (see opposite). It collects potable water from the vapor that is produced by vegetation, water that is unfit to drink, or moisture from the ground.

1 Ideally find, or dig, a hole in the ground at least 2 ft (0.6 m) wide and 2 ft (0.6 m) deep. Place an empty container in the center of the hole. Fill the hole with vegetation, a receptacle containing undrinkable water, such as saltwater or urine, or fabric soaked in undrinkable water.

2 Cover the hole with a plastic sheet, and secure it in place with stones. Place a stone in the center of the sheet to create a run-off point for the water. The sun's heat will evaporate water from the vegetation, or distill the undrinkable water, producing pure water vapor. The water vapor, which is now free of contaminants, will condense on the underside of the plastic sheet, and drip into the container where it can be collected.

TOOLS AND MATERIALS

- Spade or shovel
- Two containers
- Vegetation and/or undrinkable water
- Piece of fabric or clothing
- Plastic sheet, tarpaulin, or space blanket
- Stones
- Surgical tubing


Surgical tubing to retrieve water
Clear plastic sheet
Fabric soaked in undrinkable water or urine
Container holding undrinkable water or urine
Small stones hold plastic sheet in position
Small stone forms a drip point on underside of plastic
Fresh, green vegetation
Container catches condensed water droplets

MAKING A GYPSY WELL

A good method of using the ground to create cleaner water from stagnant water sources, a gypsy well can also be used to collect water from saturated ground. The water collected through this method will still need to be treated before it is safe to drink (see p. 201).


Stagnant water source
Dry soil
Saturated soil
Water becomes clearer in second filling

1 Dig a hole a few feet away from a stagnant water source. It should be wide enough for you to be able to dip into it with a container and at least 12 in (30 cm) below the first layer of saturated soil. The hole will quickly fill with water.

2 Bail out the muddy water and allow the hole to refill—you may have to repeat this process several times. Once the water is clear, it can be collected, treated, and used. Cover the well when not in use to prevent debris or small animals falling in.

SURGICAL TUBING

Always pack a length of surgical tubing in your survival kit. It doesn't take up much space and is an extremely versatile piece of equipment:

- It can be used as an improvised straw to reach water trapped in rocks, hollows, and trees.
- It allows you to access water procured from a solar still without taking the still apart.
- It can be built into transpiration and vegetation bags so that you can remove water without having to open the bag.

FINDING WATER: HOT CLIMATES

YOUR NEED FOR WATER increases in hot climates as your body starts to use more of its water supply to regulate its temperature through perspiration. If you fail to drink more than you perspire, you will start to dehydrate and even approaching the first stages of dehydration can affect your chances of survival. Hot climates can be divided into two groups: hot-humid and hot-dry.

WARNING!
Water sources are plentiful in jungle and rain forest environments and, under normal circumstances, you should have no problem getting hold of enough water to satisfy your needs. However, rivers and streams may not be available during certain seasons, or if you have climbed too high, so knowledge of other water procurement methods could be crucial to your survival.

HOT-HUMID CLIMATES

The hot-humid conditions found in jungles and rain forests mean that procuring water is rarely an issue. However, the body's need for water in these conditions should not be underestimated; it is not unusual to have to drink up to 3 ¾ gallons (14 liters) a day to avoid dehydration.

SOURCING WATER FROM VEGETATION

Many plants, such as pitcher plants, have hollow parts that collect rainfall or dew. Some trees store and catch rainwater in natural receptacles, such as cracks or hollows. In an emergency, life-saving liquid can be garnered from a tree's roots or sap. You can find water trapped in the sections of green bamboo by carefully cutting into the bamboo with your machete or knife; or collect small, unripe coconuts and quench your thirst with the fluid they contain; or make a spigot and tap into the water contained inside the water tree. Life-saving fluid is everywhere in the jungle, and you don't have to look far to find it.



After making a second cut in the water vine, the fluid it contains will start to flow

WATER VINES

Found throughout the jungles and rain forests of tropical regions, water vines are easily identifiable by their size and shape and can provide an excellent sort of fresh water. However, bear in mind that not all water vines are water-bearing; not all contain drinkable water and some even contain poisonous sap.

1. Most water-bearing vines are about 2 in (5 cm) in diameter. If you think you have found one, make a small cut in the vine with a machete and check the color of the sap. If the fluid is milky, don't drink it; if it's clear, then the water in the vine will be safe to drink, so cut through the vine as high as you can with a knife or machete.

2. Cut off the vine at a point lower than the first cut. The liquid, which has a neutral, fruity taste, will start to flow. Don't let the vine touch your mouth as the bark may contain irritants.

3. The pores in the upper end of the vine may re-close, stopping the flow of water. To rectify this, simply cut the top of the vine again with your machete.

CATCHING RAINWATER

Catching rainwater is the best way to procure water: it is passive and requires no energy to collect once you place your containers. There are many forms of catchment device, but make sure you filter and purify the water (see pp. 200–01) before drinking it.

BAMBOO ROOF

Construct a sloped bamboo roof with a bamboo gutter. This could be the roof of your shelter (see p. 169), but if water procurement is a problem, you will have to construct additional bamboo roofs.

WIDE-LEAF ROOF

If you're in an area where there are wide-leafed plants, it's easy to construct a roof from them. Overlay the leaves as you would with roof tiles, working from the bottom to the top (see p. 170). Placed in this way, they will allow the water to run to the bottom. A length of bamboo cut in half lengthways can be placed as a collection gutter at the bottom.

BAMBOO DRAINPIPE

Observe rainwater's route down a tree trunk and tie a length of bamboo that has been cut in half lengthwise in its path. Place the other end of the bamboo into a suitable container.

DRIP RAGS

Wrapping any absorbent material around a leaning tree, such as a rag or a T-shirt, will result in the water running down the tree and soaking the material. Shape the rag to form a low point from which water will drip and place a suitable container underneath to catch the water.

HOT-DRY CLIMATES

Anyone venturing into this environment should have sufficient water for their needs, plus an emergency supply just in case, otherwise they have no right to enter the desert. Green vegetation usually signifies water or moisture in some form, and many techniques of procuring water in temperate climates (see pp. 188–91) may work in some desert conditions.

SOURCES OF EMERGENCY FLUID

If there is no surface water to be found, and you have no other means of procuring water, a water-yielding plant may be your only option. In some plants, the clear sap, fruit, or trapped rainwater, may quench your immediate thirst, but do not rely on these sources to keep you alive for long.



The barrel-shaped cactus is characterized by numerous ribs and hundreds of sharp spines

BARREL-SHAPED CACTUS

Barrel-shaped cacti contain a milky fluid that's safe to drink. Carefully remove the top of the cactus with a machete, mash up the flesh inside with a stick to make a pulp, and extract the juice from the pulp by sucking through a hollow grass stem. Alternatively, use a cloth to soak up as much of the fluid as possible and then wring the material to extract the fluid. The rewards from both techniques are minimal.



The prickly outer layer of the fruit has to be removed before consumption

PRICKLY PEARS

Found in low-spreading clumps measuring 3 ft (0.9 m) in height, and native to dry, sandy soils throughout the world, the prickly pear cactus has an edible fruit that can provide a life-saving amount of fluid.



Agaves have large clusters of thick, fleshy leaves surrounding a large central stalk

AGAVES

Native to Mexico and the southern and western United States, agaves have a rosette of thick, fleshy leaves containing fluid that is safe to drink. Cut the huge flower stalk with a knife or machete and collect the juice.

FINDING UNDERGROUND WATER

Water is life in the desert; wherever there is life there'll be water. Unusual clusters of green plants may indicate a minor presence of water; an abundance of greenery may indicate a more substantial water source. Water is rarely found above a depth of 6 ft (1.8 m) below the surface, so you will have to dig for it. If you do, make sure you only do so during the coolest part of the day. Bear in mind that, despite what you may have seen in movies, or read in other books, your chances of procuring water from the inside bend of a dry wadi in a real survival situation are slim to non-existent. In fact, you're more likely to waste what water you do have looking for the dry wadi and die in the process!

THINK LATERALLY

The chances are that if you're having to procure water in the desert you'll already be in a desperate situation. Bear in mind that, in addition to the methods mentioned above, if you have knowledge of the techniques outlined in the temperate environment section (see pp.190–91)—such as solar stills, dew traps, and vegetation and transpiration bags—it could be enough to keep you alive in the desert.

CHECKLIST FOR HOT-DRY CLIMATES

Even the best-laid plans can hit unforeseen problems, but many problems encountered in a desert environment can be avoided with some prior preparation.

- Always start hydrated.
- Carry enough water for your needs plus emergency water; your emergency supply should be enough to get you out of danger.
- Monitor your progress against the water you use. If you're using more than you thought, re-evaluate what you want to accomplish. It's better to turn back and learn from the mistake than to push on and create a survival situation that need not exist.
- Cache water ahead if necessary.
- Check your map for probable water sources. Confirm the reliability of these sources with locals and ask if there are any sources, such as wells, that are not shown on the map.
- Mark your map, or waypoint your GPS, with any water sources you sight as you progress. It's better to go back to a known source than to move on with nothing more than hope.
- To keep the water cool, always keep the bottles in the shade or in a windy location.

FINDING WATER: COLD CLIMATES

ADOPT THE SAME METHODS of trying to find drinking water in cold climates as you would in temperate ones (see pp. 186–91), although the ability to procure water becomes a major problem in freezing temperatures. The cold-weather survivor faces a dilemma: he or she is surrounded by water, but could die of thirst because most of that water is frozen.

WARNING!
Never try to melt ice or snow in your mouth, as it can cause freezing injuries to your mouth and lips. What's more, your body will expend heat as it melts the ice, and this could cause you to cross that very fine survival line between being cold or being hypothermic.

CHECKLIST FOR COLD CLIMATES

You should prioritize water usage in cold-weather conditions in the same manner as you would in desert conditions (see p. 193).

- One of your first thoughts should be about procuring water. You will have to find a water source that's close to everything you need to build and maintain a fire.
- Always look for an alternative water source before trying to melt snow or ice. It's easier, less time-consuming, and more fuel-efficient to fill your water containers with natural meltwater than it is to melt snow or ice by the heat of a fire.
- Your ability to procure water in freezing conditions will be directly related to your ability to start and maintain a fire.
- Be aware that it takes time and patience to melt snow and ice. You'll also need enough fuel to maintain a fire for a considerable period of time.
- Regulate your body heat to minimize overheating and sweating.
- Keep drinking water close to your body to prevent it from freezing, but avoid having water containers directly next to your skin. Instead, keep them between layers of clothing and use the warmer air trapped between the layers to help raise the water's temperature.
- Do not use recently frozen sea water, as it contains high levels of salt.

MELTING ICE AND SNOW

If you have the choice between melting ice and snow, favor ice, as it melts more quickly than snow and is up to 17 times denser. However, if you can't find ice, use dense, compact snow. Always look for the whitest, purest-looking ice or snow.

MELTING ICE

If you have some water to begin with, pour some into a container and heat it over a fire. Break the ice into small pieces—rather than adding it in one lump—and keep adding pieces to the container to melt them. Keep the water hot, but not boiling, so that you avoid losing water through evaporation.

USING A HOT PLATFORM

If you don't already have water for the method above, you can melt ice slowly on a gently sloping platform fashioned from any flat piece of stone or wood positioned above a fire.

① Build a fire. Search for a large stone with a flat surface and two logs, or smaller stones, that are strong enough to support it. Place the small logs or stones on either side of the fire as a support for the flat-surfaced stone. Make sure that the platform is at an angle. This will create a natural run-off for the ice as it melts. Place a block of ice in the center of the platform.

② As the fire starts to heat up the platform, the ice will begin to melt. The meltwater will flow off the platform, where it can be collected in a container, such as a mess tin.


Set platform on a gentle slope to allow water to run off
Place block of ice in center of platform
Collect the meltwater in a pan as it flows off the platform
Support the platform on two logs
Light a small fire to heat the platform and melt the ice

MELTING SNOW

If you already have water, follow the techniques for melting ice (see opposite), heating a little water and adding the snow little by little. Don't pack the snow too tightly; if an air pocket forms, the heat from the fire will be absorbed by the metal container rather than by the snow and could result in the fire burning a hole through the metal container before it melts the snow.

MAKING A FINNISH MARSHMALLOW

Cut a solid piece of dense snow—often referred to as a "marshmallow" or a "snowman's head"—and skewer it with a stick. Secure the stick in the ground close enough to a fire that it receives heat, and position a suitable container underneath it to capture the water as it melts.

STORING WATER

Snow is a great insulator: even if the temperature dips to -40°F (-40°C), water in a bottle will remain largely unfrozen if placed under at least 1 ft (0.3 m) of snow. Make sure you store the bottles upside down. That way, if some of the water does freeze, it will freeze at the bottom of the bottle and not at the top.

USING A MELTING SACK

Using a similar principle to the Finnish marshmallow (see left), this technique involves using an improvised sack—made from any porous material, such as a T-shirt or a sock—suspended near to a fire. The heat from the fire will start to melt the snow, which can then be collected in a well-positioned container.


Skewer a stick through a compact ball of snow
Meltwater will drip from the snowball's lowest point
Place a container to collect the water


Make the sack from any porous material
Suspend the sack close enough to a fire for it to benefit from the heat

IN A WORST-CASE SCENARIO

If you're caught out on barren snow or ice, you're unlikely to have access to natural fuel to burn in order to melt snow or ice into water. As long as you have your second-line survival equipment (see p. 42), you'll have all you need to procure life-saving water.

USING YOUR FIRE TIN

Set up your fire tin on the ground and shelter it from any wind using either your body or your pack. Using your survival tin as a container, place small quantities of ice or snow into the tin. Light your fire tin and place your survival tin over the flame. Add more ice or snow as it starts to melt.

USING YOUR MATCHLESS FIRESET

Place the lid of the matchless fireset tin on the ground. Light a hexi fuel block using the cotton wool and flint/striker. Using the fireset container or your survival tin, melt small quantities of ice or snow over the flame. Once the ice or snow has melted, let the container cool so you don't burn yourself. The water is then safe to drink.


Snow or ice placed in a metal container melts over the flame
Fire tin or matchless fireset + ice/snow – life saving water

USING BODY HEAT

When Inuit hunters capture a caribou, they empty out the contents of its stomach, turn the stomach inside out, fill it with snow, and tie it shut with a length of intestine. They then put the stomach back in the cavity while they skin the caribou. By the time they have finished, the heat given off by the animal's body has melted the snow. The Inuit then open the bag carefully and suck out the water through a block of snow to filter it.

FINDING WATER: AT SEA

OF ALL ENVIRONMENTS, the sea is possibly the most difficult in a survival situation. It offers no natural resources for protection against the extremes of temperatures, wind, rain, and sea state, and provides little to aid location. Being surrounded by water that you can't drink only adds to the difficulty. Some devices are capable of making seawater safe do drink, but if you don't have one, you'll have to find a way of procuring enough fresh water to keep you alive.

WARNING!

Never drink salt water. Its salt concentration is three times higher than that of blood and ingesting it will dehydrate you. Continued use over a prolonged period will lead to kidney failure and, ultimately, death.

CONSERVING YOUR WATER RATIONS AT SEA

Rationing fresh water supplies when you're adrift at sea is a sensible precaution, as you have no idea how long it will be before you're rescued or before you reach land. Here are a few tips to help you conserve what water you have while you're at sea:

- Fix your daily water ration after taking stock of the amount of water you have, the output of solar stills and desalting kits, and the number and physical condition of your party.
- Prevent fresh water supplies from becoming contaminated by saltwater.
- Keep water supplies well shaded, both from the overhead sun and from the glare off the sea's surface.
- In hot conditions, dampening your clothes with saltwater can help to lower your body temperature—but don't overdo it. This is a trade-off between cooling yourself down and the saltwater boils and rashes that will result from continued exposure.
- Don't exert yourself. Relax and sleep whenever possible.
- Use every container you have—even a simple trash bag—to collect rainwater, and keep them well sealed and attached to the raft.
- If you don't have water, don't eat. Protein consumption will hasten the onset of dehydration.

COLLECTING FRESH WATER

If you find yourself adrift with no hope of immediate rescue, obtaining drinking water will be a major priority. If you don't have a solar still or a reverse-osmosis pump, you must find another means of procuring fresh water. Fortunately, there are several ways of doing so.

GATHERING RAINWATER

Most modern liferafts incorporate a built-in rainwater catchment system that channels rainwater and dew from the outer surface of the liferaft into collection pockets inside the liferaft. However, even if you're not in a liferaft, you can construct a similar system using a tarpaulin or any other waterproof material. Watch the clouds, be ready for the possibility of any showers (see pp. 80–81) and spread your tarpaulin in a bowl shape to catch the largest amount of rainwater possible. Always place a tarpaulin before nightfall, so that you don't miss out on any overnight rainfall.

HARVESTING DEW

At night, secure the tarpaulin like a sunshade and turn up its edges to capture dew. It's also possible to harvest any dew that may have collected on the sides of the raft using a sponge or cloth that you then wring out.



Tarpaulin is spread over large surface area to catch as much rainwater as possible

Rainwater collects in a hollow in the tarpaulin

Channel the collected rainwater into a receptacle

TREATING SALTWATER

If you have no means of collecting rainwater or dew, there are several products capable of turning undrinkable saltwater into fresh water. Although these products are standard issue on most liferafts, you should always try to have at least one of them with you if you are venturing into a marine environment.

SOLAR STILL

Solar stills are a simple way of distilling water using the power of the sun. Saltwater is placed at the bottom of the container, where it is evaporated by the sun through clear plastic. Pure water condenses on the top of the plastic and drips down to the side, where it can be collected, often via a tube. Most solar stills on modern liferafts are inflatable.


Sun's heat causes saltwater in solar still to condense
Water droplets condense on edges of the still
Black fabric interior absorbs the heat of the sun
Water can be retrieved with a tube

MAKE YOUR OWN SOLAR STILL

If you have a chance to gather together the right materials, it's easy to make a small solar still. All you need are two containers (one larger than the other), a sheet of plastic, some string, and a weight to form a natural run-off point for the water as it condenses under the heat of the sun. If you have some surgical tubing, you can use it to retrieve the fresh water without taking the still apart.


String secures plastic sheet to bucket
Plastic sheet inside bucket forms a funnel
Condensation forms on underside of plastic sheet
Rock or weight
Tubing tied off to avoid saltwater contamination
Bucket
Surgical tubing to retrieve fresh water
Cloth saturated with saltwater
Cup to catch fresh water

REVERSE-OSMOSIS PUMP

These hand-powered devices pump seawater at a very high pressure through a membrane that filters out the salt. Depending on the model, they can produce around 23 liters (49 pints) of fresh water per day.

DESALTING KIT

These kits turn seawater into freshwater through a process called "ion exchange." Because they only produce small amounts of fresh water over several hours, use desalting kits only during long periods of overcast weather when you can't use a solar still.

THE LAST RESORT

In absolute emergencies, potentially life-saving forms of liquid can be obtained from the ocean.

SEA ICE

In Arctic seas, you can obtain drinking water from old sea ice. This ice is bluish in color, has rounded corners, splinters easily and, more importantly, is nearly free of salt. New ice is gray, milky, hard, and salty. Water from icebergs is fresh, but icebergs are dangerous to approach, so you should only use them in an emergency.

FISH

Drink the aqueous fluid found along the spine and in the eyes of large fish. Carefully cut the fish in half to get to the fluid along the spine and suck the eye. If you are so short of water that you need to do this, do not drink any of the other fluids: they are rich in protein and fat and your body will use up more of its water digesting them than it obtains from them.

SEA TURTLE

Sea turtle blood has a salt concentration similar to that of humans. The blood can be collected by slitting the turtle's throat. Note that, although this may help prolong survival, sea turtles are an endangered species, so you should only kill one as a last resort.

REHYDRATION ENEMA

If you have some water that is not salty or poisonous, but is too foul to take orally, you can absorb as much as a pint a day—enough to keep you alive—through the large intestine using an improvised tubing device.

CARRYING AND STORING WATER

YOU WILL NEED TO make many decisions in any survival situation, some of which could mean the difference between life and death. One of these decisions will be whether to stay and wait for rescue or to attempt self-rescue. A major factor in this decision will be the availability of water and your ability to carry and store it.

WARNING!
Mark your containers clearly. Late at night in camp it's easy to confuse bottles that contain treated water with ones that contain untreated water or camping fuel.



If your container has a lid, it can be used to scoop water from a stream before you pour it into a larger water bottle

WATER CONTAINERS

There are many different kinds of container for carrying both hot and cold liquids. They range from solid plastic or steel flasks or bottles, to collapsible waterproof bags that can be folded up when they're empty.



Fitted with a push-pull nozzle for ease of use while on the move

PLASTIC WATER BOTTLE

Strong and lightweight, with screw-off tops or push-pull nozzles.



Metal container can be used to boil water

METAL WATER BOTTLE

Slightly heavier, but stronger, than plastic water bottles.



A metal exterior and a glass interior makes a thermos a heavy alternative

THERMOS FLASK

Although very heavy, thermos flasks allow you to store either hot or cold water.



Metal lid doubles up as a cup

MILITARY WATER BOTTLE

A standard issue bottle used by most of the world's military forces.



Store purification tablets in pouch

COLLAPSIBLE WATER CANTEEN

Heavy-duty plastic water canteen that can be hung round the neck.



HYDRATION SYSTEMS

Hydration systems usually consist of a water-storage container (called a "reservoir"), an on-demand, one-way drinking tube, and a harness. However, a common problem with these systems is that, because you can't see the water, you can suddenly discover you have used all of it without realizing.



Water container is filled and then carried in a backpack

Water is accessed via a one-way drinking tube



Use to store water once you're in camp

COLLAPSIBLE WATER BOWL

Easy to pack, light, and can also be used to seperate items in your backpack.



Stow water bags flat in your pack when not in use

WATER BAGS

Useful for carrying water from its source back to your camp. Can also be used to keep your equipment dry.

IMPROVISING WATER CONTAINERS

In an emergency, there's a strong chance that you won't have the luxury of having water bottles or storage systems at your disposal. However, with luck—and a little ingenuity—you should be able to find something that allows you to store and carry enough water to satisfy your needs.

SEA SURVIVAL SUIT

Because they are designed to keep water out, they can also be used to keep water in. Most survival suits are packed with a layer of chalk to prevent the material from sticking together, so wash it out before use.

WATERPROOF CLOTHING

Many types of waterproof clothing can be adapted to hold water. Jacket sleeves and trouser legs can be knotted to form a basic bladder; Gore-Tex® socks will hold water; and some waterproof backpacks can be used for water storage.

DISCARDED MATERIALS

Always be on the lookout for anything that can hold water, from empty plastic bags and bottles, to large industrial-type containers. Clean and sterilize found items before use.



Heavy-duty plastic bags can be used to carry water

GOURDS

The shell of a hollowed-out and dried fruit—a gourd—can hold water. Gourds made from large fruits, such as squashes, pumpkins, and melons, can hold a considerable amount of water.



Look for a gourd with a shell thickness of $\frac{1}{4}$in (60 mm)

EMERGENCY WATER

Sachets of emergency water can be bought and stored for emergency use. They usually come in a packet that contains five $1\frac{7}{10}$fl oz (50 ml) sachets of water, each being little more than a mouthful. These should always only be used as a last resort. Always try to procure water by other means before turning to your emergency water supply.

BAMBOO

A bamboo cane will provide a natural cup if you cut 1 in ($2\frac{1}{2}$cm) below one joint and then 1 in ($2\frac{1}{2}$cm) below the next. Take care to smooth the edges after cutting.



Bamboo can be cut into a ready-made cup

MAKING A MINI-RESERVOIR

Your ability to store sufficient water for your needs in a survival situation may be limited and it may be impractical—because of injury or distance—to travel back and forth for water every time you need it. If you have some basic materials, making a mini-reservoir to catch rainwater (see also p. 188) solves this problem.

1. To reduce the amount of effort required, choose a site that offers the least resistance (such as a natural hollow). Dig a shallow pit using whatever materials you have to hand, such as a stick.



Choose a site that will require the least amount of effort for you to dig a hole

2. Smooth the edges of the pit and line it with waterproof material, such as a survival blanket. Weight the edges with rocks, soil, or logs, making sure that dirt can't run into the pond when it rains.



Secure the survival blanket in place using rocks

Leave the pond uncovered when it rains, but cover it at other times to reduce evaporation

WATER HYGIENE

Water stored in a mini-reservoir for any period of time will need to be filtered and purified before it's safe to drink (see pp. 200–01).

TREATING WATER

WITH THE EXCEPTION OF rainwater, all other water procured in a survival situation should be treated before it is safe to drink to remove or destroy harmful pathogens and microorganisms that could lead to gastrointestinal illness.

FILTERING WATER

If you don't have a device that filters and disinfects the water, you will have to accomplish the same task in two stages. Before purifying the water, you will have to filter it to remove any debris. You could use the popular Millbank bag (see opposite), but it may be necessary for you to construct your own improvised filter.

MILLBANK BAG
Used extensively by military forces around the world, the Millbank bag is an effective water filter that packs down small and can be used many times to produce large quantities of filtered water. Set up the bag as soon as you arrive in camp, because the process is quite slow: the Millbank bag will filter 1 liter (2.1 pints) of water in five minutes. Note that water filtered in this way will still need to be purified.

BUILDING A TRIPOD FILTER

If you're not carrying a filtration system with you such as a Millbank bag, you could make an improvised filter. All you need are three sticks to form a tripod, and some materials to create three separate layers.

1. Use three sticks or a bent sapling to form a tripod. Using any materials you have, form layers, starting at the top with the coarsest material and working your way down using finer materials—such as parachute silk or nylon—as you go.

2. Pour water into the top layer. It will become filtered as it passes through the increasingly fine materials.


Build a tripod out of three sticks of equal length
Add layers of material inside the tripod frame
Pour water into top layer
Collect filtered water in a container

MAKING A BOTTLE FILTER

To make an improvised bottle filter, take a container, such as a plastic bottle, and cut off the bottom (or make a hole). Note that a sock used in the same manner is still effective.

1. Hang the bottle upside down from a branch. Fill the bottle with layers of different materials working from coarse to fine as you work your way down the container.

2. Pour the water into the top end of the bottle and allow it to work its way down through the layers.


Coarse gravel
Fine gravel
Coarse sand
Charcoal fragments
Fine sand
Different layers of materials, working from coarse to fine
Fine porous material, such as a piece of cloth, forms the final layer of the filter
Emerging filtered water needs to be purified before drinking

DISINFECTING WATER

If you drink untreated water, you run the risk of becoming infected with a water-borne disease (see p. 187), so it's vital that you treat any water first. If you have the ability to start a fire, the most effective way of making water safe to drink is by boiling it. However, if you are unable to make a fire, there are several devices available that are capable of filtering and purifying water to make it safe for drinking.

MINI PORTABLE WATER PURIFIERS

These are specially designed units that filter the water and then purify it, by pumping the contaminated water through either microfilters, chemicals, or a combination of both. Sizes vary from small emergency pumps capable of purifying up to 13 gallons (50 liters) of water, to larger units that can filter huge quantities of water.



Pump handle draws water through the pump

Drinkable water will flow from the output tube

Filter input tube is lowered into water that requires treatment

OTHER METHODS

If you can't boil water, or if you don't have a water-purification device, you'll have to rely on non-mechanical techniques. The concentration and contact time required for some of these methods is dictated by the quality and temperature of the water being treated.

GRAVITY/PRESSURE FILTERS

These devices are incorporated within drinking bottles. The water is either allowed to flow naturally through the system via gravity, or is squeezed through by the operator. All bottles of this type usually employ: a filter to remove sediment and organic contaminants; a micron filter to remove protozoa; and a chemical that kills water-borne bacteria and viruses.



The filter system is housed inside a water bottle

Water passes through a filter which removes debris and water-borne diseases

SURVIVAL STRAWS

Compact emergency water purifiers, survival straws contain a filter system and employ either carbon or iodine resin systems to eliminate water-borne diseases and harmful chemicals. You need to get the water to a point where you can reach it with your straw. If you want to draw a supply of water to carry with you, you'll have to draw the water into your mouth and decant it into a container—a laborious process.



The filter end of the straw can be placed into any accessible non-saline water source

Water is sucked through the straw

"BIG BUBBLES, NO TROUBLES"

Microorganisms and virtually all intestinal pathogens are killed at temperatures well below boiling point. The process of bringing water to the boil is sufficient to disinfect it—continuing to boil it just wastes fuel, time, and water.

METHOD	DESCRIPTION
Iodine (Liquid and Tablets)	Iodine—which destroys bacteria, viruses, and cysts—can be used to disinfect water effectively and conveniently. Its action is dependent on its concentration, the water temperature, and duration of contact—a concentration of 8 mgs per liter at 68°F (20°C) will destroy all pathogens if left for ten minutes.
Chlorine tablets	Chlorine-based tablets will destroy most bacteria, but are less effective for viruses and cysts. They are more effective when used in combination with phosphoric acid and will destroy both Giardiasis and Cryptosporidium.
Potassium Permanganate	Potassium permanganate can be bought at most pharmacies. Mix a few granules with your water until it turns light pink. Leave for at least 30 minutes before drinking.
Bleach	Adding unscented household bleach is the cheapest way of adding chlorine to water (it contains 5 percent sodium hypochlorite). Be careful to add just one drop of bleach per liter of water—two if the water is cloudy—and leave for at least 30 minutes before drinking. This method is not always effective against Giardiasis and Cryptosporidium.
Ultraviolet (UV) Light	When many harmful microorganisms are exposed to UV light, the process of light absorption disrupts the cell's DNA, rendering the organism harmless. The quality of the water will affect the amount of exposure to UV light required: the cloudier the water the harder it will be for UV to penetrate.
UV Passive	Fill plastic bottles with water, replace the lids, and place them in direct sunlight, preferably on a dark surface. The sun's rays will kill the bacteria that cause common water-borne diseases.
UV Active (Steripen)	A small UV purifier that is placed in pre-filtered water and activated for a short time. Some models can purify up to 1 liter (2.1 pints) of water in as little as 48 seconds.

FIND AND PREPARE FOOD

Your body converts food into fuel, which provides you with heat and energy, and helps you to recover from hard work, injury, or sickness. If you are healthy, your body can survive for weeks without food by using the reserves stored in its tissues—although you will use approximately 70 calories per hour just breathing and up to 5,500 calories a day if laboring hard.

In a short-term survival situation, food should not be your major priority. You would probably have eaten recently and, if you'd prepared properly, you should have some basic emergency food in your pack. While you may go through food withdrawal symptoms—when your stomach complains because the food it's expecting doesn't arrive—you're not going to die of starvation within a few days. However, the body will react to its fuel not being replaced: hunger, a lack of energy, and a deterioration in coordination can be expected after a few days. If the opportunity to procure food arises, it should always be taken. Eat little and often but always make sure you have sufficient water to digest it.

In this section YOU WILL DISCOVER...

- how to **cook** with **hot rocks**...
- how to **make** a **fishing reel** from a **beverage can**...
- why a **snare** must have a **perfect end**...
- how to **lasso a lizard** and **snare a squirrel**...
- that there's **more than one way** to **skin a rabbit**...
- which **grubs taste** like **scrambled eggs**...
- how to **catch** a **bird** in a **bush**...

In a long-term survival situation, your survival priorities will change and the need for food in order to simply survive will become more important. There is a thin line between food not being your priority and then subsequently finding that you're in no physical condition to do anything about it when it does become a priority—you should regularly reassess your situation and alter your plans accordingly. It takes effort, skill, and a certain amount of luck to obtain food in the wild, especially if you're not in your natural environment.

When gathering food in the wild, always ensure that the energy gained from the food is more than the energy you expended in procuring it, otherwise it's a wasteful exercise.

FOOD THAT'S EASY TO FIND and gather should always be your first priority:

- **Plants** are easy to collect and, as long as they're readily available in the environment you're in, should be your first choice for food. However, make sure that you are absolutely sure that they are edible—mistakenly eating the wrong leaf or berry could cause vomiting and diarrhea, making your situation worse.
- **Fishing** requires little effort once the lines or traps have been set, and they will work for you around the clock. Fish is high in protein and relatively simple to prepare and cook.
- **Insects, reptiles, and amphibians** may also be available, but be careful that you don't expend more energy in catching them than you gain in nutrients from eating them. Remember also that many insects, snakes, and amphibians are poisonous, but they can still be used as bait for fish and mammals.
- **Birds and mammals** have their own survival mechanisms and are wary of humans, especially in remote areas where contact with humans is limited. Even if caught, the bird or mammal will need to be killed, plucked or skinned, and cooked.

> “Always ensure that the **energy gained** from the **food** is **more than** the **energy you expended** in **procuring it**, otherwise it's a **wasteful exercise**”

WILD COOKING

IN A SURVIVAL SITUATION, you must cook every item of food that you're not sure about in order to kill any parasites or harmful bacteria. While cooking reduces the nutritional value of food, it does help to improve the taste of many wild foods and to make them more digestible than if eaten raw.

COOKING OVER AN OPEN FIRE

Use the fierce flames of a fire to boil water then, when the flames have died down, use the steady heat of the embers to cook on (see p. 121). The most basic method of cooking is roasting, using a spit made from green wood to suspend the food over a fire. Make sure the meat is thoroughly cooked.

BOILING OR STEWING

When you boil food, fat and natural juices are retained in the water. It is important to drink the water to obtain the maximum nutrition from the meal, unless you have been boiling toxic substances out of the food.

FOUND MEAT

If you find a dead animal, you can eat the meat if you cut it into small pieces and boil it for 30 minutes. Don't touch it if you have cuts on your hands—you don't know how it died.



Lash three sticks together to form the tripod

Forked stick allows you to adjust the pot height above the fire

A tripod is a very stable and therefore safe way to suspend a cooking pot over a fire

Wait until flames die down a little before you begin cooking

DAMPER BREAD

This simple method for making yeast-free bread was developed by stockmen working out in the Australian bush.

1. Mix flour and water (and a pinch of salt, if you have it) into a pliable dough, then roll it into a long, thick sausage shape.



Roll dough between your hands

2. Wind the dough around a stick, then hold it over the embers of a fire, turning regularly until it browns. It will slide easily off the stick when cooked.



Use a green stick, which is less likely to burn

STEAMING FOOD

Steaming leaches fewer nutrients away than boiling and is a particularly good way of cooking fish and green vegetables—fresh leaves will be ready to eat in just a few minutes. To steam food, it must be suspended above boiling water in some way.

BAMBOO STEAMER

Bamboo stems are tough, hollow, and divided into sections. Use a sharp stick to make small holes in the walls dividing a three-section piece of cane, leaving the wall at the base intact. Pour water into the stem until it's just below the bottom section ring. Add food to the top section and cover with grass and a loose-fitting bamboo lid. Lean the stem over a fire, propping it against a forked stick.



Steam rises up stem through holes in dividing walls

Place grass on top of food to retain heat and cover with a lid

Food to be steamed is placed in top section

Water boils in bottom section

CLAY BAKING

Baking food in clay requires no cooking utensils. Animals must be cleaned and gutted first, but can otherwise just be covered in soft clay. When the meat is cooked, skin, spines, or feathers will remain embedded in the clay. Cooking root vegetables or fish in this way removes their skins, losing valuable nutrients, so it's best to wrap them in leaves first.


Protect nutritious skin of fish by wrapping in fresh leaves
Select long, wide green leaves

① Wrap the food in a bundle of fresh green leaves and tie them in place with some long strands of grass to make a secure parcel. Use only leaves from plants that you have identified as non-toxic.

② Cover the food parcel with an even layer of clay, making sure it's well sealed.


Layer of clay is 1 in (2.5 cm) thick


Build a fire on top of clay to increase the heat and decrease the cooking time
Heat from embers radiates through clay to the food

③ Place the parcel of clay in a bed of hot embers and build a fire up on top of it. Cooking time will be between 30 and 60 minutes, depending on the size of the food item. Break open the clay and remove the food.

COOKING WITH HOT ROCKS

Rocks take a while to heat up but they stay hot for a long time, allowing food to bake steadily on them. To reduce cooking time, cover the food with some birch bark or a flat piece of wood. When cooking on rocks, don't use slate or other layered rocks as they are likely to shatter when heated. Another method of cooking with hot rocks is to place them in a pit. The food is covered with leaves and placed on the rocks, then the pit is filled in to retain the heat. The food is left buried until it is ready to eat.


Use sticks from hard-wood trees such as oak or birch
Don't use wet rocks – they may explode as they heat up

① Place some large, reasonably flat rocks close together. Light a fire on top of the rocks using some tinder and dry sticks, then leave the fire to burn down to hot ashes while you prepare your food.


Hottest rocks are in the middle

② Brush the embers and ash off the rocks, taking care not to touch the rocks with your hands as they will now be extremely hot.


Fish should be gutted but otherwise can be cooked whole

③ Place food on top of the rocks to bake. The hottest rocks will be in the center, so items that must be cooked more slowly should be put near the edges. Keep adding more food to cook until the rocks have cooled.

EDIBLE PLANTS

IN A SHORT-TERM survival situation, food is not a priority—identifying edible plants uses energy, requires knowledge and skill, and the risks of getting it wrong far outweigh the benefits. In a long-term survival situation, however, your priorities would change, so being able to identify edible plants is advantageous.

GATHERING PLANTS

When foraging for plants, take a bag or can with you and be careful not to crush what you collect. Gather only a few species to lessen the chances of mixing in something inedible or poisonous. Don't assume that because birds or mammals have eaten a plant it's safe for you to eat too. Unless you are absolutely certain, you will need to carry out the following test to find out whether a plant is edible.

WARNING!
The Universal Edibility Test (see below) does not apply to mushrooms. For this reason alone, you should never eat any mushrooms that you have gathered (especially in a survival situation) unless you are 100 percent positive that you can identify each specific mushroom as being edible. In 2008, a British woman died after eating a poisonous mushroom that had been foraged by mistake with edible mushrooms.

DIGGING FOR ROOTS

Roots and tubers are a good source of carbohydrate and their skins contain vitamins. Take care when gathering in spring as some plants will only have small shoots and will be hard to identify.

1. Cut a stick from a hard-wood tree, such as oak, sharpen one end to a chisel-shape then harden it in a fire.


Use a knife with a strong, sharp blade

2. Choose a larger plant, then dig down at its side, loosening the earth around the root until it can be pulled out in one piece.


Take care not to damage the root

UNIVERSAL EDIBILITY TEST

This test enables you to check whether a plant is safe to eat. If you're in a group, only one of you should test the plant. Make sure that you have plenty of drinking water and firewood with you (see box, right), and eat nothing for eight hours beforehand. Test only one type of plant at a time, use only one part of that plant—roots, leaves, stalk, buds, fruit—at a time, and test it in the same state in which it will be eaten: either raw or cooked. Make sure that the plant you are testing is in plentiful supply (there's no point testing it otherwise) and avoid plants with milky or soapy sap, or bright colors—they are usually Nature's warning signal.

1. First, inspect the plant—it should look fresh and in good condition. Avoid anything slimy. Next, sniff the plant. Discard it if it smells bad. If it smells of peaches or bitter almonds, it may contain cyanide.

2. Take a small portion of the plant part you're testing and gently rub it on the sensitive skin inside your elbow or wrist. Wait for 15 minutes. If no irritation, stinging sensation, rash, or swelling develops, proceed to Step 3.


If your skin reacts to the plant, wash it clean immediately

NEEDLE TEA

The needles of evergreen trees such as pine and spruce are rich in vitamins A and C and can be used to make a refreshing—and potentially life-saving—tea.

1 For each cup of tea, collect two teaspoons of fresh green needles and bruise them with a stone.

2 Drop the needles into boiling water, then let them infuse for 10 minutes. Keep the pot warm and stir occasionally.



Rub needles with a large stone

3 Strain the tea through a cloth tied over a container. Sweeten with sugar or honey, if you have any.



Needles are collected in cloth then discarded

3 Touch the corner of your mouth with the plant and wait 15 minutes. If no adverse reaction occurs, touch your lip and tongue with it. Wait another 15 minutes. If you suffer no ill effect, proceed to Step 4.



If your lips or tongue start to tingle or become numb, reject the plant

4 Place the piece of plant on your tongue, wait 15 minutes, then chew it and hold it in your mouth for 15 minutes more. If there are no ill effects, swallow the piece and wait eight hours. Eat nothing else but continue to drink water.



Place plant on tongue but do not chew or swallow it for 15 minutes

5 If no ill effect occurs, eat a quarter of a cup of the same part of the plant, prepared in the same way, then wait another eight hours. If there is no reaction, it is safe to eat. Eat little and often rather than gorging.

WHAT TO DO IF YOU HAVE AN ADVERSE REACTION

If at any stage you experience any type of adverse reaction to a plant during the edibility test, you should:

- Stop the test immediately.
- Avoid eating anything else until the symptoms cease.
- Wash the affected area thoroughly (if the reaction is external).
- Attempt to induce vomiting (if the reaction comes after eating the plant) by drinking salt water or by pushing a finger into the back of your throat.
- Drink lots of warm water (this is why you must ensure that you have a plentiful supply of purified water and firewood before you begin the test).
- Crush a teaspoonful of charcoal taken from a partially burned log and mix it into a paste with warm water, then swallow the mixture. It will either induce vomiting or, if you can keep it down, it may absorb the toxins.
- Try swallowing a paste made from white wood ash and water to reduce stomach pain.

If the tester is unconscious:

Do not induce vomiting if the tester is unconscious—get medical help and monitor the casualty.

CATCHING FISH

FISH CAN BE HOOKED, netted, trapped, speared, or even caught by hand if you're lucky. Observe their behavior—where and when they feed, and what they eat—to determine which method to try. It must be noted that some fishing techniques are illegal in some parts of the world and should only be used in a genuine survival situation.

FISHING TACKLE

Fishing equipment can be made from all kinds of material. Your survival kit should have some fishing line and a few hooks, but if you don't have a kit you can improvise. You can use a stick as a makeshift rod, for example.

IMPROVISED HOOKS

Fishhooks can be fashioned from any piece of metal, such as a nail, pin, safety pin, needle, or some wire. You can also make them from natural materials, such as thorns, hard wood, coconut shells, bone, spines, or seashells. If you don't have any fishing line you can use parachute cord (see p. 136) or make cordage from plant fibers (see p. 138).

BAIT AND LURES

Fish have a keen sense of smell to help them find their preferred food, so if one type of bait doesn't work, try another. Predatory fish are attracted to live bait by its movement—a worm wriggling on a hook, for example. You can make artificial bait out of shiny metal, cloth, or feathers. Try to imitate the fish's natural prey, such as an insect skimming across the water, to lure the fish into biting.

MAKING A FISHING REEL

You can make a reel with an empty beverage can. Tie one end of a line to the tab, then wrap it around the can until you have about 2 ft (60 cm) left. Attach a hook, float, and some sinkers. Hold the top of the can in one hand and the float in the other. Point the bottom of the can toward where you want the hook to land and throw the float. The rest of the line will unwind and follow. If a fish bites, give the line a jerk then wind it in around the can.


Line sits inside a notch

SINGLE THORN
Cut a 1 in (2.5 cm) length of bramble stem with a large, strong thorn. Tie a line to a notch at the other end.


Tie line tightly to the stems

MANY THORNS
Tie three strong thorns together securely with some fishing line. Cut a notch in the stems and attach the line.


Make a barb by tucking a splinter beneath the line tied to the twig

WOOD OR BONE
Carve a splinter of bone into an arrow point or take a sliver of hard wood, like oak, and tie to a twig.


Attach the nail securely using line

NAIL
Cut a notch at one end of a small piece of hard wood. Place the head of a nail in the notch and tie it in place.


Bend back of pin at an angle to form a barb

SAFETY PIN
Remove the safety clasp. Bend the sharp point of the pin round to form a hook. Attach line to the wire loop.

REMOVING A FISHHOOK

You should never try to remove a fishhook that is deeply embedded in flesh. Cut the fishing line as close to the hook as possible, then put a pad around the exposed part of the hook and secure with a bandage. Seek medical help as soon as possible and monitor for signs of infection. However, in a survival situation, you can try to remove the hook by doing the following:


Cut off the barbed end of the hook

① If the barb is visible, cut it off with a pair of pliers. If you can't see the barb, firmly and quickly push the hook in further until the barb emerges.



② Carefully ease the hook out by its eye. Clean the wound then cover it with a bandage.

TYPES OF BAIT

Live bait includes creatures such as:

- Worms and slugs
- Grasshoppers, crickets, and beetles
- Maggots and caterpillars
- Frogs (including large tadpoles)
- Small fish—to catch larger fish

Examples of inanimate bait include:

- Meat, guts, and reproductive organs recovered from animals
- Nuts and small fruits
- Bread, cheese, and pasta

FEATHER LURE

Make a hook, then attach it to a line. Tie a brightly colored feather just above the hook. Slowly move the lure across the water's surface to attract the fish.



FLOATS AND SINKERS

A float keeps a baited hook at the best depth to attract the species of fish you're trying to catch. A sinker (weight) placed below the hook also helps to hold it in position. Your survival kit should include a few split-shot weights but, if it doesn't, you can tie small stones to the line instead. If the float bobs below the water's surface, you may have hooked a fish.

MAKING A FLOAT

You can use any natural material that floats, such as a piece of bark or a rose hip (see below). If you find a bird's flight feather, you can make a float by trimming the feather until you are left with just the hollow quill, then folding it in half and tying the two ends together.


Make a hole in the rose hip

1 Using a sharp pin, a piece of wire, or a long thorn, pierce through the center of a rose hip.



2 Thread fishing line through the hole. If you don't have line, use a length of fine cordage.



3 Tie small twigs above and below the rose hip. These will act as stabilizers and will also prevent the float from slipping up or down the line.



4 Attach the hook (in this example, a modified safety pin) to the line at the required depth below the float. If you have one, tie a sinker below the hook.

LINE FISHING

The more hooks you can get in the water, the greater your chances of catching a fish. All the methods shown below are passive—you simply set them and leave them to work for you.

SELF-STRIKING LINE

If a fish bites at the bait, the trigger will be jerked out of the catch and the bent rod will fly up. The line will be pulled tight, embedding the hook in the fish's mouth.



ICE FISHING

First check that the ice is at least 2 in (5 cm) thick and can bear your weight, then cut a hole about 1 ft (30 cm) in diameter over the deepest part of the lake.


Ensure the ice doesn't freeze over

1 Tie a hooked and baited line to a stick with a flag at the other end and a central crosspiece.



2 If a fish takes the bait, the crosspiece will be jerked over the hole and the flagpole pulled upright.

NIGHT LINES

To increase your chances of making a catch, you need to attract fish that live at all depths. Tie a rock to one end of a line and attach hooks with live bait at intervals along it. Tie the other end to a post at the edge of the bank and throw the line in the water, leaving it there overnight.


Keep hooklines short to avoid them getting tangled

NETS, TRAPS, AND HARPOONS

You can leave a hooked line in the water, but unless you regularly check it any fish you catch may be eaten by bigger fish. In a survival situation, nets and traps are more convenient methods of fishing because once set you can leave them and they work for you all the time.

WARNING!
Gill nets and traps are illegal fishing methods in many parts of the world, so use them only in an emergency.

MAKING A DIPPING NET

Fish that are too small to hook or harpoon may still be large enough to catch with a dipping net. Such fish are usually found at the edges of streams and lakes, and around rocks in pools. You can make a simple dipping net if you can split a branch or find a forked sapling and have a mosquito net—or a spare item of clothing, such as a sleeveless vest, T-shirt, or stockings.



1 Make two small nicks in the hem of the mosquito net, vest, or stockings, then thread the forks of the sapling through them.



2 Cut another nick in the other side of the hem, where the forks meet, and pull them through. Tie the ends together with cordage, then push them back inside the hem.



3 Tie off the net (or the vest above the armholes and neck), then either cut off the excess material or invert the net. This will prevent extra drag when you use the net.

MAKING A GILL NET

Once it has been set in a river, a gill net is a highly effective way of catching fish, whether they are swimming up- or downstream. However, a gill net should only be set for short periods of time as fish of all sizes can be entangled or injured. Make the lines out of paracord or natural cordage (see pp. 136–39).


Make a loop in the middle of a length of inner paracord

1 Take a section of the outer sheath of some paracord and suspend it between two trees. Loop the inner paracord behind this line.


Tie the inner cord to the suspension line by making a prusik knot

2 Holding the two ends of the inner cord in your other hand, pass them around the suspended line and through the loop.


Prusik knot
Pull cords to tighten the knot

3 Pull the knot tight. Repeat the process every 1½ in (4 cm) along the suspended line for the required width of the net.

MAKING A HARPOON

Using a harpoon to spear fish takes time, patience, and a certain level of skill. Keep the point of your harpoon in the water to avoid splashing and scaring off the fish. Strike quickly when you see a potential catch, aiming just ahead of it. A spiked harpoon is the simplest to make.


Insert the thorny sticks into the notches

1 Gather a few short, thorny sticks to form the barbs of the harpoon. Cut a long, thick, straight branch and make notches around one end.


Wrap cordage around the sticks several times

2 Bind the thorny sticks tightly to the shaft with cordage. They will need to be able to support some of the weight of the fish so wrap them securely.


These barbs will spear the fish

3 When using the harpoon, take care not to damage the barbs by driving them against rocks or onto the riverbed. Use a dipping net, if you have one, to land the fish.

4 Make the mesh by tying a cord from one pair of cords to a cord from an adjacent pair, using a simple overhand knot (see p. 143).

■ Continue alternating along and down the line. Tie stones to the ends of the net to hold it down once it is in the water.

5 To set the gill net, hang the suspension line between trees or poles on either side of the river, submerging the net in the water to a depth of about 6 in (15 cm).

■ The net can also be used to catch birds (see p. 226).


Use these overhand knots to create the mesh



TRAPS

Fish traps can be made from a variety of materials. You can use rocks to build a wall or you can make a basket from sticks and cordage. You can even use man-made materials, such as bottles. If you only succeed in catching very small fish you can still use them as bait.

BOTTLE TRAP

Also known as a "minnow trap," this method uses a large plastic bottle to catch small fish. Cut the bottle in two just below the shoulder. Invert the neck and insert it into the cut end, then tie the two pieces together. Make holes in the plastic with a hot pin so the trap will sink. Bait the trap, then place it in a stream. Check it regularly to remove any fish caught and replace the bait.


Fish smells bait and swims into bottle but can't find its way back out
Bottle neck tied to bottle base
Holes in bottle let water in

SINGLE-WALL TRAP

If your camp is near a tidal creek, you can build a curved wall of large rocks out from the bank. Pick the location at high tide and build a low wall at low tide. Fish may be trapped in the pool created between the wall and the bank as the tide recedes.


Water and fish enter the trap at high tide
Wall prevents the fish from swimming away once the tide goes out

PREPARING FISH

ALL FRESHWATER FISH are edible but they must be cooked before eating as they are often infested with parasites and harbor bacteria. Saltwater fish are safer to eat raw, if necessary, but will taste better cooked. Never eat a fish that has pale gills, sunken eyes, flabby skin or flesh, or that smells bad.

WARNING!
When handling fish be careful not to accidentally touch your eyes. The slime may contain bacteria that can cause a painful inflammation of the eye covering (conjunctivitis). Make sure you wash your hands clean of all slime. If you have any cuts on your hands, cover them before touching the fish.

FISH HYGIENE

As soon as you have landed a fish, it should be killed and gutted, then cooked and eaten as quickly as possible, particularly in a warm climate. It doesn't take long for fish to go bad because their slimy skin provides a breeding site for flies and bacteria. In a cold climate, you can delay filleting for up to 12 hours, which will make the job easier.

FILLETING A FISH

Filleting removes the parts of a fish that might quickly go bad, while leaving as much flesh as possible. With some species, you may find it easier to remove the bones after the fish has been cooked. Boil the bones and the head to make a nutritious stock. This must be done immediately and the stock should be kept in a cool place and drunk within a few hours.


Scrape blade across skin, working from tail to head
Gills should also be removed

① Once you have killed the fish, cut its throat to bleed it and cut out the gills. Wipe the slime off its skin to make it less slippery.

- Most fish don't need to be skinned—in fact, the skin is nutritious—but eels and catfish do (see panel, opposite).

② Fish can be cooked with their scales on but, if you have time, it is best to remove them, particularly if they are large, as they can be a choking hazard.

- Hold the fish by the tail and scrape off the scales, holding the blade away from you and moving toward the head.


Keep offal to use as bait

④ Pull out the internal organs then spread the fish open to check that you have removed everything. Keep the roe to eat (it lies down the side of the fish).

- Wash the fish thoroughly, inside and out.


Use head to make stock
Slide knife under ribs to separate them from the flesh

⑤ Cut off the head, tail, and fins. Open out the body and slide the knife under the ribs to separate them from the body, working toward the head. Fish oils can make the knife slippery, so you can use your thumbs instead.

- Repeat for the ribs on the other side of the backbone.

SMALL FISH

Any fish that is less than 6 in (15 cm) long doesn't need to be filleted. After gutting, they can be fried, grilled, or roasted whole. Keeping the heads and tails on helps to prevent the fish from falling to pieces.

SKEWERING FISH

Small fish, such as perch, can be grilled over an ember fire on a skewer to make a simple, yet tasty and nutritious meal. Impale the fishes on a green stick and hold them close to the embers. They won't take long to cook.


Use a green stick as the skewer so it won't burn
Fire should have burned down to embers


Start your cut at the anal orifice
Insert only the point of the knife, blade facing upward
Slit belly up to here

3 Holding the fish with its tail toward you, insert the point of a sharp knife, blade up, into the anal orifice and slit the fish open along its belly to its throat. This prevents you from puncturing the internal organs.


Lift bones away from flesh slowly and firmly

6 Separate the top and bottom of the backbone from the flesh with the tip of your knife. Carefully pull the backbone and ribs away from the flesh in one piece.
- If you have any tweezers or needle-nose pliers, use them to remove any small bones that remain.

SKINNING FISH

Eels and catfish are tasty but have to be skinned and gutted before cooking. To gut the fish, either use the filleting method shown opposite or Step 3 below. Catfish have a cartilage skeleton and can simply be cut crosswise into steaks.


Suspend the catfish by its gills

1 Pass a stake through the gills of the fish and support on two strong uprights.
- Cut around the skin below the head with a sharp knife.
- Cut around the fins.


Tug skin down until you reach the tail

2 Separate the top of the skin from the flesh then peel the skin downward.
- You will need to use both hands to get a good grip, and a firm, steady action. If the fish is very large, you may need to slit the skin.



3 Remove the fish from the stake and break its backbone. When you pull the head off, the guts will come away with it.
- Remove tail and fins.

TRUE-LIFE ACCOUNT

EXTREME SURVIVAL—ADRIFT AT SEA

USEFUL EQUIPMENT

- Liferaft, lifejacket, survival suit
- Water catchment devices
- Solar still/reverse-osmosis pump
- Emergency Locator Beacon
- Marine VHF radio
- First-aid kit, sunscreen, sunglasses
- Flashlight and batteries
- Map, compass, GPS
- Survival tin, bushcraft knife
- Cell/satellite phone
- Poncho/bivy sack

IN 1972, A FAMILY OF FIVE SURVIVED for 38 days adrift in the Pacific Ocean. The Robertson family were 18 months into a round-the-world sailing trip when their 43 ft (13 m) wooden schooner *Lucette* sank. They survived thanks to a combination of good seamanship, improvisation, and good fortune.

The family set off from Falmouth, England, on January 27, 1971—father Dougal at the helm, wife Lynn, and children Anne (who disembarked in the Bahamas), Douglas, and twins Neil and Sandy as crew—and safely navigated the Atlantic and Caribbean. On June 15, 1972, however, about 200 miles (320 km) west of the Galapagos, disaster struck—a pod of killer whales charged the boat, splintering the hull and holing her irreparably.

With *Lucette* sinking rapidly and no time to radio a distress call, the crew launched their inflatable liferaft and roped it to the boat's 10 ft (3 m) solid-hull dinghy, the *Ednamair*, which they used as a towboat after improvising a sail. Their supplies amounted to 2 gallons (10 liters) of water, a bag of onions, oranges and lemons, vitamin-fortified bread, glucose, four fishing hooks, a fishing line, a first-aid kit, a kitchen knife, and eight signal flares. They sailed north toward the Doldrums to find rain, which they collected with the use of a tarpaulin, and caught fish, eating some of the meat raw and drying the rest in the sun to be stored as rations.

"A POD OF KILLER WHALES CHARGED THE BOAT...HOLING HER IRREPARABLY"

After 16 days, the liferaft had deteriorated to such an extent that the family was forced to transfer to the dinghy, using the remnants of the raft as a canopy to provide shelter and aid in the collection of rainwater. They used the wind and currents to sail northeast toward Central America, and built up sufficient rations over the next three weeks to provide energy for the extra exertion of rowing toward the coast. Luckily for them, there was no need—their ordeal came to an end on July 23, when a Japanese fishing boat spotted a signal flare and picked them up.

WHAT TO DO



ARE YOU IN DANGER? +

NO YES

- If you are in a group, try to help any others who are in danger
- Prepare for the possibility of abandoning ship, and try to steer closer to either land or known shipping lanes
- Delegate responsibilities
- Ensure lifejackets and liferafts are ready for deployment

Get yourself out of it:
Sinking vessel—You need water, location aids, and protection from drowning and the elements
Animals—Try not to splash in the water as this will attract sharks
Injury—Stabilize condition and apply first aid

ASSESS YOUR SITUATION

See pages 234–35

DOES ANYONE KNOW YOU WILL BE MISSING OR WHERE YOU ARE?

NO YES

If no one knows you are missing or where you are, you will need to notify people of your plight by any means at your disposal

If you are missed, a rescue party will almost certainly be dispatched to find you

DO YOU HAVE ANY MEANS OF COMMUNICATION?

NO YES

You are faced with surviving for an indefinite period—until you are located or you find help

If you have a cell or satellite phone, let someone know your predicament. If your situation is serious enough to be worthy of emergency rescue, and you have a Personal Locator Beacon (PLB), you should consider this option

CAN YOU SURVIVE WHERE YOU ARE? *

NO YES

Abandon ship in a controlled manner and deploy all the liferafts. Always try to enter the liferaft dry. Use the rescue line to reach people in distress. Follow the "immediate actions" instructions printed inside the liferaft

Address the Principles of Survival: Protection, Location, Water, Food

YOU WILL HAVE TO MOVE **

DO

- Deploy the drogue—this will lessen drifting
- Inventory all food, water, and equipment and start rationing
- Prepare water procurement devices, such as solar stills and reverse osmosis pumps
- Protect yourself from the elements—sun, wind, and salt spray
- If you have no liferaft, then huddle together in a group with children in the center. If alone, adopt the H.E.L.P. position
- Improvise flotation aids from anything that can float or hold trapped air. Good examples are plastic bags, plastic bottles, and knotted clothing

DON'T

- Cut the painter to the vessel until you know it will sink, as the vessel is what people will be looking for
- Drink seawater under any circumstances—this will only increase your rate of dehydration
- Eat unless you have sufficient water to digest the food—fish is high in protein and requires plenty of water to digest

YOU SHOULD STAY **

DO

- Ensure that the rescue services are kept aware of your situation and updated with relevant information as the situation dictates
- Prepare to abandon ship: pack lifejackets and suitable clothing
- Ensure you know how to operate your survival equipment and that you have basic aids to location such as a whistle, flashlight, or plastic water bottle on your person
- Clear the deck of loose objects and be prepared to drop sail should rescue by helicopter be attempted
- Make an inventory and ration supplies

DON'T

- Neglect to take anti-seasickness tablets. Vomiting will dehydrate you and the effects are very demotivating
- Forget to wear your survival equipment and ensure everyone knows how to operate it
- Try to second-guess the rescuers when they arrive. Do exactly as they say, they know what they are doing

+ Never abandon a vessel unless you have to—searchers will be trying to locate it. Use the vessel's equipment while you can, and before you leave collect essential items to aid your survival.
* If you cannot survive where you are, but you also cannot move owing to injury or other factors, you must do everything you can to attract rescue.
** If your situation changes (for instance, you are "moving" to find help, and you find a suitable location in which you can stay and survive) consult the alternative "Do" and "Don'ts."

TRAPPING ANIMALS

ALTHOUGH YOU SHOULD be prepared to take down sitting prey if you get the opportunity, trapping small animals is easier than hunting them—it requires less skill and energy and leaves you free to carry on with other tasks. One of the simplest traps is a snare.

MAKING A SNARE

Stainless steel snares of various strengths can be bought ready-made, with a running loop, or eye, at one end and a securing loop at the other. However, most survival kits contain a length of single-strand brass wire that can be used to make a snare.

1. Decide on the strength of snare you want (see panel, below) and double or quadruple the wire accordingly.

- Pass the strands around a stick, place it on the ground, then loop the loose ends around a second stick.
- Rotate the second stick until the strands have entwined, forming a single, thick wire. Remove the sticks.

ALTERNATIVE MATERIALS

Guitar strings make great snares as they already have a "perfect end." Natural cordage can also be used.


Hold loose ends of wire below stick resting on top of hand
Place feet on stick on either side of wire to hold it in place
Wire looped around stick on ground forms "perfect end"
Turn stick with other hand until the wire strands are intertwined

STRENGTHS OF SNARE

The single-strand wire found in most survival kits isn't strong enough to hold most animals you would want to catch. You'll need to double or quadruple the strands by winding them together to increase their strength.


"Imperfect end" has loose ends of wire
Loose ends of wire
Single strand looped around stick
"Perfect" end has no loose ends of wire
Wire folded in two then looped around stick

TWO STRANDS
A two-strand snare will be sufficient to bear the weight of a squirrel-sized animal.

FOUR STRANDS
A four-strand snare will be strong enough to hold onto an animal the size of a rabbit.

KILLING A RABBIT

Unless you're an expert, breaking a rabbit's neck by holding its head and pulling on its legs can be difficult and could result in you dislocating its hips, causing it more pain. The best method is to strike the rabbit on the back of the neck with a solid stick, thus avoiding having to pick it up and risk being bitten or scratched. The eyes will glass over immediately when the animal is dead.

LOOK AND LISTEN

To be successful at hunting and trapping, you need to decide which types of animal you are going to try to catch. To do that, you need to find out what animals are in the vicinity and where exactly they are to be found. Prey animals will use their keen senses to avoid being caught—so you will have to use your senses to find them. Look for any signs of animals, both on the ground and in the trees. And use your ears—you may be able to hear an animal even when you can't see it.

SIGNS TO LOOK OUT FOR:

- Runs, trails, and tracks
- Droppings
- Chewed or rubbed vegetation
- Feeding and watering areas
- Lairs, dens, and resting sites

SQUIRREL POLE

Make several two-strand snares with nooses 3 in (8 cm) in diameter and stake-out cords 8 in (30 cm) in length. Place them around a long pole, with the lowest 2 ft (60 cm) off the ground. If you snare a squirrel, leave it, as others will come to investigate.



Place pole against a tree that squirrels use

Cut a nick in the bark to hold the snare in position

2 To make the noose, pass the imperfect end, or securing loop, through the perfect end, or running loop. The running loop has no loose ends of wire so it won't snag in an animal's fur and prevent the noose from tightening as it struggles.

- Use a single prusik knot (see p. 210) to tie a length of cord to the securing loop.



Using wire for the snare means the noose keep its shape

Running loop, or "perfect end"
Securing loop

3 Before setting the snare, either bury it in the ground for a few hours or pass it over a flame for a few seconds to remove any human scent and dull its surface.

- Don't waste snares; always set them on runs you know the animals are using and set as many as you can.
- Use sticks to make a support from which to suspend the snare, or bend saplings into an arch.



Wrap the wire around the stick

Place the support sticks on either side of the rabbit run

Make a noose 4 in (10 cm) in diameter

Cord tied to peg anchors the snare in the ground

Set the noose 1 in (2.5 cm) off the ground

4 Avoid disturbing or treading on the run, as the disturbance or your scent could alert the animal. Camouflage the frame with vegetation, which you can also use to funnel the animal toward the snare.

- Use natural vegetation, such as holly or other prickly shrubs, to form a funnel on either side of the snare.
- The funnel helps to ensure that the animal has no option but to pass through the snare.



Branches in ground extend outwards from snare

Animal is funneled toward the snare

WEAPONS AND TECHNIQUES

A spear is the simplest weapon to make and use, but if you have the time and materials you can make more complicated weapons, although they require more skill to use. Learning other basic techniques, such as catching insects, is also invaluable when hunting.

THROWING STAR

With a throwing star you're four times more likely to hit prey than with a spear, and, if you don't succeed in wounding the animal with one of the sharp ends, the weight of the weapon will at least stun it. Keep it close at hand and ready to use, should the opportunity arise.


Cut a joint in each stick

1 Find two sticks 2 in (5 cm) thick and 18 in (45 cm) long. Make a square-cut joint in the center of each, then sharpen each end.



2 Join the sticks together by overlapping the two square-cut joints and lashing them to each other with paracord or natural cordage.


Hold at one end to throw
Weight is sufficient to kill or injure a rabbit-sized animal

3 You can exert more force if you're throwing from a standing position. Aim for the animal's legs.

RODENT SKEWER

A forked spear can be used to catch small mammals in their burrows. Thrust the pointed end into the hole. When you can feel the animal, twist the stick until you have snagged its fur, then carefully pull it out.


Use a long sapling to make the skewer
Split one end into two then separate the fork with a piece of wood
The sharp point is used to snag the animal's fur

SLINGSHOT

A slingshot can be used to kill small animals. Cut a strong forked branch and make a notch in each fork. Take the rubber tubing from your survival kit (see pp. 60–61) and thread it through a piece of leather or plastic. Tie the ends of the tubing to the notches. Place a pebble in the pouch, stretch back the sling, and take aim.


Cut fork to 4 in (10 cm)
Make handle about 6 in 1 (5 cm) long

NOOSE STICK

You can use a noose stick to lasso lizards, slow-moving mammals, or roosting birds, jerking the pole to tighten the noose around the animal's neck. Use a wire or cordage snare (see pp. 216–17). When stalking prey, move slowly and very quietly.


Select a stick strong enough to partly support the animal's weight
Make the loop large enough to fit over the animal's head

EASY PICKINGS

Ants are social insects, and most species are aggressive in defense of their nest. They have a stinging bite and some species will also squirt formic acid at their attacker. However, they make a nutritious meal if gathered with care. In summer months in northern temperate regions, you can eat the larvae of wood ants. And, if you use the technique shown below, you can get the ants to do all the work of collecting the larvae together for you. You'll have to vandalize the nest, but don't remove all of it.

ANT CUISINE

Ant larvae are best fried—they taste like shrimp. Adult ants also make a tasty snack—in Bogotá, Colombia, movie theaters sell roasted leaf-cutter ant abdomens instead of popcorn.



Ants carry the larvae into the protection of the shade

Wear gloves if you have them to protect your hands

1 Place a tarpaulin in a sunny patch next to the nest. Scoop the nest material, ants, and larvae into the middle of the tarpaulin.

2 Lay some sticks on the tarpaulin, close to the edge, then fold over the sides to create shade. The ants will carry the larvae into the shade.

3 After a while, throw back the folded sides of the tarpaulin and scoop up the larvae, which look like fat grains of white rice.

CATCHING INSECTS

Many flying insects can be eaten, but catching them takes a bit of ingenuity. Crawling insects, such as ants (see above) and termites, can provide a good meal if you can collect them in sufficient quantities.

TERMITE FISHING

Termites are found in the tropics and subtropics. Some species live in vast numbers inside mounds, which they build out of mud and saliva. If a foreign object breaches the walls, the termites will attack it with their powerful jaws.



Poke stick through wall into living chamber

1 Cut a long, thin, straight stick then peel it until smooth. Push it slowly into the termite hill.



Termites cling to the stick with their jaws

2 Remove the stick and scrape off the attached termites into a container ready for frying or roasting.

NIGHT FLIERS

Nocturnal flying insects, such as moths, are attracted to light. Stretch a white sheet between two branches and peg the bottom taut above a bowl of water. Hang a flashlight behind the sheet. Insects will fly into the sheet and fall into the water.



Ties at corners keep sheet taut

Stunned insects fall into water and drown

PREPARING SMALL MAMMALS

PARASITES SUCH AS FLEAS and lice will leave the body once a warm-blooded animal is dead so, if your circumstances permit, leave the carcass to cool before preparing it for cooking. In a hot climate, place the body in the shade. However, don't let it get too cold, as skin is more easily removed when a body is warm.

WARNING!
Rabbits, hares, and rodents may be infected with a bacteria called tularemia, which can be fatal to humans. Do not touch these animals with your bare hands if you have a scratch on your skin. If you have no gloves, cover your hands in soap lather before handling the animal, and wash your hands when you have finished. The germ is destroyed by heat, so cook the meat well. Myxamatosis, a viral disease that affects rabbits' mucous glands, is not harmful to humans.

RABBIT-SIZED MAMMALS

The method shown here applies to all furred mammals approximately the same size as a rabbit. Before gutting the animal, remove any urine by holding the body by the forelegs and progressively squeezing down from the chest toward the bowels, making sure that you direct the spray away from your own body. You'll need to remove any scent glands, which are usually inside the forelegs or around the anus, in case the musk taints the meat (take particular care when handling a skunk).

GUTTING

No part of a mammal carcass should be wasted. If your camp is near water, keep the guts for fish bait. The offal should be removed carefully and eaten if healthy—discard any organ that's pale or spotty. Liver is rich in essential vitamins and minerals and needs little cooking. It should be eaten as fresh as possible (removing the gall bladder from the middle first). Kidneys, which in most mammals are surrounded by fat, are also a valuable source of nutrition.



Pinch up the skin before knicking it with your knife

1. Place the animal on its back on clean ground, such as a bed of pine boughs, with its head pointing toward you. Cut a small hole in its belly with the point of your knife, taking care not to pierce the guts.

WARNING!
Rabbits make an easy meal, but their flesh lacks fat and vitamins so, if your diet consists entirely of rabbit, your body will use its own vitamins and minerals to digest the meat. These are then lost from your body in your feces and, if not replaced, you'll get diarrhea and so become hungry and weak. Eating more rabbit makes the condition worse and you will eventually die of starvation. You must supplement your diet with some vegetation and fatty food.



2. Pull the skin apart at the cut and insert a finger from each hand into the opening.



3. Prise open the belly to expose the guts; remove them along with the heart, liver, and kidneys. Wash your hands before moving on to skinning.

SKINNING

If you wish to keep the skin for use later (to make a pair of mittens, for example), you should remove it as carefully as possible. You'll also need to cure it; stretch the skin as tight as possible and leave it in the sun or hang it close to the heat of a fire to dry. Rubbing wood ash into the skin will help to speed up the process.


Hold the muscle down with your fingers

① Beginning at the belly, separate the skin from the muscle surrounding the gut cavity. You'll find that it pulls away quite easily. When you have reached the back on one side, repeat the process on the other.

GLOVE SKINNING

The preferred survival method of skinning and gutting a rabbit-sized mammal is to suspend it by its rear legs from a strong branch as this keeps the animal off the dirty ground.

- If you have no knife to hand, snap off the lower part of a foreleg and use the sharp edge of the broken bone to cut the skin.
- Gut the animal, then cut the skin around all four paws and between the rear legs.
- Tug the skin down toward the head.
- If you wish, pull the skin over the head. Otherwise just cut the head off.


Hang the animal by the knee tendon

Skin the mammal in the same way you would peel off a glove


Hold body clear of skin with one hand

② Hold the flesh away from the skin with one hand and pull the skin over the rear legs, one by one. The hindquarters are now free of skin and fur, except for the tail, which should be cut off and the scent glands removed.


Pull skin off the body as far as the head

Hold body off the ground

③ Hold the animal by the rear legs and pull the skin forward, easing out both forelegs. Pull the skin over the neck and then cut off the head. Wash the body to remove any traces of fur.

HOW TO SKIN A SQUIRREL

Squirrel flesh is tender and tasty. Once you have skinned the squirrel, you can simply skewer it on a spit and roast it whole over a fire. Alternatively, you can cut the meat into pieces and make a stew. A large squirrel will feed two people.



① Gut the squirrel following the method shown opposite. Cut the skin around the paws, then cut through the skin across the middle of its back.



② Insert two fingers under the skin on either side of the cut and pull the two pieces apart and off the body. Wash off any traces of fur.

PREPARING LARGE MAMMALS

ALL LARGE MAMMALS are edible, but you must not eat the livers of polar bears or bearded seals as they contain toxic levels of vitamin A. Wild game is sometimes infected with roundworm larvae and, if you eat the meat raw or undercooked, it will infect you with parasites, so always cook all wild game thoroughly.

PREPARING THE KILL

Lifting large animals, such as deer, uses energy so, if you're alone, prepare the carcass on the ground. However, if you're in a group and circumstances permit, it's best to suspend the animal by its hocks (the tarsal joints of its hind legs) from a branch, as it will bleed better and will be easier to skin and gut. If you can't find a suitable tree from which to hang it, build a frame.

WARNING!
Approach all game with caution, as the animal may still be alive and most wounded animals are extremely dangerous. To check, touch its eye with the tip of a long stick (or the muzzle of a gun). Even if the animal is unconscious, it will blink if it's alive. Always skin, gut, and butcher game at the site of the kill. You don't want the smell of fresh blood to attract predators or scavengers to your camp.

BLEEDING

Bleeding is essential to preserve the meat and stops it from tasting too gamy. It also helps to cool the carcass. Slit the animal's throat from ear to ear and let the blood drain out. Blood is rich in vitamins and minerals, including salt, so, if you're able to, collect it in a container to use later in a stew. Cover the container to protect the blood from flies and to keep it cool.

SKINNING

If you wish to preserve the hide, it's better to take the skin off before gutting. Cut the belly skin from throat to tail, cutting around the genitals. Cut along each leg from above the foot to the belly. Pull the hide off the carcass, severing connective tissue as necessary. If you're skinning on the ground and you don't want to keep the hide, you can use it to protect the meat—remove it fully only after jointing is complete.


Lift skin clear of gut cavity and guide knife with your fingers
Hold the knife sharp edge outward
Cut extends up legs to genitals
Cut skin down and around forelegs
Ventral cut extends up belly to neck
Blood drains out of slit throat
Cut skin in circle around rear legs
Cut ring in skin around genitals
Pinch up flesh to make initial incision into abdomen for gutting
Place boulder by shoulder to keep deer propped up

ON THE GROUND

Position the animal on its back on a slope with its head pointing downward. Stop the carcass from rolling by placing a boulder or log by each shoulder.

GUTTING

The method shown here is for gutting a carcass on its back. When finished, inspect the heart, liver, and kidneys for signs of worms or other parasites and, if the organs are healthy, keep them to eat. If the liver is spotted, a sign of disease, discard all internal organs and boil the meat.

1 To avoid piercing the internal organs, pinch up the abdomen near the breastbone and make an incision big enough to insert two fingers.

- Use your fingers to guide the knife, cutting toward, then around, the anus with the sharp blade-edge upward.


Slice through the muscle covering the breastbone

2 Using a saw, if you have one, cut through the outer muscle and the breastbone to open up the chest cavity.

3 Using the knife, slice through the diaphragm muscle, which separates the chest cavity from the gut cavity, getting as close to the spine as you can.

- Remove the liver, taking care not to cut the gall bladder in the center.


Ribs
Healthy liver is dark red-purple

4 Reach up through the chest cavity and cut the windpipe and esophagus. Hold them with one hand and pull out all the internal organs as one unit.

- Check that the anus is clear of feces, pushing a hand through if you can't see daylight.


Use the knife to cut organs where they adhere to body wall
Hold the top end of lungs to remove innards

KEEP THE GUTS

If you're able to carry them, take the guts, reproductive organs, and glands back to your camp in a sealed container. You can use them as bait in traplines or for fishing. Keep the fat that surrounds the intestines for cooking.

JOINTING

Large game should be cut into manageable pieces that can be carried back to camp. Boning the meat helps to reduce the weight. Bag or wrap the meat as you remove it to keep it clean and free of flies, and keep it in the shade in hot climates. How a carcass is divided partly depends on the species, but the hindquarters contain the steaks and the best cuts.


Neck and chest meat is good for stewing
Fillet steak is the most tender cut of meat
Ribs are best slow-roasted
Leg muscle is tough and should be cubed and cooked slowly
BOIL OR STEW
GRILL OR ROAST

USES FOR HIDES

Keep the skin if you can. When dried, it's light and can be used as a blanket, or it can be made into an item of clothing. Hide is one of the best materials for lashes. Sinew also makes good cordage (see p. 140).

TANNING THE HIDE

The best way to clean a skin is to stretch it on a frame and then carefully scrape off the fat and any remaining scraps of flesh, using a flint or a piece of bone. Every mammal, with the exception of buffalo, has enough brain matter for use in tanning its own hide. Mash the brains well in warm water, then apply the mixture to the hairless side of the skin and leave it to dry for 24 hours.


Stretch the skin as tightly as possible
Make the holes for the cords away from the edges of the skin

PREPARING OTHER ANIMALS

ALL TYPES OF ANIMAL should be considered when searching for your next meal. Invertebrates are far more plentiful and widespread than other animals, and take less energy to gather and prepare. Reptiles and amphibians can also provide a vital source of nutrition.

EATING FOR SURVIVAL

The thought of eating grubs or grasshoppers might not appeal, but experimentation is vital in a survival situation—don't forget that in some cultures such creatures are highly prized, if prepared properly. However, some animals are less palatable than others, in which case you should chop them finely and add to a stew.

SLUGS, SNAILS, AND WORMS

Slugs should be avoided as they often feed on poisonous fungi. To prepare snails, either starve them or feed them safe food such as wild garlic for 24 hours to purge their guts before cooking. Either boil them in water or bake them in their shells in hot embers until the juices bubble over. Avoid all marine snails and any terrestrial snail with a brightly colored shell as they may be toxic. All earthworms are edible. Place them in salty water until they are purged, then boil, though they can be eaten raw if necessary.

EDIBLE INSECTS

Insects are mostly protein and make good emergency food. Avoid any hairy or brightly colored insects or those that emit a foul smell (including larvae). As a general rule, avoid adults that sting or bite, but ants and honey bees can be eaten if collected carefully. Most insects, except those with a hard carapace, like beetles, can be eaten raw.

HOPPING INSECTS

Grasshoppers and crickets have large leg muscles, and most are quite tasty when cooked (avoid brightly colored ones). Remove the antennas, wings, and leg spurs, and roast to kill any parasites.

WITCHETTY GRUBS

Witchetty grubs are a highly nutritious Australian bush delicacy. They can be eaten raw but, if roasted quickly in hot ashes, they taste of scrambled eggs. Treat palm grubs in the same way.



Large, white grubs high in protein and calcium

AMPHIBIANS AND REPTILES

All frogs in the *Rana* genus (see pp. 292–93) are edible. Skin and then boil or roast them. The best, most meaty part is the hind legs. Don't handle or eat toads or brightly colored tropical frogs as many have highly toxic skin secretions. Lizards and snakes are a good source of protein. They must be skinned and gutted, then either roasted on a stick if small, or cut into small pieces and boiled. All snake flesh is edible—and tastes like chicken—apart from the head, which must be removed.

① Hold the dead snake firmly behind the head and cut it off about 6 in (15 cm) down the body.



Bury the head if the snake is venomous

② Slit the belly with a sharp knife and remove the entrails and other organs. Either throw them away or keep as bait.



Slice about 12 in (30 cm) along belly



If the snake isn't too big, the skin will come off in one piece

③ Peel the skin back, then grasp the body in one hand and the skin in the other and pull it off.

PREPARING A CRAB

Avoid their strong claws (tie them up if you can). To kill a crab, plunge it in boiling water or stab it through the eye socket or the orifice under the shell flap on the body. Cook the crab for about 15 minutes.


Claws contain succulent white meat

① Place the cooked crab on its back, then twist off its legs and the claws. They all contain edible meat, so crack them open with a rock.


Insert knife between the eyes

② Open the shell by inserting the point of your knife between the two halves and twisting it. Lift back the lower shell.


Feathery lungs and gills
Stomach sac sits between eyes
Creamy brown meat in upper shell

③ Remove and discard any green matter and the lungs, gills, and stomach as they're all poisonous. Scoop the meat out of the shell.

SHELLFISH

Shellfish can be found in streams and on lake and sea shores. Don't collect marine shellfish that are not covered at high tide or are near any source of pollution. Shellfish must be alive when you collect them—bivalves, such as mussels, will close their shell if you tap them, and univalves, such as limpets, will cling tightly to their rock—and you must cook and eat them immediately.

WARNING!

Tropical species of mussel should be avoided in the summer as they may be poisonous. The black mussel, which is found on Arctic and sub-Arctic coasts, may be poisonous at any time of the year. The symptoms of mussel poisoning are acute nausea, vomiting, diarrhea, abdominal pain, and fever.

HOW TO SHUCK AN OYSTER

Oysters are rich in vitamins and minerals. To eat an oyster raw, first open its shell by inserting a blunt knife into the hinge at the thicker, more pointed end of the oyster and twisting. However, in a survival situation, play safe and boil oysters in their shells for five minutes after their shells open. Do not eat any whose shells do not open during cooking.

SHRIMPS, CRABS, AND LOBSTERS

Small crustaceans, such as shrimps and crawfish, should be cooked in boiling water for five minutes. Larger crustaceans, such as some crabs and lobsters, should be boiled for up to 20 minutes. A tasty alternative to boiling shrimps or prawns is to roast them on skewers made of green wood, placed in the embers of a fire.


Handle with care as shell can be razor-sharp
Twist blade firmly to cut muscle holding shell closed


Shell turns pink when cooked
Remove head and shell before eating
Skewers stuck in the ground at an angle over the hot embers

CATCHING BIRDS

BIRDS CAN BE TRAPPED in a variety of ways—in snares, nets, tunnels, or cages—and they can be hunted with noose sticks or any projectile weapon. The trick is to observe their behavior and to match your technique—and bait—to the bird. You need to discover their regular roosts, feeding spots, and flight paths.

WARNING!
Eggs are easy to collect, particularly from ground-nesters, although gulls, for example, will attack you if you try. However, taking eggs from nests is illegal in many countries and should only be done if absolutely necessary.

FIGURE-4 CAGE TRAP

This trap enables you to catch ground-feeding birds (or rabbit-sized mammals) without killing or wounding them, so you can choose when you want to kill them and eat the meat fresh. The "Figure 4" is the trigger that's used to drop the cage over the animal.

MAKING THE TRIGGER

To construct the Figure 4 trigger you need to make three notched sticks (bait stick, upright stick, and release stick) and then link them together as shown below.


Upright stick and bait stick fit together with square-cut notches
Cage is supported by the release stick
Release stick is notched at center to pivot on upright
Notch at end of bait stick holds pointed end of release stick
Bird will peck at bait, setting off the trigger

MAKING THE CAGE

Create a pyramid of sticks by placing progressively shorter sticks across longer sticks and lashing them together at the ends. Balance the cage over the bait.

ON THE GROUND

Gamebirds, such as quail, and inquisitive scavengers, such as crows, can be lured into traps if you use the right bait. Migratory waterfowl, such as ducks and geese, molt in the late summer, which means they are easier to catch as they can't fly away.

WALK-IN TUNNEL TRAP

A tunnel trap can be used to catch gamebirds, which have stiff feathers that lie in one direction and bend only with difficulty. As a bird tries to retreat from the trap, its feathers will become wedged in the tunnel walls.

- Dig a near-horizontal, funnel-shaped tunnel close to the ground.
- Lay a trail of bait (seed or berries) leading to the rear of the tunnel.
- As it eats the bait, the bird will move deeper into the tunnel and will be unable to back out.


Bird follows bait trail
Tunnel narrows at end

ON THE WING

A fine net stretched between two trees across a flight path is an effective method of catching birds in flight. Throwing a bola requires more skill, and works by entangling the bird in the spinning ropes.

MAKING A BOLA

To make a bola, use an overhand knot (see p. 143) to tie three 3-ft (1-m) lengths of cord together about 3 in (8 cm) from one end. Find three rocks weighing about 7 oz (200 g), wrap each one in a piece of cloth, and tie it up with the free end of a cord.


Hold bola by the knot and twirl it around your head, aiming at prey
Release when bola has gained sufficient momentum

ON THE NEST

Birds are creatures of habit and will usually roost in the same place every night, such as in the branches of a tree as protection against ground predators. They rarely move once it's dark. Many birds are more accessible when breeding as, once you've located the nest, you'll always know where to find them. However, you should only take nesting birds in a genuine survival situation.

MAKING A SNARE STICK

A snare stick is used to trap birds roosting in trees. Remove a bird once it has been snared, as its squawking and fluttering will alert other birds to the danger and scare them off.

- Make several single-strand snares (see pp. 216–27) with a loop diameter of about 1–2 in (2.5–5 cm), depending on the size of the bird.
- Place them close together along a stick, making notches in the stick to hold them in position with the loops uppermost.
- Tie the stick on top of a branch where you have seen birds roosting.



Snare catches birds when they try to land on branch

BOUGH FENCE TRAP

This method is used to trap ducks, which often go ashore during the day to sun themselves, or at night to roost. They tend to favor small islands as protection against predators.

- Cut several saplings and make double-stranded snares (see p. 216).
- Place the boughs a few feet from the water's edge, and bend them into a series of overlapping hoops to form a fence around the island.
- If you only have a few snares, place them over the ducks' inward and outward tracks. Placing logs between the snares will then force the birds to pass through the hoops in order to get onto the island.
- Suspend a snare from the center of each bough arch.



Loop diameter is approximately 2 in (5 cm)

Boughs overlap

Loop of snare touches the ground

PHEASANT POLE

Pheasants roost in trees at night, usually returning to the same branch, and they won't leave once it's dark. To snare a sleeping pheasant, raise the pole up in front of it. The bird will wake and peck at the foil. As its head goes through the loop, pull the cordage and the snare will close around the bird's neck.



Silver foil or shiny paper

Lash the snare loop to the fork with something that will break easily

Lash foil stick to long forked pole

Attach cordage to snare wire

TO MAKE THE POLE

Cut a long forked pole. Tie a stick in the V of the fork and attach a piece of silver foil to it. Weakly lash the loop of a snare to the fork, then run a length of cordage down the pole from the snare wire.

PREPARING BIRDS

GAMEBIRDS AND WATERFOWL are the most commonly eaten wild birds, but all birds are edible if prepared correctly. Skinning a bird is the quickest way to get at the meat, but this removes the nutritional value of the skin, so always pluck a bird if you have the time to do so.

GETTING STARTED

If the bird hasn't already been killed by the method of capture you'll need to dispatch it—for example, by stretching its neck and cutting its throat (for the best way to kill gamebirds, see below). Whichever method you use to kill the bird, you must bleed it before plucking, but make sure you pluck it while the body is still warm.

WARNING!

Handle scavengers and carrion eaters, such as crows, buzzards, and vultures, as little as possible, because they are more likely to be infested with lice and ticks, and are prone to infection.

- The meat of such birds must be boiled for at least 30 minutes to kill any infectious organisms. This will also tenderize the meat.
- Always wash your hands after handling any bird.

KILLING GAMEBIRDS

To quickly and humanely dispatch a gamebird, such as a pheasant, fold its wings into the body and hold it under your arm. Cover its head with your jacket to calm it down (this also reduces the chances of you being injured by its claws or beak). Still holding the bird firmly, take a 2 ft (60 cm) long, thick stick and place it on the ground. Put the bird's head underneath the stick, place your feet on the stick either side of the head, and pull the bird up sharply by the legs—the bird's head will come off.

POACHER'S METHOD

The poacher's way to quickly get the meat from a dead pheasant that hasn't been decapitated is to place it face down on the ground with its head toward you, put a foot on each wing, take hold of the legs, and pull up sharply. This motion will tear the legs and breast meat away from the rest of the bird. Give it a sharp flick to detach the guts. In a survival situation, this is a good way to get meat off the bird if you don't have a knife or razor.

PLUCKING A BIRD

It's not essential, but scalding a bird in a bucket of hot (not boiling) water for a couple of minutes usually helps to loosen the feathers; the exceptions are waterfowl and seabirds—their feathers will tighten instead. Be careful not to overscald the bird or the skin will start to cook.


Grasp only a few feathers at a time
Try not to rip the skin when removing the feathers

1 Lay the bird on its back, take a few breast feathers between your finger and thumb, and begin to pluck.

- Tug sharply, pulling the feathers away from the direction in which they lie.

2 Don't try to pluck too many feathers at once or you'll tear the skin. Work your way steadily around the front and back until you've plucked the whole body.

- Keep the feathers (unless the bird is a scavenger, see box, above) to use for tinder, insulation, or fishing lures.

OPTIONAL EXTRAS

Keep the crop (esophagus) contents of a gamebird—you can use the seeds and berries as bait to catch other birds. If the bird is female and has eggs in the oviduct, keep them and eat them. You should also eat the heart and the liver if they are in good condition; discard them if they look old or spotty, or show signs of parasites.


Liver is pale brown in color
Liver is glossy, and dark red in color
OLD LIVER
YOUNG, HEALTHY LIVER


Extend the wing to locate the elbow

③ Pluck the legs in the same way, then turn to the wings. Locate the elbows and cut off the lower wings at this joint. Pluck the upper wings.

- If the bird's head is still attached, cut it off as close as possible to the body.


Place knife blade in joint
Give knife a sharp blow

④ To remove the feet, find the ankle, insert the blade of a sharp knife into the joint, and press down hard.

- If you're dealing with a large bird, such as a turkey, hit the back of the knife with a thick stick for extra force.

DRAWING METHODS

The usual way to remove the offal from a bird (known as "drawing") is to take the crop (esophagus) out of the neck end and the rest of the offal out of the rear end. The survival method is to make a cut from the throat to the tail with a sharp knife, reach in, and pull out all the offal (see below). Should you find yourself without a knife, you can still butcher a bird by pulling the skin apart with your fingers and working your way up the breast to the neck. The offal can be removed by ripping open the skin over the belly.


Cut the bird from the throat to the tail

① Hold the bird in one hand, breast upward and with its rear end toward you. Insert the point of a sharp knife into the throat.

- Make a single incision down toward the tail, being careful to not pierce the guts.


Keep inedible offal, such as the guts, to use as bait for fishing or traplines

② Reach into the gut cavity and pull out the offal, taking care not to break any eggs. Keep the liver and heart if healthy (see above left).

- Wash the bird clean with cold water and wash your hands thoroughly before further handling.

6

IN AN EMERGENCY

IN AN EMERGENCY

You're only a survivor when you have been rescued. This means that you must be able to either get yourself out of the predicament you are in (self-rescue) or be rescued from that situation by others. Sometimes you will be able to choose whether to undertake self-rescue; at other times the decision will be out of your hands. There may be several reasons why you cannot achieve self-rescue: you could be utterly lost; local conditions such as flooding or bad weather could trap you; or injury to yourself or a group member could make movement impossible. In this situation, the onus is on you to attract attention. You must be able to make contact with rescuers, using location aids you have with you or those you can improvise. Never delay any form of rescue because of the embarrassment factor—the only important factor is the outcome, and I would always rather be embarrassed and alive than eventually found dead!

Preparation is key—informing people of your intentions and timeframes will at least have someone wondering why you are not back yet. Equally, taking the best

In this chapter YOU WILL DISCOVER...

- how to **recognize** the **enemies** of **survival**...
- why **LEOs** are so **important**...
- when to **set fire** to a **log cabin**...
- that **tinsel** isn't just for **Christmas**...
- what to **do** if a **hippo yawns**...
- that you **should go** with the **flow** in an **avalanche**...
- how to **inflate** your **pants**...

location aids for your environment and knowing how best to use them will increase the chances of you being found.

In many survival situations, a major decision will be whether you remain where you are or move to a location that offers a better chance of survival, rescue, or both. There are numerous factors that will dictate your best option but, in general, it's always best to stay where you are. It's all too easy to make a rash decision and attempt to walk out of a situation only to put yourself in even greater danger.

A location aid can make the difference between life and death. A comparatively recent invention is the multi-tasking Skystreme device.

SKYSTREME is a silver, inflatable foil kite, which weighs just 1½ oz (43 g) and packs down to a small and convenient size. It can perform four tasks in a survival situation:

Location aid The kite is orally inflated and its wedge shape means it can lift off from the ground unaided in 4 mph (6 kph) winds.

- The 165 ft (50 m) of line attached to the kite (this much cordage is invaluable in itself) allows it to rise above tree levels and reflect sunlight. It can be seen by the naked eye at a distance of 2 miles (3 km).
- At night, you can hang a small flashlight or lightstick underneath the kite to aid visibility.
- The metallic surface reflects radar and can be detected by aircraft at a distance of 10 miles (17 km). A UK Royal Marine on a polar crossing flew his Skystreme behind his sled so that support aircraft could find and track him.

Emergency first aid splint The kite can be inflated around a broken or sprained limb.

Thermal vest The kite can be inflated and put inside clothing to act as a body warmer.

Water storage Instead of being inflated with air, the kite can be used to carry and store water.

“You are not a **survivor** until you have **been rescued**”

ASSESSING YOUR SITUATION

ONCE YOU'RE OUT of immediate danger, assess your situation and plan accordingly. At this initial stage, it's crucial to think clearly—the decisions you make now could mean the difference between life and death. In most cases, remaining where you are is the preferred option, but no two situations are ever the same: the circumstances, environment, conditions, and you—the individual—all have a major impact on what can and cannot be achieved.

THE STRATEGY FOR STAYING ALIVE

In an emergency situation, think of the four priorities of survival: protection, location, water, and food. Your situation will determine which is the most important. In most cases, as long as you're in no further danger from injury or the elements, you should focus your efforts on establishing a safe location and getting yourself rescued. The strategy for staying alive, known by the acronym SURVIVAL (see below), gives you a framework to use and helps you remember what you need to do to remain alive and get rescued.

THE RULE OF THREES

A common understanding among those concerned with survival is that various key time limits have a numerical value linked to the number three. Remembering the "rule of threes" can help you focus your decision-making, particularly if you are injured, at risk of further injury, or in immediate danger from the elements. In most cases:

- **Three seconds** is the psychological reaction time for making a decision.
- **Three minutes** is the length of time your brain can do without oxygen before it suffers irreparable damage.
- **Three hours** is the critical time you can survive unprotected in extreme climates.
- **Three days** is the approximate length of time you can live without water.
- **Three weeks** is the approximate length of time you can live without food.

SIZE UP YOUR SITUATION	USE ALL YOUR SENSES	REMEMBER WHERE YOU ARE	VANQUISH FEAR
▪ First, assess the particulars of your surroundings, physical condition, and equipment. ▪ If you're in a group, you can share tasks and responsibilities, but remember that everyone will be affected by the consequences of your decisions.	▪ Most people react to a true survival situation through either training (they automatically do what they've been trained to do in a particular situation) or by instinct (they automatically do what their mind and body tell them to do).	▪ In any survival situation, it always helps to know where you are so that you can make the best decisions about what to do and where to go next.	▪ Fear and panic can be formidable enemies, so it's imperative that you have the knowledge and training to counteract them and prevent them from making your situation worse.
▪ Your surroundings: every environment has its own idiosyncrasies—hot and dry, hot and wet, cold, exposed, or enclosed. Determine what you need to do in order to adapt to that environment. ▪ Your equipment: assess your equipment and consider how it can best be used in your particular situation. ▪ Your physical condition: remove yourself and others from danger. Check for injuries and administer first aid as necessary. Remember that the trauma and stress of a survival situation may cause you to overlook, or subconsciously ignore, injuries that you yourself may have received.	▪ Whatever has happened, approach your predicament in a calm and rational manner. The situation requires careful thought and planning. ▪ If you act in haste, you may overlook important factors, lose vital equipment, or simply make matters worse. The saying "Undue haste makes waste" is especially true in a survival situation. ▪ Listen to your subconscious survival senses and gut feelings, and learn to act on them when they send you warning signals.	▪ Knowing your precise location can clarify whether rescuers are likely to find you or if you'll have to rescue yourself. You'll get a good idea of the obstacles you may face, whether you should remain where you are, and where best to position your aids to location. ▪ If you have made an Emergency Plan of Action (see pp. 24–25), someone will know your approximate location, and when you're due back. ▪ Channel your efforts into making sure that when rescuers are looking for you, your aids to location are in place.	▪ If uncontrolled, fear and panic can destroy your ability to make intelligent and rational decisions. They can cause you to react to your feelings and imagination rather than to your actual situation and your abilities. Moreover, they can incapacitate you and drain your energy, thus triggering other negative emotions. ▪ If you're in a group, your responses can have a direct effect on others—positive responses are productive and can motivate, while negative responses can undermine confidence and morale.

THE ENEMIES OF SURVIVAL

In a survival situation, there are seven factors, known as "the enemies of survival," that can work against you. In many cases, you can deal with them by knowing what they are and understanding their effects. One way to memorize these is by using a mnemonic such as: "**B**e **P**repared **T**o **F**ace **T**hese **H**ostile **F**actors".

BOREDOM AND LONELINESS

When boredom sets in, you become inactive and lose the ability to deal with your situation effectively, so you need to keep busy. Loneliness makes you overwhelmed by what you need to achieve, leading to a feeling of helplessness.

PAIN

If you're injured, don't ignore the pain. Attend to a minor injury, as it could grow into a major problem that could impair your ability to survive. A positive mental attitude coupled with keeping busy helps to distract the mind from pain.

THIRST

Thirst is not a good indicator of the body's need for water. Your body can be dehydrated before you feel thirsty. Stay ahead of dehydration, rather than have to deal with it. Prioritize your need for water in a way that's relevant to your environment.

FATIGUE

Tiredness leads to mistakes that, at best, cause frustration and, at worst, may result in injury or death. In a survival situation, it's unlikely that you'll replace the energy you use effectively, so everything becomes harder to achieve. Never underestimate the importance of quality rest to your physical and mental wellbeing.

TEMPERATURE

Temperature is a major factor in any survival situation and it will be affected by wind, rain, and humidity. You should dress to suit the environment you're in and be aware of the signs and symptoms of temperature-related injuries, such as dehydration, hypothermia, heat stress, and heat stroke (see pp. 272–73).

HUNGER

In a short-term survival situation (one to five days), procuring food is not a high priority. You can offset your reduced energy and stamina levels by drinking water and pacing yourself so you work within your limits. However, take every opportunity to procure food without expending energy.

FEAR

Fear is one of our body's greatest survival tools, as it can stimulate you, so that you're ready to act—however, it can also debilitate. Fear is good as long as you have control over it, and the key to controlling fear in a survival situation is knowledge.

	IMPROVISE	VALUE LIVING AND LIFE	ACT LIKE THE LOCALS	LEARN BASIC SKILLS
	▪ The true skill of a survivor is to understand what's required and improvise solutions to particular problems. Do you have the skills and knowledge to keep yourself alive and in a condition to be proactive in your own rescue?	▪ Some people without training and equipment have survived the most horrendous situations. In many cases, this was simply because they had the will to live and refused to give up!	▪ Whatever environment you're trying to survive in, you can be sure that the local or indigenous people and the local wildlife have developed ways of adapting to it in order to survive.	▪ Learning basic skills increases your chances of survival. Without training your prospects of survival are down to luck, which is never the best place to start. There is a saying: "Luck favors those who are best prepared."
	▪ You may start out with all the right equipment, but it may get lost or broken, or simply wear out. Your ability to improvise may mean the difference between your continued struggle to survive in relative comfort, or absolute misery. ▪ Think laterally, like the climber who was stranded on the side of a mountain with no aids to location. He used the flash on his camera to signal his location to a rescue helicopter. Improvise and overcome!	▪ The stories of prisoners of war often reveal what kept them alive: religious beliefs, thoughts of family and friends, or a determination not to let the enemy win. While these alone may not always be enough, they're certainly a key factor in any survival situation. ▪ It helps to bear in mind that hardship means different things to different people and in different cultures. ▪ Survival is about dealing with hardships and having the will to live. If the will to live is not there, then just having the knowledge and equipment may not be enough.	▪ Look at how the local people dress and act: in hot countries they leave manual work until the coolest parts of the day and work in a slow and deliberate manner to reduce sweating and therefore conserve water. ▪ If you're in a desert, for example, watch where animals go to find shade: they're mostly nocturnal and spend the day underground. Learn their tricks to find water, like the darkling beetle in the Namib Desert that drinks water from the fog that condenses on its carapace. ▪ If you're in a jungle, pay attention when the animals go quiet or quickly leave an area—danger is usually around the corner.	▪ Prior preparation is the key to survival: discover what you need to know about the environment you're going to; familiarize yourself with all your equipment; and practice your basic skills until they become second nature. This thorough preparation will help you to combat the fear of the unknown and give you the self-confidence to meet the challenges of any survival situation you may be in.

ATTRACTING RESCUERS

TO BE A SURVIVOR you need to rescue yourself or be rescued by others. If you can't rescue yourself—perhaps you're injured, completely lost, or trapped by bad weather—you must attract attention with location aids that you've either brought with you or have improvised.

AIDS TO LOCATION

Location aids can save your life, so make sure you know how to use them effectively. A helicopter on a search pattern may make only one pass over an area before moving on, so you'll only have a few minutes to act decisively.

COMMUNICATING WITH SATELLITES

When activated, a Personal Locator Beacon (PLB) transmits a radio distress signal to two complementary satellite systems called LEOSAR and GEOSAR. Together, these form the "COSPAS-SARSAT" system. The signal is then relayed to a rescue coordination center closest to the beacon's location. PLBs mainly use 406Mhz; the military also use 243.5Mhz and 282.8Mhz.

ATTRACTING ATTENTION

When you're in a survival situation, you need to employ your location aids in the best way possible. There are three main principles for attracting attention:

- **Attract:** pick a place that maximizes your chances of attracting attention using your location aids, such as open or high ground. Place your aids carefully so they can be detected from as wide an area as possible. The more obvious the signal the better.
- **Hold:** you need to hold the attention of rescuers by maintaining the signal until they indicate they've seen you. Try to send some critical information (the type of assistance you require or the number of survivors and their condition, for example) via a May Day, or Help message (see pp. 237–41).
- **Direct:** regardless of which location aids you use, once rescuers have been alerted, do all you can to direct them to your present location. If you have voice communication, direct them to your position. If you leave notes before moving on from places, make sure they contain dates and precise details of your intentions.


A satellite in "geostationary earth orbit" (GEO)
A satellite in "geostationary earth orbit" (GEO)
A satellite in "low-altitude earth orbit" (LEO)
Emergency Position Indicating Radio Beacons (EPIRBs) are used at sea
Emergency Locator Transmitters (ELTs) are mostly for use in aircraft

SHOULD I STAY OR SHOULD I GO?

You need to decide whether to stay where you are or to move to a location where you have a better chance of rescue or self-rescue. If you move on, remember the following:

- Keep your aids to location at hand. It's no good having your signal mirror at the bottom of your backpack when you may have only seconds to attract a passing vehicle or plane.
- Deploy your aids to location at the end of each day, even though it takes effort and you'll be moving in the morning.
- To show where you've been and where you're heading, leave markers, such as a note left in a visible position and visual clues on the ground or vegetation, to indicate your direction of travel.



Local User Terminals (LUTs) receive signals from the satellites and alert mission control

Mission control analyzes data from the LUTs and mobilizes a rescue operation

Search-and-rescue services are deployed to search for you



A regional rescue coordination center alerts the search-and-rescue teams

A PLB is activated manually and sends a signal to one of the search-and-rescue satellites

Personal Locator Beacons (PLBs) are for personal use and kept on the body

WARNING!
PLBs are for emergency use only and should always be used responsibly.

MOBILE PHONES AND RADIOS

Always take a cell or satellite phone with you when traveling—they are essential in an emergency. On a sea trip, take a marine VHF radio to contact would-be rescuers.



CELL AND SATELLITE PHONES

Wherever you are in the world, you can rent or buy a cell phone linked to local networks. Choose one with a GPS unit for fixing and racking your position and a camera so you can send pictures of your location and any injuries you've sustained. Alternatively, rent or buy a satellite phone that's connected to the Iridium Satellite Phone System, in which 66 low-earth orbiting (LEO) satellites provide complete coverage of Earth (including oceans, airways, and polar regions).



MARINE VHF RADIOS

All large ships and most motorized small craft are equipped with marine VHF radios. These hand-held units transmit and receive on frequencies between 156 to 174MHz—usually on Channel 16, the international calling and distress channel. Channel 9 can also be used in some places. Transmission power ranges between 1 and 25 watts, giving a maximum range of up to about 60 miles (110 km) between aerials mounted on tall ships and hills, and 5 miles (9 km) between aerials mounted on small boats at sea level. Your VHF radio should be waterproof, able to float, and kept on charge. Follow the instructions whenever transmitting and receiving on VHF.

BUILDING SIGNAL FIRES

A signal fire is a very effective way of attracting the attention of rescuers, but you do need the right materials and building one requires some effort. A well-constructed signal fire located in a good position will generate a large amount of smoke that can be seen from a long way away. Two variations—the dome and the log cabin—are shown here.

TOOLS AND MATERIALS

- Knife and saw
- Poles and long saplings
- Green vegetation
- Tinder, kindling, and fuel
- Lighter or matches

SIGNAL FIRE ESSENTIALS

Whichever signal fire you make, there are several important principles to follow in order to make it as effective as possible.

FIRE FORMATION

If you can, prepare three signal fires in a recognized formation, such as a triangle or in a straight line. If the fires are random, they could be misread as a bush fire or a group of native fires. The distance between each fire should be at least 65 ft (20 m) but needs to be dictated by how quickly you can effectively light each one in turn.

FIRE COMPONENTS

Essentially, each signal fire is composed of a ready-to-light firebase made of dry tinder, kindling, and fuel. When you add the merest spark or flame to the tinder, the firebase immediately turns into a sustainable fire.

- Site the firebase off the ground to prevent damp from reaching it, and to allow enough airflow to help it ignite more effectively.
- Cover the top of the firebase with large amounts of green vegetation and anything else that produces smoke, such as tires. The covering keeps the firebase dry.
- Place a second stack of green vegetation near the firebase and add this as the original vegetation burns out.

AT THE READY

Once you have prepared the signal fire, you need to keep the following nearby, ready for use at a moment's notice:

- Dry tinder in a waterproof container underneath the firebase.
- Hexamine fuel tablets, stove fuel, gas, paper, or birch bark to guarantee the fire gets going again if it starts to dwindle.
- Something to create a spark or flame.
- A witch's broom, made of a cleft stick stuffed with kindling or bark, next to your camp fire, so you can quickly light the broom and transfer it to the signal fire.

MAKING A DOME SIGNAL FIRE

Prepare a large fire on a raised platform under a dome-shaped structure made from bent saplings. Fueled by air from below, the fire creates plumes of smoke from the green vegetation. If you have no saplings, use poles to a make a teepee shape.


Bend two long saplings to form the dome
Peg the long poles to the ground
Lash poles to each side of the dome to steady it
Large log or rock
Four stakes steady the platform
Green wood poles act as a firebase
Stick the ends of the saplings firmly into the ground

1 Lay two long poles parallel to each other. Prop them up over a log or rock at one end, and tie them to four stakes at the other. Lay lengths of green wood side by side on the long poles under the dome, to act as a firebase.

- Bend two long saplings at 90 degrees to each other to form a dome.

4 Layer green vegetation on top of the dome to form a roof over the fire platform.

- Keep additional green vegetation nearby to add to the fire when it's alight.


Leave an access point for lighting the fire, but keep it closed so the tinder, kindling, and fuel stays dry

MAKING A LOG CABIN SIGNAL FIRE

This signal fire is known as the "log cabin" because of the way the fuel wood is stacked.

- The framework for the fire is a stack of green wood, made up of pairs of poles arranged in alternating layers set at 90 degrees to each other.
- Place an additional supply of green vegetation nearby to be used as required, but not so close that it catches fire by accident.


Green wood poles produce more smoke than dead wood

1 Lay a platform of green wood on the ground and build a firebase of dry tinder, kindling, and fuel on top.

- Build a "log cabin" over the firebase using green wood.


Pile on as much green vegetation as you can find

2 Heap green vegetation over the platform to generate thick plumes of smoke when the fire is lit.

- Leave an access point at the front to allow you to light the firebase.


Tinder, kindling, fuel, and vegetation

2 Prepare a fire (see pp. 124–25) on the platform and load it with green vegetation.

- Lay the vegetation close enough to the fuel below to catch easily when the fire is lit—but don't smother it.


Stab a thin branch or vine into the bundle, wrap it around a few times and tuck it in under itself

3 Prepare some kindling bundles which will help turn the initial flame into a fire.

- Make the bundles by breaking small, dead branches (as thick as a small finger) from the lower trunks of trees.
- Fold them into a small bundle held together with a thin branch or vine.


Make a witch's broom out of kindling or bark

5 Light a witch's broom (see panel, left) from your camp fire, take it to the dome, and light the fire.

- Use kindling bundles (see Step 3) to fuel the fire.


Orange smoke from the flare mingles with the fire smoke, increasing its visibility

6 When smoke billows upward, light a preprepared signal flare (see p. 241), if you have one, taped or tied to a long pole.

- Use the pole to position the flare as high into the smoke as you can.

OTHER RESCUE SIGNALS

As well as signal fires, there are other visual devices for attracting potential rescuers. Some are unusual and others, such as a whistle, quite obvious. Whatever device you use, you have to try to hold the rescuers' attention by persisting with your signal.

CREATING A STROBE EFFECT

LED strobe lights are compact, robust, waterproof, and are sometimes incorporated within standard flashlights. They are very powerful and can be seen from a long way away. Many strobes can be set to produce a variety of sequenced flashes, including flashing SOS in Morse Code. Even if you don't have a dedicated strobe light, you can still switch your regular flashlight on and off repeatedly to attract attention.

LIGHT WINDMILL

You can create a highly visible, illuminated "windmill" effect by whirling a chemical lightstick (cyalume) in front of you attached to the end of a cord 3 ft (1 m) long. Depending on local conditions it can be seen up to 2 miles (3 km) away—or further by an aircraft. Blow your whistle at the same time, using the International Distress Signal of six blasts over one minute, then one minute's silence. The reply is three short blasts.



Activate the lightstick and whirl it in front of you



A lightstick is filled with a luminous substance known as cyalume

TINSEL TREE

The signaling device known as a "tinsel tree" is best used when you're remaining in one place for a while. It's effective only during daylight hours, so you'll need to find a suitable and easily visible tree or bush in a sunny position.

- Cut a silver survival blanket, a roll of aluminum foil, or any reflective material into strips.
- Attach the strips to the tree so that they move in the breeze, catching the sunlight and glinting like small mirrors.



WHISTLE

Take a whistle with you when you venture out into the wilderness because sound, especially in remote areas where there's little or no noise pollution, travels incredible distances. A whistle is an item of first-line gear (see pp. 42–43), and should be kept on a cord around your neck.

SIGNALING DISTRESS

Two of the most recognized signs of distress are a little red star shooting up into the sky or a billowing cloud of orange smoke. There are many different types of signal flares and rockets, ranging from simple, handheld devices that fire flares into the sky to specialized kits designed to penetrate thick jungle canopy. Usually found in the emergency survival packs of aircraft and liferafts, flares are also available from specialized shops.

SIGNAL FLARES

One end of a signal flare has an orange-colored smoke signal for daytime use. The other end has a flare for night-time use (but it can be operated during the day, too). Remember the following:

- Follow the instructions on the outside of the device.
- Wear gloves to protect your hands.
- The heat from a flare can damage a liferaft, so keep your flare well clear when you light it.
- Don't discard flares unless you have used both ends.



Hold the signal flare as high as you can to make it more visible

GROUND-TO-AIR MARKERS

You can improvise internationally recognized emergency signals on the ground that rescuers in the air can see.

GETTING NOTICED

To make a ground-to-air marker, use anything that contrasts with the ground, such as orange lifejackets, seaweed, clothing, rocks, branches of trees, or soil.

- Whatever you use, make sure the message is big and visible from all directions.
- Check on your markers regularly.
- When appropriate, use one of the emergency codes shown below. SOS or HELP written in big letters will attract attention too.

V	■ Require assistance
X	■ Require medical assistance
N	■ No/Negative
Y	■ Yes/Affirmative
↑	■ Proceed this way (arrow points)

SIGNAL MIRROR

A signal mirror, or "heliograph," has a shiny surface that reflects the sun and sends flashes over distances exceeding 30 miles (50 km), depending on the strength of the sun, the size of the mirror, and the clarity of the air. You can even use the light from the moon when it's full. By interrupting the flashes you can send messages in Morse Code.

IMPROVISING A SIGNAL MIRROR

If you don't have a heliograph or any other mirror, try using anything with a shiny, reflective surface, such as a foil food packet, a CD, or the bottom of a beverage can.

WARNING!

Don't dazzle your would-be rescuers by continuing to flash directly at them. Using your signal mirror intermittently is more effective for attracting attention.

① Polish the base of a can to a shine with a slightly abrasive paste. You can use charcoal and water, toothpaste, or even chocolate.



Polish the concave base—it will only take a couple of minutes

② Hold the can in front of your face with the polished base facing the sun.

- Direct the flash of reflected sunlight on to the palm of your other hand to practice controlling the light.
- Aim the can toward a rescuer and send a signal, either by moving your palm up and down to interrupt the flash or by directing the flash between a "V" made with your thumb and fingers.



The V-shape helps you direct the light

Hold the can up to your eye to help direct the light

WILD ANIMALS

WALKING IN THE WILDS of Alaska and coming across a fresh deposit of bear feces is a sobering experience. It quickly dawns on you that you're potentially a part of the natural food chain. What do you have to do to protect yourself, and will it be effective or just provoke the animal? Fortunately, the survival instincts of wild animals are such that, with only a few exceptions, most animals, regardless of their size, will avoid confronting you. However, they will defend themselves by attacking you if provoked, cornered, or surprised, particularly when they have young.

FERAL ANIMALS

Wherever you go in the world there are animals that have escaped into the wild from zoos, wildlife parks, and domestic situations. These feral animals include pigs, cats, dogs, mink, and muntjacs. In many cases, they have become particularly aggressive and seem to have lost any fear of confrontation with humans. Try to find out which feral animals are common in the region you're traveling in and avoid them if at all possible.

	BEARS	BIG CATS	HIPPOS	ELEPHANTS	CROCODILIANS
ANIMAL FACTS	▪ Brown bears stand taller then black bears and weigh more. Polar bears are the largest land predator. All bears are powerful, with claws on their strong paws. Brown bears can run faster than humans. ▪ Bears are found in the Northern Hemisphere and parts of South America.	▪ Tigers are the largest cat, with lions a close second. All big cats have sharp teeth and claws. ▪ Other dangerous cats include cougars (also called pumas, mountain lions, and panthers), leopards, and jaguars. ▪ Big cats are found on all continents, except for Australasia.	▪ The hippopotamus is the third-largest animal in Africa after the elephant and white rhino. ▪ Hippos can weigh more than 3 tons. They have long, razor-sharp incisors and tusklike canines.	▪ African elephants have larger ears than Indian elephants and are more aggressive. ▪ Elephants stand up to 13 ft (4 m) tall and weigh up to 6 tons. ▪ They can reach speeds of 25–30 mph (40–48 kph).	▪ Crocodilians include alligators, gharials, and crocodiles. ▪ They can stay submerged for more than an hour at a time, can swim up to 20 mph (32 kph), and run as fast as 11 mph (17 kph) over short distances. ▪ Crocodilians live in many subtropical and tropical parts of the world.
PRECAUTIONS	▪ Look for signs of bears and check with locals about bear activity. ▪ Stow and cook food away from the campsite. Keep unused food and garbage out of reach. ▪ Avoid thickets and streams where bears rest and feed. ▪ Carry a stick, knife, or spray (see opposite).	▪ Avoid coming into contact with big cats. They are most unlikely to attack unless you provoke them or threaten their cubs. ▪ An exception is the cougar, which is responsible for an increasing number of unprovoked attacks in urban areas of North America.	▪ Avoid provoking a hippo. Many encounters are the result of hitting a partially submerged hippo with a canoe or boat. Almost all hippo attacks are fatal. ▪ Stay vigilant on or beside rivers that hippos are known to frequent. ▪ Don't get between a hippo and water.	▪ Keep away from places that elephants frequent, such as watering holes. ▪ If you do come across them, don't get too close, especially if there's a baby elephant nearby. ▪ Look for a safe place to retreat to, such as a vehicle, rocky outcrop, or a tree, before you need it.	▪ Stay away from waters and river banks where crocodilians live. Be vigilant at all times. ▪ If you need to go near the water, watch the area for at least 30 minutes first. ▪ Don't go to the same spot twice, as crocodiles may lie in wait the next time. ▪ Keep a defensive weapon, such as a knife, close by.
WHAT TO DO IF...	▪ Make a noise to let a bear know you're there. ▪ If you see a bear, stay calm. Make yourself look as big as possible by raising your arms. ▪ Walk slowly backward. Don't run. If the bear follows, stop and hold your ground. ▪ If the bear attacks, play dead, or fight back.	▪ If a big cat approaches, stare at its eyes, shout, and make a noise to confuse it. Use a spray if you need to (see opposite). ▪ Don't turn your back or run away. ▪ If a big cat sees you, do not crouch or bend down. An upright human makes less attractive prey than a four-legged animal.	▪ If you encounter a hippo, go back on your tracks and find another route. ▪ If a hippo yawns at you, he's not feeling sleepy—this is a threat. He's showing you his teeth, tusks, and jaws that can snap a canoe in half! Make every effort to escape.	▪ If an elephant squares up to you with flared ears, trumpeting, and kicking the dirt in front of it, then back away. ▪ If an elephant charges, run to your safe place (see above). ▪ As a last resort, play dead and hope the elephant loses interest.	▪ If you meet a crocodilian on land, run away. ▪ If a crocodilian does grab you, it may let go—if it does, run. ▪ If it drags you into the water, fight back. Stab under its throat with a knife, hit or poke its eyes, strike its nostrils hard, or bang the large valve at the back of its throat.

ARMING YOURSELF

If you're traveling in areas where encounters with wild animals are possible, be ready with a weapon such as a knife, large stick, or deterrent spray. Remember, avoidance is always better than confrontation.

PEPPER SPRAY

One type of deterrent spray contains the pepper ingredients capsaicin and capsaicinoids. It shoots a cloud or stream that irritates an animal's eyes. The animal usually withdraws, but take care until the danger has passed.



Press to release a two-second burst

The canister releases a spray that can reach up to 30 ft (10 m)

BEAR SPRAY CANISTER

The pepper spray is under pressure in a canister

	SHARKS	SNAKES	AMPHIBIANS
ANIMAL FACTS	▪ There are more than 450 species of shark, but only a few of them pose any danger to humans. These include great white, bull, and tiger sharks. ▪ Most attacks occur in coastal waters in the tropics and subtropics, especially where the water is murky or stirred up by the surf of breaking waves.	▪ Less than 15 percent of the 3000+ types of poisonous snake are regarded as being dangerous to humans. ▪ Depending on the snake, venom either affects the blood, the nervous system, or the heart. ▪ Snakes live in every part of the world except for very cold environments.	▪ Many frogs, toads, and salamanders secrete poison through their skin. The most poisonous frog known is the golden poison-dart frog from South America. ▪ Amphibians live where the climate is sufficiently warm and wet for them to breed.
PRECAUTIONS	▪ Avoid shark-infested waters or waters where sharks are known to feed or frequent. Ask the locals about recent sightings of shark activity. ▪ Carry something, such as a pole or spear, that you can use as a weapon.	▪ Wear long pants and boots, and cover your neck. ▪ As you walk, tap the ground in front of you with a stick to alert snakes to avoid you. ▪ Step onto logs rather than over them. ▪ At night, place your boots upside down on sticks. ▪ Don't put your hands into holes or cracks where snakes might be hiding.	▪ You can touch a poisonous frog or toad with no ill effect. The poison only takes effect if it enters your system via an open wound or your mouth or eyes. If this happens, get emergency help without delay.
WHAT TO DO IF...	▪ If you see a shark, stay calm and move to safety. ▪ If it makes a move toward you, swim away smoothly but keep watching it. ▪ If it rushes at you, hit it on the nose with whatever you have at hand. ▪ If it grabs you, aggressively strike its eyes or gills.	▪ If you come across a snake, try to remain completely still. Most snakes will instinctively move away and are more likely to attack a moving target. ▪ Don't panic. If you have a stick, slowly bring it to a position ready for use. ▪ If a snake attacks, hit it hard on the head.	▪ If contact with a poisonous amphibian is unavoidable, immediately wash the affected area. Keep the water you use away from open cuts or abrasions. ▪ Thoroughly wash your hands and don't put your fingers in your mouth or rub your eyes.

DO YOUR RESEARCH

Spend some time researching the area you'll be traveling in and find out which animals present the greatest dangers. Discover as much as you can about their habits and how best to avoid coming into contact with them.

SPOT THE SIGNS

Understand the habits of these dangerous creatures: when do they forage, sleep, and drink? What are their habits?

- Learn to recognize the natural signs that indicate their presence: tracks or prints; feces/droppings; territory markings, such as flattened vegetation where the animal rubs its scent on the ground; telltale signs, such as where bears have clawed the bark from trees.
- Be aware of other animals disappearing quickly from a watering hole, or a noisy jungle suddenly going quiet.
- Ask local people if there have been any reports of animals attacking people.
- Find out the best ways to ward off an attack or defend yourself should you have no option (see left). Adopting a certain stance or submissive posture, or avoiding or maintaining eye contact, could make the difference between safety or danger, life or death.

TRUE-LIFE ACCOUNT

EXTREME SURVIVAL—IN COLD CONDITIONS

USEFUL EQUIPMENT

- Waterproof, layered clothing
- Trekking pole or ice ax
- Collapsible snow shovel
- Light, whistle, avalanche beacon
- Tarpaulin
- Gore-Tex® gloves and gaitors
- Map, compass, GPS
- Survival tin, bushcraft knife
- Cell/satellite phone
- Poncho/bivy sack

34-YEAR-OLD ICE HOCKEY PLAYER ERIC LEMARQUE became lost in the snowy wilderness of the Sierra Nevada mountains in California after snowboarding at Mammoth Mountain ski resort. Despite being under-equipped and ill-prepared, his improvisation helped him to survive for seven days.

LeMarque was snowboarding alone late on Friday, February 6, 2004, setting off down an unmarked run of virgin powder snow just as the lifts were shutting for the day. Coming to a stop on a flat section, and with visibility reduced to just 10 ft (3 m), he realized he had lost the trail. Wearing uninsulated ski trousers and jacket, and with just an MP3 player, a cell phone with a dead battery, and wet matches, he was ill-prepared for survival, so he began to search for the trail.

LeMarque chose the wrong direction and walked away from the ski resort. Realizing he faced a night in the open, he used his snowboard to dig a crude trench, lining it with bark scraped from a pine tree for insulation from the snow. He tried to light a fire with pine needles and lint from his clothing, but his matches were too wet. He also ate pine needles and bark.

"WITH VISIBILITY REDUCED TO JUST 10 FT (3 M), HE REALIZED HE HAD LOST THE TRAIL"

Over the next five days, LeMarque walked further into the wilderness, leaving scraps of clothing for rescuers and attempting to signal to passing planes with the blue LCD screen of his MP3 player. Fortunately for LeMarque, rescuers spotted his snowboard tracks and followed it for 24 hours, finding him on February 13. He was barely conscious, dehydrated, hypothermic, and malnourished—having lost 35 lb (16 kg) in body weight—and was suffering from severely frostbitten feet, which later required both legs to be amputated below the knees. But he was alive.

WHAT TO DO

ARE YOU IN DANGER?

NO YES

If you are in a group, try to help any others who are in danger

Get yourself out of it:
Cold/wind/wet—These can quickly lead to hypothermia, so get yourself out of the elements quickly
Animals—Avoid confrontation and move away from danger
Injury—Stabilize condition and apply first aid

ASSESS YOUR SITUATION
See pages 234–35

DOES ANYONE KNOW YOU WILL BE MISSING OR WHERE YOU ARE?

NO YES

If no one knows you are missing or where you are, you will need to notify people of your plight by any means at your disposal

If you are missed, a rescue party will almost certainly be dispatched to find you

DO YOU HAVE ANY MEANS OF COMMUNICATION?

NO YES

You are faced with surviving for an indefinite period—until you are located or you find help

If you have a cell or satellite phone, let someone know your predicament. If your situation is serious enough to be worthy of emergency rescue, and you have a Personal Locator Beacon (PLB), you should consider this option

CAN YOU SURVIVE WHERE YOU ARE? *

NO YES

If you cannot survive where you are and there are no physical reasons why you should remain, you will have to move to a location that offers either a better chance of survival, rescue, or both

Address the Principles of Survival: Protection, Location, Water, Food

YOU WILL HAVE TO MOVE **

DO

- Make an informed decision on the best location to move to
- Keep hydrated by wrapping snow in a wet item of clothing and suck it as it melts—but only if you are walking or working and generating heat
- Improvise a walking staff that can be used to check depth and quality of snow, and unseen drop-offs
- Check regularly for signs of frostnip or frostbite and hypothermia
- Have aids to location accessible while moving and deployed while static
- Protect all extremities from the elements—tie gloves to cord threaded through your jacket so they don't get lost

DON'T

- Underestimate the need for water just because it is cold—you are just as likely to get dehydrated in a cold environment as in a hot one
- Post-hole through virgin snow—it is exhausting. Instead, improvise a pair of snow shoes
- Sleep directly on the ground. Ventilate your shelter and first check for natural dangers (avalanche)

YOU SHOULD STAY **

DO

- Select a suitable shelter site away from dangers. Build it big enough for you and your equipment. Incorporate a cold sink and a sleeping platform higher than the sink
- Keep cutting and digging tools in the shelter in case a very heavy snow fall or an avalanche requires you to dig your way out
- Mark the entrance to the shelter so you can find it easily
- Keep a fire going: once established, you can use it to melt snow and benefit from warmth
- Prepare all of your aids to location for immediate use

DON'T

- Use your body heat to melt snow as it lowers your body temperature and can induce hypothermia
- Breathe air onto cold hands—breath contains moisture which will then cool and conduct heat away from your hands
- Sit or lay directly on the cold ground. Use whatever is available to improvise a sitting or sleeping platform

* If you cannot survive where you are, but you also cannot move owing to injury or other factors, you must do everything you can to attract rescue.
** If your situation changes (for instance, you are "moving" to find help, and you find a suitable location in which you can stay and survive) consult the alternative "Do" and "Don'ts."

ENVIRONMENTAL HAZARDS

SOME PARTS OF THE WORLD have a reputation for sudden or extreme weather conditions, and unpredictable environmental hazards that cause havoc for everyone, not just travelers. Before you set off, make sure that you're aware of any such potential hazards in the areas you're visiting, and be ready for them, just in case.

BEING PREPARED

Many environmental hazards—from avalanches and volcanoes to forest fires, tornadoes, and hurricanes—can suddenly propel you into an emergency situation. While you can never be sure of escaping the worst excesses that Nature can throw at you, you can prepare yourself. A combination of the right equipment, local knowledge, and an awareness of evasive techniques will mean that you shouldn't have to find yourself in a survival situation thinking "if only".

COMMONSENSE ADVICE

No fail-safe guidelines will protect you from every environmental danger and hazard, but there is some commonsense advice that you will do well to heed before you venture into the wilderness:

- Check the prevailing weather conditions of your destination at the time of your journey. Log onto the internet or tune into local radio stations.
- Find out if you're heading into a particularly risky season of weather—for example, monsoons in India or hurricanes in the Caribbean.
- Take an emergency survival kit (see pp. 58–59).
- Learn the relevant survival techniques either before you go or as soon as you arrive at your destination—you may not get a second chance.
- Don't challenge Nature—it rarely loses.

EQUIPPING YOURSELF FOR AN AVALANCHE REGION

Before heading for the mountains, find out whether the prevailing conditions make avalanches more likely (see right).

- Take a collapsible shovel for moving snow and a probe for checking the depth of the snow.
- Keep some survival aids in your pockets in case you lose your backpack.
- Carry an avalanche transceiver—when activated, its signal can be detected by rescue services.


Shaft slides down over the blade

COLLAPSIBLE SHOVEL



AVALANCHE TRANSCEIVER



SNOW PROBE

SURVIVING AN AVALANCHE

There's always the danger of an avalanche on slopes that face away from the sun in the middle of winter, when a fresh layer of heavy snow sits on top of a weak layer of snow. An avalanche may be triggered when snow is disturbed by loud noises, an earth tremor, or the movement of skiers or snowboarders. Learn the warning signs, take the right equipment, and practice the emergency steps in case you get caught.

SPOTTING THE WARNING SIGNS

As you cross the snowbound mountains, hills, and valleys, look out for signs that warn of a possible avalanche:

- Convex slopes at an angle between 30 and 45 degrees.
- Slopes without trees or rocks.
- Loose, dry snow that doesn't settle.
- Soft, newly fallen snow that's more than 1 ft (30 cm) deep.
- Snow that sounds hollow.
- Snow that falls as crystals or pellets.
- Snow that falls at more than 1 in (2.5 cm) an hour.

TAKING EVASIVE ACTION

If you see or hear an avalanche, and you think it might be coming your way, take evasive action at once:

- Activate your avalanche transceiver in case you get caught in the snow.
- Try to take cover—for example, under a solid rock overhang if you can see one nearby (see below).
- If you can't find or reach suitable cover, try to sidestep the avalanche by skiing out of the way—at right angles to its potential path.


Shelter under a rock overhang
Cover mouth and nose with hands

HAZARDOUS GROUND

All kinds of local conditions can prove treacherous if you don't keep your wits about you. Walking through wetlands can be risky, as the ground can suddenly give way under foot and you can find yourself in a swamp or, worse still, a patch of quicksand.

SURVIVING A SWAMP

Freshwater swamps are found in low-lying inland areas and contain masses of thorny undergrowth, reeds, and grasses, and there may be dangerous animals, such as crocodilians and snakes. The water may be foul and mosquitoes, which can cause malaria, are often present. Moving through a swamp is difficult: you can be on solid ground one moment, and chest-deep in water the next. Where possible, try to build a raft or some kind of flotation aid to help you escape. Use the waterways to navigate your way to open water, where you have the best chance of either being seen by rescuers or finding your way back to civilization.


Lie on your back with your limbs outstretched
A branch or long pole
Colleague lies on the bank and pulls you toward safety

ESCAPING FROM QUICKSAND

If you step into quicksand, try to fall onto your back with your limbs outstretched to spread your weight. Try to get to the bank by paddling with your hands. Don't struggle as you will sink faster. If you're with someone, he or she needs to lie on firm ground and pull you to safety, reaching you with the help of a long pole, rope, or branch.


Keep your head clear of the snow
"Swim" in the snow by flailing your arms and legs to create as big a space as possible

ESCAPING FROM AN AVALANCHE

If you can't take evasive action and find yourself below an advancing avalanche with no prospect of escape, try to keep calm and remember the following advice:

- Remove the bindings from your skis and the loops from your ski poles. Put your rucksack on one shoulder, but ditch it rather than risk dislocating your shoulder.
- If you're overtaken by snow, "swim" with the flow (see above) to make a big space around you before the snow compacts and "sets". Use your hands or a collapsible shovel to clear the snow around your head and to create a space for you to breathe, as often people suffocate before they freeze.
- If you don't know which way is up, dribble saliva to find out which way is down—then dig in the opposite direction.
- Get out quickly, as time is of the essence, and shout when you hear potential rescuers to attract their attention.

ESCAPING A VOLCANIC ERUPTION

Find out if there's an active volcano in the region you're visiting. If there is, and its eruption is imminent, leave the area as soon as you can. It will pump enormous quantities of lava from the mantle below the crust and produce huge amounts of ash, toxic gases, debris, and mud. However, if you do get caught in an eruption:

- Be careful when driving to safety, as the ash and mud make roads slippery.
- Take cover to avoid the flying fiery debris, hot gases, and suffocating clouds of ash. Sulfur dioxide in the ash chokes your lungs and, when mixed with rain to form sulfuric acid, burns your skin.
- If you're caught in an ash cloud, cover your face with a wet cloth (or use a mask if you have one). Wash your skin afterward.

SURVIVING AN EARTHQUAKE

Find out if an earthquake is likely to happen in the region you're visiting. If you feel an earthquake coming:

- Get into the open, away from structures or trees that can fall on you. Then lie down.
- Stay in open ground until aftershocks and tremors have stopped altogether.
- If you're in a building, go to the lowest floor, and stay beside a wall or under a sturdy table. Turn off the gas if you have time.
- If you're in a vehicle, stop, but stay inside.

SURVIVING A FOREST FIRE

When vegetation on the ground is tinder dry, the slightest spark can start a fire that gets out of control and sweeps through a forest. A forest fire may be caused by lightning, a piece of glass focusing the sun's rays, a discarded cigarette, or a spark from a camp fire. Forest fires produce intense heat, thick smoke, and toxic gases—and they use up all the available oxygen in the air, making it impossible to breathe.

PREPARATION AND SPOTTING THE WARNING SIGNS

If you're going to a place where forest fires are a hazard, find out from local radio reports whether conditions are making them more likely. If you venture into a forest, make sure you carry a cell phone or some electronic means of signaling, and let others know your route and destination. The following warning signs may help you gain time before a fire is upon you:

- You'll probably smell a fire first, and you'll hear it crackling as it burns before you see it. If you smell a fire and you notice animals growing agitated, a forest fire may be close by.
- The smoke will help you establish how close the fire is. The direction of the smoke tells you which way the wind is blowing.



TAKING EVASIVE ACTION

If the wind is blowing toward the fire then move into it quickly. However, if the wind is behind the fire you could be in serious danger because the fire will be moving very fast.

- Try to find a river, lake, road, or natural break in the forest. Stay there until you're rescued or the fire has passed you by.
- Don't go up to high ground as fire is drawn faster uphill.
- Many forest fires spread on a wide front, so avoiding the fire by going around it may be impossible.
- If the fire is upon you, and the wall of flame is fragmented, the best course of action may be to run through the flames: take off man-made clothes (as they will melt onto you), cover as much of your skin as you can, and douse yourself in water if you have any. Take a deep breath, press a damp cloth to your mouth and nose, pick a spot where the wall of flames is thinnest, and run without stopping until you're through.
- If you're in a vehicle, stay inside. Park it as far away from the trees as possible, turn off the engine, close the windows, lie down on the floor, and cover yourself if you can.
- If escape is impossible, try to dig and bury yourself under soil. Dampen all clothing and get as low as possible.

EXTREME WEATHER

High winds and torrential rain are common seasonal occurrences across the world. From tornadoes and whirlwinds to tropical storms such as hurricanes and typhoons, these extreme weather patterns cause enormous damage and threaten many lives.

AVOIDING HURRICANES AND TORNADOES

Weather forecasts can predict approximate directions and paths of impending hurricanes and local emergency services will give advice on the predicted severity. If you're planning a trek in an area known for hurricanes and tornados, check long-range weather forecasts and be prepared to cancel or alter your plans if necessary—if you're caught in the open your chances of survival are extremely limited. If you're going to be in the wilderness during a "storm season" then take a battery- or solar-powered radio, check for weather updates, and be prepared to head back to civilization. If your home is in a tornado or hurricane area, follow the advice of local services, but most importantly be prepared with a plan that will ensure you don't get caught out.


The advancing path of the tornado's vortex
If you cannot evade a tornado, you may have to wedge yourself into a ditch or between rocks

PREPARING TO EVACUATE

The arrival of a hurricane or tornado is a time when you can find yourself in a survival situation on your own home turf. The following advice can help you prepare to evacuate.

- Secure anything outside that could be picked up by winds and cause damage, such as rubbish bins and garden furniture.
- Prepare an evacuation plan (including pets if you have them). Find out where you will evacuate to and make several route plans to the location in case roads are unusable. Fuel your vehicle as soon as a hurricane warning is forecast.
- Put together a hurricane survival pack that contains what you need for a 72-hour period. Include drinking water, a change of clothing, non-perishable food, sleeping bags, radio, flashlights, and contact numbers for family and emergency services.
- Protect your house by securely boarding up all windows and doors. Turn off the water, gas, and electricity.

STAYING PUT

If you decide to stay put, you should still follow the guidelines above. As the storm approaches, move everyone and your supplies to an underground shelter or a room without windows.

- Monitor the radio reports and comply with the advice of the emergency services.
- Don't go outside until the "all-clear" has been given.

TAKING COVER OUTDOORS

If it appears that you are, or could be, in the path of a tornado or hurricane, do everything you can to move out of its way—choose a direction at a right angle to its path.

- If you're driving but can't get out of the way, try to park in an underpass. Leave the vehicle and wedge yourself into a secure position as high as you can under the underpass. If you're in the open, shelter upwind of your abandoned vehicle, so that it does not become a hazard to you.
- If you're out in the open, head for the lowest ground and find a ditch or depression (see below), in which you can shelter, or wedge yourself between rocks.


Lie face down with your hands over the back of your head

SURVIVING AN ELECTRICAL STORM

An electrical storm may develop when warm air rises and meets colder air. Electricity sparks between water droplets in the clouds, forming lightning that takes the shortest route to the ground. The following advice will help you avoid being struck by lightning, or minimize its effects if you are:

- Avoid getting caught in open ground—seek shelter but not under a lone tree: when lightning strikes a single tree a tremendous voltage fans out from its base.
- Remain in your vehicle if there is no other cover: it acts as a Faraday Cage (a metallic enclosure that prevents the entry or escape of an electromagnetic field).
- If caught in the open: make yourself as small as possible and limit the amount of area you cover. Do not lay down or stand up, crouch down low with feet together and hands off the ground.


Keep your elbows by your side
Bend your head forward
Clasp your knees
Raise your heels from the ground

SURVIVING A FLASH FLOOD

A sudden deluge of rain doesn't always drain away quickly, instead flowing rampantly over the surface of the land in torrents, and causing flash floods. Soil, animals, vegetation, and even buildings can be quickly washed away. There may be landslides, too, and rivers may break their banks. The following advice can help in the event of a flash flood:

- If you're inside a building, move to the upper floors, taking with you essentials such as bedding, food, and matches. Unless the building is threatened, stay there until the waters have receded or you have been rescued.
- If you're outside, head for higher ground.
- Never walk or drive through a flood.
- Filter and boil water for drinking, as the sources of water around you may have been contaminated. Alternatively, collect rainwater to drink.

ESCAPING A SANDSTORM

If you can see a sandstorm coming, mark your direction of travel before it strikes and find somewhere safe to shelter—for example, behind some rocks. Face away from the direction of the wind and cover yourself as completely as you can, particularly your head, face, and neck.

SURVIVING AT SEA

THE SEA IS ARGUABLY THE HARSHEST environment of all and you could be thrown into a sea-survival situation for any number of reasons: bad weather, fire, mechanical failure, or collision. However, there's plenty of good advice to follow and equipment designed to protect you.

BE PREPARED

If you're venturing onto the open seas, you should plan for the worst and be prepared with knowledge, skills, and equipment.

KNOW YOUR VESSEL

Regardless of the size of your vessel, find out everything you can about what to do in the event of a major problem that requires you to abandon ship and take to the water. The points below are generic and may not apply to all situations or types of vessel.

LARGE PASSENGER VESSELS

If you're a passenger on a large vessel, such as a ferry, liner, or cruise ship, make sure you learn the safety procedures.

- Attend the "Abandon Ship" drills.
- Find out which emergency alarms indicate fire, collision, and abandon ship.
- Find out where the lifejackets are stowed, and how to put them on and operate them.
- Learn the escape routes.
- Locate the Emergency Lifeboat Stations and find out what your responsibilities are.
- If you have children or people with special needs with you, make sure you have a system for getting them on deck and providing them with suitable survival equipment.

SMALL VESSELS

These craft include yachts, small boats, canoes, and kayaks, so crew members need to agree on an emergency plan of action and delegate responsibilities relevant to the situation and the skills of each person.

- Know where the emergency equipment is stowed and how it's operated.
- If your vessel has an EPIRB (see p. 236), make sure everyone knows where it is and how it's operated. Those activated automatically are released hydrostatically from a bracket at a water depth of 3–10 ft (1–3 m). The buoyant EPIRB then floats to the surface and begins transmitting.
- Make sure your EPIRB has been registered so that, once the signal is detected, the rescue services know who it belongs to.
- Keep a grab bag to hand (see box, right).

SURVIVAL SUIT AND LIFEJACKET

A survival suit is designed to keep you warm and dry in extreme conditions and rough seas, and a lifejacket will keep you afloat with your head out of the water, even if you're unconscious.

PROTECTION

Survival suits and lifejackets are equipped with various protection features to help you survive in the sea.


Sea-activated light
Neoprene hood
Reflector strips on hood aid visibility
High-visibility lifejacket
Top-up valve to reinflate lifejacket
Hood and clear visor
Reflector strips are prominently positioned on lifejacket
Plastic whistle
Lifejacket harness
Rescue loop/ winching point
Watertight zipper
Water-tight cuffs
Survival suit is made from a highly visible material
Strap to prevent trapped air raising the leg while in the water

GRAB BAG

Prepare a bag that contains the minimum for your survival needs, such as:

- Emergency water
- First aid kit (see p. 260)
- Personal locator beacon (see p. 237)
- Hand-held GPS (see p. 75)
- VHF radio
- Cell or iridium phone
- Flares and signal rockets
- Reverse-osmosis pump (desalination device) (see p. 197)
- Survival kit (see pp. 60–61)
- Solar still (see opposite)

TYPES OF LIFERAFT

Single-seater and multi-seater liferafts contain similar design features and survival aids. As well as being able to accommodate more people, multi-seaters carry larger quantities of fresh water and more anti-sea sickness tablets, for example.

MULTI-SEATER LIFERAFT

Many vessels carry multi-seater liferafts in a valise or a hard container. Multi-seaters can accommodate between four and 25 people and may be open-topped or covered. Many larger multi-seaters may also include locator beacons (see p. 236), paddles, and a solar still (see below).

SINGLE-SEAT LIFERAFT

Only one person can fit into a single-seat liferaft. You can inflate it with carbon dioxide, by pumping air in manually, or by oral inflation.


Clear visor keeps spray off your face
High-visibility color
Water pockets help to stabilize the raft
Recognition light
Inflatable canopy protects against the elements
Survival instructions
High-visibility color is an aid to recognition
Emergency equipment includes bellows to inflate the floor and canopy, and a kit to repair a hole
Pressure relief valve regulates the air in the raft during hot conditions
Rainwater collector
Handles for "buddying" up several liferafts or for survivors to clip on to if there's no room in the liferaft
An inflatable floor protects against the cold sea below
Water pockets help to stabilize the raft
Boarding pier
Lines for attaching to rescue vessels
Boarding ladder
Line for drogue (see below)
Drogue

SOLAR STILL

A solar still is a light, compact, and easy-to-use device for producing drinking water from sea water. Heat from the sun evaporates the salty water inside the still. Condensation on the walls collects in a channel around the rim and is directed to a store. Depending on the prevailing conditions and the availablilty of sunshine, a solar still can produce as much as 2 liters (3½ pints) of fresh drinking water a day.


Condensed sea water drips down on the inside
Channel collects drips of distilled water
Sea water evaporates
Stabilizer keeps still upright
Store of distilled water

DROGUE

A sea anchor, known as a "drogue," is a critical piece of equipment because it helps to reduce drift and keeps the liferaft stable and seaworthy, particularly in heavy seas.

STEADYING A RAFT

A drogue stops a liferaft from overturning by creating drag that "anchors" the trailing side of the raft to the water.

- A drogue can position a liferaft either downwind or 90 degrees to the wind.
- It helps to keep the raft near the ditching location, thereby improving the chance of rescue. Even in a 2-knot current a liferaft can drift 50 miles (80 km) a day.


Parachute opens as raft moves forward
Strong line
Parachute fills with water

ABANDONING SHIP

Unless your vessel is an immediate danger to you, don't abandon it until you really need to. Even a badly damaged vessel can provide you with protection from the elements, equipment such as radios and flares, and provisions such as water and food. In addition, it is a big target for rescuers to spot. Make every effort to keep the vessel afloat.

THE DANGERS THAT AWAIT

When you do decide to abandon ship, you will be faced with the following dangers. If you have prepared yourself properly before heading out to sea, you will—in many cases, at least—be able to deal with them.

- Hypothermia brought on by inadequate clothing and exposure to wet, windy, and rainy conditions.
- Drowning because you have no lifejacket.
- Dehydration caused by a lack of water or an injury.
- Malnutrition due to a lack of food.
- Cold shock (see p. 254) due to sudden immersion in cold water.

BEFORE ABANDONING SHIP

Where time and circumstances permit, don't abandon your ship until absolutely necessary. Send a May Day signal with your name, position, group size, physical condition, and circumstances. Then carry out the following measures:

- Activate the 406 EPIRB (see p. 236).
- Ensure everyone on the vessel wears layers of clothing, and has a survival suit and lifejacket (see p. 250).
- Check the liferafts are ready for launch.
- Get the grab bag (see p. 250).
- Prepare to take the jerry-cans of water on board the liferafts.
- Fill spare containers with water.
- Gather up as much food as you can.

TAKING TO THE LIFERAFT

If you have to abandon ship, make every effort to launch all available liferafts. Even the craft that are not used will make it easier for search and rescue teams to detect the "footprint" of the survivors. They also contain additional supplies of water, flares, and other useful items.

- Many liferafts have a painter. This is a line that attaches the liferaft to the vessel to ensure it does not blow away when thrown overboard and inflated.
- Should the vessel sink, the painter has a weak link that breaks under pressure, or you can cut it.

PREVENTING HYPOTHERMIA

Getting wet greatly reduces your survival chances. At 41°F (5°C), a normally dressed person has only a 50 percent chance of surviving for one hour. You are six times more likely to survive in protective clothing.

- Climb into the liferaft carefully so that you don't get wet.
- Wear several layers of clothing to trap air. Even wet layers retain some heat around the body. Don't forget your head, hands, and feet.
- Wear a survival suit (see p. 250) to increase your survival time.


Painter line attached to vessel
Multi-seat liferaft (see p. 251)

① Move slowly and deliberately into the liferaft, keeping out of the water, and trying to stay as dry as possible. If you have to enter the water, climb down or lower yourself into it, rather than jumping.

- Look for the Day-Glo instruction patch inside the liferaft. Follow the recommended advice under "Immediate Actions" (see panel, opposite).

IN THE LIFERAFT

Once you have successfully negotiated the tricky procedure of abandoning ship and climbing into the liferaft, there are a number of actions you need to take. These are prioritized into immediate, secondary, and subsequent.

IMMEDIATE ACTIONS

- Inflate the floor of the liferaft with the bellows, while carrying out a roll call of your group to check for missing members.
- If the vessel is still afloat, keep the raft attached via the painter. Someone should be ready to cut the painter close to the vessel in case it starts to sink.
- Once clear of the vessel, set up the drogue (see p. 251).
- In difficult weather conditions, close the entrances of the raft in order to keep in heat, and keep out wind, rain, seawater, or spray.
- Bale out water, check for leaks, use the sponge to dry the liferaft, and use the leak stopper and clamps if necessary.

SECONDARY ACTIONS

- Treat the injured.
- Take anti-seasickness tablets.
- Post lookouts.
- Bring liferafts together.
- Warm up as best you can.

WARNING!

Never drink seawater, because the salt it contains will increase your rate of dehydration. If you're in hot conditions without any water, dehydration can set in within one hour.

SUBSEQUENT ACTIONS

- Delegate a leader based on experience.
- Find out who has useful skills, such as first aid and sea survival training.
- Ask everyone to look for sharp objects that could puncture the liferaft. At the same time, ask them if they have anything that could have a survival use.
- Find out what survival aids you have. Prepare aids to location (see p. 236) and show everyone how to operate them.
- Establish a routine and detail a watch system for inside and outside the liferaft.
- Delegate one member of the group to make repairs, another to keep the rations, and another to administer first aid.
- Establish how much water and food you have and start to ration in accordance with your particular situation.
- Procure water as soon as possible—don't wait until you need it. Deploy solar stills (see p. 251) and use the reverse-osmosis pump (see p. 197).


If you are helping people on board, for stability, you should straddle the entrance of the liferaft, with one leg inside and the other outside
If you are waiting to board you can hold on to the handles, or clip yourself on
Wear a lifebelt at all times


Kneel to the side of the raft and steady yourself before throwing
Throw the quoit and line at the person in the water
The person in the water aims to catch the quoit
Ring
Rescue line

② If your group does end up in the water, the first two people on board the liferaft should help others on, one at a time, lifting them under the arms.

- Don't overload the raft. Those least vulnerable can hang on to the raft's handles, or tie their lifejacket lifeline to one.

③ Look for anyone who is struggling to make their way toward you. Use the rescue line and ring to pull them to safety in the liferaft.

- Avoid entering the sea unless you have to rescue an unconscious person from the water.

TAKING TO THE WATER

About two-thirds of people who drown in open water were within 10 ft (3 m) of a safe refuge and 60 percent of them were "good" swimmers. Here are some useful tips to prevent drowning.

JUMPING INTO THE WATER

Abandoning ship can be a dangerous procedure. If you have to enter the water, climb down using ropes or nets. If you have no option but to jump into the sea, these straightforward steps should improve your chances of survival. Jumping into the water is a last resort, as you will be prone to cold shock (see box, right) and at immediate risk of hypothermia and drowning. If you have to do it, first ensure your lifejacket is fitted correctly and check the surface of the water to find a safe entry point. Watch out for people, debris, and burning fuel. If you can't avoid the fuel, swim under it and, before coming up for air, poke your hand through the surface to ensure you're clear of it. As you come up, keep your face down to protect your nose, eyes, and mouth.

COLD SHOCK

Cold shock response is the body's reaction to immersion in very cold water—for example, if abandoning a ship in winter in the North Atlantic Ocean. It is a common cause of death in such circumstances. Symptoms include gasping for breath and hyperventilation, which can lead to the inhalation of water, disorientation, panic, and the possible onset of hypothermia. A sudden increase in blood pressure and heart rate can cause cardiac problems in some people. Prolonged immersion in water will make it hard to perform physical movements, making swimming, climbing aboard a liferaft, or firing a flare extremely difficult.

- Body type or mental conditioning can help some people survive swimming in icy water.
- Dressing in layers and/or wearing a survival suit improves your chances of survival.
- Avoid entering the water if you possibly can.


Keep your mouth and nose closed
With a free hand, cross your body and grasp your upper arm or shoulder
Keep your ankles together

① Once you've decided on your entry point, stand on the lowest part of the vessel.

- Close mouth and pinch nose to stop water from entering.


Keep your shoulders back
Keep your arms locked together
Ankles crossed

② Keep yourself upright with your back straight, then jump clear of the vessel.

- Cross your ankles and lock them together before entering the water.


Pull the hood or visor of your lifejacket down over your head
Inflated lifejacket
Move upright and force your legs down

③ Once you're in the water, inflate your lifejacket.

- If you're in a survival suit, raise your arms and gently pull one seal away from your wrist to let the excess air escape.


Don't kick with your legs or feet, just float to the surface
Raise your hips to the surface of the water

④ Lie on your back and swim as calmly as you can away from hazards, such as burning fuel.

- Push your head back onto the neck of the lifejacket to help raise your hips.
- Keep your feet and knees together, and use a backward butterfly stroke to swim toward the liferaft.

IF YOU HAVE NO LIFERAFT

Even without a liferaft, you stand a better chance of surviving at sea if you're in a group. More survivors create a larger target for rescuers to see, and being with others can be good for morale.

- Collect any floating debris before it disappears with the current, as this can increase your "footprint" so that rescuers can see you more easily.
- Determine what location aids and other equipment are available and prepare these for use.
- If there are children or injured among your group, place them in the center of the group and huddle close together.
- If you are alone, get into a position known as H.E.L.P. (see below), which stands for "Heat Escape Lessening Position." This will help to keep heat within the core of your body.


Draw your knees up to your chest
Cross your ankles
Fold your arms

FLOATING FACE DOWN

Don't panic if you have to enter the water without a lifejacket. Your body's natural buoyancy will keep at least the top of your head above water. To keep your face above water, too, make small windmill motions with your arms extended. However, if the water's rough, your only option may be to float face down.

STAY POSITIVE

It's very important to remain positive and to focus on your situation right now rather than on what might happen in a few hours or tomorrow.


A relaxed person floats naturally just below the surface of the water
Raise your head above the surface
Take a deep draft of air
Hold your arms out in front of you
Scoop water with your hands
Tread water with your legs as you come up for air
Stretch out your arms and rest them on the surface
Relax your legs as you return to the floating position

1 It's important to relax, even though this seems hard when your life is in danger.

- Let your face lie in the water, and put your arms out in front of you.

2 Begin to exhale into the water as you raise your head up.

- Lift your head as it breaks through the surface and empty your lungs completely before inhaling more air.

3 With fresh air in your lungs, duck your face back into the water, keeping your mouth closed.

- Let your body float again, before you repeat the sequence.

IMPROVISING A BUOYANCY AID

If you're in the water and wearing pants, you can improvise a buoyancy aid that will help you to keep your head above water. Initially, it may be awkward to organize, but the benefit outweighs the effort involved.


Tie a knot in the two legs
Collect as much air as you can

1 Take off your pants and tie the legs together near the bottom. Tighten the knot as much as you can with your teeth.

- Flick the pants over your head from behind until they fill with air. Tread water as you do this.


Put the knot at the back of your head
Grip the waist below the water to keep air in

2 Quickly catch the waist with your hands and grip it tight to hold air in.

- Put your head between the trouser legs and float.
- You will need to repeat the process regularly.

SECONDARY DROWNING

A person who nearly drowns inhales water that can cause potentially fatal chemical and biological changes in the lungs. This is known as "secondary drowning." It can be caused by inhaling fresh or salty water—even as little as 1fl oz (30 ml). Secondary drowning may occur 24–72 hours after immersion and, while uncommon, it's not rare. Take the following precautions to guard against secondary drowning:

- Monitor anyone who has nearly drowned or has spent some time in water.
- Ask the person to take a couple of deep breaths and check for any pain or discomfort that can't be accounted for.
- Look for symptoms such as coughing, breathing difficulties, chest pain, and saliva that looks like foam.
- Make sure the person is sitting in an upright position.
- If possible, provide oxygen—the blood levels of oxygen can fall quickly—and lots of rest and reassurance.

FIRST AID

FIRST AID

Regardless of the events that put you in a survival situation, a major factor that will dictate your options and actions will be whether anyone has been injured. Someone's survival may depend on the treatment they receive at the time of the incident, and during the ongoing survival ordeal, so it's essential that everyone should be proficient and confident in basic first aid techniques. In a true survival situation, the term "seek medical help" really means "deal with it yourself." While it would be impossible to be able to treat all injuries—a task even a paramedic would find daunting without the right equipment—the vast majority can be either dealt with or stabilized using a combination of basic first-aid techniques and common sense.

The "Protection" element of the survival principles (see p. 27) applies to your situation at all times—you should continually look at the consequences of every action in relation to protection against injury. Prevention is always a better option than cure. In hot climates, being able to recognize the first stages

In this chapter YOU WILL DISCOVER...

- that **maggots** have their **uses**...
- how to **improvise goggles** to prevent **snow blindness**...
- when to **stop**, **drop**, and **roll**...
- how to treat **snake bites** and **jellyfish stings**...
- when to **eat charcoal** or drink **bark tea**...
- how to prevent **frostnip** from becoming **frostbite**...
- when to **perform** a **firefighter's lift**...

of heat stress will allow you to take action with them before they develop into life-threatening dehydration and heatstroke. In cold climates, being able to recognize the first stages of frostnip will allow you to stop it from becoming frostbite. In many cases, further injury can be avoided by adopting the basic principles detailed throughout this book, such as being able to assess the best course of action in a given situation, plan a route and move safely over terrain, and protect yourself against the elements.

The will to survive is often the only factor that determines whether you live or die—regardless of your equipment, training, knowledge, and skills.

WHEN FACED WITH everything that man and nature can throw at you, when there appears to be no hope, you'll be faced with two choices: will you accept your situation and wait and see what hand fate deals you, or will you endure the pain and discomfort and fight for you own survival?

This determination was clearly shown by Aron Ralston during a hike in Blue John Canyon, Utah. After accidentally dislodging a 800 lb (363 kg) boulder, which pinned his right arm, he was faced with a bleak outlook. After five days, aware that no one knew he was missing and having run out of water, Ralston decided to amputate his own arm with his knife, applied a tourniquet, and hiked off to safety.

In another famous example, Simon Yates took the agonizing decision to cut the rope that held his injured climbing partner, Joe Simpson (who Yates thought had died), over a crevasse in the Peruvian Andes. Incredibly, Simpson survived the fall and chose to endure. He spent three days without food and only splashes of water from melting ice as he crawled and hopped the 5 miles (8 km) back over frozen mountainous terrain to reach their camp.

> “The **vast majority** of **injuries** can be either **dealt with** or **stabilized** using a **combination** of **basic first aid techniques** and **common sense**”

FIRST AID ESSENTIALS

SAFETY IS KEY on any expedition. Before you set off, make sure that you and everyone in your party has the necessary medical equipment—especially medications. If someone is injured, he or she should be treated immediately. If you can't contact the emergency services (and if there are enough of you), one person should stay with the casualty while two others go for help.

WARNING!
Protect yourself from danger at all times. You can't help anyone if you become a casualty as well. If the area is unsafe, don't approach the casualty—get emergency help and monitor the casualty's condition from a safe distance.

BASIC FIRST AID KIT

Keep your first aid kit (see panel, opposite) dry and readily accessible. Check the seals on sterile dressings; if they're not intact they're not sterile. Replace anything you use as soon as you can.

PRIORITIES AFTER AN INCIDENT

Assess a situation quickly and methodically. Find out what happened. Check casualties for life-threatening conditions such as unconsciousness or severe bleeding (see p. 264) and treat those first.

- **Response** Is the casualty conscious or unconscious? If the casualty is responding to you, he or she is conscious. Shake the shoulders gently if you're not sure.
- **Airway** Is it open and clear? If the casualty can talk, it is. If he or she is unconscious, open and clear it (see p. 276).
- **Breathing** Is it normal? Treat any difficulty such as asthma (see p. 275). If he or she is unconscious and not breathing, call for emergency help and begin CPR (see p. 277).
- **Circulation** Are there any signs of severe bleeding? If so, treat immediately.

Once life-threatening conditions are under control, you can make a more detailed assessment. Examine the casualty methodically from head to toe. Ask how the incident occurred, as it can indicate likely injuries.


Large scissors are useful for cutting clothing
Safety pins for securing bandages
Lightweight carrier
Combined sterile dressings
Antibiotic eye ointment
Tablets such as antihistamine and paracetamol
Antiseptic cream
Disposable gloves


Take fabric, waterproof, and hypoallergenic plasters


Gauze roller bandage to secure dressings—can be washed and reused


Zinc-oxide tape can be used to secure dressings

IMPROVISED SLINGS

Hand, arm, or shoulder injuries need to be immobilized and supported in a raised position. If you don't have a triangular bandage with you, use a piece of strong cloth about 3 ft (1 m) square, folded in half to form a triangle (see p. 270). You can also use your jacket or even rucksack straps. The jacket corner "sling" is the only one that provides enough support for a hand, wrist, or forearm injury. Ask the casualty to support the arm with his or her other hand while you secure the sling.



JACKET CORNER
To support an injured forearm or hand, fold the jacket up over the arm and pin it.



BUTTON-UP JACKET
Undo one of the buttons and slide the injured arm into the opening for support.



BELT SUPPORT
Support an upper arm injury in a raised position with a belt looped into a figure-eight.



PINNED SLEEVE
Pin a sleeve to a jacket or the strap of a backpack for support.



SHOULDER STRAP
Rest a sprain by tucking your hand in your backpack strap.

PROTECTING AGAINST INFECTION

Disposable gloves prevent cross-infection between you and the casualty; they must be latex-free, since contact with latex can cause an allergic reaction. Antiseptic wipes are also invaluable when cleaning wounds.



Use alcohol-free antiseptic wipes
ANTISEPTIC WIPES

COMBINED STERILE DRESSING

This is a sealed dressing consisting of a pad attached to a bandage. It's easy to apply, and can be used as a sling. It should be taped on to your backpack strap for easy access in an emergency.


Sterile pad is sewn onto a bandage



CHECK LIST

Make sure that your first aid kit and medicines are suited to the environment you will be visiting.

BASIC KIT

- Alcohol-free antiseptic wipes
- Latex-free disposable gloves
- Alcohol gel for handwashing
- Antiseptic cream
- Antibiotic eye ointment
- Adhesive dressings—fabric, waterproof, and hypoallergenic
- Gel blister bandages
- Combined sterile dressings, or sterile pads and bandages in assorted sizes
- Roller bandages—take self-adhesive for supporting joints and gauze for securing dressings
- Two triangular bandages
- Micropore or zinc oxide tape
- Scissors and tweezers
- Safety pins
- Disposable syringes

PERSONAL MEDICATION

- Painkillers
- Anti-inflammatories
- Medical alert bracelet/pendant
- Prescription medicines such as asthma inhaler and/or adrenaline (epinephrine) autoinjector
- Antihistamines
- Anti-diarrhea medicine
- Packets of oral rehydration salts
- Hydrocortisone cream

ENVIRONMENT-SPECIFIC EXTRAS

- Malaria tablets
- Mosquito repellent
- Anti-poison-ivy cream
- Sunblock
- Tick remover
- DEET powder for removing leeches

FLESH WOUNDS

ANY INJURY THAT BREAKS THE SKIN carries a risk of infection as germs can enter the body. These can come from the cause of injury, air, dirt, or clothing embedded in the wound. In the wilderness, keeping the injured area clean can be a real challenge, but it is essential. Tetanus is a potentially lethal infection caused by bacteria that live in soil. It can be prevented by immunization, so ensure that your vaccinations are up to date.

MAGGOT THERAPY

If a wound is seriously infected and you have no antibiotics, expose it to flies for one day, then cover. Maggots will develop and eat any dead tissue. Check daily, and flush the maggots out of the wound with sterile water before they start to eat healthy tissue.

BLISTERS AND BRUISING

A blister is a fluid-filled "bubble" of skin that occurs when skin is rubbed repeatedly against a surface (a friction burn). A bruise is bleeding into the skin and surrounding tissue from a blow that does not break the surface of the skin.

HOW TO TREAT BLISTERS

The ideal treatment for a blister is to rest and wait until it has healed, but this may not be possible in a survival situation. Cover it with a gel blister dressing if you have one or, if the blister is large, you may have to pierce it to enable you to continue walking. However, never pierce a blister caused by a burn—you risk infection.



Hold the foot steady with your free hand

Keep the foot flat

Use only a sterilized needle to pierce a blister

1 If you have to burst a blister, first sterilize a needle by holding it in a flame until it's red hot, then letting it cool.

- Clean the area with water or wipes, pat dry, then pierce the edge of the blister.

2 Carefully apply pressure to the side of the blister opposite the hole made by the needle. Continue to apply pressure until all of the fluid has been squeezed out.



3 Gently clean and dry the blister, then protect the wound from infection by applying a dressing.

- Use a gel blister plaster or padded moleskin, if possible.
- Alternatively, use a pad held in place with zinc-oxide tape.



BLISTER PREVENTION

Following these simple rules when out hiking should prevent blisters from developing in the first place:

- Ensure boots or shoes fit properly and are well "broken in" before you set out.
- Always wear clean, dry, comfortable socks next to your skin. Avoid wearing two pairs as they may bunch up, increasing friction.
- Keep toenails cut short and straight.
- Remove boots and air your feet during rest periods.
- If you feel a "hot spot," treat it before it becomes a problem: stop immediately and apply moleskin, a gel pad, or zinc-oxide tape.

HOW TO TREAT BRUISING

To reduce the swelling and pain of a bruise, raise the injured area, and apply a cold compress. If you have access to cold running water, ice, or snow, soak a cloth and hold it against the bruised area for at least ten minutes. Severe bruising may indicate a more serious injury, such as a broken bone (see p. 271) or internal injury (see Shock, p. 274), which will require immediate treatment.

WOUNDS AND BLEEDING

Severe bleeding can be distressing for both you and the casualty, but it can usually be controlled by a combination of direct pressure and elevation of the injury. Remain calm and reassure the casualty while treating the wound. Treat for shock (see p. 274).

FOREIGN OBJECT IN A WOUND

Any loose foreign objects, such as pieces of dirt or gravel, should be removed from a wound, otherwise they may cause infection or delay healing. Either rinse them off with cold running water or carefully pick loose pieces off the wound with tweezers. However, if an object is embedded in a wound don't remove it, but treat as shown below.

MINOR CUTS OR GRAZES

Any break in the skin, however minor, needs to be cleaned and protected from infection. Rinse the wound with clean cold water and pat it dry. Then cover the injury; the dressing pad must be larger than the wound. For small grazes, use a plaster; for larger ones, use a sterile pad and a bandage.

NATURAL WOUND DRESSING

The birch polypore, or razorstrop fungus, which grows on the sides of old birch trees, can be used as a natural wound dressing. Cut a thin slice from the top of the fungus and secure it over the wound. If you are in any doubt about the identity of the fungus, do not use it.

1 Don't try to remove the object as it may be plugging bleeding. Control bleeding by pressing firmly on either side of the wound.

- Push the edges of the cut together but take care not to press directly on the object.
- Raise the wound above the level of the heart.



Maintain pressure either side of object

Keep injured body part raised to slow blood flow to area

2 Place a piece of gauze over the object to protect it, then build up padding on either side (rolled bandages are ideal). Bandage over the pads and the object.

- Check the circulation beyond the bandage every ten minutes (see p. 264).



Bandage over the object to prevent further injury

TYPES OF WOUND

Different types of object and force produce different kinds of wound. It's useful to identify the type of wound you or the casualty has incurred so that the correct method of treatment can be applied.

BRUISE (CONTUSION)

A blunt blow will break blood vessels under the skin, causing blood to leak into the tissues. This results in a bruise: the skin is tender, swollen, and blue-black in color.

GRAZE (ABRASION)

A friction burn from a rope, or a sliding fall, will scrape off the top layers of skin, leaving a raw, tender area. Grazes often contain embedded foreign matter.

TEAR (LACERATION)

If the skin is torn open, the wound may not bleed as badly as an incised wound, but a larger area of tissue may be damaged and vulnerable to infection.

PUNCTURE WOUND

Sharp objects such as nails or sea urchin spines can puncture the skin. The entry hole will be small but the wound will be deep, with a high risk of infection.

INCISED WOUND

If a sharp-edged object cuts across the skin, blood vessels will be sliced open and bleeding will be severe. Nerves or tendons may also be damaged.

STAB WOUND

A penetrating wound from a long, bladed instrument is a very serious injury. A stab wound to the torso can damage vital organs and cause internal bleeding.

GUNSHOT WOUND

Check if the casualty has an exit wound. Treat entry and exit wounds separately.

ENTRY WOUND

Bullets drive deep into, or through, the body. They leave a small, neat entrance wound and cause serious internal damage and contamination.

EXIT WOUND

If a bullet passes through the body, the exit wound will be large and ragged. Don't remove the bullet if there is no exit wound.

SEVERE EXTERNAL BLEEDING

Control the bleeding with direct pressure over a wound and, if possible, call for emergency help. Never use a tourniquet as this can cause severe tissue damage. Life-threatening shock is likely to develop if blood loss is severe (see p. 274).



Elevate the legs as much as possible to minimize risk of shock developing

Apply pressure directly over the injury

1 Remove or cut away clothing to expose the wound. Apply direct pressure to the wound, over a sterile dressing or pad if you have one. Raise the injured limb above the level of the casualty's heart to reduce blood flow to the area. Help him to lie down and raise his legs.

2 Secure the dressing with a bandage. If blood soaks through, apply a second dressing on top of the first.



3 Every ten minutes, check the bandage is not too tight. Gently press a fingernail beyond the dressing. If the skin color does not return quickly, rebandage more loosely.



VARICOSE VEINS

When the one-way valves in veins fail, blood pools behind them, causing raised knobbly skin. The taut, thin-walled veins can easily be burst by a knock. Bleeding will be profuse.

1 Help the casualty to lie down and raise and support the injured area as high as you can. This reduces bleeding straight away. Expose the wound and apply direct pressure over a sterile dressing or pad.



2 Bandage the pad firmly to maintain pressure on the wound. Keep the area raised. Check the bandage is not too tight (see step 3, above). If necessary, loosen it but maintain pressure.



SCALP WOUNDS

A scalp wound can bleed profusely, making it appear worse than it actually is. However, it may mask a more serious head injury. If a casualty becomes drowsy, has a headache, or double vision, get emergency help if possible.



Use a pad that's larger than the wound



Roller bandage

1 Sit the casualty on the floor. Carefully replace loose flaps of skin, cover the wound with a sterile pad, and apply pressure.

2 Secure the dressing with a roller bandage. If the casualty doesn't quickly recover or if he deteriorates, get help.

EYE INJURIES

The eye can be seriously injured by a blow or contact with sharp objects, such as a tree branch, risking scarring, infection, or even loss of vision. Always wear eye protection when hiking through dense vegetation.


Cover affected eye with sterile pad

1 Lay the casualty down with his head on your knee. Cover the injured eye. Ask him to keep both eyes still, as moving one eye causes the other to move. If an object is sticking out of the eye, pad securely around it.



2 Secure the dressing with a bandage. If you're on your own, fix the dressing in place with plasters or tape and try not to move your eyes.

FOREIGN OBJECT IN THE EYE

If you can see an object on the surface of the eye, try lifting it off with the corner of a handkerchief, or wash it out with sterile water, washing away from the good eye. Don't remove anything that is sticking to the eye.

SNOW BLINDESS

Also known as "flash burn," this occurs if the surface of the eye is damaged through exposure to ultraviolet light, such as the glare from sun reflected off snow or water. Wearing sunglasses can prevent this. In an emergency, make your own goggles from cardboard or birch bark. If a person is affected by snow blindness, give him gauze pads to hold against his eyes. Bandage them in place if help is delayed.


Cut narrow slits in cardboard
Thread string through sides

IMPROVISED GOGGLES

BURNS AND SCALDS

There is a serious risk of infection with all burns. Burns may affect only the outermost layer of skin, the upper layers, or the full thickness. Severe burns will affect all three layers. If the burn is larger than the casualty's hand it needs hospital treatment.

SMALL SUPERFICIAL BURNS

Cool the injury for ten minutes with cold running water or any cold, harmless liquid. Remove jewelry or watches from the affected area before it swells. Cover the burn to prevent infection.

LARGE OR DEEP BURNS

If a burn is extensive or deep, then fluid will be lost from the body and life-threatening shock is likely to develop (see p. 274). If the injury occured in a fire, the casualty could also have burns to his air passages so may have breathing difficulties. Don't burst any blisters as you will increase the risk of infection.

STOP, DROP, AND ROLL

If clothing is on fire:

- Stop moving
- Drop to the ground
- Roll over on the ground until flames are extinguished

1 Help the casualty lie down and protect him from the ground if possible. Cool the injury by dousing it with cold water for ten minutes; this also reduces swelling and relieves pain.


Cool for at least ten minutes


Cut clothing to expose burned area

2 While cooling the burn, remove or cut away clothing from around the burn. Don't touch or remove anything that's sticking to the burn.

3 Cover the entire area with plastic kitchen wrap, a clean plastic bag, or a clean, lint-free dressing. Get emergency help as soon as possible.


Protect the injury to reduce risk of infection

BITES AND STINGS

MANY BITES OR INSECT STINGS are painful, but most can be treated with simple first aid. However, there is a risk of an allergic reaction called anaphylactic shock. If a casualty develops a red blotchy rash, watery eyes or puffiness around the eyes, and/or breathing difficulties, get urgent medical help (see p. 274).

TREATING BITES

An injury that breaks the skin carries a risk of infection. This is greatest with animal bites, since the mouth harbors so many germs. For a snake bite, you'll need to get emergency help, as the casualty needs to be transported on a stretcher in the treatment position to prevent the venom spreading through the body.

PORCUPINE QUILLS

If you are pierced by a porcupine's barbed quills, you must remove them or they will continue to work their way into the flesh and may pierce a vital organ.

- Cut off the ends of the quills, which are hollow, to allow them to deflate slightly.
- Pull the quills out, using pliers if you have them.
- Clean the puncture wounds and apply an antiseptic ointment.

SNAKE BITES

Relatively few snakes are venomous, but it's generally safer to assume that all of them are. Most snakes cause a painful bite that leaves small puncture marks in the skin; however, the bite of a poisonous snake may in fact be painless. Symptoms also include nausea and vomiting, disturbed vision, and breathing difficulties.

1 Keep the casualty calm. Help her to lie down with her head, chest, and shoulders supported.

- Advise her to keep still.
- Make a note, if you can, of the time the bite occurred.

2 Apply a bandage around the site of the injury. Do not wash the area, remove any footwear or clothing, or attempt to suck the venom.

3 Tie another bandage around the affected limb that extends from the bite as far up the limb as possible.

- Check the circulation (see p. 264).
- Immobilize the affected limb.
- Move the casualty only with the use of a stretcher.



Immobilize legs with folded triangular bandages

Bandage the limb from the bite site as far up the leg as possible

Tie the knots against the uninjured limb

Position casualty so that chest is higher than injured area

MAMMAL BITES

Bites from mammals—animals or humans—carry a serious risk of infection because the sharp teeth cause puncture wounds that transport bacteria deep into the tissue (see p. 263). As always, wear gloves to protect yourself. The bite can also crush surrounding tissue, and bleeding may be severe (see p. 264).

CLEAN WOUND

Raise the injury. Wash the wound with clean gauze and water. Pat dry, and cover it with a wound dressing.



Clean area thoroughly

SNAKE IDENTIFICATION

Identify the snake if you can, since this will help medical teams find the correct antivenom. If you're not certain of the identity, make a note of its color or distinguishing features. If it's safe, put the snake in a secure container, but bear in mind that venom is active even if a snake is dead. Don't wash the venom off the bite; it can be used to identify the antivenom.

TICK BITES

Ticks are tiny, spider-like parasites that live in grass or woodland. They feed on blood, attaching themselves to the skin with spiked mouthparts, and swell to the size of a pea. They carry Lyme Disease, so must be removed.

TRADITIONAL METHOD

Using tweezers, grasp the tick's head as close to the skin as you can. Pull the head upward using steady pressure (don't twist). Keep the tick in a container so it can be checked for Lyme Disease.



SPECIALIZED REMOVAL HOOK

Tick extractor tools that "unscrew" the mouthparts of the tick from the skin are available from pet shops. Slide the hook along the skin to grab the tick. Raise the hook very slightly and rotate it to lift the tick clear.


Slide the hook until it engages with the tick

HANDLING LEECHES

When in leech-infested territory, inspect your clothing and limbs every few minutes. Never pull a leech off if it's attached, as the jaws will remain in the skin and cause infection. To remove:

- Apply the juice of a raw lime, DEET, alcohol, or a dash of salt. If you're a smoker, put your cigarette butts in a piece of cloth, moisten the cloth, and squeeze nicotine onto the leech.
- Once the leech has dropped off, wash the area to remove the anticoagulant in and around the wound. Treat any bleeding (see p. 263) and cover the wound.

TREATING STINGS

Many stings are painful, but they are rarely life-threatening. Scorpion stings can be very painful and cause severe illness, and treatment should be as for snake bite (see opposite). Multiple insect stings of any type can produce a more serious reaction (see anaphylactic shock, p. 274).

WARNING!
A sting in the mouth or throat can cause swelling that blocks the airway. To minimize this, give the casualty cold water to sip.

INSECT STING

A bee, wasp, or hornet sting is often painful and followed by swelling and redness at the site. Some people have an allergy to stings, so monitor the casualty for signs of anaphylactic shock.





1. If the sting is visible, scrape it off sideways with the edge of a credit card, knife, or a fingernail.
   - Don't squeeze the sac as you may squeeze more venom into the area.
2. Raise the affected part and place a cold pad against it for at least ten minutes to minimize swelling.
   - Monitor the casualty for signs of allergy such as wheezing, or swelling around the face.

SEA CREATURES

When touched, sea anemones, corals, jellyfish, and Portuguese men-of-war release venomous cells that stick to the skin. Treat jellyfish stings as below; apply a cold compress to other stings to minimize swelling and relieve pain. Creatures such as weever fish have sharp spines that, if trodden on, become embedded, and may become infected.


Flood the area with vinegar or seawater


Hot water will ease the pain, but beware of scalding

JELLYFISH STING

Pour vinegar or seawater over the area to neutralize the sting. Help the casualty to sit down; treat as for snake bite (see opposite).

SEA URCHIN SPINES

Immerse the injured part in water as hot as the casualty can tolerate for about 30 minutes. Get medical help, as the spines must be removed.

POISONOUS PLANTS AND INTESTINAL PARASITES

IT'S ESSENTIAL TO MAINTAIN personal hygiene in camp, to purify all drinking water from natural sources (see pp. 198–201), and to observe the rules of food safety if you wish to remain healthy in the wilderness. You should also learn how to recognize and avoid the poisonous plants in the region you're traveling in.

CONTACT POISONING

Poisonous plants don't always have to be ingested to cause damage. If they come into contact with the skin, the result can be pain, swelling, redness, a rash, and itching. Get medical help fast and, in the meantime, rinse the skin with cold water for 20 minutes. If the water splashes an eye, rinse for ten minutes. Although plants are the most common cause of contact poisoning, chemicals such as camp fuel can also be harmful.

WARNING!

If you think you've handled a poisonous plant, don't touch especially sensitive parts of your body such as the eyes, mouth, or genitals until you have washed your hands thoroughly.

- If you develop blisters on your skin, don't scratch them—however much they itch. If you break the skin, you'll run the risk of getting an infection.
- As well as painful blistering, some people may have an extreme reaction to the toxin. They should be monitored and treated for shock (see p. 274). Get medical help as soon as possible.

POISONOUS PLANTS

Poison ivy, poison oak, and poison sumac are the most well known of the plants that contain urushiol, an irritant oil. If you damage the plant and get the oil on your skin, you must wash it off immediately with soap and cold water. You should also remove and wash any contaminated clothing to prevent the oil spreading. Apply an anti-poison-ivy cream as soon as possible. Many people will develop an itchy rash and often painful blistering within 4 to 24 hours of contact with the plant (see warning panel, above).

POISON SUMAC

Found in wet acid swamps in eastern North America, poison sumac can grow as tall as 18 ft (6 m).


Oval leaflets grow in opposite pairs

POISON IVY

Native to wooded areas of North America, poison ivy is now found worldwide.


Berries are white when ripe

POISON OAK

Like poison ivy, the leaflets of poison oak grow in threes. This plant is found in wooded parts of North America.


Leaflets are shaped like oak leaves

STINGING NETTLES

Found in many countries, stinging nettles usually cause only a temporary stinging sensation where the plant's hairs touch the skin. Apply a soothing cold compress or rub the affected area with a dock leaf if you can find one. Watch for an itchy red rash that indicates an allergic reaction.

NATURAL REMEDIES

Where nature causes a problem, she sometimes provides the solution. The following counter the effects of urushiol:

- Jewelweed has a sticky juice that will dry out blisters in a few days. Cut a piece of stem, split it down the middle, and rub the pieces on the affected skin.


Jewelweed has distinctive pale yellow or orange, spotted flowers

- To soothe itching, make a poultice of witch hazel leaves. Mash up the leaves, adding water if too dry, then apply to the affected area.
- Try washing with a tannic acid solution. Tannic acid is found in tea, or you can make it from oak bark (see opposite).
- Tea tree oil, from the leaves of the melaleuca tree, is also said to counter the effects of urushiol. Apply directly to the affected area.

SWALLOWED POISON

Try to find out what the casualty ingested, how much, and when. If you suspect the casualty has swallowed a caustic chemical, such as camp fuel, do not induce vomiting as it will burn again on the way back up. Get medical help and monitor the casualty. If the lips are burnt, give frequent sips of cool milk or water. If you know the casualty has swallowed a poisonous plant or fungus and he or she is conscious, induce vomiting by tickling the back of the throat. Dilute the poison by getting him or her to drink large quantities of water or milk, or tea mixed with charcoal.

DIARRHEA AND VOMITING

In the wilderness, diarrhea and vomiting can kill, because they lead to dehydration (see p. 272) or even shock (see p. 274). The most likely causes are food poisoning or drinking contaminated water, although infectious diseases are a possibility, so get medical help if symptoms persist. You should rest, keep warm, and replace lost fluids. If you're hungry, you can eat small amounts of bland foods such as pasta for 24 hours.

NATURAL REMEDIES

In a survival situation, there are various natural remedies you can try to stop diarrhea or alleviate symptoms such as stomach pain, although some are more palatable than others:


Cowberry (or mountain cranberry) leaves are small and oval


The hazel leaf is heart-shaped

- **Tea:** Drink tea made from hazel, cowberry, or cranberry leaves.
- **Bark:** Pull some bark off a tree (preferably oak), remove the inner bark and boil it for at least 12 hours, adding more water as necessary. The resulting black brew smells and tastes vile, but it contains tannic acid and will cure diarrhea. Drink one cup every two hours.
- **Charcoal**: Take a partially burned piece of wood, scrape off the char, then swallow about a handful with water.
- **Bones:** Burn to ashes then grind, or grind bones into a powder between two rocks. Make a paste with water, then swallow about a tablespoonful.
- **Chalk:** Grind into a powder, mix with water to a paste, then swallow about a tablespoonful.
- **Ash:** Make a paste of wood ash and water, then swallow. This will alleviate stomach pain.

REST AND REHYDRATE

Drink water to maintain your fluid levels. To help replace lost salts, dissolve a packet of rehydration salts in the water, or one teaspoon of salt in a liter of water, before drinking.

INTESTINAL PARASITES

There are two main types of intestinal parasite: helminths (tapeworms, pinworms, and roundworms) and protozoa (giardia, for example). The usual causes of infection are ingesting contaminated water or food, or poor personal hygiene. Symptoms include nausea or vomiting, diarrhea (see left), dysentry, bloating, stomach pain, weight loss, or a rash or itching around the rectum. Seek medical advice as soon as possible.

WILDERNESS CURE FOR WORMS

If you have passed a worm in your stool, swallow a couple of tablespoons of kerosene. While this method may make you sick, it will make the worms sicker. Gasoline will also work but is not as effective.

HOW TO AVOID BEING INFECTED

Prevention is far better than cure and to avoid being infected by parasites present in water or spread in feces you should always do the following in the wilderness:

- Boil all water, or use other reliable methods of purification (see pp. 198–201).
- Don't clean your teeth or rinse your mouth with water that isn't pure.
- Don't swim or stand in rivers or lakes in places where you could be at risk unless absolutely necessary.
- Cover any cuts or wounds on your skin.
- Maintain strict personal hygiene in camp (see pp. 116–17) and when handling food.
- Boil any meat you think might be infected for at least 20 minutes, or ideally until it falls off the bone, before eating it.



BONES, JOINTS, AND MUSCLES

CRAMP

This painful muscle spasm can be caused by dehydration and a reduction of body salts through perspiration—so make sure you have enough to drink when exercising. Sit down, rest, and stretch the affected muscles.

FOOT

Help the person stand on his good foot and stretch the muscles to reverse the spasm. Once the cramp has eased, massage the affected area of the foot.


Support the person's foot
Bend the toes to stretch the muscles

CALF

Sit the person down and support the affected leg. Help him to straighten his leg, and flex his toes to reverse the spasm. Then massage the painful muscle.


Push toes back to help stretch the muscle
Massage the calf muscles firmly

THIGH

If the cramp is in the back of the thigh, straighten the leg to stretch the muscle; if it's in the front of the thigh, bend the leg. Once the pain eases, massage the affected area.


Support the leg on your shoulder
Advise casualty to lie down and relax the leg

IT CAN BE DIFFICULT TO TELL whether an injury is a sprain, a broken bone, or a dislocation. The ends of broken bones can move, damaging blood vessels or nerves nearby, so treat the casualty in the position found and immobilize the injured area before letting him or her move. Anyone with a spine injury or broken leg must be carried by stretcher.

SPRAINS AND STRAINS

A strain is a pulled muscle. A sprain occurs when ligaments that hold a joint together are damaged. The ideal treatment is to raise the injury, cool, and rest it. If you provide comfortable support, gentle movement can help the injury. If in any doubt, treat the injury as a broken bone (see opposite).


Raise the injured area


Bandage an ankle from the toes to the knee

1. Rest and support the injury. Wrap a cold compress around it for at least 10 minutes to reduce swelling and bruising.

2. Leave the compress in place, or wrap padding around the injury. Apply a crêpe bandage from below the injury to the next joint.

ARM INJURY

Falling onto an outstretched hand can cause a broken wrist, forearm, upper arm, or collar bone. Support the affected arm in a sling. If a casualty can't bend his arm, he may have injured his elbow, in which case don't use a sling. Instead wrap padding around the joint and secure the arm to the body with triangular bandages. To make sure that the bandage isn't too tight, check the wrist pulse.

USING A SLING

Slide a triangular bandage between the arm and the chest. Bring the front up over the arm and tie a reef knot on the uninjured side.


Tie knot just above the collar bone on the uninjured side

LEG INJURY

Injuries to the legs can be serious, as any fracture is likely to be unstable, which means that the ends of the bones can move easily, and could pierce one of the large blood vessels in the leg, resulting in severe bleeding. Don't move the casualty unless you have to, and, even then, only when the legs have been immobilized. If you see any signs of shock (see p. 274) ensure the head is low, but do not raise the legs.

HAND INJURY

Injuries to hands are often complicated by bruising or bleeding. Raise the injured hand and treat bleeding with direct pressure (see p. 264). Remove jewelry before the area starts to swell. Wrap the hand in padding and support it in a raised position with a sling.


Wrap hand in soft, lint-free padding
Casualty can help support hand


Support joints above and below the injury
Keep the injured leg as straight as possible


Put first bandage around the knees
Secure third and fourth bandages above and below injury
Tie second bandage in a figure of eight around the ankles and feet
Secure bandages with reef knots on the injured side

1. Lay the casualty down and support the injury to minimize further damage. Call for emergency help. If this is nearby just maintain this support. You can put rolled-up coats or blankets on either side for extra support.

2. If help is delayed or you need to transport the casualty, put bandages around the knees and ankles (and pelvis, if the thigh is injured), and above and below the injury. Place padding between the legs, then tie the bandages.

SPINAL INJURY

If a person falls and lands on his back, or falls from a height, it is best to assume that he has a spinal and, probably, a head injury. Don't move him—support his head and neck in line with the rest of his back. Moving him could damage the spinal cord, which may result in permanent loss of movement below the injured area. Call for emergency help, or send someone to get help while you stay with the casualty. If you have to move him because he is in danger, use the log-roll technique (see p. 279).

SUPPORT THE HEAD AND NECK

Kneel or lie behind the casualty's head. Keep your arms steady by resting your elbows on your thighs and place your hands on either side of his head to keep it in line with his body. Wait for help.


Don't cover the casualty's ears as he must be able to hear you
Make sure you are comfortable because you may have to wait for help to arrive

TREATING EXPOSURE

EXTREMES OF HEAT AND COLD can prevent the body's temperature-regulation mechanisms from functioning properly. Both extremes can cause life-threatening injures, so it's vital to act quickly. Don't leave a casualty—call for help or, if possible, send someone to seek help while you treat him or her.

WARNING!
If a casualty becomes unconscious, be prepared to give cardiopulmonary resuscitation (see p. 277).

HEAT INJURIES

In hot weather, wear a hat, reapply sunscreen frequently, and stay in the shade when you can to avoid heat injuries such as sunburn. You'll quickly become dehydrated if you don't drink enough water to replace fluids lost through sweating.

DEHYDRATION

Help the casualty to sit down and give him fluids to drink; water is usually sufficient, but rehydration salts mixed with water is best. If the casualty complains of cramp, help him stretch the affected muscles, then massage them firmly (see p. 270).

HEAT EXHAUSTION

If a casualty feels dizzy and starts to sweat profusely, but has cold, clammy skin, get him into the shade and give him fluids to drink. Help him to lie down then raise his legs—support his feet on a backpack—to help improve blood flow to the brain. Monitor him while he recovers.



Raise the casualty's feet so that they are higher than his head

In cases of heat exhaustion, give the casualty plenty to drink

HEATSTROKE

This life-threatening condition may follow heat exhaustion or develop with no warning. Heatstroke causes the body's temperature-control mechanism to fail. If a person complains of headache, feels dizzy, has hot, dry skin, and begins losing consciousness, he or she may have heatstroke and will need urgent medical help.



Fan his face to help cool him

Pour water over the sheet

1. Move the casualty to as cool a place as possible—out of the sun. Help him to sit or lie down with his head raised and remove all of his outer clothing.

2. Do anything possible to quickly reduce the body temperature. Ideally, wrap him in a cold, wet sheet. Keep the sheet cool by continually pouring water over it.

3. When the body temperature drops below 104°F (40°C), replace the wet sheet with a dry one.

4. Monitor the level of response, pulse, and breathing. If his temperature starts to rise again, repeat the treatment.

COLD INJURIES

Exposure to cold can result in parts of the body freezing (frostnip and frostbite) or the body's core temperature becoming dangerously low (hypothermia).

FROSTNIP AND FROSTBITE

Frostnip is the freezing of the top layer of skin, usually on the face and extremities. The skin turns numb, white, and hard. Untreated, it can lead to frostbite, which is much more serious—the deeper tissues, and even the bone, freeze. The skin turns white or blue and feels solidly frozen.

WARM GRADUALLY

Frostnip and frostbite can both be treated by warming the affected area, though frostbite requires more intensive treatment. Warm the affected area with body heat—place the casualty's hands in his own armpits, or place his feet in your armpits. Remove any rings and raise the injured part to reduce swelling. Ideally, place the affected area in warm water. Dress the injury in sterile dressings.



Put gloved hands in armpits

HYPOTHERMIA

This life-threatening condition develops if the body's core temperature falls below 95°F (35°C). Treatment aims to prevent further heat loss. It's vital that a casualty is warmed up gradually. If he or she is warmed up too quickly, blood is diverted away from vital organs, such as the heart and brain, to the skin, which can actually speed up cooling of the body. A casualty with hypothermia must be moved on a stretcher.

1 Help the casualty to a sheltered place where he should rest to prevent his body temperature falling further. Send someone else to get help.

2 If possible, and if there is no risk of further cold, remove any wet clothing and replace with warm, dry clothes—but don't give up your own clothes.

3 Put a thick layer of dry leaves underneath him to insulate him from the ground. Help him to lie down in a sleeping bag and, if you have one, cover him with a survival blanket.

Give the casualty warm (not hot) sweet drinks and high-energy foods such as chocolate



Use dry heather, bracken, or pine branches for insulation

Make sure the head is covered

DROWNING

If a person has been immersed in cold water, there is a high risk of hypothermia. In addition, the cold can cause the heart to stop, or throat spasms can block the airway. Water can also enter the lungs and cause secondary drowning (see p. 255) hours after the person appeared to have recovered.

RESCUING A CASUALTY

If you have rescued a person from water, help him or her to lie down with the head low. Replace wet clothes with dry ones. Treat for hypothermia (see left). If the person is unconscious and not breathing, give five rescue breaths before beginning chest compressions (see p. 277).

ALTITUDE SICKNESS

Symptoms of altitude sickness include nausea, loss of appetite, shortness of breath, and a headache that's not relieved by medication. The casualty may also have difficulty sleeping and will feel unwell. The only solution is to start the descent immediately and remain at a lower altitude for a few days. Severe cases will need to be carried.

TREATING SHOCK

SHOCK IS A LIFE-THREATENING CONDITION that occurs if the circulatory system fails. The most common cause is severe bleeding, but it can also be a consequence of burns. Initially, there will be a rapid pulse and pale clammy skin. As the condition progresses, breathing becomes rapid and shallow, pulse weakens, and skin becomes pale gray-blue. If untreated, unconsciousness results.

ANAPHYLACTIC SHOCK

Anaphylactic shock is a rare but severe allergic reaction affecting the whole body. People who know they are susceptible to this carry a special adrenaline (epinephrine) autoinjector for use in an emergency. If the casualty has one, but is too weak to use it, take off the safety cap and, holding it in your fist, press it against the casualty's thigh (through clothing if necessary).

DEALING WITH SHOCK

Do not give the casualty anything to eat or drink as an anaesthetic may be needed; moisten his lips with water if he's thirsty. Call for help; the casualty must be transported in the treatment position.

1. Treat the cause of shock, for example bleeding or burns (see p. 265). Suspect shock, too, if you notice any symptoms, yet can't see any obvious injury—it could be caused by internal bleeding.

2. Help the casualty to lie down; insulate him from the ground with blankets or bracken. Raise and support his legs as high as you can above the level of his heart.

3. Loosen tight clothing, for example at the neck, chest, and waist. Keep his head low; this may prevent him from losing consciousness. Keep the casualty warm; cover him with a blanket or sleeping bag if you have one.



Raise the legs as high as possible. Use a tree stump, some backpacks, or anything else you have at hand

Loosen tight clothing around neck

Keep casualty warm and protect him from the ground

4. Shelter the casualty as much as you can, but don't move him unnecessarily. Monitor his level of response, breathing, and pulse while you wait for help. Begin resuscitation if he loses consciousness (see p. 277).

BREATHING DIFFICULTIES

RESPIRATORY PROBLEMS need prompt treatment because they can prevent sufficient oxygen reaching the body tissues. The cause may be temporary, for example choking, suffocation, or smoke inhalation, or it can be a long-term condition such as asthma that requires medication. You may need to get emergency help.

WARNING!
If at any stage the casualty loses consciousness, open the airway (see p. 276) and check breathing; the throat muscles may relax enough to allow breathing. If he or she is not breathing, begin resuscitation as this may dislodge the blockage (see p. 277).

CHOKING

When an object becomes stuck in the throat it can cause a muscular spasm that blocks the airway. Always ask the casualty if she is choking, to make sure. If she can speak, cough, or breathe, the obstruction is mild and she will probably be able to clear it herself.

1. If the casualty is breathing, tell her to continue coughing. If she can't speak or cough, help her to bend forward. Support her upper body and give up to five back blows in between her shoulder blades with the heel of your hand.

2. If back blows fail, stand behind her. Put your arms around her abdomen, clench one fist and grasp it with the other hand. Pull sharply inwards and upward up to five times. Check the mouth and remove any obvious blockage.

3. If the obstruction has still not cleared, repeat the five back slaps and five abdominal thrusts three times, then call for help if it's not already on the way. Continue until help arrives or the casualty becomes unconscious (see pp. 276–77).


Pull against the abdomen—not the chest

ASTHMA

This is a condition in which breathing becomes difficult because the muscles in the air passages go into spasm. Most people who suffer from asthma carry inhalers with them. Many have two inhalers—a brown or white "preventer" inhaler and a blue "reliever" inhaler to use in an attack. If the person does not have any medication, sit him or her down and call for emergency help.

1. Sit the casualty down and advise her to take a puff from her reliever inhaler. Tell her to take slow, deep breaths and to sit as upright as she can. The attack should start to ease in a few minutes.

2. If the attack does not ease, tell her to take another dose from her inhaler and rest while she recovers. If the attack still does not ease, or is becoming worse, emergency help is needed as she could lose consciousness.

WHAT TO DO IN A SURVIVAL SITUATION

The best advice is prevention—know what triggers the asthma and avoid those things if at all possible. However, should someone have an asthma attack and not have an inhaler, try the following:

- Tell her to exhale as completely as she can. This expels the "stale" air, with little or no oxygen in it. It may be difficult—and will seem strange—to blow air out when the basic instinct is to gulp air in, but this does work.
- Then, tell her to inhale, slowly and steadily, and to close her eyes to help calm herself while doing so.



UNCONSCIOUSNESS

IF SOMEONE FALLS UNCONSCIOUS, your priority is to make sure their airway is open so that they can breathe. Call for emergency help immediately (ideally ask someone to do this while you treat the casualty). Don't move the casualty and don't leave him or her alone unless you have to go and get help.


Talk to the casualty and ask him to open his eyes
Shake an adult casualty's shoulder

CHECK FOR RESPONSE

Gently shake the casualty's shoulders (if it's a child, tap the shoulders). Talk to him and watch for a response. If he's alert, he's conscious. If, for example, he reacts weakly, he may not be fully conscious—monitor him for any change (deterioration or improvement). If there's no response, he's unconscious.

OPEN THE AIRWAY

If an unconscious casualty is on his back, he's at risk of swallowing his tongue—thereby blocking his air passages. Tilting the head and lifting the chin will "lift" the tongue, clearing the air passage.

CHECK THE BREATHING

Tilt a casualty's head back with one hand and lift the chin with two fingers of your other hand; don't press on the soft tissues under the chin. Keep the airway open, and look, listen, and feel for normal breathing. If the casualty is breathing normally, place him in the recovery position (see below). If he's not breathing, begin chest compressions right away (see opposite).



1 Place a hand on the forehead to tilt the head; lift the chin.



2 Look along the casualty's chest; listen, and feel, for breath against your cheek for no more than ten seconds.

RECOVERY POSITION

If an unconscious casualty is breathing, place him in the recovery position to keep his airway open and clear. Remove anything bulky from his pockets. Kneel beside him. Bend the arm nearest you at a right angle to his body then bring the other arm across his chest until his hand rests against his near cheek, and hold it there. Bend the far leg at the knee, and, still holding the knee, pull the casualty toward you until he is on his side.


Keep lower leg straight, in line with the spine
Tilt the head back to keep airway open
Adjust arm so that hand is palm upward under the side of the face
Bent leg helps to prevent casualty rolling forward
Lower arm is at right angles to body to prevent casualty rolling forward

CARDIOPULMONARY RESUSCITATION (CPR)

If a casualty is not breathing, you must try to keep the body supplied with oxygen by using chest compressions and rescue breaths until emergency help arrives. This is known as cardiopulmonary resuscitation, or CPR. If an adult collapses, the cause is most likely to be a heart problem so treat as below. If you have rescued an unconscious casualty from water, start with rescue breaths as for a child (see right). If you are unable to achieve rescue breaths, you can give chest compressions alone.

CPR ON A CHILD

- Start by giving the child five rescue breaths.
- Give 30 compressions using the heel of one hand only and slightly less pressure than you would for an adult. Depress the chest by approximately one third of its depth.
- Continue with 30 compressions followed by two rescue breaths until the child recovers, help arrives, or you become exhausted.
- If you are on your own, give CPR for one minute before you try to call for help.

HOW TO GIVE CPR

Kneel beside the casualty, level with his chest so that you don't have to change position. If you have someone else with you, take it in turns to give CPR so you don't become too exhausted. Change over at the end of each two-minute cycle.

1 Put one hand on the center of the casualty's chest—make sure you don't press on the lower abdomen, the tip of the breastbone, or the ribs.

2 Place the heel of your other hand on top of the first and link your fingers together. Keep your fingers off the casualty's chest.

3 Begin chest compressions. Lean over and, keeping your arms straight, press straight down on the casualty's chest, depressing it by 1½–2 in (4–5 cm). Release the pressure and let the chest come back up, but don't move your hands. Repeat 30 times.

4 Tilt the casualty's head to open the airway and pinch his nose to close the nostrils. Let his mouth fall open slightly. Lift his chin with the fingers of your other hand.

5 To begin rescue breaths, take a normal breath and seal your lips over those of the casualty. Blow into his mouth until you see his chest rise, then lift your mouth away and watch his chest fall. If his chest doesn't rise, adjust his head and try again. Repeat to give a second breath, but don't make more than two attempts at giving rescue breaths before compressing again.

6 Continue the cycle of 30 compressions followed by two rescue breaths until the casualty recovers, help arrives, or you are too exhausted to keep going.

- If at any stage the casualty starts breathing normally, place him in the recovery position (see opposite) and monitor his condition until help arrives.


Place heel of hand on center of chest
Keep fingers clear of the ribs

MOVING A CASUALTY

IDEALLY, AN INJURED PERSON should be treated in the position in which he or she was found. Make the casualty as comfortable as possible and wait for help. In a survival situation, if you have to move someone, it's essential to immobilize an injury first to avoid aggravating it.

WARNING!
Move a casualty only if his life is in immediate danger if he is left where you found him. Even then, only move him if by doing so you will not injure yourself. Don't otherwise attempt to move a casualty, as it will make his injuries worse—stay with the casualty and send others for help.

PREPARING FOR A MOVE

Plan your move before you start. Choose a method appropriate to the injury. Don't attempt to move anyone by yourself if you have help. Encourage the casualty to do as much as possible himself.

FIREFIGHTER'S LIFT

This is a technique that can be used to move a conscious casualty if you're on your own and need to carry an injured person a short distance. It gets its name from the firefighters who originally used it. Don't use it if a casualty has head or facial injuries or a broken arm or leg. To prevent injuring your back, use your legs to power the move.

1 Support the casualty's injury with padding and bandages. Help him to stand up.

- Stand at right angles to the casualty, then squat down in front of him, staying as close to him as possible.
- Your shoulder should be level with the top of the casualty's legs.



Hold his wrist to help support him

Put your arm between his legs so that your shoulder is against the top of his leg

Tell the casualty to keep his weight off the injured foot

2 Pass your nearest arm between the casualty's legs, wrap it around his thigh, and grasp his leg. Grasp the casualty's wrist firmly with the other arm.

3 With your feet shoulder-width apart to ensure you're well balanced, encourage the casualty to lean across your shoulders.

- Keeping your back straight, hold his wrist firmly, and use the strength of your legs to stand up.

IMPROVISING A STRETCHER

If you need to move a casualty who is unconscious, has a broken leg, or a spine injury, he must be carried by stretcher. Ideally, call the emergency services, and wait for them to arrive. If you can't contact them and you need to get the casualty to medical assistance, you may need to make a stretcher. Use a hurdle or gate, or make the stretcher from poles and coats.

WARNING!
Rescuers should not use their own clothing to make a stretcher if this might put them at risk of exposure.


Push sleeves inside jacket for added strength


Place cross-piece at each end of the stretcher
Place the side of the stretcher against the casualty's back

1. Zip or button up two or three jackets. Cut two support poles, strong enough to bear the casualty's weight and 3 ft (1 m) longer than the casualty. Lash a short forked branch across each end (see pp. 166–67) to keep the support poles apart.

2. Immobilize any injury (see p. 271), and roll the casualty onto his uninjured side. One person should support his head while others help to keep his body straight, ideally one for the upper body and one for the legs. Slide the stretcher in place then roll him gently back on to it.

TWO-PERSON SEAT

If there are two of you, this method can be used to carry a conscious casualty who can't walk, but who can support himself with his arms. Nominate one person to be in charge of the move and give the instructions. Keep your backs straight at all times.

1. Stand facing each other behind the casualty. Grasp your left wrist with your right hand, then grasp each other's free wrist to make a seat.



2. Ask the casualty to put her arms around your shoulders. Let her sit back on to your hands. Rise and take her weight. Set off together, leading with your outside feet.

SUPPORTING THE UPPER BODY

If a casualty has an injured arm, the seat carry (see left) can be adapted to support the upper body. As before, one of you should direct the move and always move together. Keep your backs straight as you walk, and stop if it causes you or the casualty any discomfort.

1. Stand facing each other, on either side of the casualty. Put your arms around her back and grasp her clothing on the side farthest from you.



2. Pass your free hands behind the casualty's thighs. Link your fingers together or grasp each other's wrists. Help the casualty back on to the "seat," and lift her.

WILD FOOD

MANY POISONOUS PLANTS in temperate regions resemble edible ones, so you should only eat plants that you can positively identify. If you're in any doubt at all, carry out the Universal Edibility Test (UET) first (see pp. 206–07). Don't forget that some plants are edible only at certain stages of their growth. Never eat wild plants if you have any known

NAME	WHERE	IDENTIFICATION	EDIBLE PART
BISTORT/KNOTWEED *Polygonum* spp.	▪ Damp, grassy habitats, such as meadows, in North America and Eurasia.	▪ Perennial plant, 16–40 in (40–100 cm) tall. Green, triangular leaves. Small pink or white flowers form dense, cylindrical flowerheads at end of long, unbranched stem.	▪ Young shoots and leaves ▪ Roots
BRAMBLE/BLACKBERRY *Rubus fruticosus*	▪ In most temperate habitats worldwide, but particularly scrubland, hedges, and woodland.	▪ Scrambling deciduous shrub with thorny stems forming thickets. Green, toothed leaves. White or deep pink five-petaled flowers. Fruit ripens to blue-black in late summer.	▪ Fruit ▪ Young shoots ▪ Leaves
BUCKWHEAT *Fagopyrum esculentum*	▪ Open grassland worldwide.	▪ Red-stemmed plant up to 2 ft (60 cm) tall. Green, triangular leaves. Small pink, five-petaled flowers grow in clusters. Triangular seeds.	▪ Seeds
DANDELION *Taraxacum* spp.	▪ Widely distributed in temperate areas of Eurasia; introduced to the Americas, Australia, and New Zealand.	▪ Rosette of green, jagged-edged leaves grows close to the ground from a central taproot. Large, bright yellow flower head matures into a spherical "clock" of several seeds.	▪ Leaves ▪ Roots
DOG ROSE *Rosa canina*	▪ In hedgerows, woodland margins, and scrubland in Europe, northwest Africa, and western Asia; introduced to other regions.	▪ Scrambling deciduous shrub with spiny stems. Dark green, toothed leaves. Scentless, white, pink or deep pink five-petaled flowers. Fruit, or "hip," is orange-red and oval.	▪ Hips ▪ Buds and flowers ▪ Young leaves
STINGING/ COMMON NETTLE *Urtica dioica*	▪ By hedgerows and woodland margins in North America, Eurasia, and North Africa.	▪ Perennial herbaceous plant, 20–60 in (50–150 cm) tall. Green, oval, toothed leaves covered in stiff stinging hairs. Small green flowers sometimes have a red tinge.	▪ Young shoots and leaves
SUGAR MAPLE *Acer saccharum*	▪ Woods and forests in northeastern North America.	▪ Deciduous tree, usually 82–115 ft (25–35 m) tall. Gray-brown bark smooth on young trees, furrowed and flaky on old trees. Green, five-lobed leaves turn bright red in fall.	▪ Sap ▪ Inner bark
WALNUT *Juglans* spp.	▪ Temperate areas in Eurasia and North America. Common in the Himalayas.	▪ Large deciduous tree up to 82 ft (25 m) tall with distinctive gnarled bark. Green leaves have narrow leaflets. Nut has a thick, green husk, which rots away once it falls to the ground.	▪ Nuts
WATER CHESTNUT AND WATER CALTROP *Trapa natans* and *T. bicornis*	▪ In slow-moving water in warm temperate areas of Eurasia and Africa; introduced to North America and Australia.	▪ Green, triangular, saw-toothed leaves float on surface. White four-petaled flowers. Fruit is borne underwater and has four sharp spines and one hard gray seed.	▪ Seeds
WILD GRAPE *Vitis* spp.	▪ In most habitats in North America and Eurasia.	▪ Sprawling, high-climbing vine with large, lobed leaves. Fruit grows as hanging bunches of berries, which are amber or dark purple when ripe.	▪ Fruit ▪ Young leaves

TEMPERATE PLANTS

allergies, a pre-existing medical condition, or are pregnant. The UET doesn't apply to mushrooms, so never eat any mushrooms unless you can positively identify every single one as being edible. As part of your preparation for your trip, you should familiarize yourself with the edible plants in the region you're visiting, and their seasonal availability.

	PREPARATION	SIMILAR PLANTS	BEWARE OF	EXTRA INFORMATION
	▪ Young leaves and shoots can be eaten raw or boiled. ▪ Soak roots, then boil or roast.	▪ Alpine bistort (*P. viviparum*) is common on rocky soils in northern alpine regions and the Arctic.		▪ Roots are twice twisted and are said to resemble two snakes. They contain starch and can be used to make flour.
	▪ Fruit and peeled young shoots are edible raw. ▪ Infuse the leaves to make tea.	▪ Wild raspberry (*R. idaeus*) fruit ripens to a bright red. Tea made from the leaves can be used to treat diarrhea.	▪ Catching yourself on thorns.	▪ Blackberries and raspberries are high in vitamin C and sugars. Blackberry leaf tea can be used to treat colds and coughs.
	▪ Hull and grind the seeds to make buckwheat flour. ▪ Roast seeds and cook with water to make porridge.		▪ Buckwheat leaves are edible but can cause photosensitivity of the skin if eaten in large quantities.	
	▪ Young leaves can be eaten raw; boil old leaves to remove the bitter taste (change the water once). ▪ Boil the roots.			▪ Roots can be roasted and ground to make a substitute for coffee. The leaves are high in vitamins A and C, iron, and calcium.
	▪ Buds and flowers are edible raw. ▪ Chew the pulp of raw hips, or dry and eat later. ▪ Boil leaves in water to make tea.		▪ The hips of all wild roses (*Rosa* spp.) are edible, but do not eat the seeds if they are prickly as they will irritate the throat and stomach.	▪ Rose hips remain on the shrub all year. They are rich in vitamin C. Boil crushed hips in water then strain to make a nutritious syrup.
	▪ Boil the plants for 10 minutes to destroy the formic acid and histamine in the stinging hairs.	▪ Dead nettles (*Lamium* spp.) are also edible if cooked. They have heart-shaped leaves and white or purple flowers. No stinging hairs.	▪ Gather and handle the plants carefully, wearing gloves if you have them, to avoid being stung by the hairs.	▪ Fresh nettles are rich in protein and vitamin K. The fibers in mature stems can be woven into cordage (see pp. 138–41).
	▪ Boil sap into a high-energy syrup. ▪ Eat inner bark raw or boil into a gelatinous mass, then roast and grind into a flour.	▪ Red maple (*A. rubrum*) also produces sweet sap. ▪ White birch (*Betula* spp.) has edible inner bark.		▪ To collect the sap, cut a V-shape into the trunk, make a hole below the cut, and insert a leaf to guide the drips into a container below.
	▪ Crack the shell and eat the ripe nut raw.			▪ Rich in fat, protein, and vitamins. ▪ Crushed green husks of black walnut (*J. nigra*) are toxic to fish. Use to poison and catch them.
	▪ Seeds can be eaten raw or roasted.			▪ Water chestnuts are a source of carbohydrate.
	▪ Ripe fruit is best eaten raw. ▪ Boil young leaves.		▪ Moonseed vines (*Menispermum* spp.) have grapelike fruits, which are poisonous. Unlike edible grapes, they only have one seed.	▪ Ripe grapes are rich in vitamin C and sugar. Water can be obtained from the vine stem (see p. 192).

WILD FOOD

SOME OF THE PLANTS listed below are good sources of water/liquid. In a survival situation in the desert, don't eat food if you don't have any water, as your body will use up its own water to digest it. Only eat plants that you can positively identify and, if you are in any doubt at all, carry out the Universal Edibility Test (UET) first (see pp. 206–07).

NAME	WHERE	IDENTIFICATION
ACACIA/WATTLE *Acacia* spp.	▪ Africa, southern Asia, Australia, and the Americas.	▪ Thorny, medium-sized trees with gray-white bark. Green leaves divided into many small, oval leaflets. Small, ball-shaped yellow, white or pink flowers.
AGAVE *Agave* spp.	▪ Southern USA and Mexico, Central America, the Caribbean, and northeastern South America.	▪ Rosette of fleshy leaves with sharp tip and spiny margin. Central, tall flower stalk.
AMARANTH *Amaranthus* spp.	▪ The Americas, Africa, and Asia.	▪ Tall herb with alternating leaves and erect fleshy stems. Tiny brown/black seeds (one plant produces 40,000–60,000 seeds).
BAOBAB *Adansonia* spp.	▪ Africa and northern Australia.	▪ Large trees with swollen trunks, up to 30 ft (9 m) in diameter. Green leaves have 5–7 digit-like leaflets. Oblong fruit up to 8 in (20 cm) long.
CAROB TREE *Ceratonia siliqua*	▪ Mediterranean, northern Africa, Middle East, and India.	▪ Evergreen tree up to 50 ft (15 m) tall. Shiny green leaves up to 8 in (20 cm) long. Small red flowers. Flat leathery seed pods; dark-green/black when ripe. Hard brown seeds.
CARRION FLOWER *Hoodia* spp.	▪ Southwest Africa.	▪ Numerous thorny, succulent stems up to 6 ft (2 m) tall. Star-shaped or shallowly bell-shaped flowers give off the smell of rotting meat.
DATE PALM *Phoenix dactylifera*	▪ West and North Africa, Middle East, and India; introduced to Mexico and USA.	▪ Tall slender palms with a large crown of green leaves, divided into many narrow leaflets. Fruit reddish-brown when ripe.
PRICKLY PEAR CACTUS *Opuntia* spp.	▪ The Americas; introduced to the Caribbean, the Mediterranean, Africa, and Australia.	▪ Thick, jointed, flat, pad-like, green stems covered in spines. Red or yellow flowers. Fruit red when ripe.
WILD GOURDS *Cucurbitaceae*	▪ Kalahari Desert (Namibia), the Sahara, islands in the Mediterranean, the Middle East, and southeastern India.	▪ Ground-trailing green vine. Bright yellow flowers. Orange-sized green or yellow fruit.

DESERT PLANTS

Don't forget that some plants are edible only at certain stages of their growth. Don't eat wild plants if you have any known allergies, a preexisting medical condition, or are pregnant. When planning your trip, it's advisable to familiarize yourself with the edible plants in the region you are visiting and their seasonal availability.

EDIBLE PART	PREPARATION	BEWARE OF	EXTRA INFORMATION
▪ Seeds (from dark brown pods) ▪ Young leaves and shoots	▪ Roast seeds. ▪ Boil leaves and shoots.	▪ Catching yourself on thorns.	▪ Roots may be tapped for water.
▪ Stalk, before in flower ▪ Buds and flowers	▪ Roast the stalk. ▪ Boil buds and flowers.	▪ Juice from many species can cause acute contact dermatitis, with reddening and blistering lasting 1–2 weeks. Leaves have needle-like ends.	▪ Roasted stalk tastes sweet, like molasses.
▪ Young shoots and leaves ▪ Seeds	▪ Eat shoots and leaves raw or boiled or stir-fried. ▪ Remove chaff from seeds, then cook like popcorn or grind into flour to make bread.	▪ Amaranth leaves are high in oxalic acid, which can irritate the gut and cause kidney stones, so eat in moderation.	▪ Amaranth leaves are a common leaf vegetable in the tropics and warm temperate regions.
▪ Shoots and young leaves ▪ Fruit ▪ Seeds	▪ Eat the fruit pulp raw. ▪ Boil shoots and leaves. ▪ Roast seeds.		▪ Tap the trunk for water. Kalahari bushmen suck water through holes in the trunk using the hollow stems of grasses.
▪ Pods ▪ Seeds	▪ Eat the sweet, nutritious pulp of the pods raw. ▪ Grind the seeds into flour and make into porridge.		
▪ Stems	▪ Tap the stems for their water.		▪ The stems contain an appetite suppressant. Kalahari bushmen chew the stems of several *Hoodia* species before and during their long, arduous hunts.
▪ Fruit ▪ Growing tip of the palm (heart) ▪ Young leaves ▪ Sap	▪ Eat the fruit (dates) raw or sun-dried. ▪ Boil the leaves and heart. ▪ Boil the sap down to a syrup.		▪ Date palms always grow near water. The leaves can be used to thatch a shelter.
▪ Fruit ▪ Seeds ▪ Pads	▪ Peel fruit and eat raw. ▪ Roast and grind seeds to a flour. ▪ Boil or grill young pads, first removing thorns by peeling or scorching over a fire.	▪ Spines. Avoid any similar-looking plant that has milky sap as it may be poisonous.	▪ The non-milky sap from the pads is a good source of water.
▪ Fruit (Tsamma melon only) ▪ Flowers ▪ Seeds ▪ Young leaves and shoots	▪ Pound fruit to a pulp and eat raw. ▪ Eat the flowers raw. ▪ Roast or boil seeds. ▪ Chew leaves and shoots for water.	▪ The fruit of the wild desert gourd or colocynth (*Citrullus colocynthis*) is very bitter and is a strong laxative.	▪ The Tsamma melon (*C. lanatus*) is also known as the wild watermelon. The fruit pulp is a good source of water.

WILD FOOD

A GREAT NUMBER OF PLANTS flourish in the tropics, growing all year round in the warm and humid conditions—those listed below are just a few of the most common varieties. When you plan your trip, you should familiarize yourself with the edible plants in the region you are visiting. In tropical forests, most fruits are borne high in the canopy—out of reach,

NAME	WHERE	IDENTIFICATION	EDIBLE PART
BAMBOO *Bambuseae*	▪ Tropical and subtropical forests.	▪ Tree-like grasses with woody, segmented, hollow stems ranging from black to green to gold in color. Green blade-like leaves. Species range in height from 1⅔–11½ ft (0.5–3.5 m).	▪ Young shoots ▪ Seeds
BANANA AND PLANTAIN *Musa* spp.	▪ Native to Australia and Southeast Asia; introduced to other tropical regions.	▪ Tree-like herbaceous plants up to 33 ft (10 m) tall. Large, green, strap-like, split leaves. Flowers and fruit grow in dense hanging clusters.	▪ Fruit ▪ Buds and flowers ▪ Shoots and young stems ▪ Roots
BRAZIL NUT *Bertholletia excelsa*	▪ Along river banks in rain forests in South America.	▪ Large dry-season deciduous tree up to 150 ft (45 m) tall. Green, oblong, crinkly leaves. Yellow flowers. Fruit is the size of a coconut with a hard, woody shell and contains 8–24 seeds.	▪ Seeds or "nuts"
CEYLON/VINE SPINACH *Basella alba*	▪ Widespread in tropical forests.	▪ Trailing, vine-like plant reaching 100 ft (30 m) in length. Beet-red stems. Fleshy, oval or heart-shaped, green or red-purple leaves.	▪ Young leaves and stems
FIG *Ficus* spp.	▪ Variety of habitats in tropical and subtropical regions.	▪ Evergreen tree with long aerial roots growing from the trunk and branches. Leathery green leaves. Pear-shaped fruit grow directly from the trunk or branches.	▪ Ripe fruit
PAPAYA/PAWPAW *Carica papaya*	▪ Native to tropical rain forests in the Americas; introduced to other tropical and some temperate regions.	▪ Small tree up to 20 ft (6 m) high, with a soft hollow trunk. Large green leaves have seven lobes. Large melon-like fruit turn yellow or orange when ripe.	▪ Fruit ▪ Young flowers, leaves, and stems
PEANUT *Arachis hypogaea*	▪ Native to tropical rain forests in the Americas; introduced to other tropical and some temperate regions.	▪ Small, bushy plant up to 1⅔ ft (50 cm) tall. Paired, oval green leaves grow four to a stem. Yellow flowers. Underground legume (pod) contains 1–4 nuts.	▪ Seeds or "nuts"
SAGO PALM *Metroxylon sagu*	▪ Damp lowlands of tropical rain forests in Southeast Asia; introduced elsewhere.	▪ Spiny-trunked palm up to 33 ft (10 m) tall. Crown of pinnate (feather-like) green leaves.	▪ Pith ▪ Young shoots ▪ Young nuts
WATER LILY *Nymphaea*	▪ Lakes, ponds, and rivers in tropical and subtropical regions worldwide. Also found in temperate regions.	▪ Flat, green, heart-shaped leaves float on surface of water. Large, white, yellow, pink, or blue fragrant flowers.	▪ Tubers ▪ Stems ▪ Seeds

unless you can climb the tree. Only eat plants that you can positively identify. If you are in any doubt at all, carry out the Universal Edibility Test (UET) first (see pp. 206–07). Don't forget that some plants are edible only at certain stages of their growth. Don't eat wild plants if you have a known allergy, a preexisting medical condition, or are pregnant.

PREPARATION	SIMILAR PLANTS	BEWARE OF	EXTRA INFORMATION
▪ Split the tough outer sheath of the shoots, and boil or steam. ▪ Boil the seeds or grind, mix with water, make into cakes, and bake.		▪ Shoots of the giant bamboo or volohosy (*Cathariostachys madagascariensis*) contain prussic acid (cyanide).	▪ Bamboo stems often hold water (see p. 190). The stems can be used for cooking (see p. 204) and building a shelter (see p. 169).
▪ Fruit and flowers are edible raw or cooked. ▪ Cook shoots, stems, and roots.			▪ Banana and plantain fruit is rich in potassium and vitamins A, B6, and C. Hard, unripe plantain fruit is only edible when cooked.
▪ Break fruit capsule open, crack the nut's shell, and eat raw.	▪ The sapucaia tree (*Lecythis* spp.) produces edible seeds in a similar fruit capsule. They are called paradise nuts.		▪ Ripe fruit capsules fall to the ground. Rodents and monkeys are attracted to the nuts, which are rich in fats and selenium.
▪ Steam, boil, stew, or stir-fry the leaves and stems.		▪ Don't eat too much, as the plant can have a mild laxative effect.	▪ Young leaves and stems are rich in vitamins.
▪ Eat the fruit raw or cooked.		▪ Don't eat any hard, woody fruit, or those covered in hairs.	▪ Edible figs are soft when ripe and green, red, or black in color.
▪ Flesh of ripe fruit is edible raw. Unripe fruit is edible cooked. ▪ Flowers, leaves, and stems must be boiled, and the water must be changed at least once.		▪ Don't get the milky juice of green, unripe fruit in your eyes as it will cause temporary blindness.	▪ Ripe fruit is rich in vitamin C. Unripe fruit will ripen quickly if placed in the sun.
▪ Remove the shell and eat the nuts raw.		▪ Don't handle or eat if you are allergic to peanuts.	▪ Peanuts are a good source of protein, B vitamins, and minerals.
▪ Crush the pith, knead it in water, strain into a pot, and let the fine sago settle. Squeeze and let it dry. Mix to a paste with boiling water.	▪ Many palms have edible parts. The sugar palm (*Arenga pinnata*) has an edible sap which can be boiled down to a thick syrup.	▪ Don't eat a palm's fruit unless you have positively identified it as an edible variety as the fruit of some species contain harmful crystals.	▪ A mature palm will yield 330–660 lb (150–300 kg) of sago starch—almost pure carbohydrate.
▪ Peel and slice the tubers, which can be eaten raw. ▪ Stems are best cooked. ▪ Dry and grind the seeds into flour.	▪ All parts of the lotus (*Nelumbo* spp.) are edible raw or cooked.		▪ The tubers are rich in starch. The seeds have a bitter taste but they are edible.

WILD FOOD

WHEN PREPARING FOR YOUR TRIP, you should familiarize yourself with the edible plants in the region you are visiting and their seasonal availability. Only eat plants that you can positively identify and, if you are in any doubt at all, carry out the Universal Edibility Test (UET) first (see pp. 206–07). Don't forget that some plants are edible only

	NAME	WHERE	IDENTIFICATION
LICHENS	**ICELAND MOSS** *Cetraria islandica*	▪ Mountainous areas in Arctic, sub-Arctic, and cold temperate regions in North America and Europe; lava slopes and plains of Iceland.	▪ Mat-forming lichen, up to 4 in (10 cm) high. Gray-green to pale chestnut branches, rolled into tubes terminating in flattened lobes with fringed edges.
	REINDEER MOSS *Cladonia rangiferina*	▪ Tundra, bogs, and open woodlands in Arctic, sub-Arctic, and northern temperate regions.	▪ Mat-forming lichen, 2–4 in (5–10 cm) high. Gray, rounded branches resemble antlers.
	ROCK TRIPE *Umbilicaria* spp.	▪ On rocks in Arctic, sub-Arctic, and northern temperate regions.	▪ Rounded lichens with curling edges, usually gray or brown.
PLANTS	**ARCTIC WILLOW** *Salix arctica*	▪ Tundra in North America, Europe, and Asia; mountainous areas in some northern temperate regions.	▪ Mat-forming shrub, 1–2 ft (30–60 cm) high. Rounded, shiny green leaves. Flowers grow as yellow catkins.
	BEARBERRY *Arctostaphylos uva-ursi*	▪ Mountainous areas in Arctic and sub-Arctic regions.	▪ Dwarf evergreen shrub. Thick, leathery, club-shaped green leaves. Pink or white flowers. Bright red berries grow in clusters.
	BOG LABRADOR TEA *Rhododendron groenlandicum*	▪ Bogs and alpine areas in Arctic, sub-Arctic, and temperate regions in North America and Europe.	▪ Evergreen shrub, 1–3 ft (30–90 cm) high. Narrow, leathery, green leaves are hairy underneath and fragrant. Small, fragrant, white flowers grow in clusters and are sticky.
	CLOUDBERRY *Rubus chamaemorus*	▪ Bogs, marshes, and wet meadows in alpine and sub-Arctic regions of North America, Europe, and Asia.	▪ Perennial shrub, 4–10 in (10–25 cm) high. Soft, green leaves have 5–7 lobes. White flowers have five petals. Rasberry-sized, amber berries grow at the top of the plant.
	CROWBERRY *Empetrum nigrum*	▪ Tundra, moorlands, bogs, and spruce forests in Arctic, sub-Arctic, and northern temperate regions. Also found in the Andes.	▪ Dwarf, evergreen, mat-forming shrub. Short, pale green, needle-like leaves. Small, purple-red flowers. Black berries.
	KERGUELEN CABBAGE *Pringlea antiscorbutica*	▪ Rocky areas of sub-Antarctic islands in the Indian and Southern Oceans.	▪ Cabbage-like plant.

PLANTS IN COLD CLIMATES

at certain stages of their growth. Don't eat wild plants if you have any known allergies, a preexisting medical condition, or are pregnant. There are no poisonous types of lichen (althought see rock tripe entry, below), but they must all be soaked in water overnight and boiled well before they can be eaten.

EDIBLE PART	PREPARATION	BEWARE OF	EXTRA INFORMATION
▪ All	▪ Soak for several hours then boil well.	▪ All lichens contain an acid that will cause stomach irritation unless soaked and boiled before eating.	▪ Lichens are low in protein but high in carbohydrates (lichen-starch).
▪ All	▪ Soak for several hours then boil well.	▪ All lichens contain an acid that will cause stomach irritation unless soaked and boiled before eating.	▪ High in vitamins A and B. Important source of food for reindeer (caribou). Partially digested lichens from the reindeer's stomach are considered a delicacy by herders.
▪ All	▪ Soak for several hours then boil well.	▪ There have been some reports of rock tripe poisoning so apply the Universal Edibility Test first.	
▪ Young shoots ▪ Leaves ▪ Young roots	▪ Peel off outer bark and eat inner shoots raw. ▪ Eat the leaves raw. ▪ Peel roots and eat raw.		▪ Arctic willow leaves have 7–10 times more vitamin C than an orange.
▪ Berries	▪ Cook before eating.	▪ Bears feeding on the berries.	▪ Forms mats in Arctic regions.
▪ Leaves	▪ Infuse to make tea.		▪ Pick individual leaves rather than whole branches and harvest from several shrubs. Northern Labrador tea (*R. tomentosum*) leaves also make a fragrant tea. The plant grows in peaty soils and on tundra.
▪ Berries	▪ Edible raw.	▪ Bears feeding on the berries.	▪ Berries initially pink, ripening to amber in fall. High in vitamin C.
▪ Berries	▪ Eat raw or cooked.	▪ Bears feeding on the berries.	▪ Previous year's berries will last on plant until spring if not picked. Fresh berries can be dried for storage. Low in vitamins.
▪ Leaves	▪ Boil well.		▪ Leaves have a bitter taste so must be well-boiled. High in potassium and vitamin C. Antarctic explorers and whalers used to eat Kerguelen cabbage to ward off scurvy, hence its scientific name.

WILD FOOD

THERE ARE NO POISONOUS SEAWEEDS, but some may cause gastrointestinal upset. The seaweeds listed below are common and safe to eat if gathered when still growing, but should only be eaten in small quantities at first. Don't eat seaweed if you are short of fresh water to drink. Only eat plants that you can positively identify and, if you are in

	NAME	WHERE	IDENTIFICATION
SEAWEEDS	**GUTWEED** *Enteromorpha* spp.	▪ Saltmarshes and rock pools in cold-temperate waters worldwide.	▪ Pale or bright green, tubular, unbranched stems, 8–16 in (20–40 cm) long.
	KELP *Alaria* spp., *Laminaria* spp., and *Macrocystis* spp.	▪ Rocky coasts of the Atlantic and Pacific oceans.	▪ Very long, strap-like, olive-green to brown fronds. Giant kelp (*M. pyrifera*) is the largest seaweed on Earth, reaching lengths of 150 ft (45 m).
	LAVER *Poryphyra* spp.	▪ Rocky coasts worldwide.	▪ Very thin, irregularly shaped membranous frond, up to 20 in (50 cm) long. Color varies from olive-green to purple-brown or blackish.
SEASHORE PLANTS	**COCONUT PALM** *Cocos nucifera*	▪ Sandy, rocky, and coral coasts in tropics and subtropics worldwide.	▪ Woody perennial tree, up to 72 ft (22 m) tall, with a crown of pinnate (feather-like) leaves. Gray trunk is ringed with growth scars.
	GLASSWORT/ MARSH SAMPHIRE *Salicornia* spp.	▪ Salt marshes and coastal mudflats of western and eastern North America, western Europe, and the Mediterranean.	▪ Bright green, jointed, fleshy stems, 4–12 in (10–30 cm) high. Scale-like leaves and tiny flowers are sunk into the stems.
	ORACHE/SALTBUSH *Atriplex* spp.	▪ Sandy and shingle beaches worldwide.	▪ Sprawling plant with spikes of small, greenish flowers. Pale- or silvery-green leaves are either triangular or spear-shaped, sometimes lobed.
	SCREW PINE *Pandanus* spp.	▪ Tropical coasts from Madagascar to southern Asia and islands in the southwestern Pacific.	▪ Tree up to 30 ft (9 m) tall, supported by stilt-like aerial roots. Strap-like, saw-toothed leaves are grouped in spirals. Large, globular knobbly fruit ripens from green to orange or red.
	SCURVY-GRASS *Cochlearia* spp.	▪ Salt marshes and rocky coasts of northern North America and northern Europe and Asia.	▪ Creeping plant, 4–16 in (10–40 cm) high, with thick, fleshy, dark green, heart-shaped leaves. Small, white, four-petaled flowers.
	SEA BEET *Beta vulgaris maritima*	▪ Salt marshes, shingle beaches, and cliffs in Europe.	▪ Sprawling plant up to 40 in (1 m) high, with glossy green, stems and leaves often tinged red. Tiny green flowers grow in clusters on the stems.
	SEAROCKET *Cakile* spp.	▪ Sandy shores in North America, Europe, Asia, and Australia.	▪ Up to 16 in (40 cm) high with deeply lobed, fleshy, green leaves. Pale lavender, four-petaled flowers.

COASTAL PLANTS

any doubt at all, carry out the Universal Edibility Test (UET) first (see pp. 206–07). Don't eat wild plants if you have any known allergies, a preexisting medical condition, or are pregnant. When planning your trip, it is advisable to familiarize yourself with the edible plants in the region you are visiting and their seasonal availability.

EDIBLE PART	PREPARATION	BEWARE OF	EXTRA INFORMATION
▪ All	▪ Eat raw or dry in the sun and grind to a powder, for ease of storage.		▪ Gutweed is a good indicator of where fresh water runs across a seashore as it is particularly abundant in such sites.
▪ Fronds	▪ Best boiled, though young fronds can be eaten raw.	▪ Large doses of iodine can be harmful.	▪ Sugarwrack (*L. saccharina*) tastes sweet, as its name implies, and can be eaten fried or boiled. Kelp is high in iodine, small amounts of which are needed for good health.
▪ All	▪ Boil, then mash.		▪ The Welsh make a cake of out of laver and oatmeal, called laverbread. The Japanese produce thousands of tons of paper-thin sheets of dried, processed laver, called nori.
▪ Seeds (coconuts)	▪ Drink the milk fresh. ▪ Eat the flesh raw or sun-dried.	▪ Mature coconut milk needs extra water to be digested. It's also a laxative, so don't drink too much.	▪ Green, unripe coconuts are a good source of water (see p. 190). Coconut milk is rich in sugar and vitamins and contains protein. The oily flesh is also nutritious.
▪ Stems	▪ Steam or boil.		▪ Also known as Poor Man's Asparagus. Rock samphire (*Crithmum maritimum*), which is found on cliffs and rocky shores, is unrelated but has edible succulent leaves.
▪ Leaves	▪ Young leaves can be eaten raw, older leaves should be boiled.		▪ *Atriplex* species are restricted to saline soils. As well as coasts, they are also found inland on the shores of alkaline lakes and in deserts. Gray saltbush (*A. cinerea*) is a type of bushfood in Australia.
▪ Fruit	▪ Inner flesh of ripe fruit can be eaten raw. Partly ripe fruit can be eaten if baked for two hours.	▪ The leaves have small, thorn-like spines at the edges, which can scrape and irritate the skin.	▪ Unripe, green fruit is inedible.
▪ Leaves	▪ Eat the leaves raw or pulp and drink.		▪ Scurvy-grass leaves are rich in vitamin C— sailors used to eat (or drink) them to prevent scurvy. They are very bitter, so are best leached in water, but you should eat them in a survival situation.
▪ Leaves	▪ Eat raw or boiled.		▪ Sea beet is the wild ancestor of beets, sugar beets, and Swiss chard.
▪ Leaves ▪ Young pods	▪ Leaves and young pods can be eaten raw.		▪ Searocket leaves have a peppery taste. One species of *Cakile* grows in the deserts of the Arabian Peninsula.

WILD FOOD

ALL MAMMALS ARE EDIBLE, but some species or groups of mammals are in danger of extinction and are protected by law; the mammal groups listed below contain many species that are common in their areas of distribution, and are not usually dangerous if approached and handled correctly. However, when preparing for your trip, you must

	NAME	WHERE	IDENTIFICATION
AERIAL	**BATS** *Chiroptera*	- Temperate and tropical regions worldwide.	- The only mammals with true wings and the ability to fly. Wingspans vary from 6 in (15 cm) to over 5 ft (1.5 m) in the large fruit bats, or flying foxes (*Megachiroptera*).
TREES / GROUND	**TREE SQUIRRELS** *Sciurus*	- North and South America, Europe, and temperate parts of Asia.	- Small or medium-sized rodents, with large, bushy tails.
	PORCUPINES *Hystricomorpha*	- North and South America, Africa, and tropical Asia.	- Large, rounded rodents, with a coat of sharp quills.
GROUND / BURROWS	**ANTELOPE AND DEER** *Bovidae* and *Cervidae*	- North and South America, Africa, and Eurasia.	- Hoofed mammals, with long legs and barrel-shaped bodies. Male antelope have permanent horns; male deer have antlers, which they shed and regrow each year.
	GUINEA PIGS *Cavia* spp.	- Northwestern, central, and southeastern South America.	- Small rodent, with dark, coarse fur, short legs, and no tail.
	HEDGEHOGS *Erinaceinae*	- Europe, Africa, and Asia; introduced to New Zealand.	- Small, short-legged insectivorous mammal, with spines on back and sides of body.
	KANGAROOS *Macropus* spp.	- Australia.	- The largest of the marsupials (pouched mammals), with long, strong tails, large back legs, and short forelegs.
	RABBITS AND HARES *Leporidae*	- Most habitats worldwide, from arctic tundra to semi-desert.	- Small or medium-sized herbivorous mammals, with large ears and small, round, furry tails. Fur is usually brown or dark gray; the Arctic hare (*Lepus arcticus*) has a winter coat: white with black ear tips.
GROUND / AQUATIC	**BEAVER** *Castor* spp.	- North America and northwestern Eurasia.	- Large semi-aquatic rodents, with coarse, brown fur, webbed feet, and a flat, scaly tail.
	CANE RATS *Thryonomys* spp.	- Sub-Saharan Africa.	- Large rodents, with coarse, brown fur and a long, naked tail. The greater cane rat (*T. swinderianus*) is semi-aquatic.

MAMMALS

familiarize yourself with those mammals that can be hunted in the region you are visiting and their seasonal movements. Some countries and/or states will require you to have a hunting license or permit. For trapping and preparation methods, see pp. 216–23, and for cooking suggestions, see pp. 204–05.

	HOW TO FIND	BEWARE OF	EXTRA INFORMATION
	▪ Active at night. Roost in colonies in caves and trees during the day. Temperate species hibernate in the winter.	▪ Sharp teeth. Some bats carry rabies or other diseases (see pp. 300–01), so cook the meat thoroughly. Bats are protected in Europe and some parts of North America.	▪ Large, plump, fruit-eating bats, such as the Indian flying-fox (*Pteropus giganteus*), are considered a delicacy in many tropical areas.
	▪ Mostly active by day, feeding in branches and on the ground on shoots, nuts, and birds' eggs. Nest in trees in a range of woodland habitats.	▪ Sharp teeth and claws.	▪ Flying squirrels (*Pteromyini*) are nocturnal, tree-living members of the squirrel (*Sciuridae*) family. They glide from tree to tree rather than fly.
	▪ Some New World porcupines climb trees to feed, but all Old World porcupines spend all their time on the ground across a range of habitats.	▪ Barbed quills (see p. 266 for how to remove).	▪ Slow-moving, so can easily be run down and speared. Unlike most small game, the meat is fatty rather than lean.
	▪ Antelope are mainly found in savanna, or marshland habitats, and deer mainly in woodland, forests, or tundra.	▪ Horns or antlers.	▪ Most active at dawn and dusk. Usually live in groups.
	▪ Feed mostly at dawn and dusk, in shrubby grassland in mountainous regions.	▪ Sharp teeth.	▪ Have communal feeding runways. Traps can be baited with leafy vegetables.
	▪ Habitats range from woodland, hedgerows, and grassland to desert. Feed at night on small animals, such as worms and insects.	▪ Sharp spines. Usually infested with parasites, so handle carefully and cook well.	▪ Traditionally prepared for eating by covering with clay and baking in embers of a fire (see p. 205).
	▪ Live in open savanna woodland, feeding mainly at night on vegetation. Gather at waterholes in times of drought.	▪ Sharp claws and a powerful kick.	▪ Kangaroos are protected in some Australian states, but can be hunted (if you have a permit) in others.
	▪ Rabbits live in burrows, often in large numbers, coming above ground to feed on vegetation, using well-worn runs. Hares live above ground.	▪ Rabbits and hares may be infected with germs, so handle them carefully and cook well. Their meat is very lean, and must be eaten with green vegetables (see p. 220).	▪ In most areas, these are the first animals to try to trap. The European rabbit (*Oryctolagus cuniculus*) is an invasive pest species in Australia.
	▪ Look for the distinctive mud-and-stick lodges in the middle of a pond or lake. Beavers leave the lodge at night to feed on water plants and trees along the riverbank.	▪ Strong, chisel-like teeth. The Eurasian beaver (*Castor fiber*) is protected in many of the countries in which it is found.	▪ Use regular runs along streams. The tail can be eaten as well as the flesh.
	▪ Feed at night on reeds and grasses in marshland and on riverbanks, or on grasses in moist savanna, and on rocky hillsides.	▪ Sharp teeth.	▪ Cane rats are a valuable source of bush meat in West and Central Africa. "True" rats (*Rattus* spp.) are edible but often carry diseases, so handle with care.

WILD FOOD

ALL BIRDS ARE EDIBLE, although a few taste horrible (birds-of-paradise, for example), and pitohuis have poisonous feathers and skin. Some species or groups of birds are in danger of extinction and are protected by law; the bird groups listed below contain many species that are common in their areas of distribution. When planning your trip,

NAMES	WHERE	IDENTIFICATION	
GAMEBIRDS *Galliformes*	▪ Worldwide, except Antarctica.	▪ Typically have plump bodies, small heads, and short, rounded wings. Range in size from quail, which can weigh as little as 2 oz (50 g), to the wild turkey (*Meleagris galloparvo*), which can be as heavy as 22 lb (10 kg).	
OSTRICH *Struthio camelus*	▪ From West to East Africa south of the Sahara, and southern Africa.	▪ The world's tallest and heaviest bird, reaching 220 lb (100 kg), the ostrich is flightless. Long neck and long, strong legs, with two-toed feet. Males have black and white plumage, females brown.	
OWLS *Strigiformes*	▪ Every continent, except Antarctica.	▪ Upright posture and a flattened face with large, forward-facing eyes. Strong, hooked bill and sharp talons (claws).	
PIGEONS AND DOVES *Columbiformes*	▪ Worldwide, except the polar regions.	▪ Plump, full-breasted bodies, with a small head and bill. Thick, soft plumage, which can be brown or gray, or brightly colored in some tropical species.	
STORKS AND HERONS *Ciconiiformes*	▪ Worldwide, except the polar regions.	▪ All have large bodies, with long legs, long necks, and bills. Range height from 10 in (25 cm) for the smallest bitterns to 5 ft (1.5 m) for the largest storks.	
VULTURES *Accipitridae* and *Cathartidae*	▪ All continents, except Antarctica and Australasia.	▪ Large carrion-eating birds, with large wings, powerful feet with sharp talons, and a strongly hooked bill. Head and neck is often bald or sparsely feathered.	
WADERS AND GULLS *Charadriiformes*	▪ Worldwide.	▪ Vary greatly in size and shape, but most have subdued brown, gray, black, or white plumage. Waders (or shorebirds) usually have lightweight bodies and long legs. Gulls have compact bodies.	
WATERFOWL *Anseriformes*	▪ Worldwide, except Antarctica.	▪ Typically have plump bodies, powerful wings, and short legs with webbed feet. Most species have a broad, flattened bill. Ducks usually have short necks, while geese and swans have long necks.	

BIRDS

you must familiarize yourself with those birds that can be hunted in the region you are visiting and their seasonal availability. Some countries and/or states will require you to have a hunting license or permit. For trapping and preparation methods, see pp. 226–29; for cooking suggestions, see pp. 204–05.

HOW TO FIND	BEWARE OF	EXTRA INFORMATION
▪ Wide range of terrestrial habitats, from high mountains, to tropical forests, to Arctic tundra.	▪ Short but sharp beak and claws. In some species (including pheasants), the males have sharp spurs on their ankles.	▪ Nearly all gamebirds feed and nest on the ground. At night, many gamebirds roost in trees.
▪ Open semi-arid plains (from desert to savanna) and open woodland.	▪ Can run fast and deliver a powerful kick. Very protective of eggs in the nest and the young birds.	▪ The eggs are the largest of any bird, weighing 3 lb (1.4 kg). The nests are communal and contain up to 40 eggs.
▪ In most habitats, from tundra to dense forest.	▪ Sharp bill and talons.	▪ Most species hunt at night and roost in trees during the day. Usually nest in holes in trees, under rocky overhangs, or, sometimes, in burrows.
▪ Variety of forest habitats, from open woodland to dense, tropical rain forest, and grassland and semi-arid areas.		▪ Often feed in flocks on the ground or in trees, and usually roost communally in trees. Can be taken by hand from the roost if you approach slowly and quietly.
▪ Freshwater habitats, ranging from wetlands, rivers, lakes, marshes, swamps, mangroves, and lagoons to tidal mudflats.	▪ Sharp bill.	▪ Usually feed alone at the water's edge, but often nest communally in trees.
▪ Open areas, including mountains, plains, deserts, and savannas.	▪ Sharp bill and talons. Handle as little as possible, as prone to parasites and infection. Boil meat for at least 30 minutes.	▪ Carrion eaters and scavengers, such as crows (*Corvus* spp.) and gulls (see below), can be lured into traps baited with meat.
▪ Tundra and a variety of wetland and coastal habitats, including tidal mudflats, beaches, and cliffs.	▪ Sharp bill. Gulls and terns will aggressively defend their nest sites.	▪ Most birds in this group nest on the ground or on rock ledges, laying about four well-camouflaged eggs. Often nest in large colonies.
▪ Arctic tundra, wetlands, rivers, and lakes. Ducks and swans usually feed on the water, while geese graze on the land.	▪ Geese and swans can be very aggressive, particularly in the breeding season. Mute swans (*Cygnus olor*) can weigh up to 26 lb (12 kg).	▪ Many species migrate between their breeding grounds in the Arctic and their wintering grounds further south. They molt their feathers in the late summer, rendering them flightless for a couple of weeks and thus easier to catch.

WILD FOOD

SOME AMPHIBIAN AND REPTILE SPECIES are at risk of extinction and are protected by law; the animals listed below are common in their areas of distribution, and are non-venomous. As part of preparation for your trip, it is advisable to familiarize yourself with the reptiles and amphibians in the region you are visiting. Many countries and/or states

	NAME	WHERE	IDENTIFICATION
FROGS	**AFRICAN CLAWED FROG** *Xenopus* spp.	▪ Sub-Saharan Africa; introduced to North America, South America, and Europe.	▪ Flattened, brown body, 2¼–5 in (6–13 cm) long, with a line of white "stitch marks" along the sides. Clawed toes on the muscular legs.
	AMERICAN BULLFROG *Rana catesbeiana*	▪ North America; introduced to Europe and Asia.	▪ Body is green with brown markings above and white below, 3½–8 in (9–20 cm) long. Large legs and large eardrums.
	SOUTH AMERICAN BULLFROG *Leptodactylus pentadactylus*	▪ Central and northern South America.	▪ Smooth yellow or pale brown body with some dark markings, 3–9 in (8–22 cm) long.
TURTLES	**AFRICAN HELMETED TURTLE** *Pelomedusa subrufa*	▪ Sub-Saharan Africa.	▪ Flattened, brown shell, 8–12½ in (20–32 cm) long.
	ASIAN LEAF TURTLE *Cyclemus dentata*	▪ Southeast Asia.	▪ Oval, light to dark brown shell, 6–9½ in (15–24 cm) long, with serrated edge near tail. Reddish brown head and legs.
	PAINTED TURTLE *Chrysemys picta*	▪ Southern Canada, USA, and northern Mexico.	▪ Flattened, smooth shell, 6–10 in (15–25 cm) long; brown above and yellow below, sometimes patterned. Yellow or red stripes on the neck.
SNAKES	**CARPET PYTHON** *Morelia spilota*	▪ Indonesia, New Guinea, and Australia.	▪ Several subspecies, all of which have a bold pattern of irregular markings, which can be reddish brown, brown, black or gray. Average length is 6½ ft (2 m), but can reach 13 ft (4 m).
	COMMON BOA *Boa constrictor*	▪ Central America, South America, and some Caribbean islands.	▪ Several subspecies but all have characteristic dark saddle markings along the back and a dark stripe behind each eye. Narrow head and pointed snout.
	COMMON EGG-EATING SNAKE *Dasypeltis scabra*	▪ Sub-saharan Africa	▪ Reddish-brown or gray body with dark, angular markings. A slender snake, 28–39 in (70–100 cm) long. Rounded snout.
	COMMON RATSNAKE *Elaphe obsoleta*	▪ Southern Canada, and central and eastern USA	▪ Subspecies coloration varies from bright yellow-orange to pale gray with darker blotches. Length range is 4–6 ft (1.2–1.8 m). Long head with rounded snout.
LIZARDS	**COMMON/VIVIPAROUS LIZARD** *Zootoca vivipara*	▪ Europe, extending to the Arctic Circle, and central to eastern Asia, including Japan.	▪ Body is usually brown olive, sometimes black, with males having bright yellow or orange bellies and females creamy white ones. Length range is 4–7 in (10–18 cm).
	GREEN IGUANA *Iguana iguana*	▪ Central America and northern South America.	▪ Green or grayish body, 3¼–6½ ft (1–2 m) long, including the long striped tail. Long, stout legs for climbing trees. Adults have a fleshy dewlap beneath the throat, which is large in males.
	RAINBOW LIZARD *Agama agama*	▪ West, Central, and East Africa.	▪ Males turn brightly colored in the sun, with an orange-red head and a blue or turquoise body; females and juvenile males remain gray. Length range is 12–16 in (30–40 cm).
	WESTERN FENCE LIZARD *Sceloporus occidentalis*	▪ Southwestern USA and northwestern Mexico.	▪ Brown body with raised, pointed scales. Blue patches on belly are most pronounced in males. Length range is 6–9 in (15–23 cm).

AMPHIBIANS AND REPTILES

will require you to have a hunting license or permit. See p. 218 for some trapping methods and p. 224 for how to prepare the animal for cooking. Avoid brightly colored tropical frogs as they are often highly toxic. In addition, don't eat box turtles, as they sometimes eat poisonous fungi and their flesh may be toxic.

HOW TO FIND	SIMILAR SPECIES	EXTRA INFORMATION
▪ Wetlands and waterholes in savannas and tropical and subtropical forests.		▪ Also known as the African clawed toad.
▪ Wetlands.	▪ All frogs in the *Rana* genus are edible. The genus includes New World true frogs and the European common frog (*R. temporaria*).	▪ American bullfrog legs can be the size of chicken drumsticks. All temperate species of frog hibernate in the winter.
▪ Tropical forests and rain forests.		▪ Active at night. If picked up, the South American bullfrog emits a loud scream to startle the predator into dropping it.
▪ Watering holes and rain pools in open country.		▪ In the rainy season, this turtle wanders from pool to pool to forage. In the dry season, it buries itself in mud.
▪ Shallow streams in mountains or lowlands.		▪ Very active on land and in water.
▪ Lakes, ponds, and slow-moving streams and rivers.		▪ Active by day. You will often find several painted turtles piled up together on a log in the water, basking in the sun.
▪ Wide range of habitats.		▪ The carpet python is non-venomous, but it can inflict a nasty bite. It is one of Australia's most widespread snakes.
▪ Wide range of habitats, from tropical forest to dry savanna.	▪ There are several species in the boa family, which includes the world's largest snake, the green anaconda (*Eunectes murinus*).	▪ Kills its prey by coiling around it and suffocating it. Don't tackle large common boas—they can be up to 13 ft (4 m) long.
▪ Desert and open habitats.		▪ This nocturnal African snake feeds on eggs during the bird-breeding season then fasts for the rest of the year. It has no teeth.
▪ Rocky hillsides with open woodland.	▪ Ratsnakes (*Elaphe* spp.), which include the brightly colored corn snake (*E. guttata*), are found in both the New and Old Worlds.	▪ Like the common boa (see above), all ratsnakes kill their prey by constriction.
▪ Wide range of terrestrial habitats.		▪ There's no point trying to catch a common lizard by its tail as, like many lizards, it can shed the tail and regrow it.
▪ Tropical forest and rain forest.		▪ Defends itelf by lashing out with its tail and claws.
▪ Open habitats.		▪ Rainbow lizard can shed and regrow its tail.
▪ On rocks and other prominent places in temperate and coniferous woodlands.	▪ The eastern fence lizard (*S. undulatus*) is widely distributed across southeastern USA and northeastern Mexico.	▪ Fence lizard can shed and regrow its tail.

WILD FOOD

WHEN PLANNING YOUR TRIP, it is advisable to familiarize yourself with the species of fish in the region you are visiting, their seasonal availability, and the best method of catching them (see pp. 208–09 for how to make tackle and techniques to use in a survival situation). Many countries and/or states will require you to have a fishing

NAME	WHERE	IDENTIFICATION
BARRAMUNDI *Lates calcarifer*	▪ Western and eastern Indian Ocean, and northwestern and western Pacific Ocean.	▪ Up to 6½ ft (2 m) long, with a rounded tail fin. Dark greenish-gray upper body fading to silver below.
COMMON/BRONZE BREAM *Abramis brama*	▪ Europe to Central Asia.	▪ Up to 2¾ ft (82 cm) long, with a deep, narrow, bronze-colored body and a deeply forked tail.
COMMON/KING CARP *Cyprinus carpio*	▪ Europe and Asia; introduced in North America and Australasia.	▪ Up to 5 ft (1.5 m) long, with a dark gold upper body paling to silver below.
EUROPEAN TURBOT *Psetta maxima*	▪ Northeast Atlantic Ocean up to the Arctic Circle and the Mediterranean.	▪ Almost circular flatfish, up to 3¼ ft (1 m) in diameter. Sandy brown with brown or black speckles on top.
NILE PERCH *Lates niloticus*	▪ Northern, central, and eastern Africa.	▪ Up to 6¼ ft (1.9 m) long, with a rounded tail fin. Dark gray-blue upper body fading to silver below.
RUDD *Scardinius erythrophthalmus*	▪ Europe and Asia.	▪ Up to 17 in (45 cm) long, with a deeply forked tail. Dark greenish upper body paling to silver below. Red pelvic, pectoral, and anal fins.
ATLANTIC SALMON *Salmo salar*	▪ North Atlantic and Arctic oceans, and Baltic Sea and adjacent rivers; introduced to Argentina and Australasia.	▪ Up to 5 ft (1.5 m) long, with a powerful, streamlined, silver blue-green body.
TARPON *Megalops atlanticus*	▪ Eastern and western Atlantic Ocean, the Gulf of Mexico, and the Caribbean.	▪ Up to 8 ft (2.5 m) long, with a deeply forked tail. Bright silver body, with large, hard scales.
TENCH *Tinca tinca*	▪ Europe and Asia; introduced in North America.	▪ Olive green upper body, golden below, with a square tail fin. Small barbel at corners of mouth. Average length is 27 in (70 cm).
BROWN TROUT AND SEA TROUT *Salmo trutta*	▪ Temperate waters worldwide.	▪ Streamlined body with an average length of 3¼ ft (1 m). The brown trout has a brownish body flecked with distinctive black and red spots. The sea-going form, the sea trout, is silver-blue with black spots.

FISH

license or permit, and some species of fish can only be caught at certain times of the year. Before fishing, you should also check with the locals that fish in the area are safe to eat—in some regions the waters may be contaminated. See pp. 212–13 for how to prepare a fish for cooking.

HOW TO FIND	SIMILAR FISH	EXTRA INFORMATION
▪ Tropical, slow-moving creeks and estuaries, hiding in mangrove roots and rocky outcrops.		▪ Beware of the sharp dorsal fin.
▪ Bottom of still and slow-moving waters, typically in lakes, rivers and ponds. Swim in large shoals.	▪ Silver bream (*Blicca bjoerkna*) and white-eye bream (*Abramis sapa*).	
▪ Still and slow-moving waters, often among vegetation near banks of lakes or ponds.	▪ Wild carp, mirrored carp, and leather carp are all varieties of the common carp.	
▪ Sandy, rocky, or mixed sea beds in shallow coastal and brackish water.	▪ Other flatfish (*Pleuronectiformes*) found in shallow water, such as sole, plaice, and flounder.	
▪ Lakes and large rivers.	▪ Other perch (*Perciformes*).	▪ Beware of the sharp dorsal fin and teeth (the Nile perch is a voracious predator). This species weighs up to 440 lb (200 kg).
▪ Still and slow-moving waters, often near banks of ponds and marshlands.	▪ Roach (*Rutilus rutilus*)	
▪ Cold, fast-flowing rivers and coastal waters.	▪ Pacific salmon (*Oncorhynchus* spp.)	▪ The salmon run (when the fish migrate from the sea to their birth rivers) is in the autumn, with spawning between November and January.
▪ Estuaries, lagoons, tidal flats and mangrove swamps. Feed in shoals.	▪ Indo-Pacific tarpon (*M. cyprinoides*), which is smaller and rarer.	▪ This species is hard to hook because of its bony mouth. It weighs up to 160kg (350lb).
▪ Still and slow-moving waters, in ponds, lakes and rivers. The best time of day to catch tench is at dawn, at the edges of dense vegetation.		
▪ Streams, rivers, lakes, and coastal waters.	▪ Rainbow trout and steelhead trout (*Oncorhynchus mykiss*) and the cutthroat trout (*O. clarki*).	▪ Sea-going forms migrate from the sea to rivers to spawn in the autumn. Beware of small bones when eating.

WILD FOOD

SOME SPECIES OF INVERTEBRATE are in danger of extinction and are protected by law; the animals listed below are common in their areas of distribution. When preparing for your trip, it is advisable to familiarize yourself with the edible invertebrates in the region you are visiting and the best way to catch them (see p. 219 for some techniques to use in a survival

	NAME	WHERE	IDENTIFICATION
MOLLUSCS	**COMMON/BLUE MUSSEL** *Mytilus edulis*	▪ Intertidal zones of estuaries and coasts of North and southeastern Atlantic and northeastern and southwestern Pacific.	▪ Dark-shelled bivalve, reaching 4–6 in (10–15 cm) in length.
	GIANT AFRICAN LAND SNAILS *Achatina* spp.	▪ Sub-tropical and tropical parts of Africa; introduced to the Asia-Pacific region.	▪ Large terrestrial snails, reaching up to 12 in (30 cm) in length when body is extended, and 4 in (10 cm) in diameter. Whorled, conical, brownish shell with darker bands.
ARTHROPODS	**GRASSHOPPERS** *Acrididae*	▪ Worldwide, on vegetation and the ground.	▪ Winged insects with powerful hindlegs, $\frac{2}{5}$–$3\frac{1}{4}$ in (1–8 cm) long, usually with camouflage coloring and patterning.
	HONEYPOT/HONEY ANTS *Myrmecocystus* spp.	▪ Semi-arid and arid regions of southwest USA, Mexico, Africa, and Australia.	▪ Segmented bodies with six legs and a pair of antennae, and a constricted waist. Range in colour and size, from $\frac{1}{10}$–$\frac{1}{2}$in (2–12mm). Special members of the colony, called repletes, have abdomens that can swell to the size of a grape.
	WITCHETTY GRUB *Endoxyla leucomochla*	▪ Underground, in the roots of the witchetty bush (*Acacia kempeana*), central Australia.	▪ The larva of this species of cossid moth reaches about $2\frac{3}{4}$ in (7 cm) in length. It is white with a brown head.
CRUSTACEANS	**CRAYFISH/CRAWFISH/ YABBIES/KOURAS** *Astaclidea*	▪ Worldwide, in freshwater streams.	▪ Segmented bodies, which can be sandy yellow, green, dark brown, or blue-gray in color. Ten legs, the front two of which are large claws. Average length is 4 in (8 cm), but some species grow much larger.
	WOODLICE *Oniscidea* and *Armadillidiidae*	▪ Worldwide, in damp terrestrial microhabitats, such as in rotting wood and leaf litter.	▪ Flattened, segmented bodies up to $\frac{3}{4}$ in (2 cm) in length. Gray or light brown or black in color. Pill millipedes will roll up into a ball when threatened.
WORMS	**COMMON EARTHWORM** *Lumbricus terrestris*	▪ Temperate regions of Europe; introduced to most parts of the world.	▪ Reddish worm, reaching 14 in (35 cm) in length when extended.

INVERTEBRATES

situation). Many countries and/or states will require you to have a hunting license or permit, and some species of shellfish can only be caught at certain times of the year. Also check with the locals that the shellfish are safe to eat—in some regions the waters may be contaminated. See pp. 224–25 for some preparation and cooking methods.

SIMILAR INVERTEBRATES	BEWARE OF	EXTRA INFORMATION
▪ Most species of marine and freshwater bivalves and univalves are edible if alive and healthy when gathered.	▪ Don't collect marine shellfish that aren't covered at high tide. The black mussel (*Musculus niger*), found in Arctic waters, can be poisonous year-round. Mussels in tropical zones are poisonous during the summer.	▪ Healthy bivalves should close their shells when tapped and the shells should open when cooked. Healthy univalves, such as limpets, should be difficult to pry off the rocks on which they live.
▪ Many terrestrial and freshwater snails are edible. The winkle or common periwinkle (*Littorina littorea*) is an edible sea snail.	▪ Avoid any terrestrial snails with brightly colored shells and all sea snails unless you can positively identify them as an edible species, as they may be poisonous.	▪ Snails should be starved for 24 hours or fed a diet of edible green leaves to purge their guts before cooking. Boil for at least 10 minutes.
▪ Most species of cricket (*Gryllidae*) and katydid (*Tettigoniidae*) are edible.	▪ Avoid any brightly colored grasshoppers as they may be toxic.	▪ Remove the antennae, wings, and leg spurs, and roast to kill any parasites.
▪ Most species of ant are edible if gathered carefully. The larvae of wood ants (*Formica* spp.) in northern temperate regions make a nutritious meal in summer months. The abdomen of the green or weaver ant (*Oecophylla smaragdina*) found in southeast Asia and Australia tastes like citrus sherbert. Termites (*Isoptera*) are also edible. See p. 219 for catching methods.	▪ Most species of ant are aggressive in defense of their nest and have a stinging bite. Some will then squirt formic acid at the site of the bite.	▪ The swollen abdomens of the repletes contain a nutritious fluid. ▪ The repletes live deep underground in the ants' nest so you would have to dig them out.
▪ The term "witchetty grub" is also applied to the edible larvae of other cossid moths, ghost moths (*Hepialidae*), and longhorn beetles (*Cerambycidae*). Palm grubs are the edible larvae of the palm weevil (*Rhynchophorus* Spp.). They live in the trunks of sago palms (see pp. 284–285) in Southeast Asia.	▪ Do not eat any insect larvae that are already dead when you find them, or that look sick, smell bad, or that irritate the skin if handled.	▪ Should be eaten raw or roasted quickly in hot embers.
▪ Marine decapods such as crabs, lobsters, and prawns are also edible.	▪ May contain harmful parasites so cook well.	▪ Keep alive until ready to eat. See p. 225 for preparation and cooking methods.
		▪ Boil or fry gently. Will turn slightly pink, like shrimp, when cooked.
▪ All earthworms are edible.		▪ The common eathworm is unusual in that it feeds at the surface, making it easier to find and gather than other worms.

NATURAL DANGERS

FOR INFORMATION ON LARGER dangerous animals, such as bears, big cats, and sharks, and venomous animals, such as snakes, see pp. 242–43. When planning your trip, it is advisable to familiarize yourself with the potentially harmful wildlife in the region you are visiting, the nature of the threat, and how to avoid it if possible. In the case of suspected

	NAME	WHERE	IDENTIFICATION
MAMMALS	**VAMPIRE BATS** *Desmodontinae*	▪ In rain forests, deserts, and grasslands, from Mexico to northern and central South America.	▪ Small bats, with a body length of 2¾–3½ in (7–9 cm) and a wingspan of 14–16 in (35–40 cm). Dark brownish gray fur, paler on the belly. Razor-like upper incisors.
	RATS *Rattus* spp.	▪ Worldwide, except for the polar regions.	▪ Medium-sized rodents, with a minimum body length of 5 in (12 cm), and long, naked tails. Coarse brown, gray-brown, or black fur, paler on belly. Pink feet.
SNAKES	**SPITTING COBRAS AND RINKHALS** *Naja* spp. and *Hemachatus haemachatus*	▪ Warm temperate, subtropical, and tropical regions of Asia and Africa.	▪ Pale brown to black snakes up to 6 ft (2 m) long. When threatened, will rear up and spread their hoods, revealing striped patterns on their necks.
FISH	**ELECTRIC EEL** *Electrophorus electricus*	▪ Amazon and Orinoco river systems, South America, often in shallow water.	▪ Not a true eel, but an eel-like fish up to 8¼ ft (2.5 m) long and can be as thick as a human thigh. Continuous fin along lower body.
	STONEFISH *Synanceia verrucosa*	▪ In tropical coastal waters of northern Indian Ocean and southwestern Pacific Ocean.	▪ Up to 16 in (40 cm) long, this lumpy fish can match its color to the rock or sediment on which it lies while waiting for passing prey. Venomous spines in the dorsal fin.
OTHER ANIMALS	**BOX JELLYFISH/ SEA WASPS** *Cubomedusae*	▪ At the surface of tropical waters of southwest Pacific and eastern Indian Ocean.	▪ Box-shaped, transparent jellyfish, up to 10 in (25 cm) in diameter. Up to 15 long tentacles, which bear stinging cells, at each corner.
	CENTIPEDES *Chilopoda*	▪ In soil, leaf litter, cracks, and crevices in temperate, subtropical, and tropical regions worldwide.	▪ Elongated, flattened bodies divided into at least 16 segments, most of which have one pair of legs. Tropical species are typically brightly colored—yellow, red, orange, or green—with dark stripes. The world's largest centipede, *Scolpendra gigantea*, reaches 12 in (30 cm) in length.
	CONE SHELLS/ CONE SNAILS *Conidae*	▪ In inter-tidal zones and on coral reefs in warm temperate, subtropical, and tropical seas and oceans worldwide.	▪ Brightly colored and patterned, cone-shaped shells, up to 9 in (23 cm) long. These predatory snails have venomous, harpoon-like mouthparts.

WILD ANIMALS

poisoning, call the emergency services immediately. For further information regarding treatment for bites and stings, see pp. 266–67. If a casualty becomes unconscious, open the airway and check breathing (see p. 276). Be ready to begin CPR—chest compressions and rescue breaths (see p. 277), use a plastic face mask or face shield, if you have one.

	DANGER	TREATMENT	HOW TO AVOID
	▪ Many mammal species are infected with rabies, but because vampire bats feed by biting their victims, then lapping blood from the wound, the virus can be transmitted via their saliva. Symptoms include fever, headache, fear (especially of water), and seizures.	▪ If bitten by a vampire bat, or other potentially rabid mammal, clean the wound thoroughly and seek immediate medical help. Symptoms usually appear 2–8 weeks after infection, by which time the disease is almost always fatal.	▪ Vampire bats roost in hollow trees and caves, emerging at night to feed. Don't shelter in bat caves (bat dung can cause a respiratory disease). Keep covered at night, and sleep under a mosquito net. Get vaccinated before traveling to a high-risk area.
	▪ Can be infested with parasites and can also carry infectious diseases. Leptospirosis is a water-borne bacterial disease spread by infected rats' urine; the acute form in humans is called Weil's disease.	▪ If you've been in contact with potentially contaminated water and develop flu-like symptoms (fever, headache, muscle pain) you must get your blood tested as soon as possible. Antibiotics are effective in the early stages of the disease.	▪ If handling a rat, beware of its teeth and claws, and wash thoroughly afterward. Cook the meat thoroughly. In rat-infested areas avoid getting water into any cuts; if you do, wash with soap and boiled water.
	▪ Will eject a fine spray of venom from their fangs upward the eyes of an aggressor. Causes intense pain, tearing, and discharge from the eyes, spasm and swelling of the eyelids. Ulceration of the cornea can lead to infection resulting in blindness.	▪ Call the emergency services. Rinse the eyes with cool water for 10 minutes. Apply an antibiotic eye ointment.	▪ If you come across a spitting cobra, try to remain completely still and allow the snake to move away, if possible (see p. 243).
	▪ Can generate shocks of up to 600 volts, used to stun or kill prey when hunting, or in self-defense. Such a shock can be discharged up to 8 hours after its death, and is potentially lethal to humans.	▪ Call the emergency services. If the casualty becomes unconscious, open the airway and check breathing (see p. 276). Be ready to begin CPR (see p. 277).	▪ Keep your boots on if crossing a tributary and take care when washing. These waters are also home to piranhas (*Serrasalminae*), which have razor-sharp teeth.
	▪ The world's most venomous fish. If trodden on, the spines inject poison into the puncture wound. This is extremely painful and can be fatal. The injured body part will swell and muscular paralysis may set in.	▪ Call the emergency services—anti-venin is available. Immerse the injured part in water as hot as the casualty can stand for at least 30 minutes (see p. 267). Don't immobilize the injured limb. Be ready to begin CPR if the casualty loses consciousness (see pp. 276–77).	▪ Wear something on your feet when walking in shallow water. Weaverfish (*Trachinidae*) and scorpionfish (*Scorpaenidae*) also have venomous stings; the treatment is the same.
	▪ Sting is extremely painful—it will damage the skin and can cause permanent scarring. In severe cases, box jellyfish (*Chironex fleckeri*) stings can lead to cardiac arrest and death within minutes.	▪ Call the emergency services—anti-venin is available. Flood the stung area with vinegar or sea water for at least 30 seconds to neutralize the stinging cells (see p. 267). Be ready to begin CPR if the casualty loses consciousness (see pp. 276–77).	▪ Never touch jellyfish, even when dead. All jellyfish, sea anemones, corals, and the Portuguese man-of-war (*Physalia physalis*) release venomous cells when touched. Some are more toxic than others.
	▪ Have a pair of large, venomous claws on their heads, which in some species can be dangerous to humans. The sting is painful and leads to swelling. May result in anaphylactic shock.	▪ Call the emergency services. Apply a cold compress for at least 10 minutes to reduce pain and swelling. Monitor the casualty for anaphylactic shock (see p. 274) and be ready to begin CPR (see p. 277).	▪ As a general rule, avoid all multiple-legged arthropods. If you discover one on your body, gently brush it off in the direction in which it is walking.
	▪ Will fire its harpoon in self-defense if touched. Sting of most species is painful; that of the larger tropical species can be fatal. Symptoms include swelling and numbness, and may be followed by severe breathing difficulties.	▪ Call the emergency services and treat as for snake bite (see p. 266). Monitor the casualty for shock (see p. 274) and be ready to begin CPR (see p. 277).	▪ Don't pick up any cone shells in rock pools or when snorkeling or diving. (There is no anti-venin: treatment entails providing life support until the venom is metabolized by the casualty's body.)

NATURAL DANGERS

IN THE CASE OF SUSPECTED POISONING from a spider bite or a scorpion sting, you must call the emergency services immediately. For further information regarding treatment for bites and stings, see pp. 266–67. If a casualty becomes unsconscious, open the airway and check breathing (see p. 276). Be ready to begin CPR—chest compressions and rescue

	NAME	WHERE	IDENTIFICATION
INSECTS	**BEES, WASPS, AND HORNETS** *Hymenoptera*	▪ In a variety of terrestrial habitats worldwide.	▪ Narrow-waisted bodies, often striped black and yellow. Bees are hairy, while wasps and hornets have hairless bodies. Up to 1½ in (3.5 cm) long. Bees have barbed stingers, wasps and hornet stingers are smooth.
	MOSQUITOES *Culicidae*	▪ In a variety of terrestrial habitats near water worldwide, especially in warmer regions.	▪ Narrow bodies and long, slender legs. Up to ¾ in (2 cm) long. Females have syringe-like mouthparts for piercing skin.
ARACHNIDS	**BROWN RECLUSE/ FIDDLEBACK SPIDER** *Loxosceles reclusa*	▪ Southern midwestern states of USA, south to the Gulf of Mexico.	▪ Small brown spider, about ½ in (1.25 cm) long) with a distinctive dark, violin-shaped mark on the back of its cephalothorax (head).
	FUNNEL-WEB SPIDERS *Atrax robustus* and *Hadronyche* spp.	▪ Moist, cool, sheltered habitats in eastern and southern Australia.	▪ Large spiders, up to 1½ in (4.5 cm) long, with glossy dark brown or black bodies and short legs.
	TARANTULAS *Theraphosidae*	▪ Deserts and forests in subtropical and tropical regions worldwide.	▪ Very large spiders with bodies up to 5 in (12 cm) long and a legspan of up to 11 in (28 cm). Bodies and legs are covered in bristly hairs. Pale brown to black in color, with pink, red, brown, or black markings.
	WIDOW SPIDERS *Latrodectus* spp.	▪ Warm temperate, subtropical, and tropical regions worldwide.	▪ Small spiders, with dark, glossy bodies and distinctive red, yellow, or white markings on the abdomen, which are shaped like an hourglass in some species.
	SCORPIONS *Scorpiones*	▪ Deserts, grasslands, woodland, and forests in warm temperate, subtropical, and tropical regions worldwide.	▪ Segmented bodies, with large, claw-like pedipalps and sting-bearing tails. Yellow, brown, or black bodies, 3–8 in (8–20 cm) long, depending on the species.
	TICKS *Ixodidae*	▪ Grassland and woodland habitats worldwide.	▪ Rounded bodies with no distinct divisions. Yellow to red- or black-brown in color. Up to ⅖ in (1 cm) long, but larger after feeding. They have spiked mouthparts, which they use to attach themselves to the skin of warm-blooded animals to feed on their blood.

INSECTS AND ARACHNIDS

breaths (see p. 277). If you need to give rescue breaths and there is poison in the casualty's mouth, or on his or her face, use a plastic face mask or face shield, if you have one. Before your trip, it is advisable to familiarize yourself with the harmful insects and arachnids (spiders, scorpions, and ticks) in the region you are visiting, and the nature of the threat.

	DANGER	TREATMENT	HOW TO AVOID
	▪ When a bee stings you, the stinger is ripped out of its body with the venom sac. Wasps and hornets can sting repeatedly. The stings are painful, followed by redness and swelling. A single sting may result in anaphylactic shock (see p. 274)	▪ Scrape the sting off sideways at the base of the sting if it is visible, using a fingernail or a credit card. Raise the affected part and place a cold compress against it for at least 10 minutes (see p. 267). Monitor for signs of allergic reaction.	▪ Watch out for flowers where bees may be feeding. Be careful when gathering fruit, or cleaning fish or game, as wasps or hornets will be attracted to the smell. Don't disturb their nests.
	▪ Female mosquitoes feed on blood and their bites can irritate the skin. They are carriers of infectious diseases such as malaria, yellow fever, and dengue fever.	▪ Apply an antihistamine cream to the bites if they itch, and do not scratch them, as there is a risk of infection. If casualty develops a headache and fever, get medical help. Get casualty to rest, drink plenty of water, and take anti-malarials, if directed.	▪ Cover your arms and legs after sunset, use mosquito repellent, and sleep under a mosquito net. Take anti-malarial medication as directed. Get a yellow fever vaccination before traveling, where advised.
	▪ Bite can cause fever, chills, vomiting, and, pain in the joints. In most cases the bite is minor, but in some cases the tissue around the wound will die, leaving a deep scar. Rarely fatal.	▪ Sit casualty down, treat as for snakebite (see p. 266), and call the emergency services. Apply a cold compress to the site of the sting. Monitor for signs of allergic reaction, such as wheezing, and anaphylactic shock (see p. 274).	▪ This spider likes to hide in dark places, so be careful where you put your hands and bare feet, and always check your bedding.
	▪ Bite is very painful and cause profuse sweating, nausea, vomiting, tingling around the mouth and tongue, salivation, and weakness. Rarely fatal.	▪ Sit casualty down, treat as for snakebite (see p. 266), and call the emergency services—anti-venin is available. Monitor for signs of allergic reaction and anaphylactic shock (see p. 274).	▪ Take care when moving rocks and logs.
	▪ Bite can be painful but is only mildly venomous. If provoked, tarantulas will flick irritating hairs from their abdomen which will cause itching and swelling of the skin and nasal passages, and watering of the eyes.	▪ Give pain relief and apply a cold compress to the site of the bite. Monitor for signs of allergic reaction, such as wheezing, and anaphylactic shock (see p. 274). Wash any hairs away with cool water.	▪ Tarantulas are nocturnal and hunt prey in trees and on the ground. Move away if you disturb one; don't touch it.
	▪ Bite is painful and results in localized redness and swelling. More severe reactions include profuse sweating, abdominal and chest pains, nausea, and vomiting. Rarely fatal.	▪ Apply a cold compress (ice if available) and give pain relief. If symptoms worsen, call the emergency services – anti-venin is available. Monitor for signs of allergic reaction, such as wheezing, and anaphylactic shock (see p. 274).	▪ Widow spiders, which include Australia's redback spider (*L. hasselti*), build their webs in dry, sheltered spots, such as in shrubs or among rocks or logs, so take care when moving among them.
	▪ Scorpion stings can be very painful and may cause severe illness. A few species have neurotoxins in their venom, resulting in temporary paralysis for 1-2 days. Rarely fatal and only in young children, the elderly, or the ill or infirm.	▪ If swelling occurs, sit casualty down, treat as for snake bite (see p. 266). Apply an ice pack or cold compress to the site of the sting. Call the emergency services, monitor for anaphylactic shock (see p. 274) and allergic reaction. Try to identify the scorpion.	▪ Scorpions are mostly nocturnal and take shelter during the day. Check your boots and clothing before putting them on and check your bedding at night. Take care when gathering firewood or turning over rocks.
	▪ Ticks are carriers of infectious diseases such as Lyme disease and Rocky Mountain spotted fever. Sufferers of Lyme disease may develop a red, ringed "bull's-eye" skin lesion at the bite site.	▪ Carefully remove an attached tick with tweezers or a specialized tool (see p. 267). Clean and monitor the wound for symptoms. Get medical help if casualty develops a severe headache, stiff neck, or a fever.	▪ Wear light-shaded, tightly woven clothing and apply tick repellent. Check your skin and clothing for ticks at regular intervals.

NATURAL DANGERS

IN THE CASE OF SUSPECTED PLANT POISONING, you must call the emergency services immediately. If a casualty becomes unconscious, open the airway and check their breathing (see p. 276). Be ready to begin CPR—chest compressions and rescue breaths (see p. 277). If you need to give rescue breaths, use a plastic face mask or face shield, if you have one, to

	NAME	WHERE	IDENTIFICATION	POISONOUS PART
CONTACT POISONING	**COWHAGE/COWAGE/ COWITCH** *Mucana pruriens*	▪ Scrub and light woodland in the the tropics and USA.	▪ Vine-like plant with green, oval leaflets growing in threes. Spikes of hairy, dull purplish flowers. Hairy brown seedpods.	▪ Flowers ▪ Pods
	POISON IVY *Toxicodendron radicans*	▪ Wooded areas in North America; widely introduced elsewhere.	▪ See p. 268 for illustration.	▪ All
	WHITE/GRAY MANGROVE *Avicennia marina*	▪ Mangrove swamps from tropical Africa to Indonesia and Australasia.	▪ Slender tree with pale bark and long aerial roots. Green, oblong, leathery leaves. Yellow flowers and fleshy, pale orange seed capsules.	▪ Sap
INGESTION POISONING	**BANEBERRY** *Actaea* spp.	▪ Temperate woodland in the northern hemisphere.	▪ Low shrub with, toothed green leaves. Small white flowers. White, black, or red berries grow in clusters.	▪ All, but the berries are the most poisonous.
	CASTOR OIL PLANT/ CASTOR BEAN *Ricinus communis*	▪ Throughout the tropics in scrub and wasteland; introduced to temperate regions.	▪ Tall shrub with glossy dark green or dark purple, star-like leaves. Spikes of yellow flowers. Spiky red pods.	▪ All, but the seeds contain particularly high levels of the poison ricin.
	DEATH CAMAS/ DEATH LILY *Zigadenus* spp.	▪ Grassy, wooded, and rocky areas in temperate regions of North America.	▪ Long grass-like leaves arise from a bulb. Flowers have six white petals with a green heart at base.	▪ All
	PANGI *Pangium edule*	▪ Tropical forests in Southeast Asia.	▪ Tall tree with green, heart-shaped leaves. Green flower spikes. Large brownish pear-shaped fruits grow in clusters.	▪ All, but especially the seeds, which contain prussic acid (cyanide).
	PHYSIC NUT *Jatropha curcas*	▪ Woodland throughout the tropics and southern USA.	▪ Large shrub with large, green, ivy-like leaves. Small greenish-yellow flowers. Apple-sized yellow fruit has large seeds.	▪ All, but particularly the seeds.
	POISON HEMLOCK *Conium maculatum*	▪ Wet or moist ground in temperate parts of Eurasia; introduced to North America and Australia.	▪ Tall herb with branching purple-spotted stem; toothed leaves; small clusters of white flowers grown in flat umbrellas.	▪ All, but the root has the highest level of toxins.
	STRYCHNINE TREE *Strychnos nux-vomica*	▪ Tropical and subtropical forests in India, Southeast Asia, and Australia.	▪ Evergreen tree with paired oval leaves. Small clusters of greenish flowers grow at end of branches. Large orange-red berries.	▪ All, but the seeds contain lethal levels of strychnine.

POISONOUS PLANTS

protect yourself from any poison on the casualty's mouth. When planning your trip, it is advisable to familiarize yourself with the poisonous plants in the region you are visiting. For further information regarding plant contact poisoning and ingestion poisoning, and their treatment in a survival situation, see pp. 268–69.

EFFECT	TREATMENT	ADDITIONAL INFO
▪ Skin irritation. Contact with the eyes can cause blindness.	▪ Call the emergency services. Rinse the skin with cold water for 20 minutes, the eye(s) for 10 minutes. Don't let the water collect under the casualty or you.	
▪ Reddening, itching, swelling, and blistering of skin within 4–24 hours of contact with the plant. Some people may suffer an allergic reaction called anaphylactic shock (see p. 274).	▪ Wash the affected area with soap and cold water. Apply anti-poison ivy cream. Monitor and treat for shock (see p. 274) if necessary. For natural remedies, see p. 268.	▪ Western poison oak (*T. diversilobum*), Atlantic poison oak (*T. pubescens*), and poison sumac (*T. vernix*) also cause contact poisoning (see p. 268).
▪ The sap blisters the skin and will cause temporary blindness if it gets in the eyes.	▪ Call the emergency services. Rinse the skin with cold water for 20 minutes, the eye(s) for 10 minutes. Monitor casualty and treat for shock (see p. 274).	▪ Blinding or milky mangrove (*Exoecaria agallocha*) also has poisonous sap.
▪ Can be fatal—ingestion of berries can lead to cardiac arrest and death. Other symptoms include dizziness, vomiting, and severe internal irritation.	▪ Call the emergency services. Induce vomiting if casualty is still conscious. Dilute the poison by getting him or her to drink large quantities of water or milk, or tea mixed with charcoal.	
▪ Can be fatal—ingestion of raw seeds causes severe diarrhea.	▪ Call the emergency services. Induce vomiting if casualty is still conscious. Dilute the poison by getting him or her to drink large quantities of water or milk, or tea mixed with charcoal.	▪ The seedpods explode when ripe, scattering the large, oval, glossy, brown-mottled seeds, which can be mistaken for beans.
▪ Deadly poisonous. Symptoms include profuse salivation, vomiting, diarrhea, confusion, slow, irregular heartbeat, low temperature, difficulty breathing, and unconsciousness, leading to death.	▪ Call the emergency services. Induce vomiting if casualty is still conscious. Dilute the poison by getting him or her to drink large quantities of water or milk, or tea mixed with charcoal.	▪ This plant looks similar to wild onions, which are edible, but the death camas does not have the onion smell.
▪ Deadly poisonous. Causes unconsciousness and severe breathing difficulties, which, if untreated, may lead to death.	▪ Call the emergency services (antidotes are available). Induce vomiting if casualty is still conscious. Dilute the poison (see Death Camas, above). Keep casualty warm and at rest.	▪ If the casualty is unconscious and stops breathing, give rescue breaths, using a face shield. Alternatively, use an oxygen bag and a mask, if possible.
▪ Severe diarrhea and vomiting.	▪ Call the emergency services. Induce vomiting if casualty is still conscious. Dilute the poison by getting him or her to drink large quantities of water or milk, or tea mixed with charcoal.	▪ The seeds look like betel nuts and taste sweet. Several species in the *Jatropha* genus are poisonous, for example, the aptly named bellyache bush (*J. gossypifolia*).
▪ Deadly poisonous. A small amount can result in death by respiratory failure from muscular paralysis. Early symptoms include nausea, vomiting, and rapid heartbeat.	▪ Call the emergency services. Induce vomiting if casualty is still conscious. Dilute the poison (see Physic Nut, above). If the casualty is unconscious and stops breathing, begin CPR, using a face shield.	▪ Water hemlock or spotted cowbane (*Cicuta* spp.), which looks similar, is also deadly poisonous. Don't mistake these plants for wild carrots or wild parsnips.
▪ Deadly poisonous. Muscle spasms occur 10–20 minutes after exposure, leading to seizures followed by death from severe breathing difficulties or exhaustion within 2–3 hours.	▪ Call the emergency services. Induce vomiting if casualty is still conscious. Dilute the poison by getting him or her to drink large quantities of water or milk, or tea mixed with charcoal.	▪ Warning: strychnine can also enter the system through contact with the eyes.

RESOURCES

SCOUTS AND SCOUTING

Boy Scouts of America

1325 West Walnut Hill Lane
P.O. Box 152079, Irving,
Texas 75015-2079

Phone: 972-580-2000

Fax: 972-580-2413

www.scouting.org

Boy Scouts of America prepares young people to make ethical and moral choices over their lifetimes by instilling in them the values of the Scout Oath and Law.

Girl Scouts of the USA

420 Fifth Avenue
New York, New York 10018-2798

Phone: 800-GSUSA-4-U [800-478-7248] or 212-852-8000

www.girlscouts.org

Girl Scouts is one of the largest organizations dedicated specifically to girls. It encourages them to develop skills and values such as leadership, social conscience, and self-worth that will stand them in good stead in the wider world.

National Scouting Museum

Boy Scouts of America, S505,
1329 West Walnut Hill Lane, Irving,
Texas 75038

Phone: 800-303-3047 and 972-580-2100

e-mail: nsmuseum@netbsa.org

www.bsamuseum.org

This museum is a tribute to the rich history of the Boy Scouts of America and features a Norman Rockwell art gallery, virtual reality adventures, hands-on learning experiences, and a collection that traces the Scouting movement from its beginnings.

WEATHER AND ENVIRONMENTAL HAZARDS

National Oceanic and Atmospheric Administration (NOAA)

1401 Constitution Avenue, NW,
Room 6217, Washington, DC 20230

Phone: 202-482-6090

Fax: 202-482-3154

www.noaawatch.gov

The NOAA has several departments, such as the National Severe Storms Laboratory (NSSL), the Storm Prediction Center (SPC), which is part of the National Weather Service (NWS), and the National Centers for Environmental Prediction (NCEP). The SPC provides regular, timely, and accurate storm forecasts, and watches out for severe thunderstorms, tornadoes, heavy rain, heavy snow, and fire weather events over the contiguous United States.

National Weather Service

1325 East West Highway, Silver Spring,
Maryland 20910

www.weather.gov/om/severeweather/index

Provides weather, hydrologic, and climate forecasts and observations for the whole country and the waters and oceans around it. The service offers a national information database for the use of public, private, and global communities.

NOAA Weather Radio All Hazards (NWR)

www.weather.gov/nwr

A nationwide network of radio stations broadcasts continuous weather information directly from the nearest National Weather Service office. NWR broadcasts official Weather Service warnings, watches, forecasts, and other hazard information 24 hours a day, seven days a week.

National Interagency Coordination Center (NICC)

www.nifc.gov/nicc/index.htm

The NICC serves as a focal point for coordinating the national mobilization of resources, such as heavy airtankers, helicopters, smokejumpers, area command teams, and Remote Automated Weather Stations (RAWS), for wildland fire and other incidents throughout the United States.

The Forest Fire Lookout Association (FFLA)

2590 W. Versailles Drive, Coeur d'Alene,
Idaho 83815

Phone: 208-765-1714 and 800-GRN-TREE

Email: weblookout@imbris.net

www.firelookout.org

The FFLA investigates former forest-fire lookout sites, ground cabins, and early forest fire detection methods to encourage public groups and others in restoring forest-fire lookouts.

U.S. Geological Service

Western Distribution Branch,
P.O. Box 25286, Denver, Colorado 80225

Phone: 303-236-7477

www.usgs.gov

This multi-disciplinary science organization focuses on biology, geography, geology, geospatial information, and water, and is dedicated to the timely, relevant, and impartial study of the US landscape, and natural resources and hazards.

DesertUSA

www.desertusa.com

This website is a comprehensive resource for North American deserts and Southwest destinations. It includes information about desert biomes, and the ways plants and animals adapt to them, and about national and state parks.

HEALTH AND MEDICAL

Centers for Disease Control and Prevention

1600 Clifton Rd, Atlanta, Georgia 30333

Phone: 800-232-4636 and 888-232-6348

Email: cdcinfo@cdc.gov

www.cdc.gov

Provides the expertise, information, advice, and tools that individuals and communities need to protect their health, including the promotion of healthy living and the prevention of disease, injury, and disability.

U.S. Department of Health and Human Services

200 Independence Avenue, S.W.,
Washington, D.C. 20201

Phone: 202-619-0257

Toll Free: 1-877-696-6775

www.hhs.gov/disasters/index.shtml

For information and advice on coping with disasters and related medical emergencies.

American Medical Association

515 N. State Street, Chicago, Illinois 60610

Phone: 800-621-8335

www.ama-assn.org/ama/pub/category/6206.html

The AMA's Center for Public Health Preparedness and Disaster Response is an important national educational resource for enhancing the disaster preparedness and response capabilities of both civilian and military providers.

American Red Cross

National Headquarters, 2025 E Street NW
Washington, DC 20006

Phone: 800-733-2767

www.redcross.org/services

The nation's premier response organization that provides relief for communities during natural and manmade emergencies. It belongs to a worldwide movement that offers neutral humanitarian care and assistance to victims of war and devastating natural disasters such as earthquakes.

National Capital Poison Center

3201 New Mexico Ave, Suite 310,
Washington D.C. 20016

Emergency Phone: 800 222 1222

www.poison.org

Affiliated with The George Washington University Medical Center, the Poison Center is committed to prevent poisonings, save lives, and limit injury from poisoning.

SEARCH AND RESCUE

National Association for Search & Rescue (NASAR)

PO Box 232020, Centerville,
Virginia 20120-2020

Phone: 703-222-6277

Toll Free: 877-893-0702

Email: info@nasar.org

www.nasar.org/nasar

A not-for-profit association dedicated to the advancement of professional, literary, and scientific knowledge in fields related to search and rescue throughout the United States and around the world.

National Institute for Urban Search & Rescue

PO Box 91648, Santa Barbara,
California 93190

Phone: 800-767-0093 and 805-569-5066

Cell: 805-798-0169

Email: niusr@cox.net

www.niusr.org

A non-profit organization dedicated to finding ways of saving lives by improving disaster readiness and response through public awareness, collaboration, research, and engineering.

Mountain Rescue Association

www.mra.org

Represents highly skilled and active mountain rescue teams throughout the country, who work for local government authorities and who are dedicated to saving lives through rescue and mountain safety education.

International Association of Dive Rescue Specialists

201 North Link Lane, Fort Collins,
Colorado 80524-2712

Phone (toll free): 800-IADRS-911

Phone (international): 1-970-482-1562

Fax (international): 970-482-0893

www.iadrs.org

An association of public safety divers and water rescue personnel who, over the years, have educated and assisted professionals in all 50 states and 15 foreign countries.

Association of Air Medical Services

526 King Street, Suite 415,
Alexandria, Virgina 22314

Phone: 703-836-8732

Fax: 703-836-8920

www.aams.org

An international not-for-profit organization that represents providers of air and surface medical transport systems, and aims to ensure that everyone has access to quality air medical and critical care support.

FEDERAL

Environmental Protection Agency (EPA)

EPA Headquarters, Ariel Rios Building
1200 Pennsylvania Avenue, N.W.,
Washington, DC 20460

EPA Hotlines: Various phone numbers and websites for assistance.

www.epa.gov/ebtpages/
emeremergencypreparedness.html

The EPA develops, implements, and coordinates preparations for chemical and other emergencies in order to be able to respond quickly and effectively to environmental crises and to keep the public informed about hazards in their community.

Federal Emergency Management Agency (FEMA)

500 C Street S.W., Washington, D.C. 20472

Phone: 800-621-FEMA-3362

TDD: TTY users can dial 1-800-462-7585 to use the Federal Relay Service.

www.fema.gov

FEMA aims to reduce the loss of life and property, and protect the country from all hazards, including natural disasters, acts of terrorism, and other manmade disasters.

U.S. Dept of the Interior National Parks Pass

1849 C Street, NW, Washington, DC 20240

Phone: 202-208-3100

Email: webteam@ios.doi.gov

www.doi.gov/parkpass.html

You can buy an annual pass for entry into national parks from the US Geological Survey store and through the government's federal lands recreation web portal at www.recreation.gov.

CANADA

National Search and Rescue Secretariat (NSS)

400-275 Slater Street, Ottawa,
Ontario K1A 0K2

Phone: (toll-free) 1-800-727-9414

Email: inquiry@nss.gc.ca

www.nss.gc.ca

An independent government agency that coordinates the search-and-rescue requirements of the military, coastguard, police, transport, parks, and meteorological services.

Search and Rescue Volunteer Association of Canada

8 Paradise Road, Paradise,
Newfoundland and Labrador A1L 3B4

Phone (toll free): 1-866-9SARVAC
(1-866-972-7822)

Phone (office): 709-368-5533

Fax: 709-368-1298

Email: info@sarvac.ca

www.sarvac.ca

A not-for-profit organization that provides a national search-and-rescue service, and is committed to fostering the exchange of information between other rescue services.

Meteorological Service of Canada

www.msc-smc.ec.gc.ca

Provides information and conducts research on water, climate, weather, atmospheric science, and other environmental issues.

Environment Canada

Inquiry Center, 351 St. Joseph Boulevard
Place Vincent Massey, 8th Floor
Gatineau, Quebec K1A 0H3

Phone: 1-800-668-6767
or 819-997-2800

Fax: 819-994-1412

TTY: 819-994-0736

Email: enviroinfo@ec.gc.ca

www.ec.gc.ca

Government department committed to preserving and enhancing the country's environment, and to providing weather forecasts.

GLOSSARY

A-frame A type of shelter design in which the roof is suspended by a single support running from the front to the back, resting on an "A"-shaped framework at either end.

Air mass A large body of air in a weather system that has its own temperature and humidity.

Altitude sickness An illness brought on by low air pressure at high altitudes.

Anabatic winds Daytime, upslope winds.

Anaphylactic shock A dangerous allergic reaction brought on by a bite or sting.

Attack point See *Stand-off.*

Avalanche transceiver A personal beacon that can be activated to alert rescuers by someone caught in an avalanche.

Base layer The bottom layer of clothing that sits directly against the skin and is designed to "wick" sweat away from the body.

Base rate The heart rate, as measured when the body is at rest.

Beaufort scale A way of describing wind speed on land and at sea, using a scale from 0 (calm) to 12 (hurricane).

Belaying A rope technique used by climbing partners to safeguard each other.

Bivi pup tent A basic one-man tent that uses a bivi bag as a covering.

Bivi bag A large waterproof sack suitable for use as a basic shelter; smaller and lighter than a tent.

Blazes A general term for markers on a trail.

Bola A hunting device made of a rope with weights attached, designed to be spun and thrown.

Boot skiing A technique for descending snow-covered slopes without skis.

Bothy bag A large waterproof bag that provides shelter from the wind, rain or sun.

Bow-and-drill set One of the oldest methods of creating a glowing ember (coal) for use in lighting a fire.

Boxing an object See *Detouring.*

Breathable clothing Clothing that allows sweat in the form of water vapour to be carried away from the body but is waterproof from the outside so keeps liquids (rain or snow) out.

Bungee A type of elasticated cord, often with hooks at either end.

Bushcraft knife A versatile survival knife used primarily for carving, cutting, and splitting small logs.

Button compass A small, simple compass, ideal as a back-up compass.

Button tie A method of attaching cordage to fabric that has no hoops or grommets; useful in that it avoids ripping a hole in the fabric, maintaining any waterproof qualities of the fabric, and allows both fabric and cordage to be reused subsequently for other purposes.

Cairn Trail marker consisting of a pile of rocks of varying sizes, designed to be visible in fog.

Canoe An open-deck paddle boat, for one or more people, and equipment.

Carabina A metal clip used for joining ropes or attachment.

Carbon monoxide A colourless, odourless, tasteless, but highly toxic gas.

Cardiopulmonary resuscitation (CPR) An emergency system of chest compressions and rescue breaths designed to restart a casualty's heart and lungs.

Cerebral oedema Accumulation of excess water in the brain that causes reduced brain function and potentially fatal swelling.

Char cloth Cotton cloth that has been combusted in the absence of oxygen. Used for lighting fires.

Chimneying A climbing technique used for climbing up the inside of large rock clefts.

Cirrus A wispy cloud that forms high in the sky and is made from ice crystals.

Cold shock An involuntary gasp reflex followed by hyperventilation, caused by sudden immersion in very cold water. In some circumstances cold shock response can lead to the inhalation of water, disorientation, panic, hypothermia, cardiac problems, and death.

Commando saw A small saw consisting of a serrated wire blade with a ring at each end.

Compacted snow trench A shelter dug into compacted snow; the excavated snow can be cut into blocks and used to form a roof.

Compass baseplate A plate to which some compasses are fixed, containing additional markings used for orientation and navigation.

Compass scale Scaled markings on a compass baseplate that measure distances on a map and help in working out grid references.

Compass An instrument used for orientation and navigation, using a freely rotating needle that indicates the direction of magnetic north.

Coniferous tree A needle-leaved, cone-bearing, mostly evergreen tree, such as pine, spruce, or fir.

Continental air mass Air that has tracked over land and carries comparatively less moisture than maritime air mass.

Contour lines Lines on a map that show points of equal height above sea level, thus detailing the changing height of natural features.

Contour navigation Walking at a constant height around a high natural obstacle.

Contouring See *Contour navigation.*

Contusion A bruise.

Cordage A type of light rope – an essential piece of survival equipment.

COSPAS–SARSAT system A satellite system, made up of low-altitude earth-orbiting (LEOSAR) and geostationary earth-orbiting (GEOSAR) satellites, that picks up signals from distress beacons.

Cramp Painful muscle spasm, often a result of dehydration.

Crampons Spiked metal plates that attach to boots to provide grip on icy surfaces.

Cumulonimbus A type of cloud that starts low in the sky and builds upwards, producing short, heavy downpours or thunderstorms.

Cumulus A billowing, puffy cloud that is generally small and develops on bright, sunny days, indicating fine weather.

Damper bread Yeast-free bread, suitable for making on a campfire.

Deadfall A trap in which a weight falls onto the prey. Also a mass of fallen dead timber.

Defensive swimming A type of swimming technique designed to keep the swimmer protected from obstacles in the water.

Degree A unit of latitude or longitude, equal to $^{1}/_{360}$ of a circle.

Dehydration A low level of water in the body. A very dangerous condition if not reversed.

Deliberate off-set (aiming off) Deliberately aiming left or right of a known feature.

Desalting kit An emergency desalination kit for turning saltwater into freshwater.

Detouring Walking around an obstacle as a method of clearing it, using a point in the distance as a reference.

Dew point The temperature at which water vapour held in the air cools to become liquid.

Dew trap A method of collecting dew to form usable water.

Digging stick A sturdy piece of wood with a pointed end.

Dipping net A fishing net used for scooping up fish that are too small to catch on a line.

Drill and flywheel A friction-based method of starting a fire.

Drip rag A method of collecting rainwater dripping down a tree using cloth.

Drogue A sea anchor used to stabilize a vessel.

Dysentery A water-borne disease that causes severe diarrhoea.

Eastings Vertical grid lines on a map; they increase in value the further east they are.

Emergency Locator Transmitter (ELT) A beacon that can send a distress signal to an orbiting satellite to initiate a rescue; mostly for use in aircraft.

Emergency plan of action (EPA) A document left with relevant authorities that contains vital details about you and your intended route, should you need to be rescued.

Emergency Position-Indicating Radio Beacon (EPIRB) A beacon that can send a distress signal to an orbiting satellite to initiate a rescue; mostly used at sea.

Emergency rendezvous (ERV) A pre-determined point at which all members of a group should meet in the event of separation.

Equator An imaginary circle running around the Earth's diameter that is equidistant from the North and South Poles at all points.

Eskimo roll A technique for righting a capsized kayak.

Faggot A bundle of kindling.

Feather stick A stick that has been feathered to use as kindling and fuel.

Fighter trench A type of snow trench dug into soft snow. Ideally uses a tarpaulin for the roof.

Finnish marshmallow A method of melting chunks of ice over a fire then collecting the water in a container.

Fire tin A tin filled with waxed cardboard, used for lighting a campfire in difficult conditions, or as a basic cooking device.

Firebase A stable, non-flammable base suitable for building a campfire on.

Firefighter's lift A method of moving a casualty by carrying them over your shoulder.

Fire set A set of components necessary to generate a glowing ember that can start a fire.

Firesteel A metal bar which, when hit with a striker, produces a spark for lighting campfires.

Flash burn See *Snow blindness.*

Föhn effect A dry downslope wind which occurs on the lee-side of a mountain or hill.

Four-wheel drive (4WD) A system on a vehicle in which drive is provided by all four wheels, rather than just two; results in superior traction.

Frostbite A serious condition caused by excessive exposure to extreme cold, in which body tissues actually freeze, sometimes to the bone. Often starts with the extremities.

Frostnip The freezing of the top layer of skin, usually on the face and extremities, caused by exposure to extreme cold. Can develop into frostbite if left untreated.

Gaiters Protective fabric that wraps around the lower leg and ankle, to keep out water and protect against sharp objects.

Gill net A fishing net in the form of a mesh stretched across a stream.

Global positioning system (GPS) A hand-held unit that uses orbiting satellites to determine the user's position accurately.

Gourd The shell of hollowed-out, dried fruit; often used to carry water.

Grab bag A pre-prepared bag of essential survival equipment suitable for quickly picking up in an emergency at sea.

Gravity filter An effective method of filtering and purifying water, incorporated into a bottle.

Grid bearing A horizontal direction expressed in degrees east or west of north or south.

Grid magnetic angle (GMA) The difference between magnetic north and grid north, expressed as an angle.

Grid north A northerly direction that runs parallel to vertical gridlines on a map. Different from true north because a map is flat.

Grid reference A method of pinpointing the location of a place or object anywhere on a map, using coordinates provided by a numbered grid system printed on the map.

Grommet A metal-ringed eyelet in clothing.

Groundsheet A waterproof sheet.

Gypsy well A method of using a hole in the ground to filter non-potable water.

Hand jam A crack in a rockface suitable for wedging your whole hand into when climbing.

Handrailing A method of navigating using long linear features on the landscape that run in the general direction of your travel, such as rivers, roads, or paths.

Hank A small coil of cordage.

Heat exhaustion (heat stress) Dehydration that results in dizziness and profuse sweating; often a precursor of heatstroke.

Heatstroke A life-threatening condition brought on by severe overheating.

HELP (Heat Escape Lessening Posture) A posture that reduces heat-loss from the body when floating in water.

Hexamine stove A stove that uses hexamine solid fuel instead of gas or liquid fuel.

Hot platform A method of melting ice over a fire and collecting the liquid in a container.

Hyperthermia An abnormally high body temperature; potentially fatal.

Hyponatraemia An accumulation of excess water in the body, leading to a dangerously low concentration of sodium.

Hypothermia A life-threatening condition caused by exposure to cold. Symptoms usually appear in the following order: uncontrollable shivering (which may stop as the body temperature lowers); irrational or out-of-character behaviour; confusion, mood swings, and withdrawal; pale, cold skin; and slurred speech and/or stumbling. Watching out for and counteracting the early symptoms may help prevent them developing into a full-blown potentially fatal condition.

Hypoxia Inadequate levels of oxygen in the blood or body tissues. Potentially fatal.

Igloo A shelter constructed from cut blocks of snow.

Iodine A chemical used to purify water.

Isobar contours Lines on a weather chart that connect points at which the barometric pressure is the same.

Katabatic winds Cool, light downslope winds that form on clear nights.

Kayak A closed-deck paddle boat for one or more people.

Kindling Small pieces of fuel for a fire, added to burning tinder.

Kukri A large-bladed knife from Nepal, used mainly for chopping.

Land breeze A night-time wind that blows from land to sea.

Lanyard A small cord or rope used for securing or suspending an item.

Latitude The angular distance north or south of the Equator, in degrees along a meridian.

Layering Wearing several light layers of clothes rather than just one or two thick ones. Layers can be added or taken off to maintain a consistent body temperature.

Lean-to A shelter with a sloping roof that leans against a horizontal ridgepole.

Lee-side The side that is sheltered from the wind.

Lensatic compass A type of compass used for precise navigational work.

Longitude The angular distance east or west across the Earth between one meridian and the prime meridian at Greenwich, England.

Machete A large-bladed knife used mainly for chopping, approximately 45–50cm (18–20in) long.

Magnetic north The direction indicated by a magnetic compass.

Magnetic variation The difference between magnetic north and grid north.

Mantelling A technique used for climbing overhanging rock.

Maritime air mass Air that has tracked over the sea, typically containing moisture.

Mayday The internationally recognized distress signal for a grave emergency.

Matchless fire set Small kit that includes everything you need to start a fire – tinder, fuel, and spark device.

Melting sack An improvised sack that can hold snow or ice and is positioned close to a fire to provide water.

Meridian An imaginary arc on the Earth's surface from the North to the South Pole, connecting all locations running along it.

Mid-layer An insulating layer of clothing that sits between the base layer and the outer layer.

Motor impairment A limitation or loss of muscle control or movement.

Naismith's Rule A method of calculating the time it will take to arrive at a destination, taking into account distance and topography.

Natural hollow A natural dip in the ground that can be used as an emergency shelter.

New World Non-Eurasian and non-African regions of the world – specifically the Americas and Australia.

Noggin A piece of wood used to help support a structure, reducing the amount of cordage required.

Non-potable water Water that is not suitable for drinking.

Northings The horizontal grid lines on a map; increase in value the further north they are.

Occluded front A point at which two air masses meet in a weather system.

Old World Europe, Asia, and Africa.

Outer layer Outer clothing; ideally it should keep out rain but let sweat (as water vapour) escape.

Pace counting A method of determining distance; involves knowing how many paces you take to cover a set distance.

Pack animal An animal such as a mule or horse used for carrying heavy loads.

Paracord A useful type of cordage originally developed as rigging lines for parachutes. Usually comprises an outer sheath over an inner section of yarn.

Parang A large-bladed knife from Malaysia, used mainly for chopping.

Pathogen A micro-organism, especially bacteria or fungi, that causes disease.

Permafrost Permanently frozen soil.

Personal Locator Beacon (PLB) A beacon that can transmit a distress signal to an orbiting satellite to initiate a rescue.

Poncho A multi-purpose waterproof outer garment made from one sheet of fabric; also useful for building a basic shelter or bed.

Post-holing A technique for walking in deep snow without snow shoes.

Potable water Water suitable for drinking.

Potassium permanganate A chemical used for a variety of tasks, from lighting fires to purifying water.

Precipitation Moisture in a cloud that may fall as rain, snow, or hail.

Prismatic compass See *Lensatic compass.*

Protractor A device for measuring angles.

Psychogenic shock A very high level of psychological and emotional stress brought on by a sudden disaster situation.

Pulk A simple plastic sled used for carrying equipment over snow.

Pulmonary oedema Swelling and fluid accumulation in the lungs that causes potentially fatal breathing problems.

Pygmy hut A domed hut made from a circle of bent saplings or limber poles and thatched with natural materials.

Pygmy roll A method of rolling fibres together to make cordage.

Quicksand A bed of loose, wet sand that yields easily to pressure and can engulf anything on its surface.

Quinzhee A basic dome-shaped, snow-covered overnight shelter.

Ranger flint and steel	A rod of flint which, when hit with a striker, produces a spark for lighting campfires.
Recovery position	The position an unconscious person should be placed in to minimize further injury and help recovery.
Reflector	A device for directing heat from a campfire towards shelter.
Reverse-osmosis pump	A survival pump system that turns saltwater into freshwater.
Ridgepole	A long horizontal pole that forms the apex of a roof.
Romer measure	See *Compass scale.*
Salting	A salt marsh.
Scrambling	Climbing without ropes.
Scrape	A type of basic shelter built in a natural hollow or depression in the ground.
Sea breeze	A daytime wind that blows from sea to land.
Secondary drowning	Potentially fatal biological changes that can take place in the lungs after a person nearly drowns, caused by the body's response to inhaling water.
Shock	A life-threatening condition that occurs if the circulatory system fails, often triggered by severe bleeding, burns, or sudden cold.
Show-stopper	A failure in planning that could cause delays to, or stop a trip or expedition.
Sighting mirror	An advanced component on a high-end compass used for helping in orientation and navigation.
Signal fire	A fire specifically designed to produce lots of smoke to attract attention.
Signal flare	A hand-held distress flare that gives off orange smoke in daylight and a bright light at night.
Signal mirror	A simple signalling device that works by reflecting sunlight.
Silva compass	A type of basic compass useful for hiking.
Sip well	A method of extracting water trapped under rocks by sandy ground.
Skidoo	A motorized vehicle used for travelling over snow and ice.
Slingshot	A hunting weapon that fires small stones and is made from a Y-shaped stick with an elastic strip stretched between the prongs.
Snare	A wire noose used for trapping animals.
Snow blindness	Eye damage caused by ultraviolet light reflected off snow or water.
Snow cave	An effective cave-like shelter dug into compacted snow on the lee-side of a hill.
Snowshoes	Wide-soled strap-on shoes designed to stop you sinking into snow.
Soak	A water source found close to rivers and creeks in areas that are usually lower-lying than the existing water table.
Solar still	A method of extracting drinking water from any source of moisture by a process of evaporation and condensation.
Space blanket	A plastic blanket covered in aluminum foil that can be used as a shelter or a reflective signalling device; to carry, store, and heat water; or to cook in.
Stand-off	A technique for navigating to a point that may be hard to locate, by orientating from a nearby prominent feature.
Standing deadwood	Wood from a tree that has died but is still standing. Hazardous, as branches or the whole tree may fall, but makes excellent firewood.
Straddling	A climbing technique used for ascending wide chimneys.
Stratus	Dense, grey cloud that forms a sheet. Rain can fall for long periods of time if the cloud has depth.
Strobe light	An effective signalling device in the form of a rapidly flashing LED light.
Survival blanket	See *Space blanket.*
Survival kit	Essential items for survival carried on your person.
Survival straw	A compact emergency water purifier.
Survival suit	A waterproof, buoyant suit designed for survival in open water.
Survival tin	An essential, compact container carried on the person that addresses basic survival needs: protection, location, water, and food.
Taiga	A subpolar region characterized by coniferous forest.
Tarp	Shortened form of "tarpaulin", a type of sturdy waterproof sheet.
Temperate climate	A climate without extremes of temperature or rainfall.
Tetanus	A potentially lethal infection caused by bacteria that live in soil.
Throwing star	An improvised four-pointed hunting weapon used for throwing at prey.
Tinder	A dry, light, combustible material that is the first fuel used when lighting a fire.
Topographic map	A map that shows the main features on a landscape, and elevation via use of contour lines.
Transpiration bag	A method of evaporating, condensing, and siphoning off water from foliage using a plastic bag and sunlight.
Triangulation	A method of determining your location by taking bearings with a compass from recognizable landscape features.
True north	The direction of a meridian of longitude that converges on the North Pole.
Tundra	A polar region characterized by permafrost and stunted vegetation.
Universal Edibility Test (UET)	A test that checks whether a plant is safe to eat via a methodical process of testing small amounts on the skin, in the mouth, and in the stomach.
UV active purification	Purifying water via a battery-operated ultraviolet (UV) purifier.
UV passive purification	Purifying water by leaving filled bottles in strong direct sunlight. The UV rays eventually kill most pathogens.
Vegetation bag	See *Transpiration bag.*
VHF radio	Very high frequency radio transmitter; usually used at sea.
Water balance	The difference between water lost from the body through sweat and the water taken in through drinking.
Water purifier	A device that filters and purifies water by pumping it through micro filters, chemicals, or a combination of both.
Weather chart	A map of major weather systems and their predicted direction of travel.
Wicking material	A material that moves moisture away from your body to evaporate.
Wickiup	A small hut made from straight poles lashed together at the top, with an interwoven framework covered with animal hides or grass.
Witch's broom	A cleft stick stuffed with thin, dry bark suitable for lighting a fire.
Withies	The strong, flexible stems of plants, such as willow, birch, ash, and hazel.
Zig-zag route	Method of climbing a steep slope using a zig-zag path to reduce the effort required to achieve the climb. Also effective when walking down steep slopes.

INDEX

A

- A-frames
  - forest 164–65
  - front opening 165
  - jungle 168
  - poncho shelters 159, 167, 175
- abrasions (grazes) 263
- abandoning ship 250, 252–55
- ABC (airway/breathing/circulation), first aid 260, 276–77
- aerobic exercise 19
- agaves 193, 282–83
- air quality, caves 157
- aiming off 73
- air masses 79
- allergies and anaphylactic shock 266, 267, 274
- altitude sickness 33, 273
- altocumulus 80, 81
- altostratus 80, 81
- amoebic dysentery 187
- amphibians and reptiles
  - catching and eating 203, 218, 224, 294–95
  - dangers from 243, 266, 300–01
  - *see also* snakes
- anabatic winds 82
- analogue watches, navigating using 77
- anaphylactic shock 266, 267, 274
- anchor points, winching 103
- anchors, sea 39, 251
- animals
  - dangers from 115, 157, 189, 242–43, 300–3
  - edible 290–99
  - locating water 189
  - navigation aids 77
  - traveling with 42, 96–97, 98–99
  - weather forecasting 83
  - *see also* specific animals (e.g. bears); specific types (e.g. mammals)
- ants 219, 298–99
- arbor knot 142
- arm injuries 270
- ash
  - for soap 117
  - for stomach pain 269
- asthma 275
- automatic fires 124
- avalanches 32, 246–47

B

- bacillary dysentery 187
- backpacks 41, 42, 44–45, 108
- bacterial infections 185, 187, 212, 220, 262, 267, 301, 303
- baits and lures 208–09, 223, 229
- baking food 204, 205
- bamboo 284–85
  - fire saw 133
  - lean-tos 169
  - rafts 107
  - steamer 204
  - water sources and collection 192, 199
- bark
  - cordage 138
  - tea 269
  - tinder and kindling 120, 121, 238
- bats 157, 290–91, 300–01
- beaches 39, 177
- beacons, phones, and radios 39, 43, 61, 232–33, 236–37, 246, 250, 252
- bearings, compass 64–65, 68–71
- bears 28, 36, 157, 242
- Beaufort scale 83
- beds and bedding 41, 52–53, 156, 166–67
- bees 224, 267, 302–3
- belaying 91
- berms 177
- big cats 32, 242
- bilharzia 187
- birds
  - catching and eating 203, 204, 205, 218, 226–29, 292–93
  - locating water 189
- bites and stings 116, 266–67, 268, 300–03
- bivy sacks 53
  - bivy pup tent 160–61
  - hooped bivy 41, 54
- blankets, space 53, 61, 155, 175
- blazes (trail markers) 87
- bleeding
  - birds, for food 228
  - first aid 263–64
  - mammals, for food 222
- blended fuel stoves 58
- blisters 262, 268
- boats *see* ships and boats
- body fat 56
- boiling
  - food 204, 212
  - water 118, 185, 200
- bolas 226
- bones, joints, and muscles injuries 233, 270–1
- boot skiing 94
- boots 46, 49, 114
- bothy bags 161
- bottle filters 200
- bottle traps, fishing 211
- bough fence traps 227
- bow drills 130–33
- boxing an object (detouring) 73
- branches
  - as snowshoes 95
  - vehicle recovery 102
- bread, damper 204
- breathable waterproof fabric 48
- breathing difficulties
  - first aid 275
  - in shelters 157, 181
- breezes and winds 38, 79, 82–83
- brown bears 28, 242
- bruising 262, 263
- brushwood rafts 106–07
- buddy-buddy sleeping system 163
- buoyancy aids (floats) *see* lifejackets
- burns and scalds 265
- bushcraft knives 146–49
- butane stoves 58
- button compasses 68
- button ties 161

C

- cacti 193, 282–83
- cage traps, figure 4 226
- cairns 87
- calorie needs 56, 202
- camels 42, 99
- camping soap 117
- camping stoves 58–59
- camps
  - organization and administration 112–13, 114–15
  - *see also* specific areas (e.g. latrines)
- canoeing and kayaking 42, 104–05
- capacity, packs and bags 41, 42, 44
- capsizing 104, 105
- carbohydrates 56
- carbon dioxide 157
- carbon monoxide poisoning 181
- cardinal points 68, 76, 77
- cardiopulmonary resuscitation (CPR) 277
- cats, big 32, 242
- caves 157, 181
- cell phones 43, 237
- chainsaws 60, 150
- char cloths 122–23
- char test, softwoods and hardwoods 131
- charts
  - maps and map reading 43, 64–65, 66–71
  - weather 78
- chemical flames 127
- chemical lightsticks 61, 240
- chimneying 91
- chlorine tablets 201
- choking 275
- cholera 187
- cirrostratus 80, 81
- cirrus 80, 81
- clay baking, food 205
- climate 78
  - *see also* specific environments (e.g. temperate environment)
- climbing and scrambling 90–91
- clothing 46–49, 94
  - cleanliness 116
  - cultural differences 22
  - on fire 265
  - hats 43, 46, 47, 48
- clothing, improvising with
  - buoyancy aids 255
  - cordage 137
  - dipping nets 210
  - slings 261
  - stretchers 279
  - water collection and treatment 185, 190, 192, 195, 199, 200

clouds 78, 79, 80–81
coastal caves 157
coasts *see* marine environments
cold environments 36–37
  clothing 47, 94
  cold shock 254
  dos and don'ts 51, 245
  edible plants 286–87
  hypothermia and frostbite 21, 29, 33, 37, 252, 273
  tents 55
  water sources 194–95
  see also ice; snow
cold fronts, weather 78, 79
cold shock 254
cold-weather clothing 47, 94
commando saws 151
commando-style match striking 126
communications equipment 43, 61, 232–33, 236–37
compacted snow trench 178
compasses and bearings 43, 64–65, 68–71, 74–75
components of fire 118, 238
condoms 61
conjunctivitis 212
constellations, navigating by 77
continental air masses 79
contour lines 66, 67
contouring 73
contusions (bruising) 262, 263
cooking
  fires, rocks, and pits 119, 204–05
  fish preparation 212–13
  invertebrates 219, 224–25
  mammals preparation 220–23
  stoves 58–59
coping strategies 20–21, 113, 234–35, 259
cordage 136–41
cordless scrape shelters 174
cougars 32, 242
CPR (cardiopulmonary resuscitation) 277
cardiovascular fitness 18, 19
crabs 225
cramp 270
crickets and grasshoppers 224, 298–99
crocodilians 189, 242
crossing rivers 88–89, 101, 108–09
crustaceans 225
cryptosporidium 187
cumulonimbus 80
cumulus 80, 81
cuts and grazes 263
cutting tools 60, 146–51
cyalumes 61, 240

D

Dakota hole fires 125
damper bread 204
day packs 42, 44
deadfalls 115
deadwood, standing 115, 121, 131
defensive swimming 108
dehydration and rehydration 187, 190, 193, 196, 253, 269, 272
deliberate off-set 73
denatured alcohol stoves 59
desalting kits 197
desert environments 34–35
  clothing 47
  dos and don'ts 129
  edible plants 282–83
  four-wheel driving 35, 101
  night walking 86
  shelters 174–75
  water sources 34, 35, 193
detouring (boxing an object) 73
dew harvesting and traps 190, 196
dew point 80
diarrhea and vomiting 187, 203, 269
digging
  ponds 199
  roots and tubers 206
  underground water 193
  vehicle recovery 102
dipping nets 210
disaster situations and emergencies
  causes 16–17, 26, 84
  dos and don'ts 27, 51, 93, 129, 173, 215, 232–33, 245
  emergency plans of action (EPAs) 24–25, 250
  emergency rendezvous points (ERVs) 72
  environmental hazards 246–49
  four-wheel driving (4WDs) 35, 103
  gear priorities 43
  mental preparation and responses 20–21, 234–35, 259
  PLWF (protection, location, water, and food) 11, 27, 258
  rescue services 24
  rescue signaling 39, 43, 232–33, 236–41, 250, 252
  survival at sea 16–17, 39, 196–97, 214–15, 250–55
  survival kits 60–61
  SURVIVAL strategies 234–35
  water sources and rationing 39, 187, 188–97, 199, 251
  see also first aid
diseases *see* infections
distance measuring 67, 72
distilling water 185
distress signals 39, 232–33, 236–41, 250, 252
dogs 17, 96–97, 99
dome signal fires 238–39
dos and don'ts
  disaster situations and emergencies 27, 51, 93, 129, 173, 215, 232–33, 245
  fires 118, 119, 124
double overhand knot 143
double sheet bend 144
down sleeping bags 52–53
downhill walking 86, 87
drawing birds (food preparation) 229
driftwood shelters 176–77
drip rags 192
driving techniques, 4WDs 35, 100–03
drogues 39, 251
drowning 254, 255, 273
drum rafts 107
duck traps 227
dunes, sand 35, 177, 189
dysentery 187

E

E. coliform infection 187
earthquakes 247
earthworms 224, 298–99
eastings 67
edible plants 203, 206–07, 280–89
eggs 226
electric current, magnetizing compass needles 75
electrical storms 81, 249
elements of fire *see* fuel; kindling; tinder
elephants 99, 189, 242
ember pans 132
emergencies *see* disaster situations and emergencies
emergency signaling codes 240, 241, 252
emergency transmitters 39, 232–33, 236–37, 246, 250, 252
emergency water packs 199
emotional responses
  disaster situations 20–21, 113, 234–35, 259
  team dynamics 23
environmental hazards 246–49
environments
  understanding and preparing for 23, 26
  see also specific environments (e.g. cold environments)
EPAs (emergency plans of action) 24–25, 250
EPIRBs (emergency position indicating radio beacons) 236, 250, 252
equipment *see* gear and equipment
ERVs (emergency rendezvous points) 72
eskimo rolls 104
Evenk knot 144
exercise and fitness 18–19
exposure, first aid 272–73
external-frame packs 44
extreme weather 246, 248–49
eyes
  care 116
  problems and injuries 212, 265

F

fallen trees, shelters 163
fatigue 21, 235
fats 56
fear 234, 235
feather lures 209
feather sticks 120–21
features, use in navigation 70–71, 72, 73
feelings *see* emotional responses
felling trees 148–51
feral animals 242
fibre (nutrient) 56
fighter trench 179
figs 171, 284–85
filleting fish 212–13
filtering water 184, 200, 201
Finnish marshmallow 195
fire saws, bamboo 133
fire tins 123
fire wads 123
firefighter's lift 278
fires
  benefits 27, 113
  burns, first aid 265
  in caves 157
  clothing on fire 265

  - components 118, 238
  - cooking over 119, 204–05, 213
  - dos and don'ts 59, 118, 119, 124
  - elements *see* fuel; kindling; tinder
  - fire reflectors 119, 164
  - firewood 114, 148–49
  - forest fires 248
  - ice and snow melting 194–95
  - lighting 125
  - preparing and making 118–23
  - signal 30, 115, 238–39
  - snapping wood with 151
  - spark production and ignition devices 113, 118, 126–27, 130–33
  - types 124–25, 238–39
  - wildfires 34
- fireset can, matchless 118
- firesteel 113, 127
- first aid 258–9
  - ABC (airway/breathing/circulation) 260, 276–77
  - anaphylactic shock 274
  - asthma 275
  - bites and stings 266–67, 268, 300–03
  - bones, joints, and muscles injuries 233, 270–71
  - breathing difficulties 275
  - burns and scalds 265
  - cardiopulmonary resuscitation (CPR) 277
  - casualty transport 99, 278–79
  - choking 275
  - dehydration and rehydration 269, 272
  - diarrhea and vomiting 269
  - drowning 255, 273
  - exposure 272–73
  - fish-hook removal 208
  - hyponatraemia 187
  - kit 60, 260–61
  - natural remedies 263, 268, 269
  - parasites 269
  - priorities 260
  - psychological help 21
  - recovery position 276
  - shock 274
  - unconsciousness 276–77
  - wounds and bleeding 262–65, 266
  - *see also* poisoning
- fish
  - catching and eating 61, 203, 204, 205, 208–13, 296–97
  - dangers from 38, 243, 300–01
  - as water source 196
- fitting backpacks 45
- fixed dial compasses 68
- flares, signal 239, 241
- flash burn 265
- flash floods 115, 249
- flashlights 43, 60
- fleeces 46, 47
- flesh wounds 262–5, 266
- flint and steel 60, 113, 118, 127
- floating method, improvised compasses 74
- floats (buoyancy aids) *see* lifejackets
- floats and sinkers (fishing equipment) 209
- floods 115, 249
- flysheets 55
- foam mats 53
- fog 81
- Föhn effect 82
- folding saws 151
- food
  - amphibians and reptiles 203, 218, 224, 294–95
  - birds 203, 204, 205, 218, 226–29, 292–93
  - cooking fires and stoves 58–59, 119, 204–05
  - fish 203, 204, 205, 208–13, 296–97
  - food poisoning 187, 269
  - hunger 20, 202, 235
  - insects 203, 219, 224, 298–99
  - mammals 203, 204, 205, 216–23, 290–91
  - nutrients and calorie needs 56, 202
  - plants 203, 206–07, 280–89
  - protecting 114
  - purchased 57
  - shellfish 225, 298–9
  - survival without food 27, 56, 57, 202, 234, 235, 259
- foot holds, scrambling and climbing 90
- footwear 46, 48, 49, 114
  - snow shoes 94–95
- foreign objects
  - in eyes 265
  - in wounds 263
- forests
  - forest fires 248
  - mountain 32
  - taiga 36, 37
  - temperate 28, 29, 162–65
  - tropical *see* rain forests and jungles
- found meat 204
- four-wheel driving (4WD) 35, 42, 100–03
- friction, as fire starter 130–33
- frogs 224, 243, 294–95
- fronts, weather 78, 79
- frostbite 33, 273
- fuel
  - fires 114, 118, 121, 124, 125, 148–49, 238–9
  - stoves 58–9
- fungi and mushrooms 206, 263

G

- gaiters 48, 94
- gas-fueled stoves 58
- gear and equipment
  - backpacks 41, 42, 44–45, 108
  - clothing 46–49, 94
  - communications and distress signaling 39, 43, 232–33, 236–37, 240–41, 246, 250, 252
  - first aid kit 60, 260–61
  - food 57
  - keeping it dry 108–09
  - packing 41, 42, 45, 98, 136, 137–41
  - priorities 40–41, 43
  - survival kits 60–61
  - training with 23, 134–35
  - ultralight camping 41
  - water containers and treatment 60, 197, 198, 201
  - weight 41, 42
  - *see also* specific items (e.g. surgical tubing)
- giardiasis 187, 269
- gill nets 210–11
- glaciers 33, 94
- global positioning systems (GPS) 65, 75, 237
- gloves 46, 47
- glowsticks 61, 240
- gourds 199, 282–83
- GPS (global positioning systems) 65, 75, 237
- grab bags 250
- grasshoppers and crickets 224, 298–99
- grasslands 28, 34, 35
- grazes (abrasions) 263
- grid lines, references and bearings 66–71
- grips, knives 147
- ground-to-air markers 114, 241
- groups and group dynamics 23, 100, 253, 254
- grubs 224, 298–99
- gum and teeth care 19, 116
- gunshot wounds 263
- gutting mammals 220, 223
- gypsy wells 191

H

- hair
  - hair care 116
  - magnetizing compass needles 74
- half hitches 145
- hammocks 54, 166
- hand holds, scrambling and climbing 90
- hand injuries 271
- handrailing 73
- hanks, cordage 136, 137
- harpoons 211
- hats 43, 46, 47, 48
- hearth boards, bow drills 131, 132
- heat escape lessening position (HELP) 254
- heat exhaustion 272
- heat loss reduction 37, 254
- heatstroke 272
- helicopter rescues 114, 236–37, 241
- heliographs 241
- helminths 269
- HELP (heat escape lessening position) 254
- Hennessy hammocks 166
- hepatitis 187
- hexamine fuel 59, 118, 238
- hides 222, 223
- hiking *see* walking and hiking skills
- hiking boots 49
- hippos 189, 242
- hitches and knots 135, 142–45, 210
- hollows, scrapes and trenches shelters 156–57, 174–75, 176–77, 178–79
- hooks, fishing 208
- hookworms 187
- hooped bivy 41, 54
- hooped shelters 161
- hopping insects 224
- horse chestnut leaves soap 117
- horses 42, 99
- hot platforms 194
- hot rocks cooking 205
- huddle crossing, rivers 89
- hunger 20, 202, 235

- hunter fires 125
- hunting and trapping mammals 216–18
- hurricanes 38, 248–49
- huskies 96–97, 99
- huts
  - jungle 170–71
  - pygmy 171
  - wickiups 171
- hybrid boots 49
- hydration systems 198
- hygiene 116–17, 269
- hyperactivity 21
- hyponatremia 187
- hypothermia 21, 29, 33, 37, 252, 273

I

- ice
  - four-wheel driving 101
  - ice climbing 91
  - ice falls 115
  - ice fishing 209
  - ice walking 94
  - icebergs 196
  - sea ice 36, 196
  - water source 36, 194–95, 196
- igloos 180
- ignition devices and spark production 113, 118, 126–27, 130–33
- improvising 235
  - backpacks 45
  - compasses 74–75
  - goggles 265
  - signal mirrors 241
  - *see also* clothing, improvising with
- incised wounds 263
- infections
  - bacterial 185, 187, 212, 220, 262, 267, 301, 303
  - diarrhea and vomiting 187, 269
  - first aid concerns 261, 262, 263, 265, 301
  - parasites 187, 222, 223, 269
  - vaccinations 22
  - water-borne 185, 187
- infectious hepatitis 187
- injuries 233, 235, 270–71
  - *see also* first aid
- insects
  - bites and stings 116, 267, 302–03
  - catching and eating 203, 219, 224
  - locating water 189
  - maggot therapy 262
  - mosquitoes 31, 115, 302–03
  - navigation aids 77
- International Distress Signal whistle 240
- Inuit snow-melting techniques 195
- invertebrates 203, 219, 224, 298–99, 300–1, 302–3
- iodine 60, 201
- isobars 78
- isobutene stoves 58
- ivy, poison 268

J

- jackets 46, 47, 48
  - lifejackets and buoyancy aids (floats) 39, 104, 108, 109, 250, 254–55
- jellyfish stings 267, 300–01
- jointing mammals 223
- joints, bones, and muscles injuries 233, 270–71
- journey planning 22
- jungles *see* rainforests and jungles

K

- katabatic winds 82
- kayaking and canoeing 42, 104–05
- kernmantle rope 136
- kerosene 269
- killing
  - birds 228
  - rabbits 216
- kindling 118, 119, 120, 121, 124, 125, 133, 238–39
- knives 146–49
- knots 135, 142–45, 210

L

- lacerations (tears) 263
- lakes 189
- land and sea breezes 82
- larvae, ant 219
- latrines 114, 117
- layering clothing 46
- lean-tos
  - bamboo 169
  - forest 162–63
  - one-person 165
- leaves
  - cordage 139
  - roofs 170–71, 192
  - soap-making 117
- LED strobe lights 240
- ledges, snow 181
- leeches 267
- leg injuries 271
- legends, topographic maps 66, 69
- lensatic compasses 69
- leptospirosis 187
- lichens 286–87
- lifejackets and buoyancy aids (floats) 39, 104, 108, 109, 250, 254–55
- liferafts 39, 196, 251, 252–53
- lifts, moving casualties 278–79
- light windmill 240
- lighters 119, 126
- lighting fires 125
- lightning 81, 249
- lights and lightsticks 61, 240
- limitations, personal 18
- line crossing, rivers 89
- line fishing 61, 209
- liners, sleeping bags 53
- lipolysis 56
- liquid-fueled stoves 58, 59
- liver 220, 222, 223, 229
- lizards 294–95
- llamas 99
- location 11, 27, 233
  - *see also* site selection
- location aids and rescue signals 39, 43, 114, 232–33, 236–41, 250, 252
- log cabin signal fires 239
- log rafts 107
- log-splitting 114, 148–49
- lures and baits 208–09, 223, 229
- Lyme disease 267, 303

M

- machetes 146
- maggot therapy 262
- magnetic bearings 68–71
- magnetic variation 69
- magnetizing compass needles 74–75
- magnifying glasses 126
- mammals
  - catching and eating 203, 204, 205, 216–18, 220–3, 290–1
  - dangers from 242–43, 266, 300–01
  - locating water 189
  - melting snow 195
  - sinew cordage 139
  - weather forecasting 83
  - *see also* specific animals (e.g. bears)
- man-made cordage 61, 136–37
- mantelling 91
- maps and map reading 43, 64–65, 66–71
  - weather charts 78
  - *see also* navigation
- Marcandonatos, Costa 128
- marine environments 38–39
  - beaches 39, 177
  - coastal caves 157
  - drowning 254, 255, 273
  - edible plants 288–89
  - sea-sickness 21
  - shoreline shelters 176–77
  - single-wall fishing traps 211
  - stings and bites 267, 300–01
  - swimming 108–09, 254–55
  - tides 157
  - water sources 39, 196–97
  - winds 82
  - *see also* sea journeys
- maritime air masses 79
- marshmallow, Finnish 195
- matches 60, 126
- matchless fireset cans 118
- mayasticks 123
- measuring distances 67, 72
- meat *see* specific types (e.g. birds)
- melting sack 195
- mental preparation and responses, disaster situations 20–21, 234–35, 259
- minnow traps 211
- mirrors, signal 241
- money 22, 61
- moon, navigating by 77
- mosquitoes 31, 115, 302–03
- mosses 286–87
- motorized transport 35, 42, 97, 100–03
- mountain environments 32–33
  - altitude sickness 33, 273
  - avalanches 32, 246–47
  - cold environments 36
  - deserts 35
  - dos and don'ts 93, 245
  - scrambling and climbing 90–91
  - temperate areas 28–29
  - winds 82
- muddy terrain, four-wheel driving 101
- mules 99
- multi-fuel stoves 59
- multi-tools 61

muscles, bones, and joints injuries 233, 270–71
mushrooms and fungi 206, 263
mussels 225, 298–99

N

nails, fishing hooks 208
Naismaith's rule 72
natural cordage 138–41
natural remedies 263, 268, 269
navigation 64–65
  compasses 68–71, 74–75
  GPS 65, 75
  maps and map reading 43, 64–65, 66–71
  natural (sun, moon and stars) 76–77
  route finding 72–73
  trail markers (blazes) 87
needle tea 207
needles 60, 61, 68, 74–75
nets
  bird-trapping 226
  fishing 210–11
nettles
  cordage 138–39
  stinging 268, 280–81
night line fishing 209
night walking 86
night-flying insects 219
nimbostratus 80, 81
noose sticks 218
northings 67
nutrients and calorie needs 56, 202

O

oak, poison 268
oases 34
occluded fronts 78
one-handed striker 127
one-person lean-tos 165
one-pole poncho shelter 158
orienteering compasses 68
overhand knots 143
oxygen, lack of 157, 234, 259
oysters 225

P

pace counting 65, 72
pack animals 42, 98–99
pack frames, improvised 45
packing
  backpacks 41, 42, 45
  cordage 136, 137
  fuel 58
  loading pack animals 98
packs 41, 42, 44–5, 108
paddles and paddling
  kayaking and canoeing 104, 105
  rafts 107
pain 235
  see also first aid
painters, liferafts 252
palm grubs 224, 298
pants 46, 47, 48, 94
para scrapes 175
paracord (parachute cord) 61, 136–37
paraffin 269
parangs 146
parasites 187, 222, 223, 269
pepper sprays 243
periods (menstruation) 117
personal hygiene 116–17
personal locator beacons (PLBs) 39, 236–37
petroleum jelly 61
pheasants 227, 228
phones 43, 237
physical fitness 18–19
pine cones 83
pits, cooking in 205
planning *see* preparation and planning
plants and vegetation
  cordage 138–41
  edible 203, 206–07, 280–89
  poisoning 203, 206, 207, 268, 304–05
  remedies 263, 268, 269
  signal fires 238–39
  vegetation bags 190
  water sources 189, 190, 192, 193
  weather forecasting 83
  see also specific environments (e.g. temperate environment); specific parts (e.g. roots); specific types (e.g. trees)
PLBs (personal locator beacons) 39, 236–37
plucking birds 228–29
PLWF (protection, location, water, and food) 11, 27, 258
poacher's method, pheasant meat 228
pocket chainsaws 60, 150
poison ivy, oak and sumac 268, 304–05
poisoning
  basic first aid 269
  carbon monoxide 181
  fish 300–01
  food poisoning 187, 269
  mushrooms and plants 203, 206, 207, 268, 304–05
  shellfish 225
  snake bite 266, 300–01
polar areas 36, 37
polar bears 36, 242
ponchos and tarpaulins
  beds 166–67
  brushwood rafts 106–07
  poncho floats 109
  rainwater collection 188, 196
  shelters 54, 158–59, 161, 166–68, 174–77
  wet-weather clothing 48
ponds 189, 199
porcupines 2 66, 290-91
post-holing 94
potassium permanganate 60, 127, 201
preparation and planning 6–17
  camps 112–13, 114–15
  emergency plans of action (EPAs) 24–25, 250
  journey planning 22
  mental 20–21, 234–35, 259
  physical 18–19
  temperate environments 28
  training 16–17, 23, 235
  worst-case scenarios 24, 40, 234–35, 250
  see also specific aspects (e.g. gear and equipment)
prickly pears 193, 282–83
propane stoves 58
protection, location, water, and food (PLWF) 11, 27, 258
protein 56
protozoa 187, 269
Prusik knot 210
psychogenic shock 20
psychological responses
  disaster situations 20–01, 113, 234–35, 259
  team dynamics 23
pulks 97
pumps, reverse-osmosis 197
puncture wounds 263
purifying water 60, 185, 201
pygmy huts 171
pygmy roll cordage 141

Q

quick-release knots 145
quicksand 247
quinzhees 180–81

R

rabbits 216, 220–21, 290–91
radios 61, 237
rafts 106–7
  liferafts 39, 196, 251, 252–53
rain 79, 81, 82
rain forests and jungles 30–31
  dos and don'ts 173
  jungle-trekking boots 49
  shelters 54, 166–71
  water sources 192
rainwater 188, 192, 196
ranger's flint and steel 60, 113, 118, 127
rats 220, 290–91, 300–01
rattan leaves 170
razors and razor blades 60, 61, 74–75
razorstrop fungus 263
recovery position 276
recovery techniques, vehicles 35, 102–03
reels, fishing 208
rehydration and dehydration 187, 190, 193, 196, 253, 269, 272
reptiles *see* amphibians and reptiles
rescue services 24, 236–37
rescue signaling 39, 232–33, 236–41, 250, 252
resection 71
respiratory problems
  first aid 275
  in shelters 157, 181
reverse-osmosis pumps 197
rivers
  flash floods 115
  foot crossings 88–89
  four-wheel driving 101
  kayaking and canoeing 42, 104–05
  mountain environments 32
  swimming 108–09
  temperate environment 28
  tropical environment 31
  water sources 28, 32, 189
roasting food 204, 213
rock climbing and scrambling 90–91
rocks
  hot platforms 194
  hot rocks cooking 205

  - rock holes 189
  - rockfalls 115
  - single-wall fishing traps 211
  - stone-lined fires 124
  - trail markers and cairns 87
  - transpiration and vegetation bags 190
  - water distillation 185
- rodents (rats) 220, 290–91, 300–01
- rolled cordage 141
- roofs 156–57, 170–71, 192
- roosting birds, trapping 218, 227
- roots
  - cordage 138
  - food 206
  - soapwort 117
  - water sources 193
- ropes
  - climbing techniques 91
  - crossing rivers 89
- roundworms 222, 269
- route finding 64–65, 72–73
  - *see also* navigation

S

- salmonella 187
- saltwater 38, 185, 196–97, 251, 253
- sand
  - driving on 101
  - dunes 35, 177, 189
  - quicksand 247
  - sandstorms 249
- sandals 49
- satellite communications 39, 236–7, 250, 252
- savannah 34, 35
- saws, bamboo fire 133
- saws (cutting tools) and sawing 60, 150–51
- scalds and burns 265
- scale, topographic maps 66, 67
- scalp care 116
- scalp wounds 264
- scrambling and climbing 90–91
- scrapes, hollows, and trenches shelters 156–57, 174–75, 1767–7, 178–79
- scree 32, 87
- sea anchors 39, 251
- sea ice 36, 196
- sea journeys
  - abandoning ship 250, 252–55
  - radios and beacons 39, 236, 237, 250, 252
  - seasickness 21
  - survival at sea 16–17, 39, 196–97, 214–15, 250–55
  - survival suits 39, 199, 250
  - *see also* marine environments
- sea and land breezes 82
- sea urchin spines 267
- seat carries 279
- seawater 38, 185, 196–97, 251, 253
- seaweeds 288–89
- secondary drowning 255, 273
- self-striking fishing line 209
- setting maps 69
- shadow sticks 76, 77
- sharks 38, 243
- sharpening and sharpening stones 147
- sheaths, knives 146
- shellfish 225, 298–99
- shelters 154–55
  - bivys 41, 54, 160–61
  - button-ties 161
  - caves 157, 181
  - cold environments 55, 178–81
  - deserts 174–75
  - hammocks 54, 166
  - hollows, scrapes and trenches 156–57, 174–75, 176–77, 178–79
  - huts 170–71
  - jungle 166–71
  - ponchos or tarpaulins 54, 158–59, 161, 166–68, 174–77
  - positioning on site 29, 32, 115
  - shoreline 176–77
  - snow 178–81
  - temperate forest 162–65
  - tent pegs 159
  - tents 41, 54–55
  - use-anywhere 158–59
- shigellosis 187
- ships and boats
  - kayaking and canoeing 42, 104–05
  - liferafts 39, 196, 251, 252–53
  - rafts 106–07
  - safety procedures and emergency plans of action 250
  - sea-sickness 21
  - *see also* sea journeys
- shock 274
  - anaphylactic 266, 267, 274
  - cold 254
  - psychogenic 20
- shoelaces 137
- shorelines *see* marine environments
- shorts 47
- showers 116–17
- shrimps 225
- Siberian hitch 144
- signal fires 30, 115, 238–39
- signal flares 239, 241
- signal mirrors 241
- silk, magnetizing compass needles 75
- Silva compasses 68
- simple tie-off knot 143
- sinews, cordage 139
- single-wall fishing traps 211
- sinkers and floats 209
- site selection and organisation 29, 32, 112–13, 114–15
  - *see also* specific areas (e.g. latrines)
- skidoos 97
- skinning
  - fish 213
  - mammals 221, 222
- sky colour 83
- sleds 96–97
- sleeping bags 41, 52–53
- sleeping systems *see* beds and bedding; shelters
- slings 261, 270
- slingshots 218
- slip knot 142
- slugs 224
- smoke production, signal fires 30, 238–39
- snails 224, 298–99, 300–01
- snake hole fires 125
- snakes
  - bites first aid 266
  - dangers from 34, 157, 189, 243, 300–01
  - food source 224, 294–95
- snapping wood 151
- snares 60, 216–17, 227
- snow
  - avalanches 32, 246–47
  - four-wheel driving 101
  - mountain environment 32–33
  - navigation aids 77
  - snow blindness 265
  - snow shelters 178–81
  - snow shoes 94–95
  - traveling over 94–97
  - water source 194–95
- snowman's head 195
- soaks 189
- soapwort roots 117
- socks 48
- solar stills 191, 197, 251
- space blankets 53, 61, 155, 175
- spark production and ignition devices 113, 118, 126–27, 130–33
- spiders 377, 157, 302–03
- spinal injuries 271
- sprains and strains 270
- squirrels 217, 221, 290–91
- stab wounds 263
- staffs, walking 72, 85, 89
- stand off/attack point 73
- standard compasses 68
- standing deadwood 115, 121, 131
- star-shaped fires 125
- stars, navigating by 77
- steaming food 204
- steel, flint and 60, 113, 118, 127
- stills, solar 191, 197, 251
- stinging nettles 268, 280–81
- stings and bites 116, 266–67, 268, 300–03
- stock 204, 212
- stone-lined fires 124
- storms 81, 249
- stoves 58–9
- straddling, chimney climbing 91
- strains and sprains 270
- stratocumulus 80, 81
- stratus 80, 81
- streams 32, 189
- strength and stamina 18–19
- stretchers 99, 279
- stretching exercises 19
- striker, one-handed 127
- striking matches 126
- string measuring, map reading 67
- strobe lights 240
- sugar 127
- suicide 21
- sumac, poison 268
- sun and sunlight
  - navigating by 76
  - protection from 43, 47, 175
  - sundials 76
  - water purification 201
- surgical tubing 61, 191, 197
- survival enemies 235
- survival fitness 18–19
- SURVIVAL strategies 234–35
- survival straws 201
- survival suits 39, 199, 250
- survival swimming 108–9, 254–55
- survival tins 40, 43, 60–61

surviving mentally 20–21, 234–35, 259
survivor's third leg (walking staff) 72, 85, 89
suspension method, improvised compasses 74
sustainment load 43
swamps 30, 31, 247
swimming 108–09, 254–55

T

tackle, fishing 61, 208–11
taiga 36, 37
tampons 60, 117, 118
tandem canoeing 105
tannic acid 268, 269
tanning hides 223
tarp tents 54
tarpaulins *see* ponchos and tarpaulins
taut line hitch 145
tea tree oil 268
teams *see* groups
tears (lacerations) 263
teas 207, 268, 269
teepee fires 124
teeth and gum care 19, 116
temperate environments 28–29
  edible plants 280–81
  forest shelters 162–65
  water sources 28, 188–91
  weather 78–83
temperature 235
  see also specific environments (e.g. cold environments)
temperature ratings, sleeping bags 53
tent pegs 159
tents 41, 54–55
termite fishing 219
tetanus 262
thatching huts 170–71
thirst 20, 235
thorn fishing hooks 208
throwing stars 218
thumbnail test, softwoods and hardwoods 131
tick bites 116, 267, 302–03
tides 157
tie-off knots 142, 143
time, telling by the sun 76
tinder 60, 118, 119, 120, 122–23, 124, 125, 133, 238–39
tins (cans)
  fire cans 123
  matchless fireset cans 118
  survival tins 40, 43, 60–61
tinsel trees 240
tools
  cutting 60, 146–51
  multi-tools 61
topographic maps 66–7
tornadoes 248–49
tracks 28, 30
trail markers (blazes) 87
training 23, 134–35
  benefits 16–17, 20, 235
  physical fitness 19
transpiration bags 190
transport 84–85
  animals 42, 96–97, 98–99
  casualties 99, 278–79
  on foot *see* walking and hiking skills
  motorized 35, 42, 97, 100–03
  water 104–07
traps
  birds 226–27
  dew 190, 196
  fishing 211
  mammals 216–17
trees
  deadfalls 115
  felling 148–51
  hammocks 54, 166
  lightning strikes 81
  navigation aids 77
  needle tea 207
  snowshoes 95
  standing deadwood 115, 121, 131
  tannic acid 268, 269
  tinsel trees 240
  tree shelters 163, 179
  vehicle recovery 103
  water sources 193
trekking umbrellas 175
trenches, hollows and scrapes shelters 156–57, 174–75, 176–77, 178–79
triangulation 71
tropical environments 30–31
  edible plants 284–85
  shelters 54, 166–71
  water sources 192
tubers 206
tundra 36, 37
tunnel traps, walk-in 226
turtles 196, 294–95
twisted cordage 140–41
two-person seat carries 279
two-poncho shelters 159, 167, 175
typhoons 38

U

ultralight camping 41
ultraviolet (UV) light 201
unconsciousness 276–77
Universal Edibility Test 206–07
uphill walking 86, 87
use-anywhere shelters 158–59
UV (ultraviolet) light 201

V

vampire bats 157, 300–01
variation, magnetic 69
vegetation *see* plants and vegetation
vehicles, motorized 35, 42, 97, 100–03
VHF radios 237
vines, water 192
volcanoes 247
vomiting and diarrhea 187, 203, 269

W

wadis 34, 35, 193
walk-in tunnel traps 226
walking and hiking skills 85, 86–87
  river crossings 88–89, 108–09
  scrambling and climbing 90–91
  snow 94–97
  see also navigation
walking staffs 72, 85, 89
warm-weather clothing 47
water
  amount needed 184, 186
  carrying and storing 43, 198–99, 233
  dehydration and rehydration 187, 190, 193, 196, 253, 269, 272
  freezing prevention 194, 195
  hyponatraemia 187
  importance for life 27, 184–85, 186
  plant and vegetation sources 189, 190, 192, 193
  rationing 187, 197
  sources 28, 32, 34, 35, 39, 115, 188–97, 251
  thirst 20, 235
  treating and purifying 60, 118, 185, 200–01
  water-borne diseases 185, 187
water transport 104–07
waterproof fabric, breathable 48
weapons, hunting 218, 226
weather and weather systems 38, 78–83
  extreme weather 246, 248–49
  see also specific environments (e.g. temperate environment)
weight, gear and equipment 41, 42
wells 189
  gypsy wells 191
wet-weather clothing 48
whistles 43, 240
white fuel stoves 59
wicking action, clothing 46, 47, 48
wickiups 171
wilderness survival 50–51
wildfires 34
will to survive 20, 259
winching, vehicle recovery 103
windmill, light 240
winds 38, 79, 82–83
witch hazel 268
witchetty grubs 224, 298–99
witch's broom 238, 239
withies 139
wood
  backpack frame 45
  brushwood rafts 106–07
  firewood 114, 148–49
  kindling and fuel 114, 121, 148–49
  mayasticks 123
  roofs for hollows 156–57
  sledges 96–97
  snapping 151
  snowshoes 95
  standing deadwood 115, 121, 131
  tent pegs 159
  testing softwoods and hardwoods 131
wood ash
  for soap 117
  for stomach pain 269
woodland, forest shelters 162–65
worms
  earthworms 224, 298–99
  first aid 269
  leeches 267
  roundworms 222, 269
  water-borne 187, 269
wounds and bleeding 262–65, 266

Z

zig-zag routes 73

ABOUT THE AUTHOR

After joining the Royal Navy in 1977, Colin Towell qualified as a Combat Survival Instructor with 22 Regiment SAS (the British army's elite Special Air Service), and has spent over 30 years teaching land, sea, desert, jungle, and cold-weather survival skills—as well as survival and conduct in captivity—to UK Army, Navy, Royal Marines, and Air Force personnel. He was the Royal Navy's Chief Survival Instructor and also served three years as Chief Instructor at the US Navy SERE (Survival, Evasion, Resistance, and Extraction) school. Colin saw service in the Falklands, Bosnia, Germany, USA, and Northern Ireland, and still serves as a Reserve Chief Instructor with the UK Defence SERE Training Organisation, training both instructors and students. He provided the survival training, equipment and rescue coordination for Sir Richard Branson's balloon global circumnavigation attempts, and also trials, evaluates, and instructs in the use of specialized survival equipment, both in the UK and abroad.

www.colintowell-survival.com

ACKNOWLEDGEMENTS

FROM THE AUTHOR

I have undertaken as a student every survival course I have ever subsequently taught as an instructor, mainly because I have had to, but also as a reminder of what my students experience, both physically and mentally, when they undergo survival training. In writing this book, it is safe to say that I have again been the student, and the instructors have been the team at Dorling Kindersley, and I would like to take this opportunity to thank them for their dedication, professionalism, vision, and sense of humor. Thank you to Stephanie, Lee, Nicky, Richard, and Michael for heading up the team; and to Phil and Pip, Clare and Katie, Gill and Sarah, Chris and Tracy, Jill, Bob, Brian, Sharon, Chris, Gareth, and Conor, for learning how to translate my Cumbrian into English and for creating the wonderful design for this book; thanks also to the team of illustrators who possess an unnerving ability to decipher my drawings and turn them into works of art!

My warm thanks also go to the following people for generously sharing their expertise: Flt Lt John Hudson, Royal Air Force, Defence SERE Training Centre; Lt Carlton Oliver, Royal Navy, Defence SERE Training Centre; Chief Petty Officer (SE) Keith Spiller; Petty Officer (METOC) Kirk Davidson; Petty Officer (SE) Stephen Paris-Hunter; Tony Borkowski (Royal School Military Survey); Mike Dymond M.R.I.N N.DipM (RYA); Robert (Baldy Bob) Whale; Charlie Tyrrell; Colin Knox (Pre-Mac); Murray Bryars; and Paul Baker (Bushman.UK Knifes).

Finally, I would like to thank the Defence SERE Organisation and the Survival Equipment Branch of the Royal Navy for giving me an amazing career that, if the truth is known, I would have done for free, and for allowing me the opportunity to learn from the very best, both at home and around the world.

FROM THE PUBLISHER

In addition to those mentioned above, Dorling Kindersley would like to thank the following people for their help in making this book happen. At the Royal Navy: Cdr. Alan George RN, Lt. Cdr. Adrian Mundin RN, Lt. Cdr. Paula Rowe RN, and Lt. Cdr. Phil Rosindale RN. At IMG: Olivia Smales and Simon Gresswell.

Thanks also to: Gareth Jones, Chris Stone, and Conor Kilgallon for editorial assistance; Jillian Burr and Tracy Smith for design assistance; and Sue Bosanko for compiling the index.

VENTURING®·BSA

Thank you for your purchase of *The Survival Handbook: Essential Skills for Outdoor Adventure*, an officially licensed product of the Boy Scouts of America. For more than ten years, the Boy Scouts of America Venturing program has been at the forefront of educating and preparing young men and women ages 14 through 20 to enjoy the outdoors in a responsible and safe manner.

In fact, every Venturer subscribes to a standard philosophy regarding the outdoors, the Outdoor Code.

OUTDOOR CODE

As an American, I will do my best to . . .

- **Be clean in my outdoor manners.** I will treat the outdoors as a heritage. I will take care of it for myself and others. I will keep my trash and garbage out of lakes, streams, fields, woods, and roadways.

- **Be careful with fire.** I will build my fires only where they are appropriate. When I have finished using a fire, I will make sure it is cold out. I will leave a clean fire ring, or remove all evidence of my fire.

- **Be considerate in the outdoors.** I will treat public and private property with respect. I will use low-impact methods of hiking and camping.

- **Be conservation-minded.** I will learn how to practice good conservation of soil, water, forests, minerals, grassland, wildlife, and energy. I will urge others to do the same.

This code and those who follow it represent the highest ideals regarding the outdoors and the conduct necessary to not only survive, but to enjoy its full splendor.

For more information on Venturing and the exciting leadership-building programs offered, please see

www.scouting.org/venturing

BOY SCOUTS OF AMERICA

Boy Scouts of America®, the Universal Emblem, and Venturing® are trademarks or registered trademarks of the Boy Scouts of America in the United States and other countries. Printed under license from the Boy Scouts of America.